TWENTY-SEVENTH EDITION

Machinery's Handbook

INDUSTRIAL PRESS

A REFERENCE BOOK
FOR THE MECHANICAL ENGINEER, DESIGNER,
MANUFACTURING ENGINEER, DRAFTSMAN,
TOOLMAKER, AND MACHINIST

27th Edition
Machinery's Handbook

BY ERIK OBERG, FRANKLIN D. JONES,
HOLBROOK L. HORTON, AND HENRY H. RYFFEL

CHRISTOPHER J. MCCAULEY, EDITOR
RICCARDO M. HEALD, ASSOCIATE EDITOR
MUHAMMED IQBAL HUSSAIN, ASSOCIATE EDITOR

2004
INDUSTRIAL PRESS INC.
NEW YORK

Copyright 2004, Industrial Press, Inc., New York, NY

COPYRIGHT

COPYRIGHT 1914, 1924, 1928, 1930, 1931, 1934, 1936, 1937, 1939, 1940, 1941, 1942, 1943, 1944, 1945, 1946, 1948, 1950, 1951, 1952, 1953, 1954, 1955, 1956, 1957,© 1959, © 1962, © 1964, © 1966, © 1968, © 1971, © 1974, © 1975, © 1977, © 1979, © 1984, © 1988, © 1992, © 1996, © 1997, © 1998, © 2000, © 2004 by Industrial Press Inc., New York, NY.

Library of Congress Cataloging-in-Publication Data

Oberg, Erik, 1881—1951
Machinery's Handbook.
2640 p.
Includes index.
I. Mechanical engineering—Handbook, manuals, etc.
I. Jones, Franklin Day, 1879-1967
II. Horton, Holbrook Lynedon, 1907-2001
III. Ryffel, Henry H. I920- IV. Title.
TJ151.0245 2000 621.8'0212 72-622276
ISBN 0-8311-2700-7 (Toolbox Thumb Indexed 11.7 x 17.8 cm)
ISBN 0-8311-2711-2 (Large Print Thumb Indexed 17.8 x 25.4 cm)
ISBN 0-8311-2777-5 (CD-ROM)
ISBN 0-8311-2727-9 (Toolbox Thumb Indexed / CD-ROM Combo 11.7 x 17.8 cm)
ISBN 0-8311-2737-6 (Large Print Thumb Indexed / CD-ROM Combo 17.8 x 25.4 cm)
LC card number 72-622276

INDUSTRIAL PRESS, INC.
200 Madison Avenue
New York, New York 10016-4078

MACHINERY'S HANDBOOK
27th Edition
First Printing

Printed and bound in the United States of America by National Publishing Company, Philadelphia, Pa.

All rights reserved. This book or parts thereof may not be reproduced, stored in a retrieval system, or transmitted in any form without permission of the publishers.

Copyright 2004, Industrial Press, Inc., New York, NY

PREFACE

Machinery's Handbook has served as the principal reference work in metalworking, design and manufacturing facilities, and in technical schools and colleges throughout the world, for more than 90 years of continuous publication. Throughout this period, the intention of the *Handbook* editors has always been to create a comprehensive and practical tool, combining the most basic and essential aspects of sophisticated manufacturing practice. A tool to be used in much the same way that other tools are used, to make and repair products of high quality, at the lowest cost, and in the shortest time possible.

The essential basics, material that is of proven and everlasting worth, must always be included if the *Handbook* is to continue to provide for the needs of the manufacturing community. But, it remains a difficult task to select suitable material from the almost unlimited supply of data pertaining to the manufacturing and mechanical engineering fields, and to provide for the needs of design and production departments in all sizes of manufacturing plants and workshops, as well as those of job shops, the hobbyist, and students of trade and technical schools.

The editors rely to a great extent on conversations and written communications with users of the *Handbook* for guidance on topics to be introduced, revised, lengthened, shortened, or omitted. In response to such suggestions, in recent years material on logarithms, trigonometry, and sine-bar constants have been restored after numerous requests for these topics. Also at the request of users, in 1997 the first ever large-print or "desktop" edition of the *Handbook* was published, followed in 1998 by the publication of *Machinery's Handbook CD-ROM* including hundreds of additional pages of material restored from earlier editions. The large-print and CD-ROM editions have since become permanent additions to the growing family of *Machinery's Handbook* products.

Regular users of the *Handbook* will quickly discover some of the many changes embodied in the present edition. One is the combined *Mechanics and Strength of Materials* section, arising out of the two former sections of similar name; another is the *Index of Standards*, intended to assist in locating standards information. "Old style" numerals, in continuous use in the first through twenty-fifth editions, are now used only in the index for page references, and in cross reference throughout the text. The entire text of this edition, including all the tables and equations, has been reset, and a great many of the numerous figures have been redrawn. This edition contains more information than ever before, and sixty-four additional pages brings the total length of the book to 2704 pages, the longest *Handbook* ever.

The 27th edition of the *Handbook* contains significant format changes and major revisions of existing content, as well as new material on a variety of topics. The detailed tables of contents located at the beginning of each section have been expanded and fine tuned to simplify locating your topic; numerous major sections have been extensively reworked and renovated throughout, including *Mathematics*, *Mechanics and Strength of Materials*, *Properties of Materials*, *Fasteners*, *Threads and Threading*, and *Unit Conversions*. New material includes fundamentals of basic math operations, engineering economic analysis, matrix operations, disc springs, constants for metric sine-bars, additional screw thread data and information on obscure and historical threads, aerodynamic lubrication, high speed machining, grinding feeds and speeds, machining econometrics, metalworking fluids, ISO surface texture, pipe welding, geometric dimensioning and tolerancing, gearing, and EDM.

Other subjects in the *Handbook* that are new or have been revised, expanded, or updated are: analytical geometry, formulas for circular segments, construction of four-arc ellipse, geometry of rollers on a shaft, mechanisms, additional constants for measuring weight of piles, Ohm's law, binary multiples, force on inclined planes, and measurement over pins.

The large-print edition is identical to the traditional toolbox edition, but the size is increased by a comfortable 140% for easier reading, making it ideal as a desktop reference. Other than size, there are no differences between the toolbox and large-print editions.

Copyright 2004, Industrial Press, Inc., New York, NY

PREFACE

The *Machinery's Handbook 27* CD-ROM contains the complete contents of the printed edition, presented in Adobe Acrobat PDF format. This popular and well known format enables viewing and printing of pages, identical to those of the printed book, rapid searching, and the ability to magnify the view of any page. Navigation aids in the form of thousands of clickable bookmarks, page cross references, and index entries take you instantly to any page referenced.

The CD contains additional material that is not included in the toolbox or large print editions, including an extensive index of materials referenced in the Handbook, numerous useful mathematical tables, sine-bar constants for sine-bars of various lengths, material on cement and concrete, adhesives and sealants, recipes for coloring and etching metals, forge shop equipment, silent chain, worm gearing and other material on gears, and other topics.

Also new on the CD are numerous interactive math problems. Solutions are accessed from the CD by clicking an icon, located in the page margin adjacent to a covered problem, (see figure shown here). An internet connection is required to use these problems. The list of interactive math solutions currently available can be found in the *Index of Interactive Equations*, starting on page 2689. Additional interactive solutions will be added from time to time as the need becomes clear.

Those users involved in aspects of machining and grinding will be interested in the topics Machining Econometrics and Grinding Feeds and Speeds, presented in the *Machining* section. The core of all manufacturing methods start with the cutting edge and the metal removal process. Improving the control of the machining process is a major component necessary to achieve a **Lean chain** of manufacturing events. These sections describe the means that are necessary to get metal cutting processes under control and how to properly evaluate the decision making.

A major goal of the editors is to make the *Handbook* easier to use. The 27th edition of the *Handbook* continues to incorporate the timesaving thumb tabs, much requested by users in the past. The table of contents pages beginning each major section, first introduced for the 25th edition, have proven very useful to readers. Consequently, the number of contents pages has been increased to several pages each for many of the larger sections, to more thoroughly reflect the contents of these sections. In the present edition, the *Plastics* section, formerly a separate thumb tab, has been incorporated into the *Properties of Materials* section. A major task in assembling this edition has been the expansion and reorganization of the index. For the first time, most of the many Standards referenced in the *Handbook* are now included in a separate *Index Of Standards* starting on page 2677.

The editors are greatly indebted to readers who call attention to possible errors and defects in the *Handbook*, who offer suggestions concerning the omission of some matter that is considered to be of general value, or who have technical questions concerning the solution of difficult or troublesome *Handbook* problems. Such dialog is often invaluable and helps to identify topics that require additional clarification or are the source of reader confusion. Queries involving *Handbook* material usually entail an in depth review of the topic in question, and may result in the addition of new material to the *Handbook* intended to resolve or clarify the issue. The new material on the mass moment of inertia of hollow circular rings, page 248, and on the effect of temperature on the radius of thin circular rings, page 405, are good examples.

Our goal is to increase the usefulness of the *Handbook* to the greatest extent possible. All criticisms and suggestions about revisions, omissions, or inclusion of new material, and requests for assistance with manufacturing problems encountered in the shop are always welcome.

Christopher J. McCauley, Senior Editor

Copyright 2004, Industrial Press, Inc., New York, NY

ACKNOWLEDGMENTS

The editors would like to acknowledge all those who contributed ideas, suggestions, and criticisms concerning the *Handbook*.

Most importantly, we thank the readers who have contacted us with suggestions for new topics to present in this edition of the *Handbook*. We are grateful for your continuing constructive suggestions and criticisms with regard to *Handbook* topics and presentation. Your comments for this edition, as well as past and future ones are invaluable, and well appreciated.

Special thanks are also extended to current and former members of our staff, the talented engineers, recent-graduates, who performed much of the fact checking, calculations, artwork, and standards verification involved in preparing the printed and CD-ROM editions of the *Handbook*.

Many thanks to Janet Romano for her great *Handbook* cover designs. Her printing, packaging, and production expertise are irreplacable, continuing the long tradition of *Handbook* quality and ruggedness.

Many of the American National Standards Institute (ANSI) Standards that deal with mechanical engineering, extracts from which are included in the *Handbook*, are published by the American Society of Mechanical Engineers (ASME), and we are grateful for their permission to quote extracts and to update the information contained in the standards, based on the revisions regularly carried out by the ASME.

ANSI Standards are copyrighted by the publisher. Information regarding current editions of any of these Standards can be obtained from ASME International, Three Park Avenue, New York, NY 10016, or by contacting the American National Standards Institute, West 42nd Street, New York, NY 10017, from whom current copies may be purchased. Additional information concerning Standards nomenclature and other Standards bodies that may be of interest is located on page 2079.

Several individuals in particular, contributed substantial amounts of time and information to this edition.

Mr. David Belforte, for his thorough contribution on lasers.

Manfred K. Brueckner, for his excellent presentation of formulas for circular segments, and for the material on construction of the four-arc oval.

Dr. Bertil Colding, provided extensive material on grinding speeds, feeds, depths of cut, and tool life for a wide range of materials. He also provided practical information on machining econometrics, including tool wear and tool life and machining cost relationships.

Mr. Edward Craig contributed information on welding.

Dr. Edmund Isakov, contributed material on coned disc springs as well as numerous other suggestions related to hardness scales, material properties, and other topics.

Mr. Sidney Kravitz, a frequent contributor, provided additional data on weight of piles, excellent proof reading assistance, and many useful comments and suggestions concerning many topics throughout the book.

Mr. Richard Kuzmack, for his contributions on the subject of dividing heads, and additions to the tables of dividing head indexing movements.

Mr. Robert E. Green, as editor emeritus, contributed much useful, well organized material to this edition. He also provided invaluable practical guidance to the editorial staff during the *Handbook*'s compilation.

Finally, Industrial Press is extremely fortunate that Mr. Henry H. Ryffel, author and editor of *Machinery's Handbook*, continues to be deeply involved with the *Handbook*. Henry's ideas, suggestions, and vision are deeply appreciated by everyone who worked on this book.

Copyright 2004, Industrial Press, Inc., New York, NY

Machinery's Handbook 27th Edition

TABLE OF CONTENTS

COPYRIGHT iv

PREFACE v

ACKNOWLEDGMENTS ix

MATHEMATICS 1
• NUMBERS, FRACTIONS, AND DECIMALS • ALGEBRA AND EQUATIONS • GEOMETRY • SOLUTION OF TRIANGLES • LOGARITHMS • MATRICES • ENGINEERING ECONOMICS

MECHANICS AND STRENGTH OF MATERIALS 138
• MECHANICS • VELOCITY, ACCELERATION, WORK, AND ENERGY • FLYWHEELS • STRENGTH OF MATERIALS • PROPERTIES OF BODIES • BEAMS • COLUMNS • PLATES, SHELLS, AND CYLINDERS • SHAFTS • SPRINGS • DISC SPRINGS • WIRE ROPE, CHAIN, ROPE, AND HOOKS

PROPERTIES, TREATMENT, AND TESTING OF MATERIALS 396
• THE ELEMENTS, HEAT, MASS, AND WEIGHT • PROPERTIES OF WOOD, CERAMICS, PLASTICS, METALS, WATER, AND AIR • STANDARD STEELS • TOOL STEELS • HARDENING, TEMPERING, AND ANNEALING • NONFERROUS ALLOYS • PLASTICS

DIMENSIONING, GAGING, AND MEASURING 629
• DRAFTING PRACTICES • ALLOWANCES AND TOLERANCES FOR FITS • MEASURING INSTRUMENTS AND INSPECTION METHODS • SURFACE TEXTURE

TOOLING AND TOOLMAKING 746
• CUTTING TOOLS • CEMENTED CARBIDES • FORMING TOOLS • MILLING CUTTERS • REAMERS • TWIST DRILLS AND COUNTERBORES • TAPS AND THREADING DIES • STANDARD TAPERS • ARBORS, CHUCKS, AND SPINDLES • BROACHES AND BROACHING • FILES AND BURS • TOOL WEAR AND SHARPENING • JIGS AND FIXTURES

MACHINING OPERATIONS 1005
• CUTTING SPEEDS AND FEEDS • SPEED AND FEED TABLES • ESTIMATING SPEEDS AND MACHINING POWER • MACHINING ECONOMETRICS • SCREW MACHINE FEEDS AND SPEEDS • CUTTING FLUIDS • MACHINING NONFERROUS METALS AND NON-METALLIC MATERIALS • GRINDING FEEDS AND SPEEDS • GRINDING AND OTHER ABRASIVE PROCESSES • KNURLS AND KNURLING • MACHINE TOOL ACCURACY • NUMERICAL CONTROL • NUMERICAL CONTROL PROGRAMMING • CAD/CAM

MANUFACTURING PROCESSES 1326
• PUNCHES, DIES, AND PRESS WORK • ELECTRICAL DISCHARGE MACHINING • IRON AND STEEL CASTINGS • SOLDERING AND BRAZING • WELDING • LASERS • FINISHING OPERATIONS

Each section has a detailed Table of Contents or Index located on the page indicated

TABLE OF CONTENTS

FASTENERS 1473
- NAILS, SPIKES, AND WOOD SCREWS • RIVETS AND RIVETED JOINTS • TORQUE AND TENSION IN FASTENERS • INCH THREADED FASTENERS • METRIC THREADED FASTENERS
- BRITISH FASTENERS • MACHINE SCREWS AND NUTS • CAP AND SET SCREWS • SELF-THREADING SCREWS • T-SLOTS, BOLTS, AND NUTS • PINS AND STUDS • RETAINING RINGS • WING NUTS, WING SCREWS, AND THUMB SCREWS

THREADS AND THREADING 1721
- SCREW THREAD SYSTEMS • UNIFIED SCREW THREADS
- METRIC SCREW THREADS • ACME SCREW THREADS • BUTTRESS THREADS • WHITWORTH THREADS • PIPE AND HOSE THREADS
- OTHER THREADS • MEASURING SCREW THREADS • TAPPING AND THREAD CUTTING • THREAD ROLLING • THREAD GRINDING • THREAD MILLING • SIMPLE, COMPOUND, DIFFERENTIAL, AND BLOCK INDEXING

GEARS, SPLINES, AND CAMS 2026
- GEARS AND GEARING • HYPOID AND BEVEL GEARING • WORM GEARING • HELICAL GEARING • OTHER GEAR TYPES • CHECKING GEAR SIZES • GEAR MATERIALS • SPLINES AND SERRATIONS
- CAMS AND CAM DESIGN

MACHINE ELEMENTS 2214
- PLAIN BEARINGS • BALL, ROLLER, AND NEEDLE BEARINGS
- STANDARD METAL BALLS • LUBRICANTS AND LUBRICATION
- COUPLINGS AND CLUTCHES • FRICTION BRAKES • KEYS AND KEYSEATS • FLEXIBLE BELTS AND SHEAVES • TRANSMISSION CHAINS • STANDARDS FOR ELECTRIC MOTORS • ADHESIVES AND SEALANTS • MOTION CONTROL • O-RINGS • ROLLED STEEL SECTIONS, WIRE, AND SHEET-METAL GAGES • PIPE AND PIPE FITTINGS

MEASURING UNITS 2539
- SYMBOLS AND ABBREVIATIONS • MEASURING UNITS • U.S. SYSTEM AND METRIC SYSTEM CONVERSIONS

INDEX 2588

INDEX OF STANDARDS 2677

INDEX OF INTERACTIVE EQUATIONS 2689

INDEX OF MATERIALS 2694

ADDITIONAL INFORMATION FROM THE CD 2741
- MATHEMATICS • CEMENT, CONCRETE, LUTES, ADHESIVES, AND SEALANTS • SURFACE TREATMENTS FOR METALS
- MANUFACTURING • SYMBOLS FOR DRAFTING • FORGE SHOP EQUIPMENT • SILENT OR INVERTED TOOTH CHAIN • GEARS AND GEARING • MISCELLANEOUS TOPICS

Each section has a detailed Table of Contents or Index located on the page indicated

TABLE OF CONTENTS

MATHEMATICS

NUMBERS, FRACTIONS, AND DECIMALS

3 Fractional Inch, Decimal, Millimeter Conversion
4 Numbers
4 Positive and Negative Numbers
5 Sequence of Arithmetic Operations
5 Ratio and Proportion
7 Percentage
8 Fractions
8 Common Fractions
8 Reciprocals
9 Addition, Subtraction, Multiplication, Division
10 Decimal Fractions
11 Continued Fractions
12 Conjugate Fractions
13 Using Continued Fraction Convergents as Conjugates
14 Powers and Roots
14 Powers of Ten Notation
15 Converting to Power of Ten
15 Multiplication
16 Division
16 Constants Frequently Used in Mathematical Expressions
17 Imaginary and Complex Numbers
18 Factorial
18 Permutations
18 Combinations
19 Prime Numbers and Factors

ALGEBRA AND EQUATIONS

29 Rearrangement of Formulas
30 Principle Algebraic Expressions
31 Solving First Degree Equations
31 Solving Quadratic Equations
32 Factoring a Quadratic Expression
33 Cubic Equations
33 Solving Numerical Equations
34 Series
34 Derivatives and Integrals

GEOMETRY

36 Arithmetical & Geometrical Progression
39 Analytical Geometry
39 Straight Line
42 Coordinate Systems
45 Circle
45 Parabola
46 Ellipse
47 Four-arc Approximate Ellipse
47 Hyperbola
59 Areas and Volumes
59 The Prismoidal Formula
59 Pappus or Guldinus Rules
60 Area of Revolution Surface
60 Area of Irregular Plane Surface
61 Areas Enclosed by Cycloidal Curves
61 Contents of Cylindrical Tanks
63 Areas and Dimensions of Figures
69 Formulas for Regular Polygons
70 Circular Segments
73 Circles and Squares of Equal Area
74 Diagonals of Squares and Hexagons
75 Volumes of Solids
81 Circles in Circles and Rectangles
86 Circles within Rectangles
87 Rollers on a Shaft

SOLUTION OF TRIANGLES

88 Functions of Angles
89 Laws of Sines and Cosines
89 Trigonometric Identities
91 Solution of Right-angled Triangles
94 Solution of Obtuse-angled Triangles
96 Degree-radian Conversion
98 Functions of Angles, Graphic Illustration
99 Trig Function Tables
103 Versed Sine and Versed Cosine
103 Sevolute and Involute Functions
104 Involute Functions Tables
108 Compound Angles
110 Interpolation

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MATHEMATICS

LOGARITHMS

111 Common Logarithms
112 Inverse Logarithm
113 Natural Logarithms
113 Powers of Number by Logarithms
114 Roots of Number by Logarithms
115 Tables of Logarithms

MATRICES

119 Matrix Operations
119 Matrix Addition and Subtraction
119 Matrix Multiplication
120 Transpose of a Matrix
120 Determinant of a Square Matrix
121 Minors and Cofactors
121 Adjoint of a Matrix
122 Singularity and Rank of a Matrix
122 Inverse of a Matrix
122 Simultaneous Equations

ENGINEERING ECONOMICS

125 Interest
125 Simple and Compound Interest
126 Nominal vs. Effective Interest Rates
127 Cash Flow and Equivalence
128 Cash Flow Diagrams
130 Depreciation
130 Straight Line Depreciation
130 Sum of the Years Digits
130 Double Declining Balance Method
130 Statutory Depreciation System
131 Evaluating Alternatives
131 Net Present Value
132 Capitalized Cost
133 Equivalent Uniform Annual Cost
134 Rate of Return
134 Benefit-cost Ratio
134 Payback Period
134 Break-even Analysis
137 Overhead Expenses

Copyright 2004, Industrial Press, Inc., New York, NY

NUMBERS, FRACTIONS, AND DECIMALS

Table 1. Fractional and Decimal Inch to Millimeter, Exact[a] Values

Fractional Inch	Decimal Inch	Millimeters	Fractional Inch	Decimal Inch	Millimeters
1/64	0.015625	0.396875		0.511811024	13
1/32	0.03125	0.79375	33/64	0.515625	13.096875
	0.039370079	1	17/32	0.53125	13.49375
3/64	0.046875	1.190625	35/64	0.546875	13.890625
1/16	0.0625	1.5875		0.551181102	14
5/64	0.078125	1.984375	9/16	0.5625	14.2875
	0.078740157	2	37/64	0.578125	14.684375
1/12	$0.08\overline{33}$[b]	$2.11\overline{66}$	7/12	$0.58\overline{33}$	$14.81\overline{66}$
3/32	0.09375	2.38125		0.590551181	15
7/64	0.109375	2.778125	19/32	0.59375	15.08125
	0.118110236	3	39/64	0.609375	15.478125
1/8	0.125	3.175	5/8	0.625	15.875
9/64	0.140625	3.571875		0.62992126	16
5/32	0.15625	3.96875	41/64	0.640625	16.271875
	0.157480315	4	21/32	0.65625	16.66875
1/6	$0.1\overline{66}$	$4.2\overline{33}$	2/3	$0.\overline{66}$	$16.9\overline{33}$
11/64	0.171875	4.365625		0.669291339	17
3/16	0.1875	4.7625	43/64	0.671875	17.065625
	0.196850394	5	11/16	0.6875	17.4625
13/64	0.203125	5.159375	45/64	0.703125	17.859375
7/32	0.21875	5.55625		0.708661417	18
15/64	0.234375	5.953125	23/32	0.71875	18.25625
	0.236220472	6	47/64	0.734375	18.653125
1/4	0.25	6.35		0.748031496	19
17/64	0.265625	6.746875	3/4	0.75	19.05
	0.275590551	7	49/64	0.765625	19.446875
9/32	0.28125	7.14375	25/32	0.78125	19.84375
19/64	0.296875	7.540625		0.787401575	20
5/16	0.3125	7.9375	51/64	0.796875	20.240625
	0.31496063	8	13/16	0.8125	20.6375
21/64	0.328125	8.334375		0.826771654	21
1/3	$0.\overline{33}$	$8.4\overline{66}$	53/64	0.828125	21.034375
11/32	0.34375	8.73125	27/32	0.84375	21.43125
	0.354330709	9	55/64	0.859375	21.828125
23/64	0.359375	9.128125		0.866141732	22
3/8	0.375	9.525	7/8	0.875	22.225
25/64	0.390625	9.921875	57/64	0.890625	22.621875
	0.393700787	10		0.905511811	23
13/32	0.40625	10.31875	29/32	0.90625	23.01875
5/12	$0.41\overline{66}$	$10.58\overline{33}$	11/12	$0.91\overline{66}$	$23.28\overline{33}$
27/64	0.421875	10.715625	59/64	0.921875	23.415625
	0.433070866	11	15/16	0.9375	23.8125
7/16	0.4375	11.1125		0.94488189	24
29/64	0.453125	11.509375	61/64	0.953125	24.209375
15/32	0.46875	11.90625	31/32	0.96875	24.60625
	0.472440945	12		0.984251969	25
31/64	0.484375	12.303125	63/64	0.984375	25.003125
1/2	0.5	12.7			

[a] Table data are based on 1 inch = 25.4 mm, exactly. Inch to millimeter conversion values are exact. Whole number millimeter to inch conversions are rounded to 9 decimal places.

[b] Numbers with an overbar, repeat indefinately after the last figure, for example $0.08\overline{33} = 0.08333...$

Copyright 2004, Industrial Press, Inc., New York, NY

Numbers

Numbers are the basic instrumentation of computation. Calculations are made by operations of numbers. The whole numbers greater than zero are called natural numbers. The first ten numbers 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 are called numerals. Numbers follow certain fomulas. The following properties hold true:

Associative law: $x + (y + z) = (x + y) + z, x(yz) = (xy)z$

Distributive law: $x(y + z) = xy + xz$

Commutative law: $x + y = y + x$

Identity law: $0 + x = x, 1x = x$

Inverse law: $x - x = 0, x/x = 1$

Positive and Negative Numbers.— The degrees on a thermometer scale extending upward from the zero point may be called *positive* and may be preceded by a plus sign; thus +5 degrees means 5 degrees above zero. The degrees below zero may be called *negative* and may be preceded by a minus sign; thus, – 5 degrees means 5 degrees below zero. In the same way, the ordinary numbers 1, 2, 3, etc., which are larger than 0, are called positive numbers; but numbers can be conceived of as extending in the other direction from 0, numbers that, in fact, are less than 0, and these are called negative. As these numbers must be expressed by the same figures as the positive numbers they are designated by a minus sign placed before them, thus: (–3). A negative number should always be enclosed within parentheses whenever it is written in line with other numbers; for example: $17 + (-13) - 3 \times (-0.76)$.

Negative numbers are most commonly met with in the use of logarithms and natural trigonometric functions. The following rules govern calculations with negative numbers.

A negative number can be added to a positive number by subtracting its numerical value from the positive number.

Example: $4 + (-3) = 4 - 3 = 1$

A negative number can be subtracted from a positive number by adding its numerical value to the positive number.

Example: $4 - (-3) = 4 + 3 = 7$

A negative number can be added to a negative number by adding the numerical values and making the sum negative.

Example: $(-4) + (-3) = -7$

A negative number can be subtracted from a larger negative number by subtracting the numerical values and making the difference negative.

Example: $(-4) - (-3) = -1$

A negative number can be subtracted from a smaller negative number by subtracting the numerical values and making the difference positive.

Example: $(-3) - (-4) = 1$

If in a subtraction the number to be subtracted is larger than the number from which it is to be subtracted, the calculation can be carried out by subtracting the smaller number from the larger, and indicating that the remainder is negative.

Example: $3 - 5 = -(5 - 3) = -2$

When a positive number is to be multiplied or divided by a negative numbers, multiply or divide the numerical values as usual; the product or quotient, respectively, is negative. The same rule is true if a negative number is multiplied or divided by a positive number.

Examples: $4 \times (-3) = -12 \quad (-4) \times 3 = -12$

$15 \div (-3) = -5 \quad (-15) \div 3 = -5$

When two negative numbers are to be multiplied by each other, the product is positive. When a negative number is divided by a negative number, the quotient is positive.

Copyright 2004, Industrial Press, Inc., New York, NY

Examples: $(-4) \times (-3) = 12$; $(-4) \div (-3) = 1.333$

The two last rules are often expressed for memorizing as follows: "Equal signs make plus, unequal signs make minus."

Sequence of Performing Arithmetic Operations.— When several numbers or quantities in a formula are connected by signs indicating that additions, subtractions, multiplications, and divisions are to be made, the multiplications and divisions should be carried out first, in the sequence in which they appear, before the additions or subtractions are performed.

Example:

$$10 + 26 \times 7 - 2 = 10 + 182 - 2 = 190$$
$$18 \div 6 + 15 \times 3 = 3 + 45 = 48$$
$$12 + 14 \div 2 - 4 = 12 + 7 - 4 = 15$$

When it is required that certain additions and subtractions should precede multiplications and divisions, use is made of parentheses ( ) and brackets [ ]. These signs indicate that the calculation inside the parentheses or brackets should be carried out completely by itself before the remaining calculations are commenced. If one bracket is placed inside another, the one inside is first calculated.

Example:

$$(6 - 2) \times 5 + 8 = 4 \times 5 + 8 = 20 + 8 = 28$$
$$6 \times (4 + 7) \div 22 = 6 \times 11 \div 22 = 66 \div 22 = 3$$
$$2 + [10 \times 6(8 + 2) - 4] \times 2 = 2 + [10 \times 6 \times 10 - 4] \times 2$$
$$= 2 + [600 - 4] \times 2 = 2 + 596 \times 2 = 2 + 1192 = 1194$$

The parentheses are considered as a sign of multiplication; for example:

$$6(8 + 2) = 6 \times (8 + 2).$$

The line or bar between the numerator and denominator in a fractional expression is to be considered as a division sign. For example,

$$\frac{12 + 16 + 22}{10} = (12 + 16 + 22) \div 10 = 50 \div 10 = 5$$

In formulas, the multiplication sign (×) is often left out between symbols or letters, the values of which are to be multiplied. Thus,

$$AB = A \times B \qquad \text{and} \qquad \frac{ABC}{D} = (A \times B \times C) \div D$$

Ratio and Proportion.— The *ratio* between two quantities is the quotient obtained by dividing the first quantity by the second. For example, the ratio between 3 and 12 is ¼, and the ratio between 12 and 3 is 4. Ratio is generally indicated by the sign (:); thus, 12 : 3 indicates the ratio of 12 to 3.

A *reciprocal*, or *inverse* ratio, is the opposite of the original ratio. Thus, the inverse ratio of 5 : 7 is 7 : 5.

In a *compound* ratio, each term is the product of the corresponding terms in two or more simple ratios. Thus, when

$$8:2 = 4 \qquad 9:3 = 3 \qquad 10:5 = 2$$

then the compound ratio is

$$8 \times 9 \times 10:2 \times 3 \times 5 = 4 \times 3 \times 2$$
$$720:30 = 24$$

Proportion is the equality of ratios. Thus,

$$6:3 = 10:5 \qquad \text{or} \qquad 6:3::10:5$$

Copyright 2004, Industrial Press, Inc., New York, NY

The first and last terms in a proportion are called the *extremes;* the second and third, the *means*. The product of the extremes is equal to the product of the means. Thus,

$$25:2 = 100:8 \qquad \text{and} \qquad 25 \times 8 = 2 \times 100$$

If three terms in a proportion are known, the remaining term may be found by the following rules:

The first term is equal to the product of the second and third terms, divided by the fourth.

The second term is equal to the product of the first and fourth terms, divided by the third.

The third term is equal to the product of the first and fourth terms, divided by the second.

The fourth term is equal to the product of the second and third terms, divided by the first.

Example: Let x be the term to be found, then,

$$x : 12 = 3.5 : 21 \qquad x = \frac{12 \times 3.5}{21} = \frac{42}{21} = 2$$

$$\tfrac{1}{4} : x = 14 : 42 \qquad x = \frac{\frac{1}{4} \times 42}{14} = \frac{1}{4} \times 3 = \frac{3}{4}$$

$$5 : 9 = x : 63 \qquad x = \frac{5 \times 63}{9} = \frac{315}{9} = 35$$

$$\tfrac{1}{4} : \tfrac{7}{8} = 4 : x \qquad x = \frac{\frac{7}{8} \times 4}{\frac{1}{4}} = \frac{3\frac{1}{2}}{\frac{1}{4}} = 14$$

If the second and third terms are the same, that number is the *mean proportional* between the other two. Thus, 8 : 4 = 4 : 2, and 4 is the mean proportional between 8 and 2. The mean proportional between two numbers may be found by multiplying the numbers together and extracting the square root of the product. Thus, the mean proportional between 3 and 12 is found as follows:

$$3 \times 12 = 36 \qquad \text{and} \qquad \sqrt{36} = 6$$

which is the mean proportional.

Practical Examples Involving Simple Proportion: If it takes 18 days to assemble 4 lathes, how long would it take to assemble 14 lathes?

Let the number of days to be found be x. Then write out the proportion as follows:

$$4:18 = 14:x$$

(lathes : days = lathes : days)

Now find the fourth term by the rule given:

$$x = \frac{18 \times 14}{4} = 63 \text{ days}$$

Thirty-four linear feet of bar stock are required for the blanks for 100 clamping bolts. How many feet of stock would be required for 912 bolts?

Let x = total length of stock required for 912 bolts.

$$34:100 = x:912$$

(feet : bolts = feet : bolts)

Then, the third term $x = (34 \times 912)/100 = 310$ feet, approximately.

Inverse Proportion: In an inverse proportion, as one of the items involved *increases*, the corresponding item in the proportion *decreases*, or vice versa. For example, a factory employing 270 men completes a given number of typewriters weekly, the number of working hours being 44 per week. How many men would be required for the same production if the working hours were reduced to 40 per week?

Copyright 2004, Industrial Press, Inc., New York, NY

The time per week is in an inverse proportion to the number of men employed; the shorter the time, the more men. The inverse proportion is written:

$$270 : x = 40 : 44$$

(men, 44-hour basis: men, 40-hour basis = time, 40-hour basis: time, 44-hour basis)
Thus

$$\frac{270}{x} = \frac{40}{44} \qquad \text{and} \qquad x = \frac{270 \times 44}{40} = 297 \text{ men}$$

Problems Involving Both Simple and Inverse Proportions: If two groups of data are related both by direct (simple) and inverse proportions among the various quantities, then a simple mathematical relation that may be used in solving problems is as follows:

$$\frac{\text{Product of all directly proportional items in first group}}{\text{Product of all inversely proportional items in first group}} = \frac{\text{Product of all directly proportional items in second group}}{\text{Product of all inversely proportional items in second group}}$$

Example: If a man capable of turning 65 studs in a day of 10 hours is paid $6.50 per hour, how much per hour ought a man be paid who turns 72 studs in a 9-hour day, if compensated in the same proportion?

The first group of data in this problem consists of the number of hours worked by the first man, his hourly wage, and the number of studs which he produces per day; the second group contains similar data for the second man except for his unknown hourly wage, which may be indicated by x.

The labor cost per stud, as may be seen, is directly proportional to the number of hours worked and the hourly wage. These quantities, therefore, are used in the numerators of the fractions in the formula. The labor cost per stud is inversely proportional to the number of studs produced per day. (The greater the number of studs produced in a given time the less the cost per stud.) The numbers of studs per day, therefore, are placed in the denominators of the fractions in the formula. Thus,

$$\frac{10 \times 6.50}{65} = \frac{9 \times x}{72}$$

$$x = \frac{10 \times 6.50 \times 72}{65 \times 9} = \$8.00 \text{ per hour}$$

Percentage.— If out of 100 pieces made, 12 do not pass inspection, it is said that 12 per cent (12 of the hundred) are rejected. If a quantity of steel is bought for $100 and sold for $140, the profit is 28.6 per cent of the selling price.

The per cent of gain or loss is found by dividing the amount of gain or loss by the *original* number of which the percentage is wanted, and multiplying the quotient by 100.

Example: Out of a total output of 280 castings a day, 30 castings are, on an average, rejected. What is the percentage of bad castings?

$$\frac{30}{280} \times 100 = 10.7 \text{ per cent}$$

If by a new process 100 pieces can be made in the same time as 60 could formerly be made, what is the gain in output of the new process over the old, expressed in per cent?

Original number, 60; gain 100 – 60 = 40. Hence,

$$\frac{40}{60} \times 100 = 66.7 \text{ per cent}$$

Care should be taken always to use the original number, or the number of which the percentage is wanted, as the divisor in all percentage calculations. In the example just given, it

Copyright 2004, Industrial Press, Inc., New York, NY

is the percentage of gain over the old output 60 that is wanted and not the percentage with relation to the new output too. Mistakes are often made by overlooking this important point.

Fractions

Common Fractions.— Common fractions consist of two basic parts, a denominator, or bottom number, and a numerator, or top number. The denominator shows how many parts the whole unit has been divided into. The numerator indicates the number of parts of the whole that are being considered. A fraction having a value of $5/32$, means the whole unit has been divided into 32 equal parts and 5 of these parts are considered in the value of the fraction.

The following are the basic facts, rules, and definitions concerning common fractions.

A common fraction having the same numerator and denominator is equal to 1. For example, $2/2$, $4/4$, $8/8$, $16/16$, $32/32$, and $64/64$ all equal 1.

Proper Fraction: A proper fraction is a common fraction having a numerator smaller than its denominator, such as $1/4$, $1/2$, and $47/64$.

Improper Fraction: An improper fraction is a common fraction having a numerator larger than its denominator. For example, $3/2$, $5/4$, and $10/8$. To convert a whole number to an improper fractions place the whole number over 1, as in $4 = 4/1$ and $3 = 3/1$

Reducible Fraction: A reducible fraction is a common fraction that can be reduced to lower terms. For example, $2/4$ can be reduced to $1/2$, and $28/32$ can be reduced to $7/8$. To reduce a common fraction to lower terms, divide both the numerator and the denominator by the same number. For example, $24/32 \div 8/8 = 3/8$ and $6/8 \div 2/2 = 3/4$.

Least Common Denominator: A least common denominator is the smallest denominator value that is evenly divisible by the other denominator values in the problem. For example, given the following numbers, $1/2$, $1/4$, and $3/8$, the least common denominator is 8.

Mixed Number: A mixed number is a combination of a whole number and a common fraction, such as $2\frac{1}{2}$, $1\frac{7}{8}$, $3\frac{15}{16}$ and $1\frac{9}{32}$.

To convert mixed numbers to improper fractions, multiply the whole number by the denominator and add the numerator to obtain the new numerator. The denominator remains the same. For example,

$$2\frac{1}{2} = \frac{2 \times 2 + 1}{2} = \frac{5}{2}$$

$$3\frac{7}{16} = \frac{3 \times 16 + 7}{16} = \frac{55}{16}$$

To convert an improper fraction to a mixed number, divide the numerator by the denominator and reduce the remaining fraction to its lowest terms. For example,

$17/8 = 17 \div 8 = 2\frac{1}{8}$ and $26/16 = 26 \div 16 = 1\frac{10}{16} = 1\frac{5}{8}$

A fraction may be converted to higher terms by multiplying the numerator and denominator by the same number. For example, $1/4$ in 16ths $= 1/4 \times 4/4 = 4/16$ and $3/8$ in 32nds $= 3/8 \times 4/4 = 12/32$.

To change a whole number to a common fraction with a specific denominator value, convert the whole number to a fraction and multiply the numerator and denominator by the desired denominator value.

Example: 4 in 16ths $= 4/1 \times 16/16 = 64/16$ and 3 in 32nds $= 3/1 \times 32/32 = 96/32$

Reciprocals.— The *reciprocal R* of a number *N* is obtained by dividing 1 by the number; $R = 1/N$. Reciprocals are useful in some calculations because they avoid the use of negative characteristics as in calculations with logarithms and in trigonometry. In trigonometry, the

Copyright 2004, Industrial Press, Inc., New York, NY

values *cosecant*, *secant*, and *cotangent* are often used for convenience and are the reciprocals of the *sine*, *cosine*, and *tangent*, respectively (see page 88). The reciprocal of a fraction, for instance ¾, is the fraction inverted, since $1 \div \frac{3}{4} = 1 \times \frac{4}{3} = \frac{4}{3}$.

Adding Fractions and Mixed Numbers

To Add Common Fractions: 1) Find and convert to the least common denominator; 2) Add the numerators; 3) Convert the answer to a mixed number, if necessary; and 4) Reduce the fraction to its lowest terms.

To Add Mixed Numbers: 1) Find and convert to the least common denominator; 2) Add the numerators; 3) Add the whole numbers; and 4) Reduce the answer to its lowest terms.

Example, Addition of Common Fractions:

$$\frac{1}{4} + \frac{3}{16} + \frac{7}{8} =$$

$$\frac{1}{4}\left(\frac{4}{4}\right) + \frac{3}{16} + \frac{7}{8}\left(\frac{2}{2}\right) =$$

$$\frac{4}{16} + \frac{3}{16} + \frac{14}{16} = \frac{21}{16}$$

Example, Addition of Mixed Numbers:

$$2\frac{1}{2} + 4\frac{1}{4} + 1\frac{15}{32} =$$

$$2\frac{1}{2}\left(\frac{16}{16}\right) + 4\frac{1}{4}\left(\frac{8}{8}\right) + 1\frac{15}{32} =$$

$$2\frac{16}{32} + 4\frac{8}{32} + 1\frac{15}{32} = 7\frac{39}{32} = 8\frac{7}{32}$$

Subtracting Fractions and Mixed Numbers

To Subtract Common Fractions: 1) Convert to the least common denominator; 2) Subtract the numerators; and 3) Reduce the answer to its lowest terms.

To Subtract Mixed Numbers: 1) Convert to the least common denominator; 2) Subtract the numerators; 3) Subtract the whole numbers; and 4) Reduce the answer to its lowest terms.

Example, Subtraction of Common Fractions:

$$\frac{15}{16} - \frac{7}{32} =$$

$$\frac{15}{16}\left(\frac{2}{2}\right) - \frac{7}{32} =$$

$$\frac{30}{32} - \frac{7}{32} = \frac{23}{32}$$

Example, Subtraction of Mixed Numbers:

$$2\frac{3}{8} - 1\frac{1}{16} =$$

$$2\frac{3}{8}\left(\frac{2}{2}\right) - 1\frac{1}{16} =$$

$$2\frac{6}{16} - 1\frac{1}{16} = 1\frac{5}{16}$$

Multiplying Fractions and Mixed Numbers

To Multiply Common Fractions: 1) Multiply the numerators; 2) Multiply the denominators; and 3) Convert improper fractions to mixed numbers, if necessary.

To Multiply Mixed Numbers: 1) Convert the mixed numbers to improper fractions; 2) Multiply the numerators; 3) Multiply the denominators; and 4) Convert improper fractions to mixed numbers, if necessary.

Example, Multiplication of Common Fractions:

$$\frac{3}{4} \times \frac{7}{16} = \frac{3 \times 7}{4 \times 16} = \frac{21}{64}$$

Example, Multiplication of Mixed Numbers:

$$2\frac{1}{4} \times 3\frac{1}{2} = \frac{9 \times 7}{4 \times 2} = \frac{63}{8} = 7\frac{7}{8}$$

Dividing Fractions and Mixed Numbers

To Divide Common Fractions: 1) Write the fractions to be divided; 2) Invert (switch) the numerator and denominator in the dividing fraction; 3) Multiply the numerators and denominators; and 4) Convert improper fractions to mixed numbers, if necessary.

Copyright 2004, Industrial Press, Inc., New York, NY

To Divide Mixed Numbers: 1) Convert the mixed numbers to improper fractions; 2) Write the improper fraction to be divided; 3) Invert (switch) the numerator and denominator in the dividing fraction; 4) Multiplying numerators and denominators; and 5) Convert improper fractions to mixed numbers, if necessary.

Example, Division of Common Fractions:

$$\frac{3}{4} \div \frac{1}{2} = \frac{3 \times 2}{4 \times 1} = \frac{6}{4} = 1\frac{1}{2}$$

Example, Division of Mixed Numbers:

$$2\frac{1}{2} \div 1\frac{7}{8} = \frac{5 \times 8}{2 \times 15} = \frac{40}{30} = 1\frac{1}{3}$$

Decimal Fractions.— Decimal fractions are fractional parts of a whole unit, which have implied denominators that are multiples of 10. A decimal fraction of 0.1 has a value of 1/10th, 0.01 has a value of 1/100th, and 0.001 has a value of 1/1000th. As the number of decimal place values increases, the value of the decimal number changes by a multiple of 10. A single number placed to the right of a decimal point has a value expressed in tenths; two numbers to the right of a decimal point have a value expressed in hundredths; three numbers to the right have a value expressed in thousandths; and four numbers are expressed in ten-thousandths. Since the denominator is implied, the number of decimal places in the numerator indicates the value of the decimal fraction. So a decimal fraction expressed as a 0.125 means the whole unit has been divided into 1000 parts and 125 of these parts are considered in the value of the decimal fraction.

In industry, most decimal fractions are expressed in terms of thousandths rather than tenths or hundredths. So a decimal fraction of 0.2 is expressed as 200 thousandths, not 2 tenths, and a value of 0.75 is expressed as 750 thousandths, rather than 75 hundredths. In the case of four place decimals, the values are expressed in terms of ten-thousandths. So a value of 0.1875 is expressed as 1 thousand 8 hundred and 75 ten-thousandths. When whole numbers and decimal fractions are used together, whole units are shown to the left of a decimal point, while fractional parts of a whole unit are shown to the right.

Example:

10.125	
Whole Units	Fraction Units

Adding Decimal Fractions: 1) Write the problem with all decimal points aligned vertically; 2) Add the numbers as whole number values; and 3) Insert the decimal point in the same vertical column in the answer.

Subtracting Decimal Fractions: 1) Write the problem with all decimal points aligned vertically; 2) Subtract the numbers as whole number values; and 3) Insert the decimal point in the same vertical column in the answer.

Multiplying Decimal Fractions: 1) Write the problem with the decimal points aligned; 2) Multiply the values as whole numbers; 3) Count the number of decimal places in both multiplied values; and 4) Counting from right to left in the answer, insert the decimal point so the number of decimal places in the answer equals the total number of decimal places in the numbers multiplied.

Example, Adding Decimal Fractions:

0.125		1.750
1.0625		0.875
2.50	or	0.125
0.1875		2.0005
3.8750		4.7505

Example, Subtracting Decimal Fractions:

1.750		2.625
–0.250	or	–1.125
1.500		1.500

Copyright 2004, Industrial Press, Inc., New York, NY

Example, Multiplying Decimal Fractions:

0.75		1.625	
0.25		0.033	
375	(four decimal places)	4875	(six decimal places)
150		4875	
0.1875		0.053625	

Continued Fractions.— In dealing with a cumbersome fraction, or one which does not have satisfactory factors, it may be possible to substitute some other, approximately equal, fraction which is simpler or which can be factored satisfactorily. Continued fractions provide a means of computing a series of fractions each of which is a closer approximation to the original fraction than the one preceding it in the series.

A continued fraction is a proper fraction (one whose numerator is smaller than its denominator) expressed in the form shown at the left below; or, it may be convenient to write the left expression as shown at the right below.

$$\frac{N}{D} = \cfrac{1}{D_1 + \cfrac{1}{D_2 + \cfrac{1}{D_3 + \ldots}}} \qquad \frac{N}{D} = \frac{1}{D_1} + \frac{1}{D_2} + \frac{1}{D_3} + \frac{1}{D_4} + \cdots$$

The continued fraction is produced from a proper fraction N/D by dividing the numerator N both into itself and into the denominator D. Dividing the numerator into itself gives a result of 1; dividing the numerator into the denominator gives a whole number D_1 plus a remainder fraction R_1. The process is then repeated on the remainder fraction R_1 to obtain D_2 and R_2; then D_3, R_3, etc., until a remainder of zero results. As an example, using $N/D = 2153/9277$,

$$\frac{2153}{9277} = \frac{2153 \div 2153}{9277 \div 2153} = \cfrac{1}{4 + \cfrac{665}{2153}} = \frac{1}{D_1 + R_1}$$

$$R_1 = \frac{665}{2153} = \cfrac{1}{3 + \cfrac{158}{665}} = \frac{1}{D_2 + R_2} \text{ etc.}$$

from which it may be seen that $D_1 = 4, R_1 = 665/2153$; $D_2 = 3, R_2 = 158/665$; and, continuing as was explained previously, it would be found that: $D_3 = 4, R_3 = 33/158$; …; $D_9 = 2, R_9 = 0$. The complete set of continued fraction elements representing $2153/9277$ may then be written as

$$\frac{2153}{9277} = \frac{1}{4} + \frac{1}{3} + \frac{1}{4} + \frac{1}{4} + \frac{1}{1} + \frac{1}{3} + \frac{1}{1} + \frac{1}{2} + \frac{1}{2}$$

$$D_1 \ldots\ldots\ldots D_5 \ldots\ldots\ldots\ldots D_9$$

By following a simple procedure, together with a table organized similar to the one below for the fraction $2153/9277$, the denominators $D_1, D_2, \ldots$ of the elements of a continued fraction may be used to calculate a series of fractions, each of which is a successively closer approximation, called a *convergent*, to the original fraction N/D.

1) The first row of the table contains column numbers numbered from 1 through 2 plus the number of elements, $2 + 9 = 11$ in this example.

Copyright 2004, Industrial Press, Inc., New York, NY

2) The second row contains the denominators of the continued fraction elements in sequence but beginning in column 3 instead of column 1 because columns 1 and 2 must be blank in this procedure.

3) The third row contains the convergents to the original fraction as they are calculated and entered. Note that the fractions 1/0 and 0/1 have been inserted into columns 1 and 2. These are two arbitrary convergents, the first equal to infinity, the second to zero, which are used to facilitate the calculations.

4) The convergent in column 3 is now calculated. To find the numerator, multiply the denominator in column 3 by the numerator of the convergent in column 2 and add the numerator of the convergent in column 1. Thus, $4 \times 0 + 1 = 1$.

5) The denominator of the convergent in column 3 is found by multiplying the denominator in column 3 by the denominator of the convergent in column 2 and adding the denominator of the convergent in column 1. Thus, $4 \times 1 + 0 = 4$, and the convergent in column 3 is then $\frac{1}{4}$ as shown in the table.

6) Finding the remaining successive convergents can be reduced to using the simple equation

$$\text{CONVERGENT}_n = \frac{(D_n)(\text{NUM}_{n-1}) + \text{NUM}_{n-2}}{(D_n)(\text{DEN}_{n-1}) + \text{DEN}_{n-2}}$$

in which n = column number in the table; D_n = denominator in column n; NUM_{n-1} and NUM_{n-2} are numerators and DEN_{n-1} and DEN_{n-2} are denominators of the convergents in the columns indicated by their subscripts; and CONVERGENT_n is the convergent in column n.

Convergents of the Continued Fraction for 2153/9277

Column Number, n	1	2	3	4	5	6	7	8	9	10	11
Denominator, D_n	—	—	4	3	4	4	1	3	1	2	2
Convergent$_n$	$\frac{1}{0}$	$\frac{0}{1}$	$\frac{1}{4}$	$\frac{3}{13}$	$\frac{13}{56}$	$\frac{55}{237}$	$\frac{68}{293}$	$\frac{259}{1116}$	$\frac{327}{1409}$	$\frac{913}{3934}$	$\frac{2153}{9277}$

Notes: The decimal values of the successive convergents in the table are alternately larger and smaller than the value of the original fraction 2153/9277. If the last convergent in the table has the same value as the original fraction 2153/9277, then *all* of the other calculated convergents are correct.

Conjugate Fractions.— In addition to finding approximate ratios by the use of continued fractions and logarithms of ratios, conjugate fractions may be used for the same purpose, independently, or in combination with the other methods.

Two fractions a/b and c/d are said to be conjugate if $ad - bc = \pm 1$. Examples of such pairs are: 0/1 and 1/1; 1/2 and 1/1; and 9/10 and 8/9. Also, *every successive pair of the convergents of a continued fraction are conjugate*. Conjugate fractions have certain properties that are useful for solving ratio problems:

1) No fraction between two conjugate fractions a/b and c/d can have a denominator smaller than either b or d.

2) A new fraction, e/f, conjugate to both fractions of a given pair of conjugate fractions, a/b and c/d, and lying between them, may be created by adding respective numerators, $a + c$, and denominators, $b + d$, so that $e/f = (a + c)/(b + d)$.

3) The denominator $f = b + d$ of the new fraction e/f is the smallest of any possible fraction lying between a/b and c/d. Thus, 17/19 is conjugate to both 8/9 and 9/10 and no fraction with denominator smaller than 19 lies between them. This property is important if it is desired to minimize the size of the factors of the ratio to be found.

The following example shows the steps to approximate a ratio for a set of gears to any desired degree of accuracy within the limits established for the allowable size of the factors in the ratio.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: Find a set of four change gears, *ab*/*cd*, to approximate the ratio 2.105399 accurate to within ± 0.0001; no gear is to have more than 120 teeth.

Step 1. Convert the given ratio *R* to a number *r* between 0 and 1 by taking its reciprocal: 1/*R* = 1/2.105399 = 0.4749693 = *r*.

Step 2. Select a pair of conjugate fractions *a*/*b* and *c*/*d* that bracket *r*. The pair *a*/*b* = 0/1 and *c*/*d* = 1/1, for example, will bracket 0.4749693.

Step 3. Add the respective numerators and denominators of the conjugates 0/1 and 1/1 to create a new conjugate *e*/*f* between 0 and 1: *e*/*f* = (*a* + *c*)/(*b* + *d*) = (0 +1)/(1 + 1) = 1/2.

Step 4. Since 0.4749693 lies between 0/1 and 1/2, *e*/*f* must also be between 0/1 and 1/2: *e*/*f* = (0 + 1)/(1 + 2) = 1/3.

Step 5. Since 0.4749693 now lies between 1/3 and 1/2, *e*/*f* must also be between 1/3 and 1/2: *e*/*f* = (1 + 1)/(3 + 2) = 2/5.

Step 6. Continuing as above to obtain successively closer approximations of *e*/*f* to 0.4749693, and using a handheld calculator and a scratch pad to facilitate the process, the fractions below, each of which has factors less than 120, were determined:

Fraction	Numerator Factors	Denominator Factors	Error
19/40	19	2 × 2 × 2 × 5	+ .000031
28/59	2 × 2 × 7	59	– .00039
47/99	47	3 × 3 × 11	– .00022
104/219	2 × 2 × 2 × 13	3 × 73	–.000083
123/259	3 × 41	7 × 37	– .000066
142/299	2 × 71	13 × 23	– .000053
161/339	7 × 23	3 × 113	– .000043
218/459	2 × 109	3 × 3 × 3 × 17	– .000024
256/539	2 × 2 × 2 × 2 × 2 × 2 ×2 ×2	7 × 7 × 11	– .000016
370/779	2 × 5 × 37	19 × 41	– .0000014
759/1598	3 × 11 × 23	2 × 17 × 47	– .00000059

Factors for the numerators and denominators of the fractions shown above were found with the aid of the Prime Numbers and Factors tables beginning on page 20. Since in Step 1 the desired ratio of 2.105399 was converted to its reciprocal 0.4749693, all of the above fractions should be inverted. Note also that the last fraction, 759/1598, when inverted to become 1598/759, is in error from the desired value by approximately one-half the amount obtained by trial and error using earlier methods.

Using Continued Fraction Convergents as Conjugates.— Since successive convergents of a continued fraction are also conjugate, they may be used to find a series of additional fractions in between themselves. As an example, the successive convergents 55/237 and 68/293 from the table of convergents for 2153/9277 on page 12 will be used to demonstrate the process for finding the first few in-between ratios.

Desired Fraction *N*/*D* = 2153/9277 = 0.2320793

	a/*b*	*e*/*f*	*c*/*d*
(1)	55/237 = .2320675	[a]123/530 = .2320755 error = –.0000039	68/293 = .2320819
(2)	123/530 = .2320755	191/823 = .2320778 error = –.0000016	68/293 = .2320819
(3)	191/823 = .2320778	[a]259/1116 = .2320789 error = –.0000005	68/293 = .2320819
(4)	259/1116 = .2320789	327/1409 = .2320795 error = + .0000002	68/293 = .2320819
(5)	259/1116 = .2320789	586/2525 = .2320792 error = – .0000001	327/1409 = .2320795
(6)	586/2525 = .2320792	913/3934 = .2320793 error = – .0000000	327/1409 = .2320795

[a] Only these ratios had suitable factors below 120.

Step 1. Check the convergents for conjugateness: 55 × 293 – 237 × 68 = 16115 – 16116 = –1 proving the pair to be conjugate.

Copyright 2004, Industrial Press, Inc., New York, NY

Step 2. Set up a table as shown above. The leftmost column of line (1) contains the convergent of lowest value, *a/b*; the rightmost the higher value, *c/d*; and the center column the derived value *e/f* found by adding the respective numerators and denominators of *a/b* and *c/d*. The error or difference between *e/f* and the desired value *N/D*, error = *N/D* − *e/f*, is also shown.

Step 3. On line (2), the process used on line (1) is repeated with the *e/f* value from line (1) becoming the new value of *a/b* while the *c/d* value remains unchanged. Had the error in *e/f* been + instead of −, then *e/f* would have been the new *c/d* value and *a/b* would be unchanged.

Step 4. The process is continued until, as seen on line (4), the error changes sign to + from the previous −. When this occurs, the *e/f* value becomes the *c/d* value on the next line instead of *a/b* as previously and the *a/b* value remains unchanged.

Powers and Roots

The *square* of a number (or quantity) is the product of that number multiplied by itself. Thus, the square of 9 is $9 \times 9 = 81$. The square of a number is indicated by the *exponent* (2), thus: $9^2 = 9 \times 9 = 81$.

The *cube* or *third power* of a number is the product obtained by using that number as a factor three times. Thus, the cube of 4 is $4 \times 4 \times 4 = 64$, and is written 4^3.

If a number is used as a factor four or five times, respectively, the product is the fourth or fifth power. Thus, $3^4 = 3 \times 3 \times 3 \times 3 = 81$, and $2^5 = 2 \times 2 \times 2 \times 2 \times 2 = 32$. A number can be raised to any power by using it as a factor the required number of times.

The *square root* of a given number is that number which, when multiplied by itself, will give a product equal to the given number. The square root of 16 (written $\sqrt{16}$) equals 4, because $4 \times 4 = 16$.

The *cube root* of a given number is that number which, when used as a factor three times, will give a product equal to the given number. Thus, the cube root of 64 (written $\sqrt[3]{64}$) equals 4, because $4 \times 4 \times 4 = 64$.

The fourth, fifth, etc., roots of a given number are those numbers which when used as factors four, five, etc., times, will give as a product the given number. Thus, $\sqrt[4]{16} = 2$, because $2 \times 2 \times 2 \times 2 = 16$.

In some formulas, there may be such expressions as $(a^2)^3$ and $a^{3/2}$. The first of these, $(a^2)^3$, means that the number a is first to be squared, a^2, and the result then cubed to give a^6. Thus, $(a^2)^3$ is equivalent to a^6 which is obtained by *multiplying* the exponents 2 and 3. Similarly, $a^{3/2}$ may be interpreted as the cube of the square root of a, $(\sqrt{a})^3$, or $(a^{1/2})^3$, so that, for example, $16^{3/2} = (\sqrt{16})^3 = 64$.

The multiplications required for raising numbers to powers and the extracting of roots are greatly facilitated by the use of logarithms. Extracting the square root and cube root by the regular arithmetical methods is a slow and cumbersome operation, and any roots can be more rapidly found by using logarithms.

When the power to which a number is to be raised is not an integer, say 1.62, the use of either logarithms or a scientific calculator becomes the only practical means of solution.

Powers of Ten Notation.— Powers of ten notation is used to simplify calculations and ensure accuracy, particularly with respect to the position of decimal points, and also simplifies the expression of numbers which are so large or so small as to be unwieldy. For example, the metric (SI) pressure unit pascal is equivalent to 0.00000986923 atmosphere or 0.0001450377 pound/inch^2. In powers of ten notation, these figures are 9.86923×10^{-6}

Copyright 2004, Industrial Press, Inc., New York, NY

atmosphere and 1.450377×10^{-4} pound/inch^2. The notation also facilitates adaptation of numbers for electronic data processing and computer readout.

Expressing Numbers in Powers of Ten Notation.— In this system of notation, every number is expressed by two factors, one of which is some integer from 1 to 9 followed by a decimal and the other is some power of 10.

Thus, 10,000 is expressed as 1.0000×10^4 and 10,463 as 1.0463×10^4. The number 43 is expressed as 4.3×10 and 568 is expressed. as 5.68×10^2.

In the case of decimals, the number 0.0001, which as a fraction is $1/10000$ and is expressed as 1×10^{-4} and 0.0001463 is expressed as 1.463×10^{-4}. The decimal 0.498 is expressed as 4.98×10^{-1} and 0.03146 is expressed as 3.146×10^{-2}.

Rules for Converting Any Number to Powers of Ten Notation.— Any number can be converted to the powers of ten notation by means of one of two rules.

Rule 1: If the number is a whole number or a whole number and a decimal so that it has digits to the left of the decimal point, the decimal point is moved a sufficient number of places to the *left* to bring it to the immediate right of the first digit. With the decimal point shifted to this position, the number so written comprises the *first* factor when written in powers of ten notation.

The number of places that the decimal point is moved to the left to bring it immediately to the right of the first digit is the *positive* index or power of 10 that comprises the *second* factor when written in powers of ten notation.

Thus, to write 4639 in this notation, the decimal point is moved three places to the left giving the two factors: 4.639×10^3. Similarly,

$$431.412 = 4.31412 \times 10^2 \qquad 986388 = 9.86388 \times 10^5$$

Rule 2: If the number is a decimal, i.e., it has digits entirely to the right of the decimal point, then the decimal point is moved a sufficient number of places to the *right* to bring it immediately to the right of the first digit. With the decimal point shifted to this position, the number so written comprises the *first* factor when written in powers of ten notation.

The number of places that the decimal point is moved to the *right* to bring it immediately to the right of the first digit is the *negative* index or power of 10 that follows the number when written in powers of ten notation.

Thus, to bring the decimal point in 0.005721 to the immediate right of the first digit, which is 5, it must be moved *three* places to the right, giving the two factors: 5.721×10^{-3}. Similarly,

$$0.469 = 4.69 \times 10^{-1} \qquad 0.0000516 = 5.16 \times 10^{-5}$$

Multiplying Numbers Written in Powers of Ten Notation.— When multiplying two numbers written in the powers of ten notation together, the procedure is as follows:

1) Multiply the first factor of one number by the first factor of the other to obtain the first factor of the product.

2) Add the index of the second factor (which is some power of 10) of one number to the index of the second factor of the other number to obtain the index of the second factor (which is some power of 10) in the product. Thus:

$$(4.31 \times 10^{-2}) \times (9.0125 \times 10) = (4.31 \times 9.0125) \times 10^{-2+1} = 38.844 \times 10^{-1}$$

$$(5.986 \times 10^4) \times (4.375 \times 10^3) = (5.986 \times 4.375) \times 10^{4+3} = 26.189 \times 10^7$$

In the preceding calculations, neither of the results shown are in the conventional powers of ten form since the first factor in each has two digits. In the conventional powers of ten notation, the results would be

$38.844 \times 10^{-1} = 3.884 \times 10^0 = 3.884$, since $10^0 = 1$, and $26.189 \times 10^7 = 2.619 \times 10^8$

in each case rounding off the first factor to three decimal places.

Copyright 2004, Industrial Press, Inc., New York, NY

When multiplying several numbers written in this notation together, the procedure is the same. All of the first factors are multiplied together to get the first factor of the product and all of the indices of the respective powers of ten are added together, taking into account their respective signs, to get the index of the second factor of the product. Thus, $(4.02 \times 10^{-3}) \times (3.987 \times 10) \times (4.863 \times 10^{5}) = (4.02 \times 3.987 \times 4.863) \times 10^{(-3+1+5)} = 77.94 \times 10^{3} = 7.79 \times 10^{4}$ rounding off the first factor to two decimal places.

Dividing Numbers Written in Powers of Ten Notation.— When dividing one number by another when both are written in this notation, the procedure is as follows:

1) Divide the first factor of the dividend by the first factor of the divisor to get the first factor of the quotient.

2) Subtract the index of the second factor of the divisor from the index of the second factor of the dividend, taking into account their respective signs, to get the index of the second factor of the quotient. Thus:

$$(4.31 \times 10^{-2}) \div (9.0125 \times 10) =$$
$$(4.31 \div 9.0125) \times (10^{-2-1}) = 0.4782 \times 10^{-3} = 4.782 \times 10^{-4}$$

It can be seen that this system of notation is helpful where several numbers of different magnitudes are to be multiplied and divided.

Example: Find the quotient of $\dfrac{250 \times 4698 \times 0.00039}{43678 \times 0.002 \times 0.0147}$

Solution: Changing all these numbers to powers of ten notation and performing the operations indicated:

$$\frac{(2.5 \times 10^{2}) \times (4.698 \times 10^{3}) \times (3.9 \times 10^{-4})}{(4.3678 \times 10^{4}) \times (2 \times 10^{-3}) \times (1.47 \times 10^{-2})} =$$
$$= \frac{(2.5 \times 4.698 \times 3.9)(10^{2+3-4})}{(4.3678 \times 2 \times 1.47)(10^{4-3-2})} = \frac{45.8055 \times 10}{12.8413 \times 10^{-1}}$$
$$= 3.5670 \times 10^{1-(-1)} = 3.5670 \times 10^{2} = 356.70$$

Constants Frequently Used in Mathematical Expressions

$0.00872665 = \frac{\pi}{360}$	$0.8660254 = \frac{\sqrt{3}}{2}$	$2.0943951 = \frac{2\pi}{3}$	$4.712389 = \frac{3\pi}{2}$
$0.01745329 = \frac{\pi}{180}$	$1.0471975 = \frac{\pi}{3}$	$2.3561945 = \frac{3\pi}{4}$	$5.2359878 = \frac{5\pi}{3}$
$0.26179939 = \frac{\pi}{12}$	$1.1547005 = \frac{2\sqrt{3}}{3}$	$2.5980762 = \frac{3\sqrt{3}}{2}$	$5.4977871 = \frac{7\pi}{4}$
$0.39269908 = \frac{\pi}{8}$	$1.2247449 = \sqrt{\frac{3}{2}}$	$2.6179939 = \frac{5\pi}{6}$	$5.7595865 = \frac{11\pi}{6}$
$0.52359878 = \frac{\pi}{6}$	$1.4142136 = \sqrt{2}$	$3.1415927 = \pi$	$6.2831853 = 2\pi$
$0.57735027 = \frac{\sqrt{3}}{3}$	$1.5707963 = \frac{\pi}{2}$	$3.6651914 = \frac{7\pi}{6}$	$9.8696044 = \pi^2$
$0.62035049 = \sqrt[3]{\frac{3}{4\pi}}$	$1.7320508 = \sqrt{3}$	$3.9269908 = \frac{5\pi}{4}$	$9.424778 = 3\pi$
$0.78539816 = \frac{\pi}{4}$	$2.4674011 = \frac{\pi^2}{4}$	$4.1887902 = \frac{4\pi}{3}$	$12.566371 = 4\pi$
			$57.29578 = \frac{180}{\pi}$
			$114.59156 = \frac{360}{\pi}$

Copyright 2004, Industrial Press, Inc., New York, NY

Imaginary and Complex Numbers

Complex or Imaginary Numbers.— Complex or imaginary numbers represent a class of mathematical objects that are used to simplify certain problems, such as the solution of polynomial equations. The basis of the complex number system is the unit imaginary number i that satisfies the following relations:

$$i^2 = (-i)^2 = -1 \qquad i = \sqrt{-1} \qquad -i = -\sqrt{-1}$$

In electrical engineering and other fields, the unit imaginary number is often represented by j rather than i. However, the meaning of the two terms is identical.

Rectangular or Trigonometric Form: Every complex number, Z, can be written as the sum of a real number and an imaginary number. When expressed as a sum, $Z = a + bi$, the complex number is said to be in rectangular or trigonometric form. The real part of the number is a, and the imaginary portion is bi because it has the imaginary unit assigned to it.

Polar Form: A complex number $Z = a + bi$ can also be expressed in polar form, also known as phasor form. In polar form, the complex number Z is represented by a magnitude r and an angle θ as follows:

$$Z = r\angle\theta$$

$\angle\theta$ = a direction, the angle whose tangent is $b \div a$, thus $\theta = \operatorname{atan}\dfrac{b}{a}$ and

$r = \sqrt{a^2 + b^2}$ is the magnitude

A complex number can be plotted on a real-imaginary coordinate system known as the complex plane. The figure below illustrates the relationship between the rectangular coordinates a and b, and the polar coordinates r and θ.



Complex Number in the Complex Plane

The rectangular form can be determined from r and θ as follows:

$$a = r\cos\theta \qquad b = r\sin\theta \qquad a + bi = r\cos\theta + ir\sin\theta = r(\cos\theta + i\sin\theta)$$

The rectangular form can also be written using Euler's Formula:

$$e^{\pm i\theta} = \cos\theta \pm i\sin\theta \qquad \sin\theta = \frac{e^{i\theta} - e^{-i\theta}}{2i} \qquad \cos\theta = \frac{e^{i\theta} + e^{-i\theta}}{2}$$

Complex Conjugate: Complex numbers commonly arise in finding the solution of polynomials. A polynomial of n^{th} degree has n solutions, an even number of which are complex and the rest are real. The complex solutions always appear as complex conjugate pairs in the form $a + bi$ and $a - bi$. The product of these two conjugates, $(a + bi) \times (a - bi) = a^2 + b^2$, is the square of the magnitude r illustrated in the previous figure.

Operations on Complex Numbers

Example 1, Addition: When adding two complex numbers, the real parts and imaginary parts are added separately, the real parts added to real parts and the imaginary to imaginary parts. Thus,

Copyright 2004, Industrial Press, Inc., New York, NY

$$(a_1 + ib_1) + (a_2 + ib_2) = (a_1 + a_2) + i(b_1 + b_2)$$
$$(a_1 + ib_1) - (a_2 + ib_2) = (a_1 - a_2) + i(b_1 - b_2)$$
$$(3 + 4i) + (2 + i) = (3 + 2) + (4 + 1)i = 5 + 5i$$

Example 2, Multiplication: Multiplication of two complex numbers requires the use of the imaginary unit, $i^2 = -1$ and the algebraic distributive law.

$$\begin{aligned}(a_1 + ib_1)(a_2 + ib_2) &= a_1a_2 + ia_1b_2 + ia_2b_1 + i^2b_1b_2 \\ &= a_1a_2 + ia_1b_2 + ia_2b_1 - b_1b_2 \\ (7 + 2i) \times (5 - 3i) &= (7)(5) - (7)(3i) + (2i)(5) - (2i)(3i) \\ &= 35 - 21i + 10i - 6i^2 \\ &= 35 - 21i + 10i - (6)(-1) = 41 - 11i\end{aligned}$$

Multiplication of two complex numbers, $Z_1 = r_1(\cos\theta_1 + i\sin\theta_1)$ and $Z_2 = r_2(\cos\theta_2 + i\sin\theta_2)$, results in the following:

$$Z_1 \times Z_2 = r_1(\cos\theta_1 + i\sin\theta_1) \times r_2(\cos\theta_2 + i\sin\theta_2) = r_1r_2[\cos(\theta_1 + \theta_2) + i\sin(\theta_1 + \theta_2)]$$

Example 3, Division: Divide the following two complex numbers, $2 + 3i$ and $4 - 5i$. Dividing complex numbers makes use of the complex conjugate.

$$\frac{2 + 3i}{4 - 5i} = \frac{(2 + 3i)(4 + 5i)}{(4 - 5i)(4 + 5i)} = \frac{8 + 12i + 10i + 15i^2}{16 + 20i - 20i - 25i^2} = \frac{-7 + 22i}{16 + 25} = \left(\frac{-7}{41}\right) + i\left(\frac{22}{41}\right)$$

Example 4: Convert the complex number 8+6*i* into phasor form.

First find the magnitude of the phasor vector and then the direction.

$$\text{magnitude} = \sqrt{8^2 + 6^2} = 10 \quad \text{direction} = \operatorname{atan}\frac{6}{8} = 36.87°$$

$$\text{phasor} = 10\angle 36.87°$$

Factorial.— A factorial is a mathematical shortcut denoted by the symbol **!** following a number (for example, 3! is three factorial). A factorial is found by multiplying together all the integers greater than zero and less than or equal to the factorial number wanted, except for zero factorial (0!), which is defined as 1. For example: $3! = 1 \times 2 \times 3 = 6$; $4! = 1 \times 2 \times 3 \times 4 = 24$; $7! = 1 \times 2 \times 3 \times 4 \times 5 \times 6 \times 7 = 5040$; etc.

Example: How many ways can the letters X, Y, and Z be arranged?

Solution: The numbers of possible arrangements for the three letters are $3! = 3 \times 2 \times 1 = 6$.

Permutations.— The number of ways *r* objects may be arranged from a set of *n* elements is given by

$${}^nP_r = \frac{n!}{(n - r)!}$$

Example: There are 10 people are participating in the final run. In how many different ways can these people come in first, second and third.

Solution: Here *r* is 3 and *n* is 10. So the possible numbers of winning number will be

$${}^{10}P_3 = \frac{10!}{(10 - 3)!} = \frac{10!}{7!} = 10 \times 9 \times 8 = 720$$

Combinations.— The number of ways *r* distinct objects may be chosen from a set of *n* elements is given by

$${}^nC_r = \frac{n!}{(n - r)!r!}$$

Example: How many possible sets of 6 winning numbers can be picked from 52 numbers.

Copyright 2004, Industrial Press, Inc., New York, NY

Solution: Here r is 6 and n is 52. So the possible number of winning combinations will be

$$^{52}C_6 = \frac{52!}{(52-6)!6!} = \frac{52!}{46!6!} = \frac{52 \times 51 \times 50 \times 49 \times 48 \times 47}{1 \times 2 \times 3 \times 4 \times 5 \times 6} = 20358520$$

Prime Numbers and Factors of Numbers

The *factors* of a given number are those numbers which when multiplied together give a product equal to that number; thus, 2 and 3 are factors of 6; and 5 and 7 are factors of 35.

A *prime number* is one which has no factors except itself and 1. Thus, 2, 3, 5, 7, 11, etc., are prime numbers. A factor which is a prime number is called a *prime factor*.

The accompanying "Prime Number and Factor Tables," starting on page 20, give the smallest prime factor of all odd numbers from 1 to 9600, and can be used for finding all the factors for numbers up to this limit. For example, find the factors of 931. In the column headed "900" and in the line indicated by "31" in the left-hand column, the smallest prime factor is found to be 7. As this leaves another factor 133 (since 931 ÷ 7 = 133), find the smallest prime factor of this number. In the column headed "100" and in the line "33", this is found to be 7, leaving a factor 19. This latter is a prime number; hence, the factors of 931 are 7 × 7 × 19. Where no factor is given for a number in the factor table, it indicates that the number is a prime number.

The last page of the tables lists all prime numbers from 9551 through 18691; and can be used to identify quickly all unfactorable numbers in that range.

For factoring, the following general rules will be found useful:

2 is a factor of any number the right-hand figure of which is an even number or 0. Thus, 28 = 2 × 14, and 210 = 2 × 105.

3 is a factor of any number the sum of the figures of which is evenly divisible by 3. Thus, 3 is a factor of 1869, because 1 + 8 + 6 + 9 = 24 ÷ 3 = 8.

4 is a factor of any number the two right-hand figures of which, considered as one number, are evenly divisible by 4. Thus, 1844 has a factor 4, because 44 ÷ 4 = 11.

5 is a factor of any number the right-hand figure of which is 0 or 5. Thus, 85 = 5 × 17; 70 = 5 × 14.

Tables of prime numbers and factors of numbers are particularly useful for calculations involving change-gear ratios for compound gearing, dividing heads, gear-generating machines, and mechanical designs having gear trains.

Example 1: A set of four gears is required in a mechanical design to provide an overall gear ratio of 4104 ÷ 1200. Furthermore, no gear in the set is to have more than 120 teeth or less than 24 teeth. Determine the tooth numbers.

First, as explained previously, the factors of 4104 are determined to be: 2 × 2 × 2 × 3 × 3 × 57 = 4104. Next, the factors of 1200 are determined: 2 × 2 × 2 × 2 × 5 × 5 × 3 = 1200. Therefore $\frac{4104}{1200} = \frac{2 \times 2 \times 2 \times 3 \times 3 \times 57}{2 \times 2 \times 2 \times 2 \times 5 \times 5 \times 3} = \frac{72 \times 57}{24 \times 50}$. If the factors had been combined differently, say, to give $\frac{72 \times 57}{16 \times 75}$, then the 16-tooth gear in the denominator would not satisfy the requirement of no less than 24 teeth.

Example 2: Factor the number 25078 into two numbers neither of which is larger than 200.

The first factor of 25078 is obviously 2, leaving 25078 ÷ 2 = 12539 to be factored further. However, from the last table, *Prime Numbers from 9551 to 18691*, it is seen that 12539 is a prime number; therefore, no solution exists.

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 1 to 1199

From To	0 100	100 200	200 300	300 400	400 500	500 600	600 700	700 800	800 900	900 1000	1000 1100	1100 1200
1	P	P	3	7	P	3	P	P	3	17	7	3
2	P	2	2	2	2	2	2	2	2	2	2	2
3	P	P	7	3	13	P	3	19	11	3	17	P
5	P	3	5	5	3	5	5	3	5	5	3	5
7	P	P	3	P	11	3	P	7	3	P	19	3
9	3	P	11	3	P	P	3	P	P	3	P	P
11	P	3	P	P	3	7	13	3	P	P	3	11
13	P	P	3	P	7	3	P	23	3	11	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	P	3	7	P	3	11	P	3	19	7	3	P
19	P	7	3	11	P	3	P	P	3	P	P	3
21	3	11	13	3	P	P	3	7	P	3	P	19
23	P	3	P	17	3	P	7	3	P	13	3	P
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	P	P	3	7	17	3	P	P	3	13	7
29	P	3	P	7	3	23	17	3	P	P	3	P
31	P	P	3	P	P	3	P	17	3	7	P	3
33	3	7	P	3	P	13	3	P	7	3	P	11
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	P	3	P	19	3	7	11	3	P	17	3
39	3	P	P	3	P	7	3	P	P	3	P	17
41	P	3	P	11	3	P	P	3	29	P	3	7
43	P	11	3	7	P	3	P	P	3	23	7	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	P	3	13	P	3	P	P	3	7	P	3	31
49	7	P	3	P	P	3	11	7	3	13	P	3
51	3	P	P	3	11	19	3	P	23	3	P	P
53	P	3	11	P	3	7	P	3	P	P	3	P
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	P	P	3	P	P	3	P	P	3	7	13
59	P	3	7	P	3	13	P	3	P	7	3	19
61	P	7	3	19	P	3	P	P	3	31	P	3
63	3	P	P	3	P	P	3	7	P	3	P	P
65	5	3	5	5	3	5	5	3	5	5	3	5
67	P	P	3	P	P	3	23	13	3	P	11	3
69	3	13	P	3	7	P	3	P	11	3	P	7
71	P	3	P	7	3	P	11	3	13	P	3	P
73	P	P	3	P	11	3	P	P	3	7	29	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	7	3	P	13	3	P	P	3	P	P	3	11
79	P	P	3	P	P	3	7	19	3	11	13	3
81	3	P	P	3	13	7	3	11	P	3	23	P
83	P	3	P	P	3	11	P	3	P	P	3	7
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	11	7	3	P	P	3	P	P	3	P	P
89	P	3	17	P	3	19	13	3	7	23	3	29
91	7	P	3	17	P	3	P	7	3	P	P	3
93	3	P	P	3	17	P	3	13	19	3	P	P
95	5	3	5	5	3	5	5	3	5	5	3	5
97	P	P	3	P	7	3	17	P	3	P	P	3
99	3	P	13	3	P	P	3	17	29	3	7	11

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 1201 to 2399

From To	1200 1300	1300 1400	1400 1500	1500 1600	1600 1700	1700 1800	1800 1900	1900 2000	2000 2100	2100 2200	2200 2300	2300 2400
1	P	P	3	19	P	3	P	P	3	11	31	3
3	3	P	23	3	7	13	3	11	P	3	P	7
5	5	3	5	5	3	5	5	3	5	5	3	5
7	17	P	3	11	P	3	13	P	3	7	P	3
9	3	7	P	3	P	P	3	23	7	3	47	P
11	7	3	17	P	3	29	P	3	P	P	3	P
13	P	13	3	17	P	3	7	P	3	P	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	P	3	13	37	3	17	23	3	P	29	3	7
19	23	P	3	7	P	3	17	19	3	13	7	3
21	3	P	7	3	P	P	3	17	43	3	P	11
23	P	3	P	P	3	P	P	3	7	11	3	23
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	P	P	3	P	11	3	41	P	3	17	13
29	P	3	P	11	3	7	31	3	P	P	3	17
31	P	11	3	P	7	3	P	P	3	P	23	3
33	3	31	P	3	23	P	3	P	19	3	7	P
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	7	3	29	P	3	11	13	3	P	P	3
39	3	13	P	3	11	37	3	7	P	3	P	P
41	17	3	11	23	3	P	7	3	13	P	3	P
43	11	17	3	P	31	3	19	29	3	P	P	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	29	3	P	7	3	P	P	3	23	19	3	P
49	P	19	3	P	17	3	43	P	3	7	13	3
51	3	7	P	3	13	17	3	P	7	3	P	P
53	7	3	P	P	3	P	17	3	P	P	3	13
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	23	31	3	P	7	3	19	11	3	37	P
59	P	3	P	P	3	P	11	3	29	17	3	7
61	13	P	3	7	11	3	P	37	3	P	7	3
63	3	29	7	3	P	41	3	13	P	3	31	17
65	5	3	5	5	3	5	5	3	5	5	3	5
67	7	P	3	P	P	3	P	7	3	11	P	3
69	3	37	13	3	P	29	3	11	P	3	P	23
71	31	3	P	P	3	7	P	3	19	13	3	P
73	19	P	3	11	7	3	P	P	3	41	P	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	P	3	7	19	3	P	P	3	31	7	3	P
79	P	7	3	P	23	3	P	P	3	P	43	3
81	3	P	P	3	41	13	3	7	P	3	P	P
83	P	3	P	P	3	P	7	3	P	37	3	P
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	19	P	3	7	P	3	P	P	3	P	7
89	P	3	P	7	3	P	P	3	P	11	3	P
91	P	13	3	37	19	3	31	11	3	7	29	3
93	3	7	P	3	P	11	3	P	7	3	P	P
95	5	3	5	5	3	5	5	3	5	5	3	5
97	P	11	3	P	P	3	7	P	3	13	P	3
99	3	P	P	3	P	7	3	P	P	3	11	P

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 2401 to 3599

From To	2400 2500	2500 2600	2600 2700	2700 2800	2800 2900	2900 3000	3000 3100	3100 3200	3200 3300	3300 3400	3400 3500	3500 3600
1	7	41	3	37	P	3	P	7	3	P	19	3
3	3	P	19	3	P	P	3	29	P	3	41	31
5	5	3	5	5	3	5	5	3	5	5	3	5
7	29	23	3	P	7	3	31	13	3	P	P	3
9	3	13	P	3	53	P	3	P	P	3	7	11
11	P	3	7	P	3	41	P	3	13	7	3	P
13	19	7	3	P	29	3	23	11	3	P	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	P	3	P	11	3	P	7	3	P	31	3	P
19	41	11	3	P	P	3	P	P	3	P	13	3
21	3	P	P	3	7	23	3	P	P	3	11	7
23	P	3	43	7	3	37	P	3	11	P	3	13
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	7	37	3	11	P	3	53	7	3	23	P
29	7	3	11	P	3	29	13	3	P	P	3	P
31	11	P	3	P	19	3	7	31	3	P	47	3
33	3	17	P	3	P	7	3	13	53	3	P	P
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	43	3	7	P	3	P	P	3	47	7	3
39	3	P	7	3	17	P	3	43	41	3	19	P
41	P	3	19	P	3	17	P	3	7	13	3	P
43	7	P	3	13	P	3	17	7	3	P	11	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	P	3	P	41	3	7	11	3	17	P	3	P
49	31	P	3	P	7	3	P	47	3	17	P	3
51	3	P	11	3	P	13	3	23	P	3	7	53
53	11	3	7	P	3	P	43	3	P	7	3	11
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	P	P	3	P	P	3	7	P	3	P	P
59	P	3	P	31	3	11	7	3	P	P	3	P
61	23	13	3	11	P	3	P	29	3	P	P	3
63	3	11	P	3	7	P	3	P	13	3	P	7
65	5	3	5	5	3	5	5	3	5	5	3	5
67	P	17	3	P	47	3	P	P	3	7	P	3
69	3	7	17	3	19	P	3	P	7	3	P	43
71	7	3	P	17	3	P	37	3	P	P	3	P
73	P	31	3	47	13	3	7	19	3	P	23	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	P	3	P	P	3	13	17	3	29	11	3	7
79	37	P	3	7	P	3	P	11	3	31	7	3
81	3	29	7	3	43	11	3	P	17	3	59	P
83	13	3	P	11	3	19	P	3	7	17	3	P
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	13	P	3	P	29	3	P	19	3	11	17
89	19	3	P	P	3	7	P	3	11	P	3	37
91	47	P	3	P	7	3	11	P	3	P	P	3
93	3	P	P	3	11	41	3	31	37	3	7	P
95	5	3	5	5	3	5	5	3	5	5	3	5
97	11	7	3	P	P	3	19	23	3	43	13	3
99	3	23	P	3	13	P	3	7	P	3	P	59

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 3601 to 4799

From To	3600 3700	3700 3800	3800 3900	3900 4000	4000 4100	4100 4200	4200 4300	4300 4400	4400 4500	4500 4600	4600 4700	4700 4800
1	13	P	3	47	P	3	P	11	3	7	43	3
3	3	7	P	3	P	11	3	13	7	3	P	P
5	5	3	5	5	3	5	5	3	5	5	3	5
7	P	11	3	P	P	3	7	59	3	P	17	3
9	3	P	13	3	19	7	3	31	P	3	11	17
11	23	3	37	P	3	P	P	3	11	13	3	7
13	P	47	3	7	P	3	11	19	3	P	7	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	P	3	11	P	3	23	P	3	7	P	3	53
19	7	P	3	P	P	3	P	7	3	P	31	3
21	3	61	P	3	P	13	3	29	P	3	P	P
23	P	3	P	P	3	7	41	3	P	P	3	P
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	P	43	3	P	P	3	P	19	3	7	29
29	19	3	7	P	3	P	P	3	43	7	3	P
31	P	7	3	P	29	3	P	61	3	23	11	3
33	3	P	P	3	37	P	3	7	11	3	41	P
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	37	3	31	11	3	19	P	3	13	P	3
39	3	P	11	3	7	P	3	P	23	3	P	7
41	11	3	23	7	3	41	P	3	P	19	3	11
43	P	19	3	P	13	3	P	43	3	7	P	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	7	3	P	P	3	11	31	3	P	P	3	47
49	41	23	3	11	P	3	7	P	3	P	P	3
51	3	11	P	3	P	7	3	19	P	3	P	P
53	13	3	P	59	3	P	P	3	61	29	3	7
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	13	7	3	P	P	3	P	P	3	P	67
59	P	3	17	37	3	P	P	3	7	47	3	P
61	7	P	3	17	31	3	P	7	3	P	59	3
63	3	53	P	3	17	23	3	P	P	3	P	11
65	5	3	5	5	3	5	5	3	5	5	3	5
67	19	P	3	P	7	3	17	11	3	P	13	3
69	3	P	53	3	13	11	3	17	41	3	7	19
71	P	3	7	11	3	43	P	3	17	7	3	13
73	P	7	3	29	P	3	P	P	3	17	P	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	P	3	P	41	3	P	7	3	11	23	3	17
79	13	P	3	23	P	3	11	29	3	19	P	3
81	3	19	P	3	7	37	3	13	P	3	31	7
83	29	3	11	7	3	47	P	3	P	P	3	P
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	7	13	3	61	53	3	41	7	3	43	P
89	7	3	P	P	3	59	P	3	67	13	3	P
91	P	17	3	13	P	3	7	P	3	P	P	3
93	3	P	17	3	P	7	3	23	P	3	13	P
95	5	3	5	5	3	5	5	3	5	5	3	5
97	P	P	3	7	17	3	P	P	3	P	7	3
99	3	29	7	3	P	13	3	53	11	3	37	P

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 4801 to 5999

From To	4800 4900	4900 5000	5000 5100	5100 5200	5200 5300	5300 5400	5400 5500	5500 5600	5600 5700	5700 5800	5800 5900	5900 6000
1	P	13	3	P	7	3	11	P	3	P	P	3
3	3	P	P	3	11	P	3	P	13	3	7	P
5	5	3	5	5	3	5	5	3	5	5	3	5
7	11	7	3	P	41	3	P	P	3	13	P	3
9	3	P	P	3	P	P	3	7	71	3	37	19
11	17	3	P	19	3	47	7	3	31	P	3	23
13	P	17	3	P	13	3	P	37	3	29	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	P	3	29	7	3	13	P	3	41	P	3	61
19	61	P	3	P	17	3	P	P	3	7	11	3
21	3	7	P	3	23	17	3	P	7	3	P	31
23	7	3	P	47	3	P	11	3	P	59	3	P
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	13	11	3	P	7	3	P	17	3	P	P
29	11	3	47	23	3	73	61	3	13	17	3	7
31	P	P	3	7	P	3	P	P	3	11	7	3
33	3	P	7	3	P	P	3	11	43	3	19	17
35	5	3	5	5	3	5	5	3	5	5	3	5
37	7	P	3	11	P	3	P	7	3	P	13	3
39	3	11	P	3	13	19	3	29	P	3	P	P
41	47	3	71	53	3	7	P	3	P	P	3	13
43	29	P	3	37	7	3	P	23	3	P	P	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	37	3	7	P	3	P	13	3	P	7	3	19
49	13	7	3	19	29	3	P	31	3	P	P	3
51	3	P	P	3	59	P	3	7	P	3	P	11
53	23	3	31	P	3	53	7	3	P	11	3	P
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	P	13	3	7	11	3	P	P	3	P	7
59	43	3	P	7	3	23	53	3	P	13	3	59
61	P	11	3	13	P	3	43	67	3	7	P	3
63	3	7	61	3	19	31	3	P	7	3	11	67
65	5	3	5	5	3	5	5	3	5	5	3	5
67	31	P	3	P	23	3	7	19	3	73	P	3
69	3	P	37	3	11	7	3	P	P	3	P	47
71	P	3	11	P	3	41	P	3	53	29	3	7
73	11	P	3	7	P	3	13	P	3	23	7	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	P	3	P	31	3	19	P	3	7	53	3	43
79	7	13	3	P	P	3	P	7	3	P	P	3
81	3	17	P	3	P	P	3	P	13	3	P	P
83	19	3	13	71	3	7	P	3	P	P	3	31
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	P	P	3	17	P	3	37	11	3	7	P
89	P	3	7	P	3	17	11	3	P	7	3	53
91	67	7	3	29	11	3	17	P	3	P	43	3
93	3	P	11	3	67	P	3	7	P	3	71	13
95	5	3	5	5	3	5	5	3	5	5	3	5
97	59	19	3	P	P	3	23	29	3	11	P	3
99	3	P	P	3	7	P	3	11	41	3	17	7

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 6001 to 7199

From To	6000 6100	6100 6200	6200 6300	6300 6400	6400 6500	6500 6600	6600 6700	6700 6800	6800 6900	6900 7000	7000 7100	7100 7200
1	17	P	3	P	37	3	7	P	3	67	P	3
3	3	17	P	3	19	7	3	P	P	3	47	P
5	5	3	5	5	3	5	5	3	5	5	3	5
7	P	31	3	7	43	3	P	19	3	P	7	3
9	3	41	7	3	13	23	3	P	11	3	43	P
11	P	3	P	P	3	17	11	3	7	P	3	13
13	7	P	3	59	11	3	17	7	3	31	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	11	3	P	P	3	7	13	3	17	P	3	11
19	13	29	3	71	7	3	P	P	3	11	P	3
21	3	P	P	3	P	P	3	11	19	3	7	P
23	19	3	7	P	3	11	37	3	P	7	3	17
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	11	13	3	P	61	3	7	P	3	P	P
29	P	3	P	P	3	P	7	3	P	13	3	P
31	37	P	3	13	59	3	19	53	3	29	79	3
33	3	P	23	3	7	47	3	P	P	3	13	7
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	17	3	P	41	3	P	P	3	7	31	3
39	3	7	17	3	47	13	3	23	7	3	P	11
41	7	3	79	17	3	31	29	3	P	11	3	37
43	P	P	3	P	17	3	7	11	3	53	P	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	P	3	P	11	3	P	17	3	41	P	3	7
49	23	11	3	7	P	3	61	17	3	P	7	3
51	3	P	7	3	P	P	3	43	13	3	11	P
53	P	3	13	P	3	P	P	3	7	17	3	23
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	47	P	3	11	79	3	29	P	3	P	17
59	73	3	11	P	3	7	P	3	19	P	3	P
61	11	61	3	P	7	3	P	P	3	P	23	3
63	3	P	P	3	23	P	3	P	P	3	7	13
65	5	3	5	5	3	5	5	3	5	5	3	5
67	P	7	3	P	29	3	59	67	3	P	37	3
69	3	31	P	3	P	P	3	7	P	3	P	67
71	13	3	P	23	3	P	7	3	P	P	3	71
73	P	P	3	P	P	3	P	13	3	19	11	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	59	3	P	7	3	P	11	3	13	P	3	P
79	P	37	3	P	11	3	P	P	3	7	P	3
81	3	7	11	3	P	P	3	P	7	3	73	43
83	7	3	61	13	3	29	41	3	P	P	3	11
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	23	P	3	13	7	3	11	71	3	19	P
89	P	3	19	P	3	11	P	3	83	29	3	7
91	P	41	3	7	P	3	P	P	3	P	7	3
93	3	11	7	3	43	19	3	P	61	3	41	P
95	5	3	5	5	3	5	5	3	5	5	3	5
97	7	P	3	P	73	3	37	7	3	P	47	3
99	3	P	P	3	67	P	3	13	P	3	31	23

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 7201 to 8399

From To	7200 7300	7300 7400	7400 7500	7500 7600	7600 7700	7700 7800	7800 7900	7900 8000	8000 8100	8100 8200	8200 8300	8300 8400
1	19	7	3	13	11	3	29	P	3	P	59	3
3	3	67	11	3	P	P	3	7	53	3	13	19
5	5	3	5	5	3	5	5	3	5	5	3	5
7	P	P	3	P	P	3	37	P	3	11	29	3
9	3	P	31	3	7	13	3	11	P	3	P	7
11	P	3	P	7	3	11	73	3	P	P	3	P
13	P	71	3	11	23	3	13	41	3	7	43	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	7	3	P	P	3	P	P	3	P	P	3	P
19	P	13	3	73	19	3	7	P	3	23	P	3
21	3	P	41	3	P	7	3	89	13	3	P	53
23	31	3	13	P	3	P	P	3	71	P	3	7
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	17	7	3	29	P	3	P	23	3	19	11
29	P	3	17	P	3	59	P	3	7	11	3	P
31	7	P	3	17	13	3	41	7	3	47	P	3
33	3	P	P	3	17	11	3	P	29	3	P	13
35	5	3	5	5	3	5	5	3	5	5	3	5
37	P	11	3	P	7	3	17	P	3	79	P	3
39	3	41	43	3	P	71	3	17	P	3	7	31
41	13	3	7	P	3	P	P	3	11	7	3	19
43	P	7	3	19	P	3	11	13	3	17	P	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	P	3	11	P	3	61	7	3	13	P	3	17
49	11	P	3	P	P	3	47	P	3	29	73	3
51	3	P	P	3	7	23	3	P	83	3	37	7
53	P	3	29	7	3	P	P	3	P	31	3	P
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	7	P	3	13	P	3	73	7	3	23	61
59	7	3	P	P	3	P	29	3	P	41	3	13
61	53	17	3	P	47	3	7	19	3	P	11	3
63	3	37	17	3	79	7	3	P	11	3	P	P
65	5	3	5	5	3	5	5	3	5	5	3	5
67	13	53	3	7	11	3	P	31	3	P	7	3
69	3	P	7	3	P	17	3	13	P	3	P	P
71	11	3	31	67	3	19	17	3	7	P	3	11
73	7	73	3	P	P	3	P	7	3	11	P	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	19	3	P	P	3	7	P	3	41	13	3	P
79	29	47	3	11	7	3	P	79	3	P	17	3
81	3	11	P	3	P	31	3	23	P	3	7	17
83	P	3	7	P	3	43	P	3	59	7	3	83
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	83	P	3	P	13	3	7	P	3	P	P
89	37	3	P	P	3	P	7	3	P	19	3	P
91	23	19	3	P	P	3	13	61	3	P	P	3
93	3	P	59	3	7	P	3	P	P	3	P	7
95	5	3	5	5	3	5	5	3	5	5	3	5
97	P	13	3	71	43	3	53	11	3	7	P	3
99	3	7	P	3	P	11	3	19	7	3	43	37

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Number and Factor Table for 8401 to 9599

From To	8400 8500	8500 8600	8600 8700	8700 8800	8800 8900	8900 9000	9000 9100	9100 9200	9200 9300	9300 9400	9400 9500	9500 9600
1	31	P	3	7	13	3	P	19	3	71	7	3
3	3	11	7	3	P	29	3	P	P	3	P	13
5	5	3	5	5	3	5	5	3	5	5	3	5
7	7	47	3	P	P	3	P	7	3	41	23	3
9	3	67	P	3	23	59	3	P	P	3	97	37
11	13	3	79	31	3	7	P	3	61	P	3	P
13	47	P	3	P	7	3	P	13	3	67	P	3
15	3	5	5	3	5	5	3	5	5	3	5	5
17	19	3	7	23	3	37	71	3	13	7	3	31
19	P	7	3	P	P	3	29	11	3	P	P	3
21	3	P	37	3	P	11	3	7	P	3	P	P
23	P	3	P	11	3	P	7	3	23	P	3	89
25	5	5	3	5	5	3	5	5	3	5	5	3
27	3	P	P	3	7	79	3	P	P	3	11	7
29	P	3	P	7	3	P	P	3	11	19	3	13
31	P	19	3	P	P	3	11	23	3	7	P	3
33	3	7	89	3	11	P	3	P	7	3	P	P
35	5	3	5	5	3	5	5	3	5	5	3	5
37	11	P	3	P	P	3	7	P	3	P	P	3
39	3	P	53	3	P	7	3	13	P	3	P	P
41	23	3	P	P	3	P	P	3	P	P	3	7
43	P	P	3	7	37	3	P	41	3	P	7	3
45	3	5	5	3	5	5	3	5	5	3	5	5
47	P	3	P	P	3	23	83	3	7	13	3	P
49	7	83	3	13	P	3	P	7	3	P	11	3
51	3	17	41	3	53	P	3	P	11	3	13	P
53	79	3	17	P	3	7	11	3	19	47	3	41
55	5	5	3	5	5	3	5	5	3	5	5	3
57	3	43	11	3	17	13	3	P	P	3	7	19
59	11	3	7	19	3	17	P	3	47	7	3	11
61	P	7	3	P	P	3	13	P	3	11	P	3
63	3	P	P	3	P	P	3	7	59	3	P	73
65	5	3	5	5	3	5	5	3	5	5	3	5
67	P	13	3	11	P	3	P	89	3	17	P	3
69	3	11	P	3	7	P	3	53	13	3	17	7
71	43	3	13	7	3	P	47	3	73	P	3	17
73	37	P	3	31	19	3	43	P	3	7	P	3
75	3	5	5	3	5	5	3	5	5	3	5	5
77	7	3	P	67	3	47	29	3	P	P	3	61
79	61	23	3	P	13	3	7	67	3	83	P	3
81	3	P	P	3	83	7	3	P	P	3	19	11
83	17	3	19	P	3	13	31	3	P	11	3	7
85	5	5	3	5	5	3	5	5	3	5	5	3
87	3	31	7	3	P	11	3	P	37	3	53	P
89	13	3	P	11	3	89	61	3	7	41	3	43
91	7	11	3	59	17	3	P	7	3	P	P	3
93	3	13	P	3	P	17	3	29	P	3	11	53
95	5	3	5	5	3	5	5	3	5	5	3	5
97	29	P	3	19	7	3	11	17	3	P	P	3
99	3	P	P	3	11	P	3	P	17	3	7	29

Copyright 2004, Industrial Press, Inc., New York, NY

Prime Numbers from 9551 to 18691

9551	10181	10853	11497	12157	12763	13417	14071	14747	15361	16001	16693	17387	18043
9587	10193	10859	11503	12161	12781	13421	14081	14753	15373	16007	16699	17389	18047
9601	10211	10861	11519	12163	12791	13441	14083	14759	15377	16033	16703	17393	18049
9613	10223	10867	11527	12197	12799	13451	14087	14767	15383	16057	16729	17401	18059
9619	10243	10883	11549	12203	12809	13457	14107	14771	15391	16061	16741	17417	18061
9623	10247	10889	11551	12211	12821	13463	14143	14779	15401	16063	16747	17419	18077
9629	10253	10891	11579	12227	12823	13469	14149	14783	15413	16067	16759	17431	18089
9631	10259	10903	11587	12239	12829	13477	14153	14797	15427	16069	16763	17443	18097
9643	10267	10909	11593	12241	12841	13487	14159	14813	15439	16073	16787	17449	18119
9649	10271	10937	11597	12251	12853	13499	14173	14821	15443	16087	16811	17467	18121
9661	10273	10939	11617	12253	12889	13513	14177	14827	15451	16091	16823	17471	18127
9677	10289	10949	11621	12263	12893	13523	14197	14831	15461	16097	16829	17477	18131
9679	10301	10957	11633	12269	12899	13537	14207	14843	15467	16103	16831	17483	18133
9689	10303	10973	11657	12277	12907	13553	14221	14851	15473	16111	16843	17489	18143
9697	10313	10979	11677	12281	12911	13567	14243	14867	15493	16127	16871	17491	18149
9719	10321	10987	11681	12289	12917	13577	14249	14869	15497	16139	16879	17497	18169
9721	10331	10993	11689	12301	12919	13591	14251	14879	15511	16141	16883	17509	18181
9733	10333	11003	11699	12323	12923	13597	14281	14887	15527	16183	16889	17519	18191
9739	10337	11027	11701	12329	12941	13613	14293	14891	15541	16187	16901	17539	18199
9743	10343	11047	11717	12343	12953	13619	14303	14897	15551	16189	16903	17551	18211
9749	10357	11057	11719	12347	12959	13627	14321	14923	15559	16193	16921	17569	18217
9767	10369	11059	11731	12373	12967	13633	14323	14929	15569	16217	16927	17573	18223
9769	10391	11069	11743	12377	12973	13649	14327	14939	15581	16223	16931	17579	18229
9781	10399	11071	11777	12379	12979	13669	14341	14947	15583	16229	16937	17581	18233
9787	10427	11083	11779	12391	12983	13679	14347	14951	15601	16231	16943	17597	18251
9791	10429	11087	11783	12401	13001	13681	14369	14957	15607	16249	16963	17599	18253
9803	10433	11093	11789	12409	13003	13687	14387	14969	15619	16253	16979	17609	18257
9811	10453	11113	11801	12413	13007	13691	14389	14983	15629	16267	16981	17623	18269
9817	10457	11117	11807	12421	13009	13693	14401	15013	15641	16273	16987	17627	18287
9829	10459	11119	11813	12433	13033	13697	14407	15017	15643	16301	16993	17657	18289
9833	10463	11131	11821	12437	13037	13709	14411	15031	15647	16319	17011	17659	18301
9839	10477	11149	11827	12451	13043	13711	14419	15053	15649	16333	17021	17669	18307
9851	10487	11159	11831	12457	13049	13721	14423	15061	15661	16339	17027	17681	18311
9857	10499	11161	11833	12473	13063	13723	14431	15073	15667	16349	17029	17683	18313
9859	10501	11171	11839	12479	13093	13729	14437	15077	15671	16361	17033	17707	18329
9871	10513	11173	11863	12487	13099	13751	14447	15083	15679	16363	17041	17713	18341
9883	10529	11177	11867	12491	13103	13757	14449	15091	15683	16369	17047	17729	18353
9887	10531	11197	11887	12497	13109	13759	14461	15101	15727	16381	17053	17737	18367
9901	10559	11213	11897	12503	13121	13763	14479	15107	15731	16411	17077	17747	18371
9907	10567	11239	11903	12511	13127	13781	14489	15121	15733	16417	17093	17749	18379
9923	10589	11243	11909	12517	13147	13789	14503	15131	15737	16421	17099	17761	18397
9929	10597	11251	11923	12527	13151	13799	14519	15137	15739	16427	17107	17783	18401
9931	10601	11257	11927	12539	13159	13807	14533	15139	15749	16433	17117	17789	18413
9941	10607	11261	11933	12541	13163	13829	14537	15149	15761	16447	17123	17791	18427
9949	10613	11273	11939	12547	13171	13831	14543	15161	15767	16451	17137	17807	18433
9967	10627	11279	11941	12553	13177	13841	14549	15173	15773	16453	17159	17827	18439
9973	10631	11287	11953	12569	13183	13859	14551	15187	15787	16477	17167	17837	18443
10007	10639	11299	11959	12577	13187	13873	14557	15193	15791	16481	17183	17839	18451
10009	10651	11311	11969	12583	13217	13877	14561	15199	15797	16487	17189	17851	18457
10037	10657	11317	11971	12589	13219	13879	14563	15217	15803	16493	17191	17863	18461
10039	10663	11321	11981	12601	13229	13883	14591	15227	15809	16519	17203	17881	18481
10061	10667	11329	11987	12611	13241	13901	14593	15233	15817	16529	17207	17891	18493
10067	10687	11351	12007	12613	13249	13903	14621	15241	15823	16547	17209	17903	18503
10069	10691	11353	12011	12619	13259	13907	14627	15259	15859	16553	17231	17909	18517
10079	10709	11369	12037	12637	13267	13913	14629	15263	15877	16561	17239	17911	18521
10091	10711	11383	12041	12641	13291	13921	14633	15269	15881	16567	17257	17921	18523
10093	10723	11393	12043	12647	13297	13931	14639	15271	15887	16573	17291	17923	18539
10099	10729	11399	12049	12653	13309	13933	14653	15277	15889	16603	17293	17929	18541
10103	10733	11411	12071	12659	13313	13963	14657	15287	15901	16607	17299	17939	18553
10111	10739	11423	12073	12671	13327	13967	14669	15289	15907	16619	17317	17957	18583
10133	10753	11437	12097	12689	13331	13997	14683	15299	15913	16631	17321	17959	18587
10139	10771	11443	12101	12697	13337	13999	14699	15307	15919	16633	17327	17971	18593
10141	10781	11447	12107	12703	13339	14009	14713	15313	15923	16649	17333	17977	18617
10151	10789	11467	12109	12713	13367	14011	14717	15319	15937	16651	17341	17981	18637
10159	10799	11471	12113	12721	13381	14029	14723	15329	15959	16657	17351	17987	18661
10163	10831	11483	12119	12739	13397	14033	14731	15331	15971	16661	17359	17989	18671
10169	10837	11489	12143	12743	13399	14051	14737	15349	15973	16673	17377	18013	18679
10177	10847	11491	12149	12757	13411	14057	14741	15359	15991	16691	17383	18041	18691

Copyright 2004, Industrial Press, Inc., New York, NY

ALGEBRA AND EQUATIONS

An unknown number can be represented by a symbol or a letter which can be manipulated like an ordinary numeral within an arithmatic expression. The rules of arithmetic are also applicable in algebra.

Rearrangement and Transposition of Terms in Formulas

A formula is a rule for a calculation expressed by using letters and signs instead of writing out the rule in words; by this means, it is possible to condense, in a very small space, the essentials of long and cumbersome rules. The letters used in formulas simply stand in place of the figures that are to be substituted when solving a specific problem.

As an example, the formula for the horsepower transmitted by belting may be written

$$P = \frac{SVW}{33{,}000}$$

where P = horsepower transmitted; S = working stress of belt per inch of width in pounds; V = velocity of belt in feet per minute; and, W = width of belt in inches.

If the working stress S, the velocity V, and the width W are known, the horsepower can be found directly from this formula by inserting the given values. Assume $S = 33$; $V = 600$; and $W = 5$. Then

$$P = \frac{33 \times 600 \times 5}{33{,}000} = 3$$

Assume that the horsepower P, the stress S, and the velocity V are known, and that the width of belt, W, is to be found. The formula must then be rearranged so that the symbol W will be on one side of the equals sign and all the known quantities on the other. The rearranged formula is as follows:

$$\frac{P \times 33{,}000}{SV} = W$$

The quantities (S and V) that were in the numerator on the right side of the equals sign are moved to the denominator on the left side, and "33,000," which was in the denominator on the right side of the equals sign, is moved to the numerator on the other side. Symbols that are not part of a fraction, like "P" in the formula first given, are to be considered as being numerators (having the denominator 1).

Thus, any formula of the form $A = B/C$ can be rearranged as follows:

$$A \times C = B \qquad \text{and} \qquad C = \frac{B}{A}$$

Suppose a formula to be of the form $A = \dfrac{B \times C}{D}$

Then $$D = \frac{B \times C}{A} \qquad \frac{A \times D}{C} = B \qquad \frac{A \times D}{B} = C$$

The method given is only directly applicable when all the quantities in the numerator or denominator are standing independently or are *factors of a product*. If connected by + or – signs, the entire numerator or denominator must be moved as a unit, thus,

Given: $$\frac{B + C}{A} = \frac{D + E}{F}$$

To solve for F, rearrange in two steps as follows: $$\frac{F}{A} = \frac{D + E}{B + C} \quad \text{and} \quad F = \frac{A(D + E)}{B + C}$$

Copyright 2004, Industrial Press, Inc., New York, NY

A quantity preceded by a + or – sign can be transposed to the opposite side of the equals sign by changing its sign; if the sign is +, change it to – on the other side; if it is –, change it to +. This process is called *transposition* of terms.

Example: $B + C = A - D$ then $A = B + C + D$; $B = A - D - C$; $C = A - D - B$

Principal Algebraic Expressions and Formulas

$a \times a = aa = a^2$

$a \times a \times a = aaa = a^3$

$a \times b = ab$

$a^2 b^2 = (ab)^2$

$a^2 a^3 = a^{2+3} = a^5$

$a^4 \div a^3 = a^{4-3} = a$

$a^0 = 1$

$a^2 - b^2 = (a+b)(a-b)$

$(a+b)^2 = a^2 + 2ab + b^2$

$(a-b)^2 = a^2 - 2ab + b^2$

$ab = \left(\frac{a+b}{2}\right)^2 - \left(\frac{a-b}{2}\right)^2$

$\frac{a^3}{b^3} = \left(\frac{a}{b}\right)^3$

$\frac{1}{a^3} = \left(\frac{1}{a}\right)^3 = a^{-3}$

$(a^2)^3 = a^{2\times 3} = (a^3)^2 = a^6$

$a^3 + b^3 = (a+b)(a^2 - ab + b^2)$

$a^3 - b^3 = (a-b)(a^2 + ab + b^2)$

$(a+b)^3 = a^3 + 3a^2 b + 3ab^2 + b^3$

$(a-b)^3 = a^3 - 3a^2 b + 3ab^2 - b^3$

$a^3 + b^3 = (a+b)^3 - 3ab(a+b)$

$a^3 - b^3 = (a-b)^3 + 3ab(a-b)$

$\sqrt{a} \times \sqrt{a} = a$

$\sqrt[3]{a} \times \sqrt[3]{a} \times \sqrt[3]{a} = a$

$(\sqrt[3]{a})^3 = a$

$\sqrt[3]{a^2} = (\sqrt[3]{a})^2 = a^{2/3}$

$\sqrt[4]{\sqrt[3]{a}} = \sqrt[4\times 3]{a} = \sqrt[3]{\sqrt[4]{a}}$

$\sqrt{a} + \sqrt{b} = \sqrt{a + b + 2\sqrt{ab}}$

$\sqrt[3]{ab} = \sqrt[3]{a} \times \sqrt[3]{b}$

$\sqrt[3]{\frac{a}{b}} = \frac{\sqrt[3]{a}}{\sqrt[3]{b}}$

$\sqrt[3]{\frac{1}{a}} = \frac{1}{\sqrt[3]{a}} = a^{-1/3}$

When $a \times b = x$ then $\log a + \log b = \log x$

$a \div b = x$ then $\log a - \log b = \log x$

$a^3 = x$ then $3 \log a = \log x$

$\sqrt[3]{a} = x$ then $\frac{\log a}{3} = \log x$

Copyright 2004, Industrial Press, Inc., New York, NY

Equation Solving

An equation is a statement of equality between two expressions, as $5x = 105$. The unknown quantity in an equation is frequently designated by the letter such as x. If there is more than one unknown quantity, the others are designated by letters also usually selected from the end of the alphabet, as y, z, u, t, etc.

An equation of the first degree is one which contains the unknown quantity only in the first power, as in $3x = 9$. A quadratic equation is one which contains the unknown quantity in the second, but no higher, power, as in $x^2 + 3x = 10$.

Solving Equations of the First Degree with One Unknown.— Transpose all the terms containing the unknown x to one side of the equals sign, and all the other terms to the other side. Combine and simplify the expressions as far as possible, and divide both sides by the coefficient of the unknown x. (See the rules given for transposition of formulas.)

Example:

$$\begin{aligned} 22x - 11 &= 15x + 10 \\ 22x - 15x &= 10 + 11 \\ 7x &= 21 \\ x &= 3 \end{aligned}$$

Solution of Equations of the First Degree with Two Unknowns.— The form of the simplified equations is

$$\begin{aligned} a_1x + b_1y &= c_1 \\ a_2x + b_2y &= c_2 \end{aligned}$$

Then,

$$x = \frac{c_1b_2 - c_2b_1}{a_1b_2 - a_2b_1} \qquad y = \frac{a_1c_2 - a_2c_1}{a_1b_2 - a_2b_1}$$

Example:

$$\begin{aligned} 3x + 4y &= 17 \\ 5x - 2y &= 11 \end{aligned}$$

$$x = \frac{17 \times (-2) - 11 \times 4}{3 \times (-2) - 5 \times 4} = \frac{-34 - 44}{-6 - 20} = \frac{-78}{-26} = 3$$

The value of y can now be most easily found by inserting the value of x in one of the equations:

$$5 \times 3 - 2y = 11 \qquad 2y = 15 - 11 = 4 \qquad y = 2$$

Solution of Quadratic Equations with One Unknown.— If the form of the equation is $ax^2 + bx + c = 0$, then

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

Example: Given the equation, $1x^2 + 6x + 5 = 0$, then $a = 1$, $b = 6$, and $c = 5$.

$$x = \frac{-6 \pm \sqrt{6^2 - 4 \times 1 \times 5}}{2 \times 1} = \frac{(-6) + 4}{2} = -1 \quad \text{or} \quad \frac{(-6) - 4}{2} = -5$$

If the form of the equation is $ax^2 + bx = c$, then

$$x = \frac{-b \pm \sqrt{b^2 + 4ac}}{2a}$$

Example: A right-angle triangle has a hypotenuse 5 inches long and one side which is one inch longer than the other; find the lengths of the two sides.

Copyright 2004, Industrial Press, Inc., New York, NY

Let x = one side and $x + 1$ = other side; then $x^2 + (x + 1)^2 = 5^2$ or $x^2 + x^2 + 2x + 1 = 25$; or $2x^2 + 2x = 24$; or $x^2 + x = 12$. Now referring to the basic formula, $ax^2 + bx = c$, we find that $a = 1$, $b = 1$, and $c = 12$; hence,

$$x = \frac{-1 \pm \sqrt{1 + 4 \times 1 \times 12}}{2 \times 1} = \frac{(-1) + 7}{2} = 3 \quad \text{or} \quad x = \frac{(-1) - 7}{2} = -4$$

Since the positive value (3) would apply in this case, the lengths of the two sides are $x = 3$ inches and $x + 1 = 4$ inches.

Factoring a Quadratic Expression.— The method described below is useful in determining factors of the quadratic equation in the form $ax^2 + bx + c = 0$. First, obtain the product ac from the coefficients a and c, and then determine two numbers, f_1 and f_2, such that $f_1 \times f_2 = |ac|$, and $f_1 + f_2 = b$ if ac is positive, or $f_1 - f_2 = b$ if ac is negative.

The numbers f_1 and f_2 are used to modify or rearrange the bx term to simplify factoring the quadratic expression. The roots of the quadratic equation can be easily obtained from the factors.

Example: Factor $8x^2 + 22x + 5 = 0$ and find the values of x that satisfy the equation.

Solution: In this example, $a = 8$, $b = 22$, and c=5. Therefore, $ac = 8 \times 5 = 40$, and ac is positive, so we are looking for two factors of ac, f_1 and f_2, such that $f_1 \times f_2 = 40$, and $f_1 + f_2 = 22$.

The ac term can be written as $2 \times 2 \times 2 \times 5 = 40$, and the possible combination of numbers for f_1 and f_2 are (20 and 2), (8 and 5), (4 and 10) and (40 and 1). The requirements for f_1 and f_2 are satisfied by f_1=20 and $f_2 = 2$, i.e., $20 \times 2 = 40$ and $20 + 2 = 22$. Using f_1 and f_2, the original quadratic expression is rewritten and factored as follows:

$$\begin{aligned} 8x^2 + 22x + 5 &= 0 \\ 8x^2 + 20x + 2x + 5 &= 0 \\ 4x(2x + 5) + 1(2x + 5) &= 0 \\ (2x + 5)(4x + 1) &= 0 \end{aligned}$$

If the product of the two factors equals zero, then each of the factors equals zero, thus, $2x + 5 = 0$ and $4x + 1 = 0$. Rearranging and solving, $x = -\frac{5}{2}$ and $x = -\frac{1}{4}$.

Example: Factor $8x^2 + 3x - 5 = 0$ and find the solutions for x.

Solution: Here $a = 8, b = 3$, $c = -5$, and $ac = 8 \times (-5) = -40$. Because ac is negative, the required numbers, f_1 and f_2, must satisfy $f_1 \times f_2 = |ac| = 40$ and $f_1 - f_2 = 3$.

As in the previous example, the possible combinations for f_1 and f_2 are (20 and 2), (8 and 5), (4 and 10) and (40 and 1). The numbers $f_1 = 8$ and $f_2 = 5$ satisy the requirements because $8 \times 5 = 40$ and $8 - 5 = 3$. In the second line below, $5x$ is both added to and subtrtacted from the original equation, making it possible to rearrange and simplify the expression.

$$\begin{aligned} 8x^2 + 3x - 5 &= 0 \\ 8x^2 + 8x - 5x - 5 &= 0 \\ 8x(x + 1) - 5(x + 1) &= 0 \\ (x + 1)(8x - 5) &= 0 \end{aligned}$$

Solving, for $x + 1 = 0$, $x = -1$; and, for $8x - 5 = 0$, $x = \frac{5}{8}$.

Copyright 2004, Industrial Press, Inc., New York, NY

Cubic Equations.— If the given equation has the form: $x^3 + ax + b = 0$ then

$$x = \left(-\frac{b}{2} + \sqrt{\frac{a^3}{27} + \frac{b^2}{4}}\right)^{1/3} + \left(-\frac{b}{2} - \sqrt{\frac{a^3}{27} + \frac{b^2}{4}}\right)^{1/3}$$

The equation $x^3 + px^2 + qx + r = 0$, may be reduced to the form ${x_1}^3 + ax_1 + b = 0$ by substituting $x_1 - \frac{p}{3}$ for x in the given equation.

Solving Numerical Equations Having One Unknown.— The Newton-Raphson method is a procedure for solving various kinds of numerical algebraic and transcendental equations in one unknown. The steps in the procedure are simple and can be used with either a handheld calculator or as a subroutine in a computer program.

Examples of types of equations that can be solved to any desired degree of accuracy by this method are

$$f(x) = x^2 - 101 = 0, \quad f(x) = x^3 - 2x^2 - 5 = 0$$
$$\text{and} \quad f(x) = 2.9x - \cos x - 1 = 0$$

The procedure begins with an estimate, r_1, of the root satisfying the given equation. This estimate is obtained by judgment, inspection, or plotting a rough graph of the equation and observing the value r_1 where the curve crosses the x axis. This value is then used to calculate values $r_2, r_3, \ldots, r_n$ progressively closer to the exact value.

Before continuing, it is necessary to calculate the first derivative, $f'(x)$, of the function. In the above examples, $f'(x)$ is, respectively, $2x$, $3x^2 - 4x$, and $2.9 + \sin x$. These values were found by the methods described in *Derivatives and Integrals of Functions* on page 34.

In the steps that follow,
r_1 is the first estimate of the value of the root of $f(x) = 0$;
$f(r_1)$ is the value of $f(x)$ for $x = r_1$;
$f'(x)$ is the first derivative of $f(x)$;
$f'(r_1)$ is the value of $f'(x)$ for $x = r_1$.

The second approximation of the root of $f(x) = 0$, r_2, is calculated from

$$r_2 = r_1 - [f(r_1)/f'(r_1)]$$

and, to continue further approximations,

$$r_n = r_{n-1} - [f(r_{n-1})/f'(r_{n-1})]$$

Example: Find the square root of 101 using the Newton-Raphson method. This problem can be restated as an equation to be solved, i.e., $f(x) = x^2 - 101 = 0$

Step 1. By inspection, it is evident that $r_1 = 10$ may be taken as the first approximation of the root of this equation. Then, $f(r_1) = f(10) = 10^2 - 101 = -1$

Step 2. The first derivative, $f'(x)$, of $x^2 - 101$ is $2x$ as stated previously, so that

$$f'(10) = 2(10) = 20.$$

Then, $$r_2 = r_1 - f(r_1)/f'(r_1) = 10 - (-1)/20 = 10 + 0.05 = 10.05$$

Check: $10.05^2 = 101.0025$; error $= 0.0025$

Step 3. The next, better approximation is

$$r_3 = r_2 - [f(r_2)/f'(r_2)] = 10.05 - [f(10.05)/f'(10.05)]$$
$$= 10.05 - [(10.05^2 - 101)/2(10.05)] = 10.049875$$

Check: $10.049875^2 = 100.9999875$; error $= 0.0000125$

Copyright 2004, Industrial Press, Inc., New York, NY

Series.— Some hand calculations, as well as computer programs of certain types of mathematical problems, may be facilitated by the use of an appropriate series. For example, in some gear problems, the angle corresponding to a given or calculated involute function is found by using a series together with an iterative procedure such as the Newton-Raphson method described on page 33. The following are those series most commonly used for such purposes. In the series for trigonometric functions, the angles x are in radians (1 radian = 180/π degrees). The expression $\exp(-x^2)$ means that the base e of the natural logarithm system is raised to the $-x^2$ power; $e = 2.7182818$.

(1) $\sin x = x - x^3/3! + x^5/5! - x^7/7! + \cdots$ for all values of x.

(2) $\cos x = 1 - x^2/2! + x^4/4! - x^6/6! + \cdots$ for all values of x.

(3) $\tan x = x + x^3/3 + 2x^5/15 + 17x^7/315 + 62x^9/2835 + \cdots$ for $|x| < \pi/2$.

(4) $\arcsin x = x + x^3/6 + 1 \cdot 3 \cdot x^5/(2 \cdot 4 \cdot 5) + 1 \cdot 3 \cdot 5 \cdot x^7/(2 \cdot 4 \cdot 6 \cdot 7) + \cdots$ for $|x| \leq 1$.

(5) $\arccos x = \pi/2 - \arcsin x$

(6) $\arctan x = x - x^3/3 + x^5/5 - x^7/7 + \cdots$ for $|x| \leq 1$.

(7) $\pi/4 = 1 - 1/3 + 1/5 - 1/7 + 1/9 \cdots \pm 1/(2x-1) \mp \cdots$ for all values of x.

(8) $e = 1 + 1/1! + 2/2! + 1/3! + \cdots$ for all values of x.

(9) $e^x = 1 + x + x^2/2! + x^3/3! + \cdots$ for all values of x.

(10) $\exp(-x^2) = 1 - x^2 + x^4/2! - x^6/3! + \cdots$ for all values of x.

(11) $a^x = 1 + x \log_e a + (x \log_e a)^2/2! + (x \log_e a)^3/3! + \cdots$ for all values of x.

(12) $1/(1+x) = 1 - x + x^2 - x^3 + x^4 - \cdots$ for $|x| < 1$.

(13) $1/(1-x) = 1 + x + x^2 + x^3 + x^4 + \cdots$ for $|x| < 1$.

(14) $1/(1+x)^2 = 1 - 2x + 3x^2 - 4x^3 + 5x^4 - \cdots$ for $|x| < 1$.

(15) $1/(1-x)^2 = 1 + 2x + 3x^2 + 4x^3 + 5x^5 + \cdots$ for $|x| < 1$.

(16) $\sqrt{(1+x)} = 1 + x/2 - x^2/(2 \cdot 4) + 1 \cdot 3 \cdot x^3/(2 \cdot 4 \cdot 6) - 1 \cdot 3 \cdot 5 \cdot x^4/(2 \cdot 4 \cdot 6 \cdot 8) - \cdots$ for $|x| < 1$.

(17) $1/(\sqrt{1+x}) = 1 - x/2 + 1 \cdot 3 \cdot x^2/(2 \cdot 4) - 1 \cdot 3 \cdot 5 \cdot x^3/(2 \cdot 4 \cdot 6) + \cdots$ for $|x| < 1$.

(18) $(a+x)^n = a^n + na^{n-1}x + n(n-1)a^{n-2}x^2/2! + n(n-1)(n-2)a^{n-3}x^3/3! + \cdots$ for $x^2 < a^2$.

Derivatives and Integrals of Functions.— The following are formulas for obtaining the derivatives and integrals of basic mathematical functions. In these formulas, the letters a and c denotes constants; the letter x denotes a variable; and the letters u and v denote functions of the variable x. The expression d/dx means the derivative with respect to x, and as such applies to whatever expression in parentheses follows it. Thus, $d/dx\,(ax)$ means the derivative with respect to x of the product (ax) of the constant a and the variable x.

Formulas for Differential and Integral Calculus

Derivative	Value	Integral	Value
$\frac{d}{dx}(c)$	0	$\int c\,dx$	cx
$\frac{d}{dx}(x)$	1	$\int 1\,dx$	x
$\frac{d}{dx}(x^n)$	nx^{n-1}	$\int x^n dx$	$\frac{x^{n+1}}{n+1}$
$\frac{d}{dx}(g(u))$	$\frac{d}{du}g(u)\frac{du}{dx}$	$\int \frac{dx}{ax+b}$	$\frac{1}{a}\log\lvert ax+b\rvert$
$\frac{d}{dx}(u(x)+v(x))$	$\frac{d}{dx}u(x)+\frac{d}{dx}v(x)$	$\int(u(x)\pm v(x))dx$	$\int u(x)dx \pm \int v(x)dx$
$\frac{d}{dx}(u(x)\times v(x))$	$u(x)\frac{d}{dx}v(x)+v(x)\frac{d}{dx}u(x)$	$\int u(x)v(x)dx$	$u(x)v(x)-\int v(x)du(x)$

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Differential and Integral Calculus *(Continued)*

Derivative	Value	Integral	Value
$\frac{d}{dx}\left(\frac{u(x)}{v(x)}\right)$	$\frac{v(x)\frac{d}{dx}u(x) - u(x)\frac{d}{dx}v(x)}{v(x)^2}$	$\int\frac{dx}{\sqrt{x}}$	$2\sqrt{x}$
$\frac{d}{dx}(\sin x)$	$\cos x$	$\int\cos x dx$	$\sin x$
$\frac{d}{dx}(\cos x)$	$-\sin x$	$\int\sin x dx$	$-\cos x$
$\frac{d}{dx}(\tan x)$	$\sec^2 x$	$\int\tan x dx$	$-\log\cos x$
$\frac{d}{dx}(\cot x)$	$-\mathrm{cosec}^2 x$	$\int\cot x dx$	$\log\sin x$
$\frac{d}{dx}(\sec x)$	$\sec x\tan x$	$\int\sin^2 x dx$	$\left(-\frac{1}{4}\right)\sin(2x) + \frac{1}{2}x$
$\frac{d}{dx}(\csc x)$	$-\csc x\cot x$	$\int\cos^2 x dx$	$\frac{1}{4}\sin(2x) + \frac{1}{2}x$
$\frac{d}{dx}(e^x)$	e^x	$\int e^x dx$	e^x
$\frac{d}{dx}(\log x)$	$\frac{1}{x}$	$\int\frac{1}{x}dx$	$\log x$
$\frac{d}{dx}(a^x)$	$a^x\log a$	$\int a^x dx$	$\frac{a^x}{\log a}$
$\frac{d}{dx}(\mathrm{asin}\,x)$	$\frac{1}{\sqrt{1-x^2}}$	$\int\frac{dx}{\sqrt{b^2-x^2}}$	$\mathrm{asin}\frac{x}{b}$
$\frac{d}{dx}(\mathrm{acos}\,x)$	$\frac{-1}{\sqrt{1-x^2}}$	$\int\frac{dx}{\sqrt{x^2-b^2}}$	$\mathrm{acosh}\frac{x}{b} = \log(x + \sqrt{x^2-b^2})$
$\frac{d}{dx}(\mathrm{atan}\,x)$	$\frac{1}{1+x^2}$	$\int\frac{dx}{b^2+x^2}$	$\frac{1}{b}\mathrm{atan}\frac{x}{b}$
$\frac{d}{dx}(\mathrm{acot}\,x)$	$\frac{-1}{1+x^2}$	$\int\frac{dx}{b^2-x^2}$	$\frac{1}{b}\mathrm{atanh}\frac{x}{b} = \frac{-1}{2b}\log\frac{(\lvert x-b\rvert)}{(\lvert x+b\rvert)}$
$\frac{d}{dx}(\mathrm{asec}\,x)$	$\frac{1}{x\sqrt{x^2-1}}$	$\int\frac{dx}{x^2-b^2}$	$-\frac{1}{b}\mathrm{acoth}\frac{x}{b} = \frac{1}{2b}\log\frac{(\lvert x-b\rvert)}{(\lvert x+b\rvert)}$
$\frac{d}{dx}(\mathrm{acsc}\,x)$	$\frac{-1}{x\sqrt{x^2-1}}$	$\int\frac{dx}{ax^2+bx+c}$	$\frac{2}{\sqrt{4ac-b^2}}\mathrm{atan}\frac{(2ax+b)}{\sqrt{4ac-b^2}}$
$\frac{d}{dx}(\log\sin x)$	$\cot x$	$\int e^{ax}\sin bx dx$	$\frac{(\mathrm{asin}\,bx - b\cos bx)}{a^2+b^2}e^{ax}$
$\frac{d}{dx}(\log\cos x)$	$-\tan x$	$\int e^{ax}\cos(bx)dx$	$\frac{(\mathrm{acos}(bx) + b\sin(bx))}{a^2+b^2}e^{ax}$
$\frac{d}{dx}(\log\tan x)$	$\frac{2}{\sin 2x}$	$\int\frac{1}{\sin x}dx$	$\log\tan\frac{x}{2}$
$\frac{d}{dx}(\log\cot x)$	$\frac{-2}{\sin 2x}$	$\int\frac{1}{\cos x}dx$	$\log\tan\left(\frac{\pi}{4}+\frac{x}{2}\right)$
$\frac{d}{dx}(\sqrt{x})$	$\frac{1}{2\sqrt{x}}$	$\int\frac{1}{1+\cos x}dx$	$\tan\frac{x}{2}$
$\frac{d}{dx}(\log_{10}x)$	$\frac{\log_{10}e}{x}$	$\int\log x dx$	$x\log x - x$

Copyright 2004, Industrial Press, Inc., New York, NY

GEOMETRY

Arithmetical Progression

An arithmetical progression is a series of numbers in which each consecutive term differs from the preceding one by a fixed amount called the *common difference*, *d*. Thus, 1, 3, 5, 7, etc., is an arithmetical progression where the difference *d* is 2. The difference here is *added* to the preceding term, and the progression is called increasing. In the series 13, 10, 7, 4, etc., the difference is (−3), and the progression is called decreasing. In any arithmetical progression (or part of progression), let

a = first term considered
l = last term considered
n = number of terms
d = common difference
S = sum of n terms

Then the general formulas are $l = a + (n-1)d$ and $S = \frac{a+l}{2} \times n$

In these formulas, *d* is positive in an increasing and negative in a decreasing progression. When any three of the preceding live quantities are given, the other two can be found by the formulas in the accompanying table of arithmetical progression.

Example: In an arithmetical progression, the first term equals 5, and the last term 40. The difference is 7. Find the sum of the progression.

$$S = \frac{a+l}{2d}(l+d-a) = \frac{5+40}{2\times 7}(40+7-5) = 135$$

Geometrical Progression

A geometrical progression or a geometrical series is a series in which each term is derived by multiplying the preceding term by a constant multiplier called the *ratio*. When the ratio is greater than 1, the progression is increasing; when less than 1, it is decreasing. Thus, 2, 6, 18, 54, etc., is an increasing geometrical progression with a ratio of 3, and 24, 12, 6, etc., is a decreasing progression with a ratio of 1⁄2.

In any geometrical progression (or part of progression), let

a = first term
l = last (or nth) term
n = number of terms
r = ratio of the progression
S = sum of n terms

Then the general formulas are $l = ar^{n-1}$ and $S = \frac{rl-a}{r-1}$

When any three of the preceding five quantities are given, the other two can be found by the formulas in the accompanying table. For instance, geometrical progressions are used for finding the successive speeds in machine tool drives, and in interest calculations.

Example: The lowest speed of a lathe is 20 rpm. The highest speed is 225 rpm. There are 18 speeds. Find the ratio between successive speeds.

$$\text{Ratio } r = \sqrt[n-1]{\frac{l}{a}} = \sqrt[17]{\frac{225}{20}} = \sqrt[17]{11.25} = 1.153$$

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Arithmetical Progression

To Find	Given			Use Equation
a	d	l	n	$a = l-(n-1)d$
	d	n	S	$a = \frac{S}{n}-\frac{n-1}{2}\times d$
	d	l	S	$a = \frac{d}{2}\pm\frac{1}{2}\sqrt{(2l+d)^2-8dS}$
	l	n	S	$a = \frac{2S}{n}-l$
d	a	l	n	$d = \frac{l-a}{n-1}$
	a	n	S	$d = \frac{2S-2an}{n(n-1)}$
	a	l	S	$d = \frac{l^2-a^2}{2S-l-a}$
	l	n	S	$d = \frac{2nl-2S}{n(n-1)}$
l	a	d	n	$l = a+(n-1)d$
	a	d	S	$l = -\frac{d}{2}\pm\frac{1}{2}\sqrt{8dS+(2a-d)^2}$
	a	n	S	$l = \frac{2S}{n}-a$
	d	n	S	$l = \frac{S}{n}+\frac{n-1}{2}\times d$
n	a	d	l	$n = 1+\frac{l-a}{d}$
	a	d	S	$n = \frac{d-2a}{2d}\pm\frac{1}{2d}\sqrt{8dS+(2a-d)^2}$
	a	l	S	$n = \frac{2S}{a+l}$
	d	l	S	$n = \frac{2l+d}{2d}\pm\frac{1}{2d}\sqrt{(2l+d)^2-8dS}$
S	a	d	n	$S = \frac{n}{2}[2a+(n-1)d]$
	a	d	l	$S = \frac{a+l}{2}+\frac{l^2-a^2}{2d} = \frac{a+l}{2d}(l+d-a)$
	a	l	n	$S = \frac{n}{2}(a+l)$
	d	l	n	$S = \frac{n}{2}[2l-(n-1)d]$

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Geometrical Progression

To Find	Given			Use Equation
a	l	n	r	$a = \frac{l}{r^{n-1}}$
	n	r	S	$a = \frac{(r-1)S}{r^n - 1}$
	l	r	S	$a = lr - (r-1)S$
	l	n	S	$a(S-a)^{n-1} = l(S-l)^{n-1}$
l	a	n	r	$l = ar^{n-1}$
	a	r	S	$l = \frac{1}{r}[a + (r-1)S]$
	a	n	S	$l(S-l)^{n-1} = a(S-a)^{n-1}$
	n	r	S	$l = \frac{S(r-1)r^{n-1}}{r^n - 1}$
n	a	l	r	$n = \frac{\log l - \log a}{\log r} + 1$
	a	r	S	$n = \frac{\log[a + (r-1)S] - \log a}{\log r}$
	a	l	S	$n = \frac{\log l - \log a}{\log(S-a) - \log(S-l)} + 1$
	l	r	S	$n = \frac{\log l - \log[lr - (r-1)S]}{\log r} + 1$
r	a	l	n	$r = \sqrt[n-1]{\frac{l}{a}}$
	a	n	S	$r^n = \frac{Sr}{a} + \frac{a-S}{a}$
	a	l	S	$r = \frac{S-a}{S-l}$
	l	n	S	$r^n = \frac{Sr^{n-1}}{S-l} - \frac{l}{S-l}$
S	a	n	r	$S = \frac{a(r^n - 1)}{r-1}$
	a	l	r	$S = \frac{lr-a}{r-1}$
	a	l	n	$S = \frac{\sqrt[n-1]{l^n} - \sqrt[n-1]{a^n}}{\sqrt[n-1]{l} - \sqrt[n-1]{a}}$
	l	n	r	$S = \frac{l(r^n - 1)}{(r-1)r^{n-1}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Analytical Geometry

Straight Line.— A straight line is a line between two points with the minimum distance.

Coordinate System: It is possible to locate any point on a plane by a pair of numbers called the coordinates of the point. If P is a point on a plane, and perpendiculars are drawn from P to the coordinate axes, one perpendicular meets the X–axis at the x– coordinate of P and the other meets the Y–axis at the y–coordinate of P. The pair of numbers (x_1, y_1), in that order, is called the coordinates or coordinate pair for P.



Fig. 1. Coordinate Plan

Distance Between Two Points: The distance d between two points $P_1(x_1,y_1)$ and $P_2(x_2,y_2)$ is given by the formula:

$$d(P_1,P_2) = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$

Example 1: What is the distance AB between points A(4,5) and B(7,8)?

Solution: The length of line *AB* is

$$d = \sqrt{(7-4)^2 + (8-5)^2} = \sqrt{3^2 + 3^2} = \sqrt{18} = 3\sqrt{2}$$

Intermediate Point: An intermediate point, $P(x,y)$ on a line between two points, $P_1(x_1,y_1)$ and $P_2(x_2,y_2)$, Fig. 2, can be obtained by linear interpolation as follows,

$$x = \frac{r_1 x_1 + r_2 x_2}{r_1 + r_2} \qquad \text{and} \qquad y = \frac{r_1 y_1 + r_2 y_2}{r_1 + r_2}$$

where r_1 is the ratio of the distance of P_1 to P to the distance of P_1 to P_2, and r_2 is the ratio of the distance of P_2 to P to the distance of P_1 to P_2. If the desired point is the midpoint of line P_1P_2, then $r_1 = r_2 = 1$, and the coordinates of P are:

$$x = \frac{x_1 + x_2}{2} \qquad \text{and} \qquad y = \frac{y_1 + y_2}{2}$$

Example 2: What is the coordinate of point $P(x,y)$, if P divides the line defined by points A(0,0) and B(8,6) at the ratio of 5:3.

Solution: $x = \dfrac{5 \times 0 + 3 \times 8}{5 + 3} = \dfrac{24}{8} = 3$ $\qquad y = \dfrac{5 \times 0 + 3 \times 6}{5 + 3} = \dfrac{18}{8} = 2.25$

Copyright 2004, Industrial Press, Inc., New York, NY

External Point: A point, Q(x,y) on the line P_1P_2, and beyond the two points, $P_1(x_1,y_1)$ and $P_2(x_2,y_2)$, can be obtained by external interpolation as follows,

$$x = \frac{r_1x_1 - r_2x_2}{r_1 - r_2} \qquad \text{and} \qquad y = \frac{r_1y_1 - r_2y_2}{r_1 - r_2}$$

where r_1 is the ratio of the distance of P_1 to Q to the distance of P_1 to P_2, and r_2 is the ratio of the distance of P_2 to Q to the distance of P_1 to P_2.



Fig. 2. Finding Intermediate and External Points on a Line

Equation of a line P_1P_2: The general equation of a line passing through points $P_1(x_1,y_1)$ and $P_2(x_2,y_2)$ is $\frac{y - y_1}{y_1 - y_2} = \frac{x - x_1}{x_1 - x_2}$.

The previous equation is frequently written in the form $y - y_1 = \frac{y_1 - y_2}{x_1 - x_2}(x - x_1)$

where $\frac{y_1 - y_2}{x_1 - x_2}$ is the slope of the line, m, and thus becomes $y - y_1 = m(x - x_1)$ where y_1 is the coordinate of the y-intercept $(0, y_1)$ and x_1 is the coordinate of the x-intercept $(x_1, 0)$. If the line passes through point (0,0), then $x_1 = y_1 = 0$ and the equation becomes $y = mx$. The y-intercept is the y-coordinate of the point at which a line intersects the Y-axis at $x = 0$. The x-intercept is the x-coordinate of the point at which a line intersects the X-axis at $y = 0$.

If a line AB intersects the X–axis at point A$(a,0)$ and the Y–axis at point B$(0,b)$ then the equation of line AB is

$$\frac{x}{a} + \frac{y}{b} = 1$$

Slope: The equation of a line in a Cartesian coordinate system is $y = mx + b$, where x and y are coordinates of a point on a line, m is the slope of the line, and b is the y-intercept. The slope is the rate at which the x coordinates are increasing or decreasing relative to the y coordinates.

Another form of the equation of a line is the point-slope form $(y - y_1) = m(x - x_1)$. The slope, m, is defined as a ratio of the change in the y coordinates, $y_2 - y_1$, to the change in the x coordinates, $x_2 - x_1$,

$$m = \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Example 3: What is the equation of a line AB between points A(4,5) and B(7,8)?

Solution:

$$\frac{y-y_1}{y_1-y_2} = \frac{x-x_1}{x_1-x_2}$$

$$\frac{y-5}{5-8} = \frac{x-4}{4-7}$$

$$y-5 = x-4$$

$$y-x = 1$$

Example 4: Find the general equation of a line passing through the points (3,2) and (5,6), and its intersection point with the *y*-axis.

First, find the slope using the equation above

$$m = \frac{\Delta y}{\Delta x} = \frac{6-2}{5-3} = \frac{4}{2} = 2$$

The line has a general form of $y = 2x + b$, and the value of the constant b can be determined by substituting the coordinates of a point on the line into the general form. Using point (3,2), $2 = 2 \times 3 + b$ and rearranging, $b = 2 - 6 = -4$. As a check, using another point on the line, (5,6), yields equivalent results, $y = 6 = 2 \times 5 + b$ and $b = 6 - 10 = -4$.

The equation of the line, therefore, is $y = 2x - 4$, indicating that line $y = 2x - 4$ intersects the *y*-axis at point (0,–4), the *y*-intercept.

Example 5: Use the point-slope form to find the equation of the line passing through the point (3,2) and having a slope of 2.

$$(y-2) = 2(x-3)$$

$$y = 2x - 6 + 2$$

$$y = 2x - 4$$

The slope of this line is positive and crosses the *y*-axis at the *y*-intercept, point (0,–4).

Parallel Lines: The two lines, P_1P_2 and Q_1Q_2, are parallel if both lines have the same slope, that is, if $m_1 = m_2$.



Fig. 3. Parallel Lines



Fig. 4. Perpendicular Lines

Perpendicular Lines: The two lines P_1P_2 and Q_1Q_2 are perpendicular if the product of their slopes equal –1, that is, $m_1m_2 = -1$.

Example 6: Find an equation of a line that passes through the point (3,4) and is (a) parallel to and (b) perpendicular to the line $2x - 3y = 16$?

Solution (a): Line $2x - 3y = 16$ in standard form is $y = \frac{2}{3}x - \frac{16}{3}$, and the equation of a line passing through (3,4) is $y - 4 = m(x - 3)$.

Copyright 2004, Industrial Press, Inc., New York, NY

If the lines are parallel, their slopes are equal. Thus, $y - 4 = \frac{2}{3}(x - 3)$ is parallel to line $2x - 3y = -6$ and passes through point (3,4).

Solution (b): As illustrated in part (*a*), line $2x - 3y = -6$ has a slope of $\frac{2}{3}$. The product of the slopes of perpendicular lines = −1, thus the slope *m* of a line passing through point (4,3) and perpendicular to $2x - 3y = -6$ must satisfy the following:

$$m = \frac{-1}{m_1} = \frac{-1}{\frac{2}{3}} = -\frac{3}{2}$$

The equation of a line passing through point (4,3) and perpendicular to the line $2x - 3y = 16$ is $y - 4 = -\frac{3}{2}(x - 3)$, which rewritten is $3x + 2y = 17$.

Angle Between Two Lines: For two non-perpendicular lines with slopes m_1 and m_2, the angle between the two lines is given by

$$\tan\theta = \left|\frac{m_1 - m_2}{1 + m_1 m_2}\right|$$

Note: The straight brackets surrounding a symbol or number, as in $|x|$, stands for absolute value and means use the positive value of the bracketed quantity, irrespective of its sign.

Example 7: Find the angle between the following two lines: $2x - y = 4$ and $3x + 4y = 12$

Solution: The slopes are 2 and $-\frac{3}{4}$, respectively. The angle between two lines is given by

$$\tan\theta = \left|\frac{m_1 - m_2}{1 + m_1 m_2}\right| = \left|\frac{2 - \left(-\frac{3}{4}\right)}{1 + 2\left(-\frac{3}{4}\right)}\right| = \left|\frac{2 + \frac{3}{4}}{1 - \frac{6}{4}}\right| = \left|\frac{\frac{8+3}{4}}{\frac{4-6}{4}}\right| = \left|\frac{11}{-2}\right| = \frac{11}{2}$$

$$\theta = \operatorname{atan}\frac{11}{2} = 79.70°$$

Distance Between a Point and a Line: The distance between a point (x_1, y_1) and a line given by $Ax + By + C = 0$ is

$$d = \frac{|Ax_1 + By_1 + C|}{\sqrt{A^2 + B^2}}$$

Example 8: Find the distance between the point (4,6) and the line $2x + 3y - 9 = 0$.

Solution: The distance between a point and the line is

$$d = \frac{|Ax_1 + By_1 + C|}{\sqrt{A^2 + B^2}} = \frac{|2 \times 4 + 3 \times 6 - 9|}{\sqrt{2^2 + 3^2}} = \frac{|8 + 18 - 9|}{\sqrt{4 + 9}} = \frac{17}{\sqrt{13}}$$

Coordinate Systems.— *Rectangular, Cartesian Coordinates:* In a Cartesian coordinate system the coordinate axes are perpendicular to one another, and the same unit of length is chosen on the two axes. This rectangular coordinate system is used in the majority of cases.

Polar Coordinates: Another coordinate system is determined by a fixed point O, the origin or pole, and a zero direction or axis through it, on which positive lengths can be laid off and measured, as a number line. A point P can be fixed to the zero direction line at a distance *r* away and then rotated in a positive sense at an angle θ. The angle, θ, in polar coordinates can take on values from 0° to 360°. A point in polar coordinates takes the form of (r, θ).

Copyright 2004, Industrial Press, Inc., New York, NY

Changing Coordinate Systems: For simplicity it may be assumed that the origin on a Cartesian coordinate system coincides with the pole on a polar coordinate system, and it's axis with the x-axis. Then, if point P has polar coordinates of (r,θ) and Cartesian coordinates of (x, y), by trigonometry $x = r \times \cos(\theta)$ and $y = r \times \sin(\theta)$. By the Pythagorean theorem and trigonometry

$$r = \sqrt{x^2 + y^2} \qquad \theta = \operatorname{atan}\frac{y}{x}$$

Example 1: Convert the Cartesian coordinate (3, 2) into polar coordinates.

$$r = \sqrt{3^2 + 2^2} = \sqrt{9 + 4} = \sqrt{13} = 3.6 \qquad \theta = \operatorname{atan}\frac{2}{3} = 33.69°$$

Therefore the point (3.6, 33.69) is the polar form of the Cartesian point (3, 2).

Graphically, the polar and Cartesian coordinates are related in the following figure



Example 2: Convert the polar form (5, 608) to Cartesian coordinates. By trigonometry, $x = r \times \cos(\theta)$ and $y = r \times \sin(\theta)$. Then $x = 5\cos(608) = -1.873$ and $y = 5\sin(608) = -4.636$. Therefore, the Cartesian point equivalent is (−1.873, −4.636).

Spherical Coordinates: It is convenient in certain problems, for example, those concerned with spherical surfaces, to introduce non-parallel coordinates. An arbitrary point P in space can be expressed in terms of the distance r between point P and the origin O, the angle ϕ that OP' makes with the x–y plane, and the angle λ that the projection OP' (of the segment OP onto the x–y plane) makes with the positive x-axis.



The rectangular coordinates of a point in space can therefore be calculated by the formulas in the following table.

Copyright 2004, Industrial Press, Inc., New York, NY

Relationship Between Spherical and Rectangular Coordinates

Spherical to Rectangular	Rectangular to Spherical
$x = r\cos\phi\cos\lambda$ $y = r\cos\phi\sin\lambda$ $z = r\sin\phi$	$r = \sqrt{x^2 + y^2 + z^2}$ $\phi = \operatorname{atan}\dfrac{z}{\sqrt{x^2 + y^2}}$ (for $x^2 + y^2 \neq 0$) $\lambda = \operatorname{atan}\dfrac{y}{x}$ (for $x > 0, y > 0$) $\lambda = \pi + \operatorname{atan}\dfrac{y}{x}$ (for $x < 0$) $\lambda = 2\pi + \operatorname{atan}\dfrac{y}{x}$ (for $x > 0$, y < 0)

Example 3: What are the spherical coordinates of the point $P(3, -4, -12)$?

$$r = \sqrt{3^2 + (-4)^2 + (-12)^2} = 13$$

$$\phi = \operatorname{atan}\frac{-12}{\sqrt{3^2 + (-4)^2}} = \operatorname{atan}-\frac{12}{5} = -67.38°$$

$$\lambda = 360° + \operatorname{atan}-\frac{4}{3} = 360° - 53.13° = 306.87°$$

The spherical coordinates of P are therefore $r = 13$, $\phi = -67.38°$, and $\lambda = 306.87°$.

Cylindrical Coordinates: For problems on the surface of a cylinder it is convenient to use cylindrical coordinates. The cylindrical coordinates r, θ, z, of P coincide with the polar coordinates of the point P′ in the x-y plane and the rectangular z-coordinate of P. This gives the conversion formula. Those for θ hold only if $x^2 + y^2 \neq 0$; θ is undetermined if $x = y = 0$.

Cylindrical to Rectangular	Rectangular to Cylindrical
$x = r\cos\theta$ $y = r\sin\theta$ $z = z$	$r = \dfrac{1}{\sqrt{x^2 + y^2}}$ $\cos\theta = \dfrac{x}{\sqrt{x^2 + y^2}}$ $\sin\theta = \dfrac{y}{\sqrt{x^2 + y^2}}$ $z = z$



Example 4: Given the cylindrical coordinates of a point P, $r = 3$, $\theta = -30°$, $z = 51$, find the rectangular coordinates. Using the above formulas $x = 3\cos(-30°) = 3\cos(30°) = 2.598$; $y = 3\sin(-30°) = -3\sin(30°) = -1.5$; and $z = 51$. Therefore, the rectangular coordinates of point P are $x = 2.598$, $y = -1.5$, and $z = 51$.

Copyright 2004, Industrial Press, Inc., New York, NY

Circle.— The general form for the equation of a circle is $x^2 + y^2 + 2gx + 2fy + c = 0$, where $-g$ and $-f$ are the coordinates of the center and the radius is $r = \sqrt{g^2 + f^2 - c}$.

The center radius form of the circle equation is

$$(x-h)^2 + (y-k)^2 = r^2$$

where r = radius and point (h,k) is the center.



When the center of circle is at point (0,0), the equation of circle reduces to $x^2 + y^2 = r^2$ or $r = \sqrt{x^2 + y^2}$

Example: Point (4,6) lies on a circle whose center is at (−2,3). Find the circle equation?

Solution: The radius is the distance between the center (−2,3) and point (4,6), found using the method of Example 1 on page 39.

$$r = \sqrt{[4-(-2)]^2 + (6-3)^2} = \sqrt{6^2 + 3^2} = \sqrt{45}$$

The equation of the circle is

$$(x-h)^2 + (y-k)^2 = r^2$$

$$(x+2)^2 + (y-3)^2 = x^2 + 4x + 4 + y^2 - 6y + 9 = 45$$

$$x^2 + y^2 + 4x - 6y - 32 = 0$$

Parabola.— A parabola is the set of all points P in the plane that are equidistant from focus F and a line called the directrix. A parabola is symmetric with respect to its parabolic axis. The line perpendicular to the parabolic axis which passing through the focus is known as latus rectum.

The general equation of a parabola is given by $(y-k)^2 = 4p(x-h)$, where the vertex is located at point (h,k), the focus F is located at point $(h+p,k)$, the directrix is located at $x = h - p$, and the latus rectum is located at $x = h + p$.

Example: Determine the focus, directrix, axis, vertex, and latus rectum of the parabola

$$4y^2 - 8x - 12y + 1 = 0$$

Solution: Format the equation into the general form of a parabolic equation

$$4y^2 - 8x - 12y + 1 = 0$$

$$4y^2 - 12y = 8x - 1$$

$$y^2 - 3y = 2x - \frac{1}{4}$$

$$y^2 - 2y\frac{3}{2} + \left(\frac{3}{2}\right)^2 = 2x - \frac{1}{4} + \frac{9}{4}$$

$$\left(y - \frac{3}{2}\right)^2 = 2(x+1)$$



Parabola

Thus, $k = 3/2, h = -1$ and $p = 1/2$. Focus F is located at point $(h+p,k) = (1/2, 3/2)$; the directrix is located at $x = h - p = -1 - 1/2 = -3/2$; the parabolic axis is the horizontal line $y = 3/2$; the vertex $V(h,k)$ is located at point $(-1, 3/2)$; and the latus rectum is located at $x = h + p = -1/2$.

Copyright 2004, Industrial Press, Inc., New York, NY

Ellipse.— The ellipse with eccentricity e, focus F and a directrix L is the set of all points P such that the distance PF is e times the distance from P to the line L. The general equation of an ellipse is

$$Ax^2 + Cy^2 + Dx + Ey + F = 0 \Big|_{AC>0 \text{ and } A \neq C}$$

The ellipse has two foci separated along the major axis by a distance $2c$. The line passing through the focus perpendicular to the major axis is called the latus rectum. The line passing through the center, perpendicular to the major axis, is called the minor axis. The distances $2a$ and $2b$ are the major distance, and the minor distance.The ellipse is the locus of points such that the sum of the distances from the two foci to a point on the ellipse is $2a$, thus, $PF_1 + PF_2 = 2a$



Ellipse

If (h,k) are the center, the general equation of an ellipse is $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$

The eccentricity of the ellipse, $e = \frac{\sqrt{a^2-b^2}}{a}$, is always less than 1.

The distance between the two foci is $2c = 2\sqrt{a^2-b^2}$.

The aspect ratio of the ellipse is a/b.

The equation of an ellipse centered at $(0,0)$ with foci at $(\pm c, 0)$ is $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$, and the ellipse is symmetric about both coordinate axes. Its x-intercepts are $(\pm a, 0)$ and y-intercepts are $(0, \pm b)$. The line joining $(0, b)$ and $(0, -b)$ is called the minor axis.The vertices of the ellipse are $(\pm a, 0)$, and the line joining vertices is the major axis of the ellipse.

Example: Determine the values of $h, k, a, b, c,$ and e of the ellipse

$$3x^2 + 5y^2 - 12x + 30y + 42 = 0$$

Solution: Rearrange the ellipse equation into the general form as follows:

$$3x^2 + 5y^2 - 12x + 30y + 42 = 3x^2 - 12x + 5y^2 + 30y + 42 = 0$$

$$3(x^2 - 4x + 2^2) + 5(y^2 + 6y + 3^2) = 15$$

$$\frac{3(x-2)^2}{15} + \frac{5(y+3)^2}{15} = \frac{(x-2)^2}{(\sqrt{5})^2} + \frac{(y+3)^2}{(\sqrt{3})^2} = 1$$

Copyright 2004, Industrial Press, Inc., New York, NY

Comparing the result with the general form, $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$, and solving for c and e gives

$$h = 2 \qquad k = -3 \qquad a = \sqrt{5} \qquad b = \sqrt{3} \qquad c = \sqrt{2} \qquad e = \sqrt{\frac{2}{5}}$$

Four-Arc Oval that Approximates an Ellipse*.— The method of constructing an approximate ellipse by circular arcs, described on page 57, fails when the ratio of the major to minor diameter equals four or greater. Additionally, it is reported that the method always draws a somewhat larger minor axes than intended. The method described below presents an alternative.

An oval that approximates an ellipse, illustrated in Fig. 1, can be constructed from the following equations:

$$r = \frac{B^2}{2A}\left(\frac{A}{B}\right)^{0.38} \tag{1}$$

where A and B are dimensions of the major and minor axis, respectively, and r is the radius of the curve at the long ends.

The radius R and its location are found from Equations (2) and (3):

$$X = \frac{\frac{A^2}{4} - Ar + Br - \frac{B^2}{4}}{B - 2r} \tag{2} \qquad R = \frac{B}{2 + X} \tag{3}$$



Fig. 1.

To make an oval thinner or fatter than that given, select a smaller or larger radius r than calculated by Equation (1) and then find X and R using Equations (2) and (3).

Hyperbola.— The hyperbola with eccentricity e, focus F and a directrix L is the set of all points P such that the distance PF is e times the distance from P to the line L.The general equation of an hyperbola is

$$Ax^2 + Cy^2 + Dx + Ey + F = 0 \Big|_{AC<0 \text{ and } AC \neq 0}$$

The hyperbola has two foci separated along the transverse axis by a distance $2c$. Lines perpendicular to the transverse axis passing through the foci are the conjugate axis. The distance between two vertices is $2a$. The distance along a conjugate axis between two

* *Four-Arc Oval* material contributed by Manfred K. Brueckner

Copyright 2004, Industrial Press, Inc., New York, NY

points on the hyperbola is $2b$.The hyperbola is the locus of points such that the difference of the distances from the two foci is $2a$, thus, $PF_2 - PF_1 = 2a$

If point (h,k) is the center, the general equation of an ellipse is $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$



Hyperbola

The eccentricity of hyperbola, $e = \frac{\sqrt{a^2+b^2}}{a}$ is always less than 1.

The distance between the two foci is $2c = 2\sqrt{a^2+b^2}$.

The equation of a hyperbola with center at $(0,0)$ and focus at $(\pm c, 0)$ is $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$.

Example: Determine the values of $h, k, a, b, c,$ and e of the hyperbola

$$9x^2 - 4y^2 - 36x + 8y - 4 = 0$$

Solution: Convert the hyperbola equation into the general form

$$9x^2 - 4y^2 - 36x + 8y - 4 = (9x^2 - 36x) - (4y^2 - 8y) - 4 = 0$$

$$9(x^2 - 4x + 4) - 4(y^2 - 2y + 1) = 36$$

$$9\frac{(x-2)^2}{36} - \frac{4(y-1)^2}{36} = \frac{(x-2)^2}{2^2} - \frac{(y-1)^2}{3^2} = 1$$

Comparing the results above with the general form $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$ and calculating the eccentricity from $e = \frac{\sqrt{a^2+b^2}}{a}$ and c from $c = \sqrt{a^2+b^2}$ gives

$$h = 2 \qquad k = 1 \qquad a = 2 \qquad b = 3 \qquad c = \sqrt{13} \qquad e = \frac{\sqrt{13}}{2}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Propositions



The sum of the three angles in a triangle always equals 180 degrees. Hence, if two angles are known, the third angle can always be found.

$$A + B + C = 180° \qquad A = 180° - (B + C)$$
$$B = 180° - (A + C) \qquad C = 180° - (A + B)$$



If one side and two angles in one triangle are equal to one side and similarly located angles in another triangle, then the remaining two sides and angle also are equal.

If $a = a_1$, $A = A_1$, and $B = B_1$, then the two other sides and the remaining angle also are equal.



If two sides and the angle between them in one triangle are equal to two sides and a similarly located angle in another triangle, then the remaining side and angles also are equal.

If $a = a_1$, $b = b_1$, and $A = A_1$, then the remaining side and angles also are equal.



If the three sides in one triangle are equal to the three sides of another triangle, then the angles in the two triangles also are equal.

If $a = a_1$, $b = b_1$, and $c = c_1$, then the angles between the respective sides also are equal.



If the three sides of one triangle are proportional to corresponding sides in another triangle, then the triangles are called *similar*, and the angles in the one are equal to the angles in the other.

If $a : b : c = d : e : f$, then $A = D$, $B = E$, and $C = F$.



If the angles in one triangle are equal to the angles in another triangle, then the triangles are similar and their corresponding sides are proportional.

If $A = D$, $B = E$, and $C = F$, then $a : b : c = d : e : f$.



If the three sides in a triangle are equal—that is, if the triangle is *equilateral*—then the three angles also are equal.

Each of the three equal angles in an equilateral triangle is 60 degrees.

If the three angles in a triangle are equal, then the three sides also are equal.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Propositions

	A line in an equilateral triangle that bisects or divides any of the angles into two equal parts also bisects the side opposite the angle and is at right angles to it. If line *AB* divides angle *CAD* into two equal parts, it also divides line *CD* into two equal parts and is at right angles to it.
	If two sides in a triangle are equal—that is, if the triangle is an *isosceles* triangle—then the angles opposite these sides also are equal. If side *a* equals side *b*, then angle *A* equals angle *B*.
	If two angles in a triangle are equal, the sides opposite these angles also are equal. If angles *A* and *B* are equal, then side *a* equals side *b*.
	In an isosceles triangle, if a straight line is drawn from the point where the two equal sides meet, so that it bisects the third side or base of the triangle, then it also bisects the angle between the equal sides and is perpendicular to the base.
	In every triangle, that angle is greater that is opposite a longer side. In every triangle, that side is greater which is opposite a greater angle. If *a* is longer than *b*, then angle *A* is greater than *B*. If angle *A* is greater than *B*, then side *a* is longer than *b*.
	In every triangle, the sum of the lengths of two sides is always greater than the length of the third. Side *a* + side *b* is always greater than side *c*.
	In a right-angle triangle, the square of the hypotenuse or the side opposite the right angle is equal to the sum of the squares on the two sides that form the right angle. $a^2 = b^2 + c^2$

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Propositions

	If one side of a triangle is produced, then the exterior angle is equal to the sum of the two interior opposite angles. Angle D = angle A + angle B
	If two lines intersect, then the opposite angles formed by the intersecting lines are equal. Angle A = angle B Angle C = angle D
	If a line intersects two parallel lines, then the corresponding angles formed by the intersecting line and the parallel lines are equal. Lines *ab* and *cd* are parallel. Then all the angles designated *A* are equal, and all those designated *B* are equal.
	In any figure having four sides, the sum of the interior angles equals 360 degrees. $A + B + C + D$ = 360 degrees
	The sides that are opposite each other in a parallelogram are equal; the angles that are opposite each other are equal; the diagonal divides it into two equal parts. If two diagonals are drawn, they bisect each other.
	The areas of two parallelograms that have equal base and equal height are equal. If $a = a_1$ and $h = h_1$, then Area A = area A_1
	The areas of triangles having equal base and equal height are equal. If $a = a_1$ and $h = h_1$, then Area A = area A_1
	If a diameter of a circle is at right angles to a chord, then it bisects or divides the chord into two equal parts.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Propositions

	If a line is tangent to a circle, then it is also at right angles to a line drawn from the center of the circle to the point of tangency—that is, to a radial line through the point of tangency.
	If two circles are tangent to each other, then the straight line that passes through the centers of the two circles must also pass through the point of tangency.
	If from a point outside a circle, tangents are drawn to a circle, the two tangents are equal and make equal angles with the chord joining the points of tangency.
	The angle between a tangent and a chord drawn from the point of tangency equals one-half the angle at the center subtended by the chord. Angle $B = \frac{1}{2}$ angle A
	The angle between a tangent and a chord drawn from the point of tangency equals the angle at the periphery subtended by the chord. Angle B, between tangent ab and chord cd, equals angle A subtended at the periphery by chord cd.
	All angles having their vertex at the periphery of a circle and subtended by the same chord are equal. Angles A, B, and C, all subtended by chord cd, are equal.
	If an angle at the circumference of a circle, between two chords, is subtended by the same arc as the angle at the center, between two radii, then the angle at the circumference is equal to one-half of the angle at the center. Angle $A = \frac{1}{2}$ angle B

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Propositions

	An angle subtended by a chord in a circular segment larger than one-half the circle is an acute angle—an angle less than 90 degrees. An angle subtended by a chord in a circular segment less than one-half the circle is an obtuse angle—an angle greater than 90 degrees.
	If two chords intersect each other in a circle, then the rectangle of the segments of the one equals the rectangle of the segments of the other. $a \times b = c \times d$
	If from a point outside a circle two lines are drawn, one of which intersects the circle and the other is tangent to it, then the rectangle contained by the total length of the intersecting line, and that part of it that is between the outside point and the periphery, equals the square of the tangent. $a^2 = b \times c$
	If a triangle is inscribed in a semicircle, the angle opposite the diameter is a right (90-degree) angle. All angles at the periphery of a circle, subtended by the diameter, are right (90-degree) angles.
	The lengths of circular arcs of the same circle are proportional to the corresponding angles at the center. $A : B = a : b$
	The lengths of circular arcs having the same center angle are proportional to the lengths of the radii. If $A = B$, then $a : b = r : R$.
	The circumferences of two circles are proportional to their radii. The areas of two circles are proportional to the squares of their radii. $c : C = r : R$ $a : A = r^2 : R^2$

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Constructions

	To divide a line *AB* into two equal parts: With the ends *A* and *B* as centers and a radius greater than one-half the line, draw circular arcs. Through the intersections *C* and *D*, draw line *CD*. This line divides *AB* into two equal parts and is also perpendicular to *AB*.
	To draw a perpendicular to a straight line from a point *A* on that line: With *A* as a center and with any radius, draw circular arcs intersecting the given line at *B* and *C*. Then, with *B* and *C* as centers and a radius longer than *AB*, draw circular arcs intersecting at *D*. Line *DA* is perpendicular to *BC* at *A*.
	To draw a perpendicular line from a point *A* at the end of a line *AB*: With any point *D*, outside of the line *AB*, as a center, and with *AD* as a radius, draw a circular arc intersecting *AB* at *E*. Draw a line through *E* and *D* intersecting the arc at *C*; then join *AC*. This line is the required perpendicular.
	To draw a perpendicular to a line *AB* from a point *C* at a distance from it: With *C* as a center, draw a circular arc intersecting the given line at *E* and *F*. With *E* and *F* as centers, draw circular arcs with a radius longer than one-half the distance between *E* and *F*. These arcs intersect at *D*. Line *CD* is the required perpendicular.
	To divide a straight line *AB* into a number of equal parts: Let it be required to divide *AB* into five equal parts. Draw line *AC* at an angle with *AB*. Set off on *AC* five equal parts of any convenient length. Draw *B*–5 and then draw lines parallel with *B*–5 through the other division points on *AC*. The points where these lines intersect *AB* are the required division points.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Constructions

	To draw a straight line parallel to a given line *AB*, at a given distance from it: With any points *C* and *D* on *AB* as centers, draw circular arcs with the given distance as radius. Line *EF*, drawn to touch the circular arcs, is the required parallel line.
	To bisect or divide an angle *BAC* into two equal parts: With *A* as a center and any radius, draw arc *DE*. With *D* and *E* as centers and a radius greater than one-half *DE*, draw circular arcs intersecting at *F*. Line *AF* divides the angle into two equal parts.
	To draw an angle upon a line *AB*, equal to a given angle *FGH*: With point *G* as a center and with any radius, draw arc *KL*. With *A* as a center and with the same radius, draw arc *DE*. Make arc *DE* equal to *KL* and draw *AC* through *E*. Angle *BAC* then equals angle *FGH*.
	To lay out a 60-degree angle: With *A* as a center and any radius, draw an arc *BC*. With point *B* as a center and *AB* as a radius, draw an arc intersecting at *E* the arc just drawn. *EAB* is a 60-degree angle. A 30-degree angle may be obtained either by dividing a 60-degree angle into two equal parts or by drawing a line *EG* perpendicular to *AB*. Angle *AEG* is then 30 degrees.
	To draw a 45-degree angle: From point *A* on line *AB*, set off a distance *AC*. Draw the perpendicular *DC* and set off a distance *CE* equal to *AC*. Draw *AE*. Angle *EAC* is a 45-degree angle.
	To draw an equilateral triangle, the length of the sides of which equals *AB*: With *A* and *B* as centers and *AB* as radius, draw circular arcs intersecting at *C*. Draw *AC* and *BC*. Then *ABC* is an equilateral triangle.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Constructions

	To draw a circular arc with a given radius through two given points *A* and *B*: With *A* and *B* as centers, and the given radius as radius, draw circular arcs intersecting at *C*. With *C* as a center, and the same radius, draw a circular arc through *A* and *B*.
	To find the center of a circle or of an arc of a circle: Select three points on the periphery of the circle, as *A*, *B*, and *C*. With each of these points as a center and the same radius, describe arcs intersecting each other. Through the points of intersection, draw lines *DE* and *FG*. Point *H*, where these lines intersect, is the center of the circle.
	To draw a tangent to a circle from a given point on the circumference: Through the point of tangency *A*, draw a radial line *BC*. At point *A*, draw a line *EF* at right angles to *BC*. This line is the required tangent.
	To divide a circular arc *AB* into two equal parts: With *A* and *B* as centers, and a radius larger than half the distance between *A* and *B*, draw circular arcs intersecting at *C* and *D*. Line *CD* divides arc *AB* into two equal parts at *E*.
	To describe a circle about a triangle: Divide the sides *AB* and *AC* into two equal parts, and from the division points *E* and *F*, draw lines at right angles to the sides. These lines intersect at *G*. With *G* as a center and *GA* as a radius, draw circle *ABC*.
	To inscribe a circle in a triangle: Bisect two of the angles, *A* and *B*, by lines intersecting at *D*. From *D*, draw a line *DE* perpendicular to one of the sides, and with *DE* as a radius, draw circle *EFG*.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Constructions



To describe a circle about a square and to inscribe a circle in a square:

The centers of both the circumscribed and inscribed circles are located at the point *E*, where the two diagonals of the square intersect. The radius of the circumscribed circle is *AE*, and of the inscribed circle, *EF*.



To inscribe a hexagon in a circle:

Draw a diameter *AB*. With *A* and *B* as centers and with the radius of the circle as radius, describe circular arcs intersecting the given circle at *D*, *E*, *F*, and *G*. Draw lines *AD*, *DE*, etc., forming the required hexagon.



To describe a hexagon about a circle:

Draw a diameter *AB*, and with *A* as a center and the radius of the circle as radius, cut the circumference of the given circle at *D*. Join *AD* and bisect it with radius *CE*. Through *E*, draw *FG* parallel to *AD* and intersecting line *AB* at *F*. With *C* as a center and *CF* as radius, draw a circle. Within this circle, inscribe the hexagon as in the preceding problem.



To describe an ellipse with the given axes *AB* and *CD*:

Describe circles with *O* as a center and *AB* and *CD* as diameters. From a number of points, *E*, *F*, *G*, etc., on the outer circle, draw radii intersecting the inner circle at *e*, *f*, and *g*. From *E*, *F*, and *G*, draw lines perpendicular to *AB*, and from *e*, *f*, and *g*, draw lines parallel to *AB*. The intersections of these perpendicular and parallel lines are points on the curve of the ellipse.



To construct an approximate ellipse by circular arcs:

Let *AC* be the major axis and *BN* the minor. Draw half circle *ADC* with *O* as a center. Divide *BD* into three equal parts and set off *BE* equal to one of these parts. With *A* and *C* as centers and *OE* as radius, describe circular arcs *KLM* and *FGH*; with *G* and *L* as centers, and the same radius, describe arcs *FCH* and *KAM*. Through *F* and *G*, drawn line *FP*, and with *P* as a center, draw the arc *FBK*. Arc *HNM* is drawn in the same manner.

Copyright 2004, Industrial Press, Inc., New York, NY

Geometrical Constructions



To construct a parabola:

Divide line *AB* into a number of equal parts and divide *BC* into the same number of parts. From the division points on *AB*, draw horizontal lines. From the division points on *BC*, draw lines to point *A*. The points of intersection between lines drawn from points numbered alike are points on the parabola.



To construct a hyperbola:

From focus *F*, lay off a distance *FD* equal to the transverse axis, or the distance *AB* between the two branches of the curve. With *F* as a center and any distance *FE* greater than *FB* as a radius, describe a circular arc. Then with F_1 as a center and *DE* as a radius, describe arcs intersecting at *C* and *G* the arc just described. *C* and *G* are points on the hyperbola. Any number of points can be found in a similar manner.



To construct an involute:

Divide the circumference of the base circle *ABC* into a number of equal parts. Through the division points 1, 2, 3, etc., draw tangents to the circle and make the lengths *D*–1, *E*–2, *F*–3, etc., of these tangents equal to the actual length of the arcs *A*–1, *A*–2, *A*–3, etc.



To construct a helix:

Divide half the circumference of the cylinder, on the surface of which the helix is to be described, into a number of equal parts. Divide half the lead of the helix into the same number of equal parts. From the division points on the circle representing the cylinder, draw vertical lines, and from the division points on the lead, draw horizontal lines as shown. The intersections between lines numbered alike are points on the helix.

Copyright 2004, Industrial Press, Inc., New York, NY

Areas and Volumes

The Prismoidal Formula.— The prismoidal formula is a general formula by which the volume of any prism, pyramid, or frustum of a pyramid may be found.

A_1 = area at one end of the body

A_2 = area at the other end

A_m = area of middle section between the two end surfaces

h = height of body

Then, volume V of the body is $V = \frac{h}{6}(A_1 + 4A_m + A_2)$

Pappus or Guldinus Rules.— By means of these rules the area of any surface of revolution and the volume of any solid of revolution may be found. The area of the surface swept out by the revolution of a line *ABC* (see illustration) about the axis *DE* equals the length of the line multiplied by the length of the path of its center of gravity, *P*. If the line is of such a shape that it is difficult to determine its center of gravity, then the line may be divided into a number of short sections, each of which may be considered as a straight line, and the areas swept out by these different sections, as computed by the rule given, may be added to find the total area. The line must lie wholly on one side of the axis of revolution and must be in the same plane.



The volume of a solid body formed by the revolution of a surface *FGHJ* about axis *KL* equals the area of the surface multiplied by the length of the path of its center of gravity. The surface must lie wholly on one side of the axis of revolution and in the same plane.



Example: By means of these rules, the area and volume of a cylindrical ring or torus may be found. The torus is formed by a circle *AB* being rotated about axis *CD*. The center of gravity of the circle is at its center. Hence, with the dimensions given in the illustration, the length of the path of the center of gravity of the circle is $3.1416 \times 10 = 31.416$ inches. Multiplying by the length of the circumference of the circle, which is $3.1416 \times 3 = 9.4248$ inches, gives $31.416 \times 9.4248 = 296.089$ square inches which is the area of the torus.

The volume equals the area of the circle, which is $0.7854 \times 9 = 7.0686$ square inches, multiplied by the path of the center of gravity, which is 31.416, as before; hence,

$$\text{Volume} = 7.0686 \times 31.416 = 222.067 \text{ cubic inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Approximate Method for Finding the Area of a Surface of Revolution.— The accompanying illustration is shown in order to give an example of the approximate method based on Guldinus' rule, that can be used for finding the area of a symmetrical body. In the illustration, the dimensions in common fractions are the known dimensions; those in decimals are found by actual measurements on a figure drawn to scale.



The method for finding the area is as follows: First, separate such areas as are cylindrical, conical, or spherical, as these can be found by exact formulas. In the illustration *ABCD* is a cylinder, the area of the surface of which can be easily found. The top area *EF* is simply a circular area, and can thus be computed separately. The remainder of the surface generated by rotating line *AF* about the axis *GH* is found by the approximate method explained in the previous section. From point *A*, set off equal distances on line *AF*. In the illustration, each division indicated is ⅛ inch long. From the central or middle point of each of these parts draw a line at right angles to the axis of rotation *GH*, measure the length of these lines or diameters (the length of each is given in decimals), add all these lengths together and multiply the sum by the length of one division set off on line *AF* (in this case, ⅛ inch), and multiply this product by π to find the approximate area of the surface of revolution.

In setting off divisions ⅛ inch long along line *AF*, the last division does not reach exactly to point *F*, but only to a point 0.03 inch below it. The part 0.03 inch high at the top of the cup can be considered as a cylinder of ½ inch diameter and 0.03 inch height, the area of the cylindrical surface of which is easily computed. By adding the various surfaces together, the total surface of the cup is found as follows:

Cylinder, 1 ⅝ inch diameter, 0.41 inch high	2.093 square inches
Circle, ½ inch diameter	0.196 square inch
Cylinder, ½ inch diameter, 0.03 inch high	0.047 square inch
Irregular surface	3.868 square inches
Total	6.204 square inches

Area of Plane Surfaces of Irregular Outline.— One of the most useful and accurate methods for determining the approximate area of a plane figure or irregular outline is known as *Simpson's Rule*. In applying Simpson's Rule to find an area the work is done in four steps:

1) Divide the area into an *even* number, *N*, of parallel strips of equal width *W*; for example, in the accompanying diagram, the area has been divided into 8 strips of equal width.

2) Label the sides of the strips V_0, V_1, V_2, etc., up to V_N.

3) Measure the heights $V_0, V_1, V_2, \ldots, V_N$ of the sides of the strips.

4) Substitute the heights V_0, V_1, etc., in the following formula to find the area *A* of the figure:

Copyright 2004, Industrial Press, Inc., New York, NY

$$A = \frac{W}{3}[(V_0 + V_N) + 4(V_1 + V_3 + \cdots + V_{N-1}) + 2(V_2 + V_4 + \cdots + V_N$$

Example: The area of the accompanying figure was divided into 8 strips on a full-size drawing and the following data obtained. Calculate the area using Simpson's Rule.

$W = \frac{1}{2}''$
$V_0 = 0''$
$V_1 = \frac{3}{4}''$
$V_2 = 1\frac{1}{4}''$
$V_3 = 1\frac{1}{2}''$
$V_4 = 1\frac{5}{8}''$
$V_5 = 2\frac{1}{4}''$
$V_6 = 2\frac{1}{2}''$
$V_7 = 1\frac{3}{4}''$
$V_8 = \frac{1}{2}''$



Substituting the given data in the Simpson formula,

$$A = \frac{\frac{1}{2}}{3}[(0 + \tfrac{1}{2}) + 4(\tfrac{3}{4} + 1\tfrac{1}{2} + 2\tfrac{1}{4} + 1\tfrac{3}{4}) + 2(1\tfrac{1}{4} + 1\tfrac{5}{8} + 2\tfrac{1}{2})]$$

$$= \tfrac{1}{6}[(\tfrac{1}{2}) + 4(6\tfrac{1}{4}) + 2(5\tfrac{3}{8})] = \tfrac{1}{6}[36\tfrac{1}{4}]$$

$$= 6.04 \text{ square inches}$$

In applying Simpson's Rule, it should be noted that the larger the number of strips into which the area is divided the more accurate the results obtained.

Areas Enclosed by Cycloidal Curves.— The area between a cycloid and the straight line upon which the generating circle rolls, equals three times the area of the generating circle (see diagram, page 66). The areas between epicycloidal and hypocycloidal curves and the "fixed circle" upon which the generating circle is rolled, may be determined by the following formulas, in which a = radius of the fixed circle upon which the generating circle rolls; b = radius of the generating circle; A = the area for the epicycloidal curve; and A_1 = the area for the hypocycloidal curve.

$$A = \frac{3.1416b^2(3a + 2b)}{a} \qquad A_1 = \frac{3.1416b^2(3a - 2b)}{a}$$

Find the Contents of Cylindrical Tanks at Different Levels.— In conjunction with the table *Segments of Circles for Radius = 1* starting on page 71, the following relations can give a close approximation of the liquid contents, at any level, in a cylindrical tank.



A long measuring rule calibrated in length units or simply a plain stick can be used for measuring contents at a particular level. In turn, the rule or stick can be graduated to serve as a volume gauge for the tank in question. The only requirements are that the cross-section of the tank is circular; the tank's dimensions are known; the gauge rod is inserted vertically through the top center of the tank so that it rests on the exact bottom of the tank; and that consistent English *or* metric units are used throughout the calculations.

Copyright 2004, Industrial Press, Inc., New York, NY

$K = Cr^2L$ = Tank Constant (remains the same for any given tank) (1)

$V_T = \pi K$, for a tank that is completely full (2)

$V_s = KA$ (3)

$V = V_s$ when tank is less than half full (4)

$V = V_T - V_s = V_T - KA$, when tank is more than half full (5)

where C = liquid volume conversion factor, the exact value of which depends on the length and liquid volume units being used during measurement: 0.00433 U.S. gal/in^3; 7.48 U.S. gal/ft^3; 0.00360 U.K. gal/in^3; 6.23 U.K. gal/ft^3; 0.001 liter/cm^3; or 1000 liters/m^3

V_T = total volume of liquid tank can hold

V_s = volume formed by segment of circle having depth = x in given tank (see diagram)

V = volume of liquid at particular level in tank

d = diameter of tank; L = length of tank; r = radius of tank (= ½ diameter)

A = segment area of a corresponding unit circle taken from the table starting on page 71

y = actual depth of contents in tank as shown on a gauge rod or stick

x = depth of the segment of a circle to be considered in given tank. As can be seen in above diagram, x is the actual depth of contents (y) when the tank is less than half full, and is the depth of the void ($d - y$) above the contents when the tank is more than half full. From pages 71 and 74 it can also be seen that h, the height of a segment of a corresponding unit circle, is x/r

Example: A tank is 20 feet long and 6 feet in diameter. Convert a long inch-stick into a gauge that is graduated at 1000 and 3000 U.S. gallons.

$$L = 20 \times 12 = 240\,\text{in.} \qquad r = \tfrac{6}{2} \times 12 = 36\,\text{in.}$$

From Formula (1): $K = 0.00433(36)^2(240) = 1346.80$

From Formula (2): $V_T = 3.1416 \times 1347 = 4231.1$ US gal.

The 72-inch mark from the bottom on the inch-stick can be graduated for the rounded full volume "4230"; and the halfway point 36″ for 4230/2 or "2115." It can be seen that the 1000-gal mark would be below the halfway mark. From Formulas (3) and (4):

$A_{1000} = \dfrac{1000}{1347} = 0.7424$ from the table starting on page 71, h can be interpolated as 0.5724; and $x = y = 36 \times 0.5724 = 20.61$. If the desired level of accuracy permits, interpolation can be omitted by choosing h directly from the table on page 71 for the value of A nearest that calculated above.

Therefore, the 1000-gal mark is graduated 20⅝″ from bottom of rod.

It can be seen that the 3000 mark would be above the halfway mark. Therefore, the circular segment considered is the cross-section of the void space at the top of the tank. From Formulas (3) and (5):

$$A_{3000} = \frac{4230 - 3000}{1347} = 0.9131;\ h = 0.6648;\ x = 36 \times 0.6648 = 23.93''$$

Therefore, the 3000-gal mark is 72.00 – 23.93 = 48.07, or at the 48 1/16″ mark from the bottom.

Copyright 2004, Industrial Press, Inc., New York, NY

Areas and Dimensions of Plane Figures

In the following tables are given formulas for the areas of plane figures, together with other formulas relating to their dimensions and properties; the surfaces of solids; and the volumes of solids. The notation used in the formulas is, as far as possible, given in the illustration accompanying them; where this has not been possible, it is given at the beginning of each set of formulas.

Examples are given with each entry, some in English and some in metric units, showing the use of the preceding formula.

Square:



$$\text{Area} = A = s^2 = \tfrac{1}{2}d^2$$
$$s = 0.7071d = \sqrt{A}$$
$$d = 1.414s = 1.414\sqrt{A}$$

Example: Assume that the side s of a square is 15 inches. Find the area and the length of the diagonal.

$$\text{Area} = A = s^2 = 15^2 = 225 \text{ square inches}$$
$$\text{Diagonal} = d = 1.414s = 1.414 \times 15 = 21.21 \text{ inches}$$

Example: The area of a square is 625 square inches. Find the length of the side s and the diagonal d.

$$s = \sqrt{A} = \sqrt{625} = 25 \text{ inches}$$
$$d = 1.414\sqrt{A} = 1.414 \times 25 = 35.35 \text{ inches}$$

Rectangle:



$$\text{Area} = A = ab = a\sqrt{d^2 - a^2} = b\sqrt{d^2 - b^2}$$
$$d = \sqrt{a^2 + b^2}$$
$$a = \sqrt{d^2 - b^2} = A \div b$$
$$a = \sqrt{d^2 - a^2} = A \div a$$

Example: The side a of a rectangle is 12 centimeters, and the area 70.5 square centimeters. Find the length of the side b, and the diagonal d.

$$b = A \div a = 70.5 \div 12 = 5.875 \text{ centimeters}$$
$$d = \sqrt{a^2 + b^2} = \sqrt{12^2 + 5.875^2} = \sqrt{178.516} = 13.361 \text{ centimeters}$$

Example: The sides of a rectangle are 30.5 and 11 centimeters long. Find the area.

$$\text{Area} = A = a \times b = 30.5 \times 11 = 335.5 \text{ square centimeters}$$

Parallelogram:



$$\text{Area} = A = ab$$
$$a = A \div b$$
$$b = A \div a$$

Note: The dimension a is measured at right angles to line b.

Example: The base b of a parallelogram is 16 feet. The height a is 5.5 feet. Find the area.

$$\text{Area} = A = a \times b = 5.5 \times 16 = 88 \text{ square feet}$$

Example: The area of a parallelogram is 12 square inches. The height is 1.5 inches. Find the length of the base b.

$$b = A \div a = 12 \div 1.5 = 8 \text{ inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Right-Angled Triangle:



$$\text{Area} = A = \frac{bc}{2}$$

$$a = \sqrt{b^2 + c^2}$$

$$b = \sqrt{a^2 - c^2}$$

$$c = \sqrt{a^2 - b^2}$$

Example: The sides b and c in a right-angled triangle are 6 and 8 inches. Find side a and the area

$$a = \sqrt{b^2 + c^2} = \sqrt{6^2 + 8^2} = \sqrt{36 + 64} = \sqrt{100} = 10 \text{ inches}$$

$$A = \frac{b \times c}{2} = \frac{6 \times 8}{2} = \frac{48}{2} = 24 \text{ square inches}$$

Example: If $a = 10$ and $b = 6$ had been known, but not c, the latter would have been found as follows:

$$c = \sqrt{a^2 - b^2} = \sqrt{10^2 - 6^2} = \sqrt{100 - 36} = \sqrt{64} = 8 \text{ inches}$$

Acute-Angled Triangle:



$$\text{Area} = A = \frac{bh}{2} = \frac{b}{2}\sqrt{a^2 - \left(\frac{a^2 + b^2 - c^2}{2b}\right)^2}$$

If $S = \frac{1}{2}(a + b + c)$, then

$$A = \sqrt{S(S-a)(S-b)(S-c)}$$

Example: If $a = 10$, $b = 9$, and $c = 8$ centimeters, what is the area of the triangle?

$$A = \frac{b}{2}\sqrt{a^2 - \left(\frac{a^2 + b^2 - c^2}{2b}\right)^2} = \frac{9}{2}\sqrt{10^2 - \left(\frac{10^2 + 9^2 - 8^2}{2 \times 9}\right)^2} = 4.5\sqrt{100 - \left(\frac{117}{18}\right)^2}$$

$$= 4.5\sqrt{100 - 42.25} = 4.5\sqrt{57.75} = 4.5 \times 7.60 = 34.20 \text{ square centimeters}$$

Obtuse-Angled Triangle:



$$\text{Area} = A = \frac{bh}{2} = \frac{b}{2}\sqrt{a^2 - \left(\frac{c^2 - a^2 - b^2}{2b}\right)^2}$$

If $S = \frac{1}{2}(a + b + c)$, then

$$A = \sqrt{S(S-a)(S-b)(S-c)}$$

Example: The side $a = 5$, side $b = 4$, and side $c = 8$ inches. Find the area.

$$S = \tfrac{1}{2}(a + b + c) = \tfrac{1}{2}(5 + 4 + 8) = \tfrac{1}{2} \times 17 = 8.5$$

$$A = \sqrt{S(S-a)(S-b)(S-c)} = \sqrt{8.5(8.5-5)(8.5-4)(8.5-8)}$$

$$= \sqrt{8.5 \times 3.5 \times 4.5 \times 0.5} = \sqrt{66.937} = 8.18 \text{ square inches}$$

Trapezoid:



$$\text{Area} = A = \frac{(a + b)h}{2}$$

Note: In Britain, this figure is called a *trapezium* and the one below it is known as a *trapezoid*, the terms being reversed.

Example: Side $a = 23$ meters, side $b = 32$ meters, and height $h = 12$ meters. Find the area.

$$A = \frac{(a + b)h}{2} = \frac{(23 + 32)12}{2} = \frac{55 \times 12}{2} = 330 \text{ square meters}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Trapezium:



$$\text{Area} = A = \frac{(H+h)a + bh + cH}{2}$$

A trapezium can also be divided into two triangles as indicated by the dashed line. The area of each of these triangles is computed, and the results added to find the area of the trapezium.

Example: Let $a = 10, b = 2, c = 3, h = 8$, and $H = 12$ inches. Find the area.

$$A = \frac{(H+h)a + bh + cH}{2} = \frac{(12+8)10 + 2\times 8 + 3\times 12}{2}$$

$$= \frac{20\times 10 + 16 + 36}{2} = \frac{252}{2} = 126 \text{ square inches}$$

Regular Hexagon:



$A = 2.598s^2 = 2.598R^2 = 3.464r^2$
$R = s =$ radius of circumscribed circle $= 1.155r$
$r =$ radius of inscribed circle $= 0.866s = 0.866R$
$s = R = 1.155r$

Example: The side s of a regular hexagon is 40 millimeters. Find the area and the radius r of the inscribed circle.

$$A = 2.598s^2 = 2.598\times 40^2 = 2.598\times 1600 = 4156.8 \text{ square millimeters}$$

$$r = 0.866s = 0.866\times 40 = 34.64 \text{ millimeters}$$

Example: What is the length of the side of a hexagon that is drawn around a circle of 50 millimeters radius? — Here $r = 50$. Hence, $s = 1.155r = 1.155\times 50 = 57.75$ millimeters

Regular Octagon:



$A =$ area $= 4.828s^2 = 2.828R^2 = 3.3\,14r^2$
$R =$ radius of circumscribed circle $= 1.307s = 1.082r$
$r =$ radius of inscribed circle $= 1.207s = 0.924R$
$s = 0.765R = 0.828r$

Example: Find the area and the length of the side of an octagon that is inscribed in a circle of 12 inches diameter.

Diameter of circumscribed circle = 12 inches; hence, $R = 6$ inches.

$$A = 2.828R^2 = 2.828\times 6^2 = 2.828\times 36 = 101.81 \text{ square inches}$$

$$s = 0.765R = 0.765\times 6 = 4.590 \text{ inches}$$

Regular Polygon:



$A =$ area $\quad n =$ number of sides

$\alpha = 360° \div n \quad \beta = 180° - \alpha$

$$A = \frac{nsr}{2} = \frac{ns}{2}\sqrt{R^2 - \frac{s^2}{4}}$$

$$R = \sqrt{r^2 + \frac{s^2}{4}} \qquad r = \sqrt{R^2 - \frac{s^2}{4}} \qquad s = 2\sqrt{R^2 - r^2}$$

Example: Find the area of a polygon having 12 sides, inscribed in a circle of 8 centimeters radius. The length of the side s is 4.141 centimeters.

$$A = \frac{ns}{2}\sqrt{R^2 - \frac{s^2}{4}} = \frac{12\times 4.141}{2}\sqrt{8^2 - \frac{4.141^2}{4}} = 24.846\sqrt{59.713}$$

$$= 24.846\times 7.727 = 191.98 \text{ square centimeters}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Circle:



$$\text{Area} = A = \pi r^2 = 3.1416r^2 = 0.7854d^2$$
$$\text{Circumference} = C = 2\pi r = 6.2832r = 3.1416d$$
$$r = C \div 6.2832 = \sqrt{A \div 3.1416} = 0.564\sqrt{A}$$
$$d = C \div 3.1416 = \sqrt{A \div 0.7854} = 1.128\sqrt{A}$$

Length of arc for center angle of 1° = 0.008727*d*
Length of arc for center angle of *n*° = 0.008727*nd*

Example: Find the area *A* and circumference *C* of a circle with a diameter of 2¾ inches.

$A = 0.7854d^2 = 0.7854 \times 2.75^2 = 0.7854 \times 2.75 \times 2.75 = 5.9396$ square inches

$C = 3.1416d = 3.1416 \times 2.75 = 8.6394$ inches

Example: The area of a circle is 16.8 square inches. Find its diameter.

$$d = 1.128\sqrt{A} = 1.128\sqrt{16.8} = 1.128 \times 4.099 = 4.624 \text{ inches}$$

Circular Sector:



$$\text{Length of arc} = l = \frac{r \times \alpha \times 3.1416}{180} = 0.01745r\alpha = \frac{2A}{r}$$
$$\text{Area} = A = \tfrac{1}{2}rl = 0.008727\alpha r^2$$
$$\text{Angle, in degrees} = \alpha = \frac{57.296\ l}{r} \qquad r = \frac{2A}{l} = \frac{57.296\ l}{\alpha}$$

Example: The radius of a circle is 35 millimeters, and angle α of a sector of the circle is 60 degrees. Find the area of the sector and the length of arc *l*.

$A = 0.008727\alpha r^2 = 0.008727 \times 60 \times 35^2 = 641.41\,\text{mm}^2 = 6.41\,\text{cm}^2$

$l = 0.01745r\alpha = 0.01745 \times 35 \times 60 = 36.645$ millimeters

Circular Segment:



A = area l = length of arc α = angle, in degrees

$$c = 2\sqrt{h(2r-h)} \qquad A = \tfrac{1}{2}[rl - c(r-h)]$$
$$r = \frac{c^2 + 4h^2}{8h} \qquad l = 0.01745r\alpha$$
$$h = r - \tfrac{1}{2}\sqrt{4r^2 - c^2} = r[1 - \cos(\alpha/2)] \qquad \alpha = \frac{57.296\ l}{r}$$

See also, *Circular Segments* starting on page 70.

Example: The radius *r* is 60 inches and the height *h* is 8 inches. Find the length of the chord *c*.

$$c = 2\sqrt{h(2r-h)} = 2\sqrt{8 \times (2 \times 60 - 8)} = 2\sqrt{896} = 2 \times 29.93 = 59.86 \text{ inches}$$

Example: If *c* = 16, and *h* = 6 inches, what is the radius of the circle of which the segment is a part?

$$r = \frac{c^2 + 4h^2}{8h} = \frac{16^2 + 4 \times 6^2}{8 \times 6} = \frac{256 + 144}{48} = \frac{400}{48} = 8\tfrac{1}{3} \text{ inches}$$

Cycloid:



$$\text{Area} = A = 3\pi r^2 = 9.4248r^2 = 2.3562d^2$$
$$= 3 \times \text{area of generating circle}$$
$$\text{Length of cycloid} = l = 8r = 4d$$

See also, *Areas Enclosed by Cycloidal Curves* on page 61.

Example: The diameter of the generating circle of a cycloid is 6 inches. Find the length *l* of the cycloidal curve, and the area enclosed between the curve and the base line.

$l = 4d = 4 \times 6 = 24$ inches $\qquad A = 2.3562d^2 = 2.3562 \times 6^2 = 84.82$ square inches

Copyright 2004, Industrial Press, Inc., New York, NY

Circular Ring:



$$\text{Area} = A = \pi(R^2 - r^2) = 3.1416(R^2 - r^2)$$
$$= 3.1416(R + r)(R - r)$$
$$= 0.7854(D^2 - d^2) = 0.7854(D + d)(D - d)$$

Example: Let the outside diameter $D = 12$ centimeters and the inside diameter $d = 8$ centimeters. Find the area of the ring.

$$A = 0.7854(D^2 - d^2) = 0.7854(12^2 - 8^2) = 0.7854(144 - 64) = 0.7854 \times 80$$
$$= 62.83 \text{ square centimeters}$$

By the alternative formula:

$$A = 0.7854(D + d)(D - d) = 0.7854(12 + 8)(12 - 8) = 0.7854 \times 20 \times 4$$
$$= 62.83 \text{ square centimeters}$$

Circular Ring Sector:



A = area $\quad \alpha$ = angle, in degrees

$$A = \frac{\alpha\pi}{360}(R^2 - r^2) = 0.00873\alpha(R^2 - r^2)$$
$$= \frac{\alpha\pi}{4 \times 360}(D^2 - d^2) = 0.00218\alpha(D^2 - d^2)$$

Example: Find the area, if the outside radius $R = 5$ inches, the inside radius $r = 2$ inches, and $\alpha = 72$ degrees.

$$A = 0.00873\alpha(R^2 - r^2) = 0.00873 \times 72(5^2 - 2^2)$$
$$= 0.6286(25 - 4) = 0.6286 \times 21 = 13.2 \text{ square inches}$$

Spandrel or Fillet:



$$\text{Area} = A = r^2 - \frac{\pi r^2}{4} = 0.215r^2 = 0.1075c^2$$

Example: Find the area of a spandrel, the radius of which is 0.7 inch.

$$A = 0.215r^2 = 0.215 \times 0.7^2 = 0.105 \text{ square inch}$$

Example: If chord c were given as 2.2 inches, what would be the area?

$$A = 0.1075c^2 = 0.1075 \times 2.2^2 = 0.520 \text{ square inch}$$

Parabola:



$$\text{Area} = A = \tfrac{2}{3}xy$$

(The area is equal to two-thirds of a rectangle which has x for its base and y for its height.)

Example: Let x in the illustration be 15 centimeters, and y, 9 centimeters. Find the area of the shaded portion of the parabola.

$$A = \tfrac{2}{3} \times xy = \tfrac{2}{3} \times 15 \times 9 = 10 \times 9 = 90 \text{ square centimeters}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Parabola:



$$l = \text{length of arc} = \frac{p}{2}\left[\sqrt{\frac{2x}{p}\left(1+\frac{2x}{p}\right)} + \ln\left(\sqrt{\frac{2x}{p}} + \sqrt{1+\frac{2x}{p}}\right)\right]$$

When x is small in proportion to y, the following is a close approximation:

$$l = y\left[1 + \frac{2}{3}\left(\frac{x}{y}\right)^2 - \frac{2}{5}\left(\frac{x}{y}\right)^4\right] \text{ or } l = \sqrt{y^2 + \frac{4}{3}x^2}$$

Example: If $x = 2$ and $y = 24$ feet, what is the approximate length l of the parabolic curve?

$$l = y\left[1 + \frac{2}{3}\left(\frac{x}{y}\right)^2 - \frac{2}{5}\left(\frac{x}{y}\right)^4\right] = 24\left[1 + \frac{2}{3}\left(\frac{2}{24}\right)^2 - \frac{2}{5}\left(\frac{2}{24}\right)^4\right]$$

$$= 24\left[1 + \frac{2}{3} \times \frac{1}{144} - \frac{2}{5} \times \frac{1}{20{,}736}\right] = 24 \times 1.0046 = 24.11 \text{ feet}$$

Segment of Parabola:



Area BFC $= A = \frac{2}{3}$ area of parallelogram BCDE

If FG is the height of the segment, measured at right angles to BC, then:

Area of segment BFC $= \frac{2}{3}$BC × FG

Example: The length of the chord $BC = 19.5$ inches. The distance between lines BC and DE, measured at right angles to BC, is 2.25 inches. This is the height of the segment. Find the area.

Area $= A = \frac{2}{3}$BC × FG $= \frac{2}{3} \times 19.5 \times 2.25 = 29.25$ square inches

Hyperbola:



$$\text{Area BCD} = A = \frac{xy}{2} - \frac{ab}{2}\ln\left(\frac{x}{a} + \frac{y}{b}\right)$$

Example: The half-axes a and b are 3 and 2 inches, respectively. Find the area shown shaded in the illustration for $x = 8$ and $y = 5$.

Inserting the known values in the formula:

$$A = \frac{8 \times 5}{2} - \frac{3 \times 2}{2} \times \ln\left(\frac{8}{3} + \frac{5}{2}\right) = 20 - 3 \times \ln 5.167$$

$$= 20 - 3 \times 1.6423 = 20 - 4.927 = 15.073 \text{ square inches}$$

Ellipse:



$$\text{Area} = A = \pi ab = 3.1416ab$$

An approximate formula for the perimeter is

$$\text{Perimeter} = P = 3.1416\sqrt{2(a^2 + b^2)}$$

A closer approximation is

$$P = 3.1416\sqrt{2(a^2 + b^2) - \frac{(a-b)^2}{2.2}}$$

Example: The larger or major axis is 200 millimeters. The smaller or minor axis is 150 millimeters. Find the area and the approximate circumference. Here, then, $a = 100$, and $b = 75$.

$A = 3.1416ab = 3.1416 \times 100 \times 75 = 23{,}562$ square millimeters $= 235.62$ square centimeters

$P = 3.1416\sqrt{2(a^2 + b^2)} = 3.1416\sqrt{2(100^2 + 75^2)} = 3.1416\sqrt{2 \times 15{,}625}$

$= 3.1416\sqrt{31{,}250} = 3.1416 \times 176.78 = 555.37$ millimeters $=$ (55.537 centimeters)

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas and Table for Regular Polygons.— The following formulas and table can be used to calculate the area, length of side, and radii of the inscribed and circumscribed circles of regular polygons (equal sided).

$$A = NS^2 \cot\alpha \div 4 = NR^2 \sin\alpha \cos\alpha = Nr^2 \tan\alpha$$
$$r = R\cos\alpha = (S\cot\alpha) \div 2 = \sqrt{(A \times \cot\alpha) \div N}$$
$$R = S \div (2\sin\alpha) = r \div \cos\alpha = \sqrt{A \div (N\sin\alpha\cos\alpha)}$$
$$S = 2R\sin\alpha = 2r\tan\alpha = 2\sqrt{(A \times \tan\alpha) \div N}$$

where N = number of sides; S = length of side; R = radius of circumscribed circle; r = radius of inscribed circle; A = area of polygon; and, $\alpha = 180° \div N$ = one-half center angle of one side. See also *Regular Polygon* on page 65.

Area, Length of Side, and Inscribed and Circumscribed Radii of Regular Polygons

No. of Sides	$\frac{A}{S^2}$	$\frac{A}{R^2}$	$\frac{A}{r^2}$	$\frac{R}{S}$	$\frac{R}{r}$	$\frac{S}{R}$	$\frac{S}{r}$	$\frac{r}{R}$	$\frac{r}{S}$
3	0.4330	1.2990	5.1962	0.5774	2.0000	1.7321	3.4641	0.5000	0.2887
4	1.0000	2.0000	4.0000	0.7071	1.4142	1.4142	2.0000	0.7071	0.5000
5	1.7205	2.3776	3.6327	0.8507	1.2361	1.1756	1.4531	0.8090	0.6882
6	2.5981	2.5981	3.4641	1.0000	1.1547	1.0000	1.1547	0.8660	0.8660
7	3.6339	2.7364	3.3710	1.1524	1.1099	0.8678	0.9631	0.9010	1.0383
8	4.8284	2.8284	3.3137	1.3066	1.0824	0.7654	0.8284	0.9239	1.2071
9	6.1818	2.8925	3.2757	1.4619	1.0642	0.6840	0.7279	0.9397	1.3737
10	7.6942	2.9389	3.2492	1.6180	1.0515	0.6180	0.6498	0.9511	1.5388
12	11.196	3.0000	3.2154	1.9319	1.0353	0.5176	0.5359	0.9659	1.8660
16	20.109	3.0615	3.1826	2.5629	1.0196	0.3902	0.3978	0.9808	2.5137
20	31.569	3.0902	3.1677	3.1962	1.0125	0.3129	0.3168	0.9877	3.1569
24	45.575	3.1058	3.1597	3.8306	1.0086	0.2611	0.2633	0.9914	3.7979
32	81.225	3.1214	3.1517	5.1011	1.0048	0.1960	0.1970	0.9952	5.0766
48	183.08	3.1326	3.1461	7.6449	1.0021	0.1308	0.1311	0.9979	7.6285
64	325.69	3.1365	3.1441	10.190	1.0012	0.0981	0.0983	0.9988	10.178

Example 1: A regular hexagon is inscribed in a circle of 6 inches diameter. Find the area and the radius of an inscribed circle. Here $R = 3$. From the table, area $A = 2.5981R^2 = 2.5981 \times 9 = 23.3829$ square inches. Radius of inscribed circle, $r = 0.866R = 0.866 \times 3 = 2.598$ inches.

Example 2: An octagon is inscribed in a circle of 100 millimeters diameter. Thus $R = 50$. Find the area and radius of an inscribed circle. $A = 2.8284R^2 = 2.8284 \times 2500 = 7071$ mm^2 $= 70.7$ cm^2. Radius of inscribed circle, $r = 0.9239R = 09239 \times 50 = 46.195$ mm.

Example 3: Thirty-two bolts are to be equally spaced on the periphery of a bolt-circle, 16 inches in diameter. Find the chordal distance between the bolts. Chordal distance equals the side S of a polygon with 32 sides. $R = 8$. Hence, $S = 0.196R = 0.196 \times 8 = 1.568$ inch.

Example 4: Sixteen bolts are to be equally spaced on the periphery of a bolt-circle, 250 millimeters diameter. Find the chordal distance between the bolts. Chordal distance equals the side S of a polygon with 16 sides. $R = 125$. Thus, $S = 0.3902R = 0.3902 \times 125 = 48.775$ millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Circular Segments.— The table that follows gives the principle formulas for dimensions of circular segments. The dimensions are illustrated in the figures on pages 66 and 71. When two of the dimensions found together in the first column are known, the other dimensions are found by using the formulas in the corresponding row. For example, if radius r and chord c are known, solve for angle α using Equation (13), then use Equations (14) and (15) to solve for h and l, respectively. In these formulas, the value of α is in degrees between 0 and 180°.

Formulas for Circular Segments

Given	Formulas		
α, r	$c = 2r\sin\frac{\alpha}{2}$ (1)	$h = r\left(1-\cos\frac{\alpha}{2}\right)$ (2)	$l = \frac{\pi r\alpha}{180}$ (3)
α, c	$r = \frac{c}{2\sin\alpha}$ (4)	$h = -\frac{c}{2}\tan\alpha$ (5)	$l = \frac{\pi c\alpha}{360\sin\frac{\alpha}{2}}$ (6)
α, h	$r = \frac{h}{1-\cos\frac{\alpha}{2}}$ (7)	$c = \frac{2h}{\tan\frac{\alpha}{4}}$ (8)	$l = \frac{\pi H\alpha}{180\left(1-\cos\frac{\alpha}{2}\right)}$ (9)
α, l	$r = \frac{180}{\pi}\frac{l}{\alpha}$ (10)	$c = \frac{360l\sin\frac{\alpha}{2}}{\pi\alpha}$ (11)	$h = \frac{180l\left(1-\cos\frac{\alpha}{2}\right)}{\pi\alpha}$ (12)
r, c	$\alpha = \operatorname{acos}\left(\frac{1-c^2}{2R^2}\right)$ (13)	$h = r - \frac{\sqrt{4r^2-c^2}}{2}$ (14)	$l = \frac{\pi}{90}r\operatorname{asin}\left(\frac{c}{2r}\right)$ (15)
r, h	$\alpha = 2\operatorname{acos}\left(1-\frac{h}{r}\right)$ (16)	$c = 2\sqrt{h(2r-h)}$ (17)	$l = \frac{\pi}{90}r\operatorname{acos}\left(1-\frac{h}{r}\right)$ (18)
r, l	$\alpha = \frac{180}{\pi}\frac{l}{r}$ (19)	$c = 2r\sin\frac{90l}{\pi R}$ (20)	$h = r\left(1-\cos\frac{90l}{\pi r}\right)$ (21)
c, h	$\alpha = 4\operatorname{atan}\frac{2h}{c}$ (22)	$r = \frac{c^2+4h^2}{8H}$ (23)	$l = \pi\left(\frac{c^2+4h^2}{360h}\right)\operatorname{atan}\frac{2h}{c}$ (24)

Given	Formula To Find	Given	Formula To Find
c, l	$\frac{360}{\pi}\frac{l}{c} = \frac{\alpha}{\sin\frac{\alpha}{2}}$ (25) Solve Equation (25) for α by iteration[a], then r = Equation (10) h = Equation (5)	h, l	$\frac{180}{\pi}\frac{l}{h} = \frac{\alpha}{1-\cos\frac{\alpha}{2}}$ (26) Solve Equation (26) for α by iteration[a], then r = Equation (10) c = Equation (11)

[a] Equations (25) and (26) can not be easily solved by ordinary means. To solve these equations, test various values of α until the left side of the equation equals the right side. For example, if given $c = 4$ and $l = 5$, the left side of Equation (25) equals 143.24, and by testing various values of α it will be found that the right side equals 143.24 when $\alpha = 129.62°$.

Angle α is in degrees, $0 < \alpha < 180$

Formulas for Circular Segments contributed by Manfred Brueckner

Copyright 2004, Industrial Press, Inc., New York, NY

Segments of Circles for Radius = 1.— Formulas for segments of circles are given on pages 66 and 70. When the central angle α and radius *r* are known, the tables on this and the following page can be used to find the length of arc *l*, height of segment *h*, chord length *c*, and segment area *A*.

When angle α and radius *r* are not known, but segment height *h* and chord length *c* are known or can be measured, the ratio *h*/*c* can be used to enter the table and find α, *l*, and *A* by linear interpolation. Radius *r* is found by the formula on page 66 or 70. The value of *l* is then multiplied by the radius *r* and the area *A* by r^2, the square of the radius.



Angle α can be found thus with an accuracy of about 0.001 degree; arc length *l* with an error of about 0.02 per cent; and area *A* with an error ranging from about 0.02 per cent for the highest entry value of *h*/*c* to about 1 per cent for values of *h*/*c* of about 0.050. For lower values of *h*/*c*, and where greater accuracy is required, area *A* should be found by the formula on page 66.

Segments of Circles for Radius = 1 (English or metric units)

θ, Deg.	*l*	*h*	*c*	*Area A*	*h*/*c*	θ, Deg.	*l*	*h*	*c*	*Area A*	*h*/*c*
1	0.01745	0.00004	0.01745	0.0000	0.00218	41	0.71558	0.06333	0.70041	0.0298	0.09041
2	0.03491	0.00015	0.03490	0.0000	0.00436	42	0.73304	0.06642	0.71674	0.0320	0.09267
3	0.05236	0.00034	0.05235	0.0000	0.00655	43	0.75049	0.06958	0.73300	0.0342	0.09493
4	0.06981	0.00061	0.06980	0.0000	0.00873	44	0.76794	0.07282	0.74921	0.0366	0.09719
5	0.08727	0.00095	0.08724	0.0001	0.01091	45	0.78540	0.07612	0.76537	0.0391	0.09946
6	0.10472	0.00137	0.10467	0.0001	0.01309	46	0.80285	0.07950	0.78146	0.0418	0.10173
7	0.12217	0.00187	0.12210	0.0002	0.01528	47	0.82030	0.08294	0.79750	0.0445	0.10400
8	0.13963	0.00244	0.13951	0.0002	0.01746	48	0.83776	0.08645	0.81347	0.0473	0.10628
9	0.15708	0.00308	0.15692	0.0003	0.01965	49	0.85521	0.09004	0.82939	0.0503	0.10856
10	0.17453	0.00381	0.17431	0.0004	0.02183	50	0.87266	0.09369	0.84524	0.0533	0.11085
11	0.19199	0.00460	0.19169	0.0006	0.02402	51	0.89012	0.09741	0.86102	0.0565	0.11314
12	0.20944	0.00548	0.20906	0.0008	0.02620	52	0.90757	0.10121	0.87674	0.0598	0.11543
13	0.22689	0.00643	0.22641	0.0010	0.02839	53	0.92502	0.10507	0.89240	0.0632	0.11773
14	0.24435	0.00745	0.24374	0.0012	0.03058	54	0.94248	0.10899	0.90798	0.0667	0.12004
15	0.26180	0.00856	0.26105	0.0015	0.03277	55	0.95993	0.11299	0.92350	0.0704	0.12235
16	0.27925	0.00973	0.27835	0.0018	0.03496	56	0.97738	0.11705	0.93894	0.0742	0.12466
17	0.29671	0.01098	0.29562	0.0022	0.03716	57	0.99484	0.12118	0.95432	0.0781	0.12698
18	0.31416	0.01231	0.31287	0.0026	0.03935	58	1.01229	0.12538	0.96962	0.0821	0.12931
19	0.33161	0.01371	0.33010	0.0030	0.04155	59	1.02974	0.12964	0.98485	0.0863	0.13164
20	0.34907	0.01519	0.34730	0.0035	0.04374	60	1.04720	0.13397	1.00000	0.0906	0.13397
21	0.36652	0.01675	0.36447	0.0041	0.04594	61	1.06465	0.13837	1.01508	0.0950	0.13632
22	0.38397	0.01837	0.38162	0.0047	0.04814	62	1.08210	0.14283	1.03008	0.0996	0.13866
23	0.40143	0.02008	0.39874	0.0053	0.05035	63	1.09956	0.14736	1.04500	0.1043	0.14101
24	0.41888	0.02185	0.41582	0.0061	0.05255	64	1.11701	0.15195	1.05984	0.1091	0.14337
25	0.43633	0.02370	0.43288	0.0069	0.05476	65	1.13446	0.15661	1.07460	0.1141	0.14574
26	0.45379	0.02563	0.44990	0.0077	0.05697	66	1.15192	0.16133	1.08928	0.1192	0.14811
27	0.47124	0.02763	0.46689	0.0086	0.05918	67	1.16937	0.16611	1.10387	0.1244	0.15048
28	0.48869	0.02970	0.48384	0.0096	0.06139	68	1.18682	0.17096	1.11839	0.1298	0.15287
29	0.50615	0.03185	0.50076	0.0107	0.06361	69	1.20428	0.17587	1.13281	0.1353	0.15525
30	0.52360	0.03407	0.51764	0.0118	0.06583	70	1.22173	0.18085	1.14715	0.1410	0.15765
31	0.54105	0.03637	0.53448	0.0130	0.06805	71	1.23918	0.18588	1.16141	0.1468	0.16005
32	0.55851	0.03874	0.55127	0.0143	0.07027	72	1.25664	0.19098	1.17557	0.1528	0.16246
33	0.57596	0.04118	0.56803	0.0157	0.07250	73	1.27409	0.19614	1.18965	0.1589	0.16488
34	0.59341	0.04370	0.58474	0.0171	0.07473	74	1.29154	0.20136	1.20363	0.1651	0.16730
35	0.61087	0.04628	0.60141	0.0186	0.07696	75	1.30900	0.20665	1.21752	0.1715	0.16973
36	0.62832	0.04894	0.61803	0.0203	0.07919	76	1.32645	0.21199	1.23132	0.1781	0.17216
37	0.64577	0.05168	0.63461	0.0220	0.08143	77	1.34390	0.21739	1.24503	0.1848	0.17461
38	0.66323	0.05448	0.65114	0.0238	0.08367	78	1.36136	0.22285	1.25864	0.1916	0.17706
39	0.68068	0.05736	0.66761	0.0257	0.08592	79	1.37881	0.22838	1.27216	0.1986	0.17952
40	0.69813	0.06031	0.68404	0.0277	0.08816	80	1.39626	0.23396	1.28558	0.2057	0.18199

Copyright 2004, Industrial Press, Inc., New York, NY

Segments of Circles for Radius = 1 (English or metric units) *(Continued)*

θ, Deg.	*l*	*h*	*c*	*Area A*	*h/c*	θ, Deg.	*l*	*h*	*c*	*Area A*	*h/c*
81	1.41372	0.23959	1.29890	0.2130	0.18446	131	2.28638	0.58531	1.81992	0.7658	0.32161
82	1.43117	0.24529	1.31212	0.2205	0.18694	132	2.30383	0.59326	1.82709	0.7803	0.32470
83	1.44862	0.25104	1.32524	0.2280	0.18943	133	2.32129	0.60125	1.83412	0.7950	0.32781
84	1.46608	0.25686	1.33826	0.2358	0.19193	134	2.33874	0.60927	1.84101	0.8097	0.33094
85	1.48353	0.26272	1.35118	0.2437	0.19444	135	2.35619	0.61732	1.84776	0.8245	0.33409
86	1.50098	0.26865	1.36400	0.2517	0.19696	136	2.37365	0.62539	1.85437	0.8395	0.33725
87	1.51844	0.27463	1.37671	0.2599	0.19948	137	2.39110	0.63350	1.86084	0.8546	0.34044
88	1.53589	0.28066	1.38932	0.2682	0.20201	138	2.40855	0.64163	1.86716	0.8697	0.34364
89	1.55334	0.28675	1.40182	0.2767	0.20456	139	2.42601	0.64979	1.87334	0.8850	0.34686
90	1.57080	0.29289	1.41421	0.2854	0.20711	140	2.44346	0.65798	1.87939	0.9003	0.35010
91	1.58825	0.29909	1.42650	0.2942	0.20967	141	2.46091	0.66619	1.88528	0.9158	0.35337
92	1.60570	0.30534	1.43868	0.3032	0.21224	142	2.47837	0.67443	1.89104	0.9314	0.35665
93	1.62316	0.31165	1.45075	0.3123	0.21482	143	2.49582	0.68270	1.89665	0.9470	0.35995
94	1.64061	0.31800	1.46271	0.3215	0.21741	144	2.51327	0.69098	1.90211	0.9627	0.36327
95	1.65806	0.32441	1.47455	0.3309	0.22001	145	2.53073	0.69929	1.90743	0.9786	0.36662
96	1.67552	0.33087	1.48629	0.3405	0.22261	146	2.54818	0.70763	1.91261	0.9945	0.36998
97	1.69297	0.33738	1.49791	0.3502	0.22523	147	2.56563	0.71598	1.91764	1.0105	0.37337
98	1.71042	0.34394	1.50942	0.3601	0.22786	148	2.58309	0.72436	1.92252	1.0266	0.37678
99	1.72788	0.35055	1.52081	0.3701	0.23050	149	2.60054	0.73276	1.92726	1.0428	0.38021
100	1.74533	0.35721	1.53209	0.3803	0.23315	150	2.61799	0.74118	1.93185	1.0590	0.38366
101	1.76278	0.36392	1.54325	0.3906	0.23582	151	2.63545	0.74962	1.93630	1.0753	0.38714
102	1.78024	0.37068	1.55429	0.4010	0.23849	152	2.65290	0.75808	1.94059	1.0917	0.39064
103	1.79769	0.37749	1.56522	0.4117	0.24117	153	2.67035	0.76655	1.94474	1.1082	0.39417
104	1.81514	0.38434	1.57602	0.4224	0.24387	154	2.68781	0.77505	1.94874	1.1247	0.39772
105	1.83260	0.39124	1.58671	0.4333	0.24657	155	2.70526	0.78356	1.95259	1.1413	0.40129
106	1.85005	0.39818	1.59727	0.4444	0.24929	156	2.72271	0.79209	1.95630	1.1580	0.40489
107	1.86750	0.40518	1.60771	0.4556	0.25202	157	2.74017	0.80063	1.95985	1.1747	0.40852
108	1.88496	0.41221	1.61803	0.4669	0.25476	158	2.75762	0.80919	1.96325	1.1915	0.41217
109	1.90241	0.41930	1.62823	0.4784	0.25752	159	2.77507	0.81776	1.96651	1.2084	0.41585
110	1.91986	0.42642	1.63830	0.4901	0.26028	160	2.79253	0.82635	1.96962	1.2253	0.41955
111	1.93732	0.43359	1.64825	0.5019	0.26306	161	2.80998	0.83495	1.97257	1.2422	0.42328
112	1.95477	0.44081	1.65808	0.5138	0.26585	162	2.82743	0.84357	1.97538	1.2592	0.42704
113	1.97222	0.44806	1.66777	0.5259	0.26866	163	2.84489	0.85219	1.97803	1.2763	0.43083
114	1.98968	0.45536	1.67734	0.5381	0.27148	164	2.86234	0.86083	1.98054	1.2934	0.43464
115	2.00713	0.46270	1.68678	0.5504	0.27431	165	2.87979	0.86947	1.98289	1.3105	0.43849
116	2.02458	0.47008	1.69610	0.5629	0.27715	166	2.89725	0.87813	1.98509	1.3277	0.44236
117	2.04204	0.47750	1.70528	0.5755	0.28001	167	2.91470	0.88680	1.98714	1.3449	0.44627
118	2.05949	0.48496	1.71433	0.5883	0.28289	168	2.93215	0.89547	1.98904	1.3621	0.45020
119	2.07694	0.49246	1.72326	0.6012	0.28577	169	2.94961	0.90415	1.99079	1.3794	0.45417
120	2.09440	0.50000	1.73205	0.6142	0.28868	170	2.96706	0.91284	1.99239	1.3967	0.45817
121	2.11185	0.50758	1.74071	0.6273	0.29159	171	2.98451	0.92154	1.99383	1.4140	0.46220
122	2.12930	0.51519	1.74924	0.6406	0.29452	172	3.00197	0.93024	1.99513	1.4314	0.46626
123	2.14675	0.52284	1.75763	0.6540	0.29747	173	3.01942	0.93895	1.99627	1.4488	0.47035
124	2.16421	0.53053	1.76590	0.6676	0.30043	174	3.03687	0.94766	1.99726	1.4662	0.47448
125	2.18166	0.53825	1.77402	0.6813	0.30341	175	3.05433	0.95638	1.99810	1.4836	0.47865
126	2.19911	0.54601	1.78201	0.6950	0.30640	176	3.07178	0.96510	1.99878	1.5010	0.48284
127	2.21657	0.55380	1.78987	0.7090	0.30941	177	3.08923	0.97382	1.99931	1.5184	0.48708
128	2.23402	0.56163	1.79759	0.7230	0.31243	178	3.10669	0.98255	1.99970	1.5359	0.49135
129	2.25147	0.56949	1.80517	0.7372	0.31548	179	3.12414	0.99127	1.99992	1.5533	0.49566
130	2.26893	0.57738	1.81262	0.7514	0.31854	180	3.14159	1.00000	2.00000	1.5708	0.50000

Copyright 2004, Industrial Press, Inc., New York, NY

Diameters of Circles and Sides of Squares of Equal Area



The table below will be found useful for determining the diameter of a circle of an area equal to that of a square, the side of which is known, or for determining the side of a square which has an area equal to that of a circle, the area or diameter of which is known. For example, if the diameter of a circle is 17½ inches, it is found from the table that the side of a square of the same area is 15.51 inches.

Diam. of Circle, *D*	Side of Square, *S*	Area of Circle or Square	Diam. of Circle, *D*	Side of Square, *S*	Area of Circle or Square	Diam. of Circle, *D*	Side of Square, *S*	Area of Circle or Square
½	0.44	0.196	20½	18.17	330.06	40½	35.89	1288.25
1	0.89	0.785	21	18.61	346.36	41	36.34	1320.25
1½	1.33	1.767	21½	19.05	363.05	41½	36.78	1352.65
2	1.77	3.142	22	19.50	380.13	42	37.22	1385.44
2½	2.22	4.909	22½	19.94	397.61	42½	37.66	1418.63
3	2.66	7.069	23	20.38	415.48	43	38.11	1452.20
3½	3.10	9.621	23½	20.83	433.74	43½	38.55	1486.17
4	3.54	12.566	24	21.27	452.39	44	38.99	1520.53
4½	3.99	15.904	24½	21.71	471.44	44½	39.44	1555.28
5	4.43	19.635	25	22.16	490.87	45	39.88	1590.43
5½	4.87	23.758	25½	22.60	510.71	45½	40.32	1625.97
6	5.32	28.274	26	23.04	530.93	46	40.77	1661.90
6½	5.76	33.183	26½	23.49	551.55	46½	41.21	1698.23
7	6.20	38.485	27	23.93	572.56	47	41.65	1734.94
7½	6.65	44.179	27½	24.37	593.96	47½	42.10	1772.05
8	7.09	50.265	28	24.81	615.75	48	42.54	1809.56
8½	7.53	56.745	28½	25.26	637.94	48½	42.98	1847.45
9	7.98	63.617	29	25.70	660.52	49	43.43	1885.74
9½	8.42	70.882	29½	26.14	683.49	49½	43.87	1924.42
10	8.86	78.540	30	26.59	706.86	50	44.31	1963.50
10½	9.31	86.590	30½	27.03	730.62	50½	44.75	2002.96
11	9.75	95.033	31	27.47	754.77	51	45.20	2042.82
11½	10.19	103.87	31½	27.92	779.31	51½	45.64	2083.07
12	10.63	113.10	32	28.36	804.25	52	46.08	2123.72
12½	11.08	122.72	32½	28.80	829.58	52½	46.53	2164.75
13	11.52	132.73	33	29.25	855.30	53	46.97	2206.18
13½	11.96	143.14	33½	29.69	881.41	53½	47.41	2248.01
14	12.41	153.94	34	30.13	907.92	54	47.86	2290.22
14½	12.85	165.13	34½	30.57	934.82	54½	48.30	2332.83
15	13.29	176.71	35	31.02	962.11	55	48.74	2375.83
15½	13.74	188.69	35½	31.46	989.80	55½	49.19	2419.22
16	14.18	201.06	36	31.90	1017.88	56	49.63	2463.01
16½	14.62	213.82	36½	32.35	1046.35	56½	50.07	2507.19
17	15.07	226.98	37	32.79	1075.21	57	50.51	2551.76
17½	15.51	240.53	37½	33.23	1104.47	57½	50.96	2596.72
18	15.95	254.47	38	33.68	1134.11	58	51.40	2642.08
18½	16.40	268.80	38½	34.12	1164.16	58½	51.84	2687.83
19	16.84	283.53	39	34.56	1194.59	59	52.29	2733.97
19½	17.28	298.65	39½	35.01	1225.42	59½	52.73	2780.51
20	17.72	314.16	40	35.45	1256.64	60	53.17	2827.43

Copyright 2004, Industrial Press, Inc., New York, NY

Distance Across Corners of Squares and Hexagons.— The table below gives values of dimensions *D* and *E* described in the figures and equations that follow.



$$D = \frac{2\sqrt{3}}{3}d = 1.154701d$$

$$E = d\sqrt{2} = 1.414214d$$

A desired value not given directly in the table can be obtained directly from the equations above, or by the simple addition of two or more values taken directly from the table. Further values can be obtained by shifting the decimal point.

Example 1: Find *D* when $d = 2\ 5/16$ inches. From the table, 2 = 2.3094, and 5/16 = 0.3608. Therefore, D = 2.3094 + 0.3608 = 2.6702 inches.

Example 2: Find *E* when *d* = 20.25 millimeters. From the table, 20 = 28.2843; 0.2 = 0.2828; and 0.05 = 0.0707 (obtained by shifting the decimal point one place to the left at *d* = 0.5). Thus, *E* = 28.2843 + 0.2828 + 0.0707 = 28.6378 millimeters.

Distance Across Corners of Squares and Hexagons (English and metric units)

d	*D*	*E*	*d*	*D*	*E*	*d*	*D*	*E*	*d*	*D*	*E*
1/32	0.0361	0.0442	0.9	1.0392	1.2728	32	36.9504	45.2548	67	77.3650	94.7523
1/16	0.0722	0.0884	29/32	1.0464	1.2816	33	38.1051	46.6691	68	78.5197	96.1666
3/32	0.1083	0.1326	15/16	1.0825	1.3258	34	39.2598	48.0833	69	79.6744	97.5808
0.1	0.1155	0.1414	31/32	1.1186	1.3700	35	40.4145	49.4975	70	80.8291	98.9950
1/8	0.1443	0.1768	1.0	1.1547	1.4142	36	41.5692	50.9117	71	81.9838	100.409
5/32	0.1804	0.2210	2.0	2.3094	2.8284	37	42.7239	52.3259	72	83.1385	101.823
3/16	0.2165	0.2652	3.0	3.4641	4.2426	38	43.8786	53.7401	73	84.2932	103.238
0.2	0.2309	0.2828	4.0	4.6188	5.6569	39	45.0333	55.1543	74	85.4479	104.652
7/32	0.2526	0.3094	5.0	5.7735	7.0711	40	46.1880	56.5686	75	86.6026	106.066
1/4	0.2887	0.3536	6.0	6.9282	8.4853	41	47.3427	57.9828	76	87.7573	107.480
9/32	0.3248	0.3977	7.0	8.0829	9.8995	42	48.4974	59.3970	77	88.9120	108.894
0.3	0.3464	0.4243	8.0	9.2376	11.3137	43	49.6521	60.8112	78	90.0667	110.309
5/16	0.3608	0.4419	9.0	10.3923	12.7279	44	50.8068	62.2254	79	91.2214	111.723
11/32	0.3969	0.4861	10	11.5470	14.1421	45	51.9615	63.6396	80	92.3761	113.137
3/8	0.4330	0.5303	11	12.7017	15.5564	46	53.1162	65.0538	81	93.5308	114.551
0.4	0.4619	0.5657	12	13.8564	16.9706	47	54.2709	66.4681	82	94.6855	115.966
13/32	0.4691	0.5745	13	15.0111	18.3848	48	55.4256	67.8823	83	95.8402	117.380
7/16	0.5052	0.6187	14	16.1658	19.7990	49	56.5803	69.2965	84	96.9949	118.794
15/32	0.5413	0.6629	15	17.3205	21.2132	50	57.7351	70.7107	85	98.1496	120.208
0.5	0.5774	0.7071	16	18.4752	22.6274	51	58.8898	72.1249	86	99.3043	121.622
17/32	0.6134	0.7513	17	19.6299	24.0416	52	60.0445	73.5391	87	100.459	123.037
9/16	0.6495	0.7955	18	20.7846	25.4559	53	61.1992	74.9533	88	101.614	124.451
19/32	0.6856	0.8397	19	21.9393	26.8701	54	62.3539	76.3676	89	102.768	125.865
0.6	0.6928	0.8485	20	23.0940	28.2843	55	63.5086	77.7818	90	103.923	127.279
5/8	0.7217	0.8839	21	24.2487	29.6985	56	64.6633	79.1960	91	105.078	128.693
21/32	0.7578	0.9281	22	25.4034	31.1127	57	65.8180	80.6102	92	106.232	130.108
11/16	0.7939	0.9723	23	26.5581	32.5269	58	66.9727	82.0244	93	107.387	131.522
0.7	0.8083	0.9899	24	27.7128	33.9411	59	68.1274	83.4386	94	108.542	132.936
23/32	0.8299	1.0165	25	28.8675	35.3554	60	69.2821	84.8528	95	109.697	134.350
3/4	0.8660	1.0607	26	30.0222	36.7696	61	70.4368	86.2671	96	110.851	135.765
25/32	0.9021	1.1049	27	31.1769	38.1838	62	71.5915	87.6813	97	112.006	137.179
0.8	0.9238	1.1314	28	32.3316	39.5980	63	72.7462	89.0955	98	113.161	138.593
13/16	0.9382	1.1490	29	33.4863	41.0122	64	73.9009	90.5097	99	114.315	140.007
27/32	0.9743	1.1932	30	34.6410	42.4264	65	75.0556	91.9239	100	115.470	141.421
7/8	1.0104	1.2374	31	35.7957	43.8406	66	76.2103	93.3381	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Volumes of Solids

Cube:



$$\text{Diagonal of cube face} = d = s\sqrt{2}$$

$$\text{Diagonal of cube} = D = \sqrt{\frac{3d^2}{2}} = s\sqrt{3} = 1.732s$$

$$\text{Volume} = V = s^3$$

$$s = \sqrt[3]{V}$$

Example: The side of a cube equals 9.5 centimeters. Find its volume.

$$\text{Volume} = V = s^3 = 9.5^3 = 9.5 \times 9.5 \times 9.5 = 857.375 \text{ cubic centimeters}$$

Example: The volume of a cube is 231 cubic centimeters. What is the length of the side?

$$s = \sqrt[3]{V} = \sqrt[3]{231} = 6.136 \text{ centimeters}$$

Square Prism:



$$\text{Volume} = V = abc$$

$$a = \frac{V}{bc} \qquad b = \frac{V}{ac} \qquad c = \frac{V}{ab}$$

Example: In a square prism, $a = 6, b = 5, c = 4$. Find the volume.

$$V = a \times b \times c = 6 \times 5 \times 4 = 120 \text{ cubic inches}$$

Example: How high should a box be made to contain 25 cubic feet, if it is 4 feet long and 2½ feet wide? Here, $a = 4$, $c = 2.5$, and $V = 25$. Then,

$$b = \text{depth} = \frac{V}{ac} = \frac{25}{4 \times 2.5} = \frac{25}{10} = 2.5 \text{ feet}$$

Prism:



V = volume
A = area of end surface
$V = h \times A$

The area A of the end surface is found by the formulas for areas of plane figures on the preceding pages. Height h must be measured perpendicular to the end surface.

Example: A prism, having for its base a regular hexagon with a side s of 7.5 centimeters, is 25 centimeters high. Find the volume.

$$\text{Area of hexagon} = A = 2.598s^2 = 2.598 \times 56.25 = 146.14 \text{ square centimeters}$$

$$\text{Volume of prism} = h \times A = 25 \times 146.14 = 3653.5 \text{ cubic centimeters}$$

Pyramid:



$$\text{Volume} = V = \tfrac{1}{3}h \times \text{area of base}$$

If the base is a regular polygon with n sides, and s = length of side, r = radius of inscribed circle, and R = radius of circumscribed circle, then:

$$V = \frac{nsrh}{6} = \frac{nsh}{6}\sqrt{R^2 - \frac{s^2}{4}}$$

Example: A pyramid, having a height of 9 feet, has a base formed by a rectangle, the sides of which are 2 and 3 feet, respectively. Find the volume.

$$\text{Area of base} = 2 \times 3 = 6 \text{ square feet; } h = 9 \text{ feet}$$

$$\text{Volume} = V = \tfrac{1}{3}h \times \text{area of base} = \tfrac{1}{3} \times 9 \times 6 = 18 \text{ cubic feet}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Frustum of Pyramid:



$$\text{Volume} = V = \frac{h}{3}(A_1 + A_2 + \sqrt{A_1 \times A_2})$$

Example: The pyramid in the previous example is cut off 4½ feet from the base, the upper part being removed. The sides of the rectangle forming the top surface of the frustum are, then, 1 and 1½ feet long, respectively. Find the volume of the frustum.

Area of top $= A_1 = 1 \times 1\frac{1}{2} = 1\frac{1}{2}$ sq. ft. Area of base $= A_2 = 2 \times 3 = 6$ sq. ft.

$$V = \frac{4 \cdot 5}{3}(1.5 + 6 + \sqrt{1.5 \times 6}) = 1.5(7.5 + \sqrt{9}) = 1.5 \times 10.5 = 15.75 \text{ cubic feet}$$

Wedge:



$$\text{Volume} = V = \frac{(2a + c)bh}{6}$$

Example: Let $a = 4$ inches, $b = 3$ inches, and $c = 5$ inches. The height $h = 4.5$ inches. Find the volume.

$$V = \frac{(2a + c)bh}{6} = \frac{(2 \times 4 + 5) \times 3 \times 4.5}{6} = \frac{(8 + 5) \times 13.5}{6}$$

$$= \frac{175.5}{6} = 29.25 \text{ cubic inches}$$

Cylinder:



$$\text{Volume} = V = 3.1416r^2h = 0.7854d^2h$$

$$\text{Area of cylindrical surface} = S = 6.2832rh = 3.1416dh$$

Total area A of cylindrical surface and end surfaces:

$$A = 6.2832r(r + h) = 3.1416d(\tfrac{1}{2}d + h)$$

Example: The diameter of a cylinder is 2.5 inches. The length or height is 20 inches. Find the volume and the area of the cylindrical surface S.

$$V = 0.7854d^2h = 0.7854 \times 2.5^2 \times 20 = 0.7854 \times 6.25 \times 20 = 98.17 \text{ cubic inches}$$

$$S = 3.1416dh = 3.1416 \times 2.5 \times 20 = 157.08 \text{ square inches}$$

Portion of Cylinder:



$$\text{Volume} = V = 1.5708r^2(h_1 + h_2)$$

$$= 0.3927d^2(h_1 + h_2)$$

$$\text{Cylindrical surface area} = S = 3.1416r(h_1 + h_2)$$

$$= 1.5708d(h_1 + h_2)$$

Example: A cylinder 125 millimeters in diameter is cut off at an angle, as shown in the illustration. Dimension $h_1 = 150$, and $h_2 = 100$ mm. Find the volume and the area S of the cylindrical surface.

$$V = 0.3927d^2(h_1 + h_2) = 0.3927 \times 125^2 \times (150 + 100)$$

$$= 0.3927 \times 15{,}625 \times 250 = 1{,}533{,}984 \text{ cubic millimeters} = 1534 \text{ cm}^3$$

$$S = 1.5708d(h_1 + h_2) = 1.5708 \times 125 \times 250$$

$$= 49{,}087.5 \text{ square millimeters} = 490.9 \text{ square centimeters}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Portion of Cylinder:



$$\text{Volume} = V = (\tfrac{2}{3}a^3 \pm b \times \text{area ABC})\frac{h}{r \pm b}$$

$$\text{Cylindrical surface area} = S = (ad \pm b \times \text{length of arc ABC})\frac{h}{r \pm b}$$

Use + when base area is larger, and – when base area is less than one-half the base circle.

Example: Find the volume of a cylinder so cut off that line *AC* passes through the center of the base circle — that is, the base area is a half-circle. The diameter of the cylinder = 5 inches, and the height h = 2 inches.

In this case, $a = 2.5$; $b = 0$; area $ABC = 0.5 \times 0.7854 \times 5^2 = 9.82$; $r = 2.5$.

$$V = \left(\frac{2}{3} \times 2.5^3 + 0 \times 9.82\right)\frac{2}{2.5 + 0} = \frac{2}{3} \times 15.625 \times 0.8 = 8.33 \text{ cubic inches}$$

Hollow Cylinder:



$$\begin{aligned}\text{Volume} = V &= 3.1416h(R^2 - r^2) = 0.7854h(D^2 - d^2)\\ &= 3.1416ht(2R - t) = 3.1416ht(D - t)\\ &= 3.1416ht(2r + t) = 3.1416ht(d + t)\\ &= 3.1416ht(R + r) = 1.5708ht(D + d)\end{aligned}$$

Example: A cylindrical shell, 28 centimeters high, is 36 centimeters in outside diameter, and 4 centimeters thick. Find its volume.

$$\begin{aligned}V &= 3.1416ht(D - t) = 3.1416 \times 28 \times 4(36 - 4) = 3.1416 \times 28 \times 4 \times 32\\ &= 11{,}259.5 \text{ cubic centimeters}\end{aligned}$$

Cone:



$$\text{Volume} = V = \frac{3.1416r^2h}{3} = 1.0472r^2h = 0.2618d^2h$$

$$\text{Conical surface area} = A = 3.1416r\sqrt{r^2 + h^2} = 3.1416rs = 1.5708ds$$

$$s = \sqrt{r^2 + h^2} = \sqrt{\frac{d^2}{4} + h^2}$$

Example: Find the volume and area of the conical surface of a cone, the base of which is a circle of 6 inches diameter, and the height of which is 4 inches.

$$V = 0.2618d^2h = 0.2618 \times 6^2 \times 4 = 0.2618 \times 36 \times 4 = 37.7 \text{ cubic inches}$$

$$A = 3.1416r\sqrt{r^2 + h^2} = 3.1416 \times 3 \times \sqrt{3^2 + 4^2} = 9.4248 \times \sqrt{25}$$
$$= 47.124 \text{ square inches}$$

Frustum of Cone:



V = volume A = area of conical surface

$$V = 1.0472h(R^2 + Rr + r^2) = 0.2618h(D^2 + Dd + d^2)$$

$$A = 3.1416s(R + r) = 1.5708s(D + d)$$

$$a = R - r \qquad s = \sqrt{a^2 + h^2} = \sqrt{(R - r)^2 + h^2}$$

Example: Find the volume of a frustum of a cone of the following dimensions: D = 8 centimeters; d = 4 centimeters; h = 5 centimeters.

$$\begin{aligned}V &= 0.2618 \times 5(8^2 + 8 \times 4 + 4^2) = 0.2618 \times 5(64 + 32 + 16)\\ &= 0.2618 \times 5 \times 112 = 146.61 \text{ cubic centimeters}\end{aligned}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Sphere:



$$\text{Volume} = V = \frac{4\pi r^3}{3} = \frac{\pi d^3}{6} = 4.1888r^3 = 0.5236d^3$$

$$\text{Surface area} = A = 4\pi r^2 = \pi d^2 = 12.5664r^2 = 3.1416d^2$$

$$r = \sqrt[3]{\frac{3V}{4\pi}} = 0.6024\sqrt[3]{V}$$

Example: Find the volume and the surface of a sphere 6.5 centimeters diameter.

$$V = 0.5236d^3 = 0.5236 \times 6.5^3 = 0.5236 \times 6.5 \times 6.5 \times 6.5 = 143.79 \text{ cm}^3$$

$$A = 3.1416d^2 = 3.1416 \times 6.5^2 = 3.1416 \times 6.5 \times 6.5 = 132.73 \text{ cm}^2$$

Example: The volume of a sphere is 64 cubic centimeters. Find its radius.

$$r = 0.6204\sqrt[3]{64} = 0.6204 \times 4 = 2.4816 \text{ centimeters}$$

Spherical Sector:



$$V = \frac{2\pi r^2 h}{3} = 2.0944r^2h = \text{Volume}$$

$$A = 3.1416r(2h + \tfrac{1}{2}c)$$

$$= \text{total area of conical and spherical surface}$$

$$c = 2\sqrt{h(2r-h)}$$

Example: Find the volume of a sector of a sphere 6 inches in diameter, the height h of the sector being 1.5 inch. Also find the length of chord c. Here $r = 3$ and $h = 1.5$.

$$V = 2.0944r^2h = 2.0944 \times 3^2 \times 1.5 = 2.0944 \times 9 \times 1.5 = 28.27 \text{ cubic inches}$$

$$c = 2\sqrt{h(2r-h)} = 2\sqrt{1.5(2 \times 3 - 1.5)} = 2\sqrt{6.75} = 2 \times 2.598 = 5.196 \text{ inches}$$

Spherical Segment:



V = volume A = area of spherical surface

$$V = 3.1416h^2\left(r - \frac{h}{3}\right) = 3.1416h\left(\frac{c^2}{8} + \frac{h^2}{6}\right)$$

$$A = 2\pi rh = 6.2832rh = 3.1416\left(\frac{c^2}{4} + h^2\right)$$

$$c = 2\sqrt{h(2r-h)}; \qquad r = \frac{c^2 + 4h^2}{8h}$$

Example: A segment of a sphere has the following dimensions: $h = 50$ millimeters; $c = 125$ millimeters. Find the volume V and the radius of the sphere of which the segment is a part.

$$V = 3.1416 \times 50 \times \left(\frac{125^2}{8} + \frac{50^2}{6}\right) = 157.08 \times \left(\frac{15{,}625}{8} + \frac{2500}{6}\right) = 372{,}247 \text{ mm}^3 = 372 \text{ cm}^3$$

$$r = \frac{125^2 + 4 \times 50^2}{8 \times 50} = \frac{15{,}625 + 10{,}000}{400} = \frac{25{,}625}{400} = 64 \text{ millimeters}$$

Ellipsoid:



$$\text{Volume} = V = \frac{4\pi}{3}abc = 4.1888abc$$

In an ellipsoid of revolution, or spheroid, where $c = b$:

$$V = 4.1888ab^2$$

Example: Find the volume of a spheroid in which $a = 5$, and $b = c = 1.5$ inches.

$$V = 4.1888 \times 5 \times 1.5^2 = 47.124 \text{ cubic inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Spherical Zone:



$$\text{Volume} = V = 0.5236h\left(\frac{3c_1^2}{4} + \frac{3c_2^2}{4} + h^2\right)$$

$$A = 2\pi rh = 6.2832rh = \text{area of spherical surface}$$

$$r = \sqrt{\frac{c_2^2}{4} + \left(\frac{c_2^2 - c_1^2 - 4h^2}{8h}\right)^2}$$

Example: In a spherical zone, let $c_1 = 3$; $c_2 = 4$; and $h = 1.5$ inch. Find the volume.

$$V = 0.5236 \times 1.5 \times \left(\frac{3 \times 3^2}{4} + \frac{3 \times 4^2}{4} + 1.5^2\right) = 0.5236 \times 1.5 \times \left(\frac{27}{4} + \frac{48}{4} + 2.25\right) = 16.493 \text{ in}^3$$

Spherical Wedge:



V = volume A = area of spherical surface

α = center angle in degrees

$$V = \frac{\alpha}{360} \times \frac{4\pi r^3}{3} = 0.0116\alpha r^3$$

$$A = \frac{\alpha}{360} \times 4\pi r^2 = 0.0349\alpha r^2$$

Example: Find the area of the spherical surface and the volume of a wedge of a sphere. The diameter of the sphere is 100 millimeters, and the center angle α is 45 degrees.

$$V = 0.0116 \times 45 \times 50^3 = 0.0116 \times 45 \times 125{,}000 = 65{,}250 \text{ mm}^3 = 65.25 \text{ cm}^3$$

$$A = 0.0349 \times 45 \times 50^2 = 3926.25 \text{ square millimeters} = 39.26 \text{ cm}^2$$

Hollow Sphere:



V = volume of material used to make a hollow sphere

$$V = \frac{4\pi}{3}(R^3 - r^3) = 4.1888(R^3 - r^3)$$

$$= \frac{\pi}{6}(D^3 - d^3) = 0.5236(D^3 - d^3)$$

Example: Find the volume of a hollow sphere, 8 inches in outside diameter, with a thickness of material of 1.5 inch.

Here $R = 4$; $r = 4 - 1.5 = 2.5$.

$$V = 4.1888(4^3 - 2.5^3) = 4.1888(64 - 15.625) = 4.1888 \times 48.375 = 202.63 \text{ cubic inches}$$

Paraboloid:



$$\text{Volume} = V = \tfrac{1}{2}\pi r^2 h = 0.3927d^2h$$

$$\text{Area} = A = \frac{2\pi}{3p}\left[\sqrt{\left(\frac{d^2}{4} + p^2\right)^3} - p^3\right]$$

$$\text{in which } p = \frac{d^2}{8h}$$

Example: Find the volume of a paraboloid in which $h = 300$ millimeters and $d = 125$ millimeters.

$$V = 0.3927d^2h = 0.3927 \times 125^2 \times 300 = 1{,}840{,}781 \text{ mm}^3 = 1{,}840.8 \text{ cm}^3$$

Copyright 2004, Industrial Press, Inc., New York, NY

Paraboloidal Segment:



$$\text{Volume} = V = \frac{\pi}{2}h(R^2 + r^2) = 1.5708h(R^2 + r^2)$$

$$= \frac{\pi}{8}h(D^2 + d^2) = 0.3927h(D^2 + d^2)$$

Example: Find the volume of a segment of a paraboloid in which $D = 5$ inches, $d = 3$ inches, and $h = 6$ inches.

$$V = 0.3927h(D^2 + d^2) = 0.3927 \times 6 \times (5^2 + 3^2)$$

$$= 0.3927 \times 6 \times 34 = 80.11 \text{ cubic inches}$$

Torus:



$$\text{Volume} = V = 2\pi^2 Rr^2 = 19.739Rr^2$$

$$= \frac{\pi^2}{4}Dd^2 = 2.4674Dd^2$$

$$\text{Area of surface} = A = 4\pi^2 Rr = 39.478Rr$$

$$= \pi^2 Dd = 9.8696Dd$$

Example: Find the volume and area of surface of a torus in which $d = 1.5$ and $D = 5$ inches.

$$V = 2.4674 \times 5 \times 1.5^2 = 2.4674 \times 5 \times 2.25 = 27.76 \text{ cubic inches}$$

$$A = 9.8696 \times 5 \times 1.5 = 74.022 \text{ square inches}$$

Barrel:



V = approximate volume.

If the sides are bent to the arc of a circle:

$$V = \frac{1}{12}\pi h(2D^2 + d^2) = 0.262h(2D^2 + d^2)$$

If the sides are bent to the arc of a parabola:

$$V = 0.209h(2D^2 + Dd + \tfrac{3}{4}d^2)$$

Example: Find the approximate contents of a barrel, the inside dimensions of which are $D = 60$ centimeters, $d = 50$ centimeters; $h = 120$ centimeters.

$$V = 0.262h(2D^2 + d^2) = 0.262 \times 120 \times (2 \times 60^2 + 50^2)$$

$$= 0.262 \times 120 \times (7200 + 2500) = 0.262 \times 120 \times 9700$$

$$= 304{,}968 \text{ cubic centimeters} = 0.305 \text{ cubic meter}$$

Ratio of Volumes:



If d = base diameter and height of a cone, a paraboloid and a cylinder, and the diameter of a sphere, then the volumes of these bodies are to each other as follows:

$$\text{Cone : paraboloid : sphere : cylinder} = \tfrac{1}{3} : \tfrac{1}{2} : \tfrac{2}{3} : 1$$

Example: Assume, as an example, that the diameter of the base of a cone, paraboloid, and cylinder is 2 inches, that the height is 2 inches, and that the diameter of a sphere is 2 inches. Then the volumes, written in formula form, are as follows:

$$\underset{\frac{3.1416 \times 2^2 \times 2}{12}}{\text{Cone}} : \underset{\frac{3.1416 \times (2p)^2 \times 2}{8}}{\text{Paraboloid}} : \underset{\frac{3.1416 \times 2^3}{6}}{\text{Sphere}} : \underset{\frac{3.1416 \times 2^2 \times 2}{4}}{\text{Cylinder}} = \tfrac{1}{3} : \tfrac{1}{2} : \tfrac{2}{3} : 1$$

Copyright 2004, Industrial Press, Inc., New York, NY

Packing Circles in Circles and Rectangles

Diameter of Circle Enclosing a Given Number of Smaller Circles.— Four of many possible compact arrangements of circles within a circle are shown at A, B, C, and D in Fig. 1. To determine the diameter of the smallest enclosing circle for a particular number of enclosed circles all of the same size, three factors that influence the size of the enclosing circle should be considered. These are discussed in the paragraphs that follow, which are based on the article "How Many Wires Can Be Packed into a Circular Conduit," by Jacques Dutka, *Machinery*, October 1956.

1) *Arrangement of Center or Core Circles:* The four most common arrangements of center or core circles are shown cross-sectioned in Fig. 1. It may seem, offhand, that the "A" pattern would require the smallest enclosing circle for a given number of enclosed circles but this is not always the case since the most compact arrangement will, in part, depend on the number of circles to be enclosed.



Fig. 1. Arrangements of Circles within a Circle

2) *Diameter of Enclosing Circle When Outer Layer of Circles Is Complete:* Successive, complete "layers" of circles may be placed around each of the central cores, Fig. 1, of 1, 2, 3, or 4 circles as the case may be. The number of circles contained in arrangements of complete "layers" around a central core of circles, as well as the diameter of the enclosing circle, may be obtained using the data in Table 1. Thus, for example, the "A" pattern in Fig. 1 shows, by actual count, a total of 19 circles arranged in two complete "layers" around a central core consisting of one circle; this agrees with the data shown in the left half of Table 1 for $n = 2$.

To determine the diameter of the enclosing circle, the data in the right half of Table 1 is used. Thus, for $n = 2$ and an "A" pattern, the diameter D is 5 times the diameter d of the enclosed circles.

3) *Diameter of Enclosing Circle When Outer Layer of Circles Is Not Complete:* In most cases, it is possible to reduce the size of the enclosing circle from that required if the outer layer were complete. Thus, for example, the "B" pattern in Fig. 1 shows that the central core consisting of 2 circles is surrounded by 1 complete layer of 8 circles and 1 partial, outer layer of 4 circles, so that the total number of circles enclosed is 14. If the outer layer were complete, then (from Table 1) the total number of enclosed circles would be 24 and the diameter of the enclosing circle would be $6d$; however, since the outer layer is composed of only 4 circles out of a possible 14 for a complete second layer, a smaller diameter of enclosing circle may be used. Table 2 shows that for a total of 14 enclosed circles arranged in a "B" pattern with the outer layer of circles incomplete, the diameter for the enclosing circle is $4.606d$.

Table 2 can be used to determine the smallest enclosing circle for a given number of circles to be enclosed by direct comparison of the "A," "B," and "C" columns. For data outside the range of Table 2, use the formulas in Dr. Dutka's article.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Number of Circles Contained in Complete Layers of Circles and Diameter of Enclosing Circle (English or metric units)

No. Complete Layers Over Core, n	Number of Circles in Center Pattern							
	1	2	3	4	1	2	3	4
	Arrangement of Circles in Center Pattern (see Fig. 1)							
	"A"	"B"	"C"	"D"	"A"	"B"	"C"	"D"
	Number of Circles, N, Enclosed				Diameter, D, of Enclosing Circle[a]			
0	1	2	3	4	d	$2d$	$2.155d$	$2.414d$
1	7	10	12	14	$3d$	$4d$	$4.055d$	$4.386d$
2	19	24	27	30	$5d$	$6d$	$6.033d$	$6.379d$
3	37	44	48	52	$7d$	$8d$	$8.024d$	$8.375d$
4	61	70	75	80	$9d$	$10d$	$10.018d$	$10.373d$
5	91	102	108	114	$11d$	$12d$	$12.015d$	$12.372d$
n	[b]	[b]	[b]	[b]	[b]	[b]	[b]	[b]

[a] Diameter D is given in terms of d, the diameter of the enclosed circles.

[b] For n complete layers over core, the number of enclosed circles N for the "A" center pattern is $3n^2 + 3n + 1$; for "B," $3n^2 + 5n + 2$; for "C," $3n^2 + 6n + 3$; for "D," $3n^2 + 7n + 4$. The diameter D of the enclosing circle for "A" center pattern is $(2n + 1)d$; for "B," $(2n + 2)d$; for "C," $(1 + 2\sqrt{n^2 + n + \frac{1}{3}})d$ and for "D," $(1 + \sqrt{4n^2 + 5.644n + 2})d$.

Table 2. Factors for Determining Diameter, D, of Smallest Enclosing Circle for Various Numbers, N, of Enclosed Circles (English or metric units)

No. N	Center Circle Pattern			No. N	Center Circle Pattern			No. N	Center Circle Pattern		
	"A"	"B"	"C"		"A"	"B"	"C"		"A"	"B"	"C"
	Diameter Factor K				Diameter Factor K				Diameter Factor K		
2	3	2	...	34	7.001	7.083	7.111	66	9.718	9.545	9.327
3	3	2.733	2.155	35	7.001	7.245	7.111	67	9.718	9.545	9.327
4	3	2.733	3.310	36	7.001	7.245	7.111	68	9.718	9.545	9.327
5	3	3.646	3.310	37	7.001	7.245	7.430	69	9.718	9.661	9.327
6	3	3.646	3.310	38	7.929	7.245	7.430	70	9.718	9.661	10.019
7	3	3.646	4.056	39	7.929	7.558	7.430	71	9.718	9.889	10.019
8	4.465	3.646	4.056	40	7.929	7.558	7.430	72	9.718	9.889	10.019
9	4.465	4	4.056	41	7.929	7.558	7.430	73	9.718	9.889	10.019
10	4.465	4	4.056	42	7.929	7.558	7.430	74	10.166	9.889	10.019
11	4.465	4.606	4.056	43	7.929	8.001	8.024	75	10.166	10	10.019
12	4.465	4.606	4.056	44	8.212	8.001	8.024	76	10.166	10	10.238
13	4.465	4.606	5.164	45	8.212	8.001	8.024	77	10.166	10.540	10.238
14	5	4.606	5.164	46	8.212	8.001	8.024	78	10.166	10.540	10.238
15	5	5.359	5.164	47	8.212	8.001	8.024	79	10.166	10.540	10.452
16	5	5.359	5.164	48	8.212	8.001	8.024	80	10.166	10.540	10.452
17	5	5.359	5.164	49	8.212	8.550	8.572	81	10.166	10.540	10.452
18	5	5.359	5.164	50	8.212	8.550	8.572	82	10.166	10.540	10.452
19	5	5.583	5.619	51	8.212	8.550	8.572	83	10.166	10.540	10.452
20	6.292	5.583	5.619	52	8.212	8.550	8.572	84	10.166	10.540	10.452
21	6.292	5.583	5.619	53	8.212	8.811	8.572	85	10.166	10.644	10.866
22	6.292	5.583	6.034	54	8.212	8.811	8.572	86	11	10.644	10.866
23	6.292	6.001	6.034	55	8.212	8.811	9.083	87	11	10.644	10.866
24	6.292	6.001	6.034	56	9.001	8.811	9.083	88	11	10.644	10.866
25	6.292	6.197	6.034	57	9.001	8.938	9.083	89	11	10.849	10.866
26	6.292	6.197	6.034	58	9.001	8.938	9.083	90	11	10.849	10.866
27	6.292	6.568	6.034	59	9.001	8.938	9.083	91	11	10.849	11.067
28	6.292	6.568	6.774	60	9.001	8.938	9.083	92	11.393	10.849	11.067
29	6.292	6.568	6.774	61	9.001	9.186	9.083	93	11.393	11.149	11.067
30	6.292	6.568	6.774	62	9.718	9.186	9.083	94	11.393	11.149	11.067
31	6.292	7.083	7.111	63	9.718	9.186	9.083	95	11.393	11.149	11.067
32	7.001	7.083	7.111	64	9.718	9.186	9.327	96	11.393	11.149	11.067
33	7.001	7.083	7.111	65	9.718	9.545	9.327	97	11.393	11.441	11.264

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Factors for Determining Diameter, *D*, of Smallest Enclosing Circle for Various Numbers, *N*, of Enclosed Circles** (English or metric units)

No. *N*	Center Circle Pattern "A" Diameter Factor *K*	Center Circle Pattern "B" Diameter Factor *K*	Center Circle Pattern "C" Diameter Factor *K*	No. *N*	Center Circle Pattern "A" Diameter Factor *K*	Center Circle Pattern "B" Diameter Factor *K*	Center Circle Pattern "C" Diameter Factor *K*	No. *N*	Center Circle Pattern "A" Diameter Factor *K*	Center Circle Pattern "B" Diameter Factor *K*	Center Circle Pattern "C" Diameter Factor *K*
98	11.584	11.441	11.264	153	14.115	14	14.013	208	16.100	16	16.144
99	11.584	11.441	11.264	154	14.115	14	14.013	209	16.100	16.133	16.144
100	11.584	11.441	11.264	155	14.115	14.077	14.013	210	16.100	16.133	16.144
101	11.584	11.536	11.264	156	14.115	14.077	14.013	211	16.100	16.133	16.144
102	11.584	11.536	11.264	157	14.115	14.077	14.317	212	16.621	16.133	16.144
103	11.584	11.536	12.016	158	14.115	14.077	14.317	213	16.621	16.395	16.144
104	11.584	11.536	12.016	159	14.115	14.229	14.317	214	16.621	16.395	16.276
105	11.584	11.817	12.016	160	14.115	14.229	14.317	215	16.621	16.395	16.276
106	11.584	11.817	12.016	161	14.115	14.229	14.317	216	16.621	16.395	16.276
107	11.584	11.817	12.016	162	14.115	14.229	14.317	217	16.621	16.525	16.276
108	11.584	11.817	12.016	163	14.115	14.454	14.317	218	16.621	16.525	16.276
109	11.584	12	12.016	164	14.857	14.454	14.317	219	16.621	16.525	16.276
110	12.136	12	12.016	165	14.857	14.454	14.317	220	16.621	16.525	16.535
111	12.136	12.270	12.016	166	14.857	14.454	14.317	221	16.621	16.589	16.535
112	12.136	12.270	12.016	167	14.857	14.528	14.317	222	16.621	16.589	16.535
113	12.136	12.270	12.016	168	14.857	14.528	14.317	223	16.621	16.716	16.535
114	12.136	12.270	12.016	169	14.857	14.528	14.614	224	16.875	16.716	16.535
115	12.136	12.358	12.373	170	15	14.528	14.614	225	16.875	16.716	16.535
116	12.136	12.358	12.373	171	15	14.748	14.614	226	16.875	16.716	17.042
117	12.136	12.358	12.373	172	15	14.748	14.614	227	16.875	16.716	17.042
118	12.136	12.358	12.373	173	15	14.748	14.614	228	16.875	16.716	17.042
119	12.136	12.533	12.373	174	15	14.748	14.614	229	16.875	16.716	17.042
120	12.136	12.533	12.373	175	15	14.893	15.048	230	16.875	16.716	17.042
121	12.136	12.533	12.548	176	15	14.893	15.048	231	16.875	17.094	17.042
122	13	12.533	12.548	177	15	14.893	15.048	232	16.875	17.094	17.166
123	13	12.533	12.548	178	15	14.893	15.048	233	16.875	17.094	17.166
124	13	12.533	12.719	179	15	15.107	15.048	234	16.875	17.094	17.166
125	13	12.533	12.719	180	15	15.107	15.048	235	16.875	17.094	17.166
126	13	12.533	12.719	181	15	15.107	15.190	236	17	17.094	17.166
127	13	12.790	12.719	182	15	15.107	15.190	237	17	17.094	17.166
128	13.166	12.790	12.719	183	15	15.178	15.190	238	17	17.094	17.166
129	13.166	12.790	12.719	184	15	15.178	15.190	239	17	17.463	17.166
130	13.166	12.790	13.056	185	15	15.178	15.190	240	17	17.463	17.166
131	13.166	13.125	13.056	186	15	15.178	15.190	241	17	17.463	17.290
132	13.166	13.125	13.056	187	15	15.526	15.469	242	17.371	17.463	17.290
133	13.166	13.125	13.056	188	15.423	15.526	15.469	243	17.371	17.523	17.290
134	13.166	13.125	13.056	189	15.423	15.526	15.469	244	17.371	17.523	17.290
135	13.166	13.125	13.056	190	15.423	15.526	15.469	245	17.371	17.523	17.290
136	13.166	13.125	13.221	191	15.423	15.731	15.469	246	17.371	17.523	17.290
137	13.166	13.289	13.221	192	15.423	15.731	15.469	247	17.371	17.523	17.654
138	13.166	13.289	13.221	193	15.423	15.731	15.743	248	17.371	17.523	17.654
139	13.166	13.289	13.221	194	15.423	15.731	15.743	249	17.371	17.523	17.654
140	13.490	13.289	13.221	195	15.423	15.731	15.743	250	17.371	17.523	17.654
141	13.490	13.530	13.221	196	15.423	15.731	15.743	251	17.371	17.644	17.654
142	13.490	13.530	13.702	197	15.423	15.731	15.743	252	17.371	17.644	17.654
143	13.490	13.530	13.702	198	15.423	15.731	15.743	253	17.371	17.644	17.773
144	13.490	13.530	13.702	199	15.423	15.799	16.012	254	18.089	17.644	17.773
145	13.490	13.768	13.859	200	16.100	15.799	16.012	255	18.089	17.704	17.773
146	13.490	13.768	13.859	201	16.100	15.799	16.012	256	18.089	17.704	17.773
147	13.490	13.768	13.859	202	16.100	15.799	16.012	257	18.089	17.704	17.773
148	13.490	13.768	13.859	203	16.100	15.934	16.012	258	18.089	17.704	17.773
149	13.490	14	13.859	204	16.100	15.934	16.012	259	18.089	17.823	18.010
150	13.490	14	13.859	205	16.100	15.934	16.012	260	18.089	17.823	18.010
151	13.490	14	14.013	206	16.100	15.934	16.012	261	18.089	17.823	18.010
152	14.115	14	14.013	207	16.100	16	16.012	262	18.089	17.823	18.010

Copyright 2004, Industrial Press, Inc., New York, NY

The diameter D of the enclosing circle is equal to the diameter factor, K, multiplied by d, the diameter of the enclosed circles, or $D = K \times d$. For example, if the number of circles to be enclosed, N, is 12, and the center circle arrangement is "C," then for $d = 1\frac{1}{2}$ inches, $D = 4.056 \times 1\frac{1}{2} = 6.084$ inches. If $d = 50$ millimeters, then $D = 4.056 \times 50 = 202.9$ millimeters.

Approximate Formula When Number of Enclosed Circles Is Large: When a large number of circles are to be enclosed, the arrangement of the center circles has little effect on the diameter of the enclosing circle. For numbers of circles greater than 10,000, the diameter of the enclosing circle may be calculated within 2 per cent from the formula $D = d(1 + \sqrt{N \div 0.907})$. In this formula, D = diameter of the enclosing circle; d = diameter of the enclosed circles; and N is the number of enclosed circles.

An alternative approach relates the area of each of the same-sized circles to be enclosed to the area of the enclosing circle (or container), as shown in Figs. 1 through 27. The table shows efficient ways for packing various numbers of circles N, from 2 up to 97.

In the table, D = the diameter of each circle to be enclosed, d = the diameter of the enclosing circle or container, and $\Phi = Nd^2/D^2$ = ratio of the area of the N circles to the area of the enclosing circle or container, which is the packing efficiency. Cross-hatching in the diagrams indicates loose circles that may need packing constraints.

Data for Numbers of Circles in Circles

N	D/d	Φ	Fig.	N	D/d	Φ	Fig.
2	2.0000	0.500	1	17	4.7920	0.740	15
3	2.1547	0.646	2	18	4.8637	0.761	16
4	2.4142	0.686	3	19	4.8637	0.803	16
5	2.7013	0.685	4	20	5.1223	0.762	17
6	3.0000	0.667	5	21	5.2523	0.761	18
7	3.0000	0.778	5	22	5.4397	0.743	19
8	3.3048	0.733	6	23	5.5452	9.748	20
9	3.6131	0.689	7	24	5.6517	0.751	21
10	3.8130	0.688	8	25	5.7608	0.753	22
11	3.9238	0.714	9	31	6.2915	0.783	23
12	4.0296	0.739	10	37	6.7588	0.810	24
13	4.2361	0.724	11	55	8.2111	0.816	25
14	4.3284	0.747	12	61	8.6613	0.813	26
15	4.5214	0.734	13	97	11.1587	0.779	27
16	4.6154	0.751	14	...	...	...	...

Packing of large numbers of circles, such as the 97 in Fig. 27, may be approached by drawing a triangular pattern of circles, as shown in Fig. 28, which represents three circles near the center of the array. The point of a compass is then placed at A, B, or C, or anywhere within triangle ABC, and the radius of the compass is gradually enlarged until it encompasses the number of circles to be enclosed. As a first approximation of the diameter, $D = 1.14d\sqrt{N}$ may be tried.


Fig. 1. $N = 2$


Fig. 2. $N = 3$


Fig. 3. $N = 4$


Fig. 4. $N = 5$

Copyright 2004, Industrial Press, Inc., New York, NY


Fig. 5. $N = 7$


Fig. 6. $N = 8$


Fig. 7. $N = 9$


Fig. 8. $N = 10$


Fig. 9. $N = 11$


Fig. 10. $N = 12$


Fig. 11. $N = 13$


Fig. 12. $N = 14$


Fig. 13. $N = 15$


Fig. 14. $N = 16$


Fig. 15. $N = 17$


Fig. 16. $N = 19$


Fig. 17. $N = 20$


Fig. 18. $N = 21$


Fig. 19. $N = 22$


Fig. 20. $N = 23$


Fig. 21. $N = 24$


Fig. 22. $N = 25$


Fig. 23. $N = 31$


Fig. 24. $N = 37$


Fig. 25. $N = 55$


Fig. 26. $N = 61$


Fig. 27. $N = 97$



Fig. 28.

Copyright 2004, Industrial Press, Inc., New York, NY

Circles within Rectangles.— For small numbers N of circles, packing (for instance, of cans) is less vital than for larger numbers and the number will usually govern the decision whether to use a rectangular or a triangular pattern, examples of which are seen in Figs. 29 and 30.



Fig. 29. Rectangular Pattern ($r = 4, c = 5$)



Fig. 30. Triangular Pattern ($r = 3, c = 7$)

If D is the can diameter and H its height, the arrangement in Fig. 29 will hold 20 circles or cans in a volume of $5D \times 4D \times H = 20D^2 H$. The arrangement in Fig. 30 will pack the same 20 cans into a volume of $7D \times 2.732D \times H = 19.124D^2 H$, a reduction of 4.4 per cent. When the ratio of H/D is less than 1.196:1, the rectangular pattern requires less surface area (therefore less material) for the six sides of the box, but for greater ratios, the triangular pattern is better. Some numbers, such as 19, can be accommodated only in a triangular pattern.

The following table shows possible patterns for 3 to 25 cans, where N = number of circles, P = pattern (R rectangular or T triangular), and r and c = numbers of rows and columns, respectively. The final table column shows the most economical application, where V = best volume, S = best surface area (sometimes followed by a condition on H/D). For the rectangular pattern, the area of the container is $rD \times cD$, and for the triangular pattern, the area is $cD \times [1 + (r-1)\sqrt{3}/2]D$, or $cD^2[1 + 0.866(r-1)]$.

Numbers of Circles in Rectangular Arrangements

N	P	r	c	Application	N	P	r	c	Application
3	T	2	2	V, S	15	R	3	5	$(S, H/D > 0.038)$
						T	2	8	$V, (S, H/D < 0.038)$
4	R	2	2	V, S	16	R	4	4	V, S
5	T	3	2	V, S	17	T	3	6	V, S
6	R	2	3	V, S	18	T	5	4	V, S
7	T	2	4	V, S	19	T	2	10	V, S
8	R	4	2	$V, (S, H/D < 0.732)$	20	R	4	5	$(S, H/D > 1.196)$
	T	3	3	$(S, H/D > 0.732)$		T	3	7	$V, (S, H/D < 1.196)$
9	R	3	3	V, S	21	R	3	7	$(S, 0.165 < H/D < 0.479)$
10	R	5	2	$V, (S, H/D > 1.976)$		T	6	4	$(S, H/D > 0.479)$
	T	4	3	$(S, H/D > 1.976)$		T	2	11	$V, (S, H/D < 0.165)$
11	T	3	4	V, S	22	T	4	6	V, S
12	R	3	4	V, S	23	T	5	5	$(S, H/D > 0.366)$
13	T	5	3	$(S, H/D > 0.236)$		T	3	8	$V, (S, H/D < 0.366)$
	T	2	7	$V, (S, H/D < 0.236)$	24	R	4	6	V, S
14	T	4	4	$(S, H/D > 5.464)$	25	R	5	5	$(S, H/D > 1.10)$
	T	3	5	$V, (S, H/D < 5.464)$		T	7	4	$(S, 0.113 < H/D < 1.10)$
						T	2	13	$V, (S, H/D < 0.133)$

Copyright 2004, Industrial Press, Inc., New York, NY

Rollers on a Shaft*.— The following formulas illustrate the geometry of rollers on a shaft. In Fig. 31, D is the diameter of the center line of the roller circle, d is the diameter of a roller, $D_S = D - d$ is the shaft diameter, and C is the clearance along the center line of the roller circle. In the equations that follow, N is the number of rollers, and $N > 3$.

Equation (1a) applies when the clearance $C = 0$

$$D = \frac{d}{\sin\left(\frac{180}{N}\right)} \tag{1a}$$

Equation (1b) applies when clearance $C > 0$ then

$$C = D\sin\left(180° - (N-1)\,\text{asin}\left(\frac{d}{D}\right)\right) - d \tag{1b}$$



Fig. 31.

Example: Forty bearings are to be placed around a 3-inch diameter shaft with no clearance. What diameter bearings are needed?

Solution: Rearrange Equation (1a), and substitute in the value of N. Use the result to eliminate d, using $D_S = D - d$. Finally, solve for D and d.

$$d = D\sin\left(\frac{180}{N}\right) = D\sin\left(\frac{180}{40}\right) = 0.078459D$$

$$D = D_S + d = 3 + 0.078459D$$

$$D = \frac{3}{0.92154} = 3.2554$$

$$d = D - D_S = 0.2554$$

* *Rollers on a Shaft* contributed by Manfred K. Brueckner.

Copyright 2004, Industrial Press, Inc., New York, NY

SOLUTION OF TRIANGLES

Any figure bounded by three straight lines is called a triangle. Any one of the three lines may be called the base, and the line drawn from the angle opposite the base at right angles to it is called the height or altitude of the triangle.

If all three sides of a triangle are of equal length, the triangle is called *equilateral*. Each of the three angles in an equilateral triangle equals 60 degrees. If two sides are of equal length, the triangle is an *isosceles* triangle. If one angle is a right or 90-degree angle, the triangle is a *right* or *right-angled* triangle. The side opposite the right angle is called the *hypotenuse*.

If all the angles are less than 90 degrees, the triangle is called an *acute* or *acute-angled* triangle. If one of the angles is larger than 90 degrees, the triangle is called an *obtuse-angled* triangle. Both acute and obtuse-angled triangles are known under the common name of *oblique-angled* triangles. The sum of the three angles in every triangle is 180 degrees.

The sides and angles of any triangle that are not known can be found when: 1) all the three sides; 2) two sides and one angle; and 3) one side and two angles are given.

In other words, if a triangle is considered as consisting of six parts, three angles and three sides, the unknown parts can be determined when any three parts are given, provided at least one of the given parts is a side.

Functions of Angles

For every right triangle, a set of six ratios is defined; each is the length of one side of the triangle divided by the length of another side. The six ratios are the trigonometric (trig) functions sine, cosine, tangent, cosecant, secant, and cotangent (abbreviated sin, cos, tan, csc, sec, and cot). Trig functions are usually expressed in terms of an angle in degree or radian measure, as in cos 60° = 0.5. "Arc" in front of a trig function name, as in arcsin or arccos, means find the angle whose function value is given. For example, arcsin 0.5 = 30° means that 30° is the angle whose sin is equal to 0.5. Electronic calculators frequently use $\sin^{-1}$, $\cos^{-1}$, and $\tan^{-1}$ to represent the arc functions.

Example: tan 53.1° = 1.332; arctan 1.332 = $\tan^{-1}$ 1.332 = 53.1° = 53° 6′

The *sine* of an angle equals the opposite side divided by the hypotenuse. Hence, sin $B = b \div c$, and sin $A = a \div c$.



The *cosine* of an angle equals the adjacent side divided by the hypotenuse. Hence, cos $B = a \div c$, and cos $A = b \div c$.

The *tangent* of an angle equals the opposite side divided by the adjacent side. Hence, tan $B = b \div a$, and tan $A = a \div b$.

The *cotangent* of an angle equals the adjacent side divided by the opposite side. Hence, cot $B = a \div b$, and cot $A = b \div a$.

The *secant* of an angle equals the hypotenuse divided by the adjacent side. Hence, sec $B = c \div a$, and sec $A = c \div b$.

The *cosecant* of an angle equals the hypotenuse divided by the opposite side. Hence, csc $B = c \div b$, and csc $A = c \div a$.

It should be noted that the functions of the angles can be found in this manner only when the triangle is right-angled.

If in a right-angled triangle (see preceding illustration), the lengths of the three sides are represented by a, b, and c, and the angles opposite each of these sides by A, B, and C, then the side c opposite the right angle is the hypotenuse; side b is called the *side adjacent* to angle A and is also the *side opposite* to angle B; side a is the side adjacent to angle B and the

Copyright 2004, Industrial Press, Inc., New York, NY

side opposite to angle *A*. The meanings of the various functions of angles can be explained with the aid of a right-angled triangle. Note that the cosecant, secant, and cotangent are the reciprocals of, respectively, the sine, cosine, and tangent.

The following relation exists between the angular functions of the two acute angles in a right-angled triangle: The sine of angle *B* equals the cosine of angle *A*; the tangent of angle *B* equals the cotangent of angle *A*, and *vice versa*. The sum of the two acute angles in a right-angled triangle always equals 90 degrees; hence, when one angle is known, the other can easily be found. When any two angles together make 90 degrees, one is called the *complement* of the other, and the sine of the one angle equals the cosine of the other, and the tangent of the one equals the cotangent of the other.

The Law of Sines.— In any triangle, any side is to the sine of the angle opposite that side as any other side is to the sine of the angle opposite that side. If a, b, and c are the sides, and A, B, and C their opposite angles, respectively, then:

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}, \quad \text{so that:}$$

$$a = \frac{b \sin A}{\sin B} \quad \text{or} \quad a = \frac{c \sin A}{\sin C}$$

$$b = \frac{a \sin B}{\sin A} \quad \text{or} \quad b = \frac{c \sin B}{\sin C}$$

$$c = \frac{a \sin C}{\sin A} \quad \text{or} \quad c = \frac{b \sin C}{\sin B}$$

The Law of Cosines.— In any triangle, the square of any side is equal to the sum of the squares of the other two sides minus twice their product times the cosine of the included angle; or if a, b and c are the sides and A, B, and C are the opposite angles, respectively, then:

$$a^2 = b^2 + c^2 - 2bc \cos A$$
$$b^2 = a^2 + c^2 - 2ac \cos B$$
$$c^2 = a^2 + b^2 - 2ab \cos C$$

These two laws, together with the proposition that the sum of the three angles equals 180 degrees, are the basis of all formulas relating to the solution of triangles.

Formulas for the solution of right-angled and oblique-angled triangles, arranged in tabular form, are given on the following pages.

Signs of Trigonometric Functions.— The diagram, Fig. 1 on page 98, shows the proper sign (+ or −) for the trigonometric functions of angles in each of the four quadrants, 0 to 90, 90 to 180, 180 to 270, and 270 to 360 degrees. Thus, the cosine of an angle between 90 and 180 degrees is negative; the sine of the same angle is positive.

Trigonometric Identities.— Trigonometric identities are formulas that show the relationship between different trigonometric functions. They may be used to change the form of some trigonometric expressions to simplify calculations. For example, if a formula has a term, $2\sin A \cos A$, the equivalent but simpler term $\sin 2A$ may be substituted. The identities that follow may themselves be combined or rearranged in various ways to form new identities.

Copyright 2004, Industrial Press, Inc., New York, NY

Basic

$$\tan A = \frac{\sin A}{\cos A} = \frac{1}{\cot A} \qquad \sec A = \frac{1}{\cos A} \qquad \csc A = \frac{1}{\sin A}$$

Negative Angle

$$\sin(-A) = -\sin A \qquad \cos(-A) = \cos A \qquad \tan(-A) = -\tan A$$

Pythagorean

$$\sin^2 A + \cos^2 A = 1 \qquad 1 + \tan^2 A = \sec^2 A \qquad 1 + \cot^2 A = \csc^2 A$$

Sum and Difference of Angles

$$\tan(A + B) = \frac{\tan A + \tan B}{1 - \tan A \tan B} \qquad \tan(A - B) = \frac{\tan A - \tan B}{1 + \tan A \tan B}$$

$$\cot(A + B) = \frac{\cot A \cot B - 1}{\cot B + \cot A} \qquad \cot(A - B) = \frac{\cot A \cot B + 1}{\cot B - \cot A}$$

$$\sin(A + B) = \sin A \cos B + \cos A \sin B \qquad \sin(A - B) = \sin A \cos B - \cos A \sin B$$

$$\cos(A + B) = \cos A \cos B - \sin A \sin B \qquad \cos(A - B) = \cos A \cos B + \sin A \sin B$$

Double-Angle

$$\cos 2A = \cos^2 A - \sin^2 A = 2\cos^2 A - 1 = 1 - 2\sin^2 A$$

$$\sin 2A = 2\sin A \cos A \qquad \tan 2A = \frac{2\tan A}{1 - \tan^2 A} = \frac{2}{\cot A - \tan A}$$

Half-Angle

$$\sin \tfrac{1}{2}A = \sqrt{\tfrac{1}{2}(1 - \cos A)} \qquad \cos \tfrac{1}{2}A = \sqrt{\tfrac{1}{2}(1 + \cos A)}$$

$$\tan \tfrac{1}{2}A = \sqrt{\frac{1 - \cos A}{1 + \cos A}} = \frac{1 - \cos A}{\sin A} = \frac{\sin A}{1 + \cos A}$$

Product-to-Sum

$$\sin A \cos B = \tfrac{1}{2}[\sin(A + B) + \sin(A - B)]$$

$$\cos A \cos B = \tfrac{1}{2}[\cos(A + B) + \cos(A - B)]$$

$$\sin A \sin B = \tfrac{1}{2}[\cos(A - B) - \cos(A + B)]$$

$$\tan A \tan B = \frac{\tan A + \tan B}{\cot A + \cot B}$$

Sum and Difference of Functions

$$\sin A + \sin B = 2[\sin \tfrac{1}{2}(A + B)\cos \tfrac{1}{2}(A - B)]$$

$$\sin A - \sin B = 2[\sin \tfrac{1}{2}(A - B)\cos \tfrac{1}{2}(A + B)]$$

$$\cos A + \cos B = 2[\cos \tfrac{1}{2}(A + B)\cos \tfrac{1}{2}(A - B)]$$

$$\cos A - \cos B = -2[\sin \tfrac{1}{2}(A + B)\sin \tfrac{1}{2}(A - B)]$$

$$\tan A + \tan B = \frac{\sin(A + B)}{\cos A \cos B} \qquad \tan A - \tan B = \frac{\sin(A - B)}{\cos A \cos B}$$

$$\cot A + \cot B = \frac{\sin(B + A)}{\sin A \sin B} \qquad \cot A - \cot B = \frac{\sin(B - A)}{\sin A \sin B}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Solution of Right-Angled Triangles



As shown in the illustration, the sides of the right-angled triangle are designated a and b and the hypotenuse, c. The angles opposite each of these sides are designated A and B, respectively.

Angle C, opposite the hypotenuse c is the right angle, and is therefore always one of the known quantities.

Sides and Angles Known	Formulas for Sides and Angles to be Found		
Side a; side b	$c = \sqrt{a^2 + b^2}$	$\tan A = \frac{a}{b}$	$B = 90° - A$
Side a; hypotenuse c	$b = \sqrt{c^2 - a^2}$	$\sin A = \frac{a}{c}$	$B = 90° - A$
Side b; hypotenuse c	$a = \sqrt{c^2 - b^2}$	$\sin B = \frac{b}{c}$	$A = 90° - B$
Hypotenuse c; angle B	$b = c \times \sin B$	$a = c \times \cos B$	$A = 90° - B$
Hypotenuse c; angle A	$b = c \times \cos A$	$a = c \times \sin A$	$B = 90° - A$
Side b; angle B	$c = \frac{b}{\sin B}$	$a = b \times \cot B$	$A = 90° - B$
Side b; angle A	$c = \frac{b}{\cos A}$	$a = b \times \tan A$	$B = 90° - A$
Side a; angle B	$c = \frac{a}{\cos B}$	$b = a \times \tan B$	$A = 90° - B$
Side a; angle A	$c = \frac{a}{\sin A}$	$b = a \times \cot A$	$B = 90° - A$

Trig Functions Values for Common Angles

$\sin 0° = 0$	$\cos 0° = 1$	$\tan 0° = 0$
$\sin 30° = \sin\frac{\pi}{6} = 0.5$	$\cos 30° = \cos\frac{\pi}{6} = 0.8660254$	$\tan 30° = \tan\frac{\pi}{6} = 0.57735027$
$\sin 45° = \sin\frac{\pi}{4} = 0.70710678$	$\cos 45° = \cos\frac{\pi}{4} = 0.70710678$	$\tan 45° = \tan\frac{\pi}{4} = 1$
$\sin 60° = \sin\frac{\pi}{3} = 0.8660254$	$\cos 60° = \cos\frac{\pi}{3} = 0.5$	$\tan 60° = \tan\frac{\pi}{3} = 1.7320508$
$\sin 90° = \sin\frac{\pi}{2} = 1$	$°\cos 90 = \cos\frac{\pi}{2} = 0$	$\tan 90° = \tan\frac{\pi}{2} = \infty$

Copyright 2004, Industrial Press, Inc., New York, NY

Examples of the Solution of Right-Angled Triangles (English and metric units)



Hypotenuse and One Angle Known

$c = 22$ inches; $B = 41° 36′$.

$$a = c \times \cos B = 22 \times \cos 41^\circ 36' = 22 \times 0.74780 = 16.4516 \text{ inches}$$

$$b = c \times \sin B = 22 \times \sin 41^\circ 36' = 22 \times 0.66393 = 14.6065 \text{ inches}$$

$$A = 90^\circ - B = 90^\circ - 41^\circ 36' = 48^\circ 24'$$



Hypotenuse and One Side Known

$c = 25$ centimeters; $a = 20$ centimeters.

$$b = \sqrt{c^2 - a^2} = \sqrt{25^2 - 20^2} = \sqrt{625 - 400} = \sqrt{225} = 15 \text{ centimeters}$$

$$\sin A = \frac{a}{c} = \frac{20}{25} = 0.8$$

Hence,
$$A = 53^\circ 8'$$
$$B = 90^\circ - A = 90^\circ - 53^\circ 8' = 36^\circ 52'$$



Two Sides Known

$a = 36$ inches; $b = 15$ inches.

$$c = \sqrt{a^2 + b^2} = \sqrt{36^2 + 15^2} = \sqrt{1296 + 225} = \sqrt{1521} = 39 \text{ inches}$$

$$\tan A = \frac{a}{b} = \frac{36}{15} = 2.4$$

Hence,
$$A = 67^\circ 23'$$
$$B = 90^\circ - A = 90^\circ - 67^\circ 23' = 22^\circ 37'$$



One Side and One Angle Known

$a = 12$ meters; $A = 65°$.

$$c = \frac{a}{\sin A} = \frac{12}{\sin 65^\circ} = \frac{12}{0.90631} = 13.2405 \text{ meters}$$

$$b = a \times \cot A = 12 \times \cot 65^\circ = 12 \times 0.46631 = 5.5957 \text{ meters}$$

$$B = 90^\circ - A = 90^\circ - 65^\circ = 25^\circ$$

Copyright 2004, Industrial Press, Inc., New York, NY

Chart For The Rapid Solution of Right-Angle and Oblique-Angle Triangles



Copyright 2004, Industrial Press, Inc., New York, NY

Solution of Oblique-Angled Triangles

One Side and Two Angles Known (Law of Sines):



One Side and Two Angles Known

Call the known side a, the angle opposite it A, and the other known angle B. Then, $C = 180° - (A + B)$. If angles B and C are given, but not A, then $A = 180° - (B + C)$.

$$C = 180^\circ - (A + B)$$

$$b = \frac{a \times \sin B}{\sin A} \qquad c = \frac{a \times \sin C}{\sin A}$$

$$\text{Area} = \frac{a \times b \times \sin C}{2}$$



Side and Angles Known

$a = 5$ centimeters; $A = 80°$; $B = 62°$

$$C = 180° - (80° + 62°) = 180° - 142° = 38°$$

$$b = \frac{a \times \sin B}{\sin A} = \frac{5 \times \sin 62°}{\sin 80°} = \frac{5 \times 0.88295}{0.98481}$$

$$= 4.483 \text{ centimeters}$$

$$c = \frac{a \times \sin C}{\sin A} = \frac{5 \times \sin 38°}{\sin 80°} = \frac{5 \times 0.61566}{0.98481}$$

$$= 3.126 \text{ centimeters}$$

Two Sides and the Angle Between Them Known:



Two Sides and the Angle Between Them Known

Call the known sides a and b, and the known angle between them C. Then,

$$\tan A = \frac{a \times \sin C}{b - (a \times \cos C)}$$

$$B = 180^\circ - (A + C) \qquad c = \frac{a \times \sin C}{\sin A}$$

Side c may also be found directly as below:

$$c = \sqrt{a^2 + b^2 - (2ab \times \cos C)}$$

$$\text{Area} = \frac{a \times b \times \sin C}{2}$$



Sides and Angle Known

$a = 9$ inches; $b = 8$ inches; $C = 35°$.

$$\tan A = \frac{a \times \sin C}{b - (a \times \cos C)} = \frac{9 \times \sin 35°}{8 - (9 \times \cos 35°)}$$

$$= \frac{9 \times 0.57358}{8 - (9 \times 0.81915)} = \frac{5.16222}{0.62765} = 8.22468$$

Hence, $A = 83°4'$

$$B = 180° - (A + C) = 180° - 118°4' = 61°56'$$

$$c = \frac{a \times \sin C}{\sin A} = \frac{9 \times 0.57358}{0.99269} = 5.2 \text{ inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Two Sides and the Angle Opposite One of the Sides Known:



Two Sides and the Angle Opposite One of the Sides Known

Call the known angle A, the side opposite it a, and the other known side b. Then,

$$\sin B = \frac{b \times \sin A}{a} \qquad C = 180° - (A + B)$$

$$c = \frac{a \times \sin C}{\sin A} \qquad \text{Area} = \frac{a \times b \times \sin C}{2}$$

If, in the above, angle $B >$ angle A but $<90°$, then a second solution B_2, C_2, c_2 exists for which: $B_2 = 180° - B$; $C_2 = 180° - (A + B_2)$; $c_2 = (a \times \sin C_2) \div \sin A$; area $= (a \times b \times \sin C_2) \div 2$. If $a \geq b$, then the first solution only exists. If $a < b \times \sin A$, then no solution exists.



Sides and Angle Known

$a = 20$ centimeters; $b = 17$ centimeters; $A = 61°$.

$$\sin B = \frac{b \times \sin A}{a} = \frac{17 \times \sin 61°}{20}$$

$$= \frac{17 \times 0.87462}{20} = 0.74343$$

Hence, $B = 48°1'$

$$C = 180° - (A + B) = 180° - 109°1' = 70°59'$$

$$c = \frac{a \times \sin C}{\sin A} = \frac{20 \times \sin 70°59'}{\sin 61°} = \frac{20 \times 0.94542}{0.87462}$$

$$= 21.62 \text{ centimeters}$$

All Three Sides are Known:



All Three Sides Known

Call the sides a, b, and c, and the angles opposite them, A, B, and C. Then,

$$\cos A = \frac{b^2 + c^2 - a^2}{2bc} \qquad \sin B = \frac{b \times \sin A}{a}$$

$$C = 180° - (A + B) \qquad \text{Area} = \frac{a \times b \times \sin C}{2}$$



Sides and Angle Known

$a = 8$ inches; $b = 9$ inches; $c = 10$ inches.

$$\cos A = \frac{b^2 + c^2 - a^2}{2bc} = \frac{9^2 + 10^2 - 8^2}{2 \times 9 \times 10}$$

$$= \frac{81 + 100 - 64}{180} = \frac{117}{180} = 0.65000$$

Hence, $A = 49°27'$

$$\sin B = \frac{b \times \sin A}{a} = \frac{9 \times 0.75984}{8} = 0.85482$$

Hence, $B = 58°44'$

$$C = 180° - (A + B) = 180° - 108°11' = 71°49'$$

Copyright 2004, Industrial Press, Inc., New York, NY

Conversion Tables of Angular Measure.— The accompanying tables of degrees, minutes, and seconds into radians; radians into degrees, minutes, and seconds; radians into degrees and decimals of a degree; and minutes and seconds into decimals of a degree and vice versa facilitate the conversion of measurements.

Example 1: The Degrees, Minutes, and Seconds into Radians table is used to find the number of radians in 324 degrees, 25 minutes, 13 seconds as follows:

300 degrees	=	5.235988 radians
20 degrees	=	0.349066 radian
4 degrees	=	0.069813 radian
25 minutes	=	0.007272 radian
13 seconds	=	0.000063 radian
324°25′13″	=	5.662202 radians

Example 2: The Radians into Degrees and Decimals of a Degree, and Radians into Degrees, Minutes and Seconds tables are used to find the number of decimal degrees or degrees, minutes and seconds in 0.734 radian as follows:

0.7 radian	= 40.1070 degrees	0.7 radian	= 40° 6′25″
0.03 radian	= 1.7189 degrees	0.03 radian	= 1°43′8″
0.004 radian	= 0.2292 degree	0.004 radian	= 0°13′45″
0.734 radian	= 42.0551 degrees	0.734 radian	= 41°62′78″ or 42°3′18″

Degrees, Minutes, and Seconds into Radians (Based on 180 degrees = π radians)

Degrees into Radians

Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.
1000	17.453293	100	1.745329	10	0.174533	1	0.017453	0.1	0.001745	0.01	0.000175
2000	34.906585	200	3.490659	20	0.349066	2	0.034907	0.2	0.003491	0.02	0.000349
3000	52.359878	300	5.235988	30	0.523599	3	0.052360	0.3	0.005236	0.03	0.000524
4000	69.813170	400	6.981317	40	0.698132	4	0.069813	0.4	0.006981	0.04	0.000698
5000	87.266463	500	8.726646	50	0.872665	5	0.087266	0.5	0.008727	0.05	0.000873
6000	104.719755	600	10.471976	60	1.047198	6	0.104720	0.6	0.010472	0.06	0.001047
7000	122.173048	700	12.217305	70	1.221730	7	0.122173	0.7	0.012217	0.07	0.001222
8000	139.626340	800	13.962634	80	1.396263	8	0.139626	0.8	0.013963	0.08	0.001396
9000	157.079633	900	15.707963	90	1.570796	9	0.157080	0.9	0.015708	0.09	0.001571
10000	174.532925	1000	17.453293	100	1.745329	10	0.174533	1.0	0.017453	0.10	0.001745

Minutes into Radians

Min.	Rad.	Min.	Rad.	Min.	Rad.	Min.	Rad.	Min.	Rad.	Min.	Rad.
1	0.000291	11	0.003200	21	0.006109	31	0.009018	41	0.011926	51	0.014835
2	0.000582	12	0.003491	22	0.006400	32	0.009308	42	0.012217	52	0.015126
3	0.000873	13	0.003782	23	0.006690	33	0.009599	43	0.012508	53	0.015417
4	0.001164	14	0.004072	24	0.006981	34	0.009890	44	0.012799	54	0.015708
5	0.001454	15	0.004363	25	0.007272	35	0.010181	45	0.013090	55	0.015999
6	0.001745	16	0.004654	26	0.007563	36	0.010472	46	0.013381	56	0.016290
7	0.002036	17	0.004945	27	0.007854	37	0.010763	47	0.013672	57	0.016581
8	0.002327	18	0.005236	28	0.008145	38	0.011054	48	0.013963	58	0.016872
9	0.002618	19	0.005527	29	0.008436	39	0.011345	49	0.014254	59	0.017162
10	0.002909	20	0.005818	30	0.008727	40	0.011636	50	0.014544	60	0.017453

Seconds into Radians

Sec.	Rad.	Sec.	Rad.	Sec.	Rad.	Sec.	Rad.	Sec.	Rad.	Sec.	Rad.
1	0.000005	11	0.000053	21	0.000102	31	0.000150	41	0.000199	51	0.000247
2	0.000010	12	0.000058	22	0.000107	32	0.000155	42	0.000204	52	0.000252
3	0.000015	13	0.000063	23	0.000112	33	0.000160	43	0.000208	53	0.000257
4	0.000019	14	0.000068	24	0.000116	34	0.000165	44	0.000213	54	0.000262
5	0.000024	15	0.000073	25	0.000121	35	0.000170	45	0.000218	55	0.000267
6	0.000029	16	0.000078	26	0.000126	36	0.000175	46	0.000223	56	0.000271
7	0.000034	17	0.000082	27	0.000131	37	0.000179	47	0.000228	57	0.000276
8	0.000039	18	0.000087	28	0.000136	38	0.000184	48	0.000233	58	0.000281
9	0.000044	19	0.000092	29	0.000141	39	0.000189	49	0.000238	59	0.000286
10	0.000048	20	0.000097	30	0.000145	40	0.000194	50	0.000242	60	0.000291

Copyright 2004, Industrial Press, Inc., New York, NY

Radians into Degrees and Decimals of a Degree (Based on π radians = 180 degrees)

Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.	Rad.	Deg.
10	572.9578	1	57.2958	0.1	5.7296	0.01	0.5730	0.001	0.0573	0.0001	0.0057
20	1145.9156	2	114.5916	0.2	11.4592	0.02	1.1459	0.002	0.1146	0.0002	0.0115
30	1718.8734	3	171.8873	0.3	17.1887	0.03	1.7189	0.003	0.1719	0.0003	0.0172
40	2291.8312	4	229.1831	0.4	22.9183	0.04	2.2918	0.004	0.2292	0.0004	0.0229
50	2864.7890	5	286.4789	0.5	28.6479	0.05	2.8648	0.005	0.2865	0.0005	0.0286
60	3437.7468	6	343.7747	0.6	34.3775	0.06	3.4377	0.006	0.3438	0.0006	0.0344
70	4010.7046	7	401.0705	0.7	40.1070	0.07	4.0107	0.007	0.4011	0.0007	0.0401
80	4583.6624	8	458.3662	0.8	45.8366	0.08	4.5837	0.008	0.4584	0.0008	0.0458
90	5156.6202	9	515.6620	0.9	51.5662	0.09	5.1566	0.009	0.5157	0.0009	0.0516
100	5729.5780	10	572.9578	1.0	57.2958	0.10	5.7296	0.010	0.5730	0.0010	0.0573

Radians into Degrees, Minutes, and Seconds (Based on π radians = 180 degrees)

Rad.	Angle	Rad.	Angle	Rad.	Angle	Rad.	Angle	Rad.	Angle	Rad.	Angle
10	572°57′28″	1	57°17′45″	0.1	5°43′46″	0.01	0°34′23″	0.001	0°3′26″	0.0001	0°0′21″
20	1145°54′56″	2	114°35′30″	0.2	11°27′33″	0.02	1°8′45″	0.002	0°6′53″	0.0002	0°0′41″
30	1718°52′24″	3	171°53′14″	0.3	17°11′19″	0.03	1°43′8″	0.003	0°10′19″	0.0003	0°1′ 2″
40	2291°49′52″	4	229°10′59″	0.4	22°55′6″	0.04	2°17′31″	0.004	0°13′45″	0.0004	0°1′23″
50	2864°47′20″	5	286°28′44″	0.5	28°38′52″	0.05	2°51′53″	0.005	0°17′11″	0.0005	0°1′43″
60	3437°44′48″	6	343°46′29″	0.6	34°22′39″	0.06	3°26′16″	0.006	0°20′38″	0.0006	0°2′ 4″
70	4010°42′16″	7	401°4′14″	0.7	40°6′25″	0.07	4°0′39″	0.007	0°24′4″	0.0007	0°2′24″
80	4583°39′44″	8	458°21′58″	0.8	45°50′12″	0.08	4°35′1″	0.008	0°27′30″	0.0008	0°2′45″
90	5156°37′13″	9	515°39′43″	0.9	51°33′58″	0.09	5°9′24″	0.009	0°30′56″	0.0009	0°3′6″
100	5729°34′41″	10	572°57′28″	1.0	57°17′45″	0.10	5°43′46″	0.010	0°34′23″	0.0010	0°3′26″

Minutes and Seconds into Decimal of a Degree and Vice Versa (Based on 1 second = 0.00027778 degree)

Minutes into Decimals of a Degree						Seconds into Decimals of a Degree					
Min.	Deg.	Min.	Deg.	Min.	Deg.	Sec.	Deg.	Sec.	Deg.	Sec.	Deg.
1	0.0167	21	0.3500	41	0.6833	1	0.0003	21	0.0058	41	0.0114
2	0.0333	22	0.3667	42	0.7000	2	0.0006	22	0.0061	42	0.0117
3	0.0500	23	0.3833	43	0.7167	3	0.0008	23	0.0064	43	0.0119
4	0.0667	24	0.4000	44	0.7333	4	0.0011	24	0.0067	44	0.0122
5	0.0833	25	0.4167	45	0.7500	5	0.0014	25	0.0069	45	0.0125
6	0.1000	26	0.4333	46	0.7667	6	0.0017	26	0.0072	46	0.0128
7	0.1167	27	0.4500	47	0.7833	7	0.0019	27	0.0075	47	0.0131
8	0.1333	28	0.4667	48	0.8000	8	0.0022	28	0.0078	48	0.0133
9	0.1500	29	0.4833	49	0.8167	9	0.0025	29	0.0081	49	0.0136
10	0.1667	30	0.5000	50	0.8333	10	0.0028	30	0.0083	50	0.0139
11	0.1833	31	0.5167	51	0.8500	11	0.0031	31	0.0086	51	0.0142
12	0.2000	32	0.5333	52	0.8667	12	0.0033	32	0.0089	52	0.0144
13	0.2167	33	0.5500	53	0.8833	13	0.0036	33	0.0092	53	0.0147
14	0.2333	34	0.5667	54	0.9000	14	0.0039	34	0.0094	54	0.0150
15	0.2500	35	0.5833	55	0.9167	15	0.0042	35	0.0097	55	0.0153
16	0.2667	36	0.6000	56	0.9333	16	0.0044	36	0.0100	56	0.0156
17	0.2833	37	0.6167	57	0.9500	17	0.0047	37	0.0103	57	0.0158
18	0.3000	38	0.6333	58	0.9667	18	0.0050	38	0.0106	58	0.0161
19	0.3167	39	0.6500	59	0.9833	19	0.0053	39	0.0108	59	0.0164
20	0.3333	40	0.6667	60	1.0000	20	0.0056	40	0.0111	60	0.0167

Example 3: Convert 11′37″ to decimals of a degree. From the left table, 11′ = 0.1833 degree. From the right table, 37″ = 0.0103 degree. Adding, 11′37″ = 0.1833 + 0.0103 = 0.1936 degree.

Example 4: Convert 0.1234 degree to minutes and seconds. From the left table, 0.1167 degree = 7′. Subtracting 0.1167 from 0.1234 gives 0.0067. From the right table, 0.0067 = 24″ so that 0.1234 = 7′24″.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Signs of Trigonometric Functions, Fractions of π, and Degree–Radian Conversion

Graphic Illustrations of the Functions of Angles.— In graphically illustrating the functions of angles, it is assumed that all distances measured in the horizontal direction to the right of line *AB* are positive. Those measured horizontally to the left of *AB* are negative. All distances measured vertically, are positive above line *CD* and negative below it. It can then be readily seen that the sine is positive for all angles less than 180 degrees. For angles larger than 180 degrees, the sine would be measured below *CD*, and is negative. The cosine is positive up to 90 degrees, but for angles larger than 90 but less than 270 degrees, the cosine is measured to the left of line *AB* and is negative.

The table *Useful Relationships Among Angles* that follows is arranged to show directly whether the function of any given angle is positive or negative. It also gives the limits between which the numerical values of the function vary. For example, it will be seen from the table that the cosine of an angle between 90 and 180 degrees is negative, and that its value will be somewhere between 0 and – 1. In the same way, the cotangent of an angle between 180 and 270 degrees is positive and has a value between infinity and 0; in other words, the cotangent for 180 degrees is infinitely large and then the cotangent gradually decreases for increasing angles, so that the cotangent for 270 degrees equals 0.

The sine is positive for all angles up to 180 degrees. The cosine, tangent and cotangent for angles between 90 and 180 degrees, while they have the same numerical values as for angles from 0 to 90 degrees, are negative. These should be preceded by a minus sign; thus tan 123 degrees 20 minutes = –1.5204.

Copyright 2004, Industrial Press, Inc., New York, NY



Graphic Illustration of the Functions of Angles

Tables of Trigonometric Functions.— The trigonometric (trig) tables on the following pages give numerical values for sine, cosine, tangent, and cotangent functions of angles from 0 to 90 degrees. Function values for all other angles can be obtained from the tables by applying the rules for signs of trigonometric functions and the useful relationships among angles given in the following. Secant and cosecant functions can be found from sec $A = 1/\cos A$ and csc $A = 1/\sin A$.

The trig tables are divided by a double line. The body of each half table consists of four labeled columns of data between columns listing angles. The angles listed to the left of the data increase moving down the table, and angles listed to the right of the data increase moving up the table. Labels above the data identify the trig functions corresponding to angles listed in the left column of each half table. Labels below the data correspond to angles listed in the right column of each half table. To find the value of a function for a particular angle, first locate the angle in the table, then find the appropriate function label across the top or bottom row of the table, and find the function value at the intersection of the angle row and label column. Angles opposite each other are complementary angles (i.e., their sum equals 90°) and related. For example, $\sin 10° = \cos 80°$ and $\cos 10° = \sin 80°$.

All the trig functions of angles between 0° and 90° have positive values. For other angles, consult the chart below to find the sign of the function in the quadrant where the angle is located. To determine trig functions of angles greater than 90° subtract 90, 180, 270, or 360 from the angle to get an angle less than 90° and use Table 1 to find the equivalent first-quadrant function and angle to look up in the trig tables.

Table 1. Useful Relationships Among Angles

Angle Function	θ	−θ	90° ± θ	180° ± θ	270° ± θ	360° ± θ
sin	sin θ	−sin θ	+cos θ	∓sin θ	−cos θ	±sin θ
cos	cos θ	+cos θ	∓sin θ	−cos θ	±sin θ	+cos θ
tan	tan θ	−tan θ	∓cot θ	±tan θ	∓cot θ	±tan θ
cot	cot θ	−cot θ	∓tan θ	±cot θ	∓tan θ	±cot θ
sec	sec θ	+sec θ	∓csc θ	−sec θ	±csc θ	+sec θ
csc	csc θ	−csc θ	+sec θ	∓csc θ	−sec θ	±csc θ

Examples: cos (270° − θ) = −sin θ; tan (90° + θ) = −cot θ.

Example: Find the cosine of 336°40′. The diagram in *Signs of Trigonometric Functions, Fractions of p, and Degree–Radian Conversion* shows that the cosine of every angle in Quadrant IV (270° to 360°) is positive. To find the angle and trig function to use when entering the trig table, subtract 270 from 336 to get cos 336°40′ = cos (270° + 66°40′) and then find the intersection of the cos row and the 270 ± θ column in Table 1. Because cos (270 ± θ) in the fourth quadrant is equal to ± sin θ in the first quadrant, find sin 66°40′ in the trig table. Therefore, cos 336°40′ = sin 66°40′ = 0.918216.

Copyright 2004, Industrial Press, Inc., New York, NY

Trigonometric Functions of Angles from 0° to 15° and 75° to 90°

Angle	sin	cos	tan	cot		Angle	sin	cos	tan	cot	
0° 0′	0.000000	1.000000	0.000000	—	**90° 0′**	**7° 30′**	0.130526	0.991445	0.131652	7.595754	**82° 30′**
10	0.002909	0.999996	0.002909	343.7737	**50**	**40**	0.133410	0.991061	0.134613	7.428706	**20**
20	0.005818	0.999983	0.005818	171.8854	**40**	**50**	0.136292	0.990669	0.137576	7.268725	**10**
30	0.008727	0.999962	0.008727	114.5887	**30**	**8° 0′**	0.139173	0.990268	0.140541	7.115370	**82° 0′**
40	0.011635	0.999932	0.011636	85.93979	**20**	**10**	0.142053	0.989859	0.143508	6.968234	**50**
50	0.014544	0.999894	0.014545	68.75009	**10**	**20**	0.144932	0.989442	0.146478	6.826944	**40**
1° 0′	0.017452	0.999848	0.017455	57.28996	**89° 0′**	**30**	0.147809	0.989016	0.149451	6.691156	**30**
10	0.020361	0.999793	0.020365	49.10388	**50**	**40**	0.150686	0.988582	0.152426	6.560554	**20**
20	0.023269	0.999729	0.023275	42.96408	**40**	**50**	0.153561	0.988139	0.155404	6.434843	**10**
30	0.026177	0.999657	0.026186	38.18846	**30**	**9° 0′**	0.156434	0.987688	0.158384	6.313752	**81° 0′**
40	0.029085	0.999577	0.029097	34.36777	**20**	**10**	0.159307	0.987229	0.161368	6.197028	**50**
50	0.031992	0.999488	0.032009	31.24158	**10**	**20**	0.162178	0.986762	0.164354	6.084438	**40**
2° 0′	0.034899	0.999391	0.034921	28.63625	**88° 0′**	**30**	0.165048	0.986286	0.167343	5.975764	**30**
10	0.037806	0.999285	0.037834	26.43160	**50**	**40**	0.167916	0.985801	0.170334	5.870804	**20**
20	0.040713	0.999171	0.040747	24.54176	**40**	**50**	0.170783	0.985309	0.173329	5.769369	**10**
30	0.043619	0.999048	0.043661	22.90377	**30**	**10° 0′**	0.173648	0.984808	0.176327	5.671282	**80° 0′**
40	0.046525	0.998917	0.046576	21.47040	**20**	**10**	0.176512	0.984298	0.179328	5.576379	**50**
50	0.049431	0.998778	0.049491	20.20555	**10**	**20**	0.179375	0.983781	0.182332	5.484505	**40**
3° 0′	0.052336	0.998630	0.052408	19.08114	**87° 0′**	**30**	0.182236	0.983255	0.185339	5.395517	**30**
10	0.055241	0.998473	0.055325	18.07498	**50**	**40**	0.185095	0.982721	0.188349	5.309279	**20**
20	0.058145	0.998308	0.058243	17.16934	**40**	**50**	0.187953	0.982178	0.191363	5.225665	**10**
30	0.061049	0.998135	0.061163	16.34986	**30**	**11° 0′**	0.190809	0.981627	0.194380	5.144554	**79° 0′**
40	0.063952	0.997953	0.064083	15.60478	**20**	**10**	0.193664	0.981068	0.197401	5.065835	**50**
50	0.066854	0.997763	0.067004	14.92442	**10**	**20**	0.196517	0.980500	0.200425	4.989403	**40**
4° 0′	0.069756	0.997564	0.069927	14.30067	**86° 0′**	**30**	0.199368	0.979925	0.203452	4.915157	**30**
10	0.072658	0.997357	0.072851	13.72674	**50**	**40**	0.202218	0.979341	0.206483	4.843005	**20**
20	0.075559	0.997141	0.075775	13.19688	**40**	**50**	0.205065	0.978748	0.209518	4.772857	**10**
30	0.078459	0.996917	0.078702	12.70621	**30**	**12° 0′**	0.207912	0.978148	0.212557	4.704630	**78° 0′**
40	0.081359	0.996685	0.081629	12.25051	**20**	**10**	0.210756	0.977539	0.215599	4.638246	**50**
50	0.084258	0.996444	0.084558	11.82617	**10**	**20**	0.213599	0.976921	0.218645	4.573629	**40**
5° 0′	0.087156	0.996195	0.087489	11.43005	**85° 0′**	**30**	0.216440	0.976296	0.221695	4.510709	**30**
10	0.090053	0.995937	0.090421	11.05943	**50**	**40**	0.219279	0.975662	0.224748	4.449418	**20**
20	0.092950	0.995671	0.093354	10.71191	**40**	**50**	0.222116	0.975020	0.227806	4.389694	**10**
30	0.095846	0.995396	0.096289	10.38540	**30**	**13° 0′**	0.224951	0.974370	0.230868	4.331476	**77° 0′**
40	0.098741	0.995113	0.099226	10.07803	**20**	**10**	0.227784	0.973712	0.233934	4.274707	**50**
50	0.101635	0.994822	0.102164	9.788173	**10**	**20**	0.230616	0.973045	0.237004	4.219332	**40**
6° 0′	0.104528	0.994522	0.105104	9.514364	**84° 0′**	**30**	0.233445	0.972370	0.240079	4.165300	**30**
10	0.107421	0.994214	0.108046	9.255304	**50**	**40**	0.236273	0.971687	0.243157	4.112561	**20**
20	0.110313	0.993897	0.110990	9.009826	**40**	**50**	0.239098	0.970995	0.246241	4.061070	**10**
30	0.113203	0.993572	0.113936	8.776887	**30**	**14° 0′**	0.241922	0.970296	0.249328	4.010781	**76° 0′**
40	0.116093	0.993238	0.116883	8.555547	**20**	**10**	0.244743	0.969588	0.252420	3.961652	**50**
50	0.118982	0.992896	0.119833	8.344956	**10**	**20**	0.247563	0.968872	0.255516	3.913642	**40**
7° 0′	0.121869	0.992546	0.122785	8.144346	**83° 0′**	**30**	0.250380	0.968148	0.258618	3.866713	**30**
10	0.124756	0.992187	0.125738	7.953022	**50**	**40**	0.253195	0.967415	0.261723	3.820828	**20**
20	0.127642	0.991820	0.128694	7.770351	**40**	**50**	0.256008	0.966675	0.264834	3.775952	**10**
7° 30′	0.130526	0.991445	0.131652	7.595754	**82° 30**	**15° 0′**	0.258819	0.965926	0.267949	3.732051	**75° 0′**
	cos	sin	cot	tan	Angle		cos	sin	cot	tan	Angle

For angles 0° to 15° 0′ (angles found in a column to the left of the data), use the column labels at the top of the table; for angles 75° to 90° 0′ (angles found in a column to the right of the data), use the column labels at the bottom of the table.

Copyright 2004, Industrial Press, Inc., New York, NY

Trigonometric Functions of Angles from 15° to 30° and 60° to 75°

Angle	sin	cos	tan	cot		Angle	sin	cos	tan	cot	
15° 0′	0.258819	0.965926	0.267949	3.732051	**75° 0′**	**22° 30′**	0.382683	0.923880	0.414214	2.414214	**67° 30**
10	0.261628	0.965169	0.271069	3.689093	**50**	**40**	0.385369	0.922762	0.417626	2.394489	**20**
20	0.264434	0.964404	0.274194	3.647047	**40**	**50**	0.388052	0.921638	0.421046	2.375037	**10**
30	0.267238	0.963630	0.277325	3.605884	**30**	**23° 0′**	0.390731	0.920505	0.424475	2.355852	**67° 0′**
40	0.270040	0.962849	0.280460	3.565575	**20**	**10**	0.393407	0.919364	0.427912	2.336929	**50**
50	0.272840	0.962059	0.283600	3.526094	**10**	**20**	0.396080	0.918216	0.431358	2.318261	**40**
16° 0′	0.275637	0.961262	0.286745	3.487414	**74° 0′**	**30**	0.398749	0.917060	0.434812	2.299843	**30**
10	0.278432	0.960456	0.289896	3.449512	**50**	**40**	0.401415	0.915896	0.438276	2.281669	**20**
20	0.281225	0.959642	0.293052	3.412363	**40**	**50**	0.404078	0.914725	0.441748	2.263736	**10**
30	0.284015	0.958820	0.296213	3.375943	**30**	**24° 0′**	0.406737	0.913545	0.445229	2.246037	**66° 0′**
40	0.286803	0.957990	0.299380	3.340233	**20**	**10**	0.409392	0.912358	0.448719	2.228568	**50**
50	0.289589	0.957151	0.302553	3.305209	**10**	**20**	0.412045	0.911164	0.452218	2.211323	**40**
17° 0′	0.292372	0.956305	0.305731	3.270853	**73° 0′**	**30**	0.414693	0.909961	0.455726	2.194300	**30**
10	0.295152	0.955450	0.308914	3.237144	**50**	**40**	0.417338	0.908751	0.459244	2.177492	**20**
20	0.297930	0.954588	0.312104	3.204064	**40**	**50**	0.419980	0.907533	0.462771	2.160896	**10**
30	0.300706	0.953717	0.315299	3.171595	**30**	**25° 0′**	0.422618	0.906308	0.466308	2.144507	**65° 0′**
40	0.303479	0.952838	0.318500	3.139719	**20**	**10**	0.425253	0.905075	0.469854	2.128321	**50**
50	0.306249	0.951951	0.321707	3.108421	**10**	**20**	0.427884	0.903834	0.473410	2.112335	**40**
18° 0′	0.309017	0.951057	0.324920	3.077684	**72° 0′**	**30**	0.430511	0.902585	0.476976	2.096544	**30**
10	0.311782	0.950154	0.328139	3.047492	**50**	**40**	0.433135	0.901329	0.480551	2.080944	**20**
20	0.314545	0.949243	0.331364	3.017830	**40**	**50**	0.435755	0.900065	0.484137	2.065532	**10**
30	0.317305	0.948324	0.334595	2.988685	**30**	**26° 0′**	0.438371	0.898794	0.487733	2.050304	**64° 0′**
40	0.320062	0.947397	0.337833	2.960042	**20**	**10**	0.440984	0.897515	0.491339	2.035256	**50**
50	0.322816	0.946462	0.341077	2.931888	**10**	**20**	0.443593	0.896229	0.494955	2.020386	**40**
19° 0′	0.325568	0.945519	0.344328	2.904211	**71° 0′**	**30**	0.446198	0.894934	0.498582	2.005690	**30**
10	0.328317	0.944568	0.347585	2.876997	**50**	**40**	0.448799	0.893633	0.502219	1.991164	**20**
20	0.331063	0.943609	0.350848	2.850235	**40**	**50**	0.451397	0.892323	0.505867	1.976805	**10**
30	0.333807	0.942641	0.354119	2.823913	**30**	**27° 0′**	0.453990	0.891007	0.509525	1.962611	**63° 0′**
40	0.336547	0.941666	0.357396	2.798020	**20**	**10**	0.456580	0.889682	0.513195	1.948577	**50**
50	0.339285	0.940684	0.360679	2.772545	**10**	**20**	0.459166	0.888350	0.516875	1.934702	**40**
20° 0′	0.342020	0.939693	0.363970	2.747477	**70° 0′**	**30**	0.461749	0.887011	0.520567	1.920982	**30**
10	0.344752	0.938694	0.367268	2.722808	**50**	**40**	0.464327	0.885664	0.524270	1.907415	**20**
20	0.347481	0.937687	0.370573	2.698525	**40**	**50**	0.466901	0.884309	0.527984	1.893997	**10**
30	0.350207	0.936672	0.373885	2.674621	**30**	**28° 0′**	0.469472	0.882948	0.531709	1.880726	**62° 0′**
40	0.352931	0.935650	0.377204	2.651087	**20**	**10**	0.472038	0.881578	0.535446	1.867600	**50**
50	0.355651	0.934619	0.380530	2.627912	**10**	**20**	0.474600	0.880201	0.539195	1.854616	**40**
21° 0′	0.358368	0.933580	0.383864	2.605089	**69° 0′**	**30**	0.477159	0.878817	0.542956	1.841771	**30**
10	0.361082	0.932534	0.387205	2.582609	**50**	**40**	0.479713	0.877425	0.546728	1.829063	**20**
20	0.363793	0.931480	0.390554	2.560465	**40**	**50**	0.482263	0.876026	0.550513	1.816489	**10**
30	0.366501	0.930418	0.393910	2.538648	**30**	**29° 0′**	0.484810	0.874620	0.554309	1.804048	**61° 0′**
40	0.369206	0.929348	0.397275	2.517151	**20**	**10**	0.487352	0.873206	0.558118	1.791736	**50**
50	0.371908	0.928270	0.400646	2.495966	**10**	**20**	0.489890	0.871784	0.561939	1.779552	**40**
22° 0′	0.374607	0.927184	0.404026	2.475087	**68° 0′**	**30**	0.492424	0.870356	0.565773	1.767494	**30**
10	0.377302	0.926090	0.407414	2.454506	**50**	**40**	0.494953	0.868920	0.569619	1.755559	**20**
20	0.379994	0.924989	0.410810	2.434217	**40**	**50**	0.497479	0.867476	0.573478	1.743745	**10**
22° 30	0.382683	0.923880	0.414214	2.414214	**67° 30**	**30° 0′**	0.500000	0.866025	0.577350	1.732051	**60° 0′**
	cos	sin	cot	tan	Angle		cos	sin	cot	tan	Angle

For angles 15° to 30° 0′ (angles found in a column to the left of the data), use the column labels at the top of the table; for angles 60° to 75° 0′ (angles found in a column to the right of the data), use the column labels at the bottom of the table.

Copyright 2004, Industrial Press, Inc., New York, NY

Trigonometric Functions of Angles from 30° to 60°

Angle	sin	cos	tan	cot		Angle	sin	cos	tan	cot	
30° 0′	0.500000	0.866025	0.577350	1.732051	**60° 0′**	**37° 30′**	0.608761	0.793353	0.767327	1.303225	**52° 30′**
10	0.502517	0.864567	0.581235	1.720474	**50**	**40**	0.611067	0.791579	0.771959	1.295406	**20**
20	0.505030	0.863102	0.585134	1.709012	**40**	**50**	0.613367	0.789798	0.776612	1.287645	**10**
30	0.507538	0.861629	0.589045	1.697663	**30**	**38° 0′**	0.615661	0.788011	0.781286	1.279942	**52° 0′**
40	0.510043	0.860149	0.592970	1.686426	**20**	**10**	0.617951	0.786217	0.785981	1.272296	**50**
50	0.512543	0.858662	0.596908	1.675299	**10**	**20**	0.620235	0.784416	0.790697	1.264706	**40**
31° 0′	0.515038	0.857167	0.600861	1.664279	**59° 0′**	**30**	0.622515	0.782608	0.795436	1.257172	**30**
10	0.517529	0.855665	0.604827	1.653366	**50**	**40**	0.624789	0.780794	0.800196	1.249693	**20**
20	0.520016	0.854156	0.608807	1.642558	**40**	**50**	0.627057	0.778973	0.804979	1.242268	**10**
30	0.522499	0.852640	0.612801	1.631852	**30**	**39° 0′**	0.629320	0.777146	0.809784	1.234897	**51° 0′**
40	0.524977	0.851117	0.616809	1.621247	**20**	**10**	0.631578	0.775312	0.814612	1.227579	**50**
50	0.527450	0.849586	0.620832	1.610742	**10**	**20**	0.633831	0.773472	0.819463	1.220312	**40**
32° 0′	0.529919	0.848048	0.624869	1.600335	**58° 0′**	**30**	0.636078	0.771625	0.824336	1.213097	**30**
10	0.532384	0.846503	0.628921	1.590024	**50**	**40**	0.638320	0.769771	0.829234	1.205933	**20**
20	0.534844	0.844951	0.632988	1.579808	**40**	**50**	0.640557	0.767911	0.834155	1.198818	**10**
30	0.537300	0.843391	0.637070	1.569686	**30**	**40° 0′**	0.642788	0.766044	0.839100	1.191754	**50° 0′**
40	0.539751	0.841825	0.641167	1.559655	**20**	**10**	0.645013	0.764171	0.844069	1.184738	**50**
50	0.542197	0.840251	0.645280	1.549715	**10**	**20**	0.647233	0.762292	0.849062	1.177770	**40**
33° 0′	0.544639	0.838671	0.649408	1.539865	**57° 0′**	**30**	0.649448	0.760406	0.854081	1.170850	**30**
10	0.547076	0.837083	0.653551	1.530102	**50**	**40**	0.651657	0.758514	0.859124	1.163976	**20**
20	0.549509	0.835488	0.657710	1.520426	**40**	**50**	0.653861	0.756615	0.864193	1.157149	**10**
30	0.551937	0.833886	0.661886	1.510835	**30**	**41° 0′**	0.656059	0.754710	0.869287	1.150368	**49° 0′**
40	0.554360	0.832277	0.666077	1.501328	**20**	**10**	0.658252	0.752798	0.874407	1.143633	**50**
50	0.556779	0.830661	0.670284	1.491904	**10**	**20**	0.660439	0.750880	0.879553	1.136941	**40**
34° 0′	0.559193	0.829038	0.674509	1.482561	**56° 0′**	**30**	0.662620	0.748956	0.884725	1.130294	**30**
10	0.561602	0.827407	0.678749	1.473298	**50**	**40**	0.664796	0.747025	0.889924	1.123691	**20**
20	0.564007	0.825770	0.683007	1.464115	**40**	**50**	0.666966	0.745088	0.895151	1.117130	**10**
30	0.566406	0.824126	0.687281	1.455009	**30**	**42° 0′**	0.669131	0.743145	0.900404	1.110613	**48° 0′**
40	0.568801	0.822475	0.691572	1.445980	**20**	**10**	0.671289	0.741195	0.905685	1.104137	**50**
50	0.571191	0.820817	0.695881	1.437027	**10**	**20**	0.673443	0.739239	0.910994	1.097702	**40**
35° 0′	0.573576	0.819152	0.700208	1.428148	**55° 0′**	**30**	0.675590	0.737277	0.916331	1.091309	**30**
10	0.575957	0.817480	0.704551	1.419343	**50**	**40**	0.677732	0.735309	0.921697	1.084955	**20**
20	0.578332	0.815801	0.708913	1.410610	**40**	**50**	0.679868	0.733334	0.927091	1.078642	**10**
30	0.580703	0.814116	0.713293	1.401948	**30**	**43° 0′**	0.681998	0.731354	0.932515	1.072369	**47° 0′**
40	0.583069	0.812423	0.717691	1.393357	**20**	**10**	0.684123	0.729367	0.937968	1.066134	**50**
50	0.585429	0.810723	0.722108	1.384835	**10**	**20**	0.686242	0.727374	0.943451	1.059938	**40**
36° 0′	0.587785	0.809017	0.726543	1.376382	**54° 0′**	**30**	0.688355	0.725374	0.948965	1.053780	**30**
10	0.590136	0.807304	0.730996	1.367996	**50**	**40**	0.690462	0.723369	0.954508	1.047660	**20**
20	0.592482	0.805584	0.735469	1.359676	**40**	**50**	0.692563	0.721357	0.960083	1.041577	**10**
30	0.594823	0.803857	0.739961	1.351422	**30**	**44° 0′**	0.694658	0.719340	0.965689	1.035530	**46° 0′**
40	0.597159	0.802123	0.744472	1.343233	**20**	**10**	0.696748	0.717316	0.971326	1.029520	**50**
50	0.599489	0.800383	0.749003	1.335108	**10**	**20**	0.698832	0.715286	0.976996	1.023546	**40**
37° 0′	0.601815	0.798636	0.753554	1.327045	**53° 0′**	**30**	0.700909	0.713250	0.982697	1.017607	**30**
10	0.604136	0.796882	0.758125	1.319044	**50**	**40**	0.702981	0.711209	0.988432	1.011704	**20**
20	0.606451	0.795121	0.762716	1.311105	**40**	**50**	0.705047	0.709161	0.994199	1.005835	**10**
37° 30	0.608761	0.793353	0.767327	1.303225	**52° 30**	**45° 0′**	0.707107	0.707107	1.000000	1.000000	**45° 0′**
	cos	sin	cot	tan	Angle		cos	sin	cot	tan	Angle

For angles 30° to 45° 0′ (angles found in a column to the left of the data), use the column labels at the top of the table; for angles 45° to 60° 0′ (angles found in a column to the right of the data), use the column labels at the bottom of the table.

Copyright 2004, Industrial Press, Inc., New York, NY

Using a Calculator to Find Trig Functions.— A scientific calculator is quicker and more accurate than tables for finding trig functions and angles corresponding to trig functions. On scientific calculators, the keys labeled **sin**, **cos**, and **tan** are used to find the common trig functions. The other functions can be found by using the same keys and the **1/*x*** key, noting that csc $A = 1/\sin A$, sec $A = 1/\cos A$, and cot $A = 1/\tan A$. The specific keystrokes used will vary slightly from one calculator to another. To find the angle corresponding to a given trig function use the keys labeled **sin**$^{-1}$, **cos**$^{-1}$, and **tan**$^{-1}$. On some other calculators, the **sin**, **cos**, and **tan** are used in combination with the **INV,** or inverse, key to find the number corresponding to a given trig function.

If a scientific calculator or computer is not available, tables are the easiest way to find trig values. However, trig function values can be calculated very accurately without a scientific calculator by using the following formulas:

$$\sin A = A - \frac{A^3}{3!} + \frac{A^5}{5!} - \frac{A^7}{7!} \pm \cdots \qquad \cos A = 1 - \frac{A^2}{2!} + \frac{A^4}{4!} - \frac{A^6}{6!} \pm \cdots$$

$$\sin^{-1} A = \frac{1}{2} \times \frac{A^3}{3} + \frac{1}{2} \times \frac{3}{4} \times \frac{A^5}{5} + \cdots \qquad \tan^{-1} A = A - \frac{A^3}{3} + \frac{A^5}{5} - \frac{A^7}{7} \pm \cdots$$

where the angle A is expressed in radians (convert degrees to radians by multiplying degrees by $\pi/180 = 0.0174533$). The three dots at the ends of the formulas indicate that the expression continues with more terms following the sequence established by the first few terms. Generally, calculating just three or four terms of the expression is sufficient for accuracy. In these formulas, a number followed by the symbol **!** is called a factorial (for example, 3! is three factorial). Except for 0!, which is defined as 1, a factorial is found by multiplying together all the integers greater than zero and less than or equal to the factorial number wanted. For example: $3! = 1 \times 2 \times 3 = 6$; $4! = 1 \times 2 \times 3 \times 4 = 24$; $7! = 1 \times 2 \times 3 \times 4 \times 5 \times 6 \times 7 = 5040$; etc.

Versed Sine and Versed Cosine.— These functions are sometimes used in formulas for segments of a circle and may be obtained using the relationships:

$$\text{versed } \sin\theta = 1 - \cos\theta; \text{ versed } \cos\theta = 1 - \sin\theta.$$

Sevolute Functions.— Sevolute functions are used in calculating the form diameter of involute splines. They are computed by subtracting the involute function of an angle from the secant of the angle (1/cosine = secant). Thus, sevolute of 20 degrees = secant of 20 degrees – involute function of 20 degrees = 1.064178 – 0.014904 = 1.049274.

Involute Functions.— Involute functions are used in certain formulas relating to the design and measurement of gear teeth as well as measurement of threads over wires. See, for example, pages 1901 through 1904, 2111, and 2175.

The tables on the following pages provide values of involute functions for angles from 14 to 51 degrees in increments of 1 minute. These involute functions were calculated from the following formulas: Involute of $\theta = \tan\theta - \theta$, for θ in radians, and involute of $\theta = \tan\theta - \pi \times \theta/180$, for θ in degrees.

Example: For an angle of 14 degrees and 10 minutes, the involute function is found as follows: 10 minutes = 10/60 = 0.166666 degrees, 14 + 0.166666 = 14.166666 degree, so that the involute of 14.166666 degrees = tan 14.166666 – $\pi \times$ 14.166666/180 = 0.252420 – 0.247255 = 0.005165. This value is the same as that in the table *Involute Functions for Angles from 14 to 23 Degrees* for 14 degrees and 10 minutes. The same result would be obtained from using the conversion tables beginning on page 96 to convert 14 degrees and 10 minutes to radians and then applying the first of the formulas given above.

Copyright 2004, Industrial Press, Inc., New York, NY

Involute Functions for Angles from 14 to 23 Degrees

	Degrees								
	14	15	16	17	18	19	20	21	22
Minutes	Involute Functions								
0	0.004982	0.006150	0.007493	0.009025	0.010760	0.012715	0.014904	0.017345	0.020054
1	0.005000	0.006171	0.007517	0.009052	0.010791	0.012750	0.014943	0.017388	0.020101
2	0.005018	0.006192	0.007541	0.009079	0.010822	0.012784	0.014982	0.017431	0.020149
3	0.005036	0.006213	0.007565	0.009107	0.010853	0.012819	0.015020	0.017474	0.020197
4	0.005055	0.006234	0.007589	0.009134	0.010884	0.012854	0.015059	0.017517	0.020244
5	0.005073	0.006255	0.007613	0.009161	0.010915	0.012888	0.015098	0.017560	0.020292
6	0.005091	0.006276	0.007637	0.009189	0.010946	0.012923	0.015137	0.017603	0.020340
7	0.005110	0.006297	0.007661	0.009216	0.010977	0.012958	0.015176	0.017647	0.020388
8	0.005128	0.006318	0.007686	0.009244	0.011008	0.012993	0.015215	0.017690	0.020436
9	0.005146	0.006340	0.007710	0.009272	0.011039	0.013028	0.015254	0.017734	0.020484
10	0.005165	0.006361	0.007735	0.009299	0.011071	0.013063	0.015293	0.017777	0.020533
11	0.005184	0.006382	0.007759	0.009327	0.011102	0.013098	0.015333	0.017821	0.020581
12	0.005202	0.006404	0.007784	0.009355	0.011133	0.013134	0.015372	0.017865	0.020629
13	0.005221	0.006425	0.007808	0.009383	0.011165	0.013169	0.015411	0.017908	0.020678
14	0.005239	0.006447	0.007833	0.009411	0.011196	0.013204	0.015451	0.017952	0.020726
15	0.005258	0.006469	0.007857	0.009439	0.011228	0.013240	0.015490	0.017996	0.020775
16	0.005277	0.006490	0.007882	0.009467	0.011260	0.013275	0.015530	0.018040	0.020824
17	0.005296	0.006512	0.007907	0.009495	0.011291	0.013311	0.015570	0.018084	0.020873
18	0.005315	0.006534	0.007932	0.009523	0.011323	0.013346	0.015609	0.018129	0.020921
19	0.005334	0.006555	0.007957	0.009552	0.011355	0.013382	0.015649	0.018173	0.020970
20	0.005353	0.006577	0.007982	0.009580	0.011387	0.013418	0.015689	0.018217	0.021019
21	0.005372	0.006599	0.008007	0.009608	0.011419	0.013454	0.015729	0.018262	0.021069
22	0.005391	0.006621	0.008032	0.009637	0.011451	0.013490	0.015769	0.018306	0.021118
23	0.005410	0.006643	0.008057	0.009665	0.011483	0.013526	0.015809	0.018351	0.021167
24	0.005429	0.006665	0.008082	0.009694	0.011515	0.013562	0.015850	0.018395	0.021217
25	0.005448	0.006687	0.008107	0.009722	0.011547	0.013598	0.015890	0.018440	0.021266
26	0.005467	0.006709	0.008133	0.009751	0.011580	0.013634	0.015930	0.018485	0.021316
27	0.005487	0.006732	0.008158	0.009780	0.011612	0.013670	0.015971	0.018530	0.021365
28	0.005506	0.006754	0.008183	0.009808	0.011644	0.013707	0.016011	0.018575	0.021415
29	0.005525	0.006776	0.008209	0.009837	0.011677	0.013743	0.016052	0.018620	0.021465
30	0.005545	0.006799	0.008234	0.009866	0.011709	0.013779	0.016092	0.018665	0.021514
31	0.005564	0.006821	0.008260	0.009895	0.011742	0.013816	0.016133	0.018710	0.021564
32	0.005584	0.006843	0.008285	0.009924	0.011775	0.013852	0.016174	0.018755	0.021614
33	0.005603	0.006866	0.008311	0.009953	0.011807	0.013889	0.016215	0.018800	0.021665
34	0.005623	0.006888	0.008337	0.009982	0.011840	0.013926	0.016255	0.018846	0.021715
35	0.005643	0.006911	0.008362	0.010011	0.011873	0.013963	0.016296	0.018891	0.021765
36	0.005662	0.006934	0.008388	0.010041	0.011906	0.013999	0.016337	0.018937	0.021815
37	0.005682	0.006956	0.008414	0.010070	0.011939	0.014036	0.016379	0.018983	0.021866
38	0.005702	0.006979	0.008440	0.010099	0.011972	0.014073	0.016420	0.019028	0.021916
39	0.005722	0.007002	0.008466	0.010129	0.012005	0.014110	0.016461	0.019074	0.021967
40	0.005742	0.007025	0.008492	0.010158	0.012038	0.014148	0.016502	0.019120	0.022018
41	0.005762	0.007048	0.008518	0.010188	0.012071	0.014185	0.016544	0.019166	0.022068
42	0.005782	0.007071	0.008544	0.010217	0.012105	0.014222	0.016585	0.019212	0.022119
43	0.005802	0.007094	0.008571	0.010247	0.012138	0.014259	0.016627	0.019258	0.022170
44	0.005822	0.007117	0.008597	0.010277	0.012172	0.014297	0.016669	0.019304	0.022221
45	0.005842	0.007140	0.008623	0.010307	0.012205	0.014334	0.016710	0.019350	0.022272
46	0.005862	0.007163	0.008650	0.010336	0.012239	0.014372	0.016752	0.019397	0.022324
47	0.005882	0.007186	0.008676	0.010366	0.012272	0.014409	0.016794	0.019443	0.022375
48	0.005903	0.007209	0.008702	0.010396	0.012306	0.014447	0.016836	0.019490	0.022426
49	0.005923	0.007233	0.008729	0.010426	0.012340	0.014485	0.016878	0.019536	0.022478
50	0.005943	0.007256	0.008756	0.010456	0.012373	0.014523	0.016920	0.019583	0.022529
51	0.005964	0.007280	0.008782	0.010486	0.012407	0.014560	0.016962	0.019630	0.022581
52	0.005984	0.007303	0.008809	0.010517	0.012441	0.014598	0.017004	0.019676	0.022633
53	0.006005	0.007327	0.008836	0.010547	0.012475	0.014636	0.017047	0.019723	0.022684
54	0.006025	0.007350	0.008863	0.010577	0.012509	0.014674	0.017089	0.019770	0.022736
55	0.006046	0.007374	0.008889	0.010608	0.012543	0.014713	0.017132	0.019817	0.022788
56	0.006067	0.007397	0.008916	0.010638	0.012578	0.014751	0.017174	0.019864	0.022840
57	0.006087	0.007421	0.008943	0.010669	0.012612	0.014789	0.017217	0.019912	0.022892
58	0.006108	0.007445	0.008970	0.010699	0.012646	0.014827	0.017259	0.019959	0.022944
59	0.006129	0.007469	0.008998	0.010730	0.012681	0.014866	0.017302	0.020006	0.022997
60	0.006150	0.007493	0.009025	0.010760	0.012715	0.014904	0.017345	0.020054	0.023049

Copyright 2004, Industrial Press, Inc., New York, NY

Involute Functions for Angles from 23 to 32 Degrees

	Degrees								
	23	24	25	26	27	28	29	30	31
Minutes	Involute Functions								
0	0.023049	0.026350	0.029975	0.033947	0.038287	0.043017	0.048164	0.053752	0.059809
1	0.023102	0.026407	0.030039	0.034016	0.038362	0.043100	0.048253	0.053849	0.059914
2	0.023154	0.026465	0.030102	0.034086	0.038438	0.043182	0.048343	0.053946	0.060019
3	0.023207	0.026523	0.030166	0.034155	0.038514	0.043264	0.048432	0.054043	0.060124
4	0.023259	0.026581	0.030229	0.034225	0.038590	0.043347	0.048522	0.054140	0.060230
5	0.023312	0.026639	0.030293	0.034294	0.038666	0.043430	0.048612	0.054238	0.060335
6	0.023365	0.026697	0.030357	0.034364	0.038742	0.043513	0.048702	0.054336	0.060441
7	0.023418	0.026756	0.030420	0.034434	0.038818	0.043596	0.048792	0.054433	0.060547
8	0.023471	0.026814	0.030484	0.034504	0.038894	0.043679	0.048883	0.054531	0.060653
9	0.023524	0.026872	0.030549	0.034574	0.038971	0.043762	0.048973	0.054629	0.060759
10	0.023577	0.026931	0.030613	0.034644	0.039047	0.043845	0.049064	0.054728	0.060866
11	0.023631	0.026989	0.030677	0.034714	0.039124	0.043929	0.049154	0.054826	0.060972
12	0.023684	0.027048	0.030741	0.034785	0.039201	0.044012	0.049245	0.054924	0.061079
13	0.023738	0.027107	0.030806	0.034855	0.039278	0.044096	0.049336	0.055023	0.061186
14	0.023791	0.027166	0.030870	0.034926	0.039355	0.044180	0.049427	0.055122	0.061292
15	0.023845	0.027225	0.030935	0.034997	0.039432	0.044264	0.049518	0.055221	0.061400
16	0.023899	0.027284	0.031000	0.035067	0.039509	0.044348	0.049609	0.055320	0.061507
17	0.023952	0.027343	0.031065	0.035138	0.039586	0.044432	0.049701	0.055419	0.061614
18	0.024006	0.027402	0.031130	0.035209	0.039664	0.044516	0.049792	0.055518	0.061721
19	0.024060	0.027462	0.031195	0.035280	0.039741	0.044601	0.049884	0.055617	0.061829
20	0.024114	0.027521	0.031260	0.035352	0.039819	0.044685	0.049976	0.055717	0.061937
21	0.024169	0.027581	0.031325	0.035423	0.039897	0.044770	0.050068	0.055817	0.062045
22	0.024223	0.027640	0.031390	0.035494	0.039974	0.044855	0.050160	0.055916	0.062153
23	0.024277	0.027700	0.031456	0.035566	0.040052	0.044940	0.050252	0.056016	0.062261
24	0.024332	0.027760	0.031521	0.035637	0.040131	0.045024	0.050344	0.056116	0.062369
25	0.024386	0.027820	0.031587	0.035709	0.040209	0.045110	0.050437	0.056217	0.062478
26	0.024441	0.027880	0.031653	0.035781	0.040287	0.045195	0.050529	0.056317	0.062586
27	0.024495	0.027940	0.031718	0.035853	0.040366	0.045280	0.050622	0.056417	0.062695
28	0.024550	0.028000	0.031784	0.035925	0.040444	0.045366	0.050715	0.056518	0.062804
29	0.024605	0.028060	0.031850	0.035997	0.040523	0.045451	0.050808	0.056619	0.062913
30	0.024660	0.028121	0.031917	0.036069	0.040602	0.045537	0.050901	0.056720	0.063022
31	0.024715	0.028181	0.031983	0.036142	0.040680	0.045623	0.050994	0.056821	0.063131
32	0.024770	0.028242	0.032049	0.036214	0.040759	0.045709	0.051087	0.056922	0.063241
33	0.024825	0.028302	0.032116	0.036287	0.040839	0.045795	0.051181	0.057023	0.063350
34	0.024881	0.028363	0.032182	0.036359	0.040918	0.045881	0.051274	0.057124	0.063460
35	0.024936	0.028424	0.032249	0.036432	0.040997	0.045967	0.051368	0.057226	0.063570
36	0.024992	0.028485	0.032315	0.036505	0.041077	0.046054	0.051462	0.057328	0.063680
37	0.025047	0.028546	0.032382	0.036578	0.041156	0.046140	0.051556	0.057429	0.063790
38	0.025103	0.028607	0.032449	0.036651	0.041236	0.046227	0.051650	0.057531	0.063901
39	0.025159	0.028668	0.032516	0.036724	0.041316	0.046313	0.051744	0.057633	0.064011
40	0.025214	0.028729	0.032583	0.036798	0.041395	0.046400	0.051838	0.057736	0.064122
41	0.025270	0.028791	0.032651	0.036871	0.041475	0.046487	0.051933	0.057838	0.064232
42	0.025326	0.028852	0.032718	0.036945	0.041556	0.046575	0.052027	0.057940	0.064343
43	0.025382	0.028914	0.032785	0.037018	0.041636	0.046662	0.052122	0.058043	0.064454
44	0.025439	0.028976	0.032853	0.037092	0.041716	0.046749	0.052217	0.058146	0.064565
45	0.025495	0.029037	0.032920	0.037166	0.041797	0.046837	0.052312	0.058249	0.064677
46	0.025551	0.029099	0.032988	0.037240	0.041877	0.046924	0.052407	0.058352	0.064788
47	0.025608	0.029161	0.033056	0.037314	0.041958	0.047012	0.052502	0.058455	0.064900
48	0.025664	0.029223	0.033124	0.037388	0.042039	0.047100	0.052597	0.058558	0.065012
49	0.025721	0.029285	0.033192	0.037462	0.042120	0.047188	0.052693	0.058662	0.065123
50	0.025778	0.029348	0.033260	0.037537	0.042201	0.047276	0.052788	0.058765	0.065236
51	0.025834	0.029410	0.033328	0.037611	0.042282	0.047364	0.052884	0.058869	0.065348
52	0.025891	0.029472	0.033397	0.037686	0.042363	0.047452	0.052980	.058973	0.065460
53	0.025948	0.029535	0.033465	0.037761	0.042444	0.047541	0.053076	0.059077	0.065573
54	0.026005	0.029598	0.033534	0.037835	0.042526	0.047630	0.053172	0.059181	0.065685
55	0.026062	0.029660	0.033602	0.037910	0.042608	0.047718	0.053268	0.059285	0.065798
56	0.026120	0.029723	0.033671	0.037985	0.042689	0.047807	0.053365	0.059390	0.065911
57	0.026177	0.029786	0.033740	0.038060	0.042771	0.047896	0.053461	0.059494	0.066024
58	0.026235	0.029849	0.033809	0.038136	0.042853	0.047985	0.053558	0.059599	0.066137
59	0.026292	0.029912	0.033878	0.038211	0.042935	0.048074	0.053655	0.059704	0.066251
60	0.026350	0.029975	0.033947	0.038287	0.043017	0.048164	0.053752	0.059809	0.066364

Copyright 2004, Industrial Press, Inc., New York, NY

Involute Functions for Angles from 32 to 41 Degrees

	Degrees								
	32	33	34	35	36	37	38	39	40
Minutes	Involute Functions								
0	0.066364	0.073449	0.081097	0.089342	0.098224	0.107782	0.118061	0.129106	0.140968
1	0.066478	0.073572	0.081229	0.089485	0.098378	0.107948	0.118238	0.129297	0.141173
2	0.066591	0.073695	0.081362	0.089628	0.098532	0.108113	0.118416	0.129488	0.141378
3	0.066705	0.073818	0.081494	0.089771	0.098686	0.108279	0.118594	0.129679	0.141584
4	0.066820	0.073941	0.081627	0.089914	0.098840	0.108445	0.118773	0.129870	0.141789
5	0.066934	0.074064	0.081760	0.090058	0.098994	0.108611	0.118951	0.130062	0.141995
6	0.067048	0.074188	0.081894	0.090201	0.099149	0.108777	0.119130	0.130254	0.142201
7	0.067163	0.074312	0.082027	0.090345	0.099303	0.108943	0.119309	0.130446	0.142408
8	0.067277	0.074435	0.082161	0.090489	0.099458	0.109110	0.119488	0.130639	0.142614
9	0.067392	0.074559	0.082294	0.090633	0.099614	0.109277	0.119667	0.130832	0.142821
10	0.067507	0.074684	0.082428	0.090777	0.099769	0.109444	0.119847	0.131025	0.143028
11	0.067622	0.074808	0.082562	0.090922	0.099924	0.109611	0.120027	0.131218	0.143236
12	0.067738	0.074932	0.082697	0.091067	0.100080	0.109779	0.120207	0.131411	0.143443
13	0.067853	0.075057	0.082831	0.091211	0.100236	0.109947	0.120387	0.131605	0.143651
14	0.067969	0.075182	0.082966	0.091356	0.100392	0.110114	0.120567	0.131799	0.143859
15	0.068084	0.075307	0.083101	0.091502	0.100549	0.110283	0.120748	0.131993	0.144068
16	0.068200	0.075432	0.083235	0.091647	0.100705	0.110451	0.120929	0.132187	0.144276
17	0.068316	0.075557	0.083371	0.091793	0.100862	0.110619	0.121110	0.132381	0.144485
18	0.068432	0.075683	0.083506	0.091938	0.101019	0.110788	0.121291	0.132576	0.144694
19	0.068549	0.075808	0.083641	0.092084	0.101176	0.110957	0.121473	0.132771	0.144903
20	0.068665	0.075934	0.083777	0.092230	0.101333	0.111126	0.121655	0.132966	0.145113
21	0.068782	0.076060	0.083913	0.092377	0.101490	0.111295	0.121837	0.133162	0.145323
22	0.068899	0.076186	0.084049	0.092523	0.101648	0.111465	0.122019	0.133358	0.145533
23	0.069016	0.076312	0.084185	0.092670	0.101806	0.111635	0.122201	0.133553	0.145743
24	0.069133	0.076439	0.084321	0.092816	0.101964	0.111805	0.122384	0.133750	0.145954
25	0.069250	0.076565	0.084458	0.092963	0.102122	0.111975	0.122567	0.133946	0.146165
26	0.069367	0.076692	0.084594	0.093111	0.102280	0.112145	0.122750	0.134143	0.146376
27	0.069485	0.076819	0.084731	0.093258	0.102439	0.112316	0.122933	0.134339	0.146587
28	0.069602	0.076946	0.084868	0.093406	0.102598	0.112486	0.123117	0.134537	0.146799
29	0.069720	0.077073	0.085005	0.093553	0.102757	0.112657	0.123300	0.134734	0.147010
30	0.069838	0.077200	0.085142	0.093701	0.102916	0.112829	0.123484	0.134931	0.147222
31	0.069956	0.077328	0.085280	0.093849	0.103075	0.113000	0.123668	0.135129	0.147435
32	0.070075	0.077455	0.085418	0.093998	0.103235	0.113172	0.123853	0.135327	0.147647
33	0.070193	0.077583	0.085555	0.094146	0.103395	0.113343	0.124037	0.135525	0.147860
34	0.070312	0.077711	0.085693	0.094295	0.103555	0.113515	0.124222	0.135724	0.148073
35	0.070430	0.077839	0.085832	0.094443	0.103715	0.113688	0.124407	0.135923	0.148286
36	0.070549	0.077968	0.085970	0.094593	0.103875	0.113860	0.124592	0.136122	0.148500
37	0.070668	0.078096	0.086108	0.094742	0.104036	0.114033	0.124778	0.136321	0.148714
38	0.070788	0.078225	0.086247	0.094891	0.104196	0.114205	0.124964	0.136520	0.148928
39	0.070907	0.078354	0.086386	0.095041	0.104357	0.114378	0.125150	0.136720	0.149142
40	0.071026	0.078483	0.086525	0.095190	0.104518	0.114552	0.125336	0.136920	0.149357
41	0.071146	0.078612	0.086664	0.095340	0.104680	0.114725	0.125522	0.137120	0.149572
42	0.071266	0.078741	0.086804	0.095490	0.104841	0.114899	0.125709	0.137320	0.149787
43	0.071386	0.078871	0.086943	0.095641	0.105003	0.115073	0.125896	0.137521	0.150002
44	0.071506	0.079000	0.087083	0.095791	0.105165	0.115247	0.126083	0.137722	0.150218
45	0.071626	0.079130	0.087223	0.095942	0.105327	0.115421	0.126270	0.137923	0.150434
46	0.071747	0.079260	0.087363	0.096093	0.105489	0.115595	0.126457	0.138124	0.150650
47	0.071867	0.079390	0.087503	0.096244	0.105652	0.115770	0.126645	0.138326	0.150866
48	0.071988	0.079520	0.087644	0.096395	0.105814	0.115945	0.126833	0.138528	0.151083
49	0.072109	0.079651	0.087784	0.096546	0.105977	0.116120	0.127021	0.138730	0.151299
50	0.072230	0.079781	0.087925	0.096698	0.106140	0.116296	0.127209	0.138932	0.151517
51	0.072351	0.079912	0.088066	0.096850	0.106304	0.116471	0.127398	0.139134	0.151734
52	0.072473	0.080043	0.088207	0.097002	0.106467	0.116647	0.127587	0.139337	0.151952
53	0.072594	0.080174	0.088348	0.097154	0.106631	0.116823	0.127776	0.139540	0.152169
54	0.072716	0.080306	0.088490	0.097306	0.106795	0.116999	0.127965	0.139743	0.152388
55	0.072838	0.080437	0.088631	0.097459	0.106959	0.117175	0.128155	0.139947	0.152606
56	0.072960	0.080569	0.088773	0.097611	0.107123	0.117352	0.128344	0.140151	0.152825
57	0.073082	0.080700	0.088915	0.097764	0.107288	0.117529	0.128534	0.140355	0.153044
58	0.073204	0.080832	0.089057	0.097917	0.107452	0.117706	0.128725	0.140559	0.153263
59	0.073326	0.080964	0.089200	0.098071	0.107617	0.117883	0.128915	0.140763	0.153482
60	0.073449	0.081097	0.089342	0.098224	0.107782	0.118061	0.129106	0.140968	0.153702

Copyright 2004, Industrial Press, Inc., New York, NY

Involute Functions for Angles from 41 to 50 Degrees

	Degrees								
	41	42	43	44	45	46	47	48	49
Minutes	Involute Functions								
0	0.153702	0.167366	0.182024	0.197744	0.214602	0.232679	0.252064	0.272855	0.295157
1	0.153922	0.167602	0.182277	0.198015	0.214893	0.232991	0.252399	0.273214	0.295542
2	0.154142	0.167838	0.182530	0.198287	0.215184	0.233304	0.252734	0.273573	0.295928
3	0.154362	0.168075	0.182784	0.198559	0.215476	0.233616	0.253069	0.273933	0.296314
4	0.154583	0.168311	0.183038	0.198832	0.215768	0.233930	0.253405	0.274293	0.296701
5	0.154804	0.168548	0.183292	0.199104	0.216061	0.234243	0.253742	0.274654	0.297088
6	0.155025	0.168786	0.183547	0.199377	0.216353	0.234557	0.254078	0.275015	0.297475
7	0.155247	0.169023	0.183801	0.199651	0.216646	0.234871	0.254415	0.275376	0.297863
8	0.155469	0.169261	0.184057	0.199924	0.216940	0.235186	0.254753	0.275738	0.298251
9	0.155691	0.169500	0.184312	0.200198	0.217234	0.235501	0.255091	0.276101	0.298640
10	0.155913	0.169738	0.184568	0.200473	0.217528	0.235816	0.255429	0.276464	0.299029
11	0.156135	0.169977	0.184824	0.200747	0.217822	0.236132	0.255767	0.276827	0.299419
12	0.156358	0.170216	0.185080	0.201022	0.218117	0.236448	0.256106	0.277191	0.299809
13	0.156581	0.170455	0.185337	0.201297	0.218412	0.236765	0.256446	0.277555	0.300200
14	0.156805	0.170695	0.185594	0.201573	0.218708	0.237082	0.256786	0.277919	0.300591
15	0.157028	0.170935	0.185851	0.201849	0.219004	0.237399	0.257126	0.278284	0.300983
16	0.157252	0.171175	0.186109	0.202125	0.219300	0.237717	0.257467	0.278649	0.301375
17	0.157476	0.171415	0.186367	0.202401	0.219596	0.238035	0.257808	0.279015	0.301767
18	0.157701	0.171656	0.186625	0.202678	0.219893	0.238353	0.258149	0.279381	0.302160
19	0.157925	0.171897	0.186883	0.202956	0.220190	0.238672	0.258491	0.279748	0.302553
20	0.158150	0.172138	0.187142	0.203233	0.220488	0.238991	0.258833	0.280115	0.302947
21	0.158375	0.172380	0.187401	0.203511	0.220786	0.239310	0.259176	0.280483	0.303342
22	0.158601	0.172621	0.187661	0.203789	0.221084	0.239630	0.259519	0.280851	0.303736
23	0.158826	0.172864	0.187920	0.204067	0.221383	0.239950	0.259862	0.281219	0.304132
24	0.159052	0.173106	0.188180	0.204346	0.221682	0.240271	0.260206	0.281588	0.304527
25	0.159279	0.173349	0.188440	0.204625	0.221981	0.240592	0.260550	0.281957	0.304924
26	0.159505	0.173592	0.188701	0.204905	0.222281	0.240913	0.260895	0.282327	0.305320
27	0.159732	0.173835	0.188962	0.205185	0.222581	0.241235	0.261240	0.282697	0.305718
28	0.159959	0.174078	0.189223	0.205465	0.222881	0.241557	0.261585	0.283067	0.306115
29	0.160186	0.174322	0.189485	0.205745	0.223182	0.241879	0.261931	0.283438	0.306513
30	0.160414	0.174566	0.189746	0.206026	0.223483	0.242202	0.262277	0.283810	0.306912
31	0.160642	0.174811	0.190009	0.206307	0.223784	0.242525	0.262624	0.284182	0.307311
32	0.160870	0.175055	0.190271	0.206588	0.224086	0.242849	0.262971	0.284554	0.307710
33	0.161098	0.175300	0.190534	0.206870	0.224388	0.243173	0.263318	0.284927	0.308110
34	0.161327	0.175546	0.190797	0.207152	0.224690	0.243497	0.263666	0.285300	0.308511
35	0.161555	0.175791	0.191060	0.207434	0.224993	0.243822	0.264014	0.285673	0.308911
36	0.161785	0.176037	0.191324	0.207717	0.225296	0.244147	0.264363	0.286047	0.309313
37	0.162014	0.176283	0.191588	0.208000	0.225600	0.244472	0.264712	0.286422	0.309715
38	0.162244	0.176529	0.191852	0.208284	0.225904	0.244798	0.265062	0.286797	0.310117
39	0.162474	0.176776	0.192116	0.208567	0.226208	0.245125	0.265412	0.287172	0.310520
40	0.162704	0.177023	0.192381	0.208851	0.226512	0.245451	0.265762	0.287548	0.310923
41	0.162934	0.177270	0.192646	0.209136	0.226817	0.245778	0.266113	0.287924	0.311327
42	0.163165	0.177518	0.192912	0.209420	0.227123	0.246106	0.266464	0.288301	0.311731
43	0.163396	0.177766	0.193178	0.209705	0.227428	0.246433	0.266815	0.288678	0.312136
44	0.163628	0.178014	0.193444	0.209991	0.227734	0.246761	0.267167	0.289056	0.312541
45	0.163859	0.178262	0.193710	0.210276	0.228041	0.247090	0.267520	0.289434	0.312947
46	0.164091	0.178511	0.193977	0.210562	0.228347	0.247419	0.267872	0.289812	0.313353
47	0.164323	0.178760	0.194244	0.210849	0.228654	0.247748	0.268225	0.290191	0.313759
48	0.164556	0.179009	0.194511	0.211136	0.228962	0.248078	0.268579	0.290570	0.314166
49	0.164788	0.179259	0.194779	0.211423	0.229270	0.248408	0.268933	0.290950	0.314574
50	0.165021	0.179509	0.195047	0.211710	0.229578	0.248738	0.269287	0.291330	0.314982
51	0.165254	0.179759	0.195315	0.211998	0.229886	0.249069	0.269642	0.291711	0.315391
52	0.165488	0.180009	0.195584	0.212286	0.230195	0.249400	0.269998	0.292092	0.315800
53	0.165722	0.180260	0.195853	0.212574	0.230504	0.249732	0.270353	0.292474	0.316209
54	0.165956	0.180511	0.196122	0.212863	0.230814	0.250064	0.270709	0.292856	0.316619
55	0.166190	0.180763	0.196392	0.213152	0.231124	0.250396	0.271066	0.293238	0.317029
56	0.166425	0.181014	0.196661	0.213441	0.231434	0.250729	0.271423	0.293621	0.317440
57	0.166660	0.181266	0.196932	0.213731	0.231745	0.251062	0.271780	0.294004	0.317852
58	0.166895	0.181518	0.197202	0.214021	0.232056	0.251396	0.272138	0.294388	0.318264
59	0.167130	0.181771	0.197473	0.214311	0.232367	0.251730	0.272496	0.294772	0.318676
60	0.167366	0.182024	0.197744	0.214602	0.232679	0.252064	0.272855	0.295157	0.319089

Copyright 2004, Industrial Press, Inc., New York, NY

Compound Angles

Three types of compound angles are illustrated by Figs. 1 through 6. The first type is shown in Figs. 1, 2, and 3; the second in Fig. 4; and the third in Figs. 5 and 6.

In Fig. 1 is shown what might be considered as a thread-cutting tool without front clearance. A is a known angle in plane y–y of the top surface. C is the corresponding angle in plane x–x that is at some given angle B with plane y–y. Thus, angles A and B are components of the compound angle C.

Example Problem Referring to Fig. 1: Angle $2A$ in plane y–y is known, as is also angle B between planes x–x and y–y. It is required to find compound angle $2C$ in plane x–x.

Solution: Let $2A = 60$ and $B = 15$

Then

$$\tan C = \tan A \cos B = \tan 30 \cos 15$$

$$\tan C = 0.57735 \times 0.96592 = 0.55767$$

$$C = 29\ 8.8' \qquad 2C = 58\ 17.6'$$

Fig. 2 shows a thread-cutting tool with front clearance angle B. Angle A equals one-half the angle between the cutting edges in plane y–y of the top surface and compound angle C is one-half the angle between the cutting edges in a plane x–x at right angles to the inclined front edge of the tool. The angle between planes y–y and x–x is, therefore, equal to clearance angle B.

Example Problem Referring to Fig. 2: Find the angle $2C$ between the front faces of a thread-cutting tool having a known clearance angle B, which will permit the grinding of these faces so that their top edges will form the desired angle $2A$ for cutting the thread.

Solution: Let $2A = 60$ and $B = 15$

Then

$$\tan C = \frac{\tan A}{\cos B} = \frac{\tan 30°}{\cos 15°} = \frac{0.57735}{0.96592}$$

$$\tan C = 0.59772$$

$$C = 30\ 52' \qquad 2C = 61\ 44'$$

In Fig. 3 is shown a form-cutting tool in which the angle A is one-half the angle between the cutting edges in plane y–y of the top surface; B is the front clearance angle; and C is one-half the angle between the cutting edges in plane x–x at right angles to the front edges of the tool. The formula for finding angle C when angles A and B are known is the same as that for Fig. 2.

Example Problem Referring to Fig. 3: Find the angle $2C$ between the front faces of a form-cutting tool having a known clearance angle B that will permit the grinding of these faces so that their top edges will form the desired angle $2A$ for form cutting.

Solution: Let $2A = 46$ and $B = 12$

Then

$$\tan C = \frac{\tan A}{\cos B} = \frac{\tan 23°}{\cos 12°} = \frac{0.42447}{0.97815}$$

$$\tan C = 0.43395$$

$$C = 23\ 27.5' \qquad 2C = 46\ 55'$$

In Fig. 4 is shown a wedge-shaped block, the top surface of which is inclined at compound angle C with the base in a plane at right angles with the base and at angle R with the front edge. Angle A in the vertical plane of the front of the plate and angle B in the vertical plane of one side that is at right angles to the front are components of angle C.

Example Problem Referring to Fig. 4: Find the compound angle C of a wedge-shaped block having known component angles A and B in sides at right angles to each other.

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Compound Angles



Fig. 1.



Fig. 2.



Fig. 3.

For given angles A and B, find the resultant angle C in plane x–x. Angle B is measured in vertical plane y–y of midsection.

(Fig. 1) $\tan C = \tan A \times \cos B$

(Fig. 2) $\tan C = \dfrac{\tan A}{\cos B}$

(Fig. 3) (Same formula as for Fig. 2)



Fig. 4.

Fig. 4. In machining plate to angles A and B, it is held at angle C in plane x–x. Angle of rotation R in plane parallel to base (or complement of R) is for locating plate so that plane x–x is perpendicular to axis of pivot on angle-plate or work-holding vise.

$$\tan R = \frac{\tan B}{\tan A};\quad \tan C = \frac{\tan A}{\cos R}$$



Fig. 5.

Fig. 5. Angle R in horizontal plane parallel to base is angle from plane x–x to side having angle A.

$$\tan R = \frac{\tan A}{\tan B}$$

$\tan C = \tan A \cos R = \tan B \sin R$

Compound angle C is angle in plane x–x from base to corner formed by intersection of planes inclined to angles A and B. This formula for C may be used to find cot of complement of C_1, Fig. 6.



Fig. 6.

Fig. 6. Angles A_1 and B_1 are measured in vertical planes of front and side elevations. Plane x–x is located by angle R from centerline or from plane of angle B_1.

$$\tan R = \frac{\tan A_1}{\tan B_1}$$

$$\tan C_1 = \frac{\tan A_1}{\sin R} = \frac{\tan B_1}{\cos R}$$

The resultant angle C_1 would be required in drilling hole for pin.

C = compound angle in plane x–x and is the resultant of angles A and B

Copyright 2004, Industrial Press, Inc., New York, NY

Solution: Let $A = 47°14'$ and $B = 38°10'$

Then
$$\tan R = \frac{\tan B}{\tan A} = \frac{\tan 38°10'}{\tan 47°14'} = \frac{0.78598}{1.0812} = 0.72695 \qquad R = 36°09'$$
$$\tan C = \frac{\tan A}{\cos R} = \frac{\tan 47°14'}{\cos 36°0.9'} = \frac{1.0812}{0.80887} = 1.3367 \qquad C = 53°12'$$

In Fig. 5 is shown a four-sided block, two sides of which are at right angles to each other and to the base of the block. The other two sides are inclined at an oblique angle with the base. Angle C is a compound angle formed by the intersection of these two inclined sides and the intersection of a vertical plane passing through x–x, and the base of the block. The components of angle C are angles A and B and angle R is the angle in the base plane of the block between the plane of angle C and the plane of angle A.

Example Problem Referring to Fig. 5: Find the angles C and R in the block shown in Fig. 5 when angles A and B are known.

Solution: Let angle $A = 27°$ and $B = 36°$

Then
$$\cot C = \sqrt{\cot^2 A + \cot^2 B} = \sqrt{1.9626^2 + 1.3764^2} = \sqrt{5.74627572} = 2.3971$$
$$C = 22°38.6'$$
$$\tan R = \frac{\cot B}{\cot A} = \frac{\cot 36°}{\cot 27°} = \frac{1.3764}{1.9626} = 0.70131 \qquad R = 35°2.5'$$

Example Problem Referring to Fig. 6: A rod or pipe is inserted into a rectangular block at an angle. Angle C_1 is the compound angle of inclination (measured from the vertical) in a plane passing through the center line of the rod or pipe and at right angles to the top surface of the block. Angles A_1 and B_1 are the angles of inclination of the rod or pipe when viewed respectively in the front and side planes of the block. Angle R is the angle between the plane of angle C_1 and the plane of angle B_1. Find angles C_1 and R when a rod or pipe is inclined at known angles A_1 and B_1.

Solution: Let $A_1 = 39°$ and $B_1 = 34°$

Then
$$\tan C_1 = \sqrt{\tan^2 A_1 + \tan^2 B_1} = \sqrt{0.80978^2 + 0.67451^2} = 1.0539$$
$$C_1 = 46°30.2'$$
$$\tan R = \frac{\tan A_1}{\tan B_1} = \frac{0.80978}{0.67451} = 1.2005 \qquad R = 50°12.4'$$

Interpolation.— In mathematics, interpolation is the process of finding a value in a table or in a mathematical expression which falls between two given tabulated or known values. In engineering handbooks, the values of trigonometric functions are usually given to degrees and minutes; hence, if the given angle is to degrees, minutes and seconds, the value of the function is determined from the nearest given values, by interpolation.

Interpolation to Find Functions of an Angle: Assume that the sine of 14°22′26″ is to be determined. It is evident that this value lies between the sine of 14° 22′ and the sine of 14° 23′. Sine 14° 23′ = 0.24841 and sine 14° 22′ = 0.24813. The difference = 0.24841 − 0.24813 = 0.00028. Consider this difference as a whole number (28) and multiply it by a fraction having as its numerator the number of seconds (26) in the given angle, and as its denominator 60 (number of seconds in one minute). Thus $^{26}/_{60} \times 28 = 12$ nearly; hence, by adding 0.00012 to sine of 14° 22′ we find that sine 14°22′26″ = 0.24813 + 0.00012 = 0.24825. The correction value (represented in this example by 0.00012) is *added* to the function of the *smaller* angle nearest the given angle in dealing with *sines* or *tangents* but this correction value is *subtracted* in dealing with cosines or cotangents.

Copyright 2004, Industrial Press, Inc., New York, NY

LOGARITHMS

Logarithms have long been used to facilitate and shorten calculations involving multiplication, division, the extraction of roots, and obtaining powers of numbers; however, since the advent of hand-held calculators logarithms are rarely used for multiplication and division problems. Logarithms still come up in other problems, and the following properties of logarithms are useful:

$$\log_c c = 1 \qquad \log_c c^p = p \qquad \log_c 1 = 0$$

$$\log_c(a \times b) = \log_c a + \log_c b \qquad \log_c(a \div b) = \log_c a - \log_c b$$

$$\log_c(a^p) = p\log_c a \qquad \log_c(\sqrt[p]{a}) = 1/p\log_c a$$

The logarithm of a number is defined as the exponent of a base number raised to a power. For example, $\log_{10} 3.162277 = 0.500$ means the logarithm of 3.162277 is equal to 0.500. Another way of expressing the same relationship is $10^{0.500} = 3.162277$, where 10 is the base number and the exponent 0.500 is the logarithm of 3.162277. A common example of a logarithmic expression $10^2 = 100$ means that the base 10 logarithm of 100 is 2, that is, $\log_{10} 100 = 2.00$. There are two standard systems of logarithms in use: the "common" system (base 10) and the so-called "natural" system (base $e = 2.71828\ldots$). Logarithms to base e are frequently written using "ln" instead of "$\log_e$" such as $\ln 6.1 = 1.808289$. Logarithms of a number can be converted between the natural- and common-based systems as follows: $\ln_e A = 2.3026 \times \log_{10} A$ and $\log_{10} A = 0.43430 \times \ln_e A$. Additional information on the use of "natural logarithms" is given at the end of this section.

A logarithm consists of two parts, a whole number and a decimal. The whole number, which may be positive, negative, or zero, is called the characteristic; the decimal is called the mantissa. As a rule, only the decimal or mantissa is given in tables of common logarithms; tables of natural logarithms give both the characteristic and mantissa. The tables given in this section are abbreviated, but very accurate results can be obtained by using the method of interpolation described in *Interpolation from the Tables* on page 112. These tables are especially useful for finding logarithms and calculating powers and roots of numbers on calculators without these functions built in.

Evaluating Logarithms

Common Logarithms.— For common logarithms, the characteristic is prefixed to the mantissa according to the following rules: For numbers greater than or equal to 1, the characteristic is one less than the number of places to the left of the decimal point. For example, the characteristic of the logarithm of 237 is 2, and of 2536.5 is 3. For numbers smaller than 1 and greater than 0, the characteristic is negative and its numerical value is one more than the number of zeros immediately to the right of the decimal point. For example, the characteristic of the logarithm of 0.036 is –2, and the characteristic of the logarithm of 0.0006 is –4. The minus sign is usually written over the figure, as in $\overline{2}$ to indicate that the minus sign refers only to the characteristic and not to the mantissa, which is never negative. The logarithm of 0 does not exist.

The table of common logarithms in this section gives the mantissas of the logarithms of numbers from 1 to 10 and from 1.00 to 1.01. When finding the mantissa, the decimal point in a number is disregarded. The mantissa of the logarithms of 2716, 271.6, 27.16, 2.716, or 0.02716, for example, is the same. The tables give directly the mantissas of logarithms of numbers with three figures or less; the logarithms for numbers with four or more figures can be found by interpolation, as described in *Interpolation from the Tables* on page 112 and illustrated in the examples. All the mantissas in the common logarithmic tables are decimals and the decimal point has been omitted in the table. However, a decimal point should always be put before the mantissa as soon as it is taken from the table. Logarithmic

Copyright 2004, Industrial Press, Inc., New York, NY

tables are sufficient for many purposes, but electronic calculators and computers are faster, simpler, and more accurate than tables.

To find the common logarithm of a number from the tables, find the left-hand column of the table and follow down to locate the first two figures of the number. Then look at the top row of the table, on the same page, and follow across it to find the third figure of the number. Follow down the column containing this last figure until opposite the row on which the first two figures were found. The number at the intersection of the row and column is the mantissa of the logarithm. If the logarithm of a number with less than three figures is being obtained, add extra zeros to the right of the number so as to obtain three figures. For example, if the mantissa of the logarithm of 6 is required, find the mantissa of 600.

Interpolation from the Tables.— If the logarithm of a number with more than three figures is needed, linear interpolation is a method of using two values from the table to estimate the value of the logarithm desired. To find the logarithm of a number not listed in the tables, find the mantissa corresponding to the first three digits of the given number (disregarding the decimal point and leading zeros) and find the mantissa of the first three digits of the given number plus one. For example, to find the logarithm of 601.2, 60.12, or 0.006012, find the mantissa of 601 and find the mantissa of 602 from the tables. Then subtract the mantissa of the smaller number from the mantissa of the larger number and multiply the result by a decimal number made from the remaining (additional greater than 3) figures of the original number. Add the result to the mantissa of the smaller number. Find the characteristic as described previously.

Example: Find the logarithm of 4032. The characteristic portion of the logarithm found in the manner described before is 3. Find the mantissa by locating 40 in the left-hand column of the logarithmic tables and then follow across the top row of the table to the column headed 3. Follow down the 3 column to the intersection with the 40 row and read the mantissa. The mantissa of the logarithm of 4030 is 0.605305. Because 4032 is between 4030 and 4040, the logarithm of 4032 is the logarithm of 4030 plus two tenths of the difference in the logarithms of 4030 and 4040. Find the mantissa of 4040 and then subtract from it the mantissa of 4030. Multiply the difference obtained by 0.2 and add the result to the mantissa of the logarithm of 4030. Finally, add the characteristic portion of the logarithm. The result is $\log_{10} 4032 = 3 + 0.605305 + 0.2 \times (0.606381 - 0.605305) = 3.60552$.

Finding a Number Whose Logarithm Is Given.— When a logarithm is given and it is required to find the corresponding number, find the number in the body of the table equal to the value of the mantissa. This value may appear in any column 0 to 9. Follow the row on which the mantissa is found across to the left to read the first two digits of the number sought. Read the third digit of the number from the top row of the table by following up the column on which the mantissa is found to the top. If the characteristic of the logarithm is positive, the number of figures to the left of the decimal in the number is one greater than the value of the characteristic. For example, if the figures corresponding to a given mantissa are 376 and the characteristic is 5, then the number sought has six figures to the left of the decimal point and is 376,000. If the characteristic had been $\overline{3}$, then the number sought would have been 0.00376. If the mantissa is not exactly obtainable in the tables, find the mantissa in the table that is nearest to the one given and determine the corresponding number. This procedure usually gives sufficiently accurate results. If more accuracy is required, find the two mantissas in the tables nearest to the mantissa given, one smaller and the other larger. For each of the two mantissas, read the three corresponding digits from the left column and top row to obtain the first three figures of the number as described before. The exact number sought lies between the two numbers found in this manner.

Next: 1) subtract the smaller mantissa from the given mantissa and; and 2) subtract the smaller mantissa from the larger mantissa.

Divide the result of (1) by the result of (2) and add the quotient to the number corresponding to the smaller mantissa.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: Find the number whose logarithm is 2.70053. First, find the number closest to the mantissa 70053 in the body of the tables. The closest mantissa listed in the tables is 700704, so read across the table to the left to find the first two digits of the number sought (50) and up the column to find the third digit of the number (2). The characteristic of the logarithm given is 2, so the number sought has three digits to the left of the decimal point. Therefore, the number sought is slightly less than 502 and greater than 501. If greater accuracy is required, find the two mantissas in the table closest to the given mantissa (699838 and 700704). Subtract the smaller mantissa from the mantissa of the given logarithm and divide the result by the smaller mantissa subtracted from the larger mantissa. Add the result to the number corresponding to the smaller mantissa. The resulting answer is 501 + (700530 − 699838) ÷ (700704 − 699838) = 501 + 0.79 = 501.79.

Natural Logarithms.— In certain formulas and in some branches of mathematical analysis, use is made of logarithms (formerly also called Napierian or hyperbolic logarithms). As previously mentioned, the base of this system, $e = 2.7182818284\ldots$, is the limit of certain mathematical series. The logarithm of a number A to the base e is usually written $\log_e A$ or $\ln A$. Tables of natural logarithms for numbers ranging from 1 to 10 and 1.00 to 1.01 are given in this Handbook after the table of common logarithms. To obtain natural logs of numbers less than 1 or greater than 10, proceed as in the following examples: $\log_e 0.239 = \log_e 2.39 - \log_e 10$; $\log_e 0.0239 = \log_e 2.39 - 2\log_e 10$; $\log_e 239 = \log_e 2.39 + 2\log_e 10$; $\log_e 2390 = \log_e 2.39 + 3\log_e 10$, etc.

Using Calculators to Find Logarithms.— A scientific calculator is usually the quickest and most accurate method of finding logarithms and numbers corresponding to given logarithms. On most scientific calculators, the key labeled **log** is used to find common logarithms (base 10) and the key labeled **ln** is used for finding natural logarithms (base e). The keystrokes to find a logarithm will vary slightly from one calculator to another, so specific instructions are not given. To find the number corresponding to a given logarithm: use the key labeled $\mathbf{10^x}$ if a common logarithm is given or use the key labeled $\mathbf{e^x}$ if a natural logarithm is given; calculators without the 10^x or e^x keys may have a key labeled $\mathbf{x^y}$ that can be used by substituting 10 or e (2.718281…), as required, for x and substituting the logarithm whose corresponding number is sought for y. On some other calculators, the **log** and **ln** keys are used to find common and natural logarithms, and the same keys in combination with the **INV**, or inverse, key are used to find the number corresponding to a given logarithm.

Obtaining the Powers of Numbers.— A number may be raised to any power by simply multiplying the logarithm of the number by the exponent of the number. The product gives the logarithm of the value of the power.

Example 1: Find the value of 6.51^3

$$\log 6.51 = 0.81358$$
$$3 \times 0.81358 = 2.44074$$

The logarithm 2.44074 is the logarithm of 6.51^3. Hence, 6.51^3 equals the number corresponding to this logarithm, as found from the tables, or $6.51^3 = 275.9$.

Example 2: Find the value of $12^{1.29}$

$$\log 12 = 1.07918$$
$$1.29 \times 1.07918 = 1.39214$$

Hence, $12^{1.29} = 24.67$.

Raising a decimal to a decimal power presents a somewhat more difficult problem because of the negative characteristic of the logarithm and the fact that the logarithm must be multiplied by a decimal exponent. The method for avoiding the use of negative charac-

Copyright 2004, Industrial Press, Inc., New York, NY

teristics, that is adding a number to and subtracting it from the characteristic, as shown below, is helpful here.

Example 3: Find the value of $0.0813^{0.46}$

$$\log 0.0813 = \bar{2}.91009 = 8.91009 - 10$$

$$\log 0.0813^{0.46} = 0.46 \times (8.91009 - 10) = 4.09864 - 4.6$$

Subtract and add 0.6 to make the characteristic a whole number:

$$\begin{array}{rrr} & 4.09864 & -\ 4.6 \\ & -0.6 & +\ 0.6 \\ \hline \log 0.0813^{0.46} = & 3.49864 & -\ 4 \quad = \bar{1}.49864 \end{array}$$

Hence, $0.0813^{0.46} = 0.3152$.

Extracting Roots by Logarithms.— Roots of numbers, for example, $\sqrt[5]{37}$, can be extracted easily by means of logarithms. The small (^{5}) in the radical ($\sqrt{\ }$) of the root sign is called the index of the root. Any root of a number may be found by dividing its logarithm by the index of the root; the quotient is the logarithm of the root.

Example 1: Find $\sqrt[3]{276}$

$$\log 276 = 2.44091$$
$$2.44091 \div 3 = 0.81364$$

Hence, $\log \sqrt[3]{276} = 0.81364$ and $\sqrt[3]{276} = 6.511$

Example 2: Find $\sqrt[3]{0.67}$

$$\log 0.67 = \bar{1}.82607$$

Here it is not possible to divide directly, because there is a negative characteristic and a positive mantissa, another instance where the method of avoiding the use of negative characteristics, previously outlined, is helpful. The preferred procedure is to add and subtract some number to the characteristic that is evenly divisible by the index of the root. The root index is 3, so 9 can be added to and subtracted from the characteristic, and the resulting logarithm divided by 3.

$$\log\ 0.67 = \bar{1}.82607 = 8.82607 - 9$$

$$\log \sqrt[3]{0.67} = \frac{8.82607 - 9}{3} = 2.94202 - 3$$

$$\log \sqrt[3]{0.67} = 2.94202 - 3 = \bar{1}.94202$$

Hence, $\sqrt[3]{0.67} = 0.875$

Example 3: Find $\sqrt[1.7]{0.2}$

$$\log\ 0.2 = \bar{1}.30103 = 16.30103 - 17$$

$$\log \sqrt[1.7]{0.2} = \frac{16.30103 - 17}{1.7} = 9.58884 - 10 = \bar{1}.58884$$

Hence,

$$\sqrt[1.7]{0.2} = 0.388$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Logarithms

Table of Common Logarithms

	0	1	2	3	4	5	6	7	8	9
10	000000	004321	008600	012837	017033	021189	025306	029384	033424	037426
11	041393	045323	049218	053078	056905	060698	064458	068186	071882	075547
12	079181	082785	086360	089905	093422	096910	100371	103804	107210	110590
13	113943	117271	120574	123852	127105	130334	133539	136721	139879	143015
14	146128	149219	152288	155336	158362	161368	164353	167317	170262	173186
15	176091	178977	181844	184691	187521	190332	193125	195900	198657	201397
16	204120	206826	209515	212188	214844	217484	220108	222716	225309	227887
17	230449	232996	235528	238046	240549	243038	245513	247973	250420	252853
18	255273	257679	260071	262451	264818	267172	269513	271842	274158	276462
19	278754	281033	283301	285557	287802	290035	292256	294466	296665	298853
20	301030	303196	305351	307496	309630	311754	313867	315970	318063	320146
21	322219	324282	326336	328380	330414	332438	334454	336460	338456	340444
22	342423	344392	346353	348305	350248	352183	354108	356026	357935	359835
23	361728	363612	365488	367356	369216	371068	372912	374748	376577	378398
24	380211	382017	383815	385606	387390	389166	390935	392697	394452	396199
25	397940	399674	401401	403121	404834	406540	408240	409933	411620	413300
26	414973	416641	418301	419956	421604	423246	424882	426511	428135	429752
27	431364	432969	434569	436163	437751	439333	440909	442480	444045	445604
28	447158	448706	450249	451786	453318	454845	456366	457882	459392	460898
29	462398	463893	465383	466868	468347	469822	471292	472756	474216	475671
30	477121	478566	480007	481443	482874	484300	485721	487138	488551	489958
31	491362	492760	494155	495544	496930	498311	499687	501059	502427	503791
32	505150	506505	507856	509203	510545	511883	513218	514548	515874	517196
33	518514	519828	521138	522444	523746	525045	526339	527630	528917	530200
34	531479	532754	534026	535294	536558	537819	539076	540329	541579	542825
35	544068	545307	546543	547775	549003	550228	551450	552668	553883	555094
36	556303	557507	558709	559907	561101	562293	563481	564666	565848	567026
37	568202	569374	570543	571709	572872	574031	575188	576341	577492	578639
38	579784	580925	582063	583199	584331	585461	586587	587711	588832	589950
39	591065	592177	593286	594393	595496	596597	597695	598791	599883	600973
40	602060	603144	604226	605305	606381	607455	608526	609594	610660	611723
41	612784	613842	614897	615950	617000	618048	619093	620136	621176	622214
42	623249	624282	625312	626340	627366	628389	629410	630428	631444	632457
43	633468	634477	635484	636488	637490	638489	639486	640481	641474	642465
44	643453	644439	645422	646404	647383	648360	649335	650308	651278	652246
45	653213	654177	655138	656098	657056	658011	658965	659916	660865	661813
46	662758	663701	664642	665581	666518	667453	668386	669317	670246	671173
47	672098	673021	673942	674861	675778	676694	677607	678518	679428	680336
48	681241	682145	683047	683947	684845	685742	686636	687529	688420	689309
49	690196	691081	691965	692847	693727	694605	695482	696356	697229	698101
50	698970	699838	700704	701568	702431	703291	704151	705008	705864	706718
51	707570	708421	709270	710117	710963	711807	712650	713491	714330	715167
52	716003	716838	717671	718502	719331	720159	720986	721811	722634	723456
53	724276	725095	725912	726727	727541	728354	729165	729974	730782	731589
54	732394	733197	733999	734800	735599	736397	737193	737987	738781	739572
55	740363	741152	741939	742725	743510	744293	745075	745855	746634	747412
56	748188	748963	749736	750508	751279	752048	752816	753583	754348	755112
57	755875	756636	757396	758155	758912	759668	760422	761176	761928	762679
58	763428	764176	764923	765669	766413	767156	767898	768638	769377	770115
59	770852	771587	772322	773055	773786	774517	775246	775974	776701	777427

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Common Logarithms

	0	1	2	3	4	5	6	7	8	9
60	778151	778874	779596	780317	781037	781755	782473	783189	783904	784617
61	785330	786041	786751	787460	788168	788875	789581	790285	790988	791691
62	792392	793092	793790	794488	795185	795880	796574	797268	797960	798651
63	799341	800029	800717	801404	802089	802774	803457	804139	804821	805501
64	806180	806858	807535	808211	808886	809560	810233	810904	811575	812245
65	812913	813581	814248	814913	815578	816241	816904	817565	818226	818885
66	819544	820201	820858	821514	822168	822822	823474	824126	824776	825426
67	826075	826723	827369	828015	828660	829304	829947	830589	831230	831870
68	832509	833147	833784	834421	835056	835691	836324	836957	837588	838219
69	838849	839478	840106	840733	841359	841985	842609	843233	843855	844477
70	845098	845718	846337	846955	847573	848189	848805	849419	850033	850646
71	851258	851870	852480	853090	853698	854306	854913	855519	856124	856729
72	857332	857935	858537	859138	859739	860338	860937	861534	862131	862728
73	863323	863917	864511	865104	865696	866287	866878	867467	868056	868644
74	869232	869818	870404	870989	871573	872156	872739	873321	873902	874482
75	875061	875640	876218	876795	877371	877947	878522	879096	879669	880242
76	880814	881385	881955	882525	883093	883661	884229	884795	885361	885926
77	886491	887054	887617	888179	888741	889302	889862	890421	890980	891537
78	892095	892651	893207	893762	894316	894870	895423	895975	896526	897077
79	897627	898176	898725	899273	899821	900367	900913	901458	902003	902547
80	903090	903633	904174	904716	905256	905796	906335	906874	907411	907949
81	908485	909021	909556	910091	910624	911158	911690	912222	912753	913284
82	913814	914343	914872	915400	915927	916454	916980	917506	918030	918555
83	919078	919601	920123	920645	921166	921686	922206	922725	923244	923762
84	924279	924796	925312	925828	926342	926857	927370	927883	928396	928908
85	929419	929930	930440	930949	931458	931966	932474	932981	933487	933993
86	934498	935003	935507	936011	936514	937016	937518	938019	938520	939020
87	939519	940018	940516	941014	941511	942008	942504	943000	943495	943989
88	944483	944976	945469	945961	946452	946943	947434	947924	948413	948902
89	949390	949878	950365	950851	951338	951823	952308	952792	953276	953760
90	954243	954725	955207	955688	956168	956649	957128	957607	958086	958564
91	959041	959518	959995	960471	960946	961421	961895	962369	962843	963316
92	963788	964260	964731	965202	965672	966142	966611	967080	967548	968016
93	968483	968950	969416	969882	970347	970812	971276	971740	972203	972666
94	973128	973590	974051	974512	974972	975432	975891	976350	976808	977266
95	977724	978181	978637	979093	979548	980003	980458	980912	981366	981819
96	982271	982723	983175	983626	984077	984527	984977	985426	985875	986324
97	986772	987219	987666	988113	988559	989005	989450	989895	990339	990783
98	991226	991669	992111	992554	992995	993436	993877	994317	994757	995196
99	995635	996074	996512	996949	997386	997823	998259	998695	999131	999565
100	000000	000434	000868	001301	001734	002166	002598	003029	003461	003891
101	004321	004751	005181	005609	006038	006466	006894	007321	007748	008174
102	008600	009026	009451	009876	010300	010724	011147	011570	011993	012415
103	012837	013259	013680	014100	014521	014940	015360	015779	016197	016616
104	017033	017451	017868	018284	018700	019116	019532	019947	020361	020775
105	021189	021603	022016	022428	022841	023252	023664	024075	024486	024896
106	025306	025715	026125	026533	026942	027350	027757	028164	028571	028978
107	029384	029789	030195	030600	031004	031408	031812	032216	032619	033021
108	033424	033826	034227	034628	035029	035430	035830	036230	036629	037028
109	037426	037825	038223	038620	039017	039414	039811	040207	040602	040998

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Natural Logarithms

	0	1	2	3	4	5	6	7	8	9
1.0	0.00000	0.009950	0.019803	0.029559	0.039221	0.048790	0.058269	0.067659	0.076961	0.086178
1.1	0.09531	0.104360	0.113329	0.122218	0.131028	0.139762	0.148420	0.157004	0.165514	0.173953
1.2	0.18232	0.190620	0.198851	0.207014	0.215111	0.223144	0.231112	0.239017	0.246860	0.254642
1.3	0.26236	0.270027	0.277632	0.285179	0.292670	0.300105	0.307485	0.314811	0.322083	0.329304
1.4	0.33647	0.343590	0.350657	0.357674	0.364643	0.371564	0.378436	0.385262	0.392042	0.398776
1.5	0.40546	0.412110	0.418710	0.425268	0.431782	0.438255	0.444686	0.451076	0.457425	0.463734
1.6	0.47000	0.476234	0.482426	0.488580	0.494696	0.500775	0.506818	0.512824	0.518794	0.524729
1.7	0.53062	0.536493	0.542324	0.548121	0.553885	0.559616	0.565314	0.570980	0.576613	0.582216
1.8	0.58778	0.593327	0.598837	0.604316	0.609766	0.615186	0.620576	0.625938	0.631272	0.636577
1.9	0.64185	0.647103	0.652325	0.657520	0.662688	0.667829	0.672944	0.678034	0.683097	0.688135
2.0	0.69314	0.698135	0.703098	0.708036	0.712950	0.717840	0.722706	0.727549	0.732368	0.737164
2.1	0.74193	0.746688	0.751416	0.756122	0.760806	0.765468	0.770108	0.774727	0.779325	0.783902
2.2	0.78845	0.792993	0.797507	0.802002	0.806476	0.810930	0.815365	0.819780	0.824175	0.828552
2.3	0.83290	0.837248	0.841567	0.845868	0.850151	0.854415	0.858662	0.862890	0.867100	0.871293
2.4	0.87546	0.879627	0.883768	0.887891	0.891998	0.896088	0.900161	0.904218	0.908259	0.912283
2.5	0.91629	0.920283	0.924259	0.928219	0.932164	0.936093	0.940007	0.943906	0.947789	0.951658
2.6	0.95551	0.959350	0.963174	0.966984	0.970779	0.974560	0.978326	0.982078	0.985817	0.989541
2.7	0.99325	0.996949	1.000632	1.004302	1.007958	1.011601	1.015231	1.018847	1.022451	1.026042
2.8	1.02961	1.033184	1.036737	1.040277	1.043804	1.047319	1.050822	1.054312	1.057790	1.061257
2.9	1.06471	1.068153	1.071584	1.075002	1.078410	1.081805	1.085189	1.088562	1.091923	1.095273
3.0	1.09861	1.101940	1.105257	1.108563	1.111858	1.115142	1.118415	1.121678	1.124930	1.128171
3.1	1.13140	1.134623	1.137833	1.141033	1.144223	1.147402	1.150572	1.153732	1.156881	1.160021
3.2	1.16315	1.166271	1.169381	1.172482	1.175573	1.178655	1.181727	1.184790	1.187843	1.190888
3.3	1.19392	1.196948	1.199965	1.202972	1.205971	1.208960	1.211941	1.214913	1.217876	1.220830
3.4	1.22377	1.226712	1.229641	1.232560	1.235471	1.238374	1.241269	1.244155	1.247032	1.249902
3.5	1.25276	1.255616	1.258461	1.261298	1.264127	1.266948	1.269761	1.272566	1.275363	1.278152
3.6	1.28093	1.283708	1.286474	1.289233	1.291984	1.294727	1.297463	1.300192	1.302913	1.305626
3.7	1.30833	1.311032	1.313724	1.316408	1.319086	1.321756	1.324419	1.327075	1.329724	1.332366
3.8	1.33500	1.337629	1.340250	1.342865	1.345472	1.348073	1.350667	1.353255	1.355835	1.358409
3.9	1.36097	1.363537	1.366092	1.368639	1.371181	1.373716	1.376244	1.378766	1.381282	1.383791
4.0	1.38629	1.388791	1.391282	1.393766	1.396245	1.398717	1.401183	1.403643	1.406097	1.408545
4.1	1.41098	1.413423	1.415853	1.418277	1.420696	1.423108	1.425515	1.427916	1.430311	1.432701
4.2	1.43508	1.437463	1.439835	1.442202	1.444563	1.446919	1.449269	1.451614	1.453953	1.456287
4.3	1.45861	1.460938	1.463255	1.465568	1.467874	1.470176	1.472472	1.474763	1.477049	1.479329
4.4	1.48160	1.483875	1.486140	1.488400	1.490654	1.492904	1.495149	1.497388	1.499623	1.501853
4.5	1.50407	1.506297	1.508512	1.510722	1.512927	1.515127	1.517323	1.519513	1.521699	1.523880
4.6	1.52605	1.528228	1.530395	1.532557	1.534714	1.536867	1.539015	1.541159	1.543298	1.545433
4.7	1.54756	1.549688	1.551809	1.553925	1.556037	1.558145	1.560248	1.562346	1.564441	1.566530
4.8	1.56861	1.570697	1.572774	1.574846	1.576915	1.578979	1.581038	1.583094	1.585145	1.587192
4.9	1.58923	1.591274	1.593309	1.595339	1.597365	1.599388	1.601406	1.603420	1.605430	1.607436
5.0	1.60943	1.611436	1.613430	1.615420	1.617406	1.619388	1.621366	1.623341	1.625311	1.627278
5.1	1.62924	1.631199	1.633154	1.635106	1.637053	1.638997	1.640937	1.642873	1.644805	1.646734
5.2	1.64865	1.650580	1.652497	1.654411	1.656321	1.658228	1.660131	1.662030	1.663926	1.665818
5.3	1.66770	1.669592	1.671473	1.673351	1.675226	1.677097	1.678964	1.680828	1.682688	1.684545
5.4	1.68639	1.688249	1.690096	1.691939	1.693779	1.695616	1.697449	1.699279	1.701105	1.702928
5.5	1.70474	1.706565	1.708378	1.710188	1.711995	1.713798	1.715598	1.717395	1.719189	1.720979
5.6	1.722767	1.724551	1.726332	1.728109	1.729884	1.731656	1.733424	1.735189	1.736951	1.738710
5.7	1.74046	1.742219	1.743969	1.745716	1.747459	1.749200	1.750937	1.752672	1.754404	1.756132
5.8	1.75785	1.759581	1.761300	1.763017	1.764731	1.766442	1.768150	1.769855	1.771557	1.773256
5.9	1.77495	1.776646	1.778336	1.780024	1.781709	1.783391	1.785070	1.786747	1.788421	1.790091

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Natural Logarithms

	0	1	2	3	4	5	6	7	8	9
6.0	1.791759	1.793425	1.795087	1.796747	1.798404	1.800058	1.801710	1.803359	1.805005	1.806648
6.1	1.808289	1.809927	1.811562	1.813195	1.814825	1.816452	1.818077	1.819699	1.821318	1.822935
6.2	1.824549	1.826161	1.827770	1.829376	1.830980	1.832581	1.834180	1.835776	1.837370	1.838961
6.3	1.840550	1.842136	1.843719	1.845300	1.846879	1.848455	1.850028	1.851599	1.853168	1.854734
6.4	1.856298	1.857859	1.859418	1.860975	1.862529	1.864080	1.865629	1.867176	1.868721	1.870263
6.5	1.871802	1.873339	1.874874	1.876407	1.877937	1.879465	1.880991	1.882514	1.884035	1.885553
6.6	1.887070	1.888584	1.890095	1.891605	1.893112	1.894617	1.896119	1.897620	1.899118	1.900614
6.7	1.902108	1.903599	1.905088	1.906575	1.908060	1.909543	1.911023	1.912501	1.913977	1.915451
6.8	1.916923	1.918392	1.919859	1.921325	1.922788	1.924249	1.925707	1.927164	1.928619	1.930071
6.9	1.931521	1.932970	1.934416	1.935860	1.937302	1.938742	1.940179	1.941615	1.943049	1.944481
7.0	1.945910	1.947338	1.948763	1.950187	1.951608	1.953028	1.954445	1.955860	1.957274	1.958685
7.1	1.960095	1.961502	1.962908	1.964311	1.965713	1.967112	1.968510	1.969906	1.971299	1.972691
7.2	1.974081	1.975469	1.976855	1.978239	1.979621	1.981001	1.982380	1.983756	1.985131	1.986504
7.3	1.987874	1.989243	1.990610	1.991976	1.993339	1.994700	1.996060	1.997418	1.998774	2.000128
7.4	2.001480	2.002830	2.004179	2.005526	2.006871	2.008214	2.009555	2.010895	2.012233	2.013569
7.5	2.014903	2.016235	2.017566	2.018895	2.020222	2.021548	2.022871	2.024193	2.025513	2.026832
7.6	2.028148	2.029463	2.030776	2.032088	2.033398	2.034706	2.036012	2.037317	2.038620	2.039921
7.7	2.041220	2.042518	2.043814	2.045109	2.046402	2.047693	2.048982	2.050270	2.051556	2.052841
7.8	2.054124	2.055405	2.056685	2.057963	2.059239	2.060514	2.061787	2.063058	2.064328	2.065596
7.9	2.066863	2.068128	2.069391	2.070653	2.071913	2.073172	2.074429	2.075684	2.076938	2.078191
8.0	2.079442	2.080691	2.081938	2.083185	2.084429	2.085672	2.086914	2.088153	2.089392	2.090629
8.1	2.091864	2.093098	2.094330	2.095561	2.096790	2.098018	2.099244	2.100469	2.101692	2.102914
8.2	2.104134	2.105353	2.106570	2.107786	2.109000	2.110213	2.111425	2.112635	2.113843	2.115050
8.3	2.116256	2.117460	2.118662	2.119863	2.121063	2.122262	2.123458	2.124654	2.125848	2.127041
8.4	2.128232	2.129421	2.130610	2.131797	2.132982	2.134166	2.135349	2.136531	2.137710	2.138889
8.5	2.140066	2.141242	2.142416	2.143589	2.144761	2.145931	2.147100	2.148268	2.149434	2.150599
8.6	2.151762	2.152924	2.154085	2.155245	2.156403	2.157559	2.158715	2.159869	2.161022	2.162173
8.7	2.163323	2.164472	2.165619	2.166765	2.167910	2.169054	2.170196	2.171337	2.172476	2.173615
8.8	2.174752	2.175887	2.177022	2.178155	2.179287	2.180417	2.181547	2.182675	2.183802	2.184927
8.9	2.186051	2.187174	2.188296	2.189416	2.190536	2.191654	2.192770	2.193886	2.195000	2.196113
9.0	2.197225	2.198335	2.199444	2.200552	2.201659	2.202765	2.203869	2.204972	2.206074	2.207175
9.1	2.208274	2.209373	2.210470	2.211566	2.212660	2.213754	2.214846	2.215937	2.217027	2.218116
9.2	2.219203	2.220290	2.221375	2.222459	2.223542	2.224624	2.225704	2.226783	2.227862	2.228939
9.3	2.230014	2.231089	2.232163	2.233235	2.234306	2.235376	2.236445	2.237513	2.238580	2.239645
9.4	2.240710	2.241773	2.242835	2.243896	2.244956	2.246015	2.247072	2.248129	2.249184	2.250239
9.5	2.251292	2.252344	2.253395	2.254445	2.255493	2.256541	2.257588	2.258633	2.259678	2.260721
9.6	2.261763	2.262804	2.263844	2.264883	2.265921	2.266958	2.267994	2.269028	2.270062	2.271094
9.7	2.272126	2.273156	2.274186	2.275214	2.276241	2.277267	2.278292	2.279316	2.280339	2.281361
9.8	2.282382	2.283402	2.284421	2.285439	2.286456	2.287471	2.288486	2.289500	2.290513	2.291524
9.9	2.292535	2.293544	2.294553	2.295560	2.296567	2.297573	2.298577	2.299581	2.300583	2.301585
1.00	0.000000	0.001000	0.001998	0.002996	0.003992	0.004988	0.005982	0.006976	0.007968	0.008960
1.01	0.009950	0.010940	0.011929	0.012916	0.013903	0.014889	0.015873	0.016857	0.017840	0.018822
1.02	0.019803	0.020783	0.021761	0.022739	0.023717	0.024693	0.025668	0.026642	0.027615	0.028587
1.03	0.029559	0.030529	0.031499	0.032467	0.033435	0.034401	0.035367	0.036332	0.037296	0.038259
1.04	0.039221	0.040182	0.041142	0.042101	0.043059	0.044017	0.044973	0.045929	0.046884	0.047837
1.05	0.048790	0.049742	0.050693	0.051643	0.052592	0.053541	0.054488	0.055435	0.056380	0.057325
1.06	0.058269	0.059212	0.060154	0.061095	0.062035	0.062975	0.063913	0.064851	0.065788	0.066724
1.07	0.067659	0.068593	0.069526	0.070458	0.071390	0.072321	0.073250	0.074179	0.075107	0.076035
1.08	0.076961	0.077887	0.078811	0.079735	0.080658	0.081580	0.082501	0.083422	0.084341	0.085260
1.09	0.086178	0.087095	0.088011	0.088926	0.089841	0.090754	0.091667	0.092579	0.093490	0.094401

Copyright 2004, Industrial Press, Inc., New York, NY

MATRICES

A matrix is a set of real numbers arranged in rows and columns to form a rectangular array. A matrix with m rows and n columns is an $m \times n$ matrix (m by n) and may be written as

$$A_{mn} = \begin{bmatrix} a_{11} & a_{12} & \cdots & a_{1n} \\ a_{21} & a_{22} & \cdots & a_{2n} \\ \cdots & \cdots & \cdots & \cdots \\ a_{m1} & a_{m2} & \cdots & a_{mn} \end{bmatrix}$$

The a_{ij} terms are called the entries or elements of the matrix.The first subscript i identifies the row position of an entry, and the second subscript j identifies the column position in the matrix.

Some common matrix types have special names, as follows:

Column Matrix: A matrix that has only one column ($m \times 1$).

Diagonal Matrix: A square matrix in which all values are zero except for those on one of the diagonals. If the diagonal entries are all 1, the matrix is an *identity* matrix.

Identity Matrix: A diagonal matrix in which the diagonal entries are all 1.

Row Matrix: A matrix that has only one row ($1 \times n$).

Square Matrix: A matrix in which the number of rows and columns are equal, i.e., $m = n$.

Zero Matrix: A matrix in which all the entries of the matrix are zero. The zero matrix is also called the *null* matrix.

Matrix Operations

Matrix Addition and Subtraction.— Matrices can be added or subtracted if they have the same shape, that is, if number of columns in each matrix is the same, and the number of rows in each matrix is the same. The sum or difference of the matrices are determined by adding or subtracting the corresponding elements of each matrix. Thus, each element in the resultant matrix is formed using $c_{ij} = a_{ij} \pm b_{ij}$ as illustrated below:

$$\begin{bmatrix} c_{11} & c_{12} & c_{13} \\ c_{21} & c_{22} & c_{23} \\ c_{31} & c_{32} & c_{33} \end{bmatrix} = \begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \\ a_{31} & a_{32} & a_{33} \end{bmatrix} \pm \begin{bmatrix} b_{11} & b_{12} & b_{13} \\ b_{21} & b_{22} & b_{23} \\ b_{31} & b_{32} & b_{33} \end{bmatrix} = \begin{bmatrix} (a_{11} \pm b_{11}) & (a_{12} \pm b_{12}) & (a_{13} \pm b_{13}) \\ (a_{21} \pm b_{21}) & (a_{22} \pm b_{22}) & (a_{23} \pm b_{23}) \\ (a_{31} \pm b_{31}) & (a_{32} \pm b_{32}) & (a_{33} \pm b_{33}) \end{bmatrix}$$

Example 1

$$\begin{bmatrix} 4 & 6 & -5 \\ 5 & -7 & 8 \\ -8 & 6 & -7 \end{bmatrix} + \begin{bmatrix} 8 & -2 & 6 \\ -6 & 9 & 5 \\ 9 & -2 & 2 \end{bmatrix} = \begin{bmatrix} (4+8) & (6-2) & (-5+6) \\ (5-6) & (-7+9) & (8+5) \\ (-8+9) & (6-2) & (-7+2) \end{bmatrix} = \begin{bmatrix} 12 & 4 & 1 \\ -1 & 2 & 13 \\ 1 & 4 & -5 \end{bmatrix}$$

Matrix Multiplication.— Two matrices can be multiplied *only* when the number of columns in the first matrix is equal to the number of rows of the second matrix. Matrix multiplication is not commutative, thus, $A \times B$ is not necessarily equal to $B \times A$.

Each resulting entry c_{ij} in the product matrix, $C = A \times B$, is the sum of the products of each element in the i^{th} row of matrix A multiplied by the corresponding element in the j^{th} column of matrix B, as illustrated in the following:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \\ a_{31} & a_{32} & a_{33} \end{bmatrix} \times \begin{bmatrix} b_{11} & b_{12} & b_{13} \\ b_{21} & b_{22} & b_{23} \\ b_{31} & b_{32} & b_{33} \end{bmatrix}$$

$$= \begin{bmatrix} (a_{11}b_{11} + a_{12}b_{21} + a_{13}b_{31}) & (a_{11}b_{12} + a_{12}b_{22} + a_{13}b_{32}) & (a_{11}b_{13} + a_{12}b_{23} + a_{13}b_{33}) \\ (a_{21}b_{11} + a_{22}b_{21} + a_{23}b_{31}) & (a_{21}b_{12} + a_{22}b_{22} + a_{23}b_{32}) & (a_{21}b_{13} + a_{22}b_{23} + a_{23}b_{33}) \\ (a_{31}b_{11} + a_{32}b_{21} + a_{33}b_{31}) & (a_{31}b_{12} + a_{32}b_{22} + a_{33}b_{32}) & (a_{31}b_{13} + a_{32}b_{23} + a_{33}b_{33}) \end{bmatrix}$$

Example 2

$$\begin{bmatrix} 1 & 2 & 3 \\ 4 & 5 & 6 \\ 3 & 2 & 1 \end{bmatrix} \times \begin{bmatrix} 7 & 8 & 9 \\ 1 & 2 & 3 \\ 4 & 5 & 7 \end{bmatrix} = \begin{bmatrix} (1 \cdot 7 + 2 \cdot 1 + 3 \cdot 4) & (1 \cdot 8 + 2 \cdot 2 + 3 \cdot 5) & (1 \cdot 9 + 2 \cdot 3 + 3 \cdot 7) \\ (4 \cdot 7 + 5 \cdot 1 + 6 \cdot 4) & (4 \cdot 8 + 5 \cdot 2 + 6 \cdot 5) & (4 \cdot 9 + 5 \cdot 3 + 6 \cdot 7) \\ (3 \cdot 7 + 2 \cdot 1 + 1 \cdot 4) & (3 \cdot 8 + 2 \cdot 2 + 1 \cdot 5) & (3 \cdot 9 + 2 \cdot 3 + 1 \cdot 7) \end{bmatrix}$$

$$= \begin{bmatrix} (7 + 2 + 12) & (8 + 4 + 15) & (9 + 6 + 21) \\ (28 + 5 + 24) & (32 + 10 + 30) & (36 + 15 + 42) \\ (21 + 2 + 4) & (24 + 4 + 5) & (27 + 6 + 7) \end{bmatrix} = \begin{bmatrix} 21 & 27 & 36 \\ 57 & 72 & 93 \\ 27 & 33 & 40 \end{bmatrix}$$

Transpose of a Matrix.— If the rows of a matrix A_{mn} are interchanged with its columns, the new matrix is called the transpose of matrix A, or $A^{\mathrm{T}}{}_{nm}$. The first row of the matrix becomes the first column in the transposed matrix, the second row of the matrix becomes second column, and the third row of the matrix becomes third column.

Example 3:

$$A = \begin{bmatrix} 21 & 27 & 36 \\ 57 & 72 & 93 \\ 27 & 33 & 40 \end{bmatrix} \qquad A^T = \begin{bmatrix} 21 & 57 & 27 \\ 27 & 72 & 33 \\ 36 & 93 & 40 \end{bmatrix}$$

Determinant of a Square Matrix.— Every square matrix A is associated with a real number, its determinant, which may be written det (A) or $|A|$.

For $A = \begin{bmatrix} a_{11} & a_{12} \\ a_{21} & a_{22} \end{bmatrix}$, the determinant of A is

$$det(A) = |A| = \begin{vmatrix} a_{11} & a_{12} \\ a_{21} & a_{22} \end{vmatrix} = a_{11}a_{22} - a_{12}a_{21}$$

For a 3×3 matrix B, the determinant is

$$det(B) = \begin{vmatrix} b_{11} & b_{12} & b_{13} \\ b_{21} & b_{22} & b_{23} \\ b_{31} & b_{32} & b_{33} \end{vmatrix}$$

$$= (b_{11}b_{22}b_{33} - b_{11}b_{23}b_{32}) - (b_{12}b_{23}b_{31} - b_{12}b_{21}b_{33}) + (b_{13}b_{21}b_{32} - b_{13}b_{22}b_{31})$$

$$= b_{11}(b_{22}b_{33} - b_{23}b_{32}) - b_{12}(b_{23}b_{31} - b_{21}b_{33}) + b_{13}(b_{21}b_{32} - b_{22}b_{31})$$

The determinant of an $n \times n$ matrix results in n successive terms with alternating signs (+ or −). The troublesome task of keeping track of the proper sign for each term can be avoided by multiplying each term by $(-1)^{i+j}$ and adding all the terms. For example, using this rule, the last line of the previous equation can be rewritten as follows:

$$= (-1)^{(1+1)}b_{11}(b_{22}b_{33} - b_{23}b_{32}) + (-1)^{(1+2)}b_{12}(b_{23}b_{31} - b_{21}b_{33}) + (-1)^{(1+3)}b_{13}(b_{21}b_{32} - b_{22}b_{31})$$

Example 4: Find the determinant of the following matrix.

Copyright 2004, Industrial Press, Inc., New York, NY

$$A = \begin{bmatrix} 5 & 6 & 7 \\ 1 & 2 & 3 \\ 4 & 5 & 6 \end{bmatrix}$$

Solution:

$$\begin{aligned} det(A) &= (-1)^{(1+1)} \cdot 5 \cdot [(2 \times 6) - (5 \times 3)] \\ &\quad + (-1)^{(1+2)} \cdot 6 \cdot [(1 \times 6) - (4 \times 3)] \\ &\quad + (-1)^{(1+3)} \cdot 7 \cdot [(1 \times 5) - (2 \times 4)] \end{aligned}$$

$$\begin{aligned} det(A) &= 5(12 - 15) - 6(6 - 12) + 7(5 - 8) \\ &= 5(-3) - 6(-6) + 7(-3) = -15 + 36 - 21 = 0 \end{aligned}$$

Minors and Cofactors.— The minor M_{ij} of a matrix A is the determinant of a submatrix resulting from the elimination of row i and of column j. If A is a square matrix, the minor M_{ij} of the entry a_{ij} is the determinant of the matrix obtained by deleting the i^{th} row and j^{th} column of A.

The cofactor C_{ij} of the entry a_{ij} is given by $C_{ij} = (-1)^{(i+j)}M_{ij}$. When the matrix is formed by the cofactors, then it is called a cofactors matrix.

Example 5: Find the minors and cofactors of

$$A = \begin{bmatrix} 1 & 2 & 3 \\ 4 & 5 & 6 \\ 3 & 2 & 1 \end{bmatrix}$$

Solution: To determine the minor M_{11}, delete the first row and first column of A and find the determinant of the resulting matrix.

$$M_{11} = \begin{vmatrix} 5 & 6 \\ 2 & 1 \end{vmatrix} = (5 \times 1) - (6 \times 2) = 5 - 12 = -7$$

Similarly to find M_{12}, delete the first row and second column of A and find the determinant of the resulting matrix.

$$M_{12} = \begin{vmatrix} 4 & 6 \\ 3 & 1 \end{vmatrix} = (4 \times 1) - (6 \times 3) = 4 - 18 = -14$$

Continuing this way, we obtain the following minors:

$$\begin{array}{lll} M_{11} = -7 & M_{12} = -14 & M_{13} = -7 \\ M_{21} = -4 & M_{22} = -8 & M_{23} = -4 \\ M_{31} = -3 & M_{32} = -6 & M_{33} = -3 \end{array}$$

To find the cofactor $C_{ij} = (-1)^{(i+j)} \times M_{ij}$, thus $C_{11} = (-1)^{(1+1)} \times M_{11} = 1 \times (-7) = -7$

Similarly $C_{12} = (-1)^{(1+2)} \times M_{12} = -1 \times -14 = 14$, and continuing this way we obtain the following cofactors

$$\begin{array}{lll} C_{11} = -7 & C_{12} = 14 & C_{13} = -7 \\ C_{21} = 4 & C_{22} = -8 & C_{23} = 4 \\ C_{31} = -3 & C_{32} = 6 & C_{33} = -3 \end{array}$$

Adjoint of a Matrix.— The transpose of cofactor matrix is called the adjoint matrix. First determine the cofactor matrix and then transpose it to obtain the adjoint matrix.

Example 6: Find the adjoint matrix of A

Copyright 2004, Industrial Press, Inc., New York, NY

$$A = \begin{bmatrix} 1 & 2 & 3 \\ 4 & 5 & 6 \\ 3 & 2 & 1 \end{bmatrix}$$

Solution: The cofactor matrix from the above example is shown below at the left, and the adjoint matrix on the right.

$$Cofactor(A) = \begin{bmatrix} -7 & 14 & -7 \\ 4 & -8 & 4 \\ -3 & 6 & -3 \end{bmatrix} \qquad Adjoint(A) = \begin{bmatrix} -7 & 14 & -7 \\ 4 & -8 & 4 \\ -3 & 6 & -3 \end{bmatrix}^T = \begin{bmatrix} -7 & 4 & -3 \\ 14 & -8 & 6 \\ -7 & 4 & -3 \end{bmatrix}$$

Singularity and Rank of a Matrix.— A singular matrix is one whose determinant is zero. The rank of a matrix is the maximum number of linearly independent row or column vectors.

Inverse of a Matrix.— A square non-singular matrix A has an inverse A^{-1} such that the product of matrix A and inverse matrix A^{-1}, is the identity matrix I. Thus, $AA^{-1} = I$. The inverse is the ratio of adjoint of the matrix and the determinant of that matrix.

$$A^{-1} = \frac{Adjoint(A)}{|A|}$$

Example 7: What is the inverse of the following matrix?

$$A = \begin{bmatrix} 2 & 3 & 5 \\ 4 & 1 & 6 \\ 1 & 4 & 0 \end{bmatrix}$$

Solution: The basic formula of an inverse of a matrix is

$$A^{-1} = \frac{Adjoint(A)}{|A|}$$

The determinant of A is

$$\begin{aligned} |A| &= 2(1 \times 0 - 4 \times 6) - 3(4 \times 0 - 1 \times 6) + 5(4 \times 4 - 1 \times 1) \\ &= 2(0 - 24) - 3(0 - 6) + 5(16 - 1) \\ &= -48 + 18 + 75 = 45 \end{aligned}$$

The cofactors are

$$a_{11} = (-1)^{1+1}\begin{vmatrix} 1 & 6 \\ 4 & 0 \end{vmatrix} = -24 \qquad a_{12} = (-1)^{1+2}\begin{vmatrix} 4 & 6 \\ 1 & 0 \end{vmatrix} = 6 \qquad a_{13} = (-1)^{1+3}\begin{vmatrix} 4 & 1 \\ 1 & 4 \end{vmatrix} = 15$$

$$a_{21} = (-1)^{2+1}\begin{vmatrix} 3 & 5 \\ 4 & 0 \end{vmatrix} = 20 \qquad a_{22} = (-1)^{2+2}\begin{vmatrix} 2 & 5 \\ 1 & 0 \end{vmatrix} = -5 \qquad a_{23} = (-1)^{2+3}\begin{vmatrix} 2 & 3 \\ 1 & 4 \end{vmatrix} = -5$$

$$a_{31} = (-1)^{3+1}\begin{vmatrix} 3 & 5 \\ 1 & 6 \end{vmatrix} = 13 \qquad a_{32} = (-1)^{3+2}\begin{vmatrix} 2 & 5 \\ 4 & 6 \end{vmatrix} = 8 \qquad a_{33} = (-1)^{3+3}\begin{vmatrix} 2 & 3 \\ 4 & 1 \end{vmatrix} = -10$$

The matrix of cofactors is $\begin{bmatrix} -24 & 6 & 15 \\ 20 & -5 & -5 \\ 13 & 8 & -10 \end{bmatrix}$ and the adjoint matrix is $\begin{bmatrix} -24 & 20 & 13 \\ 6 & -5 & 8 \\ 15 & -5 & -10 \end{bmatrix}$

Then the inverse of matrix A is

$$A^{-1} = \frac{Adjoint(A)}{|A|} = \frac{1}{45}\begin{bmatrix} -24 & 20 & 13 \\ 6 & -5 & 8 \\ 15 & -5 & -10 \end{bmatrix}$$

Simultaneous Equations.— Matrices can be used to solve systems of simultaneous equations with a large number of unknowns. Generally, this method is less cumbersome than

Copyright 2004, Industrial Press, Inc., New York, NY

using substitution methods. The coefficients of the equations are placed in matrix form. The matrix is then manipulated into the Identity matrix, see below, to yield a solution.

$$\begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

Identity Matrix

Example 8: Solve the three simultaneous equations using matrix operations.

$$\begin{aligned} -4x_1 + 8x_2 + 12x_3 &= 16 \\ 3x_1 - x_2 + 2x_3 &= 5 \\ x_1 + 7x_2 + 6x_3 &= 10 \end{aligned}$$

Solution: First, place the equation coefficients and constants into matrix form. The object is to transform the coefficient matrix into the form shown below, thereby obtaining a solution to the system of equations.

$$\begin{bmatrix} -4 & 8 & 12 & 16 \\ 3 & -1 & 2 & 5 \\ 1 & 7 & 6 & 10 \end{bmatrix} \Leftrightarrow \begin{bmatrix} 1 & 0 & 0 & x_1 \\ 0 & 1 & 0 & x_2 \\ 0 & 0 & 1 & x_3 \end{bmatrix}$$

Transform the coefficient matrix so that element c_{11} is 1 and all other elements in the first column are 0, as follows: a) Divide *Row 1* (R_1) by –4; b) multiply new R_1 by –3, then add to R_2; and c) multiply R_1 by –1, then add to R_3.

$$\begin{bmatrix} \frac{-4}{-4} & \frac{8}{-4} & \frac{12}{-4} & \frac{16}{-4} \\ 3 & -1 & 2 & 5 \\ 1 & 7 & 6 & 10 \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & -2 & -3 & -4 \\ (3-3) & (-1+6) & (2+9) & (5+12) \\ (1-1) & (7+2) & (6+3) & (10+4) \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & -2 & -3 & -4 \\ 0 & 5 & 11 & 17 \\ 0 & 9 & 9 & 14 \end{bmatrix}$$

Transform the resulting matrix so that element c_{22} is 1 and all other elements in the second column are 0, as follows: a) Divide R_2 by 9; b) multiply new R_2 by –5, then add to R_2; c) multiply R_2 by 2, then add to R_1; and d) swap R_2 and R_3.

$$\begin{bmatrix} 1 & -2 & -3 & -4 \\ 0 & 5 & 11 & 17 \\ \frac{0}{9} & \frac{9}{9} & \frac{9}{9} & \frac{14}{9} \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & (-2+2) & (-3+2) & \left(-4+\frac{28}{9}\right) \\ 0 & (5-5) & (11-5) & \left(17-\frac{70}{9}\right) \\ 0 & 1 & 1 & \frac{14}{9} \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & 0 & -1 & -\frac{8}{9} \\ 0 & 0 & 6 & \frac{83}{9} \\ 0 & 1 & 1 & \frac{14}{9} \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & 0 & -1 & -\frac{8}{9} \\ 0 & 1 & 1 & \frac{14}{9} \\ 0 & 0 & 6 & \frac{83}{9} \end{bmatrix}$$

Transform the resulting matrix so that element c_{33} is 1 and all other elements in the third column are 0, as follows: a) Divide R_3 by 6; b) multiply new R_3 by -1, then add to R_2; and c) add R_3 to R_1.

$$\begin{bmatrix} 1 & 0 & -1 & -\frac{8}{9} \\ 0 & 1 & 1 & \frac{14}{9} \\ 0 & 0 & \frac{6}{6} & \frac{83}{9(6)} \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & 0 & (-1+1) & \left(-\frac{8}{9}+\frac{83}{54}\right) \\ 0 & 1 & (1-1) & \left(\frac{14}{9}-\frac{83}{54}\right) \\ 0 & 0 & 1 & \frac{83}{54} \end{bmatrix} \Rightarrow \begin{bmatrix} 1 & 0 & 0 & \frac{35}{54} \\ 0 & 1 & 0 & \frac{1}{54} \\ 0 & 0 & 1 & \frac{83}{54} \end{bmatrix}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Finally, when the identity matrix has been formed, the last column contains the values of x_1, x_2, and x_3 that satisfy the original equations.

$$x_1 = \frac{35}{54} \qquad x_2 = \frac{1}{54} \qquad x_3 = \frac{83}{54}$$

Checking the solutions:

$$-4x_1 + 8x_2 + 12x_3 = 16 \qquad 3x_1 - x_2 + 2x_3 = 5 \qquad x_1 + 7x_2 + 6x_3 = 10$$
$$16 = 16 \qquad 5 = 5 \qquad 10 = 10$$

Example 9: Use matrix operations to find the currents (I_1, I_2, I_3) in the following electrical network.

By Kirchoff's Current Law:

$$I_2 + I_3 = I_1$$
$$I_1 - I_2 - I_3 = 0$$

By Kirchoff's Voltage Law, and Ohm's Law:

$$2I_1 + 5I_3 - 40 = 0$$
$$10I_2 + 5I_3 - 30 = 0$$



By combining all the above equations, a linear system of three independent equations is formed. Solve the system for the currents I_1, I_2, and I_3.

$$I_1 - I_2 - I_3 = 0$$
$$2I_1 + 5I_3 = 40$$
$$10I_2 - 5I_3 = 30$$

Solution: If A is the matrix of coefficients of the currents, B is the matrix of currents (variables), and C be the matrix of constants from the right sid of the equations, then the problem can be witten in the following form: $AB = C$, and $B = A^{-1}C$, where A^{-1} is the inverse of matrix A.

Thus,

$$A = \begin{bmatrix} 1 & -1 & -1 \\ 2 & 0 & 5 \\ 0 & 10 & -5 \end{bmatrix} \qquad B = \begin{bmatrix} I_1 \\ I_2 \\ I_3 \end{bmatrix} \qquad C = \begin{bmatrix} 0 \\ 40 \\ 30 \end{bmatrix} \qquad \text{and} \qquad \begin{bmatrix} I_1 \\ I_2 \\ I_3 \end{bmatrix} = \begin{bmatrix} 1 & -1 & -1 \\ 2 & 0 & 5 \\ 0 & 10 & -5 \end{bmatrix}^{-1} \begin{bmatrix} 0 \\ 40 \\ 50 \end{bmatrix}$$

Using the method of Example 7, the inverse of matrix A is

$$A^{-1} = \begin{bmatrix} 1 & -1 & -1 \\ 2 & 0 & 5 \\ 0 & 10 & -5 \end{bmatrix}^{-1} = -\frac{1}{80}\begin{bmatrix} -50 & -15 & -5 \\ 10 & -5 & -7 \\ 20 & -10 & 2 \end{bmatrix} = \begin{bmatrix} \frac{5}{8} & \frac{3}{16} & \frac{1}{16} \\ -\frac{1}{8} & \frac{1}{16} & \frac{7}{80} \\ -\frac{1}{4} & \frac{1}{8} & -\frac{1}{40} \end{bmatrix}$$

and finally, matrix B can be found as follows:

$$B = A^{-1}C = \begin{bmatrix} \frac{5}{8} & \frac{3}{16} & \frac{1}{16} \\ -\frac{1}{8} & \frac{1}{16} & \frac{7}{80} \\ -\frac{1}{4} & \frac{1}{8} & -\frac{1}{40} \end{bmatrix} \begin{bmatrix} 0 \\ 40 \\ 50 \end{bmatrix} = \begin{bmatrix} 9.375 \\ 5.125 \\ 4.25 \end{bmatrix}$$

Thus, $I_1 = 9.375$ amps, $I_2 = 5.125$ amps, and $I_3 = 4.25$ amps

Copyright 2004, Industrial Press, Inc., New York, NY

ENGINEERING ECONOMICS

Engineers, managers, purchasing agents, and others are often required to plan and evaluate project alternatives, and make economic decisions that may greatly affect the success or failure of a project.

The goals of a project, such as reducing manufacturing cost or increasing production, selection of machine tool alternatives, or reduction of tooling, labor and other costs, determine which of the available alternatives may bring the most attractive economic return.

Various cost analysis techniques that may be used to obtain the desired outcome are discussed in the material that follows.

Interest

Interest is money paid for the use of money lent for a certain time. *Simple* interest is the interest paid on the principal (money lent) only. When simple interest that is due is not paid, and its amount is added to the interest-bearing principal, the interest calculated on this new principal is called *compound* interest. The compounding of the interest into the principal may take place yearly or more often, according to circumstances.

Interest Formulas.— The symbols used in the formulas to calculate various types of interest are:

P = principal or amount of money lent

I = nominal annual interest rate stated as a percentage, i.e., 10 per cent per annum

I_e = effective annual interest rate when interest is compounded more often than once a year (see *Nominal vs. Effective Interest Rates*)

i = nominal annual interest rate per cent expressed as a decimal, i.e., if I = 12 per cent, then $i = 12/100 = 0.12$

n = number of annual interest periods

m = number of interest compounding periods in one year

F = a sum of money at the end of n interest periods from the present date that is equivalent to P with added interest i

A = the payment at the end of each period in a uniform series of payments continuing for n periods, the entire series equivalent to P at interest rate i

Note: The exact amount of interest for one day is 1/365 of the interest for one year. Banks, however, customarily take the year as composed of 12 months of 30 days, making a total of 360 days to a year. This method is also used for home-mortgage-type payments, so that the interest rate per month is 30/360 = 1/12 of the annual interest rate. For example, if I is a 12 per cent per annum nominal interest rate, then for a 30-day period, the interest rate is $(12 \times 1/12) = 1.0$ per cent per month. The decimal rate per month is then $1.0/100 = 0.01$.

Simple Interest.— The formulas for simple interest are:

$$\text{Interest for } n \text{ years} = P \times i \times n$$

$$\text{Total amount after } n \text{ years, } S = P + P \times i \times n$$

Example: For $250 that has been lent for three years at 6 per cent simple interest: $P = 250$; $I = 6$; $i = I/100 = 0.06$; $n = 3$.

$$F = 250 + (250 \times 0.06 \times 3) = 250 + 45 = \$295$$

Compound Interest.— The following formulas apply when compound interest is to be computed and assuming that the interest is compounded annually.

Copyright 2004, Industrial Press, Inc., New York, NY

$$F = P(1 + i)^n$$

$$P = F/(1 + i)^n$$

$$i = (F/P)^{1/n} - 1$$

$$n = (\log F - \log P)/\log(1 + i)$$

Example: At 10 per cent interest compounded annually for 10 years, a principal amount P of $1000 becomes a sum F of

$$F = 1000(1 + 10/100)^{10} = \$2{,}593.74$$

If a sum $F = \$2593.74$ is to be accumulated, beginning with a principal $P = \$1{,}000$ over a period $n = 10$ years, the interest rate i to accomplish this would have to be $i = (2593.74/1000)^{1/10} - 1 = 0.09999$, which rounds to 0.1, or 10 per cent.

For a principal $P = \$500$ to become $F = \$1{,}000$ at 6 per cent interest compounded annually, the number of years n would have to be

$$n = (\log 1000 - \log 500)/\log(1 + 0.06)$$
$$= (3 - 2.69897)/0.025306 = 11.9 \text{ years}$$

To triple the principal $P = \$500$ to become $F = \$1{,}500$, the number of years would have to be

$$n = (\log 1500 - \log 500)/\log(1 + 0.06)$$
$$= (3.17609 - 2.69897)/0.025306 = 18.85 \text{ years}$$

Interest Compounded More Often Than Annually.— If interest is payable m times a year, it will be computed m times during each year, or nm times during n years. The rate for each compounding period will be i/m if i is the nominal annual decimal interest rate. Therefore, at the end of n years, the amount F will be: $F = P(1 + i/m)^{nm}$.

As an example, if $P = \$1{,}000$; n is 5 years, the interest payable quarterly, and the annual rate is 6 per cent, then $n = 5$; $m = 4$; $i = 0.06$; $i/m = 0.06/4 = 0.015$; and $nm = 5 \times 4 = 20$, so that

$$F = 1000(1 + 0.015)^{20} = \$1{,}346.86$$

Nominal vs. Effective Interest Rates.— Deposits in savings banks, automobile loans, interest on bonds, and many other transactions of this type involve computation of interest due and payable more often than once a year. For such instances, there is a difference between the *nominal* annual interest rate stated to be the cost of borrowed money and the *effective* rate that is actually charged.

For example, a loan with interest charged at 1 per cent per month is described as having an interest rate of 12 per cent per annum. To be precise, this rate should be stated as being a *nominal* 12 per cent per annum compounded monthly; the actual or *effective* rate for monthly payments is 12.7 per cent. For quarterly compounding, the effective rate would be 12.6 per cent:

$$I_e = (1 + I/m)^m - 1$$

In this formula, I_e is the effective annual rate, I is the nominal annual rate, and m is the number of times per year the money is compounded.

Example: For a nominal per annum rate of 12 per cent, with monthly compounding, the effective per annum rate is

$$I_e = (1 + 0.12/12)^{12} - 1 = 0.1268 = 12.7 \text{ per cent effective per annum rate}$$

Example: Same as before but with quarterly compounding:

$$I_e = (1 + 0.12/4)^4 - 1 = 0.1255 = 12.6 \text{ per cent effective per annum rate}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Finding Unknown Interest Rates.— If a single payment of P dollars is to produce a sum of F dollars after n annual compounding periods, the per annum decimal interest rate is found using:

$$i = \sqrt[n]{\frac{F}{P}} - 1$$

Cash Flow and Equivalence

The sum of money receipts or disbursement in a project's financial report are called cash flows. Due to the time value of money, the timing of cash flows over the project life plays a vital role in project success. Engineering economy problems involve the following four patterns of cash flow, both separately and in combination.Two cash flow patterns are said to be equivalent if they have the same value at a particular time.

Present Value and Discount.— The present value or present worth P of a given amount F is the amount P that, when placed at interest i for a given time n, will produce the given amount F.

$$\text{At simple interest, } P = F/(1 + ni)$$

$$\text{At compound interest, } P = F/(1 + i)^n$$

The *true discount* D is the difference between F and P: $D = F - P$.

These formulas are for an annual interest rate. If interest is payable other than annually, modify the formulas as indicated in the formulas in the section *Interest Compounded More Often Than Annually* on page 126.

Example: Find the present value and discount of $500 due in six months at 6 per cent simple interest. Here, $F = 500$; $n = 6/12 = 0.5$ year; $i = 0.06$. Then, $P = 500/(1 + 0.5 \times 0.06) = \$485.44$.

Example: Find the sum that, placed at 5 per cent compound interest, will in three years produce $5,000. Here, $F = 5000$; $i = 0.05$; $n = 3$. Then,

$$P = 5000/(1 + 0.05)^3 = \$4,319.19$$

Annuities.— An annuity is a fixed sum paid at regular intervals. In the formulas that follow, yearly payments are assumed. It is customary to calculate annuities on the basis of compound interest. If an annuity A is to be paid out for n consecutive years, the interest rate being i, then the present value P of the annuity is

$$P = A\frac{(1 + i)^n - 1}{i(1 + i)^n}$$

If at the *beginning* of each year a sum A is set aside at an interest rate i, the total value F of the sum set aside, with interest, at the end of n years, will be

$$F = A\frac{(1 + i)[(1 + i)^n - 1]}{i}$$

If at the *end* of each year a sum A is set aside at an interest rate i, then the total value F of the principal, with interest, at the end of n years will be

$$F = A\frac{(1 + i)^n - 1}{i}$$

If a principal P is increased or decreased by a sum A at the end of each year, then the value of the principal after n years will be

$$F = P(1 + i)^n \pm A\frac{(1 + i)^n - 1}{i}$$

Copyright 2004, Industrial Press, Inc., New York, NY

If the sum A by which the principal P is decreased each year is greater than the total yearly interest on the principal, then the principal, with the accumulated interest, will be entirely used up in n years:

$$n = \frac{\log A - \log(A - iP)}{\log(1 + i)}$$

Example: If an annuity of $200 is to be paid for 10 years, what is the present amount of money that needs to be deposited if the interest is 5 per cent. Here, $A = 200$; $i = 0.05$; $n = 10$:

$$P = 200\frac{(1 + 0.05)^{10} - 1}{0.05(1 + 0.05)^{10}} = \$1{,}544.35$$

The annuity a principal P drawing interest at the rate i will give for a period of n years is

$$A = P\frac{i(1 + i)^n}{(1 + i)^n - 1}$$

Example: A sum of $10,000 is placed at 4 per cent. What is the amount of the annuity payable for 20 years out of this sum: Here, $P = 10000$; $i = 0.04$; $n = 20$:

$$A = 10{,}000\frac{0.04(1 + 0.04)^{20}}{(1 + 0.04)^{20} - 1} = \$735.82$$

Sinking Funds.— Amortization is "the extinction of debt, usually by means of a sinking fund." The sinking fund is created by a fixed investment A placed each year at compound interest for a term of years n, and is therefore an annuity of sufficient size to produce at the end of the term of years the amount F necessary for the repayment of the principal of the debt, or to provide a definite sum for other purposes. Then,

$$F = A\frac{(1 + i)^n - 1}{i} \quad \text{and} \quad A = F\frac{i}{(1 + i)^n - 1}$$

Example: If $2,000 is invested annually for 10 years at 4 per cent compound interest, as a sinking fund, what would be the total amount of the fund at the expiration of the term? Here, $A = 2000$; $n = 10$; $i = 0.04$:

$$F = 2000\frac{(1 + 0.04)^{10} - 1}{0.04} = \$24{,}012.21$$

Cash Flow Diagrams.— The following conventions are used to standardize cash flow diagrams. The horizontal (time) axis is marked off in equal increments, one per period, up to the duration of the project. Receipts are represented by arrows directed upwards and disbursements are represented by arrows directed downwards. The arrow length is proportional to the magnitude of cash flow. In the following, i = interest rate, and n = number of payments or periods.

Table 1. Cash Flow Patterns

P-pattern *P* = present value	A single amount *P* occurring at the beginning of *n* years. *P* represents "*Present*" amount.	
F-pattern *F* = future value	A single amount *F* occurring at the end of *n* years. *F* represents "*Future*" amount.	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. *(Continued)* Cash Flow Patterns

A-pattern *A* = annual value	Equal amounts *A* occurring at the end of each of *n* years. *A* represents "*annual*" amount.	
G-pattern *G* = uniform gradient of expense	*G* is increasing by an equal amount over the period of life *n*. *G* represents "*Gradient*" amount.	

Table 2. Standard Cash Flow Factors

Symbol	To Find	Formula	Given	Symbol
	*F*	$(P/F, i\%, n)$ $F = P(1+i)^n$	*P*	
	*P*	$(F/P, i\%, n)$ $P = \frac{F}{(1+i)^n}$	*F*	
	*A*	$(A/P, i\%, n)$ $A = P\frac{i(1+i)^n}{(1+i)^n - 1}$	*P*	
	*P*	$(P/A, i\%, n)$ $P = A\frac{(1+i)^n - 1}{i(1+i)^n}$	*A*	
	*A*	$(A/F, i\%, n)$ $A = F\frac{i}{(1+i)^n - 1}$	*F*	
	*F*	$(F/A, i\%, n)$ $F = A\left(\frac{(1+i)^n - 1}{i}\right)$	*A*	
	*P*	$(P/G, i\%, n)$ $P = G\frac{1}{i}\left[\frac{(1+i)^n - 1}{i(1+i)^n} - \frac{n}{(1+i)^n}\right]$	*G*	
	*F*	$(F/G, i\%, n)$ $F = G\frac{1}{i}\left[\frac{(1+i)^n - 1}{i} - n\right]$	*G*	
	*A*	$(A/G, i\%, n)$ $A = G\left[\frac{1}{i} - \frac{n}{(1+i)^n - 1}\right]$	*G*	

Example: A rental property pays $2000/month with a $10 per month increase starting the second year. Based on 10 year period and 8% annual interest, compute the unified average annuity, considering the gradient.

Copyright 2004, Industrial Press, Inc., New York, NY

Solution

$$\text{Average rental} = G\left[\frac{1}{i} - \frac{n}{(1+i)^n - 1}\right] + A$$

$$= 10\left[\frac{1}{(8/1200)} - \frac{120}{(1+8/1200)^{120} - 1}\right] + 2000$$

$$= 516 + 2000 = \$2516$$

Depreciation

Depreciation is the allocation of the cost of an asset over its depreciable life.A machine may decline in value because it is wearing out and no longer performing its function as well as when it is new. Depreciation is a economical technique that spreads the purchase price of an asset or other property over a number of years. Tax regulations do not allow the cost of an asset to be treated as a deductible expense in the year of purchase. Portions of the expense must be allocated to each of the years of the asset's depreciation period. The amount that is allocated each year is called the depreciation.

Straight Line Depreciation.— Straight line depreciation is a constant depreciation charge over the period of life. If P is the principal value, L is the salvage value and n is the period of life. The depreciation will be

Depreciation at xth year $$D_x = \frac{P-L}{n}$$

Book Value after x years $$BV_x = \frac{(P-L)(n-x)}{n} + L$$

After Tax Depreciation Recovery $$ATDR = TR\left(\frac{P-L}{n}\right)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right)$$

Sum of the Years Digits.— Another method for allocating the cost of an asset minus salvage value over its useful life is called sum of the years digits depreciation. This method results in larger than straight line depreciation charges during the early years of an asset and smaller charges near the end period.

Depreciation at xth year $$D_x = \frac{2(P-L)(n-x+1)}{n(n+1)}$$

Book Value after x years $$BV_x = P - (P-L)(2n-x+1)\frac{x}{n(n+1)}$$

Double Declining Balance Method.— A constant depreciation is applied to the book value of the property.

Depreciation at xth year $$D_x = 2\left(\frac{P}{n}\right)\left(\frac{n-2}{n}\right)^{(x-1)}$$

Book Value after x years $$BV_x = P\left(\frac{n-2}{n}\right)^x$$

Statutory Depreciation System.— The latest depreciation method is used in U.S. income tax purpose is called accelerated cost recovery system (ACRS) depreciation. The first step in ACRS is to determine the property class of the asset being depreciated. All personal property falls into one of six classes.

Depreciation at xth year $$D_x = P \times Factor$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Property Class and Factor

ACRS Classes of Depreciable Property			Depreciation Rate for Recovery Period (n)			
Property Class	Personal Property	Year (x)	3 Years	5 Years	7 Years	10 Years
3	Handling device for food and beverage manufacture, plastic products, fabricated metal products	1	33.33%	20.00%	14.29%	10.00%
		2	44.45%	32.00%	24.49%	18.00%
		3	14.81%	19.20%	17.49%	14.40%
5	Automobiles, trucks, computer, aircraft, petroleum drilling equipment, research and experimentation equip.	4	7.41%	11.52%	12.49%	11.52%
		5		11.52%	8.93%	9.22%
7	Office furniture, fixtures, and equip.	6		5.76%	8.92%	7.37%
10	Railroad cars, manufacture of tobacco products	7			8.93%	6.55%
		8			4.46%	6.55%
15	Telephone distribution line, municipal sewers plant	9				6.56%
		10				6.55%
20	Municipal sewers	11				3.28%

Evaluating Alternatives

Two or more mutually exclusive investments compete for limited funds. There are a number of ways for selecting the superior alternative from a group of proposals. This section concerns strategies for selecting alternatives in such a way that net value is maximized.

Net Present Value.— One of the easiest way to compare mutually exclusive alternatives is to resolve their consequences to the present time. It is most frequently used to determine the present value of future money receipts and disbursements. There are three economic criteria for present worth analysis described in the table that follows. If investment cost is same, consider only the output money. If the output result is known, then minimize the investment cost. If neither input nor output is fixed, then maximize the output minus the input. This method is widely applied when alternatives have the same period of time.

With uniform annual expense before tax

$$NPV = -P + (AR - AE)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + \frac{L}{(1+i)^n}$$

With uniform gradient on annual expense before tax

$$NPV = -P + (AR - AE - (A/G, i, n)G)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + \frac{L}{(1+i)^n}$$

With uniform annual expense after tax

$$NPV = -P + (AR - AE)(1 - TR)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + \frac{L}{(1+i)^n}$$

With uniform gradient on annual expense after tax

$$NPV = -P + (AR - AE - (A/G, i, n)G)(1 - TR)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + \frac{L}{(1+i)^n}$$

The symbol used in this table are defined as follows:

P = Present value NPV = Net present value AR = Annual revenue
AE = Annual expense G = Uniform gradient of expense TR = Tax rate as percentage
i = Interest rate n = Number of payments or periods

The previous formulas do not consider depreciation. To include depreciation, the after tax depreciation recovery (ATDR) must be added to get the net present value.

Example 10 : A pharmaceutical company produces a product from different chemical compositions. Two mixing processes, batch and continuous, are available.

Copyright 2004, Industrial Press, Inc., New York, NY

Process	Continuous	Batch
Initial cost	$75000	$35000
Lifetime (years)	10	10
Maintenance (per year)	$5000	$8000
Capacity (units/year)	25000	20000

The company uses straight line depreciation, pays 40% of its net income as income tax, and has an after tax minimum attractive rate of return of 15%. The company can sell the product at $1.00 per unit. Which manufacturing process should the company invest in?

Solution: Because the lifetimes are equal, we can make a comparison using the present worth method by applying the formulas for *NPV* and also for *ATDR*.

$$NPV_{Continuous} = -P + (AR - AE)(1 - TR)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + TR\left(\frac{P-L}{n}\right)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right)$$

$$= -75000 + (25000 \times 1 - 5000)(1 - 0.40)\left(\frac{\left(1+\frac{15}{100}\right)^{10} - 1}{\left(\frac{15}{100}\right)\left(1+\frac{15}{100}\right)^{10}}\right) + 0.40\left(\frac{75000}{10}\right)\left(\frac{\left(1+\frac{15}{100}\right)^{10} - 1}{\left(\frac{15}{100}\right)\left(1+\frac{15}{100}\right)^{10}}\right)$$

$$= -14775 + 15056 = 281$$

$$NPV_{Batch} = -P + (AR - AE)(1 - TR)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right) + TR\left(\frac{P-L}{n}\right)\left(\frac{(1+i)^n - 1}{i(1+i)^n}\right)$$

$$= -35000 + ([20000 \times 1] - 8000)(1 - 0.40)\left(\frac{\left(1+\frac{15}{100}\right)^{10} - 1}{\left(\frac{15}{100}\right)\left(1+\frac{15}{100}\right)^{10}}\right) + 0.40\left(\frac{35000}{10}\right)\left(\frac{\left(1+\frac{15}{100}\right)^{10} - 1}{\left(\frac{15}{100}\right)\left(1+\frac{15}{100}\right)^{10}}\right)$$

$$= 1135 + 7026 = 8161$$

Based on above calculations, the batch production process is selected because it gives a greater net present value (*NPV*) than the continuous process.

Capitalized Cost.— In governmental analyses, there are some circumstances where a service is required for an infinite period of time such as with roads, dams, pipelines, etc. Present worth of a project with an infinite life is known as capitalized cost. Capitalized cost is the amount of money at $n = 0$ needed to perpetually support the projection the earned interest only. Capitalized cost is the present sum of money that would need to be set aside now, at some interest rate, to yield the funds required to provide the service.

$$CC = P + A(P/A, i\%, n) - L(P/F, i\%, n) + G(P/G, i\%, n)$$

Without Periodical Replacement $$CC = P + \frac{A}{i}$$

With 100% Periodical Replacement $$CC = P + \frac{P - L}{(1+i)^n - 1} + \frac{A}{i}$$

With Periodical Renovation Cost $$CC = P + \frac{RC}{(1+i)^n - 1} + \frac{A}{i}$$

where CC = capitalized cost; P = initial cost; L = salvage value; A = annual cost; RC = renovation cost; i = interest rate; and, n = effective period of time.

Copyright 2004, Industrial Press, Inc., New York, NY

Equivalent Uniform Annual Cost.— This method is applied when the alternatives have unequal periods of life. To avoid unequal periods of time, the present value and future value is converted to an annual value.The alternatives must be mutually exclusive and repeatedly renewed up to the duration of the longest lived alternative.

$$A = P(A/P, i\%, n) - L(A/F, i\%, n) + G(A/G, i\%, n) + AE$$

With Sinking Fund Depreciation
$$A = (P - L)\frac{i(1+i)^n}{(1+i)^n - 1} + Li + AE$$

With Sinking Fund Depreciation and Uniform Gradient G
$$A = (P - L)\frac{i(1+i)^n}{(1+i)^n - 1} + Li + AE + G\left(\frac{1}{i} - \frac{n}{(1+i)^n - 1}\right)$$

Straight Line Depreciation
$$A = \frac{P - L}{n} + Li + AE + \frac{(P - L)(n+1)i}{2n}$$

Example 11: An investment of $15,000 is being considered to reduce labor and labor-associated costs in a materials handling operation from $8,200 a year to $3,300. This operation is expected to be used for 10 years before being changed or discontinued entirely. In addition to the initial investment of $15,000 and the annual cost of $3,300 for labor, there are additional annual costs for power, maintenance, insurance, and property taxes of $1,800 associated with the revised operation. Based on comparisons of annual costs, should the $15,000 investment be made or the present operation continued?

The present annual cost of the operation is $8,200 for labor and labor-associated costs. The proposed operation has an annual cost of $3,300 for labor and labor extras plus $1,800 for additional power, maintenance, insurance, and taxes, plus the annual cost of recovering the initial investment of $15,000 at some interest rate (minimum acceptable rate of return).

Assuming that 10 per cent would be an acceptable rate of return on this investment over a period of 10 years, the annual amount to be recovered on the initial investment would be $15,000 multiplied by the capital recovery factor.

Putting this value into $(A/P, i\%, n)$ yields:

$$A = \frac{i(1+i)^n}{(1+i)^n - 1}P + AE = \frac{(10/100)(1+10/100)^{10}}{(1+10/100)^{10} - 1}15000 + 5100 = 7541.18$$

Adding this amount to the $5,100 annual cost associated with the investment ($3,300 + $1,800 = $5,100) gives a total annual cost of $7,542, which is less than the present annual cost of $8,200. Thus, the investment is justified unless there are other considerations such as the effects of income taxes, salvage values, expected life, uncertainty about the required rate of return, changes in the cost of borrowed funds, and others.

A tabulation of annual costs of alternative plans A, B, C, etc., is a good way to compare costs item by item. For this example:

	Item	Plan A	Plan B
1	Labor and labor extras	$8,200.00	$3,300.00
2	Annual cost of $15,000 investment		2,442.00
3	Power		400.00
4	Maintenance		1,100.00
5	Property taxes and insurance		300.00
	Total annual cost	$8,200.00	$7,542.00

Copyright 2004, Industrial Press, Inc., New York, NY

Example 12, (Annual Cost Considering Salvage Value): If in Example 11 the salvage value of the equipment installed was $5,000 at the end of 10 years, what effect does this have on the annual cost of the proposed investment of $15,000?

The only item in the annual cost of Example 11 that will be affected is the capital recovery amount of $2,442. The following formula gives the amount of annual capital recovery when salvage value is considered:

$$A = (P-L)\frac{i(1+i)^n}{(1+i)^n-1} + Li + AE$$

$$= (15000-5000)\frac{\left(\frac{10}{100}\right)\left(1+\frac{10}{100}\right)^{10}}{\left(1+\frac{10}{100}\right)^{10}-1} + 5000\left(\frac{10}{100}\right) + 5100 = 7227.45$$

Adding this amount to the $5,100 annual cost determined previously gives a total annual cost of $7,227, which is $315 less than the previous annual cost of $7,542 for the proposed investment.

Rate of Return.— The estimated interest rate produced by an investment. Rate of return is the interest rate at which the benefits are equivalent to the costs. It is defined as the interest rate paid on the unpaid balance of a loan such that the payment schedule makes the unpaid loan balance equal to zero when the final payment is made. It may be computed by finding the interest rate in such a way that the estimated expenditures are equal to the capital gain. *Net Present Worth* = 0, or *PW of benefits – PW of costs* = 0

$$\frac{((1+ror)^n-1)}{ror(1+ror)^n}(AR-AE) + \frac{L}{(1+ror)^n} = P$$

The rate of return can only be calculated by trial and error solution. To find out the present worth, select a reasonable interest rate, calculate the present worth. Choose another rate, calculate the present worth. Interpolate or extrapolate the value of *ROR* to find the zero value of present worth.

Benefit-Cost Ratio.— It is the ratio of present worth of benefit and present worth of cost. This method is applied to municipal project evaluations where benefits (B) and costs (C) accrue to different segments of the community. The project is considered acceptable if the ratio equals or exceeds 1. For fixed input maximize the $B/C \geq 1$ and for fixed output maximize the $B/C \geq 1$ and if neither input nor output is fixed, to compute the incremental benefit cost ratio ($\Delta B/\Delta C$), choose $\Delta B/\Delta C \geq 1$.

Example 13: To build a bridge over a river costs $1,200,000, benefits of $2,000,000, and disbenefits of $500,000. (a) What is the benefit cost ratio? (b) What is the excess of benefits over costs?

Solution: The benefit cost ratio is $B/C = \frac{B-D}{D} = \frac{2{,}000{,}000 - 500{,}000}{500{,}000} = 3$

The excess of benefits over cost equal 2,000,000 – 1,200,000 – 500,000 = 300,000.

Payback Period.— This is the period of time required for the profit or other benefits of an investment to equal the cost of investment. The criterion in all situations is to minimize the payback period.

Break-Even Analysis.— Break-even analysis is a method of comparing two or more alternatives to determine which works best. Frequently, cost is the basis of the comparison, with the least expensive alternative being the most desirable. Break-even analysis can be applied in situations such as: to determine if it is more efficient and cost effective to use HSS, carbide, or ceramic tooling; to compare coated versus uncoated carbide tooling; to

Copyright 2004, Industrial Press, Inc., New York, NY

decide which of several machines should be used to produce a part; or to decide whether to buy a new machine for a particular job or to continue to use an older machine. The techniques used to solve any of these problems are the same; however, the details will be different, depending on the type of comparison being made. The remainder of this section deals with break-even analysis based on comparing the costs of manufacturing a product using different machines.

Choosing a Manufacturing Method: The object of this analysis is to decide which of several machines can produce parts at the lowest cost. In order to compare the cost of producing a part, all the costs involved in making that part must be considered. The cost of manufacturing any number of parts can be expressed as the sum: $C_T = C_F + n \times C_V$, where C_T is the total cost of manufacturing one part, C_F is the sum of the fixed costs of making the parts, n is the number of parts made, and C_V is the total variable costs per piece made.

Fixed costs are manufacturing costs that have to be paid whatever the number of parts is produced and usually before any parts can be produced. They include the cost of drafting and CNC part programs, the cost of special tools and equipment required to make the part, and the cost of setting up the machine for the job. Fixed costs are generally one-time charges that occur at the beginning of a job or are recurrent charges that do not depend on the number of pieces made, such as those that might occur each time a job is run again.

Variable costs depend on the number of parts produced and are expressed as the cost per part made. The variable costs include the cost of materials, the cost of machine time, the cost of the labor directly involved in making the part, and the portion of the overhead that is attributable to production of the part. Variable costs can be expressed as: C_V = material cost + machine cost + labor cost + overhead cost. When comparing alternatives, if the same cost is incurred by each alternative, then that cost can be eliminated from the analysis without affecting the result. For example, the cost of material is frequently omitted from a manufacturing analysis if each machine is going to make parts from the same stock and if there is not going to be a significant difference in the amount of scrap produced by each method. The time to produce one part is needed to determine the machine, labor, and overhead costs. The total time expressed in hours per part is $t_T = t_f + t_s$, where t_f equals the floor-to-floor production time for one part and t_s the setup time per part. The setup time, t_s, is the time spent setting up the machine and periodically reconditioning tooling, divided by the number of parts made per setup.

Material cost equals the cost of the materials divided by the number of parts made.

Machine cost is the portion of a machine's total cost that is charged toward the production of each part. It is found by multiplying the machine rate (cost of the machine per hour) by the machine time per part, t_f. The machine hourly rate is calculated by dividing the lifetime costs (including purchase price, insurance, maintenance, etc.) by the estimated lifetime hours of operation of the machine. The total operating hours may be difficult to determine but a reasonable number can be based on experience and dealer information.

Labor costs are the wages paid to people who are directly involved in the manufacture of the part. The labor cost per part is the labor rate per hour multiplied by the time needed to manufacture each part, t_T. Indirect labor, which supports but is not directly involved in the manufacture of the part, is charged as overhead.

Overhead cost is the cost of producing an item that is not directly related to the cost of manufacture. Overhead includes the cost of management and other support personnel, building costs, heating and cooling, and similar expenses. Often, overhead is estimated as a percentage of the largest component cost of producing a part. For example, if direct labor is the largest expense in producing a part, the overhead can be estimated as a percentage of the direct labor costs. On the other hand, if equipment costs are higher, the overhead would be based on a percentage of the machine cost. Depending on the company, typical overhead charges range from about 150 to 800 per cent of the highest variable cost.

Copyright 2004, Industrial Press, Inc., New York, NY

Most of the time, the decision to use one machine or another for making parts depends on how many pieces are needed. For example, given three machines *A*, *B*, and *C*, if only a few parts need to be produced, then, in terms of cost, machine *A* might be the best; if hundreds of parts are needed, then machine *B* might be best; and, if thousands of components are to be manufactured, then machine *C* may result in the lowest cost per part. Break-even analysis reveals how many components need to be produced before a particular machine becomes more cost effective than another.

To use break-even analysis, the cost of operating each machine needs to be established. The costs are plotted on a graph as a function of the number of components to be manufactured to learn which machine can make the required parts for the least cost. The following graph is a plot of the fixed and variable costs of producing a quantity of parts on two different machines, *Machine 1* and *Machine 2*. Fixed costs for each machine are plotted on the vertical *cost* axis. Variable costs for each machine are plotted as a line that intersects the cost axis at the fixed cost for each respective machine. The variable cost line is constructed with a slope that is equal to the cost per part, that is, for each part made, the line rises by an amount equal to the cost per part. If the calculations necessary to produce the graph are done carefully, the total cost of producing any quantity of parts can be found from the data plotted on the graph.

As an example, the graph shown in Fig. 7is a comparison of the cost of manufacturing a quantity of a small part on a manually operated milling machine (*Machine 1*) and on a CNC machining center (*Machine 2*). The fixed costs (fixed costs = lead time × lead time rate + setup time × setup rate) for the manual machine are $190 and the fixed costs for the CNC machine are higher at $600. The fixed cost for each machine is the starting point of the line representing the cost of manufacturing a quantity of parts with that machine. The variable costs plotted are: $18 per piece for the manual machine and $5 per piece for the CNC mill.



Fig. 7. Quantity of Parts

The variable costs are calculated using the machine, labor, and overhead costs. The cost of materials is not included because it is assumed that materials cost will be the same for parts made on either machine and there will be no appreciable difference in the amount of scrap generated. The original cost of *Machine 1* (the manual milling machine) is $19,000 with an estimated operating life of 16,000 hours, so the hourly operating cost is 19,000/16,000 = $1.20 per hour. The labor rate is $17 per hour and the overhead is estimated as 1.6 times the labor rate, or $17 × 1.6 = $27.20 per hour. The time, t_f, needed to complete each part on *Machine 1* is estimated as 24 minutes (0.4 hour). Therefore, by using *Machine 1*, the variable cost per part excluding material is (1.20 + 17.00 + 27.20) $/h × 0.4 h/part = $18 per part. For *Machine 2* (the CNC machining center), the machine cost is calculated at $3 per hour, which is based on a $60,000 initial cost (including installation, maintenance,

Copyright 2004, Industrial Press, Inc., New York, NY

insurance, etc.) and 20,000 hours of estimated lifetime. The cost of labor is $15 per hour for *Machine 2* and the overhead is again calculated at 1.6 times the labor rate, or $24 per hour. Each part is estimated to take 7.2 minutes (0.12 h) to make, so the variable cost per part made on *Machine 2* is (3 + 15 + 24) $/h × 0.12 h/part = $5 per part.

The lines representing the variable cost of operating each machine intersect at only one point on the graph. The intersection point corresponds to a quantity of parts that can be made by either the CNC or manual machine for the same cost, which is the break-even point. In the figure, the break-even point is 31.5 parts and the cost of those parts is $757, or about $24 apiece, excluding materials. The graph shows that if fewer than 32 parts need to be made, the total cost will be lowest if the manual machine is used because the line representing *Machine 1* is lower (representing lower cost) than the line representing *Machine 2*. On the other hand, if more than 31 parts are going to be made, the CNC machine will produce them for a lower cost. It is easy to see that the per piece cost of manufacturing is lower on the CNC machine because the line for *Machine 2* rises at a slower rate than the line for *Machine 1*. For producing only a few parts, the manual machine will make them less expensively than the CNC because the fixed costs are lower, but once the CNC part program has been written, the CNC can also run small batches efficiently because very little setup work is required.

The quantity of parts corresponding to the break-even point is known as the break-even quantity Q_b. The break-even quantity can be found without the use of the graph by using the following break-even equation: $Q_b = (C_{F1} - C_{F2})/(C_{V2} - C_{V1})$. In this equation, the C_{F1} and C_{F2} are the fixed costs for *Machine 1* and *Machine 2*, respectively: C_{V1} and C_{V2} are the variable costs for *Machine 1* and *Machine 2*, respectively.

Break-even analysis techniques are also useful for comparing performance of more than two machines. Plot the manufacturing costs for each machine on a graph as before and then compare the costs of the machines in pairs using the techniques described. For example, if an automatic machine such as a rotary transfer machine is included as *Machine 3* in the preceding analysis, then three lines representing the costs of operating each machine would be plotted on the graph. The equation to find the break-even quantities is applied three times in succession, for *Machines 1* and *2*, for *Machines 1* and *3*, and again for *Machines 2* and *3*. The result of this analysis will show the region (range of quantities) within which each machine is most profitable.

Overhead Expenses.— *Machine-Hour Distribution:* The machine-hour rate method consists of distributing all the manufacturing expenses of an establishment by a charge to each job of the overhead cost of operating the machines and other facilities used on that job. This overhead charge is not an average for the whole plant or department, but is, as nearly as possible, the actual overhead cost of maintaining and operating each of the machines, group of machines, benches, etc., which are found in the plant. By the proper use of this method it is possible to show the difference between the expense cost of a boring mill and a lathe, a gear-cutter and a splining machine, etc.

Man-Hour Distribution: The man-hour method of distributing overhead has for its base the number of hours spent on a job instead of the amount of wages paid. The assumption is made that the overhead expenses have a fixed ratio to the number of hours of time spent on a job. Certain items of expense bear a direct relation to the number of hours worked, and include the expenses of the payroll, compensation, insurance, and supervision.

Man-Rate Distribution: The man-rate method of distributing overhead costs is the one in most general use because of its simplicity. To use this method, find the ratio of total expenses to total labor for a given business, and to apply this ratio to the labor cost of each job. For a factory making one kind of product, this method of distributing overhead is quite satisfactory, but where the product itself is varied and the tools used are different for each of the products, this method is incorrect and misleading as to final results.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MECHANICS AND STRENGTH OF MATERIALS

MECHANICS

141 Terms and Definitions
142 Unit Systems
142 Gravity
142 Metric system (SI)
145 Force Systems
145 Scalar and Vector Quantities
145 Graphical Resolution of Forces
147 Couples and Forces
148 Resolution of Force Systems
149 Subtraction and Addition of Force
153 Forces in Two or More Planes
154 Parallel Forces
155 Nonparallel Forces
157 Friction
157 Laws of Friction
158 Coefficients of Friction
158 Static Friction Coefficients
159 Rolling Friction
159 Mechanisms
159 Levers
161 Inclined Plane, Wedge
162 Wheels and Pulleys
163 Screw
163 Geneva Wheel
164 Toggle Joint
165 Pendulums
166 Harmonic

VELOCITY, ACCELERATION, WORK, AND ENERGY

167 Velocity and Acceleration
167 Newton's Laws of Motion
167 Constant Velocity
167 Constant Acceleration
168 Angular Velocity
169 Linear Velocity of Rotating Body
169 Rotary Motion with Acceleration
171 Force, Work, Energy, Momentum
171 Acceleration by Forces
172 Torque and Angular Acceleration
173 Energy
174 Work Performed by Forces
174 Work and Energy
175 Force of a Blow
176 Impulse and Momentum
178 Work and Power
179 Centrifugal Force
180 Centrifugal Casting

FLYWHEELS

183 Classification
184 Energy by Velocity
184 Flywheel Design
185 Flywheels for Presses, Punches and Shears
186 Dimensions of Flywheels
187 Simplified Flywheel Calculations
188 Centrifugal Stresses in Flywheels
189 Combined Stresses in Flywheels
189 Thickness of Flywheel Rims
190 Safety Factors
190 Safe Rim Speeds
191 Safe Rotation Speeds
192 Bursting Speeds
193 Stresses in Rotating Disks
193 Steam Engine Flywheels
194 Spokes or Arms of Flywheels
195 Critical Speeds
196 Critical Speed Formulas
197 Balancing Rotating Parts
197 Static and Dynamic Balancing
197 Balancing Calculations
198 Masses in Same Plane
200 Masses in Two or More Planes
201 Balancing Lathe Fixtures

STRENGTH OF MATERIALS

203 Properties of Materials
204 Yield Point, Elastic Modulus and Poission's Ratio
205 Compressive, Shear Properties
205 Creep
207 Fatigue Failure
208 Stress
208 Factors of Safety
208 Working Stress
209 Stress Concentration Factors
213 Simple Stresses
214 Deflections
215 Combined Stresses
215 Tables of Combined Stresses
219 Three-dimensional Stress
221 Sample Calculations
223 Stresses in a Loaded Ring
224 Strength of Taper Pins

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MECHANICS AND STRENGTH OF MATERIALS

PROPERTIES OF BODIES

225 Center of Gravity
232 Radius of Gyration
235 Center and Radius of Oscillation
235 Center of Percussion
236 Moment of Inertia
237 Calculating For Built-up Sections
238 Area Moments of Inertia, Section Moduli and Radius of Gyration
248 Polar Area Moment of Inertia and Section Modulus
248 Mass Moment of Inertia
250 Polar Mass Moments of Inertia
253 Tables for Rectangles and Shafts

BEAMS

260 Beam Calculations
261 Stress and Deflection Beam Table
272 Rectangular Solid Beams
273 Round Solid Beams
277 Deflection as Limiting Factor
278 Curved Beams
281 Size of Rail to Carry Load
281 American Railway Engineering Association Formulas
282 Stresses Produced by Shocks
282 Beam Stresses Due to Shock
283 Stresses in Helical Springs
284 Fatigue Stresses

COLUMNS

285 Strength of Columns or Struts
285 Rankine or Gordon Formula
285 Straight-line Formula
285 Formulas of American Railway Engineering Association
286 Euler Formula
286 Eccentrically Loaded Columns
289 AISC Formulas

PLATES, SHELLS, AND CYLINDERS

292 Square Flat Plates
294 Circular Flat Plates
294 Cylinders, Internal Pressure
295 Spherical Shells, Internal Pressure
297 Cylinders, External Pressure

SHAFTS

299 Shaft Calculations
299 Torsional Strength of Shafting
301 Torsional Deflections
302 Linear Deflections
303 Design of Transmission Shafting
305 Effect of Keyways
305 Brittle Materials
306 Critical Speeds
306 Shaft Couplings
307 Hollow and Solid Shafts

SPRINGS

308 Introduction to Spring Design
308 Notation
309 Spring Materials
309 High-Carbon Spring Steels
310 Alloy Spring Steels
310 Stainless Spring Steels
311 Copper-Base Spring Alloys
312 Nickel-Base Spring Alloys
313 Spring Stresses
313 Working Stresses
318 Endurance Limit
319 Working Stresses at Elevated Temperatures
320 Spring Design Data
320 Spring Characteristics
320 Compression Spring Design
321 Formulas for Compression Spring
324 Spring Characteristics
329 Extension Springs
331 Bending Stress
331 Extension Spring Design
333 Tolerances for Compression and Extension Springs
335 Torsion Spring Design
342 Torsion Spring Characteristics
347 Torsion Spring Tolerances
348 Miscellaneous Springs
348 Flat Springs Formula
349 Moduli of Elasticity
349 Heat Treatment of Springs
352 Spring Failure
352 Causes of Spring Failure
353 Music Wire

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MECHANICS AND STRENGTH OF MATERIALS

DISC SPRINGS

354 Performance of Disc Springs
354 Introduction
354 Nomenclature
354 Group Classifications
355 Contact Surfaces
355 Materials
356 Stacking of Disc Springs
358 Disc Spring Forces and Stresses
358 Springs Without Contact Surfaces
361 Springs Without Contact Surfaces
361 Functional Stresses
362 Fatigue Life
365 Recommended Dimensional Ratios
365 Example Applications

WIRE ROPE, CHAIN, ROPE, AND HOOKS

369 Strength and Properties of Wire Rope
369 Wire Rope Construction
370 Properties of Wire Rope
371 Classes of Wire Rope
372 Weights and Strengths
376 Sizes and Strengths
377 Factors of Safety
378 Installing Wire Rope
379 Drum and Reel Capacities
380 Pressures for Drums and Sheaves
380 Sheave and Drum Groove Dimensions
381 Cutting and Seizing
381 Maintenance
381 Lubrication of Wire Rope

WIRE ROPE, CHAIN, ROPE, AND HOOKS

(Continued)

382 Wire Rope Slings and Fittings
382 Slings
382 Wire Rope Fittings
382 Applying Clips and Attaching Sockets
384 Capacities of Wire Rope and Slings
386 Crane Chain and Hooks
386 Material for Crane Chains
386 Strength of Chains
386 Hoisting and Crane Chains
386 Maximum Wear on a Link
387 Safe Loads for Ropes and Chains
388 Strength of Manila Rope
390 Loads Lifted by Crane Chains
391 Winding Drum Scores for Chain
391 Sprocket Wheels for Link Chains
393 Crane Hooks
393 Making an Eye-splice
394 Eye-bolts
395 Eye Nuts and Lift Eyes

Copyright 2004, Industrial Press, Inc., New York, NY

MECHANICS

Throughout this section in this Handbook, both English and metric SI data and formulas are given to cover the requirements of working in either system of measurement. Except for the passage entitled *The Use of the Metric SI System in Mechanics Calculations*, formulas and text relating exclusively to SI are given in bold face type.

Terms and Definitions

Definitions.— The science of mechanics deals with the effects of forces in causing or preventing motion. *Statics* is the branch of mechanics that deals with bodies in equilibrium, i.e., the forces acting on them cause them to remain at rest or to move with uniform velocity. *Dynamics* is the branch of mechanics that deals with bodies not in equilibrium, i.e., the forces acting on them cause them to move with non-uniform velocity. *Kinetics* is the branch of dynamics that deals with both the forces acting on bodies and the motions that they cause. *Kinematics* is the branch of dynamics that deals only with the motions of bodies without reference to the forces that cause them.

Definitions of certain terms and quantities as used in mechanics follow:

Force may be defined simply as a push or a pull; the push or pull may result from the force of contact between bodies or from a force, such as magnetism or gravitation, in which no direct contact takes place.

Matter is any substance that occupies space; gases, liquids, solids, electrons, atoms, molecules, etc., all fit this definition.

Inertia is the property of matter that causes it to resist any change in its motion or state of rest.

Mass is a measure of the inertia of a body.

Work, in mechanics, is the product of force times distance and is expressed by a combination of units of force and distance, as foot-pounds, inch-pounds, meter-kilograms, etc. **The metric SI unit of work is the joule, which is the work done when the point of application of a force of one newton is displaced through a distance of one meter in the direction of the force.**

Power, in mechanics, is the product of force times distance divided by time; it measures the performance of a given amount of work in a given time. It is the rate of doing work and as such is expressed in foot-pounds per minute, foot-pounds per second, kilogram-meters per second, etc. **The metric SI unit is the watt, which is one joule per second.**

Horsepower is the unit of power that has been adopted for engineering work. One horsepower is equal to 33,000 foot-pounds per minute or 550 foot-pounds per second. The *kilowatt*, used in electrical work, equals 1.34 horsepower; or 1 horsepower equals 0.746 kilowatt. **However, in the metric SI, the term horsepower is not used, and the basic unit of power is the watt. This unit, and the derived units milliwatt and kilowatt, for example, are the same as those used in electrical work.**

Torque or moment of a force is a measure of the tendency of the force to rotate the body upon which it acts about an axis. The magnitude of the moment due to a force acting in a plane perpendicular to some axis is obtained by multiplying the force by the perpendicular distance from the axis to the line of action of the force. (If the axis of rotation is not perpendicular to the plane of the force, then the components of the force in a plane perpendicular to the axis of rotation are used to find the resultant moment of the force by finding the moment of each component and adding these component moments algebraically.) Moment or torque is commonly expressed in pound-feet, pound-inches, kilogram-meters, etc. **The metric SI unit is the newton-meter (N · m).**

Velocity is the time-rate of change of distance and is expressed as distance divided by time, that is, feet per second, miles per hour, centimeters per second, meters per second, etc.

Copyright 2004, Industrial Press, Inc., New York, NY

Acceleration is defined as the time-rate of change of velocity and is expressed as velocity divided by time or as distance divided by time squared, that is, in feet per second, per second or feet per second squared; inches per second, per second or inches per second squared; centimeters per second, per second or centimeters per second squared; etc. **The metric SI unit is the meter per second squared.**

Unit Systems.— In mechanics calculations, both *absolute* and *gravitational* systems of units are employed. The fundamental units in absolute systems are *length*, *time*, and *mass*, and from these units, the dimension of force is derived. Two absolute systems which have been in use for many years are the cgs (centimeter-gram-second) and the MKS (meter-kilogram-second) systems. Another system, known as MKSA (meter-kilogram-second-ampere), links the MKS system of units of mechanics with electro magnetic units.

The Conference General des Poids et Mesures (CGPM), which is the body responsible for all international matters concerning the metric system, adopted in 1954 a rationalized and coherent system of units based on the four MKSA units and including the kelvin as the unit of temperature, and the candela as the unit of luminous intensity. In 1960, the CGPM formally named this system the 'Systeme International d'Unites,' for which the abbreviation is SI in all languages. In 1971, the 14th CGPM adopted a seventh base unit, the mole, which is the unit of quantity ("amount of substance"). Further details of the SI are given in the section *MEASURING UNITS* starting on page 2544, and its application in mechanics calculations, contrasted with the use of the English system, is considered on page 142.

The fundamental units in gravitational systems are *length*, *time*, and *force*, and from these units, the dimension of mass is derived. In the gravitational system most widely used in English measure countries, the units of length, time, and force are, respectively, the foot, the second, and the pound. The corresponding unit of mass, commonly called the *slug*, is equal to 1 pound second^2 per foot and is derived from the formula, $M = W \div g$ in which M = mass in slugs, W = weight in pounds, and g = acceleration due to gravity, commonly taken as 32.16 feet per second^2. A body that weighs 32.16 lbs. on the surface of the earth has, therefore, a mass of one slug.

Many engineering calculations utilize a system of units consisting of the inch, the second, and the pound. The corresponding units of mass are pounds second^2 per inch and the value of g is taken as 386 inches per second^2.

In a gravitational system that has been widely used in metric countries, the units of length, time, and force are, respectively, the meter, the second, and the kilogram. The corresponding units of mass are kilograms second^2 per meter and the value of g is taken as 9.81 meters per second^2.

Acceleration of Gravity *g* Used in Mechanics Formulas.— The acceleration of a freely falling body has been found to vary according to location on the earth's surface as well as with height, the value at the equator being 32.09 feet per second, per second while at the poles it is 32.26 ft/sec^2. In the United States it is customary to regard 32.16 as satisfactory for most practical purposes in engineering calculations.

Standard Pound Force: For use in defining the magnitude of a standard unit of force, known as the *pound force*, a fixed value of 32.1740 ft/sec^2, designated by the symbol g_0, has been adopted by international agreement. As a result of this agreement, whenever the term mass, M, appears in a mechanics formula and the substitution $M = W/g$ is made, use of the standard value $g_0 = 32.1740$ ft/sec^2 is implied although as stated previously, it is customary to use approximate values for g except where extreme accuracy is required.

The Use of the Metric SI System in Mechanics Calculations.— The SI system is a development of the traditional metric system based on decimal arithmetic; fractions are avoided. For each physical quantity, units of different sizes are formed by multiplying or dividing a single base value by powers of 10. Thus, changes can be made very simply by

Copyright 2004, Industrial Press, Inc., New York, NY

adding zeros or shifting decimal points. For example, the meter is the basic unit of length; the kilometer is a multiple (1,000 meters); and the millimeter is a sub-multiple (one-thousandth of a meter).

In the older metric system, the simplicity of a series of units linked by powers of 10 is an advantage for plain quantities such as length, but this simplicity is lost as soon as more complex units are encountered. For example, in different branches of science and engineering, energy may appear as the erg, the calorie, the kilogram-meter, the liter-atmosphere, or the horsepower-hour. In contrast, the SI provides only one basic unit for each physical quantity, and universality is thus achieved.

There are seven base-units, and in mechanics calculations three are used, which are for the basic quantities of length, mass, and time, expressed as the meter (m), the kilogram (kg), and the second (s). The other four base-units are the ampere (A) for electric current, the kelvin (K) for thermodynamic temperature, the candela (cd) for luminous intensity, and the mole (mol) for amount of substance.

The SI is a coherent system. A system of units is said to be coherent if the product or quotient of any two unit quantities in the system is the unit of the resultant quantity. For example, in a coherent system in which the foot is a unit of length, the square foot is the unit of area, whereas the acre is not. Further details of the SI, and definitions of the units, are given in the section *MEASURING UNITS* starting on page 2544, near the end of the book.

Other physical quantities are derived from the base-units. For example, the unit of velocity is the meter per second (m/s), which is a combination of the base-units of length and time. The unit of acceleration is the meter per second squared (m/s^2). By applying Newton's second law of motion — force is proportional to mass multiplied by acceleration — the unit of force is obtained, which is the $kg \cdot m/s^2$. This unit is known as the newton, or N. Work, or force times distance, is the $kg \cdot m^2/s^2$, which is the joule, (1 joule = 1 newton-meter) and energy is also expressed in these terms. The abbreviation for joule is J. Power, or work per unit time, is the $kg \cdot m^2/s^3$, which is the watt (1 watt = 1 joule per second = 1 newton-meter per second). The abbreviation for watt is W.

More information on Newton's laws may be found in the section *Newton's Laws of Motion* on page 167.

The coherence of SI units has two important advantages. The first, that of uniqueness and therefore universality, has been explained. The second is that it greatly simplifies technical calculations. Equations representing physical principles can be applied without introducing such numbers as 550 in power calculations, which, in the English system of measurement have to be used to convert units. Thus conversion factors largely disappear from calculations carried out in SI units, with a great saving in time and labor.

Mass, Weight, Force, Load: SI is an absolute system (see *Unit Systems* on page 142), and consequently it is necessary to make a clear distinction between mass and weight. The *mass* of a body is a measure of its inertia, whereas the weight of a body is the *force* exerted on it by gravity. In a fixed gravitational field, weight is directly proportional to mass, and the distinction between the two can be easily overlooked. However, if a body is moved to a different gravitational field, for example, that of the moon, its weight alters, but its mass remains unchanged. Since the gravitational field on earth varies from place to place by only a small amount, and weight is proportional to mass, it is practical to use the weight of unit mass as a unit of force, and this procedure is adopted in both the English and older metric systems of measurement. In common usage, they are given the same names, and we say that a mass of 1 pound has a weight of 1 pound. In the former case the pound is being used as a unit of mass, and in the latter case, as a unit of force. This procedure is convenient in some branches of engineering, but leads to confusion in others.

As mentioned earlier, Newton's second law of motion states that force is proportional to mass times acceleration. Because an unsupported body on the earth's surface falls with acceleration g (32 ft/s^2 approximately), the pound (force) is that force which will impart an

Copyright 2004, Industrial Press, Inc., New York, NY

acceleration of g ft/s^2 to a pound (mass). Similarly, the kilogram (force) is that force which will impart an acceleration of g (9.8 meters per second^2 approximately), to a mass of one kilogram. In the SI, the *newton* is that force which will impart unit acceleration (1 m/s^2) to a mass of one kilogram. It is therefore smaller than the kilogram (force) in the ratio 1:g (about 1:9.8). This fact has important consequences in engineering calculations. The factor g now disappears from a wide range of formulas in dynamics, but appears in many formulas in statics where it was formerly absent. It is however not quite the same g, for reasons which will now be explained.

In the article on page 171, the mass of a body is referred to as M, but it is immediately replaced in subsequent formulas by W/g, where W is the weight in pounds (force), which leads to familiar expressions such as $WV^2 / 2g$ for kinetic energy. In this treatment, the M which appears briefly is really expressed in terms of the slug (page 142), a unit normally used only in aeronautical engineering. In everyday engineers' language, weight and mass are regarded as synonymous and expressions such as $WV^2 / 2g$ are used without pondering the distinction. Nevertheless, on reflection it seems odd that g should appear in a formula which has nothing to do with gravity at all. In fact the g used here is not the true, local value of the acceleration due to gravity, but an arbitrary standard value which has been chosen as part of the definition of the pound (force) and is more properly designated g_o (page 142). Its function is not to indicate the strength of the local gravitational field, but to convert from one unit to another.

In the SI the unit of mass is the *kilogram*, and the unit of force (and therefore weight) is the *newton*.

The following are typical statements in dynamics expressed in SI units:

A force of R newtons acting on a mass of M kilograms produces an acceleration of R/M meters per second^2. The kinetic energy of a mass of M kg moving with velocity V m/s is $\frac{1}{2} MV^2$ kg (m/s)^2 or $\frac{1}{2} MV^2$ joules. The work done by a force of R newtons moving a distance L meters is RL Nm, or RL joules. If this work were converted entirely into kinetic energy we could write $RL = \frac{1}{2} MV^2$ and it is instructive to consider the units. Remembering that the N is the same as the kg · m/s^2, we have (kg · m/s)^2 × m = kg (m/s)^2, which is obviously correct. It will be noted that g does not appear anywhere in these statements.

In contrast, in many branches of engineering where the weight of a body is important, rather than its mass, using SI units, g does appear where formerly it was absent. Thus, if a rope hangs vertically supporting a mass of M kilograms the tension in the rope is Mg N. Here g is the acceleration due to gravity, and its units are m/s^2. The ordinary numerical value of 9.81 will be sufficiently accurate for most purposes on earth. The expression is still valid elsewhere, for example, on the moon, provided the proper value of g is used. The maximum tension the rope can safely withstand (and other similar properties) will also be specified in terms of the newton, so that direct comparison may be made with the tension predicted.

Words like load and weight have to be used with greater care. In everyday language we might say "a lift carries a load of five people of average weight 70 kg," but in precise technical language we say that if the average mass is 70 kg, then the average weight is 70g N, and the total load (that is force) on the lift is 350g N.

If the lift starts to rise with acceleration a · m/s^2, the load becomes 350 ($g + a$) N; both g and a have units of m/s^2, the mass is in kg, so the load is in terms of kg · m/s^2, which is the same as the newton.

Pressure and stress: These quantities are expressed in terms of force per unit area. In the SI the unit is the pascal (Pa), which expressed in terms of SI derived and base units is the newton per meter squared (N/m^2). The pascal is very small—it is only equivalent to 0.15 × 10^{-3} lb/in^2 — hence the kilopascal (kPa = 1000 pascals), and the megapascal (MPa = 10^6

Copyright 2004, Industrial Press, Inc., New York, NY

pascals) may be more convenient multiples in practice. Thus, note: 1 newton per millimeter squared = 1 meganewton per meter squared = 1 megapascal.

In addition to the pascal, the bar, a non-SI unit, is in use in the field of pressure measurement in some countries, including England. Thus, in view of existing practice, the International Committee of Weights and Measures (CIPM) decided in 1969 to retain this unit for a limited time for use with those of SI. The bar = 10^5 pascals and the hectobar = 10^7 pascals.

Force Systems

Scalar and Vector Quantities.— The quantities dealt with in mechanics are of two kinds according to whether magnitude alone or direction as well as magnitude must be known in order to completely specify them. Quantities such as time, volume and density are completely specified when their magnitude is known. Such quantities are called *scalar* quantities. Quantities such as force, velocity, acceleration, moment, and displacement which must, in order to be specified completely, have a specific direction as well as magnitude, are called *vector* quantities.

Graphical Representation of Forces.— A force has three characteristics which, when known, determine it. They are *direction, point of application*, and *magnitude*. The direction of a force is the direction in which it tends to move the body upon which it acts. The point of application is the place on the line of action where the force is applied. Forces may conveniently be represented by straight lines and arrow heads. The arrow head indicates the direction of the force, and the length of the line, its magnitude to any suitable scale. The point of application may be at any point on the line, but it is generally convenient to assume it to be at one end. In the accompanying illustration, a force is supposed to act along line *AB* in a direction from left to right. The length of line *AB* shows the magnitude of the force. If point *A* is the point of application, the force is exerted as a pull, but if point *B* be assumed to be the point of application, it would indicate that the force is exerted as a push.



Vector

Velocities, moments, displacements, etc. may similarly be represented and manipulated graphically because they are all of the same class of quantities called vectors. (See *Scalar and Vector Quantities*.)

Addition and Subtraction of Forces: The resultant of two forces applied at the same point and acting in the same direction, is equal to the sum of the forces. For example, if the two forces *AB* and *AC*, one equal to two and the other equal to three pounds, are applied at point *A*, then their resultant *AD* equals the sum of these forces, or five pounds.



Fig. 1.



Fig. 2.

If two forces act in opposite directions, then their resultant is equal to their difference, and the direction of the resultant is the same as the direction of the greater of the two forces. For example: *AB* and *AC* are both applied at point *A*; then, if *AB* equals four and *AC* equals six pounds, the resultant *AD* equals two pounds and acts in the direction of *AC*.

Parallelogram of Forces: If two forces applied at a point are represented in magnitude and direction by the adjacent sides of a parallelogram (*AB* and *AC* in Fig. 3), their resultant

Copyright 2004, Industrial Press, Inc., New York, NY

will be represented in magnitude and direction by the diagonal *AR* drawn from the intersection of the two component forces.



Fig. 3.



Fig. 4.



Fig. 5.

If two forces *P* and *Q* do not have the same point of application, as in Fig. 4, but the lines indicating their directions intersect, the forces may be imagined as applied at the point of intersection between the lines (as at *A*), and the resultant of the two forces may be found by constructing the parallelogram of forces. Line *AR* shows the direction and magnitude of the resultant, the point of application of which may be assumed to be at any point on line *AR* or its extension.

If the resultant of three or more forces having the same point of application is to be found, as in Fig. 5, first find the resultant of any two of the forces (*AB* and *AC*) and then find the resultant of the resultant just found (AR_1) and the third force (*AD*). If there are more than three forces, continue in this manner until the resultant of all the forces has been found.

Parallel Forces: If two forces are parallel and act in the same direction, as in Fig. 6, then their resultant is parallel to both lines, is located between them, and is equal to the sum of the two components. The point of application of the resultant divides the line joining the points of application of the components inversely as the magnitude of the components. Thus,

$$AB : CE = CD : AD$$

The resultant of two parallel and unequal forces acting in opposite directions, Fig. 7, is parallel to both lines, is located outside of them on the side of the greater of the components, has the same direction as the greater component, and is equal in magnitude to the difference between the two components. The point of application on the line *AC* produced is found from the proportion:

$$AB : CD = CE : AE$$



Fig. 6.



Fig. 7.

Polygon of Forces: When several forces are applied at a point and act in a single plane, Fig. 8, their resultant may be found more simply than by the method just described, as follows: From the extreme end of the line representing the first force, draw a line representing the second force, parallel to it and of the same length and in the direction of the second force. Then through the extreme end of this line draw a line parallel to, and of the same length and direction as the third force, and continue this until all the forces have been thus

Copyright 2004, Industrial Press, Inc., New York, NY

represented. Then draw a line from the point of application of the forces (as *A*) to the extreme point (as 5_1) of the line last drawn. This line ($A\,5_1$) is the resultant of the forces.



Fig. 8.



Fig. 9.

Moment of a Force: The moment of a force with respect to a point is the product of the force multiplied by the perpendicular distance from the given point to the direction of the force. In Fig. 9, the moment of the force *P* with relation to point *A* is $P \times AB$. The perpendicular distance *AB* is called the lever-arm of the force. The moment is the measure of the tendency of the force to produce rotation about the given point, which is termed the center of moments. If the force is measured in pounds and the distance in inches, the moment is expressed in inch-pounds. **In metric SI units, the moment is expressed in newton-meters (N · m), or newton-millimeters (N · mm).**

The moment of the resultant of any number of forces acting together in the same plane is equal to the algebraic sum of the moments of the separate forces.

Couples.— If the forces *AB* and *CD* are equal and parallel but act in opposite directions, then the resultant equals 0, or, in other words, the two forces have no resultant and are called a couple. A couple tends to produce rotation. The measure of this tendency is called the moment of the couple and is the product of one of the forces multiplied by the distance between the two.



Two Examples of Couples

As a couple has no resultant, no single force can balance or counteract the tendency of the couple to produce rotation. To prevent the rotation of a body acted upon by a couple, two other forces are therefore required, forming a second couple. In the illustration, *E* and *F* form one couple and *G* and *H* are the balancing couple. The body on which they act is in equilibrium if the moments of the two couples are equal and tend to rotate the body in opposite directions. A couple may also be represented by a vector in the direction of the axis about which the couple acts. The length of the vector, to some scale, represents the magnitude of the couple, and the direction of the vector is that in which a right-hand screw would advance if it were to be rotated by the couple.

Copyright 2004, Industrial Press, Inc., New York, NY

Composition of a Single Force and Couple.— A single force and a couple in the same plane or in parallel planes may be replaced by another single force equal and parallel to the first force, at a distance from it equal to the moment of the couple divided by the magnitude of the force. The new single force is located so that the moment of the resultant about the point of application of the original force is of the same sign as the moment of the couple.

In the next figure, with the couple $N - N$ in the position shown, the resultant of P, $-N$, and N is O (which equals P) acting on a line through point c so that $(P - N) \times ac = N \times bc$.

Thus, it follows that,

$$ac = \frac{N(ac + bc)}{P} = \frac{\text{Moment of Couple}}{P}$$



Single Force and Couple Composition

Algebraic Composition and Resolution of Force Systems.— The graphical methods given beginning on page 145 are convenient for solving problems involving force systems in which all of the forces lie in the same plane and only a few forces are involved. If many forces are involved, however, or the forces do not lie in the same plane, it is better to use algebraic methods to avoid complicated space diagrams. Systematic procedures for solving force problems by algebraic methods are outlined beginning on page 148. In connection with the use of these procedures, it is necessary to define several terms applicable to force systems in general.

The single force which produces the same effect upon a body as two or more forces acting together is called their *resultant*. The separate forces which can be so combined are called the *components*. Finding the resultant of two or more forces is called the *composition of forces*, and finding two or more components of a given force, the *resolution of forces*. Forces are said to be *concurrent* when their lines of action can be extended to meet at a common point; forces that are *parallel* are, of course, *nonconcurrent*. Two forces having the same line of action are said to be *collinear*. Two forces equal in magnitude, parallel, and in opposite directions constitute a *couple*. Forces all in the same plane are said to be *coplanar;* if not in the same plane, they are called *noncoplanar* forces.

The *resultant* of a system of forces is the simplest equivalent system that can be determined. It may be a single force, a couple, or a noncoplanar force and a couple. This last type of resultant, a noncoplanar force and a couple, may be replaced, if desired, by two *skewed* forces (forces that are nonconcurrent, nonparallel, and noncoplanar). When the resultant of a system of forces is zero, the system is in equilibrium, that is, the body on which the force system acts remains at rest or continues to move with uniform velocity.

Copyright 2004, Industrial Press, Inc., New York, NY

Algebraic Solution of Force Systems—All Forces in the Same Plane

Finding Two Concurrent Components of a Single Force:



Case I: To find two components F_1 and F_2 at angles θ and ϕ, ϕ not being 90°.

$$F_1 = \frac{F\sin\theta}{\sin\phi}$$

$$F_2 = \frac{F\sin(\phi-\theta)}{\sin\phi}$$



Case II: Components F_1 and F_2 form 90° angle.

$$F_1 = F\sin\theta$$

$$F_2 = F\cos\theta$$

Finding the Resultant of Two Concurrent Forces:



Case I: Forces F_1 and F_2 do not form 90° angle.

$$R = \frac{F_1\sin\phi}{\sin\theta} \text{ or } R = \frac{F_2\sin\phi}{\sin(\phi-\theta)} \text{ or}$$

$$R = \sqrt{F_1^2 + F_2^2 + 2F_1F_2\cos\phi}$$

$$\tan\theta = \frac{F_1\sin\phi}{F_1\cos\phi + F_2}$$



Case II: Forces F_1 and F_2 form 90° angle.

$$R = \frac{F_2}{\cos\theta} \quad \text{or} \quad R = \frac{F_1}{\sin\theta} \text{ or}$$

$$R = \sqrt{{F_1}^2 + {F_2}^2}$$

$$\tan\theta = \frac{F_1}{F_2}$$

Finding the Resultant of Three or More Concurrent Forces:



To determine resultant of forces F_1, F_2, F_3, etc. making angles, respectively, of $\theta_1, \theta_2, \theta_3$, etc. with the *x* axis, find the *x* and *y* components F_x and F_y of each force and arrange in a table similar to that shown below for a system of three forces. Find the algebraic sum of the F_x and F_y components (ΣF_x and ΣF_y) and use these to determine resultant *R*.

Force	F_x	F_y
F_1	$F_1\cos\theta_1$	$F_1\sin\theta_1$
F_2	$F_2\cos\theta_2$	$F_2\sin\theta_2$
F_3	$F_3\cos\theta_3$	$F_3\sin\theta_3$
	ΣF_x	ΣF_y

$$R = \sqrt{(\Sigma F_x)^2 + (\Sigma F_y)^2}$$

$$\cos\theta_R = \frac{\Sigma F_x}{R}$$

$$\text{or } \tan\theta_R = \frac{\Sigma F_y}{\Sigma F_x}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Finding a Force and a Couple Which Together are Equivalent to a Single Force:



To resolve a single force F into a couple of moment M and a force P passing through any chosen point O at a distance d from the original force F, use the relations

$$P = F$$
$$M = F \times d$$

The moment M must, of course, tend to produce rotation about O in the same direction as the original force. Thus, as seen in the diagram, F tends to produce clockwise rotation; hence M is shown clockwise.

Finding the Resultant of a Single Force and a Couple:



The resultant of a single force F and a couple M is a single force R equal in magnitude and direction to F and parallel to it at a distance d to the left or right of F.

$$R = F$$
$$d = M \div R$$

Resultant R is placed to the left or right of point of application O of the original force F depending on which position will give R the same direction of moment about O as the original couple M.

Finding the Resultant of a System of Parallel Forces:



To find the resultant of a system of coplanar parallel forces, proceed as indicated below.

1) Select any convenient point O from which perpendicular distances d_1, d_2, d_3, etc. to parallel forces F_1, F_2, F_3, etc. can be specified or calculated.

2) Find the algebraic sum of all the forces; this will give the magnitude of the resultant of the system.

$$R = \Sigma F = F_1 + F_2 + F_3 + \ldots$$

3) Find the algebraic sum of the moments of the forces about O; clockwise moments may be taken as negative and counterclockwise moments as positive:

$$\Sigma M_O = F_1 d_1 + F_2 d_2 + \ldots$$

4) Calculate the distance d from O to the line of action of resultant R:

$$d = \Sigma M_O \div R$$

This distance is measured to the left or right from O depending on which position will give the moment of R the same direction of rotation about O as the couple ΣM_O, that is, if ΣM_O is negative, then d is left or right of O depending on which direction will make $R \times d$ negative.

Note Concerning Interpretation of Results: If $R = 0$, then the resultant of the system is a couple ΣM_O; if $\Sigma M_O = 0$ then the resultant is a single force R; if both R and $\Sigma M_O = 0$, then the system is in equilibrium.

Copyright 2004, Industrial Press, Inc., New York, NY

Finding the Resultant of Forces Not Intersecting at a Common Point:



To determine the resultant of a coplanar, nonconcurrent, nonparallel force system as shown in the diagram, proceed as shown below.

1) Draw a set of x and y coordinate axes through any convenient point O in the plane of the forces as shown in the diagram.

2) Determine the x and y coordinates of any convenient point on the line of action of each force and the angle θ, measured in a counterclockwise direction, that each line of action makes with the positive x axis. For example, in the diagram, coordinates x_4, y_4, and θ_4 are shown for F_4. Similar data should be known for each of the forces of the system.

3) Calculate the x and y components (F_x, F_y) of each force and the moment of each component about O. Counterclockwise moments are considered positive and clockwise moments are negative. Tabulate all results in a manner similar to that shown below for a system of three forces and find $\Sigma F_x, \Sigma F_y, \Sigma M_O$ by algebraic addition.

Force	Coordinates of F			Components of F		Moment of F about O
F	x	y	θ	F_x	F_y	$M_O = xF_y - yF_x$
F_1	x_1	y_1	θ_1	$F_1 \cos\theta_1$	$F_1 \sin\theta_1$	$x_1F_1 \sin\theta_1 - y_1F_1 \cos\theta_1$
F_2	x_2	y_2	θ_2	$F_2 \cos\theta_2$	$F_2 \sin\theta_2$	$x_2F_2 \sin\theta_2 - y_2F_2 \cos\theta_2$
F_3	x_3	y_3	θ_3	$F_3 \cos\theta_3$	$F_3 \sin\theta_3$	$x_3F_3 \sin\theta_3 - y_3F_3 \cos\theta_3$
				ΣF_x	ΣF_y	ΣM_O

4. Compute the resultant of the system and the angle θ_R it makes with the x axis by using the formulas:

$$R = \sqrt{(\Sigma F_x)^2 + (\Sigma F_y)^2}$$

$$\cos\theta_R = \Sigma F_x \div R \text{ or } \tan\theta_R = \Sigma F_y \div \Sigma F_x$$

5. Calculate the distance d from O to the line of action of the resultant R:

$$d = \Sigma M_O \div R$$

Distance d is in such direction from O as will make the moment of R about O have the same sign as ΣM_O.

Note Concerning Interpretation of Results: If $R = 0$, then the resultant is a couple ΣM_O; if $\Sigma M_O = 0$, then R passes through O; if both $R = 0$ and $\Sigma M_O = 0$, then the system is in equilibrium.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: Find the resultant of three coplanar nonconcurrent forces for which the following data are given.

$F_1 = 10$ lbs; $x_1 = 5$ in.; $y_1 = -1$ in.; $\theta_1 = 270°$

$F_2 = 20$ lbs; $x_2 = 4$ in.; $y_2 = 1.5$ in.; $\theta_2 = 50°$

$F_3 = 30$ lbs; $x_3 = 2$ in.; $y_3 = 2$ in.; $\theta_3 = 60°$

$F_{x_1} = 10\cos 270° = 10 \times 0 = 0$ lbs.

$F_{x_2} = 20\cos 50° = 20 \times 0.64279 = 12.86$ lbs.

$F_{x_3} = 30\cos 60° = 30 \times 0.5000 = 15.00$ lbs.

$F_{y_1} = 10 \times \sin 270° = 10 \times (-1) = -10.00$ lbs.

$F_{y_2} = 20 \times \sin 50° = 20 \times 0.76604 = 15.32$ lbs.

$F_{y_3} = 30 \times \sin 60° = 30 \times 0.86603 = 25.98$ lbs.

$M_{o_1} = 5 \times (-10) - (-1) \times 0 = -50$ in. lbs.

$M_{o_2} = 4 \times 15.32 - 1.5 \times 12.86 = 41.99$ in. lbs.

$M_{o_3} = 2 \times 25.98 - 2 \times 15 = 21.96$ in. lbs.

***Note:* When working in metric SI units, pounds are replaced by newtons (N); inches by meters or millimeters, and inch-pounds by newton-meters (N · m) or newton-millimeters (N · mm).**

Force	Coordinates of F			Components of F		Moment of F about O
F	x	y	θ	F_x	F_y	
$F_1 = 10$	5	−1	270°	0	−10.00	−50.00
$F_2 = 20$	4	1.5	50°	12.86	15.32	41.99
$F_3 = 30$	2	2	60°	15.00	25.98	21.96
				$\Sigma F_x = 27.86$	$\Sigma F_y = 31.30$	$\Sigma M_O = 13.95$

$$R = \sqrt{(27.86)^2 + (31.30)^2} = 41.90 \text{ lbs.}$$

$$\tan\theta_R = \frac{31.30}{27.86} = 1.1235$$

$$\theta_R = 48°20'$$

$$d = \frac{13.95}{41.90} = 0.33 \text{ inches}$$

measured as shown on the diagram.



Copyright 2004, Industrial Press, Inc., New York, NY

Algebraic Solution of Force Systems — Forces Not in Same Plane

Resolving a Single Force Into Its Three Rectangular Components:



$$F_x = F\cos\theta_x$$
$$F_y = F\cos\theta_y$$
$$F_z = F\cos\theta_z$$
$$F = \sqrt{F_x^2 + F_y^2 + F_z^2}$$

The diagram shows how a force F may be resolved at any point O on its line of action into three concurrent components each of which is perpendicular to the other two.

The x, y, z components F_x, F_y, F_z of force F are determined from the accompanying relations in which $\theta_x, \theta_y, \theta_z$ are the angles that the force F makes with the x, y, z axes.

Finding the Resultant of Any Number of Concurrent Forces:



To find the resultant of any number of noncoplanar concurrent forces F_1, F_2, F_3, etc., use the procedure outlined below.

1) Draw a set of x, y, z axes at O, the point of concurrency of the forces. The angles each force makes measured counterclockwise from the positive x, y, and z coordinate axes must be known in addition to the magnitudes of the forces. For force F_2, for example, the angles are $\theta_{x2}, \theta_{y2}, \theta_{z2}$ as indicated on the diagram.

2) Apply the first three formulas given under the heading "Resolving a Single Force Into Its Three Rectangular Components" to each force to find its x, y, and z components. Tabulate these calculations as shown below for a system of three forces. Algebraically add the calculated components to find ΣF_x, ΣF_y, and ΣF_z which are the components of the resultant.

Force	Angles			Components of Forces		
F	θ_x	θ_y	θ_z	F_x	F_y	F_z
F_1	θ_{x1}	θ_{y1}	θ_{z1}	$F_1\cos\theta_{x1}$	$F_1\cos\theta_{y1}$	$F_1\cos\theta_{z1}$
F_2	θ_{x2}	θ_{y2}	θ_{z2}	$F_2\cos\theta_{x2}$	$F_2\cos\theta_{y2}$	$F_2\cos\theta_{z2}$
F_3	θ_{x3}	θ_{y3}	θ_{z3}	$F_3\cos\theta_{x3}$	$F_3\cos\theta_{y3}$	$F_3\cos\theta_{z3}$
				ΣF_x	ΣF_y	ΣF_z

3. Find the resultant of the system from the formula $R = \sqrt{(\Sigma F_x)^2 + (\Sigma F_y)^2 + (\Sigma F_z)^2}$

4. Calculate the angles θ_{xR}, θ_{yR}, and θ_{zR} that the resultant R makes with the respective coordinate axes:

$$\cos\theta_{xR} = \frac{\Sigma F_x}{R}$$
$$\cos\theta_{yR} = \frac{\Sigma F_y}{R}$$
$$\cos\theta_{zR} = \frac{\Sigma F_z}{R}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Finding the Resultant of Parallel Forces Not in the Same Plane:



In the diagram, forces F_1, F_2, etc. represent a system of noncoplanar parallel forces. To find the resultant of such systems, use the procedure shown below.

1) Draw a set of x, y, and z coordinate axes through any point O in such a way that one of these axes, say the z axis, is parallel to the lines of action of the forces. The x and y axes then will be perpendicular to the forces.

2) Set the distances of each force from the x and y axes in a table as shown below. For example, x_1 and y_1 are the x and y distances for F_1 shown in the diagram.

3) Calculate the moment of each force about the x and y axes and set the results in the table as shown for a system consisting of three forces. The algebraic sums of the moments ΣM_x and ΣM_y are then obtained. (In taking moments about the x and y axes, assign counterclockwise moments a plus (+) sign and clockwise moments a minus (−) sign. In deciding whether a moment is counterclockwise or clockwise, look from the positive side of the axis in question toward the negative side.)

Force	Coordinates of Force F		Moments M_x and M_y due to F	
F	x	y	M_x	M_y
F_1	x_1	y_1	F_1y_1	F_1x_1
F_2	x_2	y_2	F_2y_2	F_2x_2
F_3	x_3	y_3	F_3y_3	F_3x_3
ΣF			ΣM_x	ΣM_y

4. Find the algebraic sum ΣF of all the forces; this will be the resultant R of the system.

$$R = \Sigma F = F_1 + F_2 + \ldots$$

5. Calculate x_R and y_R, the moment arms of the resultant:

$$x_R = \Sigma M_y \div R$$

$$y_R = \Sigma M_x \div R$$

These moment arms are measured in such direction along the x and y axes as will give the resultant a moment of the same direction of rotation as ΣM_x and ΣM_y.

Note Concerning Interpretation of Results: If ΣM_x and ΣM_y are both 0, then the resultant is a single force R along the z axis; if R is also 0, then the system is in equilibrium. If R is 0 but ΣM_x and ΣM_y are not both 0, then the resultant is a couple

$$M_R = \sqrt{(\Sigma M_x)^2 + (\Sigma M_y)^2}$$

that lies in a plane parallel to the z axis and making an angle θ_R measured in a counterclockwise direction from the positive x axis and calculated from the following formula:

$$\sin\theta_R = \frac{\Sigma M_x}{M_R}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Finding the Resultant of Nonparallel Forces Not Meeting at a Common Point:



The diagram shows a system of noncoplanar, nonparallel, noncon-current forces F_1, F_2, etc. for which the resultant is to be determined. Generally speaking, the resultant will be a noncoplanar force and a couple which may be further combined, if desired, into two forces that are skewed.

This is the most general force system that can be devised, so each of the other systems so far described represents a special, simpler case of this general force system. The method of solution described below for a system of three forces applies for any number of forces.

1) Select a set of coordinate x, y, and z axes at any desired point O in the body as shown in the diagram.

2) Determine the x, y, and z coordinates of any convenient point on the line of action of each force as shown for F_2. Also determine the angles, $\theta_x, \theta_y, \theta_z$ that each force makes with each coordinate axis. These angles are measured counterclockwise from the positive direction of the x, y, and z axes. The data is tabulated, as shown in the table accompanying Step 3, for convenient use in subsequent calculations.

3) Calculate the x, y, and z components of each force using the formulas given in the accompanying table. Add these components algebraically to get $\Sigma F_x, \Sigma F_y$ and ΣF_z which are the components of the resultant, R, given by the formula,

$$R = \sqrt{(\Sigma F_x)^2 + (\Sigma F_y)^2 + (\Sigma F_z)^2}$$

Force	Coordinates of Force F						Components of F		
F	x	y	z	θ_x	θ_y	θ_z	F_x	F_y	F_z
F_1	x_1	y_1	z_1	θ_{x1}	θ_{y1}	θ_{z1}	$F_1 \cos \theta_{x1}$	$F_1 \cos \theta_{y1}$	$F_1 \cos \theta_{z1}$
F_2	x_2	y_2	z_2	θ_{x2}	θ_{y2}	θ_{z2}	$F_2 \cos \theta_{x2}$	$F_2 \cos \theta_{y2}$	$F_2 \cos \theta_{z2}$
F_3	x_3	y_3	z_3	θ_{x3}	θ_{y3}	θ_{z3}	$F_3 \cos \theta_{x3}$	$F_3 \cos \theta_{y3}$	$F_3 \cos \theta_{z3}$
							ΣF_x	ΣF_y	ΣF_z

The resultant force R makes angles of θ_{xR}, θ_{yR}, and θ_{zR} with the x, y, and z axes, respectively, and passes through the selected point O. These angles are determined from the formulas,

$$\cos \theta_{xR} = \Sigma F_x \div R$$
$$\cos \theta_{yR} = \Sigma F_y \div R$$
$$\cos \theta_{zR} = \Sigma F_z \div R$$

Copyright 2004, Industrial Press, Inc., New York, NY

4. Calculate the moments M_x, M_y, M_z about x, y, and z axes, respectively, due to the F_x, F_y, and F_z components of each force and set them in tabular form. The formulas to use are given in the accompanying table.

In interpreting moments about the x, y, and z axes, consider counterclockwise moments a plus (+) sign and clockwise moments a minus (–) sign. In deciding whether a moment is counterclockwise or clockwise, look from the positive side of the axis in question toward the negative side.

Force	Moments of Components of F (F_x, F_y, F_z) about x, y, z axes		
F	$M_x = yF_z - zF_y$	$M_y = zF_x - xF_z$	$M_z = xF_y - yF_x$
F_1	$M_{x1} = y_1F_{z1} - z_1F_{y1}$	$M_{y1} = z_1F_{x1} - x_1F_{z1}$	$M_{z1} = x_1F_{y1} - y_1F_{x1}$
F_2	$M_{x2} = y_2F_{z2} - z_2F_{y2}$	$M_{y2} = z_2F_{x2} - x_2F_{z2}$	$M_{z2} = x_2F_{y2} - y_2F_{x2}$
F_3	$M_{x3} = y_3F_{z3} - z_3F_{y3}$	$M_{y3} = z_3F_{x3} - x_3F_{z3}$	$M_{z3} = x_3F_{y3} - y_3F_{x3}$
	ΣM_x	ΣM_y	ΣM_z

5. Add the component moments algebraically to get $\Sigma M_x, \Sigma M_y$ and ΣM_z which are the components of the resultant couple, M, given by the formula,

$$M = \sqrt{(\Sigma M_x)^2 + (\Sigma M_y)^2 + (\Sigma M_z)^2}$$

The resultant couple M will tend to produce rotation about an axis making angles of β_x, β_y, and β_z with the x, y, z axes, respectively. These angles are determined from the formulas,

$$\cos\beta_x = \frac{\Sigma M_x}{M} \qquad \cos\beta_y = \frac{\Sigma M_y}{M} \qquad \cos\beta_z = \frac{\Sigma M_z}{M}$$

General Method of Locating Resultant When Its Components are Known: To determine the position of the resultant force of a system of forces, proceed as follows:

From the origin, point O, of a set of coordinate axes x, y, z, lay off on the x axis a length A representing the algebraic sum ΣF_x of the x components of all the forces. From the end of line A lay off a line B representing ΣF_y, the algebraic sum of the y components; this line B is drawn in a direction parallel to the y axis. From the end of line B lay off a line C representing ΣF_z. Finally, draw a line R from O to the end of C; R will be the resultant of the system.



Copyright 2004, Industrial Press, Inc., New York, NY

Friction

Properties of Friction.— Friction is the resistance to motion that takes place when one body is moved upon another, and is generally defined as "that force which acts between two bodies at their surface of contact, so as to resist their sliding on each other." According to the conditions under which sliding occurs, the force of friction, F, bears a certain relation to the force between the two bodies called the normal force N. The relation between force of friction and normal force is given by the *coefficient of friction*, generally denoted by the Greek letter μ. Thus:

$$F = \mu \times N \qquad \text{and} \qquad \mu = \frac{F}{N}$$

Example: A body weighing 28 pounds rests on a horizontal surface. The force required to keep it in motion along the surface is 7 pounds. Find the coefficient of friction.

$$\mu = \frac{F}{N} = \frac{7}{28} = 0.25$$

If a body is placed on an inclined plane, the friction between the body and the plane will prevent it from sliding down the inclined surface, provided the angle of the plane with the horizontal is not too great. There will be a certain angle, however, at which the body will just barely be able to remain stationary, the frictional resistance being very nearly overcome by the tendency of the body to slide down. This angle is termed the angle of repose, and the tangent of this angle equals the coefficient of friction. The angle of repose is frequently denoted by the Greek letter θ. Thus, $\mu = \tan \theta$.

A greater force is required to start a body moving from a state of rest than to merely keep it in motion, because the *friction of rest* is greater than the *friction of motion*.

Laws of Friction.— The laws of friction for unlubricated or dry surfaces are summarized in the following statements.

1) For low pressures (normal force per unit area) the friction is directly proportional to the normal force between the two surfaces. As the pressure increases, the friction does not rise proportionally; but when the pressure becomes abnormally high, the friction increases at a rapid rate until seizing takes place.

2) The friction both in its total amount and its coefficient is independent of the areas in contact, so long as the normal force remains the same. This is true for moderate pressures only. For high pressures, this law is modified in the same way as in the first case.

3) At very low velocities the friction is independent of the velocity of rubbing. As the velocities increase, the friction decreases.

Lubricated Surfaces: For well lubricated surfaces, the laws of friction are considerably different from those governing dry or poorly lubricated surfaces.

1) The frictional resistance is almost independent of the pressure (normal force per unit area) if the surfaces are flooded with oil.

2) The friction varies directly as the speed, at low pressures; but for high pressures the friction is very great at low velocities, approaching a minimum at about two feet per second linear velocity, and afterwards increasing approximately as the square root of the speed.

3) For well lubricated surfaces the frictional resistance depends, to a very great extent, on the temperature, partly because of the change in the viscosity of the oil and partly because, for a journal bearing, the diameter of the bearing increases with the rise of temperature more rapidly than the diameter of the shaft, thus relieving the bearing of side pressure.

4) If the bearing surfaces are flooded with oil, the friction is almost independent of the nature of the material of the surfaces in contact. As the lubrication becomes less ample, the coefficient of friction becomes more dependent upon the material of the surfaces.

Influence of Friction on the Efficiency of Small Machine Elements.— Friction between machine parts lowers the efficiency of a machine. Average values of the efficiency, in per cent, of the most common machine elements when carefully made are ordi-

Copyright 2004, Industrial Press, Inc., New York, NY

nary bearings, 95 to 98; roller bearings, 98; ball bearings, 99; spur gears with cut teeth, including bearings, 99; bevel gears with cut teeth, including bearings, 98; belting, from 96 to 98; high-class silent power transmission chain, 97 to 99; roller chains, 95 to 97.

Coefficients of Friction.— Tables 1 and 2 provide representative values of static friction for various combinations of materials with dry (clean, unlubricated) and lubricated surfaces. The values for static or breakaway friction shown in these tables will generally be higher than the subsequent or sliding friction. Typically, the steel-on-steel static coefficient of 0.8 unlubricated will drop to 0.4 when sliding has been initiated; with oil lubrication, the value will drop from 0.16 to 0.03.

Many factors affect friction, and even slight deviations from normal or test conditions can produce wide variations. Accordingly, when using friction coefficients in design calculations, due allowance or factors of safety should be considered, and in critical applications, specific tests conducted to provide specific coefficients for material, geometry, and/or lubricant combinations.

Table 1. Coefficients of Static Friction for Steel on Various Materials

Material	Coefficient of Friction, μ		Material	Coefficient of Friction, μ	
	Clean	Lubricated		Clean	Lubricated
Steel	0.8	0.16	Hard carbon	0.14	0.11–0.14
Copper-lead alloy	0.22	…	Graphite	0.1	0.1
Phosphor-bronze	0.35	…	Tungsten carbide	0.4–0.6	0.1–0.2
Aluminum-bronze	0.45	…	Plexiglas	0.4–0.5	0.4–0.5
Brass	0.35	0.19	Polystyrene	0.3–0.35	0.3–0.35
Cast iron	0.4	0.21	Polythene	0.2	0.2
Bronze	…	0.16	Teflon	0.04	0.04
Sintered bronze	…	0.13			

Tables 1 and 2 used with permission from *The Friction and Lubrication of Solids*, Vol. 1, by Bowden and Tabor, Clarendon Press, Oxford, 1950.

Table 2. Coefficients of Static Friction for Various Materials Combinations

Material Combination	Coefficient of Friction, μ		Material Combination	Coefficient of Friction, μ	
	Clean	Lubricated		Clean	Lubricated
Aluminum-aluminum	1.35	0.30	Tungsten carbide-tungsten carbide	0.2–0.25	0.12
Cadmium-cadmium	0.5	0.05	Plexiglas-Plexiglas	0.8	0.8
Chromium-chromium	0.41	0.34	Polystyrene-polystyrene	0.5	0.5
Copper-copper	1.0	0.08	Teflon-Teflon	0.04	0.04
Iron-iron	1.0	0.15–0.20	Nylon-nylon	0.15–0.25	…
Magnesium-magnesium	0.6	0.08	Solids on rubber	1–4	…
Nickel-nickel	0.7	0.28	Wood on wood (clean)	0.25–0.5	…
Platinum-platinum	1.2	0.25	Wood on wood (wet)	0.2	…
Silver-silver	1.4	0.55	Wood on metals (clean)	0.2–0.6	…
Zinc-zinc	0.6	0.04	Wood on metals (wet)	0.2	…
Glass-glass	0.9–1.0	0.1–0.6	Brick on wood	0.6	…
Glass-metal	0.5–0.7	0.2–0.3	Leather on wood	0.3–0.4	…
Diamond-diamond	0.1	0.05–0.1	Leather on metal (clean)	0.6	…
Diamond-metal	0.1–0.15	0.1	Leather on metal (wet)	0.4	…
Sapphire-sapphire	0.2	0.2	Leather on metal (greasy)	0.2	…
Hard carbon on carbon	0.16	0.12–0.14	Brake material on cast iron	0.4	…
Graphite-graphite (in vacuum)	0.5–0.8	…	Brake material on cast iron (wet)	0.2	…
Graphite-graphite	0.1	0.1			

Copyright 2004, Industrial Press, Inc., New York, NY

Rolling Friction.— When a body rolls on a surface, the force resisting the motion is termed *rolling friction* or *rolling resistance*. Let W = total weight of rolling body or load on wheel, in pounds; r = radius of wheel, in inches; f = coefficient of rolling resistance, in inches. Then: resistance to rolling, in pounds = $(W \times f) \div r$.

The coefficient of rolling resistance varies with the conditions. For wood on wood it may be assumed as 0.06 inch; for iron on iron, 0.02 inch; iron on granite, 0.085 inch; iron on asphalt, 0.15 inch; and iron on wood, 0.22 inch.

The coefficient of rolling resistance, f, is in inches and is not the same as the sliding or static coefficient of friction given in Tables 1 and 2, which is a dimensionless ratio between frictional resistance and normal load. Various investigators are not in close agreement on the true values for these coefficients and the foregoing values should only be used for the approximate calculation of rolling resistance.

Mechanisms

Levers

Types of Levers	Examples
 $F:W = l:L$ $\quad F \times L = W \times l$ $F = \frac{W \times l}{L}$ $\quad W = \frac{F \times L}{l}$ $L = \frac{W \times a}{W+F} = \frac{W \times l}{F}$ $\quad l = \frac{F \times a}{W+F} = \frac{F \times L}{W}$	A pull of 80 pounds is exerted at the end of the lever, at W; l = 12 inches and L = 32 inches. Find the value of force F required to balance the lever. $F = \frac{80 \times 12}{32} = \frac{960}{32} = 30$ pounds If F = 20; W = 180; and l = 3; how long must L be made to secure equilibrium? $L = \frac{180 \times 3}{20} = 27$
 $F:W = l:L$ $\quad F \times L = W \times l$ $F = \frac{W \times l}{L}$ $\quad W = \frac{F \times L}{l}$ $L = \frac{W \times a}{W-F} = \frac{W \times l}{F}$ $\quad l = \frac{F \times a}{W-F} = \frac{F \times L}{W}$	Total length L of a lever is 25 inches. A weight of 90 pounds is supported at W; l is 10 inches. Find the value of F. $F = \frac{90 \times 10}{25} = 36$ pounds If F = 100 pounds, W = 2200 pounds, and a = 5 feet, what should L equal to secure equilibrium? $L = \frac{2200 \times 5}{2200 - 100} = 5.24$ feet
 When three or more forces act on lever: $F \times x = W \times a + P \times b + Q \times c$ $x = \frac{W \times a + P \times b + Q \times c}{F}$ $F = \frac{W \times a + P \times b + Q \times c}{x}$	Let W = 20, P = 30, and Q = 15 pounds; a = 4, b = 7, and c = 10 inches. If x = 6 inches, find F. $F = \frac{20 \times 4 + 30 \times 7 + 15 \times 10}{6} = 73\frac{1}{3}$ lbs Assuming F = 20 pounds in the example above, how long must lever arm x be made? $x = \frac{20 \times 4 + 30 \times 7 + 15 \times 10}{20} = 22$ inches

The above formulas are valid using metric SI units, with forces expressed in newtons, and lengths in meters. However, it should be noted that the weight of a mass W kilograms is equal to a force of Wg newtons, where g is approximately 9.81 m/s^2. Thus, supposing that in the first

Copyright 2004, Industrial Press, Inc., New York, NY

example $l = 0.4$ m, $L = 1.2$ m, and $W = 30$ kg, then the weight of W is $30g$ newtons, so that the force F required to balance the lever is $F = \frac{30g \times 0.4}{1.2} = 10g = 98.1$ newtons.

This force could be produced by suspending a mass of 10 kg at F.

Table of Forces on Inclined Planes



The table below makes it possible to find the force required for moving a body on an inclined plane. The friction on the plane is not taken into account. The column headed "Tension P in Cable per Ton of 2000 Pounds" gives the pull in pounds required for moving one ton along the inclined surface. The fourth column gives the perpendicular or normal pressure. If the coefficient of friction is known, the added pull required to overcome friction is thus easily determined:

$Q \times$ coefficient of friction = additional pull required.

Per Cent of Grade. Rise, Ft. per 100 Ft.	Angle α	Tension P in Cable per Ton of 2000 Lbs.	Perpendicular Pressure Q on Plane per Ton of 2000 Lbs.	Per Cent of Grade. Rise, Ft. per 100 Ft.	Angle α	Tension P in Cable per Ton of 2000 Lbs.	Perpendicular Pressure Q on Plane per Ton of 2000 Lbs.
1	0.57	20.00	1999.90	51	27.02	976.35	1745.49
2	1.15	40.00	1999.60	52	27.47	993.76	1735.64
3	1.72	59.99	1999.10	53	27.92	1011.07	1725.61
4	2.29	79.98	1998.40	54	28.37	1028.27	1715.42
5	2.86	99.96	1997.50	55	28.81	1045.37	1705.05
6	3.43	119.93	1996.40	56	29.25	1062.37	1694.51
7	4.00	139.89	1995.10	57	29.68	1079.26	1683.80
8	4.57	159.83	1993.60	58	30.11	1096.05	1672.93
9	5.14	179.76	1991.91	59	30.54	1112.72	1661.88
10	5.71	199.67	1990.01	60	30.96	1129.28	1650.67
11	6.28	219.56	1987.91	61	31.38	1145.73	1639.30
12	6.84	239.42	1985.62	62	31.80	1162.07	1627.76
13	7.41	259.27	1983.12	63	32.21	1178.29	1616.06
14	7.97	279.09	1980.43	64	32.62	1194.39	1604.19
15	8.53	298.88	1977.54	65	33.02	1210.37	1592.17
16	9.09	318.64	1974.45	66	33.42	1226.23	1579.98
17	9.65	338.36	1971.17	67	33.82	1241.97	1567.64
18	10.20	358.06	1967.69	68	34.22	1257.59	1555.15
19	10.76	377.72	1964.01	69	34.61	1273.07	1542.49
20	11.31	397.34	1960.13	70	34.99	1288.44	1529.68
21	11.86	416.92	1956.06	71	35.37	1303.67	1516.72
22	12.41	436.46	1951.79	72	35.75	1318.77	1503.61
23	12.95	455.96	1947.33	73	36.13	1333.74	1490.35
24	13.50	475.41	1942.68	74	36.50	1348.58	1476.94
25	14.04	494.81	1937.82	75	36.87	1363.28	1463.38
26	14.57	514.16	1932.78	76	37.23	1377.84	1449.67
27	15.11	533.46	1927.54	77	37.60	1392.27	1435.82
28	15.64	552.71	1922.11	78	37.95	1406.56	1421.83
29	16.17	571.90	1916.49	79	38.31	1420.71	1407.69
30	16.70	591.04	1910.67	80	38.66	1434.71	1393.41
31	17.22	610.12	1904.67	81	39.01	1448.57	1379.00
32	17.74	629.13	1898.47	82	39.35	1462.29	1364.44
33	18.26	648.09	1892.08	83	39.69	1475.86	1349.75
34	18.78	666.97	1885.51	84	40.03	1489.29	1334.93
35	19.29	685.80	1878.75	85	40.36	1502.56	1319.97
36	19.80	704.55	1871.79	86	40.70	1515.69	1304.87
37	20.30	723.23	1864.65	87	41.02	1528.66	1289.65
38	20.81	741.84	1857.33	88	41.35	1541.48	1274.30
39	21.31	760.38	1849.82	89	41.67	1554.14	1258.82
40	21.80	778.84	1842.12	90	41.99	1566.65	1243.22
41	22.29	797.22	1834.24	91	42.30	1579.01	1227.49
42	22.78	815.52	1826.18	92	42.61	1591.20	1211.64
43	23.27	833.74	1817.93	93	42.92	1603.24	1195.67
44	23.75	851.88	1809.50	94	43.23	1615.12	1179.58
45	24.23	869.93	1800.89	95	43.53	1626.83	1163.37
46	24.70	887.90	1792.10	96	43.83	1638.38	1147.04
47	25.17	905.77	1783.14	97	44.13	1649.77	1130.60
48	25.64	923.56	1773.99	98	44.42	1660.99	1114.05
49	26.10	941.25	1764.67	99	44.71	1672.05	1097.38
50	26.57	958.85	1755.17	100	45.00	1682.94	1080.60

Tensions and pressures in pounds.

Copyright 2004, Industrial Press, Inc., New York, NY

Inclined Plane—Wedge

W = weight of body



Neglecting friction:

$$P = W \times \frac{h}{l} = W \times \sin\alpha$$

$$W = P \times \frac{l}{h} = \frac{P}{\sin\alpha} = P \times \operatorname{cosec}\alpha$$

$$Q = W \times \frac{b}{l} = W \times \cos\alpha$$

If friction is taken into account, then

Force P to pull body up is:

$$P = W(\mu\cos\alpha + \sin\alpha)$$

Force P_1 to pull body down is:

$$P_1 = W(\mu\cos\alpha - \sin\alpha)$$

Force P_2 to hold body stationary:

$$P_2 = W(\sin\alpha - \mu\cos\alpha)$$

in which μ is the coefficient of friction.

W = weight of body



Neglecting friction:

$$P = W \times \frac{\sin\alpha}{\cos\beta}$$

$$W = P \times \frac{\cos\beta}{\sin\alpha}$$

$$Q = W \times \frac{\cos(\alpha + \beta)}{\cos\beta}$$

With friction:

Coefficient of friction $= \mu = \tan\phi$

$$P = W \times \frac{\sin(\alpha + \phi)}{\cos(\beta - \phi)}$$

W = weight of body



Neglecting friction:

$$P = W \times \frac{h}{b} = W \times \tan\alpha$$

$$W = P \times \frac{b}{h} = P \times \cot\alpha$$

$$Q = \frac{W}{\cos\alpha} = W \times \sec\alpha$$

With friction:

Coefficient of friction $= \mu = \tan\phi$

$$P = W\tan(\alpha + \phi)$$



Neglecting friction:

$$P = 2Q \times \frac{b}{l} = 2Q \times \sin\alpha$$

$$Q = P \times \frac{l}{2b} = \frac{1}{2}P \times \operatorname{cosec}\alpha$$

With friction:

Coefficient of friction = μ.

$$P = 2Q(\mu\cos\alpha + \sin\alpha)$$



Neglecting friction:

$$P = 2Q \times \frac{b}{h} = 2Q \times \tan\alpha$$

$$Q = P \times \frac{h}{2b} = \frac{1}{2}P \times \cot\alpha$$

With friction:

Coefficient of friction = $\mu = \tan\phi$.

$$P = 2Q\tan(\alpha + \phi)$$



Force Moving Body on Horizontal Plane.—F tends to move B along line CD; Q is the component which actually moves B; P is the pressure, due to F, of the body on CD.

$$Q = F \times \cos\alpha \qquad P = \sqrt{F^2 - Q^2}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Wheels and Pulleys



$$F:W = r:R$$

$$F \times R = W \times r$$

$$F = \frac{W \times r}{R}$$

$$W = \frac{F \times R}{r}$$

$$R = \frac{W \times r}{F}$$

$$r = \frac{F \times R}{W}$$

The radius of a drum on which is wound the lifting rope of a windlass is 2 inches. What force will be exerted at the periphery of a gear of 24 inches diameter, mounted on the same shaft as the drum and transmitting power to it, if one ton (2000 pounds) is to be lifted? Here $W = 2000$; $R = 12$; $r = 2$.

$$F = \frac{2000 \times 2}{12} = 333 \text{ pounds}$$



A, B, C and D are the pitch circles of gears.

$$F = \frac{W \times r \times r_1 \times r_2}{R \times R_1 \times R_2}$$

$$W = \frac{F \times R \times R_1 \times R_2}{r \times r_1 \times r_2}$$

Let the pitch diameters of gears A, B, C and D be 30, 28, 12 and 10 inches, respectively. Then $R_2 = 15$; $R_1 = 14$; $r_1 = 6$; and $r = 5$. Let $R = 12$, and $r_2 = 4$. Then the force F required to lift a weight W of 2000 pounds, friction being neglected, is:

$$F = \frac{2000 \times 5 \times 6 \times 4}{12 \times 14 \times 15} = 95 \text{ pounds}$$



$$F = \tfrac{1}{2}W$$

The velocity with which weight W will be raised equals one-half the velocity of the force applied at F.



$$F:W = \sec\alpha:2$$

$$F = \frac{W \times \sec\alpha}{2}$$

$$W = 2F \times \cos\alpha$$



n = number of strands or parts of rope (n_1, n_2, etc.).

$$F = \frac{1}{n} \times W$$

The velocity with which W will be raised equals $\frac{1}{n}$ of the velocity of the force applied at F.

In the illustration is shown a combination of a double and triple block. The pulleys each turn freely on a pin as axis, and are drawn with different diameters, to show the parts of the rope more clearly. There are 5 parts of rope. Therefore, if 200 pounds is to be lifted, the force F required at the end of the rope is:

$$F = \tfrac{1}{5} \times 200 = 40 \text{ pounds}$$

Note: The above formulas are valid using metric SI units, with forces expressed in newtons, and lengths in meters or millimeters. (See note on page 159 concerning weight and mass.)

Copyright 2004, Industrial Press, Inc., New York, NY

Differential Pulley



In the differential pulley a chain must be used, engaging sprockets, so as to prevent the chain from slipping over the pulley faces.

$$P \times R = \tfrac{1}{2}W(R - r)$$

$$P = \frac{W(R - r)}{2R}$$

$$W = \frac{2PR}{R - r}$$



Chinese Windlass

The Chinese windlass is of the differential motion principle, in that the resultant motion is the difference between two original motions. The hoisting rope is arranged to unwind from one part of a drum or pulley onto another part differing somewhat in diameter. The distance that the load or hook moves for one revolution of the compound hoisting drum is equal to half the difference between the circumferences of the two drum sections.

Screw



F = force at end of handle or wrench; R = lever-arm of F; r = pitch radius of screw; p = lead of thread; Q = load. Then, neglecting friction:

$$F = Q \times \frac{p}{6.2832R} \qquad Q = F \times \frac{6.2832R}{p}$$

If μ is the coefficient of friction, then:
For motion in direction of load Q which *assists* it:

$$F = Q \times \frac{6.2832\mu r - p}{6.2832r + \mu p} \times \frac{r}{R}$$

For motion opposite load Q which *resists* it:

$$F = Q \times \frac{p + 6.2832\mu r}{6.2832r - \mu p} \times \frac{r}{R}$$

Geneva Wheel



Geneva wheels are frequently used on machine tools for indexing or rotating some part of the machine through a fractional part of a revolution.

The driven wheel shown in the illustration has four radial slots located 90 degrees apart, and the driver carries a roller *k* which engages one of these slots each time it makes a revolution, thus turning the driven wheel one-quarter revolution. The concentric surface *b* engages the concave surface *c* between each pair of slots before the driving roller is disengaged from the driven wheel, which prevents the latter from rotating while the roller is moving around to engage the next successive slot. The circular boss *b* on the driver is cut away at *d* to provide a clearance space for the projecting arms of the driven wheel. In designing gearing of the general type illustrated, it is advisable to so proportion the driving and driven members that the angle *a* will be approximately 90 degrees.

The radial slots in the driven part will then be tangent to the circular path of the driving roller at the time the roller enters and leaves the slot. When the gearing is designed in this way, the driven wheel is started gradually from a state of rest and the motion is also gradually checked.

Copyright 2004, Industrial Press, Inc., New York, NY

Toggle Joint

A link mechanism commonly known as a toggle joint is applied to machines of different types, such as drawing and embossing presses, stone crushers, etc., for securing great pressure. The principle of the toggle joint is shown by Fig. 10. There are two links, *b* and *c*, which are connected at the center. Link *b* is free to swivel about a fixed pin or bearing at *d*, and link *e* is connected to a sliding member *e*. Rod *f* joins links *b* and *c* at the central connection. When force is applied to rod *f* in a direction at right angles to center-line *xx*, along which the driven member *e* moves, this force is greatly multiplied at *e*, because a movement at the joint *g* produces a relatively slight movement at *e*. As the angle α becomes less, motion at *e* decreases and the force increases until the links are in line. If *R* = the resistance at *e*, *P* = the applied power or force, and α= the angle between each link, and a line *x–x* passing through the axes of the pins, then:

$$2R \sin \alpha = P \cos \alpha$$



Fig. 10. Toggle Joint Principle

If arms *ED* and *EH* are of unequal length then

$$P = (F \times a) \div b$$

The relation between *P* and *F* changes constantly as *F* moves downward.

If arms *ED* and *EH* are equal, then

$$P = (F \times a) \div 2h$$

A double toggle-joint does not increase the pressure exerted so long as the relative distances moved by *F* and *P* remain the same.



Toggle-joints with Equal Arms



$$2P \sin\alpha = F \cos\alpha$$

$$\frac{P}{F} = \frac{\cos\alpha}{2\sin\alpha} = \text{coefficient}$$

$$P = F \times \text{coefficient}$$

where *F* = force applied; *P* = resistance; and, α = given angle.

Equivalent expressions (see diagram):

$$P = \frac{FS}{4h} \qquad P = \frac{Fs}{H}$$

To use the table, measure angle α, and find the coefficient in the table corresponding to the angle found. The coefficient is the ratio of the resistance to the force applied, and multiplying the force applied by the coefficient gives the resistance, neglecting friction.

Angle °	Coefficient	Angle °	Coefficient	Angle °	Coefficient	Angle °	Coefficient
0.01	2864.79	1.00	28.64	5.25	5.44	23	1.18
0.02	1432.39	1.10	26.04	5.50	5.19	24	1.12
0.03	954.93	1.20	23.87	5.75	4.97	25	1.07
0.04	716.20	1.30	22.03	6.00	4.76	26	1.03
0.05	572.96	1.40	20.46	6.50	4.39	27	0.98
0.10	286.48	1.50	19.09	7.00	4.07	28	0.94
0.15	190.99	1.60	17.90	7.50	3.80	29	0.90
0.20	143.24	1.70	16.85	8.00	3.56	30	0.87
0.25	114.59	1.80	15.91	8.50	3.35	31	0.83
0.30	95.49	1.90	15.07	9.00	3.16	32	0.80
0.35	81.85	2.00	14.32	10.00	2.84	33	0.77
0.40	71.62	2.25	12.73	11.00	2.57	34	0.74
0.45	63.66	2.50	11.45	12.00	2.35	35	0.71
0.50	57.29	2.75	10.41	13.00	2.17	36	0.69
0.55	52.09	3.00	9.54	14.00	2.01	37	0.66
0.60	47.74	3.25	8.81	15.00	1.87	38	0.64
0.65	44.07	3.50	8.17	16.00	1.74	39	0.62
0.70	40.92	3.75	7.63	17.00	1.64	40	0.60
0.75	38.20	4.00	7.15	18.00	1.54	41	0.58
0.80	35.81	4.25	6.73	19.00	1.45	42	0.56
0.85	33.70	4.50	6.35	20.00	1.37	43	0.54
0.90	31.83	4.75	6.02	21.00	1.30	44	0.52
0.95	30.15	5.00	5.72	22.00	1.24	45	0.50

Copyright 2004, Industrial Press, Inc., New York, NY

Pendulums

A *compound* or *physical* pendulum consists of any rigid body suspended from a fixed horizontal axis about which the body may oscillate in a vertical plane due to the action of gravity.

A *simple* or *mathematical* pendulum is similar to a compound pendulum except that the mass of the body is concentrated at a single point which is suspended from a fixed horizontal axis by a weightless cord. Actually, a simple pendulum cannot be constructed since it is impossible to have either a weightless cord or a body whose mass is entirely concentrated at one point. A good approximation, however, consists of a small, heavy bob suspended by a light, fine wire. If these conditions are not met by the pendulum, it should be considered as a compound pendulum.

A *conical* pendulum is similar to a simple pendulum except that the weight suspended by the cord moves at a uniform speed around the circumference of a circle in a horizontal plane instead of oscillating back and forth in a vertical plane. The principle of the conical pendulum is employed in the Watt fly-ball governor.

Four Types of Pendulum



Physical Pendulum



Simple Pendulum



Conical Pendulum



Torsional Pendulum

W = Weight of Disk

A *torsional* pendulum in its simplest form consists of a disk fixed to a slender rod, the other end of which is fastened to a fixed frame. When the disc is twisted through some angle and released, it will then oscillate back and forth about the axis of the rod because of the torque exerted by the rod.

Pendulum Formulas.— From the formulas that follow, the period of vibration or time required for one complete cycle back and forth may be determined for the types of pendulums shown in the accompanying diagram.

Copyright 2004, Industrial Press, Inc., New York, NY

For a *simple* pendulum,

$$T = 2\pi\sqrt{\frac{l}{g}} \tag{1}$$

where T = period in seconds for one complete cycle; g = acceleration due to gravity = 32.17 feet per second per second (approximately); and l is the length of the pendulum in feet as shown on the accompanying diagram.

For a *physical* or *compound* pendulum,

$$T = 2\pi\sqrt{\frac{k_o^2}{gr}} \tag{2}$$

where k_0 = radius of gyration of the pendulum about the axis of rotation, in feet, and r is the distance from the axis of rotation to the center of gravity, in feet.

The metric SI units that can be used in the two above formulas are T = seconds; g = approximately 9.81 meters per second squared, which is the value for acceleration due to gravity; l = the length of the pendulum in meters; k_0 = the radius of gyration in meters, and r = the distance from the axis of rotation to the center of gravity, in meters.

Formulas (1) and (2) are accurate when the angle of oscillation θ shown in the diagram is very small. For θ equal to 22 degrees, these formulas give results that are too small by 1 per cent; for θ equal to 32 degrees, by 2 per cent.

For a *conical* pendulum, the time in seconds for one revolution is:

$$T = 2\pi\sqrt{\frac{l\cos\phi}{g}} \quad \text{(3a)} \qquad \text{or} \qquad T = 2\pi\sqrt{\frac{r\cot\phi}{g}} \quad \text{(3b)}$$

For a *torsional* pendulum consisting of a thin rod and a disk as shown in the figure

$$T = \frac{2}{3}\sqrt{\frac{\pi W r^2 l}{g d^4 G}} \tag{4}$$

where W = weight of disk in pounds; r = radius of disk in feet; l = length of rod in feet; d = diameter of rod in feet; and G = modulus of elasticity in shear of the rod material in pounds per square inch.

The formula using metric SI units is:

$$\boldsymbol{T = 8\sqrt{\frac{\pi M r^2 l}{d^4 G}}}$$

where T = time in seconds for one complete oscillation; M = mass in kilograms; r = radius in meters; l = length of rod in meters; d = diameter of rod in meters; G = modulus of elasticity in shear of the rod material in pascals (newtons per meter squared). The same formula can be applied using millimeters, providing dimensions are expressed in millimeters throughout, and the modulus of elasticity in megapascals (newtons per millimeter squared).

Harmonic.— A harmonic is any component of a periodic quantity which is an integral multiple of the fundamental frequency. For example, a component the frequency of which is twice the fundamental frequency is called the second harmonic.

A harmonic, in electricity, is an alternating-current electromotive force wave of higher frequency than the fundamental, and superimposed on the same so as to distort it from a true sine-wave shape. It is caused by the slots, the shape of the pole pieces, and the pulsation of the armature reaction. The third and the fifth harmonics, i.e., with a frequency three and five times the fundamental, are generally the predominating ones in three-phase machines.

Copyright 2004, Industrial Press, Inc., New York, NY

VELOCITY, ACCELERATION, WORK, AND ENERGY

Velocity and Acceleration

Motion is a progressive change of position of a body. Velocity is the rate of motion, that is, the rate of change of position. When the velocity of a body is the same at every moment during which the motion takes place, the latter is called *uniform* motion. When the velocity is variable and constantly increasing, the rate at which it changes is called *acceleration;* that is, acceleration is the rate at which the velocity of a body changes in a unit of time, as the change in feet per second, in one second. When the motion is decreasing instead of increasing, it is called *retarded* motion, and the rate at which the motion is retarded is frequently called the *deceleration*. If the acceleration is uniform, the motion is called *uniformly accelerated* motion. An example of such motion is found in that of falling bodies.

Newton's Laws of Motion.— The first clear statement of the fundamental relations existing between force and motion was made in the seventeenth century by Sir Isaac Newton, the English mathematician and physicist. It was put in the form of three laws, which are given as originally stated by Newton:

1) Every body continues in its state of rest, or uniform motion in a straight line, except in so far as it may be compelled by force to change that state.
2) Change of motion is proportional to the force applied and takes place in the direction in which that force acts.
3) To every action there is always an equal reaction; or, the mutual actions of two bodies are always equal and oppositely directed.

Motion with Constant Velocity.— In the formulas that follow, S = distance moved; V = velocity; t = time of motion, θ = angle of rotation, and ω = angular velocity; the usual units for these quantities are, respectively, feet, feet per second, seconds, radians, and radians per second. Any other consistent set of units may be employed.

Constant Linear Velocity:

$$S = V \times t \qquad V = S \div t \qquad t = S \div V$$

Constant Angular Velocity:

$$\theta = \omega t \qquad \omega = \theta \div t \qquad t = \theta \div \omega$$

Relation between Angular Motion and Linear Motion: The relation between the angular velocity of a rotating body and the linear velocity of a point at a distance r feet from the center of rotation is:

$$V(\text{ft per sec}) = r(\text{ft}) \times \omega(\text{radians per sec})$$

Similarly, the distance moved by the point during rotation through angle θ is:

$$S(\text{ft}) = r(\text{ft}) \times \theta(\text{radians})$$

Linear Motion with Constant Acceleration.— The relations between distance, velocity, and time for linear motion with constant or uniform acceleration are given by the formulas in the accompanying Table 1. In these formulas, the acceleration is assumed to be in the same direction as the initial velocity; hence, if the acceleration in a particular problem should happen to be in a direction opposite that of the initial velocity, then a should be replaced by $-a$. Thus, for example, the formula $V_f = V_o + at$ becomes $V_f = V_o - at$ when a and V_o are opposite in direction.

Example: A car is moving at 60 mph when the brakes are suddenly locked and the car begins to skid. If it takes 2 seconds to slow the car to 30 mph, at what rate is it being decelerated, how long is it before the car comes to a halt, and how far will it have traveled?

The initial velocity V_o of the car is 60 mph or 88 ft/sec and the acceleration a due to braking is opposite in direction to V_o, since the car is slowed to 30 mph or 44 ft/sec.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Linear Motion with Constant Acceleration

To Find	Known	Formula	To Find	Known	Formula
Motion Uniformly Accelerated From Rest					
S	a, t	$S = \frac{1}{2}at^2$	t	S, V_f	$t = 2S \div V_f$
	V_f, t	$S = \frac{1}{2}V_f t$		S, a	$t = \sqrt{2S \div a}$
	V_f, a	$S = V_f^2 \div 2a$		a, V_f	$t = V_f \div a$
V_f	a, t	$V_f = at$	a	S, t	$a = 2S \div t^2$
	S, t	$V_f = 2S \div t$		S, V	$a = V_f^2 \div 2S$
	a, S	$V_f = \sqrt{2aS}$		V_f, t	$a = V_f \div t$
Motion Uniformly Accelerated From Initial Velocity V_o					
S	a, t, V_o	$S = V_o t + \frac{1}{2}at^2$	t	V_o, V_f, a	$t = (V_f - V_o) \div a$
	V_o, V_f, t	$S = (V_f + V_o)t \div 2$		V_o, V_f, S	$t = 2S \div (V_f + V_o)$
	V_o, V_f, a	$S = (V_f^2 - V_o^2) \div 2a$	a	V_o, V_f, S	$a = (V_f^2 - V_o^2) \div 2S$
	V_f, a, t	$S = V_f t - \frac{1}{2}at^2$		V_o, V_f, t	$a = (V_f - V_o) \div t$
V_f	V_o, a, t	$V_f = V_o + at$		V_o, S, t	$a = 2(S - V_o t) \div t^2$
	V_o, S, t	$V_f = (2S \div t) - V_o$		V_f, S, t	$a = 2(V_f t - S) \div t^2$
	V_o, a, S	$V_f = \sqrt{V_o^2 + 2aS}$	*Meanings of Symbols*		
	S, a, t	$V_f = (S \div t) + \frac{1}{2}at$	S = distance moved in feet V_f = final velocity, feet per second V_o = initial velocity, feet per second a = acceleration, feet per second per second t = time of acceleration in seconds		
V_o	V_f, a, S	$V_o = \sqrt{V_f^2 - 2aS}$			
	V_f, S, t	$V_o = (2S \div t) - V_f$			
	V_f, a, t	$V_o = V_f - at$			
	S, a, t	$V_o = (S \div t) - \frac{1}{2}at$			

Since V_o, V_f, and t are known, a can be determined from the formula

$$a = (V_f - V_o) \div t = (44 - 88) \div 2 = -22 \text{ ft/sec}^2$$

The time required to stop the car can be determined from the formula

$$t = (V_f - V_o) \div a = (0 - 88) \div (-22) = 4 \text{ seconds}$$

The distance traveled by the car is obtained from the formula

$$S = V_o t + \frac{1}{2}at^2 = (88 \times 4) + \left(\frac{1}{2} \times (-22) \times 4^2\right) = (352 - 176) = 176 \text{ feet}$$

Angular Velocity of Rotating Bodies.— The angular velocity of a rotating body is the angle through which the body turns in a unit of time. Angular velocity is commonly expressed in terms of revolutions per minute, but in certain engineering applications it is necessary to express it as radians per second. By definition there are 2π radians in 360 degrees, or one revolution, so that one radian = $360 \div 2\pi = 57.3$ degrees. To convert angular velocity in revolutions per minute, n, to angular velocity in radians per second, ω, multiply by π and divide by 30:

$$\omega = \frac{\pi n}{30} \quad (1)$$

Copyright 2004, Industrial Press, Inc., New York, NY

The following Table 2 may be used to obtain angular velocity in radians per second for all numbers of revolutions per minute from 1 to 239.

Table 2. Angular Velocity in Revolutions per Minute Converted to Radians per Second

	Angular Velocity in Radians per Second									
R.P.M.	0	1	2	3	4	5	6	7	8	9
0	0.00	0.10	0.21	0.31	0.42	0.52	0.63	0.73	0.84	0.94
10	1.05	1.15	1.26	1.36	1.47	1.57	1.67	1.78	1.88	1.99
20	2.09	2.20	2.30	2.41	2.51	2.62	2.72	2.83	2.93	3.04
30	3.14	3.25	3.35	3.46	3.56	3.66	3.77	3.87	3.98	4.08
40	4.19	4.29	4.40	4.50	4.61	4.71	4.82	4.92	5.03	5.13
50	5.24	5.34	5.44	5.55	5.65	5.76	5.86	5.97	6.07	6.18
60	6.28	6.39	6.49	6.60	6.70	6.81	6.91	7.02	7.12	7.23
70	7.33	7.43	7.54	7.64	7.75	7.85	7.96	8.06	8.17	8.27
80	8.38	8.48	8.59	8.69	8.80	8.90	9.01	9.11	9.21	9.32
90	9.42	9.53	9.63	9.74	9.84	9.95	10.05	10.16	10.26	10.37
100	10.47	10.58	10.68	10.79	10.89	11.00	11.10	11.20	11.31	11.41
110	11.52	11.62	11.73	11.83	11.94	12.04	12.15	12.25	12.36	12.46
120	12.57	12.67	12.78	12.88	12.98	13.09	13.19	13.30	13.40	13.51
130	13.61	13.72	13.82	13.93	14.03	14.14	14.24	14.35	14.45	14.56
140	14.66	14.76	14.87	14.97	15.08	15.18	15.29	15.39	15.50	15.60
150	15.71	15.81	15.92	16.02	16.13	16.23	16.34	16.44	16.55	16.65
160	16.75	16.86	16.96	17.07	17.17	17.28	17.38	17.49	17.59	17.70
170	17.80	17.91	18.01	18.12	18.22	18.33	18.43	18.53	18.64	18.74
180	18.85	18.95	19.06	19.16	19.27	19.37	19.48	19.58	19.69	19.79
190	19.90	20.00	20.11	20.21	20.32	20.42	20.52	20.63	20.73	20.84
200	20.94	21.05	21.15	21.26	21.36	21.47	21.57	21.68	21.78	21.89
210	21.99	22.10	22.20	22.30	22.41	22.51	22.62	22.72	22.83	22.93
220	23.04	23.14	23.25	23.35	23.46	23.56	23.67	23.77	23.88	23.98
230	24.09	24.19	24.29	24.40	24.50	24.61	24.71	24.82	24.92	25.03

Example: To find the angular velocity in radians per second of a flywheel making 97 revolutions per minute, locate 90 in the left-hand column and 7 at the top of the columns; at the intersection of the two lines, the angular velocity is read off as equal to 10.16 radians per second.

Linear Velocity of Points on a Rotating Body.— The linear velocity, v, of any point on a rotating body expressed in feet per second may be found by multiplying the angular velocity of the body in radians per second, ω, by the radius, r, in feet from the center of rotation to the point:

$$v = \omega r \tag{2}$$

The metric SI units are v = meters per second; ω = radians per second, r = meters.

Rotary Motion with Constant Acceleration.— The relations among angle of rotation, angular velocity, and time for rotation with constant or uniform acceleration are given in the accompanying Table 3.

In these formulas, the acceleration is assumed to be in the same direction as the initial angular velocity; hence, if the acceleration in a particular problem should happen to be in a direction opposite that of the initial angular velocity, then α should be replaced by $-\alpha$. Thus, for example, the formula $\omega_f = \omega_o + \alpha t$ becomes $\omega_f = \omega_o - \alpha t$ when α and ω_o are opposite in direction.

Linear Acceleration of a Point on a Rotating Body: A point on a body rotating about a fixed axis has a linear acceleration a that is the resultant of two component accelerations. The first component is the centripetal or normal acceleration which is directed from the point P toward the axis of rotation; its magnitude is $r\omega^2$ where r is the radius from the axis to the point P and ω is the angular velocity of the body at the time acceleration a is to be

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Rotary Motion with Constant Acceleration

To Find	Known	Formula	To Find	Known	Formula
Motion Uniformly Accelerated From Rest ($\omega_o = 0$)					
θ	α, t	$\theta = \frac{1}{2}\alpha t^2$	t	θ, ω_f	$t = 2\theta \div \omega_f$
	ω_f, t	$\theta = \frac{1}{2}\omega_f t$		θ, α	$t = \sqrt{2\theta \div \alpha}$
	ω_f, α	$\theta = \omega_f^2 \div 2\alpha$		α, ω_f	$t = \omega_f \div \alpha$
ω_f	α, t	$\omega_f = \alpha t$	α	θ, t	$\alpha = 2\theta \div t^2$
	θ, t	$\omega_f = 2\theta \div t$		θ, ω_f	$\alpha = \omega_f^2 \div 2\theta$
	α, θ	$\omega_f = \sqrt{2\alpha\theta}$		ω_f, t	$\alpha = \omega_f \div t$
Motion Uniformly Accelerated From Initial Velocity ω_o					
θ	α, t, ω_o	$\theta = \omega_o t + \frac{1}{2}\alpha t^2$	α	$\omega_o, \omega_f, \theta$	$\alpha = (\omega_f^2 - \omega_o^2) \div 2\theta$
	ω_o, ω_f, t	$\theta = (\omega_f + \omega_o)t \div 2$		ω_o, ω_f, t	$\alpha = (\omega_f - \omega_o) \div t$
	$\omega_o, \omega_f, \alpha$	$\theta = (\omega_f^2 - \omega_o^2) \div 2\alpha$		$\omega_o, \theta\ t$	$\alpha = 2(\theta - \omega_o t) \div t^2$
	ω_f, α, t	$\theta = \omega_f t - \frac{1}{2}\alpha t^2$		$\omega_f, \theta\ t$	$\alpha = 2(\omega_f t - \theta) \div t^2$
ω_f	ω_o, α, t	$\omega_f = \omega_o + \alpha t$	*Meanings of Symbols*		
	ω_o, θ, t	$\omega_f = (2\theta \div t) - \omega_o$			
	ω_o, α, θ	$\omega_f = \sqrt{\omega_o^2 + 2\alpha\theta}$	θ = angle of rotation, radians		
	θ, α, t	$\omega_f = (\theta \div t) + \frac{1}{2}\alpha t$	ω_f = final angular velocity, radians per second		
ω_o	ω_f, α, θ	$\omega_o = \sqrt{\omega_f^2 - 2\alpha\theta}$	ω_o = initial angular velocity, radians per second		
	ω_f, θ, t	$\omega_o = (2\theta \div t) - \omega_f$	α = angular acceleration, radians per second, per second		
	ω_f, α, t	$\omega_o = \omega_f - \alpha t$	t = time in seconds		
	θ, α, t	$\omega_o = (\theta \div t) - \frac{1}{2}\alpha t$			
t	$\omega_o, \omega_f, \alpha$	$t = (\omega_f - \omega_o) \div \alpha$	1 degree = 0.01745 radians		
	$\omega_o, \omega_f, \theta$	$t = 2\theta \div (\omega_f + \omega_o)$	(See conversion table on page 96)		

determined. The second component of a is the tangential acceleration which is equal to $r\alpha$ where α is the angular acceleration of the body.

The acceleration of point P is the resultant of $r\omega^2$ and $r\alpha$ and is given by the formula

$$a = \sqrt{(r\omega^2)^2 + (r\alpha)^2}$$

When $\alpha = 0$, this formula reduces to: $a = r\omega^2$

Example: A flywheel on a press rotating at 120 rpm is slowed to 102 rpm during a punching operation that requires ¾ second for the punching portion of the cycle. What angular deceleration does the flywheel experience?

From the table on page 169, the angular velocities corresponding to 120 rpm and 102 rpm, respectively, are 12.57 and 10.68 radians per second. Therefore, using the formula

$$\alpha = (\omega_f - \omega_o) \div t$$

$$\alpha = (10.68 - 12.57) \div \tfrac{3}{4} = -1.89 \div \tfrac{3}{4}$$

$$\alpha = -2.52 \text{ radians per second per second}$$

which is, from the table on page 169, – 24 rpm per second. The minus sign in the answer indicates that the acceleration α acts to slow the flywheel, that is, the flywheel is being decelerated.

Copyright 2004, Industrial Press, Inc., New York, NY

Force, Work, Energy, and Momentum

Accelerations Resulting from Unbalanced Forces.— In the section describing the resolution and composition of forces it was stated that when the resultant of a system of forces is zero, the system is in equilibrium, that is, the body on which the force system acts remains at rest or continues to move with uniform velocity. If, however, the resultant of a system of forces is not zero, the body on which the forces act will be accelerated in the direction of the unbalanced force. To determine the relation between the unbalanced force and the resulting acceleration, Newton's laws of motion must be applied. These laws may be stated as follows:

First Law: Every body continues in a state of rest or in uniform motion in a straight line, until it is compelled by a force to change its state of rest or motion.

Second Law: Change of motion is proportional to the force applied, and takes place along the straight line in which the force acts. The "force applied" represents the resultant of *all* the forces acting on the body. This law is sometimes worded: An unbalanced force acting on a body causes an acceleration of the body in the direction of the force and of magnitude proportional to the force and inversely proportional to the mass of the body. Stated as a formula, $R = Ma$ where R is the resultant of *all* the forces acting on the body, M is the mass of the body (mass = weight W divided by acceleration due to gravity g), and a is the acceleration of the body resulting from application of force R.

Third Law: To every action there is always an equal reaction, or, in other words, if a force acts to change the state of motion of a body, the body offers a resistance equal and directly opposite to the force.

Newton's second law may be used to calculate linear and angular accelerations of a body produced by unbalanced forces and torques acting on the body; however, it is necessary first to use the methods described under *Algebraic Composition and Resolution of Force Systems* starting on page 148 to determine the magnitude and direction of the resultant of *all* forces acting on the body. Then, for a body moving with pure translation,

$$R = Ma = \frac{W}{g}a$$

where R is the resultant force in pounds acting on a body weighing W pounds; g is the gravitational constant, usually taken as 32.16 ft/sec^2, approximately; and a is the resulting acceleration in ft/sec^2 of the body due to R and in the same direction as R.

Using metric SI units, the formula is $R = Ma$, where R = force in newtons (N), M = mass in kilograms, and a = acceleration in meters/second squared. It should be noted that the weight of a body of mass M kg is Mg newtons, where g is approximately 9.81 m/s^2.

Free Body Diagram: In order to correctly determine the effect of forces on the motion of a body it is necessary to resort to what is known as a *free body diagram*. This diagram shows 1) the body removed or isolated from contact with all other bodies that exert force on the body and; and 2) *all* the forces acting on the body.

Thus, for example, in Fig. 1a the block being pulled up the plane is acted upon by certain forces; the free body diagram of this block is shown at Fig. 1b. Note that all forces acting on the block are indicated. These forces include: 1) the force of gravity (weight); 2) the pull of the cable, P; 3) the normal component, $W\cos\phi$, of the force exerted on the block by the plane; and 4) the friction force, $\mu W\cos\phi$, of the plane on the block.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1a.



Fig. 1b.

In preparing a free body diagram, it is important to realize that only those forces exerted *on* the body being considered are shown; forces exerted by the body on other bodies are disregarded. This feature makes the free body diagram an invaluable aid in the solution of problems in mechanics.

Example: A 100-pound body is being hoisted by a winch, the tension in the hoisting cable being kept constant at 110 pounds. At what rate is the body accelerated?

Two forces are acting on the body, its weight, 100 pounds downward, and the pull of the cable, 110 pounds upward. The resultant force R, from a free body diagram, is therefore 110 – 100. Thus, applying Newton's second law,

$$110 - 100 = \frac{100}{32.16}a$$

$$a = \frac{32.16 \times 10}{100} = 3.216 \text{ ft/sec}^2 \text{ upward}$$

It should be noted that since in this problem the resultant force R was positive (110 – 100 = + 10), the acceleration a is also positive, that is, a is in the same direction as R, which is in accord with Newton's second law.

Example using SI metric units: **A body of mass 50 kilograms is being hoisted by a winch, and the tension in the cable is 600 newtons. What is the acceleration? The weight of the 50 kg body is 50*g* newtons, where *g* = approximately 9.81 m/s² (see *Note* on page 179). Applying the formula *R* = *Ma*, the calculation is: (600 – 50*g*) = 50*a*. Thus,**

$$a = \frac{600 - 50g}{50} = \frac{600 - (50 \times 9.81)}{50} = 2.19 \text{ m/s}^2$$

Formulas Relating Torque and Angular Acceleration: For a body rotating about a fixed axis the relation between the unbalanced torque acting to produce rotation and the resulting angular acceleration may be determined from any one of the following formulas, each based on Newton's second law:

$$T_o = J_M\alpha$$

$$T_o = Mk_o^2\alpha$$

$$T_o = \frac{Wk_o^2\alpha}{g} = \frac{Wk_o^2\alpha}{32.16}$$

where T_o is the unbalanced torque in pounds-feet; J_M in ft-lbs-sec² is the moment of inertia of the body about the axis of rotation; k_o in feet is the radius of gyration of the body with respect to the axis of rotation, and α in radians per second, per second is the angular acceleration of the body.

Example: A flywheel has a diameter of 3 feet and weighs 1000 pounds. What torque must be applied, neglecting bearing friction, to accelerate the flywheel at the rate of 100 revolutions per minute, per second?

Copyright 2004, Industrial Press, Inc., New York, NY

From page 250 the moment of inertia of a solid cylinder with respect to a gravity axis at right angles to the circular cross-section is given as $\frac{1}{2} Mr^2$. From page 169, 100 rpm = 10.47 radians per second, hence an acceleration of 100 rpm per second = 10.47 radians per second, per second. Therefore, using the first of the preceding formulas,

$$T_o = J_M\alpha = \left(\frac{1}{2}\right)\frac{1000}{32.16}\left(\frac{3}{2}\right)^2 \times 10.47 = 366 \text{ ft-lbs}$$

Using metric SI units, the formulas are: $T_o = J_M\alpha = Mk_o^2\alpha$, where T_o = torque in newton-meters; J_M = the moment of inertia in kg · m², and α = the angular acceleration in radians per second squared.

Example: **A flywheel has a diameter of 1.5 m, and a mass of 800 kg. What torque is needed to produce an angular acceleration of 100 revolutions per minute, per second? As in the preceding example, $\alpha = 10.47$ rad/s². Thus:**

$$J_M = \tfrac{1}{2}Mr^2 = \tfrac{1}{2} \times 800 \times 0.75^2 = 225 \text{ kg} \cdot \text{m}^2$$

Therefore: $T_o = J_M\alpha = 225 \times 10.47 = 2356$ N · m.

Energy.— A body is said to possess energy when it is capable of doing work or overcoming resistance. The energy may be either mechanical or non-mechanical, the latter including chemical, electrical, thermal, and atomic energy.

Mechanical energy includes *kinetic energy* (energy possessed by a body because of its motion) and *potential energy* (energy possessed by a body because of its position in a field of force and/or its elastic deformation).

Kinetic Energy: The motion of a body may be one of pure translation, pure rotation, or a combination of rotation and translation. By translation is meant motion in which every line in the body remains parallel to its original position throughout the motion, that is, no rotation is associated with the motion of the body.

The kinetic energy of a translating body is given by the formula

$$\text{Kinetic Energy in ft-lbs due to translation} = E_{KT} = \tfrac{1}{2}MV^2 = \frac{WV^2}{2g} \tag{3a}$$

where M = mass of body (= $W \div g$); V = velocity of the center of gravity of the body in feet per second; W = weight of body in pounds; and g = acceleration due to gravity = 32.16 feet per second, per second.

The kinetic energy of a body rotating about a fixed axis O is expressed by the formula:

$$\text{Kinetic Energy in ft-lbs due to rotation} = E_{KR} = \tfrac{1}{2}J_{MO}\omega^2 \tag{3b}$$

where J_{MO} is the moment of inertia of the body about the fixed axis O in pounds-feet-seconds², and ω = angular velocity in radians per second.

For a body that is moving with both translation and rotation, the total kinetic energy is given by the following formula as the sum of the kinetic energy due to translation of the center of gravity and the kinetic energy due to rotation about the center of gravity:

$$\begin{aligned}\text{Total Kinetic Energy in ft-lbs} &= E_T = \tfrac{1}{2}MV^2 + \tfrac{1}{2}J_{MG}\omega^2 \\ &= \frac{WV^2}{2g} + \tfrac{1}{2}J_{MG}\omega^2 = \frac{WV^2}{2g} + \tfrac{1}{2}\frac{Wk^2\omega^2}{g} = \frac{W}{2g}(V^2 + k^2\omega^2)\end{aligned} \tag{3c}$$

where J_{MG} is the moment of inertia of the body about its gravity axis in pounds-feet-seconds², k is the radius of gyration in feet with respect to an axis through the center of gravity, and the other quantities are as previously defined.

In the metric SI system, energy is expressed as the joule (J). One joule = 1 newton-meter. The kinetic energy of a translating body is given by the formula $E_{KT} = \frac{1}{2}MV^2$,

Copyright 2004, Industrial Press, Inc., New York, NY

where M = mass in kilograms, and V = velocity in meters per second. Kinetic energy due to rotation is expressed by the formula $E_{KR} = \frac{1}{2}J_{MO}\omega^2$, where J_{MO} = moment of inertia in kg · m², and ω = the angular velocity in radians per second. Total kinetic energy $ET = \frac{1}{2}MV^2 + \frac{1}{2}J_{MO}\omega^2$ joules = $\frac{1}{2}M(V^2 + k^2\omega^2)$ joules, where k = radius of gyration in meters.

Potential Energy: The most common example of a body having potential energy because of its position in a field of force is that of a body elevated to some height above the earth. Here the field of force is the gravitational field of the earth and the potential energy E_{PF} of a body weighing W pounds elevated to some height S in feet above the surface of the earth is WS foot-pounds. If the body is permitted to drop from this height its potential energy E_{PF} will be converted to kinetic energy. Thus, after falling through height S the kinetic energy of the body will be WS ft-lbs.

In metric SI units, the potential energy E_{PF} of a body of mass M kilograms elevated to a height of S meters, is MgS joules. After it has fallen a distance S, the kinetic energy gained will thus be MgS joules.

Another type of potential energy is elastic potential energy, such as possessed by a spring that has been compressed or extended. The amount of work in ft lbs done in compressing the spring S feet is equal to $KS^2/2$, where K is the spring constant in pounds per foot. Thus, when the spring is released to act against some resistance, it can perform $KS^2/2$ ft-lbs of work which is the amount of elastic potential energy E_{PE} stored in the spring.

Using metric SI units, the amount of work done in compressing the spring a distance S meters is $KS^2/2$ joules, where K is the spring constant in newtons per meter.

Work Performed by Forces and Couples.— The work U done by a force F in moving an object along some path is the product of the distance S the body is moved and the component $F \cos \alpha$ of the force F in the direction of S.

$$U = FS\cos\alpha$$

where U = work in ft-lbs; S = distance moved in feet; F = force in lbs; and α = angle between line of action of force and the path of S.

If the force is in the same direction as the motion, then $\cos \alpha = \cos 0 = 1$ and this formula reduces to:

$$U = FS$$

Similarly, the work done by a couple T turning an object through an angle θ is:

$$U = T\theta$$

where T = torque of couple in pounds-feet and θ = the angular rotation in radians.

The above formulas can be used with metric SI units: U is in joules; S is in meters; F is in newtons, and T is in newton-meters.

Relation between Work and Energy.— Theoretically, when work is performed on a body and there are no energy losses (such as due to friction, air resistance, etc.), the energy acquired by the body is equal to the work performed on the body; this energy may be either potential, kinetic, or a combination of both.

In actual situations, however, there may be energy losses that must be taken into account. Thus, the relation between work done on a body, energy losses, and the energy acquired by the body can be stated as:

$$\text{Work Performed} - \text{Losses} = \text{Energy Acquired}$$

$$U - \text{Losses} = E_T$$

Copyright 2004, Industrial Press, Inc., New York, NY

Example 1: A 12-inch cube of steel weighing 490 pounds is being moved on a horizontal conveyor belt at a speed of 6 miles per hour (8.8 feet per second). What is the kinetic energy of the cube?

Since the block is not rotating, Formula (3a) for the kinetic energy of a body moving with pure translation applies:

$$\text{Kinetic Energy} = \frac{WV^2}{2g} = \frac{490 \times (8.8)^2}{2 \times 32.16} = 590 \text{ ft-lbs}$$

A similar example using metric SI units is as follows: If a cube of mass 200 kg is being moved on a conveyor belt at a speed of 3 meters per second, what is the kinetic energy of the cube? It is:

$$\textbf{Kinetic Energy} = \tfrac{1}{2}MV^2 = \tfrac{1}{2} \times 200 \times 3^2 = 900 \text{ joules}$$

Example 2: If the conveyor in Example 1 is brought to an abrupt stop, how long would it take for the steel block to come to a stop and how far along the belt would it slide before stopping if the coefficient of friction μ between the block and the conveyor belt is 0.2 and the block slides without tipping over?

The only force acting to slow the motion of the block is the friction force between the block and the belt. This force F is equal to the weight of the block, W, multiplied by the coefficient of friction; $F = \mu W = 0.2 \times 490 = 98$ lbs.

The time required to bring the block to a stop can be determined from the impulse-momentum Formula (4c) on page 176.

$$R \times t = \frac{W}{g}(V_f - V_o) = (-98)t = \frac{490}{32.16} \times (0 - 8.8)$$

$$t = \frac{490 \times 8.8}{98 \times 32.16} = 1.37 \text{ seconds}$$

The distance the block slides before stopping can be determined by equating the kinetic energy of the block and the work done by friction in stopping it:

$$\text{Kinetic energy of block}\,(WV^2/2g) = \text{Work done by friction}\,(F \times S)$$

$$590 = 98 \times S$$

$$S = \frac{590}{98} = 6.0 \text{ feet}$$

If metric SI units are used, the calculation is as follows (for the cube of 200 kg mass): The friction force = μ multiplied by the weight Mg where g = approximately 9.81 m/s². Thus, $\mu Mg = 0.2 \times 200g = 392.4$ newtons. The time t required to bring the block to a stop is $(-392.4)t = 200(0 - 3)$. Therefore,

$$t = \frac{200 \times 3}{392.4} = 1.53 \text{ seconds}$$

The kinetic energy of the block is equal to the work done by friction, that is $392.4 \times S = 900$ joules. Thus, the distance S which the block moves before stopping is

$$S = \frac{900}{392.4} = 2.29 \text{ meters}$$

Force of a Blow.— A body that weighs W pounds and falls S feet from an initial position of rest is capable of doing WS foot-pounds of work. The work performed during its fall may be, for example, that necessary to drive a pile a distance d into the ground. Neglecting losses in the form of dissipated heat and strain energy, the work done in driving the pile is equal to the product of the impact force acting on the pile and the distance d which the pile is driven. Since the impact force is not accurately known, an average value, called the

Copyright 2004, Industrial Press, Inc., New York, NY

"average force of the blow," may be assumed. Equating the work done on the pile and the work done by the falling body, which in this case is a pile driver:

$$\text{Average force of blow} \times d = WS$$

or,

$$\text{Average force of blow} = \frac{WS}{d}$$

where, S = total height in feet through which the driver falls, including the distance d that the pile is driven

W = weight of driver in pounds

d = distance in feet which pile is driven

When using metric SI units, it should be noted that a body of mass *M* kilograms has a weight of *Mg* newtons, where *g* = approximately 9.81 m/s². If the body falls a distance *S* meters, it can do work equal to *MgS* joules. The average force of the blow is *MgS*/*d* newtons, where *d* is the distance in meters that the pile is driven.

Example: A pile driver weighing 200 pounds strikes the top of the pile after having fallen from a height of 20 feet. It forces the pile into the ground a distance of ½ foot. Before the ram is brought to rest, it will $200 \times (20 + ½) = 4100$ foot-pounds of work, and as this energy is expended in a distance of one-half foot, the average force of the blow equals $4100 \div ½ = 8200$ pounds.

A similar example using metric SI units is as follows: A pile driver of mass 100 kilograms falls 10 meters and moves the pile a distance of 0.3 meters. The work done = 100*g*(10 + 0.3) joules, and it is expended in 0.3 meters. Thus, the average force is

$$\frac{100g \times 10.3}{0.3} = 33680 \text{ newtons or } 33.68 \text{ kN}$$

Impulse and Momentum.— The *linear momentum* of a body is defined as the product of the mass M of the body and the velocity V of the center of gravity of the body:

$$\text{Linear momentum} = MV \text{ or since } M = W \div g$$

$$\text{Linear momentum} = \frac{WV}{g} \tag{4a}$$

It should be noted that linear momentum is a vector quantity, the momentum being in the same direction as V.

Linear impulse is defined as the product of the resultant R of *all* the forces acting on a body and the time t that the resultant acts:

$$\text{Linear Impulse} = Rt \tag{4b}$$

The change in the linear momentum of a body is numerically equal to the linear impulse that causes the change in momentum:

$$\text{Linear Impulse} = \text{change in Linear Momentum}$$

$$Rt = \frac{W}{g}V_f - \frac{W}{g}V_o = \frac{W}{g}(V_f - V_o) \tag{4c}$$

where V_f, the final velocity of the body after time t, and V_o, the initial velocity of the body, are both in the same direction as the applied force R. If V_o, and V_f are in opposite directions, then the minus sign in the formula becomes a plus sign.

In metric SI units, the formulas are: Linear Momentum = *MV* kg · m/s, where *M* = mass in kg, and *V* = velocity in meters per second; and Linear Impulse = *Rt* newton-seconds, where *R* = force in newtons, and *t* = time in seconds. In Formula (4c) above, *W*/*g* is replaced by *M* when SI units are used.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: A 1000-pound block is pulled up a 2-degree incline by a cable exerting a constant force F of 600 pounds. If the coefficient of friction μ between the block and the plane is 0.5, how fast will the block be moving up the plane 10 seconds after the pull is applied?

The resultant force R causing the body to be accelerated up the plane is the difference between F, the force acting up the plane, and P, the force acting to resist motion up the plane. This latter force for a body on a plane is given by the formula at the top of page 161 as $P = W(\mu \cos\alpha + \sin\alpha)$ where α is the angle of the incline.

Thus, $$R = F - P = F - W(\mu\cos\alpha + \sin\alpha)$$
$$= 600 - 1000(0.5\cos 2^\circ + \sin 2^\circ) = 600 - 1000(0.5 \times 0.99939 + 0.03490)$$
$$R = 600 - 535 = 65 \text{ pounds.}$$

Formula (4c) can now be applied to determine the speed at which the body will be moving up the plane after 10 seconds.

$$Rt = \frac{W}{g}V_f - \frac{W}{g}V_o$$
$$65 \times 10 = \frac{1000}{32.2}V_f - \frac{1000}{32.2} \times 0$$
$$V_f = \frac{65 \times 10 \times 32.2}{1000} = 20.9 \text{ ft per sec} = 14.3 \text{ miles per hour}$$

A similar example using metric SI units is as follows: A 500 kg block is pulled up a 2 degree incline by a constant force F of 4 kN. The coefficient of friction μ between the block and the plane is 0.5. How fast will the block be moving 10 seconds after the pull is applied?

The resultant force R is:

$$R = F - Mg(\mu\cos\alpha + \sin\alpha)$$
$$= 4000 - 500 \times 9.81(0.5 \times 0.99939 + 0.03490) = 1378\text{N or } 1.378\text{ kN}$$

Formula (4c) can now be applied to determine the speed at which the body will be moving up the plane after 10 seconds. Replacing W/g by M in the formula, the calculation is:

$$Rt = MV_f - MV_o$$
$$1378 \times 10 = 500(V_f - 0)$$
$$V_f = \frac{1378 \times 10}{500} = 27.6 \text{ m/s}$$

Angular Impulse and Momentum: In a manner similar to that for linear impulse and moment, the formulas for angular impulse and momentum for a body rotating about a fixed axis are:

$$\text{Angular momentum} = J_M\omega \tag{5a}$$

$$\text{Angular impulse} = T_o t \tag{5b}$$

where J_M is the moment of inertia of the body about the axis of rotation in pounds-feet-seconds^2, ω is the angular velocity in radians per second, T_o, is the torque in pounds-feet about the axis of rotation, and t is the time in seconds that T_o, acts.

The change in angular momentum of a body is numerically equal to the angular impulse that causes the change in angular momentum:

$$\text{Angular Impulse} = \text{Change in Angular Momentum}$$
$$T_o t = J_M\omega_f - J_M\omega_o = J_M(\omega_f - \omega_o) \tag{5c}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where ω_f and ω_o are the final and initial angular velocities, respectively.

Example: A flywheel having a moment of inertia of 25 lbs-ft-sec^2 is revolving with an angular velocity of 10 radians per second when a constant torque of 20 lbs-ft is applied to reverse its direction of rotation. For what length of time must this constant torque act to stop the flywheel and bring it up to a reverse speed of 5 radians per second?

Applying Formula (5c),

$$T_o t = J_M(\omega_f - \omega_o)$$
$$20t = 25(10 - [-5]) = 250 + 125$$
$$t = 375 \div 20 = 18.8 \text{ seconds}$$

A similar example using metric SI units is as follows: A flywheel with a moment of inertia of 20 kilogram-meters^2 is revolving with an angular velocity of 10 radians per second when a constant torque of 30 newton-meters is applied to reverse its direction of rotation. For what length of time must this constant torque act to stop the flywheel and bring it up to a reverse speed of 5 radians per second? Applying Formula (5c), the calculation is:

$$\boldsymbol{T_o t = J_M(\omega_f - \omega_o),}$$
$$\boldsymbol{30t = 20(10 - [-5]).}$$
$$\textbf{Thus, } \boldsymbol{t = \frac{20 \times 15}{30} = 10} \textbf{ seconds}$$

Formulas for Work and Power.— The formulas in the accompanying Table 4 may be used to determine work and power in terms of the applied force and the velocity at the point of application of the force.

Table 4. Formulas[a] for Work and Power

To Find	Known	Formula
S	*P*, *t*, *F*	$S = P \times t \div F$
	K, *F*	$S = K \div F$
	t, *F*, *hp*	$S = 550 \times t \times hp \div F$
V	*P*, *F*	$V = P \div F$
	K, *F*, *t*	$V = K \div (F \times t)$
	F, *hp*	$V = 550 \times hp \div F$
t	*F*, *S*, *P*	$t = F \times S \div P$
	K, *F*, *V*	$t = K \div (F \times V)$
	F, *S*, *hp*	$t = F \times S \div (550 \times hp)$
F	*P*, *V*	$F = P \div V$
	K, *S*	$F = K \div S$
	K, *V*, *t*	$F = K \div (V \times t)$
	V, *hp*	$F = 550 \times hp \div V$
P	*F*, *V*	$P = F \times V$
	F, *S*, *t*	$P = F \times S \div t$
	K, *t*	$P = K \div t$
	hp	$P = 550 \times hp$

To Find	Known	Formula
K	*F*, *S*	$K = F \times S$
	P, *t*	$K = P \times t$
	F, *V*, *t*	$K = F \times V \times t$
	t, *hp*	$K = 550 \times t \times hp$
hp	*F*, *S*, *t*	$hp = F \times S \div (550 \times t)$
	P	$hp = P \div 550$
	F, *V*	$hp = F \times V \div 550$
	K, *t*	$hp = K \div (550 \times t)$

Meanings of Symbols:

S = distance in feet
V = constant or average velocity in feet per second
t = time in seconds
F = constant or average force in pounds
P = power in foot-pounds per second
hp = horsepower

Copyright 2004, Industrial Press, Inc., New York, NY

[a] ***Note:*** **The metric SI unit of work is the joule (one joule = 1 newton-meter), and the unit of power is the watt (one watt = 1 joule per second = 1 N · m/s). The term horsepower is not used. Thus, those formulas above that involve horsepower and the factor 550 are not applicable when working in SI units. The remaining formulas can be used, and the units are: S = distance in meters; V = constant or average velocity in meters per second; t = time in seconds; F = force in newtons; P = power in watts; K = work in joules.**

Example: A casting weighing 300 pounds is to be lifted by means of an overhead crane. The casting is lifted 10 feet in 12 seconds. What is the horsepower developed? Here $F = 300$; $S = 10$; $t = 12$.

$$\text{hp} = \frac{F \times S}{550t} = \frac{300 \times 10}{550 \times 12} = 0.45$$

A similar example using metric SI units is as follows: A casting of mass 150 kg is lifted 4 meters in 15 seconds by means of a crane. What is the power? Here $F = 150g$ N, $S = 4$ m, and $t = 15$ s. Thus:

$$\textbf{Power} = \frac{FS}{t} = \frac{150g \times 4}{15} = \frac{150 \times 9.81 \times 4}{15} = \textbf{392 watts or 0.392 kW}$$

Centrifugal Force

Centrifugal Force.— When a body rotates about any axis other than one at its center of mass, it exerts an outward radial force called centrifugal force upon the axis or any arm or cord from the axis that restrains it from moving in a straight (tangential) line. In the following formulas:

F = centrifugal force in pounds
W = weight of revolving body in pounds
v = velocity at radius R on body in feet per second
n = number of revolutions per minute
g = acceleration due to gravity = 32.16 feet per second per second
R = perpendicular distance in feet from axis of rotation to center of mass, or for practical use, to center of gravity of revolving body

Note: If a body rotates about its own center of mass, R equals zero and v equals zero. This means that the *resultant* of the centrifugal forces of all the elements of the body is equal to zero or, in other words, no centrifugal force is exerted on the axis of rotation. The centrifugal force of any part or element of such a body is found by the equations given below, where R is the radius to the center of gravity of the part or element. In a flywheel rim, R is the mean radius of the rim because it is the radius to the center of gravity of a thin radial section.

$$F = \frac{Wv^2}{gR} = \frac{Wv^2}{32.16R} = \frac{4WR\pi^2n^2}{60 \times 60g} = \frac{WRn^2}{2933} = 0.000341WRn^2$$

$$W = \frac{FRg}{v^2} = \frac{2933F}{Rn^2} \qquad v = \sqrt{\frac{FRg}{W}}$$

$$R = \frac{Wv^2}{Fg} = \frac{2933F}{Wn^2} \qquad n = \sqrt{\frac{2933F}{WR}}$$

(If n is the number of revolutions per second instead of per minute, then $F = 1227WRn^2$.)

If metric SI units are used in the foregoing formulas, W/g is replaced by M, which is the mass in kilograms; F = centrifugal force in newtons; v = velocity in meters per second; n = number of revolutions per minute; and R = the radius in meters. Thus:

Copyright 2004, Industrial Press, Inc., New York, NY

$$F = Mv^2/R = \frac{Mn^2(2\pi R^2)}{60^2 R} = 0.01097\ MRn^2$$

If the rate of rotation is expressed as n_1 = revolutions per second, then $F = 39.48\ MRn_1^2$; if it is expressed as ω radians per second, then $F = MR\omega^2$.

Calculating Centrifugal Force.— In the ordinary formula for centrifugal force, $F = 0.000341\ WRn^2$; the mean radius R of the flywheel or pulley rim is given in feet. For small dimensions, it is more convenient to have the formula in the form:

$$F = 0.2842 \times 10^{-4} Wrn^2$$

in which F = centrifugal force, in pounds; W = weight of rim, in pounds; r = mean radius of rim, in inches; n = number of revolutions per minute.

In this formula let $C = 0.000028416n^2$. This, then, is the centrifugal force of one pound, one inch from the axis. The formula can now be written in the form,

$$F = WrC$$

C is calculated for various values of the revolutions per minute n, and the calculated values of C are given in Table 5. To find the centrifugal force in any given case, simply find the value of C in the table and multiply it by the product of W and r, the four multiplications in the original formula given thus having been reduced to two.

Example: A cast-iron flywheel with a mean rim radius of 9 inches, is rotated at a speed of 800 revolutions per minute. If the weight of the rim is 20 pounds, what is the centrifugal force?

From Table 5, for $n = 800$ revolutions per minute, the value of C is 18.1862.

Thus,

$$F = WrC = 20 \times 9 \times 18.1862 = 3273.52 \text{ pounds}$$

Using metric SI units, $0.01097n^2$ is the centrifugal force acting on a body of 1 kilogram mass rotating at n revolutions per minute at a distance of 1 meter from the axis. If this value is designated C_1, then the centrifugal force of mass M kilograms rotating at this speed at a distance from the axis of R meters, is C_1MR newtons. To simplify calculations, values for C_1 are given in Table 6. If it is required to work in terms of millimeters, the force is $0.001\ C_1MR_1$ newtons, where R_1 is the radius in millimeters.

***Example:* A steel pulley with a mean rim radius of 120 millimeters is rotated at a speed of 1100 revolutions per minute. If the mass of the rim is 5 kilograms, what is the centrifugal force?**

From Table 6, for $n = 1100$ revolutions per minute, the value of C_1 is 13,269.1.

Thus,

$$F = 0.001\ C_1MR_1 = 0.001 \times 13{,}269.1 \times 5 \times 120 = 7961.50 \text{ newtons}$$

Centrifugal Casting.— The centrifugal casting of metals is an old art. This process has become important in such work as the manufacture of paper-mill rolls, railroad car wheels, and cast-iron pipe. The centrifugal casting process has been successfully applied in the production of non-metallic tubes, such as concrete pipe, in the production of solid castings by locating the molds around the rim of a spinning wheel, and to a limited extent in the production of solid ingots by a largely similar process. Hollow objects such as cast-iron pipe are cast by introducing molten metal into a spinning mold. If the chilling of the metal is extremely rapid, for example in casting cast-iron pipe against a water-cooled chilled mold, it is imperative to use a movable spout. The particular feature that determines the field of application of hot-mold centrifugal casting is the ability to produce long cast shapes of comparatively thin metal.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Factors *C* for Calculating Centrifugal Force (English units)

n	*C*	*n*	*C*	*n*	*C*	*n*	*C*
50	0.07104	100	0.28416	470	6.2770	5200	768.369
51	0.07391	101	0.28987	480	6.5470	5300	798.205
52	0.07684	102	0.29564	490	6.8227	5400	828.611
53	0.07982	103	0.30147	500	7.1040	5500	859.584
54	0.08286	104	0.30735	600	10.2298	5600	891.126
55	0.08596	105	0.31328	700	13.9238	5700	923.236
56	0.08911	106	0.31928	800	18.1862	5800	955.914
57	0.09232	107	0.32533	900	23.0170	5900	989.161
58	0.09559	108	0.33144	1000	28.4160	6000	1022.980
59	0.09892	109	0.33761	1100	34.3834	6100	1057.360
60	0.10230	110	0.34383	1200	40.9190	6200	1092.310
61	0.10573	115	0.37580	1300	48.0230	6300	1127.830
62	0.10923	120	0.40921	1400	55.6954	6400	1163.920
63	0.11278	125	0.44400	1500	63.9360	6500	1200.580
64	0.11639	130	0.48023	1600	72.7450	6600	1237.800
65	0.12006	135	0.51788	1700	82.1222	6700	1275.590
66	0.12378	140	0.55695	1800	92.0678	6800	1313.960
67	0.12756	145	0.59744	1900	102.5820	6900	1352.890
68	0.13140	150	0.63936	2000	113.6640	7000	1392.380
69	0.13529	160	0.72745	2100	125.3150	7100	1432.450
70	0.13924	170	0.82122	2200	137.5330	7200	1473.090
71	0.14325	180	0.92067	2300	150.3210	7300	1514.290
72	0.14731	190	1.02590	2400	163.6760	7400	1556.060
73	0.15143	200	1.1367	2500	177.6000	7500	1598.400
74	0.15561	210	1.2531	2600	192.0920	7600	1641.310
75	0.15984	220	1.3753	2700	207.1530	7700	1684.780
76	0.16413	230	1.5032	2800	222.7810	7800	1728.830
77	0.16848	240	1.6358	2900	238.9790	7900	1773.440
78	0.17288	250	1.7760	3000	255.7400	8000	1818.620
79	0.17734	260	1.9209	3100	273.0780	8100	1864.370
80	0.18186	270	2.0715	3200	290.9800	8200	1910.690
81	0.18644	280	2.2278	3300	309.4500	8300	1957.580
82	0.19107	290	2.3898	3400	328.4890	8400	2005.030
83	0.19576	300	2.5574	3500	348.0960	8500	2053.060
84	0.20050	310	2.7308	3600	368.2710	8600	2101.650
85	0.20530	320	2.9098	3700	389.0150	8700	2150.810
86	0.21016	330	3.0945	3800	410.3270	8800	2200.540
87	0.21508	340	3.2849	3900	432.2070	8900	2250.830
88	0.22005	350	3.4809	4000	454.6560	9000	2301.700
89	0.22508	360	3.6823	4100	477.6730	9100	2353.130
90	0.23017	370	3.8901	4200	501.2580	9200	2405.130
91	0.23531	380	4.1032	4300	525.4120	9300	2457.700
92	0.24051	390	4.3220	4400	550.1340	9400	2510.840
93	0.24577	400	4.5466	4500	575.4240	9500	2564.540
94	0.25108	410	4.7767	4600	601.2830	9600	2618.820
95	0.25645	420	5.0126	4700	627.7090	9700	2673.660
96	0.26188	430	5.2541	4800	654.7050	9800	2729.070
97	0.26737	440	5.5013	4900	682.2680	9900	2785.050
98	0.27291	450	5.7542	5000	710.4000	10000	2841.600
99	0.27851	460	6.0128	5100	739.1000	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Factors C_1 for Calculating Centrifugal Force (Metric SI units)

n	C_1	n	C_1	n	C_1	n	C_1
50	27.4156	100	109.662	470	2,422.44	5200	296,527
51	28.5232	101	111.867	480	2,526.62	5300	308,041
52	29.6527	102	114.093	490	2,632.99	5400	319,775
53	30.8041	103	116.341	500	2,741.56	5500	331,728
54	31.9775	104	118.611	600	3,947.84	5600	343,901
55	33.1728	105	120.903	700	5,373.45	5700	356,293
56	34.3901	106	123.217	800	7,018.39	5800	368,904
57	35.6293	107	125.552	900	8,882.64	5900	381,734
58	36.8904	108	127.910	1000	10,966.2	6000	394,784
59	38.1734	109	130.290	1100	13,269.1	6100	408,053
60	39.4784	110	132.691	1200	15,791.4	6200	421,542
61	40.8053	115	145.028	1300	18,532.9	6300	435,250
62	42.1542	120	157.914	1400	21,493.8	6400	449,177
63	43.5250	125	171.347	1500	24,674.0	6500	463,323
64	44.9177	130	185.329	1600	28,073.5	6600	477,689
65	46.3323	135	199.860	1700	31,692.4	6700	492,274
66	47.7689	140	214.938	1800	35,530.6	6800	507,078
67	49.2274	145	230.565	1900	39,588.1	6900	522,102
68	50.7078	150	246.740	2000	43,864.9	7000	537,345
69	52.2102	160	280.735	2100	48,361.1	7100	552,808
70	53.7345	170	316.924	2200	53,076.5	7200	568,489
71	55.2808	180	355.306	2300	58,011.3	7300	584,390
72	56.8489	190	395.881	2400	63,165.5	7400	600,511
73	58.4390	200	438.649	2500	68,538.9	7500	616,850
74	60.0511	210	483.611	2600	74,131.7	7600	633,409
75	61.6850	220	530.765	2700	79,943.8	7700	650,188
76	63.3409	230	580.113	2800	85,975.2	7800	667,185
77	65.0188	240	631.655	2900	92,226.0	7900	684,402
78	66.7185	250	685.389	3000	98,696.0	8000	701,839
79	68.4402	260	741.317	3100	105,385	8100	719,494
80	70.1839	270	799.438	3200	112,294	8200	737,369
81	71.9494	280	859.752	3300	119,422	8300	755,463
82	73.7369	290	922.260	3400	126,770	8400	773,777
83	75.5463	300	986.960	3500	134,336	8500	792,310
84	77.3777	310	1,053.85	3600	142,122	8600	811,062
85	79.2310	320	1,122.94	3700	150,128	8700	830,034
86	81.1062	330	1,194.22	3800	158,352	8800	849,225
87	83.0034	340	1,267.70	3900	166,796	8900	868,635
88	84.9225	350	1,343.36	4000	175,460	9000	888,264
89	86.8635	360	1,421.22	4100	184,342	9100	908,113
90	88.8264	370	1,501.28	4200	193,444	9200	928,182
91	90.8113	380	1,583.52	4300	202,766	9300	948,469
92	92.8182	390	1,667.96	4400	212,306	9400	968,976
93	94.8469	400	1,754.60	4500	222,066	9500	989,702
94	96.8976	410	1,843.42	4600	232,045	9600	1,010,650
95	98.9702	420	1,934.44	4700	242,244	9700	1,031,810
96	101.065	430	2,027.66	4800	252,662	9800	1,053,200
97	103.181	440	2,123.06	4900	263,299	9900	1,074,800
98	105.320	450	2,220.66	5000	274,156	10000	1,096,620
99	107.480	460	2,320.45	5100	285,232	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

FLYWHEELS

Classification of Flywheels

Flywheels may be classified as *balance wheels* or as *flywheel pulleys*. The object of all flywheels is to equalize the energy exerted and the work done and thereby prevent excessive or sudden changes of speed. The permissible speed variation is an important factor in all flywheel designs. The allowable speed change varies considerably for different classes of machinery; for instance, it is about 1 or 2 per cent in steam engines, while in punching and shearing machinery a speed variation of 20 per cent may be allowed.

The function of a balance wheel is to absorb and equalize energy in case the resistance to motion, or driving power, varies throughout the cycle. Therefore, the rim section is generally quite heavy and is designed with reference to the energy that must be stored in it to prevent excessive speed variations and, with reference to the strength necessary to withstand safely the stresses resulting from the required speed. The rims of most balance wheels are either square or nearly square in section, but flywheel pulleys are commonly made wide to accommodate a belt and relatively thin in a radial direction, although this is not an invariable rule.

Flywheels, in general, may either be formed of a solid or one-piece section, or they may be of sectional construction. Flywheels in diameters up to about eight feet are usually cast solid, the hubs sometimes being divided to relieve cooling stresses. Flywheels ranging from, say, eight feet to fifteen feet in diameter, are commonly cast in half sections, and the larger sizes in several sections, the number of which may equal the number of arms in the wheel. Sectional flywheels may be divided into two general classes. One class includes cast wheels which are formed of sections principally because a solid casting would be too large to transport readily. The second class includes wheels of sectional construction which, by reason of the materials used and the special arrangement of the sections, enables much higher peripheral speeds to be obtained safely than would be possible with ordinary sectional wheels of the type not designed especially for high speeds. Various designs have been built to withstand the extreme stresses encountered in some classes of service. The rims in some designs are laminated, being partly or entirely formed of numerous segment-shaped steel plates. Another type of flywheel, which is superior to an ordinary sectional wheel, has a solid cast-iron rim connected to the hub by disk-shaped steel plates instead of cast spokes.

Steel wheels may be divided into three distinct types, including 1) those having the center and rim built up entirely of steel plates; 2) those having a cast-iron center and steel rim; and 3) those having a cast-steel center and rim formed of steel plates.

Wheels having wire-wound rims have been used to a limited extent when extremely high speeds have been necessary.

When the rim is formed of sections held together by joints it is very important to design these joints properly. The ordinary bolted and flanged rim joints located between the arms average about 20 per cent of the strength of a solid rim and about 25 per cent is the maximum strength obtainable for a joint of this kind. However, by placing the joints at the ends of the arms instead of between them, an efficiency of 50 per cent of the strength of the rim may be obtained, because the joint is not subjected to the outward bending stresses between the arms but is directly supported by the arm, the end of which is secured to the rim just beneath the joint. When the rim sections of heavy balance wheels are held together by steel links shrunk into place, an efficiency of 60 per cent may be obtained; and by using a rim of box or I-section, a link type of joint connection may have an efficiency of 100 percent.

Copyright 2004, Industrial Press, Inc., New York, NY

Flywheel Calculations

Energy Due to Changes of Velocity.— When a flywheel absorbs energy from a variable driving force, as in a steam engine, the velocity increases; and when this stored energy is given out, the velocity diminishes. When the driven member of a machine encounters a variable resistance in performing its work, as when the punch of a punching machine is passing through a steel plate, the flywheel gives up energy while the punch is at work, and, consequently, the speed of the flywheel is reduced. The total energy that a flywheel would give out if brought to a standstill is given by the formula:

$$E = \frac{Wv^2}{2g} = \frac{Wv^2}{64.32}$$

in which E = total energy of flywheel, in foot-pounds
W = weight of flywheel rim, in pounds
v = velocity at mean radius of flywheel rim, in feet per second
g = acceleration due to gravity = 32.16 ft/s^2

If the velocity of a flywheel changes, the energy it will absorb or give up is proportional to the difference between the squares of its initial and final speeds, and is equal to the difference between the energy that it would give out if brought to a full stop and the energy that is still stored in it at the reduced velocity. Hence:

$$E_1 = \frac{Wv_1{}^2}{2g} - \frac{Wv_2{}^2}{2g} = \frac{W(v_1^2 - v_2^2)}{64.32}$$

in which E_1 = energy in foot-pounds that a flywheel will give out while the speed is reduced from v_1 to v_2
W = weight of flywheel rim, in pounds
v_1 = velocity at mean radius of flywheel rim before any energy has been given out, in feet per second
v_2 = velocity of flywheel rim at end of period during which the energy has been given out, in feet per second

Ordinarily, the effects of the arms and hub do not enter into flywheel calculations, and only the weight of the rim is considered. In computing the velocity, the mean radius of the rim is commonly used.

Using metric SI units, the formulas are $E = \frac{1}{2}Mv^2$, and $E_1 = \frac{1}{2}M(v_1{}^2 - v_2{}^2)$, where E and E_1 are in joules; M = the mass of the rim in kilograms; and v, v_1, and v_2 = velocities in meters per second. Note: In the SI, the unit of mass is the kilogram. If the weight of the flywheel rim is given in kilograms, the value referred to is the mass, M. Should the weight be given in newtons, N, then

$$M = \frac{W(\text{newtons})}{g}$$

where g is approximately 9.81 meters per second squared.

General Procedure in Flywheel Design.— The general method of designing a flywheel is to determine first the value of E_1 or the energy the flywheel must either supply or absorb for a given change in velocity, which, in turn, varies for different classes of service. The mean diameter of the flywheel may be assumed, or it may be fixed within certain limits by the general design of the machine. Ordinarily the speed of the flywheel shaft is known, at least approximately; the values of v_1 and v_2 can then be determined, the latter depending upon the allowable percentage of speed variation. When these values are known, the weight of the rim and the cross-sectional area required to obtain this weight may be computed. The general procedure will be illustrated more in detail by considering the design of flywheels for punching and shearing machinery.

Copyright 2004, Industrial Press, Inc., New York, NY

Flywheels for Presses, Punches, Shears, Etc.— In these classes of machinery, the work that the machine performs is of an intermittent nature and is done during a small part of the time required for the driving shaft of the machine to make a complete revolution. To distribute the work of the machine over the entire period of revolution of the driving shaft, a heavy-rimmed flywheel is placed on the shaft, giving the belt an opportunity to perform an almost uniform amount of work during the whole revolution. During the greater part of the revolution of the driving shaft, the belt power is used to accelerate the speed of the flywheel. During the part of the revolution when the work is done, the energy thus stored up in the flywheel is given out at the expense of its velocity. The problem is to determine the weight and cross-sectional area of the rim when the conditions affecting the design of the flywheel are known.

Example: A flywheel is required for a punching machine capable of punching ¾-inch holes through structural steel plates ¾ inch thick. This machine (see accompanying diagram) is of the general type having a belt-driven shaft at the rear which carries a flywheel and a pinion that meshes with a large gear on the main shaft at the top of the machine. It is assumed that the relative speeds of the pinion and large gear are 7 to 1, respectively, and that the slide is to make 30 working strokes per minute. The preliminary layout shows that the flywheel should have a mean diameter (see enlarged detail) of about 30 inches. Find the weight of the flywheel and the remaining rim dimensions.



Punch Press and Flywheel Detail

Energy Supplied by Flywheel: The energy that the flywheel must give up for a given change in velocity, and the weight of rim necessary to supply that energy, must be determined. The maximum force for shearing a ¾-inch hole through ¾-inch structural steel equals approximately the circumference of the hole multiplied by the thickness of the stock multiplied by the tensile strength, which is nearly the same as the shearing resistance of the steel. Thus, in this case, $3.1416 \times \frac{3}{4} \times \frac{3}{4} \times 60{,}000 = 106{,}000$ pounds. The average force will be much less than the maximum. Some designers assume that the average force is about one-half the maximum, although experiments show that the material is practically sheared off when the punch has entered the sheet a distance equal to about one-third the sheet thickness. On this latter basis, the average energy E_a is 2200 foot-pounds for the example given. Thus:

$$E_a = \frac{106{,}000 \times \frac{1}{3} \times \frac{3}{4}}{12} = \frac{106{,}000}{4 \times 12} = 2200 \text{ foot-pounds.}$$

If the efficiency of the machine is taken as 85 per cent, the energy required will equal 2200/0.85 = 2600 foot-pounds nearly. Assume that the energy supplied by the belt while the punch is at work is determined by calculation to equal 175 foot-pounds. Then the flywheel must supply 2600 −175 = 2425 foot-pounds = E_1.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions of Flywheels for Punches and Shears



A	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*J*	Max. R.P.M.
24	3	3½	6	1¼	1⅜	2¾	3¼	3½	955
30	3½	4	7	1⅜	1½	3	3¾	4	796
36	4	4½	8	1½	1¾	3¼	4¼	4½	637
42	4¼	4¾	9	1¾	2	3½	4½	5	557
48	4½	5	10	1¾	2	3¾	4¾	5½	478
54	4¾	5½	11	2	2¼	4	5	6	430
60	5	6	12	2¼	2½	4½	5½	6½	382
72	5½	7	13	2½	2¾	5	6½	7	318
84	6	8	14	3	3½	5½	7½	8	273
96	7	9	15	3½	4	6	9	9	239
108	8	10	16½	3¾	4½	6½	10½	10	212
120	9	11	18	4	5	7½	12	12	191

The maximum number of revolutions per minute given in this table should never be exceeded for cast-iron flywheels.

Rim Velocity at Mean Radius: When the mean radius of the flywheel is known, the velocity of the rim at the mean radius, in feet per second, is:

$$v = \frac{2 \times 3.1416 \times R \times n}{60}$$

in which v = velocity at mean radius of flywheel, in feet per second

R = mean radius of flywheel rim, in feet

n = number of revolutions per minute

According to the preliminary layout the mean diameter in this example should be about 30 inches and the driving shaft is to make 210 rpm, hence,

$$v = \frac{2 \times 3.1416 \times 1.25 \times 210}{60} = 27.5 \text{ feet per second}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Weight of Flywheel Rim: Assuming that the allowable variation in velocity when punching is about 15 per cent, and values of v_1 and v_2 are respectively 27.5 and 23.4 feet per second ($27.5 \times 0.85 = 23.4$), the weight of a flywheel rim necessary to supply a given amount of energy in foot-pounds while the speed is reduced from v_1 to v_2 would be:

$$W = \frac{E_1 \times 64.32}{v_1^2 - v_2^2} = \frac{2425 \times 64.32}{27.5^2 - 23.4^2} = 750 \text{ pounds}$$

Size of Rim for Given Weight: Since 1 cubic inch of cast iron weighs 0.26 pound, a flywheel rim weighing 750 pounds contains 750/0.26 = 2884 cubic inches. The cross-sectional area of the rim in square inches equals the total number of cubic inches divided by the mean circumference, or 2884/94.25 = 31 square inches nearly, which is approximately the area of a rim 5⅛ inches wide and 6 inches deep.

Simplified Flywheel Calculations.— Calculations for designing the flywheels of punches and shears are simplified by the following formulas and the accompanying table of constants applying to different percentages of speed reduction. In these formulas let:

HP = horsepower required
N = number of strokes per minute
E = total energy required per stroke, in foot-pounds
E_1 = energy given up by flywheel, in foot-pounds
T = time in seconds per stroke
T_1 = time in seconds of actual cut
W = weight of flywheel rim, in pounds
D = mean diameter of flywheel rim, in feet
R = maximum allowable speed of flywheel in revolutions per minute
C and C_1 = speed reduction values as given in table
a = width of flywheel rim
b = depth of flywheel rim
y = ratio of depth to width of rim

$$HP = \frac{EN}{33,000} = \frac{E}{T \times 550} \qquad E_1 = E\left(1 - \frac{T_1}{T}\right)$$

$$W = \frac{E_1}{CD^2R^2} \qquad a = \sqrt{\frac{1.22W}{12Dy}} \qquad b = ay$$

For cast-iron flywheels, with a maximum stress of 1000 pounds per square inch:

$$W = C_1E_1 \qquad R = 1940 \div D$$

Values of C and C_1 in the Previous Formulas

Per Cent Reduction	C	C_1	Per Cent Reduction	C	C_1
2½	0.00000213	0.1250	10	0.00000810	0.0328
5	0.00000426	0.0625	15	0.00001180	0.0225
7½	0.00000617	0.0432	20	0.00001535	0.0173

Example 1: A hot slab shear is required to cut a slab 4 × 15 inches which, at a shearing stress of 6000 pounds per square inch, gives a force between the knives of 360,000 pounds. The total energy required for the cut will then be $360{,}000 \times {}^4/_{12} = 120{,}000$ foot-pounds. The shear is to make 20 strokes per minute; the actual cutting time is 0.75 second, and the balance of the stroke is 2.25 seconds.

Copyright 2004, Industrial Press, Inc., New York, NY

The flywheel is to have a mean diameter of 6 feet 6 inches and is to run at a speed of 200 rpm; the reduction in speed to be 10 per cent per stroke when cutting.

$$HP = \frac{120,000 \times 20}{33,000} = 72.7 \text{ horsepower}$$

$$E_1 = 120,000 \times \left(1 - \frac{0.75}{3}\right) = 90,000 \text{ foot-pounds}$$

$$W = \frac{90,000}{0.0000081 \times 6.5^2 \times 200^2} = 6570 \text{ pounds}$$

Assuming a ratio of 1.22 between depth and width of rim,

$$a = \sqrt{\frac{6570}{12 \times 6.5}} = 9.18 \text{ inches}$$

$$b = 1.22 \times 9.18 = 11.2 \text{ inches}$$

or size of rim, say, $9 \times 11\frac{1}{2}$ inches.

Example 2: Suppose that the flywheel in Example 1 is to be made with a stress due to centrifugal force of 1000 pounds per square inch of rim section.

$$C_1 \text{ for 10 per cent} = 0.0328$$

$$W = 0.0328 \times 90,000 = 2950 \text{ pounds}$$

$$R = \frac{1940}{D} \qquad \text{If } D = 6 \text{ feet,} \qquad R = \frac{1940}{6} = 323 \text{ rpm}$$

Assuming a ratio of 1.22 between depth and width of rim, as before:

$$a = \sqrt{\frac{2950}{12 \times 6}} = 6.4 \text{ inches}$$

$$b = 1.22 \times 6.4 = 7.8 \text{ inches}$$

or size of rim, say, $6\frac{1}{4} \times 8$ inches.

Centrifugal Stresses in Flywheel Rims.— In general, high speed is desirable for flywheels in order to avoid using wheels that are unnecessarily large and heavy. The centrifugal tension or hoop tension stress, that tends to rupture a flywheel rim of given area, depends solely upon the rim velocity and is independent of the rim radius. The bursting velocity of a flywheel, based on hoop stress alone (not considering bending stresses), is related to the tensile stress in the flywheel rim by the following formula which is based on the centrifugal force formula from mechanics.

$$V = \sqrt{10 \times s} \qquad \text{or,} \qquad s = V^2 \div 10$$

where V = velocity of outside circumference of rim in feet per second, and s is the tensile strength of the rim material in pounds per square inch.

For cast iron having a tensile strength of 19,000 pounds per square inch the bursting speed would be:

$$V = \sqrt{10 \times 19,000} = 436 \text{ feet per second}$$

Built-up Flywheels: Flywheels built up of solid disks of rolled steel plate stacked and bolted together on a through shaft have greater speed capacity than other types. The maximum hoop stress is at the bore and is given by the formula,

$$s = 0.0194V^2[4.333 + (d/D)^2]$$

Copyright 2004, Industrial Press, Inc., New York, NY

In this formula, s and V are the stress and velocity as previously defined and d and D are the bore and outside diameters, respectively.

Assuming the plates to be of steel having a tensile strength of 60,000 pounds per square inch and a safe working stress of 24,000 pounds per square inch (using a factor of safety of 2.5 on stress or $\sqrt{2.5}$ on speed) and taking the worst condition (when d approaches D), the safe rim speed for this type of flywheel is 500 feet per second or 30,000 feet per minute.

Combined Stresses in Flywheels.— The bending stresses in the rim of a flywheel may exceed the centrifugal (hoop tension) stress predicted by the simple formula $s = V^2/10$ by a considerable amount. By taking into account certain characteristics of flywheels, relatively simple formulas have been developed to determine the stress due to the combined effect of hoop tension and bending stress. Some of the factors that influence the magnitude of the maximum combined stress acting at the rim of a flywheel are:

1) *The number of spokes*. Increasing the number of spokes decreases the rim span between spokes and hence decreases the bending moment. Thus an eight-spoke wheel can be driven to a considerably higher speed before bursting than a six-spoke wheel having the same rim.

2) *The relative thickness of the spokes*. If the spokes were extremely thin, like wires, they could offer little constraint to the rim in expanding to its natural diameter under centrifugal force, and hence would cause little bending stress. Conversely, if the spokes were extremely heavy in proportion to the rim, they would restrain the rim thereby setting up heavy bending stresses at the junctions of the rim and spokes.

3) *The relative thickness of the rim to the diameter*. If the rim is quite thick (i.e., has a large section modulus in proportion to span), its resistance to bending will be great and bending stress small. Conversely, thin rims with a section modulus small in comparison with diameter or span have little resistance to bending, thus are subject to high bending stresses.

4) *Residual stresses*. These include shrinkage stresses, impact stresses, and stresses caused by operating torques and imperfections in the material. Residual stresses are taken into account by the use of a suitable factor of safety. (See *Factors of Safety for Flywheels*.)

The formulas that follow give the maximum combined stress at the rim of fly-wheels having 6, 8, and 10 spokes. These formulas are for flywheels with *rectangular rim sections* and take into account the first three of the four factors listed as influencing the magnitude of the combined stress in flywheels.

For 6 spokes: $$s = \frac{V^2}{10}\left[1 + \left(\frac{0.56B - 1.81}{3Q + 3.14}\right)Q\right]$$

For 8 spokes: $$s = \frac{V^2}{10}\left[1 + \left(\frac{0.42B - 2.53}{4Q + 3.14}\right)Q\right]$$

For 10 spokes: $$s = \frac{V^2}{10}\left[1 + \left(\frac{0.33B - 3.22}{5Q + 3.14}\right)Q\right]$$

In these formulas, s = maximum combined stress in pounds per square inch; Q = ratio of mean spoke cross-section area to rim cross-section area; B = ratio of outside diameter of rim to rim thickness; and V = velocity of flywheel rim in feet per second.

Thickness of Cast Iron Flywheel Rims.— The mathematical analysis of the stresses in flywheel rims is not conclusive owing to the uncertainty of shrinkage stresses in castings or the strength of the joint in sectional wheels. When a flywheel of ordinary design is revolving at high speed, the tendency of the rim is to bend or bow outward between the arms, and the bending stresses may be serious, especially if the rim is wide and thin and the spokes are rather widely spaced. When the rims are thick, this tendency does not need to be considered, but in a thin rim running at high speed, the stress in the middle might become suf-

Copyright 2004, Industrial Press, Inc., New York, NY

ficiently great to cause the wheel to fail. The proper thickness of a cast-iron rim to resist this tendency is given for solid rims by Formula (1) and for a jointed rim by Formula (2).

$$t = \frac{0.475d}{n^2\left(\frac{6000}{v^2} - \frac{1}{10}\right)} \quad (1) \qquad t = \frac{0.95d}{n^2\left(\frac{6000}{v^2} - \frac{1}{10}\right)} \quad (2)$$

In these formulas, t = thickness of rim, in inches; d = diameter of flywheel, in inches; n = number of arms; v = peripheral speed, in feet per second.

Factors of Safety for Flywheels.— Cast-iron flywheels are commonly designed with a factor of safety of 10 to 13. A factor of safety of 10 applied to the tensile strength of a flywheel material is equivalent to a factor of safety of $\sqrt{10}$ or 3.16 on the speed of the flywheel because the stress on the rim of a flywheel increases as the square of the speed. Thus, a flywheel operating at a speed twice that for which it was designed would undergo rim stresses four times as great as at the design speed.

Tables of Safe Speeds for Flywheels.— The accompanying Table 1, prepared by T. C. Rathbone of The Fidelity and Casualty Company of New York, gives general recommendations for safe rim speeds for flywheels of various constructions. Table 2 shows the number of revolutions per minute corresponding to the rim speeds in Table 1.

Table 1. Safe Rim Speeds for Flywheels



Type of Wheel	Safe Rim Speed	
	Feet per Sec.	Feet per Min.
Solid cast iron (balance wheels—heavy rims)	110	6,600
Solid cast iron (pulley wheels—thin rims)	85	5,100
Wheels with shrink link joints	77.5	4,650
Wheels with pad type joints	70.7	4,240
Wheels with bolted flange joints	50	3,000
Solid cast steel wheels	200	12,000
Wheels built up of stacked steel plates	500	30,000

To find the safe speed in revolutions per minute, divide the safe rim speed in feet per minute by 3.14 times the outside diameter of the flywheel rim in feet. For flywheels up to 15 feet in diameter, see Table 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Safe Speeds of Rotation for Flywheels

Outside Diameter of Rim (feet)	Safe Rim Speed in Feet per Minute (from Table 1)						
	6,600	5,100	4,650	4,240	3,000	12,000	30,000
	Safe Speed of Rotation in Revolutions per Minute						
1	2100	1623	1480	1350	955	3820	9549
2	1050	812	740	676	478	1910	4775
3	700	541	493	450	318	1273	3183
4	525	406	370	338	239	955	2387
5	420	325	296	270	191	764	1910
6	350	271	247	225	159	637	1592
7	300	232	211	193	136	546	1364
8	263	203	185	169	119	478	1194
9	233	180	164	150	106	424	1061
10	210	162	148	135	96	382	955
11	191	148	135	123	87	347	868
12	175	135	123	113	80	318	796
13	162	125	114	104	73	294	735
14	150	116	106	97	68	273	682
15	140	108	99	90	64	255	637

Safe speeds of rotation are based on safe rim speeds shown in Table 1.

Safe Speed Formulas for Flywheels and Pulleys.— No simple formula can accommodate all the various types and proportions of flywheels and pulleys and at the same time provide a uniform factor of safety for each. Because of considerations of safety, such a formula would penalize the better constructions to accommodate the weaker designs.

One formula that has been used to check the maximum rated operating speed of flywheels and pulleys and which takes into account material properties, construction, rim thickness, and joint efficiencies is the following:

$$N = \frac{CAMEK}{D}$$

In this formula,

N = maximum rated operating speed in revolutions per minute

C = 1.0 for wheels driven by a constant speed electric motor (i.e., a-c squirrel-cage induction motor or a-c synchronous motor, etc.)
0.90 for wheels driven by variable speed motors, engines or turbines where overspeed is not over 110 per cent of rated operating speed

A = 0.90 for 4 arms or spokes
1.00 for 6 arms or spokes
1.08 for 8 arms or spokes
1.50 for disc type

M = 1.00 for cast iron of 20,000 psi tensile strength, or unknown
1.12 for cast iron of 25,000 psi tensile strength
1.22 for cast iron of 30,000 psi tensile strength
1.32 for cast iron of 35,000 psi tensile strength
2.20 for nodular iron of 60,000 psi tensile strength
2.45 for cast steel of 60,000 psi tensile strength
2.75 for plate or forged steel of 60,000 psi tensile strength

E = joint efficiency
1.0 for solid rim
0.85 for link or prison joints
0.75 for split rim — bolted joint at arms
0.70 for split rim — bolted joint between arms

Copyright 2004, Industrial Press, Inc., New York, NY

K = 1355 for rim thickness equal to 1 per cent of outside diameter
1650 for rim thickness equal to 2 per cent of outside diameter
1840 for rim thickness equal to 3 per cent of outside diameter
1960 for rim thickness equal to 4 per cent of outside diameter
2040 for rim thickness equal to 5 per cent of outside diameter
2140 for rim thickness equal to 7 per cent of outside diameter
2225 for rim thickness equal to 10 per cent of outside diameter
2310 for rim thickness equal to 15 per cent of outside diameter
2340 for rim thickness equal to 20 per cent of outside diameter
D = outside diameter of rim in feet

Example: A six-spoke solid cast iron balance wheel 8 feet in diameter has a rectangular rim 10 inches thick. What is the safe speed, in revolutions per minute, if driven by a constant speed motor?

In this instance, $C = 1$; $A = 1$; $M = 1$, since tensile strength is unknown; $E = 1$; $K = 2225$ since the rim thickness is approximately 10 per cent of the wheel diameter; and $D = 8$ feet. Thus,

$$N = \frac{1 \times 1 \times 1 \times 2225}{8} = 278 \text{ rpm}$$

(*Note:* This safe speed is slightly greater than the value of 263 rpm obtainable directly from Tables 1 and 2.)

Tests to Determine Flywheel Bursting Speeds.— Tests made by Prof. C. H. Benjamin, to determine the bursting speeds of flywheels, showed the following results:

Cast-iron Wheels with Solid Rims: Cast-iron wheels having solid rims burst at a rim speed of 395 feet per second, corresponding to a centrifugal tension of about 15,600 pounds per square inch.

Wheels with Jointed Rims: Four wheels were tested with joints and bolts inside the rim, using the familiar design ordinarily employed for band wheels, but with the joints located at points one-fourth of the distance from one arm to the next. These locations represent the points of least bending moment, and, consequently, the points at which the deflection due to centrifugal force would be expected to have the least effect. The tests, however, did not bear out this conclusion. The wheels burst at a rim speed of 194 feet per second, corresponding to a centrifugal tension of about 3750 pounds per square inch. These wheels, therefore, were only about one-quarter as strong as the wheels with solid rims, and burst at practically the same speed as wheels in a previous series of tests in which the rim joints were midway between the arms.

Bursting Speed for Link Joints: Another type of wheel with deep rim, fastened together at the joints midway between the arms by links shrunk into recesses, after the manner of flywheels for massive engines, gave much superior results. This wheel burst at a speed of 256 feet per second, indicating a centrifugal tension of about 6600 pounds per square inch.

Wheel having Tie-rods: Tests were made on a band wheel having joints inside the rim, midway between the arms, and in all respects like others of this design previously tested, except that tie-rods were used to connect the joints with the hub. This wheel burst at a speed of 225 feet per second, showing an increase of strength of from 30 to 40 per cent over similar wheels without the tie-rods.

Wheel Rim of I-section: Several wheels of special design, not in common use, were also tested, the one giving the greatest strength being an English wheel, with solid rim of I-section, made of high-grade cast iron and with the rim tied to the hub by steel wire spokes. These spokes were adjusted to have a uniform tension. The wheel gave way at a rim speed of 424 feet per second, which is slightly higher than the speed of rupture of the solid rim wheels with ordinary style of spokes.

Copyright 2004, Industrial Press, Inc., New York, NY

Tests on Flywheel of Special Construction: A test was made on a flywheel 49 inches in diameter and weighing about 900 pounds. The rim was 6¾ inches wide and 1⅛ inches thick, and was built of ten segments, the material being cast steel. Each joint was secured by three "prisoners" of an I-section on the outside face, by link prisoners on each edge, and by a dovetailed bronze clamp on the inside, fitting over lugs on the rim. The arms were of phosphor-bronze, twenty in number, ten on each side, and were cros-shaped in section. These arms came midway between the rim joints and were bolted to plane faces on the polygonal hub. The rim was further reinforced by a system of diagonal bracing, each section of the rim being supported at five points on each side, in such a way as to relieve it almost entirely from bending. The braces, like the arms, were of phosphor-bronze, and all bolts and connecting links were of steel. This wheel was designed as a model of a proposed 30-foot flywheel. On account of the excessive air resistance the wheel was enclosed at the sides between sheet-metal disks. This wheel burst at 1775 revolutions per minute or at a linear speed of 372 feet per second. The hub and main spokes of the wheel remained nearly in place, but parts of the rim were found 200 feet away. This sudden failure of the rim casting was unexpected, as it was thought the flange bolts would be the parts to give way first. The tensile strength of the casting at the point of fracture was about four times the strength of the wheel rim at a solid section.

Stresses in Rotating Disks.— When a disk of uniform width is rotated, the maximum stress S_t is tangential and at the bore of the hub, and the tangential stress is always greater than the radial stress at the same point on the disk. If S_t = maximum tangential stress in pounds per sq. in.; w = weight of material, lb. per cu. in.; N = rev. per min.; m = Poisson's ratio = 0.3 for steel; R = outer radius of disk, inches; r = inner radius of disk or radius of bore, inches.

$$S_t = 0.000071wN^2[(3+m)R^2 + (1-m)r^2]$$

Steam Engine Flywheels.— The variable amount of energy during each stroke and the allowable percentage of speed variation are of special importance in designing steam engine flywheels. The earlier the point of cut-off, the greater the variation in energy and the larger the flywheel that will be required. The weight of the reciprocating parts and the length of the connecting-rod also affect the variation. The following formula is used for computing the weight of the flywheel rim:

Let W = weight of rim in pounds
D = mean diameter of rim in feet
N = number of revolutions per minute
$1/n$ = allowable variation in speed (from $1/50$ to $1/100$)
E = excess and deficiency of energy in foot-pounds
c = factor of energy excess, from the accompanying table
HP = indicated horsepower

Then, if the indicated horsepower is given:

$$W = \frac{387{,}587{,}500 \times cn \times \text{HP}}{D^2N^3} \quad (1)$$

If the work in foot-pounds is given, then:

$$W = \frac{11{,}745nE}{D^2N^2} \quad (2)$$

In the second formula, E equals the average work in foot-pounds done by the engine in one revolution, multiplied by the decimal given in the accompanying table, "*Factors for Engine Flywheel Calculations*," which covers both condensing and non-condensing engines:

Copyright 2004, Industrial Press, Inc., New York, NY

Factors for Engine Flywheel Calculations

Condensing Engines						
Fraction of stroke at which steam is cut off	1/3	1/4	1/5	1/6	1/7	1/8
Factor of energy excess	0.163	0.173	0.178	0.184	0.189	0.191
Non-condensing Engines						
Steam cut off at			1/2	1/3	1/4	1/5
Factor of energy excess			0.160	0.186	0.209	0.232

Example 1: A non-condensing engine of 150 indicated horsepower is to make 200 revolutions per minute, with a speed variation of 2 per cent. The average cut-off is to be at one-quarter stroke, and the flywheel is to have a mean diameter of 6 feet. Find the necessary weight of the rim in pounds.

From the table $c = 0.209$, and from the data given HP = 150; $N = 200$; $1/n = 1/50$ or $n = 50$; and, $D = 6$.

Substituting these values in Equation (1):

$$W = \frac{387,587,500 \times 0.209 \times 50 \times 150}{6^2 \times 200^3} = 2110 \text{ pounds, nearly}$$

Example 2: A condensing engine, 24 × 42 inches, cuts off at one-third stroke and has a mean effective pressure of 50 pounds per square inch. The flywheel is to be 18 feet in mean diameter and make 75 revolutions per minute with a variation of 1 per cent. Find the required weight of the rim.

The work done on the piston in one revolution is equal to the pressure on the piston multiplied by the distance traveled or twice the stroke in feet. The area of the piston is 452.4 square inches, and twice the stroke is 7 feet. The work done on the piston in one revolution is, therefore, 452.4 × 50 × 7 = 158,340 foot-pounds. From the table $c = 0.163$, and therefore:

$$E = 158,340 \times 0.163 = 25,810 \text{ foot-pounds}$$

From the data given: $n = 100$; $D = 18$; $N = 75$. Substituting these values in Equation (2):

$$W = \frac{11,745 \times 100 \times 25,810}{18^2 \times 75^2} = 16,650 \text{ pounds, nearly}$$

Spokes or Arms of Flywheels.— Flywheel arms are usually of elliptical cross-section. The major axis of the ellipse is in the plane of rotation to give the arms greater resistance to bending stresses and reduce the air resistance which may be considerable at high velocity. The stresses in the arms may be severe, due to the inertia of a heavy rim when sudden load changes occur. The strength of the arms should equal three-fourths the strength of the shaft in torsion.

If W equals the width of the arm at the hub (length of major axis) and D equals the shaft diameter, then W equals 1.3 D for a wheel having 6 arms; and for an 8-arm wheel W equals 1.2 D. The thickness of the arm at the hub (length of minor axis) equals one-half the width. The arms usually taper toward the rim. The cross-sectional area at the rim should not be less than two-thirds the area at the hub.

Copyright 2004, Industrial Press, Inc., New York, NY

Critical Speeds

Critical Speeds of Rotating Bodies and Shafts.— If a body or disk mounted upon a shaft rotates about it, the center of gravity of the body or disk must be at the center of the shaft, if a perfect running balance is to be obtained. In most cases, however, the center of gravity of the disk will be slightly removed from the center of the shaft, owing to the difficulty of perfect balancing. Now, if the shaft and disk be rotated, the centrifugal force generated by the heavier side will be greater than that generated by the lighter side geometrically opposite to it, and the shaft will deflect toward the heavier side, causing the center of the disk to rotate in a small circle. A rotating shaft without a body or disk mounted on it can also become dynamically unstable, and the resulting vibrations and deflections can result in damage not only to the shaft but to the machine of which it is a part. These conditions hold true up to a comparatively high speed; but a point is eventually reached (at several thousand revolutions per minute) when momentarily there will be excessive vibration, and then the parts will run quietly again. The speed at which this occurs is called the *critical speed* of the wheel or shaft, and the phenomenon itself for the shaft-mounted disk or body is called the *settling* of the wheel. The explanation of the settling is that at this speed the axis of rotation changes, and the wheel and shaft, instead of rotating about their geometrical center, begin to rotate about an axis through their center of gravity. The shaft itself is then deflected so that for every revolution its geometrical center traces a circle around the center of gravity of the rotating mass.

Critical speeds depend upon the magnitude or location of the load or loads carried by the shaft, the length of the shaft, its diameter and the kind of supporting bearings. The normal operating speed of a machine may or may not be higher than the critical speed. For instance, some steam turbines exceed the critical speed, although they do not run long enough at the critical speed for the vibrations to build up to an excessive amplitude. The practice of the General Electric Co. at Schenectady is to keep below the critical speeds. It is assumed that the maximum speed of a machine may be within 20 per cent high or low of the critical speed without vibration troubles. Thus, in a design of steam turbine sets, critical speed is a factor that determines the size of the shafts for both the generators and turbines. Although a machine may run very close to the critical speed, the alignment and play of the bearings, the balance and construction generally, will require extra care, resulting in a more expensive machine; moreover, while such a machine may run smoothly for a considerable time, any looseness or play that may develop later, causing a slight imbalance, will immediately set up excessive vibrations.

The formulas commonly used to determine critical speeds are sufficiently accurate for general purposes. There are cases, however, where the torque applied to a shaft has an important effect on its critical speed. Investigations have shown that the critical speeds of a uniform shaft are decreased as the applied torque is increased, and that there exist critical torques which will reduce the corresponding critical speed of the shaft to zero. A detailed analysis of the effects of applied torques on critical speeds may be found in a paper, "Critical Speeds of Uniform Shafts under Axial Torque," by Golumb and Rosenberg, presented at the First U.S. National Congress of Applied Mechanics in 1951.

Formulas for Critical Speeds.— The critical speed formulas given in the accompanying table (from the paper on Critical Speed Calculation presented before the ASME by S. H. Weaver) apply to (1) shafts with single concentrated loads and (2) shafts carrying uniformly distributed loads. These formulas also cover different conditions as regards bearings. If the bearings are self-aligning or very short, the shaft is considered supported at the ends; whereas, if the bearings are long and rigid, the shaft is considered fixed. These formulas, for both concentrated and distributed loads, apply to vertical shafts as well as horizontal shafts, the critical speeds having the same value in both cases. The data required for the solution of critical speed problems are the same as for shaft deflection. As the shaft is usually of variable diameter and its stiffness is increased by a long hub, an ideal shaft of uniform diameter and equal stiffness must be assumed.

Copyright 2004, Industrial Press, Inc., New York, NY

Critical Speed Formulas

Formulas for Single Concentrated Load		
 $N = 387,000\frac{d^2}{ab}\sqrt{\frac{l}{W}}$ Bearings supported	 $N = 1,550,500\frac{d^2}{l\sqrt{Wl}}$ Bearings supported	 $N = 387,000\frac{d^2 l}{ab}\sqrt{\frac{l}{Wab}}$ Bearings fixed
 $N = 3,100,850\frac{d^2}{l\sqrt{Wl}}$ Bearings fixed	 $N = 775,200\frac{d^2 l}{ab}\sqrt{\frac{l}{Wa(3l+b)}}$ One-fixed — One supported	 $N = 387,000\frac{d^2}{l\sqrt{Wl}}$ One fixed — One free end
Formulas for Distributed Loads—First Critical Speed		
 $N = 2,232,500\frac{d^2}{l\sqrt{Wl}}$ $N_1 = 4,760,000\frac{d}{l^2}$ Bearings supported	 $N = 4,979,250\frac{d^2}{l\sqrt{Wl}}$ $N_1 = 10,616,740\frac{d}{l^2}$ Bearings fixed	 $N = 795,200\frac{d^2}{l\sqrt{Wl}}$ $N_1 = 1,695,500\frac{d}{l^2}$ One fixed—One free end

N = critical speed, RPM

N_1 = critical speed of shaft alone

d = diameter of shaft, in inches

W = load applied to shaft, in pounds

l = distance between centers of bearings, in inches

a and b = distances from bearings to load

In calculating critical speeds, the weight of the shaft is either neglected or, say, one-half to two-thirds of the weight is added to the concentrated load. The formulas apply to steel shafts having a modulus of elasticity $E = 29{,}000{,}000$. Although a shaft carrying a number of loads or a distributed load may have an infinite number of critical speeds, ordinarily it is the first critical speed that is of importance in engineering work. The first critical speed is obtained by the formulas given in the distributed loads portion of the table *Critical Speed Formulas*.

Copyright 2004, Industrial Press, Inc., New York, NY

Balancing Rotating Parts

Static Balancing.— There are several methods of testing the standing or static balance of a rotating part. A simple method that is sometimes used for flywheels, etc., is illustrated by the diagram, Fig. 1. An accurate shaft is inserted through the bore of the finished wheel, which is then mounted on carefully leveled "parallels" A. If the wheel is in an unbalanced state, it will turn until the heavy side is downward. When it will stand in any position as the result of counterbalancing and reducing the heavy portions, it is said to be in standing or static balance. Another test which is used for disk-shaped parts is shown in Fig. 2. The disk D is mounted on a vertical arbor attached to an adjustable cross-slide B. The latter is carried by a table C, which is supported by a knife-edged bearing. A pendulum having an adjustable screw-weight W at the lower end is suspended from cross-slide B. To test the static balance of disk D, slide B is adjusted until pointer E of the pendulum coincides with the center of a stationary scale F. Disk D is then turned halfway around without moving the slide, and if the indicator remains stationary, it shows that the disk is in balance for this particular position. The test is then repeated for ten or twelve other positions, and the heavy sides are reduced, usually by drilling out the required amount of metal. Several other devices for testing static balance are designed on this same principle.



Fig. 1.



Fig. 2.



Fig. 3.

Running or Dynamic Balance.— A cylindrical body may be in perfect static balance and not be in a balanced state when rotating at high speed. If the part is in the form of a thin disk, static balancing, if carefully done, may be accurate enough for high speeds, but if the rotating part is long in proportion to its diameter, and the unbalanced portions are at opposite ends or in different planes, the balancing must be done so as to counteract the centrifugal force of these heavy parts when they are rotating rapidly. This process is known as a running balance or dynamic balancing. To illustrate, if a heavy section is located at H (Fig. 3), and another correspondingly heavy section at H_1, one may exactly counterbalance the other when the cylinder is stationary, and this static balance may be sufficient for a part rigidly mounted and rotating at a comparatively slow speed; but when the speed is very high, as in turbine rotors, etc., the heavy masses H and H_1, being in different planes, are in an unbalanced state owing to the effect of centrifugal force, which results in excessive strains and injurious vibrations. Theoretically, to obtain a perfect running balance, the exact positions of the heavy sections should be located and the balancing effected either by reducing their weight or by adding counterweights opposite each section and in the same plane at the proper radius; but if the rotating part is rigidly mounted on a stiff shaft, a running balance that is sufficiently accurate for practical purposes can be obtained by means of comparatively few counterbalancing weights located with reference to the unbalanced parts.

Balancing Calculations.— As indicated previously, centrifugal forces caused by an unbalanced mass or masses in a rotating machine member cause additional loads on the bearings which are transmitted to the housing or frame and to other machine members. Such dynamically unbalanced conditions can occur even though static balance (balance at

Copyright 2004, Industrial Press, Inc., New York, NY

zero speed) exists. Dynamic balance can be achieved by the addition of one or two masses rotating about the same axis and at the same speed as the unbalanced masses. A single unbalanced mass can be balanced by one counterbalancing mass located 180 degrees opposite and in the same plane of rotation as the unbalanced mass, if the product of their respective radii and masses are equal; i.e., $M_1r_1 = M_2r_2$. Two or more unbalanced masses rotating in the same plane can be balanced by a single mass rotating in the same plane, or by two masses rotating about the same axis in two separate planes. Likewise, two or more unbalanced masses rotating in different planes about a common axis can be balanced by two masses rotating about the same axis in separate planes. When the unbalanced masses are in separate planes they may be in static balance but not in dynamic balance; i.e., they may be balanced when not rotating but unbalanced when rotating. If a system is in dynamic balance, it will remain in balance at all speeds, although this is not strictly true at the critical speed of the system. (See *Critical Speeds* on page 195.)

In all the equations that follow, the symbol M denotes either mass in kilograms or in slugs, or weight in pounds. Either mass or weight units may be used and the equations may be used with metric or with customary English units without change; however, in a given problem the units must be all metric or all customary English.

Counterbalancing Several Masses Located in a Single Plane.— In all balancing problems, it is the product of counterbalancing mass (or weight) and its radius that is calculated; it is thus necessary to select either the mass or the radius and then calculate the other value from the product of the two quantities. Design considerations usually make this decision self-evident. The angular position of the counterbalancing mass must also be calculated. Referring to Fig. 4:

$$M_Br_B = \sqrt{(\Sigma Mr\cos\theta)^2 + (\Sigma Mr\sin\theta)^2} \quad (1)$$

$$\tan\theta_B = \frac{-(\Sigma Mr\sin\theta)}{-(\Sigma Mr\cos\theta)} = \frac{y}{x} \quad (2)$$



Fig. 4.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Relationship of the Signs of the Functions of the Angle with Respect to the Quadrant in Which They Occur



	Angle θ			
	0° to 90°	90° to 180°	180° to 270°	270° to 360°
	Signs of the Functions			
tan	$\frac{+y}{+x}$	$\frac{+y}{-x}$	$\frac{-y}{-x}$	$\frac{-y}{+x}$
sine	$\frac{+y}{+r}$	$\frac{+y}{+r}$	$\frac{-y}{+r}$	$\frac{-y}{+r}$
cosine	$\frac{+x}{+r}$	$\frac{-x}{+r}$	$\frac{-x}{+r}$	$\frac{+x}{+r}$

where:

$M_1, M_2, M_3, \ldots M_n$ = any unbalanced mass or weight, kg or lb

M_B = counterbalancing mass or weight, kg or lb

r = radius to center of gravity of any unbalanced mass or weight, mm or inch

r_B = radius to center of gravity of counterbalancing mass or weight, mm or inch

θ = angular position of r of any unbalanced mass or weight, degrees

θ_B = angular position of r_B of counterbalancing mass or weight, degrees

x and y = see Table 1

Table 1 is helpful in finding the angular position of the counterbalancing mass or weight. It indicates the range of the angles within which this angular position occurs by noting the plus and minus signs of the numerator and the denominator of the terms in Equation (2). In a like manner, Table 1 is helpful in determining the *sign* of the sine or cosine functions for angles ranging from 0 to 360 degrees. Balancing problems are usually solved most conveniently by arranging the arithmetical calculations in a tabular form.

Example: Referring to Fig. 4, the particular values of the unbalanced weights have been entered in the table below. Calculate the magnitude of the counterbalancing weight if its radius is to be 10 inches.

M No.	M lb.	r in.	θ deg.	cos θ	sin θ	$Mr\cos\theta$	$Mr\sin\theta$
1	10	10	30	0.8660	0.5000	86.6	50.0
2	5	20	120	−0.5000	0.8660	−50.0	86.6
3	15	15	200	−0.9397	−0.3420	−211.4	−77.0
						$-174.8 = \Sigma Mr\cos\theta$	$59.6 = \Sigma Mr\sin\theta$

$$M_B = \frac{\sqrt{(\Sigma Mr\cos\theta)^2 + (\Sigma Mr\sin\theta)^2}}{r_B} = \frac{\sqrt{(-174.8)^2 + (59.6)^2}}{10}$$

$$M_B = 18.5 \text{ lb}$$

$$\tan\theta_B = \frac{-(\Sigma Mr\sin\theta)}{-(\Sigma Mr\cos\theta)} = \frac{-(59.6)}{-(-174.8)} = \frac{-y}{+x};\ \theta_B = 341°10'$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5.

Counterbalancing Masses Located in Two or More Planes.— Unbalanced masses or weights rotating about a common axis in two separate planes of rotation form a couple, which must be counterbalanced by masses or weights, also located in two separate planes, call them planes A and B, and rotating about the same common axis (see *Couples*, page 147). In addition, they must be balanced in the direction perpendicular to the axis, as before. Since two counterbalancing masses are required, two separate equations are required to calculate the product of each mass or weight and its radius, and two additional equations are required to calculate the angular positions. The planes A and B selected as balancing planes may be any two planes separated by any convenient distance c, along the axis of rotation. In Fig. 5:

For balancing plane A:

$$M_A r_A = \frac{\sqrt{(\Sigma Mrb\cos\theta)^2 + (\Sigma Mrb\sin\theta)^2}}{c} \tag{3}$$

$$\tan\theta_A = \frac{-(\Sigma Mrb\sin\theta)}{-(\Sigma Mrb\cos\theta)} = \frac{y}{x} \tag{4}$$

For balancing plane B:

$$M_B r_B = \frac{\sqrt{(\Sigma Mra\cos\theta)^2 + (\Sigma Mra\sin\theta)^2}}{c} \tag{5}$$

$$\tan\theta_B = \frac{-(\Sigma Mra\sin\theta)}{-(\Sigma Mra\cos\theta)} = \frac{y}{x} \tag{6}$$

Where: M_A and M_B are the mass or weight of the counterbalancing masses in the balancing planes A and B, respectively; r_A and r_B are the radii; and θ_A and θ_B are the angular positions of the balancing masses in these planes. M, r, and θ are the mass or weight, radius, and angular positions of the unbalanced masses, with the subscripts defining the particular mass to which the values are assigned. The length c, the distance between the balancing planes, is always a positive value. The axial dimensions, a and b, may be either positive or negative, depending upon their position relative to the balancing plane; for example, in Fig. 5, the dimension b_2 would be negative.

Example: Referring to Fig. 5, a set of values for the masses and dimensions has been selected and put into convenient table form below. The separation of balancing planes, c, is assumed as being 15 inches. If in balancing plane A, the radius of the counterbalancing

Copyright 2004, Industrial Press, Inc., New York, NY

weight is selected to be 10 inches; calculate the magnitude of the counterbalancing mass and its position. If in balancing plane *B*, the counterbalancing mass is selected to be 10 lb; calculate its radius and position.

For balancing plane *A*:

				Balancing Plane *A*			
Plane	*M* lb	*r* in.	θ deg.	*b* in.	*Mrb*	*Mrb* cos θ	*Mrb* sin θ
1	10	8	30	6	480	415.7	240.0
2	8	10	135	−6	−480	339.4	−339.4
3	12	9	270	12	1296	0.0	−1296.0
A	?	10	?	15[a]	…	755.1	−1395.4
B	10	?	?	0	…	= Σ*Mrb* cos θ	= Σ*Mrb* sin θ

[a] 15 inches = distance *c* between planes *A* and *B*.

$$M_A = \frac{\sqrt{(\Sigma Mrb\cos\theta)^2 + (\Sigma Mrb\sin\theta)^2}}{r_A c} = \frac{\sqrt{(755.1)^2 + (-1395.4)^2}}{10(15)}$$

$$M_A = 10.6 \text{ lb}$$

$$\tan\theta_A = \frac{-(\Sigma Mrb\sin\theta)}{-(\Sigma Mrb\cos\theta)} = \frac{-(-1395.4)}{-(755.1)} = \frac{+y}{-x}$$

$$\theta_A = 118°25'$$

For balancing plane *B*:

				Balancing Plane *B*			
Plane	*M* lb	*r* in.	θ deg.	*a* in.	*Mra*	*Mra* cos θ	*Mra* sin θ
1	10	8	30	9	720	623.5	360.0
2	8	10	135	21	1680	−1187.9	1187.9
3	12	9	270	3	324	0.0	−324.0
A	?	10	?	0	…	−564.4	1223.9
B	10	?	?	15[a]	…	= Σ*Mra* cos θ	= Σ*Mra* sin θ

[a] 15 inches = distance *c* between planes *A* and *B*.

$$r_B = \frac{\sqrt{(\Sigma Mra\cos\theta)^2 + (\Sigma Mra\sin\theta)^2}}{M_B c} = \frac{\sqrt{(-564.4)^2 + (1223.9)^2}}{10(15)}$$

$$= 8.985 \text{ in.}$$

$$\tan\theta_B = \frac{-(\Sigma Mra\sin\theta)}{-(\Sigma Mra\cos\theta)} = \frac{-(1223.9)}{-(-564.4)} = \frac{-y}{+x}$$

$$\theta_B = 294°45'$$

Balancing Lathe Fixtures.— Lathe fixtures rotating at a high speed require balancing. Often it is assumed that the center of gravity of the workpiece and fixture, and of the counterbalancing masses are in the same plane; however, this is not usually the case. Counterbalancing masses are required in two separate planes to prevent excessive vibration or bearing loads at high speeds.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6.

Usually a single counterbalancing mass is placed in one plane selected to be 180 degrees directly opposite the combined center of gravity of the workpiece and the fixture. Two equal counterbalancing masses are then placed in the second counterbalancing plane, equally spaced on each side of the fixture. Referring to Fig. 6, the two counterbalancing masses M_A and the two angles θ are equal. For the design in this illustration, the following formulas can be used to calculate the magnitude of the counterbalancing masses. Since their angular positions are fixed by the design, they are not calculated.

$$M_B = \frac{M_w r_w (l_1 + l_2)}{r_B l_1} \tag{7}$$

$$M_A = \frac{M_B r_B - M_w r_w}{2 r_A \sin\theta} \tag{8}$$

In these formulas M_w and r_w denote the mass or weight and the radius of the combined center of gravity of the workpiece and the fixture.

In Fig. 6 the combined weight of the workpiece and the fixture is 18.5 lb. The following dimensions were determined from the layout of the fixture and by calculating the centers of gravity: $r_w = 2$ in.; $r_A = 6.25$ in.; $r_B = 6$ in.; $l_1 = 3$ in.; $l_2 = 5$ in.; and $\theta = 30°$. Calculate the weights of the counterbalancing masses.

$$M_B = \frac{M_w r_w (l_1 + l_2)}{r_B l_1} = \frac{18.5 \times 2 \times 8}{6 \times 3} = 16.44 \text{ lb}$$

$$M_A = \frac{M_B r_B - M_w r_w}{2 r_A \sin\theta} = \frac{(16.44 \times 6) - (18.5 \times 2)}{(2 \times 6.25)\sin 30^\circ} = 9.86 \text{ lb (each weight)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

STRENGTH OF MATERIALS

Introduction

Strength of materials deals with the relations between the external forces applied to elastic bodies and the resulting deformations and stresses. In the design of structures and machines, the application of the principles of strength of materials is necessary if satisfactory materials are to be utilized and adequate proportions obtained to resist functional forces.

Forces are produced by the action of gravity, by accelerations and impacts of moving parts, by gasses and fluids under pressure, by the transmission of mechanical power, etc. In order to analyze the stresses and deflections of a body, the magnitudes, directions and points of application of forces acting on the body must be known. Information given in the Mechanics section provides the basis for evaluating force systems.

The time element in the application of a force on a body is an important consideration. Thus a force may be static or change so slowly that its maximum value can be treated as if it were static; it may be suddenly applied, as with an impact; or it may have a repetitive or cyclic behavior.

The environment in which forces act on a machine or part is also important. Such factors as high and low temperatures; the presence of corrosive gases, vapors and liquids; radiation, etc. may have a marked effect on how well parts are able to resist stresses.

Throughout the Strength of Materials section in this Handbook, both English and metric SI data and formulas are given to cover the requirements of working in either system of measurement. Formulas and text relating exclusively to SI units are given in bold-face type.

Mechanical Properties of Materials.— Many mechanical properties of materials are determined from tests, some of which give relationships between stresses and strains as shown by the curves in the accompanying figures.

Stress is force per unit area and is usually expressed in pounds per square inch. If the stress tends to stretch or lengthen the material, it is called *tensile* stress; if to compress or shorten the material, a *compressive* stress; and if to shear the material, a *shearing* stress. Tensile and compressive stresses always act at right-angles to (normal to) the area being considered; shearing stresses are always in the plane of the area (at right-angles to compressive or tensile stresses).



Fig. 1. Stress-strain curves

In the SI, the unit of stress is the pascal (Pa), the newton per meter squared (N/m^2). The megapascal (newtons per millimeter squared) is often an appropriate sub-multiple for use in practice.

Unit strain is the amount by which a dimension of a body changes when the body is subjected to a load, divided by the original value of the dimension. The simpler term *strain* is often used instead of unit strain.

Proportional limit is the point on a stress-strain curve at which it begins to deviate from the straight-line relationship between stress and strain.

Copyright 2004, Industrial Press, Inc., New York, NY

Elastic limit is the maximum stress to which a test specimen may be subjected and still return to its original length upon release of the load. A material is said to be stressed within the *elastic region* when the working stress does not exceed the elastic limit, and to be stressed in the *plastic region* when the working stress does exceed the elastic limit. The elastic limit for steel is for all practical purposes the same as its proportional limit.

Yield point is a point on the stress-strain curve at which there is a sudden increase in strain without a corresponding increase in stress. Not all materials have a yield point. Some representative values of the yield point (in ksi) are as follows:

Aluminum, wrought, 2014-T6	60	Titanium, pure	55–70
Aluminum, wrought, 6061-T6	35	Titanium, alloy, 5Al, 2.5Sn	110
Beryllium copper	140	Steel for bridges and buildings, ASTM A7-61T, all shapes	33
Brass, naval	25–50		
Cast iron, malleable	32–45	Steel, castings, high strength, for structural purposes, ASTM A148.60 (seven grades)	40–145
Cast iron, nodular	45–65		
Magnesium, AZ80A-T5	38	Steel, stainless (0.08–0.2C, 17Cr, 7Ni) ¼ hard	78

Yield strength, S_y, is the maximum stress that can be applied without permanent deformation of the test specimen. This is the value of the stress at the elastic limit for materials for which there is an elastic limit. Because of the difficulty in determining the elastic limit, and because many materials do not have an elastic region, yield strength is often determined by the offset method as illustrated by the accompanying figure at (3). Yield strength in such a case is the stress value on the stress-strain curve corresponding to a definite amount of permanent set or strain, usually 0.1 or 0.2 per cent of the original dimension. Yield strength data for various materials are given in tables starting on pages 417, 419, 463, 464, 466, 468, 472, 554, 556, 560, 569, 570, 575, 580, 588, 590, 591, and elsewhere.

Ultimate strength, S_u, (also called *tensile strength*) is the maximum stress value obtained on a stress-strain curve.

Modulus of elasticity, E, (also called *Young's modulus*) is the ratio of unit stress to unit strain within the proportional limit of a material in tension or compression. Some representative values of Young's modulus (in 10^6 psi) are as follows:

Aluminum, cast, pure	9	Magnesium, AZ80A-T5	6.5
Aluminum, wrought, 2014-T6	10.6	Titanium, pure	15.5
Beryllium copper	19	Titanium, alloy, 5 Al, 2.5 Sn	17
Brass, naval	15	Steel for bridges and buildings, ASTM A7-61T, all shapes	29
Bronze, phosphor, ASTM B159	15		
Cast iron, malleable	26	Steel, castings, high strength, for structural purposes, ASTM A148-60 (seven grades)	29
Cast iron, nodular	23.5		

Modulus of elasticity in shear, G, is the ratio of unit stress to unit strain within the proportional limit of a material in shear.

Poisson's ratio, μ, is the ratio of lateral strain to longitudinal strain for a given material subjected to uniform longitudinal stresses within the proportional limit. The term is found in certain equations associated with strength of materials. Values of Poisson's ratio for common materials are as follows:

Aluminum	0.334	Nickel silver	0.322
Beryllium copper	0.285	Phosphor bronze	0.349
Brass	0.340	Rubber	0.500
Cast iron, gray	0.211	Steel, cast	0.265
Copper	0.340	high carbon	0.295
Inconel	0.290	mild	0.303
Lead	0.431	nickel	0.291
Magnesium	0.350	Wrought iron	0.278
Monel metal	0.320	Zinc	0.331

Copyright 2004, Industrial Press, Inc., New York, NY

Compressive Properties.— From compression tests, *compressive yield strength*, S_{cy}, and *compressive ultimate strength*, S_{cu}, are determined. Ductile materials under compression loading merely swell or buckle without fracture, hence do not have a compressive ultimate strength.

Shear Properties.— The properties of *shear yield strength*, S_{sy}, *shear ultimate strength*, S_{su}, and the *modulus of rigidity*, G, are determined by direct shear and torsional tests. The modulus of rigidity is also known as the modulus of elasticity in shear. It is the ratio of the shear stress, τ, to the shear strain, γ, in radians, within the proportional limit: $G = \tau/\gamma$.

Creep.— Continuing changes in dimensions of a stressed material over time is called creep, and it varies with different materials and periods under stress, also with temperature. Creep tests may take some time as it is necessary to apply a constant tensile load to a specimen under a selected temperature. Measurements are taken to record the resulting elongation at time periods sufficiently long for a relationship to be established. The data are then plotted as elongation against time. The load is applied to the specimen only after it has reached the testing temperature, and causes an initial elastic elongation that includes some plastic deformation if the load is above the proportional limit for the material.

Some combinations of stress and temperature may cause failure of the specimen. Others show initial high rates of deformation, followed by decreasing, then constant, rates over long periods. Generally testing times to arrive at the constant rate of deformation are over 1000 hours.

Creep Rupture.— Tests for creep rupture are similar to creep tests but are prolonged until the specimen fails. Further data to be obtained from these tests include time to rupture, amount of elongation, and reduction of area. Stress-rupture tests are performed without measuring the elongation, so that no strain data are recorded, time to failure, elongation and reduction of area being sufficient. Sometimes, a V-notch is cut in the specimen to allow measurement of notch sensitivity under the testing conditions.

Stress Analysis.— Stresses, deflections, strains, and loads may be determined by application of strain gages or lacquers to the surface of a part, then applying loads simulating those to be encountered in service. Strain gages are commercially available in a variety of configurations and are usually cemented to the part surface. The strain gages are then calibrated by application of a known moment, load, torque, or pressure. The electrical characteristics of the strain gages change in proportion to the amount of strain, and the magnitude of changes in these characteristics under loads to be applied in service indicate changes caused by stress in the shape of the components being tested.

Lacquers are compounded especially for stress analysis and are applied to the entire part surface. When the part is loaded, and the lacquer is viewed under light of specific wavelength, stresses are indicated by color shading in the lacquer. The presence and intensity of the strains can then be identified and measured on the part(s) or on photographs of the setup. From such images, it is possible to determine the need for thicker walls, strengthening ribs and other modifications to component design that will enable the part to withstand stresses in service.

Most of these tests have been standardized by the American Society for Testing and Materials (ASTM), and are published in their *Book of Standards* in separate sections for metals, plastics, rubber, and wood. Many of the test methods are also adopted by the American National Standards Institute (ANSI).

Fatigue Properties.— When a material is subjected to many cycles of stress reversal or fluctuation (variation in magnitude without reversal), failure may occur, even though the maximum stress at any cycle is considerably less than the value at which failure would occur if the stress were constant. Fatigue properties are determined by subjecting test specimens to stress cycles and counting the number of cycles to failure. From a series of such tests in which maximum stress values are progressively reduced, S-N diagrams can be

Copyright 2004, Industrial Press, Inc., New York, NY

plotted as illustrated by the accompanying figures. The S-N diagram Fig. 2a shows the behavior of a material for which there is an *endurance limit*, S_{en}. Endurance limit is the stress value at which the number of cycles to failure is infinite. Steels have endurance limits that vary according to hardness, composition, and quality; but many non-ferrous metals do not. The S-N diagram Fig. 2b does not have an endurance limit. For a metal that does not have an endurance limit, it is standard practice to specify fatigue strength as the stress value corresponding to a specific number of stress reversals, usually 100,000,000 or 500,000,000.



Fig. 2a. S-N endurance limit

Fig. 2b. S-N no endurance limit

The Influence of Mean Stress on Fatigue.— Most published data on the fatigue properties of metals are for completely reversed alternating stresses, that is, the mean stress of the cycle is equal to zero. However, if a structure is subjected to stresses that fluctuate between different values of tension and compression, then the mean stress is not zero.

When fatigue data for a specified mean stress and design life are not available for a material, the influence of nonzero mean stress can be estimated from empirical relationships that relate failure at a given life, under zero mean stress, to failure at the same life under zero mean cyclic stress. One widely used formula is Goodman's linear relationship, which is

$$S_a = S(1 - S_m/S_u)$$

where S_a is the alternating stress associated with some nonzero mean stress, S_m. S is the alternating fatigue strength at zero mean stress. S_u is the ultimate tensile strength.

Goodman's linear relationship is usually represented graphically on a so-called *Goodman Diagram*, shown in Fig. 3a. The alternating fatigue strength or the alternating stress for a given number of endurance cycles is plotted on the ordinate (y-axis) and the static tensile strength is plotted on the abscissa (x-axis). The straight line joining the alternating fatigue strength, S, and the tensile strength, S_u, is the Goodman line.

The value of an alternating stress S_{ax} at a known value of mean stress S_{mx} is determined as shown by the dashed lines on the diagram.



Fig. 3a. Goodman Diagram



Fig. 3b. Mean Tensile Stress

For ductile materials, the Goodman law is usually conservative, since approximately 90 per cent of actual test data for most ferrous and nonferrous alloys fall above the Goodman line, even at low endurance values where the yield strength is exceeded. For many brittle

Copyright 2004, Industrial Press, Inc., New York, NY

materials, however, actual test values can fall below the Goodman line, as illustrated in Fig. 3b

As a rule of thumb, materials having an elongation of less than 5 per cent in a tensile test may be regarded as brittle. Those having an elongation of 5 per cent or more may be regarded as ductile.

Cumulative Fatigue Damage.— Most data are determined from tests at a constant stress amplitude. This is easy to do experimentally, and the data can be presented in a straightforward manner. In actual engineering applications, however, the alternating stress amplitude usually changes in some way during service operation. Such changes, referred to as "spectrum loading," make the direct use of standard S-N fatigue curves inappropriate. A problem exists, therefore, in predicting the fatigue life under varying stress amplitude from conventional, constant-amplitude S-N fatigue data.

The assumption in predicting spectrum loading effects is that operation at a given stress amplitude and number of cycles will produce a certain amount of permanent fatigue damage and that subsequent operation at different stress amplitude and number of cycles will produce additional fatigue damage and a sequential accumulation of total damage, which at a critical value will cause fatigue failure. Although the assumption appears simple, the amount of damage incurred at any stress amplitude and number of cycles has proven difficult to determine, and several "cumulative damage" theories have been advanced.

One of the first and simplest methods for evaluating cumulative damage is known as Miner's law or the linear damage rule, where it is assumed that n_1 cycles at a stress of S_1, for which the average number of cycles to failure is N_1, cause an amount of damage n_1/N_1. Failure is predicted to occur when

$$\Sigma n/N = 1$$

The term n/N is known as the "cycle ratio" or the damage fraction.

The greatest advantages of the Miner rule are its simplicity and prediction reliability, which approximates that of more complex theories. For these reasons the rule is widely used. It should be noted, however, that it does not account for all influences, and errors are to be expected in failure prediction ability.

Modes of Fatigue Failure.— Several modes of fatigue failure are:

Low/High-Cycle Fatigue: This fatigue process covers cyclic loading in two significantly different domains, with different physical mechanisms of failure. One domain is characterized by relatively low cyclic loads, strain cycles confined largely to the elastic range, and long lives or a high number of cycles to failure; traditionally, this has been called "high-cycle fatigue." The other domain has cyclic loads that are relatively high, significant amounts of plastic strain induced during each cycle, and short lives or a low number of cycles to failure. This domain has commonly been called "low-cycle fatigue" or cyclic strain-controlled fatigue.

The transition from low- to high-cycle fatigue behavior occurs in the range from approximately 10,000 to 100,000 cycles. Many define low-cycle fatigue as failure that occurs in 50,000 cycles or less.

Thermal Fatigue: Cyclic temperature changes in a machine part will produce cyclic stresses and strains if natural thermal expansions and contractions are either wholly or partially constrained. These cyclic strains produce fatigue failure just as though they were produced by external mechanical loading. When strain cycling is produced by a fluctuating temperature field, the failure process is termed "thermal fatigue."

While thermal fatigue and mechanical fatigue phenomena are very similar, and can be mathematically expressed by the same types of equations, the use of mechanical fatigue results to predict thermal fatigue performance must be done with care. For equal values of plastic strain range, the number of cycles to failure is usually up to 2.5 times lower for thermally cycled than for mechanically cycled samples.

Copyright 2004, Industrial Press, Inc., New York, NY

Corrosion Fatigue: Corrosion fatigue is a failure mode where cyclic stresses and a corrosion-producing environment combine to initiate and propagate cracks in fewer stress cycles and at lower stress amplitudes than would be required in a more inert environment. The corrosion process forms pits and surface discontinuities that act as stress raisers to accelerate fatigue cracking. The cyclic loads may also cause cracking and flaking of the corrosion layer, baring fresh metal to the corrosive environment. Each process accelerates the other, making the cumulative result more serious.

Surface or Contact Fatigue: Surface fatigue failure is usually associated with rolling surfaces in contact, and results in pitting, cracking, and spalling of the contacting surfaces from cyclic Hertz contact stresses that cause the maximum values of cyclic shear stresses to be slightly below the surface. The cyclic subsurface shear stresses generate cracks that propagate to the contacting surface, dislodging particles in the process.

Combined Creep and Fatigue: In this failure mode, all of the conditions for both creep failure and fatigue failure exist simultaneously. Each process influences the other in producing failure, but this interaction is not well understood.

Factors of Safety.— There is always a risk that the working stress to which a member is subjected will exceed the strength of its material. The purpose of a factor of safety is to minimize this risk.

Factors of safety can be incorporated into design calculations in many ways. For most calculations the following equation is used:

$$s_w = S_m / f_s \tag{1}$$

where f_s is the factor of safety, S_m is the strength of the material in pounds per square inch, and S_w is the allowable working stress, also in pounds per square inch. Since the factor of safety is greater than 1, the allowable working stress will be less than the strength of the material.

In general, S_m is based on yield strength for ductile materials, ultimate strength for brittle materials, and fatigue strength for parts subjected to cyclic stressing. Most strength values are obtained by testing standard specimens at 68°F. in normal atmospheres. If, however, the character of the stress or environment differs significantly from that used in obtaining standard strength data, then special data must be obtained. If special data are not available, standard data must be suitably modified.

General recommendations for values of factors of safety are given in the following list.

f_s	Application
1.3–1.5	For use with highly reliable materials where loading and environmental conditions are not severe, and where weight is an important consideration.
1.5–2	For applications using reliable materials where loading and environmental conditions are not severe.
2–2.5	For use with ordinary materials where loading and environmental conditions are not severe.
2.5–3	For less tried and for brittle materials where loading and environmental conditions are not severe.
3–4	For applications in which material properties are not reliable and where loading and environmental conditions are not severe, or where reliable materials are to be used under difficult loading and environmental conditions.

Working Stress.— Calculated working stresses are the products of calculated nominal stress values and stress concentration factors. Calculated nominal stress values are based on the assumption of idealized stress distributions. Such nominal stresses may be simple stresses, combined stresses, or cyclic stresses. Depending on the nature of the nominal stress, one of the following equations applies:

$$s_w = K\sigma \tag{2}$$
$$s_w = K\tau \tag{3}$$
$$s_w = K\sigma' \tag{4}$$
$$s_w = K\tau' \tag{5}$$
$$s_w = K\sigma_{cy} \tag{6}$$
$$s_w = K\tau_{cy} \tag{7}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where K is a stress concentration factor; σ and τ are, respectively, simple normal (tensile or compressive) and shear stresses; σ' and τ' are combined normal and shear stresses; σ_{cy} and τ_{cy} are cyclic normal and shear stresses.

Where there is uneven stress distribution, as illustrated in the table (on page 213) of simple stresses for Cases 3, 4 and 6, the maximum stress is the one to which the stress concentration factor is applied in computing working stresses. The location of the maximum stress in each case is discussed under the section *Simple Stresses* and the formulas for these maximum stresses are given in the *Table of Simple Stresses* on page 213.

Stress Concentration Factors.— Stress concentration is related to type of material, the nature of the stress, environmental conditions, and the geometry of parts. When stress concentration factors that specifically match all of the foregoing conditions are not available, the following equation may be used:

$$K = 1 + q(K_t - 1) \tag{8}$$

K_t is a theoretical stress concentration factor that is a function only of the geometry of a part and the nature of the stress; q is the *index of sensitivity* of the material. If the geometry is such as to provide no theoretical stress concentration, $K_t = 1$.

Curves for evaluating K_t are on pages 209 through 212. For constant stresses in cast iron and in ductile materials, $q = 0$ (hence $K = 1$). For constant stresses in brittle materials such as hardened steel, q may be taken as 0.15; for very brittle materials such as steels that have been quenched but not drawn, q may be taken as 0.25. When stresses are suddenly applied (impact stresses) q ranges from 0.4 to 0.6 for ductile materials; for cast iron it is taken as 0.5; and, for brittle materials, 1.



Fig. 4. Stress-concentration factor, K_t, for a filleted shaft in tension

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Stress-concentration factor, K_t, for a filleted shaft in torsion[a]



Fig. 6. Stress-concentration factor, K_t, for a shaft with shoulder fillet in bending[a]

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Stress-concentration factor, K_t, for a shaft, with a transverse hole, in torsion[a]



Fig. 8. Stress-concentration factor, K_t, for a grooved shaft in bending[a]

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 9. Stress-concentration factor, K_t, for a grooved shaft in torsion[a]



Fig. 10. Stress-concentration factor, K_t, for a shaft, with a transverse hole, in bending[a]

[a] Source: R. E. Peterson, Design Factors for Stress Concentration, *Machine Design*, vol. 23, 1951. For other stress concentration charts, see Lipson and Juvinall, *The Handbook of Stress and Strength*, The Macmillan Co., 1963.

Copyright 2004, Industrial Press, Inc., New York, NY

Simple Stresses.— Simple stresses are produced by constant conditions of loading on elements that can be represented as beams, rods, or bars. The table on page 213 summarizes information pertaining to the calculation of simple stresses. Following is an explanation of the symbols used in simple stress formulae: σ = simple normal (tensile or compressive) stress in pounds per square inch; τ = simple shear stress in pounds per square inch; F = external force in pounds; V = shearing force in pounds; M = bending moment in inch-pounds; T = torsional moment in inch-pounds; A = cross-sectional area in square inches; Z = section modulus in inches^3; Z_p = polar section modulus in inches^3; I = moment of inertia in inches^4; J = polar moment of inertia in inches^4; a = area of the web of wide flange and I beams in square inches; y = perpendicular distance from axis through center of gravity of cross-sectional area to stressed fiber in inches; c = radial distance from center of gravity to stressed fiber in inches.

Table 2. Table of Simple Stresses

Case	Type of Loading	Illustration	Stress Distribution	Stress Equations
1	Direct tension		Uniform	$\sigma = \frac{F}{A}$ (9)
2	Direct compression		Uniform	$\sigma = -\frac{F}{A}$ (10)
3	Bending	 Bending moment diagram	 Neutral plane	$\sigma = \pm\frac{M}{Z} = \pm\frac{My}{I}$ (11)
4	Shear	 Shearing force diagram	 Neutral plane	For beams of rectangular cross-section: $\tau = \frac{3V}{2A}$ (12) For beams of solid circular cross-section: $\tau = \frac{4V}{3A}$ (13) For wide flange and I beams (approximately): $\tau = \frac{V}{a}$ (14)
5	Direct shear		Uniform	$\tau = \frac{F}{A}$ (15)
6	Torsion			$\tau = \frac{T}{Zp} = \frac{Tc}{J}$ (16)

SI metric units can be applied in the calculations in place of the English units of measurement without changes to the formulas. The SI units are the newton (N), which is the unit of force; the meter; the meter squared; the pascal (Pa) which is the

Copyright 2004, Industrial Press, Inc., New York, NY

newton per meter squared (N/M^2); and the newton-meter (N · m) for moment of force. Often in design work using the metric system, the millimeter is employed rather than the meter. In such instances, the dimensions can be converted to meters before the stress calculations are begun. Alternatively, the same formulas can be applied using millimeters in place of the meter, providing the treatment is consistent throughout. In such instances, stress and strength properties must be expressed in megapascals (MPa), which is the same as newtons per millimeter squared (N/mm^2), and moments in newton-millimeters (N · mm^2). *Note*: 1 N/mm^2 = 1 N/10^{-6}m^2 = 10^6 N/m^2 = 1 meganewton/m^2 = 1 megapascal.

For direct tension and direct compression loading, Cases 1 and 2 in the table on page 213, the force F must act along a line through the center of gravity of the section at which the stress is calculated. The equation for direct compression loading applies only to members for which the ratio of length to least radius of gyration is relatively small, approximately 20, otherwise the member must be treated as a column.

The table *Stresses and Deflections in Beams* starting on page 261 give equations for calculating stresses due to bending for common types of beams and conditions of loading. Where these tables are not applicable, stress may be calculated using Equation (11) in the table on page 213. In using this equation it is necessary to determine the value of the bending moment at the point where the stress is to be calculated. For beams of constant cross-section, stress is ordinarily calculated at the point coinciding with the maximum value of bending moment. Bending loading results in the characteristic stress distribution shown in the table for Case 3. It will be noted that the maximum stress values are at the surfaces farthest from the neutral plane. One of the surfaces is stressed in tension and the other in compression. It is for this reason that the ± sign is used in Equation (11). Numerous tables for evaluating section moduli are given in the section starting on page 236.

Shear stresses caused by bending have maximum values at neutral planes and zero values at the surfaces farthest from the neutral axis, as indicated by the stress distribution diagram shown for Case 4 in the *Table of Simple Stresses* . Values for V in Equations (12), (13) and (14) can be determined from shearing force diagrams. The shearing force diagram shown in Case 4 corresponds to the bending moment diagram for Case 3. As shown in this diagram, the value taken for V is represented by the greatest vertical distance from the x axis. The shear stress caused by direct shear loading, Case 5, has a uniform distribution. However, the shear stress caused by torsion loading, Case 6, has a zero value at the axis and a maximum value at the surface farthest from the axis.

Deflections.— For direct tension and direct compression loading on members with uniform cross sections, deflection can be calculated using Equation (17). For direct tension loading, e is an elongation; for direct compression loading, e is a contraction. Deflection is in inches when the load F is in pounds, the length L over which deflection occurs is in inches, the cross-sectional area A is in square inches, and the modulus of elasticity E is in pounds per square inch. The angular deflection of members with uniform circular cross sections subject to torsion loading can be calculated with Equation (18).

$$e = FL/AE \qquad (17) \qquad\qquad \theta = TL/GJ \qquad (18)$$

The angular deflection θ is in radians when the torsional moment T is in inch-pounds, the length L over which the member is twisted is in inches, the modulus of rigidity G is in pounds per square inch, and the polar moment of inertia J is in inches^4.

Metric SI units can be used in Equations (17) and (18), where F = force in newtons (N); L = length over which deflection or twisting occurs in meters; A = cross-sectional area in meters squared; E = the modulus of elasticity in (newtons per meter squared); θ = radians; T = the torsional moment in newton-meters (N·m); G = modulus of rigidity, in pascals; and J = the polar moment of inertia in meters^4. If the load (F) is applied as a weight, it should be noted that the weight of a mass M kilograms is Mg newtons,

Copyright 2004, Industrial Press, Inc., New York, NY

where $g = 9.81$ m/s^2. Millimeters can be used in the calculations in place of meters, providing the treatment is consistent throughout.

Combined Stresses.— A member may be loaded in such a way that a combination of simple stresses acts at a point. Three general cases occur, examples of which are shown in the accompanying illustration Fig. 11.

Superposition of Stresses: Fig. 11 at (1) illustrates a common situation that results in simple stresses combining by superposition at points **a** and **b**. The equal and opposite forces F_1 will cause a compressive stress $\sigma_1 = -F_1/A$. Force F_2 will cause a bending moment M to exist in the plane of points **a** and **b**. The resulting stress $\sigma_2 = \pm M/Z$. The combined stress at point **a**,

$$\sigma_a' = -\frac{F_1}{A} - \frac{M}{Z} \qquad (19)$$

and at **b**,

$$\sigma_b' = -\frac{F_1}{A} + \frac{M}{Z} \qquad (20)$$

where the minus sign indicates a compressive stress and the plus sign a tensile stress. Thus, the stress at **a** will be compressive and at **b** either tensile or compressive depending on which term in the equation for σ_b' has the greatest value.

Normal Stresses at Right Angles: This is shown in Fig. 11 at (2). This combination of stresses occurs, for example, in tanks subjected to internal or external pressure. The principle normal stresses are $\sigma_x = F_1/A_1$, $\sigma_y = F_2/A_2$, and $\sigma_z = 0$ in this plane stress problem. Determine the values of these three stresses with their signs, order them algebraically, and then calculate the maximum shear stress:

$$\tau = (\sigma_{\text{largest}} - \sigma_{\text{smallest}})/2 \qquad (21)$$

Normal and Shear Stresses: The example in Fig. 11 at (3) shows a member subjected to a torsional shear stress, $\tau = T/Z_p$, and a direct compressive stress, $\sigma = -F/A$. At some point **a** on the member the principal normal stresses are calculated using the equation,

$$\sigma' = \frac{\sigma}{2} \pm \sqrt{\left(\frac{\sigma}{2}\right)^2 + \tau^2} \qquad (22)$$

The maximum shear stress is calculated by using the equation,

$$\tau' = \sqrt{\left(\frac{\sigma}{2}\right)^2 + \tau^2} \qquad (23)$$

The point **a** should ordinarily be selected where stress is a maximum value. For the example shown in the figure at (3), the point **a** can be anywhere on the cylindrical surface because the combined stress has the same value anywhere on that surface.



Fig. 11. Types of Combined Loading

Tables of Combined Stresses.— Beginning on page 216, these tables list equations for maximum nominal tensile or compressive (normal) stresses, and maximum nominal shear stresses for common machine elements. These equations were derived using general Equations (19), (20), (22), and (23). The equations apply to the critical points indicated on the

Copyright 2004, Industrial Press, Inc., New York, NY

figures. Cases 1, 2, 3, and 4 are cantilever beams. These may be loaded with a combination of a vertical and horizontal force, or by a single oblique force. If the single oblique force F and the angle θ are given, then horizontal and vertical forces can be calculated using the equations $F_x = F \cos \theta$ and $F_y = F \sin \theta$. In cases 9 and 10 of the table, the equations for σ_a' can give a tensile and a compressive stress because of the ± sign in front of the radical. Equations involving direct compression are valid only if machine elements have relatively short lengths with respect to their sections, otherwise column equations apply.

Calculation of Worst Stress Condition: Stress failure can occur at any critical point if either the tensile, compressive, or shear stress properties of the material are exceeded by the corresponding working stress. It is necessary to evaluate the factor of safety for each possible failure condition.

The following rules apply to calculations using equations in the *Table of Simple Stresses* on page 213, and to calculations based on Equations (19) and (20). *Rule 1:* For every calculated normal stress there is a corresponding induced shear stress; the value of the shear stress is equal to half that of the normal stress. *Rule 2:* For every calculated shear stress there is a corresponding induced normal stress; the value of the normal stress is equal to that of the shear stress. The tables of combined stress formulas, below, include equations for calculating both maximum nominal tensile or compressive stresses, and maximum nominal shear stresses.

Formulas for Combined Stresses

(1) Circular Cantilever Beam in Direct Compression and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1.273}{d^2}\left(\frac{8LF_y}{d} - F_x\right)$ $\sigma_b' = -\frac{1.273}{d^2}\left(\frac{8LF_y}{d} + F_x\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(2) Circular Cantilever Beam in Direct Tension and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1.273}{d^2}\left(F_x + \frac{8LF_y}{d}\right)$ $\sigma_b' = \frac{1.273}{d^2}\left(F_x - \frac{8LF_y}{d}\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(3) Rectangular Cantilever Beam in Direct Compression and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1}{bh}\left(\frac{6LF_y}{h} - F_x\right)$ $\sigma_b' = -\frac{1}{bh}\left(\frac{6LF_y}{h} + F_x\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

Copyright 2004, Industrial Press, Inc., New York, NY

(4) Rectangular Cantilever Beam in Direct Tension and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1}{bh}\left(F_x + \frac{6LF_y}{h}\right)$ $\sigma_b' = \frac{1}{bh}\left(F_x - \frac{6LF_y}{h}\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(5) Circular Beam or Shaft in Direct Compression and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = -\frac{1.273}{d^2}\left(\frac{2LF_y}{d} + F_x\right)$ $\sigma_b' = \frac{1.273}{d^2}\left(\frac{2LF_y}{d} - F_x\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(6) Circular Beam or Shaft in Direct Tension and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1.273}{d^2}\left(F_x - \frac{2LF_y}{d}\right)$ $\sigma_b' = \frac{1.273}{d^2}\left(F_x + \frac{2LF_y}{d}\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(7) Rectangular Beam or Shaft in Direct Compression and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = -\frac{1}{bh}\left(\frac{3LF_y}{2h} + F_x\right)$ $\sigma_b' = \frac{1}{bh}\left(-\frac{3LF_y}{2h} - F_x\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(8) Rectangular Beam or Shaft in Direct Tension and Bending:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1}{bh}\left(F_x - \frac{3LF_y}{2h}\right)$ $\sigma_b' = \frac{1}{bh}\left(F_x + \frac{3LF_y}{2h}\right)$	$\tau_a' = 0.5\sigma_a'$ $\tau_b' = 0.5\sigma_b'$

(9) Circular Shaft in Direct Compression and Torsion:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
 a anywhere on surface	$\sigma_a' = -\frac{0.637}{d^2}\left[F \pm \sqrt{F^2 + \left(\frac{8T}{d}\right)^2}\right]$	$\tau_a' = -\frac{0.637}{d^2}\sqrt{F^2 + \left(\frac{8T}{d}\right)^2}$

Copyright 2004, Industrial Press, Inc., New York, NY

(10) Circular Shaft in Direct Tension and Torsion:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
 **a** anywhere on surface	$\sigma_a' = \frac{0.637}{d^2}\left[F \pm \sqrt{F^2 + \left(\frac{8T}{d}\right)^2}\right]$	$\tau_a' = \frac{0.637}{d^2}\sqrt{F^2 + \left(\frac{8T}{d}\right)^2}$

(11) Offset Link, Circular Cross Section, in Direct Tension:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1.273F}{d^2}\left(1 - \frac{8e}{d}\right)$	$\tau_a' = 0.5\sigma_a'$
	$\sigma_b' = \frac{1.273F}{d^2}\left(1 + \frac{8e}{d}\right)$	$\tau_b' = 0.5\sigma_b'$

(12) Offset Link, Circular Cross Section, in Direct Compression:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{1.273F}{d^2}\left(\frac{8e}{d} - 1\right)$	$\tau_a' = 0.5\sigma_a'$
	$\sigma_b' = -\frac{1.273F}{d^2}\left(\frac{8e}{d} + 1\right)$	$\tau_b' = 0.5\sigma_b'$

(13) Offset Link, Rectangular Section, in Direct Tension:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{F}{bh}\left(1 - \frac{6e}{h}\right)$	$\tau_a' = 0.5\sigma_a'$
	$\sigma_b' = \frac{F}{bh}\left(1 + \frac{6e}{h}\right)$	$\tau_b' = 0.5\sigma_b'$

(14) Offset Link, Rectangular Section, in Direct Compression:

Type of Beam and Loading	Maximum Nominal Tensile or Compressive Stress	Maximum Nominal Shear Stress
	$\sigma_a' = \frac{F}{bh}\left(\frac{6e}{h} - 1\right)$	$\tau_a' = 0.5\sigma_a'$
	$\sigma_b' = -\frac{F}{bh}\left(\frac{6e}{h} + 1\right)$	$\tau_b' = 0.5\sigma_b'$

Formulas from the simple and combined stress tables, as well as tension and shear factors, can be applied without change in calculations using metric SI units. Stresses are given in newtons per meter squared (N/m^2) or in N/mm^2.

Copyright 2004, Industrial Press, Inc., New York, NY

Three-Dimensional Stress.— Three-dimensional or triaxial stress occurs in assemblies such as a shaft press-fitted into a gear bore or in pipes and cylinders subjected to internal or external fluid pressure. Triaxial stress also occurs in two-dimensional stress problems if the loads produce normal stresses that are either both tensile or both compressive. In either case the calculated maximum shear stress, based on the corresponding two-dimensional theory, will be less than the true maximum value because of three-dimensional effects. Therefore, if the stress analysis is to be based on the maximum-shear-stress theory of failure, the triaxial stress cubic equation should first be used to calculate the three principal stresses and from these the true maximum shear stress. The following procedure provides the principal maximum normal tensile and compressive stresses and the true maximum shear stress at any point on a body subjected to any combination of loads.

The basis for the procedure is the stress cubic equation

$$S^3 - AS^2 + BS - C = 0$$

in which:

$$A = S_x + S_y + S_z$$

$$B = S_xS_y + S_yS_z + S_zS_x - S_{xy}^2 - S_{yz}^2 - S_{zx}^2$$

$$C = S_xS_yS_z + 2S_{xy}S_{yz}S_{zx} - S_xS_{yz}^2 - S_yS_{zx}^2 - S_zS_{xy}^2$$

and S_x, S_y, etc., are as shown in Fig. 12.

The coordinate system *XYZ* in Fig. 12 shows the positive directions of the normal and shear stress components on an elementary cube of material. Only six of the nine components shown are needed for the calculations: the normal stresses S_x, S_y, and S_z on three of the faces of the cube; and the three shear stresses S_{xy}, S_{yz}, and S_{zx}. The remaining three shear stresses are known because $S_{yx} = S_{xy}$, $S_{zy} = S_{yz}$, and $S_{xz} = S_{zx}$. The normal stresses S_x, S_y, and S_z are shown as positive (tensile) stresses; the opposite direction is negative (compressive). The first subscript of each shear stress identifies the coordinate axis perpendicular to the plane of the shear stress; the second subscript identifies the axis to which the stress is parallel. Thus, S_{xy}, is the shear stress in the *YZ* plane to which the *X* axis is perpendicular, and the stress is parallel to the *Y* axis.



Fig. 12. *XYZ* Coordinate System Showing Positive Directions of Stresses

Step 1. Draw a diagram of the hardware to be analyzed, such as the shaft shown in Fig. 13, and show the applied loads *P*, *T*, and any others.

Copyright 2004, Industrial Press, Inc., New York, NY

Step 2. For any point at which the stresses are to be analyzed, draw a coordinate diagram similar to Fig. 12 and show the magnitudes of the stresses resulting from the applied loads (these stresses may be calculated by using standard basic equations from strength of materials, and should include any stress concentration factors).

Step 3. Substitute the values of the six stresses S_x, S_y, S_z, S_{xy}, S_{yz}, and S_{zx}, including zero values, into the formulas for the quantities A through K. The quantities I, J, and K represent the principal normal stresses at the point analyzed. As a check, if the algebraic sum $I + J + K$ equals A, within rounding errors, then the calculations up to this point should be correct.

$$D = A^2/3 - B \quad E = A \times B/3 - C - 2 \times A^3/27$$

$$F = \sqrt{(D^3/27)} \quad G = \arccos(-E/(2 \times F))$$

$$H = \sqrt{(D/3)} \quad I = 2 \times H \times \cos(G/3) + A/3$$

$$J = 2 \times H \times [\cos(G/3 + 120°)] + A/3 \quad K = 2 \times H \times [\cos(G/3 + 240°)] + A/3$$

Step 4. Calculate the true maximum shear stress, $S_{s(\max)}$ using the formula

$$S_{s(\max)} = 0.5 \times (S_{\text{large}} - S_{\text{small}})$$

in which S_{large} is equal to the algebraically largest of the calculated principal stresses I, J, or K and S_{small} is algebraically the smallest.

The maximum principal normal stresses and the maximum true shear stress calculated above may be used with any of the various theories of failure.



Fig. 13. Example of Triaxial Stress on an Element *a* of Shaft Surface Caused by Load *P*, Torque *T*, and 5000 psi Hydraulic Pressure

Example: A torque T on the shaft in Fig. 13 causes a shearing stress S_{xy} of 8000 psi in the outer fibers of the shaft; and the loads P at the ends of the shaft produce a tensile stress S_x of 4000 psi. The shaft passes through a hydraulic cylinder so that the shaft circumference is subjected to the hydraulic pressure of 5000 psi in the cylinder, causing compressive stresses S_y and S_z of − 5000 psi on the surface of the shaft. Find the maximum shear stress at any point A on the surface of the shaft.

From the statement of the problem $S_x = +4000$ psi, $S_y = -5000$ psi, $S_z = -5000$ psi, $S_{xy} = +8000$ psi, $S_{yz} = 0$ psi, and $S_{zx} = 0$ psi.

$$A = 4000 - 5000 - 5000 = -6000$$

$$B = (4000 \times -5000) + (-5000 \times -5000) + (-5000 \times 4000) - 8000^2 - 0^2 - 0^2 = -7.9 \times 10^7$$

$$C = (4000 \times -5000 \times -5000) + 2 \times 8000 \times 0 \times 0 - (4000 \times 0^2) - (-5000 \times 0^2) - (-5000 \times 8000^2) = 4.2 \times 10^{11}$$

$$D = A^2/3 - B = 9.1 \times 10^7 \quad E = A \times B/3 - C - 2 \times A^3/27 = -2.46 \times 10^{11}$$

$$F = \sqrt{(D^3/27)} = 1.6706 \times 10^{11} \quad G = \arccos(-E/(2 \times F)) = 42.586 \text{ degrees}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$H = \sqrt{(D/3)} = 5507.57 \quad I = 2 \times H \times \cos(G/3 + A/3 = 8678.8, \text{say}, 8680 \text{ psi}$
$J = 2 \times H \times [\cos(G/3 + 120°)] + A/3 = -9678.78, \text{say}, -9680 \text{ psi}$
$K = 2 \times H [\cos(G/3 + 240°)] + A/3 = -5000 \text{ psi}$

Check: $8680 + (-9680) + (-5000) = -6000$ within rounding error.

$S_{s(\max)} = 0.5 \times (8680 - (-9680)) = 9180$ psi

Sample Calculations.— The following examples illustrate some typical strength of materials calculations, using both English and metric SI units of measurement.

Example 1(a): A round bar made from SAE 1025 low carbon steel is to support a direct tension load of 50,000 pounds. Using a factor of safety of 4, and assuming that the stress concentration factor $K = 1$, a suitable standard diameter is to be determined. Calculations are to be based on a yield strength of 40,000 psi.

Because the factor of safety and strength of the material are known, the allowable working stress s_w may be calculated using Equation (1): 40,000/4 = 10,000 psi. The relationship between working stress s_w and nominal stress σ is given by Equation (2). Since $K = 1$, σ = 10,000 psi. Applying Equation (9) in the *Table of Simple Stresses*, the area of the bar can be solved for: A = 50,000/10,000 or 5 square inches. The next largest standard diameter corresponding to this area is $2^{9}/_{16}$ inches.

***Example 1(b):* A similar example to that given in 1(a), using metric SI units is as follows. A round steel bar of 300 meganewtons/meter ^{2} yield strength, is to withstand a direct tension of 200 kilonewtons. Using a safety factor of 4, and assuming that the stress concentration factor $K = 1$, a suitable diameter is to be determined.**

Because the factor of safety and the strength of the material are known, the allowable working stress s_w may be calculated using Equation (1): 300/4 = 75 mega-newtons/meter^2. The relationship between working stress and nominal stress σ is given by Equation (2). Since $K = 1$, σ = 75 MN/m^2. Applying Equation (9) in the , the area of the bar can be determined from:

$$A = \frac{200 \text{ kN}}{75 \text{ MN/m}^2} = \frac{200{,}000 \text{ N}}{75{,}000{,}000 \text{ N/m}^2} = 0.00267 \text{ m}^2$$

The diameter corresponding to this area is 0.058 meters, or approximately 0.06 m.

Millimeters can be employed in the calculations in place of meters, providing the treatment is consistent throughout. In this instance the diameter would be 60 mm.

***Note:* If the tension in the bar is produced by hanging a mass of M kilograms from its end, the value is Mg newtons, where g = approximately 9.81 meters per second^2.**

Example 2(a): What would the total elongation of the bar in Example 1(a) be if its length were 60 inches? Applying Equation (17),

$$e = \frac{50{,}000 \times 60}{5.157 \times 30{,}000{,}000} = 0.019 \text{ inch}$$

***Example 2(b):* What would be the total elongation of the bar in Example 1(b) if its length were 1.5 meters? The problem is solved by applying Equation (17) in which F = 200 kilonewtons; L = 1.5 meters; $A = \pi 0.06^2/4 = 0.00283$ m^2. Assuming a modulus of elasticity E of 200 giganewtons/meter^2, then the calculation is:**

$$e = \frac{200{,}000 \times 1.5}{0.00283 \times 200{,}000{,}000{,}000} = 0.000530 \text{ m}$$

The calculation is less unwieldy if carried out using millimeters in place of meters; then F = 200 kN; L = 1500 mm; A = 2830 mm^2, and E = 200,000 N/mm^2. Thus:

$$e = \frac{200{,}000 \times 1500}{2830 \times 200{,}000} = 0.530 \text{ mm}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Example 3(a): Determine the size for the section of a square bar which is to be held firmly at one end and is to support a load of 3000 pounds at the outer end. The bar is to be 30 inches long and is to be made from SAE 1045 medium carbon steel with a yield point of 60,000 psi. A factor of safety of 3 and a stress concentration factor of 1.3 are to be used.

From Equation (1) the allowable working stress $s_w = 60{,}000/3 = 20{,}000$ psi. The applicable equation relating working stress and nominal stress is Equation (2); hence, $\sigma = 20{,}000/1.3 = 15{,}400$ psi. The member must be treated as a cantilever beam subject to a bending moment of 30×3000 or 90,000 inch-pounds. Solving Equation (11) in the for section modulus: $Z = 90{,}000/15{,}400 = 5.85$ inch^3. The section modulus for a square section with neutral axis equidistant from either side is $a^3/6$, where a is the dimension of the square, so $a = \sqrt[3]{35.1} = 3.27$ inches. The size of the bar can therefore be $3\frac{5}{16}$ inches.

***Example 3(b):* A similar example to that given in Example 3(a), using metric SI units is as follows. Determine the size for the section of a square bar which is to be held firmly at one end and is to support a load of 1600 kilograms at the outer end. The bar is to be 1 meter long, and is to be made from steel with a yield strength of 500 newtons/mm^2. A factor of safety of 3, and a stress concentration factor of 1.3 are to be used. The calculation can be performed using millimeters throughout.**

From Equation (1) the allowable working stress $s_w = 500$ N/mm^2/3 = 167 N/mm^2. The formula relating working stress and nominal stress is Equation (2); hence $\sigma = 167/1.3 = 128$ N/mm^2. Since a mass of 1600 kg equals a weight of 1600 g newtons, where $g = 9.81$ meters/second^2, the force acting on the bar is 15,700 newtons. The bending moment on the bar, which must be treated as a cantilever beam, is thus 1000 mm $\times$ 15,700 N = 15,700,000 N $\cdot$ mm. Solving Equation (11) in the for section modulus: $Z = M/\sigma = 15{,}700{,}000/128 = 123{,}000$ mm^3. Since the section modulus for a square section with neutral axis equidistant from either side is $a^3/6$, where a is the dimension of the square,

$$a = \sqrt[3]{6 \times 123{,}000} = 90.4 \text{ mm}$$

Example 4(a): Find the working stress in a 2-inch diameter shaft through which a transverse hole $\frac{1}{4}$ inch in diameter has been drilled. The shaft is subject to a torsional moment of 80,000 inch-pounds and is made from hardened steel so that the index of sensitivity $q = 0.2$.

The polar section modulus is calculated using the equation shown in the stress concentration curve for a Round Shaft in Torsion with Transverse Hole, Fig. 7, page 211.

$$\frac{J}{c} = Z_p = \frac{\pi \times 2^3}{16} - \frac{2^2}{4 \times 6} = 1.4 \text{ inches}^3$$

The nominal shear stress due to the torsion loading is computed using Equation (16) in the :

$$\tau = 80{,}000/1.4 = 57{,}200 \text{ psi}$$

Referring to the previously mentioned stress concentration curve on page 211, K_t is 2.82 since d/D is 0.125. The stress concentration factor may now be calculated by means of Equation (8): $K = 1 + 0.2(2.82 - 1) = 1.36$. Working stress calculated with Equation (3) is $s_w = 1.36 \times 57{,}200 = 77{,}800$ psi.

***Example 4(b):* A similar example to that given in 4(a), using metric SI units is as follows. Find the working stress in a 50 mm diameter shaft through which a transverse hole 6 mm in diameter has been drilled. The shaft is subject to a torsional moment of 8000 newton-meters, and has an index of sensitivity of $q = 0.2$. If the calculation is made in millimeters, the torsional moment is 8,000,000 N $\cdot$ mm.**

The polar section modulus is calculated using the equation shown in the stress concentration curve for a Round Shaft in Torsion with Transverse Hole, Fig. 7, page 211:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{J}{c} = Z_p = \frac{\pi \times 50^3}{16} - \frac{6 \times 50^2}{6} = 24{,}544 - 2500 = 22{,}044 \text{ mm}^3$$

The nominal shear stress due to torsion loading is computed using Equation (16) in the :

$$\tau = 8{,}000{,}000/22{,}000 = 363 \text{ N/mm}^2 = 363 \text{ megapascals}$$

Referring to the previously mentioned stress concentration curve on page 211, K_t is 2.85, since $a/d = 6/50 = 0.12$. The stress concentration factor may now be calculated by means of Equation (8): $K = 1 + 0.2(2.85 - 1) = 1.37$. From Equation (3), working stress $s_w = 1.37 \times 363 = 497$ N/mm^2 = 497 megapascals.

Example 5(a): For Case 3 in the *Tables of Combined Stresses*, calculate the least factor of safety for a 5052-H32 aluminum beam is 10 inches long, one inch wide, and 2 inches high. Yield strengths are 23,000 psi tension; 21,000 psi compression; 13,000 psi shear. The stress concentration factor is 1.5; F_y is 600 lbs; F_x 500 lbs.

From *Tables of Combined Stresses*, Case 3:

$$\sigma_b' = -\frac{1}{1 \times 2}\left(\frac{6 \times 10 \times 600}{2} + 500\right) = -9250 \text{ psi (in compression)}$$

The other formulas for Case 3 give $\sigma_a' = 8750$ psi (in tension); $\tau_a' = 4375$ psi, and $\tau_b' = 4625$ psi. Using Equation (4) for the nominal compressive stress of 9250 psi: $S_w = 1.5 \times 9250 = 13{,}900$ psi. From Equation (1) $f_s = 21{,}000/13{,}900 = 1.51$. Applying Equations (1), (4) and (5) in appropriate fashion to the other calculated nominal stress values for tension and shear will show that the factor of safety of 1.51, governed by the compressive stress at b on the beam, is minimum.

***Example 5(b):* What maximum F can be applied in Case 3 if the aluminum beam is 200 mm long; 20 mm wide; 40 mm high; $\theta = 30°$; $f_s = 2$, governing for compression, $K = 1.5$, and $S_m = 144$N/mm^2 for compression.**

From Equation (1) $S_w = -144$N/mm^2. Therefore, from Equation (4), $\sigma_b' = -72/1.5 = -48$N/mm^2. Since $F_x = F \cos 30° = 0.866F$, and $F_y = F \sin 30° = 0.5F$:

$$-48 = -\frac{1}{20 \times 40}\left(0.866F + \frac{6 \times 200 \times 0.5F}{40}\right) \qquad F = 2420 \text{ N}$$

Stresses and Deflections in a Loaded Ring.— For *thin* rings, that is, rings in which the dimension d shown in the accompanying diagram is small compared with D, the maximum stress in the ring is due primarily to bending moments produced by the forces P. The maximum stress due to bending is:

$$S = \frac{PDd}{4\pi I} \tag{24}$$



For a ring of circular cross section where d is the diameter of the bar from which the ring is made,

$$S = \frac{1.621PD}{d^3} \quad \text{or} \quad P = \frac{0.617Sd^3}{D} \tag{25}$$

The increase in the vertical diameter of the ring due to load P is:

$$\text{Increase in vertical diameter} = \frac{0.0186PD^3}{EI} \text{ inches} \tag{26}$$

Copyright 2004, Industrial Press, Inc., New York, NY

The *decrease* in the horizontal diameter will be about 92% of the increase in the vertical diameter given by Formula (26). In the above formulas, P = load on ring in pounds; D = mean diameter of ring in inches; S = tensile stress in pounds per square inch, I = moment of inertia of section in inches^4; and E = modulus of elasticity of material in pounds per square inch.

Strength of Taper Pins.— The mean diameter of taper pin required to safely transmit a known torque, may be found from the formulas:

$$d = 1.13\sqrt{\frac{T}{DS}} \qquad (27) \qquad \text{and} \qquad d = 283\sqrt{\frac{\text{HP}}{NDS}} \qquad (28a)$$

in which formulas T = torque in inch-pounds; S = safe unit stress in pounds per square inch; HP = horsepower transmitted; N = number of revolutions per minute; and d and D denote dimensions shown in the figure.

Formula (27) can be used with metric SI units where d and D denote dimensions shown in the figure in millimeters; T = torque in newton-millimeters (N · mm); and S = safe unit stress in newtons per millimeter^2 (N/mm^2). Formula (28a) is replaced by:

$$d = 110.3\sqrt{\frac{\text{Power}}{NDS}} \qquad (28b)$$

where d and D denote dimensions shown in the figure in millimeters; S = safe unit stress in N/mm^2; N = number of revolutions per minute, and Power = power transmitted in watts.

Example 6(a): A lever secured to a 2-inch round shaft by a steel tapered pin (dimension d = ⅜ inch) has a pull of 50 pounds at a 30-inch radius from shaft center. Find S, the unit working stress on the pin. By rearranging Formula (27):



$$S = \frac{1.27T}{Dd^2} = \frac{1.27 \times 50 \times 30}{2 \times \left(\frac{3}{8}\right)^2} \cong 6770 \text{ psi}$$

6770 pounds per square inch is a safe unit working stress for machine steel in shear.

Let P = 50 pounds, R = 30 inches, D = 2 inches, and S = 6000 pounds unit working stress. Using Formula (27) to find d:

$$d = 1.13\sqrt{\frac{T}{DS}} = 1.13\sqrt{\frac{50 \times 30}{2 \times 6000}} = 1.13\sqrt{\frac{1}{8}} = 0.4 \text{ inch}$$

***Example 6(b):* A similar example using SI units is as follows: A lever secured to a 50 mm round shaft by a steel tapered pin (d = 10 mm) has a pull of 200 newtons at a radius of 800 mm. Find S, the working stress on the pin. By rearranging Formula (27):**

$$S = \frac{1.27T}{Dd^2} = \frac{1.27 \times 200 \times 800}{50 \times 10^2} = 40.6 \text{ N/mm}^2 = 40.6 \text{ megapascals}$$

If a shaft of 50 mm diameter is to transmit power of 12 kilowatts at a speed of 500 rpm, find the mean diameter of the pin for a material having a safe unit stress of 40 N/mm^2. Using Equation (28b):

$$d = 110.3\sqrt{\frac{\text{Power}}{NDS}} \qquad \text{then } d = 110.3\sqrt{\frac{12{,}000}{500 \times 50 \times 40}}$$

$$= 110.3 \times 0.1096 = 12.09 \text{ mm}$$

Copyright 2004, Industrial Press, Inc., New York, NY

PROPERTIES OF BODIES

Center of Gravity

Center of Gravity.— The center of gravity of a body, volume, area, or line is that point at which if the body, volume, area, or line were suspended it would be perfectly balanced in all positions. For symmetrical bodies of uniform material it is at the geometric center. The center of gravity of a uniform round rod, for example, is at the center of its diameter halfway along its length; the center of gravity of a sphere is at the center of the sphere. For solids, areas, and arcs that are not symmetrical, the determination of the center of gravity may be made experimentally or may be calculated by the use of formulas.

The tables that follow give such formulas for some of the more important shapes. For more complicated and unsymmetrical shapes the methods outlined on page 231 may be used.

Example: A piece of wire is bent into the form of a semi-circular arc of 10-inch radius. How far from the center of the arc is the center of gravity located?

Accompanying the *Circular Arc* diagram on page 226 is a formula for the distance from the center of gravity of an arc to the center of the arc: $a = 2r \div \pi$. Therefore,

$$a = 2 \times 10 \div 3.1416 = 6.366 \text{ inches}$$

Formulas for Center of Gravity

Triangle:



Perimeter

If A, B and C are the middle points of the sides of the triangle, then the center of gravity is at the center of the circle that can be inscribed in triangle ABC. The distance d of the center of gravity from side a is:

$$d = \frac{h(b+c)}{2(a+b+c)}$$

where h is the height perpendicular to a.



Area

The center of gravity is at the intersection of lines AD and BE, which bisect the sides BC and AC. The perpendicular distance from the center of gravity to any one of the sides is equal to one-third the height perpendicular to that side. Hence, $a = h \div 3$.

Perimeter or Area of a Parallelogram :



The center of gravity is at the intersection of the diagonals.

Copyright 2004, Industrial Press, Inc., New York, NY

Area of Trapezoid:



The center of gravity is on the line joining the middle points of parallel lines *AB* and *DE*.

$$c = \frac{h(a+2b)}{3(a+b)} \qquad d = \frac{h(2a+b)}{3(a+b)}$$

$$e = \frac{a^2+ab+b^2}{3(a+b)}$$

The trapezoid can also be divided into two triangles. The center of gravity is at the intersection of the line joining the centers of gravity of the triangles, and the middle line *FG*.

Any Four-sided Figure :



Two cases are possible, as shown in the illustration. To find the center of gravity of the four-sided figure *ABCD*, each of the sides is divided into three equal parts. A line is then drawn through each pair of division points next to the points of intersection *A*, *B*, *C*, and *D* of the sides of the figure. These lines form a parallelogram *EFGH*; the intersection of the diagonals *EG* and *FH* locates center of gravity.

Circular Arc:



The center of gravity is on the line that bisects the arc, at a distance $a = \frac{r \times c}{l} = \frac{c(c^2+4h^2)}{8lh}$ from the center of the circle.

For an arc equal to one-half the periphery:

$$a = 2r \div \pi = 0.6366r$$

For an arc equal to one-quarter of the periphery:

$$a = 2r\sqrt{2} \div \pi = 0.9003r$$

For an arc equal to one-sixth of the periphery:

$$a = 3r \div \pi = 0.9549r$$



An approximate formula is very nearly exact for all arcs less than one-quarter of the periphery is:

$$a = \tfrac{2}{3}h$$

The error is only about one per cent for a quarter circle, and decreases for smaller arcs.

Circle Segment :



The distance of the center of gravity from the center of the circle is:

$$b = \frac{c^3}{12A} = \tfrac{2}{3} \times \frac{r^3 \sin^3\alpha}{A}$$

in which A = area of segment.

Copyright 2004, Industrial Press, Inc., New York, NY

Circle Sector :



Distance b from center of gravity to center of circle is:

$$b = \frac{2rc}{3l} = \frac{r^2c}{3A} = 38.197\frac{r\sin\alpha}{\alpha}$$

in which A = area of sector, and α is expressed in degrees.

For the area of a half-circle:

$$b = 4r \div 3\pi = 0.4244r$$

For the area of a quarter circle:

$$b = 4\sqrt{2} \times r \div 3\pi = 0.6002r$$

For the area of a sixth of a circle:

$$b = 2r \div \pi = 0.6366r$$

Part of Circle Ring :



Distance b from center of gravity to center of circle is:

$$b = 38.197\frac{(R^3 - r^3)\sin\alpha}{(R^2 - r^2)\alpha}$$

Angle α is expressed in degrees.

Spandrel or Fillet :



Area $= 0.2146R^2$

$x = 0.2234R$

$y = 0.2234R$

Segment of an Ellipse :



The center of gravity of an elliptic segment ABC, symmetrical about one of the axes, coincides with the center of gravity of the segment DBF of a circle, the diameter of which is equal to that axis of the ellipse about which the elliptic segment is symmetrical.

Spherical Surface of Segments and Zones of Spheres :



Distances a and b which determine the center of gravity, are:

$$a = \frac{h}{2} \qquad b = \frac{H}{2}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Area of a Parabola :



For the complete parabolic area, the center of gravity is on the center line or axis, and

$$a = \frac{3h}{5}$$

For one-half of the parabola:

$$a = \frac{3h}{5} \text{ and } b = \frac{3w}{8}$$

For the complement area *ABC*:

$$c = 0.3h \text{ and } d = 0.75w$$

Cylinder :



The center of gravity of a solid cylinder (or prism) with parallel end surfaces, is located at the middle of the line that joins the centers of gravity of the end surfaces.

The center of gravity of a cylindrical surface or shell, with the base or end surface in one end, is found from:

$$a = \frac{2h^2}{4h + d}$$

The center of gravity of a cylinder cut off by an inclined plane is located by:

$$a = \frac{h}{2} + \frac{r^2 \tan^2 \alpha}{8h} \qquad b = \frac{r^2 \tan \alpha}{4h}$$

where α is the angle between the obliquely cut off surface and the base surface.

Portion of Cylinder :



For a solid portion of a cylinder, as shown, the center of gravity is determined by:

$$a = \tfrac{3}{16} \times 3.1416r \qquad b = \tfrac{3}{32} \times 3.1416h$$

For the cylindrical surface only:

$$a = \tfrac{1}{4} \times 3.1416r \qquad b = \tfrac{1}{8} \times 3.1416h$$

If the cylinder is hollow, the center of gravity of the solid shell is found by:

$$a = \tfrac{3}{16} \times 3.1416 \frac{R^4 - r^4}{R^3 - r^3}$$

$$b = \tfrac{3}{32} \times 3.1416 \frac{H^4 - h^4}{H^3 - h^3}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Center of Gravity of Two Bodies :



If the weights of the bodies are P and Q, and the distance between their centers of gravity is a, then:

$$b = \frac{Qa}{P+Q} \qquad c = \frac{Pa}{P+Q}$$

Pyramid :



In a solid pyramid the center of gravity is located on the line joining the apex with the center of gravity of the base surface, at a distance from the base equal to one-quarter of the height; or $a = \frac{1}{4}h$.

The center of gravity of the triangular surfaces forming the pyramid is located on the line joining the apex with the center of gravity of the base surface, at a distance from the base equal to one-third of the height; or $a = \frac{1}{3}h$.

Frustum of Pyramid :



The center of gravity is located on the line that joins the centers of gravity of the end surfaces. If A_1 = area of base surface, and A_2 area of top surface,

$$a = \frac{h(A_1 + 2\sqrt{A_1 \times A_2} + 3A_2)}{4(A_1 + \sqrt{A_1 \times A_2} + A_2)}$$

Cone :



The same rules apply as for the pyramid.

For the solid cone:

$$a = \tfrac{1}{4}h$$

For the conical surface:

$$a = \tfrac{1}{3}h$$

Frustum of Cone :



The same rules apply as for the frustum of a pyramid. For a solid frustum of a circular cone the formula below is also used:

$$a = \frac{h(R^2 + 2Rr + 3r^2)}{4(R^2 + Rr + r^2)}$$

The location of the center of gravity of the conical surface of a frustum of a cone is determined by:

$$a = \frac{h(R + 2r)}{3(R + r)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Wedge :



The center of gravity is on the line joining the center of gravity of the base with the middle point of the edge, and is located at:

$$a = \frac{h(b+c)}{2(2b+c)}$$

Paraboloid :



The center of gravity of a solid paraboloid of rotation is at:

$$a = \tfrac{1}{3}h$$

Half of a Hollow Sphere :



The center of gravity is located at:

$$a = \frac{3(R^4 - r^4)}{8(R^3 - r^3)}$$

Spherical Segment :



The center of gravity of a solid segment is determined by:

$$a = \frac{3(2r-h)^2}{4(3r-h)}$$

$$b = \frac{h(4r-h)}{4(3r-h)}$$

For a half-sphere, $a = b = \tfrac{3}{8}r$

Spherical Sector :



The center of gravity of a solid sector is at:

$$a = \tfrac{3}{8}(1+\cos\alpha)r = \tfrac{3}{8}(2r-h)$$

Segment of Ellipsoid or Spheroid :



The center of gravity of a solid segment *ABC*, symmetrical about the axis of rotation, coincides with the center of gravity of the segment *DBF* of a sphere, the diameter of which is equal to the axis of rotation of the spheroid.

Copyright 2004, Industrial Press, Inc., New York, NY

Center of Gravity of Figures of any Outline.— If the figure is symmetrical about a center line, as in Fig. 1, the center of gravity will be located on that line. To find the exact location on that line, the simplest method is by taking moments with reference to any convenient axis at right angles to this center line. Divide the area into geometrical figures, the centers of gravity of which can be easily found. In the example shown, divide the figure into three rectangles KLMN, EFGH and OPRS. Call the areas of these rectangles A, B and C, respectively, and find the center of gravity of each. Then select any convenient axis, as X–X, at right angles to the center line Y–Y, and determine distances a, b and c. The distance y of the center of gravity of the complete figure from the axis X–X is then found from the equation:

$$y = \frac{Aa + Bb + Cc}{A + B + C}$$



Fig. 1.



Fig. 2.

As an example, assume that the area A is 24 square inches, B, 14 square inches, and C, 16 square inches, and that $a = 3$ inches, $b = 7.5$ inches, and $c = 12$ inches. Then:

$$y = \frac{24 \times 3 + 14 \times 7.5 + 16 \times 12}{24 + 14 + 16} = \frac{369}{54} = 6.83 \text{ inches}$$

If the figure, the center of gravity of which is to be found, is not symmetrical about any axis, as in Fig. 2, then moments must be taken with relation to two axes X–X and Y–Y, centers of gravity of which can be easily found, the same as before. The center of gravity is determined by the equations:

$$x = \frac{Aa_1 + Bb_1 + Cc_1}{A + B + C} \qquad y = \frac{Aa + Bb + Cc}{A + B + C}$$

As an example, let $A = 14$ square inches, $B = 18$ square inches, and $C = 20$ square inches. Let $a = 3$ inches, $b = 7$ inches, and $c = 11.5$ inches. Let $a_1 = 6.5$ inches, $b_1 = 8.5$ inches, and $c_1 = 7$ inches. Then:

$$x = \frac{14 \times 6.5 + 18 \times 8.5 + 20 \times 7}{14 + 18 + 20} = \frac{384}{52} = 7.38 \text{ inches}$$

$$y = \frac{14 \times 3 + 18 \times 7 + 20 \times 11.5}{14 + 18 + 20} = \frac{398}{52} = 7.65 \text{ inches}$$

In other words, the center of gravity is located at a distance of 7.65 inches from the axis X–X and 7.38 inches from the axis Y–Y.

Copyright 2004, Industrial Press, Inc., New York, NY

Radius of Gyration

The radius of gyration with reference to an axis is that distance from the axis at which the entire mass of a body may be considered as concentrated, the moment of inertia, meanwhile, remaining unchanged. If W is the weight of a body; J_M, its moment of inertia with respect to some axis; and k_o, the radius of gyration with respect to the same axis, then:

$$k_o = \sqrt{\frac{J_M g}{W}} \qquad \text{and} \qquad J_M = \frac{W k_o^2}{g}$$

When using metric SI units, the formulas are:

$$\boldsymbol{k_o = \sqrt{\frac{J_M}{M}}} \qquad \textbf{and} \qquad \boldsymbol{J_M = M k_o^2}$$

where k_o = the radius of gyration in meters, J_M = kilogram-meter squared, and M = mass in kilograms.

To find the radius of gyration of an area, such as for the cross-section of a beam, divide the moment of inertia of the area by the area and extract the square root.

When the axis, the reference to which the radius of gyration is taken, passes through the center of gravity, the radius of gyration is the least possible and is called the *principal* radius of gyration. If k is the radius of gyration with respect to such an axis passing through the center of gravity of a body, then the radius of gyration, k_o, with respect to a parallel axis at a distance d from the gravity axis is given by: $k_o = \sqrt{k^2 + d^2}$

Tables of radii of gyration for various bodies and axes follows.

Formulas for Radius of Gyration

Bar of Small Diameter:



$k = 0.5773l$
$k^2 = \frac{1}{3}l^2$

Axis at end



$k = 0.2886l$
$k^2 = \frac{1}{12}l^2$

Axis at center

Bar of Small Diameter Bent to Circular Shape:



$k = 0.7071r$
$k^2 = \frac{1}{2}r^2$

Axis, a diameter of the ring



$k = r$
$k^2 = r^2$

Axis through center of ring

Parallelogram (Thin Flat Plate):



$k = 0.5773h$
$k^2 = \frac{1}{3}h^2$

Axis at base



$k = 0.2886h$
$k^2 = \frac{1}{12}h^2$

Axis at mid-height

Copyright 2004, Industrial Press, Inc., New York, NY

Thin Circular Disk:



$$k = 0.7071r$$
$$k^2 = \frac{1}{2}r^2$$

Axis through center



$$k = \frac{1}{2}r$$
$$k^2 = \frac{1}{4}r^2$$

Axis its diameter

Thin, Flat, Circular Ring :



$$k = \tfrac{1}{4}\sqrt{D^2 + d^2}$$
$$k^2 = \frac{D^2 + d^2}{16}$$

Axis its diameter

Cylinder:



$$k = \frac{r}{\sqrt{2}}$$
$$k^2 = \frac{1}{2}r^2$$

Axis through center



$$k = \frac{\sqrt{l^2 + 3r^2}}{\sqrt{12}}$$
$$k^2 = \frac{l^2}{12} + \frac{r^2}{4}$$

Axis, diameter at mid-length



$$k = \frac{\sqrt{4l^2 + 3r^2}}{\sqrt{12}}$$
$$k^2 = \frac{l^2}{3} + \frac{r^2}{4}$$

Axis, diameter at end



$$k = \sqrt{a^2 + \tfrac{1}{2}r^2}$$
$$k^2 = a^2 + \tfrac{1}{2}r^2$$

Axis at a distance

Parallelepiped:



$$k = \frac{\sqrt{4l^2 + b^2}}{\sqrt{12}}$$
$$k^2 = \frac{4l^2 + b^2}{12}$$

Axis at one end, central



$$k = \sqrt{\frac{4l^2 + b^2}{12} + a^2 + al}$$

Axis at distance from end

Copyright 2004, Industrial Press, Inc., New York, NY

Rectangular Prism:



Axis through center

$$k = 0.577\sqrt{b^2 + c^2}$$
$$k^2 = \tfrac{1}{3}(b^2 + c^2)$$

Thin Hollow Cylinder:



Axis, diameter at mid-length

$$k = 0.289\sqrt{l^2 + 6r^2}$$
$$k^2 = \frac{l^2}{12} + \frac{r^2}{2}$$

Hollow Cylinder:



Axis, diameter at mid-length

$$k = \frac{\sqrt{l^2 + 3(R^2 + r^2)}}{\sqrt{12}}$$
$$k^2 = \frac{l^2}{12} + \frac{R^2 + r^2}{4}$$



Longitudinal Axis

$$k = \frac{\sqrt{R^2 + r^2}}{\sqrt{2}}$$
$$k^2 = \tfrac{1}{2}(R^2 + r^2)$$

Cone:



Axis at base $k = \sqrt{\dfrac{2h^2 + 3r^2}{20}}$

Axis at apex $k_1 = \sqrt{\dfrac{12h^2 + 3r^2}{20}}$



Axis through its center line

$$k = 0.5477r$$
$$k^2 = 0.3r^2$$

Frustum of Cone:



Axis at large end

$$k = \sqrt{\frac{h^2}{10}\left(\frac{R^2 + 3Rr + 6r^2}{R^2 + Rr + r^2}\right) + \frac{3}{20}\left(\frac{R^5 - r^5}{R^3 - r^3}\right)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Sphere:



$k = 0.6325r$

$k^2 = \frac{2}{5}r^2$

Axis its diameter



$k = \sqrt{a^2 + \frac{2}{5}r^2}$

$k^2 = a^2 + \frac{2}{5}r^2$

Axis at a distance

Hollow Sphere and Thin Spherical Shell:



$k = 0.6325\sqrt{\frac{R^5 - r^5}{R^3 - r^3}}$

$k^2 = \frac{2(R^5 - r^5)}{5(R^3 - r^3)}$

Hollow Sphere
Axis its diameter



$k = 0.8165r$

$k^2 = \frac{2}{3}r^2$

Thin Spherical Shell

Ellipsoid and Paraboloid:



$k = \frac{\sqrt{b^2 + c^2}}{\sqrt{5}}$

$k^2 = \frac{1}{5}(b^2 + c^2)$

Ellipsoid
Axis through center



$k = 0.5773r$

$k^2 = \frac{1}{3}r^2$

Paraboloid
Axis through center

Center and Radius of Oscillation.— If a body oscillates about a horizontal axis which does not pass through its center of gravity, there will be a point on the line drawn from the center of gravity, perpendicular to the axis, the motion of which will be the same as if the whole mass were concentrated at that point. This point is called the *center of oscillation*. The *radius of oscillation* is the distance between the center of oscillation and the point of suspension. In a straight line, or in a bar of small diameter, suspended at one end and oscillating about it, the center of oscillation is at two-thirds the length of the rod from the end by which it is suspended.

When the vibrations are perpendicular to the plane of the figure, and the figure is suspended by the vertex of an angle or its uppermost point, the radius of oscillation of an isosceles triangle is equal to $\frac{3}{4}$ of the height of the triangle; of a circle, $\frac{5}{8}$ of the diameter; of a parabola, $\frac{5}{7}$ of the height.

If the vibrations are in the plane of the figure, then the radius of oscillation of a circle equals $\frac{3}{4}$ of the diameter; of a rectangle, suspended at the vertex of one angle, $\frac{2}{3}$ of the diagonal.

Center of Percussion.— For a body that moves without rotation, the resultant of all the forces acting on the body passes through the center of gravity. On the other hand, for a body that rotates about some *fixed axis*, the resultant of all the forces acting on it does not pass through the center of gravity of the body but through a point called the *center of percus-*

Copyright 2004, Industrial Press, Inc., New York, NY

sion. The center of percussion is useful in determining the position of the resultant in mechanics problems involving angular acceleration of bodies about a fixed axis.

Finding the Center of Percussion when the Radius of Gyration and the Location of the Center of Gravity are Known: The center of percussion lies on a line drawn through the center of rotation and the center of gravity. The distance from the axis of rotation to the center of percussion may be calculated from the following formula

$$q = k_o^2 \div r$$

in which q = distance from the axis of rotation to the center of percussion; k_o = the radius of gyration of the body with respect to the axis of rotation; and r = the distance from the axis of rotation to the center of gravity of the body.

Moment of Inertia

An important property of areas and solid bodies is the moment of inertia. Standard formulas are derived by multiplying elementary particles of area or mass by the squares of their distances from reference axes. Moments of inertia, therefore, depend on the location of reference axes. Values are minimum when these axes pass through the centers of gravity.

Three kinds of moments of inertia occur in engineering formulas:

1) *Moments of inertia of plane area*, I, in which the axis is in the plane of the area, are found in formulas for calculating deflections and stresses in beams. When dimensions are given in inches, the units of I are inches^4. A table of formulas for calculating the I of common areas can be found beginning on page 238.

2) *Polar moments of inertia of plane areas*, J, in which the axis is at right angles to the plane of the area, occur in formulas for the torsional strength of shafting. When dimensions are given in inches, the units of J are inches^4. If moments of inertia, I, are known for a plane area with respect to both x and y axes, then the polar moment for the z axis may be calculated using the equation, $J_z = I_x + I_y$

A table of formulas for calculating J for common areas can be found on page 249 in this section.

When metric SI units are used, the formulas referred to in (1) and (2) above, are valid if the dimensions are given consistently in meters or millimeters. If meters are used, the units of I and J are in meters^4; if millimeters are used, these units are in millimeters^4.

3) *Polar moments of inertia of masses*, J_M*, appear in dynamics equations involving rotational motion. J_M bears the same relationship to angular acceleration as mass does to linear acceleration. If units are in the foot-pound-second system, the units of J_M are ft-lbs-sec^2 or slug-ft^2. (1 slug = 1 pound second^2 per foot.) If units are in the inch-pound-second system, the units of J_M are inch-lbs-sec^2.

If metric SI values are used, the units of J_M are kilogram-meter squared. Formulas for calculating J_M for various bodies are given beginning on page 250. If the polar moment of inertia J is known for the area of a body of constant cross section, J_M may be calculated using the equation,

$$J_M = \frac{\rho L}{g} J$$

where ρ is the density of the material, L the length of the part, and g the gravitational constant. If dimensions are in the foot-pound-second system, ρ is in lbs per ft^3, L is in ft, g is

* In some books the symbol I denotes the polar moment of inertia of masses; J_M is used in this handbook to avoid confusion with moments of inertia of plane areas.

Copyright 2004, Industrial Press, Inc., New York, NY

32.16 ft per sec^2, and J is in ft^4. If dimensions are in the inch-pound-second system, ρ is in lbs per in^3, L is in inches, g is 386 inches per sec^2, and J is in inches^4.

Using metric SI units, the above formula becomes $J_M = \rho LJ$, where ρ = the density in kilograms/meter^3, L = the length in meters, and J = the polar moment of inertia in meters^4. The units of J_M are kg · m^2.

Moment of Inertia of Built-up Sections.— The usual method of calculating the moment of inertia of a built-up section involves the calculations of the moment of inertia for each element of the section about its own neutral axis, and the transferring of this moment of inertia to the previously found neutral axis of the whole built-up section. A much simpler method that can be used in the case of any section which can be divided into rectangular elements bounded by lines parallel and perpendicular to the neutral axis is the so-called tabular method based upon the formula: $I = b(h_1^3 - h^3)/3$ in which I = the moment of inertia about axis DE, Fig. 1, and b, h and h_1 are dimensions as given in the same illustration.



Fig. 1.


Fig. 2.



Fig. 3.

Example: The method may be illustrated by applying it to the section shown in Fig. 2, and for simplicity of calculation shown "massed" in Fig. 3. The calculation may then be tabulated as shown in the accompanying table. The distance from the axis DE to the neutral axis xx (which will be designated as d) is found by dividing the sum of the geometrical moments by the area. The moment of inertia about the neutral axis is then found in the usual way by subtracting the area multiplied by d^2 from the moment of inertia about the axis DE.

Tabulated Calculation of Moment of Inertia

Section	Breadth b	Height h_1	Area $b(h_1 - h)$	h_1^2	Moment $\frac{b(h_1^2 - h^2)}{2}$	h_1^3	I about axis DE $\frac{b(h_1^3 - h^3)}{3}$
A	1.500	0.125	0.187	0.016	0.012	0.002	0.001
B	0.531	0.625	0.266	0.391	0.100	0.244	0.043
C	0.219	1.500	0.191	2.250	0.203	3.375	0.228
			$\Sigma A = 0.644$		$\Sigma M = 0.315$		$\Sigma I_{DE} = 0.272$

The distance d from DE, the axis at the base of the configuration, to the neutral axis xx is:

$$d = \frac{M}{A} = \frac{0.315}{0.644} = 0.49$$

The moment of inertia of the entire section with reference to the neutral axis xx is:

$$\begin{aligned} I_N &= I_{DE} - Ad^2 \\ &= 0.272 - 0.644 \times 0.49^2 \\ &= 0.117 \end{aligned}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Moments of Inertia, Section Moduli, etc.— On the following pages are given formulas for the moments of inertia and other properties of forty-two different cross-sections. The formulas give the area of the section A, and the distance y from the neutral axis to the extreme fiber, for each example. Where the formulas for the section modulus and radius of gyration are very lengthy, the formula for the section modulus, for example, has been simply given as $I \div y$. The radius of gyration is sometimes given as $\sqrt{I \div A}$ to save space.

Moments of Inertia, Section Moduli, and Radii of Gyration

Section A = area y = distance from axis to extreme fiber	Moment of Inertia I	Section Modulus $Z = \frac{I}{y}$	Radius of Gyration $k = \sqrt{\frac{I}{A}}$
Square and Rectangular Sections			
 $A = a^2 \quad y = a/2$	$\frac{a^4}{12}$	$\frac{a^3}{6}$	$\frac{a}{\sqrt{12}} = 0.289a$
 $A = a^2 \quad y = a$	$\frac{a^4}{3}$	$\frac{a^3}{3}$	$\frac{a}{\sqrt{3}} = 0.577a$
 $A = a^2$ $y = \frac{a}{\sqrt{2}} = 0.707a$	$\frac{a^4}{12}$	$\frac{a^3}{6\sqrt{2}} = 0.118a^3$	$\frac{a}{\sqrt{12}} = 0.289a$
 $A = a^2 - b^2 \quad y = a/2$	$\frac{a^4 - b^4}{12}$	$\frac{a^4 - b^4}{6a}$	$\sqrt{\frac{a^2 + b^2}{12}}$ $= 0.289\sqrt{a^2 + b^2}$
 $A = a^2 - b^2 \qquad y = \frac{a}{\sqrt{2}}$	$\frac{a^4 - b^4}{12}$	$\frac{\sqrt{2}(a^4 - b^4)}{12a}$ $= 0.118\frac{a^4 - b^4}{a}$	$\sqrt{\frac{a^2 + b^2}{12}}$ $= 0.289\sqrt{a^2 + b^2}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section A = area y = distance from axis to extreme fiber	Moment of Inertia I	Section Modulus $Z = \frac{I}{y}$	Radius of Gyration $k = \sqrt{\frac{I}{A}}$
Square and Rectangular Sections *(Continued)*			
 $A = bd \quad y = d/2$	$\frac{bd^3}{12}$	$\frac{bd^2}{6}$	$\frac{d}{\sqrt{12}} = 0.289d$
 $A = bd \quad y = d$	$\frac{bd^3}{3}$	$\frac{bd^2}{3}$	$\frac{d}{\sqrt{3}} = 0.577d$
 $A = bd$ $y = \frac{bd}{\sqrt{b^2 + d^2}}$	$\frac{b^3d^3}{6(b^2 + d^2)}$	$\frac{b^2d^2}{6\sqrt{b^2 + d^2}}$	$\frac{bd}{\sqrt{6(b^2 + d^2)}}$ $= 0.408\frac{bd}{\sqrt{b^2 + d^2}}$
 $A = bd$ $y = \frac{1}{2}(d\cos\alpha + b\sin\alpha)$	$\frac{bd}{12}(d^2\cos^2\alpha + b^2\sin^2\alpha)$	$\frac{bd}{6} \times \left(\frac{d^2\cos^2\alpha + b^2\sin^2\alpha}{d\cos\alpha + b\sin\alpha}\right)$	$\sqrt{\frac{d^2\cos^2\alpha + b^2\sin^2\alpha}{12}}$ $= 0.289 \times \sqrt{d^2\cos^2\alpha + b^2\sin^2\alpha}$
 $A = bd - hk$ $y = d/2$	$\frac{bd^3 - hk^3}{12}$	$\frac{bd^3 - hk^3}{6d}$	$\sqrt{\frac{bd^3 - hk^3}{12(bd - hk)}}$ $= 0.289\sqrt{\frac{bd^3 - hk^3}{bd - hk}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
Triangular Sections					
	$\frac{1}{2}bd$	$\frac{2}{3}d$	$\frac{bd^3}{36}$	$\frac{bd^2}{24}$	$\frac{d}{\sqrt{18}} = 0.236d$
	$\frac{1}{2}bd$	d	$\frac{bd^3}{12}$	$\frac{bd^2}{12}$	$\frac{d}{\sqrt{6}} = 0.408d$
Polygon Sections					
	$\frac{d(a+b)}{2}$	$\frac{d(a+2b)}{3(a+b)}$	$\frac{d^3(a^2+4ab+b^2)}{36(a+b)}$	$\frac{d^2(a^2+4ab+b^2)}{12(a+2b)}$	$\sqrt{\frac{d^2(a^2+4ab+b^2)}{18(a+b)^2}}$
	$\frac{3d^2\tan 30°}{2}$ $= 0.866d^2$	$\frac{d}{2}$	$\frac{A}{12}\left[\frac{d^2(1+2\cos^2 30°)}{4\cos^2 30°}\right]$ $= 0.06d^4$	$\frac{A}{6}\left[\frac{d(1+2\cos^2 30°)}{4\cos^2 30°}\right]$ $= 0.12d^3$	$\sqrt{\frac{d^2(1+2\cos^2 30°)}{48\cos^2 30°}}$ $= 0.264d$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$\frac{3d^2\tan 30°}{2}$ $= 0.866d^2$	$\frac{d}{2\cos 30°} = 0.577d$	$\frac{A}{12}\left[\frac{d^2(1+2\cos^2 30°)}{4\cos^2 30°}\right]$ $= 0.06d^4$	$\frac{A}{6.9}\left[\frac{d(1+2\cos^2 30°)}{4\cos^2 30°}\right]$ $= 0.104d^3$	$\sqrt{\frac{d^2(1+2\cos^2 30°)}{48\cos^2 30°}}$ $= 0.264d$
	$2d^2\tan 22½ = 0.828d^2$	$\frac{d}{2}$	$\frac{A}{12}\left[\frac{d^2(1+2\cos^2 22½°)}{4\cos^2 22½°}\right]$ $= 0.055d^4$	$\frac{A}{6}\left[\frac{d(1+2\cos^2 22½°)}{4\cos^2 22½°}\right]$ $= 0.109d^3$	$\sqrt{\frac{d^2(1+2\cos^2 22½°)}{48\cos^2 22½°}}$ $= 0.257d$
Circular, Elliptical, and Circular Arc Sections					
	$\frac{\pi d^2}{4} = 0.7854d^2$	$\frac{d}{2}$	$\frac{\pi d^4}{64} = 0.049d^4$	$\frac{\pi d^3}{32} = 0.098d^3$	$\frac{d}{4}$
	$\frac{\pi d^2}{8} = 0.393d^2$	$\frac{(3\pi-4)d}{6\pi}$ $= 0.288d$	$\frac{(9\pi^2-64)d^4}{1152\pi}$ $= 0.007d^4$	$\frac{(9\pi^2-64)d^3}{192(3\pi-4)}$ $= 0.024d^3$	$\frac{\sqrt{(9\pi^2-64)d^2}}{12\pi}$ $= 0.132d$
	$\frac{\pi(D^2-d^2)}{4}$ $= 0.7854(D^2-d^2)$	$\frac{D}{2}$	$\frac{\pi(D^4-d^4)}{64}$ $= 0.049(D^4-d^4)$	$\frac{\pi(D^4-d^4)}{32D}$ $= 0.098\frac{D^4-d^4}{D}$	$\frac{\sqrt{D^2+d^2}}{4}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$\frac{\pi(R^2 - r^2)}{2}$ $= 1.5708(R^2 - r^2)$	$\frac{4(R^3 - r^3)}{3\pi(R^2 - r^2)}$ $= 0.424\frac{R^3 - r^3}{R^2 - r^2}$	$0.1098(R^4 - r^4)$ $-\frac{0.283R^2r^2(R - r)}{R + r}$	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$
	$\pi ab = 3.1416ab$	a	$\frac{\pi a^3 b}{4} = 0.7854a^3b$	$\frac{\pi a^2 b}{4} = 0.7854a^2b$	$\frac{a}{2}$
	$\pi(ab - cd)$ $= 3.1416(ab - cd)$	a	$\frac{\pi}{4}(a^3b - c^3d)$ $= 0.7854(a^3b - c^3d)$	$\frac{\pi(a^3b - c^3d)}{4a}$ $= 0.7854\frac{a^3b - c^3d}{a}$	$\frac{1}{2}\sqrt{\frac{a^3b - c^3d}{ab - cd}}$
I–Sections					
	$bd - h(b - t)$	$\frac{b}{2}$	$\frac{2sb^3 + ht^3}{12}$	$\frac{2sb^3 + ht^3}{6b}$	$\sqrt{\frac{2sb^3 + ht^3}{12[bd - h(b - t)]}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$dt + 2a(s + n)$	$\frac{d}{2}$	$\frac{1}{12}\left[bd^3 - \frac{1}{4g}(h^4 - l^4)\right]$ in which g = slope of flange = $(h - l)/(b - t)$ = 100% for standard I-beams.	$\frac{1}{6d}\left[bd^3 - \frac{1}{4g}(h^4 - l^4)\right]$	$\sqrt{\frac{\frac{1}{12}\left[bd^3 - \frac{1}{4g}(h^4 - l^4)\right]}{dt + 2a(s + n)}}$
	$bd - h(b - t)$	$\frac{d}{2}$	$\frac{bd^3 - h^3(b - t)}{12}$	$\frac{bd^3 - h^3(b - t)}{6d}$	$\sqrt{\frac{bd^3 - h^3(b - t)}{12[bd - h(b - t)]}}$
	$dt + 2a(s + n)$	$\frac{b}{2}$	$\frac{1}{12}\left[b^3(d - h) + lt^3 + \frac{g}{4}(b^4 - t^4)\right]$ in which g = slope of flange = $(h - l)/(b - t)$ = 1/6 for standard I-beams.	$\frac{1}{6b}\left[b^3(d - h) + lt^3 + \frac{g}{4}(b^4 - t^4)\right]$	$\sqrt{\frac{I}{A}}$
	$bs + ht + as$	$d - [td^2 + s^2(b - t) + s(a - t)(2d - s)] \div 2A$	$\frac{1}{3}[b(d - y)^3 + ay^3 - (b - t)(d - y - s)^3 - (a - t)(y - s)^3]$	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
C–Sections					
	$dt + a(s + n)$	$\frac{d}{2}$	$\frac{1}{12}\left[bd^3 - \frac{1}{8g}(h^4 - l^4)\right]$ g = slope of flange $= \frac{h-l}{2(b-t)} = \frac{1}{6}$ for standard channels.	$\frac{1}{6d}\left[bd^3 - \frac{1}{8g}(h^4 - l^4)\right]$	$\sqrt{\frac{\frac{1}{12}\left[bd^3 - \frac{1}{8g}(h^4 - l^4)\right]}{dt + a(s + n)}}$
	$dt + 2a(s + n)$	$b - \left[b^2 s + \frac{ht^2}{2} + \frac{g}{3}(b-t)^2 \times (b + 2t)\right] \div A$ g = slope of flange $= \frac{h-l}{2(b-t)}$	$\frac{1}{3}\left[2sb^3 + lt^3 + \frac{g}{2}(b^4 - t^4)\right] - A(b-y)^2$ g = slope of flange $= \frac{h-l}{2(b-t)} = \frac{1}{6}$ for standard channels.	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$
	$bd - h(b-t)$	$\frac{d}{2}$	$\frac{bd^3 - h^3(b-t)}{12}$	$\frac{bd^3 - h^3(b-t)}{6d}$	$\sqrt{\frac{bd^3 - h^3(b-t)}{12[bd - h(b-t)]}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$bd - h(b-t)$	$b - \dfrac{2b^2s + ht^2}{2bd - 2h(b-t)}$	$\dfrac{2sb^3 + ht^3}{3} - A(b-y)^2$	$\dfrac{I}{y}$	$\sqrt{\dfrac{I}{A}}$
T–Sections					
	$bs + ht$	$d - \dfrac{d^2t + s^2(b-t)}{2(bs+ht)}$	$\frac{1}{3}[ty^3 + b(d-y)^3 - (b-t)(d-y-s)^3]$	$\dfrac{I}{y}$	$\sqrt{\dfrac{1}{3(bs+ht)}[ty^3 + b(d-y)^3 - (b-t)(d-y-s)^3]}$
	$\dfrac{l(T+t)}{2} + Tn + a(s+n)$	$d - [3s^2(b-T) + 2am(m+3s) + 3Td^2 - l(T-t)(3d-l)] \div 6A$	$\frac{1}{12}[l^3(T+3t) + 4bn^3 - 2am^3] - A(d-y-n)^2$	$\dfrac{I}{y}$	$\sqrt{\dfrac{I}{A}}$
	$bs + \dfrac{h(T+t)}{2}$	$d - [3bs^2 + 3ht(d+s) + h(T-t)(h+3s)] \div 6A$	$\frac{1}{12}[4bs^3 + h^3(3t+T)] - A(d-y-s)^2$	$\dfrac{I}{y}$	$\sqrt{\dfrac{I}{A}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$\frac{l(T+t)}{2} + Tn + a(s+n)$	$\frac{b}{2}$	$\frac{sb^3 + mT^3 + lt^3}{12} + \frac{am[2a^2 + (2a+3T)^2]}{36} + \frac{l(T-t)[(T-t)^2 + 2(T+2t)^2]}{144}$	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$
L–, Z–, and X–Sections					
	$t(2a-t)$	$a - \frac{a^2 + at - t^2}{2(a-t)}$	$\frac{1}{3}[ty^3 + a(a-y)^3 - (a-t)(a-y-t)^3]$	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$
	$t(a+b-t)$	$b - \frac{t(2d+a) + d^2}{2(d+a)}$	$\frac{1}{3}[ty^3 + a(b-y)^3 - (a-t)(b-y-t)^3]$	$\frac{I}{y}$	$\sqrt{\frac{1}{3t(a+b-t)}[ty^3 + a(b-y)^3 - (a-t)(b-y-t)^3]}$
	$t(a+b-t)$	$a - \frac{t(2c+b) + c^2}{2(c+b)}$	$\frac{1}{3}[ty^3 + b(a-y)^3 - (b-t)(a-y-t)^3]$	$\frac{I}{y}$	$\sqrt{\frac{1}{3t(a+b-t)}[ty^3 + b(a-y)^3 - (b-t)(a-y-t)^3]}$

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia, Section Moduli, and Radii of Gyration *(Continued)*

Section	Area of Section, A	Distance from Neutral Axis to Extreme Fiber, y	Moment of Inertia, I	Section Modulus, $Z = I/y$	Radius of Gyration, $k = \sqrt{I/A}$
	$t(2a - t)$	$\frac{a^2 + at - t^2}{2(2a - t)\cos 45°}$	$\frac{A}{12}[7(a^2 + b^2) - 12y^2]$ $-2ab^2(a - b)$ in which $b = (a - t)$	$\frac{I}{y}$	$\sqrt{\frac{I}{A}}$
	$t[b + 2(a - t)]$	$\frac{b}{2}$	$\frac{ab^3 - c(b - 2t)^3}{12}$	$\frac{ab^3 - c(b - 2t)^3}{6b}$	$\sqrt{\frac{ab^3 - c(b - 2t)^3}{12t[b + 2(a - t)]}}$
	$t[b + 2(a - t)]$	$\frac{2a - t}{2}$	$\frac{b(a + c)^3 - 2c^3d - 6a^2cd}{12}$	$\frac{b(a + c)^3 - 2c^3d - 6a^2cd}{6(2a - t)}$	$\sqrt{\frac{b(a + c)^3 - 2c^3d - 6a^2cd}{12t[b + 2(a - t)]}}$
	$dt + s(b - t)$	$\frac{d}{2}$	$\frac{td^3 + s^3(b - t)}{12}$	$\frac{td^3 - s^3(b - t)}{6d}$	$\sqrt{\frac{td^3 + s^3(b - t)}{12[td + s(b - t)]}}$

Copyright 2004, Industrial Press, Inc., New York, NY

Polar Area Moment of Inertia and Section Modulus.— The *polar moment of inertia*, J, of a cross-section with respect to a polar axis, that is, an axis at right angles to the plane of the cross-section, is defined as the moment of inertia of the cross-section with respect to the point of intersection of the axis and the plane. The polar moment of inertia may be found by taking the sum of the moments of inertia about two perpendicular axes lying in the plane of the cross-section and passing through this point. Thus, for example, the polar moment of inertia of a circular or a square area with respect to a polar axis through the center of gravity is equal to two times the moment of inertia with respect to an axis lying in the plane of the cross-section and passing through the center of gravity.

The polar moment of inertia with respect to a polar axis through the center of gravity is required for problems involving the torsional strength of shafts since this axis is usually the axis about which twisting of the shaft takes place.

The *polar section modulus* (also called section modulus of torsion), Z_p, for *circular* sections may be found by dividing the polar moment of inertia, J, by the distance c from the center of gravity to the most remote fiber. This method may be used to find the *approximate* value of the polar section modulus of sections that are *nearly* round. For other than circular cross-sections, however, the polar section modulus *does not* equal the polar moment of inertia divided by the distance c.

The accompanying table *Polar Moment of Inertia and Polar Section Modulus* on page 249 gives formulas for the polar section modulus for several different cross-sections. The polar section modulus multiplied by the allowable torsional shearing stress gives the allowable twisting moment to which a shaft may be subjected, see Formula (7) on page 300.

Mass Moments of Inertia*, J_M.— Starting on page 250, formulas for mass moment of inertia of various solids are given in a series of tables. The example that follows illustrates the derivaion of J_M for one of the bodes given on page 250.

Example, Polar Mass Moment of Inertia of a Hollow Circular Section: Referring to the figure *Hollow Cylinder* on page 250, consider a strip of width dr on a hollow circular section, whose inner radius is r and outer radius is R.

The mass of the strip = $2\pi r dr\rho$, where ρ is the density of material. In order to get the mass of an individual section, integrate the mass of the strip from r to R.

$$M = \int_r^R 2\pi r(dr)\rho = 2\pi\rho\int_r^R r(dr) = 2\pi\rho\left[\frac{r^2}{2}\right]_r^R$$

$$= 2\pi\rho\left(\frac{R^2}{2} - \frac{r^2}{2}\right) = \pi\rho(R^2 - r^2)$$

The 2nd moment of the strip about the AA axis = $2\pi r dr\rho r^2$. To find the polar moment of inertia about the AA axis, integrate the 2nd moment from r to R.

$$J_M = \int_r^R 2\pi r(dr)\rho r^2 = 2\pi\rho\int_r^R r^3(dr) = 2\pi\rho\left[\frac{r^4}{4}\right]_r^R$$

$$= 2\pi\rho\left(\frac{R^4}{4} - \frac{r^4}{4}\right) = \frac{\pi\rho}{2}(R^2 - r^2)(R^2 + r^2)$$

$$= \left(\pi\rho(R^2 - r^2)\frac{(R^2 + r^2)}{2} = \frac{M(R^2 + r^2)}{2}\right)$$

* In some books the symbol I denotes the polar moment of inertia of masses; J_M is used in this handbook to avoid confusion with moments of inertia of plane areas.

Copyright 2004, Industrial Press, Inc., New York, NY

Polar Moment of Inertia and Polar Section Modulus

Section	Polar Moment of Inertia, J	Polar Section Modulus, Z_p
	$\frac{a^4}{6} = 0.1667a^4$	$0.208a^3 = 0.074d^3$
	$\frac{bd(b^2+d^2)}{12}$	$\frac{bd^2}{3+1.8\frac{d}{b}}$ (d is the shorter side)
	$\frac{\pi D^4}{32} = 0.098D^4$ (see also footnote, page 254)	$\frac{\pi D^3}{16} = 0.196D^3$ (see also footnote, page 254)
	$\frac{\pi}{32}(D^4-d^4)$ $= 0.098(D^4-d^4)$	$\frac{\pi}{16}\left(\frac{D^4-d^4}{D}\right)$ $= 0.196\left(\frac{D^4-d^4}{D}\right)$
	$\frac{5\sqrt{3}}{8}s^4 = 1.0825s^4$ $= 0.12F^4$	$0.20F^3$
	$\frac{\pi D^4}{32}-\frac{s^4}{6}$ $= 0.098D^4-0.167s^4$	$\frac{\pi D^3}{16}-\frac{s^4}{3D}$ $= 0.196D^3-0.333\frac{s^4}{D}$
	$\frac{\pi D^4}{32}-\frac{5\sqrt{3}}{8}s^4$ $= 0.098D^4-1.0825s^4$	$\frac{\pi D^3}{16}-\frac{5\sqrt{3}}{4D}s^4$ $= 0.196D^3-2.165\frac{s^4}{D}$
	$\frac{\sqrt{3}}{48}s^4 = 0.036s^4$	$\frac{s^3}{20} = 0.05s^3$

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Polar Moment of Inertia of Masses, J_M

Prism:



With reference to axis $A-A$: $J_M = \frac{M}{12}(h^2 + b^2)$

With reference to axis $B-B$: $J_M = M\left(\frac{l^2}{3} + \frac{h^2}{12}\right)$

Cylinder:



With reference to axis $A-A$: $J_M = \frac{1}{2}Mr^2$

With reference to axis $B-B$: $J_M = M\left(\frac{l^2}{3} + \frac{r^2}{4}\right)$

Hollow Cylinder:



With reference to axis $A-A$: $J_M = \frac{1}{2}M(R^2 + r^2)$

With reference to axis $B-B$:

$$J_M = M\left(\frac{l^2}{3} + \frac{R^2 + r^2}{4}\right)$$

Pyramid, Rectangular Base:



With reference to axis $A-A$: $J_M = \frac{M}{20}(a^2 + b^2)$

With reference to axis $B-B$ (through the center of gravity):

$$J_M = M\left(\frac{3}{80}h^2 + \frac{b^2}{20}\right)$$

Sphere:



With reference to any axis through the center:

$$J_M = \frac{2}{5}Mr^2$$

Copyright 2004, Industrial Press, Inc., New York, NY

Spherical Sector:



With reference to axis $A-A$: $J_M = \frac{M}{5}(3rh - h^2)$

Spherical Segment:



Spherical Segment: With reference to axis $A-A$:

$$J_M = M\left(r^2 - \frac{3rh}{4} + \frac{3h^2}{20}\right)\frac{2h}{3r - h}$$

Torus:



With reference to axis $A-A$: $J_M = M\left(\frac{R^2}{2} + \frac{5r^2}{8}\right)$

With reference to axis $B-B$: $J_M = M(R^2 + \frac{3}{4}r^2)$

Paraboloid:



With reference to axis $A-A$: $J_M = \frac{1}{3}Mr^2$

With reference to axis $B-B$ (through the center of gravity):

$$J_M = M\left(\frac{r^2}{6} + \frac{h^2}{18}\right)$$

Ellipsoid:



With reference to axis $A-A$: $J_M = \frac{M}{5}(b^2 + c^2)$

With reference to axis $B-B$: $J_M = \frac{M}{5}(a^2 + c^2)$

With reference to axis $C-C$: $J_M = \frac{M}{5}(a^2 + b^2)$

Copyright 2004, Industrial Press, Inc., New York, NY

Cone:



With reference to axis $A-A$: $J_M = \frac{3M}{10}r^2$

With reference to axis $B-B$ (through the center of gravity):

$$J_M = \frac{3M}{20}\left(r^2 + \frac{h^2}{4}\right)$$

Frustrum of Cone:

With reference to axis $A-A$: $J_M = \frac{3M(R^5 - r^5)}{10(R^3 - r^3)}$

Moments of Inertia of Complex Areas and Masses may be evaluated by the addition and subtraction of elementary areas and masses. For example, the accompanying figure shows a complex mass at (1); its mass polar moment of inertia can be determined by adding together the moments of inertia of the bodies shown at (2) and (3), and subtracting that at (4).

Thus, $J_{M1} = J_{M2} + J_{M3} - J_{M4}$. All of these moments of inertia are with respect to the axis of rotation $z - z$. Formulas for J_{M2} and J_{M3} can be obtained from the tables beginning on page 250. The moment of inertia for the body at (4) can be evaluated by using the following transfer-axis equation: $J_{M4} = J_{M4}' + d^2M$. The term J_{M4}' is the moment of inertia with respect to axis $z' - z'$; it may be evaluated using the same equation that applies to J_{M2} where d is the distance between the $z - z$ and the $z' - z'$ axes, and M is the mass of the body (= weight in lbs ÷ g).



Moments of Inertia of Complex Masses

Similar calculations can be made when calculating I and J for complex areas using the appropriate transfer-axis equations are $I = I' + d^2A$ and $J = J' + d^2A$. The primed term, I' or J', is with respect to the center of gravity of the corresponding area A; d is the distance between the axis through the center of gravity and the axis to which I or J is referred.

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of Inertia and Section Moduli for Rectangles and Round Shafts

Moments of inertia and section modulus values shown here are for rectangles 1 millimeter wide. To obtain moment of inertia or section modulus for rectangle of given side length, multiply appropriate table value by given width. (See the text starting on page 238 for basic formulas.)

Moments of Inertia and Section Moduli for Rectangles (Metric Units)

Length of Side (mm)	Moment of Inertia	Section Modulus	Length of Side (mm)	Moment of Inertia	Section Modulus	Length of Side (mm)	Moment of Inertia	Section Modulus
5	10.4167	4.16667	56	14634.7	522.667	107	102087	1908.17
6	18.0000	6.00000	57	15432.8	541.500	108	104976	1944.00
7	28.5833	8.16667	58	16259.3	560.667	109	107919	1980.17
8	42.6667	10.6667	59	17114.9	580.167	110	110917	2016.67
9	60.7500	13.5000	60	18000.0	600.000	111	113969	2053.50
10	83.3333	16.6667	61	18915.1	620.167	112	117077	2090.67
11	110.917	20.1667	62	19860.7	640.667	113	120241	2128.17
12	144.000	24.0000	63	20837.3	661.500	114	123462	2166.00
13	183.083	28.1667	64	21845.3	682.667	115	126740	2204.17
14	228.667	32.6667	65	22885.4	704.167	116	130075	2242.67
15	281.250	37.5000	66	23958.0	726.000	117	133468	2281.50
16	341.333	42.6667	67	25063.6	748.167	118	136919	2320.67
17	409.417	48.1667	68	26202.7	770.667	119	140430	2360.17
18	486.000	54.0000	69	27375.8	793.500	120	144000	2400.00
19	571.583	60.1667	70	28583.3	816.667	121	147630	2440.17
20	666.667	66.6667	71	29825.9	840.167	122	151321	2480.67
21	771.750	73.5000	72	31104.0	864.000	123	155072	2521.50
22	887.333	80.6667	73	32418.1	888.167	124	158885	2562.67
23	1013.92	88.1667	74	33768.7	912.667	125	162760	2604.17
24	1152.00	96.0000	75	35156.3	937.500	126	166698	2646.00
25	1302.08	104.1667	76	36581.3	962.667	127	170699	2688.17
26	1464.67	112.6667	77	38044.4	988.167	128	174763	2730.67
27	1640.25	121.5000	78	39546.0	1014.00	130	183083	2816.67
28	1829.33	130.6667	79	41086.6	1040.17	132	191664	2904.00
29	2032.42	140.167	80	42666.7	1066.67	135	205031	3037.50
30	2250.00	150.000	81	44286.8	1093.50	138	219006	3174.00
31	2482.58	160.167	82	45947.3	1120.67	140	228667	3266.67
32	2730.67	170.667	83	47648.9	1148.17	143	243684	3408.17
33	2994.75	181.500	84	49392.0	1176.00	147	264710	3601.50
34	3275.33	192.667	85	51177.1	1204.17	150	281250	3750.00
35	3572.92	204.167	86	53004.7	1232.67	155	310323	4004.17
36	3888.00	216.000	87	54875.3	1261.50	160	341333	4266.67
37	4221.08	228.167	88	56789.3	1290.67	165	374344	4537.50
38	4572.67	240.667	89	58747.4	1320.17	170	409417	4816.67
39	4943.25	253.500	90	60750.0	1350.00	175	446615	5104.17
40	5333.33	266.667	91	62797.6	1380.17	180	486000	5400.00
41	5743.42	280.167	92	64890.7	1410.67	185	527635	5704.17
42	6174.00	294.000	93	67029.8	1441.50	190	571583	6016.67
43	6625.58	308.167	94	69215.3	1472.67	195	617906	6337.50
44	7098.67	322.667	95	71447.9	1504.17	200	666667	6666.67
45	7593.75	337.500	96	73728.0	1536.00	210	771750	7350.00
46	8111.33	352.667	97	76056.1	1568.17	220	887333	8066.67
47	8651.92	368.167	98	78432.7	1600.67	230	1013917	8816.67
48	9216.00	384.000	99	80858.3	1633.50	240	1152000	9600.00
49	9804.08	400.167	100	83333.3	1666.67	250	1302083	10416.7
50	10416.7	416.667	101	85858.4	1700.17	260	1464667	11266.7
51	11054.3	433.500	102	88434.0	1734.00	270	1640250	12150.0
52	11717.3	450.667	103	91060.6	1768.17	280	1829333	13066.7
53	12406.4	468.167	104	93738.7	1802.67	290	2032417	14016.7
54	13122.0	486.000	105	96468.8	1837.50	300	2250000	15000.0
55	13864.6	504.167	106	99251.3	1872.67	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli for Rectangles

Length of Side	Section Modulus	Length of Side	Section Modulus	Length of Side	Section Modulus	Length of Side	Section Modulus
1/8	0.0026	2 3/4	1.26	12	24.00	25	104.2
3/16	0.0059	3	1.50	12 1/2	26.04	26	112.7
1/4	0.0104	3 1/4	1.76	13	28.17	27	121.5
5/16	0.0163	3 1/2	2.04	13 1/2	30.38	28	130.7
3/8	0.0234	3 3/4	2.34	14	32.67	29	140.2
7/16	0.032	4	2.67	14 1/2	35.04	30	150.0
1/2	0.042	4 1/2	3.38	15	37.5	32	170.7
5/8	0.065	5	4.17	15 1/2	40.0	34	192.7
3/4	0.094	5 1/2	5.04	16	42.7	36	216.0
7/8	0.128	6	6.00	16 1/2	45.4	38	240.7
1	0.167	6 1/2	7.04	17	48.2	40	266.7
1 1/8	0.211	7	8.17	17 1/2	51.0	42	294.0
1 1/4	0.260	7 1/2	9.38	18	54.0	44	322.7
1 3/8	0.315	8	10.67	18 1/2	57.0	46	352.7
1 1/2	0.375	8 1/2	12.04	19	60.2	48	384.0
1 5/8	0.440	9	13.50	19 1/2	63.4	50	416.7
1 3/4	0.510	9 1/2	15.04	20	66.7	52	450.7
1 7/8	0.586	10	16.67	21	73.5	54	486.0
2	0.67	10 1/2	18.38	22	80.7	56	522.7
2 1/4	0.84	11	20.17	23	88.2	58	560.7
2 1/2	1.04	11 1/2	22.04	24	96.0	60	600.0

Section modulus values are shown for rectangles 1 inch wide. To obtain section modulus for rectangle of given side length, multiply value in table by given width.

Section Moduli and Moments of Inertia for Round Shafts

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
1/8	0.00019	0.00001	27/64	0.00737	0.00155	23/32	0.03645	0.01310
9/64	0.00027	0.00002	7/16	0.00822	0.00180	47/64	0.03888	0.01428
5/32	0.00037	0.00003	29/64	0.00913	0.00207	3/4	0.04142	0.01553
11/64	0.00050	0.00004	15/32	0.01011	0.00237	49/64	0.04406	0.01687
3/16	0.00065	0.00006	31/64	0.01116	0.00270	25/32	0.04681	0.01829
13/64	0.00082	0.00008	1/2	0.01227	0.00307	51/64	0.04968	0.01979
7/32	0.00103	0.00011	33/64	0.01346	0.00347	13/16	0.05266	0.02139
15/64	0.00126	0.00015	17/32	0.01472	0.00391	53/64	0.05576	0.02309
1/4	0.00153	0.00019	35/64	0.01606	0.00439	27/32	0.05897	0.02488
17/64	0.00184	0.00024	9/16	0.01747	0.00491	55/64	0.06231	0.02677
9/32	0.00218	0.00031	37/64	0.01897	0.00548	7/8	0.06577	0.02877
19/64	0.00257	0.00038	19/32	0.02055	0.00610	57/64	0.06936	0.03089
5/16	0.00300	0.00047	39/64	0.02222	0.00677	29/32	0.07307	0.03311
21/64	0.00347	0.00057	5/8	0.02397	0.00749	59/64	0.07692	0.03545
11/32	0.00399	0.00069	41/64	0.02581	0.00827	15/16	0.08089	0.03792
23/64	0.00456	0.00082	21/32	0.02775	0.00910	61/64	0.08501	0.04051
3/8	0.00518	0.00097	43/64	0.02978	0.01000	31/32	0.08926	0.04323
25/64	0.00585	0.00114	11/16	0.03190	0.01097	63/64	0.09364	0.04609
13/32	0.00658	0.00134	45/64	0.03413	0.01200	…	…	…

In this and succeeding tables, the *Polar Section Modulus* for a shaft of given diameter can be obtained by multiplying its section modulus by 2. Similarly, its *Polar Moment of Inertia* can be obtained by multiplying its moment of inertia by 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli and Moments of Inertia for Round Shafts (English or Metric Units)

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
1.00	0.0982	0.0491	1.50	0.3313	0.2485	2.00	0.7854	0.7854
1.01	0.1011	0.0511	1.51	0.3380	0.2552	2.01	0.7972	0.8012
1.02	0.1042	0.0531	1.52	0.3448	0.2620	2.02	0.8092	0.8173
1.03	0.1073	0.0552	1.53	0.3516	0.2690	2.03	0.8213	0.8336
1.04	0.1104	0.0574	1.54	0.3586	0.2761	2.04	0.8335	0.8501
1.05	0.1136	0.0597	1.55	0.3656	0.2833	2.05	0.8458	0.8669
1.06	0.1169	0.0620	1.56	0.3727	0.2907	2.06	0.8582	0.8840
1.07	0.1203	0.0643	1.57	0.3799	0.2982	2.07	0.8708	0.9013
1.08	0.1237	0.0668	1.58	0.3872	0.3059	2.08	0.8835	0.9188
1.09	0.1271	0.0693	1.59	0.3946	0.3137	2.09	0.8963	0.9366
1.10	0.1307	0.0719	1.60	0.4021	0.3217	2.10	0.9092	0.9547
1.11	0.1343	0.0745	1.61	0.4097	0.3298	2.11	0.9222	0.9730
1.12	0.1379	0.0772	1.62	0.4174	0.3381	2.12	0.9354	0.9915
1.13	0.1417	0.0800	1.63	0.4252	0.3465	2.13	0.9487	1.0104
1.14	0.1455	0.0829	1.64	0.4330	0.3551	2.14	0.9621	1.0295
1.15	0.1493	0.0859	1.65	0.4410	0.3638	2.15	0.9757	1.0489
1.16	0.1532	0.0889	1.66	0.4491	0.3727	2.16	0.9894	1.0685
1.17	0.1572	0.0920	1.67	0.4572	0.3818	2.17	1.0032	1.0885
1.18	0.1613	0.0952	1.68	0.4655	0.3910	2.18	1.0171	1.1087
1.19	0.1654	0.0984	1.69	0.4739	0.4004	2.19	1.0312	1.1291
1.20	0.1696	0.1018	1.70	0.4823	0.4100	2.20	1.0454	1.1499
1.21	0.1739	0.1052	1.71	0.4909	0.4197	2.21	1.0597	1.1710
1.22	0.1783	0.1087	1.72	0.4996	0.4296	2.22	1.0741	1.1923
1.23	0.1827	0.1124	1.73	0.5083	0.4397	2.23	1.0887	1.2139
1.24	0.1872	0.1161	1.74	0.5172	0.4500	2.24	1.1034	1.2358
1.25	0.1917	0.1198	1.75	0.5262	0.4604	2.25	1.1183	1.2581
1.26	0.1964	0.1237	1.76	0.5352	0.4710	2.26	1.1332	1.2806
1.27	0.2011	0.1277	1.77	0.5444	0.4818	2.27	1.1484	1.3034
1.28	0.2059	0.1318	1.78	0.5537	0.4928	2.28	1.1636	1.3265
1.29	0.2108	0.1359	1.79	0.5631	0.5039	2.29	1.1790	1.3499
1.30	0.2157	0.1402	1.80	0.5726	0.5153	2.30	1.1945	1.3737
1.31	0.2207	0.1446	1.81	0.5822	0.5268	2.31	1.2101	1.3977
1.32	0.2258	0.1490	1.82	0.5919	0.5386	2.32	1.2259	1.4221
1.33	0.2310	0.1536	1.83	0.6017	0.5505	2.33	1.2418	1.4468
1.34	0.2362	0.1583	1.84	0.6116	0.5627	2.34	1.2579	1.4717
1.35	0.2415	0.1630	1.85	0.6216	0.5750	2.35	1.2741	1.4971
1.36	0.2470	0.1679	1.86	0.6317	0.5875	2.36	1.2904	1.5227
1.37	0.2524	0.1729	1.87	0.6420	0.6003	2.37	1.3069	1.5487
1.38	0.2580	0.1780	1.88	0.6523	0.6132	2.38	1.3235	1.5750
1.39	0.2637	0.1832	1.89	0.6628	0.6264	2.39	1.3403	1.6016
1.40	0.2694	0.1886	1.90	0.6734	0.6397	2.40	1.3572	1.6286
1.41	0.2752	0.1940	1.91	0.6841	0.6533	2.41	1.3742	1.6559
1.42	0.2811	0.1996	1.92	0.6949	0.6671	2.42	1.3914	1.6836
1.43	0.2871	0.2053	1.93	0.7058	0.6811	2.43	1.4087	1.7116
1.44	0.2931	0.2111	1.94	0.7168	0.6953	2.44	1.4262	1.7399
1.45	0.2993	0.2170	1.95	0.7280	0.7098	2.45	1.4438	1.7686
1.46	0.3055	0.2230	1.96	0.7392	0.7244	2.46	1.4615	1.7977
1.47	0.3119	0.2292	1.97	0.7506	0.7393	2.47	1.4794	1.8271
1.48	0.3183	0.2355	1.98	0.7621	0.7545	2.48	1.4975	1.8568
1.49	0.3248	0.2419	1.99	0.7737	0.7698	2.49	1.5156	1.8870

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli and Moments of Inertia for Round Shafts (English or Metric Units)

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
2.50	1.5340	1.9175	3.00	2.6507	3.9761	3.50	4.2092	7.3662
2.51	1.5525	1.9483	3.01	2.6773	4.0294	3.51	4.2454	7.4507
2.52	1.5711	1.9796	3.02	2.7041	4.0832	3.52	4.2818	7.5360
2.53	1.5899	2.0112	3.03	2.7310	4.1375	3.53	4.3184	7.6220
2.54	1.6088	2.0432	3.04	2.7582	4.1924	3.54	4.3552	7.7087
2.55	1.6279	2.0755	3.05	2.7855	4.2479	3.55	4.3922	7.7962
2.56	1.6471	2.1083	3.06	2.8130	4.3038	3.56	4.4295	7.8844
2.57	1.6665	2.1414	3.07	2.8406	4.3604	3.57	4.4669	7.9734
2.58	1.6860	2.1749	3.08	2.8685	4.4175	3.58	4.5054	8.0631
2.59	1.7057	2.2089	3.09	2.8965	4.4751	3.59	4.5424	8.1536
2.60	1.7255	2.2432	3.10	2.9247	4.5333	3.60	4.5804	8.2248
2.61	1.7455	2.2779	3.11	2.9531	4.5921	3.61	4.6187	8.3368
2.62	1.7656	2.3130	3.12	2.9817	4.6514	3.62	4.6572	8.4295
2.63	1.7859	2.3485	3.13	3.0105	4.7114	3.63	4.6959	8.5231
2.64	1.8064	2.3844	3.14	3.0394	4.7719	3.64	4.7348	8.6174
2.65	1.8270	2.4208	3.15	3.0685	4.8329	3.65	4.7740	8.7125
2.66	1.8478	2.4575	3.16	3.0979	4.8946	3.66	4.8133	8.8083
2.67	1.8687	2.4947	3.17	3.1274	4.9569	3.67	4.8529	8.9050
2.68	1.8897	2.5323	3.18	3.1570	5.0197	3.68	4.8926	9.0025
2.69	1.9110	2.5703	3.19	3.1869	5.0831	3.69	4.9326	9.1007
2.70	1.9324	2.6087	3.20	3.2170	5.1472	3.70	4.9728	9.1998
2.71	1.9539	2.6476	3.21	3.2472	5.2118	3.71	5.0133	9.2996
2.72	1.9756	2.6869	3.22	3.2777	5.2771	3.72	5.0539	9.4003
2.73	1.9975	2.7266	3.23	3.3083	5.3429	3.73	5.0948	9.5018
2.74	2.0195	2.7668	3.24	3.3391	5.4094	3.74	5.1359	9.6041
2.75	2.0417	2.8074	3.25	3.3702	5.4765	3.75	5.1772	9.7072
2.76	2.0641	2.8484	3.26	3.4014	5.5442	3.76	5.2187	9.8112
2.77	2.0866	2.8899	3.27	3.4328	5.6126	3.77	5.2605	9.9160
2.78	2.1093	2.9319	3.28	3.4643	5.6815	3.78	5.3024	10.0216
2.79	2.1321	2.9743	3.29	3.4961	5.7511	3.79	5.3446	10.1281
2.80	2.1551	3.0172	3.30	3.5281	5.8214	3.80	5.3870	10.2354
2.81	2.1783	3.0605	3.31	3.5603	5.8923	3.81	5.4297	10.3436
2.82	2.2016	3.1043	3.32	3.5926	5.9638	3.82	5.4726	10.4526
2.83	2.2251	3.1486	3.33	3.6252	6.0360	3.83	5.5156	10.5625
2.84	2.2488	3.1933	3.34	3.6580	6.1088	3.84	5.5590	10.6732
2.85	2.2727	3.2385	3.35	3.6909	6.1823	3.85	5.6025	10.7848
2.86	2.2967	3.2842	3.36	3.7241	6.2564	3.86	5.6463	10.8973
2.87	2.3208	3.3304	3.37	3.7574	6.3313	3.87	5.6903	11.0107
2.88	2.3452	3.3771	3.38	3.7910	6.4067	3.88	5.7345	11.1249
2.89	2.3697	3.4242	3.39	3.8247	6.4829	3.89	5.7789	11.2401
2.90	2.3944	3.4719	3.40	3.8587	6.5597	3.90	5.8236	11.3561
2.91	2.4192	3.5200	3.41	3.8928	6.6372	3.91	5.8685	11.4730
2.92	2.4443	3.5686	3.42	3.9272	6.7154	3.92	5.9137	11.5908
2.93	2.4695	3.6178	3.43	3.9617	6.7943	3.93	5.9591	11.7095
2.94	2.4948	3.6674	3.44	3.9965	6.8739	3.94	6.0047	11.8292
2.95	2.5204	3.7176	3.45	4.0314	6.9542	3.95	6.0505	11.9497
2.96	2.5461	3.7682	3.46	4.0666	7.0352	3.96	6.0966	12.0712
2.97	2.5720	3.8194	3.47	4.1019	7.1168	3.97	6.1429	12.1936
2.98	2.5981	3.8711	3.48	4.1375	7.1992	3.98	6.1894	12.3169
2.99	2.6243	3.9233	3.49	4.1733	7.2824	3.99	6.2362	12.4412

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli and Moments of Inertia for Round Shafts (English or Metric Units)

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
4.00	6.2832	12.566	4.50	8.946	20.129	5.00	12.272	30.680
4.01	6.3304	12.693	4.51	9.006	20.308	5.01	12.346	30.926
4.02	6.3779	12.820	4.52	9.066	20.489	5.02	12.420	31.173
4.03	6.4256	12.948	4.53	9.126	20.671	5.03	12.494	31.423
4.04	6.4736	13.077	4.54	9.187	20.854	5.04	12.569	31.673
4.05	6.5218	13.207	4.55	9.248	21.039	5.05	12.644	31.925
4.06	6.5702	13.337	4.56	9.309	21.224	5.06	12.719	32.179
4.07	6.6189	13.469	4.57	9.370	21.411	5.07	12.795	32.434
4.08	6.6678	13.602	4.58	9.432	21.599	5.08	12.870	32.691
4.09	6.7169	13.736	4.59	9.494	21.788	5.09	12.947	32.949
4.10	6.7663	13.871	4.60	9.556	21.979	5.10	13.023	33.209
4.11	6.8159	14.007	4.61	9.618	22.170	5.11	13.100	33.470
4.12	6.8658	14.144	4.62	9.681	22.363	5.12	13.177	33.733
4.13	6.9159	14.281	4.63	9.744	22.558	5.13	13.254	33.997
4.14	6.9663	14.420	4.64	9.807	22.753	5.14	13.332	34.263
4.15	7.0169	14.560	4.65	9.871	22.950	5.15	13.410	34.530
4.16	7.0677	14.701	4.66	9.935	23.148	5.16	13.488	34.799
4.17	7.1188	14.843	4.67	9.999	23.347	5.17	13.567	35.070
4.18	7.1702	14.986	4.68	10.063	23.548	5.18	13.645	35.342
4.19	7.2217	15.130	4.69	10.128	23.750	5.19	13.725	35.616
4.20	7.2736	15.275	4.70	10.193	23.953	5.20	13.804	35.891
4.21	7.3257	15.420	4.71	10.258	24.158	5.21	13.884	36.168
4.22	7.3780	15.568	4.72	10.323	24.363	5.22	13.964	36.446
4.23	7.4306	15.716	4.73	10.389	24.571	5.23	14.044	36.726
4.24	7.4834	15.865	4.74	10.455	24.779	5.24	14.125	37.008
4.25	7.5364	16.015	4.75	10.522	24.989	5.25	14.206	37.291
4.26	7.5898	16.166	4.76	10.588	25.200	5.26	14.288	37.576
4.27	7.6433	16.319	4.77	10.655	25.412	5.27	14.369	37.863
4.28	7.6972	16.472	4.78	10.722	25.626	5.28	14.451	38.151
4.29	7.7513	16.626	4.79	10.790	25.841	5.29	14.533	38.441
4.30	7.8056	16.782	4.80	10.857	26.058	5.30	14.616	38.732
4.31	7.8602	16.939	4.81	10.925	26.275	5.31	14.699	39.025
4.32	7.9150	17.096	4.82	10.994	26.495	5.32	14.782	39.320
4.33	7.9701	17.255	4.83	11.062	26.715	5.33	14.866	39.617
4.34	8.0254	17.415	4.84	11.131	26.937	5.34	14.949	39.915
4.35	8.0810	17.576	4.85	11.200	27.160	5.35	15.034	40.215
4.36	8.1369	17.738	4.86	11.270	27.385	5.36	15.118	40.516
4.37	8.1930	17.902	4.87	11.339	27.611	5.37	15.203	40.819
4.38	8.2494	18.066	4.88	11.409	27.839	5.38	15.288	41.124
4.39	8.3060	18.232	4.89	11.480	28.068	5.39	15.373	41.431
4.40	8.3629	18.398	4.90	11.550	28.298	5.40	15.459	41.739
4.41	8.4201	18.566	4.91	11.621	28.530	5.41	15.545	42.049
4.42	8.4775	18.735	4.92	11.692	28.763	5.42	15.631	42.361
4.43	8.5351	18.905	4.93	11.764	28.997	5.43	15.718	42.675
4.44	8.5931	19.077	4.94	11.835	29.233	5.44	15.805	42.990
4.45	8.6513	19.249	4.95	11.907	29.471	5.45	15.892	43.307
4.46	8.7097	19.423	4.96	11.980	29.710	5.46	15.980	43.626
4.47	8.7684	19.597	4.97	12.052	29.950	5.47	16.068	43.946
4.48	8.8274	19.773	4.98	12.125	30.192	5.48	16.156	44.268
4.49	8.8867	19.951	4.99	12.198	30.435	5.49	16.245	44.592

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli and Moments of Inertia for Round Shafts (English or Metric Units)

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
5.5	16.3338	44.9180	30	2650.72	39760.8	54.5	15892.4	433068
6	21.2058	63.6173	30.5	2785.48	42478.5	55	16333.8	449180
6.5	26.9612	87.6241	31	2924.72	45333.2	55.5	16783.4	465738
7	33.6739	117.859	31.5	3068.54	48329.5	56	17241.1	482750
7.5	41.4175	155.316	32	3216.99	51471.9	56.5	17707.0	500223
8	50.2655	201.062	32.5	3370.16	54765.0	57	18181.3	518166
8.5	60.2916	256.239	33	3528.11	58213.8	57.5	18663.9	536588
9	71.5694	322.062	33.5	3690.92	61822.9	58	19155.1	555497
9.5	84.1726	399.820	34	3858.66	65597.2	58.5	19654.7	574901
10	98.1748	490.874	34.5	4031.41	69541.9	59	20163.0	594810
10.5	113.650	596.660	35	4209.24	73661.8	59.5	20680.0	615230
11	130.671	718.688	35.5	4392.23	77962.1	60	21205.8	636173
11.5	149.312	858.541	36	4580.44	82448.0	60.5	21740.3	657645
12	169.646	1017.88	36.5	4773.96	87124.7	61	22283.8	679656
12.5	191.748	1198.42	37	4972.85	91997.7	61.5	22836.3	702215
13	215.690	1401.98	37.5	5177.19	97072.2	62	23397.8	725332
13.5	241.547	1630.44	38	5387.05	102354	62.5	23968.4	749014
14	269.392	1885.74	38.5	5602.50	107848	63	24548.3	773272
14.5	299.298	2169.91	39	5823.63	113561	63.5	25137.4	798114
15	331.340	2485.05	39.5	6050.50	119497	64	25735.9	823550
15.5	365.591	2833.33	40	6283.19	125664	64.5	26343.8	849589
16	402.124	3216.99	40.5	6521.76	132066	65	26961.2	876241
16.5	441.013	3638.36	41	6766.30	138709	65.5	27588.2	903514
17	482.333	4099.83	41.5	7016.88	145600	66	28224.9	931420
17.5	526.155	4603.86	42	7273.57	152745	66.5	28871.2	959967
18	572.555	5153.00	42.5	7536.45	160150	67	29527.3	989166
18.5	621.606	5749.85	43	7805.58	167820	67.5	30193.3	1019025
19	673.381	6397.12	43.5	8081.05	175763	68	30869.3	1049556
19.5	727.954	7097.55	44	8362.92	183984	68.5	31555.2	1080767
20	785.398	7853.98	44.5	8651.27	192491	69	32251.3	1112670
20.5	845.788	8669.33	45	8946.18	201289	69.5	32957.5	1145273
21	909.197	9546.56	45.5	9247.71	210385	70	33673.9	1178588
21.5	975.698	10488.8	46	9555.94	219787	70.5	34400.7	1212625
22	1045.36	11499.0	46.5	9870.95	229499	71	35137.8	1247393
22.5	1118.27	12580.6	47	10192.8	239531	71.5	35885.4	1282904
23	1194.49	13736.7	47.5	10521.6	249887	72	36643.5	1319167
23.5	1274.10	14970.7	48	10857.3	260576	72.5	37412.3	1356194
24	1357.17	16286.0	48.5	11200.2	271604	73	38191.7	1393995
24.5	1443.77	17686.2	49	11550.2	282979	73.5	38981.8	1432581
25	1533.98	19174.8	49.5	11907.4	294707	74	39782.8	1471963
25.5	1627.87	20755.4	50	12271.8	306796	74.5	40594.6	1512150
26	1725.52	22431.8	50.5	12643.7	319253	75	41417.5	1553156
26.5	1827.00	24207.7	51	13023.0	332086	75.5	42251.4	1594989
27	1932.37	26087.0	51.5	13409.8	345302	76	43096.4	1637662
27.5	2041.73	28073.8	52	13804.2	358908	76.5	43952.6	1681186
28	2155.13	30171.9	52.5	14206.2	372913	77	44820.0	1725571
28.5	2272.66	32385.4	53	14616.0	387323	77.5	45698.8	1770829
29	2394.38	34718.6	53.5	15033.5	402147	78	46589.0	1816972
29.5	2520.38	37175.6	54	15459.0	417393	78.5	47490.7	1864011

Copyright 2004, Industrial Press, Inc., New York, NY

Section Moduli and Moments of Inertia for Round Shafts (English or Metric Units)

Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia	Dia.	Section Modulus	Moment of Inertia
79	48404.0	1911958	103.5	108848	5632890	128	205887	13176795
79.5	49328.9	1960823	104	110433	5742530	128.5	208310	13383892
80	50265.5	2010619	104.5	112034	5853762	129	210751	13593420
80.5	51213.9	2061358	105	113650	5966602	129.5	213211	13805399
81	52174.1	2113051	105.5	115281	6081066	130	215690	14019848
81.5	53146.3	2165710	106	116928	6197169	130.5	218188	14236786
82	54130.4	2219347	106.5	118590	6314927	131	220706	14456231
82.5	55126.7	2273975	107	120268	6434355	131.5	223243	14678204
83	56135.1	2329605	107.5	121962	6555469	132	225799	14902723
83.5	57155.7	2386249	108	123672	6678285	132.5	228374	15129808
84	58188.6	2443920	108.5	125398	6802818	133	230970	15359478
84.5	59233.9	2502631	109	127139	6929085	133.5	233584	15591754
85	60291.6	2562392	109.5	128897	7057102	134	236219	15826653
85.5	61361.8	2623218	110	130671	7186884	134.5	238873	16064198
86	62444.7	2685120	110.5	132461	7318448	135	241547	16304406
86.5	63540.1	2748111	111	134267	7451811	135.5	244241	16547298
87	64648.4	2812205	111.5	136089	7586987	136	246954	16792893
87.5	65769.4	2877412	112	137928	7723995	136.5	249688	17041213
88	66903.4	2943748	112.5	139784	7862850	137	252442	17292276
88.5	68050.2	3011223	113	141656	8003569	137.5	255216	17546104
89	69210.2	3079853	113.5	143545	8146168	138	258010	17802715
89.5	70383.2	3149648	114	145450	8290664	138.5	260825	18062131
90	71569.4	3220623	114.5	147372	8437074	139	263660	18324372
90.5	72768.9	3292791	115	149312	8585414	139.5	266516	18589458
91	73981.7	3366166	115.5	151268	8735703	140	269392	18857410
91.5	75207.9	3440759	116	153241	8887955	140.5	272288	19128248
92	76447.5	3516586	116.5	155231	9042189	141	275206	19401993
92.5	77700.7	3593659	117	157238	9198422	141.5	278144	19678666
93	78967.6	3671992	117.5	159262	9356671	142	281103	19958288
93.5	80248.1	3751598	118	161304	9516953	142.5	284083	20240878
94	81542.4	3832492	118.5	163363	9679286	143	287083	20526460
94.5	82850.5	3914688	119	165440	9843686	143.5	290105	20815052
95	84172.6	3998198	119.5	167534	10010172	144	293148	21106677
95.5	85508.6	4083038	120	169646	10178760	144.5	296213	21401356
96	86858.8	4169220	120.5	171775	10349469	145	299298	21699109
96.5	88223.0	4256760	121	173923	10522317	145.5	302405	21999959
97	89601.5	4345671	121.5	176088	10697321	146	305533	22303926
97.5	90994.2	4435968	122	178270	10874498	146.5	308683	22611033
98	92401.3	4527664	122.5	180471	11053867	147	311854	22921300
98.5	93822.8	4620775	123	182690	11235447	147.5	315047	23234749
99	95258.9	4715315	123.5	184927	11419254	148	318262	23551402
99.5	96709.5	4811298	124	187182	11605307	148.5	321499	23871280
100	98174.8	4908739	124.5	189456	11793625	149	324757	24194406
100.5	99654.8	5007652	125	191748	11984225	149.5	328037	24520802
101	101150	5108053	125.5	194058	12177126	150	331340	24850489
101.5	102659	5209956	126	196386	12372347	…	…	…
102	104184	5313376	126.5	198734	12569905	…	…	…
102.5	105723	5418329	127	201100	12769820	…	…	…
103	107278	5524828	127.5	203484	12972110	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

BEAMS

Beam Calculations

Reaction at the Supports.— When a beam is loaded by vertical loads or forces, the sum of the reactions at the supports equals the sum of the loads. In a simple beam, when the loads are symmetrically placed with reference to the supports, or when the load is uniformly distributed, the reaction at each end will equal one-half of the sum of the loads. When the loads are not symmetrically placed, the reaction at each support may be ascertained from the fact that the algebraic sum of the moments must equal zero. In the accompanying illustration, if moments are taken about the support to the left, then: $R_2 \times 40 - 8000 \times 10 - 10{,}000 \times 16 - 20{,}000 \times 20 = 0$; $R_2 = 16{,}000$ pounds. In the same way, moments taken about the support at the right give $R_1 = 22{,}000$ pounds.



The sum of the reactions equals 38,000 pounds, which is also the sum of the loads. If part of the load is uniformly distributed over the beam, this part is first equally divided between the two supports, or the uniform load may be considered as concentrated at its center of gravity.

If metric SI units are used for the calculations, distances may be expressed in meters or millimeters, providing the treatment is consistent, and loads in newtons. ***Note:*** **If the load is given in kilograms, the value referred to is the mass. A mass of *M* kilograms has a weight (applies a force) of *Mg* newtons, where *g* = approximately 9.81 meters per second^2.**

Stresses and Deflections in Beams.— On the following pages Table 1 gives an extensive list of formulas for stresses and deflections in beams, shafts, etc. It is assumed that all the dimensions are in inches, all loads in pounds, and all stresses in pounds per square inch. **The formulas are also valid using metric SI units, with all dimensions in millimeters, all loads in newtons, and stresses and moduli in newtons per millimeter^2 (N/mm^2).** ***Note:*** **A load due to the weight of a mass of *M* kilograms is *Mg* newtons, where *g* = approximately 9.81 meters per second^2.** In the tables:

E = modulus of elasticity of the material

I = moment of inertia of the cross-section of the beam

Z = section modulus of the cross-section of the beam = $I \div$ distance from neutral axis to extreme fiber

W = load on beam

s = stress in extreme fiber, or maximum stress in the cross-section considered, due to load W. A positive value of s denotes tension in the upper fibers and compression in the lower ones (as in a cantilever). A negative value of s denotes the reverse (as in a beam supported at the ends). The greatest safe load is that value of W which causes a maximum stress equal to, but not exceeding, the greatest safe value of s

y = deflection measured from the position occupied if the load causing the deflection were removed. A positive value of y denotes deflection below this position; a negative value, deflection upward

u, v, w, x = variable distances along the beam from a given support to any point

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Stresses and Deflections in Beams

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 1. — Supported at Both Ends, Uniform Load				
	$s = -\frac{W}{2Zl}x(l-x)$	Stress at center, $-\frac{Wl}{8Z}$ If cross-section is constant, this is the maximum stress.	$y = \frac{Wx(l-x)}{24EIl}[l^2 + x(l-x)]$	Maximum deflection, at center, $\frac{5}{384}\frac{Wl^3}{EI}$
Case 2. — Supported at Both Ends, Load at Center				
	Between each support and load, $s = -\frac{Wx}{2Z}$	Stress at center, $-\frac{Wl}{4Z}$ If cross-section is constant, this is the maximum stress.	Between each support and load, $y = \frac{Wx}{48EI}(3l^2 - 4x^2)$	Maximum deflection, at load, $\frac{Wl^3}{48EI}$
Case 3. — Supported at Both Ends, Load at any Point				
	For segment of length a, $s = -\frac{Wbx}{Zl}$ For segment of length b, $s = -\frac{Wav}{Zl}$	Stress at load, $-\frac{Wab}{Zl}$ If cross-section is constant, this is the maximum stress.	For segment of length a, $y = \frac{Wbx}{6EIl}(l^2 - x^2 - b^2)$ For segment of length b, $y = \frac{Wav}{6EIl}(l^2 - v^2 - a^2)$	Deflection at load, $\frac{Wa^2b^2}{3EIl}$ Let a be the length of the shorter segment and b of the longer one. The maximum deflection $\frac{Wav_1^3}{3EIl}$ is in the longer segment, at $v = b\sqrt{\frac{1}{3} + \frac{2a}{3b}} = v_1$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 4. — Supported at Both Ends, Two Symmetrical Loads				
	Between each support and adjacent load, $s = -\frac{Wx}{Z}$ Between loads, $s = -\frac{Wa}{Z}$	Stress at each load, and at all points between, $-\frac{Wa}{Z}$	Between each support and adjacent load, $y = \frac{Wx}{6EI}[3a(l-a) - x^2]$ Between loads, $y = \frac{Wa}{6EI}[3v(l-v) - a^2]$	Maximum deflection at center, $\frac{Wa}{24EI}(3l^2 - 4a^2)$ Deflection at loads $\frac{Wa^2}{6EI}(3l - 4a)$
Case 5. — Both Ends Overhanging Supports Symmetrically, Uniform Load				
	Between each support and adjacent end, $s = \frac{W}{2Zl}(c-u)^2$ Between supports, $s = \frac{W}{2ZL}[c^2 - x(l-x)]$	Stress at each support, $\frac{Wc^2}{2ZL}$ Stress at center, $\frac{W}{2ZL}(c^2 - \frac{1}{4}l^2)$ If cross-section is constant, the greater of these is the maximum stress. If l is greater than $2c$, the stress is zero at points $\sqrt{\frac{1}{4}l^2 - c^2}$ on both sides of the center. If cross-section is constant and if $l = 2.828c$, the stresses at supports and center are equal and opposite, and are $\pm\frac{WL}{46.62Z}$	Between each support and adjacent end, $y = \frac{Wu}{24EIL}[6c^2(l+u) - u^2(4c-u) - l^3]$ Between supports, $y = \frac{Wx(l-x)}{24EIL}[x(l-x) + l^2 - 6c^2]$	Deflection at ends, $\frac{Wc}{24EIL}[3c^2(c+2l) - l^3]$ Deflection at center, $\frac{Wl^2}{384EIL}(5l^2 - 24c^2)$ If l is between $2c$ and $2.449c$, there are maximum upward deflections at points $\sqrt{3(\frac{1}{4}l^2 - c^2)}$ on both sides of the center, which are, $-\frac{W}{96EIL}(6c^2 - l^2)^2$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses: General Formula for Stress at any Point	Stresses: Stresses at Critical Points	Deflections: General Formula for Deflection at any Point[a]	Deflections: Deflections at Critical Points[a]
Case 6. — Both Ends Overhanging Supports Unsymmetrically, Uniform Load				
	For overhanging end of length c, $s = \frac{W}{2ZL}(c-u)^2$ Between supports, $s = \frac{W}{2ZL}\left\{c^2\left(\frac{l-x}{l}\right) + d^2\frac{x}{l} - x(l-x)\right\}$ For overhanging end of length d, $s = \frac{W}{2ZL}(d-w)^2$	Stress at support next to end of length c, $\frac{Wc^2}{2ZL}$ Critical stress between supports is at $x = \frac{l^2+c^2-d^2}{2l} = x_1$ and is $\frac{W}{2ZL}(c^2-x_1^2)$ Stress at support next to end of length d, $\frac{Wd^2}{2ZL}$ If cross-section is constant, the greatest of these three is the maximum stress. If $x_1 > c$, the stress is zero at points $\sqrt{x_1^2-c^2}$ on both sides of $x = x_1$.	For overhanging end of length c, $y = \frac{Wu}{24EIL}[2l(d^2+2c^2) + 6c^2u - u^2(4c-u) - l^3]$ Between supports, $y = \frac{Wx(l-x)}{24EIL}\{x(l-x) + l^2 - 2(d^2+c^2) - \frac{2}{l}[d^2x + c^2(l-x)]\}$ For overhanging end of length d, $y = \frac{Ww}{24EIL}[2l(c^2+2d^2) + 6d^2w - w^2(4d-w) - l^3]$	Deflection at end c, $\frac{Wc}{24EIL}[2l(d^2+2c^2) + 3c^3 - l^3]$ Deflection at end d, $\frac{Wd}{24EIL}[2l(c^2+2d^2) + 3d^3 - l^3]$ This case is so complicated that convenient general expressions for the critical deflections between supports cannot be obtained.
Case 7. — Both Ends Overhanging Supports, Load at any Point Between				
	Between supports: For segment of length a, $s = -\frac{Wbx}{Zl}$ For segment of length b, $s = -\frac{Wav}{Zl}$ Beyond supports $s = 0$.	Stress at load, $-\frac{Wab}{Zl}$ If cross-section is constant, this is the maximum stress.	Between supports, same as Case 3. For overhanging end of length c, $y = -\frac{Wabu}{6EIl}(l+b)$ For overhanging end of length d, $y = -\frac{Wabw}{6EIl}(l+a)$	Between supports, same as Case 3. Deflection at end c, $-\frac{Wabc}{6EIl}(l+b)$ Deflection at end d, $-\frac{Wabd}{6EIl}(l+a)$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 8. — Both Ends Overhanging Supports, Single Overhanging Load				
	Between load and adjacent support, $s = \frac{W}{Z}(c-u)$ Between supports, $s = \frac{Wc}{Zl}(l-x)$ Between unloaded end and adjacent supports, $s = 0$.	Stress at support adjacent to load, $\frac{Wc}{Z}$ If cross-section is constant, this is the maximum stress. Stress is zero at other support.	Between load and adjacent support, $y = \frac{Wu}{6EI}(3cu - u^2 + 2cl)$ Between supports, $y = -\frac{Wcx}{6EIl}(l-x)(2l-x)$ Between unloaded end and adjacent support, $y = \frac{Wclw}{6EI}$	Deflection at load, $\frac{Wc^2}{3EI}(c+l)$ Maximum upward deflection is at $x = .42265l$, and is $-\frac{Wcl^2}{15.55EI}$ Deflection at unloaded end, $\frac{Wcld}{6EI}$
Case 9. — Both Ends Overhanging Supports, Symmetrical Overhanging Loads				
	Between each load and adjacent support, $s = \frac{W}{Z}(c-u)$ Between supports, $s = \frac{Wc}{Z}$	Stress at supports and at all points between, $\frac{Wc}{Z}$ If cross-section is constant, this is the maximum stress.	Between each load and adjacent support, $y = \frac{Wu}{6EI}[3c(l+u) - u^2]$ Between supports, $y = -\frac{Wcx}{2EI}(l-x)$	Deflections at loads, $\frac{Wc^2}{6EI}(2c+3l)$ Deflection at center, $-\frac{Wcl^2}{8EI}$
			The above expressions involve the usual approximations of the theory of flexure, and hold only for small deflections. Exact expressions for deflections of any magnitude are as follows: Between supports the curve is a circle of radius $r = \frac{EI}{Wc}$ Deflection at any point x between supports $y = \sqrt{r^2 - \frac{1}{4}l^2} - \sqrt{r^2 - (\frac{1}{2}l - x)^2}$ Deflection at center, $\sqrt{r^2 - \frac{1}{4}l^2} - r$	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 10. — Fixed at One End, Uniform Load				
	$s = \frac{W}{2Zl}(l-x)^2$	Stress at support, $\frac{Wl}{2Z}$ If cross-section is constant, this is the maximum stress.	$y = \frac{Wx^2}{24EIl}[2l^2 + (2l-x)^2]$	Maximum deflection, at end, $\frac{Wl^3}{8EI}$
Case 11. — Fixed at One End, Load at Other				
	$s = \frac{W}{Z}(l-x)$	Stress at support, $\frac{Wl}{Z}$ If cross-section is constant, this is the maximum stress.	$y = \frac{Wx^2}{6EI}(3l-x)$	Maximum deflection, at end, $\frac{Wl^3}{3EI}$
Case 12. — Fixed at One End, Intermediate Load				
	Between support and load, $s = \frac{W}{Z}(l-x)$ Beyond load, $s = 0$.	Stress at support, $\frac{Wl}{Z}$ If cross-section is constant, this is the maximum stress.	Between support and load, $y = \frac{Wx^2}{6EI}(3l-x)$ Beyond load, $y = \frac{Wl^2}{6EI}(3v-l)$	Deflection at load, $\frac{Wl^3}{3EI}$ Maximum deflection, at end, $\frac{Wl^2}{6EI}(2l+3b)$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 13. — Fixed at One End, Supported at the Other, Load at Center				
	Between point of fixture and load, $s = \frac{W}{16Z}(3l - 11x)$ Between support and load, $s = -\frac{5}{16}\frac{Wv}{Z}$	Maximum stress at point of fixture, $\frac{3}{16}\frac{Wl}{Z}$ Stress is zero at $x = \frac{3}{11}l$ Greatest negative stress at center, $-\frac{5}{32}\frac{Wl}{Z}$	Between point of fixture and load, $y = \frac{Wx^2}{96EI}(9l - 11x)$ Between support and load, $y = \frac{Wv}{96EI}(3l^2 - 5v^2)$	Maximum deflection is at $v =$ 0.4472l, and is $\frac{Wl^3}{107.33EI}$ Deflection at load, $\frac{7}{768}\frac{Wl^3}{EI}$
Case 14. — Fixed at One End, Supported at the Other, Load at any Point				
$m = (l + a)(l + b) + al$ $n = al(l + b)$ 	Between point of fixture and load, $s = \frac{Wb}{2Zl^3}(n - mx)$ Between support and load, $s = -\frac{Wa^2v}{2Zl^3}(3l - a)$	Greatest positive stress, at point of fixture, $\frac{Wab}{2Zl^2}(l + b)$ Greatest negative stress, at load, $-\frac{Wa^2b}{2Zl^3}(3l - a)$ If $a < 0.5858l$, the first is the maximum stress. If $a =$ 0.5858l, the two are equal and are $\pm\frac{Wl}{5.83Z}$ If $a >$ 0.5858l, the second is the maximum stress. Stress is zero at $x = \frac{n}{m}$	Between point of fixture and load, $y = \frac{Wx^2b}{12EIl^3}(3n - mx)$ Between support and load, $y = \frac{Wa^2v}{12EIl^3}[3l^2b - v^2(3l - a)]$	Deflection at load, $\frac{Wa^3b^2}{12EIl^3}(3l + b)$ If $a < 0.5858l$, maximum deflection is $\frac{Wa^2b}{6EI}\sqrt{\frac{b}{2l + b}}$ and located between load and support, at $v = l\sqrt{\frac{b}{2l + b}}$ If $a = 0.5858l$, maximum deflection is at load and is $\frac{Wl^3}{101.9EI}$ If $a > 0.5858l$, maximum deflection is $\frac{Wbn^3}{3EIm^2l^3}$ and located between load and point of fixture, at $x = \frac{2n}{m}$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 15. — Fixed at One End, Supported at the Other, Uniform Load				
	$s = \frac{W(l-x)}{2Zl}(\frac{1}{4}l - x)$	Maximum stress at point of fixture, $\frac{Wl}{8Z}$ Stress is zero at $x = \frac{1}{4}l$. Greatest negative stress is at $x = \frac{5}{8}l$ and is $-\frac{9}{128}\frac{Wl}{Z}$	$y = \frac{Wx^2(l-x)}{48EIl}(3l - 2x)$	Maximum deflection is at $x =$ 0.5785l, and is $\frac{Wl^3}{185EI}$ Deflection at center, $\frac{Wl^3}{192EI}$ Deflection at point of greatest negative stress, at $x = \frac{5}{8}l$ is $\frac{Wl^3}{187EI}$
Case 16. — Fixed at One End, Free but Guided at the Other, Uniform Load				
	$s = \frac{Wl}{Z}\left\{\frac{1}{3} - \frac{x}{l} + \frac{1}{2}\left(\frac{x}{l}\right)^2\right\}$	Maximum stress, at support, $\frac{Wl}{3Z}$ Stress is zero at $x = 0.4227l$ Greatest negative stress, at free end, $-\frac{Wl}{6Z}$	$y = \frac{Wx^2}{24EIl}(2l - x)^2$	Maximum deflection, at free end, $\frac{Wl^3}{24EI}$
Case 17. — Fixed at One End, Free but Guided at the Other, with Load				
	$s = \frac{W}{Z}(\frac{1}{2}l - x)$	Stress at support, $\frac{Wl}{2Z}$ Stress at free end $-\frac{Wl}{2Z}$ These are the maximum stresses and are equal and opposite. Stress is zero at center.	$y = \frac{Wx^2}{12EI}(3l - 2x)$	Maximum deflection, at free end, $\frac{Wl^3}{12EI}$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 18. — Fixed at Both Ends, Load at Center				
	Between each end and load, $s = \frac{W}{2Z}(\frac{1}{4}l - x)$	Stress at ends $\frac{Wl}{8Z}$ Stress at load $-\frac{Wl}{8Z}$ These are the maximum stresses and are equal and opposite. Stress is zero at $x = \frac{1}{4}l$	$y = \frac{Wx^2}{48EI}(3l - 4x)$	Maximum deflection, at load, $\frac{Wl^3}{192EI}$
Case 19. — Fixed at Both Ends, Load at any Point				
	For segment of length a, $s = \frac{Wb^2}{Zl^3}[al - x(l + 2a)]$ For segment of length b, $s = \frac{Wa^2}{Zl^3}[bl - v(l + 2b)]$	Stress at end next to segment of length a, $\frac{Wab^2}{Zl^2}$ Stress at end next to segment of length b, $\frac{Wa^2b}{Zl^2}$ Maximum stress is at end next to shorter segment. Stress is zero at $x = \frac{al}{l + 2a}$ and $v = \frac{bl}{l + 2b}$ Greatest negative stress, at load, $-\frac{2Wa^2b^2}{Zl^3}$	For segment of length a, $y = \frac{Wx^2b^2}{6EIl^3}[2a(l - x) + l(a - x)]$ For segment of length b, $y = \frac{Wv^2a^2}{6EIl^3}[2b(l - v) + l(b - v)]$	Deflection at load, $\frac{Wa^3b^3}{3EIl^3}$ Let b be the length of the longer segment and a of the shorter one. The maximum deflection is in the longer segment, at $v = \frac{2bl}{l + 2b}$ and is $\frac{2Wa^2b^3}{3EI(l + 2b)^2}$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses: General Formula for Stress at any Point	Stresses: Stresses at Critical Points	Deflections: General Formula for Deflection at any Point[a]	Deflections: Deflections at Critical Points[a]
Case 20. — Fixed at Both Ends, Uniform Load				
	$s = \frac{Wl}{2Z}\left\{\frac{1}{6} - \frac{x}{l} + \left(\frac{x}{l}\right)^2\right\}$	Maximum stress, at ends, $\frac{Wl}{12Z}$ Stress is zero at $x = 0.7887l$ and at $x = 0.2113l$ Greatest negative stress, at center, $-\frac{Wl}{24Z}$	$y = \frac{Wx^2}{24EIl}(l-x)^2$	Maximum deflection, at center, $\frac{Wl^3}{384EI}$
Case 21. — Continuous Beam, with Two Unequal Spans, Unequal, Uniform Loads				
	Between R_1 and R, $s = \frac{l_1-x}{Z}\left\{\frac{(l_1-x)W_1}{2l_1} - R_1\right\}$ Between R_2 and R, $s = \frac{l_2-u}{Z}\left\{\frac{(l_2-u)W_2}{2l_2} - R_2\right\}$	Stress at support R, $\frac{W_1l_1^2+W_2l_2^2}{8Z(l_1+l_2)}$ Greatest stress in the first span is at $x = \frac{l_1}{W_1}(W_1-R_1)$ and is $-\frac{R_1^2l_1}{2ZW_1}$ Greatest stress in the second span is at $u = \frac{l_2}{W_2}(W_2-R_2)$ and is, $-\frac{R_2^2l_2}{2ZW_2}$	Between R_1 and R, $y = \frac{x(l_1-x)}{24EI}\left\{(2l_1-x)(4R_1-W_1) - \frac{W_1(l_1-x)^2}{l_1}\right\}$ Between R_2 and R, $y = \frac{u(l_2-u)}{24EI}\left\{(2l_2-u)(4R_2-W_2) - \frac{W_2(l_2-u)^2}{l_2}\right\}$	This case is so complicated that convenient general expressions for the critical deflections cannot be obtained.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 22. — Continuous Beam, with Two Equal Spans, Uniform Load				
TOTAL LOAD ON EACH SPAN, W  	$s = \frac{W(l-x)}{2Zl}(\frac{1}{4}l - x)$	Maximum stress at point A, $\frac{Wl}{8Z}$ Stress is zero at $x = \frac{1}{4}l$ Greatest negative stress is at $x = \frac{5}{8}l$ and is, $-\frac{9}{128}\frac{Wl}{Z}$	$y = \frac{Wx^2(l-x)}{48EIl}(3l - 2x)$	Maximum deflection is at $x = 0.5785l$, and is $\frac{Wl^3}{185EI}$ Deflection at center of span, $\frac{Wl^3}{192EI}$ Deflection at point of greatest negative stress, at $x = \frac{5}{8}l$ is $\frac{Wl^3}{187EI}$
Case 23. — Continuous Beam, with Two Equal Spans, Equal Loads at Center of Each				
 	Between point A and load, $s = \frac{W}{16Z}(3l - 11x)$ Between point B and load, $s = -\frac{5}{16}\frac{Wv}{Z}$	Maximum stress at point A, $\frac{3}{16}\frac{Wl}{Z}$ Stress is zero at $x = \frac{3}{11}l$ Greatest negative stress at center of span, $-\frac{5}{32}\frac{Wl}{Z}$	Between point A and load, $y = \frac{Wx^2}{96EI}(9l - 11x)$ Between point B and load, $y = \frac{Wv}{96EI}(3l^2 - 5v^2)$	Maximum deflection is at $v = 0.4472l$, and is $\frac{Wl^3}{107.33EI}$ Deflection at load, $\frac{7}{768}\frac{Wl^3}{EI}$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Stresses and Deflections in Beams**

Type of Beam	Stresses		Deflections	
	General Formula for Stress at any Point	Stresses at Critical Points	General Formula for Deflection at any Point[a]	Deflections at Critical Points[a]
Case 24. — Continuous Beam, with Two Unequal Spans, Unequal Loads at any Point of Each				
$m = \frac{1}{2(l_1+l_2)}\left(\frac{W_1a_1b_1}{l_1}(l_1+a_1)+\frac{W_2a_2b_2}{l_2}(l_2+a_2)\right)$  $\frac{W_1b_1-m}{l_1}$ $\frac{W_1a_1+m}{l_1}+\frac{W_2a_2+m}{l_2}$ $\frac{W_2b_2-m}{l_2}$ $= r_1$ $= r$ $= r_2$	Between R_1 and W_1, $s = -\frac{wr_1}{Z}$ Between R and W_1, $s =$ $\frac{1}{l_1Z}[m(l_1-u)-W_1a_1u]$ Between R and W_2, $s =$ $\frac{1}{l_2Z}[m(l_2-x)-W_2a_2x]$ Between R_2 and W_2, $s = -\frac{vr_2}{Z}$	Stress at load W_1, $-\frac{a_1r_1}{Z}$ Stress at support R, $\frac{m}{Z}$ Stress at load W_2, $-\frac{a_2r_2}{Z}$ The greatest of these is the maximum stress.	Between R_1 and W_1, $y = \frac{w}{6EI}\left\{(l_1-w)(l_1+w)r_1-\frac{W_1b_1^3}{l_1}\right\}$ Between R and W_1, $y = \frac{u}{6EIl_1}[W_1a_1b_1(l_1+a_1)$ $-W_1a_1u^2-m(2l_1-u)(l_1-u)]$ Between R and W_2 $y = \frac{x}{6EIl_2}[W_2a_2b_2(l_2+a_2)$ $-W_2a_2x^2-m(2l_2-x)(l_2-x)]$ Between R_2 and W_2, $y = \frac{v}{6EI}\left\{(l_2-v)(l_2+v)r_2-\frac{W_2b_2^3}{l_2}\right\}$	Deflection at load W_1, $\frac{a_1b_1}{6EIl_1}[2a_1b_1W_1$ $-m(l_1+a_1)]$ Deflection at load W_2, $\frac{a_2b_2}{6EIl_2}[2a_2b_2W_2$ $-m(l_2+a_2)]$ This case is so complicated that convenient general expressions for the maximum deflections cannot be obtained.

[a] The deflections apply only to cases where the cross section of the beam is constant for its entire length.

In the diagrammatical illustrations of the beams and their loading, the values indicated near, but below, the supports are the "reactions" or upward forces at the supports. For Cases 1 to 12, inclusive, the reactions, as well as the formulas for the stresses, are the same whether the beam is of constant or variable cross-section. For the other cases, the reactions and the stresses given are for constant cross-section beams only.

The bending moment at any point in inch-pounds is $s \times Z$ and can be found by omitting the divisor Z in the formula for the stress given in the tables. A positive value of the bending moment denotes tension in the upper fibers and compression in the lower ones. A negative value denotes the reverse, The value of W corresponding to a given stress is found by transposition of the formula. For example, in Case 1, the stress at the critical point is $s = -Wl \div 8Z$. From this formula we find $W = -8Zs \div l$. Of course, the negative sign of W may be ignored.

Copyright 2004, Industrial Press, Inc., New York, NY

In Table 1, if there are several kinds of loads, as, for instance, a uniform load and a load at any point, or separate loads at different points, the total stress and the total deflection at any point is found by adding together the various stresses or deflections at the point considered due to each load acting by itself. If the stress or deflection due to any one of the loads is negative, it must be subtracted instead of added.

Tables 2a and 2b give expressions for determining dimensions of rectangular and round beams in terms of beam stresses and load.

Table 2a. Rectangular Solid Beams

Style of Loading and Support	Breadth of Beam, b inch (mm)	Beam Height, h inch (mm)	Stress in Extreme Fibers, f lb/in² (N/mm²)	Beam Length, l inch (mm)	Total Load, W lb (N)
	Beam fixed at one end, loaded at the other				
	$\frac{6lW}{fh^2} = b$	$\sqrt{\frac{6lW}{bf}} = h$	$\frac{6lW}{bh^2} = f$	$\frac{bfh^2}{6W} = l$	$\frac{bfh^2}{6l} = W$
	Beam fixed at one end, uniformly loaded				
	$\frac{3lW}{fh^2} = b$	$\sqrt{\frac{3lW}{bf}} = h$	$\frac{3lW}{bh^2} = f$	$\frac{bfh^2}{3W} = l$	$\frac{bfh^2}{3l} = W$
	Beam supported at both ends, single load in middle				
	$\frac{3lW}{2fh^2} = b$	$\sqrt{\frac{3lW}{2bf}} = h$	$\frac{3lW}{2bh^2} = f$	$\frac{2bfh^2}{3W} = l$	$\frac{2bfh^2}{3l} = W$
	Beam supported at both ends, uniformly loaded				
	$\frac{3lW}{4fh^2} = b$	$\sqrt{\frac{3lW}{4bf}} = h$	$\frac{3lW}{4bh^2} = f$	$\frac{4bfh^2}{3W} = l$	$\frac{4bfh^2}{3l} = W$
	Beam supported at both ends, single unsymmetrical load				
	$\frac{6Wac}{fh^2l} = b$	$\sqrt{\frac{6Wac}{bfl}} = h$	$\frac{6Wac}{bh^2l} = f$	$a + c = l$	$\frac{bh^2fl}{6ac} = W$
	Beam supported at both ends, two symmetrical loads				
	$\frac{3Wa}{fh^2} = b$	$\sqrt{\frac{3Wa}{bf}} = h$	$\frac{3Wa}{bh^2} = f$	l, any length $\frac{bh^2f}{3W} = a$	$\frac{bh^2f}{3a} = W$

Deflection of Beam Uniformly Loaded for Part of Its Length.— In the following formulas, lengths are in inches, weights in pounds. W = total load; L = total length between supports; E = modulus of elasticity; I = moment of inertia of beam section; a = fraction of length of beam at each end, that is not loaded = $b \div L$; and f = deflection.

$$f = \frac{WL^3}{384EI(1-2a)}(5 - 24a^2 + 16a^4)$$

The expression for maximum bending moment is: $M_{max} = \frac{1}{8}WL(1 + 2a)$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Round Solid Beams

Style of Loading and Support	Diameter of Beam, d inch (mm)	Stress in Extreme Fibers, f lb/in² (N/mm²)	Beam Length, l inch (mm)	Total Load, W lb (N)
	Beam fixed at one end, loaded at the other			
	$\sqrt[3]{\frac{10.18lW}{f}} = d$	$\frac{10.18lW}{d^3} = f$	$\frac{d^3f}{10.18W} = l$	$\frac{d^3f}{10.18l} = W$
	Beam fixed at one end, uniformly loaded			
	$\sqrt[3]{\frac{5.092Wl}{f}} = d$	$\frac{5.092Wl}{d^3} = f$	$\frac{d^3f}{5.092W} = l$	$\frac{d^3f}{5.092l} = W$
	Beam supported at both ends, single load in middle			
	$\sqrt[3]{\frac{2.546Wl}{f}} = d$	$\frac{2.546Wl}{d^3} = f$	$\frac{d^3f}{2.546W} = l$	$\frac{d^3f}{2.546l} = W$
	Beam supported at both ends, uniformly loaded			
	$\sqrt[3]{\frac{1.273Wl}{f}} = d$	$\frac{1.273Wl}{d^3} = f$	$\frac{d^3f}{1.273W} = l$	$\frac{d^3f}{1.273l} = W$
	Beam supported at both ends, single unsymmetrical load			
	$\sqrt[3]{\frac{10.18Wac}{fl}} = d$	$\frac{10.18Wac}{d^3l} = f$	$a + c = l$	$\frac{d^3fl}{10.18ac} = W$
	Beam supported at both ends, two symmetrical loads			
	$\sqrt[3]{\frac{5.092Wa}{f}} = d$	$\frac{5.092Wa}{d^3} = f$	l, any length $\frac{d^3f}{5.092W} = a$	$\frac{d^3f}{5.092a} = W$

These formulas apply to simple beams resting on supports at the ends.



If the formulas are used with metric SI units, W = total load in newtons; L = total length between supports in millimeters; E = modulus of elasticity in newtons per millimeter²; I = moment of inertia of beam section in millimeters⁴; a = fraction of length of beam at each end, that is not loaded = $b \div L$; and f = deflection in millimeters. The bending moment M_{max} is in newton-millimeters (N · mm).

Note: **A load due to the weight of a mass of M kilograms is Mg newtons, where g = approximately 9.81 meters per second².**

Copyright 2004, Industrial Press, Inc., New York, NY

Bending Stress Due to an Oblique Transverse Force.— The following illustration shows a beam and a channel being subjected to a transverse force acting at an angle ϕ to the center of gravity. To find the bending stress, the moments of inertia I around axes 3-3 and 4-4 are computed from the following equations: $I_3 = I_x\sin^2\phi + I_y\cos^2\phi$, and $I_4 = I_x\cos^2\phi + I_y\sin^2\phi$.

The computed bending stress f_b is then found from $f_b = M\left(\frac{y}{I_x}\sin\phi + \frac{x}{I_y}\cos\phi\right)$ where M is the bending moment due to force F.



Beams of Uniform Strength Throughout Their Length.— The bending moment in a beam is generally not uniform throughout its length, but varies. Therefore, a beam of uniform cross-section which is made strong enough at its most strained section, will have an excess of material at every other section. Sometimes it may be desirable to have the cross-section uniform, but at other times the metal can be more advantageously distributed if the beam is so designed that its cross-section varies from point to point, so that it is at every point just great enough to take care of the bending stresses at that point. Tables 3a and 3b are given showing beams in which the load is applied in different ways and which are supported by different methods, and the shape of the beam required for uniform strength is indicated. It should be noted that the shape given is the theoretical shape required to resist bending only. It is apparent that sufficient cross-section of beam must also be added either at the points of support (in beams supported at both ends), or at the point of application of the load (in beams loaded at one end), to take care of the vertical shear.

It should be noted that the theoretical shapes of the beams given in the two tables that follow are based on the stated assumptions of uniformity of width or depth of cross-section, and unless these are observed in the design, the theoretical outlines do not apply without modifications. For example, in a cantilever with the load at one end, the outline is a parabola only when the width of the beam is uniform. It is not correct to use a strictly parabolic shape when the thickness is not uniform, as, for instance, when the beam is made of an I- or T-section. In such cases, some modification may be necessary; but it is evident that whatever the shape adopted, the correct depth of the section can be obtained by an investigation of the bending moment and the shearing load at a number of points, and then a line can be drawn through the points thus ascertained, which will provide for a beam of practically uniform strength whether the cross-section be of uniform width or not.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3a. Beams of Uniform Strength Throughout Their Length

Type of Beam	Description	Formula[a]
	Load at one end. Width of beam uniform. Depth of beam decreasing towards loaded end. Outline of beam-shape, parabola with vertex at loaded end.	$P = \frac{Sbh^2}{6l}$
	Load at one end. Width of beam uniform. Depth of beam decreasing towards loaded end. Outline of beam, one-half of a parabola with vertex at loaded end. Beam may be reversed so that upper edge is parabolic.	$P = \frac{Sbh^2}{6l}$
	Load at one end. Depth of beam uniform. Width of beam decreasing towards loaded end. Outline of beam triangular, with apex at loaded end.	$P = \frac{Sbh^2}{6l}$
	Beam of *approximately* uniform strength. Load at one end. Width of beam uniform. Depth of beam decreasing towards loaded end, but not tapering to a sharp point.	$P = \frac{Sbh^2}{6l}$
	Uniformly distributed load. Width of beam uniform. Depth of beam decreasing towards outer end. Outline of beam, right-angled triangle.	$P = \frac{Sbh^2}{3l}$
	Uniformly distributed load. Depth of beam uniform. Width of beam gradually decreasing towards outer end. Outline of beam is formed by two parabolas which tangent each other at their vertexes at the outer end of the beam.	$P = \frac{Sbh^2}{3l}$

[a] In the formulas, P = load in pounds; S = safe stress in pounds per square inch; and a, b, c, h, and l are in inches. **If metric SI units are used, P is in newtons; S = safe stress in N/mm^2; and a, b, c, h, and l are in millimeters.**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. Beams of Uniform Strength Throughout Their Length

Type of Beam	Description	Formula[a]
	Beam supported at both ends. Load concentrated at any point. Depth of beam uniform. Width of beam maximum at point of loading. Outline of beam, two triangles with apexes at points of support.	$P = \frac{Sbh^2l}{6ac}$
	Beam supported at both ends. Load concentrated at any point. Width of beam uniform. Depth of beam maximum at point of loading. Outline of beam is formed by two parabolas with their vertexes at points of support.	$P = \frac{Sbh^2l}{6ac}$
	Beam supported at both ends. Load concentrated in the middle. Depth of beam uniform. Width of beam maximum at point of loading. Outline of beam, two triangles with apexes at points of support.	$P = \frac{2Sbh^2}{3l}$
	Beam supported at both ends. Load concentrated at center. Width of beam uniform. Depth of beam maximum at point of loading. Outline of beam, two parabolas with vertices at points of support.	$P = \frac{2Sbh^2}{3l}$
	Beam supported at both ends. Load uniformly distributed. Depth of beam uniform. Width of beam maximum at center. Outline of beam, two parabolas with vertexes at middle of beam.	$P = \frac{4Sbh^2}{3l}$
	Beam supported at both ends. Load uniformly distributed. Width of beam uniform. Depth of beam maximum at center. Outline of beam one-half of an ellipse.	$P = \frac{4Sbh^2}{3l}$

[a] For details of English and metric SI units used in the formulas, see footnote on page 275.

Copyright 2004, Industrial Press, Inc., New York, NY

Deflection as a Limiting Factor in Beam Design.— For some applications, a beam must be stronger than required by the maximum load it is to support, in order to prevent excessive deflection. Maximum allowable deflections vary widely for different classes of service, so a general formula for determining them cannot be given. When exceptionally stiff girders are required, one rule is to limit the deflection to 1 inch per 100 feet of span; hence, if l = length of span in inches, deflection = $l \div 1200$. According to another formula, deflection limit = $l \div 360$ where beams are adjacent to materials like plaster which would be broken by excessive beam deflection. Some machine parts of the beam type must be very rigid to maintain alignment under load. For example, the deflection of a punch press column may be limited to 0.010 inch or less. These examples merely illustrate variations in practice. It is impracticable to give general formulas for determining the allowable deflection in any specific application, because the allowable amount depends on the conditions governing each class of work.

Procedure in Designing for Deflection: Assume that a deflection equal to $l \div 1200$ is to be the limiting factor in selecting a wide-flange (W-shape) beam having a span length of 144 inches. Supports are at both ends and load at center is 15,000 pounds. Deflection y is to be limited to $144 \div 1200 = 0.12$ inch. According to the formula on page 261 (Case 2), in which W = load on beam in pounds, l = length of span in inches, E = modulus of elasticity of material, I = moment of inertia of cross section:

$$\text{Deflection } y = \frac{Wl^3}{48EI} \quad \text{hence, } I = \frac{Wl^3}{48yE} = \frac{15{,}000 \times 144^3}{48 \times 0.12 \times 29{,}000{,}000} = 268.1$$

A structural wide-flange beam, see *Steel Wide-Flange Sections* on page 2511, having a depth of 12 inches and weighing 35 pounds per foot has a moment of inertia I of 285 and a section modulus (Z or S) of 45.6. Checking now for maximum stress s (Case 2, page 261):

$$s = \frac{Wl}{4Z} = \frac{15{,}000 \times 144}{4 \times 46.0} = 11{,}842 \text{ lbs/in}^2$$

Although deflection is the limiting factor in this case, the maximum stress is checked to make sure that it is within the allowable limit. As the limiting deflection is decreased, for a given load and length of span, the beam strength and rigidity must be increased, and, consequently, the maximum stress is decreased. Thus, in the preceding example, if the maximum deflection is 0.08 inch instead of 0.12 inch, then the calculated value for the moment of inertia I will be 402; hence a W 12 × 53 beam having an I value of 426 could be used (nearest value above 402). The maximum stress then would be reduced to 7640 pounds per square inch and the calculated deflection is 0.076 inch.

A similar example using metric SI units is as follows. Assume that a deflection equal to $l \div 1000$ millimeters is to be the limiting factor in selecting a W-beam having a span length of 5 meters. Supports are at both ends and the load at the center is 30 kilonewtons. Deflection y is to be limited to $5000 \div 1000 = 5$ millimeters. The formula on page 261 (Case 2) is applied, and W = load on beam in newtons; l = length of span in mm; E = modulus of elasticity (assume 200,000 N/mm² in this example); and I = moment of inertia of cross-section in millimeters⁴. Thus,

$$\textbf{Deflection } y = \frac{Wl^3}{48EI}$$

hence

$$I = \frac{Wl^3}{48yE} = \frac{30{,}000 \times 5000^3}{48 \times 5 \times 200{,}000} = 78{,}125{,}000 \text{ mm}^4$$

Although deflection is the limiting factor in this case, the maximum stress is checked to make sure that it is within the allowable limit, using the formula from page 261 (Case 2):

Copyright 2004, Industrial Press, Inc., New York, NY

$$s = \frac{Wl}{4Z}$$

The units of *s* are newtons per square millimeter; *W* is the load in newtons; *l* is the length in mm; and *Z* = section modulus of the cross-section of the beam = *I* ÷ distance in mm from neutral axis to extreme fiber.

Curved Beams.— The formula $S = Mc/I$ used to compute stresses due to bending of beams is based on the assumption that the beams are straight before any loads are applied. In beams having initial curvature, however, the stresses may be considerably higher than predicted by the ordinary straight-beam formula because the effect of initial curvature is to shift the neutral axis of a curved member in from the gravity axis toward the center of curvature (the concave side of the beam). This shift in the position of the neutral axis causes an increase in the stress on the concave side of the beam and decreases the stress at the outside fibers.

Hooks, press frames, and other machine members which as a rule have a rather pronounced initial curvature may have a maximum stress at the inside fibers of up to about 3½ times that predicted by the ordinary straight-beam formula.

Stress Correction Factors for Curved Beams: A simple method for determining the maximum fiber stress due to bending of curved members consists of 1) calculating the maximum stress using the straight-beam formula $S = Mc/I$; and; and 2) multiplying the calculated stress by a stress correction factor. Table 4 on page 279 gives stress correction factors for some of the common cross-sections and proportions used in the design of curved members.

An example in the application of the method using English units of measurement is given at the bottom of the table. **A similar example using metric SI units is as follows: The fiber stresses of a curved rectangular beam are calculated as 40 newtons per millimeter^2, using the straight beam formula, $S = Mc/I$. If the beam is 150 mm deep and its radius of curvature is 300 mm, what are the true stresses? $R/c = 300/75 = 4$. From Table 4 on page 279, the *K* factors corresponding to $R/c = 4$ are 1.20 and 0.85. Thus, the inside fiber stress is $40 \times 1.20 = 48$ N/mm^2 = 48 megapascals; and the outside fiber stress is $40 \times 0.85 = 34$ N/mm^2 = 34 megapascals.**

Approximate Formula for Stress Correction Factor: The stress correction factors given in Table 4 on page 279 were determined by Wilson and Quereau and published in the University of Illinois Engineering Experiment Station Circular No. 16, "A Simple Method of Determining Stress in Curved Flexural Members." In this same publication the authors indicate that the following empirical formula may be used to calculate the value of the stress correction factor for the *inside* fibers of sections not covered by the tabular data to within 5 per cent accuracy except in triangular sections where up to 10 per cent deviation may be expected. However, for most engineering calculations, this formula should prove satisfactory for general use in determining the factor for the inside fibers.

$$K = 1.00 + 0.5\frac{I}{bc^2}\left[\frac{1}{R-c} + \frac{1}{R}\right]$$

(Use 1.05 instead of 0.5 in this formula for circular and elliptical sections.)

I = Moment of inertia of section about centroidal axis

b = maximum width of section

c = distance from centroidal axis to inside fiber, i.e., to the extreme fiber nearest the center of curvature

R = radius of curvature of centroidal axis of beam

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Values of Stress Correction Factor *K* for Various Curved Beam Sections

Section	R/c	Factor *K* Inside Fiber	Factor *K* Outside Fiber	y_0[a]	Section	R/c	Factor *K* Inside Fiber	Factor *K* Outside Fiber	y_0[a]
	1.2	3.41	.54	.224*R*		1.2	3.63	.58	.418*R*
	1.4	2.40	.60	.151*R*		1.4	2.54	.63	.299*R*
	1.6	1.96	.65	.108*R*		1.6	2.14	.67	.229*R*
	1.8	1.75	.68	.084*R*		1.8	1.89	.70	.183*R*
	2.0	1.62	.71	.069*R*		2.0	1.73	.72	.149*R*
	3.0	1.33	.79	.030*R*		3.0	1.41	.79	.069*R*
	4.0	1.23	.84	.016*R*		4.0	1.29	.83	.040*R*
	6.0	1.14	.89	.0070*R*		6.0	1.18	.88	.018*R*
	8.0	1.10	.91	.0039*R*		8.0	1.13	.91	.010*R*
	10.0	1.08	.93	.0025*R*		10.0	1.10	.92	.0065*R*
	1.2	2.89	.57	.305*R*		1.2	3.55	.67	.409*R*
	1.4	2.13	.63	.204*R*		1.4	2.48	.72	.292*R*
	1.6	1.79	.67	.149*R*		1.6	2.07	.76	.224*R*
	1.8	1.63	.70	.112*R*		1.8	1.83	.78	.178*R*
	2.0	1.52	.73	.090*R*		2.0	1.69	.80	.144*R*
	3.0	1.30	.81	.041*R*		3.0	1.38	.86	.067*R*
	4.0	1.20	.85	.021*R*		4.0	1.26	.89	.038*R*
	6.0	1.12	.90	.0093*R*		6.0	1.15	.92	.018*R*
	8.0	1.09	.92	.0052*R*		8.0	1.10	.94	.010*R*
	10.0	1.07	.94	.0033*R*		10.0	1.08	.95	.0065*R*
	1.2	3.01	.54	.336*R*		1.2	2.52	.67	.408*R*
	1.4	2.18	.60	.229*R*		1.4	1.90	.71	.285*R*
	1.6	1.87	.65	.168*R*		1.6	1.63	.75	.208*R*
	1.8	1.69	.68	.128*R*		1.8	1.50	.77	.160*R*
	2.0	1.58	.71	.102*R*		2.0	1.41	.79	.127*R*
	3.0	1.33	.80	.046*R*		3.0	1.23	.86	.058*R*
	4.0	1.23	.84	.024*R*		4.0	1.16	.89	.030*R*
	6.0	1.13	.88	.011*R*		6.0	1.10	.92	.013*R*
	8.0	1.10	.91	.0060*R*		8.0	1.07	.94	.0076*R*
	10.0	1.08	.93	.0039*R*		10.0	1.05	.95	.0048*R*
	1.2	3.09	.56	.336*R*		1.2	3.28	.58	.269*R*
	1.4	2.25	.62	.229*R*		1.4	2.31	.64	.182*R*
	1.6	1.91	.66	.168*R*		1.6	1.89	.68	.134*R*
	1.8	1.73	.70	.128*R*		1.8	1.70	.71	.104*R*
	2.0	1.61	.73	.102*R*		2.0	1.57	.73	.083*R*
	3.0	1.37	.81	.046*R*		3.0	1.31	.81	.038*R*
	4.0	1.26	.86	.024*R*		4.0	1.21	.85	.020*R*
	6.0	1.17	.91	.011*R*		6.0	1.13	.90	.0087*R*
	8.0	1.13	.94	.0060*R*		8.0	1.10	.92	.0049*R*
	10.0	1.11	.95	.0039*R*		10.0	1.07	.93	.0031*R*
	1.2	3.14	.52	.352*R*		1.2	2.63	.68	.399*R*
	1.4	2.29	.54	.243*R*		1.4	1.97	.73	.280*R*
	1.6	1.93	.62	.179*R*		1.6	1.66	.76	.205*R*
	1.8	1.74	.65	.138*R*		1.8	1.51	.78	.159*R*
	2.0	1.61	.68	.110*R*		2.0	1.43	.80	.127*R*
	3.0	1.34	.76	.050*R*		3.0	1.23	.86	.058*R*
	4.0	1.24	.82	.028*R*		4.0	1.15	.89	.031*R*
	6.0	1.15	.87	.012*R*		6.0	1.09	.92	.014*R*
	8.0	1.12	.91	.0060*R*		8.0	1.07	.94	.0076*R*
	10.0	1.10	.93	.0039*R*		10.0	1.06	.95	.0048*R*
	1.2	3.26	.44	.361*R*	*Example:* The fiber stresses of a curved rectangular beam are calculated as 5000 psi using the straight beam formula, $S = Mc/I$. If the beam is 8 inches deep and its radius of curvature is 12 inches, what are the true stresses? R/c = 12/4 = 3. The factors in the table corresponding to R/c = 3 are 0.81 and 1.30. Outside fiber stress = 5000 × 0.81 = 4050 psi; inside fiber stress = 5000 × 1.30 = 6500 psi.			
	1.4	2.39	.50	.251*R*					
	1.6	1.99	.54	.186*R*					
	1.8	1.78	.57	.144*R*					
	2.0	1.66	.60	.116*R*					
	3.0	1.37	.70	.052*R*					
	4.0	1.27	.75	.029*R*					
	6.0	1.16	.82	.013*R*					
	8.0	1.12	.86	.0060*R*					
	10.0	1.09	.88	.0039*R*					

[a] y_0 is the distance from the centroidal axis to the neutral axis of curved beams subjected to pure bending and is measured from the centroidal axis toward the center of curvature.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: The accompanying diagram shows the dimensions of a clamp frame of rectangular cross-section. Determine the maximum stress at points *A* and *B* due to a clamping force of 1000 pounds.



The cross-sectional area = 2 × 4 = 8 square inches; the bending moment at section *AB* is 1000 (24 + 6 + 2) = 32,000 inch pounds; the distance from the center of gravity of the section at *AB* to point *B* is *c* = 2 inches; and using the formula on page 239, the moment of inertia of the section is $2 \times (4)^3 \div 12 = 10.667$ inches^4.

Using the straight-beam formula, page 278, the stress at points *A* and *B* due to the bending moment is:

$$S = \frac{Mc}{I} = \frac{32{,}000 \times 2}{10.667} = 6000 \text{ psi}$$

The stress at *A* is a compressive stress of 6000 psi and that at *B* is a tensile stress of 6000 psi.

These values must be corrected to account for the curvature effect. In Table 4 on page 279 for $R/c = (6 + 2)/(2) = 4$, the value of *K* is found to be 1.20 and 0.85 for points *B* and *A* respectively. Thus, the actual stress due to bending at point *B* is 1.20 × 6000 = 7200 psi in tension and the stress at point *A* is 0.85 × 6000 = 5100 psi in compression.

To these stresses at *A* and *B* must be added, algebraically, the direct stress at section *AB* due to the 1000-pound clamping force. The direct stress on section *AB* will be a tensile stress equal to the clamping force divided by the section area. Thus 1000 ÷ 8 = 125 psi in tension.

The maximum unit stress at *A* is, therefore, 5100 – 125 = 4975 psi in compression and the maximum unit stress at *B* is 7200 + 125 = 7325 psi in tension.

The following is a similar calculation using metric SI units, assuming that it is required to determine the maximum stress at points *A* and *B* due to clamping force of 4 kilonewtons acting on the frame. The frame cross-section is 50 by 100 millimeters, the radius *R* = 200 mm, and the length of the straight portions is 600 mm. Thus, the cross-sectional area = 50 × 100 = 5000 mm^2; the bending moment at *AB* is 4000(600 + 200) = 3,200,000 newton-millimeters; the distance from the center of gravity of the section at *AB* to point *B* is *c* = 50 mm; and the moment of inertia of the section is, using the formula on page 239, 50 × (100)^3 = 4,170,000 mm^4.

Using the straight-beam formula, page 278, the stress at points *A* and *B* due to the bending moment is:

$$s = \frac{Mc}{I} = \frac{3{,}200{,}000 \times 50}{4{,}170{,}000}$$

= 38.4 newtons per millimeter^2 = 38.4 megapascals

The stress at *A* is a compressive stress of 38.4 N/mm^2, while that at *B* is a tensile stress of 38.4 N/mm^2. These values must be corrected to account for the curvature

Copyright 2004, Industrial Press, Inc., New York, NY

effect. From the table on page 279, the *K* factors are 1.20 and 0.85 for points *A* and *B* respectively, derived from *R*/*c* = 200/50 = 4. Thus, the actual stress due to bending at point *B* is 1.20 × 38.4 = 46.1 N/mm² (46.1 megapascals) in tension; and the stress at point *A* is 0.85 × 38.4 = 32.6 N/mm² (32.6 megapascals) in compression.

To these stresses at *A* and *B* must be added, algebraically, the direct stress at section *AB* due to the 4 kN clamping force. The direct stress on section *AB* will be a tensile stress equal to the clamping force divided by the section area. Thus, 4000/5000 = 0.8 N/mm². The maximum unit stress at *A* is, therefore, 32.61 – 0.8 = 31.8 N/mm² (31.8 megapascals) in compression, and the maximum unit stress at *B* is 46.1 + 0.8 = 46.9 N/mm² (46.9 megapascals) in tension.

Size of Rail Necessary to Carry a Given Load.— The following formulas may be employed for determining the size of rail and wheel suitable for carrying a given load. Let, *A* = the width of the head of the rail in inches; *B* = width of the tread of the rail in inches; *C* = the wheel-load in pounds; *D* = the diameter of the wheel in inches.



Then the width of the tread of the rail in inches is found from the formula:

$$B = \frac{C}{1250D} \tag{1}$$

The width *A* of the head equals *B* + $\frac{5}{8}$ inch. The diameter *D* of the smallest track wheel that will safely carry the load is found from the formula:

$$D = \frac{C}{A \times K} \tag{2}$$

in which *K* = 600 to 800 for steel castings; *K* = 300 to 400 for cast iron.

As an example, assume that the wheel-load is 10,000 pounds; the diameter of the wheel is 20 inches; and the material is cast steel. Determine the size of rail necessary to carry this load. From Formula (1):

$$B = \frac{10{,}000}{1250 \times 20} = 0.4 \text{ inch}$$

The width of the rail required equals 0.4 + $\frac{5}{8}$ inch = 1.025 inch. Determine also whether a wheel 20 inches in diameter is large enough to safely carry the load. From Formula (2):

$$D = \frac{10{,}000}{1.025 \times 600} = 16\tfrac{1}{4} \text{ inches}$$

This is the smallest diameter of track wheel that will safely carry the load; hence a 20-inch wheel is ample.

American Railway Engineering Association Formulas.— The American Railway Engineering Association recommends for safe operation of steel cylinders rolling on steel plates that the allowable load *p* in pounds per inch of length of the cylinder should not exceed the value calculated from the formula

Copyright 2004, Industrial Press, Inc., New York, NY

$$p = \frac{\text{y.s.} - 13{,}000}{20{,}000} 600d \text{ for diameter } d \text{ less than 25 inches}$$

This formula is based on steel having a yield strength, y.s., of 32,000 pounds per square inch. For roller or wheel diameters of up to 25 inches, the Hertz stress (contact stress) resulting from the calculated load p will be approximately 76,000 pounds per square inch.

For a 10-inch diameter roller the safe load per inch of roller length is

$$p = \frac{32{,}000 - 13{,}000}{20{,}000} 600 \times 10 = 5700 \text{ lbs per inch of length}$$

Therefore, to support a 10,000 pound load the roller or wheel would need to be 10,000/5700 = 1.75 inches wide.

Stresses Produced by Shocks

Stresses in Beams Produced by Shocks.— Any elastic structure subjected to a shock will deflect until the product of the average resistance, developed by the deflection, and the distance through which it has been overcome, has reached a value equal to the energy of the shock. It follows that for a given shock, the average resisting stresses are inversely proportional to the deflection. If the structure were perfectly rigid, the deflection would be zero, and the stress infinite. The effect of a shock is, therefore, to a great extent dependent upon the elastic property (the springiness) of the structure subjected to the impact.

The energy of a body in motion, such as a falling body, may be spent in each of four ways:

1) In deforming the body struck as a whole.

2) In deforming the falling body as a whole.

3) In partial deformation of both bodies on the surface of contact (most of this energy will be transformed into heat).

4) Part of the energy will be taken up by the supports, if these are not perfectly rigid and inelastic.

How much energy is spent in the last three ways it is usually difficult to determine, and for this reason it is safest to figure as if the whole amount were spent as in Case 1. If a reliable judgment is possible as to what percentage of the energy is spent in other ways than the first, a corresponding fraction of the total energy can be assumed as developing stresses in the body subjected to shocks.

One investigation into the stresses produced by shocks led to the following conclusions:

1) A suddenly applied load will produce the same deflection, and, therefore, the same stress as a static load twice as great; and 2) The unit stress p (see formulas in Table 1, "*Stresses Produced in Beams by Shocks*") for a given load producing a shock, varies directly as the square root of the modulus of elasticity E, and inversely as the square root of the length L of the beam and the area of the section.

Thus, for instance, if the sectional area of a beam is increased by four times, the unit stress will diminish only by half. This result is entirely different from those produced by static loads where the stress would vary inversely with the area, and within certain limits be practically independent of the modulus of elasticity.

In Table 1, the expression for the approximate value of p, which is applicable whenever the deflection of the beam is small as compared with the total height h through which the body producing the shock is dropped, is always the same for beams supported at both ends and subjected to shock at *any* point between the supports. In the formulas all dimensions are in inches and weights in pounds.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Stresses Produced in Beams by Shocks

Method of Support and Point Struck by Falling Body	Fiber (Unit) Stress p produced by Weight Q Dropped Through a Distance h	Approximate Value of p
Supported at both ends; struck in center.	$p = \frac{QaL}{4I}\left(1 + \sqrt{1 + \frac{96hEI}{QL^3}}\right)$	$p = a\sqrt{\frac{6QhE}{LI}}$
Fixed at one end; struck at the other.	$p = \frac{QaL}{I}\left(1 + \sqrt{1 + \frac{6hEI}{QL^3}}\right)$	$p = a\sqrt{\frac{6QhE}{LI}}$
Fixed at both ends; struck in center.	$p = \frac{QaL}{8I}\left(1 + \sqrt{1 + \frac{384hEI}{QL^3}}\right)$	$p = a\sqrt{\frac{6QhE}{LI}}$

I = moment of inertia of section; a = distance of extreme fiber from neutral axis; L = length of beam; E = modulus of elasticity.

If metric SI units are used, p is in newtons per square millimeter; Q is in newtons; E = modulus of elasticity in N/mm^2; I = moment of inertia of section in millimeters^4; and h, a, and L in millimeters. ***Note:*** **If Q is given in kilograms, the value referred to is mass. The weight Q of a mass M kilograms is Mg newtons, where g = approximately 9.81 meters per second^2.**

Examples of How Formulas for Stresses Produced by Shocks are Derived: The general formula from which specific formulas for shock stresses in beams, springs, and other machine and structural members are derived is:

$$p = p_s\left(1 + \sqrt{1 + \frac{2h}{y}}\right) \tag{1}$$

In this formula, p = stress in pounds per square inch due to shock caused by impact of a moving load; p_s = stress in pounds per square inch resulting when moving load is applied statically; h = distance in inches that load falls before striking beam, spring, or other member; y = deflection, in inches, resulting from static load.

As an example of how Formula (1) may be used to obtain a formula for a specific application, suppose that the load W shown applied to the beam in Case 2 on page 261 were dropped on the beam from a height of h inches instead of being gradually applied (static loading). The maximum stress p_s due to load W for Case 2 is given as $Wl \div 4Z$ and the maximum deflection y is given as $Wl^3 \div 48\,EI$. Substituting these values in Formula (1),

$$p = \frac{Wl}{4Z}\left(1 + \sqrt{1 + \frac{2h}{Wl^3 \div 48EI}}\right) = \frac{Wl}{4Z}\left(1 + \sqrt{1 + \frac{96hEI}{Wl^3}}\right) \tag{2}$$

If in Formula (2) the letter Q is used in place of W and if Z, the section modulus, is replaced by its equivalent, $I \div$ distance a from neutral axis to extreme fiber of beam, then Formula (2) becomes the first formula given in the accompanying Table 1, *Stresses Produced in Beams by Shocks*

Stresses in Helical Springs Produced by Shocks.— A load suddenly applied on a spring will produce the same deflection, and, therefore, also the same unit stress, as a static load twice as great. When the load drops from a height h, the stresses are as given in the accompanying Table 2. The approximate values are applicable when the deflection is small as compared with the height h. The formulas show that the fiber stress for a given shock will be greater in a spring made from a square bar than in one made from a round bar, if the diameter of coil be the same and the side of the square bar equals the diameter of the round

Copyright 2004, Industrial Press, Inc., New York, NY

bar. It is, therefore, more economical to use round stock for springs which must withstand shocks, due to the fact that the deflection for the same fiber stress for a square bar spring is smaller than that for a round bar spring, the ratio being as 4 to 5. The round bar spring is therefore capable of storing more energy than a square bar spring for the same stress.

Table 2. Stresses Produced in Springs by Shocks

Form of Bar from Which Spring is Made	Fiber (Unit) Stress f Produced by Weight Q Dropped a Height h on a Helical Spring	Approximate Value of f
Round	$f = \frac{8QD}{\pi d^3}\left(1 + \sqrt{1 + \frac{Ghd^4}{4QD^3n}}\right)$	$f = 1.27\sqrt{\frac{QhG}{Dd^2n}}$
Square	$f = \frac{9QD}{4d^3}\left(1 + \sqrt{1 + \frac{Ghd^4}{0.9\pi QD^3n}}\right)$	$f = 1.34\sqrt{\frac{QhG}{Dd^2n}}$

G = modulus of elasticity for torsion; d = diameter or side of bar; D = mean diameter of spring; n = number of coils in spring.

Shocks from Bodies in Motion.— The formulas given can be applied, in general, to shocks from bodies in motion. A body of weight W moving horizontally with the velocity of v feet per second, has a stored-up energy:

$$E_K = \frac{1}{2} \times \frac{Wv^2}{g} \text{ foot-pounds} \qquad \text{or} \qquad \frac{6Wv^2}{g} \text{ inch-pounds}$$

This expression may be substituted for Qh in the tables in the equations for unit stresses containing this quantity, and the stresses produced by the energy of the moving body thereby determined.

The formulas in the tables give the maximum value of the stresses, providing the designer with some definitive guidance even where there may be justification for assuming that only a part of the energy of the shock is taken up by the member under stress.

The formulas can also be applied using metric SI units. The stored-up energy of a body of mass M kilograms moving horizontally with the velocity of v meters per second is:

$$E_K = \tfrac{1}{2}Mv^2 \text{ newton-meters}$$

This expression may be substituted for Qh in the appropriate equations in the tables. For calculation in millimeters, $Qh = 1000\,E_K$ newton-millimeters.

Fatigue Stresses.— So-called "fatigue ruptures" occur in parts that are subjected to continually repeated shocks or stresses of small magnitude. Machine parts that are subjected to continual stresses in varying directions, or to repeated shocks, even if of comparatively small magnitude, may fail ultimately if designed, from a mere knowledge of the behavior of the material under a steady stress, such as is imposed upon it by ordinary tensile stress testing machines. Examinations of numerous cases of machine parts, broken under actual working conditions, indicate that at least 80 per cent of these ruptures are caused by fatigue stresses. Most fatigue ruptures are caused by bending stresses, and frequently by a revolving bending stress. Hence, to test materials for this class of stress, the tests should be made to stress the material in a manner similar to that in which it will be stressed under actual working conditions. See *Fatigue Properties* on page 205 for more on this topic.

Copyright 2004, Industrial Press, Inc., New York, NY

COLUMNS

Strength of Columns or Struts

Structural members which are subject to compression may be so long in proportion to the diameter or lateral dimensions that failure may be the result 1) of both compression and bending; and 2) of bending or buckling to such a degree that compression stress may be ignored.

In such cases, the *slenderness ratio* is important. This ratio equals the length l of the column in inches divided by the least radius of gyration r of the cross-section. Various formulas have been used for designing columns which are too slender to be designed for compression only.

Rankine or Gordon Formula.— This formula is generally applied when slenderness ratios range between 20 and 100, and sometimes for ratios up to 120. The notation, in English and metric SI units of measurement, is given on page 287.

$$p = \frac{S}{1 + K\left(\frac{l}{r}\right)^2} = \text{ultimate load, lbs. per sq. in.}$$

Factor K may be established by tests with a given material and end condition, and for the probable range of l/r. If determined by calculation, $K = S/C\pi^2E$. Factor C equals 1 for either rounded or pivoted column ends, 4 for fixed ends, and 1 to 4 for square flat ends. The factors 25,000, 12,500, etc., in the Rankine formulas, arranged as on page 287, equal $1/K$, and have been used extensively.

Straight-line Formula.— This general type of formula is often used in designing compression members for buildings, bridges, or similar structural work. It is convenient especially in designing a number of columns that are made of the same material but vary in size, assuming that factor B is known. This factor is determined by tests.

$$p = S_y - B\left(\frac{l}{r}\right) = \text{ultimate load, lbs. per sq. in.}$$

S_y equals yield point, lbs. per square inch, and factor B ranges from 50 to 100. Safe unit stress = $p \div$ factor of safety.

Formulas of American Railway Engineering Association.— The formulas that follow apply to structural steel having an ultimate strength of 60,000 to 72,000 pounds per square inch.

For building columns having l/r ratios not greater than 120, allowable unit stress = $17{,}000 - 0.485\, l^2/r^2$. For columns having l/r ratios greater than 120, allowable unit stress

$$\text{allowable unit stress} = \frac{18{,}000}{1 + l^2/18{,}000r^2}$$

For bridge compression members centrally loaded and with values of l/r not greater than 140:

$$\text{Allowable unit stress, riveted ends} = 15{,}000 - \frac{1}{4}\frac{l^2}{r^2}$$

$$\text{Allowable unit stress, pin ends} = 15{,}000 - \frac{1}{3}\frac{l^2}{r^2}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Euler Formula.— This formula is for columns that are so slender that bending or buckling action predominates and compressive stresses are not taken into account.

$$P = \frac{C\pi^2 IE}{l^2} = \text{total ultimate load, in pounds}$$

The notation, in English and metric SI units of measurement, is given in the table *Rankine's and Euler's Formulas for Columns* on page 287. Factors C for different end conditions are included in the Euler formulas at the bottom of the table. According to a series of experiments, Euler formulas should be used if the values of l/r exceed the following ratios: Structural steel and flat ends, 195; hinged ends, 155; round ends, 120; cast iron with flat ends, 120; hinged ends, 100; round ends, 75; oak with flat ends, 130. The *critical slenderness ratio*, which marks the dividing line between the shorter columns and those slender enough to warrant using the Euler formula, depends upon the column material and its end conditions. If the Euler formula is applied when the slenderness ratio is too small, the *calculated* ultimate strength will exceed the yield point of the material and, obviously, will be incorrect.

Eccentrically Loaded Columns.— In the application of the column formulas previously referred to, it is assumed that the action of the load coincides with the axis of the column. If the load is offset relative to the column axis, the column is said to be eccentrically loaded, and its strength is then calculated by using a modification of the Rankine formula, the quantity cz/r^2 being added to the denominator, as shown in the table on the next page. This modified formula is applicable to columns having a slenderness ratio varying from 20 or 30 to about 100.

Machine Elements Subjected to Compressive Loads.— As in structural compression members, an unbraced machine member that is relatively slender (i.e., its length is more than, say, six times the least dimension perpendicular to its longitudinal axis) is usually designed as a column, because failure due to overloading (assuming a compressive load centrally applied in an axial direction) may occur by buckling or a combination of buckling and compression rather than by direct compression alone. In the design of unbraced steel machine "columns" which are to carry compressive loads applied along their longitudinal axes, two formulas are in general use:

(Euler) $$P_{cr} = \frac{S_y A r^2}{Q} \quad (1)$$

(J. B. Johnson) $$P_{cr} = AS_y\left(1 - \frac{Q}{4r^2}\right) \quad (2)$$ where $$Q = \frac{S_y l^2}{n\pi^2 E} \quad (3)$$

In these formulas, P_{cr} = critical load in pounds that would result in failure of the column; A = cross-sectional area, square inches; S_y = yield point of material, pounds per square inch; r = least radius of gyration of cross-section, inches; E = modulus of elasticity, pounds per square inch; l = column length, inches; and n = coefficient for end conditions. For both ends fixed, $n = 4$; for one end fixed, one end free, $n = 0.25$; for one end fixed and the other end free but guided, $n = 2$; for round or pinned ends, free but guided, $n = 1$; and for flat ends, $n = 1$ to 4. It should be noted that these values of n represent ideal conditions that are seldom attained in practice; for example, for both ends fixed, a value of $n = 3$ to 3.5 may be more realistic than $n = 4$.

If metric SI units are used in these formulas, P_{cr} = critical load in newtons that would result in failure of the column; A = cross-sectional area, square millimeters; S_y = yield point of the material, newtons per square mm; r = least radius of gyration of cross-section, mm; E = modulus of elasticity, newtons per square mm; l = column length, mm; and n = a coefficient for end conditions. The coefficients given are valid for calculations in metric units.

Copyright 2004, Industrial Press, Inc., New York, NY

Rankine's and Euler's Formulas for Columns

Symbol	Quantity	English Unit	Metric SI Units
p	Ultimate unit load	Lbs./sq. in.	Newtons/sq. mm.
P	Total ultimate load	Pounds	Newtons
S	Ultimate compressive strength of material	Lbs./sq. in.	Newtons/sq. mm.
l	Length of column or strut	Inches	Millimeters
r	Least radius of gyration	Inches	Millimeters
I	Least moment of inertia	Inches^4	Millimeters^4
r^2	Moment of inertia/area of section	Inches^2	Millimeters^2
E	Modulus of elasticity of material	Lbs./sq. in.	Newtons/sq. mm.
c	Distance from neutral axis of cross-section to side under compression	Inches	Millimeters
z	Distance from axis of load to axis coinciding with center of gravity of cross-section	Inches	Millimeters

Rankine's Formulas

Material	Both Ends of Column Fixed	One End Fixed and One End Rounded	Both Ends Rounded
Steel	$p = \dfrac{S}{1 + \dfrac{l^2}{25{,}000r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{12{,}500r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{6250r^2}}$
Cast Iron	$p = \dfrac{S}{1 + \dfrac{l^2}{5000r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{2500r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{1250r^2}}$
Wrought Iron	$p = \dfrac{S}{1 + \dfrac{l^2}{35{,}000r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{17{,}500r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{8750r^2}}$
Timber	$p = \dfrac{S}{1 + \dfrac{l^2}{3000r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{1500r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{750r^2}}$

Formulas Modified for Eccentrically Loaded Columns

Material	Both Ends of Column Fixed	One End Fixed and One End Rounded	Both Ends Rounded
Steel	$p = \dfrac{S}{1 + \dfrac{l^2}{25{,}000r^2} + \dfrac{cz}{r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{12{,}500r^2} + \dfrac{cz}{r^2}}$	$p = \dfrac{S}{1 + \dfrac{l^2}{6250r^2} + \dfrac{cz}{r^2}}$

For materials other than steel, such as cast iron, use the Rankine formulas given in the upper table and add to the denominator the quantity cz/r^2

Euler's Formulas for Slender Columns

Both Ends of Column Fixed	One End Fixed and One End Rounded	Both Ends Rounded	One End Fixed and One End Free
$P = \dfrac{4\pi^2 IE}{l^2}$	$P = \dfrac{2\pi^2 IE}{l^2}$	$P = \dfrac{\pi^2 IE}{l^2}$	$P = \dfrac{\pi^2 IE}{4l^2}$

Allowable Working Loads for Columns: To find the total allowable working load for a given section, divide the total ultimate load P (or $p \times$ area), as found by the appropriate formula above, by a suitable factor of safety.

Copyright 2004, Industrial Press, Inc., New York, NY

Factor of Safety for Machine Columns: When the conditions of loading and the physical qualities of the material used are accurately known, a factor of safety as low as 1.25 is sometimes used when minimum weight is important. Usually, however, a factor of safety of 2 to 2.5 is applied for steady loads. The factor of safety represents the ratio of the critical load P_{cr} to the working load.

Application of Euler and Johnson Formulas: To determine whether the Euler or Johnson formula is applicable in any particular case, it is necessary to determine the value of the quantity $Q \div r^2$. If $Q \div r^2$ is greater than 2, then the Euler Formula (1) should be used; if $Q \div r^2$ is less than 2, then the J. B. Johnson formula is applicable. Most compression members in machine design are in the range of proportions covered by the Johnson formula. For this reason a good procedure is to design machine elements on the basis of the Johnson formula and then as a check calculate $Q \div r^2$ to determine whether the Johnson formula applies or the Euler formula should have been used.

Example 1, Compression Member Design: A rectangular machine member 24 inches long and ½ × 1 inch in cross-section is to carry a compressive load of 4000 pounds along its axis. What is the factor of safety for this load if the material is machinery steel having a yield point of 40,000 pounds per square inch, the load is steady, and each end of the rod has a ball connection so that $n = 1$?

From Formula (3)

$$Q = \frac{40{,}000 \times 24 \times 24}{1 \times 3.1416 \times 3.1416 \times 30{,}000{,}000} = 0.0778$$

(The values 40,000 and 30,000,000 were obtained from the table *Strength Data for Iron and Steel* on page 474.)

The radius of gyration r for a rectangular section (page 239) is 0.289 × the dimension in the direction of bending. In columns, bending is most apt to occur in the direction in which the section is the weakest, the ½-inch dimension in this example. Hence, least radius of gyration $r = 0.289 \times ½ = 0.145$ inch.

$$\frac{Q}{r^2} = \frac{0.0778}{(0.145)^2} = 3.70$$

which is more than 2 so that the Euler formula will be used.

$$P_{cr} = \frac{s_y A r^2}{Q} = \frac{40{,}000 \times ½ \times 1}{3.70}$$

$$= 5400 \text{ pounds so that the factor of safety is } 5400 \div 4000 = 1.35$$

Example 2, Compression Member Design: In the preceding example, the column formulas were used to check the adequacy of a column of known dimensions. The more usual problem involves determining what the dimensions should be to resist a specified load. For example,:

A 24-inch long bar of rectangular cross-section with width w twice its depth d is to carry a load of 4000 pounds. What must the width and depth be if a factor of safety of 1.35 is to be used?

First determine the critical load P_{cr}:

$$P_{cr} = \text{working load} \times \text{factor of safety}$$

$$= 4000 \times 1.35 = 5400 \text{ pounds}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Next determine Q which, as in Example 1, will be 0.0778.

Assume Formula (2) applies:

$$P_{cr} = As_y\left(1 - \frac{Q}{4r^2}\right)$$

$$5400 = w \times d \times 40{,}000\left(1 - \frac{0.0778}{4r^2}\right)$$

$$= 2d^2 \times 40{,}000\left(1 - \frac{0.01945}{r^2}\right)$$

$$\frac{5400}{40{,}000 \times 2} = d^2\left(1 - \frac{0.01945}{r^2}\right)$$

As mentioned in Example 1 the least radius of gyration r of a rectangle is equal to 0.289 times the least dimension, d, in this case. Therefore, substituting for d the value $r \div 0.289$,

$$\frac{5400}{40{,}000 \times 2} = \left(\frac{r}{0.289}\right)^2\left(1 - \frac{0.01945}{r^2}\right)$$

$$\frac{5400 \times 0.289 \times 0.289}{40{,}000 \times 2} = r^2 - 0.01945$$

$$0.005638 = r^2 - 0.01945$$

$$r^2 = 0.0251$$

Checking to determine if $Q \div r^2$ is greater or less than 2,

$$\frac{Q}{r^2} = \frac{0.0778}{0.0251} = 3.1$$

therefore Formula (1) should have been used to determine r and dimensions w and d. Using Formula (1),

$$5400 = \frac{40{,}000 \times 2d^2 \times r^2}{Q} = \frac{40{,}000 \times 2 \times \left(\frac{r}{0.289}\right)^2 r^2}{0.0778}$$

$$r^4 = \frac{5400 \times 0.0778 \times 0.289 \times 0.289}{40{,}000 \times 2} = 0.0004386$$

$$d = \frac{0.145}{0.289} = 0.50 \text{ inch}$$

and $w = 2d = 1$ inch as in the previous example.

American Institute of Steel Construction.— For main or secondary compression members with l/r ratios up to 120, safe unit stress = $17{,}000 - 0.485l^2/r^2$. For columns and bracing or other secondary members with l/r ratios above 120,

Safe unit stress, psi $= \dfrac{18{,}000}{1 + l^2/18{,}000r^2}$ for bracing and secondary members. For main members, safe unit stress, psi $= \dfrac{18{,}000}{1 + l^2/18{,}000r^2} \times \left(1.6 - \dfrac{l/r}{200}\right)$

Pipe Columns: Allowable concentric loads for steel pipe columns based on the above formulas are given in the table on page 290.

Copyright 2004, Industrial Press, Inc., New York, NY

Allowable Concentric Loads for Steel Pipe Columns

STANDARD STEEL PIPE								
Nominal Diameter, Inches	12	10	8	6	5	4	3½	3
Wall Thickness, Inch	0.375	0.365	0.322	0.280	0.258	0.237	0.226	0.216
Weight per Foot, Pounds	49.56	40.48	28.55	18.97	14.62	10.79	9.11	7.58
Effective Length (*KL*), Feet[a]	Allowable Concentric Loads in Thousands of Pounds							
6	303	246	171	110	83	59	48	38
7	301	243	168	108	81	57	46	36
8	299	241	166	106	78	54	44	34
9	296	238	163	103	76	52	41	31
10	293	235	161	101	73	49	38	28
11	291	232	158	98	71	46	35	25
12	288	229	155	95	68	43	32	22
13	285	226	152	92	65	40	29	19
14	282	223	149	89	61	36	25	16
15	278	220	145	86	58	33	22	14
16	275	216	142	82	55	29	19	12
17	272	213	138	79	51	26	17	11
18	268	209	135	75	47	23	15	10
19	265	205	131	71	43	21	14	9
20	261	201	127	67	39	19	12	
22	254	193	119	59	32	15	10	
24	246	185	111	51	27	13		
25	242	180	106	47	25	12		
26	238	176	102	43	23			
EXTRA STRONG STEEL PIPE								
Nominal Diameter, Inches	12	10	8	6	5	4	3½	3
Wall Thickness, Inch	0.500	0.500	0.500	0.432	0.375	0.337	0.318	0.300
Weight per Foot, Pounds	65.42	54.74	43.39	28.57	20.78	14.98	12.50	10.25
Effective Length (*KL*), Feet[a]	Allowable Concentric Loads in Thousands of Pounds							
6	400	332	259	166	118	81	66	52
7	397	328	255	162	114	78	63	48
8	394	325	251	159	111	75	59	45
9	390	321	247	155	107	71	55	41
10	387	318	243	151	103	67	51	37
11	383	314	239	146	99	63	47	33
12	379	309	234	142	95	59	43	28
13	375	305	229	137	91	54	38	24
14	371	301	224	132	86	49	33	21
15	367	296	219	127	81	44	29	18
16	363	291	214	122	76	39	25	16
18	353	281	203	111	65	31	20	12
19	349	276	197	105	59	28	18	11
20	344	271	191	99	54	25	16	
21	337	265	185	92	48	22	14	
22	334	260	179	86	44	21		
24	323	248	166	73	37	17		
26	312	236	152	62	32			
28	301	224	137	54	27			

[a] With respect to radius of gyration. The effective length (*KL*) is the actual unbraced length, *L*, in feet, multiplied by the effective length factor (*K*) which is dependent upon the restraint at the ends of the unbraced length and the means available to resist lateral movements. *K* may be determined by referring to the last portion of this table.

Copyright 2004, Industrial Press, Inc., New York, NY

Allowable Concentric Loads for Steel Pipe Columns *(Continued)*

DOUBLE-EXTRA STRONG STEEL PIPE					
Nominal Diameter, Inches	8	6	5	4	3
Wall Thickness, Inch	0.875	0.864	0.750	0.674	0.600
Weight per Foot, Pounds	72.42	53.16	38.55	27.54	18.58
Effective Length (*KL*), Feet[a]	Allowable Concentric Loads in Thousands of Pounds				
6	431	306	216	147	91
7	424	299	209	140	84
8	417	292	202	133	77
9	410	284	195	126	69
10	403	275	187	118	60
11	395	266	178	109	51
12	387	257	170	100	43
13	378	247	160	91	37
14	369	237	151	81	32
15	360	227	141	70	28
16	351	216	130	62	24
17	341	205	119	55	22
18	331	193	108	49	
19	321	181	97	44	
20	310	168	87	40	
22	288	142	72	33	
24	264	119	61		
26	240	102	52		
28	213	88	44		

EFFECTIVE LENGTH FACTORS (*K*) FOR VARIOUS COLUMN CONFIGURATIONS						
	(a)	(b)	(c)	(d)	(e)	(f)
Buckled shape of column is shown by dashed line						
Theoretical *K* value	0.5	0.7	1.0	1.0	2.0	2.0
Recommended design value when ideal conditions are approximated	0.65	0.80	1.2	1.0	2.10	2.0
End condition code		Rotation fixed and translation fixed Rotation free and translation fixed Rotation fixed and translation free Rotation free and translation free				

Load tables are given for 36 ksi yield stress steel. No load values are given below the heavy horizontal lines, because the *Kl*/*r* ratios (where *l* is the actual unbraced length in inches and *r* is the governing radius of gyration in inches) would exceed 200.

Data from "Manual of Steel Construction," 8th ed., 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

PLATES, SHELLS, AND CYLINDERS

Flat Stayed Surfaces.— Large flat areas are often held against pressure by stays distributed at regular intervals over the surface. In boiler work, these stays are usually screwed into the plate and the projecting end riveted over to insure steam tightness. The U.S. Board of Supervising Inspectors and the American Boiler Makers Association rules give the following formula for flat stayed surfaces:

$$P = \frac{C \times t^2}{S^2}$$

in which P = pressure in pounds per square inch

C = a constant, which equals

112 for plates $\frac{7}{16}$ inch and under

120, for plates over $\frac{7}{16}$ inch thick

140, for plates with stays having a nut and bolt on the inside and outside

160, for plates with stays having washers of at least one-half the thickness of the plate, and with a diameter at least one-half of the greatest pitch

t = thickness of plate in 16ths of an inch (thickness = $\frac{7}{16}$, $t = 7$)

S = greatest pitch of stays in inches

Strength and Deflection of Flat Plates.— Generally, the formulas used to determine stresses and deflections in flat plates are based on certain assumptions that can be closely approximated in practice. These assumptions are:

1) the thickness of the plate is not greater than one-quarter the least width of the plate;
2) the greatest deflection when the plate is loaded is less than one-half the plate thickness;
3) the maximum tensile stress resulting from the load does not exceed the elastic limit of the material; and
4) all loads are perpendicular to the plane of the plate.

Plates of ductile materials fail when the maximum stress resulting from deflection under load exceeds the yield strength; for brittle materials, failure occurs when the maximum stress reaches the ultimate tensile strength of the material involved.

Square and Rectangular Flat Plates.— The formulas that follow give the maximum stress and deflection of flat steel plates supported in various ways and subjected to the loading indicated. These formulas are based upon a modulus of elasticity for steel of 30,000,000 pounds per square inch and a value of Poisson's ratio of 0.3. If the formulas for maximum stress, S, are applied without modification to other materials such as cast iron, aluminum, and brass for which the range of Poisson's ratio is about 0.26 to 0.34, the maximum stress calculations will be in error by not more than about 3 per cent. The deflection formulas may also be applied to materials other than steel by substituting in these formulas the appropriate value for E, the modulus of elasticity of the material (see pages 474 and 554). The deflections thus obtained will not be in error by more than about 3 per cent.

In the stress and deflection formulas that follow,

p = uniformly distributed load acting on plate, pounds per square inch

W = total load on plate, pounds; $W = p \times$ area of plate

L = distance between supports (length of plate), inches. For rectangular plates, L = long side, l = short side

t = thickness of plate, inches

S = maximum tensile stress in plate, pounds per square inch

d = maximum deflection of plate, inches

E = modulus of elasticity in tension. E = 30,000,000 pounds per square inch for steel

Copyright 2004, Industrial Press, Inc., New York, NY

If metric SI units are used in the formulas, then,

W = **total load on plate, newtons**
L = **distance between supports (length of plate), millimeters. For rectangular plates, L = long side, l = short side**
t = **thickness of plate, millimeters**
S = **maximum tensile stress in plate, newtons per mm squared**
d = **maximum deflection of plate, mm**
E = **modulus of elasticity, newtons per mm squared**

a) Square flat plate supported at top and bottom of all four edges and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.29W}{t^2} \quad (1) \qquad d = \frac{0.0443WL^2}{Et^3} \quad (2)$$

b) Square flat plate supported at the bottom only of all four edges and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.28W}{t^2} \quad (3) \qquad d = \frac{0.0443WL^2}{Et^3} \quad (4)$$

c) Square flat plate with all edges firmly fixed and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.31W}{t^2} \quad (5) \qquad d = \frac{0.0138WL^2}{Et^3} \quad (6)$$

d) Square flat plate with all edges firmly fixed and a uniform load over small circular area at the center. In Equations (7) and (9), r_0 = radius of area to which load is applied. If $r_0 < 1.7t$, use r_s where $r_s = \sqrt{1.6{r_0}^2 + t^2} - 0.675t$.

$$S = \frac{0.62W}{t^2}\log_e\left(\frac{L}{2r_0}\right) \quad (7) \qquad d = \frac{0.0568WL^2}{Et^3} \quad (8)$$

e) Square flat plate with all edges supported above and below, or below only, and a concentrated load at the center. (See Case 4, above, for definition of r_0).

$$S = \frac{0.62W}{t^2}\left[\log_e\left(\frac{L}{2r_0}\right) + 0.577\right] \quad (9) \qquad d = \frac{0.1266WL^2}{Et^3} \quad (10)$$

f) Rectangular plate with all edges supported at top and bottom and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.75W}{t^2\left(\frac{L}{l} + 1.61\frac{l^2}{L^2}\right)} \quad (11) \qquad d = \frac{0.1422W}{Et^3\left(\frac{L}{l^3} + \frac{2.21}{L^2}\right)} \quad (12)$$

g) Rectangular plate with all edges fixed and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.5W}{t^2\left(\frac{L}{l} + \frac{0.623l^5}{L^5}\right)} \quad (13) \qquad d = \frac{0.0284W}{Et^3\left(\frac{L}{l^3} + \frac{1.056l^2}{L^4}\right)} \quad (14)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Circular Flat Plates.— In the following formulas, R = radius of plate to supporting edge in inches; W = total load in pounds; and other symbols are the same as used for square and rectangular plates.

If metric SI units are used, R = radius of plate to supporting edge in millimeters, and the values of other symbols are the same as those used for square and rectangular plates.

a) Edge supported around the circumference and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.39W}{t^2} \quad (15) \qquad d = \frac{0.221WR^2}{Et^3} \quad (16)$$

b) Edge fixed around circumference and a uniformly distributed load over the surface of the plate.

$$S = \frac{0.24W}{t^2} \quad (17) \qquad d = \frac{0.0543WR^2}{Et^3} \quad (18)$$

c) Edge supported around the circumference and a concentrated load at the center.

$$S = \frac{0.48W}{t^2}\left[1 + 1.3\log_e\frac{R}{0.325t} - 0.0185\frac{t^2}{R^2}\right] \quad (19) \qquad d = \frac{0.55WR^2}{Et^3} \quad (20)$$

d) Edge fixed around circumference and a concentrated load at the center.

$$S = \frac{0.62W}{t^2}\left[\log_e\frac{R}{0.325t} + 0.0264\frac{t^2}{R^2}\right] \quad (21) \qquad d = \frac{0.22WR^2}{Et^3} \quad (22)$$

Strength of Cylinders Subjected to Internal Pressure.— In designing a cylinder to withstand internal pressure, the choice of formula to be used depends on 1) the kind of material of which the cylinder is made (whether brittle or ductile); 2) the construction of the cylinder ends (whether open or closed); and 3) whether the cylinder is classed as a thin- or a thick-walled cylinder.

A cylinder is considered to be thin-walled when the ratio of wall thickness to inside diameter is 0.1 or less and thick-walled when this ratio is greater than 0.1. Materials such as cast iron, hard steel, cast aluminum are considered to be brittle materials; low-carbon steel, brass, bronze, etc. are considered to be ductile.

In the formulas that follow, p = internal pressure, pounds per square inch; D = inside diameter of cylinder, inches; t = wall thickness of cylinder, inches; μ = Poisson's ratio, = 0.3 for steel, 0.26 for cast iron, 0.34 for aluminum and brass; and S = allowable tensile stress, pounds per square inch.

Metric SI units can be used in Formulas (23), (25), (26), and (27), where p = internal pressure in newtons per square millimeter; D = inside diameter of cylinder, millimeters; t = wall thickness, mm; μ = Poisson's ratio, = 0.3 for steel, 0.26 for cast iron, and 0.34 for aluminum and brass; and S = allowable tensile stress, N/mm^2. For the use of metric SI units in Formula (24), see below.

Thin-walled Cylinders:

$$t = \frac{Dp}{2S} \quad (23)$$

For low-pressure cylinders of cast iron such as are used for certain engine and press applications, a formula in common use is

$$t = \frac{Dp}{2500} + 0.3 \quad (24)$$

Copyright 2004, Industrial Press, Inc., New York, NY

This formula is based on allowable stress of 1250 pounds per square inch and will give a wall thickness 0.3 inch greater than Formula (23) to allow for variations in metal thickness that may result from the casting process.

If metric SI units are used in Formula (24), t = cylinder wall thickness in millimeters; D = inside diameter of cylinder, mm; and the allowable stress is in newtons per square millimeter. The value of 0.3 inches additional wall thickness is 7.62 mm, and the next highest number in preferred metric basic sizes is 8 mm.

Thick-walled Cylinders of Brittle Material, Ends Open or Closed: Lamé's equation is used when cylinders of this type are subjected to internal pressure.

$$t = \frac{D}{2}\left(\sqrt{\frac{S+p}{S-p}} - 1\right) \tag{25}$$

The table *Ratio of Outside Radius to Inside Radius, Thick Cylinders* on page 296 is for convenience in calculating the dimensions of cylinders under high internal pressure without the use of Formula (25).

Example, Use of the Table: Assume that a cylinder of 10 inches inside diameter is to withstand a pressure of 2500 pounds per square inch; the material is cast iron and the allowable stress is 6000 pounds per square inch. To solve the problem, locate the allowable stress per square inch in the left-hand column of the table and the working pressure at the top of the columns. Then find the ratio between the outside and inside radii in the body of the table. In this example, the ratio is 1.558, and hence the outside diameter of the cylinder should be 10×1.558, or about $15\frac{5}{8}$ inches. The thickness of the cylinder wall will therefore be $(15.558 - 10)/2 = 2.779$ inches.

Unless very high-grade material is used and sound castings assured, cast iron should not be used for pressures exceeding 2000 pounds per square inch. It is well to leave more metal in the bottom of a hydraulic cylinder than is indicated by the results of calculations, because a hole of some size must be cored in the bottom to permit the entrance of a boring bar when finishing the cylinder, and when this hole is subsequently tapped and plugged it often gives trouble if there is too little thickness.

For steady or gradually applied stresses, the maximum allowable fiber stress S may be assumed to be from 3500 to 4000 pounds per square inch for cast iron; from 6000 to 7000 pounds per square inch for brass; and 12,000 pounds per square inch for steel castings. For intermittent stresses, such as in cylinders for steam and hydraulic work, 3000 pounds per square inch for cast iron; 5000 pounds per square inch for brass; and 10,000 pounds per square inch for steel castings, is ordinarily used. These values give ample factors of safety.

Note: **In metric SI units, 1000 pounds per square inch equals 6.895 newtons per square millimeter.**

Thick-walled Cylinders of Ductile Material, Closed Ends: Clavarino's equation is used:

$$t = \frac{D}{2}\left[\sqrt{\frac{S+(1-2\mu)p}{S-(1+\mu)p}} - 1\right] \tag{26}$$

Thick-walled Cylinders of Ductile Material, Open Ends: Birnie's equation is used:

$$t = \frac{D}{2}\left[\sqrt{\frac{S+(1-\mu)p}{S-(1+\mu)p}} - 1\right] \tag{27}$$

Spherical Shells Subjected to Internal Pressure.— Let:

D = internal diameter of shell in inches
p = internal pressure in pounds per square inch
S = safe tensile stress per square inch
t = thickness of metal in the shell, in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Ratio of Outside Radius to Inside Radius, Thick Cylinders

Allowable Stress in Metal per Sq. In. of Section	Working Pressure in Cylinder, Pounds per Square Inch						
	1000	2000	3000	4000	5000	6000	7000
2,000	1.732	…	…	…	…	…	…
2,500	1.527	…	…	…	…	…	…
3,000	1.414	2.236	…	…	…	…	…
3,500	1.341	1.915	…	…	…	…	…
4,000	1.291	1.732	2.645	…	…	…	…
4,500	1.253	1.612	2.236	…	…	…	…
5000	1.224	1.527	2.000	3.000	…	…	…
5,500	1.201	1.464	1.844	2.516	…	…	…
6,000	1.183	1.414	1.732	2.236	3.316	…	…
6,500	…	1.374	1.647	2.049	2.768	…	…
7,000	…	1.341	1.581	1.914	2.449	3.605	…
7,500	…	1.314	1.527	1.813	2.236	3.000	…
8,000	…	1.291	1.483	1.732	2.081	2.645	3.872
8,500	…	1.271	1.446	1.666	1.963	2.408	3.214
9,000	…	1.253	1.414	1.612	1.871	2.236	2.828
9,500	…	1.235	1.386	1.566	1.795	2.104	2.569
10,000	…	1.224	1.362	1.527	1.732	2.000	2.380
10,500	…	1.212	1.341	1.493	1.678	1.915	2.236
11,000	…	1.201	1.322	1.464	1.633	1.844	2.121
11,500	…	1.193	1.306	1.437	1.593	1.784	2.027
12,000	…	1.183	1.291	1.414	1.558	1.732	1.949
12,500	…	…	1.277	1.393	1.527	1.687	1.878
13,000	…	…	1.264	1.374	1.500	1.647	1.825
13,500	…	…	1.253	1.357	1.475	1.612	1.775
14,000	…	…	1.243	1.341	1.453	1.581	1.732
14,500	…	…	1.233	1.327	1.432	1.553	1.693
15,000	…	…	1.224	1.314	1.414	1.527	1.658
16,000	…	…	1.209	1.291	1.381	1.483	1.599

Then, $t = \frac{pD}{4S}$

This formula also applies to hemi-spherical shells, such as the hemi-spherical head of a cylindrical container subjected to internal pressure, etc.

If metric SI units are used, then:

D = **internal diameter of shell in millimeters**

p = **internal pressure in newtons per square millimeter**

S = **safe tensile stress in newtons per square millimeter**

t = **thickness of metal in the shell in millimeters**

Meters can be used in the formula in place of millimeters, providing the treatment is consistent throughout.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: Find the thickness of metal required in the hemi-spherical end of a cylindrical vessel, 2 feet in diameter, subjected to an internal pressure of 500 pounds per square inch. The material is mild steel and a tensile stress of 10,000 pounds per square inch is allowable.

$$t = \frac{500 \times 2 \times 12}{4 \times 10{,}000} = 0.3 \text{ inch}$$

A similar example using metric SI units is as follows: find the thickness of metal required in the hemi-spherical end of a cylindrical vessel, 750 mm in diameter, subjected to an internal pressure of 3 newtons/mm^2. The material is mild steel and a tensile stress of 70 newtons/mm^2 is allowable.

$$t = \frac{3 \times 750}{4 \times 70} = 8.04 \text{ mm}$$

If the radius of curvature of the domed head of a boiler or container subjected to internal pressure is made equal to the diameter of the boiler, the thickness of the cylindrical shell and of the spherical head should be made the same. For example, if a boiler is 3 feet in diameter, the radius of curvature of its head should also be 3 feet, if material of the same thickness is to be used and the stresses are to be equal in both the head and cylindrical portion.

Collapsing Pressure of Cylinders and Tubes Subjected to External Pressures.— The following formulas may be used for finding the collapsing pressures of lap-welded Bessemer steel tubes:

$$P = 86{,}670\frac{t}{D} - 1386 \tag{28}$$

$$P = 50{,}210{,}000\left(\frac{t}{D}\right)^3 \tag{29}$$

in which P = collapsing pressure in pounds per square inch; D = outside diameter of tube or cylinder in inches; t = thickness of wall in inches.

Formula (28) is for values of P greater than 580 pounds per square inch, and Formula (29) is for values of P less than 580 pounds per square inch. These formulas are substantially correct for all lengths of pipe greater than six diameters between transverse joints that tend to hold the pipe to a circular form. The pressure P found is the actual collapsing pressure, and a suitable factor of safety must be used. Ordinarily, a factor of safety of 5 is sufficient. In cases where there are repeated fluctuations of the pressure, vibration, shocks and other stresses, a factor of safety of from 6 to 12 should be used.

If metric SI units are used the formulas are:

$$\boldsymbol{P = 597.6\frac{t}{D} - 9.556} \tag{30}$$

$$\boldsymbol{P = 346{,}200\left(\frac{t}{D}\right)^3} \tag{31}$$

where P = collapsing pressure in newtons per square millimeter; D = outside diameter of tube or cylinder in millimeters; and t = thickness of wall in millimeters. Formula (30) is for values of P greater than 4 N/mm^2, and Formula (31) is for values of P less than 4 N/mm^2.

The table *Tubes Subjected to External Pressure* is based upon the requirements of the Steam Boat Inspection Service of the Department of Commerce and Labor and gives the permissible working pressures and corresponding minimum wall thickness for long, plain, lap-welded and seamless steel flues subjected to external pressure only. The table thicknesses have been calculated from the formula:

Copyright 2004, Industrial Press, Inc., New York, NY

$$t = \frac{[(F \times p) + 1386]D}{86{,}670}$$

in which D = outside diameter of flue or tube in inches; t = thickness of wall in inches; p = working pressure in pounds per square inch; F = factor of safety. The formula is applicable to working pressures greater than 100 pounds per square inch, to outside diameters from 7 to 18 inches, and to temperatures less than 650°F.

The preceding Formulas (28) and (29) were determined by Prof. R. T. Stewart, Dean of the Mechanical Engineering Department of the University of Pittsburgh, in a series of experiments carried out at the plant of the National Tube Co., McKeesport, Pa.

The apparent fiber stress under which the different tubes failed varied from about 7000 pounds per square inch for the relatively thinnest to 35,000 pounds per square inch for the relatively thickest walls. The average yield point of the material tested was 37,000 pounds and the tensile strength 58,000 pounds per square inch, so it is evident that the strength of a tube subjected to external fluid collapsing pressure is not dependent alone upon the elastic limit or ultimate strength of the material from which it is made.

Tubes Subjected to External Pressure

Outside Diameter of Tube, Inches	Working Pressure in Pounds per Square Inch						
	100	120	140	160	180	200	220
	Thickness of Tube in Inches. Safety Factor, 5						
7	0.152	0.160	0.168	0.177	0.185	0.193	0.201
8	0.174	0.183	0.193	0.202	0.211	0.220	0.229
9	0.196	0.206	0.217	0.227	0.237	0.248	0.258
10	0.218	0.229	0.241	0.252	0.264	0.275	0.287
11	0.239	0.252	0.265	0.277	0.290	0.303	0.316
12	0.261	0.275	0.289	0.303	0.317	0.330	0.344
13	0.283	0.298	0.313	0.328	0.343	0.358	0.373
14	0.301	0.320	0.337	0.353	0.369	0.385	0.402
15	0.323	0.343	0.361	0.378	0.396	0.413	0.430
16	0.344	0.366	0.385	0.404	0.422	0.440	0.459
16	0.366	0.389	0.409	0.429	0.448	0.468	0.488
18	0.387	0.412	0.433	0.454	0.475	0.496	0.516

Dimensions and Maximum Allowable Pressure of Tubes Subjected to External Pressure

Outside Dia., Inches	Thickness of Material, Inches	Max. Pressure Allowed, psi	Outside Dia., Inches	Thickness of Material, Inches	Max. Pressure Allowed, psi	Outside Dia., Inches	Thickness of Material, Inches	Max. Pressure Allowed, psi
2	0.095	427	3	0.109	327	4	0.134	303
2¼	0.095	380	3¼	0.120	332	4½	0.134	238
2½	0.109	392	3½	0.120	308	5	0.148	235
2¾	0.109	356	3¾	0.120	282	6	0.165	199

Copyright 2004, Industrial Press, Inc., New York, NY

SHAFTS

Shaft Calculations

Torsional Strength of Shafting.— In the formulas that follow,

α = angular deflection of shaft in degrees

c = distance from center of gravity to extreme fiber

D = diameter of shaft in inches

G = torsional modulus of elasticity = 11,500,000 pounds per square inch for steel

J = polar moment of inertia of shaft cross-section (see table)

l = length of shaft in inches

N = angular velocity of shaft in revolutions per minute

P = power transmitted in horsepower

S_s = allowable torsional shearing stress in pounds per square inch

T = torsional or twisting moment in inch-pounds

Z_p = polar section modulus (see table page 249)

The allowable twisting moment for a shaft of any cross-section such as circular, square, etc., is:

$$T = S_s \times Z_p \tag{1}$$

For a shaft delivering P horsepower at N revolutions per minute the twisting moment T being transmitted is:

$$T = \frac{63{,}000P}{N} \tag{2}$$

The twisting moment T as determined by this formula should be less than the value determined by using Formula (7) if the maximum allowable stress S_s is not to be exceeded.

The diameter of a solid circular shaft required to transmit a given torque T is:

$$D = \sqrt[3]{\frac{5.1T}{S_s}} \tag{3a}$$ or $$D = \sqrt[3]{\frac{321{,}000P}{NS_s}} \tag{3b}$$

The allowable stresses that are generally used in practice are: 4000 pounds per square inch for main power-transmitting shafts; 6000 pounds per square inch for lineshafts carrying pulleys; and 8500 pounds per square inch for small, short shafts, countershafts, etc. Using these allowable stresses, the horsepower P transmitted by a shaft of diameter D, or the diameter D of a shaft to transmit a given horsepower P may be determined from the following formulas:

For main power-transmitting shafts:

$$P = \frac{D^3N}{80} \tag{4a}$$ or $$D = \sqrt[3]{\frac{80P}{N}} \tag{4b}$$

For lineshafts carrying pulleys:

$$P = \frac{D^3N}{53.5} \tag{5a}$$ or $$D = \sqrt[3]{\frac{53.5P}{N}} \tag{5b}$$

Copyright 2004, Industrial Press, Inc., New York, NY

For small, short shafts:

$$P = \frac{D^3 N}{38} \quad (6a) \qquad \text{or} \qquad D = \sqrt[3]{\frac{38P}{N}} \quad (6b)$$

Shafts that are subjected to shocks, such as sudden starting and stopping, should be given a greater factor of safety resulting in the use of lower allowable stresses than those just mentioned.

Example: What should be the diameter of a lineshaft to transmit 10 horsepower if the shaft is to make 150 revolutions per minute? Using Formula (5b),

$$D = \sqrt[3]{\frac{53.5 \times 10}{150}} = 1.53 \text{ or, say, } 1\tfrac{9}{16} \text{ inches}$$

Example: What horsepower would be transmitted by a short shaft, 2 inches in diameter, carrying two pulleys close to the bearings, if the shaft makes 300 revolutions per minute? Using Formula (6a),

$$P = \frac{2^3 \times 300}{38} = 63 \text{ horsepower}$$

Torsional Strength of Shafting, Calculations in Metric SI Units.— The allowable twisting moment for a shaft of any cross-section such as circular, square, etc., can be calculated from:

$$T = S_s \times Z_p \quad (7)$$

where T = torsional or twisting moment in newton-millimeters; S_s = allowable torsional shearing stress in newtons per square millimeter; and Z_p = polar section modulus in millimeters^3.

For a shaft delivering power of P kilowatts at N revolutions per minute, the twisting moment T being transmitted is:

$$T = \frac{9.55 \times 10^6 P}{N} \quad (8) \qquad \text{or} \qquad T = \frac{10^6 P}{\omega} \quad (8a)$$

where T is in newton-millimeters, and ω = angular velocity in radians per second.

The diameter D of a solid circular shaft required to transmit a given torque T is:

$$D = \sqrt[3]{\frac{5.1T}{S_s}} \quad (9a) \qquad \text{or} \qquad D = \sqrt[3]{\frac{48.7 \times 10^6 P}{NS_s}} \quad (9b)$$

$$\text{or} \qquad D = \sqrt[3]{\frac{5.1 \times 10^6 P}{\omega S_s}} \quad (9c)$$

where D is in millimeters; T is in newton-millimeters; P is power in kilowatts; N = revolutions per minute; S_s = allowable torsional shearing stress in newtons per square millimeter, and ω = angular velocity in radians per second.

If 28 newtons/mm^2 and 59 newtons/mm^2 are taken as the generally allowed stresses for main power-transmitting shafts and small short shafts, respectively, then using these allowable stresses, the power P transmitted by a shaft of diameter D, or the diameter D of a shaft to transmit a given power P may be determined from the following formulas:

Copyright 2004, Industrial Press, Inc., New York, NY

For main power-transmitting shafts:

$$P = \frac{D^3 N}{1.77 \times 10^6} \quad \textbf{(10a)} \qquad \text{or} \qquad D = \sqrt[3]{\frac{1.77 \times 10^6 P}{N}} \quad \textbf{(10b)}$$

For small, short shafts:

$$P = \frac{D^3 N}{0.83 \times 10^6} \quad \textbf{(11a)} \qquad \text{or} \qquad D = \sqrt[3]{\frac{0.83 \times 10^6 P}{N}} \quad \textbf{(11b)}$$

where P is in kilowatts, D is in millimeters, and N = revolutions per minute.

Example: **What should be the diameter of a power-transmitting shaft to transmit 150 kW at 500 rpm?**

$$D = \sqrt[3]{\frac{1.77 \times 10^6 \times 150}{500}} = 81 \text{ millimeters}$$

Example: **What power would a short shaft, 50 millimeters in diameter, transmit at 400 rpm?**

$$P = \frac{50^3 \times 400}{0.83 \times 10^6} = 60 \text{ kilowatts}$$

Torsional Deflection of Circular Shafts.— Shafting must often be proportioned not only to provide the strength required to transmit a given torque, but also to prevent torsional deflection (twisting) through a greater angle than has been found satisfactory for a given type of service.

For a solid circular shaft the torsional deflection in degrees is given by:

$$\alpha = \frac{584 T l}{D^4 G} \quad (12)$$

Example: Find the torsional deflection for a solid steel shaft 4 inches in diameter and 48 inches long, subjected to a twisting moment of 24,000 inch-pounds. By Formula (12),

$$\alpha = \frac{584 \times 24{,}000 \times 48}{4^4 \times 11{,}500{,}000} = 0.23 \text{ degree}$$

Formula (12) can be used with metric SI units, where α = angular deflection of shaft in degrees; T = torsional moment in newton-millimeters; l = length of shaft in millimeters; D = diameter of shaft in millimeters; and G = torsional modulus of elasticity in newtons per square millimeter.

Example: **Find the torsional deflection of a solid steel shaft, 100 mm in diameter and 1300 mm long, subjected to a twisting moment of 3×10^6 newton-millimeters. The torsional modulus of elasticity is 80,000 newtons/mm^2. By Formula (12)**

$$\alpha = \frac{584 \times 3 \times 10^6 \times 1300}{100^4 \times 80{,}000} = 0.285 \text{ degree}$$

The diameter of a shaft that is to have a maximum torsional deflection α is given by:

$$D = 4.9 \times \sqrt[4]{\frac{Tl}{G\alpha}} \quad (13)$$

Formula (13) can be used with metric SI units, where D = diameter of shaft in millimeters; T = torsional moment in newton-millimeters; l = length of shaft in millime-

Copyright 2004, Industrial Press, Inc., New York, NY

ters; G = torsional modulus of elasticity in newtons per square millimeter; and α = angular deflection of shaft in degrees.

According to some authorities, the allowable twist in steel transmission shafting should not exceed 0.08 degree per foot length of the shaft. The diameter D of a shaft that will permit a maximum angular deflection of 0.08 degree per foot of length for a given torque T or for a given horsepower P can be determined from the formulas:

$$D = 0.29\sqrt[4]{T} \qquad (14a) \qquad \text{or} \qquad D = 4.6 \times \sqrt[4]{\frac{P}{N}} \qquad (14b)$$

Using metric SI units and assuming an allowable twist in steel transmission shafting of 0.26 degree per meter length, Formulas (14a) and (14b) become:

$$\boldsymbol{D = 2.26\sqrt[4]{T}} \qquad \text{or} \qquad \boldsymbol{D = 125.7 \times \sqrt[4]{\frac{P}{N}}}$$

where D = diameter of shaft in millimeters; T = torsional moment in newton-millimeters; P = power in kilowatts; and N = revolutions per minute.

Another rule that has been generally used in mill practice limits the deflection to 1 degree in a length equal to 20 times the shaft diameter. For a given torque or horsepower, the diameter of a shaft having this maximum deflection is given by:

$$D = 0.1\sqrt[3]{T} \qquad (15a) \qquad \text{or} \qquad D = 4.0 \times \sqrt[3]{\frac{P}{N}} \qquad (15b)$$

Example: Find the diameter of a steel lineshaft to transmit 10 horsepower at 150 revolutions per minute with a torsional deflection not exceeding 0.08 degree per foot of length. By Formula (14b),

$$D = 4.6 \times \sqrt[4]{\frac{10}{150}} = 2.35 \text{ inches}$$

This diameter is larger than that obtained for the same horsepower and rpm in the example given for Formula (5b) in which the diameter was calculated for strength considerations only. The usual procedure in the design of shafting which is to have a specified maximum angular deflection is to compute the diameter first by means of Formulas (13), (14a), (14b), (15a), or (15b) and then by means of Formulas (3a), (3b), (4b), (5b), or (6b), using the larger of the two diameters thus found.

Linear Deflection of Shafting.— For steel line shafting, it is considered good practice to limit the linear deflection to a maximum of 0.010 inch per foot of length. The maximum distance in feet between bearings, for average conditions, in order to avoid excessive linear deflection, is determined by the formulas:

$L = 8.95\sqrt[3]{D^2}$ for shafting subject to no bending action except it's own weight

$L = 5.2\sqrt[3]{D^2}$ for shafting subject to bending action of pulleys, etc.

in which D = diameter of shaft in inches and L = maximum distance between bearings in feet. Pulleys should be placed as close to the bearings as possible.

In general, shafting up to three inches in diameter is almost always made from cold-rolled steel. This shafting is true and straight and needs no turning, but if keyways are cut in the shaft, it must usually be straightened afterwards, as the cutting of the keyways relieves the tension on the surface of the shaft produced by the cold-rolling process. Sizes of shafting from three to five inches in diameter may be either cold-rolled or turned, more frequently the latter, and all larger sizes of shafting must be turned because cold-rolled shafting is not available in diameters larger than 5 in.

Copyright 2004, Industrial Press, Inc., New York, NY

Diameters of Finished Shafting (former American Standard *ASA B17.1***)**

Diameters, Inches		Minus Tolerances, Inches[a]	Diameters, Inches		Minus Tolerances Inches[a]	Diameters, Inches		Minus Tolerances, Inches[a]
Transmission Shafting	Machinery Shafting		Transmission Shafting	Machinery Shafting		Transmission Shafting	Machinery Shafting	
	1/2	0.002		1 13/16	0.003		3 3/4	0.004
	9/16	0.002		1 7/8	0.003		3 7/8	0.004
	5/8	0.002	1 15/16	1 15/16	0.003	3 15/16	4	0.004
	11/16	0.002		2	0.003		4 1/4	0.005
	3/4	0.002		2 1/16	0.004	4 1/16	4 1/2	0.005
	13/16	0.002		2 1/8	0.004		4 3/4	0.005
	7/8	0.002	2 3/16	2 3/16	0.004	4 15/16	5	0.005
15/16	15/16	0.002		2 1/4	0.004		5 1/4	0.005
	1	0.002		2 5/16	0.004	5 7/16	5 1/2	0.005
	1 1/16	0.003		2 3/8	0.004		5 3/4	0.005
	1 1/8	0.003	2 7/16	2 7/16	0.004	5 15/16	6	0.005
1 3/16	1 3/16	0.003		2 1/2	0.004		6 1/4	0.006
	1 1/4	0.003		2 5/8	0.004	6 1/2	6 1/2	0.006
	1 5/16	0.003		2 3/4	0.004		6 3/4	0.006
	1 3/8	0.003	2 15/16	2 7/8	0.004	7	7	0.006
1 7/16	1 7/16	0.003		3	0.004		7 1/4	0.006
	1 1/2	0.003		3 1/8	0.004	7 1/2	7 1/2	0.006
	1 9/16	0.003		3 1/4	0.004		7 3/4	0.006
	1 5/8	0.003		3 3/8	0.004	8	8	0.006
1 11/16	1 11/16	0.003	3 7/16	3 1/2	0.004	...	...	...
	1 3/4	0.003		3 5/8	0.004	...	...	...

[a] *Note:*—These tolerances are *negative* or minus and represent the maximum allowable variation *below* the exact nominal size. For instance the maximum diameter of the 1 15/16 inch shaft is 1.938 inch and its minimum allowable diameter is 1.935 inch. Stock lengths of finished transmission shafting shall be: 16, 20 and 24 feet.

Design of Transmission Shafting.— The following guidelines for the design of shafting for transmitting a given amount of power under various conditions of loading are based upon formulas given in the former American Standard ASA B17c Code for the Design of Transmission Shafting. These formulas are based on the *maximum-shear theory* of failure which assumes that the elastic limit of a *ductile* ferrous material in shear is practically one-half its elastic limit in tension. This theory agrees, very nearly, with the results of tests on ductile materials and has gained wide acceptance in practice.

The formulas given apply in all shaft designs including shafts for special machinery. The limitation of these formulas is that they provide only for the strength of shafting and are not concerned with the torsional or lineal deformations which may, in shafts used in machine design, be the controlling factor (see *Torsional Deflection of Circular Shafts* on page 301 and *Linear Deflection of Shafting* on page 302 for deflection considerations). In the formulas that follow,

$B = \sqrt[3]{1 \div (1 - K^4)}$ (see Table 3)

D = outside diameter of shaft in inches

D_1 = inside diameter of a hollow shaft in inches

K_m = shock and fatigue factor to be applied in every case to the computed bending moment (see Table 1)

K_t = combined shock and fatigue factor to be applied in every case to the computed torsional moment (see Table 1)

M = maximum bending moment in inch-pounds

N = revolutions per minute

P = maximum power to be transmitted by the shaft in horsepower

Copyright 2004, Industrial Press, Inc., New York, NY

p_t = maximum allowable shearing stress under combined loading conditions in pounds per square inch (see Table 2)

S = maximum allowable flexural (bending) stress, in either tension or compression in pounds per square inch (see Table 2)

S_s = maximum allowable torsional shearing stress in pounds per square inch (see Table 2)

T = maximum torsional moment in inch-pounds

V = maximum transverse shearing load in pounds

For shafts subjected to pure torsional loads only,

$$D = B\sqrt[3]{\frac{5.1K_tT}{S_s}} \quad (16a) \qquad \text{or} \qquad D = B\sqrt[3]{\frac{321{,}000K_tP}{S_sN}} \quad (16b)$$

For stationary shafts subjected to bending only,

$$D = B\sqrt[3]{\frac{10.2K_mM}{S}} \quad (17)$$

For shafts subjected to combined torsion and bending,

$$D = B\sqrt[3]{\frac{5.1}{p_t}\sqrt{(K_mM)^2 + (K_tT)^2}} \quad (18a)$$

or

$$D = B\sqrt[3]{\frac{5.1}{p_t}\sqrt{(K_mM)^2 + \left(\frac{63{,}000K_tP}{N}\right)^2}} \quad (18b)$$

Formulas (16a) to (18b) may be used for solid shafts or for hollow shafts. For solid shafts the factor B is equal to 1, whereas for hollow shafts the value of B depends on the value of K which, in turn, depends on the ratio of the inside diameter of the shaft to the outside diameter ($D_1 \div D = K$). Table 3 gives values of B corresponding to various values of K.

For short solid shafts subjected only to heavy transverse shear, the diameter of shaft required is:

$$D = \sqrt{\frac{1.7V}{S_s}} \quad (19)$$

Formulas (16a), (17), (18a) and (19), can be used unchanged with metric SI units. Formula (16b) becomes:

$$D = B\sqrt[3]{\frac{48.7K_tP}{S_sN}}$$ **and Formula (18b) becomes:**

$$D = B\sqrt[3]{\frac{5.1}{p_t}\sqrt{(K_mM)^2 + \left(\frac{9.55K_tP}{N}\right)^2}}$$

Throughout the formulas, D = outside diameter of shaft in millimeters; T = maximum torsional moment in newton-millimeters; S_s = maximum allowable torsional shearing stress in newtons per millimeter squared (see Table 2); P = maximum power to be transmitted in milliwatts; N = revolutions per minute; M = maximum bending moment in newton-millimeters; S = maximum allowable flexural (bending) stress, either in tension or compression in newtons per millimeter squared (see Table 2); p_t = maximum allowable shearing stress under combined loading conditions in newtons

Copyright 2004, Industrial Press, Inc., New York, NY

per millimeter squared; and V = maximum transverse shearing load in kilograms. The factors K_m, K_t, and B are unchanged, and D_1 = the inside diameter of a hollow shaft in millimeters.

Table 1. Recommended Values of the Combined Shock and Fatigue Factors for Various Types of Load

Type of Load	Stationary Shafts		Rotating Shafts	
	K_m	K_t	K_m	K_t
Gradually applied and steady	1.0	1.0	1.5	1.0
Suddenly applied, minor shocks only	1.5–2.0	1.5–2.0	1.5–2.0	1.0–1.5
Suddenly applied, heavy shocks	…	…	2.0–3.0	1.5–3.0

Table 2. Recommended Maximum Allowable Working Stresses for Shafts Under Various Types of Load

Material	Type of Load		
	Simple Bending	Pure Torsion	Combined Stress
"Commercial Steel" shafting without keyways	S = 16,000	S_s = 8000	p_t = 8000
"Commercial Steel" shafting with keyways	S = 12,000	S_s = 6000	p_t = 6000
Steel purchased under definite physical specs.	(See note [a])	(See note [b])	(See note [b])

[a] S = 60 per cent of the elastic limit in tension but not more than 36 per cent of the ultimate tensile strength.

[b] S_s and p_t = 30 per cent of the elastic limit in tension but not more than 18 per cent of the ultimate tensile strength.

If the values in the Table are converted to metric SI units, note that 1000 pounds per square inch = 6.895 newtons per square millimeter.

Table 3. Values of the Factor B Corresponding to Various Values of K for Hollow Shafts

$K = \frac{D_1}{D}$ =	0.95	0.90	0.85	0.80	0.75	0.70	0.65	0.60	0.55	0.50
$B = \sqrt[3]{1 \div (1 - K^4)}$	1.75	1.43	1.28	1.19	1.14	1.10	1.07	1.05	1.03	1.02

For solid shafts, $B = 1$ because $K = 0$, as follows: $B = \sqrt[3]{1 \div (1 - K^4)} = \sqrt[3]{1 \div (1 - 0)} = 1$

Effect of Keyways on Shaft Strength.— Keyways cut into a shaft reduce its load carrying ability, particularly when impact loads or stress reversals are involved. To ensure an adequate factor of safety in the design of a shaft with standard keyway (width, one-quarter, and depth, one-eighth of shaft diameter), the former Code for Transmission Shafting tentatively recommended that shafts with keyways be designed on the basis of a solid circular shaft using not more than 75 per cent of the working stress recommended for the solid shaft. See also page 2363.

Formula for Shafts of Brittle Materials.— The preceding formulas are applicable to ductile materials and are based on the maximum-shear theory of failure which assumes that the elastic limit of a *ductile* material in shear is one-half its elastic limit in tension.

Brittle materials are generally stronger in shear than in tension; therefore, the maximum-shear theory is not applicable. The *maximum-normal-stress theory* of failure is now generally accepted for the design of shafts made from brittle materials. A material may be considered to be brittle if its elongation in a 2-inch gage length is less than 5 per cent. Materials such as cast iron, hardened tool steel, hard bronze, etc., conform to this rule. The diameter of a shaft made of a brittle material may be determined from the following formula which is based on the maximum-normal-stress theory of failure:

Copyright 2004, Industrial Press, Inc., New York, NY

$$D = B\sqrt[3]{\frac{5.1}{S_t}\left[(K_m M) + \sqrt{(K_m M)^2 + (K_t T)^2}\right]}$$

where S_t is the maximum allowable tensile stress in pounds per square inch and the other quantities are as previously defined.

The formula can be used unchanged with metric SI units, where D = outside diameter of shaft in millimeters; S_t = the maximum allowable tensile stress in newtons per millimeter squared; M = maximum bending moment in newton-millimeters; and T = maximum torsional moment in newton-millimeters. The factors K_m, K_t, and B are unchanged.

Critical Speed of Rotating Shafts.— At certain speeds, a rotating shaft will become dynamically unstable and the resulting vibrations and deflections can result in damage not only to the shaft but to the machine of which it is a part. The speeds at which such dynamic instability occurs are called the critical speeds of the shaft. On page 196 are given formulas for the critical speeds of shafts subject to various conditions of loading and support. A shaft may be safely operated either above or below its critical speed, good practice indicating that the operating speed be at least 20 per cent above or below the critical.

The formulas commonly used to determine critical speeds are sufficiently accurate for general purposes. However, the torque applied to a shaft has an important effect on its critical speed. Investigations have shown that the critical speeds of a uniform shaft are decreased as the applied torque is increased, and that there exist critical torques which will reduce the corresponding critical speed of the shaft to zero. A detailed analysis of the effects of applied torques on critical speeds may be found in a paper. "Critical Speeds of Uniform Shafts under Axial Torque," by Golomb and Rosenberg presented at the First U.S. National Congress of Applied Mechanics in 1951.

Shaft Couplings.— A shaft coupling is a device for fastening together the ends of two shafts, so that the rotary motion of one causes rotary motion of the other. One of the most simple and common forms of coupling is the flange coupling Figs. 1a and 1b. It consists of two flanged sleeves or hubs, each of which is keyed to the end of one of the two shafts to be connected. The sleeves are held together and prevented from rotating relative to each other by bolts through the flanges as indicated.

Flange Coupling



Fig. 1a.



Fig. 1b.

Flexible Couplings: Flexible couplings are the most common mechanical means of compensating for unavoidable errors in alignment of shafts and shafting. When correctly applied, they are highly efficient for joining lengths of shafting without causing loss of power from bearing friction due to misalignment, and for use in direct motor drives for all kinds of machinery. Flexible couplings are not intended to be used for connecting a driven shaft and a driving shaft that are purposely placed in different planes or at an angle but are intended simply to overcome slight unavoidable errors in alignment that develop in service. There is a wide variety of flexible coupling designs; most of them consist essentially

Copyright 2004, Industrial Press, Inc., New York, NY

of two flanged members or hubs, fastened to the shafts and connected by some yielding arrangement. Balance is an important factor in coupling selection or design; it is not sufficient that the coupling be perfectly balanced when installed, but it must remain in balance after wear has taken place.

Comparison of Hollow and Solid Shafting with Same Outside Diameter.— Table 4 that follows gives the per cent decrease in strength and weight of a hollow shaft relative to the strength and weight of a solid shaft of the same diameter. The upper figures in each line give the per cent decrease in strength and the lower figures give the per cent decrease in weight.

Example: A 4-inch shaft, with a 2-inch hole through it, has a weight 25 per cent less than a solid 4-inch shaft, but its strength is decreased only 6.25 per cent.

Table 4. Comparative Torsional Strengths and Weights of Hollow and Solid Shafting with Same Outside Diameter

Dia. of Solid and Hollow Shaft, Inches	Diameter of Axial Hole in Hollow Shaft, Inches									
	1	1¼	1½	1¾	2	2½	3	3½	4	4½
1½	19.76	48.23	…	…	…	…	…	…	…	…
	44.44	69.44	…	…	…	…	…	…	…	…
1¾	10.67	26.04	53.98	…	…	…	…	…	…	…
	32.66	51.02	73.49	…	…	…	…	…	…	…
2	6.25	15.26	31.65	58.62	…	…	…	…	…	…
	25.00	39.07	56.25	76.54	…	…	…	…	…	…
2¼	3.91	9.53	19.76	36.60	62.43	…	…	…	…	…
	19.75	30.87	44.44	60.49	79.00	…	…	…	…	…
2½	2.56	6.25	12.96	24.01	40.96	…	…	…	…	…
	16.00	25.00	36.00	49.00	64.00	…	…	…	…	…
2¾	1.75	4.28	8.86	16.40	27.98	68.30	…	…	…	…
	13.22	20.66	29.74	40.48	52.89	82.63	…	…	…	…
3	1.24	3.01	6.25	11.58	19.76	48.23	…	…	…	…
	11.11	17.36	25.00	34.01	44.44	69.44	…	…	…	…
3¼	0.87	2.19	4.54	8.41	14.35	35.02	72.61	…	…	…
	9.46	14.80	21.30	29.00	37.87	59.17	85.22	…	…	…
3½	0.67	1.63	3.38	6.25	10.67	26.04	53.98	…	…	…
	8.16	12.76	18.36	25.00	32.66	51.02	73.49	…	…	…
3¾	0.51	1.24	2.56	4.75	8.09	19.76	40.96	75.89	…	…
	7.11	11.11	16.00	21.77	28.45	44.44	64.00	87.10	…	…
4	0.40	0.96	1.98	3.68	6.25	15.26	31.65	58.62	…	…
	6.25	9.77	14.06	19.14	25.00	39.07	56.25	76.56	…	…
4¼	0.31	0.74	1.56	2.89	4.91	11.99	24.83	46.00	78.47	…
	5.54	8.65	12.45	16.95	22.15	34.61	49.85	67.83	88.59	…
4½	0.25	0.70	1.24	2.29	3.91	9.53	19.76	36.60	62.43	…
	4.94	7.72	11.11	15.12	19.75	30.87	44.44	60.49	79.00	…
4¾	0.20	0.50	1.00	1.85	3.15	7.68	15.92	29.48	50.29	80.56
	4.43	6.93	9.97	13.57	17.73	27.70	39.90	54.29	70.91	89.75
5	0.16	0.40	0.81	1.51	2.56	6.25	12.96	24.01	40.96	65.61
	4.00	6.25	8.10	12.25	16.00	25.00	36.00	49.00	64.00	81.00
5½	0.11	0.27	0.55	1.03	1.75	4.27	8.86	16.40	27.98	44.82
	3.30	5.17	7.43	10.12	13.22	20.66	29.76	40.48	52.89	66.94
6	0.09	0.19	0.40	0.73	1.24	3.02	6.25	11.58	19.76	31.65
	2.77	4.34	6.25	8.50	11.11	17.36	25.00	34.02	44.44	56.25
6½	0.06	0.14	0.29	0.59	0.90	2.19	4.54	8.41	14.35	23.98
	2.36	3.70	5.32	7.24	9.47	14.79	21.30	28.99	37.87	47.93
7	0.05	0.11	0.22	0.40	0.67	1.63	3.38	6.25	10.67	17.08
	2.04	3.19	4.59	6.25	8.16	12.76	18.36	25.00	32.66	41.33
7½	0.04	0.08	0.16	0.30	0.51	1.24	2.56	4.75	8.09	12.96
	1.77	2.77	4.00	5.44	7.11	11.11	16.00	21.77	28.45	36.00
8	0.03	0.06	0.13	0.23	0.40	0.96	1.98	3.68	6.25	10.02
	1.56	2.44	3.51	4.78	6.25	9.77	14.06	19.14	25.00	31.64

The upper figures in each line give number of per cent decrease in strength; the lower figures give per cent decrease in weight.

Copyright 2004, Industrial Press, Inc., New York, NY

SPRINGS

Introduction to Spring Design

Many advances have been made in the spring industry in recent years. For example: developments in materials permit longer fatigue life at higher stresses; simplified design procedures reduce the complexities of design, and improved methods of manufacture help to speed up some of the complicated fabricating procedures and increase production. New types of testing instruments and revised tolerances also permit higher standards of accuracy. Designers should also consider the possibility of using standard springs now available from stock. They can be obtained from spring manufacturing companies located in different areas, and small shipments usually can be made quickly.

Designers of springs require information in the following order of precedence to simplify design procedures.

1) Spring materials and their applications
2) Allowable spring stresses
3) Spring design data with tables of spring characteristics, tables of formulas, and tolerances.

Only the more commonly used types of springs are covered in detail here. Special types and designs rarely used such as torsion bars, volute springs, Belleville washers, constant force, ring and spiral springs and those made from rectangular wire are only described briefly. Belleville and disc springs are discussed in the section *DISC SPRINGS* starting on page 354

Notation.— The following symbols are used in spring equations:

AC = Active coils
b = Widest width of rectangular wire, inches
CL = Compressed length, inches
D = Mean coil diameter, inches $= OD - d$
d = Diameter of wire or side of square, inches
E = Modulus of elasticity in tension, pounds per square inch
F = Deflection, for N coils, inches
$F°$ = Deflection, for N coils, rotary, degrees
f = Deflection, for one active coil
FL = Free length, unloaded spring, inches
G = Modulus of elasticity in torsion, pounds per square inch
IT = Initial tension, pounds
K = Curvature stress correction factor
L = Active length subject to deflection, inches
N = Number of active coils, total
P = Load, pounds
p = pitch, inches
R = Distance from load to central axis, inches
S or S_t = Stress, torsional, pounds per square inch
S_b = Stress, bending, pounds per square inch
SH = Solid height
S_{ti} = Stress, torsional, due to initial tension, pounds per square inch
T = Torque $= P \times R$, pound-inches
TC = Total coils
t = Thickness, inches
U = Number of revolutions $= F°/360°$

Copyright 2004, Industrial Press, Inc., New York, NY

Spring Materials

The spring materials most commonly used include high-carbon spring steels, alloy spring steels, stainless spring steels, copper-base spring alloys, and nickel-base spring alloys.

High-Carbon Spring Steels in Wire Form.— These spring steels are the most commonly used of all spring materials because they are the least expensive, are easily worked, and are readily available. However, they are not satisfactory for springs operating at high or low temperatures or for shock or impact loading. The following wire forms are available:

Music Wire, ASTM A228 (0.80–0.95 per cent carbon)*:* This is the most widely used of all spring materials for small springs operating at temperatures up to about 250 degrees F. It is tough, has a high tensile strength, and can withstand high stresses under repeated loading. The material is readily available in round form in diameters ranging from 0.005 to 0.125 inch and in some larger sizes up to $\frac{3}{16}$ inch. It is not available with high tensile strengths in square or rectangular sections. Music wire can be plated easily and is obtainable pretinned or preplated with cadmium, but plating after spring manufacture is usually preferred for maximum corrosion resistance.

Oil-Tempered MB Grade, ASTM A229 (0.60–0.70 per cent carbon)*:* This general-purpose spring steel is commonly used for many types of coil springs where the cost of music wire is prohibitive and in sizes larger than are available in music wire. It is readily available in diameters ranging from 0.125 to 0.500 inch, but both smaller and larger sizes may be obtained. The material should not be used under shock and impact loading conditions, at temperatures above 350 degrees F., or at temperatures in the sub-zero range. Square and rectangular sections of wire are obtainable in fractional sizes. Annealed stock also can be obtained for hardening and tempering after coiling. This material has a heat-treating scale that must be removed before plating.

Oil-Tempered HB Grade, SAE 1080 (0.75–0.85 per cent carbon)*:* This material is similar to the MB Grade except that it has a higher carbon content and a higher tensile strength. It is obtainable in the same sizes and is used for more accurate requirements than the MB Grade, but is not so readily available. In lieu of using this material it may be better to use an alloy spring steel, particularly if a long fatigue life or high endurance properties are needed. Round and square sections are obtainable in the oil-tempered or annealed conditions.

Hard-Drawn MB Grade, ASTM A227 (0.60–0.70 per cent carbon)*:* This grade is used for general-purpose springs where cost is the most important factor. Although increased use in recent years has resulted in improved quality, it is best not to use it where long life and accuracy of loads and deflections are important. It is available in diameters ranging from 0.031 to 0.500 inch and in some smaller and larger sizes also. The material is available in square sections but at reduced tensile strengths. It is readily plated. Applications should be limited to those in the temperature range of 0 to 250 degrees F.

High-Carbon Spring Steels in Flat Strip Form.— Two types of thin, flat, high-carbon spring steel strip are most widely used although several other types are obtainable for specific applications in watches, clocks, and certain instruments. These two compositions are used for over 95 per cent of all such applications. Thin sections of these materials under 0.015 inch having a carbon content of over 0.85 per cent and a hardness of over 47 on the Rockwell C scale are susceptible to hydrogen-embrittlement even though special plating and heating operations are employed. The two types are described as follows:

Cold-Rolled Spring Steel, Blue-Tempered or Annealed, SAE 1074, also 1064, and 1070 (0.60 to 0.80 per cent carbon)*:* This very popular spring steel is available in thicknesses ranging from 0.005 to 0.062 inch and in some thinner and thicker sections. The material is available in the annealed condition for forming in 4-slide machines and in presses, and can

Copyright 2004, Industrial Press, Inc., New York, NY

readily be hardened and tempered after forming. It is also available in the heat-treated or blue-tempered condition. The steel is obtainable in several finishes such as straw color, blue color, black, or plain. Hardnesses ranging from 42 to 46 Rockwell C are recommended for spring applications. Uses include spring clips, flat springs, clock springs, and motor, power, and spiral springs.

Cold-Rolled Spring Steel, Blue-Tempered Clock Steel, SAE 1095 (0.90 to 1.05 per cent carbon)*:* This popular type should be used principally in the blue-tempered condition. Although obtainable in the annealed condition, it does not always harden properly during heat-treatment as it is a "shallow" hardening type. It is used principally in clocks and motor springs. End sections of springs made from this steel are annealed for bending or piercing operations. Hardnesses usually range from 47 to 51 Rockwell C.

Other materials available in strip form and used for flat springs are brass, phosphor-bronze, beryllium-copper, stainless steels, and nickel alloys.

Alloy Spring Steels.— These spring steels are used for conditions of high stress, and shock or impact loadings. They can withstand both higher and lower temperatures than the high-carbon steels and are obtainable in either the annealed or pretempered conditions.

Chromium Vanadium, ASTM A231: This very popular spring steel is used under conditions involving higher stresses than those for which the high-carbon spring steels are recommended and is also used where good fatigue strength and endurance are needed. It behaves well under shock and impact loading. The material is available in diameters ranging from 0.031 to 0.500 inch and in some larger sizes also. In square sections it is available in fractional sizes. Both the annealed and pretempered types are available in round, square, and rectangular sections. It is used extensively in aircraft-engine valve springs and for springs operating at temperatures up to 425 degrees F.

Silicon Manganese: This alloy steel is quite popular in Great Britain. It is less expensive than chromium-vanadium steel and is available in round, square, and rectangular sections in both annealed and pretempered conditions in sizes ranging from 0.031 to 0.500 inch. It was formerly used for knee-action springs in automobiles. It is used in flat leaf springs for trucks and as a substitute for more expensive spring steels.

Chromium Silicon, ASTM A401: This alloy is used for highly stressed springs that require long life and are subjected to shock loading. It can be heat-treated to higher hardnesses than other spring steels so that high tensile strengths are obtainable. The most popular sizes range from 0.031 to 0.500 inch in diameter. Very rarely are square, flat, or rectangular sections used. Hardnesses ranging from 50 to 53 Rockwell C are quite common and the alloy may be used at temperatures up to 475 degrees F. This material is usually ordered specially for each job.

Stainless Spring Steels.— The use of stainless spring steels has increased and several compositions are available all of which may be used for temperatures up to 550 degrees F. They are all corrosion resistant. Only the stainless 18-8 compositions should be used at sub-zero temperatures.

Stainless Type 302, ASTM A313 (18 per cent chromium, 8 per cent nickel)*:* This stainless spring steel is very popular because it has the highest tensile strength and quite uniform properties. It is cold-drawn to obtain its mechanical properties and cannot be hardened by heat treatment. This material is nonmagnetic only when fully annealed and becomes slightly magnetic due to the cold-working performed to produce spring properties. It is suitable for use at temperatures up to 550 degrees F. and for sub-zero temperatures. It is very corrosion resistant. The material best exhibits its desirable mechanical properties in diameters ranging from 0.005 to 0.1875 inch although some larger diameters are available. It is also available as hard-rolled flat strip. Square and rectangular sections are available but are infrequently used.

Copyright 2004, Industrial Press, Inc., New York, NY

Stainless Type 304, ASTM A313 (18 per cent chromium, 8 per cent nickel)*:* This material is quite similar to Type 302, but has better bending properties and about 5 per cent lower tensile strength. It is a little easier to draw, due to the slightly lower carbon content.

Stainless Type 316, ASTM A313 (18 per cent chromium, 12 per cent nickel, 2 per cent molybdenum)*:* This material is quite similar to Type 302 but is slightly more corrosion resistant because of its higher nickel content. Its tensile strength is 10 to 15 per cent lower than Type 302. It is used for aircraft springs.

Stainless Type 17-7 PH ASTM A313 (17 per cent chromium, 7 per cent nickel)*:* This alloy, which also contains small amounts of aluminum and titanium, is formed in a moderately hard state and then precipitation hardened at relatively low temperatures for several hours to produce tensile strengths nearly comparable to music wire. This material is not readily available in all sizes, and has limited applications due to its high manufacturing cost.

Stainless Type 414, SAE 51414 (12 per cent chromium, 2 per cent nickel)*:* This alloy has tensile strengths about 15 per cent lower than Type 302 and can be hardened by heat-treatment. For best corrosion resistance it should be highly polished or kept clean. It can be obtained hard drawn in diameters up to 0.1875 inch and is commonly used in flat cold-rolled strip for stampings. The material is not satisfactory for use at low temperatures.

Stainless Type 420, SAE 51420 (13 per cent chromium)*:* This is the best stainless steel for use in large diameters above 0.1875 inch and is frequently used in smaller sizes. It is formed in the annealed condition and then hardened and tempered. It does not exhibit its stainless properties until after it is hardened. Clean bright surfaces provide the best corrosion resistance, therefore the heat-treating scale must be removed. Bright hardening methods are preferred.

Stainless Type 431, SAE 51431 (16 per cent chromium, 2 per cent nickel)*:* This spring alloy acquires high tensile properties (nearly the same as music wire) by a combination of heat-treatment to harden the wire plus cold-drawing after heat-treatment. Its corrosion resistance is not equal to Type 302.

Copper-Base Spring Alloys.— Copper-base alloys are important spring materials because of their good electrical properties combined with their good resistance to corrosion. Although these materials are more expensive than the high-carbon and the alloy steels, they nevertheless are frequently used in electrical components and in sub-zero temperatures.

Spring Brass, ASTM B 134 (70 per cent copper, 30 per cent zinc)*:* This material is the least expensive and has the highest electrical conductivity of the copper-base alloys. It has a low tensile strength and poor spring qualities, but is extensively used in flat stampings and where sharp bends are needed. It cannot be hardened by heat-treatment and should not be used at temperatures above 150 degrees F., but is especially good at sub-zero temperatures. Available in round sections and flat strips, this hard-drawn material is usually used in the "spring hard" temper.

Phosphor Bronze, ASTM B 159 (95 per cent copper, 5 per cent tin)*:* This alloy is the most popular of this group because it combines the best qualities of tensile strength, hardness, electrical conductivity, and corrosion resistance with the least cost. It is more expensive than brass, but can withstand stresses 50 per cent higher.The material cannot be hardened by heat-treatment. It can be used at temperatures up to 212 degrees F. and at sub-zero temperatures. It is available in round sections and flat strip, usually in the "extra-hard" or "spring hard" tempers. It is frequently used for contact fingers in switches because of its low arcing properties. An 8 per cent tin composition is used for flat springs and a superfine grain composition called "Duraflex," has good endurance properties.

Beryllium Copper, ASTM B 197 (98 per cent copper, 2 per cent beryllium)*:* This alloy can be formed in the annealed condition and then precipitation hardened after forming at

Copyright 2004, Industrial Press, Inc., New York, NY

temperatures around 600 degrees F, for 2 to 3 hours. This treatment produces a high hardness combined with a high tensile strength. After hardening, the material becomes quite brittle and can withstand very little or no forming. It is the most expensive alloy in the group and heat-treating is expensive due to the need for holding the parts in fixtures to prevent distortion. The principal use of this alloy is for carrying electric current in switches and in electrical components. Flat strip is frequently used for contact fingers.

Nickel-Base Spring Alloys.— Nickel-base alloys are corrosion resistant, withstand both elevated and sub-zero temperatures, and their non-magnetic characteristic makes them useful for such applications as gyroscopes, chronoscopes, and indicating instruments. These materials have a high electrical resistance and therefore should not be used for conductors of electrical current.

Monel[*] (67 per cent nickel, 30 per cent copper)*:* This material is the least expensive of the nickel-base alloys. It also has the lowest tensile strength but is useful due to its resistance to the corrosive effects of sea water and because it is nearly non-magnetic. The alloy can be subjected to stresses slightly higher than phosphor bronze and nearly as high as beryllium copper. Its high tensile strength and hardness are obtained as a result of cold-drawing and cold-rolling only, since it can not be hardened by heat-treatment. It can be used at temperatures ranging from −100 to +425 degrees F. at normal operating stresses and is available in round wires up to $\frac{3}{16}$ inch in diameter with quite high tensile strengths. Larger diameters and flat strip are available with lower tensile strengths.

"K" Monel[*] (66 per cent nickel, 29 per cent copper, 3 per cent aluminum)*:* This material is quite similar to Monel except that the addition of the aluminum makes it a precipitation-hardening alloy. It may be formed in the soft or fairly hard condition and then hardened by a long-time age-hardening heat-treatment to obtain a tensile strength and hardness above Monel and nearly as high as stainless steel. It is used in sizes larger than those usually used with Monel, is non-magnetic and can be used in temperatures ranging from − 100 to + 450 degrees F. at normal working stresses under 45,000 pounds per square inch.

Inconel[*](78 per cent nickel, 14 per cent chromium, 7 per cent iron)*:* This is one of the most popular of the non-magnetic nickel-base alloys because of its corrosion resistance and because it can be used at temperatures up to 700 degrees F. It is more expensive than stainless steel but less expensive than beryllium copper. Its hardness and tensile strength is higher than that of "K" Monel and is obtained as a result of cold-drawing and cold-rolling only. It cannot be hardened by heat treatment. Wire diameters up to $\frac{1}{4}$ inch have the best tensile properties. It is often used in steam valves, regulating valves, and for springs in boilers, compressors, turbines, and jet engines.

Inconel "X"[*](70 per cent nickel, 16 per cent chromium, 7 per cent iron)*:* This material is quite similar to Inconel but the small amounts of titanium, columbium and aluminum in its composition make it a precipitation-hardening alloy. It can be formed in the soft or partially hard condition and then hardened by holding it at 1200 degrees F. for 4 hours. It is non-magnetic and is used in larger sections than Inconel. This alloy is used at temperatures up to 850 degrees F. and at stresses up to 55,000 pounds per square inch.

Duranickel[*] *("Z" Nickel)* (98 per cent nickel)*:* This alloy is non-magnetic, corrosion resistant, has a high tensile strength and is hardenable by precipitation hardening at 900 degrees F. for 6 hours. It may be used at the same stresses as Inconel but should not be used at temperatures above 500 degrees F.

Nickel-Base Spring Alloys with Constant Moduli of Elasticity.— Some special nickel alloys have a constant modulus of elasticity over a wide temperature range. These materials are especially useful where springs undergo temperature changes and must exhibit uniform spring characteristics. These materials have a low or zero thermo-elastic coefficient

[*] Trade name of the International Nickel Company.

Copyright 2004, Industrial Press, Inc., New York, NY

and therefore do not undergo variations in spring stiffness because of modulus changes due to temperature differentials. They also have low hysteresis and creep values which makes them preferred for use in food-weighing scales, precision instruments, gyroscopes, measuring devices, recording instruments and computing scales where the temperature ranges from – 50 to + 150 degrees F. These materials are expensive, none being regularly stocked in a wide variety of sizes. They should not be specified without prior discussion with spring manufacturers because some suppliers may not fabricate springs from these alloys due to the special manufacturing processes required. All of these alloys are used in small wire diameters and in thin strip only and are covered by U.S. patents. They are more specifically described as follows:

Elinvar[*] (nickel, iron, chromium)*:* This alloy, the first constant-modulus alloy used for hairsprings in watches, is an austenitic alloy hardened only by cold-drawing and cold-rolling. Additions of titanium, tungsten, molybdenum and other alloying elements have brought about improved characteristics and precipitation-hardening abilities. These improved alloys are known by the following trade names: Elinvar Extra, Durinval, Modulvar and Nivarox.

Ni-Span C[*] (nickel, iron, chromium, titanium)*:* This very popular constant-modulus alloy is usually formed in the 50 per cent cold-worked condition and precipitation-hardened at 900 degrees F. for 8 hours, although heating up to 1250 degrees F. for 3 hours produces hardnesses of 40 to 44 Rockwell C, permitting safe torsional stresses of 60,000 to 80,000 pounds per square inch. This material is ferromagnetic up to 400 degrees F; above that temperature it becomes non-magnetic.

Iso-Elastic[†] (nickel, iron, chromium, molybdenum)*:* This popular alloy is relatively easy to fabricate and is used at safe torsional stresses of 40,000 to 60,000 pounds per square inch and hardnesses of 30 to 36 Rockwell C. It is used principally in dynamometers, instruments, and food-weighing scales.

Elgiloy[‡] (nickel, iron, chromium, cobalt)*:* This alloy, also known by the trade names 8J Alloy, Durapower, and Cobenium, is a non-magnetic alloy suitable for sub-zero temperatures and temperatures up to about 1000 degrees F., provided that torsional stresses are kept under 75,000 pounds per square inch. It is precipitation-hardened at 900 degrees F. for 8 hours to produce hardnesses of 48 to 50 Rockwell C. The alloy is used in watch and instrument springs.

Dynavar[**] (nickel, iron, chromium, cobalt)*:* This alloy is a non-magnetic, corrosion-resistant material suitable for sub-zero temperatures and temperatures up to about 750 degrees F., provided that torsional stresses are kept below 75,000 pounds per square inch. It is precipitation-hardened to produce hardnesses of 48 to 50 Rockwell C and is used in watch and instrument springs.

Spring Stresses

Allowable Working Stresses for Springs.— The safe working stress for any particular spring depends to a large extent on the following items:

1) Type of spring — whether compression, extension, torsion, etc.
2) Size of spring — small or large, long or short
3) Spring material
4) Size of spring material
5) Type of service — light, average, or severe
6) Stress range — low, average, or high

[*] Trade name of Soc. Anon. de Commentry Fourchambault et Decazeville, Paris, France.
[†] Trade name of John Chatillon & Sons.
[‡] Trade name of Elgin National Watch Company.
[**] Trade name of Hamilton Watch Company.

Copyright 2004, Industrial Press, Inc., New York, NY

7) Loading — static, dynamic, or shock

8) Operating temperature

9) Design of spring — spring index, sharp bends, hooks.

Consideration should also be given to other factors that affect spring life: corrosion, buckling, friction, and hydrogen embrittlement decrease spring life; manufacturing operations such as high-heat stress-equalizing, presetting, and shot-peening increase spring life.

Item 5, the type of service to which a spring is subjected, is a major factor in determining a safe working stress once consideration has been given to type of spring, kind and size of material, temperature, type of loading, and so on. The types of service are:

Light Service: This includes springs subjected to static loads or small deflections and seldom-used springs such as those in bomb fuses, projectiles, and safety devices. This service is for 1,000 to 10,000 deflections.

Average Service: This includes springs in general use in machine tools, mechanical products, and electrical components. Normal frequency of deflections not exceeding 18,000 per hour permit such springs to withstand 100,000 to 1,000,000 deflections.

Severe Service: This includes springs subjected to rapid deflections over long periods of time and to shock loading such as in pneumatic hammers, hydraulic controls and valves. This service is for 1,000,000 deflections, and above. Lowering the values 10 per cent permits 10,000,000 deflections.

Figs. 1 through 6 show curves that relate the three types of service conditions to allowable working stresses and wire sizes for compression and extension springs, and safe values are provided. Figs. 7 through 10 provide similar information for helical torsion springs. In each chart, the values obtained from the curves may be increased by 20 per cent (but not beyond the top curves on the charts if permanent set is to be avoided) for springs that are baked, and shot-peened, and compression springs that are pressed. Springs stressed slightly above the Light Service curves will take a permanent set.

A curvature correction factor is included in all curves, and is used in spring design calculations (see examples beginning page 321). The curves may be used for materials other than those designated in Figs. 1 through 10, by applying multiplication factors as given in Table 1.



Fig. 1. Allowable Working Stresses for Compression Springs — Hard Drawn Steel Wire[a]

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Allowable Working Stresses for Compression Springs — Music Wire[a]



Fig. 3. Allowable Working Stresses for Compression Springs — Oil-Tempered[a]



Fig. 4. Allowable Working Stresses for Compression Springs — Chrome-Silicon Alloy Steel Wire[a]

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Allowable Working Stresses for Compression Springs — Corrosion-Resisting Steel Wire[a]



Fig. 6. Allowable Working Stresses for Compression Springs — Chrome-Vanadium Alloy Steel Wire[a]



Fig. 7. Recommended Design Stresses in Bending for Helical Torsion Springs — Round Music Wire

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. Recommended Design Stresses in Bending for Helical Torsion Springs — Oil-Tempered MB Round Wire



Fig. 9. Recommended Design Stresses in Bending for Helical Torsion Springs — Stainless Steel Round Wire



Fig. 10. Recommended Design Stresses in Bending for Helical Torsion Springs — Chrome-Silicon Round Wire

[a] Although Figs. 1 through 6 are for compression springs, they may also be used for extension springs; for extension springs, *reduce* the values obtained from the curves by 10 to 15 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Correction Factors for Other Materials

Compression and Tension Springs			
Material	Factor	Material	Factor
Silicon-manganese	Multiply the values in the chromium-vanadium curves (Fig. 6) by 0.90	Stainless Steel, 316	Multiply the values in the corrosion-resisting steel curves (Fig. 5) by 0.90
Valve-spring quality wire	Use the values in the chromium-vanadium curves (Fig. 6)		
Stainless Steel, 304 and 420	Multiply the values in the corrosion-resisting steel curves (Fig. 5) by 0.95	Stainless Steel, 431 and 17-7PH	Multiply the values in the music wire curves (Fig. 2) by 0.90

Helical Torsion Springs			
Material	Factor[a]	Material	Factor[a]
Hard Drawn MB	0.70	Stainless Steel, 431	
Stainless Steel, 316		Up to 1/32 inch diameter	0.80
Up to 1/32 inch diameter	0.75	Over 1/32 to 1/16 inch	0.85
Over 1/32 to 3/16 inch	0.70	Over 1/16 to 1/8 inch	0.95
Over 3/16 to 1/4 inch	0.65	Over 1/8 inch	1.00
Over 1/4 inch	0.50	Chromium-Vanadium	
Stainless Steel, 17-7 PH		Up to 1/16 inch diameter	1.05
Up to 1/8 inch diameter	1.00	Over 1/16 inch	1.10
Over 1/8 to 3/16 inch	1.07	Phosphor Bronze	
Over 3/16 inch	1.12	Up to 1/8 inch diameter	0.45
Stainless Steel, 420		Over 1/8 inch	0.55
Up to 1/32 inch diameter	0.70	Beryllium Copper[b]	
Over 1/32 to 1/16 inch	0.75	Up to 1/32 inch diameter	0.55
Over 1/16 to 1/8 inch	0.80	Over 1/32 to 1/16 inch	0.60
Over 1/8 to 3/16 inch	0.90	Over 1/16 to 1/8 inch	0.70
Over 3/16 inch	1.00	Over 1/8 inch	0.80

[a] Multiply the values in the curves for oil-tempered MB grade ASTM A229 Type 1 steel (Fig. 8) by these factors to obtain required values.

[b] Hard drawn and heat treated after coiling.

For use with design stress curves shown in Figs. 2, 5, 6, and 8.

Endurance Limit for Spring Materials.— When a spring is deflected continually it will become "tired" and fail at a stress far below its elastic limit. This type of failure is called *fatigue failure* and usually occurs without warning. *Endurance limit* is the highest stress, or range of stress, in pounds per square inch that can be repeated indefinitely without failure of the spring. Usually ten million cycles of deflection is called "infinite life" and is satisfactory for determining this limit.

For severely worked springs of long life, such as those used in automobile or aircraft engines and in similar applications, it is best to determine the allowable working stresses by referring to the endurance limit curves seen in Fig. 11. These curves are based principally upon the range or difference between the stress caused by the first or initial load and the stress caused by the final load. Experience with springs designed to stresses within the limits of these curves indicates that they should have infinite or unlimited fatigue life. All values include Wahl curvature correction factor. The stress ranges shown may be increased 20 to 30 per cent for springs that have been properly heated, pressed to remove set, and then shot peened, provided that the increased values are lower than the torsional elastic limit by at least 10 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 11. Endurance Limit Curves for Compression Springs

Notes: For commercial spring materials with wire diameters up to ¼ inch except as noted. Stress ranges may be increased by approximately 30 per cent for properly heated, preset, shot-peened springs.

Materials preceeded by * are not ordinarily recommended for long continued service under severe operating conditions.

Working Stresses at Elevated Temperatures.— Since modulus of elasticity decreases with increase in temperature, springs used at high temperatures exert less load and have larger deflections under load than at room temperature. The torsional modulus of elasticity for steel may be 11,200,000 pounds per square inch at room temperature, but it will drop to 10,600,000 pounds per square inch at 400°F. and will be only 10,000,000 pounds per square inch at 600°F. Also, the elastic limit is reduced, thereby lowering the permissible working stress.

Design stresses should be as low as possible for all springs used at elevated temperatures. In addition, corrosive conditions that usually exist at high temperatures, especially with steam, may require the use of corrosion-resistant material. Table 2 shows the permissible elevated temperatures at which various spring materials may be operated, together with the maximum recommended working stresses at these temperatures. The loss in load at the temperatures shown is less than 5 per cent in 48 hours; however, if the temperatures listed are increased by 20 to 40 degrees, the loss of load may be nearer 10 per cent. Maximum stresses shown in the table are for compression and extension springs and may be increased

Copyright 2004, Industrial Press, Inc., New York, NY

by 75 per cent for torsion and flat springs. In using the data in Table 2 it should be noted that the values given are for materials in the heat-treated or spring temper condition.

Table 2. Recommended Maximum Working Temperatures and Corresponding Maximum Working Stresses for Springs

Spring Material	Max. Working Temp., °F	Max. Working Stress, psi	Spring Material	Max. Working Temp, °F	Max. Working Stress, psi
Brass Spring Wire	150	30,000	Permanickel[a]	500	50,000
Phosphor Bronze	225	35,000	Stainless Steel 18-8	550	55,000
Music Wire	250	75,000	Stainless Chromium 431	600	50,000
Beryllium-Copper	300	40,000	Inconel	700	50,000
Hard Drawn Steel Wire	325	50,000	High Speed Steel	775	70,000
Carbon Spring Steels	375	55,000	Inconel X	850	55,000
Alloy Spring Steels	400	65,000	Chromium-Molybdenum-Vanadium	900	55,000
Monel	425	40,000	Cobenium, Elgiloy	1000	75,000
K-Monel	450	45,000			

[a] Formerly called Z-Nickel, Type B.

Loss of load at temperatures shown is less than 5 per cent in 48 hours.

Spring Design Data

Spring Characteristics.— This section provides tables of spring characteristics, tables of principal formulas, and other information of a practical nature for designing the more commonly used types of springs.

Standard wire gages for springs: Information on wire gages is given in the section beginning on page 2519, and gages in decimals of an inch are given in the table on page 2520. It should be noted that the range in this table extends from Number 7/0 through Number 80. However, in spring design, the range most commonly used extends only from Gage Number 4/0 through Number 40. When selecting wire use Steel Wire Gage or Washburn and Moen gage for all carbon steels and alloy steels except music wire; use Brown & Sharpe gage for brass and phosphor bronze wire; use Birmingham gage for flat spring steels, and cold rolled strip; and use piano or music wire gage for music wire.

Spring index: The spring index is the ratio of the mean coil diameter of a spring to the wire diameter (D/d). This ratio is one of the most important considerations in spring design because the deflection, stress, number of coils, and selection of either annealed or tempered material depend to a considerable extent on this ratio. The best proportioned springs have an index of 7 through 9. Indexes of 4 through 7, and 9 through 16 are often used. Springs with values larger than 16 require tolerances wider than standard for manufacturing; those with values less than 5 are difficult to coil on automatic coiling machines.

Direction of helix: Unless functional requirements call for a definite hand, the helix of compression and extension springs should be specified as optional. When springs are designed to operate, one inside the other, the helices should be opposite hand to prevent intermeshing. For the same reason, a spring that is to operate freely over a threaded member should have a helix of opposite hand to that of the thread. When a spring is to engage with a screw or bolt, it should, of course, have the same helix as that of the thread.

Helical Compression Spring Design.— After selecting a suitable material and a safe stress value for a given spring, designers should next determine the type of end coil formation best suited for the particular application. Springs with unground ends are less expensive but they do not stand perfectly upright; if this requirement has to be met, closed ground ends are used. Helical compression springs with different types of ends are shown in Fig. 12.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 12. Types of Helical Compression Spring Ends

Spring design formulas: Table 3 gives formulas for compression spring dimensional characteristics, and Table 4 gives design formulas for compression and extension springs.

Curvature correction: In addition to the stress obtained from the formulas for load or deflection, there is a direct shearing stress and an increased stress on the inside of the section due to curvature. Therefore, the stress obtained by the usual formulas should be multiplied by a factor K taken from the curve in Fig. 13. The corrected stress thus obtained is used only for comparison with the allowable working stress (fatigue strength) curves to determine if it is a safe stress and should not be used in formulas for deflection. The curvature correction factor K is for compression and extension springs made from round wire. For square wire reduce the K value by approximately 4 per cent.

Design procedure: The limiting dimensions of a spring are often determined by the available space in the product or assembly in which it is to be used. The loads and deflections on a spring may also be known or can be estimated, but the wire size and number of coils are usually unknown. Design can be carried out with the aid of the tabular data that appears later in this section (see Table 5, which is a simple method, or by calculation alone using the formulas in Tables 3 and 4.

Example: A compression spring with closed and ground ends is to be made from ASTM A229 high carbon steel wire, as shown in Fig. 14. Determine the wire size and number of coils.

Method 1, using table: Referring to Table 5, starting on page 325, locate the spring outside diameter ($^{13}/_{16}$ inches, from Fig. 14) in the left-hand column. Note from the drawing that the spring load is 36 pounds. Move to the right in the table to the figure nearest this value, which is 41.7 pounds. This is somewhat above the required value but safe. Immediately above the load value, the deflection f is given, which in this instance is 0.1594 inch. This is the deflection of one coil under a load of 41.7 pounds with an uncorrected torsional stress S of 100,000 pounds per square inch for ASTM A229 oil-tempered MB steel. For other spring materials, see the footnotes to Table 5 on page 325. Moving vertically in Table 5 from the load entry, the wire diameter is found to be 0.0915 inch.

The remaining spring design calculations are completed as follows:

Step 1: The stress with a load of 36 pounds is obtained by proportion, as follows: The 36 pound load is 86.3 per cent of the 41.7 pound load; therefore, the stress S at 36 pounds = $0.863 \times 100{,}000 = 86{,}300$ pounds per square inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Formulas for Compression Springs

Feature	Type of End: Open or Plain (not ground)	Open or Plain (with ends ground)	Squared or Closed (not ground)	Closed and Ground
	Formula[a]			
Pitch (p)	$\frac{FL-d}{N}$	$\frac{FL}{TC}$	$\frac{FL-3d}{N}$	$\frac{FL-2d}{N}$
Solid Height (SH)	$(TC+1)d$	$TC \times d$	$(TC+\mathrm{I})d$	$TC \times d$
Number of Active Coils (N)	$N = TC = \frac{FL-d}{p}$	$N = TC-1 = \frac{FL}{p}-1$	$N = TC-2 = \frac{FL-3d}{p}$	$N = TC-2 = \frac{FL-2d}{p}$
Total Coils (TC)	$\frac{FL-d}{p}$	$\frac{FL}{p}$	$\frac{FL-3d}{p}+2$	$\frac{FL-2d}{p}+2$
Free Length (FL)	$(p \times TC)+d$	$p \times TC$	$(p \times N)+3d$	$(p \times N)+2d$

[a] The symbol notation is given on page 308.

Table 4. Formulas for Compression and Extension Springs

Feature	Formula[a, b]: Springs made from round wire	Springs made from square wire
Load, P Pounds	$P = \frac{0.393Sd^3}{D} = \frac{Gd^4F}{8ND^3}$	$P = \frac{0.416Sd^3}{D} = \frac{Gd^4F}{5.58ND^3}$
Stress, Torsional, S Pounds per square inch	$S = \frac{GdF}{\pi ND^2} = \frac{PD}{0.393d^3}$	$S = \frac{GdF}{2.32ND^2} = P\frac{D}{0.416d^3}$
Deflection, F Inch	$F = \frac{8PND^3}{Gd^4} = \frac{\pi SND^2}{Gd}$	$F = \frac{5.58PND^3}{Gd^4} = \frac{2.32SND^2}{Gd}$
Number of Active Coils, N	$N = \frac{Gd^4F}{8PD^3} = \frac{GdF}{\pi SD^2}$	$N = \frac{Gd^4F}{5.58PD^3} = \frac{GdF}{2.32SD^2}$
Wire Diameter, d Inch	$d = \frac{\pi SND^2}{GF} = \sqrt[3]{\frac{2.55PD}{S}}$	$d = \frac{2.32SND^2}{GF} = \sqrt[3]{\frac{PD}{0.416S}}$
Stress due to Initial Tension, S_{it}	$S_{it} = \frac{S}{P} \times IT$	$S_{it} = \frac{S}{P} \times IT$

[a] The symbol notation is given on page 308.
[b] Two formulas are given for each feature, and designers can use the one found to be appropriate for a given design. The end result from either of any two formulas is the same.

Step 2: The 86.3 per cent figure is also used to determine the deflection per coil f at 36 pounds load: $0.863 \times 0.1594 = 0.1375$ inch.

Step 3: The number of active coils $AC = \frac{F}{f} = \frac{1.25}{0.1375} = 9.1$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 13. Compression and Extension Spring-Stress Correction for Curvature[a]

[a] For springs made from round wire. For springs made from square wire, reduce the *K* factor values by approximately 4 per cent.



Fig. 14. Compression Spring Design Example

Step 4: Total Coils $TC = AC + 2$ (Table 3) $= 9 + 2 = 11$
Therefore, a quick answer is: 11 coils of 0.0915 inch diameter wire. However, the design procedure should be completed by carrying out these remaining steps:

Step 5: From Table 3, Solid Height $= SH = TC \times d = 11 \times 0.0915 \cong 1$ inch

Therefore, Total Deflection $= FL - SH = 1.5$ inches

Copyright 2004, Industrial Press, Inc., New York, NY

Step 6: Stress Solid $= \frac{86{,}300}{1.25} \times 1.5 = 103{,}500$ pounds per square inch

Step 7: Spring Index $= \frac{O.D.}{d} - 1 = \frac{0.8125}{0.0915} - 1 = 7.9$

Step 8: From Fig. 13, the curvature correction factor $K = 1.185$

Step 9: Total Stress at 36 pounds load = $S \times K = 86{,}300 \times 1.185 = 102{,}300$ pounds per square inch. This stress is below the 117,000 pounds per square inch permitted for 0.0915 inch wire shown on the middle curve in Fig. 3, so it is a safe working stress.

Step 10: Total Stress at Solid = $103{,}500 \times 1.185 = 122{,}800$ pounds per square inch. This stress is also safe, as it is below the 131,000 pounds per square inch shown on the top curve Fig. 3, and therefore the spring will not set.

Method 2, using formulas: The procedure for design using formulas is as follows (the design example is the same as in Method 1, and the spring is shown in Fig. 14):

Step 1: Select a safe stress S below the middle fatigue strength curve Fig. 8 for ASTM A229 steel wire, say 90,000 pounds per square inch. Assume a mean diameter D slightly below the 13/16-inch $O.D.$, say 0.7 inch. Note that the value of G is 11,200,000 pounds per square inch (Table 20).

Step 2: A trial wire diameter d and other values are found by formulas from Table 4 as follows:

$$d = \sqrt[3]{\frac{2.55PD}{S}} = \sqrt[3]{\frac{2.55 \times 36 \times 0.7}{90{,}000}}$$

$$= \sqrt[3]{0.000714} = 0.0894 \text{ inch}$$

Note: Table 21 can be used to avoid solving the cube root.

Step 3: From the table on page 2520, select the nearest wire gauge size, which is 0.0915 inch diameter. Using this value, the mean diameter $D = 13/16$ inch $- 0.0915 = 0.721$ inch.

Step 4: The stress $S = \frac{PD}{0.393d^3} = \frac{36 \times 0.721}{0.393 \times 0.0915^3} = 86{,}300$ lb/in^2

Step 5: The number of active coils is

$$N = \frac{GdF}{\pi SD^2} = \frac{11{,}200{,}000 \times 0.0915 \times 1.25}{3.1416 \times 86{,}300 \times 0.721^2} = 9.1 \text{ (say 9)}$$

The answer is the same as before, which is to use 11 total coils of 0.0915-inch diameter wire. The total coils, solid height, etc., are determined in the same manner as in Method 1.

Table of Spring Characteristics.— Table 5 gives characteristics for compression and extension springs made from ASTM A229 oil-tempered MB spring steel having a torsional modulus of elasticity G of 11,200,000 pounds per square inch, and an uncorrected torsional stress S of 100,000 pounds per square inch. The deflection f for one coil under a load P is shown in the body of the table. The method of using these data is explained in the problems for compression and extension spring design. The table may be used for other materials by applying factors to f. The factors are given in a footnote to the table.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Compression and Extension Spring Deflections[a]

Spring Outside Dia.		Wire Size or Washburn and Moen Gauge, and Decimal Equivalent[b]																		
																	19	18	17	16
		.010	.012	.014	.016	.018	.020	.022	.024	.026	.028	.030	.032	.034	.036	.038	.041	.0475	.054	.0625
Nom.	Dec.	Deflection f (inch) per coil, at Load P (pounds)[c]																		
7/64	.1094	.0277 .395	.0222 .697	.01824 1.130	.01529 1.722	.01302 2.51	.01121 3.52	.00974 4.79	.00853 6.36	.00751 8.28	.00664 10.59	.00589 13.35	… …	… …	… …	… …	… …	… …	… …	… …
1/8	.125	.0371 .342	.0299 .600	.0247 .971	.0208 1.475	.01784 2.14	.01548 2.99	.01353 4.06	.01192 5.37	.01058 6.97	.00943 8.89	.00844 11.16	.00758 13.83	.00683 16.95	.00617 20.6	… …	… …	… …	… …	… …
9/64	.1406	.0478 .301	.0387 .528	.0321 .852	.0272 1.291	.0234 1.868	.0204 2.61	.01794 3.53	.01590 4.65	.01417 6.02	.01271 7.66	.01144 9.58	.01034 11.84	.00937 14.47	.00852 17.51	.00777 21.0	… …	… …	… …	… …
5/32	.1563	.0600 .268	.0487 .470	.0406 .758	.0345 1.146	.0298 1.656	.0261 2.31	.0230 3.11	.0205 4.10	.01832 5.30	0.1649 6.72	.01491 8.39	.01354 10.35	.01234 12.62	.01128 15.23	.01033 18.22	.00909 23.5	… …	… …	… …
11/64	.1719	.0735 .243	.0598 .424	.0500 .683	.0426 1.031	.0369 1.488	.0324 2.07	.0287 2.79	.0256 3.67	.0230 4.73	.0208 5.99	.01883 7.47	.01716 9.19	.01569 11.19	.01439 13.48	.01324 16.09	.01172 21.8	.00914 33.8	… …	… …
3/16	.1875	.0884 .221	.0720 .387	.0603 .621	.0516 .938	.0448 1.351	.0394 1.876	.0349 2.53	.0313 3.32	.0281 4.27	.0255 5.40	.0232 6.73	.0212 8.27	.01944 10.05	.01788 12.09	.01650 14.41	.01468 18.47	.01157 30.07	.00926 46.3	… …
13/64	.2031	.1046 .203	.0854 .355	.0717 .570	.0614 .859	.0534 1.237	.0470 1.716	.0418 2.31	.0375 3.03	.0338 3.90	.0307 4.92	.0280 6.12	.0257 7.52	.0236 9.13	.0218 10.96	.0201 13.05	.01798 16.69	.01430 27.1	.01155 41.5	… …
7/32	.2188	… …	.1000 .328	.0841 .526	.0721 .793	.0628 1.140	.0555 1.580	.0494 2.13	.0444 2.79	.0401 3.58	.0365 4.52	.0333 5.61	.0306 6.88	.0282 8.35	.0260 10.02	.0241 11.92	.0216 15.22	.01733 24.6	.01411 37.5	.01096 61.3
15/64	.2344	… …	.1156 .305	.0974 .489	.0836 .736	.0730 1.058	.0645 1.465	.0575 1.969	.0518 2.58	.0469 3.21	.0427 4.18	.0391 5.19	.0359 6.35	.0331 7.70	.0307 9.23	.0285 10.97	.0256 13.99	.0206 22.5	.01690 34.3	.01326 55.8
1/4	.250	… …	… …	.1116 .457	.0960 .687	.0839 .987	.0742 1.366	.0663 1.834	.0597 2.40	.0541 3.08	.0494 3.88	.0453 4.82	.0417 5.90	.0385 7.14	.0357 8.56	.0332 10.17	.0299 12.95	.0242 20.8	.01996 31.6	.01578 51.1
9/32	.2813	… …	… …	.1432 .403	.1234 .606	.1080 .870	.0958 1.202	.0857 1.613	.0774 2.11	.0703 2.70	.0643 3.40	.0591 4.22	.0545 5.16	.0505 6.24	.0469 7.47	.0437 8.86	.0395 11.26	.0323 18.01	.0268 27.2	.0215 43.8
5/16	.3125	… …	… …	… …	.1541 .542	.1351 .778	.1200 1.074	.1076 1.440	.0973 1.881	.0886 2.41	.0811 3.03	.0746 3.75	.0690 4.58	.0640 5.54	.0596 6.63	.0556 7.85	.0504 9.97	.0415 15.89	.0347 23.9	.0281 38.3
11/32	.3438	… …	… …	… …	… …	.1633 .703	.1470 .970	.1321 1.300	.1196 1.697	.1090 2.17	.0999 2.73	.0921 3.38	.0852 4.12	.0792 4.98	.0733 5.95	.0690 7.05	.0627 8.94	.0518 14.21	.0436 21.3	.0355 34.1
3/8	.375	… …	… …	… …	… …	… …	.1768 .885	.1589 1.185	.1440 1.546	.1314 1.978	.1206 2.48	.1113 3.07	.1031 3.75	.0960 4.53	.0895 5.40	.0839 6.40	.0764 8.10	.0634 12.85	.0535 19.27	.0438 30.7

[a] This table is for ASTM A229 oil tempered spring steel with a torsional modulus G of 11,200,000 psi, and an uncorrected torsional stress of 100,000 psi. For other materials use the following factors: stainless steel, multiply f by 1.067; spring brass, multiply f by 2.24; phosphor bronze, multiply f by 1.867; Monel metal, multiply f by 1.244; beryllium copper, multiply f by 1.725; Inconel (non-magnetic), multiply f by 1.045.

[b] Round wire. For square wire, multiply f by 0.707, and p, by 1.2

[c] The upper figure is the deflection and the lower figure the load as read against each spring size. *Note:* Intermediate values can be obtained within reasonable accuracy by interpolation.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. *(Continued)* Compression and Extension Spring Deflections [a]

Spring Outside Dia.		Wire Size or Washburn and Moen Gauge, and Decimal Equivalent																	
									19	18	17	16	15	14	13	3/32	12	11	1/8
		.026	.028	.030	.032	.034	.036	.038	.041	.0475	.054	.0625	.072	.080	.0915	.0938	.1055	.1205	.125
Nom.	Dec.	Deflection *f* (inch) per coil, at Load *P* (pounds)																	
13/32	.4063	.1560	.1434	.1324	.1228	.1143	.1068	.1001	.0913	.0760	.0645	.0531	.0436	.0373	.0304	.0292	.0241	…	…
		1.815	2.28	2.82	3.44	4.15	4.95	5.85	7.41	11.73	17.56	27.9	43.9	61.6	95.6	103.7	153.3	…	…
7/16	.4375	.1827	.1680	.1553	.1441	.1343	.1256	.1178	.1075	.0898	.0764	.0631	.0521	.0448	.0367	.0353	.0293	.0234	.0219
		1.678	2.11	2.60	3.17	3.82	4.56	5.39	6.82	10.79	16.13	25.6	40.1	56.3	86.9	94.3	138.9	217.	245.
15/32	.4688	.212	.1947	.1800	.1673	.1560	.1459	.1370	.1252	.1048	.0894	.0741	.0614	.0530	.0437	.0420	.0351	.0282	.0265
		1.559	1.956	2.42	2.94	3.55	4.23	5.00	6.33	9.99	14.91	23.6	37.0	51.7	79.7	86.4	126.9	197.3	223.
1/2	.500	.243	.223	.207	.1920	.1792	.1678	.1575	.1441	.1209	.1033	.0859	.0714	.0619	.0512	.0494	.0414	.0335	.0316
		1.456	1.826	2.26	2.75	3.31	3.95	4.67	5.90	9.30	13.87	21.9	34.3	47.9	73.6	80.0	116.9	181.1	205.
17/32	.5313	.276	.254	.235	.219	.204	.1911	.1796	.1645	.1382	.1183	.0987	.0822	.0714	.0593	.0572	.0482	.0393	.0371
		1.366	1.713	2.12	2.58	3.10	3.70	4.37	5.52	8.70	12.96	20.5	31.9	44.6	68.4	74.1	108.3	167.3	188.8
9/16	.5625	…	.286	.265	.247	.230	.216	.203	.1861	.1566	.1343	.1122	.0937	.0816	.0680	.0657	.0555	.0455	.0430
		…	1.613	1.991	2.42	2.92	3.48	4.11	5.19	8.18	12.16	19.17	29.9	41.7	63.9	69.1	100.9	155.5	175.3
19/32	.5938	…	…	.297	.277	.259	.242	.228	.209	.1762	.1514	.1267	.1061	.0926	.0774	.0748	.0634	.0522	.0493
		…	…	1.880	2.29	2.76	3.28	3.88	4.90	7.71	11.46	18.04	28.1	39.1	60.0	64.8	94.4	145.2	163.6
5/8	.625	…	…	.331	.308	.288	.270	.254	.233	.1969	.1693	.1420	.1191	.1041	.0873	.0844	.0718	.0593	.0561
		…	…	1.782	2.17	2.61	3.11	3.67	4.63	7.29	10.83	17.04	26.5	36.9	56.4	61.0	88.7	136.2	153.4
21/32	.6563	…	…	…	.342	.320	.300	.282	.259	.219	.1884	.1582	.1330	.1164	.0978	.0946	.0807	.0668	.0634
		…	…	…	2.06	2.48	2.95	3.49	4.40	6.92	10.27	16.14	25.1	34.9	53.3	57.6	83.7	128.3	144.3
11/16	.6875	…	…	…	…	.352	.331	.311	.286	.242	.208	.1753	.1476	.1294	.1089	.1054	.0901	.0748	.0710
		…	…	…	…	2.36	2.81	3.32	4.19	6.58	9.76	15.34	23.8	33.1	50.5	54.6	79.2	121.2	136.3
23/32	.7188	…	…	…	…	…	.363	.342	.314	.266	.230	.1933	.1630	.1431	.1206	.1168	.1000	.0833	.0791
		…	…	…	…	…	2.68	3.17	3.99	6.27	9.31	14.61	22.7	31.5	48.0	51.9	75.2	114.9	129.2
3/4	.750	…	…	…	…	…	…	.374	.344	.291	.252	.212	.1791	.1574	.1329	.1288	.1105	.0923	.0877
		…	…	…	…	…	…	3.03	3.82	5.99	8.89	13.94	21.6	30.0	45.7	49.4	71.5	109.2	122.7
25/32	.7813	…	…	…	…	…	…	…	.375	.318	.275	.232	.1960	.1724	.1459	.1413	.1214	.1017	.0967
		…	…	…	…	…	…	…	3.66	5.74	8.50	13.34	20.7	28.7	43.6	47.1	68.2	104.0	116.9
13/16	.8125	…	…	…	…	…	…	…	.407	.346	.299	.253	.214	.1881	.1594	.1545	.1329	.1115	.1061
		…	…	…	…	…	…	…	3.51	5.50	8.15	12.78	19.80	27.5	41.7	45.1	65.2	99.3	111.5

[a] This table is for ASTM A229 oil tempered spring steel with a torsional modulus *G* of 11,200,000 psi, and an uncorrected torsional stress of 100,000 psi. For other materials, and other important footnotes, see page 325.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. *(Continued)* Compression and Extension Spring Deflections [a]

Spring Outside Dia.		Wire Size or Washburn and Moen Gauge, and Decimal Equivalent																
		15	14	13	3/32	12	11	1/8	10	9	5/32	8	7	3/16	6	5	7/32	4
		.072	.080	.0915	.0938	.1055	.1205	.125	.135	.1483	.1563	.162	.177	.1875	.192	.207	.2188	.2253
Nom.	Dec.	Deflection *f* (inch) per coil, at Load *P* (pounds)																
7/8	.875	.251	.222	.1882	.1825	.1574	.1325	.1262	.1138	.0999	.0928	.0880	.0772	.0707	.0682	.0605	.0552	.0526
		18.26	25.3	39.4	41.5	59.9	91.1	102.3	130.5	176.3	209.	234.	312.	377.	407.	521.	626.	691.
29/32	.9063	.271	.239	.204	.1974	.1705	.1438	.1370	.1236	.1087	.1010	.0959	.0843	.0772	.0746	.0663	.0606	.0577
		17.57	24.3	36.9	39.9	57.6	87.5	98.2	125.2	169.0	199.9	224.	299.	360.	389.	498.	598.	660.
15/16	.9375	.292	.258	.219	.213	.1841	.1554	.1479	.1338	.1178	.1096	.1041	.0917	.0842	.0812	.0723	.0662	.0632
		16.94	23.5	35.6	38.4	55.4	84.1	94.4	120.4	162.3	191.9	215.	286.	345.	373.	477.	572.	631.
31/32	.9688	.313	.277	.236	.229	.1982	.1675	.1598	.1445	.1273	.1183	.1127	.0994	.0913	.0882	.0786	.0721	.0688
		16.35	22.6	34.3	37.0	53.4	81.0	90.9	115.9	156.1	184.5	207.	275.	332.	358.	457.	548.	604.
1	1.000	.336	.297	.253	.246	.213	.1801	.1718	.1555	.1372	.1278	.1216	.1074	.0986	.0954	.0852	.0783	.0747
		15.80	21.9	33.1	35.8	51.5	78.1	87.6	111.7	150.4	177.6	198.8	264.	319.	344.	439.	526.	580.
1 1/32	1.031	.359	.317	.271	.263	.228	.1931	.1843	.1669	.1474	.1374	.1308	.1157	.1065	.1029	.0921	.0845	.0809
		15.28	21.1	32.0	34.6	49.8	75.5	84.6	107.8	145.1	171.3	191.6	255.	307.	331.	423.	506.	557.
1 1/16	1.063	.382	.338	.289	.281	.244	.207	.1972	.1788	.1580	.1474	.1404	.1243	.1145	.1107	.0993	.0913	.0873
		14.80	20.5	31.0	33.5	48.2	73.0	81.8	104.2	140.1	165.4	185.0	246.	296.	319.	407.	487.	537.
1 1/32	1.094	.407	.360	.308	.299	.260	.221	.211	.1910	.1691	.1578	.1503	.1332	.1229	.1188	.1066	.0982	.0939
		14.34	19.83	30.0	32.4	46.7	70.6	79.2	100.8	135.5	159.9	178.8	238.	286.	308.	393.	470.	517.
1 1/8	1.125	.432	.383	.328	.318	.277	.235	.224	.204	.1804	.1685	.1604	.1424	.1315	.1272	.1142	.1053	.1008
		13.92	19.24	29.1	31.4	45.2	68.4	76.7	97.6	131.2	154.7	173.0	230.	276.	298.	379.	454.	499.
1 3/16	1.188	.485	.431	.368	.358	.311	.265	.254	.231	.204	.1908	.1812	.1620	.1496	.1448	.1303	.1203	.1153
		13.14	18.15	27.5	29.6	42.6	64.4	72.1	91.7	123.3	145.4	162.4	215.	259.	279.	355.	424.	467.
1 1/4	1.250	.541	.480	.412	.400	.349	.297	.284	.258	.230	.215	.205	.1824	.1690	.1635	.1474	.1363	.1308
		12.44	17.19	26.0	28.0	40.3	60.8	68.2	86.6	116.2	137.0	153.1	203.	244.	263.	334.	399.	438.
1 5/16	1.313	.600	.533	.457	.444	.387	.331	.317	.288	.256	.240	.229	.205	.1894	.1836	.1657	.1535	.1472
		11.81	16.31	24.6	26.6	38.2	57.7	64.6	82.0	110.1	129.7	144.7	191.6	230.	248.	315.	376.	413.
1 3/8	1.375	.662	.588	.506	.491	.429	.367	.351	.320	.285	.267	.255	.227	.211	.204	.1848	.1713	.1650
		11.25	15.53	23.4	25.3	36.3	54.8	61.4	77.9	104.4	123.0	137.3	181.7	218.	235.	298.	356.	391
1 7/16	1.438	.727	.647	.556	.540	.472	.404	.387	.353	.314	.295	.282	.252	.234	.227	.205	.1905	.1829
		10.73	14.81	22.3	24.1	34.6	52.2	58.4	74.1	99.4	117.0	130.6	172.6	207.	223.	283.	337.	371.

[a] This table is for ASTM A229 oil tempered spring steel with a torsional modulus *G* of 11,200,000 psi, and an uncorrected torsional stress of 100,000 psi. For other materials, and other important footnotes, see page 325.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **Compression and Extension Spring Deflections** [a]

Spring Outside Dia.		Wire Size or Washburn and Moen Gauge, and Decimal Equivalent																	
		11	1/8	10	9	5/32	8	7	3/16	6	5	7/32	4	3	1/4	2	9/32	0	5/16
		.1205	.125	.135	.1483	.1563	.162	.177	.1875	.192	.207	.2188	.2253	.2437	.250	.2625	.2813	.3065	.3125
Nom.	Dec.	Deflection f (inch) per coil, at Load P (pounds)																	
1 1/2	1.500	.443	.424	.387	.350	.324	.310	.277	.258	.250	.227	.210	.202	.1815	.1754	.1612	.1482	.1305	.1267
		49.8	55.8	70.8	94.8	111.5	124.5	164.6	197.1	213.	269.	321.	352.	452.	499.	574.	717.	947.	1008.
1 5/8	1.625	.527	.505	.461	.413	.387	.370	.332	.309	.300	.273	.254	.244	.220	.212	.1986	.1801	.1592	.1547
		45.7	51.1	64.8	86.7	102.0	113.9	150.3	180.0	193.9	246.	292.	321.	411.	446.	521.	650.	858.	912.
1 3/4	1.750	.619	.593	.542	.485	.456	.437	.392	.366	.355	.323	.301	.290	.261	.253	.237	.215	.1908	.1856
		42.2	47.2	59.8	80.0	94.0	104.9	138.5	165.6	178.4	226.	269.	295.	377.	409.	477.	595.	783.	833.
1 7/8	1.875	.717	.687	.629	.564	.530	.508	.457	.426	.414	.377	.351	.339	.306	.296	.278	.253	.225	.219
		39.2	43.8	55.5	74.2	87.2	97.3	128.2	153.4	165.1	209.	248.	272.	348.	378.	440.	548.	721.	767.
1 15/16	1.938	.769	.738	.676	.605	.569	.546	.492	.458	.446	.405	.379	.365	.331	.320	.300	.273	.243	.237
		37.8	42.3	53.6	71.6	84.2	93.8	123.6	147.9	159.2	201.	239.	262.	335.	364.	425.	528.	693.	737.
2	2.000	.823	.789	.723	.649	.610	.585	.527	.492	.478	.436	.407	.392	.355	.344	.323	.295	.263	.256
		36.6	40.9	51.8	69.2	81.3	90.6	119.4	142.8	153.7	194.3	231.	253.	324.	351.	409.	509.	668.	710.
2 1/16	2.063	.878	.843	.768	.693	.652	.626	.564	.526	.512	.467	.436	.421	.381	.369	.346	.316	.282	.275
		35.4	39.6	50.1	66.9	78.7	87.6	115.4	138.1	148.5	187.7	223.	245.	312.	339.	395.	491.	644.	685.
2 1/8	2.125	.936	.898	.823	.739	.696	.667	.602	.562	.546	.499	.466	.449	.407	.395	.371	.339	.303	.295
		34.3	38.3	48.5	64.8	76.1	84.9	111.8	133.6	143.8	181.6	216.	236.	302.	327.	381.	474.	622.	661.
2 3/16	2.188	.995	.955	.876	.786	.740	.711	.641	.598	.582	.532	.497	.479	.435	.421	.396	.362	.324	.316
		33.3	37.2	47.1	62.8	73.8	82.2	108.3	129.5	139.2	175.8	209.	229.	292.	317.	369.	459.	601.	639.
2 1/4	2.250	1.056	1.013	.930	.835	.787	.755	.681	.637	.619	.566	.529	.511	.463	.449	.423	.387	.346	.337
		32.3	36.1	45.7	60.9	71.6	79.8	105.7	125.5	135.0	170.5	202.	222.	283.	307.	357.	444.	582.	618.
2 5/16	2.313	1.119	1.074	.986	.886	.834	.801	.723	.676	.657	.601	.562	.542	.493	.478	.449	.411	.368	.359
		31.4	35.1	44.4	59.2	69.5	77.5	101.9	121.8	131.0	165.4	196.3	215.	275.	298.	347.	430.	564.	599.
2 3/8	2.375	1.184	1.136	1.043	.938	.884	.848	.763	.716	.696	.637	.596	.576	.523	.507	.477	.437	.392	.382
		30.5	34.1	43.1	57.5	67.6	75.3	99.1	118.3	127.3	160.7	190.7	209.	267.	289.	336.	417.	547.	581.
2 7/16	2.438	…	1.201	1.102	.991	.934	.897	.810	.757	.737	.674	.631	.609	.554	.537	.506	.464	.416	.405
		…	33.2	42.0	56.0	65.7	73.2	96.3	115.1	123.7	156.1	185.3	203.	259.	281.	327.	405.	531.	564.
2 1/2	2.500	…	1.266	1.162	1.046	.986	.946	.855	.800	.778	.713	.667	.644	.586	.568	.536	.491	.441	.430
		…	32.3	40.9	54.5	64.0	71.3	93.7	111.6	120.4	151.9	180.2	197.5	252.	273.	317.	394.	516.	548.

[a] This table is for ASTM A229 oil tempered spring steel with a torsional modulus G of 11,200,000 psi, and an uncorrected torsional stress of 100,000 psi. For other materials, and other important footnotes, see page 325.

Copyright 2004, Industrial Press, Inc., New York, NY

Extension Springs.— About 10 per cent of all springs made by many companies are of this type, and they frequently cause trouble because insufficient consideration is given to stress due to initial tension, stress and deflection of hooks, special manufacturing methods, secondary operations and overstretching at assembly. Fig. 15 shows types of ends used on these springs.



Fig. 15. Types of Helical Extension Spring Ends

Initial tension: In the spring industry, the term "Initial tension" is used to define a force or load, measurable in pounds or ounces, which presses the coils of a close wound extension spring against one another. This force must be overcome before the coils of a spring begin to open up.

Initial tension is wound into extension springs by bending each coil as it is wound away from its normal plane, thereby producing a slight twist in the wire which causes the coil to spring back tightly against the adjacent coil. Initial tension can be wound into cold-coiled

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 16. Permissible Torsional Stress Caused by Initial Tension in Coiled Extension Springs for Different Spring Indexes

extension springs only. Hot-wound springs and springs made from annealed steel are hardened and tempered after coiling, and therefore initial tension cannot be produced. It is possible to make a spring having initial tension only when a high tensile strength, obtained by cold drawing or by heat-treatment, is possessed by the material as it is being wound into springs. Materials that possess the required characteristics for the manufacture of such springs include hard-drawn wire, music wire, pre-tempered wire, 18-8 stainless steel, phosphor-bronze, and many of the hard-drawn copper-nickel, and nonferrous alloys. Permissible torsional stresses resulting from initial tension for different spring indexes are shown in Fig. 16.

Hook failure: The great majority of breakages in extension springs occurs in the hooks. Hooks are subjected to both bending and torsional stresses and have higher stresses than the coils in the spring.

Stresses in regular hooks: The calculations for the stresses in hooks are quite complicated and lengthy. Also, the radii of the bends are difficult to determine and frequently vary between specifications and actual production samples. However, regular hooks are more

Copyright 2004, Industrial Press, Inc., New York, NY

highly stressed than the coils in the body and are subjected to a bending stress at section B (see Table 6.) The bending stress S_b at section B should be compared with allowable stresses for torsion springs and with the elastic limit of the material in tension (See Figs. 7 through 10.)

Stresses in cross over hooks: Results of tests on springs having a normal average index show that the cross over hooks last longer than regular hooks. These results may not occur on springs of small index or if the cross over bend is made too sharply.

In as much as both types of hooks have the same bending stress, it would appear that the fatigue life would be the same. However, the large bend radius of the regular hooks causes some torsional stresses to coincide with the bending stresses, thus explaining the earlier breakages. If sharper bends were made on the regular hooks, the life should then be the same as for cross over hooks.

Table 6. Formula for Bending Stress at Section B

Type of Hook	Stress in Bending
 Regular Hook  Cross-over Hook	$S_b = \frac{5PD^2}{\text{I.D.}d^3}$

Stresses in half hooks: The formulas for regular hooks can also be used for half hooks, because the smaller bend radius allows for the increase in stress. It will therefore be observed that half hooks have the same stress in bending as regular hooks.

Frequently overlooked facts by many designers are that one full hook deflects an amount equal to one half a coil and each half hook deflects an amount equal to one tenth of a coil. Allowances for these deflections should be made when designing springs. Thus, an extension spring, with regular full hooks and having 10 coils, will have a deflection equal to 11 coils, or 10 per cent more than the calculated deflection.

Extension Spring Design.— The available space in a product or assembly usually determines the limiting dimensions of a spring, but the wire size, number of coils, and initial tension are often unknown.

Example: An extension spring is to be made from spring steel ASTM A229, with regular hooks as shown in Fig. 17. Calculate the wire size, number of coils and initial tension.

Note: Allow about 20 to 25 per cent of the 9 pound load for initial tension, say 2 pounds, and then design for a 7 pound load (not 9 pounds) at $\frac{5}{8}$ inch deflection. Also use lower stresses than for a compression spring to allow for overstretching during assembly and to obtain a safe stress on the hooks. Proceed as for compression springs, but locate a load in the tables somewhat higher than the 9 pound load.

Method 1, using table: From Table 5 locate $\frac{3}{4}$ inch outside diameter in the left column and move to the right to locate a load P of 13.94 pounds. A deflection f of 0.212 inch appears above this figure. Moving vertically from this position to the top of the column a suitable wire diameter of 0.0625 inch is found.

The remaining design calculations are completed as follows:

Step 1: The stress with a load of 7 pounds is obtained as follows:
The 7 pound load is 50.2 per cent of the 13.94 pound load. Therefore, the stress S at 7 pounds = 0.502 per cent × 100,000 = 50,200 pounds per square inch.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 17. Extension Spring Design Example

Step 2: The 50.2 per cent figure is also used to determine the deflection per coil *f*: 0.502 per cent × 0.212 = 0.1062 inch.

Step 3: The number of active coils. (say 6)

$$AC = \frac{F}{f} = \frac{0.625}{0.1062} = 5.86$$

This result should be reduced by 1 to allow for deflection of 2 hooks (see notes 1 and 2 that follow these calculations.) Therefore, a quick answer is: 5 coils of 0.0625 inch diameter wire. However, the design procedure should be completed by carrying out the following steps:

Step 4: The body length = $(TC + 1) \times d = (5 + 1) \times 0.0625 = \frac{3}{8}$ inch.

Step 5: The length from the body to inside hook

$$= \frac{FL - \text{Body}}{2} = \frac{1.4375 - 0.375}{2} = 0.531 \text{ inch}$$

$$\text{Percentage of I.D.} = \frac{0.531}{\text{I.D.}} = \frac{0.531}{0.625} = 85 \text{ per cent}$$

This length is satisfactory, see Note 3 following this proceedure.

Step 6:

$$\text{The spring index} = \frac{\text{O.D.}}{d} - 1 = \frac{0.75}{0.0625} - 1 = 11$$

Step 7: The initial tension stress is

$$S_{it} = \frac{S \times IT}{P} = \frac{50{,}200 \times 2}{7} = 14{,}340 \text{ pounds per square inch}$$

This stress is satisfactory, as checked against curve in Fig. 16.

Step 8: The curvature correction factor $K = 1.12$ (Fig. 13).

Step 9: The total stress = (50,200 + 14,340) × 1.12 = 72.285 pounds per square inch

This result is less than 106,250 pounds per square inch permitted by the middle curve for 0.0625 inch wire in Fig. 3 and therefore is a safe working stress that permits some additional deflection that is usually necessary for assembly purposes.

Copyright 2004, Industrial Press, Inc., New York, NY

Step 10: The large majority of hook breakage is due to high stress in bending and should be checked as follows:

From Table 6, stress on hook in bending is:

$$S_b = \frac{5PD^2}{\text{I.D.}d^3} = \frac{5 \times 9 \times 0.6875^2}{0.625 \times 0.0625^3} = 139{,}200 \text{ pounds per square inch}$$

This result is less than the top curve value, Fig. 8, for 0.0625 inch diameter wire, and is therefore safe. Also see Note 5 that follows.

Notes: The following points should be noted when designing extension springs:

1) All coils are active and thus $AC = TC$.

2) Each full hook deflection is approximately equal to ½ coil. Therefore for 2 hooks, reduce the total coils by 1. (Each half hook deflection is nearly equal to 1/10 of a coil.)

3) The distance from the body to the inside of a regular full hook equals 75 to 85 per cent (90 per cent maximum) of the I.D. For a cross over center hook, this distance equals the I.D.

4) Some initial tension should usually be used to hold the spring together. Try not to exceed the maximum curve shown on Fig. 16. Without initial tension, a long spring with many coils will have a different length in the horizontal position than it will when hung vertically.

5) The hooks are stressed in bending, therefore their stress should be less than the maximum bending stress as used for torsion springs — use top fatigue strength curves Figs. 7 through 10.

Method 2, using formulas: The sequence of steps for designing extension springs by formulas is similar to that for compression springs. The formulas for this method are given in Table 3.

Tolerances for Compression and Extension Springs.— Tolerances for coil diameter, free length, squareness, load, and the angle between loop planes for compression and extension springs are given in Tables 7 through 12. To meet the requirements of load, rate, free length, and solid height, it is necessary to vary the number of coils for compression springs by ± 5 per cent. For extension springs, the tolerances on the numbers of coils are: for 3 to 5 coils, ± 20 per cent; for 6 to 8 coils, ± 30 per cent; for 9 to 12 coils, ± 40 per cent. For each additional coil, a further 1½ per cent tolerance is added to the extension spring values. Closer tolerances on the number of coils for either type of spring lead to the need for trimming after coiling, and manufacturing time and cost are increased. Fig. 18 shows deviations allowed on the ends of extension springs, and variations in end alignments.

Table 7. Compression and Extension Spring Coil Diameter Tolerances

Wire Diameter, Inch	Spring Index						
	4	6	8	10	12	14	16
	Tolerance, ± inch						
0.015	0.002	0.002	0.003	0.004	0.005	0.006	0.007
0.023	0.002	0.003	0.004	0.006	0.007	0.008	0.010
0.035	0.002	0.004	0.006	0.007	0.009	0.011	0.013
0.051	0.003	0.005	0.007	0.010	0.012	0.015	0.017
0.076	0.004	0.007	0.010	0.013	0.016	0.019	0.022
0.114	0.006	0.009	0.013	0.018	0.021	0.025	0.029
0.171	0.008	0.012	0.017	0.023	0.028	0.033	0.038
0.250	0.011	0.015	0.021	0.028	0.035	0.042	0.049
0.375	0.016	0.020	0.026	0.037	0.046	0.054	0.064
0.500	0.021	0.030	0.040	0.062	0.080	0.100	0.125

Courtesy of the Spring Manufacturers Institute

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 18. Maximum Deviations Allowed on Ends and Variation in Alignment of Ends (Loops) for Extension Springs

Table 8. Compression Spring Normal Free-Length Tolerances, Squared and Ground Ends

Number of Active Coils per Inch	Spring Index						
	4	6	8	10	12	14	16
	Tolerance, ± Inch per Inch of Free Length[a]						
0.5	0.010	0.011	0.012	0.013	0.015	0.016	0.016
1	0.011	0.013	0.015	0.016	0.017	0.018	0.019
2	0.013	0.015	0.017	0.019	0.020	0.022	0.023
4	0.016	0.018	0.021	0.023	0.024	0.026	0.027
8	0.019	0.022	0.024	0.026	0.028	0.030	0.032
12	0.021	0.024	0.027	0.030	0.032	0.034	0.036
16	0.022	0.026	0.029	0.032	0.034	0.036	0.038
20	0.023	0.027	0.031	0.034	0.036	0.038	0.040

[a] For springs less than 0.5 inch long, use the tolerances for 0.5 inch long springs. For springs with unground closed ends, multiply the tolerances by 1.7.

Courtesy of the Spring Manufacturers Institute

Table 9. Extension Spring Normal Free-Length and End Tolerances

Free-Length Tolerances		End Tolerances		Free-Length Tolerances		End Tolerances	
Spring Free Length (inch)	Tolerance (inch)	Total Number of Coils	Angle Between Loop Planes	Spring Free Length (inch)	Tolerance (inch)	Total Number of Coils	Angle Between Loop Planes
Up to 0.5	±0.020			Over 4.0 to 8.0	±0.093	13 to 16	±60°
Over 0.5 to 1.0	±0.030	3 to 6	±25°	Over 8.0 to 16.0	±0.156	Over 16	Random
Over 1.0 to 2.0	±0.040	7 to 9	±35°	Over 16.0 to 24.0	±0.218		
Over 2.0 to 4.0	±0.060	10 to 12	±45°				

Courtesy of the Spring Manufacturers Institute

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Compression Spring Squareness Tolerances

Slenderness Ratio *FL/D*[a]	Spring Index						
	4	6	8	10	12	14	16
	Squareness Tolerances (± degrees)						
0.5	3.0	3.0	3.5	3.5	3.5	3.5	4.0
1.0	2.5	3.0	3.0	3.0	3.0	3.5	3.5
1.5	2.5	2.5	2.5	3.0	3.0	3.0	3.0
2.0	2.5	2.5	2.5	2.5	3.0	3.0	3.0
3.0	2.0	2.5	2.5	2.5	2.5	2.5	3.0
4.0	2.0	2.0	2.5	2.5	2.5	2.5	2.5
6.0	2.0	2.0	2.0	2.5	2.5	2.5	2.5
8.0	2.0	2.0	2.0	2.0	2.5	2.5	2.5
10.0	2.0	2.0	2.0	2.0	2.0	2.5	2.5
12.0	2.0	2.0	2.0	2.0	2.0	2.0	2.5

[a] Slenderness Ratio = $FL \div D$

Springs with closed and ground ends, in the free position. Squareness tolerances closer than those shown require special process techniques which increase cost. Springs made from fine wire sizes, and with high spring indices, irregular shapes or long free lengths, require special attention in determining appropriate tolerance and feasibility of grinding ends.

Table 11. Compression Spring Normal Load Tolerances

Length Tolerance, ± inch	Deflection (inch)[a]													
	0.05	0.10	0.15	0.20	0.25	0.30	0.40	0.50	0.75	1.00	1.50	2.00	3.00	4.00	6.00
	Tolerance, ± Per Cent of Load														
0.005	12	7	6	5	…	…	…	…	…	…	…	…	…	…	…
0.010	…	12	8.5	7	6.5	5.5	5	…	…	…	…	…	…	…	…
0.020	…	22	15.5	12	10	8.5	7	6	5	…	…	…	…	…	…
0.030	…	…	22	17	14	12	9.5	8	6	5	…	…	…	…	…
0.040	…	…	…	22	18	15.5	12	10	7.5	6	5	…	…	…	…
0.050	…	…	…	…	22	19	14.5	12	9	7	5.5	…	…	…	…
0.060	…	…	…	…	25	22	17	14	10	8	6	5	…	…	…
0.070	…	…	…	…	…	25	19.5	16	11	9	6.5	5.5	…	…	…
0.080	…	…	…	…	…	…	22	18	12.5	10	7.5	6	5	…	…
0.090	…	…	…	…	…	…	25	20	14	11	8	6	5	…	…
0.100	…	…	…	…	…	…	…	22	15.5	12	8.5	7	5.5	…	…
0.200	…	…	…	…	…	…	…	…	…	22	15.5	12	8.5	7	5.5
0.300	…	…	…	…	…	…	…	…	…	…	22	17	12	9.5	7
0.400	…	…	…	…	…	…	…	…	…	…	…	21	15	12	8.5
0.500	…	…	…	…	…	…	…	…	…	…	…	25	18.5	14.5	10.5

[a] From free length to loaded position.

Torsion Spring Design.— Fig. 19 shows the types of ends most commonly used on torsion springs. To produce them requires only limited tooling. The straight torsion end is the least expensive and should be used whenever possible. After determining the spring load or torque required and selecting the end formations, the designer usually estimates suitable space or size limitations. However, the space should be considered approximate until the wire size and number of coils have been determined. The wire size is dependent principally upon the torque. Design data can be devoloped with the aid of the tabular data, which is a simple method, or by calculation alone, as shown in the following sections. Many other factors affecting the design and operation of torsion springs are also covered in the section, *Torsion Spring Design Recommendations* on page 341. Design formulas are shown in Table 13.

Curvature correction: In addition to the stress obtained from the formulas for load or deflection, there is a direct shearing stress on the inside of the section due to curvature. Therefore, the stress obtained by the usual formulas should be multiplied by the factor *K*

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Extension Spring Normal Load Tolerances

Spring Index	$\frac{FL}{F}$	Wire Diameter (inch)										
		0.015	0.022	0.032	0.044	0.062	0.092	0.125	0.187	0.250	0.375	0.437
		Tolerance, ± Per Cent of Load										
4	12	20.0	18.5	17.6	16.9	16.2	15.5	15.0	14.3	13.8	13.0	12.6
	8	18.5	17.5	16.7	15.8	15.0	14.5	14.0	13.2	12.5	11.5	11.0
	6	16.8	16.1	15.5	14.7	13.8	13.2	12.7	11.8	11.2	9.9	9.4
	4.5	15.0	14.7	14.1	13.5	12.6	12.0	11.5	10.3	9.7	8.4	7.9
	2.5	13.1	12.4	12.1	11.8	10.6	10.0	9.1	8.5	8.0	6.8	6.2
	1.5	10.2	9.9	9.3	8.9	8.0	7.5	7.0	6.5	6.1	5.3	4.8
	0.5	6.2	5.4	4.8	4.6	4.3	4.1	4.0	3.8	3.6	3.3	3.2
6	12	17.0	15.5	14.6	14.1	13.5	13.1	12.7	12.0	11.5	11.2	10.7
	8	16.2	14.7	13.9	13.4	12.6	12.2	11.7	11.0	10.5	10.0	9.5
	6	15.2	14.0	12.9	12.3	11.6	10.9	10.7	10.0	9.4	8.8	8.3
	4.5	13.7	12.4	11.5	11.0	10.5	10.0	9.6	9.0	8.3	7.6	7.1
	2.5	11.9	10.8	10.2	9.8	9.4	9.0	8.5	7.9	7.2	6.2	6.0
	1.5	9.9	9.0	8.3	7.7	7.3	7.0	6.7	6.4	6.0	4.9	4.7
	0.5	6.3	5.5	4.9	4.7	4.5	4.3	4.1	4.0	3.7	3.5	3.4
8	12	15.8	14.3	13.1	13.0	12.1	12.0	11.5	10.8	10.2	10.0	9.5
	8	15.0	13.7	12.5	12.1	11.4	11.0	10.6	10.1	9.4	9.0	8.6
	6	14.2	13.0	11.7	11.2	10.6	10.0	9.7	9.3	8.6	8.1	7.6
	4.5	12.8	11.7	10.7	10.1	9.7	9.0	8.7	8.3	7.8	7.2	6.6
	2.5	11.2	10.2	9.5	8.8	8.3	7.9	7.7	7.4	6.9	6.1	5.6
	1.5	9.5	8.6	7.8	7.1	6.9	6.7	6.5	6.2	5.8	4.9	4.5
	0.5	6.3	5.6	5.0	4.8	4.5	4.4	4.2	4.1	3.9	3.6	3.5
10	12	14.8	13.3	12.0	11.9	11.1	10.9	10.5	9.9	9.3	9.2	8.8
	8	14.2	12.8	11.6	11.2	10.5	10.2	9.7	9.2	8.6	8.3	8.0
	6	13.4	12.1	10.8	10.5	9.8	9.3	8.9	8.6	8.0	7.6	7.2
	4.5	12.3	10.8	10.0	9.5	9.0	8.5	8.1	7.8	7.3	6.8	6.4
	2.5	10.8	9.6	9.0	8.4	8.0	7.7	7.3	7.0	6.5	5.9	5.5
	1.5	9.2	8.3	7.5	6.9	6.7	6.5	6.3	6.0	5.6	5.0	4.6
	0.5	6.4	5.7	5.1	4.9	4.7	4.5	4.3	4.2	4.0	3.8	3.7
12	12	14.0	12.3	11.1	10.8	10.1	9.8	9.5	9.0	8.5	8.2	7.9
	8	13.2	11.8	10.7	10.2	9.6	9.3	8.9	8.4	7.9	7.5	7.2
	6	12.6	11.2	10.2	9.7	9.0	8.5	8.2	7.9	7.4	6.9	6.4
	4.5	11.7	10.2	9.4	9.0	8.4	8.0	7.6	7.2	6.8	6.3	5.8
	2.5	10.5	9.2	8.5	8.0	7.8	7.4	7.0	6.6	6.1	5.6	5.2
	1.5	8.9	8.0	7.2	6.8	6.5	6.3	6.1	5.7	5.4	4.8	4.5
	0.5	6.5	5.8	5.3	5.1	4.9	4.7	4.5	4.3	4.2	4.0	3.3
14	12	13.1	11.3	10.2	9.7	9.1	8.8	8.4	8.1	7.6	7.2	7.0
	8	12.4	10.9	9.8	9.2	8.7	8.3	8.0	7.6	7.2	6.8	6.4
	6	11.8	10.4	9.3	8.8	8.3	7.7	7.5	7.2	6.8	6.3	5.9
	4.5	11.1	9.7	8.7	8.2	7.8	7.2	7.0	6.7	6.3	5.8	5.4
	2.5	10.1	8.8	8.1	7.6	7.1	6.7	6.5	6.2	5.7	5.2	5.0
	1.5	8.6	7.7	7.0	6.7	6.3	6.0	5.8	5.5	5.2	4.7	4.5
	0.5	6.6	5.9	5.4	5.2	5.0	4.8	4.6	4.4	4.3	4.2	4.0
16	12	12.3	10.3	9.2	8.6	8.1	7.7	7.4	7.2	6.8	6.3	6.1
	8	11.7	10.0	8.9	8.3	7.8	7.4	7.2	6.8	6.5	6.0	5.7
	6	11.0	9.6	8.5	8.0	7.5	7.1	6.9	6.5	6.2	5.7	5.4
	4.5	10.5	9.1	8.1	7.5	7.2	6.8	6.5	6.2	5.8	5.3	5.1
	2.5	9.7	8.4	7.6	7.0	6.7	6.3	6.1	5.7	5.4	4.9	4.7
	1.5	8.3	7.4	6.6	6.2	6.0	5.8	5.6	5.3	5.1	4.6	4.4
	0.5	6.7	5.9	5.5	5.3	5.1	5.0	4.8	4.6	4.5	4.3	4.1

FL/F = the ratio of the spring free length FL to the deflection F.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 19. The Most Commonly Used Types of Ends for Torsion Springs



Fig. 20. Torsion Spring Stress Correction for Curvature

obtained from the curve in Fig. 20. The corrected stress thus obtained is used only for comparison with the allowable working stress (fatigue strength) curves to determine if it is a safe value, and should not be used in the formulas for deflection.

Torque: Torque is a force applied to a moment arm and tends to produce rotation. Torsion springs exert torque in a circular arc and the arms are rotated about the central axis. It should be noted that the stress produced is in bending, not in torsion. In the spring industry it is customary to specify torque in conjunction with the deflection or with the arms of a spring at a definite position. Formulas for torque are expressed in pound-inches. If ounce-inches are specified, it is necessary to divide this value by 16 in order to use the formulas.

When a load is specified at a distance from a centerline, the torque is, of course, equal to the load multiplied by the distance. The load can be in pounds or ounces with the distances in inches or the load can be in grams or kilograms with the distance in centimeters or millimeters, but to use the design formulas, all values must be converted to pounds and inches. Design formulas for torque are based on the tangent to the arc of rotation and presume that a rod is used to support the spring. The stress in bending caused by the moment $P \times R$ is identical in magnitude to the torque T, provided a rod is used.

Theoretically, it makes no difference how or where the load is applied to the arms of torsion springs. Thus, in Fig. 21, the loads shown multiplied by their respective distances pro-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Formulas for Torsion Springs

Feature	Springs made from round wire	Springs made from square wire
	Formula[a,b]	
d = Wire diameter, Inches	$\sqrt[3]{\frac{10.18T}{S_b}}$	$\sqrt[3]{\frac{6T}{S_b}}$
	$\sqrt[4]{\frac{4000TND}{EF^\circ}}$	$\sqrt[4]{\frac{2375TND}{EF^\circ}}$
S_b = Stress, bending pounds per square inch	$\frac{10.18T}{d^3}$	$\frac{6T}{d^3}$
	$\frac{EdF^\circ}{392ND}$	$\frac{EdF^\circ}{392ND}$
N = Active Coils	$\frac{EdF^\circ}{392S_bD}$	$\frac{EdF^\circ}{392S_bD}$
	$\frac{Ed^4F^\circ}{4000TD}$	$\frac{Ed^4F^\circ}{2375TD}$
F° = Deflection	$\frac{392S_bND}{Ed}$	$\frac{392S_bND}{Ed}$
	$\frac{4000TND}{Ed^4}$	$\frac{2375TND}{Ed^4}$
T = Torque Inch lbs. (Also = $P \times R$)	$0.0982S_bd^3$	$0.1666S_bd^3$
	$\frac{Ed^4F^\circ}{4000ND}$	$\frac{Ed^4F^\circ}{2375ND}$
ID_1 = Inside Diameter After Deflection, Inches	$\frac{N(ID\ \text{free})}{N+\frac{F^\circ}{360}}$	$\frac{N(ID\ \text{free})}{N+\frac{F^\circ}{360}}$

[a] Where two formulas are given for one feature, the designer should use the one found to be appropriate for the given design. The end result from either of any two formulas is the same.

[b] The symbol notation is given on page 308.

duce the same torque; i.e., 20 × 0.5 = 10 pound-inches; 10 × 1 = 10 pound-inches; and 5 × 2 = 10 pound-inches. To further simplify the understanding of torsion spring torque, observe in both Fig. 22 and Fig. 23 that although the turning force is in a circular arc the torque is not equal to P times the radius. The torque in both designs equals $P \times R$ because the spring rests against the support rod at point a.

Design Procedure: Torsion spring designs require more effort than other kinds because consideration has to be given to more details such as the proper size of a supporting rod, reduction of the inside diameter, increase in length, deflection of arms, allowance for friction, and method of testing.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 21. Right-Hand Torsion Spring



Fig. 22. Left-Hand Torsion Spring

The Torque is $T = P \times R$, Not $P \times$ Radius, because the Spring is Resting Against the Support Rod at Point *a*



Fig. 23. Left-Hand Torsion Spring

As with the Spring in Fig. 22, the Torque is $T = P \times R$, Not $P \times$ Radius, Because the Support Point Is at *a*

Copyright 2004, Industrial Press, Inc., New York, NY

Example: What music wire diameter and how many coils are required for the torsion spring shown in Fig. 24, which is to withstand at least 1000 cycles? Determine the corrected stress and the reduced inside diameter after deflection.



Fig. 24. Torsion Spring Design Example. The Spring Is to be Assembled on a 7/16-Inch Support Rod

Method 1, using table: From Table 14, page 343, locate the ½ inch inside diameter for the spring in the left-hand column. Move to the right and then vertically to locate a torque value nearest to the required 10 pound-inches, which is 10.07 pound-inches. At the top of the same column, the music wire diameter is found, which is Number 31 gauge (0.085 inch). At the bottom of the same column the deflection for one coil is found, which is 15.81 degrees. As a 90-degree deflection is required, the number of coils needed is $^{90}/_{1581} = 5.69$ (say $5\frac{3}{4}$ coils).

The spring index $\frac{D}{d} = \frac{0.500 + 0.085}{0.085} = 6.88$ and thus the curvature correction factor K from Fig. 20 = 1.13. Therefore the corrected stress equals 167,000 × 1.13 = 188,700 pounds per square inch which is below the Light Service curve (Fig. 7) and therefore should provide a fatigue life of over 1,000 cycles. The reduced inside diameter due to deflection is found from the formula in Table 13:

$$\mathrm{ID}_1 = \frac{N(ID\ \text{free})}{N + \frac{F}{360}} = \frac{5.75 \times 0.500}{5.75 + \frac{90}{360}} = 0.479 \text{ in.}$$

This reduced diameter easily clears a suggested 7/16 inch diameter supporting rod: 0.479 – 0.4375 = 0.041 inch clearance, and it also allows for the standard tolerance. The overall length of the spring equals the total number of coils plus one, times the wire diameter. Thus, $6\frac{3}{4} \times 0.085 = 0.574$ inch. If a small space of about 1/64 in. is allowed between the coils to eliminate coil friction, an overall length of $2^{1}/_{32}$ inch results.

Although this completes the design calculations, other tolerances should be applied in accordance with the Torsion Spring Tolerance Tables 16 through 17 shown at the end of this section.

Copyright 2004, Industrial Press, Inc., New York, NY

Longer fatigue life: If a longer fatigue life is desired, use a slightly larger wire diameter. Usually the next larger gage size is satisfactory. The larger wire will reduce the stress and still exert the same torque, but will require more coils and a longer overall length.

Percentage method for calculating longer life: The spring design can be easily adjusted for longer life as follows:

1) Select the next larger gage size, which is Number 32 (0.090 inch) from Table 14. The torque is 11.88 pound-inches, the design stress is 166,000 pounds per square inch, and the deflection is 14.9 degrees per coil. As a percentage the torque is 10/11.88 × 100 = 84 per cent.

2) The new stress is 0.84 × 166,000 = 139,440 pounds per square inch. This value is under the bottom or Severe Service curve, Fig. 7, and thus assures longer life.

3) The new deflection per coil is 0.84 × 14.97 = 12.57 degrees. Therefore, the total number of coils required = 90/12.57 = 7.16 (say 7 1/8). The new overall length = 8 1/8 × 0.090 = 0.73 inch (say 3/4 inch). A slight increase in the overall length and new arm location are thus necessary.

Method 2, using formulas: When using this method, it is often necessary to solve the formulas several times because assumptions must be made initially either for the stress or for a wire size. The procedure for design using formulas is as follows (the design example is the same as in Method 1, and the spring is shown in Fig. 24):

Step 1: Note from Table 13, page 338 that the wire diameter formula is:

$$d = \sqrt[3]{\frac{10.18T}{S_b}}$$

Step 2: Referring to Fig. 7, select a trial stress, say 150,000 pounds per square inch.

Step 3: Apply the trial stress, and the 10 pound-inches torque value in the wire diameter formula:

$$d = \sqrt[3]{\frac{10.18T}{S_b}} = \sqrt[3]{\frac{10.18 \times 10}{150{,}000}} = \sqrt[3]{0.000679} = 0.0879 \text{ inch}$$

The nearest gauge sizes are 0.085 and 0.090 inch diameter. *Note*: Table 21, page 351, can be used to avoid solving the cube root.

Step 4: Select 0.085 inch wire diameter and solve the equation for the actual stress:

$$S_b = \frac{10.18T}{d^3} = \frac{10.18 \times 10}{0.085^3} = 165{,}764 \text{ pounds per square inch}$$

Step 5: Calculate the number of coils from the equation, Table 13:

$$N = \frac{EdF^\circ}{392S_bD} = \frac{28{,}500{,}000 \times 0.085 \times 90}{392 \times 165{,}764 \times 0.585} = 5.73 \text{ (say } 5\tfrac{3}{4}\text{)}$$

Step 6: Calculate the total stress. The spring index is 6.88, and the correction factor K is 1.13, therefore total stress = 165,764 × 1.13 = 187,313 pounds per square inch. *Note*: The corrected stress should not be used in any of the formulas as it does not determine the torque or the deflection.

Torsion Spring Design Recommendations.— The following recommendations should be taken into account when designing torsion springs:

Hand: The hand or direction of coiling should be specified and the spring designed so deflection causes the spring to wind up and to have more coils. This increase in coils and overall length should be allowed for during design. Deflecting the spring in an unwinding direction produces higher stresses and may cause early failure. When a spring is sighted down the longitudinal axis, it is "right hand" when the direction of the wire into the spring takes a clockwise direction or if the angle of the coils follows an angle similar to the threads

Copyright 2004, Industrial Press, Inc., New York, NY

of a standard bolt or screw, otherwise it is "left hand." A spring must be coiled right-handed to engage the threads of a standard machine screw.

Rods: Torsion springs should be supported by a rod running through the center whenever possible. If unsupported, or if held by clamps or lugs, the spring will buckle and the torque will be reduced or unusual stresses may occur.

Diameter Reduction: The inside diameter reduces during deflection. This reduction should be computed and proper clearance provided over the supporting rod. Also, allowances should be considered for normal spring diameter tolerances.

Winding: The coils of a spring may be closely or loosely wound, but they seldom should be wound with the coils pressed tightly together. Tightly wound springs with initial tension on the coils do not deflect uniformly and are difficult to test accurately. A small space between the coils of about 20 to 25 per cent of the wire thickness is desirable. Square and rectangular wire sections should be avoided whenever possible as they are difficult to wind, expensive, and are not always readily available.

Arm Length: All the wire in a torsion spring is active between the points where the loads are applied. Deflection of long extended arms can be calculated by allowing one third of the arm length, from the point of load contact to the body of the spring, to be converted into coils. However, if the length of arm is equal to or less than one-half the length of one coil, it can be safely neglected in most applications.

Total Coils: Torsion springs having less than three coils frequently buckle and are difficult to test accurately. When thirty or more coils are used, light loads will not deflect all the coils simultaneously due to friction with the supporting rod. To facilitate manufacturing it is usually preferable to specify the total number of coils to the nearest fraction in eighths or quarters such as 5 ⅛, 5 ¼, 5 ½, etc.

Double Torsion: This design consists of one left-hand-wound series of coils and one series of right-hand-wound coils connected at the center. These springs are difficult to manufacture and are expensive, so it often is better to use two separate springs. For torque and stress calculations, each series is calculated separately as individual springs; then the torque values are added together, but the deflections are not added.

Bends: Arms should be kept as straight as possible. Bends are difficult to produce and often are made by secondary operations, so they are therefore expensive. Sharp bends raise stresses that cause early failure. Bend radii should be as large as practicable. Hooks tend to open during deflection; their stresses can be calculated by the same procedure as that for tension springs.

Spring Index: The spring index must be used with caution. In design formulas it is D/d. For shop measurement it is O.D./d. For arbor design it is I.D./d. Conversions are easily performed by either adding or subtracting 1 from D/d.

Proportions: A spring index between 4 and 14 provides the best proportions. Larger ratios may require more than average tolerances. Ratios of 3 or less, often cannot be coiled on automatic spring coiling machines because of arbor breakage. Also, springs with smaller or larger spring indexes often do not give the same results as are obtained using the design formulas.

Table of Torsion Spring Characteristics.— Table 14 shows design characteristics for the most commonly used torsion springs made from wire of standard gauge sizes. The deflection for one coil at a specified torque and stress is shown in the body of the table. The figures are based on music wire (ASTM A228) and oil-tempered MB grade (ASTM A229), and can be used for several other materials which have similar values for the modulus of elasticity E. However, the design stress may be too high or too low, and the design stress, torque, and deflection per coil should each be multiplied by the appropriate correction factor in Table 15 when using any of the materials given in that table.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Torsion Spring Deflections

AMW Wire Gauge Decimal Equivalent[a]		1 .010	2 .011	3 .012	4 .013	5 .014	6 .016	7 .018	8 .020	9 .022	10 .024	11 .026	12 .029	13 .031	14 .033	15 .035	16 .037
Design Stress, kpsi		232	229	226	224	221	217	214	210	207	205	202	199	197	196	194	192
Torque, pound-inch		.0228	.0299	.0383	.0483	.0596	.0873	.1226	.1650	.2164	.2783	.3486	.4766	.5763	.6917	.8168	.9550
Inside Diameter, inch		Deflection, degrees per coil															
1/16	0.0625	22.35	20.33	18.64	17.29	16.05	14.15	18.72	11.51	10.56	9.818	9.137	8.343	7.896	…	…	…
5/64	0.078125	27.17	24.66	22.55	20.86	19.32	16.96	15.19	13.69	12.52	11.59	10.75	9.768	9.215	…	…	…
3/32	0.09375	31.98	28.98	26.47	24.44	22.60	19.78	17.65	15.87	14.47	13.36	12.36	11.19	10.53	10.18	9.646	9.171
7/64	0.109375	36.80	33.30	30.38	28.02	25.88	22.60	20.12	18.05	16.43	15.14	13.98	12.62	11.85	11.43	10.82	10.27
1/8	0.125	41.62	37.62	34.29	31.60	29.16	25.41	22.59	20.23	18.38	16.91	15.59	14.04	13.17	12.68	11.99	11.36
9/64	0.140625	46.44	41.94	38.20	35.17	32.43	28.23	25.06	22.41	20.33	18.69	17.20	15.47	14.49	13.94	13.16	12.46
5/32	0.15625	51.25	46.27	42.11	38.75	35.71	31.04	27.53	24.59	22.29	20.46	18.82	16.89	15.81	15.19	14.33	13.56
3/16	0.1875	60.89	54.91	49.93	45.91	42.27	36.67	32.47	28.95	26.19	24.01	22.04	19.74	18.45	17.70	16.67	15.75
7/32	0.21875	70.52	63.56	57.75	53.06	48.82	42.31	37.40	33.31	30.10	27.55	25.27	22.59	21.09	20.21	19.01	17.94
1/4	0.250	80.15	72.20	65.57	60.22	55.38	47.94	42.34	37.67	34.01	31.10	28.49	25.44	23.73	22.72	21.35	20.13

AMW Wire Gauge Decimal Equivalent[a]		17 .039	18 .041	19 .043	20 .045	21 .047	22 .049	23 .051	24 .055	25 .059	26 .063	27 .067	28 .071	29 .075	30 .080	31 .085
Design Stress, kpsi		190	188	187	185	184	183	182	180	178	176	174	173	171	169	167
Torque, pound-inch		1.107	1.272	1.460	1.655	1.876	2.114	2.371	2.941	3.590	4.322	5.139	6.080	7.084	8.497	10.07
Inside Diameter, inch		Deflection, degrees per coil														
1/8	0.125	10.80	10.29	9.876	9.447	9.102	8.784	…	…	…	…	…	…	…	…	…
9/64	0.140625	11.83	11.26	10.79	10.32	9.929	9.572	9.244	8.654	8.141	…	…	…	…	…	…
5/32	0.15625	12.86	12.23	11.71	11.18	10.76	10.36	9.997	9.345	8.778	8.279	7.975	…	…	…	…
3/16	0.1875	14.92	14.16	13.55	12.92	12.41	11.94	11.50	10.73	10.05	9.459	9.091	8.663	8.232	7.772	7.364
7/32	0.21875	16.97	16.10	15.39	14.66	14.06	13.52	13.01	12.11	11.33	10.64	10.21	9.711	9.212	8.680	8.208
1/4	0.250	19.03	18.04	17.22	16.39	15.72	15.09	14.52	13.49	12.60	11.82	11.32	10.76	10.19	9.588	9.053

[a] For sizes up to 13 gauge, the table values are for music wire with a modulus *E* of 29,000,000 psi; and for sizes from 27 to 31 guage, the values are for oil-tempered MB with a modulus of 28,500,000 psi.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Torsion Spring Deflections**

AMW Wire Gauge Decimal Equivalent[a]		8 .020	9 .022	10 .024	11 .026	12 .029	13 .031	14 .033	15 .035	16 .037	17 .039	18 .041	19 .043	20 .045	21 .047	22 .049	23 .051
Design Stress, kpsi		210	207	205	202	199	197	196	194	192	190	188	187	185	184	183	182
Torque, pound-inch		.1650	.2164	.2783	.3486	.4766	.5763	.6917	.8168	.9550	1.107	1.272	1.460	1.655	1.876	2.114	2.371
Inside Diameter, inch		Deflection, degrees per coil															
9/32	0.28125	42.03	37.92	34.65	31.72	28.29	26.37	25.23	23.69	22.32	21.09	19.97	19.06	18.13	17.37	16.67	16.03
5/16	0.3125	46.39	41.82	38.19	34.95	31.14	29.01	27.74	26.04	24.51	23.15	21.91	20.90	19.87	19.02	18.25	17.53
11/32	0.34375	50.75	45.73	41.74	38.17	33.99	31.65	30.25	28.38	26.71	25.21	23.85	22.73	21.60	20.68	19.83	19.04
3/8	0.375	55.11	49.64	45.29	41.40	36.84	34.28	32.76	30.72	28.90	27.26	25.78	24.57	23.34	22.33	21.40	20.55
13/32	0.40625	59.47	53.54	48.85	44.63	39.69	36.92	35.26	33.06	31.09	29.32	27.72	26.41	25.08	23.99	22.98	22.06
7/16	0.4375	63.83	57.45	52.38	47.85	42.54	39.56	37.77	35.40	33.28	31.38	29.66	28.25	26.81	25.64	24.56	23.56
15/32	0.46875	68.19	61.36	55.93	51.00	45.39	42.20	40.28	37.74	35.47	33.44	31.59	30.08	28.55	27.29	26.14	25.07
1/2	0.500	72.55	65.27	59.48	54.30	48.24	44.84	42.79	40.08	37.67	35.49	33.53	31.92	30.29	28.95	27.71	26.58

AMW Wire Gauge Decimal Equivalent[a]		24 .055	25 .059	26 .063	27 .067	28 .071	29 .075	30 .080	31 .085	32 .090	33 .095	34 .100	35 .106	36 .112	37 .118	1/8 125
Design Stress, kpsi		180	178	176	174	173	171	169	167	166	164	163	161	160	158	156
Torque, pound-inch		2.941	3.590	4.322	5.139	6.080	7.084	8.497	10.07	11.88	13.81	16.00	18.83	22.07	25.49	29.92
Inside Diameter, inch		Deflection, degrees per coil														
9/32	0.28125	14.88	13.88	13.00	12.44	11.81	11.17	10.50	9.897	9.418	8.934	8.547	8.090	7.727	7.353	6.973
5/16	0.3125	16.26	15.15	14.18	13.56	12.85	12.15	11.40	10.74	10.21	9.676	9.248	8.743	8.341	7.929	7.510
11/32	0.34375	17.64	16.42	15.36	14.67	13.90	13.13	12.31	11.59	11.00	10.42	9.948	9.396	8.955	8.504	8.046
3/8	0.375	19.02	17.70	16.54	15.79	14.95	14.11	13.22	12.43	11.80	11.16	10.65	10.05	9.569	9.080	8.583
13/32	0.40625	20.40	18.97	17.72	16.90	15.99	15.09	14.13	13.28	12.59	11.90	11.35	10.70	10.18	9.655	9.119
7/16	0.4375	21.79	20.25	18.90	18.02	17.04	16.07	15.04	14.12	13.38	12.64	12.05	11.35	10.80	10.23	9.655
15/32	0.46875	23.17	21.52	20.08	19.14	18.09	17.05	15.94	14.96	14.17	13.39	12.75	12.01	11.41	10.81	10.19
1/2	0.500	24.55	22.80	21.26	20.25	19.14	18.03	16.85	15.81	14.97	14.13	13.45	12.66	12.03	11.38	10.73

[a] For sizes up to 13 gauge, the table values are for music wire with a modulus *E* of 29,000,000 psi; and for sizes from 27 to 31 guage, the values are for oil-tempered MB with a modulus of 28,500,000 psi.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Torsion Spring Deflections**

AMW Wire Gauge Decimal Equivalent[a]		16 .037	17 .039	18 .041	19 .043	20 .045	21 .047	22 .049	23 .051	24 .055	25 .059	26 .063	27 .067	28 .071	29 .075	30 .080
Design Stress, kpsi		192	190	188	187	185	184	183	182	180	178	176	174	173	171	169
Torque, pound-inch		.9550	1.107	1.272	1.460	1.655	1.876	2.114	2.371	2.941	3.590	4.322	5.139	6.080	7.084	8.497
Inside Diameter, inch		Deflection, degrees per coil														
17/32	0.53125	39.86	37.55	35.47	33.76	32.02	30.60	29.29	28.09	25.93	24.07	22.44	21.37	20.18	19.01	17.76
9/16	0.5625	42.05	39.61	37.40	35.59	33.76	32.25	30.87	29.59	27.32	25.35	23.62	22.49	21.23	19.99	18.67
19/32	0.59375	44.24	41.67	39.34	37.43	35.50	33.91	32.45	31.10	28.70	26.62	24.80	23.60	22.28	20.97	19.58
5/8	0.625	46.43	43.73	41.28	39.27	37.23	35.56	34.02	32.61	30.08	27.89	25.98	24.72	23.33	21.95	20.48
21/32	0.65625	48.63	45.78	43.22	41.10	38.97	37.22	35.60	34.12	31.46	29.17	27.16	25.83	24.37	22.93	21.39
11/16	0.6875	50.82	47.84	45.15	42.94	40.71	38.87	37.18	35.62	32.85	30.44	28.34	26.95	25.42	23.91	22.30
23/32	0.71875	53.01	49.90	47.09	44.78	42.44	40.52	38.76	37.13	34.23	31.72	29.52	28.07	26.47	24.89	23.21
3/4	0.750	55.20	51.96	49.03	46.62	44.18	42.18	40.33	38.64	35.61	32.99	30.70	29.18	27.52	25.87	24.12

Wire Gauge[ab] or Size and Decimal Equivalent		31 .085	32 .090	33 .095	34 .100	35 .106	36 .112	37 .118	1/8 .125	10 .135	9 .1483	5/32 .1563	8 .162	7 .177	3/16 .1875	6 .192	5 .207
Design Stress, kpsi		167	166	164	163	161	160	158	156	161	158	156	154	150	149	146	143
Torque, pound-inch		10.07	11.88	13.81	16.00	18.83	22.07	25.49	29.92	38.90	50.60	58.44	64.30	81.68	96.45	101.5	124.6
Inside Diameter, inch		Deflection, degrees per coil															
17/32	0.53125	16.65	15.76	14.87	14.15	13.31	12.64	11.96	11.26	10.93	9.958	9.441	9.064	8.256	7.856	7.565	7.015
9/16	0.5625	17.50	16.55	15.61	14.85	13.97	13.25	12.53	11.80	11.44	10.42	9.870	9.473	8.620	8.198	7.891	7.312
19/32	0.59375	18.34	17.35	16.35	15.55	14.62	13.87	13.11	12.34	11.95	10.87	10.30	9.882	8.984	8.539	8.218	7.609
5/8	0.625	19.19	18.14	17.10	16.25	15.27	14.48	13.68	12.87	12.47	11.33	10.73	10.29	9.348	8.881	8.545	7.906
21/32	0.65625	20.03	18.93	17.84	16.95	15.92	15.10	14.26	13.41	12.98	11.79	11.16	10.70	9.713	9.222	8.872	8.202
11/16	0.6875	20.88	19.72	18.58	17.65	16.58	15.71	14.83	13.95	13.49	12.25	11.59	11.11	10.08	9.564	9.199	8.499
23/32	0.71875	21.72	20.52	19.32	18.36	17.23	16.32	15.41	14.48	14.00	12.71	12.02	11.52	10.44	9.905	9.526	8.796
3/4	0.750	22.56	21.31	20.06	19.06	17.88	16.94	15.99	15.02	14.52	13.16	12.44	11.92	10.81	10.25	9.852	9.093

[a] For sizes up to 26 gauge, the table values are for music wire with a modulus *E* of 29,500,000 psi; for sizes from 27 to 1/8 inch diameter the table values are for music wire with a modulus of 28,500,000 psi; for sizes from 10 gauge to 1/8 inch diameter, the values are for oil-tempered MB with a modulus of 28,500,000 psi.

[b] Gauges 31 through 37 are AMW gauges. Gauges 10 through 5 are Washburn and Moen.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Torsion Spring Deflections**

AMW Wire Gauge Decimal Equivalent[a]		24 .055	25 .059	26 .063	27 .067	28 .071	29 .075	30 .080	31 .085	32 .090	33 .095	34 .100	35 .106	36 .112	37 .118	1/8 .125
Design Stress, kpsi		180	178	176	174	173	171	169	167	166	164	163	161	160	158	156
Torque, pound-inch		2.941	3.590	4.322	5.139	6.080	7.084	8.497	10.07	11.88	13.81	16.00	18.83	22.07	25.49	29.92
Inside Diameter, inch		Deflection, degrees per coil														
13/16	0.8125	38.38	35.54	33.06	31.42	29.61	27.83	25.93	24.25	22.90	21.55	20.46	19.19	18.17	17.14	16.09
7/8	0.875	41.14	38.09	35.42	33.65	31.70	29.79	27.75	25.94	24.58	23.03	21.86	20.49	19.39	18.29	17.17
15/16	0.9375	43.91	40.64	37.78	35.88	33.80	31.75	29.56	27.63	26.07	24.52	23.26	21.80	20.62	19.44	18.24
1	1.000	46.67	43.19	40.14	38.11	35.89	33.71	31.38	29.32	27.65	26.00	24.66	23.11	21.85	20.59	19.31
1 1/16	1.0625	49.44	45.74	42.50	40.35	37.99	35.67	33.20	31.01	29.24	27.48	26.06	24.41	23.08	21.74	20.38
1 1/8	1.125	52.20	48.28	44.86	42.58	40.08	37.63	35.01	32.70	30.82	28.97	27.46	25.72	24.31	22.89	21.46
1 3/16	1.1875	54.97	50.83	47.22	44.81	42.18	39.59	36.83	34.39	32.41	30.45	28.86	27.02	25.53	24.04	22.53
1 1/4	1.250	57.73	53.38	49.58	47.04	44.27	41.55	38.64	36.08	33.99	31.94	30.27	28.33	26.76	25.19	23.60

Washburn and Moen Gauge or Size and Decimal Equivalent [a]		10 .135	9 .1483	5/32 .1563	8 .162	7 .177	3/16 .1875	6 .192	5 .207	7/32 .2188	4 .2253	3 .2437	1/4 .250	9/32 .2813	5/16 .3125	11/32 .3438	3/8 .375
Design Stress, kpsi		161	158	156	154	150	149	146	143	142	141	140	139	138	137	136	135
Torque, pound-inch		38.90	50.60	58.44	64.30	81.68	96.45	101.5	124.6	146.0	158.3	199.0	213.3	301.5	410.6	542.5	700.0
Inside Diameter, inch		Deflection, degrees per coil															
13/16	0.8125	15.54	14.08	13.30	12.74	11.53	10.93	10.51	9.687	9.208	8.933	8.346	8.125	7.382	6.784	6.292	5.880
7/8	0.875	16.57	15.00	14.16	13.56	12.26	11.61	11.16	10.28	9.766	9.471	8.840	8.603	7.803	7.161	6.632	6.189
15/16	0.9375	17.59	15.91	15.02	14.38	12.99	12.30	11.81	10.87	10.32	10.01	9.333	9.081	8.225	7.537	6.972	6.499
1	1.000	18.62	16.83	15.88	15.19	13.72	12.98	12.47	11.47	10.88	10.55	9.827	9.559	8.647	7.914	7.312	6.808
1 1/16	1.0625	19.64	17.74	16.74	16.01	14.45	13.66	13.12	12.06	11.44	11.09	10.32	10.04	9.069	8.291	7.652	7.118
1 1/8	1.125	20.67	18.66	17.59	16.83	15.18	14.35	13.77	12.66	12.00	11.62	10.81	10.52	9.491	8.668	7.993	7.427
1 3/16	1.1875	21.69	19.57	18.45	17.64	15.90	15.03	14.43	13.25	12.56	12.16	11.31	10.99	9.912	9.045	8.333	7.737
1 1/4	1.250	22.72	20.49	19.31	18.46	16.63	15.71	15.08	13.84	13.11	12.70	11.80	11.47	10.33	9.422	8.673	8.046

[a] For sizes up to 26 gauge, the table values are for music wire with a modulus *E* of 29,500,000 psi; for sizes from 27 to 1/8 inch diameter the table values are for music wire with a modulus of 28,500,000 psi; for sizes from 10 gauge to 1/8 inch diameter, the values are for oil-tempered MB with a modulus of 28,500,000 psi.

For an example in the use of the table, see the example starting on page 340. Note: Intermediate values may be interpolated within reasonable accuracy.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Correction Factors for Other Materials

Material[a]	Factor	Material[a]	Factor
Hard Drawn MB	0.75	Stainless 316	
Chrome-vanadium	1.10	Up to 1/8 inch diameter	0.75
Chrome-silicon	1.20	Over 1/8 to 1/4 inch diameter	0.65
Stainless 302 and 304		Over 1/4 inch diameter	0.65
Up to 1/8 inch diameter	0.85	Stainless 17–7 PH	
Over 1/8 to 1/4 inch diameter	0.75	Up to 1/8 inch diameter	1.00
Over 1/4 inch diameter	0.65	Over 1/8 to 3/16 inch diameter	1.07
Stainless 431	0.80	Over 3/16 inch diameter	1.12
Stainless 420	0.85	…	…

[a] For use with values in Table 14. *Note*: The figures in Table 14 are for music wire (ASTM A228) and oil-tempered MB grade (ASTM A229) and can be used for several other materials that have a similar modulus of elasticity *E*. However, the design stress may be too high or too low, and therefore the design stress, torque, and deflection per coil should each be multiplied by the appropriate correction factor when using any of the materials given in this table (Table 15).

Torsion Spring Tolerances.— Torsion springs are coiled in a different manner from other types of coiled springs and therefore different tolerances apply. The commercial tolerance on loads is ± 10 per cent and is specified with reference to the angular deflection. For example: 100 pound-inches ± 10 per cent at 45 degrees deflection. One load specified usually suffices. If two loads and two deflections are specified, the manufacturing and testing times are increased. Tolerances smaller than ± 10 per cent require each spring to be individually tested and adjusted, which adds considerably to manufacturing time and cost. Tables 16, 17, and 18 give, respectively, free angle tolerances, tolerances on the number of coils, and coil diameter tolerances.

Table 16. Torsion Spring Tolerances for Angular Relationship of Ends

Number of Coils (*N*)	Spring Index								
	4	6	8	10	12	14	16	18	20
	Free Angle Tolerance, ± degrees								
1	2	3	3.5	4	4.5	5	5.5	5.5	6
2	4	5	6	7	8	8.5	9	9.5	10
3	5.5	7	8	9.5	10.5	11	12	13	14
4	7	9	10	12	14	15	16	16.5	17
5	8	10	12	14	16	18	20	20.5	21
6	9.5	12	14.5	16	19	20.5	21	22.5	24
8	12	15	18	20.5	23	25	27	28	29
10	14	19	21	24	27	29	31.5	32.5	34
15	20	25	28	31	34	36	38	40	42
20	25	30	34	37	41	44	47	49	51
25	29	35	40	44	48	52	56	60	63
30	32	38	44	50	55	60	65	68	70
50	45	55	63	70	77	84	90	95	100

Table 17. Torsion Spring Tolerance on Number of Coils

Number of Coils	Tolerance	Number of Coils	Tolerance
up to 5	±5°	over 10 to 20	±15°
over 5 to 10	±10°	over 20 to 40	±30°

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. Torsion Spring Coil Diameter Tolerances

Wire Diameter, Inch	Spring Index						
	4	6	8	10	12	14	16
	Coil Diameter Tolerance, ± inch						
0.015	0.002	0.002	0.002	0.002	0.003	0.003	0.004
0.023	0.002	0.002	0.002	0.003	0.004	0.005	0.006
0.035	0.002	0.002	0.003	0.004	0.006	0.007	0.009
0.051	0.002	0.003	0.005	0.007	0.008	0.010	0.012
0.076	0.003	0.005	0.007	0.009	0.012	0.015	0.018
0.114	0.004	0.007	0.010	0.013	0.018	0.022	0.028
0.172	0.006	0.010	0.013	0.020	0.027	0.034	0.042
0.250	0.008	0.014	0.022	0.030	0.040	0.050	0.060

Miscellaneous Springs.— This section provides information on various springs, some in common use, some less commonly used.

Conical compression: These springs taper from top to bottom and are useful where an increasing (instead of a constant) load rate is needed, where solid height must be small, and where vibration must be damped. Conical springs with a uniform pitch are easiest to coil. Load and deflection formulas for compression springs can be used – using the average mean coil diameter, and providing the deflection does not cause the largest active coil to lie against the bottom coil. When this happens, each coil must be calculated separately, using the standard formulas for compression springs.

Constant force springs: Those springs are made from flat spring steel and are finding more applications each year. Complicated design procedures can be eliminated by selecting a standard design from thousands now available from several spring manufacturers.

Spiral, clock, and motor springs: Although often used in wind-up type motors for toys and other products, these springs are difficult to design and results cannot be calculated with precise accuracy. However, many useful designs have been developed and are available from spring manufacturing companies.

Flat springs: These springs are often used to overcome operating space limitations in various products such as electric switches and relays. Table 19 lists formulas for designing flat springs. The formulas are based on standard beam formulas where the deflection is small.

Table 19. Formulas for Flat Springs

Feature				
Deflect., f Inches	$f = \frac{PL^3}{4Ebt^3}$ $= \frac{S_b L^2}{6Et}$	$f = \frac{4PL^3}{Ebt^3}$ $= \frac{2S_b L^2}{3Et}$	$f = \frac{6PL^3}{Ebt^3}$ $= \frac{S_b L^2}{Et}$	$f = \frac{5.22PL^3}{Ebt^3}$ $= \frac{0.87S_b L^2}{Et}$
Load, P Pounds	$P = \frac{2S_b bt^2}{3L}$ $= \frac{4Ebt^3 F}{L^3}$	$P = \frac{S_b bt^2}{6L}$ $= \frac{Ebt^3 F}{4L^3}$	$P = \frac{S_b bt^2}{6L}$ $= \frac{Ebt^3 F}{6L^3}$	$P = \frac{S_b bt^2}{6L}$ $= \frac{Ebt^3 F}{5.22L^3}$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. ***(Continued)*** **Formulas for Flat Springs**

Feature				
Stress, S_b Bending psi	$S_b = \frac{3PL}{2bt^2} = \frac{6EtF}{L^2}$	$S_b = \frac{6PL}{bt^2} = \frac{3EtF}{2L^2}$	$S_b = \frac{6PL}{bt^2} = \frac{EtF}{L^2}$	$S_b = \frac{6PL}{bt^2} = \frac{EtF}{0.87L^2}$
Thickness, t Inches	$t = \frac{S_bL^2}{6EF} = \sqrt[3]{\frac{PL^3}{4EbF}}$	$t = \frac{2S_bL^2}{3EF} = \sqrt[3]{\frac{4PL^3}{EbF}}$	$t = \frac{S_bL^2}{EF} = \sqrt[3]{\frac{6PL^3}{EbF}}$	$t = \frac{0.87S_bL^2}{EF} = \sqrt[3]{\frac{5.22PL^3}{EbF}}$

Based on standard beam formulas where the deflection is small.
See page 308 for notation.
Note: Where two formulas are given for one feature, the designer should use the one found to be appropriate for the given design. The result from either of any two formulas is the same.

Belleville washers or disc springs: These washer type springs can sustain relatively large loads with small deflections, and the loads and deflections can be increased by stacking the springs.

Information on springs of this type is given in the section *DISC SPRINGS* starting on page 354.

Volute springs: These springs are often used on army tanks and heavy field artillery, and seldom find additional uses because of their high cost, long production time, difficulties in manufacture, and unavailability of a wide range of materials and sizes. Small volute springs are often replaced with standard compression springs.

Torsion bars: Although the more simple types are often used on motor cars, the more complicated types with specially forged ends are finding fewer applications as time goes.

Moduli of Elasticity of Spring Materials.— The modulus of elasticity in tension, denoted by the letter E, and the modulus of elasticity in torsion, denoted by the letter G, are used in formulas relating to spring design. Values of these moduli for various ferrous and nonferrous spring materials are given in Table 20.

General Heat Treating Information for Springs.— The following is general information on the heat treatment of springs, and is applicable to pre-tempered or hard-drawn spring materials only.

Compression springs are baked after coiling (before setting) to relieve residual stresses and thus permit larger deflections before taking a permanent set.

Extension springs also are baked, but heat removes some of the initial tension. Allowance should be made for this loss. Baking at 500 degrees F for 30 minutes removes approximately 50 per cent of the initial tension. The shrinkage in diameter however, will slightly increase the load and rate.

Outside diameters shrink when springs of music wire, pretempered MB, and other carbon or alloy steels are baked. Baking also slightly increases the free length and these changes produce a little stronger load and increase the rate.

Outside diameters expand when springs of stainless steel (18-8) are baked. The free length is also reduced slightly and these changes result in a little lighter load and a decrease the spring rate.

Inconel, Monel, and nickel alloys do not change much when baked.

Copyright 2004, Industrial Press, Inc., New York, NY

Beryllium-copper shrinks and deforms when heated. Such springs usually are baked in fixtures or supported on arbors or rods during heating.

Brass and phosphor bronze springs should be given a light heat only. Baking above 450 degrees F will soften the material. Do not heat in salt pots.

Torsion springs do not require baking because coiling causes residual stresses in a direction that is helpful, but such springs frequently are baked so that jarring or handling will not cause them to lose the position of their ends.

Table 20. Moduli of Elasticity in Torsion and Tension of Spring Materials

Ferrous Materials			Nonferrous Materials		
Material (Commercial Name)	Modulus of Elasticity[a], psi		Material (Commercial Name)	Modulus of Elasticity[a], psi	
	In Torsion, G	In Tension, E		In Torsion, G	In Tension, E
Hard Drawn MB			Spring Brass		
Up to 0.032 inch	11,700,000	28,800,000	Type 70–30	5,000,000	15,000,000
0.033 to 0.063 inch	11,600,000	28,700,000	Phosphor Bronze		
0.064 to 0.125 inch	11,500,000	28,600,000	5 per cent tin	6,000,000	15,000,000
0.126 to 0.625 inch	11,400,000	28,500,000	Beryllium-Copper		
Music Wire			Cold Drawn 4 Nos.	7,000,000	17,000,000
Up to 0.032 inch	12,000,000	29,500,000	Pretempered, fully hard	7,250,000	19,000,000
0.033 to 0.063 inch	11,850,000	29,000,000	Inconel[b] 600	10,500,000	31,000,000[c]
0.064 to 0.125 inch	11,750,000	28,500,000	Inconel[b] X 750	10,500,000	31,000,000[c]
0.126 to 0.250 inch	11,600,000	28,000,000	Monel[b] 400	9,500,000	26,000,000
Oil-Tempered MB	11,200,000	28,500,000	Monel[b] K 500	9,500,000	26,000,000
Chrome-Vanadium	11,200,000	28,500,000	Duranickel[b] 300	11,000,000	30,000,000
Chrome-Silicon	11,200,000	29,500,000	Permanickel[b]	11,000,000	30,000,000
Silicon-Manganese	10,750,000	29,000,000	Ni Span[b] C 902	10,000,000	27,500,000
Stainless Steel			Elgiloy[d]	12,000,000	29,500,000
Types 302, 304, 316	10,000,000	28,000,000[c]	Iso-Elastic[e]	9,200,000	26,000,000
Type 17–7 PH	10,500,000	29,500,000			
Type 420	11,000,000	29,000,000			
Type 431	11,400,000	29,500,000			

[a] *Note:* Modulus G (shear modulus) is used for compression and extension springs; modulus E (Young's modulus) is used for torsion, flat, and spiral springs.

[b] Trade name of International Nickel Company.

[c] May be 2,000,000 pounds per square inch less if material is not fully hard.

[d] Trade name of Hamilton Watch Company.

[e] Trade name of John Chatillon & Sons.

Spring brass and phosphor bronze springs that are not very highly stressed and are not subject to severe operating use may be stress relieved after coiling by immersing them in boiling water for a period of 1 hour.

Positions of loops will change with heat. Parallel hooks may change as much as 45 degrees during baking. Torsion spring arms will alter position considerably. These changes should be allowed for during looping or forming.

Quick heating after coiling either in a high-temperature salt pot or by passing a spring through a gas flame is not good practice. Samples heated in this way will not conform with production runs that are properly baked. A small, controlled-temperature oven should be used for samples and for small lot orders.

Plated springs should always be baked before plating to relieve coiling stresses and again after plating to relieve hydrogen embrittlement.

Hardness values fall with high heat—but music wire, hard drawn, and stainless steel will increase 2 to 4 points Rockwell C.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. Squares, Cubes, and Fourth Powers of Wire Diameters

Steel Wire Gage (U.S.)	Music or Piano Wire Gage	Diameter Inch	Section Area	Square	Cube	Fourth Power
7-0	…	0.4900	0.1886	0.24010	0.11765	0.05765
6-0	…	0.4615	0.1673	0.21298	0.09829	0.04536
5-0	…	0.4305	0.1456	0.18533	0.07978	0.03435
4-0	…	0.3938	0.1218	0.15508	0.06107	0.02405
3-0	…	0.3625	0.1032	0.13141	0.04763	0.01727
2-0	…	0.331	0.0860	0.10956	0.03626	0.01200
1-0	…	0.3065	0.0738	0.09394	0.02879	0.008825
1	…	0.283	0.0629	0.08009	0.02267	0.006414
2	…	0.2625	0.0541	0.06891	0.01809	0.004748
3	…	0.2437	0.0466	0.05939	0.01447	0.003527
4	…	0.2253	0.0399	0.05076	0.01144	0.002577
5	…	0.207	0.0337	0.04285	0.00887	0.001836
6	…	0.192	0.0290	0.03686	0.00708	0.001359
…	45	0.180	0.0254	0.03240	0.00583	0.001050
7	…	0.177	0.0246	0.03133	0.00555	0.000982
…	44	0.170	0.0227	0.02890	0.00491	0.000835
8	43	0.162	0.0206	0.02624	0.00425	0.000689
…	42	0.154	0.0186	0.02372	0.00365	0.000563
9	…	0.1483	0.0173	0.02199	0.00326	0.000484
…	41	0.146	0.0167	0.02132	0.00311	0.000455
…	40	0.138	0.0150	0.01904	0.00263	0.000363
10	…	0.135	0.0143	0.01822	0.00246	0.000332
…	39	0.130	0.0133	0.01690	0.00220	0.000286
…	38	0.124	0.0121	0.01538	0.00191	0.000237
11	…	0.1205	0.0114	0.01452	0.00175	0.000211
…	37	0.118	0.0109	0.01392	0.00164	0.000194
…	36	0.112	0.0099	0.01254	0.00140	0.000157
…	35	0.106	0.0088	0.01124	0.00119	0.000126
12	…	0.1055	0.0087	0.01113	0.001174	0.0001239
…	34	0.100	0.0078	0.0100	0.001000	0.0001000
…	33	0.095	0.0071	0.00902	0.000857	0.0000815
13	…	0.0915	0.0066	0.00837	0.000766	0.0000701
…	32	0.090	0.0064	0.00810	0.000729	0.0000656
…	31	0.085	0.0057	0.00722	0.000614	0.0000522
14	30	0.080	0.0050	0.0064	0.000512	0.0000410
…	29	0.075	0.0044	0.00562	0.000422	0.0000316
15	…	0.072	0.0041	0.00518	0.000373	0.0000269
…	28	0.071	0.0040	0.00504	0.000358	0.0000254
…	27	0.067	0.0035	0.00449	0.000301	0.0000202
…	26	0.063	0.0031	0.00397	0.000250	0.0000158
16	…	0.0625	0.0031	0.00391	0.000244	0.0000153
…	25	0.059	0.0027	0.00348	0.000205	0.0000121
…	24	0.055	0.0024	0.00302	0.000166	0.00000915
17	…	0.054	0.0023	0.00292	0.000157	0.00000850
…	23	0.051	0.0020	0.00260	0.000133	0.00000677
…	22	0.049	0.00189	0.00240	0.000118	0.00000576
18	…	0.0475	0.00177	0.00226	0.000107	0.00000509
…	21	0.047	0.00173	0.00221	0.000104	0.00000488
…	20	0.045	0.00159	0.00202	0.000091	0.00000410
…	19	0.043	0.00145	0.00185	0.0000795	0.00000342
19	18	0.041	0.00132	0.00168	0.0000689	0.00000283
…	17	0.039	0.00119	0.00152	0.0000593	0.00000231
…	16	0.037	0.00108	0.00137	0.0000507	0.00000187
…	15	0.035	0.00096	0.00122	0.0000429	0.00000150
20	…	0.0348	0.00095	0.00121	0.0000421	0.00000147
…	14	0.033	0.00086	0.00109	0.0000359	0.00000119
21	…	0.0317	0.00079	0.00100	0.0000319	0.00000101
…	13	0.031	0.00075	0.00096	0.0000298	0.000000924
…	12	0.029	0.00066	0.00084	0.0000244	0.000000707
22	…	0.0286	0.00064	0.00082	0.0000234	0.000000669
…	11	0.026	0.00053	0.00068	0.0000176	0.000000457
23	…	0.0258	0.00052	0.00067	0.0000172	0.000000443
…	10	0.024	0.00045	0.00058	0.0000138	0.000000332
24	…	0.023	0.00042	0.00053	0.0000122	0.000000280
…	9	0.022	0.00038	0.00048	0.0000106	0.000000234

Copyright 2004, Industrial Press, Inc., New York, NY

Spring Failure.— Spring failure may be breakage, high permanent set, or loss of load. The causes are listed in groups in Table 22. Group 1 covers causes that occur most frequently; Group 2 covers causes that are less frequent; and Group 3 lists causes that occur occasionally.

Table 22. Causes of Spring Failure

	Cause	Comments and Recommendations
Group 1	High stress	The majority of spring failures are due to high stresses caused by large deflections and high loads. High stresses should be used only for statically loaded springs. Low stresses lengthen fatigue life.
	Hydrogen embrittlement	Improper electroplating methods and acid cleaning of springs, without proper baking treatment, cause spring steels to become brittle, and are a frequent cause of failure. Nonferrous springs are immune.
	Sharp bends and holes	Sharp bends on extension, torsion, and flat springs, and holes or notches in flat springs, cause high concentrations of stress, resulting in failure. Bend radii should be as large as possible, and tool marks avoided.
	Fatigue	Repeated deflections of springs, especially above 1,000,000 cycles, even with medium stresses, may cause failure. Low stresses should be used if a spring is to be subjected to a very high number of operating cycles.
Group 2	Shock loading	Impact, shock, and rapid loading cause far higher stresses than those computed by the regular spring formulas. High-carbon spring steels do not withstand shock loading as well as do alloy steels.
	Corrosion	Slight rusting or pitting caused by acids, alkalis, galvanic corrosion, stress corrosion cracking, or corrosive atmosphere weakens the material and causes higher stresses in the corroded area.
	Faulty heat treatment	Keeping spring materials at the hardening temperature for longer periods than necessary causes an undesirable growth in grain structure, resulting in brittleness, even though the hardness may be correct.
	Faulty material	Poor material containing inclusions, seams, slivers, and flat material with rough, slit, or torn edges is a cause of early failure. Overdrawn wire, improper hardness, and poor grain structure also cause early failure.
Group 3	High temperature	High operating temperatures reduce spring temper (or hardness) and lower the modulus of elasticity, thereby causing lower loads, reducing the elastic limit, and increasing corrosion. Corrosion-resisting or nickel alloys should be used.
	Low temperature	Temperatures below –40 degrees F reduce the ability of carbon steels to withstand shock loads. Carbon steels become brittle at –70 degrees F. Corrosion-resisting, nickel, or nonferrous alloys should be used.
	Friction	Close fits on rods or in holes result in a wearing away of material and occasional failure. The outside diameters of compression springs expand during deflection but they become smaller on torsion springs.
	Other causes	Enlarged hooks on extension springs increase the stress at the bends. Carrying too much electrical current will cause failure. Welding and soldering frequently destroy the spring temper. Tool marks, nicks, and cuts often raise stresses. Deflecting torsion springs outwardly causes high stresses and winding them tightly causes binding on supporting rods. High speed of deflection, vibration, and surging due to operation near natural periods of vibration or their harmonics cause increased stresses.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 23. Arbor Diameters for Springs Made from Music Wire

Wire Dia. (inch)	Spring Outside Diameter (inch)												
	1/16	3/32	1/8	5/32	3/16	7/32	1/4	9/32	5/16	11/32	3/8	7/16	1/2
	Arbor Diameter (inch)												
0.008	0.039	0.060	0.078	0.093	0.107	0.119	0.129	…	…	…	…	…	…
0.010	0.037	0.060	0.080	0.099	0.115	0.129	0.142	0.154	0.164	…	…	…	…
0.012	0.034	0.059	0.081	0.101	0.119	0.135	0.150	0.163	0.177	0.189	0.200	…	…
0.014	0.031	0.057	0.081	0.102	0.121	0.140	0.156	0.172	0.187	0.200	0.213	0.234	…
0.016	0.028	0.055	0.079	0.102	0.123	0.142	0.161	0.178	0.194	0.209	0.224	0.250	0.271
0.018	…	0.053	0.077	0.101	0.124	0.144	0.161	0.182	0.200	0.215	0.231	0.259	0.284
0.020	…	0.049	0.075	0.096	0.123	0.144	0.165	0.184	0.203	0.220	0.237	0.268	0.296
0.022	…	0.046	0.072	0.097	0.122	0.145	0.165	0.186	0.206	0.224	0.242	0.275	0.305
0.024	…	0.043	0.070	0.095	0.120	0.144	0.166	0.187	0.207	0.226	0.245	0.280	0.312
0.026	…	…	0.067	0.093	0.118	0.143	0.166	0.187	0.208	0.228	0.248	0.285	0.318
0.028	…	…	0.064	0.091	0.115	0.141	0.165	0.187	0.208	0.229	0.250	0.288	0.323
0.030	…	…	0.061	0.088	0.113	0.138	0.163	0.187	0.209	0.229	0.251	0.291	0.328
0.032	…	…	0.057	0.085	0.111	0.136	0.161	0.185	0.209	0.229	0.251	0.292	0.331
0.034	…	…	…	0.082	0.109	0.134	0.159	0.184	0.208	0.229	0.251	0.292	0.333
0.036	…	…	…	0.078	0.106	0.131	0.156	0.182	0.206	0.229	0.250	0.294	0.333
0.038	…	…	…	0.075	0.103	0.129	0.154	0.179	0.205	0.227	0.251	0.293	0.335
0.041	…	…	…	…	0.098	0.125	0.151	0.176	0.201	0.226	0.250	0.294	0.336
0.0475	…	…	…	…	0.087	0.115	0.142	0.168	0.194	0.220	0.244	0.293	0.337
0.054	…	…	…	…	…	0.103	0.132	0.160	0.187	0.212	0.245	0.287	0.336
0.0625	…	…	…	…	…	…	0.108	0.146	0.169	0.201	0.228	0.280	0.330
0.072	…	…	…	…	…	…	…	0.129	0.158	0.186	0.214	0.268	0.319
0.080	…	…	…	…	…	…	…	…	0.144	0.173	0.201	0.256	0.308
0.0915	…	…	…	…	…	…	…	…	…	…	0.181	0.238	0.293
0.1055	…	…	…	…	…	…	…	…	…	…	…	0.215	0.271
0.1205	…	…	…	…	…	…	…	…	…	…	…	…	0.215
0.125	…	…	…	…	…	…	…	…	…	…	…	…	0.239

Wire Dia. (inch)	Spring Outside Diameter (inches)													
	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1	1 1/8	1 1/4	1 3/8	1 1/2	1 3/4	2
	Arbor Diameter (inches)													
0.022	0.332	0.357	0.380	…	…	…	…	…	…	…	…	…	…	…
0.024	0.341	0.367	0.393	0.415	…	…	…	…	…	…	…	…	…	…
0.026	0.350	0.380	0.406	0.430	…	…	…	…	…	…	…	…	…	…
0.028	0.356	0.387	0.416	0.442	0.467	…	…	…	…	…	…	…	…	…
0.030	0.362	0.395	0.426	0.453	0.481	0.506	…	…	…	…	…	…	…	…
0.032	0.367	0.400	0.432	0.462	0.490	0.516	0.540	…	…	…	…	…	…	…
0.034	0.370	0.404	0.437	0.469	0.498	0.526	0.552	0.557	…	…	…	…	…	…
0.036	0.372	0.407	0.442	0.474	0.506	0.536	0.562	0.589	…	…	…	…	…	…
0.038	0.375	0.412	0.448	0.481	0.512	0.543	0.572	0.600	0.650	…	…	…	…	…
0.041	0.378	0.416	0.456	0.489	0.522	0.554	0.586	0.615	0.670	0.718	…	…	…	…
0.0475	0.380	0.422	0.464	0.504	0.541	0.576	0.610	0.643	0.706	0.763	0.812	…	…	…
0.054	0.381	0.425	0.467	0.509	0.550	0.589	0.625	0.661	0.727	0.792	0.850	0.906	…	…
0.0625	0.379	0.426	0.468	0.512	0.556	0.597	0.639	0.678	0.753	0.822	0.889	0.951	1.06	1.17
0.072	0.370	0.418	0.466	0.512	0.555	0.599	0.641	0.682	0.765	0.840	0.911	0.980	1.11	1.22
0.080	0.360	0.411	0.461	0.509	0.554	0.599	0.641	0.685	0.772	0.851	0.930	1.00	1.13	1.26
0.0915	0.347	0.398	0.448	0.500	0.547	0.597	0.640	0.685	0.776	0.860	0.942	1.02	1.16	1.30
0.1055	0.327	0.381	0.433	0.485	0.535	0.586	0.630	0.683	0.775	0.865	0.952	1.04	1.20	1.35
0.1205	0.303	0.358	0.414	0.468	0.520	0.571	0.622	0.673	0.772	0.864	0.955	1.04	1.22	1.38
0.125	0.295	0.351	0.406	0.461	0.515	0.567	0.617	0.671	0.770	0.864	0.955	1.05	1.23	1.39

Copyright 2004, Industrial Press, Inc., New York, NY

DISC SPRINGS

Performance of Disc Springs

Introduction.— Disc springs, also known as Belleville springs, are conically formed from washers and have rectangular cross section. The disc spring concept was invented by a Frenchman Louis Belleville in 1865. His springs were relatively thick and had a small amount of cone height or "dish", which determined axial deflection. At that time, these springs were used in the buffer parts of railway rolling stock, for recoil mechanisms of guns, and some other applications. The use of disc springs will be advantageous when space is limited and high force is required, as these conditions cannot be satisfied by using coil springs. Load-deflection characteristics of disc springs are linear and regressive depending on their dimensions and the type of stacking. A large number of standard sizes are available from disc spring manufacturers and distributors, so that custom sizes may not be required. Therefore, disc springs are widely used today in virtually all branches of engineering with possibilities of new applications.

Disc Spring Nomenclature.— Disc spring manufacturers assign their own part number for each disc spring, but the catalog numbers for disc springs are similar, so each item can often be identified regardless of the manufacturer. The disc spring identification number is a numerical code that provides basic dimensions in millimeters. Identification numbers representing the primary dimensions of the disc spring and consist of one, two, or three numbers separated from each other by dash marks or spaces. Disc spring manufacturers in the United States also provide dimensions in inches. Dimensions of several typical disc springs are shown in the following table. Basic nomenclature is illustrated in Fig. 1.

Catalog Number (mm)	Outside Diameter D (mm)	Inside Diameter d (mm)	Thickness t (mm)	Equivalent Catalog Number (inch)
8–4.2–0.4	8	4.2	0.4	0.315–0.165–0.0157
50–25.4–2	50	25.4	2	1.97–1.00–0.0787
200–102–12	200	102	12	7.87–4.02–0.472

Additional dimensions shown in catalogs are cone (dish) height h at unloaded condition, and overall height $H = h + t$, that combines the cone height and the thickness of a disc spring.



Fig. 1. Disc Spring Nomenclature

Disc Spring Group Classification.— Forces and stresses generated by compression depend on disc spring thickness much more than on any other dimensions. Standard DIN 2093 divides all disc springs into three groups in accordance with their thickness:

Group 1 includes all disc springs with thickness less than 1.25 mm (0.0492 inch).

Group 2 includes all disc springs with thickness between 1.25 mm and 6.0 mm (0.0492 inch and 0.2362 inch).

Group 3 includes disc springs with thickness greater than 6.0 mm (0.2362 inch).

There are 87 standard disc spring items, which are manufactured in accordance with Standard DIN 2093 specifications for dimensions and quality requirements. There are 30 standard disc spring items in *Group 1*. The smallest and the largest disc springs in this

Copyright 2004, Industrial Press, Inc., New York, NY

group are 8–4.2–0.2 and 40–20.4–1 respectively. *Group 2* has 45 standard disc spring items. The smallest and the largest disc springs are 22.5–11.2–1.25 and 200–102–5.5 respectfully. *Group 3* includes 12 standard disc spring items. The smallest and the largest disc springs of this group are 125–64–8 and 250–127–14 respectively.

Summary of Disc Spring Sizes Specified in *DIN 2093*

	OD		ID		Thickness	
Classification	Min.	Max	Min.	Max	Min.	Max
Group 1	6 mm (0.236 in)	40 mm (1.575 in)	3.2 mm (0.126 in)	20.4 mm (0.803 in)	0.2 mm (0.008 in)	1.2 mm (0.047 in)
Group 2	20 mm (0.787 in)	225 mm (8.858 in)	10.2 mm (0.402 in)	112 mm (4.409 in)	1.25 mm (0.049 in)	6 mm (0.236 in)
Group 3	125 mm (4.921 in)	250 mm (9.843 in)	61 mm (2.402 in)	127 mm (5.000 in)	6.5 mm (0.256 in)	16 mm (0.630 in)

The number of catalog items by disc spring dimensions depends on the manufacturer. Currently, the smallest disc spring is 6–3.2–0.3 and the largest is 250–127–16. One of the U.S. disc spring manufacturers, Key Bellevilles, Inc. offers 190 catalog items. The greatest number of disc spring items can be found in Christian Bauer GmbH + Co. catalog. There are 291 disc spring catalog items in all three groups.

Disc Spring Contact Surfaces.— Disc springs are manufactured with and without contact (also called load-bearing) surfaces. Contact surfaces are small flats at points 1 and 3 in Fig. 2, adjacent to the corner radii of the spring. The width of the contact surfaces w depends on the outside diameter D of the spring, and its value is approximately $w = D/150$.



Fig. 2. Disc Spring with Contact Surfaces

Disc springs of *Group 1* and *Group 2*, that are contained in the DIN 2093 Standard, do not have contact surfaces, although some *Group 2* disc springs not included in DIN 2093 are manufactured with contact surfaces. All disc springs of *Group 3* (standard and nonstandard) are manufactured with contact surfaces. Almost all disc springs with contact surfaces are manufactured with reduced thickness.

Disc springs without contact surfaces have a corner radii r whose value depends on the spring thickness, t. One disc spring manufacturers recommends the following relationship:

$$r = t/6$$

Disc Spring Materials .— A wide variety of materials are available for disc springs, but selection of the material depends mainly on application. High-carbon steels are used only for *Group 1* disc springs. AISI 1070 and AISI 1095 carbon steels are used in the U.S. Similar high-carbon steels such as DIN 1.1231 and DIN 1.1238 (Germany), and BS 060 A67 and BS 060 A78 (Great Britain) are used in other countries. The most common materials for *Groups 2* and *3* springs operating under normal conditions are chromium-vanadium alloy steels such as AISI 6150 used in the U.S. Similar alloys such as DIN 1.8159 and DIN

Copyright 2004, Industrial Press, Inc., New York, NY

1.7701 (Germany) and BS 735 A50 (Great Britain) are used in foreign countries. Some disc spring manufacturers in the U.S. also use chromium alloy steel AISI 5160. The hardness of disc springs in *Groups 2* and *3* should be 42 to 52 HRC. The hardness of disc springs in *Group 1* tested by the Vickers method should be 412 to 544 HV.

If disc springs must withstand corrosion and high temperatures, stainless steels and heat-resistant alloys are used. Most commonly used stainless steels in the United States are AISI types 301, 316, and 631, which are similar to foreign material numbers DIN 1.4310, DIN 1.4401, and DIN 1.4568, respectively. The operating temperature range for 631 stainless steel is −330 to 660°F (−200 to 350°C). Among heat-resistant alloys, Inconel 718 and Inconel X750 (similar to DIN 2.4668 and DIN 2.4669, respectively) are the most popular. Operating temperature range for Inconel 718 is −440 to 1290°F (−260 to 700°C).

When disc springs are stacked in large numbers and their total weight becomes a major concern, titanium α-β alloys can be used to reduce weight. In such cases, Ti-6Al-4V alloy is used.

If nonmagnetic and corrosion resistant properties are required and material strength is not an issue, phosphor bronzes and beryllium-coppers are the most popular copper alloys for disc springs. Phosphor bronze C52100, which is similar to DIN material number 2.1030, is used at the ordinary temperature range. Beryllium-coppers C17000 and C17200, similar to material numbers DIN 2.1245 and DIN 2.1247 respectively, works well at very low temperatures.

Strength properties of disc spring materials are characterized by moduli of elasticity and Poisson's ratios. These are summarized in Table 1.

Table 1. Strength Characteristics of Disc Spring Materials

Material	Modulus of Elasticity		Poisson's Ratio
	10^6 psi	N/mm^2	
All Steels	28–31	193,000–213,700	0.30
Heat-resistant Alloys			0.28–0.29
α-β Titanium Alloys (Ti-6Al-4V)	17	117,200	0.32
Phosphor Bronze (C52100)	16	110,300	0.35
Beryllium-copper (C17000)	17	117,200	0.30
Beryllium-copper (C17200)	18	124,100	0.30

Stacking of Disc Springs.— Individual disc springs can be arranged in series and parallel stacks. Disc springs in series stacking, Fig. 3, provide larger deflection S_{total} under the same load F as a single disc spring would generate. Disc springs in parallel stacking, Fig. 4, generate higher loads F_{total} with the same deflection s, that a single disc spring would have.

n = number of disc springs in stack
s = deflection of single spring
S_{total} = total deflection of stack of n springs
F = load generated by a single spring
F_{total} = total load generated by springs in stack
L_0 = length of unloaded spring stack

Series: For n disc springs arranged in series as in Fig. 3, the following equations are applied:

$$F_{total} = F$$

$$S_{total} = s \times n$$

$$L_0 = H \times n = (t \div h) \times n \quad (1)$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Disc Springs in Series Stacking
$L_{1,2}$ indices indicate length of spring stack under minimum and maximum load

Parallel: Parallel stacking generates a force that is directly proportional to number of springs arranged in parallel. Two springs in parallel will double the force, three springs in parallel will triple the force, and so on. However, it is a common practice to use two springs in parallel in order to keep the frictional forces between the springs as low as possible. Otherwise, the actual spring force cannot be accurately determined due to deviation from its theoretical value.

For n disc springs arranged in parallel as in Fig. 4, the following equations are applied:

$$F_{total} = F \times n$$

$$S_{total} = s$$

$$L_0 = H + t(n-1) = (h+t) + tn - t = h + tn \quad (2)$$



Fig. 4. Disc Springs in Parallel Stacking

Parallel-Series: When both higher force and greater deflection are required, disc springs must be arranged in a combined parallel-series stacking as illustrated in Fig. 5.



Fig. 5. Disc Springs in Parallel-Series Stacking

Normally, two springs in parallel are nested in series stacking. Two springs in parallel, called a pair, double the force, and the number of pairs, n_p, determines the total deflection, S_{total}.

Copyright 2004, Industrial Press, Inc., New York, NY

For n_p disc spring pairs arranged in series, the following equations are applied:

$$F_{total} = 2 \times F$$

$$S_{total} = s \times n_p$$

$$L_0 = H \times n_p = (2t + h) \times n_p \tag{3}$$

Disc Spring Forces and Stresses

Several methods of calculating forces and stresses for given disc spring configurations exist, some very complicated, others of limited accuracy. The theory which is widely used today for force and stress calculations was developed more than 65 years ago by Almen and Laszlo.

The theory is based on the following assumptions: cross sections are rectangular without radii, over the entire range of spring deflection; no stresses occur in the radial direction; disc springs are always under elastic deformation during deflection; and due to small cone angles of unloaded disc springs (between 3.5° and 8.6°), mathematical simplifications are applied.

The theory provides accurate results for disc springs with the following ratios: outside-to-inside diameter, $D/d = 1.3$ to 2.5; and cone height-to-thickness, h/t is up to 1.5.

Force Generated by Disc Springs Without Contact Surfaces.— Disc springs in *Group 1* and most of disc springs in *Group 2* are manufactured without contact (load-bearing) surfaces, but have corner radii.

A single disc spring force applied to points 1 and 3 in Fig. 6 can be found from Equation (4) in which corner radii are not considered:

$$F = \frac{4 \cdot E \cdot s}{(1 - \mu^2) \cdot K_1 \cdot D^2}\left[\left(h - \frac{s}{2}\right) \cdot (h - s) \cdot t + t^3\right] \tag{4}$$

where F = disc spring force; E = modulus of elasticity of spring material; μ = Poisson's ratio of spring material; K_1 = constant depending on outside-to-inside diameter ratio; D = disc spring nominal outside diameter; h = cone (dish) height; s = disc spring deflection; and, t = disc spring thickness.



Fig. 6. Schematic of Applied Forces

It has been found that the theoretical forces calculated using Equation (4) are lower than the actual (measured) spring forces, as illustrated in Fig. 7. The difference between theoretical (trace 1) and measured force values (trace 3) was significantly reduced (trace 2) when the actual outside diameter of the spring in loaded condition was used in the calculations.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Force–Deflection Relationships (80–36–3.6 Disc Springs)
1 – Theoretical Force Calculated by Equation (4)
2 – Theoretical Force Calculated by Equation (10)
3 – Measured Force

The actual outside diameter D_a of a disc spring contact circle is smaller than the nominal outside diameter D due to cone angle α and corner radius r, as shown in Fig. 8. Diameter D_a cannot be measured, but can be calculated by Equation (9) developed by the author.



Fig. 8. Conventional Shape of Disc Spring

Copyright 2004, Industrial Press, Inc., New York, NY

From Fig. 8,

$$\frac{D_a}{2} = \frac{D}{2} - (a + b) \tag{5}$$

where $a = t \times \sin\alpha$ and $b = r \times \cos\alpha$. Substitution of a and b values into Equation (5) gives:

$$\frac{D_a}{2} = \frac{D}{2} - (t\sin\alpha + r\cos\alpha) \tag{6}$$

The cone angle α is found from:

$$\tan\alpha = \frac{h}{\frac{D}{2} - \frac{d}{2}} = \frac{2h}{D-d} \qquad \alpha = \operatorname{atan}\left(\frac{2h}{D-d}\right) \tag{7}$$

Substituting α from Equation (7) and $r = t/6$ into Equation (6) gives:

$$\frac{D_a}{2} = \frac{D}{2} - t\left\{\sin\left[\operatorname{atan}\left(\frac{2h}{D-d}\right)\right] + \frac{1}{6}\cos\left[\operatorname{atan}\left(\frac{2h}{D-d}\right)\right]\right\} \tag{8}$$

Finally,

$$D_a = D - 2t\left\{\sin\left[\operatorname{atan}\left(\frac{2h}{D-d}\right)\right] + \frac{1}{6}\cos\left[\operatorname{atan}\left(\frac{2h}{D-d}\right)\right]\right\} \tag{9}$$

Substituting D_a from Equation (9) for D in Equation (4) yields Equation (10), that provides better accuracy for calculating disc spring forces.

$$F = \frac{4 \cdot E \cdot s}{(1-\mu^2) \cdot K_1 \cdot D_a^2}\left[\left(h - \frac{s}{2}\right) \cdot (h-s) \cdot t + t^3\right] \tag{10}$$

The constant K_1 depends on disc spring outside diameter D, inside diameter d, and their ratio $\delta = D/d$:

$$K_1 = \frac{\left(\frac{\delta - 1}{\delta}\right)^2}{\pi \cdot \left(\frac{\delta + 1}{\delta - 1} - \frac{2}{\ln\delta}\right)} \tag{11}$$

Table 2 compares the spring force of a series of disc springs deflected by 75% of their cone height, i.e., $s = 0.75h$, as determined from manufacturers catalogs calculated in accordance with Equation (4), calculated forces by use of Equation (10), and measured forces.

Table 2. Comparison Between Calculated and Measured Disc Spring Forces

Disc Spring Catalog Item	*Schnorr* Handbook for Disc Springs	*Christian Bauer* Disc Spring Handbook	*Key Bellevilles* Disc Spring Catalog	Spring Force Calculated by Equation (10)	Measured Disc Spring Force
50 – 22.4 – 2.5 S = 1.05 mm	8510 N 1913 lbf	8510 N 1913 lbf	8616 N 1937 lbf	9020 N 2028 lbf	9563 N 2150 lbf
60 – 30.5 – 2.5 S = 1.35 mm	8340 N 1875 lbf	8342 N 1875 lbf	8465 N 1903 lbf	8794 N 1977 lbf	8896 N 2000 lbf
60 – 30.5 – 3 S = 1.275 mm	13200 N 2967 lbf	13270 N 2983 lbf	13416 N 3016 lbf	14052 N 3159 lbf	13985 N 3144 lbf
70 – 35.5 – 3 S = 1.575 mm	12300 N 2765 lbf	12320 N 2770 lbf	12397 N 2787 lbf	12971 N 2916 lbf	13287 N 2987 lbf
70 – 35.5 – 3.5 S = 1.35 mm		16180 N 3637 lbf		17170 N 3860 lbf	17304 N 3890 lbf

Comparison made at 75% deflection, in Newtons (N) and pounds (lbf)

Copyright 2004, Industrial Press, Inc., New York, NY

The difference between disc spring forces calculated by Equation (10) and the measured forces varies from –5.7% (maximum) to +0.5% (minimum). Disc spring forces calculated by Equation (4) and shown in manufacturers catalogs are less than measured forces by –11% (maximum) to –6% (minimum).

Force Generated by Disc Spring with Contact Surfaces.— Some of disc springs in *Group 2* and all disc springs in *Group 3* are manufactured with small contact (load-bearing) surfaces or flats in addition to the corner radii. These flats provide better contact between disc springs, but, at the same time, they reduce the springs outside diameter and generate higher spring force because in Equation (4) force F is inversely proportional to the square of outside diameter D^2. To compensate for the undesired force increase, the disc spring thickness is reduced from t to t'. Thickness reduction factors t'/t are approximately 0.94 for disc spring series A and B, and approximately 0.96 for series C springs. With such reduction factors, the disc spring force at 75% deflection is the same as for equivalent disc spring without contact surfaces. Equation (12), which is similar to Equation (10), has an additional constant K_4 that correlates the increase in spring force due to contact surfaces. If disc springs do not have contact surfaces, then $K_4^2 = K_4 = 1$.

$$F = \frac{4 \cdot E \cdot K_4^2 \cdot s}{(1-\mu^2) \cdot K_1 \cdot D_a^2}\left[K_4^2 \cdot \left(h' - \frac{s}{2}\right) \cdot (h' - s) \cdot t' + (t')^3\right] \tag{12}$$

where t' = reduced thickness of a disc spring

h' = cone height adjusted to reduced thickness: $h' = H - t'$ $(h' > h)$

K_4 = constant applied to disc springs with contact surfaces.

K_4^2 can be calculated as follows:

$$K_4^2 = \frac{-b + \sqrt{b^2 - 4ac}}{2a} \tag{13}$$

where $a = t'(H - 4t' + 3t)$ $(5H - 8t' + 3t)$; $b = 32(t')^3$; and, $c = -t\,[5(H-t)^2 + 32t^2]$.

Disc Spring Functional Stresses.— Disc springs are designed for both static and dynamic load applications. In static load applications, disc springs may be under constant or fluctuating load conditions that change up to 5,000 or 10,000 cycles over long time intervals. Dynamic loads occur when disc springs are under continuously changing deflection between pre-load (approximately 15% to 20% of the cone height) and the maximum deflection values over short time intervals. Both static and dynamic loads cause compressive and tensile stresses. The position of critical stress points on a disc spring cross section are shown in Fig. 9.



Fig. 9. Critical Stress Points
s is deflection of spring by force F; $h - s$ is a cone height of loaded disc spring

Compressive stresses are acting at points *0* and *1*, that are located on the top surface of the disc spring. Point *0* is located on the cross-sectional mid-point diameter, and point *1* is located on the top inside diameter. Tensile stresses are acting at points *2* and *3*, which are located on the bottom surface of the disc spring. Point *2* is on the bottom inside diameter, and point *3* is on the bottom outside diameter. The following equations are used to calcu-

Copyright 2004, Industrial Press, Inc., New York, NY

late stresses. The minus sign "–" indicates that compressive stresses are acting in a direction opposite to the tensile stresses.

$$\text{Point 0:} \qquad \sigma_0 = -\frac{3}{\pi} \cdot \frac{4E \cdot t \cdot s \cdot K_4}{(1-\mu^2) \cdot K_1 \cdot D_a^2} \tag{14}$$

$$\text{Point 1:} \qquad \sigma_1 = -\frac{4E \cdot K_4 \cdot s \cdot \left[K_4 \cdot K_2 \cdot \left(h - \frac{s}{2}\right) + K_3 \cdot t\right]}{(1-\mu^2) \cdot K_1 \cdot D_a^2} \tag{15}$$

$$\text{Point 2:} \qquad \sigma_2 = \frac{4E \cdot K_4 \cdot s \cdot \left[K_3 \cdot t - K_2 \cdot K_4 \cdot \left(h - \frac{s}{2}\right)\right]}{(1-\mu^2) \cdot K_1 \cdot D_a^2} \tag{16}$$

$$\text{Point 3:} \qquad \sigma_3 = \frac{4E \cdot K_4 \cdot s \cdot \left[K_4 \cdot (2K_3 - K_2) \cdot \left(h - \frac{s}{2}\right) + K_3 \cdot t\right]}{(1-\mu^2) \cdot K_1 \cdot D_a^2 \cdot \delta} \tag{17}$$

K_2 and K_3 are disc spring dimensional constants, defined as follows:

$$K_2 = \frac{6\left(\frac{\delta - 1}{\ln \delta} - 1\right)}{\pi \cdot \ln \delta} \tag{18}$$

$$K_3 = \frac{3 \cdot (\delta - 1)}{\pi \cdot \ln \delta} \tag{19}$$

where $\delta = D/d$ is the outside-to-inside diameter ratio.

In static application, if disc springs are fully flattened (100% deflection), compressive stress at point *0* should not exceed the tensile strength of disc spring materials. For most spring steels, the permissible value is $\sigma_0 \leq 1600$ N/mm^2 or 232,000 psi.

In dynamic applications, certain limitations on tensile stress values are recommended to obtain controlled fatigue life of disc springs utilized in various stacking. Maximum tensile stresses at points *2* and *3* depend on the *Group* number of the disc springs. Stresses σ_2 and σ_3 should not exceed the following values:

	Group 1	Group 2	Group 3
Maximum allowable tensile stresses at points *2* and *3*	1300 N/mm^2 (188,000 psi)	1250 N/mm^2 (181,000 psi)	1200 N/mm^2 (174,000 psi)

Fatigue Life of Disc Springs.— Fatigue life is measured in terms of the maximum number of cycles that dynamically loaded disc springs can sustain prior to failure. Dynamically loaded disc springs are divided into two groups: disc springs with unlimited fatigue life, which exceeds 2×10^6 cycles without failure, and disc springs with limited fatigue life between 10^4 cycles and less then 2×10^6 cycles.

Typically, fatigue life is estimated from three diagrams, each representing one of the three Groups of disc springs (Figs. 10, 11, and 12). Fatigue life is found at the intersection of the vertical line representing minimum tensile stress σ_{min} with the horizontal line, which represents maximum tensile stress σ_{max}. The point of intersection of these two lines defines fatigue life expressed in number of cycles N that can be sustained prior to failure.

Example: For *Group 2* springs in Fig. 11, the intersection point of the $\sigma_{min} = 500$ N/mm^2 line with the $\sigma_{max} = 1200$ N/mm^2 line, is located on the $N = 10^5$ cycles line. The estimated fatigue life is 10^5 cycles.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 10. *Group 1* Diagram for Estimating Fatigue Life of Disc Springs ($0.2 \le t < 1.25$ mm)



Fig. 11. *Group 2* Diagram for Estimating Fatigue Life of Disc Springs ($1.25 \le t \le 6$ mm)



Fig. 12. *Group 3* Diagram for Estimating Fatigue Life of Disc Springs ($6 < t \le 16$ mm)

Copyright 2004, Industrial Press, Inc., New York, NY

When the intersection points of the minimum and maximum stress lines fall inside the areas of each cycle line, only the approximate fatigue life can be estimated by extrapolating the distance from the point of intersection to the nearest cycle line. The extrapolation cannot provide accurate values of fatigue life, because the distance between the cycle lines is expressed in logarithmic scale, and the distance between tensile strength values is expressed in linear scale (Figs. 10, 11, and 12), therefore linear-to-logarithmic scales ratio is not applicable.

When intersection points of minimum and maximum stress lines fall outside the cycle lines area, especially outside the $N = 10^5$ cycles line, the fatigue life cannot be estimated.

Thus, the use of the fatigue life diagrams should be limited to such cases when the minimum and maximum tensile stress lines intersect exactly with each of the cycle lines.

To calculate fatigue life of disc springs without the diagrams, the following equations developed by the author can be used.

Disc Springs in Group 1 $$N = 10^{10.29085532 - 0.00542096(\sigma_{max} - 0.5\sigma_{min})} \quad (20)$$

Disc Springs in Group 2 $$N = 10^{10.10734911 - 0.00537616(\sigma_{max} - 0.5\sigma_{min})} \quad (21)$$

Disc Springs in Group 3 $$N = 10^{13.23985664 - 0.01084192(\sigma_{max} - 0.5\sigma_{min})} \quad (22)$$

As can be seen from Equations (20), (21), and (22), the maximum and minimum tensile stress range affects the fatigue life of disc springs. Since tensile stresses at Points *2* and *3* have different values, see Equations (16) and (17), it is necessary to determine at which critical point the minimum and maximum stresses should be used for calculating fatigue life. The general method is based on the diagram, Fig. 9, from which Point *2* or Point *3* can be found in relationship with disc spring outside-to-inside diameters ratio D/d and disc spring cone height-to-thickness ratio h/r. This method requires intermediate calculations of D/d and h/t ratios and is applicable only to disc springs without contact surfaces. The method is not valid for *Group 3* disc springs or for disc springs in *Group 2* that have contact surfaces and reduced thickness.

A simple and accurate method, that is valid for all disc springs, is based on the following statements:

if $(\sigma_{2\,max} - 0.5\,\sigma_{2\,min}) > (\sigma_{3\,max} - 0.5\,\sigma_{3\,min})$, then Point *2* is used, otherwise

if $(\sigma_{3\,max} - 0.5\,\sigma_{3\,min}) > (\sigma_{2\,max} - 0.5\,\sigma_{2\,min})$, then Point *3* is used

The maximum and minimum tensile stress range for disc springs in *Groups 1*, *2*, and *3* is found from the following equations.

For disc springs in *Group 1*:

$$\sigma_{max} - 0.5\sigma_{min} = \frac{10.29085532 - \log N}{0.00542096} \quad (23)$$

For disc springs in *Group 2*:

$$\sigma_{max} - 0.5\sigma_{min} = \frac{10.10734911 - \log N}{0.00537616} \quad (24)$$

For disc springs in *Group 3*:

$$\sigma_{max} - 0.5\sigma_{min} = \frac{13.23985664 - \log N}{0.01084192} \quad (25)$$

Thus, Equations (23), (24), and (25) can be used to design any spring stack that provides required fatigue life. The following example illustrates how a maximum-minimum stress range is calculated in relationship with fatigue life of a given disc spring stack.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: A dynamically loaded stack, which utilizes disc springs in *Group 2*, must have the fatigue life of 5×10^5 cycles. The maximum allowable tensile stress at Points *2* or *3* is 1250 N/mm^2. Find the minimum tensile stress value to sustain $N = 5 \times 10^5$ cycles.

Solution: Substitution of $\sigma_{max} = 1250$ and $N = 5 \times 10^5$ in Equation (24) gives:

$$1250 - 0.5\sigma_{min} = \frac{10.10734911 - \log(5 \times 10^5)}{0.00537616} = \frac{10.10734911 - 5.69897}{0.00537616} = 820$$

from which $\sigma_{min} = \dfrac{1250 - 820}{0.5} = 860$ N/mm^2 (124,700 psi)

Recommended Dimensional Characteristics of Disc Springs.— Dimensions of disc springs play a very important role in their performance. It is imperative to check selected disc springs for dimensional ratios, that should fall within the following ranges:

1) Diameters ratio, $\delta = D/d = 1.7$ to 2.5.
2) Cone height-to-thickness ratio, $h/t = 0.4$ to 1.3.
3) Outside diameter-to-thickness ratio, $D/t = 18$ to 40.

Small values of δ correspond with small values of the other two ratios. The h/t ratio determines the shape of force-deflection characteristic graphs, that may be nearly linear or strongly curved. If $h/t = 0.4$ the graph is almost linear during deflection of a disc spring up to its flat position. If $h/t = 1.6$ the graph is strongly curved and its maximum point is at 75% deflection. Disc spring deflection from 75% to 100% slightly reduces spring force. Within the $h/t = 0.4 - 1.3$ range, disc spring forces increase with the increase in deflection and reach maximum values at 100% deflection. In a stack of disc springs with a ratio $h/t > 1.3$ deflection of individual springs may be unequal, and only one disc spring should be used if possible.

Example Applications of Disc Springs

Example 1, Disc Springs in Group 2 (no contact surfaces): A mechanical device that works under dynamic loads must sustain a minimum of 1,000,000 cycles. The applied load varies from its minimum to maximum value every 30 seconds. The maximum load is approximately 20,000N (4,500 lbf). A 40-mm diameter guide rod is a receptacle for the disc springs. The rod is located inside a hollow cylinder. Deflection of the disc springs under minimum load should not exceed 5.5 mm (0.217 inch) including a 20 per cent preload deflection. Under maximum load, the deflection is limited to 8 mm (0.315 inch) maximum. Available space for the disc spring stack inside the cylinder is 35 to 40 mm (1.38 to 1.57 inch) in length and 80 to 85 mm (3.15 to 3.54 inch) in diameter.

Select the disc spring catalog item, determine the number of springs in the stack, the spring forces, the stresses at minimum and maximum deflection, and actual disc spring fatigue life.

Solution: 1) Disc spring standard inside diameter is 41 mm (1.61 inch) to fit the guide rod. The outside standard diameter is 80 mm (3.15 in) to fit the cylinder inside diameter. Disc springs with such diameters are available in various thickness: 2.25, 3.0, 4.0, and 5.0 mm (0.089, 0.118, 0.157, and 0.197 inch). The 2.25- and 3.0-mm thick springs do not fit the applied loads, since the maximum force values for disc springs with such thickness are 7,200N and 13,400N (1,600 lbf and 3,000 lbf) respectively. A 5.0-mm thick disc spring should not be used because its D/t ratio, $80/5 = 16$, is less than 18 and is considered as unfavorable. Disc spring selection is narrowed to an 80–41–4 catalog item.

2) Checking 80 – 41 – 4 disc spring for dimensional ratios:

$$\delta = D/d = 80/41 = 1.95 \qquad h/t = 22/4 = 0.55 \qquad D/t = 80/4 = 20$$

Because the dimensional ratios are favorable, the 80–41–4 disc springs are selected.

Copyright 2004, Industrial Press, Inc., New York, NY

3) The number of springs in the stack is found from Equation (1):

$$n = L_o/(t+h) = 40/(4+2.2) = {}^{40}\!/_{62} = 6.45.$$

Rounding n to the nearest integer gives $n = 6$. The actual length of unloaded spring stack is $L_o = 6.2 \times 6 = 37.2$ mm (1.465 inch) and it satisfies the $L_o < 40$ mm condition.

4) Calculating the cone angle α from Equation (7) and actual outside diameter D_a from Equation (9) gives:

$$\alpha = \text{atan}\left(\frac{2 \times 2.2}{80 - 41}\right) = \text{atan}(0.11282) = 6.4°$$

$$D_a = 80 - 2 \times 4\left(\sin[\text{atan}(0.11282)] + \frac{1}{6}\cos[\text{atan}(0.11282)]\right)$$

$$D_a = 77.78 \text{ mm (3.062 in)}$$

5) Calculating constant K_1 from Equation (11):

$$\delta = \frac{D}{d} = 1.95122$$

$$K_1 = \frac{\left(\frac{1.95122 - 1}{1.95122}\right)^2}{\pi \cdot \left[\frac{1.95122 + 1}{1.95122 - 1} - \frac{2}{\ln(1.95122)}\right]} = 0.6841$$

6) Calculating minimum and maximum forces, F_{min} and F_{max} from Equation (10):

Based on the design requirements, the disc spring stack is deflecting by 5.5 mm (0.217 in) under minimum load, and each individual disc spring is deflecting by $5.5/6 \cong 0.92$ mm (0.036 in). A single disc spring deflection $s_{min} = 0.9$ mm (0.035 in) is used to calculate F_{min}. Under maximum load, the disc spring stack is permitted maximum deflection of 8 mm (0.315 in), and each individual disc spring deflects by $8/6 \cong 1.33$ mm (0.0524 in). A disc spring deflection $s_{max} = 1.32$ mm (0.052 in) will be used to calculate F_{max}. If disc springs are made of AISI 6150 alloy steel, then modulus of elasticity $E = 206{,}000$ N/mm^2 (30×10^6 psi) and Poisson's ratio $\mu = 0.3$.

$$F_{min} = \frac{4 \cdot 206000}{(1 - 0.3^2)(0.6841)(77.78)^2}\left[\left(2.2 - \frac{0.9}{2}\right) \cdot (2.2 - 0.9) \cdot 4 + 4^3\right]0.9$$

$$F_{min} = 14390\text{N (3235 lbf)}$$

$$F_{max} = \frac{4 \cdot 206000}{(1 - 0.3^2)(0.6841)(77.78)^2}\left[\left(2.2 - \frac{1.32}{2}\right) \cdot (2.2 - 1.32) \cdot 4 + 4^3\right]1.32$$

$$F_{max} = 20050\text{N (4510 lbf)}$$

7) Calculating constant K_2, Equation (18):

$$\delta = \frac{D}{d} = \frac{80}{41} = 1.95122$$

$$K_2 = \frac{6\left(\frac{\delta - 1}{\ln\delta} - 1\right)}{\pi \cdot \ln\delta} = \frac{6\left(\frac{1.95122 - 1}{\ln(1.95122)} - 1\right)}{\pi \cdot \ln(1.95122)} = 1.2086$$

8) Calculating constant K_3 (Equation (19)):

$$K_3 = \frac{3 \cdot (\delta - 1)}{\pi \cdot \ln\delta} = \frac{3 \cdot (1.95122 - 1)}{\pi \cdot \ln(1.95122)} = 1.3589$$

Copyright 2004, Industrial Press, Inc., New York, NY

9) Compressive stress σ_0 at point *0* due to maximum deflection, Equation (14):

$$\sigma_0 = -\frac{3}{\pi}\cdot\frac{4E\cdot t\cdot s\cdot K_4}{(1-\mu^2)\cdot K_1\cdot D_a^2} = -\frac{3}{\pi}\cdot\frac{4\cdot 206000\cdot 4\cdot 1.32\cdot 1}{(1-0.3^2)\cdot 0.6841\cdot 77.78^2}$$

$$\sigma_0 = 1103\,\text{N/mm}^2 = 160000\,\text{psi}$$

Because the compressive stress at point *0* does not exceed 1600 N/mm^2, its current value satisfies the design requirement.

10) Tensile stress σ_2 at point *2* due to minimum deflection $s = 0.9$ mm, Equation (16):

$$\sigma_{2min} = \frac{4E\cdot K_4\cdot s\cdot\left[K_3\cdot t - K_2\cdot K_4\cdot\left(h-\frac{s}{2}\right)\right]}{(1-\mu^2)\cdot K_1\cdot D_a^2} =$$

$$\frac{4\cdot 206000\cdot 1\cdot 0.9\cdot\left[1.3589\cdot 4 - 1.2086\cdot 1\cdot\left(2.2-\frac{0.9}{2}\right)\right]}{(1-0.3^2)\cdot 0.6841\cdot 77.78^2} = 654\ \text{N/mm}^2$$

11) Tensile stress σ_2 at point *2* due to maximum deflection $s = 1.32$ mm, Equation (16):

$$\sigma_{2max} = \frac{4E\cdot K_4\cdot s\cdot\left[K_3\cdot t - K_2\cdot K_4\cdot\left(h-\frac{s}{2}\right)\right]}{(1-\mu^2)\cdot K_1\cdot D_a^2} =$$

$$\frac{4\cdot 206000\cdot 1\cdot 1.32\cdot\left[1.3589\cdot 4 - 1.2086\cdot 1\cdot\left(2.2-\frac{1.32}{2}\right)\right]}{(1-0.3^2)\cdot 0.6841\cdot 77.78^2} = 1032\ \text{N/mm}^2$$

Thus, $\sigma_{2\,min} = 654$ N/mm^2 (94,850 psi) and $\sigma_{2\,max} = 1032$ N/mm^2 (149,700 psi).

12) Tensile stress σ_3 at point *3* due to minimum deflection $s = 0.9$ mm, Equation (17):

$$\sigma_{3min} = \frac{4E\cdot K_4\cdot s\cdot\left[K_4\cdot(2K_3-K_2)\cdot\left(h-\frac{s}{2}\right)+K_3\cdot t\right]}{(1-\mu^2)\cdot K_1\cdot D_a^2\cdot\delta} =$$

$$\frac{4\cdot 206000\cdot 1\cdot 0.9\cdot\left[1\cdot(2\cdot 1.3589-1.2086)\cdot\left(2.2-\frac{0.9}{2}\right)+1.3589\cdot 4\right]}{(1-0.3^2)\cdot 0.6841\cdot 77.78^2\cdot 1.95122} = 815\,\text{N/mm}^2$$

13) Tensile stress σ_3 at point *3* due to maximum deflection $s = 1.32$ mm, Equation (17):

$$\sigma_{3max} = \frac{4E\cdot K_4\cdot s\cdot\left[K_4\cdot(2K_3-K_2)\cdot\left(h-\frac{s}{2}\right)+K_3\cdot t\right]}{(1-\mu^2)\cdot K_1\cdot D_a^2\cdot\delta} =$$

$$\frac{4\cdot 206000\cdot 1\cdot 1.32\cdot\left[1\cdot(2\cdot 1.3589-1.2086)\cdot\left(2.2-\frac{1.32}{2}\right)+1.3589\cdot 4\right]}{(1-0.3^2)\cdot 0.6841\cdot 77.78^2\cdot 1.95122} = 1149\ \text{N/mm}^2$$

Thus, $\sigma_{3\,min} = 815$ N/mm^2 (118,200 psi) and $\sigma_{3\,max} = 1149$ N/mm^2 (166,600 psi).

14) Functional tensile stress range at critical points *2* and *3*.

Point *2*: $\sigma_{2\,max} - 0.5\sigma_{2\,min} = 1032 - 0.5\times 654 = 705$ N/mm^2

Point *3*: $\sigma_{3\,max} - 0.5\sigma_{3\,min} = 1149 - 0.5\times 815 = 741.5$ N/mm^2

Because $\sigma_{3\,max} - 0.5\sigma_{3\,min} > \sigma_{2\,max} - 0.5\,\sigma_{2\,min}$, the tensile stresses at point *3* are used for fatigue life calculations.

Copyright 2004, Industrial Press, Inc., New York, NY

15) Fatigue life of selected disc springs, Equation (21):

$N = 10^{[10.10734911 - 0.00537616\,(1149 - 0.5 \times 815)]} = 10^{10.10734911 - 3.98642264} = 10^{6.12092647}$

$N = 1{,}321{,}000$ cycles. Thus, the calculated actual fatigue life exceeds required minimum number of cycles by 32%.

In conclusion, the six 80–41–4 disc springs arranged in series stacking, satisfy the requirements and will provide a 32 % longer fatigue life than required by the design criteria.

Example 2: A company wishes to use *Group 3* disc springs with contact surfaces on couplings to absorb bumping impacts between railway cars.

Given:

$D = 200$ mm, disc spring outside diameter
$d = 102$ mm, disc spring inside diameter
$t = 14$ mm, spring standard thickness
$t' = 13.1$ mm, spring reduced thickness
$h = 4.2$ mm, cone height of unloaded spring
$n = 22$, number of springs in series stacking
$S_i = 33.9$ mm, initial deflection of the pack
$S_a = 36.0$ mm, additional deflection of the pack

Find the fatigue life in cycles and determine if the selected springs are suitable for the application.

The calculations are performed in the following sequence:

1) Determine the minimum s_{min} and maximum s_{max} deflections of a single disc spring:

$$s_{max} = \frac{(S_i + S_a)}{n} = \frac{(33.9 + 36)}{22} = 3.18\,\text{mm}$$

$$s_{min} = \frac{S_i}{n} = \frac{33.9}{22} = 1.54\,\text{mm}$$

2) Use Equations (16) and (17) to calculate tensile stresses σ_2 and σ_3 at s_{min} and s_{max} deflections:

$\sigma_{2min} = 674$ N/mm^2, $\sigma_{2max} = 1513$ N/mm^2, $\sigma_{3min} = 707$ N/mm^2, $\sigma_{3max} = 1379$ N/mm^2

3) Determine critical stress points:

$\sigma_{2max} - 0.5\sigma_{2min} = 1513 - 0.5 \times 674 = 1176$ N/mm^2

$\sigma_{3max} - 0.5\sigma_{3min} = 1379 - 0.5 \times 707 = 1025.5$ N/mm^2

Because $(\sigma_{2max} - 0.5\sigma_{2min}) > (\sigma_{3max} - 0.5\sigma_{3min})$, then tensile stresses at Point *2* are used to calculate fatigue life.

4) Fatigue life N is calculated using Equation (22):

$N = 10^{[13.23985664 - (0.01084192 \times 1176)]} = 10^{0.49} = 3$ cycles

The selected disc springs at the above-mentioned minimum and maximum deflection values will not sustain any number of cycles. It is imperative to check the selected disc springs for dimensional ratios:

Outside-to-inside diameters ratio, 200/102 = 1.96; within recommended range.

Cone height-to-thickness ratio is 4.2/13.1 = 0.3; out of range, the minimum ratio is 0.4.

Outside diameter-to-thickness ratio is 200 /13.1 = 15; out of range, the minimum ratio is 18. Thus, only one of the dimensional ratios satisfies the requirements for the best disc spring performance.

Copyright 2004, Industrial Press, Inc., New York, NY

WIRE ROPE, CHAIN, ROPE, AND HOOKS

Strength and Properties of Wire Rope

Wire Rope Construction.— Essentially, a wire rope is made up of a number of strands laid helically about a metallic or non-metallic core. Each strand consists of a number of wires also laid helically about a metallic or non-metallic center. Various types of wire rope have been developed to meet a wide range of uses and operating conditions. These types are distinguished by the kind of core; the number of strands; the number, sizes, and arrangement of the wires in each strand; and the way in which the wires and strands are wound or laid about each other. The following descriptive material is based largely on information supplied by the Bethlehem Steel Co.

Rope Wire Materials: Materials used in the manufacture of rope wire are, in order of increasing strength: iron, phosphor bronze, traction steel, plow steel, improved plow steel, and bridge rope steel. Iron wire rope is largely used for low-strength applications such as elevator ropes not used for hoisting, and for stationary guy ropes.

Phosphor bronze wire rope is used occasionally for elevator governor-cable rope and for certain marine applications as life lines, clearing lines, wheel ropes and rigging.

Traction steel wire rope is used primarily as hoist rope for passenger and freight elevators of the traction drive type, an application for which it was specifically designed.

Ropes made of galvanized wire or wire coated with zinc by the electro-deposition process are used in certain applications where additional protection against rusting is required. As will be noted from the tables of wire-rope sizes and strengths, the breaking strength of galvanized wire rope is 10 per cent less than that of ungalvanized (bright) wire rope. Bethanized (zinc-coated) wire rope can be furnished to bright wire rope strength when so specified.

Galvanized carbon steel, tinned carbon steel, and stainless steel are used for small cords and strands ranging in diameter from $\frac{1}{64}$ to $\frac{3}{8}$ inch and larger.

Marline clad wire rope has each strand wrapped with a layer of tarred marline. The cladding provides hand protection for workers and wear protection for the rope.

Rope Cores: Wire-rope cores are made of fiber, cotton, asbestos, polyvinyl plastic, a small wire rope (independent wire-rope core), a multiple-wire strand (wire-strand core) or a cold-drawn wire-wound spring.

Fiber (manila or sisal) is the type of core most widely used when loads are not too great. It supports the strands in their relative positions and acts as a cushion to prevent nicking of the wires lying next to the core.

Cotton is used for small ropes such as sash cord and aircraft cord.

Asbestos cores can be furnished for certain special operations where the rope is used in oven operations.

Polyvinyl plastics cores are offered for use where exposure to moisture, acids, or caustics is excessive.

A wire-strand core often referred to as WSC, consists of a multiple-wire strand that may be the same as one of the strands of the rope. It is smoother and more solid than the independent wire rope core and provides a better support for the rope strands.

The *independent wire rope core*, often referred to as IWRC, is a small 6 × 7 wire rope with a wire-strand core and is used to provide greater resistance to crushing and distortion of the wire rope. For certain applications it has the advantage over a wire-strand core in that it stretches at a rate closer to that of the rope itself.

Wire ropes with wire-strand cores are, in general, less flexible than wire ropes with independent wire-rope or non-metallic cores.

Copyright 2004, Industrial Press, Inc., New York, NY

Ropes with metallic cores are rated 7½ per cent stronger than those with non-metallic cores.

Wire-Rope Lay: The lay of a wire rope is the direction of the helical path in which the strands are laid and, similarly, the lay of a strand is the direction of the helical path in which the wires are laid. If the wires in the strand or the strands in the rope form a helix similar to the threads of a right-hand screw, i.e., they wind around to the right, the lay is called right hand and, conversely, if they wind around to the left, the lay is called left hand. In the *regular lay*, the wires in the strands are laid in the opposite direction to the lay of the strands in the rope. In right-regular lay, the strands are laid to the right and the wires to the left. In left-regular lay, the strands are laid to the left, the wires to the right. In *Lang lay*, the wires and strands are laid in the same direction, i.e., in right Lang lay, both the wires and strands are laid to the right and in left Lang they are laid to the left.

Alternate lay ropes having alternate right and left laid strands are used to resist distortion and prevent clamp slippage, but because other advantages are missing, have limited use.

The regular lay wire rope is most widely used and right regular lay rope is customarily furnished. Regular lay rope has less tendency to spin or untwist when placed under load and is generally selected where long ropes are employed and the loads handled are frequently removed. Lang lay ropes have greater flexibility than regular lay ropes and are more resistant to abrasion and fatigue.

In preformed wire ropes the wires and strands are preshaped into a helical form so that when laid to form the rope they tend to remain in place. In a non-preformed rope, broken wires tend to "wicker out" or protrude from the rope and strands that are not seized tend to spring apart. Preforming also tends to remove locked-in stresses, lengthen service life, and make the rope easier to handle and to spool.

Strand Construction: Various arrangements of wire are used in the construction of wire rope strands. In the simplest arrangement six wires are grouped around a central wire thus making seven wires, all of the same size. Other types of construction known as "filler-wire," Warrington, Seale, etc. make use of wires of different sizes. Their respective patterns of arrangement are shown diagrammatically in the table of wire weights and strengths.

Specifying Wire Rope.— In specifying wire rope the following information will be required: length, diameter, number of strands, number of wires in each strand, type of rope construction, grade of steel used in rope, whether preformed or not preformed, type of center, and type of lay. The manufacturer should be consulted in selecting the best type of wire rope for a new application.

Properties of Wire Rope.— Important properties of wire rope are strength, wear resistance, flexibility, and resistance to crushing and distortion.

Strength: The strength of wire rope depends upon its size, kind of material of which the wires are made and their number, the type of core, and whether the wire is galvanized or not. Strengths of various types and sizes of wire ropes are given in the accompanying tables together with appropriate factors to apply for ropes with steel cores and for galvanized wire ropes.

Wear Resistance: When wire rope must pass back and forth over surfaces that subject it to unusual wear or abrasion, it must be specially constructed to give satisfactory service.

Such construction may make use of 1) relatively large outer wires; 2) Lang lay in which wires in each strand are laid in the same direction as the strand; and 3) flattened strands.

The object in each type is to provide a greater outside surface area to take the wear or abrasion. From the standpoint of material, improved plow steel has not only the highest tensile strength but also the greatest resistance to abrasion in regularly stocked wire rope.

Copyright 2004, Industrial Press, Inc., New York, NY

Flexibility: Wire rope that undergoes repeated and severe bending, such as in passing around small sheaves and drums, must have a high degree of flexibility to prevent premature breakage and failure due to fatigue. Greater flexibility in wire rope is obtained by

1) using small wires in larger numbers; 2) using Lang lay; and 3) preforming, that is, the wires and strands of the rope are shaped during manufacture to fit the position they will assume in the finished rope.

Resistance to Crushing and Distortion: Where wire rope is to be subjected to transverse loads that may crush or distort it, care should be taken to select a type of construction that will stand up under such treatment.

Wire rope designed for such conditions may have 1) large outer wires to spread the load per wire over a greater area; and 2) an independent wire core or a high-carbon cold-drawn wound spring core.

Standard Classes of Wire Rope.— Wire rope is commonly designated by two figures, the first indicating the number of strands and the second, the number of wires per strand, as: 6 × 7, a six-strand rope having seven wires per strand, or 8 × 19, an eight-strand rope having 19 wires per strand. When such numbers are used as designations of standard wire rope classes, the second figure in the designation may be purely nominal in that the number of wires per strand for various ropes in the class may be slightly less or slightly more than the nominal as will be seen from the following brief descriptions. (For ropes with a wire strand core, a second group of two numbers may be used to indicate the construction of the wire core, as 1 × 21, 1 × 43, and so on.)

6 × 7 Class (Standard Coarse Laid Rope): Wire ropes in this class are for use where resistance to wear, as in dragging over the ground or across rollers, is an important requirement. Heavy hauling, rope transmissions, and well drilling are common applications. These wire ropes are furnished in right regular lay and occasionally in Lang lay. The cores may be of fiber, independent wire rope, or wire strand. Since this class is a relatively stiff type of construction, these ropes should be used with large sheaves and drums. Because of the small number of wires, a larger factor of safety may be called for.



Fig. 1a.
6 × 7 with fiber core



Fig. 1b.
6 × 7 with 1 × 7 WSC



Fig. 1c.
6 × 7 with 1 × 19 WSC



Fig. 1d.
6 × 7 with IWRC

As shown in Figs. 1a through Figs. 1d, this class includes a 6 × 7 construction with fiber core: a 6 × 7 construction with 1 × 7 wire strand core (sometimes called 7 × 7); a 6 × 7 construction with 1 × 19 wire strand core; and a 6 × 7 construction with independent wire rope core. Table 1 provides strength and weight data for this class.

Two special types of wire rope in this class are: aircraft cord, a 6 × 6 or 7 × 7 Bethanized wire rope of high tensile strength and sash cord, a 6 × 7 iron rope used for a variety of purposes where strength is not an important factor.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Weights and Strengths of 6 × 7 (Standard Coarse Laid) Wire Ropes, Preformed and Not Preformed

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.			Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		
		Impr. Plow Steel	Plow Steel	Mild Plow Steel			Impr. Plow Steel	Plow Steel	Mild Plow Steel
1/4	0.094	2.64	2.30	2.00	3/4	0.84	22.7	19.8	17.2
5/16	0.15	4.10	3.56	3.10	7/8	1.15	30.7	26.7	23.2
3/8	0.21	5.86	5.10	4.43	1	1.50	39.7	34.5	30.0
7/16	0.29	7.93	6.90	6.00	1 1/8	1.90	49.8	43.3	37.7
1/2	0.38	10.3	8.96	7.79	1 1/4	2.34	61.0	53.0	46.1
9/16	0.48	13.0	11.3	9.82	1 3/8	2.84	73.1	63.6	55.3
5/8	0.59	15.9	13.9	12.0	1 1/2	3.38	86.2	75.0	65.2

For ropes with steel cores, add 7½ per cent to above strengths.

For galvanized ropes, deduct 10 per cent from above strengths.

Source: Rope diagrams, Bethlehem Steel Co. All data, U.S. Simplified Practice Recommendation 198–50.

6 × 19 Class (Standard Hoisting Rope): This rope is the most popular and widely used class. Ropes in this class are furnished in regular or Lang lay and may be obtained preformed or not preformed. Cores may be of fiber, independent wire rope, or wire strand. As can be seen from Table 2 and Figs. 2a through 2h, there are four common types: 6 × 25 filler wire construction with fiber core (not illustrated), independent wire core, or wire strand core (1 × 25 or 1 × 43); 6 × 19 Warrington construction with fiber core; 6 × 21 filler wire construction with fiber core; and 6 × 19, 6 × 21, and 6 × 17 Seale construction with fiber core.

Table 2. Weights and Strengths of 6 × 19 (Standard Hoisting) Wire Ropes, Preformed and Not Preformed

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.			Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		
		Impr. Plow Steel	Plow Steel	Mild Plow Steel			Impr. Plow Steel	Plow Steel	Mild Plow Steel
1/4	0.10	2.74	2.39	2.07	1 1/4	2.50	64.6	56.2	48.8
5/16	0.16	4.26	3.71	3.22	1 3/8	3.03	77.7	67.5	58.8
3/8	0.23	6.10	5.31	4.62	1 1/2	3.60	92.0	80.0	69.6
7/16	0.31	8.27	7.19	6.25	1 5/8	4.23	107	93.4	81.2
1/2	0.40	10.7	9.35	8.13	1 3/4	4.90	124	108	93.6
9/16	0.51	13.5	11.8	10.2	1 7/8	5.63	141	123	107
5/8	0.63	16.7	14.5	12.6	2	6.40	160	139	121
3/4	0.90	23.8	20.7	18.0	2 1/8	7.23	179	156	…
7/8	1.23	32.2	28.0	24.3	2 1/4	8.10	200	174	…
1	1.60	41.8	36.4	31.6	2 1/2	10.00	244	212	…
1 1/8	2.03	52.6	45.7	39.8	2 3/4	12.10	292	254	…

The 6 × 25 filler wire with fiber core not illustrated.

For ropes with steel cores, add 7½ per cent to above strengths.

For galvanized ropes, deduct 10 per cent from above strengths.

Source: Rope diagrams, Bethlehem Steel Co. All data, U.S. Simplified Practice Recommendation 198–50.

6 × 37 Class (Extra Flexible Hoisting Rope): For a given size of rope, the component wires are of smaller diameter than those in the two classes previously described and hence have less resistance to abrasion. Ropes in this class are furnished in regular and Lang lay with fiber core or independent wire rope core, preformed or not preformed.

Copyright 2004, Industrial Press, Inc., New York, NY


Fig. 2a.
6 × 25 filler wire
with WSC (1 × 25)


Fig. 2b.
6 × 25 filler wire
with IWRC


Fig. 2c.
6 × 19 Seale
with fiber core


Fig. 2d.
6 × 21 Seale
with fiber core


Fig. 2e.
6 × 25 filler wire
with WSC (1 × 43)


Fig. 2f.
6 × 19 Warrington
with fiber core


Fig. 2g.
6 × 17 Seale
with fiber core


Fig. 2h.
6 × 21 filler wire
with fiber core

Table 3. Weights and Strengths of 6 × 37 (Extra Flexible Hoisting) Wire Ropes, Preformed and Not Preformed

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.	
		Impr. Plow Steel	Plow Steel			Impr. Plow Steel	Plow Steel
1/4	0.10	2.59	2.25	1 1/2	3.49	87.9	76.4
5/16	0.16	4.03	3.50	1 5/8	4.09	103	89.3
3/8	0.22	5.77	5.02	1 3/4	4.75	119	103
7/16	0.30	7.82	6.80	1 7/8	5.45	136	118
1/2	0.39	10.2	8.85	2	6.20	154	134
9/16	0.49	12.9	11.2	2 1/8	7.00	173	150
5/8	0.61	15.8	13.7	2 1/4	7.85	193	168
3/4	0.87	22.6	19.6	2 1/2	9.69	236	205
7/8	1.19	30.6	26.6	2 3/4	11.72	284	247
1	1.55	39.8	34.6	3	14.0	335	291
1 1/8	1.96	50.1	43.5	3 1/4	16.4	390	339
1 1/4	2.42	61.5	53.5	3 1/2	19.0	449	390
1 3/8	2.93	74.1	64.5	…	…	…	…

For ropes with steel cores, add 7½ per cent to above strengths.

For galvanized ropes, deduct 10 per cent from above strengths.

Source: Rope diagrams, Bethlehem Steel Co. All data, U. S. Simplified Practice Recommendation 198-50.

As shown in Table 3 and Figs. 3a through 3h, there are four common types: 6 × 29 filler wire construction with fiber core and 6 × 36 filler wire construction with independent wire rope core, a special rope for construction equipment; 6 × 35 (two operations) construction with fiber core and 6 × 41 Warrington Seale construction with fiber core, a standard crane rope in this class of rope construction; 6 × 41 filler wire construction with fiber core or independent wire core, a special large shovel rope usually furnished in Lang lay; and 6 × 46

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3a.
6 × 29 filler wire
with fiber core



Fig. 3b.
6 × 36 filler wire
with IWRC



Fig. 3c.
6 × 35 with
fiber core



Fig. 3d.
6 × 41 Warrington-Seale
with fiber core



Fig. 3e.
6 × 41 filler wire
with fiber core



Fig. 3f.
6 × 41 filler wire
with IWRC



Fig. 3g.
6 × 46 filler wire
with fiber core



Fig. 3h.
6 × 46 filler wire
with IWRC

filler wire construction with fiber core or independent wire rope core, a special large shovel and dredge rope.

8 × 19 Class (Special Flexible Hoisting Rope): This rope is stable and smooth-running, and is especially suitable, because of its flexibility, for high speed operation with reverse bends. Ropes in this class are available in regular lay with fiber core.

As shown in Table 4 and Figs. 4a through 4d, there are four common types: 8 × 25 filler wire construction, the most flexible but the least wear resistant rope of the four types; Warrington type in 8 × 19 construction, less flexible than the 8 × 25; 8 × 21 filler wire construction, less flexible than the Warrington; and Seale type in 8 × 19 construction, which has the greatest wear resistance of the four types but is also the least flexible.

Table 4. Weights and Strengths of 8 × 19 (Special Flexible Hoisting) Wire Ropes, Preformed and Not Preformed

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.	
		Impr. Plow Steel	Plow Steel			Impr. Plow Steel	Plow Steel
1/4	0.09	2.35	2.04	3/4	0.82	20.5	17.8
5/16	0.14	3.65	3.18	7/8	1.11	27.7	24.1
3/8	0.20	5.24	4.55	1	1.45	36.0	31.3
7/16	0.28	7.09	6.17	1 1/8	1.84	45.3	39.4
1/2	0.36	9.23	8.02	1 1/4	2.27	55.7	48.4
9/16	0.46	11.6	10.1	1 3/8	2.74	67.1	58.3
5/8	0.57	14.3	12.4	1 1/2	3.26	79.4	69.1

For ropes with steel cores, add 7½ per cent to above strengths.

For galvanized ropes, deduct 10 per cent from above strengths.

Source: Rope diagrams, Bethlehem Steel Co. All data, U. S. Simplified Practice Recommendation 198-50.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4a.
8 × 25 filler wire
with fiber core



Fig. 4b.
8 × 19 Warrington
with fiber core



Fig. 4c.
8 × 21 filler wire
with fiber core



Fig. 4d.
8 × 19 Seale
with fiber core

Also in this class, but not shown in Table 4 are elevator ropes made of traction steel and iron.

18 × 7 Non-rotating Wire Rope: This rope is specially designed for use where a minimum of rotating or spinning is called for, especially in the lifting or lowering of free loads with a single-part line. It has an inner layer composed of 6 strands of 7 wires each laid in left Lang lay over a fiber core and an outer layer of 12 strands of 7 wires each laid in right regular lay. The combination of opposing lays tends to prevent rotation when the rope is stretched. However, to avoid any tendency to rotate or spin, loads should be kept to at least one-eighth and preferably one-tenth of the breaking strength of the rope. Weights and strengths are shown in Table 5.

Table 5. Weights and Strengths of Standard 18 × 7 Nonrotating Wire Rope, Preformed and Not Preformed



Fig. 5.

Recommended Sheave and Drum Diameters

Single layer on drum	36 rope diameters
Multiple layers on drum	48 rope diameters
Mine service	60 rope diameters

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.	
		Impr. Plow Steel	Plow Steel			Impr. Plow Steel	Plow Steel
3/16	0.061	1.42	1.24	7/8	1.32	29.5	25.7
1/4	0.108	2.51	2.18	1	1.73	38.3	33.3
5/16	0.169	3.90	3.39	1 1/8	2.19	48.2	41.9
3/8	0.24	5.59	4.86	1 1/4	2.70	59.2	51.5
7/16	0.33	7.58	6.59	1 3/8	3.27	71.3	62.0
1/2	0.43	9.85	8.57	1 1/2	3.89	84.4	73.4
9/16	0.55	12.4	10.8	1 5/8	4.57	98.4	85.6
5/8	0.68	15.3	13.3	1 3/4	5.30	114	98.8
3/4	0.97	21.8	19.0	…	…	…	…

For galvanized ropes, deduct 10 per cent from above strengths.

Source: Rope diagrams, sheave and drum diameters, and data for 3/16, 1/4 and 5/16-inch sizes, Bethlehem Steel Co. All other data, U. S. Simplified Practice Recommendation 198-50.

Flattened Strand Wire Rope: The wires forming the strands of this type of rope are wound around triangular centers so that a flattened outer surface is provided with a greater area than in the regular round rope to withstand severe conditions of abrasion. The triangu-

Copyright 2004, Industrial Press, Inc., New York, NY

lar shape of the strands also provides superior resistance to crushing. Flattened strand wire rope is usually furnished in Lang lay and may be obtained with fiber core or independent wire rope core. The three types shown in Table 6 and Figs. 6a through 6c are flexible and are designed for hoisting work.



Fig. 6a.
6 × 25 with fiber core



Fig. 6b.
6 × 30 with fiber core



Fig. 6c.
6 × 27 with fiber core

Table 6. Weights and Strengths of Flattened Strand Wire Rope, Preformed and Not Preformed

Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		Dia., Inches	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.	
		Impr. Plow Steel	Mild Plow Steel			Impr. Plow Steel	Mild Plow Steel
3/8[a]	0.25	6.71	…	1 3/8	3.40	85.5	…
1/2[a]	0.45	11.8	8.94	1 1/2	4.05	101	…
9/16[a]	0.57	14.9	11.2	1 5/8	4.75	118	…
5/8	0.70	18.3	13.9	1 3/4	5.51	136	…
3/4	1.01	26.2	19.8	2	7.20	176	…
7/8	1.39	35.4	26.8	2 1/4	9.10	220	…
1	1.80	46.0	34.8	2 1/2	11.2	269	…
1 1/8	2.28	57.9	43.8	2 3/4	13.6	321	…
1 1/4	2.81	71.0	53.7	…	…	…	…

[a] These sizes in Type B only.

Type H is not in U.S. Simplified Practice Recommendation.

Source: Rope diagrams, Bethlehem Steel Co. All other data, U.S. Simplified Practice Recommendation 198-50.

Flat Wire Rope: This type of wire rope is made up of a number of four-strand rope units placed side by side and stitched together with soft steel sewing wire. These four-strand units are alternately right and left lay to resist warping, curling, or rotating in service. Weights and strengths are shown in Table 7.

Simplified Practice Recommendations.— Because the total number of wire rope types is large, manufacturers and users have agreed upon and adopted a U.S. Simplified Practice Recommendation to provide a simplified listing of those kinds and sizes of wire rope which are most commonly used and stocked. These, then, are the types and sizes which are most generally available. Other types and sizes for special or limited uses also may be found in individual manufacturer's catalogs.

Sizes and Strengths of Wire Rope.— The data shown in Tables 1 through 7 have been taken from U.S. Simplified Practice Recommendation 198-50 but do not include those wire ropes shown in that Simplified Practice Recommendation which are intended primarily for marine use.

Wire Rope Diameter: The diameter of a wire rope is the diameter of the circle that will just enclose it, hence when measuring the diameter with calipers, care must be taken to obtain the largest outside dimension, taken across the opposite strands, rather than the smallest dimension across opposite "valleys" or "flats." It is standard practice for the nominal diameter to be the minimum with all tolerances taken on the plus side. Limits for diam-

Copyright 2004, Industrial Press, Inc., New York, NY

eter as well as for minimum breaking strength and maximum pitch are given in Federal Specification for Wire Rope, RR-R—571a.

Wire Rope Strengths: The strength figures shown in the accompanying tables have been obtained by a mathematical derivation based on actual breakage tests of wire rope and represent from 80 to 95 per cent of the total strengths of the individual wires, depending upon the type of rope construction.

Table 7. Weights and Strengths of Standard Flat Wire Rope, Not Preformed

Flat Wire Rope

This rope consists of a number of 4-strand rope units placed side by side and stitched together with soft steel sewing wire.

Width and Thickness, Inches	No. of Ropes	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.		Width and Thickness, Inches	No. of Ropes	Approx. Weight per Ft., Pounds	Breaking Strength, Tons of 2000 Lbs.	
			Plow Steel	Mild Plow-Steel				Plow Steel	Mild Plow Steel
1/4 × 1 1/2	7	0.69	16.8	14.6	1/2 × 4	9	3.16	81.8	71.2
1/4 × 2	9	0.88	21.7	18.8	1/2 × 4 1/2	10	3.82	90.9	79.1
1/4 × 2 1/2	11	1.15	26.5	23.0	1/2 × 5	12	4.16	109	94.9
1/4 × 3	13	1.34	31.3	27.2	1/2 × 5 1/2	13	4.50	118	103
					1/2 × 6	14	4.85	127	111
5/16 × 1 1/2	5	0.77	18.5	16.0	1/2 × 7	16	5.85	145	126
5/16 × 2	7	1.05	25.8	22.4					
5/16 × 2 1/2	9	1.33	33.2	28.8	5/8 × 3 1/2	6	3.40	85.8	74.6
5/16 × 3	11	1.61	40.5	35.3	5/8 × 4	7	3.95	100	87.1
5/16 × 3 1/2	13	1.89	47.9	41.7	5/8 × 4 1/2	8	4.50	114	99.5
5/16 × 4	15	2.17	55.3	48.1	5/8 × 5	9	5.04	129	112
					5/8 × 5 1/2	10	5.59	143	124
3/8 × 2	6	1.25	31.4	27.3	5/8 × 6	11	6.14	157	137
3/8 × 2 1/2	8	1.64	41.8	36.4	5/8 × 7	13	7.23	186	162
3/8 × 3	9	1.84	47.1	40.9	5/8 × 8	15	8.32	214	186
3/8 × 3 1/2	11	2.23	57.5	50.0					
3/8 × 4	12	2.44	62.7	54.6	3/4 × 5	8	6.50	165	143
3/8 × 4 1/2	14	2.83	73.2	63.7	3/4 × 6	9	7.31	185	161
3/8 × 5	15	3.03	78.4	68.2	3/4 × 7	10	8.13	206	179
3/8 × 5 1/2	17	3.42	88.9	77.3	3/4 × 8	11	9.70	227	197
3/8 × 6	18	3.63	94.1	81.9					
					7/8 × 5	7	7.50	190	165
1/2 × 2 1/2	6	2.13	54.5	47.4	7/8 × 6	8	8.56	217	188
1/2 × 3	7	2.47	63.6	55.4	7/8 × 7	9	9.63	244	212
1/2 × 3 1/2	8	2.82	72.7	63.3	7/8 × 8	10	10.7	271	236

Source: Rope diagram, Bethlehem Steel Co.; all data, U.S. Simplified Practice Recommendation 198–50.

Safe Working Loads and Factors of Safety.— The maximum load for which a wire rope is to be used should take into account such associated factors as friction, load caused by bending around each sheave, acceleration and deceleration, and, if a long length of rope is to be used for hoisting, the weight of the rope at its maximum extension. The condition of the rope — whether new or old, worn or corroded — and type of attachments should also be considered.

Factors of safety for standing rope usually range from 3 to 4; for operating rope, from 5 to 12. Where there is the element of hazard to life or property, higher values are used.

Copyright 2004, Industrial Press, Inc., New York, NY

Installing Wire Rope.— The main precaution to be taken in removing and installing wire rope is to avoid kinking which greatly lessens the strength and useful life. Thus, it is preferable when removing wire rope from the reel to have the reel with its axis in a horizontal position and, if possible, mounted so that it will revolve and the wire rope can be taken off straight. If the rope is in a coil, it should be unwound with the coil in a vertical position as by rolling the coil along the ground. Where a drum is to be used, the rope should be run directly onto it from the reel, taking care to see that it is not bent around the drum in a direction opposite to that on the reel, thus causing it to be subject to reverse bending. On flat or smooth-faced drums it is important that the rope be started from the proper end of the drum. A right lay rope that is being overwound on the drum, that is, it passes over the top of the drum as it is wound on, should be started from the right flange of the drum (looking at the drum from the side that the rope is to come) and a left lay rope from the left flange.

When the rope is under wound on the drum, a right lay rope should be started from the left flange and a left lay rope from the right flange, so that the rope will spool evenly and the turns will lie snugly together.



Sheaves and drums should be properly aligned to prevent undue wear. The proper position of the main or lead sheave for the rope as it comes off the drum is governed by what is called the fleet angle or angle between the rope as it stretches from drum to sheave and an imaginary center-line passing through the center of the sheave groove and a point halfway between the ends of the drum. When the rope is at one end of the drum, this angle should not exceed one and a half to two degrees. With the lead sheave mounted with its groove on this center-line, a safe fleet angle is obtained by allowing 30 feet of lead for each two feet of drum width.

Sheave and Drum Dimensions: Sheaves and drums should be as large as possible to obtain maximum rope life. However, factors such as the need for lightweight equipment for easy transport and use at high speeds, may call for relatively small sheaves with consequent sacrifice in rope life in the interest of overall economy. No hard and fast rules can be laid down for any particular rope if the utmost in economical performance is to be obtained. Where maximum rope life is of prime importance, the following recommendations of Federal Specification RR-R-571a for minimum sheave or drum diameters D in terms of rope diameter d will be of interest. For 6 × 7 rope (six strands of 7 wires each) $D = 72d$; for 6 × 19 rope, $D = 45d$; for 6 × 25 rope, $D = 45d$; for 6 × 29 rope, $D = 30d$; for 6 × 37 rope, $D = 27d$; and for 8 × 19 rope, $D = 31d$.

Too small a groove for the rope it is to carry will prevent proper seating of the rope in the bottom of the groove and result in uneven distribution of load on the rope. Too large a groove will not give the rope sufficient side support. Federal Specification RR-R-571a recommends that sheave groove diameters be larger than the nominal rope diameters by the following minimum amounts: For ropes of $\frac{1}{4}$- to $\frac{5}{16}$-inch diameters, $\frac{1}{64}$ inch larger; for $\frac{3}{8}$- to $\frac{3}{4}$-inch diameter ropes, $\frac{1}{32}$ inch larger; for $\frac{13}{16}$- to $1\frac{1}{8}$-inch diameter ropes, $\frac{3}{64}$ inch larger; for $1\frac{3}{16}$- to $1\frac{1}{2}$-inch ropes, $\frac{1}{16}$ inch larger; for $1\frac{9}{16}$- to $2\frac{1}{4}$-inch ropes, $\frac{3}{32}$ inch larger; and for $2\frac{5}{16}$ and larger diameter ropes, $\frac{1}{8}$ inch larger. For new or regrooved sheaves these values should be doubled; in other words for $\frac{1}{4}$- to $\frac{5}{16}$-inch diameter ropes, the groove diameter should be $\frac{1}{32}$ inch larger, and so on.

Copyright 2004, Industrial Press, Inc., New York, NY

Drum or Reel Capacity: The length of wire rope, in feet, that can be spooled onto a drum or reel, is computed by the following formula, where

A = depth of rope space on drum, inches: $A = (H - D - 2Y) \div 2$

B = width between drum flanges, inches

D = diameter of drum barrel, inches

H = diameter of drum flanges, inches

K = factor from Table 8 for size of line selected

Y = depth not filled on drum or reel where winding is to be less than full capacity

L = length of wire rope on drum or reel, feet: $L = (A + D) \times A \times B \times K$

Table 8. Factors *K* Used in Calculating Wire Rope Drum and Reel Capacities

Rope Dia., In.	Factor *K*	Rope Dia., In.	Factor *K*	Rope Dia., In.	Factor *K*
3/32	23.4	1/2	0.925	1 3/8	0.127
1/8	13.6	9/16	0.741	1 1/2	0.107
9/64	10.8	5/8	0.607	1 5/8	0.0886
5/32	8.72	11/16	0.506	1 3/4	0.0770
3/16	6.14	3/4	0.428	1 7/8	0.0675
7/32	4.59	13/16	0.354	2	0.0597
1/4	3.29	7/8	0.308	2 1/8	0.0532
5/16	2.21	1	0.239	2 1/4	0.0476
3/8	1.58	1 1/8	0.191	2 3/8	0.0419
7/16	1.19	1 1/4	0.152	2 1/2	0.0380

Note: The values of "*K*" allow for normal oversize of ropes, and the fact that it is practically impossible to "thread-wind" ropes of small diameter. However, the formula is based on uniform rope winding and will not give correct figures if rope is wound non-uniformly on the reel. The amount of tension applied when spooling the rope will also affect the length. The formula is based on the same number of wraps of rope in each layer, which is not strictly correct, but does not result in appreciable error unless the width (*B*) of the reel is quite small compared with the flange diameter (*H*).

Example: Find the length in feet of 9/16-inch diameter rope required to fill a drum having the following dimensions: $B = 24$ inches, $D = 18$ inches, $H = 30$ inches,

$$A = (30 - 18 - 0) \div 2 = 6 \text{ inches}$$

$$L = (6 + 18) \times 6 \times 24 \times 0.741 = 2560.0 \text{ or } 2560 \text{ feet}$$

The above formula and factors *K* allow for normal oversize of ropes but will not give correct figures if rope is wound non-uniformly on the reel.

Load Capacity of Sheave or Drum: To avoid excessive wear and groove corrugation, the radial pressure exerted by the wire rope on the sheave or drum must be kept within certain maximum limits. The radial pressure of the rope is a function of rope tension, rope diameter, and tread diameter of the sheave and can be determined by the following equation:

$$P = \frac{2T}{D \times d}$$

where P = Radial pressure in pounds per square inch (see Table 9)

T = Rope tension in pounds

D = Tread diameter of sheave or drum in inches

d = Rope diameter in inches

According to the Bethlehem Steel Co. the radial pressures shown in Table 9 are recommended as maximums according to the material of which the sheave or drum is made.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Maximum Radial Pressures for Drums and Sheaves

Type of Wire Rope	Drum or Sheave Material: Cast Iron	Cast Steel	Manganese Steel[a]	Type of Wire Rope	Drum or Sheave Material: Cast Iron	Cast Steel	Manganese Steel[a]
	Recommended Maximum Radial Pressures, psi				Recommended Maximum Radial Pressures, psi		
6 × 7	300[b]	550[b]	1500[b]	6 × 8 Flattened Strand	450	850	2200
6 × 19	500[b]	900[b]	2500[b]	6 × 25 Flattened Strand	800	1450	4000
6 × 37	600	1075	3000	6 × 30 Flattened Strand	800	1450	4000

[a] 11 to 13 per cent manganese.
[b] These values are for regular lay rope. Lang lay rope values may be increased by 15 per cent.

Minimum Sheave- and Drum-Groove Dimensions for Wire Rope Applications

Nominal Rope Diameter	Groove Radius: New	Worn	Nominal Rope Diameter	Groove Radius: New	Worn	Nominal Rope Diameter	Groove Radius: New	Worn
1/4	0.135	0.129	1 5/8	0.876	0.833	3 3/8	1.807	1.730
5/16	0.167	0.160	1 3/4	0.939	0.897	3 1/2	1.869	1.794
3/8	0.201	0.190	1 7/8	1.003	0.959	3 3/4	1.997	1.918
7/16	0.234	0.220	2	1.085	1.025	4	2.139	2.050
1/2	0.271	0.256	2 1/8	1.137	1.079	4 1/4	2.264	2.178
9/16	0.303	0.288	2 1/4	1.210	1.153	4 1/2	2.396	2.298
5/8	0.334	0.320	2 3/8	1.271	1.199	4 3/4	2.534	2.434
3/4	0.401	0.380	2 1/2	1.338	1.279	5	2.663	2.557
7/8	0.468	0.440	2 5/8	1.404	1.339	5 1/4	2.804	2.691
1	0.543	0.513	2 3/4	1.481	1.409	5 1/2	2.929	2.817
1 1/8	0.605	0.577	2 7/8	1.544	1.473	5 3/4	3.074	2.947
1 1/4	0.669	0.639	3	1.607	1.538	6	3.198	3.075
1 3/8	0.736	0.699	3 1/8	1.664	1.598			
1 1/2	0.803	0.759	3 1/4	1.731	1.658			

All dimensions in inches. Data taken from *Wire Rope Users Manual*, 2nd ed., American Iron and Steel Institute, Washington, D. C. The values given in this table are applicable to grooves in sheaves and drums but are not generally suitable for pitch design, since other factors may be involved.

Rope Loads due to Bending: When a wire rope is bent around a sheave, the resulting bending stress s_b in the outer wire, and equivalent bending load P_b (amount that direct tension load on rope is increased by bending) may be computed by the following formulas:

$s_b = Ed_w \div D$; $P_b = s_b A$, where $A = d^2Q$. E is the modulus of elasticity of the wire rope (varies with the type and condition of rope from 10,000,000 to 14,000,000. An average value of 12,000,000 is frequently used), d is the diameter of the wire rope, d_w is the diameter of the component wire (for 6 × 7 rope, $d_w = 0.106d$; for 6 × 19 rope, $0.063d$; for 6 × 37 rope, $0.045d$; and for 8 × 19 rope, $d_w = 0.050d$). D is the pitch diameter of the sheave in inches, A is the metal cross-sectional area of the rope, and Q is a constant, values for which are: 6 × 7 (Fiber Core) rope, 0.380; 6 × 7 (IWRC or WSC), 0.437; 6 × 19 (Fiber Core), 0.405; 6 × 19 (IWRC or WSC), 0.475; 6 × 37 (Fiber Core), 0.400; 6 × 37 (IWRC), 0.470; 8 × 19 (Fiber Core), 0.370; and Flattened Strand Rope, 0.440.

Example: Find the bending stress and equivalent bending load due to the bending of a 6 × 19 (Fiber Core) wire rope of 1/2-inch diameter around a 24-inch pitch diameter sheave.

$$d_w = 0.063 \times 0.5 = 0.0315 \text{ in.} \qquad A = 0.5^2 \times 0.405 = 0.101 \text{ sq. in.}$$
$$s_b = 12{,}000{,}000 \times 0.0315 \div 24 = 15{,}750 \text{ lbs. per sq. in.}$$
$$P_b = 15{,}750 \times 0.101 = 1590 \text{ lbs.}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Cutting and Seizing of Wire Rope.— Wire rope can be cut with mechanical wire rope shears, an abrasive wheel, an electric resistance cutter (used for ropes of smaller diameter only), or an acetylene torch. This last method fuses the ends of the wires in the strands. It is important that the rope be seized on either side of where the cut is to be made. Any annealed low carbon steel wire may be used for seizing, the recommended sizes being as follows: For a wire rope of $\frac{1}{4}$- to $\frac{15}{16}$-inch diameter, use a seizing wire of 0.054-inch (No. 17 Steel Wire Gage); for a rope of 1- to $1\frac{5}{8}$-inch diameter, use a 0.105-inch wire (No. 12); and for rope of $1\frac{3}{4}$- to $3\frac{1}{2}$-inch diameter, use a 0.135-inch wire (No. 10). Except for preformed wire ropes, a minimum of two seizings on either side of a cut is recommended. Four seizings should be used on either side of a cut for Lang lay rope, a rope with a steel core, or a non-spinning type of rope.

The following method of seizing is given in Federal Specification for wire rope, RR-R-571a. Lay one end of the seizing wire in the groove between two strands of wire rope and wrap the other end tightly in a close helix over the portion in the groove. A seizing iron (round bar $\frac{1}{2}$ to $\frac{5}{8}$ inch diameter by 18 inches long) should be used to wrap the seizing tightly. This bar is placed at right angles to the rope next to the first turn or two of the seizing wire. The seizing wire is brought around the back of the seizing iron and wrapped loosely around the wire rope in the opposite direction to that of the seizing coil. As the seizing iron is now rotated around the rope it will carry the seizing wire snugly and tightly into place. When completed, both ends of the seizing should be twisted together tightly.

Maintenance of Wire Rope.— Heavy abrasion, overloading, and bending around sheaves or drums that are too small in diameter are the principal reasons for the rapid deterioration of wire rope. Wire rope in use should be inspected periodically for evidence of wear and damage by corrosion. Such inspections should take place at progressively shorter intervals over the useful life of the rope as wear tends to accelerate with use. Where wear is rapid, the outside of a wire rope will show flattened surfaces in a short time.

If there is any hazard involved in the use of the rope, it may be prudent to estimate the remaining strength and service life. This assessment should be done for the weakest point where the most wear or largest number of broken wires are in evidence. One way to arrive at a conclusion is to set an arbitrary number of broken wires in a given strand as an indication that the rope should be removed from service and an ultimate strength test run on the worn sample. The arbitrary figure can then be revised and rechecked until a practical working formula is arrived at. A piece of waste rubbed along the wire rope will help to reveal broken wires. The effects of corrosion are not easy to detect because the exterior wires may appear to be only slightly rusty, and the damaging effects of corrosion may be confined to the hidden inner wires where it cannot be seen. To prevent damage by corrosion, the rope should be kept well lubricated. Use of zinc coated wire rope may be indicated for some applications.

Periodic cleaning of wire rope by using a stiff brush and kerosene or with compressed air or live steam and relubricating will help to lengthen rope life and reduce abrasion and wear on sheaves and drums. Before storing after use, wire rope should be cleaned and lubricated.

Lubrication of Wire Rope.— Although wire rope is thoroughly lubricated during manufacture to protect it against corrosion and to reduce friction and wear, this lubrication should be supplemented from time to time. Special lubricants are supplied by wire rope manufacturers. These lubricants vary somewhat with the type of rope application and operating condition. Where the preferred lubricant can not be obtained from the wire rope manufacturer, an adhesive type of lubricant similar to that used for open gearing will often be found suitable. At normal temperatures, some wire rope lubricants may be practically solid and will require thinning before application. Thinning may be done by heating to 160 to 200 degrees F. or by diluting with gasoline or some other fluid that will allow the lubricant to penetrate the rope. The lubricant may be painted on the rope or the rope may be passed through a box or tank filled with the lubricant.

Copyright 2004, Industrial Press, Inc., New York, NY

Replacement of Wire Rope.— When an old wire rope is to be replaced, all drums and sheaves should be examined for wear. All evidence of scoring or imprinting of grooves from previous use should be removed and sheaves with flat spots, defective bearings, and broken flanges, should be repaired or replaced. It will frequently be found that the area of maximum wear is located relatively near one end of the rope. By cutting off that portion, the remainder of the rope may be salvaged for continued use. Sometimes the life of a rope can be increased by simply changing it end for end at about one-half the estimated normal life. The worn sections will then no longer come at the points that cause the greatest wear.

Wire Rope Slings and Fittings

Slings.— A few of the simpler sling arrangements or hitches as they are called, are shown in the accompanying illustration. Normally 6 × 19 Class wire rope is recommended where a diameter in the ¼-inch to 1⅛-inch range is to be used and 6 × 37 Class wire rope where a diameter in the 1¼-inch and larger range is to be used. However, the 6 × 19 Class may be used even in the larger sizes if resistance to abrasion is of primary importance and the 6 × 37 Class in the smaller sizes if greater flexibility is desired.

The *straight lift hitch*, Fig. 7a, is a straight connector between crane hook and load.

The *basket hitch* may be used with two hooks so that the sides are vertical as shown at Fig. 7b or with a single hook with sides at various angles with the vertical as shown at Fig. 7c, Fig. 7d, and Fig. 7e. As the angle with the vertical increases, a greater tension is placed on the rope so that for any given load, a sling of greater lifting capacity must be used.

The *choker hitch*, shown at Fig. 7f, is widely used for lifting bundles of items such as bars, poles, pipe, and similar objects. The choker hitch holds these items firmly, but the load must be balanced so that it rides safely. Since additional stress is imposed on the rope due to the choking action, the capacity of this type of hitch is 25 per cent less than that of the comparable straight lift. If two choker hitches are used at an angle, these angles must also be taken into consideration as with the basket hitches.

Wire Rope Fittings.— Many varieties of swaged fittings are available for use with wire rope and several industrial and aircraft types are shown in the accompanying illustration. Swaged fittings on wire rope have an efficiency (ability to hold the wire rope) of approximately 100 per cent of the catalogue rope strength. These fittings are attached to the end or body of the wire rope by the application of high pressure through special dies that cause the material of the fitting to "flow" around the wires and strands of the rope to form a union that is as strong as the rope itself. The more commonly used types, of swaged fittings range from ⅛- to ⅝-inch diameter sizes in industrial types and from the 1/16- to ⅝-inch sizes in aircraft types. These fittings are furnished attached to the wire strand, rope, or cable.

Applying Clips and Attaching Sockets.— In attaching U-bolt clips for fastening the end of a wire rope to form a loop, it is essential that the saddle or base of the clip bears against the longer or "live" end of the rope loop and the U-bolt against the shorter or "dead" end. The "U" of the clips should never bear against the live end of the rope because the rope may be cut or kinked. A wire-rope thimble should be used in the loop eye of the rope to prevent kinking when rope clips are used. The strength of a clip fastening is usually less than 80 percent of the strength of the rope. Table 10 gives the proper size, number, and spacing for each size of wire rope.

In attaching commercial sockets of forged steel to wire rope ends, the following procedure is recommended. The wire rope is seized at the end and another seizing is applied at a distance from the end equal to the length of the basket of the socket. As explained in a previous section, soft iron wire is used and particularly for the larger sizes of wire rope, it is important to use a seizing iron to secure a tight winding. For large ropes, the seizing should be several inches long.

Copyright 2004, Industrial Press, Inc., New York, NY

Wire Rope Slings and Fittings



Fig. 7a. Straight Lift
One leg vertical
Load capacity is 100% of a single rope.



Fig. 7b. Basket Hitch
Two legs vertical
Load capacity is 200% of the single rope in Fig. 7a.



Fig. 7c. Basket Hitch
Two legs at 30° with the vertical
Load capacity is 174% of the single rope in Fig. 7a.



Fig. 7d. Basket Hitch
Two legs at 45° with the vertical
Load capacity is 141% of the single rope in Fig. 7a.



Fig. 7e. Basket Hitch
Two legs at 60° with the vertical
Load capacity is 100% of the single rope in Fig. 7a.

Fig. 7f. Choker Hitch
One leg vertical, with slip-through loop
Rated capacity is 75% of the single rope in Fig. 7a.

The end seizing is now removed and the strands are separated so that the fiber core can be cut back to the next seizing. The individual wires are then untwisted and "broomed out" and for the distance they are to be inserted in the socket are carefully cleaned with benzine, naphtha, or unleaded gasoline. The wires are then dipped into commercial muriatic (hydrochloric) acid and left (usually one to three minutes) until the wires are bright and clean or, if zinc coated, until the zinc is removed. After cleaning, the wires are dipped into a hot soda solution (1 pound of soda to 4 gallons of water at 175 degrees F. minimum) to neutralize the acid. The rope is now placed in a vise. A temporary seizing is used to hold the wire ends

Copyright 2004, Industrial Press, Inc., New York, NY

Rated Capacities for Improved Plow Steel Wire Rope and Wire Rope Slings (in tons of 2,000 lbs)

Dia. (in.)	Independent Wire Rope Core															Fiber Core												
	Vertical			Choker			60° Bridle			45°Bridle			30°Bridle			Vertical			Choker			60° Bridle			45° Bridle			30° Bridle		
	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C
Single Leg, 6 × 19 Wire Rope																														
¼	0.59	0.56	0.53	0.44	0.42	0.40	…	…	…	…	…	…	…	…	…	0.55	0.51	0.49	0.41	0.38	0.37	…	…	…	…	…	…	…	…	…
⅜	1.3	1.2	1.1	0.98	0.93	0.86	…	…	…	…	…	…	…	…	…	1.2	1.1	1.1	0.91	0.85	0.80	…	…	…	…	…	…	…	…	…
½	2.3	2.2	2.0	1.7	1.6	1.5	…	…	…	…	…	…	…	…	…	2.1	2.0	1.8	1.6	1.5	1.4	…	…	…	…	…	…	…	…	…
⅝	3.6	3.4	3.0	2.7	2.5	2.2	…	…	…	…	…	…	…	…	…	3.3	3.1	2.8	2.5	2.3	2.1	…	…	…	…	…	…	…	…	…
¾	5.1	4.9	4.2	3.8	3.6	3.1	…	…	…	…	…	…	…	…	…	4.8	4.4	3.9	3.6	3.3	2.9	…	…	…	…	…	…	…	…	…
⅞	6.9	6.6	5.5	5.2	4.9	4.1	…	…	…	…	…	…	…	…	…	6.4	5.9	5.1	4.8	4.5	3.9	…	…	…	…	…	…	…	…	…
1	9.0	8.5	7.2	6.7	6.4	5.4	…	…	…	…	…	…	…	…	…	8.4	7.7	6.7	6.3	5.8	5.0	…	…	…	…	…	…	…	…	…
1⅛	11	10	9.0	8.5	7.8	6.8	…	…	…	…	…	…	…	…	…	10	9.5	8.4	7.9	7.1	6.3	…	…	…	…	…	…	…	…	…
Single Leg, 6 × 37 Wire Rope																														
1¼	13	12	10	9.9	9.2	7.9	…	…	…	…	…	…	…	…	…	12	11	9.8	9.2	8.3	7.4	…	…	…	…	…	…	…	…	…
1⅜	16	15	13	12	11	9.6	…	…	…	…	…	…	…	…	…	15	13	12	11	10	8.9	…	…	…	…	…	…	…	…	…
1½	19	17	15	14	13	11	…	…	…	…	…	…	…	…	…	17	16	14	13	12	10	…	…	…	…	…	…	…	…	…
1¾	26	24	20	19	18	15	…	…	…	…	…	…	…	…	…	24	21	19	18	16	14	…	…	…	…	…	…	…	…	…
2	33	30	26	25	23	20	…	…	…	…	…	…	…	…	…	31	28	25	23	21	18	…	…	…	…	…	…	…	…	…
2¼	41	38	33	31	29	25	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…
Two-Leg Bridle or Basket Hitch, 6 × 19 Wire Rope Sling																														
¼	1.2	1.1	1.0	…	…	…	1.0	0.97	0.92	0.83	0.79	0.75	0.59	0.56	0.53	1.1	1.0	0.99	…	…	…	0.95	0.88	0.85	0.77	0.72	0.70	0.55	0.51	0.49
⅜	2.0	2.5	2.3	…	…	…	2.3	2.1	2.0	1.8	1.8	1.8	1.3	1.2	1.1	2.4	2.2	2.1	…	…	…	2.1	1.9	1.8	1.7	1.6	1.5	1.2	1.1	1.1
½	4.0	4.4	3.9	…	…	…	4.0	3.6	3.4	3.2	3.1	2.8	2.3	2.2	2.0	4.3	3.9	3.7	…	…	…	3.7	3.4	3.2	3.0	2.8	2.6	2.1	2.0	1.8
⅝	7.2	6.6	6.0	…	…	…	6.2	5.9	5.2	5.1	4.8	4.2	3.6	3.4	3.0	6.7	6.2	5.6	…	…	…	6.2	5.3	4.8	4.7	4.4	4.0	3.3	3.1	2.8
¾	10	9.7	8.4	…	…	…	8.9	8.4	7.3	7.2	6.9	5.9	5.1	4.9	4.2	9.5	8.8	7.8	…	…	…	8.2	7.6	6.8	6.7	6.2	5.5	4.8	4.4	3.9
⅞	14	13	11	…	…	…	12	11	9.6	9.8	9.3	7.8	6.9	6.6	5.5	13	12	10	…	…	…	11	10	8.9	9.1	8.4	7.3	6.4	5.9	5.1
1	18	17	14	…	…	…	15	15	12	13	12	10	9.0	8.5	7.2	17	15	13	…	…	…	14	13	11	12	11	9.4	8.4	7.7	6.7
1⅛	23	21	18	…	…	…	19	18	16	16	15	13	11	10	9.0	21	19	17	…	…	…	18	16	14	15	13	12	10	9.5	8.4
Two-Leg Bridle or Basket Hitch, 6 × 37 Wire Rope Sling																														
1¼	26	24	21	…	…	…	23	21	18	19	17	15	13	12	10	25	22	20	…	…	…	21	19	17	17	16	14	12	11	9.8
1⅜	32	29	25	…	…	…	28	25	22	22	21	18	16	15	13	30	27	24	…	…	…	26	23	20	21	19	17	15	13	12
1½	38	35	30	…	…	…	33	30	26	27	25	21	19	17	15	35	32	28	…	…	…	30	27	24	25	22	20	17	16	14
1¾	51	47	41	…	…	…	44	41	35	36	33	29	26	24	20	46	43	39	…	…	…	41	37	33	34	30	27	24	21	19
2	66	61	53	…	…	…	57	53	46	47	43	37	33	30	26	62	55	49	…	…	…	53	43	43	43	39	35	31	26	25
2¼	83	76	66	…	…	…	72	66	67	58	54	47	41	38	33	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…

A–socket or swaged terminal attachment; B–mechanical sleeve attachment; C–hand-tucked splice attachment. Data from *Longshoring Industry*, OSHA Safety and Health Standards Digest, OSHA 2232, 1985.

Copyright 2004, Industrial Press, Inc., New York, NY



Wire Rope Fittings

together until the socket is placed over the rope end. The temporary seizing is then removed and the socket located so that the ends of the wires are about even with the upper end of the basket. The opening around the rope at the bottom of the socket is now sealed with putty.

Table 10. Clips Required for Fastening Wire Rope End

Rope Dia., In.	U-Bolt Dia., In.	Min. No. of Clips	Clip Spacing, In.	Rope Dia., In.	U-Bolt Dia., In.	Min. No. of Clips	Clip Spacing, In.	Rope Dia., In.	U-Bolt Dia., In.	Min. No. of Clips	Clip Spacing, In.
3/16	11/32	2	3	3/4	7/8	4	6 3/4	1 5/8	1 3/4	6	13 1/4
1/4	7/16	2	3 1/4	7/8	1	4	8	1 3/4	1 15/16	7	14 1/2
5/16	1/2	2	3 1/4	1	1 1/8	4	8 3/4	2	2 1/8	8	16 1/2
3/8	9/16	2	4	1 1/8	1 1/4	5	9 3/4	2 1/4	2 5/8	8	16 1/2
7/16	5/8	2	4 1/2	1 1/4	1 7/16	5	10 3/4	2 1/2	2 7/8	8	17 3/4
1/2	11/16	3	5	1 3/8	1 1/2	6	11 1/2	…	…	…	…
5/8	3/4	3	5 3/4	1 1/2	1 23/32	6	12 1/2	…	…	…	…

A special high grade pure zinc is used to fill the socket. Babbit metal should not be used as it will not hold properly. For proper fluidity and penetration, the zinc is heated to a tem-

Copyright 2004, Industrial Press, Inc., New York, NY

perature in the 830- to 900-degree F. range. If a pyrometer is not available to measure the temperature of the molten zinc, a dry soft pine stick dipped into the zinc and quickly withdrawn will show only a slight discoloration and no zinc will adhere to it. If the wood chars, the zinc is too hot. The socket is now permitted to cool and the resulting joint is ready for use. When properly prepared, the strength of the joint should be approximately equal to that of the rope itself.

Crane Chain and Hooks

Material for Crane Chains.— The best material for crane and hoisting chains is a good grade of wrought iron, in which the percentage of phosphorus, sulfur, silicon, and other impurities is comparatively low. The tensile strength of the best grades of wrought iron does not exceed 46,000 pounds per square inch, whereas mild steel with about 0.15 per cent carbon has a tensile strength nearly double this amount. The ductility and toughness of wrought iron, however, is greater than that of ordinary commercial steel, and for this reason it is preferable for chains subjected to heavy intermittent strains, because wrought iron will always give warning by bending or stretching, before breaking. Another important reason for using wrought iron in preference to steel is that a perfect weld can be effected more easily. Heat-treated alloy steel is also widely used for chains. This steel contains carbon, 0.30 per cent, max; phosphorus, 0.045 per cent, max; and sulfur, 0.045 per cent, max. The selection and amounts of alloying elements are left to the individual manufacturers.

Strength of Chains.— When calculating the strength of chains it should be observed that the strength of a link subjected to tensile stresses is not equal to twice the strength of an iron bar of the same diameter as the link stock, but is a certain amount less, owing to the bending action caused by the manner in which the load is applied to the link. The strength is also reduced somewhat by the weld. The following empirical formula is commonly used for calculating the breaking load, in pounds, of wrought-iron crane chains: $W = 54{,}000D^2$ in which W = breaking load in pounds and D = diameter of bar (in inches) from which links are made. The working load for chains should not exceed one-third the value of W, and, it is often one-fourth or one-fifth of the breaking load. When a chain is wound around a casting and severe bending stresses are introduced, a greater factor of safety should be used.

Care of Hoisting and Crane Chains.— Chains used for hoisting heavy loads are subject to deterioration, both apparent and invisible. The links wear, and repeated loading causes localized deformations to form cracks that spread until the links fail. Chain wear can be reduced by occasional lubrication. The life of a wrought-iron chain can be prolonged by frequent annealing or normalizing unless it has been so highly or frequently stressed that small cracks have formed. If this condition is present, annealing or normalizing will not "heal" the material, and the links will eventually fracture. To anneal a wrought-iron chain, heat it to cherry-red and allow it to cool slowly. Annealing should be done every six months, and oftener if the chain is subjected to unusually severe service.

Maximum Allowable Wear at Any Point of Link

Chain Size (in.)	Maximum Allowable Wear (in.)	Chain Size (in.)	Maximum Allowable Wear (in.)	Chain Size (in.)	Maximum Allowable Wear (in.)
1/4 (9/32)	3/64	3/4	5/32	1 1/4	1/4
3/8	5/64	7/8	11/64	1 3/8	3/32
1/2	7/64	1	3/16	1 1/2	5/16
5/8	9/64	1 1/8	7/32	1 3/4	11/32

Source: Longshoring Industry, OSHA 2232, 1985.

Chains should be examined periodically for twists, as a twisted chain will wear rapidly. Any links that have worn excessively should be replaced with new ones, so that every link will do its full share of work during the life of the chain, without exceeding the limit of

Copyright 2004, Industrial Press, Inc., New York, NY

safety. Chains for hoisting purposes should be made with short links, so that they will wrap closely around the sheaves or drums without bending. The diameter of the winding drums should be not less than 25 or 30 times the diameter of the iron used for the links. The accompanying table lists the maximum allowable wear for various sizes of chains.

Safe Loads for Ropes and Chains.— Safe loads recommended for wire rope or chain slings depend not only upon the strength of the sling but also upon the method of applying it to the load, as shown by the accompanying table giving safe loads as prepared by OSHA. The loads recommended in this table are more conservative than those usually specified, in order to provide ample allowance for some unobserved weakness in the sling, or the possibility of excessive strains due to misjudgment or accident.

Safe Working Loads in Pounds for Manila Rope and Chains

Diameter of Rope, or Chain Link, Inch	Rope or Chain Vertical			Sling at 60°			Sling at 45°			Sling at 30°		
		Crane Chain			Crane Chain			Crane Chain			Crane Chain	
	Manila Rope	Wrought Iron	Alloy Steel	Manila Rope	Wrought Iron	Alloy Steel	Manila Rope	Wrought Iron	Alloy Steel	Manila Rope	Wrought Iron	Alloy Steel
1/4 [a]	120	1060	3240	204	1835	5640	170	1500	4540	120	1060	3240
5/16 [a]	200	1655	…	346	2865	…	282	2340	…	200	1655	…
3/8	270	2385	6600	467	4200	11,400	380	3370	9300	270	2385	6600
7/16 [a]	350	3250	…	605	5600	…	493	4600	…	350	3250	…
15/32	450	…	…	775	…	…	635	…	…	450	…	…
1/2	530	4200	11,240	915	7400	19,500	798	6000	15,800	530	4200	11,240
9/16 [a]	690	5400	…	1190	9200	…	973	7600	…	690	5400	…
5/8	880	6600	16,500	1520	11,400	28,500	1240	9400	23,300	880	6600	16,500
3/4	1080	9600	23,000	1870	16,600	39,800	1520	13,400	32,400	1080	9600	23,000
13/16	1300	…	…	2250	…	…	1830	…	…	1300	…	…
7/8	1540	13,000	28,600	2660	22,400	49,800	2170	18,400	40,600	1540	13,000	28,600
1	1800	17,000	38,600	3120	29,400	67,000	2540	24,000	54,600	1800	17,000	38,600
1 1/16	2000	…	…	3400	…	…	2800	…	…	2000	…	…
1 1/8	2400	20,000	44,400	4200	34,600	77,000	3400	28,400	63,000	2400	20,000	44,400
1 1/4	2700	24,800	57,400	4600	42,600	99,400	3800	35,000	81,000	2700	24,800	57,400
1 5/16	3000	…	…	5200	…	…	4200	…	…	3000	…	…
1 3/8	…	30,000	67,000	…	51,800	116,000	…	42,200	94,000	…	30,000	67,000
1 1/2	3600	35,600	79,400	6200	61,600	137,000	5000	50,400	112,000	3600	35,600	79,400
1 5/8	4500	41,800	85,000	7800	72,400	147,000	6400	59,000	119,000	4500	41,800	85,000
1 3/4	5200	48,400	95,800	9000	84,000	163,000	7400	68,600	124,000	5200	48,400	95,800
1 7/8	…	55,200	…	…	95,800	…	…	78,200	…	…	55,200	…
2	6200	63,200	…	10,800	109,600	…	8800	89,600	…	6200	63,200	…
2 1/8	7200	…	…	12,400	…	…	10,200	…	…	7200	…	…

[a] These sizes of wrought chain are no longer manufactured in the United States.

Data from *Longshoring Industry*, OSHA Safety and Health Standards Digest, OSHA 2232, 1985.

The working load limit is defined as the maximum load in pounds that should ever be applied to chain, when the chain is new or in "as new" condition, and when the load is uniformly applied in direct tension to a straight length of chain. This limit is also affected by the number of chains used and their configuration. The accompanying table shows the working load limit for various configurations of heat-treated alloy steel chain using a 4 to 1 design factor, which conforms to ISO practice.

Copyright 2004, Industrial Press, Inc., New York, NY

Working Load Limit for Heat-Treated Alloy Steel Chain, pounds

Chain Size (in.)	Single Leg	Double Leg			Triple and Quad Leg		
	90°	60°	45°	30°	60°	45°	30°
1/4	3,600	6,200	5,050	3,600	9,300	7,600	5,400
3/8	6,400	11,000	9,000	6,400	16,550	13,500	9,500
1/2	11,400	19,700	16,100	11,400	29,600	24,200	17,100
5/8	17,800	30,800	25,150	17,800	46,250	37,750	26,700
3/4	25,650	44,400	36,250	25,650	66,650	54,400	38,450
7/8	34,900	60,400	49,300	34,900	90,650	74,000	52,350

Source: The Crosby Group.

Protection from Sharp Corners: When the load to be lifted has sharp corners or edges, as are often encountered with castings, and with structural steel and other similar objects, pads or wooden protective pieces should be applied at the corners, to prevent the slings from being abraded or otherwise damaged where they come in contact with the load. These precautions are especially important when the slings consist of wire cable or fiber rope, although they should also be used even when slings are made of chain. Wooden corner-pieces are often provided for use in hoisting loads with sharp angles. If pads of burlap or other soft material are used, they should be thick and heavy enough to sustain the pressure, and distribute it over a considerable area, instead of allowing it to be concentrated directly at the edges of the part to be lifted.

Strength of Manila Rope

Dia. (in.)	Circum-ference (in.)	Weight of 100 feet of Rope[a] (lb)	New Rope Tensile Strength[b] (lb)	Working Load[c] (lb)	Dia. (in.)	Circum-ference (in.)	Weight of 100 feet of Rope[a] (lb)	New Rope Tensile Strength[b] (lb)	Working Load[c] (lb)
3/16	5/8	1.50	406	41	1 5/16	4	47.8	13,500	1930
1/4	3/4	2.00	540	54	1 1/2	4 1/2	60.0	16,700	2380
5/16	1	2.90	900	90	1 5/8	5	74.5	20,200	2880
3/8	1 1/8	4.10	1220	122	1 3/4	5 1/2	89.5	23,800	3400
7/16	1 1/4	5.25	1580	176	2	6	108	28,000	4000
1/2	1 1/2	7.50	2380	264	2 1/8	6 1/2	125	32,400	4620
9/16	1 3/4	10.4	3100	388	2 1/4	7	146	37,000	5300
5/8	2	13.3	3960	496	2 1/2	7 1/2	167	41,800	5950
3/4	2 1/4	16.7	4860	695	2 5/8	8	191	46,800	6700
13/16	2 1/2	19.5	5850	835	2 7/8	8 1/2	215	52,000	7450
7/8	2 3/4	22.4	6950	995	3	9	242	57,500	8200
1	3	27.0	8100	1160	3 1/4	10	298	69,500	9950
1 1/16	3 1/4	31.2	9450	1350	3 1/2	11	366	82,000	11,700
1 1/8	3 1/2	36.0	10,800	1540	4	12	434	94,500	13,500
1 1/4	3 3/4	41.6	12,200	1740	…	…	…	…	…

[a] Average value is shown; maximum is 5 per cent higher.

[b] Based on tests of new and unused rope of standard construction in accordance with Cordage Institute Standard Test Methods.

[c] These values are for rope in good condition with appropriate splices, in noncritical applications, and under normal service conditions. These values should be reduced where life, limb, or valuable propety are involved, or for exceptional service conditions such as shock loads or sustained loads.

Data from Cordage Institute Rope Specifications for three-strand laid and eight-strand plaited manila rope (standard construction).

Copyright 2004, Industrial Press, Inc., New York, NY

Strength of Nylon and Double Braided Nylon Rope

Dia. (in.)	Circum-ference (in.)	Weight of 100 feet of Rope[a] (lb)	New Rope Tensile Strength[b] (lb)	Working Load[c] (lb)	Dia. (in.)	Circum-ference (in.)	Weight of 100 feet of Rope[a] (lb)	New Rope Tensile Strength[a] (lb)	Working Load[c] (lb)
Nylon Rope									
3/16	5/8	1.00	900	75	1 5/16	4	45.0	38,800	4,320
1/4	3/4	1.50	1,490	124	1 1/2	4 1/2	55.0	47,800	5,320
5/16	1	2.50	2,300	192	1 5/8	5	66.5	58,500	6,500
3/8	1 1/8	3.50	3,340	278	1 3/4	5 1/2	83.0	70,000	7,800
7/16	1 1/4	5.00	4,500	410	2	6	95.0	83,000	9,200
1/2	1 1/2	6.50	5,750	525	2 1/8	6 1/2	109	95,500	10,600
9/16	1 3/4	8.15	7,200	720	2 1/4	7	129	113,000	12,600
5/8	2	10.5	9,350	935	2 1/2	7 1/2	149	126,000	14,000
3/4	2 1/4	14.5	12,800	1,420	2 5/8	8	168	146,000	16,200
13/16	2 1/2	17.0	15,300	1,700	2 7/8	8 1/2	189	162,000	18,000
7/8	2 3/4	20.0	18,000	2,000	3	9	210	180,000	20,000
1	3	26.4	22,600	2,520	3 1/4	10	264	226,000	25,200
1 1/16	3 1/4	29.0	26,000	2,880	3 1/2	11	312	270,000	30,000
1 1/8	3 1/2	34.0	29,800	3,320	4	12	380	324,000	36,000
1 1/4	3 3/4	40.0	33,800	3,760	…	…	…	…	…
Double Braided Nylon Rope (Nylon Cover—Nylon Core)									
1/4	3/4	1.56	1,650	150	1 5/16	4	43.1	44,700	5,590
5/16	1	2.44	2,570	234	1 3/8	4 1/4	47.3	49,000	6,130
3/8	1 1/8	3.52	3,700	336	1 1/2	4 1/2	56.3	58,300	7,290
7/16	1 5/16	4.79	5,020	502	1 5/8	5	66.0	68,300	8,540
1/2	1 1/2	6.25	6,550	655	1 3/4	5 1/2	76.6	79,200	9,900
9/16	1 3/4	7.91	8,270	919	2	6	100	103,000	12,900
5/8	2	9.77	10,200	1,130	2 1/8	6 1/2	113	117,000	14,600
3/4	2 1/4	14.1	14,700	1,840	2 1/4	7	127	131,000	18,700
13/16	2 1/2	16.5	17,200	2,150	2 1/2	7 1/2	156	161,000	23,000
7/8	2 3/4	19.1	19,900	2,490	2 5/8	8	172	177,000	25,300
1	3	25.0	26,000	3,250	3	9	225	231,000	33,000
1 1/16	3 1/4	28.2	29,300	3,660	3 1/4	10	264	271,000	38,700
1 1/8	3 1/2	31.6	32,800	4,100	3 1/2	11	329	338,000	48,300
1 1/4	3 3/4	39.1	40,600	5,080	4	12	400	410,000	58,600

[a] Average value is shown. Maximum for nylon rope is 5 per cent higher; tolerance for double braided nylon rope is ± 5 per cent.

[b] Based on tests of new and unused rope of standard construction in accordance with Cordage Institute Standard Test Methods. For double braided nylon rope these values are minimums and are based on a large number of tests by various manufacturers; these values represent results two standard deviations below the mean. The minimum tensile strength is determined by the formula $1057 \times (\text{linear density})^{0.995}$.

[c] These values are for rope in good condition with appropriate splices, in noncritical applications, and under normal service conditions. These values should be reduced where life, limb, or valuable property are involved, or for exceptional service conditions such as shock loads or sustained loads.

Data from Cordage Institute Specifications for nylon rope (three-strand laid and eight-strand plaited, standard construction) and double braided nylon rope.

Copyright 2004, Industrial Press, Inc., New York, NY

Loads Lifted by Crane Chains.— To find the approximate weight a chain will lift when rove as a tackle, multiply the safe load given in the table *Close-link Hoisting, Sling and Crane Chain* by the number of parts or chains at the movable block, and subtract one-quarter for frictional resistance.

To find the size of chain required for lifting a given weight, divide the weight by the number of chains at the movable block, and add one-third for friction; next find in the column headed "Average Safe Working Load" the corresponding load, and then the corresponding size of chain in the column headed "Size." With the heavy chain or where the chain is unusually long, the weight of the chain itself should also be considered.



Close-link Hoisting, Sling and Crane Chain

Size	Standard Pitch, *P* Inches	Average Weight per Foot, Pounds	Outside Length, *L* Inches	Outside Width, *W* Inches	Average Safe Working Load, Pounds	Proof Test, Pounds[a]	Approximate Breaking Load, Pounds
1/4	25/32	3/4	1 5/16	7/8	1,200	2,500	5,000
5/16	27/32	1	1 1/2	1 1/16	1,700	3,500	7,000
3/8	31/32	1 1/2	1 3/4	1 1/4	2,500	5,000	10,000
7/16	1 5/32	2	2 1/16	1 3/8	3,500	7,000	14,000
1/2	1 11/32	2 1/2	2 3/8	1 11/16	4,500	9,000	18,000
9/16	1 15/32	3 1/4	2 5/8	1 7/8	5,500	11,000	22,000
5/8	1 23/32	4	3	2 1/16	6,700	14,000	27,000
11/16	1 13/16	5	3 1/4	2 1/4	8,100	17,000	32,500
3/4	1 15/16	6 1/4	3 1/2	2 1/2	10,000	20,000	40,000
13/16	2 1/16	7	3 3/4	2 11/16	10,500	23,000	42,000
7/8	2 3/16	8	4	2 7/8	12,000	26,000	48,000
15/16	2 7/16	9	4 3/8	3 1/16	13,500	29,000	54,000
1	2 1/2	10	4 5/8	3 1/4	15,200	32,000	61,000
1 1/16	2 5/8	12	4 7/8	3 5/16	17,200	35,000	69,000
1 1/8	2 3/4	13	5 1/8	3 3/4	19,500	40,000	78,000
1 3/16	3 1/16	14 1/2	5 5/16	3 7/8	22,000	46,000	88,000
1 1/4	3 1/8	16	5 3/4	4 1/8	23,700	51,000	95,000
1 5/16	3 3/8	17 1/2	6 1/8	4 1/4	26,000	54,000	104,000
1 3/8	3 9/16	19	6 7/16	4 9/16	28,500	58,000	114,000
1 7/16	3 11/16	21 1/2	6 11/16	4 3/4	30,500	62,000	122,000
1 1/2	3 7/8	23	7	5	33,500	67,000	134,000
1 9/16	4	25	7 3/8	5 5/16	35,500	70,500	142,000
1 5/8	4 1/4	28	7 3/4	5 1/2	38,500	77,000	154,000
1 11/16	4 1/2	30	8 1/8	5 11/16	39,500	79,000	158,000
1 3/4	4 3/4	31	8 1/2	5 7/8	41,500	83,000	166,000
1 13/16	5	33	8 7/8	6 1/16	44,500	89,000	178,000
1 7/8	5 1/4	35	9 1/4	6 3/8	47,500	95,000	190,000
1 15/16	5 1/2	38	9 5/8	6 9/16	50,500	101,000	202,000
2	5 3/4	40	10	6 3/4	54,000	108,000	216,000
2 1/16	6	43	10 3/8	6 15/16	57,500	115,000	230,000
2 1/8	6 1/4	47	10 3/4	7 1/8	61,000	122,000	244,000
2 3/16	6 1/2	50	11 1/8	7 5/16	64,500	129,000	258,000
2 1/4	6 3/4	53	11 1/2	7 5/8	68,200	136,500	273,000
2 3/8	6 7/8	58 1/2	11 7/8	8	76,000	152,000	304,000
2 1/2	7	65	12 1/4	8 3/8	84,200	168,500	337,000
2 5/8	7 1/8	70	12 5/8	8 3/4	90,500	181,000	362,000
2 3/4	7 1/4	73	13	9 1/8	96,700	193,500	387,000
2 7/8	7 1/2	76	13 1/2	9 1/2	103,000	206,000	412,000
3	7 3/4	86	14	9 7/8	109,000	218,000	436,000

[a] Chains tested to U.S. Government and American Bureau of Shipping requirements.

Copyright 2004, Industrial Press, Inc., New York, NY

Winding Drum Scores for Chain





Chain Size	*A*	*B*	*C*	*D*	Chain Size	*A*	*B*	*C*	*D*
3/8	1 1/2	3/16	9/16	3/16	3/8	1 1/4	11/32	3/16	1
7/16	1 11/16	7/32	5/8	9/32	7/16	1 7/16	3/8	7/32	1 1/8
1/2	1 7/8	1/4	11/16	5/16	1/2	1 9/16	7/16	1/4	1 1/4
9/16	2 1/16	9/32	3/4	11/32	9/16	1 3/4	15/32	9/32	1 3/8
5/8	2 5/16	5/16	13/16	3/8	5/8	1 7/8	17/32	5/16	1 1/2
11/16	2 1/2	11/32	7/8	13/32	11/16	2 1/16	9/16	11/32	1 5/8
3/4	2 11/16	3/8	15/16	7/16	3/4	2 3/16	5/8	3/8	1 3/4
13/16	2 7/8	13/32	1	15/32	13/16	2 3/8	21/32	13/32	1 7/8
7/8	3 1/8	7/16	1 1/16	1/2	7/8	2 1/2	23/32	7/16	2
15/16	3 5/16	15/32	1 1/8	17/32	15/16	2 11/16	3/4	15/32	2 1/8
1	3 1/2	1/2	1 3/16	9/16	1	2 13/16	13/16	1/2	2 1/4

All dimensions are in inches.

Sprocket Wheels for Ordinary Link Chains

Size of Chain		3/16	1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
Length of Link		1 3/8	1 1/2	1 3/4	2	2 1/4	2 1/2	2 7/8	3 1/4	3 1/2	3 3/4	4	4 1/4	4 1/2	4 3/4
Width of Link		13/16	1	1 3/16	1 3/8	1 9/16	1 3/4	1 15/16	2 1/8	2 5/16	2 1/2	2 11/16	3	3 1/4	3 1/2
	X	1/16	3/32	3/32	3/32	3/32	3/32	1/16	1/16	1/16	1/16	1/16	1/16	1/16	1/16
	y	3/32	3/32	3/32	3/32	3/32	1/16	1/16	1/16	1/16	1/16	1/16	1/16	1/16	…
No. of Teeth	Angle α	D = Pitch Diameter in Inches													
7	12°51′	4.50	4.50	5.06	5.63	6.18	6.76	7.88	9.01	9.58	10.14	10.71	11.27	11.84	12.40
8	11°15′	5.13	5.13	5.77	6.42	7.06	7.71	8.97	10.27	10.91	11.56	12.20	12.85	13.50	14.13
9	10°0′	5.76	5.76	6.48	7.21	7.74	8.65	10.08	11.53	12.26	12.98	13.72	14.43	15.15	15.87
10	9°0′	6.40	6.40	7.18	8.00	8.79	9.61	11.19	12.80	13.61	14.40	15.21	16.01	16.81	17.61
11	8°11′	7.03	7.03	7.91	8.79	9.67	10.55	12.30	14.07	14.95	15.83	16.71	17.55	18.47	19.35
12	7°30′	7.66	7.66	8.62	9.59	10.53	11.49	13.41	15.33	16.29	17.26	18.20	19.17	20.13	21.09
13	6°55′	8.29	8.29	9.33	10.38	11.41	12.45	14.52	16.60	17.65	18.68	19.72	20.76	21.80	22.84
14	6°25′	8.93	8.93	10.05	11.17	12.28	13.40	15.63	17.90	18.99	20.06	21.23	22.35	23.46	24.58
15	6°0′	9.57	9.57	10.76	11.96	13.16	14.35	16.74	19.14	20.34	21.54	22.74	23.93	25.13	26.33
16	5°37′	10.20	10.20	11.47	12.76	14.03	15.30	17.85	20.41	21.69	22.97	24.24	25.52	26.80	28.08
17	5°17′	10.84	10.84	12.19	13.56	14.90	16.26	18.97	21.68	23.04	24.40	25.75	27.11	28.47	29.83
18	5°0′	11.47	11.47	12.91	14.36	15.78	17.21	20.08	22.95	24.34	25.83	27.26	28.70	30.14	31.57
19	4°44′	12.11	12.11	13.62	15.16	16.65	18.16	21.19	24.22	25.73	27.26	28.77	30.29	31.80	33.31
20	4°30′	12.75	12.75	14.34	15.96	17.53	19.12	22.30	25.50	27.09	28.69	30.28	31.88	33.46	35.06
21	4°17′	13.38	13.38	15.05	16.74	18.40	20.07	23.42	26.77	28.44	30.12	31.79	33.46	35.13	36.81
22	4°6′	14.02	14.02	15.77	17.53	19.27	21.03	24.53	28.03	29.79	31.55	33.30	35.04	36.83	38.56
23	3°55′	14.66	14.66	16.49	18.32	20.15	21.98	25.64	29.31	31.14	32.97	34.81	36.63	38.48	40.30
24	3°45′	15.29	15.29	17.20	19.11	21.02	22.94	26.76	30.58	32.49	34.41	36.32	38.23	40.15	…
25	3°36′	15.93	15.93	17.92	19.90	21.90	23.89	27.87	31.85	33.84	35.84	37.83	39.82	…	…
26	3°28′	16.56	16.56	18.62	20.70	22.77	24.85	28.98	33.13	35.20	37.27	39.34	41.41	…	…
27	3°20′	17.20	17.20	19.34	21.50	23.65	25.80	30.10	34.40	36.55	38.70	40.85	…	…	…
28	3°13′	17.84	17.84	20.06	22.29	24.52	26.75	31.21	35.67	37.90	40.04	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Sprocket Wheels for Ordinary Link Chains *(Continued)*



Additional Tables

Dimensions of Forged Round Pin, Screw Pin, and Bolt Type Chain Shackles and Bolt Type Anchor Shackles



Working Load Limit (tons)	Nominal Shackle Size	A	B	C	D	E	F	G	H	I
½	¼	7/8	15/16	5/16	11/16	…	…	…	…	…
¾	5/16	1 1/32	17/32	3/8	13/16	…	…	…	…	…
1	3/8	1¼	21/32	7/16	31/32	…	…	…	…	…
1½	7/16	1 7/16	23/32	½	1 1/16	…	…	…	…	…
2	½	1 5/8	13/16	5/8	1 3/16	1 7/8	1 5/8	13/16	5/8	1 3/16
3¼	5/8	2	1 1/16	¾	1 9/16	2 3/8	2	1 1/16	¾	1 9/16
4¾	¾	2 3/8	1¼	7/8	1 7/8	2 13/16	2 3/8	1¼	7/8	1 7/8
6½	7/8	2 13/16	1 7/16	1	2 1/8	3 5/16	2 13/16	1 7/16	1	2 1/8
8½	1	3 3/16	1 11/16	1 1/8	2 3/8	3¾	3 3/16	1 11/16	1 1/8	2 3/8
9½	1 1/8	3 9/16	1 13/16	1¼	2 5/8	4¼	3 9/16	1 13/16	1¼	2 5/8
12	1¼	3 15/16	2 1/32	1 3/8	3	4 11/16	3 15/16	2 1/32	1 3/8	3
13½	1 3/8	4 3/8	2¼	1½	3 5/16	5 3/16	4 3/8	2¼	1½	3 5/16
17	1½	4 13/16	2 3/8	1 5/8	3 5/8	5¾	4 13/16	2 3/8	1 5/8	3 5/8
25	1 3/4	5 3/4	2 7/8	2	4 1/8	7	5 3/4	2 7/8	2	4 1/8
35	2	6¾	3¼	2¼	5	7¾	6¾	3¼	2¼	5

All dimensions are in inches. Load limits are in tons of 2000 pounds.
Source: The Crosby Group.

Copyright 2004, Industrial Press, Inc., New York, NY



Eye Hook



Eye Hook With Latch Assembled



Swivel Hook



Swivel Hook With Latch Assembled

Dimensions of Crane Hooks

Feature	Capacity of Hook in Tons (tons of 2000 lbs)											
	1.1	1.65	2.2	3.3	4.95	7.7	12.1	16.5	24.2	33	40.7	49.5
	Dimensions for Eye Hooks											
A	1.47	1.75	2.03	2.41	2.94	3.81	4.69	5.38	6.62	7.00	8.50	9.31
B	0.75	0.91	1.12	1.25	1.56	2.00	2.44	2.84	3.50	3.50	4.50	4.94
D	2.88	3.19	3.62	4.09	4.94	6.50	7.56	8.69	11.00	13.62	14.06	15.44
E	0.94	1.03	1.06	1.22	1.50	1.88	2.25	2.50	3.38	4.00	4.25	4.75
G	0.75	0.84	1.00	1.12	1.44	1.81	2.25	2.59	3.00	3.66	4.56	5.06
H	0.81	0.94	1.16	1.31	1.62	2.06	2.62	2.94	3.50	4.62	5.00	5.50
K	0.56	0.62	0.75	0.84	1.12	1.38	1.62	1.94	2.38	3.00	3.75	4.12
L	4.34	4.94	5.56	6.40	7.91	10.09	12.44	13.94	17.09	19.47	24.75	27.38
R	3.22	3.66	4.09	4.69	5.75	7.38	9.06	10.06	12.50	14.06	18.19	20.12
T	0.81	0.81	0.84	1.19	1.38	1.78	2.12	2.56	2.88	3.44	3.88	4.75
O	0.88	0.97	1.00	1.12	1.34	1.69	2.06	2.25	3.00	3.62	3.75	4.25
	Dimensions for Swivel Hooks											
A	2	2.50	3	3	3.50	4.50	5	5.63	7	7	…	…
B	0.94	1.31	1.63	1.56	1.75	2.31	2.38	2.69	4.19	4.19	…	…
C	1.25	1.50	1.75	1.75	2	2.50	2.75	3.13	4	4	…	…
D	2.88	3.19	3.63	4.09	4.94	6.5	7.56	8.69	11	13.63	…	…
E	0.94	1.03	1.06	1.22	1.5	1.88	2.25	2.5	3.38	4	…	…
L	5.56	6.63	7.63	8.13	9.59	12.41	14.50	15.88	21.06	23.22	…	…
R	4.47	5.28	6.02	6.38	7.41	9.59	11.13	12.03	16.56	18.06	…	…
S	0.38	0.50	0.63	0.63	0.75	1	1.13	1.25	1.5	1.5	…	…
T	0.81	0.81	0.84	1.19	1.38	1.78	2.13	2.56	2.88	3.44	…	…
O	0.88	0.97	1	1.13	1.34	1.69	2.06	2.25	3	3.63	…	…

Source: The Crosby Group. All dimensions are in inches. Hooks are made of alloy steel, quenched and tempered. For swivel hooks, the data are for a bail of carbon steel. The ultimate load is four times the working load limit (capacity). The swivel hook is a positioning device and is not intended to rotate under load; special load swiveling hooks must be used in such applications.

Method of Making an Eye-splice.— When a loop is formed at the end of a rope by splicing the free end to the main or standing part of the rope, this is known as an *eye-splice*. The end of the rope is first unlaid about as far as it would be for making a short splice. After bending the end around to form a loop of the required size, the middle strand *a*, Fig. 8a, is tucked under a strand on the main part of the rope. The strand *b* is next inserted from the rear side under the strand on the main part which is just above the strand under which *a* was inserted. Since strand *b* is pushed under the strand on the main part from the rear side, it will come out at the point where strand *a* went in, as Fig. 8b. The third strand *c* is now passed over the strand under which strand *a* was inserted, and then under the next successive one, as Fig. 8c. These three strands are next pulled taut and then about one-third of the fiber should be cut from them; they are next tucked away by passing a strand over its adjoining one and under the next successive strand. The reason for cutting away part of the fiber or yarns is to reduce the size of the splice and give it a neater appearance. By gradually thinning out the fiber, the over-lapping strands may be given a gradual taper, as Fig. 8d which shows the completed eye-splice.

Copyright 2004, Industrial Press, Inc., New York, NY



Hot Dip Galvanized, Forged Steel Eye-bolts

Shank		Eye Dia.		Safe Load[a] (tons)	Shank		Eye Dia.		Safe Load[a] (tons)
D	C	A	B		D	C	A	B	
Regular Pattern									
1/4	2	1/2	1	0.25	3/4	4 1/2	1 1/2	3	2.6
1/4	4	1/2	1	0.25	3/4	6	1 1/2	3	2.6
5/16	2 1/4	5/8	1 1/4	0.4	3/4	8	1 1/2	3	2.6
5/16	4 1/4	5/8	1 1/4	0.4	3/4	10	1 1/2	3	2.6
3/8	2 1/2	3/4	1 1/2	0.6	3/4	10	1 1/2	3	2.6
3/8	4 1/2	3/4	1 1/2	0.6	3/4	10	1 1/2	3	2.6
3/8	6	3/4	1 1/2	0.6	7/8	5	1 3/4	3 1/2	3.6
1/2	3 1/4	1	2	1.1	7/8	8	1 3/4	3 1/2	3.6
1/2	6	1	2	1.1	7/8	10	1 3/4	3 1/2	3.6
1/2	8	1	2	1.1	1	6	2	4	5
1/2	10	1	2	1.1	1	9	2	4	5
1/2	12	1	2	1.1	1	10	2	4	5
5/8	4	1 1/4	2 1/2	1.75	1	10	2	4	5
5/8	6	1 1/4	2 1/2	1.75	1 1/4	8	2 1/2	5	7.6
5/8	8	1 1/4	2 1/2	1.75	1 1/4	10	2 1/2	5	7.6
5/8	10	1 1/4	2 1/2	1.75	1 1/4	10	2 1/2	5	7.6
5/8	12	1 1/4	2 1/2	1.75	…	…	…	…	…
Shoulder Pattern									
1/4	2	1/2	7/8	0.25	5/8	6	1 1/4	2 1/4	1.75
1/4	4	1/2	7/8	0.25	3/4	4 1/2	1 1/2	2 3/4	2.6
5/16	2 1/4	5/8	1 1/8	0.4	3/4	6	1 1/2	2 3/4	2.6
5/16	4 1/4	5/8	1 1/8	0.4	7/8	5	1 3/4	3 1/4	3.6
3/8	2 1/2	3/4	1 3/8	0.6	1	6	2	3 3/4	5
3/8	4 1/2	3/4	1 3/8	0.6	1	9	2	3 3/4	5
1/2	3 1/4	1	1 3/4	1.1	1 1/4	8	2 1/2	4 1/2	7.6
1/2	6	1	1 3/4	1.1	1 1/4	12	2 1/2	4 1/2	7.6
5/8	4	1 1/4	2 1/4	1.75	1 1/2	15	3	5 1/2	10.7

[a] The ultimate or breaking load is 5 times the safe working load.
All dimensions are in inches. Safe loads are in tons of 2000 pounds.
Source: The Crosby Group.

Fig. 8a. Eye -Splice

Fig. 8b. Eye -Splice

Fig. 8c. Eye -Splice

Fig. 8d. Eye -Splice

Copyright 2004, Industrial Press, Inc., New York, NY

Eye Nuts and Lift Eyes



Eye Nut



Lifting Eye

Eye Nuts

The general function of eye nuts is similar to that of eye-bolts. Eye nuts are utilized for a variety of applications in either the swivel or tapped design.

M	A	C	D	E	F	S	T	Working Load Limit (lbs)[a]
1/4	1 1/4	3/4	1 1/16	21/32	1/2	1/4	1 11/16	520
5/16	1 1/4	3/4	1 1/16	21/32	1/2	1/4	1 11/16	850
3/8	1 5/8	1	1 1/4	3/4	9/16	5/16	2 1/16	1,250
7/16	2	1 1/4	1 1/2	1	13/16	3/8	2 1/2	1,700
1/2	2	1 1/4	1 1/2	1	13/16	3/8	2 1/2	2,250
5/8	2 1/2	1 1/2	2	1 3/16	1	1/2	3 3/16	3,600
3/4	3	1 3/4	2 3/8	1 3/8	1 1/8	5/8	3 7/8	5,200
7/8	3 1/2	2	2 5/8	1 5/8	1 5/16	3/4	4 5/16	7,200
1	4	2 1/4	3 1/16	1 7/8	1 9/16	7/8	5	10,000
1 1/8	4	2 1/4	3 1/16	1 7/8	1 9/16	7/8	5	12,300
1 1/4	4 1/2	2 1/2	3 1/2	1 15/16	1 7/8	1	5 3/4	15,500
1 3/8	5	2 3/4	3 3/4	2	2	1 1/8	6 1/4	18,500
1 1/2	5 5/8	3 1/8	4	2 3/8	2 1/4	1 1/4	6 3/4	22,500
2	7	4	6 1/4	4	3 3/8	1 1/2	10	40,000

[a] Data for eye nuts are for hot dip galvanized, quenched, and tempered forged steel.

Lifting Eyes

A	C	D	E	F	G	H	L	S	T	Working Load Limit Threaded (lbs)[a]
1 1/4	3/4	1 1/16	19/32	1/2	3/8	5/16	11/16	1/4	2 3/8	850
1 5/8	1	1 1/4	3/4	9/16	1/2	3/8	15/16	5/16	3	1,250
2	1 1/4	1 1/2	1	13/16	5/8	1/2	1 1/4	3/8	3 3/4	2,250
2 1/2	1 1/2	2	1 3/16	1	11/16	5/8	1 1/2	1/2	4 11/16	3,600
3	1 3/4	2 3/8	1 3/8	1 1/8	7/8	3/4	1 3/4	5/8	5 5/8	5,200
3 1/2	2	2 5/8	1 5/8	1 5/16	15/16	7/8	2	3/4	6 5/16	7,200
4	2 1/4	3 1/16	1 7/8	1 9/16	1 1/16	1	2 1/16	7/8	7 1/16	10,000
4 1/2	2 1/2	3 1/2	1 15/16	1 7/8	1 1/4	1 1/8	2 1/2	1	8 1/4	12,500
5 5/8	3 1/8	4	2 3/8	2 3/8	1 1/2	1 3/8	2 15/16	1 1/4	9 11/16	18,000

[a] Data for lifting eyes are for quenched and tempered forged steel.

All dimensions are in inches. *Source:* The Crosby Group.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

PROPERTIES, TREATMENT, AND TESTING OF MATERIALS

THE ELEMENTS, HEAT, MASS, AND WEIGHT

398 The Elements
399 Latent Heat
399 Specific Heat
402 Coefficient of Thermal Expansion
403 Ignition Temperatures
403 Thermal Properties of Metals
405 Adjusting Length for Temperature
405 Length and Radius Change Due to Temperature
407 Specific Gravity
409 Weights and Volumes of Fuels
409 Weight of Natural Piles
410 Earth or Soil Weight
410 Molecular Weight
410 Mol

PROPERTIES OF WOOD, CERAMICS, PLASTICS, METALS, WATER, AND AIR

411 Properties of Wood
411 Mechanical Properties
412 Weight of Wood
413 Density of Wood
413 Machinability of Wood
Properties of
415 Ceramics
416 Plastics
417 Investment Casting Alloys
419 Powdered Metals
420 Elastic Properties of Materials
421 Tensile Strength of Spring Wire
421 Temperature Effects on Strength
422 Pressure and Flow of Water
422 Water Pressure
423 Flow of Water in Pipes
424 Buoyancy
425 Flow through Nozzle
427 Friction Loss
428 Properties of Air
428 Volumes and Weights
429 Density of Air
430 Expansion and Compression
432 Horsepower Required to Compress Air
432 Continuity Equation
436 Flow of Air in Pipes
436 Flow of Compressed Air in Pipes

STANDARD STEELS

438 Properties, Compositions, and Applications
438 Standard Steel Classification
440 Numbering Systems
440 Unified Numbering System
441 Standard Steel Numbering System
441 Binary, Ternary and Quarternary
441 Damascus Steel
442 AISI-SAE Numbers for Steels
443 AISI-SAE Designation System
444 Composition of Carbon Steels
446 Composition of Alloy Steels
448 Composition of Stainless Steels
449 Thermal Treatments of Steel
450 Applications of Steels
452 Carbon Steels
455 Carburizing Grade Alloy Steels
456 Hardenable Grade Alloy Steels
457 Characteristics of Stainless Steels
460 Chromium-Nickel Austenitic Steels
462 High-Strength, Low-Alloy Steels
464 Mechanical Properties of Steels

TOOL STEELS

475 Overview
475 Properties of Tool Steels
478 Tool Faults, Failures and Cures
479 Tool Steel Properties
481 Classification
482 Tool Steel Selection
488 High-Speed Tool Steels
488 Molybdenum-Type
490 Tungsten-Type
491 Hot-Work Tool Steels
493 Tungsten-Types
493 Molybdenum-Types
494 Cold-Work Tool Steels
494 Oil-Hardening Types
495 Air-Hardening Types
497 Shock-Resisting Tool Steels
497 Mold Steels
499 Special-Purpose Tool Steels
499 Water-Hardening Tool Steels
501 Forms of Tool Steel
502 Tolerances of Dimensions
502 Allowances for Machining
502 Decarburization Limits

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

PROPERTIES, TREATMENT, AND TESTING OF MATERIALS

HARDENING, TEMPERING, AND ANNEALING

503 Heat Treatment Of Standard Steels
503 Heat-Treating Definitions
507 Hardness and Hardenability
509 Case Hardening
511 Slow Cooling
511 Rapid Cooling or Quenching
512 Heat-Treating Furnaces
513 Physical Properties
513 Hardening
515 Hardening Temperatures
516 Heating Steel in Liquid Baths
516 Salt Baths
517 Quenching Baths
517 Hardening or Quenching Baths
518 Quenching in Water
518 Quenching in Molten Salt Bath
519 Tanks for Quenching Baths
521 Tempering
522 Color as Temperature Indicator
526 Case Hardening
526 Carburization
527 Pack-Hardening
527 Cyanide Hardening
527 Nitriding Process
529 Flame Hardening
529 Induction Hardening
532 SAE Carbon Steels
533 SAE Alloy Steels
534 Metallography
536 Chromium-Ni Austenitic Steels
537 Stainless Chromium Steels
538 Heat Treating High-Speed Steels
538 Tungsten High-Speed Steels
541 Molybdenum High-Speed Steels
543 Nitriding High-Speed Steel
544 Subzero Treatment of Steel
547 Testing the Hardness of Metals
547 Brinell Hardness Test
548 Rockwell Hardness Test
548 Shore's Scleroscope
548 Vickers Hardness Test
549 Knoop Hardness Numbers
549 Monotron Hardness Indicator
549 Keep's Test
550 Comparative Hardness Scales

NONFERROUS ALLOYS

554 Strength of Nonferrous Metals
555 Copper and Copper Alloys
555 Cast Copper Alloys
560 Wrought Copper Alloys
569 Copper–Silicon and Copper–Beryllium Alloys
569 Everdur
571 Aluminum and Aluminum Alloys
571 Characteristics
572 Temper Designations
575 Alloy Designation Systems
575 Composition of Casting Alloys
576 Properties of Casting Alloys
578 Composition of Wrought Alloys
580 Properties of Wrought Alloys
584 Clad Aluminum Alloys
584 Principal Alloy Groups
585 Type Metal
586 Magnesium Alloys
586 Alloy and Temper Designation
589 Nickel and Nickel Alloys
589 Characteristics
589 Properties of Nickel Alloys
589 Titanium and Titanium Alloys
591 Mechanical Properties Table

PLASTICS

592 Properties of Plastics
592 Characteristics of Plastics
593 Plastics Materials
593 Structures
593 Mixtures
594 Physical Properties
596 Mechanical Properties
601 Strength and Modulus
602 Time Related Properties
603 Thermal Properties
605 Electrical Properties
607 Chemical Resistance
607 Design Analysis
607 Structural Analysis
609 Design Stresses
610 Thermal Stresses
611 Design for Injection Moldings
615 Design for Assembly
620 Assembly with Fasteners
621 Machining Plastics
624 Development of Prototypes
625 Plastics Gearing

Copyright 2004, Industrial Press, Inc., New York, NY

THE ELEMENTS, HEAT, MASS, AND WEIGHT

Table 1. The Elements — Symbols, Atomic Numbers and Weights, Melting Points

Name of Element	Symbol	Atomic Num.	Atomic Weight	Melting Point, °C	Name of Element	Symbol	Atomic Num.	Atomic Weight	Melting Point, °C
Actinium	Ac	89	227.028	1050	Neon	Ne	10	20.1179	−248.67
Aluminum	Al	13	26.9815	660.37	Neptunium	Np	93	237.048	640 ± 1
Americium	Am	95	(243)	994 ± 4	Nickel	Ni	28	58.69	1453
Antimony	Sb	51	121.75	630.74	Niobium	Nb	41	92.9064	2468 ± 10
Argon	A	18	39.948	−189.2	Nitrogen	N	7	14.0067	−209.86
Arsenic	As	33	74.9216	817[a]	Nobelium	No	102	(259)	…
Astatine	At	85	(210)	302	Osmium	Os	76	190.2	3045 ± 30
Barium	Ba	56	137.33	725	Oxygen	O	8	15.9994	−218.4
Berkelium	Bk	97	(247)	…	Palladium	Pd	46	106.42	1554
Beryllium	Be	4	9.01218	1278 ± 5	Phosphorus	P	15	30.9738	44.1
Bismuth	Bi	83	208.980	271.3	Platinum	Pt	78	195.08	1772
Boron	B	5	10.81	2079	Plutonium	Pu	94	(244)	641
Bromine	Br	35	79.904	−7.2	Polonium	Po	84	(209)	254
Cadmium	Cd	48	112.41	320.9	Potassium	K	19	39.0938	63.25
Calcium	Ca	20	40.08	839 ± 2	Praseodymium	Pr	59	140.908	931 ± 4
Californium	Cf	98	(251)	…	Promethium	Pm	61	(145)	1080[b]
Carbon	C	6	12.011	3652[c]	Protactinium	Pa	91	231.0359	1600
Cerium	Ce	58	140.12	798 ± 2	Radium	Ra	88	226.025	700
Cesium	Cs	55	132.9054	28.4 ± 0.01	Radon	Rn	86	(222)	−71
Chlorine	Cl	17	35.453	−100.98	Rhenium	Re	75	186.207	3180
Chromium	Cr	24	51.996	1857 ± 20	Rhodium	Rh	45	102.906	1965 ± 3
Cobalt	Co	27	58.9332	1495	Rubidium	Rb	37	85.4678	38.89
Copper	Cu	29	63.546	1083.4 ± 0.2	Ruthenium	Ru	44	101.07	2310
Curium	Cm	96	(247)	1340 ± 40	Samarium	Sm	62	150.36	1072 ± 5
Dysprosium	Dy	66	162.5	1409	Scandium	Sc	21	44.9559	1539
Einsteinium	Es	99	(252)	…	Selenium	Se	34	78.96	217
Erbium	Er	68	167.26	1522	Silicon	Si	14	28.0855	1410
Europium	Eu	63	151.96	822 ± 5	Silver	Ag	47	107.868	961.93
Fermium	Fm	100	(257)	…	Sodium	Na	11	22.9898	97.81 ± 0.03
Fluorine	F	9	18.9984	−219.62	Strontium	Sr	38	87.62	769
Francium	Fr	87	(223)	27[b]	Sulfur	S	16	32.06	112.8
Gadolinium	Gd	64	157.25	1311 ± 1	Tantalum	Ta	73	180.9479	2996
Gallium	Ga	31	69.72	29.78	Technetium	Tc	43	(98)	2172
Germanium	Ge	32	72.59	937.4	Tellurium	Te	52	127.60	449.5 ± 0.3
Gold	Au	79	196.967	1064.434	Terbium	Tb	65	158.925	1360 ± 4
Hafnium	Hf	72	178.49	2227 ± 20	Thallium	Tl	81	204.383	303.5
Helium	He	2	4.00260	−272.2[d]	Thorium	Th	90	232.038	1750
Holmium	Ho	67	164.930	1470	Thulium	Tm	69	168.934	1545 ± 15
Hydrogen	H	1	1.00794	−259.14	Tin	Sn	50	118.71	231.9681
Indium	In	49	114.82	156.61	Titanium	Ti	22	47.88	1660 ± 10
Iodine	I	53	126.905	113.5	Tungsten	W	74	183.85	3410 ± 20
Iridium	Ir	77	192.22	2410	Unnilhexium	Unh	106	(266)	…
Iron	Fe	26	55.847	1535	Unnilnonium	Unn	109	(266)	…
Krypton	Kr	36	83.80	−156.6	Unniloctium	Uno	108	(265)	…
Lanthanum	La	57	138.906	920 ± 5	Unnilpentium	Unp	105	(262)	…
Lawrencium	Lw	103	(260)	…	Unnilquadium	Unq	104	(261)	…
Lead	Pb	82	207.2	327.502	Unnilseptium	Uns	107	(261)	…
Lithium	Li	3	6.941	180.54	Uranium	U	92	238.029	1132 ± 0.8
Lutetium	Lu	71	174.967	1656 ± 5	Vanadium	V	23	50.9415	1890 ± 10
Magnesium	Mg	12	24.305	648.8 ± 0.5	Xenon	Xe	54	131.29	−111.9
Manganese	Mn	25	54.9380	1244 ± 2	Ytterbium	Yb	70	173.04	824 ± 5
Mendelevium	Md	101	(258)	…	Yttrium	Y	39	88.9059	1523 ± 8
Mercury	Hg	80	200.59	−38.87	Zinc	Zn	30	65.39	419.58
Molybdenum	Mo	42	95.94	2617	Zirconium	Zr	40	91.224	1852 ± 2
Neodymium	Nd	60	144.24	1010					

[a] At 28 atm.
[b] Approximate.
[c] Sublimates.
[d] At 26 atm.

Notes: Values in parentheses are atomic weights of the most stable known isotopes. Melting points at standard pressure except as noted.

Copyright 2004, Industrial Press, Inc., New York, NY

Heat and Combustion Related Properties

Latent Heat.— When a body changes from the solid to the liquid state or from the liquid to the gaseous state, a certain amount of heat is used to accomplish this change. This heat does not raise the temperature of the body and is called latent heat. When the body changes again from the gaseous to the liquid, or from the liquid to the solid state, it gives out this quantity of heat. The *latent heat of fusion* is the heat supplied to a solid body at the melting point; this heat is absorbed by the body although its temperature remains nearly stationary during the whole operation of melting. The *latent heat of evaporation* is the heat that must be supplied to a liquid at the boiling point to transform the liquid into a vapor. The latent heat is generally given in British thermal units per pound. When it is said that the latent heat of evaporation of water is 966.6, this means that it takes 966.6 heat units to evaporate 1 pound of water after it has been raised to the boiling point, 212°F.

When a body changes from the solid to the gaseous state without passing through the liquid stage, as solid carbon dioxide does, the process is called *sublimation*.

Table 2. Latent Heat of Fusion

Substance	Btu per Pound	Substance	Btu per Pound	Substance	Btu per Pound
Bismuth	22.75	Paraffine	63.27	Sulfur	16.86
Beeswax	76.14	Phosphorus	9.06	Tin	25.65
Cast iron, gray	41.40	Lead	10.00	Zinc	50.63
Cast iron, white	59.40	Silver	37.92	Ice	144.00

Table 3. Latent Heat of Evaporation

Liquid	Btu per Pound	Liquid	Btu per Pound	Liquid	Btu per Pound
Alcohol, ethyl	371.0	Carbon bisulfide	160.0	Turpentine	133.0
Alcohol, methyl	481.0	Ether	162.8	Water	966.6
Ammonia	529.0	Sulfur dioxide	164.0		

Table 4. Boiling Points of Various Substances at Atmospheric Pressure

Substance	Boiling Point, °F	Substance	Boiling Point, °F	Substance	Boiling Point, °F
Aniline	363	Chloroform	140	Saturated brine	226
Alcohol	173	Ether	100	Sulfur	833
Ammonia	–28	Linseed oil	597	Sulfuric acid	590
Benzine	176	Mercury	676	Water, pure	212
Bromine	145	Napthaline	428	Water, sea	213.2
Carbon bisulfide	118	Nitric acid	248	Wood alcohol	150
		Oil of turpentine	315		

Specific Heat.— The specific heat of a substance is the ratio of the heat required to raise the temperature of a certain weight of the given substance 1°F, to the heat required to raise the temperature of the same weight of water 1°F. As the specific heat is not constant at all temperatures, it is generally assumed that it is determined by raising the temperature from 62 to 63°F. For most substances, however, specific heat is practically constant for temperatures up to 212°F.

In metric units, specific heat is defined as the ratio of the heat needed to raise the temperature of a mass by 1°C, to the heat needed to raise the temperature of the same mass of water by 1°C. In the metic system, heat is measued in calories (cal), mass is in grams (g), and measurements usually taken at 15°C.

Because specific heat is a dimensionless ratio, the values given in the table that follows are valid in both the US system and the metric system.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Average Specific Heats (Btu/lb-°F) of Various Substances

Substance	Specific Heat	Substance	Specific Heat
Alcohol (absolute)	0.700	Lead	0.031
Alcohol (density 0.8)	0.622	Lead (fluid)	0.037
Aluminum	0.214	Limestone	0.217
Antimony	0.051	Magnesia	0.222
Benzine	0.450	Marble	0.210
Brass	0.094	Masonry, brick	0.200
Brickwork	0.200	Mercury	0.033
Cadmium	0.057	Naphtha	0.310
Carbon	0.204	Nickel	0.109
Charcoal	0.200	Oil, machine	0.400
Chalk	0.215	Oil, olive	0.350
Coal	0.240	Paper	0.32
Coke	0.203	Phosphorus	0.189
Copper, 32° to 212° F	0.094	Platinum	0.032
Copper, 32° to 572° F	0.101	Quartz	0.188
Corundum	0.198	Sand	0.195
Ether	0.503	Silica	0.191
Fusel oil	0.564	Silver	0.056
Glass	0.194	Soda	0.231
Gold	0.031	Steel, high carbon	0.117
Graphite	0.201	Steel, mild	0.116
Ice	0.504	Stone (generally)	0.200
Iron, cast	0.130	Sulfur	0.178
Iron, wrought, 32° to 212° F	0.110	Sulfuric acid	0.330
32° to 392° F	0.115	Tin (solid)	0.056
32° to 572° F	0.122	Tin (fluid)	0.064
32° to 662° F	0.126	Turpentine	0.472
Iron, at high temperatures:		Water	1.000
1382° to 1832° F	0.213	Wood, fir	0.650
1750° to 1840° F	0.218	Wood, oak	0.570
1920° to 2190° F	0.199	Wood, pine	0.467
Kerosene	0.500	Zinc	0.095

Table 6. Specific Heat of Gases (Btu/lb-°F)

Gas	Constant Pressure	Constant Volume	Gas	Constant Pressure	Constant Volume
Acetic acid	0.412	…	Chloroform	0.157	…
Air	0.238	0.168	Ethylene	0.404	0.332
Alcohol	0.453	0.399	Hydrogen	3.409	2.412
Ammonia	0.508	0.399	Nitrogen	0.244	0.173
Carbonic acid	0.217	0.171	Oxygen	0.217	0.155
Carbonic oxide	0.245	0.176	Steam	0.480	0.346
Chlorine	0.121	…			

Heat Loss from Uncovered Steam Pipes.— The loss of heat from a bare steam or hot-water pipe varies with the temperature difference of the inside the pipe and that of the surrounding air. The loss is 2.15 Btu per hour, per square foot of pipe surface, per degree F of temperature difference when the latter is 100 degrees; for a difference of 200 degrees, the loss is 2.66 Btu; for 300 degrees, 3.26 Btu; for 400 degrees, 4.03 Btu; for 500 degrees, 5.18 Btu. Thus, if the pipe area is 1.18 square feet per foot of length, and the temperature difference 300°F, the loss per hour per foot of length = $1.18 \times 300 \times 3.26 = 1154$ Btu.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Values of Thermal Conductivity (*k*) and of Conductance (*C*) of Common Building and Insulating Materials

Type of Material	Thickness, in.	*k* or *C*[a]	Type of Material	Thickness, in.	*k* or *C*[a]	Max. Temp.,° F	Density, lb per cu. ft.	*k*[a]
BUILDING			BUILDING (*Continued*)					
Batt:	…	…	Siding:	…	…	…	…	…
Mineral Fiber	2–2¾	0.14	Metal[b]	Avg.	1.61	…	…	…
Mineral Fiber	3–3½	0.09	Wood, Med. Density	7/16	1.49	…	…	…
Mineral Fiber	3½–6½	0.05	Stone:	…	…	…	…	…
Mineral Fiber	6–7	0.04	Lime or Sand	1	12.50	…	…	…
Mineral Fiber	8½	0.03	Wall Tile:	…	…	…	…	…
Block:	…	…	Hollow Clay, 1-Cell	4	0.9	…	…	…
Cinder	4	0.90	Hollow Clay, 2-Cell	8	0.54	…	…	…
Cinder	8	0.58	Hollow Clay, 3-Cell	12	0.40	…	…	…
Cinder	12	0.53	Hollow Gypsum	Avg.	0.7	…	…	…
Block:	…	…	INSULATING					
Concrete	4	1.40	Blanket, Mineral Fiber:	…	…	…	…	…
Concrete	8	0.90	Felt	…	…	400	3 to 8	0.26
Concrete	12	0.78	Rock or Slag	…	…	1200	6 to 12	0.26[c]
Board:	…	…	Glass	…	…	350	0.65	0.33
Asbestos Cement	¼	16.5	Textile	…	…	350	0.65	0.31
Plaster	½	2.22	Blanket, Hairfelt	…	…	180	10	0.29
Plywood	¾	1.07	Board, Block and Pipe	…	…	…	…	…
Brick:	…	…	Insulation:	…	…	…	…	…
Common	1	5.0	Amosite	…	…	1500	15 to 18	0.32[c]
Face	1	9.0	Asbestos Paper	…	…	700	30	0.40[c]
Concrete (poured)	1	12.0	Glass or Slag (for Pipe)	…	…	350	3 to 4	0.23
Floor:	…	…	Glass or Slag (for Pipe)	…	…	1000	10 to 15	0.33[c]
Wood Subfloor	¾	1.06	Glass, Cellular	…	…	800	9	0.40
Hardwood Finish	¾	1.47	Magnesia (85%)	…	…	600	11 to 12	0.35[c]
Tile	Avg.	20.0	Mineral Fiber	…	…	100	15	0.29
Glass:	…	…	Polystyrene, Beaded	…	…	170	1	0.28
Architectural	…	10.00	Polystyrene, Rigid	…	…	170	1.8	0.25
Mortar:	…	…	Rubber, Rigid Foam	…	…	150	4.5	0.22
Cement	1	5.0	Wood Felt	…	…	180	20	0.31
Plaster:	…	…	Loose Fill:	…	…	…	…	…
Sand	⅜	13.30	Cellulose	…	…	…	2.5 to 3	0.27
Sand and Gypsum	½	11.10	Mineral Fiber	…	…	…	2 to 5	0.28
Stucco	1	5.0	Perlite	…	…	…	5 to 8	0.37
Roofing:	…	…	Silica Aerogel	…	…	…	7.6	0.17
Asphalt Roll	Avg.	6.50	Vermiculite	…	…	…	7 to 8.2	0.47
Shingle, asb. cem.	Avg.	4.76	Mineral Fiber Cement:	…	…	…	…	…
Shingle, asphalt	Avg.	2.27	Clay Binder	…	…	1800	24 to 30	0.49[c]
Shingle, wood	Avg.	1.06	Hydraulic Binder	…	…	1200	30 to 40	0.75[c]

[a] Units are in Btu/hr-ft^2-°F. Where thickness is given as 1 inch, the value given is thermal conductivity (*k*); for other thicknesses the value given is thermal conductance (*C*). All values are for a test mean temperature of 75°F, except those designated with [c], which are for 100°F.

[b] Over hollowback sheathing.

[c] Test mean temperature 100°F, see footnote [a].

Source: American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc.: *Handbook of Fundamentals*.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Typical Values of Coefficient of Linear Thermal Expansion for Thermoplastics and Other Commonly Used Materials

Material[a]	in/in/deg F × 10^{-5}	cm/cm/deg C × 10^{-5}	Material[a]	in/in/deg F × 10^{-5}	cm/cm/deg C × 10^{-5}
Liquid Crystal—GR	0.3	0.6	ABS—GR	1.7	3.1
Glass	0.4	0.7	Polypropylene—GR	1.8	3.2
Steel	0.6	1.1	Epoxy—GR	2.0	3.6
Concrete	0.8	1.4	Polyphenylene sulfide—GR	2.0	3.6
Copper	0.9	1.6	Acetal—GR	2.2	4.0
Bronze	1.0	1.8	Epoxy	3.0	5.4
Brass	1.0	1.8	Polycarbonate	3.6	6.5
Aluminum	1.2	2.2	Acrylic	3.8	6.8
Polycarbonate—GR	1.2	2.2	ABS	4.0	7.2
Nylon—GR	1.3	2.3	Nylon	4.5	8.1
TP polyester—GR	1.4	2.5	Acetal	4.8	8.5
Magnesium	1.4	2.5	Polypropylene	4.8	8.6
Zinc	1.7	3.1	TP Polyester	6.9	12.4
ABS—GR	1.7	3.1	Polyethylene	7.2	13.0

[a] GR = Typical glass fiber-reinforced material. Other plastics materials shown are unfilled.

Table 9. Linear Expansion of Various Substances between 32 and 212°F

Expansion of Volume = 3 × Linear Expansion

Substance	Linear Expansion for 1°F	Substance	Linear Expansion for 1°F
Brick	0.0000030	Masonry, brick from	0.0000026
Cement, Portland	0.0000060	to	0.0000050
Concrete	0.0000080	Plaster	0.0000092
Ebonite	0.0000428	Porcelain	0.0000020
Glass, thermometer	0.0000050	Quartz, from	0.0000043
Glass, hard	0.0000040	to	0.0000079
Granite	0.0000044	Slate	0.0000058
Marble, from	0.0000031	Sandstone	0.0000065
to	0.0000079	Wood, pine	0.0000028

Table 10. Coefficients of Heat Transmission

Metal	Btu per Second	Metal	Btu per Second	Metal	Btu per Second
Aluminum	0.00203	German silver	0.00050	Steel, soft	0.00062
Antimony	0.00022	Iron	0.00089	Silver	0.00610
Brass, yellow	0.00142	Lead	0.00045	Tin	0.00084
Brass, red	0.00157	Mercury	0.00011	Zinc	0.00170
Copper	0.00404	Steel, hard	0.00034	…	…

Heat transmitted, in British thermal units, per second, through metal 1 inch thick, per square inch of surface, for a temperature difference of 1°F

Table 11. Coefficients of Heat Radiation

Surface	Btu per Hour	Surface	Btu per Hour
Cast-iron, new	0.6480	Sawdust	0.7215
Cast-iron, rusted	0.6868	Sand, fine	0.7400
Copper, polished	0.0327	Silver, polished	0.0266
Glass	0.5948	Tin, polished	0.0439
Iron, ordinary	0.5662	Tinned iron, polished	0.0858
Iron, sheet-, polished	0.0920	Water	1.0853
Oil	1.4800	…	…

Heat radiated, in British thermal units, per square foot of surface per hour, for a temperature difference of 1° F

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Freezing Mixtures

Mixture	Temperature Change,°F From	To
Common salt (NaCl), 1 part; snow, 3 parts	32	±0
Common salt (NaCl), 1 part; snow, 1 part	32	−0.4
Calcium chloride ($CaCl_2$), 3 parts; snow, 2 parts	32	−27
Calcium chloride ($CaCl_2$), 2 parts; snow, 1 part	32	−44
Sal ammoniac (NH_4Cl), 5 parts; saltpeter (KNO_3), 5 parts; water,16 parts	50	+10
Sal ammoniac (NH_4Cl), 1 part; saltpeter (KNO_3), 1 part; water,1 part	46	−11
Ammonium nitrate (NH_4NO_3), 1 part; water, 1 part	50	+3
Potassium hydrate (KOH), 4 parts; snow, 3 parts	32	−35

Ignition Temperatures.— The following temperatures are required to ignite the different substances specified: Phosphorus, transparent, 120°F; bisulfide of carbon, 300°F; gun cotton, 430°F; nitro-glycerine, 490°F; phosphorus, amorphous, 500°F; rifle powder, 550°F; charcoal, 660°F; dry pine wood, 800°F; dry oak wood, 900°F.

Table 13. Typical Thermal Properties of Various Metals

Material and Alloy Designation[a]	Density, ρ lb/in^3	Melting Point, °F solidus	liquidus	Conductivity, *k*, Btu/hr-ft-°F	Specific Heat, *C*, Btu/lb/°F	Coeff. of Expansion, α µin/in-°F
Aluminum Alloys						
2011	0.102	995	1190	82.5	0.23	12.8
2017	0.101	995	1185	99.4	0.22	13.1
2024	0.100	995	1180	109.2	0.22	12.9
3003	0.099	1190	1210	111	0.22	12.9
5052	0.097	1100	1200	80	0.22	13.2
5086	0.096	1085	1185	73	0.23	13.2
6061	0.098	1080	1200	104	0.23	13.0
7075	0.101	890	1180	70	0.23	13.1
Copper-Base Alloys						
Manganese Bronze	0.302	1590	1630	61	0.09	11.8
C11000 (Electrolytic tough pitch)	0.321	1941	1981	226	0.09	9.8
C14500 (Free machining Cu)	0.323	1924	1967	205	0.09	9.9
C17200, C17300 (Beryllium Cu)	0.298	1590	1800	62	0.10	9.9
C18200 (Chromium Cu)	0.321	1958	1967	187	0.09	9.8
C18700 (Leaded Cu)	0.323	1750	1975	218	0.09	9.8
C22000 (Commercial bronze, 90%)	0.318	1870	1910	109	0.09	10.2
C23000 (Red brass, 85%)	0.316	1810	1880	92	0.09	10.4
C26000 (Cartridge brass, 70%)	0.313	1680	1750	70	0.09	11.1
C27000 (Yellow brass)	0.306	1660	1710	67	0.09	11.3
C28000 (Muntz metal, 60%)	0.303	1650	1660	71	0.09	11.6
C33000 (Low-leaded brass tube)	0.310	1660	1720	67	0.09	11.2
C35300 (High-leaded brass)	0.306	1630	1670	67	0.09	11.3
C35600 (Extra-high-leaded brass)	0.307	1630	1660	67	0.09	11.4
C36000 (Free machining brass)	0.307	1630	1650	67	0.09	11.4
C36500 (Leaded Muntz metal)	0.304	1630	1650	71	0.09	11.6
C46400 (Naval brass)	0.304	1630	1650	67	0.09	11.8
C51000 (Phosphor bronze, 5% A)	0.320	1750	1920	40	0.09	9.9
C54400 (Free cutting phos. bronze)	0.321	1700	1830	50	0.09	9.6
C62300 (Aluminum bronze, 9%)	0.276	1905	1915	31.4	0.09	9.0
C62400 (Aluminum bronze, 11%)	0.269	1880	1900	33.9	0.09	9.2
C63000 (Ni-Al bronze)	0.274	1895	1930	21.8	0.09	9.0
Nickel-Silver	0.314	1870	2030	17	0.09	9.0

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Typical Thermal Properties of Various Metals *(Continued)*

Material and Alloy Designation[a]	Density, ρ lb/in^3	Melting Point, °F		Conductivity, *k*, Btu/hr-ft-°F	Specific Heat, *C*, Btu/lb/°F	Coeff. of Expansion, α µin/in-°F
		solidus	liquidus			
Nickel-Base Alloys						
Nickel 200, 201, 205	0.321	2615	2635	43.3	0.11	8.5
Hastelloy C-22	0.314	2475	2550	7.5	0.10	6.9
Hastelloy C-276	0.321	2415	2500	7.5	0.10	6.2
Inconel 718	0.296	2300	2437	6.5	0.10	7.2
Monel	0.305	2370	2460	10	0.10	8.7
Monel 400	0.319	2370	2460	12.6	0.10	7.7
Monel K500	0.306	2400	2460	10.1	0.10	7.6
Monel R405	0.319	2370	2460	10.1	0.10	7.6
Stainless Steels						
S30100	0.290	2550	2590	9.4	0.12	9.4
S30200, S30300, S30323	0.290	2550	2590	9.4	0.12	9.6
S30215	0.290	2500	2550	9.2	0.12	9.0
S30400, S30500	0.290	2550	2650	9.4	0.12	9.6
S30430	0.290	2550	2650	6.5	0.12	9.6
S30800	0.290	2550	2650	8.8	0.12	9.6
S30900, S30908	0.290	2550	2650	9.0	0.12	8.3
S31000, S31008	0.290	2550	2650	8.2	0.12	8.8
S31600, S31700	0.290	2500	2550	9.4	0.12	8.8
S31703	0.290	2500	2550	8.3	0.12	9.2
S32100	0.290	2550	2600	9.3	0.12	9.2
S34700	0.290	2550	2650	9.3	0.12	9.2
S34800	0.290	2550	2650	9.3	0.12	9.3
S38400	0.290	2550	2650	9.4	0.12	9.6
S40300, S41000, S41600, S41623	0.280	2700	2790	14.4	0.11	5.5
S40500	0.280	2700	2790	15.6	0.12	6.0
S41400	0.280	2600	2700	14.4	0.11	5.8
S42000, S42020	0.280	2650	2750	14.4	0.11	5.7
S42200	0.280	2675	2700	13.8	0.11	6.2
S42900	0.280	2650	2750	14.8	0.11	5.7
S43000, S43020, S43023	0.280	2600	2750	15.1	0.11	5.8
S43600	0.280	2600	2750	13.8	0.11	5.2
S44002, S44004	0.280	2500	2700	14.0	0.11	5.7
S44003	0.280	2500	2750	14.0	0.11	5.6
S44600	0.270	2600	2750	12.1	0.12	5.8
S50100, S50200	0.280	2700	2800	21.2	0.11	6.2
Cast Iron and Steel						
Malleable Iron, A220 (50005, 60004, 80002)	0.265			29.5	0.12	7.5
Grey Cast Iron	0.25			28.0	0.25	5.8
Ductile Iron, A536 (120–90–02)	0.25	liquidus approximately, 2100 to 2200, depending on composition			0.16	5.9–6.2
Ductile Iron, A536 (100–70–03)	0.25			20.0	0.16	5.9–6.2
Ductile Iron, A536 (80–55–06)	0.25			18.0	0.15	5.9–6.2
Ductile Iron, A536 (65–45–120)	0.25			20.8	0.15	5.9–6.2
Ductile Iron, A536 (60–40–18)	0.25				0.12	5.9–6.2
Cast Steel, 3%C	0.25	liquidus, 2640		28.0	0.12	7.0
Titanium Alloys						
Commercially Pure	0.163	3000	3040	9.0	0.12	5.1
Ti-5Al-2.5Sn	0.162	2820	3000	4.5	0.13	5.3
Ti-8Mn	0.171	2730	2970	6.3	0.19	6.0

[a] Alloy designations correspond to the AluminumAssociation numbers for aluminum alloys and to the unified numbering system (UNS) for copper and stainless steel alloys. A220 and A536 are ASTM specified irons.

Copyright 2004, Industrial Press, Inc., New York, NY

Adjusting Lengths for Reference Temperature.— The standard reference temperature for industrial length measurements is 20 degrees Celsius (68 degrees Fahrenheit). For other temperatures, corrections should be made in accordance with the difference in thermal expansion for the two parts, especially when the gage is made of a different material than the part to be inspected.

Example: An aluminum part is to be measured with a steel gage when the room temperature is 30 °C. The aluminum part has a coefficient of linear thermal expansion, $\alpha_{Part} = 24.7 \times 10^{-6}$ mm/mm-°C, and for the steel gage, $\alpha_{Gage} = 10.8 \times 10^{-6}$ mm/mm-°C.

At the reference temperature, the specified length of the aluminum part is 20.021 mm. What is the length of the part at the measuring (room) temperature?

ΔL, the change in the measured length due to temperature, is given by:

$$\begin{aligned}\Delta L &= L(T_R - T_0)(\alpha_{Part} - \alpha_{Gage}) \\ &= 20.021(30 - 20)(24.7 - 10.8) \times 10^{-6} \text{ mm} \\ &= 2782.919 \times 10^{-6} \approx 0.003 \text{ mm}\end{aligned}$$

where L = length of part at reference temperature; T_R = room temperature (temperature of part and gage); and, T_0 = reference temperature.

Thus, the temperature corrected length at 30°C is $L + \Delta L = 20.021 + 0.003 = 20.024$ mm.

Length Change Due to Temperature.— Table 14 gives changes in length for variations from the standard reference temperature of 68°F (20°C) for materials of known coefficients of expansion, α. Coefficients of expansion are given in tables on pages 402, 403, 415, 416, 427, and elsewhere.

Example: In Table 14, for coefficients between those listed, add appropriate listed values. For example, a length change for a coefficient of 7 is the sum of values in the 5 and 2 columns. Fractional interpolation also is possible. Thus, in a steel bar with a coefficient of thermal expansion of $6.3 \times 10^{-6} = 0.0000063$ in/in = 6.3 µin/in of length/°F, the increase in length at 73°F is 25 + 5 + 1.5 = 31.5 µin/in of length. For a steel with the same coefficient of expansion, the change in length, measured in degrees C, is expressed in microns (micrometers)/meter (µm/m) of length.

Alternatively, and for temperatures beyond the scope of the table, the length difference due to a temperature change is equal to the coefficient of expansion multiplied by the change in temperature, i.e., $\triangle L = \alpha \triangle T$. Thus, for the previous example, $\triangle L = 6.3 \times (73 - 68) = 6.3 \times 5 = 31.5$ µin/in.

Change in Radius of Thin Circular Ring with Temperature.— Consider a circular ring of initial radius r, that undergoes a temperature change $\triangle T$. Initially, the circumference of the ring is $c = 2\pi r$. If the coefficient of expansion of the ring material is α, the change in circumference due to the temperature change is $\triangle c = 2\pi r \, \alpha \triangle T$

The new circumference of the ring will be: $c_n = c + \triangle c = 2\pi r + 2\pi r \alpha \triangle T = 2\pi r(1 + \alpha \triangle T)$

Note: An increase in temperature causes $\triangle c$ to be positive, and a decrease in temperature causes $\triangle c$ to be negative.

As the circumference increases, the radius of the circle also increases. If the new radius is R, the new circumference $2\pi R$. For a given change in temperature, $\triangle T$, the change in radius of the ring is found as follows:

$$c_n = 2\pi R = 2\pi r(1 + \alpha \Delta T) \qquad R = r + r\alpha \Delta T \qquad \Delta r = R - r = r\alpha \Delta T$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Differences in Length in Inches/Inch (Microns/Meter) for Changes from the Standard Temperature of 68°F (20°C)

Temperature Deg. F	Temperature Deg. C	Coefficient of Thermal Expansion of Material per Degree F (C) × 10^6 1	2	3	4	5	10	15	20	25	30
		Total Change in Length from Standard Temperature { for °F in microinches/inch of length (μin/in) for °C or °K in microns/meter of length (μm/m)									
38	−10	−30	−60	−90	−120	−150	−300	−450	−600	−750	−900
39	−9	−29	−58	−87	−116	−145	−290	−435	−580	−725	−870
40	−8	−28	−56	−84	−112	−140	−280	−420	−560	−700	−840
41	−7	−27	−54	−81	−108	−135	−270	−405	−540	−675	−810
42	−6	−26	−52	−78	−104	−130	−260	−390	−520	−650	−780
43	−5	−25	−50	−75	−100	−125	−250	−375	−500	−625	−750
44	−4	−24	−48	−72	−96	−120	−240	−360	−480	−600	−720
45	−3	−23	−46	−69	−92	−115	−230	−345	−460	−575	−690
46	−2	−22	−44	−66	−88	−110	−220	−330	−440	−550	−660
47	−1	−21	−42	−63	−84	−105	−210	−315	−420	−525	−630
48	0	−20	−40	−60	−80	−100	−200	−300	−400	−500	−600
49	1	−19	−38	−57	−76	−95	−190	−285	−380	−475	−570
50	2	−18	−36	−54	−72	−90	−180	−270	−360	−450	−540
51	3	−17	−34	−51	−68	−85	−170	−255	−340	−425	−510
52	4	−16	−32	−48	−64	−80	−160	−240	−320	−400	−480
53	5	−15	−30	−45	−60	−75	−150	−225	−300	−375	−450
54	6	−14	−28	−42	−56	−70	−140	−210	−280	−350	−420
55	7	−13	−26	−39	−52	−65	−130	−195	−260	−325	−390
56	8	−12	−24	−36	−48	−60	−120	−180	−240	−300	−360
57	9	−11	−22	−33	−44	−55	−110	−165	−220	−275	−330
58	10	−10	−20	−30	−40	−50	−100	−150	−200	−250	−300
59	11	−9	−18	−27	−36	−45	−90	−135	−180	−225	−270
60	12	−8	−16	−24	−32	−40	−80	−120	−160	−200	−240
61	13	−7	−14	−21	−28	−35	−70	−105	−140	−175	−210
62	14	−6	−12	−18	−24	−30	−60	−90	−120	−150	−180
63	15	−5	−10	−15	−20	−25	−50	−75	−100	−125	−150
64	16	−4	−8	−12	−16	−20	−40	−60	−80	−100	−120
65	17	−3	−6	−9	−12	−15	−30	−45	−60	−75	−90
66	18	−2	−4	−6	−8	−10	−20	−30	−40	−50	−60
67	19	−1	−2	−3	−4	−5	−10	−15	−20	−25	−30
68	20	0	0	0	0	0	0	0	0	0	0
69	21	1	2	3	4	5	10	15	20	25	30
70	22	2	4	6	8	10	20	30	40	50	60
71	23	3	6	9	12	15	30	45	60	75	90
72	24	4	8	12	16	20	40	60	80	100	120
73	25	5	10	15	20	25	50	75	100	125	150
74	26	6	12	18	24	30	60	90	120	150	180
75	27	7	14	21	28	35	70	105	140	175	210
76	28	8	16	24	32	40	80	120	160	200	240
77	29	9	18	27	36	45	90	135	180	225	270
78	30	10	20	30	40	50	100	150	200	250	300
79	31	11	22	33	44	55	110	165	220	275	330
80	32	12	24	36	48	60	120	180	240	300	360
81	33	13	26	39	52	65	130	195	260	325	390
82	34	14	28	42	56	70	140	210	280	350	420
83	35	15	30	45	60	75	150	225	300	375	450
84	36	16	32	48	64	80	160	240	320	400	480
85	37	17	34	51	68	85	170	255	340	425	510
86	38	18	36	54	72	90	180	270	360	450	540
87	39	19	38	57	76	95	190	285	380	475	570
88	40	20	40	60	80	100	200	300	400	500	600
89	41	21	42	63	84	105	210	315	420	525	630
90	42	22	44	66	88	110	220	330	440	550	660
91	43	23	46	69	92	115	230	345	460	575	690
92	44	24	48	72	96	120	240	360	480	600	720
93	45	25	50	75	100	125	250	375	500	625	750
94	46	26	52	78	104	130	260	390	520	650	780
95	47	27	54	81	108	135	270	405	540	675	810
96	48	28	56	84	112	140	280	420	560	700	840
97	49	29	58	87	116	145	290	435	580	725	870
98	50	30	60	90	120	150	300	450	600	750	900

Copyright 2004, Industrial Press, Inc., New York, NY

Properties of Mass and Weight

Specific Gravity.— Specific gravity is a number indicating how many times a certain volume of a material is heavier than an equal volume of water. The density of water differs slightly at different temperatures, so the usual custom is to make comparisons on the basis that the water has a temperature of 62°F. The weight of 1 cubic inch of pure water at 62°F is 0.0361 pound. If the specific gravity of any material is known, the weight of a cubic inch of the material, therefore, can be found by multiplying its specific gravity by 0.0361. To find the weight per cubic foot of a material, multiply the specific gravity by 62.355. If the weight of a cubic inch of a material is known, the specific gravity is found by dividing the weight per cubic inch by 0.0361.

Example: Given the specific gravity of cast iron is 7.2. Then, the weight of 5 cubic inches of cast iron = $7.2 \times 0.0361 \times 5 = 1.2996$ pounds.

Example: Given the weight of a cubic inch of gold is 0.697 pound. Then, the specific gravity of gold = $0.697 \div 0.0361 = 19.31$

If the weight per cubic foot of a material is known, the specific gravity is found by multiplying this weight by 0.01604.

Table 15. Average Specific Gravity of Various Substances

Substance	Specific Gravity	[a]Weight lb/ft^3	Substance	Specific Gravity	[a]Weight lb/ft^3	Substance	Specific Gravity	[a]Weight lb/ft^3
ABS	1.05	66	Glass	2.6	162	Platinum	21.5	1342
Acrylic	1.19	74	Glass, crushed	…	74	Polycarbonate	1.19	74
Aluminum bronze	7.8	486	Gold, 22 carat fine	17.5	1091	Polyethylene	0.97	60
Aluminum, cast	2.6	160	Gold, pure	19.3	1204	Polypropylene	0.91	57
Aluminum, wrought	2.7	167	Granite	2.7	168	Polyurethane	1.05	66
Asbestos	2.4	150	Gravel	…	109	Quartz	2.6	162
Asphaltum	1.4	87	Gypsum	2.4	150	Salt, common	…	48
Borax	1.8	112	Ice	0.9	56	Sand, dry	…	100
Brick, common	1.8	112	Iron, cast	7.2	447	Sand, wet	…	125
Brick, fire	2.3	143	Iron, wrought	7.7	479	Sandstone	2.3	143
Brick, hard	2.0	125	Iron slag	2.7	168	Silver	10.5	656
Brick, pressed	2.2	137	Lead	11.4	711	Slate	2.8	175
Brickwork, in cement	1.8	112	Limestone	2.6	162	Soapstone	2.7	168
Brickwork, in mortar	1.6	100	Marble	2.7	168	Steel	7.9	491
CPVC	1.55	97	Masonry	2.4	150	Sulfur	2.0	125
Cement, Portland (set)	3.1	193	Mercury	13.56	845.3	Tar, bituminous	1.2	75
Chalk	2.3	143	Mica	2.8	175	Tile	1.8	112
Charcoal	0.4	25	Mortar	1.5	94	Trap rock	3.0	187
Coal, anthracite	1.5	94	Nickel, cast	8.3	517	Water at 62°F	1.0	62.355
Coal, bituminous	1.3	81	Nickel, rolled	8.7	542	White metal	7.3	457
Concrete	2.2	137	Nylon 6, Cast	1.16	73	Zinc, cast	6.9	429
Earth, loose	…	75	PTFE	2.19	137	Zinc, sheet	7.2	450
Earth, rammed	…	100	Phosphorus	1.8	112	…	…	…
Emery	4.0	249	Plaster of Paris	1.8	112	…	…	…

[a] The weight per cubic foot is calculated on the basis of the specific gravity except for those substances that occur in bulk, heaped, or loose form. In these instances, only the weights per cubic foot are given because the voids present in representative samples make the values of the specific gravities inaccurate.

Specific Gravity of Gases.— The specific gravity of gases is the number that indicates their weight in comparison with that of an equal volume of air. The specific gravity of air is 1, and the comparison is made at 32°F. Values are given in Table 16.

Specific Gravity of Liquids.— The specific gravity of liquids is the number that indicates how much a certain volume of the liquid weighs compared with an equal volume of water, the same as with solid bodies. Specific gravity of various liquids is given in Table 17.

The density of liquid is often expressed in degrees on the hydrometer, an instrument for determining the density of liquids, provided with graduations made to an arbitrary scale. The hydrometer consists of a glass tube with a bulb at one end containing air, and arranged with a weight at the bottom so as to float in an upright position in the liquid, the density of

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. Specific Gravity of Gases At 32°F

Gas	Sp. Gr.	Gas	Sp. Gr.	Gas	Sp. Gr.
Air[a]	1.000	Ether vapor	2.586	Marsh gas	0.555
Acetylene	0.920	Ethylene	0.967	Nitrogen	0.971
Alcohol vapor	1.601	Hydrofluoric acid	2.370	Nitric oxide	1.039
Ammonia	0.592	Hydrochloric acid	1.261	Nitrous oxide	1.527
Carbon dioxide	1.520	Hydrogen	0.069	Oxygen	1.106
Carbon monoxide	0.967	Illuminating gas	0.400	Sulfur dioxide	2.250
Chlorine	2.423	Mercury vapor	6.940	Water vapor	0.623

[a] 1 cubic foot of air at 32°F and atmospheric pressure weighs 0.0807 pound.

which is to be measured. The depth to which the hydrometer sinks in the liquid is read off on the graduated scale. The most commonly used hydrometer is the Baumé, see Table 18. The value of the degrees of the Baumé scale differs according to whether the liquid is heavier or lighter than water. The specific gravity for liquids heavier than water equals 145 ÷ (145 – degrees Baumé). For liquids lighter than water, the specific gravity equals 140 ÷ (130 + degrees Baumé).

Table 17. Specific Gravity of Liquids

Liquid	Sp. Gr.	Liquid	Sp. Gr.	Liquid	Sp. Gr.
Acetic acid	1.06	Fluoric acid	1.50	Petroleum oil	0.82
Alcohol, commercial	0.83	Gasoline	0.70	Phosphoric acid	1.78
Alcohol, pure	0.79	Kerosene	0.80	Rape oil	0.92
Ammonia	0.89	Linseed oil	0.94	Sulfuric acid	1.84
Benzine	0.69	Mineral oil	0.92	Tar	1.00
Bromine	2.97	Muriatic acid	1.20	Turpentine oil	0.87
Carbolic acid	0.96	Naphtha	0.76	Vinegar	1.08
Carbon disulfide	1.26	Nitric acid	1.50	Water	1.00
Cotton-seed oil	0.93	Olive oil	0.92	Water, sea	1.03
Ether, sulfuric	0.72	Palm oil	0.97	Whale oil	0.92

Table 18. Degrees on Baumé's Hydrometer Converted to Specific Gravity

	Specific Gravity for Liquids			Specific Gravity for Liquids			Specific Gravity for Liquids	
Deg. Baumé	Heavier than Water	Lighter than Water	Deg. Baumé	Heavier than Water	Lighter than Water	Deg. Baumé	Heavier than Water	Lighter than Water
0	1.000	…	27	1.229	0.892	54	1.593	0.761
1	1.007	…	28	1.239	0.886	55	1.611	0.757
2	1.014	…	29	1.250	0.881	56	1.629	0.753
3	1.021	…	30	1.261	0.875	57	1.648	0.749
4	1.028	…	31	1.272	0.870	58	1.667	0.745
5	1.036	…	32	1.283	0.864	59	1.686	0.741
6	1.043	…	33	1.295	0.859	60	1.706	0.737
7	1.051	…	34	1.306	0.854	61	1.726	0.733
8	1.058	…	35	1.318	0.849	62	1.747	0.729
9	1.066	…	36	1.330	0.843	63	1.768	0.725
10	1.074	1.000	37	1.343	0.838	64	1.790	0.721
11	1.082	0.993	38	1.355	0.833	65	1.813	0.718
12	1.090	0.986	39	1.368	0.828	66	1.836	0.714
13	1.099	0.979	40	1.381	0.824	67	1.859	0.710
14	1.107	0.972	41	1.394	0.819	68	1.883	0.707
15	1.115	0.966	42	1.408	0.814	69	1.908	0.704
16	1.124	0.959	43	1.422	0.809	70	1.933	0.700
17	1.133	0.952	44	1.436	0.805	71	1.959	0.696
18	1.142	0.946	45	1.450	0.800	72	1.986	0.693
19	1.151	0.940	46	1.465	0.796	73	2.014	0.689
20	1.160	0.933	47	1.480	0.791	74	2.042	0.686
21	1.169	0.927	48	1.495	0.787	75	2.071	0.683
22	1.179	0.921	49	1.510	0.782	76	2.101	0.679
23	1.189	0.915	50	1.526	0.778	77	2.132	0.676
24	1.198	0.909	51	1.542	0.773	78	2.164	0.673
25	1.208	0.903	52	1.559	0.769	79	2.197	0.669
26	1.219	0.897	53	1.576	0.765	80	2.230	0.666

Copyright 2004, Industrial Press, Inc., New York, NY

Average Weights and Volumes of Solid Fuels.— Anthracite coal, 55–65 lb/ft^3; 34–41 ft^3/ton (2240 lb); 67 lb/bushel. Bituminous coal, 50–55 lb/ft^3; 41–45 ft^3/ton (2240 lb); 60 lb/bushel.Charcoal, 8–18.5 lb/ft^3; 120–124 ft^3/ton (2240 lb); 20 lb/bushel. Coke, 28 lb/ft^3; 80 ft^3/ton (2240 lb); 40 lb/bushel.

How to Estimate the Weight of Natural Piles.— To calculate the upper and lower limits of the weight of a substance piled naturally on a circular plate, so as to form a cone of material, use the equation:

$$W = MD^3 \quad (1)$$

where W = weight, lb; D = diameter of plate, ft. (Fig. 1a); and, M = materials factor, whose upper and lower limits are given in Table 19b.

For a rectangular plate, calculate the weight of material piled naturally by means of the following equation:

$$W = MRA^3 \quad (2)$$

where A and B = the length and width in ft., respectively, of the rectangular plate in Fig. 1b, with $B \le A$; and, R = is a factor given in Table 19a as a function of the ratio B/A.

Example: Find the upper and lower limits of the weight of dry ashes piled naturally on a plate 10 ft. in diameter.

Using Equation (1), $M = 4.58$ from Table 19b, the lower limit $W = 4.58 \times 10^3 = 4{,}580$ lb. For $M = 5.89$, the upper limit $W = 5.89 \times 10^3 = 5{,}890$ lb.

Example: What weight of dry ashes rests on a rectangular plate 10 ft. by 5 ft.?

For $B/A = 5/10 = 0.5$, $R = 0.39789$ from Table 19a. Using Equation (2), for $M = 4.58$, the lower limit $W = 4.58 \times 0.39789 \times 10^3 = 1{,}822$ lb. For $M = 5.89$, the upper limit $W = 5.89 \times 0.39789 \times 10^3 = 2{,}344$lb.



Fig. 1a. Conical Pile



Fig. 1b. Rectangular Pile

Table 19a. Factor *R* as a function of *B*/*A* (*B* ≤ *A*)

B/*A*	*R*	*B*/*A*	*R*	*B*/*A*	*R*	*B*/*A*	*R*	*B*/*A*	*R*	*B*/*A*	*R*
0.01	0.00019	0.18	0.05817	0.35	0.20666	0.52	0.42691	0.69	0.70015	0.86	1.00761
0.02	0.00076	0.19	0.06458	0.36	0.21782	0.53	0.44170	0.70	0.71747	0.87	1.02636
0.03	0.00170	0.20	0.07130	0.37	0.22921	0.54	0.45667	0.71	0.73491	0.88	1.04516
0.04	0.00302	0.21	0.07833	0.38	0.24085	0.55	0.47182	0.72	0.75245	0.89	1.06400
0.05	0.00470	0.22	0.08566	0.39	0.25273	0.56	0.48713	0.73	0.77011	0.90	1.08289
0.06	0.00674	0.23	0.09329	0.40	0.26483	0.57	0.50262	0.74	0.78787	0.91	1.10182
0.07	0.00914	0.24	0.10121	0.41	0.27717	0.58	0.51826	0.75	0.80572	0.92	1.12078
0.08	0.01190	0.25	0.10942	0.42	0.28973	0.59	0.53407	0.76	0.82367	0.93	1.13977
0.09	0.01501	0.26	0.11792	0.43	0.30252	0.60	0.55004	0.77	0.84172	0.94	1.15879
0.10	0.01846	0.27	0.12670	0.44	0.31552	0.61	0.56616	0.78	0.85985	0.95	1.17783
0.11	0.02226	0.28	0.13576	0.45	0.32873	0.62	0.58243	0.79	0.87807	0.96	1.19689
0.12	0.02640	0.29	0.14509	0.46	0.34216	0.63	0.59884	0.80	0.89636	0.97	1.21596
0.13	0.03088	0.30	0.15470	0.47	0.35579	0.64	0.61539	0.81	0.91473	0.98	1.23505
0.14	0.03569	0.31	0.16457	0.48	0.36963	0.65	0.63208	0.82	0.93318	0.99	1.25414
0.15	0.04082	0.32	0.17471	0.49	0.38366	0.66	0.64891	0.83	0.95169	1.00	1.27324
0.16	0.04628	0.33	0.18511	0.50	0.39789	0.67	0.66586	0.84	0.97027	…	…
0.17	0.05207	0.34	0.19576	0.51	0.41231	0.68	0.68295	0.85	0.98891	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19b. Limits of Factor *M* for Various Materials

Material	Factor *M*	Material	Factor *M*	Material	Factor *M*
Almonds, whole	2.12–3.93	Coffee, ground	1.89–3.27	Peanuts, unshelled	1.13–3.14
Aluminum chips	0.92–1.96	Coke, pulverized	2.21	Peanuts, shelled	2.65–5.89
Aluminum silicate	3.7–6.41	Copper oxide, powdered	20.87	Peas, dry	2.75–3.05
Ammonium chloride	3.93–6.81	Cork, granulated	1.57–1.96	Potassium carbonate	3.85–6.68
Asbestos, shred	2.62–3.27	Corn on cob	1.29–1.33	Potasiuin sulphate	5.5–6.28
Ashes, dry	4.58–5.89	Corn sugar	2.34–4.06	Pumice	5.24–5.89
Ashes, damp	6.24–7.80	Cottonseed, dry, de–linted	1.66–5.24	Rice, bran	1.51–2.75
Asphalt, crushed	3.4–5.89	Diatoinaceous earth	0.83–1.83	Rubber, scrap, ground	2.11–4.58
Bakelite, powdered	3.93–5.24	Dicalcium phosphate	5.63	Salt, dry, coarse	3.02–8.38
Baking powder	3.1–5.37	Ebonite, crushed	4.91–9.16	Salt, dry, fine	5.29–10.47
Barium carbonate	9.42	Epsoin salts	3.02–6.54	Saltpeter	6.05–10.47
Bauxite, mine run	5.9–6.69	Feldspar, ground	8.51–9.16	Salt rock, crushed	4.58
Beans, navy, dry	3.63	Fish scrap	5.24–6.54	Sand, very fine	7.36–9
Beets, sugar, shredded	0.47–0.55	Flour	5.61–10.43	Sawdust, dry	0.95–2.85
Bicarbonate of soda	3.10	Flue dust	2.65–3.40	Sesame seed	2.04–4.84
Borax	3.78–9.16	Flourspar (Flourite)	10.73–14.40	Shellac, powdered	2.34–4.06
Boric acid	4.16–7.20	Graphite, flake	3.02–5.24	Slag, furnace, granular	4.53–8.51
Bronze chips	3.93–6.54	Gravel	6.8–13.18	Soap powder	1.51–3.27
Buckwheat	2.8–3.17	Gypsum, calcined	6.04–6.59	Sodium nitrate	3.96–4.66
Calcium lactate	3.4–3.8	Hominy	2.8–6.54	Sodium sulphite	10.54
Calcium oxide (lime)	3.30	Hops, dry	4.58	Sodium sulphate	6.92
Carbon, ground	2.51	Kaolin clay	12.32–21.34	Soybeans	3.48–6.28
Casein	2.72–4.71	Lead silicate, granulated	25.26	Steel chips, crushed	7.56–19.63
Cashew nuts	4.19–4.84	Lead sulphate, pulverized	24.09	Sugar, refined	3.78–7.2
Cast iron chips	17.02–26.18	Lime ground	7.85	Sulphur	4.5–6.95
Cement, Portland	6.8–13.09	Limestone, crushed	6.42–11.78	Talcum powder	4.37–5.9
Cinders, coal	3.02–5.24	Magnesium chloride	4.32	Tin oxide, ground	9.17
Clay, blended for tile	5.89	Malt, dry, ground	1.66–2.88	Tobacco stems	1.96–3.27
Coal, anthracite, chestnut	2.43	Manganese sulphate	5.29–9.16	Trisodium phosphate	4.53–7.85
Coal, bituminous, sized	2.64–4.48	Marble, crushed	6.8–12.44	Walnut shells, crushed	2.65–5.24
Coal, ground	2.90	Mica, ground	1.24–1.43	Wood chips, fir	2.49–2.88
Cocoa, powdered	3.93–4.58	Milk, whole, powdered	2.62	Zinc sulphate	8.85–11.12
Coconut, shredded	2.62–2.88	Oats	1.74–2.86	…	…
Coffee beans	2.42–5.89	Orange peel, dry	1.96	…	…

Earth or Soil Weight.— Loose earth has a weight of approximately 75 pounds per cubic foot and rammed earth, 100 pounds per cubic foot. The solid crust of the earth, according to an estimate, is composed approximately of the following elements:

Oxygen, 44.0 to 48.7 per cent; silicon, 22.8 to 36.2 per cent; aluminum, 6.1 to 9.9 per cent; iron, 2.4 to 9.9 per cent; calcium, 0.9 to 6.6 per cent; magnesium, 0.1 to 2.7 per cent; sodium, 2.4 to 2.5 per cent; potassium, 1.7 to 3.1 per cent.

Molecular Weight.— The smallest mass of a chemical combination which can be conceived of as existing and yet preserving its chemical properties is known as a *molecule*. The molecular weight of a chemical compound is equal to the sum of the atomic weights of the atoms contained in the molecule, and are calculated from the atomic weights, when the symbol of the compound is known. The atomic weight of silver is 107.88; of nitrogen, 14.01; and of oxygen, 16; hence, the molecular weight of silver-nitrate, the chemical formula of which is $AgNO_3$ equals $107.88 + 14.01 + (3 \times 16) = 169.89$.

Mol.— The term "mol" is used as a designation of quantity in electro-chemistry, and indicates the number of grams of a substance equal to its molecular weight. For example, one mol of siliver-nitrate equals 169.89 grams, the molecular weight of silver-nitrate being 169.89.

Copyright 2004, Industrial Press, Inc., New York, NY

PROPERTIES OF WOOD, CERAMICS, PLASTICS, METALS, WATER, AND AIR

Properties of Wood

Mechanical Properties of Wood.— Wood is composed of cellulose, lignin, ash-forming minerals, and extractives formed into a cellular structure. (Extractives are substances that can be removed from wood by extraction with such solvents as water, alcohol, acetone, benzene, and ether.) Variations in the characteristics and volumes of the four components and differences in the cellular structure result in some woods being heavy and some light, some stiff and some flexible, and some hard and some soft. For a single species, the properties are relatively constant within limits; therefore, selection of wood by species alone may sometimes be adequate. However, to use wood most effectively in engineering applications, the effects of physical properties or specific characteristics must be considered.

The mechanical properties listed in the accompanying Table 1 were obtained from tests on small pieces of wood termed "clear" and "straight grained" because they did not contain such characteristics as knots, cross grain, checks, and splits. However, these test pieces did contain such characteristics as growth rings that occur in consistent patterns within the piece. Since wood products may contain knots, cross grain, etc., these characteristics must be taken into account when assessing actual properties or when estimating actual performance. In addition, the methods of data collection and analysis have changed over the years during which the data in Table 1 have been collected; therefore, the appropriateness of the data should be reviewed when used for critical applications such as stress grades of lumber.

Wood is an orthotropic material; that is, its mechanical properties are unique and independent in three mutually perpendicular directions—longitudinal, radial, and tangential. These directions are illustrated in the following figure.



Modulus of Rupture: The modulus of rupture in bending reflects the maximum load-carrying capacity of a member and is proportional to the maximum moment borne by the member. The modulus is an accepted criterion of strength, although it is not a true stress because the formula used to calculate it is valid only to the proportional limit.

Work to Maximum Load in Bending: The work to maximum load in bending represents the ability to absorb shock with some permanent deformation and more or less injury to a specimen; it is a measure of the combined strength and toughness of the wood under bending stress.

Maximum Crushing Strength: The maximum crushing strength is the maximum stress sustained by a compression parallel-to-grain specimen having a ratio of length to least diameter of less than 11.

Compression Perpendicular to Grain: Strength in compression perpendicular to grain is reported as the stress at the proportional limit because there is no clearly defined ultimate stress for this property.

Copyright 2004, Industrial Press, Inc., New York, NY

Shear Strength Parallel to Grain: Shear strength is a measure of the ability to resist internal slipping of one part upon another along the grain. The values listed in the table are averages of the radial and tangential shears.

Tensile Strength Perpendicular to Grain: The tensile strength perpendicular to the grain is a measure of the resistance of wood to forces acting across the grain that tend to split the material. Averages of radial and tangential measurements are listed.

Table 1. Mechanical Properties of Commercially Important U.S. Grown Woods

Use the first number in each column for GREEN wood; use the second number for DRY wood.	Static Bending				Maximum Crushing Strength (10^3 psi)		Compression Strength Perpendicular to Grain (psi)		Shear Strength Parallel to Grain (psi)		Tensile Strength Perp. to Grain (psi)	
	Modulus of Rupture (10^3 psi)		Work to Max Load (in.-lb/in.^{3})									
Basswood, American	5.0	8.7	5.3	7.2	2.22	4.73	170	370	600	990	280	350
Cedar, N. white	4.2	6.5	5.7	4.8	1.90	3.96	230	310	620	850	240	240
Cedar, W. red	5.2	7.5	5.0	5.8	2.77	4.56	240	460	770	990	230	220
Douglas Fir, coast[a]	7.7	12.4	7.6	9.9	3.78	7.23	380	800	900	1,130	300	340
Douglas Fir, interior W.	7.7	12.6	7.2	10.6	3.87	7.43	420	760	940	1,290	290	350
Douglas Fir, interior N.	7.4	13.1	8.1	10.5	3.47	6.90	360	770	950	1,400	340	390
Douglas Fir, interior S.	6.8	11.9	8.0	9.0	3.11	6.23	340	740	950	1,510	250	330
Fir, balsam	5.5	9.2	4.7	5.1	2.63	5.28	190	404	662	944	180	180
Hemlock, Eastern	6.4	8.9	6.7	6.8	3.08	5.41	360	650	850	1,060	230	…
Hemlock, Mountain	6.3	11.5	11.0	10.4	2.88	6.44	370	860	930	1,540	330	…
Hemlock, Western	6.6	11.3	6.9	8.3	3.36	7.20	280	550	860	1,290	290	340
Pine, E. white	4.9	9.9	5.2	8.3	2.44	5.66	220	580	680	1,170	250	420
Pine, Virginia	7.3	13.0	10.9	13.7	3.42	6.71	390	910	890	1,350	400	380
Pine, W. white	4.7	9.7	5.0	8.8	2.43	5.04	190	470	680	1,040	260	…
Redwood, old-growth	7.5	10.0	7.4	6.9	4.20	6.15	420	700	800	940	260	240
Redwood, young-growth	5.9	7.9	5.7	5.2	3.11	5.22	270	520	890	1,110	300	250
Spruce, Engelmann	4.7	9.3	5.1	6.4	2.18	4.48	200	410	640	1,200	240	350
Spruce, red	6.0	10.8	6.9	8.4	2.72	5.54	260	550	750	1,290	220	350
Spruce, white	5.0	9.4	6.0	7.7	2.35	5.18	210	430	640	970	220	360

[a] Coast: grows west of the summit of the Cascade Mountains in OR and WA. Interior west: grows in CA and all counties in OR and WA east of but adjacent to the Cascade summit. Interior north: grows in remainder of OR and WA and ID, MT, and WY. Interior south: grows in UT, CO, AZ, and NM.

Results of tests on small, clear, straight-grained specimens. Data for dry specimens are from tests of seasoned material adjusted to a moisture content of 12%.

Source: U.S. Department of Agriculture: *Wood Handbook*.

Weight of Wood.— The weight of seasoned wood per cord is approximately as follows, assuming about 70 cubic feet of *solid wood* per cord: beech, 3300 pounds; chestnut, 2600 pounds; elm, 2900 pounds; maple, 3100 pounds; poplar, 2200 pounds; white pine, 2200 pounds; red oak, 3300 pounds; white oak, 3500 pounds. For additional weights of green and dry woods, see Table 2.

Weight per Foot of Wood, Board Measure.— The following is the weight in pounds of various kinds of woods, commercially known as dry timber, per foot board measure: white oak, 4.16; white pine, 1.98; Douglas fir, 2.65; short-leaf yellow pine, 2.65; red pine, 2.60; hemlock, 2.08; spruce, 2.08; cypress, 2.39; cedar, 1.93; chestnut, 3.43; Georgia yellow pine, 3.17; California spruce, 2.08. For other woods, divide the weight/ft^3 from Table 2 by 12 to obtain the approximate weight per board foot.

Effect of Pressure Treatment on Mechanical Properties of Wood.— The strength of wood preserved with creosote, coal-tar, creosote-coal-tar mixtures, creosote-petroleum mixtures, or pentachlorophenol dissolved in petroleum oil is not reduced. However, waterborne salt preservatives contain chemicals such as copper, arsenic, chromium, and ammonia, which have the potential of affecting mechanical properties of treated wood and

Copyright 2004, Industrial Press, Inc., New York, NY

causing mechanical fasteners to corrode. Preservative salt-retention levels required for marine protection may reduce bending strength by 10 per cent or more.

Density of Wood.— The following formula can be used to find the density of wood in lb/ft^3 as a function of its moisture content.

$$\rho = 62.4\left(\frac{G}{1 + G \times 0.009 \times M}\right)\left(1 + \frac{M}{100}\right)$$

where ρ is the density, G is the specific gravity of wood, and M is the moisture content expressed in per cent.

Table 2. Weights of American Woods, in Pounds per Cubic Foot

Species	Green	Airdry	Species	Green	Airdry	Species	Green	Airdry
Alder, red	46	28	Douglas fir, Rocky Mt. region	35	30	Oak, red	64	44
Ash, black	52	34	Elm, American	54	35	Oak, white	63	47
Ash, commercial white	48	41	Elm, rock	53	44	Pine, lodgepole	39	29
Ash, Oregon	46	38	Elm, slippery	56	37	Pine, northern white	36	25
Aspen	43	26	Fir, balsam	45	25	Pine, Norway	42	34
Basswood	42	26	Fir, commercial white	46	27	Pine, ponderosa	45	28
Beech	54	45	Gum, black	45	35	Pines, southern yellow:		
Birch	57	44	Gum, red	50	34	Pine, loblolly	53	36
Birch, paper	50	38	Hemlock, eastern	50	28	Pine, longleaf	55	41
Cedar, Alaska	36	31	Hemlock, western	41	29	Pine, shortleaf	52	36
Cedar, eastern red	37	33	Hickory, pecan	62	45	Pine, sugar	52	25
Cedar, northern white	28	22	Hickory, true	63	51	Pine, western white	35	27
Cedar, southern white	26	23	Honeylocust	61	…	Poplar, yellow	38	28
Cedar, western red	27	23	Larch, western	48	36	Redwood	50	28
Cherry, black	45	35	Locust, black	58	48	Spruce, eastern	34	28
Chestnut	55	30	Maple, bigleaf	47	34	Spruce, Engelmann	39	23
Cottonwood, eastern	49	28	Maple, black	54	40	Spruce, Sitka	33	28
Cottonwood, northern black	46	24	Maple, red	50	38	Sycamore	52	34
Cypress, southern	51	32	Maple, silver	45	33	Tamarack	47	37
Douglas fir, coast region	38	34	Maple, sugar	56	44	Walnut, black	58	38

Source: United States Department of Agriculture

Machinability of Wood.— The ease of working wood with hand tools generally varies directly with the specific gravity of the wood; the lower the specific gravity, the easier the wood is to cut with a sharp tool. A rough idea of the specific gravity of various woods can be obtained from the preceding table by dividing the weight of wood in lb/ft^3 by 62.355.

A wood species that is easy to cut does not necessarily develop a smooth surface when it is machined. Three major factors, other than specific gravity, influence the smoothness of the surface obtained by machining: interlocked and variable grain, hard deposits in the grain, and reaction wood. Interlocked and variable grain is a characteristic of many tropical and some domestic species; this type of grain structure causes difficulty in planing quarter sawn boards unless careful attention is paid to feed rates, cutting angles, and sharpness of the knives. Hard deposits of calcium carbonate, silica, and other minerals in the grain tend to dull cutting edges quickly, especially in wood that has been dried to the usual in service moisture content. Reaction wood results from growth under some physical stress such as occurs in leaning trunks and crooked branches. Generally, reaction wood occurs as tension wood in hardwoods and as compression wood in softwoods. Tension wood is particularly troublesome, often resulting in fibrous and fuzzy surfaces, especially in woods of lower density. Reaction wood may also be responsible for pinching saw blades, resulting in burning and dulling of teeth.

The Table 3 rates the suitability of various domestic hardwoods for machining. The data for each species represent the percentage of pieces machined that successfully met the listed quality requirement for the processes. For example, 62 per cent of the black walnut

Copyright 2004, Industrial Press, Inc., New York, NY

pieces planed came out perfect, but only 34 per cent of the pieces run on the shaper achieved good to excellent results.

Table 3. Machinability and Related Properties of Various Domestic Hardwoods

	Planing	Shaping	Turning	Boring	Mortising	Sanding
	Quality Required					
Type of Wood	Perfect	Good to Excellent	Fair to Excellent	Good to Excellent	Fair to Excellent	Good to Excellent
Alder, red	61	20	88	64	52	…
Ash	75	55	79	94	58	75
Aspen	26	7	65	78	60	…
Basswood	64	10	68	76	51	17
Beech	83	24	90	99	92	49
Birch	63	57	80	97	97	34
Birch, paper	47	22	…	…	…	…
Cherry, black	80	80	88	100	100	…
Chestnut	74	28	87	91	70	64
Cottonwood	21	3	70	70	52	19
Elm, soft	33	13	65	94	75	66
Hackberry	74	10	77	99	72	…
Hickory	76	20	84	100	98	80
Magnolia	65	27	79	71	32	37
Maple, bigleaf	52	56	8	100	80	…
Maple, hard	54	72	82	99	95	38
Maple, soft	41	25	76	80	34	37
Oak, red	91	28	84	99	95	81
Oak, white	87	35	85	95	99	83
Pecan	88	40	89	100	98	…
Sweetgum	51	28	86	92	53	23
Sycamore	22	12	85	98	96	21
Tanoak	80	39	81	100	100	…
Tupelo, black	48	32	75	82	24	21
Tupelo, water	55	52	79	62	33	34
Walnut, black	62	34	91	100	98	…
Willow	52	5	58	71	24	24
Yellow-poplar	70	13	81	87	63	19

The data above represent the percentage of pieces attempted that meet the quality requirement listed.

Nominal and Minimum Sizes of Sawn Lumber

Type of Lumber	Thickness (inches)			Face Widths (inches)		
	Nominal, T_n	Dry	Green	Nominal, W_n	Dry	Green
Boards	1	$\frac{3}{4}$	$\frac{25}{32}$	2 to 4	$W_n - \frac{1}{2}$	$W_n - \frac{7}{16}$
	$1\frac{1}{4}$	1	$1\frac{1}{32}$	5 to 7	$W_n - \frac{1}{2}$	$W_n - \frac{3}{8}$
	$1\frac{1}{2}$	$1\frac{1}{4}$	$1\frac{9}{32}$	8 to 16	$W_n - \frac{3}{4}$	$W_n - \frac{1}{2}$
Dimension Lumber	2	$1\frac{1}{2}$	$1\frac{9}{16}$	2 to 4	$W_n - \frac{1}{2}$	$W_n - \frac{7}{16}$
	$2\frac{1}{2}$	2	$2\frac{1}{16}$	5 to 6	$W_n - \frac{1}{2}$	$W_n - \frac{3}{8}$
	3	$2\frac{1}{2}$	$2\frac{9}{16}$	8 to 16	$W_n - \frac{3}{4}$	$W_n - \frac{1}{2}$
	$3\frac{1}{2}$	3	$3\frac{1}{16}$	…	…	…
	4	$3\frac{1}{2}$	$3\frac{9}{16}$	…	…	…
	$4\frac{1}{2}$	4	$4\frac{1}{16}$	…	…	…
Timbers	5 and up	…	$T_n - \frac{1}{2}$	5 and up	…	$W_n - \frac{1}{2}$

Source: National Forest Products Association: *Design Values for Wood Construction*. Moisture content: dry lumber ≤ 19%; green lumber > 19%. Dimension lumber refers to lumber 2 to 4 inches thick (nominal) and 2 inches or greater in width. Timbers refers to lumber of approximately square cross-section, 5 × 5 inches or larger, and a width no more than 2 inches greater than the thickness.

Copyright 2004, Industrial Press, Inc., New York, NY

Tabulated Properties of Ceramics, Plastics, and Metals

Typical Properties of Ceramics Materials

Material		Density[a] (lb/in.^{3})	Dielectric Strength (V/mil)	Coeff. of Expansion[b] (10^{-6} in./in.-°F)	Flexural Strength (10^3 psi)	Mohs's Hardness[c]	Operating Temperature (°F)	Tensile Strength (10^3 psi)	Compressive Strength (10^3 psi)	Thermal Conductivity[d] (Btu-ft-hr-ft^2-°F)
Machinable Glass Ceramic		0.09	1000	4.1–7.0		48 Ra	1472	…	50	0.85
		0.11	400	6	15	5.5	700	…	40	0.24
		0.10	380	5.2	14	5.0	1100	…	32	0.34
Glass-Mica	Machining Grades	0.09–0.10	400	10.5–11.2	12.5–13	90 Rh	750	6	40–45	0.24–0.29
		0.10	380	9.4	11	90 Rh	1100	5	32	0.34
	Molding Grades	0.13–0.17	300–325	11–11.5	9–10	90 Rh	700–750	6–6.5	33–35	0.29–0.31
		0.14	350	10.3	9	90 Rh	1300	6	30	0.3
Aluminum Silicate		0.10	80	2.5	4.5	1–2	1000	…	12	0.92
		0.08	100	2.9	10	6.0	2100	…	25	0.75
Alumina Silicate		0.08	70	…	…	…	2370	…	…	0.38
Silica Foam		0.03	80	0.3	0.4	NA	2000	…	1.4	0.10
TiO_2 (Titania)		0.14	100	4.61	20	8	1800	7.5	100	…
Lava (Grade A)		0.08	80	1.83	9	6	2000	2.5	40	0.92
Zirconium Phosphate		0.11	NA	0.5	7.5	NA	2800	…	30	0.4 (approx.)
ZrO_2		0.21	…	6.1	102	1300 V	…	…	261	1.69
$ZrO_2 \cdot SiO_2$ (Zircon)		0.11	220	1.94	16	7.5	1825	10	90	…
$2MgO \cdot SiO_2$ (Forsterite)		0.11	240	5.56	20	7.5	1825	10	85	4.58
$MgO \cdot SiO_2$ (Steatite)		0.09–0.10	210–240	3.83–5.44	18–21	7.5	1825	8.5–10	80–90	3.17–3.42
$2MgO \cdot 2Al_2O_3 \cdot 5SiO_2$ (Cordierite)		0.06	60	0.33	3.4	6.5	2000	2.5	18.5	1.00
		0.08	100–172	1.22–1.28	8–12	7–7.5	2000	3.5–3.7	30–40	1.00
		0.09	200	1.33	15	8	2000	4	50	1.83
Al_2O_3	94%	0.13	210	3.33	44	9	2700	20	315	16.00
(Alumina)	96%	0.13–0.14	210	3.5–3.7	48–60	9	2600–2800	25	375	20.3–20.7
	99.5%	0.14	200	3.72	70	9	2700	28	380	21.25
	99.9%	0.14	…	3.75	72	9	2900	…	400	…

[a] Obtain specific gravity by dividing density in lb/in.^{3} by 0.0361; for density in lb/ft^3, multiply lb/in.^{3} by 1728; for g/cm^3, multiply density in lb/in.^{3} by 27.68; for kg/m^3, multiply density in lb/in.^{3} by 27,679.9.

[b] To convert coefficient of expansion to 10^{-6} in./in.-°C, multiply table value by 1.8.

[c] Mohs's Hardness scale is used unless otherwise indicated as follows: Ra and Rh for Rockwell A and H scales, respectively; V for Vickers hardness.

[d] To convert conductivity from Btu-ft/hr-ft^2-°F to cal-cm/sec-cm^2-°C, divide by 241.9.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Properties of Plastics Materials

Material	Density[a] (lb/in^3)	Specific Gravity	Dielectric Strength (V/mil)	Coeff. of Expansion[b] (10^{-6} in/in-°F)	Tensile Modulus (10^3 psi)	Izod Impact (ft-lb/in of notch)	Flexural Modulus (ksi at 73°F)	% Elongation	Hardness[c]	Max. Operating Temp. (°F)
ABS, Extrusion Grade	0.038	1.05	…	53.0	275	7	300	…	105 Rr	200
ABS, High Impact	0.037	1.03	…	…	200	…	330	…	105 Rr	…
Acetal, 20% Glass	0.056	1.55	…	…	1000	0.9	715	…	94 Rm	…
Acetal, Copolymer	0.051	1.41	380	47.0	437	2	400	13	94 Rm	…
Acetyl, Homopolymer	0.051	1.41	…	58.0	310	…	320	…	94 Rm	200
Acrylic	0.043	1.19	500	35.0	400	0.5	400	2.7	94 Rm	180
Azdel	0.043	1.19	500	15.0	750	14	800	2.1	94 Rm	311
CPVC	0.056	1.55	…	34.0	400	3	400	4	…	212
Fiber Glass Sheet	0.067	1.87	…	11.1	…	8	1	…	101 Rm	260
Nylon 6, 30% Glass	0.050	1.39	…	…	1350	2.8	1400	…	119 Rr	…
Nylon 6, Cast	0.042	1.16	295	45.0	380	1.4	450	20	100 Rr	210
Nylon 6/6, Cast	0.047	1.30	…	…	…	…	…	…	…	…
Nylon 6/6, Extruded	0.041	1.14	600	45.0	390	1	…	240	118 Rr	230
Nylon 60L, Cast	0.042	1.16	…	…	…	2.2	…	…	…	…
PET, unfilled	0.049	1.36	1300	39.0	500	0.5	400	70	…	230
PTFE (Teflon)	0.079	2.19	480	50.0	225	3	80	350	…	…
PVC	0.050	1.39	500	29.5	550	0.8	400	31–40	110 Rr	170
PVDF	0.064	1.77	260	60.0	320	3	200	80	100 Rr	180
Phenolics	0.050	1.38	…	11.1	…	2.4	1000	…	100 Rm	248
Polycarbonate	0.043	1.19	380	37.5	345	14	340	110	74 Rm	290
Polyetherimide	0.046	1.27	480	…	430	1.1	480	…	…	…
Polyethylene, HD	0.035	0.97	475	20.0	156	6	160	900	…	180
Polyethylene, UHMW	0.034	0.94	710	19.0	110	No Break	130	450	64 Rr	176
Polymethylpentene	0.030	0.83	…	…	220	2.5	…	…	…	…
Polymid, unfilled	0.051	1.41	560	…	300	1.5	…	…	…	…
Polyphenylene Sulfide	0.047	1.30	380	…	…	0.5	550	…	…	…
Polypropylene	0.033	0.91	600	96.0	155	0.75	200	120	92 Rr	150
Polysulfone	0.045	1.25	425	31.0	360	1.2	390	50	120 Rr	325
Polyurethane	0.038	1.05	…	…	…	…	…	465–520	…	…

[a] To obtain specific gravity, divide density in lb/in^3 by 0.0361; for density in lb/ft^3, multiply lb/in^3 by 1728; for g/cm^3, multiply density in lb/in^3 by 27.68; for kg/m^3, multiply density in lb/in^3 by 27,679.9.

[b] To convert coefficient of expansion to 10^{-6} in/in-°C, multiply table value by 1.8.

[c] Hardness value scales are as follows: Rm for Rockwell M scale; Rr for Rockwell R scale.

Copyright 2004, Industrial Press, Inc., New York, NY

Mechanical Properties of Various Investment Casting Alloys

Alloy Designation	Material Condition	Tensile Strength (10^3 psi)	0.2% Yield Strength[a] (10^3 psi)	% Elongation	Hardness
Aluminum					
356	As Cast	32–40	22–30	3–7	…
A356	As Cast	38–40	28–36	3–10	…
A357	As Cast	33–50	27–40	3–9	…
355, C355	As Cast	35–50	28–39	1–8	…
D712 (40E)	As Cast	34–40	25–32	4–8	…
A354	As Cast	47–55	36–45	2–5	…
RR-350	As Cast	32–45	24–38	1.5–5	…
Precedent 71	As Cast	35–55	25–45	2–5	…
KO-1	As Cast	56–60	48–55	3–5	…
Copper-Base Alloys[a]					
Al Bronze C (954)	As Cast	75–85	30–40	10–20	80–85 Rb
	Heat-Treated	90–105	45–55	6–10	91–96 Rb
Al Bronze D (955)	As Cast	90–100	40–50	6–10	91–96 Rb
	Heat-Treated	110–120	60–70	5–8	93–98 Rb
Manganese Bronze, A	…	65–75	25–40	16–24	60–65 Rb
Manganese Bronze, C	…	110–120	60–70	8–16	95–100 Rb
Silicon Bronze	…	45	18	20	…
Tin Bronze	…	40–50	18–30	20–35	40–50 Rb
Lead. Yellow Brass (854)	…	30–50	11–20	15–25	…
Red Brass	…	30–40	14–25	20–30	30–35 Rb
Silicon Brass	…	70	32	24	…
Pure Copper	…	20–30	…	4–50	35–42 Rb
Beryllium Cu 10C (820)	As Cast	45–50	40–45	15–20	50–55 Rb
	Hardened	90–100	90–130	3–8	90–95 Rb
Beryllium Cu 165C (824)	…	70–155	40–140	1–15	60 Rb–38 Rc
Beryllium Cu 20C (825)	As Cast	70–80	50–55	18–23	75–80 Rb
	Hardened	110–160	…	1–4	25–44 Rc
Beryllium Cu 275C (828)	As Cast	80–90	…	15–20	80–85 Rb
Chrome Copper	…	33–50	20–40	20–30	70–78 Rb
Carbon and Low-Alloy Steels and Iron					
IC 1010	Annealed	50–60	30–35	30–35	50–55 Rb
IC 1020	Annealed	60–70	40–45	25–40	80 Rb
IC 1030	Annealed	65–75	45–50	20–30	75 Rb
	Hardened	85–150	60–150	0–15	20–50 Rc
IC 1035	Annealed	70–80	45–55	20–30	80 Rb
	Hardened	90–150	85–150	0–15	25–52 Rc
IC 1045	Annealed	80–90	50–60	20–25	100 Rb
	Hardened	100–180	90–180	0–10	25–57 Rc
IC 1050	Annealed	90–110	50–65	20–25	100 Rb
	Hardened	125–180	100–180	0–10	30–60 Rc
IC 1060	Annealed	100–120	55–70	5–10	25 Rc
	Hardened	120–200	100–180	0–3	30–60 Rc
IC 1090	Annealed	110–150	70–80	12–20	30 Rc
	Hardened	130–180	130–180	0–3	37–50 Rc
IC 2345	Hardened	130–200	110–180	5–10	30–58 Rc
IC 4130	Hardened	130–170	100–130	5–20	23–49 Rc
IC 4140	Hardened	130–200	100–155	5–20	29–57 Rc
IC 4150	Hardened	140–200	120–180	5–10	25–58 Rc
IC 4330	Hardened	130–190	100–175	5–20	25–48 Rc
IC 4340	Hardened	130–200	100–180	5–20	20–55 Rc
IC 4620	Hardened	110–150	90–130	10–20	20–32 Rc
IC 6150, IC 8740	Hardened	140–200	120–180	5–10	30–60 Rc
IC 8620	Hardened	100–130	80–110	10–20	20–45 Rc
IC 8630	Hardened	120–170	100–130	7–20	25–50 Rc
IC 8640	Hardened	130–200	100–180	5–20	30–60 Rc

Copyright 2004, Industrial Press, Inc., New York, NY

Mechanical Properties of Various Investment Casting Alloys *(Continued)*

Alloy Designation	Material Condition	Tensile Strength (10^3 psi)	0.2% Yield Strength[a] (10^3 psi)	% Elongation	Hardness
Carbon and Low-Alloy Steels and Iron *(Continued)*					
IC 8665	Hardened	170–220	140–200	0–10	…
IC 8730	Hardened	120–170	110–150	7–20	…
IC 52100	Hardened	180–230	140–180	1–7	30–65 Rc
IC 1722AS	Hardened	130–170	100–140	6–12	25–48 Rc
1.2% Si Iron	…	50–60	37–43	30–35	55 Rb
Ductile Iron, Ferritic	Annealed	60–80	40–50	18–24	143–200 Bhn
Ductile Iron, Pearlitic	Normalized	100–120	70–80	3–10	243–303 Bhn
Hardenable Stainless Steel					
CA-15	Hardened	95–200	75–160	5–12	94 Rb–45 Rc
IC 416	Hardened	95–200	75–160	3–8	94 Rb–45 Rc
CA-40	Hardened	200–225	130–210	0–5	30–52 Rc
IC 431	Hardened	110–160	75–105	5–20	20–40 Rc
IC 17–4	Hardened	150–190	140–160	6–20	34–44 Rc
Am-355	Hardened	200–220	150–165	6–12	…
IC 15–5	Hardened	135–170	110–145	5–15	26–38 Rc
CD-4M Cu	Annealed	100–115	75–85	20–30	94–100 Rb
	Hardened	135–145	100–120	10–25	28–32 Rc
Austenitic Stainless Steels					
CF-3, CF-3M, CF-8, CF-8M, IC 316F	Annealed	70–85	40–50	35–50	90 Rb (max)
CF-8C	Annealed	70–85	32–36	30–40	90 Rb (max)
CF-16F	Annealed	65–75	30–35	35–45	90 Rb (max)
CF-20	Annealed	65–75	30–45	35–60	90 Rb (max)
CH-20	Annealed	70–80	30–40	30–45	90 Rb (max)
CN-7M	Annealed	65–75	25–35	35–45	90 Rb (max)
IC 321, CK-20	Annealed	65–75	30–40	35–45	90 Rb (max)
Nickel-Base Alloys					
Alloy B	Annealed	75–85	50–60	8–12	90–100 Rb
Alloy C	As Cast	80–95	45–55	8–12	90–100 Rb
	Annealed	75–95	45–55	8–12	90 Rb–25 Rc
Alloy X[b]	AC to 24°C	63–70	41–45	10–15	85–96 Rb
	AC to 816°C	35–45	…	12–20	…
Invar (Fe–Ni alloy)	As Cast	50–60	25–30	30–40	50–60 Rb
In 600 (Inconel)	As Cast	65–75	35–40	10–20	80–90 Rb
In 625 (Inconel)	Annealed	80–100	40–55	15–30	10–20 Rc
Monel 410	As Cast	65–75	32–38	25–35	65–75 Rb
S Monel	Annealed	100–110	55–65	5–10	20–28 Rc
	Hardened	120–140	85–100	0	32–38 Rc
RH Monel	As Cast	100–110	60–80	10–20	20–30 Rc
Monel E	As Cast	65–80	33–40	25–35	67–78 Rb
M-35 Monel	As Cast	65–80	25–35	25–40	65–85 Rb
Cobalt-Base Alloys					
Cobalt 21	As Cast	95–130	65–95	8–20	24–32 Rc
Cobalt 25	As Cast	90–120	60–75	15–25	20–25 Rc
Cobalt 31	As Cast	105–130	75–90	6–10	20–30 Rc
Cobalt 36	As Cast	90–105	60–70	15–20	30–36 Rc
F75	As Cast	95–110	70–80	8–15	25–34 Rc
N-155	Sol. Anneal	90–100	50–60	15–30	90–100 Rb

[a] For copper alloys, yield strength is determined by 0.5% extension under load or 0.2% offset method. A number in parentheses following a copper alloy indicates the UNS designation of that alloy (for example, Al Bronze C (954) identifies the alloy as UNS C95400).

[b] AC = air cooled to temperature indicated.

Source: Investment Casting Institute. Mechanical properties are average values of separately cast test bars, and are for reference only. Items marked … indicates data are not available. Alloys identified by IC followed by an SAE designation number (IC 1010 steel, for example) are generally similar to the SAE material although properties and chemical composition may be different.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Properties of Compressed and Sintered Powdered Metal Alloys

Alloy Number[a] and Nominal Composition (%)		Density (g/cc)	Hardness	Strength (10^3 psi)			% Elongation
				Transverse Rupture	Ultimate Tensile	Yield	
Copper Base							
…	100Cu	7.7–7.9	81–82 Rh	54–68	24–34	…	10–26
CZP-3002	70Cu, 1.5Pb, Bal. Zn	8	75 Rh	…	33.9	…	24
CNZ-1818	63Cu, 17.5Ni, Bal. Zn	7.9	90 Rh	73	34	20	11
CTG-1004	10Sn, 4.4C, Bal. Cu	7	67 Rh	20	9.4	6.5	6
CTG-1001	10Sn, 1C, Bal. Cu	6.5	45 Rh	25.8	15.1	9.6	9.7
Iron Base (Balance of composition, Fe)							
FC-2015	23.5Cu, 1.5C	6.5	65 Rb	80	52.4	48.5	0
FC-0800	8Cu, 0.4C	6.3–6.8	39–55 Rb	75–100	38–54	32–47	1 or less
FX-2008	20Cu, 1C	7.3	93 Rb	164.2	72.3	57.7	2
FN-0408	4Ni, 1–2Cu, 0.75C	6.3–7	64–84 Rb	70–107	37–63	30–47	1–1.6
F-0000	100Fe	6.5	26 Rf	37.7	15.7	11	5.7
FN-0005	0.45C, 0.50 MnS	6.4–6.8	66–78 Rf	44–61	…	…	…
F-0000	0.02C, 0.45P	6.6–7.2	35–50 Rb	90–125	…	29–38	3.9–5.5
F-0008	0.6–0.9C	6.2–7	50–70 Rb	61–100	35–57	30–40	<0.5 to 1
FC-0508	0.6–0.9C, 4–6Cu	5.9–6.8	60–80 Rb	100–145	58–82	50–70	<0.5 to 1
FN-0405	4Ni, 0.5C	6.6–7.0	73–82 Rb	90–100	47–50	38–40	<1
FN-0208	2Ni, 0.8C	6.6–7.0	50–70 Rb	70–108	47–58	35–51	<1
FN-0205	2Ni, 0.5C	6.6–7.0	51–61 Rb	72–93	35–45	27–31	2.0–2.5
FN-0200	2Ni, 0.25C	6.6	29 Rb	57.5	25.8	19.0	1.3
FC-0208	2Cu, 0.75C	6.5–6.7	68–72 Rb	95–107	56–61	51–54	up to 1
FC-2008	20Cu, 1C	6.2	45 Rb	79.5	47.8	40.0	1.3
…	4Ni, 0.6C, 1.6Cu, 0.55Mo	7.0	92 Rb	190.0	100.0	65.0	2.5
FL-4605	1.8Ni, 0.6C, 1.6Cu, 0.55Mo	7.0	87 Rb	170.0	80.0	55.0	2.5
FL-4605	1.8Ni, 0.6C, 0.55Mo	7.0	80 Rb	150.0	…	…	…
SS-316L	17Cr, 13Ni, 2.2Mo, 0.9Si	6.5	65 Rb	94.0	45.0	30.0	6.0
…	17Cr, 13Ni, 2.2Mo, 0.9Si, 15–20Cu	7.3	66 Rb	108.6	59.2	49.7	4.3
SS-410	13Cr, 0.8Si, 0.8Mn	6.2	15 Rc	85.0	66.7	56.9	0
FL-4608	2Cu, 3.8Ni, 0.9C, 0.75Mo	6.8	24 Rc	107.3	55.8	46.5	1.5
SS-303N1	18Cr, 11Ni, 1Mn	6.4	62 Rb	86.0	39.0	32.0	0.5
SS-304N1	19Cr, 10Ni, 1Mn	6.4	61 Rb	112.0	43.0	38.0	0.5
Tungsten Base							
90W, 6Ni, 4Cu		17.0	24 Rc	…	110	80	6
90W, 7Ni, 3Cu		17.0	25 Rc	…	120	88	10
92.5W, 5.25Ni, 2.25Cu		17.5	26 Rc	…	114	84	7
92.5W, Bal. Ni, Fe, and Mo		17.6	30 Rc	…	120	90	4
93W, Bal. Ni, Fe, and Mo		17.7	32 Rc	…	125	95	4
95W, 3.5Ni, 1.5Cu		18.0	27 Rc	…	110	85	7
95W, 3.5Ni, 1.5Fe		18.0	27 Rc	…	120	90	7
97W, 2.1Ni, 0.9Fe		18.5	28 Rc	…	123	85	5

[a] Copper- and iron-base alloy designations are Metal Powder Industries Federation (MPIF) alloy numbers.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Elastic Properties of Materials

Material	Modulus of Elasticity (10^6 psi)	Shear Modulus (10^6 psi)	Bulk Modulus (10^6 psi)	Poisson's Ratio
Aluminum, var. alloys	9.9–10.3	3.7–3.9	9.9–10.2	0.330–0.334
Aluminum, 6061-T6	10.2	3.8	…	0.35
Aluminum, 2024-T4	10.6	4.0	…	0.32
Beryllium copper	18	7	…	0.29
Brass, 70–30	15.9	6	15.7	0.331
Brass, cast	14.5	5.3	16.8	0.357
Bronze	14.9	6.5	…	0.14
Copper	15.6	5.8	17.9	0.355
Glass	6.7	2.7	…	0.24
Glass ceramic (machinable)	9.7	3.7	…	0.29
Inconel	31	11	…	0.27–0.38
Iron, cast	13.5–21.0	5.2–8.2	8.4–15.5	0.221–0.299
Iron, ductile	23.8–25.2	9.1–9.6	…	0.26–0.31
Iron, grey cast	14.5	6	…	0.211
Iron, malleable	23.6	9.3	17.2	0.271
Lead	5.3	1.9	…	0.43
Magnesium	6.5	2.4	…	0.35
Magnesium alloy	6.3	2.5	4.8	0.281
Molybdenum	48	17	…	0.307
Monel metal	25	9.5	22.5	0.315
Nickel silver	18.5	7	…	0.322
Nickel steel	30	11.5	…	0.291
Phosphor bronze	13.8	5.1	16.3	0.359
Stainless steel 18–8	27.6	10.6	23.6	0.305
Steel, cast	28.5	11.3	20.2	0.265
Steel, cold-rolled	29.5	11.5	23.1	0.287
Steel, all others	28.6–30.0	11.0–11.9	22.6–24.0	0.283–0.292
Titanium (99.0 Ti)	15–16	6.5	…	0.24
Titanium (Ti-8Al-1Mo-1V)	18	6.8	…	0.32
Zinc, cast alloys	10.9–12.4	…	…	0.33
Zinc, wrought alloys	6.2–14	…	…	0.33
Z-nickel	30	11	…	0.36

Data represent typical values, but material properties may vary widely, depending on exact composition, material condition, and processing. Symbol … indicates no data available.

Average Ultimate Strength of Common Materials other than Metals
(pounds per square inch)

Material	Compression	Tension	Material	Compression	Tension
Bricks, best hard	12,000	400	Concrete, Portland	1,000	200
Bricks, light red	1,000	40	Concrete, Portland, 1 year old	2,000	400
Brickwork, common	1,000	50	Granite	19,000	700
Brickwork, best	2,000	300	Limestone and sandstone	9,000	300
Cement, Portland, 1 month old	2,000	400	Trap rock	20,000	800
Cement, Portland, 1 year old	3,000	500	Slate	14,000	500
			Vulcanized fiber	39,000	13,000

Copyright 2004, Industrial Press, Inc., New York, NY

Minimum Tensile Strength of Spring Wire by Diameter

Wire Dia. (in.)	Wire Type						
	Music Wire	Hard-Drawn MB	Oil Temp. MB	Stainless Steel 18-8	Cr–V Alloy	Phosphor Bronze	Chrome Silicon
	Minimum Tensile Strength (10^3 psi)						
0.004	439	…	…	325	…	140	…
0.008	399	…	…	325	…	140	…
0.012	377	…	…	316	…	…	…
0.020	350	283	288	300	…	…	…
0.028	333	271	281	284	…	…	…
0.032	327	265	275	278	281	…	300
0.035	322	261	268	274	276	…	298
0.041	314	255	261	270	270	135	298
0.047	307	248	254	262	263	…	292
0.054	301	243	248	258	257	…	292
0.063	293	237	242	251	251	130	290
0.072	287	232	236	245	245	…	288
0.080	282	227	230	240	240	…	285
0.092	275	220	225	233	235	…	280
0.105	269	216	220	227	229	125	275
0.120	263	210	215	221	222	…	275
0.135	258	206	210	213	219	…	270
0.148	253	203	205	207	215	…	268
0.162	249	200	200	200	212	…	162
0.177	245	195	195	195	210	…	260
0.192	241	192	190	189	206	…	260
0.207	238	190	185	185	204	…	260
0.225	225	186	183	180	200	120	255
0.250	220	182	180	174	196	…	250
0.312	…	174	178	160	189	110	245
0.375	…	167	175	…	187	…	240
0.437	…	165	170	…	186	…	235
0.500	…	156	165	…	185	100	230

For allowable working stresses and recommended design stresses in bending, related to severity of service, refer to Fig. 1 through Fig. 10 on pages 314 through 317, and for endurance limits for compression springs made from these materials refer to Fig. 11 on page 319 in the section on spring stresses.

Effect of Temperature on Strength and Elasticity of Metals.— Most ferrous metals have a maximum strength at approximately 400 degrees F, whereas the strength of nonferrous alloys is a maximum at about room temperature. The table on page 421 gives general data for variation in metal strength with temperature.

The modulus of elasticity of metals decreases regularly with increasing temperatures above room temperature until at some elevated temperature it falls off rapidly and reaches zero at the melting point.

Influence of Temperature on the Strength of Metals

Material	Degrees Fahrenheit							
	210	400	570	750	930	1100	1300	1475
	Strength in Per Cent of Strength at 70 Degrees F							
Wrought iron	104	112	116	96	76	42	25	15
Cast iron	…	100	99	92	76	42	…	…
Steel castings	109	125	121	97	57	…	…	…
Structural steel	103	132	122	86	49	28	…	…
Copper	95	85	73	59	42	…	…	…
Bronze	101	94	57	26	18	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Pressure and Flow of Water

Water Pressure.— Water is composed of two elements, hydrogen and oxygen, in the ratio of two volumes of hydrogen to one of oxygen. In the common system of measure, water boils under atmospheric pressure at 212 degrees F and freezes at 32 degrees F. Water's greatest density is 62.425 pounds per cubic foot, at 39.1 degrees F. In metric (SI) measure, water boils under atmospheric pressure at 100°C (Celsius) and freezes at 0°C. Its density is equal to 1 kilogram per liter, where 1 liter is 1 cubic decimeter. Also in metric SI, pressure is given in pascals (Pa) or the equivalent newtons per square meter. See page 2544 for additional information on the metric (SI) system of units.

For higher temperatures, the pressure slightly decreases in the proportion indicated by the table *Density of Water at Different Temperatures*. The pressure per square inch is equal in all directions, downwards, upwards, and sideways. Water can be compressed only to a very slight degree, the compressibility being so slight that even at the depth of a mile, a cubic foot of water weighs only about one-half pound more than at the surface.

Pressure in Pounds per Square Inch for Different Heads of Water

Head, ft	0	1	2	3	4	5	6	7	8	9
0	…	0.43	0.87	1.30	1.73	2.16	2.60	3.03	3.46	3.90
10	4.33	4.76	5.20	5.63	6.06	6.49	6.93	7.36	7.79	8.23
20	8.66	9.09	9.53	9.96	10.39	10.82	11.26	11.69	12.12	12.56
30	12.99	13.42	13.86	14.29	14.72	15.15	15.59	16.02	16.45	16.89
40	17.32	17.75	18.19	18.62	19.05	19.48	19.92	20.35	20.78	21.22
50	21.65	22.08	22.52	22.95	23.38	23.81	24.25	24.68	25.11	25.55
60	25.98	26.41	26.85	27.28	27.71	28.14	28.58	29.01	29.44	29.88
70	30.31	30.74	31.18	31.61	32.04	32.47	32.91	33.34	33.77	34.21
80	34.64	35.07	35.51	35.94	36.37	36.80	37.24	37.67	38.10	38.54
90	38.97	39.40	39.84	40.27	40.70	41.13	41.57	42.00	42.43	42.87

Heads of Water in Feet Corresponding to Certain Pressures in Pounds per Square Inch

Pressure, lb/in^2	0	1	2	3	4	5	6	7	8	9
0	…	2.3	4.6	6.9	9.2	11.5	13.9	16.2	18.5	20.8
10	23.1	25.4	27.7	30.0	32.3	34.6	36.9	39.3	41.6	43.9
20	46.2	48.5	50.8	53.1	55.4	57.7	60.0	62.4	64.7	67.0
30	69.3	71.6	73.9	76.2	78.5	80.8	83.1	85.4	87.8	90.1
40	92.4	94.7	97.0	99.3	101.6	103.9	106.2	108.5	110.8	113.2
50	115.5	117.8	120.1	122.4	124.7	127.0	129.3	131.6	133.9	136.3
60	138.6	140.9	143.2	145.5	147.8	150.1	152.4	154.7	157.0	159.3
70	161.7	164.0	166.3	168.6	170.9	173.2	175.5	177.8	180.1	182.4
80	184.8	187.1	189.4	191.7	194.0	196.3	198.6	200.9	203.2	205.5
90	207.9	210.2	212.5	214.8	217.1	219.4	221.7	224.0	226.3	228.6

Volumes of Water at Different Temperatures

Degrees F	Volume	Degrees F	Volume	Degrees F	Volume	Degrees F	Volume
39.1	1.00000	86	1.00425	131	1.01423	176	1.02872
50	1.00025	95	1.00586	140	1.01678	185	1.03213
59	1.00083	104	1.00767	149	1.01951	194	1.03570
68	1.00171	113	1.00967	158	1.02241	203	1.03943
77	1.00286	122	1.01186	167	1.02548	212	1.04332

Copyright 2004, Industrial Press, Inc., New York, NY

Density of Water at Different Temperatures

Temp. (°F)	Wt. per Cu Ft (lb/ft³)	Temp. (°F)	Wt. per Cu Ft (lb/ft³)	Temp. (°F)	Wt. per Cu Ft (lb/ft³)	Temp. (°F)	Wt. per Cu Ft (lb/ft³)	Temp. (°F)	Wt. per Cu Ft (lb/ft³)	Temp. (°F)	Wt. per Cu Ft (lb/ft³)
32	62.42	130	61.56	220	59.63	320	56.66	420	52.6	520	47.6
40	62.42	140	61.37	230	59.37	330	56.30	430	52.2	530	47.0
50	62.41	150	61.18	240	59.11	340	55.94	440	51.7	540	46.3
60	62.37	160	60.98	250	58.83	350	55.57	450	51.2	550	45.6
70	62.31	170	60.77	260	58.55	360	55.18	460	50.7	560	44.9
80	62.23	180	60.55	270	58.26	370	54.78	470	50.2	570	44.1
90	62.13	190	60.32	280	57.96	380	54.36	480	49.7	580	43.3
100	62.02	200	60.12	290	57.65	390	53.94	490	49.2	590	42.6
110	61.89	210	59.88	300	57.33	400	53.50	500	48.7	600	41.8
120	61.74	212	59.83	310	57.00	410	53.00	510	48.1	…	…

Table of Horsepower due to Certain Head of Water

Head in Feet	Horse-power	Head in Feet	Horse-power	Head in Feet	Horse-power	Head in Feet	Horse-power	Head in Feet	Horse-power
1	0.0016	170	0.274	340	0.547	520	0.837	1250	2.012
10	0.0161	180	0.290	350	0.563	540	0.869	1300	2.093
20	0.0322	190	0.306	360	0.580	560	0.901	1350	2.173
30	0.0483	200	0.322	370	0.596	580	0.934	1400	2.254
40	0.0644	210	0.338	380	0.612	600	0.966	1450	2.334
50	0.0805	220	0.354	390	0.628	650	1.046	1500	2.415
60	0.0966	230	0.370	400	0.644	700	1.127	1550	2.495
70	0.1127	240	0.386	410	0.660	750	1.207	1600	2.576
80	0.1288	250	0.402	420	0.676	800	1.288	1650	2.656
90	0.1449	260	0.418	430	0.692	850	1.368	1700	2.737
100	0.1610	270	0.435	440	0.708	900	1.449	1750	2.818
110	0.1771	280	0.451	450	0.724	950	1.529	1800	2.898
120	0.1932	290	0.467	460	0.740	1000	1.610	1850	2.978
130	0.2093	300	0.483	470	0.757	1050	1.690	1900	3.059
140	0.2254	310	0.499	480	0.773	1100	1.771	1950	3.139
150	0.2415	320	0.515	490	0.789	1150	1.851	2000	3.220
160	0.2576	330	0.531	500	0.805	1200	1.932	2100	3.381

The table gives the horsepower of 1 cubic foot of water per minute, and is based on an efficiency of 85 per cent.

Flow of Water in Pipes.— The quantity of water that will flow through a pipe depends primarily on the head but also on the diameter of the pipe, the character of the interior surface, and the number and shape of the bends. The head may be either the distance between the levels of the surface of water in a reservoir and the point of discharge, or it may be caused by mechanically applied pressure, as by pumping, when the head is calculated as the vertical distance corresponding to the pressure.

One pound per square inch is equal to 2.309 feet head, and a 1-foot head is equal to a pressure of 0.433 pound per square inch.

All formulas for finding the amount of water that will flow through a pipe in a given time are approximate. The formula that follows will give results within 5 or 10 per cent of actual flows, if applied to pipe lines carefully laid and in fair condition.

Copyright 2004, Industrial Press, Inc., New York, NY

$$V = C\sqrt{\frac{hD}{L + 54D}}$$

where V = approximate mean velocity in feet per second; C = coefficient from the accompanying table; D = diameter of pipe in feet; h = total head in feet; and, L = total length of pipe line in feet.

Values of Coefficient *C*

Dia. of Pipe			Dia. of Pipe			Dia. of Pipe		
Feet	Inches	*C*	Feet	Inches	*C*	Feet	Inches	*C*
0.1	1.2	23	0.8	9.6	46	3.5	42	64
0.2	2.4	30	0.9	10.8	47	4.0	48	66
0.3	3.6	34	1.0	12.0	48	5.0	60	68
0.4	4.8	37	1.5	18.0	53	6.0	72	70
0.5	6.0	39	2.0	24.0	57	7.0	84	72
0.6	7.2	42	2.5	30.0	60	8.0	96	74
0.7	8.4	44	3.0	36.0	62	10.0	120	77

Example: A pipe line, 1 mile long, 12 inches in diameter, discharges water under a head of 100 feet. Find the velocity and quantity of discharge.

From the table, the coefficient C is found to be 48 for a pipe 1 foot in diameter, hence:

$$V = 48\sqrt{\frac{100 \times 1}{5280 + 54 \times 1}} = 6.57 \text{ feet per second}$$

To find the discharge in cubic feet per second, multiply the velocity found by the area of cross-section of the pipe in square feet:

$$6.57 \times 0.7854 = 5.16 \text{ cubic feet per second}$$

The loss of head due to a bend in the pipe is most frequently given as the equivalent length of straight pipe, which would cause the same loss in head as the bend. Experiments show that a right-angle bend should have a radius of about three times the diameter of the pipe. Assuming this curvature, then, if d is the diameter of the pipe in inches and L is the length of straight pipe in feet that causes the same loss of head as the bend in the pipe, the following formula gives the equivalent length of straight pipe that should be added to simulate a right-angle bend:

$$L = 4d \div 3$$

Thus, the loss of head due to a right-angle bend in a 6-inch pipe would be equal to that in 8 feet of straight pipe. Experiments undertaken to determine the losses due to valves in pipe lines indicate that a fully open gate valve in a pipe causes a loss of head corresponding to the loss in a length of pipe equal to six diameters.

Buoyancy.— A body submerged in water or other fluid will lose in weight an amount equal to the weight of the fluid displaced by the body. This is known as the principle of Archimedes.

Example, Weight of a Submerged Body: To illustrate, suppose the upper surface of a 10-inch cube is 20 inches below the surface of the water. The total downward pressure on the upper side of this cube will equal the area of the top surface of the cube, in square inches, multiplied by the product of the depth, in inches, to which the surface is submerged and the weight of 1 cubic inch of water.

Thus, the
weight of 1 cubic inch of water: 0.03617 pounds
downward pressure: 10 × 10 × 20 × 0.03617 = 72.34 pounds
upward pressure on the under side: 10 × 10 × 30 × 0.03617 = 108.51 pounds
weight of the water displaced by the body: 10 × 10× 10 × 0.03617 = 36.17 pounds
upward pressure – downward pressure: 108.51 –72.34 = 36.17 pounds

This excess of upward pressure explains why it is comparatively easy to lift a submerged stone or other body.

Copyright 2004, Industrial Press, Inc., New York, NY

Flow of Water Through Nozzles in Cubic Feet per Second

Head in Feet, at Nozzle	Pressure, lb/in^2	Theoretical Velocity, ft/s	Diameter of Nozzle, Inches							
			1	1.5	2	2.5	3	3.5	4	4.5
5	2.17	17.93	0.10	0.22	0.39	0.61	0.88	1.20	1.56	1.98
10	4.33	25.36	0.14	0.31	0.55	0.86	1.24	1.69	2.21	2.80
20	8.66	35.87	0.20	0.44	0.78	1.22	1.76	2.40	3.13	3.96
30	12.99	43.93	0.24	0.54	0.96	1.50	2.16	2.93	3.83	4.85
40	17.32	50.72	0.28	0.62	1.11	1.73	2.49	3.39	4.43	5.60
50	21.65	56.71	0.31	0.70	1.24	1.93	2.78	3.79	4.95	6.26
60	25.99	62.12	0.34	0.76	1.36	2.12	3.05	4.15	5.42	6.86
70	30.32	67.10	0.37	0.82	1.46	2.29	3.29	4.48	5.86	7.41
80	34.65	71.73	0.39	0.88	1.56	2.45	3.52	4.79	6.26	7.92
90	38.98	76.08	0.41	0.93	1.66	2.59	3.73	5.08	6.64	8.40
100	43.31	80.20	0.44	0.98	1.75	2.73	3.94	5.36	7.00	8.86
120	51.97	87.85	0.48	1.08	1.92	2.99	4.31	5.87	7.67	9.70
140	60.63	94.89	0.52	1.16	2.07	3.23	4.66	6.34	8.28	10.48
160	69.29	101.45	0.55	1.24	2.21	3.46	4.98	6.78	8.85	11.20
180	77.96	107.60	0.59	1.32	2.35	3.67	5.28	7.19	9.39	11.88
200	86.62	113.42	0.62	1.39	2.47	3.87	5.57	7.58	9.90	12.53
250	108.27	126.81	0.69	1.56	2.77	4.32	6.22	8.47	11.07	14.01
300	129.93	138.91	0.76	1.70	3.03	4.74	6.82	9.28	12.12	15.34
350	151.58	150.04	0.82	1.84	3.27	5.11	7.37	10.02	13.09	16.57
400	173.24	160.40	0.87	1.97	3.50	5.47	7.87	10.72	14.00	17.72
450	194.89	170.13	0.93	2.09	3.71	5.80	8.35	11.37	14.85	18.79
500	216.54	179.33	0.98	2.20	3.91	6.11	8.80	11.98	15.65	19.81
Head in Feet, at Nozzle	Pressure, lb/in^2	Theoretical Velocity, ft/s	Diameter of Nozzle, Inches							
			5	6	7	8	9	10	11	12
5	2.17	17.93	2.45	3.52	4.79	6.3	7.9	9.8	11.8	14.1
10	4.33	25.36	3.46	4.98	6.78	8.9	11.2	13.8	16.7	19.9
20	8.66	35.87	4.89	7.04	9.59	12.5	15.8	19.6	23.7	28.2
30	12.99	43.93	5.99	8.63	11.74	15.3	19.4	24.0	29.0	34.5
40	17.32	50.72	6.92	9.96	13.56	17.7	22.4	27.7	33.5	39.8
50	21.65	56.71	7.73	11.13	15.16	19.8	25.1	30.9	37.4	44.5
60	25.99	62.12	8.47	12.20	16.60	21.7	27.4	33.9	41.0	48.8
70	30.32	67.10	9.15	13.18	17.93	23.4	29.6	36.6	44.3	52.7
80	34.65	71.73	9.78	14.08	19.17	25.0	31.7	39.1	47.3	56.3
90	38.98	76.08	10.37	14.94	20.33	26.6	33.6	41.5	50.2	59.8
100	43.31	80.20	10.94	15.75	21.43	28.0	35.4	43.7	52.9	63.0
120	51.97	87.85	11.98	17.25	23.48	30.7	38.8	47.9	58.0	69.0
140	60.63	94.89	12.94	18.63	25.36	33.1	41.9	51.8	62.6	74.5
160	69.29	101.45	13.83	19.92	27.11	35.4	44.8	55.3	66.9	79.7
180	77.96	107.60	14.67	21.13	28.76	37.6	47.5	58.7	71.0	84.5
200	86.62	113.42	15.47	22.27	30.31	39.6	50.1	61.9	74.9	89.1
250	108.27	126.81	17.29	24.90	33.89	44.3	56.0	69.2	83.7	99.6
300	129.93	138.91	18.94	27.27	37.12	48.5	61.4	75.8	91.7	109.1
350	151.58	150.04	20.46	29.46	40.10	52.4	66.3	81.8	99.0	117.8
400	173.24	160.40	21.87	31.49	42.87	56.0	70.9	87.5	105.9	126.0
450	194.89	170.13	23.20	33.40	45.47	59.4	75.2	92.8	112.3	133.6
500	216.54	179.33	24.45	35.21	47.93	62.6	79.2	97.8	118.4	140.8

Copyright 2004, Industrial Press, Inc., New York, NY

Theoretical Velocity of Water Due to Head in Feet

Head in Feet	Theoretical Velocity		Head in Feet	Theoretical Velocity		Head in Feet	Theoretical Velocity	
	ft/s	ft/min		ft/s	ft/min		ft/s	ft/min
1	8.01	481	48	55.56	3334	95	78.16	4690
2	11.34	681	49	56.13	3368	96	78.57	4715
3	13.89	833	50	56.70	3403	97	78.98	4739
4	16.04	962	51	57.27	3436	98	79.39	4764
5	17.93	1076	52	57.83	3470	99	79.79	4788
6	19.64	1179	53	58.38	3503	100	80.19	4812
7	21.21	1273	54	58.93	3536	105	82.18	4931
8	22.68	1361	55	59.47	3569	110	84.11	5047
9	24.05	1444	56	60.01	3601	115	86.00	5160
10	25.36	1522	57	60.54	3633	120	87.85	5271
11	26.59	1596	58	61.07	3665	125	89.66	5380
12	27.78	1667	59	61.60	3696	130	91.44	5487
13	28.91	1735	60	62.12	3727	135	93.18	5591
14	30.00	1800	61	62.63	3758	140	94.89	5694
15	31.06	1864	62	63.14	3789	145	96.57	5794
16	32.07	1925	63	63.65	3819	150	98.22	5893
17	33.06	1984	64	64.15	3850	155	99.84	5991
18	34.02	2042	65	64.65	3880	160	101.44	6087
19	34.95	2097	66	65.15	3909	165	103.01	6181
20	35.86	2152	67	65.64	3939	170	104.56	6274
21	36.75	2205	68	66.13	3968	175	106.09	6366
22	37.61	2257	69	66.61	3997	180	107.59	6456
23	38.46	2308	70	67.09	4026	185	109.08	6545
24	39.28	2357	71	67.57	4055	190	110.54	6633
25	40.09	2406	72	68.05	4083	195	111.99	6720
26	40.89	2454	73	68.52	4111	200	113.42	6805
27	41.67	2500	74	68.99	4139	205	114.82	6890
28	42.43	2546	75	69.45	4167	210	116.22	6973
29	43.18	2591	76	69.91	4195	215	117.59	7056
30	43.92	2636	77	70.37	4222	220	118.95	7137
31	44.65	2679	78	70.83	4250	225	120.30	7218
32	45.36	2722	79	71.28	4277	230	121.62	7298
33	46.07	2764	80	71.73	4304	235	122.94	7377
34	46.76	2806	81	72.17	4331	240	124.24	7455
35	47.44	2847	82	72.62	4357	245	125.53	7532
36	48.11	2887	83	73.06	4384	250	126.80	7608
37	48.78	2927	84	73.50	4410	255	128.06	7684
38	49.43	2966	85	73.94	4436	260	129.31	7759
39	50.08	3005	86	74.37	4462	270	131.78	7907
40	50.72	3043	87	74.80	4488	280	134.20	8052
41	51.35	3081	88	75.23	4514	290	136.57	8195
42	51.97	3119	89	75.66	4540	300	138.91	8335
43	52.59	3155	90	76.08	4565	310	141.20	8472
44	53.19	3192	91	76.50	4590	320	143.46	8608
45	53.79	3228	92	76.92	4615	330	145.69	8741
46	54.39	3264	93	77.34	4641	340	147.88	8873
47	54.98	3299	94	77.75	4665	350	150.04	9002

Copyright 2004, Industrial Press, Inc., New York, NY

Gallons of Water per Foot of Pipe

Nominal Pipe Size (in.)	Iron or Steel		Copper		
	Sched. 40	Sched. 80	Type K	Type L	Type M
1/8	0.0030	0.0019	0.0014	0.0016	0.0016
1/4	0.0054	0.0037	0.0039	0.0040	0.0043
3/8	0.0099	0.0073	0.0066	0.0075	0.0083
1/2	0.0158	0.0122	0.0113	0.0121	0.0132
5/8	…	…	0.0173	0.0181	0.0194
3/4	0.0277	0.0225	0.0226	0.0251	0.0268
1	0.0449	0.0374	0.0404	0.0429	0.0454

Multiply the length of pipe in feet by the factor from the table to find the volume contained in gallons.

Friction Loss in Fittings—Equivalent Length of Pipe in Feet

Nominal Pipe Size (in.)	Elbows						Standard Tee	
	90° Std.	45° Std.	90° Long Radius	90° Street	45° Street	Square Corner	Flow thru Run	Flow thru Branch
1/4	0.9	0.5	0.6	1.5	0.8	1.7	0.6	1.8
1/2	1.6	0.8	1.0	2.6	1.3	3.0	1.0	4.0
3/4	2.1	1.1	1.4	3.4	1.8	3.9	1.4	5.1
1	2.6	1.4	1.7	4.4	2.3	5.0	1.7	6.0
1 1/4	3.5	1.8	2.3	5.8	3.0	6.5	2.3	6.9
1 1/2	4.0	2.1	2.7	6.7	3.5	7.6	2.7	8.1
2	5.5	2.8	4.3	8.6	4.5	9.8	4.3	12.0
2 1/2	6.2	3.3	5.1	10.3	5.4	11.7	5.1	14.3
3	7.7	4.1	6.3	12.8	6.6	14.6	6.3	16.3
4	10.1	5.4	8.3	16.8	8.7	19.1	8.3	22.1
6	15.2	8.1	12.5	25.3	13.1	28.8	12.5	32.2
8	20.0	10.6	16.5	33.3	17.3	37.9	16.5	39.9
10	25.1	13.4	20.7	41.8	21.7	47.6	20.7	50.1
12	29.8	15.9	24.7	49.7	25.9	56.7	24.7	59.7

Pipe Expansion Due to Temperature Changes.— The expansion for any length of pipe caused by a given temperature change can be determined from the following table. Find the expansion factor corresponding to the expected difference in the minimum and maximum pipe temperatures and divide by 100 to obtain the increase in length per foot of pipe. Multiply the increase per foot result by the length of the pipe run to get the total change in pipe length.

Linear Expansion and Contraction Factors per 100 Feet of Pipe

Temperature Change, °F	Pipe Material				
	Steel	Copper	PVC	FRP	PP & PVDF
0	0	0	0	0	0
20	0.15	0.25	0.62	0.26	2.00
40	0.30	0.45	1.30	0.52	4.00
60	0.46	0.65	2.20	0.78	6.00
80	0.61	0.87	2.80	1.05	8.00
100	0.77	1.10	3.50	1.31	10.00
120	0.92	1.35	4.25	1.57	12.00
140	1.08	1.57	4.80	1.83	14.00
160	1.24	1.77	5.50	2.09	16.00
180	1.40	2.00	6.30	2.35	18.00
200	1.57	2.25	7.12	2.62	20.00

Multiply the length of pipe by the table factor and divide by 100 for the increase or decrease in length.

Copyright 2004, Industrial Press, Inc., New York, NY

Properties, Compression, and Flow of Air

Properties of Air.— Air is a mechanical mixture composed of 78 per cent of nitrogen, 21 per cent of oxygen, and 1 per cent of argon, by volume. The density of dry air at 32 degrees F and atmospheric pressure (29.92 inches of mercury or 14.70 pounds per square inch) is 0.08073 pound per cubic foot. The density of air at any other temperature or pressure is

$$\rho = \frac{1.325 \times B}{T}$$

in which ρ = density in pounds per cubic foot; B = height of barometric pressure in inches of mercury; T = absolute temperature in degrees Rankine. (When using pounds as a unit, here and elsewhere, care must be exercised to differentiate between pounds mass and pounds force. See *Acceleration of Gravity g Used in Mechanics Formulas* on page 142 and *The Use of the Metric SI System in Mechanics Calculations* on page 142.)

Volumes and Weights of Air at Different Temperatures, at Atmospheric Pressure

Temperature, °F	Volume of 1 lb of Air in Cubic Feet	Density, Pounds per Cubic Foot	Temperature, °F	Volume of 1 lb of Air in Cubic Feet	Density, Pounds per Cubic Foot	Temperature, °F	Volume of 1 lb of Air in Cubic Feet	Density, Pounds per Cubic Foot
0	11.57	0.0864	172	15.92	0.0628	800	31.75	0.0315
12	11.88	0.0842	182	16.18	0.0618	900	34.25	0.0292
22	12.14	0.0824	192	16.42	0.0609	1000	37.31	0.0268
32	12.39	0.0807	202	16.67	0.0600	1100	39.37	0.0254
42	12.64	0.0791	212	16.92	0.0591	1200	41.84	0.0239
52	12.89	0.0776	230	17.39	0.0575	1300	44.44	0.0225
62	13.14	0.0761	250	17.89	0.0559	1400	46.95	0.0213
72	13.39	0.0747	275	18.52	0.0540	1500	49.51	0.0202
82	13.64	0.0733	300	19.16	0.0522	1600	52.08	0.0192
92	13.89	0.0720	325	19.76	0.0506	1700	54.64	0.0183
102	14.14	0.0707	350	20.41	0.0490	1800	57.14	0.0175
112	14.41	0.0694	375	20.96	0.0477	2000	62.11	0.0161
122	14.66	0.0682	400	21.69	0.0461	2200	67.11	0.0149
132	14.90	0.0671	450	22.94	0.0436	2400	72.46	0.0138
142	15.17	0.0659	500	24.21	0.0413	2600	76.92	0.0130
152	15.41	0.0649	600	26.60	0.0376	2800	82.64	0.0121
162	15.67	0.0638	700	29.59	0.0338	3000	87.72	0.0114

The absolute zero from which all temperatures must be counted when dealing with the weight and volume of gases is assumed to be –459.7 degrees F. Hence, to obtain the absolute temperature T used in preceding formula, add the value 459.7 to the temperature observed on a regular Fahrenheit thermometer.

In obtaining the value of B, 1 inch of mercury at 32 degrees F may be taken as equal to a pressure of 0.491 pound per square inch.

Example 1: What would be the weight of a cubic foot of air at atmospheric pressure (29.92 inches of mercury) at 100 degrees F? The weight, W, is given by $W = \rho V$.

$$W = \rho V = \frac{1.325 \times 29.92}{100 + 459.7} \times 1 = 0.0708 \text{ pound}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Density of Air at Different Pressures and Temperatures

Temp. of Air, °F	Gage Pressure, Pounds														
	0	5	10	20	30	40	50	60	80	100	120	150	200	250	300
	Density in Pounds per Cubic Foot														
-20	0.0900	0.1205	0.1515	0.2125	0.274	0.336	0.397	0.458	0.580	0.702	0.825	1.010	1.318	1.625	1.930
-10	0.0882	0.1184	0.1485	0.2090	0.268	0.328	0.388	0.448	0.567	0.687	0.807	0.989	1.288	1.588	1.890
0	0.0864	0.1160	0.1455	0.2040	0.263	0.321	0.380	0.438	0.555	0.672	0.790	0.968	1.260	1.553	1.850
10	0.0846	0.1136	0.1425	0.1995	0.257	0.314	0.372	0.429	0.543	0.658	0.774	0.947	1.233	1.520	1.810
20	0.0828	0.1112	0.1395	0.1955	0.252	0.307	0.364	0.420	0.533	0.645	0.757	0.927	1.208	1.489	1.770
30	0.0811	0.1088	0.1366	0.1916	0.246	0.301	0.357	0.412	0.522	0.632	0.742	0.908	1.184	1.460	1.735
40	0.0795	0.1067	0.1338	0.1876	0.241	0.295	0.350	0.404	0.511	0.619	0.727	0.890	1.161	1.431	1.701
50	0.0780	0.1045	0.1310	0.1839	0.237	0.290	0.343	0.396	0.501	0.607	0.713	0.873	1.139	1.403	1.668
60	0.0764	0.1025	0.1283	0.1803	0.232	0.284	0.336	0.388	0.493	0.596	0.700	0.856	1.116	1.376	1.636
80	0.0736	0.0988	0.1239	0.1738	0.224	0.274	0.324	0.374	0.473	0.572	0.673	0.824	1.074	1.325	1.573
100	0.0710	0.0954	0.1197	0.1676	0.215	0.264	0.312	0.360	0.455	0.551	0.648	0.794	1.035	1.276	1.517
120	0.0680	0.0921	0.1155	0.1618	0.208	0.255	0.302	0.348	0.440	0.533	0.626	0.767	1.001	1.234	1.465
140	0.0663	0.0889	0.1115	0.1565	0.201	0.246	0.291	0.336	0.426	0.516	0.606	0.742	0.968	1.194	1.416
150	0.0652	0.0874	0.1096	0.1541	0.198	0.242	0.286	0.331	0.419	0.508	0.596	0.730	0.953	1.175	1.392
175	0.0626	0.0840	0.1054	0.1482	0.191	0.233	0.275	0.318	0.403	0.488	0.573	0.701	0.914	1.128	1.337
200	0.0603	0.0809	0.1014	0.1427	0.184	0.225	0.265	0.305	0.388	0.470	0.552	0.674	0.879	1.084	1.287
225	0.0581	0.0779	0.0976	0.1373	0.177	0.216	0.255	0.295	0.374	0.452	0.531	0.649	0.846	1.043	1.240
250	0.0560	0.0751	0.0941	0.1323	0.170	0.208	0.247	0.284	0.360	0.436	0.513	0.627	0.817	1.007	1.197
275	0.0541	0.0726	0.0910	0.1278	0.164	0.201	0.238	0.274	0.348	0.421	0.494	0.605	0.789	0.972	1.155
300	0.0523	0.0707	0.0881	0.1237	0.159	0.194	0.230	0.265	0.336	0.407	0.478	0.585	0.762	0.940	1.118
350	0.0491	0.0658	0.0825	0.1160	0.149	0.183	0.216	0.249	0.316	0.382	0.449	0.549	0.715	0.883	1.048
400	0.0463	0.0621	0.0779	0.1090	0.140	0.172	0.203	0.235	0.297	0.360	0.423	0.517	0.674	0.831	0.987
450	0.0437	0.0586	0.0735	0.1033	0.133	0.163	0.192	0.222	0.281	0.340	0.399	0.488	0.637	0.786	0.934
500	0.0414	0.0555	0.0696	0.978	0.126	0.154	0.182	0.210	0.266	0.322	0.379	0.463	0.604	0.746	0.885
550	0.0394	0.0528	0.0661	0.930	0.120	0.146	0.173	0.200	0.253	0.306	0.359	0.440	0.573	0.749	0.841
600	0.0376	0.0504	0.0631	0.885	0.114	0.139	0.165	0.190	0.241	0.292	0.343	0.419	0.547	0.675	0.801

Copyright 2004, Industrial Press, Inc., New York, NY

Relation Between Pressure, Temperature, and Volume of Air.— This relationship is expressed by the following formulas:

$$PV = 53.3mT \qquad \text{For fps units}$$

$$PV = 1545.3nT \qquad \text{For fps units}$$

$$PV = 8314nT \qquad \text{For SI units}$$

in which P = absolute pressure in pounds per square foot or Pa (N/m^2); V = volume in cubic feet or cubic meter; T = absolute temperature in degrees R or degrees K; m = the mass of substance; and n = number of pound moles or kg moles. A mole is the mass of substance, in appropriate units, divided by its molecular weight. The first equation above is for air only; the second and third are general forms that apply to any gas that behaves the ideal gas law.

Example 2: What is the volume of one pound of air at a pressure of 24.7 pounds per square inch and at a temperature of 210 degrees F?

$$PV = 53.3mT \qquad V = \frac{53.3mT}{P} \qquad V = \frac{53.3 \times 1 \times (210 + 459.6)}{24.7 \times 144}$$

$$= 10.04 \quad \text{cubic ft}$$

Relation Between Barometric Pressure, and Pressures in Pounds per Square Inch and Square Foot

Barometer, Inches	Pressure in Psi[a]	Pressure in Psf[a]	Barometer, Inches	Pressure in Psi[a]	Pressure in Psf[a]	Barometer, Inches	Pressure in Psi[a]	Pressure in Psf[a]
28.00	13.75	1980	29.25	14.36	2068	30.50	14.98	2156
28.25	13.87	1997	29.50	14.48	2086	30.75	15.10	2174
28.50	13.99	2015	29.75	14.61	2103	31.00	15.22	2192
28.75	14.12	2033	30.00	14.73	2121	31.25	15.34	2210
29.00	14.24	2050	30.25	14.85	2139	…	…	…

[a] Psi is pounds per square inch; Psf is pounds per square foot

Expansion and Compression of Air.— The formula for the relationship between pressure, temperature, and volume of air just given indicates that when the pressure remains constant the volume is directly proportional to the absolute temperature. If the temperature remains constant, the volume is inversely proportional to the absolute pressure. Theoretically, air (as well as other gases) can be expanded or compressed according to different laws.

Adiabatic Expansion or Compression takes place when the air is expanded or compressed without transmission of heat to or from it, as, for example, if the air could be expanded or compressed in a cylinder of an absolutely nonconducting material.

Let: P_1 = initial absolute pressure in pounds per square foot
V_1 = initial volume in cubic feet
T_1 = initial absolute temperature in degrees R
P_2 = absolute pressure in pounds per square foot, after compression
V_2 = volume in cubic feet, after compression
T_2 = absolute temperature in degrees R, after compression

Then:

$$\frac{V_2}{V_1} = \left(\frac{P_1}{P_2}\right)^{0.71} \qquad \frac{P_2}{P_1} = \left(\frac{V_1}{V_2}\right)^{1.41} \qquad \frac{T_2}{T_1} = \left(\frac{V_1}{V_2}\right)^{0.41}$$

$$\frac{V_2}{V_1} = \left(\frac{T_1}{T_2}\right)^{2.46} \qquad \frac{P_2}{P_1} = \left(\frac{T_2}{T_1}\right)^{3.46} \qquad \frac{T_2}{T_1} = \left(\frac{P_2}{P_1}\right)^{0.29}$$

Copyright 2004, Industrial Press, Inc., New York, NY

These formulas are also applicable if all pressures are in pounds per square inch; if all volumes are in cubic inches; or if any other consistent set of units is used for pressure or volume.

Example 3: A volume of 165 cubic feet of air, at a pressure of 15 pounds per square inch, is compressed adiabatically to a pressure of 80 pounds per square inch. What will be the volume at this pressure?

$$V_2 = V_1\left(\frac{P_1}{P_2}\right)^{0.71} = 165\left(\frac{15}{80}\right)^{0.71} = 50 \text{ cubic feet, approx.}$$

Isothermal Expansion or Compression takes place when a gas is expanded or compressed with an addition or transmission of sufficient heat to maintain a constant temperature.

Let: P_1 = initial absolute pressure in pounds per square foot
V_1 = initial volume in cubic feet
P_2 = absolute pressure in pounds per square foot, after compression
V_2 = volume in cubic feet, after compression
$R = 53.3$
T = temperature in degrees Rankine maintained during isothermal expansion or contraction

Then:

$$P_1 \times V_1 = P_2 \times V_2 = RT$$

Example 4: The same volume of air as in Example 3 is compressed isothermally from 15 to 80 pounds per square inch. What will be the volume after compression?

$$V_2 = \frac{P_1 \times V_1}{P_2} = \frac{15 \times 165}{80} = 31 \text{ cubic feet}$$

Foot-pounds of Work Required in Compression of Air
Initial Pressure = 1 atmosphere = 14.7 pounds per square inch

Gage Pressure in Pounds per Square Inch	Isothermal Compression	Adiabatic Compression	Actual Compression	Gage Pressure in Pounds per Square Inch	Isothermal Compression	Adiabatic Compression	Actual Compression
	Foot-pounds Required per Cubic Foot of Air at Initial Pressure				Foot-pounds Required per Cubic Foot of Air at Initial Pressure		
5	619.6	649.5	637.5	55	3393.7	4188.9	3870.8
10	1098.2	1192.0	1154.6	60	3440.4	4422.8	4029.8
15	1488.3	1661.2	1592.0	65	3577.6	4645.4	4218.2
20	1817.7	2074.0	1971.4	70	3706.3	4859.6	4398.1
25	2102.6	2451.6	2312.0	75	3828.0	5063.9	4569.5
30	2353.6	2794.0	2617.8	80	3942.9	5259.7	4732.9
35	2578.0	3111.0	2897.8	85	4051.5	5450.0	4890.1
40	2780.8	3405.5	3155.6	90	4155.7	5633.1	5042.1
45	2966.0	3681.7	3395.4	95	4254.3	5819.3	5187.3
50	3136.2	3942.3	3619.8	100	4348.1	5981.2	5327.9

Work Required in Compression of Air.— The total work required for compression and expulsion of air, adiabatically compressed, is:

$$\text{Total work in foot-pounds} = 3.46 P_1 V_1 \left[\left(\frac{P_2}{P_1}\right)^{0.29} - 1\right]$$

where P_1 = initial absolute pressure in pounds per square foot; P_2 = absolute pressure in pounds per square foot, after compression; and, V_1 = initial volume in cubic feet.

Copyright 2004, Industrial Press, Inc., New York, NY

The total work required for isothermal compression is:

$$\text{Total work in foot-pounds} = P_1 V_1 \log_e \frac{V_1}{V_2}$$

in which P_1, P_2, and V_1 denote the same quantities as in the previous equation, and V_2 = volume of air in cubic feet, after compression.

The work required to compress air isothermally, that is, when the heat of compression is removed as rapidly as produced, is considerably less than the work required for compressing air adiabatically, or when all the heat is retained. In practice, neither of these two theoretical extremes is obtainable, but the power required for air compression is about the median between the powers that would be required for each. The accompanying table gives the average number of foot-pounds of work required to compress air.

Horsepower Required to Compress Air.— In the accompanying tables is given the horsepower required to compress one cubic foot of free air per minute (isothermally and adiabatically) from atmospheric pressure (14.7 pounds per square inch) to various gage pressures, for one-, two-, and three-stage compression. The formula for calculating the horsepower required to compress, adiabatically, a given volume of free air to a given pressure is:

$$\text{HP} = \frac{144 N P V n}{33{,}000(n-1)} \left[\left(\frac{P_2}{P} \right)^{\frac{n-1}{Nn}} - 1 \right]$$

where N = number of stages in which compression is accomplished
P = atmospheric pressure in pounds per square inch
P_2 = absolute terminal pressure in pounds per square inch
V = volume of air, in cubic feet, compressed per minute, at atmospheric pressure
n = exponent of the compression curve = 1.41 for adiabatic compression

For different methods of compression and for one cubic foot of air per minute, this formula may be simplified as follows:

For one-stage compression: $\text{HP} = 0.015P(R^{0.29} - 1)$

For two-stage compression: $\text{HP} = 0.030\,P(R^{0.145} - 1)$

For three-stage compression: $\text{HP} = 0.045\,P(R^{0.0975} - 1)$

For four-stage compression: $\text{HP} = 0.060\,P(R^{0.0725} - 1)$

In these latter formulas $R = \frac{P_2}{P}$ = number of atmospheres to be compressed

The formula for calculating the horsepower required to compress isothermally a given volume of free air to a given pressure is:

$$\text{HP} = \frac{144 P V}{33000} \left(\log_e \frac{P_2}{P} \right)$$

Natural logarithms are obtained by multiplying common logarithms by 2.30259 or by using a handheld calculator.

Continuity Equation.— The net rate of mass inflow to the control volume is equal to the rate of increase of mass within the control volume.

For steady flow, $\rho_1 A_1 V_1 = \rho_2 A_2 V_2 = M$ where ρ = density, A = area, V = velocity, and M = mass flow rate.

If the flow is steady and incompressible, then $A_1 V_1 = A_2 V_2 = Q$ where Q is flow.

Copyright 2004, Industrial Press, Inc., New York, NY

Horsepower Required to Compress Air, Single-Stage Compression

Horsepower required to compress one cubic foot of free air per minute (isothermally and adiabatically) from atmospheric pressure (14.7 pounds per square inch) to various gage pressures.
Single-Stage Compression, initial temperature of air, 60°F, jacket cooling not considered.

Gage Pressure, Pounds	Absolute Pressure, Pounds	Number of Atmospheres	Isothermal Compression		Adiabatic Compression			
			Mean Effective Pressure[a]	Horsepower	Mean Effective Pressure,[a] Theoretical	Mean Eff. Pressure plus 15% Friction	Horsepower, Theoretical	Horsepower plus 15% Friction
5	19.7	1.34	4.13	0.018	4.46	5.12	0.019	0.022
10	24.7	1.68	7.57	0.033	8.21	9.44	0.036	0.041
15	29.7	2.02	11.02	0.048	11.46	13.17	0.050	0.057
20	34.7	2.36	12.62	0.055	14.30	16.44	0.062	0.071
25	39.7	2.70	14.68	0.064	16.94	19.47	0.074	0.085
30	44.7	3.04	16.30	0.071	19.32	22.21	0.084	0.096
35	49.7	3.38	17.90	0.078	21.50	24.72	0.094	0.108
40	54.7	3.72	19.28	0.084	25.53	27.05	0.103	0.118
45	59.7	4.06	20.65	0.090	25.40	29.21	0.111	0.127
50	64.7	4.40	21.80	0.095	27.23	31.31	0.119	0.136
55	69.7	4.74	22.95	0.100	28.90	33.23	0.126	0.145
60	74.7	5.08	23.90	0.104	30.53	35.10	0.133	0.153
65	79.7	5.42	24.80	0.108	32.10	36.91	0.140	0.161
70	84.7	5.76	25.70	0.112	33.57	38.59	0.146	0.168
75	89.7	6.10	26.62	0.116	35.00	40.25	0.153	0.175
80	94.7	6.44	27.52	0.120	36.36	41.80	0.159	0.182
85	99.7	6.78	28.21	0.123	37.63	43.27	0.164	0.189
90	104.7	7.12	28.93	0.126	38.89	44.71	0.169	0.195
95	109.7	7.46	29.60	0.129	40.11	46.12	0.175	0.201
100	114.7	7.80	30.30	0.132	41.28	47.46	0.180	0.207
110	124.7	8.48	31.42	0.137	43.56	50.09	0.190	0.218
120	134.7	9.16	32.60	0.142	45.69	52.53	0.199	0.229
130	144.7	9.84	33.75	0.147	47.72	54.87	0.208	0.239
140	154.7	10.52	34.67	0.151	49.64	57.08	0.216	0.249
150	164.7	11.20	35.59	0.155	51.47	59.18	0.224	0.258
160	174.7	11.88	36.30	0.158	53.70	61.80	0.234	0.269
170	184.7	12.56	37.20	0.162	55.60	64.00	0.242	0.278
180	194.7	13.24	38.10	0.166	57.20	65.80	0.249	0.286
190	204.7	13.92	38.80	0.169	58.80	67.70	0.256	0.294
200	214.7	14.60	39.50	0.172	60.40	69.50	0.263	0.303

[a] Mean Effective Pressure (MEP) is defined as that single pressure rise, above atmospheric, which would require the same horsepower as the actual varying pressures during compression.

Copyright 2004, Industrial Press, Inc., New York, NY

Horsepower Required to Compress Air, Two-Stage Compression

Horsepower required to compress one cubic foot of free air per minute (isothermally and adiabatically) from atmospheric pressure (14.7 pounds per square inch) to various gage pressures.
Two-Stage Compression, initial temperature of air, 60°F, jacket cooling not considered.

Gage Pressure, Pounds	Absolute Pressure, Pounds	Number of Atmospheres	Correct Ratio of Cylinder Volumes	Intercooler Gage Pressure	Isothermal Compression		Adiabatic Compression				Percentage of Saving over One-stage Compression
					Mean Effective Pressure[a]	Horsepower	Mean Eff. Pressure,[a] Theoretical	Mean Eff. Pressure plus 15 per cent Friction	Horsepower, Theoretical	HP plus 15 per cent Friction	
50	64.7	4.40	2.10	16.2	21.80	0.095	24.30	27.90	0.106	0.123	10.9
60	74.7	5.08	2.25	18.4	23.90	0.104	27.20	31.30	0.118	0.136	11.3
70	84.7	5.76	2.40	20.6	25.70	0.112	29.31	33.71	0.128	0.147	12.3
80	94.7	6.44	2.54	22.7	27.52	0.120	31.44	36.15	0.137	0.158	13.8
90	104.7	7.12	2.67	24.5	28.93	0.126	33.37	38.36	0.145	0.167	14.2
100	114.7	7.80	2.79	26.3	30.30	0.132	35.20	40.48	0.153	0.176	15.0
110	124.7	8.48	2.91	28.1	31.42	0.137	36.82	42.34	0.161	0.185	15.2
120	134.7	9.16	3.03	29.8	32.60	0.142	38.44	44.20	0.168	0.193	15.6
130	144.7	9.84	3.14	31.5	33.75	0.147	39.86	45.83	0.174	0.200	16.3
140	154.7	10.52	3.24	32.9	34.67	0.151	41.28	47.47	0.180	0.207	16.7
150	164.7	11.20	3.35	34.5	35.59	0.155	42.60	48.99	0.186	0.214	16.9
160	174.7	11.88	3.45	36.1	36.30	0.158	43.82	50.39	0.191	0.219	18.4
170	184.7	12.56	3.54	37.3	37.20	0.162	44.93	51.66	0.196	0.225	19.0
180	194.7	13.24	3.64	38.8	38.10	0.166	46.05	52.95	0.201	0.231	19.3
190	204.7	13.92	3.73	40.1	38.80	0.169	47.16	54.22	0.206	0.236	19.5
200	214.7	14.60	3.82	41.4	39.50	0.172	48.18	55.39	0.210	0.241	20.1
210	224.7	15.28	3.91	42.8	40.10	0.174	49.35	56.70	0.216	0.247	…
220	234.7	15.96	3.99	44.0	40.70	0.177	50.30	57.70	0.220	0.252	…
230	244.7	16.64	4.08	45.3	41.30	0.180	51.30	59.10	0.224	0.257	…
240	254.7	17.32	4.17	46.6	41.90	0.183	52.25	60.10	0.228	0.262	…
250	264.7	18.00	4.24	47.6	42.70	0.186	52.84	60.76	0.230	0.264	…
260	274.7	18.68	4.32	48.8	43.00	0.188	53.85	62.05	0.235	0.270	…
270	284.7	19.36	4.40	50.0	43.50	0.190	54.60	62.90	0.238	0.274	…
280	294.7	20.04	4.48	51.1	44.00	0.192	55.50	63.85	0.242	0.278	…
290	304.7	20.72	4.55	52.2	44.50	0.194	56.20	64.75	0.246	0.282	…
300	314.7	21.40	4.63	53.4	45.80	0.197	56.70	65.20	0.247	0.283	…
350	364.7	24.80	4.98	58.5	47.30	0.206	60.15	69.16	0.262	0.301	…
400	414.7	28.20	5.31	63.3	49.20	0.214	63.19	72.65	0.276	0.317	…
450	464.7	31.60	5.61	67.8	51.20	0.223	65.93	75.81	0.287	0.329	…
500	514.7	35.01	5.91	72.1	52.70	0.229	68.46	78.72	0.298	0.342	…

[a] Mean Effective Pressure (MEP) is defined as that single pressure rise, above atmospheric, which would require the same horsepower as the actual varying pressures during compression.

Copyright 2004, Industrial Press, Inc., New York, NY

Horsepower Required to Compress Air, Three-stage Compression

Horsepower required for compressing one cubic foot of free air per minute (isothermally and adiabatically) from atmospheric pressure (14.7 pounds per square inch) to various gage pressures.

Three-stage Compression, initial temperature of air, 60°F, jacket-cooling not considered.

Gage Pressure, Pounds	Absolute Pressure, Pounds	Number of Atmospheres	Correct Ratio of Cylinder Volumes	Intercooler Gage Pressure, First and Second Stages	Isothermal Compression		Adiabatic Compression				Saving over Two-stage Compression
					Mean Effective Pressure[a]	Horsepower	Mean Eff. Pressure,[a] Theoretical	Mean Eff. Pressure plus 15 per cent Friction	Horsepower Theoretical	HP plus 15 per cent Friction	Percentage of
100	114.7	7.8	1.98	14.4–42.9	30.30	0.132	33.30	38.30	0.145	0.167	5.23
150	164.7	11.2	2.24	18.2–59.0	35.59	0.155	40.30	46.50	0.175	0.202	5.92
200	214.7	14.6	2.44	21.2–73.0	39.50	0.172	45.20	52.00	0.196	0.226	6.67
250	264.7	18.0	2.62	23.8–86.1	42.70	0.186	49.20	56.60	0.214	0.246	6.96
300	314.7	21.4	2.78	26.1–98.7	45.30	0.197	52.70	60.70	0.229	0.264	7.28
350	364.7	24.8	2.92	28.2–110.5	47.30	0.206	55.45	63.80	0.242	0.277	7.64
400	414.7	28.2	3.04	30.0–121.0	49.20	0.214	58.25	66.90	0.253	0.292	8.33
450	464.7	31.6	3.16	31.8–132.3	51.20	0.223	60.40	69.40	0.263	0.302	8.36
500	514.7	35.0	3.27	33.4–142.4	52.70	0.229	62.30	71.70	0.273	0.314	8.38
550	564.7	38.4	3.38	35.0–153.1	53.75	0.234	65.00	74.75	0.283	0.326	8.80
600	614.7	41.8	3.47	36.3–162.3	54.85	0.239	66.85	76.90	0.291	0.334	8.86
650	664.7	45.2	3.56	37.6–171.5	56.00	0.244	67.90	78.15	0.296	0.340	9.02
700	714.7	48.6	3.65	38.9–180.8	57.15	0.249	69.40	79.85	0.303	0.348	9.18
750	764.7	52.0	3.73	40.1–189.8	58.10	0.253	70.75	81.40	0.309	0.355	…
800	814.7	55.4	3.82	41.4–199.5	59.00	0.257	72.45	83.25	0.315	0.362	…
850	864.7	58.8	3.89	42.5–207.8	60.20	0.262	73.75	84.90	0.321	0.369	…
900	914.7	62.2	3.95	43.4–214.6	60.80	0.265	74.80	86.00	0.326	0.375	…
950	964.7	65.6	4.03	44.6–224.5	61.72	0.269	76.10	87.50	0.331	0.381	…
1000	1014.7	69.0	4.11	45.7–233.3	62.40	0.272	77.20	88.80	0.336	0.383	…
1050	1064.7	72.4	4.15	46.3–238.3	63.10	0.275	78.10	90.10	0.340	0.391	…
1100	1114.7	75.8	4.23	47.5–248.3	63.80	0.278	79.10	91.10	0.344	0.396	…
1150	1164.7	79.2	4.30	48.5–256.8	64.40	0.281	80.15	92.20	0.349	0.401	…
1200	1214.7	82.6	4.33	49.0–261.3	65.00	0.283	81.00	93.15	0.353	0.405	…
1250	1264.7	86.0	4.42	50.3–272.3	65.60	0.286	82.00	94.30	0.357	0.411	…
1300	1314.7	89.4	4.48	51.3–280.8	66.30	0.289	82.90	95.30	0.362	0.416	…
1350	1364.7	92.8	4.53	52.0–287.3	66.70	0.291	84.00	96.60	0.366	0.421	…
1400	1414.7	96.2	4.58	52.6–293.5	67.00	0.292	84.60	97.30	0.368	0.423	…
1450	1464.7	99.6	4.64	53.5–301.5	67.70	0.295	85.30	98.20	0.371	0.426	…
1500	1514.7	103.0	4.69	54.3–309.3	68.30	0.298	85.80	98.80	0.374	0.430	…
1550	1564.7	106.4	4.74	55.0–317.3	68.80	0.300	86.80	99.85	0.378	0.434	…
1600	1614.7	109.8	4.79	55.8–323.3	69.10	0.302	87.60	100.80	0.382	0.438	…

[a] Mean Effective Pressure (MEP) is defined as that single pressure rise, above atmospheric, which would require the same horsepower as the actual varying pressures during compression.

Copyright 2004, Industrial Press, Inc., New York, NY

Flow of Air in Pipes.— The following formulas are used:

$$v = \sqrt{\frac{25,000\ dp}{L}} \qquad p = \frac{Lv^2}{25,000\ d}$$

where v = velocity of air in feet per second

p = loss of pressure due to flow through the pipes in ounces per square inch

d = inside diameter of pipe in inches

L = length of pipe in feet

The quantity of air discharged in cubic feet per second is the product of the velocity as obtained from the preceding formula and the area of the pipe in square feet. The horsepower required to drive air through a pipe equals the volume of air in cubic feet per second multiplied by the pressure in pounds per square foot, and this product divided by 550.

Volume of Air Transmitted Through Pipes, in Cubic Feet per Minute

Velocity of Air in Feet per Second	Actual Inside Diameter of Pipe, Inches									
	1	2	3	4	6	8	10	12	16	24
1	0.33	1.31	2.95	5.2	11.8	20.9	32.7	47.1	83.8	188
2	0.65	2.62	5.89	10.5	23.6	41.9	65.4	94.2	167.5	377
3	0.98	3.93	8.84	15.7	35.3	62.8	98.2	141.4	251.3	565
4	1.31	5.24	11.78	20.9	47.1	83.8	131.0	188.0	335.0	754
5	1.64	6.55	14.7	26.2	59.0	104.0	163.0	235.0	419.0	942
6	1.96	7.85	17.7	31.4	70.7	125.0	196.0	283.0	502.0	1131
7	2.29	9.16	20.6	36.6	82.4	146.0	229.0	330.0	586.0	1319
8	2.62	10.50	23.5	41.9	94.0	167.0	262.0	377.0	670.0	1508
9	2.95	11.78	26.5	47.0	106.0	188.0	294.0	424.0	754.0	1696
10	3.27	13.1	29.4	52.0	118.0	209.0	327.0	471.0	838.0	1885
12	3.93	15.7	35.3	63.0	141.0	251.0	393.0	565.0	1005.0	2262
15	4.91	19.6	44.2	78.0	177.0	314.0	491.0	707.0	1256.0	2827
18	5.89	23.5	53.0	94.0	212.0	377.0	589.0	848.0	1508.0	3393
20	6.55	26.2	59.0	105.0	235.0	419.0	654.0	942.0	1675.0	3770
24	7.86	31.4	71.0	125.0	283.0	502.0	785.0	1131.0	2010.0	4524
25	8.18	32.7	73.0	131.0	294.0	523.0	818.0	1178.0	2094.0	4712
28	9.16	36.6	82.0	146.0	330.0	586.0	916.0	1319.0	2346.0	5278
30	9.80	39.3	88.0	157.0	353.0	628.0	982.0	1414.0	2513.0	5655

Flow of Compressed Air in Pipes.— When there is a comparatively small difference of pressure at the two ends of the pipe, the volume of flow in cubic feet per minute is found by the formula:

$$V = 58\sqrt{\frac{pd^5}{WL}}$$

where V = volume of air in cubic feet per minute

p = difference in pressure at the two ends of the pipe in pounds per square inch

d = inside diameter of pipe in inches

W = weight in pounds of one cubic foot of entering air

L = length of pipe in feet

Copyright 2004, Industrial Press, Inc., New York, NY

Velocity of Escaping Compressed Air.— If air, or gas, flows from one chamber to another, as from a chamber or tank through an orifice or nozzle into the open air, large changes in velocity may take place owing to the difference in pressures. Since the change takes place almost instantly, little heat can escape from the fluid and the flow may be assumed to be adiabatic.

For a large container with a small orifice or hole from which the air escapes, the velocity of escape (theoretical) may be calculated from the formula:

$$v_2 = \sqrt{2g \cdot \frac{k}{k-1} \cdot 53.3(459.7 + F)\left[1 - \left(\frac{p_2}{p_1}\right)^{\frac{k-1}{k}}\right]}$$

In this formula, v_2 = velocity of escaping air in feet per second; g = acceleration due to gravity, 32.16 feet per second squared; $k = 1.41$ for adiabatic expansion or compression of air; F = temperature, degrees F; p_2 = atmospheric pressure = 14.7 pounds per square inch; and p_1 = pressure of air in container, pounds per square inch. In applying the preceding formula, when the ratio p_2/p_1 approximately equals 0.53, under normal temperature conditions at sea level, the escape velocity v_2 will be equal to the velocity of sound. Increasing the pressure p_1 will not increase the velocity of escaping air beyond this limiting velocity unless a special converging diverging nozzle design is used rather than an orifice.

The accompanying table provides velocity of escaping air for various values of p_1. These values were calculated from the preceding formula simplified by substituting the appropriate constants:

$$v_2 = 108.58\sqrt{(459.7 + F)\left[1 - \left(\frac{14.7}{p_1}\right)^{0.29}\right]}$$

Velocity of Escaping Air at 70-Degrees F

Pressure Above Atmospheric Pressure			Theoretical Velocity, Feet per Second	Pressure Above Atmospheric Pressure			Theoretical Velocity, Feet per Second
In Atmospheres	In Inches Mercury	In lbs per sq. in.		In Atmospheres	In Inches Mercury	In lbs per sq. in.	
0.010	0.30	0.147	134	0.408	12.24	6.00	769
0.068	2.04	1.00	344	0.500	15.00	7.35	833
0.100	3.00	1.47	413	0.544	16.33	8.00	861
0.136	4.08	2.00	477	0.612	18.37	9.00	900
0.204	6.12	3.00	573	0.680	20.41	10.0	935
0.272	8.16	4.00	650	0.816	24.49	12.0	997
0.340	10.20	5.00	714	0.884	26.53	13.0	1025

The theoretical velocities in the preceding table must be reduced by multiplying by a "coefficient of discharge," which varies with the orifice and the pressure. The following coefficients are used for orifices in thin plates and short tubes.

Type of Orifice	Pressures in Atmospheres Above Atmospheric Pressure			
	0.01	0.1	0.5	1
Orifice in thin plate	0.65	0.64	0.57	0.54
Orifice in short tube	0.83	0.82	0.71	0.67

Copyright 2004, Industrial Press, Inc., New York, NY

STANDARD STEELS

Properties, Compositions, and Applications

Steel is the generic term for a large family of iron–carbon alloys, which are malleable, within some temperature range, immediately after solidification from the molten state. The principal raw materials used in steelmaking are iron ore, coal, and limestone. These materials are converted in a blast furnace into a product known as "pig iron," which contains considerable amounts of carbon, manganese, sulfur, phosphorus, and silicon. Pig iron is hard, brittle, and unsuitable for direct processing into wrought forms. Steelmaking is the process of refining pig iron as well as iron and steel scrap by removing undesirable elements from the melt and then adding desirable elements in predetermined amounts. A primary reaction in most steelmaking is the combination of carbon with oxygen to form a gas. If dissolved oxygen is not removed from the melt prior to or during pouring, the gaseous products continue to evolve during solidification. If the steel is strongly deoxidized by the addition of deoxidizing elements, no gas is evolved, and the steel is called "killed" because it lies quietly in the molds. Increasing degrees of gas evolution (decreased deoxidation) characterize steels called "semikilled", "capped," or "rimmed." The degree of deoxidation affects some of the properties of the steel. In addition to oxygen, liquid steel contains measurable amounts of dissolved hydrogen and nitrogen. For some critical steel applications, special deoxidation practices as well as vacuum treatments may be used to reduce and control dissolved gases.

The carbon content of common steel grades ranges from a few hundredths of a per cent to about 1 per cent. All steels also contain varying amounts of other elements, principally manganese, which acts as a deoxidizer and facilitates hot working. Silicon, phosphorus, and sulfur are also always present, if only in trace amounts. Other elements may be present, either as residuals that are not intentionally added, but result from the raw materials or steelmaking practice, or as alloying elements added to effect changes in the properties of the steel.

Steels can be cast to shape, or the cast ingot or strand can be reheated and hot worked by rolling, forging, extrusion, or other processes into a wrought mill shape. Wrought steels are the most widely used of engineering materials, offering a multitude of forms, finishes, strengths, and usable temperature ranges. No other material offers comparable versatility for product design.

Standard Steel Classification.— Wrought steels may be classified systematically into groups based on some common characteristic, such as chemical composition, deoxidation practice, finishing method, or product form. Chemical composition is the most often used basis for identifying and assigning standard designations to wrought steels. Although carbon is the principal hardening and strengthening element in steel, no single element controls the steel's characteristics. The combined effect of several elements influences response to heat treatment, hardness, strength, microstructure, corrosion resistance, and formability. The standard steels can be divided broadly into three main groups: carbon steels, alloy steels, and stainless steels.

Carbon Steels: A steel qualifies as a carbon steel when its manganese content is limited to 1.65 per cent (max), silicon to 0.60 per cent (max), and copper to 0.60 per cent (max). With the exception of deoxidizers and boron when specified, no other alloying elements are added intentionally, but they may be present as residuals. If any of these incidental elements are considered detrimental for special applications, maximum acceptable limits may be specified. In contrast to most alloy steels, carbon steels are most often used without a final heat treatment; however, they may be annealed, normalized, case hardened, or quenched and tempered to enhance fabrication or mechanical properties. Carbon steels may be killed, semikilled, capped, or rimmed, and, when necessary, the method of deoxidation may be specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Alloy Steels: Alloy steels comprise not only those grades that exceed the element content limits for carbon steel, but also any grade to which different elements than used for carbon steel are added, within specific ranges or specific minimums, to enhance mechanical properties, fabricating characteristics, or any other attribute of the steel. By this definition, alloy steels encompass all steels other than carbon steels; however, by convention, steels containing over 3.99 per cent chromium are considered "special types" of alloy steel, which include the stainless steels and many of the tool steels.

In a technical sense, the term alloy steel is reserved for those steels that contain a modest amount of alloying elements (about 1–4 per cent) and generally depend on thermal treatments to develop specific mechanical properties. Alloy steels are always killed, but special deoxidation or melting practices, including vacuum, may be specified for special critical applications. Alloy steels generally require additional care throughout their manufacture, because they are more sensitive to thermal and mechanical operations.

Stainless Steels: Stainless steels are high-alloy steels and have superior corrosion resistance to the carbon and conventional low-alloy steels because they contain relatively large amounts of chromium. Although other elements may also increase corrosion resistance, their usefulness in this respect is limited.

Stainless steels generally contain at least 10 per cent chromium, with or without other elements. It has been customary in the United States, however, to include in the stainless steel classification those steels that contain as little as 4 per cent chromium. Together, these steels form a family known as the stainless and heat-resisting steels, some of which possess very high strength and oxidation resistance. Few, however, contain more than 30 per cent chromium or less than 50 per cent iron.

In the broadest sense, the standard stainless steels can be divided into three groups based on their structures: austenitic, ferritic, and martensitic. In each of the three groups, there is one composition that represents the basic, general-purpose alloy. All other compositions are derived from the basic alloy, with specific variations in composition being made to obtain very specific properties.

The *austenitic grades* are nonmagnetic in the annealed condition, although some may become slightly magnetic after cold working. They can be hardened only by cold working, and not by heat treatment, and combine outstanding corrosion and heat resistance with good mechanical properties over a wide temperature range. The austenitic grades are further classified into two subgroups: the chromium–nickel types and the less frequently used chromium–manganese–low–nickel types. The basic composition in the chromium–nickel group is widely known as 18–8 (Cr–Ni) and is the general-purpose austenitic grade. This grade is the basis for over 20 modifications that can be characterized as follows: the chromium–nickel ratio has been modified to change the forming characteristics; the carbon content has been decreased to prevent intergranular corrosion; the elements niobium or titanium have been added to stabilize the structure; or molybdenum has been added or the chromium and nickel contents have been increased to improve corrosion or oxidation resistance.

The standard *ferritic grades* are always magnetic and contain chromium but no nickel. They can be hardened to some extent by cold working, but not by heat treatment, and they combine corrosion and heat resistance with moderate mechanical properties and decorative appeal. The ferritic grades generally are restricted to a narrower range of corrosive conditions than the austenitic grades. The basic ferritic grade contains 17 per cent chromium. In this series, there are free-machining modifications and grades with increased chromium content to improve scaling resistance. Also in this ferritic group is a 12 per cent chromium steel (the basic composition of the martensitic group) with other elements, such as aluminum or titanium, added to prevent hardening.

The standard *martensitic grades* are magnetic and can be hardened by quenching and tempering. They contain chromium and, with two exceptions, no nickel. The basic martensitic grade normally contains 12 per cent chromium. There are more than 10 standard com-

Copyright 2004, Industrial Press, Inc., New York, NY

positions in the martensitic series; some are modified to improve machinability and others have small additions of nickel or other elements to improve the mechanical properties or their response to heat treatment. Still others have greatly increased carbon content, in the tool steel range, and are hardenable to the highest levels of all the stainless steels. The martensitic grades are excellent for service in mild environments such as the atmosphere, freshwater, steam, and weak acids, but are not resistant to severely corrosive solutions.

Numbering Systems for Metals and Alloys.— Several different numbering systems have been developed for metals and alloys by various trade associations, professional engineering societies, standards organizations, and by private industries for their own use. The numerical code used to identify the metal or alloy may or may not be related to a specification, which is a statement of the technical and commercial requirements that the product must meet. Numbering systems in use include those developed by the American Iron and Steel Institute (AISI), Society of Automotive Engineers (SAE), American Society for Testing and Materials (ASTM), American National Standards Institute (ANSI), Steel Founders Society of America, American Society of Mechanical Engineers (ASME), American Welding Society (AWS), Aluminum Association, Copper Development Association, U.S. Department of Defense (Military Specifications), and the General Accounting Office (Federal Specifications).

The Unified Numbering System (UNS) was developed through a joint effort of the ASTM and the SAE to provide a means of correlating the different numbering systems for metals and alloys that have a commercial standing. This system avoids the confusion caused when more than one identification number is used to specify the same material, or when the same number is assigned to two entirely different materials. It is important to understand that a UNS number is not a specification; it is an identification number for metals and alloys for which detailed specifications are provided elsewhere. UNS numbers are shown in Table 1; each number consists of a letter prefix followed by five digits. In some, the letter is suggestive of the family of metals identified by the series, such as A for aluminum and C for copper. Whenever possible, the numbers in the UNS groups contain numbering sequences taken directly from other systems to facilitate identification of the material; e.g., the corresponding UNS number for AISI 1020 steel is G10200. The UNS numbers corresponding to the commonly used AISI-SAE numbers that are used to identify plain carbon, alloy, and tool steels are given in Table 2.

Table 1. Unified Numbering System (UNS) for Metals and Alloys

UNS Series	Metal
A00001 to A99999	Aluminum and aluminum alloys
C00001 to C99999	Copper and copper alloys
D00001 to D99999	Specified mechanical property steels
E00001 to E99999	Rare earth and rare earthlike metals and alloys
F00001 to F99999	Cast irons
G00001 to G99999	AISI and SAE carbon and alloy steels (except tool steels)
H00001 to H99999	AISI and SAE H-steels
J00001 to J99999	Cast steels (except tool steels)
K00001 to K99999	Miscellaneous steels and ferrous alloys
L00001 to L99999	Low-melting metals and alloys
M00001 to M99999	Miscellaneous nonferrous metals and alloys
N00001 to N99999	Nickel and nickel alloys
P00001 to P99999	Precious metals and alloys
R00001 to R99999	Reactive and refractory metals and alloys
S00001 to S99999	Heat and corrosion resistant (stainless) steels
T00001 to T99999	Tool steels, wrought and cast
W00001 to W99999	Welding filler metals
Z00001 to Z99999	Zinc and zinc alloys

Copyright 2004, Industrial Press, Inc., New York, NY

Identifying Metals.— When it is necessary to sort materials, several rough methods may be used without elaborate chemical analysis. The most obvious of these is by using a magnet to pick out those materials that contain magnetic elements. To differentiate various levels of carbon and other elements in a steel bar, hold the bar in contact with a grinding wheel and observe the sparks. With high levels of carbon, for instance, sparks are produced that appear to split into several bright tracers. Patterns produced by several other elements, including small amounts of aluminum and titanium, for instance, can be identified with the aid of Data Sheet 13, issued by the American Society for Metals (ASM), Metals Park, OH.

Standard Steel Numbering System.— The most widely used systems for identifying wrought carbon, low–alloy, and stainless steels are based on chemical composition, and are those of the American Iron and Steel Institute (AISI) and the Society of Automotive Engineers (SAE). These systems are almost identical, but they are carefully coordinated. The standard steels so designated have been developed cooperatively by producers and users and have been found through long experience to cover most of the wrought ferrous metals used in automotive vehicles and related equipment. These designations, however, are not specifications, and should not be used for purchasing unless accompanied by supplementary information necessary to describe commercially the product desired. Engineering societies, associations, and institutes whose members make, specify, or purchase steel products publish standard specifications, many of which have become well known and respected. The most comprehensive and widely used specifications are those published by the American Society for Testing and Materials (ASTM). The U.S. government and various companies also publish their own specification for steel products to serve their own special procurement needs. The Unified Numbering System (UNS) for metals and alloys is also used to designate steels (see pages 440 and 442).

The numerical designation system used by both AISI and SAE for wrought carbon, alloy, and stainless steels is summarized in Table 3. In Table 4 is given the compositions of the standard carbon steels; Table 5 lists the standard low–alloy steel compositions; and Table 6 includes the typical compositions of the standard stainless steels.

Binary Alloy.— An alloy containing two elements. When the term is used in regard to iron or steel, it refers to a material that has one alloying element in addition to iron. Since carbon is always present in steel, plain carbon steel is the typical binary iron alloy.

Ternary Alloy.— This is an alloy consisting of three elements. When the term refers to steel, it denotes a steel which contains two alloying elements in addition to iron; since carbon is always present, it is one of these elements. The third element may be nickel, chromium, manganese, tungsten, molybdenum, titanium, or any other element that is alloyed to give the steel some special property.

Quarternary Alloy.— A quarternary alloy is an alloy consisting of four elements. When applied to steel, such an alloy contains, in addition to iron, three alloying elements. Carbon is one of these, and the other two may be chromium and nickel, silicon and manganese, etc.

Damascus Steel.— A characteristic feature of Damascus steel is its surface patterns which vary with the carbon content and are either in the form of wavy parallel stripes or mottled patterns. This steel represents an early development in steel making, as it was imported during the Middle Ages to Western Europe through Syria and Palestine, and is known also as Indian steel and bulat. The old Indian method of producing real damascene steel consists in using a pure ore and the best grade of charcoal. The Persian practice is to use soft iron bars and charcoal and plumbago (black lead or graphite) to supply the carbon; and a third method consists of a certain heat-treatment which resembles a prolonged tempering. One investigator has concluded that the carbon, irregularly dispersed in the metal and forming two distinct combinations, is what causes the damask or characteristic pattern and that the slower the cooling the larger the veins will be.

An imitation of Damascus steel can be obtained by etching the surface of the steel blade with acids, the parts which are not to be attacked by the acid being protected by a "resist."

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. AISI and SAE Numbers and Their Corresponding UNS Numbers for Plain Carbon, Alloy, and Tool Steels

AISI-SAE Numbers	UNS Numbers	AISI-SAE Numbers	UNS Numbers	AISI-SAE Numbers	UNS Numbers	AISI-SAE Numbers	UNS Numbers
Plain Carbon Steels							
1005	G10050	1030	G10300	1070	G10700	1566	G15660
1006	G10060	1035	G10350	1078	G10780	1110	G11100
1008	G10080	1037	G10370	1080	G10800	1117	G11170
1010	G10100	1038	G10380	1084	G10840	1118	G11180
1012	G10120	1039	G10390	1086	G10860	1137	G11370
1015	G10150	1040	G10400	1090	G10900	1139	G11390
1016	G10160	1042	G10420	1095	G10950	1140	G11400
1017	G10170	1043	G10430	1513	G15130	1141	G11410
1018	G10180	1044	G10440	1522	G15220	1144	G11440
1019	G10190	1045	G10450	1524	G15240	1146	G11460
1020	G10200	1046	G10460	1526	G15260	1151	G11510
1021	G10210	1049	G10490	1527	G15270	1211	G12110
1022	G10220	1050	G10500	1541	G15410	1212	G12120
1023	G10230	1053	G10530	1548	G15480	1213	G12130
1025	G10250	1055	G10550	1551	G15510	1215	G12150
1026	G10260	1059	G10590	1552	G15520	12L14	G12144
1029	G10290	1060	G10600	1561	G15610	…	…
Alloy Steels							
1330	G13300	4150	G41500	5140	G51400	8642	G86420
1335	G13350	4161	G41610	5150	G51500	8645	G86450
1340	G13400	4320	G43200	5155	G51550	8655	G86550
1345	G13450	4340	G43400	5160	G51600	8720	G87200
4023	G40230	E4340	G43406	E51100	G51986	8740	G87400
4024	G40240	4615	G46150	E52100	G52986	8822	G88220
4027	G40270	4620	G46200	6118	G61180	9260	G92600
4028	G40280	4626	G46260	6150	G61500	50B44	G50441
4037	G40370	4720	G47200	8615	G86150	50B46	G50461
4047	G40470	4815	G48150	8617	G86170	50B50	G50501
4118	G41180	4817	G48170	8620	G86200	50B60	G50601
4130	G41300	4820	G48200	8622	G86220	51B60	G51601
4137	G41370	5117	G51170	8625	G86250	81B45	G81451
4140	G41400	5120	G51200	8627	G86270	94B17	G94171
4142	G41420	5130	G51300	8630	G86300	94B30	G94301
4145	G41450	5132	G51320	8637	G86370	…	…
4147	G41470	5135	G51350	8640	G86400	…	…
Tool Steels (AISI and UNS Only)							
M1	T11301	T6	T12006	A6	T30106	P4	T51604
M2	T11302	T8	T12008	A7	T30107	P5	T51605
M4	T11304	T15	T12015	A8	T30108	P6	T51606
M6	T11306	H10	T20810	A9	T30109	P20	T51620
M7	T11307	H11	T20811	A10	T30110	P21	T51621
M10	T11310	H12	T20812	D2	T30402	F1	T60601
M3-1	T11313	H13	T20813	D3	T30403	F2	T60602
M3-2	T11323	H14	T20814	D4	T30404	L2	T61202
M30	T11330	H19	T20819	D5	T30405	L3	T61203
M33	T11333	H21	T20821	D7	T30407	L6	T61206
M34	T11334	H22	T20822	O1	T31501	W1	T72301
M36	T11336	H23	T20823	O2	T31502	W2	T72302
M41	T11341	H24	T20824	O6	T31506	W5	T72305
M42	T11342	H25	T20825	O7	T31507	CA2	T90102
M43	T11343	H26	T20826	S1	T41901	CD2	T90402
M44	T11344	H41	T20841	S2	T41902	CD5	T90405
M46	T11346	H42	T20842	S4	T41904	CH12	T90812
M47	T11347	H43	T20843	S5	T41905	CH13	T90813
T1	T12001	A2	T30102	S6	T41906	CO1	T91501
T2	T12002	A3	T30103	S7	T41907	CS5	T91905
T4	T12004	A4	T30104	P2	T51602	…	…
T5	T12005	A5	T30105	P3	T51603	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. AISI-SAE System of Designating Carbon and Alloy Steels

AISI-SAE Designation[a]	Type of Steel and Nominal Alloy Content (%)
	Carbon Steels
10xx	Plain Carbon (Mn 1.00% max.)
11xx	Resulfurized
12xx	Resulfurized and Rephosphorized
15xx	Plain Carbon (Max. Mn range 1.00 to 1.65%)
	Manganese Steels
13xx	Mn 1.75
	Nickel Steels
23xx	Ni 3.50
25xx	Ni 5.00
	Nickel–Chromium Steels
31xx	Ni 1.25; Cr 0.65 and 0.80
32xx	Ni 1.75; Cr 1.07
33xx	Ni 3.50; Cr 1.50 and 1.57
34xx	Ni 3.00; Cr 0.77
	Molybdenum Steels
40xx	Mo 0.20 and 0.25
44xx	Mo 0.40 and 0.52
	Chromium–Molybdenum Steels
41xx	Cr 0.50, 0.80, and 0.95; Mo 0.12, 0.20, 0.25, and 0.30
	Nickel–Chromium–Molybdenum Steels
43xx	Ni 1.82; Cr 0.50 and 0.80; Mo 0.25
43BVxx	Ni 1.82; Cr 0.50; Mo 0.12 and 0.35; V 0.03 min.
47xx	Ni 1.05; Cr 0.45; Mo 0.20 and 0.35
81xx	Ni 0.30; Cr 0.40; Mo 0.12
86xx	Ni 0.55; Cr 0.50; Mo 0.20
87xx	Ni 0.55; Cr 0.50; Mo 0.25
88xx	Ni 0.55; Cr 0.50; Mo 0.35
93xx	Ni 3.25; Cr 1.20; Mo 0.12
94xx	Ni 0.45; Cr 0.40; Mo 0.12
97xx	Ni 0.55; Cr 0.20; Mo 0.20
98xx	Ni 1.00; Cr 0.80; Mo 0.25
	Nickel–Molybdenum Steels
46xx	Ni 0.85 and 1.82; Mo 0.20 and 0.25
48xx	Ni 3.50; Mo 0.25
	Chromium Steels
50xx	Cr 0.27, 0.40, 0.50, and 0.65
51xx	Cr 0.80, 0.87, 0.92, 0.95, 1.00, and 1.05
50xxx	Cr 0.50; C 1.00 min.
51xxx	Cr 1.02; C 1.00 min.
52xxx	Cr 1.45; C 1.00 min.
	Chromium–Vanadium Steels
61xx	Cr 0.60, 0.80, and 0.95; V 0.10 and 0.15 min
	Tungsten–Chromium Steels
72xx	W 1.75; Cr 0.75
	Silicon–Manganese Steels
92xx	Si 1.40 and 2.00; Mn 0.65, 0.82, and 0.85; Cr 0.00 and 0.65
	High–Strength Low–Alloy Steels
9xx	Various SAE grades
xxBxx	B denotes boron steels
xxLxx	L denotes leaded steels

AISI	SAE	Stainless Steels
2xx	302xx	Chromium–Manganese–Nickel Steels
3xx	303xx	Chromium–Nickel Steels
4xx	514xx	Chromium Steels
5xx	515xx	Chromium Steels

[a] xx in the last two digits of the carbon and low–alloy designations (but not the stainless steels) indicates that the carbon content (in hundredths of a per cent) is to be inserted.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Composition of AISI-SAE Standard Carbon Steels

AISI-SAE No.	UNS No.	Composition(%)[a]			
		C	Mn	P(max)[b]	S(max)[b]
Nonresulfurized Grades — 1 per cent Mn (max)					
1005[c]	G10050	0.06 max	0.35 max	0.040	0.050
1006[c]	G10060	0.08 max	0.25–0.40	0.040	0.050
1008	G10080	0.10 max	0.30–0.50	0.040	0.050
1010	G10100	0.08–0.13	0.30–0.60	0.040	0.050
1012	G10120	0.10–0.15	0.30–0.60	0.040	0.050
1015	G10150	0.13–0.18	0.30–0.60	0.040	0.050
1016	G10160	0.13–0.18	0.60–0.90	0.040	0.050
1017	G10170	0.15–0.20	0.30–0.60	0.040	0.050
1018	G10180	0.15–0.20	0.60–0.90	0.040	0.050
1019	G10190	0.15–0.20	0.70–1.00	0.040	0.050
1020	G10200	0.18–0.23	0.30–0.60	0.040	0.050
1021	G10210	0.18–0.23	0.60–0.90	0.040	0.050
1022	G10220	0.18–0.23	0.70–1.00	0.040	0.050
1023	G10230	0.20–0.25	0.30–0.60	0.040	0.050
1025	G10250	0.22–0.28	0.30–0.60	0.040	0.050
1026	G10260	0.22–0.28	0.60–0.90	0.040	0.050
1029	G10290	0.25–0.31	0.60–0.90	0.040	0.050
1030	G10300	0.28–0.34	0.60–0.90	0.040	0.050
1035	G10350	0.32–0.38	0.60–0.90	0.040	0.050
1037	G10370	0.32–0.38	0.70–1.00	0.040	0.050
1038	G10380	0.35–0.42	0.60–0.90	0.040	0.050
1039	G10390	0.37–0.44	0.70–1.00	0.040	0.050
1040	G10400	0.37–0.44	0.60–0.90	0.040	0.050
1042	G10420	0.40–0.47	0.60–0.90	0.040	0.050
1043	G10430	0.40–0.47	0.70–1.00	0.040	0.050
1044	G10440	0.43–0.50	0.30–0.60	0.040	0.050
1045	G10450	0.43–0.50	0.60–0.90	0.040	0.050
1046	G10460	0.43–0.50	0.70–1.00	0.040	0.050
1049	G10490	0.46–0.53	0.60–0.90	0.040	0.050
1050	G10500	0.48–0.55	0.60–0.90	0.040	0.050
1053	G10530	0.48–0.55	0.70–1.00	0.040	0.050
1055	G10550	0.50–0.60	0.60–0.90	0.040	0.050
1059[c]	G10590	0.55–0.65	0.50–0.80	0.040	0.050
1060	G10600	0.55–0.65	0.60–0.90	0.040	0.050
1064[c]	G10640	0.60–0.70	0.50–0.80	0.040	0.050
1065[c]	G10650	0.60–0.70	0.60–0.90	0.040	0.050
1069[c]	G10690	0.65–0.75	0.40–0.70	0.040	0.050
1070	G10700	0.65–0.75	0.60–0.90	0.040	0.050
1078	G10780	0.72–0.85	0.30–0.60	0.040	0.050
1080	G10800	0.75–0.88	0.60–0.90	0.040	0.050
1084	G10840	0.80–0.93	0.60–0.90	0.040	0.050
1086[c]	G10860	0.80–0.93	0.30–0.50	0.040	0.050
1090	G10900	0.85–0.98	0.60–0.90	0.040	0.050
1095	G10950	0.90–1.03	0.30–0.50	0.040	0.050

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Composition of AISI-SAE Standard Carbon Steels**

AISI-SAE No.	UNS No.	Composition(%)[a]			
		C	Mn	P(max)[b]	S(max)[b]
Nonresulfurized Grades — Over 1 per cent Mn					
1513	G15130	0.10–0.16	1.10–1.40	0.040	0.050
1522	G15220	0.18–0.24	1.10–1.40	0.040	0.050
1524	G15240	0.19–0.25	1.35–1.65	0.040	0.050
1526	G15260	0.22–0.29	1.10–1.40	0.040	0.050
1527	G15270	0.22–0.29	1.20–1.50	0.040	0.050
1541	G15410	0.36–0.44	1.35–1.65	0.040	0.050
1548	G15480	0.44–0.52	1.10–1.40	0.040	0.050
1551	G15510	0.45–0.56	0.85–1.15	0.040	0.050
1552	G15520	0.47–0.55	1.20–1.50	0.040	0.050
1561	G15610	0.55–0.65	0.75–1.05	0.040	0.050
1566	G15660	0.60–0.71	0.85–1.15	0.040	0.050
Free-Machining Grades — Resulfurized					
1110	G11100	0.08–0.13	0.30–0.60	0.040	0.08–0.13
1117	G11170	0.14–0.20	1.00–1.30	0.040	0.08–0.13
1118	G11180	0.14–0.20	1.30–1.60	0.040	0.08–0.13
1137	G11370	0.32–0.39	1.35–1.65	0.040	0.08–0.13
1139	G11390	0.35–0.43	1.35–1.65	0.040	0.13–0.20
1140	G11400	0.37–0.44	0.70–1.00	0.040	0.08–0.13
1141	G11410	0.37–0.45	1.35–1.65	0.040	0.08–0.13
1144	G11440	0.40–0.48	1.35–1.65	0.040	0.24–0.33
1146	G11460	0.42–0.49	0.70–1.00	0.040	0.08–0.13
1151	G11510	0.48–0.55	0.70–1.00	0.040	0.08–0.13
Free-Machining Grades — Resulfurized and Rephosphorized					
1211	G12110	0.13 max	0.60–0.90	0.07–0.12	0.10–0.15
1212	G12120	0.13 max	0.70–1.00	0.07–0.12	0.16–0.23
1213	G12130	0.13 max	0.70–1.00	0.07–0.12	0.24–0.33
1215	G12150	0.09 max	0.75–1.05	0.04–0.09	0.26–0.35
12L14[d]	G12144	0.15 max	0.85–1.15	0.04–0.09	0.26–0.35

[a] The following notes refer to boron, copper, lead, and silicon additions: Boron: Standard killed carbon steels, which are generally fine grain, may be produced with a boron treatment addition to improve hardenability. Such steels are produced to a range of 0.0005–0.003 per cent B. These steels are identified by inserting the letter "B" between the second and third numerals of the AISI or SAE number, e.g., 10B46. Copper: When copper is required, 0.20 per cent (min) is generally specified. Lead: Standard carbon steels can be produced with a lead range of 0.15–0.35 per cent to improve machinability. Such steels are identified by inserting the letter "L" between the second and third numerals of the AISI or SAE number, e.g., 12L15 and 10L45. Silicon: It is not common practice to produce the 12XX series of resulfurized and rephosphorized steels to specified limits for silicon because of its adverse effect on machinability. When silicon ranges or limits are required for resulfurized or nonresulfurized steels, however, these values apply: a range of 0.08 per cent Si for Si max up to 0.15 per cent inclusive, a range of 0.10 per cent Si for Si max over 0.15 to 0.20 per cent inclusive, a range of 0.15 per cent Si for Si max over 0.20 to 0.30 per cent inclusive, and a range of 0.20 per cent Si for Si max over 0.30 to 0.60 per cent inclusive. Example: Si max is 0.25 per cent, range is 0.10–0.25 per cent.

[b] Values given are maximum percentages, except where a range of values is given.

[c] Standard grades for wire rods and wire only.

[d] 0.15–0.35 per cent Pb.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Compositions of AISI-SAE Standard Alloy Steels

AISI-SAE No.	UNS No.	Composition (%)[a,b]							
		C	Mn	P (max)	S (max)	Si	Ni	Cr	Mo
1330	G13300	0.28–0.33	1.60–1.90	0.035	0.040	0.15–0.35	…	…	…
1335	G13350	0.33–0.38	1.60–1.90	0.035	0.040	0.15–0.35	…	…	…
1340	G13400	0.38–0.43	1.60–1.90	0.035	0.040	0.15–0.35	…	…	…
1345	G13450	0.43–0.48	1.60–1.90	0.035	0.040	0.15–0.35	…	…	…
4023	G40230	0.20–0.25	0.70–0.90	0.035	0.040	0.15–0.35	…	…	0.20–0.30
4024	G40240	0.20–0.25	0.70–0.90	0.035	0.035–0.050	0.15–0.35	…	…	0.20–0.30
4027	G40270	0.25–0.30	0.70–0.90	0.035	0.040	0.15–0.35	…	…	0.20–0.30
4028	G40280	0.25–0.30	0.70–0.90	0.035	0.035–0.050	0.15–0.35	…	…	0.20–0.30
4037	G40370	0.35–0.40	0.70–0.90	0.035	0.040	0.15–0.35	…	…	0.20–0.30
4047	G40470	0.45–0.50	0.70–0.90	0.035	0.040	0.15–0.35	…	…	0.20–0.30
4118	G41180	0.18–0.23	0.70–0.90	0.035	0.040	0.15–0.35	…	0.40–0.60	0.08–0.15
4130	G41300	0.28–0.33	0.40–0.60	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4137	G41370	0.35–0.40	0.70–0.90	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4140	G41400	0.38–0.43	0.75–1.00	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4142	G41420	0.40–0.45	0.75–1.00	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4145	G41450	0.43–0.48	0.75–1.00	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4147	G41470	0.45–0.50	0.75–1.00	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4150	G41500	0.48–0.53	0.75–1.00	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15–0.25
4161	G41610	0.56–0.64	0.75–1.00	0.035	0.040	0.15–0.35	…	0.70–0.90	0.25–0.35
4320	G43200	0.17–0.22	0.45–0.65	0.035	0.040	0.15–0.35	1.65–2.00	0.40–0.60	0.20–0.30
4340	G43400	0.38–0.43	0.60–0.80	0.035	0.040	0.15–0.35	1.65–2.00	0.70–0.90	0.20–0.30
E4340[c]	G43406	0.38–0.43	0.65–0.85	0.025	0.025	0.15–0.35	1.65–2.00	0.70–0.90	0.20–0.30
4615	G46150	0.13–0.18	0.45–0.65	0.035	0.040	0.15–0.35	1.65–2.00	…	0.20–0.30
4620	G46200	0.17–0.22	0.45–0.65	0.035	0.040	0.15–0.35	1.65–2.00	…	0.20–0.30
4626	G46260	0.24–0.29	0.45–0.65	0.035	0.040	0.15–0.35	0.70–1.00	…	0.15–0.25
4720	G47200	0.17–0.22	0.50–0.70	0.035	0.040	0.15–0.35	0.90–1.20	0.35–0.55	0.15–0.25
4815	G48150	0.13–0.18	0.40–0.60	0.035	0.040	0.15–0.35	3.25–3.75	…	0.20–0.30
4817	G48170	0.15–0.20	0.40–0.60	0.035	0.040	0.15–0.35	3.25–3.75	…	0.20–0.30
4820	G48200	0.18–0.23	0.50–0.70	0.035	0.040	0.15–0.35	3.25–3.75	…	0.20–0.30
5117	G51170	0.15–0.20	0.70–0.90	0.035	0.040	0.15–0.35	…	070–0.90	…
5120	G51200	0.17–0.22	0.70–0.90	0.035	0.040	0.15–0.35	…	0.70–0.90	…
5130	G51300	0.28–0.33	0.70–0.90	0.035	0.040	0.15–0.35	…	0.80–1.10	…
5132	G51320	0.30–0.35	0.60–0.80	0.035	0.040	0.15–0.35	…	0.75–1.00	…
5135	G51350	0.33–0.38	0.60–0.80	0.035	0.040	0.15–0.35	…	0.80–1.05	…
5140	G51400	0.38–0.43	0.70–0.90	0.035	0.040	0.15–0.35	…	0.70–0.90	…
5150	G51500	0.48–0.53	0.70–0.90	0.035	0.040	0.15–0.35	…	0.70–0.90	…
5155	G51550	0.51–0.59	0.70–0.90	0.035	0.040	0.15–0.35	…	0.70–0.90	…
5160	G51600	0.56–0.64	0.75–1.00	0.035	0.040	0.15–0.35	…	0.70–0.90	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **Compositions of AISI-SAE Standard Alloy Steels**

AISI-SAE No.	UNS No.	Composition (%)[a,b]							
		C	Mn	P (max)	S (max)	Si	Ni	Cr	Mo
E51100[c]	G51986	0.98–1.10	0.25–0.45	0.025	0.025	0.15–0.35	…	0.90–1.15	…
E52100[c]	G52986	0.98–1.10	0.25–0.45	0.025	0.025	0.15–0.35	…	1.30–1.60	…
6118	G61180	0.16–0.21	0.50–0.70	0.035	0.040	0.15–0.35	…	0.50–0.70	0.10–0.15 V
6150	G61500	0.48–0.53	0.70–0.90	0.035	0.040	0.15–0.35	…	0.80–1.10	0.15 V min
8615	G86150	0.13–0.18	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8617	G86170	0.15–0.20	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8620	G86200	0.18–0.23	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8622	G86220	0.20–0.25	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8625	G86250	0.23–0.28	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8627	G86270	0.25–0.30	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8630	G86300	0.28–0.33	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8637	G86370	0.35–0.40	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8640	G86400	0.38–0.43	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8642	G86420	0.40–0.45	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8645	G86450	0.43–0.48	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8655	G86550	0.51–0.59	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.15–0.25
8720	G87200	0.18–0.23	0.70–0.90	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.20–0.30
8740	G87400	0.38–0.43	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.20–0.30
8822	G88220	0.20–0.25	0.75–1.00	0.035	0.040	0.15–0.35	0.40–0.70	0.40–0.60	0.30–0.40
9260	G92600	0.56–0.64	0.75–1.00	0.035	0.040	1.80–2.20	…	…	…
Standard Boron Grades[d]									
50B44	G50441	0.43–0.48	0.75–1.00	0.035	0.040	0.15–0.35	…	0.40–0.60	…
50B46	G50461	0.44–0.49	0.75–1.00	0.035	0.040	0.15–0.35	…	0.20–0.35	…
50B50	G50501	0.48–0.53	0.75–1.00	0.035	0.040	0.15–0.35	…	0.40–0.60	…
50B60	G50601	0.56–0.64	0.75–1.00	0.035	0.040	0.15–0.35	…	0.40–0.60	…
51B60	G51601	0.56–0.64	0.75–1.00	0.035	0.040	0.15–0.35	…	0.70–0.90	…
81B45	G81451	0.43–0.48	0.75–1.00	0.035	0.040	0.15–0.35	0.20–0.40	0.35–0.55	0.08–0.15
94B17	G94171	0.15–0.20	0.75–1.00	0.035	0.040	0.15–0.35	0.30–0.60	0.30–0.50	0.08–0.15
94B30	G94301	0.28–0.33	0.75–1.00	0.035	0.040	0.15–0.35	0.30–0.60	0.30–0.50	0.08–0.15

[a] Small quantities of certain elements are present that are not specified or required. These incidental elements may be present to the following maximum amounts: Cu, 0.35 per cent; Ni, 0.25 per cent; Cr, 0.20 per cent; and Mo, 0.06 per cent.

[b] Standard alloy steels can also be produced with a lead range of 0.15–0.35 per cent. Such steels are identified by inserting the letter "L" between the second and third numerals of the AISI or SAE number, e.g., 41L40.

[c] Electric furnace steel.

[d] 0.0005–0.003 per cent B.

Source: American Iron and Steel Institute: *Steel Products Manual*.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Standard Stainless Steels — Typical Compositions

AISI Type (UNS)	Typical Composition (%)	AISI Type (UNS)	Typical Composition (%)
Austenitic			
201 (S20100)	16–18 Cr, 3.5–5.5 Ni, 0.15 C, 5.5–7.5 Mn, 0.75 Si, 0.060 P, 0.030 S, 0.25 N	310 (S31000)	24–26 Cr, 19–22 Ni, 0.25 C, 2.0 Mn, 1.5 Si, 0.045 P, 0.030 S
202 (S20200)	17–19 Cr, 4–6 Ni, 0.15 C, 7.5–10.0 Mn, 0.75 Si, 0.060 P, 0.030 S, 0.25 N	310S (S31008)	24–26 Cr, 19–22 Ni, 0.08 C, 2.0 Mn, 1.5 Si, 0.045 P, 0.30 S
205 (S20500)	16.5–18 Cr, 1–1.75 Ni, 0.12–0.25 C, 14–15.5 Mn, 0.75 Si, 0.060 P, 0.030 S, 0.32–0.40 N	314 (S31400)	23–26 Cr, 19–22 Ni, 0.25 C, 2.0 Mn, 1.5–3.0 Si, 0.045 P, 0.030 S
301 (S30100)	16–18 Cr, 6–8 Ni, 0.15 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S	316 (S31600)	16–18 Cr, 10–14 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 2.0–3.0 Mo, 0.10 N
302 (S30200)	17–19 Cr, 8–10 Ni, 0.15 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 0.10 N	316L (S31603)	16–18 Cr, 10–14 Ni, 0.03 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 2.0–3.0 Mo, 0.10 N
302B (S30215)	17–19 Cr, 8–10 Ni, 0.15 C, 2.0 Mn, 2.0–3.0 Si, 0.045 P, 0.030 S	316F (S31620)	16–18 Cr, 10–14 Ni, 0.08 C, 2.0 Mn, 1.0 Si, 0.20 P, 0.10 S min, 1.75–2.50 Mo
303 (S30300)	17–19 Cr, 8–10 Ni, 0.15 C, 2.0 Mn, 1.0 Si, 0.20 P, 0.015 S min, 0.60 Mo (optional)	316N (S31651)	16–18 Cr, 10–14 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 2–3 Mo, 0.10–0.16 N
303Se (S30323)	17–19 Cr, 8–10 Ni, 0.15 C, 2.0 Mn, 1.0 Si, 0.20 P, 0.060 S, 0.15 Se min	317 (S31700)	18–20 Cr, 11–15 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 3.0–4.0 Mo, 0.10 N max
304 (S30400)	18–20 Cr, 8–10.50 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 0.10 N	317L (S31703)	18–20 Cr, 11–15 Ni, 0.03 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 3–4 Mo, 0.10 N max
304L (S30403)	18–20 Cr, 8–12 Ni, 0.03 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 0.10 N	321 (S32100)	17–19 Cr, 9–12 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S [Ti, 5(C + N) min, 0.70 max], 0.10 max
304 Cu (S30430)	17–19 Cr, 8–10 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 3–4 Cu	329 (S32900)	23–28 Cr, 2.5–5 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.040 P, 0.030 S, 1–2 Mo
304N (S30451)	18–20 Cr, 8–10.5 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S, 0.10–0.16 N	330 (N08330)	17–20 Cr, 34–37 Ni, 0.08 C, 2.0 Mn, 0.75–1.50 Si, 0.040 P, 0.030 S
305 (S30500)	17–19 Cr, 10.50–13 Ni, 0.12 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S	347 (S34700)	17–19 Cr, 9–13 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S (Nb + Ta, 10 × C min, 1 max)
308 (S30800)	19–21 Cr, 10–12 Ni, 0.08 C, 2.0 Mn, 1.0 Si, 0.045 P, 0.030 S	348 (S34800)	17–19 Cr, 9–13 Ni, 0.08 C, 2.0 Mn, 0.75 Si, 0.045 P, 0.030 S (Nb + Ta, 10 × C min, 1 max, but 0.10 Ta max), 0.20 Ca
309 (S30900)	22–24 Cr, 12–15 Ni, 0.20 C, 2.0 Mn, 1.0 Si, 0.045 P, 0.030 S	384 (S38400)	15–17 Cr, 17–19 Ni, 0.08 C, 2.0 Mn, 1.0 Si, 0.045 P, 0.030 S
309S (S30908)	22–24 Cr, 12–15 Ni, 0.08 C, 2.0 Mn, 1.0 Si, 0.045 P, 0.030 S	…	…
Ferritic			
405 (S40500)	11.5–14.5 Cr, 0.08 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.1–0.3 Al, 0.60 max	430FSe (S43023)	16–18 Cr, 0.12 C, 1.25 Mn, 1.0 Si, 0.060 P, 0.060 S, 0.15 Se min
409 (S40900)	10.5–11.75 Cr, 0.08 C, 1.0 Mn, 1.0 Si, 0.045 P, 0.030 S, 0.05 Ni (Ti 6 × C, but with 0.75 max)	434 (S43400)	16–18 Cr, 0.12 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.75–1.25 Mo
429 (S42900)	14–16 Cr, 0.12 C, 1.0 Mn, 1.0 Si, 0.040 P, 030 S, 0.75 Ni	436 (S43600)	16–18 Cr, 0.12 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.75–1.25 Mo (Nb + Ta 5 × C min, 0.70 max)
430 (S43000)	16–18 Cr, 0.12 C, 1.0 Mn, 1.0 Si, 0.040 P, 030 S, 0.75 Ni	442 (S44200)	18–23 Cr, 0.20 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S
430F (S43020)	16–18 Cr, 0.12 C, 1.25 Mn, 1.0 Si, 0.060 P, 0.15 S min, 0.60 Mo (optional)	446 (S44600)	23–27 Cr, 0.20 C, 1.5 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.025 N

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ***(Continued)*** **Standard Stainless Steels — Typical Compositions**

AISI Type (UNS)	Typical Composition (%)	AISI Type (UNS)	Typical Composition (%)
Martensitic			
403 (S40300)	11.5–13.0 Cr, 1.15 C, 1.0 Mn, 0.5 Si, 0.040 P, 0.030 S, 0.60 Ni	420F (S42020)	12–14 Cr, over 0.15 C, 1.25 Mn, 1.0 Si, 0.060 P, 0.15 S min, 0.60 Mo max (optional)
410 (S41000)	11.5–13.5 Cr, 0.15 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.75 Ni	422 (S42200)	11–12.50 Cr, 0.50–1.0 Ni, 0.20– 0.25 C, 0.50–1.0 Mn, 0.50 Si, 0.025 P, 0.025 S, 0.90–1.25 Mo, 0.20–0.30 V, 0.90–1.25 W
414 (S41400)	11.5–13.5 Cr, 1.25–2.50 Ni, 0.15 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 1.25–2.50 Ni	431 (S41623)	15–17 Cr, 1.25–2.50 Ni, 0.20 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S
416 (S41600)	12–14 Cr, 0.15 C, 1.25 Mn, 1.0 Si, 0.060 P, 0.15 S min, 0.060 Mo (optional)	440A (S44002)	16–18 Cr, 0.60–0.75 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.75 Mo
416Se (S41623)	12–14 Cr, 0.15 C, 1.25 Mn, 1.0 Si, 0.060 P, 0.060 S, 0.15 Se min	440B (S44003)	16–18 Cr, 0.75–0.95 C, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.75 Mo
420 (S42000)	12–14 Cr, 0.15 C min, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S	440C (S44004)	16–18 Cr, 0.95–1.20 C, 1.0 Mn, 1.0 Si, 0040 P, 0.030 S, 0.75 Mo
Heat-Resisting			
501 (S50100)	4–6 Cr, 0.10 C min, 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.40–0.65 Mo	502 (S50200)	4–6 Cr, 0.10 C. 1.0 Mn, 1.0 Si, 0.040 P, 0.030 S, 0.40–0.65 Mo

Thermal Treatments of Steel.— Steel's versatility is due to its response to thermal treatment. Although most steel products are used in the as-rolled or un-heat-treated condition, thermal treatment greatly increases the number of properties that can be obtained, because at certain "critical temperatures" iron changes from one type of crystal structure to another. This structural change, known as an allotropic transformation, is spontaneous and reversible and can be made to occur by simply changing the temperature of the metal.

In steel, the transformation in crystal structure occurs over a range of temperatures, bounded by lower and upper critical points. When heated, most carbon and low–alloy steels have a critical temperature range between 1300 and 1600 degrees F. Steel above this temperature, but below the melting range, has a crystalline structure known as austenite, in which the carbon and alloying elements are dissolved in a solid solution. Below this critical range, the crystal structure changes to a phase known as ferrite, which is capable of maintaining only a very small percentage of carbon in solid solution. The remaining carbon exists in the form of carbides, which are compounds of carbon and iron and certain of the other alloying elements. Depending primarily on cooling rate, the carbides may be present as thin plates alternating with the ferrite (pearlite); as spheroidal globular particles at ferrite grain boundaries or dispersed throughout the ferrite; or as a uniform distribution of extremely fine particles throughout a "ferritelike" phase, which has an acicular (needle-like) appearance, named martensite. In some of the highly alloyed stainless steels the addtion of certain elements stabilizes the austenite structure so that it persists even at very low temperatures (austenitic grades). Other alloying elements can prevent the formation of austenite entirely up to the melting point (ferritic grades).

Fundamentally, all steel heat treatments are intended to either harden or soften the metal. They involve one or a series of operations in which the solid metal is heated and cooled under specified conditions to develop a required structure and properties. In general, there are five major forms of heat treatment for the standard steels that modify properties to suit either fabrication or end use.

Quenching and Tempering: The primary hardening treatment for steel, quenching and tempering, usually consists of three successive operations: heating the steel above the critical range and holding it at these temperatures for a sufficient time to approach a uniform

Copyright 2004, Industrial Press, Inc., New York, NY

solid solution (austenitizing); cooling the steel rapidly by quenching in oil, water, brine, salt or air to form a hard, usually brittle, metastable structure known as untempered or white martensite; tempering the steel by reheating it to a temperature below the critical range in order to obtain the required combination of hardness, strength, ductility, toughness, and structural stability (tempered martensite).

Two well-known modifications of conventional quenching and tempering are "austempering" and "martempering." They involve interrupted quenching techniques (two or more quenching media) that can be utilized for some steels to obtain desired structures and properties while minimizing distortion and cracking problems that may occur in conventional hardening.

Normalizing: The steel is heated to a temperature above the critical range, after which it is cooled in still air to produce a generally fine pearlite structure. The purpose is to promote uniformity of structure and properties after a hot-working operation such as forging or extrusion. Steels may be placed in service in the normalized condition, or they may be subjected to additional thermal treatment after subsequent machining or other operations.

Annealing: The steel is heated to a temperature above or within the critical range, then cooled at a predetermined slow rate (usually in a furnace) to produce a coarse pearlite structure. This treatment is used to soften the steel for improved machinability; to improve or restore ductility for subsequent forming operations; or to eliminate the residual stresses and microstructural effects of cold working.

Spheroidize Annealing: This is a special form of annealing that requires prolonged heating at an appropriate temperature followed by slow cooling in order to produce globular carbides, a structure desirable for machining, cold forming, or cold drawing, or for the effect it will have on subsequent heat treatment.

Stress Relieving: This process reduces internal stresses, caused by machining, cold working, or welding, by heating the steel to a temperature below the critical range and holding it there long enough to equalize the temperature throughout the piece.

See the sections *HARDENING, TEMPERING, AND ANNEALING* on page 503 and *Heat Treating High-Speed Steels* on page 538 for more information about the heat treatment of steels.

Applications.— Many factors enter into the selection of a steel for a particular application. These factors include the mechanical and physical properties needed to satisfy the design requirements and service environment; the cost and availability of the material; the cost of processing (machining, heat treatment, welding, etc.); and the suitability of available processing equipment or the cost of any new equipment required.

These steel selection considerations require input from designers, metallurgists, manufacturing engineers, service engineers, and procurement specialists, and can be considered proper or optimum when the part is made from the lowest cost material consistent with satisfying engineering and service requirements. The factors in selection can vary widely among different organizations, so that several different steels may be used successfully for similar applications. The best choice of a steel for any application most often results from a balance or trade-offs among the various selection considerations.

The AISI/SAE designated "standard steels" provide a convenient way for engineers and metallurgists to state briefly but clearly the chemical composition and, in some instances, some of the properties desired, and they are widely recognized and used in the United States and in many other countries. There are, however, numerous nonstandard carbon, alloy, and stainless steel grades that are widely used for special applications.

The following sections and tables illustrate the general characteristics and typical applications of most of the standard carbon, alloy, and stainless steel grades.

General Application of SAE Steels: These applications are intended as a general guide only since the selection may depend on the exact character of the service, cost of material,

Copyright 2004, Industrial Press, Inc., New York, NY

machinability when machining is required, or other factors. When more than one steel is recommended for a given application, information on the characteristics of each steel listed will be found in the section beginning on page 452.

Adapters, 1145
Agricultural steel, 1070, 1080
Aircraft forgings, 4140
Axles front or rear, 1040, 4140
Axle shafts, 1045, 2340, 2345, 3135, 3140, 3141, 4063, 4340
Ball-bearing races, 52100
Balls for ball bearings, 52100
Body stock for cars, rimmed*
Bolts and screws, 1035
Bolts
  anchor, 1040
  cold-headed, 4042
  connecting-rod, 3130
  heat-treated, 2330
  heavy-duty, 4815, 4820
  steering-arm, 3130
Brake levers, 1030, 1040
Bumper bars, 1085
Cams free-wheeling, 4615, 4620
Camshafts, 1020, 1040
Carburized parts, 1020, 1022, 1024, 1117, 1118, 1320, 2317, 2515, 3310, 3115, 3120, 4023, 4032
Chain pins transmission, 4320, 4815, 4820
Chains transmission, 3135, 3140
Clutch disks, 1060, 1070, 1085
Clutch springs, 1060
Coil springs, 4063
Cold-headed bolts, 4042
Cold-heading
  steel, 30905, 1070
  wire or rod, rimmed*, 1035
Cold-rolled steel, 1070
Connecting-rods, 1040, 3141
Connecting-rod bolts, 3130
Corrosion resisting, 51710, 30805
Covers transmission, rimmed*
Crankshafts, 1045, 1145, 3135, 3140, 3141
Crankshafts Diesel engine, 4340
Cushion springs, 1060
Cutlery stainless, 51335
Cylinder studs, 3130
Deep-drawing steel, rimmed*, 30905
Differential gears, 4023
Disks clutch, 1070, 1060
Ductile steel, 30905
Fan blades, 1020
Fatigue resisting 4340, 4640
Fender stock for cars, rimmed*
Forgings
  aircraft, 4140
  carbon steel, 1040, 1045
  heat-treated, 3240, 5140, 6150
  high-duty, 6150
  small or medium, 1035
  large, 1036
Free-cutting steel
  carbon, 1111, 1113
  chromium-nickel steel, 30615
  manganese steel, 1132, 1137
Gears
  carburized, 1320, 2317, 3115, 3120, 3310, 4119, 4125, 4320, 4615, 4620, 4815, 4820
  heat-treated, 2345
  car and truck, 4027, 4032
  cyanide-hardening, 5140
  differential, 4023
  high duty, 4640, 6150
  oil-hardening, 3145, 3150, 4340, 5150
  ring, 1045, 3115, 3120, 4119
  transmission, 3115, 3120, 4119
  truck and bus, 3310, 4320
Gear shift levers, 1030
Harrow disks, 1080
Hay-rake teeth, 1095
Key stock, 1030, 2330, 3130
Leaf springs, 1085, 9260
Levers
  brake, 1030, 1040
  gear shift, 1030
  heat-treated, 2330
Lock washers, 1060
Mower knives, 1085
Mower sections, 1070
Music wire, 1085
Nuts, 3130
  heat-treated, 2330
Oil pans automobile, rimmed*
Pinions carburized, 3115, 3120, 4320
Piston pins, 3115, 3120
Plow
  beams, 1070

* The "rimmed" and "killed" steels listed are in the SAE 1008, 1010, and 1015 group. See general description of these steels.

Copyright 2004, Industrial Press, Inc., New York, NY

disks, 1080
shares, 1080
Propeller shafts, 2340, 2345, 4140
Races ball-bearing, 52100
Ring gears, 3115, 3120, 4119
Rings snap, 1060, 1070, 1090
Rivets, rimmed*
Rod and wire, killed*
Rod cold-heading, 1035
Roller bearings, 4815
Rollers for bearings, 52100
Screws and bolts, 1035
Screw stock
Bessemer, 1111, 1112, 1113
open-hearth, 1115
Screws heat-treated, 2330
Seat springs, 10956
Shafts
axle, 1045
cyanide-hardening, 5140
heavy-duty, 4340, 6150, 4615, 4620
oil-hardening, 5150
propeller, 2340, 2345, 4140
transmission, 4140
Sheets and strips, rimmed*
Snap rings, 1060, 1070, 1090
Spline shafts, 1045, 1320, 2340, 2345, 3115, 3120, 3135, 3140, 4023
Spring clips, 1060
Springs
coil, 1095, 4063, 6150
clutch, 1060
cushion, 1060
hard-drawn coiled, 1066
leaf, 1085, 1095, 4063, 4068, 9260, 6150
oil-hardening, 5150
oil-tempered wire, 1066
seat, 1095
valve, 1060
Spring wire, 1045
hard-drawn, 1055
oil-tempered, 1055
Stainless irons, 51210, 51710
Steel
cold-rolled, 1070
cold-heading, 30905
free-cutting carbon, 1111, 1113
free-cutting chrome-nickel, 30615
free-cutting manganese, 1132
minimum distortion, 4615, 4620, 4640
soft ductile, 30905
Steering arms, 4042
Steering-arm bolts, 3130
Steering knuckles, 3141
Steering-knuckle pins, 4815, 4820
Tacks, rimmed*
Thrust washers, 1060
oil-hardened, 5150
Transmission shafts, 4140
Tubing, 1040
front axle, 4140
seamless, 1030
welded, 1020
Universal joints, 1145
Valve springs, 1060
Washers lock, 1060
Welded structures, 30705
Wire and rod, killed*
Wire
cold-heading, rimmed*
hard-drawn spring, 1045, 1055
music, 1085
oil-tempered spring, 1055
Wrist-pins automobile, 1020
Yokes, 1145

Carbon Steels.— *SAE Steels 1006, 1008, 1010, 1015:* These steels are the lowest carbon steels of the plain carbon type, and are selected where cold formability is the primary requisite of the user. They are produced both as rimmed and killed steels. Rimmed steel is used for sheet, strip, rod, and wire where excellent surface finish or good drawing qualities are required, such as body and fender stock, hoods, lamps, oil pans, and other deep-drawn and -formed products. This steel is also used for cold-heading wire for tacks, and rivets and low carbon wire products. Killed steel (usually aluminum killed or special killed) is used for difficult stampings, or where nonaging properties are needed. Killed steels (usually silicon killed) should be used in preference to rimmed steel for forging or heat-treating applications.

These steels have relatively low tensile values and should not be selected where much strength is desired. Within the carbon range of the group, strength and hardness will rise with increases in carbon and/or with cold work, but such increases in strength are at the sacrifice of ductility or the ability to withstand cold deformation. Where cold rolled strip is used, the proper temper designation should be specified to obtain the desired properties.

Copyright 2004, Industrial Press, Inc., New York, NY

With less than 0.15 carbon, the steels are susceptible to serious grain growth, causing brittleness, which may occur as the result of a combination of critical strain (from cold work) followed by heating to certain elevated temperatures. If cold-worked parts formed from these steels are to be later heated to temperatures in excess of 1100 degrees F, the user should exercise care to avoid or reduce cold working. When this condition develops, it can be overcome by heating the parts to a temperature well in excess of the upper critical point, or at least 1750 degrees F.

Steels in this group, being nearly pure iron or ferritic in structure, do not machine freely and should be avoided for cut screws and operations requiring broaching or smooth finish on turning. The machinability of bar, rod, and wire products is improved by cold drawing. Steels in this group are readily welded.

SAE 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1027, 1030:

Steels in this group, due to the carbon range covered, have increased strength and hardness, and reduced cold formability compared to the lowest carbon group. For heat-treating purposes, they are known as carburizing or case hardening grades. When uniform response to heat treatment is required, or for forgings, killed steel is preferred; for other uses, semi-killed or rimmed steel may be indicated, depending on the combination of properties desired. Rimmed steels can ordinarily be supplied up to 0.25 carbon.

Selection of one of these steels for carburizing applications depends on the nature of the part, the properties desired, and the processing practice preferred. Increases in carbon give greater core hardness with a given quench, or permit the use of thicker sections. Increases in manganese improve the hardenability of both the core and case; in carbon steels this is the only change in composition that will increase case hardenability. The higher manganese variants also machine much better. For carburizing applications, SAE 1016, 1018, and 1019 are widely used for thin sections or water-quenched parts. SAE 1022 and 1024 are used for heavier sections or where oil quenching is desired, and SAE 1024 is sometimes used for such parts as transmission and rear axle gears. SAE 1027 is used for parts given a light case to obtain satisfactory core properties without drastic quenching. SAE 1025 and 1030, although not usually regarded as carburizing types, are sometimes used in this manner for larger sections or where greater core hardness is needed.

For cold-formed or -headed parts, the lowest manganese grades (SAE 1017, 1020, and 1025) offer the best formability at their carbon level. SAE 1020 is used for fan blades and some frame members, and SAE 1020 and 1025 are widely used for low-strength bolts. The next higher manganese types (SAE 1018, 1021, and 1026) provide increased strength.

All steels listed may be readily welded or brazed by the common commercial methods. SAE 1020 is frequently used for welded tubing. These steels are used for numerous forged parts, the lower-carbon grades where high strength is not essential. Forgings from the lower-carbon steels usually machine better in the as-forged condition without annealing, or after normalizing.

SAE 1030, 1033, 1034, 1035, 1036, 1038, 1039, 1040, 1041, 1042, 1043, 1045, 1046, 1049, 1050, 1052: These steels, of the medium-carbon type, are selected for uses where higher mechanical properties are needed and are frequently further hardened and strengthened by heat treatment or by cold work. These grades are ordinarily produced as killed steels.

Steels in this group are suitable for a wide variety of automotive-type applications. The particular carbon and manganese level selected is affected by a number of factors. Increases in the mechanical properties required in section thickness, or in depth of hardening, ordinarily indicate either higher carbon or manganese or both. The heat-treating practice preferred, particularly the quenching medium, has a great effect on the steel selected. In general, any of the grades over 0.30 carbon may be selectively hardened by induction or flame methods.

Copyright 2004, Industrial Press, Inc., New York, NY

The lower-carbon and manganese steels in this group find usage for certain types of cold-formed parts. SAE 1030 is used for shift and brake levers. SAE 1034 and 1035 are used in the form of wire and rod for cold upsetting such as bolts, and SAE 1038 for bolts and studs. The parts cold-formed from these steels are usually heat-treated prior to use. Stampings are generally limited to flat parts or simple bends. The higher-carbon SAE 1038, 1040, and 1042 are frequently cold drawn to specified physical properties for use without heat treatment for some applications such as cylinder head studs.

Any of this group of steels may be used for forgings, the selection being governed by the section size and the physical properties desired after heat treatment. Thus, SAE 1030 and 1035 are used for shifter forks and many small forgings where moderate properties are desired, but the deeper-hardening SAE 1036 is used for more critical parts where a higher strength level and more uniformity are essential, such as some front suspension parts. Forgings such as connecting rods, steering arms, truck front axles, axle shafts, and tractor wheels are commonly made from the SAE 1038 to 1045 group. Larger forgings at similar strength levels need more carbon and perhaps more manganese. Examples are crankshafts made from SAE 1046 and 1052. These steels are also used for small forgings where high hardness after oil quenching is desired. Suitable heat treatment is necessary on forgings from this group to provide machinability. These steels are also widely used for parts machined from bar stock, the selection following an identical pattern to that described for forgings. They are used both with and without heat treatment, depending on the application and the level of properties needed. As a class, they are considered good for normal machining operations. It is also possible to weld these steels by most commercial methods, but precautions should be taken to avoid cracking from too rapid cooling.

SAE 1055, 1060, 1062, 1064, 1065, 1066, 1070, 1074, 1078, 1080, 1085, 1086, 1090, 1095: Steels in this group are of the high-carbon type, having more carbon than is required to achieve maximum as quenched hardness. They are used for applications where the higher carbon is needed to improve wear characteristics for cutting edges, to make springs, and for special purposes. Selection of a particular grade is affected by the nature of the part, its end use, and the manufacturing methods available.

In general, cold-forming methods are not practical on this group of steels, being limited to flat stampings and springs coiled from small-diameter wire. Practically all parts from these steels are heat treated before use, with some variations in heat-treating methods to obtain optimum properties for the particular use to which the steel is to be put.

Uses in the spring industry include SAE 1065 for pretempered wire and SAE 1066 for cushion springs of hard-drawn wire, SAE 1064 may be used for small washers and thin stamped parts, SAE 1074 for light flat springs formed from annealed stock, and SAE 1080 and 1085 for thicker flat springs. SAE 1085 is also used for heavier coil springs. Valve spring wire and music wire are special products.

Due to good wear properties when properly heat-treated, the high-carbon steels find wide usage in the farm implement industry. SAE 1070 has been used for plow beams, SAE 1074 for plow shares, and SAE 1078 for such parts as rake teeth, scrapers, cultivator shovels, and plow shares. SAE 1085 has been used for scraper blades, disks, and for spring tooth harrows. SAE 1086 and 1090 find use as mower and binder sections, twine holders, and knotter disks.

SAE 1111, 1112, 1113: This class of steels is intended for those uses where easy machining is the primary requirement. They are characterized by a higher sulfur content than comparable carbon steels. This composition results in some sacrifice of cold-forming properties, weldability, and forging characteristics. In general, the uses are similar to those for carbon steels of similar carbon and manganese content.

These steels are commonly known as Bessemer screw stock, and are considered the best machining steels available, machinability improving within the group as sulfur increases. They are used for a wide variety of machined parts. Although of excellent strength in the

Copyright 2004, Industrial Press, Inc., New York, NY

cold-drawn condition, they have an unfavorable property of cold shortness and are not commonly used for vital parts. These steels may be cyanided or carburized, but when uniform response to heat-treating is necessary, open-hearth steels are recommended.

SAE 1109, 1114, 1115, 1116, 1117, 1118, 1119, 1120, 1126: Steels in this group are used where a combination of good machinability and more uniform response to heat treatment is needed. The lower-carbon varieties are used for small parts that are to be cyanided or carbonitrided. SAE 1116, 1117, 1118, and 1119 carry more manganese for better hardenability, permitting oil quenching after case-hardening heat treatments in many instances. The higher-carbon SAE 1120 and 1126 provide more core hardness when this is needed.

SAE 1132, 1137, 1138, 1140, 1141, 1144, 1145, 1146, 1151: This group of steels has characteristics comparable to carbon steels of the same carbon level, except for changes due to higher sulfur as noted previously. They are widely used for parts where large amounts of machining are necessary, or where threads, splines, or other contours present special problems with tooling. SAE 1137, for example, is widely used for nuts and bolts and studs with machined threads. The higher-manganese SAE 1132, 1137, 1141, and 1144 offer greater hardenability, the higher-carbon types being suitable for oil quenching for many parts. All these steels may be selectively hardened by induction or flame heating if desired.

Carburizing Grades of Alloy Steels.— *Properties of the Case:* The properties of carburized and hardened cases (surface layers) depend on the carbon and alloy content, the structure of the case, and the degree and distribution of residual stresses. The carbon content of the case depends on the details of the carburizing process, and the response of iron and the alloying elements present, to carburization. The original carbon content of the steel has little or no effect on the carbon content produced in the case. The hardenability of the case, therefore, depends on the alloy content of the steel and the final carbon content produced by carburizing, but not on the initial carbon content of the steel.

With complete carbide solution, the effect of alloying elements on the hardenability of the case is about the same as the effect of these elements on the hardenability of the core. As an exception to this statement, any element that inhibits carburizing may reduce the hardenability of the case. Some elements that raise the hardenability of the core may tend to produce more retained austenite and consequently somewhat lower hardness in the case.

Alloy steels are frequently used for case hardening because the required surface hardness can be obtained by moderate speeds of quenching. Slower quenching may mean less distortion than would be encountered with water quenching. It is usually desirable to select a steel that will attain a minimum surface hardness of 58 or 60 Rockwell C after carburizing and oil quenching. Where section sizes are large, a high-hardenability alloy steel may be necessary, whereas for medium and light sections, low-hardenability steels will suffice.

In general, the case-hardening alloy steels may be divided into two classes as far as the hardenability of the case is concerned. Only the general type of steel (SAE 3300–4100, etc.) is discussed. The original carbon content of the steel has no effect on the carbon content of the case, so the last two digits in the specification numbers are not meaningful as far as the case is concerned.

a) High-Hardenability Case: SAE 2500, 3300, 4300, 4800, 9300

As these are high-alloy steels, both the case and the core have high hardenability. They are used particularly for carburized parts having thick sections, such as bevel drive pinions and heavy gears. Good case properties can be obtained by oil quenching. These steels are likely to have retained austenite in the case after carburizing and quenching; consequently, special precautions or treatments, such as refrigeration, may be required.

b) Medium-Hardenability Case: SAE 1300, 2300, 4000, 4100, 4600, 5100, 8600, 8700

Carburized cases of these steels have medium hardenability, which means that their hardenability is intermediate between that of plain carbon steel and the higher-alloy car-

Copyright 2004, Industrial Press, Inc., New York, NY

burizing steels discussed earlier. In general, these steels can be used for average-size case-hardened automotive parts such as gears, pinions, piston pins, ball studs, universal joint crosses, crankshafts, etc. Satisfactory case hardness is usually produced by oil quenching.

Core Properties: The core properties of case-hardened steels depend on both carbon and alloy content of the steel. Each of the general types of alloy case-hardening steel is usually made with two or more carbon contents to permit different hardenability in the core.

The most desirable hardness for the core depends on the design and functioning of the individual part. In general, where high compressive loads are encountered, relatively high core hardness is beneficial in supporting the case. Low core hardnesses may be desirable where great toughness is essential.

The case-hardening steels may be divided into three general classes, depending on hardenability of the core.

a) Low-Hardenability Core: SAE 4017, 4023, 4024, 4027,* 4028,* 4608, 4615, 4617,* 8615,* 8617*

b) Medium-Hardenability Core: SAE 1320, 2317, 2512, 2515,* 3115, 3120, 4032, 4119, 4317, 4620, 4621, 4812, 4815,* 5115, 5120, 8620, 8622, 8720, 9420

c) High-Hardenability Core: SAE 2517, 3310, 3316, 4320, 4817, 4820, 9310, 9315, 9317

Heat Treatments: In general, all the alloy carburizing steels are made with fine grain and most are suitable for direct quenching from the carburizing temperature. Several other types of heat treatment involving single and double quenching are also used for most of these steels. (See on page 532 and on page 533)

Directly Hardenable Grades of Alloy Steels.— These steels may be considered in five groups on the basis of approximate mean carbon content of the SAE specification. In general, the last two figures of the specification agree with the mean carbon content. Consequently the heading "0.30–0.37 Mean Carbon Content of SAE Specification" includes steels such as SAE 1330, 3135, and 4137.

It is necessary to deviate from the above plan in the classification of the carbon molybdenum steels. When carbon molybdenum steels are used, it is customary to specify higher carbon content for any given application than would be specified for other alloy steels, due to the low alloy content of these steels. For example, SAE 4063 is used for the same applications as SAE 4140, 4145, and 5150. Consequently, in the following discussion, the carbon molybdenum steels have been shown in the groups where they belong on the basis of applications rather than carbon content.

Mean Carbon Content of SAE Specification	Common Applications
(a) 0.30–0.37 per cent	Heat-treated parts requiring moderate strength and great toughness.
(b) 0.40–0.42 per cent	Heat-treated parts requiring higher strength and good toughness.
(c) 0.45–0.50 per cent	Heat-treated parts requiring fairly high hardness and strength with moderate toughness.
(d) 0.50–0.62 per cent	Springs and hand tools.
(e) 1.02 per cent	Ball and roller bearings.

For the present discussion, steels of each carbon content are divided into two or three groups on the basis of hardenability. Transformation ranges and consequently heat-treating practices vary somewhat with different alloying elements even though the hardenability is not changed.

0.30–0.37 Mean Carbon Content of SAE Specification: These steels are frequently used for water-quenched parts of moderate section size and for oil-quenched parts of small section size. Typical applications of these steels are connecting rods, steering arms and steering knuckles, axle shafts, bolts, studs, screws, and other parts requiring strength and

* Borderline classifications might be considered in the next higher hardenability group.

Copyright 2004, Industrial Press, Inc., New York, NY

toughness where section size is small enough to permit the desired physical properties to be obtained with the customary heat treatment.

Steels falling in this classification may be subdivided into two groups on the basis of hardenability:

a) Low Hardenability: SAE 1330, 1335, 4037, 4042, 4130, 5130, 5132, 8630

b) Medium Hardenability: SAE 2330, 3130, 3135, 4137, 5135, 8632, 8635, 8637, 8735, 9437

0.40–0.42 Mean Carbon Content of SAE Specification: In general, these steels are used for medium and large size parts requiring high degree of strength and toughness. The choice of the proper steel depends on the section size and the mechanical properties that must be produced. The low and medium hardenabilty steels are used for average size automotive parts such as steering knuckles, axle shafts, propeller shafts, etc. The high hardenability steels are used particularly for large axles and shafts for large aircraft parts.

These steels are usually considered as oil quenching steels, although some large parts made of the low and medium hardenability classifications may be quenched in water under properly controlled conditions.

These steels may be divided into three groups on the basis of hardenability:

a) Low Hardenability: SAE 1340, 4047, 5140, 9440

b) Medium Hardenability: SAE 2340, 3140, 3141, 4053, 4063, 4140, 4640, 8640, 8641, 8642, 8740, 8742, 9442

c) High Hardenability: SAE 4340, 9840

0.45–0.50 Mean Carbon Content of SAE Specification: These steels are used primarily for gears and other parts requiring fairly high hardness as well as strength and toughness. Such parts are usually oil-quenched and a minimum of 90 per cent martensite in the as-quenched condition is desirable.

a) Low Hardenability: SAE 5045, 5046, 5145, 9747, 9763

b) Medium Hardenability: SAE 2345, 3145, 3150, 4145, 5147, 5150, 8645, 8647, 8650, 8745, 8747, 8750, 9445, 9845

c) High Hardenability: SAE 4150, 9850

0.50–0.63 Mean Carbon Content of SAE Specification: These steels are used primarily for springs and hand tools. The hardenability necessary depends on the thickness of the material and the quenching practice.

a) Medium hardenability: SAE 4068, 5150, 5152, 6150, 8650, 9254, 9255, 9260, 9261

b) High Hardenability: SAE 8653, 8655, 8660, 9262

1.02 Mean Carbon Content of SAE Specification—SAE 50100, 51100, 52100: These straight chromium electric furnace steels are used primarily for the races and balls or rollers of antifriction bearings. They are also used for other parts requiring high hardness and wear resistance. The compositions of the three steels are identical, except for a variation in chromium, with a corresponding variation in hardenability.

a) Low Hardenability: SAE 50100

b) Medium Hardenability: SAE 51100, 52100

Resulfurized Steel: Some of the alloy steels, SAE 4024, 4028, and 8641, are made resulfurized so as to give better machinability at a relatively high hardness. In general, increased sulfur results in decreased transverse ductility, notched impact toughness, and weldability.

Characteristics and Typical Applications of Standard Stainless Steels.— Typical applications of various stainless steel alloys are given in the following. The first number given is the AISI designation followed by the UNS number in parenthesis. (See also *Numbering Systems for Metals and Alloys* on page 440)

201 (S20100): High work-hardening rate; low-nickel equivalent of type 301. Flatware; automobile wheel covers, trim.

Copyright 2004, Industrial Press, Inc., New York, NY

202 (S20200): General-purpose low-nickel equivalent of type 302. Kitchen equipment; hub caps; milk handling.

205 (S20500): Lower work-hardening rate than type 202; used for spinning and special drawing operations. Nonmagnetic and cryogenic parts.

301 (S30100): High work-hardening rate; used for structural applications where high strength plus high ductility are required. Railroad cars; trailer bodies; aircraft structurals; fasteners; automobile wheel covers, trim; pole line hardware.

302 (S30200): General-purpose austenitic stainless steel. Trim; food-handling equipment; aircraft cowlings; antennas; springs; cookware; building exteriors; tanks; hospital, household appliances; jewelry; oil refining equipment; signs.

302B (S30215): More resistant to scale than type 302. Furnace parts; still liners; heating elements; annealing covers; burner sections.

303 (S30300): Free-machining modification of type 302, for heavier cuts. Screw machine products; shafts; valves; bolts; bushings; nuts.

303Se (S30323): Free-machining modification of type 302, for lighter cuts; used where hot working or cold heading may be involved. Aircraft fittings; bolts; nuts; rivets; screws; studs.

304 (S30400): Low-carbon modification of type 302 for restriction of carbide precipitation during welding. Chemical and food processing equipment; brewing equipment; cryogenic vessels; gutters; downspouts; flashings.

304L (S30403): Extra-low-carbon modification of type 304 for further restriction of carbide precipitation during welding. Coal hopper linings; tanks for liquid fertilizer and tomato paste.

304Cu (S30430): Lower work-hardening rate than type 304. Severe cold-heading applications.

304N (S30451): Higher nitrogen than type 304 to increase strength with minimum effect on ductility and corrosion resistance, more resistant to increased magnetic permeability. Type 304 applications requiring higher strength.

305 (S30500): Low work-hardening rate; used for spin forming, severe drawing, cold heading, and forming. Coffee urn tops; mixing bowls; reflectors.

308 (S30800): Higher-alloy steel having high corrosion and heat resistance. Welding filler metals to compensate for alloy loss in welding; industrial furnaces.

309 (S30900): High-temperature strength and scale resistance. Aircraft heaters; heat-treating equipment; annealing covers; furnace parts; heat exchangers; heat-treating trays; oven linings; pump parts.

309S (S30908): Low-carbon modification of type 309. Welded constructions; assemblies subject to moist corrosion conditions.

310 (S31000): Higher elevated temperature strength and scale resistance than type 309. Heat exchangers; furnace parts; combustion chambers; welding filler metals; gas-turbine parts; incinerators; recuperators; rolls for roller hearth furnaces.

310S (S31008): Low-carbon modification of type 310. Welded constructions; jet engine rings.

314 (S31400): More resistant to scale than type 310. Severe cold-heading or -forming applications. Annealing and carburizing boxes; heat-treating fixtures; radiant tubes.

316 (S31600): Higher corrosion resistance than types 302 and 304; high creep strength. Chemical and pulp handling equipment; photographic equipment; brandy vats; fertilizer parts; ketchup cooking kettles; yeast tubs.

316L (S31603): Extra-low-carbon modification of type 316. Welded construction where intergranular carbide precipitation must be avoided. Type 316 applications requiring extensive welding.

316F (S31620): Higher phosphorus and sulfur than type 316 to improve machining and nonseizing characteristics. Automatic screw machine parts.

316N (S31651): Higher nitrogen than type 316 to increase strength with minimum effect on ductility and corrosion resistance. Type 316 applications requiring extra strength.

Copyright 2004, Industrial Press, Inc., New York, NY

317 (S31700): Higher corrosion and creep resistance than type 316. Dyeing and ink manufacturing equipment.

317L (S31703): Extra-low-carbon modification of type 317 for restriction of carbide precipitation during welding. Welded assemblies.

321 (S32100): Stabilized for weldments subject to severe corrosive conditions, and for service from 800 to 1650°F Aircraft exhaust manifolds; boiler shells; process equipment; expansion joints; cabin heaters; fire walls; flexible couplings; pressure vessels.

329 (S32900): Austenitic-ferritic type with general corrosion resistance similar to type 316 but with better resistance to stress-corrosion cracking; capable of age hardening. Valves; valve fittings; piping; pump parts.

330 (N08330): Good resistance to carburization and oxidation and to thermal shock. Heat-treating fixtures.

347 (S34700): Similar to type 321 with higher creep strength. Airplane exhaust stacks; welded tank cars for chemicals; jet engine parts.

348 (S34800): Similar to type 321; low retentivity. Tubes and pipes for radioactive systems; nuclear energy uses.

384 (S38400): Suitable for severe cold heading or cold forming; lower cold-work-hardening rate than type 305. Bolts; rivets; screws; instrument parts.

403 (S40300): "Turbine quality" grade. Steam turbine blading and other highly stressed parts including jet engine rings.

405 (S40500): Nonhardenable grade for assemblies where air-hardening types such as 410 or 403 are objectionable. Annealing boxes; quenching racks; oxidation-resistant partitions.

409 (S40900): General-purpose construction stainless. Automotive exhaust systems; transformer and capacitor cases; dry fertilizer spreaders; tanks for agricultural sprays.

410 (S41000): General-purpose heat-treatable type. Machine parts; pump shafts; bolts; bushings; coal chutes; cutlery; hardware; jet engine parts; mining machinery; rifle barrels; screws; valves.

414 (41400): High hardenability steel. Springs; tempered rules; machine parts, bolts; mining machinery; scissors; ships' bells; spindles; valve seats.

416 (S41600): Free-machining modification of type 410, for heavier cuts. Aircraft fittings; bolts; nuts; fire extinguisher inserts; rivets; screws.

416Se (S41623): Free-machining modification of type 410, for lighter cuts. Machined parts requiring hot working or cold heading.

420 (S42000): Highercarbon modification of type 410. Cutlery; surgical instruments; valves; wear-resisting parts; glass molds; hand tools; vegetable choppers.

420F (S42020): Free-machining modification of type 420. Applications similar to those for type 420 requiring better machinability.

422 (S42200): High strength and toughness at service temperatures up to 1200 degrees F. Steam turbine blades; fasteners.

429 (S42900): Improved weldability as compared to type 430. Nitric acid and nitrogen-fixation equipment.

430 (S43000): General-purpose nonhardenable chromium type. Decorative trim; nitric acid tanks; annealing baskets; combustion chambers; dishwashers; heaters; mufflers; range hoods; recuperators; restaurant equipment.

430F (S43020): Free-machining modification of type 430, for heavier cuts. Screw machine parts.

430FSe (S43023): Free-machining modification of type 430, for lighter cuts. Machined parts requiring light cold heading or forming.

431 (S43100): Special-purpose hardenable steel used where particularly high mechanical properties are required. Aircraft fittings; beater bars; paper machinery; bolts.

434 (S43400): Modification of type 430 designed to resist atmospheric corrosion in the presence of winter road conditioning and dust-laying compounds. Automotive trim and fasteners.

Copyright 2004, Industrial Press, Inc., New York, NY

436 (S43600): Similar to types 430 and 434. Used where low "roping" or "ridging" required. General corrosion and heat-resistant applications such as automobile trim.

440A (S44002): Hardenable to higher hardeness than type 420 with good corrosion resistance. Cutlery; bearings; surgical tools.

440B (S44003): Cutlery grade. Cutlery, valve parts; instrument bearings.

440C (S44004): Yields highest hardnesses of hardenable stainless steels. Balls; bearings; races; nozzles; balls and seats for oil well pumps; valve parts.

442 (S44200): High-chromium steel, principally for parts that must resist high service temperatures without scaling. Furnace parts; nozzles; combustion chambers.

446 (S44600): High-resistance to corrosion and scaling at high temperatures, especially for intermittent service; often used in sulfur-bearing atmosphere. Annealing boxes; combustion chambers; glass molds; heaters; pyrometer tubes; recuperators; stirring rods; valves.

501 (S50100): Heat resistance; good mechanical properties at moderately elevated temperatures. Heat exchangers; petroleum refining equipment.

502 (S50200): More ductility and less strength than type 501. Heat exchangers; petroleum refining equipment; gaskets.

Chromium-Nickel Austenitic Steels (Not capable of heat treatment)**.—** *SAE 30201:*

This steel is an austenitic chromium–nickel–manganese stainless steel usually required in flat products. In the annealed condition, it exhibits higher strength values than the corresponding chromium–nickel stainless steel (SAE 30301). It is nonmagnetic in the annealed condition, but may be magnetic when cold-worked. SAE 30201 is used to obtain high strength by work-hardening and is well suited for corrosion-resistant structural members requiring high strength with low weight. It has excellent resistance to a wide variety of corrosive media, showing behavior comparable to stainless grade SAE 30301. It has high ductility and excellent forming properties. Owing to this steel's work-hardening rate and yield strength, tools for forming must be designed to allow for a higher springback or recovery rate. It is used for automotive trim, automotive wheel covers, railroad passenger car bodies and structural members, and truck trailer bodies.

SAE 30202: Like chromium–nickel stainless steel SAE 30302, this is a general-purpose stainless steel. It has excellent corrosion resistance and deep drawing qualities. It is nonhardenable by thermal treatments, but may be cold worked to high tensile strengths. In the annealed condition, it is nonmagnetic but slightly magnetic when cold-worked. Applications for this stainless steel are hub cap, railcar and truck trailer bodies, and spring wire.

SAE 30301: Capable of attaining high tensile strength and ductility by moderate or severe cold working. It is used largely in the cold-rolled or cold-drawn condition in the form of sheet, strip, and wire. Its corrosion resistance is good but not equal to SAE 30302.

SAE 30302: The most widely used of the general-purpose austenitic chromium–nickel stainless steels. It is used for deep drawing largely in the annealed condition. It can be worked to high tensile strengths but with slightly lower ductility than SAE 30301.

SAE 30303F: A free-machining steel recommended for the manufacture of parts produced on automatic screw machines. Caution must be used in forging this steel.

SAE 30304: Similar to SAE 30302 but somewhat superior in corrosion resistance and having superior welding properties for certain types of equipment.

SAE 30305: Similar to SAE 30304 but capable of lower hardness. Has greater ductility with slower work-hardening tendency.

SAE 30309: A steel with high heat-resisting qualities which is resistant to oxidation at temperatures up to about 1800 degrees F.

SAE 30310: This steel has the highest heat-resisting properties of the chromium nickel steels listed here and will resist oxidation at temperatures up to about 1900 degrees F.

Copyright 2004, Industrial Press, Inc., New York, NY

SAE 30316: Recommended for use in parts where unusual resistance to chemical or salt water corrosion is necessary. It has superior creep strength at elevated temperatures.

SAE 30317: Similar to SAE 30316 but has the highest corrosion resistance of all these alloys in many environments.

SAE 30321: Recommended for use in the manufacture of welded structures where heat treatment after welding is not feasible. It is also recommended for use where temperatures up to 1600 degrees F are encountered in service.

SAE 30325: Used for such parts as heat control shafts.

SAE 30347: This steel is similar to SAE 30321. This niobium alloy is sometimes preferred to titanium because niobium is less likely to be lost in welding operations.

Stainless Chromium Irons and Steels.— *SAE 51409:* An 11 per cent chromium alloy developed, especially for automotive mufflers and tailpipes. Resistance to corrosion and oxidation is very similar to SAE 51410. It is nonhardenable and has good forming and welding characteristics. This alloy is recommended for mildly corrosive applications where surface appearance is not critical.

SAE 51410: A general-purpose stainless steel capable of heat treatment to show good physical properties. It is used for general stainless applications, both in the heat-treated and annealed condition but is not as resistant to corrosion as SAE 51430 in either the annealed or heat-treated condition.

SAE 51414: A corrosion and heat-resisting nickel-bearing chromium steel with somewhat better corrosion resistance than SAE 51410. It will attain slightly higher mechanical properties when heat-treated than SAE 51410. It is used in the form of tempered strip or wire, and in bars and forgings for heat-treated parts.

SAE 51416F: A free-machining grade for the manufacture of parts produced in automatic screw machines.

SAE 51420: This steel heat-treatable to a relatively high hardness. It will harden to a maximum of approximately 500 Brinell. Maximum corrosion resisting qualities exist only in the fully hardened condition. It is used for cutlery, hardened pump shafts, etc.

SAE 51420F: This is similar to SAE 51420 except for its free-machining properties.

SAE 51430: This high-chromium steel is not capable of heat treatment and is recommended for use in shallow parts requiring moderate draw. Corrosion and heat resistance are superior to SAE 51410.

SAE 51430F: This steel is similar to SAE 51430 except for its free-machining properties.

SAE 51431: This nickel-bearing chromium steel is designed for heat treatment to high mechanical properties. Its corrosion resistance is superior to other hardenable steels.

SAE 51440A: A hardenable chromium steel with greater quenched hardness than SAE 51420 and greater toughness than SAE 51440B and 51440C. Maximum corrosion resistance is obtained in the fully hardened and polished condition.

SAE 51440B: A hardenable chromium steel with greater quenched hardness than SAE 51440A. Maximum corrosion resistance is obtained in the fully hardened and polished condition. Capable of hardening to 50–60 Rockwell C depending on carbon content.

SAE 51440C: This steel has the greatest quenched hardness and wear resistance on heat treatment of any corrosion- or heat-resistant steel.

SAE 51440F: The same as SAE 51440C, except for its free-machining characteristics.

SAE 51442: A corrosion- and heat-resisting chromium steel with corrosion-resisting properties slightly better than SAE 51430 and with good scale resistance up to 1600 degrees F.

SAE 51446: A corrosion- and heat-resisting steel with maximum amount of chromium consistent with commercial malleability. Used principally for parts that must resist high temperatures in service without scaling. Resists oxidation up to 2000 degrees F.

SAE 51501: Used for its heat and corrosion resistance and good mechanical properties at temperatures up to approximately 1000 degrees F.

Copyright 2004, Industrial Press, Inc., New York, NY

High-Strength, Low-Alloy Steels.— High-strength, low-alloy (HSLA) steel represents a specific group of steels in which enhanced mechanical properties and, sometimes, resistance to atmospheric corrosion are obtained by the addition of moderate amounts of one or more alloying elements other than carbon. Different types are available, some of which are carbon–manganese steels and others contain further alloy additions, governed by special requirements for weldability, formability, toughness, strength, and economics. These steels may be obtained in the form of sheet, strip, plates, structural shapes, bars, and bar size sections.

HSLA steels are especially characterized by their mechanical properties, obtained in the as-rolled condition. They are not intended for quenching and tempering. For certain applications, they are sometimes annealed, normalized, or stress relieved with some influence on mechanical properties.

Where these steels are used for fabrication by welding, care must be exercised in selection of grade and in the details of the welding process. Certain grades may be welded without preheat or postheat.

Because of their high strength-to-weight ratio, abrasion resistance, and, in certain compositions, improved atmospheric corrosion resistance, these steels are adapted particularly for use in mobile equipment and other structures where substantial weight savings are generally desirable. Typical applications are truck bodies, frames, structural members, scrapers, truck wheels, cranes, shovels, booms, chutes, and conveyors.

Grade 942X: A niobium- or vanadium-treated carbon–manganese high-strength steel similar to 945X and 945C except for somewhat improved welding and forming properties.

Grade 945A: A HSLA steel with excellent welding characteristics, both arc and resistance, and the best formability, weldability, and low-temperature notch toughness of the high-strength steels. It is generally used in sheets, strip, and light plate thicknesses.

Grade 945C: A carbon–manganese high-strength steel with satisfactory arc welding properties if adequate precautions are observed. It is similar to grade 950C, except that lower carbon and manganese improve arc welding characteristics, formability, and low-temperature notch toughness at some sacrifice in strength.

Grade 945X: A niobium- or vanadium-treated carbon–manganese high-strength steel similar to 945C, except for somewhat improved welding and forming properties.

Grade 950A: A HSLA steel with good weldability, both arc and resistance, with good low-temperature notch toughness, and good formability. It is generally used in sheet, strip, and light plate thicknesses.

Grade 950B: A HSLA steel with satisfactory arc welding properties and fairly good low-temperature notch toughness and formability.

Grade 950C: A carbon–manganese high-strength steel that can be arc welded with special precautions, but is unsuitable for resistance welding. The formability and toughness are fair.

Grade 950D: A HSLA steel with good weldability, both arc and resistance, and fairly good formability. Where low-temperature properties are important, the effect of phosphorus in conjunction with other elements present should be considered.

Grade 950X: A niobium- or vanadium-treated carbon–manganese high-strength steel similar to 950C, except for somewhat improved welding and forming properties.

Grades 955X, 960X, 965X, 970X, 980X: These are steels similar to 945X and 950X with higher strength obtained by increased amounts of strengthening elements, such as carbon or manganese, or by the addition of nitrogen up to about 0.015 per cent. This increased strength involves reduced formability and usually decreased weldability. Toughness will vary considerably with composition and mill practice.

The formability, composition, and minimum mechanical properties of the HSLA steel grades are shown in Tables 7 through Table 9 on page 463.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. HSLA Steel Grades in Approximate Order of Increasing Excellence

Weldability	Formability	Toughness
980X	980X	980X
970X	970X	970X
965X	965X	965X
960X	960X	960X
955X, 950C, 942X	955X	955X
945C	950C	945C, 950C, 942X
950B, 950X	950D	945X, 950X
945X	950B, 950X, 942X	950D
950D	945C, 945X	950B
950A	950A	950A
945A	945A	945A

Source: SAE Handbook, 1990. Reprinted with permission. Copyright © 1990. Society of Automotive Engineers, Inc. All rights reserved.

Table 8. Chemical Composition Ladle Analysis of HSLA Steels (max. per cent)

Grade	C	Mn	P	Grade	C	Mn	P
942X	0.21	1.35	0.04	950D	0.15	1.00	0.15
945A	0.15	1.00	0.04	950X	0.23	1.35	0.04
945C	0.23	1.40	0.04	955X	0.25	1.35	0.04
945X	0.22	1.35	0.04	960X	0.26	1.45	0.04
950A	0.15	1.30	0.04	965X	0.26	1.45	0.04
950B	0.22	1.30	0.04	970X	0.26	1.65	0.04
950C	0.25	1.60	0.04	980X	0.26	1.65	0.04

Sulfur, 0.05 per cent max; silicon, 0.90 per cent max.

Source: SAE Handbook, 1990. Reprinted with permission. Copyright © 1990. Society of Automotive Engineers, Inc. All rights reserved.

Table 9. Minimum Mechanical Properties of High-strength Low-alloy Steels

		Strength[a] (psi)		% Elongation				Strength[a] (psi)		% Elongation	
Grade	Form	Yield	Tensile	2 in.	8 in.	Grade	Form	Yield	Tensile	2 in.	8 in.
942X	Plates, shapes, bars to 4 in. incl.	42,000	60,000	24	20	955X	Sheet and strip	55,000	70,000	20	…
945A, C	Sheet and strip	45,000	60,000	22	…		Plates, shapes, bars				
	Plates, shapes, bars						To 1½ in. incl.	55,000	70,000	…	17
	To ½ in. incl.	45,000	65,000	22	18	960X	Sheet and strip	60,000	75,000	18	…
	½–1½ in. incl.	42,000	62,000	24	19		Plates, shapes, bars				
	1½–3 in. incl.	40,000	62,000	24	19		To 1½ in. incl.	60,000	75,000	…	16
945X	Sheet and strip	45,000	60,000	25	…	965X	Sheet and strip	65,000	80,000	16	…
	Plates, shapes, bars						Plates, shapes, bars				
	To 1½ in. incl.	45,000	60,000	22	19		To ¾ in. incl.	65,000	80,000	…	15
950A, B, C, D	Sheet and strip	50,000	70,000	22	…	970X	Sheet and strip	70,000	85,000	14	…
	Plates, shapes, bars						Plates, shapes, bars				
	To ½ in. incl.	50,000	70,000	22	18		To ¾ in. incl.	70,000	85,000	…	14
	½–1½ in. incl.	45,000	67,000	24	19	980X	Sheet and strip	80,000	95,000	12	…
	1½–3 in. incl.	42,000	63,000	24	19		Plates to ⅜ in. incl.	80,000	95,000	…	10
950X	Sheet and strip	50,000	65,000	22	…						
	Plates, shapes, bars										
	To 1½ in. incl.	50,000	65,000	…	18						

[a] Yield strength to be measured at 0.2 per cent offset. Mechanical properties to be determined in accordance with ASTM A 370.

Source: SAE Handbook, 1990. Reprinted with permission. Copyright © 1990. Society of Automotive Engineers, Inc. All rights reserved.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Mechanical Properties of Steel.— Tables 10 through 13 provide expected minimum and/or typical mechanical properties of selected standard carbon and alloy steels and stainless steels.

Table 10. Expected Minimum Mechanical Properties of Cold-Drawn Carbon-Steel Rounds, Squares, and Hexagons

Size, in.	As Cold-Drawn					Cold-Drawn Followed by Low-Temperature Stress Relief					Cold-Drawn Followed by High-Temperature Stress Relief				
	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn
	Tensile	Yield				Tensile	Yield				Tensile	Yield			
	1000 lb/in.^{2}					1000 lb/in^2					1000 lb/in^2				
AISI 1018 and 1025 Steels															
$\frac{5}{8}$–$\frac{7}{8}$	70	60	18	40	143	....	....	....	....	…	65	45	20	45	131
Over $\frac{7}{8}$–1$\frac{1}{4}$	65	55	16	40	131	....	....	....	....	…	60	45	20	45	121
Over 1$\frac{1}{4}$–2	60	50	15	35	121	....	....	....	....	…	55	45	16	40	111
Over 2–3	55	45	15	35	111	....	....	....	....	…	50	40	15	40	101
AISI 1117 and 1118 Steels															
$\frac{5}{8}$–$\frac{7}{8}$	75	65	15	40	149	80	70	15	40	163	70	50	18	45	143
Over $\frac{7}{8}$–1$\frac{1}{4}$	70	60	15	40	143	75	65	15	40	149	65	50	16	45	131
Over 1$\frac{1}{4}$–2	65	55	13	35	131	70	60	13	35	143	60	50	15	40	121
Over 2–3	60	50	12	30	121	65	55	12	35	131	55	45	15	40	111
AISI 1035 Steel															
$\frac{5}{8}$–$\frac{7}{8}$	85	75	13	35	170	90	80	13	35	179	80	60	16	45	163
Over $\frac{7}{8}$–1$\frac{1}{4}$	80	70	12	35	163	85	75	12	35	170	75	60	15	45	149
Over 1$\frac{1}{4}$–2	75	65	12	35	149	80	70	12	35	163	70	60	15	40	143
Over 2–3	70	60	10	30	143	75	65	10	30	149	65	55	12	35	131
AISI 1040 and 1140 Steels															
$\frac{5}{8}$–$\frac{7}{8}$	90	80	12	35	179	95	85	12	35	187	85	65	15	45	170
Over $\frac{7}{8}$–1$\frac{1}{4}$	85	75	12	35	170	90	80	12	35	179	80	65	15	45	163
Over 1$\frac{1}{4}$–2	80	70	10	30	163	85	75	10	30	170	75	60	15	40	149
Over 2–3	75	65	10	30	149	80	70	10	30	163	70	55	12	35	143

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **Expected Minimum Mechanical Properties of Cold-Drawn Carbon-Steel Rounds, Squares, and Hexagons**

Size, in.	As Cold-Drawn					Cold-Drawn Followed by Low-Temperature Stress Relief					Cold-Drawn Followed by High-Temperature Stress Relief				
	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn	Strength		Elongation in 2 in., Per cent	Reduction in Area, Per cent	Hardness, Bhn
	Tensile	Yield				Tensile	Yield				Tensile	Yield			
	1000 lb/in.^{2}					1000 lb/in^2					1000 lb/in^2				
AISI 1045, 1145, and 1146 Steels															
$\frac{5}{8}$–$\frac{7}{8}$	95	85	12	35	187	100	90	12	35	197	90	70	15	45	179
Over $\frac{7}{8}$–1$\frac{1}{4}$	90	80	11	30	179	95	85	11	30	187	85	70	15	45	170
Over 1$\frac{1}{4}$–2	85	75	10	30	170	90	80	10	30	179	80	65	15	40	163
Over 2–3	80	70	10	30	163	85	75	10	25	170	75	60	12	35	149
AISI 1050, 1137, and 1151 Steels															
$\frac{5}{8}$–$\frac{7}{8}$	100	90	11	35	197	105	95	11	35	212	95	75	15	45	187
Over $\frac{7}{8}$–1$\frac{1}{4}$	95	85	11	30	187	100	90	11	30	197	90	75	15	40	179
Over 1$\frac{1}{4}$–2	90	80	10	30	179	95	85	10	30	187	85	70	15	40	170
Over 2–3	85	75	10	30	170	90	80	10	25	179	80	65	12	35	163
AISI 1141 Steel															
$\frac{5}{8}$–$\frac{7}{8}$	105	95	11	30	212	110	100	11	30	223	100	80	15	40	197
Over $\frac{7}{8}$–1$\frac{1}{4}$	100	90	10	30	197	105	95	10	30	212	95	80	15	40	187
Over 1$\frac{1}{4}$–2	95	85	10	30	187	100	90	10	25	197	90	75	15	40	179
Over 2–3	90	80	10	20	179	95	85	10	20	187	85	70	12	30	170
AISI 1144 Steel															
$\frac{5}{8}$–$\frac{7}{8}$	110	100	10	30	223	115	105	10	30	229	105	85	15	40	212
Over $\frac{7}{8}$–1$\frac{1}{4}$	105	95	10	30	212	110	100	10	30	223	100	85	15	40	197
Over 1$\frac{1}{4}$–2	100	90	10	25	197	105	95	10	25	212	95	80	15	35	187
Over 2–3	95	85	10	20	187	100	90	10	20	197	90	75	12	30	179

Source: AISI Committee of Hot-Rolled and Cold-Finished Bar Producers and published in 1974 DATABOOK issue of the American Society for Metals' *METAL PROGRESS* magazine and used with its permission.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11a. Typical Mechanical Properties of Selected Carbon and Alloy Steels (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Treatment	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn	Impact Strength (Izod), ft-lb
		Tensile	Yield				
		lb/in.[2]					
1015	As-rolled	61,000	45,500	39.0	61.0	126	81.5
	Normalized (1700 F)	61,500	47,000	37.0	69.6	121	85.2
	Annealed (1600 F)	56,000	41,250	37.0	69.7	111	84.8
1020	As-rolled	65,000	48,000	36.0	59.0	143	64.0
	Normalized (1600 F)	64,000	50,250	35.8	67.9	131	86.8
	Annealed (1600 F)	57,250	42,750	36.5	66.0	111	91.0
1022	As-rolled	73,000	52,000	35.0	67.0	149	60.0
	Normalized (1700 F)	70,000	52,000	34.0	67.5	143	86.5
	Annealed (1600 F)	65,250	46,000	35.0	63.6	137	89.0
1030	As-rolled	80,000	50,000	32.0	57.0	179	55.0
	Normalized (1700 F)	75,000	50,000	32.0	60.8	149	69.0
	Annealed (1550 F)	67,250	49,500	31.2	57.9	126	51.2
1040	As-rolled	90,000	60,000	25.0	50.0	201	36.0
	Normalized (1650 F)	85,500	54,250	28.0	54.9	170	48.0
	Annealed (1450 F)	75,250	51,250	30.2	57.2	149	32.7
1050	As-rolled	105,000	60,000	20.0	40.0	229	23.0
	Normalized (1650 F)	108,500	62,000	20.0	39.4	217	20.0
	Annealed (1450 F)	92,250	53,000	23.7	39.9	187	12.5
1060	As-rolled	118,000	70,000	17.0	34.0	241	13.0
	Normalized (1650 F)	112,500	61,000	18.0	37.2	229	9.7
	Annealed (1450 F)	90,750	54,000	22.5	38.2	179	8.3
1080	As-rolled	140,000	85,000	12.0	17.0	293	5.0
	Normalized (1650 F)	146,500	76,000	11.0	20.6	293	5.0
	Annealed (1450 F)	89,250	54,500	24.7	45.0	174	4.5
1095	As-rolled	140,000	83,000	9.0	18.0	293	3.0
	Normalized (1650 F)	147,000	72,500	9.5	13.5	293	4.0
	Annealed (1450 F)	95,250	55,000	13.0	20.6	192	2.0
1117	As-rolled	70,600	44,300	33.0	63.0	143	60.0
	Normalized (1650 F)	67,750	44,000	33.5	63.8	137	62.8
	Annealed (1575 F)	62,250	40,500	32.8	58.0	121	69.0
1118	As-rolled	75,600	45,900	32.0	70.0	149	80.0
	Normalized (1700 F)	69,250	46,250	33.5	65.9	143	76.3
	Annealed (1450 F)	65,250	41,250	34.5	66.8	131	78.5
1137	As-rolled	91,000	55,00	28.0	61.0	192	61.0
	Normalized (1650 F)	97,000	57,500	22.5	48.5	197	47.0
	Annealed (1450 F)	84,750	50,000	26.8	53.9	174	36.8
1141	As-rolled	98,000	52,000	22.0	38.0	192	8.2
	Normalized (1650 F)	102,500	58,750	22.7	55.5	201	38.8
	Annealed (1500 F)	86,800	51,200	25.5	49.3	163	25.3
1144	As-rolled	102,000	61,000	21.0	41.0	212	39.0
	Normalized (1650 F)	96,750	58,000	21.0	40.4	197	32.0
	Annealed (1450 F)	84,750	50,250	24.8	41.3	167	48.0

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11a. ***(Continued)*** **Typical Mechanical Properties of Selected Carbon and Alloy Steels** (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Treatment	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn	Impact Strength (Izod), ft-lb
		Tensile	Yield				
		lb/in.^{2}					
1340	Normalized (1600 F)	121,250	81,000	22.0	62.9	248	68.2
	Annealed (1475 F)	102,000	63,250	25.5	57.3	207	52.0
3140	Normalized (1600 F)	129,250	87,000	19.7	57.3	262	39.5
	Annealed (1500 F)	100,000	61,250	24.5	50.8	197	34.2
4130	Normalized (1600 F)	97,000	63,250	25.5	59.5	197	63.7
	Annealed (1585 F)	81,250	52,250	28.2	55.6	156	45.5
4140	Normalized (1600 F)	148,000	95,000	17.7	46.8	302	16.7
	Annealed (1500 F)	95,000	60,500	25.7	56.9	197	40.2
4150	Normalized (1600 F)	167,500	106,500	11.7	30.8	321	8.5
	Annealed (1500 F)	105,750	55,000	20.2	40.2	197	18.2
4320	Normalized (1640 F)	115,000	67,250	20.8	50.7	235	53.8
	Annealed (1560 F)	84,000	61,625	29.0	58.4	163	81.0
4340	Normalized (1600 F)	185,500	125,000	12.2	36.3	363	11.7
	Annealed (1490 F)	108,000	68,500	22.0	49.9	217	37.7
4620	Normalized (1650 F)	83,250	53,125	29.0	66.7	174	98.0
	Annealed (1575 F)	74,250	54,000	31.3	60.3	149	69.0
4820	Normalized (1580 F)	109,500	70,250	24.0	59.2	229	81.0
	Annealed (1500 F)	98,750	67,250	22.3	58.8	197	68.5
5140	Normalized (1600 F)	115,000	68,500	22.7	59.2	229	28.0
	Annealed (1525 F)	83,000	42,500	28.6	57.3	167	30.0
5150	Normalized (1600 F)	126,250	76,750	20.7	58.7	255	23.2
	Annealed (1520 F)	98,000	51,750	22.0	43.7	197	18.5
5160	Normalized (1575 F)	138,750	77,000	17.5	44.8	269	8.0
	Annealed (1495 F)	104,750	40,000	17.2	30.6	197	7.4
6150	Normalized (1600 F)	136,250	89,250	21.8	61.0	269	26.2
	Annealed (1500 F)	96,750	59,750	23.0	48.4	197	20.2
8620	Normalized (1675 F)	91,750	51,750	26.3	59.7	183	73.5
	Annealed (1600 F)	77,750	55,875	31.3	62.1	149	82.8
8630	Normalized (1600 F)	94,250	62,250	23.5	53.5	187	69.8
	Annealed (1550 F)	81,750	54,000	29.0	58.9	156	70.2
8650	Normalized (1600 F)	148,500	99,750	14.0	40.4	302	10.0
	Annealed (1465 F)	103,750	56,000	22.5	46.4	212	21.7
8740	Normalized (1600 F)	134,750	88,000	16.0	47.9	269	13.0
	Annealed (1500 F)	100,750	60,250	22.2	46.4	201	29.5
9255	Normalized (1650 F)	135,250	84,000	19.7	43.4	269	10.0
	Annealed (1550 F)	112,250	70,500	21.7	41.1	229	6.5
9310	Normalized (1630 F)	131,500	82,750	18.8	58.1	269	88.0
	Annealed (1550 F)	119,000	63,750	17.3	42.1	241	58.0

[a] All grades are fine-grained except those in the 1100 series that are coarse-grained. Austenitizing temperatures are given in parentheses. Heat-treated specimens were oil-quenched unless otherwise indicated.

Source: Bethlehem Steel Corp. and Republic Steel Corp. as published in 1974 DATABOOK issue of the American Society for Metals' METAL PROGRESS magazine and used with its permission.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11b. Typical Mechanical Properties of Selected Carbon and Alloy Steels (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Tempering Temperature, °F	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn
		Tensile	Yield			
		1000 lb/in.^{2}				
1030[b]	400	123	94	17	47	495
	600	116	90	19	53	401
	800	106	84	23	60	302
	1000	97	75	28	65	255
	1200	85	64	32	70	207
1040[b]	400	130	96	16	45	514
	600	129	94	18	52	444
	800	122	92	21	57	352
	1000	113	86	23	61	269
	1200	97	72	28	68	201
1040	400	113	86	19	48	262
	600	113	86	20	53	255
	800	110	80	21	54	241
	1000	104	71	26	57	212
	1200	92	63	29	65	192
1050[b]	400	163	117	9	27	514
	600	158	115	13	36	444
	800	145	110	19	48	375
	1000	125	95	23	58	293
	1200	104	78	28	65	235
1050	400	…	…	…	…	…
	600	142	105	14	47	321
	800	136	95	20	50	277
	1000	127	84	23	53	262
	1200	107	68	29	60	223
1060	400	160	113	13	40	321
	600	160	113	13	40	321
	800	156	111	14	41	311
	1000	140	97	17	45	277
	1200	116	76	23	54	229
1080	400	190	142	12	35	388
	600	189	142	12	35	388
	800	187	138	13	36	375
	1000	164	117	16	40	321
	1200	129	87	21	50	255
1095[b]	400	216	152	10	31	601
	600	212	150	11	33	534
	800	199	139	13	35	388
	1000	165	110	15	40	293
	1200	122	85	20	47	235
1095	400	187	120	10	30	401
	600	183	118	10	30	375
	800	176	112	12	32	363
	1000	158	98	15	37	321
	1200	130	80	21	47	269
1137	400	157	136	5	22	352
	600	143	122	10	33	285
	800	127	106	15	48	262
	1000	110	88	24	62	229
	1200	95	70	28	69	197

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11b. ***(Continued)*** **Typical Mechanical Properties of Selected Carbon and Alloy Steels** (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Tempering Temperature, °F	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn
		Tensile	Yield			
		1000 lb/in.^{2}				
1137[b]	400	217	169	5	17	415
	600	199	163	9	25	375
	800	160	143	14	40	311
	1000	120	105	19	60	262
	1200	94	77	25	69	187
1141	400	237	176	6	17	461
	600	212	186	9	32	415
	800	169	150	12	47	331
	1000	130	111	18	57	262
	1200	103	86	23	62	217
1144	400	127	91	17	36	277
	600	126	90	17	40	262
	800	123	88	18	42	248
	1000	117	83	20	46	235
	1200	105	73	23	55	217
1330[b]	400	232	211	9	39	459
	600	207	186	9	44	402
	800	168	150	15	53	335
	1000	127	112	18	60	263
	1200	106	83	23	63	216
1340	400	262	231	11	35	505
	600	230	206	12	43	453
	800	183	167	14	51	375
	1000	140	120	17	58	295
	1200	116	90	22	66	252
4037	400	149	110	6	38	310
	600	138	111	14	53	295
	800	127	106	20	60	270
	1000	115	95	23	63	247
	1200	101	61	29	60	220
4042	400	261	241	12	37	516
	600	234	211	13	42	455
	800	187	170	15	51	380
	1000	143	128	20	59	300
	1200	115	100	28	66	238
4130[b]	400	236	212	10	41	467
	600	217	200	11	43	435
	800	186	173	13	49	380
	1000	150	132	17	57	315
	1200	118	102	22	64	245
4140	400	257	238	8	38	510
	600	225	208	9	43	445
	800	181	165	13	49	370
	1000	138	121	18	58	285
	1200	110	95	22	63	230
4150	400	280	250	10	39	530
	600	256	231	10	40	495
	800	220	200	12	45	440
	1000	175	160	15	52	370
	1200	139	122	19	60	290
4340	400	272	243	10	38	520
	600	250	230	10	40	486
	800	213	198	10	44	430
	1000	170	156	13	51	360
	1200	140	124	19	60	280

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11b. ***(Continued)*** **Typical Mechanical Properties of Selected Carbon and Alloy Steels** (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Tempering Temperature, °F	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn
		Tensile	Yield			
		1000 lb/in.^{2}				
5046	400	253	204	9	25	482
	600	205	168	10	37	401
	800	165	135	13	50	336
	1000	136	111	18	61	282
	1200	114	95	24	66	235
50B46	400	…	…	…	…	560
	600	258	235	10	37	505
	800	202	181	13	47	405
	1000	157	142	17	51	322
	1200	128	115	22	60	273
50B60	400	…	…	…	…	600
	600	273	257	8	32	525
	800	219	201	11	34	435
	1000	163	145	15	38	350
	1200	130	113	19	50	290
5130	400	234	220	10	40	475
	600	217	204	10	46	440
	800	185	175	12	51	379
	1000	150	136	15	56	305
	1200	115	100	20	63	245
5140	400	260	238	9	38	490
	600	229	210	10	43	450
	800	190	170	13	50	365
	1000	145	125	17	58	280
	1200	110	96	25	66	235
5150	400	282	251	5	37	525
	600	252	230	6	40	475
	800	210	190	9	47	410
	1000	163	150	15	54	340
	1200	117	118	20	60	270
5160	400	322	260	4	10	627
	600	290	257	9	30	555
	800	233	212	10	37	461
	1000	169	151	12	47	341
	1200	130	116	20	56	269
51B60	400	…	…	…	…	600
	600	…	…	…	…	540
	800	237	216	11	36	460
	1000	175	160	15	44	355
	1200	140	126	20	47	290
6150	400	280	245	8	38	538
	600	250	228	8	39	483
	800	208	193	10	43	420
	1000	168	155	13	50	345
	1200	137	122	17	58	282
81B45	400	295	250	10	33	550
	600	256	228	8	42	475
	800	204	190	11	48	405
	1000	160	149	16	53	338
	1200	130	115	20	55	280

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11b. ***(Continued)*** **Typical Mechanical Properties of Selected Carbon and Alloy Steels** (Hot Rolled, Normalized, and Annealed)

AISI No.[a]	Tempering Temperature, °F	Strength		Elongation, Per cent	Reduction in Area, Per cent	Hardness, Bhn
		Tensile	Yield			
		1000 lb/in.^{2}				
8630	400	238	218	9	38	465
	600	215	202	10	42	430
	800	185	170	13	47	375
	1000	150	130	17	54	310
	1200	112	100	23	63	240
8640	400	270	242	10	40	505
	600	240	220	10	41	460
	800	200	188	12	45	400
	1000	160	150	16	54	340
	1200	130	116	20	62	280
86B45	400	287	238	9	31	525
	600	246	225	9	40	475
	800	200	191	11	41	395
	1000	160	150	15	49	335
	1200	131	127	19	58	280
8650	400	281	243	10	38	525
	600	250	225	10	40	490
	800	210	192	12	45	420
	1000	170	153	15	51	340
	1200	140	120	20	58	280
8660	400	…	…	…	…	580
	600	…	…	…	…	535
	800	237	225	13	37	460
	1000	190	176	17	46	370
	1200	155	138	20	53	315
8740	400	290	240	10	41	578
	600	249	225	11	46	495
	800	208	197	13	50	415
	1000	175	165	15	55	363
	1200	143	131	20	60	302
9255	400	305	297	1	3	601
	600	281	260	4	10	578
	800	233	216	8	22	477
	1000	182	160	15	32	352
	1200	144	118	20	42	285
9260	400	…	…	…	…	600
	600	…	…	…	…	540
	800	255	218	8	24	470
	1000	192	164	12	30	390
	1200	142	118	20	43	295
94B30	400	250	225	12	46	475
	600	232	206	12	49	445
	800	195	175	13	57	382
	1000	145	135	16	65	307
	1200	120	105	21	69	250

[a] All grades are fine-grained except those in the 1100 series that are coarse-grained. Austenitizing temperatures are given in parentheses. Heat-treated specimens were oil-quenched unless otherwise indicated.

[b] Water quenched.

Source: Bethlehem Steel Corp. and Republic Steel Corp. as published in 1974 DATABOOK issue of the American Society for Metals' *METAL PROGRESS* magazine and used with its permission.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Nominal Mechanical Properties of Standard Stainless Steels

Grade	Condition	Tensile Strength (psi)	0.2 Per Cent Yield Strength (psi)	Elongation in 2 in. (%)	Reduction of Area (%)	Hardness	
						Rockwell	Bhn
Austenitic Steels							
201	Annealed	115,000	55,000	55	…	B90	…
	1/4-hard	125,000[a]	75,000[a]	20[a]	…	C25	…
	1/2-hard	150,000[a]	110,000[a]	10[a]	…	C32	…
	3/4-hard	175,000[a]	135,000[a]	5[a]	…	C37	…
	Full-hard	185,000[a]	140,000[a]	4[a]	…	C41	…
202	Annealed	105,000	55,000	55	…	B90	…
	1/4-hard	125,000[a]	75,000[a]	12[a]	…	C27	…
301	Annealed	110,000	40,000	60	…	B85	165
	1/4-hard	125,000[a]	75,000[a]	25[a]	…	C25	…
	1/2-hard	150,000[a]	110,000[a]	15[a]	…	C32	…
	3/4-hard	175,000[a]	135,000[a]	12[a]	…	C37	…
	Full-hard	185,000	140,000[a]	8[a]	…	C41	…
302	Annealed	90,000	37,000	55	65	B82	155
	1/4-hard (sheet, strip)	125,000[a]	75,000[a]	12[a]	…	C25	…
	Cold-drawn (bar, wire)[b]	To 350,000	…	…	…	…	…
302B	Annealed	95,000	40,000	50	65	B85	165
303, 303Se	Annealed	90,000	35,000	50	55	B84	160
304	Annealed	85,000	35,000	55	65	B80	150
304L	Annealed	80,000	30,000	55	65	B76	140
305	Annealed	85,000	37,000	55	70	B82	156
308	Annealed	85,000	35,000	55	65	B80	150
309, 309S	Annealed	90,000	40,000	45	65	B85	165
310, 310S	Annealed	95,000	40,000	45	65	B87	170
314	Annealed	100,000	50,000	45	60	B87	170
316	Annealed	85,000	35,000	55	70	B80	150
	Cold-drawn (bar, wire)[b]	To 300,000	…	…	…	…	…
316L	Annealed	78,000	30,000	55	65	B76	145
317	Annealed	90,000	40,000	50	55	B85	160
321	Annealed	87,000	35,000	55	65	B80	150
347, 348	Annealed	92,000	35,000	50	65	B84	160
Martensitic Steels							
403, 410, 416, 416Se	Annealed	75,000	40,000	30	65	B82	155
	Hardened[c]	…	…	…	…	C43	410
	Tempered at						
	400°F	190,000	145,000	15	55	C41	390
	600°F	180,000	140,000	15	55	C39	375
	800°F	195,000	150,000	17	55	C41	390
	1000°F	145,000	115,000	20	65	C31	300
	1200°F	110,000	85,000	23	65	B97	225
	1400°F	90,000	60,000	30	70	B89	180

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Nominal Mechanical Properties of Standard Stainless Steels**

Grade	Condition	Tensile Strength (psi)	0.2 Per Cent Yield Strength (psi)	Elongation in 2 in. (%)	Reduction of Area (%)	Hardness	
						Rockwell	Bhn
Martensitic Steels *(Continued)*							
414	Annealed	120,000	95,000	17	55	C22	235
	Hardened[c]	…	…	…	…	C44	426
	Tempered at						
	400°F	200,000	150,000	15	55	C43	415
	600°F	190,000	145,000	15	55	C41	400
	800°F	200,000	150,000	16	58	C43	415
	1000°F	145,000	120,000	20	60	C34	325
	1200°F	120,000	105,000	20	65	C24	260
420, 420F	Annealed	95,000	50,000	25	55	B92	195
	Hardened[d]	…	…	…	…	C54	540
	Tempered at						
	600°F	230,000	195,000	8	25	C50	500
431	Annealed	125,000	95,000	20	60	C24	260
	Hardened[d]	…	…	…	…	C45	440
	Tempered at						
	400°F	205,000	155,000	15	55	C43	415
	600°F	195,000	150,000	15	55	C41	400
	800°F	205,000	155,000	15	60	C43	415
	1000°F	150,000	130,000	18	60	C34	325
	1200°F	125,000	95,000	20	60	C24	260
440A	Annealed	105,000	60,000	20	45	B95	215
	Hardened[d]	…	…	…	…	C56	570
	Tempered						
	600°F	260,000	240,000	5	20	C51	510
440B	Annealed	107,000	62,000	18	35	B96	220
	Hardened[d]	…	…	…	…	C58	590
	Tempered						
	600°F	280,000	270,000	3	15	C55	555
440C, 440F	Annealed	110,000	65,000	13	25	B97	230
	Hardened[d]	…	…	…	…	C60	610
	Tempered						
	600°F	285,000	275,000	2	10	C57	580
501	Annealed	70,000	30,000	28	65	…	160
502	Annealed	70,000	30,000	30	75	B80	150
Ferritic Steels							
405	Annealed	70,000	40,000	30	60	B80	150
430	Annealed	75,000	45,000	30	60	B82	155
430F, 430FSe	Annealed	80,000	55,000	25	60	B86	170
446	Annealed	80,000	50,000	23	50	B86	170

[a] Minimum.
[b] Depending on size and amount of cold reduction.
[c] Hardening temperature 1800 degrees F, 1-in.-diam. bars.
[d] Hardening temperature 1900 degrees F, 1-in.-diam. bars.
Source: Metals Handbook, 8th edition, Volume 1.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Strength Data for Iron and Steel

Material	Ultimate Strength			Yield Point, Thousands of Pounds per Square Inch	Modulus of Elasticity	
	Tension, Thousands of Pounds per Square Inch, T	Compression, in terms of T	Shear, in terms of T		Tension, Millions of psi, E	Shear,[a] in terms of E
Cast iron, gray, class 20	20[b]	3.6T to 4.4T	1.6T	…	11.6	0.40E
class 25	25[b]	3.6T to 4.4T	1.4T	…	14.2	0.40E
class 30	30[b]	3.7T	1.4T	…	14.5	0.40E
class 35	35[b]	3.2T to 3.9T	1.4T	…	16.0	0.40E
class 40	40[b]	3.1T to 3.4T	1.3T	…	17	0.40E
class 50	50[b]	3.0T to 3.4T	1.3T	…	18	0.40E
class 60	60[b]	2.8T	1.0T	…	19.9	0.40E
malleable	40 to 100[c]	…	…	30 to 80[c]	25	0.43E
nodular (ductile iron)	60 to 120[d]	…	…	40 to 90[d]	23	…
Cast steel, carbon	60 to 100	T	0.75T	30 to 70	30	0.38E
low-alloy	70 to 200	T	0.75T	45 to 170	30	0.38E
Steel, SAE 950 (low-alloy)	65 to 70	T	0.75T	45 to 50	30	0.38E
1025 (low-carbon)	60 to 103	T	0.75T	40 to 90	30	0.38E
1045 (medium-carbon)	80 to 182	T	0.75T	50 to 162	30	0.38E
1095 (high-carbon)	90 to 213	T	0.75T	20 to 150	30	0.39E
1112 (free-cuttting)[e]	60 to 100	T	0.75T	30 to 95	30	0.38E
1212 (free-cuttting)	57 to 80	T	0.75T	25 to 72	30	0.38E
1330 (alloy)	90 to 162	T	0.75T	27 to 149	30	0.38E
2517 (alloy)[e]	88 to 190	T	0.75T	60 to 155	30	0.38E
3140 (alloy)	93 to 188	T	0.75T	62 to 162	30	0.38E
3310 (alloy)[e]	104 to 172	T	0.75T	56 to 142	30	0.38E
4023 (alloy)[e]	105 to 170	T	0.75T	60 to 114	30	0.38E
4130 (alloy)	81 to 179	T	0.75T	46 to 161	30	0.38E
4340 (alloy)	109 to 220	T	0.75T	68 to 200	30	0.38E
4640 (alloy)	98 to 192	T	0.75T	62 to 169	30	0.38E
4820 (alloy)[e]	98 to 209	T	0.75T	68 to 184	30	0.38E
5150 (alloy)	98 to 210	T	0.75T	51 to 190	30	0.38E
52100 (alloy)	100 to 238	T	0.75T	81 to 228	30	0.38E
6150 (alloy)	96 to 228	T	0.75T	59 to 210	30	0.38E
8650 (alloy)	110 to 228	T	0.75T	69 to 206	30	0.38E
8740 (alloy)	100 to 179	T	0.75T	60 to 165	30	0.38E
9310 (alloy)[e]	117 to 187	T	0.75T	63 to 162	30	0.38E
9840 (alloy)	120 to 285	T	0.75T	45 to 50	30	0.38E
Steel, stainless, SAE						
30302[f]	85 to 125	T	…	35 to 95	28	0.45E
30321[f]	85 to 95	T	…	30 to 60	28	…
30347[f]	90 to 100	T	…	35 to 65	28	…
51420[g]	95 to 230	T	…	50 to 195	29	0.40E
51430[h]	75 to 85	T	…	40 to 70	29	…
51446[h]	80 to 85	T	…	50 to 70	29	…
51501[g]	70 to 175	T	…	30 to 135	29	…
Steel, structural						
common	60 to 75	T	0.75T	33[b]	29	0.41E
rivet	52 to 62	T	0.75T	28[b]	29	…
rivet, high-strength	68 to 82	T	0.75T	38[b]	29	…
Wrought iron	34 to 54	T	0.83T	23 to 32	28	…

[a] Synonymous in other literature to the modulus of elasticity in torsion and the modulus of rigidity, G.

[b] Minimum specified value of the American Society for Testing and Materials. The specifications for the various materials are as follows: Cast iron, ASTM A48; structural steel for bridges and structures, ASTM A7; structural rivet steel, ASTM A141; high-strength structural rivet steel, ASTM A195.

[c] Range of minimum specified values of the ASTM (ASTM A47, A197, and A220).

[d] Range of minimum specified values of the ASTM (ASTM A339) and the Munitions Board Standards Agency (MIL-I-17166A and MIL-I-11466).

[e] Carburizing grades of steel.

[f] Nonhardenable nickel–chromium and Chromium–nickel–manganese steel (austenitic).

[g] Hardenable chromium steel (martensitic).

[h] Nonhardenable chromium steel (ferritic).

Copyright 2004, Industrial Press, Inc., New York, NY

TOOL STEELS

Overview

As the designation implies, tool steels serve primarily for making tools used in manufacturing and in the trades for the working and forming of metals, wood, plastics, and other industrial materials. Tools must withstand high specific loads, often concentrated at exposed areas, may have to operate at elevated or rapidly changing temperatures and in continual contact with abrasive types of work materials, and are often subjected to shocks, or may have to perform under other varieties of adverse conditions. Nevertheless, when employed under circumstances that are regarded as normal operating conditions, the tool should not suffer major damage, untimely wear resulting in the dulling of the edges, or be susceptible to detrimental metallurgical changes.

Tools for less demanding uses, such as ordinary handtools, including hammers, chisels, files, mining bits, etc., are often made of standard AISI steels that are not considered as belonging to any of the tool steel categories.

The steel for most types of tools must be used in a heat-treated state, generally hardened and tempered, to provide the properties needed for the particular application. The adaptability to heat treatment with a minimurn of harmful effects, which dependably results in the intended beneficial changes in material properties, is still another requirement that tool steels must satisfy.

To meet such varied requirements, steel types of different chemical composition, often produced by special metallurgical processes, have been developed. Due to the large number of tool steel types produced by the steel mills, which generally are made available with proprietary designations, it is rather difficult for the user to select those types that are most suitable for any specific application, unless the recommendations of a particular steel producer or producers are obtained.

Substantial clarification has resulted from the development of a classification system that is now widely accepted throughout the industry, on the part of both the producers and the users of tool steels. That system is used in the following as a base for providing concise information on tool steel types, their properties, and methods of tool steel selection.

The tool steel classification system establishes seven basic categories of tool and die steels. These categories are associated with the predominant applicational characteristics of the tool steel types they comprise. A few of these categories are composed of several groups to distinguish between families of steel types that, while serving the same general purpose, differ with regard to one or more dominant characteristics.

To provide an easily applicable guide for the selection of tool steel types best suited for a particular application, the subsequent discussions and tables are based on the previously mentioned application-related categories. As an introduction to the detailed surveys, a concise discussion is presented of the principal tool steel characteristics that govern the suitability for varying service purposes and operational conditions. A brief review of the major steel alloying elements and of the effect of these constituents on the significant characteristics of tool steels is also given in the following sections.

The Properties of Tool Steels.— Tool steels must possess certain properties to a higher than ordinary degree to make them adaptable for uses that require the ability to sustain heavy loads and perform dependably even under adverse conditions.

The extent and the types of loads, the characteristics of the operating conditions, and the expected performance with regard to both the duration and the level of consistency are the principal considerations, in combination with the aspects of cost, that govern the selection of tool steels for specific applications.

Although it is not possible to define and apply exact parameters for measuring significant tool steel characteristics, certain properties can be determined that may greatly assist in appraising the suitability of various types of tool steels for specific uses.

Copyright 2004, Industrial Press, Inc., New York, NY

Because tool steels are generally heat-treated to make them adaptable to the intended use by enhancing the desirable properties, *the behavior of the steel during heat treatment* is of prime importance. The behavior of the steel comprises, in this respect, both the resistance to harmful effects and the attainment of the desirable properties. The following are considered the major properties related to heat treatment:

Safety in Hardening: This designation expresses the ability of the steel to withstand the harmful effects of exposure to very high heat and particularly to the sudden temperature changes during quenching, without harmful effects. One way of obtaining this property is by adding alloying elements to reduce the critical speed at which quenching must be carried out, thus permitting the use of milder quenching media such as oil, salt, or just still air.



Fig. 1. Tool and die design tips to reduce breakage in heat treatment.
Courtesy of Society of Automotive Engineers, Inc.

The most common harm parts made of tool steel suffer from during heat treatment is the development of cracks. In addition to the composition of the steel and the applied heat-treating process, the configuration of the part can also affect the sensitivity to cracking. The preceding figure illustrates a few design characteristics related to cracking and warpage in heat treatment; the observation of these design tips, which call for generous filleting, avoidance of sharp angles, and major changes without transition in the cross-section, is particularly advisable when using tool steel types with a low index value for safety in hardening.

In current practice, the previously mentioned property of tool steels is rated in the order of decreasing safety (i.e., increasing sensitivity) as Highest, Very High, High, Medium, and Low safety, expressed in Tables 6 through 11 by the letters A, B, C, D, and E.

Distortions in Heat Treating: In parts made from tool steels, distortions are often a consequence of inadequate design (See Fig. 1.) or improper heat treatment (e.g., lack of stress relieving). However, certain types of tool steels display different degrees of sensitivity to

Copyright 2004, Industrial Press, Inc., New York, NY

distortion. Steels that are less stable require safer design of the parts for which they are used, more careful heat treatment, including the proper support for long and slender parts, or thin sections, and possibly greater grinding allowance to permit subsequent correction of the distorted shape. Some parts made of a type of steel generally sensitive to distortions can be heat-treated with very little damage when the requirements of the part call for a relatively shallow hardened layer over a soft core. However, for intricate shapes and large tools, steel types should be selected that possess superior nondeforming properties. The ratings used in Tables 6 through 11 express the nondeforming properties (stability of shape in heat treatment) of the steel types and start with the lowest distortion (the best stability) designated as A; the greatest susceptibility to distortion is designated as E.

Depth of Hardening: Hardening depth is indicated by a relative rating based on how deep the phase transformation penetrates from the surface and thus produces a hardened layer. Because of the effect of the heat-treating process, and particularly of the applied quenching medium, on the depth of hardness, reference is made in Tables 6 through 11 to the quench that results in the listed relative hardenability values. These values are designated by letters A, B, and C, expressing deep, medium, and shallow depth, respectively.

Resistance to Decarburization: Higher or lower sensitivity to losing a part of the carbon content of the surface exposed to heat depends on the chemistry of the steel. The sensitivity can be balanced partially by appropriate heat-treating equipment and processes. Also, the amount of material to be removed from the surface after heat treatment, usually by grinding, should be specified in such a manner as to avoid the retention of a decarburized layer on functional surfaces. The relative resistance of individual tool steel types to decarburization during heat treatment is rated in Tables 6 through 11 from High to Low, expressed by the letters A, B, and C.

Tool steels must be workable with generally available means, without requiring highly specialized processes. The tools made from these steels must, of course, perform adequately, often under adverse environmental and burdensome operational conditions. The ability of the individual types of tool steels to satisfy, to different degrees, such applicational requirements can also be appraised on the basis of significant properties, such as the following.

Machinability: Tools are precision products whose final shape and dimensions must be produced by machining, a process to which not all tool steel types lend themselves equally well. The difference in machinability is particularly evident in tool steels that, depending on their chemical composition, may contain substantial amounts of metallic carbides, beneficial to increased wear resistance, yet detrimental to the service life of tools with which the steel has to be worked. The microstructure of the steel type can also affect the ease of machining and, in some types, certain phase conditions, such as those due to low carbon content, may cause difficulties in achieving a fine surface finish. Certain types of tool steels have their machinability improved by the addition of small amounts of sulfur or lead.

Machinability affects the cost of making the tool, particularly for intricate tool shapes, and must be considered in selection of the steel to be used. The ratings in Tables 6 through 11, starting with A for the greatest ease of machining to E for the lowest machinability, refer to working of the steel in an unhardened condition. Machinability is not necessarily identical with grindability, which expresses how well the steel is adapted to grinding after heat treating. The ease of grinding, however, may become an important consideration in tool steel selection, particularly for cutting tools and dies, which require regular sharpening involving extensive grinding. AVCO Bay State Abrasives Company compiled information on the relative grindability of frequently used types of tool steels. A simplified version of that information is presented in Table 1, which assigns the listed tool steel types to one of the following grindability grades: High (A), Medium (B), Low (C), and Very Low (D), expressing decreasing ratios of volume of metal removed to wheel wear.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Relative Grindability of Selected Types of Frequently Used Tool Steels

AISI Tool Steel Type	H41	H42	H43	Other H	D2	D3	D5	D7	A Types	O Types	L Types	F Types
Relative Grindability Index	B	B	B	A	B	B	B	C	A	A	A	B

High-Speed Tool Steel Type	M1	M2	M3 (1)	M3 (2)	M4	M7	M8	M10	M15	M36	M43	T1	T2	T3	T5	T6	T15
Relative Grindability Index	A	B	C	C	D	B	A	B	D	B	B	A	B	C	B	B	D

Hot Hardness: This property designates the steel's resistance to the softening effect of elevated temperature. This characteristic is related to the tempering temperature of the type of steel, which is controlled by various alloying elements such as tungsten, molybdenum, vanadium, cobalt, and chromium.

Hot hardness is a necessary property of tools used for hot work, like forging, casting, and hot extrusion. Hot hardness is also important in cutting tools operated at high-speed, which generate sufficient heat to raise their temperature well above the level where ordinary steels lose their hardness; hence the designation *high-speed steels*, which refers to a family of tool steels developed for use at high cutting speeds. Frequently it is the degree of the tool steel's resistance to softening at elevated temperature that governs important process data, such as the applicable cutting speed. In the ratings of Tables 6 through 11, tool steel types having the highest hot hardness are marked with A, subsequent letters expressing gradually decreasing capacity to endure elevated temperature without losing hardness.

Wear Resistance: The gradual erosion of the tool's operating surface, most conspicuously occurring at the exposed edges, is known as wear. Resistance to wear prolongs the useful life of the tool by delaying the degradation of its surface through abrasive contact with the work at regular operating temperatures; these temperatures vary according to the type of process. Wear resistance is observable experimentally and measurable by comparison. Certain types of metallic carbides embedded into the steel matrix are considered to be the prime contributing factors to wear resistance, besides the hardness of the heat-treated steel material. The ratings of Tables 6 through 11, starting with A for the best to E for poor, are based on conditions thought to be normal in operations for which various types of tool materials are primarily used.

Toughness: In tool steels, this property expresses ability to sustain shocks, suddenly applied and relieved loads, or major impacts, without breaking. Steels used for making tools must also be able to absorb such forces with only a minimum of elastic deformation and without permanent deformation to any extent that would interfere with the proper functioning of the tool. Certain types of tool steels, particularly those with high carbon content and without the presence of beneficial alloying constituents, tend to be the most sensitive to shocks, although they can also be made to act tougher when used for tools that permit a hardened case to be supported by a soft core. Tempering improves toughness, while generally reducing hardness. The rating indexes in Tables 6 through 11, A for the highest toughness through E for the types most sensitive to shocks, apply to tools heat treated to hardness values normally used for the particular type of tool steel.

Common Tool Faults and Failures.— The proper selection of the steel grade used for any particular type of tool is of great importance, but it should be recognized that many of the failures experienced in common practice originate from causes other than those related to the tool material.

To permit a better appraisal of the actual causes of failure and possible corrective action, a general, although not complete, list of common tool faults, resulting failures, and corrective actions is shown in Tables 2a through 2d. In this list, the potential failure causes are grouped into four categories. The possibility of more than a single cause being responsible for the experienced failure should not be excluded.

Copyright 2004, Industrial Press, Inc., New York, NY

Note: Examples of tool failures from causes such as listed above may be found in "The Tool Steel Trouble Shooter" handbook, published by Bethlehem Steel Corporation.

Finally, it must be remembered that the proper usage of tools is indispensable for obtaining satisfactory performance and tool life. Using the tools properly involves, for example, the avoidance of damage to the tool; overloading; excessive speeds and feeds; the application of adequate coolant when called for; a rigid setup; proper alignment; and firm tool and work holding.

Table 2a. Common Tool Faults, Failures, and Cures
Improper Tool Design

Fault Description	Probable Failure	Possible Cure
Drastic section changes—widely different thicknesses of adjacent wall sections or protruding elements	In liquid quenching, the thin section will cool and then harden more rapidly than the adjacent thicker section, setting up stresses that may exceed the strength of the steel.	Make such parts of two pieces or use an air-hardening tool steel that avoids the harsh action of a liquid quench.
Sharp corners on shoulders or in square holes	Cracking can occur, particularly in liquid quenching, due to stress concentrations.	Apply fillets to the corners and/or use an air-hardening tool steel.
Sharp cornered keyways	Failure may arise during service, and is usually considered to be caused by fatigue.	The use of round keyways should be preferred when the general configuration of the part makes it prone to failure due to square keyways.
Abrupt section changes in battering tools	Due to impact in service, pneumatic tools are particularly sensitive to stress concentrations that lead to fatigue failures.	Use taper transitions, which are better than even generous fillets.
Functional inadequacy of tool design—e.g., insufficient guidance for a punch	Excessive wear or breakage in service may occur.	Assure solid support, avoid unnecessary play, adapt travel length to operational conditions (e.g., punch to penetrate to four-fifths of thickness in hard work material).
Improper tool clearance, such as in blanking and punching tools	Deformed and burred parts may be produced, excessive tool wear or breakage can result.	Adapt clearances to material conditions and dimensions to reduce tool load and to obtain clean sheared surfaces.

The Effect of Alloying Elements on Tool Steel Properties.— *Carbon (C):* The presence of carbon, usually in excess of 0.60 per cent for nonalloyed types, is essential for raising the hardenability of steels to the levels needed for tools. Raising the carbon content by different amounts up to a maximum of about 1.3 per cent increases the hardness slightly and the wear resistance considerably. The amount of carbon in tool steels is designed to attain certain properties (such as in the water-hardening category where higher carbon content may be chosen to improve wear resistance, although to the detriment of toughness) or, in the alloyed types of tool steels, in conformance with the other constituents to produce well-balanced metallurgical and performance properties.

Manganese (Mn): In small amounts, to about 0.60 per cent, manganese is added to reduce brittleness and to improve forgeability. Larger amounts of manganese improve hardenability, permitting oil quenching for nonalloyed carbon steels, thus reducing deformation, although with regard to several other properties, manganese is not an equivalent replacement for the regular alloying elements.

Silicon (Si): In itself, silicon may not be considered an alloying element of tool steels, but it is needed as a deoxidizer and improves the hot-forming properties of the steel. In combination with certain alloying elements, the silicon content is sometimes raised to about 2 per cent to increase the strength and toughness of steels used for tools that have to sustain shock loads.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Common Tool Faults, Failures, and Cures
Faulty Condition or Inadequate Grade of Tool Steel

Fault Description	Probable Failure	Possible Cure
Improper tool steel grade selection	Typical failures: Chipping—insufficient toughness. Wear—poor abrasion resistance. Softening—inadequate "red hardness."	Choose the tool steel grade by following recommendations and improve selection when needed, guided by property ratings.
Material defects—voids, streaks, tears, flakes, surface cooling cracks, etc.	When not recognized during material inspection, tools made of defective steel often prove to be useless.	Obtain tool steels from reliable sources and inspect tool material for detectable defects.
Decarburized surface layer ("bark") in rolled tool steel bars	Cracking may originate from the decarburized layer or it will not harden ("soft skin").	Provide allowance for stock to be removed from all surfaces of hot-rolled tool steel. Recommended amounts are listed in tool steel catalogs and vary according to section size, generally about 10 per cent for smaller and 5 per cent for larger diameters.
Brittleness caused by poor carbide distribution in high-alloy tool steels	Excessive brittleness can cause chipping or breakage during service.	Bars with large diameter (above about 4 inches) tend to be prone to nonuniform carbide distribution. Choose upset forged discs instead of large-diameter bars.
Unfavorable grain flow	Improper grain flow of the steel used for milling cutters and similar tools can cause teeth to break out.	Upset forged discs made with an upset ratio of about 2 to 1 (starting to upset thickness) display radial grain flow. Highly stressed tools, such as gear-shaper cutters, may require the cross forging of blanks.

Tungsten (W): Tungsten is one of the important alloying elements of tool steels, particularly because of two valuable properties: it improves "hot hardness," that is, the resistance of the steel to the softening effect of elevated temperature, and it forms hard, abrasion-resistant carbides, thus improving the wear properties of tool steels.

Vanadium (V): Vanadium contributes to the refinement of the carbide structure and thus improves the forgeability of alloy tool steels. Vanadium has a very strong tendency to form a hard carbide, which improves both the hardness and the wear properties of tool steels. However, a large amount of vanadium carbide makes the grinding of the tool very difficult (causing low grindability).

Molybdenum (Mo): In small amounts, molybdenum improves certain metallurgical properties of alloy steels such as deep hardening and toughness. It is used often in larger amounts in certain high-speed tool steels to replace tungsten, primarily for economic reasons, often with nearly equivalent results.

Cobalt (Co): As an alloying element of tool steels, cobalt increases hot hardness and is used in applications where that property is needed. Substantial addition of cobalt, however, raises the critical quenching temperature of the steel with a tendency to increase the decarburization of the surface, and reduces toughness.

Chromium (Cr): This element is added in amounts of several per cent to high-alloy tool steels, and up to 12 per cent to types in which chromium is the major alloying element. Chromium improves hardenability and, together with high carbon, provides both wear resistance and toughness, a combination valuable in certain tool applications. However, high chromium raises the hardening temperature of the tool steel, and thus can make it prone to hardening deformations. A high percentage of chromium also affects the grindability of the tool steel.

Nickel (Ni): Generally in combination with other alloying elements, particularly chromium, nickel is used to improve the toughness and, to some extent, the wear resistance of tool steels.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2c. Common Tool Faults, Failures, and Cures
Heat-Treatment Faults

Fault Description	Probable Failure	Possible Cure
Improper preparation for heat treatment. Certain tools may require stress relieving or annealing, and often preheating, too	Tools highly stressed during machining or forming, unless stress relieved, may aggravate the thermal stresses of heat treatment, thus causing cracks. Excessive temperature gradients developed in nonpreheated tools with different section thicknesses can cause warpage.	Stress relieve, when needed, before hardening. Anneal prior to heavy machining or cold forming (e.g., hobbing). Preheat tools (a) having substantial section thickness variations or (b) requiring high quenching temperatures, as those made of high-speed tool steels.
Overheating during hardening; quenching from too high a temperature	Causes grain coarsening and a sensitivity to cracking that is more pronounced in tools with drastic section changes.	Overheated tools have a characteristic microstructure that aids recognition of the cause of failure and indicates the need for improved temperature control.
Low hardening temperature	The tool may not harden at all, or in its outer portion only, thereby setting up stresses that can lead to cracks.	Controlling both the temperature of the furnace and the time of holding the tool at quenching temperature will prevent this not too frequent deficiency.
Inadequate composition or condition of the quenching media	Water-hardening tool steels are particularly sensitive to inadequate quenching media, which can cause soft spots or even violent cracking.	For water-hardening tool steels, use water free of dissolved air and contaminants, also assure sufficient quantity and proper agitation of the quench.
Improper handling during and after quenching	Cracking, particularly of tools with sharp corners, during the heat treatment can result from holding the part too long in the quench or incorrectly applied tempering.	Following the steel producer's specifications is a safe way to assure proper heat-treatment handling. In general, the tool should be left in the quench until it reaches a temperature of 150 to 200°F, and should then be transferred promptly into a warm tempering furnace.
Insufficient tempering	Omission of double tempering for steel types that require it may cause early failure by heat checking in hot-work steels or make the tool abnormally sensitive to grinding checks.	Double temper highly alloyed tool steel of the high-speed, hot-work, and high-chromium categories, to remove stresses caused by martensite formed during the first tempering phase. Second temper also increases hardness of most high-speed steels.
Decarburization and carburization	Unless hardened in a neutral atmosphere the original carbon content of the tool surface may be changed: Reduced carbon (decarburization) causes a soft layer that wears rapidly. Increased carbon (carburization) when excessive may cause brittleness.	Heating in neutral atmosphere or well-maintained salt bath and controlling the furnace temperature and the time during which the tool is subjected to heating can usually keep the carbon imbalance within acceptable limits.

The addition of more than one element to a steel often produces what is called a synergistic effect. Thus, the combined effects of two or more alloy elements may be greater than the sum of the individual effects of each element.

Classification of Tool Steels.— Steels for tools must satisfy a number of different, often conflicting requirements. The need for specific steel properties arising from widely varying applications has led to the development of many compositions of tool steels, each intended to meet a particular combination of applicational requirements. The diversity of tool steels, their number being continually expanded by the addition of new developments, makes it extremely difficult for the user to select the type best suited to his needs, or to find equivalent alternatives for specific types available from particular sources.

As a cooperative industrial effort under the sponsorship of AISI and SAE, a tool classification system has been developed in which the commonly used tool steels are grouped into seven major categories. These categories, several of which contain more than a single group, are listed in Table 3 with the letter symbols used for their identification. The individual types of tool steels within each category are identified by suffix numbers following the letter symbols.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2d. Common Tool Faults, Failures, and Cures
Grinding Damages

Fault Description	Probable Failure	Possible Cure
Grinding Damages		
Excessive stock removal rate causing heating of the part surface beyond the applied tempering temperature	Scorched tool surface displaying temper colors varying from yellow to purple, depending on the degree of heat, causes softening of the ground surface. When coolant is used, a local hardening can take place, often resulting in cracks.	Prevention: by reducing speed and feed, or using coarser, softer, more open-structured grinding wheel, with ample coolant. Correction: eliminate the discolored layer by subsequent light stock removal. Not always a cure, because the effects of abusive grinding may not be corrected.
Improper grinding wheel specifications; grain too fine or bond too hard	Intense localized heating during grinding may set up surface stresses causing grinding cracks. These cracks are either parallel but at right angles to the direction of grinding or, when more advanced, form a network. May need cold etch or magnetic particle testing to become recognizable.	Prevention: by correcting the grinding wheel specifications. Correction: in shallow (0.002- to 0.004-inch) cracks, by removing the damaged layer, when permitted by the design of the tool, using very light grinding passes.
Incorrectly dressed or loaded grinding wheel	Heating of the work surface can cause scorching or cracking. Incorrect dressing can also cause a poor finish of the ground work surface.	Dress wheel with sharper diamond and faster diamond advance to produce coarser wheel surface. Alternate dressing methods, like crush-dressing, can improve wheel surface conditions. Dress wheel regularly to avoid loading or glazing of the wheel surface.
Inadequate coolant, with regard to composition, amount, distribution, and cleanliness	Introducing into the tool surface heat that is not adequately dissipated or absorbed by the coolant can cause softening, or even the development of cracks.	Improve coolant supply and quality, or reduce stock removal rate to reduce generation of heat in grinding.
Damage caused by abusive abrasive cutoff	The intensive heat developed during this process can cause a hardening of the steel surface, or may even result in cracks.	Reduce rate of advance; adopt wheel specifications better suited for the job. Use ample coolant or, when harmful effect not eliminated, replace abrasive cutoff by some cooler-acting stock separation method (e.g., sawing or lathe cutoff) unless damaged surface is being removed by subsequent machining.

Table 3. Classification of Tool Steels

Category Designation	Letter Symbol	Group Designation
High-Speed Tool Steels	M	Molybdenum types
	T	Tungsten types
Hot-Work Tool Steels	H1–H19	Chromium types
	H20–H39	Tungsten types
	H40–H59	Molybdenum types
Cold-Work Tool Steels	D	High-carbon, high-chromium types
	A	Medium-alloy, air-hardening types
	O	Oil-hardening types
Shock-Resisting Tool Steels	S	…
Mold Steels	P	…
Special-Purpose Tool Steels	L	Low-alloy types
	F	Carbon–tungsten types
Water-Hardening Tool Steels	W	…

The following detailed discussion of tool steels will be in agreement with these categories, showing for each type the percentages of the major alloying elements. However, these values are for identification only; elements in tool steels of different producers in the mean analysis of the individual types may deviate from the listed percentages.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Classification, Approximate Compositions, and Properties Affecting Selection of Tool and Die Steels
(From SAE Recommended Practice)

Type of Tool Steel	Chemical Composition[a]								Non-warping Prop.	Safety in Hardening	Tough-ness	Depth of Hardening	Wear Resistance
	C	Mn	Si	Cr	V	W	Mo	Co					
Water Hardening													
0.80 Carbon	70–0.85	[b]	[b]	[b]	…	…	…	…	Poor	Fair	Good[c]	Shallow	Fair
0.90 Carbon	0.85–0.95	[b]	[b]	[b]	…	…	…	…	Poor	Fair	Good[c]	Shallow	Fair
1.00 Carbon	0.95–1.10	[b]	[b]	[b]	…	…	…	…	Poor	Fair	Good[c]	Shallow	Good
1.20 Carbon	1.10–1.30	[b]	[b]	[b]	…	…	…	…	Poor	Fair	Good[c]	Shallow	Good
0.90 Carbon–V	0.85–0.95	[b]	[b]	[b]	0.15–0.35	…	…	…	Poor	Fair	Good	Shallow	Fair
1.00 Carbon–V	0.95–1.10	[b]	[b]	[b]	0.15–0.35	…	…	…	Poor	Fair	Good	Shallow	Good
1.00 Carbon–VV	0.90–1.10	[b]	[b]	[b]	0.35–0.50	…	…	…	Poor	Fair	Good	Shallow	Good
Oil Hardening													
Low Manganese	0.90	1.20	0.25	0.50	0.20[d]	0.50	…	…	Good	Good	Fair	Deep	Good
High Manganese	0.90	1.60	0.25	0.35[d]	0.20[d]	…	0.30[d]	…	Good	Good	Fair	Deep	Good
High-Carbon, High-Chromium[e]	2.15	0.35	0.35	12.00	0.80[d]	0.75[d]	0.80[d]	…	Good	Good	Poor	Through	Best
Chromium	1.00	0.35	0.25	1.40	…	…	0.40	…	Fair	Good	Fair	Deep	Good
Molybdenum Graphitic	1.45	0.75	1.00	…	…	…	0.25	…	Fair	Good	Fair	Deep	Good
Nickel–Chromium[f]	0.75	0.70	0.25	0.85	0.25[d]	…	0.50[d]	…	Fair	Good	Fair	Deep	Fair
Air Hardening													
High-Carbon, High-Chromium	1.50	0.40	0.40	12.00	0.80[d]	…	0.90	0.60[d]	Best	Best	Fair	Through	Best
5 Per Cent Chromium	1.00	0.60	0.25	5.25	0.40[d]	…	1.10	…	Best	Best	Fair	Through	Good
High-Carbon, High-Chromium–Cobalt	1.50	0.40	0.40	12.00	0.80[d]	…	0.90	3.10	Best	Best	Fair	Through	Best
Shock-Resisting													
Chromium–Tungsten	0.50	0.25	0.35	1.40	0.20	2.25	0.40[d]	…	Fair	Good	Good	Deep	Fair
Silicon–Molybdenum	0.50	0.40	1.00	…	0.25[d]	…	0.50	…	Poor[g]	Poor[h]	Best	Deep	Fair
Silicon–Manganese	0.55	0.80	2.00	0.30[d]	0.25[d]	…	0.40[d]	…	Poor[g]	Poor[h]	Best	Deep	Fair
Hot Work													
Chromium–Molybdenum–Tungsten	0.35	0.30	1.00	5.00	0.25[d]	1.25	1.50	…	Good	Good	Good	Through	Fair
Chromium–Molybdenum–V	0.35	0.30	1.00	5.00	0.40	…	1.50	…	Good	Good	Good	Through	Fair
Chromium–Molybdenum–VV	0.35	0.30	1.00	5.00	0.90	…	1.50	…	Good	Good	Good	Through	Fair
Tungsten	0.32	0.30	0.20	3.25	0.40	9.00	…	…	Good	Good	Good	Through	Fair

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Classification, Approximate Compositions, and Properties Affecting Selection of Tool and Die Steels**
(From SAE Recommended Practice)

Type of Tool Steel	Chemical Composition[a]								Non-warping Prop.	Safety in Hardening	Tough-ness	Depth of Hardening	Wear Resistance
	C	Mn	Si	Cr	V	W	Mo	Co					
High Speed													
Tungsten, 18–4–1	0.70	0.30	0.30	4.10	1.10	18.00	…	…	Good	Good	Poor	Through	Good
Tungsten, 18–4–2	0.80	0.30	0.30	4.10	2.10	18.50	0.80	…	Good	Good	Poor	Through	Good
Tungsten, 18–4–3	1.05	0.30	0.30	4.10	3.25	18.50	0.70	…	Good	Good	Poor	Through	Best
Cobalt–Tungsten, 14–4–2–5	0.80	0.30	0.30	4.10	2.00	14.00	0.80	5.00	Good	Fair	Poor	Through	Good
Cobalt–Tungsten, 18–4–1–5	0.75	0.30	0.30	4.10	1.00	18.00	0.80	5.00	Good	Fair	Poor	Through	Good
Cobalt–Tungsten, 18–4–2–8	0.80	0.30	0.30	4.10	1.75	18.50	0.80	8.00	Good	Fair	Poor	Through	Good
Cobalt–Tungsten, 18–4–2–12	0.80	0.30	0.30	4.10	1.75	20.00	0.80	12.00	Good	Fair	Poor	Through	Good
Molybdenum, 8–2–1	0.80	0.30	0.30	4.00	1.15	1.50	8.50	…	Good	Fair	Poor	Through	Good
Molybdenum–Tungsten, 6–6–2	0.83	0.30	0.30	4.10	1.90	6.25	5.00	…	Good	Fair	Poor	Through	Good
Molybdenum–Tungsten, 6–6–3	1.15	0.30	0.30	4.10	3.25	5.75	5.25	…	Good	Fair	Poor	Through	Best
Molybdenum–Tungsten, 6–6–4	1.30	0.30	0.30	4.25	4.25	5.75	5.25	…	Good	Fair	Poor	Through	Best
Cobalt–Molybdenum–Tungsten, 6–6–2–8	0.85	0.30	0.30	4.10	2.00	6.00	5.00	8.00	Good	Fair	Poor	Through	Good

[a] C = carbon; Mn = manganese; Si = silicon; Cr = chromium; V = vanadium; W = tungsten; Mo = molybdenum; Co = cobalt.

[b] Carbon tool steels are usually available in four grades or qualities: *Special (Grade 1)*—The highest quality water-hardening carbon tool steel, controlled for hardenability, chemistry held to closest limits, and subject to rigid tests to ensure maximum uniformity in performance; *Extra (Grade 2)*—A high-quality water-hardening carbon tool steel, controlled for hardenability, subject to tests to ensure good service; *Standard (Grade 3)*—A good-quality water-hardening carbon tool steel, not controlled for hardenability, recommended for application where some latitude with respect to uniformity is permissible; *Commercial (Grade 4)*—A commercial-quality water-hardening carbon tool steel, not controlled for hardenability, not subject to special tests. On *special* and *extra* grades, limits on manganese, silicon, and chromium are not generally required if Shepherd hardenability limits are specified. For *standard* and *commercial* grades, limits are 0.35 max. each for Mn and Si; 0.15 max. Cr for standard; 0.20 max. Cr for commercial.

[c] Toughness decreases somewhat when increasing depth of hardening.

[d] Optional element. Steels have found satisfactory application either with or without the element present. In silicon–manganese steel listed under Shock-Resisting Steels, if chromium, vanadium, and molybdenum are not present, then hardenability will be affected.

[e] This steel may have 0.50 per cent nickel as an optional element. The steel has been found to give satisfactory application either with or without the element present.

[f] Approximate nickel content of this steel is 1.50 per cent.

[g] Poor when water quenched, fair when oil quenched.

[h] Poor when water quenched, good when oil quenched.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Quick Reference Guide for Tool Steel Selection

Application Areas	Tool Steel Categories and AISI Letter Symbol						
	High-Speed Tool Steels, M and T	Hot-Work Tool Steels, H	Cold-Work Tool Steels, D, A, and O	Shock-Resisting Tool Steels, S	Mold Steels, P	Special-Purpose Tool Steels, L and F	Water-Hardening Tool Steels, W
	Examples of Typical Applications						
Cutting Tools Single-point types (lathe, planer, boring) Milling cutters Drills Reamers Taps Threading dies Form cutters	General-purpose production tools: M2, T1 For increased abrasion resistance: M3, M4, and M10 Heavy-duty work calling for high hot hardness: T5, T15 Heavy-duty work calling for high abrasion resistance: M42, M44		Tools with keen edges (knives, razors) Tools for operations where no high-speed is involved, yet stability in heat treatment and substantial abrasion resistance are needed	Pipe cutter wheels			Uses that do not require hot hardness or high abrasion resistance. Examples with carbon content of applicable group: Taps (1.05/1.10% C) Reamers (1.10/1.15% C) Twist drills (1.20/1.25% C) Files (1.35/1.40% C)
Hot Forging Tools and Dies Dies and inserts Forging machine plungers and pierces	For combining hot hardness with high abrasion resistance: M2, T1	Dies for presses and hammers: H20, H21 For severe conditions over extended service periods: H22 to H26, also H43	Hot trimming dies: D2	Hot trimming dies Blacksmith tools Hot swaging dies			Smith's tools (1.65/0.70% C) Hot chisels (0.70/0.75% C) Drop forging dies (0.90/1.00% C) Applications limited to short-run production
Hot Extrusion Tools and Dies Extrusion dies and mandrels, Dummy blocks Valve extrusion tools	Brass extrusion dies: T1	Extrusion dies and dummy blocks: H20 to H26 For tools that are exposed to less heat: H10 to H19		Compression molding: S1			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **Quick Reference Guide for Tool Steel Selection**

Application Areas	Tool Steel Categories and AISI Letter Symbol						
	High-Speed Tool Steels, M and T	Hot-Work Tool Steels, H	Cold-Work Tool Steels, D, A, and O	Shock-Resisting Tool Steels, S	Mold Steels, P	Special-Purpose Tool Steels, L and F	Water-Hardening Tool Steels, W
	Examples of Typical Applications						
Cold-Forming Dies Bending, forming, drawing, and deep drawing dies and punches	Burnishing tools: M1, T1	Cold heading: die casting dies: H13	Drawing dies: O1 Coining tools: O1, D2 Forming and bending dies: A2 Thread rolling dies: D2	Hobbing and short-run applications: S1, S7 Rivet sets and rivet busters		Blanking, forming, and trimmer dies when toughness has precedence over abrasion resistance: L6	Cold-heading dies: W1 or W2 (C ≅ 1.00%) Bending dies: W1 (C ≅ 1.00%)
Shearing Tools Dies for piercing, punching, and trimming Shear blades	Special dies for cold and hot work: T1 For work requiring high abrasion resistance: M2, M3	For shearing knives: H11, H12 For severe hot shearing applications: M21, M25	Dies for medium runs: A2, A6 also O1 and O4 Dies for long runs: D2, D3 Trimming dies (also for hot trimming): A2	Cold and hot shear blades Hot punching and piercing tools Boilermaker's tools		Knives for work requiring high toughness: L6	Trimming dies (0.90/0.95% C) Cold blanking and punching dies (1.00% C)
Die Casting Dies and Plastics Molds		For zinc and lead: H11 For aluminum: H13 For brass: H21	A2 and A6 O1		Plastics molds: P2 to P4, and P20		
Structural Parts for Severe Service Conditions	Roller bearings for high-temperature environment: T1 Lathe centers: M2 and T1	For aircraft components (landing gear, arrester hooks, rocket cases): H11	Lathe centers: D2, D3 Arbors: O1 Bushings: A4 Gages: D2	Pawls Clutch parts		Spindles, clutch parts (where high toughness is needed): L6	Spring steel (1.10/1.15% C)
Battering Tools for Hand and Power Tool Use				Pneumatic chisels for cold work: S5 For higher performance: S7			For intermittent use: W1 (0.80% C)

Copyright 2004, Industrial Press, Inc., New York, NY

The Selection of Tool Steels for Particular Applications.— Although the advice of the specialized steel producer is often sought as a reliable source of information, the engineer is still faced with the task of selecting the tool steel. It must be realized that frequently the designation of the tool or of the process will not define the particular tool steel type best suited for the job. For that reason, tool steel selection tables naming a single type for each listed application cannot take into consideration such often conflicting work factors as ease of tool fabrication and maintenance (resharpening), productivity, product quality, and tooling cost.

When data related to past experience with tool steels for identical or similar applications are not available, a tool steel selection procedure may be followed, based on information in this Handbook section as follows:

1) Identify the AISI category that contains the sought type of steel by consulting the Quick Reference Table, Table 5, starting on page 485.

Within the defined category

a) find from the listed applications of the most frequently used types of tool steels the particular type that corresponds to the job on hand; or

b) evaluate from the table of property ratings the best compromise between any conflicting properties (e.g., compromising on wear resistance to obtain better toughness).

For those willing to refine even further the first choice or to improve on it when there is not entirely satisfactory experience in one or more meaningful respects, the identifying analyses of the different types of tool steels within each general category may provide additional guidance. In this procedure, the general discussion of the effects of different alloying elements on the properties of tool steels, in a previous section, will probably be found useful.

The following two examples illustrate the procedure for refining an original choice with the purpose of adopting a tool steel grade best suited to a particular set of conditions:

Example 1, Workpiece—Trimming Dies: For the manufacture of a type of trimming die, the first choice was grade A2, because for the planned medium rate of production, the lower material cost was considered an advantage.

A subsequent rise in the production rate indicated the use of a higher-alloy tool steel, such as D2, whose increased abrasion resistance would permit longer runs between regrinds.

A still further increase in the abrasion-resistant properties was then sought, which led to the use of D7, the high carbon and high chromium content of which provided excellent edge retainment, although at the cost of greatly reduced grindability. Finally, it became a matter of economic appraisal, whether the somewhat shorter tool regrind intervals (for D2) or the more expensive tool sharpening (for D7) constituted the lesser burden.

Example 2, Workpiece—Circular form cutter made of high-speed tool steel for use on multiple-spindle automatic turning machines: The first choice from the Table 5 may be the classical tungsten-base high-speed tool steel T1, because of its good performance and ease of heat treatment, or its alternate in the molybdenum high-speed tool steel category, the type M2.

In practice, neither of these grades provided a tool that could hold its edge and profile over the economical tool change time, because of the abrasive properties of the work material and the high cutting speeds applied in the cycle. An overrating of the problem resulted in reaching for the top of the scale, making the tool from T15, a high-alloy high-speed tool steel (high vanadium and high cobalt).

Although the performance of the tools made of T15 was excellent, the cost of this steel type was rather high, and the grinding of the tool, both for making it and in the regularly needed resharpening, proved to be very time-consuming and expensive. Therefore, an intermediate tool steel type was tried, the M3 that provided added abrasion resistance (due to increased carbon and vanadium content), and was less expensive and much easier to grind than the T15.

Copyright 2004, Industrial Press, Inc., New York, NY

High-Speed Tool Steels

The primary application of high-speed steels is to tools used for the working of metals at high cutting speeds. Cutting metal at high speed generates heat, the penetration of the cutting tool edge into the work material requires great hardness and strength, and the continued frictional contact of the tool with both the parent material and the detached chips can only be sustained by an abrasion-resistant tool edge.

Accordingly, the dominant properties of high-speed steel are a) resistance to the softening effect of elevated temperature; b) great hardness penetrating to substantial depth from the surface; and c) excellent abrasion resistance.

High-speed tool steels are listed in the AISI specifications in two groups: molybdenum types and tungsten types, these designations expressing the dominant alloying element of the respective group.

Molybdenum-Type High-Speed Tool Steels.— Unlike the traditional tungsten-base high-speed steels, the tool steels listed in this category are considered to have molybdenum as the principal alloying constituent, this element also being used in the designation of the group. Other significant elements like tungsten and cobalt might be present in equal, or even greater amounts in several types listed in this category. The available range of types also includes high-speed tool steels with higher than usual carbon and vanadium content. Amounts of these alloying elements have been increased to obtain better abrasion resistance although such a change in composition may adversely affect the machinability and the grindability of the steel. The series in whose AISI identification numbers the number 4 is the first digit was developed to attain exceptionally high hardness in heat treatment that, for these types, usually requires triple tempering rather than the double tempering generally applied for high-speed tool steels.

Frequently Used Molybdenum Types: AISI M1: This alloy was developed as a substitute for the classical T1 to save on the alloying element tungsten by replacing most of it with molybdenum. In most uses, this steel is an acceptable substitute, although it requires greater care or more advanced equipment for its heat treatment than the tungsten alloyed type it replaces. The steel is often selected for cutting tools like drills, taps, milling cutters, reamers, lathe tools used for lighter cuts, and for shearing dies.

AISI M2: Similar to M1, yet with substantial tungsten content replacing a part of the molybdenum. This is one of the general-purpose high-speed tool steels, combining the economic advantages of the molybdenum-type steels with greater ease of hardening, excellent wear resistance, and improved toughness. It is a preferred steel type for the manufacture of general-purpose lathe tools; of most categories of multiple-edge cutting tools, like milling cutters, taps, dies, reamers, and for form tools in lathe operations.

AISI M3: A high-speed tool steel with increased vanadium content for improved wear resistance, yet still below the level where vanadium would interfere with the ease of grinding. This steel is preferred for cutting tools requiring improved wear resistance, like broaches, form tools, milling cutters, chasers, and reamers.

AISI M7: The chemical composition of this type is similar to that of M1, except for the higher carbon and vanadium content that raises the cutting efficiency without materially reducing the toughness. Because of sensitivity to decarburization, heat treatment in a salt bath or a controlled atmosphere is advisable. Used for blanking and trimming dies, shear blades, lathe tools, and thread rolling dies.

AISI M10: Although the relatively high vanadium content assures excellent wear and cutting properties, the only slightly increased carbon does not cause brittleness to an extent that is harmful in many applications. Form cutters and single-point lathe tools, broaches, planer tools, punches, blanking dies, and shear blades are examples of typical uses.

AISI M42: In applications where high hardness both at regular and at elevated temperatures is needed, this type of high-speed steel with high cobalt content can provide excellent service. Typical applications are tool bits, form tools, shaving tools, fly cutters, roll turning

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Molybdenum High-Speed Steels

Identifying Chemical Composition and Typical Heat-Treatment Data																				
	AISI Type		M1	M2	M3 Cl. 1	M3 Cl. 2	M4	M6	M7	M10	M30	M33	M34	M36	M41	M42	M43	M44	M46	M47
Identifying Chemical Elements in Per Cent	C		0.80	0.85; 1.00	1.05	1.20	1.30	0.80	1.00	0.85; 1.00	0.80	0.90	0.90	0.80	1.10	1.10	1.20	1.15	1.25	1.10
	W		1.50	6.00	6.00	6.00	5.50	4.00	1.75	…	2.00	1.50	2.00	6.00	6.75	1.50	2.75	5.25	2.00	1.50
	Mo		8.00	5.00	5.00	5.00	4.50	5.00	8.75	8.00	8.00	9.50	8.00	5.00	3.75	9.50	8.00	6.25	8.25	9.50
	Cr		4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.00	4.25	3.75	3.75	4.25	4.00	3.75
	V		1.00	2.00	2.40	3.00	4.00	1.50	2.00	2.00	1.25	1.15	2.00	2.00	2.00	1.15	1.60	2.25	3.20	1.25
	Co		…	…	…	…	…	12.00	…	…	5.00	8.00	8.00	8.00	5.00	8.00	8.25	12.00	8.25	5.00
Heat-Treat. Data	Hardening Temperature Range, °F		2150–2225	2175–2225	2200–2250	2200–2250	2200–2250	2150–2200	2150–2225	2150–2225	2200–2250	2200–2250	2200–2250	2225–2275	2175–2220	2175–2210	2175–2220	2190–2240	2175–2225	2150–2200
	Tempering Temperature Range, °F		1000–1100	1000–1160	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	950–1100	950–1100	1000–1160	975–1050	975–1100
	Approx. Tempered Hardness, Rc		65–60	65–60	66–61	66–61	66–61	66–61	66–61	65–60	65–60	65–60	65–60	65–60	70–65	70–65	70–65	70–62	69–67	70–65
Relative Ratings of Properties (A = greatest to E = least)																				
Characteristics in Heat Treatment	Safety in Hardening		D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D
	Depth of Hardening		A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
	Resistance to Decarburization		C	B	B	B	B	C	C	C	C	C	C	C	C	C	C	C	C	C
	Stability of Shape in Heat Treatment	Quenching Medium: Air or Salt	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
		Quenching Medium: Oil	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D
Service Properties	Machinability		D	D	D	D/E	D	D	D	D	D	D	D	D	D	D	D	D	D	D
	Hot Hardness		B	B	B	B	B	A	B	B	A	A	A	A	A	A	A	A	A	A
	Wear Resistance		B	B	B	B	A	B	B	B	B	B	B	B	B	B	B	B	B	B
	Toughness		E	E	E	E	E	E	E	E	E	E	E	E	E	E	E	E	E	E

Copyright 2004, Industrial Press, Inc., New York, NY

tools, and thread rolling dies. Important uses are found for M42, and for other types of the "M40" group in the working of "difficult-to-machine" alloys.

Tungsten-Type High-Speed Tool Steels.— For several decades following their introduction, the tungsten-base high-speed steels were the only types available for cutting operations involving the generation of substantial heat, and are still preferred by users who do not have the kind of advanced heat-treating equipment that efficient hardening of the molybdenum-type high-speed tool steels requires. Most tungsten high-speed steels display excellent resistance to decarburization and can be brought to good hardness by simple heat treatment. However, even with tungsten-type high-speed steels, heat treatment using modern methods and furnaces can appreciably improve the metallurgical qualities of the hardened material and the performance of the cutting tools made from these steels.

Table 7. Tungsten High-Speed Tool Steels—Identifying Chemical Composition and Typical Heat-Treatment Data

AISI Type			T1	T2	T4	T5	T6	T8	T15
Identifying Chemical Elements in Per Cent									
C			0.75	0.80	0.75	0.80	0.80	0.75	1.50
W			18.00	18.00	18.00	18.00	20.00	14.00	12.00
Cr			4.00	4.00	4.00	4.00	4.50	4.00	4.00
V			1.00	2.00	1.00	2.00	1.50	2.00	5.00
Co			…	…	5.00	…	…	5.00	5.00
Heat-Treatment Data									
Hardening Temperature Range, °F			2300–2375	2300–2375	2300–2375	2325–2375	2325–2375	2300–2375	2200–2300
Tempering Temperature Range, °F			1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1100	1000–1200
Approx. Tempered Hardness, R_c			65–60	66–61	66–62	65–60	65–60	65–60	68–63
Characteristics in Heat Treatment[a]									
Safety in Hardening			C	C	D	D	D	D	D
Depth of Hardening			A	A	A	A	A	A	A
Resistance to Decarburization			A	A	B	C	C	B	B
Stability of Shape in Heat Treatment	Quenching Medium	Air or Salt	C	C	C	C	C	C	C
		Oil	D	D	D	D	D	D	D
Service Properties									
Machinability			D	D	D	D	D/E	D	D/E
Hot Hardness			B	B	A	A	A	A	A
Wear Resistance			B	B	B	B	B	B	A
Toughness			E	E	E	E	E	E	E

[a] Relative Ratings of Properties (A = greatest to E = least)

Frequently Used Tungsten Types: AISI T1: Also mentioned as the 18–4–1 type with reference to the nominal percentage of its principal alloying elements (W–Cr–V), it is considered to be the classical type of high-speed tool steel. The chemical composition of T1 was developed in the early 1900s, and has changed very little since. T1 is still considered to be perhaps the best general-purpose high-speed tool steel because of the comparative ease of its machining and heat treatment. It combines a high degree of cutting ability with relative toughness. T1 steel is used for all types of multiple-edge cutting tools like drills, reamers, milling cutters, threading taps and dies, light- and medium-duty lathe tools, and is also used for punches, dies, and machine knives, as well as for structural parts that are subjected to elevated temperatures, like lathe centers, and certain types of antifriction bearings.

AISI T2: Similar to T1 except for somewhat higher carbon content and twice the vanadium contained in the former grade. Its handling ease, both in machining and heat treating, is comparable to that of T1, although it should be held at the quenching temperature slightly longer, particularly when the heating is carried out in a controlled atmosphere furnace. The applications are similar to that of T1, however, because of its increased wear

Copyright 2004, Industrial Press, Inc., New York, NY

resistance T2 is preferred for tools required for finer cuts, and where the form or size retention of the tool is particularly important, such as for form and finishing tools.

AISI T5: The essential characteristic of this type of high-speed steel, its superior red hardness, stems from its substantial cobalt content that, combined with the relatively high amount of vanadium, provides this steel with excellent wear resistance. In heat treatment, the tendency for decarburization must be considered, and heating in a controlled, slightly reducing atmosphere is recommended. This type of high-speed tool steel is mainly used for single-point tools and inserts; it is well adapted for working at high-speeds and feeds, for cutting hard materials and those that produce discontinuous chips, also for nonferrous metals and, for all kinds of tools needed for hogging (removing great bulks of material).

AISI T15: The performance qualities of this high-alloy tool steel surpass most of those found in other grades of high-speed tool steels. The high vanadium content, supported by uncommonly high carbon assures superior cutting ability and wear resistance. The addition of high cobalt increases the "hot hardness," and therefore tools made of T15 can sustain cutting speeds in excess of those commonly applicable to tools made of steel. The machining and heat treatment of T15 does not cause extraordinary problems, although for best results, heating to high temperature is often applied in its heat treatment, and double or even triple tempering is recommended. On the other hand, T15 is rather difficult to grind because of the presence of large amounts of very hard metallic carbides; therefore, it is considered to have a very low "grindability" index. The main uses are in the field of high-speed cutting and the working of hard metallic materials, T15 being often considered to represent in its application a transition from the regular high-speed tool steels to cemented carbides. Lathe tool bits, form cutters, and solid and inserted blade milling cutters are examples of uses of this steel type for cutting tools; excellent results may also be obtained with such tools as cold-work dies, punches, blanking, and forming dies, etc. The low toughness rating of the T15 steel excludes its application for operations that involve shock or sudden variations in load.

Hot-Work Tool Steels

A family of special tool steels has been developed for tools that in their regular service are in contact with hot metals over a shorter or longer period of time, with or without cooling being applied, and are known as hot-work steels. The essential property of these steels is their capability to sustain elevated temperature without seriously affecting the usefulness of the tools made from them. Depending on the purpose of the tools for which they were developed, the particular types of hot-work tool steels have different dominant properties and are assigned to one of three groups, based primarily on their principal alloying elements.

Hot-Work Tool Steels, Chromium Types.— As referred to in the group designation, the chromium content is considered the characteristic element of these tool steels. Their predominant properties are high hardenability, excellent toughness, and great ductility, even at the cost of wear resistance. Some members of this family are made with the addition of tungsten, and in one type, cobalt as well. These alloying elements improve the resistance to the softening effect of elevated temperatures, but reduce ductility.

Frequently Used Chromium Types: AISI H11: This hot-work tool steel of the Chromium–molybdenum–vanadium type has excellent ductility, can be machined easily, and retains its strength at temperatures up to 1000 degrees F.

These properties, combined with relatively good abrasion and shock resistance, account for the varied fields of application of H11, which include the following typical uses: a) structural applications where high strength is needed at elevated operating temperatures, as for gas turbine engine components; and b) hot-work tools, particularly of the kind whose service involves shocks and drastic cooling of the tool, such as in extrusion tools, pierce and draw punches, bolt header dies, etc.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Hot-Work Tool Steels

Identifying Chemical Composition and Typical Heat-Treatment Data																	
AISI	Group			Chromium Types						Tungsten Types						Molybdenum Types		
	Type			H10	H11	H12	H13	H14	H19	H21	H22	H23	H24	H25	H26	H41	H42	H43
Identifying Chemical Elements in Per Cent	C			0.40	0.35	0.35	0.35	0.40	0.40	0.35	0.35	0.35	0.45	0.25	0.50	0.65	0.60	0.55
	W			…	…	1.50	…	5.00	4.25	9.00	11.00	12.00	15.00	15.00	18.00	1.50	6.00	…
	Mo			2.50	1.50	1.50	1.50	…	…	…	…	…	…	…	…	8.00	5.00	8.00
	Cr			3.25	5.00	5.00	5.00	5.00	4.25	3.50	2.00	12.00	3.00	4.00	4.00	4.00	4.00	4.00
	V			0.40	0.40	0.40	1.00	…	2.00	…	…	…	…	…	1.00	1.00	2.00	2.00
	Co			…	…	…	…	…	4.25	…	…	…	…	…	…	…	…	…
Heat-Treat. Data	Hardening Temperature Range, °F			1850–1900	1825–1875	1825–1875	1825–1900	1850–1950	2000–2200	2000–2200	2000–2200	2000–2300	2000–2250	2100–2300	2150–2300	2000–2175	2050–2225	2000–2175
	Tempering Temperature Range, °F			1000–1200	1000–1200	1000–1200	1000–1200	1100–1200	1000–1300	1100–1250	1100–1250	1200–1500	1050–1200	1050–1250	1050–1250	1050–1200	1050–1200	1050–1200
	Approx. Tempered Hardness, Rc			56–39	54–38	55–38	53–38	47–40	59–40	54–36	52–39	47–30	55–45	44–35	58–43	60–50	60–50	58–45
Relative Ratings of Properties (A = greatest to D = least)																		
Characteristics in Heat Treatment	Safety in Hardening			A	A	A	A	A	B	B	B	B	B	B	B	C	C	C
	Depth of Hardening			A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
	Resistance to Decarburization			B	B	B	B	B	B	B	B	B	B	B	B	C	B	C
	Stability of Shape in Heat Treatment	Quenching Medium	Air or Salt	B	B	B	B	C	C	C	C	…	C	C	C	C	C	C
			Oil	…	…	…	…	…	D	D	D	D	D	D	D	D	D	D
Service Properties	Machinability			C/D	C/D	C/D	C/D	D	D	D	D	D	D	D	D	D	D	D
	Hot Hardness			C	C	C	C	C	C	C	C	B	B	B	B	B	B	B
	Wear Resistance			D	D	D	D	D	C/D	C/D	C/D	C/D	C	D	C	C	C	C
	Toughness			C	B	B	B	C	C	C	C	D	D	C	D	D	D	D

Copyright 2004, Industrial Press, Inc., New York, NY

AISI H12: The properties of this type of steel are comparable to those of H11, with increased abrasion resistance and hot hardness, resulting from the addition of tungsten, yet in an amount that does not affect the good toughness of this steel type. The applications, based on these properties, are hot-work tools that often have to withstand severe impact, such as various punches, bolt header dies, trimmer dies, and hot shear blades. H12 is also used to make aluminum extrusion dies and die-casting dies.

AISI H13: This type of tool steel differs from the preceding ones particularly in properties related to the addition of about 1 per cent vanadium, which contributes to increased hot hardness, abrasion resistance, and reduced sensitivity to heat checking. Such properties are needed in die casting, particularly of aluminum, where the tools are subjected to drastic heating and cooling at high operating temperatures. Besides die-casting dies, H13 is also widely used for extrusion dies, trimmer dies, hot gripper and header dies, and hot shear blades.

AISI H19: This high-alloyed hot-work tool steel, containing chromium, tungsten, cobalt, and vanadium, has excellent resistance to abrasion and shocks at elevated temperatures. It is particularly well adapted to severe hot-work uses where the tool, to retain its size and shape, must withstand wear and the washing-out effect of molten work material. Typical applications include brass extrusion dies and dummy blocks, inserts for forging and valve extrusion dies, press forging dies, and hot punches.

Hot-Work Tool Steels, Tungsten Types.— Substantial amounts of tungsten, yet very low-carbon content characterize the hot-work tool steels of this group. These tool steels have been developed for applications where the tool is in contact with the hot-work material over extended periods of time; therefore, the resistance of the steel to the softening effect of elevated temperatures is of prime importance. even to the extent of accepting a lower degree of toughness.

Frequently Used Tungsten Types: AISI H21: This medium-tungsten alloyed hot-work tool steel has substantially increased abrasion resistance over the chromium alloyed types, yet possesses a degree of toughness that represents a transition between the chromium and the higher-alloyed tungsten-steel types. The principal applications are for tools subjected to continued abrasion, yet to only a limited amount of shock loads, like tools for the extrusion of brass, both dies and dummy blocks, pierces for forging machines, inserts for forging tools, and hot nut tools. Another typical application is dies for the hot extrusion of automobile valves.

AISI H24: The comparatively high tungsten content (about 14 per cent) of this steel results in good hardness, great compression strength, and excellent abrasion resistance, but makes it sensitive to shock loads. By taking these properties into account, the principal applications include extrusion dies for brass in long-run operations, hot-forming and gripper dies with shallow impressions, punches that are subjected to great wear yet only to moderate shocks, and hot shear blades.

AISI H20: The composition of this high-alloyed tungsten-type hot-work steel resembles the tungsten-type high-speed steel AISI T1, except for the somewhat lower carbon content for improved toughness. The high amount of tungsten provides the maximum resistance to the softening effect of elevated temperature and assures excellent wear-resistant properties, including withstanding the washing-out effect of certain processes. However, this steel is less resistant to thermal shocks than the chromium hot-work steels. Typical applications comprise extrusion dies for long production runs, extrusion mandrels operated without cooling, hot piercing punches, hot forging dies and inserts. It is also used as special structural steel for springs operating at elevated temperatures.

Hot-Work Tool Steels, Molybdenum Types.— These steels are closely related to certain types of molybdenum high-speed steels and possess excellent resistance to the softening effect of elevated temperature but their ductility is rather low. These steel types are generally available on special orders only.

Copyright 2004, Industrial Press, Inc., New York, NY

Frequently Used Molybdenum Types: AISI H43: The principal constituents of this hot-work steel, chromium, molybdenum, and vanadium, provide excellent abrasion- and wear-resistant properties at elevated temperatures. H43 has a good resistance to the development of heat checks and a toughness adequate for many different purposes. Applications include tools and operations that tend to cause surface wear in high-temperature work, like hot headers, punch and die inserts, hot heading and hot nut dies, as well as different kinds of punches operating at high temperature in service involving considerable wear.

Cold-Work Tool Steels

Tool steels of the cold-working category are primarily intended for die work, although their use is by no means restricted to that general field. Cold-work tool steels are extensively used for tools whose regular service does not involve elevated temperatures. They are available in chemical compositions adjusted to the varying requirements of a wide range of different applications. According to their predominant properties, characterized either by the chemical composition or by the quenching medium in heat treatment, the cold-work tool steels are assigned to three different groups, as discussed in what follows.

Cold-Work Tool Steels, High-Carbon, High-Chromium Types.— The chemical composition of tool steels of this family is characterized by the very high chromium content, to the order of 12 to 13 per cent, and the uncommonly high carbon content, in the range of about 1.50 to 2.30 per cent. Additional alloying elements that are present in different amounts in some of the steel types of this group are vanadium, molybdenum, and cobalt, each of which contributes desirable properties.

The predominant properties of the whole group are: 1) excellent dimensional stability in heat treatment, where, with one exception, air quench is used; 2) great wear resistance, particularly in the types with the highest carbon content; and 3) rather good machinability.

Frequently Used High-Carbon, High-Chromium Types: AISI D2: An air-hardening die steel with high-carbon, high-chromium content having several desirable tool steel properties, such as abrasion resistance. high hardness, and nondeforming characteristics. The carbon content of this type, although relatively high, is not particularly detrimental to its machining. The ease of working can be further improved by selecting the same basic type with the addition of sulfur. Several steel producers supply the sulfurized version of D2, in which the uniformly distributed sulfide particles substantially improve the machinability and the resulting surface finish. The applications comprise primarily cold-working press tools for shearing (blanking and stamping dies, punches, shear blades), for forming (bending, seaming), also for thread rolling dies, solid gages, and wear-resistant structural parts. Dies for hot trimming of forgings are also made of D2 which is then heated treated to a lower hardness for the purpose of increasing toughness.

AISI D3: The high carbon content of this high-chromium tool steel type results in excellent resistance to wear and abrasion and provides superior compressive strength as long as the pressure is applied gradually, without exerting sudden shocks. In hardening, an oil quench is used, without affecting the excellent nondeforming properties of this type. Its deep-hardening properties make it particularly suitable for tools that require repeated regrinding during their service life, such as different types of dies and punches. The more important applications comprise blanking, stamping, and trimming dies and punches for long production runs; forming, bending and drawing tools; and structural elements like plug and ring gages, and lathe centers, in applications where high wear resistance is important.

Cold-Work Tool Steels, Oil-Hardening Types.— With a relatively low percentage of alloying elements, yet with a substantial amount of manganese, these less expensive types of tool steels attain good depth of hardness in an oil quench, although at the cost of reduced resistance to deformation. Their good machinability supports general-purpose applica-

Copyright 2004, Industrial Press, Inc., New York, NY

tions, yet because of relatively low wear resistance, they are mostly selected for comparatively short-run work.

Frequently Used Oil-Hardening Types: AISI O1: A low-alloy tool steel that is hardened in oil and exhibits only a low tendency to shrinking or warping. It is used for cutting tools, the operation of which does not generate high heat, such as taps and threading dies, reamers, and broaches, and for press tools like blanking, trimming, and forming dies in short- or medium-run operations.

AISI O2: Manganese is the dominant alloying element in this type of oil-hardening tool steel that has good nondeforming properties, can be machined easily, and performs satisfactorily in low-volume production. The low hardening temperature results in good safety in hardening, both with regard to form stability and freedom from cracking. The combination of handling ease, including free-machining properties, with good wear resistance, makes this type of tool steel adaptable to a wide range of common applications such as cutting tools for low- and medium-speed operations; forming tools including thread rolling dies; structural parts such as bushings and fixed gages, and for plastics molds.

AISI O6: This oil-hardening type of tool steel belongs to a group often designated as graphitic because of the presence of small particles of graphitic carbon that are uniformly dispersed throughout the steel. Usually, about one-third of the total carbon is present as free graphite in nodular form, which contributes to the uncommon ease of machining. In the service of parts made of this type of steel, the free graphite acts like a lubricant, reducing wear and galling. The ease of hardening is also excellent, requiring only a comparatively low quenching temperature. Deep hardness penetration is produced and the oil quench causes very little dimensional change. The principal applications of the O6 tool steel are in the field of structural parts, like arbors, bushings, bodies for inserted tool cutters, and shanks for cutting tools, jigs, and machine parts, and fixed gages like plugs, rings, and snap gages. It is also used for blanking, forming, and trimming dies and punches, in applications where the stability of the tool material is more important than high wear resistance.

Cold-Work Tool Steels, Medium-Alloy, Air-Hardening Types.— The desirable nondeforming properties of the high-chromium types are approached by the members of this family, with substantially lower alloy content that, however, is sufficient to permit hardening by air quenching. The machinability is good, and the comparatively low wear resistance is balanced by relatively high toughness, a property that, in certain applications, may be considered of prime importance.

Frequently Used Medium-Alloy, Air-Hardening Types: AISI A2: The lower chromium content, about 5 per cent, makes this air-hardening tool steel less expensive than the high-chromium types, without affecting its nondeforming properties. The somewhat reduced wear resistance is balanced by greater toughness, making this type suitable for press work where the process calls for tough tool materials. The machinability is improved by the addition of about 0.12 percent sulfur, offered as a variety of the basic composition by several steel producers. The prime uses of this tool steel type are punches for blanking and forming, cold and hot trimming dies (the latter heat treated to a lower hardness), thread rolling dies, and plastics molds.

AISI A6: The composition of this type of tool steel makes it adaptable to air hardening from a relatively low temperature, comparable to that of oil-hardening types, yet offering improved stability in heat treating. Its reduced tendency to heat-treatment distortions makes this tool steel type well adapted for die work, forming tools, and gages, which do not require the highest degree of wear resistance.

Shock-Resisting, Mold, and Special-Purpose Tool Steels

There are fields of tool application in which specific properties of the tool steels have dominant significance, determining to a great extent the performance and the service life of tools made of these materials. To meet these requirements, special types of tool steels

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Cold-Work Tool Steels

Identifying Chemical Composition and Typical Heat-Treatment Data																		
AISI	Group	High-Carbon, High-Chromium Types					Medium-Alloy, Air-Hardening Types								Oil-Hardening Types			
	Types	D2	D3	D4	D5	D7	A2	A3	A4	A6	A7	A8	A9	A10	O1	O2	O6	O7
Identifying Chemical Elements in Per Cent	C	1.50	2.25	2.25	1.50	2.35	1.00	1.25	1.00	0.70	2.25	0.55	0.50	1.35	0.90	0.90	1.45	1.20
	Mn	…	…	…	…	…	…	…	2.00	2.00	…	…	…	1.80	1.00	1.60	…	…
	Si	…	…	…	…	…	…	…	…	…	…	…	…	1.25	…	…	1.00	…
	W	…	…	…	…	…	…	…	…	…	1.00	1.25	…	…	0.50	…	…	1.75
	Mo	1.00	…	1.00	1.00	1.00	1.00	1.00	1.00	1.25	1.00	1.25	1.40	1.50	…	…	0.25	…
	Cr	12.00	12.00	12.00	12.00	12.00	5.00	5.00	1.00	1.00	5.25	5.00	5.00	…	0.50	…	…	0.75
	V	1.00	…	…	…	4.00	…	1.00	…	…	4.75	…	1.00	…	…	…	…	…
	Co	…	…	…	3.00	…	…	…	…	…	…	…	…	…	…	…	…	…
Heat-Treatment Data	Ni	…	…	…	…	…	…	…	…	…	…	…	1.50	1.80	…	…	…	…
	Hardening Temperature Range, °F	1800–1875	1700–1800	1775–1850	1800–1875	1850–1950	1700–1800	1750–1850	1500–1600	1525–1600	1750–1800	1800–1850	1800–1875	1450–1500	1450–1500	1400–1475	1450–1500	1550–1525
	Quenching Medium	Air	Oil	Air	Air	Air	Air	Air	Air	Air	Air	Air	Air	Air	Oil	Oil	Oil	Oil
	Tempering Temperature Range, °F	400–1000	400–1000	400–1000	400–1000	300–1000	350–1000	350–1000	350–800	300–800	300–1000	350–1100	950–1150	350–800	350–500	350–500	350–600	350–550
	Approx. Tempered Hardness, Rc	61–54	61–54	61–54	61–54	65–58	62–57	65–57	62–54	60–54	67–57	60–50	56–35	62–55	62–57	62–57	63–58	64–58
Relative Ratings of Properties (A = greatest to E = least)																		
Characteristics in Heat Treatment	Safety in Hardening	A	C	A	A	A	A	A	A	A	A	A	A	A	B	B	B	B
	Depth of Hardening	A	A	A	A	A	A	A	A	A	A	A	A	A	B	B	B	B
	Resistance to Decarburization	B	B	B	B	B	B	B	A/B	A/B	B	B	B	A/B	A	A	A	A
	Stability of Shape in Heat Treatment	A	B	A	A	A	A	A	A	A	A	A	A	A	B	B	B	B
Service Properties	Machinability	E	E	E	E	E	D	D	D/E	D/E	E	D	D	C/D	C	C	B	C
	Hot Hardness	C	C	C	C	C	C	C	D	D	C	C	C	D	E	E	E	E
	Wear Resistance	B/C	B	B	B/C	A	C	B	C/D	C/D	A	C/D	C/D	C	D	D	D	D
	Toughness	E	E	E	E	E	D	D	D	D	E	C	C	D	D	D	D	C

Copyright 2004, Industrial Press, Inc., New York, NY

have been developed. These individual types grew into families with members that, while similar in their major characteristics, provide related properties to different degrees. Originally developed for a specific use, the resulting particular properties of some of these tool steels made them desirable for other uses as well. In the tool steel classification system, they are shown in three groups, as discussed in what follows.

Shock-Resisting Tool Steels.— These steels are made with low-carbon content for increased toughness, even at the expense of wear resistance, which is generally low. Each member of this group also contains alloying elements, different in composition and amount, selected to provide properties particularly adjusted to specific applications. Such varying properties are the degree of toughness (generally, high in all members), hot hardness, abrasion resistance, and machinability.

Properties and Applications of Frequently Used Shock-Resisting Types: AISI S1: This Chromium–tungsten alloyed tool steel combines, in its hardened state, great toughness with high hardness and strength. Although it has a low-carbon content for reasons of good toughness, the carbon-forming alloys contribute to deep hardenability and abrasion resistance. When high wear resistance is also required, this property can be improved by carburizing the surface of the tool while still retaining its shock-resistant characteristics. Primary uses are for battering tools, including hand and pneumatic chisels. The chemical composition, particularly the silicon and tungsten content, provides good hot hardness, too, up to operating temperatures of about 1050 °F, making this tool steel type also adaptable for such hot-work tool applications involving shock loads, as headers, pierces, forming tools, drop forge die inserts, and heavy shear blades.

AISI S2: This steel type serves primarily for hand chisels and pneumatic tools, although it also has limited applications for hot work. Although its wear-resistance properties are only moderate, S2 is sometimes used for forming and thread rolling applications, when the resistance to rupturing is more important than extended service life. For hot-work applications, this steel requires heat treatment in a neutral atmosphere to avoid either carburization or decarburization of the surface. Such conditions make this tool steel type particularly susceptible to failure in hot-work uses.

AISI S5: This composition is essentially a Silicon–manganese type tool steel with small additions of chromium, molybdenum, and vanadium for the purpose of improved deep hardening and refinement of the grain structure. The most important properties of this steel are its high elastic limit and good ductility, resulting in excellent shock-resisting characteristics, when used at atmospheric temperatures. Its recommended quenching medium is oil, although a water quench may also be applied as long as the design of the tools avoids sharp corners or drastic sectional changes. Typical applications include pneumatic tools in severe service, like chipping chisels, also shear blades, heavy-duty punches, and bending rolls. Occasionally, this steel is also used for structural applications, like shanks for carbide tools and machine parts subject to shocks.

Mold Steels.— These materials differ from all other types of tool steels by their very low-carbon content, generally requiring carburizing to obtain a hard operating surface. A special property of most steel types in this group is the adaptability to shaping by impression (hobbing) instead of by conventional machining. They also have high resistance to decarburization in heat treatment and dimensional stability, characteristics that obviate the need for grinding following heat treatment. Molding dies for plastics materials require an excellent surface finish, even to the degree of high luster; the generally high-chromium content of these types of tool steels greatly aids in meeting this requirement.

Properties and Applications of Frequently Used Mold Steel Types: AISI P3 and P4:

Essentially, both types of tool steels were developed for the same special purpose, that is, the making of plastics molds. The application conditions of plastics molds require high core strength, good wear resistance at elevated temperature, and excellent surface finish. Both types are carburizing steels that possess good dimensional stability. Because hob-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Shock-Resisting, Mold, and Special-Purpose Tool Steels

Identifying Chemical Composition and Typical Heat-Treatment Data																	
AISI	Category		Shock-Resisting Tool Steels				Mold Steels							Special-Purpose Tool Steels				
	Types		S1	S2	S5	S7	P2	P3	P4	P5	P6	P20	P21[a]	L2[b]	L3[b]	L6	F1	F2
Identifying Elements in Per Cent	C		0.50	0.50	0.55	0.50	0.07	0.10	0.07	0.10	0.10	0.35	0.20	0.50/ 1.10	1.00	0.70	1.00	1.25
	Mn		…	…	0.80	…	…	…	…	…	…	…	…	…	…	…	…	…
	Si		…	1.00	2.00	…	…	…	…	…	…	…	…	…	…	…	…	…
	W		2.50	…	…	…	…	…	…	…	…	…	…	…	…	…	1.25	3.50
	Mo		…	0.50	0.40	1.40	0.20	…	0.75	…	…	0.40	…	…	…	0.25	…	…
	Cr		1.50	…	…	3.25	2.00	0.60	5.00	2.25	1.50	1.25	…	1.00	1.50	0.75	…	…
	V		…	…	…	…	…	…	…	…	…	…	…	0.20	0.20	…	…	…
	Ni		…	…	…	…	0.50	1.25	…	…	3.50	…	4.00	…	…	1.50	…	…
Heat-Treat. Data	Hardening Temperature, °F		1650–1750	1550–1650	1600–1700	1700–1750	1525–1550[c]	1475–1525[c]	1775–1825[c]	1550–1600[c]	1450–1500[c]	1500–1600[c]	Soln. treat.	1550–1700	1500–1600	1450–1550	1450–1600	1450–1600
	Tempering Temp. Range, °F		400–1200	350–800	350–800	400–1150	350–500	350–500	350–900	350–500	350–450	900–1100	Aged	350–1000	350–600	350–1000	350–500	350–500
	Approx. Tempered Hardness, Rc		58–40	60–50	60–50	57–45	64–58[d]	64–58[d]	64–58[d]	64–58[d]	61–58[d]	37–28[d]	40–30	63–45	63–56	62–45	64–60	65–62
Relative Ratings of Properties (A = greatest to E = least)																		
Characteristics in Heat Treatment	Safety in Hardening		C	E	C	B/C	C	C	C	C	C	C	A	D	D	C	E	E
	Depth of Hardening		B	B	B	A	B[e]	B[e]	B[e]	B[e]	A[e]	B	A	B	B	B	C	C
	Resist. to Decarb.		B	C	C	B	A	A	A	A	A	A	A	A	A	A	A	A
	Stability of Shape in Heat Treatment	Quench. Med. Air	…	…	…	A	…	…	B	…	B	C	A	…	…	…	…	…
		Oil	D	…	D	C	C	C	…	C	C	…	A	D	D	C	…	…
		Water[f]	…	E	…	…	…	…	…	E	…	…	…	E	E	…	E	E
Service Properties	Machinability		D	C/D	C/D	D	C/D	D	D/E	D	D	C/D	D	C	C	D	C	D
	Hot Hardness		D	E	E	C	E	E	D	E	E	E	D	E	E	E	E	E
	Wear Resistance		D/E	D/E	D/E	D/E	D	D	C	D	D	D/E	D	D/E	D	D	D	B/C
	Toughness		B	A	A	B	C	C	C	C	C	C	D	B	D	B	E	E

[a] Contains also about 1.20 per cent A1. Solution treated in hardening.
[b] Quenched in oil.
[c] After carburizing.
[d] Carburized case.
[e] Core hardenability.
[f] Sometimes brine is used.

Copyright 2004, Industrial Press, Inc., New York, NY

bing, that is, sinking the cavity by pressing a punch representing the inverse replica of the cavity into the tool material, is the process by which many plastics mold cavities are produced, good "hobbability" of the tool steels used for this purpose is an important requirement. The different chemistry of these two types of mold steels is responsible for the high core hardness of the P4, which makes it better suited for applications requiring high strength at elevated temperature.

AISI P6: This nickel–chromium-type plastics mold steel has exceptional core strength and develops a deep carburized case. Due to the high nickel–chromium content, the cavities of molds made of this steel type are produced by machining rather than by hobbing. An outstanding characteristic of this steel type is the high luster that is produced by polishing of the hard case surface.

AISI P20: This general-type mold steel is adaptable to both through hardening and carburized case hardening. In through hardening, an oil quench is used and a relatively lower, yet deeply penetrating hardness is obtained, such as is needed for zinc die-casting dies and injection molds for plastics. After the direct quenching and tempering, carburizing produces a very hard case and comparatively high core hardness. When thus heat treated, this steel is particularly well adapted for making compression, transfer, and plunger-type plastics molds.

Special-Purpose Tool Steels.— These steels include several low-alloy types of tool steels that were developed to provide transitional types between the more commonly used basic types of tool steels, and thereby contribute to the balancing of certain conflicting properties such as wear resistance and toughness; to offer intermediate depth of hardening; and to be less expensive than the higher-alloyed types of tool steels.

Properties and Applications of Frequently Used Special-Purpose Types: AISI L6: This material is a low-alloy-type special-purpose tool steel. The comparatively safe hardening and the fair nondeforming properties, combined with the service advantage of good toughness in comparison to most other oil-hardening types, explains the acceptance of this steel with a rather special chemical composition. The uses of L6 are for tools whose toughness requirements prevail over abrasion-resistant properties, such as forming rolls and forming and trimmer dies in applications where combinations of moderate shock- and wear-resistant properties are sought. The areas of use also include structural parts, like clutch members, pawls, and knuckle pins, that must withstand shock loads and still display good wear properties.

AISI F2: This carbon–tungsten type is one of the most abrasion-resistant of all water-hardening tool steels. However, it is sensitive to thermal changes, such as are involved in heat treatment and it is also susceptible to distortions. Consequently, its use is limited to tools of simple shape in order to avoid cracking in hardening. The shallow hardening characteristics of F2 result in a tough core and are desirable properties for certain tool types that, at the same time, require excellent wear-resistant properties.

Water-Hardening Tool Steels.— Steel types in this category are made without, or with only a minimum amount of alloying elements and, their heat treatment needs the harsh quenching action of water or brine, hence the general designation of the category.

Water-hardening steels are usually available with different percentages of carbon, to provide properties required for different applications; the classification system lists a carbon range of 0.60 to 1.40 per cent. In practice, however, the steel mills produce these steels in a few varieties of differing carbon content, often giving proprietary designations to each particular group. Typical carbon content limits of frequently used water-hardening tool steels are 0.70–0.90, 0.90–1.10, 1.05–1.20, and 1.20–1.30 per cent. The appropriate group should be chosen according to the intended use, as indicated in the steel selection guide for this category, keeping in mind that whereas higher carbon content results in deeper hardness penetration, it also reduces toughness.

The general system distinguishes the following four grades, listed in the order of decreasing quality: 1) special; 2) extra; 3) standard; and 4) commercial.

Copyright 2004, Industrial Press, Inc., New York, NY

The differences between these grades, which are not offered by all steel mills, are defined in principle only. The distinguishing characteristics are purity and consistency, resulting from different degrees of process refinement and inspection steps applied in making the steel. Higher qualities are selected for assuring dependable uniformity and performance of the tools made from the steel.

The groups with higher carbon content are more sensitive to heat-treatment defects and are generally used for the more demanding applications, so the better grades are usually chosen for the high-carbon types and the lower grades for applications where steels with lower carbon content only are needed.

Water-hardening tool steels, although the least expensive, have several drawbacks, but these are quite acceptable in many types of applications. Some limiting properties are the tendency to deformation in heat treatment due to harsh effects of the applied quenching medium, the sensitivity to heat during the use of the tools made of these steels, the only fair degree of toughness, and the shallow penetration of hardness. However, this last-mentioned property may prove a desirable characteristic in certain applications, such as cold-heading dies, because the relatively shallow hard case is supported by the tough, although softer core.

The AISI designation for water-hardening tool steels is W, followed by a numeral indicating the type, primarily defined by the chemical composition, as shown in Table 11.

Table 11. Water-Hardening Tool Steels—Identifying Chemical Composition and Heat-Treatment Data

Chemical Composition in Per Cent	AISI Types		
	W1	W2	W5
C	0.60–1.40	0.60–1.40	1.10
	Varying carbon content may be available		
V	…	0.25	…
Cr	These elements are adjusted to satisfy the hardening requirements		0.50
Mn			
Si			

Heat-Treatment Data		
Hardening TemperatureRanges, °F Varying with Carbon Content	0.60–0.80%	1450–1500
	0.85–1.05%	1425–1550
	1.10–1.40%	1400–1525
Quenching Medium		Brine or Water
Tempering Temperature Range, °F		350–650
Approx. Tempered Hardness, Rc		64–50

Relative Ratings of Properties (A = greatest to E = least)							
Characteristics in Heat Treatment				Service Properties			
Safety in Hardening	Depth of Hardening	Resistance to Decarburization	Stability of Shape in Heat Treatment	Machinability	Hot Hardness	Wear Resistance	Toughness
D	C	A	E	A	E	D/E	C/D

Water-Hardening Type W1 (Plain Carbon) Tool Steels, Recommended Applications:

Group I (C-0.70 to 0.90%): This group is relatively tough and therefore preferred for tools that are subjected to shocks or abusive treatment. Used for such applications as: hand tools, chisels, screwdriver blades, cold punches, and nail sets, and fixture elements, vise jaws, anvil faces, and chuck jaws.

Group II (C-0.90 to 1.10%): This group combines greater hardness with fair toughness, resulting in improved cutting capacity and moderate ability to sustain shock loads. Used for such applications as: hand tools, knives, center punches, pneumatic chisels, cutting tools, reamers, hand taps, and threading dies, wood augers; die parts, drawing and heading dies, shear knives, cutting and forming dies; and fixture elements, drill bushings, lathe centers, collets, and fixed gages.

Copyright 2004, Industrial Press, Inc., New York, NY

Group III (C-1.05 to 1.20%): The higher carbon content of this group increases the depth of hardness penetrations, yet reduces toughness, thus the resistance to shock loads. Preferred for applications where wear resistance and cutting ability are the prime considerations. Used for such applications as: hand tools, woodworking chisels, paper knives, cutting tools (for low-speed applications), milling cutters, reamers, planer tools, thread chasers, center drills, die parts, cold blanking, coining, bending dies.

Group IV (C-1.20 to 1–30%): The high carbon content of this group produces a hard case of considerable depth with improved wear resistance yet sensitive to shock and concentrated stresses. Selected for applications where the capacity to withstand abrasive wear is needed, and where the retention of a keen edge or the original shape of the tool is important. Used for such applications as: cutting tools for finishing work, like cutters and reamers, and for cutting chilled cast iron and forming tools, for ferrous and nonferrous metals, and burnishing tools.

By adding small amounts of alloying elements to W-steel types 2 and 5, certain characteristics that are desirable for specific applications are improved. The vanadium in type 2 contributes to retaining a greater degree of fine-grain structure after heat treating. Chromium in type 5 improves the deep-hardening characteristics of the steel, a property needed for large sections, and assists in maintaining the keen cutting edge that is desirable in cutting tools like broaches, reamers, threading taps, and dies.

Mill Production Forms of Tool Steels

Tool steels are produced in many different forms, but not all those listed in the following are always readily available; certain forms and shapes are made for special orders only.

Hot-Finished Bars and Cold-Finished Bars: These bars are the most commonly produced forms of tool steels. Bars can be furnished in many different cross-sections, the round shape being the most common. Sizes can vary over a wide range, with a more limited number of standard stock sizes. Various conditions may also be available, however, technological limitations prevent all conditions applying to every size, shape, or type of steel. Tool steel bars may be supplied in one of the following conditions and surface finishes:

Conditions: Hot-rolled or forged (natural); hot-rolled or forged and annealed; hot-rolled or forged and heat-treated; cold- or hot-drawn (as drawn); and cold- or hot-drawn and annealed.

Finishes: Hot-rolled finish (scale not removed); pickled or blast-cleaned; cold-drawn; turned or machined; rough ground; centerless ground or precision flat ground; and polished (rounds only).

Other forms in which tool steels are supplied are the following:

Rolled or Forged Special Shapes: These shapes are usually produced on special orders only, for the purpose of reducing material loss and machining time in the large-volume manufacture of certain frequently used types of tools.

Forgings: All types of tool steels may be supplied in the form of forgings, that are usually specified for special shapes and for dimensions that are beyond the range covered by bars.

Wires: Tool steel wires are produced either by hot or cold drawing and are specified when special shapes, controlled dimensional accuracy, improved surface finish, or special mechanical properties are required. Round wire is commonly produced within an approximate size range of 0.015 to 0.500 inch, and these dimensions also indicate the limits within which other shapes of tool steel wires, like oval, square, or rectangular, may be produced.

Drill Rods: Rods are produced in round, rectangular, square, hexagonal, and octagonal shapes, usually with tight dimensional tolerances to eliminate subsequent machining, thereby offering manufacturing economies for the users.

Hot-Rolled Plates and Sheets, and Cold-Rolled Strips: Such forms of tool steel are generally specified for the high-volume production of specific tool types.

Copyright 2004, Industrial Press, Inc., New York, NY

Tool Bits: These pieces are semifinished tools and are used by clamping in a tool holder or shank in a manner permitting ready replacement. Tool bits are commonly made of high-speed types of tool steels, mostly in square, but also in round, rectangular, and other shapes. Tool bits are made of hot rolled bars and are commonly, yet not exclusively, supplied in hardened and ground form, ready for use after the appropriate cutting edges are ground, usually in the user's plant.

Hollow Bars: These bars are generally produced by trepanning, boring, or drilling of solid round rods and are used for making tools or structural parts of annular shapes, like rolls, ring gages, bushings, etc.

Tolerances of Dimensions.— Such tolerances have been developed and published by the American Iron and Steel Institute (AISI) as a compilation of available industry experience that, however, does not exclude the establishment of closer tolerances, particularly for hot rolled products manufactured in large quantities. The tolerances differ for various categories of production processes (e.g., forged, hot-rolled, cold-drawn, centerless ground) and of general shapes.

Allowances for Machining.— These allowances provide freedom from soft spots and defects of the tool surface, thereby preventing failures in heat treatment or in service. After a layer of specific thickness, known as the allowance, has been removed, the bar or other form of tool steel material should have a surface without decarburization and other surface defects, such as scale marks or seams. The industry wide accepted machining allowance values for tool steels in different conditions, shapes, and size ranges are spelled out in AISI specifications and are generally also listed in the tool steel catalogs of the producer companies.

Decarburization Limits.— Heating of steel for production operation causes the oxidation of the exposed surfaces resulting in the loss of carbon. That condition, called decarburization, penetrates to a certain depth from the surface, depending on the applied process, the shape and the dimensions of the product. Values of tolerance for decarburization must be considered as one of the factors for defining the machining allowances, which must also compensate for expected variations of size and shape, the dimensional effects of heat treatment, and so forth. Decarburization can be present not only in hot-rolled and forged, but also in rough turned and cold-drawn conditions.

Advances in Tool Steel Making Technology.— Significant advances in processes for tool steel production have been made that offer more homogeneous materials of greater density and higher purity for applications where such extremely high quality is required. Two of these methods of tool steel production are of particular interest.

Vacuum-melted tool steels: These steels are produced by the consumable electrode method, which involves remelting of the steel originally produced by conventional processes. Inside a vacuum-tight shell that has been evacuated, the electrode cast of tool steel of the desired chemical analysis is lowered into a water-cooled copper mold where it strikes a low-voltage, high-amperage arc causing the electrode to be consumed by gradual melting. The undesirable gases and volatiles are drawn off by the vacuum, and the inclusions float on the surface of the pool, accumulating on the top of the produced ingot, to be removed later by cropping. In the field of tool steels, the consumable-electrode vacuum-melting (CVM) process is applied primarily to the production of special grades of hot-work and high-speed tool steels.

High-speed tool steels produced by powder metallurgy: The steel produced by conventional methods is reduced to a fine powder by a gas atomization process. The powder is compacted by a hot isostatic method with pressures in the range of 15,000 to 17,000 psi. The compacted billets are hot-rolled to the final bar size, yielding a tool-steel material which has 100 per cent theoretical density. High-speed tool steels produced by the P/M method offer a tool material providing increased tool wear life and high impact strength, of particular advantage in interrupted cuts.

Copyright 2004, Industrial Press, Inc., New York, NY

HARDENING, TEMPERING, AND ANNEALING

Heat Treatment Of Standard Steels

Heat-Treating Definitions.— This glossary of heat-treating terms has been adopted by the American Foundrymen's Association, the American Society for Metals, the American Society for Testing and Materials, and the Society of Automotive Engineers. Since it is not intended to be a specification but is strictly a set of definitions, temperatures have purposely been omitted.

Aging: Describes a time–temperature-dependent change in the properties of certain alloys. Except for strain aging and age softening, it is the result of precipitation from a solid solution of one or more compounds whose solubility decreases with decreasing temperature. For each alloy susceptible to aging, there is a unique range of time–temperature combinations to which it will respond.

Annealing: A term denoting a treatment, consisting of heating to and holding at a suitable temperature followed by cooling at a suitable rate, used primarily to soften but also to simultaneously produce desired changes in other properties or in microstructure. The purpose of such changes may be, but is not confined to, improvement of machinability; facilitation of cold working; improvement of mechanical or electrical properties; or increase in stability of dimensions. The time–temperature cycles used vary widely both in maximum temperature attained and in cooling rate employed, depending on the composition of the material, its condition, and the results desired. When applicable, the following more specific process names should be used: Black Annealing, Blue Annealing, Box Annealing, Bright Annealing, Cycle Annealing, Flame Annealing, Full Annealing, Graphitizing, Intermediate Annealing, Isothermal Annealing, Process Annealing, Quench Annealing, and Spheroidizing. When the term is used without qualification, full annealing is implied. When applied only for the relief of stress, the process is properly called stress relieving.

Black Annealing: Box annealing or pot annealing, used mainly for sheet, strip, or wire.

Blue Annealing: Heating hot-rolled sheet in an open furnace to a temperature within the transformation range and then cooling in air, to soften the metal. The formation of a bluish oxide on the surface is incidental.

Box Annealing: Annealing in a sealed container under conditions that minimize oxidation. In box annealing, the charge is usually heated slowly to a temperature below the transformation range, but sometimes above or within it, and is then cooled slowly; this process is also called "close annealing" or "pot annealing."

Bright Annealing: Annealing in a protective medium to prevent discoloration of the bright surface.

Cycle Annealing: An annealing process employing a predetermined and closely controlled time–temperature cycle to produce specific properties or microstructure.

Flame Annealing: Annealing in which the heat is applied directly by a flame.

Full Annealing: Austenitizing and then cooling at a rate such that the hardness of the product approaches a minimum.

Graphitizing: Annealing in such a way that some or all of the carbon is precipitated as graphite.

Intermediate Annealing: Annealing at one or more stages during manufacture and before final thermal treatment.

Isothermal Annealing: Austenitizing and then cooling to and holding at a temperature at which austenite transforms to a relatively soft ferrite-carbide aggregate.

Process Annealing: An imprecise term used to denote various treatments that improve workability. For the term to be meaningful, the condition of the material and the time–temperature cycle used must be stated.

Quench Annealing: Annealing an austenitic alloy by *Solution Heat Treatment*.

Spheroidizing: Heating and cooling in a cycle designed to produce a spheroidal or globular form of carbide.

Copyright 2004, Industrial Press, Inc., New York, NY

Austempering: Quenching from a temperature above the transformation range, in a medium having a rate of heat abstraction high enough to prevent the formation of high-temperature transformation products, and then holding the alloy, until transformation is complete, at a temperature below that of pearlite formation and above that of martensite formation.

Austenitizing: Forming austenite by heating into the transformation range (partial austenitizing) or above the transformation range (complete austenitizing). When used without qualification, the term implies complete austenitizing.

Baking: Heating to a low temperature in order to remove entrained gases.

Bluing: A treatment of the surface of iron-base alloys, usually in the form of sheet or strip, on which, by the action of air or steam at a suitable temperature, a thin blue oxide film is formed on the initially scale-free surface, as a means of improving appearance and resistance to corrosion. This term is also used to denote a heat treatment of springs after fabrication, to reduce the internal stress created by coiling and forming.

Carbon Potential: A measure of the ability of an environment containing active carbon to alter or maintain, under prescribed conditions, the carbon content of the steel exposed to it. In any particular environment, the carbon level attained will depend on such factors as temperature, time, and steel composition.

Carbon Restoration: Replacing the carbon lost in the surface layer from previous processing by carburizing this layer to substantially the original carbon level.

Carbonitriding: A case-hardening process in which a suitable ferrous material is heated above the lower transformation temperature in a gaseous atmosphere of such composition as to cause simultaneous absorption of carbon and nitrogen by the surface and, by diffusion, create a concentration gradient. The process is completed by cooling at a rate that produces the desired properties in the workpiece.

Carburizing: A process in which carbon is introduced into a solid iron-base alloy by heating above the transformation temperature range while in contact with a carbonaceous material that may be a solid, liquid, or gas. Carburizing is frequently followed by quenching to produce a hardened case.

Case: 1) The surface layer of an iron-base alloy that has been suitably altered in composition and can be made substantially harder than the interior or core by a process of case hardening; and 2) the term case is also used to designate the hardened surface layer of a piece of steel that is large enough to have a distinctly softer core or center.

Cementation: The process of introducing elements into the outer layer of metal objects by means of high-temperature diffusion.

Cold Treatment: Exposing to suitable subzero temperatures for the purpose of obtaining desired conditions or properties, such as dimensional or microstructural stability. When the treatment involves the transformation of retained austenite, it is usually followed by a tempering treatment.

Conditioning Heat Treatment: A preliminary heat treatment used to prepare a material for a desired reaction to a subsequent heat treatment. For the term to be meaningful, the treatment used must be specified.

Controlled Cooling: A term used to describe a process by which a steel object is cooled from an elevated temperature, usually from the final hot-forming operation in a predetermined manner of cooling to avoid hardening, cracking, or internal damage.

Core: 1) The interior portion of an iron-base alloy that after case hardening is substantially softer than the surface layer or case; and 2) the term core is also used to designate the relatively soft central portion of certain hardened tool steels.

Critical Range or Critical Temperature Range: Synonymous with *Transformation Range*, which is preferred.

Cyaniding: A process of case hardening an iron-base alloy by the simultaneous absorption of carbon and nitrogen by heating in a cyanide salt. Cyaniding is usually followed by quenching to produce a hard case.

Copyright 2004, Industrial Press, Inc., New York, NY

Decarburization: The loss of carbon from the surface of an iron-base alloy as the result of heating in a medium that reacts with the carbon.

Drawing: Drawing, or drawing the temper, is synonymous with *Tempering*, which is preferable.

Eutectic Alloy: The alloy composition that freezes at constant temperature similar to a pure metal. The lowest melting (or freezing) combination of two or more metals. The alloy structure (homogeneous) of two or more solid phases formed from the liquid eutectically.

Hardenability: In a ferrous alloy, the property that determines the depth and distribution of hardness induced by quenching.

Hardening: Any process of increasing hardness of metal by suitable treatment, usually involving heating and cooling. See also *Aging*.

Hardening, Case: A process of surface hardening involving a change in the composition of the outer layer of an iron-base alloy followed by appropriate thermal treatment. Typical case-hardening processes are *Carburizing*, *Cyaniding*, *Carbonitriding*, and *Nitriding*.

Hardening, Flame: A process of heating the surface layer of an iron-base alloy above the transformation temperature range by means of a high-temperature flame, followed by quenching.

Hardening, Precipitation: A process of hardening an alloy in which a constituent precipitates from a supersaturated solid solution. See also *Aging*.

Hardening, Secondary: An increase in hardness following the normal softening that occurs during the tempering of certain alloy steels.

Heating, Differential: A heating process by which the temperature is made to vary throughout the object being heated so that on cooling, different portions may have such different physical properties as may be desired.

Heating, Induction: A process of local heating by electrical induction.

Heat Treatment: A combination of heating and cooling operations applied to a metal or alloy in the solid state to obtain desired conditions or properties. Heating for the sole purpose of hot working is excluded from the meaning of this definition.

Heat Treatment, Solution: A treatment in which an alloy is heated to a suitable temperature and held at this temperature for a sufficient length of time to allow a desired constituent to enter into solid solution, followed by rapid cooling to hold the constituent in solution. The material is then in a supersaturated, unstable state, and may subsequently exhibit *Age Hardening*.

Homogenizing: A high-temperature heat-treatment process intended to eliminate or to decrease chemical segregation by diffusion.

Isothermal Transformation: A change in phase at constant temperature.

Malleablizing: A process of annealing white cast iron in which the combined carbon is wholly or in part transformed to graphitic or free carbon and, in some cases, part of the carbon is removed completely. See *Temper Carbon*.

Maraging: A precipitation hardening treatment applied to a special group of iron-base alloys to precipitate one or more intermetallic compounds in a matrix of essentially carbon-free martensite.

Martempering: A hardening procedure in which an austenitized ferrous workpiece is quenched into an appropriate medium whose temperature is maintained substantially at the M_s of the workpiece, held in the medium until its temperature is uniform throughout but not long enough to permit bainite to form, and then cooled in air. The treatment is followed by tempering.

Nitriding: A process of case hardening in which an iron-base alloy of special composition is heated in an atmosphere of ammonia or in contact with nitrogenous material. Surface hardening is produced by the absorption of nitrogen without quenching.

Normalizing: A process in which an iron-base alloy is heated to a temperature above the transformation range and subsequently cooled in still air at room temperature.

Copyright 2004, Industrial Press, Inc., New York, NY

Overheated: A metal is said to have been overheated if, after exposure to an unduly high temperature, it develops an undesirably coarse grain structure but is not permanently damaged. The structure damaged by overheating can be corrected by suitable heat treatment or by mechanical work or by a combination of the two. In this respect it differs from a Burnt structure.

Patenting: A process of heat treatment applied to medium- or high-carbon steel in wire making prior to the wire drawing or between drafts. It consists in heating to a temperature above the transformation range, followed by cooling to a temperature below that range in air or in a bath of molten lead or salt maintained at a temperature appropriate to the carbon content of the steel and the properties required of the finished product.

Preheating: Heating to an appropriate temperature immediately prior to austenitizing when hardening high-hardenability constructional steels, many of the tool steels, and heavy sections.

Quenching: Rapid cooling. When applicable, the following more specific terms should be used: Direct Quenching, Fog Quenching, Hot Quenching, Interrupted Quenching, Selective Quenching, Slack Quenching, Spray Quenching, and Time Quenching.

Direct Quenching: Quenching carburized parts directly from the carburizing operation.

Fog Quenching: Quenching in a mist.

Hot Quenching: An imprecise term used to cover a variety of quenching procedures in which a quenching medium is maintained at a prescribed temperature above 160 degrees F (71 degrees C).

Interrupted Quenching: A quenching procedure in which the workpiece is removed from the first quench at a temperature substantially higher than that of the quenchant and is then subjected to a second quenching system having a different cooling rate than the first.

Selective Quenching: Quenching only certain portions of a workpiece.

Slack Quenching: The incomplete hardening of steel due to quenching from the austenitizing temperature at a rate slower than the critical cooling rate for the particular steel, resulting in the formation of one or more transformation products in addition to martensite.

Spray Quenching: Quenching in a spray of liquid.

Time Quenching: Interrupted quenching in which the duration of holding in the quenching medium is controlled.

Soaking: Prolonged heating of a metal at a selected temperature.

Stabilizing Treatment: A treatment applied to stabilize the dimensions of a workpiece or the structure of a material such as 1) before finishing to final dimensions, heating a workpiece to or somewhat beyond its operating temperature and then cooling to room temperature a sufficient number of times to ensure stability of dimensions in service; 2) transforming retained austenite in those materials that retain substantial amounts when quench hardened (see cold treatment); and 3) heating a solution-treated austenitic stainless steel that contains controlled amounts of titanium or niobium plus tantalum to a temperature below the solution heat-treating temperature to cause precipitation of finely divided, uniformly distributed carbides of those elements, thereby substantially reducing the amount of carbon available for the formation of chromium carbides in the grain boundaries on subsequent exposure to temperatures in the sensitizing range.

Stress Relieving: A process to reduce internal residual stresses in a metal object by heating the object to a suitable temperature and holding for a proper time at that temperature. This treatment may be applied to relieve stresses induced by casting, quenching, normalizing, machining, cold working, or welding.

Temper Carbon: The free or graphitic carbon that comes out of solution usually in the form of rounded nodules in the structure during *Graphitizing* or *Malleablizing*.

Tempering: Heating a quench-hardened or normalized ferrous alloy to a temperature below the transformation range to produce desired changes in properties.

Double Tempering: A treatment in which quench hardened steel is given two complete tempering cycles at substantially the same temperature for the purpose of ensuring completion of the tempering reaction and promoting stability of the resulting microstructure.

Copyright 2004, Industrial Press, Inc., New York, NY

Snap Temper: A precautionary interim stress-relieving treatment applied to high hardenability steels immediately after quenching to prevent cracking because of delay in tempering them at the prescribed higher temperature.

Temper Brittleness: Brittleness that results when certain steels are held within, or are cooled slowly through, a certain range of temperatures below the transformation range. The brittleness is revealed by notched-bar impact tests at or below room temperature.

Transformation Ranges or Transformation Temperature Ranges: Those ranges of temperature within which austenite forms during heating and transforms during cooling. The two ranges are distinct, sometimes overlapping but never coinciding. The limiting temperatures of the ranges depend on the composition of the alloy and on the rate of change of temperature, particularly during cooling.

Transformation Temperature: The temperature at which a change in phase occurs. The term is sometimes used to denote the limiting temperature of a transformation range. The following symbols are used for iron and steels:

Ac_{cm} = In hypereutectoid steel, the temperature at which the solution of cementite in austenite is completed during heating

Ac_1 = The temperature at which austenite begins to form during heating

Ac_3 = The temperature at which transformation of ferrite to austenite is completed during heating

Ac_4 = The temperature at which austenite transforms to delta ferrite during heating

$Ae_1, Ae_3, Ae_{cm}, Ae_4$ = The temperatures of phase changes at equilibrium

Ar_{cm} = In hypereutectoid steel, the temperature at which precipitation of cementite starts during cooling

Ar_1 = The temperature at which transformation of austenite to ferrite or to ferrite plus cementite is completed during cooling

Ar_3 = The temperature at which austenite begins to transform to ferrite during cooling

Ar_4 = The temperature at which delta ferrite transforms to austenite during cooling

M_s = The temperature at which transformation of austenite to martensite starts during cooling

M_f = The temperature, during cooling, at which transformation of austenite to martensite is substantially completed

All these changes except the formation of martensite occur at lower temperatures during cooling than during heating, and depend on the rate of change of temperature.

Hardness and Hardenability.— Hardenability is the property of steel that determines the *depth and distribution of hardness* induced by quenching from the austenitizing temperature. Hardenability should not be confused with hardness as such or with maximum hardness. Hardness is a measure of the ability of a metal to resist penetration as determined by any one of a number of standard tests (Brinell, Rockwell, Vickers, etc). The maximum attainable hardness of any steel depends solely on carbon content and is not significantly affected by alloy content. Maximum hardness is realized only when the cooling rate in quenching is rapid enough to ensure full transformation to martensite.

The as-quenched surface hardness of a steel part is dependent on carbon content and cooling rate, but the *depth* to which a certain hardness level is maintained with given quenching conditions is a function of its hardenability. Hardenability is largely determined by the percentage of alloying elements in the steel; however, austenite grain size, time and temperature during austenitizing, and prior microstructure also significantly affect the hardness depth. The hardenability required for a particular part depends on size, design, and service stresses. For highly stressed parts, the best combination of strength and toughness is obtained by through hardening to a martensitic structure followed by adequate tempering. There are applications, however, where through hardening is not necessary or even

Copyright 2004, Industrial Press, Inc., New York, NY

desirable. For parts that are stressed principally at or near the surface, or in which wear resistance or resistance to shock loading is anticipated, a shallow hardening steel with a moderately soft core may be appropriate.

For through hardening of thin sections, carbon steels may be adequate; but as section size increases, alloy steels of increasing hardenability are required. The usual practice is to select the most economical grade that can meet the desired properties consistently. It is not good practice to utilize a higher alloy grade than necessary, because excessive use of alloying elements adds little to the properties and can sometimes induce susceptibility to quenching cracks.

Quenching Media: The choice of quenching media is often a critical factor in the selection of steel of the proper hardenability for a particular application. Quenching severity can be varied by selection of quenching medium, agitation control, and additives that improve the cooling capability of the quenchant. Increasing the quenching severity permits the use of less expensive steels of lower hardenability; however, consideration must also be given to the amount of distortion that can be tolerated and the susceptibility to quench cracking. In general, the more severe the quenchant and the less symmetrical the part being quenched, the greater are the size and shape changes that result from quenching and the greater is the risk of quench cracking. Consequently, although water quenching is less costly than oil quenching, and water quenching steels are less expensive than those requiring oil quenching, it is important to know that the parts being hardened can withstand the resulting distortion and the possibility of cracking.

Oil, salt, and synthetic water-polymer quenchants are also used, but they often require steels of higher alloy content and hardenability. A general rule for the selection of steel and quenchant for a particular part is that the steel should have a hardenability not exceeding that required by the severity of the quenchant selected. The carbon content of the steel should also not exceed that required to meet specified hardness and strength, because quench cracking susceptibility increases with carbon content.

The choice of quenching media is important in hardening, but another factor is agitation of the quenching bath. The more rapidly the bath is agitated, the more rapidly heat is removed from the steel and the more effective is the quench.

Hardenability Test Methods: The most commonly used method for determining hardenability is the end-quench test developed by Jominy and Boegehold, and described in detail in both SAE J406 and ASTM A255. In this test a normalized 1-inch-round, approximately 4-inch-long specimen of the steel to be evaluated is heated uniformly to its austenitizing temperature. The specimen is then removed from the furnace, placed in a jig, and immediately end quenched by a jet of room-temperature water. The water is played on the end face of the specimen, without touching the sides, until the entire specimen has cooled. Longitudinal flat surfaces are ground on opposite sides of the piece and Rockwell C scale hardness readings are taken at $\frac{1}{16}$-inch intervals from the quenched end. The resulting data are plotted on graph paper with the hardness values as ordinates (y-axis) and distances from the quenched end as abscissas (x-axis). Representative data have been accumulated for a variety of standard steel grades and are published by SAE and AISI as "H-bands." These data show graphically and in tabular form the high and low limits applicable to each grade. The suffix H following the standard AISI/SAE numerical designation indicates that the steel has been produced to specific hardenability limits.

Experiments have confirmed that the cooling rate at a given point along the Jominy bar corresponds closely to the cooling rate at various locations in round bars of various sizes. In general, when end-quench curves for different steels coincide approximately, similar treatments will produce similar properties in sections of the same size. On occasion it is necessary to predict the end-quench hardenability of a steel not available for testing, and reasonably accurate means of calculating hardness for any Jominy location on a section of steel of known analysis and grain size have been developed.

Copyright 2004, Industrial Press, Inc., New York, NY

Tempering: As-quenched steels are in a highly stressed condition and are seldom used without tempering. Tempering imparts plasticity or toughness to the steel, and is inevitably accompanied by a loss in hardness and strength. The loss in strength, however, is only incidental to the very important increase in toughness, which is due to the relief of residual stresses induced during quenching and to precipitation, coalescence, and spheroidization of iron and alloy carbides resulting in a microstructure of greater plasticity.

Alloying slows the tempering rate, so that alloy steel requires a higher tempering temperature to obtain a given hardness than carbon steel of the same carbon content. The higher tempering temperature for a given hardness permits a greater relaxation of residual stress and thereby improves the steel's mechanical properties. Tempering is done in furnaces or in oil or salt baths at temperatures varying from 300 to 1200 degrees F. With most grades of alloy steel, the range between 500 and 700 degrees F is avoided because of a phenomenon known as "blue brittleness," which reduces impact properties. Tempering the martensitic stainless steels in the range of 800-1100 degrees F is not recommended because of the low and erratic impact properties and reduced corrosion resistance that result. Maximum toughness is achieved at higher temperatures. It is important to temper parts as soon as possible after quenching, because any delay greatly increases the risk of cracking resulting from the high-stress condition in the as-quenched part.

Surface Hardening Treatment (Case Hardening).— Many applications require high hardness or strength primarily at the surface, and complex service stresses frequently require not only a hard, wear–resistant surface, but also core strength and toughness to withstand impact stress.

To achieve these different properties, two general processes are used: 1) The chemical composition of the surface is altered, prior to or after quenching and tempering; the processes used include carburizing, nitriding, cyaniding, and carbonitriding; and 2) Only the surface layer is hardened by the heating and quenching process; the most common processes used for surface hardening are flame hardening and induction hardening.

Carburizing: Carbon is diffused into the part's surface to a controlled depth by heating the part in a carbonaceous medium. The resulting depth of carburization, commonly referred to as case depth, depends on the carbon potential of the medium used and the time and temperature of the carburizing treatment. The steels most suitable for carburizing to enhance toughness are those with sufficiently low carbon contents, usually below 0.03 per cent. Carburizing temperatures range from 1550 to 1750 degrees F, with the temperature and time at temperature adjusted to obtain various case depths. Steel selection, hardenability, and type of quench are determined by section size, desired core hardness, and service requirements.

Three types of carburizing are most often used: 1) *Liquid carburizing* involves heating the steel in molten barium cyanide or sodium cyanide. The case absorbs some nitrogen in addition to carbon, thus enhancing surface hardness; 2) *Gas carburizing* involves heating the steel in a gas of controlled carbon content. When used, the carbon level in the case can be closely controlled; and 3) *Pack carburizing*, which involves sealing both the steel and solid carbonaceous material in a gas-tight container, then heating this combination.

With any of these methods, the part may be either quenched after the carburizing cycle without reheating or air cooled followed by reheating to the austenitizing temperature prior to quenching. The case depth may be varied to suit the conditions of loading in service. However, service characteristics frequently require that only selective areas of a part have to be case hardened. Covering the areas not to be cased, with copper plating or a layer of commercial paste, allows the carbon to penetrate only the exposed areas. Another method involves carburizing the entire part, then removing the case in selected areas by machining, prior to quench hardening.

Nitriding: The steel part is heated to a temperature of 900–1150 degrees F in an atmosphere of ammonia gas and dissociated ammonia for an extended period of time that

Copyright 2004, Industrial Press, Inc., New York, NY

depends on the case depth desired. A thin, very hard case results from the formation of nitrides. Strong nitride-forming elements (chromium and molybdenum) are required to be present in the steel, and often special nonstandard grades containing aluminum (a strong nitride former) are used. The major advantage of this process is that parts can be quenched and tempered, then machined, prior to nitriding, because only a little distortion occurs during nitriding.

Cyaniding: This process involves heating the part in a bath of sodium cyanide to a temperature slightly above the transformation range, followed by quenching, to obtain a thin case of high hardness.

Carbonitriding: This process is similar to cyaniding except that the absorption of carbon and nitrogen is accomplished by heating the part in a gaseous atmosphere containing hydrocarbons and ammonia. Temperatures of 1425–1625 degrees F are used for parts to be quenched, and lower temperatures, 1200–1450 degrees F, may be used where a liquid quench is not required.

Flame Hardening: This process involves rapid heating with a direct high-temperature gas flame, such that the surface layer of the part is heated above the transformation range, followed by cooling at a rate that causes the desired hardening. Steels for flame hardening are usually in the range of 0.30–0.60 per cent carbon, with hardenability appropriate for the case depth desired and the quenchant used. The quenchant is usually sprayed on the surface a short distance behind the heating flame. Immediate tempering is required and may be done in a conventional furnace or by a flame-tempering process, depending on part size and costs.

Induction Hardening: This process is similar in many respects to flame hardening except that the heating is caused by a high-frequency electric current sent through a coil or inductor surrounding the part. The depth of heating depends on the frequency, the rate of heat conduction from the surface, and the length of the heating cycle. Quenching is usually accomplished with a water spray introduced at the proper time through jets in or near the inductor block or coil. In some instances, however, parts are oil-quenched by immersing them in a bath of oil after they reach the hardening temperature.

Structure of Fully Annealed Carbon Steel.— In carbon steel that has been fully annealed, there are normally present, apart from such impurities as phosphorus and sulfur, two constituents: the element iron in a form metallurgically known as *ferrite* and the chemical compound iron carbide in the form metallurgically known as *cementite*. This latter constituent consists of 6.67 per cent carbon and 93.33 per cent iron. A certain proportion of these two constituents will be present as a mechanical mixture. This mechanical mixture, the amount of which depends on the carbon content of the steel, consists of alternate bands or layers of ferrite and cementite. Under the microscope, the matrix frequently has the appearance of mother-of-pearl and hence has been named *pearlite*. Pearlite contains about 0.85 per cent carbon and 99.15 per cent iron, neglecting impurities. A fully annealed steel containing 0.85 per cent carbon would consist entirely of pearlite. Such a steel is known as *eutectoid* steel and has a laminated structure characteristic of a eutectic alloy. Steel that has less than 0.85 per cent carbon (*hypoeutectoid* steel) has an excess of ferrite above that required to mix with the cementite present to form pearlite; hence, both ferrite and pearlite are present in the fully annealed state. Steel having a carbon content greater than 0.85 per cent (*hypereutectoid* steel) has an excess of cementite over that required to mix with the ferrite to form pearlite; hence, both cementite and pearlite are present in the fully annealed state. The structural constitution of carbon steel in terms of ferrite, cementite, pearlite and austenite for different carbon contents and at different temperatures is shown by the accompanying figure, *Phase Diagram of Carbon Steel*.

Effect of Heating Fully Annealed Carbon Steel.— When carbon steel in the fully annealed state is heated above the lower critical point, which is some temperature in the range of 1335 to 1355 degrees F (depending on the carbon content), the alternate bands or

Copyright 2004, Industrial Press, Inc., New York, NY

layers of ferrite and cementite that make up the pearlite begin to merge into each other. This process continues until the pearlite is thoroughly "dissolved," forming what is known as *austenite*. If the temperature of the steel continues to rise and there is present, in addition to the pearlite, any excess ferrite or cementite, this also will begin to dissolve into the austenite until finally only austenite will be present. The temperature at which the excess ferrite or cementite is completely dissolved in the austenite is called the *upper critical point*. This temperature varies with the carbon content of the steel much more widely than the lower critical point (see Fig. 1).



Fig. 1. Phase Diagram of Carbon Steel

Effect of Slow Cooling on Carbon Steel.— If carbon steel that has been heated to the point where it consists entirely of austenite is slowly cooled, the process of transformation that took place during the heating will be reversed, but the upper and lower critical points will occur at somewhat lower temperatures than they do on heating. Assuming that the steel was originally fully annealed, its structure on returning to atmospheric temperature after slow cooling will be the same as before in terms of the proportions of ferrite or cementite and pearlite present. The austenite will have entirely disappeared.

Effect of Rapid Cooling or Quenching on Carbon Steel.— Observations have shown that as the rate at which carbon steel is cooled from an austenitic state is increased, the temperature at which the austenite begins to change into pearlite drops more and more below the slow cooling transformation temperature of about 1300 degrees F. (For example, a 0.80 per cent carbon steel that is cooled at such a rate that the temperature drops 500 degrees in one second will show transformation of austenite beginning at 930 degrees F.) As the cooling rate is increased, the laminations of the pearlite formed by the transformation of the austenite become finer and finer up to the point where they cannot be detected under a high-power microscope, while the steel itself increases in hardness and tensile strength. As the rate of cooling is still further increased, this transformation temperature suddenly drops to around 500 degrees F or lower, depending on the carbon content of the steel. The cooling rate at which this sudden drop in transformation temperature takes place is called the *critical cooling rate*. When a piece of carbon steel is quenched at this rate or faster, a new struc-

Copyright 2004, Industrial Press, Inc., New York, NY

ture is formed. The austenite is transformed into *martensite*, which is characterized by an angular needlelike structure and a very high hardness.

If carbon steel is subjected to a severe quench or to extremely rapid cooling, a small percentage of the austenite, instead of being transformed into martensite during the quenching operation, may be retained. Over a period of time, however, this remaining austenite tends to be gradually transformed into martensite even though the steel is not subjected to further heating or cooling. Martensite has a lower density than austenite, and such a change, or "aging" as it is called, often results in an appreciable increase in volume or "growth" and the setting up of new internal stresses in the steel.

Steel Heat-Treating Furnaces.— Various types of furnaces heated by gas, oil, or electricity are used for the heat treatment of steel. These furnaces include the oven or box type in various modifications for "in-and-out" or for continuous loading and unloading; the retort type; the pit type; the pot type; and the salt-bath electrode type.

Oven or Box Furnaces: This type of furnace has a box or oven-shaped heating chamber. The "in-and-out" oven furnaces are loaded by hand or by a track-mounted car that, when rolled into the furnace, forms the bottom of the heating chamber. The car type is used where heavy or bulky pieces must be handled. Some oven-type furnaces are provided with a full muffle or a semimuffle, which is an enclosed refractory chamber into which the parts to be heated are placed. The full-muffle, being fully enclosed, prevents any flames or burning gases from coming in contact with the work and permits a special atmosphere to be used to protect or condition the work. The semimuffle, which is open at the top, protects the work from direct impingement of the flame although it does not shut off the work from the hot gases. In the direct-heat-type oven furnace, the work is open to the flame. In the electric oven furnace, a retort is provided when gas atmospheres are to be employed to confine the gas and prevent it from attacking the heating elements. Where muffles are used, they must be replaced periodically, and a greater amount of fuel is required than in a direct-heat type of oven furnace.

For continuous loading and unloading, there are several types of furnaces such as rotary hearth car; roller-, furnace belt-, walking-beam, or pusher-conveyor; and a continuous-kiln-type through which track-mounted cars are run. In the continuous type of furnace, the work may pass through several zones that are maintained at different temperatures for preheating, heating, soaking, and cooling.

Retort Furnace: This is a vertical type of furnace provided with a cylindrical metal retort into which the parts to be heat-treated are suspended either individually, if large enough, or in a container of some sort. The use of a retort permits special gas atmospheres to be employed for carburizing, nitriding, etc.

Pit-Type Furnace: This is a vertical furnace arranged for the loading of parts in a metal basket. The parts within the basket are heated by convection, and when the basket is lowered into place, it fits into the furnace chamber in such a way as to provide a dead-air space to prevent direct heating.

Pot-Type Furnace: This furnace is used for the immersion method of heat treating small parts. A cast-alloy pot is employed to hold a bath of molten lead or salt in which the parts are placed for heating.

Salt Bath Electrode Furnace: In this type of electric furnace, heating is accomplished by means of electrodes suspended directly in the salt bath. The patented grouping and design of electrodes provide an electromagnetic action that results in an automatic stirring action. This stirring tends to produce an even temperature throughout the bath.

Vacuum Furnace: Vacuum heat treatment is a relatively new development in metallurgical processing, with a vacuum substituting for the more commonly used protective gas atmospheres. The most often used furnace is the "cold wall" type, consisting of a water-cooled vessel that is maintained near ambient temperature during operation. During quenching, the chamber is backfilled up to or above atmospheric pressure with an inert gas,

Copyright 2004, Industrial Press, Inc., New York, NY

which is circulated by an internal fan. When even faster cooling rates are needed, furnaces are available with capability for liquid quenching, performed in an isolated chamber.

Fluidized-Bed Furnace: Fluidized-bed techniques are not new; however, new furnace designs have extended the technology into the temperature ranges required for most common heat treatments. In fluidization, a bed of dry, finely divided particles, typically aluminum oxide, is made to behave like a liquid by feeding gas upward through the bed. An important characteristic of the bed is high-efficiency heat transfer. Applications include continuous or batch-type units for all general heat treatments.

Physical Properties of Heat-Treated Steels.— Steels that have been "fully hardened" to the same hardness when quenched will have about the same tensile and yield strengths regardless of composition and alloying elements. When the hardness of such a steel is known, it is also possible to predict its reduction of area and tempering temperature. The accompanying figures illustrating these relationships have been prepared by the Society of Automotive Engineers.

Fig. 1 gives the range of Brinell hardnesses that could be expected for any particular tensile strength or it may be used to determine the range of tensile strengths that would correspond to any particular hardness. Fig. 2 shows the relationship between the tensile strength or hardness and the yield point. The solid line is the normal-expectancy curve. The dotted-line curves give the range of the variation of scatter of the plotted data. Fig. 3 shows the relationship that exists between the tensile strength (or hardness) and the reduction of area. The curve to the left represents the alloy steels and that on the right the carbon steels. Both are normal-expectancy curves and the extremities of the perpendicular lines that intersect them represent the variations from the normal-expectancy curves that may be caused by quality differences and by the magnitude of parasitic stresses induced by quenching. Fig. 4 shows the relationship between the hardness (or approximately equivalent tensile strength) and the tempering temperature. Three curves are given, one for fully hardened steels with a carbon content between 0.40 and 0.55 per cent, one for fully hardened steels with a carbon content between 0.30 and 0.40 per cent, and one for steels that are not fully hardened.

From Fig. 1, it can be seen that for a tensile strength of, say, 200,000 pounds per square inch, the Brinell hardness could range between 375 and 425. By taking 400 as the mean hardness value and using Fig. 4, it can be seen that the tempering temperature of fully hardened steels of 0.40 to 0.55 per cent carbon content would be 990 degrees F and that of fully hardened steels of 0.30 to 0.40 per cent carbon would be 870 degrees F. This chart also shows that the tempering temperature for a steel not fully hardened would approach 520 degrees F. A yield point of $0.9 \times 200{,}000$, or 180,000, pounds per square inch is indicated (Fig. 2) for the fully hardened steel with a tensile strength of 200,000 pounds per square inch. Most alloy steels of 200,000 pounds per square inch tensile strength would probably have a reduction in area of close to 44 per cent (Fig. 3) but some would have values in the range of 35 to 53 per cent. Carbon steels of the same tensile strength would probably have a reduction in area of close to 24 per cent but could possibly range from 17 to 31 per cent.

Figs. 2 and 3 represent steel in the quenched and tempered condition and Fig. 1 represents steel in the hardened and tempered, as-rolled, annealed, and normalized conditions. These charts give a good general indication of mechanical properties; however, more exact information when required should be obtained from tests on samples of the individual heats of steel under consideration.

Hardening

Basic Steps in Hardening.— The operation of hardening steel consists fundamentally of two steps. The first step is to heat the steel to some temperature above (usually at least 100 degrees F above) its transformation point so that it becomes entirely austenitic in structure. The second step is to quench the steel at some rate faster than the critical rate (which

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1.



Fig. 2.



Fig. 3.



Fig. 4.

depends on the carbon content, the amounts of alloying elements present other than carbon, and the grain size of the austenite) to produce a martensitic structure. The hardness of a martensitic steel depends on its carbon content and ranges from about 460 Brinell at 0.20 per cent carbon to about 710 Brinell above 0.50 carbon. In comparison, ferrite has a hardness of about 90 Brinell, pearlite about 240 Brinell, and cementite around 550 Brinell.

Critical Points of Decalescence and Recalescence.— The critical or transformation point at which pearlite is transformed into austenite as it is being heated is also called the *decalescence point*. If the temperature of the steel was observed as it passed through the

Copyright 2004, Industrial Press, Inc., New York, NY

decalescence point, it would be noted that it would continue to absorb heat without appreciably rising in temperature, although the immediate surroundings were hotter than the steel. Similarly, the critical or transformation point at which austenite is transformed back into pearlite on cooling is called the *recalescence point*. When this point is reached, the steel will give out heat so that its temperature instead of continuing to fall, will momentarily increase.

The recalescence point is lower than the decalescence point by anywhere from 85 to 215 degrees F, and the lower of these points does not manifest itself unless the higher one has first been fully passed. These critical points have a direct relation to the hardening of steel. Unless a temperature sufficient to reach the decalescence point is obtained, so that the pearlite is changed into austenite, no hardening action can take place; and unless the steel is cooled suddenly before it reaches the recalescence point, thus preventing the changing back again from austenite to pearlite, no hardening can take place. The critical points vary for different kinds of steel and must be determined by tests. The variation in the critical points makes it necessary to heat different steels to different temperatures when hardening.

Hardening Temperatures.— The maximum temperature to which a steel is heated before quenching to harden it is called the hardening temperature. Hardening temperatures vary for different steels and different classes of service, although, in general, it may be said that the hardening temperature for any given steel is above the lower critical point of that steel.

Just how far above this point the hardening temperature lies for any particular steel depends on three factors: 1) the chemical composition of the steel; 2) the amount of excess ferrite (if the steel has less than 0.85 per cent carbon content) or the amount of excess cementite (if the steel has more than 0.85 per cent carbon content) that is to be dissolved in the austenite; and 3) the maximum grain size permitted, if desired.

The general range of full-hardening temperatures for carbon steels is shown by the diagram. This range is merely indicative of general practice and is not intended to represent absolute hardening temperature limits. It can be seen that for steels of less than 0.85 per cent carbon content, the hardening range is above the upper critical point — that is, above the temperature at which all the excess ferrite has been dissolved in the austenite. On the other hand, for steels of more than 0.85 per cent carbon content, the hardening range lies somewhat below the upper critical point. This indicates that in this hardening range, some of the excess cementite still remains undissolved in the austenite. If steel of more than 0.85 per cent carbon content were heated above the upper critical point and then quenched, the resulting grain size would be excessively large.

At one time, it was considered desirable to heat steel only to the minimum temperature at which it would fully harden, one of the reasons being to avoid grain growth that takes place at higher temperature. It is now realized that no such rule as this can be applied generally since there are factors other than hardness that must be taken into consideration. For example, in many cases, toughness can be impaired by too low a temperature just as much as by too high a temperature. It is true, however, that too high hardening temperatures result in warpage, distortion, increased scale, and decarburization.

Hardening Temperatures for Carbon Tool Steels.— The best hardening temperatures for any given tool steel are dependent on the type of tool and the intended class of service. Wherever possible, the specific recommendations of the tool steel manufacturer should be followed. General recommendations for hardening temperatures of carbon tool steels based on carbon content are as follows: For steel of 0.65 to 0.80 per cent carbon content, 1450 to 1550 degrees F; for steel of 0.80 to 0.95 per cent carbon content, 1410 to 1460 degrees F; for steel of 0.95 to 1.10 per cent carbon content, 1390 to 1430 degrees F; and for steels of 1.10 per cent and over carbon content, 1380 to 1420 degrees F. For a given hardening temperature range, the higher temperatures tend to produce deeper hardness penetration and increased compressional strength, whereas the lower temperatures tend to result in shallower hardness penetration but increased resistance to splitting or bursting stresses.

Copyright 2004, Industrial Press, Inc., New York, NY

Determining Hardening Temperatures.— A hardening temperature can be specified directly or it may be specified indirectly as a certain temperature rise above the lower critical point of the steel. Where the temperature is specified directly, a pyrometer of the type that indicates the furnace temperature or a pyrometer of the type that indicates the work temperature may be employed. If the pyrometer shows furnace temperature, care must be taken to allow sufficient time for the work to reach the furnace temperature after the pyrometer indicates that the required hardening temperature has been attained. If the pyrometer indicates work temperature, then, where the workpiece is large, time must be allowed for the interior of the work to reach the temperature of the surface, which is the temperature indicated by the pyrometer.

Where the hardening temperature is specified as a given temperature rise above the critical point of the steel, a pyrometer that indicates the temperature of the work should be used. The critical point, as well as the given temperature rise, can be more accurately determined with this type of pyrometer. As the work is heated, its temperature, as indicated by the pyrometer, rises steadily until the lower critical or decalescence point of the steel is reached. At this point, the temperature of the work ceases to rise and the pyrometer indicating or recording pointer remains stationary or fluctuates slightly. After a certain elapsed period, depending on the heat input rate, the internal changes in structure of the steel that take place at the lower critical point are completed and the temperature of the work again begins to rise. A small fluctuations in temperature may occur in the interval during which structural changes are taking place, so for uniform practice, the critical point may be considered as the temperature at which the pointer first becomes stationary.

Heating Steel in Liquid Baths.— The liquid bath commonly used for heating steel tools preparatory to hardening are molten lead, sodium cyanide, barium chloride, a mixture of barium and potassium chloride, and other metallic salts. The molten substance is retained in a crucible or pot and the heat required may be obtained from gas, oil, or electricity. The principal advantages of heating baths are as follows: No part of the work can be heated to a temperature above that of the bath; the temperature can be easily maintained at whatever degree has proved, in practice, to give the best results; the submerged steel can be heated uniformly, and the finished surfaces are protected against oxidation.

Salt Baths.— Molten baths of various salt mixtures or compounds are used extensively for heat-treating operations such as hardening and tempering; they are also utilized for annealing ferrous and nonferrous metals. Commercial salt-bath mixtures are available that meet a wide range of temperature and other metallurgical requirements. For example, there are neutral baths for heating tool and die steels without carburizing the surfaces; baths for carburizing the surfaces of low-carbon steel parts; baths adapted for the usual tempering temperatures of, say, 300 to 1100 degrees F; and baths that may be heated to temperatures up to approximately 2400 degrees F for hardening high-speed steels. Salt baths are also adapted for local or selective hardening, the type of bath being selected to suit the requirements. For example, a neutral bath may be used for annealing the ends of tubing or other parts, or an activated cyanide bath for carburizing the ends of shafts or other parts. Surfaces that are not to be carburized are protected by copper plating. When the work is immersed, the unplated surfaces are subjected to the carburizing action.

Baths may consist of a mixture of sodium, potassium, barium, and calcium chlorides or nitrates of sodium, potassium, barium, and calcium in varying proportions, to which sodium carbonate and sodium cyanide are sometimes added to prevent decarburization. Various proportions of these salts provide baths of different properties. Potassium cyanide is seldom used as sodium cyanide costs less. The specific gravity of a salt bath is not as high as that of a lead bath; consequently, the work may be suspended in a salt bath and does not have to be held below the surface as in a lead bath.

The Lead Bath.— The lead bath is extensively used, but is not adapted to the high temperatures required for hardening high-speed steel, as it begins to vaporize at about 1190 degrees F. As the temperature increases, the lead volatilizes and gives off poisonous

Copyright 2004, Industrial Press, Inc., New York, NY

vapors; hence, lead furnaces should be equipped with hoods to carry away the fumes. Lead baths are generally used for temperatures below 1500 or 1600 degrees F. They are often employed for heating small pieces that must be hardened in quantities. It is important to use pure lead that is free from sulfur. The work should be preheated before plunging it into the molten lead.

Defects in Hardening.— Uneven heating is the cause of most of the defects in hardening. Cracks of a circular form, from the corners or edges of a tool, indicate uneven heating in hardening. Cracks of a vertical nature and dark-colored fissures indicate that the steel has been burned and should be put on the scrap heap. Tools that have hard and soft places have been either unevenly heated, unevenly cooled, or "soaked," a term used to indicate prolonged heating. A tool not thoroughly moved about in the hardening fluid will show hard and soft places, and have a tendency to crack. Tools that are hardened by dropping them to the bottom of the tank sometimes have soft places, owing to contact with the floor or sides.

Scale on Hardened Steel.— The formation of scale on the surface of hardened steel is due to the contact of oxygen with the heated steel; hence, to prevent scale, the heated steel must not be exposed to the action of the air. When using an oven heating furnace, the flame should be so regulated that it is not visible in the heating chamber. The heated steel should be exposed to the air as little as possible, when transferring it from the furnace to the quenching bath. An old method of preventing scale and retaining a fine finish on dies used in jewelry manufacture, small taps, etc., is as follows: Fill the die impression with powdered boracic acid and place near the fire until the acid melts; then add a little more acid to ensure covering all the surfaces. The die is then hardened in the usual way. If the boracic acid does not come off entirely in the quenching bath, immerse the work in boiling water. Dies hardened by this method are said to be as durable as those heated without the acid.

Hardening or Quenching Baths.— The purpose of a quenching bath is to remove heat from the steel being hardened at a rate that is faster than the critical cooling rate. Generally speaking, the more rapid the rate of heat extraction above the cooling rate, the higher will be the resulting hardness. To obtain the different rates of cooling required by different classes of work, baths of various kinds are used. These include plain or fresh water, brine, caustic soda solutions, oils of various classes, oil–water emulsions, baths of molten salt or lead for high-speed steels, and air cooling for some high-speed steel tools when a slow rate of cooling is required. To minimize distortion and cracking where such tendencies are present, without sacrificing depth-of-hardness penetration, a quenching medium should be selected that will cool rapidly at the higher temperatures and more slowly at the lower temperatures, that is below 750 degrees F. Oil quenches in general meet this requirement.

Oil Quenching Baths: Oil is used very extensively as a quenching medium as it results in a good proportion of hardness, toughness, and freedom from warpage when used with standard steels. Oil baths are used extensively for alloy steels. Various kinds of oils are employed, such as prepared mineral oils and vegetable, animal, and fish oils, either singly or in combination. Prepared mineral quenching oils are widely used because they have good quenching characteristics, are chemically stable, do not have an objectionable odor, and are relatively inexpensive. Special compounded oils of the soluble type are used in many plants instead of such oils as fish oil, linseed oil, cottonseed oil, etc. The soluble properties enable the oil to form an emulsion with water.

Oil cools steel at a slower rate than water, but the rate is fast enough for alloy steel. Oils have different cooling rates, however, and this rate may vary through the initial and final stages of the quenching operation. Faster cooling in the initial stage and slower cooling at lower temperatures are preferable because there is less danger of cracking the steel. The temperature of quenching oil baths should range ordinarily between 90 and 130 degrees F. A fairly constant temperature may be maintained either by circulating the oil through cooling coils or by using a tank provided with a cold-water jacket.

Copyright 2004, Industrial Press, Inc., New York, NY

A good quenching oil should possess a flash and fire point sufficiently high to be safe under the conditions used and 350 degrees F should be about the minimum point. The specific heat of the oil regulates the hardness and toughness of the quenched steel; and the greater the specific heat, the higher will be the hardness produced. Specific heats of quenching oils vary from 0.20 to 0.75, the specific heats of fish, animal, and vegetable oils usually being from 0.2 to 0.4, and of soluble and mineral oils from 0.5 to 0.7. The efficient temperature range for quenching oil is from 90 to 140 degrees F.

Quenching in Water.— Many carbon tool steels are hardened by immersing them in a bath of fresh water, but water is not an ideal quenching medium. Contact between the water and work and the cooling of the hot steel are impaired by the formation of gas bubbles or an insulating vapor film especially in holes, cavities, or pockets. The result is uneven cooling and sometimes excessive strains which may cause the tool to crack; in fact, there is greater danger of cracking in a fresh-water bath than in one containing salt water or brine.

In order to secure more even cooling and reduce danger of cracking, either rock salt (8 or 9 per cent) or caustic soda (3 to 5 per cent) may be added to the bath to eliminate or prevent the formation of a vapor film or gas pockets, thus promoting rapid early cooling. Brine is commonly used and ¾ pound of rock salt per gallon of water is equivalent to about 8 per cent of salt. Brine is not inherently a more severe or drastic quenching medium than plain water, although it may seem to be because the brine makes better contact with the heated steel and, consequently, cooling is more effective. In still-bath quenching, a slow up-and-down movement of the tool is preferable to a violent swishing around.

The temperature of water-base quenching baths should preferably be kept around 70 degrees F, but 70 to 90 or 100 degrees F is a safe range. The temperature of the hardening bath has a great deal to do with the hardness obtained. The higher the temperature of the quenching water, the more nearly does its effect approach that of oil; and if boiling water is used for quenching, it will have an effect even more gentle than that of oil — in fact, it would leave the steel nearly soft. Parts of irregular shape are sometimes quenched in a water bath that has been warmed somewhat to prevent sudden cooling and cracking.

When water is used, it should be "soft" because unsatisfactory results will be obtained with "hard" water. Any contamination of water-base quenching liquids by soap tends to decrease their rate of cooling. A water bath having 1 or 2 inches of oil on the top is sometimes employed to advantage for quenching tools made of high-carbon steel as the oil through which the work first passes reduces the sudden quenching action of the water.

The bath should be amply large to dissipate the heat rapidly and the temperature should be kept about constant so that successive pieces will be cooled at the same rate. Irregularly shaped parts should be immersed so that the heaviest or thickest section enters the bath first. After immersion, the part to be hardened should be agitated in the bath; the agitation reduces the tendency of the formation of a vapor coating on certain surfaces, and a more uniform rate of cooling is obtained. The work should never be dropped to the bottom of the bath until quite cool.

Flush or Local Quenching by Pressure-Spraying: When dies for cold heading, drawing, extruding, etc., or other tools, require a hard working surface and a relatively soft but tough body, the quenching may be done by spraying water under pressure against the interior or other surfaces to be hardened. Special spraying fixtures are used to hold the tool and apply the spray where the hardening is required. The pressure spray prevents the formation of gas pockets previously referred to in connection with the fresh-water quenching bath; hence, fresh water is effective for flush quenching and there is no advantage in using brine.

Quenching in Molten Salt Bath.— A molten salt bath may be used in preference to oil for quenching high-speed steel. The object in using a liquid salt bath for quenching (instead of an oil bath) is to obtain maximum hardness with minimum cooling stresses and distortion that might result in cracking expensive tools, especially if there are irregular sections. The temperature of the quenching bath may be around 1100 or 1200 degrees F. Quenching is

Copyright 2004, Industrial Press, Inc., New York, NY

followed by cooling to room temperature and then the tool is tempered or drawn in a bath having a temperature range of 950 to 1100 degrees F. In many cases, the tempering temperature is about 1050 degrees F.

Tanks for Quenching Baths.— The main point to be considered in a quenching bath is to keep it at a uniform temperature, so that successive pieces quenched will be subjected to the same heat treatment. The next consideration is to keep the bath agitated, so that it will not be of different temperatures in different places; if thoroughly agitated and kept in motion, as the case with the bath shown in Fig. 1, it is not even necessary to keep the pieces in motion in the bath, as steam will not be likely to form around the pieces quenched. Experience has proved that if a piece is held still in a thoroughly agitated bath, it will come out much straighter than if it has been moved around in an unagitated bath, an important consideration, especially when hardening long pieces. It is, besides, no easy matter to keep heavy and long pieces in motion unless it be done by mechanical means.

In Fig. 1 is shown a water or brine tank for quenching baths. Water is forced by a pump or other means through the supply pipe into the intermediate space between the outer and inner tank. From the intermediate space, it is forced into the inner tank through holes as indicated. The water returns to the storage tank by overflowing from the inner tank into the outer one and then through the overflow pipe as indicated. In Fig. 3 is shown another water or brine tank of a more common type. In this case, the water or brine is pumped from the storage tank and continuously returned to it. If the storage tank contains a large volume of water, there is no need for a special means for cooling. Otherwise, arrangements must be made for cooling the water after it has passed through the tank. The bath is agitated by the force with which the water is pumped into it. The holes at A are drilled at an angle, so as to throw the water toward the center of the tank. In Fig. 2 is shown an oil-quenching tank in which water is circulated in an outer surrounding tank to keep the oil bath cool. Air is forced into the oil bath to keep it agitated. Fig. 4 shows the ordinary type of quenching tank cooled by water forced through a coil of pipe. This arrangement can be used for oil, water, or brine. Fig. 5 shows a similar type of quenching tank, but with two coils of pipe. Water flows through one of these and steam through the other. By these means, it is possible to keep the bath at a constant temperature.



Fig. 1.



Fig. 2.

Interrupted Quenching.— *Austempering, martempering, and isothermal quenching* are three methods of interrupted quenching that have been developed to obtain greater toughness and ductility for given hardnesses and to avoid the difficulties of quench cracks, internal stresses, and warpage, frequently experienced when the conventional method of

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3.


Fig. 4.


Fig. 5.

quenching steel directly and rapidly from above the transformation point to atmospheric temperature is employed. In each of these three methods, quenching is begun when the work has reached some temperature above the transformation point and is conducted at a rate faster than the critical rate. The rapid cooling of the steel is interrupted, however, at some temperature above that at which martensite begins to form. The three methods differ in the temperature range at which interruption of the rapid quench takes place, the length of time that the steel is held at this temperature, and whether the subsequent cooling to atmospheric temperature is rapid or slow, and is or is not preceded by a tempering operation.

One of the reasons for maintaining the steel at a constant temperature for a definite period of time is to permit the inside sections of the piece to reach the same temperature as the outer sections so that when transformation of the structure does take place, it will occur at about the same rate and period of time throughout the piece. In order to maintain the constant temperature required in interrupted quenching, a quenching arrangement for absorbing and dissipating a large quantity of heat without increase in temperature is needed. Molten salt baths equipped for water spray or air cooling around the exterior of the bath container have been used for this purpose.

Austempering: This is a heat-treating process in which steels are quenched in a bath maintained at some constant temperature in the range of 350 to 800 degrees F, depending on the analysis of the steel and the characteristics to be obtained. On immersion in the quenching bath, the steel is cooled more rapidly than the critical quenching rate. When the temperature of the steel reaches that of the bath, however, the quenching action is interrupted. If the steel is now held at this temperature for a predetermined length of time, say, from 10 to 60 minutes, the austenitic structure of the steel is gradually changed into a new structure, called *bainite*. The structure of bainite is acicular (needlelike) and resembles that of tempered martensite such as is usually obtained by quenching in the usual manner to atmospheric temperature and tempering at 400 degrees F or higher.

Hardnesses ranging up to 60 Rockwell C, depending on the carbon and alloy content of the steel, are obtainable and compare favorably with those obtained for the respective steels by a conventional quench and tempering to above 400 degrees F. Much greater

Copyright 2004, Industrial Press, Inc., New York, NY

toughness and ductility are obtained in an austempered piece, however, as compared with a similar piece quenched and tempered in the usual manner.

Two factors are important in austempering. First, the steel must be quenched rapidly enough to the specified subtransformation temperature to avoid any formation of pearlite, and, second, it must be held at this temperature until the transformation from austenite to bainite is completed. Time and temperature transformation curves (called S-curves because of their shape) have been developed for different steels and these curves provide important data governing the conduct of austempering, as well as the other interrupted quenching methods.

Austempering has been applied chiefly to steels having 0.60 per cent or more carbon content with or without additional low-alloy content, and to pieces of small diameter or section, usually under 1 inch, but varying with the composition of the steel. Case-hardened parts may also be austempered.

Martempering: In this process the steel is first rapidly quenched from some temperature above the transformation point down to some temperature (usually about 400 degrees F) just above that at which martensite begins to form. It is then held at this temperature for a length of time sufficient to equalize the temperature throughout the part, after which it is removed and cooled in air. As the temperature of the steel drops below the transformation point, martensite begins to form in a matrix of austenite at a fairly uniform rate throughout the piece. The soft austenite acts as a cushion to absorb some of the stresses which develop as the martensite is formed. The difficulties presented by quench cracks, internal stresses, and dimensional changes are largely avoided, thus a structure of high hardness can be obtained. If greater toughness and ductility are required, conventional tempering may follow. In general, heavier sections can be hardened more easily by the martempering process than by the austempering process. The martempering process is especially suited to the higher-alloyed steels.

Isothermal Quenching: This process resembles austempering in that the steel is first rapidly quenched from above the transformation point down to a temperature that is above that at which martensite begins to form and is held at this temperature until the austenite is completely transformed into bainite. The constant temperature to which the piece is quenched and then maintained is usually 450 degrees F or above. The process differs from austempering in that after transformation to a bainite structure has been completed, the steel is immersed in another bath and is brought up to some higher temperature, depending on the characteristics desired, and is maintained at this temperature for a definite period of time, followed by cooling in air. Thus, tempering to obtain the desired toughness or ductility takes place immediately after the structure of the steel has changed to bainite and before it is cooled to atmospheric temperature.

Laser and Electron-Beam Surface Hardening.— Industrial lasers and electron-beam equipment are now available for surface hardening of steels. The laser and electron beams can generate very intense energy fluxes and steep temperature profiles in the workpiece, so that external quench media are not needed. This self-quenching is due to a cold interior with sufficient mass acting as a large heat sink to rapidly cool the hot surface by conducting heat to the interior of a part. The laser beam is a beam of light and does not require a vacuum for operation. The electron beam is a stream of electrons and processing usually takes place in a vacuum chamber or envelope. Both processes may normally be applied to finished machined or ground surfaces, because little distortion results.

Tempering

The object of *tempering* or *drawing* is to reduce the brittleness in hardened steel and to remove the internal strains caused by the sudden cooling in the quenching bath. The tempering process consists in heating the steel by various means to a certain temperature and then cooling it. When steel is in a fully hardened condition, its structure consists largely of

Copyright 2004, Industrial Press, Inc., New York, NY

martensite. On reheating to a temperature of from about 300 to 750 degrees F, a softer and tougher structure known as *troostite* is formed. If the steel is reheated to a temperature of from 750 to 1290 degrees F, a structure known as *sorbite* is formed that has somewhat less strength than troostite but much greater ductility.

Tempering Temperatures.— If steel is heated in an oxidizing atmosphere, a film of oxide forms on the surface that changes color as the temperature increases. These oxide colors (see Table 1) have been used extensively in the past as a means of gaging the correct amount of temper; but since these colors are affected to some extent by the composition of the metal, the method is not dependable.

Table 1. Temperatures as Indicated by the Color of Plain Carbon Steel

Degrees Centi-grade	Degrees Fahrenheit	Color of Steel	Degrees Centi-grade	Degrees Fahrenheit	Color of Steel
221.1	430	Very pale yellow	265.6	510	Spotted red-brown
226.7	440	Light yellow	271.1	520	Brown-purple
232.2	450	Pale straw-yellow	276.7	530	Light purple
237.8	460	Straw-yellow	282.2	540	Full purple
243.3	470	Deep straw-yellow	287.8	550	Dark purple
248.9	480	Dark yellow	293.3	560	Full blue
254.4	490	Yellow-brown	298.9	570	Dark blue
260.0	500	Brown-yellow	337.8	640	Light blue

The availability of reliable pyrometers in combination with tempering baths of oil, salt, or lead make it possible to heat the work uniformly and to a given temperature within close limits.

Suggested temperatures for tempering various tools are given in Table 2.

Tempering in Oil.— Oil baths are extensively used for tempering tools (especially in quantity), the work being immersed in oil heated to the required temperature, which is indicated by a thermometer. It is important that the oil have a uniform temperature throughout and that the work be immersed long enough to acquire this temperature. Cold steel should not be plunged into a bath heated for tempering, owing to the danger of cracking. The steel should either be preheated to about 300 degrees F, before placing it in the bath, or the latter should be at a comparatively low temperature before immersing the steel, and then be heated to the required degree. A temperature of from 650 to 700 degrees F can be obtained with heavy tempering oils; for higher temperatures, either a bath of nitrate salts or a lead bath may be used.

In tempering, the best method is to immerse the pieces to be tempered before starting to heat the oil, so that they are heated with the oil. After the pieces tempered are taken out of the oil bath, they should be immediately dipped in a tank of caustic soda, and after that in a tank of hot water. This will remove all oil that might adhere to the tools. The following tempering oil has given satisfactory results: mineral oil, 94 per cent; saponifiable oil, 6 per cent; specific gravity, 0.920; flash point, 550 degrees F; fire test, 625 degrees F.

Tempering in Salt Baths.— Molten salt baths may be used for tempering or drawing operations. Nitrate baths are particularly adapted for the usual drawing temperature range of, say, 300 to 1100 degrees F. Tempering in an oil bath usually is limited to temperatures of 500 to 600 degrees F, and some heat-treating specialists recommend the use of a salt bath for temperatures above 350 or 400 degrees F, as it is considered more efficient and economical. Tempering in a bath (salt or oil) has several advantages, such as ease in controlling the temperature range and maintenance of a uniform temperature. The work is also heated much more rapidly in a molten bath. A gas- or oil-fired muffle or semimuffle furnace may be used for tempering, but a salt bath or oil bath is preferable. A salt bath is rec-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Tempering Temperatures for Various Plain Carbon Steel Tools

Degrees F	Class of Tool
495 to 500	Taps ½ inch or over, for use on automatic screw machines
495 to 500	Nut taps ½ inch and under
515 to 520	Taps ¼ inch and under, for use on automatic screw machines
525 to 530	Thread dies to cut thread close to shoulder
500 to 510	Thread dies for general work
495	Thread dies for tool steel or steel tube
525 to 540	Dies for bolt threader threading to shoulder
460 to 470	Thread rolling dies
430 to 435	Hollow mills (solid type) for roughing on automatic screw machines
485	Knurls
450	Twist drills for hard service
450	Centering tools for automatic screw machines
430	Forming tools for automatic screw machines
430 to 435	Cut-off tools for automatic screw machines
440 to 450	Profile cutters for milling machines
430	Formed milling cutters
435 to 440	Milling cutters
430 to 440	Reamers
460	Counterbores and countersinks
480	Cutters for tube- or pipe-cutting machines
460 to 520	Snaps for pneumatic hammers — harden full length, temper to 460 degrees, then bring point to 520 degrees

ommended for tempering high-speed steel, although furnaces may also be used. The bath or furnace temperature should be increased gradually, say, from 300 to 400 degrees F up to the tempering temperature, which may range from 1050 to 1150 degrees F for high-speed steel.

Tempering in a Lead Bath.— The lead bath is commonly used for heating steel in connection with tempering, as well as for hardening. The bath is first heated to the temperature at which the steel should be tempered; the preheated work is then placed in the bath long enough to acquire this temperature, after which it is removed and cooled. As the melting temperature of pure lead is about 620 degrees F, tin is commonly added to it to lower the temperature sufficiently for tempering. Reductions in temperature can be obtained by varying the proportions of lead and tin, as shown in Table 3.

Table 3. Temperatures of Lead Bath Alloys

Parts Lead	Parts Tin	Melting Temp., Deg. F	Parts Lead	Parts Tin	Melting Temp., Deg. F	Parts Lead	Parts Tin	Melting Temp., Deg. F
200	8	560	39	8	510	19	8	460
100	8	550	33	8	500	17	8	450
75	8	540	28	8	490	16	8	440
60	8	530	24	8	480	15	8	430
48	8	520	21	8	470	14	8	420

To Prevent Lead from Sticking to Steel.— To prevent hot lead from sticking to parts heated in it, mix common whiting with wood alcohol, and paint the part that is to be heated. Water can be used instead of alcohol, but in that case, the paint must be thoroughly dry, as

Copyright 2004, Industrial Press, Inc., New York, NY

otherwise the moisture will cause the lead to "fly." Another method is to make a thick paste according to the following formula: Pulverized charred leather, 1 pound; fine wheat flour, 1½ pounds; fine table salt, 2 pounds. Coat the tool with this paste and heat slowly until dry, then proceed to harden. Still another method is to heat the work to a blue color, or about 600 degrees F, and then dip it in a strong solution of salt water, prior to heating in the lead bath. The lead is sometimes removed from parts having fine projections or teeth, by using a stiff brush just before immersing in the cooling bath. Removal of lead is necessary to prevent the formation of soft spots.

Tempering in Sand.— The sand bath is used for tempering certain classes of work. One method is to deposit the sand on an iron plate or in a shallow box that has burners beneath it. With this method of tempering, tools such as boiler punches, etc., can be given a varying temper by placing them endwise in the sand. As the temperature of the sand bath is higher toward the bottom, a tool can be so placed that the color of the lower end will become a deep dark blue when the middle portion is a very dark straw, and the working end or top a light straw color, the hardness gradually increasing from the bottom up.

Double Tempering.— In tempering high-speed steel tools, it is common practice to repeat the tempering operation or "double temper" the steel. Double tempering is done by heating the steel to the tempering temperature (say, 1050 degrees F) and holding it at that temperature for two hours. It is then cooled to room temperature, reheated to 1050 degrees F for another two-hour period, and again cooled to room temperature. After the first tempering operation, some untempered martensite remains in the steel. This martensite is not only tempered by a second tempering operation but is relieved of internal stresses, thus improving the steel for service conditions. The hardening temperature for the higher-alloy steels may affect the hardness after tempering. For example, molybdenum high-speed steel when heated to 2100 degrees F had a hardness of 61 Rockwell C after tempering, whereas a temperature of 2250 degrees F resulted in a hardness of 64.5 Rockwell C after tempering.

Annealing, Spheroidizing, and Normalizing

Annealing of steel is a heat-treating process in which the steel is heated to some elevated temperature, usually in or near the critical range, is held at this temperature for some period of time, and is then cooled, usually at a slow rate. Spheroidizing and normalizing may be considered as special cases of annealing.

The *full annealing* of carbon steel consists in heating it slightly above the *upper* critical point for hypoeutectoid steels (steels of less than 0.85 per cent carbon content) and slightly above the *lower* critical point for hypereutectoid steels (steels of more than 0.85 per cent carbon content), holding it at this temperature until it is uniformly heated and then slowly cooling it to 1000 degrees F or below. The resulting structure is layerlike, or lamellar, in character due to the pearlite that is formed during the slow cooling.

Anealing is employed 1) to soften steel for machining, cutting, stamping, etc., or for some particular service; 2) to alter ductility, toughness, electrical or magnetic characteristics or other physical properties; 3) to refine the crystal structure; 4) to produce grain reorientation; and 5) to relieve stresses and hardness resulting from cold working.

The *spheroidizing* of steel, according to the American Society of Metals, is "any process of heating and cooling that produces a rounded or globular form of carbide." High-carbon steels are spheroidized to improve their machinability especially in continuous cutting operations such as are performed by lathes and screw machines. In low-carbon steels, spheroidizing may be employed to meet certain strength requirements before subsequent heat treatment. Spheroidizing also tends to increase resistance to abrasion.

The *normalizing* of steel consists in heating it to some temperature above that used for annealing, usually about 100 degrees F above the upper critical range, and then cooling it in still air at room temperature. Normalizing is intended to put the steel into a uniform, unstressed condition of proper grain size and refinement so that it will properly respond to

Copyright 2004, Industrial Press, Inc., New York, NY

further heat treatments. It is particularly important in the case of forgings that are to be later heat treated. Normalizing may or may not (depending on the composition) leave steel in a sufficiently soft state for machining with available tools. Annealing for machinability is often preceded by normalizing and the combined treatment — frequently called a *double anneal* — produces a better result than a simple anneal.

Annealing Practice.— For carbon steels, the following annealing temperatures are recommended by the American Society for Testing and Materials: Steels of less than 0.12 per cent carbon content, 1600 to 1700 degrees F; steels of 0.12 to 0.29 per cent carbon content, 1550 to 1600 degrees F, steels of 0.30 to 0.49 per cent carbon content, 1500 to 1550 degrees F; and for 0.50 to 1.00 per cent carbon steels, from 1450 to 1500 degrees F. Slightly lower temperatures are satisfactory for steels having more than 0.75 per cent manganese content. Heating should be uniform to avoid the formation of additional stresses. In the case of large workpieces, the heating should be slow enough so that the temperature of the interior does not lag too far behind that of the surface.

It has been found that in annealing steel, the higher the temperature to which it is heated to produce an austenitic structure, the greater the tendency of the structure to become lamellar (pearlitic) in cooling. On the other hand, the closer the austenitizing temperature to the critical temperature, the greater is the tendency of the annealed steel to become spheroidal.

Rate of Cooling: After heating the steel to some temperature within the annealing range, it should be cooled slowly enough to permit the development of the desired softness and ductility. In general, the slower the cooling rate, the greater the resulting softness and ductility. Steel of a high-carbon content should be cooled more slowly than steel of a low-carbon content; and the higher the alloy content, the slower is the cooling rate usually required. Where extreme softness and ductility are not required. the steel may be cooled in the annealing furnace to some temperature well below the critical point, say, to about 1000 degrees F and then removed and cooled in air.

Annealing by Constant-Temperature Transformation.— It has been found that steel that has been heated above the critical point so that it has an austenitic structure can be transformed into a lamellar (pearlitic) or a spheroidal structure by holding it for a definite period of time at some constant subcritical temperature. In other words, it is feasible to anneal steel by means of a constant-temperature transformation as well as by the conventional continuous cooling method. When the constant-temperature transformation method is employed, the steel, after being heated to some temperature above the critical and held at this temperature until it is austenitized, is cooled as rapidly as feasible to some relatively high subcritical transformation temperature. The selection of this temperature is governed by the desired microstructure and hardness required and is taken from a transformation time and temperature curve (often called a TTT curve). As drawn for a particular steel, such a curve shows the length of time required to transform that steel from an austenitic state at various subcritical temperatures. After being held at the selected sub-critical temperature for the required length of time, the steel is cooled to room temperature — again, as rapidly as feasible. This rapid cooling down to the selected transformation temperature and then down to room temperature has a negligible effect on the structure of the steel and often produces a considerable saving in time over the conventional slow cooling method of annealing.

The softest condition in steel can be developed by heating it to a temperature usually less than 100 degrees F above the lower critical point and then cooling it to some temperature, usually less than 100 degrees, below the critical point, where it is held until the transformation is completed. Certain steels require a very lengthy period of time for transformation of the austenite when held at a constant temperature within this range. For such steels, a practical procedure is to allow most of the transformation to take place in this temperature range where a soft product is formed and then to finish the transformation at a lower temperature where the time for the completion of the transformation is short.

Copyright 2004, Industrial Press, Inc., New York, NY

Spheroidizing Practice.— A common method of spheroidizing steel consists in heating it to or slightly below the lower critical point, holding it at this temperature for a period of time, and then cooling it slowly to about 1000 degrees F or below. The length of time for which the steel is held at the spheroidizing temperature largely governs the degree of spheroidization. High-carbon steel may be spheroidized by subjecting it to a temperature that alternately rises and falls between a point within and a point without the critical range. Tool steel may be spheroidized by heating to a temperature slightly above the critical range and then, after being held at this temperature for a period of time, cooling without removal from the furnace.

Normalizing Practice.— When using the lower-carbon steels, simple normalizing is often sufficient to place the steel in its best condition for machining and will lessen distortion in carburizing or hardening. In the medium- and higher-carbon steels, combined normalizing and annealing constitutes the best practice. For unimportant parts, the normalizing may be omitted entirely or annealing may be practiced only when the steel is otherwise difficult to machine. Both processes are recommended in the following heat treatments (for SAE steels) as representing the best metallurgical practice. The temperatures recommended for normalizing and annealing have been made indefinite in many instances because of the many different types of furnaces used in various plants and the difference in results desired.

Case Hardening

In order to harden low-carbon steel, it is necessary to increase the carbon content of the surface of the steel so that a thin outer "case" can be hardened by heating the steel to the hardening temperature and then quenching it. The process, therefore, involves two separate operations. The first is the *carburizing* operation for impregnating the outer surface with sufficient carbon, and the second operation is that of heat treating the carburized parts so as to obtain a hard outer case and, at the same time, give the "core" the required physical properties. The term "case hardening" is ordinarily used to indicate the complete process of carburizing and hardening.

Carburization.— Carburization is the result of heating iron or steel to a temperature below its melting point in the presence of a solid, liquid, or gaseous material that decomposes so as to liberate carbon when heated to the temperature used. In this way, it is possible to obtain by the gradual penetration, diffusion, or absorption of the carbon by the steel, a "zone" or "case" of higher-carbon content at the outer surfaces than that of the original object. When a carburized object is rapidly cooled or quenched in water, oil, brine, etc., from the proper temperature, this case becomes hard, leaving the inside of the piece soft, but of great toughness.

Use of Carbonaceous Mixtures.— When carburizing materials of the solid class are used, the case-hardening process consists in packing steel articles in metal boxes or pots, with a carbonaceous compound surrounding the steel objects. The boxes or pots are sealed and placed in a carburizing oven or furnace maintained usually at a temperature of from about 1650 to 1700 degrees F for a length of time depending on the extent of the carburizing action desired. The carbon from the carburizing compound will then be absorbed by the steel on the surfaces desired, and the low-carbon steel is converted into high-carbon steel at these portions. The internal sections and the insulated parts of the object retain practically their original low-carbon content. The result is a steel of a dual structure, a high-carbon and a low-carbon steel in the same piece. The carburized steel may now be heat treated by heating and quenching, in much the same way as high-carbon steel is hardened, in order to develop the properties of hardness and toughness; but as the steel is, in reality, two steels in one, one high-carbon and one low-carbon, the correct heat treatment after carburizing includes two distinct processes, one suitable for the high-carbon portion or the "case," as it is generally called, and one suitable for the low-carbon portion or core. The method of heat treatment varies according to the kind of steel used. Usually, an initial heating and slow

Copyright 2004, Industrial Press, Inc., New York, NY

cooling is followed by reheating to 1400–1450 degrees F, quenching in oil or water, and a final tempering. More definite information is given in the following section on S.A.E. steels.

Carburizers: There are many commercial carburizers on the market in which the materials used as the generator may be hard and soft wood charcoal, animal charcoal, coke, coal, beans and nuts, bone and leather, or various combinations of these. The energizers may be barium, cyanogen, and ammonium compounds, various salts, soda ash, or lime and oil hydrocarbons.

Pack-Hardening.— When cutting tools, gages, and other parts made from high-carbon steels are heated for hardening while packed in some carbonaceous material in order to protect delicate edges, corners, or finished surfaces, the process usually is known as pack-hardening. Thus, the purpose is to protect the work, prevent scale formation, ensure uniform heating, and minimize the danger of cracking and warpage. The work is packed, as in carburizing, and in the same type of receptacle. Common hardwood charcoal often is used, especially if it has had an initial heating to eliminate shrinkage and discharge its more impure gases. The lowest temperature required for hardening should be employed for pack-hardening — usually 1400 to 1450 degrees F for carbon steels. Pack-hardening has also been applied to high-speed steels, but modern developments in heat-treating salts have made it possible to harden high-speed steel without decarburization, injury to sharp edges, or marring the finished surfaces. See *Salt Baths* on page 516.

Cyanide Hardening.— When low-carbon steel requires a very hard outer surface but does not need high shock-resisting qualities, the cyanide-hardening process may be employed to produce what is known as superficial hardness. This superficial hardening is the result of carburizing a very thin outer skin (which may be only a few thousandths inch thick) by immersing the steel in a bath containing sodium cyanide. The temperatures usually vary from 1450 to 1650 degrees F and the percentage of sodium cyanide in the bath extends over a wide range, depending on the steel used and properties required.

Nitriding Process.— Nitriding is a process for surface hardening certain alloy steels by heating the steel in an atmosphere of nitrogen (ammonia gas) at approximately 950 degrees F. The steel is then cooled slowly. Finish machined surfaces hardened by nitriding are subject to minimum distortion. The physical properties, such as toughness, high impact strength, etc., can be imparted to the core by previous heat treatments and are unaffected by drawing temperatures up to 950 degrees F. The "Nitralloy" steels suitable for this process may be readily machined in the heat-treated as well as in the annealed state, and they forge as easily as alloy steels of the same carbon content. Certain heat treatments must be applied prior to nitriding, the first being annealing to relieve rolling, forging, or machining strains. Parts or sections not requiring heat treating should be machined or ground to the exact dimensions required. Close tolerances must be maintained in finish machining, but allowances for growth due to adsorption of nitrogen should be made, and this usually amounts to about 0.0005 inch for a case depth of 0.02 inch. Parts requiring heat treatment for definite physical properties are forged or cut from annealed stock, heat treated for the desired physical properties, rough machined, normalized, and finish machined. If quenched and drawn parts are normalized afterwards, the drawing and normalizing temperatures should be alike. The normalizing temperature may be below but should never be above the drawing temperature.

Ion Nitriding.— Ion nitriding, also referred to as glow discharge nitriding, is a process for case hardening of steel parts such as tool spindles, cutting tools, extrusion equipment, forging dies, gears, and crankshafts. An electrical potential ionizes low-pressure nitrogen gas, and the ions produced are accelerated to and impinge on the workpiece, heating it to the appropriate temperature for diffusion to take place. Therefore, there is no requirement for a supplemental heat source. The inward diffusion of the nitrogen ions forms the iron and

Copyright 2004, Industrial Press, Inc., New York, NY

alloy nitrides in the case. White layer formation, familiar in conventional gas nitriding, is readily controlled by this process.

Liquid Carburizing.— Activated liquid salt baths are now used extensively for carburizing. Sodium cyanide and other salt baths are used. The salt bath is heated by electrodes immersed in it, the bath itself acting as the conductor and resistor. One or more groups of electrodes, with two or more electrodes per group, may be used. The heating is accompanied by a stirring action to ensure uniform temperature and carburizing activity throughout the bath. The temperature may be controlled by a thermocouple immersed in the bath and connecting with a pyrometer designed to provide automatic regulation. The advantages of liquid baths include rapid action; uniform carburization; minimum distortion; and elimination of the packing and unpacking required when carbonaceous mixtures are used. In selective carburizing, the portions of the work that are not to be carburized are copper-plated and the entire piece is then immersed in an activated cyanide bath. The copper inhibits any carburizing action on the plated parts, and this method offers a practical solution for selectively carburizing any portion of a steel part.

Gas Carburizing.— When carburizing gases are used, the mixture varies with the type of case and quality of product desired. The gaseous hydrocarbons most widely used are methane (natural gas), propane, and butane. These carbon-bearing gases are mixed with air, with manufactured gases of several types, with flue gas, or with other specially prepared "diluent" gases. It is necessary to maintain a continuous fresh stream of carburizing gases to the carburizing retort or muffle, as well as to remove the spent gases from the muffle continuously, in order to obtain the correct mixture of gases inside the muffle. A slight pressure is maintained on the muffle to exclude unwanted gases.

The horizontal rotary type of gas carburizing furnace has a retort or muffle that revolves slowly. This type of furnace is adapted to small parts such as ball and roller bearings, chain links, small axles, bolts, etc. With this type of furnace, very large pieces such as gears, for example, may be injured by successive shocks due to tumbling within the rotor.

The vertical pit type of gas carburizer has a stationary workholder that is placed vertically in a pit. The work, instead of circulating in the gases as with the rotary type, is stationary and the gases circulate around it. This type is applicable to long large shafts or other parts or shapes that cannot be rolled in a rotary type of furnace.

There are three types of continuous gas furnaces that may be designated as
1) direct quench and manually operated
2) direct quench and mechanically operated
3) cooling-zone type

Where production does not warrant using a large continuous-type furnace, a horizontal muffle furnace of the batch type may be used, especially if the quantities of work are varied and the production not continuous.

Vacuum Carburizing.— Vacuum carburizing is a high-temperature gas carburizing process that is performed at pressures below atmospheric. The furnace atmosphere usually consists solely of an enriching gas, such as natural gas, pure methane, or propane; nitrogen is sometimes used as a carrier gas. Vacuum carburizing offers several advantages such as combining of processing operations and reduced total processing time.

Carburizing Steels.— A low-carbon steel containing, say, from 0.10 to 0.20 per cent of carbon is suitable for carburized case hardening. In addition to straight-carbon steels, the low-carbon alloy steels are employed. The alloys add to case-hardened parts the same advantageous properties that they give to other classes of steel. Various steels suitable for case hardening will be found in the section on SAE steels.

To Clean Work after Case Hardening.— To clean work, especially if knurled, or if dirt is likely to stick into crevices after case hardening, wash it in caustic soda (1 part soda to 10 parts water). In making the solution, the soda should be put into hot water gradually, and the mixture stirred until the soda is thoroughly dissolved. A still more effective method of

Copyright 2004, Industrial Press, Inc., New York, NY

cleaning is to dip the work into a mixture of 1 part sulfuric acid and 2 parts water. Leave the pieces in this mixture about three minutes; then wash them immediately in a soda solution.

Flame Hardening.— This method of hardening is especially applicable to the selective hardening of large steel forgings or castings that must be finish-machined prior to heat-treatment, or that because of size or shape cannot be heat treated by using a furnace or bath. An oxyacetylene torch is used to heat quickly the surface to be hardened; this surface is then quenched to secure a hardened layer that may vary in depth from a mere skin to ¼ inch and with hardness ranging from 400 to 700 Brinell. A multiflame torchhead may be equipped with quenching holes or a spray nozzle back of the flame. This is not a carburizing or a case-hardening process as the torch is only a heating medium. Most authorities recommend tempering or drawing of the hardened surface at temperatures between 200 and 350 degrees F. This treatment may be done in a standard furnace, an oil bath, or with a gas flame. It should follow the hardening process as closely as possible. Medium-carbon and many low-alloy steels are suitable for flame hardening. Plain carbon steels ranging from 0.35 to 0.60 per cent carbon will give hardnesses of from 400 to 700 Brinell. Steels in the 0.40 to 0.45 per cent carbon range are preferred, as they have excellent core properties and produce hardnesses of from 400 to 500 Brinell without checking or cracking. Higher-carbon steels will give greater hardnesses, but extreme care must be taken to prevent cracking. Careful control of the quenching operation is required.

Spinning Method of Flame Hardening: This method is employed on circular objects that can be rotated or spun past a stationary flame. It may be subdivided according to the speed of rotation, as where the part is rotated slowly in front of a stationary flame and the quench is applied immediately after the flame. This method is used on large circular pieces such as track wheels and bearing surfaces. There will be a narrow band of material with lower hardness between adjacent torches if more than one path of the flame is required to harden the surface. There will also be an area of lower hardness where the flame is extinguished. A second method is applicable to small rollers or pinions. The work is spun at a speed of 50 to 150 rpm in front of the flame until the entire piece has reached the proper temperature; then it is quenched as a unit by a cooling spray or by ejecting it into a cooling bath.

The Progressive Method: In this method the torch travels along the face of the work and the work remains stationary. It is used to harden lathe ways, gear teeth, and track rails.

The Stationary or Spot-hardening Method: When this method is employed, the work and torch are both stationary. When the spot to be hardened reaches the quenching temperature, the flame is removed and the quench applied.

The Combination Method: This approach is a combination of the spinning and progressive methods, and is used for long bearing surfaces. The work rotates slowly past the torch as the torch travels longitudinally across the face of the work at the rate of the torch width per revolution of the work.

Equipment for the stationary method of flame hardening consists merely of an acetylene torch, an oxyacetylene supply, and a suitable means of quenching; but when the other methods are employed, work-handling tools are essential and specialty designed torches are desirable. A lathe is ideally suited for the spinning or combination hardening method, whereas a planer is easily adapted for progressive hardening. Production jobs, such as the hardening of gears, require specially designed machines. These machines reduce handling and hardening time, as well as assuring consistent results.

Induction Hardening.— The hardening of steel by means of induction heating and subsequent quenching in either liquid or air is particularly applicable to parts that require localized hardening or controlled depth of hardening and to irregularly shaped parts, such as cams that require uniform surface hardening around their contour.

Advantages offered by induction hardening are: 1) a short heating cycle that may range from a fraction of a second to several seconds (heat energy can be induced in a piece of steel at the rate of 100 to 250 Btu per square inch per minute by induction heating, as com-

Copyright 2004, Industrial Press, Inc., New York, NY

pared with a rate of 3 Btu per square inch per minute for the same material at room temperature when placed in a furnace with a wall temperature of 2000 degrees F); 2) absence of tendency to produce oxidation or decarburization; 3) exact control of depth and area of hardening; 4) close regulation of degree of hardness obtained by automatic timing of heating and quenching cycles; 5) minimum amount of warpage or distortion; and 6) possibility of substituting carbon steels for higher-cost alloy steels.

The principal advantage of induction hardening to the designer lies in its application to localized zones. Thus, specific areas in a given part can be heat treated separately to the respective hardnesses required. Parts can be designed so that the stresses at any given point in the finished piece can be relieved by local heating. Parts can be designed in which welded or brazed assemblies are built up prior to heat treating with only internal surfaces or projections requiring hardening.

Types of Induction Heating Equipment.— Induction heating is secured by placing the metal part inside or close to an "applicator" coil of one or more turns, through which alternating current is passed. The coil, formed to suit the general class of workto be heated, is usually made of copper tubing through which water is passed to prevent overheating of the coil itself. The workpiece is held either in a fixed position or is rotated slowly within or close to the applicator coil. Where the length of work is too great to permit heating in a fixed position, progressive heating may be employed. Thus, a rod or tube of steel may be fed through an applicator coil of one or more turns so that the heating zone travels progressively along the entire length of the workpiece.

The frequency of the alternating current used and the type of generator employed to supply this current to the applicator coil depend on the character of the work to be done.

There are three types of commercial equipment used to produce high-frequency current for induction heating: 1) motor generator sets that deliver current at frequencies of approximately 1000, 2000, 3000, and 10,000 cycles; 2) spark gap oscillator units that produce frequencies ranging from 80,000 to 300,000 cycles; and 3) vacuum tube oscillator sets, which produce currents at frequencies ranging from 350,000 to 15,000,000 cycles or more.

Depth of Heat Penetration.— Generally speaking, the higher the frequency used, the shallower the depth of heat penetration. For heating clear through, for deep hardening, and for large workpieces, low power concentrations and low frequencies are usually used. For very shallow and closely controlled depths of heating, as in surface hardening, and in localized heat treating of small workpieces, currents at high frequencies are used.

For example, a ½-inch round bar of hardenable steel will be heated through its entire structure quite rapidly by an induced current of 2000 cycles. After quenching, the bar would show through hardness with a decrease in hardness from surface to center. The same piece of steel could be readily heated and surface hardened to a depth of 0.100 inch with current at 9600 cycles, and to an even shallower depth with current at 100,000 cycles. A ¼-inch bar, however, would not reach a sufficiently high temperature at 2000 cycles to permit hardening, but at 9600 cycles through hardening would be accomplished. Current at over 100,000 cycles would be needed for surface hardening such a bar.

Types of Steel for Induction Hardening.— Most of the standard types of steels can be hardened by induction heating, providing the carbon content is sufficient to produce the desired degree of hardness by quenching. Thus, low-carbon steels with a carburized case, medium- and high-carbon steels (both plain and alloy), and cast iron with a portion of the carbon in combined form, may be used for this purpose. Induction heating of alloy steels should be limited primarily to the shallow hardening type, that is those of low alloy content, otherwise the severe quench usually required may result in a highly stressed surface with consequent reduced load-carrying capacity and danger of cracking.

Through Hardening, Annealing, and Normalizing by Induction.— For through hardening, annealing, and normalizing by induction, low power concentrations are desirable to prevent too great a temperature differential between the surface and the interior of the

Copyright 2004, Industrial Press, Inc., New York, NY

work. A satisfactory rate of heating is obtained when the total power input to the work is slightly greater than the radiation losses at the desired temperature. If possible, as low a frequency should be used as is consistent with good electrical coupling. A number of applicator coils may be connected in a series so that several workpieces can be heated simultaneously, thus reducing the power input to each. Widening the spacing between work and applicator coil also will reduce the amount of power delivered to the work.

Induction Surface Hardening.— As indicated earlier in "Depth of Heat Penetration," currents at much higher frequencies are required in induction surface hardening than in through hardening by induction. In general, the smaller the workpiece, the thinner the section, or the shallower the depth to be hardened, the higher will be the frequency required. High power concentrations are also needed to make possible a short heating period so that an undue amount of heat will not be conducted to adjacent or interior areas, where a change in hardness is not desired. Generators of large capacity and applicator coils of but a few turns, or even a single turn, provide the necessary concentration of power in the localized area to be hardened.

Induction heating of internal surfaces, such as the interior of a hollow cylindrical part or the inside of a hole, can be accomplished readily with applicator coils shaped to match the cross-section of the opening, which may be round, square, elliptical or other form. If the internal surface is of short length, a multiturn applicator coil extending along its entire length may be employed. Where the power available is insufficient to heat the entire internal surface at once, progressive heating is used. For this purpose, an applicator coil of few turns — often but a single turn — is employed, and either coil or work is moved so that the heated zone passes progressively from one end of the hole or opening to the other. For bores of small diameter, a hairpin-shaped applicator, extending the entire length of the hole, may be used and the work rotated about the axis of the hole to ensure even heating.

Quenching After Induction Heating.— After induction heating, quenching may be by immersion in a liquid bath (usually oil), by liquid spray (usually water), or by self-quenching. (The term "self-quenching" is used when there is no quenching medium and hardening of the heated section is due chiefly to rapid absorption of heat by the mass of cool metal adjacent to it.) Quenching by immersion offers the advantage of even cooling and is particularly satisfactory for through heated parts. Spray quenching may be arranged so that the quenching ring and applicator coil are in the same or adjacent units, permitting the quenching cycle to follow the heating cycle immediately without removal of the work from the holding fixture. Automatic timing to a fraction of a second may also be employed for both heating and quenching with this arrangement to secure the exact degree of hardness desired. Self-quenching is applicable only in thin-surface hardening where the mass of adjacent cool metal in the part is great enough to conduct the heat rapidly out of the surface layer that is being hardened. It has been recommended that for adequate self-quenching, the mass of the unheated section should be at least ten times that of the heated shell. It has been found difficult to use the self-quenching technique to produce hardened shells of much more than about 0.060 inch thickness. Close to this limit, self-quenching can only be accomplished with the easily hardenable steels. By using a combination of self-quench and liquid quench, however, it is possible to produced hardened shells on work too thin to self-quench completely. In general, self-quenching is confined chiefly to relatively small parts and simple shapes.

Induction Hardening of Gear Teeth.— Several advantages are claimed for the induction hardening of gear teeth. One advantage is that the gear teeth can be completely machined, including shaving, when in the soft-annealed or normalized condition, and then hardened, because when induction heating is used, distortion is held to a minimum. Another advantage claimed is that bushings and inserts can be assembled in the gears before hardening. A wide latitude in choice of built-up webs and easily machined hubs is afforded because the hardness of neither web nor hub is affected by the induction-hardening operation although slight dimensional changes may occur in certain designs. Regular carbon steels can be

Copyright 2004, Industrial Press, Inc., New York, NY

used in place of alloy steels for a wide variety of gears, and a steel with a higher carbon content can frequently be substituted for a carburizing steel so that the carburizing operation can be eliminated. Another saving in time is the elimination of cleaning after hardening.

In heating spur gear teeth by induction, the gear is usually placed inside a circular unit that combines the applicator coil and quenching ring. An automatic timing device controls both the heating and quenching cycles. During the heating cycle, the gear is rotated at 25 to 35 rpm to ensure uniform heating.

In hardening bevel gears, the applicator coil is wound to conform to the face angle of the gear. In some spiral-bevel gears, there is a tendency to obtain more heat on one side of the tooth than on the other. In some sizes of spiral-bevel gears, this tendency can be overcome by applying slightly more heat to ensure hardening of the concave side. In some forms of spiral-bevel gears, it has been the practice to carburize that part of the gear surface which is to be hardened, after the teeth have been rough-cut. Carburizing is followed by the finish-cutting operation, after which the teeth can be induction heated, using a long enough period to heat the entire tooth. When the gear is quenched, only the carburized surface will become hardened.

Table 4a. Typical Heat Treatments for SAE Carbon Steels (Carburizing Grades)

SAE No.	Normalize, Deg. F	Carburize, Deg. F	Cool[a]	Reheat, Deg. F	Cool[a]	2nd Reheat, Deg. F	Cool[a]	Temper,[b] Deg. F
1010 to 1022	…	1650–1700	A	…	…	…	…	250–400
	…	1650–1700	B	1400–1450	A	…	…	250–400
	…	1650–1700	C	1400–1450	A	…	…	250–400
	…	1650–1700	C	1650–1700	B	1400–1450	A	250–400
	…	1500–1650[c,d]	B	…	…	…	…	Optional
	…	1350–1575[e,d]	D	…	…	…	…	Optional
1024	1650–1750[f]	1650–1700	E	……	…	…	…	250–400
	…	1350–1575[e,d]	D	…	…	…	…	Optional
1025 1026	…	1650–1700	A	…	…	…	…	250–400
	…	1500–1650[c,d]	B	…	…	…	…	Optional
1027	…	1350–1575[e,d]	D	…	…	…	…	Optional
1030	…	1500–1650[c,d]	B	…	…	…	…	Optional
	…	1350–1575[e,d]	D	…	…	…	…	Optional
1111 1112 1113	…	1500–1650[c,d]	B	…	…	…	…	Optional
	…	1350–1575[e,d]	D	…	…	…	…	Optional
1109 to 1120	…	1650–1700	A	…	…	…	…	250–400
	…	1650–1700	B	1400–1450	A	…	…	250–400
	…	1650–1700	C	1400–1450	A	…	…	250–400
	…	1650–1700	C	1650–1700	B	1400–1450	A	250–400
	…	1500–1650[c,d]	B	…	…	…	…	Optional
	…	1350–1575[e,d]	D	…	…	…	…	Optional
1126	…	1500–1650[c,d]	B	…	…	…	…	Optional
	…	1350–1575[e,d]	D	…	…	…	…	Optional

[a] Symbols: A = water or brine; B = water or oil; C = cool slowly; D = air or oil; E = oil; F = water, brine, or oil.

[b] Even where tempering temperatures are shown, tempering is not mandatory in many applications. Tempering is usually employed for partial stress relief and improves resistance to grinding cracks.

[c] Activated or cyanide baths.

[d] May be given refining heat as in other processes.

[e] Carbonitriding atmospheres

[f] Normalizing temperatures at least 50 deg. F above the carburizing temperature are sometimes recommended where minimum heat-treatment distortion is of vital importance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. Typical Heat Treatments for SAE Carbon Steels (Heat-Treating Grades)

SAE Number	Normalize, Deg. F		Anneal, Deg. F	Harden, Deg. F	Quench[a]	Temper, Deg. F
1025 & 1030	…		…	1575–1650	A	To Desired Hardness
1033 to 1035	…		…	1525–1575	B	
1036	1600–1700		…	1525–1575	B	
	…		…	1525–1575	B	
1038 to 1040	1600–1700		…	1525–1575	B	
	…		…	1525–1575	B	
1041	1600–1700	and/or	1400–1500	1475–1550	E	
1042 to 1050	1600–1700		…	1475–1550	B	
1052 & 1055	1550–1650	and/or	1400–1500	1475–1550	E	
1060 to 1074	1550–1650	and/or	1400–1500	1475–1550	E	
1078	…		1400–1500[a]	1450–1500	A	
1080 to 1090	1550–1650	and/or	1400–1500[a]	1450–1500	E[b]	
1095	…		1400–1500[a]	1450–1500	F	
	…		1400–1500[a]	1500–1600	E	
1132 & 1137	1600–1700	and/or	1400–1500	1525–1575	B	
1138 & 1140	…		…	1500–1550	B	
	1600–1700		…	1500–1550	B	
1141 & 1144	…		1400–1500	1475–1550	E	
	1600–1700		1400–1500	1475–1550	E	
1145 to 1151	…		…	1475–1550	B	
	1600–1700		…	1475–1550	B	

[a] Slow cooling produces a spheroidal structure in these high-carbon steels that is sometimes required for machining purposes.

[b] May be water- or brine-quenched by special techniques such as partial immersion or time quenched; otherwise they are subject to quench cracking.

Table 5a. Typical Heat Treatments for SAE Alloy Steels
(Carburizing Grades)

SAE No.	Normalize[a]	Cycle Anneal[b]	Carburized, Deg. F	Cool[c]	Reheat, Deg. F	Cool[c]	Temper,[d] Deg. F
1320	yes	…	1650–1700	E	1400–1450[e]	E	250–350
	yes	…	1650–1700	E	1475–1525[f]	E	250–350
	yes	…	1650–1700	C	1400–1450[e]	E	250–350
	yes	…	1650–1700	C	1500–1550[f]	E	250–350
	yes	…	1650–1700	E[g]	…	…	250–350
	yes	…	1500–1650[h]	E	…	…	250–350
2317	yes	yes	1650–1700	E	1375–1425[e]	E	250–350
	yes	yes	1650–1700	E	1450–1500[f]	E	250–350
	yes	yes	1650–1700	C	1375–1425[e]	E	250–350
	yes	yes	1650–1700	C	1475–1525[f]	E	250–350
	yes	yes	1650–1700	E[g]	…	…	250–350
	yes	yes	1450–1650[h]	E	…	…	250–350
2512 to 2517	yes[i]	…	1650–1700	C	1325–1375[e]	E	250–350
	yes[i]	…	1650–1700	C	1425–1475[f]	E	250–350
3115 & 3120	yes	…	1650–1700	E	1400–1450[e]	E	250–350
	yes	…	1650–1700	E	1475–1525[f]	E	250–350
	yes	…	1650–1700	C	1400–1450[e]	E	250–350
	yes	…	1650–1700	C	1500–1550[f]	E	250–350
	yes	…	1650–1700	E[g]	…	…	250–350
	yes	……	1500–1650[h]	E	…	…	250–350
3310 & 3316	yes[i]	…	1650–1700	E	1400–1450[e]	E	250–350
	yes[i]	…	1650–1700	C	1475–1500[f]	E	250–350
4017 to 4032	yes	yes	1650–1700	E[g]	…	…	250–350

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5a. ***(Continued)*** **Typical Heat Treatments for SAE Alloy Steels**
(Carburizing Grades)

SAE No.	Normalize[a]	Cycle Anneal[b]	Carburized, Deg. F	Cool[c]	Reheat, Deg. F	Cool[c]	Temper,[d] Deg. F
4119 & 4125	yes	…	1650–1700	E[g]	…	…	250–350
4317 & 4320 4608 to 4621	yes	yes	1650–1700	E	1425–1475[e]	E	250–350
	yes	yes	1650–1700	E	1475–1527[f]	E	250–350
	yes	yes	1650–1700	C	1425–1475[e]	E	250–350
	yes	yes	1650–1700	C	1475–1525[f]	E	250–350
	yes	yes	1650–1700	E[g]	…	…	250–350
	yes	yes	1650–1700	E[g]	…	…	250–350
	yes	…	1500–1650[h]	E	…	…	250–350
4812 to 4820	yes[i]	yes	1650–1700	E	1375–1425[e]	E	250–350
	yes[i]	yes	1650–1700	E	1450–1500[f]	E	250–350
	yes[i]	yes	1650–1700	C	1375–1425[e]	E	250–350
	yes[i]	yes	1650–1700	C	1450–1500[f]	E	250–350
	…	…	1650–1700	E[g]	…	…	250–350
5115 & 5120	yes	…	1650–1700	E	1425–1475[e]	E	250–350
	yes	…	1650–1700	E	1500–1550[f]	E	250–350
	yes	…	1650–1700	C	1425–1475[e]	E	250–350
	yes	…	1650–1700	C	1500–1550[f]	E	250–350
	yes	…	1500–1650[h]	E	…	…	250–350
8615 to 8625 8720	yes	yes	1650–1700	E	1475–1525[e]	E	250–350
	yes	yes	1650–1700	E	1525–1575[f]	E	250–350
	yes	yes	1650–1700	C	1475–1525[e]	E	250–350
	yes	yes	1650–1700	C	1525–1575[f]	E	250–350
	yes	yes	1650–1700	E[g]	…	…	250–350
	yes	yes	1500–1650[h]	E	…	…	250–350
9310 to 9317	yes[i]	…	1650–1700	E	1400–1450[e]	E	250–350
	yes[i]	…	1650–1700	C	1500–1525	E	250–350

[a] Normalizing temperatures should be not less than 50 deg. F higher than the carburizing temperature. Follow by air cooling.

[b] For cycle annealing, heat to normalizing temperature—hold for uniformity—cool rapidly to 1000–1250 deg. F; hold 1 to 3 hours, then air or furnace cool to obtain a structure suitable for machining and finishing.

[c] Symbols: C = cool slowly; E = oil.

[d] Tempering treatment is optional and is generally employed for partial stress relief and improved resistance to cracking from grinding operations.

[e] For use when case hardness only is paramount.

[f] For use when higher core hardness is desired.

[g] Treatment is for fine-grained steels only, when a second reheat is often unnecessary.

[h] Treatment is for activated or cyanide baths. Parts may be given refining heats as indicated for other heat-treating processes.

[i] After normalizing, reheat to temperatures of 1000–1200 deg. F and hold approximately 4 hours.

Metallography.— The science or study of the microstructure of metal is known by most metallurgists as "metallography" or sometimes "crystallography". The examination of metals and metal alloys by the aid of the microscope is one of the most effective methods of studying their properties, and is also a valuable means of controlling the quality of manufactured metallic articles and of testing the finished product. In preparing the specimen, a flat surface is first formed by filing or grinding, and then given a high polish, which is later etched in order to reveal clearly the internal structure under the microscope. This process shows clearly to an experienced observer the effect of variation in composition, heat-treatment, etc., and in many cases it has proved a correct means of determining certain properties of industrial products that a chemical analysis has failed to reveal.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5b. Typical Heat Treatments for SAE Alloy Steels (Directly Hardenable Grades)

SAE No.	Normalize, Deg. F		Anneal, Deg. F	Harden, Deg. F	Quench[a]	Temper, Deg. F
1330	…		…	1525–1575	B	To desired hardness
	1600–1700	and/or	1500–1600	1525–1575	B	
1335 & 1340	…		…	1500–1550	E	
	1600–1700	and/or	1500–1600	1525–1575	E	
2330	…		…	1450–1500	E	
	1600–1700	and/or	1400–1500	1450–1500	E	
2340 & 2345	…		…	1425–1475	E	
	1600–1700	and/or	1400–1500	1425–1475	E	
3130	1600–1700		…	1500–1550	B	
3135 to 3141	…		…	1500–1550	E	
	1600–1700	and/or	1450–1550	1500–1550	E	
3145 & 3150	…		…	1500–1550	E	
	1600–1700	and/or	1400–1500	1500–1550	E	
4037 & 4042	…		1525–1575	1500–1575	E	Gears, 350–450 To desired hardness
4047 & 4053	…		1450–1550	1500–1575	E	To desired hardness
4063 & 4068	…		1450–1550	1475–1550	E	
4130	1600–1700	and/or	1450–1550	1600–1650	B	
4137 & 4140	1600–1700	and/or	1450–1550	1550–1600	E	
4145 & 4150	1600–1700	and/or	1450–1550	1500–1600	E	
4340	1600–1700	and draw	1100–1225	1475–1525	E	
4640	1600–1700	and/or	1450–1550	1450–1500	E	To desired hardness
	1600–1700	and/or	1450–1500	1450–1500	E	Gears, 350–450
5045 & 5046	1600–1700	and/or	1450–1550	1475–1500	E	250–300
5130 & 5132	1650–1750	and/or	1450–1550	1500–1550	G	To desired hardness
5135 to 5145	1650–1750	and/or	1450–1550	1500–1550	E	To desired hardness Gears, 350–400
5147 to 5152	1650–1750	and/or	1450–1550	1475–1550	E	To desired hardness Gears, 350–400
50100 51100 52100	… …		1350–1450 1350–1450	1425–1475 1500–1600	H E	To desired hardness
6150	1650–1750	and/or	1550–1650	1600–1650	E	To desired hardness
9254 to 9262	…		…	1500–1650	E	
8627 to 8632	1600–1700	and/or	1450–1550	1550–1650	B	
8635 to 8641	1600–1700	and/or	1450–1550	1525–1575	E	
8642 to 8653	1600–1700	and/or	1450–1550	1500–1550	E	
8655 & 8660	1650–1750	and/or	1450–1550	1475–1550	E	
8735 & 8740	1600–1700	and/or	1450–1550	1525–1575	E	
8745 & 8750	1600–1700	and/or	1450–1500	1500–1550	E	
9437 & 9440	1600–1700	and/or	1450–1550	1550–1600	E	
9442 to 9747	1600–1700	and/or	1450–1550	1500–1600	E	
9840	1600–1700	and/or	1450–1550	1500–1550	E	
9845 & 9850	1600–1700	and/or	1450–1550	1500–1550	E	

[a] Symbols: B = water or oil; E = oil; G = water, caustic solution, or oil; H = water.

Table 5c. Typical Heat Treatments for SAE Alloy Steels
(Heat-Treating Grades—Chromium–Nickel Austenitic Steels)

SAE No.	Normalize	Anneal,[a] Deg. F	Harden, Deg. F	Quenching Medium	Temper
30301 to 30347	…	1800–2100	…	Water or Air	…

[a] Quench to produce full austenitic structure using water or air in accordance with thickness of section. Annealing temperatures given cover process and full annealing as used by industry, the lower end of the range being used for process annealing.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5d. Typical Heat Treatments for SAE Alloy Steels
(Heat-Treating Grades—Stainless Chromium Irons and Steels)

SAE No.[a]	Normalize	Sub-critical Anneal, Deg. F	Full Anneal Deg. F	Harden Deg. F	Quenching Medium	Temper Deg. F
51410	…	1300–1350[b]	1550–1650[c]	…	Oil or air	To desired hardness
	…	…	…	1750–1850		
51414	…	1200–1250[b]	…	…	Oil or air	To desired hardness
	…	…	…	1750–1850		
51416	…	1300–1350[b]	1550–1650[c]	…	Oil or air	To desired hardness
	…	…	…	1750–1850		
51420 51420F	…	1350–1450[b]	1550–1650[c]	…	Oil or air	To desired hardness
	…	…	…	1800–1850		
51430	…	1400–1500[d]	…	…	…	…
51430F	…	1250–1500[d]	…	…	…	…
51431	…	1150–1225[b]	…	1800–1900	Oil or air	To desired hardness
51440A 51440B 51440C 51440F	…	1350–1440[b]	1550–1650[c]	1850–1950	Oil or air	To desired hardness
51442	…	1400–1500[d]	…	…	…	…
51446	…	1500–1650[d]	…	…	…	…
51501	…	1325–1375[b]	1525–1600[c]	1600–1700	Oil or air	To desired hardness

[a] Suffixes A, B, and C denote steels differing in carbon content only. Suffix F denotes a free-machining steel.
[b] Usually air cooled, but may be furnace cooled.
[c] Cool slowly in furnace.
[d] Cool rapidly in air.

Table 6. Typical SAE Heat Treatments for Grades of Chromium–Nickel Austenitic Steels Not Hardenable by Thermal Treatment

SAE Steels	AISI No.	Annealing[a] Temperature (degrees F)	Annealing Temperature (deg. C)	Quenching Medium
30201	201	1850–2050	1010–1120	Air
30202	202	1850–2050	1010–1120	Air
30301	301	1850–2050	1010–1120	Air
30302	302	1850–2050	1010–1120	Air
30303	303	1850–2050	1010–1120	Air
30304	304	1850–2050	1010–1120	Air
30305	305	1850–2050	1010–1120	Air
30309	309	1900–2050	1040–1120	Air
30310	310	1900–2100	1040–1150	Air
30316	316	1850–2050	1010–1120	Air
30317	317	1850–2050	1010–1120	Air
30321	321	1750–2050	955–1120	Air
30325	325	1800–2100	980–1150	Air
30330	…	1950–2150	1065–1175	Air
30347	347	1850–2050	1010–1120	Air

[a] Quench to produce full austenitic structure in accordance with the thickness of the section. Annealing temperatures given cover process and full annealing as already established and used by industry, the lower end of the range being used for process annealing.

Source: SAE Handbook, 1990. Reprinted with permission. Copyright © 1990. Society of Automotive Engineers, Inc. All rights reserved.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Typical SAE Heat Treatments for Stainless Chromium Steels

SAE Steels	AISI No.	Normalizing Temperature (degrees F)	Subcritical Annealing Temperature (degrees F)	Full Annealing[a] Temperature (degrees F)	Hardening Temperature (degrees F)	Quenching Medium	Temper
51409	…	…	…	1625	…	Air	…
51410	410	…	1300–1350[b]	1500–1650	…	Oil or air	To desired hardness
		…	…	…	1700–1850		
51414	414	…	1200–1250[b]	…	…	Oil or air	To desired hardness
		…	…	…	1800–1900		
51416	416	…	1300–1350[c]	1500–1650	…	Oil or air	To desired hardness
		…	…	…	1700–1850		
51420	420	…	1350–1450[b]	1550–1650	…	Oil or air	To desired hardness
		…	…	…	1800–1900		
51420F[d]	…	…	1350–1450[b]	1550–1650	…	Oil or air	To desired hardness
		…	…	…	1800–1900		
51430	430	…	1400–1500[c]	…	…	…	…
51430F[d]	…	…	1250–1400[c]	…	…	…	…
51431	431	…	1150–1225[b]	…	1800–1950	Oil or air	To desired hardness
51434	…	…	1400–1600[c]	…	…	…	…
51436	…						
51440A[d]	440A[d]						
51440B[d]	440B[d]	…	1350–1440[b]	1550–1650	1850–1950	Oil or air	To desired hardness
51440C[d]	440C[d]						
51440F[d]	…						
51442	442	…	1350–1500[c]	…	…	…	…
51446	446	…	1450–1600[b]	…	…	…	…
51501	501	…	1325–1375[c]	1525–1600	1600–1700	Oil or air	To desired hardness

[a] Cool slowly in furnace.
[b] Usually air cooled but may be furnace cooled.
[c] Cool rapidly in air.
[d] Suffixes A, B, and C denote three types of steel differing only in carbon content. Suffix F denotes a free-machining steel.

Source: SAE Handbook, 1990. Reprinted with permission. Copyright © 1990. Society of Automotive Engineers, Inc. All rights reserved.

Copyright 2004, Industrial Press, Inc., New York, NY

Heat Treating High-Speed Steels

Cobaltcrom Steel.— A tungstenless alloy steel or high-speed steel that contains approximately 1.5 per cent carbon, 12.5 per cent chromium, and 3.5 per cent cobalt. Tools such as dies and milling cutters, made from cobaltcrom steel can be cast to shape in suitable molds, the teeth of cutters being formed so that it is necessary only to grind them.

Before the blanks can be machined, they must be annealed; this operation is performed by pack annealing at the temperature of 1800 degrees F, for a period of from three to six hours, according to the size of the castings being annealed. The following directions are given for the hardening of blanking and trimming dies, milling cutters, and similar tools made from cobaltcrom steel: Heat slowly in a hardening furnace to about 1830 degrees F, and hold at this temperature until the tools are thoroughly soaked. Reduce the temperature about 50 degrees, withdraw the tools from the furnace, and allow them to cool in the atmosphere. As soon as the red color disappears from the cooling tool, place it in quenching oil until cold. The slight drop of 50 degrees in temperature while the tool is still in the hardening furnace is highly important to obtain proper results. The steel will be injured if the tool is heated above 1860 degrees F. In cooling milling cutters or other rotary tools, it is suggested that they be suspended on a wire to ensure a uniform rate of cooling.

Tools that are to be subjected to shocks or vibration, such as pneumatic rivet sets, shear blades, etc., should be heated slowly to 1650 degrees F, after which the temperature should be reduced to about 1610 degrees F, at which point the tool should be removed from the furnace and permitted to cool in the atmosphere. No appreciable scaling occurs in the hardening of cobaltcrom steel tools.

Preheating Tungsten High-Speed Steel.— Tungsten high-speed steel must be hardened at a very high temperature; consequently, tools made from such steel are seldom hardened without at least one preheating stage to avoid internal strain. This requirement applies especially to milling cutters, taps, and other tools having thin teeth and thick bodies and to forming tools of irregular shape and section. The tools should be heated slowly and carefully to a temperature somewhat below the critical point of the steel, usually in the range of 1500 to 1600 degrees F. Limiting the preheating temperature prevents the operation from being unduly sensitive, and the tool may be safely left in the furnace until it reaches a uniform temperature throughout its length and cross-section.

A single stage of preheating is customary for tools of simple form that are not more than from 1 to 1½ inches in thickness. For large, intricate tools, two stages of preheating are frequently used. The first brings the tool up to a temperature of about 1100 to 1200 degrees F, and the second raises its temperature to 1550 to 1600 degrees F. A preheating time of 5 minutes for each ¼ inch in tool thickness has been recommended for a furnace temperature of 1600 degrees F. This is where a single stage of preheating is used and the furnace capacity should be sufficient to maintain practically constant temperature when the tools are changed. To prevent undue chilling, it is common practice to insert a single tool or a small lot in the hardening furnace whenever a tool or lot is removed, rather than to insert a full charge of cold metal at one time.

Preheating is usually done in a simple type of oven furnace heated by gas, electricity, or oil. Atmospheric control is seldom used, although for 18–4–1 steel a slightly reducing atmosphere (2 to 6 per cent carbon monoxide) has been found to produce the least amount of scale and will result in a better surface after final hardening.

Hardening of Tungsten High-Speed Steel.— All tungsten high-speed steels must be heated to a temperature close to their fusion point to develop their maximum efficiency as metal-cutting tools. Hardening temperatures ranging from 2200 to 2500 deg. F may be needed. The effects of changes in the hardening temperature on the cutting efficiency of several of the more common high-speed steels are shown in Table 1. The figures given are ratios, the value 1.00 for each steel being assigned to the highest observed cutting speed for

Copyright 2004, Industrial Press, Inc., New York, NY

that steel. The figures for different steels, therefore, cannot be directly compared with each other, except to note changes in the point of maximum cutting efficiency.

Table 1. Relation of Hardening Temperature to Cutting Efficiency

Hardening Temperature, Deg. F	Typical Analyses of High-Speed Steels			
	18 – 4 – 1	14 – 4 – 2	18 – 4 –1 Cobalt	14 – 4 – 2 Cobalt
2200	0.86	0.83	0.84	0.85
2250	0.88	0.88	0.86	0.88
2300	0.90	0.93	0.90	0.91
2350	0.95	0.98	0.94	0.94
2400	0.99	0.98	0.98	0.98
2450	1.00	…	0.99	1.00
2500	0.98	…	1.00	0.97

The figures in the table refer to tools heated in an oven-type furnace in which a neutral atmosphere is maintained. The available data indicate that a steel reaches its best cutting qualities at a temperature approximately 50 deg. F lower than the figures in the table if it is hardened in a bath-type furnace. It is, however, desirable to use a hardening temperature approximately 50 deg. F lower than that giving maximum cutting qualities, to avoid the possibility of overheating the tool.

Length of Time for Heating: The cutting efficiency of a tool is affected by the time that it is kept at the hardening temperature, almost as much as by the hardening temperature itself. It has been common practice to heat a tool for hardening until a "sweat" appeared on its surface. This sweat is presumably a melting of the oxide film on the surface of a tool heated in an oxidizing atmosphere. It does not appear when the tool is heated in an inert atmosphere. This method of determining the proper heating time is at best an approximation and indicates only the temperature on the outside of the tool rather than the condition of the interior. As such, it cannot be relied upon to give consistent results.

The only safe method is to heat the tool for a definite predetermined time, based on the size and the thickness of metal that the heat must penetrate to reach the interior. The values given in Table 2 are based on a series of experiments to determine the relative cutting efficiency of a group of tools hardened in an identical manner, except for variations in the time the tools were kept at the hardening temperature. The time given is based on that required to harden throughout a tool resting on a conducting hearth; the tool receives heat freely from three sides, on its large top surface and its smaller side surfaces. (The table does not apply to a disk lying flat on the hearth.) For a tool having a projecting cutting edge, such as a tap, the thickness or depth of the projecting portion on which the cutting edge is formed should be used when referring to the table.

Table 2. Length of Heating Time for Through Hardening

High-Speed Steel Tool Thickness, in Inches	Time in Furnace at High Heat, in Minutes	High-Speed Steel Tool Thickness, in Inches	Time in Furnace at High Heat, in Minutes	High-Speed Steel Tool Thickness, in Inches	Time in Furnace at High Heat, in Minutes
¼	2	1½	7	5	18
½	3	2	8	6	20
¾	4	3	12	8	25
1	5	4	15	10	30

The time periods given in Table 2 are based on complete penetration of the hardening effect. For very thick tools, the practical procedure is to harden to a depth sufficient to produce an adequate cutting edge, leaving the interior of the tool relatively soft.

Copyright 2004, Industrial Press, Inc., New York, NY

Where atmosphere control is not provided, it often will be found impracticable to use both the temperature for maximum cutting efficiency, given in Table 1, and the heating time, given in Table 2, because abnormal scaling, grain growth, and surface decarburization of the tool will result. The principal value of an accurate control of the furnace atmosphere appears to lie in the fact that its use makes possible the particular heat treatment that produces the best structure in the tool without destruction of the tool surface or grain.

Quenching Tungsten High-Speed Steel.— High-speed steel is usually quenched in oil. The oil bath offers a convenient quench; it calls for no unusual care in handling and brings about a uniform and satisfactory rate of cooling, which does not vary appreciably with the temperature of the oil. Some authorities believe it desirable to withdraw the tool from the oil bath for a few seconds after it has reached a dull red. It is also believed desirable to move the tool around in the quenching oil, particularly immediately after it has been placed in it, to prevent the formation of a gas film on the tool. Such a film is usually a poor conductor of heat and slows the rate of cooling.

Salt Bath: Quenching in a lead or salt bath at from 1000 to 1200 deg. F has the advantage that cooling of the tool from hardening to room temperature is accomplished in two stages, thus reducing the possibility of setting up internal strains that may tend to crack the tool. The quenching temperature is sufficiently below the lower critical point for a tool so quenched to be allowed to cool to room temperature in still air. This type of quench is particularly advantageous for tools of complicated section that would easily develop hardening cracks. The salt quench has the advantage that the tool sinks and requires only a support, whereas the same tool will float in the lead bath and must be held under the surface. It is believed that the lead quench gives a somewhat higher matrix hardness, and is of advantage for tools that tend to fail by nose abrasion. Tools treated as described are brittle unless given a regular tempering treatment, because the 1000-deg. F quenching temperature is not a substitute for later tempering at the same temperature, after the tool has cooled to room temperature.

Air Cooling: Many high-speed steel tools are quenched in air, either in a stream of dry compressed air or in still air. Small sections harden satisfactorily in still air, but heavier sections should be subjected to air under pressure. One advantage of air cooling is that the tool can be kept straight and free from distortion, although it is likely that there will be more scale on a tool thus quenched than when oil, lead, or salt is used. Cooling between steel plates may help to keep thin flat tools straight and flat.

Straightening High-Speed Tools when Quenching.— The final straightness required in a tool must be considered when it is quenched. When several similar tools are to be hardened, a jig can be used to advantage for holding the tools while quenching. When long slender tools are quenched without holders, they frequently warp and must be straightened later. The best time for this straightening is during the first few minutes after the tools have been quenched, as the steel is then quite pliable and may be straightened without difficulty. The straightening must be done at once, as the tools become hard in a few minutes.

Anneal Before Rehardening.— Tools that are too soft after hardening must be annealed before rehardening. A quick anneal, such as previously described, is all that is required to put such a tool into the proper condition for rehardening. This treatment is absolutely essential. For milling cutters and forming tools of irregular section, a full anneal should be used.

Tempering or Drawing Tungsten High-Speed Steel.— The tempering or drawing temperature for high-speed steel tools usually varies from 900 to 1200 deg. F. This temperature is higher for turning and planing tools than for such tools as milling cutters, forming tools, etc. If the temperature is below 800 deg. F, the tool is likely to be too brittle. The general idea is to temper tools at the highest temperature likely to occur in service. Because this temperature ordinarily would not be known, the general practice is to temper at whatever temperature experience with that particular steel and tool has proved to be the best.

Copyright 2004, Industrial Press, Inc., New York, NY

The furnace used for tempering usually is kept at a temperature of from 1000 to 1100 deg. F for ordinary high-speed steels and from 1200 to 1300 deg. F for steels of the cobalt type. These furnace temperatures apply to tools of the class used on lathes and planers. Such tools, in service, frequently heat to the point of visible redness. Milling cutters, forming tools, or any other tools for lighter duty may be tempered as low as 850 or 900 deg. F. When the tool has reached the temperature of the furnace, it should be held at this temperature for from one to several hours until it has been heated evenly throughout. It should then be allowed to cool gradually in the air and in a place that is dry and free from air drafts. In tempering, the tool should not be quenched, because quenching tends to produce strains that may result later in cracks.

Annealing Tungsten High-Speed Steel.— The following method of annealing high-speed steel has been used extensively. Use an iron box or pipe of sufficient size to allow at least ½ inch of packing between the pieces of steel to be annealed and the sides of the box or pipe. It is not necessary that each piece of steel be kept separate from every other piece, but only that the steel be prevented from touching the sides of the annealing pipe or box. Pack carefully with powdered charcoal, fine dry lime, or mica (preferably charcoal), and cover with an airtight cap or lute with fire clay; heat slowly to 1600 to 1650 deg. F and keep at this heat from 2 to 8 hours, depending on the size of the pieces to be annealed. A piece measuring 2 by 1 by 8 inches requires about 3 hours. Cool as slowly as possible, and do not expose to the air until cold, because cooling in air is likely to cause partial hardening. A good method is to allow the box or pipe to remain in the furnace until cold.

Hardening Molybdenum High-Speed Steels.— Table 3 gives the compositions of several molybdenum high-speed steels that are widely used for general commercial tool applications. The general method of hardening molybdenum high-speed steels resembles that used for 18–4–1 tungsten high-speed steel except that the hardening temperatures are lower and more precautions must be taken to avoid decarburization, especially on tools made from Type I or Type II steels, when the surface is not ground after hardening. Either salt baths or atmosphere-controlled furnaces are recommended for hardening molybdenum high-speed steels.

Table 3. Compositions of Molybdenum High-Speed Steels

Element	Molybdenum–Tungsten		Molybdenum–Vanadium	Tungsten–Molybdenum
	Type Ia (Per Cent)	Type Ib[a] (Per Cent)	Type II (Per Cent)	Type III (Per Cent)
Carbon	0.70–0.85	0.76–0.82	0.70–0.90	0.75–0.90
Tungsten	1.25–2.00	1.60–2.30	…	5.00–6.00
Chromium	3.00–5.00	3.70–4.20	3.00–5.00	3.50–5.00
Vanadium	0.90–1.50	1.05–1.35	1.50–2.25	1.25–1.75
Molybdenum	8.00–9.50	8.00–9.00	7.50–9.50	3.50–5.50
Cobalt	See footnote	4.50–5.50	See footnote	See footnote

[a] Cobalt may be used in any of these steels in varying amounts up to 9 per cent, and the vanadium content may be as high as 2.25 percent. When cobalt is used in Type III steel, the vanadium content may be as high as 2.25 per cent. When cobalt is used in Type III steel, this steel becomes susceptible to decarburization. As an illustration of the use of cobalt, Type Ib steel is included. This is steel T10 in the U.S. Navy Specification 46S37, dated November 1, 1939.

The usual method is to preheat uniformly in a separate furnace to 1250 to 1550 deg. F then transfer to a high-heat furnace maintained within the hardening temperature range given in Table 4. Single-point cutting tools, in general, should be hardened at the upper end of the temperature range indicated by Table 4. Slight grain coarsening is not objectionable in such tools when they are properly supported in service and are not subjected to chattering; however, when these tools are used for intermittent cuts, it is better to use the middle of the temperature range. All other cutting tools, such as drills, countersinks, taps, milling

Copyright 2004, Industrial Press, Inc., New York, NY

cutters, reamers, broaches, and form tools, should be hardened in the middle of the range shown. For certain tools, such as slender taps, cold punches, and blanking and trimming dies, where greater toughness to resist shocks is required, the lower end of the hardening temperature range should be used.

Table 4. Heat Treatment of Molybdenum High-Speed Steels

Heat-Treating Operation	Molybdenum–Tungsten Types Ia and Ib[a] (Temp., in Deg. F)	Molybdenum–Vanadium Type II (Temp., in Deg. F)	Tungsten–Molybdenum Type III (Temp., in Deg. F)
Forging	1850–2000	1850–2000	1900–2050
Not below	1600	1600	1600
Annealing	1450–1550	1450–1550	1450–1550
Strain relief	1150–1350	1150–1350	1150–1350
Preheating	1250–1500	1250–1500	1250–1550
Hardening[b]	2150–2250[a]	2150–2250	2175–2275
Salt	2150–2225	2150–2225	2150–2250
Tempering	950–1100	950–1100	950–1100

[a] For similar working conditions, Type Ib steel requires a slightly higher hardening heat than Type Ia.

[b] The higher side of the hardening range should be used for large sections, and the lower side for small sections.

Molybdenum high-speed steels can be pack-hardened following the same practice as is used for tungsten high-speed steels, but keeping on the lower side of the hardening range (approximately 1850 degrees F). Special surface treatments such as nitriding by immersion in molten cyanide that are used for tungsten high-speed steels are also applicable to molybdenum high-speed tools.

When heated in an open fire or in furnaces without atmosphere control, these steels do not sweat like 18–4–1 steels; consequently, determining the proper time in the high-heat chamber is a matter of experience. This time approximates that used with 18–4–1 steels, although it may be slightly longer when the lower part of the hardening range is used. Much can be learned by preliminary hardening of test pieces and checking on the hardness fracture and structure. It is difficult to give the exact heating time, because it is affected by temperature, type of furnace, size and shape, and furnace atmosphere. Rate of heat transfer is most rapid in salt baths, and slowest in controlled-atmosphere furnaces with high carbon monoxide content.

Quenching and Tempering of Molybdenum High-Speed Tools.— Quenching may be done in oil, air, or molten bath. To reduce the possibility of breakage and undue distortion of intricately shaped tools, it is advisable to quench in a molten bath at approximately 1100 degrees F. The tool also may be quenched in oil and removed while still red, or at approximately 1100 degrees F. The tool is then cooled in air to room temperature, and tempered immediately to avoid cracking.

When straightening is necessary, it should be done after quenching and before cooling to room temperature prior to tempering.

To temper, the tools should be reheated slowly and uniformly to 950 to 1100 degrees F. For general work, 1050 degrees F is most common. The tools should be held at this temperature at least 1 hour. Two hours is a safer minimum, and 4 hours is maximum. The time and temperature depend on the hardness and toughness required. Where tools are subjected to more or less shock, multiple temperings are suggested.

Protective Coatings for Molybdenum Steels.— To protect the surface from oxidation during heat treatment, borax may be applied by sprinkling it lightly over the steel when the latter is heated in a furnace to a low temperature (1200 to 1400 deg. F). Small tools may be rolled in a box of borax before heating. Another method more suitable for finished tools is

Copyright 2004, Industrial Press, Inc., New York, NY

to apply the borax or boric acid in the form of a supersaturated water solution. The tools are then immersed in the solution at 180 to 212 deg. F, or the solution may be applied with a brush or spray. Pieces so treated are heated as usual, taking care in handling to ensure good adherence of the coating. Special protective coatings or paints, when properly applied, have been found extremely useful. These materials do not fuse or run at the temperatures used, and therefore do not affect the furnace hearth. When applying these coatings, it is necessary to have a surface free from scale or grease to ensure good adherence. Coatings may be sprayed or brushed on, and usually one thin coat is sufficient. Heavy coats tend to pit the surface of the tool and are difficult to remove. Tools covered with these coatings should be allowed to dry before they are charged into the preheat furnace. After hardening and tempering, the coating can be easily removed by light blasting with sand or steel shot. When tools are lightly ground, these coatings come off immediately. Protection may also be obtained by wrapping pieces in stainless steel foil.

Nitriding High-Speed Steel Tools.— Nitriding is applied to high-speed steel for the purpose of increasing tool life by producing a very hard skin or case, the thickness of which ordinarily is from 0.001 to 0.002 inch. Nitriding is done after the tool has been fully heat treated and finish-ground. (The process differs entirely from that which is applied to surface harden certain alloy steels by heating in an atmosphere of nitrogen or ammonia gas.) The temperature of the high-speed steel nitriding bath, which is a mixture of sodium and potassium cyanides, is equal to or slightly lower than the tempering temperature. For ordinary tools, this temperature usually varies from about 1025 to 1050 deg. F; but if the tools are exceptionally fragile, the range may be reduced to 950 or 1000 deg. F. Accurate temperature control is essential to prevent exceeding the final tempering temperature. The nitriding time may vary from 10 or 15 minutes to 30 minutes or longer, and should be determined by experiment. The shorter periods are applied to tools for iron or steel, or any shock-resisting tools, and the longer periods are for tools used in machining nonferrous metals and plastics. This nitriding process is applied to tools such as hobs, reamers, taps, box tools, form tools, and milling cutters. Nitriding may increase tool life 50 to 200 per cent, or more, but it should always be preceded by correct heat treatment.

Nitriding Bath Mixtures and Temperatures: A mixture of 60 per cent sodium cyanide and 40 per cent potassium cyanide is commonly used for nitriding. This mixture has a melting point of 925 deg. F, which is gradually reduced to 800 deg. F as the cyanate content of the bath increases. A more economical mixture of 70 per cent sodium cyanide and 30 per cent potassium cyanide may be used if the operating temperature of the bath is only 1050 deg. F. Nitriding bath temperatures should not exceed 1100 deg. F because higher temperatures accelerate the formation of carbonate at the expense of the essential cyanide. A third mixture suitable for nitriding consists of 55 per cent sodium cyanide, 25 per cent potassium chloride, and 20 per cent sodium carbonate. This mixture melts at 930 deg. F.

Equipment for Hardening High-Speed Steel.— Equipment for hardening high-speed steel consists of a hardening furnace capable of maintaining a temperature of 2350 to 2450 deg. F; a preheating furnace capable of maintaining a temperature of 1700 to 1800 deg. F, and of sufficient size to hold a number of pieces of the work; a tempering (drawing) furnace capable of maintaining a temperature of 1000 to 1200 deg. F as a general rule; and a water-cooled tank of quenching oil.

High-speed steels usually are heated for hardening either in some type of electric furnace or in a gas-fired furnace of the muffle type. The small furnaces used for high-speed steel seldom are oil-fired. It is desirable to use automatic temperature control and, where an oven type of furnace is employed, a controlled atmosphere is advisable because of the variations in cutting qualities caused by hardening under uncontrolled conditions. Some furnaces of both electric and fuel-fired types are equipped with a salt bath suitable for high-speed steel hardening temperatures. Salt baths have the advantage of providing protection against the atmosphere during the heating period. A type of salt developed for commercial use is water-soluble, so that all deposits from the hardening bath may be removed by

Copyright 2004, Industrial Press, Inc., New York, NY

immersion in water after quenching in oil or salt, or after air cooling. One type of electric furnace heats the salt bath internally by electrodes immersed in it. The same type of furnace is also applied to various heat-treating operations, such as cyanide hardening, liquid carburizing, tempering, and annealing.

An open-forge fire has many disadvantages, especially in hardening cutters or other tools that cannot be ground all over after hardening. The air blast decarburizes the steel and lack of temperature control makes it impossible to obtain uniform results. Electric and gas furnaces provide continuous uniform heat, and the temperature may be regulated accurately, especially when pyrometers are used. In shops equipped with only one furnace for carbon steel and one for high-speed steel, the tempering can be done in the furnace used for hardening carbon steel after the preheating is finished and the steel has been removed for hardening.

Heating High-Speed Steel for Forging.— Care should be taken not to heat high-speed steel for forging too abruptly. In winter, the steel may be extremely cold when brought into the forge shop. If the steel is put directly into the hot forge fire, it is likely to develop cracks that will show up later in the finished tool. The steel, therefore, should be warmed gradually before heating for forging.

Subzero Treatment of Steel

Subzero treatment consists of subjecting the steel, after hardening and either before or after tempering, to a subzero temperature (that usually ranges from −100 to −120 deg. F) and for a period of time varying with the size or volume of the tool, gage, or other part. Commercial equipment is available for obtaining these low temperatures.

The subzero treatment is employed by most gage manufacturers to stabilize precision gages and prevent subsequent changes in size or form. Subzero treatment is also applied to some high-speed steel cutting tools. The object here is to increase the durability or life of the tools; however, up to the present time, the results of tests by metallurgists and tool engineers often differ considerably and in some instances are contradictory. Methods of procedure also vary, especially with regard to the order and number of operations in the complete heat-treating and cooling cycle.

Changes Resulting From Subzero Treatment.— When steel is at the hardening temperature it contains a solid solution of carbon and iron known as *austenite*. When the steel is hardened by sudden cooling, most of the austenite, which is relatively soft, tough, and ductile even at room temperatures, is transformed into martensite, a hard and strong constituent. If all the austenite were changed to martensite upon reaching room temperature, this process would be an ideal hardening operation, but many steels retain some austenite. In general, the higher the carbon and alloy contents and the higher the hardening temperature, the greater the tendency to retain austenite. When steel is cooled to subzero temperatures, the stability of the retained austenite is reduced so that it is more readily transformed. To obtain more complete transformation, the subzero treatment may be repeated. The ultimate transformation of austenite to martensite may take place in carbon steel without the aid of subzero treatment, but this natural transformation might require 6 months or longer, whereas by refrigeration this change occurs in a few hours.

The thorough, uniform heating that is always recommended in heat-treating operations should be accompanied by thorough, uniform cooling when the subzero treatment is applied. To ensure uniform cooling, the subzero cooling period should be increased for the larger tools and it may range from 2 to 6 hours. The tool or other part is sometimes surrounded by one or more layers of heavy wrapping or asbestos paper to delay the cooling somewhat and ensure uniformity. After the cooling cycle is started, it should continue without interruption.

Subzero treatment may sometimes cause cracking. Normally, the austenite in steel provides a cushioning effect that may prevent cracking or breakage resulting from treatments

Copyright 2004, Industrial Press, Inc., New York, NY

involving temperature and dimensional changes; but if this cushioning effect is removed, particularly at very low temperatures as in subzero treatments, there may be danger of cracking, especially with tools having large or irregular sections and sharp corners offering relatively low resistance to stresses. This effect is one reason why subzero treatments may differ in regard to the cooling and tempering cycle.

Stabilizing Dimensions of Gages or Precision Parts by Subzero Cooling.— Transformation of austenite into martensite is accompanied by an increase in volume; consequently, the transformation of austenite, that may occur naturally over a period of months or years, tends to change the dimensions and form of steel parts, and such changes may be serious in the case of precision gages, close-fitting machine parts, etc. To prevent such changes, the subzero treatment has proved effective. Gage-blocks, for example, may be stabilized by hardening followed by repeated cycles of chilling and tempering, to transform a large percentage of the austenite into martensite.

Order of Operations for Stabilizing Precision Gages: If precision gages and sine-bars, are heat-treated in the ordinary manner and then are finished without some stabilizing treatment, dimensional changes and warpage are liable to occur. Sub-zero cooling provides a practical and fairly rapid method of obtaining the necessary stabilization by transforming the austenite into martensite. In stabilization treatments of this kind, tempering is the final operation. One series of treatments that has been recommended after hardening and rough-grinding is as follows:

a) Cool to −120 degrees F. (This cooling period may require from one to six hours, depending on the size and form of the gage.)

b) Place gage in boiling water for two hours (oil or salt bath may also be used).

Note: Steps (a) and (b) may be repeated from two to six times, depending on the size and form of the gage. These repeated cycles will eventually transform practically all the austenite into martensite. Two or three cooling and drawing operations usually are sufficient for such work as thread gages and gage-blocks.

c) Follow with regular tempering or drawing operation and finish gage by lapping.

Series of Stabilizing Treatments for Chromium Steel: The following series of treatments has proved successful in stabilizing precision gage-blocks made from SAE 52100 chromium steel.

a) Preheat to 600 degrees F and then heat to 1575 degrees F for a period of four minutes.

b) Quench in oil at 85 degrees F. (Uniform quenching is essential.)

c) Temper at 275 degrees F for one hour.

d) Cool in tempering furnace to room temperature.

e) Continue cooling in atmosphere of industrial refrigerator for six hours with temperature of atmosphere at −120 degrees F.

f) Allow gage-blocks to return to room temperature and again temper.

Note: The complete treatment consists of six subzero cooling periods, each followed by a tempering operation. The transformation to martensite is believed to be complete even after the fifth cooling period. The hardness is about 66 Rockwell C. Transformation is checked by magnetic tests based upon the magnetism of martensite and the nonmagnetic qualities of austenite.

Stabilizing Dimensions of Close-Fitting Machine Parts.— Subzero treatment will always cause an increase in size. Machine parts subjected to repeated and perhaps drastic changes in temperature, as in aircraft, may eventually cause trouble due to growth or warpage as the austenite gradually changes to martensite. In some instances, the sizes of close-fitting moving parts have increased sufficiently to cause seizure. Such treatment, for example, may be applied to precision bearings made from SAE 52100 or alloy carburizing steels for stabilizing or aging them. *Time* aging of 52100 steels after hardening has been found to cause changes as large as 0.0025 inch in medium size sections. A practical remedy is to apply the subzero treatment before the final grinding or other machining operation.

Copyright 2004, Industrial Press, Inc., New York, NY

Subzero Treatment of Carburized Parts to Improve Physical Properties.— The subzero treatment has been applied to carburized machine parts. For example, the amount of retained austenite in carburized gears may be sufficient to reduce the life of the gears. In one component, the Rockwell hardness was increased from 55 C to 65 C without loss of impact resistance qualities; in fact, impact and fatigue resistance may be increased in some examples.

Application of Subzero Treatments to High-Speed Steel.— The subzero treatment has been applied to such tools as milling cutters, hobs, taps, broaches, and drills. It is applicable to different classes of high-speed steels, such as the 18–4–1 tungsten, 18–4–14 cobalt, and the molybdenum high-speed steels. This *cold* treatment is applied preferably in conjunction with the heat treatment, both being combined in a continuous cycle of operations. The general procedure is either to harden the steel, cool it to a subzero temperature, and then temper; or, especially if there is more than one tempering operation, the first one may *precede* subzero cooling. The cooling and tempering cycle may be repeated two or more times. The number and order of the operations, or the complete cycle, may be varied to suit the class of work and, to minimize the danger of cracking, particularly if the tool has large or irregular sections, sharp corners or edges, or a high cobalt content. A subzero treatment of some kind with a final tempering operation for stress relief, is intended to increase strength and toughness without much loss in hardness; consequently, if there is greater strength at a given hardness, tools subjected to subzero treatment can operate with a higher degree of hardness than those heat treated in the ordinary manner, or, if greater toughness is preferred, it can be obtained by tempering to the original degree of hardness.

Order of Cooling and Tempering Periods for High-speed Steel.— The order or cycle for the cooling and tempering periods has not been standardized. The methods that follow have been applied to high-speed steel tools. They are given as examples of procedure and are subject to possible changes due to subsequent developments. The usual ranges of preheating and hardening temperatures are given; but for a particular steel, the recommended temperatures should be obtained from the manufacturer.

1) *Double Subzero Treatment:* (For rugged simple tool forms without irregular sections, sharp corners or edges where cracks might develop during the subzero treatment).

a) Preheat between 1400 and 1600 degrees F (double preheating is preferable, the first preheating ranging from 700 to 1000 degrees F).

b) Heat to the hardening temperature. (*Note:* Tests indicate that the effect of subzero treatment on high-speed steel may be influenced decidedly by the hardening temperature. If this temperature is near the lower part of the range, the results are unsatisfactory. Effective temperatures for ordinary high-speed steels appear to range from 2300 to 2350 degrees F).

c) Quench in oil, salt, lead, or air, down to a workpiece temperature of 150–200 degrees F. (*Note:* One method is to quench in oil; a second method is to quench in oil to about 200–225 degrees F and then air cool; a third method is to quench in salt bath at 1050–1100 degrees F and then air cool.)

d) Cool in refrigerating unit to temperature of –100 to –120 degrees F *right after quenching*. (*Note:* Tests have shown that a delay of one hour has a detrimental effect, and in ten hours the efficiency of the subzero treatment is reduced 50 per cent. This is because the austenite becomes more and more stabilized when the subzero treatment is delayed; consequently, the austenite is more difficult to transform into martensite.) The refrigerating period usually varies from two to six hours, depending on the size of the tool. Remove the tool from the refrigerating unit and allow it to return to room temperature.

e) Temper to required hardness for a period of two and one-half to three hours. The tempering temperature usually varies from a minimum of 1000 to 1100 degrees F for ordinary high-speed steels. Tests indicate that if this first tempering is less than two and one-half hours at 1050 degrees F, there will not be sufficient precipitation of car-

Copyright 2004, Industrial Press, Inc., New York, NY

bides at the tempering temperature to allow complete transformation of the retained austenite on cooling, whereas more than three hours causes some loss in room temperature hardness, hot hardness, strength, and toughness.

f) Repeat subzero treatment, step (d).

g) Repeat the tempering operation, step (e). (*Note:* The time for the second tempering operation is sometimes reduced to about one-half the time required for the first tempering.)

2) *Single Subzero Treatment:* This treatment is the same as procedure (1) except that a second subzero cooling is omitted; hence, the cycle consists of hardening, subzero cooling, and double tempering. Procedure (3), which follows, also has one subzero cooling period in the cycle, but this *follows* the first tempering operation.

3) *Tempering Followed by Subzero Treatment:* This treatment is for tools having irregular sections, sharp corners, or edges where cracks might develop if the hardening operation were followed immediately by subzero cooling.

a) Preheat and heat for hardening.

b) Preheat and heat for hardening.

c) Quench as described under procedure (1).

d) Temper to required hardness.

e) Cool to subzero temperature −100 to −120 degrees F and then allow the tool to return to room temperature.

f) Repeat tempering operation.

Testing the Hardness of Metals

Brinell Hardness Test.— The Brinell test for determining the hardness of metallic materials consists in applying a known load to the surface of the material to be tested through a hardened steel ball of known diameter. The diameter of the resulting permanent impression in the metal is measured and the Brinell Hardness Number (BHN) is then calculated from the following formula in which D = diameter of ball in millimeters, d = measured diameter at the rim of the impression in millimeters, and P = applied load in kilograms.

$$\text{BHN} = \frac{\text{load on indenting tool in kilograms}}{\text{surface area of indentation in sq. mm.}} = \frac{P}{\frac{\pi D}{2}(D - \sqrt{D^2 - d^2})}$$

If the steel ball were not deformed under the applied load and if the impression were truly spherical, then the preceding formula would be a general one, and any combination of applied load and size of ball could be used. The impression, however, is not quite a spherical surface because there must always be some deformation of the steel ball and some recovery of form of the metal in the impression; hence, for a standard Brinell test, the size and characteristics of the ball and the magnitude of the applied load must be standardized. In the standard Brinell test, a ball 10 millimeters in diameter and a load of 3000, 1500, or 500 kilograms is used. It is desirable, although not mandatory, that the test load be of such magnitude that the diameter of the impression be in the range of 2.50 to 4.75 millimeters. The following test loads and approximate Brinell numbers for this range of impression diameters are: 3000 kg, 160 to 600 BHN; 1500 kg, 80 to 300 BHN; 500 kg, 26 to 100 BHN. In making a Brinell test, the load should be applied steadily and without a jerk for at least 15 seconds for iron and steel, and at least 30 seconds in testing other metals. A minimum period of 2 minutes, for example, has been recommended for magnesium and magnesium alloys. (For the softer metals, loads of 250, 125, or 100 kg are sometimes used.)

According to the American Society for Testing and Materials Standard E10-66, a steel ball may be used on material having a BHN not over 450, a Hultgren ball on material not over 500, or a carbide ball on material not over 630. The Brinell hardness test is not recommended for material having a BHN over 630.

Copyright 2004, Industrial Press, Inc., New York, NY

Rockwell Hardness Test.— The Rockwell hardness tester is essentially a machine that measures hardness by determining the depth of penetration of a penetrator into the specimen under certain fixed conditions of test. The penetrator may be either a steel ball or a diamond spheroconical penetrator. The hardness number is related to the depth of indentation and the number is higher the harder the material. A minor load of 10 kg is first applied, causing an initial penetration; the dial is set at zero on the black-figure scale, and the major load is applied. This major load is customarily 60 or 100 kg when a steel ball is used as a penetrator, but other loads may be used when necessary. The ball penetrator is $\frac{1}{16}$ inch in diameter normally, but other penetrators of larger diameter, such as $\frac{1}{8}$ inch, may be employed for soft metals. When a diamond spheroconical penetrator is employed, the load usually is 150 kg. Experience decides the best combination of load and penetrator for use. After the major load is applied and removed, according to standard procedure, the reading is taken while the minor load is still applied.

The Rockwell Hardness Scales.— The various Rockwell scales and their applications are shown in the following table. The type of penetrator and load used with each are shown in Tables 1 and 2, which give comparative hardness values for different hardness scales.

Scale	Testing Application
A	For tungsten carbide and other extremely hard materials. Also for thin, hard sheets.
B	For materials of medium hardness such as low- and medium-carbon steels in the annealed condition.
C	For materials harder than Rockwell B-100.
D	Where a somewhat lighter load is desired than on the C scale, as on case-hardened pieces.
E	For very soft materials such as bearing metals.
F	Same as the E scale but using a $\frac{1}{16}$-inch ball.
G	For metals harder than tested on the B scale.
H & K	For softer metals.
15–N; 30–N; 45–N	Where a shallow impression or a small area is desired. For hardened steel and hard alloys.
15–T; 30–T; 45-T	Where a shallow impression or a small area is desired for materials softer than hardened steel.

Shore's Scleroscope.— The scleroscope is an instrument that measures the hardness of the work in terms of elasticity. A diamond-tipped hammer is allowed to drop from a known height on the metal to be tested. As this hammer strikes the metal, it rebounds, and the harder the metal, the greater the rebound. The extreme height of the rebound is recorded, and an average of a number of readings taken on a single piece will give a good indication of the hardness of the work. The surface smoothness of the work affects the reading of the instrument. The readings are also affected by the contour and mass of the work and the depth of the case, in carburized work, the soft core of light-depth carburizing, pack-hardening, or cyanide hardening, absorbing the force of the hammer fall and decreasing the rebound. The hammer weighs about 40 grains, the height of the rebound of hardened steel is in the neighborhood of 100 on the scale, or about $6\frac{1}{4}$ inches, and the total fall is about 10 inches or 255 millimeters.

Vickers Hardness Test.— The Vickers test is similar in principle to the Brinell test. The standard Vickers penetrator is a square-based diamond pyramid having an included point angle of 136 degrees. The numerical value of the hardness number equals the applied load in kilograms divided by the area of the pyramidal impression: A smooth, firmly supported, flat surface is required. The load, which usually is applied for 30 seconds, may be 5, 10, 20, 30, 50, or 120 kilograms. The 50-kilogram load is the most usual. The hardness number is based upon the diagonal length of the square impression. The Vickers test is considered to

Copyright 2004, Industrial Press, Inc., New York, NY

be very accurate, and may be applied to thin sheets as well as to larger sections with proper load regulation.

Knoop Hardness Numbers.— The Knoop hardness test is applicable to extremely thin metal, plated surfaces, exceptionally hard and brittle materials, very shallow carburized or nitrided surfaces, or whenever the applied load must be kept below 3600 grams. The Knoop indentor is a diamond ground to an elongated pyramidal form and it produces an indentation having long and short diagonals with a ratio of approximately 7 to 1. The longitudinal angle of the indentor is 172 degrees, 30 minutes, and the transverse angle 130 degrees. The Tukon Tester in which the Knoop indentor is used is fully automatic under electronic control. The Knoop hardness number equals the load in kilograms divided by the projected area of indentation in square millimeters. The indentation number corresponding to the long diagonal and for a given load may be determined from a table computed for a theoretically perfect indentor. The load, which may be varied from 25 to 3600 grams, is applied for a definite period and always normal to the surface tested. Lapped plane surfaces free from scratches are required.

Monotron Hardness Indicator.— With this instrument, a diamond-ball impressor point $\frac{3}{4}$ mm in diameter is forced into the material to a depth of $\frac{9}{5000}$ inch and the pressure required to produce this constant impression indicates the hardness. One of two dials shows the pressure in kilograms and pounds, and the other shows the depth of the impression in millimeters and inches. Readings in Brinell numbers may be obtained by means of a scale designated as *M*–1.

Keep's Test.— With this apparatus, a standard steel drill is caused to make a definite number of revolutions while it is pressed with standard force against the specimen to be tested. The hardness is automatically recorded on a diagram on which a dead soft material gives a horizontal line, and a material as hard as the drill itself gives a vertical line, intermediate hardness being represented by the corresponding angle between 0 and 90 degrees.

Comparison of Hardness Scales.— Tables 1 and 2 show comparisons of various hardness scales. All such tables are based on the assumption that the metal tested is homogeneous to a depth several times that of the indentation. To the extent that the metal being tested is not homogeneous, errors are introduced because different loads and different shapes of penetrators meet the resistance of metal of varying hardness, depending on the depth of indentation. Another source of error is introduced in comparing the hardness of different materials as measured on different hardness scales. This error arises from the fact that in any hardness test, metal that is severely cold-worked actually supports the penetrator, and different metals, different alloys, and different analyses of the same type of alloy have different cold-working properties. In spite of the possible inaccuracies introduced by such factors, it is of considerable value to be able to compare hardness values in a general way.

The data shown in Table 1 are based on extensive tests on carbon and alloy steels mostly in the heat-treated condition, but have been found to be reliable on constructional alloy steels and tool steels in the as-forged, annealed, normalized, quenched, and tempered conditions, providing they are homogeneous. These hardness comparisons are not as accurate for special alloys such as high manganese steel, 18–8 stainless steel and other austenitic steels, nickel-base alloys, constructional alloy steels, and nickel-base alloys in the cold-worked condition.

The data shown in Table 2 are for hardness measurements of unhardened steel, steel of soft temper, grey and malleable cast iron, and most nonferrous metals. Again these hardness comparisons are not as accurate for annealed metals of high Rockwell B hardness such as austenitic stainless steel, nickel and high nickel alloys, and cold-worked metals of low B-scale hardness such as aluminum and the softer alloys.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Comparative Hardness Scales for Steel

Rockwell C-Scale Hardness Number	Diamond Pyramid Hardness Number Vickers	Brinell Hardness Number 10-mm Ball, 3000-kgf Load			Rockwell Hardness Number		Rockwell Superficial Hardness Number Superficial Diamond Indenter			Shore Scleroscope Hardness Number
		Standard Ball	Hultgren Ball	Tungsten Carbide Ball	A-Scale 60-kgf Load Diamond Indenter	D-Scale 100-kgf Load Diamond Indenter	15-N Scale 15-kgf Load	30-N Scale 30-kgf Load	45-N Scale 45-kgf Load	
68	**940**	…	…	…	**85.6**	**76.9**	**93.2**	**84.4**	**75.4**	97
67	**900**	…	…	…	**85.0**	**76.1**	**92.9**	**83.6**	**74.2**	95
66	**865**	…	…	…	**84.5**	**75.4**	**92.5**	**82.8**	**73.3**	92
65	**832**	…	…	(**739**)	**83.9**	**74.5**	**92.2**	**81.9**	**72.0**	91
64	**800**	…	…	(**722**)	**83.4**	**73.8**	**91.8**	**81.1**	**71.0**	88
63	**772**	…	…	(**705**)	**82.8**	**73.0**	**91.4**	**80.1**	**69.9**	87
62	**746**	…	…	(**688**)	**82.3**	**72.2**	**91.1**	**79.3**	**68.8**	85
61	**720**	…	…	(**670**)	**81.8**	**71.5**	**90.7**	**78.4**	**67.7**	83
60	**697**	…	(**613**)	(**654**)	**81.2**	**70.7**	**90.2**	**77.5**	**66.6**	81
59	**674**	…	(**599**)	(**634**)	**80.7**	**69.9**	**89.8**	**76.6**	**65.5**	80
58	**653**	…	(**587**)	**615**	**80.1**	**69.2**	**89.3**	**75.7**	**64.3**	78
57	**633**	…	(**575**)	**595**	**79.6**	**68.5**	**88.9**	**74.8**	**63.2**	76
56	**613**	…	(**561**)	**577**	**79.0**	**67.7**	**88.3**	**73.9**	**62.0**	75
55	**595**	…	(**546**)	**560**	**78.5**	**66.9**	**87.9**	**73.0**	**60.9**	74
54	**577**	…	(**534**)	**543**	**78.0**	**66.1**	**87.4**	**72.0**	**59.8**	72
53	**560**	…	(**519**)	**525**	**77.4**	**65.4**	**86.9**	**71.2**	**58.6**	71
52	**544**	(**500**)	(**508**)	**512**	**76.8**	**64.6**	**86.4**	**70.2**	**57.4**	69
51	**528**	(**487**)	(**494**)	**496**	**76.3**	**63.8**	**85.9**	**69.4**	**56.1**	68
50	**513**	(**475**)	(**481**)	**481**	**75.9**	**63.1**	**85.5**	**68.5**	**55.0**	67
49	**498**	(**464**)	(**469**)	**469**	**75.2**	**62.1**	**85.0**	**67.6**	**53.8**	66
48	**484**	(**451**)	(**455**)	**455**	**74.7**	**61.4**	**84.5**	**66.7**	**52.5**	64
47	**471**	**442**	**443**	**443**	**74.1**	**60.8**	**83.9**	**65.8**	**51.4**	63
46	**458**	**432**	**432**	**432**	**73.6**	**60.0**	**83.5**	**64.8**	**50.3**	62
45	**446**	**421**	**421**	**421**	**73.1**	**59.2**	**83.0**	**64.0**	**49.0**	60
44	**434**	**409**	**409**	**409**	**72.5**	**58.5**	**82.5**	**63.1**	**47.8**	58
43	**423**	**400**	**400**	**400**	**72.0**	**57.7**	**82.0**	**62.2**	**46.7**	57
42	**412**	**390**	**390**	**390**	**71.5**	**56.9**	**81.5**	**61.3**	**45.5**	56
41	**402**	**381**	**381**	**381**	**70.9**	**56.2**	**80.9**	**60.4**	**44.3**	55
40	**392**	**371**	**371**	**371**	**70.4**	**55.4**	**80.4**	**59.5**	**43.1**	54
39	**382**	**362**	**362**	**362**	**69.9**	**54.6**	**79.9**	**58.6**	**41.9**	52
38	**372**	**353**	**353**	**353**	**69.4**	**53.8**	**79.4**	**57.7**	**40.8**	51
37	**363**	**344**	**344**	**344**	**68.9**	**53.1**	**78.8**	**56.8**	**39.6**	50
36	**354**	**336**	**336**	**336**	**68.4**	**52.3**	**78.3**	**55.9**	**38.4**	49
35	**345**	**327**	**327**	**327**	**67.9**	**51.5**	**77.7**	**55.0**	**37.2**	48
34	**336**	**319**	**319**	**319**	**67.4**	**50.8**	**77.2**	**54.2**	**36.1**	47
33	**327**	**311**	**311**	**311**	**66.8**	**50.0**	**76.6**	**53.3**	**34.9**	46
32	**318**	**301**	**301**	**301**	**66.3**	**49.2**	**76.1**	**52.1**	**33.7**	44
31	**310**	**294**	**294**	**294**	**65.8**	**48.4**	**75.6**	**51.3**	**32.5**	43
30	**302**	**286**	**286**	**286**	**65.3**	**47.7**	**75.0**	**50.4**	**31.3**	42
29	**294**	**279**	**279**	**279**	**64.7**	**47.0**	**74.5**	**49.5**	**30.1**	41
28	**286**	**271**	**271**	**271**	**64.3**	**46.1**	**73.9**	**48.6**	**28.9**	41
27	**279**	**264**	**264**	**264**	**63.8**	**45.2**	**73.3**	**47.7**	**27.8**	40
26	**272**	**258**	**258**	**258**	**63.3**	**44.6**	**72.8**	**46.8**	**26.7**	38
25	**266**	**253**	**253**	**253**	**62.8**	**43.8**	**72.2**	**45.9**	**25.5**	38
24	**260**	**247**	**247**	**247**	**62.4**	**43.1**	**71.6**	**45.0**	**24.3**	37
23	**254**	**243**	**243**	**243**	**62.0**	**42.1**	**71.0**	**44.0**	**23.1**	36
22	**248**	**237**	**237**	**237**	**61.5**	**41.6**	**70.5**	**43.2**	**22.0**	35

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Comparative Hardness Scales for Steel**

Rockwell C-Scale Hardness Number	Diamond Pyramid Hardness Number Vickers	Brinell Hardness Number 10-mm Ball, 3000-kgf Load			Rockwell Hardness Number		Rockwell Superficial Hardness Number Superficial Diamond Indenter			Shore Scleroscope Hardness Number
		Standard Ball	Hultgren Ball	Tungsten Carbide Ball	A-Scale 60-kgf Load Diamond Indenter	D-Scale 100-kgf Load Diamond Indenter	15-N Scale 15-kgf Load	30-N Scale 30-kgf Load	45-N Scale 45-kgf Load	
21	**243**	**231**	**231**	**231**	**61.0**	**40.9**	**69.9**	**42.3**	**20.7**	35
20	**238**	**226**	**226**	**226**	**60.5**	**40.1**	**69.4**	**41.5**	**19.6**	34
(18)	230	219	219	219	…	…	…	…	…	33
(16)	222	212	212	212	…	…	…	…	…	32
(14)	213	203	203	203	…	…	…	…	…	31
(12)	204	194	194	194	…	…	…	…	…	29
(10)	196	187	187	187	…	…	…	…	…	28
(8)	188	179	179	179	…	…	…	…	…	27
(6)	180	171	171	171	…	…	…	…	…	26
(4)	173	165	165	165	…	…	…	…	…	25
(2)	166	158	158	158	…	…	…	…	…	24
(0)	160	152	152	152	…	…	…	…	…	24

Note: The values in this table shown in **boldface** type correspond to those shown in American Society for Testing and Materials Specification E140-67.

Values in ( ) are beyond the normal range and are given for information only.

Turner's Sclerometer.— In making this test a weighted diamond point is drawn, once forward and once backward, over the smooth surface of the material to be tested. The hardness number is the weight in grams required to produce a standard scratch.

Mohs's Hardness Scale.— Hardness, in general, is determined by what is known as Mohs's scale, a standard for hardness that is applied mainly to nonmetallic elements and minerals. In this hardness scale, there are ten degrees or steps, each designated by a mineral, the difference in hardness of the different steps being determined by the fact that any member in the series will scratch any of the preceding members. This scale is as follows:

1) talc; 2) gypsum; 3) calcite; 4) fluor spar; 5) apatite; 6) orthoclase; 7) quartz; 8) topaz; 9) sapphire or corundum; and 10) diamond.

These minerals, arbitrarily selected as standards, are successively harder, from talc, the softest of all minerals, to diamond, the hardest. This scale, which is now universally used for nonmetallic minerals, is not applied to metals.

Relation Between Hardness and Tensile Strength.— The approximate relationship between the hardness and tensile strength is shown by the following formula:

Tensile strength = $Bhn \times 515$ (for Brinell numbers up to 175).

Tensile strength = $Bhn \times 490$ (for Brinell numbers larger than 175).

The above formulas give the tensile strength in pounds per square inch for steels. These approximate relationships between hardness and tensile strength do not apply to nonferrous metals with the possible exception of certain aluminum alloys.

Durometer Tests.— The durometer is a portable hardness tester for measuring hardness of rubber, plastics, and some soft metals. The instrument is designed to apply pressure to the specimen and the hardness is read from a scale while the pressure is maintained. Various scales can be used by changing the indentor and the load applied.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Comparative Hardness Scales for Unhardened Steel, Soft-Temper Steel, Grey and Malleable Cast Iron, and Nonferrous Alloys

Rockwell Hardness Number			Rockwell Superficial Hardness Number			Rockwell Hardness Number				Brinell Hardness Number	
1/16″ Ball Indenter			1/16″ Ball Indenter			1/8″ Ball Indenter			"Brale" Indenter	10-mm Standard Ball	
B scale 100-kg Load	F scale 60-kg Load	G scale 150-kg Load	15-T scale 15-kg Load	30-T scale 30-kg Load	45-T scale 45-kg Load	E scale 100-kg Load	H scale 100-kg Load	K scale 150-kg Load	A scale 60-kg Load	500-kg Load	3000-kg Load
100	…	82.5	93.0	82.0	72.0	…	…	…	61.5	201	240
99	…	81.0	92.5	81.5	71.0	…	…	…	61.0	195	234
98	…	79.0	…	81.0	70.0	…	…	…	60.0	189	228
97	…	77.5	92.0	80.5	69.0	…	…	…	59.5	184	222
96	…	76.0	…	80.0	68.0	…	…	…	59.0	179	216
95	…	74.0	91.5	79.0	67.0	…	…	…	58.0	175	210
94	…	72.5	…	78.5	66.0	…	…	…	57.5	171	205
93	…	71.0	91.0	78.0	65.5	…	…	…	57.0	167	200
92	…	69.0	90.5	77.5	64.5	…	…	100	56.5	163	195
91	…	67.5	…	77.0	63.5	…	…	99.5	56.0	160	190
90	…	66.0	90.0	76.0	62.5	…	…	98.5	55.5	157	185
89	…	64.0	89.5	75.5	61.5	…	…	98.0	55.0	154	180
88	…	62.5	…	75.0	60.5	…	…	97.0	54.0	151	176
87	…	61.0	89.0	74.5	59.5	…	…	96.5	53.5	148	172
86	…	59.0	88.5	74.0	58.5	…	…	95.5	53.0	145	169
85	…	57.5	…	73.5	58.0	…	…	94.5	52.5	142	165
84	…	56.0	88.0	73.0	57.0	…	…	94.0	52.0	140	162
83	…	54.0	87.5	72.0	56.0	…	…	93.0	51.0	137	159
82	…	52.5	…	71.5	55.0	…	…	92.0	50.5	135	156
81	…	51.0	87.0	71.0	54.0	…	…	91.0	50.0	133	153
80	…	49.0	86.5	70.0	53.0	…	…	90.5	49.5	130	150
79	…	47.5	…	69.5	52.0	…	…	89.5	49.0	128	147
78	…	46.0	86.0	69.0	51.0	…	…	88.5	48.5	126	144
77	…	44.0	85.5	68.0	50.0	…	…	88.0	48.0	124	141
76	…	42.5	…	67.5	49.0	…	…	87.0	47.0	122	139
75	99.5	41.0	85.0	67.0	48.5	…	…	86.0	46.5	120	137
74	99.0	39.0	…	66.0	47.5	…	…	85.0	46.0	118	135
73	98.5	37.5	84.5	65.5	46.5	…	…	84.5	45.5	116	132
72	98.0	36.0	84.0	65.0	45.5	…	…	83.5	45.0	114	130
71	97.5	34.5	…	64.0	44.5	100	…	82.5	44.5	112	127
70	97.0	32.5	83.5	63.5	43.5	99.5	…	81.5	44.0	110	125
69	96.0	31.0	83.0	62.5	42.5	99.0	…	81.0	43.5	109	123
68	95.5	29.5	…	62.0	41.5	98.0	…	80.0	43.0	107	121
67	95.0	28.0	82.5	61.5	40.5	97.5	…	79.0	42.5	106	119
66	94.5	26.5	82.0	60.5	39.5	97.0	…	78.0	42.0	104	117
65	94.0	25.0	…	60.0	38.5	96.0	…	77.5	…	102	116
64	93.5	23.5	81.5	59.5	37.5	95.5	…	76.5	41.5	101	114
63	93.0	22.0	81.0	58.5	36.5	95.0	…	75.5	41.0	99	112
62	92.0	20.5	…	58.0	35.5	94.5	…	74.5	40.5	98	110
61	91.5	19.0	80.5	57.0	34.5	93.5	…	74.0	40.0	96	108
60	91.0	17.5	…	56.5	33.5	93.0	…	73.0	39.5	95	107
59	90.5	16.0	80.0	56.0	32.0	92.5	…	72.0	39.0	94	106
58	90.0	14.5	79.5	55.0	31.0	92.0	…	71.0	38.5	92	…
57	89.5	13.0	…	54.5	30.0	91.0	…	70.5	38.0	91	…
56	89.0	11.5	79.0	54.0	29.0	90.5	…	69.5	…	90	…
55	88.0	10.0	78.5	53.0	28.0	90.0	…	68.5	37.5	89	…
54	87.5	8.5	…	52.5	27.0	89.5	…	68.0	37.0	87	…
53	87.0	7.0	78.0	51.5	26.0	89.0	…	67.0	36.5	86	…
52	86.5	5.5	77.5	51.0	25.0	88.0	…	66.0	36.0	85	…
51	86.0	4.0	…	50.5	24.0	87.5	…	65.0	35.5	84	…
50	85.5	2.5	77.0	49.5	23.0	87.0	…	64.5	35.0	83	…
49	85.0	1.0	76.5	49.0	22.0	86.5	…	63.5	…	82	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Comparative Hardness Scales for Unhardened Steel, Soft-Temper Steel, Grey and Malleable Cast Iron, and Nonferrous Alloys**

Rockwell Hardness Number			Rockwell Superficial Hardness Number			Rockwell Hardness Number				Brinell Hardness Number	
1/16" Ball Indenter			1/16" Ball Indenter			1/8" Ball Indenter			"Brale" Indenter	10-mm Standard Ball	
B scale 100-kg Load	F scale 60-kg Load	G scale 150-kg Load	15-T scale 15-kg Load	30-T scale 30-kg Load	45-T scale 45-kg Load	E scale 100-kg Load	H scale 100-kg Load	K scale 150-kg Load	A scale 60-kg Load	500-kg Load	3000-kg Load
48	84.5	…	…	48.5	20.5	85.5	…	62.5	34.5	81	…
47	84.0	…	76.0	47.5	19.5	85.0	…	61.5	34.0	80	…
46	83.0	…	75.5	47.0	18.5	84.5	…	61.0	33.5	…	…
45	82.5	…	…	46.0	17.5	84.0	…	60.0	33.0	79	…
44	82.0	…	75.0	45.5	16.5	83.5	…	59.0	32.5	78	…
43	81.5	…	74.5	45.0	15.5	82.5	…	58.0	32.0	77	…
42	81.0	…	…	44.0	14.5	82.0	…	57.5	31.5	76	…
41	80.5	…	74.0	43.5	13.5	81.5	…	56.5	31.0	75	…
40	79.5	…	73.5	43.0	12.5	81.0	…	55.5	…	…	…
39	79.0	…	…	42.0	11.0	80.0	…	54.5	30.5	74	…
38	78.5	…	73.0	41.5	10.0	79.5	…	54.0	30.0	73	…
37	78.0	…	72.5	40.5	9.0	79.0	…	53.0	29.5	72	…
36	77.5	…	…	40.0	8.0	78.5	100	52.0	29.0	…	…
35	77.0	…	72.0	39.5	7.0	78.0	99.5	51.5	28.5	71	…
34	76.5	…	71.5	38.5	6.0	77.0	99.0	50.5	28.0	70	…
33	75.5	…	…	38.0	5.0	76.5	…	49.5	…	69	…
32	75.0	…	71.0	37.5	4.0	76.0	98.5	48.5	27.5	…	…
31	74.5	…	…	36.5	3.0	75.5	98.0	48.0	27.0	68	…
30	74.0	…	70.5	36.0	2.0	75.0	…	47.0	26.5	67	…
29	73.5	…	70.0	35.5	1.0	74.0	97.5	46.0	26.0	…	…
28	73.0	…	…	34.5	…	73.5	97.0	45.0	25.5	66	…
27	72.5	…	69.5	34.0	…	73.0	96.5	44.5	25.0	…	…
26	72.0	…	69.0	33.0	…	72.5	…	43.5	24.5	65	…
25	71.0	…	…	32.5	…	72.0	96.0	42.5	…	64	…
24	70.5	…	68.5	32.0	…	71.0	95.5	41.5	24.0	…	…
23	70.0	…	68.0	31.0	…	70.5	…	41.0	23.5	63	…
22	69.5	…	…	30.5	…	70.0	95.0	40.0	23.0	…	…
21	69.0	…	67.5	29.5	…	69.5	94.5	39.0	22.5	62	…
20	68.5	…	…	29.0	…	68.5	…	38.0	22.0	…	…
19	68.0	…	67.0	28.5	…	68.0	94.0	37.5	21.5	61	…
18	67.0	…	66.5	27.5	…	67.5	93.5	36.5	…	…	…
17	66.5	…	…	27.0	…	67.0	93.0	35.5	21.0	60	…
16	66.0	…	66.0	26.0	…	66.5	…	35.0	20.5	…	…
15	65.5	…	65.5	25.5	…	65.5	92.5	34.0	20.0	59	…
14	65.0	…	…	25.0	…	65.0	92.0	33.0	…	…	…
13	64.5	…	65.0	24.0	…	64.5	…	32.0	…	58	…
12	64.0	…	64.5	23.5	…	64.0	91.5	31.5	…	…	…
11	63.5	…	…	23.0	…	63.5	91.0	30.5	…	…	…
10	63.0	…	64.0	22.0	…	62.5	90.5	29.5	…	57	…
9	62.0	…	…	21.5	…	62.0	…	29.0	…	…	…
8	61.5	…	63.5	20.5	…	61.5	90.0	28.0	…	…	…
7	61.0	…	63.0	20.0	…	61.0	89.5	27.0	…	56	…
6	60.5	…	…	19.5	…	60.5	…	26.0	…	…	…
5	60.0	…	62.5	18.5	…	60.0	89.0	25.5	…	55	…
4	59.5	…	62.0	18.0	…	59.0	88.5	24.5	…	…	…
3	59.0	…	…	17.0	…	58.5	88.0	23.5	…	…	…
2	58.0	…	61.5	16.5	…	58.0	…	23.0	…	54	…
1	57.5	…	61.0	16.0	…	57.5	87.5	22.0	…	…	…
0	57.0	…	…	15.0	…	57.0	87.0	21.0	…	53	…

Not applicable to annealed metals of high B-scale hardness such as austenitic stainless steels, nickel and high-nickel alloys nor to cold-worked metals of low B-scale hardness such as aluminum and the softer alloys. (Compiled by Wilson Mechanical Instrument Co.)

Copyright 2004, Industrial Press, Inc., New York, NY

NONFERROUS ALLOYS

Strength Data for Nonferrous Metals

The ultimate tensile, shear, and yield strengths and moduli of elasticity of many nonferrous metals are given in Table 1. Values for the most part are given in ranges rather than as single values because of differences in composition, forms, sizes, and shapes for the aluminum alloys plus differences in heat treatments undergone for the other nonferrous metals. The values in the table are meant to serve as a guide, not as specifications. More specific data should be obtained from the supplier.

Table 1. Strength Data for Nonferrous Metals

Material	Ultimate Strength, kpsi		Yield Strength, kpsi (0.2% offset)	Modulus of Elasticity, 10^6 psi	
	in Tension	in Shear		in Tension, E	in Shear, G
Aluminum alloys, cast,					
sand-cast	19 to 35	14 to 26	8 to 25	10.3	…
heat-treated	20 to 48	20 to 34	16 to 40	10.3	…
permanent-mold-cast,	23 to 35	16 to 27	9 to 24	10.3	…
heat-treated	23 to 48	15 to 36	8.5 to 43	10.3	…
die-cast	30 to 46	19 to 29	16 to 27	10.3	…
Aluminum alloys, wrought,					
annealed	10 to 42	7 to 26	4 to 22	10.0 to 10.6	…
cold-worked	12 to 63	8 to 34	11 to 59	10.0 to 10.3	…
heat-treated	22 to 83	14 to 48	13 to 73	10.0 to 11.4	…
Aluminum bronze, cast,	62 to 90	…	25 to 37	15 to 18	…
heat-treated	80 to 110	…	32 to 65	15 to 18	…
Aluminum bronze, wrought,					
annealed	55 to 80	…	20 to 40	16 to 19	…
cold-worked	71 to 110	…	62 to 66	16 to 19	…
heat-treated	101 to 151	…	48 to 94	16 to 19	…
Brasses, leaded, cast	32 to 40	29 to 31	12 to 15	12 to 14	…
flat products, wrought	46 to 85	31 to 45	14 to 62	14 to 17	5.3 to 6.4
wire, wrought	50 to 88	34 to 46	…	15	5.6
Brasses, nonleaded,					
flat products, wrought	34 to 99	28 to 48	10 to 65	15 to 17	5.6 to 6.4
wire, wrought	40 to 130	29 to 60	…	15 to 17	5.6 to 6.4
Copper, wrought,					
flat products	32 to 57	22 to 29	10 to 53	17	6.4
wire	35 to 66	24 to 33	…	17	6.4
Inconel, cast	70 to 95	…	30 to 45	23	…
flat products, wrought	80 to 170	…	30 to 160	31	11
wire, wrought	80 to 185	…	25 to 175	31	11
Lead	2.2 to 4.9	…	…	0.8 to 2.0	…
Magnesium, cast,					
sand & permanent mold	22 to 40	17 to 22	12 to 23	6.5	2.4
die-cast	33	20	22	6.5	2.4
Magnesium, wrought					
sheet and plate	35 to 42	21 to 23	20 to 32	6.5	2.4
bars, rods, and shapes	37 to 55	19 to 27	26 to 44	6.5	2.4
Monel, cast	65 to 90	…	32 to 40	19	…
flat products, wrought	70 to 140	…	25 to 130	26	9.5
wire, wrought	70 to 170	…	25 to 160	26	9.5
Nickel, cast,	45 to 60	…	20 to 30	21.5	…
flat products, wrought	55 to 130	…	15 to 115	30	11
wire, wrought	50 to 165	…	10 to 155	30	11
Nickel silver, cast	40 to 50	…	24 to 25	…	…
flat products, wrought	49 to 115	41 to 59	18 to 90	17.5 to 18	6.6 to 6.8
wire, wrought	50 to 145	…	25 to 90	17.5 to 18	6.6 to 6.8
Phosphor bronze, wrought					
flat products	40 to 128	…	14 to 80	15 to 17	5.6 to 6.4
wire	50 to 147	…	20 to 80	16 to 17	6 to 6.4
Silicon bronze, wrought,					
flat products	56 to 110	42 to 63	21 to 62	15	5.6
wire	50 to 145	36 to 70	25 to 70	15 to 17	5.6 to 6.4
Tin bronze, leaded, cast	21 to 38	23 to 43	15 to 18	10 to 14.5	…
Titanium	50 to 135	…	40 to 120	15.0 to 16.5	…
Zinc, commercial rolled	19.5 to 31	…	…	…	…
Zirconium	22 to 83	…	…	9 to 14.5	4.8

Consult the index for data on metals not listed and for more data on metals listed.

Copyright 2004, Industrial Press, Inc., New York, NY

Copper and Copper Alloys

Pure copper is a reddish, highly malleable metal, and was one of the first to be found and utilized. Copper and its alloys are widely used because of their excellent electrical and thermal conductivities, outstanding resistance to corrosion, ease of fabrication, and broad ranges of obtainable strengths and special properties. Almost 400 commercial copper and copper-alloy compositions are available from mills as wrought products (rod, plate, sheet, strip, tube, pipe, extrusions, foil, forgings, and wire) and from foundries as castings.

Copper alloys are grouped into several general categories according to composition:

coppers and high-copper alloys
brasses
bronzes
copper nickels
copper–nickel–zinc alloys (nickel silvers)
leaded coppers
special alloys

The designation system originally developed by the U.S. copper and brass industry for identifying copper alloys used a three-digit number preceded by the letters CA. These designations have now been made part of the Unified Numbering System (UNS) simply by expanding the numbers to five digits preceded by the letter C. Because the old numbers are embedded in the new UNS numbers, no confusion results. UNS C10000 to C79999 are assigned to wrought compositions, and UNS C80000 to C99999 are assigned to castings. The designation system is not a specification, but a method for identifying the composition of mill and foundry products. The precise technical and quality assurance requirements to be satisfied are defined in relevant standard specifications issued by the federal government, the military, and the ASTM.

Classification of Copper and Copper Alloys

Family	Principal Alloying Element	UNS Numbers[a]
Coppers, high-copper alloys		C1xxxx
Brasses	Zn	C2xxxx, C3xxxx, C4xxxx, C66400 to C69800
Phosphor bronzes	Sn	C5xxxx
Aluminum bronzes	Al	C60600 to C64200
Silicon bronzes	Si	C64700 to C66100
Copper nickels, nickel silvers	Ni	C7xxxx

[a] Wrought alloys.

Cast Copper Alloys.— Generally, casting permits greater latitude in the use of alloying elements than in the fabrication of wrought products, which requires either hot or cold working. The cast compositions of coppers and high-copper alloys have a designated minimum copper content and may include other elements to impart special properties. The cast brasses comprise copper–zinc–tin alloys (red, semired, and yellow brasses); manganese bronze alloys (high-strength yellow brasses); leaded manganese bronze alloys (leaded high-strength yellow brasses); and copper–zinc–silicon alloys (silicon brasses and bronzes).

The cast bronze alloys have four main families: copper–tin alloys (tin bronzes); copper–tin–lead alloys (leaded and high leaded tin bronzes); copper–tin–nickel alloys (nickel–tin bronzes); and copper–aluminum alloys (aluminum bronzes).

The cast copper–nickel alloys contain nickel as the principal alloying element. The leaded coppers are cast alloys containing 20 per cent or more lead.

Table 2 lists the properties and applications of common cast copper alloys.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Properties and Applications of Cast Coppers and Copper Alloys

UNS Designation	Nominal Composition (%)	Typical Mechanical Properties, as Cast or Heat Treated[a]				Typical Applications
		Tensile Strength (ksi)	Yield Strength (ksi)	Elongation in 2 in. (%)	Machinability Rating[b]	
	Copper Alloys					
C80100	99.95 Cu + Ag min, 0.05 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation-resisant applications.
C80300	99.95 Cu + Ag min, 0.034 Ag min, 0.05 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation-resistant applications.
C80500	99.75 Cu + Ag min, 0.034 Ag min, 0.02 B max, 0.23 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation-resistant applications.
C80700	99.75 Cu + Ag min, 0.02 B max, 0.23 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation-resistant applications.
C80900	99.70 Cu + Ag min, 0.034 Ag min, 0.30 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation-resistant applications.
C81100	99.70 Cu + Ag min, 0.30 others max	25	9	40	10	Electrical and thermal conductors; corrosion and oxidation resstant applications.
	High-Copper Alloys					
C81300	98.5 Cu min, 0.06 Be, 0.80 Co, 0.40 others max	(53)	(36)	(11)	20	Higher hardness electrical and thermal conductors.
C81400	98.5 Cu min, 0.06 Be, 0.80 Cr, 0.40 others max	(53)	(36)	(11)	20	Higher hardness electrical and thermal conductors.
C81500	98.0 Cu min, 1.0 Cr, 0.50 others max	(51)	(40)	(17)	20	Electrical and/or thermal conductors used as structural members where strength and hardness greater than that of C80100–81100 are required.
C81700	94.2 Cu min, 1.0 Ag, 0.4 Be, 0.9 Co, 0.9 Ni	(92)	(68)	(8)	30	Electrical and/or thermal conductors used as structural members where strength and hardness greater than that of C80100–81100 are required. Also used in place of C81500 where electrical and/or thermal conductivities can be sacrificed for hardness and strength.
C81800	95.6 Cu min,1.0 Ag, 0.4 Be,1.6 Co	50 (102)	25 (75)	20 (8)	20	Resistance-welding electrodes, dies.
C82000	96.8 Cu, 0.6 Be, 2.6 Co	50 (100)	20 (75)	20 (8)	20	Current-carrying parts, contact and switch blades, bushings and bearings, and soldering iron and resistance-welding tips.
C82100	97.7 Cu, 0.5 Be, 0.9 Co, 0.9 Ni	(92)	(68)	(8)	30	Electrical and/or thermal conductors used as structural members where strength and hardness greater than that of C80100–81100 are required. Also used in place of C81500 where electrical and/or thermal conductivities can be sacrificed for hardness and strength.
C82200	96.5 Cu min, 0.6 Be, 1.5 Ni	57 (95)	30 (75)	20 (8)	20	Clutch rings, brake drums, seam-welder electrodes, projection welding dies, spot-welding tips, beam-welder shapes, bushings, water-cooled holders.
C82400	96.4 Cu min, 1.70 Be, 0.25 Co	72 (150)	37 (140)	20 (1)	20	Safety tools, molds for plastic parts, cams, bushings, bearings, valves, pump parts, gears.
C82500	97.2 Cu, 2.0 Be, 0.5 Co, 0.25 Si	80 (160)	45	20 (1)	20	Safety tools, molds for plastic parts, cams, bushings, bearings, valves, pump parts.
C82600	95.2 Cu min,2.3 Be, 0.5 Co, 0.25 Si	82 (165)	47 (155)	20 (1)	20	Bearings and molds for plastic parts.
C82700	96.3 Cu, 2.45 Be, 1.25 Ni	(155)	(130)	(0)	20	Bearings and molds for plastic parts.
C82800	96.6 Cu, 2.6 Be, 0.5 Co, 0.25 Si	97 (165)	55 (145)	20 (1)	10	Molds for plastic parts, cams, bushings, bearings, valves, pump parts, sleeves.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Properties and Applications of Cast Coppers and Copper Alloys**

UNS Designation	Nominal Composition (%)	Typical Mechanical Properties, as Cast or Heat Treated[a]				Typical Applications
		Tensile Strength (ksi)	Yield Strength (ksi)	Elongation in 2 in. (%)	Machinability Rating[b]	
	Red Brasses and Leaded Red Brasses					
C83300	93 Cu, 1.5 Sn,1.5 Pb, 4 Zn	32	10	35	35	Terminal ends for electrical cables.
C83400	90 Cu, 10 Zn	35	10	30	60	Moderate strength, moderate conductivity castings; rotating bands.
C83600	85 Cu, 5 Sn, 5 Pb, 5 Zn	37	17	30	84	Valves, flanges, pipe fittings, plumbing goods, pump castings, water pump impellers and housings, ornamental fixtures, small gears.
C83800	83 Cu, 4 Sn, 6 Pb,7 Zn	35	16	25	90	Low-pressure valves and fittings, plumbing supplies and fittings, general hardware, air–gas–water fittings, pump components, railroad catenary fittings.
	Semired Brasses and Leaded Semired Brasses					
C84200	80 Cu, 5 Sn,2.5 Pb, 12.5 Zn	35	14	27	80	Pipe fittings, elbows, T's, couplings, bushings, locknuts, plugs, unions.
C84400	81 Cu, 3 Sn, 7 Pb, 9 Zn	34	15	26	90	General hardware, ornamental castings, plumbing supplies and fixtures, low-pressure valves and fittings.
C84500	78 Cu, 3 Sn, 7 Pb, 12 Zn	35	14	28	90	Plumbing fixtures, cocks, faucets, stops, waste, air and gas fittings, low-pressure valve fittings.
C84800	76 Cu, 3 Sn, 6 Pb, 15 Zn	36	14	30	90	Plumbing fixtures, cocks, faucets, stops, waste, air, and gas, general hardware, and low-pressure valve fittings.
	Yellow Brasses and Leaded Yellow Brasses					
C85200	72 Cu, 1 Sn, 3 Pb, 24 Zn	38	13	35	80	Plumbing fittings and fixtures, ferrules, valves, hardware, ornamental brass, chandeliers, andirons.
C85400	67 Cu, 1 Sn, 3 Pb, 29 Zn	34	12	35	80	General-purpose yellow casting alloy not subject to high internal pressure. Furniture hardware, ornamental castings, radiator fittings, ship trimmings, battery clamps, valves, and fittings.
C85500	61 Cu, 0.8 Al, bal Zn	60	23	40	80	Ornamental castings.
C85700	63 Cu, 1 Sn, 1 Pb, 34.7 Zn, 0.3 Al	50	18	40	80	Bushings, hardware fittings, ornamental castings.
C85800	58 Cu, 1 Sn, 1 Pb, 40 Zn	55	30	15	80	General-purpose die-casting alloy having moderate strength.
	Manganese and Leaded Manganese Bronze Alloys					
C86100	67 Cu, 21 Zn, 3 Fe, 5 Al, 4 Mn	95	50	20	30	Marine castings, gears, gun mounts, bushings and bearings, marine racing propellers.
C86200	64 Cu, 26 Zn, 3 Fe, 4 Al, 3 Mn	95	48	20	30	Marine castings, gears, gun mounts, bushings and bearings.
C86300	63 Cu, 25 Zn, 3 Fe, 6 Al, 3 Mn	115	83	15	8	Extra-heavy duty, high-strength alloy. Large valve stems, gears, cams, slow-speed heavy-load bearings, screwdown nuts, hydraulic cylinder-parts.
C86400	59 Cu, 1 Pb, 40 Zn	65	25	20	65	Free-machining manganese bronze. Valve stems, marine fittings, lever arms, brackets, light-duty gears.
C86500	58 Cu, 0.5 Sn, 39.5 Zn, 1 Fe, 1 Al	71	28	30	26	Machinery parts requiring strength and toughness, lever arms, valve stems, gears.
C86700	58 Cu, 1 Pb, 41 Zn	85	42	20	55	High strength, free-machining manganese bronze. Valve stems.
C86800	55 Cu, 37 Zn, 3 Ni, 2 Fe, 3 Mn	82	38	22	30	Marine fittings, marine propellers.
	Silicon Bronzes and Silicon Brasses					
C87200	89 Cu min, 4 Si	55	25	30	40	Bearings, bells, impellers, pump and valve components, marine fittings, corrosion-resistant castings.
C87400	83 Cu, 14 Zn, 3 Si	55	24	30	50	Bearings, gears, impellers, rocker arms, valve stems, clamps.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Properties and Applications of Cast Coppers and Copper Alloys**

UNS Designation	Nominal Composition (%)	Typical Mechanical Properties, as Cast or Heat Treated[a]				Typical Applications
		Tensile Strength (ksi)	Yield Strength (ksi)	Elongation in 2 in. (%)	Machinability Rating[b]	
C87500	82 Cu, 14 Zn, 4 Si	67	30	21	50	Bearings, gears, impellers, rocker arms, valve stems, small boat proellers.
C87600	90 Cu, 5.5 Zn,4.5 Si	66	32	20	40	Valve stems.
C87800	82 Cu, 14 Zn, 4 Si	85	50	25	40	High-strength, thin-wall die castings; brush holders, lever arms, brackets, clamps, hexagonal nuts.
C87900	65 Cu, 34 Zn, 1 Si	70	35	25	80	General-purpose die-casting alloy having moderate strength.
	Tin Bronzes					
C90200	93 Cu, 7 Sn	38	16	30	20	Bearings and bushings.
C90300	88 Cu, 8 Sn, 4 Zn	45	21	30	30	Bearings, bushings, pump impellers, piston rings, valve components, seal rings, steam fittings, gears.
C90500	88 Cu, 10 Sn, 2 Zn	45	22	25	30	Bearings, bushings, pump impellers, piston rings, valve components, steam fittings, gears.
C90700	89 Cu, 11 Sn	44 (55)	22 (30	20 (16)	20	Gears, bearings, bushings.
C90900	87 Cu, 13 Sn	40	20	15	20	Bearings and bushings.
C91000	85 Cu, 14 Sn, 1 Zn	32	25	2	20	Piston rings and bearings.
C91100	84 Cu, 16 Sn	35	25	2	10	Piston rings, bearings, bushings, bridge plates.
C91300	81 Cu, 19 Sn	35	30	0.5	10	Piston rings, bearings, bushings, bridge plates, bells.
C91600	88 Cu, 10.5 Sn,1.5 Ni	44 (60)	22 (32)	16 (16)	20	Gears.
C91700	86.5 Cu, 12 Sn,1.5 Ni	44 (60)	22 (32)	16 (16)	20	Gears.
	Leaded Tin Bronzes					
C92200	88 Cu, 6 Sn,1.5 Pb, 4.5 Zn	40	20	30	42	Valves, fittings, and pressure-containing parts for use up to 550°F.
C92300	87 Cu, 8 Sn, 4 Zn	40	20	25	42	Valves, pipe fittings, and high-pressure steam castings. Superior machinability to C90300.
C92500	87 Cu, 11 Sn,1 Pb, 1 Ni	44	20	20	30	Gears, automotive synchronizer rings.
C92600	87 Cu, 10 Sn,1 Pb, 2 Zn	44	20	30	40	Bearings, bushings, pump impellers, piston rings, valve components, steam fittings, and gears. Superior machinability to C90500.
C92700	88 Cu, 10 Sn,2 Pb	42	21	20	45	Bearings, bushings, pump impellers, piston rings, and gears. Superior machinability to C90500.
C92800	79 Cu, 16 Sn, 5 Pb	40	30	1	70	Piston rings.
C92900	82 Cu min, 9 Sn min, 2 Pb min,2.8 Ni min	47 (47)	26 (26)	20 (20)	40	Gears, wear plates, guides, cams, parts requiring machinability superior to that of C91600 or 91700.
	High-Leaded Tin Bronzes					
C93200	83 Cu, 6.3 Sn min, 7 Pb, 3 Zn	35	18	20	70	General-utility bearings and bushings.
C93400	84 Cu, 8 Sn, 8 Pb	32	16	20	70	Bearings and bushings.
C93500	85 Cu, 5 Sn, 9 Pb	32	16	20	70	Small bearings and bushings, bronze backing for babbit-lined automotive bearings.
C93700	80 Cu, 10 Sn,10 Pb	35	18	20	80	Bearings for high speed and heavy pressures, pumps, impellers, corrosion-resistant applications, pressure tight castings.
C93800	78 Cu, 7 Sn, 15 Pb	30	16	18	80	Bearings for general service and moderate pressure, pump impellers, and bodies for use in acid mine water.
C93900	79 Cu, 6 Sn, 15 Pb	32	22	7	80	Continuous castings only. Bearings for general service, pump bodies, and impellers for mine waters.
C94300	70 Cu, 5 Sn, 25 Pb	27	13	15	80	High-speed bearings for light loads.
C94400	81 Cu, 8 Sn, 11 Pb, 0.35 P	32	16	18	80	General-utility alloy for bushings and bearings.
C94500	73 Cu, 7 Sn, 20 Pb	25	12	12	80	Locomotive wearing parts; high-low, low-speed bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Properties and Applications of Cast Coppers and Copper Alloys**

UNS Designation	Nominal Composition (%)	Typical Mechanical Properties, as Cast or Heat Treated[a]				Typical Applications
		Tensile Strength (ksi)	Yield Strength (ksi)	Elongation in 2 in. (%)	Machinability Rating[b]	
			Nickel–Tin Bronzes			
C94700	88 Cu, 5 Sn, 2 Zn, 5 Ni	50 (85)	23 (60)	35 (10)	30 (20)	Valve stems and bodies, bearings, wear guides, shift forks, feeding mechanisms, circuit breaker parts, gears, piston cylinders, nozzles.
C94800	87 Cu, 5 Sn, 5 Ni	45 (60)	23 (30)	35 (8)	50 (40)	Structural castings, gear components, motion-translation devices, machinery parts, bearings.
			Aluminum Bronzes			
C95200	88 Cu, 3 Fe, 9 Al	80	27	35	50	Acid-resisting pumps, bearing, gears, valve seats, guides, plungers, pump rods, bushings.
C95300	89 Cu, 1 Fe, 10 Al	75 (85)	27 (42)	25 (15)	55	Pickling baskets, nuts, gears, steel mill slippers, marine equipment, welding jaws.
C95400	85 Cu, 4 Fe, 11 Al	85 (105)	35 (54)	18 (8)	60	Bearings, gears, worms, bushings, valve seats and guides, pickling hooks.
C95500	81 Cu, 4 Ni, 4 Fe, 11 Al	100 (120)	44 (68)	12 (10)	50	Valve guides and seats in aircraft engines, corrosion-resistant parts, bushings, gears, worms, pickling hooks and baskets, agitators.
C95600	91 Cu, 7 Al, 2 Si	75	34	18	60	Cable connectors, terminals, valve stems, marine hardware, gears, worms, pole-line hardware.
C95700	75 Cu, 2 Ni, 3 Fe, 8 Al, 12 Mn	95	45	26	50	Propellers, impellers, stator clamp segments, safety tools, welding rods, valves, pump casings.
C95800	81 Cu, 5 Ni, 4 Fe, 9 Al, 1 Mn	95	38	25	50	Propeller hubs, blades, and other parts in contact with salt water.
			Copper–Nickels			
C96200	88.6 Cu, 10 Ni,1.4 Fe	45 min	25 min	20 min	10	Components of items being used for seawater corrosion resistance.
C96300	79.3 Cu, 20 Ni,0.7 Fe	75 min	55 min	10 min	15	Centrifugally cast tailshaft sleeves.
C96400	69.1 Cu, 30 Ni,0.9 Fe	68	37	28	20	Valves, pump bodies, flanges, elbows used for seawater corrosion resistance.
C96600	68.5 Cu, 30 Ni, 1 Fe, 0.5 Be	(110)	(70)	(7)	20	High-strength constructional parts for seawater corrosion resistance.
			Nickel Silvers			
C97300	56 Cu, 2 Sn,10 Pb, 12 Ni,20 Zn	35	17	20	70	Hardware fittings, valves and valve trim, statuary, ornamental castings.
C97400	59 Cu, 3 Sn, 5 Pb, 17 Ni, 16 Zn	38	17	20	60	Valves, hardware, fittings, ornamental castings.
C97600	64 Cu, 4 Sn, 4 Pb, 20 Ni, 8 Zn	45	24	20	70	Marine castings, sanitary fittings, ornamental hardware, valves,pumps.
C97800	66 Cu, 5 Sn, 2 Pb, 25 Ni, 2 Zn	55	30	15	60	Ornamental and sanitary castings, valves and valve seats, musical instrument components.
			Special Alloys			
C99300	71.8 Cu,15 Ni,0.7 Fe, 11 Al,1.5 Co	95	55	2	20	Glass-making molds, plate glass rolls, marine hardware.
C99400	90.4 Cu, 2.2 Ni,2.0 Fe, 1.2 Al,1.2 Si, 3.0 Zn	66 (79)	34 (54)	25	50	Valve stems, marine and other uses requiring resistance to dezincification and dealuminification, propeller wheels, electrical parts, mining equipment gears.
C99500	87.9 Cu, 4.5 Ni, 4.0 Fe, 1.2 Al,1.2 Si, 1.2 Zn	70 min	40 min	12 min	50	Same as C99400, but where higher yield strength is required.
C99700	56.5 Cu, Al,1.5 Pb, 12 Mn,5 Ni, 24 Zn	55	25	25	80	…
C99750	58 Cu,1 Al,1 Pb, 20 Mn, 20 Zn	65 (75)	32 (40)	30 (20)	…	…

[a] Values in parentheses are for heat-treated condition.

[b] Free cutting brass = 100.

Source: Copper Development Association, New York.

Copyright 2004, Industrial Press, Inc., New York, NY

Wrought Copper Alloys.— Wrought copper alloys can be utilized in the annealed, cold-worked, stress-relieved, or hardened-by-heat-treatment conditions, depending on composition and end use. The "temper designation" for copper alloys is defined in ASTM Standard Recommended Practice B601, which is applicable to all product forms.

Wrought copper and high-copper alloys, like cast alloys, have a designated minimum copper content and may include other elements to impart special properties. Wrought brasses have zinc as the principal alloying element and may have other designated elements. They comprise the copper–zinc alloys; copper–zinc–lead alloys (leaded brasses); and copper–zinc–tin alloys (tin brasses).

Wrought bronzes comprise four main groups; copper–tin–phosphorus alloys (phosphor bronze); copper–tin–lead–phosphorus alloys (leaded phosphor bronze); copper–aluminum alloys (aluminum bronzes); and copper–silicon alloys (silicon bronze).

Wrought copper–nickel alloys, like the cast alloys, have nickel as the principal alloying element. The wrought copper–nickel–zinc alloys are known as "nickel silvers" because of their color.

Table 3 lists the nominal composition, properties, and applications of common wrought copper alloys.

Table 3. Properties and Applications of Wrought Coppers and Copper Alloys

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C10100 Oxygen-free electronic	99.99 Cu	32 –66	10 –53	55	20	Excellent hot and cold workability; good forgeability. Fabricated by blanking, coining, coppersmithing, drawing and upsetting, hot forging and pressing, spinning, swaging, stamping. Uses: busbars, bus conductors, waveguides, hollow conductors, lead-in wires and anodes for vacuum tubes, vacuum seals, transistor components, glass to metal seals, coaxial cables and tubes, klystrons, microwave tubes, rectifiers.
C10200 Oxygen-free copper	99.95 Cu	32–66	10–53	55	20	Fabricating characteristics same as C10100. Uses: busbars, waveguides.
C10300 Oxygen-free, extra-low phosphorus	99.95 Cu, 0.003 P	32–55	10–50	50	20	Fabricating characteristics same as C10100. Uses: busbars, electrical conductors, tubular bus, and applications requiring good conductivity and welding or brazing properties.
C10400, C10500, C10700 Oxygen-free, silver-bearing	99.95 Cu	32–66	10–53	55	20	Fabricating characteristics same as C10100. Uses: auto gaskets, radiators, busbars, conductivity wire, contacts, radio parts, winding, switches, terminals, commutator segments; chemical process equipment, printing rolls, clad metals, printed-circuit foil.
C10800 Oxygen-free, low phosphorus	99.95 Cu, 0.009 P	32–55	10–50	50	20	Fabricating characteristics same as C10100. Uses: refrigerators, air conditioners, gas and heater lines, oil burner tubes, plumbing pipe and tube, brewery tubes, condenser and heat-exchanger tubes, dairy and distiller tubes, pulp and paper lines, tanks; air, gasoline, and hydraulic lines.
C11000 Electrolytic tough pitch copper	99.90 Cu, 0.04 O	32–66	10–53	55	20	Fabricating characteristics same as C10100. Uses: downspouts, gutters, roofing, gaskets, auto radiators, busbars, nails, printing rolls, rivets, radio parts.
C11000 Electrolytic tough pitch, anneal-resistant	99.90 Cu, 0.04 O, 0.01 Cd	66	…	…	20	Fabricated by drawing and stranding, stamping. Uses: electrical power transmission where resistance to softening under overloads is desired.
C11300, C11400, C11500, C11600 Silver- bearing tough pitch copper	99.90 Cu, 0.04 O, Ag	32–66	10–53	55	20	Fabricating characteristics same as C10100. Uses: gaskets, radiators, busbars, windings, switches, chemical process equipment, clad metals, printed-circuit foil.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C12000, C12100 Phosphorus deoxidized, low residual phosphorus	99.9 Cu	32–57	10–53	55	20	Fabricating characteristics same as C10100. Uses: busbars, electrical conductors, tubular bus, and applications requiring welding or brazing.
C12200, C12210 Phosphorus deoxidized copper, high residual phosphorus	99.90 Cu, 0.02 P	32–55	10–53	55	20	Fabricating characteristics same as C10100. Uses: gas and heater lines; oil burner tubing; plumbing pipe and tubing; condenser, evaporator, heat exchanger, dairy, and distiller tubing; steam and water lines; air, gasoline, and hydraulic lines.
C12500, C12700, C12800, C12900, C13000 Fire-refined tough pitch with silver	99.88 Cu	32–66	10–53	55	20	Fabricating characteristics same as C10100. Uses: same as C11000, Electrolytic tough pitch copper.
C14200 Phosphorus deoxidized, arsenical	99.68 Cu, 0.3 As, 0.02 P	32–55	10–50	45	20	Fabricating characteristics same as C10100. Uses: staybolts, heat-exchanger and condenser tubes.
C14300, C14310 Cadmium copper, deoxidized	99.9 Cu, 0.1 Cd	32–58	11–56	42	20	Fabricating characteristics same as C10100. Uses: anneal-resistant electrical applications requiring thermal softening and embrittlement resistance, lead frames, contacts, terminals, solder-coated and solder-fabricated parts, furnace-brazed assemblies and welded components, cable wrap.
C14500, C14510, C14520 Tellurium bearing	99.5 Cu, 0.50 Te, 0.008 P	32–56	10–51	50	85	Fabricating characteristics same as C10100. Uses: Forgings and screw-machine products, and parts requiring high conductivity, extensive machining, corrosion resistance, copper color, or a combination of these; electrical connectors, motor and switch parts, plumbing fittings, soldering coppers, welding torch tips, transistor bases, and furnace-brazed articles.
C14700, C14710, C14720 Sulfur bearing	99.6 Cu, 0.40 S	32–57	10–55	52	85	Fabricating characteristics same as C10100. Uses: screw-machine products and parts requiring high conductivity, extensive machining, corrosion resistance, copper color, or a combination of these; electrical connectors, motor and switch components, plumbing fittings, cold-headed and machined parts, cold forgings, furnace-brazed articles, screws, soldering coppers, rivets and welding torch tips.
C15000 Zirconium copper	99.8 Cu, 0.15 Zr	29–76	6–72	54	20	Fabricating characteristics same as C10100. Uses: switches, high-temperature circuit breakers, commutators, stud bases for power transmitters, rectifiers, soldering welding tips.
C15500	99.75 Cu, 0.06 P, 0.11 Mg, Ag	40–80	18–72	40	20	Fabricating characteristics same as C10100. Uses: high-conductivity light-duty springs, electrical contacts, fittings, clamps, connectors, diahragms, electronic components, resistance-welding electrodes.
C15715	99.6 Cu, 0.13 Al_2O_3	52–88	44–84	27	20	Excellent cold workability. Fabricated by extrusion, drawing, rolling, heading, swaging, machining, blanking, roll threading. Uses: integrated-circuit lead frames, diode leads; vacuum, microwave, and x-ray tube components; electrical components; brush springs; commutators, electric generator and motor components.
C15720	99.5 Cu, 0.18 Al_2O_3	64–98	54–96	25	…	Excellent cold workability, Fabricated by extrusion, drawing, rolling, heading, swaging, machining, blanking. Uses: relay and switch springs, lead frames, contact supports, heat sinks, circuit breaker parts, rotor bars, resistance-welding electrodes and wheels, connectors, soldering gun tips.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C15760	98.8 Cu, 0.58 Al_2O_3	70–90	65–87	22	…	Excellent cold workability. Fabricated by extrusion and drawing. Uses: resistance-welding electrodes, soldering gun tips, MIG welding contact tips, continuous-casting molds.
C16200, C16210 Cadmium copper	99.0 Cu, 1.0 Cd	35–100	7–69	57	20	Excellent cold workability; good hot formability. Uses: trolley wires, heating pads, electric-blanket elements, spring contacts, railbands, high-strength transmission lines, connectors, cable wrap, switchgear components, and waveguide cavities.
C16500	98.6 Cu, 0.8 Cd, 0.6 Sn	40–95	14–71	53	20	Fabricating characteristics same as C16200. Uses: electrical springs and contacts, trolley wire, clips, flat cable, resistance-welding electrodes.
C17000 Beryllium copper	98.3 Cu, 1.7 Be, 0.20 Co	70–190	32–170	45	20	Fabricating characteristics same as C16200. Commonly fabricated by blanking, forming and bending, turning, drilling, tapping. Uses: bellows, Bourdon tubing, diaphragms, fuse clips, fasteners, lock-washers, springs, switch parts, roll pins, valves, welding equipment.
C17200 Beryllium copper	98.1 Cu, 1.9 Be, 0.20 Co	68–212	25–195	48	20	Similar to C17000, particularly for its nonsparking characteristics.
C17300 Beryllium copper	98.1 Cu, 1.9 Be, 0.40 Pb	68–212	25–195	48	50	Combines superior machinability with good fabricating characteristics of C17200.
C17500, C17510 Beryllium copper	96.9 Cu, 2.5 Co, 0.6 Be	45–115	25–110	28	…	Fabricating characteristics same as C16200. Uses: fuse clips, fasteners, springs, switch and relay parts, electrical conductors, welding equipment.
C18200, C18400, C18500 Chromium copper	99.2 Cu	34–86	14–77	40	20	Excellent cold workability, good hot workability. Uses: resistance-welding electrodes, seam-welding wheels, switch gear, electrode holder jaws, cable connectors, current-carrying arms and shafts, circuit-breaker parts, molds, spot-welding tips, flash-welding electrodes, electrical and thermal conductors requiring strength, switch contacts.
C18700 Leaded copper	99.0 Cu, 1.0 Pb	32–55	10–50	45	85	Good cold workability; poor hot formability. Uses: connectors, motor and switch parts, screw-machine parts requiring high conductivity.
C18900	98.7 Cu, 0.8 Sn, 0.3 Si, 0.20 Mn	38–95	9–52	48	20	Fabricating characteristics same as C10100. Uses: welding rod and wire for inert gas tungsten arc and metal arc welding and oxyacetylene welding of copper.
C19000 Copper–nickel–phosphorus alloy	98.6 Cu, 1.1 Ni, 0.3 P	38–115	20–81	50	30	Fabricating characteristics same as C10100. Uses: springs, clips, electrical connectors, power tube and electron tube components, high-strength electrical conductors, bolts, nails, screws, cotter pins, and parts requiring some combination of high strength, high electrical or thermal conductivity, high resistance to fatigue and creep, and good workability.
C19100 Copper– nickel– phosphorus– tellurium alloy	98.2 Cu, 1.1 Ni, 0.5 Te, 0.2 P	36–104	10–92	27	75	Good hot and cold workability. Uses: forgings and screw-machine parts requiring high strength, hardenability, extensive machining, corrosion resistance, copper color, good conductivity, or a combination of these; bolts, bushings, electrical connectors, gears, marine hardware, nuts, pinions, tie rods, turnbuckle barrels, welding torch tips.
C19200	99 Cu, 1.0 Fe, 0.03 P	37–77	11–74	40	20	Excellent hot and cold workability. Uses: automotive hydraulic brake lines, flexible hose, electrical terminals, fuse clips, gaskets, gift hollow ware, applications requiring resistance to softening and stress corrosion, air-conditioning and heat-exchanger tubing.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C19400	97.4 Cu, 2.4 Fe, 0.13 Zn, 0.04 P	45–76	24–73	32	20	Excellent hot and cold workability. Uses: circuit-breaker components, contact springs, electrical clamps, electrical springs, electrical terminals, flexible hose, fuse clips, gaskets, gift hollow ware, plug contacts, rivets, and welded condenser tubes.
C19500	97.0 Cu, 1.5 Fe, 0.6 Sn, 0.10 P, 0.80 Co	80–97	65–95	15	20	Excellent hot and cold workability. Uses: electrical springs, sockets, terminals, connectors, clips, and other current-carrying parts requiring strength.
C21000 Gilding, 95%	95.0 Cu, 5.0 Zn	34–64	10–58	45	20	Excellent cold workability, good hot workability for blanking, coining, drawing, piercing and punching, shearing, spinning, squeezing and swaging, stamping. Uses: coins, medals, bullet jackets, fuse caps, primers, plaques, jewelry base for gold plate.
C22000 Commercial bronze, 90%	90.0 Cu, 10.0 Zn	37–72	10–62	50	20	Fabricating characteristics same as C21000, plus heading and up-setting, roll threading and knurling, hot forging and pressing. Uses: etching bronze, grillwork, screen cloth, weatherstripping, lipstick cases, compacts, marine hardware, screws, rivets.
C22600 Jewelry bronze, 87.5%	87.5 Cu, 12.5 Zn	39–97	11–62	46	30	Fabricating characteristics same as C21000, plus heading and up-setting, roll threading and knurling. Uses: angles, channels, chain, fasteners, costume jewelry, lipstick cases, powder compacts, base for gold plate.
C23000 Red brass, 85%	85.0 Cu, 15.0 Zn	39–105	10–63	55	30	Excellent cold workability; good hot formability. Uses: weather-stripping, conduit, sockets, fasteners, fire extinguishers, condenser and heat-exchanger tubing, plumbing pipe, radiator cores.
C24000 Low brass, 80%	80.0 Cu, 20.0 Zn	42–125	12–65	55	30	Excellent cold workability. Fabricating characteristics same as C23000. Uses: battery caps, bellows, musical instruments, clock dials, pump lines, flexible hose.
C26000, C26100, C26130, C26200 Cartridge brass, 70%	70.0 Cu, 30.0 Zn	44 – 130	11–65	66	…	Excellent cold workability. Uses: radiator cores and tanks, flashlight shells, lamp fixtures, fasteners, screws, springs, grillwork, stencils, plumbing accessories, plumbing brass goods, locks, hinges, ammunition components, plumbing accessories, pins, rivets.
C26800, C27000 Yellow brass	65.0 Cu, 35.0 Zn	46–128	14–62	65	30	Excellent cold workability. Fabricating characteristics same as C23000. Uses: same as C26000 except not used for ammunition.
C28000 Muntz metal, 60%	60.0 Cu, 40.0 Zn	54–74	21–55	52	40	Excellent hot formability and forgeability for blanking, forming and bending, hot forging and pressing, hot heading and upsetting, shearing. Uses: architectural, large nuts and bolts, brazing rod, condenser plates, heat-exchanger and condenser tubing, hot forgings.
C31400 Leaded commercial bronze	89.0 Cu, 1.9 Pb, 0.1 Zn	37–60	12–55	45	80	Excellent machinability. Uses: screws, machine parts, pickling crates.
C31600 Leaded commercial bronze, nickel-bearing	89.0 Cu, 1.9 Pb, 1.0 Ni, 8.1 Zn	37–67	12–59	45	80	Good cold workability; poor hot formability. Uses: electrical connectors, fasteners, hardware, nuts, screws, screw-machine parts.
C33000 Low-leaded brass tube	66.0 Cu, 0.5 Pb, 33.5 Zn	47–75	15–60	60	60	Combines good machinability and excellent cold workability. Fabricated by forming and bending, machining, piercing and punching. Uses: pump and power cylinders and liners, ammunition primers, plumbing accessories.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C33200 High-leaded brass tube	66.0 Cu, 2.0 Pb, 32.0 Zn	47–75	15–60	50	80	Excellent machinability. Fabricated by piercing, punching, and machining. Uses: general-purpose screw-machine parts.
C33500 Low-leaded brass	63.5 Cu, 0.5 Pb, 36 Zn	46–74	14–60	65	60	Similar to C33200. Commonly fabricated by blanking, drawing, machining, piercing and punching, stamping. Uses: butts, hinges, watch backs.
C34000 Medium-leaded brass	63.5 Cu, 1.0 Pb, 35.5 Zn	47–88	15–60	60	70	Similar to C33200. Fabricated by blanking, heading and upsetting, machining, piercing and punching, roll threading and knurling, stamping. Uses: butts, gears, nuts, rivets, screws, dials, engravings, instrument plates.
C34200 High-leaded brass	63.5 Cu, 2.0 Pb, 34.5 Zn	49–85	17–62	52	90	Combines excellent machinability with moderate cold workability. Uses: clock plates and nuts, clock and watch backs, gears, wheels and channel plate.
C35000 Medium-leaded brass	62.5 Cu, 1.1 Pb, 36.4 Zn	45–95	13–70	66	70	Fair cold workability; poor hot formability. Uses: bearing cages, book dies, clock plates, gears, hinges, hose couplings, keys, lock parts, lock tumblers, meter parts, nuts, sink strainers, strike plates, templates, type characters, washers, wear plates.
C35300 High-leaded brass	61.5 Cu, 2.8 Pb, 36.5 Zn	49–85	17–62	52	90	Similar to C34200.
C35600 Extra-high-leaded brass	61.5 Cu, 2.5 Pb, 36 Zn	47–97	17–87	60	100	Excellent machinability. Fabricated by blanking, machining, piercing and punching, stamping. Uses: clock plates and nuts, clock and watch backs, gears, wheels, and channel plate.
C36000 Free-cutting brass	61.5 Cu, 3.1 Pb, 35.4 Zn	49–68	18–45	53	100	Excellent machinability. Fabricated by machining, roll threading, and knurling. Uses: gears, pinions, automatic high-speed screw-machine parts.
C36500 to C36800 Leaded Muntz metal	59.5 Cu, 0.5 Pb, 40.0 Zn	54 (As hot rolled)	20	45	60	Combines good machinability with excellent hot formability. Uses: condenser-tube plates.
C37000 Free-cutting Muntz metal	60.0 Cu, 1.0 Pb, 39.0 Zn	54–80	20–60	40	70	Fabricating characteristics similar to C36500 to 36800. Uses: automatic screw-machine parts.
C37700 Forging brass	59.5 Cu, 2.0 Pb, 38.0 Zn	52 (As extruded)	20	45	80	Excellent hot workability. Fabricated by heading and upsetting, hot forging and pressing, hot heading and upsetting, machining. Uses: forgings and pressings of all kinds.
C38500 Architectural bronze	57.0 Cu, 3.0 Pb, 40.0 Zn	60 (As extruded)	20	30	90	Excellent machinability and hot workability. Fabricated by hot forging and pressing, forming, bending, and machining. Uses: architectural extrusions, store fronts, thresholds, trim, butts, hinges, lock bodies, and forgings.
C40500	95 Cu, 1 Sn, 4 Zn	39–78	12–70	49	20	Excellent cold workability. Fabricated by blanking, forming, and drawing. Uses: meter clips, terminals, fuse clips, contact and relay springs, washers.
C40800	95 Cu, 2 Sn, 3 Zn	42–79	13–75	43	20	Excellent cold workability. Fabricated by blanking, stamping, and shearing. Uses: electrical connectors.
C41100	91 Cu, 0.5 Sn, 8.5 Zn	39–106	11–72	43	20	Excellent cold workability, good hot formability. Fabricated by blanking, forming and bending, drawing, piercing and punching, shearing, spinning, and stamping. Uses: bushings, bearing sleeves, thrust washers, flexible metal hose.
C41300	90.0 Cu, 1.0 Sn, 9.0 Zn	41–105	12–82	45	20	Excellent cold workability; good hot formability. Uses: plater bar for jewelry products, flat springs for electrical switchgear.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C41500	91 Cu, 1.8 Sn, 7.2 Zn	46–81	17–75	44	30	Excellent cold workability. Fabricated by blanking, drawing, bending, forming, shearing, and stamping. Uses: spring applications for electrical switches.
C42200	87.5 Cu, 1.1 Sn, 11.4 Zn	43–88	15–75	46	30	Excellent cold workability; good hot formability. Fabricated by blanking, piercing, forming, and drawing. Uses: sash chains, fuse clips, terminals, spring washers, contact springs, electrical connectors.
C42500	88.5 Cu, 2.0 Sn, 9.5 Zn	45–92	18–76	49	30	Excellent cold workability. Fabricated by blanking, piercing, forming, and drawing. Uses: electrical switches, springs, terminals, connectors, fuse clips, pen clips, weather stripping.
C43000	87.0 Cu, 2.2 Sn, 10.8 Zn	46–94	18–73	55	30	Excellent cold workability; good hot formability. Fabricated by blanking, coining, drawing, forming, bending, heading, and upsetting. Uses: same as C42500.
C43400	85.0 Cu, 0.7 Sn, 14.3 Zn	45–90	15–75	49	30	Excellent cold workability. Fabricated by blanking, drawing, bonding, forming, stamping, and shearing. Uses: electrical switch parts, blades, relay springs, contacts.
C43500	81.0 Cu, 0.9 Sn, 18.1 Zn	46–80	16–68	46	30	Excellent cold workability for fabrication by forming and bending. Uses: Bourdon tubing and musical instruments.
C44300, C44400, C44500 Inhibited admiralty	71.0 Cu, 28.0 Zn, 1.0 Sn	48–55	18–22	65	30	Excellent cold workability for forming and bending. Uses: condenser, evaporator and heat-exchanger tubing, condenser tubing plates, distiller tubing, ferrules.
C46400 to C46700 Naval brass	60.0 Cu, 39.2 Zn, 0.8 Sn	55–88	25–66	50	30	Excellent hot workability and hot forgeability. Fabricated by blanking, drawing, bending, heading and upsetting, hot forging, pressing. Uses: aircraft turnbuckle barrels, balls, bolts, marine hardware, nuts, propeller shafts, rivets, valve stems, condenser plates, welding rod.
C48200 Naval brass, medium-leaded	60.5 Cu, 0.7 Pb, 0.8 Sn, 38.0 Zn	56–75	25–53	43	50	Good hot workability for hot forging, pressing, and machining operations. Uses: marine hardware, screw-machine products, valve stems.
C48500 Leaded naval brass	60.0 Cu, 1.8 Pb, 37.5 Zn, 0.7 Sn	57–75	25–53	40	70	Combines good hot forgeability and machinability. Fabricated by hot forging and pressing, machining. Uses: marine hardware, screw-machine parts, valve stems.
C50500 Phosphor bronze, 1.25% E	98.7 Cu, 1.3 Sn, trace P	40–79	14–50	48	20	Excellent cold workability; good hot formability. Fabricated by blanking, bending, heading and upsetting, shearing and swaging. Uses: electrical contacts, flexible hose, pole-line hardware.
C51000 Phosphor bronze, 5% A	94.8 Cu, 5.0 Sn, trace P	47–140	19–80	64	20	Excellent cold workability. Fabricated by blanking, drawing, bending, heading and upsetting, roll threading and knurling, shearing, stamping. Uses: bellows, Bourdon tubing, clutch discs, cotter pins, diaphragms, fasteners, lock washers, wire brushes, chemical hardware, textile machinery, welding rod.
C51100	95.6 Cu, 4.2 Sn, 0.2 P	46–103	50–80	48	20	Excellent cold workability. Uses: bridge bearing plates, locator bars, fuse clips, sleeve bushings, springs, switch parts, truss wire, wire brushes, chemical hardware, perforated sheets, textile machinery.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C52100 Phosphor bronze, 8% C	92.0 Cu, 8.0 Sn, trace P	55–140	24–80	70	20	Good cold workability for blanking, drawing, forming and bending, shearing, stamping. Uses: generally for more severe service conditions than C51000.
C52400 Phosphor bronze, 10% D	90.0 Cu, 10.0 Sn, trace P	66–147	28	70	20	Good cold workability for blanking, forming and bending, shearing. Uses: heavy bars and plates for severe compression, bridge and expansion plates and fittings, articles requiring good spring qualities, resilience, fatigue resistance, good wear and corrosion resistance.
C54400	88.0 Cu, 4.0 Pb, 4.0 Zn, 4.0 Sn	44–75	19–63	50	80	Excellent machinability; good cold workability. Fabricated by blanking, drawing, bending, machining, shearing, stamping. Uses: bearings, bushings, gears, pinions, shafts, thrust washers, valve parts.
C60800	95.0 Cu, 5.0 Al	60	27	55	20	Good cold workability; fair hot formability. Uses: condenser, evaporator and heat-exchanger tubes, distiller tubes, ferrules.
C61000	92.0 Cu, 8.0 Al	52–60	17–27	45	20	Good hot and cold workability. Uses: bolts, pump parts, shafts, tie rods, overlay on steel for wearing surfaces.
C61300	90.3 Cu, 0.35 Sn, 6.8 Al, 0.35 Sn	70–85	30–58	42	30	Good hot and cold formability. Uses: nuts, bolts, corrosion resistant vessels and tanks, structural components, machine parts, condenser tube and piping systems, marine protective sheathing and fasteners, munitions mixing troughs and blending chambers.
C61400 Aluminum bronze, D	91.0 Cu, 7.0 Al, 2.0 Fe	76–89	33–60	45	20	Similar to C61300.
C61500	90.0 Cu, 8.0 Al, 2.0 Ni	70–145	22–140	55	30	Good hot and cold workability. Fabricating characteristics similar to C52100. Uses: hardware, decorative metal trim, interior furnishings and other articles requiring high tarnish resistance.
C61800	89.0 Cu, 1.0 Fe, 10.0 Al	80–85	39–42.5	28	40	Fabricated by hot forging and hot pressing. Uses: bushings, bearings, corrosion-resistant applications, welding rods.
C61900	86.5 Cu, 4.0 Fe, 9.5 Al	92–152	49–145	30	…	Excellent hot formability for fabricating by blanking, forming, bending, shearing, and stamping. Uses: springs, contacts, and switch components.
C62300	87.0 Cu, 3.0 Fe, 10.0 Al	75–98	35–52	35	50	Good hot and cold formability. Fabricated by bending, hot forging, hot pressing, forming, and welding. Uses: bearings, bushings, valve guides, gears, valve seats, nuts, bolts, pump rods, worm gears, and cams.
C62400	86.0 Cu, 3.0 Fe, 11.0 Al	90–105	40–52	18	50	Excellent hot formability for fabrication by hot forging and hot bending. Uses: bushings, gears, cams, wear strips, nuts, drift pins, tie rods.
C62500	82.7 Cu, 4.3 Fe, 13.0 Al	100 (As extruded)	55	1	20	Excellent hot formability for fabrication by hot forging and machining. Uses: guide bushings, wear strips, cams, dies, forming rolls.
C63000	82.0 Cu, 3.0 Fe, 10.0 Al, 5.0 Ni	90–118	50–75	20	30	Good hot formability. Fabricated by hot forming and forging. Uses: nuts, bolts, valve seats, plunger tips, marine shafts, valve guides, aircraft parts, pump shafts, structural members.
C63200	82.0 Cu, 4.0 Fe, 9.0 Al, 5.0 Ni	90–105	45–53	25	30	Good hot formability. Fabricated by hot forming and welding. Uses: nuts, bolts, structural pump parts, shafting requiring corrosion resistance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C63600	95.5 Cu, 3.5 Al, 1.0 Si	60–84	…	64	40	Excellent cold workability; fair hot formability. Fabricated by cold heading. Uses: components for pole-line hardware, cold-headed nuts for wire and cable connectors, bolts and screw products.
C63800	95.0 Cu, 2.8 Al, 1.8 Si, 0.40 Co	82–130	54–114	36	…	Excellent cold workability and hot formability. Uses: springs, switch parts, contacts, relay springs, glass sealing, and porcelain enameling.
C64200	91.2 Cu, 7.0 Al, 1.8 Si	75–102	35–68	32	60	Excellent hot formability. Fabricated by hot forming, forging, machining. Uses: valve stems, gears, marine hardware, pole-line hardware, bolts, nuts, valve bodies, and components.
C65100 Low-silicon bronze, B	98.5 Cu, 1.5 Si	40–105	15–71	55	30	Excellent hot and cold workability. Fabricated by forming and bending, heading and upsetting, hot forging and pressing, roll threading and knurling, squeezing and swaging. Uses: hydraulic pressure lines, anchor screws, bolts, cable clamps, cap screws, machine screws, marine hardware, nuts, pole-line hardware, rivets, U-bolts, electrical conduits, heat-exchanger tubing, welding rod.
C65500 High-silicon bronze, A	97.0 Cu, 3.0 Si	56–145	21–71	63	30	Excellent hot and cold workability. Fabricated by blanking, drawing, forming and bending, heading and upsetting, hot forging and pressing, roll threading and knurling, shearing, squeezing and swaging. Uses: similar to C65100 including propeller shafts.
C66700 Manganese brass	70.0 Cu, 28.8 Zn, 1.2 Mn	45.8–100	12–92.5	60	30	Excellent cold formability. Fabricated by blanking, bending, forming, stamping, welding. Uses: brass products resistance welded by spot, seam, and butt welding.
C67400	58.5 Cu, 36.5 Zn, 1.2 Al, 2.8 Mn, 1.0 Sn	70–92	34–55	28	25	Excellent hot formability. Fabricated by hot forging and pressing, machining. Uses: bushings, gears, connecting rods, shafts, wear plates.
C67500 Manganese bronze, A	58.5 Cu, 1.4 Fe, 39.0 Zn, 1.0 Sn, 0.1 Mn	65–84	30–60	33	30	Excellent hot workability. Fabricated by hot forging and pressing, hot heading and upsetting. Uses: clutch discs, pump rods, shafting, balls, valve stems and bodies.
C68700 Aluminum brass, arsenical	77.5 Cu, 20.5 Zn, 2.0 Al, trace As	60	27	55	30	Excellent cold workability for forming and bending. Uses: condenser, evaporator- and heat-exchanger tubing, condenser tubing plates, distiller tubing, ferrules.
C68800	73.5 Cu, 22.7 Zn, 3.4 Al, 0.40 Co	82–129	55–114	36	…	Excellent hot and cold formability. Fabricated by blanking, drawing, forming and bending, shearing and stamping. Uses: springs, switches, contacts, relays, drawn parts.
C69000	73.3 Cu, 3.4 Al, 0.6 Ni, 22.7 Zn	82–130	52–117	35	…	Fabricating characteristics same as C68800. Uses: contacts, relays, switches, springs, drawn parts.
C69400 Silicon red brass	81.5 Cu, 14.5 Zn, 4.0 Si	80–100	40–57	25	30	Excellent hot formability for fabrication by forging, screw-machine operations. Uses: valve stems where corrosion resistance and high strength are critical.
C70400 Copper nickel, 5%	92.4 Cu, 1.5 Fe, 5.5 Ni, 0.6 Mn	38–77	40–76	46	20	Excellent cold workability; good hot formability. Fabricated by forming, bending, and welding. Uses: condensers, evaporators, heat exchangers, ferrules, salt water piping, lithium bromide absorption tubing, shipboard condenser intake systems.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Properties and Applications of Wrought Coppers and Copper Alloys**

Name and Number	Nominal Composition (%)	Strength (ksi)		Elongation in 2 in. (%)	Machinability Rating[a]	Fabricating Characteristics and Typical Applications
		Tensile	Yield			
C70600 Copper nickel, 10%	88.6 Cu, 1.4 Fe, 10.0 Ni	44–60	16–57	42	20	Good hot and cold workability. Fabricated by forming and bending, welding. Uses: condensers, condenser plates, distiller tubing, evaporator and heat-exchanger tubing, ferrules.
C71000 Copper nickel, 20%	79.0 Cu, 21.0 Ni	49–95	13–85	40	20	Good hot and cold formability. Fabricated by blanking, forming and bending, welding. Uses: communication relays, condensers, condenser plates, electrical springs, evaporator and heat-exchanger tubes, ferrules, resistors.
C71500 Copper nickel, 30%	69.5 Cu, 30.0 Ni, 0.5 Fe	54–75	20–70	45	20	Similar to C70600.
C72200	82.2 Cu, 16.5 Ni, 0.8 Fe, 0.5 Cr	46–70	18–66	46	…	Good hot and cold formability. Fabricated by forming, bending, and welding. Uses: condenser tubing, heat-exchanger tubing, salt water piping.
C72500	88.2 Cu, 9.5 Ni, 2.3 Sn	55–120	22–108	35	20	Excellent cold and hot formability. Fabricated by blanking, brazing, coining, drawing, etching, forming and bending, heading and upsetting, roll threading and knurling, shearing, spinning, squeezing, stamping, and swaging. Uses: relay and switch springs, connectors, brazing alloy, lead frames, control and sensing bellows.
C73500	72.0 Cu, 10.0 Zn, 18.0 Ni	50–100	15–84	37	20	Fabricating characteristics same as C74500. Uses: hollow ware, medallions, jewelry, base for silver plate, cosmetic cases, musical instruments, name plates, contacts.
C74500 Nickel silver, 65–10	65.0 Cu, 25.0 Zn, 10.0 Ni	49–130	18–76	50	20	Excellent cold workability. Fabricated by blanking, drawing, etching, forming and bending, heading and upsetting, roll threading and knurling, shearing, spinning, squeezing, and swaging. Uses: rivets, screws, slide fasteners, optical parts, etching stock, hollow ware, nameplates, platers' bars.
C75200 Nickel silver, 65–18	65.0 Cu, 17.0 Zn, 18.0 Ni	56–103	25–90	45	20	Fabricating characteristics similar to C74500. Uses: rivets, screws, table flatware, truss wire, zippers, bows, camera parts, core bars, temples, base for silver plate, costume jewelry, etching stock, hollow ware, nameplates, radio dials.
C75400 Nickel silver, 65–15	65.0 Cu, 20.0 Zn, 15.0 Ni	53–92	18–79	43	20	Fabricating characteristics similar to C74500. Uses: camera parts, optical equipment, etching stock, jewelry.
C75700 Nickel silver, 65–12	65.0 Cu, 23.0 Zn, 12.0 Ni	52–93	18–79	48	20	Fabricating characteristics similar to C74500. Uses: slide fasteners, camera parts, optical parts, etching stock, name plates.
C76390	61 Cu, 13 Zn, 24.5 Ni, 1 Pb, 0.5 Sn	90	85	6	40	Fabricated by machining, roll threading, and knurling. Uses: hardware, fasteners, connectors for electronic applications.
C77000 Nickel silver, 55–18	55.0 Cu, 27.0 Zn, 18.0 Ni	60–145	27–90	40	30	Good cold workability. Fabricated by blanking, forming and bending, and shearing. Uses: optical goods, springs, and resistance wire.
C78200	65.0 Cu, 2.0 Pb, 25.0 Zn, 8.0 Ni	53–91	23–76	40	60	Good cold formability. Fabricated by blanking, milling, and drilling. Uses: key blanks, watch plates, watch parts.

[a] Free-cutting brass = 100.

Source: Copper Development Association, New York.

Copyright 2004, Industrial Press, Inc., New York, NY

Strength of Copper–Zinc–Tin Alloys (U.S. Government Tests)

Percentage of			Tensile Strength, lb/in²	Percentage of			Tensile Strength, lb/in²	Percentage of			Tensile Strength, lb/in²
Copper	Zinc	Tin		Copper	Zinc	Tin		Copper	Zinc	Tin	
45	50	5	15,000	60	20	20	10,000	75	20	5	45,000
50	45	5	50,000	65	30	5	50,000	75	15	10	45,000
50	40	10	15,000	65	25	10	42,000	75	10	15	43,000
55	43	2	65,000	65	20	15	30,000	75	5	20	41,000
55	40	5	62,000	65	15	20	18,000	80	15	5	45,000
55	35	10	32,500	65	10	25	12,000	80	10	10	45,000
55	30	15	15,000	70	25	5	45,000	80	5	15	47,500
60	37	3	60,000	70	20	10	44,000	85	10	5	43,500
60	35	5	52,500	70	15	15	37,000	85	5	10	46,500
60	30	10	40,000	70	10	20	30,000	90	5	5	42,000

Copper–Silicon and Copper–Beryllium Alloys

Everdur.— This copper–silicon alloy is available in five slightly different nominal compositions for applications that require high strength, good fabricating and fusing qualities, immunity to rust, free-machining and a corrosion resistance equivalent to copper. The following table gives the nominal compositions and tensile strengths, yield strengths, and per cent elongations for various tempers and forms.

Table 4. Nominal Composition and Properties of Everdur

Desig. No.	Nominal Composition					Temper[a]	Strength		Elongation (%)
	Cu	Si	Mn	Pb	Al		Tensile (ksi)	Yield (ksi)	
655	95.80	3.10	1.10	…	…	A	52	15	35[b]
						HRA	50	18	40
						CRA	52	18	35
						CRHH	71	40	10
						CRH	87	60	3
						H	70 to 85	38 to 50	17 to 8[b]
651	98.25	1.50	0.25	…	…	AP	38	10	35
						HP	50	40	7
						XHB	75 to 85	45 to 55	8 to 6[b]
661	95.60	3.00	1.00	0.40	…	A	52	15	35[b]
						H	85	50	13 to 8[b]
6552	94.90	4.00	1.10	…	…	AC	45	…	15
637	90.75	2.00	…	…	7.25	A	75 to 90	37.5 to 45	12 to 9[b]

[a] Symbols used are: HRA for hot-rolled and annealed tank plates; CRA for cold-rolled sheets and strips; CRHH for cold-rolled half hard strips; abd CRH for cold-rolled hard strips. For round, square, hexagonal, and octagonal rods: A for anealed; H for hard; and XHB for extra-hard bolt temper (in coils for cold-heading). For pipe and tube: AP for annealed; and HP for hard. For castings: AC for as cast.

[b] Per cent elongation in 4 times the diameter or thickness of the specimen. All other values are per cent elongation in 2 inches.

Designation numbers are those of the American Brass Co.

The values given for the tensile srength, yield strength, and elongation are all minimum values. Where ranges are shown, the first values given are for the largest diameter or largest size specimens. Yield strength values were determined at 0.50 per cent elongation under load.

Copper–Beryllium Alloys.— Alloys of copper and beryllium present health hazards. Particles produced by machining may be absorbed into the body through the skin, the mouth, the nose, or an open wound, resulting in a condition requiring immediate medical attention. Working of these alloys requires protective clothing or other shielding in a monitored environment. Copper–beryllium alloys involved in a fire give off profuse toxic fumes that must not be inhaled.

Copyright 2004, Industrial Press, Inc., New York, NY

These alloys contain copper, beryllium, cobalt, and silver, and fall into two groups. One group whose beryllium content is greater than one per cent is characterized by its high strength and hardness and the other, whose beryllium content is less than one per cent, by its high electrical and thermal conductivity. The alloys have many applications in the electrical and aircraft industries or wherever strength, corrosion resistance, conductivity, nonmagnetic and nonsparking properties are essential. Beryllium copper is obtainable in the form of strips, rods and bars, wire, platers, bars, billets, tubes, and casting ingots.

Composition and Properties: Table 5 lists some of the more common wrought alloys and gives some of their mechanical properties.

Table 5. Wrought Copper–Beryllium Properties

Alloy[a]	Form	Temper[b]	Heat Treatment	Tensile Strength (ksi)	Yield Strength 0.2% Offset (ksi)	Elongation in 2 in. (%)
25	Rod, Bar, and Plate	A	…	60–85	20–30	35–60
		½ H or H	…	85–130	75–105	10–20
		AT	3 hr at 600°F or mill heat treated	165–190	145–175	3–10
		½ HT or HT	2 hr at 600°F or mill heat treated	175–215	150–200	2–5
	Wire	A	…	58–78	20–35	35–55
		¼ H	…	90–115	70–95	10–35
		½ H	…	110–135	90–110	5–10
		¾ H	…	130–155	110–135	2–8
		AT	3 hr at 600°F	165–190	145–175	3–8
		¼ HT	2 hr at 600°F	175–205	160–190	2–5
		½ HT	2 hr at 600°F	190–215	175–200	1–3
		¾ HT	2 hr at 600°F	195–220	180–205	1–3
		XHT	Mill heat treated	115–165	95–145	2–8
165	Rod, Bar, and Plate	A	…	60–85	20–30	35–60
		½ H or H	…	85–130	75–105	10–20
		AT	3 hr at 650°F or mill heat treated	150–180	125–155	4–10
		½ HT or HT	2 hr at 650°F or mill heat treated	165–200	135–165	2–5
10	Rod, Bar, and Plate	A	…	35–55	20–30	20–35
		½ H or H	…	65–80	55–75	10–15
		AT	3 hr at 900°F or mill heat treated	100–120	80–100	10–25
		½ HT or HT	2 hr at 900°F or mill heat treated	110–130	100–120	8–20
50	Rod, Bar, and Plate	A	…	35–55	20–30	20–35
		½ H or H	…	65–80	55–75	10–15
		AT	3 hr at 900°F or mill heat treated	100–120	80–100	10–25
		½ HT or HT	2 hr at 900°F or mill heat treated	110–130	100–120	8–20
35	Rod, Bar, and Plate	A	…	35–55	20–30	20–35
		½ H or H	…	65–80	55–75	10–15
		AT	3 hr at 900°F or mill heat treated	100–120	80–100	10–25
		½ HT or HT	2 hr at 900°F or mill heat treated	110–130	100–120	8–20

[a] Composition (in per cent) of alloys is asfollows: alloy 25: 1.80–2.05 Be, 0.20–0.35 Co, balance Cu; alloy 165: 1.6–1.8 Be, 0.20–0.35 Co, balance Cu; alloy 10: 0.4–0.7 Be, 2.35–2.70 Co, balance Cu; alloy 50, 0.25–0.50 Be, 1.4–1.7 Co, 0.9–1.1 Ag, balance Cu; alloy 35, 0.25–0.50 Be, 1.4–1.6 Ni, balance Cu.

[b] Temper symbol designations: A, solution annealed; H, hard; HT, heat-treated from hard; At, heat-treated from solution annealed.

Copyright 2004, Industrial Press, Inc., New York, NY

Aluminum and Aluminum Alloys

Pure aluminum is a silver-white metal characterized by a slightly bluish cast. It has a specific gravity of 2.70, resists the corrosive effects of many chemicals, and has a malleability approaching that of gold. When alloyed with other metals, numerous properties are obtained that make these alloys useful over a wide range of applications.

Aluminum alloys are light in weight compared with steel, brass, nickel, or copper; can be fabricated by all common processes; are available in a wide range of sizes, shapes, and forms; resist corrosion; readily accept a wide range of surface finishes; have good electrical and thermal conductivities; and are highly reflective to both heat and light.

Characteristics of Aluminum and Aluminum Alloys.— Aluminum and its alloys lose part of their strength at elevated temperatures, although some alloys retain good strength at temperatures from 400 to 500 degrees F. At subzero temperatures, however, their strength increases without loss of ductility so that aluminum is a particularly useful metal for low-temperature applications.

When aluminum surfaces are exposed to the atmosphere, a thin invisible oxide skin forms immediately that protects the metal from further oxidation. This self-protecting characteristic gives aluminum its high resistance to corrosion. Unless exposed to some substance or condition that destroys this protective oxide coating, the metal remains protected against corrosion. Aluminum is highly resistant to weathering, even in industrial atmospheres. It is also corrosion resistant to many acids. Alkalis are among the few substances that attack the oxide skin and therefore are corrosive to aluminum. Although the metal can safely be used in the presence of certain mild alkalis with the aid of inhibitors, in general, direct contact with alkaline substances should be avoided. Direct contact with certain other metals should be avoided in the presence of an electrolyte; otherwise, galvanic corrosion of the aluminum may take place in the contact area. Where other metals must be fastened to aluminum, the use of a bituminous paint coating or insulating tape is recommended.

Aluminum is one of the two common metals having an electrical conductivity high enough for use as an electric conductor. The conductivity of electric-conductor (EC) grade is about 62 per cent that of the International Annealed Copper Standard. Because aluminum has less than one-third the specific gravity of copper, however, a pound of aluminum will go almost twice as far as a pound of copper when used as a conductor. Alloying lowers the conductivity somewhat so that wherever possible the EC grade is used in electric conductor applications. However, aluminum takes a set, which often results in loosening of screwed connectors, leading to arcing and fires. Special clamping designs are therefore required when aluminum is used for electrical wiring, especially in buildings.

Aluminum has nonsparking and nonmagnetic characteristics that make the metal useful for electrical shielding purposes such as in bus bar housings or enclosures for other electrical equipment and for use around inflammable or explosive substances.

Aluminum can be cast by any method known. It can be rolled to any desired thickness down to foil thinner than paper and in sheet form can be stamped, drawn, spun, or roll-formed. The metal also may be hammered or forged. Aluminum wire, drawn from rolled rod, may be stranded into cable of any desired size and type. The metal may be extruded into a variety of shapes. It may be turned, milled, bored, or otherwise machined in equipment often operating at their maximum speeds. Aluminum rod and bar may readily be employed in the high-speed manufacture of parts made on automatic screw-machine.

Almost any method of joining is applicable to aluminum—riveting, welding, or brazing. A wide variety of mechanical aluminum fasteners simplifies the assembly of many products. Resin bonding of aluminum parts has been successfully employed, particularly in aircraft components.

For the majority of applications, aluminum needs no protective coating. Mechanical finishes such as polishing, sandblasting, or wire brushing meet the majority of needs. When

Copyright 2004, Industrial Press, Inc., New York, NY

additional protection is desired, chemical, electrochemical, and paint finishes are all used. Vitreous enamels have been developed for aluminum, and the metal may also be electroplated.

Temper Designations for Aluminum Alloys.— The temper designation system adopted by the Aluminum Association and used in industry pertains to all forms of wrought and cast aluminum and aluminum alloys except ingot. It is based on the sequences of basic treatments used to produce the various tempers. The temper designation follows the alloy designation, being separated by a dash.

Basic temper designations consist of letters. Subdivisions of the basic tempers, where required, are indicated by one or more digits following the letter. These digits designate specific sequences of basic treatments, but only operations recognized as significantly influencing the characteristics of the product are indicated. Should some other variation of the same sequence of basic operations be applied to the same alloy, resulting in different characteristics, then additional digits are added.

The basic temper designations and subdivisions are as follows:

–F, as fabricated: Applies to products that acquire some temper from shaping processes not having special control over the amount of strain-hardening or thermal treatment. For wrought products, there are no mechanical property limits.

–O, annealed, recrystallized (wrought products only): Applies to the softest temper of wrought products.

–H, strain-hardened (wrought products only): Applies to products that have their strength increased by strain-hardening with or without supplementary thermal treatments to produce partial softening.

The –H is always followed by two or more digits. The first digit indicates the specific combination of basic operations, as follows:

–H1, strain-hardened only: Applies to products that are strain-hardened to obtain the desired mechanical properties without supplementary thermal treatment. The number following this designation indicates the degree of strain-hardening.

–H2, strain-hardened and then partially annealed: Applies to products that are strain-hardened more than the desired final amount and then reduced in strength to the desired level by partial annealing. For alloys that age-soften at room temperature, the –H2 tempers have approximately the same ultimate strength as the corresponding –H3 tempers. For other alloys, the –H2 tempers have approximately the same ultimate strengths as the corresponding –H1 tempers and slightly higher elongations.The number following this designation indicates the degree of strain-hardening remaining after the product has been partially annealed.

–H3, strain-hardened and then stabililized: Applies to products which are strain-hardened and then stabilized by a low-temperature heating to slightly lower their strength and increase ductility. This designation applies only to the magnesium-containing alloys that, unless stabilized, gradually age-soften at room temperature.The number following this designation indicates the degree of strain-hardening remaining after the product has been strain-hardened a specific amount and then stabilized.

The second digit following the designations –H1, –H2, and –H3 indicates the final degree of strain-hardening. Numeral 8 has been assigned to indicate tempers having a final degree of strain-hardening equivalent to that resulting from approximately 75 per cent reduction of area. Tempers between –O (annealed) and 8 (full hard) are designated by numerals 1 through 7. Material having an ultimate strength about midway between that of the –O temper and that of the 8 temper is designated by the numeral 4 (half hard); between –O and 4 by the numeral 2 (quarter hard); and between 4 and 8 by the numeral 6 (three-quarter hard). (*Note:* For two-digit –H tempers whose second figure is odd, the standard limits for ultimate strength are exactly midway between those for the adjacent two-digit –H tempers whose second figures are even.) Numeral 9 designates extra-hard tempers.

Copyright 2004, Industrial Press, Inc., New York, NY

The third digit, when used, indicates a variation of a two-digit –H temper, and is used when the degree of control of temper or the mechanical properties are different from but close to those for the two-digit –H temper designation to which it is added. (*Note:* The minimum ultimate strength of a three-digit –H temper is at least as close to that of the corresponding two-digit –H temper as it is to the adjacent two-digit –H tempers.) Numerals 1 through 9 may be arbitrarily assigned and registered with the Aluminum Association for an alloy and product to indicate a specific degree of control of temper or specific mechanical property limits. Zero has been assigned to indicate degrees of control of temper or mechanical property limits negotiated between the manufacturer and purchaser that are not used widely enough to justify registration with the Aluminum Association.

The following three-digit –H temper designations have been assigned for wrought products in all alloys:

–H111: Applies to products that are strain-hardened less than the amount required for a controlled H11 temper.

–H112: Applies to products that acquire some temper from shaping processes not having special control over the amount of strain-hardening or thermal treatment, but for which there are mechanical property limits, or mechanical property testing is required.

The following three-digit H temper designations have been assigned for wrought products in alloys containing more than a normal 4 per cent magnesium.

–H311: Applies to products that are strain-hardened less than the amount required for a controlled H31 temper.

–H321: Applies to products that are strain-hardened less than the amount required for a controlled H32 temper.

–H323: Applies to products that are specially fabricated to have acceptable resistance to stress-corrosion cracking.

–H343: Applies to products that are specially fabricated to have acceptable resistance to stress-corrosion cracking.

The following three-digit –H temper designations have been assigned for

Patterned or Embossed Sheet	Fabricated Form
–H114	–O temper
–H124, –H224, –H324	–H11, –H21, –H31 temper, respectively
–H134, –H234, –H334	–H12, –H22, –H32 temper, respectively
–H144, –H244, –H344	–H13, –H23, –H33 temper, respectively
–H154, –H254, –H354	–H14, –H24, –H34 temper, respectively
–H164, –H264, –H364	–H15, –H25, –H35 temper, respectively
–H174, –H274, –H374	–H16, –H26, –H36 temper, respectively
–H184, –H284, –H384	–H17, –H27, –H37 temper, respectively
–H194, –H294, –H394	–H18, –H28, –H38 temper, respectively
–H195, –H395	–H19, –H39 temper, respectively

–W, solution heat-treated: An unstable temper applicable only to alloys that spontaneously age at room temperature after solution heat treatment. This designation is specific only when the period of natural aging is indicated.

–T, thermally treated to produce stable tempers other than –F, –O, or –H: Applies to products that are thermally treated, with or without supplementary strain-hardening, to produce stable tempers.The –T is always followed by one or more digits. Numerals 2 through 10 have been assigned to indicate specific sequences of basic treatments, as follows:

–T1, naturally aged to a substantially stable condition: Applies to products for which the rate of cooling from an elevated temperature-shaping process, such as casting or extrusion, is such that their strength is increased by room-temperature aging.

Copyright 2004, Industrial Press, Inc., New York, NY

–T2, annealed (cast products only): Designates a type of annealing treatment used to improve ductility and increase dimensional stability of castings.

–T3, solution heat-treated and then cold-worked: Applies to products that are cold-worked to improve strength, or in which the effect of cold work in flattening or straightening is recognized in applicable specifications.

–T4, solution heat-treated and naturally aged to a substantially stable condition: Applies to products that are not cold-worked after solution heat treatment, or in which the effect of cold work in flattening or straightening may not be recognized in applicable specifications.

–T5, artificially aged only: Applies to products that are artificially aged after an elevated-temperature rapid-cool fabrication process, such as casting or extrusion, to improve mechanical properties or dimensional stability, or both.

–T6, solution heat-treated and then artificially aged: Applies to products that are not cold-worked after solution heat-treatment, or in which the effect of cold work in flattening or straightening may not be recognized in applicable specifications.

–T7, solution heat-treated and then stabilized: Applies to products that are stabilized to carry them beyond the point of maximum hardness, providing control of growth or residual stress or both.

–T8, solution heat-treated, cold-worked, and then artificially aged: Applies to products that are cold-worked to improve strength, or in which the effect of cold work in flattening or straightening is recognized in applicable specifications.

–T9, solution heat-treated, artificially aged, and then cold-worked: Applies to products that are cold-worked to improve strength.

–T10, artificially aged and then cold-worked: Applies to products that are artificially aged after an elevated-temperature rapid-cool fabrication process, such as casting or extrusion, and then cold-worked to improve strength.

Additional digits may be added to designations –T1 through –T10 to indicate a variation in treatment that significantly alters the characteristics of the product. These may be arbitrarily assigned and registered with The Aluminum Association for an alloy and product to indicate a specific treatment or specific mechanical property limits.

These additional digits have been assigned for wrought products in all alloys:

–T__51, stress-relieved by stretching: Applies to products that are stress-relieved by stretching the following amounts after solution heat-treatment:

Plate	1½ to 3 per cent permanent set
Rod, Bar and Shapes	1 to 3 per cent permanent set
Drawn tube	0.5 to 3 per cent permanent set

Applies directly to plate and rolled or cold-finished rod and bar.

These products receive no further straightening after stretching.

Applies to extruded rod and bar shapes and tube when designated as follows:

–T__510 : Products that receive no further straightening after stretching.

–T__511: Products that receive minor straightening after stretching to comply with standard tolerances.

–T__52, stress-relieved by compressing: Applies to products that are stress-relieved by compressing after solution heat-treatment, to produce a nominal permanent set of 2½ per cent.

–T__54, stress-relieved by combined stretching and compressing: Applies to die forgings that are stress relieved by restriking cold in the finish die.

The following two-digit –T temper designations have been assigned for wrought products in all alloys:

Copyright 2004, Industrial Press, Inc., New York, NY

–T42: Applies to products solution heat-treated and naturally aged that attain mechanical properties different from those of the –T4 temper.

–T62: Applies to products solution heat-treated and artificially aged that attain mechanical properties different from those of the –T6 temper.

Aluminum Alloy Designation Systems.— Aluminum casting alloys are listed in many specifications of various standardizing agencies. The numbering systems used by each differ and are not always correlatable. Casting alloys are available from producers who use a commercial numbering system and this numbering system is the one used in the tables of aluminum casting alloys given in this section.

Table 6a lists the nominal composition of commonly used aluminum casting alloys, and Tables 6b and 6c list the typical tensile properties of separately cast bars.

Table 6a. Nominal Compositions (in per cent) of Common Aluminum Casting Alloys (AA/ANSI)

Alloy	Product[a]	Si	Fe	Cu	Mn	Mg	Cr	Ni	Zn	Ti	Others	
											Each	Total
201.0	S	0.10	0.15	4.0–5.2	0.20–0.50	0.15–0.55	…	…	…	0.15–0.35	0.05[b]	0.10
204.0	S&P	0.20	0.35	4.2–5.0	0.10	0.15–0.35	…	0.05	0.10	0.15–0.30	0.05[c]	0.15
208.0	S&P	2.5–3.5	1.2	3.5–4.5	0.50	0.10	…	0.35	1.0	0.25	…	0.50
222.0	S&P	2.0	1.5	9.2–10.7	0.50	0.15–0.35	…	0.50	0.8	0.25	…	0.35
242.0	S&P	0.7	1.0	3.5–4.5	0.35	1.2–1.8	0.25	1.7–2.3	0.35	0.25	0.05	0.15
295.0	S	0.7–1.5	1.0	4.0–5.0	0.35	0.03	…	…	0.35	0.25	0.05	0.15
308.0	P	5.0–6.0	1.0	4.0–5.0	0.50	0.10	…	…	1.0	0.25	…	0.50
319.0	S&P	5.5–6.5	1.0	3.0–4.0	0.50	0.10	…	0.35	1.0	0.25	…	0.50
328.0	S	7.5–8.5	1.0	1.0–2.0	0.20–0.6	0.20–0.6	0.35	0.25	1.5	0.25	…	0.50
332.0	P	8.5–10.5	1.2	2.0–4.0	0.50	0.50–1.5	…	0.50	1.0	0.25	…	0.50
333.0	P	8.0–10.0	1.0	3.0–4.0	0.50	0.05–0.50	…	0.50	1.0	0.25	…	0.50
336.0	P	11.0–13.0	1.2	0.50–1.5	0.35	0.7–1.3	…	2.0–3.0	0.35	0.25	0.05	…
355.0	S&P	4.5–5.5	0.6[d]	1.0–1.5	0.50[d]	0.40–0.6	0.25	…	0.35	0.25	0.05	0.15
C355.0	S&P	4.5–5.5	0.20	1.0–1.5	0.10	0.40–0.6	…	…	0.10	0.20	0.05	0.15
356.0	S&P	6.5–7.5	0.6[d]	0.25	0.35[d]	0.20–0.45	…	…	0.35	0.25	0.05	0.15
356.0	S&P	6.5–7.5	0.20	0.20	0.10	0.25–0.45	…	…	0.10	0.20	0.05	0.15
357.0	S&P	6.5–7.5	0.15	0.05	0.03	0.45–0.6	…	…	0.05	0.20	0.05	0.15
A357.0	S&P	6.5–7.5	0.20	0.20	0.10	0.40–0.7	…	…	0.10	0.04–0.20	0.05[e]	0.15
443.0	S&P	4.5–6.0	0.8	0.6	0.50	0.05	0.25	…	0.50	0.25	…	0.35
B443.0	S&P	4.5–6.0	0.8	0.15	0.35	0.05	…	…	0.35	0.25	0.05	0.15
A444.0	P	6.5–7.5	0.20	0.10	0.10	0.05	…	…	0.10	0.20	0.05	0.15
512.0	S	1.4–2.2	0.6	0.35	0.8	3.5–4.5	0.25	…	0.35	0.25	0.05	0.15
513.0	P	0.30	0.40	0.10	0.30	3.5–4.5	…	…	1.4–2.2	0.20	0.05	0.15
514.0	S	0.35	0.50	0.15	0.35	3.5–4.5	…	…	0.15	0.25	0.05	0.15
520.0	S	0.25	0.30	0.25	0.15	9.5–10.6	…	…	0.15	0.25	0.05	0.15
705.0	S&P	0.20	0.8	0.20	0.40–0.6	1.4–1.8	0.20–0.40	…	2.7–3.3	0.25	0.05	0.15
707.0	S&P	0.20	0.8	0.20	0.40–0.6	1.8–2.4	0.20–0.40	…	4.0–4.5	0.25	0.05	0.15
710.0	S	0.15	0.50	0.35–0.65	0.05	0.6–0.8	…	…	6.0–7.0	0.25	0.05	0.15
711.0	P	0.30	0.7–1.4	0.35–0.65	0.05	0.25–0.45	…	…	6.0–7.0	0.20	0.05	0.15
712.0	S	0.30	0.50	0.25	0.10	0.50–0.65	0.40–0.6	…	5.0–6.5	0.15–0.25	0.05	0.20
850.0	S&P	0.7	0.7	0.7–1.3	0.10	0.10	…	0.7–1.3	…	0.20	__[f]	0.30
851.0	S&P	2.0–3.0	0.7	0.7–1.3	0.10	0.10	…	0.3–0.7	…	0.20	__[f]	0.30

[a] S = sand cast; P = permanent mold cast. The sum of those "Others" metallic elements 0.010 per cent or more each, expressed to the second decimal before determining the sum. *Source: Standards for Aluminum Sand and Permanent Mold Castings*, courtesy of the Aluminum Association.

[b] Also contains 0.40–1.0 per cent silver.

[c] Also contains 0.05 max. per cent tin.

[d] If iron exceeds 0.45 per cent, manganese content should not be less than one-half the iron content.

[e] Also contains 0.04-0.07 per cent beryllium.

[f] Also contains 5.5–7.0 per cent tin.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6b. Mechanical Property Limits for Separately Cast Test Bars of Commonly Used Aluminum Sand Casting Alloys

Alloy	Temper[a]	Minimum Properties			Typical Brinell Hardness (500 kgf load, 10-mm ball)
		Tensile Strength (ksi)		Elongation In 2 inches (%)	
		Ultimate	Yield		
201.0	T7	60.0	50.0	3.0	110–140
204.0	T4	45.0	28.0	6.0	…
208.0	F	19.0	12.0	1.5	40–70
222.0	O	23.0	…	…	65–95
222.0	T61	30.0	…	…	100–130
242.0	O	23.0	…	…	55–85
242.0	T571	29.0	…	…	70–100
242.0	T61	32.0	20.0	…	90–120
242.0	T77	24.0	13.0	1.0	60–90
295.0	T4	29.0	13.0	6.0	45–75
295.0	T6	32.0	20.0	3.0	60–90
295.0	T62	36.0	28.0	…	80–110
295.0	T7	29.0	16.0	3.0	55–85
319.0	F	23.0	13.0	1.5	55–85
319.0	T5	25.0	…	…	65–95
319.0	T6	31.0	20.0	1.5	65–95
328.0	F	25.0	14.0	1.0	45–75
328.0	T6	34.0	21.0	1.0	65–95
354.0	[b]	…	…	…	…
355.0	T51	25.0	18.0	…	50–80
355.0	T6	32.0	20.0	2.0	70–105
355.0	T7	35.0	…	…	70–100
355.0	T71	30.0	22.0	…	60–95
C355.0	T6	36.0	25.0	2.5	75–105
356.0	F	19.0	…	2.0	40–70
356.0	T51	23.0	16.0	…	45–75
356.0	T6	30.0	20.0	3.0	55–90
356.0	T7	31.0	29.0	…	60–90
356.0	T71	25.0	18.0	3.0	45–75
A356.0	T6	34.0	24.0	3.5	70–105
443.0	F	17.0	7.0	3.0	25–55
B443.0	F	17.0	6.0	3.0	25–55
512.0	F	17.0	10.0	…	35–65
514.0	F	22.0	9.0	6.0	35–65
520.0	T4[c]	42.0	22.0	12.0	60–90
535.0	F or T5	35.0	18.0	9.0	60–90
705.0	F or T5	30.0	17.0	5.0	50–80
707.0	T5	33.0	22.0	2.0	70–100
707.0	T7	37.0	30.0	1.0	65–95
710.0	F or T5	32.0	20.0	2.0	60–90
712.0	F or T5	34.0	25.0	4.0	60–90
713.0	F or T5	32.0	22.0	3.0	60–90
771.0	T5	42.0	38.0	1.5	85–115
771.0	T51	32.0	27.0	3.0	70–100
771.0	T52	36.0	30.0	1.5	70–100
771.0	T53	36.0	27.0	1.5	…
771.0	T6	42.0	35.0	5.0	75–105
771.0	T71	48.0	45.0	2.0	105–135
850.0	T5	16.0	…	5.0	30–60
851.0	T5	17.0	…	3.0	30–60
852.0	T5	24.0	18.0	…	45–75

Source: Standards for Aluminum Sand and Permanent Mold Castings, courtesy of the Aluminum Association.

[a] F indicates "as cast" condition.

[b] Mechanical properties for these alloys depend on the casting process. For further information consult the individual foundries.

[c] The T4 temper of Alloy 520.0 is unstable; significant room temperature aging occurs within life expectancy of most castings. Elongation may decrease by as much as 80 percent.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6c. Mechanical Property Limits for Separately Cast Test Bars of Commonly Used Aluminum Permanent Mold Casting Alloys

Alloy	Temper[a]	Minimum Properties			Typical Brinell Hardness (500 kgf load, 10-mm ball)
		Tensile Strength (ksi)		Elongation In 2 inches (%)	
		Ultimate	Yield		
204.0	T4	48.0	29.0	8.0	…
208.0	T4	33.0	15.0	4.5	60–90
208.0	T6	35.0	22.0	2.0	75–105
208.0	T7	33.0	16.0	3.0	65–95
222.0	T551	30.0	…	…	100–130
222.0	T65	40.0	…	…	125–155
242.0	T571	34.0	…	…	90–120
242.0	T61	40.0	…	…	95–125
296.0	T6	35.0	…	2.0	75–105
308.0	F	24.0	…	…	55–85
319.0	F	28.0	14.0	1.5	70–100
319.0	T6	34.0	…	2.0	75–105
332.0	T5	31.0	…	…	90–120
333.0	F	28.0	…	…	65–100
333.0	T5	30.0	…	…	70–105
333.0	T6	35.0	…	…	85–115
333.0	T7	31.0	…	…	75–105
336.0	T551	31.0	…	…	90–120
336.0	T65	40.0	…	…	110–140
354.0	T61	48.0	37.0	3.0	…
354.0	T62	52.0	42.0	2.0	…
355.0	T51	27.0	…	…	60–90
355.0	T6	37.0	…	1.5	75–105
355.0	T62	42.0	…	…	90–120
355.0	T7	36.0	…	…	70–100
355.0	T71	34.0	27.0	…	65–95
C355.0	T61	40.0	30.0	3.0	75–105
356.0	F	21.0	…	3.0	40–70
356.0	T51	25.0	…	…	55–85
356.0	T6	33.0	22.0	3.0	65–95
356.0	T7	25.0	…	3.0	60–90
356.0	T71	25.0	…	3.0	60–90
A356.0	T61	37.0	26.0	5.0	70–100
357.0	T6	45.0	…	3.0	75–105
A357.0	T61	45.0	36.0	3.0	85–115
359.0	T61	45.0	34.0	4.0	75–105
359.0	T62	47.0	38.0	3.0	85–115
443.0	F	21.0	7.0	2.0	30–60
B443.0	F	21.0	6.0	2.5	30–60
A444.0	T4	20.0	…	20.0	…
513.0	F	22.0	12.0	2.5	45–75
535.0	F	35.0	18.0	8.0	60–90
705.0	T5	37.0	17.0	10.0	55–85
707.0	T7	45.0	35.0	3.0	80–110
711.0	T1	28.0	18.0	7.0	55–85
713.0	T5	32.0	22.0	4.0	60–90
850.0	T5	18.0	…	8.0	30–60
851.0	T5	17.0	…	3.0	30–60
851.0	T6	18.0	…	8.0	…
852.0	T5	27.0	…	3.0	55–85

Source: Standards for Aluminum Sand and Permanent Mold Castings. Courtesy of the Aluminum Association.

[a] F indicates "as cast" condition.

Copyright 2004, Industrial Press, Inc., New York, NY

A system of four-digit numerical designations for wrought aluminum and wrought aluminum alloys was adopted by the Aluminum Association in 1954. This system is used by the commercial producers and is similar to the one used by the SAE; the difference being the addition of two prefix letters.

The first digit of the designation identifies the alloy type: 1) indicating an aluminum of 99.00 per cent or greater purity; 2) copper; 3) manganese; 4) silicon; 5) magnesium; 6) magnesium and silicon; 7) zinc; 8) some element other than those aforementioned; and 9) unused (not assigned at present).

If the second digit in the designation is zero, it indicates that there is no special control on individual impurities; integers 1 through 9 indicate special control on one or more individual impurities.

In the 1000 series group for aluminum of 99.00 per cent or greater purity, the last two of the four digits indicate to the nearest hundredth the amount of aluminum above 99.00 per cent. Thus designation 1030 indicates 99.30 per cent minimum aluminum. In the 2000 to 8000 series groups the last two of the four digits have no significance but are used to identify different alloys in the group. At the time of adoption of this designation system most of the existing commercial designation numbers were used for these last two digits, as for example, 14S became 2014, 3S became 3003, and 75S became 7075. When new alloys are developed and are commercially used these last two digits are assigned consecutively beginning with –01, skipping any numbers previously assigned at the time of initial adoption.

Experimental alloys are also designated in accordance with this system but they are indicated by the prefix X. The prefix is dropped upon standardization.

Table 7a shows the product forms and nominal compositions of common wrought aluminum alloys, and Table 7b lists typical mechanical properties of wrought aluminum alloys.

Table 7a. Nominal Compositions of Common Wrought Aluminum Alloys

	Alloying Elements — Aluminum and Normal Impurities Constitute Remainder												
Alloy	Si	Cu	Mn	Mg	Cr	Ni	Zn	Ti	Pb	Bi	V	Z	Fe
1050	…	…	99.50 per cent minimum aluminum				…	…	…	…	…	…	…
1060	…	…	99.60 per cent minimum aluminum				…	…	…	…	…	…	…
1100	…	0.12	99.00 per cent minimum aluminum				…	…	…	…	…	…	…
1145	…	…	99.45 per cent minimum aluminum				…	…	…	…	…	…	…
1175	…	…	99.75 per cent minimum aluminum				…	…	…	…	…	…	…
1200	…	…	99.00 per cent minimum aluminum				…	…	…	…	…	…	…
1230	…	…	99.30 per cent minimum aluminum				…	…	…	…	…	…	…
1235	…	…	99.35 per cent minimum aluminum				…	…	…	…	…	…	…
1345	…	…	99.45 per cent minimum aluminum				…	…	…	…	…	…	…
1350[a]	…	…	99.50 per cent minimum aluminum				…	…	…	…	…	…	…
2011	…	5.5	…	…	…	…	…	…	0.4	0.4	…	…	…
2014	0.8	4.4	0.8	0.50	…	…	…	…	…	…	…	…	…
2017	0.50	4.0	0.7	0.6	…	…	…	…	…	…	…	…	…
2018	…	4.0	…	0.7	…	2.0	…	…	…	…	…	…	…
2024	…	4.4	0.6	1.5	…	…	…	…	…	…	…	…	…
2025	0.8	4.4	0.8	…	…	…	…	…	…	…	…	…	…
2036	…	2.6	0.25	0.45	…	…	…	…	…	…	…	…	…
2117	…	2.6	…	0.35	…	…	…	…	…	…	…	…	…
2124	…	4.4	0.6	1.5	…	…	…	…	…	…	…	…	…
2218	…	4.0	…	1.5	…	2.0	…	…	…	…	…	…	…
2219	…	6.3	0.30	…	…	…	…	0.06	…	…	0.10	0.18	…
2319	…	6.3	0.30	…	…	…	…	0.15	…	…	0.10	0.18	…
2618	0.18	2.3	…	1.6	…	1.0	…	0.07	…	…	…	…	1.1

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7a. ***(Continued)*** **Nominal Compositions of Common Wrought Aluminum Alloys**

	Alloying Elements — Aluminum and Normal Impurities Constitute Remainder												
Alloy	Si	Cu	Mn	Mg	Cr	Ni	Zn	Ti	Pb	Bi	V	Z	Fe
3003	…	0.12	1.2	…	…	…	…	…	…	…	…	…	…
3004	…	…	1.2	1.0	…	…	…	…	…	…	…	…	…
3005	…	…	1.2	0.40	…	…	…	…	…	…	…	…	…
4032	12.2	0.9	…	1.0	…	0.9	…	…	…	…	…	…	…
4043	5.2	…	…	…	…	…	…	…	…	…	…	…	…
4045	10.0	…	…	…	…	…	…	…	…	…	…	…	…
4047	12.0	…	…	…	…	…	…	…	…	…	…	…	…
4145	10.0	4.0	…	…	…	…	…	…	…	…	…	…	…
5005	…	…	…	0.8	…	…	…	…	…	…	…	…	…
5050	…	…	…	1.4	…	…	…	…	…	…	…	…	…
5052	…	…	…	2.5	0.25	…	…	…	…	…	…	…	…
5056	…	…	0.12	5.0	0.12	…	…	…	…	…	…	…	…
5083	…	…	0.7	4.4	0.15	…	…	…	…	…	…	…	…
5086	…	…	0.45	4.0	0.15	…	…	…	…	…	…	…	…
5183	…	…	0.8	4.8	0.15	…	…	…	…	…	…	…	…
5252	…	…	…	2.5	…	…	…	…	…	…	…	…	…
5254	…	…	…	3.5	0.25	…	…	…	…	…	…	…	…
5356	…	…	0.12	5.0	0.12	…	…	0.13	…	…	…	…	…
5456	…	…	0.8	5.1	0.12	…	…	…	…	…	…	…	…
5457	…	…	0.30	1.0	…	…	…	…	…	…	…	…	…
5554	…	…	0.8	2.7	0.12	…	…	0.12	…	…	…	…	…
5556	…	…	0.8	5.1	0.12	…	…	0.12	…	…	…	…	…
5652	…	…	…	2.5	0.25	…	…	…	…	…	…	…	…
5654	…	…	…	3.5	0.25	…	…	0.10	…	…	…	…	…
6003	0.7	…	…	1.2	…	…	…	…	…	…	…	…	…
6005	0.8	…	…	0.50	…	…	…	…	…	…	…	…	…
6053	0.7	…	…	1.2	0.25	…	…	…	…	…	…	…	…
6061	0.6	0.28	…	1.0	0.20	…	…	…	…	…	…	…	…
6066	1.4	1.0	0.8	1.1	…	…	…	…	…	…	…	…	…
6070	1.4	0.28	0.7	0.8	…	…	…	…	…	…	…	…	…
6101	0.50	…	…	0.6	…	…	…	…	…	…	…	…	…
6105	0.8	…	…	0.62	…	…	…	…	…	…	…	…	…
6151	0.9	…	…	0.6	0.25	…	…	…	…	…	…	…	…
6201	0.7	…	…	0.8	…	…	…	…	…	…	…	…	…
6253	0.7	…	…	1.2	0.25	…	2.0	…	…	…	…	…	…
6262	0.6	0.28	…	1.0	0.09	…	…	…	0.6	0.6	…	…	…
6351	1.0	…	0.6	0.6	…	…	…	…	…	…	…	…	…
6463	0.40	…	…	0.7	…	…	…	…	…	…	…	…	…
7005	…	…	0.45	1.4	0.13	…	4.5	0.04	…	…	…	0.14	…
7008	…	…	…	1.0	0.18	…	5.0	…	…	…	…	…	…
7049	…	1.6	…	2.4	0.16	…	7.7	…	…	…	…	…	…
7050	…	2.3	…	2.2	6.2	…	…	…	…	…	…	0.12	…
7072	…	…	…	…	…	…	1.0	…	…	…	…	…	…
7075	…	1.6	…	2.5	0.23	…	5.6	…	…	…	…	…	…
7108	…	…	…	1.0	…	…	5.0	…	…	…	…	0.18	…
7178	…	2.0	…	2.8	0.23	…	6.8	…	…	…	…	…	…
8017	…	0.15	…	0.03	…	…	…	…	…	…	…	…	0.7
8030[b]	…	0.22	…	…	…	…	…	…	…	…	…	…	…
8177	…	…	…	0.08	…	…	…	…	…	…	…	…	0.35

[a] Formerly designated EC.
[b] Boron 0.02 per cent.
Source: Aluminum Standards and Data. Courtesy of the Aluminum Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. Typical Mechanical Properties of Wrought Aluminum Alloys

Alloy and Temper	Tension				Brinell Hardness Number 500 kg load, 10-mm ball	Ultimate Shearing Strength (ksi)	Endurance Limit[a] (ksi)
	Strength (ksi)		Elongation in 2 inches (%)				
	Ulti-mate	Yield	1/16-inch Thick Specimen	1/2-inch Diameter Specimen			
1060-O	10	4	43	…	19	7	3
1060-H12	12	11	16	…	23	8	4
1060-H14	14	13	12	…	26	9	5
1060-H16	16	15	8	…	30	10	6.5
1060-H18	19	18	6	…	35	11	6.5
1100-O	13	5	35	45	23	9	5
1100-H12	16	15	12	25	28	10	6
1100-H14	18	17	9	20	32	11	7
1100-H16	21	20	6	17	38	12	9
1100-H18	24	22	5	15	44	13	9
1350-O	12	4	…	…[b]	…	8	…
1350-H12	14	12	…	…	…	9	…
1350-H14	16	14	…	…	…	10	…
1350-H16	18	16	…	…	…	11	…
1350-H19	27	24	…	…[c]	…	15	7
2011-T3	55	43	…	15	95	32	18
2011-T8	59	45	…	12	100	35	18
2014-O	27	14	…	18	45	18	13
2014-T4, T451	62	42	…	20	105	38	20
2014-T6, T651	70	60	…	13	135	42	18
Alclad 2014-O	25	10	21	…	…	18	…
Alclad 2014-T3	63	40	20	…	…	37	…
Alclad 2014-T4, T451	61	37	22	…	…	37	…
Alclad 2014-T6, T651	68	60	10	…	…	41	…
2017-O	26	10	…	22	45	18	13
2017-T4, T451	62	40	…	22	105	38	18
2018-T61	61	46	…	12	120	39	17
2024-O	27	11	20	22	47	18	13
2024-T3	70	50	18	…	120	41	20
2024-T4, T351	68	47	20	19	120	41	20
2024-T361[d]	72	57	13	…	130	42	18
Alclad 2024-O	26	11	20	…	…	18	…
Alclad 2024-T3	65	45	18	…	…	40	…
Alclad 2024-T4, T351	64	42	19	…	…	40	…
Alclad 2024-T361[d]	67	53	11	…	…	41	…
Alclad 2024-T81, T851	65	60	6	…	…	40	…
Alclad 2024-T861[d]	70	66	6	…	…	42	…
2025-T6	58	37	…	19	110	35	18
2036-T4	49	28	24	…	…	…	18[e]
2117-T4	43	24	…	27	70	28	14
2218-T72	48	37	…	11	95	30	…
2219-O	25	11	18	…	…	…	…
2219-T42	52	27	20	…	…	…	…
2219-T31, T351	52	36	17	…	…	…	…
2219-T37	57	46	11	…	…	…	…
2219-T62	60	42	10	…	…	…	15
2219-T81, T851	66	51	10	…	…	…	15
2219-T87	69	57	10	…	…	…	15
3003-O	16	6	30	40	28	11	7

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. ***(Continued)*** **Typical Mechanical Properties of Wrought Aluminum Alloys**

Alloy and Temper	Tension				Brinell Hardness Number 500 kg load, 10-mm ball	Ultimate Shearing Strength (ksi)	Endurance Limit[a] (ksi)
	Strength (ksi)		Elongation in 2 inches (%)				
	Ulti-mate	Yield	1/16-inch Thick Specimen	1/2-inch Diameter Specimen			
3003-H12	19	18	10	20	35	12	8
3003-H14	22	21	8	16	40	14	9
3003-H16	26	25	5	14	47	15	10
3003-H18	29	27	4	10	55	16	10
Alclad 3003-O	16	6	30	40	…	11	…
Alclad 3003-H12	19	18	10	20	…	12	…
Alclad 3003-H14	22	21	8	16	…	14	…
Alclad 3003-H16	26	25	5	14	…	15	…
Alclad 3003-H18	29	27	4	10	…	16	…
3004-O	26	10	20	25	45	16	14
3004-H32	31	25	10	17	52	17	15
3004-H34	35	29	9	12	63	18	15
3004-H36	38	33	5	9	70	20	16
3004-H38	41	36	5	6	77	21	16
Alclad 3004-O	26	10	20	25	…	16	…
Alclad 3004-H32	31	25	10	17	…	17	…
Alclad 3004-H34	35	29	9	12	…	18	…
Alclad 3004-H36	38	33	5	9	…	20	…
Alclad 3004-H38	41	36	5	6	…	21	…
3105-O	17	8	24	…	…	12	…
3105-H12	22	19	7	…	…	14	…
3105-H14	25	22	5	…	…	15	…
3105-H16	28	25	4	…	…	16	…
3105-H18	31	28	3	…	…	17	…
3105-H25	26	23	8	…	…	15	…
4032-T6	55	46	…	9	120	38	16
5005-O	18	6	25	…	28	11	…
5005-H12	20	19	10	…	…	14	…
5005-H14	23	22	6	…	…	14	…
5005-H16	26	25	5	…	…	15	…
5005-H18	29	28	4	…	…	16	…
5005-H32	20	17	11	…	36	14	…
5005-H34	23	20	8	…	41	14	…
5005-H36	26	24	6	…	46	15	…
5005-H38	29	27	5	…	51	16	…
5050-O	21	8	24	…	36	15	12
5050-H32	25	21	9	…	46	17	13
5050-H34	28	24	8	…	53	18	13
5050-H36	30	26	7	…	58	19	14
5050-H38	32	29	6	…	63	20	14
5052-O	28	13	25	30	47	18	16
5052-H32	33	28	12	18	60	20	17
5052-H34	38	31	10	14	68	21	18
5052-H36	40	35	8	10	73	23	19
5052-H38	42	37	7	8	77	24	20
5056-O	42	22	…	35	65	26	20
5056-H18	63	59	…	10	105	34	22
5056-H38	60	50	…	15	100	32	22
5083-O	42	21	…	22	…	25	…
5083-H321, H116	46	33	…	16	…	…	23

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. ***(Continued)*** **Typical Mechanical Properties of Wrought Aluminum Alloys**

Alloy and Temper	Tension				Brinell Hardness Number 500 kg load, 10-mm ball	Ultimate Shearing Strength (ksi)	Endurance Limit[a] (ksi)
	Strength (ksi)		Elongation in 2 inches (%)				
	Ulti-mate	Yield	1/16-inch Thick Specimen	1/2-inch Diameter Specimen			
5086-O	38	17	22	…	…	23	…
5086-H32, H116	42	30	12	…	…	…	…
5086-H34	47	37	10	…	…	27	…
5086-H112	39	19	14	…	…	…	…
5154-O	35	17	27	…	58	22	17
5154-H32	39	30	15	…	67	22	18
5154-H34	42	33	13	…	73	24	19
5154-H36	45	36	12	…	78	26	20
5154-H38	48	39	10	…	80	28	21
5154-H112	35	17	25	…	63	…	17
5252-H25	34	25	11	…	68	21	…
5252-H38, H28	41	35	5	…	75	23	…
5254-O	35	17	27	…	58	22	17
5254-H32	39	30	15	…	67	22	18
5254-H34	42	33	13	…	73	24	19
5254-H36	45	36	12	…	78	26	20
5254-H38	48	39	10	…	80	28	21
5254-H112	35	17	25	…	63	…	17
5454-O	36	17	22	…	62	23	…
5454-H32	40	30	10	…	73	24	…
5454-H34	44	35	10	…	81	26	…
5454-H111	38	26	14	…	70	23	…
5454-H112	36	18	18	…	62	23	…
5456-O	45	23	…	24	…	…	…
5456-H112	45	24	…	22	…	…	…
5456-H321, H116	51	37	…	16	90	30	…
5457-O	19	7	22	…	32	12	…
5457-H25	26	23	12	…	48	16	…
5457-H38, H28	30	27	6	…	55	18	…
5652-O	28	13	25	30	47	18	16
5652-H32	33	28	12	18	60	20	17
5652-H34	38	31	10	14	68	21	18
5652-H36	40	35	8	10	73	23	19
5652-H38	42	37	7	8	77	24	20
5657-H25	23	20	12	…	40	14	…
5657-H38, H28	28	24	7	…	50	15	…
6061-O	18	8	25	30	30	12	9
6061-T4, T451	35	21	22	25	65	24	14
6061-T6, T651	45	40	12	17	95	30	14
Alclad 6061-O	17	7	25	…	…	11	…
Alclad 6061-T4, T451	33	19	22	…	…	22	…
Alclad 6061-T6, T651	42	37	12	…	…	27	…
6063-O	13	7	…	…	25	10	8
6063-T1	22	13	20	…	42	14	9
6063-T4	25	13	22	…	…	…	…
6063-T5	27	21	12	…	60	17	10
6063-T6	35	31	12	…	73	22	10
6063-T83	37	35	9	…	82	22	…
6063-T831	30	27	10	…	70	18	…
6063-T832	42	39	12	…	95	27	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. ***(Continued)*** **Typical Mechanical Properties of Wrought Aluminum Alloys**

Alloy and Temper	Tension				Brinell Hardness Number 500 kg load, 10-mm ball	Ultimate Shearing Strength (ksi)	Endurance Limit[a] (ksi)
	Strength (ksi)		Elongation in 2 inches (%)				
	Ulti-mate	Yield	1/16-inch Thick Specimen	1/2-inch Diameter Specimen			
6066-O	22	12	…	18	43	14	…
6066-T4, T451	52	30	…	18	90	29	…
6066-T6, T651	57	52	…	12	120	34	16
6070-T6	55	51	10	…	…	34	14
6101-H111	14	11	…	…	…	…	…
6101-T6	32	28	15	…	71	20	…
6262-T9	58	55	…	10	120	35	13
6351-T4	36	22	20	…	…	…	…
6351-T6	45	41	14	…	95	29	13
6463-T1	22	13	20	…	42	14	10
6463-T5	27	21	12	…	60	17	10
6463-T6	35	31	12	…	74	22	10
7049-T73	75	65	…	12	135	44	…
7049-T7352	75	63	…	11	135	43	…
7050-T73510, T73511	72	63	…	12	…	…	…
7050-T7451[f]	76	68	…	11	…	44	…
7050-T7651	80	71	…	11	…	47	…
7075-O	33	15	17	16	60	22	…
7075-T6, T651	83	73	11	11	150	48	23
Alclad 7075-O	32	14	17	…	…	22	…
Alclad 7075-T6, T651	76	67	11	…	…	46	…
7178-O	33	15	15	16	…	…	…
7178-T6, T651	88	78	10	11	…	…	…
7178-T76, T7651	83	73	…	11	…	…	…
Alclad 7178-O	32	14	16	…	…	…	…
Alclad 7178-T6, T651	81	71	10	…	…	…	…
8176-H24	17	14	15	…	…	10	…

[a] Based on 500,000,000 cycles of completely reversed stress using the R. R. Moore type of machine and specimen.

[b] 1350-O wire should have an elongation of approximately 23 per cent in 10 inches.

[c] 1350-H19 wire should have an elongation of approximately 1.5 per cent in 10 inches.

[d] Tempers T361 and T861 were formerly designated T36 and T86, respectively.

[e] Based on 10^7 cycles using flexural type testing of sheet specimens.

[f] T7451, although not previously registered, has appeared in the literature and in some specifications as T73651.

The data given in this table are intended only as a basis for comparing alloys and tempers and should not be specified as engineering requirements or used for design purposes. The indicated typical mechanical properties for all except O temper material are higher than the specified minimum properties. For O temper products, typical ultimate and yield values are slightly lower than specified (maximum) values.

Source: Aluminum Standards and Data. Courtesy of the Aluminum Association.

Heat-treatability of Wrought Aluminum Alloys.— In high-purity form, aluminum is soft and ductile. Most commercial uses, however, require greater strength than pure aluminum affords. This extra strength is achieved in aluminum first by the addition of other elements to produce various alloys, which singly or in combination impart strength to the metal. Further strengthening is possible by means that classify the alloys roughly into two categories, non-heat-treatable and heat-treatable.

Non-heat-treatable alloys: The initial strength of alloys in this group depends upon the hardening effect of elements such as manganese, silicon, iron and magnesium, singly or in

Copyright 2004, Industrial Press, Inc., New York, NY

various combinations. The non-heat-treatable alloys are usually designated, therefore, in the 1000, 3000, 4000, or 5000 series. These alloys are work-hardenable, so further strengthening is made possible by various degrees of cold working, denoted by the "H" series of tempers. Alloys containing appreciable amounts of magnesium when supplied in strain-hardened tempers are usually given a final elevated-temperature treatment called *stabilizing* for property stability.

Heat-treatable alloys: The initial strength of alloys in this group is enhanced by the addition of alloying elements such as copper, magnesium, zinc, and silicon. These elements singly or in various combinations show increasing solid solubility in aluminum with increasing temperature, so it is possible to subject them to thermal treatments that will impart pronounced strengthening.

The first step, called *heat-treatment* or *solution heat-treatment,* is an elevated-temperature process designed to put the soluble element in solid solution. This step is followed by rapid quenching, usually in water, which momentarily "freezes" the structure and for a short time renders the alloy very workable. Some fabricators retain this more workable structure by storing the alloys at below freezing temperatures until they can be formed. At room or elevated temperatures the alloys are not stable after quenching, however, and precipitation of the constituents from the supersaturated solution begins. After a period of several days at room temperature, termed *aging* or *room-temperature precipitation,* the alloy is considerably stronger. Many alloys approach a stable condition at room temperature, but some alloys, particularly those containing magnesium and silicon or magnesium and zinc, continue to age-harden for long periods of time at room temperature.

Heating for a controlled time at slightly elevated temperatures provides even further strengthening and properties are stabilized. This process is called *artificial aging* or *precipitation hardening*. By application of the proper combination of solution heat-treatment, quenching, cold working and artificial aging, the highest strengths are obtained.

Clad Aluminum Alloys.— The heat-treatable alloys in which copper or zinc are major alloying constituents are less resistant to corrosive attack than the majority of non-heat-treatable alloys. To increase the corrosion resistance of these alloys in sheet and plate form they are often clad with high-purity aluminum, a low magnesium-silicon alloy, or an alloy containing 1 per cent zinc. The cladding, usually from 2½ to 5 per cent of the total thickness on each side, not only protects the composite due to its own inherently excellent corrosion resistance but also exerts a galvanic effect that further protects the core material.

Special composites may be obtained such as clad non-heat-treatable alloys for extra corrosion protection, for brazing purposes, or for special surface finishes. Some alloys in wire and tubular form are clad for similar reasons and on an experimental basis extrusions also have been clad.

Aluminum Alloys, Wrought, Sheet.— *Physical Properties:* In the form of sheets, the tensile strength varies from 35,000 for soft temper to 62,000 pounds per square inch for heat-treated sheets, and the elongation in 2 inches from 12 to 18 per cent. The yield strength of a heat-treated sheet is about 40,000 pounds per square inch minimum.

Characteristics of Principal Aluminum Alloy Series Groups.— *1000 series:* These alloys are characterized by high corrosion resistance, high thermal and electrical conductivity, low mechanical properties and good workability. Moderate increases in strength may be obtained by strain-hardening. Iron and silicon are the major impurities.

2000 series: Copper is the principal alloying element in this group. These alloys require solution heat-treatment to obtain optimum properties; in the heat-treated condition mechanical properties are similar to, and sometimes exceed, those of mild steel. In some instances artificial aging is employed to further increase the mechanical properties. This treatment materially increases yield strength, with attendant loss in elongation; its effect on tensile (ultimate) strength is not as great. The alloys in the 2000 series do not have as good corrosion resistance as most other aluminum alloys and under certain conditions they

Copyright 2004, Industrial Press, Inc., New York, NY

may be subject to intergranular corrosion. Therefore, these alloys in the form of sheet are usually clad with a high-purity alloy or a magnesium-silicon alloy of the 6000 series which provides galvanic protection to the core material and thus greatly increases resistance to corrosion. Alloy 2024 is perhaps the best known and most widely used aircraft alloy.

3000 series: Manganese is the major alloying element of alloys in this group, which are generally non-heat-treatable. Because only a limited percentage of manganese, up to about 1.5 per cent, can be effectively added to aluminum, it is used as a major element in only a few instances. One of these, however, is the popular 3003, used for moderate-strength applications requiring good workability.

4000 series: The major alloying element of this group is silicon, which can be added in sufficient quantities to cause substantial lowering of the melting point without producing brittleness in the resulting alloys. For these reasons aluminum-silicon alloys are used in welding wire and as brazing alloys where a lower melting point than that of the parent metal is required. Most alloys in this series are non-heat-treatable, but when used in welding heat-treatable alloys they will pick up some of the alloying constituents of the latter and so respond to heat-treatment to a limited extent. The alloys containing appreciable amounts of silicon become dark gray when anodic oxide finishes are applied, and hence are in demand for architectural applications.

5000 series: Magnesium is one of the most effective and widely used alloying elements for aluminum. When it is used as the major alloying element or with manganese, the result is a moderate to high strength non-heat-treatable alloy. Magnesium is considerably more effective than manganese as a hardener, about 0.8 per cent magnesium being equal to 1.25 per cent manganese, and it can be added in considerably higher quantities. Alloys in this series possess good welding characteristics and good resistance to corrosion in marine atmospheres. However, certain limitations should be placed on the amount of cold work and the safe operating temperatures permissible for the higher magnesium content alloys (over about 3½ per cent for operating temperatures over about 150 deg. F) to avoid susceptibility to stress corrosion.

6000 series: Alloys in this group contain silicon and magnesium in approximate proportions to form magnesium silicide, thus making them capable of being heat-treated. The major alloy in this series is 6061, one of the most versatile of the heat-treatable alloys. Though less strong than most of the 2000 or 7000 alloys, the magnesium-silicon (or magnesium-silicide) alloys possess good formability and corrosion resistance, with medium strength. Alloys in this heat-treatable group may be formed in the –T4 temper (solution heat-treated but not artificially aged) and then reach full –T6 properties by artificial aging.

7000 series: Zinc is the major alloying element in this group, and when coupled with a smaller percentage of magnesium, results in heat-treatable alloys of very high strength. Other elements such as copper and chromium are ussually added in small quantities. A notable member of this group is 7075, which is among the highest strength aluminum alloys available and is used in air-frame structures and for highly stressed parts.

Type Metal.— Antimony gives to metals the property of expansion on solidification, and hence, is used in type metal for casting type for the printing trades to insure completely filling the molds. Type metals are generally made with from 5 to 25 per cent of antimony, and with lead, tin and sometimes a small percentage of copper as the other alloying metals.

The compositions of a number of type metal alloys are as follows (figures given are percentages): lead 77.5, tin 6.5, antimony 16; lead 70, tin, 10, antimony 18, copper, 2; lead 63.2, tin 12, antimony 24, copper 0.8; lead 60.5, tin 14.5, antimony 24–25, copper 0.75; lead 60, tin 35, antimony 5; and lead 55.5, tin 40, antimony 4.5.

A high grade of type metal is composed of the following percentages: lead 50; tin 25; and antimony 25.

Copyright 2004, Industrial Press, Inc., New York, NY

Magnesium Alloys

Magnesium Alloys.— Magnesium is the lightest of all structural metals. Silver-white in color, pure magnesium is relatively soft, so is rarely used for structural purposes in the pure state. Principal metallurgical uses for pure magnesium are as an alloying element for aluminum and other metals; as a reducing agent in the extraction of such metals as titanium, zirconium, hafnium, and uranium; as a nodularizing agent in the manufacture of ductile iron; and as a sulfur removal agent in steel manufacture. Magnesium alloys are made by alloying up to about 10 per cent of other metals and have low density and an excellent combination of mechanical properties, as shown in Table 8a, resulting in high strength-to-weight ratios.

Magnesium alloys are the easiest of all the structural metals to machine, and these alloys have very high weld efficiencies. Magnesium is readily processed by all the standard casting and fabrication techniques used in metalworking, especially by pressure die casting. Because the metal work hardens rapidly, cold forming is limited to mild deformation, but magnesium alloys have excellent working characteristics at temperatures between 300 and 500 degrees F.

These alloys have relatively low elastic moduli, so they will absorb energy with good resistance to dents and high damping capacities. Fatigue strength also is good, particularly in the low-stress, high-cycle range. The alloys can be precipitation hardened, so mechanical properties can be improved by solution heat treatment and aging. Corrosion resistance was greatly improved recently, when methods were found to limit heavy metal impurities to "parts per million."

Applications of Magnesium Alloys.— Magnesium alloys are used in a wide variety of structural applications including industrial, materials handling, automotive, consumer-durable, and aerospace equipment. In industrial machinery, the alloys are used for parts that operate at high speeds, which must have light weight to allow rapid acceleration and minimize inertial forces. Materials handling equipment applications include hand trucks, dockboards, grain shovels, and gravity conveyors. Automotive applications include wheels, gearboxes, clutch housings, valve covers, and brake pedal and other brackets. Consumer durables include luggage, softball bats, tennis rackets, and housings for cameras and projectors. Their high strength-to-weight ratio suits magnesium alloys to use in a variety of aircraft structures, particularly helicopters. Very intricate shapes that are uneconomical to produce in other materials are often cast in magnesium, sometimes without draft. Wrought magnesium alloys are made in the form of bars, forgings, extrusions, wire, sheet, and plate.

Alloy and Temper Designation.— Magnesium alloys are designated by a standard four-part system established by the ASTM, and now also used by the SAE, that indicates both chemical composition and temper. Designations begin with two letters representing the two alloying elements that are specified in the greatest amount; these letters are arranged in order of decreasing percentage of alloying elements or alphabetically if they are present in equal amounts. The letters are followed by digits representing the respective composition percentages, rounded off to whole numbers, and then by a serial letter indicating some variation in composition of minor constituents. The final part, separated by a hyphen, consists of a letter followed by a number, indicating the temper condition. The letters that designate the more common alloying elements are A, aluminum; E, rare earths; H, thorium; K, zirconium; M, manganese; Q, silver; S, silicon; T, tin; Z, zinc.

The letters and numbers that indicate the temper designation are: F, as fabricated; O, annealed; H10, H11, strain hardened; H23, H24, H26, strain hardened and annealed; T4, solution heat treated; T5, artificially aged; T6, solution heat treated and artificially aged; and T8, solution heat treated, cold-worked, and artificially aged.

The nominal composition and typical properties of magnesium alloys are listed in Tables 8a and 8b.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8a. Nominal Compositions of Magnesium Alloys

Alloy	Al	Zn	Mn[a]	Si	Zr	Ag	Th	Y	Rare Earth
Sand and Permanent Mold (Gravity Die) Castings									
AM100A-T61	10.0	…	0.10	…	…	…	…	…	…
AZ63A-T6	6.0	3.0	0.15	…	…	…	…	…	…
AZ81A-T4	7.6	0.7	0.13	…	…	…	…	…	…
AZ91C-T6	8.7	0.7	0.13	…	…	…	…	…	…
AZ91E-T6[b]	8.7	0.7	0.17	…	…	…	…	…	…
AZ92A-T6	9.0	2.0	0.10	…	…	…	…	…	…
EZ33A-T5	…	2.6	…	…	0.8	…	…	…	3.3
HK31A-T6	…	0.3	…	…	0.7	…	3.3	…	…
HZ32A-T6	…	2.1	…	…	0.8	…	3.3	…	0.1
K1A-F	…	…	…	…	0.7	…	…	…	…
QE22A-T6	…	…	…	…	0.7	2.5	…	…	2.2
QH21A-T6	…	0.2	…	…	0.7	…	1.1	…	1.1
ZE41A-T5	…	4.3	0.15	…	0.7	…	…	…	1.3
ZE63A-T6	…	5.8	…	…	0.7	…	…	…	2.6
ZH62A-T5	…	5.7	…	…	0.8	…	1.8	…	…
ZK51A-T5	…	4.6	…	…	0.8	…	…	…	…
ZK61A-T6	…	6.0	…	…	0.8	…	…	…	…
WE54A-F	…	…	…	…	0.5	…	…	5.3	3.5
Pressure Die Castings									
AZ91A-F	9.0	0.7	0.13	…	…	…	…	…	…
AZ91B-F[c]	9.0	0.7	0.13	…	…	…	…	…	…
AZ91D-F[b]	9.0	0.7	0.15	…	…	…	…	…	…
AM60A-F	6.0	…	0.13	…	…	…	…	…	…
AM60B-F[b]	6.0	…	0.25	…	…	…	…	…	…
AS41A-F[d]	4.3	…	0.35	1.0	…	…	…	…	…
Extruded Bars and Shapes									
AZ10A-F	1.3	0.4	0.20	…	…	…	…	…	…
AZ31B-F	3.0	1.0	0.20	…	…	…	…	…	…
AZ31C-F	3.0	1.0	0.15	…	…	…	…	…	…
AZ61A-F	6.5	1.0	0.15	…	…	…	…	…	…
AZ80A-T5	8.5	0.5	0.12	…	…	…	…	…	…
HM31A-F	…	…	1.20	…	…	…	3.0	…	…
M1A-F	…	…	1.20	…	…	…	…	…	…
ZK40A-T5	…	4.0	…	…	0.45	…	…	…	…
ZK60A-F	…	5.5	…	…	0.45	…	…	…	…
Sheet and Plate									
AZ31B-H24	3.0	1.0	0.20	…	…	…	…	…	…
AZ31C-H24	3.0	1.0	0.15	…	…	…	…	…	…
HK31A-H24	…	…	…	…	0.7	…	3.3	…	…
HM21A-T8	…	…	0.80	…	…	…	2.0	…	…

[a] All manganese vales are minium.
[b] High-purity alloy, Ni, Fe, and Cu severely restricted.
[c] 0.30 per cent maximum residual copper is allowed.
[d] For battery applications.
Source: Metals Handbook, 9th edition, Vol. 2, American Society for Metals.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8b. Typical Room-Temperature Mechanical Properties of Magnesium Alloys

Alloy	Tensile Strength (ksi)	Yield Strength			Elongation in 2 in. (%)	Shear Strength (ksi)	Hardness Rockwell B[a]
		Tensile (ksi)	Compressive (ksi)	Bearing (ksi)			
Sand and Permanent Mold (Gravity Die) Castings							
AM100A-T61	40	22	22	68	1	…	69
AZ63A-T6	40	14	14	44	12	18	55
AZ81A-T4	40	12	12	35	15	21	55
AZ91C-T6	40	21	21	52	6	21	70
AZ91E-T6[b]	40	21	21	52	6	21	70
AZ92A-T6	40	22	22	65	3	21	81
EZ33A-T5	23	16	16	40	3	20	50
HK31A-T6	32	15	15	40	8	21	55
HZ32A-T6	27	13	13	37	4	20	55
K1A-F	26	8	8	18	19	8	…
QE22A-T6	38	28	28	…	3	…	80
QH21A-T6	40	30	30	…	4	22	…
ZE41A-T5	30	20	20	51	4	23	62
ZE63A-T6	44	28	28	…	10	…	60–85
ZH62A-T5	35	22	22	49	4	23	70
ZK51A-T5	30	20	20	51	4	22	62
ZK61A-T6	45	28	28	…	10	…	…
WE54A-F	40	29	29	…	4	…	…
Pressure Die Castings							
AZ91A-F	34	23	23	…	3	20	63
AZ91B-FAZ91B-F[c]	34	23	23	…	3	20	63
AZ91D-F[b]	34	23	23	…	3	20	63
AM60A-F	32	19	19	…	8	…	…
AM60B-F[b]	32	19	19	…	8	…	…
AS41A-F[d]	31	20	20	…	6	…	…
Extruded Bars and Shapes							
AZ10A-F	35	21	10	…	10	…	…
AZ31B-F	38	29	14	33	15	19	49
AZ31C-F	38	29	14	33	15	19	49
AZ61A-F	45	33	19	41	16	20	60
AZ80A-T5	55	40	35	…	7	24	82
HM31A-F	42	33	27	50	10	22	…
M1A-F	37	26	12	28	12	18	44
ZK40A-T5	40	37	20	…	4	…	…
ZK60A-F	51	41	36	59	11	26	88
Sheet and Plate							
AZ31B-H24	42	32	26	47	15	23	73
AZ31C-H24	42	32	26	47	15	23	73
HK31A-H24	38	30	23	41	9	…	68
HM21A-T8	34	25	19	39	11	18	…

[a] 500 kg load, 10-mm ball.
[b] High-purity alloy, Ni, Fe, and Cu severely restricted.
[c] 0.30 per cent maximum residual copper is allowed.
[d] For battery applications.

Source: Metals Handbook, 9th edition, Vol. 2, American Society for Metals.

Copyright 2004, Industrial Press, Inc., New York, NY

Nickel and Nickel Alloys

Characteristics of Nickel and Nickel Alloys.— Nickel is a white metal, similar in some respects to iron but with good oxidation and corrosion resistances. Nickel and its alloys are used in a variety of applications, usually requiring specific corrosion resistance or high strength at high temperature. Some nickel alloys exhibit very high toughness; others have very high strength, high proportional limits, and high moduli compared with steel. Commercially, pure nickel has good electrical, magnetic, and magnetostrictive properties. Nickel alloys are strong, tough, and ductile at cryogenic temperatures, and several of the so-called nickel-based superalloys have good strength at temperatures up to 2000 degrees F.

Most wrought nickel alloys can be hot and cold-worked, machined, and welded successfully; an exception is the most highly alloyed nickel compound—forged nickel-based superalloys—in which these operations are more difficult. The casting alloys can be machined or ground, and many can be welded and brazed.

There are five categories into which the common nickel-based metals and alloys can be separated: the pure nickel and high nickel (over 94 per cent Ni) alloys; the nickel–molybdenum and nickel–molybdenum–chromium superalloys, which are specifically for corrosive or high-temperature, high-strength service; the nickel–molybdenum–chromium–copper alloys, which are also specified for corrosion applications; the nickel–copper (Monel) alloys, which are used in actively corrosive environments; and the nickel–chromium and nickel–chromium–iron superalloys, which are noted for their strength and corrosion resistance at high temperatures.

Descriptions and compositions of some commonly used nickel and high nickel alloys are shown in Table 9.

Titanium and Titanium Alloys

Titanium is a gray, light metal with a better strength-to-weight ratio than any other metal at room temperature, and is used in corrosive environments or in applications that take advantage of its light weight, good strength, and nonmagnetic properties. Titanium is available commercially in many alloys, but multiple requirements can be met by a single grade of the commercially pure metal. The alloys of titanium are of three metallurgical types: alpha, alpha–beta, and beta, with these designations referring to the predominant phases present in the microstructure.

Titanium has a strong affinity for hydrogen, oxygen, and nitrogen gases, which tend to embrittle the material; carbon is another embrittling agent. Titanium is outstanding in its resistance to strongly oxidizing acids, aqueous chloride solutions, moist chlorine gas, sodium hypochlorite, and seawater and brine solutions. Nearly all nonaircraft applications take advantage of this corrosion resistance. Its uses in aircraft engine compressors and in airframe structures are based on both its high corrosion resistance and high strength-to-weight ratio.

Procedures for forming titanium are similar to those for forming stainless steel. Titanium and its alloys can be machined and abrasive ground; however, sharp tools and continuous feed are required to prevent work hardening. Tapping is difficult because the metal galls.

Titanium castings can be produced by investment or graphite mold methods; however, because of the highly reactive nature of the metal in the presence of oxygen, casting must be done in a vacuum.

Generally, titanium is welded by gas-tungsten arc or plasma arc techniques, and the key to successful welding lies in proper cleaning and shielding. The alpha–beta titanium alloys can be heat treated for higher strength, but they are not easily welded. Beta and alpha–beta alloys are designed for formability; they are formed in the soft state, and then heat treated for high strength.

The properties of some wrought titanium alloys are shown in Table 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Common Cast and Wrought Nickel and High Nickel Alloys — Designations, Compositions, Typical Properties, and Uses

UNS Designation	Description and Common Name	Nominal Composition (Weight %)	Typical Room-Temperature Properties			Form	Typical Uses
			Tensile (ksi)	0.2% Yield (ksi)	Elong. (%)		
N02200	Commercially pure Ni (Nickel 200)	99.5 Ni	67	22	47	Wrought	Food processing and chemical equipment.
N04400	Nickel–copper alloy (Monel 400)	65 Ni, 32 Cu, 2 Fe	79	30	48	Wrought	Valves, pumps, shafts, marine fixtures and fasteners, electrical and petroleum refining equipment.
N05500	Age-hardened Ni–Cu alloy (Monel K 500)	65 Ni, 30 Cu, 2 Fe, 3 Al + Ti	160	111	24	Wrought	Pump shafts, impellers, springs, fasteners, and electronic and oil well components.
N06002	Ni–Cr Alloy (Hastelloy X)	60 Ni, 22 Cr, 19 Fe, 9 Mo, 0.6 W	114	52	43	Wrought	Turbine and furnace parts, petrochemical equipment.
N06003	Ni–Cr alloy (Nichrome V)	80 Ni, 20 Cr	100	60	30	Wrought	Heating elements, resistors, electronic parts.
N06333	Ni–Cr alloy (RA 333)	48 Ni, 25 Cr, 18 Fe, 3 Mo, 3 W, 3 Co	100	50	50	Wrought	Turbine and furnace parts.
N06600	Ni–Cr alloy (Inconel 600)	75 Ni, 15 Cr, 10 Fe	90	36	47	Wrought	Chemical, electronic, food processing and heat treating equipment; nuclear steam generator tubing.
N06625	Ni–Cr alloy (Inconel 625)	61 Ni, 21 Cr, 2 Fe, 9 Mo, 4 Nb	142	86	42	Wrought	Turbine parts, marine and chemical equipment.
N07001	Age-hardened Ni–Cr alloy (Waspalloy)	58 Ni, 20 Cr, 14 Co, 4 Mo, 3 Al, 1.3 Ti, B, Zr	185	115	25	Wrought	Turbine parts.
N07500	Age-hardened Ni–Cr alloy (Udimet 500)	52 Ni, 18 Cr, 19 Co, 4 Mo, 3 Al, 3 Ti, B, Zr	176	110	16	Wrought & Cast	Turbine parts.
N07750	Age-hardened Ni–Cr alloy (Inconel X-750)	73 Ni, 16 Cr, 7 Fe, 2.5 Ti, 1 Al, 1 Nb	185	130	20	Wrought	Turbine parts, nuclear reactor springs, bolts, extrusion dies, forming tools.
N08800	Ni–Cr–Fe alloy (Incoloy 800)	32 Ni, 21 Cr, 46 Fe, 0.4 Ti, 0.4 Al	87	42	44	Wrought	Heat exchangers, furnace parts, chemical and power plant piping.
N08825	Ni–Cr–Fe alloy (Incoloy 825)	42 Ni, 22 Cr, 30 Fe, 3 Mo, 2 Cu, 1 Ti, Al	91	35	50	Wrought	Heat treating and chemical handling equipment.
N09901	Age-hardened Ni–Cr–Fe alloy (Incoloy 901)	43 Ni, 12 Cr, 36 Fe, 6 Mo, 3 Ti + Al, B	175	130	14	Wrought	Turbine parts.
N10001	Ni–Mo alloy (Hastelloy B)	67 Ni, 28 Mo, 5 Fe	121	57	63	Wrought	Chemical handling equipment.
N10004	Ni–Cr–Mo alloy (Hastelloy W)	59 Ni, 5 Cr, 25 Mo, 5 Fe, 0.6 V	123	53	55	Wrought	Weld wire for joining dissimilar metals, engine repair and maintenance.
N10276	Ni–Cr–Mo alloy (Hastelloy C-276)	57 Ni, 15 Cr, 16 Mo, 5 Fe, 4 W, 2 Co	116	52	60	Wrought	Chemical handling equipment.
N13100	Ni–Co alloy (IN 100)	60 Ni, 10 Cr, 15 Co, 3 Mo, 5.5 Al, 5 Ti, 1 V. B, Zr	147	123	9	Cast	Turbine parts.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Mechanical Properties of Wrought Titanium Alloys

Nominal Composition (%)	Condition	Tensile Strength (ksi)	Room Temperature		Reduction in Area (%)
			Yield Strength (ksi)	Elongation (%)	
Commercially Pure					
99.5 Ti	Annealed	48	35	30	55
99.2 Ti	Annealed	63	50	28	50
99.1 Ti	Annealed	75	65	25	45
99.0 Ti	Annealed	96	85	20	40
99.2 Ti[a]	Annealed	63	50	28	50
98.9 Ti[b]	Annealed	75	65	25	42
Alpha Alloys					
5 Al, 2.5 Sn	Annealed	125	117	16	40
5 Al, 2.5 Sn (low O_2)	Annealed	117	108	16	…
Near Alpha Alloys					
8 Al, 1 Mo, 1 V	Duplex annealed	145	138	15	28
11 Sn, 1 Mo, 2.25 Al, 5.0 Zr, 1 Mo, 0.2 Si	Duplex annealed	160	144	15	35
6 Al, 2 Sn, 4 Zr, 2 Mo	Duplex annealed	142	130	15	35
5 Al, 5 Sn, 2 Zr, 2 Mo, 0.25 Si	975°C (1785°F) (½ h), AC 595°C (1100°F)(2 h), AC	152	140	13	…
6 Al, 2 Nb, 1 Ta, 1 Mo	As rolled 2.5 cm (1 in.) plate	124	110	13	34
6 Al, 2 Sn, 1.5 Zr, 1 Mo, 0.35 Bi, 0.1 Si	Beta forge + duplex anneal	147	137	11	…
Alpha–Beta Alloys					
8 Mn	Annealed	137	125	15	32
3 Al, 2.5 V	Annealed	100	85	20	…
6 Al, 4 V	Annealed	144	134	14	30
	Solution + age	170	160	10	25
6 Al, 4 V (low O_2)	Annealed	130	120	15	35
6 Al, 6 V, 2 Sn	Annealed	155	145	14	30
	Solution + age	185	170	10	20
7 Al, 4 Mo	Solution + age	160	150	16	22
6 Al, 2 Sn, 4 Zr, 6 Mo	Solution + age	184	170	10	23
6 Al, 2 Sn, 2 Zr, 2 Mo, 2 Cr, 0.25 Si	Solution + age	185	165	11	33
10 V, 2 Fe, 3 Al	Solution + age	185	174	10	19
Beta Alloys					
13 V, 11 Cr, 3 Al	Solution + age	177	170	8	…
	Solution + age	185	175	8	…
8 Mo, 8 V, 2 Fe, 3 Al	Solution + age	190	180	8	…
3 Al, 8 V, 6 Cr, 4 Mo, 4 Zr	Solution + age	210	200	7	…
	Annealed	128	121	15	…
11.5 Mo, 6 Zr, 4.5 Sn	Solution + age	201	191	11	…

[a] Also contains 0.2 Pd.
[b] Also contains 0.8 Ni and 0.3 Mo.

Source: Titanium Metals Corp. of America and RMI Co.

Copyright 2004, Industrial Press, Inc., New York, NY

PLASTICS

Properties of Plastics

Characteristics of Important Plastics Families

ABS (acrylonitrile-butadiene-styrene)	Rigid, low-cost thermoplastic, easily machined and thermo-formed.
Acetal	Engineering thermoplastic with good strength, wear resistance, and dimensional stability. More dimensionally stable than nylon under wet and humid conditions.
Acrylic	Clear, transparent, strong, break-resistant thermoplastic with excellent chemical resistance and weatherability.
CPVC (chlorinated PVC)	Thermoplastic with properties similar to PVC, but operates to a 40-60°F higher temperature.
Fiberglass	Thermosetting composite with high strength-to-weight ratio, excellent dielectric properties, and unaffected by corrosion.
Nylon	Thermoplastic with excellent impact resistance, ideal for wear applications such as bearings and gears, self-lubricating under some circumstances.
PEEK (polyetheretherketone)	Engineering thermoplastic, excellent temperature resistance, suitable for continuous use above 500°F, excellent flexural and tensile properties.
PET (polyethyleneterephthalate)	Dimensionally stable thermoplastic with superior machining characteristics compared to acetal.
Phenolic	Thermosetting family of plastics with minimal thermal expansion, high compressive strength, excellent wear and abrasion resistance, and a low coefficient of friction. Used for bearing applications and molded parts.
Polycarbonate	Transparent tough thermoplastic with high impact strength, excellent chemical resistance and electrical properties, and good dimensional stability.
Polypropylene	Good chemical resistance combined with low moisture absorption and excellent electrical properties, retains strength up to 250°F.
Polysulfone	Durable thermoplastic, good electrical properties, operates at temperatures in excess of 300°F.
Polyurethane	Thermoplastic, excellent impact and abrasion resistance, resists sunlight and weathering.
PTFE (polytetrafluoroethylene)	Thermoplastic, low coefficient of friction, withstands up to 500°F, inert to chemicals and solvents, self-lubricating with a low thermal-expansion rate.
PVC (polyvinyl chloride)	Thermoplastic, resists corrosive solutions and gases both acid and alkaline, good stiffness.
PVDF (polyvinylidenefluoride)	Thermoplastic, outstanding chemical resistance, excellent substitute for PVC or polypropylene. Good mechanical strength and dielectric properties.

Copyright 2004, Industrial Press, Inc., New York, NY

Plastics Materials.— Plastics materials, often called resins, are made up of many repeating groups of atoms or molecules linked in long chains (called polymers) that combine such elements as oxygen, hydrogen, nitrogen, carbon, silicon, fluorine, and sulfur. Both the lengths of the chains and the mechanisms that bond the links of the chains together are related directly to the mechanical and physical properties of the materials. There are two main groups: thermoplastics and thermosets.

Thermoplastic materials become soft and moldable when heated, and change back to solids when allowed to cool. Examples of thermoplastics are acetal, acrylic, cellulose acetate, nylon, polyethylene, polystyrene, vinyl, and nylon. Thermoplastic materials that are flexible even when cool are known as thermoplastic elastomers or TPEs. When thermoplastic materials are heated, the linked chains of molecules can move relative to each other, allowing the mass to flow into a different shape. Cooling prevents further flow. Although the heating/cooling cycle can be repeated, recycling reduces mechanical properties and appearance.

Thermoset plastics such as amino, epoxy, phenolic, and unsaturated polyesters, are so named because they are changed chemically during processing and become hard solids. Although the structures of thermoset materials are similar to those of thermoplastic materials, processing develops cross-links between adjacent molecules, forming complex networks that prevent relative movement between the chains at any temperature. Many rubbers that are processed by vulcanizing, such as butyl, latex, neoprene, nitrile, polyurethane, and silicone, also are classified as thermosets. Heating a thermoset degrades the material so that it cannot be reprocessed satisfactorily.

Elastomers are flexible materials that can be stretched up to about double their length at room temperature and can return to their original length when released. Thermoplastic elastomers are often used in place of rubber, and may also be used as additives to improve the impact strength of rigid thermoplastics.

Structures.— Thermoplastics can be classified by their structures into categories such as amorphous (noncrystalline), crystalline, and liquid crystalline polymers (LCP). Amorphous thermoplastics include polycarbonate, polystyrene, ABS (acrylonitrile-butadiene-styrene), SAN (styrene-acrylonitrile), and PVC (polyvinylchloride). Crystalline thermoplastics have polymer chains that are packed together in an organized way, as distinct from the unorganized structures of amorphous plastics, and include acetal, nylon, polyethylene, polypropylene, and polyester. The organized regions in crystalline thermoplastics are joined by noncrystalline (amorphous) zones, and the structures are such that the materials are stronger and stiffer, though less resistant to impact, than completely noncrystalline materials. Crystalline thermoplastics have higher melting temperatures and higher shrinkage and warpage factors than amorphous plastics. Liquid crystalline plastics are polymers with highly ordered rod-like structures and have high mechanical property values, good dimensional stability and chemical resistance, and are easy to process, with melting temperatures similar to those of crystalline plastics. Unlike amorphous and crystalline plastics, liquid crystalline plastics retain significant order in the melt phase. As a result, they have the lowest shrinkage and warpage of the three types of thermoplastics.

Mixtures.— Characteristics of plastics materials can be changed by mixing or combining different types of polymers and by adding nonplastics materials. Particulate fillers such as wood flour, silica, sand, ceramic and carbon powder, tiny glass balls, and powdered metal are added to increase modulus and electrical conductivity, to improve resistance to heat or ultraviolet light, and to reduce cost, for example. Plasticizers may be added to decrease modulus and increase flexibility. Other additives may be used to increase resistance to effects of ultraviolet light and heat or to prevent oxidation, and for a variety of other purposes.

Reinforcing fibers of glass, carbon, or Aramid (aromatic polyamide fibers having high tensile strength, a range of moduli, good toughness, and stress–strain behavior similar to

Copyright 2004, Industrial Press, Inc., New York, NY

that of metals) are added to improve mechanical properties. Careful design and process selection must be used to position the fibers so that they will provide the required strength where it is needed. Continuous fiber may be positioned carefully in either a thermoplastics or thermoset matrix to produce basic parts generally called composites, which have the highest mechanical properties and cost of the reinforced plastics.

Copolymers embody two or more different polymers and may have properties that are completely different from those of the individual polymers (homopolymers) from which they are made. An approach known as alloying consists of pure mechanical blending of two or more different polymers, often with special additives to make them compatible. These "alloys" are compounded so as to retain the most desirable characteristics of each constituent, especially in impact strength and flame resistance. However, properties usually are intermediate between those of the constituent materials.

Physical Properties.— Almost all proposed uses of plastics require some knowledge of the physical properties of the materials, and this information is generally readily available from manufacturers. Properties such as density, ductility, elasticity and plasticity, homogeneity, uniformity of composition, shrinkage during cooling from the molding temperature, transmittal of light, toughness (resistance to impact), brittleness, notch sensitivity, isotropy (properties that are the same when measured in any direction) and anisotropy (properties that vary when measured in different directions), and lubricity (load-bearing characteristics under relative motion) may all need consideration when a material suitable for a specific application is to be specified.

Most of the terms used to describe the physical characteristics of metals, such as density, ductility, brittleness, elasticity, notch sensitivity, specific gravity, and toughness, have similar meanings when they are applied to plastics, but different measures are often used with plastics. Like cast metals, many plastics are isotropic so that their characteristics are the same measured in any direction. Properties of rolled metals and extruded plastics vary when measured in the longitudinal and transverse directions, so these materials are anisotropic.

Density is a measure of the mass per unit volume, usually expressed in lb/in.^{3} or g/cm^3 at a temperature of 73.4 degrees F (23 degrees C). Density information is used mainly to calculate the amount of material required to make a part of a given volume, the volume being calculated from drawing dimensions.

Specific gravity is the ratio of the mass of a given volume of a material to the mass of the same volume of water, both measured at 73.4 degrees F (23 degrees C). The ratio is dimensionless so is useful for comparing different materials, and is used in cost estimating and quality control.

Shrinkage is the ratio of the dimension of the plastics molding to the corresponding dimension of the mold, expressed in in./in. or cm/cm, both at room temperature. As with a die casting die, the moldmaker uses this ratio to determine mold cavity measurements that will produce a part of the required dimensions. Shrinkage in a given material can vary with wall thickness, direction of flow of the plastics in the mold, and molding conditions. Amorphous and liquid crystalline thermoplastics have lower shrinkage ratios than crystalline thermoplastics. Glass-reinforced and filled materials have lower shrinkage than unfilled materials.

Water absorption is the amount of increase in weight of a material due to absorption of water, expressed as a percentage of the original weight. Standard test specimens are first dried for 24 hr, then weighed before and after immersion in water at 73.4 degrees F (23 degrees C) for various lengths of time. Water absorption affects both mechanical and electrical properties and part dimensions. Parts made from materials with low water absorption rates tend to have greater dimensional stability.

Opacity (or transparency) is a measure of the amount of light transmitted through a given material under specific conditions. Measures are expressed in terms of haze and

Copyright 2004, Industrial Press, Inc., New York, NY

luminous transmittance. Haze measurements indicate the percentage of light transmitted through a test specimen that is scattered more than 2.5 degrees from the incident beam. Luminous transmittance is the ratio of transmitted light to incident light.

Elasticity is the ability of a material to return to its original size and shape after being deformed. Most plastics have limited elasticity, although rubber and materials classified as thermoplastic elastomers (TPEs) have excellent elasticity.

Plasticity is the inverse of elasticity, and a material that tends to stay in the shape or size to which it has been deformed has high plasticity. Some plastics can be formed cold by being stressed beyond the yield point and such plastics then exhibit plasticity. When thermoplastics are heated to their softening temperature, they have almost perfect plasticity.

Ductility is the ability of a material to be stretched, pulled, or rolled into shape without destroying the integrity of the material.

Toughness is a measure of the ability of a material to absorb mechanical energy without cracking or breaking. Tough material can absorb mechanical energy with either elastic or plastic deformation. High-impact unfilled plastics generally have excellent toughness, and low- or moderate-impact materials may also be tough if their ultimate strength is high enough (see *Typical Stress–Strain Curves* on page 598). The area under the stress–strain curve is often used as the measure of toughness for a particular plastics material.

Brittleness is the lack of toughness. Brittle plastics frequently have low impact and high stiffness properties. Many glass-reinforced and mineral-filled materials are brittle.

Notch sensitivity is a measure of the ease with which a crack progresses through a material from an existing notch, crack, or sharp corner.

Lubricity describes the load-bearing characteristics of a material under relative motion. Plastics with good lubricity have low coefficients of friction with other materials (or sometimes with themselves) and no tendency to gall.

Homogeneous means uniform. The degree of homogeneity indicates the uniformity of composition of a material throughout its mass. In a completely homogeneous body, the smallest sample has the same physical properties as the body. An unfilled thermoplastics is a reasonably homogeneous material.

Heterogeneous means varying. In a heterogeneous body, for example, a glass-reinforced material, the composition varies from point to point. Many heterogeneous materials are treated as homogeneous for design purposes because a small sample of the material has the same properties as the body.

Isotropy means that the properties at any point in a body are the same, regardless of the direction in which they are measured.

Anisotropy means that the physical properties of a material depend on the direction of measurement. Various degrees of anisotropy exist, depending on the amount of symmetry of the material or component shape. For example, cast metals and plastics tend to be isotropic so that samples cut in any direction within a cast body tend to have the same physical properties. However, rolled metals tend to develop crystal orientation in the direction of rolling so that they have different mechanical properties in the rolling and transverse-to-rolling directions.

Extruded plastics film also may have different properties in the extruding and transverse directions so that these materials are oriented biaxially and are anisotropic. Composite materials that have fiber reinforcements carefully oriented in the direction of applied loads, surrounded by a plastics matrix, have a high degree of property orientation with direction at various points in the structure and are anisotropic.

As another example, wood, page 411, is an anisotropic material with distinct properties in three directions and is very stiff and strong in the direction of growth. Fair properties are also found in one direction perpendicular to the growth direction, but in a third direction at right angles to the other two directions, the mechanical properties are much lower.

Copyright 2004, Industrial Press, Inc., New York, NY

The preceding examples involve mechanical properties, but anisotropy is also used in referring to the way a material shrinks in the mold. Anisotropic shrinkage is important in molding crystalline and glass-fiber-reinforced materials for which shrinkage values are usually listed for the flow direction and the cross-flow direction. These values are of most concern to the tool designer and molder, but the existence of anisotropy and its severity must be considered when a material is chosen for a part having tight tolerances.

Significance of Elasticity, Homogeneity, and Isotropy: Structural analysis during design of components uses two independent constants, Young's modulus (E) and Poisson's ratio (ν), but two constants are sufficient only for elastic, isotropic materials that respond linearly to loads (when load is proportional to deformation). Designers often use the same values for these constants everywhere in the structure, which is correct only if the structure is homogeneous.

Assumptions of linear elasticity, isotropy, and homogeneity are reasonable for many analyses and are a good starting point, but use of these assumptions can lead to significant design errors with plastics, particularly with glass-reinforced and liquid crystalline polymers, which are highly anisotropic. In the following, plastics are assumed to be linearly elastic, homogeneous, and isotropic to allow a simpler presentation of mechanical properties in line with the data provided in plastics manufacturers' marketing data sheets. The standard equations of structural analysis (bending, torsion, pressure in a pipe, etc.) also require these assumptions.

As the degree of anisotropy increases, the number of constants or moduli required to describe the material also increases, up to a maximum of 21. Uncertainty about material properties and the questionable applicability of the simple analysis techniques employed point to the need for extensive end-use testing of plastics parts before approval of a particular application. A partial solution to this problem lies in the use of finite-element-analysis (FEA) methods. The applicability of FEA methods requires good understanding of the anisotropic nature of plastics materials.

Mechanical Properties.— Almost all end-use applications involve some degree of loading, so mechanical properties are of prime importance in designing with plastics. Material selection is usually based on manufacturers' marketing data sheets listing tensile strength, modulus of elasticity (E), elongation, impact strength, stress and strain behavior, and shear strength. Suppliers' data often are generated under standard test conditions so may not be directly transferable to the components produced. Because of the somewhat lower modulus of elasticity of plastics materials (10^5 for plastics compared with 10^6 lb_f/in^2 for metals), different units of measure are used to express the results.

Determination of the true meaning of mechanical properties and their relation to end-use requirements is of vital importance in design. In practical applications, materials are seldom subjected to steady deformation without the influence of other factors such as environment and temperature. A thorough understanding of mechanical properties and tests used to determine such properties, and the effects of adverse or beneficial conditions on mechanical properties over long time periods, is extremely important. Some manufacturers offer design and technical advice to customers who do not possess this understanding.

Stress: A three-dimensional body having a balanced system of external forces F_1 through F_5 acting on it, such that the body is at rest, is shown in Fig. 1. Such a body develops internal forces to transfer and distribute the external loads. If the body is cut at an arbitrary cross-section and one part is removed, as shown at the right in Fig. 1, a new system of

Copyright 2004, Industrial Press, Inc., New York, NY

forces acting on the cut surface is developed to balance the remaining external forces. Similar forces (stresses) exist within the uncut body.



Fig. 1. Internal Forces and Stresses in a Body



Fig. 2. Simple Tension Load

Stresses must be defined with both magnitude and direction. The stress S acting in the direction shown in Fig. 1, on the point P of the cut surface, has two stress components. One of these components, σ, acts perpendicular to the surface and is called a normal or direct stress. The other stress, τ, acts parallel to the surface and is called a shear stress.

Normal stress is illustrated by the simple tension test shown in Fig. 2, where the direct stress is the ratio of applied load to the original cross-sectional area in lb_f/in^2. In the Système International (SI or metric system, see pages 2544, and starting on page 2576) the stress, σ, is expressed in newtons/meter^2 (N/m^2).

$$\text{Stress} = \frac{\text{Load}}{\text{Area}} \text{ or } \sigma = \frac{F}{A} \tag{1}$$

If the load is applied as shown in Fig. 2, the test piece is in tension, and if reversed, it is in compression.

Normal strain is also illustrated by the diagram in Fig. 2, where the load or stress applied to the test piece causes it to change its length. If the bar has an original length L, and changes its length by ΔL, the strain, $\in$, is defined as

$$\text{Strain} = \frac{\text{Change of Length}}{\text{Original Length}} \text{ or } \in = \frac{\Delta L}{L} \tag{2}$$

Strain is the ratio between the amount of deformation of the material and its original length and is a dimensionless quantity. Extensions of most materials under load are generally very small. Strain ($\mu\in$ or microstrain in most metals) is measured and expressed in microinches (millionths of an inch) per inch, or 10^{-6} in./in. (10^{-6} cm/cm). Alternatively, strain is expressed as a percentage. The three methods compare as follows:

$$1000\,\mu\in = 0.001 = 0.1 \text{ per cent strair}$$

$$10000\,\mu\in = 0.010 = 1 \text{ per cent strain}$$

Modulus of Elasticity: Most metals and plastics have deformations that are proportional to the imposed loads over a range of loads. Stress is proportional to load and strain is proportional to deformation, so stress is proportional to strain and is expressed by Hooke's law:

$$\frac{\text{Stress}}{\text{Strain}} = \text{Constant} = E \tag{3}$$

The constant E is called the modulus of elasticity, Young's modulus, or, in the plastics industry, tensile modulus. Referring to Fig. 2, tensile modulus is given by the formula:

Copyright 2004, Industrial Press, Inc., New York, NY

$$E = \frac{\sigma}{\epsilon} = \frac{F/A}{\Delta L/L} = \frac{FL}{A\Delta L} \quad (4)$$

Thus, the modulus is the slope of the initial portion of the stress–strain curve. An elastic material does not necessarily obey Hooke's law, since it is possible for a material to return to its original shape without the stress being proportional to the strain. If a material does obey Hooke's law, however, it is elastic.

The straight portion of the stress–strain curve for many plastics is difficult to locate, and it is necessary to construct a straight line tangent to the initial portion of the curve to use as a modulus. The shape of a line so obtained is called the initial modulus. In some plastics, the initial modulus can be misleading, owing to the nonlinear elasticity of the material. Some suppliers therefore provide the so-called 1 per cent secant modulus, which is the ratio of stress to strain at 1 per cent strain on the stress–strain curve. In the illustration of typical stress–strain curves in Fig. 3, the secant modulus at the point *E* is the slope of the line *OE*.



Fig. 3. Typical Stress–Strain Curves

For metals, Young's modulus is expressed in terms of 10^6 $lb_f/in.^2$, N/m^2, or Pa, as convenient (see starting on page 2576). For plastics, tensile modulus is expressed as 10^5 lb_f/in^2 or in GPa (1 GPa = 145,000 $lb_f/in.^2$).

Secant modulus is the ratio of stress to corresponding strain at any point on the stress–strain curve (see *Modulus of Elasticity*).

Proportional limit is the greatest stress at which a material is capable of sustaining the applied load without losing the proportionality of stress to strain. This limit is the point on the stress–strain curve where the slope begins to change, as shown at A on each of the curves in Fig. 3. Proportional limit is expressed in $lb_f/in.^2$ (MPa or GPa).

Yield point is the first point on the stress–strain curve where an increase in strain occurs without an increase in stress, and is indicated by *B* on some of the curves in Fig. 3. The slope of the curve is zero at this point; however, some materials do not have a yield point.

Ultimate strength is the maximum stress a material withstands when subjected to a load, and is indicated by *C* in Fig. 3. Ultimate strength is expressed in $lb_f/in.^2$ (MPa or GPa).

Elastic limit is indicated by the point *D* on the stress–strain curve in Fig. 3, and is the level beyond which the material is permanently deformed when the load is removed.Although many materials can be loaded beyond their proportional limit and still return to zero strain when the load is removed, some plastics have no proportional limit in that no region exists where the stress is proportional to strain (i.e., where the material obeys Hooke's law).

Yield strength is the stress at which a material shows a specified deviation from stress to strain proportionality. Some materials do not show a yield strength clearly, and it may be desirable to choose an arbitrary stress level beyond the elastic limit, especially with plas-

Copyright 2004, Industrial Press, Inc., New York, NY

tics that have a very high strain at the yield point, to establish a realistic yield strength. Such a point is seen at *F* on some of the curves in Fig. 3, and is defined by constructing a line parallel to *OA* at a specified offset strain, *H*. The stress at the intersection of the line with the stress–strain curve at *F* would be the yield strength at *H* offset. If *H* were at 2 per cent strain, *F* would be described as the yield strength at a 2 per cent strain offset.

Poisson's ratio is defined on page 204. Under a tensile load, a rectangular bar of length *L*, with sides of widths *b* and *d*, lengthens by an amount ΔL, producing a longitudinal strain of

$$\epsilon = \frac{\Delta L}{L} \tag{5}$$

The bar is reduced in its lateral dimensions and the associated lateral strains will be opposite in sign, resulting in

$$\epsilon = -\frac{\Delta b}{b} = -\frac{\Delta d}{d} \tag{6}$$

If the deformation is within the elastic range, the ratio (Poisson's ratio *v*) of the lateral to the longitudinal strains will be constant. The formula is:

$$v = \frac{\text{Lateral Strain}}{\text{Longitudinal Strain}} = \frac{\Delta d/d}{\Delta L/L} \tag{7}$$

Values of *v* for most engineering materials lie between 0.20 and 0.40, and these values hold for unfilled rigid thermoplastics. Values of *v* for filled or reinforced rigid thermoplastics fall between 0.10 and 0.40 and for structural foam between 0.30 and 0.40. Rigid thermoset plastics have Poisson's ratios between 0.20 and 0.40, whether filled or unfilled, and elastomers can approach 0.5.

Shear stress is treated on page 215. Any block of material is subject to a set of equal and opposite shearing forces *Q*. If the block is envisaged as an infinite number of infinitesimally thin layers as shown diagrammatically in Fig. 4, it is easy to imagine a tendency for one layer subject to a force to slide over the next layer, producing a shear form of deformation or failure. The shear stress τ is defined as

$$\tau = \frac{\text{Shear Load}}{\text{Area Resisting Load}} = \frac{Q}{A} \tag{8}$$

Shear stress is always tangential to the area on which it acts. Shearing strain is the angle of deformation γ and is measured in radians.



Fig. 4. Shear Stress is Visualized as a Force *Q* Causing Infinitely Thin Layers of a Component to Slide Past Each Other, Producing a Shear Form of Failure

Copyright 2004, Industrial Press, Inc., New York, NY

Shear modulus is a constant G, otherwise called the modulus of rigidity, and, for materials that behave according to Hooke's law, is directly comparable to the modulus of elasticity used in direct stress calculations. The constant is derived from

$$G = \frac{\text{Shear Stress}}{\text{Shear Strain}} = \frac{\tau}{\gamma} \tag{9}$$

Relating Material Constants: Although only two material constants are required to characterize a material that is linearly elastic, homogeneous, and isotropic, three such constants have been introduced here. These three constants are tensile modulus E, Poisson's ratio v, and shear modulus G, and they are related by the following equation, based on elasticity principles:

$$\frac{E}{G} = 2(1 + v) \tag{10}$$

This relationship holds for most metals and is generally applicable to injection-moldable thermoplastics. It must be remembered, however, that most plastics, and particularly fiber-reinforced and liquid crystalline materials, are inherently either nonlinear, or anisotropic, or both.

Direct shear refers to a shear strength test much used in the plastics industry with a setup similar to that shown in Fig. 5, and the results of such tests are often described in manufacturers' marketing data sheets as the shear strength of the material. The shear strength reported from such a test is not a pure shear strength because a considerable part of the load is transferred by bending or compressing, or both, rather than by pure shear, and results can be affected by the susceptibility of the material to the sharpness of the load faces in the test apparatus. Thus, the test cannot be used to develop shear stress–strain curves or to determine the shear modulus.

When analyzing plastics in a pure shear situation or when the maximum shear stress is calculated in a complex stress environment, designers often use a shear strength value of about half the tensile strength, or the direct shear strength obtained from the test referred to above, whichever is least.



Fig. 5. Direct Shear Test Used in the Plastics Industry

True stress and true strain are terms not in frequent use. In Fig. 2, the stress, sometimes called the engineering stress, is calculated from an increasing load F, acting over a constant area A. Because the cross-sectional area is reduced with most materials, use of that smaller cross-sectional area in the calculation yields what is called the "true stress." In addition, the direct strain referred to earlier, that is, the total change in length divided by the original length, is often called the "engineering strain." The true strain would be the instantaneous deformation divided by the instantaneous length. Therefore, the shape of such a stress–strain curve would not be the same as a simple stress–strain curve. Modulus values and stress–strain curves are almost universally based on engineering stress and strain.

Copyright 2004, Industrial Press, Inc., New York, NY

Other Measures of Strength and Modulus.— Tensile and compression properties of many engineering materials, which are treated as linearly elastic, homogeneous, and isotropic, are often considered to be identical, so as to eliminate the need to measure properties in compression. Also, if tension and compression properties are identical, under standard beam bending theory, there is no need to measure the properties in bending. In a concession to the nonlinear, anisotropic nature of most plastics, these properties, particularly flexural properties, are often reported on manufacturers' marketing data sheets.

Compression Strength and Modulus: Because of the relative simplicity of testing in tension the elastic modulus of a material is usually measured and reported as a tension value. For design purposes it often is necessary to know the stress–strain relationship for compression loading. With most elastic materials at low stress levels, the tensile and compressive stress–strain curves are nearly equivalent. At higher stress levels, the compressive strain is less than the tensile strain. Unlike tensile loading, which usually results in a clear-cut failure, stressing in compression produces a slow and indefinite yielding that seldom leads to failure. Because of this phenomenon, compressive strength is customarily expressed as the stress in $lb_f/in.^2$ (Pa) required to deform a standard plastics test specimen to a certain strain. Compression modulus is not always reported, because defining a stress at a given strain is equivalent to reporting a secant modulus. If a compression modulus is given, it is usually an initial modulus.

Bending Strength and Modulus: When material of rectangular cross-section is bent, it is apparent that one surface is stretched in tension and the other side is compressed. Within the material is a line or plane of zero stress called the neutral axis. Simple beam bending theory makes the following assumptions: that the beam is initially straight, unstressed, and symmetric; the material is linearly elastic, homogeneous, and isotropic; the proportional limit is not exceeded; Young's modulus for the material is the same in tension and compression; and all deflections are small so that planar cross-sections remain planar before and after bending.

In these conditions, the formula for bending stress σ is

$$\sigma = \frac{3FL}{2bh^2} \tag{11}$$

the formula for bending or flexural modulus E is

$$E = \frac{FL^3}{4bh^3Y} \tag{12}$$

and the formula for deflection Y is

$$Y = \frac{FL^3}{4Ebh^3} \tag{13}$$

where F, the force in pounds, is centered between the specimen support points, L is the distance in inches between the support points, b and h are the width and thickness of the test specimen in inches, and Y is the deflection in inches at the central load point.

Using the preceding relationships, the flexural strength and flexural modulus (of elasticity) for any material can be determined in the laboratory. The flexural modulus reported is usually the initial modulus from the load deflection curve. Most plastics parts must be analyzed in bending, so use of flexural values should give more accurate results than corresponding tensile values.

Rate Dependence of Mechanical Properties: Tensile and flexural data in manufacturers' literature are measured at specific displacement rates. These rates are usually not consistent with the loading environment encountered in use of the product. The same plastics material, under differing rates or in other environmental conditions, can produce different stress–strain curves. Designers should be aware of the loading rates in specific applica-

Copyright 2004, Industrial Press, Inc., New York, NY

tions and request the appropriate data. End-use testing must always be considered, but particularly when adequate data are not available.

Time-Related Mechanical Properties.— Mechanical properties discussed previously were related to loads applied gradually and applied for short periods. Long-term and very short-term loading may give somewhat different results. With high-performance thermoplastics it is important to consider creep, impact, fatigue, and related issues. Even the best laboratory test methods do not always predict structural response of production parts accurately, and other factors may also affect results.

Creep is defined as increasing strain over time in the presence of a constant stress when deformation continues without increases in load or stress. The rate of creep for a given material depends on applied stress, temperature, and time.

Creep behavior of a material is important, and a crucial issue with plastics, where parts are to be subjected to loads for extended periods and where the maximum deflection is critical. To determine the creep behavior, test samples may be loaded in tension, compression, or flexure in a constant-temperature environment. Under constant loads, deflection is recorded at regular intervals over suitable periods. Results are generally obtained for four or more stress levels and recorded as creep curves of strain versus time on a logarithmic scale. In general, crystalline materials have lower creep rates than amorphous plastics. Glass reinforcement generally improves the creep resistance.

Apparent or Creep Modulus: If the deflection of a part subjected to continuous loading is calculated by using the modulus of elasticity E, results are likely to be inaccurate because the effects of creep have not been considered. If the stress level and temperature are known and creep curves are available for the temperature in question, an apparent or creep modulus E_{app} can be calculated from the creep curves by the formula: $E_{app} = \sigma/\epsilon_c$, where σ is the calculated stress level and ϵ_c is the strain from the creep curve at the expected time and temperature.

This value E_{app} can be used instead of E in predicting the maximum deflection, using the methods described subsequently (page 602).

Manufacturers' data often include curves of creep modulus (or log creep modulus) versus log time at either constant stress or constant strain, derived from creep data. This information may also be provided as tables of values at constant stress and temperature for various time periods. Some manufacturers provide creep data in the form of creep modulus figures rather than curves.

Creep rupture data are obtained in the same manner as creep data except that higher stresses are used and time is measured to failure. Such failures may be brittle or ductile with some degree of necking. Results are generally plotted as log stress versus log time to failure.

Stress relaxation occurs when plastics parts are assembled into a permanent deflected condition, as in a press fit, a bolted assembly, or some plastics springs. Under constant strain over a period of time, the stress level decreases due to the same internal molecular movement that produces creep. Stress relaxation is important with such applications as bolt preloading and springs, where loading must be maintained.The relaxation can be assessed by applying a fixed strain to a sample and measuring the load over time. A relaxation modulus similar to the creep modulus can be derived from the relaxation data. Relaxation data are not as readily available as creep data, but the decrease in load due to stress relaxation can be approximated by using the creep modulus E_{app} calculated from the creep curves.

Plastics parts often fail due to imposition of excessive fixed strains over extended periods of time, for example, a plastics tube that is a press fit over a steel shaft. No relaxation rupture equivalent to creep rupture exists, so for initial design purposes a strain limit of 20 per cent of the strain at the yield point or yield strength is suggested for high-elongation plas-

Copyright 2004, Industrial Press, Inc., New York, NY

tics. For low-elongation brittle plastics that have no yield point, 20 per cent of the elongation at break is also recommended. These figures should be regarded only as guidelines for development of initial design concepts; prototype parts should be thoroughly tested under end-use conditions to confirm the suitability of the design. Higher or lower property limits may also be indicated in manufacturers' data on specific materials.

Extrapolating creep and relaxation data must be done with caution. When creep and relaxation data are plotted as log property against log time, the curves are generally less pronounced, facilitating extrapolation. This procedure is common practice, particularly with creep modulus and creep rupture data. Extrapolation should not exceed one unit of log time, and the strain limit of 20 per cent of the yield or ultimate strength mentioned above should not be exceeded.

Impact loading describes a situation in which a load is imposed rapidly. Any moving body has kinetic energy and when the motion is stopped by a collision, the energy is dissipated. Ability of a plastics part to absorb energy is determined by the shape, size, thickness, and type of material. Impact testing methods now available do not provide designers with information that can be used analytically. The tests can be used for comparing relative notch sensitivity or relative impact resistance, so can be useful in choosing a series of materials to be evaluated for an application or in grading materials within a series.

Impact testing by the Izod and Charpy methods, in which a pendulum arm is swung from a certain height to impact a notched test specimen, is the most widely used for measuring impact strength. Impact with the test specimen reduces the energy remaining in the arm, and this energy loss is recorded in ft-lb (J). The value of such tests is that they permit comparison of the relative notch toughness of two or more materials under specific conditions.

Tensile impact tests mount the test specimen on the swinging arm. Attached to the test specimen is a cross piece that is arrested by a notched anvil as the bar swings down, allowing the energy stored in the arm to break the specimen under tension as it passes through the notch. Another impact test used for plastics allows a weighted, round-ended cylindrical "dart" to fall on a flat disk of the plastics to be tested. This test is good for ranking materials because it represents conditions that are encountered by actual parts in certain applications.

Fatigue tests are designed to measure the relative ability of plastics materials to withstand repeated stresses or other cyclic phenomena. For example, a snap-action, or snap-fit latch that is continually opened and closed, a gear tooth, a bearing, a structural component subject to vibration or to repeated impacts. Cyclic loading can cause mechanical deterioration and progressive fracture, leading to failure in service. Typical fatigue tests are carried out on machines designed to subject a cantilever test piece to reversing flexural loading cycles at different stress levels. Numbers of cycles before failure are recorded for each stress level. Data are normally presented in plots of log stress versus log cycles called *S-N* curves for specific cycle rates and environmental temperatures. With thermoplastics materials there is the added complication that heat built up by the frequency of the cyclic stress may contribute to failure. Significantly different *S-N* curves can be produced for the same materials by testing at different frequencies, mean stresses, waveforms, and methods, such as testing in tension rather than in bending. Testing usually cannot reproduce the conditions under which components will work. Only tests on the end product can determine whether the design is suitable for the purpose to be served.

Thermal Properties.— Melting temperatures of crystalline thermoplastics are sharp and clearly defined, but amorphous and liquid crystalline materials soften and become more fluid over wider temperature ranges. Melting points have greater significance in molding and assembly operations than in product design, which usually deals with the product's temperatures.

Copyright 2004, Industrial Press, Inc., New York, NY

Glass transition temperature is a level at which a plastics material undergoes a significant change in properties. Below this temperature T_g, the material has a stiff, glassy, brittle response to loads. Above T_g the material has a more ductile, rubbery response.

Vicat softening point is the temperature at which a small, circular, lightly gravity-loaded, heated probe penetrates a specific distance into a thermoplastics test specimen. This test measures the ability of a thermoplastics material to withstand a short-term contact with a heated surface, and is most useful for crystalline plastics. Amorphous thermoplastics materials tend to creep during the test, which reduces its usefulness for such materials.

Deflection temperature under load (DTUL) is the temperature at which a test bar of 0.5 in. thickness, loaded to a specified bending stress, will deflect by 0.010 in. This test is run at bending stresses of 66 $lb_f/in.^2$ or 264 $lb_f/in.^2$ or both. The value obtained is sometimes referred to as the heat distortion temperature (HDT), and is an indication of the ability of the material to perform at elevated temperatures under load. Both stress and deflection for a specific design of test bar are given so the test may be regarded as establishing the temperature at which the flexural modulus is reduced to particular values, 35,200 $lb_f/in.^2$ at 66 $lb_f/in.^2$ stress, and 140,000 $lb_f/in.^2$ at 264 $lb_f/in.^2$ stress.

Linear thermal expansion: Like metals, thermoplastic materials expand when heated and contract when cooled. For a given temperature range, most plastics change dimensions much more than metals. The coefficient of linear thermal expansion (CLTE) is the ratio of the change in a linear dimension to the original dimension for a unit change of temperature and is expressed as in/in/degree F, or cm/cm/degree C. Typical average values for common materials are shown in the table on page 402. These values do not take account of grades, molding conditions, wall thickness, or direction of flow in molding.

Thermal conductivity is the rate at which a material conducts heat energy along its length or through its thickness.

Aging at elevated temperatures may affect physical, mechanical, electrical, or thermal properties of plastics materials. Data from tests on specimens stored at specific temperatures for suitable periods are presented as plots of properties versus aging time at various temperatures, and may be used as an indication of thermal stability of the material.

Temperature index is a rating by Underwriters Laboratories (UL) of electrical and mechanical properties (with and without effects of impacts) of plastics materials used in electrical equipment for certain continuous operating conditions.

Flammability ratings also are produced by Underwriters Laboratories. UL tests measure the ability to continue burning after a flame is removed, and the percentage of oxygen needed for the material to continue burning. Other tests measure combustibility, ignition temperatures, and smoke generation.

Effect of Temperature on Mechanical Properties.— The inverse relationship between strain rate and temperature must be kept in mind when designing with plastics materials. Stress/strain curves for tests performed with one strain rate at several temperatures are similar to those for tests with one temperature and several strain rates. Therefore, very high strain rates and very low temperatures produce similar responses in materials. Conversely, the effects of very low strain rates, that is, creep effects, can be determined more quickly by testing at elevated temperatures. Testing at temperatures near or above the highest values expected in everyday use of a product helps the designer estimate long-term performance of components.

Strength, modulus, and elongation behavior are similar for tensile, compressive, flexural, and shear properties. Generally, strength and modulus decrease with increasing temperature. The effect of temperature increases is shown by the curves in Fig. 6 for crystalline and amorphous materials, where a gradual drop in modulus is seen as the glass transition temperature T_g is approached. Above the glass transition temperature, amorphous materi-

Copyright 2004, Industrial Press, Inc., New York, NY

als have a rapid loss of modulus, and even with glass-fiber reinforcement they display a rapid drop in modulus above the glass transition temperature. Crystalline materials maintain a significant usable modulus at temperatures approaching the crystalline melting point, and glass-fiber reinforcement can significantly improve the modulus of crystalline materials between the glass transition and melting temperatures. Generally, strength versus temperature curves are similar to modulus curves and elongation increases with rising temperatures.



Fig. 6. Modulus Behavior of Crystalline and Amorphous Plastics Showing T_g and Melt Temperatures and the Effect of Reinforcement on Deflection Temperature Under Load (DTUL)

Isochronous stress and isometric stress curves are taken from measurements made at fixed temperatures, although sometimes curves are available for other-than-ambient temperatures. Creep rupture and apparent modulus curves also are often plotted against the log of time, with temperature as a parameter. Refer to sections on creep, creep modulus, and creep rupture beginning on page 602.

As temperatures drop significantly below ambient, most plastics materials lose much of their room temperature impact strength, although a few materials show only a gradual decrease. Plastics reinforced with long glass fibers have relatively high Izod impact values at room temperature, and retain these values at –40 degrees F (– 40 degrees C).

Electrical Properties.— The most notable electrical property of plastics is that they are good insulators, but there are many other electrical properties that must be considered in plastics part design.

Conductivity in solids depends on the availability and mobility of movable charge carriers within the material. Metals are good conductors because the metal atom has a loosely held, outermost electron, and the close proximity of the atoms allows these outer electrons to break free and move within the lattice structure. These free electrons give metals the ability to conduct large currents, even at low voltages. Outer electrons in materials such as glass, porcelain, and plastics are tightly bound to the atoms or molecules so there are no free electrons. Electrical current cannot be conducted and the materials act as insulators.

Volume resistivity is the electrical resistance of a material when a current is applied to it. The resistance is measured in ohm-cm. Materials having values above 10^8 ohm-cm are considered to be insulators, and materials with values between 10^8 and 10^3 ohm-cm are considered to be partial conductors. Most plastics have volume resistivity in the range of 10^{12} to 10^{18} ohm-cm.

Surface resistivity is a measure of the susceptibility of a material to surface contamination, particularly moisture. The tests use electrodes that are placed on the same side of the material.

Copyright 2004, Industrial Press, Inc., New York, NY

Dielectric strength is a measure of the voltage required to cause an insulator to break down and allow an electric current to pass and is expressed in volts per 0.001 in. of thickness. Variables that may affect test results include temperature, sample thickness and condition, rate of voltage increase and duration of test, sample contamination, and internal voids.

Dielectric constant or permittivity is a dimensionless constant that indicates how easily a material can become polarized by imposition of an electrical field on an insulator. Reversal of the direction of flow of the current results in reversal of the polarization. The dielectric constant is the ratio of the permittivity of the material in normal ambient conditions to the permittivity of a vacuum. Permittivity is important when plastics are used as insulating materials in high-frequency electrical apparatus. Changes in temperature, moisture levels, electrical frequency, and part thickness may affect the dielectric constant.

Heat dissipation factor is a measure of heat energy dissipated by rapidly repeated reversals of polarization, as with an alternating current. The dissipation factor may also be thought of as the ratio of heat energy lost compared to that transmitted at a given frequency, often 1 MHz (10^6 cycles/sec). Some dielectric constants and heat dissipation factor values are shown in Table 1.

Arc resistance is the length of time required for an electric arc imposed on the surface of an insulating material to develop a conductive path. Materials that resist such a development are preferred for parts of switchgear and other high-voltage apparatus. Tests are used mostly for thermosetting materials because conductive paths can be formed on such materials from the decomposition products resulting from heating by an electric arc.

Table 1. Typical Values of Dielectric Constants and Heat Dissipation Factors for Various Thermoplastics at Room Temperature

Material	Dielectric Constant	Heat Dissipation Factor	Material	Dielectric Constant	Heat Dissipation Factor
Acetal	3.7–3.9	0.001–0.007	Polypropylene	2.3–2.9	0.003–0.014
Acrylic	2.1–3.9	0.001–0.060	Polysulfone	2.7–3.8	0.0008–0.009
ABS	2.9–3.4	0.006–0.021	Modified PPO	2.4–3.1	0.0002–0.005
Nylon 6/6	3.1–8.3	0.006–0.190	Polyphenylene sulfide	2.9–4.5	0.001–0.002
Polycarbonate	2.9–3.8	0.0006–0.026	Polyarylate	2.6–3.1	0.001–0.022
TP Polyester	3.0–4.5	0.0012–0.022	Liquid crystal	3.7–10	0.010–0.060

Comparative tracking index (CTI) is another UL test that is similar to the arc resistance test except that the surface to be tested is precoated with an ammonium chloride electrolyte. The test measures the voltage required to cause a conductive path to form between the electrodes, and indicates the arc resistance of a contaminated surface, often found in electrical and electronic equipment.

End-Use Environmental Considerations.— The environment that will be encountered by the product is a prime consideration at the design stage. Problems with cracking, crazing, discoloration, loss of properties, melting, or dissolving can be encountered in the presence of high or low temperatures, chemical substances, energy sources, and radiation. Plastics components also are often subjected to processing, assembly, finishing, and cleaning operations before reaching their ultimate environment.

The stress level in the plastics product greatly affects performance. Generally, increased stress levels resulting from injection molding, forming, assembly work, and end-use forces reduce resistance to environmental factors. Although many plastics are hygroscopic and absorption of water results in dimensional and property changes, plastics are widely accepted because of their relative compatibility with the environment compared with metals. Some chemicals attack the polymer chain directly by reaction, resulting in a progres-

Copyright 2004, Industrial Press, Inc., New York, NY

sive lowering of the molecular weight of the polymer and changes in the short-term mechanical properties. Others dissolve the material, although high-molecular-weight plastics dissolve very slowly. Swelling, changes in weight and dimensions, and loss of properties are evidence of solvation.

Plasticization may result if the chemical is miscible with the polymer, resulting in loss of strength, stiffness, and creep resistance, and increased impact resistance. The material may swell and warp due to relaxation of molded-in stresses. Environmental stress cracking may cause catastrophic failure when plastics are stressed, even when the product appears to be unaffected by exposure to a chemical.

Chemical compatibility data are obtained from standard test bars exposed to or placed in the chemical of study and tested as previously described for such properties as tensile strength, flexural modulus, dimensional change, weight, and discoloration. Chemical resistance from some commonly used thermoplastics materials are shown in Table 2, but are only general guidelines and cannot substitute for tests on the end product. More extensive tests expose samples to a chemical in the presence of fixed stress or fixed strain distribution along its length, followed by examination for the stress or strain location at which damage begins.

The preceding tests may provide data about chemical compatibility but do not generate reliable information on performance properties for design purposes. The only test that provides such information is the creep rupture test, conducted at appropriate temperatures in the environment that will be encountered by the product, preferably on prototype parts. Plastics are degraded to varying degrees by ultraviolet light, which causes fading, chalking, and embrittlement. Plastics that will resist the action of ultraviolet rays are available on the market.

Design Analysis

Structural Analysis.— Even the simplest plastics parts may be subjected to stresses caused by assembly, handling, temperature variations, and other environmental effects. Simple analysis using information in *Moment of Inertia* starting on page 236 and *Beam Calculations* on page 260 can be used to make sure that newly designed parts can withstand these stresses. These methods may also be used for product improvement, cost reduction, and failure analysis of existing parts.

Safety Factors: In setting safety factors for plastics parts there are no hard and fast rules. The most important consideration is the consequence of failure. For example, a little extra deflection in an outside wall or a crack in one of six internal screw bosses may not cause much concern, but the failure of a pressure vessel or water valve might have serious safety or product liability implications. Tests should be run on actual parts at the most extreme operating conditions that could possibly be encountered before any product is marketed. For example, maximum working load should be applied at the maximum temperature and in the presence of any chemicals that might be encountered in service. Loads, temperatures, and chemicals to which a product may be exposed prior to its end use also should be investigated. Impact loading tests should be performed at the lowest temperature expected, including during assembly and shipping. Effects of variations in resin lots and molding conditions must also be considered.

Failures in testing of preproduction lots often can be corrected by increasing the wall thickness, using ribs or gussets, and eliminating stress concentrations. Changing the material to another grade of the same resin or to a different plastics with more suitable mechanical properties is another possible solution. Reviews of product data and discussions with experienced engineers suggest the design stresses shown in Table 3 are suitable for use with the structural analysis information indicated above and the equations presented here, for preliminary design analysis and evaluating general product dimensions. Products designed under these guidelines must be thoroughly tested before being marketed.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Chemical Resistance of Various Materials by Chemical Classes

Polyarylate																			Polycarbonate
Polyphenylene Sulfide*	●	●	●	●	●	●	●	●		●									Polysulfone*
Liquid Crystal Polymer*								●		●			●	●	●	●	●	●	Modified Polyphenylene Oxide
Polyester Elastomer	●	●	●	●	●	●	●	●		●			●						Polypropylene
Thermoplastic Polyester (PET)							●	●		●			●		●	●	●	●	ABS
Thermoplastic Polyester (PBT)	●	●	●	●			●	●		●			●		●				316 Stainless Steel
Nylon 6/6				●			●	●		●			●		●		●	●	Carbon Steel
Acetal Homopolymer	●	●		●			●	●		●			●		●		●		Aluminum
Acetal Copolymer		●		●			●	●		●			●		●				
ACIDS AND BASES																			
Acids, weak	A	B	C	A	A	A	A	A	A	A	B	A	A	A	A	A	C		Dilute mineral acids
Acids, strong	C	C	C	B	—	C	B	A	—	C	C	—	A	A	B	C	C		Concentrated mineral acids
Bases, weak	A	C	A	B	B	A	B	A	—	C	A	A	A	A	A	B	C		Dilute sodium hydroxide
Bases, strong	A	C	C	—	—	B	C	A	—	C	A	—	A	A	B	B	C		Concentrated sodium hydroxide
Acids, organic, weak	A	B	C	A	A	A	A	A	A	A	B	A	A	A	A	C	C		Acetic acid, vinegar
Acids, organic, strong	C	C	C	B	—	C	B	A	—	C	C	A	A	A	B	C	C		Trichloroacetic acid
AUTOMOTIVE																			
Automotive, fuel	A	A	A	A	A	A	A	A	C	C	A	C	C	A	A	A	A		
Automotive, lubricants	A	A	A	A	A	A	A	A	C	C	A	A	A	A	A	B	A		
Automotive, hydraulic	A	A	—	A	A	—	A	A	C	C	C	A	A	A	—	—	—		
SOLVENTS																			
Aliphatic hydrocarbons	A	A	A	A	A	A	A	A	A	A	A	B	C	A	A	A	A		Heptane, hexane
Aliphatic hydrocarbons, halogenated	A	B	C	B	B	A	A	A	C	C	C	—	—	—	B	B	B		Ethylene chloride, chloroform
Alcohols	A	A	B	A	A	A	A	A	A	A	A	A	A	A	A	A	B		Ethanol, cyclohexanol
Aldehydes	A	A	A	A	B	B	A	A	—	C	B	—	A	—	A	B	A		Acetaldehyde, formaldehyde
Amines	—	—	—	—	—	—	C	B	—	C	C	—	A	—	A	B	B		Aniline, triethanolamine
Aromatic hydrocarbons	A	B	A	A	B	B	A	A	C	C	C	C	C	A	A	A			Toluene, xylene, naphtha
Aromatic hydrocarbons, halogenated	—	—	—	—	—	C	—	A	C	C	C	—	—	—	A	A	A		Chlorobenzene
Aromatic, hydroxy	C	C	C	C	—	C	A	A	—	C	C	—	A	—	B	C	A		Phenol
Esters	B	B	A	B	B	B	A	A	C	C	C	—	C	—	B	B	B		Ethyl acetate, dioctyl phthalate
Ethers	B	—	A	A	—	—	—	A	—	A	B	—	C	—	A	A	A		Butyl ether, diethyl ether
Ketones	B	B	A	B	B	B	A	A	C	C	C	—	B	C	A	A	A		Methyl ethyl ketone, acetone
MISCELLANEOUS																			
Detergents	A	—	A	—	B	—	—	A	A	A	—	B	A	—	A	A	B		Laundry and dishwashing detergents, soaps
Inorganic salts	B	B	B	—	A	—	—	A	—	A	—	—	A	A	B	B	B		Zinc chloride, cupric sulfate
Oxidizing agents, strong	C	C	C	—	C	—	B	B	—	C	—	—	A	—	C	C	C		30% hydrogen peroxide, bromine (wet)
Oxidizing agents, weak	C	C	C	A	—	A	A	A	—	A	—	A	A	A	B	C	A		Sodium hypochlorite solution
Water, ambient	A	A	B	A	A	A	A	A	A	A	A	A	A	—	A	C	B		
Water, hot	B	C	B	C	C	B	A	A	—	C	—	A	C	—	A	C	B		
Water, steam	C	C	C	C	C	C	B	A	—	C	—	—	C	—	A	C	—		

This information is presented for instructional purposes and is not intended for design. The data were extracted from numerous sources making consistent rating assignments difficult. Furthermore, the response of any given material to specific chemicals in any one class can vary significantly. Indeed, during the preparation of the table, the effect on one plastics of various chemicals in the same category ranged from essentially no effect to total dissolution. Therefore, an "A" rating for a particular plastics exposed to a particular class of chemicals should not be interpreted as applying to all chemicals in that class. The rating simply means that for the chemicals in that class found in the literature reviewed, the rating was generally an "A." There may be other chemicals in the same class for which the rating would be "C." Finally, the typical chemicals listed do not necessarily correspond to the ones on which the individual ratings are based.

A—minimal effect; B—some effect; C—generally not recommended.

Room temperature except for hot water, steam, and materials marked with a * ≡ 200°. Generally, extended exposure (more than a week) data were used.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Design Stresses for Preliminary Part Designs Expressed as a Percentage of Manufacturers' Data Sheet Strength Values

	Failure Not Critical	Failure Critical
Intermittent (Nonfatigue) loading	25–50	10–25
Continuous loading	10–25	5–10

Failure Criteria: Setting of failure criteria is beyond the scope of this section, which is intended to give only basic general information on plastics. Designers who wish to rationalize complex stress states and analyses might investigate the maximum shear theory of failure (otherwise known as Coulomb or Tresca theory). It is further suggested that the shear strength be taken as the manufacturer's published shear strength, or half the tensile strength, whichever is lower. Better still, use half the stress at the elastic limit, if known.

Pressure Vessels: The most common plastics pressure vessel takes the form of a tube with internal pressure. In selecting a wall thickness for the tube, it is convenient to use the thin-wall hoop stress equation:

$$\text{hoop stress } \sigma = \frac{Pd}{2t} \tag{14}$$

where P = the uniform internal pressure in the tube, d = inside diameter of the tube, and t = the tube wall thickness. This equation is reasonably accurate for tubes where the wall thickness is less than 0.1 of the inside diameter of the tube. As the wall thickness increases, the error becomes quite large.

For thick-walled tubes the maximum hoop stress on the wall surface inside the tube can be calculated from

$$\text{hoop stress } \sigma = P\frac{1+R}{1-R} \tag{15}$$

where $R = (d_i/d_o)^2$, and d_i and d_o are the inside and outside diameters of the tube, respectively.

Press Fits: Press fits are used widely in assembly work for speed and convenience, although they sometimes are unsatisfactory with thermoplastics parts. Common applications are to a plastics hub or boss accepting a plastics or metal shaft or pin. Forcing the pin into the hole expands the hub, creating a tensile or hoop stress.

If the interference is too great, very high strain and stress develop and the plastics part will: a) fail immediately by developing a crack parallel to the hub axis to relieve the stress, a typical hoop stress failure; b) survive assembly but fail prematurely due to creep rupture caused by the high induced-stress levels; and c) undergo stress relaxation sufficient to reduce the stress to a level that can be sustained.

For a typical press fit, the allowable design stress depends on the particular plastics material, temperature, and other environmental considerations. Hoop stress equations for such a design make use of a geometry factor γ:

$$\gamma = \frac{1+(d_s/d_o)^2}{1-(d_s/d_o)^2} \tag{16}$$

where d_s = diameter of the pin to be inserted and d_o = outside diameter of the boss.

When both the shaft and the hub are of the same, or essentially the same, materials, the hoop stress σ, given the diametral interference, $i = d_s - d_i$, is

$$\sigma = \frac{i}{d_s}E_p\frac{\gamma}{\gamma+1} \tag{17}$$

Copyright 2004, Industrial Press, Inc., New York, NY

and the allowable interference i_a, given the permissible design stress σ_a, is

$$i_a = d_s \frac{\sigma_a}{E_p} \frac{\gamma + 1}{\gamma} \tag{18}$$

When the shaft is metal and the hub is plastics, the hoop stress, given i, is obtained from

$$\sigma = \frac{i}{d_s} E_p \frac{\gamma}{\gamma + \nu_p} \tag{19}$$

and the allowable interference i_a, given the permissible design stress for plastics σ_a, is

$$i_a = d_s \frac{\sigma_a}{E_p} \frac{\gamma + \nu_p}{\gamma} \tag{20}$$

where E_p = modulus of elasticity of plastics and ν_p = Poisson's ratio for plastics.

Pipe Threads: Pipe threads on plastics pipes and other parts used in plastics plumbing and pneumatic assemblies require only hand tight assembly to effect a good seat, especially if a compatible sealant tape or compound is used. Assembling a tapered male pipe thread into a mating female thread in a plastics part is analogous to driving a cone into a round hole and may result in a split boss. Sometimes straight threads and an O-ring seal can avoid the need for pipe threads. When pipe threads must be used, torque control is essential.

When mating metal to plastics pipe threads, the threaded plastics component should be the male member, so that the plastics are in compression. If torque can be controlled during assembly, use fluoroplastics tape on female plastics pipe threads. If torque cannot be controlled, consider using an external hoop ring, either pressed on or molded in. Do not design flats into plastics parts for assembly purposes, because they will encourage overtightening. If some provision for improved gripping must be made, use wings or a textured surface. An approximate formula for the hoop stress σ produced in a plastics boss with internal pipe threads is

$$\sigma = \frac{3T}{tdL} \tag{21}$$

where T = torque in in.-lb, t = wall thickness of the plastics boss in in., d = pipe outside diameter in in., and L = length of thread engagement in in.

This equation assumes certain geometric relationships and a coefficient of friction of 0.15. If compatible thread lubricants are used during assembly, the torque must be reduced. To ensure safety and reliability, all threaded assemblies must be subjected to long-term testing under operating pressures, temperatures, and stresses caused by installation procedures exceeding those likely to be encountered in service.

Thermal Stresses.— When materials with different coefficients of thermal expansion are bolted, riveted, bonded, crimped, pressed, welded, or fastened by any method that prevents relative movement between the parts, there is potential for thermal stress to exist. Typical examples are joining of nonreinforced thermoplastics parts with materials such as metals, glass, or ceramics that usually have much lower coefficients of thermal expansion. The basic relationship for thermal expansion is

$$\Delta L = \alpha L \Delta T \tag{22}$$

where ΔL = change in length, α = coefficient of thermal expansion (see page 402), L = linear dimension under consideration (including hole diameters), and ΔT = temperature change.

If the plastics component is constrained so that it cannot expand or contract, the strain $\in_T$, induced by a temperature change, is calculated by

Copyright 2004, Industrial Press, Inc., New York, NY

$$\epsilon_T = \frac{\Delta L}{L} = \alpha \Delta T \tag{23}$$

The stress can then be calculated by multiplying the strain ϵ_T by the tensile modulus of the material at the temperature involved. A typical example is of a plastics part to be mounted to a metal part, such as a window in a housing. Both components expand with changes in temperature. The plastics imposes insignificant load to the metal but considerable stress is generated in the plastics. For such an example, the approximate thermal stress σ_T in the plastics is given by

$$\sigma_T = (\alpha_m - \alpha_p) E_p \Delta T \tag{24}$$

where α_m = coefficient of thermal expansion of the metal, α_p = coefficient of thermal expansion of the plastics, and E_p = tensile modulus of the plastics at the temperature involved.

Other equations for thermal expansion in various situations are shown in Fig. 7.

Most plastics expand more than metals with temperature increases and their modulus drops. The result is a compressive load in the plastics that often results in buckling. Conversely, as the temperature drops, the plastics shrinks more than the metal and develops an increased tensile modulus. These conditions can cause tensile rupture of the plastics part. Clearances around fasteners, warpage, creep, or failure, or yield of adhesives tend to relieve the thermal stress. Allowances must be made for temperature changes, especially with large parts subjected to wide variations. Provision is often made for relative motion ΔL_{rel}, between two materials, as illustrated in Fig. 7:

$$\Delta L_{rel} = (\alpha_p - \alpha_m) L \Delta T \tag{25}$$



Fig. 7. Thermal Expansion Equations for Various Combinations of Materials and Situations

Design for Injection Moldings.— Injection molding uses equipment similar to that for die casting, in that a precision steel mold is clamped shut, and melted material (here, plasticized plastics) is forced into the cavity between the mold components. The pelletized plastics material is fed into a heated chamber, or barrel, by a large, slowly rotating screw,

Copyright 2004, Industrial Press, Inc., New York, NY

and is melted. When a sufficient quantity to fill the cavity has been prepared, the screw is moved axially under high pressure to force the material into the cavity. The mold has channels through which coolant is circulated to remove heat and to chill the plastics. When the plastics has cooled sufficiently, the mold is unclamped and opened, and the molding is forced out by strategically located ejectors. During cooling and removal, material for the next part is plasticized within the barrel, ready for the cycle to be repeated.

Product analysis provides a good approach to design for plastics molding. A basic principle of plastics molding design, when moldings are being substituted for parts made by other means, is to incorporate as many functions into the molding as possible, especially those requiring nuts, bolts, and washers, for instance. Material should be selected that fulfills the maximum requirements, such as the functions mentioned, as well as insulation from the passage of heat or electricity, and allows use of the minimum amount of material.

Important material selection criteria include ability to withstand the heat of assembly, finishing, shipping, operating, and heat from internal sources. Effects of chemicals in the environment and approvals of government and other agencies also should be checked. Many such approvals specify wall thicknesses, color additives, fillers, and operating temperatures. Plans for assembly by bonding may dictate use of certain materials, and the question of painting, plating, or other surface coatings must be considered. Cost of candidate materials compared with the alternatives must be weighed, using the formula for cost per $in.^3 = 0.0361 \times$ specific gravity $\times$ material cost per lb. Material cost required for a part is obtained by multiplying the cost per $in.^3$ by the part volume. A rough estimate of likely part cost is double the cost of material for the part.

Wall Thicknesses: The thickness of material used in a plastics molding is of the greatest importance, and should be settled before the mold is made, since modifications are costly. In general, wall thicknesses should be kept as thin as practical and as uniform as possible. Ideally, the flow of molding material should be so arranged that it moves through thicker sections into thinner ones rather than the reverse. Geometric, structural, or functional needs may prevent ideal design, but examination of alternatives can often prevent problems from arising. Most injection-molded plastics parts range in thickness from $\frac{1}{32}$ to $\frac{3}{16}$ in. (0.8 to 4.8 mm) with the dimensions within that range related to the total size of the part.

Impact Resistance: The impact resistance of a plastics part is directly related to its ability to absorb mechanical energy without fracture or deformation, and this ability depends on the material properties and the part geometry. Increasing wall thickness may improve the impact resistance but may also hurt impact resistance by making the part too stiff so that it is unable to deflect and distribute the force.



Fig. 8. Typical Spiral-Flow Curves for (1) Nylon 6/6, (2) Polyester Thermoplastics PBT, Liquid-Crystal-Glass-Reinforced, and Polyphenylene-Sulfide-Glass-Reinforced, (3) Acetal Copolymer, and (4) PBT-Glass-Reinforced Plastics Materials

Copyright 2004, Industrial Press, Inc., New York, NY

Design engineers must also have some knowledge of mold design and, in determining wall thickness, should consider the ability of plastics to flow into the narrow mold channels. This flowability depends on temperature and pressure to some extent, but varies for different materials, as shown in Fig. 8.

Table 4 shows typical nominal wall thicknesses for various types of thermoplastics.

Table 4. Typical Nominal Wall Thicknesses for Various Classes of Thermoplastics

Thermoplastics Group	Typical Working Range (in.)	Thermoplastics Group	Typical Working Range (in.)
Acrylonitrile-butadiene-styrene (ABS)	0.045–0.140	Polyester elastomer	0.025–0.125
Acetal	0.030–0.120	Polyethylene	0.030–0.200
Acrylic	0.025–0.150	Polyphenylene sulfide	0.020–0.180
Liquid-crystal polymer	0.008–0.120	Polypropylene	0.025–0.150
Long-fiber-reinforced plastics	0.075–1.000	Polystyrene	0.035–0.150
Modified polyphenylene ether	0.045–0.140	Polysulfone	0.050–0.150
Nylon	0.010–0.115	Polyurethane	0.080–0.750
Polyarylate	0.045–0.150	Polyvinyl chloride (PVC)	0.040–0.150
Polycarbonate	0.040–0.150	Styrene-acrylonitrile (SAN)	0.035–0.150
Polyester	0.025–0.125	…	…

If the plastics part is to carry loads, load-bearing areas should be analyzed for stress and deflection. When stress or deflection is too high, solutions are to use ribs or contours to increase section modulus; to use a higher-strength, higher-modulus (fiber-reinforced) material; or to increase the wall thickness if it is not already too thick. Where space allows, adding or thickening ribs can increase structural integrity without thickening walls.

Equations (11), (12), and (13) can be related to formulas using the section modulus and moment of inertia on page 261, where Case 2, for (i), stress at the beam center is given by $\sigma = -Wl/4Z$.

On page 260, note that $Z = I \div$ distance from neutral axis to extreme fiber ($h \div 2$ in the plastics example). The rectangular beam section diagrammed on page 239 gives the equivalent of $I = bh^3/12$ for the rectangular section in the plastics example. Therefore,

$$Z = \frac{I}{h/2} = \frac{bh^3}{12} \times \frac{2}{h} = \frac{bh^2}{6}$$

In $\sigma = -Wl/4Z$, the (−) sign indicates that the beam is supported at the ends, so that the upper fibers are in compression and the lower fibers are in tension. Also, $W = F$ and $l = L$ in the respective equations, so that stress, $\sigma = FL/4(bh^2)/6$, and $\sigma = 3FL/2bh^2$.

To calculate (ii) maximum deflection Y at load, use $Y = Wl^3/48EI$ from page 261, where $W = F$, $l = L$, $E = E$, from Equation (12) and $I = bh^3/12$. Therefore,

$$Y = \frac{FL^3}{48E(bh^2/12)} = \frac{FL^3}{4Ebh^3}$$

As an example, assume that a beam as described in connection with Equations (11), (12), and (13) is 0.75 in. wide, with a constant wall thickness of 0.080 in., so that the cross-sectional area is 0.060 in.^{2}, and there is a central load W of 5 lb. Based on a bending or flexural modulus of 300,000 lb/in.^{2}, the maximum stress is calculated at 6250 lb/in.^{2} and the maximum deflection at 0.694 in. Both the stress and the deflection are too high, so a decision is made to add a rib measuring 0.040 in. thick by 0.400 in. deep, with a small draft of ½ degree per side, to reinforce the structure.

The equations on page 261, the drawing page 245 representing the ribbed section (neglecting radii), and the accompanying formulas, permit calculation of the maximum stress and deflection for the ribbed section.

Copyright 2004, Industrial Press, Inc., New York, NY

With the new cross-sectional area only slightly larger at 0.0746 in.^{2}, the calculated stress is reduced to 2270 lb/in.^{2}, and the deflection goes down to 0.026 in., which is acceptable for both the material and the application. To achieve the same result from a heavier beam would require a thickness of 0.239 in., tripling the weight of the beam and increasing molding difficulties. The rib adds only 25 percent to the total section weight.

Use of ribs allows the structural characteristics of a part to be tailored to suit its function, but ribs can cause warping and appearance problems, so are best avoided if they are not structurally necessary. If the first parts produced require strengthening, ribs can be added or thickened without high cost after the tool is finished because the work consists only of removing steel from the mold. In general, ribs should have a base thickness of about half the thickness of the adjacent wall, and be kept as thin as possible where they are positioned near faces that need to have a good appearance.

Where structural strength is more important than appearance, or when using materials that have low shrinkage, ribs can be made 75 or 100 per cent of the wall thickness. However, where the rib base joins the main molding there is an increase in thickness forming a heavy mass of material. Shrinkage of this mass can produce a cavity or void, a hollow area or sink, or can distort the molding. If the mass is very large, cooling time may be prolonged, leading to low output from the machine. Large masses of material in other parts of a molding are also best avoided. These problems can usually be addressed by good mold design.

Ribs need not be of constant height or width, and are often varied in proportions to suit the stress distribution in the part. All ribs should have a minimum of ½ degree of draft per side for ease of removal from the mold, and a minimum radius of 0.005 in. at the base to avoid stress-raising corners. Draft and thickness requirements will usually limit the height of the rib, which can be from 1.5 to 5 times the base thickness, and several evenly spaced ribs are generally preferred to a single large one. Smooth transitions should be made to other structural features such as bosses, walls, and pads.

Other ways to improve section properties include use of top-hat and corrugated sections, crowning or doming of some areas, and reinforcement with metal or other inserts that are placed in the mold before it is closed. To keep molded parts uniform in wall thickness, cores or projections may be provided in the mold to prevent a space being filled with molding material. Blind holes can be cored by pins that are supported on only one side of the mold and through holes by pins that pass through both sides. The length to width ratio should be kept as low as possible to prevent bending or breakage under the high pressures used in the injection molding process.

Agency approvals for resistance to flammability or heat, electrical properties, or other characteristics are usually based on specific wall thicknesses. These restrictions sometimes necessitate thicker walls than are required for structural strength purposes.

Draft: Most molded parts have features that must be cut into the mold perpendicular to the parting line. Removal of these parts from the mold is easier if they are tapered in the direction of mold opening. This taper is called draft in the line of draw or mold movement, and it allows the part to break free of the mold by creating a clearance as soon as the mold starts to open. Plastics materials shrink as they cool, so they grip mold projections very tightly and ejection can be difficult without sufficient draft. A draft of ½ degree on each side of a projection on the part is generally considered as a minimum, although up to 3 degrees per side is often used. Draft angles in degrees for various draw depths, and the resulting dimensional changes per side in inches (rounded to three decimal places), between the dimensions at the base and at the top of a projection are shown in Table 5. A rule of thumb is that 1 degree of draft yields 0.017 in. of difference in dimension per inch of draw length. Where a minimum of variation in wall thickness is needed to produce walls that are perpendicular to the direction of draw, the mold sometimes can be designed to produce parallel draft, as seen at the left in Table 5. The amount of draft required also depends

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Dimensional Changes for Various Combinations of Draft Angles and Draw Depths (Values to Nearest 0.001 in.)



Draw Depth (in)	Draft Angle (degrees)							
	1/8	1/4	1/2	1	2	3	4	5
1	0.002	0.004	0.009	0.017	0.035	0.052	0.070	0.080
2	0.004	0.009	0.017	0.035	0.070	0.105	0.140	0.175
3	0.007	0.013	0.026	0.053	0.105	0.157	0.210	0.263
4	0.009	0.018	0.035	0.070	0.140	0.210	0.280	0.350
5	0.011	0.022	0.044	0.088	0.175	0.262	0.350	0.437
6	0.013	0.026	0.052	0.105	0.209	0.314	0.420	0.525
7	0.015	0.031	0.061	0.123	0.244	0.367	0.490	0.612
8	0.018	0.035	0.070	0.140	0.279	0.419	0.559	0.700
9	0.020	0.040	0.078	0.158	0.314	0.472	0.629	0.787
10	0.022	0.044	0.087	0.175	0.349	0.524	0.699	0.875

on the surface finish of the mold walls. Any surface texture will increase the draft requirement by at least 1 degree per side for every 0.001 in. of texture depth.

Fillets, Radii, and Undercuts: Sharp corners are always to be avoided in injection-molded part designs because they represent points of stress concentration. Sharp corners in metal parts often are less important because the stresses are low compared with the strength of the material or because local yielding redistributes the loads. Sharp inside corners are particularly to be avoided in moldings because severe molded-in stresses are generated as the material shrinks onto the mold corner. Sharp corners also cause poor material flow patterns, reduced mechanical properties, and increased tool wear. Therefore, inside corner radii should be made equal to half the nominal wall thickness, with a minimum of 0.020 in. for parts subject to stress and 0.005 in. radius for stress-free parts. Outside corners should have a radius equal to the inside corner radius plus the wall thickness.

With an inside radius of half the wall thickness, a stress concentration of 1.5 is a reasonable assumption, and for radii down to 0.1 times the wall thickness, a stress concentration of 3 is likely. More information on stress concentrations is found in *Working Stress* on page 208, *Stress Concentration Factors* on page 209, and in the charts pages 209 through 212. A suitable value for q in Equation (8) on page 209, for plastics materials, is 1. Most plastics parts are so designed that they can be ejected parallel with the direction of mold parting. Complex parts with undercuts may require mold designs with cavity-forming projections that must move at an angle to the direction of opening. Between these two extremes lie such items as "windows," or simple openings in the side of a molding, which can be produced by the normal interaction of the two main parts of the mold.

Design for Assembly.— An advantage of the flexibility of plastics parts is that they can often be designed for assembly by means of molded-in snap-fit, press-fit, pop-on, and thread fasteners, so that no additional fasteners, adhesives, solvents, or special equipment is required. Improper assembly can be minimized, but tooling is often made more complex and disassembly may be difficult with these methods.

Copyright 2004, Industrial Press, Inc., New York, NY

Chemical bonding involves fixtures, substances, and safety equipment, is suited to applications that must be leak-tight, and does not create stresses. However, adhesives and solvents can be dangerous and preparation and cure times can be prolonged.

Thermal welding methods include ultrasonic, hot-plate, spin, induction, and radio-frequency energy and require special equipment. Thermal methods are also used for staking, swaging, and other heat deformation procedures. Materials must be compatible and have similar melting temperatures.

Mechanical fasteners designed for metals are generally usable with plastics, and there are many other fasteners designed specifically for plastics. Typical are bolts, self-tapping and thread-forming screws, rivets, threaded inserts, and spring clips. Care must be taken to avoid overstressing the parts. Creep can result in loss of preload in poorly designed systems.

Snap-fit designs are widely used, a typical application being to battery compartment covers. All snap-fit designs have a molded part that must flex like a spring, usually past a designed-in interference, then return to its unflexed position to hold the parts together. There must be sufficient holding power without exceeding the elastic or fatigue limits of the material. With the typical snap-fit designs in Fig. 9, beam equations can be used to calculate the maximum strain during assembly. If the stress is kept below the yield point of the material, the flexing finger returns to its original position.



Fig. 9. Snap-fit Designs for Cantilever Beams with Rectangular Cross Sections

With some materials the calculated bending stress can exceed the yield point stress considerably if the movement is done rapidly. In other words, the flexing finger passes through its maximum deflection or strain and the material does not respond as it should if the yield stress has been greatly exceeded. It is common to evaluate snap-ins by calculating strain instead of stress.

Dynamic strain ϵ, for the straight beam, is calculated from

$$\epsilon = \frac{3Yh_o}{2L^2} \tag{26}$$

Copyright 2004, Industrial Press, Inc., New York, NY

and for the tapered beam, from

$$\in = \frac{3Yh_o}{2L^2K} \tag{27}$$

The derived values should be compared with the permissible dynamic strain limits for the material in question, if known. A tapered finger provides more-uniform stress distribution and is recommended where possible. Sharp corners or structural discontinuities that will cause stress concentrations on fingers such as those shown must be avoided.

Snap-in arrangements usually require undercuts produced by a sliding core in the mold as shown in Fig. 10a. Sometimes the snap finger can be simply popped off when the mold is opened. An alternative to the sliding core is shown in Fig. 10b, which requires an opening in the molding at the base of the flexing finger. Other snap-in assembly techniques that take advantage of the flexibility of plastics are shown in Fig. 11.

Molded-in threads in holes usually are formed by cores that require some type of unscrewing or collapsing mechanism leading to tooling complications. External threads can often be molded by positioning them across the parting plane of the mold. Molding of threads finer than 28 to the inch is generally not practical.



Fig. 10. (left) (a) Arrangement for Molding an Undercut on the End of a Flexible Finger Using a Sliding Core; (b) With the Undercut Formed by a Mold Projection, the Sliding Core is Eliminated.



Fig. 11. (right) Examples of Snap-In and Snap-On Arrangements

Chemical bonding may use solvents or adhesives. Use of solvents is limited to compatible materials that can be dissolved by the same solvent. Chemical resistance of many plastics, especially crystalline materials, limits the use of this method. Safety precautions must also be considered in handling the solvents to protect workers and for solvent recovery.

Copyright 2004, Industrial Press, Inc., New York, NY

With adhesive bonding, a third adhesive substance is introduced at the interface between the parts to be joined. Adhesives can join plastics, metals, ceramics, glass, wood, or other bondable substances.

Typical adhesives used for thermoplastics are epoxies, acrylics, polyurethanes, phenolics, rubbers, polyesters, and vinyls. Cyanoacrylates are often used because of their rapid adhesion to many materials. Manufacturers' recommendations should be sought because many adhesives contain solvents that partially dissolve the plastics surfaces, giving improved adhesion. However, some adhesives can attack certain plastics, leading to deterioration and failure. The main disadvantages of adhesives are that they are slow, use long clamp times, require fixtures, and may involve special ovens or curing conditions. Surface preparation also may be difficult because the presence of grease, oil, mold-release material, or even a fingerprint can spoil a bond. Some materials may need surface preparation such as chemical etching or mechanical roughening to improve joint strength.

Ultrasonic welding is frequently used for joining parts of similar material, of small and medium size, is rapid, and can be automated. High-frequency (20–40 kHz) vibrational energy is directed to the interfaces to be joined, creating localized molecular excitation that causes the plastics to melt. With proper joint designs, welds can be made in only 2 seconds that are as strong as the base materials. When the energy is switched off, the plastics solidifies immediately. Parts to be welded ultrasonically must be so designed that the energy is concentrated in an initially small contact area, creating rapid melting and melt flow that progresses along the joint as the parts are pressed together. The lower part of the assembly is supported in a rigid nest fixture and the upper part is aligned, usually by the joint design. This upper part has freedom to couple acoustically when it is in contact with the horn through which the ultrasonic energy is transmitted.



Fig. 12. (left) Energy Director Types of Ultrasonic Weld Joint Designs for Assembly of Plastics Moldings, and (right) Typical Shear Interference

Typical joint designs are shown in Fig. 12, where the example at the left is of a simple butt-type energy director design that works well with amorphous materials. The inverted V-projection, known as an energy director, concentrates the energy in a small area on both sides of the joint. This area melts quickly and the material flows as the parts are pressed together. A basic shear interference joint is seen at the right in Fig. 12. Melting of both components starts at the small initial contact area and flow continues along the near-verti-

Copyright 2004, Industrial Press, Inc., New York, NY

cal wall as the parts are pressed together, creating a continuous, leakproof joint with a strength that often exceeds that of the parts joined.

This design is preferred with liquid crystal polymers and crystalline materials such as nylon, acetal, and thermoplastics polyester, and for any application of these materials where high strength and a hermetic seal are required. Many variations of these basic designs are possible and manufacturers of materials and ultrasonic equipment offer literature and design assistance. Ultrasonic vibrations may also be used for staking, swaging, and spot-welding in assembly of plastics parts.

With hygroscopic materials, welding should be completed as soon as possible after molding because moisture can cause weaker bonds. Drying may be advisable immediately before welding. Drawbacks with ultrasonic welding are that design, quality control, equipment maintenance, and settings are of critical importance for consistent, high-strength welds; the equipment is costly; the process uses large amounts of electric power especially with large parts; and parts to be joined must be of the same or similar materials. Filled and reinforced materials also present difficulties with compatibility.

Operating frequencies used in ultrasonic welding are in the range of 20–40 kHz, above the range detectable by the ear. However, discomforting sounds may be generated when plastics parts vibrate at lower frequencies, and may make sound-proofing necessary.

Vibration welding resembles ultrasonic welding except that the parts to be joined are rubbed together to produce heat to melt the joint faces by friction. The energy is transferred in the form of high-amplitude, low-frequency, reciprocating motion. When the vibration stops, the weld area cools and the parts remain joined in the alignment provided by the welding fixture. Typical frequencies used are 120–240 Hz and amplitudes range between 0.10 and 0. 20 in. of linear displacement. When the geometry or assembly design prevents linear movement, vibration-welding equipment can be designed to produce angular displacement of parts.

Like ultrasonic welding, vibration welding produces high-strength joints and is better suited to large parts and irregular joint faces. Moisture in hygroscopic materials such as nylon has less effect on the joint strength than it does with ultrasonic methods.

Spin welding is a rapid and economical method of joining parts that have circular joint interfaces. The process usually is completed in about 3 seconds and can be automated easily. Frictional heat for welding is generated by rotating one part against the other (usually fixed) with a controlled pressure. When the rotation is stopped, pressure is maintained during cooling and solidification of the melted material. Simple equipment such as a drill press is often sufficient for this process.

Radio-frequency welding, often called heat sealing, is widely used with flexible thermoplastics films and sheets of materials such as vinyl (plasticized PVC) and polyurethane, and for joining injection-molded parts, usually to film. Heat for welding is generated by a strong radio-frequency field to the joint region through a metal die formed to suit the joint shape. The die also applies the pressure required to complete the weld. Some plastics are transparent to radio frequency, so cannot be welded by this method.

Electromagnetic or induction welding uses inductive heating to generate fusion temperatures in thermoplastics materials as shown at the top in Fig. 13. Fine, magnetizable particles embedded in a gasket, preform, filament, ribbon, adhesive, coextruded film, or molded part are excited by the radio frequency and are thus heated to welding temperatures. The heated parts are pressed together, and as the temperature rises, the material of the particle carrier flows under pressure through the joint interface, filling voids and cavities and becoming an integral part of the weld. Ideally, the melted material should be contained and subjected to an internal pressure by the surrounding component surfaces. Proper joint design is essential to successful welding and some basic designs are also shown in Fig. 13.

Requirements of the preform often add cost to this welding method but the cost is offset by low reject rates resulting from good reliability of the welds. Structural, hermetic welds

Copyright 2004, Industrial Press, Inc., New York, NY

can be produced in most thermoplastics materials and automation can be used for large-volume production. The process also offers great latitude in joint size, configuration, tolerance requirements, and ability to bond some dissimilar materials. A disadvantage is that no metal can be near the joint line during energization of the inductor coil. All components of an assembly to be induction-welded must therefore be nonmetallic, or metallic components must be placed where they will not be subjected to the radio-frequency field from the inductor.

Assembly with Fasteners.— Metal fasteners of high strength can overstress plastics parts, so torque-controlled tightening or special design provisions are needed. Examples of poor and preferred designs are shown in Fig. 14. Where torque cannot be controlled, even with a shoulder screw, various types of washers can be used to spread the compression force over wider areas.



Fig. 13. Typical Joint Designs Used in Induction Welding of Plastics Materials

Metal inserts are available in a wide range of shapes and sizes for permanent installation of metal threads or bushings in plastics parts. Inserts are typically installed in molded bosses, designed with holes to suit the insert to be used. Some inserts are pressed into place and others are installed by methods designed to limit stress and increase strength. Generally, the outside of the insert is provided with projections of various configurations that penetrate the plastics and prevent movement under normal forces exerted during assem-

Copyright 2004, Industrial Press, Inc., New York, NY

bly. Inserts can also be installed with equipment similar to that used for ultrasonic welding, the plastics being melted to enhance contact with the metal and reduce insertion stresses.

Thread-cutting and -forming screws are widely used with plastics parts. Information on standard self-threading screws is found in *SELF-THREADING SCREWS* starting on page 1639. Thread-forming screws must be used carefully with high-modulus, low-creep materials, as high hoop stresses can be generated during insertion. Screws with multiple lobes and screws with alternating low and high threads have excellent holding power in plastics. Molded holes must have sufficient depth to prevent bottoming, and boss walls must be thick enough to resist stresses. A rule of thumb is that the outside diameter of the boss should be double the major diameter of the screw.

Hollow aluminum or other metal rivets are often used in plastics assembly, as arestamped sheet metal components, especially push-on or -in designs. Molded plastics fasteners also are frequently used.



Fig. 14. Examples of Poor and Good Designs Used for Assembly of Plastics Parts with Metal Fasteners

Machining Plastics.— Plastics can be molded into complex shapes so do not usually need to be machined. However, machining is sometimes more cost-effective than making a complex tool, especially when requirements are for prototype development, low-volume production, undercuts, angular holes, or other openings that are difficult to produce in a mold. Specialized methods for development of prototypes are discussed later. All machin-

Copyright 2004, Industrial Press, Inc., New York, NY

ing of plastics requires dust control, adequate ventilation, safety guards, and eye protection.

Like some metals, plastics may need to be annealed before machining to avoid warpage. Specific annealing instructions can be obtained from plastics suppliers. The modulus of elasticity of plastics is 10–60 times smaller than for metals, and this resilience permits much greater deflection of the work material during cutting. Thermoplastics materials must be held and supported firmly to prevent distortion, and sharp tools are essential to keep cutting forces to a minimum.

Plastics recover elastically during and after machining so that drilled or tapped holes often end up tapered or of smaller diameter than the tool. Turned diameters also can end up larger than the dimensions measured immediately after the finishing cut. The low thermal conductivity of plastics causes most of the heat generated in cutting to be absorbed by the tool. Heat in the plastics tends to stay at the surface. The heat must be removed by an air blast or a liquid coolant for good results in machining.

Plastics have thermal expansion coefficients some 10 times higher than those of metals, so that more heat is generated during machining than with metals. Adequate tool clearances must be provided to minimize heating. Compared with metals, temperatures at which plastics soften, deform and degrade are quite low. Allowing frictional heat to build up causes gumming, discoloration, poor tolerance control, and rough finishes. These effects are more pronounced with plastics such as polystyrene and polyvinyl chloride, having low melting points, than with plastics having higher melting points such as nylon, fluoroplastics, and polyphenylene sulfide. Sufficient clearances must be provided on cutting tools to prevent rubbing contact between the tool and the work. Tool surfaces that will come into contact with plastics during machining must be polished to reduce frictional drag and resulting temperature increases. Proper rake angles depend on depth of cut, cutting speed, and type of plastics being cut. Large rake angles should be used to produce continuous-type cuttings, but they should not be so large as to cause brittle fracture of the work, and resulting discontinuous chips. A discussion of machining techniques follows.

Turning and Cutting Off: High speed steel and carbide tools are commonly used with cutting speeds of 200–500 and 500–800 ft/min, respectively. Water-soluble coolants can be used to keep down temperatures at the shear zone and improve the finish, except when they react with the work material. Chatter may result from the low modulus of elasticity and can be reduced by close chucking and follow rests. Box tools are good for long, thin parts. Tools for cutting off plastics require greater front and side clearances than are needed for metal. Cutting speeds should be about half those used for turning operations.

Drilling: Chip flow in drilling is poor, the rake angles are insufficient and cutting speeds vary from the center to the periphery of the drill, so that drilling imposes severe loading on the workpiece. Drills of high speed steel or premium high speed steel (T15, M33, or M41–M47) are recommended, with low helix angles, point angles of 70–120 deg, and wide, highly polished flutes to ease chip exit. Normal feed rates are in the range of 0.001–0.012 in./rev for holes of $\frac{1}{16}$ to 2 in. diameter, with speeds of 100–250 ft/min, using lower speeds for deep and blind holes. Point angles of 60–90 deg (included) are used for many plastics, but an angle of 120 deg should be used for rigid polyvinyl chloride and acrylic (polymethyl methacrylate).

Clearance angles of 9–15 deg are usually sufficient to prevent the drill flanks from rubbing in the bottom of the hole, but acrylic materials require angles of 12–20 deg. Tests may be needed to determine the drill diameter for accurately sized holes, taking thermal expansion and elastic recovery into account. Reaming may be used to size holes accurately, but diameters produced may also be affected by thermal expansion of the plastics. Close-fitting bushings in drill jigs may increase friction on the drill and cause chips to plug up the drill flutes. For positioning accuracy, removable templates may be used to spot the hole position, then removed for the drilling to be completed. Pilot holes are not necessary,

Copyright 2004, Industrial Press, Inc., New York, NY

except when the hole is to be reamed or counterbored. Peck feeds to remove chips and compressed air cooling may be needed, especially for deep holes.

Drilling and reaming speed and feed recommendations for various materials are shown in Table 6.

These speeds and feeds can be increased where there is no melting, burning, discoloration, or poor surface finish. Drilling is best done with commercially available drills designed for plastics, usually having large helix angles, narrow lands, and highly polished or chromium-plated flutes to expel chips rapidly and minimize frictional heating. Circle cutters are often preferred for holes in thin materials. Deep holes may require peck feeds. Drills must be kept sharp and cool, and carbide tools may be needed in high production, especially with glass-reinforced materials. Cool with clean compressed air to avoid contamination. Use aqueous solutions for deep drilling because metalcutting fluids and oils may degrade or attack the plastics and may cause a cleaning problem. Hold plastics parts firmly during drilling to counter the tendency for the tooling to grab and spin the work.

Table 6. Speeds and Feeds for Drilling Holes of 0.25 to 0.375 in. Diameter in Various Thermoplastics

Material	Speed (rpm)	Feed[a]	Comments
Polyethylene	1,000–2,000	H	Easy to machine
Polyvinyl chloride	1,000–2,000	M	Tends to become gummy
Acrylic	500–1,500	M–H	Easy to drill with lubricant
Polystyrene	500–1,500	H	Must have coolant
ABS	500–1,000	M–H	
Polytetrafluoroethylene	1,000	L–M	Easy to drill
Nylon 6/6	1,000	H	Easy to drill
Polycarbonate	500–1,500	M–H	Easy to drill, some gumming
Acetal	1,000–2,000	H	Easy to drill
Polypropylene	1,000–2,000	H	Easy to drill
Polyester	1,000–1,500	H	Easy to drill

[a] H = high; M = medium; L = low.

Tapping and Threading of Plastics: Many different threaded fasteners can be used with plastics, including thread-tapping and -forming screws, threaded metal inserts, and molded-in threads, but threads must sometimes be machined after molding. For tapping of through-holes in thin cast, molded, or extruded thermoplastics and thermosets, a speed of 50 ft/min is appropriate. Tapping of filled materials is done at 25 ft/min. These speeds should be reduced for deep or blind holes, and when the percentage of thread is greater than 65–75 per cent. Taps should be of M10, M7, or M1, molybdenum high-speed steel, with finish-ground and -polished flutes. Two-flute taps are recommended for holes up to 0.125 in. diameter. Oversize taps may be required to make up for elastic recovery of the plastics. The danger of retapping on the return stroke can be reduced by blunting the withdrawal edges of the tool.

Sawing Thermoset Cast or Molded Plastics: Circular or band saws may be used for sawing. Circular saws provide smoother cut faces than band saws, but band saws run cooler so are often preferred even for straight cuts. Projection of the circular saw above the table should be minimized. Saws should have skip teeth or buttress teeth with zero front rake and a raker set. Precision-tooth saw blades should be used for thicknesses up to 1 in., and saws with buttress teeth are recommended for thicknesses above 1 in. Dull edges to the teeth cause chipping of the plastics and may cause breakage of the saw. Sawing speeds and other recommendations for using blades of high-carbon steel are shown in the accompanying table.

Copyright 2004, Industrial Press, Inc., New York, NY

Speeds and Numbers of Teeth for Sawing Plastics Materials with High-Carbon Steel Saw Blades

Material Thickness (in.)	Number of Teeth on Blade	Peripheral Speed (ft/min)	
		Thermoset Cast or Molded Plastics	Thermoplastics (and Epoxy, Melamine, Phenolic and Allyl Thermosets)
0–0.5	8–14	2000–3000	4000–5000
0.5–1	6–8	1800–2200	3500–4300
1–3	3	1500–2200	3000–3500
>3	>3	1200–1800	2500–3000

Milling of Plastics: Peripheral cutting with end mills is used for edge preparation, slotting and similar milling operations, and end cutting can also be used for facing operations. Speeds for milling range from 800 to 1400 ft/min for peripheral end milling of many thermoplastics and from 400 to 800 ft/min for many thermosets. However, slower speeds are generally used for other milling operations, with some thermoplastics being machined at 300–500 ft/min, and some thermosets at 150–300 ft/min. Adequate support and suitable feed rates are very important. A table feed that is too low will generate excessive heat and cause surface cracks, loss of dimensional accuracy, and poor surface finish. Too high a feed rate will produce a rough surface. High-speed steel tools (M2, M3, M7, or T15) are generally used, but for glass-reinforced nylon, silicone, polyimide, and allyl, carbide (C2) is recommended.

New Techniques: Lasers can be used for machining plastics, especially sheet laminates, although their use may generate internal stresses. Ultrasonic machining has no thermal, chemical, or electrical reaction with the workpiece and can produce holes down to 0.003 in. diameter, tight tolerances (0.0005 in.), and very smooth finishes (0.15 µin. with No. 600 boron carbide abrasive powder). Water-jet cutting using pressures up to 60,000 lb/in.^{2} is widely used for plastics and does not introduce stresses into the material. Tolerances of ± 0.004 in. can be held, depending on the equipment available. Process variables, pressures, feed rates, and the nozzle diameter depend on the material being cut. This method does not work with hollow parts unless they can be filled with a solid core.

Development of Prototypes.— Prototypes are made for testing of properties such as stress and fatigue resistance, to find ways to improve quality and reliability, to improve tooling, and to reduce time to market. Prototyping may answer questions about finish, sink marks that result from contraction, witness lines from mold joints, ejector pin marks, knit or weld lines, texturing, moldability, shrinkage, mechanical strength, pull-out resistance of inserts, electrical properties, and problems of mating with other parts.

Prototypes of moldings are made in five major steps including design; refining the design; making a model (physical or computer); making a mold; and producing parts. The model may be made from wood, plaster, plastics (by machining), or a metal. Some 90 per cent of prototypes are made by modern CAD/CAM methods that allow holding of dimensional tolerances of 2–3 per cent of drawing specifications.

Prototypes can also be made by a process called stereo lithography that uses a tank of photosensitive liquid polymer, an *x-y* scanning, ultraviolet laser with a beam diameter of 0.010 in., a *z*-axis elevator platform, and a controlling computer. The platform height is adjusted so that a suitable thickness of liquid polymer covers its surface. The laser beam is focused on the liquid surface and hardens the polymer at this point by heating.

The CAD representation of the prototype is described by a model in which thin (0.005–0.020 in.) cross sections can be isolated. Data representing the lowest level of the prototype are used to move the platform so that a layer of the polymer corresponding to the lowest "slice" is hardened. The platform is then lowered, the liquid polymer flows over the hard-

Copyright 2004, Industrial Press, Inc., New York, NY

ened layer, and the platform is again raised, less an amount equal to the next "slice." The process is repeated for successive "slices" of the prototype, which is thus built up gradually to form a hollow, three-dimensional shape corresponding to the model in the CAD program. The part thus produced is fairly brittle but can be used for visual examination, design verification, and marketing evaluation, and can be replicated from other materials such as plastics or metals by casting or other methods.

Finishing and decorating methods used for plastics parts include spray painting, vacuum metallizing, hot stamping, silk screening, and plating. Conductive coatings may be applied to inside surfaces, usually by flame- or arc-spraying, to dissipate static electricity and provide electromagnetic shielding. Thorough cleaning is essential. Materials such as polyethylene, polypropylene, and acetal have waxlike surfaces that may not be painted easily or may need pretreatment or special primers. Many amorphous plastics are easy to paint. Suitable coatings include polyurethane-, epoxy-, acrylic-, alkyd-, and vinyl-based paints. Oven curing may distort parts made from non-heat-resistant materials.

Vacuum metallizing and sputter-plating require application of a special base coat and a protective clear top coat before and after treatment. Resistance heating or an electron beam can be used to melt the metallizing materials such as aluminum, silver, copper, and gold, which usually are pure elements. Sputter plating uses a plasma to produce the metallic vapor and can use brass as well as the metals mentioned. Chromium plating requires etched surfaces to ensure good adhesion.

Plastics may be polished by buffing methods similar to those used on metals, but experiments to determine the effect of frictional heat are recommended. Surfaces can be heated to 300–400 deg. F by buffing, and some plastics soften and melt at these temperatures. Heating sometimes causes plastics to give off toxic gases, so masks should be worn to filter out such gases and dust. Parting lines, imperfections, scratches, saw lines, and scars resulting from fabrication can be treated with abrasives prior to buffing. Wet or dry abrasives such as silicon carbide or aluminum oxide are generally used, in grain sizes of 60 to as fine as 320. Some buffing compounds are ineffective on plastics. Scratch lines should be presented at a slight angle to the buff surface for best results. Light, tallow-free grease will help keep the abrasive surface free from buildup, and speeds of 5,000 to 6,000 surface feet per minute are recommended.

For low-melting point plastics, soft cotton buffs are best, with surface speeds of 4,000 to 5,000 feet per minute, using a wet or greasy tripoli or silica compound. For finishing, only rouge may be needed for a satisfactory finish. If a cleaning solvent is used it should be checked to see that it does not dissolve the plastics, and it should be used only in a well-ventilated area. Acrylics such as Acrylite or Plexiglass may also be 'flame polished,' under advice from the materials supplier.

Plastics Gearing.— Plastics gears may be cut from blanks, as with metal gears, or molded to shape in an injection-molding machine, for lower production costs, though tooling may cost more. Cut plastics gears may be of similar design to their metal counterparts, but molded gears are usually of modified form to suit the material characteristics. Plastics materials also may be preferred for gears because of superior sliding properties with reduced noise and need for lubrication, chemical or electrical properties, or resistance to wear. However, plastics gear teeth slide more smoothly and easily against metal teeth than do plastics against plastics, and wear is less. For power transmission, plastics gear teeth are usually of involute form. See also *Non-metallic Gearing* on page 2149.

Most plastics gears are made from nylons and acetals, although acrylonitrile-butadiene-styrenes (ABS), polycarbonates, polysulfones, phenylene oxides, poly-urethanes, and thermoplastic polyesters can also be used. Additives used in plastics gears include glass fiber for added strength, and fibers, beads, and powders for reduced thermal expansion and improved dimensional stability. Other materials, such as molybdenum disulfide, tetrafluoroethylene (TFE), and silicones, may be added as lubricants to improve wear resistance.

Copyright 2004, Industrial Press, Inc., New York, NY

Choice of plastics gear material depends on requirements for size and nature of loads to be transmitted, speeds, required life, working environment, type of cooling, lubrication, and operating precision. Because of cost, plastics gears are sometimes not enclosed in sealed housings, so are often given only a single coating of lubricant grease. Overloading of lubricated plastics gear teeth will usually cause tooth fracture, and unlubricated teeth often suffer excessive wear. Thermoplastics strength varies with temperature, with higher temperatures reducing root stress and permitting tooth deformation. In calculating power to be transmitted by spur, helical, and straight bevel gearing, the following formulas should be used with the factors given in Tables 7, 8, and 9.

For internal and external spur gears,

$$HP = \frac{S_s FYV}{55(600 + V)PC_s} \tag{28}$$

For internal and external helical gears,

$$HP = \frac{S_s FYV}{423(78 + \sqrt{V})P_n C_s} \tag{29}$$

For straight bevel gears,

$$HP = \frac{S_s FYV(C - F)}{55(600 + V)PCC_s} \tag{30}$$

where S_s = safe stress in bending (from Table 8); F = face width in inches; Y = tooth form factor (from Table 7); C = pitch cone distance in inches; C_s = service factor (from Table 9); P = diametral pitch; P_n = normal diametral pitch; and V = velocity at pitch circle diameter in ft/min.

Table 7. Tooth Form Factors *Y* for Plastics Gears

Number of Teeth	14½-deg Involute or Cycloidal	20-deg Full Depth Involute	20-deg Stub Tooth Involute	20-deg Internal Full Depth	
				Pinion	Gear
12	0.210	0.245	0.311	0.327	…
13	0.220	0.261	0.324	0.327	…
14	0.226	0.276	0.339	0.330	…
15	0.236	0.289	0.348	0.330	…
16	0.242	0.259	0.361	0.333	…
17	0.251	0.302	0.367	0.342	…
18	0.261	0.308	0.377	0.349	…
19	0.273	0.314	0.386	0.358	…
20	0.283	0.320	0.393	0.364	…
21	0.289	0.327	0.399	0.371	…
22	0.292	0.330	0.405	0.374	…
24	0.298	0.336	0.415	0.383	…
26	0.307	0.346	0.424	0.393	…
28	0.314	0.352	0.430	0.399	0.691
30	0.320	0.358	0.437	0.405	0.679
34	0.327	0.371	0.446	0.415	0.660
38	0.336	0.383	0.456	0.424	0.644
43	0.346	0.396	0.462	0.430	0.628

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. *(Continued)* Tooth Form Factors *Y* for Plastics Gears

Number of Teeth	14½-deg Involute or Cycloidal	20-deg Full Depth Involute	20-deg Stub Tooth Involute	20-deg Internal Full Depth	
				Pinion	Gear
50	0.352	0.480	0.474	0.437	0.613
60	0.358	0.421	0.484	0.446	0.597
75	0.364	0.434	0.496	0.452	0.581
100	0.371	0.446	0.506	0.462	0.565
150	0.377	0.459	0.518	0.468	0.550
300	0.383	0.471	0.534	0.478	0.534
Rack	0.390	0.484	0.550	…	…

These values assume a moderate temperature increase and some initial lubrication. With bevel gearing, divide the number of teeth by the cosine of the pitch angle and use the data in the table. For example, if a 20-deg PA bevel gear has 40 teeth and a pitch angle of 58 deg, 40 divided by the cosine of 58 deg = 40 ÷ 0.529919 ~ 75, and $Y = 0.434$.

Table 8. Safe Bending Stress (lb/in²) Values for Plastics Gears

Plastics Type	Safe Stress	
	Unfilled	Glass-filled
ABS	3,000	6,000
Acetal	5,000	7,000
Nylon	6,000	12,000
Polycarbonate	6,000	9,000
Polyester	3,500	8,000
Polyurethane	2,500	…

Table 9. Service Factors for Plastics Gears

Type of Load	8–10 Hr/Day	24 Hr/Day	Intermittent, 3 Hr/Day	Occasional, ½ Hr/Day
Steady	1.00	1.25	0.80	0.50
Light shock	1.25	1.5	1.00	0.80
Medium shock	1.5	1.75	1.25	1.00
Heavy shock	1.75	2.00	1.5	1.25

Example: As an example, assume that a material is to be selected for a spur gear that must transmit ⅛ hp at 350 rpm, for 8 hrs/day under a steady load. The gear is to have 75 teeth, 32 diametral pitch, 20 deg pressure angle, 0.375 in. face width, and a pitch diameter of 2.3438 in. Using Equation (28),

$$HP = \frac{S_s FYV}{55(600 + V)PC_s} \quad \text{or} \quad S_s = \frac{55(600 + V)PC_s HP}{FYV}$$

$$\text{hp} = 0.125, \quad Y = 0.434 \quad \text{and}$$

$$V = \frac{rpm \times \pi \times D}{12} = \frac{350 \times 3.1416 \times 2.3438}{12} = 215 \text{ ft/min}$$

Copyright 2004, Industrial Press, Inc., New York, NY

therefore,

$$S_s = \frac{55(600 + 215)32 \times 1.00 \times 0.125}{0.375 \times 0.434 \times 215} = 5{,}124 \text{ lb/in.}^2$$

From Table 8 it is apparent that the gear could be molded from several materials. Available physical and chemical characteristics must now be considered in relation to the operating environment for the gear. Strengths of plastics materials decrease with increasing temperatures and not all plastics resist the effects of some liquids, including some lubricants. Some plastics deteriorate when in sunlight for long periods; some are more dimensionally stable than others; and wear resistance varies from one to another. Manufacturers' data sheets will answer some of these questions.

Backlash: Plastics gears should be so dimensioned that they will provide sufficient backlash at the highest temperatures likely to be encountered in service. Dimensional allowances must also be made for gears made of hygroscopic plastics that may be exposed to damp service conditions. Teeth of heavily loaded gears usually have tip relief to reduce effects of deflection, and have full fillet radii to reduce stress concentrations. Such modifications to tooth form are also desirable in plastics gears. If the pinion in a pair of gears has a small number of teeth, undercutting may result. Undercutting weakens teeth, causes undue wear, and may affect continuity of action. The undercutting can be reduced by using the long-short addendum system, which involves increasing the addendum of the pinion teeth and reducing that of the gear teeth. The modified addendum method will also reduce the amount of initial wear that takes place during the initial stages of contact between the teeth.

Accuracy: The Gear Handbook, AGMA 390-03a-1980, Part 2, Gear Classification, provides a system whereby results of gear accuracy measurements are expressed in terms of maximum tooth-to-tooth and composite tolerances. This system uses AGMA quality numbers related to maximum tolerances, by pitch and diameter, and is equally applicable to plastics gears as to metal gears. AGMA quality numbers must be chosen for a pair of mating gears early in the design process, and the finished gears must be inspected by being run in close mesh with a master gear in a center-distance measuring instrument to make sure that the errors do not exceed the specified tolerances.

To prevent failure from fatigue and wear caused by excessive flexing of the teeth, plastics gears must be made to the same standards of acccuracy as metal gears. Solidification shrinkage of plastics requires that dimensions of molds for gears be larger than the dimensions of the parts to be produced from them. The amount of the shrinkage is usually added to the mold dimension (with the mold at operating temperature). However, this procedure cannot be followed for the tooth profile as it would introduce large errors in the pressure angle. Increases in pressure angle cause gear teeth to become wider at the root and more pointed. Sliding conditions are improved and the teeth are stronger, so that higher loading values can be used.

Shrinkage allowances have the greatest effect on the accuracy of the molded gears, so tooth profiles must be calculated extremely carefully in terms of mold profile. If a tooth is merely made larger by using a standard hobbing cutter to cut the tool whereby the teeth in the mold are electroeroded, differential shrinkage caused by the molded tooth being thicker at the root than at the tip will distort the shape of the molded tooth, making it thinner at the tip and thicker at the root. With two mating gears, these faulty shapes will affect the pressure angle resulting in binding, wear, and general malfunction. If the tooth thickness limits for a molded gear are to be held to +0.000 in., –0.001 in., the outside diameter must be permitted to vary up to 0.0027 in. for 20-deg, and 0.0039 in. for 14½-deg pressure angle gears. All high-accuracy gears should be specified with AGMA quality numbers and inspected with center-distance measuring machines if the required accuracy is to be achieved.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

DIMENSIONING, GAGING, AND MEASURING

DRAFTING PRACTICES

630 ANSI Drafting Practices
630 Sizes of Drawing Sheets
630 Symbols for Section Lining
630 Geometric Dimensioning
633 ANSI and ISO Symbols
634 Definitions
638 Datum Referencing
640 Positional Tolerance
642 Checking Drawings

ALLOWANCES AND TOLERANCES FOR FITS

645 Basic Dimensions
645 Tolerances
647 Force fits
648 Expansion and Shrinkage Fits
649 Temperatures for Shrinkage Fits
651 ANSI Standard Limits and Fits
651 Definitions
652 Preferred Basic Sizes
652 Standard Tolerances
652 ANSI Standard Fits
656 Modified Standard Fits
658 Running and Sliding Fits
660 Clearance Locational Fits
662 Transition Locational Fits
665 ANSI Metric Limits and Fits
665 Definitions
666 Tolerances Designation
667 Preferred Metric Fits
670 Hole Basis Fits
670 Clearance Fits
672 Transition and Interference Fits
674 Shaft Basis Fits
674 Clearance Fits
676 Transition and Interference Fits
678 Gagemakers Tolerances
679 ISO Metric Limits and Fits
680 Definitions
680 Calculated Limits of Tolerance
682 Tolerance for Selected Holes
682 Tolerance for Selected Shafts
683 Clearances
685 Deviations for Shafts
687 Deviations for Holes
689 Preferred Numbers
689 ANSI Preferred Numbers
690 Preferred Metric Sizes

MEASURING INSTRUMENTS AND INSPECTION METHODS

692 Verniers and Micrometers
693 Dual Metric-Inch Vernier
695 Metric Micrometer
695 Sine-bar
695 Types of Sine-bars
696 Setting a Sine-bar
697 Using Sine-bar Tables
698 Measuring Tapers with V-block
698 Dimensioning Tapers
699 Constants for 5-inch Sine-bar
706 Constants for 100-mm Sine-bar
713 Angles and Tapers
713 Measuring Dovetail Slides
714 Tapers per Foot
715 Figuring Tapers
717 Measurement over Pins and Rolls
717 Measurement over Pins
717 Checking a V-shaped Groove
718 Checking Radius of Arc
719 Checking Shaft Conditions
721 Out-of-Roundness and Lobing
723 Measurements Using Light

SURFACE TEXTURE

724 ANSI Surface Texture
726 Definitions
727 Sampling Lengths
728 Roughness Parameters
729 Waviness Parameters
729 Surface Roughness to Tolerances
730 Instruments for Measurement
731 Roughness Measurements
731 Surface Texture Symbols
734 Roughness Average Values
735 Lay Symbols
735 Surface Texture of Castings
735 Metric Dimensions on Drawings
738 ISO Surface Finish
738 Surface Finish Symbology
740 Roughness Lengths
743 Gage Blocks
743 Precision Gage Blocks
744 Gage Block Sets

Copyright 2004, Industrial Press, Inc., New York, NY

DRAFTING PRACTICES

American National Standard Drafting Practices

Several American National Standards for use in preparing engineering drawings and related documents are referred to for use.

Sizes of Drawing Sheets.— Recommended trimmed sheet sizes, based on ANSI Y14.1-1980 (R1987), are shown in the following table.

Size, inches				Metric Size, mm			
A	8½ × 11	*D*	22 × 34	*A0*	841 × 1189	*A3*	297 × 420
B	11 × 17	*E*	34 × 44	*A1*	594 × 841	*A4*	210 × 297
C	17 × 22	*F*	28 × 40	*A2*	420 × 594		

The standard sizes shown by the left-hand section of the table are based on the dimensions of the commercial letter head, 8½ × 11 inches, in general use in the United States. The use of the basic sheet size 8½ × 11 inches and its multiples permits filing of small tracings and folded blueprints in commercial standard letter files with or without correspondence. These sheet sizes also cut without unnecessary waste from the present 36-inch rolls of paper and cloth.

For drawings made in the metric system of units or for foreign correspondence, it is recommended that the metric standard trimmed sheet sizes be used. (Right-hand section of table.) These sizes are based on the width-to-length ratio of 1 to $\sqrt{2}$.

Line Conventions and Drawings.— American National Standard Y14.2M-1979 (R1987) establishes line and lettering practices for engineering drawings. The line conventions and the symbols for section lining are as shown on Tables 1 and 2.

Approximate width of THICK lines for metric drawings are 0.6 mm, and for inch drawings, 0.032 inch. Approximate width of THIN lines for metric drawings are 0.3 mm, and for inch drawings, 0.016 inch. These approximate line widths are intended to differentiate between THICK and THIN lines and are not values for control of acceptance or rejection of the drawings.

Surface-Texture Symbols.— A detailed explanation of the use of surface-texture symbols from American National Standard Y14.36M-1996 begins on page 731.

Geometric Dimensioning and Tolerancing.— ANSI/ASME Y14.5M-1994, "Dimensioning and Tolerancing," covers dimensioning, tolerancing, and similar practices for engineering drawings and related documentation. The mathematical definitions of dimensioning and tolerancing principles are given in the standard ANSI/ASME Y14.5.1M-1994. ISO standards ISO 8015 and ISO 26921 contain a detailed explanation of ISO geometric dimensioning and tolerancing practices.

Geometric dimensioning and tolerancing provides a comprehensive system for symbolically defining the geometrical tolerance zone within which features must be contained. It provides an accurate transmission of design specifications among the three primary users of engineering drawings; design, manufacturing and quality assurance.

Some techniques introduced in ANSI/ASME Y14.5M-1994 have been accepted by ISO. These techniques include projected tolerance zone, three-plane datum concept, total runout tolerance, multiple datums, and datum targets. Although this Standard follows ISO practice closely, there are still differences between ISO and U.S. practice. (A comparison of the symbols used in ISO standards and Y14.5M is given on page 633.)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard for Engineering Drawings
ANSI/ASME Y14.2M-1992



Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Symbols for Section Lining
ANSI Y14.2M-1979 (R1987)

	Cast and Malleable iron (Also for general use of all materials)		Titanium and refractory material
	Steel		Electric windings, electro magnets, resistance, etc.
	Bronze, brass, copper, and compositions		Concrete
	White metal, zinc, lead, babbitt, and alloys		Marble, slate, glass, porcelain, etc.
	Magnesium, aluminum, and aluminum alloys		Earth
	Rubber, plastic electrical insulation		Rock
	Cork, felt, fabric, leather, fiber		Sand
	Sound insulation		Water and other liquids
	Thermal insulation		Wood-across grain Wood-with grain

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Comparison of ANSI and ISO Geometric Symbols *ASME Y14.5M-1994*

Symbol for	ANSI Y14.5M	ISO	Symbol for	ANSI Y14.5	ISO	Symbol for	ANSI Y14.5M	ISO
Straightness			Circular Runout[a]			Feature Control Frame		
Flatness			Total Runout[a]			Datum Feature[a]		
Circularity			At Maximum Material Condition			All Around - Profile		
Cylindricity			At Least Material Condition			Conical Taper		
Profile of a Line			Regardless of Feature Size	NONE	NONE	Slope		
Profile of a Surface			Projected Tolerance Zone			Counterbore/Spotface		
Angularity			Diameter			Countersink		
Perpendicularity			Basic Dimension	50	50	Depth/Deep		
Parallelism			Reference Dimension	(50)	(50)	Square (Shape)		
Position			Datum Target			Dimension Not to Scale	15	15
Concentricity/Coaxiality			Target Point			Number of Times/Places	8X	8X
Symmetry			Dimension Origin			Arc Length		
Radius	R	R	Spherical Radius	SR	SR	Sperical Diameter	SØ	SØ
Between[a]		None	Controlled Radius	CR	None	Statical Tolerance		None

[a] Arrowheads may be filled in.

Copyright 2004, Industrial Press, Inc., New York, NY

One major area of disagreement is the ISO "principle of independency" versus the "Taylor principle." Y14.5M and standard U.S. practice both follow the Taylor principle, in which a geometric tolerancing zone may not extend beyond the boundary (or envelope) of perfect form at MMC (maximum material condition). This boundary is prescribed to control variations as well as the size of individual features. The U.S. definition of independency further defines features of size as being independent and not required to maintain a perfect relationship with other features. The envelope principle is optional in treatment of these principles. A summary of the application of ANSI/ASME geometric control symbols and their use with basic dimensions and modifiers is given in Table 1.

Table 1. Application of Geometric Control Symbols

Type	Geometric Characteristics		Pertains To	Basic Dimensions	Feature Modifier	Datum Modifier
Form		Straightness	ONLY individual feature		Modifier not applicable	NO datum
		Circularity				
		Flatness				
		Cylindricity				
Profile		Profile (Line)	Individual or related	Yes if related		RFS implied unless MMC or LMC is stated
		Profile (Surface)				
Orientation		Angularity	ALWAYS related feature(s)	Yes	RFS implied unless MMC or LMC is stated	
		Perpendicularity				
		Parallelism				
Location		Position		Yes		
		Concentricity			Only RFS	Only RFS
		Symmetry				
Runout		Circular Runout				
		Total Runout				

Five types of geometric control, when datums are indicated, when basic dimensions are required, and when MMC and LMC modifiers may be used.

ANSI/ASME Y14.5M features metric SI units (the International System of Units), but customary units may be used without violating any principles. On drawings where all dimensions are either in millimeters or in inches, individual identification of linear units is not required. However, the drawing should contain a note stating UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN MILLIMETERS (or IN INCHES, as applicable). According to this Standard, all dimensions are applicable at a temperature of 20 C (68 F) unless otherwise specified. Compensation may be made for measurements taken at other temperatures.

Angular units are expressed in degrees and decimals of a degree (35.4) or in degrees (°), minutes (′), and seconds (″), as in 35° 25′ 10″. A 90-degree angle is implied where center lines and depicting features are shown on a drawing at right angles and no angle is specified. A 90-degree BASIC angle applies where center lines of features in a pattern or surface shown at right angles on a drawing are located or defined by basic dimensions and no angle is specified.

Definitions.— The following terms are defined as their use applies to ANSI/ASME Y14.5M.

Datum Feature: The feature of a part that is used to establish a datum.

Datum Identifier: The graphic symbol on a drawing used to indicate the datum feature.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Datum Feature Symbol

Datum Plane: The individual theoretical planes of the reference frame derived from a specified datum feature. A datum is the origin from which the location or other geometric characteristics of features of a part are established.

Datum Reference Frame: Sufficient features on a part are chosen to position the part in relationship to three planes. The three planes are mutually perpendicular and together called the datum reference frame. The planes follow an order of precedence and allow the part to be immobilized. This immobilization in turn creates measurable relationships among features.

Datum Simulator: Formed by the datum feature contacting a precision surface such as a surface plate, gage surface or by a mandrel contacting the datum. Thus, the plane formed by contact restricts motion and constitutes the specific reference surface from which measurements are taken and dimensions verified. The datum simulator is the practical embodiment of the datum feature during manufacturing and quality assurance.

Datum Target: A specified point, line, or area on a part, used to establish a datum.

Degrees of Freedom: The six directions of movement or translation are called degrees of freedom in a three-dimensional environment. They are up-down, left-right, fore-aft, roll, pitch and yaw.



Fig. 2. Degrees of Freedom (Movement) That Must be Controlled, Depending on the Design Requirements.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimension, Basic: A numerical value used to describe the theoretically exact size, orientation, location, or optionally, profile, of a feature or datum or datum target. Basic dimensions are indicated by a rectangle around the dimension and are not toleranced directly or by default. The specific dimensional limits are determined by the permissible variations as established by the tolerance zone specified in the feature control frame. A dimension is only considered basic for the geometric control to which it is related.



Fig. 3. Basic Dimensions

Dimension Origin: Symbol used to indicate the origin and direction of a dimension between two features. The dimension originates from the symbol with the dimension tolerance zone being applied at the other feature.



Fig. 4. Dimension Origin Symbol

Dimension, Reference: A dimension, usually without tolerance, used for information purposes only. Considered to be auxiliary information and not governing production or inspection operations. A reference dimension is a repeat of a dimension or is derived from a calculation or combination of other values shown on the drawing or on related drawings.

Feature Control Frame: Specification on a drawing that indicates the type of geometric control for the feature, the tolerance for the control, and the related datums, if applicable.



Fig. 5. Feature Control Frame and Datum Order of Precedence

Feature: The general term applied to a physical portion of a part, such as a surface, hole, pin, tab, or slot.

Least Material Condition (LMC): The condition in which a feature of size contains the least amount of material within the stated limits of size, for example, upper limit or maximum hole diameter and lower limit or minimum shaft diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

Limits, Upper and Lower (UL and LL): The arithmetic values representing the maximum and minimum size allowable for a dimension or tolerance. The upper limit represents the maximum size allowable. The lower limit represents the minimum size allowable.

Maximum Material Condition (MMC): The condition in which a feature of size contains the maximum amount of material within the stated limits of size. For example, the lower limit of a hole is the minimum hole diameter. The upper limit of a shaft is the maximum shaft diameter.

Position: Formerly called true position, position is the theoretically exact location of a feature established by basic dimensions.

Regardless of Feature Size (RFS): The term used to indicate that a geometric tolerance or datum reference applies at any increment of size of the feature within its tolerance limits. RFS is the default condition unless MMC or LMC is specified. The concept is now the default in ANSI/ASME Y14.5M-1994, unless specifically stated otherwise. Thus the symbol for RFS is no longer supported in ANSI/ASME Y14.5M-1994.

Size, Actual: The term indicating the size of a feature as produced.

Size, Feature of: A feature that can be described dimensionally. May include a cylindrical or spherical surface, or a set of two opposed parallel surfaces associated with a size dimension.

Tolerance Zone Symmetry: In geometric tolerancing, the tolerance value stated in the feature control frame is always a single value. Unless otherwise specified, it is assumed that the boundaries created by the stated tolerance are bilateral and equidistant about the perfect form control specified. However, if desired, the tolerance may be specified as unilateral or unequally bilateral. (See Figs. 6 through 8)

Tolerance, Bilateral: A tolerance where variation is permitted in both directions from the specified dimension. Bilateral tolerances may be equal or unequal.

Tolerance, Geometric: The general term applied to the category of tolerances used to control form, profile, orientation, location, and runout.

Tolerance, Unilateral: A tolerance where variation is permitted in only one direction from the specified dimension.

True Geometric Counterpart: The theoretically perfect plane of a specified datum feature.

Virtual Condition: A constant boundary generated by the collective effects of the feature size, its specified MMC or LMC material condition, and the geometric tolerance for that condition.



Fig. 6. Application of a bilateral geometric tolerance

Copyright 2004, Industrial Press, Inc., New York, NY



Unilateral zone with all of the 0.25 tolerance outside perfect form.

Fig. 7. Application of a unilateral geometric tolerance zone outside perfect form



Unilateral zone with all of the 0.25 tolerance inside perfect form.

Fig. 8. Application of a unilateral geometric tolerance zone inside a perfect form

Datum Referencing.— A datum indicates the origin of a dimensional relationship between a toleranced feature and a designated feature or features on a part. The designated feature serves as a datum feature, whereas its true geometric counterpart establishes the datum plane. Because measurements cannot be made from a true geometric counterpart, which is theoretical, a datum is assumed to exist in, and be simulated by the associated processing equipment.

For example, machine tables and surface plates, although not true planes, are of such quality that they are used to simulate the datums from which measurements are taken and dimensions are verified. When magnified, flat surfaces of manufactured parts are seen to have irregularities, so that contact is made with a datum plane formed at a number of surface extremities or high points.

Sufficient datum features, those most important to the design of the part, are chosen to position the part in relation to a set of three mutually perpendicular planes, the datum reference frame. This reference frame exists only in theory and not on the part. Therefore, it is necessary to establish a method for simulating the theoretical reference frame from existing features of the part. This simulation is accomplished by positioning the part on appropriate datum features to adequately relate the part to the reference frame and to restrict the degrees of freedom of the part in relation to it.

These reference frame planes are simulated in a mutually perpendicular relationship to provide direction as well as the origin for related dimensions and measurements. Thus, when the part is positioned on the datum reference frame (by physical contact between each datum feature and its counterpart in the associated processing equipment), dimensions related to the datum reference frame by a feature control frame are thereby mutually perpendicular. This theoretical reference frame constitutes the three-plane dimensioning system used for datum referencing.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 9. Datum target symbols

Depending on the degrees of freedom that must be controlled, a simple reference frame may suffice. At other times, additional datum reference frames may be necessary where physical separation occurs or the functional relationship. Depending on the degrees of freedom that must be controlled, a single datum of features require that datum reference frames be applied at specific locations on the part. Each feature control frame must contain the datum feature references that are applicable.

Datum Targets: Datum targets are used to establish a datum plane. They may be points, lines or surface areas. Datum targets are used when the datum feature contains irregularities, the surface is blocked by other features or the entire surface cannot be used. Examples where datum targets may be indicated include uneven surfaces, forgings and castings, weldments, non-planar surfaces or surfaces subject to warping or distortion. The datum target symbol is located outside the part outline with a leader directed to the target point, area or line. The targets are dimensionally located on the part using basic or toleranced dimensions. If basic dimensions are used, established tooling or gaging tolerances apply. A solid leader line from the symbol to the target is used for visible or near side locations with a dashed leader line used for hidden or far side locations. The datum target symbol is divided horizontally into two halves. The top half contains the target point area if applicable; the bottom half contains a datum feature identifying letter and target number. Target

Copyright 2004, Industrial Press, Inc., New York, NY

numbers indicate the quantity required to define a primary, secondary, or tertiary datum. If indicating a target point or target line, the top half is left blank. Datum targets and datum features may be combined to form the datum reference frame, Fig. 9.

Datum Target points: A datum target point is indicated by the symbol "X," which is dimensionally located on a direct view of the surface. Where there is no direct view, the point location is dimensioned on multiple views.

Datum Target Lines: A datum target line is dimensionally located on an edge view of the surface using a phantom line on the direct view. Where there is no direct view, the location is dimensioned on multiple views. Where the length of the datum target line must be controlled, its length and location are dimensioned.

Datum Target Areas: Where it is determined that an area or areas of flat contact are necessary to ensure establishment of the datum, and where spherical or pointed pins would be inadequate, a target area of the desired shape is specified. Examples include the need to span holes, finishing irregularities, or rough surface conditions. The datum target area may be indicated with the "X" symbol as with a datum point, but the area of contact is specified in the upper half of the datum target symbol. Datum target areas may additionally be specified by defining controlling dimensions and drawing the contact area on the feature with section lines inside a phantom outline of the desired shape.

Positional Tolerance.— A positional tolerance defines a zone within which the center, axis, or center plane of a feature of size is permitted to vary from true (theoretically exact) position. Basic dimensions establish the true position from specified datum features and between interrelated features. A positional tolerance is indicated by the position symbol, a tolerance, and appropriate datum references placed in a feature control frame.

Modifiers: In certain geometric tolerances, modifiers in the form of additional symbols may be used to further refine the level of control. The use of the MMC and LMC modifiers has been common practice for many years. However, several new modifiers were introduced with the 1994 U.S. national standard. Some of the new modifiers include free state, tangent plane and statistical tolerancing, Fig. 10.

Free State	MMC	LMC	Tangent Plane	Projected Tolerance Zone	Statistical Tolerance
Ⓕ	Ⓜ	Ⓛ	Ⓣ	Ⓟ	ST

Fig. 10. Tolerance modifiers

Projected Tolerance Zone: Application of this concept is recommended where any variation in perpendicularity of the threaded or press-fit holes could cause fasteners such as screws, studs, or pins to interfere with mating parts. An interference with subsequent parts can occur even though the hole axes are inclined within allowable limits. This interference occurs because, without a projected tolerance zone, a positional tolerance is applied only to the depth of threaded or press-fit holes. Unlike the floating fastener application involving clearance holes only, the attitude of a fixed fastener is restrained by the inclination of the produced hole into which it assembles.



Fig. 11. Projected tolerance zone callout

Copyright 2004, Industrial Press, Inc., New York, NY

With a projected tolerance zone equal to the thickness of the mating part, the inclinational error is accounted for in both parts. The minimum extent and direction of the projected tolerance zone is shown as a value in the feature control frame. The zone may be shown in a drawing view as a dimensioned value with a heavy chain line drawn closely adjacent to an extension of the center line of the hole.



Fig. 12. Projected tolerance zone application

Statistical Tolerance: The statistical tolerancing symbol is a modifier that may be used to indicate that a tolerance is controlled statistically as opposed to being controlled arithmetically. With arithmetic control, assembly tolerances are typically divided arithmetically among the individual components of the assembly. This division results in the assumption that assemblies based on "worst case" conditions would be guaranteed to fit because the worst case set of parts fit — so that anything better would fit as well.

When this technique is restrictive, statistical tolerancing, via the symbol, may be specified in the feature control frame as a method of increasing tolerances for individual parts. This procedure may reduce manufacturing costs because its use changes the assumption that statistical process control may make a statistically significant quantity of parts fit, but not absolutely all. The technique should only be used when sound statistical methods are employed.

Copyright 2004, Industrial Press, Inc., New York, NY

Tangent Plane: When it is desirable to control the surface of a feature by the contacting or high points of the surface, a tangent plane symbol is added as a modifier to the tolerance in the feature control frame, Fig. 13.



Fig. 13. Tangent plane modifier

Free State: The free state modifier symbol is used when the geometric tolerance applies to the feature in its "free state," or after removal of any forces used in the manufacturing process. With removal of forces the part may distort due to gravity, flexibility, spring back, or other release of internal stresses developed during fabrication. Typical applications include parts with extremely thin walls and non-rigid parts made of rubber or plastics. The modifier is placed in the tolerance portion of the feature control frame and follows any other modifier.

The above examples are just a few of the numerous concepts and related symbols covered by ANSI/ASME Y14.5M-1994. Refer to the standard for a complete discussion with further examples of the application of geometric dimensioning and tolerancing principles.

Checking Drawings.— In order that the drawings may have a high standard of excellence, a set of instructions, as given in the following, has been issued to the checkers, and also to the draftsmen and tracers in the engineering department of a well-known machine-building company.

Inspecting a New Design: When a new design is involved, first inspect the layouts carefully to see that the parts function correctly under all conditions, that they have the proper relative proportions, that the general design is correct in the matters of strength, rigidity, bearing areas, appearance, convenience of assembly, and direction of motion of the parts, and that there are no interferences. Consider the design as a whole to see if any improvements can be made. If the design appears to be unsatisfactory in any particular, or improvements appear to be possible, call the matter to the attention of the chief engineer.

Checking for Strength: Inspect the design of the part being checked for strength, rigidity, and appearance by comparing it with other parts for similar service whenever possible, giving preference to the later designs in such comparison, unless the later designs are known to be unsatisfactory. If there is any question regarding the matter, compute the stresses and deformations or find out whether the chief engineer has approved the stresses or deformations that will result from the forces applied to the part in service. In checking parts that are to go on a machine of increased size, be sure that standard parts used in similar machines and proposed for use on the larger machine, have ample strength and rigidity under the new and more severe service to which they will be put.

Materials Specified: Consider the kind of material required for the part and the various possibilities of molding, forging, welding, or otherwise forming the rough part from this material. Then consider the machining operations to see whether changes in form or design will reduce the number of operations or the cost of machining.

See that parts are designed with reference to the economical use of material, and whenever possible, utilize standard sizes of stock and material readily obtainable from local

Copyright 2004, Industrial Press, Inc., New York, NY

dealers. In the case of alloy steel, special bronze, and similar materials, be sure that the material can be obtained in the size required.

Method of Making Drawing: Inspect the drawing to see that the projections and sections are made in such a way as to show most clearly the form of the piece and the work to be done on it. Make sure that any worker looking at the drawing will understand what the shape of the piece is and how it is to be molded or machined. Make sure that the delineation is correct in every particular, and that the information conveyed by the drawing as to the form of the piece is complete.

Checking Dimensions: Check all dimensions to see that they are correct. Scale all dimensions and see that the drawing is to scale. See that the dimensions on the drawing agree with the dimensions scaled from the lay-out. Wherever any dimension is out of scale, see that the dimension is so marked. Investigate any case where the dimension, the scale of the drawing, and the scale of the lay-out do not agree. All dimensions not to scale must be underlined on the tracing. In checking dimensions, note particularly the following points:

See that all figures are correctly formed and that they will print clearly, so that the workers can easily read them correctly.

See that the overall dimensions are given.

See that all witness lines go to the correct part of the drawing.

See that all arrow points go to the correct witness lines.

See that proper allowance is made for all fits.

See that the tolerances are correctly given where necessary.

See that all dimensions given agree with the corresponding dimensions of adjacent parts.

Be sure that the dimensions given on a drawing are those that the machinist will use, and that the worker will not be obliged to do addition or subtraction to obtain the necessary measurements for machining or checking his work.

Avoid strings of dimensions where errors can accumulate. It is generally better to give a number of dimensions from the same reference surface or center line.

When holes are to be located by boring on a horizontal spindle boring machine or other similar machine, give dimensions to centers of bored holes in rectangular coordinates and from the center lines of the first hole to be bored, so that the operator will not be obliged to add measurements or transfer gages.

Checking Assembly: See that the part can readily be assembled with the adjacent parts. If necessary, provide tapped holes for eyebolts and cored holes for tongs, lugs, or other methods of handling.

Make sure that, in being assembled, the piece will not interfere with other pieces already in place and that the assembly can be taken apart without difficulty.

Check the sum of a number of tolerances; this sum must not be great enough to permit two pieces that should not be in contact to come together.

Checking Castings: In checking castings, study the form of the pattern, the methods of molding, the method of supporting and venting the cores, and the effect of draft and rough molding on clearances.

Avoid undue metal thickness, and especially avoid thick and thin sections in the same casting.

Indicate all metal thicknesses, so that the molder will know what chaplets to use for supporting the cores.

See that ample fillets are provided, and that they are properly dimensioned.

See that the cores can be assembled in the mold without crushing or interference.

See that swelling, shrinkage, or misalignment of cores will not make trouble in machining.

See that the amount of extra material allowed for finishing is indicated.

Copyright 2004, Industrial Press, Inc., New York, NY

See that there is sufficient extra material for finishing on large castings to permit them to be "cleaned up," even though they warp. In such castings, make sure that the metal thickness will be sufficient after finishing, even though the castings do warp.

Make sure that sufficient sections are shown so that the pattern makers and molders will not be compelled to make assumptions about the form of any part of the casting. These details are particularly important when a number of sections of the casting are similar in form, while others differ slightly.

Checking Machined Parts: Study the sequences of operations in machining and see that all finish marks are indicated.

See that the finish marks are placed on the lines to which dimensions are given.

See that methods of machining are indicated where necessary.

Give all drill, reamer, tap, and rose bit sizes.

See that jig and gage numbers are indicated at the proper places.

See that all necessary bosses, lugs, and openings are provided for lifting, handling, clamping, and machining the piece.

See that adequate wrench room is provided for all nuts and bolt heads.

Avoid special tools, such as taps, drills, reamers, etc., unless such tools are specifically authorized.

Where parts are right- and left-hand, be sure that the hand is correctly designated. When possible, mark parts as symmetrical, so as to avoid having them right- and left-hand, but do not sacrifice correct design or satisfactory operation on this account.

When heat-treatment is required, the heat-treatment should be specified.

Check the title, size of machine, the scale, and the drawing number on both the drawing and the drawing record card.

Tapers for Machine Tool Spindles.— Various standard tapers have been used for the taper holes in the spindles of machine tools, such as drilling machines, lathes, milling machines, or other types requiring a taper hole for receiving either the shank of a cutter, an arbor, a center, or any tool or accessory requiring a tapering seat. The Morse taper represents a generally accepted standard for drilling machines.

Morse Tapers

Morse Taper	Taper per Foot	Morse Taper	Taper per Foot	Morse Taper	Taper per Foot
0	0.62460	2	0.59941	4	0.62326
1	0.59858	3	0.60235	5	0.63151

The headstock and tailstock spindles of lathes also have the Morse taper in most cases; but the Jarno, the Reed (which is the short Jarno), and the Brown & Sharpe have also been used. Milling machine spindles formerly had Brown & Sharpe tapers in most cases.

In 1927, the milling machine manufacturers of the National Machine Tool Builders' Association adopted a standard taper of 3½ inches per foot. This comparatively steep taper has the advantage of insuring instant release of arbors or adapters.

National Machine Tool Builders' Association Tapers

Taper Number[a]	Large End Diameter	Taper Number[a]	Large End Diameter
30	1¼	50	2¾
40	1¾	60	4¼

[a] Standard taper of 3½ inches per foot

The British Standard for milling machine spindles is also 3½ inches taper per foot and includes these large end diameters: 1⅜ inches, 1¾ inches, 2¾ inches, and 3¼ inches.

Copyright 2004, Industrial Press, Inc., New York, NY

ALLOWANCES AND TOLERANCES FOR FITS

Limits and Fits

Fits between cylindrical parts, i.e., cylindrical fits, govern the proper assembly and performance of many mechanisms. Clearance fits permit relative freedom of motion between a shaft and a hole—axially, radially, or both. Interference fits secure a certain amount of tightness between parts, whether these are meant to remain permanently assembled or to be taken apart from time to time. Or again, two parts may be required to fit together snugly—without apparent tightness or looseness. The designer's problem is to specify these different types of fits in such a way that the shop can produce them. Establishing the specifications requires the adoption of two manufacturing limits for the hole and two for the shaft, and, hence, the adoption of a manufacturing tolerance on each part.

In selecting and specifying limits and fits for various applications, it is essential in the interests of interchangeable manufacturing that 1) standard definitions of terms relating to limits and fits be used; 2) preferred basic sizes be selected wherever possible to reduce material and tooling costs; 3) limits be based upon a series of preferred tolerances and allowances; and 4) a uniform system of applying tolerances (preferably unilateral) be used. These principles have been incorporated in both the American and British standards for limits and fits. Information about these standards is given beginning on page 651.

Basic Dimensions.— The basic size of a screw thread or machine part is the theoretical or nominal standard size from which variations are made. For example, a shaft may have a *basic* diameter of 2 inches, but a maximum variation of minus 0.010 inch may be permitted. The minimum hole should be of basic size wherever the use of standard tools represents the greatest economy. The maximum shaft should be of basic size wherever the use of standard purchased material, without further machining, represents the greatest economy, even though special tools are required to machine the mating part.

Tolerances.— Tolerance is the amount of variation permitted on dimensions or surfaces of machine parts. The tolerance is equal to the difference between the maximum and minimum limits of any specified dimension. For example, if the maximum limit for the diameter of a shaft is 2.000 inches and its minimum limit 1.990 inches, the tolerance for this diameter is 0.010 inch. The extent of these tolerances is established by determining the maximum and minimum clearances required on operating surfaces. As applied to the fitting of machine parts, the word tolerance means the amount that duplicate parts are allowed to vary in size in connection with manufacturing operations, owing to unavoidable imperfections of workmanship. Tolerance may also be defined as the amount that duplicate parts are permitted to vary in size to secure sufficient accuracy without unnecessary refinement. The terms "tolerance" and "allowance" are often used interchangeably, but, according to common usage, *allowance* is a difference in dimensions prescribed to secure various classes of fits between different parts.

Unilateral and Bilateral Tolerances.— The term "unilateral tolerance" means that the total tolerance, as related to a basic dimension, is in *one* direction only. For example, if the basic dimension were 1 inch and the tolerance were expressed as 1.000 – 0.002, or as 1.000 + 0.002, these would be unilateral tolerances because the total tolerance in each is in one direction. On the contrary, if the tolerance were divided, so as to be partly plus and partly minus, it would be classed as "bilateral."

$$\text{Thus,} \qquad 1.000 \begin{matrix} +0.001 \\ -0.001 \end{matrix}$$

is an example of bilateral tolerance, because the total tolerance of 0.002 is given in two directions—plus and minus.

When unilateral tolerances are used, one of the three following methods should be used to express them:

Copyright 2004, Industrial Press, Inc., New York, NY

1) Specify, limiting dimensions only as
Diameter of hole: 2.250, 2.252
Diameter of shaft: 2.249, 2.247
2) One limiting size may be specified with its tolerances as
Diameter of hole: $2.250 + 0.002, -0.000$
Diameter of shaft: $2.249 + 0.000, -0.002$
3) The nominal size may be specified for both parts, with a notation showing both allowance and tolerance, as
Diameter of hole: $2\frac{1}{4} + 0.002, -0.000$
Diameter of shaft: $2\frac{1}{4} - 0.001, -0.003$

Bilateral tolerances should be specified as such, usually with plus and minus tolerances of equal amount. An example of the expression of bilateral tolerances is

$$2 \pm 0.001 \text{ or } 2\ ^{+0.001}_{-0.001}$$

Application of Tolerances.— According to common practice, tolerances are applied in such a way as to show the permissible amount of dimensional variation in the direction that is less dangerous. When a variation in either direction is equally dangerous, a bilateral tolerance should be given. When a variation in one direction is more dangerous than a variation in another, a unilateral tolerance should be given in the less dangerous direction.

For nonmating surfaces, or atmospheric fits, the tolerances may be bilateral, or unilateral, depending entirely upon the nature of the variations that develop in manufacture. On mating surfaces, with few exceptions, the tolerances should be unilateral.

Where tolerances are required on the distances between holes, usually they should be bilateral, as variation in either direction is normally equally dangerous. The variation in the distance between shafts carrying gears, however, should always be unilateral and plus; otherwise, the gears might run too tight. A slight increase in the backlash between gears is seldom of much importance.

One exception to the use of unilateral tolerances on mating surfaces occurs when tapers are involved; either bilateral or unilateral tolerances may then prove advisable, depending upon conditions. These tolerances should be determined in the same manner as the tolerances on the distances between holes. When a variation either in or out of the position of the mating taper surfaces is equally dangerous, the tolerances should be bilateral. When a variation in one direction is of less danger than a variation in the opposite direction, the tolerance should be unilateral and in the less dangerous direction.

Locating Tolerance Dimensions.— Only one dimension in the same straight line can be controlled within fixed limits. That dimension is the distance between the cutting surface of the tool and the locating or registering surface of the part being machined. Therefore, it is incorrect to locate any point or surface with tolerances from more than one point in the same straight line.

Every part of a mechanism must be located in each plane. Every operating part must be located with proper operating allowances. After such requirements of location are met, all other surfaces should have liberal clearances. Dimensions should be given between those points or surfaces that it is essential to hold in a specific relation to each other. This restriction applies particularly to those surfaces in each plane that control the location of other component parts. Many dimensions are relatively unimportant in this respect. It is good practice to establish a common locating point in each plane and give, as far as possible, all such dimensions from these common locating points. The locating points on the drawing, the locatingor registering points used for machining the surfaces and the locating points for measuring should all be identical.

The initial dimensions placed on component drawings should be the exact dimensions that would be used if it were possible to work without tolerances. Tolerances should be

Copyright 2004, Industrial Press, Inc., New York, NY

given in that direction in which variations will cause the least harm or danger. When a variation in either direction is equally dangerous, the tolerances should be of equal amount in both directions, or bilateral. The initial clearance, or allowance, between operating parts should be as small as the operation of the mechanism will permit. The maximum clearance should be as great as the proper functioning of the mechanism will permit.

Direction of Tolerances on Gages.— The extreme sizes for all plain limit gages shall not exceed the extreme limits of the part to be gaged. All variations in the gages, whatever their cause or purpose, shall bring these gages within these extreme limits.

The data for gage tolerances on page 678 cover gages to inspect workpieces held to tolerances in the American National Standard ANSI B4.4M-1981.

Allowance for Forced Fits.— The allowance per inch of diameter usually ranges from 0.001 inch to 0.0025 inch, 0.0015 being a fair average. Ordinarily the allowance per inch decreases as the diameter increases; thus the total allowance for a diameter of 2 inches might be 0.004 inch, whereas for a diameter of 8 inches the total allowance might not be over 0.009 or 0.010 inch. The parts to be assembled by forced fits are usually made cylindrical, although sometimes they are slightly tapered. The advantages of the taper form are that the possibility of abrasion of the fitted surfaces is reduced; that less pressure is required in assembling; and that the parts are more readily separated when renewal is required. On the other hand, the taper fit is less reliable, because if it loosens, the entire fit is free with but little axial movement. Some lubricant, such as white lead and lard oil mixed to the consistency of paint, should be applied to the pin and bore before assembling, to reduce the tendency toward abrasion.

Pressure for Forced Fits.— The pressure required for assembling cylindrical parts depends not only upon the allowance for the fit, but also upon the area of the fitted surfaces, the pressure increasing in proportion to the distance that the inner member is forced in. The approximate ultimate pressure in tons can be determined by the use of the following formula in conjunction with the accompanying table of *Pressure Factors for Forced Fits*. Assuming that A = area of surface in contact in "fit"; a = total allowance in inches; P = ultimate pressure required, in tons; F = pressure factor based upon assumption that the diameter of the hub is twice the diameter of the bore, that the shaft is of machine steel, and that the hub is of cast iron:

$$P = \frac{A \times a \times F}{2}$$

Pressure Factors for Forced Fits

Diameter, Inches	Pressure Factor	Diameter, Inches	Pressure Factor	Diameter, Inches	Pressure Factor	Diameter, Inches	Pressure Factor	Diameter, Inches	Pressure Factor
1	500	3½	132	6	75	9	48.7	14	30.5
1¼	395	3¾	123	6¼	72	9½	46.0	14½	29.4
1½	325	4	115	6½	69	10	43.5	15	28.3
1¾	276	4¼	108	6¾	66	10½	41.3	15½	27.4
2	240	4½	101	7	64	11	39.3	16	26.5
2¼	212	4¾	96	7¼	61	11½	37.5	16½	25.6
2½	189	5	91	7½	59	12	35.9	17	24.8
2¾	171	5¼	86	7¾	57	12½	34.4	17½	24.1
3	156	5½	82	8	55	13	33.0	18	23.4
3¼	143	5¾	78	8½	52	13½	31.7	…	…

Allowance for Given Pressure.— By transposing the preceding formula, the approximate allowance for a required ultimate tonnage can be determined. Thus, $a = \frac{2P}{AF}$. The

Copyright 2004, Industrial Press, Inc., New York, NY

average ultimate pressure in tons commonly used ranges from 7 to 10 times the diameter in inches.

Expansion Fits.— In assembling certain classes of work requiring a very tight fit, the inner member is contracted by sub-zero cooling to permit insertion into the outer member and a tight fit is obtained as the temperature rises and the inner part expands. To obtain the sub-zero temperature, solid carbon dioxide or "dry ice" has been used but its temperature of about 109 degrees F. below zero will not contract some parts sufficiently to permit insertion in holes or recesses. Greater contraction may be obtained by using high purity liquid nitrogen which has a temperature of about 320 degrees F. below zero. During a temperature reduction from 75 degrees F. to –321 degrees F., the shrinkage per inch of diameter varies from about 0.002 to 0.003 inch for steel; 0.0042 inch for aluminum alloys; 0.0046 inch for magnesium alloys; 0.0033 inch for copper alloys; 0.0023 inch for monel metal; and 0.0017 inch for cast iron (not alloyed). The cooling equipment may vary from an insulated bucket to a special automatic unit, depending upon the kind and quantity of work. One type of unit is so arranged that parts are precooled by vapors from the liquid nitrogen before immersion. With another type, cooling is entirely by the vapor method.

Shrinkage Fits.— General practice seems to favor a smaller allowance for shrinkage fits than for forced fits, although in many shops the allowances are practically the same for each, and for some classes of work, shrinkage allowances exceed those for forced fits. The shrinkage allowance also varies to a great extent with the form and construction of the part that has to be shrunk into place. The thickness or amount of metal around the hole is the most important factor. The way in which the metal is distributed also has an influence on the results. Shrinkage allowances for locomotive driving wheel tires adopted by the American Railway Master Mechanics Association are as follows:

Center diameter, inches	38	44	50	56	62	66
Allowances, inches	0.040	0.047	0.053	0.060	0.066	0.070

Whether parts are to be assembled by forced or shrinkage fits depends upon conditions. For example, to press a tire over its wheel center, without heating, would ordinarily be a rather awkward and difficult job. On the other hand, pins, etc., are easily and quickly forced into place with a hydraulic press and there is the additional advantage of knowing the exact pressure required in assembling, whereas there is more or less uncertainty connected with a shrinkage fit, unless the stresses are calculated. Tests to determine the difference in the quality of shrinkage and forced fits showed that the resistance of a shrinkage fit to slippage for an axial pull was 3.66 times greater than that of a forced fit, and in rotation or torsion, 3.2 times greater. In each comparative test, the dimensions and allowances were the same.

Allowances for Shrinkage Fits.— The most important point to consider when calculating shrinkage fits is the stress in the hub at the bore, which depends chiefly upon the shrinkage allowance. If the allowance is excessive, the elastic limit of the material will be exceeded and permanent set will occur, or, in extreme conditions, the ultimate strength of the metal will be exceeded and the hub will burst. The intensity of the grip of the fit and the resistance to slippage depends mainly upon the thickness of the hub; the greater the thickness, the stronger the grip, and *vice versa*. Assuming the modulus of elasticity for steel to be 30,000,000, and for cast iron, 15,000,000, the shrinkage allowance per inch of nominal diameter can be determined by the following formula, in which A = allowance per inch of diameter; T = true tangential tensile stress at inner surface of outer member; C = factor taken from one of the accompanying Tables 1, 2, and 3.

For a cast-iron hub and steel shaft:

$$A = \frac{T(2 + C)}{30{,}000{,}000} \quad (1)$$

Copyright 2004, Industrial Press, Inc., New York, NY

When both hub and shaft are of steel:

$$A = \frac{T(1 + C)}{30{,}000{,}000} \quad (2)$$

If the shaft is solid, the factor C is taken from Table 1; if it is hollow and the hub is of steel, factor C is taken from Table 2; if it is hollow and the hub is of cast iron, the factor is taken from Table 3.

Table 1. Factors for Calculating Shrinkage Fit Allowances for Steel Shafts and Steel or Cast Iron Hubs

Ratio of Diameters $\frac{D_2}{D_1}$	Steel Hub	Cast-iron Hub	Ratio of Diameters $\frac{D_2}{D_1}$	Steel Hub	Cast-iron Hub
	C			C	
1.5	0.227	0.234	2.8	0.410	0.432
1.6	0.255	0.263	3.0	0.421	0.444
1.8	0.299	0.311	3.2	0.430	0.455
2.0	0.333	0.348	3.4	0.438	0.463
2.2	0.359	0.377	3.6	0.444	0.471
2.4	0.380	0.399	3.8	0.450	0.477
2.6	0.397	0.417	4.0	0.455	0.482

Values of factor C for solid steel shafts of nominal diameter D_1, and hubs of steel or cast iron of nominal external and internal diameters D_2 and D_1, respectively.

Example 1: A steel crank web 15 inches outside diameter is to be shrunk on a 10-inch solid steel shaft. Required the allowance per inch of shaft diameter to produce a maximum tensile stress in the crank of 25,000 pounds per square inch, assuming the stresses in the crank to be equivalent to those in a ring of the diameter given.

The ratio of the external to the internal diameters equals $15 \div 10 = 1.5$; $T = 25{,}000$ pounds; from Table 1, $C = 0.227$. Substituting in Formula (2):

$$A = \frac{25{,}000 \times (1 + 0.227)}{30{,}000{,}000} = 0.001 \text{ inch}$$

Example 2: Find the allowance per inch of diameter for a 10-inch shaft having a 5-inch axial through hole, other conditions being the same as in Example 1.

The ratio of external to internal diameters of the hub equals $15 \div 10 = 1.5$, as before, and the ratio of external to internal diameters of the shaft equals $10 \div 5 = 2$. From Table 2, we find that factor $C = 0.455$; $T = 25{,}000$ pounds. Substituting these values in Formula (2):

$$A = \frac{25{,}000(1 + 0.455)}{30{,}000{,}000} = 0.0012 \text{ inch}$$

The allowance is increased, as compared with Example 1, because the hollow shaft is more compressible.

Example 3: If the crank web in Example 1 is of cast iron and 4000 pounds per square inch is the maximum tensile stress in the hub, what is the allowance per inch of diameter?

$$\frac{D_2}{D_1} = 1.5 \qquad T = 4000$$

In Table 1, we find that $C = 0.234$. Substituting in Formula (1), for cast-iron hubs, $A = 0.0003$ inch, which, owing to the lower tensile strength of cast iron, is about one-third the shrinkage allowance in Example 1, although the stress is two-thirds of the elastic limit.

Temperatures for Shrinkage Fits.— The temperature to which the outer member in a shrinkage fit should be heated for clearance in assembling the parts depends on the total

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Factors for Calculating Shrinkage Fit Allowances for Hollow Steel Shafts and Steel Hubs

$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a	$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a	$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a
1.5	2.0	0.455	2.4	2.0	0.760	3.4	2.0	0.876
	2.5	0.357		2.5	0.597		2.5	0.689
	3.0	0.313		3.0	0.523		3.0	0.602
	3.5	0.288		3.5	0.481		3.5	0.555
1.6	2.0	0.509	2.6	2.0	0.793	3.6	2.0	0.888
	2.5	0.400		2.5	0.624		2.5	0.698
	3.0	0.350		3.0	0.546		3.0	0.611
	3.5	0.322		3.5	0.502		3.5	0.562
1.8	2.0	0.599	2.8	2.0	0.820	3.8	2.0	0.900
	2.5	0.471		2.5	0.645		2.5	0.707
	3.0	0.412		3.0	0.564		3.0	0.619
	3.5	0.379		3.5	0.519		3.5	0.570
2.0	2.0	0.667	3.0	2.0	0.842	4.0	2.0	0.909
	2.5	0.524		2.5	0.662		2.5	0.715
	3.0	0.459		3.0	0.580		3.0	0.625
	3.5	0.422		3.5	0.533		3.5	0.576
2.2	2.0	0.718	3.2	2.0	0.860	…	…	…
	2.5	0.565		2.5	0.676		…	…
	3.0	0.494		3.0	0.591		…	…
	3.5	0.455		3.5	0.544		…	…

[a] Values of factor C for hollow steel shafts of external and internal diameters D_1 and D_0, respectively, and steel hubs of nominal external diameter D_2.

Table 3. Factors for Calculating Shrinkage Fit Allowances for Hollow Steel Shafts and Cast-iron Hubs

$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a	$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a	$\frac{D_2}{D_1}$	$\frac{D_1}{D_0}$	C^a
1.5	2.0	0.468	2.4	2.0	0.798	3.4	2.0	0.926
	2.5	0.368		2.5	0.628		2.5	0.728
	3.0	0.322		3.0	0.549		3.0	0.637
	3.5	0.296		3.5	0.506		3.5	0.587
1.6	2.0	0.527	2.6	2.0	0.834	3.6	2.0	0.941
	2.5	0.414		2.5	0.656		2.5	0.740
	3.0	0.362		3.0	0.574		3.0	0.647
	3.5	0.333		3.5	0.528		3.5	0.596
1.8	2.0	0.621	2.8	2.0	0.864	3.8	2.0	0.953
	2.5	0.488		2.5	0.679		2.5	0.749
	3.0	0.427		3.0	0.594		3.0	0.656
	3.5	0.393		3.5	0.547		3.5	0.603
2.0	2.0	0.696	3.0	2.0	0.888	4.0	2.0	0.964
	2.5	0.547		2.5	0.698		2.5	0.758
	3.0	0.479		3.0	0.611		3.0	0.663
	3.5	0.441		3.5	0.562		3.5	0.610
2.2	2.0	0.753	3.2	2.0	0.909	…	…	…
	2.5	0.592		2.5	0.715		…	…
	3.0	0.518		3.0	0.625		…	…
	3.5	0.477		3.5	0.576		…	…

[a] Values of factor C for hollow steel shafts and cast-iron hubs. Notation as in Table 2.

Copyright 2004, Industrial Press, Inc., New York, NY

expansion required and on the coefficient α of linear expansion of the metal (i.e., the increase in length of any section of the metal in any direction for an increase in temperature of 1 degree F). The total expansion in diameter that is required consists of the total allowance for shrinkage and an added amount for clearance. The value of the coefficient α is, for nickel-steel, 0.000007; for steel in general, 0.0000065; for cast iron, 0.0000062. As an example, take an outer member of steel to be expanded 0.005 inch per inch of internal diameter, 0.001 being the shrinkage allowance and the remainder for clearance. Then

$$\alpha \times t^{\circ} = 0.005$$

$$t = \frac{0.005}{0.0000065} = 769 \text{ degrees F}$$

The value t is the number of degrees F that the temperature of the member must be raised above that of the room temperature.

ANSI Standard Limits and Fits

This American National Standard for Preferred Limits and Fits for Cylindrical Parts, ANSI B4.1-1967 (R1999), presents definitions of terms applying to fits between plain (non threaded) cylindrical parts and makes recommendations on preferred sizes, allowances, tolerances, and fits for use wherever they are applicable. This standard is in accord with the recommendations of American-British-Canadian (ABC) conferences up to a diameter of 20 inches. Experimental work is being carried on with the objective of reaching agreement in the range above 20 inches. The recommendations in the standard are presented for guidance and for use where they might serve to improve and simplify products, practices, and facilities. They should have application for a wide range of products.

As revised in 1967, and reaffirmed in 1999, the definitions in ANSI B4.1 have been expanded and some of the limits in certain classes have been changed.

Factors Affecting Selection of Fits.— Many factors, such as length of engagement, bearing load, speed, lubrication, temperature, humidity, and materials must be taken into consideration in the selection of fits for a particular application, and modifications in the ANSI recommendations may be required to satisfy extreme conditions. Subsequent adjustments may also be found desirable as a result of experience in a particular application to suit critical functional requirements or to permit optimum manufacturing economy.

Definitions.— The following terms are defined in this standard:

Nominal Size: The nominal size is the designation used for the purpose of general identification.

Dimension: A dimension is a geometrical characteristic such as diameter, length, angle, or center distance.

Size: Size is a designation of magnitude. When a value is assigned to a dimension, it is referred to as the size of that dimension. (It is recognized that the words "dimension" and "size" are both used at times to convey the meaning of magnitude.)

Allowance: An allowance is a prescribed difference between the maximum material limits of mating parts. (See definition of *Fit*). It is a minimum clearance (positive allowance) or maximum interference (negative allowance) between such parts.

Tolerance: A tolerance is the total permissible variation of a size. The tolerance is the difference between the limits of size.

Basic Size: The basic size is that size from which the limits of size are derived by the application of allowances and tolerances.

Design Size: The design size is the basic size with allowance applied, from which the limits of size are derived by the application of tolerances. Where there is no allowance, the design size is the same as the basic size.

Actual Size: An actual size is a measured size.

Limits of Size: The limits of size are the applicable maximum and minimum sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Maximum Material Limit: A maximum material limit is that limit of size that provides the maximum amount of material for the part. Normally it is the maximum limit of size of an external dimension or the minimum limit of size of an internal dimension.*

Minimum Material Limit: A minimum material limit is that limit of size that provides the minimum amount of material for the part. Normally it is the minimum limit of size of an external dimension or the maximum limit of size of an internal dimension.*

Tolerance Limit: A tolerance limit is the variation, positive or negative, by which a size is permitted to depart from the design size.

Unilateral Tolerance: A unilateral tolerance is a tolerance in which variation is permitted in only one direction from the design size.

Bilateral Tolerance: A bilateral tolerance is a tolerance in which variation is permitted in both directions from the design size.

Unilateral Tolerance System: A design plan that uses only unilateral tolerances is known as a Unilateral Tolerance System.

Bilateral Tolerance System: A design plan that uses only bilateral tolerances is known as a Bilateral Tolerance System.

Fits.— *Fit:* Fit is the general term used to signify the range of tightness that may result from the application of a specific combination of allowances and tolerances in the design of mating parts.

Actual Fit: The actual fit between two mating parts is the relation existing between them with respect to the amount of clearance or interference that is present when they are assembled. (Fits are of three general types: clearance, transition, and interference.)

Clearance Fit: A clearance fit is one having limits of size so specified that a clearance always results when mating parts are assembled.

Interference Fit: An interference fit is one having limits of size so specified that an interference always results when mating parts are assembled.

Transition Fit: A transition fit is one having limits of size so specified that either a clearance or an interference may result when mating parts are assembled.

Basic Hole System: A basic hole system is a system of fits in which the design size of the hole is the basic size and the allowance, if any, is applied to the shaft.

Basic Shaft System: A basic shaft system is a system of fits in which the design size of the shaft is the basic size and the allowance, if any, is applied to the hole.

Preferred Basic Sizes.— In specifying fits, the basic size of mating parts shall be chosen from the decimal series or the fractional series in Table 4.

Prefered Series for Tolerances and Allowances.— All fundamental tolerances and allowances of all shafts and holes have been taken from the series given in Table 5.

Standard Tolerances.— The series of standard tolerances shown in Table 6 are so arranged that for any one grade they represent approximately similar production difficulties throughout the range of sizes. This table provides a suitable range from which appropriate tolerances for holes and shafts can be selected and enables standard gages to be used. The tolerances shown in Table 6 have been used in the succeeding tables for different classes of fits.

Table 7 graphically illustrates the range of tolearance grades that various machining processes may produce under normal conditions.

ANSI Standard Fits.— Tables 8a through 12 inclusive show a series of standard types and classes of fits on a unilateral hole basis, such that the fit produced by mating parts in any one class will produce approximately similar performance throughout the range of sizes. These tables prescribe the fit for any given size, or type of fit; they also prescribe the

* An example of exceptions: an exterior corner radius where the maximum radius is the minimum material limit and the minimum radius is the maximum material limit.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Preferred Basic Sizes *ANSI B4.1-1967 (R1999)*

Decimal[a]			Fractional[a]					
0.010	2.00	8.50	1/64	0.015625	2 1/4	2.2500	9 1/2	9.5000
0.012	2.20	9.00	1/32	0.03125	2 1/2	2.5000	10	10.0000
0.016	2.40	9.50	1/16	0.0625	2 3/4	2.7500	10 1/2	10.5000
0.020	2.60	10.00	3/32	0.09375	3	3.0000	11	11.0000
0.025	2.80	10.50	1/8	0.1250	3 1/4	3.2500	11 1/2	11.5000
0.032	3.00	11.00	5/32	0.15625	3 1/2	3.5000	12	12.0000
0.040	3.20	11.50	3/16	0.1875	3 3/4	3.7500	12 1/2	12.5000
0.05	3.40	12.00	1/4	0.2500	4	4.0000	13	13.0000
0.06	3.60	12.50	5/16	0.3125	4 1/4	4.2500	13 1/2	13.5000
0.08	3.80	13.00	3/8	0.3750	4 1/2	4.5000	14	14.0000
0.10	4.00	13.50	7/16	0.4375	4 3/4	4.7500	14 1/2	14.5000
0.12	4.20	14.00	1/2	0.5000	5	5.0000	15	15.0000
0.16	4.40	14.50	9/16	0.5625	5 1/4	5.2500	15 1/2	15.5000
0.20	4.60	15.00	5/8	0.6250	5 1/2	5.5000	16	16.0000
0.24	4.80	15.50	11/16	0.6875	5 3/4	5.7500	16 1/2	16.5000
0.30	5.00	16.00	3/4	0.7500	6	6.0000	17	17.0000
0.40	5.20	16.50	7/8	0.8750	6 1/2	6.5000	17 1/2	17.5000
0.50	5.40	17.00	1	1.0000	7	7.0000	18	18.0000
0.60	5.60	17.50	1 1/4	1.2500	7 1/2	7.5000	18 1/2	18.5000
0.80	5.80	18.00	1 1/2	1.5000	8	8.0000	19	19.0000
1.00	6.00	18.50	1 3/4	1.7500	8 1/2	8.5000	19 1/2	19.5000
1.20	6.50	19.00	2	2.0000	9	9.0000	20	20.0000
1.40	7.00	19.50	…	…	…	…	…	…
1.60	7.50	20.00	…	…	…	…	…	…
1.80	8.00	…	…	…	…	…	…	…

[a] All dimensions are in inches.

Table 5. Preferred Series of Tolerances and Allowances [a] *ANSI B4.1-1967 (R1999)*

0.1	1	10	100	0.3	3	30	…
…	1.2	12	125	…	3.5	35	…
0.15	1.4	14	…	0.4	4	40	…
…	1.6	16	160	…	4.5	45	…
…	1.8	18	…	0.5	5	50	…
0.2	2	20	200	0.6	6	60	…
…	2.2	22	…	0.7	7	70	…
0.25	2.5	25	250	0.8	8	80	…
…	2.8	28	…	0.9	9	…	…

[a] All values in thousandths of an inch

standard limits for the mating parts that will produce the fit. The fits listed in these tables contain all those that appear in the approved American-British-Canadian proposal.

Selection of Fits: In selecting limits of size for any application, the type of fit is determined first, based on the use or service required from the equipment being designed; then the limits of size of the mating parts are established, to insure that the desired fit will be produced.

Theoretically, an infinite number of fits could be chosen, but the number of standard fits shown in the accompanying tables should cover most applications.

Designation of Standard Fits: Standard fits are designated by means of the following symbols which, facilitate reference to classes of fit for educational purposes. The symbols are not intended to be shown on manufacturing drawings; instead, sizes should be specified on drawings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ANSI Standard Tolerances *ANSI B4.1-1967 (R1999)*

Nominal Size, Inches		Grade									
		4	5	6	7	8	9	10	11	12	13
Over	To	Tolerances in thousandths of an inch[a]									
0	0.12	0.12	0.15	0.25	0.4	0.6	1.0	1.6	2.5	4	6
0.12	0.24	0.15	0.20	0.3	0.5	0.7	1.2	1.8	3.0	5	7
0.24	0.40	0.15	0.25	0.4	0.6	0.9	1.4	2.2	3.5	6	9
0.40	0.71	0.2	0.3	0.4	0.7	1.0	1.6	2.8	4.0	7	10
0.71	1.19	0.25	0.4	0.5	0.8	1.2	2.0	3.5	5.0	8	12
1.19	1.97	0.3	0.4	0.6	1.0	1.6	2.5	4.0	6	10	16
1.97	3.15	0.3	0.5	0.7	1.2	1.8	3.0	4.5	7	12	18
3.15	4.73	0.4	0.6	0.9	1.4	2.2	3.5	5	9	14	22
4.73	7.09	0.5	0.7	1.0	1.6	2.5	4.0	6	10	16	25
7.09	9.85	0.6	0.8	1.2	1.8	2.8	4.5	7	12	18	28
9.85	12.41	0.6	0.9	1.2	2.0	3.0	5.0	8	12	20	30
12.41	15.75	0.7	1.0	1.4	2.2	3.5	6	9	14	22	35
15.75	19.69	0.8	1.0	1.6	2.5	4	6	10	16	25	40
19.69	30.09	0.9	1.2	2.0	3	5	8	12	20	30	50
30.09	41.49	1.0	1.6	2.5	4	6	10	16	25	40	60
41.49	56.19	1.2	2.0	3	5	8	12	20	30	50	80
56.19	76.39	1.6	2.5	4	6	10	16	25	40	60	100
76.39	100.9	2.0	3	5	8	12	20	30	50	80	125
100.9	131.9	2.5	4	6	10	16	25	40	60	100	160
131.9	171.9	3	5	8	12	20	30	50	80	125	200
171.9	200	4	6	10	16	25	40	60	100	160	250

[a] All tolerances above heavy line are in accordance with American-British-Canadian (ABC) agreements.

Table 7. Relation of Machining Processes to Tolerance Grades *ANSI B4.1-1967 (R1999)*

This chart may be used as a general guide to determine the machining processes that will under normal conditions, produce work withen the tolerance grades indicated.

(See also *Relation of Surface Roughness to Tolerances* starting on page 729.



The letter symbols used to designate standard fits are as follows:

RC = Running or Sliding Clearance Fit *LC* = Locational Clearance Fit

LT = Transition Clearance or Interference Fit

LN = Locational Interference Fit

FN = Force or Shrink Fit

Copyright 2004, Industrial Press, Inc., New York, NY

These letter symbols are used in conjunction with numbers representing the class of fit; thus FN 4 represents a Class 4, force fit.

Each of these symbols (two letters and a number) represents a complete fit for which the minimum and maximum clearance or interference and the limits of size for the mating parts are given directly in the tables.

Description of Fits.— The classes of fits are arranged in three general groups: running and sliding fits, locational fits, and force fits.

Running and Sliding Fits (RC): Running and sliding fits, for which limits of clearance are given in Table 8a, are intended to provide a similar running performance, with suitable lubrication allowance, throughout the range of sizes. The clearances for the first two classes, used chiefly as slide fits, increase more slowly with the diameter than for the other classes, so that accurate location is maintained even at the expense of free relative motion.

These fits may be described as follows:

RC 1 *Close sliding fits* are intended for the accurate location of parts that must assemble without perceptible play.

RC 2 *Sliding fits* are intended for accurate location, but with greater maximum clearance than class RC 1. Parts made to this fit move and turn easily but are not intended to run freely, and in the larger sizes may seize with small temperature changes.

RC 3 *Precision running fits* are about the closest fits that can be expected to run freely, and are intended for precision work at slow speeds and light journal pressures, but are not suitable where appreciable temperature differences are likely to be encountered.

RC 4 *Close running fits* are intended chiefly for running fits on accurate machinery with moderate surface speeds and journal pressures, where accurate location and minimum play are desired.

RC 5 and RC 6 *Medium running fits* are intended for higher running speeds, or heavy journal pressures, or both.

RC 7 *Free running fits* are intended for use where accuracy is not essential, or where large temperature variations are likely to be encountered, or under both these conditions.

RC 8 and RC 9 *Loose running fits* are intended for use where wide commercial tolerances may be necessary, together with an allowance, on the external member.

Locational Fits (LC, LT, and LN): Locational fits are fits intended to determine only the location of the mating parts; they may provide rigid or accurate location, as with interference fits, or provide some freedom of location, as with clearance fits. Accordingly, they are divided into three groups: clearance fits (LC), transition fits (LT), and interference fits (LN).

These are described as follows:

LC *Locational clearance fits* are intended for parts which are normally stationary, but that can be freely assembled or disassembled. They range from snug fits for parts requiring accuracy of location, through the medium clearance fits for parts such as spigots, to the looser fastener fits where freedom of assembly is of prime importance.

LT *Locational transition fits* are a compromise between clearance and interference fits, for applications where accuracy of location is important, but either a small amount of clearance or interference is permissible.

LN *Locational interference fits* are used where accuracy of location is of prime importance, and for parts requiring rigidity and alignment with no special requirements for bore pressure. Such fits are not intended for parts designed to transmit frictional loads from one part to another by virtue of the tightness of fit. These conditions are covered by force fits.

Force Fits: (FN): Force or shrink fits constitute a special type of interference fit, normally characterized by maintenance of constant bore pressures throughout the range of sizes. The interference therefore varies almost directly with diameter, and the difference

Copyright 2004, Industrial Press, Inc., New York, NY

between its minimum and maximum value is small, to maintain the resulting pressures within reasonable limits.

These fits are described as follows:

FN 1 *Light drive fits* are those requiring light assembly pressures, and produce more or less permanent assemblies. They are suitable for thin sections or long fits, or in cast-iron external members.

FN 2 *Medium drive fits* are suitable for ordinary steel parts, or for shrink fits on light sections. They are about the tightest fits that can be used with high-grade cast-iron external members.

FN 3 *Heavy drive fits* are suitable for heavier steel parts or for shrink fits in medium sections.

FN 4 and FN 5 *Force fits* are suitable for parts that can be highly stressed, or for shrink fits where the heavy pressing forces required are impractical.

Graphical Representation of Limits and Fits.— A visual comparison of the hole and shaft tolerances and the clearances or interferences provided by the various types and classes of fits can be obtained from the diagrams on page 657. These diagrams have been drawn to scale for a nominal diameter of 1 inch.

Use of Standard Fit Tables.— *Example 1:* A Class RC 1 fit is to be used in assembling a mating hole and shaft of 2-inch nominal diameter. This class of fit was selected because the application required accurate location of the parts with no perceptible play (see *Description of Fits*, RC 1 close sliding fits). From the data in Table 8a, establish the limits of size and clearance of the hole and shaft.

Maximum hole = 2 + 0.0005 = 2.0005; minimum hole = 2 inches

Maximum shaft = 2 – 0.0004 = 1.9996; minimum shaft = 2 – 0.0007 = 1.9993 inches

Minimum clearance = 0.0004; maximum clearance = 0.0012 inch

Modified Standard Fits.— Fits having the same limits of clearance or interference as those shown in Tables 8a to 12 may sometimes have to be produced by using holes or shafts having limits of size other than those shown in these tables. These modifications may be accomplished by using either a *Bilateral Hole System* (*Symbol B*) or a *Basic Shaft System* (*Symbol S*). Both methods will result in nonstandard holes and shafts.

Bilateral Hole Fits (Symbol B): The common situation is where holes are produced with fixed tools such as drills or reamers; to provide a longer wear life for such tools, a bilateral tolerance is desired.

The symbols used for these fits are identical with those used for standard fits except that they are followed by the letter B. Thus, LC 4B is a clearance locational fit, Class 4, except that it is produced with a bilateral hole.

The limits of clearance or interference are identical with those shown in Tables 8a to 12 for the corresponding fits.

The hole tolerance, however, is changed so that the plus limit is that for one grade finer than the value shown in the tables and the minus limit equals the amount by which the plus limit was lowered. The shaft limits are both lowered by the same amount as the lower limit of size of the hole. The finer grade of tolerance required to make these modifications may be obtained from Table 6. For example, an LC 4B fit for a 6-inch diameter hole would have tolerance limits of +4.0, –2.0 (+0.0040 inch, – 0.0020 inch); the shaft would have tolerance limits of –2.0, –6.0 (–0.0020 inch, –0.0060 inch).

Basic Shaft Fits (Symbol S): For these fits, the maximum size of the shaft is basic. The limits of clearance or interference are identical with those shown in Tables 8a to 12 for the corresponding fits and the symbols used for these fits are identical with those used for standard fits except that they are followed by the letter S. Thus, LC 4S is a clearance locational fit, Class 4, except that it is produced on a basic shaft basis.

Copyright 2004, Industrial Press, Inc., New York, NY

The limits for hole and shaft as given in Tables 8a to 12 are increased for clearance fits (*decreased* for transition or interference fits) by the value of the upper shaft limit; that is, by the amount required to change the maximum shaft to the basic size.

Graphical Representation of ANSI Standard Limits and Fits
ANSI B4.1-1967 (R1999)



Diagrams show disposition of hole and shaft tolerances (in thousandths of an inch) with respect to basic size (0) for a diameter of 1 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8a. American National Standard Running and Sliding Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class RC 1			Class RC 2			Class RC 3			Class RC 4		
		Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits		
	Clearance[a]	Hole H5	Shaft g4	Clearance[a]	Hole H6	Shaft g5	Clearance[a]	Hole H7	Shaft f6	Clearance[a]	Hole H8	Shaft f7
Over To	Values shown below are in thousandths of an inch											
0 – 0.12	0.1	+0.2	−0.1	0.1	+0.25	−0.1	0.3	+0.4	−0.3	0.3	+0.6	−0.3
	0.45	0	−0.25	0.55	0	−0.3	0.95	0	−0.55	1.3	0	−0.7
0.12 – 0.24	0.15	+0.2	−0.15	0.15	+0.3	−0.15	0.4	+0.5	−0.4	0.4	+0.7	−0.4
	0.5	0	−0.3	0.65	0	−0.35	1.12	0	−0.7	1.6	0	−0.9
0.24 – 0.40	0.2	+0.25	−0.2	0.2	+0.4	−0.2	0.5	+0.6	−0.5	0.5	+0.9	−0.5
	0.6	0	−0.35	0.85	0	−0.45	1.5	0	−0.9	2.0	0	−1.1
0.40 – 0.71	0.25	+0.3	−0.25	0.25	+0.4	−0.25	0.6	+0.7	−0.6	0.6	+1.0	−0.6
	0.75	0	−0.45	0.95	0	−0.55	1.7	0	−1.0	2.3	0	−1.3
0.71 – 1.19	0.3	+0.4	−0.3	0.3	+0.5	−0.3	0.8	+0.8	−0.8	0.8	+1.2	−0.8
	0.95	0	−0.55	1.2	0	−0.7	2.1	0	−1.3	2.8	0	−1.6
1.19 – 1.97	0.4	+0.4	−0.4	0.4	+0.6	−0.4	1.0	+1.0	−1.0	1.0	+1.6	−1.0
	1.1	0	−0.7	1.4	0	−0.8	2.6	0	−1.6	3.6	0	−2.0
1.97 – 3.15	0.4	+0.5	−0.4	0.4	+0.7	−0.4	1.2	+1.2	−1.2	1.2	+1.8	−1.2
	1.2	0	−0.7	1.6	0	−0.9	3.1	0	−1.9	4.2	0	−2.4
3.15 – 4.73	0.5	+0.6	−0.5	0.5	+0.9	−0.5	1.4	+1.4	−1.4	1.4	+2.2	−1.4
	1.5	0	−0.9	2.0	0	−1.1	3.7	0	−2.3	5.0	0	−2.8
4.73 – 7.09	0.6	+0.7	−0.6	0.6	+1.0	−0.6	1.6	+1.6	−1.6	1.6	+2.5	−1.6
	1.8	0	−1.1	2.3	0	−1.3	4.2	0	−2.6	5.7	0	−3.2
7.09 – 9.85	0.6	+0.8	−0.6	0.6	+1.2	−0.6	2.0	+1.8	−2.0	2.0	+2.8	−2.0
	2.0	0	−1.2	2.6	0	−1.4	5.0	0	−3.2	6.6	0	−3.8
9.85 – 12.41	0.8	+0.9	−0.8	0.8	+1.2	−0.8	2.5	+2.0	−2.5	2.5	+3.0	−2.5
	2.3	0	−1.4	2.9	0	−1.7	5.7	0	−3.7	7.5	0	−4.5
12.41 – 15.75	1.0	+1.0	−1.0	1.0	+1.4	−1.0	3.0	+2.2	−3.0	3.0	+3.5	−3.0
	2.7	0	−1.7	3.4	0	−2.0	6.6	0	−4.4	8.7	0	−5.2
15.75 – 19.69	1.2	+1.0	−1.2	1.2	+1.6	−1.2	4.0	+2.5	−4.0	4.0	+4.0	−4.0
	3.0	0	−2.0	3.8	0	−2.2	8.1	0	−5.6	10.5	0	−6.5

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8b. American National Standard Running and Sliding Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class RC 5			Class RC 6			Class RC 7			Class RC 8			Class RC 9		
			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits	
Over	To	Clearance[a]	Hole H8	Shaft e7	Clearance[a]	Hole H9	Shaft e8	Clearance[a]	Hole H9	Shaft d8	Clearance[a]	Hole H10	Shaft c9	Clearance[a]	Hole H11	Shaft
		Values shown below are in thousandths of an inch														
0 –	0.12	0.6	+0.6	– 0.6	0.6	+1.0	– 0.6	1.0	+1.0	– 1.0	2.5	+1.6	– 2.5	4.0	+2.5	– 4.0
		1.6	0	– 1.0	2.2	0	– 1.2	2.6	0	– 1.6	5.1	0	– 3.5	8.1	0	– 5.6
0.12 –	0.24	0.8	+0.7	– 0.8	0.8	+1.2	– 0.8	1.2	+1.2	– 1.2	2.8	+1.8	– 2.8	4.5	+3.0	– 4.5
		2.0	0	– 1.3	2.7	0	– 1.5	3.1	0	– 1.9	5.8	0	– 4.0	9.0	0	– 6.0
0.24 –	0.40	1.0	+0.9	– 1.0	1.0	+1.4	– 1.0	1.6	+1.4	– 1.6	3.0	+2.2	– 3.0	5.0	+3.5	– 5.0
		2.5	0	– 1.6	3.3	0	– 1.9	3.9	0	– 2.5	6.6	0	– 4.4	10.7	0	– 7.2
0.40 –	0.71	1.2	+1.0	– 1.2	1.2	+1.6	– 1.2	2.0	+1.6	– 2.0	3.5	+2.8	– 3.5	6.0	+4.0	– 6.0
		2.9	0	– 1.9	3.8	0	– 2.2	4.6	0	– 3.0	7.9	0	– 5.1	12.8	0	– 8.8
0.71 –	1.19	1.6	+1.2	– 1.6	1.6	+2.0	– 1.6	2.5	+2.0	– 2.5	4.5	+3.5	– 4.5	7.0	+5.0	– 7.0
		3.6	0	– 2.4	4.8	0	– 2.8	5.7	0	– 3.7	10.0	0	– 6.5	15.5	0	–10.5
1.19 –	1.97	2.0	+1.6	– 2.0	2.0	+2.5	– 2.0	3.0	+2.5	– 3.0	5.0	+4.0	– 5.0	8.0	+6.0	– 8.0
		4.6	0	– 3.0	6.1	0	– 3.6	7.1	0	– 4.6	11.5	0	– 7.5	18.0	0	–12.0
1.97 –	3.15	2.5	+1.8	– 2.5	2.5	+3.0	– 2.5	4.0	+3.0	– 4.0	6.0	+4.5	– 6.0	9.0	+7.0	– 9.0
		5.5	0	– 3.7	7.3	0	– 4.3	8.8	0	– 5.8	13.5	0	– 9.0	20.5	0	–13.5
3.15 –	4.73	3.0	+2.2	– 3.0	3.0	+3.5	– 3.0	5.0	+3.5	– 5.0	7.0	+5.0	– 7.0	10.0	+9.0	–10.0
		6.6	0	– 4.4	8.7	0	– 5.2	10.7	0	– 7.2	15.5	0	–10.5	24.0	0	–15.0
4.73 –	7.09	3.5	+2.5	– 3.5	3.5	+4.0	– 3.5	6.0	+4.0	– 6.0	8.0	+6.0	– 8.0	12.0	+10.0	–12.0
		7.6	0	– 5.1	10.0	0	– 6.0	12.5	0	– 8.5	18.0	0	–12.0	28.0	0	–18.0
7.09 –	9.85	4.0	+2.8	– 4.0	4.0	+4.5	– 4.0	7.0	+4.5	– 7.0	10.0	+7.0	–10.0	15.0	+12.0	–15.0
		8.6	0	– 5.8	11.3	0	– 6.8	14.3	0	– 9.8	21.5	0	–14.5	34.0	0	–22.0
9.85 –	12.41	5.0	+3.0	– 5.0	5.0	+5.0	– 5.0	8.0	+5.0	– 8.0	12.0	+8.0	–12.0	18.0	+12.0	–18.0
		10.0	0	– 7.0	13.0	0	– 8.0	16.0	0	–11.0	25.0	0	–17.0	38.0	0	–26.0
12.41 –	15.75	6.0	+3.5	– 6.0	6.0	+6.0	– 6.0	10.0	+6.0	–10.0	14.0	+9.0	–14.0	22.0	+14.0	–22.0
		11.7	0	– 8.2	15.5	0	– 9.5	19.5	0	–13.5	29.0	0	–20.0	45.0	0	–31.0
15.75 –	19.69	8.0	+4.0	– 8.0	8.0	+6.0	– 8.0	12.0	+6.0	–12.0	16.0	+10.0	–16.0	25.0	+16.0	–25.0
		14.5	0	–10.5	18.0	0	–12.0	22.0	0	–16.0	32.0	0	–22.0	51.0	0	–35.0

[a] Pairs of values shown represent minimum and maximum amounts of clearance resulting from application of standard tolerance limits.

Tolerance limits given in body of table are added to or subtracted from basic size (as indicated by + or – sign) to obtain maximum and minimum sizes of mating parts.

All data above heavy lines are in accord with ABC agreements. Symbols H5, g4, etc. are hole and shaft designations in ABC system. Limits for sizes above 19.69 inches are also given in the ANSI Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9a. American National Standard Clearance Locational Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class LC 1			Class LC 2			Class LC 3			Class LC 4			Class LC 5		
		Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits		
Over	To	Clearance[a]	Hole H6	Shaft h5	Clearance[a]	Hole H7	Shaft h6	Clearance[a]	Hole H8	Shaft h7	Clearance[a]	Hole H10	Shaft h9	Clearance[a]	Hole H7	Shaft g6
		Values shown below are in thousandths of an inch														
0	0.12	0	+0.25	0	0	+0.4	0	0	+0.6	0	0	+1.6	0	0.1	+0.4	−0.1
		0.45	0	−0.2	0.65	0	−0.25	1	0	−0.4	2.6	0	−1.0	0.75	0	−0.35
0.12	0.24	0	+0.3	0	0	+0.5	0	0	+0.7	0	0	+1.8	0	0.15	+0.5	−0.15
		0.5	0	−0.2	0.8	0	−0.3	1.2	0	−0.5	3.0	0	−1.2	0.95	0	−0.45
0.24	0.40	0	+0.4	0	0	+0.6	0	0	+0.9	0	0	+2.2	0	0.2	+0.6	−0.2
		0.65	0	−0.25	1.0	0	−0.4	1.5	0	−0.6	3.6	0	−1.4	1.2	0	−0.6
0.40	0.71	0	+0.4	0	0	+0.7	0	0	+1.0	0	0	+2.8	0	0.25	+0.7	−0.25
		0.7	0	−0.3	1.1	0	−0.4	1.7	0	−0.7	4.4	0	−1.6	1.35	0	−0.65
0.71	1.19	0	+0.5	0	0	+0.8	0	0	+1.2	0	0	+3.5	0	0.3	+0.8	−0.3
		0.9	0	−0.4	1.3	0	−0.5	2	0	−0.8	5.5	0	−2.0	1.6	0	−0.8
1.19	1.97	0	+0.6	0	0	+1.0	0	0	+1.6	0	0	+4.0	0	0.4	+1.0	−0.4
		1.0	0	−0.4	1.6	0	−0.6	2.6	0	−1	6.5	0	−2.5	2.0	0	−1.0
1.97	3.15	0	+0.7	0	0	+1.2	0	0	+1.8	0	0	+4.5	0	0.4	+1.2	−0.4
		1.2	0	−0.5	1.9	0	−0.7	3	0	−1.2	7.5	0	−3	2.3	0	−1.1
3.15	4.73	0	+0.9	0	0	+1.4	0	0	+2.2	0	0	+5.0	0	0.5	+1.4	−0.5
		1.5	0	−0.6	2.3	0	−0.9	3.6	0	−1.4	8.5	0	−3.5	2.8	0	−1.4
4.73	7.09	0	+1.0	0	0	+1.6	0	0	+2.5	0	0	+6.0	0	0.6	+1.6	−0.6
		1.7	0	−0.7	2.6	0	−1.0	4.1	0	−1.6	10.0	0	−4	3.2	0	−1.6
7.09	9.85	0	+1.2	0	0	+1.8	0	0	+2.8	0	0	+7.0	0	0.6	+1.8	−0.6
		2.0	0	−0.8	3.0	0	−1.2	4.6	0	−1.8	11.5	0	−4.5	3.6	0	−1.8
9.85	12.41	0	+1.2	0	0	+2.0	0	0	+3.0	0	0	+8.0	0	0.7	+2.0	−0.7
		2.1	0	−0.9	3.2	0	−1.2	5	0	−2.0	13.0	0	−5	3.9	0	−1.9
12.41	15.75	0	+1.4	0	0	+2.2	0	0	+3.5	0	0	+9.0	0	0.7	+2.2	−0.7
		2.4	0	−1.0	3.6	0	−1.4	5.7	0	−2.2	15.0	0	−6	4.3	0	−2.1
15.75	19.69	0	+1.6	0	0	+2.5	0	0	+4	0	0	+10.0	0	0.8	+2.5	−0.8
		2.6	0	−1.0	4.1	0	−1.6	6.5	0	−2.5	16.0	0	−6	4.9	0	−2.4

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9b. American National Standard Clearance Locational Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class LC 6			Class LC 7			Class LC 8			Class LC 9			Class LC 10			Class LC 11		
			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits	
Over	To	Clearance[a]	Hole H9	Shaft f8	Clearance[a]	Hole H10	Shaft e9	Clearance[a]	Hole H10	Shaft d9	Clearance[a]	Hole H11	Shaft c10	Clearance[a]	Hole H12	Shaft	Clearance[a]	Hole H13	Shaft
		Values shown below are in thousandths of an inch																	
0 –	0.12	0.3	+1.0	–0.3	0.6	+1.6	– 0.6	1.0	+1.6	– 1.0	2.5	+2.5	– 2.5	4	+4	– 4	5	+6	– 5
		1.9	0	–0.9	3.2	0	– 1.6	2.0	0	– 2.0	6.6	0	– 4.1	12	0	– 8	17	0	– 11
0.12 –	0.24	0.4	+1.2	–0.4	0.8	+1.8	– 0.8	1.2	+1.8	– 1.2	2.8	+3.0	– 2.8	4.5	+5	– 4.5	6	+7	– 6
		2.3	0	–1.1	3.8	0	– 2.0	4.2	0	– 2.4	7.6	0	– 4.6	14.5	0	– 9.5	20	0	–13
0.24 –	0.40	0.5	+1.4	–0.5	1.0	+2.2	– 1.0	1.6	+2.2	– 1.6	3.0	+3.5	– 3.0	5	+6	– 5	7	+9	– 7
		2.8	0	–1.4	4.6	0	– 2.4	5.2	0	– 3.0	8.7	0	– 5.2	17	0	–11	25	0	–16
0.40 –	0.71	0.6	+1.6	–0.6	1.2	+2.8	– 1.2	2.0	+2.8	– 2.0	3.5	+4.0	– 3.5	6	+7	– 6	8	+10	– 8
		3.2	0	–1.6	5.6	0	– 2.8	6.4	0	– 3.6	10.3	0	– 6.3	20	0	–13	28	0	–18
0.71 –	1.19	0.8	+2.0	–0.8	1.6	+3.5	– 1.6	2.5	+3.5	– 2.5	4.5	+5.0	– 4.5	7	+8	– 7	10	+12	–10
		4.0	0	–2.0	7.1	0	– 3.6	8.0	0	– 4.5	13.0	0	– 8.0	23	0	–15	34	0	–22
1.19 –	1.97	1.0	+2.5	–1.0	2.0	+4.0	– 2.0	3.6	+4.0	– 3.0	5.0	+6	– 5.0	8	+10	– 8	12	+16	–12
		5.1	0	–2.6	8.5	0	– 4.5	9.5	0	– 5.5	15.0	0	– 9.0	28	0	–18	44	0	–28
1.97 –	3.15	1.2	+3.0	–1.0	2.5	+4.5	– 2.5	4.0	+4.5	– 4.0	6.0	+7	– 6.0	10	+12	–10	14	+18	–14
		6.0	0	–3.0	10.0	0	– 5.5	11.5	0	– 7.0	17.5	0	–10.5	34	0	–22	50	0	–32
3.15 –	4.73	1.4	+3.5	–1.4	3.0	+5.0	– 3.0	5.0	+5.0	– 5.0	7	+9	– 7	11	+14	–11	16	+22	–16
		7.1	0	–3.6	11.5	0	– 6.5	13.5	0	– 8.5	21	0	–12	39	0	–25	60	0	–38
4.73 –	7.09	1.6	+4.0	–1.6	3.5	+6.0	– 3.5	6	+6	– 6	8	+10	– 8	12	+16	–12	18	+25	–18
		8.1	0	–4.1	13.5	0	– 7.5	16	0	–10	24	0	–14	44	0	–28	68	0	–43
7.09 –	9.85	2.0	+4.5	–2.0	4.0	+7.0	– 4.0	7	+7	– 7	10	+12	–10	16	+18	–16	22	+28	–22
		9.3	0	–4.8	15.5	0	– 8.5	18.5	0	–11.5	29	0	–17	52	0	–34	78	0	–50
9.85 –	12.41	2.2	+5.0	–2.2	4.5	+8.0	– 4.5	7	+8	– 7	12	+12	–12	20	+20	–20	28	+30	–28
		10.2	0	–5.2	17.5	0	– 9.5	20	0	–12	32	0	–20	60	0	–40	88	0	–58
12.41 –	15.75	2.5	+6.0	–2.5	5.0	+9.0	– 5	8	+9	– 8	14	+14	–14	22	+22	–22	30	+35	–30
		12.0	0	–6.0	20.0	0	–11	23	0	–14	37	0	–23	66	0	–44	100	0	–65
15.75–	19.69	2.8	+6.0	–2.8	5.0	+10.0	– 5	9	+10	– 9	16	+16	–16	25	+25	–25	35	+40	–35
		12.8	0	–6.8	21.0	0	–11	25	0	–15	42	0	–26	75	0	–50	115	0	–75

[a] Pairs of values shown represent minimum and maximum amounts of interference resulting from application of standard tolerance limits.

Tolerance limits given in body of table are added or subtracted to basic size (as indicated by + or – sign) to obtain maximum and minimum sizes of mating parts. All data above heavy lines are in accordance with American-British-Canadian (ABC) agreements. Symbols H6, H7, s6, etc. are hole and shaft designations in ABC system. Limits for sizes above 19.69 inches are not covered by ABC agreements but are given in the ANSI Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ANSI Standard Transition Locational Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class LT 1			Class LT 2			Class LT 3			Class LT 4			Class LT 5			Class LT 6		
			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits			Std. Tolerance Limits	
Over	To	Fit[a]	Hole H7	Shaft js6	Fit[a]	Hole H8	Shaft js7	Fit[a]	Hole H7	Shaft k6	Fit[a]	Hole H8	Shaft k7	Fit[a]	Hole H7	Shaft n6	Fit[a]	Hole H7	Shaft n7
		Values shown below are in thousandths of an inch																	
0 –	0.12	–0.12 +0.52	+0.4 0	+0.12 –0.12	–0.2 +0.8	+0.6 0	+0.2 –0.2							–0.5 +0.15	+0.4 0	+0.5 +0.25	–0.65 +0.15	+0.4 0	+0.65 +0.25
0.12 –	0.24	–0.15 +0.65	+0.5 0	+0.15 –0.15	–0.25 +0.95	+0.7 0	+0.25 –0.25							–0.6 +0.2	+0.5 0	+0.6 +0.3	–0.8 +0.2	+0.5 0	+0.8 +0.3
0.24 –	0.40	–0.2 +0.8	+0.6 0	+0.2 –0.2	–0.3 +1.2	+0.9 0	+0.3 –0.3	–0.5 +0.5	+0.6 0	+0.5 +0.1	–0.7 +0.8	+0.9 0	+0.7 +0.1	–0.8 +0.2	+0.6 0	+0.8 +0.4	–1.0 +0.2	+0.6 0	+1.0 +0.4
0.40 –	0.71	–0.2 +0.9	+0.7 0	+0.2 –0.2	–0.35 +1.35	+1.0 0	+0.35 –0.35	–0.5 +0.6	+0.7 0	+0.5 +0.1	–0.8 +0.9	+1.0 0	+0.8 +0.1	–0.9 +0.2	+0.7 0	+0.9 +0.5	–1.2 +0.2	+0.7 0	+1.2 +0.5
0.71 –	1.19	–0.25 +1.05	+0.8 0	+0.25 –0.25	–0.4 +1.6	+1.2 0	+0.4 –0.4	–0.6 +0.7	+0.8 0	+0.6 +0.1	–0.9 +1.1	+1.2 0	+0.9 +0.1	–1.1 +0.2	+0.8 0	+1.1 +0.6	–1.4 +0.2	+0.8 0	+1.4 +0.6
1.19 –	1.97	–0.3 +1.3	+1.0 0	+0.3 –0.3	–0.5 +2.1	+1.6 0	+0.5 –0.5	–0.7 +0.9	+1.0 0	+0.7 +0.1	–1.1 +1.5	+1.6 0	+1.1 +0.1	–1.3 +0.3	+1.0 0	+1.3 +0.7	–1.7 +0.3	+1.0 0	+1.7 +0.7
1.97 –	3.15	–0.3 +1.5	+1.2 0	+0.3 –0.3	–0.6 +2.4	+1.8 0	+0.6 –0.6	–0.8 +1.1	+1.2 0	+0.8 +0.1	–1.3 +1.7	+1.8 0	+1.3 +0.1	–1.5 +0.4	+1.2 0	+1.5 +0.8	–2.0 +0.4	+1.2 0	+2.0 +0.8
3.15 –	4.73	–0.4 +1.8	+1.4 0	+0.4 –0.4	–0.7 +2.9	+2.2 0	+0.7 –0.7	–1.0 +1.3	+1.4 0	+1.0 +0.1	–1.5 +2.1	+2.2 0	+1.5 +0.1	–1.9 +0.4	+1.4 0	+1.9 +1.0	–2.4 +0.4	+1.4 0	+2.4 +1.0
4.73 –	7.09	–0.5 +2.1	+1.6 0	+0.5 –0.5	–0.8 +3.3	+2.5 0	+0.8 –0.8	–1.1 +1.5	+1.6 0	+1.1 +0.1	–1.7 +2.4	+2.5 0	+1.7 +0.1	–2.2 +0.4	+1.6 0	+2.2 +1.2	–2.8 +0.4	+1.6 0	+2.8 +1.2
7.09 –	9.85	–0.6 +2.4	+1.8 0	+0.6 –0.6	–0.9 +3.7	+2.8 0	+0.9 –0.9	–1.4 +1.6	+1.8 0	+1.4 +0.2	–2.0 +2.6	+2.8 0	+2.0 +0.2	–2.6 +0.4	+1.8 0	+2.6 +1.4	–3.2 +0.4	+1.8 0	+3.2 +1.4
9.85 –	12.41	–0.6 +2.6	+2.0 0	+0.6 –0.6	–1.0 +4.0	+3.0 0	+1.0 –1.0	–1.4 +1.8	+2.0 0	+1.4 +0.2	–2.2 +2.8	+3.0 0	+2.2 +0.2	–2.6 +0.6	+2.0 0	+2.6 +1.4	–3.4 +0.6	+2.0 0	+3.4 +1.4
12.41 –	15.75	–0.7 +2.9	+2.2 0	+0.7 –0.7	–1.0 +4.5	+3.5 0	+1.0 –1.0	–1.6 +2.0	+2.2 0	+1.6 +0.2	–2.4 +3.3	+3.5 0	+2.4 +0.2	–3.0 +0.6	+2.2 0	+3.0 +1.6	–3.8 +0.6	+2.2 0	+3.8 +1.6
15.75 –	19.69	–0.8 +3.3	+2.5 0	+0.8 –0.8	–1.2 +5.2	+4.0 0	+1.2 –1.2	–1.8 +2.3	+2.5 0	+1.8 +0.2	–2.7 +3.8	+4.0 0	+2.7 +0.2	–3.4 +0.7	+2.5 0	+3.4 +1.8	–4.3 +0.7	+2.5 0	+4.3 +1.8

[a] Pairs of values shown represent maximum amount of interference (–) and maximum amount of clearance (+) resulting from application of standard tolerance limits. All data above heavy lines are in accord with ABC agreements. Symbols H7, js6, etc., are hole and shaft designations in the ABC system.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ANSI Standard Force and Shrink Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class FN 1			Class FN 2			Class FN 3			Class FN 4			Class FN 5		
		Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits			Standard Tolerance Limits		
		Interference[a]	Hole H6	Shaft	Interference[a]	Hole H7	Shaft s6	Interference[a]	Hole H7	Shaft t6	Interference[a]	Hole H7	Shaft u6	Interference[a]	Hole H8	Shaft x7
Over	To	Values shown below are in thousandths of an inch														
0	0.12	0.05	+0.25	+0.5	0.2	+0.4	+0.85				0.3	+0.4	+0.95	0.3	+0.6	+1.3
		0.5	0	+0.3	0.85	0	+0.6				0.95	0	+0.7	1.3	0	+0.9
0.12	0.24	0.1	+0.3	+0.6	0.2	+0.5	+1.0				0.4	+0.5	+1.2	0.5	+0.7	+1.7
		0.6	0	+0.4	1.0	0	+0.7				1.2	0	+0.9	1.7	0	+1.2
0.24	0.40	0.1	+0.4	+0.75	0.4	+0.6	+1.4				0.6	+0.6	+1.6	0.5	+0.9	+2.0
		0.75	0	+0.5	1.4	0	+1.0				1.6	0	+1.2	2.0	0	+1.4
0.40	0.56	0.1	+0.4	+0.8	0.5	+0.7	+1.6				0.7	+0.7	+1.8	0.6	+1.0	+2.3
		0.8	0	+0.5	1.6	0	+1.2				1.8	0	+1.4	2.3	0	+1.6
0.56	0.71	0.2	+0.4	+0.9	0.5	+0.7	+1.6				0.7	+0.7	+1.8	0.8	+1.0	+2.5
		0.9	0	+0.6	1.6	0	+1.2				1.8	0	+1.4	2.5	0	+1.8
0.71	0.95	0.2	+0.5	+1.1	0.6	+0.8	+1.9				0.8	+0.8	+2.1	1.0	+1.2	+3.0
		1.1	0	+0.7	1.9	0	+1.4				2.1	0	+1.6	3.0	0	+2.2
0.95	1.19	0.3	+0.5	+1.2	0.6	+0.8	+1.9	0.8	+0.8	+2.1	+1.0	+0.8	+2.3	1.3	+1.2	+3.3
		1.2	0	+0.8	1.9	0	+1.4	2.1	0	+1.6	2.3	0	+1.8	3.3	0	+2.5
1.19	1.58	0.3	+0.6	+1.3	0.8	+1.0	+2.4	1.0	+1.0	+2.6	1.5	+1.0	+3.1	1.4	+1.6	+4.0
		1.3	0	+0.9	2.4	0	+1.8	2.6	0	+2.0	3.1	0	+2.5	4.0	0	+3.0
1.58	1.97	0.4	+0.6	+1.4	0.8	+1.0	+2.4	1.2	+1.0	+2.8	1.8	+1.0	+3.4	2.4	+1.6	+5.0
		1.4	0	+1.0	2.4	0	+1.8	2.8	0	+2.2	3.4	0	+2.8	5.0	0	+4.0
1.97	2.56	0.6	+0.7	+1.8	0.8	+1.2	+2.7	1.3	+1.2	+3.2	2.3	+1.2	+4.2	3.2	+1.8	+6.2
		1.8	0	+1.3	2.7	0	+2.0	3.2	0	+2.5	4.2	0	+3.5	6.2	0	+5.0
2.56	3.15	0.7	+0.7	+1.9	1.0	+1.2	+2.9	1.8	+1.2	+3.7	2.8	+1.2	+4.7	4.2	+1.8	+7.2
		1.9	0	+1.4	2.9	0	+2.2	3.7	0	+3.0	4.7	0	+4.0	7.2	0	+6.0
3.15	3.94	0.9	+0.9	+2.4	1.4	+1.4	+3.7	2.1	+1.4	+4.4	3.6	+1.4	+5.9	4.8	+2.2	+8.4
		2.4	0	+1.8	3.7	0	+2.8	4.4	0	+3.5	5.9	0	+5.0	8.4	0	+7.0
3.94	4.73	1.1	+0.9	+2.6	1.6	+1.4	+3.9	2.6	+1.4	+4.9	4.6	+1.4	+6.9	5.8	+2.2	+9.4
		2.6	0	+2.0	3.9	0	+3.0	4.9	0	+4.0	6.9	0	+6.0	9.4	0	+8.0

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ***(Continued)*** **ANSI Standard Force and Shrink Fits** *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class FN 1			Class FN 2			Class FN 3			Class FN 4			Class FN 5		
		Interference[a]	Standard Tolerance Limits		Interference[a]	Standard Tolerance Limits		Interference[a]	Standard Tolerance Limits		Interference[a]	Standard Tolerance Limits		Interference[a]	Standard Tolerance Limits	
			Hole H6	Shaft		Hole H7	Shaft s6		Hole H7	Shaft t6		Hole H7	Shaft u6		Hole H8	Shaft x7
Over	To	Values shown below are in thousandths of an inch														
4.73–	5.52	1.2	+1.0	+2.9	1.9	+1.6	+4.5	3.4	+1.6	+6.0	5.4	+1.6	+8.0	7.5	+2.5	+11.6
		2.9	0	+2.2	4.5	0	+3.5	6.0	0	+5.0	8.0	0	+7.0	11.6	0	+10.0
5.52–	6.30	1.5	+1.0	+3.2	2.4	+1.6	+5.0	3.4	+1.6	+6.0	5.4	+1.6	+8.0	9.5	+2.5	+13.6
		3.2	0	+2.5	5.0	0	+4.0	6.0	0	+5.0	8.0	0	+7.0	13.6	0	+12.0
6.30–	7.09	1.8	+1.0	+3.5	2.9	+1.6	+5.5	4.4	+1.6	+7.0	6.4	+1.6	+9.0	9.5	+2.5	+13.6
		3.5	0	+2.8	5.5	0	+4.5	7.0	0	+6.0	9.0	0	+8.0	13.6	0	+12.0
7.09–	7.88	1.8	+1.2	+3.8	3.2	+1.8	+6.2	5.2	+1.8	+8.2	7.2	+1.8	+10.2	11.2	+2.8	+15.8
		3.8	0	+3.0	6.2	0	+5.0	8.2	0	+7.0	10.2	0	+9.0	15.8	0	+14.0
7.88–	8.86	2.3	+1.2	+4.3	3.2	+1.8	+6.2	5.2	+1.8	+8.2	8.2	+1.8	+11.2	13.2	+2.8	+17.8
		4.3	0	+3.5	6.2	0	+5.0	8.2	0	+7.0	11.2	0	+10.0	17.8	0	+16.0
8.86–	9.85	2.3	+1.2	+4.3	4.2	+1.8	+7.2	6.2	+1.8	+9.2	10.2	+1.8	+13.2	13.2	+2.8	+17.8
		4.3	0	+3.5	7.2	0	+6.0	9.2	0	+8.0	13.2	0	+12.0	17.8	0	+16.0
9.85–	11.03	2.8	+1.2	+4.9	4.0	+2.0	+7.2	7.0	+2.0	+10.2	10.0	+2.0	+13.2	15.0	+3.0	+20.0
		4.9	0	+4.0	7.2	0	+6.0	10.2	0	+9.0	13.2	0	+12.0	20.0	0	+18.0
11.03–	12.41	2.8	+1.2	+4.9	5.0	+2.0	+8.2	7.0	+2.0	+10.2	12.0	+2.0	+15.2	17.0	+3.0	+22.0
		4.9	0	+4.0	8.2	0	+7.0	10.2	0	+9.0	15.2	0	+14.0	22.0	0	+20.0
12.41–	13.98	3.1	+1.4	+5.5	5.8	+2.2	+9.4	7.8	+2.2	+11.4	13.8	+2.2	+17.4	18.5	+3.5	+24.2
		5.5	0	+4.5	9.4	0	+8.0	11.4	0	+10.0	17.4	0	+16.0	24.2	0	+22.0
13.98–	15.75	3.6	+1.4	+6.1	5.8	+2.2	+9.4	9.8	+2.2	+13.4	15.8	+2.2	+19.4	21.5	+3.5	+27.2
		6.1	0	+5.0	9.4	0	+8.0	13.4	0	+12.0	19.4	0	+18.0	27.2	0	+25.0
15.75–	17.72	4.4	+1.6	+7.0	6.5	+2.5	+10.6	+9.5	+2.5	+13.6	17.5	+2.5	+21.6	24.0	+4.0	+30.5
		7.0	0	+6.0	10.6	0	+9.0	13.6	0	+12.0	21.6	0	+20.0	30.5	0	+28.0
17.72–	19.69	4.4	+1.6	+7.0	7.5	+2.5	+11.6	11.5	+2.5	+15.6	19.5	+2.5	+23.6	26.0	+4.0	+32.5
		7.0	0	+6.0	11.6	0	+10.0	15.6	0	+14.0	23.6	0	+22.0	32.5	0	+30.0

[a] Pairs of values shown represent minimum and maximum amounts of interference resulting from application of standard tolerance limits.

All data above heavy lines are in accordance with American-British-Canadian (ABC) agreements. Symbols H6, H7, s6, etc., are hole and shaft designations in the ABC system. Limits for sizes above 19.69 inches are not covered by ABC agreements but are given in the ANSI standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ANSI Standard Interference Location Fits *ANSI B4.1-1967 (R1999)*

Nominal Size Range, Inches		Class LN 1			Class LN 2			Class LN 3		
		Limits of Interference	Standard Limits		Limits of Interference	Standard Limits		Limits of Interference	Standard Limits	
			Hole H6	Shaft n5		Hole H7	Shaft p6		Hole H7	Shaft r6
Over	To	Values shown below are given in thousandths of an inch								
0–	0.12	0	+0.25	+0.45	0	+0.4	+0.65	0.1	+0.4	+0.75
		0.45	0	+0.25	0.65	0	+0.4	0.75	0	+0.5
0.12–	0.24	0	+0.3	+0.5	0	+0.5	+0.8	0.1	+0.5	+0.9
		0.5	0	+0.3	0.8	0	+0.5	0.9	0	+0.6
0.24–	0.40	0	+0.4	+0.65	0	+0.6	+1.0	0.2	+0.6	+1.2
		0.65	0	+0.4	1.0	0	+0.6	1.2	0	+0.8
0.40–	0.71	0	+0.4	+0.8	0	+0.7	+1.1	0.3	+0.7	+1.4
		0.8	0	+0.4	1.1	0	+0.7	1.4	0	+1.0
0.71–	1.19	0	+0.5	+1.0	0	+0.8	+1.3	0.4	+0.8	+1.7
		1.0	0	+0.5	1.3	0	+0.8	1.7	0	+1.2
1.19–	1.97	0	+0.6	+1.1	0	+1.0	+1.6	0.4	+1.0	+2.0
		1.1	0	+0.6	1.6	0	+1.0	2.0	0	+1.4
1.97–	3.15	0.1	+0.7	+1.3	0.2	+1.2	+2.1	0.4	+1.2	+2.3
		1.3	0	+0.8	2.1	0	+1.4	2.3	0	+1.6
3.15–	4.73	0.1	+0.9	+1.6	0.2	+1.4	+2.5	0.6	+1.4	+2.9
		1.6	0	+1.0	2.5	0	+1.6	2.9	0	+2.0
4.73–	7.09	0.2	+1.0	+1.9	0.2	+1.6	+2.8	0.9	+1.6	+3.5
		1.9	0	+1.2	2.8	0	+1.8	3.5	0	+2.5
7.09–	9.85	0.2	+1.2	+2.2	0.2	+1.8	+3.2	1.2	+1.8	+4.2
		2.2	0	+1.4	3.2	0	+2.0	4.2	0	+3.0
9.85–	12.41	0.2	+1.2	+2.3	0.2	+2.0	+3.4	1.5	+2.0	+4.7
		2.3	0	+1.4	3.4	0	+2.2	4.7	0	+3.5
12.41–	15.75	0.2	+1.4	+2.6	0.3	+2.2	+3.9	2.3	+2.2	+5.9
		2.6	0	+1.6	3.9	0	+2.5	5.9	0	+4.5
15.75–	19.69	0.2	+1.6	+2.8	0.3	+2.5	+4.4	2.5	+2.5	+6.6
		2.8	0	+1.8	4.4	0	+2.8	6.6	0	+5.0

All data in this table are in accordance with American-British-Canadian (ABC) agreements.

Limits for sizes above 19.69 inches are not covered by ABC agreements but are given in the ANSI Standard.

Symbols H7, p6, etc., are hole and shaft designations in the ABC system.

Tolerance limits given in body of table are added or subtracted to basic size (as indicated by + or – sign) to obtain maximum and minimum sizes of mating parts.

American National Standard Preferred Metric Limits and Fits

This standard ANSI B4.2-1978 (R1999) describes the ISO system of metric limits and fits for mating parts as approved for general engineering usage in the United States.

It establishes: 1) the designation symbols used to define dimensional limits on drawings, material stock, related tools, gages, etc.; 2) the preferred basic sizes (first and second choices); 3) the preferred tolerance zones (first, second, and third choices); 4) the preferred limits and fits for sizes (first choice only) up to and including 500 millimeters; and 5) the definitions of related terms.

The general terms "hole" and "shaft" can also be taken to refer to the space containing or contained by two parallel faces of any part, such as the width of a slot, or the thickness of a key.

Definitions.— The most important terms relating to limits and fits are shown in Fig. 1 and are defined as follows:

Basic Size: The size to which limits of deviation are assigned. The basic size is the same for both members of a fit. For example, it is designated by the numbers 40 in 40H7.

Deviation: The algebraic difference between a size and the corresponding basic size.

Copyright 2004, Industrial Press, Inc., New York, NY

Upper Deviation: The algebraic difference between the maximum limit of size and the corresponding basic size.

Lower Deviation: The algebraic difference between the minimum limit of size and the corresponding basic size.

Fundamental Deviation: That one of the two deviations closest to the basic size. For example, it is designated by the letter H in 40H7.

Tolerance: The difference between the maximum and minimum size limits on a part.

Tolerance Zone: A zone representing the tolerance and its position in relation to the basic size.



Fig. 1. Illustration of Definitions

International Tolerance Grade: (*IT*): A group of tolerances that vary depending on the basic size, but that provide the same relative level of accuracy within a given grade. For example, it is designated by the number 7 in 40H7 or as IT7.

Hole Basis: The system of fits where the minimum hole size is basic. The fundamental deviation for a hole basis system is H.

Shaft Basis: The system of fits where the maximum shaft size is basic. The fundamental deviation for a shaft basis system is h.

Clearance Fit: The relationship between assembled parts when clearance occurs under all tolerance conditions.

Interference Fit: The relationship between assembled parts when interference occurs under all tolerance conditions.

Transition Fit: The relationship between assembled parts when either a clearance or an interference fit can result, depending on the tolerance conditions of the mating parts.

Tolerances Designation.— An "International Tolerance grade" establishes the magnitude of the tolerance zone or the amount of part size variation allowed for external and internal dimensions alike (see Fig. 1). Tolerances are expressed in grade numbers that are consistent with International Tolerance grades identified by the prefix IT, such as IT6, IT11, etc. A smaller grade number provides a smaller tolerance zone.

Copyright 2004, Industrial Press, Inc., New York, NY

A fundamental deviation establishes the position of the tolerance zone with respect to the basic size (see Fig. 1). Fundamental deviations are expressed by tolerance position letters. Capital letters are used for internal dimensions and lowercase or small letters for external dimensions.

Symbols.— By combining the IT grade number and the tolerance position letter, the tolerance symbol is established that identifies the actual maximum and minimum limits of the part. The toleranced size is thus defined by the basic size of the part followed by a symbol composed of a letter and a number, such as 40H7, 40f7, etc.

A fit is indicated by the basic size common to both components, followed by a symbol corresponding to each component, the internal part symbol preceding the external part symbol, such as 40H8/f7.

Some methods of designating tolerances on drawings are:

40H8 $\qquad$ 40H8 $\binom{40.039}{40.000}$ $\qquad$ $\binom{40.039}{40.000}$ 40H8

The values in parentheses indicate reference only.

Preferred Metric Fits.— First-choice tolerance zones are used to establish preferred fits in ANSI B4.2, *Preferred Metric Limits and Fits*, as shown in Figs. 2 and 3. A complete listing of first-, second-, and third- choice tolerance zones is given in the Standard.

Hole basis fits have a fundamental deviation of H on the hole, and shaft basis fits have a fundamental deviation of *h* on the shaft and are shown in Fig. 2 for hole basis and Fig. 3 for shaft basis fits. A description of both types of fits, that have the same relative fit condition, is given in Table 1. Normally, the hole basis system is preferred; however, when a common shaft mates with several holes, the shaft basis system should be used.

The hole basis and shaft basis fits shown in the table *Description of Preferred Fits* on page 669 are combined with the first-choice preferred metric sizes from Table 1 on page 690, to form Tables 2, 3, 4, and 5, in which specific limits as well as the resultant fits are tabulated.

If the required size is not found tabulated in Tables 2 through 5 then the preferred fit can be calculated from numerical values given in an appendix of ANSI B4.2-1978 (R1999). It is anticipated that other fit conditions may be necessary to meet special requirements, and a preferred fit can be loosened or tightened simply by selecting a standard tolerance zone as given in the Standard. Information on how to calculate limit dimensions, clearances, and interferences, for nonpreferred fits and sizes can be found in an appendix of this Standard.

Conversion of Fits: It may sometimes be neccessary or desirable to modify the tolerance zone on one or both of two mating parts, yet still keep the total tolerance and fit condition the same. Examples of this appear in Table 1 on page 669 when converting from a hole basis fit to a shaft basis fit. The corresponding fits are identical yet the individual tolerance zones are different.

To convert from one type of fit to another, reverse the fundamental devations between the shaft and hole keeping the IT grade the same on each individual part. The examples below represent preferred fits from Table 1 for a 60-mm basic size. These fits have the same maximum clearance (0.520) and the same minimum clearance (0.140).

Hole basis, loose running fit, values from Table 2

Hole 60H11 $\binom{60.190}{60.000}$ $\qquad$ Shaft 60c11 $\binom{59.860}{59.670}$ $\qquad$ Fit 60H11/c11 $\binom{0.520}{0.140}$

Hole basis, loose running fit, values from Table 4

Hole 60C11 $\binom{60.330}{60.140}$ $\qquad$ Shaft 60h11 $\binom{60.000}{59.810}$ $\qquad$ Fit 60C11/h11 $\binom{0.520}{0.140}$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Preferred Hole Basis Fits



Fig. 3. Preferred Shaft Basis Fits

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Description of Preferred Fits

	ISO SYMBOL		DESCRIPTION	
	Hole Basis	**Shaft Basis**		
Clearance Fits	H11/c11	C11/h11	*Loose running* fit for wide commercial tolerances or allowances on external members.	↑ More Clearance
	H9/d9	D9/h9	*Free running* fit not for use where accuracy is essential, but good for large temperature variations, high running speeds, or heavy journal pressures.	
	H8/f7	F8/h7	*Close Running* fit for running on accurate machines and for accurate moderate speeds and journal pressures.	
	H7/g6	G7/h6	*Sliding fit* not intended to run freely, but to move and turn freely and locate accurately.	
	H7/h6	H7/h6	*Locational clearance* fit provides snug fit for locating stationary parts; but can be freely assembled and disassembled.	
Transition Fits	H7/k6	K7/h6	*Locational transition* fit for accurate location, a compromise between clearance and interferance.	
	H7/n6	N7/h6	*Locational transition* fit for more accurate location where greater interferance is permissible.	
Interference Fits	H7/p6[a]	P7/h6	*Locational interference* fit for parts requiring rigidity and alignment with prime accuracy of location but without special bore pressure requirements.	More Interference ↓
	H7/s6	S7/h6	*Medium drive* fit for ordinary steel parts or shrink fits on light sections, the tightest fit usable with cast iron.	
	H7/u6	U7/h6	*Force* fit suitable for parts which can be highly stressed or for shrink fits where the heavy pressing forces required are impractical.	

[a] Transition fit for basic sizes in range from 0 through 3 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Preferred Hole Basis Metric Clearance Fits *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Loose Running			Free Running			Close Running			Sliding			Locational Clearance		
		Hole H11	Shaft C11	Fit[b]	Hole H9	Shaft d9	Fit[b]	Hole H8	Shaft f7	Fit[b]	Hole H7	Shaft g6	Fit[b]	Hole H7	Shaft h6	Fit[b]
1	Max	1.060	0.940	0.180	1.025	0.980	0.070	1.014	0.994	0.030	1.010	0.998	0.018	1.010	1.000	0.016
	Min	1.000	0.880	0.060	1.000	0.995	0.020	1.000	0.984	0.006	1.000	0.992	0.002	1.000	0.994	0.000
1.2	Max	1.260	1.140	0.180	1.225	1.180	0.070	1.214	1.194	0.030	1.210	1.198	0.018	1.210	1.200	0.016
	Min	1.200	1.080	0.060	1.200	1.155	0.020	1.200	1.184	0.006	1.200	1.192	0.002	1.200	1.194	0.000
1.6	Max	1.660	1.540	0.180	1.625	1.580	0.070	1.614	1.594	0.030	1.610	1.598	0.018	1.610	1.600	0.016
	Min	1.600	1.480	0.060	1.600	1.555	0.020	1.600	1.584	0.006	1.600	1.592	0.002	1.600	1.594	0.000
2	Max	2.060	1.940	0.180	2.025	1.980	0.070	2.014	1.994	0.030	2.010	1.998	0.018	2.010	2.000	0.016
	Min	2.000	1.880	0.060	2.000	1.955	0.020	2.000	1.984	0.006	2.000	1.992	0.002	2.000	1.994	0.000
2.5	Max	2.560	2.440	0.180	2.525	2.480	0.070	2.514	2.494	0.030	2.510	2.498	0.018	2.510	2.500	0.016
	Min	2.500	2.380	0.060	2.500	2.455	0.020	2.500	2.484	0.006	2.500	2.492	0.002	2.500	2.494	0.000
3	Max	3.060	2.940	0.180	3.025	2.980	0.070	3.014	2.994	0.030	3.010	2.998	0.018	3.010	3.000	0.016
	Min	3.000	2.880	0.060	3.000	2.955	0.020	3.000	2.984	0.006	3.000	2.992	0.002	3.000	2.994	0.000
4	Max	4.075	3.930	0.220	4.030	3.970	0.090	4.018	3.990	0.040	4.012	3.996	0.024	4.012	4.000	0.020
	Min	4.000	3.855	0.070	4.000	3.940	0.030	4.000	3.978	0.010	4.000	3.988	0.004	4.000	3.992	0.000
5	Max	5.075	4.930	0.220	5.030	4.970	0.090	5.018	4.990	0.040	5.012	4.996	0.024	5.012	5.000	0.020
	Min	5.000	4.855	0.070	5.000	4.940	0.030	5.000	4.978	0.010	5.000	4.988	0.004	5.000	4.992	0.000
6	Max	6.075	5.930	0.220	6.030	5.970	0.090	6.018	5.990	0.040	6.012	5.996	0.024	6.012	6.000	0.020
	Min	6.000	5.855	0.070	6.000	5.940	0.030	6.000	5.978	0.010	6.000	5.988	0.004	6.000	5.992	0.000
8	Max	8.090	7.920	0.260	8.036	7.960	0.112	8.022	7.987	0.050	8.015	7.995	0.029	8.015	8.000	0.024
	Min	8.000	7.830	0.080	8.000	7.924	0.040	8.000	7.972	0.013	8.000	7.986	0.005	8.000	7.991	0.000
10	Max	10.090	9.920	0.260	10.036	9.960	0.112	10.022	9.987	0.050	10.015	9.995	0.029	10.015	10.000	0.024
	Min	10.000	9.830	0.080	10.000	9.924	0.040	10.000	9.972	0.013	10.000	9.986	0.005	10.000	9.991	0.000
12	Max	12.110	11.905	0.315	12.043	11.956	0.136	12.027	11.984	0.061	12.018	11.994	0.035	12.018	12.000	0.029
	Min	12.000	11.795	0.095	12.000	11.907	0.050	12.000	11.966	0.016	12.000	11.983	0.006	12.000	11.989	0.000
16	Max	16.110	15.905	0.315	16.043	15.950	0.136	16.027	15.984	0.061	16.018	15.994	0.035	16.018	16.000	0.029
	Min	16.000	15.795	0.095	16.000	15.907	0.050	16.000	15.966	0.016	16.000	15.983	0.006	16.000	15.989	0.000
20	Max	20.130	19.890	0.370	20.052	19.935	0.169	20.033	19.980	0.074	20.021	19.993	0.041	20.021	20.000	0.034
	Min	20.000	19.760	0.110	20.000	19.883	0.065	20.000	19.959	0.020	20.000	19.980	0.007	20.000	19.987	0.000
25	Max	25.130	24.890	0.370	25.052	24.935	0.169	25.033	24.980	0.074	25.021	24.993	0.041	25.021	25.000	0.034
	Min	25.000	24.760	0.110	25.000	24.883	0.065	25.000	24.959	0.020	25.000	24.980	0.007	25.000	24.987	0.000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **American National Standard Preferred Hole Basis Metric Clearance Fits** *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Loose Running			Free Running			Close Running			Sliding			Locational Clearance		
		Hole H11	Shaft C11	Fit[b]	Hole H9	Shaft d9	Fit[b]	Hole H8	Shaft f7	Fit[b]	Hole H7	Shaft g6	Fit[b]	Hole H7	Shaft h6	Fit[b]
30	Max	30.130	29.890	0.370	30.052	29.935	0.169	30.033	29.980	0.074	30.021	29.993	0.041	30.021	30.000	0.034
	Min	30.000	29.760	0.110	30.000	29.883	0.065	30.000	29.959	0.020	30.000	29.980	0.007	30.000	29.987	0.000
40	Max	40.160	39.880	0.440	40.062	39.920	0.204	40.039	39.975	0.089	40.025	39.991	0.050	40.025	40.000	0.041
	Min	40.000	39.720	0.120	40.000	39.858	0.080	40.000	39.950	0.025	40.000	39.975	0.009	40.000	39.984	0.000
50	Max	50.160	49.870	0.450	50.062	49.920	0.204	50.039	49.975	0.089	50.025	49.991	0.050	50.025	50.000	0.041
	Min	50.000	49.710	0.130	50.000	49.858	0.080	50.000	49.950	0.025	50.000	49.975	0.009	50.000	49.984	0.000
60	Max	60.190	59.860	0.520	60.074	59.900	0.248	60.046	59.970	0.106	60.030	59.990	0.059	60.030	60.000	0.049
	Min	60.000	59.670	0.140	60.000	59.826	0.100	60.000	59.940	0.030	60.000	59.971	0.010	60.000	59.981	0.000
80	Max	80.190	79.850	0.530	80.074	79.900	0.248	80.046	79.970	0.106	80.030	79.990	0.059	80.030	80.000	0.049
	Min	80.000	79.660	0.150	80.000	79.826	0.100	80.000	79.940	0.030	80.000	79.971	0.010	80.000	79.981	0.000
100	Max	100.220	99.830	0.610	100.087	99.880	0.294	100.054	99.964	0.125	100.035	99.988	0.069	100.035	100.000	0.057
	Min	100.000	99.610	0.170	100.000	99.793	0.120	100.000	99.929	0.036	100.000	99.966	0.012	100.000	99.978	0.000
120	Max	120.220	119.820	0.620	120.087	119.880	0.294	120.054	119.964	0.125	120.035	119.988	0.069	120.035	120.000	0.057
	Min	120.000	119.600	0.180	120.000	119.793	0.120	120.000	119.929	0.036	120.000	119.966	0.012	120.000	119.978	0.000
160	Max	160.250	159.790	0.710	160.100	159.855	0.345	160.063	159.957	0.146	160.040	159.986	0.079	160.040	160.000	0.065
	Min	160.000	159.540	0.210	160.000	159.755	0.145	160.000	159.917	0.043	160.000	159.961	0.014	160.000	159.975	0.000
200	Max	200.290	199.760	0.820	200.115	199.830	0.400	200.072	199.950	0.168	200.046	199.985	0.090	200.046	200.000	0.075
	Min	200.000	199.470	0.240	200.000	199.715	0.170	200.000	199.904	0.050	200.000	199.956	0.015	200.000	199.971	0.000
250	Max	250.290	249.720	0.860	250.115	249.830	0.400	250.072	249.950	0.168	250.046	249.985	0.090	250.046	250.000	0.075
	Min	250.000	249.430	0.280	250.000	249.715	0.170	250.000	249.904	0.050	250.000	249.956	0.015	250.000	249.971	0.000
300	Max	300.320	299.670	0.970	300.130	299.810	0.450	300.081	299.944	0.189	300.052	299.983	0.101	300.052	300.000	0.084
	Min	300.000	299.350	0.330	300.000	299.680	0.190	300.000	299.892	0.056	300.000	299.951	0.017	300.000	299.968	0.000
400	Max	400.360	399.600	1.120	400.140	399.790	0.490	400.089	399.938	0.208	400.057	399.982	0.111	400.057	400.000	0.093
	Min	400.000	399.240	0.400	400.000	399.650	0.210	400.000	399.881	0.062	400.000	399.946	0.018	400.000	399.964	0.000
500	Max	500.400	499.520	1.280	500.155	499.770	0.540	500.097	499.932	0.228	500.063	499.980	0.123	500.063	500.000	0.103
	Min	500.000	499.120	0.480	500.000	499.615	0.230	500.000	499.869	0.068	500.000	499.940	0.020	500.000	499.960	0.000

[a] The sizes shown are first-choice basic sizes (see Table 1). Preferred fits for other sizes can be calculated from data given in ANSI B4.2-1978 (R1999).
[b] All fits shown in this table have clearance.
All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Preferred Hole Basis Metric Transition and Interference Fits *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Locational Transition			Locational Transition			Locational Interference			Medium Drive			Force		
		Hole H7	Shaft k6	Fit[b]	Hole H7	Shaft n6	Fit[b]	Hole H7	Shaft p6	Fit[b]	Hole H7	Shaft s6	Fit[b]	Hole H7	Shaft u6	Fit[b]
1	Max	1.010	1.006	+0.010	1.010	1.010	+0.006	1.010	1.012	+0.004	1.010	1.020	−0.004	1.010	1.024	−0.008
	Min	1.000	1.000	−0.006	1.000	1.004	−0.010	1.000	1.006	−0.012	1.000	1.014	−0.020	1.000	1.018	−0.024
1.2	Max	1.210	1.206	+0.010	1.210	1.210	+0.006	1.210	1.212	+0.004	1.210	1.220	−0.004	1.210	1.224	−0.008
	Min	1.200	1.200	−0.006	1.200	1.204	−0.010	1.200	1.206	−0.012	1.200	1.214	−0.020	1.200	1.218	−0.024
1.6	Max	1.610	1.606	+0.010	1.610	1.610	+0.006	1.610	1.612	+0.004	1.610	1.620	−0.004	1.610	1.624	−0.008
	Min	1.600	1.600	−0.006	1.600	1.604	−0.010	1.600	1.606	−0.012	1.600	1.614	−0.020	1.600	1.618	−0.024
2	Max	2.010	2.006	+0.010	2.010	2.010	+0.006	2.010	2.012	+0.004	2.010	2.020	−0.004	2.010	2.024	−0.008
	Min	2.000	2.000	−0.006	2.000	2.004	−0.010	2.000	2.006	−0.012	2.000	2.014	−0.020	2.000	2.018	−0.024
2.5	Max	2.510	2.506	+0.010	2.510	2.510	+0.006	2.510	2.512	+0.004	2.510	2.520	−0.004	2.510	2.524	−0.008
	Min	2.500	2.500	−0.006	2.500	2.504	−0.010	2.500	2.506	−0.012	2.500	2.514	−0.020	2.500	2.518	−0.024
3	Max	3.010	3.006	+0.010	3.010	3.010	+0.006	3.010	3.012	+0.004	3.010	3.020	−0.004	3.010	3.024	−0.008
	Min	3.000	3.000	−0.006	3.000	3.004	−0.010	3.000	3.006	−0.012	3.000	3.014	−0.020	3.000	3.018	−0.024
4	Max	4.012	4.009	+0.011	4.012	4.016	+0.004	4.012	4.020	0.000	4.012	4.027	−0.007	4.012	4.031	−0.011
	Min	4.000	4.001	−0.009	4.000	4.008	−0.016	4.000	4.012	−0.020	4.000	4.019	−0.027	4.000	4.023	−0.031
5	Max	5.012	5.009	+0.011	5.012	5.016	+0.004	5.012	5.020	0.000	5.012	5.027	−0.007	5.012	5.031	−0.011
	Min	5.000	5.001	−0.009	5.000	5.008	−0.016	5.000	5.012	−0.020	5.000	5.019	−0.027	5.000	5.023	−0.031
6	Max	6.012	6.009	+0.011	6.012	6.016	+0.004	6.012	6.020	0.000	6.012	6.027	−0.007	6.012	6.031	−0.011
	Min	6.000	6.001	−0.009	6.000	6.008	−0.016	6.000	6.012	−0.020	6.000	6.019	−0.027	6.000	6.023	−0.031
8	Max	8.015	8.010	+0.014	8.015	8.019	+0.005	8.015	8.024	0.000	8.015	8.032	−0.008	8.015	8.037	−0.013
	Min	8.000	8.001	−0.010	8.000	8.010	−0.019	8.000	8.015	−0.024	8.000	8.023	−0.032	8.000	8.028	−0.037
10	Max	10.015	10.010	+0.014	10.015	10.019	+0.005	10.015	10.024	0.000	10.015	10.032	−0.008	10.015	10.034	−0.013
	Min	10.000	10.001	−0.010	10.000	10.010	−0.019	10.000	10.015	−0.024	10.000	10.023	−0.032	10.000	10.028	−0.037
12	Max	12.018	12.012	+0.017	12.018	12.023	+0.006	12.018	12.029	0.000	12.018	12.039	−0.010	12.018	12.044	−0.015
	Min	12.000	12.001	−0.012	12.000	12.012	−0.023	12.000	12.018	−0.029	12.000	12.028	−0.039	12.000	12.033	−0.044
16	Max	16.018	16.012	+0.017	16.018	16.023	+0.006	16.018	16.029	0.000	16.018	16.039	−0.010	16.018	16.044	−0.015
	Min	16.000	16.001	−0.012	16.000	16.012	−0.023	16.000	16.018	−0.029	16.000	16.028	−0.039	16.000	16.033	−0.044
20	Max	20.021	20.015	+0.019	20.021	20.028	+0.006	20.021	20.035	−0.001	20.021	20.048	−0.014	20.021	20.054	−0.020
	Min	20.000	20.002	−0.015	20.000	20.015	−0.028	20.000	20.022	−0.035	20.000	20.035	−0.048	20.000	20.041	−0.054
25	Max	25.021	25.015	+0.019	25.021	25.028	+0.006	25.021	25.035	−0.001	25.021	25.048	−0.014	25.021	25.061	−0.027
	Min	25.000	25.002	−0.015	25.000	25.015	−0.028	25.000	25.022	−0.035	25.000	25.035	−0.048	25.000	25.048	−0.061

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **American National Standard Preferred Hole Basis Metric Transition and Interference Fits** *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Locational Transition			Locational Transition			Locational Interference			Medium Drive			Force		
		Hole H7	Shaft k6	Fit[b]	Hole H7	Shaft n6	Fit[b]	Hole H7	Shaft p6	Fit[b]	Hole H7	Shaft s6	Fit[b]	Hole H7	Shaft u6	Fit[b]
30	Max	30.021	30.015	+0.019	30.021	30.028	+0.006	30.021	30.035	−0.001	30.021	30.048	−0.014	30.021	30.061	−0.027
	Min	30.000	30.002	−0.015	30.000	30.015	−0.028	30.000	30.022	−0.035	30.000	30.035	−0.048	30.000	30.048	−0.061
40	Max	40.025	40.018	+0.023	40.025	40.033	+0.008	40.025	40.042	−0.001	40.025	40.059	−0.018	40.025	40.076	−0.035
	Min	40.000	40.002	−0.018	40.000	40.017	−0.033	40.000	40.026	−0.042	40.000	40.043	−0.059	40.000	40.060	−0.076
50	Max	50.025	50.018	+0.023	50.025	50.033	+0.008	50.025	50.042	−0.001	50.025	50.059	−0.018	50.025	50.086	−0.045
	Min	50.000	50.002	−0.018	50.000	50.017	−0.033	50.000	50.026	−0.042	50.000	50.043	−0.059	50.000	50.070	−0.086
60	Max	60.030	60.021	+0.028	60.030	60.039	+0.010	60.030	60.051	−0.002	60.030	60.072	−0.023	60.030	60.106	−0.057
	Min	60.000	60.002	−0.021	60.000	60.020	−0.039	60.000	60.032	−0.051	60.000	60.053	−0.072	60.000	60.087	−0.106
80	Max	80.030	80.021	+0.028	80.030	80.039	+0.010	80.030	80.051	−0.002	80.030	80.078	−0.029	80.030	80.121	−0.072
	Min	80.000	80.002	−0.021	80.000	80.020	−0.039	80.000	80.032	−0.051	80.000	80.059	−0.078	80.000	80.102	−0.121
100	Max	100.035	100.025	+0.032	100.035	100.045	+0.012	100.035	100.059	−0.002	100.035	100.093	−0.036	100.035	100.146	−0.089
	Min	100.000	100.003	−0.025	100.000	100.023	−0.045	100.000	100.037	−0.059	100.000	100.071	−0.093	100.000	100.124	−0.146
120	Max	120.035	120.025	+0.032	120.035	120.045	+0.012	120.035	120.059	−0.002	120.035	120.101	−0.044	120.035	120.166	−0.109
	Min	120.000	120.003	−0.025	120.000	120.023	−0.045	120.000	120.037	−0.059	120.000	120.079	−0.101	120.000	120.144	−0.166
160	Max	160.040	160.028	+0.037	160.040	160.052	+0.013	160.040	160.068	−0.003	160.040	160.125	−0.060	160.040	160.215	−0.150
	Min	160.000	160.003	−0.028	160.000	160.027	−0.052	160.000	160.043	−0.068	160.000	160.100	−0.125	160.000	160.190	−0.215
200	Max	200.046	200.033	+0.042	200.046	200.060	+0.015	200.046	200.079	−0.004	200.046	200.151	−0.076	200.046	200.265	−0.190
	Min	200.000	200.004	−0.033	200.000	200.031	−0.060	200.000	200.050	−0.079	200.000	200.122	−0.151	200.000	200.236	−0.265
250	Max	250.046	250.033	+0.042	250.046	250.060	+0.015	250.046	250.079	−0.004	250.046	250.169	−0.094	250.046	250.313	−0.238
	Min	250.000	250.004	−0.033	250.000	250.031	−0.060	250.000	250.050	−0.079	250.000	250.140	−0.169	250.000	250.284	−0.313
300	Max	300.052	300.036	+0.048	300.052	300.066	+0.018	300.052	300.088	−0.004	300.052	300.202	−0.118	300.052	300.382	−0.298
	Min	300.000	300.004	−0.036	300.000	300.034	−0.066	300.000	300.056	−0.088	300.000	300.170	−0.202	300.000	300.350	−0.382
400	Max	400.057	400.040	+0.053	400.057	400.073	+0.020	400.057	400.098	−0.005	400.057	400.244	−0.151	400.057	400.471	−0.378
	Min	400.000	400.004	−0.040	400.000	400.037	−0.073	400.000	400.062	−0.098	400.000	400.208	−0.244	400.000	400.435	−0.471
500	Max	500.063	500.045	+0.058	500.063	500.080	+0.023	500.063	500.108	−0.005	500.063	500.292	−0.189	500.063	500.580	−0.477
	Min	500.000	500.005	−0.045	500.000	500.040	−0.080	500.000	500.068	−0.108	500.000	500.252	−0.292	500.000	500.540	−0.580

[a] The sizes shown are first-choice basic sizes (see Table 1). Preferred fits for other sizes can be calculated from data given in ANSI B4.2-1978 (R1999).
[b] A plus sign indicates clearance; a minus sign indicates interference.
All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Preferred Shaft Basis Metric Clearance Fits *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Loose Running			Free Running			Close Running			Sliding			Locational Clearance		
		Hole C11	Shaft h11	Fit[b]	Hole D9	Shaft h9	Fit[b]	Hole F8	Shaft h7	Fit[b]	Hole G7	Shaft h6	Fit[b]	Hole H7	Shaft h6	Fit[b]
1	Max	1.120	1.000	0.180	1.045	1.000	0.070	1.020	1.000	0.030	1.012	1.000	0.018	1.010	1.000	0.016
	Min	1.060	0.940	0.060	1.020	0.975	0.020	1.006	0.990	0.006	1.002	0.994	0.002	1.000	0.994	0.000
1.2	Max	1.320	1.200	0.180	1.245	1.200	0.070	1.220	1.200	0.030	1.212	1.200	0.018	1.210	1.200	0.016
	Min	1.260	1.140	0.060	1.220	1.175	0.020	1.206	1.190	0.006	1.202	1.194	0.002	1.200	1.194	0.000
1.6	Max	1.720	1.600	0.180	1.645	1.600	0.070	1.620	1.600	0.030	1.612	1.600	0.018	1.610	1.600	0.016
	Min	1.660	1.540	0.060	1.620	1.575	0.020	1.606	1.590	0.006	1.602	1.594	0.002	1.600	1.594	0.000
2	Max	2.120	2.000	0.180	2.045	2.000	0.070	2.020	2.000	0.030	2.012	2.000	0.018	2.010	2.000	0.016
	Min	2.060	1.940	0.060	2.020	1.975	0.020	2.006	1.990	0.006	2.002	1.994	0.002	2.000	1.994	0.000
2.5	Max	2.620	2.500	0.180	2.545	2.500	0.070	2.520	2.500	0.030	2.512	2.500	0.018	2.510	2.500	0.016
	Min	2.560	2.440	0.060	2.520	2.475	0.020	2.506	2.490	0.006	2.502	2.494	0.002	2.500	2.494	0.000
3	Max	3.120	3.000	0.180	3.045	3.000	0.070	3.020	3.000	0.030	3.012	3.000	0.018	3.010	3.000	0.016
	Min	3.060	2.940	0.060	3.020	2.975	0.020	3.006	2.990	0.006	3.002	2.994	0.002	3.000	2.994	0.000
4	Max	4.145	4.000	0.220	4.060	4.000	0.090	4.028	4.000	0.040	4.016	4.000	0.024	4.012	4.000	0.020
	Min	4.070	3.925	0.070	4.030	3.970	0.030	4.010	3.988	0.010	4.004	3.992	0.004	4.000	3.992	0.000
5	Max	5.145	5.000	0.220	5.060	5.000	0.090	5.028	5.000	0.040	5.016	5.000	0.024	5.012	5.000	0.020
	Min	5.070	4.925	0.070	5.030	4.970	0.030	5.010	4.988	0.010	5.004	4.992	0.004	5.000	4.992	0.000
6	Max	6.145	6.000	0.220	6.060	6.000	0.090	6.028	6.000	0.040	6.016	6.000	0.024	6.012	6.000	0.020
	Min	6.070	5.925	0.070	6.030	5.970	0.030	6.010	5.988	0.010	6.004	5.992	0.004	6.000	5.992	0.000
8	Max	8.170	8.000	0.260	8.076	8.000	0.112	8.035	8.000	0.050	8.020	8.000	0.029	8.015	8.000	0.024
	Min	8.080	7.910	0.080	8.040	7.964	0.040	8.013	7.985	0.013	8.005	7.991	0.005	8.000	7.991	0.000
10	Max	10.170	10.000	0.260	10.076	10.000	0.112	10.035	10.000	0.050	10.020	10.000	0.029	10.015	10.000	0.024
	Min	10.080	9.910	0.080	10.040	9.964	0.040	10.013	9.985	0.013	10.005	9.991	0.005	10.000	9.991	0.000
12	Max	12.205	12.000	0.315	12.093	12.000	0.136	12.043	12.000	0.061	12.024	12.000	0.035	12.018	12.000	0.029
	Min	12.095	11.890	0.095	12.050	11.957	0.050	12.016	11.982	0.016	12.006	11.989	0.006	12.000	11.989	0.000
16	Max	16.205	16.000	0.315	16.093	16.000	0.136	16.043	16.000	0.061	16.024	16.000	0.035	16.018	16.000	0.029
	Min	16.095	15.890	0.095	16.050	15.957	0.050	16.016	15.982	0.016	16.006	15.989	0.006	16.000	15.989	0.000
20	Max	20.240	20.000	0.370	20.117	20.000	0.169	20.053	20.000	0.074	20.028	20.000	0.041	20.021	20.000	0.034
	Min	20.110	19.870	0.110	20.065	19.948	0.065	20.020	19.979	0.020	20.007	19.987	0.007	20.000	19.987	0.000
25	Max	25.240	25.000	0.370	25.117	25.000	0.169	25.053	25.000	0.074	25.028	25.000	0.041	25.021	25.000	0.034
	Min	25.110	24.870	0.110	25.065	24.948	0.065	25.020	24.979	0.020	25.007	24.987	0.007	25.000	24.987	0.000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **American National Standard Preferred Shaft Basis Metric Clearance Fits** *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Loose Running			Free Running			Close Running			Sliding			Locational Clearance		
		Hole C11	Shaft h11	Fit[b]	Hole D9	Shaft h9	Fit[b]	Hole F8	Shaft h7	Fit[b]	Hole G7	Shaft h6	Fit[b]	Hole H7	Shaft h6	Fit[b]
30	Max	30.240	30.000	0.370	30.117	30.000	0.169	30.053	30.000	0.074	30.028	30.000	0.041	30.021	30.000	0.034
	Min	30.110	29.870	0.110	30.065	29.948	0.065	30.020	29.979	0.020	30.007	29.987	0.007	30.000	29.987	0.000
40	Max	40.280	40.000	0.440	40.142	40.000	0.204	40.064	40.000	0.089	40.034	40.000	0.050	40.025	40.000	0.041
	Min	40.120	39.840	0.120	40.080	39.938	0.080	40.025	39.975	0.025	40.009	39.984	0.009	40.000	39.984	0.000
50	Max	50.290	50.000	0.450	50.142	50.000	0.204	50.064	50.000	0.089	50.034	50.000	0.050	50.025	50.000	0.041
	Min	50.130	49.840	0.130	50.080	49.938	0.080	50.025	49.975	0.025	50.009	49.984	0.009	50.000	49.984	0.000
60	Max	60.330	60.000	0.520	60.174	60.000	0.248	60.076	60.000	0.106	60.040	60.000	0.059	60.030	60.000	0.049
	Min	60.140	59.810	0.140	60.100	59.926	0.100	60.030	59.970	0.030	60.010	59.981	0.010	60.000	59.981	0.000
80	Max	80.340	80.000	0.530	80.174	80.000	0.248	80.076	80.000	0.106	80.040	80.000	0.059	80.030	80.000	0.049
	Min	80.150	79.810	0.150	80.100	79.926	0.100	80.030	79.970	0.030	80.010	79.981	0.010	80.000	79.981	0.000
100	Max	100.390	100.000	0.610	100.207	100.000	0.294	100.090	100.000	0.125	100.047	100.000	0.069	100.035	100.000	0.057
	Min	100.170	99.780	0.170	100.120	99.913	0.120	100.036	99.965	0.036	100.012	99.978	0.012	100.000	99.978	0.000
120	Max	120.400	120.000	0.620	120.207	120.000	0.294	120.090	120.000	0.125	120.047	120.000	0.069	120.035	120.000	0.057
	Min	120.180	119.780	0.180	120.120	119.913	0.120	120.036	119.965	0.036	120.012	119.978	0.012	120.000	119.978	0.000
160	Max	160.460	160.000	0.710	160.245	160.000	0.345	160.106	160.000	0.146	160.054	160.000	0.079	160.040	160.000	0.065
	Min	160.210	159.750	0.210	160.145	159.900	0.145	160.043	159.960	0.043	160.014	159.975	0.014	160.000	159.975	0.000
200	Max	200.530	200.000	0.820	200.285	200.000	0.400	200.122	200.000	0.168	200.061	200.000	0.090	200.046	200.000	0.075
	Min	200.240	199.710	0.240	200.170	199.885	0.170	200.050	199.954	0.050	200.015	199.971	0.015	200.000	199.971	0.000
250	Max	250.570	250.000	0.860	250.285	250.000	0.400	250.122	250.000	0.168	250.061	250.000	0.090	250.046	250.000	0.075
	Min	250.280	249.710	0.280	250.170	249.885	0.170	250.050	249.954	0.050	250.015	249.971	0.015	250.000	249.971	0.000
300	Max	300.650	300.000	0.970	300.320	300.000	0.450	300.137	300.000	0.189	300.069	300.000	0.101	300.052	300.000	0.084
	Min	300.330	299.680	0.330	300.190	299.870	0.190	300.056	299.948	0.056	300.017	299.968	0.017	300.000	299.968	0.000
400	Max	400.760	400.000	1.120	400.350	400.000	0.490	400.151	400.000	0.208	400.075	400.000	0.111	400.057	400.000	0.093
	Min	400.400	399.640	0.400	400.210	399.860	0.210	400.062	399.943	0.062	400.018	399.964	0.018	400.000	399.964	0.000
500	Max	500.880	500.000	1.280	500.385	500.000	0.540	500.165	500.000	0.228	500.083	500.000	0.123	500.063	500.000	0.103
	Min	500.480	499.600	0.480	500.230	499.845	0.230	500.068	499.937	0.068	500.020	499.960	0.020	500.000	499.960	0.000

[a] The sizes shown are first-choice basic sizes (see Table 1). Preferred fits for other sizes can be calculated from data given in ANSI B4.2-1978 (R1999).
[b] All fits shown in this table have clearance.
All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Preferred Shaft Basis Metric Transition and Interference Fits *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Locational Transition			Locational Transition			Locational Interference			Medium Drive			Force		
		Hole K7	Shaft h6	Fit[b]	Hole N7	Shaft h6	Fit[b]	Hole P7	Shaft h6	Fit[b]	Hole S7	Shaft h6	Fit[b]	Hole U7	Shaft h6	Fit[b]
1	Max	1.000	1.000	+0.006	0.996	1.000	+0.002	0.994	1.000	0.000	0.986	1.000	−0.008	0.982	1.000	−0.012
	Min	0.990	0.994	−0.010	0.986	0.994	−0.014	0.984	0.994	−0.016	0.976	0.994	−0.024	0.972	0.994	−0.028
1.2	Max	1.200	1.200	+0.006	1.196	1.200	+0.002	1.194	1.200	0.000	1.186	1.200	−0.008	1.182	1.200	−0.012
	Min	1.190	1.194	−0.010	1.186	1.194	−0.014	1.184	1.194	−0.016	1.176	1.194	−0.024	1.172	1.194	−0.028
1.6	Max	1.600	1.600	+0.006	1.596	1.600	+0.002	1.594	1.600	0.000	1.586	1.600	−0.008	1.582	1.600	−0.012
	Min	1.590	1.594	−0.010	1.586	1.594	−0.014	1.584	1.594	−0.016	1.576	1.594	−0.024	1.572	1.594	−0.028
2	Max	2.000	2.000	+0.006	1.996	2.000	+0.002	1.994	2.000	0.000	1.986	2.000	−0.008	1.982	2.000	−0.012
	Min	1.990	1.994	−0.010	1.986	1.994	−0.014	1.984	1.994	−0.016	1.976	1.994	−0.024	1.972	1.994	−0.028
2.5	Max	2.500	2.500	+0.006	2.496	2.500	+0.002	2.494	2.500	0.000	2.486	2.500	−0.008	2.482	2.500	−0.012
	Min	2.490	2.494	−0.010	2.486	2.494	−0.014	2.484	2.494	−0.016	2.476	2.494	−0.024	2.472	2.494	−0.028
3	Max	3.000	3.000	+0.006	2.996	3.000	+0.002	2.994	3.000	0.000	2.986	3.000	−0.008	2.982	3.000	−0.012
	Min	2.990	2.994	−0.010	2.986	2.994	−0.014	2.984	2.994	−0.016	2.976	2.994	−0.024	2.972	2.994	−0.028
4	Max	4.003	4.000	+0.011	3.996	4.000	+0.004	3.992	4.000	0.000	3.985	4.000	−0.007	3.981	4.000	−0.011
	Min	3.991	3.992	−0.009	3.984	3.992	−0.016	3.980	3.992	−0.020	3.973	3.992	−0.027	3.969	3.992	−0.031
5	Max	5.003	5.000	+0.011	4.996	5.000	+0.004	4.992	5.000	0.000	4.985	5.000	−0.007	4.981	5.000	−0.011
	Min	4.991	4.992	−0.009	4.984	4.992	−0.016	4.980	4.992	−0.020	4.973	4.992	−0.027	4.969	4.992	−0.031
6	Max	6.003	6.000	+0.011	5.996	6.000	+0.004	5.992	6.000	0.000	5.985	6.000	−0.007	5.981	6.000	−0.011
	Min	5.991	5.992	−0.009	5.984	5.992	−0.016	5.980	5.992	−0.020	5.973	5.992	−0.027	5.969	5.992	−0.031
8	Max	8.005	8.000	+0.014	7.996	8.000	+0.005	7.991	8.000	0.000	7.983	8.000	−0.008	7.978	8.000	−0.013
	Min	7.990	7.991	−0.010	7.981	7.991	−0.019	7.976	7.991	−0.024	7.968	7.991	−0.032	7.963	7.991	−0.037
10	Max	10.005	10.000	+0.014	9.996	10.000	+0.005	9.991	10.000	0.000	9.983	10.000	−0.008	9.978	10.000	−0.013
	Min	9.990	9.991	−0.010	9.981	9.991	−0.019	9.976	9.991	−0.024	9.968	9.991	−0.032	9.963	9.991	−0.037
12	Max	12.006	12.000	+0.017	11.995	12.000	+0.006	11.989	12.000	0.000	11.979	12.000	−0.010	11.974	12.000	−0.015
	Min	11.988	11.989	−0.012	11.977	11.989	−0.023	11.971	11.989	−0.029	11.961	11.989	−0.039	11.956	11.989	−0.044
16	Max	16.006	16.000	+0.017	15.995	16.000	+0.006	15.989	16.000	0.000	15.979	16.000	−0.010	15.974	16.000	−0.015
	Min	15.988	15.989	−0.012	15.977	15.989	−0.023	15.971	15.989	−0.029	15.961	15.989	−0.039	15.956	15.989	−0.044
20	Max	20.006	20.000	+0.019	19.993	20.000	+0.006	19.986	20.000	−0.001	19.973	20.000	−0.014	19.967	20.000	−0.020
	Min	19.985	19.987	−0.015	19.972	19.987	−0.028	19.965	19.987	−0.035	19.952	19.987	−0.048	19.946	19.987	−0.054
25	Max	25.006	25.000	+0.019	24.993	25.000	+0.006	24.986	25.000	−0.001	24.973	25.000	−0.014	24.960	25.000	−0.027
	Min	24.985	24.987	−0.015	24.972	24.987	−0.028	24.965	24.987	−0.035	24.952	24.987	−0.048	24.939	24.987	−0.061

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Standard Preferred Shaft Basis Metric Transition and Interference Fits** *ANSI B4.2-1978 (R1999)*

Basic Size[a]		Locational Transition			Locational Transition			Locational Interference			Medium Drive			Force		
		Hole K7	Shaft h6	Fit[b]	Hole N7	Shaft h6	Fit[b]	Hole P7	Shaft h6	Fit[b]	Hole S7	Shaft h6	Fit[b]	Hole U7	Shaft h6	Fit[b]
30	Max	30.006	30.000	+0.019	29.993	30.000	+0.006	29.986	30.000	–0.001	29.973	30.000	–0.014	29.960	30.000	–0.027
	Min	29.985	29.987	–0.015	29.972	29.987	–0.028	29.965	29.987	–0.035	29.952	29.987	–0.048	29.939	29.987	–0.061
40	Max	40.007	40.000	+0.023	39.992	40.000	+0.008	39.983	40.000	–0.001	39.966	40.000	–0.018	39.949	40.000	–0.035
	Min	39.982	39.984	–0.018	39.967	39.984	–0.033	39.958	39.984	–0.042	39.941	39.984	–0.059	39.924	39.984	–0.076
50	Max	50.007	50.000	+0.023	49.992	50.000	+0.008	49.983	50.000	–0.001	49.966	50.000	–0.018	49.939	50.000	–0.045
	Min	49.982	49.984	–0.018	49.967	49.984	–0.033	49.958	49.984	–0.042	49.941	49.984	–0.059	49.914	49.984	–0.086
60	Max	60.009	60.000	+0.028	59.991	60.000	+0.010	59.979	60.000	–0.002	59.958	60.000	–0.023	59.924	60.000	–0.087
	Min	59.979	59.981	–0.021	59.961	59.981	–0.039	59.949	59.981	–0.051	59.928	59.981	–0.072	59.894	59.981	–0.106
80	Max	80.009	80.000	+0.028	79.991	80.000	+0.010	79.979	80.000	–0.002	79.952	80.000	–0.029	79.909	80.000	–0.072
	Min	79.979	79.981	–0.021	79.961	79.981	–0.039	79.949	79.981	–0.051	79.922	79.981	–0.078	79.879	79.981	–0.121
100	Max	100.010	100.000	+0.032	99.990	100.000	+0.012	99.976	100.000	–0.002	99.942	100.000	–0.036	99.889	100.000	–0.089
	Min	99.975	99.978	–0.025	99.955	99.978	–0.045	99.941	99.978	–0.059	99.907	99.978	–0.093	99.854	99.978	–0.146
120	Max	120.010	120.000	+0.032	119.990	120.000	+0.012	119.976	120.000	–0.002	119.934	120.000	–0.044	119.869	120.000	–0.109
	Min	119.975	119.978	–0.025	119.955	119.978	–0.045	119.941	119.978	–0.059	119.899	119.978	–0.101	119.834	119.978	–0.166
160	Max	160.012	160.000	+0.037	159.988	160.000	+0.013	159.972	160.000	–0.003	159.915	160.000	–0.060	159.825	160.000	–0.150
	Min	159.972	159.975	–0.028	159.948	159.975	–0.052	159.932	159.975	–0.068	159.875	159.975	–0.125	159.785	159.975	–0.215
200	Max	200.013	200.00	+0.042	199.986	200.000	+0.015	199.967	200.000	–0.004	199.895	200.000	–0.076	199.781	200.000	–0.190
	Min	199.967	199.971	–0.033	199.940	199.971	–0.060	199.921	199.971	–0.079	199.849	199.971	–0.151	199.735	199.971	–0.265
250	Max	250.013	250.000	+0.042	249.986	250.000	+0.015	249.967	250.000	–0.004	249.877	250.000	–0.094	249.733	250.000	–0.238
	Min	249.967	249.971	–0.033	249.940	249.971	–0.060	249.921	249.971	–0.079	249.831	249.971	–0.169	249.687	249.971	–0.313
300	Max	300.016	300.000	+0.048	299.986	300.000	+0.018	299.964	300.000	–0.004	299.850	300.000	–0.118	299.670	300.000	–0.298
	Min	299.964	299.968	–0.036	299.934	299.968	–0.066	299.912	299.968	–0.088	299.798	299.968	–0.202	299.618	299.968	–0.382
400	Max	400.017	400.000	+0.053	399.984	400.000	+0.020	399.959	400.000	–0.005	399.813	400.000	–0.151	399.586	400.000	–0.378
	Min	399.960	399.964	–0.040	399.927	399.964	–0.073	399.902	399.964	–0.098	399.756	399.964	–0.244	399.529	399.964	–0.471
500	Max	500.018	500.000	+0.058	499.983	500.000	+0.023	499.955	500.000	–0.005	499.771	500.000	–0.189	499.483	500.000	–0.477
	Min	499.955	499.960	–0.045	499.920	499.960	–0.080	499.892	499.960	–0.108	499.708	499.960	–0.292	499.420	499.960	–0.580

[a] The sizes shown are first-choice basic sizes (see Table 1). Preferred fits for other sizes can be calculated from data given in ANSI B4.2-1978 (R1999).
[b] A plus sign indicates clearance; a minus sign indicates interference.
All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Gagemakers Tolerances
ANSI B4.4M-1981 (R1987)

Gagemakers Tolerance			Workpiece Tolerance	
	Class	ISO Symbol[a]	IT Grade	Recommended Gage Usage
Rejection of Good Parts Increase ↑	ZM	0.05 IT11	IT11	Low-precision gages recommended to be used to inspect workpieces held to internal (hole) tolerances C11 and H11 and to external (shaft) tolerances c11 and h11.
	YM	0.05 IT9	IT9	Gages recommended to be used to inspect workpieces held to internal (hole) tolerances D9 and H9 and to external (shaft) tolerances d9 and h9.
	XM	0.05 IT8	IT8	Precision gages recommended to be used to inspect workpieces held to internal (hole) tolerances F8 and H8.
Gage Cost Increase ↓	XXM	0.05 IT7	IT7	Recommended to be used for gages to inspect workpieces held to internal (hole) tolerances G7, H7, K7, N7, P7, S7, and U7, and to external (shaft) tolerances f7 and h7.
	XXXM	0.05 IT6	IT6	High-precision gages recommended to be used to inspect workpieces held to external (shaft) tolerances g6, h6, k6, n6, p6, s6, and u6.

[a] Gagemakers tolerance is equal to 5 per cent of workpiece tolerance or 5 per cent of applicable IT grade value. See Table 7.

For workpiece tolerance class values, see previous Tables 2 through 5, incl.

Table 7. American National Standard Gagemakers Tolerances
ANSI B4.4M-1981 (R1987)

Basic Size		Class ZM	Class YM	Class XM	Class XXM	Clas XXXM
Over	To	(0.05 IT11)	(0.05 IT9)	(0.05 IT8)	(0.05 IT7)	(0.05 IT6)
0	3	0.0030	0.0012	0.0007	0.0005	0.0003
3	6	0.0037	0.0015	0.0009	0.0006	0.0004
6	10	0.0045	0.0018	0.0011	0.0007	0.0005
10	18	0.0055	0.0021	0.0013	0.0009	0.0006
18	30	0.0065	0.0026	0.0016	0.0010	0.0007
30	50	0.0080	0.0031	0.0019	0.0012	0.0008
50	80	0.0095	0.0037	0.0023	0.0015	0.0010
80	120	0.0110	0.0043	0.0027	0.0017	0.0011
120	180	0.0125	0.0050	0.0031	0.0020	0.0013
180	250	0.0145	0.0057	0.0036	0.0023	0.0015
250	315	0.0160	0.0065	0.0040	0.0026	0.0016
315	400	0.0180	0.0070	0.0044	0.0028	0.0018
400	500	0.0200	0.0077	0.0048	0.0031	0.0020

All dimensions are in millimeters. For closer gagemakers tolerance classes than Class XXXM, specify 5 per cent of IT5, IT4, or IT3 and use the designation 0.05 IT5, 0.05 IT4, etc.



Fig. 4. Relationship between Gagemakers Tolerance, Wear Allowance and Workpiece Tolerance

Copyright 2004, Industrial Press, Inc., New York, NY

Applications.— Many factors such as length of engagement, bearing load, speed, lubrication, operating temperatures, humidity, surface texture, and materials must be taken into account in fit selections for a particular application.

Choice of other than the preferred fits might be considered necessary to satisfy extreme conditions. Subsequent adjustments might also be desired as the result of experience in a particular application to suit critical functional requirements or to permit optimum manufacturing economy. Selection of a departure from these recommendations will depend upon consideration of the engineering and economic factors that might be involved; however, the benefits to be derived from the use of preferred fits should not be overlooked.

A general guide to machining processes that may normally be expected to produce work within the tolerances indicated by the IT grades given in ANSI B4.2-1978 (R1999) is shown in Table 8. Practical usage of the various IT tolerance grades is shown in Table 9.

Table 8. Relation of Machining Processes to IT Tolerance Grades



Table 9. Practical Use of International Tolerance Grades

	For Measurig Tools										For Material										
IT Grades	01	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16			
							For Fits							For Large Manufacturing Tolerances							

British Standard for Metric ISO Limits and Fits

Based on ISO Recommendation R286, this British Standard BS 4500:1969 is intended to provide a comprehensive range of metric limits and fits for engineering purposes, and meets the requirements of metrication in the United Kingdom. Sizes up to 3,150 mm are covered by the Standard, but the condensed information presented here embraces dimensions up to 500 mm only. The system is based on a series of tolerances graded to suit all classes of work from the finest to the most coarse, and the different types of fits that can be obtained range from coarse clearance to heavy interference. In the Standard, only cylindrical parts, designated holes and shafts are referred to explicitly, but it is emphasized that the recommendations apply equally well to other sections, and the general term *hole* or *shaft*

Copyright 2004, Industrial Press, Inc., New York, NY

can be taken to mean the space contained by or containing two parallel faces or tangent planes of any part, such as the width of a slot, or the thickness of a key. It is also strongly emphasized that the grades series of tolerances are intended for the most general application, and should be used wherever possible whether the features of the component involved are members of a fit or not.

Definitions.— The definitions given in the Standard include the following:

Limits of Size: The maximum and minimum sizes permitted for a feature.

Basic Size: The reference size to which the limits of size are fixed. The basic size is the same for both members of a fit.

Upper Deviation: The algebraical difference between the maximum limit of size and the corresponding basic size. It is designated as ES for a hole, and as es for a shaft, which stands for the French term *écart supérieur*.

Lower Deviation: The algebraical difference between the minimum limit of size and the corresponding basic size. It is designated as EI for a hole, and as ei for a shaft, which stands for the French term *écart inférieur*.

Zero Line: In a graphical representation of limits and fits, the straight line to which the deviations are referred. The zero line is the line of zero deviation and represents the basic size.

Tolerance: The difference between the maximum limit of size and the minimum limit of size. It is an absolute value without sign.

Tolerance Zone: In a graphical representation of tolerances, the zone comprised between the two lines representing the limits of tolerance and defined by its magnitude (tolerance) and by its position in relation to the zero line.

Fundamental Deviation: That one of the two deviations, being the one nearest to the zero line, which is conventionally chosen to define the position of the tolerance zone in relation to the zero line.

Shaft-Basis System of Fits: A system of fits in which the different clearances and interferences are obtained by associating various holes with a single shaft. In the ISO system, the basic shaft is the shaft the upper deviation of which is zero.

Hole-Basis System of Fits: A system of fits in which the different clearances and interferences are obtained by associating various shafts with a single hole. In the ISO system, the basic hole is the hole the lower deviation of which is zero.

Selected Limits of Tolerance, and Fits.— The number of fit combinations that can be built up with the ISO system is very large. However, experience shows that the majority of fits required for usual engineering products can be provided by a limited selection of tolerances. Limits of tolerance for selected holes are shown in Table 1, and for shafts, in Table 2. Selected fits, based on combinations of the selected hole and shaft tolerances, are given in Table 3.

Tolerances and Fundamental Deviations.— There are 18 tolerance grades intended to meet the requirements of different classes of work, and they are designated IT01, IT0, and IT1 to IT16. (IT stands for ISO series of tolerances.) Table 4 shows the standardized numerical values for the 18 tolerance grades, which are known as standard tolerances. The system provides 27 fundamental deviations for sizes up to and including 500 mm, and Tables 5a and 5b contain the values for shafts and Tables 6a and 6b for holes. Uppercase (capital) letters designate hole deviations, and the same letters in lower case designate shaft deviations. The deviation j_s (J_s for holes) is provided to meet the need for symmetrical bilateral tolerances. In this instance, there is no fundamental deviation, and the tolerance zone, of whatever magnitude, is equally disposed about the zero line.

Calculated Limits of Tolerance.— The deviations and fundamental tolerances provided by the ISO system can be combined in any way that appears necessary to give a required fit. Thus, for example, the deviations H (basic hole) and f (clearance shaft) could be associated, and with each of these deviations any one of the tolerance grades IT01 to IT16 could

Copyright 2004, Industrial Press, Inc., New York, NY

be used. All the limits of tolerance that the system is capable of providing for sizes up to and including 500 mm can be calculated from the standard tolerances given in Table 4, and the fundamental deviations given in Tables 5a, 5b, 6a and 6b. The range includes limits of tolerance for shafts and holes used in small high-precision work and horology.

The system provides for the use of either hole-basis or shaft-basis fits, and the Standard includes details of procedures for converting from one type of fit to the other.

The limits of tolerance for a shaft or hole are designated by the appropriate letter indicating the fundamental deviation, followed by a suffix number denoting the tolerance grade. This suffix number is the numerical part of the tolerance grade designation. Thus, a hole tolerance with deviation H and tolerance grade IT7 is designated H7. Likewise, a shaft with deviation p and tolerance grade IT6 is designated p6. The limits of size of a component feature are defined by the basic size, say, 45 mm, followed by the appropriate tolerance designation, for example, 45 H7 or 45 p6. A fit is indicated by combining the basic size common to both features with the designation appropriate to each of them, for example, 45 H7-p6 or 45 H7/p6.

When calculating the limits of size for a shaft, the upper deviation es, or the lower deviation ei, is first obtained from Tables 5a or 5b, depending on the particular letter designation, and nominal dimension. If an upper deviation has been determined, the lower deviation ei = es − IT. The IT value is obtained from Table 4 for the particular tolerance grade being applied. If a lower deviation has been obtained from Tables 5a or 5b, the upper deviation es = ei + IT. When the upper deviation ES has been determined for a hole from Tables 6a or 6b, the lower deviation EI = ES − IT. If a lower deviation EI has been obtained from Table 6a, then the upper deviation ES = EI + IT.

The upper deviations for holes K, M, and N with tolerance grades up to and including IT8, and for holes P to ZC with tolerance grades up to and including IT7 must be calculated by adding the delta (Δ) values given in Table 6b as indicated.

Example 1: The limits of size for a part of 133 mm basic size with a tolerance designation g9 are derived as follows:

From Table 5a, the upper deviation (es) is − 0.014 mm. From Table 4, the tolerance grade (IT9) is 0.100 mm. The lower deviation (ei) = es − IT = 0.114 mm, and the limits of size are thus 132.986 and 132.886 mm.

Example 2: The limits of size for a part 20 mm in size, with tolerance designation D3, are derived as follows: From Table 6a, the lower deviation (EI) is + 0.065 mm. From Table 4, the tolerance grade (IT3) is 0.004 mm. The upper deviation (ES) = EI + IT = 0.069 mm, and thus the limits of size for the part are 20.069 and 20.065 mm.

Example 3: The limits of size for a part 32 mm in size, with tolerance designation M5, which involves a delta value, are obtained as follows: From Table 6a, the upper deviation ES is − 0.009 mm + Δ = −0.005 mm. (The delta value given at the end of Table 6b for this size and grade IT5 is 0.004 mm.) From Table 4, the tolerance grade (IT5) is 0.011 mm. The lower deviation (EI) = ES − IT = − 0.016 mm, and thus the limits of size for the part are 31.995 and 31.984 mm.

Where the designations h and H or j_s and J_s are used, it is only necessary to refer to Table 4. For h and H, the fundamental deviation is always zero, and the disposition of the tolerance is always negative (−) for a shaft, and positive (+) for a hole.

Example 4: The limits for a part 40 mm in size, designated h8 are derived as follows: From Table 4, the tolerance grade (IT8) is 0.039 mm, and the limits are therefore 40.000 and 39.961 mm.

Example 5: The limits for a part 60 mm in size, designated j_s7 or J_s7 are derived as follows: From Table 4, the tolerance grade (IT7) is 0.030 mm, and this value is divided equally about the basic size to give limits of 60.015 and 59.985 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. British Standard Limits of Tolerance for Selected Holes (Upper and Lower Deviations) *BS 4500:1969*

Nominal Sizes, mm		H7		H8		H9		H11	
Over	Up to and Including	ES +	EI	ES +	EI	ES +	EI	ES +	EI
…	3	10	0	14	0	25	0	60	0
3	6	12	0	18	0	30	0	75	0
6	10	15	0	22	0	36	0	90	0
10	18	18	0	27	0	43	0	110	0
18	30	21	0	33	0	52	0	130	0
30	50	25	0	39	0	62	0	160	0
50	80	30	0	46	0	74	0	190	0
80	120	35	0	54	0	87	0	220	0
120	180	40	0	63	0	100	0	250	0
180	250	46	0	72	0	115	0	290	0
250	315	52	0	81	0	130	0	320	0
315	400	57	0	89	0	140	0	360	0
400	500	63	0	97	0	155	0	400	0

ES = Upper deviation, EI = Lower deviation.

The dimensions are given in 0.001 mm, except for the nominal sizes, which are in millimeters.

Table 2. British Standard Limits of Tolerance for Selected Shafts (Upper and Lower Deviations) *BS 4500:1969*

Nominal Sizes, mm		c11		d10		e9		f7		g6		h6		k6		n6		p6		s6	
Over	Up to and Incl.	es −	ei −	es −	ei −	es −	ei −	es −	ei −	es −	ei −	es −	ei −	es +	ei +	es +	ei +	es +	ei +	es +	ei +
…	3	60	120	20	60	14	39	6	16	2	8	0	6	6	0	10	4	12	6	20	14
3	6	70	145	30	78	20	50	10	22	4	12	0	8	9	1	16	8	20	12	27	19
6	10	80	170	40	98	25	61	13	28	5	14	0	9	10	1	19	10	24	15	32	23
10	18	95	205	50	120	32	75	16	34	6	17	0	11	12	1	23	12	29	18	39	28
18	30	110	240	65	149	40	92	20	41	7	20	0	13	15	2	28	15	35	22	48	35
30	40	120	280	80	180	50	112	25	50	9	25	0	16	18	2	33	17	42	26	59	43
40	50	130	290	80	180	50	112	25	50	9	25	0	16	18	2	33	17	42	26	59	43
50	65	140	330	100	220	60	134	30	60	10	29	0	19	21	2	39	20	51	32	72	53
65	80	150	340	100	220	60	134	30	60	10	29	0	19	21	2	39	20	51	32	78	59
80	100	170	390	120	260	72	159	36	71	12	34	0	22	25	3	45	23	59	37	93	71
100	120	180	400	120	260	72	159	36	71	12	34	0	22	25	3	45	23	59	37	101	79
120	140	200	450	145	305	85	185	43	83	14	39	0	25	28	3	52	27	68	43	117	92
140	160	210	460	145	305	85	185	43	83	14	39	0	25	28	3	52	27	68	43	125	100
160	180	230	480	145	305	85	185	43	83	14	39	0	25	28	3	52	27	68	43	133	108
180	200	240	530	170	355	100	215	50	96	15	44	0	29	33	4	60	31	79	50	151	122
200	225	260	550	170	355	100	215	50	96	15	44	0	29	33	4	60	31	79	50	159	130
225	250	280	570	170	355	100	215	50	96	15	44	0	29	33	4	60	31	79	50	169	140
250	280	300	620	190	400	110	240	56	108	17	49	0	32	36	4	66	34	88	56	190	158
280	315	330	650	190	400	110	240	56	108	17	49	0	32	36	4	66	34	88	56	202	170
315	355	360	720	210	440	125	265	62	119	18	54	0	36	40	4	73	37	98	62	226	190
355	400	400	760	210	440	125	265	62	119	18	54	0	36	40	4	73	37	98	62	244	208
400	450	440	840	230	480	135	290	68	131	20	60	0	40	45	5	80	40	108	68	272	232
450	500	480	880	230	480	135	290	68	131	20	60	0	40	45	5	80	40	108	68	292	252

es = Upper deviation, ei = Lower deviation.

The dimensions are given in 0.001 mm, except for the nominal sizes, which are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. British Standard Selected Fits, Minimum and Maximum Clearances *BS 4500:1969*

Nominal Sizes, mm		H11—c11		H9—d10		H9—e9		H8—f7		H7—g6		H7—h6		H7—k6		H7—n6		H7—p6		H7—s6	
Over	Up to and Incl.	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
…	3	60	180	20	85	14	64	6	30	2	18	0	16	−6	+10	−10	+6	−12	+4	−20	−4
3	6	70	220	30	108	20	80	10	40	4	24	0	20	−9	+11	−16	+4	−20	0	−27	−7
6	10	80	260	40	134	25	97	13	50	5	29	0	24	−10	+14	−19	+5	−24	0	−32	−8
10	18	95	315	50	163	32	118	16	61	6	35	0	29	−12	+17	−23	+6	−29	0	−39	−10
18	30	110	370	65	201	40	144	20	74	7	41	0	34	−15	+19	−28	+6	−35	−1	−48	−14
30	40	120	440	80	242	50	174	25	89	9	50	0	41	−18	+23	−33	+8	−42	−1	−59	−18
40	50	130	450	80	242	50	174	25	89	9	50	0	41	−18	+23	−33	+8	−42	−1	−59	−18
50	65	140	520	100	294	60	208	30	106	10	59	0	49	−21	+28	−39	+10	−51	−2	−72	−23
65	80	150	530	100	294	60	208	30	106	10	59	0	49	−21	+28	−39	+10	−51	−2	−78	−29
80	100	170	610	120	347	72	246	36	125	12	69	0	57	−25	+32	−45	+12	−59	−2	−93	−36
100	120	180	620	120	347	72	246	36	125	12	69	0	57	−25	+32	−45	+12	−59	−2	−101	−44
120	140	200	700	145	405	85	285	43	146	14	79	0	65	−28	+37	−52	+13	−68	−3	−117	−52
140	160	210	710	145	405	85	285	43	146	14	79	0	65	−28	+37	−52	+13	−68	−3	−125	−60
160	180	230	730	145	405	85	285	43	146	14	79	0	65	−28	+37	−52	+13	−68	−3	−133	−68
180	200	240	820	170	470	100	330	50	168	15	90	0	75	−33	+42	−60	+15	−79	−4	−151	−76
200	225	260	840	170	470	100	330	50	168	15	90	0	75	−33	+42	−60	+15	−79	−4	−159	−84
225	250	280	860	170	470	100	330	50	168	15	90	0	75	−33	+42	−60	+15	−79	−4	−169	−94
250	280	300	940	190	530	110	370	56	189	17	101	0	84	−36	+48	−66	+18	−88	−4	−190	−126
280	315	330	970	190	530	110	370	56	189	17	101	0	84	−36	+48	−66	+18	−88	−4	−202	−112
315	355	360	1080	210	580	125	405	62	208	18	111	0	93	−40	−53	−73	+20	−98	−5	−226	−133
355	400	400	1120	210	580	125	405	62	208	18	111	0	93	−40	−53	−73	+20	−98	−5	−244	−151
400	450	440	1240	230	635	135	445	68	228	20	123	0	103	−45	+58	−80	+23	−108	−5	−272	−169
450	500	480	1280	230	635	135	445	68	228	20	123	0	103	−45	+58	−80	+23	−108	−5	−292	−189

The dimensions are given in 0.001 mm, except for the nominal sizes, which are in millimeters.

Minus (−) sign indicates negative clearance, i.e., interference.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. British Standard Limits and Fits *BS 4500:1969*

Nominal Sizes, mm		Tolerance Grades																	
Over	To	IT 01	IT 0	IT 1	IT 2	IT 3	IT 4	IT 5	IT 6	IT 7	IT 8	IT 9	IT 10	IT 11	IT 12	IT 13	IT 14[a]	IT 15[a]	IT 16[a]
…	3	0.3	0.5	0.8	1.2	2	3	4	6	10	14	25	40	60	100	140	250	400	600
3	6	0.4	0.6	1	1.5	2.5	4	5	8	12	18	30	48	75	120	180	300	480	750
6	10	0.4	0.6	1	1.5	2.5	4	6	9	15	22	36	58	90	150	220	360	580	900
10	18	0.5	0.8	1.2	2	3	5	8	11	18	27	43	70	110	180	270	430	700	1100
18	30	0.6	1	1.5	2.5	4	6	9	13	21	33	52	84	130	210	330	520	840	1300
30	50	0.6	1	1.5	2.5	4	7	11	16	25	39	62	100	160	250	390	620	1000	1600
50	80	0.8	1.2	2	3	5	8	13	19	30	46	74	120	190	300	460	740	1200	1900
80	120	1	1.5	2.5	4	6	10	15	22	35	54	87	140	220	350	540	870	1400	2200
120	180	1.2	2	3.5	5	8	12	18	25	40	63	100	160	250	400	630	1000	1600	2500
180	250	2	3	4.5	7	10	14	20	29	46	72	115	185	290	460	720	1150	1850	2900
250	315	2.5	4	6	8	12	16	23	32	52	81	130	210	320	520	810	1300	2100	3200
315	400	3	5	7	9	13	18	25	36	57	89	140	230	360	570	890	1400	2300	3600
400	500	4	6	8	10	15	20	27	40	63	97	155	250	400	630	970	1550	2500	4000

[a] Not applicable to sizes below 1 mm.

The dimensions are given in 0.001 mm, except for the nominal sizes which are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5a. British Standard Fundamental Deviations for Shafts *BS 4500:1969*

Nominal Sizes, mm		Grade																
		01 to 16												5–6	7	8	4–7	≤3 >7
		Fundamental (Upper) Deviation es												Fundamental (Lower) Deviation ei				
Over	To	a[a]	b[a]	c	cd	d	e	ef	f	fg	g	h	js[b]	j			k	
…	3	−270	−140	−60	−34	−20	−14	−10	−6	−4	−2	0		−2	−4	−6	0	0
3	6	−270	−140	−70	−46	−30	−20	−14	−10	−6	−4	0		−2	−4	…	+1	0
6	10	−280	−150	−80	−56	−40	−25	−18	−13	−8	−5	0		−2	−5	…	+1	0
10	14	−290	−150	−95	…	−50	−32	…	−16	…	−6	0		−3	−6	…	+1	0
14	18	−290	−150	−95	…	−50	−32	…	−16	…	−6	0		−3	−6	…	+1	0
18	24	−300	−160	−110	…	−65	−40	…	−20	…	−7	0		−4	−8	…	+2	0
24	30	−300	−160	−110	…	−65	−40	…	−20	…	−7	0		−4	−8	…	+2	0
30	40	−310	−170	−120	…	−80	−50	…	−25	…	−9	0		−5	−10	…	+2	0
40	50	−320	−180	−130	…	−80	−50	…	−25	…	−9	0		−5	−10	…	+2	0
50	65	−340	−190	−140	…	−100	−60	…	−30	…	−10	0		−7	−12	…	+2	0
65	80	−360	−200	−150	…	−100	−60	…	−30	…	−10	0		−7	−12	…	+2	0
80	100	−380	−220	−170	…	−120	−72	…	−36	…	−12	0		−9	−15	…	+3	0
100	120	−410	−240	−180	…	−120	−72	…	−36	…	−12	0	±IT/2	−9	−15	…	+3	0
120	140	−460	−260	−200	…	−145	−85	…	−43	…	−14	0		−11	−18	…	+3	0
140	160	−520	−280	−210	…	−145	−85	…	−43	…	−14	0		−11	−18	…	+3	0
160	180	−580	−310	−230	…	−145	−85	…	−43	…	−14	0		−11	−18	…	+3	0
180	200	−660	−340	−240	…	−170	−100	…	−50	…	−15	0		−13	−21	…	+4	0
200	225	−740	−380	−260	…	−170	−100	…	−50	…	−15	0		−13	−21	…	+4	0
225	250	−820	−420	−280	…	−170	−100	…	−50	…	−15	0		−13	−21	…	+4	0
250	280	−920	−480	−300	…	−190	−110	…	−56	…	−17	0		−16	−26	…	+4	0
280	315	−1050	−540	−330	…	−190	−110	…	−56	…	−17	0		−16	−26	…	+4	0
315	355	−1200	−600	−360	…	−210	−125	…	−62	…	−18	0		−18	−28	…	+4	0
355	400	−1350	−680	−400	…	−210	−125	…	−62	…	−18	0		−18	−28	…	+4	0
400	450	−1500	−760	−440	…	−230	−135	…	−68	…	−20	0		−20	−32	…	+5	0
450	500	−1650	−840	−480	…	−230	−135	…	−68	…	−20	0		−20	−32	…	+5	0

[a] Not applicable to sizes up to 1 mm.

[b] In grades 7 to 11, the two symmetrical deviations ±IT/2 should be rounded if the IT value in micrometers is an odd value by replacing it with the even value immediately below. For example, if IT = 175, replace it by 174.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5b. British Standard Fundamental Deviations for Shafts *BS 4500:1969*

Nominal Sizes, mm		Grade													
		01 to 16													
		Fundamental (Lower) Deviation ei													
Over	To	m	n	p	r	s	t	u	v	x	y	z	za	zb	zc
…	3	+2	+4	+6	+10	+14	…	+18	…	+20	…	+26	+32	+40	+60
3	6	+4	+8	+12	+15	+19	…	+23	…	+28	…	+35	+42	+50	+80
6	10	+6	+10	+15	+19	+23	…	+28	…	+34	…	+42	+52	+67	+97
10	14	+7	+12	+18	+23	+28	…	+33	…	+40	…	+50	+64	+90	+130
14	18	+7	+12	+18	+23	+28	…	+33	+39	+45	…	+60	+77	+108	+150
18	24	+8	+15	+22	+28	+35	…	+41	+47	+54	+63	+73	+98	+136	+188
24	30	+8	+15	+22	+28	+35	+41	+48	+55	+64	+75	+88	+118	+160	+218
30	40	+9	+17	+26	+34	+43	+48	+60	+68	+80	+94	+112	+148	+200	+274
40	50	+9	+17	+26	+34	+43	+54	+70	+81	+97	+114	+136	+180	+242	+325
50	65	+11	+20	+32	+41	+53	+66	+87	+102	+122	+144	+172	+226	+300	+405
65	80	+11	+20	+32	+43	+59	+75	+102	+120	+146	+174	+210	+274	+360	+480
80	100	+13	+23	+37	+51	+71	+91	+124	+146	+178	+214	+258	+335	+445	+585
100	120	+13	+23	+37	+54	+79	+104	+144	+172	+210	+254	+310	+400	+525	+690
120	140	+15	+27	+43	+63	+92	+122	+170	+202	+248	+300	+365	+470	+620	+800
140	160	+15	+27	+43	+65	+100	+134	+190	+228	+280	+340	+415	+535	+700	+900
160	180	+15	+27	+43	+68	+108	+146	+210	+252	+310	+380	+465	+600	+780	+1000
180	200	+17	+31	+50	+77	+122	+166	+236	+284	+350	+425	+520	+670	+880	+1150
200	225	+17	+31	+50	+80	+130	+180	+258	+310	+385	+470	+575	+740	+960	+1250
225	250	+17	+31	+50	+84	+140	+196	+284	+340	+425	+520	+640	+820	+1050	+1350
250	280	+20	+34	+56	+94	+158	+218	+315	+385	+475	+580	+710	+920	+1200	+1550
280	315	+20	+34	+56	+98	+170	+240	+350	+425	+525	+650	+790	+1000	+1300	+1700
315	355	+21	+37	+62	+108	+190	+268	+390	+475	+590	+730	+900	+1150	+1500	+1900
355	400	+21	+37	+62	+114	+208	+294	+435	+530	+660	+820	+1000	+1300	+1650	+2100
400	450	+23	+40	+68	+126	+232	+330	+490	+595	+740	+920	+1100	+1450	+1850	+2400
450	500	+23	+40	+68	+132	+252	+360	+540	+660	+820	+1000	+1250	+1600	+2100	+2600

The dimensions are in 0.001 mm, except the nominal sizes, which are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6a. British Standard Fundamental Deviations for Holes *BS 4500:1969*

Nominal Sizes, mm		Grade																				
		01 to 16											6	7	8	≤8	>8	≤8[a]	>8	≤8	>8[b]
		Fundamental (Lower) Deviation EI											Fundamental (Upper) Deviation ES								
Over	To	A[b]	B[b]	C	CD	D	E	EF	F	FG	G	H	Js[c]	J			K[d]		M[d]		N[d]	
…	3	+270	+140	+60	+34	+20	+14	+10	+6	+4	+2	0		+2	+4	+6	0	0	−2	−2	−4	−4
3	6	+270	+140	+70	+46	+30	+20	+14	+10	+6	+4	0		+5	+6	+10	−1+Δ	…	−4+Δ	−4	−8+Δ	0
6	10	+280	+150	+80	+56	+40	+25	+18	+13	+8	+5	0		+5	+8	+12	−1+Δ	…	−6+Δ	−6	−10+Δ	0
10	14	+290	+150	+95	…	+50	+32	…	+16	…	+6	0		+6	+10	+15	−1+Δ	…	−7+Δ	−7	−12+Δ	0
14	18	+290	+150	+95	…	+50	+32	…	+16	…	+6	0		+6	+10	+15	−1+Δ	…	−7+Δ	−7	−12+Δ	0
18	24	+300	+160	+110	…	+65	+40	…	+20	…	+7	0		+8	+12	+20	−2+Δ	…	−8+Δ	−8	−15+Δ	0
24	30	+300	+160	+110	…	+65	+40	…	+20	…	+7	0		+8	+12	+20	−2+Δ	…	−8+Δ	−8	−15+Δ	0
30	40	+310	+170	+120	…	+80	+50	…	+25	…	+9	0		+10	+14	+24	−2+Δ	…	−9+Δ	−9	−17+Δ	0
40	50	+320	+180	+130	…	+80	+50	…	+25	…	+9	0		+10	+14	+24	−2+Δ	…	−9+Δ	−9	−17+Δ	0
50	65	+340	+190	+140	…	+100	+60	…	+30	…	+10	0		+13	+18	+28	−2+Δ	…	−11+Δ	−11	−20+Δ	0
65	80	+360	+200	+150	…	+100	+60	…	+30	…	+10	0		+13	+18	+28	−2+Δ	…	−11+Δ	−11	−20+Δ	0
80	100	+380	+220	+170	…	+120	+72	…	+36	…	+12	0		+16	+22	+34	−3+Δ	…	−13+Δ	−13	−23+Δ	0
100	120	+410	+240	+180	…	+120	+72	…	+36	…	+12	0	±IT/2	+16	+22	+34	−3+Δ	…	−13+Δ	−13	−23+Δ	0
120	140	+460	+260	+200	…	+145	+85	…	+43	…	+14	0		+18	+26	+41	−3+Δ	…	−15+Δ	−15	−27+Δ	0
140	160	+520	+280	+210	…	+145	+85	…	+43	…	+14	0		+18	+26	+41	−3+Δ	…	−15+Δ	−15	−27+Δ	0
160	180	+580	+310	+230	…	+145	+85	…	+43	…	+14	0		+18	+26	+41	−3+Δ	…	−15+Δ	−15	−27+Δ	0
180	200	+660	+340	+240	…	+170	+100	…	+50	…	+15	0		+22	+30	+47	−4+Δ	…	−17+Δ	−17	−31+Δ	0
200	225	+740	+380	+260	…	+170	+100	…	+50	…	+15	0		+22	+30	+47	−4+Δ	…	−17−Δ	−17	−31+Δ	0
225	250	+820	+420	+280	…	+170	+100	…	+50	…	+15	0		+22	+30	+47	−4+Δ	…	−17+Δ	−17	−31+Δ	0
250	280	+920	+480	+300	…	+190	+110	…	+56	…	+17	0		+25	+36	+55	−4+Δ	…	−20+Δ	−20	−34+Δ	0
280	315	+1050	+540	+330	…	+190	+110	…	+56	…	+17	0		+25	+36	+55	−4+Δ	…	−20+Δ	−20	−34+Δ	0
315	355	+1200	+600	+360	…	+210	+125	…	+62	…	+18	0		+29	+39	+60	−4+Δ	…	−21+Δ	−21	−37+Δ	0
355	400	+1350	+680	+400	…	+210	+125	…	+62	…	+18	0		+29	+39	+60	−4+Δ	…	−21+Δ	−21	−37+Δ	0
400	450	+1500	+760	+440	…	+230	+135	…	+68	…	+20	0		+33	+43	+66	−5+4	…	−23+Δ	−23	−40+Δ	0
450	500	+1650	+840	+480	…	+230	+135	…	+68	…	+20	0		+33	+43	+66	−5+4	…	−23+Δ	−23	−40+Δ	0

[a] Special case: for M6, ES = −9 for sizes from 250 to 315 mm, instead of −11.

[b] Not applicable to sizes up to 1 mm.

[c] In grades 7 to 11, the two symmetrical deviations ±IT/2 should be rounded if the IT value in micrometers is an odd value, by replacing it with the even value below. For example, if IT = 175, replace it by 174.

[d] When calculating deviations for holes K, M, and N with tolerance grades up to and including IT8, and holes F to ZC with tolerance grades up to and including IT7, the delta (Δ) values are added to the upper deviation ES. For example, for 25 P7, ES = −0.022 + 0.008 = −0.014 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6b. British Standard Fundamental Deviations for Holes *BS 4500:1969*

Nominal Sizes, mm		Grade													Values for delta (Δ)[d]					
		≤7	>7																	
		Fundamental (Upper) Deviation ES													Grade					
Over	To	P to ZC	P	R	S	T	U	V	X	Y	Z	ZA	ZB	ZC	3	4	5	6	7	8
…	3		− 6	−10	−14	…	−18	…	−20	…	−26	−32	−40	−60	0	0	0	0	0	0
3	6		−12	−15	−19	…	−23	…	−28	…	−35	−42	−50	−80	1	1.5	1	3	4	6
6	10		−15	−19	−23	…	−28	…	−34	…	−42	−52	−67	−97	1	1.5	2	3	6	7
10	14		−18	−23	−28	…	−33	…	−40	…	−50	−64	−90	−130	1	2	3	3	7	9
14	18		−18	−23	−28	…	−33	−39	−45	…	−60	−77	−108	−150	1	2	3	3	7	9
18	24		−22	−28	−35	…	−41	−47	−54	−63	−73	−98	−136	−188	1.5	2	3	4	8	12
24	30		−22	−28	−35	−41	−48	−55	−64	−75	−88	−118	−160	−218	1.5	2	3	4	8	12
30	40		−26	−34	−43	−48	−60	−68	−80	−94	−112	−148	−200	−274	1.5	3	4	5	9	14
40	50		−26	−34	−43	−54	−70	−81	−97	−114	−136	−180	−242	−325	1.5	3	4	5	9	14
50	65		−32	−41	−53	−66	−87	−102	−122	−144	−172	−226	−300	−405	2	3	5	6	11	16
65	80	Same deviation as for grades above 7 increased by Δ	−32	−43	−59	−75	−102	−120	−146	−174	−210	−274	−360	−480	2	3	5	6	11	16
80	100		−37	−51	−71	−91	−124	−146	−178	−214	−258	−335	−445	−585	2	4	5	7	13	19
100	120		−37	−54	−79	−104	−144	−172	−210	−254	−310	−400	−525	−690	2	4	5	7	13	19
120	140		−43	−63	−92	−122	−170	−202	−248	−300	−365	−470	−620	−800	3	4	6	7	15	23
140	160		−43	−65	−100	−134	−190	−228	−280	−340	−415	−535	−700	−900	3	4	6	7	15	23
160	180		−43	−68	−108	−146	−210	−252	−310	−380	−465	−600	−780	−1000	3	4	6	7	15	23
180	200		−50	−77	−122	−166	−226	−284	−350	−425	−520	−670	−880	−1150	3	4	6	9	17	26
200	225		−50	−80	−130	−180	−258	−310	−385	−470	−575	−740	−960	−1250	3	4	6	9	17	26
225	250		−50	−84	−140	−196	−284	−340	−425	−520	−640	−820	−1050	−1350	3	4	6	9	17	26
250	280		−56	−94	−158	−218	−315	−385	−475	−580	−710	−920	−1200	−1550	4	4	7	9	20	29
280	315		−56	−98	−170	−240	−350	−425	−525	−650	−790	−1000	−1300	−1700	4	4	7	9	20	29
315	355		−62	−108	−190	−268	−390	−475	−590	−730	−900	−1150	−1500	−1800	4	5	7	11	21	32
355	400		−62	−114	−208	−294	−435	−530	−660	−820	−1000	−1300	−1650	−2100	4	5	7	11	21	32
400	450		−68	−126	−232	−330	−490	−595	−740	−920	−1100	−1450	−1850	−2400	5	5	7	13	23	34
450	500		−68	−132	−252	−360	−540	−660	−820	−1000	−1250	−1600	−2100	−2600	5	5	7	13	23	34

The dimensions are given in 0.001 mm, except the nominal sizes, which are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Preferred Numbers

Preferred numbers are series of numbers selected to be used for standardization purposes in preference to any other numbers. Their use will lead to simplified practice and they should be employed whenever possible for individual standard sizes and ratings, or for a series, in applications similar to the following:

1) Important or characteristic linear dimensions, such as diameters and lengths, areas, volume, weights, capacities.

2) Ratings of machinery and apparatus in horsepower, kilowatts, kilovolt-amperes, voltages, currents, speeds, power-factors, pressures, heat units, temperatures, gas or liquid-flow units, weight-handling capacities, etc.

3) Characteristic ratios of figures for all kinds of units.

American National Standard for Preferred Numbers.— This ANSI Standard Z17.1-1973 covers basic series of preferred numbers which are independent of any measurement system and therefore can be used with metric or customary units.

The numbers are rounded values of the following five geometric series of numbers: $10^{N/5}$, $10^{N/10}$, $10^{N/20}$, $10^{N/40}$, and $10^{N/80}$, where N is an integer in the series 0, 1, 2, 3, etc. The designations used for the five series are respectively R5, R10, R20, R40, and R80, where R stands for Renard (Charles Renard, originator of the first preferred number system) and the number indicates the root of 10 on which the particular series is based.

The R5 series gives 5 numbers approximately 60 per cent apart, the R10 series gives 10 numbers approximately 25 per cent apart, the R20 series gives 20 numbers approximately 12 per cent apart, the R40 series gives 40 numbers approximately 6 per cent apart, and the R80 series gives 80 numbers approximately 3 per cent apart. The number of sizes for a given purpose can be minimized by using first the R5 series and adding sizes from the R10 and R20 series as needed. The R40 and R80 series are used principally for expressing tolerances in sizes based on preferred numbers. Preferred numbers below 1 are formed by dividing the given numbers by 10, 100, etc., and numbers above 10 are obtained by multiplying the given numbers by 10, 100, etc. Sizes graded according to the system may not be exactly proportional to one another due to the fact that preferred numbers may differ from calculated values by +1.26 per cent to −1.01 per cent. Deviations from preferred numbers are used in some instances — for example, where whole numbers are needed, such as 32 instead of 31.5 for the number of teeth in a gear.

Basic Series of Preferred Numbers *ANSI Z17.1-1973*

Series Designation								
R5	R10	R20	R40	R40	R80	R80	R80	R80
Preferred Numbers								
1.00	1.00	1.00	1.00	3.15	1.00	1.80	3.15	5.60
1.60	1.25	1.12	1.06	3.35	1.03	1.85	3.25	5.80
2.50	1.60	1.25	1.12	3.55	1.06	1.90	3.35	6.00
4.00	2.00	1.40	1.18	3.75	1.09	1.95	3.45	6.15
6.30	2.50	1.60	1.25	4.00	1.12	2.00	3.55	6.30
…	3.15	1.80	1.32	4.25	1.15	2.06	3.65	6.50
…	4.00	2.00	1.40	4.50	1.18	2.12	3.75	6.70
…	5.00	2.24	1.50	4.75	1.22	2.18	3.87	6.90
…	6.30	2.50	1.60	5.00	1.25	2.24	4.00	7.10
…	8.00	2.80	1.70	5.30	1.28	2.30	4.12	7.30
…	…	3.15	1.80	5.60	1.32	2.36	4.25	7.50
…	…	3.55	1.90	6.00	1.36	2.43	4.37	7.75
…	…	4.00	2.00	6.30	1.40	2.50	4.50	8.00
…	…	4.50	2.12	6.70	1.45	2.58	4.62	8.25
…	…	5.00	2.24	7.10	1.50	2.65	4.75	8.50
…	…	5.60	2.36	7.50	1.55	2.72	4.87	8.75
…	…	6.30	2.50	8.00	1.60	2.80	5.00	9.00
…	…	7.10	2.65	8.50	1.65	2.90	5.15	9.25
…	…	8.00	2.80	9.00	1.70	3.00	5.20	9.50
…	…	9.00	3.00	9.50	1.75	3.07	5.45	9.75

Copyright 2004, Industrial Press, Inc., New York, NY

Preferred Metric Sizes.— American National Standard ANSI B32.4M-1980 (R1994), presents series of preferred metric sizes for round, square, rectangular, and hexagonal metal products. Table 1 gives preferred metric diameters from 1 to 320 millimeters for round metal products. Wherever possible, sizes should be selected from the Preferred Series shown in the table. A Second Preference series is also shown. A Third Preference Series not shown in the table is: 1.3, 2.1, 2.4, 2.6, 3.2, 3.8, 4.2, 4.8, 7.5, 8.5, 9.5, 36, 85, and 95.

Most of the Preferred Series of sizes are derived from the American National Standard "10 series" of preferred numbers (see *American National Standard for Preferred Numbers* on page 689). Most of the Second Preference Series are derived from the "20 series" of preferred numbers. Third Preference sizes are generally from the "40 series" of preferred numbers.

For preferred metric diameters less than 1 millimeter, preferred across flat metric sizes of square and hexagon metal products, preferred across flat metric sizes of rectangular metal products, and preferred metric lengths of metal products, reference should be made to the Standard.

Table 1. American National Standard Preferred Metric Sizes
ANSI B4.2-1978 (R1999)

Basic Size, mm		Basic Size, mm		Basic Size, mm		Basic Size, mm	
1st Choice	2nd Choice	1st Choice	2nd Choice	1st Choice	2nd Choice	1st Choice	2nd Choice
1	…	6	…	40	…	250	…
…	1.1	…	7	…	45	…	280
1.2	…	8	…	50	…	300	…
…	1.4	…	9	…	55	…	350
1.6	…	10	…	60	…	400	…
…	1.8	…	11	…	70	…	450
2	…	12	…	80	…	500	…
…	2.2	…	14	…	90	…	550
2.5	…	16	…	100	…	600	…
…	2.8	…	18	…	110	…	700
3	…	20	…	120	…	800	…
…	3.5	…	22	…	140	…	900
4	…	25	…	160	…	1000	…
…	4.5	…	28	…	180	…	…
5	…	30	…	200	…	…	…
…	5.5	…	35	…	220	…	…

British Standard Preferred Numbers and Preferred Sizes.— This British Standard, PD 6481:1977 1983, gives recommendations for the use of preferred numbers and preferred sizes for functional characteristics and dimensions of various products.

The preferred number system is internationally standardized in ISO 3. It is also referred to as the Renard, or R, series (see *American National Standard for Preferred Numbers*, on page 689).

The series in the preferred number system are geometric series, that is, there is a constant ratio between each figure and the succeeding one, within a decimal framework. Thus, the R5 series has five steps between 1 and 10, the R10 series has 10 steps between 1 and 10, the R20 series, 20 steps, and the R40 series, 40 steps, giving increases between steps of approximately 60, 25, 12, and 6 per cent, respectively.

The preferred size series have been developed from the preferred number series by rounding off the inconvenient numbers in the basic series and adjusting for linear measurement in millimeters. These series are shown in Table 2.

After taking all normal considerations into account, it is recommended that (a) for ranges of values of the primary *functional* characteristics (outputs and capacities) of a series of

Copyright 2004, Industrial Press, Inc., New York, NY

products, the preferred number series R5 to R40 (see page 689) should be used, and (b) whenever linear sizes are concerned, the preferred sizes as given in the following table should be used. The presentation of preferred sizes gives designers and users a logical selection and the benefits of rational variety reduction.

The second-choice size given should only be used when it is not possible to use the first choice, and the third choice should be applied only if a size from the second choice cannot be selected. With this procedure, common usage will tend to be concentrated on a limited range of sizes, and a contribution is thus made to variety reduction. However, the decision to use a particular size cannot be taken on the basis that one is first choice and the other not. Account must be taken of the effect on the design, the availability of tools, and other relevant factors.

Table 2. British Standard Preferred Sizes, *PD 6481: 1977 (1983)*

Choice			Choice			Choice			Choice			Choice			Choice		
1st	2nd	3rd	1st	2nd	3rd	1st	2nd	3rd	1st	2nd	3rd	1st	2nd	3rd	1st	2nd	3rd
1					5.2			23	65					122			188
	1.1			5.5				24			66		125		190		
1.2					5.8	25				68				128			192
		1.3	6					26	70			130				195	
	1.4				6.2		28			72				132			198
		1.5		6.5		30					74		135		200		
1.6					6.8		32		75					138			205
		1.7		7				34			76	140				210	
	1.8				7.5	35				78				142			215
		1.9	8					36	80				145		220		
2					8.5		38				82			148			225
		2.1		9		40				85		150				230	
	2.2				9.5		42				88			152			235
		2.4	10					44	90				155		240		
2.5				11		45					92			158			245
		2.6	12					46		95		160				250	
2.8					13		48				98			162			255
3				14		50			100				165		260		
		3.2			15		52				102			168			265
	3.5		16					54	105			170				270	
		3.8			17	55					108			172			275
4				18				56	110				175		280		
		4.2			19		58				112			178			285
	4.5		20			60				115		180				290	
		4.8			21		62				118			182			295
5				22				64	120				185		300		

For dimensions above 300, each series continues in a similar manner, i.e., the intervals between each series number are the same as between 200 and 300.

Copyright 2004, Industrial Press, Inc., New York, NY

MEASURING INSTRUMENTS AND INSPECTION METHODS

Verniers and Micrometers

Reading a Vernier.— A general rule for taking readings with a vernier scale is as follows: Note the number of inches and sub-divisions of an inch that the zero mark of the vernier scale has moved along the true scale, and then add to this reading as many thousandths, or hundredths, or whatever fractional part of an inch the vernier reads to, as there are spaces between the vernier zero and that line on the vernier which coincides with one on the true scale. For example, if the zero line of a vernier which reads to thousandths is slightly beyond the 0.5 inch division on the main or true scale, as shown in Fig. 1, and graduation line 10 on the vernier exactly coincides with one on the true scale, the reading is 0.5 + 0.010 or 0.510 inch. In order to determine the reading or fractional part of an inch that can be obtained by a vernier, multiply the denominator of the finest sub-division given on the true scale by the total number of divisions on the vernier. For example, if one inch on the true scale is divided into 40 parts or fortieths (as in Fig. 1), and the vernier into twenty-five parts, the vernier will read to thousandths of an inch, as $25 \times 40 = 1000$. Similarly, if there are sixteen divisions to the inch on the true scale and a total of eight on the vernier, the latter will enable readings to be taken within one-hundred-twenty-eighths of an inch, as $8 \times 16 = 128$.



Fig. 1.



Fig. 2.

If the vernier is on a protractor, note the whole number of degrees passed by the vernier zero mark and then count the spaces between the vernier zero and that line which coincides with a graduation on the protractor scale. If the vernier indicates angles within five minutes or one-twelfth degree (as in Fig. 2), the number of spaces multiplied by 5 will, of course, give the number of minutes to be added to the whole number of degrees. The reading of the protractor set as illustrated would be 14 whole degrees (the number passed by the zero mark on the vernier) plus 30 minutes, as the graduation 30 on the vernier is the only one to

Copyright 2004, Industrial Press, Inc., New York, NY

the right of the vernier zero which exactly coincides with a line on the protractor scale. It will be noted that there are duplicate scales on the vernier, one being to the right and the other to the left of zero. The left-hand scale is used when the vernier zero is moved to the left of the zero of the protractor scale, whereas the right-hand graduations are used when the movement is to the right.

Reading a Metric Vernier.— The smallest graduation on the bar (true or main scale) of the metric vernier gage shown in Fig. 1, is 0.5 millimeter. The scale is numbered at each twentieth division, and thus increments of 10, 20, 30, 40 millimeters, etc., are indicated. There are 25 divisions on the vernier scale, occupying the same length as 24 divisions on the bar, which is 12 millimeters. Therefore, one division on the vernier scale equals one twenty-fifth of 12 millimeters = $0.04 \times 12 = 0.48$ millimeter. Thus, the difference between one bar division (0.50 mm) and one vernier division (2.48 mm) is $0.50 - 0.48 = 0.02$ millimeter, which is the minimum measuring increment that the gage provides. To permit direct readings, the vernier scale has graduations to represent tenths of a millimeter (0.1 mm) and fiftieths of a millimeter (0.02 mm).



Fig. 1.

To read a vernier gage, first note how many millimeters the zero line on the vernier is from the zero line on the bar. Next, find the graduation on the vernier scale which exactly coincides with a graduation line on the bar, and note the value of the vernier scale graduation. This value is added to the value obtained from the bar, and the result is the total reading.

In the example shown in Fig. 1, the vernier zero is just past the 40.5 millimeters graduation on the bar. The 0.18 millimeter line on the vernier coincides with a line on the bar, and the total reading is therefore $40.5 + 0.18 = 40.68$ mm.

Dual Metric-Inch Vernier.— The vernier gage shown in Fig. 2 has separate metric and inch 50-division vernier scales to permit measurements in either system.

A 50-division vernier has more widely spaced graduations than the 25-division vernier shown on the previous pages, and is thus easier to read. On the bar, the smallest metric graduation is 1 millimeter, and the 50 divisions of the vernier occupy the same length as 49 divisions on the bar, which is 49 mm. Therefore, one division on the vernier scale equals one-fiftieth of 49 millimeters = $0.02 \times 49 = 0.98$ mm. Thus, the difference between one bar division (1.0 mm) and one vernier division (0.98 mm) is 0.02 mm, which is the minimum measuring increment the gage provides.

The vernier scale is graduated for direct reading to 0.02 mm. In the figure, the vernier zero is just past the 27 mm graduation on the bar, and the 0.42 mm graduation on the vernier coincides with a line on the bar. The total reading is therefore 27.42 mm.

The smallest inch graduation on the bar is 0.05 inch, and the 50 vernier divisions occupy the same length as 49 bar divisions, which is 2.45 inches. Therefore, one vernier division

Copyright 2004, Industrial Press, Inc., New York, NY

equals one-fiftieth of 2.45 inches = 0.02 × 2.45 = 0.049 inch. Thus, the difference between the length of a bar division and a vernier division is 0.050-0.049 = 0.001 inch. The vernier scale is graduated for direct reading to 0.001 inch. In the example, the vernier zero is past the 1.05 graduation on the bar, and the 0.029 graduation on the vernier coincides with a line on the bar. Thus, the total reading is 1.079 inches.



Fig. 2.

Reading a Micrometer.— The spindle of an inch-system micrometer has 40 threads per inch, so that one turn moves the spindle axially 0.025 inch (1 ÷ 40 = 0.025), equal to the distance between two graduations on the frame. The 25 graduations on the thimble allow the 0.025 inch to be further divided, so that turning the thimble through one division moves the spindle axially 0.001 inch (0.025 ÷ 25 = 0.001). To read a micrometer, count the number of whole divisions that are visible on the scale of the frame, multiply this number by 25 (the number of thousandths of an inch that each division represents) and add to the product the number of that division on the thimble which coincides with the axial zero line on the frame. The result will be the diameter expressed in thousandths of an inch. As the numbers 1, 2, 3, etc., opposite every fourth sub-division on the frame, indicate hundreds of thousandths, the reading can easily be taken mentally. Suppose the thimble were screwed out so that graduation 2, and three additional sub-divisions, were visible (as shown in Fig. 3), and that graduation 10 on the thimble coincided with the axial line on the frame. The reading then would be 0.200 + 0.075 + 0.010, or 0.285 inch.



Fig. 3. Inch Micrometer



Fig. 4. Inch Micrometer with Vernier

Some micrometers have a vernier scale on the frame in addition to the regular graduations, so that measurements within 0.0001 part of an inch can be taken. Micrometers of this type are read as follows: First determine the number of thousandths, as with an ordinary micrometer, and then find a line on the vernier scale that exactly coincides with one on the thimble; the number of this line represents the number of ten-thousandths to be added to the number of thousandths obtained by the regular graduations. The reading shown in the illustration, Fig. 4, is 0.270 + 0.0003 = 0.2703 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Micrometers graduated according to the English system of measurement ordinarily have a table of decimal equivalents stamped on the sides of the frame, so that fractions such as sixty-fourths, thirty-seconds, etc., can readily be converted into decimals.

Reading a Metric Micrometer.— The spindle of an ordinary metric micrometer has 2 threads per millimeter, and thus one complete revolution moves the spindle through a distance of 0.5 millimeter. The longitudinal line on the frame is graduated with 1 millimeter divisions and 0.5 millimeter sub-divisions. The thimble has 50 graduations, each being 0.01 millimeter (one-hundredth of a millimeter).

To read a metric micrometer, note the number of millimeter divisions visible on the scale of the sleeve, and add the total to the particular division on the thimble which coincides with the axial line on the sleeve. Suppose that the thimble were screwed out so that graduation 5, and one additional 0.5 sub-division were visible (as shown in Fig. 5), and that graduation 28 on the thimble coincided with the axial line on the sleeve. The reading then would be 5.00 + 0.5 + 0.28 = 5.78 mm.

Some micrometers are provided with a vernier scale on the sleeve in addition to the regular graduations to permit measurements within 0.002 millimeter to be made. Micrometers of this type are read as follows: First determine the number of whole millimeters (if any) and the number of hundredths of a millimeter, as with an ordinary micrometer, and then find a line on the sleeve vernier scale which exactly coincides



Fig. 5. Metric Micrometer

with one on the thimble. The number of this coinciding vernier line represents the number of two-thousandths of a millimeter to be added to the reading already obtained. Thus, for example, a measurement of 2.958 millimeters would be obtained by reading 2.5 millimeters on the sleeve, adding 0.45 millimeter read from the thimble, and then adding 0.008 millimeter as determined by the vernier.

Note: 0.01 millimeter = 0.000393 inch, and 0.002 millimeter = 0.000078 inch (78 millionths). Therefore, metric micrometers provide smaller measuring increments than comparable inch unit micrometers—the smallest graduation of an ordinary inch reading micrometer is 0.001 inch; the vernier type has graduations down to 0.0001 inch. When using either a metric or inch micrometer, without a vernier, smaller readings than those graduated may of course be obtained by visual interpolation between graduations.

Sine-bar

The sine-bar is used either for very accurate angular measurements or for locating work at a given angle as, for example, in surface grinding templets, gages, etc. The sine-bar is especially useful in measuring or checking angles when the limit of accuracy is 5 minutes or less. Some bevel protractors are equipped with verniers which read to 5 minutes but the setting depends upon the alignment of graduations whereas a sine-bar usually is located by positive contact with precision gage-blocks selected for whatever dimension is required for obtaining a given angle.

Types of Sine-bars.— A sine-bar consists of a hardened, ground and lapped steel bar with very accurate cylindrical plugs of equal diameter attached to or near each end. The form illustrated by Fig. 3 has notched ends for receiving the cylindrical plugs so that they are held firmly against both faces of the notch. The standard center-to-center distance C between the plugs is either 5 or 10 inches. The upper and lower sides of sine-bars are parallel to the center line of the plugs within very close limits. The body of the sine-bar ordi-

Copyright 2004, Industrial Press, Inc., New York, NY

narily has several through holes to reduce the weight. In the making of the sine-bar shown in Fig. 4, if too much material is removed from one locating notch, regrinding the shoulder at the opposite end would make it possible to obtain the correct center distance. That is the reason for this change in form. The type of sine-bar illustrated by Fig. 5 has the cylindrical disks or plugs attached to one side. These differences in form or arrangement do not, of course, affect the principle governing the use of the sine-bar. An accurate surface plate or master flat is always used in conjunction with a sine-bar in order to form the base from which the vertical measurements are made.



Fig. 1.



Fig. 2.



Fig. 3.



Fig. 4.

Setting a Sine-bar to a Given Angle.— To find the vertical distance *H*, for setting a sine-bar to the required angle, convert the angle to decimal form on a pocket calculator, take the sine of that angle, and multiply by the distance between the cylinders. For example, if an angle of 31 degrees, 30 minutes is required, the equivalent angle is 31 degrees plus $^{30}/_{60} = 31 + 0.5$, or 31.5 degrees. (For conversions from minutes and seconds to decimals of degrees and vice versa, see page 96). The sine of 31.5 degrees is 0.5225 and multiplying this value by the sine-bar length gives 2.613 in. for the height *H*, Fig. 1 and 3, of the gage blocks.

Finding Angle when Height *H* of Sine-bar is Known.— To find the angle equivalent to a given height *H*, reverse the above procedure. Thus, if the height *H* is 1.4061 in., dividing by 5 gives a sine of 0.28122, which corresponds to an angle of 16.333 degrees, or 16 degrees 20 minutes.

Checking Angle of Templet or Gage by Using Sine-bar.— Place templet or gage on sine-bar as indicated by dotted lines, Fig. 1. Clamps may be used to hold work in place. Place upper end of sine-bar on gage blocks having total height *H* corresponding to the required angle. If upper edge *D* of work is parallel with surface plate *E*, then angle *A* of work equals angle *A* to which sine-bar is set. Parallelism between edge *D* and surface plate may be tested by checking the height at each end with a dial gage or some type of indicating comparator.

Measuring Angle of Templet or Gage with Sine-bar.— To measure such an angle, adjust height of gage blocks and sine-bar until edge *D*, Fig. 1, is parallel with surface plate *E*; then find angle corresponding to height *H*, of gage blocks. For example, if height *H* is

Copyright 2004, Industrial Press, Inc., New York, NY

2.5939 inches when *D* and *E* are parallel, the calculator will show that the angle *A* of the work is 31 degrees, 15 minutes.

Checking Taper per Foot with Sine-bar.— As an example, assume that the plug gage in Fig. 2 is supposed to have a taper of 6⅛ inches per foot and taper is to be checked by using a 5-inch sine-bar. The table of *Tapers per Foot and Corresponding Angles* on page 714 shows that the included angle for a taper of 6 ⅛ inches per foot is 28 degrees 38 minutes 1 second, or 28.6336 degrees from the calculator. For a 5-inch sine-bar, the calculator gives a value of 2.396 inch for the height *H* of the gage blocks. Using this height, if the upper surface *F* of the plug gage is parallel to the surface plate the angle corresponds to a taper of 6 ⅛ inches per foot.

Setting Sine-bar having Plugs Attached to Side.— If the lower plug does not rest directly on the surface plate, as in Fig. 3, the height *H* for the sine-bar is the difference between heights *x* and *y*, or the difference between the heights of the plugs; otherwise, the procedure in setting the sine-bar and checking angles is the same as previously described.

Checking Templets Having Two Angles.— Assume that angle *a* of templet, Fig. 4, is 9 degrees, angle *b* 12 degrees, and that edge *G* is parallel to the surface plate. For an angle *b* of 12 degrees, the calculator shows that the height *H* is 1.03956 inches. For an angle *a* of 9 degrees, the difference between measurements *x* and *y* when the sine-bar is in contact with the upper edge of the templet is 0.78217 inch.

Using Sine-bar Tables to Set 5-inch and 100-mm Sine-bars to Given Angle.— The table starting on page page 699 gives constants for a 5-inch sine-bar, and starting on page 706 are given constants for a 100-mm sine-bar. These constants represent the vertical height *H* for setting a sine-bar of the corresponding length to the required angle.

Using Sine-bar Tables with Sine-bars of Other Lengths.— A sine-bar may sometimes be preferred that is longer (or shorter) than that given in available tables because of its longer working surface or because the longer center distance is conducive to greater precision. To use the sine-bar tables with a sine-bar of another length to obtain the vertical distances *H*, multiply the value obtained from the table by the fraction (length of sine-bar used ÷ length of sine-bar specified in table).

Example: Use the 5-inch sine-bar table to obtain the vertical height *H* for setting a 10-inch sine-bar to an angle of 39°. The sine of 39 degrees is 0.62932, hence the vertical height *H* for setting a 10-inch sine-bar is 6.2932 inches.

Solution: The height H given for 39° in the 5-inch sine-bar table (page 703) is 3.14660. The corresponding height for a 10-inch sine-bar is $^{10}/_{5} \times 3.14660 = 6.2932$ inches.

Using a Calculator to Determine Sine-bar Constants for a Given Angle.— The constant required to set a given angle for a sine-bar of any length can be quickly determined by using a scientific calculator. The required formaulas are as follows:

a) angle *A* given in degrees and calculator is set to measure angles in radian

$$H = L \times \sin\left(A \times \frac{\pi}{180}\right)$$

or

a) angle *A* is given in radian, or
b) angle *A* is given in degrees and calculator is set to measure angles in degrees

$$H = L \times \sin(A)$$

where L = length of the sine-bar A = angle to which the sine-bar is to be set
H = vertical height to which one end of sine-bar must be set to obtain angle A
$\pi = 3.141592654$

In the previous formulas, the height *H* and length *L* must be given in the same units, but may be in either metric or US units. Thus, if *L* is given in mm, then *H* is in mm; and, if *L* is given in inches, then *H* is in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Measuring Tapers with Vee-block and Sine-bar.— The taper on a conical part may be checked or found by placing the part in a vee-block which rests on the surface of a sine-plate or sine-bar as shown in the accompanying diagram. The advantage of this method is that the axis of the vee-block may be aligned with the sides of the sine-bar. Thus when the tapered part is placed in the vee-block it will be aligned perpendicular to the transverse axis of the sine-bar.



The sine-bar is set to angle $B = (C + A/2)$ where $A/2$ is one-half the included angle of the tapered part. If D is the included angle of the precision vee-block, the angle C is calculated from the formula:

$$\sin C = \frac{\sin(A/2)}{\sin(D/2)}$$

If dial indicator readings show no change across all points along the top of the taper surface, then this checks that the angle A of the taper is correct.

If the indicator readings vary, proceed as follows to find the actual angle of taper: 1) Adjust the angle of the sine-bar until the indicator reading is constant. Then find the new angle B' as explained in the paragraph *Measuring Angle of Templet or Gage with Sine-bar* on page 696; and 2) Using the angle B' calculate the actual half-angle $A'/2$ of the taper from the formula:.

$$\tan\frac{A'}{2} = \frac{\sin B'}{\csc\frac{D}{2} + \cos B'}$$

The taper per foot corresponding to certain half-angles of taper may be found in the table on page 714.

Dimensioning Tapers.— At least three methods of dimensioning tapers are in use.

Standard Tapers: Give one diameter or width, the length, and insert note on drawing designating the taper by number.

Special Tapers: In dimensioning a taper when the slope is specified, the length and only one diameter should be given or the diameters at both ends of the taper should be given and length omitted.

Precision Work: In certain cases where very precise measurements are necessary the taper surface, either external or internal, is specified by giving a diameter at a certain distance from a surface and the slope of the taper.

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 5-inch Sine-bar

Constants for Setting a 5-inch Sine-bar for 1° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.00000	0.08726	0.17450	0.26168	0.34878	0.43578	0.52264	0.60935
1	0.00145	0.08872	0.17595	0.26313	0.35023	0.43723	0.52409	0.61079
2	0.00291	0.09017	0.17740	0.26458	0.35168	0.43868	0.52554	0.61223
3	0.00436	0.09162	0.17886	0.26604	0.35313	0.44013	0.52698	0.61368
4	0.00582	0.09308	0.18031	0.26749	0.35459	0.44157	0.52843	0.61512
5	0.00727	0.09453	0.18177	0.26894	0.35604	0.44302	0.52987	0.61656
6	0.00873	0.09599	0.18322	0.27039	0.35749	0.44447	0.53132	0.61801
7	0.01018	0.09744	0.18467	0.27185	0.35894	0.44592	0.53277	0.61945
8	0.01164	0.09890	0.18613	0.27330	0.36039	0.44737	0.53421	0.62089
9	0.01309	0.10035	0.18758	0.27475	0.36184	0.44882	0.53566	0.62234
10	0.01454	0.10180	0.18903	0.27620	0.36329	0.45027	0.53710	0.62378
11	0.01600	0.10326	0.19049	0.27766	0.36474	0.45171	0.53855	0.62522
12	0.01745	0.10471	0.19194	0.27911	0.36619	0.45316	0.54000	0.62667
13	0.01891	0.10617	0.19339	0.28056	0.36764	0.45461	0.54144	0.62811
14	0.02036	0.10762	0.19485	0.28201	0.36909	0.45606	0.54289	0.62955
15	0.02182	0.10907	0.19630	0.28346	0.37054	0.45751	0.54433	0.63099
16	0.02327	0.11053	0.19775	0.28492	0.37199	0.45896	0.54578	0.63244
17	0.02473	0.11198	0.19921	0.28637	0.37344	0.46040	0.54723	0.63388
18	0.02618	0.11344	0.20066	0.28782	0.37489	0.46185	0.54867	0.63532
19	0.02763	0.11489	0.20211	0.28927	0.37634	0.46330	0.55012	0.63677
20	0.02909	0.11634	0.20357	0.29072	0.37779	0.46475	0.55156	0.63821
21	0.03054	0.11780	0.20502	0.29218	0.37924	0.46620	0.55301	0.63965
22	0.03200	0.11925	0.20647	0.29363	0.38069	0.46765	0.55445	0.64109
23	0.03345	0.12071	0.20793	0.29508	0.38214	0.46909	0.55590	0.64254
24	0.03491	0.12216	0.20938	0.29653	0.38360	0.47054	0.55734	0.64398
25	0.03636	0.12361	0.21083	0.29798	0.38505	0.47199	0.55879	0.64542
26	0.03782	0.12507	0.21228	0.29944	0.38650	0.47344	0.56024	0.64686
27	0.03927	0.12652	0.21374	0.30089	0.38795	0.47489	0.56168	0.64830
28	0.04072	0.12798	0.21519	0.30234	0.38940	0.47633	0.56313	0.64975
29	0.04218	0.12943	0.21664	0.30379	0.39085	0.47778	0.56457	0.65119
30	0.04363	0.13088	0.21810	0.30524	0.39230	0.47923	0.56602	0.65263
31	0.04509	0.13234	0.21955	0.30669	0.39375	0.48068	0.56746	0.65407
32	0.04654	0.13379	0.22100	0.30815	0.39520	0.48212	0.56891	0.65551
33	0.04800	0.13525	0.22246	0.30960	0.39665	0.48357	0.57035	0.65696
34	0.04945	0.13670	0.22391	0.31105	0.39810	0.48502	0.57180	0.65840
35	0.05090	0.13815	0.22536	0.31250	0.39954	0.48647	0.57324	0.65984
36	0.05236	0.13961	0.22681	0.31395	0.40099	0.48791	0.57469	0.66128
37	0.05381	0.14106	0.22827	0.31540	0.40244	0.48936	0.57613	0.66272
38	0.05527	0.14252	0.22972	0.31686	0.40389	0.49081	0.57758	0.66417
39	0.05672	0.14397	0.23117	0.31831	0.40534	0.49226	0.57902	0.66561
40	0.05818	0.14542	0.23263	0.31976	0.40679	0.49370	0.58046	0.66705
41	0.05963	0.14688	0.23408	0.32121	0.40824	0.49515	0.58191	0.66849
42	0.06109	0.14833	0.23553	0.32266	0.40969	0.49660	0.58335	0.66993
43	0.06254	0.14979	0.23699	0.32411	0.41114	0.49805	0.58480	0.67137
44	0.06399	0.15124	0.23844	0.32556	0.41259	0.49949	0.58624	0.67281
45	0.06545	0.15269	0.23989	0.32702	0.41404	0.50094	0.58769	0.67425
46	0.06690	0.15415	0.24134	0.32847	0.41549	0.50239	0.58913	0.67570
47	0.06836	0.15560	0.24280	0.32992	0.41694	0.50383	0.59058	0.67714
48	0.06981	0.15705	0.24425	0.33137	0.41839	0.50528	0.59202	0.67858
49	0.07127	0.15851	0.24570	0.33282	0.41984	0.50673	0.59346	0.68002
50	0.07272	0.15996	0.24715	0.33427	0.42129	0.50818	0.59491	0.68146
51	0.07417	0.16141	0.24861	0.33572	0.42274	0.50962	0.59635	0.68290
52	0.07563	0.16287	0.25006	0.33717	0.42419	0.51107	0.59780	0.68434
53	0.07708	0.16432	0.25151	0.33863	0.42564	0.51252	0.59924	0.68578
54	0.07854	0.16578	0.25296	0.34008	0.42708	0.51396	0.60068	0.68722
55	0.07999	0.16723	0.25442	0.34153	0.42853	0.51541	0.60213	0.68866
56	0.08145	0.16868	0.25587	0.34298	0.42998	0.51686	0.60357	0.69010
57	0.08290	0.17014	0.25732	0.34443	0.43143	0.51830	0.60502	0.69154
58	0.08435	0.17159	0.25877	0.34588	0.43288	0.51975	0.60646	0.69298
59	0.08581	0.17304	0.26023	0.34733	0.43433	0.52120	0.60790	0.69443
60	0.08726	0.17450	0.26168	0.34878	0.43578	0.52264	0.60935	0.69587

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	0.69587	0.78217	0.86824	0.95404	1.03956	1.12476	1.20961	1.29410
1	0.69731	0.78361	0.86967	0.95547	1.04098	1.12617	1.21102	1.29550
2	0.69875	0.78505	0.87111	0.95690	1.04240	1.12759	1.21243	1.29690
3	0.70019	0.78648	0.87254	0.95833	1.04383	1.12901	1.21384	1.29831
4	0.70163	0.78792	0.87397	0.95976	1.04525	1.13042	1.21525	1.29971
5	0.70307	0.78935	0.87540	0.96118	1.04667	1.13184	1.21666	1.30112
6	0.70451	0.79079	0.87683	0.96261	1.04809	1.13326	1.21808	1.30252
7	0.70595	0.79223	0.87827	0.96404	1.04951	1.13467	1.21949	1.30393
8	0.70739	0.79366	0.87970	0.96546	1.05094	1.13609	1.22090	1.30533
9	0.70883	0.79510	0.88113	0.96689	1.05236	1.13751	1.22231	1.30673
10	0.71027	0.79653	0.88256	0.96832	1.05378	1.13892	1.22372	1.30814
11	0.71171	0.79797	0.88399	0.96974	1.05520	1.14034	1.22513	1.30954
12	0.71314	0.79941	0.88542	0.97117	1.05662	1.14175	1.22654	1.31095
13	0.71458	0.80084	0.88686	0.97260	1.05805	1.14317	1.22795	1.31235
14	0.71602	0.80228	0.88829	0.97403	1.05947	1.14459	1.22936	1.31375
15	0.71746	0.80371	0.88972	0.97545	1.06089	1.14600	1.23077	1.31516
16	0.71890	0.80515	0.89115	0.97688	1.06231	1.14742	1.23218	1.31656
17	0.72034	0.80658	0.89258	0.97830	1.06373	1.14883	1.23359	1.31796
18	0.72178	0.80802	0.89401	0.97973	1.06515	1.15025	1.23500	1.31937
19	0.72322	0.80945	0.89544	0.98116	1.06657	1.15166	1.23640	1.32077
20	0.72466	0.81089	0.89687	0.98258	1.06799	1.15308	1.23781	1.32217
21	0.72610	0.81232	0.89830	0.98401	1.06941	1.15449	1.23922	1.32357
22	0.72754	0.81376	0.89973	0.98544	1.07084	1.15591	1.24063	1.32498
23	0.72898	0.81519	0.90117	0.98686	1.07226	1.15732	1.24204	1.32638
24	0.73042	0.81663	0.90260	0.98829	1.07368	1.15874	1.24345	1.32778
25	0.73185	0.81806	0.90403	0.98971	1.07510	1.16015	1.24486	1.32918
26	0.73329	0.81950	0.90546	0.99114	1.07652	1.16157	1.24627	1.33058
27	0.73473	0.82093	0.90689	0.99256	1.07794	1.16298	1.24768	1.33199
28	0.73617	0.82237	0.90832	0.99399	1.07936	1.16440	1.24908	1.33339
29	0.73761	0.82380	0.90975	0.99541	1.08078	1.16581	1.25049	1.33479
30	0.73905	0.82524	0.91118	0.99684	1.08220	1.16723	1.25190	1.33619
31	0.74049	0.82667	0.91261	0.99826	1.08362	1.16864	1.25331	1.33759
32	0.74192	0.82811	0.91404	0.99969	1.08504	1.17006	1.25472	1.33899
33	0.74336	0.82954	0.91547	1.00112	1.08646	1.17147	1.25612	1.34040
34	0.74480	0.83098	0.91690	1.00254	1.08788	1.17288	1.25753	1.34180
35	0.74624	0.83241	0.91833	1.00396	1.08930	1.17430	1.25894	1.34320
36	0.74768	0.83384	0.91976	1.00539	1.09072	1.17571	1.26035	1.34460
37	0.74911	0.83528	0.92119	1.00681	1.09214	1.17712	1.26175	1.34600
38	0.75055	0.83671	0.92262	1.00824	1.09355	1.17854	1.26316	1.34740
39	0.75199	0.83815	0.92405	1.00966	1.09497	1.17995	1.26457	1.34880
40	0.75343	0.83958	0.92547	1.01109	1.09639	1.18136	1.26598	1.35020
41	0.75487	0.84101	0.92690	1.01251	1.09781	1.18278	1.26738	1.35160
42	0.75630	0.84245	0.92833	1.01394	1.09923	1.18419	1.26879	1.35300
43	0.75774	0.84388	0.92976	1.01536	1.10065	1.18560	1.27020	1.35440
44	0.75918	0.84531	0.93119	1.01678	1.10207	1.18702	1.27160	1.35580
45	0.76062	0.84675	0.93262	1.01821	1.10349	1.18843	1.27301	1.35720
46	0.76205	0.84818	0.93405	1.01963	1.10491	1.18984	1.27442	1.35860
47	0.76349	0.84961	0.93548	1.02106	1.10632	1.19125	1.27582	1.36000
48	0.76493	0.85105	0.93691	1.02248	1.10774	1.19267	1.27723	1.36140
49	0.76637	0.85248	0.93834	1.02390	1.10916	1.19408	1.27863	1.36280
50	0.76780	0.85391	0.93976	1.02533	1.11058	1.19549	1.28004	1.36420
51	0.76924	0.85535	0.94119	1.02675	1.11200	1.19690	1.28145	1.36560
52	0.77068	0.85678	0.94262	1.02817	1.11342	1.19832	1.28285	1.36700
53	0.77211	0.85821	0.94405	1.02960	1.11483	1.19973	1.28426	1.36840
54	0.77355	0.85965	0.94548	1.03102	1.11625	1.20114	1.28566	1.36980
55	0.77499	0.86108	0.94691	1.03244	1.11767	1.20255	1.28707	1.37119
56	0.77643	0.86251	0.94833	1.03387	1.11909	1.20396	1.28847	1.37259
57	0.77786	0.86394	0.94976	1.03529	1.12050	1.20538	1.28988	1.37399
58	0.77930	0.86538	0.95119	1.03671	1.12192	1.20679	1.29129	1.37539
59	0.78074	0.86681	0.95262	1.03814	1.12334	1.20820	1.29269	1.37679
60	0.78217	0.86824	0.95404	1.03956	1.12476	1.20961	1.29410	1.37819

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	1.37819	1.46186	1.54509	1.62784	1.71010	1.79184	1.87303	1.95366
1	1.37958	1.46325	1.54647	1.62922	1.71147	1.79320	1.87438	1.95499
2	1.38098	1.46464	1.54785	1.63059	1.71283	1.79456	1.87573	1.95633
3	1.38238	1.46603	1.54923	1.63197	1.71420	1.79591	1.87708	1.95767
4	1.38378	1.46742	1.55062	1.63334	1.71557	1.79727	1.87843	1.95901
5	1.38518	1.46881	1.55200	1.63472	1.71693	1.79863	1.87977	1.96035
6	1.38657	1.47020	1.55338	1.63609	1.71830	1.79998	1.88112	1.96169
7	1.38797	1.47159	1.55476	1.63746	1.71966	1.80134	1.88247	1.96302
8	1.38937	1.47298	1.55615	1.63884	1.72103	1.80270	1.88382	1.96436
9	1.39076	1.47437	1.55753	1.64021	1.72240	1.80405	1.88516	1.96570
10	1.39216	1.47576	1.55891	1.64159	1.72376	1.80541	1.88651	1.96704
11	1.39356	1.47715	1.56029	1.64296	1.72513	1.80677	1.88786	1.96837
12	1.39496	1.47854	1.56167	1.64433	1.72649	1.80812	1.88920	1.96971
13	1.39635	1.47993	1.56306	1.64571	1.72786	1.80948	1.89055	1.97105
14	1.39775	1.48132	1.56444	1.64708	1.72922	1.81083	1.89190	1.97238
15	1.39915	1.48271	1.56582	1.64845	1.73059	1.81219	1.89324	1.97372
16	1.40054	1.48410	1.56720	1.64983	1.73195	1.81355	1.89459	1.97506
17	1.40194	1.48549	1.56858	1.65120	1.73331	1.81490	1.89594	1.97639
18	1.40333	1.48687	1.56996	1.65257	1.73468	1.81626	1.89728	1.97773
19	1.40473	1.48826	1.57134	1.65394	1.73604	1.81761	1.89863	1.97906
20	1.40613	1.48965	1.57272	1.65532	1.73741	1.81897	1.89997	1.98040
21	1.40752	1.49104	1.57410	1.65669	1.73877	1.82032	1.90132	1.98173
22	1.40892	1.49243	1.57548	1.65806	1.74013	1.82168	1.90266	1.98307
23	1.41031	1.49382	1.57687	1.65943	1.74150	1.82303	1.90401	1.98440
24	1.41171	1.49520	1.57825	1.66081	1.74286	1.82438	1.90535	1.98574
25	1.41310	1.49659	1.57963	1.66218	1.74422	1.82574	1.90670	1.98707
26	1.41450	1.49798	1.58101	1.66355	1.74559	1.82709	1.90804	1.98841
27	1.41589	1.49937	1.58238	1.66492	1.74695	1.82845	1.90939	1.98974
28	1.41729	1.50075	1.58376	1.66629	1.74831	1.82980	1.91073	1.99108
29	1.41868	1.50214	1.58514	1.66766	1.74967	1.83115	1.91207	1.99241
30	1.42008	1.50353	1.58652	1.66903	1.75104	1.83251	1.91342	1.99375
31	1.42147	1.50492	1.58790	1.67041	1.75240	1.83386	1.91476	1.99508
32	1.42287	1.50630	1.58928	1.67178	1.75376	1.83521	1.91610	1.99641
33	1.42426	1.50769	1.59066	1.67315	1.75512	1.83657	1.91745	1.99775
34	1.42565	1.50908	1.59204	1.67452	1.75649	1.83792	1.91879	1.99908
35	1.42705	1.51046	1.59342	1.67589	1.75785	1.83927	1.92013	2.00041
36	1.42844	1.51185	1.59480	1.67726	1.75921	1.84062	1.92148	2.00175
37	1.42984	1.51324	1.59617	1.67863	1.76057	1.84198	1.92282	2.00308
38	1.43123	1.51462	1.59755	1.68000	1.76193	1.84333	1.92416	2.00441
39	1.43262	1.51601	1.59893	1.68137	1.76329	1.84468	1.92550	2.00574
40	1.43402	1.51739	1.60031	1.68274	1.76465	1.84603	1.92685	2.00708
41	1.43541	1.51878	1.60169	1.68411	1.76601	1.84738	1.92819	2.00841
42	1.43680	1.52017	1.60307	1.68548	1.76737	1.84873	1.92953	2.00974
43	1.43820	1.52155	1.60444	1.68685	1.76873	1.85009	1.93087	2.01107
44	1.43959	1.52294	1.60582	1.68821	1.77010	1.85144	1.93221	2.01240
45	1.44098	1.52432	1.60720	1.68958	1.77146	1.85279	1.93355	2.01373
46	1.44237	1.52571	1.60857	1.69095	1.77282	1.85414	1.93490	2.01506
47	1.44377	1.52709	1.60995	1.69232	1.77418	1.85549	1.93624	2.01640
48	1.44516	1.52848	1.61133	1.69369	1.77553	1.85684	1.93758	2.01773
49	1.44655	1.52986	1.61271	1.69506	1.77689	1.85819	1.93892	2.01906
50	1.44794	1.53125	1.61408	1.69643	1.77825	1.85954	1.94026	2.02039
51	1.44934	1.53263	1.61546	1.69779	1.77961	1.86089	1.94160	2.02172
52	1.45073	1.53401	1.61683	1.69916	1.78097	1.86224	1.94294	2.02305
53	1.45212	1.53540	1.61821	1.70053	1.78233	1.86359	1.94428	2.02438
54	1.45351	1.53678	1.61959	1.70190	1.78369	1.86494	1.94562	2.02571
55	1.45490	1.53817	1.62096	1.70327	1.78505	1.86629	1.94696	2.02704
56	1.45629	1.53955	1.62234	1.70463	1.78641	1.86764	1.94830	2.02837
57	1.45769	1.54093	1.62371	1.70600	1.78777	1.86899	1.94964	2.02970
58	1.45908	1.54232	1.62509	1.70737	1.78912	1.87034	1.95098	2.03103
59	1.46047	1.54370	1.62647	1.70873	1.79048	1.87168	1.95232	2.03235
60	1.46186	1.54509	1.62784	1.71010	1.79184	1.87303	1.95366	2.03368

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	2.03368	2.11309	2.19186	2.26995	2.34736	2.42405	2.50000	2.57519
1	2.03501	2.11441	2.19316	2.27125	2.34864	2.42532	2.50126	2.57644
2	2.03634	2.11573	2.19447	2.27254	2.34993	2.42659	2.50252	2.57768
3	2.03767	2.11704	2.19578	2.27384	2.35121	2.42786	2.50378	2.57893
4	2.03900	2.11836	2.19708	2.27513	2.35249	2.42913	2.50504	2.58018
5	2.04032	2.11968	2.19839	2.27643	2.35378	2.43041	2.50630	2.58142
6	2.04165	2.12100	2.19970	2.27772	2.35506	2.43168	2.50755	2.58267
7	2.04298	2.12231	2.20100	2.27902	2.35634	2.43295	2.50881	2.58391
8	2.04431	2.12363	2.20231	2.28031	2.35763	2.43422	2.51007	2.58516
9	2.04563	2.12495	2.20361	2.28161	2.35891	2.43549	2.51133	2.58640
10	2.04696	2.12626	2.20492	2.28290	2.36019	2.43676	2.51259	2.58765
11	2.04829	2.12758	2.20622	2.28420	2.36147	2.43803	2.51384	2.58889
12	2.04962	2.12890	2.20753	2.28549	2.36275	2.43930	2.51510	2.59014
13	2.05094	2.13021	2.20883	2.28678	2.36404	2.44057	2.51636	2.59138
14	2.05227	2.13153	2.21014	2.28808	2.36532	2.44184	2.51761	2.59262
15	2.05359	2.13284	2.21144	2.28937	2.36660	2.44311	2.51887	2.59387
16	2.05492	2.13416	2.21275	2.29066	2.36788	2.44438	2.52013	2.59511
17	2.05625	2.13547	2.21405	2.29196	2.36916	2.44564	2.52138	2.59635
18	2.05757	2.13679	2.21536	2.29325	2.37044	2.44691	2.52264	2.59760
19	2.05890	2.13810	2.21666	2.29454	2.37172	2.44818	2.52389	2.59884
20	2.06022	2.13942	2.21796	2.29583	2.37300	2.44945	2.52515	2.60008
21	2.06155	2.14073	2.21927	2.29712	2.37428	2.45072	2.52640	2.60132
22	2.06287	2.14205	2.22057	2.29842	2.37556	2.45198	2.52766	2.60256
23	2.06420	2.14336	2.22187	2.29971	2.37684	2.45325	2.52891	2.60381
24	2.06552	2.14468	2.22318	2.30100	2.37812	2.45452	2.53017	2.60505
25	2.06685	2.14599	2.22448	2.30229	2.37940	2.45579	2.53142	2.60629
26	2.06817	2.14730	2.22578	2.30358	2.38068	2.45705	2.53268	2.60753
27	2.06950	2.14862	2.22708	2.30487	2.38196	2.45832	2.53393	2.60877
28	2.07082	2.14993	2.22839	2.30616	2.38324	2.45959	2.53519	2.61001
29	2.07214	2.15124	2.22969	2.30745	2.38452	2.46085	2.53644	2.61125
30	2.07347	2.15256	2.23099	2.30874	2.38579	2.46212	2.53769	2.61249
31	2.07479	2.15387	2.23229	2.31003	2.38707	2.46338	2.53894	2.61373
32	2.07611	2.15518	2.23359	2.31132	2.38835	2.46465	2.54020	2.61497
33	2.07744	2.15649	2.23489	2.31261	2.38963	2.46591	2.54145	2.61621
34	2.07876	2.15781	2.23619	2.31390	2.39091	2.46718	2.54270	2.61745
35	2.08008	2.15912	2.23749	2.31519	2.39218	2.46844	2.54396	2.61869
36	2.08140	2.16043	2.23880	2.31648	2.39346	2.46971	2.54521	2.61993
37	2.08273	2.16174	2.24010	2.31777	2.39474	2.47097	2.54646	2.62117
38	2.08405	2.16305	2.24140	2.31906	2.39601	2.47224	2.54771	2.62241
39	2.08537	2.16436	2.24270	2.32035	2.39729	2.47350	2.54896	2.62364
40	2.08669	2.16567	2.24400	2.32163	2.39857	2.47477	2.55021	2.62488
41	2.08801	2.16698	2.24530	2.32292	2.39984	2.47603	2.55146	2.62612
42	2.08934	2.16830	2.24660	2.32421	2.40112	2.47729	2.55271	2.62736
43	2.09066	2.16961	2.24789	2.32550	2.40239	2.47856	2.55397	2.62860
44	2.09198	2.17092	2.24919	2.32679	2.40367	2.47982	2.55522	2.62983
45	2.09330	2.17223	2.25049	2.32807	2.40494	2.48108	2.55647	2.63107
46	2.09462	2.17354	2.25179	2.32936	2.40622	2.48235	2.55772	2.63231
47	2.09594	2.17485	2.25309	2.33065	2.40749	2.48361	2.55896	2.63354
48	2.09726	2.17616	2.25439	2.33193	2.40877	2.48487	2.56021	2.63478
49	2.09858	2.17746	2.25569	2.33322	2.41004	2.48613	2.56146	2.63602
50	2.09990	2.17877	2.25698	2.33451	2.41132	2.48739	2.56271	2.63725
51	2.10122	2.18008	2.25828	2.33579	2.41259	2.48866	2.56396	2.63849
52	2.10254	2.18139	2.25958	2.33708	2.41386	2.48992	2.56521	2.63972
53	2.10386	2.18270	2.26088	2.33836	2.41514	2.49118	2.56646	2.64096
54	2.10518	2.18401	2.26217	2.33965	2.41641	2.49244	2.56771	2.64219
55	2.10650	2.18532	2.26347	2.34093	2.41769	2.49370	2.56895	2.64343
56	2.10782	2.18663	2.26477	2.34222	2.41896	2.49496	2.57020	2.64466
57	2.10914	2.18793	2.26606	2.34350	2.42023	2.49622	2.57145	2.64590
58	2.11045	2.18924	2.26736	2.34479	2.42150	2.49748	2.57270	2.64713
59	2.11177	2.19055	2.26866	2.34607	2.42278	2.49874	2.57394	2.64836
60	2.11309	2.19186	2.26995	2.34736	2.42405	2.50000	2.57519	2.64960

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	2.64960	2.72320	2.79596	2.86788	2.93893	3.00908	3.07831	3.14660
1	2.65083	2.72441	2.79717	2.86907	2.94010	3.01024	3.07945	3.14773
2	2.65206	2.72563	2.79838	2.87026	2.94128	3.01140	3.08060	3.14886
3	2.65330	2.72685	2.79958	2.87146	2.94246	3.01256	3.08174	3.14999
4	2.65453	2.72807	2.80079	2.87265	2.94363	3.01372	3.08289	3.15112
5	2.65576	2.72929	2.80199	2.87384	2.94481	3.01488	3.08403	3.15225
6	2.65699	2.73051	2.80319	2.87503	2.94598	3.01604	3.08518	3.15338
7	2.65822	2.73173	2.80440	2.87622	2.94716	3.01720	3.08632	3.15451
8	2.65946	2.73295	2.80560	2.87741	2.94833	3.01836	3.08747	3.15564
9	2.66069	2.73416	2.80681	2.87860	2.94951	3.01952	3.08861	3.15676
10	2.66192	2.73538	2.80801	2.87978	2.95068	3.02068	3.08976	3.15789
11	2.66315	2.73660	2.80921	2.88097	2.95185	3.02184	3.09090	3.15902
12	2.66438	2.73782	2.81042	2.88216	2.95303	3.02300	3.09204	3.16015
13	2.66561	2.73903	2.81162	2.88335	2.95420	3.02415	3.09318	3.16127
14	2.66684	2.74025	2.81282	2.88454	2.95538	3.02531	3.09433	3.16240
15	2.66807	2.74147	2.81402	2.88573	2.95655	3.02647	3.09547	3.16353
16	2.66930	2.74268	2.81523	2.88691	2.95772	3.02763	3.09661	3.16465
17	2.67053	2.74390	2.81643	2.88810	2.95889	3.02878	3.09775	3.16578
18	2.67176	2.74511	2.81763	2.88929	2.96007	3.02994	3.09890	3.16690
19	2.67299	2.74633	2.81883	2.89048	2.96124	3.03110	3.10004	3.16803
20	2.67422	2.74754	2.82003	2.89166	2.96241	3.03226	3.10118	3.16915
21	2.67545	2.74876	2.82123	2.89285	2.96358	3.03341	3.10232	3.17028
22	2.67668	2.74997	2.82243	2.89403	2.96475	3.03457	3.10346	3.17140
23	2.67791	2.75119	2.82364	2.89522	2.96592	3.03572	3.10460	3.17253
24	2.67913	2.75240	2.82484	2.89641	2.96709	3.03688	3.10574	3.17365
25	2.68036	2.75362	2.82604	2.89759	2.96827	3.03803	3.10688	3.17478
26	2.68159	2.75483	2.82723	2.89878	2.96944	3.03919	3.10802	3.17590
27	2.68282	2.75605	2.82843	2.89996	2.97061	3.04034	3.10916	3.17702
28	2.68404	2.75726	2.82963	2.90115	2.97178	3.04150	3.11030	3.17815
29	2.68527	2.75847	2.83083	2.90233	2.97294	3.04265	3.11143	3.17927
30	2.68650	2.75969	2.83203	2.90351	2.97411	3.04381	3.11257	3.18039
31	2.68772	2.76090	2.83323	2.90470	2.97528	3.04496	3.11371	3.18151
32	2.68895	2.76211	2.83443	2.90588	2.97645	3.04611	3.11485	3.18264
33	2.69018	2.76332	2.83563	2.90707	2.97762	3.04727	3.11599	3.18376
34	2.69140	2.76453	2.83682	2.90825	2.97879	3.04842	3.11712	3.18488
35	2.69263	2.76575	2.83802	2.90943	2.97996	3.04957	3.11826	3.18600
36	2.69385	2.76696	2.83922	2.91061	2.98112	3.05073	3.11940	3.18712
37	2.69508	2.76817	2.84042	2.91180	2.98229	3.05188	3.12053	3.18824
38	2.69630	2.76938	2.84161	2.91298	2.98346	3.05303	3.12167	3.18936
39	2.69753	2.77059	2.84281	2.91416	2.98463	3.05418	3.12281	3.19048
40	2.69875	2.77180	2.84401	2.91534	2.98579	3.05533	3.12394	3.19160
41	2.69998	2.77301	2.84520	2.91652	2.98696	3.05648	3.12508	3.19272
42	2.70120	2.77422	2.84640	2.91771	2.98813	3.05764	3.12621	3.19384
43	2.70243	2.77543	2.84759	2.91889	2.98929	3.05879	3.12735	3.19496
44	2.70365	2.77664	2.84879	2.92007	2.99046	3.05994	3.12848	3.19608
45	2.70487	2.77785	2.84998	2.92125	2.99162	3.06109	3.12962	3.19720
46	2.70610	2.77906	2.85118	2.92243	2.99279	3.06224	3.13075	3.19831
47	2.70732	2.78027	2.85237	2.92361	2.99395	3.06339	3.13189	3.19943
48	2.70854	2.78148	2.85357	2.92479	2.99512	3.06454	3.13302	3.20055
49	2.70976	2.78269	2.85476	2.92597	2.99628	3.06568	3.13415	3.20167
50	2.71099	2.78389	2.85596	2.92715	2.99745	3.06683	3.13529	3.20278
51	2.71221	2.78510	2.85715	2.92833	2.99861	3.06798	3.13642	3.20390
52	2.71343	2.78631	2.85834	2.92950	2.99977	3.06913	3.13755	3.20502
53	2.71465	2.78752	2.85954	2.93068	3.00094	3.07028	3.13868	3.20613
54	2.71587	2.78873	2.86073	2.93186	3.00210	3.07143	3.13982	3.20725
55	2.71709	2.78993	2.86192	2.93304	3.00326	3.07257	3.14095	3.20836
56	2.71831	2.79114	2.86311	2.93422	3.00443	3.07372	3.14208	3.20948
57	2.71953	2.79235	2.86431	2.93540	3.00559	3.07487	3.14321	3.21059
58	2.72076	2.79355	2.86550	2.93657	3.00675	3.07601	3.14434	3.21171
59	2.72198	2.79476	2.86669	2.93775	3.00791	3.07716	3.14547	3.21282
60	2.72320	2.79596	2.86788	2.93893	3.00908	3.07831	3.14660	3.21394

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	3.21394	3.28030	3.34565	3.40999	3.47329	3.53553	3.59670	3.65677
1	3.21505	3.28139	3.34673	3.41106	3.47434	3.53656	3.59771	3.65776
2	3.21617	3.28249	3.34781	3.41212	3.47538	3.53759	3.59872	3.65875
3	3.21728	3.28359	3.34889	3.41318	3.47643	3.53862	3.59973	3.65974
4	3.21839	3.28468	3.34997	3.41424	3.47747	3.53965	3.60074	3.66073
5	3.21951	3.28578	3.35105	3.41531	3.47852	3.54067	3.60175	3.66172
6	3.22062	3.28688	3.35213	3.41637	3.47956	3.54170	3.60276	3.66271
7	3.22173	3.28797	3.35321	3.41743	3.48061	3.54273	3.60376	3.66370
8	3.22284	3.28907	3.35429	3.41849	3.48165	3.54375	3.60477	3.66469
9	3.22395	3.29016	3.35537	3.41955	3.48270	3.54478	3.60578	3.66568
10	3.22507	3.29126	3.35645	3.42061	3.48374	3.54580	3.60679	3.66667
11	3.22618	3.29235	3.35753	3.42168	3.48478	3.54683	3.60779	3.66766
12	3.22729	3.29345	3.35860	3.42274	3.48583	3.54785	3.60880	3.66865
13	3.22840	3.29454	3.35968	3.42380	3.48687	3.54888	3.60981	3.66964
14	3.22951	3.29564	3.36076	3.42486	3.48791	3.54990	3.61081	3.67063
15	3.23062	3.29673	3.36183	3.42592	3.48895	3.55093	3.61182	3.67161
16	3.23173	3.29782	3.36291	3.42697	3.48999	3.55195	3.61283	3.67260
17	3.23284	3.29892	3.36399	3.42803	3.49104	3.55297	3.61383	3.67359
18	3.23395	3.30001	3.36506	3.42909	3.49208	3.55400	3.61484	3.67457
19	3.23506	3.30110	3.36614	3.43015	3.49312	3.55502	3.61584	3.67556
20	3.23617	3.30219	3.36721	3.43121	3.49416	3.55604	3.61684	3.67655
21	3.23728	3.30329	3.36829	3.43227	3.49520	3.55707	3.61785	3.67753
22	3.23838	3.30438	3.36936	3.43332	3.49624	3.55809	3.61885	3.67852
23	3.23949	3.30547	3.37044	3.43438	3.49728	3.55911	3.61986	3.67950
24	3.24060	3.30656	3.37151	3.43544	3.49832	3.56013	3.62086	3.68049
25	3.24171	3.30765	3.37259	3.43649	3.49936	3.56115	3.62186	3.68147
26	3.24281	3.30874	3.37366	3.43755	3.50039	3.56217	3.62286	3.68245
27	3.24392	3.30983	3.37473	3.43861	3.50143	3.56319	3.62387	3.68344
28	3.24503	3.31092	3.37581	3.43966	3.50247	3.56421	3.62487	3.68442
29	3.24613	3.31201	3.37688	3.44072	3.50351	3.56523	3.62587	3.68540
30	3.24724	3.31310	3.37795	3.44177	3.50455	3.56625	3.62687	3.68639
31	3.24835	3.31419	3.37902	3.44283	3.50558	3.56727	3.62787	3.68737
32	3.24945	3.31528	3.38010	3.44388	3.50662	3.56829	3.62887	3.68835
33	3.25056	3.31637	3.38117	3.44494	3.50766	3.56931	3.62987	3.68933
34	3.25166	3.31746	3.38224	3.44599	3.50869	3.57033	3.63087	3.69031
35	3.25277	3.31854	3.38331	3.44704	3.50973	3.57135	3.63187	3.69130
36	3.25387	3.31963	3.38438	3.44810	3.51077	3.57236	3.63287	3.69228
37	3.25498	3.32072	3.38545	3.44915	3.51180	3.57338	3.63387	3.69326
38	3.25608	3.32181	3.38652	3.45020	3.51284	3.57440	3.63487	3.69424
39	3.25718	3.32289	3.38759	3.45126	3.51387	3.57542	3.63587	3.69522
40	3.25829	3.32398	3.38866	3.45231	3.51491	3.57643	3.63687	3.69620
41	3.25939	3.32507	3.38973	3.45336	3.51594	3.57745	3.63787	3.69718
42	3.26049	3.32615	3.39080	3.45441	3.51697	3.57846	3.63886	3.69816
43	3.26159	3.32724	3.39187	3.45546	3.51801	3.57948	3.63986	3.69913
44	3.26270	3.32832	3.39294	3.45651	3.51904	3.58049	3.64086	3.70011
45	3.26380	3.32941	3.39400	3.45757	3.52007	3.58151	3.64186	3.70109
46	3.26490	3.33049	3.39507	3.45862	3.52111	3.58252	3.64285	3.70207
47	3.26600	3.33158	3.39614	3.45967	3.52214	3.58354	3.64385	3.70305
48	3.26710	3.33266	3.39721	3.46072	3.52317	3.58455	3.64484	3.70402
49	3.26820	3.33375	3.39827	3.46177	3.52420	3.58557	3.64584	3.70500
50	3.26930	3.33483	3.39934	3.46281	3.52523	3.58658	3.64683	3.70598
51	3.27040	3.33591	3.40041	3.46386	3.52627	3.58759	3.64783	3.70695
52	3.27150	3.33700	3.40147	3.46491	3.52730	3.58861	3.64882	3.70793
53	3.27260	3.33808	3.40254	3.46596	3.52833	3.58962	3.64982	3.70890
54	3.27370	3.33916	3.40360	3.46701	3.52936	3.59063	3.65081	3.70988
55	3.27480	3.34025	3.40467	3.46806	3.53039	3.59164	3.65181	3.71085
56	3.27590	3.34133	3.40573	3.46910	3.53142	3.59266	3.65280	3.71183
57	3.27700	3.34241	3.40680	3.47015	3.53245	3.59367	3.65379	3.71280
58	3.27810	3.34349	3.40786	3.47120	3.53348	3.59468	3.65478	3.71378
59	3.27920	3.34457	3.40893	3.47225	3.53451	3.59569	3.65578	3.71475
60	3.28030	3.34565	3.40999	3.47329	3.53553	3.59670	3.65677	3.71572

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	3.71572	3.77355	3.83022	3.88573	3.94005	3.99318	4.04508	4.09576
1	3.71670	3.77450	3.83116	3.88665	3.94095	3.99405	4.04594	4.09659
2	3.71767	3.77546	3.83209	3.88756	3.94184	3.99493	4.04679	4.09743
3	3.71864	3.77641	3.83303	3.88847	3.94274	3.99580	4.04765	4.09826
4	3.71961	3.77736	3.83396	3.88939	3.94363	3.99668	4.04850	4.09909
5	3.72059	3.77831	3.83489	3.89030	3.94453	3.99755	4.04936	4.09993
6	3.72156	3.77927	3.83583	3.89122	3.94542	3.99842	4.05021	4.10076
7	3.72253	3.78022	3.83676	3.89213	3.94631	3.99930	4.05106	4.10159
8	3.72350	3.78117	3.83769	3.89304	3.94721	4.00017	4.05191	4.10242
9	3.72447	3.78212	3.83862	3.89395	3.94810	4.00104	4.05277	4.10325
10	3.72544	3.78307	3.83956	3.89487	3.94899	4.00191	4.05362	4.10409
11	3.72641	3.78402	3.84049	3.89578	3.94988	4.00279	4.05447	4.10492
12	3.72738	3.78498	3.84142	3.89669	3.95078	4.00366	4.05532	4.10575
13	3.72835	3.78593	3.84235	3.89760	3.95167	4.00453	4.05617	4.10658
14	3.72932	3.78688	3.84328	3.89851	3.95256	4.00540	4.05702	4.10741
15	3.73029	3.78783	3.84421	3.89942	3.95345	4.00627	4.05787	4.10823
16	3.73126	3.78877	3.84514	3.90033	3.95434	4.00714	4.05872	4.10906
17	3.73222	3.78972	3.84607	3.90124	3.95523	4.00801	4.05957	4.10989
18	3.73319	3.79067	3.84700	3.90215	3.95612	4.00888	4.06042	4.11072
19	3.73416	3.79162	3.84793	3.90306	3.95701	4.00975	4.06127	4.11155
20	3.73513	3.79257	3.84886	3.90397	3.95790	4.01062	4.06211	4.11238
21	3.73609	3.79352	3.84978	3.90488	3.95878	4.01148	4.06296	4.11320
22	3.73706	3.79446	3.85071	3.90579	3.95967	4.01235	4.06381	4.11403
23	3.73802	3.79541	3.85164	3.90669	3.96056	4.01322	4.06466	4.11486
24	3.73899	3.79636	3.85257	3.90760	3.96145	4.01409	4.06550	4.11568
25	3.73996	3.79730	3.85349	3.90851	3.96234	4.01495	4.06635	4.11651
26	3.74092	3.79825	3.85442	3.90942	3.96322	4.01582	4.06720	4.11733
27	3.74189	3.79919	3.85535	3.91032	3.96411	4.01669	4.06804	4.11816
28	3.74285	3.80014	3.85627	3.91123	3.96500	4.01755	4.06889	4.11898
29	3.74381	3.80109	3.85720	3.91214	3.96588	4.01842	4.06973	4.11981
30	3.74478	3.80203	3.85812	3.91304	3.96677	4.01928	4.07058	4.12063
31	3.74574	3.80297	3.85905	3.91395	3.96765	4.02015	4.07142	4.12145
32	3.74671	3.80392	3.85997	3.91485	3.96854	4.02101	4.07227	4.12228
33	3.74767	3.80486	3.86090	3.91576	3.96942	4.02188	4.07311	4.12310
34	3.74863	3.80581	3.86182	3.91666	3.97031	4.02274	4.07395	4.12392
35	3.74959	3.80675	3.86274	3.91756	3.97119	4.02361	4.07480	4.12475
36	3.75056	3.80769	3.86367	3.91847	3.97207	4.02447	4.07564	4.12557
37	3.75152	3.80863	3.86459	3.91937	3.97296	4.02533	4.07648	4.12639
38	3.75248	3.80958	3.86551	3.92027	3.97384	4.02619	4.07732	4.12721
39	3.75344	3.81052	3.86644	3.92118	3.97472	4.02706	4.07817	4.12803
40	3.75440	3.81146	3.86736	3.92208	3.97560	4.02792	4.07901	4.12885
41	3.75536	3.81240	3.86828	3.92298	3.97649	4.02878	4.07985	4.12967
42	3.75632	3.81334	3.86920	3.92388	3.97737	4.02964	4.08069	4.13049
43	3.75728	3.81428	3.87012	3.92478	3.97825	4.03050	4.08153	4.13131
44	3.75824	3.81522	3.87104	3.92568	3.97913	4.03136	4.08237	4.13213
45	3.75920	3.81616	3.87196	3.92658	3.98001	4.03222	4.08321	4.13295
46	3.76016	3.81710	3.87288	3.92748	3.98089	4.03308	4.08405	4.13377
47	3.76112	3.81804	3.87380	3.92839	3.98177	4.03394	4.08489	4.13459
48	3.76207	3.81898	3.87472	3.92928	3.98265	4.03480	4.08572	4.13540
49	3.76303	3.81992	3.87564	3.93018	3.98353	4.03566	4.08656	4.13622
50	3.76399	3.82086	3.87656	3.93108	3.98441	4.03652	4.08740	4.13704
51	3.76495	3.82179	3.87748	3.93198	3.98529	4.03738	4.08824	4.13785
52	3.76590	3.82273	3.87840	3.93288	3.98616	4.03823	4.08908	4.13867
53	3.76686	3.82367	3.87931	3.93378	3.98704	4.03909	4.08991	4.13949
54	3.76782	3.82461	3.88023	3.93468	3.98792	4.03995	4.09075	4.14030
55	3.76877	3.82554	3.88115	3.93557	3.98880	4.04081	4.09158	4.14112
56	3.76973	3.82648	3.88207	3.93647	3.98967	4.04166	4.09242	4.14193
57	3.77068	3.82742	3.88298	3.93737	3.99055	4.04252	4.09326	4.14275
58	3.77164	3.82835	3.88390	3.93826	3.99143	4.04337	4.09409	4.14356
59	3.77259	3.82929	3.88481	3.93916	3.99230	4.04423	4.09493	4.14437
60	3.77355	3.83022	3.88573	3.94005	3.99318	4.04508	4.09576	4.14519

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 100-millimeter Sine-bar

Constants for Setting a 100-mm Sine-bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	1.745241	3.489950	5.233596	6.975647	8.715574	10.452847	12.186934
1	0.029089	1.774325	3.519021	5.262644	7.004666	8.744553	10.481776	12.215807
2	0.058178	1.803409	3.548091	5.291693	7.033682	8.773529	10.510704	12.244677
3	0.087266	1.832493	3.577162	5.320741	7.062699	8.802505	10.539631	12.273546
4	0.116355	1.861577	3.606232	5.349788	7.091714	8.831481	10.568558	12.302414
5	0.145444	1.890661	3.635301	5.378835	7.120730	8.860456	10.597483	12.331282
6	0.174533	1.919744	3.664371	5.407881	7.149745	8.889430	10.626408	12.360147
7	0.203622	1.948828	3.693440	5.436927	7.178759	8.918404	10.655332	12.389013
8	0.232710	1.977911	3.722509	5.465973	7.207772	8.947375	10.684254	12.417877
9	0.261799	2.006994	3.751578	5.495018	7.236785	8.976348	10.713176	12.446741
10	0.290888	2.036077	3.780646	5.524063	7.265797	9.005319	10.742096	12.475602
11	0.319977	2.065159	3.809714	5.553107	7.294809	9.034289	10.771017	12.504464
12	0.349065	2.094242	3.838781	5.582151	7.323820	9.063258	10.799935	12.533323
13	0.378154	2.123324	3.867848	5.611194	7.352830	9.092227	10.828855	12.562182
14	0.407242	2.152407	3.896915	5.640237	7.381840	9.121195	10.857771	12.591040
15	0.436331	2.181489	3.925982	5.669279	7.410849	9.150162	10.886688	12.619897
16	0.465420	2.210570	3.955048	5.698321	7.439858	9.179129	10.915604	12.648753
17	0.494508	2.239652	3.984114	5.727362	7.468865	9.208094	10.944518	12.677608
18	0.523596	2.268733	4.013179	5.756403	7.497873	9.237060	10.973432	12.706462
19	0.552685	2.297815	4.042244	5.785443	7.526879	9.266023	11.002344	12.735313
20	0.581773	2.326896	4.071309	5.814483	7.555886	9.294987	11.031256	12.764166
21	0.610861	2.355977	4.100374	5.843522	7.584891	9.323949	11.060166	12.793015
22	0.639950	2.385057	4.129438	5.872561	7.613896	9.352911	11.089077	12.821865
23	0.669038	2.414138	4.158502	5.901600	7.642900	9.381871	11.117986	12.850713
24	0.698126	2.443218	4.187566	5.930638	7.671903	9.410831	11.146894	12.879560
25	0.727214	2.472298	4.216629	5.959675	7.700905	9.439791	11.175800	12.908405
26	0.756302	2.501378	4.245691	5.988712	7.729908	9.468750	11.204707	12.937251
27	0.785390	2.530457	4.274754	6.017748	7.758909	9.497706	11.233611	12.966094
28	0.814478	2.559537	4.303816	6.046784	7.787910	9.526664	11.262516	12.994938
29	0.843566	2.588616	4.332878	6.075819	7.816910	9.555620	11.291419	13.023779
30	0.872654	2.617695	4.361939	6.104854	7.845910	9.584576	11.320322	13.052620
31	0.901741	2.646774	4.391000	6.133888	7.874909	9.613530	11.349223	13.081459
32	0.930829	2.675852	4.420060	6.162922	7.903907	9.642484	11.378123	13.110297
33	0.959916	2.704930	4.449121	6.191956	7.932905	9.671437	11.407023	13.139134
34	0.989004	2.734009	4.478180	6.220988	7.961901	9.700389	11.435922	13.167971
35	1.018091	2.763086	4.507240	6.250021	7.990898	9.729341	11.464819	13.196806
36	1.047179	2.792164	4.536299	6.279052	8.019893	9.758290	11.493715	13.225639
37	1.076266	2.821241	4.565357	6.308083	8.048887	9.787240	11.522612	13.254473
38	1.105353	2.850318	4.594416	6.337114	8.077881	9.816189	11.551505	13.283303
39	1.134440	2.879395	4.623474	6.366144	8.106875	9.845137	11.580400	13.312135
40	1.163527	2.908472	4.652532	6.395174	8.135867	9.874084	11.609291	13.340963
41	1.192613	2.937548	4.681589	6.424202	8.164860	9.903030	11.638184	13.369792
42	1.221700	2.966624	4.710645	6.453231	8.193851	9.931975	11.667073	13.398619
43	1.250787	2.995700	4.739702	6.482259	8.222842	9.960920	11.695964	13.427444
44	1.279873	3.024776	4.768757	6.511286	8.251831	9.989863	11.724852	13.456269
45	1.308960	3.053851	4.797813	6.540313	8.280821	10.018806	11.753740	13.485093
46	1.338046	3.082927	4.826868	6.569339	8.309810	10.047749	11.782627	13.513916
47	1.367132	3.112001	4.855923	6.598365	8.338798	10.076690	11.811512	13.542737
48	1.396218	3.141076	4.884977	6.627390	8.367785	10.105630	11.840398	13.571558
49	1.425304	3.170151	4.914031	6.656415	8.396770	10.134569	11.869281	13.600377
50	1.454390	3.199224	4.943084	6.685439	8.425757	10.163508	11.898164	13.629195
51	1.483476	3.228298	4.972137	6.714462	8.454741	10.192446	11.927045	13.658011
52	1.512561	3.257372	5.001190	6.743485	8.483727	10.221383	11.955926	13.686828
53	1.541646	3.286445	5.030242	6.772508	8.512710	10.250319	11.984805	13.715641
54	1.570732	3.315518	5.059294	6.801529	8.541693	10.279254	12.013684	13.744455
55	1.599817	3.344591	5.088346	6.830551	8.570675	10.308188	12.042562	13.773267
56	1.628902	3.373663	5.117396	6.859571	8.599656	10.337122	12.071439	13.802078
57	1.657987	3.402735	5.146447	6.888591	8.628636	10.366054	12.100314	13.830888
58	1.687072	3.431807	5.175497	6.917611	8.657617	10.394986	12.129189	13.859696
59	1.716156	3.460879	5.204546	6.946630	8.686596	10.423916	12.158062	13.888504
60	1.745241	3.489950	5.233596	6.975647	8.715574	10.452847	12.186934	13.917311

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	13.917311	15.643447	17.364819	19.080900	20.791170	22.495106	24.192190	25.881905
1	13.946115	15.672176	17.393463	19.109453	20.819622	22.523447	24.220413	25.910002
2	13.974920	15.700907	17.422110	19.138006	20.848074	22.551790	24.248636	25.938097
3	14.003723	15.729633	17.450752	19.166555	20.876522	22.580128	24.276855	25.966188
4	14.032524	15.758359	17.479393	19.195105	20.904968	22.608463	24.305073	25.994278
5	14.061324	15.787084	17.508034	19.223652	20.933413	22.636799	24.333288	26.022366
6	14.090124	15.815807	17.536674	19.252197	20.961857	22.665133	24.361502	26.050451
7	14.118922	15.844529	17.565311	19.280741	20.990299	22.693462	24.389713	26.078535
8	14.147718	15.873250	17.593946	19.309282	21.018738	22.721790	24.417923	26.106615
9	14.176514	15.901969	17.622580	19.337824	21.047176	22.750118	24.446129	26.134695
10	14.205309	15.930688	17.651215	19.366364	21.075613	22.778444	24.474335	26.162773
11	14.234102	15.959404	17.679844	19.394899	21.104048	22.806767	24.502539	26.190845
12	14.262894	15.988119	17.708475	19.423435	21.132481	22.835087	24.530739	26.218918
13	14.291684	16.016832	17.737103	19.451969	21.160910	22.863405	24.558937	26.246988
14	14.320475	16.045546	17.765730	19.480503	21.189341	22.891726	24.587135	26.275057
15	14.349262	16.074257	17.794355	19.509033	21.217768	22.920040	24.615330	26.303122
16	14.378049	16.102966	17.822979	19.537561	21.246193	22.948353	24.643522	26.331184
17	14.406837	16.131676	17.851603	19.566090	21.274618	22.976665	24.671715	26.359247
18	14.435621	16.160383	17.880222	19.594616	21.303040	23.004974	24.699902	26.387306
19	14.464404	16.189089	17.908842	19.623138	21.331459	23.033281	24.728088	26.415361
20	14.493186	16.217793	17.937458	19.651661	21.359877	23.061586	24.756271	26.443417
21	14.521968	16.246496	17.966076	19.680183	21.388294	23.089891	24.784456	26.471470
22	14.550748	16.275198	17.994690	19.708702	21.416710	23.118193	24.812635	26.499519
23	14.579526	16.303898	18.023304	19.737219	21.445122	23.146492	24.840813	26.527567
24	14.608303	16.332596	18.051914	19.765734	21.473532	23.174789	24.868988	26.555613
25	14.637080	16.361296	18.080526	19.794249	21.501944	23.203087	24.897163	26.583656
26	14.665854	16.389990	18.109135	19.822762	21.530350	23.231380	24.925335	26.611696
27	14.694628	16.418684	18.137741	19.851271	21.558756	23.259672	24.953505	26.639736
28	14.723400	16.447378	18.166346	19.879780	21.587158	23.287962	24.981672	26.667770
29	14.752172	16.476070	18.194950	19.908289	21.615562	23.316252	25.009838	26.695807
30	14.780942	16.504761	18.223553	19.936794	21.643963	23.344538	25.038002	26.723839
31	14.809710	16.533449	18.252153	19.965298	21.672359	23.372820	25.066162	26.751867
32	14.838478	16.562140	18.280754	19.993801	21.700758	23.401104	25.094322	26.779896
33	14.867244	16.590824	18.309351	20.022301	21.729153	23.429384	25.122478	26.807920
34	14.896008	16.619509	18.337948	20.050800	21.757544	23.457661	25.150633	26.835943
35	14.924772	16.648193	18.366541	20.079296	21.785934	23.485937	25.178785	26.863964
36	14.953535	16.676876	18.395136	20.107794	21.814325	23.514212	25.206938	26.891983
37	14.982296	16.705557	18.423727	20.136286	21.842712	23.542484	25.235085	26.920000
38	15.011056	16.734236	18.452316	20.164778	21.871098	23.570755	25.263231	26.948013
39	15.039814	16.762913	18.480906	20.193268	21.899481	23.599022	25.291374	26.976025
40	15.068572	16.791590	18.509493	20.221758	21.927864	23.627289	25.319517	27.004034
41	15.097328	16.820265	18.538078	20.250244	21.956244	23.655554	25.347658	27.032042
42	15.126082	16.848938	18.566662	20.278730	21.984621	23.683815	25.375795	27.060045
43	15.154835	16.877609	18.595243	20.307213	22.012997	23.712074	25.403931	27.088047
44	15.183589	16.906282	18.623825	20.335695	22.041372	23.740334	25.432064	27.116049
45	15.212339	16.934952	18.652405	20.364176	22.069744	23.768589	25.460196	27.144045
46	15.241088	16.963619	18.680981	20.392654	22.098114	23.796844	25.488325	27.172041
47	15.269837	16.992287	18.709558	20.421131	22.126484	23.825096	25.516453	27.200035
48	15.298584	17.020950	18.738132	20.449606	22.154850	23.853346	25.544577	27.228025
49	15.327330	17.049614	18.766705	20.478079	22.183216	23.881594	25.572699	27.256014
50	15.356073	17.078276	18.795275	20.506550	22.211578	23.909840	25.600819	27.284000
51	15.384818	17.106937	18.823847	20.535021	22.239941	23.938086	25.628939	27.311985
52	15.413560	17.135597	18.852413	20.563488	22.268299	23.966328	25.657055	27.339966
53	15.442300	17.164253	18.880980	20.591955	22.296656	23.994566	25.685167	27.367945
54	15.471039	17.192909	18.909544	20.620419	22.325012	24.022804	25.713280	27.395922
55	15.499778	17.221565	18.938108	20.648882	22.353367	24.051041	25.741390	27.423899
56	15.528514	17.250219	18.966669	20.677343	22.381718	24.079275	25.769497	27.451870
57	15.557248	17.278872	18.995230	20.705801	22.410067	24.107506	25.797602	27.479839
58	15.585982	17.307520	19.023787	20.734259	22.438416	24.135736	25.825705	27.507807
59	15.614716	17.336170	19.052345	20.762716	22.466763	24.163965	25.853807	27.535774
60	15.643447	17.364819	19.080900	20.791170	22.495106	24.192190	25.881905	27.563736

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	27.563736	29.237171	30.901701	32.556816	34.202015	35.836796	37.460659	39.073112
1	27.591696	29.264988	30.929363	32.584320	34.229347	35.863953	37.487629	39.099888
2	27.619656	29.292801	30.957024	32.611816	34.256680	35.891102	37.514595	39.126659
3	27.647610	29.320612	30.984682	32.639317	34.284004	35.918251	37.541557	39.153427
4	27.675568	29.348425	31.012341	32.666813	34.311333	35.945400	37.568520	39.180195
5	27.703518	29.376230	31.039993	32.694302	34.338654	35.972542	37.595474	39.206955
6	27.731466	29.404034	31.067644	32.721790	34.365971	35.999683	37.622429	39.233715
7	27.759413	29.431835	31.095291	32.749275	34.393288	36.026817	37.649376	39.260468
8	27.787357	29.459635	31.122936	32.776760	34.420597	36.053951	37.676323	39.287220
9	27.815298	29.487431	31.150579	32.804241	34.447906	36.081081	37.703266	39.313965
10	27.843239	29.515224	31.178219	32.831718	34.475216	36.108212	37.730206	39.340710
11	27.871176	29.543015	31.205856	32.859192	34.502518	36.135334	37.757145	39.367451
12	27.899113	29.570807	31.233494	32.886665	34.529823	36.162460	37.784081	39.394192
13	27.927044	29.598593	31.261126	32.914135	34.557121	36.189579	37.811012	39.420929
14	27.954975	29.626377	31.288755	32.941601	34.584415	36.216694	37.837940	39.447659
15	27.982903	29.654158	31.316381	32.969067	34.611706	36.243805	37.864864	39.474388
16	28.010828	29.681936	31.344006	32.996525	34.638996	36.270912	37.891785	39.501110
17	28.038750	29.709713	31.371626	33.023983	34.666283	36.298019	37.918701	39.527832
18	28.066669	29.737488	31.399244	33.051437	34.693565	36.325123	37.945614	39.554550
19	28.094591	29.765261	31.426865	33.078896	34.720848	36.352226	37.972530	39.581268
20	28.122507	29.793030	31.454477	33.106342	34.748127	36.379322	37.999439	39.607979
21	28.150421	29.820797	31.482088	33.133789	34.775398	36.406418	38.026344	39.634686
22	28.178331	29.848560	31.509697	33.161236	34.802670	36.433506	38.053246	39.661392
23	28.206240	29.876320	31.537302	33.188675	34.829941	36.460594	38.080143	39.688091
24	28.234146	29.904079	31.564903	33.216114	34.857204	36.487679	38.107037	39.714790
25	28.262049	29.931835	31.592505	33.243549	34.884468	36.514759	38.133930	39.741486
26	28.289951	29.959589	31.620102	33.270981	34.911728	36.541840	38.160820	39.768173
27	28.317852	29.987343	31.647699	33.298416	34.938988	36.568916	38.187706	39.794865
28	28.345749	30.015091	31.675291	33.325840	34.966240	36.595989	38.214588	39.821548
29	28.373644	30.042837	31.702881	33.353264	34.993492	36.623058	38.241470	39.848232
30	28.401535	30.070581	31.730467	33.380688	35.020741	36.650124	38.268345	39.874908
31	28.429424	30.098322	31.758051	33.408104	35.047985	36.677185	38.295216	39.901581
32	28.457312	30.126060	31.785631	33.435520	35.075226	36.704247	38.322086	39.928253
33	28.485195	30.153795	31.813210	33.462933	35.102463	36.731304	38.348953	39.954922
34	28.513081	30.181532	31.840790	33.490349	35.129704	36.758358	38.375816	39.981586
35	28.540960	30.209263	31.868362	33.517754	35.156937	36.785408	38.402679	40.008247
36	28.568838	30.236990	31.895933	33.545158	35.184166	36.812458	38.429535	40.034904
37	28.596712	30.264715	31.923500	33.572559	35.211395	36.839500	38.456387	40.061558
38	28.624586	30.292439	31.951065	33.599960	35.238617	36.866543	38.483238	40.088207
39	28.652456	30.320160	31.978628	33.627354	35.265839	36.893581	38.510082	40.114857
40	28.680323	30.347878	32.006187	33.654747	35.293056	36.920616	38.536926	40.141499
41	28.708189	30.375593	32.033745	33.682137	35.320271	36.947647	38.563766	40.168140
42	28.736053	30.403309	32.061302	33.709530	35.347488	36.974678	38.590607	40.194778
43	28.763914	30.431019	32.088852	33.736912	35.374695	37.001705	38.617439	40.221413
44	28.791773	30.458725	32.116402	33.764294	35.401901	37.028725	38.644272	40.248043
45	28.819628	30.486431	32.143948	33.791672	35.429104	37.055744	38.671097	40.274670
46	28.847481	30.514133	32.171490	33.819050	35.456306	37.082760	38.697922	40.301292
47	28.875332	30.541832	32.199032	33.846420	35.483501	37.109772	38.724743	40.327911
48	28.903179	30.569530	32.226570	33.873791	35.510696	37.136784	38.751560	40.354530
49	28.931028	30.597227	32.254108	33.901161	35.537891	37.163792	38.778374	40.381145
50	28.958872	30.624920	32.281639	33.928528	35.565079	37.190796	38.805187	40.407757
51	28.986712	30.652609	32.309170	33.955887	35.592262	37.217796	38.831993	40.434361
52	29.014551	30.680296	32.336697	33.983246	35.619446	37.244793	38.858799	40.460964
53	29.042387	30.707981	32.364220	34.010601	35.646626	37.271790	38.885597	40.487564
54	29.070219	30.735662	32.391743	34.037956	35.673801	37.298779	38.912395	40.514160
55	29.098051	30.763342	32.419262	34.065304	35.700974	37.325768	38.939190	40.540752
56	29.125879	30.791018	32.446777	34.092651	35.728142	37.352753	38.965981	40.567341
57	29.153708	30.818695	32.474293	34.119999	35.755314	37.379734	38.992771	40.593929
58	29.181532	30.846365	32.501804	34.147343	35.782478	37.406712	39.019554	40.620510
59	29.209352	30.874035	32.529312	34.174679	35.809639	37.433689	39.046337	40.647091
60	29.237171	30.901701	32.556816	34.202015	35.836796	37.460659	39.073112	40.673664

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	40.673664	42.261826	43.837116	45.399052	46.947159	48.480965	50.000000	51.503807
1	40.700237	42.288189	43.863258	45.424969	46.972839	48.506401	50.025192	51.528740
2	40.726807	42.314545	43.889397	45.450878	46.998516	48.531837	50.050377	51.553669
3	40.753372	42.340900	43.915531	45.476788	47.024189	48.557270	50.075558	51.578590
4	40.779934	42.367252	43.941666	45.502697	47.049862	48.582699	50.100735	51.603512
5	40.806492	42.393600	43.967796	45.528595	47.075527	48.608120	50.125908	51.628426
6	40.833046	42.419945	43.993919	45.554493	47.101189	48.633541	50.151077	51.653336
7	40.859600	42.446285	44.020039	45.580387	47.126846	48.658955	50.176239	51.678242
8	40.886147	42.472618	44.046154	45.606274	47.152500	48.684364	50.201397	51.703140
9	40.912689	42.498951	44.072269	45.632160	47.178150	48.709770	50.226555	51.728039
10	40.939232	42.525280	44.098377	45.658043	47.203796	48.735172	50.251705	51.752930
11	40.965767	42.551605	44.124481	45.683918	47.229439	48.760571	50.276852	51.777817
12	40.992306	42.577930	44.150589	45.709797	47.255077	48.785969	50.301998	51.802704
13	41.018837	42.604248	44.176685	45.735664	47.280712	48.811359	50.327137	51.827583
14	41.045364	42.630566	44.202778	45.761532	47.306343	48.836742	50.352268	51.852455
15	41.071888	42.656876	44.228870	45.787392	47.331966	48.862125	50.377399	51.877327
16	41.098408	42.683182	44.254955	45.813251	47.357590	48.887505	50.402523	51.902191
17	41.124924	42.709488	44.281040	45.839104	47.383205	48.912876	50.427647	51.927055
18	41.151436	42.735786	44.307117	45.864956	47.408821	48.938244	50.452763	51.951912
19	41.177948	42.762085	44.333199	45.890804	47.434433	48.963612	50.477879	51.976768
20	41.204453	42.788380	44.359268	45.916649	47.460041	48.988976	50.502987	52.001614
21	41.230957	42.814667	44.385338	45.942486	47.485641	49.014332	50.528091	52.026459
22	41.257458	42.840954	44.411400	45.968323	47.511238	49.039684	50.553192	52.051300
23	41.283951	42.867237	44.437462	45.994152	47.536831	49.065033	50.578285	52.076134
24	41.310444	42.893513	44.463520	46.019978	47.562420	49.090378	50.603378	52.100964
25	41.336933	42.919788	44.489571	46.045803	47.588009	49.115715	50.628464	52.125790
26	41.363419	42.946060	44.515621	46.071621	47.613590	49.141052	50.653545	52.150612
27	41.389900	42.972332	44.541668	46.097439	47.639168	49.166386	50.678627	52.175430
28	41.416378	42.998592	44.567711	46.123253	47.664742	49.191715	50.703701	52.200245
29	41.442856	43.024853	44.593750	46.149059	47.690311	49.217037	50.728771	52.225052
30	41.469326	43.051109	44.619781	46.174862	47.715878	49.242359	50.753838	52.249859
31	41.495792	43.077362	44.645813	46.200661	47.741440	49.267673	50.778900	52.274658
32	41.522259	43.103615	44.671841	46.226460	47.766994	49.292984	50.803955	52.299454
33	41.548717	43.129860	44.697861	46.252251	47.792549	49.318291	50.829010	52.324245
34	41.575176	43.156105	44.723885	46.278042	47.818100	49.343597	50.854061	52.349033
35	41.601631	43.182343	44.749901	46.303825	47.843647	49.368893	50.879105	52.373814
36	41.628082	43.208576	44.775909	46.329605	47.869186	49.394188	50.904144	52.398594
37	41.654526	43.234806	44.801918	46.355381	47.894726	49.419479	50.929180	52.423367
38	41.680969	43.261036	44.827923	46.381153	47.920258	49.444763	50.954208	52.448135
39	41.707409	43.287258	44.853924	46.406921	47.945786	49.470047	50.979237	52.472900
40	41.733845	43.313480	44.879917	46.432686	47.971313	49.495323	51.004261	52.497658
41	41.760277	43.339695	44.905910	46.458447	47.996834	49.520596	51.029278	52.522415
42	41.786709	43.365910	44.931904	46.484207	48.022350	49.545868	51.054295	52.547169
43	41.813133	43.392120	44.957886	46.509960	48.047863	49.571133	51.079304	52.571915
44	41.839558	43.418324	44.983868	46.535709	48.073372	49.596394	51.104309	52.596657
45	41.865974	43.444527	45.009846	46.561455	48.098877	49.621651	51.129311	52.621395
46	41.892391	43.470726	45.035820	46.587193	48.124378	49.646904	51.154308	52.646126
47	41.918800	43.496918	45.061787	46.612930	48.149876	49.672153	51.179298	52.670856
48	41.945210	43.523109	45.087753	46.638664	48.175369	49.697395	51.204288	52.695580
49	41.971615	43.549301	45.113720	46.664394	48.200859	49.722637	51.229275	52.720303
50	41.998016	43.575481	45.139679	46.690121	48.226341	49.747875	51.254253	52.745018
51	42.024414	43.601662	45.165630	46.715843	48.251823	49.773106	51.279228	52.769730
52	42.050804	43.627838	45.191582	46.741558	48.277298	49.798332	51.304199	52.794434
53	42.077194	43.654011	45.217529	46.767273	48.302773	49.823555	51.329163	52.819138
54	42.103580	43.680180	45.243473	46.792980	48.328239	49.848774	51.354126	52.843834
55	42.129963	43.706345	45.269409	46.818687	48.353703	49.873989	51.379082	52.868526
56	42.156345	43.732506	45.295345	46.844387	48.379162	49.899200	51.404037	52.893215
57	42.182724	43.758667	45.321281	46.870090	48.404621	49.924408	51.428989	52.917904
58	42.209095	43.784821	45.347206	46.895782	48.430073	49.949612	51.453934	52.942581
59	42.235462	43.810970	45.373131	46.921471	48.455521	49.974808	51.478874	52.967258
60	42.261826	43.837116	45.399052	46.947159	48.480965	50.000000	51.503807	52.991928

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	52.991928	54.463905	55.919292	57.357643	58.778526	60.181503	61.566151	62.932041
1	53.016594	54.488297	55.943405	57.381470	58.802055	60.204731	61.589069	62.954643
2	53.041256	54.512688	55.967514	57.405293	58.825584	60.227955	61.611984	62.977242
3	53.065914	54.537071	55.991615	57.429108	58.849102	60.251175	61.634892	62.999836
4	53.090565	54.561451	56.015717	57.452919	58.872620	60.274387	61.657795	63.022423
5	53.115211	54.585827	56.039810	57.476723	58.896130	60.297596	61.680695	63.045002
6	53.139858	54.610195	56.063900	57.500523	58.919636	60.320797	61.703587	63.067581
7	53.164497	54.634560	56.087982	57.524323	58.943134	60.343994	61.726475	63.090153
8	53.189137	54.658928	56.112068	57.548119	58.966637	60.367195	61.749363	63.112724
9	53.213768	54.683285	56.136143	57.571903	58.990128	60.390381	61.772240	63.135284
10	53.238392	54.707634	56.160213	57.595684	59.013615	60.413563	61.795113	63.157837
11	53.263012	54.731983	56.184280	57.619461	59.037094	60.436741	61.817982	63.180389
12	53.287628	54.756325	56.208340	57.643234	59.060570	60.459915	61.840843	63.202934
13	53.312241	54.780663	56.232395	57.667000	59.084042	60.483082	61.863697	63.225471
14	53.336849	54.804996	56.256447	57.690762	59.107506	60.506245	61.886551	63.248005
15	53.361454	54.829323	56.280495	57.714520	59.130966	60.529400	61.909397	63.270535
16	53.386051	54.853649	56.304535	57.738274	59.154423	60.552551	61.932236	63.293056
17	53.410645	54.877968	56.328571	57.762020	59.177872	60.575699	61.955074	63.315575
18	53.435234	54.902283	56.352604	57.785763	59.201317	60.598839	61.977905	63.338089
19	53.459820	54.926594	56.376633	57.809502	59.224758	60.621979	62.000729	63.360596
20	53.484402	54.950897	56.400654	57.833233	59.248196	60.645107	62.023548	63.383095
21	53.508976	54.975197	56.424675	57.856960	59.271626	60.668236	62.046364	63.405594
22	53.533546	54.999493	56.448685	57.880684	59.295052	60.691357	62.069172	63.428085
23	53.558121	55.023792	56.472702	57.904408	59.318478	60.714478	62.091984	63.450573
24	53.582684	55.048077	56.496704	57.928120	59.341892	60.737587	62.114780	63.473053
25	53.607243	55.072361	56.520702	57.951828	59.365303	60.760693	62.137577	63.495529
26	53.631794	55.096638	56.544697	57.975533	59.388710	60.783794	62.160362	63.517998
27	53.656342	55.120911	56.568687	57.999229	59.412109	60.806889	62.183147	63.540462
28	53.680889	55.145176	56.592670	58.022926	59.435505	60.829979	62.205925	63.562923
29	53.705425	55.169441	56.616650	58.046612	59.458893	60.853065	62.228699	63.585377
30	53.729961	55.193699	56.640625	58.070297	59.482281	60.876144	62.251465	63.607822
31	53.754494	55.217953	56.664597	58.093975	59.505661	60.899220	62.274227	63.630264
32	53.779018	55.242203	56.688560	58.117649	59.529037	60.922287	62.296986	63.652702
33	53.803539	55.266449	56.712521	58.141319	59.552406	60.945354	62.319736	63.675137
34	53.828056	55.290688	56.736477	58.164982	59.575771	60.968414	62.342484	63.697563
35	53.852570	55.314922	56.760429	58.188641	59.599133	60.991467	62.365223	63.719982
36	53.877079	55.339153	56.784374	58.212296	59.622486	61.014515	62.387959	63.742397
37	53.901581	55.363380	56.808315	58.235947	59.645836	61.037560	62.410690	63.764809
38	53.926086	55.387608	56.832256	58.259594	59.669186	61.060604	62.433418	63.787220
39	53.950581	55.411823	56.856190	58.283234	59.692528	61.083637	62.456139	63.809620
40	53.975067	55.436035	56.880116	58.306870	59.715862	61.106667	62.478855	63.832012
41	53.999554	55.460243	56.904037	58.330498	59.739193	61.129688	62.501564	63.854401
42	54.024036	55.484444	56.927956	58.354122	59.762516	61.152706	62.524269	63.876785
43	54.048512	55.508644	56.951866	58.377743	59.785835	61.175720	62.546967	63.899162
44	54.072983	55.532837	56.975777	58.401360	59.809151	61.198727	62.569660	63.921535
45	54.097450	55.557026	56.999676	58.424969	59.832462	61.221729	62.592350	63.943901
46	54.121910	55.581207	57.023575	58.448574	59.855766	61.244728	62.615032	63.966263
47	54.146370	55.605389	57.047470	58.472172	59.879066	61.267719	62.637711	63.988621
48	54.170822	55.629562	57.071358	58.495770	59.902359	61.290707	62.660381	64.010971
49	54.195271	55.653732	57.095242	58.519360	59.925652	61.313686	62.683048	64.033318
50	54.219715	55.677895	57.119118	58.542942	59.948933	61.336662	62.705711	64.055656
51	54.244152	55.702057	57.142994	58.566525	59.972214	61.359634	62.728367	64.077988
52	54.268589	55.726212	57.166862	58.590099	59.995487	61.382603	62.751019	64.100319
53	54.293022	55.750370	57.190731	58.613674	60.018761	61.405567	62.773670	64.122650
54	54.317448	55.774513	57.214592	58.637238	60.042027	61.428524	62.796310	64.144966
55	54.341869	55.798656	57.238445	58.660801	60.065285	61.451473	62.818943	64.167282
56	54.366287	55.822792	57.262295	58.684357	60.088539	61.474419	62.841576	64.189590
57	54.390697	55.846924	57.286140	58.707905	60.111790	61.497360	62.864201	64.211891
58	54.415104	55.871052	57.309978	58.731449	60.135033	61.520294	62.886818	64.234184
59	54.439507	55.895172	57.333817	58.754990	60.158272	61.543224	62.909431	64.256477
60	54.463905	55.919292	57.357643	58.778526	60.181503	61.566151	62.932041	64.278763

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	64.278763	65.605904	66.913063	68.199837	69.465836	70.710678	71.933983	73.135368
1	64.301041	65.627853	66.934677	68.221107	69.486763	70.731247	71.954185	73.155205
2	64.323318	65.649803	66.956284	68.242371	69.507675	70.751808	71.974380	73.175034
3	64.345589	65.671738	66.977890	68.263634	69.528587	70.772362	71.994576	73.194855
4	64.367851	65.693672	66.999481	68.284889	69.549492	70.792908	72.014755	73.214676
5	64.390106	65.715599	67.021072	68.306137	69.570389	70.813446	72.034935	73.234482
6	64.412361	65.737526	67.042664	68.327377	69.591278	70.833984	72.055107	73.254288
7	64.434608	65.759438	67.064240	68.348610	69.612167	70.854515	72.075279	73.274086
8	64.456856	65.781357	67.085823	68.369850	69.633049	70.875038	72.095444	73.293884
9	64.479095	65.803261	67.107391	68.391075	69.653923	70.895561	72.115601	73.313667
10	64.501328	65.825165	67.128952	68.412292	69.674797	70.916069	72.135750	73.333450
11	64.523552	65.847061	67.150513	68.433502	69.695656	70.936577	72.155891	73.353226
12	64.545769	65.868950	67.172058	68.454712	69.716515	70.957077	72.176025	73.372986
13	64.567986	65.890831	67.193611	68.475914	69.737366	70.977570	72.196159	73.392746
14	64.590195	65.912712	67.215149	68.497108	69.758209	70.998055	72.216278	73.412506
15	64.612396	65.934586	67.236679	68.518303	69.779045	71.018539	72.236397	73.432251
16	64.634598	65.956451	67.258209	68.539482	69.799881	71.039017	72.256508	73.451996
17	64.656792	65.978310	67.279732	68.560661	69.820709	71.059486	72.276619	73.471733
18	64.678978	66.000168	67.301254	68.581833	69.841530	71.079948	72.296715	73.491463
19	64.701164	66.022018	67.322762	68.603004	69.862343	71.100403	72.316811	73.511185
20	64.723335	66.043861	67.344269	68.624161	69.883156	71.120857	72.336899	73.530899
21	64.745506	66.065704	67.365768	68.645317	69.903961	71.141304	72.356979	73.550613
22	64.767677	66.087532	67.387268	68.666466	69.924759	71.161743	72.377052	73.570320
23	64.789841	66.109367	67.408760	68.687614	69.945549	71.182182	72.397125	73.590019
24	64.811996	66.131187	67.430244	68.708755	69.966339	71.202606	72.417191	73.609711
25	64.834145	66.153008	67.451721	68.729889	69.987114	71.223030	72.437248	73.629395
26	64.856285	66.174820	67.473190	68.751015	70.007889	71.243446	72.457298	73.649078
27	64.878426	66.196625	67.494659	68.772133	70.028656	71.263855	72.477341	73.668755
28	64.900558	66.218422	67.516121	68.793251	70.049423	71.284256	72.497383	73.688416
29	64.922684	66.240219	67.537575	68.814354	70.070175	71.304657	72.517410	73.708084
30	64.944809	66.262009	67.559021	68.835457	70.090927	71.325043	72.537437	73.727737
31	64.966919	66.283791	67.580467	68.856560	70.111671	71.345428	72.557457	73.747383
32	64.989037	66.305565	67.601906	68.877647	70.132408	71.365814	72.577469	73.767029
33	65.011139	66.327339	67.623337	68.898735	70.153145	71.386185	72.597481	73.786659
34	65.033241	66.349106	67.644760	68.919815	70.173866	71.406555	72.617485	73.806290
35	65.055336	66.370865	67.666183	68.940887	70.194588	71.426910	72.637474	73.825920
36	65.077423	66.392624	67.687599	68.961952	70.215302	71.447266	72.657463	73.845535
37	65.099503	66.414368	67.709007	68.983017	70.236015	71.467613	72.677452	73.865143
38	65.121590	66.436119	67.730415	69.004074	70.256721	71.487961	72.697433	73.884758
39	65.143661	66.457855	67.751808	69.025131	70.277420	71.508301	72.717400	73.904350
40	65.165726	66.479591	67.773201	69.046173	70.298111	71.528633	72.737366	73.923943
41	65.187790	66.501320	67.794586	69.067207	70.318794	71.548958	72.757324	73.943535
42	65.209846	66.523041	67.815971	69.088242	70.339470	71.569275	72.777275	73.963112
43	65.231895	66.544754	67.837341	69.109268	70.360146	71.589592	72.797226	73.982689
44	65.253937	66.566467	67.858711	69.130295	70.380814	71.609894	72.817162	74.002251
45	65.275978	66.588165	67.880074	69.151306	70.401474	71.630196	72.837097	74.021812
46	65.298012	66.609863	67.901436	69.172318	70.422127	71.650490	72.857025	74.041367
47	65.320038	66.631561	67.922783	69.193321	70.442780	71.670776	72.876945	74.060921
48	65.342064	66.653244	67.944130	69.214317	70.463425	71.691063	72.896866	74.080460
49	65.364075	66.674927	67.965469	69.235313	70.484062	71.711334	72.916771	74.099998
50	65.386093	66.696602	67.986809	69.256294	70.504692	71.731606	72.936676	74.119530
51	65.408096	66.718277	68.008133	69.277275	70.525314	71.751869	72.956573	74.139053
52	65.430099	66.739944	68.029457	69.298248	70.545937	71.772133	72.976463	74.158569
53	65.452095	66.761604	68.050781	69.319221	70.566551	71.792389	72.996353	74.178085
54	65.474083	66.783257	68.072090	69.340187	70.587158	71.812630	73.016228	74.197586
55	65.496071	66.804909	68.093399	69.361145	70.607765	71.832870	73.036102	74.217087
56	65.518044	66.826546	68.114693	69.382095	70.628357	71.853104	73.055969	74.236580
57	65.540016	66.848183	68.135986	69.403038	70.648949	71.873337	73.075829	74.256065
58	65.561989	66.869820	68.157280	69.423981	70.669533	71.893555	73.095680	74.275543
59	65.583946	66.891441	68.178558	69.444908	70.690109	71.913773	73.115532	74.295013
60	65.605904	66.913063	68.199837	69.465836	70.710678	71.933983	73.135368	74.314484

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 100-mm Sine-bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	74.314484	75.470963	76.604446	77.714600	78.801079	79.863556	80.901703	81.915207
1	74.333946	75.490044	76.623138	77.732903	78.818985	79.881058	80.918793	81.931885
2	74.353401	75.509117	76.641830	77.751198	78.836884	79.898552	80.935883	81.948563
3	74.372849	75.528183	76.660507	77.769485	78.854774	79.916039	80.952965	81.965225
4	74.392288	75.547241	76.679184	77.787766	78.872658	79.933525	80.970039	81.981888
5	74.411728	75.566299	76.697853	77.806046	78.890533	79.950996	80.987106	81.998543
6	74.431152	75.585350	76.716515	77.824318	78.908409	79.968468	81.004166	82.015190
7	74.450577	75.604385	76.735168	77.842575	78.926277	79.985931	81.021217	82.031830
8	74.470001	75.623428	76.753822	77.860840	78.944138	80.003387	81.038269	82.048462
9	74.489410	75.642456	76.772469	77.879089	78.961990	80.020836	81.055305	82.065086
10	74.508812	75.661484	76.791100	77.897331	78.979836	80.038277	81.072342	82.081711
11	74.528214	75.680496	76.809731	77.915565	78.997673	80.055710	81.089363	82.098320
12	74.547600	75.699509	76.828354	77.933800	79.015503	80.073143	81.106384	82.114922
13	74.566986	75.718513	76.846970	77.952019	79.033325	80.090561	81.123398	82.131523
14	74.586365	75.737511	76.865578	77.970238	79.051147	80.107979	81.140404	82.148109
15	74.605736	75.756500	76.884186	77.988449	79.068962	80.125381	81.157402	82.164696
16	74.625107	75.775482	76.902779	78.006653	79.086761	80.142784	81.174393	82.181274
17	74.644463	75.794464	76.921371	78.024849	79.104561	80.160179	81.191376	82.197845
18	74.663818	75.813431	76.939957	78.043045	79.122353	80.177567	81.208351	82.214401
19	74.683167	75.832397	76.958534	78.061226	79.140137	80.194946	81.225327	82.230957
20	74.702507	75.851357	76.977104	78.079399	79.157921	80.212318	81.242287	82.247513
21	74.721840	75.870308	76.995667	78.097572	79.175690	80.229683	81.259247	82.264053
22	74.741173	75.889259	77.014229	78.115738	79.193451	80.247047	81.276199	82.280586
23	74.760498	75.908203	77.032784	78.133896	79.211220	80.264404	81.293144	82.297119
24	74.779816	75.927132	77.051331	78.152054	79.228966	80.281754	81.310081	82.313637
25	74.799118	75.946060	77.069862	78.170197	79.246712	80.299088	81.327011	82.330154
26	74.818428	75.964981	77.088394	78.188332	79.264450	80.316422	81.343933	82.346664
27	74.837723	75.983894	77.106926	78.206467	79.282181	80.333748	81.360847	82.363159
28	74.857010	76.002800	77.125443	78.224586	79.299904	80.351067	81.377754	82.379654
29	74.876297	76.021706	77.143951	78.242706	79.317627	80.368385	81.394661	82.396141
30	74.895576	76.040596	77.162460	78.260818	79.335335	80.385689	81.411552	82.412621
31	74.914848	76.059486	77.180962	78.278923	79.353043	80.402985	81.428444	82.429092
32	74.934113	76.078369	77.199455	78.297020	79.370735	80.420280	81.445320	82.445557
33	74.953369	76.097244	77.217941	78.315109	79.388428	80.437561	81.462196	82.462013
34	74.972618	76.116112	77.236420	78.333199	79.406113	80.454842	81.479065	82.478470
35	74.991867	76.134972	77.254890	78.351273	79.423790	80.472115	81.495926	82.494911
36	75.011108	76.153831	77.273354	78.369347	79.441460	80.489380	81.512779	82.511353
37	75.030342	76.172684	77.291817	78.387413	79.459129	80.506638	81.529625	82.527779
38	75.049568	76.191528	77.310272	78.405472	79.476791	80.523895	81.546471	82.544205
39	75.068794	76.210365	77.328720	78.423523	79.494438	80.541138	81.563301	82.560623
40	75.088005	76.229195	77.347160	78.441566	79.512085	80.558372	81.580132	82.577034
41	75.107216	76.248016	77.365593	78.459610	79.529716	80.575607	81.596947	82.593437
42	75.126419	76.266838	77.384026	78.477638	79.547348	80.592827	81.613762	82.609833
43	75.145615	76.285645	77.402443	78.495667	79.564972	80.610046	81.630569	82.626221
44	75.164803	76.304451	77.420860	78.513680	79.582588	80.627258	81.647362	82.642601
45	75.183983	76.323250	77.439262	78.531693	79.600204	80.644463	81.664154	82.658974
46	75.203156	76.342041	77.457664	78.549698	79.617805	80.661659	81.680939	82.675346
47	75.222328	76.360825	77.476059	78.567696	79.635399	80.678848	81.697723	82.691704
48	75.241493	76.379601	77.494446	78.585693	79.652992	80.696030	81.714493	82.708061
49	75.260651	76.398376	77.512833	78.603676	79.670578	80.713211	81.731255	82.724403
50	75.279800	76.417145	77.531204	78.621651	79.688156	80.730377	81.748009	82.740746
51	75.298943	76.435898	77.549576	78.639626	79.705719	80.747543	81.764763	82.757080
52	75.318085	76.454651	77.567932	78.657593	79.723289	80.764694	81.781502	82.773399
53	75.337219	76.473404	77.586296	78.675552	79.740845	80.781853	81.798248	82.789726
54	75.356346	76.492142	77.604645	78.693504	79.758392	80.798988	81.814972	82.806038
55	75.375458	76.510880	77.622986	78.711449	79.775940	80.816124	81.831696	82.822342
56	75.394577	76.529602	77.641319	78.729393	79.793472	80.833252	81.848412	82.838638
57	75.413681	76.548325	77.659653	78.747322	79.811005	80.850380	81.865120	82.854927
58	75.432777	76.567039	77.677971	78.765244	79.828529	80.867493	81.881821	82.871216
59	75.451874	76.585747	77.696289	78.783165	79.846046	80.884598	81.898521	82.887489
60	75.470963	76.604446	77.714600	78.801079	79.863556	80.901703	81.915207	82.903755

Copyright 2004, Industrial Press, Inc., New York, NY

Accurate Measurement of Angles and Tapers

When great accuracy is required in the measurement of angles, or when originating tapers, disks are commonly used. The principle of the disk method of taper measurement is that if two disks of unequal diameters are placed either in contact or a certain distance apart, lines tangent to their peripheries will represent an angle or taper, the degree of which depends upon the diameters of the two disks and the distance between them.



The gage shown in the accompanying illustration, which is a form commonly used for originating tapers or measuring angles accurately, is set by means of disks. This gage consists of two adjustable straight edges A and A_1, which are in contact with disks B and B_1. The angle α or the taper between the straight edges depends, of course, upon the diameters of the disks and the center distance C, and as these three dimensions can be measured accurately, it is possible to set the gage to a given angle within very close limits. Moreover, if a record of the three dimensions is kept, the exact setting of the gage can be reproduced quickly at any time. The following rules may be used for adjusting a gage of this type, and cover all problems likely to arise in practice. Disks are also occasionally used for the setting of parts in angular positions when they are to be machined accurately to a given angle: the rules are applicable to these conditions also.

Measuring Dovetail Slides.— Dovetail slides that must be machined accurately to a given width are commonly gaged by using pieces of cylindrical rod or wire and measuring as indicated by the dimensions x and y of the accompanying illustrations.



The rod or wire used should be small enough so that the point of contact e is somewhat below the corner or edge of the dovetail.

To obtain dimension x for measuring male dovetails, add 1 to the cotangent of one-half the dovetail angle α, multiply by diameter D of the rods used, and add the product to dimension α.

$$x = D(1 + \cot \tfrac{1}{2}\alpha) + a \qquad c = h \times \cot \alpha$$

To obtain dimension y for measuring a female dovetail, add 1 to the cotangent of one-half the dovetail angle α, multiply by diameter D of the rod used, and subtract the result from dimension b. Expressing these rules as formulas:

$$y = b - D(1 + \cot \tfrac{1}{2}\alpha)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Tapers per Foot and Corresponding Angles

Taper per Foot	Included Angle				Angle with Center Line			Taper per Foot	Included Angle				Angle with Center Line		
1/64	0.149208°	0°	4′	29″	0°	2′	14″	1 7/8	9.230863°	8°	56′	4″	4°	28′	2″
1/32	0.298415	0	8	57	0	4	29	1 15/16	9.527283	9	13	51	4	36	56
1/16	0.447621	0	17	54	0	8	57	2	10.119738	9	31	38	4	45	49
3/32	0.596826	0	26	51	0	13	26	2 1/8	10.711650	10	7	11	5	3	36
1/8	0.746028	0	35	49	0	17	54	2 1/4	11.302990	10	42	42	5	21	21
5/32	0.895228	0	44	46	0	22	23	2 3/8	11.893726	11	18	11	5	39	5
3/16	1.044425	0	53	43	0	26	51	2 1/2	12.483829	11	53	37	5	56	49
7/32	1.193619	1	2	40	0	31	20	2 5/8	13.073267	12	29	2	6	14	31
1/4	1.342808	1	11	37	0	35	49	2 3/4	13.662012	13	4	24	6	32	12
9/32	1.491993	1	20	34	0	40	17	2 7/8	14.250033	13	39	43	6	49	52
5/16	1.641173	1	29	31	0	44	46	3	14.837300	14	15	0	7	7	30
11/32	1.790347	1	38	28	0	49	14	3 1/8	15.423785	14	50	14	7	25	7
3/8	1.939516	1	47	25	0	53	43	3 1/4	16.009458	15	25	26	7	42	43
13/32	2.088677	1	56	22	0	58	11	3 3/8	16.594290	16	0	34	8	0	17
7/16	2.237832	2	5	19	1	2	40	3 1/2	17.178253	16	35	39	8	17	50
15/32	2.386979	2	14	16	1	7	8	3 5/8	17.761318	17	10	42	8	35	21
1/2	2.536118	2	23	13	1	11	37	3 3/4	18.343458	17	45	41	8	52	50
17/32	2.685248	2	32	10	1	16	5	3 7/8	18.924644	18	20	36	9	10	18
9/16	2.834369	2	41	7	1	20	33	4	19.504850	18	55	29	9	27	44
19/32	2.983481	2	50	4	1	25	2	4 1/8	20.084047	19	30	17	9	45	9
5/8	3.132582	2	59	1	1	29	30	4 1/4	20.662210	20	5	3	10	2	31
21/32	3.281673	3	7	57	1	33	59	4 3/8	21.239311	20	39	44	10	19	52
11/16	3.430753	3	16	54	1	38	27	4 1/2	21.815324	21	14	22	10	37	11
23/32	3.579821	3	25	51	1	42	55	4 5/8	22.390223	21	48	55	10	54	28
3/4	3.728877	3	34	47	1	47	24	4 3/4	22.963983	22	23	25	11	11	42
25/32	3.877921	3	43	44	1	51	52	4 7/8	23.536578	22	57	50	11	28	55
13/16	4.026951	3	52	41	1	56	20	5	24.107983	23	32	12	11	46	6
27/32	4.175968	4	1	37	2	0	49	5 1/8	24.678175	24	6	29	12	3	14
7/8	4.324970	4	10	33	2	5	17	5 1/4	25.247127	24	40	41	12	20	21
29/32	4.473958	4	19	30	2	9	45	5 3/8	25.814817	25	14	50	12	37	25
15/16	4.622931	4	28	26	2	14	13	5 1/2	26.381221	25	48	53	12	54	27
31/32	4.771888	4	37	23	2	18	41	5 5/8	26.946316	26	22	52	13	11	26
1	5.069753	4	46	19	2	23	9	5 3/4	27.510079	26	56	47	13	28	23
1 1/16	5.367550	5	4	11	2	32	6	5 7/8	28.072487	27	30	36	13	45	18
1 1/8	5.665275	5	22	3	2	41	2	6	28.633518	28	4	21	14	2	10
1 3/16	5.962922	5	39	55	2	49	57	6 1/8	29.193151	28	38	1	14	19	0
1 1/4	6.260490	5	57	47	2	58	53	6 1/4	29.751364	29	11	35	14	35	48
1 5/16	6.557973	6	15	38	3	7	49	6 3/8	30.308136	29	45	5	14	52	32
1 3/8	6.855367	6	33	29	3	16	44	6 1/2	30.863447	30	18	29	15	9	15
1 7/16	7.152669	6	51	19	3	25	40	6 5/8	31.417276	30	51	48	15	25	54
1 1/2	7.449874	7	9	10	3	34	35	6 3/4	31.969603	31	25	2	15	42	31
1 9/16	7.746979	7	27	0	3	43	30	6 7/8	32.520409	31	58	11	15	59	5
1 5/8	8.043980	7	44	49	3	52	25	7	33.069676	32	31	13	16	15	37
1 11/16	8.340873	8	2	38	4	1	19	7 1/8	33.617383	33	4	11	16	32	5
1 3/4	8.637654	8	20	27	4	10	14	7 1/4	34.163514	33	37	3	16	48	31
1 13/16	0.149208	8	38	16	4	19	8	7 3/8	9.230863	34	9	49	17	4	54

Taper per foot represents inches of taper per foot of length. For conversions into decimal degrees and radians see *Conversion Tables of Angular Measure* on page 96.

Copyright 2004, Industrial Press, Inc., New York, NY

Rules for Figuring Tapers

Given	To Find	Rule
The taper per foot.	The taper per inch.	Divide the taper per foot by 12.
The taper per inch.	The taper per foot.	Multiply the taper per inch by 12.
End diameters and length of taper in inches.	The taper per foot.	Subtract small diameter from large; divide by length of taper; and multiply quotient by 12.
Large diameter and length of taper in inches, and taper per foot.	Diameter at small end in inches	Divide taper per foot by 12; multiply by length of taper; and subtract result from large diameter.
Small diameter and length of taper in inches, and taper per foot.	Diameter at large end in inches.	Divide taper per foot by 12; multiply by length of taper; and add result to small diameter.
The taper per foot and two diameters in inches.	Distance between two given diameters in inches.	Subtract small diameter from large; divide remainder by taper per foot; and multiply quotient by 12.
The taper per foot.	Amount of taper in a certain length in inches.	Divide taper per foot by 12; multiply by given length of tapered part.

To find angle α for given taper *T* in inches per foot.—



$$\alpha = 2\arctan(T/24)$$

Example: What angle α is equivalent to a taper of 1.5 inches per foot?

$$\alpha = 2 \times \arctan(1.5/24) = 7.153°$$

To find taper per foot *T* given angle α in degrees.—

$$T = 24\ \tan(\alpha/2) \text{ inches per foot}$$

Example: What taper *T* is equivalent to an angle of 7.153°?

$$T = 24\tan(7.153/2) = 1.5 \text{ inches per foot}$$

To find angle α given dimensions *D*, *d*, and *C*.— Let *K* be the difference in the disk diameters divided by twice the center distance. $K = (D - d)/(2C)$, then $\alpha = 2\arcsin K$

Example: If the disk diameters *d* and *D* are 1 and 1.5 inches, respectively, and the center distance *C* is 5 inches, find the included angle α.

$$K = (1.5 - 1)/(2 \times 5) = 0.05 \qquad \alpha = 2 \times \arcsin 0.05 = 5.732°$$

To find taper *T* measured at right angles to a line through the disk centers given dimensions *D*, *d*, and distance *C*.— Find *K* using the formula in the previous example, then $T = 24K/\sqrt{1 - K^2}$ inches per foot

Example: If disk diameters *d* and *D* are 1 and 1.5 inches, respectively, and the center distance *C* is 5 inches, find the taper per foot.

$$K = (1.5 - 1)/(2 \times 5) = 0.05 \qquad T = \frac{24 \times 0.05}{\sqrt{1 - (0.05)^2}} = 1.2015 \text{ inches per foot}$$

Copyright 2004, Industrial Press, Inc., New York, NY

To find center distance *C* for a given taper *T* in inches per foot.—

$$C = \frac{D-d}{2} \times \frac{\sqrt{1+(T/24)^2}}{T/24} \text{ inches}$$

Example: Gage is to be set to ¾ inch per foot, and disk diameters are 1.25 and 1.5 inches, respectively. Find the required center distance for the disks.

$$C = \frac{1.5-1.25}{2} \times \frac{\sqrt{1+(0.75/24)^2}}{0.75/24} = 4.002 \text{ inches}$$

To find center distance *C* for a given angle α and dimensions *D* and *d*.—

$$C = (D-d)/2\sin(\alpha/2) \text{ inches}$$

Example: If an angle α of 20° is required, and the disks are 1 and 3 inches in diameter, respectively, find the required center distance *C*.

$$C = (3-1)/(2 \times \sin 10°) = 5.759 \text{ inches}$$

To find taper *T* measured at right angles to one side .— When one side is taken as a base line and the taper is measured at right angles to that side, calculate *K* as explained above and use the following formula for determining the taper *T*:



$$T = 24K\frac{\sqrt{1-K^2}}{1-2K^2} \text{ inches per foot}$$

Example: If the disk diameters are 2 and 3 inches, respectively, and the center I distance is 5 inches, what is the taper per foot measured at right angles to one side?

$$K = \frac{3-2}{2\times 5} = 0.1 \qquad T = 24 \times 0.1 \times \frac{\sqrt{1-(0.1)^2}}{1-[2\times(0.1)^2]} = 2.4367 \text{ in. per ft.}$$

To find center distance *C* when taper *T* is measured from one side.—

$$C = \frac{D-d}{\sqrt{2-2/\sqrt{1+(T/12)^2}}} \text{ inches}$$

Example: If the taper measured at right angles to one side is 6.9 inches per foot, and the disks are 2 and 5 inches in diameter, respectively, what is center distance *C*?

$$C = \frac{5-2}{\sqrt{2-2/\sqrt{1+(6.9/12)^2}}} = 5.815 \text{ inches.}$$

To find diameter *D* of a large disk in contact with a small disk of diameter *d* given angle α.—



$$D = d \times \frac{1+\sin(\alpha/2)}{1-\sin(\alpha/2)} \text{ inches}$$

Example: The required angle α is 15°. Find diameter *D* of a large disk that is in contact with a standard 1-inch reference disk.

Copyright 2004, Industrial Press, Inc., New York, NY

$$D = 1 \times \frac{1 + \sin 7.5°}{1 - \sin 7.5°} = 1.3002 \text{ inches}$$

Measurement over Pins and Rolls

Measurement over Pins.— When the distance across a bolt circle is too large to measure using ordinary measuring tools, then the required distance may be found from the distance across adacent or alternate holes using one of the methods that follow:



Fig. 1a.



Fig. 1b.



Fig. 1c.

Even Number of Holes in Circle: To measure the unknown distance x over opposite plugs in a bolt circle of n holes (n is even and greater than 4), as shown in Fig. 1a, where y is the distance over alternate plugs, d is the diameter of the holes, and $\theta = 360°/n$ is the angle between adjacent holes, use the following general equation for obtaining x:

$$x = \frac{y - d}{\sin\theta} + d$$

Example: In a die that has six 3/4-inch diameter holes equally spaced on a circle, where the distance y over alternate holes is 4½ inches, and the angle θ between adjacent holes is 60°, then

$$x = \frac{4.500 - 0.7500}{\sin 60°} + 0.7500 = 5.0801$$

In a similar problem, the distance c over adjacent plugs is given, as shown in Fig. 1b. If the number of holes is even and greater than 4, the distance x over opposite plugs is given in the following formula:

$$x = 2(c - d)\left(\frac{\sin\left(\frac{180 - \theta}{2}\right)}{\sin\theta}\right) + d$$

where d and θ are as defined above.

Odd Number of Holes in Circle: In a circle as shown in Fig. 1c, where the number of holes n is odd and greater than 3, and the distance c over adjacent holes is given, then θ equals $360/n$ and the distance x across the most widely spaced holes is given by:

$$x = \frac{\frac{c - d}{2}}{\sin\frac{\theta}{4}} + d$$

Checking a V-shaped Groove by Measurement Over Pins.— In checking a groove of the shape shown in Fig. 2, it is necessary to measure the dimension X over the pins of radius R. If values for the radius R, dimension Z, and the angles α and β are known, the problem is

Copyright 2004, Industrial Press, Inc., New York, NY

to determine the distance *Y*, to arrive at the required overall dimension for *X*. If a line *AC* is drawn from the bottom of the V to the center of the pin at the left in Fig. 2, and a line *CB* from the center of this pin to its point of tangency with the side of the V, a right-angled triangle is formed in which one side, *CB*, is known and one angle *CAB*, can be determined. A line drawn from the center of a circle to the point of intersection of two tangents to the circle bisects the angle made by the tangent lines, and angle *CAB* therefore equals $\frac{1}{2}(\alpha + \beta)$. The length *AC* and the angle *DAC* can now be found, and with *AC* known in the right-angled triangle *ADC*, *AD*, which is equal to *Y* can be found.



Fig. 2.

The value for *X* can be obtained from the formula

$$X = Z + 2R\left(\csc\frac{\alpha+\beta}{2}\cos\frac{\alpha-\beta}{2} + 1\right)$$

For example, if $R = 0.500$, $Z = 1.824$, $\alpha = 45$ degrees, and $\beta = 35$ degrees,

$$X = 1.824 + (2 \times 0.5)\left(\csc\frac{45° + 35°}{2}\cos\frac{45° - 35°}{2} + 1\right)$$

$$X = 1.824 + \csc 40° \cos 5° + 1$$

$$X = 1.824 + 1.5557 \times 0.99619 + 1$$

$$X = 1.824 + 1.550 + 1 = 4.374$$

Checking Radius of Arc by Measurement Over Rolls.— The radius *R* of large-radius concave and convex gages of the type shown in Figs. 3a, 3b and 3c can be checked by measurement *L* over two rolls with the gage resting on the rolls as shown. If the diameter of the rolls *D*, the length *L*, and the height *H* of the top of the arc above the surface plate (for the concave gage, Fig. 3a) are known or can be measured, the radius *R* of the workpiece to be checked can be calculated trigonometrically, as follows.

Referring to Fig. 3a for the concave gage, if *L* and *D* are known, *cb* can be found, and if *H* and *D* are known, *ce* can be found. With *cb* and *ce* known, *ab* can be found by means of a diagram as shown in Fig. 3c.

In diagram Fig. 3c, *cb* and *ce* are shown at right angles as in Fig. 3a. A line is drawn connecting points *b* and *e* and line *ce* is extended to the right. A line is now drawn from point *b* perpendicular to *be* and intersecting the extension of *ce* at point *f*. A semicircle can now be drawn through points *b*, *e*, and *f* with point *a* as the center. Triangles *bce* and *bcf* are similar and have a common side. Thus *ce*:*bc*::*bc*:*cf*. With *ce* and *bc* known, *cf* can be found from this proportion and hence *ef* which is the diameter of the semicircle and radius *ab*. Then $R = ab + D/2$.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3a.



Fig. 3b.



Fig. 3c.

The procedure for the convex gage is similar. The distances *cb* and *ce* are readily found and from these two distances *ab* is computed on the basis of similar triangles as before. Radius *R* is then readily found.

The derived formulas for concave and convex gages are as follows:

Formulas:

$$R = \frac{(L-D)^2}{8(H-D)} + \frac{H}{2} \qquad \text{(Concave gage Fig. 3a)}$$

$$R = \frac{(L-D)^2}{8D} \qquad \text{(Convex gage Fig. 3b)}$$

For example: For Fig. 3a, let $L = 17.8$, $D = 3.20$, and $H = 5.72$, then

$$R = \frac{(17.8-3.20)^2}{8(5.72-3.20)} + \frac{5.72}{2} = \frac{(14.60)^2}{8 \times 2.52} + 2.86$$

$$R = \frac{213.16}{20.16} + 2.86 = 13.43$$

For Fig. 3b, let $L = 22.28$ and $D = 3.40$, then

$$R = \frac{(22.28-3.40)^2}{8 \times 3.40} = \frac{356.45}{27.20} = 13.1$$

Checking Shaft Conditions

Checking for Various Shaft Conditions.— An indicating height gage, together with V-blocks can be used to check shafts for ovality, taper, straightness (bending or curving), and concentricity of features (as shown exaggerated in Fig. 4). If a shaft on which work has

Copyright 2004, Industrial Press, Inc., New York, NY

been completed shows lack of concentricity. it may be due to the shaft having become bent or bowed because of mishandling or oval or tapered due to poor machine conditions. In checking for concentricity, the first step is to check for ovality, or out-of-roundness, as in Fig. 4a. The shaft is supported in a suitable V-block on a surface table and the dial indicator plunger is placed over the workpiece, which is then rotated beneath the plunger to obtain readings of the amount of eccentricity.

This procedure (sometimes called clocking, owing to the resemblance of the dial indicator to a clock face) is repeated for other shaft diameters as necessary, and, in addition to making a written record of the measurements, the positions of extreme conditions should be marked on the workpiece for later reference.



Fig. 4.

To check for taper, the shaft is supported in the V-block and the dial indicator is used to measure the maximum height over the shaft at various positions along its length, as shown in Fig. 4b, without turning the workpiece. Again, the shaft should be marked with the reading positions and values, also the direction of the taper, and a written record should be made of the amount and direction of any taper discovered.

Checking for a bent shaft requires that the shaft be clocked at the shoulder and at the farther end, as shown in Fig. 4c. For a second check the shaft is rotated only 90° or a quarter turn. When the recorded readings are compared with those from the ovality and taper checks, the three conditions can be distinguished.

Copyright 2004, Industrial Press, Inc., New York, NY

To detect a curved or bowed condition, the shaft should be suspended in two V-blocks with only about ⅛ inch of each end in each vee. Alternatively, the shaft can be placed between centers. The shaft is then clocked at several points, as shown in Fig. 4d, but preferably not at those locations used for the ovality, taper, or crookedness checks. If the single element due to curvature is to be distinguished from the effects of ovality, taper, and crookedness, and its value assessed, great care must be taken to differentiate between the conditions detected by the measurements.

Finally, the amount of eccentricity between one shaft diameter and another may be tested by the setup shown in Fig. 4e. With the indicator plunger in contact with the smaller diameter, close to the shoulder, the shaft is rotated in the V-block and the indicator needle position is monitored to find the maximum and minimum readings.

Curvature, ovality, or crookedness conditions may tend to cancel each other, as shown in Fig. 5, and one or more of these degrees of defectiveness may add themselves to the true eccentricity readings, depending on their angular positions. Fig. 5a shows, for instance, how crookedness and ovality tend to cancel each other, and also shows their effect in falsifying the reading for eccentricity. As the same shaft is turned in the V-block to the position shown in Fig. 5b, the maximum curvature reading could tend to cancel or reduce the maximum eccentricity reading. Where maximum readings for ovality, curvature, or crookedness occur at the same angular position, their values should be subtracted from the eccentricity reading to arrive at a true picture of the shaft condition. Confirmation of eccentricity readings may be obtained by reversing the shaft in the V-block, as shown in Fig. 5c, and clocking the larger diameter of the shaft.



Fig. 5.

Out-of-Roundness—Lobing.— With the imposition of finer tolerances and the development of improved measurement methods, it has become apparent that no hole,' cylinder, or sphere can be produced with a perfectly symmetrical round shape. Some of the conditions are diagrammed in Fig. 6, where Fig. 6a shows simple ovality and Fig. 6b shows ovality occurring in two directions. From the observation of such conditions have come the terms lobe and lobing. Fig. 6c shows the three-lobed shape common with centerless-ground components, and Fig. 6d is typical of multi-lobed shapes. In Fig. 6e are shown surface waviness, surface roughness, and out-of-roundness, which often are combined with lobing.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6.

In Figs. 6a through 6d, the cylinder (or hole) diameters are shown at full size but the lobes are magnified some 10,000 times to make them visible. In precision parts, the deviation from the round condition is usually only in the range of millionths of an inch, although it occasionally can be 0.0001 inch, 0.0002 inch, or more. For instance, a 3-inch-diameter part may have a lobing condition amounting to an inaccuracy of only 30 millionths (0.000030 inch). Even if the distortion (ovality, waviness, roughness) is small, it may cause hum, vibration, heat buildup, and wear, possibly leading to eventual failure of the component or assembly.

Plain elliptical out-of-roundness (two lobes), or any even number of lobes, can be detected by rotating the part on a surface plate under a dial indicator of adequate resolution, or by using an indicating caliper or snap gage. However, supporting such a part in a V-block during measurement will tend to conceal roundness errors. Ovality in a hole can be detected by a dial-type bore gage or internal measuring machine. Parts with odd numbers of lobes require an instrument that can measure the envelope or complete circumference. Plug and ring gages will tell whether a shaft can be assembled into a bearing, but not whether there will be a good fit, as illustrated in Fig. 6e.

A standard, 90-degree included-angle V-block can be used to detect and count the number of lobes, but to measure the exact amount of lobing indicated by *R*-*r* in Fig. 7 requires a V-block with an angle α, which is related to the number of lobes. This angle α can be calculated from the formula $2\alpha = 180° - 360°/N$, where N is the number of lobes. Thus, for a three-lobe form, α becomes 30 degrees, and the V-block used should have a 60-degree included angle. The distance M, which is obtained by rotating the part under the comparator plunger, is converted to a value for the radial variation in cylinder contour by the formula $M = (R - r)(1 + \csc \alpha)$.



Fig. 7.

Using a V-block (even of appropriate angle) for parts with odd numbers of lobes will give exaggerated readings when the distance $R - r$ (Fig. 7) is used as the measure of the amount of out-of-roundness. The accompanying table shows the appropriate V-block angles for various odd numbers of lobes, and the factors $(1 + \csc \alpha)$ by which the readings are increased over the actual out-of-roundness values.

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Lobes, V-block Angles and Exaggeration Factors in Measuring Out-of-round Conditions in Shafts

Number of Lobes	Included Angle of V-block (deg)	Exaggeration Factor $(1 + \csc \alpha)$
3	60	3.00
5	108	2.24
7	128.57	2.11
9	140	2.06

Measurement of a complete circumference requires special equipment, often incorporating a precision spindle running true within two millionths (0.000002) inch. A stylus attached to the spindle is caused to traverse the internal or external cylinder being inspected, and its divergences are processed electronically to produce a polar chart similar to the wavy outline in Fig. 6e. The electronic circuits provide for the variations due to surface effects to be separated from those of lobing and other departures from the "true" cylinder traced out by the spindle.

Measurements Using Light

Measuring by Light-wave Interference Bands.— Surface variations as small as two millionths (0.000002) inch can be detected by light-wave interference methods, using an optical flat. An optical flat is a transparent block, usually of plate glass, clear fused quartz, or borosilicate glass, the faces of which are finished to extremely fine limits (of the order of 1 to 8 millionths [0.000001 to 0.000008] inch, depending on the application) for flatness. When an optical flat is placed on a "flat" surface, as shown in Fig. 8, any small departure from flatness will result in formation of a wedge-shaped layer of air between the work surface and the underside of the flat.

Light rays reflected from the work surface and the underside of the flat either interfere with or reinforce each other. Interference of two reflections results when the air gap measures exactly half the wavelength of the light used, and produces a dark band across the work surface when viewed perpendicularly, under monochromatic helium light. A light band is produced halfway between the dark bands when the rays reinforce each other. With the 0.0000232-inch-wavelength helium light used, the dark bands occur where the optical flat and the work surface are separated by 11.6 millionths (0.0000116) inch, or multiples thereof.



Fig. 8.

For instance, at a distance of seven dark bands from the point of contact, as shown in Fig. 8, the underface of the optical flat is separated from the work surface by a distance of 7 × 0.0000116 inch or 0.0000812 inch. The bands are separated more widely and the indications become increasingly distorted as the viewing angle departs from the perpendicular. If the bands appear straight, equally spaced and parallel with each other, the work surface is flat. Convex or concave surfaces cause the bands to curve correspondingly, and a cylindrical tendency in the work surface will produce unevenly spaced, straight bands.

Copyright 2004, Industrial Press, Inc., New York, NY

SURFACE TEXTURE

American National Standard Surface Texture (Surface Roughness, Waviness, and Lay)

American National Standard ANSI/ASME B46.1-1995 is concerned with the geometric irregularities of surfaces of solid materials, physical specimens for gaging roughness, and the characteristics of stylus instrumentation for measuring roughness. The standard defines surface texture and its constituents: roughness, waviness, lay, and flaws. A set of symbols for drawings, specifications, and reports is established. To ensure a uniform basis for measurements the standard also provides specifications for Precision Reference Specimens, and Roughness Comparison Specimens, and establishes requirements for stylus-type instruments. The standard is not concerned with luster, appearance, color, corrosion resistance, wear resistance, hardness, subsurface microstructure, surface integrity, and many other characteristics that may be governing considerations in specific applications.

The standard is expressed in SI metric units but U.S. customary units may be used without prejudice. The standard does not define the degrees of surface roughness and waviness or type of lay suitable for specific purposes, nor does it specify the means by which any degree of such irregularities may be obtained or produced. However, criteria for selection of surface qualities and information on instrument techniques and methods of producing, controlling and inspecting surfaces are included in Appendixes attached to the standard. The Appendix sections are not considered a part of the standard: they are included for clarification or information purposes only.

Surfaces, in general, are very complex in character. The standard deals only with the height, width, and direction of surface irregularities because these characteristics are of practical importance in specific applications. Surface texture designations as delineated in this standard may not be a sufficient index to performance. Other part characteristics such as dimensional and geometrical relationships, material, metallurgy, and stress must also be controlled.

Definitions of Terms Relating to the Surfaces of Solid Materials.— The terms and ratings in the standard relate to surfaces produced by such means as abrading, casting, coating, cutting, etching, plastic deformation, sintering, wear, and erosion.

Error of form is considered to be that deviation from the nominal surface caused by errors in machine tool ways, guides, insecure clamping or incorrect alignment of the workpiece or wear, all of which are not included in surface texture. Out-of-roundness and out-of-flatness are examples of errors of form. See ANSI/ASME B46.3.1-1988 for measurement of out-of-roundness.

Flaws are unintentional, unexpected, and unwanted interruptions in the topography typical of a part surface and are defined as such only when agreed upon by buyer and seller. If flaws are defined, the surface should be inspected specifically to determine whether flaws are present, and rejected or accepted prior to performing final surface roughness measurements. If defined flaws are not present, or if flaws are not defined, then interruptions in the part surface may be included in roughness measurements.

Lay is the direction of the predominant surface pattern, ordinarily determined by the production method used.

Roughness consists of the finer irregularities of the surface texture, usually including those irregularities that result from the inherent action of the production process. These irregularities are considered to include traverse feed marks and other irregularities within the limits of the roughness sampling length.

Surface is the boundary of an object that separates that object from another object, substance or space.

Surface, measured is the real surface obtained by instrumental or other means.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Pictorial Display of Surface Characteristics

Surface, nominal is the intended surface contour (exclusive of any intended surface roughness), the shape and extent of which is usually shown and dimensioned on a drawing or descriptive specification.

Surface, real is the actual boundary of the object. Manufacturing processes determine its deviation from the nominal surface.

Surface texture is repetitive or random deviations from the real surface that forms the three-dimensional topography of the surface. Surface texture includes roughness, waviness, lay and flaws. Fig. 1 is an example of a unidirectional lay surface. Roughness and waviness parallel to the lay are not represented in the expanded views.

Waviness is the more widely spaced component of surface texture. Unless otherwise noted, waviness includes all irregularities whose spacing is greater than the roughness sampling length and less than the waviness sampling length. Waviness may result from

Copyright 2004, Industrial Press, Inc., New York, NY

such factors as machine or work deflections, vibration, chatter, heat-treatment or warping strains. Roughness may be considered as being superposed on a 'wavy' surface.

Definitions of Terms Relating to the Measurement of Surface Texture.— Terms regarding surface texture pertain to the geometric irregularities of surfaces and include roughness, waviness and lay.

Profile is the contour of the surface in a plane measured normal, or perpendicular, to the surface, unless another other angle is specified.

Graphical centerline. See Mean Line.

Height (z) is considered to be those measurements of the profile in a direction normal, or perpendicular, to the nominal profile. For digital instruments, the profile Z(x) is approximated by a set of digitized values. Height parameters are expressed in micrometers (μm).

Height range (z) is the maximum peak-to-valley surface height that can be detected accurately with the instrument. It is measurement normal, or perpendicular, to the nominal profile and is another key specification.

Mean line (M) is the line about which deviations are measured and is a line parallel to the general direction of the profile within the limits of the sampling length. See Fig. 2. The mean line may be determined in one of two ways. The filtered mean line is the centerline established by the selected cutoff and its associated circuitry in an electronic roughness average measuring instrument. The least squares mean line is formed by the nominal profile but by dividing into selected lengths the sum of the squares of the deviations minimizes the deviation from the nominal form. The form of the nominal profile could be a curve or a straight line.

Peak is the point of maximum height on that portion of a profile that lies above the mean line and between two intersections of the profile with the mean line.

Profile measured is a representation of the real profile obtained by instrumental or other means. When the measured profile is a graphical representation, it will usually be distorted through the use of different vertical and horizontal magnifications but shall otherwise be as faithful to the profile as technically possible.

Profile, modified is the measured profile where filter mechanisms (including the instrument datum) are used to minimize certain surface texture characteristics and emphasize others. Instrument users apply profile modifications typically to differentiate surface roughness from surface waviness.

Profile, nominal is the profile of the nominal surface; it is the intended profile (exclusive of any intended roughness profile). Profile is usually drawn in an x-z coordinate system. See Fig. 2.



Fig. 2. Nominal and Measured Profiles

Profile, real is the profile of the real surface.

Profile, total is the measured profile where the heights and spacing may be amplified differently but otherwise no filtering takes place.

Roughness profile is obtained by filtering out the longer wavelengths characteristic of waviness.

Roughness spacing is the average spacing between adjacent peaks of the measured profile within the roughness sampling length.

Copyright 2004, Industrial Press, Inc., New York, NY

Roughness topography is the modified topography obtained by filtering out the longer wavelengths of waviness and form error.

Sampling length is the nominal spacing within which a surface characteristic is determined. The range of sampling lengths is a key specification of a measuring instrument.

Spacing is the distance between specified points on the profile measured parallel to the nominal profile.

Spatial (x) resolution is the smallest wavelength which can be resolved to 50% of the actual amplitude. This also is a key specification of a measuring instrument.

System height resolution is the minimum height that can be distinguished from background noise of the measurement instrument. Background noise values can be determined by measuring approximate rms roughness of a sample surface where actual roughness is significantly less than the background noise of the measuring instrument. It is a key instrumentation specification.

Topography is the three-dimensional representation of geometric surface irregularities.

Topography, measured is the three-dimensional representation of geometric surface irregularities obtained by measurement.

Topography, modified is the three-dimensional representation of geometric surface irregularities obtained by measurement but filtered to minimize certain surface characteristics and accentuate others.

Valley is the point of maximum depth on that portion of a profile that lies below the mean line and between two intersections of the profile with the mean line.

Waviness, evaluation length (L), is the length within which waviness parameters are determined.

Waviness, long-wavelength cutoff (lcw) the spatial wavelength above which the undulations of waviness profile are removed to identify form parameters. A digital Gaussian filter can be used to separate form error from waviness but its use must be specified.

Waviness profile is obtained by filtering out the shorter roughness wavelengths characteristic of roughness and the longer wavelengths associated with the part form parameters.

Waviness sampling length is a concept no longer used. See waviness long-wavelength cutoff and waviness evaluation length.

Waviness short-wavelength cutoff (lsw) is the spatial wavelength below which roughness parameters are removed by electrical or digital filters.

Waviness topography is the modified topography obtained by filtering out the shorter wavelengths of roughness and the longer wavelengths associated with form error.

Waviness spacing is the average spacing between adjacent peaks of the measured profile within the waviness sampling length.

Sampling Lengths.— Sampling length is the normal interval for a single value of a surface parameter. Generally it is the longest spatial wavelength to be included in the profile measurement. Range of sampling lengths is an important specification for a measuring instrument.



Fig. 3. Traverse Length

Roughness sampling length (l) is the sampling length within which the roughness average is determined. This length is chosen to separate the profile irregularities which are des-

Copyright 2004, Industrial Press, Inc., New York, NY

ignated as roughness from those irregularities designated as waviness. It is different from evaluation length (L) and the traversing length. See Fig. 3.

Evaluation length (L) is the length the surface characteristics are evaluated. The evaluation length is a key specification of a measuring instrument.

Traversing length is profile length traversed to establish a representative evaluation length. It is always longer than the evaluation length. See Section 4.4.4 of ANSI/ASME B46.1-1995 for values which should be used for different type measurements.

Cutoff is the electrical response characteristic of the measuring instrument which is selected to limit the spacing of the surface irregularities to be included in the assessment of surface texture. Cutoff is rated in millimeters. In most electrical averaging instruments, the cutoff can be user selected and is a characteristic of the instrument rather than of the surface being measured. In specifying the cutoff, care must be taken to choose a value which will include all the surface irregularities to be assessed.

Waviness sampling length (l) is a concept no longer used. See waviness long-wavelength cutoff and waviness evaluation length.

Roughness Parameters.— Roughness is the fine irregularities of the surface texture resulting from the production process or material condition.

Roughness average (Ra), also known as arithmetic average (AA) is the arithmetic average of the absolute values of the measured profile height deviations divided by the evaluation length, L. This is shown as the shaded area of Fig. 4 and generally includes sampling lengths or cutoffs. For graphical determinations of roughness average, the height deviations are measured normal, or perpendicular, to the chart center line.



Fig. 4.

Roughness average is expressed in micrometers (μm). A micrometer is one millionth of a meter (0.000001 meter). A microinch (μin) is one millionth of an inch (0.000001 inch). One microinch equals 0.0254 micrometer (1 μin. = 0.0254 μm).

Roughness Average Value (Ra) From Continuously Averaging Meter Reading may be made of readings from stylus-type instruments of the continuously averaging type. To ensure uniform interpretation, it should be understood that the reading that is considered significant is the mean reading around which the needle tends to dwell or fluctuate with a small amplitude.

Roughness is also indicated by the root-mean-square (rms) average, which is the square root of the average value squared, within the evaluation length and measured from the mean line shown in Fig. 4, expressed in micrometers. A roughness-measuring instrument calibrated for rms average usually reads about 11 per cent higher than an instrument calibrated for arithmetical average. Such instruments usually can be recalibrated to read arithmetical average. Some manufacturers consider the difference between rms and AA to be small enough that rms on a drawing may be read as AA for many purposes.

Roughness evaluation length (L), for statistical purposes should, whenever possible, consist of five sampling lengths (l). Use of other than five sampling lengths must be clearly indicated.

Copyright 2004, Industrial Press, Inc., New York, NY

Waviness Parameters.— Waviness is the more widely spaced component of surface texture. Roughness may be thought of as superimposed on waviness.

Waviness height (Wt) is the peak-to-valley height of the modified profile with roughness and part form errors removed by filtering, smoothing or other means. This value is typically three or more times the roughness average. The measurement is taken normal, or perpendicular, to the nominal profile within the limits of the waviness sampling length.

Waviness evaluation length (Lw) is the evaluation length required to determine waviness parameters. For waviness, the sampling length concept is no longer used. Rather, only waviness evaluation length (*Lw*) and waviness long-wavelength cutoff (*lew*) are defined. For better statistics, the waviness evaluation length should be several times the waviness long-wavelength cutoff.

Relation of Surface Roughness to Tolerances.— Because the measurement of surface roughness involves the determination of the average linear deviation of the measured surface from the nominal surface, there is a direct relationship between the dimensional tolerance on a part and the permissible surface roughness. It is evident that a requirement for the accurate measurement of a dimension is that the variations introduced by surface roughness should not exceed the dimensional tolerances. If this is not the case, the measurement of the dimension will be subject to an uncertainty greater than the required tolerance, as illustrated in Fig. 5.



Fig. 5.

The standard method of measuring surface roughness involves the determination of the average deviation from the mean surface. On most surfaces the total profile height of the surface roughness (peak-to-valley height) will be approximately four times (4×) the measured average surface roughness. This factor will vary somewhat with the character of the surface under consideration, but the value of four may be used to establish approximate profile heights.

From these considerations it follows that if the arithmetical average value of surface roughness specified on a part exceeds one eighth of the dimensional tolerance, the whole tolerance will be taken up by the roughness height. In most cases, a smaller roughness specification than this will be found; but on parts where very small dimensional tolerances are given, it is necessary to specify a suitably small surface roughness so useful dimensional measurements can be made. The tables on pages pages 652 and 679 show the relations between machining processes and working tolerances.

Values for surface roughness produced by common processing methods are shown in Table 1. The ability of a processing operation to produce a specific surface roughness depends on many factors. For example, in surface grinding, the final surface depends on the peripheral speed of the wheel, the speed of the traverse, the rate of feed, the grit size, bonding material and state of dress of the wheel, the amount and type of lubrication at the

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Surface Roughness Produced by Common Production Methods



point of cutting, and the mechanical properties of the piece being ground. A small change in any of the above factors can have a marked effect on the surface produced.

Instrumentation for Surface Texture Measurement.— Instrumentation used for measurement of surface texture, including roughness and waviness generally falls into six types. These include:

Type I, Profiling Contact Skidless Instruments: Used for very smooth to very rough surfaces. Used for roughness and may measure waviness. Can generate filtered or unfiltered profiles and may have a selection of filters and parameters for data analysis. Examples include: 1) skidless stylus-type with LVDT (linear variable differential transformer) vertical transducers; 2) skidless-type using an interferometric transducer; 3)skidless stylus-type using capacitance transducer.

Type II, Profiling Non-contact Instruments: Capable of full profiling or topographical analysis. Non-contact operation may be advantageous for softness but may vary with sample type and reflectivity. Can generate filtered or unfiltered profiles but may have difficulty with steeply inclined surfaces. Examples include: 1) interferometric microscope; 2) optical focus sending; 3) Nomarski differential profiling; 4) laser triangulation; 5) scanning electron microscope (SEM) stereoscopy; 6) confocal optical microscope.

Type III, Scanned Probe Microscope: Feature high spatial resolution (at or near the atomic scale) but area of measurement may be limited. Examples include: 1) scanning tunneling microscope (STM) and 2) atomic force microscope (AFM).

Copyright 2004, Industrial Press, Inc., New York, NY

Type IV, Profiling Contact Skidded Instruments: Uses a skid as a datum to eliminate longer wavelengths; thus cannot be used for waviness or errors of form. May have a selection of filters and parameters and generates an output recording of filtered and skid-modified profiles. Examples include: 1) skidded, stylus-type with LVDT vertical measuring transducer and 2) fringe-field capacitance (FFC) transducer.

Type V, Skidded Instruments with Parameters Only: Uses a skid as a datum to eliminate longer wavelengths; thus cannot be used for waviness or errors of form. Does not generate a profile. Filters are typically 2RC type and generate Ra but other parameters may be available. Examples include: 1) skidded, stylus-type with piezoelectric measuring transducer and 2) skidded, stylus-type with moving coil measuring transducer.

Type VI, Area Averaging Methods: Used to measure averaged parameters over defined areas but do not generate profiles. Examples include: 1) parallel plate capacitance (PPC) method; 2) total integrated scatter (TIS); 3) angle resolved scatter (ARS)/bi-directional reflectance distribution function (BRDF).

Selecting Cutoff for Roughness Measurements.— In general, surfaces will contain irregularities with a large range of widths. Surface texture instruments are designed to respond only to irregularity spacings less than a given value, called cutoff. In some cases, such as surfaces in which actual contact area with a mating surface is important, the largest convenient cutoff will be used. In other cases, such as surfaces subject to fatigue failure only the irregularities of small width will be important, and more significant values will be obtained when a short cutoff is used. In still other cases, such as identifying chatter marks on machined surfaces, information is needed on only the widely space irregularities. For such measurements, a large cutoff value and a larger radius stylus should be used.

The effect of variation in cutoff can be understood better by reference to Fig. 6. The profile at the top is the true movement of a stylus on a surface having a roughness spacing of about 1 mm and the profiles below are interpretations of the same surface with cutoff value settings of 0.8 mm, 0.25 mm and 0.08 mm, respectively. It can be seen that the trace based on 0.8 mm cutoff includes most of the coarse irregularities and all of the fine irregularities of the surface. The trace based on 0.25 mm excludes the coarser irregularities but includes the fine and medium fine. The trace based on 0.08 mm cutoff includes only the very fine irregularities. In this example the effect of reducing the cutoff has been to reduce the roughness average indication. However, had the surface been made up only of irregularities as fine as those of the bottom trace, the roughness average values would have been the same for all three cutoff settings.

In other words, all irregularities having a spacing less than the value of the cutoff used are included in a measurement. Obviously, if the cutoff value is too small to include coarser irregularities of a surface, the measurements will not agree with those taken with a larger cutoff. For this reason, care must be taken to choose a cutoff value which will include all of the surface irregularities it is desired to assess.

To become proficient in the use of continuously averaging stylus-type instruments the inspector or machine operator must realize that for uniform interpretation, the reading which is considered significant is the mean reading around which the needle tends to dwell or fluctuate under small amplitude.

Drawing Practices for Surface Texture Symbols.— American National Standard ANSI/ASME Y14.36M-1996 establishes the method to designate symbolic controls for surface texture of solid materials. It includes methods for controlling roughness, waviness, and lay, and provides a set of symbols for use on drawings, specifications, or other documents. The standard is expressed in SI metric units but U.S. customary units may be used without prejudice. Units used (metric or non-metric) should be consistent with the other units used on the drawing or documents. Approximate non-metric equivalents are shown for reference.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6. Effects of Various Cutoff Values

Surface Texture Symbol.— The symbol used to designate control of surface irregularities is shown in Fig. 7b and Fig. 7d. Where surface texture values other than roughness average are specified, the symbol must be drawn with the horizontal extension as shown in Fig. 7f.

Use of Surface Texture Symbols: When required from a functional standpoint, the desired surface characteristics should be specified. Where no surface texture control is specified, the surface produced by normal manufacturing methods is satisfactory provided it is within the limits of size (and form) specified in accordance with ANSI/ASME Y14.5M-1994, Dimensioning and Tolerancing. It is considered good practice to always specify some maximum value, either specifically or by default (for example, in the manner of the note shown in Fig. 2).

Material Removal Required or Prohibited: The surface texture symbol is modified when necessary to require or prohibit removal of material. When it is necessary to indicate that a surface must be produced by removal of material by machining, specify the symbol shown in Fig. 7b. When required, the amount of material to be removed is specified as shown in Fig. 7c, in millimeters for metric drawings and in inches for non-metric drawings. Tolerance for material removal may be added to the basic value shown or specified in a general note. When it is necessary to indicate that a surface must be produced without material removal, specify the machining prohibited symbol as shown in Fig. 7d.

Proportions of Surface Texture Symbols: The recommended proportions for drawing the surface texture symbol are shown in Fig. 7f. The letter height and line width should be the same as that for dimensions and dimension lines.

Copyright 2004, Industrial Press, Inc., New York, NY

Surface Texture Symbols and Construction

Symbol	Meaning
Fig. 7a.	Basic Surface Texture Symbol. Surface may be produced by any method except when the bar or circle (Fig. 7b or 7d) is specified.
Fig. 7b.	Material Removal By Machining Is Required. The horizontal bar indicates that material removal by machining is required to produce the surface and that material must be provided for that purpose.
Fig. 7c.	Material Removal Allowance. The number indicates the amount of stock to be removed by machining in millimeters (or inches). Tolerances may be added to the basic value shown or in general note.
Fig. 7d.	Material Removal Prohibited. The circle in the vee indicates that the surface must be produced by processes such as casting, forging, hot finishing, cold finishing, die casting, powder metallurgy or injection molding without subsequent removal of material.
Fig. 7e.	Surface Texture Symbol. To be used when any surface characteristics are specified above the horizontal line or the right of the symbol. Surface may be produced by any method except when the bar or circle (Fig. 7b and 7d) is specified.



Fig. 7f.

Applying Surface Texture Symbols.— The point of the symbol should be on a line representing the surface, an extension line of the surface, or a leader line directed to the surface, or to an extension line. The symbol may be specified following a diameter dimension. Although ANSI/ASME Y14.5M-1994, "Dimensioning and Tolerancing" specifies that normally all textual dimensions and notes should be read from the bottom of the drawing, the surface texture symbol itself with its textual values may be rotated as required. Regardless, the long leg (and extension) must be to the right as the symbol is read. For parts requiring extensive and uniform surface roughness control, a general note may be added to the drawing which applies to each surface texture symbol specified without values as shown in Fig. 8.

When the symbol is used with a dimension, it affects the entire surface defined by the dimension. Areas of transition, such as chamfers and fillets, shall conform with the roughest adjacent finished area unless otherwise indicated.

Surface texture values, unless otherwise specified, apply to the complete surface. Drawings or specifications for plated or coated parts shall indicate whether the surface texture values apply before plating, after plating, or both before and after plating.

Only those values required to specify and verify the required texture characteristics should be included in the symbol. Values should be in metric units for metric drawing and non-metric units for non-metric drawings. Minority units on dual dimensioned drawings are enclosed in brackets.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. Application of Surface Texture Symbols

Roughness and waviness measurements, unless otherwise specified, apply in a direction which gives the maximum reading; generally across the lay.

Cutoff or Roughness Sampling Length, (l): Standard values are listed in Table 2. When no value is specified, the value 0.8 mm (0.030 in.) applies.

Table 2. Standard Roughness Sampling Length (Cutoff) Values

mm	in.	mm	in.
0.08	0.003	2.5	0.1
0.25	0.010	8.0	0.3
0.80	0.030	25.0	1.0

Roughness Average (Ra): The preferred series of specified roughness average values is given in Table 3.

Table 3. Preferred Series Roughness Average Values (R_a)

µm	µin	µm	µin	µm	µin
0.012	0.5	0.40[a]	16[a]	4.0	160
0.025[a]	1[a]	0.50	20	5.0	200
0.050[a]	2[a]	0.63	25	6.3[a]	250[a]
0.075[a]	3	0.80[a]	32[a]	8.0	320
0.10[a]	4[a]	1.00	40	10.0	400
0.125	5	1.25	50	12.5[a]	500[a]
0.15	6	1.60[a]	63[a]	15	600
0.20[a]	8[a]	2.0	80	20	800
0.25	10	2.5	100	25[a]	1000[a]
0.32	13	3.2[a]	125[a]	…	…

[a] Recommended

Copyright 2004, Industrial Press, Inc., New York, NY

Waviness Height (Wt): The preferred series of maximum waviness height values is listed in Table 3. Waviness height is not currently shown in U.S. or ISO Standards. It is included here to follow present industry practice in the United States.

Table 4. Preferred Series Maximum Waviness Height Values

mm	in.	mm	in.	mm	in.
0.0005	0.00002	0.008	0.0003	0.12	0.005
0.0008	0.00003	0.012	0.0005	0.20	0.008
0.0012	0.00005	0.020	0.0008	0.25	0.010
0.0020	0.00008	0.025	0.001	0.38	0.015
0.0025	0.0001	0.05	0.002	0.50	0.020
0.005	0.0002	0.08	0.003	0.80	0.030

Lay: Symbols for designating the direction of lay are shown and interpreted in Table 5.

Example Designations.— Table 6 illustrates examples of designations of roughness, waviness, and lay by insertion of values in appropriate positions relative to the symbol.

Where surface roughness control of several operations is required within a given area, or on a given surface, surface qualities may be designated, as in Fig. 9a. If a surface must be produced by one particular process or a series of processes, they should be specified as shown in Fig. 9b. Where special requirements are needed on a designated surface, a note should be added at the symbol giving the requirements and the area involved. An example is illustrated in Fig. 9c.

Surface Texture of Castings.— Surface characteristics should not be controlled on a drawing or specification unless such control is essential to functional performance or appearance of the product. Imposition of such restrictions when unnecessary may increase production costs and in any event will serve to lessen the emphasis on the control specified for important surfaces. Surface characteristics of castings should never be considered on the same basis as machined surfaces. Castings are characterized by random distribution of non-directional deviations from the nominal surface.

Surfaces of castings rarely need control beyond that provided by the production method necessary to meet dimensional requirements. Comparison specimens are frequently used for evaluating surfaces having specific functional requirements. Surface texture control should not be specified unless required for appearance or function of the surface. Specification of such requirements may increase cost to the user.

Engineers should recognize that different areas of the same castings may have different surface textures. It is recommended that specifications of the surface be limited to defined areas of the casting. Practicality of and methods of determining that a casting's surface texture meets the specification shall be coordinated with the producer. The Society of Automotive Engineers standard J435 "Automotive Steel Castings" describes methods of evaluating steel casting surface texture used in the automotive and related industries.

Metric Dimensions on Drawings.— The length units of the metric system that are most generally used in connection with any work relating to mechanical engineering are the meter (39.37 inches) and the millimeter (0.03937 inch). One meter equals 1000 millimeters. On mechanical drawings, all dimensions are generally given in millimeters, no matter how large the dimensions may be. In fact, dimensions of such machines as locomotives and large electrical apparatus are given exclusively in millimeters. This practice is adopted to avoid mistakes due to misplacing decimal points, or misreading dimensions as when other units are used as well. When dimensions are given in millimeters, many of them can be given without resorting to decimal points, as a millimeter is only a little more than $\frac{1}{32}$ inch. Only dimensions of precision need be given in decimals of a millimeter; such dimensions are generally given in hundredths of a millimeter—for example, 0.02 millimeter,

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Lay Symbols

Lay Symbol	Meaning	Example Showing Direction of Tool Marks
=	Lay approximately parallel to the line representing the surface to which the symbol is applied.	
⊥	Lay approximately perpendicular to the line representing the surface to which the symbol is applied.	
X	Lay angular in both directions to line representing the surface to which the symbol is applied.	
M	Lay multidirectional	
C	Lay approximately circular relative to the center of the surface to which the symbol is applied.	
R	Lay approximately radial relative to the center of the surface to which the symbol is applied.	
P	Lay particulate, non-directional, or protuberant	

which is equal to 0.0008 inch. As 0.01 millimeter is equal to 0.0004 inch, dimensions are seldom given with greater accuracy than to hundredths of a millimeter.

Scales of Metric Drawings: Drawings made to the metric system are not made to scales of $\frac{1}{2}$, $\frac{1}{4}$, $\frac{1}{8}$, etc., as with drawings made to the English system. If the object cannot be drawn full size, it may be drawn $\frac{1}{2}$, $\frac{1}{5}$, $\frac{1}{10}$, $\frac{1}{20}$, $\frac{1}{50}$, $\frac{1}{100}$, $\frac{1}{200}$, $\frac{1}{500}$, or $\frac{1}{1000}$ size. If the object is too small and has to be drawn larger, it is drawn 2, 5, or 10 times its actual size.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Application of Surface Texture Values to Symbol

1.6	Roughness average rating is placed at the left of the long leg. The specification of only one rating shall indicate the maximum value and any lesser value shall be acceptable. Specify in micrometers (microinch).	1.6 3.5	Material removal by machining is required to produce the surface. The basic amount of stock provided forf material removal is specified at the left of the short leg of the symbol. Specify in millimeters (inch).
1.6 0.8	The specification of maximum and minimum roughness average values indicates permissible range of roughness. Specify in micrometers (microinch).	1.6	Removal of material is prohibited.
0.005-5 0.8	Maximum waviness height rating is the first rating place above the horizontal extension. Any lesser rating shall be acceptable. Specify in millimeters (inch). Maximum waviness spacing rating is the second rating placed above the horizontal extension and to the right of the waviness height rating. Any lesser rating shall be acceptable. Specify in millimeters (inch).	0.8 ⊥	Lay designation is indicated by the lay symbol placed at the right of the long leg.
		0.8 2.5	Roughness sampling length or cutoff rating is placed below the horizontal extension. When no value is shown, 0.80 mm (0.030 inch) applies. Specify in millimeters (inch).
		0.8 ⊥ 0.5	Where required maximum roughness spacing shall be placed at the right of the lay symbol. Any lesser rating shall be acceptable. Specify in millimeters (inch).

Table 7. Examples of Special Designations



Fig. 9a.



Fig. 9b.



Fig. 9c.

Copyright 2004, Industrial Press, Inc., New York, NY

ISO Surface Finish

Differences Between ISO and ANSI Surface Finish Symbology.— ISO surface finish standards are comprised of numerous individual standards that taken as a whole form a set of standards roughly comparable in scope to American National Standard ANSI/ASME Y14.36M.

The primary standard dealing with surface finish, ISO 1302:1992, is concerned with the methods of specifying surface texture symbology and additional indications on engineering drawings. The parameters in ISO surface finish standards relate to surfaces produced by abrading, casting, coating, cutting, etching, plastic deformation, sintering, wear, erosion, and some other methods.

ISO 1302 defines how surface texture and its constituents, roughness, waviness, and lay, are specified on the symbology. Surface defects are specifically excluded from consideration during inspection of surface texture, but definitions of flaws and imperfections are discussed in ISO 8785.

As with American National Standard ASME Y14.36M, ISO 1302 is not concerned with luster, appearance, color, corrosion resistance, wear resistance, hardness, sub-surface microstructure, surface integrity, and many other characteristics that may govern considerations in specific applications. Visually, the ISO surface finish symbol is similar to the ANSI symbol, but the proportions of the symbol in relationship to text height differs from ANSI, as do some of the parameters as described in Fig. 10. Examples of the application of the ISO surface finish symbol are illustrated in Table 10.

The ISO 1302 standard does not define the degrees of surface roughness and waviness or type of lay for specific purposes, nor does it specify the means by which any degree of such irregularities may be obtained or produced. Also, errors of form such as out-of-roundness and out-of-flatness are not addressed in the ISO surface finish standards.

Other ISO Standards Related To Surface Finish

ISO 468:1982	"Surface roughness — parameters. Their values and general rules for specifying requirements."
ISO 4287:1997	"Surface texture: Profile method — Terms, definitions and surface texture parameters."
ISO 4288:1996	"Surface texture: Profile method — Rules and procedures for the assessment of surface texture." Includes specifications for precision reference specimens, and roughness comparison specimens, and establishes requirements for stylus-type instruments."
ISO 8785:1998	"Surface imperfections — Terms, definitions and parameters."
ISO 10135-1:CD	"Representation of parts produced by shaping processes — Part 1: Molded parts."

Rules for Comparing Measured Values to Specified Limits.— *Max rule:* When a maximum requirement is specified for a surface finish parameter on a drawing (e.g. *Rz*1.5max), none of the inspected values may extend beyond the upper limit over the entire surface. MAX must be added to the parametric symbol in the surface finish symbology on the drawing.

16% rule: When upper and lower limits are specified, no more than 16% of all measured values of the selected parameter within the evaluation length may exceed the upper limit. No more than 16% of all measured values of the selected parameter within the evaluation length may be less than the lower limit.

Copyright 2004, Industrial Press, Inc., New York, NY



Text height **h** (ISO 3098-1)	2.5	3.5	5	7	10	14	20
Line width for symbols **d** and **d'**	0.25	0.35	0.5	0.7	1	1.2	2
Height for segment **x**	3.5	5	7	10	14	20	28
Height for symbol segment **x'**	8	11	15	21	30	42	60

Fig. 10. ISO Surface Finish Symbol

ISO Surface Parameter Symbols

Rp = max height profile	*Rδc* = profile section height difference
Rv = max profile valley depth	*Ip* = sampling length – primary profile
*Rz** = max height of the profile	*lw* = sampling length – waviness profile
Rc = mean height of profile	*lr* = sampling length – roughness profile
Rt = total height of the profile	*ln* = evaluation length
Ra = arithmetic mean deviation of the profile	*Z(x)* = ordinate value
Rq = root mean square deviation of the profile	*dZ/dX* = local slope
Rsk = skewness of the profile	*Zp* = profile peak height
Rku = kurtosis of the profile	*Zv* = profile valley depth
RSm = mean width of the profile	*Zt* = profile element height
RΔq = root mean square slope of the profile	*Xs* = profile element width
Rmr = material ration of the profile	*Ml* = material length of profile

Exceptions to the 16% rule: Where the measured values of roughness profiles being inspected follow a normal distribution, the 16% rule may be overridden. This is allowed when greater than 16% of the measured values exceed the upper limit, but the total roughness profile conforms with the sum of the arithmetic mean and standard deviation ($\mu + \sigma$). Effectively this means that the greater the value of σ, the further μ must be from the upper limit (see Fig. 11).

Basic rules for determining cut-off wavelength: When the sampling length is specified on the drawing or in documentation, the cut-off wavelength λc is equal to the sample length. When no sampling length is specified, the cut-off wavelength is estimated using Table 8.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 11.

Basic rules for measurement of roughness parameters: For non-periodic roughness the parameter $Ra, Rz, Rz1_{max}$ or RSm are first estimated using visual inspection, comparison to specimens, graphic analysis, etc. The sampling length is then selected from Table 8, based on the use of $Ra, Rz, Rz1_{max}$ or RSm. Then with instrumentation, a representative sample is taken using the sampling length chosen above.

Table 8. Sampling Lengths

Curves for Non-periodic Profiles such as Ground Surfaces		Curves for Periodic and Non-periodic Profiles	Sampling length, lr (mm)	Evaluation length, ln (mm)
For $Ra, Rq, Rsk, Rku, R\Delta q$	For Rz, Rv, Rp, Rc, Rt	For R-parameters and RSm		
Ra, μm	$Rz, Rz1_{max}$, μm	RSm, μm		
$(0.006) < Ra \le 0.02$	$(0.025) < Rz, Rz1_{max} \le 0.1$	$0.013 < RSm \le 0.04$	0.08	0.4
$0.02 < Ra \le 0.1$	$0.1 < Rz, Rz1_{max} \le 0.5$	$0.04 < RSm \le 0.13$	0.25	1.25
$0.1 < Ra \le 2$	$0.5 < Rz, Rz1_{max} \le 10$	$0.13 < RSm \le 0.4$	0.8	4
$2 < Ra \le 10$	$10 < Rz, Rz1_{max} \le 50$	$0.4 < RSm \le 1.3$	2.5	12.5
$10 < Ra \le 80$	$50 < Rz, Rz1_{max} \le 200$	$1.3 < RSm \le 4$	8	40

The measured values are then compared to the ranges of values in Table 8 for the particular parameter. If the value is outside the range of values for the estimated sampling length, the measuring instrument is adjusted for the next higher or lower sampling length and the measurement repeated. If the final setting corresponds to Table 8, then both the sampling length setting and $Ra, Rz, Rz1_{max}$ or RSm values are correct and a representative measurement of the parameter can be taken.

For periodic roughness, the parameter RSm is estimated graphically and the recommended cut-off values selected using Table 8. If the value is outside the range of values for the estimated sampling length, the measuring instrument is adjusted for the next higher or lower sampling length and the measurement repeated. If the final setting corresponds to Table 8, then both the sampling length setting and RSm values are correct and a representative measurement of the parameter can be taken.

Table 9. Preferred Roughness Values and Roughness Grades

Roughness values, Ra		Previous Grade Number from ISO 1302	Roughness values, Ra		Previous Grade Number from ISO 1302
μm	μin		μm	μin	
50	2000	N12	0.8	32	N6
25	1000	N11	0.4	16	N5
12.5	500	N10	0.2	8	N4
6.3	250	N9	0.1	4	N3
3.2	125	N8	0.05	2	N2
1.6	63	N7	0.025	1	N1

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Examples of ISO Applications of Surface Texture Symbology

Interpretation	Example
Surface roughness is produced by milling and between upper limit of *Ra* = 50 µm and *Ra* = 6.3 µm; direction of lay is crossed in oblique directions relative to plane of projection; sampling length is 5 mm.	
Surface roughness of *Rz* = 6.3 µm is the default for all surfaces as indicated by the *Rz* = 6.3 specification, plus basic symbol within parentheses. Any deviating specification is called out with local notes such as the *Ra* = 0.8 µm specification.	
Surface roughness is produced by grinding to *Ra* = 1.2 µm and limited to Ry = 6.3 µm max; direction of lay is perpendicular relative to the plane of projection; sampling length is 2.4 mm.	
Surface treatment without any machining; nickel-chrome plated to *Rz* = 1 µm on all surfaces.	
Surface is nickel-chrome plated to roughness of *Ra* = 3.2 µm with a sampling length of 0.8 mm; limited to *Rz* = 16 µm to *Rz* = 6.3 µm with a sampling length of 2.5 mm.	
Surface roughness of *Rz* = 6.3 µm is the default for all surfaces except the inside diameter which is *Ra* = 0.8 mm.	
Surface texture symbology may be combined with dimension leaders and witness (extension) lines.	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **Examples of ISO Applications of Surface Texture Symbology**

Interpretation	Example
Surface texture symbology may be applied to extended extension lines or on extended projection lines.	
Surface roughness is produced by milling and between upper limit of Ra = 50 µm and Ra = 6.3 µm; direction of lay is crossed in oblique directions relative to plane of projection; sampling length is 5 mm.	
Surface treatment without any machining; nickel-chrome plated to Rz = 1 µm on all surfaces.	
Surface texture characteristics may be specified both before and after surface treatment.	
The symbol may be expanded with additional lines for textual information where there is insufficient room on the drawing.	

Copyright 2004, Industrial Press, Inc., New York, NY

Gage Blocks

Precision Gage Blocks.— Precision gage blocks are usually purchased in sets comprising a specific number of blocks of different sizes. The nominal gage lengths of individual blocks in a set are determined mathematically so that particular desired lengths can be obtained by combining selected blocks. They are made to several different tolerance grades which categorize them as master blocks, calibration blocks, inspection blocks, and workshop blocks. *Master blocks* are employed as basic reference standards; *calibration blocks* are used for high precision gaging work and calibrating inspection blocks; *inspection blocks* are used as toolroom standards and for checking and setting limit and comparator gages, for example. The *workshop blocks* are working gages used as shop standards for a variety of direct precision measurements and gaging applications, including sine-bar settings.

Federal Specification GGG-G-15C, Gage Blocks (see below), lists typical sets, and gives details of materials, design, and manufacturing requirements, and tolerance grades. When there is in a set no single block of the exact size that is wanted, two or more blocks are combined by "wringing" them together. Wringing is achieved by first placing one block crosswise on the other and applying some pressure. Then a swiveling motion is used to twist the blocks to a parallel position, causing them to adhere firmly to one another.

When combining blocks for a given dimension, the object is to use as few blocks as possible to obtain the dimension. The procedure for selecting blocks is based on successively eliminating the right-hand figure of the desired dimension.

Example: Referring to gage block set number 1 in Table 1, determine the blocks required to obtain 3.6742 inches. *Step 1:* Eliminate 0.0002 by selecting a 0.1002 block. Subtract 0.1002 from 3.6743 = 3.5740. *Step 2:* Eliminate 0.004 by selecting a 0.124 block. Subtract 0.124 from 3.5740 = 3.450. *Step 3:* Eliminate 0.450 with a block this size. Subtract 0.450 from 3.450 = 3.000. *Step 4:* Select a 3.000 inch block. The combined blocks are 0.1002 + 0.124 + 0.450 + 3.000 = 3.6742 inches.

Federal Specification for Gage Blocks, Inch and Metric Sizes.— This Specification, GGG-G-15C, March 20, 1975, which supersedes GGG-G-15B, November 6, 1970, covers design, manufacturing, and purchasing details for precision gage blocks in inch and metric sizes up to and including 20 inches and 500 millimeters gage lengths. The shapes of blocks are designated Style 1, which is rectangular; Style 2, which is square with a center accessory hole, and Style 3, which defines other shapes as may be specified by the purchaser. Blocks may be made from steel, chromium-plated steel, chromium carbide, or tungsten carbide. There are four tolerance grades, which are designated Grade 0.5 (formerly Grade AAA in the GGG-G-15A issue of the Specification); Grade 1 (formerly Grade AA); Grade 2 (formerly Grade A +); and Grade 3 (a compromise between former Grades A and B). Grade 0.5 blocks are special reference gages used for extremely high precision gaging work, and are not recommended for general use. Grade 1 blocks are laboratory reference standards used for calibrating inspection gage blocks and high precision gaging work. Grade 2 blocks are used as inspection and toolroom standards, and Grade 3 blocks are used as shop standards.

Inch and metric sizes of blocks in specific sets are given in Tables 1 and 2, which is not a complete list of available sizes. It should be noted that some gage blocks must be ordered as specials, some may not be available in all materials, and some may not be available from all manufacturers. Gage block set number 4 (88 blocks), listed in the Specification, is not given in Table 1. It is the same as set number 1 (81 blocks) but contains seven additional blocks measuring 0.0625, 0.078125, 0.093750, 0.100025, 0.100050, 0.100075, and 0.109375 inch. In Table 2, gage block set number 3M (112 blocks) is not given. It is similar to set number 2M (88 blocks), and the chief difference is the inclusion of a larger number of blocks in the 0.5 millimeter increment series up to 24.5 mm. Set numbers 5M (88 blocks), 6M (112 blocks), and 7M (17 blocks) also are not listed.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Gage Block Sets—Inch Sizes *Federal Specification GGG-G-15C*

Set Number 1 (81 Blocks)									
First Series: 0.0001 Inch Increments (9 Blocks)									
.1001	.1002	.1003	.1004	.1005	.1006	.1007	.1008	.1009	
Second Series: 0.001 Inch Increments (49 Blocks)									
.101	.102	.103	.104	.105	.106	.107	.108	.109	.110
.111	.112	.113	.114	.115	.116	.117	.118	.119	.120
.121	.122	.123	.124	.125	.126	.127	.128	.129	.130
.131	.132	.133	.134	.135	.136	.137	.138	.139	.140
.141	.142	.143	.144	.145	.146	.147	.148	.149	
Third Series: 0.050 Inch Increments (19 Blocks)									
.050	.100	.150	.200	.250	.300	.350	.400	.450	.500
.550	.600	.650	.700	.750	.800	.850	.900	.950	
Fourth Series: 1.000 Inch Increments (4 Blocks)									
	1.000			2.000		3.000		4.000	
Set Number 5 (21 Blocks)									
First Series: 0.0001 Inch Increments (9 Blocks)									
.0101	.0102	.0103	.0104	.0105	.0106	.0107	.0108	.0109	
Second Series: 0.001 Inch Increments (11 Blocks)									
.010	.011	.012	.013	.014	.015	.016	.017	.018	.019	.020
One Block 0.01005 Inch									
Set Number 6 (28 Blocks)									
First Series: 0.0001 Inch Increments (9 Blocks)									
.0201	.0202	.0203	.0204	.0205	.0206	.0207	.0208	.0209	
Second Series: 0.001 Inch Increments (9 Blocks)									
.021	.022	.023	.024	.025	.026	.027	.028	.029	
Third Series: 0.010 Inch Increments (9 Blocks)									
.010	.020	.030	.040	.050	.060	.070	.080	.090	
One Block 0.02005 Inch									
Long Gage Block Set Number 7 (8 Blocks)									
Whole Inch Series (8 Blocks)									
5		6	7	8	10	12	16	20	
Set Number 8 (36 Blocks)									
First Series: 0.0001 Inch Increments (9 Blocks)									
.1001	.1002	.1003	.1004	.1005	.1006	.1007	.1008	.1009	
Second Series: 0.001 Inch Increments (11 Blocks)									
.100	.101	.102	.103	.104	.105	.106	.107	.108	.109	.110
Third Series: 0.010 Inch Increments (8 Blocks)									
.120	.130	.140	.150	.160	.170	.180	.190		
Fourth Series: 0.100 Inch Increments (4 Blocks)									
	.200		.300	.400		.500			
Whole Inch Series (3 Blocks)									
	1		2			4			
One Block 0.050 Inch									
Set Number 9 (20 Blocks)									
First Series: 0.0001 Inch Increments (9 Blocks)									
.0501	.0502	.0503	.0504	.0505	.0506	.0507	.0508	.0509	
Second Series: 0.001 Inch Increments (10 Blocks)									
.050	.051	.052	.053	.054	.055	.056	.057	.058	.059
One Block 0.05005 Inch									

Set number 4 is not shown, and the Specification does not list a set 2 or 3.
Arranged here in incremental series for convenience of use.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Gage Block Sets—Metric Sizes *Federal Specification GGG-G-15C*

Set Number 1M (45 Blocks)								
First Series: 0.001 Millimeter Increments (9 Blocks)								
1.001	1.002	1.003	1.004	1.005	1.006	1.007	1.008	1.009
Second Series: 0.01 Millimeter Increments (9 Blocks)								
1.01	1.02	1.03	1.04	1.05	1.06	1.07	1.08	1.09
Third Series: 0.10 Millimeter Increments (9 Blocks)								
1.10	1.20	1.30	1.40	1.50	1.60	1.70	1.80	1.90
Fourth Series: 1.0 Millimeter Increments (9 Blocks)								
1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0
Fifth Series: 10 Millimeter Increments (9 Blocks)								
10	20	30	40	50	60	70	80	90
Set Number 2M (88 Blocks)								
First Series: 0.001 Millimeter Increments (9 Blocks)								
1.001	1.002	1.003	1.004	1.005	1.006	1.007	1.008	1.009
Second Series: 0.01 Millimeter Increments (49 Blocks)								
1.01	1.02	1.03	1.04	1.05	1.06	1.07	1.08	1.09	1.10
1.11	1.12	1.13	1.14	1.15	1.16	1.17	1.18	1.19	1.20
1.21	1.22	1.23	1.24	1.25	1.26	1.27	1.28	1.29	1.30
1.31	1.32	1.33	1.34	1.35	1.36	1.37	1.38	1.39	1.40
1.41	1.42	1.43	1.44	1.45	1.46	1.47	1.48	1.49	
Third Series: 0.50 Millimeter Increments (19 Blocks)									
0.5	1.0	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0
5.5	6.0	6.5	7.0	7.5	8.0	8.5	9.0	9.5	
Fourth Series: 10 Millimeter Increments (10 Blocks)									
10	20	30	40	50	60	70	80	90	100
One Block 1.0005 mm									
Set Number 4M (45 Blocks)									
First Series: 0.001 Millimeter Increments (9 Blocks)									
2.001	2.002	2.003	2.004	2.005	2.006	2.007	2.008	2.009	
Second Series: 0.01 Millimeter Increments (9 Blocks)									
2.01	2.02	2.03	2.04	2.05	2.06	2.07	2.08	2.09	
Third Series: 0.10 Millimeter Increments (9 Blocks)									
2.1	2.2	2.3	2.4	2.5	2.6	2.7	2.8	2.9	
Fourth Series: 1 Millimeter Increments (9 Blocks)									
1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0	9.0	
Fifth Series: 10 Millimeter Increments (9 Blocks)									
10	20	30	40	50	60	70	80	90	
Long Gage Block Set Number 8M (8 Blocks)									
Whole Millimeter Series (8 Blocks)									
125	150	175	200	250	300	400	500		

Set numbers 3M, 5M, 6M, and 7M are not listed.

Arranged here in incremental series for convenience of use.

Note: Gage blocks measuring 1.09 millimeters and under in set number 1M, blocks measuring 1.5 millimeters and under in set number 2M, and block measuring 1.0 millimeter in set number 4M are not available in tolerance grade 0.5.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

TOOLING AND TOOLMAKING

CUTTING TOOLS

749 Terms and Definitions
749 Tool Contour
752 Relief Angles
753 Rake Angles
754 Nose Radius
755 Chipbreakers
756 Planing Tools
756 Indexable Inserts
757 Identification System
758 Indexable Insert Tool Holders
759 Standard Shank Sizes
760 Letter Symbols
761 Indexable Insert Holders
764 Sintered Carbide Tools
764 Sintered Carbide Blanks
764 Single Point Tools
764 Single-Point, Sintered-Carbide-Tipped Tools
767 Tool Nose Radii
767 Tool Angle Tolerances
767 Carbide Tipped Tools
767 Style A
768 Style B
769 Style C
769 Style D
770 Style E
770 Styles ER and EL
771 Style F
772 Style G

CEMENTED CARBIDES

773 Cemented Carbide
773 Carbides and Carbonitrides
774 Properties of Tungsten-Carbide-Based Cutting-Tool
778 ISO Classifications of Hardmetals
778 Ceramics
781 Superhard Materials
782 Machining Data
783 Hardmetal Tooling
783 Cutting Blades

FORMING TOOLS

784 Dovetail Forming Tools
784 Straight Forming Tools
787 Circular Forming Tools
788 Circular Forming Tools Formula
789 Top Rake

FORMING TOOLS

(Continued)

789 Constants for Diameters
789 Corrected Diameters
794 Arrangement of Circular Tools
795 Circular Cut-Off Tools

MILLING CUTTERS

796 Selection of Milling Cutters
796 Number of Teeth
797 Hand of Milling Cutters
798 Plain Milling Cutters
799 Side Milling Cutters
800 Staggered Teeth,T-Slot Milling Cutters
801 Metal Slitting Saws
801 Milling Cutter Terms
803 Shell Mills
804 Multiple- and Two-Flute Single-End Helical End Mills
805 Regular-, Long-, and Extra Long-Length, Mills
806 Two-Flute, High Helix, Regular-, Long-, and Extra Long-Length, Mills
807 Roughing, Single-End End Mills
815 Concave, Convex, and Corner-Rounding Arbor-Type Cutters
817 Roller Chain Sprocket
819 Keys and Keyways
820 Woodruff Keyseat Cutters
824 Spline-Shaft Milling Cutter
824 Cutter Grinding
825 Wheel Speeds and Feeds
825 Clearance Angles
826 Rake Angles for Milling Cutters
826 Eccentric Type Radial Relief
829 Indicator Drop Method
830 Relieving Attachments
831 Distance to Set Tooth

REAMERS

832 Hand Reamers
833 Irregular Tooth Spacing in Reamers
833 Threaded-end Hand Reamers
833 Fluted and Rose Chucking Reamers
835 Vertical Adjustment of Tooth-rest
835 Reamer Terms and Definitions

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

TOOLING AND TOOLMAKING

REAMERS

(Continued)
839 Direction of Rotation and Helix
839 Dimensions of Centers
840 Reamer Difficulties
842 Expansion Chucking Reamers
843 Hand Reamers
844 Expansion Hand Reamers
845 Driving Slots and Lugs
846 Chucking Reamers
849 Shell Reamers
851 Center Reamers
852 Taper Pipe Reamers

TWIST DRILLS AND COUNTERBORES

854 Definitions of Twist Drill Terms
855 Types of Drills
875 Split-Sleeve, Collet Type Drill Drivers
876 Three- and Four-Flute Straight Shank Core Drills
877 Twist Drills and Centering Tools
878 British Standard Combined Drills
878 Drill Drivers
878 British Standard Metric Twist Drills
879 Gauge and Letter Sizes
880 Morse Taper Shank Twist Drills
881 Tolerance on Diameter
882 Parallel Shank Jobber Series Twist Drills
884 Stub Drills
884 Steels for Twist Drills
884 Accuracy of Drilled Holes
885 Counterboring
886 Interchangeable Cutters
886 Three Piece Counterbores
887 Sintered Carbide Boring Tools
887 Style Designations
889 Square Boring Tools
890 Carbide-Tipped Square Boring Tools
891 Solid Carbide Round Boring Tools
891 Boring Machines, Origin

TAPS AND THREADING DIES

892 Taps
892 Types of Taps
892 Definitions of Tap Terms
896 Fraction-Size Taps
898 Machine Screw Taps
899 Ground Thread Limits
900 Taper Pipe Taps
901 Straight Pipe Taps
903 Straight Fluted Taps
905 Spiral-Pointed Taps
910 ANSI Standard Taps
911 Pulley Taps
911 Spark Plug Taps
913 Spiral Pointed Ground Thread Taps
914 Taper and Straight Pipe Taps
916 Thread Series Designations
917 Pitch Diameter Tolerance
917 Eccentricity Tolerances
919 Acme and Square-Threaded Taps
919 Acme Threads Taps
921 Proportions
921 Drill Hole Sizes for Acme Threads
922 Screwing Taps for ISO Metric Threads
925 Tapping Square Threads

STANDARD TAPERS

926 Standard Tapers
926 Morse Taper
926 Brown & Sharpe Taper
926 Jarno Taper
934 British Standard Tapers
935 Morse Taper Sleeves
936 Brown & Sharpe Taper Shank
937 Jarno Taper Shanks
937 Machine Tool Spindles
938 Plug and Ring Gages
939 Jacobs Tapers and Threads
940 Spindle Noses
942 Tool Shanks
943 Draw-in Bolt Ends
944 Spindle Nose
945 Collets
945 Collets for Lathes, Mills, Grinders, and Fixtures

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

TOOLING AND TOOLMAKING

ARBORS, CHUCKS, AND SPINDLES

948 Portable Tool Spindles
948 Circular Saw Arbors
948 Spindles for Geared Chucks
948 Spindle Sizes
948 Straight Grinding Wheel Spindles
949 Square Drives for Portable Air
950 Threaded and Tapered Spindles
950 Abrasion Tool Spindles
951 Hexagonal Chucks for Portable Air
952 Mounted Wheels and Points
954 Shapes of Mounted Wheels and Points

BROACHES AND BROACHING

955 The Broaching Process
955 Types of Broaches
956 Pitch of Broach Teeth
957 Designing Data for Surface Broaches
957 Broaching Pressure
958 Depth of Cut per Tooth
959 Face Angle or Rake
959 Clearance Angle
959 Land Width
959 Depth of Broach Teeth
959 Radius of Tooth Fillet
959 Total Length of Broach
959 Chip Breakers
960 Shear Angle
960 Types of Broaching Machines
960 Ball-Broaching
961 Broaching Difficulties

FILES AND BURS

962 Definitions of File Terms
963 File Characteristics
963 Classes of Files
965 Effectiveness of Rotary Files and Burs
966 Speeds of Rotary Files and Burs

TOOL WEAR AND SHARPENING

969 Sharpening Twist Drills
969 Relief Grinding of the Tool Flanks
970 Drill Point Thinning
971 Sharpening Carbide Tools
971 Silicon Carbide Wheels
972 Diamond Wheels
972 Diamond Wheel Grit Sizes
972 Diamond Wheel Grades
972 Diamond Concentration
973 Dry Versus Wet Grinding of Carbide Tools
973 Coolants for Carbide Tool Grinding
973 Peripheral Versus Flat Side Grinding
974 Lapping Carbide Tools
974 Chip Breaker Grinding
974 Summary of Miscellaneous Points

JIGS AND FIXTURES

975 Jig Bushings
975 Materials
975 American National Standard
976 Head Type Press Fit Wearing Bushings
979 Specifications for Press Fit Wearing Bushings
979 Slip Type Renewable Wearing Bushings
981 Fixed Type Renewable Wearing Bushings
982 Headless Type Liner Bushings
984 Locking Mechanisms
985 Jig Bushing Definitions
985 Jig Plate Thickness
985 Jig Bushing Designation System
985 Jig Boring
985 Definition of Jig and Fixture
985 Jig Borers
986 Jig-Boring Practice
987 Transfer of Tolerances
989 Determining Hole Coordinates
989 Hole Coordinate Dimension Factors
991 Spacing Off the Circumferences of Circles
993 Hole Coordinate Tables

Copyright 2004, Industrial Press, Inc., New York, NY

CUTTING TOOLS

Terms and Definitions

Tool Contour.— Tools for turning, planing, etc., are made in straight, bent, offset, and other forms to place the cutting edges in convenient positions for operating on differently located surfaces. The contour or shape of the cutting edge may also be varied to suit different classes of work. Tool shapes, however, are not only related to the kind of operation, but, in roughing tools particularly, the contour may have a decided effect upon the cutting efficiency of the tool. To illustrate, an increase in the side cutting-edge angle of a roughing tool, or in the nose radius, tends to permit higher cutting speeds because the chip will be thinner for a given feed rate. Such changes, however, may result in chattering or vibrations unless the work and the machine are rigid; hence, the most desirable contour may be a compromise between the ideal form and one that is needed to meet practical requirements.

Terms and Definitions.— The terms and definitions relating to single-point tools vary somewhat in different plants, but the following are in general use.



Fig. 1. Terms Applied to Single-point Turning Tools

Single-point Tool: This term is applied to tools for turning, planing, boring, etc., which have a cutting edge at one end. This cutting edge may be formed on one end of a solid piece of steel, or the cutting part of the tool may consist of an insert or tip which is held to the body of the tool by brazing, welding, or mechanical means.

Shank: The shank is the main body of the tool. If the tool is an inserted cutter type, the shank supports the cutter or bit. (See diagram, Fig. 1.)

Nose: A general term sometimes used to designate the cutting end but usually relating more particularly to the rounded tip of the cutting end.

Face: The surface against which the chips bear, as they are severed in turning or planing operations, is called the face.

Flank: The flank is that end surface adjacent to the cutting edge and below it when the tool is in a horizontal position as for turning.

Base: The base is the surface of the tool shank that bears against the supporting toolholder or block.

Side Cutting Edge: The side cutting edge is the cutting edge on the side of the tool. Tools such as shown in Fig. 1 do the bulk of the cutting with this cutting edge and are, therefore, sometimes called side cutting edge tools.

End Cutting Edge: The end cutting edge is the cutting edge at the end of the tool.

On side cutting edge tools, the end cutting edge can be used for light plunging and facing cuts. Cutoff tools and similar tools have only one cutting edge located on the end. These

Copyright 2004, Industrial Press, Inc., New York, NY

tools and other tools that are intended to cut primarily with the end cutting edge are sometimes called end cutting edge tools.

Rake: A metal-cutting tool is said to have rake when the tool face or surface against which the chips bear as they are being severed, is inclined for the purpose of either increasing or diminishing the keenness or bluntness of the edge. The magnitude of the rake is most conveniently measured by two angles called the back rake angle and the side rake angle. The tool shown in Fig. 1 has rake. If the face of the tool did not incline but was parallel to the base, there would be no rake; the rake angles would be zero.

Positive Rake: If the inclination of the tool face is such as to make the cutting edge keener or more acute than when the rake angle is zero, the rake angle is defined as positive.

Negative Rake: If the inclination of the tool face makes the cutting edge less keen or more blunt than when the rake angle is zero, the rake is defined as negative.

Back Rake: The back rake is the inclination of the face toward or away from the end or the end cutting edge of the tool. When the inclination is away from the end cutting edge, as shown in Fig. 1, the back rake is positive. If the inclination is downward toward the end cutting edge the back rake is negative.

Side Rake: The side rake is the inclination of the face toward or away from the side cutting edge. When the inclination is away from the side cutting edge, as shown in Fig. 1, the side rake is positive. If the inclination is toward the side cutting edge the side rake is negative.

Relief: The flanks below the side cutting edge and the end cutting edge must be relieved to allow these cutting edges to penetrate into the workpiece when taking a cut. If the flanks are not provided with relief, the cutting edges will rub against the workpiece and be unable to penetrate in order to form the chip. Relief is also provided below the nose of the tool to allow it to penetrate into the workpiece. The relief at the nose is usually a blend of the side relief and the end relief.

End Relief Angle: The end relief angle is a measure of the relief below the end cutting edge.

Side Relief Angle: The side relief angle is a measure of the relief below the side cutting edge.

Back Rake Angle: The back rake angle is a measure of the back rake. It is measured in a plane that passes through the side cutting edge and is perpendicular to the base. Thus, the back rake angle can be defined by measuring the inclination of the side cutting edge with respect to a line or plane that is parallel to the base. The back rake angle may be positive, negative, or zero depending upon the magnitude and direction of the back rake.

Side Rake Angle: The side rake angle is a measure of the side rake. This angle is always measured in a plane that is perpendicular to the side cutting edge and perpendicular to the base. Thus, the side rake angle is the angle of inclination of the face perpendicular to the side cutting edge with reference to a line or a plane that is parallel to the base.

End Cutting Edge Angle: The end cutting edge angle is the angle made by the end cutting edge with respect to a plane perpendicular to the axis of the tool shank. It is provided to allow the end cutting edge to clear the finish machined surface on the workpiece.

Side Cutting Edge Angle: The side cutting edge angle is the angle made by the side cutting edge and a plane that is parallel to the side of the shank.

Nose Radius: The nose radius is the radius of the nose of the tool. The performance of the tool, in part, is influenced by nose radius so that it must be carefully controlled.

Lead Angle: The lead angle, shown in Fig. 2, is not ground on the tool. It is a tool setting angle which has a great influence on the performance of the tool. The lead angle is bounded by the side cutting edge and a plane perpendicular to the workpiece surface when the tool is in position to cut; or, more exactly, the lead angle is the angle between the side cutting edge and a plane perpendicular to the direction of the feed travel.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Lead Angle on Single-point Turning Tool

Solid Tool: A solid tool is a cutting tool made from one piece of tool material.

Brazed Tool: A brazed tool is a cutting tool having a blank of cutting-tool material permanently brazed to a steel shank.

Blank: A blank is an unground piece of cutting-tool material from which a brazed tool is made.

Tool Bit: A tool bit is a relatively small cutting tool that is clamped in a holder in such a way that it can readily be removed and replaced. It is intended primarily to be reground when dull and not indexed.

Tool-bit Blank: The tool-bit blank is an unground piece of cutting-tool material from which a tool bit can be made by grinding. It is available in standard sizes and shapes.

Tool-bit Holder: Usually made from forged steel, the tool-bit holder is used to hold the tool bit, to act as an extended shank for the tool bit, and to provide a means for clamping in the tool post.

Straight-shank Tool-bit Holder: A straight-shank tool-bit holder has a straight shank when viewed from the top. The axis of the tool bit is held parallel to the axis of the shank.

Offset-shank Tool-bit Holder: An offset-shank tool-bit holder has the shank bent to the right or left, as seen in Fig. 3. The axis of the tool bit is held at an angle with respect to the axis of the shank.

Side cutting Tool: A side cutting tool has its major cutting edge on the side of the cutting part of the tool. The major cutting edge may be parallel or at an angle with respect to the axis of the tool.

Indexable Inserts: An indexable insert is a relatively small piece of cutting-tool material that is geometrically shaped to have two or several cutting edges that are used until dull. The insert is then indexed on the holder to apply a sharp cutting edge. When all the cutting edges have been dulled, the insert is discarded. The insert is held in a pocket or against other locating surfaces on an indexable insert holder by means of a mechanical clamping device that can be tightened or loosened easily.

Indexable Insert Holder: Made of steel, an indexable insert holder is used to hold indexable inserts. It is equipped with a mechanical clamping device that holds the inserts firmly in a pocket or against other seating surfaces.

Straight-shank Indexable Insert Holder: A straight-shank indexable insert tool-holder is essentially straight when viewed from the top, although the cutting edge of the insert may be oriented parallel, or at an angle to, the axis of the holder.

Offset-shank Indexable Insert Holder: An offset-shank indexable insert holder has the head end, or the end containing the insert pocket, offset to the right or left, as shown in Fig. 3.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Top: Right-hand Offset-shank, Indexable Insert Holder
Bottom: Right-hand Offset-shank Tool-bit Holder

End cutting Tool: An end cutting tool has its major cutting edge on the end of the cutting part of the tool. The major cutting edge may be perpendicular or at an angle, with respect to the axis of the tool.

Curved Cutting-edge Tool: A curved cutting-edge tool has a continuously variable side cutting edge angle. The cutting edge is usually in the form of a smooth, continuous curve along its entire length, or along a large portion of its length.

Right-hand Tool: A right-hand tool has the major, or working, cutting edge on the right-hand side when viewed from the cutting end with the face up. As used in a lathe, such a tool is usually fed into the work from right to left, when viewed from the shank end.

Left-hand Tool: A left-hand tool has the major or working cutting edge on the left-hand side when viewed from the cutting end with the face up. As used in a lathe, the tool is usually fed into the work from left to right, when viewed from the shank end.

Neutral-hand Tool: A neutral-hand tool is a tool to cut either left to right or right to left; or the cut may be parallel to the axis of the shank as when plunge cutting.

Chipbreaker: A groove formed in or on a shoulder on the face of a turning tool back of the cutting edge to break up the chips and prevent the formation of long,continuous chips which would be dangerous to the operator and also bulky and cumbersome to handle. A chipbreaker of the shoulder type may be formed directly on the tool face or it may consist of a separate piece that is held either by brazing or by clamping.

Relief Angles.— The end relief angle and the side relief angle on single-point cutting tools are usually, though not invariably, made equal to each other. The relief angle under the nose of the tool is a blend of the side and end relief angles.

The size of the relief angles has a pronounced effect on the performance of the cutting tool. If the relief angles are too large, the cutting edge will be weakened and in danger of breaking when a heavy cutting load is placed on it by a hard and tough material. On finish cuts, rapid wear of the cutting edge may cause problems with size control on the part. Relief angles that are too small will cause the rate of wear on the flank of the tool below the cutting edge to increase, thereby significantly reducing the tool life. In general, when cutting hard and tough materials, the relief angles should be 6 to 8 degrees for high-speed steel tools and 5 to 7 degrees for carbide tools. For medium steels, mild steels, cast iron, and other average work the recommended values of the relief angles are 8 to 12 degrees for high-speed steel tools and 5 to 10 degrees for carbides. Ductile materials having a relatively low modulus of elasticity should be cut using larger relief angles. For example, the relief angles recommended for turning copper, brass, bronze, aluminum, ferritic malleable

Copyright 2004, Industrial Press, Inc., New York, NY

iron, and similar metals are 12 to 16 degrees for high-speed steel tools and 8 to 14 degrees for carbides.

Larger relief angles generally tend to produce a better finish on the finish machined surface because less surface of the worn flank of the tool rubs against the workpiece. For this reason, single-point thread-cutting tools should be provided with relief angles that are as large as circumstances will permit. Problems encountered when machining stainless steel may be overcome by increasing the size of the relief angle. The relief angles used should never be smaller than necessary.

Rake Angles.— Machinability tests have confirmed that when the rake angle along which the chip slides, called the true rake angle, is made larger in the positive direction, the cutting force and the cutting temperature will decrease. Also, the tool life for a given cutting speed will increase with increases in the true rake angle up to an optimum value, after which it will decrease again. For turning tools which cut primarily with the side cutting edge, the true rake angle corresponds rather closely with the side rake angle except when taking shallow cuts. Increasing the side rake angle in the positive direction lowers the cutting force and the cutting temperature, while at the same time it results in a longer tool life or a higher permissible cutting speed up to an optimum value of the side rake angle. After the optimum value is exceeded, the cutting force and the cutting temperature will continue to drop; however, the tool life and the permissible cutting speed will decrease.

As an approximation, the magnitude of the cutting force will decrease about one per cent per degree increase in the side rake angle. While not exact, this rule of thumb does correspond approximately to test results and can be used to make rough estimates. Of course, the cutting force also increases about one per cent per degree decrease in the side rake angle. The limiting value of the side rake angle for optimum tool life or cutting speed depends upon the work material and the cutting tool material. In general, lower values can be used for hard and tough work materials. Cemented carbides are harder and more brittle than high-speed steel; therefore, the rake angles usually used for cemented carbides are less positive than for high-speed steel.

Negative rake angles cause the face of the tool to slope in the opposite direction from positive rake angles and, as might be expected, they have an opposite effect. For side cutting edge tools, increasing the side rake angle in a negative direction will result in an increase in the cutting force and an increase in the cutting temperature of approximately one per cent per degree change in rake angle. For example, if the side rake angle is changed from 5 degrees positive to 5 degrees negative, the cutting force will be about 10 per cent larger. Usually the tool life will also decrease when negative side rake angles are used, although the tool life will sometimes increase when the negative rake angle is not too large and when a fast cutting speed is used.

Negative side rake angles are usually used in combination with negative back rake angles on single-point cutting tools. The negative rake angles strengthen the cutting edges enabling them to sustain heavier cutting loads and shock loads. They are recommended for turning very hard materials and for heavy interrupted cuts. There is also an economic advantage in favor of using negative rake indexable inserts and tool holders inasmuch as the cutting edges provided on both the top and bottom of the insert can be used.

On turning tools that cut primarily with the side cutting edge, the effect of the back rake angle alone is much less than the effect of the side rake angle although the direction of the change in cutting force, cutting temperature, and tool life is the same. The effect that the back rake angle has can be ignored unless, of course, extremely large changes in this angle are made. A positive back rake angle does improve the performance of the nose of the tool somewhat and is helpful in taking light finishing cuts. A negative back rake angle strengthens the nose of the tool and is helpful when interrupted cuts are taken. The back rake angle has a very significant effect on the performance of end cutting edge tools, such as cut-off tools. For these tools, the effect of the back rake angle is very similar to the effect of the side rake angle on side cutting edge tools.

Copyright 2004, Industrial Press, Inc., New York, NY

Side Cutting Edge and Lead Angles.— These angles are considered together because the side cutting edge angle is usually designed to provide the desired lead angle when the tool is being used. The side cutting edge angle and the lead angle will be equal when the shank of the cutting tool is positioned perpendicular to the workpiece, or, more correctly, perpendicular to the direction of the feed. When the shank is not perpendicular, the lead angle is determined by the side cutting edge and an imaginary line perpendicular to the feed direction.

The flow of the chips over the face of the tool is approximately perpendicular to the side cutting edge except when shallow cuts are taken. The thickness of the undeformed chip is measured perpendicular to the side cutting edge. As the lead angle is increased, the length of chip in contact with the side cutting edge is increased, and the chip will become longer and thinner. This effect is the same as increasing the depth of cut and decreasing the feed, although the actual depth of cut and feed remain the same and the same amount of metal is removed. The effect of lengthening and thinning the chip by increasing the lead angle is very beneficial as it increases the tool life for a given cutting speed or that speed can be increased. Increasing the cutting speed while the feed and the tool life remain the same leads to faster production.

However, an adverse effect must be considered. Chatter can be caused by a cutting edge that is oriented at a high lead angle when turning and sometimes, when turning long and slender shafts, even a small lead angle can cause chatter. In fact, an unsuitable lead angle of the side cutting edge is one of the principal causes of chatter. When chatter occurs, often simply reducing the lead angle will cure it. Sometimes, very long and slender shafts can be turned successfully with a tool having a zero degree lead angle (and having a small nose radius). Boring bars, being usually somewhat long and slender, are also susceptible to chatter if a large lead angle is used. The lead angle for boring bars should be kept small, and for very long and slender boring bars a zero degree lead angle is recommended. It is impossible to provide a rule that will determine when chatter caused by a lead angle will occur and when it will not. In making a judgment, the first consideration is the length to diameter ratio of the part to be turned, or of the boring bar. Then the method of holding the workpiece must be considered — a part that is firmly held is less apt to chatter. Finally, the overall condition and rigidity of the machine must be considered because they may be the real cause of chatter.

Although chatter can be a problem, the advantages gained from high lead angles are such that the lead angle should be as large as possible at all times.

End Cutting Edge Angle.— The size of the end cutting edge angle is important when tool wear by cratering occurs. Frequently, the crater will enlarge until it breaks through the end cutting edge just behind the nose, and tool failure follows shortly. Reducing the size of the end cutting edge angle tends to delay the time of crater breakthrough. When cratering takes place, the recommended end cutting edge angle is 8 to 15 degrees. If there is no cratering, the angle can be made larger. Larger end cutting edge angles may be required to enable profile turning tools to plunge into the work without interference from the end cutting edge.

Nose Radius.— The tool nose is a very critical part of the cutting edge since it cuts the finished surface on the workpiece. If the nose is made to a sharp point, the finish machined surface will usually be unacceptable and the life of the tool will be short. Thus, a nose radius is required to obtain an acceptable surface finish and tool life. The surface finish obtained is determined by the feed rate and by the nose radius if other factors such as the work material, the cutting speed, and cutting fluids are not considered. A large nose radius will give a better surface finish and will permit a faster feed rate to be used.

Machinability tests have demonstrated that increasing the nose radius will also improve the tool life or allow a faster cutting speed to be used. For example, high-speed steel tools were used to turn an alloy steel in one series of tests where complete or catastrophic tool failure was used as a criterion for the end of tool life. The cutting speed for a 60-minute tool

Copyright 2004, Industrial Press, Inc., New York, NY

life was found to be 125 fpm when the nose radius was 1/16 inch and 160 fpm when the nose radius was 1/4 inch.

A very large nose radius can often be used but a limit is sometimes imposed because the tendency for chatter to occur is increased as the nose radius is made larger. A nose radius that is too large can cause chatter and when it does, a smaller nose radius must be used on the tool. It is always good practice to make the nose radius as large as is compatible with the operation being performed.

Chipbreakers.— Many steel turning tools are equipped with chipbreaking devices to prevent the formation of long continuous chips in connection with the turning of steel at the high speeds made possible by high-speed steel and especially cemented carbide tools. Long steel chips are dangerous to the operator, and cumbersome to handle, and they may twist around the tool and cause damage. Broken chips not only occupy less space, but permit a better flow of coolant to the cutting edge. Several different forms of chipbreakers are illustrated in Fig. 4.

Angular Shoulder Type: The angular shoulder type shown at *A* is one of the commonly used forms. As the enlarged sectional view shows, the chipbreaking shoulder is located back of the cutting edge. The angle *a* between the shoulder and cutting edge may vary from 6 to 15 degrees or more, 8 degrees being a fair average. The ideal angle, width *W* and depth *G*, depend upon the speed and feed, the depth of cut, and the material. As a general rule, width *W*, at the end of the tool, varies from 3/32 to 7/32 inch, and the depth *G* may range from 1/64 to 1/16 inch. The shoulder radius equals depth *G*. If the tool has a large nose radius, the corner of the shoulder at the nose end may be beveled off, as illustrated at *B*, to prevent it from coming into contact with the work. The width *K* for type *B* should equal approximately 1.5 times the nose radius.

Parallel Shoulder Type: Diagram C shows a design with a chipbreaking shoulder that is parallel with the cutting edge. With this form, the chips are likely to come off in short curled sections. The parallel form may also be applied to straight tools which do not have a side cutting-edge angle. The tendency with this parallel shoulder form is to force the chips against the work and damage it.



Fig. 4. Different Forms of Chipbreakers for Turning Tools

Groove Type: This type (diagram D) has a groove in the face of the tool produced by grinding. Between the groove and the cutting edge, there is a land *L*. Under ideal conditions, this width *L*, the groove width *W*, and the groove depth *G*, would be varied to suit the feed, depth of cut and material. For average use, *L* is about 1/32 inch; *G*, 1/32 inch; and *W*, 1/16 inch. There are differences of opinion concerning the relative merits of the groove type and

Copyright 2004, Industrial Press, Inc., New York, NY

the shoulder type. Both types have proved satisfactory when properly proportioned for a given class of work.

Chipbreaker for Light Cuts: Diagram E illustrates a form of chipbreaker that is sometimes used on tools for finishing cuts having a maximum depth of about 1/32 inch. This chipbreaker is a shoulder type having an angle of 45 degrees and a maximum width of about 1/16 inch. It is important in grinding all chipbreakers to give the chip-bearing surfaces a fine finish, such as would be obtained by honing. This finish greatly increases the life of the tool.

Planing Tools.— Many of the principles which govern the shape of turning tools also apply in the grinding of tools for planing. The amount of rake depends upon the hardness of the material, and the direction of the rake should be away from the *working part* of the cutting edge. The angle of clearance should be about 4 or 5 degrees for planer tools, which is less than for lathe tools. This small clearance is allowable because a planer tool is held about square with the platen, whereas a lathe tool, the height and inclination of which can be varied, may not always be clamped in the same position.

Carbide Tools: Carbide tools for planing usually have negative rake. Round-nose and square-nose end-cutting tools should have a "negative back rake" (or front rake) of 2 or 3 degrees. Side cutting tools may have a negative back rake of 10 degrees, a negative side rake of 5 degrees, and a side cutting-edge angle of 8 degrees.

Indexable Inserts

Introduction.— A large proportion of the cemented carbide, single-point cutting tools are indexable inserts and indexable insert tool holders. Dimensional specifications for solid sintered carbide indexable inserts are given in American National Standard ANSI B212.12-1991 (R2002). Samples of the many insert shapes are shown in Table 3. Most modern, cemented carbide, face milling cutters are of the indexable insert type. Larger size end milling cutters, side milling or slotting cutters, boring tools, and a wide variety of special tools are made to use indexable inserts. These inserts are primarily made from cemented carbide, although most of the cemented oxide cutting tools are also indexable inserts.

The objective of this type of tooling is to provide an insert with several cutting edges. When an edge is worn, the insert is indexed in the tool holder until all the cutting edges are used up, after which it is discarded. The insert is not intended to be reground. The advantages are that the cutting edges on the tool can be rapidly changed without removing the tool holder from the machine, tool-grinding costs are eliminated, and the cost of the insert is less than the cost of a similar, brazed carbide tool. Of course, the cost of the tool holder must be added to the cost of the insert; however, one tool holder will usually last for a long time before it, too, must be replaced.

Indexable inserts and tool holders are made with a negative rake or with a positive rake. Negative rake inserts have the advantage of having twice as many cutting edges available as comparable positive rake inserts, because the cutting edges on both the top and bottom of negative rake inserts can be used, while only the top cutting edges can be used on positive rake inserts. Positive rake inserts have a distinct advantage when machining long and slender parts, thin-walled parts, or other parts that are subject to bending or chatter when the cutting load is applied to them, because the cutting force is significantly lower as compared to that for negative rake inserts. Indexable inserts can be obtained in the following forms: utility ground, or ground on top and bottom only; precision ground, or ground on all surfaces; prehoned to produce a slight rounding of the cutting edge; and precision molded, which are unground. Positive-negative rake inserts also are available. These inserts are held on a negative-rake tool holder and have a chipbreaker groove that is formed to produce an effective positive-rake angle while cutting. Cutting edges may be available on the top surface only, or on both top and bottom surfaces. The positive-rake chipbreaker surface may be ground or precision molded on the insert.

Copyright 2004, Industrial Press, Inc., New York, NY

Many materials, such as gray cast iron, form a discontinuous chip. For these materials an insert that has plain faces without chipbreaker grooves should always be used. Steels and other ductile materials form a continuous chip that must be broken into small segments when machined on lathes and planers having single-point, cemented-carbide and cemented-oxide cutting tools; otherwise, the chips can cause injury to the operator. In this case a chipbreaker must be used. Some inserts are made with chipbreaker grooves molded or ground directly on the insert. When inserts with plain faces are used, a cemented-carbide plate-type chipbreaker is clamped on top of the insert.

Identification System for Indexable Inserts.— The size of indexable inserts is determined by the diameter of an inscribed circle (I.C.), except for rectangular and parallelogram inserts where the length and width dimensions are used. To describe an insert in its entirety, a standard ANSI B212.4-2002 identification system is used where each position number designates a feature of the insert. The ANSI Standard includes items now commonly used and facilitates identification of items not in common use. Identification consists of up to ten positions; each position defines a characteristic of the insert as shown below:

1	2	3	4	5	6	7	8[a]	9[a]	10[a]
T	**N**	**M**	**G**	**5**	**4**	**3**			**A**

[a] Eighth, Ninth, and Tenth Positions are used only when required.

1) *Shape:* The shape of an insert is designated by a letter: **R** for round; **S,** square; **T,** triangle; **A,** 85° parallelogram; **B,** 82° parallelogram; **C,** 80° diamond; **D,** 55° diamond; **E,** 75° diamond; **H,** hexagon; **K,** 55° parallelogram; **L,** rectangle; **M,** 86° diamond; **O,** octagon; **P,** pentagon; **V,** 35° diamond; and **W,** 80° trigon.

2) *Relief Angle (Clearances):* The second position is a letter denoting the relief angles; **N** for 0°; **A,** 3°; **B,** 5°; **C,** 7°; **P,** 11°; **D,** 15°; **E,** 20°; **F,** 25°; **G,** 30°; **H,** 0° & 11°*; **J,** 0° & 14°*; **K,** 0° & 17°*; **L,** 0° & 20°*; **M,** 11° & 14°*; **R,** 11° & 17°*; **S,** 11° & 20°*. When mounted on a holder, the actual relief angle may be different from that on the insert.

3) *Tolerances:* The third position is a letter and indicates the tolerances which control the indexability of the insert. Tolerances specified do not imply the method of manufacture.

	Tolerance (± from nominal)			Tolerance (± from nominal)	
Symbol	Inscribed Circle, Inch	Thicknes, Inch	Symbol	Inscribed Circle, Inch	Thickness, Inch
A	0.001	0.001	**H**	0.0005	0.001
B	0.001	0.005	**J**	0.002–0.005	0.001
C	0.001	0.001	**K**	0.002–0.005	0.001
D	0.001	0.005	**L**	0.002–0.005	0.001
E	0.001	0.001	**M**	0.002–0.004[a]	0.005
F	0.0005	0.001	**U**	0.005–0.010[a]	0.005
G	0.001	0.005	**N**	0.002–0.004[a]	0.001

[a] Exact tolerance is determined by size of insert. See ANSI B212.12.

4) *Type:* The type of insert is designated by a letter. **A,** with hole; **B,** with hole and countersink; **C,** with hole and two countersinks; **F,** chip grooves both surfaces, no hole; **G,** same as **F** but with hole; **H,** with hole, one countersink, and chip groove on one rake surface; **J,** with hole, two countersinks and chip grooves on two rake surfaces; **M,** with hole and chip groove on one rake surface; **N,** without hole; **Q,** with hole and two countersinks; **R,** without hole but with chip groove on one rake surface; **T,** with hole, one countersink, and chip

* Second angle is secondary facet angle, which may vary by ± 1°.

Copyright 2004, Industrial Press, Inc., New York, NY

groove on one rake face; **U,** with hole, two countersinks, and chip grooves on two rake faces; and **W,** with hole and one countersink. *Note:* a dash may be used after position 4 to separate the shape-describing portion from the following dimensional description of the insert and is not to be considered a position in the standard description.

5) *Size:* The size of the insert is designated by a one- or a two-digit number. For regular polygons and diamonds, it is the number of eighths of an inch in the nominal size of the inscribed circle, and will be a one- or two-digit number when the number of eighths is a whole number. It will be a two-digit number, including one decimal place, when it is not a whole number. Rectangular and parallelogram inserts require two digits: the first digit indicates the number of eighths of an inch width and the second digit, the number of quarters of an inch length.

6) *Thickness:* The thickness is designated by a one- or two-digit number, which indicates the number of sixteenths of an inch in the thickness of the insert. It is a one-digit number when the number of sixteenths is a whole number; it is a two-digit number carried to one decimal place when the number of sixteenths of an inch is not a whole number.

7) *Cutting Point Configuration:* The cutting point, or nose radius, is designated by a number representing 1/64ths of an inch; a flat at the cutting point or nose, is designated by a letter: **0** for sharp corner; **1,** 1/64 inch radius; **2,** 1/32 inch radius; **3,** 3/64inch radius; **4,** 1/16 inch radius; **5,** 5/64 inch radius; **6,** 3/32 inch radius; **7,** 7/64 inch radius; **8,** 1/8 inch radius; **A,** square insert with 45° chamfer; **D,** square insert with 30° chamfer; **E,** square insert with 15° chamfer; **F,** square insert with 3° chamfer; **K,** square insert with 30° double chamfer; **L,** square insert with 15° double chamfer; **M,** square insert with 3° double chamfer; **N,** truncated triangle insert; and **P,** flatted corner triangle insert.

8) *Special Cutting Point Definition:* The eighth position, if it follows a letter in the 7th position, is a number indicating the number of 1/64ths of an inch measured parallel to the edge of the facet.

9) *Hand:* **R,** right; **L,** left; to be used when required in ninth position.

10) *Other Conditions:* The tenth position defines special conditions (such as edge treatment, surface finish) as follows: **A,** honed, 0.0005 inch to less than 0.003 inch; **B,** honed, 0.003 inch to less than 0.005 inch; **C,** honed, 0.005 inch to less than 0.007 inch; **J,** polished, 4 microinch arithmetic average (AA) on rake surfaces only; **T,** chamfered, manufacturer's standard negative land, rake face only.

Indexable Insert Tool Holders.— Indexable insert tool holders are made from a good grade of steel which is heat treated to a hardness of 44 to 48 Rc for most normal applications. Accurate pockets that serve to locate the insert in position and to provide surfaces against which the insert can be clamped are machined in the ends of tool holders. A cemented carbide seat usually is provided, and is held in the bottom of the pocket by a screw or by the clamping pin, if one is used. The seat is necessary to provide a flat bearing surface upon which the insert can rest and, in so doing, it adds materially to the ability of the insert to withstand the cutting load. The seating surface of the holder may provide a positive-, negative-, or a neutral-rake orientation to the insert when it is in position on the holder. Holders, therefore, are classified as positive, negative, or neutral rake.

Four basic methods are used to clamp the insert on the holder: 1) Clamping, usually top clamping; 2) Pin-lock clamping; 3) Multiple clamping using a clamp, usually a top clamp, and a pin lock; and 4) Clamping the insert with a machine screw.

All top clamps are actuated by a screw that forces the clamp directly against the insert. When required, a cemented-carbide, plate-type chipbreaker is placed between the clamp and the insert. Pin-lock clamps require an insert having a hole: the pin acts against the walls of the hole to clamp the insert firmly against the seating surfaces of the holder. Multiple or combination clamping, simultaneously using both a pin-lock and a top clamp, is recommended when taking heavier or interrupted cuts. Holders are available on which all the above-mentioned methods of clamping may be used. Other holders are made with only a

Copyright 2004, Industrial Press, Inc., New York, NY

top clamp or a pin lock. Screw-on type holders use a machine screw to hold the insert in the pocket. Most standard indexable insert holders are either straight-shank or offset-shank, although special holders are made having a wide variety of configurations.

The common shank sizes of indexable insert tool holders are shown in Table 1. Not all styles are available in every shank size. Positive- and negative-rake tools are also not available in every style or shank size. Some manufacturers provide additional shank sizes for certain tool holder styles. For more complete details the manufacturers' catalogs must be consulted.

Table 1. Standard Shank Sizes for Indexable Insert Holders



Basic Shank Size	Shank Dimensions for Indexable Insert Holders					
	A		B		C[a]	
	In.	mm	In.	mm	In.	mm
½ × ½ × 4½	0.500	12.70	0.500	12.70	4.500	114.30
⅝ × ⅝ × 4½	0.625	15.87	0.625	15.87	4.500	114.30
⅝ × 1¼ × 6	0.625	15.87	1.250	31.75	6.000	152.40
¾ × ¾ × 4½	0.750	19.05	0.750	19.05	4.500	114.30
¾ × 1 × 6	0.750	19.05	1.000	25.40	6.000	152.40
¾ × 1¼ × 6	0.750	19.05	1.250	31.75	6.000	152.40
1 × 1 × 6	1.000	25.40	1.000	25.40	6.000	152.40
1 × 1¼ × 6	1.000	25.40	1.250	31.75	6.000	152.40
1 × 1½ × 6	1.000	25.40	1.500	38.10	6.000	152.40
1¼ × 1¼ × 7	1.250	31.75	1.250	31.75	7.000	177.80
1¼ × 1½ × 8	1.250	31.75	1.500	38.10	8.000	203.20
1⅜ × 2 1/16 × 6⅜	1.375	34.92	2.062	52.37	6.380	162.05
1½ × 1½ × 7	1.500	38.10	1.500	38.10	7.000	177.80
1¾ × 1¾ × 9½	1.750	44.45	1.750	44.45	9.500	241.30
2 × 2 × 8	2.000	50.80	2.000	50.80	8.000	203.20

[a] Holder length; may vary by manufacturer. Actual shank length depends on holder style.

Identification System for Indexable Insert Holders.— The following identification system conforms to the American National Standard, ANSI B212.5-2002, Metric Holders for Indexable Inserts.

Each position in the system designates a feature of the holder in the following sequence:

1	2	3	4	5	—	6	—	7	—	8[a]	—	9	—	10[a]
C	**T**	**N**	**A**	**R**	**—**	**85**	**—**	**25**	**—**	**D**	**—**	**16**	**—**	**Q**

1) *Method of Holding Horizontally Mounted Insert:* The method of holding or clamping is designated by a letter: **C,** top clamping, insert without hole; **M,** top and hole clamping, insert with hole; **P,** hole clamping, insert with hole; **S,** screw clamping through hole, insert with hole; **W,** wedge clamping.

2) *Insert Shape:* The insert shape is identified by a letter: **H,** hexagonal; **O,** octagonal; **P,** pentagonal; **S,** square; **T,** triangular; **C,** rhombic, 80° included angle; **D,** rhombic, 55° included angle; **E,** rhombic, 75° included angle; **M,** rhombic, 86° included angle; **V,** rhombic, 35° included angle; **W,** hexagonal, 80° included angle; **L,** rectangular; **A,** parallelogram, 85° included angle; **B,** parallelogram, 82° included angle; **K,** parallelogram, 55° included angle; **R,** round. The included angle is always the smaller angle.

Copyright 2004, Industrial Press, Inc., New York, NY

3) *Holder Style:* The holder style designates the shank style and the side cutting edge angle, or end cutting edge angle, or the purpose for which the holder is used. It is designated by a letter: **A,** for straight shank with 0° side cutting edge angle; **B,** straight shank with 15° side cutting edge angle; **C,** straight-shank end cutting tool with 0° end cutting edge angle; **D,** straight shank with 45° side cutting edge angle; **E,** straight shank with 30° side cutting edge angle; **F,** offset shank with 0° end cutting edge angle; **G,** offset shank with 0° side cutting edge angle; **J,** offset shank with negative 3° side cutting edge angle; **K,** offset shank with 15° end cutting edge angle; **L,** offset shank with negative 5° side cutting edge angle and 5° end cutting edge angle; **M,** straight shank with 40° side cutting edge angle; **N,** straight shank with 27° side cutting edge angle; **R,** offset shank with 15° side cutting edge angle; **S,** offset shank with 45° side cutting edge angle; **T,** offset shank with 30° side cutting edge angle; **U,** offset shank with negative 3° end cutting edge angle; **V,** straight shank with 17½° side cutting edge angle; **W,** offset shank with 30° end cutting edge angle; **Y,** offset shank with 5° end cutting edge angle.

4) *Normal Clearances:* The normal clearances of inserts are identified by letters: **A,** 3°; **B,** 5°; **C,** 7°; **D,** 15°; **E,** 20°; **F,** 25°; **G,** 30°; **N,** 0°; **P,** 11°.

5) *Hand of tool:* The hand of the tool is designated by a letter: **R** for right-hand; **L,** left-hand; and **N,** neutral, or either hand.

6) *Tool Height for Rectangular Shank Cross Sections:* The tool height for tool holders with a rectangular shank cross section and the height of cutting edge equal to shank height is given as a two-digit number representing this value in millimeters. For example, a height of 32 mm would be encoded as 32; 8 mm would be encoded as 08, where the one-digit value is preceded by a zero.

7) *Tool Width for Rectangular Shank Cross Sections:* The tool width for tool holders with a rectangular shank cross section is given as a two-digit number representing this value in millimeters. For example, a width of 25 mm would be encoded as 25; 8 mm would be encoded as 08, where the one-digit value is preceded by a zero.

8) *Tool Length:* The tool length is designated by a letter: **A,** 32 mm; **B,** 40 mm; **C,** 50 mm; **D,** 60 mm; **E,** 70 mm; **F,** 80 mm; **G,** 90 mm; **H,** 100 mm; **J,** 110 mm; **K,** 125 mm; **L,** 140 mm; **M,** 150 mm; **N,** 160 mm; **P,** 170 mm; **Q,** 180 mm; **R,** 200 mm; **S,** 250 mm; **T,** 300 mm; **U,** 350 mm; **V,** 400 mm; **W,** 450 mm; **X,** special length to be specified; **Y,** 500 mm.

9) *Indexable Insert Size:* The size of indexable inserts is encoded as follows: For insert shapes **C**, **D**, **E**, **H**. **M**, **O**, **P**, **R**, **S**, **T**, **V**, the side length (the diameter for **R** inserts) in millimeters is used as a two-digit number, with decimals being disregarded. For example, the symbol for a side length of 16.5 mm is 16. For insert shapes **A**, **B**, **K**, **L**, the length of the main cutting edge or of the longer cutting edge in millimeters is encoded as a two-digit number, disregarding decimals. If the symbol obtained has only one digit, then it should be preceded by a zero. For example, the symbol for a main cutting edge of 19.5 mm is 19; for an edge of 9.5 mm, the symbol is 09.

10) *Special Tolerances:* Special tolerances are indicated by a letter: **Q,** back and end qualified tool; **F,** front and end qualified tool; **B,** back, front, and end qualified tool. A qualified tool is one that has tolerances of ±0.08 mm for dimensions *F*, *G*, and *C*. (See Table 2.)

Table 2. Letter Symbols for Qualification of Tool Holders
Position 10 *ANSI B212.5-2002*

Qualification of Tool Holder	Letter Symbol		
	Q	F	B
			
	Back and end qualified tool	Front and end qualified tool	Back, front, and end qualified tool

Copyright 2004, Industrial Press, Inc., New York, NY

Selecting Indexable Insert Holders.— A guide for selecting indexable insert holders is provided by Table 3b. Some operations such as deep grooving, cut-off, and threading are not given in this table. However, tool holders designed specifically for these operations are available. The boring operations listed in Table 3b refer primarily to larger holes, into which the holders will fit. Smaller holes are bored using boring bars. An examination of this table shows that several tool-holder styles can be used and frequently are used for each operation. Selection of the best holder for a given job depends largely on the job and there are certain basic facts that should be considered in making the selection.

Rake Angle: A negative-rake insert has twice as many cutting edges available as a comparable positive-rake insert. Sometimes the tool life obtained when using the second face may be less than that obtained on the first face because the tool wear on the cutting edges of the first face may reduce the insert strength. Nevertheless, the advantage of negative-rake inserts and holders is such that they should be considered first in making any choice. Positive-rake holders should be used where lower cutting forces are required, as when machining slender or small-diameter parts, when chatter may occur, and for machining some materials, such as aluminum, copper, and certain grades of stainless steel, when positive-negative rake inserts can sometimes be used to advantage. These inserts are held on negative-rake holders that have their rake surfaces ground or molded to form a positive-rake angle.

Insert Shape: The configuration of the workpiece, the operation to be performed, and the lead angle required often determine the insert shape. When these factors need not be considered, the insert shape should be selected on the basis of insert strength and the maximum number of cutting edges available. Thus, a round insert is the strongest and has a maximum number of available cutting edges. It can be used with heavier feeds while producing a good surface finish. Round inserts are limited by their tendency to cause chatter, which may preclude their use. The square insert is the next most effective shape, providing good corner strength and more cutting edges than all other inserts except the round insert. The only limitation of this insert shape is that it must be used with a lead angle. Therefore, the square insert cannot be used for turning square shoulders or for back-facing. Triangle inserts are the most versatile and can be used to perform more operations than any other insert shape. The 80-degree diamond insert is designed primarily for heavy turning and facing operations, using the 100-degree corners, and for turning and back-facing square shoulders using the 80-degree corners. The 55- and 35-degree diamond inserts are intended primarily for tracing.

Lead Angle: Tool holders should be selected to provide the largest possible lead angle, although limitations are sometimes imposed by the nature of the job. For example, when tuning and back-facing a shoulder, a negative lead angle must be used. Slender or small-diameter parts may deflect, causing difficulties in holding size, or chatter when the lead angle is too large.

End Cutting Edge Angle: When tracing or contour turning, the plunge angle is determined by the end cutting edge angle. A 2-deg minimum clearance angle should be provided between the workpiece surface and the end cutting edge of the insert. Table 3a provides the maximum plunge angle for holders commonly used to plunge when tracing where insert shape identifiers are S = square, T = triangle, D = 55-deg diamond, V = 35-deg diamond. When severe cratering cannot be avoided, an insert having a small, end cutting edge angle is desirable to delay the crater breakthrough behind the nose. For very heavy cuts a small, end cutting edge angle will strengthen the corner of the tool. Tool holders for numerical control machines are discussed in the NC section, beginning page 1309.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3a. Maximum Plunge Angle for Tracing or Contour Turning

Tool Holder Style	Insert Shape	Maximum Plunge Angle	Tool Holder Style	Insert Shape	Maximum Plunge Angle
E	T	58°	J	D	30°
D and S	S	43°	J	V	50°
H	D	71°	N	T	55°
J	T	25°	N	D	58°–60°

Table 3b. Indexable Insert Holder Application Guide

Tool	Tool Holder Style	Insert Shape	N-Negative P-Positive Rake	Application: Turn	Face	Turn and Face	Turn and Backface	Trace	Groove	Chamfer	Bore	Plane
	A	T	N	●	●						●	
			P	●	●						●	
	A	T	N	●	●			●				
			P	●	●			●				
	A	R	N	●	●	●						●
	A	R	N	●	●	●		●				●
	B	T	N	●	●						●	
			P	●	●						●	
	B	T	N	●	●			●			●	
			P	●	●			●			●	
	B	S	N	●	●						●	
			P	●	●						●	
	B	C	N	●	●	●					●	●
	C	T	N	●	●				●	●		
			P	●	●				●	●		

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. ***(Continued)*** **Indexable Insert Holder Application Guide**

Tool	Tool Holder Style	Insert Shape	N-Negative P-Positive Rake	Application								
				Turn	Face	Turn and Face	Turn and Backface	Trace	Groove	Chamfer	Bore	Plane
	D	S	N	●	●	●		●		●	●	●
			P	●	●	●		●		●	●	●
	E	T	N	●	●			●	●	●		
			P	●	●			●	●	●		
	F	T	N	●	●						●	
			P	●	●						●	
	G	T	N	●	●						●	
			P	●	●						●	
	G	R	N	●	●	●						
	G	C	N	●	●	●						
			P	●	●	●						
	H	D	N	●	●			●				
	J	T	N				●	●				
			P				●	●				
	J	D	N				●	●				
	J	V	N				●	●				
	K	S	N	●	●						●	
			P	●	●						●	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. ***(Continued)*** **Indexable Insert Holder Application Guide**

Tool	Tool Holder Style	Insert Shape	N-Negative P-Positive Rake	Application: Turn	Face	Turn and Face	Turn and Backface	Trace	Groove	Chamfer	Bore	Plane
	K	C	N	●	●						●	
	L	C	N			●	●					
	N	T	N	●	●			●				
			P	●	●			●				
	N	D	N	●	●			●				
	S	S	N	●	●	●		●		●	●	●
			P	●	●	●		●		●	●	●
	W	S	N	●	●							

Sintered Carbide Blanks and Cutting Tools

Sintered Carbide Blanks.— As shown in Table 4, American National Standard ANSI B212.1-2002 provides standard sizes and designations for eight styles of sintered carbide blanks. These blanks are the unground solid carbide from which either solid or tipped cutting tools are made. Tipped cutting tools are made by brazing a blank onto a shank to produce the cutting tool; these tools differ from carbide *insert* cutting tools which consist of a carbide insert held mechanically in a tool holder. A typical single-point carbide-tipped cutting tool is shown in Fig. 1 on page 766.

Single-Point, Sintered-Carbide-Tipped Tools.— American National Standard ANSI B212.1-2002 covers eight different styles of single-point, carbide-tipped general purpose tools. These styles are designated by the letters A to G inclusive. Styles A, B, F, G, and E with offset point are either right- or left-hand cutting as indicated by the letters R or L. Dimensions of tips and shanks are given in Tables 5 to 12. For dimensions and tolerances not shown, and for the identification system, dimensions, and tolerances of sintered carbide boring tools, see the Standard.

A number follows the letters of the tool style and hand designation and for square shank tools, represents the number of sixteenths of an inch of width, *W*, and height, *H*. With rectangular shanks, the first digit of the number indicates the number of eighths of an inch in the shank width, *W*, and the second digit the number of quarters of an inch in the shank

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Sizes and Designations for Carbide Blanks
ANSI B212.1-2002

Blank Dimensions[a]			Style[b]	
T	*W*	*L*	1000	2000
			Blank Designation	
1/16	1/8	5/8	1010	2010
1/16	5/32	1/4	1015	2015
1/16	3/16	1/4	1020	2020
1/16	1/4	1/4	1025	2025
1/16	1/4	5/16	1030	2030
3/32	1/8	3/4	1035	2035
3/32	3/16	5/16	1040	2040
3/32	3/16	1/2	1050	2050
3/32	1/4	3/8	1060	2060
3/32	1/4	1/2	1070	2070
3/32	5/16	3/8	1080	2080
3/32	3/8	3/8	1090	2090
3/32	3/8	1/2	1100	2100
3/32	7/16	1/2	1105	2105
3/32	5/16	3/8	1080	2080
1/8	3/16	3/4	1110	2110
1/8	1/4	1/2	1120	2120
1/8	1/4	5/8	1130	2130
1/8	1/4	3/4	1140	2140
1/8	5/16	7/16	1150	2150
1/8	5/16	1/2	1160	2160
1/8	3/16	3/4	1110	2110
1/8	5/16	5/8	1170	2170
1/8	3/8	1/2	1180	2180
1/8	3/8	3/4	1190	2190
1/8	1/2	1/2	1200	2200
1/8	1/2	3/4	1210	2210
1/8	3/4	3/4	1215	2215
5/32	3/8	9/16	1220	2220
5/32	3/8	3/4	1230	2230
5/32	5/8	5/8	1240	2240
3/16	5/16	7/16	1250	2250
3/16	5/16	5/8	1260	2260
3/16	3/8	1/2	1270	2270
3/16	3/8	5/8	1280	2280
3/16	3/8	3/4	1290	2290
3/16	7/16	5/8	1300	2300
3/16	7/16	13/16	1310	2310
3/16	1/2	1/2	1320	2320
3/16	1/2	3/4	1330	2330
3/16	3/4	3/4	1340	2340

Blank Dimensions[a]			Style[b]			
T	*W*	*L*	0000	1000	3000	4000
			Blank Designation			
1/4	3/8	9/16	0350	1350	3350	4350
1/4	3/8	3/4	0360	1360	3360	4360
1/4	7/16	5/8	0370	1370	3370	4370
1/4	1/2	3/4	0380	1380	3380	4380
1/4	9/16	1	0390	1390	3390	4390
1/4	5/8	5/8	0400	1400	3400	4400
1/4	3/4	3/4	0405	1405	3405	4405
1/4	3/4	1	0410	1410	3410	4410
1/4	1	1	0415	1415	3415	4415
5/16	7/16	5/8	0420	1420	3420	4420
5/16	7/16	15/16	0430	1430	3430	4430
5/16	1/2	3/4	0440	1440	3440	4440
5/16	1/2	1	0450	1450	3450	4450
5/16	5/8	1	0460	1460	3460	4460
5/16	3/4	3/4	0470	1470	3470	4470
5/16	3/4	1	0475	1475	3475	4475
5/16	3/4	1 1/4	0480	1480	3480	4480
3/8	1/2	3/4	0490	1490	3490	4490
3/8	1/2	1	0500	1500	3500	4500
3/8	5/8	1	0510	1510	3510	4510
3/8	5/8	1 1/4	0515	1515	3515	4515
3/8	3/4	1 1/4	0520	1520	3520	4520
3/8	3/4	1 1/2	0525	1525	3525	4525
1/2	3/4	1	0530	1530	3530	4530
1/2	3/4	1 1/4	0540	1540	3540	4540
3/8	1/2	3/4	0490	1490	3490	4490
1/2	3/4	1 1/2	0550	1550	3550	4550

				Style[b]		
T	*W*	*L*	*F*	5000	6000	70000
				Blank Designation		
1/16	1/4	5/16	…	5030	…	…
3/32	1/4	3/8	1/16	…	…	7060
3/32	5/16	3/8	…	5080	6080	…
3/32	3/8	1/2	…	5100	6100	…
3/32	7/16	1/2	…	5105	…	…
1/8	5/16	5/8	3/32	…	…	7170
3/32	1/4	3/8	1/16	…	…	7060
1/8	1/2	1/2	…	5200	6200	…
5/32	3/8	3/4	1/8	…	…	7230
5/32	5/8	5/8	…	5240	6240	…
3/16	3/4	3/4	…	5340	6340	…
1/4	1	3/4	…	5410	…	…

[a] All dimensions are in inches.

[b] See Fig. 1 on page 766 for a description of styles.

height, *H*. One exception is the 1½ × 2-inch size which has been arbitrarily assigned the number 90.

A typical single-point carbide tipped cutting tool is shown in Fig. 2. The side rake, side relief, and the clearance angles are normal to the side-cutting edge, rather than the shank, to facilitate its being ground on a tilting-table grinder. The end-relief and clearance angles are

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Eight styles of sintered carbide blanks (see Table 4.)



Fig. 2. A typical single-point carbide tipped cutting tool.

normal to the end-cutting edge. The back-rake angle is parallel to the side-cutting edge. The tip of the brazed carbide blank overhangs the shank of the tool by either $\frac{1}{32}$ or $\frac{1}{16}$ inch, depending on the size of the tool. For tools in Tables 5, 6, 7, 8, 11 and , the maximum overhang is $\frac{1}{32}$ inch for shank sizes 4, 5, 6, 7, 8, 10, 12 and 44; for other shank sizes in these tables, the maximum overhang is $\frac{1}{16}$ inch. In Tables 9 and 10 all tools have maximum overhang of $\frac{1}{32}$ inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Single-point Tool Nose Radii: The tool nose radii recommended in the American National Standard are as follows: For square-shank tools up to and including ⅜-inch square tools, 1/64 inch; for those over ⅜-inch square through 1¼-inches square, 1/32 inch; and for those above 1¼-inches square, 1/16 inch. For rectangular-shank tools with shank section of ½ × 1 inch through 1 × 1½ inches, the nose radii are 1/32 inch, and for 1 × 2 and 1½ × 2 inch shanks, the nose radius is 1/16 inch.

Single-point Tool Angle Tolerances: The tool angles shown on the diagrams in the Tables 5 through 12 are general recommendations. Tolerances applicable to these angles are ± 1 degree on all angles except end and side clearance angles; for these the tolerance is ± 2 degrees.

Table 5. American National Standard Style A Carbide Tipped Tools
ANSI B212.1-2002



Designation		Shank Dimensions			Tip	Tip Dimensions		
Style AR[a]	Style AL[a]	Width *A*	Height *B*	Length *C*	Designation[a]	Thickness *T*	Width *W*	Length *L*
Square Shank								
AR 4	AL 4	1/4	1/4	2	2040	3/32	3/16	5/16
AR 5	AL 5	5/16	5/16	2 1/4	2070	3/32	1/4	1/2
AR 6	AL 6	3/8	3/8	2 1/2	2070	3/32	1/4	1/2
AR 7	AL 7	7/16	7/16	3	2070	3/32	1/4	1/2
AR 8	AL 8	1/2	1/2	3 1/2	2170	1/8	5/16	5/8
AR 10	AL 10	5/8	5/8	4	2230	5/32	3/8	3/4
AR 12	AL 12	3/4	3/4	4 1/2	2310	3/16	7/16	13/16
AR 16	AL 16	1	1	6	{ P3390, P4390	1/4	9/16	1
AR 20	AL 20	1 1/4	1 1/4	7	{ P3460, P4460	5/16	5/8	1
AR 24	AL 24	1 1/2	1 1/2	8	{ P3510, P4510	3/8	5/8	1
Rectangular Shank								
AR 44	AL 44	1/2	1	6	P2260	3/16	5/16	5/8
AR 54	AL 54	5/8	1	6	{ P3360, P4360	1/4	3/8	3/4
AR 55	AL 55	5/8	1 1/4	7	{ P3360, P4360	1/4	3/8	3/4
AR 64	AL 64	3/4	1	6	{ P3380, P4380	1/4	1/2	3/4
AR 66	AL 66	3/4	1 1/2	8	{ P3430, P4430	5/16	7/16	15/16
AR 85	AL 85	1	1 1/4	7	{ P3460, P4460	5/16	5/8	1
AR 86	AL 86	1	1 1/2	8	{ P3510, P4510	3/8	5/8	1
AR 88	AL 88	1	2	10	{ P3510, P4510	3/8	5/8	1
AR 90	AL 90	1 1/2	2	10	{ P3540, P4540	1/2	3/4	1 1/4

[a] "A" is straight shank, 0 deg., SCEA (side-cutting-edge angle). "R" is right-cut. "L" is left-cut. Where a pair of tip numbers is shown, the upper number applies to AR tools, the lower to AL tools. All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Style B Carbide Tipped Tools with 15-degree Side-cutting-edge Angle *ANSI B212.1-2002*



Designation		Shank Dimensions				Tip Dimensions		
Style BR	Style BL	Width *A*	Height *B*	Length *C*	Tip Designation[a]	Thickness *T*	Width *W*	Length *L*
Square Shank								
BR 4	BL 4	1/4	1/4	2	2015	1/16	5/32	1/4
BR 5	BL 5	5/16	5/16	2 1/4	2040	3/32	3/16	5/16
BR 6	BL 6	3/8	3/8	2 1/2	2070	3/32	1/4	1/2
BR 7	BL 7	7/16	7/16	3	2070	3/32	1/4	1/2
BR 8	BL 8	1/2	1/2	3 1/2	2170	1/8	5/16	5/8
BR 10	BL 10	5/8	5/8	4	2230	5/32	3/8	3/4
BR 12	BL 12	3/4	3/4	4 1/2	2310	3/16	7/16	13/16
BR 16	BL 16	1	1	6	{ 3390, 4390	1/4	9/16	1
BR 20	BL 20	1 1/4	1 1/4	7	{ 3460, 4460	5/16	5/8	1
BR 24	BL 24	1 1/2	1 1/2	8	{ 3510, 4510	3/8	5/8	1
Rectangular Shank								
BR 44	BL 44	1/2	1	6	2260	3/16	5/16	5/8
BR 54	BL 54	5/8	1	6	{ 3360, 4360	1/4	3/8	3/4
BR 55	BL 55	5/8	1 1/4	7	{ 3360, 4360	1/4	3/8	3/4
BR 64	BL 64	3/4	1	6	{ 3380, 4380	1/4	1/2	3/4
BR 66	BL 66	3/4	1 1/2	8	{ 3430, 4430	5/16	7/16	15/16
BR 85	BL 85	1	1 1/4	7	{ 3460, 4460	5/16	5/8	1
BR 86	BL 86	1	1 1/2	8	{ 3510, 4510	3/8	5/8	1
BR 88	BL 88	1	2	10	{ 3510, 4510	3/8	5/8	1
BR 90	BL 90	1 1/2	2	10	{ 3540, 4540	1/2	3/4	1 1/4

[a] Where a pair of tip numbers is shown, the upper number applies to BR tools, the lower to BL tools. All dimensions are in inches.

Brazing Carbide Tips to Steel Shanks.— Sintered carbide tips or blanks are attached to steel shanks by brazing. Shanks usually are made of low-alloy steels having carbon contents ranging from 0.40 to 0.60 per cent. *Shank Preparation:* The carbide tip usually is inserted into a milled recess or seat. When a recess is used, the bottom should be flat to provide a firm even support for the tip. The corner radius of the seat should be somewhat smaller than the radius on the tip to avoid contact and insure support along each side of the recess. *Cleaning:* All surfaces to be brazed must be absolutely clean. Surfaces of the tip may be cleaned by grinding lightly or by sand-blasting. *Brazing Materials and Equipment:* The brazing metal may be copper, naval brass such as Tobin bronze, or silver solder. A flux such as borax is used to protect the clean surfaces and prevent oxidation. Heating may be done in a furnace or by oxy-acetylene torch or an oxy-hydrogen torch. Copper brazing usually is done in a furnace, although an oxy-hydrogen torch with excess hydrogen is sometimes used. *Brazing Procedure:* One method using a torch is to place a thin sheet material, such as copper foil, around and beneath the carbide tip, the top of which is covered with flux. The flame is applied to the under side of the tool shank, and, when the materials melt, the tip is pressed firmly into its seat with tongs or with the end of a rod. Brazing material in the form of wire or rod may be used to coat or tin the surfaces of the recess after the flux melts and runs freely. The tip is then inserted, flux is applied to the top, and heating continued until the coatings melt and run freely. The tip, after coating with flux, is placed in the recess and the shank end is heated. Then a small piece of silver solder, having a melting point of 1325 degrees F., is placed on top of the tip. When this solder melts, it runs over the nickel-coated surfaces while the tip is held firmly into its seat. The brazed tool should be cooled slowly to avoid cracking due to unequal contraction between the steel and carbide.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Style C Carbide Tipped Tools
ANSI B212.1-2002



Designation	Shank Dimensions			Tip Designnation	Tip Dimensions		
	Width, *A*	Height, *B*	Length, *C*		Thickness, *T*	Width, *W*	Length, *L*
C 4	1/4	1/4	2	1030	1/16	1/4	5/16
C 5	5/16	5/16	2 1/4	1080	3/32	5/16	3/8
C 6	3/8	3/8	2 1/2	1090	3/32	3/8	3/8
C 7	7/16	7/16	3	1105	3/32	7/16	1/2
C 8	1/2	1/2	3 1/2	1200	1/8	1/2	1/2
C 10	5/8	5/8	4	1240	5/32	5/8	5/8
C 12	3/4	3/4	4 1/2	1340	3/16	3/4	3/4
C 16	1	1	6	1410	1/4	1	3/4
C 20	1 1/4	1 1/4	7	1480	5/16	1 1/4	3/4
C 44	1/2	1	6	1320	3/16	1/2	1/2
C 54	5/8	1	6	1400	1/4	5/8	5/8
C 55	5/8	1 1/4	7	1400	1/4	5/8	5/8
C 64	3/4	1	6	1405	1/4	3/4	3/4
C 66	3/4	1 1/2	8	1470	5/16	3/4	3/4
C 86	1	1 1/2	8	1475	5/16	1	3/4

All dimensions are in inches. Square shanks above horizontal line; rectangular below.

Table 8. American National Standard Style D, 80-degree Nose-angle Carbide Tipped Tools *ANSI B212.1-2002*



Designation	Shank Dimensions			Tip Designation	Tip Dimensions		
	Width, *A*	Height, *B*	Length, *C*		Thickness, *T*	Width, *W*	Length, *L*
D 4	1/4	1/4	2	5030	1/16	1/4	5/16
D 5	5/16	5/16	2 1/4	5080	3/32	5/16	3/8
D 6	3/8	3/8	2 1/2	5100	3/32	3/8	1/2
D 7	7/16	7/16	3	5105	3/32	7/16	1/2
D 8	1/2	1/2	3 1/2	5200	1/8	1/2	1/2
D 10	5/8	5/8	4	5240	5/32	5/8	5/8
D 12	3/4	3/4	4 1/2	5340	3/16	3/4	3/4
D 16	1	1	6	5410	1/4	1	3/4

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Style E, 60-degree Nose-angle, Carbide Tipped Tools *ANSI B212.1-2002*



	Shank Dimensions				Tip Dimensions		
Designation	Width *A*	Height *B*	Length *C*	Tip Designation	Thickness *T*	Width *W*	Length *L*
E 4	1/4	1/4	2	6030	1/16	1/4	3/16
E 5	5/16	5/16	2 1/4	6080	3/32	5/16	3/8
E 6	3/8	3/8	2 1/2	6100	3/32	3/8	1/2
E 8	1/2	1/2	3 1/2	6200	1/8	1/2	1/2
E 10	5/8	5/8	4	6240	5/32	3/8	5/8
E 12	3/4	3/4	4 1/2	6340	3/16	3/4	3/4

All dimensions are in inches.

Table 10. American National Standard Styles ER and EL, 60-degree Nose-angle, Carbide Tipped Tools with Offset Point *ANSI B212.1-2002*



Designation		Shank Dimensions			Tip	Tip Dimensions		
Style ER	Style EL	Width *A*	Height *B*	Length *C*	Designation	Thick. *T*	Width *W*	Length *L*
ER 4	EL 4	1/4	1/4	2	1020	1/16	3/16	1/4
ER 5	EL 5	5/16	5/16	2 1/4	7060	3/32	1/4	3/8
ER 6	EL 6	3/8	3/8	2 1/2	7060	3/32	1/4	3/8
ER 8	EL 8	1/2	1/2	3 1/2	7170	1/8	5/16	5/8
ER 10	EL 10	5/8	5/8	4	7170	1/8	5/16	5/8
ER 12	EL 12	3/4	3/4	4 1/2	7230	5/32	3/8	3/4

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. American National Standard Style F, Offset, End-cutting Carbide Tipped Tools *ANSI B212.1-2002*



Designation		Shank Dimensions						Tip Dimensions		
Style FR	Style FL	Width *A*	Height *B*	Length *C*	Offset *G*	Length of Offset *E*	Tip Designation	Thickness *T*	Width *W*	Length *L*
Square Shank										
FR 8	FL 8	1/2	1/2	3 1/2	1/4	3/4	{ P4170, P3170	1/8	5/16	5/8
FR 10	FL 10	5/8	5/8	4	3/8	1	{ P1230, P3230	5/32	3/8	3/4
FR 12	FL 12	3/4	3/4	4 1/2	5/8	1 1/8	{ P4310, P3310	3/16	7/16	13/16
FR 16	FL 16	1	1	6	3/4	1 3/8	{ P4390, P3390	1/4	9/16	1
FR 20	FL 20	1 1/4	1 1/4	7	3/4	1 1/2	{ P4460, P3460	5/16	5/8	1
FR 24	FL 24	1 1/2	1 1/2	8	3/4	1 1/2	{ P4510, P3510	3/8	5/8	1
Rectangular Shank										
FR 44	FL 44	1/2	1	6	1/2	7/8	{ P4260, P1260	3/16	5/16	5/8
FR 55	FL 55	5/8	1 1/4	7	5/8	1 1/8	{ P4360, P3360	1/4	3/8	3/4
FR 64	FL 64	3/4	1	6	5/8	1 3/16	{ P4380, P3380	1/4	1/2	3/4
FR 66	FL 66	3/4	1 1/2	8	3/4	1 1/4	{ P4430, P3430	5/16	7/16	15/16
FR 85	FL 85	1	1 1/4	7	3/4	1 1/2	{ P4460, P3460	5/16	5/8	1
FR 86	FL 86	1	1 1/2	8	3/4	1 1/2	{ P4510, P3510	3/8	5/8	1
FR 90	FL 90	1 1/2	2	10	3/4	1 5/8	{ P4540, P3540	1/2	3/4	1 1/4

All dimensions are in inches. Where a pair of tip numbers is shown, the upper number applies to FR tools, the lower number to FL tools.

Carbide Tools.— Cemented or sintered carbides are used in the machine building and various other industries, chiefly for cutting tools but also for certain other tools or parts subject to considerable abrasion or wear. Carbide cutting tools, when properly selected to obtain the right combination of strength and hardness, are very effective in machining all classes of iron and steel, non-ferrous alloys, non-metallic materials, hard rubber, synthetic resins, slate, marble, and other materials which would quickly dull steel tools either because of hardness or abrasive action. Carbide cutting tools are not only durable, but capable of exceptionally high cutting speeds. See *CEMENTED CARBIDES* starting on page 773 for more on these materials.

Tungsten carbide is used extensively in cutting cast iron, nonferrous metals which form short chips in cutting; plastics and various other non-metallic materials. A grade having a hardness of 87.5 Rockwell A might be used where a strong grade is required, as for roughing cuts, whereas for light high-speed finishing or other cuts, a hardness of about 92 might be preferable. When tungsten carbide is applied to steel, craters or chip cavities are formed

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. American National Standard Style G, Offset, Side-cutting, Carbide Tipped Tools *ANSI B212.1-2002*



Designation		Shank Dimensions						Tip Dimensions		
Style GR	Style GL	Width *A*	Height *B*	Length *C*	Offset *G*	Length of Offset *E*	Tip Designation	Thickness *T*	Width *W*	Length *L*
Square Shank										
GR 8	GL 8	1/2	1/2	3 1/2	1/4	1 1/16	{ P3170, P4170	1/8	5/16	5/8
GR 10	GL 10	5/8	5/8	4	3/8	1 3/8	{ P3230, P4230	5/32	3/8	3/4
GR 12	GL 12	3/4	3/4	4 1/2	3/8	1 1/2	{ P3310, P2310	3/16	7/16	13/16
GR 16	GL 16	1	1	6	1/2	1 11/16	{ P3390, P4390	1/4	9/16	1
GR 20	GL 20	1 1/4	1 1/4	7	3/4	1 13/16	{ P3460, P4460	5/16	5/8	1
GR 24	GL 24	1 1/2	1 1/2	8	3/4	1 13/16	{ P3510, P4510	3/8	5/8	1
Rectangular Shank										
GR 44	GL 44	1/2	1	6	1/4	1 1/16	{ P3260, P4260	3/16	5/16	5/8
GR 55	GL 55	5/8	1 1/4	7	3/8	1 3/8	{ P3360, P4360	1/4	3/8	3/4
GR 64	GL 64	3/4	1	6	1/2	1 7/16	{ P3380, P4380	1/4	1/2	3/4
GR 66	GL 66	3/4	1 1/2	8	1/2	1 5/8	{ P3430, P4430	5/16	7/16	15/16
GR 85	GL 85	1	1 1/4	7	1/2	1 11/16	{ P3460, P4460	5/16	5/8	1
GR 86	GL 86	1	1 1/2	8	1/2	1 11/16	{ P3510, P4510	3/8	5/8	1
GR 90	GL 90	1 1/2	2	10	3/4	2 1/16	{ P3540, P4540	1/2	3/4	1 1/4

All dimensions are in inches. Where a pair of tip numbers is shown, the upper number applies to GR tools, the lower number to GL tools.

back of the cutting edge; hence other carbides have been developed which offer greater resistance to abrasion.

Tungsten-titanium carbide (often called "titanium carbide") is adapted to cutting either heat-treated or unheattreated steels, cast steel, or any tough material which might form chip cavities. It is also applicable to bronzes, monel metal, aluminum alloys, etc.

Tungsten-tantalum carbide or "tantalum carbide" cutting tools are also applicable to steels, bronzes or other tough materials. A hardness of 86.8 Rockwell A is recommended by one manufacturer for roughing steel, whereas a grade for finishing might have a hardness ranging from 88.8 to 91.5 Rockwell A.

Copyright 2004, Industrial Press, Inc., New York, NY

CEMENTED CARBIDES

Cemented Carbides and Other Hard Materials

Carbides and Carbonitrides.— Though high-speed steel retains its importance for such applications as drilling and broaching, most metal cutting is carried out with carbide tools. For materials that are very difficult to machine, carbide is now being replaced by carbonitrides, ceramics, and superhard materials. Cemented (or sintered) carbides and carbonitrides, known collectively in most parts of the world as hard metals, are a range of very hard, refractory, wear-resistant alloys made by powder metallurgy techniques. The minute carbide or nitride particles are "cemented" by a binder metal that is liquid at the sintering temperature. Compositions and properties of individual hardmetals can be as different as those of brass and high-speed steel.

All hardmetals are *cermets*, combining *cer*amic particles with a *met*allic binder. It is unfortunate that (owing to a mistranslation) the term *cermet* has come to mean either all hardmetals with a titanium carbide (TiC) base or simply cemented titanium carbonitrides. Although no single element other than carbon is present in all hard-metals, it is no accident that the generic term is "tungsten carbide." The earliest successful grades were based on carbon, as are the majority of those made today, as listed in Table 1.

The outstanding machining capabilities of high-speed steel are due to the presence of very hard carbide particles, notably tungsten carbide, in the iron-rich matrix. Modern methods of making cutting tools from pure tungsten carbide were based on this knowledge. Early pieces of cemented carbide were much too brittle for industrial use, but it was soon found that mixing tungsten carbide powder with up to 10 per cent of metals such as iron, nickel, or cobalt, allowed pressed compacts to be sintered at about 1500°C to give a product with low porosity, very high hardness, and considerable strength. This combination of properties made the materials ideally suitable for use as tools for cutting metal.

Cemented carbides for cutting tools were introduced commercially in 1927, and although the key discoveries were made in Germany, many of the later developments have taken place in the United States, Austria, Sweden, and other countries. Recent years have seen two "revolutions" in carbide cutting tools, one led by the United States and the other by Europe. These were the change from brazed to clamped carbide inserts and the rapid development of coating technology.

When indexable tips were first introduced, it was found that so little carbide was worn away before they were discarded that a minor industry began to develop, regrinding the so-called "throwaway" tips and selling them for reuse in adapted toolholders. Hardmetal consumption, which had grown dramatically when indexable inserts were introduced, leveled off and began to decline. This situation was changed by the advent and rapid acceptance of carbide, nitride, and oxide coatings. Application of an even harder, more wear-resistant surface to a tougher, more shock-resistant substrate allowed production of new generations of longer-lasting inserts. Regrinding destroyed the enhanced properties of the coatings, so was abandoned for coated tooling.

Brazed tools have the advantage that they can be reground over and over again, until almost no carbide is left, but the tools must always be reset after grinding to maintain machining accuracy. However, all brazed tools suffer to some extent from the stresses left by the brazing process, which in unskilled hands or with poor design can shatter the carbide even before it has been used to cut metal. In present conditions it is cheaper to use indexable inserts, which are tool tips of precise size, clamped in similarly precise holders, needing no time-consuming and costly resetting but usable only until each cutting edge or corner has lost its initial sharpness (see *Introduction* and related topics starting on page 756 and *Indexable Insert Holders for NC* on page 1309. The absence of brazing stresses and the "one-use" concept also means that harder, longer-lasting grades can be used.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Typical Properties of Tungsten-Carbide-Based Cutting-Tool Hardmetals

ISO Application Code	Composition (%)				Density (g/cm^3)	Hardness (Vickers)	Transverse Rupture Strength (N/mm^2)
	WC	TiC	TaC	Co			
P01	50	35	7	6	8.5	1900	1100
P05	78	16		6	11.4	1820	1300
P10	69	15	8	8	11.5	1740	1400
P15	78	12	3	7	11.7	1660	1500
P20	79	8	5	8	12.1	1580	1600
P25	82	6	4	8	12.9	1530	1700
P30	84	5	2	9	13.3	1490	1850
P40	85	5		10	13.4	1420	1950
P50	78	3	3	16	13.1	1250	2300
M10	85	5	4	6	13.4	1590	1800
M20	82	5	5	8	13.3	1540	1900
M30	86	4		10	13.6	1440	2000
M40	84	4	2	10	14.0	1380	2100
K01	97			3	15.2	1850	1450
K05	95		1	4	15.0	1790	1550
K10	92		2	6	14.9	1730	1700
K20	94			6	14.8	1650	1950
K30	91			9	14.4	1400	2250
K40	89			11	14.1	1320	2500

A complementary development was the introduction of ever-more complex chip-breakers, derived from computer-aided design and pressed and sintered to precise shapes and dimensions. Another advance was the application of hot isostatic pressing (HIP), which has moved hardmetals into applications that were formerly uneconomic. This method allows virtually all residual porosity to be squeezed out of the carbide by means of inert gas at high pressure, applied at about the sintering temperature. Toughness, rupture strength, and shock resistance can be doubled or tripled by this method, and the reject rates of very large sintered components are reduced to a fraction of their previous levels.

Further research has produced a substantial number of excellent cutting-tool materials based on titanium carbonitride. Generally called "cermets," as noted previously, carbonitride-based cutting inserts offer excellent performance and considerable prospects for the future.

Compositions and Structures: Properties of hardmetals are profoundly influenced by microstructure. The microstructure in turn depends on many factors including basic chemical composition of the carbide and matrix phases; size, shape, and distribution of carbide particles; relative proportions of carbide and matrix phases; degree of intersolubility of carbides; excess or deficiency of carbon; variations in composition and structure caused by diffusion or segregation; production methods generally, but especially milling, carburizing, and sintering methods, and the types of raw materials; post sintering treatments such as hot isostatic pressing; and coatings or diffusion layers applied after initial sintering.

Tungsten Carbide/Cobalt (WC/Co): The first commercially available cemented carbides consisted of fine angular particles of tungsten carbide bonded with metallic cobalt. Intended initially for wire-drawing dies, this composition type is still considered to have the greatest resistance to simple abrasive wear and therefore to have many applications in machining.

For maximum hardness to be obtained from closeness of packing, the tungsten carbide grains should be as small as possible, preferably below 1 μm swaging 0.00004 in.) and considerably less for special purposes. Hardness and abrasion resistance increase as the cobalt content is lowered, provided that a minimum of cobalt is present (2 per cent can be

Copyright 2004, Industrial Press, Inc., New York, NY

enough, although 3 per cent is the realistic minimum) to ensure complete sintering. In general, as carbide grain size or cobalt content or both are increased—frequently in unison—tougher and less hard grades are obtained. No porosity should be visible, even under the highest optical magnification.

WC/Co compositions used for cutting tools range from about 2 to 13 per cent cobalt, and from less than 0.5 to more than 5 μm (0.00002–0.0002 in.) in grain size. For stamping tools, swaying dies, and other wear applications for parts subjected to moderate or severe shock, cobalt content can be as much as 30 per cent, and grain size a maximum of about 10 μm (0.0004 in.). In recent years, "micrograin" carbides, combining submicron (less than 0.00004 in.) carbide grains with relatively high cobalt content have found increasing use for machining at low speeds and high feed rates. An early use was in high-speed woodworking cutters such as are used for planing.

For optimum properties, porosity should be at a minimum, carbide grain size as regular as possible, and carbon content of the tungsten carbide phase close to the theoretical (stoichiometric) value. Many tungsten carbide/cobalt compositions are modified by small but important additions—from 0.5 to perhaps 3 per cent of tantalum, niobium, chromium, vanadium, titanium, hafnium, or other carbides. The basic purpose of these additions is generally inhibition of grain growth, so that a consistently fine structure is maintained.

Tungsten – Titanium Carbide/Cobalt (WC/TiC/Co): These grades are used for tools to cut steels and other ferrous alloys, the purpose of the TiC content being to resist the high-temperature diffusive attack that causes chemical breakdown and cratering. Tungsten carbide diffuses readily into the chip surface, but titanium carbide is extremely resistant to such diffusion. A solid solution or "mixed crystal" of WC in TiC retains the anticratering property to a great extent.

Unfortunately, titanium carbide and TiC-based solid solutions are considerably more brittle and less abrasion resistant than tungsten carbide. TiC content, therefore, is kept as low as possible, only sufficient TiC being provided to avoid severe cratering wear. Even 2 or 3 per cent of titanium carbide has a noticeable effect, and as the relative content is substantially increased, the cratering tendency becomes more severe.

In the limiting formulation the carbide is tungsten-free and based entirely on TiC, but generally TiC content extends to no more than about 18 per cent. Above this figure the carbide becomes excessively brittle and is very difficult to braze, although this drawback is not a problem with throwaway inserts.

WC/TiC/Co grades generally have two distinct carbide phases, angular crystals of almost pure WC and rounded TiC/WC mixed crystals. Among progressive manufacturers, although WC/TiC/Co hardmetals are very widely used, in certain important respects they are obsolescent, having been superseded by the WC/TiC/Ta(Nb)C/Co series in the many applications where higher strength combined with crater resistance is an advantage. TiC, TiN, and other coatings on tough substrates have also diminished the attractions of high-TiC grades for high-speed machining of steels and ferrous alloys.

Tungsten-Titanium-Tantalum (-Niobium) Carbide/Cobalt: Except for coated carbides, tungsten-titanium-tantalum (-niobium) grades could be the most popular class of hardmetals. Used mainly for cutting steel, they combine and improve upon most of the best features of the longer-established WC/TiC/Co compositions. These carbides compete directly with carbonitrides and silicon nitride ceramics, and the best cemented carbides of this class can undertake very heavy cuts at high speeds on all types of steels, including austenitic stainless varieties. These tools also operate well on ductile cast irons and nickel-base superalloys, where great heat and high pressures are generated at the cutting edge. However, they do not have the resistance to abrasive wear possessed by micrograin straight tungsten carbide grades nor the good resistance to cratering of coated grades and titanium carbide-based cermets.

Copyright 2004, Industrial Press, Inc., New York, NY

Titanium Carbide/Molybdenum/Nickel (TiC/Mo/Ni): The extreme indentation hardness and crater resistance of titanium carbide, allied to the cheapness and availability of its main raw material (titanium dioxide, TiO_2), provide a strong inducement to use grades based on this carbide alone. Although developed early in the history of hardmetals, these carbides were difficult to braze satisfactorily and consequently were little used until the advent of clamped, throwaway inserts. Moreover, the carbides were notoriously brittle and could take only fine cuts in minimal-shock conditions.

Titanium-carbide-based grades again came into prominence about 1960, when nickel-molybdenum began to be used as a binder instead of nickel. The new grades were able to perform a wider range of tasks including interrupted cutting and cutting under shock conditions.

The very high indentation hardness values recorded for titanium carbide grades are not accompanied by correspondingly greater resistance to abrasive wear, the apparently less hard tungsten carbide being considerably superior in this property. Moreover, carbonitrides, advanced tantalum-containing multicarbides, and coated variants generally provide better all-round cutting performances.

Titanium-Base Carbonitrides: Development of titanium-carbonitride-based cutting-tool materials predates the use of coatings of this type on more conventional hardmetals by many years. Appreciable, though uncontrolled, amounts of carbonitride were often present, if only by accident, when cracked ammonia was used as a less expensive substitute for hydrogen in some stages of the production process in the 1950's and perhaps for two decades earlier.

Much of the recent, more scientific development of this class of materials has taken place in the United States, particularly by Teledyne Firth Sterling with its SD_3 grade and in Japan by several companies. Many of the compositions currently in use are extremely complex, and their structures—even with apparently similar compositions—can vary enormously. For instance, Mitsubishi characterizes its Himet NX series of cermets as TiC/WC/Ta(Nb)C/Mo_2C/TiN/Ni/Co/Al, with a structure comprising both large and medium-size carbide particles (mainly TiC according to the quoted density) in a superalloy-type matrix containing an aluminum-bearing intermetallic compound.

Steel- and Alloy-Bonded Titanium Carbide: The class of material exemplified by Ferro-Tic, as it is known, consists primarily of titanium carbide bonded with heat-treatable steel, but some grades also contain tungsten carbide or are bonded with nickel- or copper-base alloys. These cemented carbides are characterized by high binder contents (typically 50–60 per cent by volume) and lower hardnesses, compared with the more usual hardmetals, and by the great variation in properties obtained by heat treatment.

In the annealed condition, steel-bonded carbides have a relatively soft matrix and can be machined with little difficulty, especially by CBN (superhard cubic boron nitride) tools. After heat treatment, the degree of hardness and wear resistance achieved is considerably greater than that of normal tool steels, although understandably much less than that of traditional sintered carbides. Microstructures are extremely varied, being composed of 40–50 per cent TiC by volume and a matrix appropriate to the alloy composition and the stage of heat treatment. Applications include stamping, blanking and drawing dies, machine components, and similar items where the ability to machine before hardening reduces production costs substantially.

Coating: As a final stage in carbide manufacture, coatings of various kinds are applied mainly to cutting tools, where for cutting steel in particular it is advantageous to give the rank and clearance surfaces characteristics that are quite different from those of the body of the insert. Coatings of titanium carbide, nitride, or carbonitride; of aluminum oxide; and of other refractory compounds are applied to a variety of hardmetal substrates by chemical or physical vapor deposition (CVD or PVD) or by newer plasma methods.

Copyright 2004, Industrial Press, Inc., New York, NY

The most recent types of coatings include hafnium, tantalum, and zirconium carbides and nitrides; alumina/titanium oxide; and multiple carbide/carbonitride/nitride/oxide, oxynitride or oxycarbonitride combinations. Greatly improved properties have been claimed for variants with as many as 13 distinct CVD coatings. A markedly sharper cutting edge compared with other CVD-coated hardmetals is claimed, permitting finer cuts and the successful machining of soft but abrasive alloys.

The keenest edges on coated carbides are achieved by the techniques of physical vapor deposition. In this process, ions are deposited directionally from the electrodes, rather than evenly on all surfaces, so the sharpness of cutting edges is maintained and may even be enhanced. PVD coatings currently available include titanium nitride and carbonitride, their distinctive gold color having become familiar throughout the world on high-speed steel tooling. The high temperatures required for normal CVD tends to soften heat-treated high-speed steel. PVD-coated hardmetals have been produced commercially for several years, especially for precision milling inserts.

Recent developments in extremely hard coatings, generally involving exotic techniques, include boron carbide, cubic boron nitride, and pure diamond. Almost the ultimate in wear resistance, the commercial applications of thin plasma-generated diamond surfaces at present are mainly in manufacture of semiconductors, where other special properties are important.

For cutting tools the substrate is of equal importance to the coating in many respects, its critical properties including fracture toughness (resistance to crack propagation), elastic modulus, resistance to heat and abrasion, and expansion coefficient. Some manufacturers are now producing inserts with graded composition, so that structures and properties are optimized at both surface and interior, and coatings are less likely to crack or break away.

Specifications: Compared with other standardized materials, the world of sintered hardmetals is peculiar. For instance, an engineer who seeks a carbide grade for the finish-machining of a steel component may be told to use *ISO Standard Grade P10 or Industry Code C7*. If the composition and nominal properties of the designated tool material are then requested, the surprising answer is that, in basic composition alone, the tungsten carbide content of P10 (or of the now superseded C7) can vary from zero to about 75, titanium carbide from 8 to 80, cobalt 0 to 10, and nickel 0 to 15 per cent. There are other possible constituents, also, in this so-called standard alloy, and many basic properties can vary as much as the composition. All that these dissimilar materials have in common, and all that the so-called standards mean, is that their suppliers—and sometimes their suppliers alone—consider them suitable for one particular and ill-defined machining application (which for P10 or C7 is the finish machining of steel).

This peculiar situation arose because the production of cemented carbides in occupied Europe during World War II was controlled by the German Hartmetallzentrale, and no factory other than Krupp was permitted to produce more than one grade. By the end of the war, all German-controlled producers were equipped to make the G, S, H, and F series to German standards. In the postwar years, this series of carbides formed the basis of unofficial European standardization. With the advent of the newer multicarbides, the previous identities of grades were gradually lost. The applications relating to the old grades were retained, however, as a new German DIN standard, eventually being adopted, in somewhat modified form, by the International Standards Organization (ISO) and by ANSI in the United States.

The American cemented carbides industry developed under diverse ownership and solid competition. The major companies actively and independently developed new varieties of hardmetals, and there was little or no standardization, although there were many attempts to compile equivalent charts as a substitute for true standardization. Around 1942, the Buick division of GMC produced a simple classification code that arranged nearly 100 grades derived from 10 manufacturers under only 14 symbols (TC-1 to TC-14). In spite of serious deficiencies, this system remained in use for many years as an American industry

Copyright 2004, Industrial Press, Inc., New York, NY

standard; that is, Buick TC-1 was equivalent to industry code C1. Buick itself went much further, using the tremendous influence, research facilities, and purchasing potential of its parent company to standardize the products of each carbide manufacturer by properties that could be tested, rather than by the indeterminate recommended applications. Many large-scale carbide users have developed similar systems in attempts to exert some degree of in-house standardization and quality control. Small and medium-sized users, however, still suffer from so-called industry standards, which only provide a starting point for grade selection.

ISO standard 513, summarized in Table 2, divides all machining grades into three color-coded groups: straight tungsten carbide grades (letter K, color red) for cutting gray cast iron, nonferrous metals, and nonmetallics; highly alloyed grades (letter, P. color blue) for machining steel; and less alloyed grades (letter M, color yellow, generally with less TiC than the corresponding P series), which are multipurpose and may be used on steels, nickel-base superalloys, ductile cast irons, and so on. Each grade within a group is also given a number to represent its position in a range from maximum hardness to maximum toughness (shock resistance). Typical applications are described for grades at more or less regular numerical intervals. Although coated grades scarcely existed when the ISO standard was prepared, it is easy to classify coated as uncoated carbides—or carbonitrides, ceramics, and superhard materials—according to this system.

In this situation, it is easy to see how one plant will prefer one manufacturer's carbide and a second plant will prefer that of another. Each has found the carbide most nearly ideal for the particular conditions involved. In these circumstances it pays each manufacturer to make grades that differ in hardness, toughness, and crater resistance, so that they can provide a product that is near the optimum for a specific customer's application.

Although not classified as a hard metal, new particle or powder metallurgical methods of manufacture, coupled with new coating technology have led in recent years to something of an upsurge in the use of high speed steel. Lower cost is a big factor, and the development of such coatings as titanium nitride, cubic boron nitride, and pure diamond, has enabled some high speed steel tools to rival tools made from tungsten and other carbides in their ability to maintain cutting accuracy and prolong tool life. Multiple layers may be used to produce optimum properties in the coating, with adhesive strength where there is contact with the substrate, combined with hardness at the cutting surface to resist abrasion. Total thickness of such coating, even with multiple layers, is seldom more than 15 microns (0.000060 in.).

Importance of Correct Grades: A great diversity of hardmetal types is required to cope with all possible combinations of metals and alloys, machining operations, and working conditions. Tough, shock-resistant grades are needed for slow speeds and interrupted cutting, harder grades for high-speed finishing, heat-resisting alloyed grades for machining superalloys, and crater-resistant compositions, including most of the many coated varieties, for machining steels and ductile iron.

Ceramics.— Moving up the hardness scale, ceramics provide increasing competition for cemented carbides, both in performance and in cost-effectiveness, though not yet in reliability. Hardmetals themselves consist of ceramics—nonmetallic refractory compounds, usually carbides or carbonitrides—with a metallic binder of much lower melting point. In such systems, densification generally takes place by liquid-phase sintering. Pure ceramics have no metallic binder, but may contain lower-melting-point compounds or ceramic mixtures that permit liquid-phase sintering to take place. Where this condition is not possible, hot pressing or hot isostatic pressing can often be used to make a strong, relatively pore-free component or cutting insert. This section is restricted to those ceramics that compete directly with hardmetals, mainly in the cutting-tool category as shown in Table 3.

Ceramics are hard, completely nonmetallic substances that resist heat and abrasive wear. Increasingly used as clamped indexable tool inserts, ceramics differ significantly from tool

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ISO Classifications of Hardmetals (Cemented Carbides and Carbonitrides) by Application

Main Types of Chip Removal		Groups of Applications			Direction of Decrease in Characteristic	
Symbol and Color	Broad Categories of Materials to be Machined	Designation (Grade)	Specific Material to be Machined	Use and Working Conditions	of cut	of carbide
P Blue	Ferrous with long chips	P01	Steel, steel castings	Finish turning and boring; high cutting speeds, small chip sections, accurate dimensions, fine finish, vibration-free operations	↑ speed	
		P10	Steel, steel casting	Turning, copying, threading, milling; high cutting speeds; small or medium chip sections	↑	
		P20	Steel, steel castings, ductile cast iron with long chips	Turning, copying, milling; medium cutting speeds and chip sections, planing with small chip sections	wear	
		P30	Steel, steel castings, ductile cast iron with long chips	Turning, milling, planing; medium or large chip sections, unfavorable machining conditions		
		P40	Steel, steel castings with sand inclusions and cavities	Turning, planing, slotting; low cutting speeds, large chip sections, with possible large cutting angles, unfavorable cutting conditions, and work on automatic machines		
		P50	Steel, steel castings of medium or low tensile strength, with sand inclusions and cavities	Operations demanding very tough carbides; turning, planing, slotting; low cutting speeds, large chip sections, with possible large cutting angles, unfavorable conditions and work on automatic machines		
M Yellow	Ferrous metals with long or short chips, and non ferrous metals	M10	Steel, steel castings, manganese steel, gray cast iron, alloy cast iron	Turning; medium or high cutting speeds, small or medium chip sections		
		M20	Steel, steel castings, austenitic or manganese steel, gray cast iron	Turning, milling; medium cutting speeds and chip sections		
		M30	Steel, steel castings, austenitic steel, gray cast iron, high-temperature-resistant alloys	Turning, milling, planing; medium cutting speeds, medium or large chip sections		
		M40	Mild, free-cutting steel, low-tensile steel, nonferrous metals and light alloys	Turning, parting off; particularly on automatic machines		
K Red	Ferrous metals with short chips, non-ferrous metals and non-metallic materials	K01	Very hard gray cast iron, chilled castings over 85 Shore, high-silicon aluminum alloys, hardened steel, highly abrasive plastics, hard cardboard, ceramics	Turning, finish turning, boring, milling, scraping		
		K10	Gray cast iron over 220 Brinell, malleable cast iron with short chips, hardened steel, silicon-aluminum and copper alloys, plastics, glass, hard rubber, hard cardboard, porcelain, stone	Turning, milling, drilling, boring, broaching, scraping		
		K20	Gray cast iron up to 220 Brinell, nonferrous metals, copper, brass, aluminum	Turning, milling, planing, boring, broaching, demanding very tough carbide		
		K30	Low-hardness gray cast iron, low-tensile steel, compressed wood	Turning, milling, planing, slotting, unfavorable conditions, and possibility of large cutting angles	↓ feed	
		K40	Softwood or hard wood, nonferrous metals	Turning, milling, planing, slotting, unfavorable conditions, and possibility of large cutting angles	↓ toughness	

Copyright 2004, Industrial Press, Inc., New York, NY

steels, which are completely metallic. Ceramics also differ from cermets such as cemented carbides and carbonitrides, which comprise minute ceramic particles held together by metallic binders.

Table 3. Typical Properties of Cutting Tool Ceramics

Group	Alumina	Alumina/TiC	Silicon Nitride	PCD	PCBN
Typical composition types	Al_2O_3 or Al_2O_3/ZrO_2	70/30 Al_2O_3/TiC	Si_3N_4/Y_2O_3 plus		
Density (g/cm³)	4.0	4.25	3.27	3.4	3.1
Transverse rupture strength (N/mm²)	700	750	800		800
Compressive strength (kN/mm²)	4.0	4.5	4.0	4.7	3.8
Hardness (HV)	1750	1800	1600		
Hardness HK (kN/mm²)				50	28
Young's modulus (kN/mm²)	380	370	300	925	680
Modulus of rigidity (kN/mm²)	150	160	150	430	280
Poisson's ratio	0.24	0.22	0.20	0.09	0.22
Thermal expansion coefficient (10^{-6}/K)	8.5	7.8	3.2	3.8	4.9
Thermal conductivity (W/m K)	23	17	22	120	100
Fracture toughness (K_{1c}MN/m$^{3/2}$)	2.3	3.3	5.0	7.9	10

Alumina-based ceramics were introduced as cutting inserts during World War II, and were for many years considered too brittle for regular machine-shop use. Improved machine tools and finer-grain, tougher compositions incorporating zirconia or silicon carbide "whiskers" now permit their use in a wide range of applications. Silicon nitride, often combined with alumina (aluminum oxide), yttria (yttrium oxide), and other oxides and nitrides, is used for much of the high-speed machining of superalloys, and newer grades have been formulated specifically for cast iron—potentially a far larger market.

In addition to improvements in toolholders, great advances have been made in machine tools, many of which now feature the higher powers and speeds required for the efficient use of ceramic tooling. Brittleness at the cutting edge is no longer a disadvantage, with the improvements made to the ceramics themselves, mainly in toughness, but also in other critical properties.

Although very large numbers of useful ceramic materials are now available, only a few combinations have been found to combine such properties as minimum porosity, hardness, wear resistance, chemical stability, and resistance to shock to the extent necessary for cutting-tool inserts. Most ceramics used for machining are still based on high-purity, fine-grained alumina (aluminum oxide), but embody property-enhancing additions of other ceramics such as zirconia (zirconium oxide), titania (titanium oxide), titanium carbide, tungsten carbide, and titanium nitride. For commercial purposes, those more commonly used are often termed "white" (alumina with or without zirconia) or "black" (roughly 70/30 alumina/titanium carbide). More recent developments are the distinctively green alumina ceramics strengthened with silicon carbide whiskers and the brown-tinged silicon nitride types.

Ceramics benefit from hot isostatic pressing, used to remove the last vestiges of porosity and raise substantially the material's shock resistance, even more than carbide-based hardmetals. Significant improvements are derived by even small parts such as tool inserts, although, in principle, they should not need such treatment if raw materials and manufacturing methods are properly controlled.

Oxide Ceramics: Alumina cutting tips have extreme hardness—more than HV 2000 or HRA 94—and give excellent service in their limited but important range of uses such as the machining of chilled iron rolls and brake drums. A substantial family of alumina-based materials has been developed, and fine-grained alumina-based composites now have suf-

Copyright 2004, Industrial Press, Inc., New York, NY

ficient strength for milling cast iron at speeds up to 2500 ft/min (800 m/min). Resistance to cratering when machining steel is exceptional.

Oxide/Carbide Ceramics: A second important class of alumina-based cutting ceramics combines aluminum oxide or alumina-zirconia with a refractory carbide or carbides, nearly always 30 per cent TiC. The compound is black and normally is hot pressed or hot isostatically pressed (HIPed). As shown in Table 3, the physical and mechanical properties of this material are generally similar to those of the pure alumina ceramics, but strength and shock resistance are generally higher, being comparable with those of higher-toughness simple alumina-zirconia grades. Current commercial grades are even more complex, combining alumina, zirconia, and titanium carbide with the further addition of titanium nitride.

Silicon Nitride Base: One of the most effective ceramic cutting-tool materials developed in the UK is Syalon (from SiAlON or silicon-aluminum-oxynitride) though it incorporates a substantial amount of yttria for efficient liquid-phase sintering). The material combines high strength with hot hardness, shock resistance, and other vital properties. Syalon cutting inserts are made by Kennametal and Sandvik and sold as Kyon 2000 and CC680, respectively. The brown Kyon 200 is suitable for machining high-nickel alloys and cast iron, but a later development, Kyon 3000 has good potential for machining cast iron.

Resistance to thermal stress and thermal shock of Kyon 2000 are comparable to those of sintered carbides. Toughness is substantially less than that of carbides, but roughly twice that of oxide-based cutting-tool materials at temperatures up to 850°C. Syon 200 can cut at high edge temperatures and is harder than carbide and some other ceramics at over 700°C, although softer than most at room temperature.

Whisker-Reinforced Ceramics: To improve toughness, Greenleaf Corp. has reinforced alumina ceramics with silicon carbide single-crystal "whiskers" that impart a distinctive green color to the material, marketed as WG300. Typically as thin as human hairs, the immensely strong whiskers improve tool life under arduous conditions. Whisker-reinforced ceramics and perhaps hardmetals are likely to become increasingly important as cutting and wear-resistant materials. Their only drawback seems to be the carcinogenic nature of the included fibers, which requires stringent precautions during manufacture.

Superhard Materials.— Polycrystalline synthetic diamond (PCD) and cubic boron nitride (PCBN), in the two columns at the right in Table 3, are almost the only cutting-insert materials in the "superhard" category. Both PCD and PCBN are usually made with the highest practicable concentration of the hard constituent, although ceramic or metallic binders can be almost equally important in providing overall strength and optimizing other properties. Variations in grain size are another critical factor in determining cutting characteristics and edge stability. Some manufacturers treat CBN in similar fashion to tungsten carbide, varying the composition and amount of binder within exceptionally wide limits to influence the physical and mechanical properties of the sintered compact.

In comparing these materials, users should note that some inserts comprise solid polycrystalline diamond or CBN and are double-sized to provide twice the number of cutting edges. Others consist of a layer, from 0.020 to 0.040 in. (0.5 to 1 mm) thick, on a tough carbide backing. A third type is produced with a solid superhard material almost surrounded by sintered carbide. A fourth type, used mainly for cutting inserts, comprises solid hard metal with a tiny superhard insert at one or more (usually only one) cutting corners or edges. Superhard cutting inserts are expensive—up to 30 times the cost of equivalent shapes or sizes in ceramic or cemented carbide—but their outstanding properties, exceptional performance and extremely long life can make them by far the most cost-effective for certain applications.

Diamond: Diamond is the hardest material found or made. As harder, more abrasive ceramics and other materials came into widespread use, diamond began to be used for grinding-wheel grits. Cemented carbide tools virtually demanded diamond grinding wheels for fine edge finishing. Solid single-crystal diamond tools were and are used to a

Copyright 2004, Industrial Press, Inc., New York, NY

small extent for special purposes, such as microtomes, for machining of hard materials, and for exceptionally fine finishes. These diamonds are made from comparatively large, high-quality gem-type diamonds, have isotropic properties, and are very expensive. By comparison, diamond abrasive grits cost only a few dollars a carat.

Synthetic diamonds are produced from graphite using high temperatures and extremely high pressures. The fine diamond particles produced are sintered together in the presence of a metal "catalyst" to produce high-efficiency anisotropic cutting tool inserts. These tools comprise either a solid diamond compact or a layer of sintered diamond on a carbide backing, and are made under conditions similar to, though less severe than, those used in diamond synthesis. Both natural and synthetic diamond can be sintered in this way, although the latter method is the most frequently used.

Polycrystalline diamond (PCD) compacts are immensely hard and can be used to machine many substances, from highly abrasive hardwoods and glass fiber to nonferrous metals, hardmetals, and tough ceramics. Important classes of tools that are also available with cubic boron nitride inserts include brazed-tip drills, single-point turning tools, and face-milling cutters.

Boron Nitride: Polycrystalline diamond has one big limitation: it cannot be used to machine steel or any other ferrous material without rapid chemical breakdown. Boron nitride does not have this limitation. Normally soft and slippery like graphite, the soft hexagonal crystals (HBN) become cubic boron nitride (CBN) when subjected to ultrahigh pressures and temperatures, with a structure similar to and hardness second only to diamond. As a solid insert of polycrystalline cubic boron nitride (PCBN), the compound machines even the hardest steel with relative immunity from chemical breakdown or cratering.

Backed by sintered carbide, inserts of PCBN can readily be brazed, increasing the usefulness of the material and the range of tooling in which it can be used. With great hardness and abrasion resistance, coupled with extreme chemical stability when in contact with ferrous alloys at high temperatures, PCBN has the ability to machine both steels and cast irons at high speeds for long operating cycles. Only its currently high cost in relation to hardmetals prevents its wider use in mass-production machining.

Similar in general properties to PCBN, the recently developed "Wurbon" consists of a mixture of ultrafine (0.02 μm grain size) hexagonal and cubic boron nitride with a "wurtzite" structure, and is produced from soft hexagonal boron nitride in a microsecond by an explosive shock-wave.

Basic Machining Data: Most mass-production metalcutting operations are carried out with carbide-tipped tools but their correct application is not simple. Even apparently similar batches of the same material vary greatly in their machining characteristics and may require different tool settings to attain optimum performance. Depth of cut, feed, surface speed, cutting rate, desired surface finish, and target tool life often need to be modified to suit the requirements of a particular component.

For the same downtime, the life of an insert between indexings can be less than that of an equivalent brazed tool between regrinds, so a much higher rate of metal removal is possible with the indexable or throwaway insert. It is commonplace for the claims for a new coating to include increases in surface-speed rates of 200–300 per cent, and for a new insert design to offer similar improvements. Many operations are run at metal removal rates that are far from optimum for tool life because the rates used maximize productivity and cost-effectiveness.

Thus any recommendations for cutting speeds and feeds must be oversimplified or extremely complex, and must be hedged with many provisos, dependent on the technical and economic conditions in the manufacturing plant concerned. A preliminary grade selection should be made from the ISO-based tables and manufacturers' literature consulted for recommendations on the chosen grades and tool designs. If tool life is much

Copyright 2004, Industrial Press, Inc., New York, NY

greater than that desired under the suggested conditions, speeds, feeds, or depths of cut may be increased. If tools fail by edge breakage, a tougher (more shock-resistant) grade should be selected, with a numerically higher ISO code.

Alternatively, increasing the surface speed and decreasing the feed may be tried. If tools fail prematurely from what appears to be abrasive wear, a harder grade with numerically lower ISO designation should be tried. If cratering is severe, use a grade with higher titanium carbide content; that is, switch from an ISO K to M or M to P grade, use a P grade with lower numerical value, change to a coated grade, or use a coated grade with a (claimed) more-resistant surface layer.

Built-Up Edge and Cratering: The big problem in cutting steel with carbide tools is associated with the built-up edge and the familar phenomenon called cratering. Research has shown that the built-up edge is continuous with the chip itself during normal cutting. Additions of titanium, tantalum, and niobium to the basic carbide mixture have a remarkable effect on the nature and degree of cratering, which is related to adhesion between the tool and the chip.

Hardmetal Tooling for Wood and Nonmetallics.— Carbide-tipped circular saws are now conventional for cutting wood, wood products such as chipboard, and plastics, and tipped bandsaws of large size are also gaining in popularity. Tipped handsaws and mechanical equivalents are seldom needed for wood, but they are extremely useful for cutting abrasive building boards, glass-reinforced plastics, and similar material. Like the hardmetal tips used on most other woodworking tools, saw tips generally make use of straight (unalloyed) tungsten carbide/cobalt grades. However, where excessive heat is generated as with the cutting of high-silica hardwoods and particularly abrasive chipboards, the very hard but tough tungsten-titanium-tantalum-niobium carbide solid-solution grades, normally reserved for steel finishing, may be preferred. Saw tips are usually brazed and reground a number of times during service, so coated grades appear to have little immediate potential in this field.

Cutting Blades and Plane Irons: These tools comprise long, thin, comparatively wide slabs of carbide on a minimal-thickness steel backing. Compositions are straight tungsten carbide, preferably micrograin (to maintain a keen cutting edge with an included angle of 30° or less), but with relatively high amounts of cobalt, 11–13 per cent, for toughness. Considerable expertise is necessary to braze and grind these cutters without inducing or failing to relieve the excessive stresses that cause distortion or cracking.

Other Woodworking Cutters: Routers and other cutters are generally similar to those used on metals and include many indexable-insert designs. The main difference with wood is that rotational and surface speeds can be the maximum available on the machine. High-speed routing of aluminum and magnesium alloys was developed largely from machines and techniques originally designed for work on wood.

Cutting Other Materials: The machining of plastics, fiber-reinforced plastics, graphite, asbestos, and other hard and abrasive constructional materials mainly requires abrasion resistance. Cutting pressures and power requirements are generally low. With thermoplastics and some other materials, particular attention must be given to cooling because of softening or degradation of the work material that might be caused by the heat generated in cutting. An important application of cemented carbides is the drilling and routing of printed circuit boards. Solid tungsten carbide drills of extremely small sizes are used for this work.

Copyright 2004, Industrial Press, Inc., New York, NY

FORMING TOOLS

When curved surfaces or those of stepped, angular or irregular shape are required in connection with turning operations, especially on turret lathes and "automatics," forming tools are used. These tools are so made that the contour of the cutting edge corresponds to the shape required and usually they may be ground repeatedly without changing the shape of the cutting edge. There are two general classes of forming tools—the straight type and the circular type. The circular forming tool is generally used on small narrow forms, whereas the straight type is more suitable for wide forming operations. Some straight forming tools are clamped in a horizontal position upon the cut-off slide, whereas the others are held in a vertical position in a special holder. A common form of holder for these vertical tools is one having a dovetail slot in which the forming tool is clamped; hence they are often called "dovetail forming tools." In many cases, two forming tools are used, especially when a very smooth surface is required, one being employed for roughing and the other for finishing.

There was an American standard for forming tool blanks which covered both straight or dovetailed, and circular forms. The formed part of the finished blanks must be shaped to suit whatever job the tool is to be used for. This former standard includes the important dimensions of holders for both straight and circular forms.

Dimensions of Steps on Straight or Dovetail Forming Tools.— The diagrams at the top of the accompanying Table 1 illustrate a straight or "dovetail" forming tool. The upper or cutting face lies in the same plane as the center of the work and there is no rake. (Many forming tools have rake to increase the cutting efficiency, and this type will be referred to later.) In making a forming tool, the various steps measured perpendicular to the front face (as at *d*) must be proportioned so as to obtain the required radial dimensions on the work. For example, if *D* equals the difference between two radial dimensions on the work, then:

$$\text{Step } d = D \times \text{cosine front clearance angle}$$

Angles on Straight Forming Tools.— In making forming tools to the required shape or contour, any angular surfaces (like the steps referred to in the previous paragraph) are affected by the clearance angle. For example, assume that angle *A* on the work (see diagram at top of accompanying table) is 20 degrees. The angle on the tool in plane *x*-*x*, in that case, will be slightly less than 20 degrees. In making the tool, this modified or reduced angle is required because of the convenience in machining and measuring the angle square to the front face of the tool or in the plane *x*–*x*.

If the angle on the work is measured from a line parallel to the axis (as at *A* in diagram), then the reduced angle on the tool as measured square to the front face (or in plane *x*–*x*) is found as follows:

$$\tan \text{ reduced angle on tool} = \tan A \times \cos \text{ front clearance angle}$$

If angle *A* on the work is larger than, say, 45 degrees, it may be given on the drawing as indicated at *B*. In this case, the angle is measured from a plane perpendicular to the axis of the work. When the angle is so specified, the angle on the tool in plane *x*–*x* may be found as follows:

$$\tan \text{reduced angle on tool} = \frac{\tan B}{\cos \text{ clearance angle}}$$

Table Giving Step Dimensions and Angles on Straight or Dovetailed Forming Tools.— The accompanying table gives the required dimensions and angles within its range, direct or without calculation.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Dimensions of Steps and Angles on Straight Forming Tools



Radial Depth of Step *D*	Depth *d* of step on tool			Radial Depth of Step *D*	Depth *d* of step on tool		
	When *C* = 10°	When *C* = 15°	When *C* = 20°		When *C* = 10°	When *C* = 15°	When *C* = 20°
0.001	0.00098	0.00096	0.00094	0.040	0.03939	0.03863	0.03758
0.002	0.00197	0.00193	0.00187	0.050	0.04924	0.04829	0.04698
0.003	0.00295	0.00289	0.00281	0.060	0.05908	0.05795	0.05638
0.004	0.00393	0.00386	0.00375	0.070	0.06893	0.06761	0.06577
0.005	0.00492	0.00483	0.00469	0.080	0.07878	0.07727	0.07517
0.006	0.00590	0.00579	0.00563	0.090	0.08863	0.08693	0.08457
0.007	0.00689	0.00676	0.00657	0.100	0.09848	0.09659	0.09396
0.008	0.00787	0.00772	0.00751	0.200	0.19696	0.19318	0.18793
0.009	0.00886	0.00869	0.00845	0.300	0.29544	0.28977	0.28190
0.010	0.00984	0.00965	0.00939	0.400	0.39392	0.38637	0.37587
0.020	0.01969	0.01931	0.01879	0.500	0.49240	0.48296	0.46984
0.030	0.02954	0.02897	0.02819	…	…	…	…

Upper section of table gives depth *d* of step on forming tool for a given dimension *D* that equals the actual depth of the step on the work, measured radially and along the cutting face of the tool (see diagram at left). First, locate depth *D* required on work; then find depth *d* on tool under tool clearance angle *C*. Depth *d* is measured perpendicular to front face of tool.

Angle *A* in Plane of Tool Cutting Face	Angle on tool in plane *x*–*x*						Angle *A* in Plane of Tool Cutting Face	Angle on tool in plane *x*–*x*					
	When *C* = 10°		When *C* = 15°		When *C* = 20°			When *C* = 10°		When *C* = 15°		When *C* = 20°	
5°	4°	55′	4°	50′	4°	42′	50°	49°	34′	49°	1′	48°	14′
10	9	51	9	40	9	24	55	54	35	54	4	53	18
15	14	47	14	31	14	8	60	59	37	59	8	58	26
20	19	43	19	22	18	53	65	64	40	64	14	63	36
25	24	40	24	15	23	40	70	69	43	69	21	68	50
30	29	37	29	9	28	29	75	74	47	74	30	74	5
35	34	35	34	4	33	20	80	79	51	79	39	79	22
40	39	34	39	1	38	15	85	84	55	84	49	84	41
45	44	34	44	0	43	13	…	…		…		…	

Lower section of table gives angles as measured in plane *x*–*x* perpendicular to front face of forming tool (see diagram on right). Find in first column the angle *A* required on work; then find reduced angle in plane *x*–*x* under given clearance angle *C*.

To Find Dimensions of Steps: The upper section of Table 1 is used in determining the dimensions of steps. The radial depth of the step or the actual cutting depth *D* (see left-hand diagram) is given in the first column of the table. The columns that follow give the corresponding depths *d* for a front clearance angle of 10, 15, or 20 degrees. To illustrate the use of the table, suppose a tool is required for turning the part shown in Fig. 1, which has diameters of 0.75, 1.25, and 1.75 inches, respectively. The difference between the largest and the smallest radius is 0.5 inch, which is the depth of one step. Assume that the clearance angle is 15 degrees. First, locate 0.5 in the column headed "Radial Depth of Step *D*"; then find depth *d* in the column headed "when C = 15°." As will be seen, this depth is 0.48296

Copyright 2004, Industrial Press, Inc., New York, NY

inch. Practically the same procedure is followed in determining the depth of the second step on the tool. The difference in the radii in this case equals0.25. This value is not given directly in the table, so first find the depth equivalent to 0.200 and add to it the depth equivalent to 0.050. Thus, we have 0.19318 + 0.04829 = 0.24147. In using Table 1, it is assumed that the top face of the tool is set at the height of the work axis.

To Find Angle: The lower section of Table 1 applies to angles when they are measured relative to the axis of the work. The application of the table will again be illustrated by using the part shown in Fig. 1. The angle used here is 40 degrees (which is also the angle in the plane of the cutting face of the tool). If the clearance angle is 15 degrees, the angle measured in plane *x*–*x* square to the face of the tool is shown by the table to be 39° 1′- a reduction of practically 1 degree.



Fig. 1.



Fig. 2.

If a straight forming tool has rake, the depth *x* of each step (see Fig. 2), measured perpendicular to the front or clearance face, is affected not only by the clearance angle, but by the rake angle *F* and the radii *R* and *r* of the steps on the work. First, it is necessary to find three angles, designated *A*, *B*, and *C*, that are not shown on the drawing.

$$\text{Angle } A = 180° - \text{ rake angle } F$$

$$\sin B = \frac{r \sin A}{R}$$

$$\text{Angle } C = 180° - (A + B)$$

$$y = \frac{R \sin C}{\sin A}$$

$$\text{Angle } D \text{ of tool} = 90° - (E + F)$$

$$\text{Depth } x = y \sin D$$

If the work has two or more shoulders, the depth *x* for other steps on the tool may be determined for each radius *r*. If the work has curved or angular forms, it is more practical to use a tool without rake because its profile, in the plane of the cutting face, duplicates that of the work.

Example: Assume that radius *R* equals 0.625 inch and radius *r* equals 0.375 inch, so that the step on the work has a radial depth of 0.25 inch. The tool has a rake angle *F* of 10 degrees and a clearance angle *E* of 15 degrees. Then angle *A* = 180 – 10 = 170 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

$$\sin B = \frac{0.375 \times 0.17365}{0.625} = 0.10419 \qquad \text{Angle } B = 5°59' \text{ nearly.}$$

$$\text{Angle } C = 180 - (170° + 5°59') = 4°1'$$

$$\text{Dimension } y = \frac{0.625 \times 0.07005}{0.17365} = 0.25212$$

$$\text{Angle } D = 90° - (15 + 10) = 65 \text{ degrees}$$

$$\text{Depth } x \text{ of step} = 0.25212 \times 0.90631 = 0.2285 \text{ inch}$$

Circular Forming Tools.— To provide sufficient peripheral clearance on circular forming tools, the cutting face is offset with relation to the center of the tool a distance *C*, as shown in Fig. 3. Whenever a circular tool has two or more diameters, the difference in the radii of the steps on the tool will not correspond exactly to the difference in the steps on the work. The form produced with the tool also changes, although the change is very slight, unless the amount of offset *C* is considerable. Assume that a circular tool is required to produce the piece *A* having two diameters as shown.



Fig. 3.

If the difference D_1 between the large and small radii of the tool were made equal to dimension *D* required on the work, *D* would be a certain amount oversize, depending upon the offset *C* of the cutting edge. The following formulas can be used to determine the radii of circular forming tools for turning parts to different diameters:

Let *R* = largest radius of tool in inches; *D* = difference in radii of steps on work; *C* = amount cutting edge is offset from center of tool; *r* = required radius in inches; then

$$r = \sqrt{\left(\sqrt{R^2 - C^2} - D\right)^2 + C^2} \qquad (1)$$

If the small radius *r* is given and the large radius *R* is required, then

$$R = \sqrt{\left(\sqrt{r^2 - C^2} + D\right)^2 + C^2} \qquad (2)$$

To illustrate, if *D* (Fig. 3) is to be $\frac{1}{8}$ inch, the large radius *R* is $1\frac{1}{8}$ inches, and *C* is $\frac{5}{32}$ inch, what radius *r* would be required to compensate for the offset *C* of the cutting edge? Inserting these values in Formula (1):

$$r = \sqrt{\sqrt{(1\tfrac{1}{8})^2 - (\tfrac{5}{32})^2} - (\tfrac{1}{8})^2 + (\tfrac{5}{32})^2} = 1.0014 \text{ inches}$$

The value of *r* is thus found to be 1.0014 inches; hence, the diameter = 2 × 1.0014 = 2.0028 inches instead of 2 inches, as it would have been if the cutting edge had been exactly on the center line. Formulas for circular tools used on different makes of screw machines can be simplified when the values *R* and *C* are constant for each size of machine. The accompanying Table 2, *Formulas for Circular Forming Tools*, gives the standard values of *R* and *C* for circular tools used on different automatics. The formulas for determining the

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Formulas for Circular Forming Tools [a]

Make of Machine	Size of Machine	Radius R, Inches	Offset C, Inches	Radius r, Inches
Brown & Sharpe	No. 00	0.875	0.125	$r = \sqrt{(0.8660 - D)^2 + 0.0156}$
	No. 0	1.125	0.15625	$r = \sqrt{(1.1141 - D)^2 + 0.0244}$
	No. 2	1.50	0.250	$r = \sqrt{(1.4790 - D)^2 + 0.0625}$
	No. 6	2.00	0.3125	$r = \sqrt{(1.975 - D)^2 + 0.0976}$
Acme	No. 51	0.75	0.09375	$r = \sqrt{(1.7441 - D)^2 + 0.0088}$
	No. 515	0.75	0.09375	$r = \sqrt{(0.7441 - D)^2 + 0.0088}$
	No. 52	1.0	0.09375	$r = \sqrt{(0.9956 - D)^2 + 0.0088}$
	No. 53	1.1875	0.125	$r = \sqrt{(1.1809 - D)^2 + 0.0156}$
	No. 54	1.250	0.15625	$r = \sqrt{(1.2402 - D)^2 + 0.0244}$
	No. 55	1.250	0.15625	$r = \sqrt{(1.2402 - D)^2 + 0.0244}$
	No. 56	1.50	0.1875	$r = \sqrt{(1.4882 - D)^2 + 0.0352}$
Cleveland	1/4″	0.625	0.03125	$r = \sqrt{(0.6242 - D)^2 + 0.0010}$
	3/8″	0.084375	0.0625	$r = \sqrt{(0.8414 - D)^2 + 0.0039}$
	5/8″	1.15625	0.0625	$r = \sqrt{(1.1546 - D)^2 + 0.0039}$
	7/8″	1.1875	0.0625	$r = \sqrt{(1.1859 - D)^2 + 0.0039}$
	1 1/4″	1.375	0.0625	$r = \sqrt{(1.3736 - D)^2 + 0.0039}$
	2″	1.375	0.0625	
	2 1/4″	1.625	0.125	$r = \sqrt{(1.6202 - D)^2 + 0.0156}$
	2 3/4″	1.875	0.15625	$r = \sqrt{(1.8685 - D)^2 + 0.0244}$
	3 1/4″	1.875	0.15625	
	4 1/4″	2.50	0.250	$r = \sqrt{(2.4875 - D)^2 + 0.0625}$
	6″	2.625	0.250	$r = \sqrt{(2.6131 - D)^2 + 0.0625}$

[a] For notation, see Fig. 3

radius r (see column at right-hand side of table) contain a constant that represents the value of the expression $\sqrt{R^2 - C^2}$ in Formula (1).

Table 3, *Constant for Determining Diameters of Circular Forming Tools* has been compiled to facilitate proportioning tools of this type and gives constants for computing the various diameters of forming tools, when the cutting face of the tool is 1/8, 3/16, 1/4, or 5/16 inch below the horizontal center line. As there is no standard distance for the location of the cutting face, the table has been prepared to correspond with distances commonly used. As an example, suppose the tool is required for a part having three diameters of 1.75, 0.75, and 1.25 inches, respectively, as shown in Fig. 1, and that the largest diameter of the tool is 3 inches and the cutting face is 1/4 inch below the horizontal center line. The first step would

Copyright 2004, Industrial Press, Inc., New York, NY

be to determine approximately the respective diameters of the forming tool and then correct the diameters by the use of the table. To produce the three diameters shown in Fig. 1, with a 3-inch forming tool, the tool diameters would be approximately 2, 3, and 2.5 inches, respectively. The first dimension (2 inches) is 1 inch less in diameter than that of the tool, and the necessary correction should be given in the column "Correction for Difference in Diameter"; but as the table is only extended to half-inch differences, it will be necessary to obtain this particular correction in two steps. On the line for 3-inch diameter and under corrections for ½ inch, we find 0.0085; then in line with 2½ and under the same heading, we find 0.0129, hence the total correction would be 0.0085 + 0.0129 = 0.0214 inch. This correction is added to the approximate diameter, making the exact diameter of the first step 2 + 0.0214 = 2.0214 inches. The next step would be computed in the same way, by noting on the 3-inch line the correction for ½ inch and adding it to the approximate diameter of the second step, giving an exact diameter of 2.5 + 0.0085 + 2.5085 inches. Therefore, to produce the part shown in Fig. 1, the tool should have three steps of 3, 2.0214, and 2.5085 inches, respectively, provided the cutting face is ¼ inch below the center. All diameters are computed in this way, from the largest diameter of the tool.

Tables 4a, 4b, and 4c, *Corrected Diameters of Circular Forming Tools*, are especially applicable to tools used on Brown & Sharpe automatic screw machines. Directions for using these tables are given on page 789.

Circular Tools Having Top Rake.— Circular forming tools without top rake are satisfactory for brass, but tools for steel or other tough metals cut better when there is a rake angle of 10 or 12 degrees. For such tools, the small radius r (see Fig. 3) for an outside radius R may be found by the formula

$$r = \sqrt{P^2 + R^2 - 2PR\cos\theta}$$

To find the value of P, proceed as follows: sin ϕ = small radius on work × sin rake angle ÷ large radius on work. Angle β = rake angle − ϕ. P = large radius on work × sin β ÷ sin rake angle. Angle θ = rake angle + δ. Sin δ = vertical height C from center of tool to center of work ÷ R. It is assumed that the tool point is to be set at the same height as the work center.

Using Tables for "Corrected Diameters of Circular Forming Tools".— Tables 4a, 4b, and 4c are especially applicable to Brown & Sharpe automatic screw machines. The maximum diameter D of forming tools for these machines should be as follows: For No. 00 machine, 1¾ inches; for No. 0 machine, 2¼ inches; for No. 2 machine, 3 inches. To find the other diameters of the tool for any piece to be formed, proceed as follows: Subtract the smallest diameter of the work from the diameter of the work that is to be formed by the required tool diameter; divide the remainder by 2; locate the quotient obtained in the column headed "Length c on Tool," and opposite the figure thus located and in the column headed by the number of the machine used, read off directly the diameter to which the tool is to be made. The quotient obtained, which is located in the column headed "Length c on Tool," is the length c, as shown in Fig. 4.

Example: A piece of work is to be formed on a No. 0 machine to two diameters, one being ¼ inch and one 0.550 inch; find the diameters of the tool. The maximum tool diameter is 2¼ inches, or the diameter that will cut the ¼-inch diameter of the work. To find the other diameter, proceed according to the rule given: 0.550 − ¼ = 0.300; 0.300 ÷ 2 = 0.150. In Table 4b, opposite 0.150, we find that the required tool diameter is 1.9534 inches. These tables are for tools without rakes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Constant for Determining Diameters of Circular Forming Tools

Dia. of Tool	Radius of Tool	Cutting Face 1/8 Inch Below Center			Cutting Face 3/16 Inch Below Center			Cutting Face 1/4 Inch Below Center			Cutting Face 5/16 Inch Below Center		
		Correction for Difference in Diameter			Correction for Difference in Diameter			Correction for Difference in Diameter			Correction for Difference in Diameter		
		1/8 Inch	1/4 Inch	1/2 Inch	1/8 Inch	1/4 Inch	1/2 Inch	1/8 Inch	1/4 Inch	1/2 Inch	1/8 Inch	1/4 Inch	1/2 Inch
1	0.500	…	…	…	…	…	…	…	…	…	…	…	…
1 1/8	0.5625	0.0036	…	…	0.0086	…	…	0.0167	…	…	0.0298	…	…
1 1/4	0.625	0.0028	0.0065	…	0.0067	0.0154	…	0.0128	0.0296	…	0.0221	0.0519	…
1 3/8	0.6875	0.0023	…	…	0.0054	…	…	0.0102	…	…	0.0172	…	…
1 1/2	0.750	0.0019	0.0042	0.0107	0.0045	0.0099	0.0253	0.0083	0.0185	0.0481	0.0138	0.0310	0.0829
1 5/8	0.8125	0.0016	…	…	0.0037	…	…	0.0069	…	…	0.0114	…	…
1 3/4	0.875	0.0014	0.0030	…	0.0032	0.0069	…	0.0058	0.0128	…	0.0095	0.0210	…
1 7/8	0.9375	0.0012	…	…	0.0027	…	…	0.0050	…	…	0.0081	…	…
2	1.000	0.0010	0.0022	0.0052	0.0024	0.0051	0.0121	0.0044	0.0094	0.0223	0.0070	0.0152	0.0362
2 1/8	1.0625	0.0009	…	…	0.0021	…	…	0.0038	…	…	0.0061	…	…
2 1/4	1.125	0.0008	0.0017	…	0.0018	0.0040	…	0.0034	0.0072	…	0.0054	0.0116	…
2 3/8	1.1875	0.0007	…	…	0.0016	…	…	0.0029	…	…	0.0048	…	…
2 1/2	1.250	0.0006	0.0014	0.0031	0.0015	0.0031	0.0071	0.0027	0.0057	0.0129	0.0043	0.0092	0.0208
2 5/8	1.3125	0.0006	…	…	0.0013	…	…	0.0024	…	…	0.0038	…	…
2 3/4	1.375	0.0005	0.0011	…	0.0012	0.0026	…	0.0022	0.0046	…	0.0035	0.0073	…
2 7/8	1.4375	0.0005	…	…	0.0011	…	…	0.0020	…	…	0.0032	…	…
3	1.500	0.0004	0.0009	0.0021	0.0010	0.0021	0.0047	0.0018	0.0038	0.0085	0.0029	0.0061	0.0135
3 1/8	1.5625	0.00004	…	…	0.0009	…	…	0.0017	…	…	0.0027	…	…
3 1/4	1.625	0.0003	0.0008	…	0.0008	0.0018	…	0.0015	0.0032	…	0.0024	0.0051	…
3 3/8	1.6875	0.0003	…	…	0.0008	…	…	0.0014	…	…	0.0023	…	…
3 1/2	1.750	0.0003	0.0007	0.0015	0.0007	0.0015	0.0033	0.0013	0.0028	0.0060	0.0021	0.0044	0.0095
3 5/8	1.8125	0.0003	…	…	0.0007	…	…	0.0012	…	…	0.0019	…	…
3 3/4	1.875	0.0002	0.0006	…	0.0.0006	0.0013	…	0.0011	0.0024	…	0.0018	0.0038	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. Corrected Diameters of Circular Forming Tools

Length *c* on Tool	Number of B. & S. Automatic Screw Machine			Length *c* on Tool	Number of B. & S. Automatic Screw Machine		
	No. 00	No. 0	No. 2		No. 00	No. 0	No. 2
0.001	1.7480	2.2480	2.9980	0.058	1.6353	2.1352	2.8857
0.002	1.7460	2.2460	2.9961	0.059	1.6333	2.1332	2.8837
0.003	1.7441	2.2441	2.9941	0.060	1.6313	2.1312	2.8818
0.004	1.7421	2.2421	2.9921	0.061	1.6294	2.1293	2.8798
0.005	1.7401	2.2401	2.9901	0.062	1.6274	2.1273	2.8778
0.006	1.7381	2.2381	2.9882	1/16	1.6264	2.1263	2.8768
0.007	1.7362	2.2361	2.9862	0.063	1.6254	2.1253	2.8759
0.008	1.7342	2.2341	2.9842	0.064	1.6234	2.1233	2.8739
0.009	1.7322	2.2321	2.9823	0.065	1.6215	2.1213	2.8719
0.010	1.7302	2.2302	2.9803	0.066	1.6195	2.1194	2.8699
0.011	1.7282	2.2282	2.9783	0.067	1.6175	2.1174	2.8680
0.012	1.7263	2.2262	2.9763	0.068	1.6155	2.1154	2.8660
0.013	1.7243	2.2243	2.9744	0.069	1.6136	2.1134	2.8640
0.014	1.7223	2.2222	2.9724	0.070	1.6116	2.1115	2.8621
0.015	1.7203	2.2203	2.9704	0.071	1.6096	2.1095	2.8601
1/64	1.7191	2.2191	2.9692	0.072	1.6076	2.1075	2.8581
0.016	1.7184	2.2183	2.9685	0.073	1.6057	2.1055	2.8561
0.017	1.7164	2.2163	2.9665	0.074	1.6037	2.1035	2.8542
0.018	1.7144	2.2143	2.9645	0.075	1.6017	2.1016	2.8522
0.019	1.7124	2.2123	2.9625	0.076	1.5997	2.0996	2.8503
0.020	1.7104	2.2104	2.9606	0.077	1.5978	2.0976	2.8483
0.021	1.7085	2.2084	2.9586	0.078	1.5958	2.0956	2.8463
0.022	1.7065	2.2064	2.9566	5/64	1.5955	2.0954	2.8461
0.023	1.7045	2.2045	2.9547	0.079	1.5938	2.0937	2.8443
0.024	1.7025	2.2025	2.9527	0.080	1.5918	2.0917	2.8424
0.025	1.7005	2.2005	2.9507	0.081	1.5899	2.0897	2.8404
0.026	1.6986	2.1985	2.9488	0.082	1.5879	2.0877	2.8384
0.027	1.6966	2.1965	2.9468	0.083	1.5859	2.0857	2.8365
0.028	1.6946	2.1945	2.9448	0.084	1.5839	2.0838	2.8345
0.029	1.6926	2.1925	2.9428	0.085	1.5820	2.0818	2.8325
0.030	1.6907	2.1906	2.9409	0.086	1.5800	2.0798	2.8306
0.031	1.6887	2.1886	2.9389	0.087	1.5780	2.0778	2.8286
1/32	1.6882	2.1881	2.9384	0.088	1.5760	2.0759	2.8266
0.032	1.6867	2.1866	2.9369	0.089	1.5740	2.0739	2.8247
0.033	1.6847	2.1847	2.9350	0.090	1.5721	2.0719	2.8227
0.034	1.6827	2.1827	2.9330	0.091	1.5701	2.0699	2.8207
0.035	1.6808	2.1807	2.9310	0.092	1.5681	2.0679	2.8187
0.036	1.6788	2.1787	2.9290	0.093	1.5661	2.0660	2.8168
0.037	1.6768	2.1767	2.9271	3/32	1.5647	2.0645	2.8153
0.038	1.6748	2.1747	2.9251	0.094	1.5642	2.0640	2.8148
0.039	1.6729	2.1727	2.9231	0.095	1.5622	2.0620	2.8128
0.040	1.6709	2.1708	2.9211	0.096	1.5602	2.0600	2.8109
0.041	1.6689	2.1688	2.9192	0.097	1.5582	2.0581	2.8089
0.042	1.6669	2.1668	2.9172	0.098	1.5563	2.0561	2.8069
0.043	1.6649	2.1649	2.9152	0.099	1.5543	2.0541	2.8050
0.044	1.6630	2.1629	2.9133	0.100	1.5523	2.0521	2.8030
0.045	1.6610	2.1609	2.9113	0.101	1.5503	2.0502	2.8010
0.046	1.6590	2.1589	2.9093	0.102	1.5484	2.0482	2.7991
3/64	1.6573	2.1572	2.9076	0.103	1.5464	2.0462	2.7971
0.047	1.6570	2.1569	2.9073	0.104	1.5444	2.0442	2.7951
0.048	1.6550	2.1549	2.9054	0.105	1.5425	2.0422	2.7932
0.049	1.6531	2.1529	2.9034	0.106	1.5405	2.0403	2.7912
0.050	1.6511	2.1510	2.9014	0.107	1.5385	2.0383	2.7892
0.051	1.6491	2.1490	2.8995	0.108	1.5365	2.0363	2.7873
0.052	1.6471	2.1470	2.8975	0.109	1.5346	2.0343	2.7853
0.053	1.6452	2.1451	2.8955	7/64	1.5338	2.0336	2.7846
0.054	1.6432	2.1431	2.8936	0.110	1.5326	2.0324	2.7833
0.055	1.6412	2.1411	2.8916	0.111	1.5306	2.0304	2.7814
0.056	1.6392	2.1391	2.8896	0.112	1.5287	2.0284	2.7794
0.057	1.6373	2.1372	2.8877	0.113	1.5267	2.0264	2.7774

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. Corrected Diameters of Circular Forming Tools *(Continued)*

Length *c* on Tool	Number of B. & S. Automatic Screw Machine			Length *c* on Tool	Number of B. & S. Automatic Screw Machine		
	No. 00	No. 0	No. 2		No. 00	No. 0	No. 2
0.113	1.5267	2.0264	2.7774	0.171	1.4124	1.9119	2.6634
0.114	1.5247	2.0245	2.7755	11/64	1.4107	1.9103	2.6617
0.115	1.5227	2.0225	2.7735	0.172	1.4104	1.9099	2.6614
0.116	1.5208	2.0205	2.7715	0.173	1.4084	1.9080	2.6595
0.117	1.5188	2.0185	2.7696	0.174	1.4065	1.9060	2.6575
0.118	1.5168	2.0166	2.7676	0.175	1.4045	1.9040	2.6556
0.119	1.5148	2.0146	2.7656	0.176	1.4025	1.9021	2.6536
0.120	1.5129	2.0126	2.7637	0.177	1.4006	1.9001	2.6516
0.121	1.5109	2.0106	2.7617	0.178	1.3986	1.8981	2.6497
0.122	1.5089	2.0087	2.7597	0.179	1.3966	1.8961	2.6477
0.123	1.5070	2.0067	2.7578	0.180	1.3947	1.8942	2.6457
0.124	1.5050	2.0047	2.7558	0.181	1.3927	1.8922	2.6438
0.125	1.5030	2.0027	2.7538	0.182	1.3907	1.8902	2.6418
0.126	1.5010	2.0008	2.7519	0.183	1.3888	1.8882	2.6398
0.127	1.4991	1.9988	2.7499	0.184	1.3868	1.8863	2.6379
0.128	1.4971	1.9968	2.7479	0.185	1.3848	1.8843	2.6359
0.129	1.4951	1.9948	2.7460	0.186	1.3829	1.8823	2.6339
0.130	1.4932	1.9929	2.7440	0.187	1.3809	1.8804	2.6320
0.131	1.4912	1.9909	2.7420	3/16	1.3799	1.8794	2.6310
0.132	1.4892	1.9889	2.7401	0.188	1.3789	1.8784	2.6300
0.133	1.4872	1.9869	2.7381	0.189	1.3770	1.8764	2.6281
0.134	1.4853	1.9850	2.7361	0.190	1.3750	1.8744	2.6261
0.135	1.4833	1.9830	2.7342	0.191	1.3730	1.8725	2.6241
0.136	1.4813	1.9810	2.7322	0.192	1.3711	1.8705	2.6222
0.137	1.4794	1.9790	2.7302	0.193	1.3691	1.8685	2.6202
0.138	1.4774	1.9771	2.7282	0.194	1.3671	1.8665	2.6182
0.139	1.4754	1.9751	2.7263	0.195	1.3652	1.8646	2.6163
0.140	1.4734	1.9731	2.7243	0.196	1.3632	1.8626	2.6143
9/64	1.4722	1.9719	2.7231	0.197	1.3612	1.8606	2.6123
0.141	1.4715	1.9711	2.7224	0.198	1.3592	1.8587	2.6104
0.142	1.4695	1.9692	2.7204	0.199	1.3573	1.8567	2.6084
0.143	1.4675	1.9672	2.7184	0.200	1.3553	1.8547	2.6064
0.144	1.4655	1.9652	2.7165	0.201	…	1.8527	2.6045
0.145	1.4636	1.9632	2.7145	0.202	…	1.8508	2.6025
0.146	1.4616	1.9613	2.7125	0.203	…	1.8488	2.6006
0.147	1.4596	1.9593	2.7106	13/64	…	1.8486	2.6003
0.148	1.4577	1.9573	2.7086	0.204	…	1.8468	2.5986
0.149	1.4557	1.9553	2.7066	0.205	…	1.8449	2.5966
0.150	1.4537	1.9534	2.7047	0.206	…	1.8429	2.5947
0.151	1.4517	1.9514	2.7027	0.207	…	1.8409	2.5927
0.152	1.4498	1.9494	2.7007	0.208	…	1.8390	2.5908
0.153	1.4478	1.9474	2.6988	0.209	…	1.8370	2.5888
0.154	1.4458	1.9455	2.6968	0.210	…	1.8350	2.5868
0.155	1.4439	1.9435	2.6948	0.211	…	1.8330	2.5849
0.156	1.4419	1.9415	2.6929	0.212	…	1.8311	2.5829
5/32	1.4414	1.9410	2.6924	0.213	…	1.8291	2.5809
0.157	1.4399	1.9395	2.6909	0.214	…	1.8271	2.5790
0.158	1.4380	1.9376	2.6889	0.215	…	1.8252	2.5770
0.159	1.4360	1.9356	2.6870	0.216	…	1.8232	2.5751
0.160	1.4340	1.9336	2.6850	0.217	…	1.8212	2.5731
0.161	1.4321	1.9317	2.6830	0.218	…	1.8193	2.5711
0.162	1.4301	1.9297	2.6811	7/32	…	1.8178	2.5697
0.163	1.4281	1.9277	2.6791	0.219	…	1.8173	2.5692
0.164	1.4262	1.9257	2.6772	0.220	…	1.8153	2.5672
0.165	1.4242	1.9238	2.6752	0.221	…	1.8133	2.5653
0.166	1.4222	1.9218	2.6732	0.222	…	1.8114	2.5633
0.167	1.4203	1.9198	2.6713	0.223	…	1.8094	2.5613
0.168	1.4183	1.9178	2.6693	0.224	…	1.8074	2.5594
0.169	1.4163	1.9159	2.6673	0.225	…	1.8055	2.5574
0.170	1.4144	1.9139	2.6654	0.226	…	1.8035	2.5555

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. Corrected Diameters of Circular Forming Tools

Length *c* on Tool	Number of B. & S. Screw Machine		Length *c* on Tool	Number of B. & S. Screw Machine		Length *c* on Tool	Number 2 B. & S. Machine
	No. 0	No. 2		No. 0	No. 2		
0.227	1.8015	2.5535	0.284	1.6894	2.4418	0.341	2.3303
0.228	1.7996	2.5515	0.285	1.6874	2.4398	0.342	2.3284
0.229	1.7976	2.5496	0.286	1.6854	2.4378	0.343	2.3264
0.230	1.7956	2.5476	0.287	1.6835	2.4359	11/32	2.3250
0.231	1.7936	2.5456	0.288	1.6815	2.4340	0.344	2.3245
0.232	1.7917	2.5437	0.289	1.6795	2.4320	0.345	2.3225
0.233	1.7897	2.5417	0.290	1.6776	2.4300	0.346	2.3206
0.234	1.7877	2.5398	0.291	1.6756	2.4281	0.347	2.3186
15/64	1.7870	2.5390	0.292	1.6736	2.4261	0.348	2.3166
0.235	1.7858	2.5378	0.293	1.6717	2.4242	0.349	2.3147
0.236	1.7838	2.5358	0.294	1.6697	2.4222	0.350	2.3127
0.237	1.7818	2.5339	0.295	1.6677	2.4203	0.351	2.3108
0.238	1.7799	2.5319	0.296	1.6658	2.4183	0.352	2.3088
0.239	1.7779	2.5300	19/64	1.6641	2.4166	0.353	2.3069
0.240	1.7759	2.5280	0.297	1.6638	2.4163	0.354	2.3049
0.241	1.7739	2.5260	0.298	1.6618	2.4144	0.355	2.3030
0.242	1.7720	2.5241	0.299	1.6599	2.4124	0.356	2.3010
0.243	1.7700	2.5221	0.300	1.6579	2.4105	0.357	2.2991
0.244	1.7680	2.5201	0.301	…	2.4085	0.358	2.2971
0.245	1.7661	2.5182	0.302	…	2.4066	0.359	2.2952
0.246	1.7641	2.5162	0.303	…	2.4046	23/64	2.2945
0.247	1.7621	2.5143	0.304	…	2.4026	0.360	2.2932
0.248	1.7602	2.5123	0.305	…	2.4007	0.361	2.2913
0.249	1.7582	2.5104	0.306	…	2.3987	0.362	2.2893
0.250	1.7562	2.5084	0.307	…	2.3968	0.363	2.2874
0.251	1.7543	2.5064	0.308	…	2.3948	0.364	2.2854
0.252	1.7523	2.5045	0.309	…	2.3929	0.365	2.2835
0.253	1.7503	2.5025	0.310	…	2.3909	0.366	2.2815
0.254	1.7484	2.5005	0.311	…	2.3890	0.367	2.2796
0.255	1.7464	2.4986	0.312	…	2.3870	0.368	2.2776
0.256	1.7444	2.4966	5/16	…	2.3860	0.369	2.2757
0.257	1.7425	2.4947	0.313	…	2.3851	0.370	2.2737
0.258	1.7405	2.4927	0.314	…	2.3831	0.371	2.2718
0.259	1.7385	2.4908	0.315	…	2.3811	0.372	2.2698
0.260	1.7366	2.4888	0.316	…	2.3792	0.373	2.2679
0.261	1.7346	2.4868	0.317	…	2.3772	0.374	2.2659
0.262	1.7326	2.4849	0.318	…	2.3753	0.375	2.2640
0.263	1.7306	2.4829	0.319	…	2.3733	0.376	2.2620
0.264	1.7287	2.4810	0.320	…	2.3714	0.377	2.2601
0.265	1.7267	2.4790	0.321	…	2.3694	0.378	2.2581
17/64	1.7255	2.4778	0.322	…	2.3675	0.379	2.2562
0.266	1.7248	2.4770	0.323	…	2.3655	0.380	2.2542
0.267	1.7228	2.4751	0.324	…	2.3636	0.381	2.2523
0.268	1.7208	2.4731	0.325	…	2.3616	0.382	2.2503
0.269	1.7189	2.4712	0.326	…	2.3596	0.383	2.2484
0.270	1.7169	2.4692	0.327	…	2.3577	0.384	2.2464
0.271	1.7149	2.4673	0.328	…	2.3557	0.385	2.2445
0.272	1.7130	2.4653	21/64	…	2.3555	0.386	2.2425
0.273	1.7110	2.4633	0.329	…	2.3538	0.387	2.2406
0.274	1.7090	2.4614	0.330	…	2.3518	0.388	2.2386
0.275	1.7071	2.4594	0.331	…	2.3499	0.389	2.2367
0.276	1.7051	2.4575	0.332	…	2.3479	0.390	2.2347
0.277	1.7031	2.4555	0.333	…	2.3460	25/64	2.2335
0.278	1.7012	2.4535	0.334	…	2.3440	0.391	2.2328
0.279	1.6992	2.4516	0.335	…	2.3421	0.392	2.2308
0.280	1.6972	2.4496	0.336	…	2.3401	0.393	2.2289
0.281	1.6953	2.4477	0.337	…	2.3381	0.394	2.2269
9/32	1.6948	2.4472	0.338	…	2.3362	0.395	2.2250
0.282	1.6933	2.4457	0.339	…	2.3342	0.396	2.2230
0.283	1.6913	2.4438	0.340	…	2.3323	0.397	2.2211

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4c. Corrected Diameters of Circular Forming Tools

Length *c* on Tool	Number 2 B. & S. Machine	Length *c* on Tool	Number 2 B. & S. Machine	Length *c* on Tool	Number 2 B. & S. Machine	Length *c* on Tool	Number 2 B. & S. Machine
0.398	2.2191	0.423	2.1704	0.449	2.1199	0.474	2.0713
0.399	2.2172	0.424	2.1685	0.450	2.1179	0.475	2.0694
0.400	2.2152	0.425	2.1666	0.451	2.1160	0.476	2.0674
0.401	2.2133	0.426	2.1646	0.452	2.1140	0.477	2.0655
0.402	2.2113	0.427	2.1627	0.453	2.1121	0.478	2.0636
0.403	2.2094	0.428	2.1607	29/64	2.1118	0.479	2.0616
0.404	2.2074	0.429	2.1588	0.454	2.1101	0.480	2.0597
0.405	2.2055	0.430	2.1568	0.455	2.1082	0.481	2.0577
0.406	2.2035	0.431	2.1549	0.456	2.1063	0.482	2.0558
13/32	2.2030	0.432	2.1529	0.457	2.1043	0.483	2.0538
0.407	2.2016	0.433	2.1510	0.458	2.1024	0.484	2.0519
0.408	2.1996	0.434	2.1490	0.459	2.1004	0.485	2.0500
0.409	2.1977	0.435	2.1471	0.460	2.0985	0.486	2.0480
0.410	2.1957	0.436	2.1452	0.461	2.0966	0.487	2.0461
0.411	2.1938	0.437	2.1432	0.462	2.0946	0.488	2.0441
0.412	2.1919	7/16	2.1422	0.463	2.0927	0.489	2.0422
0.413	2.1899	0.438	2.1413	0.464	2.0907	0.490	2.0403
0.414	2.1880	0.439	2.1393	0.465	2.0888	0.491	2.0383
0.415	2.1860	0.440	2.1374	0.466	2.0868	0.492	2.0364
0.416	2.1841	0.441	2.1354	0.467	2.0849	0.493	2.0344
0.417	2.1821	0.442	2.1335	0.468	2.0830	0.494	2.0325
0.418	2.1802	0.443	2.1315	15/32	2.0815	0.495	2.0306
0.419	2.1782	0.444	2.1296	0.469	2.0810	0.496	2.0286
0.420	2.1763	0.445	2.1276	0.470	2.0791	0.497	2.0267
0.421	2.1743	0.446	2.1257	0.471	2.0771	0.498	2.0247
27/64	2.1726	0.447	2.1237	0.472	2.0752	0.499	2.0228
0.422	2.1724	0.448	2.1218	0.473	2.0733	0.500	2.0209

Dimensions of Forming Tools for B. & S. Automatic Screw Machines



Fig. 4.

No. of Machine	Max. Dia., *D*	*h*	*T*	*W*
00	1¾	⅛	⅜–16	¼
0	2¼	5/32	½–14	5/16
2	3	¼	⅝–12	⅜
6	4	5/16	¾–12	⅜

Arrangement of Circular Tools.— When applying circular tools to automatic screw machines, their arrangement has an important bearing on the results obtained. The various ways of arranging the circular tools, with relation to the rotation of the spindle, are shown at A, B, C, and D in Fig. 5. These diagrams represent the view obtained when looking toward the chuck. The arrangement shown at A gives good results on long forming operations on brass and steel because the pressure of the cut on the front tool is downward; the support is more rigid than when the forming tool is turned upside down on the front slide, as shown at B; here the stock, turning up toward the tool, has a tendency to lift the cross-slide, causing chattering; therefore, the arrangement shown at A is recommended when a high-quality finish is desired. The arrangement at B works satisfactorily for short steel pieces that do not require a high finish; it allows the chips to drop clear of the work, and is especially advantageous when making screws, when the forming and cut-off tools operate after the die, as no time is lost in reversing the spindle. The arrangement at C is recommended for heavy cutting on large work, when both tools are used for forming the piece; a

Copyright 2004, Industrial Press, Inc., New York, NY

rigid support is then necessary for both tools and a good supply of oil is also required. The arrangement at D is objectionable and should be avoided; it is used only when a left-hand thread is cut on the piece and when the cut-off tool is used on the front slide, leaving the heavy cutting to be performed from the rear slide. In all "cross-forming" work, it is essential that the spindle bearings be kept in good condition, and that the collet or chuck has a parallel contact upon the bar that is being formed.



Fig. 5.

Feeds and Speeds for Forming Tools.— Approximate feeds and speeds for forming tools are given in the table beginning on page 1132. The feeds and speeds are average values, and if the job at hand has any features out of the ordinary, the figures given should be altered accordingly.

Dimensions for Circular Cut-Off Tools



Dia. of Stock	Soft Brass, Copper a = 23 Deg.		Norway Iron, Machine Steel a = 15 Deg.		Drill Rod, Tool Steel a = 12 Deg.	
	T	x	T	x	T	x
1/16	0.031	0.013	0.039	0.010	0.043	0.009
1/8	0.044	0.019	0.055	0.015	0.062	0.013
3/16	0.052	0.022	0.068	0.018	0.076	0.016
1/4	0.062	0.026	0.078	0.021	0.088	0.019
5/16	0.069	0.029	0.087	0.023	0.098	0.021
3/8	0.076	0.032	0.095	0.025	0.107	0.023
7/16	0.082	0.035	0.103	0.028	0.116	0.025
1/2	0.088	0.037	0.110	0.029	0.124	0.026
9/16	0.093	0.039	0.117	0.031	0.131	0.028
5/8	0.098	0.042	0.123	0.033	0.137	0.029
11/16	0.103	0.044	0.129	0.035	0.145	0.031
3/4	0.107	0.045	0.134	0.036	0.152	0.032
13/16	0.112	0.047	0.141	0.038	0.158	0.033
7/8	0.116	0.049	0.146	0.039	0.164	0.035
15/16	0.120	0.051	0.151	0.040	0.170	0.036
1	0.124	0.053	0.156	0.042	0.175	0.037

The length of the blade equals radius of stock $R + x + r + 1/32$ inch (for notation, see illustration above); $r = 1/16$ inch for 3/8- to 3/4-inch stock, and 3/32 inch for 3/4- to 1-inch stock.

Copyright 2004, Industrial Press, Inc., New York, NY

MILLING CUTTERS

Selection of Milling Cutters

The most suitable type of milling cutter for a particular milling operation depends on such factors as the kind of cut to be made, the material to be cut, the number of parts to be machined, and the type of milling machine available. Solid cutters of small size will usually cost less, initially, than inserted blade types; for long-run production, inserted-blade cutters will probably have a lower overall cost. Depending on either the material to be cut or the amount of production involved, the use of carbide-tipped cutters in preference to high-speed steel or other cutting tool materials may be justified.

Rake angles depend on both the cutter material and the work material. Carbide and cast alloy cutting tool materials generally have smaller rake angles than high-speed steel tool materials because of their lower edge strength and greater abrasion resistance. Soft work materials permit higher radial rake angles than hard materials; thin cutters permit zero or practically zero axial rake angles; and wide cutters operate smoother with high axial rake angles. See *Rake Angles for Milling Cutters* on page 826.

Cutting edge relief or clearance angles are usually from 3 to 6 degrees for hard or tough materials, 4 to 7 degrees for average materials, and 6 to 12 degrees for easily machined materials. See *Clearance Angles for Milling Cutter Teeth* on page 825.

The number of teeth in the milling cutter is also a factor that should be given consideration, as explained in the next paragraph.

Number of Teeth in Milling Cutters.— In determining the number of teeth a milling cutter should have for optimum performance, there is no universal rule.

There are, however, two factors that should be considered in making a choice: 1) The number of teeth should never be so great as to reduce the chip space between the teeth to a point where a free flow of chips is prevented; and 2) The chip space should be smooth and without sharp corners that would cause clogging of the chips in the space.

For milling ductile materials that produce a continuous and curled chip, a cutter with large chip spaces is preferable. Such coarse tooth cutters permit an easier flow of the chips through the chip space than would be obtained with fine tooth cutters, and help to eliminate cutter "chatter." For cutting operations in thin materials, fine tooth cutters reduce cutter and workpiece vibration and the tendency for the cutter teeth to "straddle" the workpiece and dig in. For slitting copper and other soft nonferrous materials, teeth that are either chamfered or alternately flat and V-shaped are best.

As a general rule, to give satisfactory performance the number of teeth in milling cutters should be such that *no more than two teeth at a time are engaged in the cut*. Based on this rule, the following formulas are recommended:

For face milling cutters,

$$T = \frac{6.3D}{W} \tag{1}$$

For peripheral milling cutters,

$$T = \frac{12.6D\cos A}{D + 4d} \tag{2}$$

where T = number of teeth in cutter; D = cutter diameter in inches; W = width of cut in inches; d = depth of cut in inches; and A = helix angle of cutter.

To find the number of teeth that a cutter should have when other than two teeth in the cut at the same time is desired, Formulas (1) and (2) should be divided by 2 and the result multiplied by the number of teeth desired in the cut.

Copyright 2004, Industrial Press, Inc., New York, NY

Example: Determine the required number of teeth in a face mill where $D = 6$ inches and $W = 4$ inches. Using Formula (1),

$$T = \frac{6.3 \times 6}{4} = 10 \text{ teeth, approximately}$$

Example: Determine the required number of teeth in a plain milling cutter where $D = 4$ inches and $d = \frac{1}{4}$ inch. Using Formula (2),

$$T = \frac{12.6 \times 4 \times \cos 0^{\circ}}{4 + (4 \times \frac{1}{4})} = 10 \text{ teeth, approximately}$$

In *high speed milling* with sintered carbide, high-speed steel, and cast non-ferrous cutting tool materials, a formula that permits full use of the power available at the cutter but prevents overloading of the motor driving the milling machine is:

$$T = \frac{K \times H}{F \times N \times d \times W} \quad (3)$$

where T = number of cutter teeth; H = horsepower available at the cutter; F = feed per tooth in inches; N = revolutions per minute of cutter; d = depth of cut in inches; W = width of cut in inches; and K = a constant which may be taken as 0.65 for average steel, 1.5 for cast iron, and 2.5 for aluminum. These values are conservative and take into account dulling of the cutter in service.

Example: Determine the required number of teeth in a sintered carbide tipped face mill for high speed milling of 200 Brinell hardness alloy steel if $H = 10$ horsepower; $F = 0.008$ inch; $N = 272$ rpm; $d = 0.125$ inch; $W = 6$ inches; and K for alloy steel is 0.65. Using Formula (3),

$$T = \frac{0.65 \times 10}{0.008 \times 272 \times 0.125 \times 6} = 4 \text{ teeth, approximately}$$

American National Standard Milling Cutters.— According to American National Standard ANSI/ASME B94.19-1997 milling cutters may be classified in two general ways, which are given as follows:

By Type of Relief on Cutting Edges: Milling cutters may be described on the basis of one of two methods of providing relief for the cutting edges. *Profile sharpened* cutters are those on which relief is obtained and which are resharpened by grinding a narrow land back of the cutting edges. Profile sharpened cutters may produce flat, curved, or irregular surfaces. *Form relieved* cutters are those which are so relieved that by grinding only the faces of the teeth the original form is maintained throughout the life of the cutters. Form relieved cutters may produce flat, curved or irregular surfaces.

By Method of Mounting: Milling cutters may be described by one of two methods used to mount the cutter. *Arbor type* cutters are those which have a hole for mounting on an arbor and usually have a keyway to receive a driving key. These are sometimes called *Shell type*. *Shank type* cutters are those which have a straight or tapered shank to fit the machine tool spindle or adapter.

Explanation of the "Hand" of Milling Cutters.— In the ANSI Standard the terms "right hand" and "left hand" are used to describe hand of rotation, hand of cutter and hand of flute helix.

Hand of Rotation or Hand of Cut: is described as either "right hand" if the cutter revolves counterclockwise as it cuts when viewed from a position in front of a horizontal milling machine and facing the spindle or "left hand" if the cutter revolves clockwise as it cuts when viewed from the same position.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Plain Milling Cutters *ANSI/ASME B94.19-1997*

Cutter Diameter			Range of Face Widths, Nom.[a]	Hole Diameter		
Nom.	Max.	Min.		Nom.	Max.	Min.
Light-duty Cutters[b]						
2½	2.515	2.485	3/16, 1/4, 5/16, 3/8, 1/2, 5/8, 3/4, 1, 1½, 2 and 3	1	1.00075	1.0000
3	3.015	2.985	3/16, 1/4, 5/16, 3/8, 5/8, 3/4, and 1½	1	1.00075	1.0000
3	3.015	2.985	1/2, 5/8, 3/4, 1, 1¼, 1½, 2 and 3	1¼	1.2510	1.2500
4	4.015	3.985	1/4, 5/16 and 3/8	1	1.00075	1.0000
4	4.015	3.985	3/8, 1/2, 5/8, 3/4, 1, 1½, 2, 3 and 4	1¼	1.2510	1.2500
Heavy-duty Cutters[c]						
2½	2.515	2.485	2	1	1.00075	1.0000
2½	2.515	2.485	4	1	1.0010	1.0000
3	3.015	2.985	2, 2½, 3, 4 and 6	1¼	1.2510	1.2500
4	4.015	3.985	2, 3, 4 and 6	1½	1.5010	1.5000
High-helix Cutters[d]						
3	3.015	2.985	4 and 6	1¼	1.2510	1.2500
4	4.015	3.985	8	1½	1.5010	1.5000

[a] *Tolerances on Face Widths:* Up to 1 inch, inclusive, ± 0.001 inch; over 1 to 2 inches, inclusive, +0.010, –0.000 inch; over 2 inches, +0.020, –0.000 inch.

[b] Light-duty plain milling cutters with face widths under 3/4 inch have straight teeth. Cutters with 3/4-inch face and wider have helix angles of not less than 15 degrees nor greater than 25 degrees.

[c] Heavy-duty plain milling cutters have a helix angle of not less than 25 degrees nor greater than 45 degrees.

[d] High-helix plain milling cutters have a helix angle of not less than 45 degrees nor greater than 52 degrees.

All dimensions are in inches. All cutters are high-speed steel. Plain milling cutters are of cylindrical shape, having teeth on the peripheral surface only.

Hand of Cutter: Some types of cutters require special consideration when referring to their hand. These are principally cutters with unsymmetrical forms, face type cutters, or cutters with threaded holes. *Symmetrical* cutters may be reversed on the arbor in the same axial position and rotated in the cutting direction without altering the contour produced on the work-piece, and may be considered as either right or left hand. *Unsymmetrical* cutters reverse the contour produced on the work-piece when reversed on the arbor in the same axial position and rotated in the cutting direction. A *single-angle* cutter is considered to be a right-hand cutter if it revolves counterclockwise, or a left-hand cutter if it revolves clockwise, when cutting as viewed from the side of the larger diameter. The *hand of rotation* of a single angle milling cutter need not necessarily be the same as its *hand of cutter*. A *single corner rounding* cutter is considered to be a right-hand cutter if it revolves counterclockwise, or a left-hand cutter if it revolves clockwise, when cutting as viewed from the side of the smaller diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Side Milling Cutters *ANSI/ASME B94.19-1997*

Cutter Diameter			Range of Face Widths Nom.[a]	Hole Diameter		
Nom.	Max.	Min.		Nom.	Max.	Min.
Side Cutters[b]						
2	2.015	1.985	3/16, 1/4, 3/8	5/8	0.62575	0.6250
2 1/2	2.515	2.485	1/4, 3/8, 1/2	7/8	0.87575	0.8750
3	3.015	2.985	1/4, 5/16, 3/8, 7/16, 1/2	1	1.00075	1.0000
4	4.015	3.985	1/4, 3/8, 1/2, 5/8, 3/4, 7/8	1	1.00075	1.0000
4	4.015	3.985	1/2, 5/8, 3/4	1 1/4	1.2510	1.2500
5	5.015	4.985	1/2, 5/8, 3/4	1	1.00075	1.0000
5	5.015	4.985	1/2, 5/8, 3/4, 1	1 1/4	1.2510	1.2500
6	6.015	5.985	1/2	1	1.00075	1.0000
6	6.015	5.985	1/2, 5/8, 3/4, 1	1 1/4	1.2510	1.2500
7	7.015	6.985	3/4	1 1/4	1.2510	1.2500
7	7.015	6.985	3/4	1 1/2	1.5010	1.5000
8	8.015	7.985	3/4, 1	1 1/4	1.2510	1.2500
8	8.015	7.985	3/4, 1	1 1/2	1.5010	1.5000
Staggered-tooth Side Cutters[c]						
2 1/2	2.515	2.485	1/4, 5/16, 3/8, 1/2	7/8	0.87575	0.8750
3	3.015	2.985	3/16, 1/4, 5/16, 3/8	1	1.00075	1.0000
3	3.015	2.985	1/2, 5/8, 3/4	1 1/4	1.2510	1.2500
4	4.015	3.985	1/4, 5/16, 3/8, 7/16, 1/2, 5/8, 3/4 and 7/8	1 1/4	1.2510	1.2500
5	5.015	4.985	1/2, 5/8, 3/4	1 1/4	1.2510	1.2500
6	6.015	5.985	3/8, 1/2, 5/8, 3/4, 7/8, 1	1 1/4	1.2510	1.2500
8	8.015	7.985	3/8, 1/2, 5/8, 3/4, 1	1 1/2	1.5010	1.5000
Half Side Cutters[d]						
4	4.015	3.985	3/4	1 1/4	1.2510	1.2500
5	5.015	4.985	3/4	1 1/4	1.2510	1.2500
6	6.015	5.985	3/4	1 1/4	1.2510	1.2500

[a] *Tolerances on Face Widths:* For side cutters, +0.002, –0.001 inch; for staggered-tooth side cutters up to 3/4 inch face width, inclusive, +0.000 –0.0005 inch, and over 3/4 to 1 inch, inclusive, +0.000 – 0.0010 inch; and for half side cutters, +0.015, –0.000 inch.

[b] Side milling cutters have straight peripheral teeth and side teeth on both sides.

[c] Staggered-tooth side milling cutters have peripheral teeth of alternate right- and left-hand helix and alternate side teeth.

[d] Half side milling cutters have side teeth on one side only. The peripheral teeth are helical of the same hand as the cut. Made either with right-hand or left-hand cut.

All dimensions are in inches. All cutters are high-speed steel. Side milling cutters are of cylindrical shape, having teeth on the periphery and on one or both sides.

Hand of Flute Helix: Milling cutters may have *straight flutes* which means that their cutting edges are in planes parallel to the cutter axis. Milling cutters with flute helix in one direction only are described as having a right-hand helix if the flutes twist away from the observer in a clockwise direction when viewed from either end of the cutter or as having a left-hand helix if the flutes twist away from the observer in a counterclockwise direction when viewed from either end of the cutter. *Staggered tooth cutters* are milling cutters with every other flute of opposite (right and left hand) helix.

An illustration describing the various milling cutter elements of both a profile cutter and a form-relieved cutter is given on page 801.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Staggered Teeth, T-Slot Milling Cutters with Brown & Sharpe Taper and Weldon Shanks *ANSI/ASME B94.19-1997*



Bolt Size	Cutter Dia., *D*	Face Width, *W*	Neck Dia., *N*	With B. & S. Taper[a,b] Length, *L*	With B. & S. Taper[a,b] Taper No.	With Weldon Shank Length, *L*	With Weldon Shank Dia., *S*
1/4	9/16	15/64	17/64	…	…	2 19/32	1/2
5/16	21/32	17/64	21/64	…	…	2 11/16	1/2
3/8	25/32	21/64	13/32	…	…	3 1/4	3/4
1/2	31/32	25/64	17/32	5	7	3 7/16	3/4
5/8	1 1/4	31/64	21/32	5 1/4	7	3 15/16	1
3/4	1 15/32	5/8	25/32	6 7/8	9	4 7/16	1
1	1 27/32	53/64	1 1/32	7 1/4	9	4 13/16	1 1/4

[a] For dimensions of Brown & Sharpe taper shanks, see information given on page 936.

[b] Brown & Sharpe taper shanks have been removed from ANSI/ASME B94.19 they are included for reference only.

All dimensions are in inches. All cutters are high-speed steel and only right-hand cutters are standard.

Tolerances: On *D*, +0.000, –0.010 inch; on *W*, +0.000, –0.005 inch; on *N*, +0.000, –0.005 inch; on *L*, ± 1/16 inch; on *S*, –00001 to –0.0005 inch.

American National Standard Form Relieved Corner Rounding Cutters with Weldon Shanks *ANSI/ASME B94.19-1997*



Rad., *R*	Dia., *D*	Dia., *d*	*S*	*L*	Rad., *R*	Dia., *D*	Dia., *d*	*S*	*L*
1/16	7/16	1/4	3/8	2 1/2	3/8	1 1/4	3/8	1/2	3 1/2
3/32	1/2	1/4	3/8	2 1/2	3/16	7/8	5/16	3/4	3 1/8
1/8	5/8	1/4	1/2	3	1/4	1	3/8	3/4	3 1/4
5/32	3/4	5/16	1/2	3	5/16	1 1/8	3/8	7/8	3 1/2
3/16	7/8	5/16	1/2	3	3/8	1 1/4	3/8	7/8	3 3/4
1/4	1	3/8	1/2	3	7/16	1 3/8	3/8	1	4
5/16	1 1/8	3/8	1/2	3 1/4	1/2	1 1/2	3/8	1	4 1/8

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters are standard.

Tolerances: On *D*, ±0.010 inch; on diameter of circle, 2*R*, ±0.001 inch for cutters up to and including 1/8-inch radius, +0.002, –0.001 inch for cutters over 1/8-inch radius; on *S*, –0.0001 to –0.0005 inch; and on *L*, ± 1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Metal Slitting Saws *ANSI/ASME B94.19-1997*

Cutter Diameter			Range of Face Widths Nom.[a]	Hole Diameter		
Nom.	Max.	Min.		Nom.	Max.	Min.
Plain Metal Slitting Saws[b]						
2½	2.515	2.485	1/32, 3/64, 1/16, 3/32, 1/8	7/8	0.87575	0.8750
3	3.015	2.985	1/32, 3/64, 1/16, 3/32, 1/8 and 5/32	1	1.00075	1.0000
4	4.015	3.985	1/32, 3/64, 1/16, 3/32, 1/8, 5/32 and 3/16	1	1.00075	1.0000
5	5.015	4.985	1/16, 3/32, 1/8	1	1.00075	1.0000
5	5.015	4.985	1/8	1 1/4	1.2510	1.2500
6	6.015	5.985	1/16, 3/32, 1/8	1	1.00075	1.0000
6	6.015	5.985	1/8, 3/16	1 1/4	1.2510	1.2500
8	8.015	7.985	1/8	1	1.00075	1.0000
8	8.015	7.985	1/8	1 1/4	1.2510	1.2500
Metal Slitting Saws with Side Teeth[c]						
2½	2.515	2.485	1/16, 3/32, 1/8	7/8	0.87575	0.8750
3	3.015	2.985	1/16, 3/32, 1/8, 5/32	1	1.00075	1.0000
4	4.015	3.985	1/16, 3/32, 1/8, 5/32, 3/16	1	1.00075	1.0000
5	5.015	4.985	1/16, 3/32, 1/8, 5/32, 3/16	1	1.00075	1.0000
5	5.015	4.985	1/8	1 1/4	1.2510	1.2500
6	6.015	5.985	1/16, 3/32, 1/8, 3/16	1	1.00075	1.0000
6	6.015	5.985	1/8, 3/16	1 1/4	1.2510	1.2500
8	8.015	7.985	1/8	1	1.00075	1.0000
8	8.015	7.985	1/8, 3/16	1 1/4	1.2510	1.2500
Metal Slitting Saws with Staggered Peripheral and Side Teeth[d]						
3	3.015	2.985	3/16	1	1.00075	1.0000
4	4.015	3.985	3/16	1	1.00075	1.0000
5	5.015	4.985	3/16, 1/4	1	1.00075	1.0000
6	6.015	5.985	3/16, 1/4	1	1.00075	1.0000
6	6.015	5.985	3/16, 1/4	1 1/4	1.2510	1.2500
8	8.015	7.985	3/16, 1/4	1 1/4	1.2510	1.2500
10	10.015	9.985	3/16, 1/4	1 1/4	1.2510	1.2500
12	12.015	11.985	1/4, 5/16	1 1/2	1.5010	1.5000

[a] Tolerances on face widths are plus or minus 0.001 inch.

[b] Plain metal slitting saws are relatively thin plain milling cutters having peripheral teeth only. They are furnished with or without hub and their sides are concaved to the arbor hole or hub.

[c] Metal slitting saws with side teeth are relatively thin side milling cutters having both peripheral and side teeth.

[d] Metal slitting saws with staggered peripheral and side teeth are relatively thin staggered tooth milling cutters having peripheral teeth of alternate right- and left-hand helix and alternate side teeth.

All dimensions are in inches. All saws are high-speed steel. Metal slitting saws are similar to plain or side milling cutters but are relatively thin.

Milling Cutter Terms



Copyright 2004, Industrial Press, Inc., New York, NY

Milling Cutter Terms *(Continued)*



American National Standard Single- and Double-Angle Milling Cutters *ANSI/ASME B94.19-1997*

Cutter Diameter				Hole Diameter		
Nom.	Max.	Min.	Nominal Face Width[a]	Nom.	Max.	Min.
Single-angle Cutters[b]						
[c]1¼	1.265	1.235	7/16	3/8-24 UNF-2B RH 3/8-24 UNF-2B LH		
[c]1⅝	1.640	1.610	9/16	½-20 UNF-2B RH		
2¾	2.765	2.735	½	1	1.00075	1.0000
3	3.015	2.985	½	1¼	1.2510	1.2500
Double-angle Cutters[d]						
2¾	2.765	2.735	½	1	1.00075	1.0000

[a] Face width tolerances are plus or minus 0.015 inch.

[b] Single-angle milling cutters have peripheral teeth, one cutting edge of which lies in a conical surface and the other in the plane perpendicular to the cutter axis. There are two types: one has a plain keywayed hole and has an included tooth angle of either 45 or 60 degrees plus or minus 10 minutes; the other has a threaded hole and has an included tooth angle of 60 degrees plus or minus 10 minutes. Cutters with a right-hand threaded hole have a right-hand hand of rotation and a right-hand hand of cutter. Cutters with a left-hand threaded hole have a left-hand hand of rotation and a left-hand hand of cutter. Cutters with plain keywayed holes are standard as either right-hand or left-hand cutters.

[c] These cutters have threaded holes, the sizes of which are given under "Hole Diameter."

[d] Double-angle milling cutters have symmetrical peripheral teeth both sides of which lie in conical surfaces. They are designated by the included angle, which may be 45, 60 or 90 degrees. Tolerances are plus or minus 10 minutes for the half angle on each side of the center.

All dimensions are in inches. All cutters are high-speed steel.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Shell Mills *ANSI/ASME B94.19-1997*



Dia., *D*	Width, *W*	Dia., *H*	Length, *B*	Width, *C*	Depth, *E*	Radius, *F*	Dia., *J*	Dia., *K*	Angle, *L*
inches	inches	inches	inches	inches	inches	inches	inches	degrees	inches
1¼	1	½	⅝	¼	5/32	1/64	11/16	⅝	0
1½	1⅛	½	⅝	¼	5/32	1/64	11/16	⅝	0
1¾	1¼	¾	¾	5/16	3/16	1/32	15/16	⅞	0
2	1⅜	¾	¾	5/16	3/16	1/32	15/16	⅞	0
2¼	1½	1	¾	⅜	7/32	1/32	1¼	1⅜	0
2½	1⅝	1	¾	⅜	7/32	1/32	1⅜	1⅜	0
2¾	1⅝	1	¾	⅜	7/32	1/32	1½	1⅜	5
3	1¾	1¼	¾	½	9/32	1/32	1 21/32	1½	5
3½	1⅞	1¼	¾	½	9/32	1/32	1 11/16	1½	5
4	2¼	1½	1	⅝	⅜	1/16	2 1/32	1⅞	5
4½	2¼	1½	1	⅝	⅜	1/16	2 1/16	1⅞	10
5	2¼	1½	1	⅝	⅜	1/16	2 9/16	1⅞	10
6	2¼	2	1	¾	7/16	1/16	2 13/16	2½	15

All cutters are high-speed steel. Right-hand cutters with right-hand helix and square corners are standard.

Tolerances: On *D*, +1/64 inch; on *W*, ±1/64 inch; on *H*, +0.0005 inch; on *B*, +1/64 inch; on *C*, at least +0.008 but not more than +0.012 inch; on *E*, +1/64 inch; on *J*, ±1/64 inch; on *K*, ±1/64 inch.

End Mill Terms



Enlarged Section of End Mill Tooth

Copyright 2004, Industrial Press, Inc., New York, NY

End Mill Terms *(Continued)*



Enlarged Section of End Mill

American National Standard Multiple- and Two-Flute Single-End Helical End Mills with Plain Straight and Weldon Shanks *ANSI/ASME B94.19-1997*



Cutter Diameter, *D*			Shank Diameter, *S*		Length of Cut, *W*	Length Overall, *L*
Nom.	Max.	Min.	Max.	Min.		
Multiple-flute with Plain Straight Shanks						
1/8	.130	.125	.125	.1245	5/16	1 1/4
3/16	.1925	.1875	.1875	.1870	1/2	1 3/8
1/4	.255	.250	.250	.2495	5/8	1 11/16
3/8	.380	.375	.375	.3745	3/4	1 13/16
1/2	.505	.500	.500	.4995	15/16	2 1/4
3/4	.755	.750	.750	.7495	1 1/4	2 5/8
Two-flute for Keyway Cutting with Weldon Shanks						
1/8	.125	.1235	.375	.3745	3/8	2 5/16
3/16	.1875	.1860	.375	.3745	7/16	2 5/16
1/4	.250	.2485	.375	.3745	1/2	2 5/16
5/16	.3125	.3110	.375	.3745	9/16	2 5/16
3/8	.375	.3735	.375	.3745	9/16	2 5/16
1/2	.500	.4985	.500	.4995	1	3
5/8	.625	.6235	.625	.6245	1 5/16	3 7/16
3/4	.750	.7485	.750	.7495	1 5/16	3 9/16
7/8	.875	.8735	.875	.8745	1 1/2	3 3/4
1	1.000	.9985	1.000	.9995	1 5/8	4 1/8
1 1/4	1.250	1.2485	1.250	1.2495	1 5/8	4 1/8
1 1/2	1.500	1.4985	1.250	1.2495	1 5/8	4 1/8

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard.

The helix angle is not less than 10 degrees for multiple-flute cutters with plain straight shanks; the helix angle is optional with the manufacturer for two-flute cutters with Weldon shanks.

Tolerances: On W, $\pm 1/32$ inch; on L, $\pm 1/16$ inch.

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Regular-, Long-, and Extra Long-Length, Multiple-Flute Medium Helix Single-End End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



As Indicated By The Dimensions Given Below, Shank Diameter S May Be Larger, Smaller, Or The Same As The Cutter Diameter D

Cutter Dia.,	Regular Mills				Long Mills				Extra Long Mills			
D	*S*	*W*	*L*	*N*[a]	*S*	*W*	*L*	*N*[a]	*S*	*W*	*L*	*N*[a]
1/8 [b]	3/8	3/8	2 5/16	4	…	…	…	…	…	…	…	…
3/16 [b]	3/8	1/2	2 3/8	4	…	…	…	…	…	…	…	…
1/4 [b]	3/8	5/8	2 7/16	4	3/8	1 1/4	3 1/16	4	3/8	1 3/4	3 9/16	4
5/16 [b]	3/8	3/4	2 1/2	4	3/8	1 3/8	3 1/8	4	3/8	2	3 3/4	4
3/8 [b]	3/8	3/4	2 1/2	4	3/8	1 1/2	3 1/4	4	3/8	2 1/2	4 1/4	4
7/16	3/8	1	2 11/16	4	1/2	1 3/4	3 3/4	4	…	…	…	…
1/2	3/8	1	2 11/16	4	1/2	2	4	4	1/2	3	5	4
1/2 [b]	1/2	1 1/4	3 1/4	4	…	…	…	…	…	…	…	…
9/16	1/2	1 3/8	3 3/8	4	…	…	…	…	…	…	…	…
5/8	1/2	1 3/8	3 3/8	4	5/8	2 1/2	4 5/8	4	5/8	4	6 1/8	4
11/16	1/2	1 5/8	3 5/8	4	…	…	…	…	…	…	…	…
3/4	1/2	1 5/8	3 5/8	4	3/4	3	5 1/4	4	3/4	4	6 1/4	4
5/8 [b]	5/8	1 5/8	3 3/4	4	…	…	…	…	…	…	…	…
11/16	5/8	1 5/8	3 3/4	4	…	…	…	…	…	…	…	…
3/4 [b]	5/8	1 5/8	3 3/4	4	…	…	…	…	…	…	…	…
13/16	5/8	1 7/8	4	6	…	…	…	…	…	…	…	…
7/8	5/8	1 7/8	4	6	7/8	3 1/2	5 3/4	4	7/8	5	7 1/4	4
1	5/8	1 7/8	4	6	1	4	6 1/2	4	1	6	8 1/2	4
7/8	7/8	1 7/8	4 1/8	4	…	…	…	…	…	…	…	…
1	7/8	1 7/8	4 1/8	4	…	…	…	…	…	…	…	…
1 1/8	7/8	2	4 1/4	6	1	4	6 1/2	6	…	…	…	…
1 1/4	7/8	2	4 1/4	6	1	4	6 1/2	6	1 1/4	6	8 1/2	6
1	1	2	4 1/2	4	…	…	…	…	…	…	…	…
1 1/8	1	2	4 1/2	6	…	…	…	…	…	…	…	…
1 1/4	1	2	4 1/2	6	…	…	…	…	…	…	…	…
1 3/8	1	2	4 1/2	6	…	…	…	…	…	…	…	…
1 1/2	1	2	4 1/2	6	1	4	6 1/2	6	…	…	…	…
1 1/4	1 1/4	2	4 1/2	6	1 1/4	4	6 1/2	6	…	…	…	…
1 1/2	1 1/4	2	4 1/2	6	1 1/4	4	6 1/2	6	1 1/4	8	10 1/2	6
1 3/4	1 1/4	2	4 1/2	6	1 1/4	4	6 1/2	6	…	…	…	…
2	1 1/4	2	4 1/2	8	1 1/4	4	6 1/2	8	…	…	…	…

[a] N = Number of flutes.

[b] In this size of regular mill a left-hand cutter with left-hand helix is also standard.

All dimensions are in inches. All cutters are high-speed steel. Helix angle is greater than 19 degrees but not more than 39 degrees. Right-hand cutters with right-hand helix are standard.

Tolerances: On D, +0.003 inch; on S, –0.0001 to –0.0005 inch; on W, $\pm 1/32$ inch; on L, $\pm 1/16$ inch.

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Two-Flute, High Helix, Regular-, Long-, and Extra Long-Length, Single-End End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



Cutter Dia., *D*	Regular Mill			Long Mill			Extra Long Mill		
	S	*W*	*L*	*S*	*W*	*L*	*S*	*W*	*L*
1/4	3/8	5/8	2 7/16	3/8	1 1/4	3 1/16	3/8	1 3/4	3 9/16
5/16	3/8	3/4	2 1/2	3/8	1 3/8	3 1/8	3/8	2	3 3/4
3/8	3/8	3/4	2 1/2	3/8	1 1/2	3 1/4	3/8	2 1/2	4 1/4
7/16	3/8	1	2 11/16	1/2	1 3/4	3 3/4	…	…	…
1/2	1/2	1 1/4	3 1/4	1/2	2	4	1/2	3	5
5/8	5/8	1 5/8	3 3/4	5/8	2 1/2	4 5/8	5/8	4	6 1/8
3/4	3/4	1 5/8	3 7/8	3/4	3	5 1/4	3/4	4	6 1/4
7/8	7/8	1 7/8	4 1/8	…	…	…	…	…	…
1	1	2	4 1/2	1	4	6 1/2	1	6	8 1/2
1 1/4	1 1/4	2	4 1/2	1 1/4	4	6 1/2	1 1/4	6	8 1/2
1 1/2	1 1/4	2	4 1/2	1 1/4	4	6 1/2	1 1/4	8	10 1/2
2	1 1/4	2	4 1/2	1 1/4	4	6 1/2	…	…	…

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 39 degrees.

Tolerances: On *D*, +0.003 inch; on *S*, –0.0001 to –0.0005 inch; on *W*, ±1/32 inch; and on *L*, ±1/16 inch.

Combination Shanks for End Mills *ANSI/ASME B94.19-1997*

Right-hand Cut



Left-hand Cut



Dia. *A*	*L*[a]	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*J*	*K*	*M*
1 1/2	2 11/16	1 3/16	.515	1.406	1 1/2	.515	1.371	9/16	1.302	.377	7/16
2	3 1/4	1 23/32	.700	1.900	1 3/4	.700	1.809	5/8	1.772	.440	1/2
2 1/2	3 1/2	1 15/16	.700	2.400	2	.700	2.312	3/4	2.245	.503	9/16

[a] Length of shank.

All dimensions are in inches.

Modified for use as Weldon or Pin Drive shank.

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Roughing, Single-End End Mills with Weldon Shanks, High-Speed Steel *ANSI/ASME B94.19-1997*



Diameter		Length		Diameter		Length	
Cutter	Shank	Cut	Overall	Cutter	Shank	Cut	Overall
D	*S*	*W*	*L*	*D*	*S*	*W*	*L*
½	½	1	3	2	2	2	5¾
½	½	1¼	3¼	2	2	3	6¾
½	½	2	4	2	2	4	7¾
⅝	⅝	1¼	3⅜	2	2	5	8¾
⅝	⅝	1⅝	3¾	2	2	6	9¾
⅝	⅝	2½	4⅜	2	2	7	10¾
¾	¾	1½	3¾	2	2	8	11¾
¾	¾	1⅝	3⅞	2	2	10	13¾
¾	¾	3	5¼	2	2	12	15¾
1	1	2	4½	2½	2	4	7¾
1	1	4	6½	2½	2	6	9¾
1¼	1¼	2	4½	2½	2	8	11¾
1¼	1¼	4	6½	2½	2	10	13¾
1½	1¼	2	4½	3	2½	4	7¾
1½	1¼	4	6½	3	2½	6	9¾
1¾	1¼	2	4½	3	2½	8	11¾
1¾	1¼	4	6½	3	2½	10	13¾

All dimensions are in inches. Right-hand cutters with right-hand helix are standard.
Tolerances: Outside diameter, +0.025, –0.005 inch; length of cut, +⅛, –1/32 inch.

American National Standard Heavy Duty, Medium Helix Single-End End Mills, 2½-inch Combination Shank, High-Speed Steel *ANSI/ASME B94.19-1997*



Dia. of Cutter, *D*	No. of Flutes	Length of Cut, *W*	Length Overall, *L*	Dia. of Cutter, *D*	No. of Flutes	Length of Cut, *W*	Length Overall, *L*
2½	3	8	12	3	3	4	7¾
2½	3	10	14	3	3	6	9¾
2½	6	4	8	3	3	8	11¾
2½	6	6	10	3	8	4	7¾
2½	6	8	12	3	8	6	9¾
2½	6	10	14	3	8	8	11¾
2½	6	12	16	3	8	10	13¾
3	2	4	7¾	3	8	12	15¾
3	2	6	9¾	…	…	…	…

All dimensions are in inches. For shank dimensions see page 806. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.
Tolerances: On *D*, +0.005 inch; on *W*, ±1/32 inch; on *L*, ±1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Stub-, Regular-, and Long-Length, Four-Flute, Medium Helix, Plain-End, Double-End Miniature End Mills with 3/16-Inch Diameter Straight Shanks

ANSI/ASME B94.19-1997



Dia. *D*	Stub Length		Regular Length	
	W	*L*	*W*	*L*
1/16	3/32	2	3/16	2 1/4
3/32	9/64	2	9/32	2 1/4
1/8	3/16	2	3/8	2 1/4
5/32	15/64	2	7/16	2 1/4
3/16	9/32	2	1/2	2 1/4

Dia. *D*	Long Length		
	B	*W*	*L*
1/16	3/8	7/32	2 1/2
3/32	1/2	9/32	2 5/8
1/8	3/4	3/4	3 1/8
5/32	7/8	7/8	3 1/4
3/16	1	1	3 3/8

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *D*, + 0.003 inch (if the shank is the same diameter as the cutting portion, however, then the tolerance on the cutting diameter is – 0.0025 inch.); on *W*, + 1/32 , – 1/64 inch; and on *L*, ±1/16 inch.

American National Standard 60-Degree Single-Angle Milling Cutters with Weldon Shanks *ANSI/ASME B94.19-1997*



Dia., *D*	*S*	*W*	*L*	Dia., *D*	*S*	*W*	*L*
3/4	3/8	5/16	2 1/8	1 7/8	7/8	13/16	3 1/4
1 3/8	5/8	9/16	2 7/8	2 1/4	1	1 1/16	3 3/4

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters are standard.

Tolerances: On *D*, ± 0.015 inch; on *S*, – 0.0001 to – 0.0005 inch; on *W*, ± 0.015 inch; and on *L*, ±1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Stub-, Regular-, and Long-Length, Two-Flute, Medium Helix, Plain- and Ball-End, Double-End Miniature End Mills with 3/16-Inch Diameter Straight Shanks *ANSI/ASME B94.19-1997*



Dia., *C* and *D*	Stub Length				Regular Length			
	Plain End		Ball End		Plain End		Ball End	
	W	*L*	*W*	*L*	*W*	*L*	*W*	*L*
1/32	3/64	2	…	…	3/32	2 1/4	…	…
3/64	1/16	2	…	…	9/64	2 1/4	…	…
1/16	3/32	2	3/32	2	3/16	2 1/4	3/16	2 1/4
5/64	1/8	2	…	…	15/64	2 1/4	…	…
3/32	9/64	2	9/64	2	9/32	2 1/4	9/32	2 1/4
7/64	5/32	2	…	…	21/64	2 1/4	…	…
1/8	3/16	2	3/16	2	3/8	2 1/4	3/8	2 1/4
9/64	7/32	2	…	…	13/32	2 1/4	…	…
5/32	15/64	2	15/64	2	7/16	2 1/4	7/16	2 1/4
11/64	1/4	2	…	…	1/2	2 1/4	…	…
3/16	9/32	2	9/32	2	1/2	2 1/4	1/2	2 1/4

Dia., *D*	Long Length, Plain End			Dia., *D*	Long Length, Plain End		
	B [a]	*W*	*L*		*B* [a]	*W*	*L*
1/16	3/8	7/32	2 1/2	5/32	7/8	7/8	3 1/4
3/32	1/2	9/32	2 5/8	3/16	1	1	3 3/8
1/8	3/4	3/4	3 1/8				

[a] *B* is the length below the shank.

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *C* and *D*, – 0.0015 inch for stub and regular length; + 0.003 inch for long length (if the shank is the same diameter as the cutting portion, however, then the tolerance on the cutting diameter is – 0.0025 inch.); on *W*, + 1/32 , – 1/64 inch; and on *L*, ± 1/16 inch.

American National Standard Multiple Flute, Helical Series End Mills with Brown & Sharpe Taper Shanks



Dia., *D*	*W*	*L*	Taper No.	Dia., *D*	*W*	*L*	Taper No.
1/2	15/16	4 15/16	7	1 1/4	2	7 1/4	9
3/4	1 1/4	5 1/4	7	1 1/2	2 1/4	7 1/2	9
1	1 5/8	5 5/8	7	2	2 3/4	8	9

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is not less than 10 degrees.

No. 5 taper is standard without tang; Nos. 7 and 9 are standard with tang only.

Tolerances: On *D*, +0.005 inch; on *W*, ±1/32 inch; and on *L* ±1/16 inch.

For dimensions of B & S taper shanks, see information given on page 936.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Stub- and Regular-Length, Two-Flute, Medium Helix, Plain- and Ball-End, Single-End End Mills with Weldon Shanks

ANSI/ASME B94.19-1997



Regular Length — Plain End			
Dia., *D*	*S*	*W*	*L*
1/8	3/8	3/8	2 5/16
3/16	3/8	7/16	2 5/16
1/4	3/8	1/2	2 5/16
5/16	3/8	9/16	2 5/16
3/8	3/8	9/16	2 5/16
7/16	3/8	13/16	2 1/2
1/2	3/8	13/16	2 1/2
1/2	1/2	1	3
9/16	1/2	1 1/8	3 1/8
5/8	1/2	1 1/8	3 1/8
11/16	1/2	1 5/16	3 5/16
3/4	1/2	1 5/16	3 5/16
5/8	5/8	1 5/16	3 7/16
11/16	5/8	1 5/16	3 7/16
3/4	5/8	1 5/16	3 7/16
13/16	5/8	1 1/2	3 5/8
7/8	5/8	1 1/2	3 5/8
1	5/8	1 1/2	3 5/8
7/8	7/8	1 1/2	3 3/4
1	7/8	1 1/2	3 3/4
1 1/8	7/8	1 5/8	3 7/8
1 1/4	7/8	1 5/8	3 7/8
1	1	1 5/8	4 1/8
1 1/8	1	1 5/8	4 1/8
1 1/4	1	1 5/8	4 1/8
1 3/8	1	1 5/8	4 1/8
1 1/2	1	1 5/8	4 1/8
1 1/4	1 1/4	1 5/8	4 1/8
1 1/2	1 1/4	1 5/8	4 1/8
1 3/4	1 1/4	1 5/8	4 1/8
2	1 1/4	1 5/8	4 1/8

Stub Length — Plain End			
Cutter Dia., *D*	Shank Dia., *S*	Length of Cut. *W*	Length Overall. *L*
1/8	3/8	3/16	2 1/8
3/16	3/8	9/32	2 3/16
1/4	3/8	3/8	2 1/4

Regular Length — Ball End			
Dia., *C* and *D*	Shank Dia., *S*	Length of Cut. *W*	Length Overall. *L*
1/8	3/8	3/8	2 5/16
3/16	3/8	1/2	2 3/8
1/4	3/8	5/8	2 7/16
5/16	3/8	3/4	2 1/2
3/8	3/8	3/4	2 1/2
7/16	1/2	1	3
1/2	1/2	1	3
9/16	1/2	1 1/8	3 1/8
5/8	1/2	1 1/8	3 1/8
5/8	5/8	1 3/8	3 1/2
3/4	1/2	1 5/16	3 5/16
3/4	3/4	1 5/8	3 7/8
7/8	7/8	2	4 1/4
1	1	2 1/4	4 3/4
1 1/8	1	2 1/4	4 3/4
1 1/4	1 1/4	2 1/2	5
1 1/2	1 1/4	2 1/2	5

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *C* and *D*, –0.0015 inch for stub-length mills, + 0.003 inch for regular-length mills; on *S*, –0.0001 to –0.0005 inch; on *W*, ± 1/32 inch; and on *L*, ± 1/16 inch.

The following single-end end mills are available in premium high speed steel: ball end, two flute, with *D* ranging from 1/8 to 1 1/2 inches; ball end, multiple flute, with *D* ranging from 1/8 to 1 inch; and plain end, two flute, with *D* ranging from 1/8 to 1 1/2 inches.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Long-Length Single-End and Stub-, and Regular Length, Double-End, Plain- and Ball-End, Medium Helix, Two-Flute End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



Single End

Dia., *C* and *D*	Long Length — Plain End				Long Length — Ball End			
	S	*B*[a]	*W*	*L*	*S*	*B*[a]	*W*	*L*
1/8	…	…	…	…	3/8	13/16	3/8	2 3/8
3/16	…	…	…	…	3/8	1 1/8	1/2	2 11/16
1/4	3/8	1 1/2	5/8	3 1/16	3/8	1 1/2	5/8	3 1/16
5/16	3/8	1 3/4	3/4	3 5/16	3/8	1 3/4	3/4	3 5/16
3/8	3/8	1 3/4	3/4	3 5/16	3/8	1 3/4	3/4	3 5/16
7/16	…	…	…	…	1/2	1 7/8	1	3 11/16
1/2	1/2	2 7/32	1	4	1/2	2 1/4	1	4
5/8	5/8	2 23/32	1 3/8	4 5/8	5/8	2 3/4	1 3/8	4 5/8
3/4	3/4	3 11/32	1 5/8	5 3/8	3/4	3 3/8	1 5/8	5 3/8
1	1	4 31/32	2 1/2	7 1/4	1	5	2 1/2	7 1/4
1 1/4	1 1/4	4 31/32	3	7 1/4	…	…	…	…

[a] *B* is the length below the shank.

Double End

Dia., *C* and *D*	Stub Length — Plain End			Regular Length — Plain End			Regular Length — Ball End		
	S	*W*	*L*	*S*	*W*	*L*	*S*	*W*	*L*
1/8	3/8	3/16	2 3/4	3/8	3/8	3 1/16	3/8	3/8	3 1/16
5/32	3/8	15/64	2 3/4	3/8	7/16	3 1/8	…	…	…
3/16	3/8	9/32	2 3/4	3/8	7/16	3 1/8	3/8	7/16	3 1/8
7/32	3/8	21/64	2 7/8	3/8	1/2	3 1/8	…	…	…
1/4	3/8	3/8	2 7/8	3/8	1/2	3 1/8	3/8	1/2	3 1/8
9/32	…	…	…	3/8	9/16	3 1/8	…	…	…
5/16	…	…	…	3/8	9/16	3 1/8	3/8	9/16	3 1/8
11/32	…	…	…	3/8	9/16	3 1/8	…	…	…
3/8	…	…	…	3/8	9/16	3 1/8	3/8	9/16	3 1/8
13/32	…	…	…	1/2	13/16	3 3/4	…	…	…
7/16	…	…	…	1/2	13/16	3 3/4	1/2	13/16	3 3/4
15/32	…	…	…	1/2	13/16	3 3/4	…	…	…
1/2	…	…	…	1/2	13/16	3 3/4	1/2	13/16	3 3/4
9/16	…	…	…	5/8	1 1/8	4 1/2	…	…	…
5/8	…	…	…	5/8	1 1/8	4 1/2	5/8	1 1/8	4 1/2
11/16	…	…	…	3/4	1 5/16	5	…	…	…
3/4	…	…	…	3/4	1 5/16	5	3/4	1 5/16	5
7/8	…	…	…	7/8	1 9/16	5 1/2	…	…	…
1	…	…	…	1	1 5/8	5 7/8	1	1 5/8	5 7/8

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *C* and *D*, + 0.003 inch for single-end mills, –0.0015 inch for double-end mills; on *S*, –0.0001 to –0.0005 inch; on *W*, ±1/32 inch; and on *L*, ±1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Regular-, Long-, and Extra Long-Length, Three-and Four-Flute, Medium Helix, Center Cutting, Single-End End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



Four Flute

Dia.,	Regular Length			Long Length			Extra Long Length		
D	*S*	*W*	*L*	*S*	*W*	*L*	*S*	*W*	*L*
1/8	3/8	3/8	2 5/16	...	...	...	...	...	...
3/16	3/8	1/2	2 3/8	...	...	...	...	...	...
1/4	3/8	5/8	2 7/16	3/8	1 1/4	3 3/16	3/8	1 3/4	3 9/16
5/16	3/8	3/4	2 1/2	3/8	1 3/8	3 1/8	3/8	2	3 3/4
3/8	3/8	3/4	2 1/2	3/8	1 1/2	3 1/4	3/8	2 1/2	4 1/4
1/2	1/2	1 1/4	3 1/4	1/2	2	4	1/2	3	5
5/8	5/8	1 5/8	3 3/4	5/8	2 1/2	4 5/8	5/8	4	6 1/8
11/16	5/8	1 5/8	3 3/4	...	...	...	...	...	...
3/4	3/4	1 5/8	3 7/8	3/4	3	5 1/4	3/4	4	6 1/4
7/8	7/8	1 7/8	4 1/8	7/8	3 1/2	5 3/4	7/8	5	7 1/4
1	1	2	4 1/2	1	4	6 1/2	1	6	8 1/2
1 1/8	1	2	4 1/2	...	...	...	...	...	...
1 1/4	1 1/4	2	4 1/2	1 1/4	4	6 1/2	1 1/4	6	8 1/2
1 1/2	1 1/4	2	4 1/2	...	...	...	...	...	...

Three Flute

Dia., *D*	*S*	*W*	*L*	Dia., *D*	*S*	*W*	*L*
Regular Length				Regular Length (*cont.*)			
1/8	3/8	3/8	2 5/16	1 1/8	1	2	4 1/2
3/16	3/8	1/2	2 3/8	1 1/4	1	2	4 1/2
1/4	3/8	5/8	2 7/16	1 1/2	1	2	4 1/2
5/16	3/8	3/4	2 1/2	1 1/4	1 1/4	2	4 1/2
3/8	3/8	3/4	2 1/2	1 1/2	1 1/4	2	4 1/2
7/16	3/8	1	2 11/16	1 3/4	1 1/4	2	4 1/2
1/2	3/8	1	2 11/16	2	1 1/4	2	4 1/2
1/2	1/2	1 1/4	3 1/4	Long Length			
9/16	1/2	1 3/8	3 3/8				
9/16	1/2	1 3/8	3 3/8	1/4	3/8	1 1/4	3 11/16
5/8	1/2	1 3/8	3 3/8	5/16	3/8	1 3/8	3 1/8
3/4	1/2	1 5/8	3 5/8	3/8	3/8	1 1/2	3 1/4
5/8	5/8	1 5/8	3 3/4	7/16	1/2	1 3/4	3 3/4
3/4	5/8	1 5/8	3 3/4	1/2	1/2	2	4
7/8	5/8	1 7/8	4	5/8	5/8	2 1/2	4 5/8
1	5/8	1 7/8	4	3/4	3/4	3	5 1/4
3/4	3/4	1 5/8	3 7/8	1	1	4	6 1/2
7/8	3/4	1 7/8	4 1/8	1 1/4	1 1/4	4	6 1/2
1	3/4	1 7/8	4 1/8	1 1/2	1 1/4	4	6 1/2
1	7/8	1 7/8	4 1/8	1 3/4	1 1/4	4	6 1/2
1	1	2	4 1/2	2	1 1/4	4	6 1/2

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On D, +0.003 inch; on S, –0.0001 to –0.0005 inch; on W, $\pm 1/32$ inch; and on L, $\pm 1/16$ inch.

The following center-cutting, single-end end mills are available in premium high speed steel: regular length, multiple flute, with D ranging from 1/8 to 1 1/2 inches; long length, multiple flute, with D ranging from 3/8 to 1 1/4 inches; and extra long-length, multiple flute, with D ranging from 3/8 to 1 1/4 inches.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Stub- and Regular-length, Four-flute, Medium Helix, Double-end End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



Dia., *D*	*S*	*W*	*L*	Dia., *D*	*S*	*W*	*L*	Dia., *D*	*S*	*W*	*L*
Stub Length											
1/8	3/8	3/16	2 3/4	3/16	3/8	9/32	2 3/4	1/4	3/8	3/8	2 7/8
5/32	3/8	15/64	2 3/4	7/32	3/8	21/64	2 7/8	…	…	…	…
Regular Length											
1/8 [a]	3/8	3/8	3 1/16	11/32	3/8	3/4	3 1/2	5/8 [a]	5/8	1 3/8	5
5/32 [a]	3/8	7/16	3 1/8	3/8 [a]	3/8	3/4	3 1/2	11/16	3/4	1 5/8	5 5/8
3/16 [a]	3/8	1/2	3 1/4	13/32	1/2	1	4 1/8	3/4 [a]	3/4	1 5/8	5 5/8
7/32	3/8	9/16	3 1/4	7/16	1/2	1	4 1/8	13/16	7/8	1 7/8	6 1/8
1/4 [a]	3/8	5/8	3 3/8	15/32	1/2	1	4 1/8	7/8	7/8	1 7/8	6 1/8
9/32	3/8	11/16	3 3/8	1/2 [a]	1/2	1	4 1/8	1	1	1 7/8	6 3/8
5/16 [a]	3/8	3/4	3 1/2	9/16	5/8	1 3/8	5	…	…	…	…

[a] In this size of regular mill a left-hand cutter with a left-hand helix is also standard.

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *D*, +0.003 inch (if the shank is the same diameter as the cutting portion, however, then the tolerance on the cutting diameter is –0.0025 inch); on *S*, –0.0001 to –0.0005 inch; on *W*, ±1/32 inch; and on *L*, ±1/16 inch.

American National Standard Stub- and Regular-Length, Four-Flute, Medium Helix, Double-End End Mills with Weldon Shanks *ANSI/ASME B94.19-1997*



Dia., *D*	*S*	*W*	*L*	Dia., *D*	*S*	*W*	*L*
Three Flute				Four Flute			
1/8	3/8	3/8	3 1/16	1/8	3/8	3/8	3 1/16
3/16	3/8	1/2	3 1/4	3/16	3/8	1/2	3 1/4
1/4	3/8	5/8	3 3/8	1/4	3/8	5/8	3 3/8
5/16	3/8	3/4	3 1/2	5/16	3/8	3/4	3 1/2
3/8	3/8	3/4	3 1/2	3/8	3/8	3/4	3 1/2
7/16	1/2	1	4 1/8	1/2	1/2	1	4 1/8
1/2	1/2	1	4 1/8	5/8	5/8	1 3/8	5
9/16	5/8	1 3/8	5	3/4	3/4	1 5/8	5 5/8
5/8	5/8	1 3/8	5	7/8	7/8	1 7/8	6 1/8
3/4	3/4	1 5/8	5 5/8	1	1	1 7/8	6 3/8
1	1	1 7/8	6 3/8	…	…	…	…

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *D*, +0.0015 inch; on *S*, –0.0001 to –0.0005 inch; on *W*, ±1/32 inch; and on *L*, ±1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Plain- and Ball-End, Heavy Duty, Medium Helix, Single-End End Mills with 2-Inch Diameter Shanks *ANSI/ASME B94.19-1997*



Dia., *C* and *D*	Plain End			Ball End		
	W	*L*	No. of Flutes	*W*	*L*	No. of Flutes
2	2	5¾	2, 4, 6	…	…	…
2	3	6¾	2, 3	…	…	…
2	4	7¾	2, 3, 4, 6	4	7¾	6
2	…	…	…	5	8¾	2, 4
2	6	9¾	2, 3, 4, 6	6	9¾	6
2	8	11¾	6	8	11¾	6
2½	4	7¾	2, 3, 4, 6	…	…	…
2½	…	…	…	5	8¾	4
2½	6	9¾	2, 4, 6	…	…	…
2½	8	11¾	6	…	…	…

All dimensions are in inches. All cutters are high-speed steel. Right-hand cutters with right-hand helix are standard. Helix angle is greater than 19 degrees but not more than 39 degrees.

Tolerances: On *C* and *D*, + 0.005 inch for 2, 3, 4 and 6 flutes: on *W*, ± 1/16 inch; and on *L*, ± 1/16 inch.

Dimensions of American National Standard Weldon Shanks
ANSI/ASME B94.19-1997

Shank		Flat		Shank		Flat	
Dia.	Length	*X*[a]	Length[b]	Dia.	Length	*X*[a]	Length[b]
3/8	1 9/16	0.325	0.280	1	2 9/32	0.925	0.515
1/2	1 25/32	0.440	0.330	1¼	2 9/32	1.156	0.515
5/8	1 29/32	0.560	0.400	1½	2 11/16	1.406	0.515
3/4	2 1/32	0.675	0.455	2	3¼	1.900	0.700
7/8	2 1/32	0.810	0.455	2½	3½	2.400	0.700

[a] *X* is distance from bottom of flat to opposite side of shank.
[b] Minimum.

All dimensions are in inches.

Centerline of flat is at half-length of shank except for 1½-, 2- and 2½-inch shanks where it is 1 3/16, 1 27/32 and 1 15/16 from shank end, respectively.

Tolerance on shank diameter, – 0.0001 to – 0.0005 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Amerian National Standard Form Relieved, Concave, Convex, and Corner-Rounding Arbor-Type Cutters *ANSI/ASME B94.19-1997*



Concave



Convex

Corner-rounding

Diameter *C* or Radius *R*			Cutter Dia. D[a]	Width *W* ± .010[b]	Diameter of Hole *H*		
Nom.	Max.	Min.			Nom.	Max.	Min.
Concave Cutters[c]							
1/8	0.1270	0.1240	2 1/4	1/4	1	1.00075	1.00000
3/16	0.1895	0.1865	2 1/4	3/8	1	1.00075	1.00000
1/4	0.2520	0.2490	2 1/2	7/16	1	1.00075	1.00000
5/16	0.3145	0.3115	2 3/4	9/16	1	1.00075	1.00000
3/8	0.3770	0.3740	2 3/4	5/8	1	1.00075	1.00000
7/16	0.4395	0.4365	3	3/4	1	1.00075	1.00000
1/2	0.5040	0.4980	3	13/16	1	1.00075	1.00000
5/8	0.6290	0.6230	3 1/2	1	1 1/4	1.251	1.250
3/4	0.7540	0.7480	3 3/4	1 3/16	1 1/4	1.251	1.250
7/8	0.8790	0.8730	4	1 3/8	1 1/4	1.251	1.250
1	1.0040	0.9980	4 1/4	1 9/16	1 1/4	1.251	1.250
Convex Cutters[c]							
1/8	0.1270	0.1230	2 1/4	1/8	1	1.00075	1.00000
3/16	0.1895	0.1855	2 1/4	3/16	1	1.00075	1.00000
1/4	0.2520	0.2480	2 1/2	1/4	1	1.00075	1.00000
5/16	0.3145	0.3105	2 3/4	5/16	1	1.00075	1.00000
3/8	0.3770	0.3730	2 3/4	3/8	1	1.00075	1.00000
7/16	0.4395	0.4355	3	7/16	1	1.00075	1.00000
1/2	0.5020	0.4980	3	1/2	1	1.00075	1.00000
5/8	0.6270	0.6230	3 1/2	5/8	1 1/4	1.251	1.250
3/4	0.7520	0.7480	3 3/4	3/4	1 1/4	1.251	1.250
7/8	0.8770	0.8730	4	7/8	1 1/4	1.251	1.250
1	1.0020	0.9980	4 1/4	1	1 1/4	1.251	1.250
Corner-rounding Cutters[d]							
1/8	0.1260	0.1240	2 1/2	1/4	1	1.00075	1.00000
1/4	0.2520	0.2490	3	13/32	1	1.00075	1.00000
3/8	0.3770	0.3740	3 3/4	9/16	1 1/4	1.251	1.250
1/2	0.5020	0.4990	4 1/4	3/4	1 1/4	1.251	1.250
5/8	0.6270	0.6240	4 1/4	15/16	1 1/4	1.251	1.250

[a] Tolerances on cutter diameter are + 1/16 , – 1/16 inch for all sizes.

[b] Tolerance does not apply to convex cutters.

[c] Size of cutter is designated by specifying diameter *C* of circular form.

[d] Size of cutter is designated by specifying radius *R* of circular form.

All dimensions in inches. All cutters are high-speed steel and are form relieved.

Right-hand corner rounding cutters are standard, but left-hand cutter for 1/4 -inch size is also standard.

For key and keyway dimensions for these cutters, see page 819.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Roughing and Finishing Gear Milling Cutters for Gears with 14½-Degree Pressure Angles *ANSI/ASME B94.19-1997*





ROUGHING				FINISHING				
Diametral Pitch	Dia. of Cutter, *D*	Dia. of Hole, *H*	Diametral Pitch	Dia. of Cutter, *D*	Dia. of Hole, *H*	Diametral Pitch	Dia. of Cutter, *D*	Dia. of Hole, *H*
Roughing Gear Milling Cutters								
1	8½	2	3	5¼	1½	5	3⅜	1
1¼	7¾	2	3	4¾	1¼	6	3⅞	1½
1½	7	1¾	4	4¾	1¾	6	3½	1¼
1¾	6½	1¾	4	4½	1½	6	3⅛	1
2	6½	1¾	4	4¼	1¼	7	3⅜	1¼
2	5¾	1½	4	3⅝	1	7	2⅞	1
2½	6⅛	1¾	5	4⅜	1¾	8	3¼	1¼
2½	5¾	1½	5	4¼	1½	8	2⅞	1
3	5⅝	1¾	5	3¾	1¼	…	…	…
Finishing Gear Milling Cutters								
1	8½	2	6	3⅞	1½	14	2⅛	⅞
1¼	7¾	2	6	3½	1¼	16	2½	1
1½	7	1¾	6	3⅛	1	16	2⅛	⅞
1¾	6½	1¾	7	3⅝	1½	18	2⅜	1
2	6½	1¾	7	3⅜	1¼	18	2	⅞
2	5¾	1½	7	2⅞	1	20	2⅜	1
2½	6⅛	1¾	8	3½	1½	20	2	⅞
2½	5¾	1½	8	3¼	1¼	22	2¼	1
3	5⅝	1¾	8	2⅞	1	22	2	⅞
3	5¼	1½	9	3⅛	1¼	24	2¼	1
3	4¾	1¼	9	2¾	1	24	1¾	⅞
4	4¾	1¾	10	3	1¼	26	1¾	⅞
4	4½	1½	10	2¾	1	28	1¾	⅞
4	4¼	1¼	10	2⅜	⅞	30	1¾	⅞
4	3⅝	1	11	2⅝	1	32	1¾	⅞
5	4⅜	1¾	11	2⅜	⅞	36	1¾	⅞
5	4¼	1½	12	2⅞	1¼	40	1¾	⅞
5	3¾	1¼	12	2⅝	1	48	1¾	⅞
5	3⅜	1	12	2¼	⅞	…	…	…
6	4¼	1¾	14	2½	1	…	…	…

All dimensions are in inches.

All gear milling cutters are high-speed steel and are form relieved.

For keyway dimensions see page 819.

Tolerances: On outside diameter, + 1/16, −1/16 inch; on hole diameter, through 1-inch hole diameter, +0.00075 inch, over 1-inch and through 2-inch hole diameter, +0.0010 inch.

For cutter number relative to numbers of gear teeth, see page 2052. Roughing cutters are made with No. 1 cutter form only.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Gear Milling Cutters for Mitre and Bevel Gears with 14½-Degree Pressure Angles *ANSI/ASME B94.19-1997*

Diametral Pitch	Diameter of Cutter, *D*	Diameter of Hole, *H*	Diametral Pitch	Diameter of Cutter, *D*	Diameter of Hole, *H*
3	4	1¼	10	2⅜	⅞
4	3⅝	1¼	12	2¼	⅞
5	3⅜	1¼	14	2⅛	⅞
6	3⅛	1	16	2⅛	⅞
7	2⅞	1	20	2	⅞
8	2⅞	1	24	1¾	⅞

All dimensions are in inches.

All cutters are high-speed steel and are form relieved.

For keyway dimensions see page 819. For cutter selection see page 2091.

Tolerances: On outside diameter, +1/16, –1/16 inch; on hole diameter, through 1-inch hole diameter, +0.00075 inch, for 1¼-inch hole diameter, +0.0010 inch.

To select the cutter number for bevel gears with the axis at any angle, double the back cone radius and multiply the result by the diametral pitch. This procedure gives the number of equivalent spur gear teeth and is the basis for selecting the cutter number from the table on page 2054.



American National Standard Roller Chain Sprocket Milling Cutters

American National Standard Roller Chain Sprocket Milling Cutters *ANSI/ASME B94.19-1997*

Chain Pitch	Dia. of Roll	No. of Teeth in Sprocket	Dia. of Cutter, *D*	Width of Cutter, *W*	Dia. of Hole, *H*
¼	0.130	6	2¾	5/16	1
¼	0.130	7–8	2¾	5/16	1
¼	0.130	9–11	2¾	5/16	1
¼	0.130	12–17	2¾	5/16	1
¼	0.130	18–34	2¾	9/32	1
¼	0.130	35 and over	2¾	9/32	1
⅜	0.200	6	2¾	15/32	1
⅜	0.200	7–8	2¾	15/32	1
⅜	0.200	9–11	2¾	15/32	1
⅜	0.200	12–17	2¾	7/16	1
⅜	0.200	18–34	2¾	7/16	1
⅜	0.200	35 and over	2¾	13/32	1
½	0.313	6	3	¾	1
½	0.313	7–8	3	¾	1
½	0.313	9–11	3⅛	¾	1
½	0.313	12–17	3⅛	¾	1
½	0.313	18–34	3⅛	23/32	1
½	0.313	35 and over	3⅛	11/16	1
⅝	0.400	6	3⅛	¾	1
⅝	0.400	7–8	3⅛	¾	1
⅝	0.400	9–11	3¼	¾	1
⅝	0.400	12–17	3¼	¾	1
⅝	0.400	18–34	3¼	23/32	1
⅝	0.400	35 and over	3¼	11/16	1

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Roller Chain Sprocket Milling Cutters *ANSI/ASME B94.19-1997(Continued)*

Chain Pitch	Dia. of Roll	No. of Teeth in Sprocket	Dia. of Cutter, *D*	Width of Cutter, *W*	Dia. of Hole, *H*
¾	0.469	6	3¼	29/32	1
¾	0.469	7–8	3¼	29/32	1
¾	0.469	9–11	3⅜	29/32	1
¾	0.469	12–17	3⅜	7/8	1
¾	0.469	18–34	3⅜	27/32	1
¾	0.469	35 and over	3⅜	13/16	1
1	0.625	6	3⅞	1½	1¼
1	0.625	7–8	4	1½	1¼
1	0.625	9–11	4⅛	1 15/32	1¼
1	0.625	18–34	4¼	1 13/32	1¼
1	0.625	35 and over	4¼	1 11/32	1¼
1¼	0.750	6	4¼	1 13/16	1¼
1¼	0.750	7–8	4⅜	1 13/16	1¼
1¼	0.750	9–11	4½	1 25/32	1¼
1¼	0.750	18–34	4⅝	1 11/16	1¼
1¼	0.750	35 and over	4⅝	1⅝	1¼
1½	0.875	6	4⅜	1 13/16	1¼
1½	0.875	7–8	4½	1 13/16	1¼
1½	0.875	9–11	4⅝	1 25/32	1¼
1½	0.875	12–17	4⅝	1¾	1¼
1½	0.875	18–34	4¾	1 11/16	1¼
1½	0.875	35 and over	4¾	1⅝	1¼
1¾	1.000	6	5	2 3/32	1½
1¾	1.000	7–8	5⅛	2 3/32	1½
1¾	1.000	9–11	5¼	2 1/16	1½
1¾	1.000	12–17	5⅜	2 1/32	1½
1¾	1.000	18–34	5½	1 31/32	1½
1¾	1.000	35 and over	5½	1⅞	1½
2	1.125	6	5⅜	2 13/32	1½
2	1.125	7–8	5½	2 13/32	1½
2	1.125	9–11	5⅝	2⅜	1½
2	1.125	12–17	5¾	2 5/16	1½
2	1.125	18–34	5⅞	2¼	1½
2	1.125	35 and over	5⅞	2 5/32	1½
2¼	1.406	6	5⅞	2 11/16	1½
2¼	1.406	7–8	6	2 11/16	1½
2¼	1.406	9–11	6¼	2 21/32	1½
2¼	1.406	12–17	6⅜	2 19/32	1½
2¼	1.406	18–34	6½	2 15/32	1½
2¼	1.406	35 and over	6½	2 13/32	1½
2½	1.563	6	6⅜	3	1¾
2½	1.563	7–8	6⅜	3	1¾
2½	1.563	9–11	6¾	2 15/16	1¾
2½	1.563	12–17	6⅞	2 29/32	1¾
2½	1.563	18–34	7	2¾	1¾
2½	1.563	35 and over	7⅛	2 11/16	1¾
3	1.875	6	7½	3 19/32	2
3	1.875	7–8	7¾	3 19/32	2
3	1.875	9–11	7⅞	3 17/32	2
3	1.875	12–17	8	3 15/32	2
3	1.875	18–34	8	3 11/32	2
3	1.875	35 and over	8¼	3 7/32	2

All dimensions are in inches.

All cutters are high-speed steel and are form relieved.

For keyway dimensions see page 819.

Tolerances: Outside diameter, +1/16, −1/16 inch; hole diameter, through 1-inch diameter, + 0.00075 inch, above 1-inch diameter and through 2-inch diameter, + 0.0010 inch.

For tooth form, see ANSI sprocket tooth form table on page 2458.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Keys and Keyways for Milling Cutters and Arbors *ANSI/ASME B94.19-1997*



ARBOR AND KEYSEAT



CUTTER HOLE AND KEYWAY



ARBOR AND KEY

Nom.Arbor and Cutter Hole Dia.	Nom. Size Key (Square)	Arbor and Keyseat				Hole and Keyway					Arbor and Key			
		A Max.	*A* Min.	*B* Max.	*B* Min.	*C* Max.	*C* Min.	*D*[a] Min.	*H* Nom.	Corner Radius	*E* Max.	*E* Min.	*F* Max.	*F* Min.
1/2	3/32	0.0947	0.0937	0.4531	0.4481	0.106	0.099	0.5578	3/64	0.020	0.0932	0.0927	0.5468	0.5408
5/8	1/8	0.1260	0.1250	0.5625	0.5575	0.137	0.130	0.6985	1/16	1/32	0.1245	0.1240	0.6875	0.6815
3/4	1/8	0.1260	0.1250	0.6875	0.6825	0.137	0.130	0.8225	1/16	1/32	0.1245	0.1240	0.8125	0.8065
7/8	1/8	0.1260	0.1250	0.8125	0.8075	0.137	0.130	0.9475	1/16	1/32	0.1245	0.1240	0.9375	0.9315
1	1/4	0.2510	0.2500	0.8438	0.8388	0.262	0.255	1.1040	3/32	3/64	0.2495	0.2490	1.0940	1.0880
1 1/4	5/16	0.3135	0.3125	1.0630	1.0580	0.343	0.318	1.3850	1/8	1/16	0.3120	0.3115	1.3750	1.3690
1 1/2	3/8	0.3760	0.3750	1.2810	1.2760	0.410	0.385	1.6660	5/32	1/16	0.3745	0.3740	1.6560	1.6500
1 3/4	7/16	0.4385	0.4375	1.5000	1.4950	0.473	0.448	1.9480	3/16	1/16	0.4370	0.4365	1.9380	1.9320
2	1/2	0.5010	0.5000	1.6870	1.6820	0.535	0.510	2.1980	3/16	1/16	0.4995	0.4990	2.1880	2.1820
2 1/2	5/8	0.6260	0.6250	2.0940	2.0890	0.660	0.635	2.7330	7/32	1/16	0.6245	0.6240	2.7180	2.7120
3	3/4	0.7510	0.7500	2.5000	2.4950	0.785	0.760	3.2650	1/4	3/32	0.7495	0.7490	3.2500	3.2440
3 1/2	7/8	0.8760	0.8750	3.0000	2.9950	0.910	0.885	3.8900	3/8	3/32	0.8745	0.8740	3.8750	3.8690
4	1	1.0010	1.0000	3.3750	3.3700	1.035	1.010	4.3900	3/8	3/32	0.9995	0.9990	4.3750	4.3690
4 1/2	1 1/8	1.1260	1.1250	3.8130	3.8080	1.160	1.135	4.9530	7/16	1/8	1.1245	1.1240	4.9380	4.9320
5	1 1/4	1.2510	1.2500	4.2500	4.2450	1.285	1.260	5.5150	1/2	1/8	1.2495	1.2490	5.5000	5.4940

[a] *D* max. is 0.010 inch larger than *D* min.

All dimensions given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Woodruff Keyseat Cutters—Shank-Type Straight-Teeth and Arbor-Type Staggered-Teeth *ANSI/ASME B94.19-1997*



Shank-type Cutters

Cutter Number	Nom. Dia.of Cutter, *D*	Width of Face, *W*	Length Over-all, *L*	Cutter Number	Nom. Dia. of Cutter, *D*	Width of Face, *W*	Length Over-all, *L*	Cutter Number	Nom. Dia.of Cutter, *D*	Width of Face, *W*	Length Over-all, *L*
202	1/4	1/16	2 1/16	506	3/4	5/32	2 5/32	809	1 1/8	1/4	2 1/4
202 1/2	5/16	1/16	2 1/16	606	3/4	3/16	2 3/16	1009	1 1/8	5/16	2 5/16
302 1/2	5/16	3/32	2 3/32	806	3/4	1/4	2 1/4	610	1 1/4	3/16	2 3/16
203	3/8	1/16	2 1/16	507	7/8	5/32	2 5/32	710	1 1/4	7/32	2 7/32
303	3/8	3/32	2 3/32	607	7/8	3/16	2 3/16	810	1 1/4	1/4	2 1/4
403	3/8	1/8	2 1/8	707	7/8	7/32	2 7/32	1010	1 1/4	5/16	2 5/16
204	1/2	1/16	2 1/16	807	7/8	1/4	2 1/4	1210	1 1/4	3/8	2 3/8
304	1/2	3/32	2 3/32	608	1	3/16	2 3/16	811	1 3/8	1/4	2 1/4
404	1/2	1/8	2 1/8	708	1	7/32	2 7/32	1011	1 3/8	5/16	2 5/16
305	5/8	3/32	2 3/32	808	1	1/4	2 1/4	1211	1 3/8	3/8	2 3/8
405	5/8	1/8	2 1/8	1008	1	5/16	2 5/16	812	1 1/2	1/4	2 1/4
505	5/8	5/32	2 5/32	1208	1	3/8	2 3/8	1012	1 1/2	5/16	2 5/16
605	5/8	3/16	2 3/16	609	1 1/8	3/16	2 3/16	1212	1 1/2	3/8	2 3/8
406	3/4	1/8	2 1/8	709	1 1/8	7/32	2 7/32	…	…	…	…

Arbor-type Cutters

Cutter Number	Nom. Dia.of Cutter, *D*	Width of Face, *W*	Dia. of Hole, *H*	Cutter Number	Nom. Dia.of Cutter, *D*	Width of Face, *W*	Dia. of Hole, *H*	Cutter Number	Nom. Dia.of Cutter, *D*	Width of Face, *W*	Dia. of Hole, *H*
617	2 1/8	3/16	3/4	1022	2 3/4	5/16	1	1628	3 1/2	1/2	1
817	2 1/8	1/4	3/4	1222	2 3/4	3/8	1	1828	3 1/2	9/16	1
1017	2 1/8	5/16	3/4	1422	2 3/4	7/16	1	2028	3 1/2	5/8	1
1217	2 1/8	3/8	3/4	1622	2 3/4	1/2	1	2428	3 1/2	3/4	1
822	2 3/4	1/4	1	1228	3 1/2	3/8	1	…	…	…	…

All dimensions are given in inches. All cutters are high-speed steel.

Shank type cutters are standard with right-hand cut and straight teeth. All sizes have 1/2-inch diameter straight shank.

Arbor type cutters have staggered teeth.

For Woodruff key and key-slot dimensions, see pages 2369 through 2371.

Tolerances: Face with *W* for shank type cutters: 1/16- to 5/32-inch face, + 0.0000, –0.0005; 3/16 to 7/32, – 0.0002, – 0.0007; 1/4, –0.0003, –0.0008; 5/16, –0.0004, –0.0009; 3/8, – 0.0005, –0.0010 inch. Face width *W* for arbor type cutters; 3/16 inch face, –0.0002, –0.0007; 1/4, –0.0003, –0.0008; 5/16, –0.0004, –0.0009; 3/8 and over, –0.0005, –0.0010 inch. Hole size *H:* +0.00075, –0.0000 inch. Diameter *D* for shank type cutters: 1/4- through 3/4-inch diameter, +0.010, +0.015, 7/8 through 1 1/8, +0.012, +0.017; 1 1/4

Copyright 2004, Industrial Press, Inc., New York, NY

through 1½, +0.015, +0.020 inch. These tolerances include an allowance for sharpening. For arbor type cutters diameter D is furnished $\frac{1}{32}$ inch larger than listed and a tolerance of ±0.002 inch applies to the oversize diameter.

Setting Angles for Milling Straight Teeth of Uniform Land Width in End Mills, Angular Cutters, and Taper Reamers.— The accompanying tables give setting angles for the dividing head when straight teeth, having a land of uniform width throughout their length, are to be milled using single-angle fluting cutters. These setting angles depend upon three factors: the number of teeth to be cut; the angle of the blank in which the teeth are to be cut; and the angle of the fluting cutter. Setting angles for various combinations of these three factors are given in the tables. For example, assume that 12 teeth are to be cut on the end of an end mill using a 60-degree cutter. By following the horizontal line from 12 teeth, read in the column under 60 degrees that the dividing head should be set to an angle of 70 degrees and 32 minutes.



The following formulas, which were used to compile these tables, may be used to calculate the setting-angles for combinations of number of teeth, blank angle, and cutter angle not covered by the tables. In these formulas, A = setting-angle for dividing head, B = angle of blank in which teeth are to be cut, C = angle of fluting cutter, N = number of teeth to be cut, and D and E are angles not shown on the accompanying diagram and which are used only to simplify calculations.

$$\tan D = \cos(360°/N) \times \cot B \quad (1)$$

$$\sin E = \tan(360°/N) \times \cot C \times \sin D \quad (2)$$

$$\text{Setting-angle } A = D - E \quad (3)$$

Example: Suppose 9 teeth are to be cut in a 35-degree blank using a 55-degree single-angle fluting cutter. Then, $N = 9$, $B = 35°$, and $C = 55°$.

$\tan D = \cos(360°/9) \times \cot 35° = 0.76604 \times 1.4281 = 1.0940$; and $D = 47°34'$

$\sin E = \tan(360°/9) \times \cot 55° \times \sin 47°34' = 0.83910 \times 0.70021 \times 0.73806$
$= 0.43365$; and $E = 25°42'$

$$\text{Setting angle } A = 47°34' - 25°42' = 21°52'$$

For end mills and side mills the angle of the blank B is 0 degrees and the following simplified formula may be used to find the setting angle A

$$\cos A = \tan(360°/N) \times \cot C \quad (4)$$

Example: If in the previous example the blank angle was 0 degrees,
$\cos A = \tan(360°/9) \times \cot 55° = 0.83910 \times 0.70021 = 0.58755$,
and setting-angle $A = 54°1'$

Copyright 2004, Industrial Press, Inc., New York, NY

Angles of Elevation for Milling Straight Teeth in 0-, 5-, 10-, 15-, 20-, 25-, 30-, and 35-degree Blanks Using Single-Angle Fluting Cutters

No. of Teeth	Angle of Fluting Cutter									
	90°	80°	70°	60°	50°	90°	80°	70°	60°	50°
	0° Blank (End Mill)					5° Blank				
6	…	72° 13′	50° 55′	…	…	80° 4′	62° 34′	41° 41′	…	…
8	…	79 51	68 39	54° 44′	32° 57′	82 57	72 52	61 47	48° 0′	25° 40′
10	…	82 38	74 40	65 12	52 26	83 50	76 31	68 35	59 11	46 4
12	…	84 9	77 52	70 32	61 2	84 14	78 25	72 10	64 52	55 5
14	…	85 8	79 54	73 51	66 10	84 27	79 36	74 24	68 23	60 28
16	…	85 49	81 20	76 10	69 40	84 35	80 25	75 57	70 49	64 7
18	…	86 19	82 23	77 52	72 13	84 41	81 1	77 6	72 36	66 47
20	…	86 43	83 13	79 11	74 11	84 45	81 29	77 59	73 59	68 50
22	…	87 2	83 52	80 14	75 44	84 47	81 50	78 40	75 4	70 26
24	…	87 18	84 24	81 6	77 0	84 49	82 7	79 15	75 57	71 44
	10° Blank					15° Blank				
6	70° 34′	53° 50′	34° 5′	…	…	61° 49′	46° 12′	28° 4′	…	…
8	76 0	66 9	55 19	41° 56′	20° 39′	69 15	59 46	49 21	36° 34′	17° 34′
10	77 42	70 31	62 44	53 30	40 42	71 40	64 41	57 8	48 12	36 18
12	78 30	72 46	66 37	59 26	49 50	72 48	67 13	61 13	54 14	45 13
14	78 56	74 9	69 2	63 6	55 19	73 26	68 46	63 46	57 59	50 38
16	79 12	75 5	70 41	65 37	59 1	73 50	69 49	65 30	60 33	54 20
18	79 22	75 45	71 53	67 27	61 43	74 5	70 33	66 46	62 26	57 0
20	79 30	76 16	72 44	68 52	63 47	74 16	71 6	67 44	63 52	59 3
22	79 35	76 40	73 33	69 59	65 25	74 24	71 32	68 29	65 0	60 40
24	79 39	76 59	74 9	70 54	66 44	74 30	71 53	69 6	65 56	61 59
	20° Blank					25° Blank				
6	53° 57′	39° 39′	23° 18′	…	…	47° 0′	34° 6′	19° 33′	…	…
8	62 46	53 45	43 53	31° 53′	14° 31′	56 36	48 8	38 55	27° 47′	11° 33′
10	65 47	59 4	51 50	43 18	32 1	60 2	53 40	46 47	38 43	27 47
12	67 12	61 49	56 2	49 18	40 40	61 42	56 33	51 2	44 38	36 10
14	68 0	63 29	58 39	53 4	46 0	62 38	58 19	53 41	48 20	41 22
16	68 30	64 36	60 26	55 39	49 38	63 13	59 29	55 29	50 53	44 57
18	68 50	65 24	61 44	57 32	52 17	63 37	60 19	56 48	52 46	47 34
20	69 3	65 59	62 43	58 58	54 18	63 53	60 56	57 47	54 11	49 33
22	69 14	66 28	63 30	60 7	55 55	64 5	61 25	58 34	55 19	51 9
24	69 21	66 49	64 7	61 2	57 12	64 14	61 47	59 12	56 13	52 26
	30° Blank					35° Blank				
6	40° 54′	29° 22′	16° 32′	…	…	35° 32′	25° 19′	14° 3′	…	…
8	50 46	42 55	34 24	24° 12′	10° 14′	45 17	38 5	30 18	21° 4′	8° 41′
10	54 29	48 30	42 3	34 31	24 44	49 7	43 33	37 35	30 38	21 40
12	56 18	51 26	46 14	40 12	32 32	51 3	46 30	41 39	36 2	28 55
14	57 21	53 15	48 52	43 49	37 27	52 9	48 19	44 12	39 28	33 33
16	58 0	54 27	50 39	46 19	40 52	52 50	49 20	45 56	41 51	36 45
18	58 26	55 18	51 57	48 7	43 20	53 18	50 21	47 12	43 36	39 8
20	58 44	55 55	52 56	49 30	45 15	53 38	50 59	48 10	44 57	40 57
22	58 57	56 24	53 42	50 36	46 46	53 53	51 29	48 56	46 1	42 24
24	59 8	56 48	54 20	51 30	48 0	54 4	51 53	49 32	46 52	43 35

Copyright 2004, Industrial Press, Inc., New York, NY

Angles of Elevation for Milling Straight Teeth in 40-, 45-, 50-, 55-, 60-, 65-, 70-, and 75-degree Blanks Using Single-Angle Fluting Cutters

No. of Teeth	Angle of Fluting Cutter									
	90°	80°	70°	60°	50°	90°	80°	70°	60°	50°
	40° Blank					45° Blank				
6	30° 48′	21° 48′	11° 58′	…	…	26° 34′	18° 43′	10° 11′	…	…
8	40 7	33 36	26 33	18° 16′	7° 23′	35 16	29 25	23 8	15° 48′	5° 58′
10	43 57	38 51	33 32	27 3	18 55	38 58	34 21	29 24	23 40	16 10
12	45 54	41 43	37 14	32 3	25 33	40 54	37 5	33 0	28 18	22 13
14	47 3	43 29	39 41	35 19	29 51	42 1	38 46	35 17	31 18	26 9
16	47 45	44 39	41 21	37 33	32 50	42 44	39 54	36 52	33 24	28 57
18	48 14	45 29	42 34	39 13	35 5	43 13	40 42	38 1	34 56	30 1
20	48 35	46 7	43 30	40 30	36 47	43 34	41 18	38 53	36 8	32 37
22	48 50	46 36	44 13	41 30	38 8	43 49	41 46	39 34	37 5	34 53
24	49 1	46 58	44 48	42 19	39 15	44 0	42 7	40 7	37 50	35 55
	50° Blank					55° Blank				
6	22° 45′	15° 58′	8° 38′	…	…	19° 17′	13° 30′	7° 15′	…	…
8	30 41	25 31	19 59	13° 33′	5° 20′	26 21	21 52	17 3	11° 30′	4° 17′
10	34 10	30 2	25 39	20 32	14 9	29 32	25 55	22 3	17 36	11 52
12	36 0	32 34	28 53	24 42	19 27	31 14	28 12	24 59	21 17	16 32
14	37 5	34 9	31 1	27 26	22 58	32 15	29 39	26 53	23 43	19 40
16	37 47	35 13	32 29	29 22	25 30	32 54	30 38	28 12	25 26	21 54
18	38 15	35 58	33 33	30 46	27 21	33 21	31 20	29 10	26 43	23 35
20	38 35	36 32	34 21	31 52	28 47	33 40	31 51	29 54	27 42	24 53
22	38 50	36 58	34 59	32 44	29 57	33 54	32 15	30 29	28 28	25 55
24	39 1	37 19	35 30	33 25	30 52	34 5	32 34	30 57	29 7	26 46
	60° Blank					65° Blank				
6	16° 6′	11° 12′	6° 2′	…	…	13° 7′	9° 8′	4° 53′	…	…
8	22 13	18 24	14 19	9° 37′	3° 44′	18 15	15 6	11 42	7° 50′	3° 1′
10	25 2	21 56	18 37	14 49	10 5	20 40	18 4	15 19	12 9	8 15
12	26 34	23 57	21 10	17 59	14 13	21 59	19 48	17 28	14 49	11 32
14	27 29	25 14	22 51	20 6	16 44	22 48	20 55	18 54	16 37	13 48
16	28 5	26 7	24 1	21 37	18 40	23 18	21 39	19 53	17 53	15 24
18	28 29	26 44	24 52	22 44	20 6	23 40	22 11	20 37	18 50	16 37
20	28 46	27 11	25 30	23 35	21 14	23 55	22 35	21 10	19 33	17 34
22	29 0	27 34	26 2	24 17	22 8	24 6	22 53	21 36	20 8	18 20
24	29 9	27 50	26 26	24 50	22 52	24 15	23 8	21 57	20 36	18 57
	70° Blank					75° Blank				
6	10° 18′	7° 9′	3° 48′	…	…	7° 38′	5° 19′	2° 50′	…	…
8	14 26	11 55	9 14	6° 9′	2° 21′	10 44	8 51	6 51	4° 34′	1° 45′
10	16 25	14 21	12 8	9 37	6 30	12 14	10 40	9 1	7 8	4 49
12	17 30	15 45	13 53	11 45	9 8	13 4	11 45	10 21	8 45	6 47
14	18 9	16 38	15 1	13 11	10 55	13 34	12 26	11 13	9 50	8 7
16	18 35	17 15	15 50	14 13	12 13	13 54	12 54	11 50	10 37	9 7
18	18 53	17 42	16 26	14 59	13 13	14 8	13 14	12 17	11 12	9 51
20	19 6	18 1	16 53	15 35	13 59	14 18	13 29	12 38	11 39	10 27
22	19 15	18 16	17 15	16 3	14 35	14 25	13 41	12 53	12 0	10 54
24	19 22	18 29	17 33	16 25	15 5	14 31	13 50	13 7	12 18	11 18

Copyright 2004, Industrial Press, Inc., New York, NY

Angles of Elevation for Milling Straight Teeth in 80- and 85-degree Blanks Using Single-Angle Fluting Cutters

No.of Teeth	Angle of Fluting Cutter									
	90°	80°	70°	60°	50°	90°	80°	70°	60°	50°
	80° Blank					85° Blank				
6	5° 2′	3° 30′	1° 52′	…	…	2° 30′	1° 44′	0° 55′	…	…
8	7 6	5 51	4 31	3° 2′	1° 8′	3 32	2 55	2 15	1° 29′	0° 34′
10	8 7	7 5	5 59	4 44	3 11	4 3	3 32	2 59	2 21	1 35
12	8 41	7 48	6 52	5 48	4 29	4 20	3 53	3 25	2 53	2 15
14	9 2	8 16	7 28	6 32	5 24	4 30	4 7	3 43	3 15	2 42
16	9 15	8 35	7 51	7 3	6 3	4 37	4 17	3 56	3 30	3 1
18	9 24	8 48	8 10	7 26	6 33	4 42	4 24	4 5	3 43	3 16
20	9 31	8 58	8 24	7 44	6 56	4 46	4 29	4 12	3 52	3 28
22	9 36	9 6	8 35	7 59	7 15	4 48	4 33	4 18	3 59	3 37
24	9 40	9 13	8 43	8 11	7 30	4 50	4 36	4 22	4 5	3 45

Spline-Shaft Milling Cutter.— The most efficient method of forming splines on shafts is by hobbing, but special milling cutters may also be used. Since the cutter forms the space between adjacent splines, it must be made to suit the number of splines and the root diameter of the shaft. The cutter angle B equals 360 degrees divided by the number of splines. The following formulas are for determining the chordal width C at the root of the splines or the chordal width across the concave edge of the cutter. In these formulas, A = angle between center line of spline and a radial line passing through the intersection of the root circle and one side of the spline; W = width of spline; d = root diameter of splined shaft; C = chordal width at root circle between adjacent splines; N = number of splines.



$$\sin A = \frac{W}{d} \qquad C = d \times \sin\left(\frac{180}{N} - A\right)$$

Splines of involute form are often used in preference to the straight-sided type. Dimensions of the American Standard involute splines and hobs are given in the section on splines.

Cutter Grinding

Wheels for Sharpening Milling Cutters.— Milling cutters may be sharpened either by using the periphery of a disk wheel or the face of a cup wheel. The latter grinds the lands of the teeth flat, whereas the periphery of a disk wheel leaves the teeth slightly concave back of the cutting edges. The concavity produced by disk wheels reduces the effective clearance angle on the teeth, the effect being more pronounced for wheels of small diameter than for wheels of large diameter. For this reason, large diameter wheels are preferred when sharpening milling cutters with disk type wheels. Irrespective of what type of wheel is used to sharpen a milling cutter, any burrs resulting from grinding should be carefully

Copyright 2004, Industrial Press, Inc., New York, NY

removed by a hand stoning operation. Stoning also helps to reduce the roughness of grinding marks and improves the quality of the finish produced on the surface being machined. Unless done very carefully, hand stoning may dull the cutting edge. Stoning may be avoided and a sharper cutting edge produced if the wheel rotates toward the cutting edge, which requires that the operator maintain contact between the tool and the rest while the wheel rotation is trying to move the tool away from the rest. Though slightly more difficult, this method will eliminate the burr.

Specifications of Grinding Wheels for Sharpening Milling Cutters

Cutter Material	Operation	Grinding Wheel			
		Abrasive Material	Grain Size	Grade	Bond
Carbon Tool Steel	Roughing Finishing	Aluminum Oxide	46–60 100	K H	Vitrified Vitrified
High-speed Steel:					
18-4-1 {	Roughing	Aluminum Oxide	60	K,H	Vitrified
	Finishing		100	H	Vitrified
18-4-2 {	Roughing		80	F,G,H	Vitrified
	Finishing		100	H	Vitrified
Cast Non-Ferrous Tool Material	Roughing Finishing	Aluminum Oxide	46 100–120	H,K,L,N H	Vitrified Vitrified
Sintered Carbide	Roughing after Brazing	Silicon Carbide	60	G	Vitrified
	Roughing	Diamond	100	[a]	Resinoid
	Finishing	Diamond	Up to 500	[a]	Resinoid
Carbon Tool Steel and High-Speed Steel[b]	Roughing Finishing	Cubic Boron Nitride	80–100 100–120	R,P S,T	Resinoid Resinoid

[a] Not indicated in diamond wheel markings.
[b] For hardnesses above Rockwell C 56.

Wheel Speeds and Feeds for Sharpening Milling Cutters.— Relatively low cutting speeds should be used when sharpening milling cutters to avoid tempering and heat checking. Dry grinding is recommended in all cases except when diamond wheels are employed. The surface speed of grinding wheels should be in the range of 4500 to 6500 feet per minute for grinding milling cutters of high-speed steel or cast non-ferrous tool material. For sintered carbide cutters, 5000 to 5500 feet per minute should be used.

The maximum stock removed per pass of the grinding wheel should not exceed about 0.0004 inch for sintered carbide cutters; 0.003 inch for large high-speed steel and cast non-ferrous tool material cutters; and 0.0015 inch for narrow saws and slotting cutters of high-speed steel or cast non-ferrous tool material. The stock removed per pass of the wheel may be increased for backing-off operations such as the grinding of secondary clearance behind the teeth since there is usually a sufficient body of metal to carry off the heat.

Clearance Angles for Milling Cutter Teeth.— The clearance angle provided on the cutting edges of milling cutters has an important bearing on cutter performance, cutting efficiency, and cutter life between sharpenings. It is desirable in all cases to use a clearance angle as small as possible so as to leave more metal back of the cutting edges for better heat dissipation and to provide maximum support. Excessive clearance angles not only weaken the cutting edges, but also increase the likelihood of "chatter" which will result in poor finish on the machined surface and reduce the life of the cutter. According to The Cincinnati Milling Machine Co., milling cutters used for general purpose work and having diameters from $\frac{1}{8}$ to 3 inches should have clearance angles from 13 to 5 degrees, respectively, decreasing proportionately as the diameter increases. General purpose cutters over 3

Copyright 2004, Industrial Press, Inc., New York, NY

inches in diameter should be provided with a clearance angle of 4 to 5 degrees. The land width is usually $\frac{1}{64}$, $\frac{1}{32}$, and $\frac{1}{16}$ inch, respectively, for small, medium, and large cutters.

The primary clearance or relief angle for best results varies according to the material being milled about as follows: low carbon, high carbon, and alloy steels, 3 to 5 degrees; cast iron and medium and hard bronze, 4 to 7 degrees; brass, soft bronze, aluminum, magnesium, plastics, etc., 10 to 12 degrees. When milling cutters are resharpened, it is customary to grind a secondary clearance angle of 3 to 5 degrees behind the primary clearance angle to reduce the land width to its original value and thus avoid interference with the surface to be milled. A general formula for plain milling cutters, face mills, and form relieved cutters which gives the clearance angle C, in degrees, necessitated by the feed per revolution F, in inches, the width of land L, in inches, the depth of cut d, in inches, the cutter diameter D, in inches, and the Brinell hardness number B of the work being cut is:

$$C = \frac{45860}{DB}\left(1.5L + \frac{F}{\pi D}\sqrt{d(D-d)}\right)$$

Rake Angles for Milling Cutters.— In peripheral milling cutters, the rake angle is generally defined as the angle in degrees that the tooth face deviates from a radial line to the cutting edge. In face milling cutters, the teeth are inclined with respect to both the radial and axial lines. These angles are called *radial* and *axial* rake, respectively. The radial and axial rake angles may be positive, zero, or negative.

Positive rake angles should be used whenever possible for all types of high-speed steel milling cutters. For sintered carbide tipped cutters, zero and negative rake angles are frequently employed to provide more material back of the cutting edge to resist shock loads.

Rake Angles for High-speed Steel Cutters: Positive rake angles of 10 to 15 degrees are satisfactory for milling steels of various compositions with plain milling cutters. For softer materials such as magnesium and aluminum alloys, the rake angle may be 25 degrees or more. Metal slitting saws for cutting alloy steel usually have rake angles from 5 to 10 degrees, whereas zero and sometimes negative rake angles are used for saws to cut copper and other soft non-ferrous metals to reduce the tendency to "hog in." Form relieved cutters usually have rake angles of 0, 5, or 10 degrees. Commercial face milling cutters usually have 10 degrees positive radial and axial rake angles for general use in milling cast iron, forged and alloy steel, brass, and bronze; for milling castings and forgings of magnesium and free-cutting aluminum and their alloys, the rake angles may be increased to 25 degrees positive or more, depending on the operating conditions; a smaller rake angle is used for abrasive or difficult to machine aluminum alloys.

Cast Non-ferrous Tool Material Milling Cutters: Positive rake angles are generally provided on milling cutters using cast non-ferrous tool materials although negative rake angles may be used advantageously for some operations such as those where shock loads are encountered or where it is necessary to eliminate vibration when milling thin sections.

Sintered Carbide Milling Cutters: Peripheral milling cutters such as slab mills, slotting cutters, saws, etc., tipped with sintered carbide, generally have negative radial rake angles of 5 degrees for soft low carbon steel and 10 degrees or more for alloy steels. Positive axial rake angles of 5 and 10 degrees, respectively, may be provided, and for slotting saws and cutters, 0 degree axial rake may be used. On soft materials such as free-cutting aluminum alloys, positive rake angles of 10 to so degrees are used. For milling abrasive or difficult to machine aluminum alloys, small positive or even negative rake angles are used.

Eccentric Type Radial Relief.— When the radial relief angles on peripheral teeth of milling cutters are ground with a disc type grinding wheel in the conventional manner the ground surfaces on the lands are slightly concave, conforming approximately to the radius of the wheel. A flat land is produced when the radial relief angle is ground with a cup wheel. Another entirely different method of grinding the radial angle is by the eccentric method, which produces a slightly convex surface on the land. If the radial relief angle at

Copyright 2004, Industrial Press, Inc., New York, NY

the cutting edge is equal for all of the three types of land mentioned, it will be found that the land with the eccentric relief will drop away from the cutting edge a somewhat greater distance for a given distance around the land than will the others. This is evident from a study of Table 1 entitled, *Indicator Drops for Checking the Radial Relief Angle on Peripheral Teeth*. This feature is an advantage of the eccentric type relief which also produces an excellent finish.

Table 1. Indicator Drops for Checking the Radial Relief Angle on Peripheral Teeth

Cutter Diameter, Inch	Rec. Range of Radial Relief Angles, Degrees	Checking Distance, Inch	Indicator Drops, Inches				Rec. Max. Primary Land Width, Inch
			For Flat and Concave Relief		For Eccentric Relief		
			Min.	Max.	Min.	Max.	
1/16	20–25	.005	.0014	.0019	.0020	.0026	.007
3/32	16–20	.005	.0012	.0015	.0015	.0019	.007
1/8	15–19	.010	.0018	.0026	.0028	.0037	.015
5/32	13–17	.010	.0017	.0024	.0024	.0032	.015
3/16	12–16	.010	.0016	.0023	.0022	.0030	.015
7/32	11–15	.010	.0015	.0022	.0020	.0028	.015
1/4	10–14	.015	.0017	.0028	.0027	.0039	.020
9/32	10–14	.015	.0018	.0029	.0027	.0039	.020
5/16	10–13	.015	.0019	.0027	.0027	.0035	.020
11/32	10–13	.015	.0020	.0028	.0027	.0035	.020
3/8	10–13	.015	.0020	.0029	.0027	.0035	.020
13/32	9–12	.020	.0022	.0032	.0032	.0044	.025
7/16	9–12	.020	.0022	.0033	.0032	.0043	.025
15/32	9–12	.020	.0023	.0034	.0032	.0043	.025
1/2	9–12	.020	.0024	.0034	.0032	.0043	.025
9/16	9–12	.020	.0024	.0035	.0032	.0043	.025
5/8	8–11	.020	.0022	.0032	.0028	.0039	.025
11/16	8–11	.030	.0029	.0045	.0043	.0059	.035
3/4	8–11	.030	.0030	.0046	.0043	.0059	.035
13/16	8–11	.030	.0031	.0047	.0043	.0059	.035
7/8	8–11	.030	.0032	.0048	.0043	.0059	.035
15/16	7–10	.030	.0027	.0043	.0037	.0054	.035
1	7–10	.030	.0028	.0044	.0037	.0054	.035
1 1/8	7–10	.030	.0029	.0045	.0037	.0053	.035
1 1/4	6–9	.030	.0024	.0040	.0032	.0048	.035
1 3/8	6–9	.030	.0025	.0041	.0032	.0048	.035
1 1/2	6–9	.030	.0026	.0041	.0032	.0048	.035
1 5/8	6–9	.030	.0026	.0042	.0032	.0048	.035
1 3/4	6–9	.030	.0026	.0042	.0032	.0048	.035
1 7/8	6–9	.030	.0027	.0043	.0032	.0048	.035
2	6–9	.030	.0027	.0043	.0032	.0048	.035
2 1/4	5–8	.030	.0022	.0038	.0026	.0042	.040
2 1/2	5–8	.030	.0023	.0039	.0026	.0042	.040
2 3/4	5–8	.030	.0023	.0039	.0026	.0042	.040
3	5–8	.030	.0023	.0039	.0026	.0042	.040
3 1/2	5–8	.030	.0024	.0040	.0026	.0042	.047
4	5–8	.030	.0024	.0040	.0026	.0042	.047
5	4–7	.030	.0019	.0035	.0021	.0037	.047
6	4–7	.030	.0019	.0035	.0021	.0037	.047
7	4–7	.030	.0020	.0036	.0021	.0037	.060
8	4–7	.030	.0020	.0036	.0021	.0037	.060
10	4–7	.030	.0020	.0036	.0021	.0037	.060
12	4–7	.030	.0020	.0036	.0021	.0037	.060

Copyright 2004, Industrial Press, Inc., New York, NY

The setup for grinding an eccentric relief is shown in Fig. 1. In this setup the point of contact between the cutter and the tooth rest must be in the same plane as the centers, or axes, of the grinding wheel and the cutter. A wide face is used on the grinding wheel, which is trued and dressed at an angle with respect to the axis of the cutter. An alternate method is to tilt the wheel at this angle. Then as the cutter is traversed and rotated past the grinding wheel while in contact with the tooth rest, an eccentric relief will be generated by the angular face of the wheel. This type of relief can only be ground on the peripheral teeth on milling cutters having helical flutes because the combination of the angular wheel face and the twisting motion of the cutter is required to generate the eccentric relief. Therefore, an eccentric relief cannot be ground on the peripheral teeth of straight fluted cutters.

Table 2 is a table of wheel angles for grinding an eccentric relief for different combinations of relief angles and helix angles. When angles are required that cannot be found in this table, the wheel angle, W, can be calculated by using the following formula, in which R is the radial relief angle and H is the helix angle of the flutes on the cutter.

$$\tan W = \tan R \times \tan H$$

Table 2. Grinding Wheel Angles for Grinding Eccentric Type Radial Relief Angle

Radial Relief Angle, R, Degrees	Helix Angle of Cutter Flutes, H, Degrees							
	12	18	20	30	40	45	50	52
	Wheel Angle, W, Degrees							
1	0°13′	0°19′	0°22′	0°35′	0°50′	1°00′	1°12′	1°17′
2	0°26′	0°39′	0°44′	1°09′	1°41′	2°00′	2°23′	2°34′
3	0°38′	0°59′	1°06′	1°44′	2°31′	3°00′	3°34′	3°50′
4	0°51′	1°18′	1°27′	2°19′	3°21′	4°00′	4°46′	5°07′
5	1°04′	1°38′	1°49′	2°53′	4°12′	5°00′	5°57′	6°23′
6	1°17′	1°57′	2°11′	3°28′	5°02′	6°00′	7°08′	7°40′
7	1°30′	2°17′	2°34′	4°03′	5°53′	7°00′	8°19′	8°56′
8	1°43′	2°37′	2°56′	4°38′	6°44′	8°00′	9°30′	10°12′
9	1°56′	2°57′	3°18′	5°13′	7°34′	9°00′	10°41′	11°28′
10	2°09′	3°17′	3°40′	5°49′	8°25′	10°00′	11°52′	12°43′
11	2°22′	3°37′	4°03′	6°24′	9°16′	11°00′	13°03′	13°58′
12	2°35′	3°57′	4°25′	7°00′	10°07′	12°00′	14°13′	15°13′
13	2°49′	4°17′	4°48′	7°36′	10°58′	13°00′	15°23′	16°28′
14	3°02′	4°38′	5°11′	8°11′	11°49′	14°00′	16°33′	17°42′
15	3°16′	4°59′	5°34′	8°48′	12°40′	15°00′	17°43′	18°56′
16	3°29′	5°19′	5°57′	9°24′	13°32′	16°00′	18°52′	20°09′
17	3°43′	5°40′	6°21′	10°01′	14°23′	17°00′	20°01′	21°22′
18	3°57′	6°02′	6°45′	10°37′	15°15′	18°00′	21°10′	22°35′
19	4°11′	6°23′	7°09′	11°15′	16°07′	19°00′	22°19′	23°47′
20	4°25′	6°45′	7°33′	11°52′	16°59′	20°00′	23°27′	24°59′
21	4°40′	7°07′	7°57′	12°30′	17°51′	21°00′	24°35′	26°10′
22	4°55′	7°29′	8°22′	13°08′	18°44′	22°00′	25°43′	27°21′
23	5°09′	7°51′	8°47′	13°46′	19°36′	23°00′	26°50′	28°31′
24	5°24′	8°14′	9°12′	14°25′	20°29′	24°00′	27°57′	29°41′
25	5°40′	8°37′	9°38′	15°04′	21°22′	25°00′	29°04′	30°50′

Copyright 2004, Industrial Press, Inc., New York, NY

Indicator Drop Method of Checking Relief and Rake Angles.— The most convenient and inexpensive method of checking the relief and rake angles on milling cutters is by the indicator drop method. Three tables, Tables 1, 3 and 4, of indicator drops are provided in this section, for checking radial relief angles on the peripheral teeth, relief angles on side and end teeth, and rake angles on the tooth faces.



Fig. 1. Setup for Grinding Eccentric Type Radial Relief Angle

Table 3. Indicator Drops for Checking Relief Angles on Side Teeth and End Teeth

Checking Distance, Inch	Given Relief Angle								
	1°	2°	3°	4°	5°	6°	7°	8°	9°
	Indicator Drop, inch								
.005	.00009	.00017	.00026	.00035	.0004	.0005	.0006	.0007	.0008
.010	.00017	.00035	.00052	.0007	.0009	.0011	.0012	.0014	.0016
.015	.00026	.0005	.00079	.0010	.0013	.0016	.0018	.0021	.0024
.031	.00054	.0011	.0016	.0022	.0027	.0033	.0038	.0044	.0049
.047	.00082	.0016	.0025	.0033	.0041	.0049	.0058	.0066	.0074
.062	.00108	.0022	.0032	.0043	.0054	.0065	.0076	.0087	.0098



Fig. 2. Setup for Checking the Radial Relief Angle by Indicator Drop Method

The setup for checking the radial relief angle is illustrated in Fig. 2. Two dial test indicators are required, one of which should have a sharp pointed contact point. This indicator is positioned so that the axis of its spindle is vertical, passing through the axis of the cutter. The cutter may be held by its shank in the spindle of a tool and cutter grinder workhead, or

Copyright 2004, Industrial Press, Inc., New York, NY

between centers while mounted on a mandrel. The cutter is rotated to the position where the vertical indicator contacts a cutting edge. The second indicator is positioned with its spindle axis horizontal and with the contact point touching the tool face just below the cutting edge. With both indicators adjusted to read zero, the cutter is rotated a distance equal to the checking distance, as determined by the reading on the second indicator. Then the indicator drop is read on the vertical indicator and checked against the values in the tables. The indicator drops for radial relief angles ground by a disc type grinding wheel and those ground with a cup wheel are so nearly equal that the values are listed together; values for the eccentric type relief are listed separately, since they are larger. A similar procedure is used to check the relief angles on the side and end teeth of milling cutters; however, only one indicator is used. Also, instead of rotating the cutter, the indicator or the cutter must be moved a distance equal to the checking distance in a straight line.

Table 4. Indicator Drops for Checking Rake Angles on Milling Cutter Face



Set indicator to read zero on horizontal plane passing through cutter axis. Zero cutting edge against indicator.

Move cutter or indicator measuring distance.

Rate Angle, Deg.	Measuring Distance, inch				Rate Angle, Deg.	Measuring Distance, inch			
	.031	.062	.094	.125		.031	.062	.094	.125
	Indicator Drop, inch					Indicator Drop, inch			
1	.0005	.0011	.0016	.0022	11	.0060	.0121	.0183	.0243
2	.0011	.0022	.0033	.0044	12	.0066	.0132	.0200	.0266
3	.0016	.0032	.0049	.0066	13	.0072	.0143	.0217	.0289
4	.0022	.0043	.0066	.0087	14	.0077	.0155	.0234	.0312
5	.0027	.0054	.0082	.0109	15	.0083	.0166	.0252	.0335
6	.0033	.0065	.0099	.0131	16	.0089	.0178	.0270	.0358
7	.0038	.0076	.0115	.0153	17	.0095	.0190	.0287	.0382
8	.0044	.0087	.0132	.0176	18	.0101	.0201	.0305	.0406
9	.0049	.0098	.0149	.0198	19	.0107	.0213	.0324	.0430
10	.0055	.0109	.0166	.0220	20	.0113	.0226	.0342	.0455

Relieving Attachments.— A relieving attachment is a device applied to lathes (especially those used in tool-rooms) for imparting a reciprocating motion to the tool-slide and tool, in order to provide relief or clearance for the cutting edges of milling cutters, taps, hobs, etc. For example, in making a milling cutter of the formed type, such as is used for cutting gears, it is essential to provide clearance for the teeth and so form them that they may he ground repeatedly without changing the contour or shape of the cutting edge. This may be accomplished by using a relieving attachment. The tool for "backing off" or giving clearance to the teeth corresponds to the shape required, and it is given a certain amount of reciprocating movement, so that it forms a surface back of each cutting edge, which is of uniform cross-section on a radial plane but eccentric to the axis of the cutter sufficiently to provide the necessary clearance for the cutting edges.

Copyright 2004, Industrial Press, Inc., New York, NY

Various Set-ups Used in Grinding the Clearance Angle on Milling Cutter Teeth



Wheel Above Center | Wheel Below Center | In-Line Centers | Cup Wheel

Distance to Set Center of Wheel Above the Cutter Center (Disk Wheel)

Dia. of Wheel, Inches	Desired Clearance Angle, Degrees											
	1	2	3	4	5	6	7	8	9	10	11	12
	[a]Distance to Offset Wheel Center Above Cutter Center, Inches											
3	.026	.052	.079	.105	.131	.157	.183	.209	.235	.260	.286	.312
4	.035	.070	.105	.140	.174	.209	.244	.278	.313	.347	.382	.416
5	.044	.087	.131	.174	.218	.261	.305	.348	.391	.434	.477	.520
6	.052	.105	.157	.209	.261	.314	.366	.417	.469	.521	.572	.624
7	.061	.122	.183	.244	.305	.366	.427	.487	.547	.608	.668	.728
8	.070	.140	.209	.279	.349	.418	.488	.557	.626	.695	.763	.832
9	.079	.157	.236	.314	.392	.470	.548	.626	.704	.781	.859	.936
10	.087	.175	.262	.349	.436	.523	.609	.696	.782	.868	.954	1.040

[a] Calculated from the formula: Offset = Wheel Diameter × ½ × Sine of Clearance Angle.

Distance to Set Center of Wheel Below the Cutter Center (Disk Wheel)

Dia. of Cutter, Inches	Desired Clearance Angle, Degrees											
	1	2	3	4	5	6	7	8	9	10	11	12
	[a]Distance to Offset Wheel Center Below Cutter Center, Inches											
2	.017	.035	.052	.070	.087	.105	.122	.139	.156	.174	.191	.208
3	.026	.052	.079	.105	.131	.157	.183	.209	.235	.260	.286	.312
4	.035	.070	.105	.140	.174	.209	.244	.278	.313	.347	.382	.416
5	.044	.087	.131	.174	.218	.261	.305	.348	.391	.434	.477	.520
6	.052	.105	.157	.209	.261	.314	.366	.417	.469	.521	.572	.624
7	.061	.122	.183	.244	.305	.366	.427	.487	.547	.608	.668	.728
8	.070	.140	.209	.279	.349	.418	.488	.557	.626	.695	.763	.832
9	.079	.157	.236	.314	.392	.470	.548	.626	.704	.781	.859	.936
10	.087	.175	.262	.349	.436	.523	.609	.696	.782	.868	.954	1.040

[a] Calculated from the formula: Offset = Cutter Diameter × ½ × Sine of Clearance Angle.

Distance to Set Tooth Rest Below Center Line of Wheel and Cutter.— When the clearance angle is ground with a disk type wheel by keeping the center line of the wheel in line with the center line of the cutter, the tooth rest should be lowered by an amount given by the following formula:

$$\text{Offset} = \frac{\text{Wheel Diam.} \times \text{Cutter Dia.} \times \text{Sine of One-half the Clearance Angle}}{\text{Wheel Dia.} + \text{Cutter Dia.}}$$

Distance to Set Tooth Rest Below Cutter Center When Cup Wheel is Used.— When the clearance is ground with a cup wheel, the tooth rest is set below the center of the cutter the same amount as given in the table for *Distance to Set Center of Wheel Below the Cutter Center (Disk Wheel)*.

Copyright 2004, Industrial Press, Inc., New York, NY

REAMERS

Hand Reamers.— Hand reamers are made with both straight and helical flutes. Helical flutes provide a shearing cut and are especially useful in reaming holes having keyways or grooves, as these are bridged over by the helical flutes, thus preventing binding or chattering. Hand reamers are made in both solid and expansion forms. The American standard dimensions for solid forms are given in the accompanying table. The expansion type is useful whenever, in connection with repair or other work, it is necessary to enlarge a reamed hole by a few thousandths of an inch. The expansion form is split through the fluted section and a slight amount of expansion is obtained by screwing in a tapering plug. The diameter increase may vary from 0.005 to 0.008 inch for reamers up to about 1 inch diameter and from 0.010 to 0.012 inch for diameters between 1 and 2 inches. Hand reamers are tapered slightly on the end to facilitate starting them properly. The actual diameter of the shanks of commercial reamers may be from 0.002 to 0.005 inch under the reamer size. That part of the shank that is squared should be turned smaller in diameter than the shank itself, so that, when applying a wrench, no burr may be raised that may mar the reamed hole if the reamer is passed clear through it.

When fluting reamers, the cutter is so set with relation to the center of the reamer blank that the tooth gets a slight negative rake; that is, the cutter should be set *ahead* of the center, as shown in the illustration accompanying the table giving the amount to set the cutter ahead of the radial line. The amount is so selected that a tangent to the circumference of the reamer at the cutting point makes an angle of approximately 95 degrees with the front face of the cutting edge.

Amount to Set Cutter Ahead of Radial Line to Obtain Negative Front Rake



Size of Reamer	*a*, Inches	Size of Reamer	*a*, Inches	Size of Reamer	*a*, Inches
1/4	0.011	7/8	0.038	2	0.087
3/8	0.016	1	0.044	2 1/4	0.098
1/2	0.022	1 1/4	0.055	2 1/2	0.109
5/8	0.027	1 1/2	0.066	2 3/4	0.120
3/4	0.033	1 3/4	0.076	3	0.131

When fluting reamers, it is necessary to "break up the flutes"; that is, to space the cutting edges unevenly around the reamer. The difference in spacing should be very slight and need not exceed two degrees one way or the other. The manner in which the breaking up of the flutes is usually done is to move the index head to which the reamer is fixed a certain amount more or less than it would be moved if the spacing were regular. A table is given showing the amount of this additional movement of the index crank for reamers with different numbers of flutes. When a reamer is provided with helical flutes, the angle of spiral should be such that the cutting edges make an angle of about 10 or at most 15 degrees with the axis of the reamer.

The relief of the cutting edges should be comparatively slight. An eccentric relief, that is, one where the land back of the cutting edge is convex, rather than flat, is used by one or two manufacturers, and is preferable for finishing reamers, as the reamer will hold its size longer. When hand reamers are used merely for removing stock, or simply for enlarging holes, the flat relief is better, because the reamer has a keener cutting edge. The width of the land of the cutting edges should be about 1/32 inch for a 1/4-inch, 1/16 inch for a 1-inch, and 3/32 inch for a 3-inch reamer.

Copyright 2004, Industrial Press, Inc., New York, NY

Irregular Spacing of Teeth in Reamers

Number of flutes in reamer	4	6	8	10	12	14	16
Index circle to use	39	39	39	39	39	49	20
Before cutting	Move Spindle the Number of Holes below More or Less than for Regular Spacing						
2d flute	8 less	4 less	3 less	2 less	4 less	3 less	2 less
3d flute	4 more	5 more	5 more	3 more	4 more	2 more	2 more
4th flute	6 less	7 less	2 less	5 less	1 less	2 less	1 less
5th flute	…	6 more	4 more	2 more	3 more	4 more	2 more
6th flute	…	5 less	6 less	2 less	4 less	1 less	2 less
7th flute	…	…	2 more	3 more	4 more	3 more	1 more
8th flute	…	…	3 less	2 less	3 less	2 less	2 less
9th flute	…	…	…	5 more	2 more	1 more	2 more
10th flute	…	…	…	1 less	2 less	3 less	2 less
11th flute	…	…	…	…	3 more	3 more	1 more
12th flute	…	…	…	…	4 less	2 less	2 less
13th flute	…	…	…	…	…	2 more	2 more
14th flute	…	…	…	…	…	3 less	1 less
15th flute	…	…	…	…	…	…	2 more
16th flute	…	…	…	…	…	…	2 less

Threaded-end Hand Reamers.— Hand reamers are sometimes provided with a thread at the extreme point in order to give them a uniform feed when reaming. The diameter on the top of this thread at the point of the reamer is slightly smaller than the reamer itself, and the thread tapers upward until it reaches a dimension of from 0.003 to 0.008 inch, according to size, below the size of the reamer; at this point, the thread stops and a short neck about 1/16-inch wide separates the threaded portion from the actual reamer, which is provided with a short taper from 3/16 to 7/16 inch long up to where the standard diameter is reached. The length of the threaded portion and the number of threads per inch for reamers of this kind are given in the accompanying table. The thread employed is a sharp V-thread.

Dimensions for Threaded-End Hand Reamers

Sizes of Reamers	Length of Threaded Part	No. of Threads per Inch	Dia. of Thread at Point of Reamer	Sizes of Reamers	Length of Threaded Part	No. of Threads per Inch	Dia. of Thread at Point of Reamer
			Full diameter				Full diameter
1/8–5/16	3/8	32	–0.006	1 1/32–1 1/2	9/16	18	–0.010
11/32–1/2	7/16	28	–0.006	1 17/32–2	9/16	18	–0.012
17/32–3/4	1/2	24	–0.008	2 1/32–2 1/2	9/16	18	–0.015
25/32–1	9/16	18	–0.008	2 17/32–3	9/16	18	–0.020

Fluted Chucking Reamers.— Reamers of this type are used in turret lathes, screw machines, etc., for enlarging holes and finishing them smooth and to the required size. The best results are obtained with a floating type of holder that permits a reamer to align itself with the hole being reamed. These reamers are intended for removing a small amount of metal, 0.005 to 0.010 inch being common allowances. Fluted chucking reamers are provided either with a straight shank or a standard taper shank. (See table for standard dimensions.)

Copyright 2004, Industrial Press, Inc., New York, NY

Fluting Cutters for Reamers



Reamer Dia.	Fluting Cutter Dia. A	Fluting Cutter Thickness B	Hole Dia. in Cutter C	Radius between Cutting Faces D	Reamer Dia.	Fluting Cutter Dia. A	Fluting Cutter Thickness B	Hole Dia. in Cutter C	Radius between Cutting Faces D
1/8	1 3/4	3/16	3/4	none[a]	1 1/4	2 1/4	9/16	1	1/16
3/16	1 3/4	3/16	3/4	none[a]	1 1/2	2 1/4	5/8	1	1/16
1/4	1 3/4	3/16	3/4	1/64	1 3/4	2 1/4	5/8	1	5/64
3/8	2	1/4	3/4	1/64	2	2 1/2	3/4	1	5/64
1/2	2	5/16	3/4	1/32	2 1/4	2 1/2	3/4	1	5/64
5/8	2	3/8	3/4	1/32	2 1/2	2 1/2	7/8	1	3/16
3/4	2	7/16	3/4	3/64	2 3/4	2 1/2	7/8	1	3/16
1	2 1/4	1/2	1	3/64	3	2 1/2	1	1	3/16

[a] Sharp corner, no radius

Rose Chucking Reamers.— The rose type of reamer is used for enlarging cored or other holes. The cutting edges at the end are ground to a 45-degree bevel. This type of reamer will remove considerable metal in one cut. The cylindrical part of the reamer has no cutting edges, but merely grooves cut for the full length of the reamer body, providing a way for the chips to escape and a channel for lubricant to reach the cutting edges. There is no relief on the cylindrical surface of the body part, but it is slightly back-tapered so that the diameter at the point with the beveled cutting edges is slightly larger than the diameter farther back. The back-taper should not exceed 0.001 inch per inch. This form of reamer usually produces holes slightly larger than its size and it is, therefore, always made from 0.005 to 0.010 inch smaller than its nominal size, so that it may be followed by a fluted reamer for finishing. The grooves on the cylindrical portion are cut by a convex cutter having a width equal to from one-fifth to one-fourth the diameter of the rose reamer itself. The depth of the groove should be from one-eighth to one-sixth the diameter of the reamer. The teeth at the end of the reamer are milled with a 75-degree angular cutter; the width of the land of the cutting edge should be about one-fifth the distance from tooth to tooth. If an angular cutter is preferred to a convex cutter for milling the grooves on the cylindrical portion, because of the higher cutting speed possible when milling, an 80-degree angular cutter slightly rounded at the point may be used.

Cutters for Fluting Rose Chucking Reamers.— The cutters used for fluting rose chucking reamers on the end are 80-degree angular cutters for 1/4- and 5/16-inch diameter reamers; 75-degree angular cutters for 3/8- and 7/16-inch reamers; and 70-degree angular cutters for all larger sizes. The grooves on the cylindrical portion are milled with convex cutters of approximately the following sizes for given diameters of reamers: 5/32-inch convex cutter

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions of Formed Reamer Fluting Cutters



The making and maintenance of cutters of the formed type involves greater expense than the use of angular cutters of which dimensions are given on the previous page; but the form of flute produced by the formed type of cutter is preferred by many reamer users. The claims made for the formed type of flute are that the chips can be more readily removed from the reamer, and that the reamer has greater strength and is less likely to crack or spring out of shape in hardening.

Reamer Size	No. of Teeth in Reamer	Cutter Dia. *D*	Cutter Width *A*	Hole Dia. *B*	Bearing Width *C*	Bevel Length *E*	Radius *F*	Radius *F*	Tooth Depth *H*	No. of Cutter Teeth
1/8–3/16	6	1 3/4	3/16	7/8	…	0.125	0.016	7/32	0.21	14
1/4–5/16	6	1 3/4	1/4	7/8	…	0.152	0.022	9/32	0.25	13
3/8–7/16	6	1 7/8	3/8	7/8	1/8	0.178	0.029	1/2	0.28	12
1/2–11/16	6–8	2	7/16	7/8	1/8	0.205	0.036	9/16	0.30	12
3/4–1	8	2 1/8	1/2	7/8	5/32	0.232	0.042	11/16	0.32	12
1 1/16–1 1/2	10	2 1/4	9/16	7/8	5/32	0.258	0.049	3/4	0.38	11
1 9/16–2 1/8	12	2 3/8	5/8	7/8	3/16	0.285	0.056	27/32	0.40	11
2 1/4–3	14	2 5/8	11/16	7/8	3/16	0.312	0.062	7/8	0.44	10

for 1/2-inch reamers; 5/16-inch cutter for 1-inch reamers; 3/8-inch cutter for 1 1/2-inch reamers; 13/32-inch cutters for 2-inch reamers; and 15/32-inch cutters for 2 1/2-inch reamers. The smaller sizes of reamers, from 1/4 to 3/8 inch in diameter, are often milled with regular double-angle reamer fluting cutters having a radius of 1/64 inch for 1/4-inch reamer, and 1/32 inch for 5/16- and 3/8-inch sizes.

Reamer Terms and Definitions.— *Reamer:* A rotary cutting tool with one or more cutting elements used for enlarging to size and contour a previously formed hole. Its principal support during the cutting action is obtained from the workpiece. (See Fig. 1.)

Actual Size: The actual measured diameter of a reamer, usually slightly larger than the nominal size to allow for wear.

Angle Of Taper: The included angle of taper on a taper tool or taper shank.

Arbor Hole: The central mounting hole in a shell reamer.

Axis: the imaginary straight line which forms the longitudinal centerline of a reamer, usually established by rotating the reamer between centers.

Back Taper: A slight decrease in diameter, from front to back, in the flute length of reamers.

Bevel: An unrelieved angular surface of revolution (not to be confused with chamfer).

Body: The fluted full diameter portion of a reamer, inclusive of the chamfer, starting taper, and bevel.

Chamfer: The angular cutting portion at the entering end of a reamer (see also *Secondary Chamfer*).

Copyright 2004, Industrial Press, Inc., New York, NY

Vertical Adjustment of Tooth-rest for Grinding Clearance on Reamers

Size of Reamer	Hand Reamer for Steel. Cutting Clearance Land 0.006 inch Wide		Hand Reamer for Cast Iron and Bronze. Cutting Clearance Land 0.025 inch Wide		Chucking Reamer for Cast Iron and Bronze. Cutting Clearance Land 0.025 inch Wide		Rose Chucking Reamers for Steel
	For Cutting Clearance	For Second Clearance	For Cutting Clearance	For Second Clearance	For Cutting Clearance	For Second Clearance	For Cutting Clearance on Angular Edge at End
½	0.012	0.052	0.032	0.072	0.040	0.080	0.080
⅝	0.012	0.062	0.032	0.072	0.040	0.090	0.090
¾	0.012	0.072	0.035	0.095	0.040	0.100	0.100
⅞	0.012	0.082	0.040	0.120	0.045	0.125	0.125
1	0.012	0.092	0.040	0.120	0.045	0.125	0.125
1⅛	0.012	0.102	0.040	0.120	0.045	0.125	0.125
1¼	0.012	0.112	0.045	0.145	0.050	0.160	0.160
1⅜	0.012	0.122	0.045	0.145	0.050	0.160	0.175
1½	0.012	0.132	0.048	0.168	0.055	0.175	0.175
1⅝	0.012	0.142	0.050	0.170	0.060	0.200	0.200
1¾	0.012	0.152	0.052	0.192	0.060	0.200	0.200
1⅞	0.012	0.162	0.056	0.196	0.060	0.200	0.200
2	0.012	0.172	0.056	0.216	0.064	0.224	0.225
2⅛	0.012	0.172	0.059	0.219	0.064	0.224	0.225
2¼	0.012	0.172	0.063	0.223	0.064	0.224	0.225
2⅜	0.012	0.172	0.063	0.223	0.068	0.228	0.230
2½	0.012	0.172	0.065	0.225	0.072	0.232	0.230
2⅝	0.012	0.172	0.065	0.225	0.075	0.235	0.235
2¾	0.012	0.172	0.065	0.225	0.077	0.237	0.240
2⅞	0.012	0.172	0.070	0.230	0.080	0.240	0.240
3	0.012	0.172	0.072	0.232	0.080	0.240	0.240
3⅛	0.012	0.172	0.075	0.235	0.083	0.240	0.240
3¼	0.012	0.172	0.078	0.238	0.083	0.243	0.245
3⅜	0.012	0.172	0.081	0.241	0.087	0.247	0.245
3½	0.012	0.172	0.084	0.244	0.090	0.250	0.250
3⅝	0.012	0.172	0.087	0.247	0.093	0.253	0.250
3¾	0.012	0.172	0.090	0.250	0.097	0.257	0.255
3⅞	0.012	0.172	0.093	0.253	0.100	0.260	0.255
4	0.012	0.172	0.096	0.256	0.104	0.264	0.260
4⅛	0.012	0.172	0.096	0.256	0.104	0.264	0.260
4¼	0.012	0.172	0.096	0.256	0.106	0.266	0.265
4⅜	0.012	0.172	0.096	0.256	0.108	0.268	0.265
4½	0.012	0.172	0.100	0.260	0.108	0.268	0.265
4⅝	0.012	0.172	0.100	0.260	0.110	0.270	0.270
4¾	0.012	0.172	0.104	0.264	0.114	0.274	0.275
4⅞	0.012	0.172	0.106	0.266	0.116	0.276	0.275
5	0.012	0.172	0.110	0.270	0.118	0.278	0.275

Chamfer Angle: The angle between the axis and the cutting edge of the chamfer measured in an axial plane at the cutting edge.

Chamfer Length: The length of the chamfer measured parallel to the axis at the cutting edge.

Chamfer Relief Angle: See under *Relief*.

Chamfer Relief: See under *Relief*.

Chip Breakers: Notches or grooves in the cutting edges of some taper reamers designed. to break the continuity of the chips.

Circular Land: See preferred term *Margin*.

Copyright 2004, Industrial Press, Inc., New York, NY

Illustration of Terms Applying to Reamers



Hand Reamer Machine Reamer



Hand Reamer, Pilot and Guide



Chucking Reamer, Straight and Taper Shank

Clearance: The space created by the relief behind the cutting edge or margin of a reamer.

Core: The central portion of a reamer below the flutes which joins the lands.

Core Diameter: The diameter at a given point along the axis of the largest circle which does not project into the flutes.

Cutter Sweep: The section removed by the milling cutter or grinding wheel in entering or leaving a flute.

Cutting Edge: The leading edge of the relieved land in the direction of rotation for cutting.

Cutting Face: The leading side of the relieved land in the direction of rotation for cutting on which the chip impinges.

External Center: The pointed end of a reamer. The included angle varies with manufacturing practice.

Flutes: Longitudinal channels formed in the body of the reamer to provide cutting edges, permit passage of chips, and allow cutting fluid to reach the cutting edges.

Angular Flute: A flute which forms a cutting face lying in a plane intersecting the reamer axis at an angle. It is unlike a helical flute in that it forms a cutting face which lies in a single plane.

Helical Flute: Sometimes called spiral flute, a flute which is formed in a helical path around the axis of a reamer.

Spiral flute: 1) On a taper reamer, a flute of constant lead; or, 2) in reference to a straight reamer, see preferred term helical flute.

Straight Flute: A flute which forms a cutting edge lying in an axial plane.

Flute Length: The length of the flutes not including the cutter sweep.

Copyright 2004, Industrial Press, Inc., New York, NY

Guide: A cylindrical portion following the flutes of a reamer to maintain alignment.

Heel: The trailing edge of the land in the direction of rotation for cutting.

Helix Angle: The angle which a helical cutting edge at a given point makes with an axial plane through the same point.

Hook: A concave condition of a cutting face. The rake of a hooked cutting face must be determined at a given point.

Internal Center: A 60 degree countersink with clearance at the bottom, in one or both ends of a tool, which establishes the tool axis.

Irregular Spacing: A deliberate variation from uniform spacing of the reamer cutting edges.

Land: The section of the reamer between adjacent flutes.

Land Width: The distance between the leading edge of the land and the heel measured at a right angle to the leading edge.

Lead of Flute: The axial advance of a helical or spiral cutting edge in one turn around the reamer axis.

Length: The dimension of any reamer element measured parallel to the reamer axis.

Limits: The maximum and minimum values designated for a specific element.

Margin: The unrelieved part of the periphery of the land adjacent to the cutting edge.

Margin Width: The distance between the cutting edge and the primary relief measured at a right angle to the cutting edge.

Neck: The section of reduced diameter connecting shank to body, or connecting other portions of the reamer.

Nominal Size: The designated basic size of a reamer overall length–the extreme length of the complete reamer from end to end, but not including external centers or expansion screws.

Periphery: The outside circumference of a reamer.

Pilot: A cylindrical portion preceding the entering end of the reamer body to maintain alignment.

Rake: The angular relationship between the cutting face, or a tangent to the cutting face at a given point and a given reference plane or line.

Axial Rake: Applies to angular (not helical or spiral) cutting faces. It is the angle between a plane containing the cutting face, or tangent to the cutting face at a given point, and the reamer axis.

Helical Rake: Applies only to helical and spiral cutting faces (not angular). It is the angle between a plane, tangent to the cutting face at a given point on the cutting edge, and the reamer axis.

Negative Rake: Describes a cutting face in rotation whose cutting edge lags the surface of the cutting face.

Positive Rake: Describes a cutting face in rotation whose cutting edge leads the surface of the cutting face.

Radial Rake Angle: The angle in a transverse plane between a straight cutting face and a radial line passing through the cutting edge.

Relief: The result of the removal of tool material behind or adjacent to the cutting edge to provide clearance and prevent rubbing (heel drag).

Axial Relief: The relief measured in the axial direction between a plane perpendicular to the axis and the relieved surface. It can be measured by the amount of indicator drop at a given radius in a given amount of angular rotation.

Cam Relief : The relief from the cutting edge to the heel of the land produced by a cam action.

Chamfer Relief Angle: The axial relief angle at the outer corner of the chamfer. It is measured by projection into a plane tangent to the periphery at the outer corner of the chamfer.

Chamfer Relief: The axial relief on the chamfer of the reamer.

Eccentric Relief: A convex relieved surface behind the cutting edge.

Copyright 2004, Industrial Press, Inc., New York, NY

Flat Relief: A relieved surface behind the cutting edge which is essentially flat.

Radial Relief: Relief in a radial direction measured in the plane of rotation. It can be measured by the amount of indicator drop at a given radius in a given amount of angular rotation.

Primary Relief: The relief immediately behind the cutting edge or margin. Properly called relief.

Secondary Relief: An additional relief behind the primary relief.

Relief Angle: The angle, measured in a transverse plane, between the relieved surface and a plane tangent to the periphery at the cutting edge.

Secondary Chamfer: A slight relieved chamfer adjacent to and following the initial chamfer on a reamer.

Shank: The portion of the reamer by which it is held and driven.

Squared Shank: A cylindrical shank having a driving square on the back end.

Starting Radius: A relieved radius at the entering end of a reamer in place of a chamfer.

Starting Taper: A slight relieved taper on the front end of a reamer.

Straight Shank: A cylindrical shank.

Tang: The flatted end of a taper shank which fits a slot in the socket.

Taper per Foot: The difference in diameter between two points 12 in. apart measured along the axis.

Taper Shank: A shank made to fit a specific (conical) taper socket.

Direction of Rotation and Helix.— The terms "right hand" and "left hand" are used to describe both direction of rotation and direction of flute helix or reamers.

Hand of Rotation (or Hand of Cut): Right-hand Rotation (or Right-hand Cut): When viewed from the cutting end, the reamer must revolve counterclockwise to cut

Left-hand Rotation (or Left-hand Cut): When viewed from the cutting end, the reamer must revolve clockwise to cut

Hand of Flute Helix: Right-hand Helix: When the flutes twist away from the observer in a clockwise direction when viewed from either end of the reamer.

Left-hand helix: When the flutes twist away from the observer in a counterclockwise direction when viewed from either end of the reamer. The standard reamers on the tables that follow are all right-hand rotation.

Dimensions of Centers for Reamers and Arbors



Arbor. Dia. *A*	Large Center Dia. *B*	Drill No. *C*	Hole Depth *D*
1/4	1/8	55	5/32
5/16	5/32	52	3/16
3/8	3/16	48	7/32
7/16	7/32	43	1/4
1/2	1/4	39	5/16
9/16	9/32	33	11/32
5/8	5/16	30	3/8
11/16	11/32	29	13/32

Arbor Dia. *A*	Large Center Dia. *B*	Drill No. *C*	Hole Depth *D*	Arbor Dia. *A*	Large Center Dia. *B*	Drill No. *C*	Hole Depth *D*
3/4	3/8	25	7/16	2 1/2	1 11/16	J	27/32
13/16	13/32	20	1/2	2 5/8	45/64	K	7/8
7/8	7/16	17	17/32	2 3/4	23/32	L	29/32
15/16	15/32	12	9/16	2 7/8	47/64	M	29/32
1	1/2	8	19/32	3	3/4	N	15/16
1 1/8	33/64	5	5/8	3 1/8	49/64	N	31/32
1 1/4	17/32	3	21/32	3 1/4	25/32	O	31/32
1 3/8	35/64	2	21/32	3 3/8	51/64	O	1
1 1/2	9/16	1	11/16	3 1/2	13/16	P	1
…	…	Letter	…	3 5/8	53/64	Q	1 1/16
1 5/8	37/64	A	23/32	3 3/4	27/32	R	1 1/16
1 3/4	19/32	B	23/32	3 7/8	55/64	R	1 1/16
1 7/8	39/64	C	3/4	4	7/8	S	1 1/8
2	5/8	E	3/4	4 1/4	29/32	T	1 1/8
2 1/8	41/64	F	25/32	4 1/2	15/16	V	1 3/16
2 1/4	21/32	G	13/16	4 3/4	31/32	W	1 1/4
2 3/8	43/64	H	27/32	5	1	X	1 1/4

Copyright 2004, Industrial Press, Inc., New York, NY

Straight Shank Center Reamers and Machine Countersinks
ANSI B94.2-1983 (R1988)





Center Reamers (Short Countersinks)				Machine Countersinks			
Dia. of Cut	Approx. Length Overall, *A*	Length of Shank, *S*	Dia. of Shank, *D*	Dia. of Cut	Approx. Length Overall, *A*	Length of Shank, *S*	Dia. of Shank, *D*
1/4	1 1/2	3/4	3/16	1/2	3 7/8	2 1/4	1/2
3/8	1 3/4	7/8	1/4	5/8	4	2 1/4	1/2
1/2	2	1	3/8	3/4	4 1/8	2 1/4	1/2
5/8	2 1/4	1	3/8	7/8	4 1/4	2 1/4	1/2
3/4	2 5/8	1 1/4	1/2	1	4 3/8	2 1/4	1/2

All dimensions are given in inches. Material is high-speed steel. Reamers and countersinks have 3 or 4 flutes. Center reamers are standard with 60, 82, 90, or 100 degrees included angle. Machine countersinks are standard with either 60 or 82 degrees included angle.

Tolerances: On overall length *A*, the tolerance is ±1/8 inch for center reamers in a size range of from 1/4 to 3/8 inch, incl., and machine countersinks in a size range of from 1/2 to 5/8 inch. incl.; ± 3/16 inch for center reamers, 1/2 to 3/4 inch, incl.; and machine countersinks, 3/4 to 1 inch, incl. On shank diameter *D*, the tolerance is –0.0005 to –0.002 inch. On shank length *S*, the tolerance is ±1/16 inch.

Reamer Difficulties.— Certain frequently occurring problems in reaming require remedial measures. These difficulties include the production of oversize holes, bellmouth holes, and holes with a poor finish. The following is taken from suggestions for correction of these difficulties by the National Twist Drill and Tool Co. and Winter Brothers Co.*

Oversize Holes: The cutting of a hole oversize from the start of the reaming operations usually indicates a mechanical defect in the setup or reamer. Thus, the wrong reamer for the workpiece material may have been used or there may be inadequate workpiece support, inadequate or worn guide bushings, or misalignment of the spindles, bushings, or workpiece or runout of the spindle or reamer holder. The reamer itself may be defective due to chamfer runout or runout of the cutting end due to a bent or nonconcentric shank.

When reamers gradually start to cut oversize, it is due to pickup or galling, principally on the reamer margins. This condition is partly due to the workpiece material. Mild steels, certain cast irons, and some aluminum alloys are particularly troublesome in this respect.

Corrective measures include reducing the reamer margin widths to about 0.005 to 0.010 inch, use of hard case surface treatments on high-speed-steel reamers, either alone or in combination with black oxide treatments, and the use of a high-grade finish on the reamer faces, margins, and chamfer relief surfaces.

Bellmouth Holes: The cutting of a hole that becomes oversize at the entry end with the oversize decreasing gradually along its length always reflects misalignment of the cutting portion of the reamer with respect to the hole. The obvious solution is to provide improved guiding of the reamer by the use of accurate bushings and pilot surfaces. If this solution is not feasible, and the reamer is cutting in a vertical position, a flexible element may be employed to hold the reamer in such a way that it has both radial and axial float, with the hope that the reamer will follow the original hole and prevent the bellmouth condition.

In horizontal setups where the reamer is held fixed and the workpiece rotated, any misalignment exerts a sideways force on the reamer as it is fed to depth, resulting in the forma-

* "Some Aspects of Reamer Design and Operation," *Metal Cuttings,* April 1963.

Copyright 2004, Industrial Press, Inc., New York, NY

tion of a tapered hole. This type of bellmouthing can frequently be reduced by shortening the bearing length of the cutting portion of the reamer. One way to do this is to reduce the reamer diameter by 0.010 to 0.030 inch, depending on size and length, behind a short full-diameter section, ⅛ to ½ inch long according to length and size, following the chamfer. The second method is to grind a high back taper, 0.008 to 0.015 inch per inch, behind the short full-diameter section. Either of these modifications reduces the length of the reamer tooth that can cause the bellmouth condition.

Poor Finish: The most obvious step toward producing a good finish is to reduce the reamer feed per revolution. Feeds as low as 0.0002 to 0.0005 inch per tooth have been used successfully. However, reamer life will be better if the maximum feasible feed is used.

The minimum practical amount of reaming stock allowance will often improve finish by reducing the volume of chips and the resulting heat generated on the cutting portion of the chamfer. Too little reamer stock, however, can be troublesome in that the reamer teeth may not cut freely but will deflect or push the work material out of the way. When this happens, excessive heat, poor finish, and rapid reamer wear can occur.

Because of their superior abrasion resistance, carbide reamers are often used when fine finishes are required. When properly conditioned, carbide reamers can produce a large number of good-quality holes. Careful honing of the carbide reamer edges is very important.

American National Standard Fluted Taper Shank Chucking Reamers—Straight and Helical Flutes, Fractional Sizes *ANSI B94.2-1983 (R1988)*



Reamer Dia.	Length Overall *A*	Flute Length *B*	No. of Morse Taper Shank[a]	No. of Flutes	Reamer Dia.	Length Overall *A*	Flute Length *B*	No. of Morse Taper Shank[a]	No. of Flutes
¼	6	1½	1	4 to 6	27/32	9½	2½	2	8 to 10
5/16	6	1½	1	4 to 6	⅞	10	2⅝	2	8 to 10
⅜	7	1¾	1	4 to 6	29/32	10	2⅝	2	8 to 10
7/16	7	1¾	1	6 to 8	15/16	10	2⅝	3	8 to 10
½	8	2	1	6 to 8	31/32	10	2⅝	3	8 to 10
17/32	8	2	1	6 to 8	1	10½	2¾	3	8 to 12
9/16	8	2	1	6 to 8	1 1/16	10½	2¾	3	8 to 12
19/32	8	2	1	6 to 8	1⅛	11	2⅞	3	8 to 12
5/8	9	2¼	2	6 to 8	1 3/16	11	2⅞	3	8 to 12
21/32	9	2¼	2	6 to 8	1 ¼	11 ½	3	4	8 to 12
11/16	9	2¼	2	6 to 8	1 5/16	11½	3	4	8 to 12
23/32	9	2¼	2	6 to 8	1⅜	12	3¼	4	10 to 12
¾	9½	2½	2	6 to 8	1 7/16	12	3¼	4	10 to 12
25/32	9½	2½	2	8 to 10	1½	12½	3½	4	10 to 12
13/16	9½	2½	2	8 to 10	…	…	…	…	…

[a] American National Standard self-holding tapers (see Table 7a on page 933.)

All dimensions are given in inches. Material is high-speed steel.

Helical flute reamers with right-hand helical flutes are standard.

Tolerances: On reamer diameter, ¼-inch size, +.0001 to +.0004 inch; over ¼- to 1-inch size, +.0001 to +.0005 inch; over 1-inch size, +.0002 to +.0006 inch. On length overall *A* and flute length *B*, ¼- to 1-inch size, incl., ±1/16 inch; 1 1/16- to 1½-inch size, incl., 3/32 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Expansion Chucking Reamers—Straight and Taper Shanks

ANSI B94.2-1983 (R1988)



Dia of Reamer	Length, A	Flute Length, B	Shank Dia., D		Dia. of Reamer	Length, A	Flute Length, B	Shank Dia., D	
			Max.	Min.				Max.	Min.
3/8	7	3/4	0.3105	0.3095	1 3/32	10 1/2	1 5/8	0.8745	0.8730
13/32	7	3/4	0.3105	0.3095	1 1/8	11	1 3/4	0.8745	0.8730
7/16	7	7/8	0.3730	0.3720	1 5/32	11	1 3/4	0.8745	0.8730
15/32	7	7/8	0.3730	0.3720	1 3/16	11	1 3/4	0.9995	0.9980
1/2	8	1	0.4355	0.4345	1 7/32	11	1 3/4	0.9995	0.9980
17/32	8	1	0.4355	0.4345	1 1/4	11 1/2	1 7/8	0.9995	0.9980
9/16	8	1 1/8	0.4355	0.4345	1 5/16	11 1/2	1 7/8	0.9995	0.9980
19/32	8	1 1/8	0.4355	0.4345	1 3/8	12	2	0.9995	0.9980
5/8	9	1 1/4	0.5620	0.5605	1 7/16	12	2	1.2495	1.2480
21/32	9	1 1/4	0.5620	0.5605	1 1/2	12 1/2	2 1/8	1.2495	1.2480
11/16	9	1 1/4	0.5620	0.5605	1 9/16 [a]	12 1/2	2 1/8	1.2495	1.2480
23/32	9	1 1/4	0.5620	0.5605	1 5/8	13	2 1/4	1.2495	1.2480
3/4	9 1/2	1 3/8	0.6245	0.6230	1 11/16 [a]	13	2 1/4	1.2495	1.2480
25/32	9 1/2	1 3/8	0.6245	0.6230	1 3/4	13 1/2	2 3/8	1.2495	1.2480
13/16	9 1/2	1 3/8	0.6245	0.6230	1 13/16 [a]	13 1/2	2 3/8	1.4995	1.4980
27/32	9 1/2	1 3/8	0.6245	0.6230	1 7/8	14	2 1/2	1.4995	1.4980
7/8	10	1 1/2	0.7495	0.7480	1 15/16 [a]	14	2 1/2	1.4995	1.4980
29/32	10	1 1/2	0.7495	0.7480	2	14	2 1/2	1.4995	1.4980
15/16	10	1 1/2	0.7495	0.7480	2 1/8 [b]	14 1/2	2 3/4	…	…
31/32	10	1 1/2	0.7495	0.7480	2 1/4 [b]	14 1/2	2 3/4	…	…
1	10 1/2	1 5/8	0.8745	0.8730	2 3/8 [b]	15	3	…	…
1 1/32	10 1/2	1 5/8	0.8745	0.8730	2 1/2 [b]	15	3	…	…
1 1/16	10 1/2	1 5/8	0.8745	0.8730	…	…	…	…	…

[a] Straight shank only.

[b] Taper shank only.

All dimensions in inches. Material is high-speed steel. The number of flutes is as follows: 3/8- to 15/32-inch sizes, 4 to 6; 1/2- to 31/32-inch sizes, 6 to 8; 1- to 1 11/16-inch sizes, 8 to 10; 1 3/4- to 1 15/16-inch sizes, 8 to 12; 2 - to 2 1/4-inch sizes, 10 to 12; 2 3/8- and 2 1/2-inch sizes, 10 to 14. The expansion feature of these reamers provides a means of adjustment that is important in reaming holes to close tolerances. When worn undersize, they may be expanded and reground to the original size.

Tolerances: On reamer diameter, 8/8- to 1-inch sizes, incl., +0.0001 to +0.0005 inch; over 1-inch size, + 0.0002 to + 0.0006 inch. On length *A* and flute length *B*, 3/8- to 1-inch sizes, incl., ±1/16 inch; 1 1/32- to 2-inch sizes, incl., ±3/32 inch; over 2-inch sizes, ±1/8 inch.

Taper is Morse taper: No. 1 for sizes 3/8 to 19/32 inch, incl.; No. 2 for sizes 5/8 to 29/32 incl.; No. 3 for sizes 15/16 to 1 7/32, incl.; No. 4 for sizes 1 1/4 to 1 5/8, incl.; and No. 5 for sizes 1 3/4 to 2 1/2, incl. For amount of taper, see Table 1b on page 928.

Copyright 2004, Industrial Press, Inc., New York, NY

Hand Reamers—Straight and Helical Flutes *ANSI B94.2-1983 (R1988)*



Reamer Diameter			Length Overall *A*	Flute Length *B*	Square Length *C*	Size of Square	No. of Flutes
Straight Flutes	Helical Flutes	Decimal Equivalent					
1/8	…	0.1250	3	1 1/2	5/32	0.095	4 to 6
5/32	…	0.1562	3 1/4	1 5/8	7/32	0.115	4 to 6
3/16	…	0.1875	3 1/2	1 3/4	7/32	0.140	4 to 6
7/32	…	0.2188	3 3/4	1 7/8	1/4	0.165	4 to 6
1/4	1/4	0.2500	4	2	1/4	0.185	4 to 6
9/32	…	0.2812	4 1/4	2 1/8	1/4	0.210	4 to 6
5/16	5/16	0.3125	4 1/2	2 1/4	5/16	0.235	4 to 6
11/32	…	0.3438	4 3/4	2 3/8	5/16	0.255	4 to 6
3/8	3/8	0.3750	5	2 1/2	3/8	0.280	4 to 6
13/32	…	0.4062	5 1/4	2 5/8	3/8	0.305	6 to 8
7/16	7/16	0.4375	5 1/2	2 3/4	7/16	0.330	6 to 8
15/32	…	0.4688	5 3/4	2 7/8	7/16	0.350	6 to 8
1/2	1/2	0.5000	6	3	1/2	0.375	6 to 8
17/32	…	0.5312	6 1/4	3 1/8	1/2	0.400	6 to 8
9/16	9/16	0.5625	6 1/2	3 1/4	9/16	0.420	6 to 8
19/32	…	0.5938	6 3/4	3 3/8	9/16	0.445	6 to 8
5/8	5/8	0.6250	7	3 1/2	5/8	0.470	6 to 8
21/32	…	0.6562	7 3/8	3 11/16	5/8	0.490	6 to 8
11/16	11/16	0.6875	7 3/4	3 7/8	11/16	0.515	6 to 8
23/32	…	0.7188	8 1/8	4 1/16	11/16	0.540	6 to 8
3/4	3/4	0.7500	8 3/8	4 3/16	3/4	0.560	6 to 8
…	13/16	0.8125	9 1/8	4 9/16	13/16	0.610	8 to 10
7/8	7/8	0.8750	9 3/4	4 7/8	7/8	0.655	8 to 10
…	15/16	0.9375	10 1/4	5 1/8	15/16	0.705	8 to 10
1	1	1.0000	10 7/8	5 7/16	1	0.750	8 to 10
1 1/8	1 1/8	1.1250	11 5/8	5 13/16	1	0.845	8 to 10
1 1/4	1 1/4	1.2500	12 1/4	6 1/8	1	0.935	8 to 12
1 3/8	1 3/8	1.3750	12 5/8	6 5/16	1	1.030	10 to 12
1 1/2	1 1/2	1.5000	13	6 1/2	1 1/8	1.125	10 to 14

All dimensions in inches. Material is high-speed steel. The nominal shank diameter *D* is the same as the reamer diameter. Helical-flute hand reamers with left-hand helical flutes are standard. Reamers are tapered slightly on the end to facilitate proper starting.

Tolerances: On diameter of reamer, up to 1/4-inch size, incl., + .0001 to + .0004 inch; over 1/4-to 1-inch size, incl., +.0001 to + .0005 inch; over 1-inch size, +.0002 to +.0006 inch. On length overall *A* and flute length *B*, 1/8- to 1-inch size, incl., ± 1/16 inch; 1 1/8- to 1 1/2-inch size, incl., ±3/32 inch. On length of square *C*, 1/8- to 1 inch size, incl., ±1/32 inch; 1 1/8-to 1 1/2-inch size, incl., ±1/16 inch. On shank diameter *D*, 1/8- to 1-inch size, incl., –.001 to –.005 inch; 1 1/8- to 1 1/2-inch size, incl., –.0015 to – .006 inch. On size of square, 1/8- to 1/2-inch size, incl., –.004 inch; 17/32- to 1-inch size, incl., –.006 inch; 1 1/8- to 1 1/2-inch size, incl., –.008 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Expansion Hand Reamers—Straight and Helical Flutes, Squared Shank *ANSI B94.2-1983 (R1988)*



Reamer Dia.	Length Overall *A* Max	Length Overall *A* Min	Flute Length *B* Max	Flute Length *B* Min	Length of Square *C*	Shank Dia. *D*	Size of Square	Number of Flutes
Straight Flutes								
1/4	4 3/8	3 3/4	1 3/4	1 1/2	1/4	1/4	0.185	6 to 8
5/16	4 3/8	4	1 7/8	1 1/2	5/16	5/16	0.235	6 to 8
3/8	5 3/8	4 1/4	2	1 3/4	3/8	3/8	0.280	6 to 9
7/16	5 3/8	4 1/2	2	1 3/4	7/16	7/16	0.330	6 to 9
1/2	6 1/2	5	2 1/2	1 3/4	1/2	1/2	0.375	6 to 9
9/16	6 1/2	5 3/8	2 1/2	1 7/8	9/16	9/16	0.420	6 to 9
5/8	7	5 3/4	3	2 1/4	5/8	5/8	0.470	6 to 9
11/16	7 5/8	6 1/4	3	2 1/2	11/16	11/16	0.515	6 to 10
3/4	8	6 1/2	3 1/2	2 5/8	3/4	3/4	0.560	6 to 10
7/8	9	7 1/2	4	3 1/8	7/8	7/8	0.655	8 to 10
1	10	8 3/8	4 1/2	3 1/8	1	1	0.750	8 to 10
1 1/8	10 1/2	9	4 3/4	3 1/2	1	1 1/8	0.845	8 to 12
1 1/4	11	9 3/4	5	4 1/4	1	1 1/4	0.935	8 to 12
Helical Flutes								
1/4	4 3/8	3 7/8	1 3/4	1 1/2	1/4	1/4	0.185	6 to 8
5/16	4 3/8	4	1 3/4	1 1/2	5/16	5/16	0.235	6 to 8
3/8	6 1/8	4 1/4	2	1 3/4	3/8	3/8	0.280	6 to 9
7/16	6 1/4	4 1/2	2	1 3/4	7/16	7/16	0.330	6 to 9
1/2	6 1/2	5	2 1/2	1 3/4	1/2	1/2	0.375	6 to 9
5/8	8	6	3	2 1/4	5/8	5/8	0.470	6 to 9
3/4	8 5/8	6 1/2	3 1/2	2 5/8	3/4	3/4	0.560	6 to 10
7/8	9 3/8	7 1/2	4	3 1/8	7/8	7/8	0.655	6 to 10
1	10 1/4	8 3/8	4 1/2	3 1/8	1	1	0.750	6 to 10
1 1/4	11 3/8	9 3/4	5	4 1/4	1	1 1/4	0.935	8 to 12

All dimensions are given in inches. Material is carbon steel. Reamers with helical flutes that are left hand are standard. Expansion hand reamers are primarily designed for work where it is necessary to enlarge reamed holes by a few thousandths. The pilots and guides on these reamers are ground undersize for clearance. The maximum expansion on these reamers is as follows: .006 inch for the 1/4- to 7/16-inch sizes. .010 inch for the 1/2- to 7/8-inch sizes and .012 inch for the 1- to 1 1/4-inch sizes.

Tolerances: On length overall *A* and flute length *B*, ±1/16 inch for 1/4- to 1-inch sizes, ± 3/32 inch for 1 1/8- to 1 1/4-inch sizes; on length of square *C*, ±1/32 inch for 1/4- to 1-inch sizes, ± 1/16 inch for 1 1/8- to 1 1/4-inch sizes; on shank diameter *D* –.001 to –.005 inch for 1/4- to 1-inch sizes, –.0015 to –.006 inch for 1 1/8- to 1 1/4-inch sizes; on size of square, –.004 inch for 1/4- to 1/2-inch sizes. –.006 inch for 9/16- to 1-inch sizes, and –.008 inch for 1 1/8- to 1 1/4-inch sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Taper Shank Jobbers Reamers—Straight Flutes *ANSI B94.2-1983 (R1988)*



Reamer Diameter		Length Overall *A*	Length of Flute *B*	No. of Morse Taper Shank[a]	No. of Flutes
Fractional	Dec. Equiv.				
1/4	0.2500	5 3/16	2	1	6 to 8
5/16	0.3125	5 1/2	2 1/4	1	6 to 8
3/8	0.3750	5 13/16	2 1/2	1	6 to 8
7/16	0.4375	6 1/8	2 3/4	1	6 to 8
1/2	0.5000	6 7/16	3	1	6 to 8
9/16	0.5625	6 3/4	3 1/4	1	6 to 8
5/8	0.6250	7 9/16	3 1/2	2	6 to 8
11/16	0.6875	8	3 7/8	2	8 to 10
3/4	0.7500	8 3/8	4 3/16	2	8 to 10
13/16	0.8125	8 13/16	4 9/16	2	8 to 10
7/8	0.8750	9 3/16	4 7/8	2	8 to 10
15/16	0.9375	10	5 1/8	3	8 to 10
1	1.0000	10 3/8	5 7/16	3	8 to 10
1 1/16	1.0625	10 5/8	5 5/8	3	8 to 10
1 1/8	1.1250	10 7/8	5 13/16	3	8 to 10
1 3/16	1.1875	11 1/8	6	3	8 to 12
1 1/4	1.2500	12 9/16	6 1/8	4	8 to 12
1 3/8	1.3750	12 13/16	6 5/16	4	10 to 12
1 1/2	1.5000	13 1/8	6 1/2	4	10 to 12

[a] American National Standard self-holding tapers (Table 7a on page 933.)

All dimensions in inches. Material is high-speed steel.

Tolerances: On reamer diameter, 1/4-inch size, +.0001 to +.0004 inch; over 1/4- to 1-inch size, incl., +.0001 to +.0005 inch; over 1-inch size, +.0002 to +.0006 inch. On overall length *A* and length of flute *B*, 1/4- to 1-inch size, incl., ±1/16 inch; and 1 1/16- to 1 1/2-inch size, incl., ±3/32 inch.

American National Standard Driving Slots and Lugs for Shell Reamers or Shell Reamer Arbors *ANSI B94.2-1983 (R1988)*



Arbor Size No.	Fitting Reamer Sizes	Driving Slot		Lug on Arbor		Reamer Hole Dia. at Large End
		Width *W*	Depth *J*	Width *L*	Depth *M*	
4	3/4	5/32	3/16	9/64	5/32	0.375
5	13/16 to 1	3/16	1/4	11/64	7/32	0.500
6	1 1/16 to 1 1/4	3/16	1/4	11/64	7/32	0.625
7	1 5/16 to 1 5/8	1/4	5/16	15/64	9/32	0.750
8	1 11/16 to 2	1/4	5/16	15/64	9/32	1.000
9	2 1/16 to 2 1/2	5/16	3/8	19/64	11/32	1.250

All dimension are given in inches. The hole in shell reamers has a taper of 1/8 inch per foot, with arbors tapered to correspond. Shell reamer arbor tapers are made to permit a driving fit with the reamer.

Copyright 2004, Industrial Press, Inc., New York, NY

Straight Shank Chucking Reamers—Straight Flutes, Wire Gage Sizes

ANSI B94.2-1983 (R1988)



Reamer Diameter		Lgth. Overall *A*	Lgth. of Flute *B*	Shank Dia. *D*		No. of Flutes	Reamer Diameter		Lgth. Overall *A*	Lgth. of Flute *B*	Shank Dia. *D*		No. of Flutes
Wire Gage	Inch			Max	Min		Wire Gage	Inch			Max	Min	
60	.0400	2½	½	.0390	.0380	4	49	.0730	3	¾	.0660	.0650	4
59	.0410	2½	½	.0390	.0380	4	48	.0760	3	¾	.0720	.0710	4
58	.0420	2½	½	.0390	.0380	4	47	.0785	3	¾	.0720	.0710	4
57	.0430	2½	½	.0390	.0380	4	46	.0810	3	¾	.0771	.0701	4
56	.0465	2½	½	.0455	.0445	4	45	.0820	3	¾	.0771	.0761	4
55	.0520	2½	½	.0510	.0500	4	44	.0860	3	¾	.0810	.0800	4
54	.0550	2½	½	.0510	.0500	4	43	.0890	3	¾	.0810	.0800	4
53	.0595	2½	½	.0585	.0575	4	42	.0935	3	¾	.0880	.0870	4
52	.0635	2½	½	.0585	.0575	4	41	.0960	3½	⅞	.0928	.0918	4 to 6
51	.0670	3	¾	.0660	.0650	4	40	.0980	3½	⅞	.0928	.0918	4 to 6
50	.0700	3	¾	.0660	.0650	4	39	.0995	3½	⅞	.0928	.0918	4 to 6
38	.1015	3½	⅞	.0950	.0940	4 to 6	19	.1660	4½	1⅛	.1595	.1585	4 to 6
37	.1040	3½	⅞	.0950	.0940	4 to 6	18	.1695	4½	1⅛	.1595	.1585	4 to 6
36	.1065	3½	⅞	.1030	.1020	4 to 6	17	.1730	4½	1⅛	.1645	.1635	4 to 6
35	.1100	3½	⅞	.1030	.1020	4 to 6	16	.1770	4½	1¼	.1704	.1694	4 to 6
34	.1110	3½	⅞	.1055	.1045	4 to 6	15	.1800	4½	1⅛	.1755	.1745	4 to 6
33	.1130	3½	⅞	.1055	.1045	4 to 6	14	.1820	4½	1⅛	.1755	.1745	4 to 6
32	.1160	3½	⅞	.1120	.1110	4 to 6	13	.1850	4½	1⅛	.1805	.1795	4 to 6
31	.1200	3½	⅞	.1120	.1110	4 to 6	12	.1890	4½	1⅛	.1805	.1795	4 to 6
30	.1285	3½	⅞	.1190	.1180	4 to 6	11	.1910	5	1¼	.1860	.1850	4 to 6
29	.1360	4	1	.1275	.1265	4 to 6	10	.1935	5	1¼	.1860	.1850	4 to 6
28	.1405	4	1	.1350	.1340	4 to 6	9	.1960	5	1¼	.1895	.1885	4 to 6
27	.1440	4	1	.1350	.1340	4 to 6	8	.1990	5	1¼	.1895	.1885	4 to 6
26	.1470	4	1	.1430	.1420	4 to 6	7	.2010	5	1¼	.1945	.1935	4 to 6
25	.1495	4	1	.1430	.1420	4 to 6	6	.2040	5	1¼	.1945	.1935	4 to 6
24	.1520	4	1	.1460	.1450	4 to 6	5	.2055	5	1¼	.2016	.2006	4 to 6
23	.1540	4	1	.1460	.1450	4 to 6	4	.2090	5	1¼	.2016	.2006	4 to 6
22	.1570	4	1	.1510	.1500	4 to 6	3	.2130	5	1¼	.2075	.2065	4 to 6
21	.1590	4½	1⅛	.1530	.1520	4 to 6	2	2210	6	1½	.2173	.2163	4 to 6
20	.1610	4½	1⅛	.1530	.1520	4 to 6	1	.2280	6	1½	.2173	.2163	4 to 6

All dimensions in inches. Material is high-speed steel.

Tolerances: On diameter of reamer, plus .0001 to plus .0004 inch. On overall length *A*, plus or minus 1/16 inch. On length of flute *B*, plus or minus 1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Straight Shank Chucking Reamers—Straight Flutes, Letter Sizes

ANSI B94.2-1983 (R1988)



Reamer Diameter		Lgth. Over-all *A*	Lgth. of Flute *B*	Shank Dia. *D*		No. of Flutes	Reamer Diameter		Lgth. Over-all *A*	Lgth. of Flute *B*	Shank Dia. *D*		No. of Flutes
Letter	Inch			Max	Min		Letter	Inch			Max	Min	
A	0.2340	6	1½	0.2265	.2255	4 to 6	N	0.3020	6	1½	0.2792	0.2782	4 to 6
B	0.2380	6	1½	0.2329	.2319	4 to 6	O	0.3160	6	1½	0.2792	0.2782	4 to 6
C	0.2420	6	1½	0.2329	.2319	4 to 6	P	0.3230	6	1½	0.2792	0.2782	4 to 6
D	0.2460	6	1½	0.2329	.2319	4 to 6	Q	0.3320	6	1½	0.2792	0.2782	4 to 6
E	0.2500	6	1½	0.2405	.2395	4 to 6	R	0.3390	6	1½	0.2792	0.2782	4 to 6
F	0.2570	6	1½	0.2485	.2475	4 to 6	S	0.3480	7	1¾	0.3105	0.3095	4 to 6
G	0.2610	6	1½	0.2485	.2475	4 to 6	T	0.3580	7	1¾	0.3105	0.3095	4 to 6
H	0.2660	6	1½	0.2485	.2475	4 to 6	U	0.3680	7	1¾	0.3105	0.3095	4 to 6
I	0.2720	6	1½	0.2485	.2475	4 to 6	V	0.3770	7	1¾	0.3105	0.3095	4 to 6
J	0.2770	6	1½	0.2485	.2475	4 to 6	W	0.3860	7	1¾	0.3105	0.3095	4 to 6
K	0.2810	6	1½	0.2485	.2475	4 to 6	X	0.3970	7	1¾	0.3105	0.3095	4 to 6
L	0.2900	6	1½	0.2792	.2782	4 to 6	Y	0.4040	7	1¾	0.3105	0.3095	4 to 6
M	0.2950	6	1½	0.2792	.2782	4 to 6	Z	0.4130	7	1¾	0.3730	0.3720	6 to 8

All dimensions in inches. Material is high-speed steel.

Tolerances: On diameter of reamer, for sizes A to E, incl., plus .0001 to plus .0004 inch and for sizes F to Z, incl., plus .0001 to plus .0005 inch. On overall length *A*, plus or minus 1/16 inch. On length of flute *B*, plus or minus 1/16 inch.

Straight Shank Chucking Reamers— Straight Flutes, Decimal Sizes

ANSI B94.2-1983 (R1988)



Reamer Dia.	Lgth. Overall *A*	Lgth. of Flute *B*	Shank Diameter *D*		No. of Flutes	Reamer Dia.	Lgth. Overall *A*	Lgth. of Flute *B*	Shank Diameter *D*		No. of Flutes
			Max.	Min.					Max.	Min.	
0.1240	3½	7/8	0.1190	0.1180	4 to 6	0.3135	6	1½	0.2792	0.2782	4 to 6
0.1260	3½	7/8	0.1190	0.1180	4 to 6	0.3740	7	1¾	0.3105	0.3095	6 to 8
0.1865	4½	1⅛	0.1805	0.1795	4 to 6	0.3760	7	1¾	0.3105	0.3095	6 to 8
0.1885	4½	1⅛	0.1805	0.1795	4 to 6	0.4365	7	1¾	0.3730	0.3720	6 to 8
0.2490	6	1½	0.2405	0.2395	4 to 6	0.4385	7	1¾	0.3730	0.3720	6 to 8
0.2510	6	1½	0.2405	0.2395	4 to 6	0.4990	8	2	0.4355	0.4345	6 to 8
0.3115	6	1½	0.2792	0.2782	4 to 6	0.5010	8	2	0.4355	0.4345	6 to 8

All dimensions in inches. Material is high-speed steel.

Tolerances: On diameter of reamer, for 0.124 to 0.249-inch sizes, plus .0001 to plus .0004 inch and for 0.251 to 0.501-inch sizes, plus .0001 to plus .0005 inch. On overall length *A*, plus or minus 1/16 inch. On length of flute *B*, plus or minus 1/16 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Straight Shank Rose Chucking and Chucking Reamers—Straight and Helical Flutes, Fractional Sizes *ANSI B94.2-1983 (R1988)*



Reamer Diameter		Length	Flute	Shank Dia. *D*		No. of
Chucking	Rose Chucking	Overall *A*	Length *B*	Max	Min	Flutes
3/64 [a]	…	2 1/2	1/2	0.0455	0.0445	4
1/16	…	2 1/2	1/2	0.0585	0.0575	4
5/64	…	3	3/4	0.0720	0.0710	4
3/32	…	3	3/4	0.0880	0.0870	4
7/64	…	3 1/2	7/8	0.1030	0.1020	4 to 6
1/8	1/8 [a]	3 1/2	7/8	0.1190	0.1180	4 to 6
9/64	…	4	1	0.1350	0.1340	4 to 6
5/32	…	4	1	0.1510	0.1500	4 to 6
11/64	…	4 1/2	1 1/8	0.1645	0.1635	4 to 6
3/16	3/16 [a]	4 1/2	1 1/8	0.1805	0.1795	4 to 6
13/64	…	5	1 1/4	0.1945	0.1935	4 to 6
7/32	…	5	1 1/4	0.2075	0.2065	4 to 6
15/64	…	6	1 1/2	0.2265	0.2255	4 to 6
1/4	1/4 [a]	6	1 1/2	0.2405	0.2395	4 to 6
17/64	…	6	1 1/2	0.2485	0.2475	4 to 6
9/32	…	6	1 1/2	0.2485	0.2475	4 to 6
19/64	…	6	1 1/2	0.2792	0.2782	4 to 6
5/16	5/16 [a]	6	1 1/2	0.2792	0.2782	4 to 6
21/64	…	6	1 1/2	0.2792	0.2782	4 to 6
11/32	…	6	1 1/2	0.2792	0.2782	4 to 6
23/64	…	7	1 3/4	0.3105	0.3095	4 to 6
3/8	3/8 [a]	7	1 3/4	0.3105	0.3095	4 to 6
25/64	…	7	1 3/4	0.3105	0.3095	4 to 6
13/32	…	7	1 3/4	0.3105	0.3095	4 to 6
27/64	…	7	1 3/4	0.3730	0.3720	6 to 8
7/16	7/16 [a]	7	1 3/4	0.3730	0.3720	6 to 8
29/64	…	7	1 3/4	0.3730	0.3720	6 to 8
15/32	…	7	1 3/4	0.3730	0.3720	6 to 8
31/64	…	8	2	0.4355	0.4345	6 to 8
1/2	1/2 [a]	8	2	0.4355	0.4345	6 to 8
17/32	…	8	2	0.4355	0.4345	6 to 8
9/16	…	8	2	0.4355	0.4345	6 to 8
19/32	…	8	2	0.4355	0.4345	6 to 8
5/8	…	9	2 1/4	0.5620	0.5605	6 to 8
21/32	…	9	2 1/4	0.5620	0.5605	6 to 8
11/16	…	9	2 1/4	0.5620	0.5605	6 to 8
23/32	…	9	2 1/4	0.5620	0.5605	6 to 8
3/4	…	9 1/2	2 1/2	0.6245	0.6230	6 to 8
25/32	…	9 1/2	2 1/2	0.6245	0.6230	8 to 10
13/16	…	9 1/2	2 1/2	0.6245	0.6230	8 to 10
27/32	…	9 1/2	2 1/2	0.6245	0.6230	8 to 10
7/8	…	10	2 5/8	0.7495	0.7480	8 to 10
29/32	…	10	2 5/8	0.7495	0.7480	8 to 10
15/16	…	10	2 5/8	0.7495	0.7480	8 to 10
31/32	…	10	2 5/8	0.7495	0.7480	8 to 10
1	…	10 1/2	2 3/4	0.8745	0.8730	8 to 12
1 1/16	…	10 1/2	2 3/4	0.8745	0.8730	8 to 12
1 1/8	…	11	2 7/8	0.8745	0.8730	8 to 12
1 3/16	…	11	2 7/8	0.9995	0.9980	8 to 12
1 1/4	…	11 1/2	3	0.9995	0.9980	8 to 12
1 5/16 [b]	…	11 1/2	3	0.9995	0.9980	10 to 12
1 3/8	…	12	3 1/4	0.9995	0.9980	10 to 12
1 7/16 [b]	…	12	3 1/4	1.2495	1.2480	10 to 12
1 1/2	…	12 1/2	3 1/2	1.2495	1.2480	10 to 12

[a] Reamer with straight flutes is standard only.

Copyright 2004, Industrial Press, Inc., New York, NY

[b] Reamer with helical flutes is standard only.

All dimensions are given in inches. Material is high-speed steel. Chucking reamers are end cutting on the chamfer and the relief for the outside diameter is ground in back of the margin for the full length of land. Lands of rose chucking reamers are not relieved on the periphery but have a relatively large amount of back taper.

Tolerances: On reamer diameter, up to 1/4-inch size, incl., + .0001 to + .0004 inch; over 1/4-to 1-inch size, incl., + .0001 to + .0005 inch; over 1-inch size, + .0002 to + .0006 inch. On length overall *A* and flute length *B*, up to 1-inch size, incl., ±1/16 inch; 1 1/16- to 1 1/2-inch size, incl., ±3/32 inch.

Helical flutes are right- or left-hand helix, right-hand cut, except sizes 1 1/16 through 1 1/2 inches, which are right-hand helix only.

Shell Reamers—Straight and Helical Flutes *ANSI B94.2-1983 (R1988)*



Diameter of Reamer	Length Overall *A*	Flute Length *B*	Hole Diameter Large End *H*	Fitting Arbor No.	Number of Flutes
3/4	2 1/4	1 1/2	0.375	4	8 to 10
7/8	2 1/2	1 3/4	0.500	5	8 to 10
15/16[a]	2 1/2	1 3/4	0.500	5	8 to 10
1	2 1/2	1 3/4	0.500	5	8 to 10
1 1/16	2 3/4	2	0.625	6	8 to 12
1 1/8	2 3/4	2	0.625	6	8 to 12
1 3/16	2 3/4	2	0.625	6	8 to 12
1 1/4	2 3/4	2	0.625	6	8 to 12
1 5/16	3	2 1/4	0.750	7	8 to 12
1 3/8	3	2 1/4	0.750	7	8 to 12
1 7/16	3	2 1/4	0.750	7	8 to 12
1 1/2	3	2 1/4	0.750	7	10 to 14
1 9/16	3	2 1/4	0.750	7	10 to 14
1 5/8	3	2 1/4	0.750	7	10 to 14
1 11/16	3 1/2	2 1/2	1.000	8	10 to 14
1 3/4	3 1/2	2 1/2	1.000	8	12 to 14
1 13/16	3 1/2	2 1/2	1.000	8	12 to 14
1 7/8	3 1/2	2 1/2	1.000	8	12 to 14
1 15/16	3 1/2	2 1/2	1.000	8	12 to 14
2	3 1/2	2 1/2	1.000	8	12 to 14
2 1/16[a]	3 3/4	2 3/4	1.250	9	12 to 16
2 1/8	3 3/4	2 3/4	1.250	9	12 to 16
2 3/16[a]	3 3/4	2 3/4	1.250	9	12 to 16
2 1/4	3 3/4	2 3/4	1.250	9	12 to 16
2 3/8[a]	3 3/4	2 3/4	1.250	9	14 to 16
2 1/2[a]	3 3/4	2 3/4	1.250	9	14 to 16

[a] Helical flutes only.

All dimensions are given in inches. Material is high-speed steel. Helical flute shell reamers with left-hand helical flutes are standard. Shell reamers are designed as a sizing or finishing reamer and are held on an arbor provided with driving lugs. The holes in these reamers are ground with a taper of 1/8 inch per foot.

Tolerances: On diameter of reamer, 3/4- to 1-inch size, incl., + .0001 to + .0005 inch; over 1-inch size, + .0002 to + .0006 inch. On length overall *A* and flute length *B*, 3/4- to 1-inch size, incl., ± 1/16 inch; 1 1/16- to 2-inch size, incl., ± 3/32 inch; 2 1/16- to 2 1/2-inch size, incl., ± 1/8 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Arbors for Shell Reamers—Straight and Taper Shanks *ANSI B94.2-1983 (R1988)*



Arbor Size No.	Overall Length *A*	Approx. Length of Taper *L*	Reamer Size	Taper Shank No.[a]	Straight Shank Dia. *D*	Arbor Size No.	Overall Length *A*	Approx. Length of Taper *L*	Reamer Size	Taper Shank No.[a]	Straight Shank Dia. *D*
4	9	2¼	¾	2	½	7	11	3	1 5/16 to 1⅝	3	⅞
5	9½	2½	13/16 to 1	2	⅝	8	12	3½	1 11/16 to 2	4	1⅛
6	10	2¾	1 1/16 to 1¼	3	¾	9	13	3¾	2 1/16 to 2½	4	1⅜

[a] American National Standard self-holding tapers (see Table 7a on page 933.)

All dimensions are given in inches. These arbors are designed to fit standard shell reamers (see table). End which fits reamer has taper of ⅛ inch per foot.

Stub Screw Machine Reamers—Helical Flutes *ANSI B94.2-1983 (R1988)*



Series No.	Diameter Range	Length Over-all *A*	Length of Flute *B*	Dia. of Shank *D*	Size of Hole *H*	Flute No.	Series No.	Diameter Range	Length Over-all *A*	Length of Flute *B*	Dia. of Shank *D*	Size of Hole *H*	Flute No.
00	.0600-.066	1¾	½	⅛	1/16	4	12	.3761-.407	2½	1¼	½	3/16	6
0	.0661-.074	1¾	½	⅛	1/16	4	13	.4071-.439	2½	1¼	½	3/16	6
1	.0741-.084	1¾	½	⅛	1/16	4	14	.4391-.470	2½	1¼	½	3/16	6
2	.0841-.096	1¾	½	⅛	1/16	4	15	.4701-.505	2½	1¼	½	3/16	6
3	.0961-.126	2	¾	⅛	1/16	4	16	.5051-.567	3	1½	⅝	¼	6
4	.1261-.158	2¼	1	¼	3/32	4	17	.5671-.630	3	1½	⅝	¼	6
5	.1581-.188	2¼	1	¼	3/32	4	18	.6301-.692	3	1½	⅝	¼	6
6	.1881-.219	2¼	1	¼	3/32	6	19	.6921-.755	3	1½	¾	5/16	8
7	.2191-.251	2¼	1	¼	3/32	6	20	.7551-.817	3	1½	¾	5/16	8
8	.2511-.282	2¼	1	⅜	⅛	6	21	.8171-.880	3	1½	¾	5/16	8
9	.2821-.313	2¼	1	⅜	⅛	6	22	.8801-.942	3	1½	¾	5/16	8
10	.3131-.344	2½	1¼	⅜	⅛	6	23	.9421-1.010	3	1½	¾	5/16	8
11	.3441-.376	2½	1¼	⅜	⅛	6	…	…	…	…	…	…	…

All dimensions in inches. Material is high-speed steel.

These reamers are standard with right-hand cut and left-hand helical flutes within the size ranges shown.

Tolerances: On diameter of reamer, for sizes 00 to 7, incl., plus .0001 to plus .0004 inch and for sizes 8 to 23, incl., plus .0001 to plus .0005 inch. On overall length *A*, plus or minus 1/16 inch. On length of flute *B*, plus or minus 1/16 inch. On diameter of shank *D*, minus .0005 to minus .002 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Morse Taper Finishing Reamers
ANSI B94.2-1983 (R1988)



Straight Flutes and Squared Shank							
Taper No.[a]	Small End Dia. (Ref.)	Large End Dia. (Ref.)	Length Overall *A*	Flute Length *B*	Square Length *C*	Shank Dia. *D*	Square Size
0	0.2503	0.3674	3¾	2¼	5/16	5/16	0.235
1	0.3674	0.5170	5	3	7/16	7/16	0.330
2	0.5696	0.7444	6	3½	5/8	5/8	0.470
3	0.7748	0.9881	7¼	4¼	7/8	7/8	0.655
4	1.0167	1.2893	8½	5¼	1	1⅛	0.845
5	1.4717	1.8005	9¾	6¼	1⅛	1½	1.125

Straight and Spiral Flutes and Taper Shank						
Taper No.[a]	Small End Dia. (Ref.)	Large End Dia. (Ref.)	Length Overall *A*	Flute Length *B*	Taper Shank No.[a]	Squared and Taper Shank Number of Flutes
0	0.2503	0.3674	5 11/32	2¼	0	4 to 6 incl.
1	0.3674	0.5170	6 5/16	3	1	6 to 8 incl.
2	0.5696	0.7444	7⅜	3½	2	6 to 8 incl.
3	0.7748	0.9881	8⅞	4¼	3	8 to 10 incl.
4	1.0167	1.2893	10⅞	5¼	4	8 to 10 incl.
5	1.4717	1.8005	13⅛	6¼	5	10 to 12 incl.

[a] Morse. For amount of taper see Table 1b on page 928.

All dimension are given in inches. Material is high-speed steel. The chamfer on the cutting end of the reamer is optional. Squared shank reamers are standard with straight flutes. Tapered shank reamers are standard with straight or spiral flutes. Spiral flute reamers are standard with left-had spiral flutes.

Tolerances: On overall length *A* and flute length *B*, in taper numbers 0 to 3, incl., ±1/16 inch, in taper numbers 4 and 5, ±3/32 inch. On length of square *C*, in taper numbers 0 to 3, incl., ±1/32 inch; in taper numbers 4 and 5, ±1/16 inch. On shank diameter *D*, – .0005 to – .002 inch. On size of square, in taper numbers 0 and 1, – .004 inch; in taper numbers 2 and 3, – .006 inch; in taper numbers 4 and 5, – .008 inch.

Center Reamers.— A "center reamer" is a reamer the teeth of which meet in a point. By their use small conical holes may be reamed in the ends of parts to be machined as on lathe centers. When large holes—usually cored—must be center-reamed, a large reamer is ordinarily used in which the teeth do not meet in a point, the reamer forming the frustum of a cone. Center reamers for such work are called "bull" or "pipe" center reamers.

Bull Center Reamer: A conical reamer used for reaming the ends of large holes—usually cored—so that they will fit on a lathe center. The cutting part of the reamer is generally in the shape of a frustum of a cone. It is also known as a pipe center reamer.

Copyright 2004, Industrial Press, Inc., New York, NY

Taper Pipe Reamers—Spiral Flutes *ANSI B94.2-1983 (R1988)*



Nom. Size	Diameter Large End	Diameter Small End	Length Overall *A*	Flute Length *B*	Square Length *C*	Shank Diameter *D*	Size of Square	No. of Flutes
1/8	0.362	0.316	2 1/8	3/4	3/8	0.4375	0.328	4 to 6
1/4	0.472	0.406	2 7/16	1 1/16	7/16	0.5625	0.421	4 to 6
3/8	0.606	0.540	2 9/16	1 1/16	1/2	0.7000	0.531	4 to 6
1/2	0.751	0.665	3 1/8	1 3/8	5/8	0.6875	0.515	4 to 6
3/4	0.962	0.876	3 1/4	1 3/8	11/16	0.9063	0.679	6 to 10
1	1.212	1.103	3 3/4	1 3/4	13/16	1.1250	0.843	6 to 10
1 1/4	1.553	1.444	4	1 3/4	15/16	1.3125	0.984	6 to 10
1 1/2	1.793	1.684	4 1/4	1 3/4	1	1.5000	1.125	6 to 10
2	2.268	2.159	4 1/2	1 3/4	1 1/8	1.8750	1.406	8 to 12

All dimensions are given in inches. These reamers are tapered 3/4 inch per foot and are intended for reaming holes to be tapped with American National Standard Taper Pipe Thread taps. Material is high-speed steel. Reamers are standard with left-hand spiral flutes.

Tolerances: On length overall *A* and flute length *B*, 1/8- to 3/4-inch size, incl., ±1/16 inch; 1- to 1 1/2-inch size, incl., ±3/32 inch; 2-inch size, ±1/8 inch. On length of square *C*, 1/8- to 3/4-inch size, incl., ±1/32 inch; 1- to 2-inch size, incl., ±1/16 inch. On shank diameter *D*, 1/8-inch size, – .0015 inch; 1/4- to 1-inch size, incl., – .002 inch; 1 1/4- to 2-inch size, incl., – .003 inch. On size of square, 1/8-inch size, – .004 inch; 1/4- to 3/4-inch size, incl., – .006 inch; 1- to 2-inch size, incl., – .008 inch.

B & S Taper Reamers—Straight and Spiral Flutes, Squared Shank

Taper No.[a]	Dia., Small End	Dia., Large End	Overall Length	Square Length	Flute Length	Dia. of Shank	Size of Square	No. of Flutes
1	0.1974	0.3176	4 3/4	1/4	2 7/8	9/32	0.210	4 to 6
2	0.2474	0.3781	5 1/8	5/16	3 1/8	11/32	0.255	4 to 6
3	0.3099	0.4510	5 1/2	3/8	3 3/8	13/32	0.305	4 to 6
4	0.3474	0.5017	5 7/8	7/16	3 11/16	7/16	0.330	4 to 6
5	0.4474	0.6145	6 3/8	1/2	4	9/16	0.420	4 to 6
6	0.4974	0.6808	6 7/8	5/8	4 3/8	5/8	0.470	4 to 6
7	0.5974	0.8011	7 1/2	3/4	4 7/8	3/4	0.560	6 to 8
8	0.7474	0.9770	8 1/8	13/16	5 1/2	13/16	0.610	6 to 8
9	0.8974	1.1530	8 7/8	7/8	6 1/8	1	0.750	6 to 8
10	1.0420	1.3376	9 3/4	1	6 7/8	1 1/8	0.845	6 to 8

[a] For taper per foot, see Table 10 on page 936.

These reamers are no longer ANSI Standard.

All dimensions are given in inches. Material is high-speed steel. The chamfer on the cutting end of the reamer is optional. All reamers are finishing reamers. Spiral flute reamers are standard with left-hand spiral flutes. (Tapered reamers, especially those with left-hand spirals, should not have circular lands because cutting must take place on the outer diameter of the tool.) B & S taper reamers are designed for use in reaming out Brown & Sharpe standard taper sockets.

Tolerances: On length overall *A* and flute length *B*, taper nos. 1 to 7, incl., ±1/16 inch; taper nos. 8 to 10, incl., ±3/32 inch. On length of square *C*, taper nos. 1 to 9, incl., ±1/32 inch; taper no. 10, ±1/16 inch. On shank diameter *D*, – .0005 to – .002 inch. On size of square, taper nos. 1 to 3, incl., – .004 inch; taper nos. 4 to 9, incl., – .006 inch; taper no. 10, – .008 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Die-Maker's Reamers *ANSI B94.2-1983 (R1988)*



Letter Size	Diameter		Length		Letter Size	Diameter		Length		Letter Size	Diameter		Length	
	Small End	Large End	*A*	*B*		Small End	Large End	*A*	*B*		Small End	Large End	*A*	*B*
AAA	0.055	0.070	2 1/4	1 1/8	G	0.135	0.158	3	1 3/4	O	0.250	0.296	5	3 1/2
AA	0.065	0.080	2 1/4	1 1/8	H	0.145	0.169	3 1/4	1 7/8	P	0.275	0.327	5 1/2	4
A	0.075	0.090	2 1/4	1 1/8	I	0.160	0.184	3 1/4	1 7/8	Q	0.300	0.358	6	4 1/2
B	0.085	0.103	2 3/8	1 3/8	J	0.175	0.199	3 1/4	1 7/8	R	0.335	0.397	6 1/2	4 3/4
C	0.095	0.113	2 1/2	1 3/8	K	0.190	0.219	3 1/2	2 1/4	S	0.370	0.435	6 3/4	5
D	0.105	0.126	2 5/8	1 3/8	L	0.205	0.234	3 1/2	2 1/4	T	0.405	0.473	7	5 1/4
E	0.115	0.136	2 3/4	1 3/8	M	0.220	0.252	4	2 1/2	U	0.440	0.511	7 1/4	5 1/2
F	0.125	0.148	3	1 3/4	N	0.235	0.274	4 1/2	3	…	…	…	…	…

All dimensions in inches. Material is high-speed steel. These reamers are designed for use in die-making, have a taper of 3/4 degree included angle or 0.013 inch per inch, and have 2 or 3 flutes. Reamers are standard with left-hand spiral flutes.

Tip of reamer may have conical end.

Tolerances: On length overall *A* and flute length *B*, ±1/16 inch.

Taper Pin Reamers — Straight and Left-Hand Spiral Flutes, Squared Shank; and Left-Hand High-Spiral Flutes, Round Shank *ANSI B94.2-1983 (R1988)*



No. of Taper Pin Reamer	Diameter at Large End of Reamer (Ref.)	Diameter at Small End of Reamer (Ref.)	Overall Lengthof Reamer *A*	Length of Flute *B*	Length of Square *C*[a]	Diameter of Shank *D*	Size of Square[a]
8/0[b]	0.0514	0.0351	1 5/8	25/32	…	1/16	…
7/0	0.0666	0.0497	1 13/16	13/16	5/32	5/64	0.060
6/0	0.0806	0.0611	1 15/16	15/16	5/32	3/32	0.070
5/0	0.0966	0.0719	2 3/16	1 3/16	5/32	7/64	0.080
4/0	0.1142	0.0869	2 5/16	1 5/16	5/32	1/8	0.095
3/0	0.1302	0.1029	2 5/16	1 5/16	5/32	9/64	0.105
2/0	0.1462	0.1137	2 9/16	1 9/16	7/32	5/32	0.115
0	0.1638	0.1287	2 15/16	1 11/16	7/32	11/64	0.130
1	0.1798	0.1447	2 15/16	1 11/16	7/32	3/16	0.140
2	0.2008	0.1605	3 3/16	1 15/16	1/4	13/64	0.150
3	0.2294	0.1813	3 11/16	2 5/16	1/4	15/64	0.175
4	0.2604	0.2071	4 1/16	2 9/16	1/4	17/64	0.200
5	0.2994	0.2409	4 5/16	2 13/16	5/16	5/16	0.235
6	0.3540	0.2773	5 7/16	3 11/16	3/8	23/64	0.270
7	0.4220	0.3297	6 5/16	4 7/16	3/8	13/32	0.305
8	0.5050	0.3971	7 3/16	5 3/16	7/16	7/16	0.330
9	0.6066	0.4805	8 3/16	6 1/16	9/16	9/16	0.420
10	0.7216	0.5799	9 5/16	6 13/16	5/8	5/8	0.470

[a] Not applicable to high-spiral flute reamers.

[b] Not applicable to straight and left-hand spiral fluted, squared shank reamers.

All dimensions in inches. Reamers have a taper of 1/4 inch per foot and are made of high-speed steel. Straight flute reamers of carbon steel are also standard. The number of flutes is as follows; 3 or 4, for 7/0 to 4/0 sizes; 4 to 6, for 3/0 to 0 sizes; 5 or 6, for 1 to 5 sizes; 6 to 8, for 6 to 9 sizes; 7 or 8, for the 10 size in the case of straight- and spiral-flute reamers; and 2 or 3, for 8/0 to 8 sizes; 2 to 4, for the 9 and 10 sizes in the case of high-spiral flute reamers.

Tolerances: On length overall *A* and flute length *B*, ±1/16 inch. On length of square *C*, ±1/32 inch. On shank diameter *D*, –.001 to –.005 inch for straight- and spiral-flute reamers and –.0005 to –.002 inch for high-spiral flute reamers. On size of square, –.004 inch for 7/0 to 7 sizes and –.006 inch for 8 to 10 sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

TWIST DRILLS AND COUNTERBORES

Twist drills are rotary end-cutting tools having one or more cutting lips and one or more straight or helical flutes for the passage of chips and cutting fluids. Twist drills are made with straight or tapered shanks, but most have straight shanks. All but the smaller sizes are ground with "back taper," reducing the diameter from the point toward the shank, to prevent binding in the hole when the drill is worn.

Straight Shank Drills: Straight shank drills have cylindrical shanks which may be of the same or of a different diameter than the body diameter of the drill and may be made with or without driving flats, tang, or grooves.

Taper Shank Drills: Taper shank drills are preferable to the straight shank type for drilling medium and large size holes. The taper on the shank conforms to one of the tapers in the American Standard (Morse) Series.

American National Standard.— American National Standard B94.11M-1993 covers nomenclature, definitions, sizes and tolerances for High Speed Steel Straight and Taper Shank Drills and Combined Drills and Countersinks, Plain and Bell types. It covers both inch and metric sizes. Dimensional tables from the Standard will be found on the following pages.

Definitions of Twist Drill Terms.— The following definitions are included in the Standard.

Axis: The imaginary straight line which forms the longitudinal center of the drill.

Back Taper: A slight decrease in diameter from point to back in the body of the drill.

Body: The portion of the drill extending from the shank or neck to the outer corners of the cutting lips.

Body Diameter Clearance: That portion of the land that has been cut away so it will not rub against the wall of the hole.

Chisel Edge: The edge at the ends of the web that connects the cutting lips.

Chisel Edge Angle: The angle included between the chisel edge and the cutting lip as viewed from the end of the drill.

Clearance Diameter: The diameter over the cutaway portion of the drill lands.

Drill Diameter: The diameter over the margins of the drill measured at the point.

Flutes: Helical or straight grooves cut or formed in the body of the drill to provide cutting lips, to permit removal of chips, and to allow cutting fluid to reach the cutting lips.

Helix Angle: The angle made by the leading edge of the land with a plane containing the axis of the drill.

Land: The peripheral portion of the drill body between adjacent flutes.

Land Width: The distance between the leading edge and the heel of the land measured at a right angle to the leading edge.

Lips—Two Flute Drill: The cutting edges extending from the chisel edge to the periphery.

Lips—Three or Four Flute Drill (Core Drill): The cutting edges extending from the bottom of the chamfer to the periphery.

Lip Relief: The axial relief on the drill point.

Lip Relief Angle: The axial relief angle at the outer corner of the lip. It is measured by projection into a plane tangent to the periphery at the outer corner of the lip. (Lip relief angle is usually measured across the margin of the twist drill.)

Margin: The cylindrical portion of the land which is not cut away to provide clearance.

Neck: The section of reduced diameter between the body and the shank of a drill.

Overall Length: The length from the extreme end of the shank to the outer corners of the cutting lips. It does not include the conical shank end often used on straight shank drills, nor does it include the conical cutting point used on both straight and taper shank drills. (For core drills with an external center on the cutting end it is the same as for two-flute

Copyright 2004, Industrial Press, Inc., New York, NY

drills. For core drills with an internal center on the cutting end, the overall length is to the extreme ends of the tool.)

Point: The cutting end of a drill made up of the ends of the lands, the web, and the lips. In form, it resembles a cone, but departs from a true cone to furnish clearance behind the cutting lips.

Point Angle: The angle included between the lips projected upon a plane parallel to the drill axis and parallel to the cutting lips.

Shank: The part of the drill by which it is held and driven.

Tang: The flattened end of a taper shank, intended to fit into a driving slot in the socket.

Tang Drive: Two opposite parallel driving flats on the end of a straight shank.

Web: The central portion of the body that joins the end of the lands. The end of the web forms the chisel edge on a two-flute drill.

Web Thickness: The thickness of the web at the point unless another specific location is indicated.

Web Thinning: The operation of reducing the web thickness at the point to reduce drilling thrust.



ANSI Standard Twist Drill Nomenclature

Types of Drills.— Drills may be classified based on the type of shank, number of flutes or hand of cut.

Straight Shank Drills: Those having cylindrical shanks which may be the same or different diameter than the body of the drill. The shank may be with or without driving flats, tang, grooves, or threads.

Taper Shank Drills: Those having conical shanks suitable for direct fitting into tapered holes in machine spindles, driving sleeves, or sockets. Tapered shanks generally have a driving tang.

Two-Flute Drills: The conventional type of drill used for originating holes.

Three-Flute Drills (Core Drills): Drill commonly used for enlarging and finishing drilled, cast or punched holes. They will not produce original holes.

Four-Flute Drills (Core Drills): Used interchangeably with three-flute drills. They are of similar construction except for the number of flutes.

Right-Hand Cut: When viewed from the cutting point, the counterclockwise rotation of a drill in order to cut.

Left-Hand Cut: When viewed from the cutting point, the clockwise rotation of a drill in order to cut.

Teat Drill: The cutting edges of a teat drill are at right angles to the axis, and in the center there is a small teat of pyramid shape which leads the drill and holds it in position. This form is used for squaring the bottoms of holes made by ordinary twist drills or for drilling the entire hole, especially if it is not very deep and a square bottom is required. For instance, when drilling holes to form clearance spaces at the end of a keyseat, preparatory to cutting it out by planing or chipping, the teat drill is commonly used.

Copyright 2004, Industrial Press, Inc., New York, NY



Table 1. ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.		Equivalent		Flute		Overall		Flute		Overall		Flute		Overall	
				F		*L*		*F*		*L*		*F*		*L*	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
97	0.15	0.0059	0.150	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
96	0.16	0.0063	0.160	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
95	0.17	0.0067	0.170	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
94	0.18	0.0071	0.180	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
93	0.19	0.0075	0.190	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
92	0.20	0.0079	0.200	1/16	1.6	3/4	19	…	…	…	…	…	…	…	…
91		0.0083	0.211	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
90	0.22	0.0087	0.221	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
89		0.0091	0.231	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
88		0.0095	0.241	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
	0.25	0.0098	0.250	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
87		0.0100	0.254	5/64	2.0	3/4	19	…	…	…	…	…	…	…	…
86		0.0105	0.267	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
85	0.28	0.0110	0.280	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
84		0.0115	0.292	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
	0.30	0.0118	0.300	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
83		0.0120	0.305	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
82		0.0125	0.318	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
	0.32	0.0126	0.320	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
81		0.0130	0.330	3/32	2.4	3/4	19	…	…	…	…	…	…	…	…
80		0.0135	0.343	1/8	3	3/4	19	…	…	…	…	…	…	…	…
	0.35	0.0138	0.350	1/8	3	3/4	19	…	…	…	…	…	…	…	…
79		0.0145	0.368	1/8	3	3/4	19	…	…	…	…	…	…	…	…
	0.38	0.0150	0.380	3/16	5	3/4	19	…	…	…	…	…	…	…	…
1/64		0.0156	0.396	3/16	5	3/4	19	…	…	…	…	…	…	…	…
	0.40	0.0157	0.400	3/16	5	3/4	19	…	…	…	…	…	…	…	…
78		0.0160	0.406	3/16	5	7/8	22	…	…	…	…	…	…	…	…
	0.42	0.0165	0.420	3/16	5	7/8	22	…	…	…	…	…	…	…	…
	0.45	0.0177	0.450	3/16	5	7/8	22	…	…	…	…	…	…	…	…
77		0.0180	0.457	3/16	5	7/8	22	…	…	…	…	…	…	…	…
	0.48	0.0189	0.480	3/16	5	7/8	22	…	…	…	…	…	…	…	…
	0.50	0.0197	0.500	3/16	5	7/8	22	…	…	…	…	…	…	…	…
76		0.0200	0.508	3/16	5	7/8	22	…	…	…	…	…	…	…	…
75		0.0210	0.533	1/4	6	1	25	…	…	…	…	…	…	…	…
	0.55	0.0217	0.550	1/4	6	1	25	…	…	…	…	…	…	…	…
74		0.0225	0.572	1/4	6	1	25	…	…	…	…	…	…	…	…
	0.60	0.0236	0.600	5/16	8	1 1/8	29	…	…	…	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, D[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.	Equivalent			Flute		Overall		Flute		Overall		Flute		Overall	
				F		L		F		L		F		L	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
73		0.0240	0.610	5/16	8	1 1/8	29	…	…	…	…	…	…	…	…
72		0.0250	0.635	5/16	8	1 1/8	29	…	…	…	…	…	…	…	…
	0.65	0.0256	0.650	3/8	10	1 1/4	32	…	…	…	…	…	…	…	…
71		0.0260	0.660	3/8	10	1 1/4	32	…	…	…	…	…	…	…	…
	0.70	0.0276	0.700	3/8	10	1 1/4	32	…	…	…	…	…	…	…	…
70		0.0280	0.711	3/8	10	1 1/4	32	…	…	…	…	…	…	…	…
69		0.0292	0.742	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
	0.75	0.0295	0.750	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
68		0.0310	0.787	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
1/32		0.0312	0.792	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
	0.80	0.0315	0.800	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
67		0.0320	0.813	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
66		0.0330	0.838	1/2	13	1 3/8	35	…	…	…	…	…	…	…	…
	0.85	0.0335	0.850	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
65		0.0350	0.889	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
	0.90	0.0354	0.899	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
64		0.0360	0.914	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
63		0.0370	0.940	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
	0.95	0.0374	0.950	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
62		0.0380	0.965	5/8	16	1 1/2	38	…	…	…	…	…	…	…	…
61		0.0390	0.991	11/16	17	1 5/8	41	…	…	…	…	…	…	…	…
	1.00	0.0394	1.000	11/16	17	1 5/8	41	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
60		0.0400	1.016	11/16	17	1 5/8	41	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
59		0.0410	1.041	11/16	17	1 5/8	41	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
	1.05	0.0413	1.050	11/16	17	1 5/8	41	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
58		0.0420	1.067	11/16	17	1 5/8	41	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
57		0.0430	1.092	3/4	19	1 3/4	44	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
	1.10	0.0433	1.100	3/4	19	1 3/4	44	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
	1.15	0.0453	1.150	3/4	19	1 3/4	44	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
56		0.0465	1.181	3/4	19	1 3/4	44	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
3/64		0.0469	1.191	3/4	19	1 3/4	44	1 1/8	29	2 1/4	57	1/2	13	1 3/8	35
	1.20	0.0472	1.200	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.25	0.0492	1.250	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.30	0.0512	1.300	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
55		0.0520	1.321	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.35	0.0531	1.350	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
54		0.0550	1.397	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.40	0.0551	1.400	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.45	0.0571	1.450	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.50	0.0591	1.500	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
53		0.0595	1.511	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.55	0.0610	1.550	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
1/16		0.0625	1.588	7/8	22	1 7/8	48	1 3/4	44	3	76	5/8	16	1 5/8	41
	1.60	0.0630	1.600	7/8	22	1 7/8	48	2	51	3 3/4	95	11/16	17	1 11/16	43
52		0.0635	1.613	7/8	22	1 7/8	48	2	51	3 3/4	95	11/16	17	1 11/16	43
	1.65	0.0650	1.650	1	25	2	51	2	51	3 3/4	95	11/16	17	1 11/16	43

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, D[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.		Equivalent		Flute		Overall		Flute		Overall		Flute		Overall	
				F		*L*		*F*		*L*		*F*		*L*	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	1.70	0.0669	1.700	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
51		0.0670	1.702	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
	1.75	0.0689	1.750	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
50		0.0700	1.778	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
	1.80	0.0709	1.800	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
	1.85	0.0728	1.850	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
49		0.0730	1.854	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
	1.90	0.0748	1.900	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
48		0.0760	1.930	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
	1.95	0.0768	1.950	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
5/64		0.0781	1.984	1	25	2	51	2	51	3¾	95	11/16	17	1 11/16	43
47		0.0785	1.994	1	25	2	51	2¼	57	4¼	108	11/16	17	1 11/16	43
	2.00	0.0787	2.000	1	25	2	51	2¼	57	4¼	108	11/16	17	1 11/16	43
	2.05	0.0807	2.050	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
46		0.0810	2.057	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
45		0.0820	2.083	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
	2.10	0.0827	2.100	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
	2.15	0.0846	2.150	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
44		0.0860	2.184	1⅛	29	2⅛	54	2¼	57	4¼	108	¾	19	1¾	44
	2.20	0.0866	2.200	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
	2.25	0.0886	2.250	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
43		0.0890	2.261	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
	2.30	0.0906	2.300	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
	2.35	0.0925	2.350	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
42		0.0935	2.375	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
3/32		0.0938	2.383	1¼	32	2¼	57	2¼	57	4¼	108	¾	19	1¾	44
	2.40	0.0945	2.400	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
41		0.0960	2.438	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
	2.46	0.0965	2.450	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
40		0.0980	2.489	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
	2.50	0.0984	2.500	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
39		0.0995	2.527	1⅜	35	2⅜	60	2½	64	4⅝	117	13/16	21	1 13/16	46
38		0.1015	2.578	1 7/16	37	2½	64	2½	64	4⅝	117	13/16	21	1 13/16	46
	2.60	0.1024	2.600	1 7/16	37	2½	64	2½	64	4⅝	117	13/16	21	1 13/16	46
37		0.1040	2.642	1 7/16	37	2½	64	2½	64	4⅝	117	13/16	21	1 13/16	46
	2.70	0.1063	2.700	1 7/16	37	2½	64	2½	64	4⅝	117	13/16	21	1 13/16	46
36		0.1065	2.705	1 7/16	37	2½	64	2½	64	4⅝	117	13/16	21	1 13/16	46
7/64		0.1094	2.779	1½	38	2⅝	67	2½	64	4⅝	117	13/16	21	1 13/16	46
35		0.1100	2.794	1½	38	2⅝	67	2¾	70	5⅛	130	⅞	22	1⅞	48
	2.80	0.1102	2.800	1½	38	2⅝	67	2¾	70	5⅛	130	⅞	22	1⅞	48
34		0.1110	2.819	1½	38	2⅝	67	2¾	70	5⅛	130	⅞	22	1⅞	48
33		0.1130	2.870	1½	38	2⅝	67	2¾	70	5⅛	130	⅞	22	1⅞	48
	2.90	0.1142	2.900	1⅝	41	2¾	70	2¾	70	5⅛	130	⅞	22	1⅞	48
32		0.1160	2.946	1⅝	41	2¾	70	2¾	70	5⅛	130	⅞	22	1⅞	48
	3.00	0.1181	3.000	1⅝	41	2¾	70	2¾	70	5⅛	130	⅞	22	1⅞	48
31		0.1200	3.048	1⅝	41	2¾	70	2¾	70	5⅛	130	⅞	22	1⅞	48

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, D[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.		Equivalent		Flute		Overall		Flute		Overall		Flute		Overall	
		Decimal In.		F		L		F		L		F		L	
	mm		mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	3.10	0.1220	3.100	1 5/8	41	2 3/4	70	2 3/4	70	5 1/8	130	7/8	22	1 7/8	48
1/8		0.1250	3.175	1 5/8	41	2 3/4	70	2 3/4	70	5 1/8	130	7/8	22	1 7/8	48
	3.20	0.1260	3.200	1 5/8	41	2 3/4	70	3	76	5 3/8	137	15/16	24	1 15/16	49
30		0.1285	3.264	1 5/8	41	2 3/4	70	3	76	5 3/8	137	15/16	24	1 15/16	49
	3.30	0.1299	3.300	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
	3.40	0.1339	3.400	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
29		0.1360	3.454	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
	3.50	0.1378	3.500	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
28		0.1405	3.569	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
9/64		0.1406	3.571	1 3/4	44	2 7/8	73	3	76	5 3/8	137	15/16	24	1 15/16	49
	3.60	0.1417	3.600	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
27		0.1440	3.658	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
	3.70	0.1457	3.700	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
26		0.1470	3.734	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
25		0.1495	3.797	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
	3.80	0.1496	3.800	1 7/8	48	3	76	3	76	5 3/8	137	1	25	2 1/16	52
24		0.1520	3.861	2	51	3 1/8	79	3	76	5 3/8	137	1	25	2 1/16	52
	3.90	0.1535	3.900	2	51	3 1/8	79	3	76	5 3/8	137	1	25	2 1/16	52
23		0.1540	3.912	2	51	3 1/8	79	3	76	5 3/8	137	1	25	2 1/16	52
5/32		0.1562	3.967	2	51	3 1/8	79	3	76	5 3/8	137	1	25	2 1/16	52
22		0.1570	3.988	2	51	3 1/8	79	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
	4.00	0.1575	4.000	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
21		0.1590	4.039	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
20		0.1610	4.089	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
	4.10	0.1614	4.100	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
	4.20	0.1654	4.200	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
19		0.1660	4.216	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
	4.30	0.1693	4.300	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
18		0.1695	4.305	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
11/64		0.1719	4.366	2 1/8	54	3 1/4	83	3 3/8	86	5 3/4	146	1 1/16	27	2 1/8	54
17		0.1730	4.394	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
	4.40	0.1732	4.400	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
16		0.1770	4.496	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
	4.50	0.1772	4.500	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
15		0.1800	4.572	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
	4.60	0.1811	4.600	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
14		0.1820	4.623	2 3/16	56	3 3/8	86	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
13	4.70	0.1850	4.700	2 5/16	59	3 1/2	89	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
3/16		0.1875	4.762	2 5/16	59	3 1/2	89	3 3/8	86	5 3/4	146	1 1/8	29	2 3/16	56
12	4.80	0.1890	4.800	2 5/16	59	3 1/2	89	3 5/8	92	6	152	1 3/16	30	2 1/4	57
11		0.1910	4.851	2 5/16	59	3 1/2	89	3 5/8	92	6	152	1 3/16	30	2 1/4	57
	4.90	0.1929	4.900	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
10		0.1935	4.915	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
9		0.1960	4.978	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
	5.00	0.1969	5.000	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
8		0.1990	5.054	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, D[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.		Equivalent		Flute		Overall		Flute		Overall		Flute		Overall	
				F		L		F		L		F		L	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	5.10	0.2008	5.100	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
7		0.2010	5.105	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
13/64		0.2031	5.159	2 7/16	62	3 5/8	92	3 5/8	92	6	152	1 3/16	30	2 1/4	57
6		0.2040	5.182	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
	5.20	0.2047	5.200	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
5		0.2055	5.220	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
	5.30	0.2087	5.300	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
4		0.2090	5.309	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
	5.40	0.2126	5.400	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
3		0.2130	5.410	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
	5.50	0.2165	5.500	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
7/32		0.2188	5.558	2 1/2	64	3 3/4	95	3 5/8	92	6	152	1 1/4	32	2 3/8	60
	5.60	0.2205	5.600	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
2		0.2210	5.613	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
	5.70	0.2244	5.700	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
1		0.2280	5.791	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
	5.80	0.2283	5.800	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
	5.90	0.2323	5.900	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
A		0.2340	5.944	2 5/8	67	3 7/8	98	…	…	…	…	1 5/16	33	2 7/16	62
15/64		0.2344	5.954	2 5/8	67	3 7/8	98	3 3/4	95	6 1/8	156	1 5/16	33	2 7/16	62
	6.00	0.2362	6.000	2 3/4	70	4	102	3 3/4	95	6 1/8	156	1 3/8	35	2 1/2	64
B		0.2380	6.045	2 3/4	70	4	102	…	…	…	…	1 3/8	35	2 1/2	64
	6.10	0.2402	6.100	2 3/4	70	4	102	3 3/4	95	6 1/8	156	1 3/8	35	2 1/2	64
C		0.2420	6.147	2 3/4	70	4	102	…	…	…	…	1 3/8	35	2 1/2	64
	6.20	0.2441	6.200	2 3/4	70	4	102	3 3/4	95	6 1/8	156	1 3/8	35	2 1/2	64
D		0.2460	6.248	2 3/4	70	4	102	…	…	…	…	1 3/8	35	2 1/2	64
	6.30	0.2480	6.300	2 3/4	70	4	102	3 3/4	95	6 1/8	156	1 3/8	35	2 1/2	64
E, 1/4		0.2500	6.350	2 3/4	70	4	102	3 3/4	95	6 1/8	156	1 3/8	35	2 1/2	64
	6.40	0.2520	6.400	2 7/8	73	4 1/8	105	3 7/8	98	6 1/4	159	1 7/16	37	2 5/8	67
	6.50	0.2559	6.500	2 7/8	73	4 1/8	105	3 7/8	98	6 1/4	159	1 7/16	37	2 5/8	67
F		0.2570	6.528	2 7/8	73	4 1/8	105	…	…	…	…	1 7/16	37	2 5/8	67
	6.60	0.2598	6.600	2 7/8	73	4 1/8	105	…	…	…	…	1 7/16	37	2 5/8	67
G		0.2610	6.629	2 7/8	73	4 1/8	105	…	…	…	…	1 7/16	37	2 5/8	67
	6.70	0.2638	6.700	2 7/8	73	4 1/8	105	…	…	…	…	1 7/16	37	2 5/8	67
17/64		0.2656	6.746	2 7/8	73	4 1/8	105	3 7/8	98	6 1/4	159	1 7/16	37	2 5/8	67
H		0.2660	6.756	2 7/8	73	4 1/8	105	…	…	…	…	1 1/2	38	2 11/16	68
	6.80	0.2677	6.800	2 7/8	73	4 1/8	105	3 7/8	98	6 1/4	159	1 1/2	38	2 11/16	68
	6.90	0.2717	6.900	2 7/8	73	4 1/8	105	…	…	…	…	1 1/2	38	2 11/16	68
I		0.2720	6.909	2 7/8	73	4 1/8	105	…	…	…	…	1 1/2	38	2 11/16	68
	7.00	0.2756	7.000	2 7/8	73	4 1/8	105	3 7/8	98	6 1/4	159	1 1/2	38	2 11/16	68
J		0.2770	7.036	2 7/8	73	4 1/8	105	…	…	…	…	1 1/2	38	2 11/16	68
	7.10	0.2795	7.100	2 15/16	75	4 1/4	108	…	…	…	…	1 1/2	38	2 11/16	68
K		0.2810	7.137	2 15/16	75	4 1/4	108	…	…	…	…	1 1/2	38	2 11/16	68
9/32		0.2812	7.142	2 15/16	75	4 1/4	108	3 7/8	98	6 1/4	159	1 1/2	38	2 11/16	68
	7.20	0.2835	7.200	2 15/16	75	4 1/4	108	4	102	6 3/8	162	1 9/16	40	2 3/4	70
	7.30	0.2874	7.300	2 15/16	75	4 1/4	108	…	…	…	…	1 9/16	40	2 3/4	70

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, D[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.	Equivalent			Flute		Overall		Flute		Overall		Flute		Overall	
		Decimal In.		F		L		F		L		F		L	
	mm		mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
L		0.2900	7.366	$2\frac{15}{16}$	75	$4\frac{1}{4}$	108	…	…	…	…	$1\frac{9}{16}$	40	$2\frac{3}{4}$	70
	7.40	0.2913	7.400	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	…	…	…	…	$1\frac{9}{16}$	40	$2\frac{3}{4}$	70
M		0.2950	7.493	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	…	…	…	…	$1\frac{9}{16}$	40	$2\frac{3}{4}$	70
	7.50	0.2953	7.500	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	4	102	$6\frac{3}{8}$	162	$1\frac{9}{16}$	40	$2\frac{3}{4}$	70
$\frac{19}{64}$		0.2969	7.541	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	4	102	$6\frac{3}{8}$	162	$1\frac{9}{16}$	40	$2\frac{3}{4}$	70
	7.60	0.2992	7.600	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	…	…	…	…	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
N		0.3020	7.671	$3\frac{1}{16}$	78	$4\frac{3}{8}$	111	…	…	…	…	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
	7.70	0.3031	7.700	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	…	…	…	…	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
	7.80	0.3071	7.800	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	4	102	$6\frac{3}{8}$	162	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
	7.90	0.3110	7.900	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	…	…	…	…	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
$\frac{5}{16}$		0.3125	7.938	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	4	102	$6\frac{3}{8}$	162	$1\frac{5}{8}$	41	$2\frac{13}{16}$	71
	8.00	0.3150	8.000	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	$4\frac{1}{8}$	105	$6\frac{1}{2}$	165	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
O		0.3160	8.026	$3\frac{3}{16}$	81	$4\frac{1}{2}$	114	…	…	…	…	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
	8.10	0.3189	8.100	$3\frac{5}{16}$	84	$4\frac{5}{8}$	117	…	…	…	…	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
	8.20	0.3228	8.200	$3\frac{5}{16}$	84	$4\frac{5}{8}$	117	$4\frac{1}{8}$	105	$6\frac{1}{2}$	165	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
P		0.3230	8.204	$3\frac{5}{16}$	84	$4\frac{5}{8}$	117	…	…	…	…	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
	8.30	0.3268	8.300	$3\frac{5}{16}$	84	$4\frac{5}{8}$	117	…	…	…	…	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
$\frac{21}{64}$		0.3281	8.334	$3\frac{5}{16}$	84	$4\frac{5}{8}$	117	$4\frac{1}{8}$	105	$6\frac{1}{2}$	165	$1\frac{11}{16}$	43	$2\frac{15}{16}$	75
	8.40	0.3307	8.400	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	…	…	…	…	$1\frac{11}{16}$	43	3	76
Q		0.3320	8.433	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	…	…	…	…	$1\frac{11}{16}$	43	3	76
	8.50	0.3346	8.500	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	$4\frac{1}{8}$	105	$6\frac{1}{2}$	165	$1\frac{11}{16}$	43	3	76
	8.60	0.3386	8.600	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	…	…	…	…	$1\frac{11}{16}$	43	3	76
R		0.3390	8.611	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	…	…	…	…	$1\frac{11}{16}$	43	3	76
	8.70	0.3425	8.700	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	…	…	…	…	$1\frac{11}{16}$	43	3	76
$\frac{11}{32}$		0.3438	8.733	$3\frac{7}{16}$	87	$4\frac{3}{4}$	121	$4\frac{1}{8}$	105	$6\frac{1}{2}$	165	$1\frac{11}{16}$	43	3	76
	8.80	0.3465	8.800	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
S		0.3480	8.839	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	…	…	…	…	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
	8.90	0.3504	8.900	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	…	…	…	…	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
	9.00	0.3543	9.000	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
T		0.3580	9.093	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	…	…	…	…	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
	9.10	0.3583	9.100	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	…	…	…	…	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
$\frac{23}{64}$		0.3594	9.129	$3\frac{1}{2}$	89	$4\frac{7}{8}$	124	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{3}{4}$	44	$3\frac{1}{16}$	78
	9.20	0.3622	9.200	$3\frac{5}{8}$	92	5	127	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
	9.30	0.3661	9.300	$3\frac{5}{8}$	92	5	127	…	…	…	…	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
U		0.3680	9.347	$3\frac{5}{8}$	92	5	127	…	…	…	…	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
	9.40	0.3701	9.400	$3\frac{5}{8}$	92	5	127	…	…	…	…	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
	9.50	0.3740	9.500	$3\frac{5}{8}$	92	5	127	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
$\frac{3}{8}$		0.3750	9.525	$3\frac{5}{8}$	92	5	127	$4\frac{1}{4}$	108	$6\frac{3}{4}$	171	$1\frac{13}{16}$	46	$3\frac{1}{8}$	79
V		0.3770	9.576	$3\frac{5}{8}$	92	5	127	…	…	…	…	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
	9.60	0.3780	9.600	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	…	…	…	…	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
	9.70	0.3819	9.700	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	…	…	…	…	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
	9.80	0.3858	9.800	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	$4\frac{3}{8}$	111	7	178	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
W		0.3860	9.804	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	…	…	…	…	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
	9.90	0.3898	9.900	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	…	…	…	…	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
$\frac{25}{64}$		0.3906	9.921	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	$4\frac{3}{8}$	111	7	178	$1\frac{7}{8}$	48	$3\frac{1}{4}$	83
	10.00	0.3937	10.000	$3\frac{3}{4}$	95	$5\frac{1}{8}$	130	$4\frac{3}{8}$	111	7	178	$1\frac{15}{16}$	49	$3\frac{5}{16}$	84

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.	Equivalent			Flute		Overall		Flute		Overall		Flute		Overall	
				F		*L*		*F*		*L*		*F*		*L*	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
X		0.3970	10.084	3 3/4	95	5 1/8	130	…	…	…	…	1 15/16	49	3 5/16	84
	10.20	0.4016	10.200	3 7/8	98	5 1/4	133	4 3/8	111	7	178	1 15/16	49	3 5/16	84
Y		0.4040	10.262	3 7/8	98	5 1/4	133	…	…	…	…	1 15/16	49	3 5/16	84
13/32		0.4062	10.317	3 7/8	98	5 1/4	133	4 3/8	111	7	178	1 15/16	49	3 5/16	84
Z		0.4130	10.490	3 7/8	98	5 1/4	133	…	…	…	…	2	51	3 3/8	86
	10.50	0.4134	10.500	3 7/8	98	5 1/4	133	4 5/8	117	7 1/4	184	2	51	3 3/8	86
27/64		0.4219	10.716	3 15/16	100	5 3/8	137	4 5/8	117	7 1/4	184	2	51	3 3/8	86
	10.80	0.4252	10.800	4 1/16	103	5 1/2	140	4 5/8	117	7 1/4	184	2 1/16	52	3 7/16	87
	11.00	0.4331	11.000	4 1/16	103	5 1/2	140	4 5/8	117	7 1/4	184	2 1/16	52	3 7/16	87
7/16		0.4375	11.112	4 1/16	103	5 1/2	140	4 5/8	117	7 1/4	184	2 1/16	52	3 7/16	87
	11.20	0.4409	11.200	4 3/16	106	5 5/8	143	4 3/4	121	7 1/2	190	2 1/8	54	3 9/16	90
	11.50	0.4528	11.500	4 3/16	106	5 5/8	143	4 3/4	121	7 1/2	190	2 1/8	54	3 9/16	90
29/64		0.4531	11.509	4 3/16	106	5 5/8	143	4 3/4	121	7 1/2	190	2 1/8	54	3 9/16	90
	11.80	0.4646	11.800	4 5/16	110	5 3/4	146	4 3/4	121	7 1/2	190	2 1/8	54	3 5/8	92
15/32		0.4688	11.908	4 5/16	110	5 3/4	146	4 3/4	121	7 1/2	190	2 1/8	54	3 5/8	92
	12.00	0.4724	12.000	4 3/8	111	5 7/8	149	4 3/4	121	7 3/4	197	2 3/16	56	3 11/16	94
	12.20	0.4803	12.200	4 3/8	111	5 7/8	149	4 3/4	121	7 3/4	197	2 3/16	56	3 11/16	94
31/64		0.4844	12.304	4 3/8	111	5 7/8	149	4 3/4	121	7 3/4	197	2 3/16	56	3 11/16	94
	12.50	0.4921	12.500	4 1/2	114	6	152	4 3/4	121	7 3/4	197	2 1/4	57	3 3/4	95
1/2		0.5000	12.700	4 1/2	114	6	152	4 3/4	121	7 3/4	197	2 1/4	57	3 3/4	95
	12.80	0.5039	12.800	4 1/2	114	6	152	…	…	…	…	2 3/8	60	3 7/8	98
	13.00	0.5118	13.000	4 1/2	114	6	152	…	…	…	…	2 3/8	60	3 7/8	98
33/64		0.5156	13.096	4 13/16	122	6 1/8	168	…	…	…	…	2 3/8	60	3 7/8	98
	13.20	0.5197	13.200	4 13/16	122	6 1/8	168	…	…	…	…	2 3/8	60	3 7/8	98
17/32		0.5312	13.492	4 13/16	122	6 1/8	168	…	…	…	…	2 3/8	60	3 7/8	98
	13.50	0.5315	13.500	4 13/16	122	6 1/8	168	…	…	…	…	2 3/8	60	3 7/8	98
	13.80	0.5433	13.800	4 13/16	122	6 1/8	168	…	…	…	…	2 1/2	64	4	102
35/64		0.5469	13.891	4 13/16	122	6 1/8	168	…	…	…	…	2 1/2	64	4	102
	14.00	0.5512	14.000	4 13/16	122	6 1/8	168	…	…	…	…	2 1/2	64	4	102
	14.25	0.5610	14.250	4 13/16	122	6 1/8	168	…	…	…	…	2 1/2	64	4	102
9/16		0.5625	14.288	4 13/16	122	6 1/8	168	…	…	…	…	2 1/2	64	4	102
	14.50	0.5709	14.500	4 13/16	122	6 1/8	168	…	…	…	…	2 5/8	67	4 1/8	105
37/64		0.5781	14.684	4 13/16	122	6 1/8	168	…	…	…	…	2 5/8	67	4 1/8	105
	14.75	0.5807	14.750	5 3/16	132	7 1/8	181	…	…	…	…	2 5/8	67	4 1/8	105
	15.00	0.5906	15.000	5 3/16	132	7 1/8	181	…	…	…	…	2 5/8	67	4 1/8	105
19/32		0.5938	15.083	5 3/16	132	7 1/8	181	…	…	…	…	2 5/8	67	4 1/8	105
	15.25	0.6004	15.250	5 3/16	132	7 1/8	181	…	…	…	…	2 3/4	70	4 1/4	108
39/64		0.6094	15.479	5 3/16	132	7 1/8	181	…	…	…	…	2 3/4	70	4 1/4	108
	15.50	0.6102	15.500	5 3/16	132	7 1/8	181	…	…	…	…	2 3/4	70	4 1/4	108
	15.75	0.6201	15.750	5 3/16	132	7 1/8	181	…	…	…	…	2 3/4	70	4 1/4	108
5/8		0.6250	15.875	5 3/16	132	7 1/8	181	…	…	…	…	2 3/4	70	4 1/4	108
	16.00	0.6299	16.000	5 3/16	132	7 1/8	181	…	…	…	…	2 7/8	73	4 1/2	114
	16.25	0.6398	16.250	5 3/16	132	7 1/8	181	…	…	…	…	2 7/8	73	4 1/2	114
41/64		0.6406	16.271	5 3/16	132	7 1/8	181	…	…	…	…	2 7/8	73	4 1/2	144
	16.50	0.6496	16.500	5 3/16	132	7 1/8	181	…	…	…	…	2 7/8	73	4 1/2	114
21/32		0.6562	16.669	5 3/16	132	7 1/8	181	…	…	…	…	2 7/8	73	4 1/2	114

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **ANSI Straight Shank Twist Drills — Jobbers Length through 17.5 mm, Taper Length through 12.7 mm, and Screw Machine Length through 25.4 mm Diameter** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*[a]				Jobbers Length				Taper Length				Screw Machine Length			
Fraction No. or Ltr.	Equivalent			Flute		Overall		Flute		Overall		Flute		Overall	
				F		*L*		*F*		*L*		*F*		*L*	
	mm	Decimal In.	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	16.75	0.6594	16.750	5 5/8	143	7 5/8	194	…	…	…	…	2 7/8	73	4 1/2	114
	17.00	0.6693	17.000	5 5/8	143	7 5/8	194	…	…	…	…	2 7/8	73	4 1/2	114
43/64		0.6719	17.066	5 5/8	143	7 5/8	194	…	…	…	…	2 7/8	73	4 1/2	114
	17.25	0.6791	17.250	5 5/8	143	7 5/8	194	…	…	…	…	2 7/8	73	4 1/2	114
11/16		0.6875	17.462	5 5/8	143	7 5/8	194	…	…	…	…	2 7/8	73	4 1/2	114
	17.50	0.6890	17.500	5 5/8	143	7 5/8	194	…	…	…	…	3	76	4 3/4	121
45/64		0.7031	17.859	…	…	…	…	…	…	…	…	3	76	4 3/4	121
	18.00	0.7087	18.000	…	…	…	…	…	…	…	…	3	76	4 3/4	121
23/32		0.7188	18.258	…	…	…	…	…	…	…	…	3	76	4 3/4	121
	18.50	0.7283	18.500	…	…	…	…	…	…	…	…	3 1/8	79	5	127
47/64		0.7344	18.654	…	…	…	…	…	…	…	…	3 1/8	79	5	127
	19.00	0.7480	19.000	…	…	…	…	…	…	…	…	3 1/8	79	5	127
3/4		0.7500	19.050	…	…	…	…	…	…	…	…	3 1/8	79	5	127
49/64		0.7656	19.446	…	…	…	…	…	…	…	…	3 1/4	83	5 1/8	130
	19.50	0.7677	19.500	…	…	…	…	…	…	…	…	3 1/4	83	5 1/8	130
25/32		0.7812	19.845	…	…	…	…	…	…	…	…	3 1/4	83	5 1/8	130
	20.00	0.7879	20.000	…	…	…	…	…	…	…	…	3 3/8	86	5 1/4	133
51/64		0.7969	20.241	…	…	…	…	…	…	…	…	3 3/8	86	5 1/4	133
	20.50	0.8071	20.500	…	…	…	…	…	…	…	…	3 3/8	86	5 1/4	133
13/16		0.8125	20.638	…	…	…	…	…	…	…	…	3 3/8	86	5 1/4	133
	21.00	0.8268	21.000	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
53/64		0.8281	21.034	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
27/32		0.8438	21.433	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
	21.50	0.8465	21.500	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
55/64		0.8594	21.829	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
	22.00	0.8661	22.000	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
7/8		0.8750	22.225	…	…	…	…	…	…	…	…	3 1/2	89	5 3/8	137
	22.50	0.8858	22.500	…	…	…	…	…	…	…	…	3 5/8	92	5 5/8	143
57/64		0.8906	22.621	…	…	…	…	…	…	…	…	3 5/8	92	5 5/8	143
	23.00	0.9055	23.000	…	…	…	…	…	…	…	…	3 5/8	92	5 5/8	143
29/32		0.9062	23.017	…	…	…	…	…	…	…	…	3 5/8	92	5 5/8	143
59/64		0.9219	23.416	…	…	…	…	…	…	…	…	3 3/4	95	5 3/4	146
	23.50	0.9252	23.500	…	…	…	…	…	…	…	…	3 3/4	95	5 3/4	146
15/16		0.9375	23.812	…	…	…	…	…	…	…	…	3 3/4	95	5 3/4	146
	24.00	0.9449	24.000	…	…	…	…	…	…	…	…	3 7/8	98	5 7/8	149
61/64		0.9531	24.209	…	…	…	…	…	…	…	…	3 7/8	98	5 7/8	149
	24.50	0.9646	24.500	…	…	…	…	…	…	…	…	3 7/8	98	5 7/8	149
31/32		0.9688	24.608	…	…	…	…	…	…	…	…	3 7/8	98	5 7/8	149
	25.00	0.9843	25.000	…	…	…	…	…	…	…	…	4	102	6	152
63/64		0.9844	25.004	…	…	…	…	…	…	…	…	4	102	6	152
1		1.0000	25.400	…	…	…	…	…	…	…	…	4	102	6	152

[a] Fractional inch, number, letter, and metric sizes.

Copyright 2004, Industrial Press, Inc., New York, NY



Nominal Shank Size is Same as Nominal Drill Size

Table 2. ANSI Straight Shank Twist Drills — Taper Length — Over ½ in. (12.7 mm) Dia., Fractional and Metric Sizes *ANSI/ASME B94.11M-1993*

Diameter of Drill				Flute Length		Overall Length		Length of Body		Minimum Length of Shk.		Maximum Length of Neck	
D		Decimal	Millimeter	*F*		*L*		*B*		*S*		*N*	
Frac.	mm	Inch Equiv.	Equiv.	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	12.80	0.5039	12.800	4¾	121	8	203	4⅞	124	2⅝	66	½	13
	13.00	0.5117	13.000	4¾	121	8	203	4⅞	124	2⅝	66	½	13
33/64		0.5156	13.096	4¾	121	8	203	4⅞	124	2⅝	66	½	13
	13.20	0.5197	13.200	4¾	121	8	203	4⅞	124	2⅝	66	½	13
17/32		0.5312	13.492	4¾	121	8	203	4⅞	124	2⅝	66	½	13
	13.50	0.5315	13.500	4¾	121	8	203	4⅞	124	2⅝	66	½	13
	13.80	0.5433	13.800	4⅞	124	8¼	210	5	127	2¾	70	½	13
35/64		0.5419	13.891	4⅞	124	8¼	210	5	127	2¾	70	½	13
	14.00	0.5512	14.000	4⅞	124	8¼	210	5	127	2¾	70	½	13
	14.25	0.5610	14.250	4⅞	124	8¼	210	5	127	2¾	70	½	13
9/16		0.5625	14.288	4⅞	124	8¼	210	5	127	2¾	70	½	13
	14.50	0.5709	14.500	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
37/64		0.5781	14.684	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	14.75	0.5807	14.750	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	15.00	0.5906	15.000	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
19/32		0.5938	15.083	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	15.25	0.6004	15.250	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
39/64		0.6094	15.479	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	15.50	0.6102	15.500	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	15.75	0.6201	15.750	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
⅝		0.6250	15.875	4⅞	124	8¾	222	5	127	3⅛	79	⅝	16
	16.00	0.6299	16.000	5⅛	130	9	228	5¼	133	3⅛	79	⅝	16
	16.25	0.6398	16.250	5⅛	130	9	228	5¼	133	3⅛	79	⅝	16
41/64		0.6406	16.271	5⅛	130	9	228	5¼	133	3⅛	79	⅝	16
	16.50	0.6496	16.500	5⅛	130	9	228	5¼	133	3⅛	79	⅝	16
21/32		0.6562	16.667	5⅛	130	9	228	5¼	133	3⅛	79	⅝	16
	16.75	0.6594	16.750	5⅜	137	9¼	235	5½	140	3⅛	79	⅝	16
	17.00	0.6693	17.000	5⅜	137	9¼	235	5½	140	3⅛	79	⅝	16
43/64		0.6719	17.066	5⅜	137	9¼	235	5½	140	3⅛	79	⅝	16
	17.25	0.6791	17.250	5⅜	137	9¼	235	5½	140	3⅛	79	⅝	16
11/16		0.6875	17.462	5⅜	137	9¼	235	5½	140	3⅛	79	⅝	16
	17.50	0.6890	17.500	5⅝	143	9½	241	5¾	146	3⅛	79	⅝	16
45/64		0.7031	17.859	5⅝	143	9½	241	5¾	146	3⅛	79	⅝	16
	18.00	0.7087	18.000	5⅝	143	9½	241	5¾	146	3⅛	79	⅝	16
23/32		0.7188	18.258	5⅝	143	9½	241	5¾	146	3⅛	79	⅝	16
	18.50	0.7283	18.500	5⅞	149	9¾	247	6	152	3⅛	79	⅝	16
47/64		0.7344	18.654	5⅞	149	9¾	247	6	152	3⅛	79	⅝	16
	19.00	0.7480	19.000	5⅞	149	9¾	247	6	152	3⅛	79	⅝	16
¾		0.7500	19.050	5⅞	149	9¾	247	6	152	3⅛	79	⅝	16
49/64		0.7656	19.446	6	152	9⅞	251	6⅛	156	3⅛	79	⅝	16
	19.50	0.7677	19.500	6	152	9⅞	251	6⅛	156	3⅛	79	⅝	16
25/32		0.7812	19.842	6	152	9⅞	251	6⅛	156	3⅛	79	⅝	16

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **ANSI Straight Shank Twist Drills — Taper Length — Over ½ in. (12.7 mm) Dia., Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Diameter of Drill				Flute Length		Overall Length		Length of Body		Minimum Length of Shk.		Maximum Length of Neck	
D		Decimal	Millimeter	*F*		*L*		*B*		*S*		*N*	
Frac.	mm	Inch Equiv.	Equiv.	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
	20.00	0.7874	20.000	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
51/64		0.7969	20.241	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	20.50	0.8071	20.500	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
13/16		0.8125	20.638	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	21.00	0.8268	21.000	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
53/64		0.8281	21.034	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
27/32		0.8438	21.433	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	21.50	0.8465	21.500	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
55/64		0.8594	21.829	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	22.00	0.8661	22.000	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
7/8		0.8750	22.225	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	22.50	0.8858	22.500	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
57/64		0.8906	22.621	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
	23.00	0.9055	23.000	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
29/32		0.9062	23.017	6 1/8	156	10	254	6 1/4	159	3 1/8	79	5/8	16
59/64		0.9219	23.416	6 1/8	156	10 3/4	273	6 1/4	159	3 7/8	98	5/8	16
	23.50	0.9252	23.500	6 1/8	156	10 3/4	273	6 1/4	159	3 7/8	98	5/8	16
15/16		0.9375	23.812	6 1/8	156	10 3/4	273	6 1/4	159	3 7/8	98	5/8	16
	24.00	0.9449	24.000	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
61/64		0.9531	24.209	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
	24.50	0.9646	24.500	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
31/32		0.9688	24.608	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
	25.00	0.9843	25.000	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
63/64		0.9844	25.004	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
1		1.0000	25.400	6 3/8	162	11	279	6 1/2	165	3 7/8	98	5/8	16
	25.50	1.0039	25.500	6 1/2	165	11 1/8	282	6 5/8	168	3 7/8	98	5/8	16
1 1/64		1.0156	25.796	6 1/2	165	11 1/8	282	6 5/8	168	3 7/8	98	5/8	16
	26.00	1.0236	26.000	6 1/2	165	11 1/8	282	6 5/8	168	3 7/8	98	5/8	16
1 1/32		1.0312	26.192	6 1/2	165	11 1/8	282	6 5/8	168	3 7/8	98	5/8	16
	26.50	1.0433	26.560	6 5/8	168	11 1/4	286	6 3/4	172	3 7/8	98	5/8	16
1 3/64		1.0469	26.591	6 5/8	168	11 1/4	286	6 3/4	172	3 7/8	98	5/8	16
1 1/16		1.0625	26.988	6 5/8	168	11 1/4	286	6 3/4	172	3 7/8	98	5/8	16
	27.00	1.0630	27.000	6 5/8	168	11 1/4	286	6 3/4	172	3 7/8	98	5/8	16
1 5/64		1.0781	27.384	6 7/8	175	11 1/2	292	7	178	3 7/8	98	5/8	16
	27.50	1.0827	27.500	6 7/8	175	11 1/2	292	7	178	3 7/8	98	5/8	16
1 3/32		1.0938	27.783	6 7/8	175	11 1/2	292	7	178	3 7/8	98	5/8	16
	28.00	1.1024	28.000	7 1/8	181	11 3/4	298	7 1/4	184	3 7/8	98	5/8	16
1 7/64		1.1094	28.179	7 1/8	181	11 3/4	298	7 1/4	184	3 7/8	98	5/8	16
	28.50	1.1220	28.500	7 1/8	181	11 3/4	298	7 1/4	184	3 7/8	98	5/8	16
1 1/8		1.1250	28.575	7 1/8	181	11 3/4	298	7 1/4	184	3 7/8	98	5/8	16
1 9/64		1.1406	28.971	7 1/4	184	11 7/8	301	7 3/8	187	3 7/8	98	5/8	16
	29.00	1.1417	29.000	7 1/4	184	11 7/8	301	7 3/8	187	3 7/8	98	5/8	16
1 5/32		1.1562	29.367	7 1/4	184	11 7/8	301	7 3/8	187	3 7/8	98	5/8	16
	29.50	1.1614	29.500	7 3/8	187	12	305	7 1/2	191	3 7/8	98	5/8	16
1 11/64		1.1719	29.766	7 3/8	187	12	305	7 1/2	191	3 7/8	98	5/8	16
	30.00	1.1811	30.000	7 3/8	187	12	305	7 1/2	191	3 7/8	98	5/8	16
1 3/16		1.1875	30.162	7 3/8	187	12	305	7 1/2	191	3 7/8	98	5/8	16
	30.50	1.2008	30.500	7 1/2	190	12 1/8	308	7 5/8	194	3 7/8	98	5/8	16
1 13/64		1.2031	30.559	7 1/2	190	12 1/8	308	7 5/8	194	3 7/8	98	5/8	16
1 7/32		1.2188	30.958	7 1/2	190	12 1/8	308	7 5/8	194	3 7/8	98	5/8	16
	31.00	1.2205	31.000	7 7/8	200	12 1/2	317	8	203	3 7/8	98	5/8	16
1 15/64		1.2344	31.354	7 7/8	200	12 1/2	317	8	203	3 7/8	98	5/8	16
	31.50	1.2402	31.500	7 7/8	200	12 1/2	317	8	203	3 7/8	98	5/8	16

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **ANSI Straight Shank Twist Drills — Taper Length — Over ½ in. (12.7 mm) Dia., Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Diameter of Drill				Flute Length		Overall Length		Length of Body		Minimum Length of Shk.		Maximum Length of Neck	
D		Decimal	Millimeter	*F*		*L*		*B*		*S*		*N*	
Frac.	mm	Inch Equiv.	Equiv.	Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
1¼		1.2500	31.750	7⅞	200	12½	317	8	203	3⅞	98	⅝	16
	32.00	1.2598	32.000	8½	216	14⅛	359	8⅝	219	4⅞	124	⅝	16
	32.50	1.2795	32.500	8½	216	14⅛	359	8⅝	219	4⅞	124	⅝	16
1 9/32		1.2812	32.542	8½	216	14⅛	359	8⅝	219	4⅞	124	⅝	16
	33.00	1.2992	33.000	8⅝	219	14¼	362	8¾	222	4⅞	124	⅝	16
1 5/16		1.3125	33.338	8⅝	219	14¼	362	8¾	222	4⅞	124	⅝	16
	33.50	1.3189	33.500	8¾	222	14⅜	365	8⅞	225	4⅞	124	⅝	16
	34.00	1.3386	34.000	8¾	222	14⅜	365	8⅞	225	4⅞	124	⅝	16
1 11/32		1.3438	34.133	8¾	222	14⅜	365	8⅞	225	4⅞	124	⅝	16
	34.50	1.3583	34.500	8⅞	225	14½	368	9	229	4⅞	124	⅝	16
1⅜		1.3750	34.925	8⅞	225	14½	368	9	229	4⅞	124	⅝	16
	35.00	1.3780	35.000	9	229	14⅝	372	9⅛	232	4⅞	124	⅝	16
	35.50	1.3976	35.500	9	229	14⅝	372	9⅛	232	4⅞	124	⅝	16
1 13/32		1.4062	35.717	9	229	14⅝	372	9⅛	232	4⅞	124	⅝	16
	36.00	1.4173	36.000	9⅛	232	14¾	375	9¼	235	4⅞	124	⅝	16
	36.50	1.4370	36.500	9⅛	232	14¾	375	9¼	235	4⅞	124	⅝	16
1 7/16		1.4375	36.512	9⅛	232	14¾	375	9¼	235	4⅞	124	⅝	16
	37.00	1.4567	37.000	9¼	235	14⅞	378	9⅜	238	4⅞	124	⅝	16
1 15/32		1.4688	37.308	9¼	235	14⅞	378	9⅜	238	4⅞	124	⅝	16
	37.50	1.4764	37.500	9⅜	238	15	381	9½	241	4⅞	124	⅝	16
	38.00	1.4961	38.000	9⅜	238	15	381	9½	241	4⅞	124	⅝	16
1½		1.5000	38.100	9⅜	238	15	381	9½	241	4⅞	124	⅝	16
1 9/16		1.5625	39.688	9⅝	244	15¼	387	9¾	247	4⅞	124	⅝	16
1⅝		1.6250	41.275	9⅞	251	15⅝	397	10	254	4⅞	124	¾	19
1¾		1.7500	44.450	10½	267	16¼	413	10⅝	270	4⅞	124	¾	19



Table 3. American National Standard Tangs for Straight Shank Drills
ANSI/ASME B94.11M-1993

Nominal Diameter of Drill Shank, *A*		Thickness of Tang, *J*				Length of Tang, *K*	
		Inches		Millimeters			
Inches	Millimeters	Max.	Min.	Max.	Min.	Inches	Millimeters
1/8 thru 3/16	3.18 thru 4.76	0.094	0.090	2.39	2.29	9/32	7.0
over 3/16 thru ¼	over 4.76 thru 6.35	0.122	0.118	3.10	3.00	5/16	8.0
over ¼ thru 5/16	over 6.35 thru 7.94	0.162	0.158	4.11	4.01	11/32	8.5
over 5/16 thru ⅜	over 7.94 thru 9.53	0.203	0.199	5.16	5.06	⅜	9.5
over ⅜ thru 15/32	over 9.53 thru 11.91	0.243	0.239	6.17	6.07	7/16	11.0
over 15/32 thru 9/16	over 11.91 thru 14.29	0.303	0.297	7.70	7.55	½	12.5
over 9/16 thru 21/32	over 14.29 thru 16.67	0.373	0.367	9.47	9.32	9/16	14.5
over 21/32 thru ¾	over 16.67 thru 19.05	0.443	0.437	11.25	11.10	⅝	16.0
over ¾ thru ⅞	over 19.05 thru 22.23	0.514	0.508	13.05	12.90	11/16	17.5
over ⅞ thru 1	over 22.23 thru 25.40	0.609	0.601	15.47	15.27	¾	19.0
over 1 thru 1 1/16	over 25.40 thru 30.16	0.700	0.692	17.78	17.58	13/16	20.5
over 1 1/16 thru 1⅜	over 30.16 thru 34.93	0.817	0.809	20.75	20.55	⅞	22.0

To fit split sleeve collet type drill drivers. See page 878.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Straight Shank Twist Drills — Screw Machine Length — Over 1 in. (25.4 mm) Dia. *ANSI/ASME B94.11M-1993*



Diameter of Drill				Flute Length		Overall Length		Shank Diameter	
D		Decimal Inch Equivalent	Millimeter Equivalent	*F*		*L*		*A*	
Frac.	mm			Inch	mm	Inch	mm	Inch	mm
	25.50	1.0039	25.500	4	102	6	152	0.9843	25.00
	26.00	1.0236	26.000	4	102	6	152	0.9843	25.00
1 1/16		1.0625	26.988	4	102	6	152	1.0000	25.40
	28.00	1.1024	28.000	4	102	6	152	0.9843	25.00
1 1/8		1.1250	28.575	4	102	6	152	1.0000	25.40
	30.00	1.1811	30.000	4 1/4	108	6 5/8	168	0.9843	25.00
1 3/16		1.1875	30.162	4 1/4	108	6 5/8	168	1.0000	25.40
1 1/4		1.2500	31.750	4 3/8	111	6 3/4	171	1.0000	25.40
	32.00	1.2598	32.000	4 3/8	111	7	178	1.2402	31.50
1 5/16		1.3125	33.338	4 3/8	111	7	178	1.2500	31.75
	34.00	1.3386	34.000	4 1/2	114	7 1/8	181	1.2402	31.50
1 3/8		1.3750	34.925	4 1/2	114	7 1/8	181	1.2500	31.75
	36.00	1.4173	36.000	4 3/4	121	7 3/8	187	1.2402	31.50
1 7/16		1.4375	36.512	4 3/4	121	7 3/8	187	1.2500	31.75
	38.00	1.4961	38.000	4 7/8	124	7 1/2	190	1.2402	31.50
1 1/2		1.5000	38.100	4 7/8	124	7 1/2	190	1.2500	31.75
1 9/16		1.5625	39.688	4 7/8	124	7 3/4	197	1.5000	38.10
	40.00	1.5748	40.000	4 7/8	124	7 3/4	197	1.4961	38.00
1 5/8		1.6250	41.275	4 7/8	124	7 3/4	197	1.5000	38.10
	42.00	1.6535	42.000	5 1/8	130	8	203	1.4961	38.00
1 11/16		1.6875	42.862	5 1/8	130	8	203	1.5000	38.10
	44.00	1.7323	44.000	5 1/8	130	8	203	1.4961	38.00
1 3/4		1.7500	44.450	5 1/8	130	8	203	1.5000	38.10
	46.00	1.8110	46.000	5 3/8	137	8 1/4	210	1.4961	38.00
1 13/16		1.8125	46.038	5 3/8	137	8 1/4	210	1.5000	38.10
1 7/8		1.8750	47.625	5 3/8	137	8 1/4	210	1.5000	38.10
	48.00	1.8898	48.000	5 5/8	143	8 1/2	216	1.4961	38.00
1 15/16		1.9375	49.212	5 5/8	143	8 1/2	216	1.5000	38.10
	50.00	1.9685	50.000	5 5/8	143	8 1/2	216	1.4961	38.00
2		2.0000	50.800	5 5/8	143	8 1/2	216	1.5000	38.10

Copyright 2004, Industrial Press, Inc., New York, NY



Table 5. American National Taper Shank Twist Drills
Fractional and Metric Sizes *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
	3.00	0.1181	3.000	1	1 7/8	48	5 1/8	130	…	…	…	…	…
1/8		0.1250	3.175	1	1 7/8	48	5 1/8	130	…	…	…	…	…
	3.20	0.1260	3.200	1	2 1/8	54	5 3/8	137	…	…	…	…	…
	3.50	0.1378	3.500	1	2 1/8	54	5 3/8	137	…	…	…	…	…
9/64		0.1406	3.571	1	2 1/8	54	5 3/8	137	…	…	…	…	…
	3.80	0.1496	3.800	1	2 1/8	54	5 3/8	137	…	…	…	…	…
5/32		0.1562	3.967	1	2 1/8	54	5 3/8	137	…	…	…	…	…
	4.00	0.1575	4.000	1	2 1/2	64	5 3/4	146	…	…	…	…	…
	4.20	0.1654	4.200	1	2 1/2	64	5 3/4	146	…	…	…	…	…
11/64		0.1719	4.366	1	2 1/2	64	5 3/4	146	…	…	…	…	…
	4.50	0.1772	4.500	1	2 1/2	64	5 3/4	146	…	…	…	…	…
3/16		0.1875	4.762	1	2 1/2	64	5 3/4	146	…	…	…	…	…
	4.80	0.1890	4.800	1	2 3/4	70	6	152	…	…	…	…	…
	5.00	0.1969	5.000	1	2 3/4	70	6	152	…	…	…	…	…
13/64		0.2031	5.159	1	2 3/4	70	6	152	…	…	…	…	…
	5.20	0.2047	5.200	1	2 3/4	70	6	152	…	…	…	…	…
	5.50	0.2165	5.500	1	2 3/4	70	6	152	…	…	…	…	…
7/32		0.2183	5.558	1	2 3/4	70	6	152	…	…	…	…	…
	5.80	0.2223	5.800	1	2 7/8	73	6 1/8	156	…	…	…	…	…
15/64		0.2344	5.954	1	2 7/8	73	6 1/8	156	…	…	…	…	…
	6.00	0.2362	6.000	1	2 7/8	73	6 1/8	156	…	…	…	…	…
	6.20	0.2441	6.200	1	2 7/8	73	6 1/8	156	…	…	…	…	…
1/4		0.2500	6.350	1	2 7/8	73	6 1/8	156	…	…	…	…	…
	6.50	0.2559	6.500	1	3	76	6 1/4	159	…	…	…	…	…
17/64		0.2656	6.746	1	3	76	6 1/4	159	…	…	…	…	…
	6.80	0.2677	6.800	1	3	76	6 1/4	159	…	…	…	…	…
	7.00	0.2756	7.000	1	3	76	6 1/4	159	…	…	…	…	…
9/32		0.2812	7.142	1	3	76	6 1/4	159	…	…	…	…	…
	7.20	0.2835	7.200	1	3 1/8	79	6 3/8	162	…	…	…	…	…
	7.50	0.2953	7.500	1	3 1/8	79	6 3/8	162	…	…	…	…	…
19/64		0.2969	7.541	1	3 1/8	79	6 3/8	162	…	…	…	…	…
	7.80	0.3071	7.800	1	3 1/8	79	6 3/8	162	…	…	…	…	…
5/16		0.3125	7.938	1	3 1/8	79	6 3/8	162	…	…	…	…	…
	8.00	0.3150	8.000	1	3 1/4	83	6 1/2	165	…	…	…	…	…
	8.20	0.3228	8.200	1	3 1/4	83	6 1/2	165	…	…	…	…	…
21/64		0.3281	8.334	1	3 1/4	83	6 1/2	165	…	…	…	…	…
	8.50	0.3346	8.500	1	3 1/4	83	6 1/2	165	…	…	…	…	…
11/32		0.3438	8.733	1	3 1/4	83	6 1/2	165	…	…	…	…	…
	8.80	0.3465	8.800	1	3 1/2	89	6 3/4	171	…	…	…	…	…
	9.00	0.3543	9.000	1	3 1/2	89	6 3/4	171	…	…	…	…	…
23/64		0.3594	9.129	1	3 1/2	89	6 3/4	171	…	…	…	…	…
	9.20	0.3622	9.200	1	3 1/2	89	6 3/4	171	…	…	…	…	…
	9.50	0.3740	9.500	1	3 1/2	89	6 3/4	171	…	…	…	…	…
3/8		0.3750	9.525	1	3 1/2	89	6 3/4	171	2	3 1/2	89	7 3/8	187
	9.80	0.3858	9.800	1	3 5/8	92	7	178	…	…	…	…	…
25/64		0.3906	9.921	1	3 5/8	92	7	178	2	3 5/8	92	7 1/2	190
	10.00	0.3937	10.000	1	3 5/8	92	7	178	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Taper Shank Twist Drills Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
	10.20	0.4016	10.200	1	3 3/8	92	7	178	…	…	…	…	…
13/32		0.4062	10.320	1	3 3/8	92	7	178	2	3 3/8	92	7 1/2	190
	10.50	0.4134	10.500	1	3 3/8	98	7 1/4	184	…	…	…	…	…
27/64		0.4219	10.716	1	3 3/8	98	7 1/4	184	2	3 3/8	98	7 3/4	197
	10.80	0.4252	10.800	1	3 3/8	98	7 1/4	184	…	…	…	…	…
	11.00	0.4331	11.000	1	3 3/8	98	7 1/4	184	…	…	…	…	…
7/16		0.4375	11.112	1	3 3/8	98	7 1/4	184	2	3 3/8	98	7 3/4	197
	11.20	0.4409	11.200	1	4 1/8	105	7 1/2	190	…	…	…	…	…
	11.50	0.4528	11.500	1	4 1/8	105	7 1/2	190	…	…	…	…	…
29/64		0.4531	11.509	1	4 1/8	105	7 1/2	190	2	4 1/8	105	8	203
	11.80	0.4646	11.800	1	4 1/8	105	7 1/2	190	…	…	…	…	…
15/32		0.4688	11.906	1	4 1/8	105	7 1/2	190	2	4 1/8	105	8	203
	12.00	0.4724	12.000	2	4 3/8	111	8 1/4	210	1	4 3/8	111	7 3/4	197
	12.20	0.4803	12.200	2	4 3/8	111	8 1/4	210	1	4 3/8	111	7 3/4	197
31/64		0.4844	12.304	2	4 3/8	111	8 1/4	210	1	4 3/8	111	7 3/4	197
	12.50	0.4921	12.500	2	4 3/8	111	8 1/4	210	1	4 3/8	111	7 3/4	197
1/2		0.5000	12.700	2	4 3/8	111	8 1/4	210	1	4 3/8	111	7 3/4	197
	12.80	0.5034	12.800	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
	13.00	0.5118	13.000	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
33/64		0.5156	13.096	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
	13.20	0.5197	13.200	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
17/32		0.5312	13.492	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
	13.50	0.5315	13.500	2	4 5/8	117	8 1/2	216	1	4 5/8	117	8	203
	13.80	0.5433	13.800	2	4 7/8	124	8 3/4	222	1	4 7/8	124	8 1/4	210
35/64		0.5469	13.891	2	4 7/8	124	8 3/4	222	1	4 7/8	124	8 1/4	210
	14.00	0.5572	14.000	2	4 7/8	124	8 3/4	222	1	4 7/8	124	8 1/4	210
	14.25	0.5610	14.250	2	4 7/8	124	8 3/4	222	1	4 7/8	124	8 1/4	210
9/16		0.5625	14.288	2	4 7/8	124	8 3/4	222	1	4 7/8	124	8 1/4	210
	14.50	0.5709	14.500	2	4 7/8	124	8 3/4	222	…	…	…	…	…
37/64		0.5781	14.684	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	14.75	0.5807	14.750	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	15.00	0.5906	15.000	2	4 7/8	124	8 3/4	222	…	…	…	…	…
19/32		0.5938	15.083	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	15.25	0.6004	15.250	2	4 7/8	124	8 3/4	222	…	…	…	…	…
39/64		0.6094	15.479	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	15.50	0.6102	15.500	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	15.75	0.6201	15.750	2	4 7/8	124	8 3/4	222	…	…	…	…	…
5/8		0.6250	15.875	2	4 7/8	124	8 3/4	222	…	…	…	…	…
	16.00	0.6299	16.000	2	5 1/8	130	9	229	…	…	…	…	…
	16.25	0.6398	16.250	2	5 1/8	130	9	229	…	…	…	…	…
41/64		0.6406	16.271	2	5 1/8	130	9	229	3	5 1/8	130	9 3/4	248
	16.50	0.6496	16.500	2	5 1/8	130	9	229	…	…	…	…	…
21/32		0.6562	16.667	2	5 1/8	130	9	229	3	5 1/8	130	9 3/4	248
	16.75	0.6594	16.750	2	5 3/8	137	9 1/4	235	…	…	…	…	…
	17.00	0.6693	17.000	2	5 3/8	137	9 1/4	235	…	…	…	…	…
43/64		0.6719	17.066	2	5 3/8	137	9 1/4	235	3	5 3/8	137	10	254
	17.25	0.6791	17.250	2	5 3/8	137	9 1/4	235	…	…	…	…	…
11/16		0.6875	17.462	2	5 3/8	137	9 1/4	235	3	5 3/8	137	10	254
	17.50	0.6880	17.500	2	5 5/8	143	9 1/2	241	…	…	…	…	…
45/64		0.7031	17.859	2	5 5/8	143	9 1/2	241	3	5 5/8	143	10 1/4	260
	18.00	0.7087	18.000	2	5 5/8	143	9 1/2	241	…	…	…	…	…
23/32		0.7188	18.258	2	5 5/8	143	9 1/2	241	3	5 5/8	143	10 1/4	260
	18.50	0.7283	18.500	2	5 7/8	149	9 3/4	248	…	…	…	…	…
47/64		0.7344	18.654	2	5 7/8	149	9 3/4	248	3	5 7/8	149	10 1/2	267

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Taper Shank Twist Drills Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
	19.00	0.7480	19.000	2	5 7/8	149	9 3/4	248	…	…	…	…	…
3/4		0.7500	19.050	2	5 7/8	149	9 3/4	248	3	5 7/8	149	10 1/2	267
49/64		0.7656	19.446	2	6	152	9 7/8	251	3	6	152	10 5/8	270
	19.50	0.7677	19.500	2	6	152	9 7/8	251	…	…	…	…	…
25/32		0.7812	19.843	2	6	152	9 7/8	251	3	6	152	10 5/8	270
	20.00	0.7821	20.000	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
51/64		0.7969	20.241	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	20.50	0.8071	20.500	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
13/16		0.8125	20.638	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	21.00	0.8268	21.000	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
53/64		0.8281	21.034	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
27/32		0.8438	21.433	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	21.50	0.8465	21.500	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
55/64		0.8594	21.829	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	22.00	0.8661	22.000	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
7/8		0.8750	22.225	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	22.50	0.8858	22.500	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
57/64		0.8906	22.621	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
	23.00	0.9055	23.000	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
29/32		0.9062	23.017	3	6 1/8	156	10 3/4	273	2	6 1/8	156	10	254
59/64		0.9219	23.416	3	6 1/8	156	10 3/4	273	…	…	…	…	…
	23.50	0.9252	23.500	3	6 1/8	156	10 3/4	273	…	…	…	…	…
15/16		0.9375	23.813	3	6 1/8	156	10 3/4	273	…	…	…	…	…
	24.00	0.9449	24.000	3	6 3/8	162	11	279	…	…	…	…	…
61/64		0.9531	24.209	3	6 3/8	162	11	279	…	…	…	…	…
	24.50	0.9646	24.500	3	6 3/8	162	11	279	…	…	…	…	…
31/32		0.9688	24.608	3	6 3/8	162	11	279	…	…	…	…	…
	25.00	0.9843	25.000	3	6 3/8	162	11	279	…	…	…	…	…
63/64		0.9844	25.004	3	6 3/8	162	11	279	…	…	…	…	…
1		1.0000	25.400	3	6 3/8	162	11	279	4	6 3/8	162	12	305
	25.50	1.0039	25.500	3	6 1/2	165	11 1/8	283	…	…	…	…	…
1 1/64		1.0156	25.796	3	6 1/2	165	11 1/8	283	…	…	…	…	…
	26.00	1.0236	26.000	3	6 1/2	165	11 1/8	283	…	…	…	…	…
1 1/32		1.0312	26.192	3	6 1/2	165	11 1/8	283	4	6 1/2	165	12 1/8	308
	26.50	1.0433	26.500	3	6 5/8	168	11 1/4	286	…	…	…	…	…
1 3/64		1.0469	26.591	3	6 5/8	168	11 1/4	286	…	…	…	…	…
1 1/16		1.0625	26.988	3	6 5/8	168	11 1/4	286	4	6 5/8	168	12 1/4	311
	27.00	1.0630	27.000	3	6 5/8	168	11 1/4	286	…	…	…	…	…
1 5/64		1.0781	27.384	4	6 7/8	175	12 1/2	318	3	6 7/8	175	11 1/2	292
	27.50	1.0827	27.500	4	6 7/8	175	12 1/2	318	3	6 7/8	175	11 1/2	292
1 3/32		1.0938	27.783	4	6 7/8	175	12 1/2	318	3	6 7/8	175	11 1/2	292
	28.00	1.1024	28.000	4	7 1/8	181	12 3/4	324	3	7 1/8	181	11 3/4	298
1 7/64		1.1094	28.179	4	7 1/8	181	12 3/4	324	3	7 1/8	181	11 3/4	298
	28.50	1.1220	28.500	4	7 1/8	181	12 3/4	324	3	7 1/8	181	11 3/4	298
1 1/8		1.1250	28.575	4	7 1/8	181	12 3/4	324	3	7 1/8	181	11 3/4	298
1 9/64		1.1406	28.971	4	7 1/4	184	12 7/8	327	3	7 1/4	184	11 7/8	302
	29.00	1.1417	29.000	4	7 1/4	184	12 7/8	327	3	7 1/4	184	11 7/8	302
1 5/32		1.1562	29.367	4	7 1/4	184	12 7/8	327	3	7 1/4	184	11 7/8	302
	29.50	1.1614	29.500	4	7 3/8	187	13	330	3	7 3/8	187	12	305
1 11/64		1.1719	29.797	4	7 3/8	187	13	330	3	7 3/8	187	12	305
	30.00	1.1811	30.000	4	7 3/8	187	13	330	3	7 3/8	187	12	305
1 3/16		1.1875	30.162	4	7 3/8	187	13	330	3	7 3/8	187	12	305
	30.50	1.2008	30.500	4	7 1/2	190	13 1/8	333	3	7 1/2	190	12 1/8	308
1 13/64		1.2031	30.559	4	7 1/2	190	13 1/8	333	3	7 1/2	190	12 1/8	308

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Taper Shank Twist Drills Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
1 7/32		1.2188	30.958	4	7 1/2	190	13 1/8	333	3	7 1/2	190	12 1/8	308
	31.00	1.2205	31.000	4	7 7/8	200	13 1/2	343	3	7 7/8	200	12 1/2	318
1 15/64		1.2344	31.354	4	7 7/8	200	13 1/2	343	3	7 7/8	200	12 1/2	318
	31.50	1.2402	31.500	4	7 7/8	200	13 1/2	343	3	7 7/8	200	12 1/2	318
1 1/4		1.2500	31.750	4	7 7/8	200	13 1/2	343	3	7 7/8	200	12 1/2	318
	32.00	1.2598	32.000	4	8 1/2	216	14 1/8	359	…	…	…	…	…
1 17/64		1.2656	32.146	4	8 1/2	216	14 1/8	359	…	…	…	…	…
	32.50	1.2795	32.500	4	8 1/2	216	14 1/8	359	…	…	…	…	…
1 9/32		1.2812	32.542	4	8 1/2	216	14 1/8	359	…	…	…	…	…
1 19/64		1.2969	32.941	4	8 5/8	219	14 1/4	362	…	…	…	…	…
	33.00	1.2992	33.000	4	8 5/8	219	14 1/4	362	…	…	…	…	…
1 5/16		1.3125	33.338	4	8 5/8	219	14 1/4	362	…	…	…	…	…
	33.50	1.3189	33.500	4	8 3/4	222	14 3/8	365	…	…	…	…	…
1 21/64		1.3281	33.734	4	8 3/4	222	14 3/8	365	…	…	…	…	…
	34.00	1.3386	34.000	4	8 3/4	222	14 3/8	365	…	…	…	…	…
1 11/32		1.3438	34.133	4	8 3/4	222	14 3/8	365	…	…	…	…	…
	34.50	1.3583	34.500	4	8 7/8	225	14 1/2	368	…	…	…	…	…
1 23/64		1.3594	34.529	4	8 7/8	225	14 1/2	368	…	…	…	…	…
1 3/8		1.3750	34.925	4	8 7/8	225	14 1/2	368	…	…	…	…	…
	35.00	1.3780	35.000	4	9	229	14 5/8	371	…	…	…	…	…
1 25/64		1.3906	35.321	4	9	229	14 5/8	371	…	…	…	…	…
	35.50	1.3976	35.500	4	9	229	14 5/8	371	…	…	…	…	…
1 13/32		1.4062	35.717	4	9	229	14 5/8	371	…	…	…	…	…
	36.00	1.4173	36.000	4	9 1/8	232	14 3/4	375	…	…	…	…	…
1 27/64		1.4219	36.116	4	9 1/8	232	14 3/4	375	…	…	…	…	…
	36.50	1.4370	36.500	4	9 1/8	232	14 3/4	375	…	…	…	…	…
1 7/16		1.4375	36.512	4	9 1/8	232	14 3/4	375	…	…	…	…	…
1 29/64		1.4531	36.909	4	9 1/4	235	14 7/8	378	…	…	…	…	…
	37.00	1.4567	37.000	4	9 1/4	235	14 7/8	378	…	…	…	…	…
1 15/32		1.4688	37.308	4	9 1/4	235	14 7/8	378	…	…	…	…	…
	37.50	1.4764	37.500	4	9 3/8	238	15	381	…	…	…	…	…
1 31/64		1.4844	37.704	4	9 3/8	238	15	381	…	…	…	…	…
	38.00	1.4961	38.000	4	9 3/8	238	15	381	…	…	…	…	…
1 1/2		1.5000	38.100	4	9 3/8	238	15	381	…	…	…	…	…
1 33/64		1.5156	38.496	…	…	…	…	…	4	9 3/4	238	15	381
1 17/32		1.5312	38.892	5	9 3/8	238	16 3/8	416	4	9 3/8	238	15	381
	39.00	1.5354	39.000	5	9 5/8	244	16 5/8	422	4	9 5/8	244	15 1/4	387
1 35/64		1.5469	39.291	…	…	…	…	…	4	9 5/8	244	15 1/4	387
1 9/16		1.5625	39.688	5	9 5/8	244	16 5/8	422	4	9 5/8	244	15 1/4	387
	40.00	1.5748	40.000	5	9 7/8	251	16 7/8	429	4	9 7/8	251	15 1/2	394
1 37/64		1.5781	40.084	…	…	…	…	…	4	9 7/8	251	15 1/2	394
1 19/32		1.5938	40.483	5	9 7/8	251	16 7/8	429	4	9 7/8	251	15 1/2	394
1 39/64		1.6094	40.879	…	…	…	…	…	4	10	254	15 5/8	397
	41.00	1.6142	41.000	5	10	254	17	432	4	10	254	15 5/8	397
1 5/8		1.6250	41.275	5	10	254	17	432	4	10	254	15 5/8	397
1 41/64		1.6406	41.671	…	…	…	…	…	4	10 1/8	257	15 3/4	400
	42.00	1.6535	42.000	5	10 1/8	257	17 1/8	435	4	10 1/8	257	15 3/4	400
1 21/32		1.6562	42.067	5	10 1/8	257	17 1/8	435	4	10 1/8	257	15 3/4	400
1 43/64		1.6719	42.466	…	…	…	…	…	4	10 1/8	257	15 3/4	400
1 11/16		1.6875	42.862	5	10 1/8	257	17 1/4	435	4	10 1/8	257	15 3/4	400
	43.00	1.6929	43.000	5	10 1/8	257	17 1/8	435	4	10 1/8	257	15 3/4	400
1 45/64		1.7031	43.259	…	…	…	…	…	4	10 1/8	257	15 3/4	400
1 23/32		1.7188	43.658	5	10 1/8	257	17 1/8	435	4	10 1/8	257	15 3/4	400
	44.00	1.7323	44.000	5	10 1/8	257	17 1/8	435	4	10 3/8	264	16 1/4	413

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Taper Shank Twist Drills Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
1 47/64		1.7344	44.054	…	…	…	…	…	4	10 3/8	264	16 1/4	413
1 3/4		1.7500	44.450	5	10 1/8	257	17 1/8	435	4	10 3/4	264	16 1/4	413
	45.00	1.7717	45.000	5	10 1/4	257	17 1/4	435	4	10 3/8	264	16 1/4	413
1 25/32		1.7812	45.242	5	10 1/8	257	17 1/8	435	4	10 3/8	264	16 1/4	413
	46.00	1.8110	46.000	5	10 1/8	257	17 1/8	435	4	10 3/8	264	16 1/4	413
1 13/16		1.8125	46.038	5	10 1/8	257	17 1/8	435	4	10 3/8	264	16 1/4	413
1 27/32		1.8438	46.833	5	10 1/8	257	17 1/8	435	4	10 3/8	264	16 1/4	413
	47.00	1.8504	47.000	5	10 3/8	264	17 3/8	441	4	10 1/2	267	16 1/2	419
1 7/8		1.8750	47.625	5	10 3/8	264	17 3/8	441	4	10 1/2	267	16 1/2	419
	48.00	1.8898	48.000	5	10 3/8	264	17 3/8	441	4	10 1/2	267	16 1/2	419
1 29/32		1.9062	48.417	5	10 3/8	264	17 3/8	441	4	10 1/2	267	16 1/2	419
	49.00	1.9291	49.000	5	10 3/8	264	17 3/8	441	4	10 5/8	270	16 5/8	422
1 15/16		1.9375	49.212	5	10 3/8	264	17 3/8	441	4	10 5/8	270	16 5/8	422
	50.00	1.9625	50.000	5	10 3/8	264	17 3/8	441	4	10 5/8	270	16 5/8	422
1 31/32		1.9688	50.008	5	10 3/8	264	17 3/8	441	4	10 5/8	270	16 5/8	422
2		2.0000	50.800	5	10 3/8	264	17 3/8	441	4	10 5/8	270	16 5/8	422
	51.00	2.0079	51.000	5	10 3/8	264	17 3/8	441	…	…	…	…	…
2 1/32		2.0312	51.592	5	10 3/8	264	17 3/8	441	…	…	…	…	…
	52.00	2.0472	52.000	5	10 1/4	260	17 3/8	441	…	…	…	…	…
2 1/16		2.0625	52.388	5	10 1/4	260	17 3/8	441	…	…	…	…	…
	53.00	2.0866	53.000	5	10 1/4	260	17 3/8	441	…	…	…	…	…
2 3/32		2.0938	53.183	5	10 1/4	260	17 3/8	441	…	…	…	…	…
2 1/8		2.1250	53.975	5	10 1/4	260	17 3/8	441	…	…	…	…	…
	54.00	2.1260	54.000	5	10 1/4	260	17 3/8	441	…	…	…	…	…
2 5/32		2.1562	54.767	5	10 1/4	260	17 3/8	441	…	…	…	…	…
	55.00	2.1654	55.000	5	10 1/4	260	17 3/8	441	…	…	…	…	…
2 3/16		2.1875	55.563	5	10 1/4	260	17 3/4	441	…	…	…	…	…
	56.00	2.2000	56.000	5	10 1/8	257	17 3/8	441	…	…	…	…	…
2 7/32		2.2188	56.358	5	10 1/8	257	17 3/8	441	…	…	…	…	…
	57.00	2.2441	57.000	5	10 1/8	257	17 3/8	441	…	…	…	…	…
2 1/4		2.2500	57.150	5	10 1/8	257	17 3/8	441	…	…	…	…	…
	58.00	2.2835	58.000	5	10 1/8	257	17 3/8	441	…	…	…	…	…
2 5/16		2.3125	58.738	5	10 1/8	257	17 3/8	441	…	…	…	…	…
	59.00	2.3228	59.000	5	10 1/8	257	17 3/8	441	…	…	…	…	…
	60.00	2.3622	60.000	5	10 1/8	257	17 3/8	441	…	…	…	…	…
2 3/8		2.3750	60.325	5	10 1/8	257	17 3/8	441	…	…	…	…	…
	61.00	2.4016	61.000	5	11 1/4	286	18 3/4	476	…	…	…	…	…
2 7/16		2.4375	61.912	5	11 1/4	286	18 3/4	476	…	…	…	…	…
	62.00	2.4409	62.000	5	11 1/4	286	18 3/4	476	…	…	…	…	…
	63.00	2.4803	63.000	5	11 1/4	286	18 3/4	476	…	…	…	…	…
2 1/2		2.5000	63.500	5	11 1/4	286	18 3/4	476	…	…	…	…	…
	64.00	2.5197	64.000	5	11 7/8	302	19 1/2	495	…	…	…	…	…
	65.00	2.5591	65.000	5	11 7/8	302	19 1/2	495	…	…	…	…	…
2 9/16		2.5625	65.088	5	11 7/8	302	19 1/2	495	…	…	…	…	…
	66.00	2.5984	66.000	5	11 7/8	302	19 1/2	495	…	…	…	…	…
2 5/8		2.6250	66.675	5	11 7/8	302	19 1/2	495	…	…	…	…	…
	67.00	2.6378	67.000	5	12 3/4	324	20 3/8	518	…	…	…	…	…
	68.00	2.6772	68.000	5	12 3/4	324	20 3/8	518	…	…	…	…	…
2 11/16		2.6875	68.262	5	12 3/4	324	20 3/8	518	…	…	…	…	…
	69.00	2.7165	69.000	5	12 3/4	324	20 3/8	518	…	…	…	…	…
2 3/4		2.7500	69.850	5	12 3/4	324	20 3/8	518	…	…	…	…	…
	70.00	2.7559	70.000	5	13 3/8	340	21 1/8	537	…	…	…	…	…
	71.00	2.7953	71.000	5	13 3/8	340	21 1/8	537	…	…	…	…	…
2 13/16		2.8125	71.438	5	13 3/8	340	21 1/8	537	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Taper Shank Twist Drills Fractional and Metric Sizes** *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*				Regular Shank					Larger or Smaller Shank[a]				
		Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Fraction	mm	Decimal Inch	mm		Inch	mm	Inch	mm		Inch	mm	Inch	mm
	72.00	2.8346	72.000	5	13 3/8	340	21 1/8	537	…	…	…	…	…
	73.00	2.8740	73.000	5	13 3/8	340	21 1/8	537	…	…	…	…	…
2 7/8		2.8750	73.025	5	13 3/8	340	21 1/8	537	…	…	…	…	…
	74.00	2.9134	74.000	5	14	356	21 3/4	552	…	…	…	…	…
2 15/16		2.9375	74.612	5	14	356	21 3/4	552	…	…	…	…	…
	75.00	2.9528	75.000	5	14	356	21 3/4	552	…	…	…	…	…
	76.00	2.9921	76.000	5	14	356	21 3/4	552	…	…	…	…	…
3		3.0000	76.200	5	14	356	21 3/4	552	…	…	…	…	…
	77.00	3.0315	77.000	6	14 5/8	371	24 1/2	622	5	14 1/4	362	22	559
	78.00	3.0709	78.000	6	14 5/8	371	24 1/2	622	5	14 1/4	362	22	559
3 1/8		3.1250	79.375	6	14 5/8	371	24 1/2	622	5	14 1/4	362	22	559
3 1/4		3.2500	82.550	6	15 1/2	394	25 1/2	648	5	15 1/4	387	23	584
3 1/2		3.5000	88.900	…	…	…	…	…	5	16 1/4	413	24	610

[a] Larger or smaller than regular shank.

Table 6. American National Standard Combined Drills and Countersinks — Plain and Bell Types *ANSI/ASME B94.11M-1993*



Plain Type								
Size Designation	Body Diameter *A*		Drill Diameter *D*		Drill Length *C*		Overall Length *L*	
	Inches	Millimeters	Inches	Millimeters	Inches	Millimeters	Inches	Millimeters
00	1/8	3.18	.025	0.64	.030	0.76	1 1/8	29
0	1/8	3.18	1/32	0.79	.038	0.97	1 1/8	29
1	1/8	3.18	3/64	1.19	3/64	1.19	1 1/4	32
2	3/16	4.76	5/64	1.98	5/64	1.98	1 7/8	48
3	1/4	6.35	7/64	2.78	7/64	2.78	2	51
4	5/16	7.94	1/8	3.18	1/8	3.18	2 1/6	54
5	7/16	11.11	3/16	4.76	3/16	4.76	2 3/4	70
6	1/2	12.70	7/32	5.56	7/32	5.56	3	76
7	5/8	15.88	1/4	6.35	1/4	6.35	3 1/4	83
8	3/4	19.05	5/16	7.94	5/16	7.94	3 1/2	89

Bell Type										
Size Designation	Body Diameter *A*		Drill Diameter *D*		Bell Diameter *E*		Drill Length *C*		Overall Length L	
	Inches	mm	Inches	mm	Inches	mm	Inches	mm	Inches	mm
11	1/8	3.18	3/64	1.19	0.10	2.5	3/64	1.19	1 1/4	32
12	3/16	4.76	1/16	1.59	0.15	3.8	1/16	1.59	1 7/8	48
13	1/4	6.35	3/32	2.38	0.20	5.1	3/32	2.38	2	51
14	5/16	7.94	7/64	2.78	0.25	6.4	7/64	2.78	2 1/6	54
15	7/16	11.11	5/32	3.97	0.35	8.9	5/32	3.97	2 3/4	70
16	1/2	12.70	3/16	4.76	0.40	10.2	3/16	4.76	3	76
17	5/8	15.88	7/32	5.56	0.50	12.7	7/32	5.56	3 1/4	83
18	3/4	19.05	1/4	6.35	0.60	15.2	1/4	6.35	3 1/2	89

Copyright 2004, Industrial Press, Inc., New York, NY



Table 7. American National Standard Three- and Four-Flute Taper Shank Core Drills — Fractional Sizes Only *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*			Three-Flute Drills					Four-Flute Drills				
	Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Inch	Decimal Inch	mm	A	Inch	mm	Inch	mm	A	Inch	mm	Inch	mm
1/4	0.2500	6.350	1	2 7/8	73	6 1/8	156	…	…	…	…	…
9/32	0.2812	7.142	1	3	76	6 1/4	159	…	…	…	…	…
5/16	0.3175	7.938	1	3 1/8	79	6 3/8	162	…	…	…	…	…
11/32	0.3438	8.733	1	3 1/4	83	6 1/2	165	…	…	…	…	…
3/8	0.3750	9.525	1	3 1/2	89	6 3/4	171	…	…	…	…	…
13/32	0.4062	10.319	1	3 5/8	92	7	178	…	…	…	…	…
7/16	0.4375	11.112	1	3 7/8	98	7 1/4	184	…	…	…	…	…
15/32	0.4688	11.908	1	4 1/8	105	7 1/2	190	…	…	…	…	…
1/2	0.5000	12.700	2	4 3/8	111	8 1/4	210	2	4 3/8	111	8 1/4	210
17/32	0.5312	13.492	2	4 5/8	117	8 1/2	216	2	4 5/8	117	8 1/2	216
9/16	0.5625	14.288	2	4 7/8	124	8 3/4	222	2	4 7/8	124	8 3/4	222
19/32	0.5938	15.083	2	4 7/8	124	8 3/4	222	2	4 7/8	124	8 3/4	222
5/8	0.6250	15.815	2	4 7/8	124	8 3/4	222	2	4 7/8	124	8 3/4	222
21/32	0.6562	16.668	2	5 1/8	130	9	229	2	5 1/8	130	9	229
11/16	0.6875	17.462	2	5 3/8	137	9 1/4	235	2	5 3/8	137	9 1/4	235
23/32	0.7188	18.258	2	5 5/8	143	9 1/2	241	2	5 5/8	143	9 1/2	241
3/4	0.7500	19.050	2	5 7/8	149	9 3/4	248	2	5 7/8	149	9 3/4	248
25/32	0.7812	19.842	2	6	152	9 7/8	251	2	6	152	9 7/8	251
13/16	0.8125	20.638	3	6 1/8	156	10 3/4	273	3	6 1/8	156	10 3/4	273
27/32	0.8438	21.433	3	6 1/8	156	10 3/4	273	3	6 1/8	156	10 3/4	273
7/8	0.8750	22.225	3	6 1/8	156	10 3/4	273	3	6 1/8	156	10 3/4	273
29/32	0.9062	23.019	3	6 1/8	156	10 3/4	273	3	6 1/8	156	10 3/4	273
15/16	0.9375	23.812	3	6 1/8	156	10 3/4	273	3	6 1/8	156	10 3/4	273
31/32	0.9688	24.608	3	6 3/8	162	11	279	3	6 3/8	162	11	279
1	1.0000	25.400	3	6 3/8	162	11	279	3	6 3/8	162	11	279
1 1/32	1.0312	26.192	3	6 1/2	165	11 1/8	283	3	6 1/2	165	11 1/8	283
1 1/16	1.0625	26.988	3	6 5/8	168	11 1/4	286	3	6 5/8	168	11 1/4	286
1 3/32	1.0938	27.783	4	6 7/8	175	12 1/2	318	4	6 7/8	175	12 1/2	318
1 1/8	1.1250	28.575	4	7 1/8	181	12 3/4	324	4	7 1/8	181	12 3/4	324
1 5/32	1.1562	29.367	4	7 1/4	184	12 7/8	327	4	7 1/4	184	12 7/8	327
1 3/16	1.1875	30.162	4	7 3/8	187	13	330	4	7 3/8	187	13	330
1 7/32	1.2188	30.958	4	7 1/2	190	13 1/8	333	4	7 1/2	190	13 1/8	333
1 1/4	1.2500	31.750	4	7 7/8	200	13 1/2	343	4	7 7/8	200	13 1/2	343
1 9/32	1.2812	32.542	…	…	…	…	…	4	8 1/2	216	14 1/8	359

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Three- and Four-Flute Taper Shank Core Drills — Fractional Sizes Only *ANSI/ASME B94.11M-1993*

Drill Diameter, *D*			Three-Flute Drills					Four-Flute Drills				
	Equivalent		Morse Taper No.	Flute Length *F*		Overall Length *L*		Morse Taper No.	Flute Length *F*		Overall Length *L*	
Inch	Decimal Inch	mm	A	Inch	mm	Inch	mm	A	Inch	mm	Inch	mm
15/16	1.3125	33.338	…	…	…	…	…	4	8 5/8	219	14 1/4	362
1 11/32	1.3438	34.133	…	…	…	…	…	4	8 3/4	222	14 3/8	365
1 3/8	1.3750	34.925	…	…	…	…	…	4	8 7/8	225	14 1/2	368
1 13/32	1.4062	35.717	…	…	…	…	…	4	9	229	14 5/8	371
1 7/16	1.4375	36.512	…	…	…	…	…	4	9 1/8	232	14 3/4	375
1 15/32	1.4688	37.306	…	…	…	…	…	4	9 1/4	235	14 7/8	378
1 1/2	1.5000	38.100	…	…	…	…	…	4	9 3/8	238	15	381
1 17/32	1.5312	38.892	…	…	…	…	…	5	9 3/8	238	16 3/8	416
1 9/16	1.5675	39.688	…	…	…	…	…	5	9 5/8	244	16 5/8	422
1 19/32	1.5938	40.483	…	…	…	…	…	5	9 7/8	251	16 7/8	429
1 5/8	1.6250	41.275	…	…	…	…	…	5	10	254	17	432
1 21/32	1.6562	42.067	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 11/16	1.6875	42.862	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 23/32	1.7188	43.658	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 3/4	1.7500	44.450	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 25/32	1.7812	45.244	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 13/16	1.8125	46.038	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 27/32	1.8438	46.833	…	…	…	…	…	5	10 1/8	257	17 1/8	435
1 7/8	1.8750	47.625	…	…	…	…	…	5	10 3/8	264	17 3/8	441
1 29/32	1.9062	48.417	…	…	…	…	…	5	10 3/8	264	17 3/8	441
1 15/16	1.9375	49.212	…	…	…	…	…	5	10 3/8	264	17 3/8	441
1 31/32	1.9688	50.008	…	…	…	…	…	5	10 3/8	264	17 3/8	441
2	2.0000	50.800	…	…	…	…	…	5	10 3/8	264	17 3/8	441
2 1/8	2.1250	53.975	…	…	…	…	…	5	10 1/4	260	17 3/8	441
2 1/4	2.2500	57.150	…	…	…	…	…	5	10 1/8	257	17 3/8	441
2 3/8	2.3750	60.325	…	…	…	…	…	5	10 1/8	257	17 3/8	441
2 1/2	2.5000	63.500	…	…	…	…	…	5	11 1/4	286	18 3/4	476

Table 8. American National Standard Drill Drivers — Split-Sleeve, Collet Type *ANSI B94.35-1972 (R1995)*



Taper Number	*G* Overall Length	*H* Diameter at Gage Line	*J* Taper per Foot[a]	*K* Length to Gage Line	*L* Driver Projection
0[b]	2.38	0.356	0.62460	2.22	0.16
1	2.62	0.475	0.59858	2.44	0.19
2	3.19	0.700	0.59941	2.94	0.25

[a] Taper rate in accordance with ANSI/ASME B5.10-1994 (R2002), Machine Tapers.

[b] Size 0 is not an American National Standard but is included here to meet special needs.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ANSI Three- and Four-Flute Straight Shank Core Drills — Fractional Sizes Only *ANSI/ASME B94.11M-1993*



Drill Diameter 11/32″ (8.733 mm) and Smaller



Drill Diameter 3/8″ (9.525 mm) and Larger

Nominal Shank Size is same as Nominal Drill Size

Drill Diameter, *D*			Three-Flute Drills				Four-Flute Drills			
	Equivalent		Flute Length		Overall Length		Flute Length		Overall Length	
			F		*L*		*F*		*L*	
Inch	Decimal Inch	mm	Inch	mm	Inch	mm	Inch	mm	Inch	mm
1/4	0.2500	6.350	3 3/4	95	6 1/8	156	…	…	…	…
9/32	0.2812	7.142	3 7/8	98	6 1/4	159	…	…	…	…
5/16	0.3125	7.938	4	102	6 3/8	162	…	…	…	…
11/32	0.3438	8.733	4 1/8	105	6 1/2	165	…	…	…	…
3/8	0.3750	9.525	4 1/8	105	6 3/4	171	…	…	…	…
13/32	0.4062	10.317	4 3/8	111	7	178	…	…	…	…
7/16	0.4375	11.112	4 5/8	117	7 1/4	184	…	…	…	…
15/32	0.4688	11.908	4 3/4	121	7 1/2	190	…	…	…	…
1/2	0.5000	12.700	4 3/4	121	7 3/4	197	4 3/4	121	7 3/4	197
17/32	0.5312	13.492	4 3/4	121	8	203	4 3/4	121	8	203
9/16	0.5625	14.288	4 7/8	124	8 1/4	210	4 7/8	124	8 1/4	210
19/32	0.5938	15.083	4 7/8	124	8 3/4	222	4 7/8	124	8 3/4	222
5/8	0.6250	15.875	4 7/8	124	8 3/4	222	4 7/8	124	8 3/4	222
21/32	0.6562	16.667	5 1/8	130	9	229	5 1/8	130	9	229
11/16	0.6875	17.462	5 3/8	137	9 1/4	235	5 3/8	137	9 1/4	235
23/32	0.7188	18.258	…	…	…	…	5 5/8	143	9 1/2	241
3/4	0.7500	19.050	5 7/8	149	9 3/4	248	5 7/8	149	9 3/4	248
25/32	0.7812	19.842	…	…	…	…	6	152	9 7/8	251
13/16	0.8125	20.638	…	…	…	…	6 1/8	156	10	254
27/32	0.8438	21.433	…	…	…	…	6 1/8	156	10	254
7/8	0.8750	22.225	…	…	…	…	6 1/8	156	10	254
29/32	0.9062	23.017	…	…	…	…	6 1/8	156	10	254
15/16	0.9375	23.812	…	…	…	…	6 1/8	156	10 3/4	273
31/32	0.9688	24.608	…	…	…	…	6 3/8	162	11	279
1	1.0000	25.400	…	…	…	…	6 3/8	162	11	279
1 1/32	1.0312	26.192	…	…	…	…	6 1/2	165	11 1/8	283
1 1/16	1.0625	26.988	…	…	…	…	6 5/8	168	11 1/4	286
1 3/32	1.0938	27.783	…	…	…	…	6 7/8	175	11 1/2	292
1 1/8	1.1250	28.575	…	…	…	…	7 1/8	181	11 3/4	298
1 1/4	1.2500	31.750	…	…	…	…	7 7/8	200	12 1/2	318

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Length of Point on Twist Drills and Centering Tools

Size of Drill	Decimal Equivalent	Length of Point when Included Angle = 90°	Length of Point when Included Angle = 118°	Size of Drill	Decimal Equivalent	Length of Point when Included Angle = 90°	Length of Point when Included Angle = 118°	Size or Dia. of Drill	Decimal Equivalent	Length of Point when Included Angle = 90°	Length of Point when Included Angle = 118°	Dia. of Drill	Decimal Equivalent	Length of Point when Included Angle = 90°	Length of Point when Included Angle = 118°
60	0.0400	0.020	0.012	37	0.1040	0.052	0.031	14	0.1820	0.091	0.055	3/8	0.3750	0.188	0.113
59	0.0410	0.021	0.012	36	0.1065	0.054	0.032	13	0.1850	0.093	0.056	25/64	0.3906	0.195	0.117
58	0.0420	0.021	0.013	35	0.1100	0.055	0.033	12	0.1890	0.095	0.057	13/32	0.4063	0.203	0.122
57	0.0430	0.022	0.013	34	0.1110	0.056	0.033	11	0.1910	0.096	0.057	27/64	0.4219	0.211	0.127
56	0.0465	0.023	0.014	33	0.1130	0.057	0.034	10	0.1935	0.097	0.058	7/16	0.4375	0.219	0.131
55	0.0520	0.026	0.016	32	0.1160	0.058	0.035	9	0.1960	0.098	0.059	29/64	0.4531	0.227	0.136
54	0.0550	0.028	0.017	31	0.1200	0.060	0.036	8	0.1990	0.100	0.060	15/32	0.4688	0.234	0.141
53	0.0595	0.030	0.018	30	0.1285	0.065	0.039	7	0.2010	0.101	0.060	31/64	0.4844	0.242	0.145
52	0.0635	0.032	0.019	29	0.1360	0.068	0.041	6	0.2040	0.102	0.061	1/2	0.5000	0.250	0.150
51	0.0670	0.034	0.020	28	0.1405	0.070	0.042	5	0.2055	0.103	0.062	33/64	0.5156	0.258	0.155
50	0.0700	0.035	0.021	27	0.1440	0.072	0.043	4	0.2090	0.105	0.063	17/32	0.5313	0.266	0.159
49	0.0730	0.037	0.022	26	0.1470	0.074	0.044	3	0.2130	0.107	0.064	35/64	0.5469	0.273	0.164
48	0.0760	0.038	0.023	25	0.1495	0.075	0.045	2	0.2210	0.111	0.067	9/16	0.5625	0.281	0.169
47	0.0785	0.040	0.024	24	0.1520	0.076	0.046	1	0.2280	0.114	0.068	37/64	0.5781	0.289	0.173
46	0.0810	0.041	0.024	23	0.1540	0.077	0.046	15/64	0.2344	0.117	0.070	19/32	0.5938	0.297	0.178
45	0.0820	0.041	0.025	22	0.1570	0.079	0.047	1/4	0.2500	0.125	0.075	39/64	0.6094	0.305	0.183
44	0.0860	0.043	0.026	21	0.1590	0.080	0.048	17/64	0.2656	0.133	0.080	5/8	0.6250	0.313	0.188
43	0.0890	0.045	0.027	20	0.1610	0.081	0.048	9/32	0.2813	0.141	0.084	41/64	0.6406	0.320	0.192
42	0.0935	0.047	0.028	19	0.1660	0.083	0.050	19/64	0.2969	0.148	0.089	21/32	0.6563	0.328	0.197
41	0.0960	0.048	0.029	18	0.1695	0.085	0.051	5/16	0.3125	0.156	0.094	43/64	0.6719	0.336	0.202
40	0.0980	0.049	0.029	17	0.1730	0.087	0.052	21/64	0.3281	0.164	0.098	11/16	0.6875	0.344	0.206
39	0.0995	0.050	0.030	16	0.1770	0.089	0.053	11/32	0.3438	0.171	0.103	23/32	0.7188	0.359	0.216
38	0.1015	0.051	0.030	15	0.1800	0.090	0.054	23/64	0.3594	0.180	0.108	3/4	0.7500	0.375	0.225

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Combined Drills and Countersinks (Center Drills).— BS 328: Part 2: 1972 (1990) provides dimensions of combined drills and countersinks for center holes. Three types of drill and countersink combinations are shown in this standard but are not given here. These three types will produce center holes without protecting chamfers, with protecting chamfers, and with protecting chamfers of radius form.

Drill Drivers—Split-Sleeve, Collet Type.— American National Standard ANSI B94.35-1972 (R1995) covers split-sleeve, collet-type drivers for driving straight shank drills, reamers, and similar tools, without tangs from 0.0390-inch through 0.1220-inch diameter, and with tangs from 0.1250-inch through 0.7500-inch diameter, including metric sizes.

For sizes 0.0390 through 0.0595 inch, the standard taper number is 1 and the optional taper number is 0. For sizes 0.0610 through 0.1875 inch, the standard taper number is 1, first optional taper number is 0, and second optional taper number is 2. For sizes 0.1890 through 0.2520 inch, the standard taper number is 1, first optional taper number is 2, and second optional taper number is 0. For sizes 0.2570 through 0.3750 inch, the standard taper number is 1 and the optional taper number is 2. For sizes 0.3860 through 0.5625 inch, the standard taper number is 2 and the optional taper number is 3. For sizes 0.5781 through 0.7500 inch, the standard taper number is 3 and the optional taper number is 4.

The depth *B* that the drill enters the driver is 0.44 inch for sizes 0.0390 through 0.0781 inch; 0.50 inch for sizes 0.0785 through 0.0938 inch; 0.56 inch for sizes 0.0960 through 0.1094 inch; 0.62 inch for sizes 0.1100 through 0.1220 inch; 0.75 inch for sizes 0.1250 through 0.1875 inch; 0.88 inch for sizes 0.1890 through 0.2500 inch; 1.00 inch for sizes 0.2520 through 0.3125 inch; 1.12 inches for sizes 0.3160 through 0.3750 inch; 1.25 inches for sizes 0.3860 through 0.4688 inch; 1.31 inches for sizes 0.4844 through 0.5625 inch; 1.47 inches for sizes 0.5781 through 0.6562 inch; and 1.62 inches for sizes 0.6719 through 0.7500 inch.

British Standard Metric Twist Drills.— BS 328: Part 1:1959 (incorporating amendments issued March 1960 and March 1964) covers twist drills made to inch and metric dimensions that are intended for general engineering purposes. ISO recommendations are taken into account. The accompanying tables give the standard metric sizes of Morse taper shank twist drills and core drills, parallel shank jobbing and long series drills, and stub drills.

All drills are right-hand cutting unless otherwise specified, and normal, slow, or quick helix angles may be provided. A "back-taper" is ground on the diameter from point to shank to provide longitudinal clearance. Core drills may have three or four flutes, and are intended for opening up cast holes or enlarging machined holes, for example. The parallel shank jobber, and long series drills, and stub drills are made without driving tenons.

Morse taper shank drills with oversize dimensions are also listed, and Table 11 shows metric drill sizes superseding gage and letter size drills, which are now obsolete in Britain. To meet special requirements, the Standard lists nonstandard sizes for the various types of drills.

The limits of tolerance on cutting diameters, as measured across the lands at the outer corners of a drill, shall be h8, in accordance with BS 1916, Limits and Fits for Engineering (Part I, Limits and Tolerances), and Table 14 shows the values common to the different types of drills mentioned before.

The drills shall be permanently and legibly marked whenever possible, preferably by rolling, showing the size, and the manufacturer's name or trademark. If they are made from high-speed steel, they shall be marked with the letters H.S. where practicable.

Drill Elements: The following definitions of drill elements are given.

Axis: The longitudinal center line.

Body: That portion of the drill extending from the extreme cutting end to the commencement of the shank.

Copyright 2004, Industrial Press, Inc., New York, NY

Shank: That portion of the drill by which it is held and driven.

Flutes: The grooves in the body of the drill that provide lips and permit the removal of chips and allow cutting fluid to reach the lips.

Web (Core): The central portion of the drill situated between the roots of the flutes and extending from the point end toward the shank; the point end of the web or core forms the chisel edge.

Lands: The cylindrical-ground surfaces on the leading edges of the drill flutes. The width of the land is measured at right angles to the flute helix.

Body Clearance: The portion of the body surface that is reduced in diameter to provide diametral clearance.

Heel: The edge formed by the intersection of the flute surface and the body clearance.

Point: The sharpened end of the drill, consisting of all that part of the drill that is shaped to produce lips, faces, flanks, and chisel edge.

Face: That portion of the flute surface adjacent to the lip on which the chip impinges as it is cut from the work.

Flank: The surface on a drill point that extends behind the lip to the following flute.

Lip (Cutting Edge): The edge formed by the intersection of the flank and face.

Relative Lip Height: The relative position of the lips measured at the outer corners in a direction parallel to the drill axis.

Outer Corner: The corner formed by the intersection of the lip and the leading edge of the land.

Chisel Edge: The edge formed by the intersection of the flanks.

Chisel Edge Corner: The corner formed by the intersection of a lip and the chisel edge.

Table 11. British Standard Drills — Metric Sizes Superseding Gauge and Letter Sizes *BS 328: Part 1:1959, Appendix B*

Obsolete Drill Size	Recommended MetricSize (mm)	Obsolete Drill Size	Recommended Metric Size (mm)	Obsolete Drill Size	Recommended Metric Size (mm)	Obsolete Drill Size	Recommended Metric Size (mm)	Obsolete Drill Size	Recommended Metric Size (mm)
80	0.35	58	1.05	36	2.70	14	4.60	I	6.90
79	0.38	57	1.10	35	2.80	13	4.70	J	7.00
78	0.40	56	1/64 in.	34	2.80	12	4.80	K	9/32 in.
77	0.45	55	1.30	33	2.85	11	4.90	L	7.40
76	0.50	54	1.40	32	2.95	10	4.90	M	7.50
75	0.52	53	1.50	31	3.00	9	5.00	N	7.70
74	0.58	52	1.60	30	3.30	8	5.10	O	8.00
73	0.60	51	1.70	29	3.50	7	5.10	P	8.20
72	0.65	50	1.80	28	9/64 in.	6	5.20	Q	8.40
71	0.65	49	1.85	27	3.70	5	5.20	R	8.60
70	0.70	48	1.95	26	3.70	4	5.30	S	8.80
69	0.75	47	2.00	25	3.80	3	5.40	T	9.10
68	1/32 in.	46	2.05	24	3.90	2	5.60	U	9.30
67	0.82	45	2.10	23	3.90	1	5.80	V	3/8 in.
66	0.85	44	2.20	22	4.00	A	15/64 in.	W	9.80
65	0.90	43	2.25	21	4.00	B	6.00	X	10.10
64	0.92	42	3/32 in.	20	4.10	C	6.10	Y	10.30
63	0.95	41	2.45	19	4.20	D	6.20	Z	10.50
62	0.98	40	2.50	18	4.30	E	1/4 in.	…	…
61	1.00	39	2.55	17	4.40	F	6.50	…	…
60	1.00	38	2.60	16	4.50	G	6.60	…	…
59	1.05	37	2.65	15	4.60	H	17/64 in.	…	…

Gauge and letter size drills are now obsolete in the United Kingdom and should not be used in the production of new designs. The table is given to assist users in changing over to the recommended standard sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. British Standard Morse Taper Shank Twist Drills and Core Drills — Standard Metric Sizes *BS 328: Part 1:1959*

Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length
3.00	33	114	16.75	125	223	30.25	180	301
3.20	36	117	17.00			30.50		
3.50	39	120	17.25	130	228	30.75		
3.80	43	123	17.50			31.00		
4.00			17.75			31.25		
4.20			18.00			31.50		
4.50	47	128	18.25	135	233	31.75	185	306
4.80	52	133	18.50			32.00	185	334
5.00			18.75			32.50		
5.20			19.00			33.00		
5.50	57	138	19.25	140	238	33.50	190	339
5.80			19.50			34.00		
6.00			19.75			34.50		
6.20	63	144	20.00			35.00		
6.50			20.25	145	243	35.50		
6.80	69	150	20.50			36.00	195	344
7.00			20.75			36.50		
7.20			21.00			37.00		
7.50			21.25	150	248	37.50		
7.80	75	156	21.50			38.00	200	349
8.00			21.75			38.50		
8.20			22.00			39.00		
8.50			22.25			39.50		
8.80	81	162	22.50	155	253	40.00	205	354
9.00			22.75			40.50		
9.20			23.00			41.00		
9.50			23.25	155	276	41.50		
9.80	87	168	23.50			42.00		
10.00			23.75	160	281	42.50	210	359
10.20			24.00			43.00		
10.50			24.25			43.50		
10.80	94	175	24.50			44.00		
11.00			24.75			44.50		
11.20			25.00			45.00		
11.50			25.25	165	286	45.50	215	364
11.80			25.50			46.00		
12.00	101	182	25.75			46.50		
12.20			26.00			47.00		
12.50			26.25			47.50		
12.80			26.50			48.00	220	369
13.00			26.75	170	291	48.50		
13.20			27.00			49.00		
13.50	108	189	27.25			49.50		
13.80			27.50			50.00		
14.00			27.75			50.50	225	374
14.25	114	212	28.00			51.00	225	412
14.50			28.25	175	296	52.00		
14.75			28.50			53.00		
15.00			28.75			54.00	230	417
15.25	120	218	29.00			55.00		
15.50			29.25			56.00		
15.75			29.50	175	296	57.00	235	422
16.00			29.75			58.00		
16.25	125	223	30.00			59.00		
16.50						60.00		

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **British Standard Morse Taper Shank Twist Drills and Core Drills — Standard Metric Sizes** *BS 328: Part 1:1959*

Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length
61.00			76.00	260	477	91.00		
62.00	240	427	77.00			92.00		
63.00			78.00	260	514	93.00	275	529
64.00			79.00			94.00		
65.00	245	432	80.00			95.00		
66.00			81.00			96.00		
67.00			82.00			97.00		
68.00			83.00	265	519	98.00	280	534
69.00	250	437	84.00			99.00		
70.00			85.00			100.00		
71.00	250	437	86.00					
72.00			87.00					
73.00	255	442	88.00	270	524			
74.00			89.00					
75.00			90.00					

All dimensions are in millimeters. Tolerances on diameters are given in the table below.

Table 13, shows twist drills that may be supplied with the shank and length oversize, but they should be regarded as nonpreferred.

The Morse taper shanks of these twist and core drills are as follows: 3.00 to 14.00 mm diameter, M.T. No. 1; 14.25 to 23.00 mm diameter, M.T. No. 2; 23.25 to 31.50 mm diameter, M.T. No. 3; 31.75 to 50.50 mm diameter, M.T. No. 4; 51.00 to 76.00 mm diameter, M.T. No. 5; 77.00 to 100.00 mm diameter, M.T. No. 6.

Table 13. British Standard Morse Taper Shank Twist Drills — Metric Oversize Shank and Length Series *BS 328: Part 1:1959*

Dia. Range	Overall Length	M. T. No.	Dia. Range	Overall Length	M. T. No.	Dia. Range	Overall Length	M. T. No.
12.00 to 13.20	199	2	22.50 to 23.00	276	3	45.50 to 47.50	402	5
13.50 to 14.00	206	2	26.75 to 28.00	319	4	48.00 to 50.00	407	5
18.25 to 19.00	256	3	29.00 to 30.00	324	4	50.50	412	5
19.25 to 20.00	251	3	30.25 to 31.50	329	4	64.00 to 67.00	499	6
20.25 to 21.00	266	3	40.50 to 42.50	392	5	68.00 to 71.00	504	6
21.25 to 22.25	271	3	43.00 to 45.00	397	5	72.00 to 75.00	509	6

Diameters and lengths are given in millimeters. For the individual sizes within the diameter ranges given, see Table 12.

This series of drills should be regarded as non-preferred.

Table 14. British Standard Limits of Tolerance on Diameter for Twist Drills and Core Drills — Metric Series *BS 328: Part 1:1959*

Drill Size (Diameter measured across lands at outer corners)	Tolerance (h8)
0 to 1 inclusive	Plus 0.000 to Minus 0.014
Over 1 to 3 inclusive	Plus 0.000 to Minus 0.014
Over 3 to 6 inclusive	Plus 0.000 to Minus 0.018
Over 6 to 10 inclusive	Plus 0.000 to Minus 0.022
Over 10 to 18 inclusive	Plus 0.000 to Minus 0.027
Over 18 to 30 inclusive	Plus 0.000 to Minus 0.033
Over 30 to 50 inclusive	Plus 0.000 to Minus 0.039
Over 50 to 80 inclusive	Plus 0.000 to Minus 0.046
Over 80 to 120 inclusive	Plus 0.000 to Minus 0.054

All dimensions are given in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. British Standard Parallel Shank Jobber Series Twist Drills — Standard Metric Sizes *BS 328: Part 1:1959*

Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length
0.20	2.5	19	1.75	22	46	5.40	57	93	10.20	87	133
0.22			1.80			5.50			10.30		
0.25	3.0	19	1.85			5.60			10.40		
0.28			1.90			5.70			10.50		
0.30	4	19	1.95	24	49	5.80			10.60		
0.32			2.00			5.90			10.70	94	142
0.35			2.05			6.00			10.80		
0.38			2.10			6.10	63	101	10.90		
0.40	5	20	2.15	27	53	6.20			11.00		
0.42			2.20			6.30			11.10		
0.45			2.25			6.40			11.20		
0.48			2.30			6.50			11.30		
0.50	6	22	2.35			6.60			11.40		
0.52			2.40	30	57	6.70			11.50		
0.55	7	24	2.45			6.80	69	109	11.60		
0.58			2.50			6.90			11.70		
0.60			2.55			7.00			11.80		
0.62	8	26	2.60			7.10			11.90	101	151
0.65			2.65			7.20			12.00		
0.68	9	28	2.70	33	61	7.30			12.10		
0.70			2.75			7.40			12.20		
0.72			2.80			7.50			12.30		
0.75			2.85			7.60	75	117	12.40		
0.78	10	30	2.90			7.70			12.50		
0.80			2.95			7.80			12.60		
0.82			3.00			7.90			12.70		
0.85			3.10	36	65	8.00			12.80		
0.88	11	32	3.20			8.10			12.90		
0.90			3.30			8.20			13.00		
0.92			3.40	39	70	8.30			13.10		
0.95			3.50			8.40			13.20		
0.98	12	34	3.60			8.50			13.30	108	160
1.00			3.70			8.60	81	125	13.40		
1.05			3.80	43	75	8.70			13.50		
1.10	14	36	3.90			8.80			13.60		
1.15			4.00			8.90			13.70		
1.20	16	38	4.10			9.00			13.80		
1.25			4.20			9.10			13.90		
1.30			4.30	47	80	9.20			14.00		
	18	40	4.40			9.30					
1.35			4.50			9.40			14.25	114	169
1.40			4.60			9.50			14.50		
1.45			4.70						14.75		
1.50			4.80	52	86	9.60	87	133	15.00		
	20	43	4.90			9.70					
1.55			5.00			9.80			15.25	120	178
1.60			5.10			9.90			15.50		
1.65			5.20			10.00			15.75		
1.70			5.30			10.10			16.00		

All dimensions are in millimeters. Tolerances on diameters are given in Table 14.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. British Standard Parallel Shank Long Series Twist Drills — Standard Metric Sizes *BS 328: Part 1:1959*

Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length
2.00	56	85	6.80	102	156	12.70	134	205
2.05			6.90			12.80		
2.10			7.00			12.90		
2.15	59	90	7.10			13.00		
2.20			7.20			13.10		
2.25			7.30			13.20		
2.30			7.40			13.30	140	214
2.35			7.50			13.40		
2.40	62	95	7.60	109	165	13.50		
2.45			7.70			13.60		
2.50			7.80			13.70		
2.55			7.90			13.80		
2.60			8.00			13.90		
2.65			8.10			14.00		
2.70	66	100	8.20			14.25	144	220
2.75			8.30			14.50		
2.80			8.40			14.75		
2.85			8.50			15.00		
2.90			8.60	115	175	15.25	149	227
2.95			8.70			15.50		
3.00			8.80			15.75		
3.10	69	106	8.90			16.00		
3.20			9.00			16.25	154	235
3.30			9.10			16.50		
3.40	73	112	9.20			16.75		
3.50			9.30			17.00		
3.60			9.40			17.25	158	241
3.70			9.50			17.50		
3.80	78	119	9.60	121	184	17.75		
3.90			9.70			18.00		
4.00			9.80			18.25	162	247
4.10			9.90			18.50		
4.20			10.00			18.75		
			10.10			19.00		
4.30	82	126	10.20			19.25	166	254
4.40			10.30			19.50		
4.50			10.40			19.75		
4.60			10.50			20.00		
4.70			10.60					
4.80	87	132	10.70	128	195	20.25	171	261
4.90			10.80			20.50		
5.00			10.90			20.75		
5.10			11.00			21.00		
5.20			11.10			21.25	176	268
5.30			11.20			21.50		
5.40	91	139	11.30			21.75		
5.50			11.40			22.00		
5.60			11.50			22.25		
5.70			11.60			22.50	180	275
5.80			11.70			22.75		
5.90			11.80			23.00		
6.00			11.90	134	205	23.25		
6.10	97	148	12.00			23.50		
6.20			12.10			23.75	185	282
6.30			12.20			24.00		
6.40			12.30			24.25		
6.50			12.40			24.50		
6.60			12.50			24.75		
6.70			12.60			25.00		

All dimensions are in millimeters. Tolerances on diameters are given in Table 14.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. British Standard Stub Drills — Metric Sizes *BS 328: Part 1:1959*

Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length	Diameter	Flute Length	Overall Length
0.50	3	20	5.00	26	62	9.50	40	84	14.00	54	107
0.80	5	24	5.20			9.80	43	89	14.50	56	111
1.00	6	26	5.50	28	66	10.00			15.00		
1.20	8	30	5.80			10.20			15.50	58	115
1.50	9	32	6.00			10.50			16.00		
1.80	11	36									
2.00	12	38	6.20	31	70	10.80	47	95	16.50	60	119
2.20	13	40	6.50			11.00			17.00		
2.50	14	43	6.80	34	74	11.20			17.50	62	123
2.80	16	46	7.00			11.50			18.00		
3.00			7.20			11.80			18.50	64	127
3.20	18	49	7.50			12.00	51	102	19.00		
3.50	20	52	7.80	37	79	12.20			19.50	66	131
			8.00			12.50			20.00		
3.80	22	55	8.20			12.80			21.00	68	136
4.00			8.50			13.00			22.00	70	141
4.20			8.80			13.20			23.00	72	146
4.50	24	58	9.00	40	84	13.50	54	107	24.00	75	151
4.80	26	62	9.20			13.80			25.00		

All dimensions are given in millimeters. Tolerances on diameters are given in Table 14.

Steels for Twist Drills.— Twist drill steels need good toughness, abrasion resistance, and ability to resist softening due to heat generated by cutting. The amount of heat generated indicates the type of steel that should be used.

Carbon Tool Steel may be used where little heat is generated during drilling.

High-Speed Steel is preferred because of its combination of red hardness and wear resistance, which permit higher operating speeds and increased productivity. Optimum properties can be obtained by selection of alloy analysis and heat treatment.

Cobalt High-Speed Steel alloys have higher red hardness than standard high-speed steels, permitting drilling of materials such as heat-resistant alloys and materials with hardness greater than Rockwell 38 C. These high-speed drills can withstand cutting speeds beyond the range of conventional high-speed-steel drills and have superior resistance to abrasion but are not equal to tungsten-carbide tipped tools.

Accuracy of Drilled Holes.— Normally the diameter of drilled holes is not given a tolerance; the size of the hole is expected to be as close to the drill size as can be obtained.

The accuracy of holes drilled with a two-fluted twist drill is influenced by many factors, which include: the accuracy of the drill point; the size of the drill; length and shape of the chisel edge; whether or not a bushing is used to guide the drill; the work material; length of the drill; runout of the spindle and the chuck; rigidity of the machine tool, workpiece, and the setup; and also the cutting fluid used, if any.

The diameter of the drilled holes will be oversize in most materials. The table *Oversize Diameters in Drilling* on page 885 provides the results of tests reported by The United States Cutting Tool Institute in which the diameters of over 2800 holes drilled in steel and cast iron were measured. The values in this table indicate what might be expected under average shop conditions; however, when the drill point is accurately ground and the other machining conditions are correct, the resulting hole size is more likely to be between the mean and average minimum values given in this table. If the drill is ground and used incorrectly, holes that are even larger than the average maximum values can result.

Copyright 2004, Industrial Press, Inc., New York, NY

Oversize Diameters in Drilling

Drill Dia., Inch	Amount Oversize, Inch			Drill Dia., Inch	Amount Oversize, Inch		
	Average Max.	Mean	Average Min.		Average Max.	Mean	Average Min.
1/16	0.002	0.0015	0.001	1/2	0.008	0.005	0.003
1/8	0.0045	0.003	0.001	3/4	0.008	0.005	0.003
1/4	0.0065	0.004	0.0025	1	0.009	0.007	0.004

Courtesy of The United States Cutting Tool Institute

Some conditions will cause the drilled hole to be undersize. For example, holes drilled in light metals and in other materials having a high coefficient of thermal expansion such as plastics, may contract to a size that is smaller than the diameter of the drill as the material surrounding the hole is cooled after having been heated by the drilling. The elastic action of the material surrounding the hole may also cause the drilled hole to be undersize when drilling high strength materials with a drill that is dull at its outer corner.

The accuracy of the drill point has a great effect on the accuracy of the drilled hole. An inaccurately ground twist drill will produce holes that are excessively over-size. The drill point must be symmetrical; i.e., the point angles must be equal, as well as the lip lengths and the axial height of the lips. Any alterations to the lips or to the chisel edge, such as thinning the web, must be done carefully to preserve the symmetry of the drill point. Adequate relief should be provided behind the chisel edge to prevent heel drag. On conventionally ground drill points this relief can be estimated by the chisel edge angle.

When drilling a hole, as the drill point starts to enter the workpiece, the drill will be unstable and will tend to wander. Then as the body of the drill enters the hole the drill will tend to stabilize. The result of this action is a tendency to drill a bellmouth shape in the hole at the entrance and perhaps beyond. Factors contributing to bellmouthing are: an unsymmetrically ground drill point; a large chisel edge length; inadequate relief behind the chisel edge; runout of the spindle and the chuck; using a slender drill that will bend easily; and lack of rigidity of the machine tool, workpiece, or the setup. Correcting these conditions as required will reduce the tendency for bellmouthing to occur and improve the accuracy of the hole diameter and its straightness. Starting the hole with a short stiff drill, such as a center drill, will quickly stabilize the drill that follows and reduce or eliminate bellmouthing; this procedure should always be used when drilling in a lathe, where the work is rotating. Bellmouthing can also be eliminated almost entirely and the accuracy of the hole improved by using a close fitting drill jig bushing placed close to the workpiece. Although specific recommendations cannot be made, many cutting fluids will help to increase the accuracy of the diameters of drilled holes. Double margin twist drills, available in the smaller sizes, will drill a more accurate hole than conventional twist drills having only a single margin at the leading edge of the land. The second land, located on the trailing edge of each land, provides greater stability in the drill bushing and in the hole. These drills are especially useful in drilling intersecting off-center holes. Single and double margin step drills, also available in the smaller sizes, will produce very accurate drilled holes, which are usually less than 0.002 inch larger than the drill size.

Counterboring.— Counterboring (called spot-facing if the depth is shallow) is the enlargement of a previously formed hole. Counterbores for screw holes are generally made in sets. Each set contains three counterbores: one with the body of the size of the screw head and the pilot the size of the hole to admit the body of the screw; one with the body the size of the head of the screw and the pilot the size of the tap drill; and the third with the body the size of the body of the screw and the pilot the size of the tap drill. Counterbores are usually provided with helical flutes to provide positive effective rake on the cutting edges. The four flutes are so positioned that the end teeth cut ahead of center to provide a shearing action and eliminate chatter in the cut. Three designs are most common: solid, two-piece, and three-piece. Solid designs have the body, cutter, and pilot all in one piece. Two-piece designs have an integral shank and counterbore cutter, with an interchangeable pilot, and provide true concentricity of the cutter diameter with the shank, but allowing use of various

Copyright 2004, Industrial Press, Inc., New York, NY

pilot diameters. Three-piece counterbores have separate holder, counterbore cutter, and pilot, so that a holder will take any size of counterbore cutter. Each counterbore cutter, in turn, can be fitted with any suitable size diameter of pilot. Counterbores for brass are fluted straight.

Counterbores with Interchangeable Cutters and Guides



No. of Holder	No. of Morse Taper Shank	Range of Cutter Diameters, *A*	Range of Pilot Diameters, *B*	Total Length, *C*	Length of Cutter Body, *D*	Length of Pilot, *E*	Dia. of Shank, *F*
1	1 or 2	¾-1 1/16	½-¾	7¼	1	⅝	¾
2	2 or 3	1⅛-1 9/16	1 1/16-1⅛	9½	1⅜	⅞	1⅛
3	3 or 4	1⅝-2 1/16	⅞-1⅝	12½	1¾	1⅛	1⅝
4	4 or 5	2 1/16-3½	1-2⅛	15	2¼	1⅜	2⅛

Solid Counterbores with Integral Pilot

Counterbore Diameters	Pilot Diameters			Straight Shank Diameter	Overall Length	
	Nominal	+1/64	+1/32		Short	Long
13/32	¼	17/64	9/32	⅜	3½	5½
½	5/16	21/64	11/32	⅜	3½	5½
19/32	⅜	25/64	13/32	½	4	6
11/16	7/16	29/64	15/32	½	4	6
25/32	½	33/64	17/32	½	5	7
0.110	0.060	0.076	…	7/64	2½	…
0.133	0.073	0.089	…	⅛	2½	…
0.155	0.086	0.102	…	5/32	2½	…
0.176	0.099	0.115	…	11/64	2½	…
0.198	0.112	0.128	…	3/16	2½	…
0.220	0.125	0.141	…	3/16	2½	…
0.241	0.138	0.154	…	7/32	2½	…
0.285	0.164	0.180	…	¼	2½	…
0.327	0.190	0.206	…	9/32	2¾	…
0.372	0.216	0.232	…	5/16	2¾	…

All dimensions are in inches.

Small counterbores are often made with three flutes, but should then have the size plainly stamped on them before fluting, as they cannot afterwards be conveniently measured. The flutes should be deep enough to come below the surface of the pilot. The counterbore should be relieved on the end of the body only, and not on the cylindrical surface. To facilitate the relieving process, a small neck is turned between the guide and the body for clearance. The amount of clearance on the cutting edges is, for general work, from 4 to 5 degrees. The accompanying table gives dimensions for straight shank counterbores.

Three Piece Counterbores.— Data shown for the first two styles of counterbores are for straight shank designs. These tools are also available with taper shanks in most sizes. Sizes of taper shanks for cutter diameters of ¼ to 9/16 in. are No. 1, for 19/32 to ⅞ in., No. 2; for 15/16 to 1⅜ in., No. 3; for 1½ to 2 in., No. 4; and for 2⅛ to 2½ in., No. 5.

Copyright 2004, Industrial Press, Inc., New York, NY

Counterbore Sizes for Hex-head Bolts and Nuts.— Table 2, page 1531, shows the maximum socket wrench dimensions for standard ¼-, ½- and ¾-inch drive socket sets. For a given socket size (nominal size equals the maximum width across the flats of nut or bolt head), the dimension *K* given in the table is the minimum counterbore diameter required to provide socket wrench clearance for access to the bolt or nut.

Sintered Carbide Boring Tools.— Industrial experience has shown that the shapes of tools used for boring operations need to be different from those of single-point tools ordinarily used for general applications such as lathe work. Accordingly, Section 5 of American National Standard ANSI B212.1-2002 gives standard sizes, styles and designations for four basic types of sintered carbide boring tools, namely: solid carbide square; carbide-tipped square; solid carbide round; and carbide-tipped round boring tools. In addition to these ready-to-use standard boring tools, solid carbide round and square unsharpened boring tool bits are provided.

Style Designations for Carbide Boring Tools: Table 1 shows designations used to specify the styles of American Standard sintered carbide boring tools. The first letter denotes solid (S) or tipped (T). The second letter denotes square (S) or round (R). The side cutting edge angle is denoted by a third letter (A through H) to complete the style designation. Solid square and round bits with the mounting surfaces ground but the cutting edges unsharpened (Table 3) are designated using the same system except that the third letter indicating the side cutting edge angle is omitted.

Table 1. American National Standard Sintered Carbide Boring Tools — Style Designations *ANSI B212.1-2002*

Side Cutting Edge Angle *E*		Boring Tool Styles			
Degrees	Designation	Solid Square (SS)	Tipped Square (TS)	Solid Round (SR)	Tipped Round (TR)
0	A		TSA		
10	B		TSB		
30	C	SSC	TSC	SRC	TRC
40	D		TSD		
45	E	SSE	TSE	SRE	TRE
55	F		TSF		
90 (0° Rake)	G				TRG
90 (10° Rake)	H				TRH

Size Designation of Carbide Boring Tools: Specific sizes of boring tools are identified by the addition of numbers after the style designation. The first number denotes the diameter or square size in number of 1/32nds for types SS and SR and in number of 1/16ths for types TS and TR. The second number denotes length in number of 1/8ths for types SS and SR. For styles TRG and TRH, a letter "U" after the number denotes a semi-finished tool (cutting edges unsharpened). Complete designations for the various standard sizes of carbide boring tools are given in Tables 2 through 7. In the diagrams in the tables, angles shown without tolerance are ± 1°.

Examples of Tool Designation: The designation TSC-8 indicates: a carbide-tipped tool (T); square cross-section (S); 30-degree side cutting edge angle (C); and 8/16 or ½ inch square size (8).

The designation SRE-66 indicates: a solid carbide tool (S); round cross-section (R); 45 degree side cutting edge angle (E); 6/32 or 3/16 inch diameter (6); and 6/8 or ¾ inch long (6).

The designation SS-610 indicates: a solid carbide tool (S); square cross-section (S); 6/32 or 3/16 inch square size (6); 10/8 or 1¼ inches long (10).

It should be noted in this last example that the absence of a third letter (from A to H) indicates that the tool has its mounting surfaces ground but that the cutting edges are unsharpened.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Carbide-Tipped Round General-Purpose Square-End Boring Tools Style TRG with 0° Rake and Style TRH with 10° Rake *ANSI B212.1-2002*



Tool Designation		Shank Dimensions, Inches					Rake Angle Deg.	Tip No.	Tip Dimensions, Inches		
Finished	Semi-finished[a]	Dia. *D*	Length *C*	Dim.Over Flat *B*	Nose Height *H*	Set-back *M* (Min)			*T*	*W*	*L*
TRG-5	TRG-5U	5/16	1 1/2	19/64	3/16	3/16	0	1025	1/16	1/4	1/4
TRH-5	TRH-5U			±.005	7/32	3/16	10				
TRG-6	TRG-6U	3/8	1 3/4	11/32	7/32	3/16	0	1030	1/16	5/16	1/4
TRH-6	TRH-6U			±.010	1/4		10				
TRG-7	TRG-7U	7/16	2 1/2	13/32	1/4	3/16	0	1080	3/32	5/16	3/8
TRH-7	TRH-7U			±.010	5/16		10				
TRG-8	TRG-8U	1/2	2 1/2	15/32	9/32	1/4	0	1090	3/32	3/8	3/8
TRH-8	TRH-8U			±.010	11/32		10				

[a] Semifinished tool will be without Flat (B) and carbide unground on the end.

Table 3. Solid Carbide Square and Round Boring Tool Bits



Square Bits				Round Bits							
Tool Designation	*A*	*B*	*C*	Tool Designation	*D*	*C*	Tool Designation	*D*	*C*	Tool Designation	*D*	*C*
SS-58	5/32	5/32	1	SR-33	3/32	3/8	SR-55	5/32	5/8	SR-88	1/4	1
SS-610	3/16	3/16	1 1/4	SR-34	3/32	1/2	SR-64	3/16	1/2	SR-810	1/4	1 1/4
SS-810	1/4	1/4	1 1/4	SR-44	1/8	1/2	SR-66	3/16	3/4	SR-1010	5/16	1 1/4
SS-1012	5/16	5/16	1 1/2	SR-46	1/8	3/4	SR-69	3/16	1 1/8	…	…	…
SS-1214	3/8	3/8	1 3/4	SR-48	1/8	1	SR-77	7/32	7/8	…	…	…

All dimensions are in inches.
Tolerance on Length: Through 1 inch, + 1/32, − 0; over 1 inch, +1/16, −0.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ANSI Solid Carbide Square Boring Tools
Style SSC for 60° Boring Bar and Style SSE for 45° Boring Bar
ANSI B212.1-2002



Tool Designation	Boring Bar Angle, Deg. from Axis	Shank Dimensions, Inches			Side Cutting Edge Angle E,Deg.	End Cutting Edge Angle G ,Deg.	Shoulder Angle F ,Deg.
		Width A	Height B	Length C			
SSC-58	60	5/32	5/32	1	30	38	60
SSE-58	45				45	53	45
SSC-610	60	3/16	3/16	1 1/4	30	38	60
SSE-610	45				45	53	45
SSC-810	60	1/4	1/4	1 1/4	30	38	60
SSE-810	45				45	53	45
SSC-1012	60	5/16	5/16	1 1/2	30	38	60
SSE-1012	45				45	53	45

Table 5. ANSI Carbide-Tipped Round Boring Tools
Style TRC for 60° Boring Bar and Style TRE for 45° Boring Bar
ANSI B212.1-2002



Tool Designation	Bor. Bar Angle from Axis, Deg.	Shank Dimensions, Inches					Side Cut. Edge Angle E, Deg.	End Cut. Edge Angle G, Deg.	Shoulder Angle F, Deg.	Tip No.	Tip Dimensions, Inches		
		D	C	B	H	R					T	W	L
TRC-5	60	5/16	1 1/2	19/64 ±.005	7/32	1/64 ±.005	30	38	60	2020	1/16	3/16	1/4
TRE-5	45						45	53	45				
TRC-6	60	3/8	1 3/4	11/32 ±.010	9/32	1/64 ±.005	30	38	60	2040	3/32	3/16	5/16
TRE-6	45						45	53	45	2020	1/16	3/16	1/4
TRC-7	60	7/16	2 1/2	13/32 ±.010	5/16	1/32 ±.010	30	38	60	2060	3/32	1/4	3/8
TRE-7	45						45	53	45				
TRC-8	60	1/2	2 1/2	15/32 ±.010	3/8	1/32 ±.010	30	38	60	2060	3/32	1/4	3/8
TRE-8	45						45	53	45	2080	3/32	5/16	3/8

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ANSI Carbide-Tipped Square Boring Tools — *ANSI B212.1-2002*
Styles TSA and TSB for 90° Boring Bar, Styles TSC and TSD for 60° Boring Bar, and Styles TSE and TSF for 45° Boring Bar



Tool Designation	Bor. Bar Angle from Axis, Deg.	Shank Dimensions, Inches				Side Cut. Edge Angle E, Deg.	End Cut. Edge Angle G, Deg.	Shoulder Angle F, Deg.	Tip No.	Tip Dimensions, Inches		
		A	B	C	R					T	W	L
TSA-5	90	5/16	5/16	1 1/2		0	8	90	2040	3/32	3/16	5/16
TSB-5	90	5/16	5/16	1 1/2		10	8	90	2040	3/32	3/16	5/16
TSC-5	60	5/16	5/16	1 1/2		30	38	60	2040	3/32	3/16	5/16
TSD-5	60	5/16	5/16	1 1/2		40	38	60	2040	3/32	3/16	5/16
TSE-5	45	5/16	5/16	1 1/2		45	53	45	2040	3/32	3/16	5/16
TSF-5	45	5/16	5/16	1 1/2	1/64 ± 0.005	55	53	45	2040	3/32	3/16	5/16
TSA-6	90	3/8	3/8	1 3/4		0	8	90	2040	3/32	3/16	5/16
TSB-6	90	3/8	3/8	1 3/4		10	8	90	2040	3/32	3/16	5/16
TSC-6	60	3/8	3/8	1 3/4		30	38	60	2040	3/32	3/16	5/16
TSD-6	60	3/8	3/8	1 3/4		40	38	60	2040	3/32	3/16	5/16
TSE-6	45	3/8	3/8	1 3/4		45	53	45	2040	3/32	3/16	5/16
TSF-6	45	3/8	3/8	1 3/4		55	53	45	2040	3/32	3/16	5/16
TSA-7	90	7/16	7/16	2 1/2		0	8	90	2060	3/32	1/4	3/8
TSB-7	90	7/16	7/16	2 1/2		10	8	90	2060	3/32	1/4	3/8
TSC-7	60	7/16	7/16	2 1/2		30	38	60	2060	3/32	1/4	3/8
TSD-7	60	7/16	7/16	2 1/2		40	38	60	2060	3/32	1/4	3/8
TSE-7	45	7/16	7/16	2 1/2		45	53	45	2060	3/32	1/4	3/8
TSF-7	45	7/16	7/16	2 1/2	1/32 ± 0.010	55	53	45	2060	3/32	1/4	3/8
TSA-8	90	1/2	1/2	2 1/2		0	8	90	2150	1/8	5/16	7/16
TSB-8	90	1/2	1/2	2 1/2		10	8	90	2150	1/8	5/16	7/16
TSC-8	60	1/2	1/2	2 1/2		30	38	60	2150	1/8	5/16	7/16
TSD-8	60	1/2	1/2	2 1/2		40	38	60	2150	1/8	5/16	7/16
TSE-8	45	1/2	1/2	2 1/2		45	53	45	2150	1/8	5/16	7/16
TSF-8	45	1/2	1/2	2 1/2		55	53	45	2150	1/8	5/16	7/16
TSA-10	90	5/8	5/8	3		0	8	90	2220	5/32	3/8	9/16
TSB-10	90	5/8	5/8	3		10	8	90	2220	5/32	3/8	9/16
TSC-10	60	5/8	5/8	3		30	38	60	2220	5/32	3/8	9/16
TSD-10	60	5/8	5/8	3		40	38	60	2220	5/32	3/8	9/16
TSE-10	45	5/8	5/8	3		45	53	45	2220	5/32	3/8	9/16
TSF-10	45	5/8	5/8	3	1/32 ± 0.010	55	53	45	2220	5/32	3/8	9/16
TSA-12	90	3/4	3/4	3 1/2		0	8	90	2300	3/16	7/16	5/8
TSB-12	90	3/4	3/4	3 1/2		10	8	90	2300	3/16	7/16	5/8
TSC-12	60	3/4	3/4	3 1/2		30	38	60	2300	3/16	7/16	5/8
TSD-12	60	3/4	3/4	3 1/2		40	38	60	2300	3/16	7/16	5/8
TSE-12	45	3/4	3/4	3 1/2		45	53	45	2300	3/16	7/16	5/8
TSF-12	45	3/4	3/4	3 1/2		55	53	45	2300	3/16	7/16	5/8

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. ANSI Solid Carbide Round Boring Tools — *ANSI B212.1-2002*
Style SRC for 60° Boring Bar and Style SRE for 45° Boring Bar



Tool Designation	Bor. Bar Angle from Axis, Deg.	Shank Dimensions, Inches				Side Cut. Edge Angle *E*, Deg.	End Cut. Edge Angle *G*, Deg.	Shoulder Angle *F*, Deg.
		Dia. *D*	Length *C*	Dim. Over Flat *B*	Nose Height *H*			
SRC-33	60	3/32	3/8	0.088	0.070 [+0.000 −0.005]	30	38	60
SRE-33	45	3/32	3/8	0.088	0.070	45	53	45
SRC-44	60	1/8	1/2	0.118	0.094 [+0.000 −0.005]	30	38	60
SRE-44	45	1/8	1/2	0.118	0.094	45	53	45
SRC-55	60	5/32	5/8	0.149	0.117 ±0.005	30	38	60
SRE-55	45	5/32	5/8	0.149	0.117 ±0.005	45	53	45
SRC-66	60	3/16	3/4	0.177	0.140 ±0.005	30	38	60
SRE-66	45	3/16	3/4	0.177	0.140 ±0.005	45	53	45
SRC-88	60	1/4	1	0.240	0.187 ±0.005	30	38	60
SRE-88	45	1/4	1	0.240	0.187 ±0.005	45	53	45
SRC-1010	60	5/16	1 1/4	0.300	0.235 ±0.005	30	38	60
SRE-1010	45	5/16	1 1/4	0.300	0.235 ±0.005	45	53	45

Boring Machines, Origin.— The first boring machine was built by John Wilkinson, in 1775. Smeaton had built one in 1769 which had a large rotary head, with inserted cutters, carried on the end of a light, overhanging shaft. The cylinder to be bored was fed forward against the cutter on a rude carriage, running on a track laid in the floor. The cutter head followed the inaccuracies of the bore, doing little more than to smooth out local roughness of the surface. Watt's first steam cylinders were bored on this machine and he complained that one, 18 inches in diameter, was 3/8 inch out of true. Wilkinson thought of the expedient, which had escaped both Smeaton and Watt, of extending the boring-bar completely through the cylinder and giving it an out-board bearing, at the same time making it much larger and stiffer. With this machine cylinders 57 inches in diameter were bored which were within 1/16 inch of true. Its importance can hardly be overestimated as it insured the commercial success of Watt's steam engine which, up to that time, had not passed the experimental stage.

Copyright 2004, Industrial Press, Inc., New York, NY

TAPS AND THREADING DIES

Taps

General dimensions and tap markings given in the ASME B94.9 Standard for straight fluted taps, spiral pointed taps, spiral pointed only taps, spiral fluted taps, fast spiral fluted taps, thread forming taps, pulley taps, nut taps, and pipe taps are shown in the tables on the pages that follow. This Standard also gives the thread limits for taps with cut threads and ground threads. The thread limits for cut thread and ground thread taps for screw threads are given in Tables 1 through 5 and Tables 4a and 4b; thread limits for cut thread and ground thread taps for pipe threads are given in Tables 6a through 7c. Taps recommended for various classes of Unified screw threads are given in Tables 8a through 11 in numbered sizes and Table 9 for nuts in fractional sizes.

Types of Taps.— Taps included in ASME B94.9 are categorized either by the style of fluting or by the specific application for which the taps are designed. The following types 1 through 6 are generally short in length, and were originally called "Hand Taps" but this design is generally used in machine applications. The remaining types have special lengths, which are detailed in the tables.

The thread size specifications for these types may be fractional or machine screw inch sizes, or metric sizes. The thread form may be ground or cut (unground) as further defined in each table. Additionally, the cutting chamfer on the thread may be Bottoming (B), Plug (P), or Taper (T).

(1) Straight Flute Taps: These taps have straight flutes of a number specified as either standard or optional, and are for general purpose applications.

(2) Spiral Pointed Taps: These taps have straight flutes and the cutting face of the first few threads is ground at an angle to force the chips ahead and prevent clogging in the flutes.

(3) Spiral Pointed Only Taps: These taps are made with the spiral point feature only without longitudinal flutes. These taps are especially suitable for tapping thin materials.

(4) Spiral Fluted Taps: These taps have right-hand helical flutes with a helix angle of 25 to 35 deg. These features are designed to help draw chips from the hole or to bridge a keyway.

(5) Fast Spiral Fluted Taps: These taps are similar to spiral fluted taps, except the helix angle is from 45 to 60 deg.

(6) Thread Forming Taps: These taps are fluteless except as optionally designed with one or more lubricating grooves. The thread form on the tap is lobed, so that there are a finite number of points contacting the work thread form. The tap does not cut, but forms the thread by extrusion.

(7) Pulley Taps: These taps have shanks that are extended in length by a standard amount for use where added reach is required. The shank is the same nominal diameter as the thread.

(8) Nut Taps: These taps are designed for tapping nuts on a low-production basis. Approximately one-half to three-quarters of the threaded portion has a chamfered section, which distributes the cutting over many teeth and facilitates entering the hole to be tapped. The length overall, the length of the thread, and the length of the shank are appreciably longer than on a regular straight fluted tap. Nut taps have been removed from ASME B94.9 but are retained for reference.

(9) Pipe Taps: These taps are used to produce standard straight or tapered pipe threads.

Definitions of Tap Terms.— The definitions that follow are taken from ASME B94.9 but include only the more important terms. Some tap terms are the same as screw thread terms; therefore, see *Definitions of Screw Threads* starting on page 1727.

Back Taper: A gradual decrease in the diameter of the thread form on a tap from the chamfered end of the land toward the back, which creates a slight radial relief in the threads.

Copyright 2004, Industrial Press, Inc., New York, NY

Base of Thread: Coincides with the cylindrical or conical surface from which the thread projects.

Chamfer: Tapering of the threads at the front end of each land or chaser of a tap by cutting away and relieving the crest of the first few teeth to distribute the cutting action over several teeth.

Chamfer Angle: Angle formed between the chamfer and the axis of the tap measured in an axial plane at the cutting edge.

Chamfer Relief Angle: Complement of the angle formed between a tangent to the relieved surface at the cutting edge and a radial line to the same point on the cutting edge.

Core Diameter: Diameter of a circle which is tangent to the bottom of the flutes at a given point on the axis.

First Full Thread: First full thread on the cutting edge back of the chamfer. It is at this point that rake, hook, and thread elements are measured.

Crest Clearance: Radial distance between the root of the internal thread and the crest of the external thread of the coaxially assembled design forms of mating threads.

Class of Thread: Designation of the class that determines the specification of the size, allowance, and tolerance to which a given threaded product is to be manufactured. It is not applicable to the tools used for threading.



Copyright 2004, Industrial Press, Inc., New York, NY

Flank Angle: Angle between the individual flank and the perpendicular to the axis of the thread, measured in an axial plane. A flank angle of a symmetrical thread is commonly termed the "half angle of thread."

Flank—Leading: 1) Flank of a thread facing toward the chamfered end of a threading tool; and 2) The leading flank of a thread is the one which, when the thread is about to be assembled with a mating thread, faces the mating thread.

Flank—Trailing: The trailing flank of a thread is the one opposite the leading flank.

Flutes: Longitudinal channels formed in a tap to create cutting edges on the thread profile and to provide chip spaces and cutting fluid passages. On a parallel or straight thread tap they may be straight, angular or helical; on a taper thread tap they may be straight, angular or spiral.

Flute-Angular: A flute lying in a plane intersecting the tool axis at an angle.

Flute-Helical: A flute with uniform axial lead and constant helix in a helical path around the axis of a cylindrical tap.

Flute-Spiral: A flute with uniform axial lead in a spiral path around the axis of a conical tap.

Flute Lead Angle: Angle at which a helical or spiral cutting edge at a given point makes with an axial plane through the same point.

Flute-Straight: A flute which forms a cutting edge lying in an axial plane.

Front Taper: A gradual increase in the diameter of the thread form on a tap from the leading end of the tool toward the back.

Heel: Edge of the land opposite the cutting edge.

Hook Angle: Inclination of a concave cutting face, usually specified either as Chordal Hook or Tangential Hook.

Hook-Chordal Angle: Angle between the chord passing through the root and crest of a thread form at the cutting face, and a radial line through the crest at the cutting edge.

Hook-Tangential Angle: Angle between a line tangent to a hook cutting face at the cutting edge and a radial line to the same point.

Interrupted Thread Tap: A tap having an odd number of lands with alternate teeth in the thread helix removed. In some designs alternate teeth are removed only for a portion of the thread length.

Land: One of the threaded sections between the flutes of a tap.

Lead: Distance a screw thread advances axially in one complete turn.

Lead Error: Deviation from prescribed limits.

Lead Deviation: Deviation from the basic nominal lead.

Progressive Lead Deviation: (1) On a straight thread the deviation from a true helix where the thread helix advances uniformly. (2) On a taper thread the deviation from a true spiral where the thread spiral advances uniformly.

Length of Thread: The length of the thread of the tap includes the chamfered threads and the full threads but does not include an external center. It is indicated by the letter "B" in the illustrations at the heads of the tables.

Limits: The limits of size are the applicable maximum and minimum sizes.

Major Diameter: On a straight thread the major diameter is that of the major cylinder. On a taper thread the major diameter at a given position on the thread axis is that of the major cone at that position.

Minor Diameter: On a straight thread the minor diameter is that of the minor cylinder. On a taper thread the minor diameter at a given position on the thread axis is that of the minor cone at that position.

Pitch Diameter (Simple Effective Diameter): On a straight thread, the pitch diameter is the diameter of the imaginary coaxial cylinder, the surface of which would pass through the thread profiles at such points as to make the width of the groove equal to one-half the basic pitch. On a perfect thread this coincidence occurs at the point where the widths of the thread and groove are equal. On a taper thread, the pitch diameter at a given position on the thread axis is the diameter of the pitch cone at that position.

Copyright 2004, Industrial Press, Inc., New York, NY

Point Diameter: Diameter at the cutting edge of the leading end of the chamfered section.

Rake: Angular relationship of the straight cutting face of a tooth with respect to a radial line through the crest of the tooth at the cutting edge. Positive rake means that the crest of the cutting face is angularly ahead of the balance of the cutting face of the tooth. Negative rake means that the crest of the cutting face is angularly behind the balance of the cutting face of the tooth. Zero rake means that the cutting face is directly on a radial line.

Relief: Removal of metal behind the cutting edge to provide clearance between the part being threaded and the threaded land.

Relief-Center: Clearance produced on a portion of the tap land by reducing the diameter of the entire thread form between cutting edge and heel.

Relief-Chamfer: Gradual decrease in land height from cutting edge to heel on the chamfered portion of the land on a tap to provide radial clearance for the cutting edge.

Relief-Con-eccentric Thread: Radial relief in the thread form starting back of a concentric margin.

Relief-Double Eccentric Thread: Combination of a slight radial relief in the thread form starting at the cutting edge and continuing for a portion of the land width, and a greater radial relief for the balance of the land.

Relief-Eccentric Thread: Radial relief in the thread form starting at the cutting edge and continuing to the heel.

Relief-Flatted Land: Clearance produced on a portion of the tap land by truncating the thread between cutting edge and heel.

Relief-Grooved Land: Clearance produced on a tap land by forming a longitudinal groove in the center of the land.

Relief-Radial: Clearance produced by removal of metal from behind the cutting edge. Taps should have the chamfer relieved and should have back taper, but may or may not have relief in the angle and on the major diameter of the threads. When the thread angle is relieved, starting at the cutting edge and continuing to the heel, the tap is said to have "eccentric" relief. If the thread angle is relieved back of a concentric margin (usually one-third of land width), the tap is said to have "con-eccentric" relief.

Size-Actual: Measured size of an element on an individual part.

Size-Basic: That size from which the limits of size are derived by the application of allowances and tolerances.

Size-Functional: The functional diameter of an external or internal thread is the pitch diameter of the enveloping thread of perfect pitch, lead and flank angles, having full depth of engagement but clear at crests and roots, and of a specified length of engagement. It may be derived by adding to the pitch diameter in an external thread, or subtracting from the pitch diameter in an internal thread, the cumulative effects of deviations from specified profile, including variations in lead and flank angle over a specified length of engagement. The effects of taper, out-of-roundness, and surface defects may be positive or negative on either external or internal threads.

Size-Nominal: Designation used for the purpose of general identification.

Spiral Flute: See *Flutes*.

Spiral Point: Angular fluting in the cutting face of the land at the chamfered end. It is formed at an angle with respect to the tap axis of opposite hand to that of rotation. Its length is usually greater than the chamfer length and its angle with respect to the tap axis is usually made great enough to direct the chips ahead of the tap. The tap may or may not have longitudinal flutes.

Thread Lead Angle: On a straight thread, the lead angle is the angle made by the helix of the thread at the pitch line with a plane perpendicular to the axis. On a taper thread, the lead angle at a given axial position is the angle made by the conical spiral of the thread, with the plane perpendicular to the axis, at the pitch line.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Standard Fraction-Size Taps — Cut Thread Limits
ASME B94.9-1999

Tap Size	Threads per Inch			Major Diameter			Pitch Diameter		
	NC UNC	NF UNF	NS UNS	Basic	Min.	Max.	Basic	Min.	Max.
1/8	…	…	40	0.1250	0.1266	0.1286	0.1088	0.1090	0.1105
5/32	…	…	32	0.1563	0.1585	0.1605	0.1360	0.1365	0.1380
3/16	…	…	24	0.1875	0.1903	0.1923	0.1604	0.1609	0.1624
3/16	…	…	32	0.1875	0.1897	0.1917	0.1672	0.1677	0.1692
1/4	20	…	…	0.2500	0.2532	0.2557	0.2175	0.2180	0.2200
1/4	…	28	…	0.2500	0.2524	0.2549	0.2268	0.2273	0.2288
5/16	18	…	…	0.3125	0.3160	0.3185	0.2764	0.2769	0.2789
5/16	…	24	…	0.3125	0.3153	0.3178	0.2854	0.2859	0.2874
3/8	16	…	…	0.3750	0.3789	0.3814	0.3344	0.3349	0.3369
3/8	…	24	…	0.3750	0.3778	0.3803	0.3479	0.3484	0.3499
7/16	14	…	…	0.4375	0.4419	0.4449	0.3911	0.3916	0.3941
7/16	…	20	…	0.4375	0.4407	0.4437	0.4050	0.4055	0.4075
1/2	13	…	…	0.5000	0.5047	0.5077	0.4500	0.4505	0.4530
1/2	…	20	…	0.5000	0.5032	0.5062	0.4675	0.4680	0.4700
9/16	12	…	…	0.5625	0.5675	0.5705	0.5084	0.5089	0.5114
9/16	…	18	…	0.5625	0.5660	0.5690	0.5264	0.5269	0.5289
5/8	11	…	…	0.6250	0.6304	0.6334	0.5660	0.5665	0.5690
5/8	…	18	…	0.6250	0.6285	0.6315	0.5889	0.5894	0.5914
3/4	10	…	…	0.7500	0.7559	0.7599	0.6850	0.6855	0.6885
3/4	…	16	…	0.7500	0.7539	0.7579	0.7094	0.7099	0.7124
7/8	9	…	…	0.8750	0.8820	0.8860	0.8028	0.8038	0.8068
7/8	…	14	…	0.8750	0.8799	0.8839	0.8286	0.8296	0.8321
1	8	…	…	1.0000	1.0078	1.0118	0.9188	0.9198	0.9228
1	…	12	…	1.0000	1.0055	1.0095	0.9459	0.9469	0.9494
1	…	…	14	1.0000	1.0049	1.0089	0.9536	0.9546	0.9571
1 1/8	7	…	…	1.1250	1.1337	1.1382	1.0322	1.0332	1.0367
1 1/8	…	12	…	1.1250	1.1305	1.1350	1.0709	1.0719	1.0749
1 1/4	7	…	…	1.2500	1.2587	1.2632	1.1572	1.1582	1.1617
1 1/4	…	12	…	1.2500	1.2555	1.2600	1.1959	1.1969	1.1999
1 3/8	6	…	…	1.3750	1.3850	1.3895	1.2667	1.2677	1.2712
1 3/8	…	12	…	1.3750	1.3805	1.3850	1.3209	1.3219	1.3249
1 1/2	6	…	…	1.5000	1.5100	1.5145	1.3917	1.3927	1.3962
1 1/2	…	12	…	1.5000	1.5055	1.5100	1.4459	1.4469	1.4499
1 3/4	5	…	…	1.7500	1.7602	1.7657	1.6201	1.6216	1.6256
2	4 1/2	…	…	2.0000	2.0111	2.0166	1.8557	1.8572	1.8612

All dimensions are given in inches.

Lead Tolerance: Plus or minus 0.003 inch max. per inch of thread.

Angle Tolerance: Plus or minus 35 min. in half angle or 53 min. in full angle for 4½ to 5½ thds. per in.; 40 min. half angle and 60 min. full angle for 6 to 9 thds.; 45 min. half angle and 68 min. full angle for 10 to 28 thds.; 60 min. half angle and 90 min. full angle for 30 to 64 thds. per in.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Standard Fractional-Size Taps — Ground Thread Limits *ASME B94.9-1999*

Size in.	Threads per Inch NC UNC	NF UNF	NS UNS	Major Diameter Basic	Min.	Max.	Basic Pitch Dia.	Pitch Diameter H1 Limit Min.	H1 Limit Max.	H2 Limit Min.	H2 Limit Max.	H3 & H4 [a] Limits Min.	H3 & H4 [a] Limits Max.	H4 [a], H5 [b], H6 [c] Limits Min.	H4 [a], H5 [b], H6 [c] Limits Max.	H7 [e], H8 [f] Limits Min.	H7 [e], H8 [f] Limits Max.
1/4	20	…	…	0.2500	0.2532	0.2565	0.2175	0.2175	0.2180	0.2180	0.2185	0.2185	0.2190	0.2195 [b,d]	0.2200 [b,d]	…	…
1/4	…	28	…	0.2500	0.2523	0.2546	0.2268	0.2268	0.2273	0.2273	0.2278	0.2278	0.2283	0.2283 [a]	0.2288 [a]	…	…
5/16	18	…	…	0.3125	0.3161	0.3197	0.2764	0.2764	0.2769	0.2769	0.2774	0.2774	0.2779	0.2784 [b,d]	0.2789 [b,d]	0.2794 [e,h]	0.2799 [e,h]
5/16	…	24	…	0.3125	0.3152	0.3179	0.2854	0.2854	0.2859	0.2859	0.2864	0.2864	0.2869	0.2869 [a]	0.2874 [a]	0.2884 [e,h]	0.2889 [e,h]
3/8	16	…	…	0.3750	0.3790	0.3831	0.3344	0.3344	0.3349	0.3349	0.3354	0.3354	0.3359	0.3364 [b,d]	0.3369 [b,d]	0.3374 [e,h]	0.3379 [e,h]
3/8	…	24	…	0.3750	0.3777	0.3804	0.3479	0.3479	0.3484	0.3484	0.3489	0.3489	0.3494	0.3494 [a]	0.3499 [a]	0.3509 [e,h]	0.3514 [e,h]
7/16	14	…	…	0.4375	0.4422	0.4468	0.3911	…	…	0.3916	0.3921	0.3921	0.3926	0.3931 [b,d]	0.3936 [b,d]	0.3946 [f]	0.3951 [f]
7/16	…	20	…	0.4375	0.4407	0.4440	0.4050	…	…	…	…	0.4060	0.4065	0.4070 [b,d]	0.4075 [b,d]	0.4085 [f]	0.4090 [f]
1/2	13	…	…	0.5000	0.5050	0.5100	0.4500	0.4500	0.4505	0.4505	0.4510	0.4510	0.4515	0.4520 [b,d]	0.4525 [b,d]	0.4536 [f]	0.4240 [f]
1/2	…	20	…	0.5000	0.5032	0.5065	0.4675	0.4675	0.4680	0.4680	0.4685	0.4685	0.4690	0.4695 [b,d]	0.4700 [b,d]	0.4710 [f]	0.4715 [f]
9/16	12	…	…	0.5625	0.5679	0.5733	0.5084	…	…	…	…	0.5094	0.5099	0.5104 [b,d]	0.5109 [b,d]	0.5114 [e,h]	0.5119 [e,h]
9/16	…	18	…	0.5625	0.5661	0.5697	0.5264	…	…	0.5269	0.5274	0.5274	0.5279	0.5284 [b,d]	0.5289 [b,d]	0.5294 [e,h]	0.5299 [e,h]
5/8	11	…	…	0.6250	0.6309	0.6368	0.5660	…	…	0.5665	0.5670	0.5670	0.5675	0.5680 [b,d]	0.5685 [b,d]	0.5690 [e,h]	0.5695 [e,h]
5/8	…	18	…	0.6250	0.6286	0.6322	0.5889	…	…	0.5894	0.5899	0.5899	0.5904	0.5909 [b,d]	0.5914 [b,d]	0.5919 [e,h]	0.5924 [e,h]
11/16	…	…	11	0.6875	0.6934	0.6993	0.6285	…	…	…	…	0.6295	0.6300	…	…	…	…
11/16	…	…	16	0.6875	0.6915	0.6956	0.6469	…	…	…	…	0.6479	0.6484	…	…	…	…
3/4	10	…	…	0.7500	0.7565	0.7630	0.6850	…	…	0.6855	0.6860	0.6860	0.6865	0.6870 [b,d]	0.6875 [b,d]	0.6880 [e,i]	0.6885 [e,i]
3/4	…	16	…	0.7500	0.7540	0.7581	0.7094	0.7094	0.7099	0.7099	0.7104	0.7104	0.7109	0.7114 [b,d]	0.7119 [b,d]	0.7124 [e,i]	0.7129 [e,i]
7/8	9	…	…	0.8750	0.8822	0.8894	0.8028	…	…	…	…	0.8043 [a]	0.8048 [a]	0.8053 [c]	0.8058 [c]	…	…
7/8	…	14	…	0.8750	0.8797	0.8843	0.8286	…	…	0.8291	0.8296	0.8301 [a]	0.8306 [a]	…	…	…	…
1	8	…	…	1.0000	1.0082	1.0163	0.9188					0.9203 [a]	0.9208 [a]	0.9213 [c]	0.9218 [c]	…	…
1	…	12	…	1.0000	1.0054	1.0108	0.9459					0.9474 [a]	0.9479 [a]	…	…	…	…
1	…	…	14	1.0000	1.0047	1.0093	0.9536					0.9551 [a]	0.9556 [a]	…	…	…	…
1 1/8	7	…	…	1.1250	1.1343	1.1436	1.0322					1.0337 [a]	1.0342 [a]	…	…	…	…
1 1/8	…	12	…	1.1250	1.1304	1.1358	1.0709					1.0724 [a]	1.0729 [a]	…	…	…	…
1 1/4	7	…	…	1.2500	1.2593	1.2686	1.1572					1.1587 [a]	1.1592 [a]	…	…	…	…
1 1/4	…	12	…	1.2500	1.2554	1.2608	1.1959					1.1974 [a]	1.1979 [a]	…	…	…	…
1 3/8	6	…	…	1.3750	1.3859	1.3967	1.2667					1.2682 [a]	1.2687 [a]	…	…	…	…
1 3/8	…	12	…	1.3750	1.3804	1.3858	1.3209					1.3224 [a]	1.3229 [a]	…	…	…	…
1 1/2	6	…	…	1.5000	1.5109	1.5217	1.3917					1.3932 [a]	1.3937 [a]	…	…	…	…
1 1/2	…	12	…	1.5000	1.5054	1.5108	1.4459					1.4474 [a]	1.4479 [a]	…	…	…	…
1 3/4	…	5	…	1.7500	1.7630	1.7760	1.6201					1.6216 [a]	1.6221 [a]	…	…	…	…
2	…	4.5	…	2.0000	2.0145	2.0289	1.8557					1.8572 [a]	1.8577 [a]	…	…	…	…

Notes:

[a] H4 limit value; [b] H5 limit value; [c] H6 limit value; [e] H7 limit value; [f] H8 limit value.

Minimum and maximum major diameters are: [d] 0.0010 larger than shown; [g] 0.0035 larger than shown; [h] 0.0020 larger than shown; [i] 0.0015 larger than shown.

All dimensions are given in inches. Limits listed in the above table are the most commonly used in industry. Not all styles of taps are available with all limits listed. For calculation of limits not listed see ASME B94.9-1999

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ANSI Standard Machine Screw Taps — Ground Thread Limits *ASME B94.9-1999*

Size	Threads per Inch			Major Diameter			Basic Pitch Dia.	H1 Limit		H2 Limit		H3 [a], H4 [b], H5 [c] Limits		H6 [d], H7 [e], H10 [f] Limits	
	NC UNC	NF UNF	NS UNS	Basic	Min.	Max.		Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.
0	…	80	…	0.0600	0.0605	0.0616	0.0519	0.0519	0.0524	0.0524	0.0529	*Notes:*			
1	64	…	…	0.0730	0.0736	0.0750	0.0629	0.0629	0.0634	0.0634	0.0639	[a] H3 limit value; [b] H4 limit value; [c] H5 limit value; [d] H6 limit value; [e] H7 limit value; [f] H10 limit value.			
1	…	72	…	0.0730	0.0736	0.0748	0.0640	0.0640	0.0645	0.0645	0.0650				
2	56	…	…	0.0860	0.0867	0.0883	0.0744	0.0744	0.0749	0.0749	0.0754	Minimum and maximum major diameters are: [g] 0.0010 larger than shown; [h] 0.0020 larger than shown; [i] 0.0035 larger than shown; [j] 0.0015 larger than shown.			
2	…	64	…	0.0860	0.0866	0.0880	0.0759	…	…	0.0764	0.0769				
3	48	…	…	0.0990	0.0999	0.1017	0.0855	…	…	0.0860	0.0865				
3	…	56	…	0.0990	0.0997	0.1013	0.0874	0.0874	0.0879	0.0879	0.0884				
4	40	…	…	0.1120	0.1134	0.1152	0.0958	0.0958	0.0963	0.0963	0.0968	0.0978 [c, j]	0.0983 [c, j]	…	…
4	…	48	…	0.1120	0.1129	0.1147	0.0985	0.0985	0.0990	0.0990	0.0995	0.1005 [c, j]	0.1010 [c, j]	…	…
4	…	…	36	0.1120	0.1135	0.1156	0.0940	0.0940	0.0945	0.0945	0.0950	0.0960 [c, j]	0.0965 [c, j]	…	…
5	40	…	…	0.1250	0.1264	0.1283	0.1088	0.1088	0.1093	0.1093	0.1098	0.1108 [c, j]	0.1113 [c, j]	…	…
5	…	44	…	0.1250	0.1263	0.1280	0.1102	…	…	0.1107	0.1112	0.1122 [c, j]	0.1127 [c, j]	…	…
6	32	…	…	0.1380	0.1401	0.1421	0.1177	0.1177	0.1182	0.1182	0.1187	0.1187 [a] 0.1197 [c, g]	0.1192 [a] 0.1202 [g]	0.1207 [e, h] 0.1222 [f, i]	0.1212 [e, h] 0.1227 [f, i]
6	…	40	…	0.1380	0.1394	0.1413	0.1218	0.1218	0.1223	0.1223	0.1228	0.1238 [c]	0.1243 [c]	…	…
8	32	…	…	0.1640	0.1661	0.1681	0.1437	0.1437	0.1442	0.1442	0.1447	0.1447 [a] 0.1457 [g]	0.1452 [a] 0.1462 [g]	0.1467 [e, h] 0.1482 [f, i]	0.1472 [e, h] 0.1487 [f, i]
8	…	36	…	0.1640	0.1655	0.1676	0.1460	…	…	0.1465	0.1470	0.1480 [g]	0.1485 [g]	…	…
10	24	…	…	0.1900	0.1927	0.1954	0.1629	0.1629	0.1634	0.1634	0.1639	0.1639 [a] 0.1644 [b]	0.1644 [a] 0.1649 [b]	0.1654 [d, g] 0.1659 [e, h]	0.1659 [d, g] 0.1664 [e, h]
10	…	32	…	0.1900	0.1921	0.1941	0.1697	0.1697	0.1702	0.1702	0.1707	0.1707 [a] 0.1712 [b]	0.1712 [a] 0.1717 [b]	0.1722 [d, g] 0.1727 [e, h] 0.1742 [f, i]	0.1727 [d, g] 0.1732 [e, h] 0.1747 [f, i]
12	24	…	…	0.2160	0.2187	0.2214	0.1889	…	…	…	…	0.1899 [a] 0.0914 [b]	0.1904 [a] 0.1919 [b]	0.1914 [d, g]	0.1919 [d, g]
12	…	28	…	0.2160	0.2183	0.2206	0.1928	…	…	…	…	0.1938 [a] 0.1953 [b]	0.1943 [a] 0.1958 [b]	0.1953 [d, g]	0.1958 [d, g]

All dimensions are given in inches. Limits listed in table are most commonly used in industry. Not all style of taps are available with all limits listed.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. ANSI Standard Metric Tap Ground Thread Limits in Inches — M Profile *ASME B94.9-1999*

Nominal Diam, mm	Pitch, mm	Major Diameter (Inches)			Pitch Diameter (Inches)		
		Basic	Min	Max	Basic	Min	Max
1.6	0.35	0.06299	0.06409	0.06508	0.05406	0.05500	0.05559
2	0.4	0.07874	0.08000	0.08098	0.06850	0.06945	0.07004
2.5	0.45	0.09843	0.09984	0.10083	0.08693	0.08787	0.08846
3	0.5	0.11811	0.11969	0.12067	0.10531	0.10626	0.10685
3.5	0.6	0.13780	0.13969	0.14067	0.12244	0.12370	0.12449
4	0.7	0.15748	0.15969	0.16130	0.13957	0.14083	0.14161
4.5	0.75	0.17717	0.17953	0.18114	0.15799	0.15925	0.16004
5	0.8	0.19685	0.19937	0.20098	0.17638	0.17764	0.17843
6	1	0.23622	0.23937	0.24098	0.21063	0.21220	0.21319
7	1	0.27559	0.27874	0.28035	0.25000	0.25157	0.25256
8	1.25	0.31496	0.31890	0.32142	0.28299	0.28433	0.28555
10	1.5	0.39370	0.39843	0.40094	0.35535	0.35720	0.35843
12	1.75	0.47244	0.47795	0.48047	0.42768	0.42953	0.43075
14	2	0.55118	0.55748	0.56000	0.50004	0.50201	0.50362
16	2	0.62992	0.63622	0.63874	0.57878	0.58075	0.58236
20	2.5	0.78740	0.79538	0.79780	0.72346	0.72543	0.72705
24	3	0.94488	0.95433	0.95827	0.86815	0.87063	0.87224
30	3.5	1.18110	1.19213	1.19606	1.09161	1.09417	1.09622
36	4	1.41732	1.42992	1.43386	1.31504	1.31760	1.31965
42	4.5	1.65354	1.66772	1.71102	1.53846	1.54154	1.54358
48	5	1.88976	1.90551	1.98819	1.76189	1.76496	1.76701

Basic pitch diameter is the same as minimum pitch diameter of internal thread, Class 6H as shown in table starting on page 1798.

Pitch diameter limits are designated in the Standard as D3 for 1.6 to 3 mm diameter sizes, incl.: D4 for 3.5 to 5 mm sizes, incl.; D5 for 6 and 8 mm sizes; D6 for 10 and 12 mm sizes; D7 for 14 to 20 mm sizes, incl.; D8 for 24 mm size; and D9 for 30 and 36 mm sizes.

Angle tolerances are plus or minus 30 minutes in half angle for pitches ranging from 0.35 through 2.5 mm, incl. and plus or minus 25 minutes in half angle for pitches ranging from 3 to 4 mm, incl.

A maximum deviation of plus or minus 0.0005 inch within any two threads not farther apart than one inch is permitted.

Table 4b. ANSI Standard Metric Tap Ground Thread Limits in Millimeters — M Profile *ASME B94.9-1999*

Nominal Diam, mm	Pitch, mm	Major Diameter (mm)			Pitch Diameter (mm)		
		Basic	Min	Max	Basic	Min	Max
1.6	0.35	1.600	1.628	1.653	1.373	1.397	1.412
2	0.4	2.000	2.032	2.057	1.740	1.764	1.779
2.5	0.45	2.500	2.536	2.561	2.208	2.232	2.247
3	0.5	3.000	3.040	3.065	2.675	2.699	2.714
3.5	0.6	3.500	3.548	3.573	3.110	3.142	3.162
4	0.7	4.000	4.056	4.097	3.545	3.577	3.597
4.5	0.75	4.500	4.560	4.601	4.013	4.045	4.065
5	0.8	5.000	5.064	5.105	4.480	4.512	4.532
6	1	6.000	6.080	6.121	5.350	5.390	5.415
7	1	7.000	7.080	7.121	6.350	6.390	6.415
8	1.25	8.000	8.100	8.164	7.188	7.222	7.253
10	1.5	10.000	10.120	10.184	9.026	9.073	9.104
12	1.75	12.000	12.140	12.204	10.863	10.910	10.941
14	2	14.000	14.160	14.224	12.701	12.751	12.792
16	2	16.000	16.160	16.224	14.701	14.751	14.792
20	2.5	20.000	20.200	20.264	18.376	18.426	18.467
24	3	24.000	24.240	24.340	22.051	22.114	22.155
30	3.5	30.000	30.280	30.380	27.727	27.792	27.844
36	4	36.000	36.320	36.420	33.402	33.467	33.519
42	4.5	42.000	42.360	43.460	39.077	39.155	36.207
48	5	48.000	48.400	50.500	44.752	44.830	44.882

Basic pitch diameter is the same as minimum pitch diameter of internal thread, Class 6H as shown in table starting on page 1798.

Pitch diameter limits are designated in the Standard as D3 for 1.6 to 3 mm diameter sizes, incl.: D4 for 3.5 to 5 mm sizes, incl.; D5 for 6 and 8 mm sizes; D6 for 10 and 12 mm sizes; D7 for 14 to 20 mm sizes, incl.; D8 for 24 mm size; D9 for 30 and 36 mm sizes; D10 for 42 and 48 mm sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ANSI Standard Machine Screw Taps — Cut Threads Limits *ASME B94.9-1999*

Size	Threads per Inch			Major Diameter			Pitch Diameter		
	NC UNC	NF UNF	NS UNS	Basic	Min.	Max.	Basic	Min.	Max.
0	…	80	…	0.0600	0.0609	0.0624	0.0519	0.0521	0.0531
1	64	…	…	0.0730	0.0740	0.0755	0.0629	0.0631	0.0641
1	…	72	…	0.0730	0.0740	0.0755	0.0640	0.0642	0.0652
2	56	…	…	0.0860	0.0872	0.0887	0.0744	0.0746	0.0756
2	…	64	…	0.0860	0.0870	0.0885	0.0759	0.0761	0.0771
3	48	…	…	0.0990	0.1003	0.1018	0.0855	0.0857	0.0867
3	…	56	…	0.0990	0.1002	0.1017	0.0874	0.0876	0.0886
4	…	…	36	0.1120	0.1137	0.1157	0.0940	0.0942	0.0957
4	40	…	…	0.1120	0.1136	0.1156	0.0958	0.0960	0.0975
4	…	48	…	0.1120	0.1133	0.1153	0.0985	0.0987	0.1002
5	40	…	…	0.1250	0.1266	0.1286	0.1088	0.1090	0.1105
6	32	…	…	0.1380	0.1402	0.1422	0.1177	0.1182	0.1197
6	…	…	36	0.1380	0.1397	0.1417	0.1200	0.1202	0.1217
6	…	40	…	0.1380	0.1396	0.1416	0.1218	0.1220	0.1235
8	32	…	…	0.1640	0.1662	0.1682	0.1437	0.1442	0.1457
8	…	36	…	0.1640	0.1657	0.1677	0.1460	0.1462	0.1477
8	…	…	40	0.1640	0.1656	0.1676	0.1478	0.1480	0.1495
10	24	…	…	0.1900	0.1928	0.1948	0.1629	0.1634	0.1649
10	…	32	…	0.1900	0.1922	0.1942	0.1697	0.1702	0.1717
12	24	…	…	0.2160	0.2188	0.2208	0.1889	0.1894	0.1909
12	…	28	…	0.2160	0.2184	0.2204	0.1928	0.1933	0.1948
14	…	…	24	0.2420	0.2448	0.2473	0.2149	0.2154	0.2174

All dimensions are given in inches.

Lead Tolerance: Plus or minus 0.003 inch per inch of thread. *Angle Tolerance:* Plus or minus 45 min. in half angle and 65 min. in full angle for 20 to 28 threads per inch; plus or minus 60 min. in half angle and 90 min. in full angle for 30 or more threads per inch.

Table 6a. ANSI Standard Taper Pipe Taps — Cut Thread Tolerances for NPT and Ground Thread Tolerances for NPT, NPTF, and ANPT *ASME B94.9-1999*

Nominal Size	Threads per Inch NPT, NPTF, or ANPT	Gage Measurement[a]			Taper per Inch on Diameter, Inches			
			Tolerance Plus or Minus		Cut Thread		Ground Thread	
		Projection Inches	Cut Thread	Ground Thread	Min.	Max.	Min.	Max.
1/16	27	0.312	0.0625	0.0625	0.0599	0.0703	0.0599	0.0651
1/8	27	0.312	0.0625	0.0625	0.0599	0.0703	0.0599	0.0651
1/4	18	0.459	0.0625	0.0625	0.0599	0.0703	0.0599	0.0651
3/8	18	0.454	0.0625	0.0625	0.0599	0.0703	0.0599	0.0651
1/2	14	0.579	0.0625	0.0625	0.0599	0.0677	0.0599	0.0651
3/4	14	0.565	0.0625	0.0625	0.0599	0.0677	0.0599	0.0651
1	11½	0.678	0.0937	0.0937	0.0599	0.0677	0.0599	0.0651
1¼	11½	0.686	0.0937	0.0937	0.0599	0.0677	0.0599	0.0651
1½	11½	0.699	0.0937	0.0937	0.0599	0.0677	0.0599	0.0651
2	11½	0.667	0.0937	0.0937	0.0599	0.0677	0.0599	0.0651
2½	8	0.925	0.0937	0.0937	0.0612	0.0664	0.0612	0.0651
3	8	0.925	0.0937	0.0937	0.0612	0.0664	0.0612	0.0651
3½[b]	8	0.938	1/8	1/8	47/64[c]	51/64[c]	47/64[c]	25/32[c]
4[b]	8	0.950	1/8	1/8	47/64[c]	51/64[c]	47/64[c]	25/32[c]

[a] Distance that small end of tap projects through L1 taper ring gage (see ANSI B1.20.3).

[b] No longer included in ASME B94.9-1999 shown for reference only.

[c] Taper per foot, inches.

All dimensions are given in inches.

Lead Tolerance: Plus or minus 0.003 inch per inch of cut thread and plus or minus 0.0005 inch per inch of ground thread.

Angle Tolerance: Plus or minus 40 min. in half angle and 60 min. in full angle for 8 cut threads per inch; plus or minus 45 min. in half angle and 60 min. in full angle for 11½ to 27 cut threads per inch; plus or minus 25 min. in half angle for 8 ground threads per inch; and plus and minus 30 min. in half angle for 11½ to 27 ground threads per inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6b. ANSI Taper Pipe Thread — Widths of Flats at Tap Crests and Roots for Cut Thread NPT and Ground Thread NPT, ANPT, and NPTF *ASME B94.9-1999*

Threads per Inch	Tap Flat Width at	Column I NPT—Cut and Ground Thread ANPT—Ground Thread		Column II NPTF—Cut and Ground Thread	
		Minimum[a]	Maximum	Minimum[a]	Maximum
27	{ Major Diameter	0.0014	0.0041	0.0040	0.0055
	{ Minor Diameter	…	0.0041	…	0.0040
18	{ Major Diameter	0.0021	0.0057	0.0050	0.0065
	{ Minor Diameter	…	0.0057	…	0.0050
14	{ Major Diameter	0.0027	0.0064	0.0050	0.0065
	{ Minor Diameter	…	0.0064	…	0.0050
11½	{ Major Diameter	0.0033	0.0073	0.0060	0.0083
	{ Minor Diameter	…	0.0073	…	0.0060
8	{ Major Diameter	0.0048	0.0090	0.0080	0.0103
	{ Minor Diameter	…	0.0090	…	0.0080

[a] Minimum minor diameter falts are not specified. May be sharp as practicable.

All dimensions are given in inches.

Note: Cut Thread taps made to Column I are marked NPT but are not recommended for ANPT applications. Ground Thread taps made to Column I are marked NPT and may be used for NPT and ANPT applications. Ground Thread taps made to Column II are marked NPTF and used for Dryseal application.

Table 7a. ANSI Standard Straight Pipe Taps (NPSF—Dryseal) Ground Thread Limits *ASME B94.9-1999*

Nominal Size, Inches	Threads per Inch	Major Diameter		Pitch Diameter			
		Min. *G*	Max. *H*	Plug at Gaging Notch *E*	Min. *K*	Max. *L*	Minor[a] Dia. Flat, Max.
1/16	27	0.3008	0.3018	0.2812	0.2772	0.2777	0.004
1/8	27	0.3932	0.3942	0.3736	0.3696	0.3701	0.004
1/4	18	0.5239	0.5249	0.4916	0.4859	0.4864	0.005
3/8	18	0.6593	0.6603	0.6270	0.6213	0.6218	0.005
1/2	14	0.8230	0.8240	0.7784	0.7712	0.7717	0.005
3/4	14	1.0335	1.0345	0.9889	0.9817	0.9822	0.005

[a] As specified or sharper.

Formulas For American Dryseal (NPSF) Ground Thread Taps					
Nominal Size, Inches	Major Diameter		Pitch Diameter		Max. Minor Dia.
	Min. *G*	Max. *H*	Min. *K*	Max. *L*	
1/16	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$
1/8	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$
1/4	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$
3/8	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$
1/2	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$
3/4	$H - 0.0010$	$K + Q - 0.0005$	$L - 0.0005$	$E - F$	$M - Q$

Values to Use in Formulas				
Threads per Inch	*E*	*F*	*M*	*Q*
27	Pitch diameter of plug at gaging notch	0.0035	Actual measured pitch diameter	0.0251
18		0.0052		0.0395
14		0.0067		0.0533

All dimensions are given in inches.

Lead Tolerance: Plus or minus 0.0005 inch within any two threads not farther apart than one inch.

Angle Tolerance: Plus or minus 30 min. in half angle for 14 to 27 threads per inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. ANSI Standard Straight Pipe Taps (NPS)
Cut Thread Limits *ASME B94.9-1999*

Nominal Size	Threads per Inch, NPS, NPSC	Size at Gaging Notch	Pitch Diameter		Values to Use in Formulas		
			Min.	Max.	*A*	*B*	*C*
1/8	27	0.3736	0.3721	0.3751	0.0267	0.0296	0.0257
1/4	18	0.4916	0.4908	0.4938	} 0.0408	0.0444	0.0401
3/8	18	0.6270	0.6257	0.6292			
1/2	14	0.7784	0.7776	0.7811	} 0.0535	0.0571	0.0525
3/4	14	0.9889	0.9876	0.9916			
1	11 1/2	1.2386	1.2372	1.2412	0.0658	0.0696	0.0647

The following are approximate formulas, in which M = measured pitch diameter in inches:

Major dia., min. = $M + A$

Major dia., max. = $M + B$ Minor dia., max. = $M - C$

All dimensions are given in inches.

Lead Tolerance: Plus or minus 0.003 inch per inch of thread.

Angle Tolerance: All pitches, plus or minus 45 min. in half angle and 68 min. in full angle. Taps made to these specifications are to be marked NPS and used for NPSC thread form.

Table 7c. ANSI Standard Straight Pipe Taps (NPS)
Ground Thread Limits *ASME B94.9-1999*

Nominal Size, Inches	Threads per Inch, NPS, NPSC, NPSM	Major Diameter			Pitch Diameter		
		Plug at Gaging Notch	Min. *G*	Max. *H*	Plug at Gaging Notch *E*	Min. *K*	Max. *L*
1/8	27	0.3983	0.4022	0.4032	0.3736	0.3746	0.3751
1/4	18	0.5286	0.5347	0.5357	0.4916	0.4933	0.4938
3/8	18	0.6640	0.6701	0.6711	0.6270	0.6287	0.6292
1/2	14	0.8260	0.8347	0.8357	0.7784	0.7806	0.7811
3/4	14	1.0364	1.0447	1.0457	0.9889	0.9906	0.9916
1	11 1/2	1.2966	1.3062	1.3077	1.2386	1.2402	1.2412

Formulas for NPS Ground Thread Taps[a]						
Nominal Size	Major Diameter		Minor Dia.	Threads per Inch	*A*	*B*
	Min. *G*	Max. *H*	Max.			
1/8	$H - 0.0010$	$(K + A) - 0.0010$	$M - B$	27	0.0296	0.0257
1/4 to 3/4	$H - 0.0010$	$(K + A) - 0.0020$	$M - B$	18	0.0444	0.0401
1	$H - 0.0015$	$(K + A) - 0.0021$	$M - B$	14	0.0571	0.0525
				11 1/2	0.0696	0.0647

The maximum Pitch Diameter of tap is based upon an allowance deducted from the maximum product pitch diameter of NPSC or NPSM, whichever is smaller.

The minimum Pitch Diameter of tap is derived by subtracting the ground thread pitch diameter tolerance for actual equivalent size.

[a] In the formulas, M equals the actual measured pitch diameter.

All dimensions are given in inches.

Lead tolerance: Plus or minus 0.0005 inch within any two threads not farther apart than one inch.

Angle Tolerance: All pitches, plus or minus 30 min. in half angle. Taps made to these specifications are to be marked NPS and used for NPSC and NPSM.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8a. ANSI Standard Ground Thread Straight Fluted Taps
Machine Screw Sizes *ASME B94.9-1999*



STANDARD NUMBER OF FLUTES



OPTIONAL NUMBER OF FLUTES

Size	Basic Major Diameter	Threads per Inch			No. of Flutes	Pitch Dia.Limits and Chamfers[a]				Length Overall *A*	Length of Thread *B*	Length of Square *C*	Diameter of Shank *D*	*E*
		NC UNC	NF UNF	NS UNS		H1	H2	H3	H7					
0	0.060	…	80	…	2	TPB	PB	…	…	1 5/8	5/16	3/16	0.141	0.110
1	0.073	64	…	…	2	TPB	P	…	…	1 11/16	3/16	3/16	0.141	0.110
1	0.073	…	72	…	2	TPB	PB	…	…	1 11/16	3/8	3/16	0.141	0.110
2	0.086	56	…	…	2[b]	…	PB	…	…	1 3/4	7/16	3/16	0.141	0.110
2	0.086	56	…	…	3	TPB	TPB	…	…	1 3/4	7/16	3/16	0.141	0.110
2	0.086	…	64	…	3	…	TPB	…	…	1 3/4	7/16	3/16	0.141	0.110
3	0.099	48	…	…	2[b]	…	PB	…	…	1 13/16	1/2	3/16	0.141	0.110
3	0.099	48	…	…	3	P	TPB	…	…	1 13/16	1/2	3/16	0.141	0.110
3	0.099	…	56	…	3	…	TPB	…	…	1 13/16	1/2	3/16	0.141	0.110
4	0.112	…	…	36	3	…	TPB	…	…	1 7/8	9/16	3/16	0.141	0.110
4	0.112	40	…	…	2[b]	P	PB	…	…	1 7/8	9/16	3/16	0.141	0.110
4	0.112	40	…	…	3	…	TPB	…	…	1 7/8	9/16	3/16	0.141	0.110
4	0.112	…	48	…	3	…	TPB	…	…	1 7/8	9/16	3/16	0.141	0.110
5	0.125	40	…	…	2[b]	…	PB	…	…	1 15/16	5/8	3/16	0.141	0.110
5	0.125	40	…	…	3	P	TPB	…	…	1 15/16	5/8	3/16	0.141	0.110
5	0.125	…	44	…	3	…	TPB	…	…	1 15/16	5/8	3/16	0.141	0.110
6	0.138	32	…	…	2[b]	P	PB	PB	…	2	11/16	3/16	0.141	0.110
6	0.138	32	…	…	3	TPB	TPB	TPB	PB	2	11/16	3/16	0.141	0.110
6	0.138	…	40	…	2[b]	…	P	…	…	2	11/16	3/16	0.141	0.110
6	0.138	…	40	…	3	P	TPB	…	…	2	11/16	3/16	0.141	0.110
8	0.164	32	…	…	2[b]	P	PB	PB	…	2 1/8	3/4	1/4	0.168	0.131
8	0.164	32	…	…	3[b]	…	PB	PB	PB	2 1/8	3/4	1/4	0.168	0.131
8	0.164	32	…	…	4	TPB	TPB	TPB	PB	2 1/8	3/4	1/4	0.168	0.131
8	0.164	…	36	…	4	…	TPB	…	…	2 1/8	3/4	1/4	0.168	0.131
10	0.190	24	…	…	2*	…	PB	PB	…	2 3/8	7/8	1/4	0.194	0.152
10	0.190	24	…	…	3[b]	…	P	PB	…	2 3/8	7/8	1/4	0.194	0.152
10	0.190	…	32	…	2[b]	P	PB	PB	…	2 3/8	7/8	1/4	0.194	0.152
10	0.190	…	32	…	3[b]	…	PB	PB	PB	2 3/8	7/8	1/4	0.194	0.152
10	0.190	24	32	…	4	TPB	TPB	TPB	PB	2 3/8	7/8	1/4	0.194	0.152
12	0.216	24	…	…	4	…	…	TPB	…	2 3/8	15/16	9/32	0.220	0.165
12	0.216	…	28	…	4	…	…	TPB	…	2 3/8	15/16	9/32	0.220	0.165

[a] Chamfer designations are: T = taper, P = plug, and B = bottoming.

[b] Optional number of flutes.

All dimensions are given in inches.

These taps are standard as high-speed steel taps with ground threads, with standard and optional number of flutes and pitch diameter limits and chamfers as given in the table.

These are style 1 taps and have external centers on thread and shank ends (may be removed on thread end of bottoming taps).

For standard thread limits see Table 3. For eccentricity tolerances see Table 22.

Tolerances: Numbers 0 to 12 size range — $A, \pm 1/32$; $B, \pm 3/64$; $C, \pm 1/32$; $D, -0.0015$; $E, -0.004$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8b. ANSI Standard Cut Thread Straight Fluted Taps
Machine Screw Sizes *ASME B94.9-1999*



Size	Basic Major Diameter	Threads per Inch					Number of Flutes	Dimensions				
		Carbon Steel			HS Steel			Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Diameter of Shank, *D*	Size of Square, *E*
		NC UNC	NF UNF	NS UNS	NC UNC	NF UNF						
0	0.060	…	80[a]	…	…	…	2	1 5/8	5/16	3/16	0.141	0.110
1	0.073	64[a]	72[a]	…	…	…	2	1 11/16	3/8	3/16	0.141	0.110
2	0.086	56	64[a]	…	…	…	3	1 3/4	7/16	3/16	0.141	0.110
3	0.099	48[a]	56[a]	…	…	…	3	1 13/16	1/2	3/16	0.141	0.110
4	0.112	40	48[a]	36[a]	40[a]	…	3	1 7/8	9/16	3/16	0.141	0.110
5	0.125	40	…	…	40[a]	…	3	1 15/16	5/8	3/16	0.141	0.110
6	0.138	32	40[a]	36[a]	32	…	3	2	11/16	3/16	0.141	0.110
8	0.164	32	36[a]	40[a]	32	…	4	2 1/4	3/4	1/4	0.168	0.131
10	0.190	24	32	…	24	32	4	2 3/8	7/8	1/4	0.194	0.152
12	0.216	24	28[a]	…	24	…	4	2 3/8	15/16	9/32	0.220	0.165
14	0.242	…	…	24[a]	…	…	4	2 1/2	1	5/16	0.255	0.191

[a] These taps are standard with plug chamfer only. All others are standard with taper, plug or bottoming chamfer.

Tolerances for General Dimensions					
Element	Range	Tolerance	Element	Range	Tolerance
Length Overall, *A*	0 to 14 incl	±1/32	Diameter of Shank, *D*	0 to 12 incl	–0.004
Length of Thread, *B*	0 to 12 incl	±3/64		14	–0.005
	14	±1/16	Size of Square, *E*	0 to 14 incl	–0.004
Length of Square, *C*	0 to 14 incl	±1/32			

All dimensions are given in inches.

Styles 1 and 2 cut thread taps have optional style centers on thread and shank ends.

For standard thread limits see Table 5. For eccentricity tolerances see Table 22.

Table 9. ANSI Standard Nut Taps (formerly *ANSI/ASME B94.9-1987)*



Dia. of Tap	Threads per Inch NC,UNC	Number of Flutes	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Diameter of Shank, *D*	Size of Square, *E*
1/4	20	4	5	1 5/8	9/16	0.185	0.139
5/16	18	4	5 1/2	1 13/16	5/8	0.240	0.180
3/8	16	4	6	2	11/16	0.294	0.220
1/2	13	4	7	2 1/2	7/8	0.400	0.300

Tolerances for General Dimensions					
Element	Diameter Range	Tolerance	Element	Diameter Range	Tolerance
Overall Length, *A*	1/4 to 1/2	±1/16	Shank Diameter,D	1/4 to 1/2	–0.005
Thread Length, *B*	1/4 to 1/2	±1/16	Size of Square,E	1/4 to 1/2	–0.004
Square Length, *C*	1/4 to 1/2	±1/32			

All dimensions are given in inches. These ground thread high-speed steel taps are standard in H3 limit only. All taps have an internal center in thread end. For standard limits see Table 2.

Chamfer *J* is made 1/2 ro 3/4 the thread length of *B*.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ANSI Standard Spiral-Pointed Taps
Machine Screw Sizes *ASME B94.9-1999*



STYLE 1

High-Speed Steel Taps with Ground Threads

Size	Basic Major Diameter	Threads per Inch NC UNC	Threads per Inch NF UNF	Threads per Inch NS UNS	No. of Flutes	Pitch Dia. Limits and Chamfers† H1	H2	H3	H7	Length Overall *A*	Length of Thread *B*	Length of Square *C*	Diameter of Shank *D*	Size of Square *E*
0	0.060	…	80	…	2	PB	PB	…	…	1 5/8	5/16	3/16	0.141	0.110
1	0.073	64	72	…	2	P	P	…	…	1 11/16	3/8	3/16	0.141	0.110
2	0.086	56	…	…	2	PB	PB	…	…	1 3/4	7/16	3/16	0.141	0.110
2	0.086	…	64	…	2	…	P	…	…	1 3/4	7/16	3/16	0.141	0.110
3	0.099	48	…	…	2	…	PB	…	…	1 13/16	1/2	3/16	0.141	0.110
3	0.099	…	56	…	2	P	P	…	…	1 13/16	1/2	3/16	0.141	0.110
4	0.112	…	…	36	2	…	P	…	…	1 7/8	9/16	3/16	0.141	0.110
4	0.112	40	…	…	2	P	PB	…	…	1 7/8	9/16	3/16	0.141	0.110
4	0.112	…	48	…	2	P	PB	…	…	1 7/8	9/16	3/16	0.141	0.110
5	0.125	40	…	…	2	P	PB	…	…	1 15/16	5/8	3/16	0.141	0.110
5	0.125	…	44	…	2	…	P	…	…	1 15/16	5/8	3/16	0.141	0.110
6	0.138	32	…	…	2	P	PB	PB	PB	2	11/16	3/16	0.141	0.110
6	0.138	…	40	…	2	…	PB	…	…	2	11/16	3/16	0.141	0.110
8	0.164	32	…	…	2	P	PB	PB	PB	2 1/8	3/4	1/4	0.168	0.131
8	0.164	…	36	…	2	…	P	…	…	2 1/8	3/4	1/4	0.168	0.131
10	0.190	24	…	…	2	P	PB	PB	P	2 3/8	7/8	1/4	0.194	0.152
10	0.190	…	32	…	2	PB	PB	PB	P	2 3/8	7/8	1/4	0.194	0.152
12	0.216	24	…	…	2	…	…	PB	…	2 3/8	15/16	9/32	0.220	0.165
12	0.216	…	28	…	2	…	…	P	…	2 3/8	15/16	9/32	0.220	0.165

High-Speed and Carbon Steel Taps with Cut Threads

Size	Basic Major Diameter	Threads per Inch Carbon Steel NC UNC	Threads per Inch Carbon Steel NF UNF	Threads per Inch HS Steel NC UNC	Threads per Inch HS Steel NF UNF	No. of Flutes	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Diameter of Shank, *D*	Size of Square, *E*
4	0.112	…	…	40	…	2	1 7/8	9/16	3/16	0.141	0.110
5	0.125	…	…	40	…	2	1 15/16	5/8	3/16	0.141	0.110
6	0.138	32	…	32	…	2	2	11/16	3/16	0.141	0.110
8	0.164	32	…	32	…	2	2 1/8	3/4	1/4	0.168	0.131
10	0.190	24	32	24	32	2	2 3/8	7/8	1/4	0.194	0.152
12	0.216	…	…	24	…	2	2 3/8	15/16	9/32	0.220	0.165

Tolerances for General Dimensions

Element	Size Range	Tolerance Ground Thread	Tolerance Cut Thread	Element	Size Range	Tolerance Ground Thread	Tolerance Cut Thread
Overall Length, *A*	0 to 12	±1/32	±1/32	Shank Diameter, *D*	0 to 12	–0.0015	–0.004
Thread Length, *B*	0 to 12	±3/64	±3/64	Size of Square, *E*	0 to 12	–0.004	–0.004
Square Length, *C*	0 to 12	±1/32	±1/32				

All dimensions are in inches. Chamfer designations are: P = plug and B = bottoming. Cut thread taps are standard with plug chamfer only. Style 1 ground thread taps have external centers on thread and shank ends (may be removed on thread end of bottoming taps). Style 1 cut thread taps have optional style centers on thread and shank ends. Standard thread limits for ground threads are given in Table 3 and for cut threads in Table 5. For eccentricity tolerances see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ANSI Standard Spiral Pointed Only and Regular and Fast Spiral-Fluted Taps — Machine Screw Sizes *ASME B94.9-1999*

STYLE 1



Size	Basic Major Diameter	Threads per Inch		No. of Flutes	Pitch Dia. Limits & Chamfers[a]		Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Diameter of Shank, *D*	Size of Square, *E*
		NC UNC	NF UNF		H2	H3					
3[b]	0.099	48	…	2	PB	…	1 13/16	1/2	3/16	0.141	0.110
4	0.112	40	…	2	PB	…	1 7/8	9/16	3/16	0.141	0.110
5	0.125	40	…	2	PB	…	1 15/16	5/8	3/16	0.141	0.110
6	0.138	32	…	2	…	PB	2	11/16	3/16	0.141	0.110
8	0.164	32	…	2[c], 3[b]	…	PB	2 1/8	3/4	1/4	0.168	0.131
10	0.190	24	32	2[c], 3[b]	…	PB	2 3/8	7/8	1/4	0.194	0.152
12[d]	0.216	24	…	2[c], 3[b]	…	PB	2 3/8	15/16	9/32	0.220	0.165

[a] Bottom chamfer applies only to regular and fast spiral-fluted machine screw taps.
[b] Applies only to fast spiral-fluted machine screw taps.
[c] Does not apply to fast spiral-fluted machine screw taps.
[d] Does not apply to regular spiral-fluted machine screw taps.

Tolerances for General Dimensions					
Element	Size Range	Tolerance	Element	Size Range	Tolerance
Overall Length, *A*	3 to 12	±1/32	Shank Diameter, *D*	3 to 12	–0.0015
Thread Length, *B*	3 to 12	±3/64	Size of Square, *E*	3 to 12	–0.004
Square Length, *C*	3 to 12	±1/32			

All dimensions are given in inches. These standard taps are made of high-speed steel with ground threads. For standard thread limits see Table 3. For eccentricity tolerances see Table 22.

Spiral Pointed Only Taps: These taps are standard with plug chamfer only. They are provided with a spiral point only; the balance of the threaded section is left unfluted. These Style 1 taps have external centers on thread and shank ends.

Regular Spiral Fluted Taps: These taps have right-hand spiral flutes with a helix angle of from 25 to 35 degrees.

Fast Spiral Fluted Taps: These taps have right-hand spiral flutes with a helix angle of from 45 to 60 degrees.

Both regular and fast spiral-fluted Style 1 taps have external centers on thread and shank ends (may be removed on thread end of bottoming taps).

Chamfer designations: P = plug and B = bottoming.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12a. ANSI Standard Ground Thread Straight Fluted Taps
Fractional Sizes *ASME B94.9-1999*



STYLE 2



STYLE 3

Dia. of Tap	Threads per Inch NC UNC	Threads per Inch NF UNF	No. of Flutes	Pitch Diameter Limits and Chamfers H1	H2	H3	H4	H5	Dimensions Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Dia. of Shank, *D*	Size of Square, *E*
1/4	20	…	4	TPB	TPB	TPB	…	PB	2 1/2	1	5/16	0.255	0.191
1/4	…	28	4	PB	PB	TBP	PB	…	2 1/2	1	5/16	0.255	0.191
5/16	18	…	4	PB	PB	TPB	…	PB	2 23/32	1 1/8	3/8	0.318	0.238
5/16	…	24	4	PB	P	TPB	PB	…	2 23/32	1 1/8	3/8	0.318	0.238
3/8	16	…	4	PB	PB	TPB	…	PB	2 15/16	1 1/4	7/16	0.381	0.286
3/8	…	24	4	PB	PB	TPB	PB	…	2 15/16	1 1/4	7/16	0.381	0.286
7/16	14	20	4	…	…	TPB	…	PB	3 5/32	1 7/16	13/32	0.323	0.242
1/2	13	…	4	P	…	TPB	…	PB	3 3/8	1 21/32	7/16	0.367	0.275
1/2	…	20	4	PB	…	TPB	…	P	3 3/8	1 21/32	7/16	0.367	0.275
9/16	12	…	4	…	…	TPB	…	P	3 19/32	1 21/32	1/2	0.429	0.322
9/16	…	18	4	…	P	TPB	…	P	3 19/32	1 21/32	1/2	0.429	0.322
5/8	11	…	4	…	P	TPB	…	PB	3 13/16	1 13/16	9/16	0.480	0.360
5/8	…	18	4	…	P	TPB	…	PB	3 13/16	1 13/16	9/16	0.480	0.360
11/16 [a]	…	…	4	…	…	TPB	…	…	4 1/32	1 13/16	5/8	0.542	0.406
3/4	10	…	4	…	P	TPB	…	PB	4 1/4	2	11/16	0.590	0.442
3/4	…	16	4	P	P	TPB	…	PB	4 1/4	2	11/16	0.590	0.442
7/8 [b]	9	…	4	…	…	…	TPB	…	4 11/16	2 7/32	3/4	0.697	0.523
7/8	…	14	4	…	P	…	TPB	…	4 11/16	2 7/32	3/4	0.697	0.523
1 [b]	8	…	4	…	…	…	TPB	…	5 1/8	2 1/2	13/16	0.800	0.600
1	…	12	4	…	…	…	TPB	…	5 1/8	2 1/2	13/16	0.800	0.600
1 [c]	…	…	4	…	…	…	TPB	…	5 1/8	2 1/2	13/16	0.800	0.600
1 1/8	7	12	4	…	…	…	TPB	…	5 7/16	2 9/16	7/8	0.896	0.672
1 1/4	7	12 [d]	4	…	…	…	TPB	…	5 3/4	2 9/16	1	1.021	0.766
1 3/8	6	12 [d]	4	…	…	…	TPB	…	6 1/16	3	1 1/16	1.108	0.831
1 1/2	6	12 [d]	4	…	…	…	TPB	…	6 3/8	3	1 1/8	1.233	0.925

[a] This size has 11 or 16 threads per inch NS-UNS.

[b] These sizes are also available with plug chamfer in H6 pitch diameter limits.

[c] This size has 14 threads per inch NS-UNS.

[d] In these sizes NF-UNF thread taps have six flutes.

Tolerances for General Dimensions					
Element	Diameter Range	Tolerance	Element	Diameter Range	Tolerance
Length Overall, *A*	1/4 to 1 incl	±1/32	Diameter of Shank, *D*	1/4 to 5/8 incl	–0.0015
	1 1/8 to 1 1/2 incl	±1/16		11/16 to 1 1/2 incl	–0.002
Length of Thread, *B*	1/4 to 1/2 incl	±1/16			
	9/16 to 1 1/2 incl	±3/32	Size of Square, *E*	1/4 to 1/2 incl	–0.004
Length of Square, *C*	1/4 to 1 incl	±1/32		9/16 to 1 incl	–0.006
	1 1/8 to 1 1/2 incl	±1/16		1 1/8 to 1 1/2 incl	–0.008

All dimensions are given in inches.

These taps are standard in high-speed steel.

Chamfer designations are: T = taper, P = plug, and B = bottoming.

Style 2 taps, 3/8 inch and smaller, have external center on thread end (may be removed on bottoming taps) and external partial cone center on shank end with length of come approximately one-quarter of diameter of shank.

Style 3 taps, larger than 3/8 inch, have internal center in thread and shank ends.

For standared thread limits see Table 2. For eccentricity tolerances see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12b. ANSI Standard Cut Thread Straight Fluted Taps
Fractional Sizes *ASME B94.9-1999*



Dia. of Tap	Threads Per Inch: Carbon Steel NC UNC	Carbon Steel NF UNF	Carbon Steel NS UNS	HS Steel NC UNC	HS Steel NF UNF	No. of Flutes	Dimensions: Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Dia. of Shank, *D*	Size of Square, *E*
1/8	…	…	40	…	…	3	1 15/16	5/8	3/16	0.141	0.110
5/32	…	…	32	…	…	4	2 1/8	3/4	1/4	0.168	0.131
3/16	…	…	24, 32	…	…	4	2 3/8	7/8	1/4	0.194	0.152
1/4	20	28	…	20	28	4	2 1/2	1	5/16	0.255	0.191
5/16	18	24	…	18	24	4	2 23/32	1 1/8	3/8	0.318	0.238
3/8	16	24	…	16	24	4	2 15/16	1 1/4	7/16	0.381	0.286
7/16	14	20	…	14	20	4	3 5/32	1 7/16	13/32	0.323	0.242
1/2	13	20	…	13	20	4	3 3/8	1 21/32	7/16	0.367	0.275
9/16	12	18	…	12	…	4	3 19/32	1 21/32	1/2	0.429	0.322
5/8	11	18	…	11	18	4	3 13/16	1 13/16	9/16	0.480	0.360
3/4	10	16	…	10	16	4	4 1/4	2	11/16	0.590	0.442
7/8	9	14	…	9	14	4	4 11/16	2 7/32	3/4	0.697	0.523
1	8	…	14[a]	8	…	4	5 1/8	2 1/2	13/16	0.800	0.600
1 1/8	7	12	…	…	…	4	5 7/16	2 9/16	7/8	0.896	0.672
1 1/4	7	12[b]	…	…	…	4	5 3/4	2 9/16	1	1.021	0.766
1 3/8	6[a]	12[ba]	…	…	…	4	6 1/16	3	1 1/16	1.108	0.831
1 1/2	6	12[ba]	…	…	…	4	6 3/8	3	1 1/8	1.233	0.925
1 3/4	5[a]	…	…	…	…	6	7	3 3/16	1 1/4	1.430	1.072
2	4 1/2[a]	…	…	…	…	6	7 5/8	3 9/16	1 3/8	1.644	1.233

[a] Standard in plug chamfer only.
[b] In these sizes NF-UNF thread taps have six flutes.

Tolerances for General Dimensions					
Elements	Range	Tolerance	Elements	Range	Tolerance
Length Overall, *A*	1/16 to 1 1 1/8 to 2	±1/32 ±1/16	Diameter of Shank, *D*	1/16 to 3/16 1/4 to 1 1 1/8 to 2	–0.004 –0.005 –0.007
Length of Thread, *B*	1/16 to 3/16 1/4 to 1/2 9/16 to 1 1/2 1 5/8 to 2	±3/64 ±1/16 ±3/32 ±1/8	Size of Square, *E*	1/16 to 1/2 9/16 to 1 1 1/8 to 2	–0.004 –0.006 –0.008
Length of Square, *C*	1/16 to 1 1 1/8 to 2	±1/32 ±1/16			

All dimensions are given in inches.
These taps are standard in carbon steel and high-speed steel.
Except where indicated, these taps are standard with taper, plug, or bottoming chamfer.
Cut thread taps, sizes 3/8 inch and smaller have optional style center on thread and shank ends; sizes larger than 3/8 inch have internal centers in thread and shank ends.
For standard thread limits see Table 1. For eccentricity tolerances see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ANSI Standard Straight Fluted (Optional Number of Flutes) and Spiral Pointed Taps—Fractional Sizes *ASME B94.9-1999*



Dia. of Tap	Threads per Inch NC, UNC	Threads per Inch NF, UNF	No. of Flutes	Pitch Diameter Limits and Chamfers[ab] H1	H2	H3	H4	H5	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Dia. of Shank, *D*	Size of Square, *E*
Ground Thread High-Speed-Steel Straight Fluted Taps													
1/4	20	…	2	…	…	PB	…	…	2 1/2	1	5/16	0.255	0.191
1/4	20	…	3	P	P	PB	…	P	2 1/2	1	5/16	0.255	0.191
1/4	…	28	2, 3	…	…	PB	…	…	2 1/2	1	5/16	0.255	0.191
5/16	18	…	2	…	…	PB	…	…	2 23/32	1 1/8	3/8	0.318	0.238
5/16	18	…	3	…	…	PB	…	…	2 23/32	1 1/8	3/8	0.318	0.238
5/16	…	24	3	…	…	PB	…	…	2 23/32	1 1/8	3/8	0.318	0.238
3/8	16	…	3	…	…	PB	…	…	2 15/16	1 1/4	7/16	0.381	0.286
3/8	…	24	3	…	…	PB	…	…	2 15/16	1 1/4	7/16	0.381	0.286
7/16	14	…	3	…	…	P	…	…	3 5/32	1 7/16	13/32	0.323	0.242
7/16	…	20	3	…	…	P	…	…	3 5/32	1 7/16	13/32	0.323	0.242
1/2	13	…	3	…	…	PB	…	…	3 3/8	1 21/32	7/16	0.367	0.275
1/2	…	20	3	…	…	P	…	…	3 3/8	1 21/32	7/16	0.367	0.275
Ground Thread High-Speed-Steel and Cut Thread High-Speed-Steel Spiral Pointed Taps													
1/4	20	…	2	P	P	PB	…	P	2 1/2	1	5/16	0.255	0.191
1/4[a]	20	…	3	…	…	P	…	P	2 1/2	1	5/16	0.255	0.191
1/4	…	28	2	P	P	PB	P	…	2 1/2	1	5/16	0.255	0.191
1/4[a]	…	28	3	…	P	…	P	…	2 1/2	1	5/16	0.255	0.191
5/16	18	…	2	P	P	PB	…	P	2 23/32	1 1/8	3/8	0.318	0.238
5/16[a]	18	…	3	…	…	P	…	P	2 23/32	1 1/8	3/8	0.318	0.238
5/16	…	24	2	P	P	PB	P	…	2 23/32	1 1/8	3/8	0.318	0.238
5/16[a]	…	24	3	…	P	P	P	…	2 23/32	1 1/8	3/8	0.318	0.238
3/8	16	…	3	P	P	P	…	P	2 15/16	1 1/4	7/16	0.381	0.286
3/8	…	24	3	P	P	P	P	…	2 15/16	1 1/4	7/16	0.381	0.286
7/16[a]	14	20	3	…	P[c]	P	…	P	3 5/32	1 7/16	13/32	0.323	0.242
1/2	13	20[a]	3	P	P	P	…	P	3 3/8	1 21/32	7/16	0.367	0.275
5/8[a]	11	18	3	…	…	P	…	P[d]	3 13/16	1 13/16	9/16	0.480	0.360
3/4[a]	10	16	3	…	…	P	…	P[e]	4 1/4	2	11/16	0.590	0.442

[a] Applies only to ground thread high-speed-steel taps.

[b] Cut thread high-speed-steel taps are standard with plug chamfer only.

[c] Applies only to 7/16-14 tap.

[d] Applies only to 5/8-11 tap.

[e] Applies ony to 3/4-10 tap. For eccentricity tolerances see Table 22.

Tolerances for General Dimensions							
Element	Diameter Range	Tolerance Ground Thread	Tolerance Cut Thread	Element	Diameter Range	Tolerance Ground Thread	Tolerance CutThread
Overall Length, *A*	1/4 to 3/4	±1/32	±1/32	ShankDiameter,*D*	1/4 to 5/8 3/4	–0.0015 –0.0020	–0.005 …
Thread Length, *B*	1/4 to 1/2 5/8 to 3/4	±1/16 ±1/32	±1/16	Size of Square,*E*	1/4 to 1/2 5/8 to 3/4	–0.0040 –0.0060	–0.004 …
Square Length, *C*	1/4 to 3/4	±1/32					

All dimensions are given in inches. P = plug and B = bottoming. Ground thread taps — Style 2, 3/8 inch and smaller, have external center on thread end (may be removed on bottoming taps) and external partial cone center on shank end, with length of cone approximately 1/4 of shank diameter. Ground thread taps—Style 3, larger than 3/8 inch, have internal center in thread and shank ends. Cut thread-taps, 3/8 inch and smaller have optional style center on thread and shank ends; sizes larger than 3/8 inch have internal centers in thread and shank ends. For standard thread limits see Tables 1 and 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Other Types of ANSI Standard Taps *ASME B94.9-1999*



Dia. of Tap	Threads per Inch NC UNC	Threads per Inch NF UNF	Number of Flutes	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Dia. of Shank, *D*	Size of Square, *E*
1/4	20	28[a]	2[b,c], 3[a]	2 1/2	1	5/16	0.255	0.191
5/16	18	24[a]	2[d], 3[a]	2 23/32	1 1/8	3/8	0.318	0.238
3/8	16	24[a]	3	2 15/16	1 1/4	7/16	0.381	0.286
7/16[e]	14	20	3	3 5/32	1 7/16	13/32	0.323	0.242
1/2	13	20[a]	3	3 3/8	1 23/32	7/16	0.367	0.275

[a] Does not apply to spiral pointed only taps.
[b] Does not apply to spiral fluted taps with 28 threads per inch.
[c] Does not apply to fast spiral fluted taps.
[d] Applies only to spiral pointed only taps.
[e] Applies only to fast spiral fluted taps.

Tolerances for General Dimensions					
Element	Diameter Range	Tolerance	Element	Diameter Range	Tolerance
Overall Length, *A*	1/4 to 1/2	±1/32	Shank Diameter, *D*	1/4 to 1/2	−0.0015
Thread Length, *B*	1/4 to 1/2	±1/16	Size of Square, *E*	1/4 to 1/2	−0.004
Square Length, *C*	1/4 to 1/2	±1/32			

All dimensions are given in inches. These standard taps are made of high-speed steel with ground threads. For standard thread limits see Table 2.

Spiral Pointed Only Taps: These taps are standard with plulg chamfer only in H3 limit. They are provided with spiral point only. The balance of the threaded section is left unfluted.

Spiral Fluted Taps: These taps are standard with plug or bottoming chamfer in H3 limit and have right-hand spiral flutes with a helix angle of from 25 to 35 degrees.

Fast Spiral Fluted Taps: These taps are standard with plug or bottoming chamfer in H3 limit and have right-hand spiral flutes with a helix angle of from 45 to 60 degrees.

Style 2 taps, 3/8 inch and smaller, have external center on thread end (may be removed on bottoming taps) and external partial cone center on shank end with cone length approximately 1/4 shank diameter.

Style 3 taps larger than 3/8 inch have internal center in thread and shank ends.

For standard thread limits see Table 2. For eccentricity tolerances see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. ANSI Standard Pulley Taps *ASME B94.9-1999*



Dia. of Tap	Threads per Inch NC UNC	Number of Flutes	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Dia. of Shank, *D*	Length of Shank Close Tolerance, *T*[a]	Size of Square, *E*[b]	Length of Neck, *K*[c]
1/4	20	4	6, 8	1.00	0.31	0.2550	1.50	0.191	0.38
5/16	18	4	6, 8	1.13	0.38	0.3180	1.56	0.238	0.38
3/8	16	4	6, 8, 10	1.25	0.44	0.3810	1.63	0.286	0.38
7/16	14	4	6, 8	1.44	0.50	0.4440	1.69	0.333	0.44
1/2	13	4	6, 8, 10, 12	1.66	0.56	0.5070	1.69	0.380	0.50
5/8	11	4	6,8,10,12	1.81	0.69	0.6330	2.00	0.475	0.63
3/4	10	4	10, 12	2.00	0.75	0.7590	2.25	0.569	0.75

[a] *T* is minimum length of shank which is held to eccentricity tolerances.
[b] Size of square is equal to 0.75*D* to the nearest 0.001 inch.
[c] *K* neck optional with manufacturer.

Tolerances for General Dimensions					
Element	Diameter Range	Tolerance	Element	Diameter Range	Tolerance
Overall Length, *A*	1/4 to 3/4	±0.06	Shank Diameter, *D*	1/4 to 3/4	–0.0050
Thread Length, *B*	1/4 to 3/4	±0.06	Size of Square, *E*	1/4 to 1/2	–0.004
Square Length, *C*	1/4 to 3/4	±0.03		5/8 to 3/4	–0.006

All dimensions are given in inches. These ground thread high-speed steel taps are standard with plug chamfer in H3 limit only. All taps have an internal center in thread end. For standard thread limits see Table 2. For eccentricity tolerances see Table 22.

Table 16. ANSI Standard Ground Thread Spark Plug Taps Metric Sizes *ASME B94.9-1999*

Tap Diameter, mm	Pitch, mm	Number of Flutes	Overall Length, In. *A*	Thread Length, In. *B*	Square Length, In. *C*	Shank Dia., In. *D*	Square Size, In. *E*
14	1.25	4	3 19/32	1 21/32	1/2	0.429	0.322
18	1.50	4	4 1/32	1 13/16	5/8	0.542	0.406

These are high-speed steel Style 3 taps and have internal center in thread and shank ends. They are standard with plug chamfer only, right-hand threads with 60-degree form of thread.

Tolerances: Overall length, ± 1/32 inch; thread length, ± 3/32 inch; square length, ± 1/32 inch; shank diameter, 14 mm, –0.0015 inch, 18 mm, –0.0020 inch; and size of square, –0.0040 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17a. ANSI Standard Ground Thread Straight Fluted Taps
M Profile — Metric Sizes *ASME B94.9-1999*



STYLE 2



STYLE 1



STYLE 3

Nom. Dia. mm.	Pitch mm	No. of Flutes	Pitch Diameter Limits and Chamfers							Length Overall	Length of Thread	Length of Square	Dia. of Square	Size of Square
			D3	D4	D5	D6	D7	D8	D9	*A*	*B*	*C*	*D*	*E*
1.6	0.35	2	PB	…	…	…	…	…	…	1 5/8	5/16	3/16	0.141	0.110
2	0.4	3	PB	…	…	…	…	…	…	1 3/4	7/16	3/16	0.141	0.110
2.5	0.45	3	PB	…	…	…	…	…	…	1 13/16	1/2	3/16	0.141	0.110
3	0.5	3	PB	…	…	…	…	…	…	1 15/16	5/8	3/16	0.141	0.110
3.5	0.6	3	…	PB	…	…	…	…	…	2	11/16	3/16	0.141	0.110
4	0.7	4	…	PB	…	…	…	…	…	2 1/8	3/4	1/4	0.168	0.131
4.5	0.75	4	…	PB	…	…	…	…	…	2 3/8	7/8	1/4	0.194	0.152
5	0.8	4	…	PB	…	…	…	…	…	2 3/8	7/8	1/4	0.194	0.152
6	1	4	…	…	PB	…	…	…	…	2 1/2	1	5/16	0.255	0.191
7	1	4	…	…	PB	…	…	…	…	2 23/32	1 1/8	3/8	0.318	0.238
8	1.25	4	…	…	PB	…	…	…	…	2 23/32	1 1/8	3/8	0.318	0.238
10	1.5	4	…	…	…	PB	…	…	…	2 15/16	1 1/4	7/16	0.381	0.286
12	1.75	4	…	…	…	PB	…	…	…	3 3/8	1 21/32	7/16	0.367	0.275
14	2	4	…	…	…	…	PB	…	…	3 19/32	1 21/32	1/2	0.429	0.322
16	2	4	…	…	…	…	PB	…	…	3 13/16	1 13/16	9/16	0.480	0.360
20	2.5	4	…	…	…	…	PB	…	…	4 15/32	2	11/16	0.652	0.489
24	3	4	…	…	…	…	…	PB	…	4 29/32	2 7/32	3/4	0.760	0.570
30	3.5	4	…	…	…	…	…	…	PB	5 7/16	2 9/16	1	1.021	0.766
36	4	4	…	…	…	…	…	…	PB	6 1/16	3	1 1/8	1.233	0.925

Tolerances					
Element	Nom. Dia. Range, mm	Toler., Inch	Element	Nom. Dia. Range, mm	Toler., Inch
Overall Length, *A*	M1.6 to M24, incl.	±1/32	Shank Diameter, *D*	M1.6 to M14, incl.	–0.0015
	M30 and M36	±1/16		M16 to M36	–0.002
Thread Length, *B*	M1.6 to M5, incl.	±3/64			
	M6 to M12 incl.	±1/16			
	M14 to M36	±3/32	Size of Square, *E*	M1.6 to M12, incl.	–0.004
Square Length, *C*	M1.6 to M24, incl.	±1/32		M14 to M24, incl.	–0.006
	M30 and M36	±1/16		M30 and M36	–0.008

All dimensions are in inches except where otherwise stated.

Chamfer Designation: P — Plug, B — Bottoming. These taps are high-speed steel.

Style 1 taps, sizes M1.6 through M5, have external center on thread and shank ends (may be removed on thread end of bottoming taps).

Style 2 taps, sizes M6, M7, M8, and M10, have external center on thread end (may be removed on bottoming taps) and external partial cone center on shank end with length of cone approximately 1/4 of diameter of shank.

Style 3 taps, sizes larger than M10 have external center on thread and shank ends.

For standard thread limits see Tables 4a and 4b.

For eccentricity tolerances of tap elements see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17b. ANSI Standard Spiral Pointed Ground Thread Taps
M Profile — Metric Sizes *ASME B94.9-1999*



Nom. Dia. mm.	Pitch mm	No. of Flutes	Pitch Diameter Limits and Styles					Length Overall	Length of Thread	Length of Square	Dia. of Square	Size of Square
			D3	D4	D5	D6	D7	*A*	*B*	*C*	*D*	*E*
1.6	0.35	2	P	…	…	…	…	1 5/8	5/16	3/16	0.141	0.110
2	0.4	2	P	…	…	…	…	1 3/4	7/16	3/16	0.141	0.110
2.5	0.45	2	P	…	…	…	…	1 13/16	1/2	3/16	0.141	0.110
3	0.5	2	P	…	…	…	…	1 15/16	5/8	3/16	0.141	0.110
3.5	0.6	2	…	P	…	…	…	2	11/16	3/16	0.141	0.110
4	0.7	2	…	P	…	…	…	2 1/8	3/4	1/4	0.168	0.131
5	0.8	2	…	P	…	…	…	2 3/8	7/8	1/4	0.194	0.152
6	1	2	…	…	P	…	…	2 1/2	1	5/16	0.255	0.191
8	1.25	2	…	…	P	…	…	2 23/32	1 1/8	3/8	0.318	0.238
10	1.5	3	…	…	…	P	…	2 15/16	1 1/4	7/16	0.381	0.286
12	1.75	3	…	…	…	P	…	3 3/8	1 21/32	7/16	0.367	0.275
14	2	3	…	…	…	…	P	3 19/32	1 21/32	1/2	0.429	0.322
16	2	3	…	…	…	…	P	3 13/16	1 13/16	9/16	0.480	0.360
20	2.5	3	…	…	…	…	P	4 15/32	2	11/16	0.652	0.489

Tolerances					
Element	Nom. Dia. Range, mm	Toler., Inch	Element	Nom. Dia. Range, mm	Toler., Inch
Overall Length, *A*	M1.6 to M20, incl.	±1/32	Shank Diameter, *D*	M1.6 to M14, incl. M16 to M20	–0.0015 –0.002
Thread Length, *B*	M1.6 to M5, incl. M16 to M12 incl. M14 to M20	±3/64 ±1/16 ±3/32	Size of Square, *E*	M1.6 to M12, incl. M14 to M20, incl.	–0.004 –0.006
Square Length, *C*	M1.6 to M20	±1/32			

All dimensions are in inches except where otherwise stated.

Chamfer Designation: P — Plug. These taps are high-speed steel.

Style 1 taps, sizes M1.6 through M5, have external center on thread and shank ends.

Style 2 taps, sizes M6, M8 and M10, have external center on thread end and external partial cone center on shank end with length of cone approximately 1/4 of diameter of shank.

Style 3 taps, sizes larger than M10 have external center on thread and shank ends.

For standards thread limits see Table 4a and 4b.

For eccentricity tolerances of tap elements see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. ANSI Standard Taper and Straight Pipe Taps *ASME B94.9-1999*



TAPER PIPE TAP



STRAIGHT PIPE TAP

Nominal Size	Threads per Inch		Number of Flutes		Dimensions				
	Carbon Steel	High-Speed Steel	Regular	Interrupted	Length Overall, *A*	Length of Thread, *B*	Length of Square, *C*	Diameter of Shank, *D*	Size of Square, *E*
Taper Pipe Taps									
1/16 [a]	…	27	4	…	2 1/8	11/16	3/8	0.3125	0.234
1/8	27	27	4	5	2 1/8	3/4	3/8	0.3125	0.234
1/8	27	27	4	5	2 1/8	3/4	3/8	0.4375	0.328
1/4	18	18	4	5	2 7/16	1 1/16	7/16	0.5625	0.421
3/8	18	18	4	5	2 9/16	1 1/16	1/2	0.7000	0.531
1/2	14	14	4	5	3 1/8	1 3/8	5/8	0.6875	0.515
3/4	14	14	5	5	3 1/4	1 3/8	11/16	0.9063	0.679
1	11 1/2	11 1/2	5	5	3 3/4	1 3/4	13/16	1.1250	0.843
1 1/4	11 1/2	11 1/2	5	5	4	1 3/4	15/16	1.3125	0.984
1 1/2	11 1/2	11 1/2	7	7 [ba]	4 1/4	1 3/4	1	1.5000	1.125
2	11 1/2	11 1/2	7	7 [ba]	4 1/2	1 3/4	1 1/8	1.8750	1.406
2 1/2 [c]	8	…	8	…	5 1/2	2 9/16	1 1/4	2.2500	1.687
3 [c]	8	…	8	…	6	2 5/8	1 3/8	2.6250	1.968
Straight Pipe Taps									
1/8 [a]	…	27	4	…	2 1/8	3/4	3/8	0.3125	0.234
1/8	…	27	4	…	2 1/8	3/4	3/8	0.4375	0.328
1/4	…	18	4	…	2 7/16	1 1/16	7/16	0.5625	0.421
3/8	…	18	4	…	2 9/16	1 1/16	1/2	0.7000	0.531
1/2	…	14	4	…	3 1/8	1 3/8	5/8	0.6875	0.515
3/4	…	14	5	…	3 1/4	1 3/8	11/16	0.9063	0.679
1	…	11 1/2	5	…	3 3/4	1 3/4	13/16	1.1250	0.843

[a] Ground thread taps only.
[b] Standard in NPT form of thread only.
[c] Cut thread taps only.

Tolerances for General Dimensions							
Element	Diameter Range	Tolerance		Element	Diameter Range	Tolerance	
		Cut Thread	Ground Thread			Cut Thread	Ground Thread
Overall Length, *A*	1/16 to 3/4	±1/32	±1/32	Shank Diameter, *D*	1/16 to 1/8	…	−0.0015
	1 to 3	±1/16	± 1/16		1/8 to 1/2	−0.007	…
Thread Length, *B*	1/16 to 3/4	±1/16	±1/16		1/4 to 1	…	−0.002
	1 to 1 1/4	±3/32	±3/32		3/4 to 3	−0.009	…
	1 1/2 to 3	±1/8	±1/8		1 1/4 to 2	…	−0.003
Square Length, *C*	1/16 to 3/4	±1/32	±1/32	Size of Square, *E*	1/16 to 1/8	−0.004	−0.004
	1 to 3	±1/16	±1/16		1/8 to 3/4	−0.006	−0.006
					1 to 3	−0.008	−0.008

All dimensions are given in inches. These taps have an internal center in the thread end. *Taper Pipe Threads*: The 1/8-inch pipe tap is furnished with large size shank unless the small shank is specified. These taps have 2 to 3 1/2 threads chamfer. The first few threads on interrupted thread pipe taps are left full. The following styles and sizes are standard: 1/16 to 2 inches regular ground thread, NPT, NPTF, and ANPT: 1/8 to 2 inches interrupted ground thread, NPT, NPTF and ANPT: 1/8 to 3 inches carbon steel regular cut thread, NPT; 1/8 to 2 inches high-speed steel, regular cut thread, NPT; 1/8 to 1 1/4 inches high-speed steel interrupted cut thread, NPT. For standard thread limits see Tables 6a and 6b. *Straight Pipe Threads:* The 1/8-inch pipe tap is furnished with large size shank unless the small size is specified. These taps are standard with plug chamfer only. The following styles and sizes are standard: ground threads — 1/8 to 1 inch, NPSC and NPSM; 1/8 to 3/4 inch, NPSF; cut threads — 1/8 to 1 inch, NPSC and NPSM. For standard thread limits see Tables 7a, 7b, and 7c. For eccentricity tolerances see Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. Taps Recommended for Classes 2B and 3B Unified Screw Threads Numbered and Fractional Sizes *ASME B94.9-1999*

Size	Threads per Inch NC UNC	Threads per Inch NF UNF	Recommended Tap For Class of Thread Class 2B[a]	Recommended Tap For Class of Thread Class 3B	Pitch Diameter Limits For Class of Thread Min, All Classes (Basic)	Pitch Diameter Limits For Class of Thread Max Class 2B	Pitch Diameter Limits For Class of Thread Max Class 3B
Machine Screw Numbered Size Taps							
0	…	80	G H2	G H1	0.0519	0.0542	0.0536
1	64	…	G H2	G H1	0.0629	0.0655	0.0648
1	…	72	G H2	G H1	0.0640	0.0665	0.0659
2	56	…	G H2	G H1	0.0744	0.0772	0.0765
2	…	64	G H2	G H1	0.0759	0.0786	0.0779
3	48	…	G H2	G H1	0.0855	0.0885	0.0877
3	…	56	G H2	G H1	0.0874	0.0902	0.0895
4	40	…	G H2	G H2	0.0958	0.0991	0.0982
4	…	48	G H2	G H1	0.0985	0.1016	0.1008
5	40	…	G H2	G H2	0.1088	0.1121	0.1113
5	…	44	G H2	G H1	0.1102	0.1134	0.1126
6	32	…	G H3	G H2	0.1177	0.1214	0.1204
6	…	40	G H2	G H2	0.1218	0.1252	0.1243
8	32	…	G H3	G H2	0.1437	0.1475	0.1465
8	…	36	G H2	G H2	0.1460	0.1496	0.1487
10	24	…	G H3	G H3	0.1629	0.1672	0.1661
10	…	32	G H3	G H2	0.1697	0.1736	0.1726
12	24	…	G H3	G H3	0.1889	0.1933	0.1922
12	…	28	G H3	G H3	0.1928	0.1970	0.1959
Fractional Size Taps							
1/4	20	…	G H5	G H3	0.2175	0.2224	0.2211
1/4	…	28	G H4	G H3	0.2268	0.2311	0.2300
5/16	18	…	G H5	G H3	0.2764	0.2817	0.2803
5/16	…	24	G H4	G H3	0.2854	0.2902	0.2890
3/8	16	…	G H5	G H3	0.3344	0.3401	0.3387
3/8	…	24	G H4	G H3	0.3479	0.3528	0.3516
7/16	14	…	G H5	G H3	0.3911	0.3972	0.3957
7/16	…	20	G H5	G H3	0.4050	0.4104	0.4091
1/2	13	…	G H5	G H3	0.4500	0.4565	0.4548
1/2	…	20	G H5	G H3	0.4675	0.4731	0.4717
9/16	12	…	G H5	G H3	0.5084	0.5152	0.5135
9/16	…	18	G H5	G H3	0.5264	0.5323	0.5308
5/8	11	…	G H5	G H3	0.5660	0.5732	0.5714
5/8	…	18	G H5	G H3	0.5889	0.5949	0.5934
3/4	10	…	G H5	G H5	0.6850	0.6927	0.6907
3/4	…	16	G H5	G H3	0.7094	0.7159	0.7143
7/8	9	…	G H6[b]	G H4	0.8028	0.8110	0.8089
7/8	…	14	G H6[b]	G H4	0.8286	0.8356	0.8339
1	8	…	G H6[b]	G H4	0.9188	0.9276	0.9254
1	…	12	G H6[b]	G H4	0.9459	0.9535	0.9516
1	14NS		G H6[b]	G H4	0.9536	0.9609	0.9590
1 1/8	7	…	G H8[b]	G H4	1.0322	1.0416	1.0393
1 1/8	…	12	G H6[b]	G H4	1.0709	1.0787	1.0768
1 1/4	7	…	G H8[b]	G H4	1.1572	1.1668	1.1644
1 1/4	…	12	G H6[b]	G H4	1.1959	1.2039	1.2019
1 3/8	6	…	G H8[b]	G H4	1.2667	1.2771	1.2745
1 3/8	…	12	G H6[b]	G H4	1.3209	1.3291	1.3270
1 1/2	6	…	G H8[b]	G H4	1.3917	1.4022	1.3996
1 1/2	…	12	G H6[b]	G H4	1.4459	1.4542	1.4522

[a] Cut thread taps in all fractional sizes and in numbered sizes 3 to 12 NC and NF may be used under normal conditions and in average materials to produce tapped holes in this classification.

[b] Standard G H4 taps are also suitable for this class of thread.

All dimensions are given in inches.

The above recommended taps normally produce the class of thread indicated in average materials when used with reasonable care. However, if the tap specified does not give a satisfactory gage fit in the work, a choice of some other limit tap will be necessary.

Copyright 2004, Industrial Press, Inc., New York, NY

Standard System of Tap Marking.— Ground thread taps, inch screw threads, are marked with the nominal size, number of threads per inch, the proper symbol to identify the thread form, "HS" for high-speed steel, "G" for ground thread, and designators for tap pitch diameter and special features, such as left-hand and multi-start threads.

Cut thread taps, inch screw threads, are marked with the nominal size, number of threads per inch, and the proper symbol to identify the thread form. High-speed steel taps are marked "HS," but carbon steel taps need not be marked.

Ground thread taps made with metric screw threads, M profile, are marked with "M," followed by the nominal size and pitch in millimeters, separated by "x." Marking also includes "HS" for high-speed steel, "G" for ground thread, designators for tap pitch diameter and special features, such as left-hand and multi-start threads.

Thread symbol designators are listed in the accompanying table. Tap pitch diameter designators, systems of limits, special features, and examples for ground threads are given in the following section.

Standard System Tap Thread Limits and Identification for Unified Inch Screw Threads, Ground Thread.— *H or L Limits:* For Unified inch screw threads, when the maximum tap pitch diameter is over basic pitch diameter by an even multiple of 0.0005 in. or the minimum tap pitch diameter limit is under basic pitch diameter by an even multiple of 0.0005 in., the taps are marked "H" or "L," respectively, followed by a limit number, determined as follows:

H limit number =Amount maximum tap PD limit is over basic PD divided by 0.0005
L limit number =Amount minimum tap PD limit is under basic PD divided by 0.0005

Table 20. Thread Series Designations

Standard Tap Marking	Product Thread Designation	Third Series
M	M	Metric Screw Threads—M Profile, with basic ISO 68 profile
M	MJ	Metric Screw Threads—M Profile, with rounded root of radius 0.15011*P* to 0.18042*P* Class 5 interference-fit thread
NC	NC5IF	Entire ferrous material range
NC	NC5INF	Entire nonferrous material range
NPS	NPSC	American Standard straight pipe threads in pipe couplings
NPSF	NPSF	Dry seal American Standard fuel internal straight pipe threads
NPSH	NPSH	American Standard straight hose coupling threads for joining to American Standard taper pipe threads
NPSI	NPSI	Dryseal American Standard intermediate internal straight pipe threads
NPSL	NPSL	American Standard straight pipe threads for loose-fitting mechanical joints with locknuts
NPS	NPSM	American Standard straight pipe threads for free-fitting mechanical joints for fixtures
NPT	NPT	American Standard taper pipe threads for general use
NPTF	NPTF	Dryseal American Standard taper pipe threads
NPTR	NPTR	American Standard taper pipe threads for railing joints
Unified Inch Screw Thread		
N	UN	Constant-pitch series
NC	UNC	Coarse pitch series
NF	UNF	Fine pitch series
NEF	UNEF	Extra-fine pitch series
N	UNJ	Constant-pitch series, with rounded root of radius 0.15011*P* to 0.18042*P* (ext. thd. only)
NC	UNJC	Coarse pitch series, with rounded root of radius 0.15011*P* to 0.18042 *P* (ext. thd. only)
NF	UNJF	Fine pitch series, with rounded root of radius 0.15011*P* to 0.18042*P* (ext. thd. only)
NEF	UNJEF	Extra-fine pitch series, with rounded root of radius 0.15011*P* to 0.18042*P* (ext. thd. only)
N	UNR	Constant-pitch series, with rounded root of radius not less than 0.108*P* (ext. thd. only)
NC	UNRC	Coarse thread series, with rounded root of radius not less than 0.108*P* (ext. thd. only)
NF	UNRF	Fine pitch series, with rounded root of radius not less than 0.108*P* (ext. thd. only)
NEF	UNREF	Extra-fine pitch series, with rounded root of radius not less than 0.108*P* (ext. thd. only)
NS	UNS	Special diameter pitch, or length of engagement

Copyright 2004, Industrial Press, Inc., New York, NY

The PD limits for various H limit numbers are given in Table 2. The PD limits for L limit numbers are determined as follows. The minimum tap PD equals the basic PD minus the number of half-thousandths (0.0005 in.) represented by the limit number. The maximum tap PD equals the minimum PD plus the PD tolerance given in Table 21.

Table 21. PD Tolerance for Unified Inch Screw Threads
Ground Thread *ASME B94.9-1999*

Threads per Inch	To 1 in., incl.	Over 1 in. to 1½ in., incl.	Over 1½ to 2½ in., incl.	Over 2 ½ in.
80-28	0.0005	0.0010	0.0010	0.0015
24-18	0.0005	0.0010	0.0015	0.0015
16-18	0.0005	0.0010	0.0015	0.0020
7-6	0.0010	0.0010	0.0020	0.0025
5½-4	0.0010	0.0015	0.0020	0.0025

Example: ⅜-16 NC HS H1
Max. tap PD = 0.3349
Min. tap PD = 0.3344

Example: ⅜-16 NC HS G L2
Min. tap PD = Basic PD – 0.0010 in. = 0.3344 – 0.0010 = 0.3334
Max. tap PD = Min. Tap PD + 0.0005 = 0.3334 + 0.0005 = 0.3339

Oversize or Undersize: When the maximum tap PD over basic PD or the minimum tap PD under basic PD is not an even multiple of 0.0005, the tap PD is usually designated as an amount oversize or undersize. The amount oversize is added to the basic PD to establish the *minimum* tap PD. The amount undersize is subtracted from the basic PD to establish the *minimum* tap PD. The PD tolerance in Table 21 is added to the minimum tap PD to establish the maximum tap PD for both.

Example : 7/16-14 NC plus 0.0017 HS G
Min. tap PD = Basic PD + 0.0017 in.
Max. tap PD = Min. tap PD + 0.0005 in.

Whenever possible for oversize or other special tap PD requirements, the maximum and minimum tap PD requirements should be specified.

Special Tap Pitch Diameter: Taps not made to H or L limit numbers, to Table 22, or to the formula for oversize or undersize taps, may be marked with the letter "S" enclosed by a circle or by some other special identifier. *Example:* ½-16 NC HS G .

Table 22. ANSI Standard Runout and Location Tolerance of Tap Elements
ASME B94.9-1999

Element	Range Sizes are Inclusive			Cut Thread		Ground Thread		Location, inch
	Hand, Mch. Screw	Metric	Pipe	Eccentricity	tiv[a]	Eccentricity	tiv[a]	
Square (at central point)	#0–½″	M1.6–M12	1/16–⅛″	…	…	…	…	0.0060
	17/32–4″	M14–M100	¼–4″	…	…	…	…	0.0080
Shank	#0–5/16″	M1.6–M8	1/16″	0.0030	0.0060	0.0005	0.0010	…
	11/32–4″	M10–M100	⅛–4″	0.0040	0.0080	0.0008	0.0016	…
Major Diameter	#0–5/16″	M1.6–M8	1/16″	0.0025	0.0050	0.0005	0.0010	…
	11/32–4″	M10–M100	⅛–4″	0.0040	0.0080	0.0008	0.0016	…
Pitch Diameter (at first full thread)	#0–5/16″	M1.6–M8	1/16″	0.0025	0.0050	0.0005	0.0010	…
	11/32–4″	M10–M100	⅛–4″	0.0040	0.0080	0.0008	0.0016	…
Chamfer[b]	#0–½″	M1.6–M12	1/16–⅛″	0.0020	0.0040	0.0010	0.0020	…
	17/32–4″	M14–M100	¼–4″	0.0030	0.0060	0.0015	0.0030	…

[a] tiv = total indicator variation. This data no longer included in Standard, but for reference figures are given for both eccentricity and total indicator variation to avoid misunderstanding.

[b] Chamfer should preferably be inspected by light projection to avoid errors due to indicator contact points dropping into the thread groove.

All dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Left-Hand Taps: Taps with left-hand threads are marked "LEFT HAND" or "LH." *Example:* ⅜-16 NC LH HS G H3.

Multiple-Start Threads: Taps with multiple-start threads are marked with the lead designated as a fraction, also "Double," "Triple," etc. The Unified Screw Thread form symbol is always designated as "NS" for multiple-start threads. *Example:* ⅜-16 NS Double ⅛ Lead HS G H5.

Standard System of Ground Thread Tap Limits and Identification for Metric Screw Threads, M Profile.— All calculations for metric taps use millimeter values. When U.S. customary values are needed, they are translated from the three-place millimeter tap diameters only after the calculations are completed.

Table 23. PD Tolerance for Metric Screw Threads
M Profile—Ground Threads *ASME B94.9-1999*

Pitch, *P* (mm)	M1.6 to M6.3, inclusive.	Over M6.3 to M25, inclusive	Over M25 to M90, inclusive	Over M90
0.3	0.015	0.015	0.020	0.020
0.35	0.015	0.015	0.020	0.020
0.4	0.015	0.015	0.020	0.025
0.45	0.015	0.020	0.020	0.025
0.5	0.015	0.020	0.025	0.025
0.6	0.020	0.020	0.025	0.025
0.7	0.020	0.020	0.025	0.025
0.75	0.020	0.025	0.025	0.031
0.8	0.020	0.025	0.025	0.031
0.9	0.020	0.025	0.025	0.031
1	0.025	0.025	0.031	0.031
1.25	0.025	0.031	0.031	0.041
1.5	0.025	0.031	0.031	0.041
1.75	…	0.031	0.041	0.041
2	…	0.041	0.041	0.041
2.5	…	0.041	0.041	0.052
3	…	0.041	0.052	0.052
3.5	…	0.041	0.052	0.052
4	…	0.052	0.052	0.064
4.5	…	0.052	0.052	0.064
5	…	…	0.064	0.064
5.5	…	…	0.064	0.064
6	…	…	0.064	0.064

D or DU Limits: When the maximum tap pitch diameter is over basic pitch diameter by an even multiple of 0.013 mm (0.000512 in. reference), or the minimum tap pitch diameter limit is under basic pitch diameter by an even multiple of 0.013 mm, the taps are marked with the letters "D" or "DU," respectively, followed by a limit number. The limit number is determined as follows:

D limit number = Amount maximum tap PD limit is over basic PD divided by 0.013

DU limit number = Amount minimum tap PD limit is under basic PD divided by 0.013

Copyright 2004, Industrial Press, Inc., New York, NY

The PD limits for various D limit numbers are given in Table 4b. The PD limits for DU limit numbers are determined as follows. The minimum tap PD equals the basic PD minus the number of millimeters represented by the limit number (multiples of 0.013 mm). The maximum tap PD equals the minimum tap PD plus the PD tolerance given in Table 23.

Example: M1.6 × 0.35 HS G D3
Max. tap PD = 1.412
Min. tap PD = 1.397
M6 × 1 HS G DU4
Min. tap PD = Basic PD – 0.052 mm = 5.350 – 0.052 = 5.298
Max. tap PD = Min. tap PD + 0.025 mm = 5.323

Metric oversize or undersize taps, taps with special pitch diameters, and left-hand taps follow the marking system given for inch taps.

Examples: M12 × 1.75 + 0.044 HS G
M10 × 1.5 HS G
M10 × 1.5 LH HS G D6

Multiple-Start Threads: Metric taps with multiple-start threads are marked with the lead designated in millimeters preceded by the letter "L," the pitch in millimeters preceded by the letter "P," and the words "(2 starts)," "(3 starts)," etc.

Examples: M16 × L4-P2 (2 starts) HS G D8
M14 × L6-P2 (3 starts) HS G D7

Acme and Square-Threaded Taps

These taps are usually made in sets, three taps in a set being the most common. For very fine pitches, two taps in a set will be found sufficient, whereas as many as five taps in a set are used for coarse pitches. The table on the next page gives dimensions for proportioning both Acme and square-threaded taps when made in sets. In cutting the threads of square-threaded taps, one leading tap maker uses the following rules: The width of the groove between two threads is made equal to one-half the pitch of the thread, less 0.004 inch, making the width of the thread itself equal to one-half of the pitch, plus 0.004 inch. The depth of the thread is made equal to 0.45 times the pitch, plus 0.0025 inch. This latter rule produces a thread that for all the ordinarily used pitches for square-threaded taps has a depth less than the generally accepted standard depth, this latter depth being equal to one-half the pitch. The object of this shallow thread is to ensure that if the hole to be threaded by the tap is not bored out so as to provide clearance at the bottom of the thread, the tap will cut its own clearance. The hole should, however, always be drilled out large enough so that the cutting of the clearance is not required of the tap.

The table, *Dimensions of Acme Threads Taps in Sets of Three Taps*, may also be used for the length dimensions for Acme taps. The dimensions in this table apply to single-threaded taps. For multiple-threaded taps or taps with very coarse pitch, relative to the diameter, the length of the chamfered part of the thread may be increased. Square-threaded taps are made to the same table as Acme taps, with the exception of the figures in column *K*, which for square-threaded taps should be equal to the nominal diameter of the tap, no oversize allowance being customary in these taps. The first tap in a set of Acme taps (not square-threaded taps) should be turned to a taper at the bottom of the thread for a distance of about one-quarter of the length of the threaded part. The taper should be so selected that the root diameter is about $\frac{1}{32}$ inch smaller at the point than the proper root diameter of the tap. The first tap should preferably be provided with a short pilot at the point. For very coarse pitches, the first tap may be provided with spiral flutes at right angles to the angle of the thread. Acme and square-threaded taps should be relieved or backed off on the top of the thread of the chamfered portion on all the taps in the set. When the taps are used as machine taps, rather than as hand taps, they should be relieved in the angle of the thread, as well as on the top,

Copyright 2004, Industrial Press, Inc., New York, NY

Table 24. Dimensions of Acme Threads Taps in Sets of Three Taps



Nominal Dia.	A	B	C	D	E	F	G	H	I	K
1/2	4 1/4	1 7/8	2 3/8	1/2	1 7/8	5/8	1 3/4	7/8	1 1/2	0.520
9/16	4 7/8	2 1/8	2 3/4	9/16	2 3/16	3/4	2	1	1 3/4	0.582
5/8	5 1/2	2 3/8	3 1/8	5/8	2 1/2	7/8	2 1/4	1 1/8	2	0.645
11/16	6	2 1/2	3 1/2	3 13/16	2 13/16	15/16	2 9/16	1 1/4	2 1/4	0.707
3/4	6 1/2	2 11/16	3 13/16	11/16	3 1/8	1	2 13/16	1 3/8	2 7/16	0.770
13/16	6 7/8	2 13/16	4 1/16	3/4	3 5/16	1 1/16	3	1 7/16	2 5/8	0.832
7/8	7 1/4	3	4 1/4	3/4	3 1/2	1 1/8	3 1/8	1 1/2	2 3/4	0.895
15/16	7 9/16	3 1/8	4 7/16	13/16	3 5/8	1 3/16	3 1/4	1 9/16	2 7/8	0.957
1	7 7/8	3 1/4	4 5/8	13/16	3 13/16	1 1/4	3 3/8	1 5/8	3	1.020
1 1/8	8 1/2	3 9/16	4 15/16	7/8	4 1/16	1 5/16	3 5/8	1 3/4	3 3/16	1.145
1 1/4	9	3 3/4	5 1/4	15/16	4 5/16	1 3/8	3 7/8	1 7/8	3 3/8	1.270
1 3/8	9 1/2	4	5 1/2	1	4 1/2	1 7/16	4 1/16	2	3 1/2	1.395
1 1/2	10	4 1/4	5 3/4	1	4 3/4	1 1/2	4 1/4	2 1/8	3 5/8	1.520
1 5/8	10 1/2	4 1/2	6	1	5	1 1/2	4 1/2	2 1/8	3 7/8	1.645
1 3/4	11	4 3/4	6 1/4	1 1/16	5 3/16	1 9/16	4 11/16	2 1/4	4	1.770
1 7/8	11 3/8	4 7/8	6 1/2	1 1/16	5 7/16	1 9/16	4 15/16	2 1/4	4 1/4	1.895
2	11 3/4	5	6 3/4	1 1/8	5 5/8	1 5/8	5 1/8	2 3/8	4 3/8	2.020
2 1/4	12 1/2	5 1/4	7 1/4	1 1/8	6 1/8	1 3/16	5 1/2	2 1/2	4 3/4	2.270
2 1/2	13 1/4	5 1/2	7 3/4	1 3/4	6 9/16	1 7/8	5 7/8	2 5/8	5 1/8	2.520
2 3/4	14	5 3/4	8 1/4	1 1/4	7	2	6 1/4	2 3/4	5 1/2	2.770
3	15	6 1/4	8 3/4	1 1/4	7 1/2	2	6 3/4	3	5 3/4	3.020

for the whole length of the chamfered portion. Acme taps should also always be relieved on the front side of the thread to within 1/32 inch of the cutting edge.

Adjustable Taps: Many adjustable taps are now used, especially for accurate work. Some taps of this class are made of a solid piece of tool steel that is split and provided with means of expanding sufficiently to compensate for wear. Most of the larger adjustable taps have inserted blades or chasers that are held rigidly, but are capable of radial adjustment. The use of taps of this general class enables standard sizes to be maintained readily.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 25. Proportions of Acme and Square-Threaded Taps Made in Sets



R **= root diameter of thread.** ***D*** **= full diameter of tap.**
T **= double depth of full thread.**

Kind of Tap	No. of Taps in Set	Order of Tap in Set	*A*	*B*	*C*
Acme Thread Taps	2	1st	$R + 0.65T$	$R + 0.010$	$\frac{1}{8}L$ to $\frac{1}{6}L$
		2d	D	A on 1st tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	3	1st	$R + 0.45T$	$R + 0.010$	$\frac{1}{8}L$ to $\frac{1}{6}L$
		2d	$R + 0.80T$	A on 1st tap – 0.005	$\frac{1}{6}L$ to $\frac{1}{4}L$
		3d	D	A on 2d tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	4	1st	$R + 0.40T$	$R + 0.010$	$\frac{1}{8}L$
		2d	$R + 0.70T$	A on 1st tap – 0.005	$\frac{1}{6}L$
		3d	$R + 0.90T$	A on 2d tap – 0.005	$\frac{1}{5}L$
		4th	D	A on 3d tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	5	1st	$R + 0.37T$	$R + 0.010$	$\frac{1}{8}L$
		2d	$R + 0.63T$	A on 1st tap – 0.005	$\frac{1}{6}L$
		3d	$R + 0.82T$	A on 2d tap – 0.005	$\frac{1}{5}L$
		4th	$R + 0.94T$	A on 3d tap – 0.005	$\frac{1}{5}L$ to $\frac{1}{4}L$
		5th	D	A on 4th tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
Square-Threaded Taps	2	1st	$R + 0.67T$	R	$\frac{1}{8}L$ to $\frac{1}{6}L$
		2d	D	A on 1st tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	3	1st	$R + 0.41T$	R	$\frac{1}{8}L$ to $\frac{1}{6}L$
		2d	$R + 0.080T$	A on 1st tap – 0.005	$\frac{1}{6}L$ to $\frac{1}{4}L$
		3d	D	A on 2d tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	4	1st	$R + 0.32T$	R	$\frac{1}{8}L$
		2d	$R + 0.62T$	A on 1st tap – 0.005	$\frac{1}{6}L$
		3d	$R + 0.90T$	A on 2d tap – 0.005	$\frac{1}{5}L$
		4th	D	A on 3d tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$
	5	1st	$R + 0.26T$	R	$\frac{1}{8}L$
		2d	$R + 0.50T$	A on 1st tap – 0.005	$\frac{1}{6}L$
		3d	$R + 0.72T$	A on 2d tap – 0.005	$\frac{1}{5}L$
		4th	$R + 0.92T$	A on 3d tap – 0.005	$\frac{1}{5}L$ to $\frac{1}{4}L$
		5th	D	A on 4th tap – 0.005	$\frac{1}{4}L$ to $\frac{1}{3}L$

Drill Hole Sizes for Acme Threads.— Many tap and die manufacturers and vendors make available to their customers computer programs designed to calculate drill hole sizes for all the Acme threads in their ranges from the basic dimensions. The large variety and combination of dimensions for such tools prevent inclusion of a complete set of tables of tap drills for Acme taps in this Handbook. The following formulas (dimensions in inches) for calculating drill hole sizes for Acme threads are derived from the American National Standard, ANSI/ASME B1.5-1997, Acme Screw Threads.

Copyright 2004, Industrial Press, Inc., New York, NY

To select a tap drill size for an Acme thread, first calculate the maximum and minimum internal product minor diameters for the thread to be produced. (Dimensions for general purpose, centralizing, and stub Acme screw threads are given in the Threads and Threading section, starting on page 1825.) Then select a drill that will yield a finished hole somewhere between the established maximum and minimum product minor diameters. Consider staying close to the maximum product limit in selecting the hole size, to reduce the amount of material to be removed when cutting the thread. If there is no standard drill size that matches the hole diameter selected, it may be necessary to drill and ream, or bore the hole to size, to achieve the required hole diameter.

Diameters of General-Purpose Acme Screw Threads of Classes 2G, 3G, and 4G may be calculated from:

minimum diameter = basic major diameter − pitch

maximum diameter = minimum minor diameter + 0.05 × pitch

pitch = 1/number of threads per inch

Example: ½-10 Acme 2G, pitch = 1/10 = 0.1

minimum diameter = 0.5 − 0.1 = 0.4

maximum diameter = 0.4 + (0.05 × 0.1) = 0.405

drill selected = letter X or 0.3970 + 0.0046 (probable oversize) = 0.4016

Diameters of Acme Centralizing Screw Threads of Classes 2C, 3C, and 4C may be calculated from:

minimum diameter = basic major diameter − 0.9 × pitch

maximum diameter = minimum minor diameter + 0.05 × pitch

pitch = 1/number of threads per inch

Example: ½-10 Acme 2C, pitch = 1/10 = 0.1

minimum diameter = 0.5 − (0.9 × 0.1) = 0.41

maximum diameter = 0.41 + (0.05 × 0.1) = 0.415

drill selected = 13/32 or 0.4062 + 0.0046 (probable oversize) = 0.4108.

Diameters for Acme Centralizing Screw Threads of Classes 5C and 6C: These classes are not recommended for new designs, but may be calculated from:

minimum diameter = [basic major diameter − (0.025 √ basic major diameter)] − 0.9 × pitch

maximum diameter = minimum minor diameter + 0.05 × pitch

pitch = 1/number of threads per inch

Example: ½-10 Acme 5C, pitch = 1/10 = 0.1

minimum diameter = [0.5 − (0.025 √ 0.5)] − (0.9 × 0.1) = 0.3923

maximum diameter = 0.3923 + (0.05 × 0.1) = 0.3973

drill selected = 25/64 or 0.3906 + 0.0046 (probable oversize) = 0.3952

British Standard Screwing Taps for ISO Metric Threads.— BS 949: Part 1:1976 provides dimensions and tolerances for screwing taps for ISO metric coarse-pitch series threads in accordance with BS 3643: Part 2; and for metric fine-pitch series threads in accordance with BS 3643: Part 3.

Table 26 provides dimensional data for the cutting portion of cut-thread taps for coarse-series threads of ISO metric sizes. The sizes shown were selected from the first-choice combinations of diameter and pitch listed in BS 3643:Part 1:1981 (1998). Table 13 provides similar data for ground-thread taps for both coarse- and fine-pitch series threads of ISO metric sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 26. British Standard Screwing Taps for ISO Metric Threads Dimensional Limits for the Threaded Portion of Cut Taps—Coarse Pitch Series *BS 949: Part 1:1976*

Designation	Pitch	Major Diameter	Pitch Diameter			Tolerance on Thread Angle, Degrees
		Minimum[a]	Basic	Max.	Min.	
M1	0.25	1.030	0.838	0.875	0.848	4.0
M1.2	0.25	1.230	1.038	1.077	1.048	4.0
M1.6	0.35	1.636	1.373	1.417	1.385	3.4
M2	0.40	2.036	1.740	1.786	1.752	3.2
M2.5	0.45	2.539	2.208	2.259	2.221	3.0
M3	0.50	3.042	2.675	2.730	2.689	2.9
M4	0.70	4.051	3.545	3.608	3.562	2.4
M5	0.80	5.054	4.480	4.547	4.498	2.3
M6	1.00	6.060	5.350	5.424	5.370	2.0
M8	1.25	8.066	7.188	7.270	7.210	1.8
M10	1.50	10.072	9.026	9.116	9.050	1.6
M12	1.75	12.078	10.863	10.961	10.889	1.5
M16	2.00	16.084	14.701	14.811	14.729	1.4
M20	2.50	20.093	18.376	18.497	18.407	1.3
M24	3.00	24.102	22.051	22.183	22.085	1.2
M30	3.50	30.111	27.727	27.874	27.764	1.1
M36	4.00	36.117	33.402	33.563	33.441	1.0

[a] See notes under Table 27.

Table 27. British Standard Screwing Taps for ISO Metric Threads Dimensional Limits for the Threaded Portion of Ground Taps—Coarse-and Fine-Pitch *BS 949: Part 1:1976*

Thread			All Classes of Taps		Class 1 Taps		Class 2 Taps		Class 3 Taps		Tolerance on ½ Thd Angle
					Pitch Diameter						
Designation	Nominal Major Dia. (basic) d	Pitch p	Min. Major Dia. $d_{1\min}$[a]	Basic Pitch Dia. d_2	$d_2$min	$d_2$max	$d_2$min	$d_2$max	$d_2$min	$d_2$max	
COARSE-PITCH THREAD SERIES											
M1	1	0.25	1.022	0.838	0.844	0.855	…	…	…	…	±60′
M1.2	1.2	0.25	1.222	1.038	1.044	1.055	…	…	…	…	±60′
M1.6	1.6	0.35	1.627	1.373	1.380	1.393	1.393	1.407	…	…	±50′
M2	2	0.40	2.028	1.740	1.747	1.761	1.761	1.776	…	…	±40′
M2.5	2.5	0.45	2.530	2.208	2.216	2.231	2.231	2.246	…	…	±38′
M3	3	0.50	3.032	2.675	2.683	2.699	2.699	2.715	2.715	2.731	±36′
M4	4	0.70	4.038	3.545	3.555	3.574	3.574	3.593	3.593	3.612	±30′
M5	5	0.80	5.040	4.480	4.490	4.510	4.510	4.530	4.530	4.550	±26′
M6	6	1.00	6.047	5.350	5.362	5.385	5.385	5.409	5.409	5.433	±24′
M8	8	1.25	8.050	7.188	7.201	7.226	7.226	7.251	7.251	7.276	±22′
M10	10	1.50	10.056	9.026	9.040	9.068	9.068	9.096	9.096	9.124	±20′
M12	12	1.75	12.064	10.863	10.879	10.911	10.911	10.943	10.943	10.975	±19′
M16	16	2.00	16.068	14.701	14.718	14.752	14.752	14.786	14.786	14.820	±18′
M20	20	2.50	20.072	18.376	18.394	18.430	18.430	18.466	18.466	18.502	±16′
M24	24	3.00	24.085	22.051	22.072	22.115	22.115	22.157	22.157	22.199	±14′

Copyright 2004, Industrial Press, Inc., New York, NY

Table 27. ***(Continued)*** **British Standard Screwing Taps for ISO Metric Threads Dimensional Limits for the Threaded Portion of Ground Taps—Coarse-and Fine-Pitch** *BS 949: Part 1:1976*

Thread			All Classes of Taps		Class 1 Taps		Class 2 Taps		Class 3 Taps		Tolerance on ½ Thd Angle
					Pitch Diameter						
Designation	Nominal Major Dia. (basic) d	Pitch p	Min. Major Dia. d_{min}[a]	Basic Pitch Dia. d_2	$d_2$min	$d_2$max	$d_2$min	$d_2$max	$d_2$min	$d_2$max	
M30	30	3.50	30.090	27.727	27.749	27.794	27.794	27.839	27.839	27.884	±13′
M36	36	4.00	36.094	33.402	33.426	33.473	33.473	33.520	33.520	33.567	±12′
FINE-PITCH THREAD SIZES											
M1 × 0.2	1	0.20	1.020	0.870	0.875	0.885	…	…	…	…	±70′
M1.2 × 0.2	1.2	0.20	1.220	1.070	1.075	1.085	…	…	…	…	±70′
M1.6 × 0.2	1.6	0.20	1.621	1.470	1.475	1.485	…	…	…	…	±70′
M2 × 0.25	2	0.25	2.024	1.838	1.844	1.856	…	…	…	…	±60′
M2.5 × 0.35	2.5	0.35	2.527	2.273	2.280	2.293	2.293	2.307	…	…	±50′
M3 × 0.35	3	0.35	3.028	2.773	2.780	2.794	2.794	2.809	…	…	±50′
M4 × 0.5	4	0.50	4.032	3.675	3.683	3.699	3.699	3.715	3.715	3.731	±36′
M5 × 0.5	5	0.50	5.032	4.675	4.683	4.699	4.699	4.715	4.715	4.731	±36′
M6 × 0.75	6	0.75	6.042	5.513	5.524	5.545	5.545	5.566	5.566	5.587	±28′
M8 × 1	8	1.00	8.047	7.350	7.362	7.385	7.385	7.409	7.409	7.433	±24′
M10 × 1.25	10	1.25	10.050	9.188	9.201	9.226	9.226	9.251	9.251	9.276	±22′
M12 × 1.25	12	1.25	12.056	11.188	11.202	11.230	11.230	11.258	11.258	11.286	±22′
M16 × 1.5	16	1.50	16.060	15.026	15.041	15.071	15.071	15.101	15.101	15.131	±20′
M20 × 1.5	20	1.50	20.060	19.026	19.041	19.071	19.071	19.101	19.101	19.131	±20′
M24 × 2	24	2.00	24.072	22.701	22.719	22.755	22.755	22.791	22.791	22.827	±18′
M30 × 2	30	2.00	30.072	28.701	28.719	28.755	28.755	28.791	28.791	28.827	±18′

[a] The maximum tap major diameter, d max, is not specified and is left to the manufacturer's discretion.

All dimension are in millimeters. The thread sizes in the table have been selected from the preferred series shown in BS 3643:Part 1:1981 (1998). For other sizes, and for second and third choice combinations of diameters and pitches, see the Standard.

Tolerance Classes of Taps: Three tolerance classes (class 1, class 2, and class 3) are used for the designation of taps used for the production of nuts of the following classes:

nut classes 4H, 5H, 6H, 7H, and 8H, all having zero minimum clearance;

nut classes 4G, 5G, and 6G, all having positive minimum clearance.

The tolerances for the three classes of taps are stated in terms of a tolerance unit t, the value of which is equal to the pitch diameter tolerance, T_{D2}, grade 5, of the nut. Thus, $t = T_{D2}$, grade 5, of the nut. Taps of the different classes vary in the limits of size of the tap pitch diameter. The tolerance on the tap pitch diameter, T_{d2}, is the same for all three classes of taps (20 percent of t), but the position of the tolerance zone with respect to the basic pitch diameter depends upon the lower deviation value Em which is: for tap class 1, $Em = +0.1t$; for tap class 2, $Em = +0.3t$; and for tap class 3, $Em = +0.5t$.

Copyright 2004, Industrial Press, Inc., New York, NY



The disposition of the tolerances described is shown in the accompanying illustration of nut class tolerances compared against tap class tolerances. The distance *EI* shown in this illustration is the minumum clearance, which is zero for *H* classes and positive for *G* classes of nuts.

Choice of Tap Tolerance Class: Unless otherwise specified, class 1 taps are used for nuts of classes 4H and 5H; class 2 taps for nuts of classes 6H, 4G, and 5G; and class 3 taps for nuts of classes 7H, 8H, and 6G. This relationship of tap and nut classes is a general one, since the accuracy of tapping varies with a number of factors such as the material being tapped, the condition of the machine tool used, the tapping attachment used, the tapping speed, and the lubricant.

Tap Major Diameter: Except when a screwed connection has to be tight against gaseous or liquid pressure, it is undesirable for the mating threads to bear on the roots and crests. By avoiding contact in these regions of the threads, the opposite flanks of the two threads are allowed to make proper load bearing contact when the connection is tightened. In general, the desired clearance between crests and roots of mating threads is obtained by increasing the major and minor diameters of the internal thread. Such an increase in the minor diameter is already provided on threads such as the ISO metric thread, in which there is a basic clearance between the crests of minimum size nuts and the roots of maximum size bolts. For this reason, and the fact that taps are susceptible to wear on the crests of their threads, a minimum size is specified for the major diameter of new taps which provides a reasonable margin for the wear of their crests and at the same time provides the desired clearance at the major diameter of the hole. These minimum major diameters for taps are shown in Tables 26 and 13. The maximum tap major diameter is not specified and is left to the manufacturer to take advantage of this concession to produce taps with as liberal a margin possible for wear on the major diameter.

Tapping Square Threads.— If it is necessary to tap square threads, this should be done by using a set of taps that will form the thread by a progressive cutting action, the taps varying in size in order to distribute the work, especially for threads of comparatively coarse pitch. From three to five taps may be required in a set, depending upon the pitch. Each tap should have a pilot to steady it. The pilot of the first tap has a smooth cylindrical end from 0.003 to 0.005 inch smaller than the hole, and the pilots of following taps should have teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

STANDARD TAPERS

Standard Tapers

Certain types of small tools and machine parts, such as twist drills, end mills, arbors, lathe centers, etc., are provided with taper shanks which fit into spindles or sockets of corresponding taper, thus providing not only accurate alignment between the tool or other part and its supporting member, but also more or less frictional resistance for driving the tool. There are several standards for "self-holding" tapers, but the American National, Morse, and the Brown & Sharpe are the standards most widely used by American manufacturers.

The name *self-holding* has been applied to the smaller tapers—like the Morse and the Brown & Sharpe—because, where the angle of the taper is only 2 or 3 degrees, the shank of a tool is so firmly seated in its socket that there is considerable frictional resistance to any force tending to turn or rotate the tool relative to the socket. The term "self-holding" is used to distinguish relatively small tapers from the larger or *self-releasing* type. A milling machine spindle having a taper of 3½ inches per foot is an example of a self-releasing taper. The included angle in this case is over 16 degrees and the tool or arbor requires a positive locking device to prevent slipping, but the shank may be released or removed more readily than one having a smaller taper of the self-holding type.

Morse Taper.— Dimensions relating to Morse standard taper shanks and sockets may be found in an accompanying table. The taper for different numbers of Morse tapers is slightly different, but it is approximately ⅝ inch per foot in most cases. The table gives the actual tapers, accurate to five decimal places. Morse taper shanks are used on a variety of tools, and exclusively on the shanks of twist drills. Dimensions for *Morse Stub Taper Shanks* are given in Table 1a, and for *Morse Standard Taper Shanks* in Table 1b.

Brown & Sharpe Taper.— This standard taper is used for taper shanks on tools such as end mills and reamers, the taper being approximately ½ inch per foot for all sizes except for taper No. 10, where the taper is 0.5161 inch per foot. Brown & Sharpe taper sockets are used for many arbors, collets, and machine tool spindles, especially milling machines and grinding machines. In many cases there are a number of different lengths of sockets corresponding to the same number of taper; all these tapers, however, are of the same diameter at the small end.

Jarno Taper.— The Jarno taper was originally proposed by Oscar J. Beale of the Brown & Sharpe Mfg. Co. This taper is based on such simple formulas that practically no calculations are required when the number of taper is known. The taper per foot of all Jarno taper sizes is 0.600 inch on the diameter. The diameter at the large end is as many eighths, the diameter at the small end is as many tenths, and the length as many half inches as are indicated by the number of the taper. For example, a No. 7 Jarno taper is ⅞ inch in diameter at the large end; $^{7}/_{10}$, or 0.700 inch at the small end; and $^{7}/_{2}$, or 3½ inches long; hence, diameter at large end = No. of taper ÷ 8; diameter at small end = No. of taper ÷ 10; length of taper = No. of taper ÷ 2. The Jarno taper is used on various machine tools, especially profiling machines and die-sinking machines. It has also been used for the headstock and tailstock spindles of some lathes.

American National Standard Machine Tapers: This standard includes a self-holding series (Tables 2, 3, 4, 5 and 7a) and a steep taper series, Table 6. The self-holding taper series consists of 22 sizes which are listed in Table 7a. The reference gage for the self-holding tapers is a plug gage. Table 7b gives the dimensions and tolerances for both plug and ring gages applying to this series. Tables 2 through 5 inclusive give the dimensions for self-holding taper shanks and sockets which are classified as to (1) means of transmitting torque from spindle to the tool shank, and (2) means of retaining the shank in the socket. The steep machine tapers consist of a preferred series (bold-face type, Table 6) and an intermediate series (light-face type). A self-holding taper is defined as "a taper with an

Copyright 2004, Industrial Press, Inc., New York, NY

angle small enough to hold a shank in place ordinarily by friction without holding means. (Sometimes referred to as slow taper.)" A steep taper is defined as "a taper having an angle sufficiently large to insure the easy or self-releasing feature." The term "gage line" indicates the basic diameter at or near the large end of the taper.

Table 1a. Morse Stub Taper Shanks



No. of Taper	Taper per Foot[a]	Taper per Inch[b]	Small End of Plug,[b] *D*	Dia. End of Socket,[a] *A*	Shank		Tang	
					Total Length, *B*	Depth, *C*	Thickness, *E*	Length, *F*
1	0.59858	0.049882	0.4314	0.475	1 5/16	1 1/8	13/64	5/16
2	0.59941	0.049951	0.6469	0.700	1 11/16	1 7/16	19/64	7/16
3	0.60235	0.050196	0.8753	0.938	2	1 3/4	25/64	9/16
4	0.62326	0.051938	1.1563	1.231	2 3/8	2 1/16	33/64	11/16
5	0.63151	0.052626	1.6526	1.748	3	2 11/16	3/4	15/16

No. of Taper	Tang		Socket				Tang Slot	
	Radius of Mill, *G*	Diameter, *H*	Plug Depth, *P*	Min. Depth of Tapered Hole		Socket End to Tang Slot, *M*	Width, *N*	Length, *O*
				Drilled *X*	Reamed *Y*			
1	3/16	13/32	7/8	5/16	29/32	25/32	7/32	23/32
2	7/32	39/64	1 1/16	1 5/32	1 7/64	15/16	5/16	15/16
3	9/32	13/16	1 1/4	1 3/8	1 5/16	1 1/16	13/32	1 1/8
4	3/8	1 3/32	1 7/16	1 9/16	1 1/2	1 3/16	17/32	1 3/8
5	9/16	1 19/32	1 13/16	1 15/16	1 7/8	1 7/16	25/32	1 3/4

[a] These are basic dimensions.

[b] These dimensions are calculated for reference only.

All dimensions in inches.

Radius *J* is 3/64, 1/16, 5/64, 3/32, and 1/8 inch respectively for Nos. 1, 2, 3, 4, and 5 tapers.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Morse Standard Taper Shanks



No. of Taper	Taper per Foot	Taper per Inch	Small End of Plug *D*	Diameter End of Socket *A*	Shank		Depth of Hole *H*
					Length *B*	Depth *S*	
0	0.62460	0.05205	0.252	0.3561	2 11/32	2 7/32	2 1/32
1	0.59858	0.04988	0.369	0.475	2 9/16	2 7/16	2 5/32
2	0.59941	0.04995	0.572	0.700	3 1/8	2 15/16	2 39/64
3	0.60235	0.05019	0.778	0.938	3 7/8	3 11/16	3 1/4
4	0.62326	0.05193	1.020	1.231	4 7/8	4 5/8	4 1/8
5	0.63151	0.05262	1.475	1.748	6 1/8	5 7/8	5 1/4
6	0.62565	0.05213	2.116	2.494	8 9/16	8 1/4	7 21/64
7	0.62400	0.05200	2.750	3.270	11 5/8	11 1/4	10 5/64

Plug Depth *P*	Tang or Tongue				Keyway		Keyway to End *K*
	Thickness *t*	Length *T*	Radius *R*	Dia.	Width *W*	Length *L*	
2	0.1562	1/4	5/32	0.235	11/64	9/16	1 15/16
2 1/8	0.2031	3/8	3/16	0.343	0.218	3/4	2 1/16
2 9/16	0.2500	7/16	1/4	17/32	0.266	7/8	2 1/2
3 3/16	0.3125	9/16	9/32	23/32	0.328	1 3/16	3 1/16
4 1/16	0.4687	5/8	5/16	31/32	0.484	1 1/4	3 7/8
5 3/16	0.6250	3/4	3/8	1 13/32	0.656	1 1/2	4 15/16
7 1/4	0.7500	1 1/8	1/2	2	0.781	1 3/4	7
10	1.1250	1 3/8	3/4	2 5/8	1.156	2 5/8	9 1/2

Tolerances on rate of taper: all sizes 0.002 in. per foot. This tolerance may be applied on shanks only in the direction that increases the rate of taper, and on sockets only in the direction that decreases the rate of taper.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Taper Drive with Tang, Self-Holding Tapers *ANSI/ASME B5.10-1994 (R2002)*



No. of Taper	Diameter at Gage Line (1) *A*	Shank		Tang			
		Total Length of Shank *B*	Gage Line to End of Shank *C*	Thickness *E*	Length *F*	Radius of Mill *G*	Diameter *H*
0.239	0.23922	1.28	1.19	0.125	0.19	0.19	0.18
0.299	0.29968	1.59	1.50	0.156	0.25	0.19	0.22
0.375	0.37525	1.97	1.88	0.188	0.31	0.19	0.28
1	0.47500	2.56	2.44	0.203	0.38	0.19	0.34
2	0.70000	3.13	2.94	0.250	0.44	0.25	0.53
3	0.93800	3.88	3.69	0.312	0.56	0.22	0.72
4	1.23100	4.88	4.63	0.469	0.63	0.31	0.97
4½	1.50000	5.38	5.13	0.562	0.69	0.38	1.20
5	1.74800	6.12	5.88	0.625	0.75	0.38	1.41
6	2.49400	8.25	8.25	0.750	1.13	0.50	2.00

No. of Taper	Radius *J*	Socket		Gage Line to Tang Slot *M*	Tang Slot		
		Min. Depth of Hole *K*			Width *N*	Length *O*	Shank End to Back of Tang Slot *P*
		Drilled	Reamed				
0.239	0.03	1.06	1.00	0.94	0.141	0.38	0.13
0.299	0.03	1.31	1.25	1.17	0.172	0.50	0.17
0.375	0.05	1.63	1.56	1.47	0.203	0.63	0.22
1	0.05	2.19	2.16	2.06	0.218	0.75	0.38
2	0.06	2.66	2.61	2.50	0.266	0.88	0.44
3	0.08	3.31	3.25	3.06	0.328	1.19	0.56
4	0.09	4.19	4.13	3.88	0.484	1.25	0.50
4½	0.13	4.62	4.56	4.31	0.578	1.38	0.56
5	0.13	5.31	5.25	4.94	0.656	1.50	0.56
6	0.16	7.41	7.33	7.00	0.781	1.75	0.50

All dimensions are in inches. (1) See Table 7b for plug and ring gage dimensions.

Tolerances: For shank diameter *A* at gage line, + 0.002 – 0.000; for hole diameter *A*, + 0.000 – 0.002. For tang thickness *E* up to No. 5 inclusive, + 0.000 – 0.006; No. 6, + 0.000 – 0.008. For width *N* of tang slot up to No. 5 inclusive, + 0.006; – 0.000; No. 6, + 0.008 – 0.000. For centrality of tang *E* with center line of taper, 0.0025 (0.005 total indicator variation). These centrality tolerances also apply to the tang slot *N*. On rate of taper, all sizes 0.002 per foot. This tolerance may be applied on *shanks* only in the direction which *increases* the rate of taper and on *sockets* only in the direction which *decreases* the rate of taper. Tolerances for two-decimal dimensions are plus or minus 0.010, unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Taper Drive with Keeper Key Slot, Self-Holding Tapers *ANSI/ASME B5.10-1994 (R2002)*



No. of Taper	Dia. at Gage Line (1) *A*	Shank		Tang					Socket		
		Total Length *B*	Gage Line to End *C*	Thickness *E*	Length *F*	Radius of Mill *G*	Diameter *H*	Radius *J*	Min. Depth of Hole *K*		Gage Line to Tang Slot *M*
									Drill	Ream	
3	0.938	3.88	3.69	0.312	0.56	0.28	0.78	0.08	3.31	3.25	3.06
4	1.231	4.88	4.63	0.469	0.63	0.31	0.97	0.09	4.19	4.13	3.88
4½	1.500	5.38	5.13	0.562	0.69	0.38	1.20	0.13	4.63	4.56	4.32
5	1.748	6.13	5.88	0.625	0.75	0.38	1.41	0.13	5.31	5.25	4.94
6	2.494	8.56	8.25	0.750	1.13	0.50	2.00	0.16	7.41	7.33	7.00
7	3.270	11.63	11.25	1.125	1.38	0.75	2.63	0.19	10.16	10.08	9.50

No. of Taper	Tang Slot			Keeper Slot in Shank			Keeper Slot in Socket		
	Width *N*	Length *O*	Shank End to Back of Slot *P*	Gage Line to Bottom of Slot *Y′*	Length *X*	Width *N′*	Gage Line to Front of Slot *Y*	Length *Z*	Width *N′*
3	0.328	1.19	0.56	1.03	1.13	0.266	1.13	1.19	0.266
4	0.484	1.25	0.50	1.41	1.19	0.391	1.50	1.25	0.391
4½	0.578	1.38	0.56	1.72	1.25	0.453	1.81	1.38	0.453
5	0.656	1.50	0.56	2.00	1.38	0.516	2.13	1.50	0.516
6	0.781	1.75	0.50	2.13	1.63	0.641	2.25	1.75	0.641
7	1.156	2.63	0.88	2.50	1.69	0.766	2.63	1.81	0.766

All dimensions are in inches. (1) See Table 7b for plug and ring gage dimensions.

Tolerances: For shank diameter *A* at gage line, +0.002, –0; for hole diameter *A*, +0, –0.002. For tang thickness *E* up to No. 5 inclusive, +0, –0.006; larger than No. 5, +0, –0.008. For width of slots *N* and *N′* up to No. 5 inclusive, +0.006, –0; larger than No. 5, +0.008, –0. For centrality of tang *E* with center line of taper 0.0025 (0.005 total indicator variation). These centrality tolerances also apply to slots *N* and *N′*. On rate of taper, see footnote in Table 2. Tolerances for two-decimal dimensions are ±0.010 unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Nose Key Drive with Keeper Key Slot, Self-Holding Tapers *ANSI/ASME B5.10-1994 (R2002)*



Taper	*A*(1)	*B′*	*C*	*Q*	*I′*	*I*	*R*	*S*
200	2.000	5.13		0.25	1.38	1.63	1.010	0.562
250	2.500	5.88		0.25	1.38	2.06	1.010	0.562
300	3.000	6.63	Min 0.003 Max 0.035 for all sizes	0.25	1.63	2.50	2.010	0.562
350	3.500	7.44		0.31	2.00	2.94	2.010	0.562
400	4.000	8.19		0.31	2.13	3.31	2.010	0.562
450	4.500	9.00		0.38	2.38	3.81	3.010	0.812
500	5.000	9.75		0.38	2.50	4.25	3.010	0.812
600	6.000	11.31		0.44	3.00	5.19	3.010	0.812
800	8.000	14.38		0.50	3.50	7.00	4.010	1.062
1000	10.000	17.44		0.63	4.50	8.75	4.010	1.062
1200	12.000	20.50		0.75	5.38	10.50	4.010	1.062

Taper	*D*	*D′*[a]	*W*	*X*	*N′*	*R′*	*S′*	*T*
200	1.41	0.375	3.44	1.56	0.656	1.000	0.50	4.75
250	1.66	0.375	3.69	1.56	0.781	1.000	0.50	5.50
300	2.25	0.375	4.06	1.56	1.031	2.000	0.50	6.25
350	2.50	0.375	4.88	2.00	1.031	2.000	0.50	6.94
400	2.75	0.375	5.31	2.25	1.031	2.000	0.50	7.69
450	3.00	0.500	5.88	2.44	1.031	3.000	0.75	8.38
500	3.25	0.500	6.44	2.63	1.031	3.000	0.75	9.13
600	3.75	0.500	7.44	3.00	1.281	3.000	0.75	10.56
800	4.75	0.500	9.56	4.00	1.781	4.000	1.00	13.50
1000	…	…	11.50	4.75	2.031	4.000	1.00	16.31
1200	…	…	13.75	5.75	2.031	4.000	1.00	19.00

Taper	*U*	*V*	*M*	*N*	*O*	*P*	*Y*	Z
200	1.81	1.00	4.50	0.656	1.56	0.94	2.00	1.69
250	2.25	1.00	5.19	0.781	1.94	1.25	2.25	1.69
300	2.75	1.00	5.94	1.031	2.19	1.50	2.63	1.69
350	3.19	1.25	6.75	1.031	2.19	1.50	3.00	2.13
400	3.63	1.25	7.50	1.031	2.19	1.50	3.25	2.38
450	4.19	1.50	8.00	1.031	2.75	1.75	3.63	2.56
500	4.63	1.50	8.75	1.031	2.75	1.75	4.00	2.75
600	5.50	1.75	10.13	1.281	3.25	2.06	4.63	3.25
800	7.38	2.00	12.88	1.781	4.25	2.75	5.75	4.25
1000	9.19	2.50	15.75	2.031	5.00	3.31	7.00	5.00
1200	11.00	3.00	18.50	2.531	6.00	4.00	8.25	6.00

[a] Thread is UNF-2B for hole; UNF-2A for screw. (1) See Table 7b for plug and ring gage dimensions.

All dimensions are in inches. *AE* is 0.005 greater than one-half of *A*.

Width of drive key *R″* is 0.001 less than width *R″* of keyway.

Tolerances: For diameter *A* of hole at gage line, +0, –0.002; for diameter *A* of shank at gage line, +0.002, –0; for width of slots *N* and *N′*, +0.008, –0; for width of drive keyway *R′* in socket, +0, –0.001; for width of drive keyway *R* in shank, 0.010, –0; for centrality of slots *N* and *N′* with center line of spindle, 0.007; for centrality of keyway with spindle center line: for *R*, 0.004 and for *R′*, 0.002 T.I.V. On rate of taper, see footnote in Table 2. Two-decimal dimensions, ±0.010 unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Nose Key Drive with Drawbolt, Self-Holding Tapers *ANSI/ASME B5.10-1994 (R2002)*



Sockets										
		Drive Key			Drive Keyway					
		Screw Holes								
No. of Taper	Dia. at Gage Line *A*[a]	Center Line to Center of Screw *D*	UNF 2B Hole UNF 2A Screw *D′*	Width *R″*	Width *R′*	Depth *S′*	Gage Line to Front of Relief *T*	Dia. of Relief *U*	Depth of Relief *V*	Dia. of Draw Bolt Hole *d*
200	2.000	1.41	0.38	0.999	1.000	0.50	4.75	1.81	1.00	1.00
250	2.500	1.66	0.38	0.999	1.000	0.50	5.50	2.25	1.00	1.00
300	3.000	2.25	0.38	1.999	2.000	0.50	6.25	2.75	1.00	1.13
350	3.500	2.50	0.38	1.999	2.000	0.50	6.94	3.19	1.25	1.13
400	4.000	2.75	0.38	1.999	2.000	0.50	7.69	3.63	1.25	1.63
450	4.500	3.00	0.50	2.999	3.000	0.75	8.38	4.19	1.50	1.63
500	5.000	3.25	0.50	2.999	3.000	0.75	9.13	4.63	1.50	1.63
600	6.000	3.75	0.50	2.999	3.000	0.75	10.56	5.50	1.75	2.25
800	8.000	4.75	0.50	3.999	4.000	1.00	13.50	7.38	2.00	2.25
1000	10.000	…	…	3.999	4.000	1.00	16.31	9.19	2.50	2.25
1200	12.000	…	…	3.999	4.000	1.00	19.00	11.00	3.00	2.25

[a] See Table 7b for plug and ring gage dimensions.

Shanks										
		Drawbar Hole						Drive Keyway		
No. of Taper	Length from Gage Line B′	Dia. UNC-2B *AL*	Depth of Drilled Hole *E*	Depth of Thread *AP*	Dia. of Counter Bore *G*	Gage Line to First Thread *AO*	Depth of 60° Chamfer *J*	Width *R*	Depth *S*	Center Line to Bottom of Keyway *AE*
200	5.13	⅞–9	2.44	1.75	0.91	4.78	0.13	1.010	0.562	1.005
250	5.88	⅞–9	2.44	1.75	0.91	5.53	0.13	1.010	0.562	1.255
300	6.63	1–8	2.75	2.00	1.03	6.19	0.19	2.010	0.562	1.505
350	7.44	1–8	2.75	2.00	1.03	7.00	0.19	2.010	0.562	1.755
400	8.19	1½–6	4.00	3.00	1.53	7.50	0.31	2.010	0.562	2.005
450	9.00	1½–6	4.00	3.00	1.53	8.31	0.31	3.010	0.812	2.255
500	9.75	1½–6	4.00	3.00	1.53	9.06	0.31	3.010	0.812	2.505
600	11.31	2–4½	5.31	4.00	2.03	10.38	0.50	3.010	0.812	3.005
800	14.38	2–4½	5.31	4.00	2.03	13.44	0.50	4.010	1.062	4.005
1000	17.44	2–4½	5.31	4.00	2.03	16.50	0.50	4.010	1.062	5.005
1200	20.50	2–4½	5.31	4.00	2.03	19.56	0.50	4.010	1.062	6.005

All dimensions in inches.

Exposed length *C* is 0.003 minimum and 0.035 maximum for all sizes.

Drive Key *D′* screw sizes are ⅜–24 UNF-2A up to taper No. 400 inclusive and ½–20 UNF-2A for larger tapers.

Tolerances: For diameter *A* of hole at gage line, +0.000, –0.002 for all sizes; for diameter *A* of shank at gage line, +0.002, –0.000; for all sizes; for width of drive keyway *R′* in socket, +0.000, –0.001; for width of drive keyway *R* in shank, +0.010, –0.000; for centrality of drive keyway *R′*, with center line of shank, 0.004 total indicator variation, and for drive keyway *R′*, with center line of spindle, 0.002. On rate of taper, see footnote in Table 2. Tolerances for two-decimal dimensions are ±0.010 unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ANSI Standard Steep Machine Tapers *ANSI/ASME B5.10-1994 (R2002)*

No. of Taper	Taper per Foot[a]	Dia. at Gage Line[b]	Length Along Axis	No. of Taper	Taper per Foot[a]	Dia.at Gage Line[b]	Length Along Axis
5	3.500	0.500	0.6875	35	3.500	1.500	2.2500
10	**3.500**	**0.625**	**0.8750**	**40**	**3.500**	**1.750**	**2.5625**
15	3.500	0.750	1.0625	45	3.500	2.250	3.3125
20	**3.500**	**0.875**	**1.3125**	**50**	**3.500**	**2.750**	**4.0000**
25	3.500	1.000	1.5625	55	3.500	3.500	5.1875
30	**3.500**	**1.250**	**1.8750**	**60**	**3.500**	**4.250**	**6.3750**

[a] This taper corresponds to an included angle of 16°, 35′, 39.4″.
[b] The basic diameter at gage line is at large end of taper.

All dimensions given in inches.

The tapers numbered 10, 20, 30, 40, 50, and 60 that are printed in heavy-faced type are designated as the "Preferred Series." The tapers numbered 5, 15, 25, 35, 45, and 55 that are printed in light-faced type are designated as the "Intermediate Series."

Table 7a. American National Standard Self-holding Tapers — Basic Dimensions *ANSI/ASME B5.10-1994 (R2002)*

No. of Taper	Taper per Foot	Dia. at Gage Line[a] *A*	Means of Driving and Holding[a]	Origin of Series
.239	0.50200	0.23922	} Tang Drive With Shank Held in by Friction (See Table 2)	Brown & Sharpe Taper Series
.299	0.50200	0.29968		
.375	0.50200	0.37525		
1	0.59858	0.47500	} Tang Drive With Shank Held in by Key (See Table 3)	Morse Taper Series
2	0.59941	0.70000		
3	0.60235	0.93800		
4	0.62326	1.23100		
4½	0.62400	1.50000		
5	0.63151	1.74800		
6	0.62565	2.49400		
7	0.62400	3.27000		
200	0.750	2.000	} Key Drive With Shank Held in by Key (See Table 4) } Key Drive With Shank Held in by Draw-bolt (See Table 5)	¾ Inch per Foot Taper Series
250	0.750	2.500		
300	0.750	3.000		
350	0.750	3.500		
400	0.750	4.000		
450	0.750	4.500		
500	0.750	5.000		
600	0.750	6.000		
800	0.750	8.000		
1000	0.750	10.000		
1200	0.750	12.000		

[a] See illustrations above Tables 2 through 5.

All dimensions given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7b. American National Standard Plug and Ring Gages for the Self-Holding Taper Series *ANSI/ASME B5.10-1994 (R2002)*



No. of Taper	Taper[a] per Foot	Diameter[a] at Gage Line *A*	Tolerances for Diameter *A*[b]			Diameter at Small End *A′*	Length Gage Line to End *L*	Depth of Gaging-Notch, Plug Gage *L′*
			Class X Gage	Class Y Gage	Class Z Gage			
0.239	0.50200	0.23922	0.00004	0.00007	0.00010	0.20000	0.94	0.048
0.299	0.50200	0.29968	0.00004	0.00007	0.00010	0.25000	1.19	0.048
0.375	0.50200	0.37525	0.00004	0.00007	0.00010	0.31250	1.50	0.048
1	0.59858	0.47500	0.00004	0.00007	0.00010	0.36900	2.13	0.040
2	0.59941	0.70000	0.00004	0.00007	0.00010	0.57200	2.56	0.040
3	0.60235	0.93800	0.00006	0.00009	0.00012	0.77800	3.19	0.040
4	0.62326	1.23100	0.00006	0.00009	0.00012	1.02000	4.06	0.038
4½	0.62400	1.50000	0.00006	0.00009	0.00012	1.26600	4.50	0.038
5	0.63151	1.74800	0.00008	0.00012	0.00016	1.47500	5.19	0.038
6	0.62565	2.49400	0.00008	0.00012	0.00016	2.11600	7.25	0.038
7	0.62400	3.27000	0.00010	0.00015	0.00020	2.75000	10.00	0.038
200	0.75000	2.00000	0.00008	0.00012	0.00016	1.703	4.75	0.032
250	0.75000	2.50000	0.00008	0.00012	0.00016	2.156	5.50	0.032
300	0.75000	3.00000	0.00010	0.00015	0.00020	2.609	6.25	0.032
350	0.75000	3.50000	0.00010	0.00015	0.00020	3.063	7.00	0.032
400	0.75000	4.00000	0.00010	0.00015	0.00020	3.516	7.75	0.032
450	0.75000	4.50000	0.00010	0.00015	0.00020	3.969	8.50	0.032
500	0.75000	5.00000	0.00013	0.00019	0.00025	4.422	9.25	0.032
600	0.75000	6.00000	0.00013	0.00019	0.00025	5.328	10.75	0.032
800	0.75000	8.00000	0.00016	0.00024	0.00032	7.141	13.75	0.032
1000	0.75000	10.00000	0.00020	0.00030	0.00040	8.953	16.75	0.032
1200	0.75000	12.00000	0.00020	0.00030	0.00040	10.766	19.75	0.032

[a] The taper per foot and diameter *A* at gage line are basic dimensions. Dimensions in Column *A′* are calculated for reference only.

[b] Tolerances for diameter *A* are plus for plug gages and minus for ring gages.

All dimensions are in inches.

The amount of taper deviation for Class X, Class Y, and Class Z gages are the same, respectively, as the amounts shown for tolerances on diameter *A*. Taper deviation is the permissible allowance from true taper at any point of diameter in the length of the gage. On taper *plug* gages, this deviation may be applied only in the direction which *decreases* the rate of taper. On taper *ring* gages, this deviation may be applied only in the direction which *increases* the rate of taper. Tolerances on two-decimal dimensions are ±0.010.

British Standard Tapers.— British Standard 1660: 1972, "Machine Tapers, Reduction Sleeves, and Extension Sockets," contains dimensions for self-holding and self-releasing tapers, reduction sleeves, extension sockets, and turret sockets for tools having Morse and metric 5 per cent taper shanks. Adapters for use with 7/24 tapers and dimensions for spindle noses and tool shanks with self-release tapers and cotter slots are included in this Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Dimensions of Morse Taper Sleeves



A	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*I*	*K*	*L*	*M*
2	1	3 9/16	0.700	5/8	1/4	7/16	2 3/16	0.475	2 1/16	3/4	0.213
3	1	3 15/16	0.938	1/4	5/16	9/16	2 3/16	0.475	2 1/16	3/4	0.213
3	2	4 7/16	0.938	3/4	5/16	9/16	2 5/8	0.700	2 1/2	7/8	0.260
4	1	4 7/8	1.231	1/4	15/32	5/8	2 3/16	0.475	2 1/16	3/4	0.213
4	2	4 7/8	1.231	1/4	15/32	5/8	2 5/8	0.700	2 1/2	7/8	0.260
4	3	5 3/8	1.231	3/4	15/32	5/8	3 1/4	0.938	3 1/16	1 3/16	0.322
5	1	6 1/8	1.748	1/4	5/8	3/4	2 3/16	0.475	2 1/16	3/4	0.213
5	2	6 1/8	1.748	1/4	5/8	3/4	2 5/8	0.700	2 1/2	7/8	0.260
5	3	6 1/8	1.748	1/4	5/8	3/4	3 1/4	0.938	3 1/16	1 3/16	0.322
5	4	6 5/8	1.748	3/4	5/8	3/4	4 1/8	1.231	3 7/8	1 1/4	0.478
6	1	8 5/8	2.494	3/8	3/4	1 1/8	2 3/16	0.475	2 1/16	3/4	0.213
6	2	8 5/8	2.494	3/8	3/4	1 1/8	2 5/8	0.700	2 1/2	7/8	0.260
6	3	8 5/8	2.494	3/8	3/4	1 1/8	3 1/4	0.938	3 1/16	1 3/16	0.322
6	4	8 5/8	2.494	3/8	3/4	1 1/8	4 1/8	1.231	3 7/8	1 1/4	0.478
6	5	8 5/8	2.494	3/8	3/4	1 1/8	5 1/4	1.748	4 15/16	1 1/2	0.635
7	3	11 5/8	3.270	3/8	1 1/8	1 3/8	3 1/4	0.938	3 1/16	1 3/16	0.322
7	4	11 5/8	3.270	3/8	1 1/8	1 3/8	4 1/8	1.231	3 7/8	1 1/4	0.478
7	5	11 5/8	3.270	3/8	1 1/8	1 3/8	5 1/4	1.748	4 15/16	1 1/2	0.635
7	6	12 1/2	3.270	1 1/4	1 1/8	1 3/8	7 3/8	2.494	7	1 3/4	0.760

Table 9. Morse Taper Sockets — Hole and Shank Sizes



	Morse Taper			Morse Taper			Morse Taper	
Size	Hole	Shank	Size	Hole	Shank	Size	Hole	Shank
1 by 2	No. 1	No. 2	2 by 5	No. 2	No. 5	4 by 4	No. 4	No. 4
1 by 3	No. 1	No. 3	3 by 2	No. 3	No. 2	4 by 5	No. 4	No. 5
1 by 4	No. 1	No. 4	3 by 3	No. 3	No. 3	4 by 6	No. 4	No. 6
1 by 5	No. 1	No. 5	3 by 4	No. 3	No. 4	5 by 4	No. 5	No. 4
2 by 3	No. 2	No. 3	3 by 5	No. 3	No. 5	5 by 5	No. 5	No. 5
2 by 4	No. 2	No. 4	4 by 3	No. 4	No. 3	5 by 6	No. 5	No. 6

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Brown & Sharpe Taper Shanks



Number of Taper	Taper per Foot (inch)	Dia. of Plug at Small End	Plug Depth, *P*			Keyway from End of Spindle	Shank Depth	Length of Keyway[a]	Width of Keyway	Length of Arbor Tongue	Diameter of Arbor Tongue	Thickness of Arbor Tongue
			B & S[b] Standard	Mill. Mach. Standard	Miscell.							
		D				*K*	*S*	*L*	*W*	*T*	*d*	*t*
1[c]	.50200	.20000	15/16	…	…	15/16	1 3/16	3/8	.135	3/16	.170	1/8
2[c]	.50200	.25000	1 3/16	…	…	1 11/64	1 1/2	1/2	.166	1/4	.220	5/32
3[c]	.50200	.31250	1 1/2	…	…	1 15/32	1 7/8	5/8	.197	5/16	.282	3/16
			…	…	1 3/4	1 23/32	2 1/8	5/8	.197	5/16	.282	3/16
			…	…	2	1 31/32	2 3/8	5/8	.197	5/16	.282	3/16
4	.50240	.35000	…	1 1/4	…	1 13/64	1 21/32	11/16	.228	11/32	.320	7/32
			1 11/16	…	…	1 41/64	2 3/32	11/16	.228	11/32	.320	7/32
5	.50160	.45000	…	1 3/4	…	1 11/16	2 3/16	3/4	.260	3/8	.420	1/4
			…	…	2	1 15/16	2 7/16	3/4	.260	3/8	.420	1/4
			2 1/8	…	…	2 1/16	2 9/16	3/4	.260	3/8	.420	1/4
6	.50329	.50000	2 3/8	…	…	2 19/64	2 7/8	7/8	.291	7/16	.460	9/32
7	.50147	.60000	…	…	2 1/2	2 13/32	3 1/32	15/16	.322	15/32	.560	5/16
			2 7/8	…	…	2 25/32	3 13/32	15/16	.322	15/32	.560	5/16
			…	3	…	2 29/32	3 17/32	15/16	.322	15/32	.560	5/16
8	.50100	.75000	3 9/16	…	…	3 29/64	4 1/8	1	.353	1/2	.710	11/32
9	.50085	.90010	…	4	…	3 7/8	4 5/8	1 1/8	.385	9/16	.860	3/8
			4 1/4	…	…	4 1/8	4 7/8	1 1/8	.385	9/16	.860	3/8
10	.51612	1.04465	5	…	…	4 27/32	5 23/32	1 5/16	.447	21/32	1.010	7/16
			…	5 11/16	…	5 17/32	6 13/32	1 5/16	.447	21/32	1.010	7/16
			…	…	6 7/32	6 1/16	6 15/16	1 5/16	.447	21/32	1.010	7/16
11	.50100	1.24995	5 15/16	…	…	5 25/32	6 21/32	1 5/16	.447	21/32	1.210	7/16
			…	6 3/4	…	6 19/32	7 15/32	1 5/16	.447	21/32	1.210	7/16
12	.49973	1.50010	7 1/8	7 1/8	…	6 15/16	7 15/16	1 1/2	.510	3/4	1.460	1/2
			…	…	6 1/4	…	…	…	…	…	…	…
13	.50020	1.75005	7 3/4	…	…	7 9/16	8 9/16	1 1/2	.510	3/4	1.710	1/2
14	.50000	2.00000	8 1/4	8 1/4	…	8 1/32	9 5/32	1 11/16	.572	27/32	1.960	9/16
15	.5000	2.25000	8 3/4	…	…	8 17/32	9 21/32	1 11/16	.572	27/32	2.210	9/16
16	.50000	2.50000	9 1/4	…	…	9	10 1/4	1 7/8	.635	15/16	2.450	5/8
17	.50000	2.75000	9 3/4	…	…	…	…	…	…	…	…	…
18	.50000	3.00000	10 1/4	…	…	…	…	…	…	…	…	…

[a] Special lengths of keyway are used instead of standard lengths in some places. Standard lengths need not be used when keyway is for driving only and not for admitting key to force out tool.

[b] "B & S Standard" Plug Depths are not used in all cases.

[c] Adopted by American Standards Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Jarno Taper Shanks



$$D = \frac{\text{no. of taper}}{8} \qquad C = \frac{\text{no. of taper}}{10} \qquad B = \frac{\text{no. of taper}}{2}$$

Number of Taper	Length *A*	Length *B*	Diameter *C*	Diameter *D*	Taper per foot
2	1 1/8	1	0.20	0.250	0.600
3	1 5/8	1 1/2	0.30	0.375	0.600
4	2 3/16	2	0.40	0.500	0.600
5	2 11/16	2 1/2	0.50	0.625	0.600
6	3 3/16	3	0.60	0.750	0.600
7	3 11/16	3 1/2	0.70	0.875	0.600
8	4 3/16	4	0.80	1.000	0.600
9	4 11/16	4 1/2	0.90	1.125	0.600
10	5 1/4	5	1.00	1.250	0.600
11	5 3/4	5 1/2	1.10	1.375	0.600
12	6 1/4	6	1.20	1.500	0.600
13	6 3/4	6 1/2	1.30	1.625	0.600
14	7 1/4	7	1.40	1.750	0.600
15	7 3/4	7 1/2	1.50	1.875	0.600
16	8 5/16	8	1.60	2.000	0.600
17	8 13/16	8 1/2	1.70	2.125	0.600
18	9 5/16	9	1.80	2.250	0.600
19	9 13/16	9 1/2	1.90	2.375	0.600
20	10 5/16	10	2.00	2.500	0.600

Tapers for Machine Tool Spindles.— Most lathe spindles have Morse tapers, most milling machine spindles have American Standard tapers, almost all smaller milling machine spindles have R8 tapers, and large vertical milling machine spindles have American Standard tapers. The spindles of drilling machines and the taper shanks of twist drills are made to fit the Morse taper. For lathes, the Morse taper is generally used, but lathes may have the Jarno, Brown & Sharpe, or a special taper. Of 33 lathe manufacturers, 20 use the Morse taper; 5, the Jarno; 3 use special tapers of their own; 2 use modified Morse (longer than the standard but the same taper); 2 use Reed (which is a short Jarno); 1 uses the Brown & Sharpe standard. For grinding machine centers, Jarno, Morse, and Brown & Sharpe tapers are used. Of ten grinding machine manufacturers, 3 use Brown & Sharpe; 3 use Morse; and 4 use Jarno. The Brown & Sharpe taper is used extensively for milling machine and dividing head spindles. The standard milling machine spindle adopted in 1927 by the milling machine manufacturers of the National Machine Tool Builders' Association (now The Association for Manufacturing Technology [AMT]), has a taper of 3½ inches per foot. This comparatively steep taper was adopted to ensure easy release of arbors.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. American National Standard Plug and Ring Gages for Steep Machine Tapers *ANSI/ASME B5.10-1994 (R2002)*



Class X Type Gage



Class Y & Z Type Gage



Class X Type Gage



Class Y & Z Type Gage

No. of Taper	Taper per Foot[a] (Basic)	Diameter at Gage Line[a] *A*	Tolerances for Diameter A[b]			Diameter at Small End[a] *A′*	Length Gage Line to Small End *L*	Overall Length of Gage Body *B*	Dia. of Opening *C*
			Class X Gage	Class Y Gage	Class Z Gage				
5	3.500	0.500	0.00004	0.00007	0.00010	0.2995	0.6875	0.81	0.30
10	3.500	0.625	0.00004	0.00007	0.00010	0.3698	0.8750	1.00	0.36
15	3.500	0.750	0.00004	0.00007	0.00010	0.4401	1.0625	1.25	0.44
20	3.500	0.875	0.00006	0.00009	0.00012	0.4922	1.3125	1.50	0.48
25	3.500	1.000	0.00006	0.00009	0.00012	0.5443	1.5625	1.75	0.53
30	3.500	1.250	0.00006	0.00009	0.00012	0.7031	1.8750	2.06	0.70
35	3.500	1.500	0.00006	0.00009	0.00012	0.8438	2.2500	2.44	0.84
40	3.500	1.750	0.00008	0.00012	0.00016	1.0026	2.5625	2.75	1.00
45	3.500	2.250	0.00008	0.00012	0.00016	1.2839	3.3125	3.50	1.00
50	3.500	2.750	0.00010	0.00015	0.00020	1.5833	4.0000	4.25	1.00
55	3.500	3.500	0.00010	0.00015	0.00020	1.9870	5.1875	5.50	1.00
60	3.500	4.250	0.00010	0.00015	0.00020	2.3906	6.3750	6.75	2.00

[a] The taper per foot and diameter *A* at gage line are basic dimensions. Dimensions in Column *A′* are calculated for reference only.

[b] Tolerances for diameter *A* are plus for plug gages and minus for ring gages.

All dimensions are in inches.

The amounts of taper deviation for Class X, Class Y, and Class Z gages are the same, respectively, as the amounts shown for tolerances on diameter *A*. Taper deviation is the permissible allowance from true taper at any point of diameter in the length of the gage. On taper *plug* gages, this deviation may be applied only in the direction which *decreases* the rate of taper. On taper *ring* gages, this deviation may be applied only in the direction which *increases* the rate of taper. Tolerances on two-decimal dimensions are ±0.010.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Jacobs Tapers and Threads for Drill Chucks and Spindles



American Standard Thread Form

Taper Series	*A*	*B*	*C*	Taper per Ft.	Taper Series	*A*	*B*	*C*	Taper per Ft.
No. 0	0.2500	0.22844	0.43750	0.59145	No. 4	1.1240	1.0372	1.6563	0.62886
No. 1	0.3840	0.33341	0.65625	0.92508	No. 5	1.4130	1.3161	1.8750	0.62010
No. 2	0.5590	0.48764	0.87500	0.97861	No. 6	0.6760	0.6241	1.0000	0.62292
No. 2[a]	0.5488	0.48764	0.75000	0.97861	No. 33	0.6240	0.5605	1.0000	0.76194
No. 3	0.8110	0.74610	1.21875	0.63898	…	…	…	…	…

[a] These dimensions are for the No. 2 "short" taper.

Thread Size	Diameter *D*		Diameter *E*		Dimension *F*	
	Max.	Min.	Max.	Min.	Max.	Min.
5/16–24	0.531	0.516	0.3245	0.3195	0.135	0.115
5/16–24	0.633	0.618	0.3245	0.3195	0.135	0.115
3/8–24	0.633	0.618	0.385	0.380	0.135	0.115
1/2–20	0.860	0.845	0.510	0.505	0.135	0.115
5/8–11	1.125	1.110	0.635	0.630	0.166	0.146
5/8–16	1.125	1.110	0.635	0.630	0.166	0.146
45/64–16	1.250	1.235	0.713	0.708	0.166	0.146
3/4–16	1.250	1.235	0.760	0.755	0.166	0.146
1–8	1.437	1.422	1.036	1.026	0.281	0.250
1–10	1.437	1.422	1.036	1.026	0.281	0.250
1 1/2–8	1.871	1.851	1.536	1.526	0.343	0.312

Thread[a] Size	*G*		*H*[b]	Plug Gage Pitch Dia.		Ring Gage Pitch Dia.	
	Max	Min		Go	Not Go	Go	Not Go
5/16–24	0.3114	0.3042	0.437[c]	0.2854	0.2902	0.2843	0.2806
3/8–24	0.3739	0.3667	0.562[d]	0.3479	0.3528	0.3468	0.3430
1/2–20	0.4987	0.4906	0.562	0.4675	0.4731	0.4662	0.4619
5/8–11	0.6234	0.6113	0.687	0.5660	0.5732	0.5644	0.5589
5/8–16	0.6236	0.6142	0.687	0.5844	0.5906	0.5830	0.5782
45/64–16	0.7016	0.6922	0.687	0.6625	0.6687	0.6610	0.6561
3/4–16	0.7485	0.7391	0.687	0.7094	0.7159	0.7079	0.7029
1–8	1.000	0.9848	1.000	0.9188	0.9242	0.9188	0.9134
1–10	1.000	0.9872	1.000	0.9350	0.9395	0.9350	0.9305
1 1/2–8	1.500	1.4848	1.000	1.4188	1.4242	1.4188	1.4134

[a] Except for 1–8, 1–10, 1 1/2–8 all threads are now manufactured to the American National Standard Unified Screw Thread System, Internal Class 2B, External Class 2A. Effective date 1976.

[b] Tolerances for dimension *H* are as follows: 0.030 inch for thread sizes 5/16 –24 to 3/4–16, inclusive and 0.125 inch for thread sizes 1–8 to 1 1/2–8, inclusive.

[c] Length for Jacobs 0B5/16 chuck is 0.375 inch, length for 1B5/16 chuck is 0.437 inch.

[d] Length for Jacobs No. 1BS chuck is 0.437 inch.

Usual Chuck Capacities for Different Taper Series Numbers: No. 0 taper, drill diameters, 0–5/32 inch; No. 1, 0–1/4 inch; No. 2, 0–1/2 inch; No. 2 "Short," 0–5/16 inch; No. 3, 0–1/2, 1/8–5/8, 3/16–3/4, or 1/4–13/16 inch; No. 4, 1/8–3/4 inch; No. 5, 3/8–1; No. 6, 0–1/2 inch; No. 33, 0–1/2 inch.

Usual Chuck Capacities for Different Thread Sizes: Size 5/16–24, drill diameters 0–1/4 inch; size 3/8–24, drill diameters 0–3/8, 1/16–3/8, or 5/64–1/2 inch; size 1/2–20, drill diameters 0–1/2, 1/16–3/8, or 5/64–1/2 inch; size 5/8–11, drill diameters 0–1/2 inch; size 5/8–16, drill diameters 0–1/2, 1/8– –5/8, or 3/16–3/4 inch; size 45/64–16, drill diameters 0–1/2 inch; size 3/4–16, drill diameters 0–1/2 or 3/16–3/4.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Essential Dimensions of American National Standard Spindle Noses for Milling Machines *ANSI B5.18-1972 (R1998)*



Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Essential Dimensions of American National Standard Spindle Noses for Milling Machines** *ANSI B5.18-1972 (R1998)*

Size No.	Gage Dia.of Taper *A*	Dia.of Spindle *B*	Pilot Dia. *C*	Clearance Hole for Draw-in Bolt Min. *D*	Minimum Dimension Spindle End to Column *E*	Width of Driving Key *F*	Width of Keyseat *F′*	Maximum Height of Driving Key *G*	Minimum Depth of Keyseat *G′*	Distance fromCenter to Driving Keys *H*	Radius of Bolt Hole Circle *J*	Size of Threads for Bolt Holes UNC-2B *K*	Full Depth of Arbor Hole in Spindle Min. *L*	Depth of Usable Thread for Bolt Hole *M*
30	1.250	2.7493 2.7488	0.692 0.685	0.66	0.50	0.6255 0.6252	0.624 0.625	0.31	0.31	0.660 0.654	1.0625 (Note 1)	0.375–16	2.88	0.62
40	1.750	3.4993 3.4988	1.005 0.997	0.66	0.62	0.6255 0.6252	0.624 0.625	0.31	0.31	0.910 0.904	1.3125 (Note 1)	0.500–13	3.88	0.81
45	2.250	3.9993 3.9988	1.286 1.278	0.78	0.62	0.7505 0.7502	0.749 0.750	0.38	0.38	1.160 1.154	1.500 (Note 1)	0.500–13	4.75	0.81
50	2.750	5.0618 5.0613	1.568 1.559	1.06	0.75	1.0006 1.0002	0.999 1.000	0.50	0.50	1.410 1.404	2.000(Note 2)	0.625–11	5.50	1.00
60	4.250	8.7180 8.7175	2.381 2.371	1.38	1.50	1.0006 1.0002	0.999 1.000	0.50	0.50	2.420 2.414	3.500 (Note 2)	0.750–10	8.62	1.25

All dimensions are given in inches.

Tolerances:

Two-digit decimal dimensions ± 0.010 unless otherwise specified.

A—Taper: Tolerance on rate of taper to be 0.001 inch per foot applied only in direction which decreases rate of taper.

F′—Centrality of keyway with axis of taper 0.002 total at maximum material condition. (0.002 Total indicator variation)

F—Centrality of solid key with axis of taper 0.002 total at maximum material condition. (0.002 Total indicator variation)

Note 1: Holes spaced as shown and located within 0.006 inch diameter of true position.

Note 2: Holes spaced as shown and located within 0.010 inch diameter of true position.

Note 3: Maximum turnout on test plug:
0.0004 at 1 inch projection from gage line.
0.0010 at 12 inch projection from gage line.

Note 4: Squareness of mounting face measured near mounting bolt hole circle.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Essential Dimensions of American National Standard Tool Shanks for Milling Machines *ANSI B5.18-1972 (R1998)*



Size No.	Gage Dia.of Taper *N*	Tap Drill Size for Draw-in Thread *O*	Dia.of Neck *P*	Size of Thread for Draw-in Bolt UNC-2B *M*	Pilot Dia. *R*	Length of Pilot *S*	Minimum Length of Usable Thread *T*	Minimum Depth of Clearance Hole *U*
30	1.250	0.422 0.432	0.66 0.65	0.500–13	0.675 0.670	0.81	1.00	2.00
40	1.750	0.531 0.541	0.94 0.93	0.625–11	0.987 0.980	1.00	1.12	2.25
45	2.250	0.656 0.666	1.19 1.18	0.750–10	1.268 1.260	1.00	1.50	2.75
50	2.750	0.875 0.885	1.50 1.49	1.000–8	1.550 1.540	1.00	1.75	3.50
60	4.250	1.109 1.119	2.28 2.27	1.250–7	2.360 2.350	1.75	2.25	4.25

Size. No.	Distance from Rear of Flange to End of Arbor *V*	Clearance of Flange from Gage Diameter *W*	Tool Shank Centerline to Driving Slot *X*	Width of Driving Slot *Y*	Distance from Gage Line to Bottom of C'bore *Z*	Depth of 60° Center *K*	Diameter of C'bore *L*
30	2.75	0.045 0.075	0.640 0.625	0.635 0.645	2.50	0.05 0.07	0.525 0.530
40	3.75	0.045 0.075	0.890 0.875	0.635 0.645	3.50	0.05 0.07	0.650 0.655
45	4.38	0.105 0.135	1.140 1.125	0.760 0.770	4.06	0.05 0.07	0.775 0.780
50	5.12	0.105 0.135	1.390 1.375	1.010 1.020	4.75	0.05 0.12	1.025 1.030
60	8.25	0.105 0.135	2.400 2.385	1.010 1.020	7.81	0.05 0.12	1.307 1.312

All dimensions are given in inches.

Tolerances: Two digit decimal dimensions ± 0.010 inch unless otherwise specified.

M—Permissible for Class 2B "NoGo" gage to enter five threads before interference.

N—Taper tolerance on rate of taper to be 0.001 inch per foot applied only in direction which increases rate of taper.

Y—Centrality of drive slot with axis of taper shank 0.004 inch at maximum material condition. (0.004 inch total indicator variation)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Draw-in Bolt Ends
ANSI B5.18-1972 (R1998)



Size No.	Length of Small End *A*	Length of Usable Thread at Small End *B*	Length of Usable Thread on Large Diameter *C*	Size of Thread for Large End UNC-2A *M*	Size of Thread for Small End UNC-2A *D*
30	1.06	0.75	0.75	0.500–13	0.375–16
40	1.25	1.00	1.12	0.625–11	0.500–13
45	1.50	1.12	1.25	0.750–10	0.625–11
50	1.50	1.25	1.38	1.000–8	0.625–11
60	1.75	1.37	2.00	1.250–7	1.000–8

All dimensions are given in inches.

Table 4. American National Standard Pilot Lead on Centering Plugs for Flatback Milling Cutters *ANSI B5.18-1972 (R1998)*



Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Essential Dimensions for American National Standard Spindle Nose with Large Flange *ANSI B5.18-1972 (R1998)*



Size No.	Gage Diam. of Taper *A*	Dia. of Spindle Flange *B*	Pilot Dia. *C*	Clearance Hole for Draw-in Bolt Min. *D*	Min. Dim. Spindle End to Column *E*	Width of Driving Key *F*	Height of Driving Key Max. *G*	Depth of Keyseat Min. G_1	Distance from Center to Driving Keys First Position H_1
50A	2.750	8.7180 8.7175	1.568 1.559	1.06	0.75	1.0006 1.0002	0.50	0.50	1.410 1.404

Size No.	Distance from Center to Driving Keys Second Position	Radius of Bolt Hole Circles (See Note 3)		Size of Threads for Bolt Holes UNC-2B		Full Depth of Arbor Hole in Spindle Min.	Depth of Usable Thread for Bolt Holes		Width of Keyseat
		Inner	Outer						
	H_2	J_1	J_2	K_1	K_2	*L*	M_1	M_2	F_1
50A	2.420 2.410	2.000	3.500	0.625–11	0.750–10	5.50	1.00	1.25	0.999 1.000

All dimensions are given in inches.

Tolerances: Two-digit decimal dimensions ± 0.010 unless otherwise specified.

A—Tolerance on rate of taper to be 0.001 inch per foot applied only in direction which decreases rate of taper.

F—Centrality of solid key with axis of taper 0.002 inch total at maximum material condition. (0.002 inch Total indicator variation)

F_1—Centrality of keyseat with axis of taper 0.002 inch total at maximum material condition. (0.002 inch Total indicator variation)

Note 1: Maximum runout on test plug:
0.0004 at 1 inch projection from gage line.
0.0010 at 12 inch projection from gage line.

Note 2: Squareness of mounting face measured near mounting bolt hole circle.

Note 3: Holes located as shown and within 0.010 inch diameter of true position.

Copyright 2004, Industrial Press, Inc., New York, NY

Collets

Collets for Lathes, Mills, Grinders, and Fixtures



Collet Styles

Collets for Lathes, Mills, Grinders, and Fixtures

		Dimensions			Max. Capacity (inches)		
Collet	Style	Bearing Diam., A	Length, B	Thread, C	Round	Hex	Square
1A	1	0.650	2.563	0.640 × 26 RH	0.500	0.438	0.344
1AM	1	1.125	3.906	1.118 × 24 RH	1.000	0.875	0.719
1B	2	0.437	1.750	0.312 × 30 RH	0.313	0.219	0.188
1C	1	0.335	1.438	0.322 × 40 RH	0.250	0.219	0.172
1J	1	1.250	3.000	1.238 × 20 RH	1.063	0.875	0.750
1K	3	1.250	2.813	None	1.000	0.875	0.719
2A	1	0.860	3.313	0.850 × 20 RH	0.688	0.594	0.469
2AB	2	0.750	2.563	0.500 × 20 RH	0.625	0.484	0.391
2AM	1	0.629	3.188	0.622 × 24 RH	0.500	0.438	0.344
2B	2	0.590	2.031	0.437 × 26 RH	0.500	0.438	0.344
2C	1	0.450	1.812	0.442 × 30 RH	0.344	0.594	0.234
2H	1	0.826	4.250	0.799 × 20 RH	0.625	0.531	1.000
2J	1	1.625	3.250	1.611 × 18 RH	1.375	1.188	0.438
2L	1	0.950	3.000	0.938 × 20 RH	0.750	0.656	1.000
2M	4	2 Morse	2.875	0.375 × 16 RH	0.500	0.438	0.344
2NS	1	0.324	1.562	0.318 × 40 RH	0.250	0.203	0.172
2OS	1	0.299	1.250	0.263 × 40 RH	0.188	0.156	0.125
2S	1	0.750	3.234	0.745 × 18 RH	0.563	0.484	0.391
2VB	2	0.595	2.438	0.437 × 26 RH	0.500	0.438	0.344
3AM	1	0.750	3.188	0.742 × 24 RH	0.625	0.531	0.438
3AT	1	0.687	2.313	0.637 × 26 RH	0.500	0.438	0.344

Copyright 2004, Industrial Press, Inc., New York, NY

Collets for Lathes, Mills, Grinders, and Fixtures *(Continued)*

Collet	Style	Dimensions			Max. Capacity (inches)		
		Bearing Diam., A	Length, B	Thread, C	Round	Hex	Square
3B	2	0.875	3.438	0.625 × 16 RH	0.750	0.641	0.531
3C	1	0.650	2.688	0.640 × 26 RH	0.500	0.438	0.344
3H	1	1.125	4.438	1.050 × 20 RH	0.875	0.750	0.625
3J	1	2.000	3.750	1.988 × 20 RH	1.750	1.500	1.250
3NS	1	0.687	2.875	0.647 × 20 RH	0.500	0.438	0.344
3OS	1	0.589	2.094	0.518 × 26 RH	0.375	0.313	0.266
3PN	1	0.650	2.063	0.645 × 24 RH	0.500	0.438	0.344
3PO	1	0.599	2.063	0.500 × 24 RH	0.375	0.313	0.266
3S	1	1.000	4.594	0.995 × 20 RH	0.750	0.656	0.531
3SC	1	0.350	1.578	0.293 × 36 RH	0.188	0.156	0.125
3SS	1	0.589	2.125	0.515 × 26 RH	0.375	0.313	0.266
4C	1	0.950	3.000	0.938 × 20 RH	0.750	0.656	0.531
4NS	1	0.826	3.500	0.800 × 20 RH	0.625	0.531	0.438
4OS	1	0.750	2.781	0.660 × 20 RH	0.500	0.438	0.344
4PN	1	1.000	2.906	0.995 × 16 RH	0.750	0.656	0.531
4S	1	0.998	3.250	0.982 × 20 RH	0.750	0.656	0.531
5C	1	1.250	3.281	1.238 × 20 RH[a]	1.063	0.906	0.750
5M	5	1.438	3.438	1.238 × 20 RH	0.875	0.750	0.625
5NS	1	1.062	4.219	1.050 × 20 RH	0.875	0.750	0.625
5OS	1	3.500	3.406	0.937 × 18 RH	0.750	0.641	0.516
5P	1	0.812	3.687	0.807 × 24 RH	0.625	0.531	0.438
5PN	1	1.312	3.406	1.307 × 16 RH	1.000	0.875	0.719
5SC	1	0.600	2.438	0.500 × 26 RH	0.375	0.328	0.266
5ST	1	1.250	3.281	1.238 × 20 RH	1.063	0.906	0.750
5V	1	0.850	3.875	0.775 × 18 RH	0.563	0.484	0.391
6H	1	1.375	4.750	1.300 × 10 RH	1.125	0.969	0.797
6K	1	0.842	3.000	0.762 × 26 RH	0.625	0.531	0.438
6L	1	1.250	4.438	1.178 × 20 RH	1.000	0.875	0.719
6NS	1	1.312	5.906	1.234 × 14 RH	1.000	0.859	0.703
6R	1	1.375	4.938	1.300 × 20 RH	1.125	0.969	0.781
7B	4	7 B&S	3.125	0.375 × 16 RH	0.500	0.406	0.344
7 B&S	4	7 B&S	2.875	0.375 × 16 RH	0.500	0.406	0.344
7P	1	1.125	4.750	1.120 × 20 RH	0.875	0.750	0.625
7R	6	1.062	3.500	None	0.875	0.750	0.625
8H	1	1.500	4.750	1.425 × 20 RH	1.250	1.063	0.875
8ST	1	2.375	5.906	2.354 × 12 RH	2.125	1.844	1.500
8WN	1	1.250	3.875	1.245 × 16 RH	1.000	0.875	0.719
9B	4	9 B&S	4.125	0.500 × 13 RH	0.750	0.641	0.531
10L	1	1.562	5.500	1.490 × 18 RH	1.250	1.063	0.875
10P	1	1.500	4.750	1.495 × 20 RH	1.250	1.063	0.875
16C	1	1.889	4.516	1.875 × 1.75 mm RH[b]	1.625	1.406	1.141
20W	1	0.787	2.719	0.775 × 6–1 cm	0.563	0.484	0.391
22J	1	2.562	4.000	2.550 × 18 RH	2.250	1.938	1.563
32S	1	0.703	2.563	0.690 × 24 RH	0.500	0.438	0.344
35J	1	3.875	5.000	3.861 × 18 RH	3.500	3.000	2.438
42S	1	1.250	3.688	1.236 × 20 RH	1.000	0.875	0.719
50V	8	1.250	4.000	1.125 × 24 RH	0.938	0.813	0.656
52SC	1	0.800	3.688	0.795 × 20 RH	0.625	0.531	0.438
115	1	1.344	3.500	1.307 × 20 LH	1.125	0.969	0.797

Copyright 2004, Industrial Press, Inc., New York, NY

Collets for Lathes, Mills, Grinders, and Fixtures *(Continued)*

Collet	Style	Dimensions			Max. Capacity (inches)		
		Bearing Diam., A	Length, B	Thread, C	Round	Hex	Square
215	1	2.030	4.750	1.990 × 18 LH	1.750	1.500	1.219
315	1	3.687	5.500	3.622 × 16 LH	3.250	2.813	2.250
B3	7	0.650	3.031	0.437 × 20 RH	0.500	0.438	0.344
D5	7	0.780	3.031	0.500 × 20 RH	0.625	0.531	0.438
GTM	7	0.625	2.437	0.437 × 20 RH	0.500	0.438	0.344
J&L	9	0.999	4.375	None	0.750	0.641	0.516
JC	8	1.360	4.000	None	1.188	1.000	0.813
LB	10	0.687	2.000	None	0.500	0.438	0.344
RO	11	1.250	2.938	0.875 × 16 RH	1.125	0.969	0.781
RO	12	1.250	4.437	0.875 × 16 RH	0.800	0.688	0.563
RO	12	1.250	4.437	0.875 × 16 RH	1.125	0.969	0.781
RO	11	1.250	2.938	0.875 × 16 RH	0.800	0.688	0.563
R8	7	0.950	4.000	0.437 × 20 RH	0.750	0.641	0.531

[a] Internal stop thread is 1.041 × 24 RH.
[b] Internal stop thread is 1.687 × 20 RH.
Dimensions in inches unless otherwise noted. Courtesy of Hardinge Brothers, Inc.

DIN 6388, Type B, and DIN 6499, ER Type Collets



ER Type



Type B

Collet Standard	Type	Dimensions			
		B (mm)	*L* (mm)	*A* (mm)	*C*
Type B, DIN 6388	16	25.50	40	4.5–16	…
	20	29.80	45	5.5–20	…
	25	35.05	52	5.5–25	…
	32	43.70	60	9.5–32	…
ER Type, DIN 6499	ERA8	8.50	13.5	0.5–5	8°
	ERA11	11.50	18	0.5–7	8°
	ERA16	17	27	0.5–10	8°
	ERA20	21	31	0.5–13	8°
	ERA25	26	35	0.5–16	8°
	ERA32	33	40	2–20	8°
	ERA40	41	46	3–26	8°
		41	39	26–30	8°
	ERA50	52	60	5–34	8°

Copyright 2004, Industrial Press, Inc., New York, NY

ARBORS, CHUCKS, AND SPINDLES

Portable Tool Spindles

Circular Saw Arbors.— ANSI Standard B107.4-1982 "Driving and Spindle Ends for Portable Hand, Air, and Air Electric Tools" calls for a round arbor of 5/8-inch diameter for nominal saw blade diameters of 6 to 8.5 inches, inclusive, and a 3/4-inch diameter round arbor for saw blade diameters of 9 to 12 inches, inclusive.

Spindles for Geared Chucks.— Recommended threaded and tapered spindles for portable tool geared chucks of various sizes are as given in the following table:

Recommended Spindle Sizes

Chuck Sizes, Inch	Recommended Spindles	
	Threaded	Taper[a]
3/16 and 1/4 Light	3/8–24	1
1/4 and 5/16 Medium	3/8–24 or 1/2–20	2 Short
3/8 Light	3/8–24 or 1/2–20	2
3/8 Medium	1/2–20 or 5/8–16	2
1/2 Light	1/2–20 or 5/8–16	33
1/2 Medium	5/8–16 or 3/4–16	6
5/8 and 3/4 Medium	5/8–16 or 3/4–16	3

[a] Jacobs number.

Vertical and Angle Portable Tool Grinder Spindles.— The 5/8–11 spindle with a length of 1 1/8 inches shown on page 950 is designed to permit the use of a jam nut with threaded cup wheels. When a revolving guard is used, the length of the spindle is measured from the wheel bearing surface of the guard. For unthreaded wheels with a 7/8-inch hole, a safety sleeve nut is recommended. The unthreaded wheel with 5/8-inch hole is not recommended because a jam nut alone may not resist the inertia effect when motor power is cut off.

Straight Grinding Wheel Spindles for Portable Tools.— Portable grinders with pneumatic or induction electric motors should be designed for the use of organic bond wheels rated 9500 feet per minute. Light-duty electric grinders may be designed for vitrified wheels rated 6500 feet per minute. Recommended maximum sizes of wheels of both types are as given in the following table:

Recommended Maximum Grinding Wheel Sizes for Portable Tools

Spindle Size	Maximum Wheel Dimensions			
	9500 fpm		6500 fpm	
	Diameter *D*	Thickness *T*	Diameter *D*	Thickness *T*
3/8–24 × 1 1/8	2 1/2	1/2	4	1/2
1/2–13 × 1 3/4	4	3/4	5	3/4
5/8–11 × 2 1/8	8	1	8	1
5/8–11 × 3 1/8	6	2	…	…
5/8–11 × 3 1/8	8	1 1/2	…	…
3/4–10 × 3 1/4	8	2	…	…

Minimum *T* with the first three spindles is about 1/8 inch to accommodate cutting off wheels. Flanges are assumed to be according to ANSI B7.1 and threads to ANSI B1.1.

Copyright 2004, Industrial Press, Inc., New York, NY

American Standard Square Drives for Portable Air and Electric Tools *ASA B5.38-1958*



DESIGN A



DESIGN B

Drive Size	Desig n.	Male End A_M Max.	A_M Min.	B_M Max.	C_M Max.	C_M Min.	D_M Max.	D_M Min.	E_M Min.	F_M Max.	R_M Max.
1/4	A	0.252	0.247	0.330	0.312	0.265	0.165	0.153	…	0.078	0.015
3/8	A	0.377	0.372	0.500	0.438	0.406	0.227	0.215	…	0.156	0.031
1/2	A	0.502	0.497	0.665	0.625	0.531	0.321	0.309	…	0.187	0.031
5/8	A	0.627	0.622	0.834	0.656	0.594	0.321	0.309	…	0.187	0.047
3/4	B	0.752	0.747	1.000	0.938	0.750	0.415	0.403	0.216	…	0.047
1	B	1.002	0.997	1.340	1.125	1.000	0.602	0.590	0.234	…	0.063
1 1/2	B	1.503	1.498	1.968	1.625	1.562	0.653	0.641	0.310	…	0.094



DESIGN A



DESIGN B

Drive Size	Design	Female End A_F Max.	A_F Min.	B_F Min.	D_F Max.	D_F Min.	E_F Min.	R_F Max.
1/4	A	0.258	0.253	0.335	0.159	0.147	0.090	…
3/8	A	0.383	0.378	0.505	0.221	0.209	0.170	…
1/2	A	0.508	0.503	0.670	0.315	0.303	0.201	…
5/8	A	0.633	0.628	0.839	0.315	0.303	0.201	…
3/4	B	0.758	0.753	1.005	0.409	0.397	0.216	0.047
1	B	1.009	1.004	1.350	0.596	0.584	0.234	0.062
1 1/2	B	1.510	1.505	1.983	0.647	0.635	0.310	0.125

All dimensions in inches.

Incorporating fillet radius (R_M) at shoulder of male tang precludes use of minimum diameter cross-hole in socket (E_F), unless female drive end is chamfered (shown as optional).

If female drive end is not chamfered, socket cross-hole diameter (E_F) is increased to compensate for fillet radius R_M, max.

Minimum clearance across flats male to female is 0.001 inch through 3/4-inch size; 0.002 inch in 1- and 1 1/2-inch sizes. For impact wrenches A_M should be held as close to maximum as practical.

C_F, min. for both designs A and B should be equal to C_M, max.

Copyright 2004, Industrial Press, Inc., New York, NY

American Standard Threaded and Tapered Spindles for Portable Air and Electric Tools *ASA B5.38-1958*



Threaded Spindle **Taper Spindle (Jacobs)** **Master Plug Gage**

Nom. Dia. and Thd.	Pitch Dia. Max.	Pitch Dia. Min.	*R*	*L*	No.[a]	D_M	L_M	E_G	D_G	L_G	Taper per Foot[b]
3/8–24	0.3479	0.3455	1/16	9/16[c]	1	0.335-0.333	0.656	0.38400	0.33341	0.65625	0.92508
1/2–20	0.4675	0.4649	1/16	9/16	2S[d]	0.490-0.488	0.750	0.54880	0.48764	0.7500	0.97861
					2	0.490-0.488	0.875	0.55900	0.48764	0.87500	0.97861
5/8–16	0.5844	0.5812	3/32	11/16	33	0.563-0.561	1.000	0.62401	0.56051	1.000	0.76194
					6	0.626-0.624	1.000	0.67600	0.62409	1.000	0.62292
3/4–16	0.7094	0.7062	3/32	11/16	3	0.748-0.746	1.219	0.81100	0.74610	1.21875	0.63898

[a] Jacobs taper number.

[b] Calculated from E_G, D_G, L_G for the master plug gage.

[c] Also 7/16 inch.

[d] 2S stands for 2 Short.

All dimensions in inches. Threads are per inch and right-hand. *Tolerances:* On *R*, plus or minus 1/64 inch; on *L*, plus 0.000, minus 0.030 inch.

American Standard Abrasion Tool Spindles for Portable Air and Electric Tools *ASA B5.38-1958*

Sanders and Polishers



Vertical and Angle Grinders



With Revolving Cup Guard Stationary Guard

Copyright 2004, Industrial Press, Inc., New York, NY

American Standard Abrasion Tool Spindles for Portable Air and Electric Tools *ASA B5.38-1958* ***(Continued)***

Straight Wheel Grinders			Cone Wheel Grinders	
				
H	*R*	*L*	*D*	*L*
3/8–24 UNF-2A	1/4	1 1/8	3/8–24 UNF-2A	9/16
1/2–13 UNC-2A	3/8	1 3/4	1/2–13 UNC-2A	11/16
5/8–11 UNC-2A	1/2	2 1/8	5/8–11 UNC-2A	15/16
5/8–11 UNC-2A	1	3 1/8		
3/4–10 UNC-2A	1	3 1/4		

All dimensions in inches. Threads are right-hand.

American Standard Hexagonal Chucks and Shanks for Portable Air and Electric Tools *ASA B5.38-1958*



Nominal Hexagon	*H* Min.	*H* Max.	*B*	*L* Max.	Nominal Hexagon	*H* Min.	*H* Max.	*B*	*L* Max.
1/4	0.253	0.255	3/8	15/16	5/8	0.630	0.632	11/32	1 5/8
5/16	0.314	0.316	13/64	1	3/4	0.755	0.758	11/32	1 7/8
7/16	0.442	0.444	17/64	1 1/8	…	…	…	…	…

Shanks



All dimensions in inches. Tolerances on *B* is plus or minus 0.005 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Mounted Wheels and Mounted Points

These wheels and points are used in hard-to-get-at places and are available with a vitrified bond. The wheels are available with aluminum oxide or silicon carbide abrasive grains. The aluminum oxide wheels are used to grind tough and tempered die steels and the silicon carbide wheels, cast iron, chilled iron, bronze, and other non-ferrous metals.

The illustrations on pages 952 and 953 give the standard shapes of mounted wheels and points as published by the Grinding Wheel Institute. A note about the maximum operating speed for these wheels is given at the bottom of the first page of illustrations. Metric sizes are given on page 954.



Fig. 1a. Standard Shapes and Sizes of Mounted Wheels and Points ANSI B74.2-1982

See Table 1 for inch sizes of Group W shapes, and for metric sizes for all shapes

The maximum speeds of mounted vitrified wheels and points of average grade range from about 38,000 to 152,000 rpm for diameters of 1 inch down to ¼ inch. However, the safe operating speed usually is limited by the critical speed (speed at which vibration or whip tends to become excessive) which varies according to wheel or point dimensions, spindle diameter, and overhang.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1b. Standard Shapes and Sizes of Mounted Wheels and Points ANSI B74.2-1982

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Shapes and Sizes of Mounted Wheels and Points *ANSI B74.2-1982*

Abrasive Shape No.[a]	Abrasive Shape Size		Abrasive Shape No.[a]	Abrasive Shape Size	
	Diameter mm	Thickness mm		Diameter mm	Thickness mm
A 1	20	65	A 24	6	20
A 3	22	70	A 25	25	…
A 4	30	30	A 26	16	…
A 5	20	28	A 31	35	26
A 11	21	45	A 32	25	20
A 12	18	30	A 34	38	10
A 13	25	25	A 35	25	10
A 14	18	22	A 36	40	10
A 15	6	25	A 37	30	6
A 21	25	25	A 38	25	25
A 23	20	25	A 39	20	20
B 41	16	16	B 97	3	10
B 42	13	20	B 101	16	18
B 43	6	8	B 103	16	5
B 44	5.6	10	B 104	8	10
B 51	11	20	B 111	11	18
B 52	10	20	B 112	10	13
B 53	8	16	B 121	13	…
B 61	20	8	B 122	10	…
B 62	13	10	B 123	5	…
B 71	16	3	B 124	3	…
B 81	20	5	B 131	13	13
B 91	13	16	B 132	10	13
B 92	6	6	B 133	10	10
B 96	3	6	B 135	6	13

Abrasive Shape No.[a]	Abrasive Shape Size				Abrasive Shape No.[a]	Abrasive Shape Size			
	D mm	*T* mm	*D* inch	*T* inch		*D* mm	*T* mm	*D* inch	*T* inch
W 144	3	6	1/8	1/4	W 196	16	26	5/8	1
W 145	3	10	1/8	3/8	W 197	16	50	5/8	2
W 146	3	13	1/8	1/2	W 200	20	3	3/4	1/8
W 152	5	6	3/16	1/4	W 201	20	6	3/4	1/4
W 153	5	10	3/16	3/8	W 202	20	10	3/4	3/8
W 154	5	13	3/16	1/2	W 203	20	13	3/4	1/2
W 158	6	3	1/4	1/8	W 204	20	20	3/4	3/4
W 160	6	6	1/4	1/4	W 205	20	25	3/4	1
W 162	6	10	1/4	3/8	W 207	20	40	3/4	1 1/2
W 163	6	13	1/4	1/2	W 208	20	50	3/4	2
W 164	6	20	1/4	3/4	W 215	25	3	1	1/8
W 174	10	6	3/8	1/4	W 216	25	6	1	1/4
W 175	10	10	3/8	3/8	W 217	25	10	1	3/8
W 176	10	13	3/8	1/2	W 218	25	13	1	1/2
W 177	10	20	3/8	3/4	W 220	25	25	1	1
W 178	10	25	3/8	1	W 221	25	40	1	1 1/2
W 179	10	30	3/8	1 1/4	W 222	25	50	1	2
W 181	13	1.5	1/2	1/16	W 225	30	6	1 1/4	1/4
W 182	13	3	1/2	1/8	W 226	30	10	1 1/4	3/8
W 183	13	6	1/2	1/4	W 228	30	20	1 1/4	3/4
W 184	13	10	1/2	3/8	W 230	30	30	1 1/4	1 1/4
W 185	13	13	1/2	1/2	W 232	30	50	1 1/4	2
W 186	13	20	1/2	3/4	W 235	40	6	1 1/2	1/4
W 187	13	25	1/2	1	W 236	40	13	1 1/2	1/2
W 188	13	40	1/2	1 1/2	W 237	40	25	1 1/2	1
W 189	13	50	1/2	2	W 238	40	40	1 1/2	1 1/2
W 195	16	20	5/8	3/4	W 242	50	25	2	1

[a] See shape diagrams in Figs. 1a and 1b on pages 952 and 953.

Copyright 2004, Industrial Press, Inc., New York, NY

BROACHES AND BROACHING

The Broaching Process

The broaching process may be applied in machining holes or other internal surfaces and also to many flat or other external surfaces. Internal broaching is applied in forming either symmetrical or irregular holes, grooves, or slots in machine parts, especially when the size or shape of the opening, or its length in proportion to diameter or width, make other machining processes impracticable. Broaching originally was utilized for such work as cutting keyways, machining round holes into square, hexagonal, or other shapes, forming splined holes, and for a large variety of other internal operations. The development of broaching machines and broaches finally resulted in extensive application of the process to external, flat, and other surfaces. Most external or surface broaching is done on machines of vertical design, but horizontal machines are also used for some classes of work. The broaching process is very rapid, accurate, and it leaves a finish of good quality. It is employed extensively in automotive and other plants where duplicate parts must be produced in large quantities and for dimensions within small tolerances.

Types of Broaches.— A number of typical broaches and the operations for which they are intended are shown by the diagrams, Fig. 1. Broach A produces a round-cornered, square hole. Prior to broaching square holes, it is usually the practice to drill a round hole having a diameter *d* somewhat larger than the width of the square. Hence, the sides are not completely finished, but this unfinished part is not objectionable in most cases. In fact, this clearance space is an advantage during the broaching operation in that it serves as a channel for the broaching lubricant; moreover, the broach has less metal to remove. Broach *B* is for finishing round holes. Broaching is superior to reaming for some classes of work, because the broach will hold its size for a much longer period, thus insuring greater accuracy. Broaches *C* and *D* are for cutting single and double keyways, respectively. Broach *C* is of rectangular section and, when in use, slides through a guiding bushing which is inserted in the hole. Broach *E* is for forming four integral splines in a hub. The broach at *F* is for producing hexagonal holes. Rectangular holes are finished by broach *G*. The teeth on the sides of this broach are inclined in opposite directions, which has the following advantages: The broach is stronger than it would be if the teeth were opposite and parallel to each other; thin work cannot drop between the inclined teeth, as it tends to do when the teeth are at right angles, because at least two teeth are always cutting; the inclination in opposite directions neutralizes the lateral thrust. The teeth on the edges are staggered, the teeth on one side being midway between the teeth on the other edge, as shown by the dotted line. A double cut broach is shown at *H*. This type is for finishing, simultaneously, both sides *f* of a slot, and for similar work. Broach *I* is the style used for forming the teeth in internal gears. It is practically a series of gear-shaped cutters, the outside diameters of which gradually increase toward the finishing end of the broach, Broach *J* is for round holes but differs from style *B* in that it has a continuous helical cutting edge. Some prefer this form because it gives a shearing cut. Broach *K* is for cutting a series of helical grooves in a hub or bushing. In helical broaching, either the work or the broach is rotated to form the helical grooves as the broach is pulled through.

In addition to the typical broaches shown in Fig. 1, many special designs are now in use for performing more complex operations. Two surfaces on opposite sides of a casting or forging are sometimes machined simultaneously by twin broaches and, in other cases, three or four broaches are drawn through a part at the same time, for finishing as many duplicate holes or surfaces. Notable developments have been made in the design of broaches for external or "surface" broaching.

Burnishing Broach: This is a broach having teeth or projections which are rounded on the top instead of being provided with a cutting edge, as in the ordinary type of broach. The teeth are highly polished, the tool being used for broaching bearings and for operations on

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Types of Broaches

other classes of work where the metal is relatively soft. The tool compresses the metal, thus making the surface hard and smooth. The amount of metal that can be displaced by a smooth-toothed burnishing broach is about the same as that removed by reaming. Such broaches are primarily intended for use on babbitt, white metal, and brass, but may also be satisfactorily used for producing a glazed surface on cast iron. This type of broach is also used when it is only required to accurately size a hole.

Pitch of Broach Teeth.— The pitch of broach teeth depends upon the depth of cut or chip thickness, length of cut, the cutting force required and power of the broaching machine. In the pitch formulas which follow

L = length, in inches, of layer to be removed by broaching

d = depth of cut per tooth as shown by Table 1 (For internal broaches, d = depth of cut as measured on one side of broach or one-half difference in diameters of successive teeth in case of a round broach)

F = a factor. (For brittle types of material, $F = 3$ or 4 for roughing teeth, and 6 for finishing teeth. For ductile types of material, $F = 4$ to 7 for roughing teeth and 8 for finishing teeth.)

b = width of inches, of layer to be removed by broaching

P = pressure required in tons per square inch, of an area equal to depth of cut times width of cut, in inches (Table 2)

T = usable capacity, in tons, of broaching machine = 70% of maximum tonnage

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Designing Data for Surface Broaches

Material to be Broached	Depth of Cut per Tooth, Inch		Face Angle or Rake, Degrees	Clearance Angle, Degrees	
	Roughing[a]	Finishing		Roughing	Finishing
Steel, High Tensile Strength	0.0015–0.002	0.0005	10–12	1.5–3	0.5–1
Steel, Medium Tensile Strength	0.0025–0.005	0.0005	14–18	1.5–3	0.5–1
Cast Steel	0.0025–0.005	0.0005	10	1.53	0.5
Malleable Iron	0.0025–0.005	0.0005	7	1.5–3	0.5
Cast Iron, Soft	0.006 –0.010	0.0005	10–15	1.5–3	0.5
Cast Iron, Hard	0.003 –0.005	0.0005	5	1.5–3	0.5
Zinc Die Castings	0.005 –0.010	0.0010	12[b]	5	2
Cast Bronze	0.010 –0.025	0.0005	8	0	0
Wrought Aluminum Alloys	0.005 –0.010	0.0010	15[b]	3	1
Cast Aluminum Alloys	0.005 –0.010	0.0010	12[b]	3	1
Magnesium Die Castings	0.010 –0.015	0.0010	20[b]	3	1

[a] The lower depth-of-cut values for roughing are recommended when work is not very rigid, the tolerance is small, a good finish is required, or length of cut is comparatively short.

[b] In broaching these materials, smooth surfaces for tooth and chip spaces are especially recommended.

Table 2. Broaching Pressure *P* for Use in Pitch Formula (2)

Material to be Broached	Depth *d* of Cut per Tooth, Inch					Pressure *P*, Side-cutting Broaches
	0.024	0.010	0.004	0.002	0.001	
	Pressure *P* in Tons per Square Inch					
Steel, High Ten. Strength	…	…	…	250	312	200-.004″cut
Steel, Med. Ten. Strength	…	…	158	185	243	143-.006″cut
Cast Steel	…	…	128	158	…	115-.006″ cut
Malleable Iron	…	…	108	128	…	100-.006″ cut
Cast Iron	…	115	115	143	…	115-.020″ cut
Cast Brass	…	50	50	…	…	.....
Brass, Hot Pressed	…	85	85	…	…	.....
Zinc Die Castings	…	70	70	…	…	.....
Cast Bronze	35	35	…	…	…	.....
Wrought Aluminum	…	70	70	…	…	.....
Cast Aluminum	…	85	85	…	…	.....
Magnesium Alloy	35	35	…	…	…	.....

The minimum pitch shown by Formula (1) is based upon the receiving capacity of the chip space. The minimum, however, should not be less than 0.2 inch unless a smaller pitch is required for exceptionally short cuts to provide at least two teeth in contact simultaneously, with the part being broached. A reduction below 0.2 inch is seldom required in surface broaching but it may be necessary in connection with internal broaching.

$$\text{Minimum pitch} = 3\sqrt{LdF} \qquad (1)$$

Whether the minimum pitch may be used or not depends upon the power of the available machine. The factor *F* in the formula provides for the increase in volume as the material is broached into chips. If a broach has adjustable inserts for the finishing teeth, the pitch of the finishing teeth may be smaller than the pitch of the roughing teeth because of the smaller depth *d* of the cut. The higher value of *F* for finishing teeth prevents the pitch from becoming too small, so that the spirally curled chips will not be crowded into too small a space.

Copyright 2004, Industrial Press, Inc., New York, NY

The pitch of the roughing and finishing teeth should be equal for broaches without separate inserts (notwithstanding the different values of d and F) so that some of the finishing teeth may be ground into roughing teeth after wear makes this necessary.

$$\text{Allowable pitch} = \frac{dLbP}{T} \quad (2)$$

If the pitch obtained by Formula (2) is larger than the minimum obtained by Formula (1), this larger value should be used because it is based upon the usable power of the machine. As the notation indicates, 70 per cent of the maximum tonnage T is taken as the usable capacity. The 30 per cent reduction is to provide a margin for the increase in broaching load resulting from the gradual dulling of the cutting edges. The procedure in calculating both minimum and allowable pitches will be illustrated by an example.

Example: Determine pitch of broach for cast iron when $L = 9$ inches; $d = 0.004$; and $F = 4$.

$$\text{Minimum pitch} = 3\sqrt{9 \times 0.004 \times 4} = 1.14$$

Next, apply Formula (2). Assume that $b = 3$ and $T = 10$; for cast iron and depth d of 0.004, $P = 115$ (Table 2). Then,

$$\text{Allowable pitch} = \frac{0.004 \times 9 \times 3 \times 115}{10} = 1.24$$

This pitch is safely above the minimum. If in this case the usable tonnage of an available machine were, say, 8 tons instead of 10 tons, the pitch as shown by Formula (2) might be increased to about 1.5 inches, thus reducing the number of teeth cutting simultaneously and, consequently, the load on the machine; or the cut per tooth might be reduced instead of increasing the pitch, especially if only a few teeth are in cutting contact, as might be the case with a short length of cut. If the usable tonnage in the preceding example were, say, 15, then a pitch of 0.84 would be obtained by Formula (2); hence the pitch in this case should not be less than the minimum of approximately 1.14 inches.

Depth of Cut per Tooth.— The term "depth of cut" as applied to surface or external broaches means the difference in the heights of successive teeth. This term, as applied to internal broaches for round, hexagonal or other holes, may indicate the total increase in the diameter of successive teeth; however, to avoid confusion, the term as here used means in all cases and regardless of the type of broach, the depth of cut as measured on one side.

In broaching free cutting steel, the Broaching Tool Institute recommends 0.003 to 0.006 inch depth of cut for surface broaching; 0.002 to 0.003 inch for multispline broaching; and 0.0007 to 0.0015 inch for round hole broaching. The accompanying table contains data from a German source and applies specifically to surface broaches. All data relating to depth of cut are intended as a general guide only. While depth of cut is based primarily upon the machinability of the material, some reduction from the depth thus established may be required particularly when the work supporting fixture in surface broaching is not sufficiently rigid to resist the thrust from the broaching operation. In some cases, the pitch and cutting length may be increased to reduce the thrust force. Another possible remedy in surface broaching certain classes of work is to use a side-cutting broach instead of the ordinary depth cutting type. A broach designed for side cutting takes relatively deep narrow cuts which extend nearly to the full depth required. The side cutting section is followed by teeth arranged for depth cutting to obtain the required size and surface finish on the work. In general, small tolerances in surface broaching require a reduced cut per tooth to minimize work deflection resulting from the pressure of the cut. See *Cutting Speed for Broaching* starting on page 1074 for broaching speeds.

Copyright 2004, Industrial Press, Inc., New York, NY



Terms Commonly Used in Broach Design

Face Angle or Rake.— The face angle (see diagram) of broach teeth affects the chip flow and varies considerably for different materials. While there are some variations in practice, even for the same material, the angles given in the accompanying table are believed to represent commonly used values. Some broach designers increase the rake angle for finishing teeth in order to improve the finish on the work.

Clearance Angle.— The clearance angle (see illustration) for roughing steel varies from 1.5 to 3 degrees and for finishing steel from 0.5 to 1 degree. Some recommend the same clearance angles for cast iron and others, larger clearance angles varying from 2 to 4 or 5 degrees. Additional data will be found in Table 1.

Land Width.— The width of the land usually is about 0.25 × pitch. It varies, however, from about one-fourth to one-third of the pitch. The land width is selected so as to obtain the proper balance between tooth strength and chip space.

Depth of Broach Teeth.— The tooth depth as established experimentally and on the basis of experience, usually varies from about 0.37 to 0.40 of the pitch. This depth is measured radially from the cutting edge to the bottom of the tooth fillet.

Radius of Tooth Fillet.— The "gullet" or bottom of the chip space between the teeth should have a rounded fillet to strengthen the broach, facilitate curling of the chips, and safeguard against cracking in connection with the hardening operation. One rule is to make the radius equal to one-fourth the pitch. Another is to make it equal 0.4 to 0.6 the tooth depth. A third method preferred by some broach designers is to make the radius equal one-third of the sum obtained by adding together the land width, one-half the tooth depth, and one-fourth of the pitch.

Total Length of Broach.— After the depth of cut per tooth has been determined, the total amount of material to be removed by a broach is divided by this decimal to ascertain the number of cutting teeth required. This number of teeth multiplied by the pitch gives the length of the active portion of the broach. By adding to this dimension the distance over three or four straight teeth, the length of a pilot to be provided at the finishing end of the broach, and the length of a shank which must project through the work and the faceplate of the machine to the draw-head, the overall length of the broach is found. This calculated length is often greater than the stroke of the machine, or greater than is practical for a broach of the diameter required. In such cases, a set of broaches must be used.

Chip Breakers.— The teeth of broaches frequently have rounded chip-breaking grooves located at intervals along the cutting edges. These grooves break up wide curling chips and prevent them from clogging the chip spaces, thus reducing the cutting pressure and strain on the broach. These chip-breaking grooves are on the roughing teeth only. They are staggered and applied to both round and flat or surface broaches. The grooves are formed by a round edged grinding wheel and usually vary in width from about $\frac{1}{32}$ to $\frac{3}{32}$ inch depending upon the size of broach. The more ductile the material, the wider the chip breaker grooves should be and the smaller the distance between them. Narrow slotting broaches may have the right- and left-hand corners of alternate teeth beveled to obtain chip-breaking action.

Copyright 2004, Industrial Press, Inc., New York, NY

Shear Angle.— The teeth of surface broaches ordinarily are inclined so they are not at right angles to the broaching movement. The object of this inclination is to obtain a shearing cut which results in smoother cutting action and an improvement in surface finish. The shearing cut also tends to eliminate troublesome vibration. Shear angles for surface broaches are not suitable for broaching slots or any profiles that resist the outward movement of the chips. When the teeth are inclined, the fixture should be designed to resist the resulting thrusts unless it is practicable to incline the teeth of right- and left-hand sections in opposite directions to neutralize the thrust. The shear angle usually varies from 10 to 25 degrees.

Types of Broaching Machines.— Broaching machines may be divided into horizontal and vertical designs, and they may be classified further according to the method of operation, as, for example, whether a broach in a vertical machine is pulled up or pulled down in forcing it through the work. Horizontal machines usually pull the broach through the work in internal broaching but short rigid broaches may be pushed through. External surface broaching is also done on some machines of horizontal design, but usually vertical machines are employed for flat or other external broaching. Although parts usually are broached by traversing the broach itself, some machines are designed to hold the broach or broaches stationary during the actual broaching operation. This principle has been applied both to internal and surface broaching.

Vertical Duplex Type: The vertical duplex type of surface broaching machine has two slides or rams which move in opposite directions and operate alternately. While the broach connected to one slide is moving downward on the cutting stroke, the other broach and slide is returning to the starting position, and this returning time is utilized for reloading the fixture on that side; consequently, the broaching operation is practically continuous. Each ram or slide may be equipped to perform a separate operation on the same part when two operations are required.

Pull-up Type: Vertical hydraulically operated machines which pull the broach or broaches up through the work are used for internal broaching of holes of various shapes, for broaching bushings, splined holes, small internal gears, etc. A typical machine of this kind is so designed that all broach handling is done automatically.

Pull-down Type: The various movements in the operating cycle of a hydraulic pull-down type of machine equipped with an automatic broach-handling slide, are the reverse of the pull-up type. The broaches for a pull-down type of machine have shanks on each end, there being an upper one for the broach-handling slide and a lower one for pulling through the work.

Hydraulic Operation: Modern broaching machines, as a general rule, are operated hydraulically rather than by mechanical means. Hydraulic operation is efficient, flexible in the matter of speed adjustments, low in maintenance cost, and the "smooth" action required for fine precision finishing may be obtained. The hydraulic pressures required, which frequently are 800 to 1000 pounds per square inch, are obtained from a motor-driven pump forming part of the machine. The cutting speeds of broaching machines frequently are between 20 and 30 feet per minute, and the return speeds often are double the cutting speed, or higher, to reduce the idle period.

Ball-Broaching.— Ball-broaching is a method of securing bushings, gears, or other components without the need for keys, pins, or splines. A series of axial grooves, separated by ridges, is formed in the bore of the workpiece by cold plastic deformation of the metal when a tool, having a row of three rotating balls around its periphery, is pressed through the parts. When the bushing is pressed into a broached bore, the ridges displace the softer material of the bushing into the grooves—thus securing the assembly. The balls can be made of high-carbon chromium steel or carbide, depending on the hardness of the component.

Copyright 2004, Industrial Press, Inc., New York, NY

Broaching Difficulties.— The accompanying table has been compiled from information supplied by the National Broach and Machine Co. and presents some of the common broaching difficulties, their causes and means of correction.

Causes of Broaching Difficulties

Broaching Difficulty	Possible Causes
Stuck broach	Insufficient machine capacity; dulled teeth; clogged chip gullets; failure of power during cutting stroke. To remove a stuck broach, workpiece and broach are removed from the machine as a unit; never try to back out broach by reversing machine. If broach does not loosen by tapping workpiece lightly and trying to slide it off its starting end, mount workpiece and broach in a lathe and turn down workpiece to the tool surface. Workpiece may be sawed longitudinally into several sections in order to free the broach. Check broach design, perhaps tooth relief (back off) angle is too small or depth of cut per tooth is too great.
Galling and pickup	Lack of homogeneity of material being broached—uneven hardness, porosity; improper or insufficient coolant; poor broach design, mutilated broach; dull broach; improperly sharpened broach; improperly designed or outworn fixtures. Good broach design will do away with possible chip build-up on tooth faces and excessive heating. Grinding of teeth should be accurate so that the correct gullet contour is maintained. Contour should be fair and smooth.
Broach breakage	Overloading; broach dullness; improper sharpening; interrupted cutting stroke; backing up broach with workpiece in fixture; allowing broach to pass entirely through guide hole; ill fitting and/or sharp edged key; crooked holes; untrue locating surface; excessive hardness of workpiece; insufficient clearance angle; sharp corners on pull end of broach. When grinding bevels on pull end of broach use wheel that is not too pointed.
Chatter	Too few teeth in cutting contact simultaneously; excessive hardness of material being broached; loose or poorly constructed tooling; surging of ram due to load variations. Chatter can be alleviated by changing the broaching speed, by using shear cutting teeth instead of right angle teeth, and by changing the coolant and the face and relief angles of the teeth.
Drifting or misalignment of tool during cutting stroke	Lack of proper alignment when broach is sharpened in grinding machine, which may be caused by dirt in the female center of the broach; inadequate support of broach during the cutting stroke, on a horizontal machine especially; body diameter too small; cutting resistance variable around I.D. of hole due to lack of symmetry of surfaces to be cut; variations in hardness around I.D. of hole; too few teeth in cutting contact.
Streaks in broached surface	Lands too wide; presence of forging, casting or annealing scale; metal pickup; presence of grinding burrs and grinding and cleaning abrasives.
Rings in the broached hole	Due to surging resulting from uniform pitch of teeth; presence of sharpening burrs on broach; tooth clearance angle too large; locating face not smooth or square; broach not supported for all cutting teeth passing through the work. The use of differential tooth spacing or shear cutting teeth helps in preventing surging. Sharpening burrs on a broach may be removed with a wood block.

Copyright 2004, Industrial Press, Inc., New York, NY

FILES AND BURS

Files

Definitions of File Terms.— The following file terms apply to hand files but not to rotary files and burs.

Axis: Imaginary line extending the entire length of a file equidistant from faces and edges.

Back: The convex side of a file having the same or similar cross-section as a half-round file.

Bastard Cut: A grade of file coarseness between coarse and second cut of American pattern files and rasps.

Blank: A file in any process of manufacture before being cut.

Blunt: A file whose cross-sectional dimensions from point to tang remain unchanged.

Coarse Cut: The coarsest of all American pattern file and rasp cuts.

Coarseness: Term describing the relative number of teeth per unit length, the coarsest having the least number of file teeth per unit length; the smoothest, the most. American pattern files and rasps have four degrees of coarseness: coarse, bastard, second and smooth. Swiss pattern files usually have seven degrees of coarseness: 00, 0, 1, 2, 3, 4, 6 (from coarsest to smoothest). Curved tooth files have three degrees of coarseness: standard, fine and smooth.

Curved Cut: File teeth which are made in curved contour across the file blank.

Cut: Term used to describe file teeth with respect to their coarseness or their character (single, double, rasp, curved, special).

Double Cut: A file tooth arrangement formed by two series of cuts, namely the overcut followed, at an angle, by the upcut.

Edge: Surface joining faces of a file. May have teeth or be smooth.

Face: Widest cutting surface or surfaces that are used for filing.

Heel or Shoulder: That portion of a file that abuts the tang.

Hopped: A term used among file makers to represent a very wide skip or spacing between file teeth.

Length: The distance from the heel to the point.

Overcut: The first series of teeth put on a double-cut file.

Point: The front end of a file; the end opposite the tang.

Rasp Cut: A file tooth arrangement of round-topped teeth, usually not connected, that are formed individually by means of a narrow, punch-like tool.

Re-cut: A worn-out file which has been re-cut and re-hardened after annealing and grinding off the old teeth.

Safe Edge: An edge of a file that is made smooth or uncut, so that it will not injure that portion or surface of the workplace with which it may come in contact during filing.

Second Cut: A grade of file coarseness between bastard and smooth of American pattern files and rasps.

Set: To blunt the sharp edges or corners of file blanks before and after the overcut is made, in order to prevent weakness and breakage of the teeth along such edges or corners when the file is put to use.

Shoulder or Heel: See *Heel or Shoulder*.

Single Cut: A file tooth arrangement where the file teeth are composed of single unbroken rows of parallel teeth formed by a single series of cuts.

Smooth Cut: An American pattern file and rasp cut that is smoother than second cut.

Tang: The narrowed portion of a file which engages the handle.

Upcut: The series of teeth superimposed on the overcut, and at an angle to it, on a double-cut file.

Copyright 2004, Industrial Press, Inc., New York, NY

File Characteristics.— Files are classified according to their shape or cross-section and according to the pitch or spacing of their teeth and the nature of the cut.

Cross-section and Outline: The cross-section may be quadrangular, circular, triangular, or some special shape. The outline or contour may be tapered or blunt. In the former, the point is more or less reduced in width and thickness by a gradually narrowing section that extends for one-half to two-thirds of the length. In the latter the cross-section remains uniform from tang to point.

Cut: The character of the teeth is designated as single, double, rasp or curved. The *single cut file* (or *float* as the coarser cuts are sometimes called) has a single series of parallel teeth extending across the face of the file at an angle of from 45 to 85 degrees with the axis of the file. This angle depends upon the form of the file and the nature of the work for which it is intended. The single cut file is customarily used with a light pressure to produce a smooth finish. The *double cut file* has a multiplicity of small pointed teeth inclining toward the point of the file arranged in two series of diagonal rows that cross each other. For general work, the angle of the first series of rows is from 40 to 45 degrees and of the second from 70 to 80 degrees. For *double cut finishing files* the first series has an angle of about 30 degrees and the second, from 80 to 87 degrees. The second, or upcut, is almost always deeper than the first or overcut. Double cut files are usually employed, under heavier pressure, for fast metal removal and where a rougher finish is permissible. The *rasp* is formed by raising a series of individual rounded teeth from the surface of the file blank with a sharp narrow, punch-like cutting tool and is used with a relatively heavy pressure on soft substances for fast removal of material. The curved tooth file has teeth that are in the form of parallel arcs extending across the face of the file, the middle portion of each arc being closest to the point of the file. The teeth are usually single cut and are relatively coarse. They may be formed by steel displacement but are more commonly formed by milling.

With reference to coarseness of cut the terms *coarse, bastard, second* and *smooth cuts* are used, the coarse or bastard files being used on the heavier classes of work and the second or smooth cut files for the finishing or more exacting work. These degrees of coarseness are only comparable when files of the same length are compared, as the number or teeth per inch of length decreases as the length of the file increases. The number of teeth per inch varies considerably for different sizes and shapes and for files of different makes. The coarseness range for the curved tooth files is given as standard, fine and smooth. In the case of Swiss pattern files, a series of numbers is used to designate coarseness instead of names; Nos. 00, 0, 1, 2, 3, 4 and 6 being the most common with No. 00 the coarsest and No. 6 the finest.

Classes of Files.— There are five main classes of files: mill or saw files; machinists' files; curved tooth files; Swiss pattern files; and rasps. The first two classes are commonly referred to as American pattern files.

Mill or Saw Files: These are used for sharpening mill or circular saws, large crosscut saws; for lathe work; for draw filing; for filing brass and bronze; and for smooth filing generally. The number identifying the following files refers to the illustration in Fig. 1

1) *Cantsaw files* have an obtuse isosceles triangular section, a blunt outline, are single cut and are used for sharpening saws having "M"-shaped teeth and teeth of less than 60-degree angle; 2) *Crosscut files* have a narrow triangular section with short side rounded, a blunt outline, are single cut and are used to sharpen crosscut saws. The rounded portion is used to deepen the gullets of saw teeth and the sides are used to sharpen the teeth themselves. ;

3) *Double ender files*have a triangular section, are tapered from the middle to both ends, are tangless are single cut and are used reversibly for sharpening saws; 4) The *mill file* itself, is usually single cut, tapered in width, and often has two square cutting edges in addition to the cutting sides. Either or both edges may be rounded, however, for filing the gul-

Copyright 2004, Industrial Press, Inc., New York, NY

lets of saw teeth. The *blunt mill file* has a uniform rectangular cross-section from tip to tang; 5) The *The triangular saw files or taper saw files* have an equilateral triangular section, are tapered, are single cut and are used for filing saws with 60-degree angle teeth. They come in taper, slim taper, extra slim taper and double extra slim taper thicknesses *Blunt triangular* and *blunt hand saw files* are without taper; and 6) *Web saw files* have a diamond-shaped section, a blunt outline, are single cut and are used for sharpening pulpwood or web saws. .

Machinists' Files: These files are used throughout industry where metal must be removed rapidly and finish is of secondary importance. Except for certain exceptions in the round and half-round shapes, all are double cut. 7) *Flat files* have a rectangular section, are tapered in width and thickness, are cut on both sides and edges and are used for general utility work; 8) *Half round files* have a circular segmental section, are tapered in width and thickness, have their flat side double cut, their rounded side mostly double but sometimes single cut, and are used to file rounded holes, concave corners, etc. in general filing work; 9) *Hand files* are similar to flat files but taper in thickness only. One edge is uncut or "safe."; and 10) *Knife files* have a "knife-blade" section, are tapered in width only, are double cut, and are used by tool and die makers on work having acute angles.

Machinist's general purpose files have a rectangular section, are tapered and have single cut teeth divided by angular serrations which produce short cutting edges. These edges help stock removal but still leave a smooth finish and are suitable for use on various materials including aluminum, bronze, cast iron, malleable iron, mild steels and annealed tool steels.

11) *Pillar files* are similar to hand files but are thicker and not as wide; 12) *Round files* have a circular section, are tapered, single cut, and are generally used to file circular openings or curved surfaces; 13) *Square files* have a square section, are tapered, and are used for filing slots, keyways and for general surface filing where a heavier section is preferred; 14) *Three square files* have an equilateral triangular section and are tapered on all sides. They are double cut and have sharp corners as contrasted with taper triangular files which are single cut and have somewhat rounded corners. They are used for filing accurate internal angles, for clearing out square corners, and for filing taps and cutters; and 15) *Warding files* have a rectangular section, and taper in width to a narrow point. They are used for general narrow space filing. .

Wood files are made in the same sections as flat and half round files but with coarser teeth especially suited for working on wood.



Fig. 1. Styles of Mill or Saw Files

Curved Tooth Files: Regular curved tooth files are made in both rigid and flexible forms. The rigid type has either a tang for a conventional handle or is made plain with a hole at each end for mounting in a special holder. The flexible type is furnished for use in special holders only. The curved tooth files come in standard fine and smooth cuts and in parallel

Copyright 2004, Industrial Press, Inc., New York, NY

flat, square, pillar, pillar narrow, half round and shell types. A special curved tooth file is available with teeth divided by long angular serrations. The teeth are cut in an "off center" arc. When moved across the work toward one edge of the file a fast cutting action is provided; when moved toward the other edge, a smoothing action; thus the file is made to serve a dual purpose.

Swiss Pattern Files: These are used by tool and die makers, model makers and delicate instrument parts finishers. They are made to closer tolerances than the conventional American pattern files although with similar cross-sections. The points of the Swiss pattern files are smaller, the tapers are longer and they are available in much finer cuts. They are primarily finishing tools for removing burrs left from previous finishing operations truing up narrow grooves, notches and keyways, cleaning out corners and smoothing small parts. For very fine work, *round* and *square handled needle files,* available in numerous cross-sectional shapes in overall lengths from 4 to 7 ¾ inches, are used. Die sinkers use *die sinkers files* and *die sinkers rifflers*. The files, also made in many different cross-sectional shapes, are 3½ inches in length and are available in the cut Nos. 0, 1, 2, and 4. The rifflers are from 5½ to 6¾ inches long, have cutting surfaces on either end, and come in numerous cross-sectional shapes in cut Nos. 0, 2, 3, 4 and 6. These rifflers are used by die makers for getting into corners, crevices, holes and contours of intricate dies and molds. Used in the same fashion as die sinkers rifflers, *silversmiths rifflers,* that have a much heavier cross-section, are available in lengths from 6 ⅞ to 8 inches and in cuts Nos. 0, 1, 2, and 3. *Blunt machine files* in Cut Nos. 00, 0, and 2 for use in ordinary and bench filing machines are available in many different cross-sectional shapes, in lengths from 3 to 8 inches.

Rasps: Rasps are employed for work on relatively soft substances such as wood, leather, and lead where fast removal or material is required. They come in rectangular and half round cross-sections, the latter with and without a sharp edge.

Special Purpose Files: Falling under one of the preceding five classes of files, but modified to meet the requirements of some particular function, are a number of special purpose files. The *long angle lathe file* is used for filing work that is rotating in a lathe. The long tooth angle provides a clean shear, eliminates drag or tear and is self-clearing. This file has safe or uncut edges to protect shoulders of the work which are not to be filed. The *foundry file* has especially sturdy teeth with heavy set edges for the snagging of castings—the removing of fins, sprues, and other projections. The *die casting file* has extra strong teeth on corners and edges as well as sides for working on die castings of magnesium, zinc, or aluminum alloys. A special file for stainless steel is designed to stand up under the abrasive action of stainless steel alloys. *Aluminum rasps* and *files* are designed to eliminate clogging. A special tooth construction is used in one type of aluminum tile which breaks up the filings, allows the file to clear itself and overcomes chatter. A *brass file* is designed so that with a little pressure the sharp, high-cut teeth bite deep while with less pressure, their short uncut angle produces a smoothing effect. The *lead float* has coarse, single cut teeth at almost right angles to the file axis. These shear away the metal under ordinary pressure and produce a smoothing effect under light pressure. The *shear tooth file* has a coarse single cut with a long angle for soft metals or alloys, plastics, hard rubber and wood. *Chain saw files* are designed to sharpen all types of chain saw teeth. These files come in round, rectangular, square and diamond-shaped sections. The round and square sectioned files have either double or single cut teeth, the rectangular files have single cut teeth and the diamond-shaped files have double cut teeth.

Effectiveness of Rotary Files and Burs.— There it very little difference in the efficiency of rotary files or burs when used in electric tools and when used in air tools, provided the speeds have been reasonably well selected. Flexible-shaft and other machines used as a source of power for these tools have a limited number of speeds which govern the revolutions per minute at which the tools can be operated.

Copyright 2004, Industrial Press, Inc., New York, NY

The carbide bur may be used on hard or soft materials with equally good results. The principle difference in construction of the carbide bur is that its teeth or flutes are provided with a negative rather than a radial rake. Carbide burs are relatively brittle, and must be treated more carefully than ordinary burs. They should be kept cutting freely, in order to prevent too much pressure, which might result in crumbling of the cutting epics.

At the same speeds, both high-speed steel and carbide burs remove approximately the same amount of metal. However, when carbide burs are used at their most efficient speeds, the rate of stock removal may be as much as four times that of ordinary burs. In certain cases, speeds much higher than those shown in the table can be used. It has been demonstrated that a carbide bur will last up to 100 times as long as a high-speed steel bur of corresponding size and shape.

Approximate Speeds of Rotary Files and Burs

Tool Diam., Inches	Medium Cut, High-Speed Steel Bur or File					Carbide Bur	
	Mild Steel	Cast Iron	Bronze	Aluminum	Magnesium	Medium Cut	Fine Cut
	Speed, Revolutions per Minute					Any Material	
1/8	4600	7000	15,000	20,000	30,000	45,000	30,000
1/4	3450	5250	11,250	15,000	22,500	30,000	20,000
3/8	2750	4200	9000	12,000	18,000	24,000	16,000
1/2	2300	3500	7500	10,000	15,000	20,000	13,350
5/8	2000	3100	6650	8900	13,350	18,000	12,000
3/4	1900	2900	6200	8300	12,400	16,000	10,650
7/8	1700	2600	5600	7500	11,250	14,500	9650
1	1600	2400	5150	6850	10,300	13,000	8650
1 1/8	1500	2300	4850	6500	9750	…	…
1 1/4	1400	2100	4500	6000	9000	…	…

As recommended by the Nicholson File Company.

Steel Wool.— Steel wool is made by shaving thin layers of steel from wire. The wire is pulled, by special machinery built for the purpose, past cutting tools or through cutting dies which shave off chips from the outside. Steel wool consists of long, relatively strong, and resilient steel shavings having sharp edges. This characteristic renders it an excellent abrasive. The fact that the cutting characteristics of steel wool vary with the size of the fiber, which is readily controlled in manufacture, has adapted it to many applications.

Metals other than steel have been made into wool by the same processes as steel, and when so manufactured have the same general characteristics. Thus wool has been made from copper, lead, aluminum, bronze, brass, monel metal, and nickel. The wire from which steel wool is made may be produced by either the Bessemer, or the basic or acid open-hearth processes. It should contain from 0.10 to 0.20 per cent carbon; from 0.50 to 1.00 per cent manganese; from 0.020 to 0.090 per cent sulphur; from 0.050 to 0.120 per cent phosphorus; and from 0.001 to 0.010 per cent silicon. When drawn on a standard tensile-strength testing machine, a sample of the steel should show an ultimate strength of not less than 120,000 pounds per square inch.

Steel Wool Grades

Description	Grade	Fiber Thickness		Description	Grade	Fiber Thickness	
		Inch	Millimeter			Inch	Millimeter
Super Fine	0000	0.001	0.025	Medium	1	0.0025	0.06
Extra Fine	000	0.0015	0.035	Medium Coarse	2	0.003	0.075
Very Fine	00	0.0018	0.04	Coarse	3	0.0035	0.09
Fine	0	0.002	0.05	Extra Coarse	4	0.004	0.10

Copyright 2004, Industrial Press, Inc., New York, NY

TOOL WEAR AND SHARPENING

Metal cutting tools wear constantly when they are being used. A normal amount of wear should not be a cause for concern until the size of the worn region has reached the point where the tool should be replaced. Normal wear cannot be avoided and should be differentiated from abnormal tool breakage or excessively fast wear. Tool breakage and an excessive rate of wear indicate that the tool is not operating correctly and steps should be taken to correct this situation.

There are several basic mechanisms that cause tool wear. It is generally understood that tools wear as a result of abrasion which is caused by hard particles of work material plowing over the surface of the tool. Wear is also caused by diffusion or alloying between the work material and the tool material. In regions where the conditions of contact are favorable, the work material reacts with the tool material causing an attrition of the tool material. The rate of this attrition is dependent upon the temperature in the region of contact and the reactivity of the tool and the work materials with each other. Diffusion or alloying also occurs where particles of the work material are welded to the surface of the tool. These welded deposits are often quite visible in the form of a built-up edge, as particles or a layer of work material inside a crater or as small mounds attached to the face of the tool. The diffusion or alloying occurring between these deposits and the tool weakens the tool material below the weld. Frequently these deposits are again rejoined to the chip by welding or they are simply broken away by the force of collision with the passing chip. When this happens, a small amount of the tool material may remain attached to the deposit and be plucked from the surface of the tool, to be carried away with the chip. This mechanism can cause chips to be broken from the cutting edge and the formation of small craters on the tool face called pull-outs. It can also contribute to the enlargement of the larger crater that sometimes forms behind the cutting edge. Among the other mechanisms that can cause tool wear are severe thermal gradients and thermal shocks, which cause cracks to form near the cutting edge, ultimately leading to tool failure. This condition can be caused by improper tool grinding procedures, heavy interrupted cuts, or by the improper application of cutting fluids when machining at high cutting speeds. Chemical reactions between the active constituents in some cutting fluids sometimes accelerate the rate of tool wear. Oxidation of the heated metal near the cutting edge also contributes to tool wear, particularly when fast cutting speeds and high cutting temperatures are encountered. Breakage of the cutting edge caused by overloading, heavy shock loads, or improper tool design is not normal wear and should be corrected.

The wear mechanisms described bring about visible manifestations of wear on the tool which should be understood so that the proper corrective measures can be taken, when required. These visible signs of wear are described in the following paragraphs and the corrective measures that might be required are given in the accompanying Tool Trouble-Shooting Check List. The best procedure when trouble shooting is to try to correct only one condition at a time. When a correction has been made it should be checked. After one condition has been corrected, work can then start to correct the next condition.

Flank Wear: Tool wear occurring on the flank of the tool below the cutting edge is called flank wear. Flank wear always takes place and cannot be avoided. It should not give rise to concern unless the rate of flank wear is too fast or the flank wear land becomes too large in size. The size of the flank wear can be measured as the distance between the top of the cutting edge and the bottom of the flank wear land. In practice, a visual estimate is usually made instead of a precise measurement, although in many instances flank wear is ignored and the tool wear is "measured" by the loss of size on the part. The best measure of tool wear, however, is flank wear. When it becomes too large, the rubbing action of the wear land against the workpiece increases and the cutting edge must be replaced. Because conditions vary, it is not possible to give an exact amount of flank wear at which the tool should be replaced. Although there are many exceptions, as a rough estimate, high-speed steel

Copyright 2004, Industrial Press, Inc., New York, NY

tools should be replaced when the width of the flank wear land reaches 0.005 to 0.010 inch for finish turning and 0.030 to 0.060 inch for rough turning; and for cemented carbides 0.005 to 0.010 inch for finish turning and 0.020 to 0.040 inch for rough turning.

Under ideal conditions which, surprisingly, occur quite frequently, the width of the flank wear land will be very uniform along its entire length. When the depth of cut is uneven, such as when turning out-of-round stock, the bottom edge of the wear land may become somewhat slanted, the wear land being wider toward the nose. A jagged-appearing wear land usually is evidence of chipping at the cutting edge. Sometimes, only one or two sharp depressions of the lower edge of the wear land will appear, to indicate that the cutting edge has chipped above these depressions. A deep notch will sometimes occur at the "depth of cut line," or that part of the cutting opposite the original surface of the work. This can be caused by a hard surface scale on the work, by a work-hardened surface layer on the work, or when machining high-temperature alloys. Often the size of the wear land is enlarged at the nose of the tool. This can be a sign of crater breakthrough near the nose or of chipping in this region. Under certain conditions, when machining with carbides, it can be an indication of deformation of the cutting edge in the region of the nose.

When a sharp tool is first used, the initial amount of flank wear is quite large in relation to the subsequent total amount. Under normal operating conditions, the width of the flank wear land will increase at a uniform rate until it reaches a critical size after which the cutting edge breaks down completely. This is called catastrophic failure and the cutting edge should be replaced before this occurs. When cutting at slow speeds with high-speed steel tools, there may be long periods when no increase in the flank wear can be observed. For a given work material and tool material, the rate of flank wear is primarily dependent on the cutting speed and then the feed rate.

Cratering: A deep crater will sometimes form on the face of the tool which is easily recognizable. The crater forms at a short distance behind the side cutting edge leaving a small shelf between the cutting edge and the edge of the crater. This shelf is sometimes covered with the built-up edge and at other times it is uncovered. Often the bottom of the crater is obscured with work material that is welded to the tool in this region. Under normal operating conditions, the crater will gradually enlarge until it breaks through a part of the cutting edge. Usually this occurs on the end cutting edge just behind the nose. When this takes place, the flank wear at the nose increases rapidly and complete tool failure follows shortly. Sometimes cratering cannot be avoided and a slow increase in the size of the crater is considered normal. However, if the rate of crater growth is rapid, leading to a short tool life, corrective measures must be taken.

Cutting Edge Chipping: Small chips are sometimes broken from the cutting edge which accelerates tool wear but does not necessarily cause immediate tool failure. Chipping can be recognized by the appearance of the cutting edge and the flank wear land. A sharp depression in the lower edge of the wear land is a sign of chipping and if this edge of the wear land has a jagged appearance it indicates that a large amount of chipping has taken place. Often the vacancy or cleft in the cutting edge that results from chipping is filled up with work material that is tightly welded in place. This occurs very rapidly when chipping is caused by a built-up edge on the face of the tool. In this manner the damage to the cutting edge is healed; however, the width of the wear land below the chip is usually increased and the tool life is shortened.

Deformation: Deformation occurs on carbide cutting tools when taking a very heavy cut using a slow cutting speed and a high feed rate. A large section of the cutting edge then becomes very hot and the heavy cutting pressure compresses the nose of the cutting edge, thereby lowering the face of the tool in the area of the nose. This reduces the relief under the nose, increases the width of the wear land in this region, and shortens the tool life.

Surface Finish: The finish on the machined surface does not necessarily indicate poor cutting tool performance unless there is a rapid deterioration. A good surface finish is,

Copyright 2004, Industrial Press, Inc., New York, NY

however, sometimes a requirement. The principal cause of a poor surface finish is the built-up edge which forms along the edge of the cutting tool. The elimination of the built-up edge will always result in an improvement of the surface finish. The most effective way to eliminate the built-up edge is to increase the cutting speed. When the cutting speed is increased beyond a certain critical cutting speed, there will be a rather sudden and large improvement in the surface finish. Cemented carbide tools can operate successfully at higher cutting speeds, where the built-up edge does not occur and where a good surface finish is obtained. Whenever possible, cemented carbide tools should be operated at cutting speeds where a good surface finish will result. There are times when such speeds are not possible. Also, high-speed tools cannot be operated at the speed where the built-up edge does not form. In these conditions the most effective method of obtaining a good surface finish is to employ a cutting fluid that has active sulphur or chlorine additives.

Cutting tool materials that do not alloy readily with the work material are also effective in obtaining an improved surface finish. Straight titanium carbide and diamond are the two principal tool materials that fall into this category.

The presence of feed marks can mar an otherwise good surface finish and attention must be paid to the feed rate and the nose radius of the tool if a good surface finish is desired. Changes in the tool geometry can also be helpful. A small "flat," or secondary cutting edge, ground on the end cutting edge behind the nose will sometimes provide the desired surface finish. When the tool is in operation, the flank wear should not be allowed to become too large, particularly in the region of the nose where the finished surface is produced.

Sharpening Twist Drills.— Twist drills are cutting tools designed to perform concurrently several functions, such as penetrating directly into solid material, ejecting the removed chips outside the cutting area, maintaining the essentially straight direction of the advance movement and controlling the size of the drilled hole. The geometry needed for these multiple functions is incorporated into the design of the twist drill in such a manner that it can be retained even after repeated sharpening operations. Twist drills are resharpened many times during their service life, with the practically complete restitution of their original operational characteristics. However, in order to assure all the benefits which the design of the twist drill is capable of providing, the surfaces generated in the sharpening process must agree with the original form of the tool's operating surfaces, unless a change of shape is required for use on a different work material.

The principal elements of the tool geometry which are essential for the adequate cutting performance of twist drills are shown in Fig. 1. The generally used values for these dimensions are the following:

Point angle: Commonly 118°, except for high strength steels, 118° to 135°; aluminum alloys, 90° to 140°; and magnesium alloys, 70° to 118°.

Helix angle: Commonly 24° to 32°, except for magnesium and copper alloys, 10° to 30°.

Lip relief angle: Commonly 10° to 15°, except for high strength or tough steels, 7° to 12°. The lower values of these angle ranges are used for drills of larger diameter, the higher values for the smaller diameters. For drills of diameters less than $\frac{1}{4}$ inch, the lip relief angles are increased beyond the listed maximum values up to 24°. For soft and free machining materials, 12° to 18° except for diameters less than $\frac{1}{4}$ inch, 20° to 26°.

Relief Grinding of the Tool Flanks.— In sharpening twist drills the tool flanks containing the two cutting edges are ground. Each flank consists of a curved surface which provides the relief needed for the easy penetration and free cutting of the tool edges. In grinding the flanks, Fig. 2, the drill is swung around the axis *A* of an imaginary cone while resting in a support which holds the drill at one-half the point angle *B* with respect to the face of the grinding wheel. Feed *f* for stock removal is in the direction of the drill axis. The relief angle is usually measured at the periphery of the twist drill and is also specified by that value. It is not a constant but should increase toward the center of the drill.

Copyright 2004, Industrial Press, Inc., New York, NY

The relief grinding of the flank surfaces will generate the chisel angle on the web of the twist drill. The value of that angle, typically 55°, which can be measured, for example, with the protractor of an optical projector, is indicative of the correctness of the relief grinding.



Fig. 1. The principal elements of tool geometry on twist drills.



Fig. 2. In grinding the face of the twist drill the tool is swung around the axis *A* of an imaginary cone, while resting in a support tilted by half of the point angle β with respect to the face of the grinding wheel. Feed *f* for stock removal is in the direction of the drill axis.



Fig. 3. The chisel edge *C* after thinning the web by grinding off area *T*.



Fig. 4. Split point or "crankshaft" type web thinning.

Drill Point Thinning.— The chisel edge is the least efficient operating surface element of the twist drill because it does not cut, but actually squeezes or extrudes the work material. To improve the inefficient cutting conditions caused by the chisel edge, the point width is often reduced in a drill-point thinning operation, resulting in a condition such as that shown in Fig. 3. Point thinning is particularly desirable on larger size drills and also on those which become shorter in usage, because the thickness of the web increases toward the shaft of the twist drill, thereby adding to the length of the chisel edge. The extent of point thinning is limited by the minimum strength of the web needed to avoid splitting of the drill point under the influence of cutting forces.

Both sharpening operations—the relieved face grinding and the point thinning—should be carried out in special drill grinding machines or with twist drill grinding fixtures mounted on general-purpose tool grinding machines, designed to assure the essential accu-

Copyright 2004, Industrial Press, Inc., New York, NY

racy of the required tool geometry. Off-hand grinding may be used for the important web thinning when a special machine is not available; however, such operation requires skill and experience.

Improperly sharpened twist drills, e.g. those with unequal edge length or asymmetrical point angle, will tend to produce holes with poor diameter and directional control.

For deep holes and also drilling into stainless steel, titanium alloys, high temperature alloys, nickel alloys, very high strength materials and in some cases tool steels, split point grinding, resulting in a "crankshaft" type drill point, is recommended. In this type of pointing, see Fig. 4, the chisel edge is entirely eliminated, extending the positive rake cutting edges to the center of the drill, thereby greatly reducing the required thrust in drilling. Points on modified-point drills must be restored after sharpening to maintain their increased drilling efficiency.

Sharpening Carbide Tools.— Cemented carbide indexable inserts are usually not resharpened but sometimes they require a special grind in order to form a contour on the cutting edge to suit a special purpose. Brazed type carbide cutting tools are resharpened after the cutting edge has become worn. On brazed carbide tools the cutting-edge wear should not be allowed to become excessive before the tool is re-sharpened. One method of determining when brazed carbide tools need resharpening is by periodic inspection of the flank wear and the condition of the face. Another method is to determine the amount of production which is normally obtained before excessive wear has taken place, or to determine the equivalent period of time. One disadvantage of this method is that slight variations in the work material will often cause the wear rate not to be uniform and the number of parts machined before regrinding will not be the same each time. Usually, sharpening should not require the removal of more than 0.005 to 0.010 inch of carbide.

General Procedure in Carbide Tool Grinding: The general procedure depends upon the kind of grinding operation required. If the operation is to resharpen a dull tool, a diamond wheel of 100 to 120 grain size is recommended although a finer wheel—up to 150 grain size—is sometimes used to obtain a better finish. If the tool is new or is a "standard" design and changes in shape are necessary, a 100-grit diamond wheel is recommended for roughing and a finer grit diamond wheel can be used for finishing. Some shops prefer to rough grind the carbide with a vitrified silicon carbide wheel, the finish grinding being done with a diamond wheel. A final operation commonly designated as lapping may or may not be employed for obtaining an extra-fine finish.

Wheel Speeds: The speed of silicon carbide wheels usually is about 5000 feet per minute. The speeds of diamond wheels generally range from 5000 to 6000 feet per minute; yet lower speeds (550 to 3000 fpm) can be effective.

Offhand Grinding: In grinding single-point tools (excepting chip breakers) the common practice is to hold the tool by hand, press it against the wheel face and traverse it continuously across the wheel face while the tool is supported on the machine rest or table which is adjusted to the required angle. This is known as "offhand grinding" to distinguish it from the machine grinding of cutters as in regular cutter grinding practice. The selection of wheels adapted to carbide tool grinding is very important.

Silicon Carbide Wheels.— The green colored silicon carbide wheels generally are preferred to the dark gray or gray-black variety, although the latter are sometimes used.

Grain or Grit Sizes: For roughing, a grain size of 60 is very generally used. For finish grinding with silicon carbide wheels, a finer grain size of 100 or 120 is common. A silicon carbide wheel such as C60-I-7V may be used for grinding both the steel shank and carbide tip. However, for under-cutting steel shanks up to the carbide tip, it may be advantageous to use an aluminum oxide wheel suitable for grinding softer, carbon steel.

Grade: According to the standard system of marking, different grades from soft to hard are indicated by letters from A to Z. For carbide tool grinding fairly soft grades such as G, H, I, and J are used. The usual grades for roughing are I or J and for finishing H, I, and J. The

Copyright 2004, Industrial Press, Inc., New York, NY

grade should be such that a sharp free-cutting wheel will be maintained without excessive grinding pressure. Harder grades than those indicated tend to overheat and crack the carbide.

Structure: The common structure numbers for carbide tool grinding are 7 and 8. The larger cup-wheels (10 to 14 inches) may be of the porous type and be designated as 12P. The standard structure numbers range from 1 to 15 with progressively higher numbers indicating less density and more open wheel structure.

Diamond Wheels.— Wheels with diamond-impregnated grinding faces are fast and cool cutting and have a very low rate of wear. They are used extensively both for resharpening and for finish grinding of carbide tools when preliminary roughing is required. Diamond wheels are also adapted for sharpening multi-tooth cutters such as milling cutters, reamers, etc., which are ground in a cutter grinding machine.

Resinoid bonded wheels are commonly used for grinding chip breakers, milling cutters, reamers or other multi-tooth cutters. They are also applicable to precision grinding of carbide dies, gages, and various external, internal and surface grinding operations. Fast, cool cutting action is characteristic of these wheels.

Metal bonded wheels are often used for offhand grinding of single-point tools especially when durability or long life and resistance to grooving of the cutting face, are considered more important than the rate of cutting. *Vitrified bonded* wheels are used both for roughing of chipped or very dull tools and for ordinary resharpening and finishing. They provide rigidity for precision grinding, a porous structure for fast cool cutting, sharp cutting action and durability.

Diamond Wheel Grit Sizes.— For roughing with diamond wheels a grit size of 100 is the most common both for offhand and machine grinding.

Grit sizes of 120 and 150 are frequently used in offhand grinding of single point tools 1) for resharpening; 2) for a combination roughing and finishing wheel; and 3) for chip-breaker grinding.

Grit sizes of 220 or 240 are used for ordinary finish grinding all types of tools (offhand and machine) and also for cylindrical, internal and surface finish grinding. Grits of 320 and 400 are used for "lapping" to obtain very fine finishes, and for hand hones. A grit of 500 is for lapping to a mirror finish on such work as carbide gages and boring or other tools for exceptionally fine finishes.

Diamond Wheel Grades.— Diamond wheels are made in several different grades to better adapt them to different classes of work. The grades vary for different types and shapes of wheels. Standard Norton grades are H, J, and L, for resinoid bonded wheels, grade N for metal bonded wheels and grades J, L, N, and P, for vitrified wheels. Harder and softer grades than standard may at times be used to advantage.

Diamond Concentration.— The relative amount (by carat weight) of diamond in the diamond section of the wheel is known as the "diamond concentration." Concentrations of 100 (high), 50 (medium) and 25 (low) ordinarily are supplied. A concentration of 50 represents one-half the diamond content of 100 (if the depth of the diamond is the same in each case) and 25 equals one-fourth the content of 100 or one-half the content of 50 concentration.

100 Concentration: Generally interpreted to mean 72 carats of diamond/in.^{3} of abrasive section. (A 75 concentration indicates 54 carats/in.^{3}.) Recommended (especially in grit sizes up to about 220) for general machine grinding of carbides, and for grinding cutters and chip breakers. Vitrified and metal bonded wheels usually have 100 concentration.

50 Concentration: In the finer grit sizes of 220, 240, 320, 400, and 500, a 50 concentration is recommended for offhand grinding with resinoid bonded cup-wheels.

Copyright 2004, Industrial Press, Inc., New York, NY

25 Concentration: A low concentration of 25 is recommended for offhand grinding with resinoid bonded cup-wheels with grit sizes of 100, 120 and 150.

Depth of Diamond Section: The radial depth of the diamond section usually varies from $\frac{1}{16}$ to $\frac{1}{4}$ inch. The depth varies somewhat according to the wheel size and type of bond.

Dry Versus Wet Grinding of Carbide Tools.— In using silicon carbide wheels, grinding should be done either absolutely dry or with enough coolant to flood the wheel and tool. Satisfactory results may be obtained either by the wet or dry method. However, dry grinding is the most prevalent usually because, in wet grinding, operators tend to use an inadequate supply of coolant to obtain better visibility of the grinding operation and avoid getting wet; hence checking or cracking in many cases is more likely to occur in wet grinding than in dry grinding.

Wet Grinding with Silicon Carbide Wheels: One advantage commonly cited in connection with wet grinding is that an ample supply of coolant permits using wheels about one grade harder than in dry grinding thus increasing the wheel life. Plenty of coolant also prevents thermal stresses and the resulting cracks, and there is less tendency for the wheel to load. A dust exhaust system also is unnecessary.

Wet Grinding with Diamond Wheels: In grinding with diamond wheels the general practice is to use a coolant to keep the wheel face clean and promote free cutting. The amount of coolant may vary from a small stream to a coating applied to the wheel face by a felt pad.

Coolants for Carbide Tool Grinding.— In grinding either with silicon carbide or diamond wheels a coolant that is used extensively consists of water plus a small amount either of soluble oil, sal soda, or soda ash to prevent corrosion. One prominent manufacturer recommends for silicon carbide wheels about 1 ounce of soda ash per gallon of water and for diamond wheels kerosene. The use of kerosene is quite general for diamond wheels and usually it is applied to the wheel face by a felt pad. Another coolant recommended for diamond wheels consists of 80 per cent water and 20 per cent soluble oil.

Peripheral Versus Flat Side Grinding.— In grinding single point carbide tools with silicon carbide wheels, the roughing preparatory to finishing with diamond wheels may be done either by using the flat face of a cup-shaped wheel (side grinding) or the periphery of a "straight" or disk-shaped wheel. Even where side grinding is preferred, the periphery of a straight wheel may be used for heavy roughing as in grinding back chipped or broken tools (see left-hand diagram). Reasons for preferring peripheral grinding include faster cutting with less danger of localized heating and checking especially in grinding broad surfaces. The advantages usually claimed for side grinding are that proper rake or relief angles are easier to obtain and the relief or land is ground flat. The diamond wheels used for tool sharpening are designed for side grinding. (See right-hand diagram.)



Copyright 2004, Industrial Press, Inc., New York, NY

Lapping Carbide Tools.— Carbide tools may be finished by lapping, especially if an exceptionally fine finish is required on the work as, for example, tools used for precision boring or turning non-ferrous metals. If the finishing is done by using a diamond wheel of very fine grit (such as 240, 320, or 400), the operation is often called "lapping." A second lapping method is by means of a power-driven lapping disk charged with diamond dust, Norbide powder, or silicon carbide finishing compound. A third method is by using a hand lap or hone usually of 320 or 400 grit. In many plants the finishes obtained with carbide tools meet requirements without a special lapping operation. In all cases any feather edge which may be left on tools should be removed and it is good practice to bevel the edges of roughing tools at 45 degrees to leave a chamfer 0.005 to 0.010 inch wide. This is done by hand honing and the object is to prevent crumbling or flaking off at the edges when hard scale or heavy chip pressure is encountered.

Hand Honing: The cutting edge of carbide tools, and tools made from other tool materials, is sometimes hand honed before it is used in order to strengthen the cutting edge. When interrupted cuts or heavy roughing cuts are to be taken, or when the grade of carbide is slightly too hard, hand honing is beneficial because it will prevent chipping, or even possibly, breakage of the cutting edge. Whenever chipping is encountered, hand honing the cutting edge before use will be helpful. It is important, however, to hone the edge lightly and only when necessary. Heavy honing will always cause a reduction in tool life. Normally, removing 0.002 to 0.004 inch from the cutting edge is sufficient. When indexable inserts are used, the use of pre-honed inserts is preferred to hand honing although sometimes an additional amount of honing is required. Hand honing of carbide tools in between cuts is sometimes done to defer grinding or to increase the life of a cutting edge on an indexable insert. If correctly done, so as not to change the relief angle, this procedure is sometimes helpful. If improperly done, it can result in a reduction in tool life.

Chip Breaker Grinding.— For this operation a straight diamond wheel is used on a universal tool and cutter grinder, a small surface grinder, or a special chipbreaker grinder. A resinoid bonded wheel of the grade J or N commonly is used and the tool is held rigidly in an adjustable holder or vise. The width of the diamond wheel usually varies from $\frac{1}{8}$ to $\frac{1}{4}$ inch. A vitrified bond may be used for wheels as thick as $\frac{1}{4}$ inch, and a resinoid bond for relatively narrow wheels.

Summary of Miscellaneous Points.— In grinding a single-point carbide tool, traverse it across the wheel face continuously to avoid localized heating. This traverse movement should be quite rapid in using silicon carbide wheels and comparatively slow with diamond wheels. A hand traversing and feeding movement, whenever practicable, is generally recommended because of greater sensitivity. In grinding, maintain a constant, moderate pressure. Manipulating the tool so as to keep the contact area with the wheel as small as possible will reduce heating and increase the rate of stock removal. Never cool a hot tool by dipping it in a liquid, as this may crack the tip. Wheel rotation should preferably be *against* the cutting edge or from the front face toward the back. If the grinder is driven by a reversing motor, opposite sides of a cup wheel can be used for grinding right-and left-hand tools and with rotation against the cutting edge. If it is necessary to grind the top face of a single-point tool, this should precede the grinding of the side and front relief, and top-face grinding should be minimized to maintain the tip thickness. In machine grinding with a diamond wheel, limit the feed per traverse to 0.001 inch for 100 to 120 grit; 0.0005 inch for 150 to 240 grit; and 0.0002 inch for 320 grit and finer.

Copyright 2004, Industrial Press, Inc., New York, NY

JIGS AND FIXTURES

Jig Bushings

Material for Jig Bushings.— Bushings are generally made of a good grade of tool steel to ensure hardening at a fairly low temperature and to lessen the danger of fire cracking. They can also be made from machine steel, which will answer all practical purposes, provided the bushings are properly casehardened to a depth of about $\frac{1}{16}$ inch. Sometimes, bushings for guiding tools may be made of cast iron, but only when the cutting tool is of such a design that no cutting edges come within the bushing itself. For example, bushings used simply to support the smooth surface of a boring-bar or the shank of a reamer might, in some instances, be made of cast iron, but hardened steel bushings should always be used for guiding drills, reamers, taps, etc., when the cutting edges come in direct contact with the guiding surfaces. If the outside diameter of the bushing is very large, as compared with the diameter of the cutting tool, the cost of the bushing can sometimes be reduced by using an outer cast-iron body and inserting a hardened tool steel bushing.

When tool steel bushings are made and hardened, it is recommended that A-2 steel be used. The furnace should be set to 1750°F and the bushing placed in the furnace and held there approximately 20 minutes after the furnace reaches temperature. Remove the bushing and cool in still air. After the part cools to 100–150°F, immediately place in a tempering furnace that has been heated to 300°F. Remove the bushing after one hour and cool in still air. If an atmospherically controlled furnace is unavailable, the part should be wrapped in stainless foil to prevent scaling and oxidation at the 1750°F temperature.

American National Standard Jig Bushings.— Specifications for the following types of jig bushings are given in American National Standard B94.33-1974 (R1986). Head Type Press Fit Wearing Bushings, Type H (Fig. 1 and Tables 1 and 3); Headless Type Press Fit Wearing Bushings, Type P (Fig. 2 and Tables 1 and 3); Slip Type Renewable Wearing Bushings, Type S (Fig. 3 and Tables 4 and 5); Fixed Type Renewable Wearing Bushings, Type F (Fig. 4 and Tables 5 and 6); Headless Type Liner Bushings, Type L (Fig. 5 and Table 7); and Head Type Liner Bushings, Type HL (Fig. 6 and Table 8). Specifications for locking mechanisms are also given in Table 9.



Fig. 1. Head Type Press Fit-Wearing Bushings — Type H



Fig. 2. Headless Type Press Fit Wearing Bushings — Type P



Fig. 3. Slip Type Renewable Wearing Bushings—Type S



Fig. 4. Fixed Type Renewable Wearing Bushings — Type F



Fig. 5. Headless Type Liner Bushings — Type L



Fig. 6. Head Type Liner Bushings — Type HL

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard Head Type Press Fit Wearing Bushings — Type H *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*					Body Length *C*	Radius *D*	Head Diam. *E* Max	Head Thickness *F* Max	Number
	Nom	Unfinished Max	Unfinished Min	Finished Max	Finished Min					
0.0135 up to and including 0.0625	0.156	0.166	0.161	0.1578	0.1575	0.250 0.312 0.375 0.500	0.016	0.250	0.094	H-10-4 H-10-5 H-10-6 H-10-8
0.0630 to 0.0995	0.203	0.213	0.208	0.2046	0.2043	0.250 0.312 0.375 0.500 0.750	0.016	0.312	0.094	H-13-4 H-13-5 H-13-6 H-13-8 H-13-12
0.1015 to 0.1405	0.250	0.260	0.255	0.2516	0.2513	0.250 0.312 0.375 0.500 0.750	0.016	0.375	0.094	H-16-4 H-16-5 H-16-6 H-16-8 H-16-12
0.1406 to 0.1875	0.312	0.327	0.322	0.3141	0.3138	0.250 0.312 0.375 0.500 0.750 1.000	0.031	0.438	0.125	H-20-4 H-20-5 H-20-6 H-20-8 H-20-12 H-20-16
0.189 to 0.2500	0.406	0.421	0.416	0.4078	0.4075	0.250 0.312 0.375 0.500 0.750 1.000 1.375 1.750	0.031	0.531	0.156	H-26-4 H-26-5 H-26-6 H-26-8 H-26-12 H-26-16 H-26-22 H-26-28
0.2570 to 0.3125	0.500	0.520	0.515	0.5017	0.5014	0.312 0.375 0.500 0.750 1.000 1.375 1.750	0.047	0.625	0.219	H-32-5 H-32-6 H-32-8 H-32-12 H-32-16 H-32-22 H-32-28
0.3160 to 0.4219	0.625	0.645	0.640	0.6267	0.6264	0.312 0.375 0.500 0.750 1.000 1.375 1.750 2.125	0.047	0.812	0.219	H-40-5 H-40-6 H-40-8 H-40-12 H-40-16 H-40-22 H-40-28 H-40-34
0.4375 to 0.5000	0.750	0.770	0.765	0.7518	0.7515	0.500 0.750 1.000 1.375 1.750 2.125	0.062	0.938	0.219	H-48-8 H-48-12 H-48-16 H-48-22 H-29-28 H-48-34
0.5156 to 0.6250	0.875	0.895	0.890	0.8768	0.8765	0.500 0.750 1.000 1.375 1.750 2.125 2.500	0.062	0.125	0.250	H-56-8 H-56-12 H-56-16 H-56-22 H-56-28 H-56-34 H-56-40

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **American National Standard Head Type Press Fit Wearing Bushings — Type H** *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*					Body Length *C*	Radius *D*	Head Diam. *E* Max	Head Thickness *F* Max	Number
		Unfinished		Finished						
	Nom	Max	Min	Max	Min					
0.6406 to 0.7500	1.000	1.020	1.015	1.0018	1.0015	0.500 0.750 1.000 1.375 1.750 2.125 2.500	0.094	1.250	0.312	H-64-8 H-64-12 H-64-16 H-64-22 H-64-28 H-64-34 H-64-40
0.7656 to 1.0000	1.375	1.395	1.390	1.3772	1.3768	0.750 1.000 1.375 1.750 2.125 2.500	0.094	1.625	0.375	H-88-12 H-88-16 H-88-22 H-88-28 H-88-34 H-88-40
1.0156 to 1.3750	1.750	1.770	1.765	1.7523	1.7519	1.000 1.375 1.750 2.125 2.500 3.000	0.094	2.000	0.375	H-112-16 H-112-22 H-112-28 H-112-34 H-112-40 H-112-48
1.3906 to 1.7500	2.250	2.270	2.265	2.2525	2.2521	1.000 1.375 1.750 2.125 2.500 3.000	0.094	2.500	0.375	H-144-16 H-144-22 H-144-28 H-144-34 H-144-40 H-144-48

All dimensions are in inches.
See also Table 3 for additional specifications.

Table 2. American National Standard Headless Type Press Fit Wearing Bushings — Type P *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*					Body Length *C*	Radius *D*	Number
		Unfinished		Finished				
	Nom	Max	Min	Max	Min			
0.0135 up to and including 0.0625	0.156	0.166	0.161	0.1578	0.1575	0.250 0.312 0.375 0.500	0.016	P-10-4 P-10-5 P-10-6 P-10-8
0.0630 to 0.0995	0.203	0.213	0.208	0.2046	0.2043	0.250 0.312 0.375 0.500 0.750	0.016	P-13-4 P-13-5 P-13-6 P-13-8 P-13-12
0.1015 to 0.1405	0.250	0.260	0.255	0.2516	0.2513	0.250 0.312 0.375 0.500 0.750	0.016	P-16-4 P-16-5 P-16-6 P-16-8 P-16-12
0.1406 to 0.1875	0.312	0.327	0.322	0.3141	0.3138	0.250 0.312 0.375 0.500 0.750 1.000	0.031	P-20-4 P-20-5 P-20-6 P-20-8 P-20-12 P-20-16

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **American National Standard Headless Type Press Fit Wearing Bushings — Type P** *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*					Body Length *C*	Radius *D*	Number
		Unfinished		Finished				
	Nom	Max	Min	Max	Min			
0.1890 to 0.2500	0.406	0.421	0.416	0.4078	0.4075	0.250	0.031	P-26-4
						0.312		P-26-5
						0.375		P-26-6
						0.500		P-26-8
						0.750		P-26-12
						1.000		P-26-16
						1.375		P-26-22
						1.750		P-26-28
0.2570 to 0.3125	0.500	0.520	0.515	0.5017	0.5014	0.312	0.047	P-32-5
						0.375		P-32-6
						0.500		P-32-8
						0.750		P-32-12
						1.000		P-32-16
						1.375		P-32-22
						1.750		P-32-28
0.3160 to 0.4219	0.625	0.645	0.640	0.6267	0.6264	0.312	0.047	P-40-5
						0.375		P-40-6
						0.500		P-40-8
						0.750		P-40-12
						1.000		P-40-16
						1.375		P-40-22
						1.750		P-40-28
						2.125		P-40-34
0.4375 to 0.5000	0.750	0.770	0.765	0.7518	0.7515	0.500	0.062	P-48-8
						0.750		P-48-12
						1.000		P-48-16
						1.375		P-48-22
						1.750		P-48-28
						2.125		P-48-34
0.5156 to 0.6250	0.875	0.895	0.890	0.8768	0.8765	0.500	0.062	P-56-8
						0.750		P-56-12
						1.000		P-56-16
						1.375		P-56-22
						1.750		P-56-28
						2.125		P-56-34
						2.500		P-56-40
0.6406 to 0.7500	1.000	1.020	1.015	1.0018	1.0015	0.500	0.062	P-64-8
						0.750		P-64-12
						1.000		P-64-16
						1.375		P-64-22
						1.750		P-64-28
						2.125		P-64-34
						2.500		P-64-40
0.7656 to 1.0000	1.375	1.395	1.390	1.3772	1.3768	0.750	0.094	P-88-12
						1.000		P-88-16
						1.375		P-88-22
						1.750		P-88-28
						2.125		P-88-34
						2.500		P-88-40
1.0156 to 1.3750	1.750	1.770	1.765	1.7523	1.7519	1.000	0.094	P-112-16
						1.375		P-112-22
						1.750		P-112-28
						2.125		P-112-34
						2.500		P-112-40
						3.000		P-112-48
1.3906 to 1.7500	2.250	2.270	2.265	2.2525	2.2521	1.000	0.094	P-144-16
						1.375		P-144-22
						1.750		P-144-28
						2.125		P-144-34
						2.500		P-144-40
						3.000		P-144-48

All dimensions are in inches. See Table 3 for additional specifications.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Specifications for Head Type H and Headless Type P Press Fit Wearing Bushings *ANSI B94.33-1974 (R1986)*

All dimensions given in inches. Tolerance on dimensions where not otherwise specified shall be ±0.010 inch.

Size and type of chamfer on lead end to be manufacturer's option.

The length, *C*, is the overall length for the headless type and length underhead for the head type.

The head design shall be in accordance with the manufacturer's practice.

Diameter *A* must be concentric to diameter *B* within 0.0005 T.I.V. on finish ground bushings.

The body diameter, *B*, for unfinished bushings is larger than the nominal diameter in order to provide grinding stock for fitting to jig plate holes. The grinding allowance is:

0.005 to 0.010 in. for sizes 0.156, 0.203 and 0.250 in.
0.010 to 0.015 in. for sizes 0.312 and 0.406 in.
0.015 to 0.020 in. for sizes 0.500 in. and up.

Hole sizes are in accordance with American National Standard Twist Drill Sizes.

The maximum and minimum values of the hole size, *A*, shall be as follows:

Nominal Size of Hole	Maximum	Minimum
Above 0.0135 to 0.2500 in., incl.	Nominal + 0.0004 in.	Nominal + 0.0001 in.
Above 0.2500 to 0.7500 in., incl.	Nominal + 0.0005 in.	Nominal + 0.0001 in.
Above 0.7500 to 1.5000 in., incl.	Nominal + 0.0006 in.	Nominal + 0.0002 in.
Above 1.5000 in.	Nominal + 0.0007 in.	Nominal + 0.0003 in.

Bushings in the size range from 0.0135 through 0.3125 will be counterbored to provide for lubrication and chip clearance.

Bushings without counterbore are optional and will be furnished upon request.

The size of the counterbore shall be inside diameter of the bushing + 0.031 inch.

The included angle at the bottom of the counterbore shall be 118 deg, ± 2 deg.

The depth of the counterbore shall be in accordance with the table below to provide adequate drill bearing.

	Drill Bushing Hole Size											
	0.0135 to 0.0625		0.0630 to 0.0995		0.1015 to 0.1405		0.1406 to 0.1875		0.1890 to 0.2500		0.2570 to 0.3125	
Body Length	P	H	P	H	P	H	P	H	P	H	P	H
	Minimum Drill Bearing Length—Inch											
0.250	X	0.250	X	X	X	X	X	X	X	X	X	X
0.312	X	0.250	X	X	X	X	X	X	X	X	X	X
0.375	0.250	0.250	X	X	X	X	X	X	X	X	X	X
0.500	0.250	0.250	X	0.312	X	0.312	X	0.375	X	X	X	X
0.750	+	+	0.375	0.375	0.375	0.375	X	0.375	X	X	X	X
1.000	+	+	+	+	+	+	0.625	0.625	0.625	0.625	0.625	0.625
1.375	+	+	+	+	+	+	+	+	0.625	0.625	0.625	0.625
1.750	+	+	+	+	+	+	+	+	0.625	0.625	0.625	0.625

All dimensions are in inches.

X indicates no counterbore.

+ indicates not American National Standard

Table 4. American National Standard Slip Type Renewable Wearing Bushings — Type S *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*			Length UnderHead *C*	Radius *D*	Head Diam. *E* Max	Head Thickness *F* Max	Number
	Nom	Max	Min					
0.0135 up to and including 0.0469	0.188	0.1875	0.1873	0.250 0.312 0.375 0.500	0.031	0.312	0.188	S-12-4 S-12-5 S-12-6 S-12-8
0.0492 to 0.1562	0.312	0.3125	0.3123	0.312 0.500 0.750 1.000	0.047	0.562	0.375	S-20-5 S-20-8 S-20-12 S-20-16
0.1570 to 0.3125	0.500	0.5000	0.4998	0.312 0.500 0.750 1.000 1.375 1.750	0.047	0.812	0.438	S-32-5 S-32-8 S-32-12 S-32-16 S-32-22 S-32-28
0.3160 to 0.5000	0.750	0.7500	0.7498	0.500 0.750 1.000 1.375 1.750 2.125	0.094	1.062	0.438	S-48-8 S-48-12 S-48-16 S-48-22 S-48-28 S-48-34

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. *(Continued)* American National Standard Slip Type Renewable Wearing Bushings — Type S *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*			Length UnderHead *C*	Radius *D*	Head Diam. *E* Max	Head Thickness *F* Max	Number
	Nom	Max	Min					
0.5156 to 0.7500	1.000	1.0000	0.9998	0.500 0.750 1.000 1.375 1.750 2.125 2.500	0.094	1.438	0.438	S-64-8 S-64-12 S-64-16 S-64-22 S-64-28 S-64-34 S-64-40
0.7656 to 1.0000	1.375	1.3750	1.3747	0.750 1.000 1.375 1.750 2.125 2.500	0.094	1.812	0.438	S-88-12 S-88-16 S-88-22 S-88-28 S-88-34 S-88-40
1.0156 to 1.3750	1.750	1.7500	1.7497	1.000 1.375 1.750 2.125 2.500 3.000	0.125	2.312	0.625	S-112-16 S-112-22 S-112-28 S-112-34 S-112-40 S-112-48
1.3906 to 1.7500	2.250	2.2500	2.2496	1.000 1.375 1.750 2.125 2.500 3.000	0.125	2.812	0.625	S-144-16 S-144-22 S-144-28 S-144-34 S-144-40 S-144-48

All dimensions are in inches. See also Table 5 for additional specifications.

Table 5. Specifications for Slip Type S and Fixed Type F Renewable Wearing Bushings *ANSI B94.33-1974 (R1986)*

Tolerance on dimensions where not otherwise specified shall be plus or minus 0.010 inch.
Hole sizes are in accordance with the American Standard Twist Drill Sizes.
The maximum and minimum values of hole size, *A*, shall be as follows:

Nominal Size of Hole	Maximum	Minimum
Above 0.0135 to 0.2500 in. incl.	Nominal + 0.0004 in.	Nominal + 0.0001 in.
Above 0.2500 to 0.7500 in. incl.	Nominal + 0.0005 in.	Nominal + 0.0001 in.
Above 0.7500 to 1.5000 in. incl.	Nominal + 0.0006 in.	Nominal + 0.0002 in.
Above 1.5000	Nominal + 0.0007 in.	Nominal + 0.0003 in.

The head design shall be in accordance with the manufacturer's practice.
Head of slip type is usually knurled.
When renewable wearing bushings are used with liner bushings of the head type, the length under the head will still be equal to the thickness of the jig plate, because the head of the liner bushing will be countersunk into the jig plate.
Diameter *A* must be concentric to diameter *B* within 0.0005 T.I.R. on finish ground bushings.
Size and type of chamfer on lead end to be manufacturer's option.
Bushings in the size range from 0.0135 through 0.3125 will be counterbored to provide for lubrication and chip clearance.
Bushings without counterbore are optional and will be furnished upon request.
The size of the counterbore shall be inside diameter of the bushings plus 0.031 inch.
The included angle at the bottom of the counterbore shall be 118 deg., plus or minus 2 deg.
The depth of the counterbore shall be in accordance with the table below to provide adequate drill bearing.

Body Length	Drill Bearing Hole Size											
	0.0135 to 0.0625		0.0630 to 0.0995		0.1015 to 0.1405		0.1406 to 0.1875		0.1890 to 0.2500		0.2500 to 0.3125	
	S	F	S	F	S	F	S	F	S	F	S	F
	Minimum Drill Bearing Length											
0.250	0.250	0.250	0.375	0.375	X	X	X	X	X	X	X	X
0.312	0.250	0.250	0.375	0.375	0.375	0.375	0.375	0.375	0.375	0.375	X	X
0.375	0.250	0.250	0.375	0.375	0.375	0.375	0.375	0.375	0.375	0.375	X	X
0.500	0.250	0.250	0.375	0.375	0.375	0.375	0.375	0.375	0.375	0.375	X	X
0.750	0.250	0.250	0.375	0.375	0.375	0.375	0.375	0.375	0.625	0.625	0.625	0.625
1.000	0.312	0.312	0.375	0.375	0.375	0.375	0.625	0.625	0.625	0.625	0.625	0.625
1.375	+	+	+	+	+	+	0.625	0.625	0.625	0.625	0.625	0.625
1.750	+	+	+	+	+	+	0.625	0.625	0.625	0.625	0.625	0.625

All dimensions are in inches.
X indicates no counterbore, + indicates not American National Standard length.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Fixed Type Renewable Wearing Bushings — Type F *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes *A*	Body Diameter *B*			Length Under Head *C*	Radius *D*	Head Diam. *E* Max	Head Thickness *F* Max	Number
	Nom	Max	Min					
0.0135 up to and including 0.0469	0.188	0.1875	0.1873	0.250	0.031	0.312	0.188	F-12-4
				0.312				F-12-5
				0.375				F-12-6
				0.500				F-12-8
0.0492 to 0.1562	0.312	0.3125	0.3123	0.312	0.047	0.562	0.250	F-20-5
				0.500				F-20-8
				0.750				F-20-12
				1.000				F-20-16
0.1570 to 0.3125	0.500	0.5000	0.4998	0.312	0.047	0.812	0.250	F-32-5
				0.500				F-32-8
				0.750				F-32-12
				1.000				F-32-16
				1.375				F-32-22
				1.750				F-32-28
0.3160 to 0.5000	0.750	0.7500	0.7498	0.500	0.094	1.062	0.250	F-48-8
				0.750				F-48-12
				1.000				F-48-16
				1.375				F-48-22
				1.750				F-48-28
				2.125				F-48-34
0.5156 to 0.7500	1.000	1.0000	0.9998	0.500	0.094	1.438	0.375	F-64-8
				0.750				F-64-12
				1.000				F-64-16
				1.375				F-64-22
				1.750				F-64-28
				2.125				F-64-34
				2.500				F-64-40
0.7656 to 1.0000	1.375	1.3750	1.3747	0.750	0.094	1.812	0.375	F-88-12
				1.000				F-88-16
				1.375				F-88-22
				1.750				F-88-28
				2.125				F-88-34
				2.500				F-88-40
1.0156 to 1.3750	1.750	1.7500	1.7497	1.000	0.125	2.312	0.375	F-112-16
				1.375				F-112-22
				1.750				F-112-28
				2.125				F-112-34
				2.500				F-112-40
				3.000				F-112-48
1.3906 to 1.7500	2.250	2.2500	2.2496	1.000	0.125	2.812	0.375	F-144-16
				1.375				F-144-22
				1.750				F-144-28
				2.125				F-144-34
				2.500				F-144-40
				3.000				F-144-48

All dimensions are in inches. See also Table 5 for additional specifications.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Headless Type Liner Bushings — Type L *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes in Renewable Bushings	Inside Diameter *A*			Body Diameter *B*					Over-all Length *C*	Radius *D*	Number
					Unfinished		Finished				
	Nom	Max	Min	Nom	Max	Min	Max	Min			
0.0135 up to and including 0.0469	0.188	0.1879	0.1876	0.312	0.3341	0.3288	0.3141	0.3138	0.250 0.312 0.375 0.500	0.031	L-20-4 L-20-5 L-20-6 L-20-8
0.0492 to 0.1562	0.312	0.3129	0.3126	0.500	0.520	0.515	0.5017	0.5014	0.312 0.500 0.750 1.000	0.047	L-32-5 L-32-8 L-32-12 L-32-16
0.1570 to 0.3125	0.500	0.5005	0.5002	0.750	0.770	0.765	0.7518	0.7515	0.312 0.500 0.750 1.000 1.375 1.750	0.062	L-48-5 L-48-8 L-48-12 L-48-16 L-48-22 L-48-28
0.3160 to 0.5000	0.750	0.7506	0.7503	1.000	1.020	1.015	1.0018	1.0015	0.500 0.750 1.000 1.375 1.750 2.125	0.062	L-64-8 L-64-12 L-64-16 L-64-22 L-64-28 L-64-34
0.5156 to 0.7500	1.000	1.0007	1.0004	1.375	1.395	1.390	1.3772	1.3768	0.500 1.750 1.000 1.375 1.750 2.125 2.500	0.094	L-88-8 L-88-12 L-88-16 L-88-22 L-88-28 L-88-34 L-88-40
0.7656 to 1.0000	1.375	1.3760	1.3756	1.750	1.770	1.765	1.7523	1.7519	0.750 1.000 1.375 1.750 2.125 2.500	0.094	L-112-12 L-112-16 L-112-22 L-112-28 L-112-34 L-112-40
1.0156 to 1.3750	1.750	1.7512	1.7508	2.250	2.270	2.265	2.2525	2.2521	1.000 1.375 1.750 2.125 2.500 3.000	0.094	L-144-16 L-144-22 L-144-28 L-144-34 L-144-40 L-144-48
1.3906 to 1.7500	2.250	2.2515	2.2510	2.750	2.770	2.765	2.7526	2.7522	1.000 1.375 1.750 2.125 2.500 3.000	0.125	L-176-16 L-176-22 L-176-28 L-176-34 L-176-40 L-176-48

All dimensions are in inches.

Tolerances on dimensions where otherwise not specified are ± 0.010 in.

The body diameter, *B*, for unfinished bushings is 0.015 to 0.020 in. larger than the nominal diameter in order to provide grinding stock for fitting to jig plate holes.

Diameter *A* must be concentric to diameter *B* within 0.0005 T.I.R. on finish ground bushings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. American National Standard Head Type Liner Bushing — Type HL *ANSI B94.33-1974 (R1986)*

Range of Hole Sizes in Renewable Bushings	Inside Diameter *A*			Body Diameter *B*					Overall Length *C*	Radius *D*	Head Dia. *E*	Head Thickness *F* Max	Number
					Unfinished		Finished						
	Nom	Max	Min	Nom	Max	Min	Max	Min					
0.0135 to 0.1562	0.312	0.3129	0.3126	0.500	0.520	0.515	0.5017	0.5014	0.312	0.047	0.625	0.094	HL-32-5
									0.500				HL-32-8
									0.750				HL-32-12
									1.000				HL-32-16
0.1570 to 0.3125	0.500	0.5005	0.5002	0.750	0.770	0.765	0.7518	0.7515	0.312	0.062	0.875	0.094	HL-48-5
									0.500				HL-48-8
									0.750				HL-48-12
									1.000				HL-48-16
									1.375				HL-48-22
									1.750				HL-48-28
0.3160 to 0.5000	0.750	0.7506	0.7503	1.000	1.020	1.015	1.0018	1.0015	0.500	0.062	1.125	0.125	HL-64-8
									0.750				HL-64-12
									1.000				HL-64-16
									1.375				HL-64-22
									1.750				HL-64-28
									2.125				HL-64-34
0.5156 to 0.7500	1.000	1.0007	1.0004	1.375	1.395	1.390	1.3772	1.3768	0.500	0.094	1.500	0.125	HL-88-8
									0.750				HL-88-12
									1.000				HL-88-16
									1.375				HL-88-22
									1.750				HL-88-28
									2.125				HL-88-34
									2.500				HL-88-40
0.7656 to 1.0000	1.375	1.3760	1.3756	1.750	1.770	1.765	1.7523	1.7519	0.750	0.094	1.875	0.188	HL-112-12
									1.000				HL-112-16
									1.375				HL-112-22
									1.750				HL-112-28
									2.125				HL-112-34
									2.500				HL-112-40
1.0156 to 1.3750	1.750	1.7512	1.7508	2.250	2.27	2.265	2.2525	2.2521	1.000	0.094	2.375	0.188	HL-144-16
									1.375				HL-144-22
									1.750				HL-144-28
									2.125				HL-144-34
									2.500				HL-144-40
									3.000				HL-144-48
1.3906 to 1.7500	2.250	2.2515	2.2510	2.750	2.770	2.765	2.7526	2.7522	1.000	0.125	2.875	0.188	HL-176-16
									1.375				HL-176-22
									1.750				HL-176-28
									2.125				HL-176-34
									2.500				HL-176-40
									3.000				HL-176-48

All dimensions are in inches.

See also footnotes to Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Locking Mechanisms for Jig Bushings
ANSI B94.33-1974 (R1986)

Lock Screw for Use with Slip or Fixed Renewable Bushings



No.	*A*	*B*	*C*	*D*	*E*	*F*	UNC Thread
LS-0	0.438	0.188	0.312	Per Manufacturer's Standard	0.188	0.105-0.100	8–32
LS-1	0.625	0.375	0.625		0.250	0.138-0.132	5/16–18
LS-2	0.875	0.375	0.625		0.375	0.200-0.194	5/16–18
LS-3	1.000	0.438	0.750		0.375	0.200-0.194	3/8–16

Round Clamp Optional Only for Use with Fixed Renewable Bushing



NOTE: F DIMENSION ALLOWS FOR CLAMPING. MATERIAL AND HARDNESS TO MANUFACTURER'S STANDARD. TO CHANGE TO THE ROUND CLAMP IN OLD FIXTURES, REMOVE THE CONVENTIONAL SCREW AND USE THE SAME TAPPED HOLE TO SECURE THE NEW CLAMP WITH STANDARD SOCKET HEAD SCREW.

Number	*A*	*B*	*C*	*D*	*E*	*F*	*G*	*H*	Use With Socket Head Screw
RC-1	0.625	0.312	0.484	0.150	0.203	0.125	0.531	0.328	5/16–18
RC-2	0.625	0.438	0.484	0.219	0.187	0.188	0.906	0.328	5/16–18
RC-3	0.750	0.500	0.578	0.281	0.219	0.188	1.406	0.391	3/8–16

Locking Mechanism Dimensions of Slip and Fixed Renewable Bushings



Body OD	Max Diam. *F* When Used With Locking Device	*G* Head Thickness		*H* ± 0.005	*J*	*L* Max	*R*	Locking Dim. of Lock Screw (Slip or Fixed)	Locking Dim. of Clamp (Fixed Only)	Max Head Diam. of Mating Liner Used to Clear Locking Device	Clamp or Screw LS or RC
		Slip	Fixed								
0.188	0.312	0.188	0.188	0.094	0.094	55°	0.266	0.105-0.100	…	…	0
0.312	0.562	0.375	0.250	0.125	0.172	65°	0.500	0.138-0.132	0.125-0.115	0.625	1
0.500	0.812	0.438	0.250	0.125	0.297	65°	0.625	0.138-0.132	0.125-0.115	0.875	1
0.750	1.062	0.438	0.250	0.125	0.422	50°	0.750	0.138-0.132	0.125-0.115	1.125	1
1.000	1.438	0.438	0.375	0.188	0.594	35°	0.922	0.200-0.194	0.187-0.177	1.500	2
1.375	1.812	0.438	0.375	0.188	0.781	30°	1.109	0.200-0.194	0.187-0.177	1.875	2
1.750	2.312	0.625	0.375	0.188	1.000	30°	1.391	0.200-0.194	0.187-0.177	2.375	3
2.250	2.812	0.625	0.375	0.188	1.250	25°	1.641	0.200-0.194	0.187-0.177	2.875	3

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Jig Bushing Definitions.— *Renewable Bushings:* Renewable wearing bushings to guide the tool are for use in liners which in turn are installed in the jig. They are used where the bushing will wear out or become obsolete before the jig or where several bushings are to be interchangeable in one hole. Renewable wearing bushings are divided into two classes, "Fixed" and "Slip." Fixed renewable bushings are installed in the liner with the intention of leaving them in place until worn out. Slip renewable bushings are interchangeable in a given size of liner and, to facilitate removal, they are usually made with a knurled head. They are most frequently used where two or more operations requiring different inside diameters are performed in a single jig, such as where drilling is followed by reaming, tapping, spot facing, counterboring, or some other secondary operation.

Press Fit Bushings: Press fit wearing bushings to guide the tool are for installation directly in the jig without the use of a liner and are employed principally where the bushings are used for short production runs and will not require replacement. They are intended also for short center distances.

Liner Bushings: Liner bushings are provided with and without heads and are permanently installed in a jig to receive the renewable wearing bushings. They are sometimes called master bushings.

Jig Plate Thickness.— The standard length of the press fit portion of jig bushings as established are based on standardized uniform jig plate thicknesses of 5/16, 3/8, 1/2, 3/4, 1, 1 3/8, 1 3/4, 2 1/8, 2 1/2, and 3 inches.

Jig Bushing Designation System.— *Inside Diameter:* The inside diameter of the hole is specified by a decimal dimension.

Type Bushing: The type of bushing is specified by a letter: S for Slip Renewable, F for Fixed Renewable, L for Headless Liner, HL for Head Liner, P for Headless Press Fit, and H for Head Press Fit.

Body Diameter: The body diameter is specified in multiples of 0.0156 inch. For example, a 0.500-inch body diameter = 0.500/0.0156 = 32.

Body Length: The effective or body length is specified in multiples of 0.0625 inch. For example, a 0.500-inch length = 0.500/0.0625 = 8.

Unfinished Bushings: All bushings with grinding stock on the body diameter are designated by the letter U following the number.

Example: A slip renewable bushing having a hole diameter of 0.5000 inch, a body diameter of 0.750 inch, and a body length of 1.000 inch would be designated as .5000-S-48-16.

Jig Boring

Definition of Jig and Fixture.— The distinction between a jig and fixture is not easy to define, but, as a general rule, it is as follows: A jig either holds or is held on the work, and, at the same time, contains guides for the various cutting tools, whereas a fixture holds the work while the cutting tools are in operation, but does not contain any special arrangements for guiding the tools. A fixture, therefore, must be securely held or fixed to the machine on which the operation is performed—hence the name. A fixture is sometimes provided with a number of gages and stops, but not with bushings or other devices for guiding and supporting the cutting tools.

Jig Borers.— Jig borers are used for precision hole-location work. For this reason, the coordinate measuring systems on these machines are designed to provide longitudinal and transverse movements that are accurate to 0.0001 in. One widely used method of obtaining this accuracy utilizes ultraprecision lead screws. Another measuring system employs precision end measuring rods and a micrometer head that are placed in a trough which is parallel to the table movement. However, the purpose of all coordinate measuring systems used is the same: to provide a method of aligning the spindle at the precise location where a hole is to be produced. Since the work table of a jig borer moves in two directions, the

Copyright 2004, Industrial Press, Inc., New York, NY

coordinate system of dimensioning is used, where dimensions are given from two perpendicular reference axes, usually the sides of the workpiece, frequently its upper left-hand corner. See Fig. 1C.

Jig-Boring Practice.— The four basic steps to follow to locate and machine a hole on a jig borer are:

Align and Clamp the Workpiece: The first consideration in placing the workpiece on the jig-borer table should be the relation of the coordinate measuring system of the jig borer to the coordinate dimensions on the drawing. Therefore, the coordinate measuring system is designed so that the readings of the coordinate measurements are direct when the table is moved toward the left and when it is moved toward the column of the jig borer. The result would be the same if the spindle were moved toward the right and away from the column, with the workpiece situated in such a position that one reference axis is located at the left and the other axis at the back, toward the column.

If the holes to be bored are to pass through the bottom of the workpiece, then the workpiece must be placed on precision parallel bars. In order to prevent the force exerted by the clamps from bending the workpiece the parallel bars are placed directly under the clamps, which hold the workpiece on the table. The reference axes of the workpiece must also be aligned with respect to the transverse and longitudinal table movements before it is firmly clamped. This alignment can be done with a dial-test indicator held in the spindle of the jig borer and bearing against the longitudinal reference edge. As the table is traversed in the longitudinal direction, the workpiece is adjusted until the dial-test indicator readings are the same for all positions.

Locate the Two Reference Axes of the Workpiece with Respect to the Spindle: The jig-borer table is now moved to position the workpiece in a precise and known location from where it can be moved again to the location of the holes to be machined. Since all the holes are dimensioned from the two reference axes, the most convenient position to start from is where the axis of the jig-borer spindle and the intersection of the two workpiece reference axes are aligned. This is called the starting position, which is similar to a zero reference position. When so positioned, the longitudinal and transverse measuring systems of the jig borer are set to read zero. Occasionally, the reference axes are located outside the body of the workpiece: a convenient edge or hole on the workpiece is picked up as the starting position, and the dimensions from this point to the reference axes are set on the positioning measuring system.

Locate the Hole: Precise coordinate table movements are used to position the workpiece so that the spindle axis is located exactly where the hole is to be machined. When the measuring system has been set to zero at the starting position, the coordinate readings at the hole location will be the same as the coordinate dimensions of the hole center.

The movements to each hole must be made in one direction for both the transverse and longitudinal directions, to eliminate the effect of any backlash in the lead screw. The usual table movements are toward the left and toward the column.

The most convenient sequence on machines using micrometer dials as position indicators (machines with lead screws) is to machine the hole closest to the starting position first and then the next closest, and so on. On jig borers using end measuring rods, the opposite sequence is followed: The farthest hole is machined first and then the next farthest, and so on, since it is easier to remove end rods and replace them with shorter rods.

Drill and Bore Hole to Size: The sequence of operations used to produce a hole on a jig borer is as follows: 1) a short, stiff drill, such as a center drill, that will not deflect when cutting should be used to spot a hole when the work and the axis of the machine tool spindle are located at the exact position where the hole is wanted; 2) the initial hole is made by a twist drill; and 3) a single-point boring tool that is set to rotate about the axis of the machine tool spindle is then used to generate a cut surface that is concentric to the axis of rotation.

Copyright 2004, Industrial Press, Inc., New York, NY

Heat will be generated by the drilling operation, so it is good practice to drill all the holes first, and then allow the workpiece to cool before the holes are bored to size.

Transfer of Tolerances.— All of the dimensions that must be accurately held on precision machines and engine parts are usually given a tolerance. And when such dimensions are changed from the conventional to the coordinate system of dimensioning, the tolerances must also be included. Because of their importance, the transfer of the tolerances must be done with great care, keeping in mind that the sum of the tolerances of any pair of dimensions in the coordinate system must not be larger than the tolerance of the dimension that they replaced in the conventional system. An example is given in Fig. 1.

The first step in the procedure is to change the tolerances given in Fig. 1A to equal, bilateral tolerances given in Fig. 1B. For example, the dimension $2.125^{+.003}_{-.001}$ has a total tolerance of 0.004. The equal, bilateral tolerance would be plus or minus one-half of this value, or ±.002. Then to keep the limiting dimensions the same, the basic dimension must be changed to 2.126, in order to give the required values of 2.128 and 2.124. When changing to equal, bilateral tolerances, if the upper tolerance is decreased (as in this example), the basic dimension must be increased by a like amount. The upper tolerance was decreased by 0.003 – 0.002 = 0.001; therefore, the basic dimension was increased by 0.001 to 2.126. Conversely, if the upper tolerance is increased, the basic dimension is decreased.

The next step is to transfer the revised basic dimension to the coordinate dimensioning system. To transfer the 2.126 dimension, the distance of the applicable holes from the left reference axis must be determined. The first holes to the right are 0.8750 from the reference axis. The second hole is 2.126 to the right of the first holes. Therefore, the second hole is 0.8750 + 2.126 = 3.0010 to the right of the reference axis. This value is then the coordinate dimension for the second hole, while the 0.8750 value is the coordinate dimension of the first two, vertically aligned holes. This procedure is followed for all the holes to find their distances from the two reference axes. These values are given in Fig. 1C.

The final step is to transfer the tolerances. The 2.126 value in Fig. 1B has been replaced by the 0.8750 and 3.0010 values in Fig. 1C. The 2.126 value has an available tolerance of ±0.002. Dividing this amount equally between the two replacement values gives 0.8750 ± 0.001 and 3.0010 ± 0.001. The sum of these tolerances is .002, and as required, does not exceed the tolerance that was replaced. Next transfer the tolerance of the 0.502 dimension. Divide the available tolerance, ±0.002, equally between the two replacement values to yield 3.0010 ±0.001 and 3.5030 ±0.001. The sum of these two tolerances equals the replaced tolerance, as required. However, the 1.125 value of the last hole to the right (coordinate dimension 4.6280 in.) has a tolerance of only ±0.001. Therefore, the sum of the tolerances on the 3.5030 and 4.6280 values cannot be larger than 0.001. Dividing this tolerance equally would give 3.5030 ± .0005 and 4.6280 ±0.0005. This new, smaller tolerance replaces the ± 0.001 tolerance on the 3.5030 value in order to satisfy all tolerance sum requirements. This example shows how the tolerance of a coordinate value is affected by more than one other dimensional requirement.

The following discussion will summarize the various tolerances listed in Fig. 1C. For the 0.8750 ± 0.0010 dimension, the ± 0.0010 tolerance together with the ± 0.0010 tolerance on the 3.0010 dimension is required to maintain the ± 0.002 tolerance of the 2.126 dimension. The ± .0005 tolerances on the 3.5030 and 4.2680 dimensions are required to maintain the ± 0.001 tolerance of the 1.125 dimension, at the same time as the sum of the ± .0005 tolerance on the 3.5030 dimension and the ± 0.001 tolerance on the 3.0010 dimension does not exceed the ± 0.002 tolerance on the replaced 0.503 dimension. The ± 0.0005 tolerances on the 1.0000 and 2.0000 values maintain the ± 0.001 tolerance on the 1.0000 value given at the right in Fig. 1A. The ± 0.0045 tolerance on the 3.0000 dimension together with the ± 0.0005 tolerance on the 1.0000 value maintains the ± .005 tolerance on the 2.0000 dimension of Fig. 1A. It should be noted that the 2.000 ± .005 dimension in Fig. 1A was replaced by the 1.0000 and 3.0000 dimensions in Fig. 1C. Each of these values could have had a tol-

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. (A) Conventional Dimensions, Mixed Tolerances; (B) Conventional Dimensions, All Equal, Bilateral Tolerances; and (C) Coordinate Dimensions

Copyright 2004, Industrial Press, Inc., New York, NY

erance of ± 0.0025, except that the tolerance on the 1.0000 dimension on the left in Fig. 1A is also bound by the ± 0.001 tolerance on the 1.0000 dimension on the right, thus the ± 0.0005 tolerance value is used. This procedure requires the tolerance on the 3.0000 value to be increased to ± 0.0045.

Determining Hole Coordinates

On the following pages are given tables of the lengths of chords for spacing off the circumferences of circles. The object of these tables is to make possible the division of the periphery into a number of equal parts without trials with the dividers. The first table, Table 10, is calculated for circles having a diameter equal to 1. For circles of other diameters, the length of chord given in the table should be multiplied by the diameter of the circle. Table 10 may be used by toolmakers when setting "buttons" in circular formation. Assume that it is required to divide the periphery of a circle of 20 inches diameter into thirty-two equal parts. From the table the length of the chord is found to be 0.098017 inch, if the diameter of the circle were 1 inch. With a diameter of 20 inches the length of the chord for one division would be 20 × 0.098017 = 1.9603 inches. Another example in metric units: For a 100 millimeter diameter requiring 5 equal divisions, the length of the chord for one division would be 100 × 0.587785 = 58.7785 millimeters.

Tables 11a and 11b starting on page 991 are additional tables for the spacing off of circles; the tables, in this case, being worked out for diameters from 1/16 inch to 14 inches. As an example, assume that it is required to divide a circle having a diameter of 6½ inches into seven equal parts. Find first, in the column headed "6" and in line with 7 divisions, the length of the chord for a 6-inch circle, which is 2.603 inches. Then find the length of the chord for a ½-inch diameter circle, 7 divisions, which is 0.217. The sum of these two values, 2.603 + 0.217 = 2.820 inches, is the length of the chord required for spacing off the circumference of a 6½-inch circle into seven equal divisions.

As another example, assume that it is required to divide a circle having a diameter of 9 23/32 inches into 15 equal divisions. First find the length of the chord for a 9-inch circle, which is 1.871 inch. The length of the chord for a 23/32-inch circle can easily be estimated from the table by taking the value that is exactly between those given for 11/16 and 3/4 inch. The value for 11/16 inch is 0.143, and for 3/4 inch, 0.156. For 23/32, the value would be 0.150. Then, 1.871 + 0.150 = 2.021 inches.

Hole Coordinate Dimension Factors for Jig Boring.— Tables of hole coordinate dimension factors for use in jig boring are given in Tables 12 through 15 starting on page 993. The coordinate axes shown in the figure accompanying each table are used to reference the tool path; the values listed in each table are for the end points of the tool path. In this machine coordinate system, a positive *Y* value indicates that the effective motion of the tool with reference to the work is toward the front of the jig borer (the actual motion of the jig borer table is toward the column). Similarly, a positive *X* value indicates that the effective motion of the tool with respect to the work is toward the right (the actual motion of the jig borer table is toward the left). When entering data into most computer-controlled jig borers, current practice is to use the more familiar Cartesian coordinate axis system in which the positive *Y* direction is "up" (i.e., pointing toward the column of the jig borer). The computer will automatically change the signs of the entered *Y* values to the signs that they would have in the machine coordinate system. Therefore, before applying the coordinate dimension factors given in the tables, it is important to determine the coordinate system to be used. If a Cartesian coordinate system is to be used for the tool path, then the sign of the *Y* values in the tables must be changed, from positive to negative and from negative to positive. For example, when programming for a three-hole type *A* circle using Cartesian coordinates, the *Y* values from Table 14 would be $y1 = +0.50000$, $y2 = -0.25000$, and $y3 = -0.25000$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Lengths of Chords for Spacing Off the Circumferences of Circles with a Diameter Equal to 1 (English or metric units)

No. of Spaces	Length of Chord	No. of Spaces	Length of Chord	No. of Spaces	Length of Chord	No. of Spaces	Length of Chord
3	0.866025	41	0.076549	79	0.039757	117	0.026848
4	0.707107	42	0.074730	80	0.039260	118	0.026621
5	0.587785	43	0.072995	81	0.038775	119	0.026397
6	0.500000	44	0.071339	82	0.038303	120	0.026177
7	0.433884	45	0.069756	83	0.037841	121	0.025961
8	0.382683	46	0.068242	84	0.037391	122	0.025748
9	0.342020	47	0.066793	85	0.036951	123	0.025539
10	0.309017	48	0.065403	86	0.036522	124	0.025333
11	0.281733	49	0.064070	87	0.036102	125	0.025130
12	0.258819	50	0.062791	88	0.035692	126	0.024931
13	0.239316	51	0.061561	89	0.035291	127	0.024734
14	0.222521	52	0.060378	90	0.034899	128	0.024541
15	0.207912	53	0.059241	91	0.034516	129	0.024351
16	0.195090	54	0.058145	92	0.034141	130	0.024164
17	0.183750	55	0.057089	93	0.033774	131	0.023979
18	0.173648	56	0.056070	94	0.033415	132	0.023798
19	0.164595	57	0.055088	95	0.033063	133	0.023619
20	0.156434	58	0.054139	96	0.032719	134	0.023443
21	0.149042	59	0.053222	97	0.032382	135	0.023269
22	0.142315	60	0.052336	98	0.032052	136	0.023098
23	0.136167	61	0.051479	99	0.031728	137	0.022929
24	0.130526	62	0.050649	100	0.031411	138	0.022763
25	0.125333	63	0.049846	101	0.031100	139	0.022599
26	0.120537	64	0.049068	102	0.030795	140	0.022438
27	0.116093	65	0.048313	103	0.030496	141	0.022279
28	0.111964	66	0.047582	104	0.030203	142	0.022122
29	0.108119	67	0.046872	105	0.029915	143	0.021967
30	0.104528	68	0.046183	106	0.029633	144	0.021815
31	0.101168	69	0.045515	107	0.029356	145	0.021664
32	0.098017	70	0.044865	108	0.029085	146	0.021516
33	0.095056	71	0.044233	109	0.028818	147	0.021370
34	0.092268	72	0.043619	110	0.028556	148	0.021225
35	0.089639	73	0.043022	111	0.028299	149	0.021083
36	0.087156	74	0.042441	112	0.028046	150	0.020942
37	0.084806	75	0.041876	113	0.027798	151	0.020804
38	0.082579	76	0.041325	114	0.027554	152	0.020667
39	0.080467	77	0.040789	115	0.027315	153	0.020532
40	0.078459	78	0.040266	116	0.027079	154	0.020399

For circles of other diameters, multiply length given in table by diameter of circle.

Example: In a drill jig, 8 holes, each ½ inch diameter, were spaced evenly on a 6-inch diameter circle. To test the accuracy of the jig, plugs were placed in adjacent holes, and the distance over the plugs was measured with a micrometer. What should be the micrometer reading?

Solution: The micrometer reading equals the diameter of one plug plus 6 times the chordal distance between adjacent hole centers given in the table above. Thus, the reading should be $\frac{1}{2} + (6 \times 0382683) = 2.796098$ inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11a. Table for Spacing Off the Circumferences of Circles

No. of Divisions	Degrees in Arc	Diameter of Circle to be Spaced Off														
		1/16	1/8	3/16	1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16
		Length of Chord														
3	120	0.054	0.108	0.162	0.217	0.271	0.325	0.379	0.433	0.487	0.541	0.595	0.650	0.704	0.758	0.812
4	90	0.044	0.088	0.133	0.177	0.221	0.265	0.309	0.354	0.398	0.442	0.486	0.530	0.575	0.619	0.663
5	72	0.037	0.073	0.110	0.147	0.184	0.220	0.257	0.294	0.331	0.367	0.404	0.441	0.478	0.514	0.551
6	60	0.031	0.063	0.094	0.125	0.156	0.188	0.219	0.250	0.281	0.313	0.344	0.375	0.406	0.438	0.469
7	51 3/7	0.027	0.054	0.081	0.108	0.136	0.163	0.190	0.217	0.244	0.271	0.298	0.325	0.353	0.380	0.407
8	45	0.024	0.048	0.072	0.096	0.120	0.144	0.167	0.191	0.215	0.239	0.263	0.287	0.311	0.335	0.359
9	40	0.021	0.043	0.064	0.086	0.107	0.128	0.150	0.171	0.192	0.214	0.235	0.257	0.278	0.299	0.321
10	36	0.019	0.039	0.058	0.077	0.097	0.116	0.135	0.155	0.174	0.193	0.212	0.232	0.251	0.270	0.290
11	32 8/11	0.018	0.035	0.053	0.070	0.088	0.106	0.123	0.141	0.158	0.176	0.194	0.211	0.229	0.247	0.264
12	30	0.016	0.032	0.049	0.065	0.081	0.097	0.113	0.129	0.146	0.162	0.178	0.194	0.210	0.226	0.243
13	27 9/13	0.015	0.030	0.045	0.060	0.075	0.090	0.105	0.120	0.135	0.150	0.165	0.179	0.194	0.209	0.224
14	25 5/7	0.014	0.028	0.042	0.056	0.069	0.083	0.097	0.111	0.125	0.139	0.153	0.167	0.181	0.195	0.209
15	24	0.013	0.026	0.039	0.052	0.065	0.078	0.091	0.104	0.117	0.130	0.143	0.156	0.169	0.182	0.195
16	22 1/2	0.012	0.024	0.037	0.049	0.061	0.073	0.085	0.098	0.110	0.122	0.134	0.146	0.159	0.171	0.183
17	21 3/17	0.011	0.023	0.034	0.046	0.057	0.069	0.080	0.092	0.103	0.115	0.126	0.138	0.149	0.161	0.172
18	20	0.011	0.022	0.033	0.043	0.054	0.065	0.076	0.087	0.098	0.109	0.119	0.130	0.141	0.152	0.163
19	18 18/19	0.010	0.021	0.031	0.041	0.051	0.062	0.072	0.082	0.093	0.103	0.113	0.123	0.134	0.144	0.154
20	18	0.010	0.020	0.029	0.039	0.049	0.059	0.068	0.078	0.088	0.098	0.108	0.117	0.127	0.137	0.147
21	17 1/7	0.009	0.019	0.028	0.037	0.047	0.056	0.065	0.075	0.084	0.093	0.102	0.112	0.121	0.130	0.140
22	16 4/11	0.009	0.018	0.027	0.036	0.044	0.053	0.062	0.071	0.080	0.089	0.098	0.107	0.116	0.125	0.133
23	15 15/23	0.009	0.017	0.026	0.034	0.043	0.051	0.060	0.068	0.077	0.085	0.094	0.102	0.111	0.119	0.128
24	15	0.008	0.016	0.024	0.033	0.041	0.049	0.057	0.065	0.073	0.082	0.090	0.098	0.106	0.114	0.122
25	14 2/5	0.008	0.016	0.023	0.031	0.039	0.047	0.055	0.063	0.070	0.078	0.086	0.094	0.102	0.110	0.117
26	13 11/13	0.008	0.015	0.023	0.030	0.038	0.045	0.053	0.060	0.068	0.075	0.083	0.090	0.098	0.105	0.113
28	12 6/7	0.007	0.014	0.021	0.028	0.035	0.042	0.049	0.056	0.063	0.070	0.077	0.084	0.091	0.098	0.105
30	12	0.007	0.013	0.020	0.026	0.033	0.039	0.046	0.052	0.059	0.065	0.072	0.078	0.085	0.091	0.098
32	11 1/4	0.006	0.012	0.018	0.025	0.031	0.037	0.043	0.049	0.055	0.061	0.067	0.074	0.080	0.086	0.092

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11b. Table for Spacing Off the Circumferences of Circles

No. of Divisions	Degrees in Arc	Diameter of Circle to be Spaced Off													
		1	2	3	4	5	6	7	8	9	10	11	12	13	14
		Length of Chord													
3	120	0.866	1.732	2.598	3.464	4.330	5.196	6.062	6.928	7.794	8.660	9.526	10.392	11.258	12.124
4	90	0.707	1.414	2.121	2.828	3.536	4.243	4.950	5.657	6.364	7.071	7.778	8.485	9.192	9.899
5	72	0.588	1.176	1.763	2.351	2.939	3.527	4.114	4.702	5.290	5.878	6.466	7.053	7.641	8.229
6	60	0.500	1.000	1.500	2.000	2.500	3.000	3.500	4.000	4.500	5.000	5.500	6.000	6.500	7.000
7	51 6/7	0.434	0.868	1.302	1.736	2.169	2.603	3.037	3.471	3.905	4.339	4.773	5.207	5.640	6.074
8	45	0.383	0.765	1.148	1.531	1.913	2.296	2.679	3.061	3.444	3.827	4.210	4.592	4.975	5.358
9	40	0.342	0.684	1.026	1.368	1.710	2.052	2.394	2.736	3.078	3.420	3.762	4.104	4.446	4.788
10	36	0.309	0.618	0.927	1.236	1.545	1.854	2.163	2.472	2.781	3.090	3.399	3.708	4.017	4.326
11	32 8/11	0.282	0.563	0.845	1.127	1.409	1.690	1.972	2.254	2.536	2.817	3.099	3.381	3.663	3.944
12	30	0.259	0.518	0.776	1.035	1.294	1.553	1.812	2.071	2.329	2.588	2.847	3.106	3.365	3.623
13	27 9/13	0.239	0.479	0.718	0.957	1.197	1.436	1.675	1.915	2.154	2.393	2.632	2.872	3.111	3.350
14	25 5/7	0.223	0.445	0.668	0.890	1.113	1.335	1.558	1.780	2.003	2.225	2.448	2.670	2.893	3.115
15	24	0.208	0.416	0.624	0.832	1.040	1.247	1.455	1.663	1.871	2.079	2.287	2.495	2.703	2.911
16	22 1/2	0.195	0.390	0.585	0.780	0.975	1.171	1.366	1.561	1.756	1.951	2.146	2.341	2.536	2.731
17	21 3/17	0.184	0.367	0.551	0.735	0.919	1.102	1.286	1.470	1.654	1.837	2.021	2.205	2.389	2.572
18	20	0.174	0.347	0.521	0.695	0.868	1.042	1.216	1.389	1.563	1.736	1.910	2.084	2.257	2.431
19	18 18/19	0.165	0.329	0.494	0.658	0.823	0.988	1.152	1.317	1.481	1.646	1.811	1.975	2.140	2.304
20	18	0.156	0.313	0.469	0.626	0.782	0.939	1.095	1.251	1.408	1.564	1.721	1.877	2.034	2.190
21	17 1/7	0.149	0.298	0.447	0.596	0.745	0.894	1.043	1.192	1.341	1.490	1.639	1.789	1.938	2.087
22	16 4/11	0.142	0.285	0.427	0.569	0.712	0.854	0.996	1.139	1.281	1.423	1.565	1.708	1.850	1.992
23	15 15/23	0.136	0.272	0.408	0.545	0.681	0.817	0.953	1.089	1.225	1.362	1.498	1.634	1.770	1.906
24	15	0.131	0.261	0.392	0.522	0.653	0.783	0.914	1.044	1.175	1.305	1.436	1.566	1.697	1.827
25	14 2/5	0.125	0.251	0.376	0.501	0.627	0.752	0.877	1.003	1.128	1.253	1.379	1.504	1.629	1.755
26	13 11/13	0.121	0.241	0.362	0.482	0.603	0.723	0.844	0.964	1.085	1.205	1.326	1.446	1.567	1.688
28	12 6/7	0.112	0.224	0.336	0.448	0.560	0.672	0.784	0.896	1.008	1.120	1.232	1.344	1.456	1.568
30	12	0.105	0.209	0.314	0.418	0.523	0.627	0.732	0.836	0.941	1.045	1.150	1.254	1.359	1.463
32	11 1/4	0.098	0.196	0.294	0.392	0.490	0.588	0.686	0.784	0.882	0.980	1.078	1.176	1.274	1.372

See *Determining Hole Coordinates* on page 989 for explanatory matter.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

3 Holes		4 Holes		5 Holes		6 Holes		7 Holes		8 Holes		9 Holes	
*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000
*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000
*x*2	0.06699	*x*2	0.00000	*x*2	0.02447	*x*2	0.06699	*x*2	0.10908	*x*2	0.14645	*x*2	0.17861
*y*2	0.75000	*y*2	0.50000	*y*2	0.34549	*y*2	0.25000	*y*2	0.18826	*y*2	0.14645	*y*2	0.11698
*x*3	0.93301	*x*3	0.50000	*x*3	0.20611	*x*3	0.06699	*x*3	0.01254	*x*3	0.00000	*x*3	0.00760
*y*3	0.75000	*y*3	1.00000	*y*3	0.90451	*y*3	0.75000	*y*3	0.61126	*y*3	0.50000	*y*3	0.41318
		*x*4	1.00000	*x*4	0.79389	*x*4	0.50000	*x*4	0.28306	*x*4	0.14645	*x*4	0.06699
		*y*4	0.50000	*y*4	0.90451	*y*4	1.00000	*y*4	0.95048	*y*4	0.85355	*y*4	0.75000
				*x*5	0.97553	*x*5	0.93301	*x*5	0.71694	*x*5	0.50000	*x*5	0.32899
				*y*5	0.34549	*y*5	0.75000	*y*5	0.95048	*y*5	1.00000	*y*5	0.96985
						*x*6	0.93301	*x*6	0.98746	*x*6	0.85355	*x*6	0.67101
						*y*6	0.25000	*y*6	0.61126	*y*6	0.85355	*y*6	0.96985
								*x*7	0.89092	*x*7	1.00000	*x*7	0.93301
								*y*7	0.18826	*y*7	0.50000	*y*7	0.75000
										*x*8	0.85355	*x*8	0.99240
										*y*8	0.14645	*y*8	0.41318
												*x*9	0.82139
												*y*9	0.11698

10 Holes		11 Holes		12 Holes		13 Holes		14 Holes		15 Holes		16 Holes	
*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000
*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000
*x*2	0.20611	*x*2	0.22968	*x*2	0.25000	*x*2	0.26764	*x*2	0.28306	*x*2	0.29663	*x*2	0.30866
*y*2	0.09549	*y*2	0.07937	*y*2	0.06699	*y*2	0.05727	*y*2	0.04952	*y*2	0.04323	*y*2	0.03806
*x*3	0.02447	*x*3	0.04518	*x*3	0.06699	*x*3	0.08851	*x*3	0.10908	*x*3	0.12843	*x*3	0.14645
*y*3	0.34549	*y*3	0.29229	*y*3	0.25000	*y*3	0.21597	*y*3	0.18826	*y*3	0.16543	*y*3	0.14645
*x*4	0.02447	*x*4	0.00509	*x*4	0.00000	*x*4	0.00365	*x*4	0.01254	*x*4	0.02447	*x*4	0.03806
*y*4	0.65451	*y*4	0.57116	*y*4	0.50000	*y*4	0.43973	*y*4	0.38874	*y*4	0.34549	*y*4	0.30866
*x*5	0.20611	*x*5	0.12213	*x*5	0.06699	*x*5	0.03249	*x*5	0.01254	*x*5	0.00274	*x*5	0.00000
*y*5	0.90451	*y*5	0.82743	*y*5	0.75000	*y*5	0.67730	*y*5	0.61126	*y*5	0.55226	*y*5	0.50000
*x*6	0.50000	*x*6	0.35913	*x*6	0.25000	*x*6	0.16844	*x*6	0.10908	*x*6	0.06699	*x*6	0.03806
*y*6	1.00000	*y*6	0.97975	*y*6	0.93301	*y*6	0.87426	*y*6	0.81174	*y*6	0.75000	*y*6	0.69134
*x*7	0.79389	*x*7	0.64087	*x*7	0.50000	*x*7	0.38034	*x*7	0.28306	*x*7	0.20611	*x*7	0.14645
*y*7	0.90451	*y*7	0.97975	*y*7	1.00000	*y*7	0.98547	*y*7	0.95048	*y*7	0.90451	*y*7	0.85355
*x*8	0.97553	*x*8	0.87787	*x*8	0.75000	*x*8	0.61966	*x*8	0.50000	*x*8	0.39604	*x*8	0.30866
*y*8	0.65451	*y*8	0.82743	*y*8	0.93301	*y*8	0.98547	*y*8	1.00000	*y*8	0.98907	*y*8	0.96194
*x*9	0.97553	*x*9	0.99491	*x*9	0.93301	*x*9	0.83156	*x*9	0.71694	*x*9	0.60396	*x*9	0.50000
*y*9	0.34549	*y*9	0.57116	*y*9	0.75000	*y*9	0.87426	*y*9	0.95048	*y*9	0.98907	*y*9	1.00000
*x*10	0.79389	*x*10	0.95482	*x*10	1.00000	*x*10	0.96751	*x*10	0.89092	*x*10	0.79389	*x*10	0.69134
*y*10	0.09549	*y*10	0.29229	*y*10	0.50000	*y*10	0.67730	*y*10	0.81174	*y*10	0.90451	*y*10	0.96194
		*x*11	0.77032	*x*11	0.93801	*x*11	0.99635	*x*11	0.98746	*x*11	0.93301	*x*11	0.85355
		*y*11	0.07937	*y*11	0.25000	*y*11	0.43973	*y*11	0.61126	*y*11	0.75000	*y*11	0.85355
				*x*12	0.75000	*x*12	0.91149	*x*12	0.98746	*x*12	0.99726	*x*12	0.96194
				*y*12	0.06699	*y*12	0.21597	*y*12	0.38874	*y*12	0.55226	*y*12	0.69134
						*x*13	0.73236	*x*13	0.89092	*x*13	0.97553	*x*13	1.00000
						*y*13	0.05727	*y*13	0.18826	*y*13	0.34549	*y*13	0.50000
								*x*14	0.71694	*x*14	0.87157	*x*14	0.96194
								*y*14	0.04952	*y*14	0.16543	*y*14	0.30866
										*x*15	0.70337	*x*15	0.85355
										*y*15	0.04323	*y*15	0.14645
												*x*16	0.69134
												*y*16	0.03806

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles** (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

17 Holes		18 Holes		19 Holes		20 Holes		21 Holes		22 Holes		23 Holes	
*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000
*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000
*x*2	0.31938	*x*2	0.32899	*x*2	0.33765	*x*2	0.34549	*x*2	0.35262	*x*2	0.35913	*x*2	0.36510
*y*2	0.03376	*y*2	0.03015	*y*2	0.02709	*y*2	0.02447	*y*2	0.02221	*y*2	0.02025	*y*2	0.01854
*x*3	0.16315	*x*3	0.17861	*x*3	0.19289	*x*3	0.20611	*x*3	0.21834	*x*3	0.22968	*x*3	0.24021
*y*3	0.13050	*y*3	0.11698	*y*3	0.10543	*y*3	0.09549	*y*3	0.08688	*y*3	0.07937	*y*3	0.07279
*x*4	0.05242	*x*4	0.06699	*x*4	0.08142	*x*4	0.09549	*x*4	0.10908	*x*4	0.12213	*x*4	0.13458
*y*4	0.27713	*y*4	0.25000	*y*4	0.22653	*y*4	0.20611	*y*4	0.18826	*y*4	0.17257	*y*4	0.15872
*x*5	0.00213	*x*5	0.00760	*x*5	0.01530	*x*5	0.02447	*x*5	0.03456	*x*5	0.04518	*x*5	0.05606
*y*5	0.45387	*y*5	0.41318	*y*5	0.37726	*y*5	0.34549	*y*5	0.31733	*y*5	0.29229	*y*5	0.26997
*x*6	0.01909	*x*6	0.00760	*x*6	0.00171	*x*6	0.00000	*x*6	0.00140	*x*6	0.00509	*x*6	0.01046
*y*6	0.63683	*y*6	0.58682	*y*6	0.54129	*y*6	0.50000	*y*6	0.46263	*y*6	0.42884	*y*6	0.39827
*x*7	0.10099	*x*7	0.06699	*x*7	0.04211	*x*7	0.02447	*x*7	0.01254	*x*7	0.00509	*x*7	0.00117
*y*7	0.80132	*y*7	0.75000	*y*7	0.70085	*y*7	0.65451	*y*7	0.61126	*y*7	0.57116	*y*7	0.53412
*x*8	0.23678	*x*8	0.17861	*x*8	0.13214	*x*8	0.09549	*x*8	0.06699	*x*8	0.04518	*x*8	0.02887
*y*8	0.92511	*y*8	0.88302	*y*8	0.83864	*y*8	0.79389	*y*8	0.75000	*y*8	0.70771	*y*8	0.66744
*x*9	0.40813	*x*9	0.32899	*x*9	0.26203	*x*9	0.20611	*x*9	0.15991	*x*9	0.12213	*x*9	0.09152
*y*9	0.99149	*y*9	0.96985	*y*9	0.93974	*y*9	0.90451	*y*9	0.86653	*y*9	0.82743	*y*9	0.78834
*x*10	0.59187	*x*10	0.50000	*x*10	0.41770	*x*10	0.34549	*x*10	0.28306	*x*10	0.22968	*x*10	0.18446
*y*10	0.99149	*y*10	1.00000	*y*10	0.99318	*y*10	0.97553	*y*10	0.95048	*y*10	0.92063	*y*10	0.88786
*x*11	0.76322	*x*11	0.67101	*x*11	0.58230	*x*11	0.50000	*x*11	0.42548	*x*11	0.35913	*x*11	0.30080
*y*11	0.92511	*y*11	0.96985	*y*11	0.99318	*y*11	1.00000	*y*11	0.99442	*y*11	0.97975	*y*11	0.95861
*x*12	0.89901	*x*12	0.82139	*x*12	0.73797	*x*12	0.65451	*x*12	0.57452	*x*12	0.50000	*x*12	0.43192
*y*12	0.80132	*y*12	0.88302	*y*12	0.93974	*y*12	0.97553	*y*12	0.99442	*y*12	1.00000	*y*12	0.99534
*x*13	0.98091	*x*13	0.93301	*x*13	0.86786	*x*13	0.79389	*x*13	0.71694	*x*13	0.64087	*x*13	0.56808
*y*13	0.63683	*y*13	0.75000	*y*13	0.83864	*y*13	0.90451	*y*13	0.95048	*y*13	0.97975	*y*13	0.99534
*x*14	0.99787	*x*14	0.99240	*x*14	0.95789	*x*14	0.90451	*x*14	0.84009	*x*14	0.77032	*x*14	0.69920
*y*14	0.45387	*y*14	0.58682	*y*14	0.70085	*y*14	0.79389	*y*14	0.86653	*y*14	0.92063	*y*14	0.95861
*x*15	0.94758	*x*15	0.99240	*x*15	0.99829	*x*15	0.97553	*x*15	0.93301	*x*15	0.87787	*x*15	0.81554
*y*15	0.27713	*y*15	0.41318	*y*15	0.54129	*y*15	0.65451	*y*15	0.75000	*y*15	0.82743	*y*15	0.88786
*x*16	0.83685	*x*16	0.93301	*x*16	0.98470	*x*16	1.00000	*x*16	0.98746	*x*16	0.95482	*x*16	0.90848
*y*16	0.13050	*y*16	0.25000	*y*16	0.37726	*y*16	0.50000	*y*16	0.61126	*y*16	0.70771	*y*16	0.78834
*x*17	0.68062	*x*17	0.82139	*x*17	0.91858	*x*17	0.97553	*x*17	0.99860	*x*17	0.99491	*x*17	0.97113
*y*17	0.03376	*y*17	0.11698	*y*17	0.22658	*y*17	0.34549	*y*17	0.46263	*y*17	0.57116	*y*17	0.66744
		*x*18	0.67101	*x*18	0.80711	*x*18	0.90451	*x*18	0.96544	*x*18	0.99491	*x*18	0.99883
		*y*18	0.03015	*y*18	0.10543	*y*18	0.20611	*y*18	0.31733	*y*18	0.42884	*y*18	0.53412
				*x*19	0.66235	*x*19	0.79389	*x*19	0.89092	*x*19	0.95482	*x*19	0.98954
				*y*19	0.02709	*y*19	0.09549	*y*19	0.18826	*y*19	0.29229	*y*19	0.39827
						*x*20	0.65451	*x*20	0.78166	*x*20	0.87787	*x*20	0.94394
						*y*20	0.02447	*y*20	0.08688	*y*20	0.17257	*y*20	0.26997
								*x*21	0.64738	*x*21	0.77032	*x*21	0.86542
								*y*21	0.02221	*y*21	0.07937	*y*21	0.15872
										*x*22	0.64087	*x*22	0.75979
										*y*22	0.02025	*y*22	0.07279
												*x*23	0.63490
												*y*23	0.01854

24Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000	*x*1	0.50000
*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000	*y*1	0.00000
*x*2	0.37059	*x*2	0.37566	*x*2	0.38034	*x*2	0.38469	*x*2	0.38874
*y*2	0.01704	*y*2	0.01571	*y*2	0.01453	*y*2	0.01348	*y*2	0.01254
*x*3	0.25000	*x*3	0.25912	*x*3	0.26764	*x*3	0.27560	*x*3	0.28306

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles** (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

24Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*y*3	0.06699	*y*3	0.06185	*y*3	0.05727	*y*3	0.05318	*y*3	0.04952
*x*4	0.14645	*x*4	0.15773	*x*4	0.16844	*x*4	0.17861	*x*4	0.18826
*y*4	0.14645	*y*4	0.13552	*y*4	0.12574	*y*4	0.11698	*y*4	0.10908
*x*5	0.06699	*x*5	0.07784	*x*5	0.08851	*x*5	0.09894	*x*5	0.10908
*y*5	0.25000	*y*5	0.23209	*y*5	0.21597	*y*5	0.20142	*y*5	0.18826
*x*6	0.01704	*x*6	0.02447	*x*6	0.03249	*x*6	0.04089	*x*6	0.04952
*y*6	0.37059	*y*6	0.34549	*y*6	0.32270	*y*6	0.30196	*y*6	0.28306
*x*7	0.00000	*x*7	0.00099	*x*7	0.00365	*x*7	0.00760	*x*7	0.01254
*y*7	0.50000	*y*7	0.46860	*y*7	0.43973	*y*7	0.41318	*y*7	0.38874
*x*8	0.01704	*x*8	0.00886	*x*8	0.00365	*x*8	0.00085	*x*8	0.00000
*y*8	0.62941	*y*8	0.59369	*y*8	0.56027	*y*8	0.52907	*y*8	0.50000
*x*9	0.06699	*x*9	0.04759	*x*9	0.03249	*x*9	0.02101	*x*9	0.01254
*y*9	0.75000	*y*9	0.71289	*y*9	0.67730	*y*9	0.64340	*y*9	0.61126
*x*10	0.14645	*x*10	0.11474	*x*10	0.08851	*x*10	0.06699	*x*10	0.04952
*y*10	0.85355	*y*10	0.81871	*y*10	0.78403	*y*10	0.75000	*y*10	0.71694
*x*11	0.25000	*x*11	0.20611	*x*11	0.16844	*x*11	0.13631	*x*11	0.10908
*y*11	0.93301	*y*11	0.90451	*y*11	0.87426	*y*11	0.84312	*y*11	0.81174
*x*12	0.37059	*x*12	0.31594	*x*12	0.26764	*x*12	0.22525	*x*12	0.18826
*y*12	0.98296	*y*12	0.96489	*y*12	0.94273	*y*12	0.91774	*y*12	0.89092
*x*13	0.50000	*x*13	0.43733	*x*13	0.38034	*x*13	0.32899	*x*13	0.28306
*y*13	1.00000	*y*13	0.99606	*y*13	0.98547	*y*13	0.96985	*y*13	0.95048
*x*14	0.62941	*x*14	0.56267	*x*14	0.50000	*x*14	0.44195	*x*14	0.38874
*y*14	0.98296	*y*14	0.99606	*y*14	1.00000	*y*14	0.99662	*y*14	0.98746
*x*15	0.75000	*x*15	0.68406	*x*15	0.61966	*x*15	0.55805	*x*15	0.50000
*y*15	0.93301	*y*15	0.96489	*y*15	0.98547	*y*15	0.99662	*y*15	1.00000
*x*16	0.85355	*x*16	0.79389	*x*16	0.73236	*x*16	0.67101	*x*16	0.61126
*y*16	0.85355	*y*16	0.90451	*y*16	0.94273	*y*16	0.96985	*y*16	0.98746
*x*17	0.93301	*x*17	0.88526	*x*17	0.83156	*x*17	0.77475	*x*17	0.71694
*y*17	0.75000	*y*17	0.81871	*y*17	0.87426	*y*17	0.91774	*y*17	0.95048
*x*18	0.98296	*x*18	0.95241	*x*18	0.91149	*x*18	0.86369	*x*18	0.81174
*y*18	0.62941	*y*18	0.71289	*y*18	0.78403	*y*18	0.84312	*y*18	0.89092
*x*19	1.00000	*x*19	0.99114	*x*19	0.96751	*x*19	0.93301	*x*19	0.89092
*y*19	0.50000	*y*19	0.59369	*y*19	0.67730	*y*19	0.75000	*y*19	0.81174
*x*20	0.98296	*x*20	0.99901	*x*20	0.99635	*x*20	0.97899	*x*20	0.95048
*y*20	0.37059	*y*20	0.46860	*y*20	0.56027	*y*20	0.64340	*y*20	0.71694
*x*21	0.93301	*x*21	0.97553	*x*21	0.99635	*x*21	0.99915	*x*21	0.98746
*y*21	0.25000	*y*21	0.34549	*y*21	0.43973	*y*21	0.52907	*y*21	0.61126
*x*22	0.85355	*x*22	0.92216	*x*22	0.96751	*x*22	0.99240	*x*22	1.00000
*y*22	0.14645	*y*22	0.23209	*y*22	0.32270	*y*22	0.41318	*y*22	0.50000
*x*23	0.75000	*x*23	0.84227	*x*23	0.91149	*x*23	0.95911	*x*23	0.98746
*y*23	0.6699	*y*23	0.13552	*y*23	0.21597	*y*23	0.30196	*y*23	0.38874
*x*24	0.62941	*x*24	0.74088	*x*24	0.83156	*x*24	0.90106	*x*24	0.95048
*y*24	0.01704	*y*24	0.06185	*y*24	0.12574	*y*24	0.20142	*y*24	0.28306
		*x*25	0.62434	*x*25	0.73236	*x*25	0.82139	*x*25	0.89092
		*y*25	0.01571	*y*25	0.05727	*y*25	0.11698	*y*25	0.18826
				*x*26	0.61966	*x*26	0.72440	*x*26	0.81174
				*y*26	0.01453	*y*26	0.05318	*y*26	0.10908
						*x*27	0.61531	*x*27	0.71694
						*y*27	0.01348	*y*27	0.04952
								*x*28	0.61126
								*y*28	0.01254

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles (English or Metric Units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, y are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

3 Holes		4 Holes		5 Holes		6 Holes		7 Holes		8 Holes		9 Holes	
*x*1	0.06699	*x*1	0.14645	*x*1	0.20611	*x*1	0.25000	*x*1	0.28306	*x*1	0.30866	*x*1	0.32899
*y*1	0.25000	*y*1	0.14645	*y*1	0.09549	*y*1	0.06699	*y*1	0.04952	*y*1	0.03806	*y*1	0.03015
*x*2	0.50000	*x*2	0.14645	*x*2	0.02447	*x*2	0.00000	*x*2	0.01254	*x*2	0.03806	*x*2	0.06699
*y*2	1.00000	*y*2	0.85355	*y*2	0.65451	*y*2	0.50000	*y*2	0.38874	*y*2	0.30866	*y*2	0.25000
*x*3	0.93301	*x*3	0.85355	*x*3	0.50000	*x*3	0.25000	*x*3	0.10908	*x*3	0.03806	*x*3	0.00760
*y*3	0.25000	*y*3	0.85355	*y*3	1.00000	*y*3	0.93301	*y*3	0.81174	*y*3	0.69134	*y*3	0.58682
		*x*4	0.85355	*x*4	0.97553	*x*4	0.75000	*x*4	0.50000	*x*4	0.30866	*x*4	0.17861
		*y*4	0.14645	*y*4	0.65451	*y*4	0.93301	*y*4	1.00000	*y*4	0.96194	*y*4	0.88302
				*x*5	0.79389	*x*5	1.00000	*x*5	0.89092	*x*5	0.69134	*x*5	0.50000
				*y*5	0.09549	*y*5	0.50000	*y*5	0.81174	*y*5	0.96194	*y*5	1.00000
						*x*6	0.75000	*x*6	0.98746	*x*6	0.96194	*x*6	0.82139
						*y*6	0.06699	*y*6	0.38874	*y*6	0.69134	*y*6	0.88302
								*x*7	0.71694	*x*7	0.96194	*x*7	0.99240
								*y*7	0.04952	*y*7	0.30866	*y*7	0.58682
										*x*8	0.69134	*x*8	0.93301
										*y*8	0.03806	*y*8	0.25000
												*x*9	0.67101
												*y*9	0.03015

10 Holes		11 Holes		12 Holes		13 Holes		14 Holes		15 Holes		16 Holes	
*x*1	0.34549	*x*1	0.35913	*x*1	0.37059	*x*1	0.38034	*x*1	0.38874	*x*1	0.39604	*x*1	0.40245
*y*1	0.02447	*y*1	0.02025	*y*1	0.01704	*y*1	0.01453	*y*1	0.01254	*y*1	0.01093	*y*1	0.00961
*x*2	0.09549	*x*2	0.12213	*x*2	0.14645	*x*2	0.16844	*x*2	0.18826	*x*2	0.20611	*x*2	0.22221
*y*2	0.20611	*y*2	0.17257	*y*2	0.14645	*y*2	0.12574	*y*2	0.10908	*y*2	0.09549	*y*2	0.08427
*x*3	0.00000	*x*3	0.00509	*x*3	0.01704	*x*3	0.03249	*x*3	0.04952	*x*3	0.06699	*x*3	0.08427
*y*3	0.50000	*y*3	0.42884	*y*3	0.37059	*y*3	0.32270	*y*3	0.28306	*y*3	0.25000	*y*3	0.22221
*x*4	0.09549	*x*4	0.04518	*x*4	0.01704	*x*4	0.00365	*x*4	0.00000	*x*4	0.00274	*x*4	0.00961
*y*4	0.79389	*y*4	0.70771	*y*4	0.62941	*y*4	0.56027	*y*4	0.50000	*y*4	0.44774	*y*4	0.40245
*x*5	0.34549	*x*5	0.22968	*x*5	0.14645	*x*5	0.08851	*x*5	0.04952	*x*5	0.02447	*x*5	0.00961
*y*5	0.97553	*y*5	0.92063	*y*5	0.85355	*y*5	0.78403	*y*5	0.71694	*y*5	0.65451	*y*5	0.59755
*x*6	0.65451	*x*6	0.50000	*x*6	0.37059	*x*6	0.26764	*x*6	0.18826	*x*6	0.12843	*x*6	0.08427
*y*6	0.97553	*y*6	1.00000	*y*6	0.98296	*y*6	0.94273	*y*6	0.89092	*y*6	0.83457	*y*6	0.77779
*x*7	0.90451	*x*7	0.77032	*x*7	0.62941	*x*7	0.50000	*x*7	0.38874	*x*7	0.29663	*x*7	0.22221
*y*7	0.79389	*y*7	0.92063	*y*7	0.98296	*y*7	1.00000	*y*7	0.98746	*y*7	0.95677	*y*7	0.91573
*x*8	1.00000	*x*8	0.95482	*x*8	0.85355	*x*8	0.73236	*x*8	0.61126	*x*8	0.50000	*x*8	0.40245
*y*8	0.50000	*y*8	0.70771	*y*8	0.85355	*y*8	0.94273	*y*8	0.98746	*y*8	1.00000	*y*8	0.99039
*x*9	0.90451	*x*9	0.99491	*x*9	0.98296	*x*9	0.91149	*x*9	0.81174	*x*9	0.70337	*x*9	0.59755
*y*9	0.20611	*y*9	0.42884	*y*9	0.62941	*y*9	0.78403	*y*9	0.89092	*y*9	0.95677	*y*9	0.99039
*x*10	0.65451	*x*10	0.87787	*x*10	0.98296	*x*10	0.99635	*x*10	0.95048	*x*10	0.87157	*x*10	0.77779
*y*10	0.02447	*y*10	0.17257	*y*10	0.37059	*y*10	0.56027	*y*10	0.71694	*y*10	0.83457	*y*10	0.91573
		*x*11	0.64087	*x*11	0.85355	*x*11	0.96751	*x*11	1.00000	*x*11	0.97553	*x*11	0.91573
		*y*11	0.02025	*y*11	0.14645	*y*11	0.32270	*y*11	0.50000	*y*11	0.65451	*y*11	0.77779
				*x*12	0.62941	*x*12	0.83156	*x*12	0.95048	*x*12	0.99726	*x*12	0.99039
				*y*12	0.01704	*y*12	0.12574	*y*12	0.28306	*y*12	0.44774	*y*12	0.59755
						*x*13	0.61966	*x*13	0.81174	*x*13	0.93301	*x*13	0.99039
						*y*13	0.01453	*y*13	0.10908	*y*13	0.25000	*y*13	0.40245
								*x*14	0.61126	*x*14	0.79389	*x*14	0.91573
								*y*14	0.01254	*y*14	0.09549	*y*14	0.22221
										*x*15	0.60396	*x*15	0.77779
										*y*15	0.01093	*y*15	0.08427
												*x*16	0.59755
												*y*16	0.00961

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles** (English or Metric Units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

17 Holes		18 Holes		19 Holes		20 Holes		21 Holes		22 Holes		23 Holes	
*x*1	0.40813	*x*1	0.41318	*x*1	0.41770	*x*1	0.42178	*x*1	0.42548	*x*1	0.42884	*x*1	0.43192
*y*1	0.00851	*y*1	0.00760	*y*1	0.00682	*y*1	0.00616	*y*1	0.00558	*y*1	0.00509	*y*1	0.00466
*x*2	0.23678	*x*2	0.25000	*x*2	0.26203	*x*2	0.27300	*x*2	0.28306	*x*2	0.29229	*x*2	0.30080
*y*2	0.07489	*y*2	0.06699	*y*2	0.06026	*y*2	0.05450	*y*2	0.04952	*y*2	0.04518	*y*2	0.04139
*x*3	0.10099	*x*3	0.11698	*x*3	0.13214	*x*3	0.14645	*x*3	0.15991	*x*3	0.17257	*x*3	0.18446
*y*3	0.19868	*y*3	0.17861	*y*3	0.16136	*y*3	0.14645	*y*3	0.13347	*y*3	0.12213	*y*3	0.11214
*x*4	0.01909	*x*4	0.03015	*x*4	0.04211	*x*4	0.05450	*x*4	0.06699	*x*4	0.07937	*x*4	0.09152
*y*4	0.36317	*y*4	0.32899	*y*4	0.29915	*y*4	0.27300	*y*4	0.25000	*y*4	0.22968	*y*4	0.21166
*x*5	0.00213	*x*5	0.00000	*x*5	0.00171	*x*5	0.00616	*x*5	0.01254	*x*5	0.02025	*x*5	0.02887
*y*5	0.54613	*y*5	0.50000	*y*5	0.45871	*y*5	0.42178	*y*5	0.38874	*y*5	0.35913	*y*5	0.33256
*x*6	0.05242	*x*6	0.03015	*x*6	0.01530	*x*6	0.00616	*x*6	0.00140	*x*6	0.00000	*x*6	0.00117
*y*6	0.72287	*y*6	0.67101	*y*6	0.62274	*y*6	0.57822	*y*6	0.53737	*y*6	0.50000	*y*6	0.46588
*x*7	0.16315	*x*7	0.11698	*x*7	0.08142	*x*7	0.05450	*x*7	0.03456	*x*7	0.02025	*x*7	0.01046
*y*7	0.86950	*y*7	0.82139	*y*7	0.77347	*y*7	0.72700	*y*7	0.68267	*y*7	0.64087	*y*7	0.60173
*x*8	0.31938	*x*8	0.25000	*x*8	0.19289	*x*8	0.14645	*x*8	0.10908	*x*8	0.07937	*x*8	0.05606
*y*8	0.96624	*y*8	0.93301	*y*8	0.89457	*y*8	0.85355	*y*8	0.81174	*y*8	0.77032	*y*8	0.73003
*x*9	0.50000	*x*9	0.41318	*x*9	0.33765	*x*9	0.27300	*x*9	0.21834	*x*9	0.17257	*x*9	0.13458
*y*9	1.00000	*y*9	0.99240	*y*9	0.97291	*y*9	0.94550	*y*9	0.91312	*y*9	0.87787	*y*9	0.84128
*x*10	0.68062	*x*10	0.58682	*x*10	0.50000	*x*10	0.42178	*x*10	0.35262	*x*10	0.29229	*x*10	0.24021
*y*10	0.96624	*y*10	0.99240	*y*10	1.00000	*y*10	0.99384	*y*10	0.97779	*y*10	0.95482	*y*10	0.92721
*x*11	0.83685	*x*11	0.75000	*x*11	0.66235	*x*11	0.57822	*x*11	0.50000	*x*11	0.42884	*x*11	0.36510
*y*11	0.86950	*y*11	0.93301	*y*11	0.97291	*y*11	0.99384	*y*11	1.00000	*y*11	0.99491	*y*11	0.98146
*x*12	0.94758	*x*12	0.88302	*x*12	0.80711	*x*12	0.72700	*x*12	0.64738	*x*12	0.57116	*x*12	0.50000
*y*12	0.72287	*y*12	0.82139	*y*12	0.89457	*y*12	0.94550	*y*12	0.97779	*y*12	0.99491	*y*12	1.00000
*x*13	0.99787	*x*13	0.96985	*x*13	0.91858	*x*13	0.85355	*x*13	0.78166	*x*13	0.70771	*x*13	0.63490
*y*13	0.54613	*y*13	0.67101	*y*13	0.77347	*y*13	0.85355	*y*13	0.91312	*y*13	0.95482	*y*13	0.98146
*x*14	0.98091	*x*14	1.00000	*x*14	0.98470	*x*14	0.94550	*x*14	0.89092	*x*14	0.82743	*x*14	0.75979
*y*14	0.36317	*y*14	0.50000	*y*14	0.62274	*y*14	0.72700	*y*14	0.81174	*y*14	0.87787	*y*14	0.92721
*x*15	0.89901	*x*15	0.96985	*x*15	0.99829	*x*15	0.99384	*x*15	0.96544	*x*15	0.92063	*x*15	0.86542
*y*15	0.19868	*y*15	0.32899	*y*15	0.45871	*y*15	0.57822	*y*15	0.68267	*y*15	0.77032	*y*15	0.84128
*x*16	0.76322	*x*16	0.88302	*x*16	0.95789	*x*16	0.99384	*x*16	0.99860	*x*16	0.97975	*x*16	0.94394
*y*16	0.07489	*y*16	0.17861	*y*16	0.29915	*y*16	0.42178	*y*16	0.53737	*y*16	0.64087	*y*16	0.73003
*x*17	0.59187	*x*17	0.75000	*x*17	0.86786	*x*17	0.94550	*x*17	0.98746	*x*17	1.00000	*x*17	0.98954
*y*17	0.00851	*y*17	0.06699	*y*17	0.16136	*y*17	0.27300	*y*17	0.38874	*y*17	0.50000	*y*17	0.60173
		*x*18	0.58682	*x*18	0.73797	*x*18	0.85355	*x*18	0.93301	*x*18	0.97975	*x*18	0.99883
		*y*18	0.00760	*y*18	0.06026	*y*18	0.14645	*y*18	0.25000	*y*18	0.35913	*y*18	0.46588
				*x*19	0.58230	*x*19	0.72700	*x*19	0.84009	*x*19	0.92063	*x*19	0.97113
				*y*19	0.00682	*y*19	0.05450	*y*19	0.13347	*y*19	0.22968	*y*19	0.33256
						*x*20	0.57822	*x*20	0.71694	*x*20	0.82743	*x*20	0.90848
						*y*20	0.00616	*y*20	0.04952	*y*20	0.12213	*y*20	0.21166
								*x*21	0.57452	*x*21	0.70771	*x*21	0.81554
								*y*21	0.00558	*y*21	0.04518	*y*21	0.11214
										*x*22	0.57116	*x*22	0.69920
										*y*22	0.00509	*y*22	0.04139
												*x*23	0.56808
												*y*23	0.00466

24 Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*x*1	0.43474	*x*1	0.43733	*x*1	0.43973	*x*1	0.44195	*x*1	0.44402
*y*1	0.00428	*y*1	0.00394	*y*1	0.00365	*y*1	0.00338	*y*1	0.00314
*x*2	0.30866	*x*2	0.31594	*x*2	0.32270	*x*2	0.32899	*x*2	0.33486
*y*2	0.03806	*y*2	0.03511	*y*2	0.03249	*y*2	0.03015	*y*2	0.02806
*x*3	0.19562	*x*3	0.20611	*x*3	0.21597	*x*3	0.22525	*x*3	0.23398
*y*3	0.10332	*y*3	0.09549	*y*3	0.08851	*y*3	0.08226	*y*3	0.07664

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles** (English or Metric Units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

24 Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*x*4	0.10332	*x*4	0.11474	*x*4	0.12574	*x*4	0.13631	*x*4	0.14645
*y*4	0.19562	*y*4	0.18129	*y*4	0.16844	*y*4	0.15688	*y*4	0.14645
*x*5	0.03806	*x*5	0.04759	*x*5	0.05727	*x*5	0.06699	*x*5	0.07664
*y*5	0.30866	*y*5	0.28711	*y*5	0.26764	*y*5	0.25000	*y*5	0.23398
*x*6	0.00428	*x*6	0.00886	*x*6	0.01453	*x*6	0.02101	*x*6	0.02806
*y*6	0.43474	*y*6	0.40631	*y*6	0.38034	*y*6	0.35660	*y*6	0.33486
*x*7	0.00428	*x*7	0.00099	*x*7	0.00000	*x*7	0.00085	*x*7	0.00314
*y*7	0.56526	*y*7	0.53140	*y*7	0.50000	*y*7	0.47093	*y*7	0.44402
*x*8	0.03806	*x*8	0.02447	*x*8	0.01453	*x*8	0.00760	*x*8	0.00314
*y*8	0.69134	*y*8	0.65451	*y*8	0.61966	*y*8	0.58682	*y*8	0.55598
*x*9	0.10332	*x*9	0.07784	*x*9	0.05727	*x*9	0.04089	*x*9	0.02806
*y*9	0.80438	*y*9	0.76791	*y*9	0.73236	*y*9	0.69804	*y*9	0.66514
*x*10	0.19562	*x*10	0.15773	*x*10	0.12574	*x*10	0.09894	*x*10	0.07664
*y*10	0.89668	*y*10	0.86448	*y*10	0.83156	*y*10	0.79858	*y*10	0.76602
*x*11	0.30866	*x*11	0.25912	*x*11	0.21597	*x*11	0.17861	*x*11	0.14645
*y*11	0.96194	*y*11	0.93815	*y*11	0.91149	*y*11	0.88302	*y*11	0.85355
*x*12	0.43474	*x*12	0.37566	*x*12	0.32270	*x*12	0.27560	*x*12	0.23398
*y*12	0.99572	*y*12	0.98429	*y*12	0.96751	*y*12	0.94682	*y*12	0.92336
*x*13	0.56526	*x*13	0.50000	*x*13	0.43973	*x*13	0.38469	*x*13	0.33486
*y*13	0.99572	*y*13	1.00000	*y*13	0.99635	*y*13	0.98652	*y*13	0.97194
*x*14	0.69134	*x*14	0.62434	*x*14	0.56027	*x*14	0.50000	*x*14	0.44402
*y*14	0.96194	*y*14	0.98429	*y*14	0.99635	*y*14	1.00000	*y*14	0.99686
*x*15	0.80438	*x*15	0.74088	*x*15	0.67730	*x*15	0.61531	*x*15	0.55598
*y*15	0.89668	*y*15	0.93815	*y*15	0.96751	*y*15	0.98652	*y*15	0.99686
*x*16	0.89668	*x*16	0.84227	*x*16	0.78403	*x*16	0.72440	*x*16	0.66514
*y*16	0.80438	*y*16	0.86448	*y*16	0.91149	*y*16	0.94682	*y*16	0.97194
*x*17	0.96194	*x*17	0.92216	*x*17	0.87426	*x*17	0.82139	*x*17	0.76602
*y*17	0.69134	*y*17	0.76791	*y*17	0.83156	*y*17	0.88302	*y*17	0.92336
*x*18	0.99572	*x*18	0.97553	*x*18	0.94273	*x*18	0.90106	*x*18	0.85355
*y*18	0.56526	*y*18	0.65451	*y*18	0.73236	*y*18	0.79858	*y*18	0.85355
*x*19	0.99572	*x*19	0.99901	*x*19	0.98547	*x*19	0.95911	*x*19	0.92336
*y*19	0.43474	*y*19	0.53140	*y*19	0.61966	*y*19	0.69804	*y*19	0.76602
*x*20	0.96194	*x*20	0.99114	*x*20	1.00000	*x*20	0.99240	*x*20	0.97194
*y*20	0.30866	*y*20	0.40631	*y*20	0.50000	*y*20	0.58682	*y*20	0.66514
*x*21	0.89668	*x*21	0.95241	*x*21	0.98547	*x*21	0.99915	*x*21	0.99686
*y*21	0.19562	*y*21	0.28711	*y*21	0.38034	*y*21	0.47093	*y*21	0.55598
*x*22	0.80438	*x*22	0.88526	*x*22	0.94273	*x*22	0.97899	*x*22	0.99686
*y*22	0.10332	*y*22	0.18129	*y*22	0.26764	*y*22	0.35660	*y*22	0.44402
*x*23	0.69134	*x*23	0.79389	*x*23	0.87426	*x*23	0.93301	*x*23	0.97194
*y*23	0.03806	*y*23	0.09549	*y*23	0.16844	*y*23	0.25000	*y*23	0.33486
*x*24	0.56526	*x*24	0.68406	*x*24	0.78403	*x*24	0.86369	*x*24	0.92336
*y*24	0.00428	*y*24	0.03511	*y*24	0.08851	*y*24	0.15688	*y*24	0.23398
		*x*25	0.56267	*x*25	0.67730	*x*25	0.77475	*x*25	0.85355
		*y*25	0.00394	*y*25	0.03249	*y*25	0.08226	*y*25	0.14645
				*x*26	0.56027	*x*26	0.67101	*x*26	0.76602
				*y*26	0.00365	*y*26	0.03015	*y*26	0.07664
						*x*27	0.55805	*x*27	0.66514
						*y*27	0.00338	*y*27	0.02806
								*x*28	0.55598
								*y*28	0.00314

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles, Central Coordinates (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

3 Holes		4 Holes		5 Holes		6 Holes		7 Holes		8 Holes		9 Holes	
*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000
*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000
*x*2	−0.43301	*x*2	−0.50000	*x*2	−0.47553	*x*2	−0.43301	*x*2	−0.39092	*x*2	−0.35355	*x*2	−0.32139
*y*2	+0.25000	*y*2	0.00000	*y*2	−0.15451	*y*2	−0.25000	*y*2	−0.31174	*y*2	−0.35355	*y*2	−0.38302
*x*3	+0.43301	*x*3	0.00000	*x*3	−0.29389	*x*3	−0.43301	*x*3	−0.48746	*x*3	−0.50000	*x*3	−0.49240
*y*3	+0.25000	*y*3	+0.50000	*y*3	+0.40451	*y*3	+0.25000	*y*3	+0.11126	*y*3	0.00000	*y*3	−0.08682
		*x*4	+0.50000	*x*4	+0.29389	*x*4	0.00000	*x*4	−0.21694	*x*4	−0.35355	*x*4	−0.43301
		*y*4	0.00000	*y*4	+0.40451	*y*4	+0.50000	*y*4	+0.45048	*y*4	+0.35355	*y*4	+0.25000
				*x*5	+0.47553	*x*5	+0.43301	*x*5	+0.21694	*x*5	0.00000	*x*5	−0.17101
				*y*5	−0.15451	*y*5	+0.25000	*y*5	+0.45048	*y*5	+0.50000	*y*5	+0.46985
						*x*6	+0.43301	*x*6	+0.48746	*x*6	+0.35355	*x*6	+0.17101
						*y*6	−0.25000	*y*6	+0.11126	*y*6	+0.35355	*y*6	+0.46985
								*x*7	+0.39092	*x*7	+0.50000	*x*7	+0.43301
								*y*7	−0.31174	*y*7	0.00000	*y*7	+0.25000
										*x*8	+0.35355	*x*8	+0.49240
										*y*8	−0.35355	*x*8	−0.08682
												*x*9	+0.32139
												*y*9	−0.38302

10 Holes		11 Holes		12 Holes		13 Holes		14 Holes		15 Holes		16 Holes	
*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000
*y*1	−0.50000	*y*1	−0.5000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000
*x*2	−0.29389	*x*2	−0.27032	*x*2	−0.25000	*x*2	−0.23236	*x*2	−0.21694	*x*2	−0.20337	*x*2	−0.19134
*y*2	−0.40451	*y*2	−0.42063	*y*2	−0.43301	*y*2	−0.44273	*y*2	−0.45048	*y*2	−0.45677	*y*2	−0.46194
*x*3	−0.47553	*x*3	−0.45482	*x*3	−0.43301	*x*3	−0.41149	*x*3	−0.39092	*x*3	−0.37157	*x*3	−0.35355
*y*3	−0.15451	*y*3	−0.20771	*y*3	−0.25000	*y*3	−2.28403	*y*3	−0.31174	*y*3	−0.33457	*y*3	−0.35355
*x*4	−0.47553	*x*4	−0.49491	*x*4	−0.50000	*x*4	−0.49635	*x*4	−0.48746	*x*4	−0.47553	*x*4	−0.46194
*y*4	+0.15451	*y*4	+0.07116	*y*4	0.00000	*y*4	−0.06027	*y*4	−0.11126	*y*4	−0.15451	*y*4	−0.19134
*x*5	−0.29389	*x*5	−0.37787	*x*5	−0.43301	*x*5	−0.46751	*x*5	−0.48746	*x*5	−0.49726	*x*5	−0.50000
*y*5	+0.40451	*y*5	+0.32743	*y*5	+0.25000	*y*5	+0.17730	*y*5	+0.11126	*y*5	+0.05226	*y*5	0.00000
*x*6	0.00000	*x*6	−0.14087	*x*6	−0.25000	*x*6	− 0.33156	*x*6	−0.39092	*x*6	−0.43301	*x*6	−0.46194
*y*6	+0.50000	*y*6	+0.47975	*y*6	+0.43301	*y*6	+0.37426	*y*6	+0.31174	*y*6	+0.25000	*y*6	+0.19134
*x*7	+0.29389	*x*7	+0.14087	*x*7	0.00000	*x*7	−0.11966	*x*7	−0.21694	*x*7	−0.29389	*x*7	−0.35355
*y*7	+0.40451	*y*7	+0.47975	*y*7	+0.50000	*y*7	+0.48547	*y*7	+0.45048	*y*7	+0.40451	*y*7	+0.35355
*x*8	+0.47553	*x*8	+0.37787	*x*8	+0.25000	*x*8	+0.11966	*x*8	0.00000	*x*8	−0.10396	*x*8	−0.19134
*y*8	+0.15451	*y*8	+0.32743	*y*8	+0.43301	*y*8	+0.48547	*y*8	+0.50000	*y*8	+0.48907	*y*8	+0.46194
*x*9	+0.47553	*x*9	+0.49491	*x*9	+0.43301	*x*9	+0.33156	*x*9	+0.21694	*x*9	+0.10396	*x*9	0.00000
*y*9	−0.15451	*y*9	+0.07116	*y*9	+0.25000	*y*9	+0.37426	*y*9	+0.45048	*y*9	+0.48907	*y*9	+0.50000
*x*10	+0.29389	*x*10	+0.45482	*x*10	+0.50000	*x*10	+0.46751	*x*10	+0.39092	*x*10	+0.29389	*x*10	+0.19134
*y*10	−0.40451	*y*10	−0.20771	*y*10	0.00000	*y*10	+0.17730	*y*10	+0.31174	*y*10	+0.40451	*y*10	+0.46194
		*x*11	+0.27032	*x*11	+0.43301	*x*11	+0.49635	*x*11	+0.48746	*x*11	+0.43301	*x*11	+0.35355
		*y*11	−0.42063	*y*11	−0.25000	*y*11	−0.06027	*y*11	+0.11126	*y*11	+0.25000	*y*11	+0.35355
				*x*12	+0.25000	*x*12	+0.41149	*x*12	+0.48746	*x*12	+0.49726	*x*12	+0.46194
				*y*12	−0.43301	*y*12	−0.28403	*y*12	−0.11126	*y*12	+0.05226	*y*12	+0.19134
						*x*13	+0.23236	*x*13	+0.39092	*x*13	+0.47553	*x*13	+0.50000
						*y*13	−0.44273	*y*13	−0.31174	*y*13	−0.15451	*y*13	0.00000
								*x*14	+0.21694	*x*14	+0.37157	*x*14	+0.46194
								*y*14	−0.45048	*y*14	−0.33457	*y*14	−0.19134
										*x*15	+0.20337	*x*15	+0.35355
										*y*15	−0.45677	*y*15	−0.35355
												*x*16	+0.19134
												*y*16	−0.46194

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles, Central Coordinates** (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

17 Holes		18 Holes		19 Holes		20 Holes		21 Holes		22 Holes		23 Holes	
*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.000000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000
*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000
*x*2	−0.18062	*x*2	−0.17101	*x*2	−0.16235	*x*2	−0.15451	*x*2	−0.14738	*x*2	−0.14087	*x*2	−0.13490
*y*2	−0.46624	*y*2	−0.46985	*y*2	−0.47291	*y*2	−0.47553	*y*2	−0.47779	*y*2	−0.47975	*y*2	−0.48146
*x*3	−0.33685	*x*3	+0.32139	*x*3	−0.30711	*x*3	−0.29389	*x*3	−0.28166	*x*3	−0.27032	*x*3	−0.25979
*y*3	−0.36950	*y*3	−0.38302	*y*3	−0.39457	*y*3	−0.40451	*y*3	−0.41312	*y*3	−0.42063	*y*3	−0.42721
*x*4	−0.44758	*x*4	−0.43301	*x*4	−0.41858	*x*4	−0.40451	*x*4	−0.39092	*x*4	−0.37787	*x*4	−0.36542
*y*4	−0.22287	*y*4	−0.25000	*y*4	−0.27347	*y*4	−0.29389	*y*4	−0.31174	*y*4	−0.32743	*y*4	−0.34128
*x*5	−0.49787	*x*5	−0.49240	*x*5	−0.48470	*x*5	−0.47553	*x*5	−.046544	*x*5	−0.45482	*x*5	−0.44394
*y*5	−0.04613	*y*5	−0.08682	*y*5	−0.12274	*y*5	−0.15451	*y*5	−0.18267	*y*5	−0.20771	*y*5	−0.23003
*x*6	−0.48091	*x*6	−0.49420	*x*6	−0.49829	*x*6	−0.50000	*x*6	−0.49860	*x*6	−0.49491	*x*6	−0.48954
*y*6	+0.13683	*y*6	+0.08682	*y*6	+0.04129	*y*6	0.00000	*y*6	−0.03737	*y*6	−0.07116	*y*6	−0.10173
*x*7	−0.39901	*x*7	−0.43301	*x*7	−0.45789	*x*7	−0.47553	*x*7	−0.48746	*x*7	−0.49491	*x*7	−0.49883
*y*7	+0.30132	*y*7	+0.25000	*y*7	+0.20085	*y*7	+0.15451	*y*7	+0.11126	*y*7	+0.07116	*y*7	+0.03412
*x*8	−0.26322	*x*8	−0.32139	*x*8	−0.36786	*x*8	−0.40451	*x*8	−0.43301	*x*8	−0.45482	*x*8	−0.47113
*y*8	+0.42511	*y*8	+0.38302	*y*8	+0.33864	*y*8	+0.29389	*y*8	+0.25000	*y*8	+0.20771	*y*8	+0.16744
*x*9	−0.09187	*x*9	−0.17101	*x*9	−0.23797	*x*9	−0.29389	*x*9	−0.34009	*x*9	−0.37787	*x*9	−0.40848
*y*9	+0.49149	*y*9	+0.46985	*y*9	+0.43974	*y*9	+0.40451	*y*9	+0.36653	*y*9	+0.32743	*y*9	+0.28834
*x*10	+0.09187	*x*10	0.00000	*x*10	−0.08230	*x*10	−0.15451	*x*10	−0.21694	*x*10	−0.27032	*x*10	−0.31554
*y*10	+0.49149	*y*10	+0.50000	*y*10	+0.49318	*y*10	+0.47553	*y*10	+0.45048	*y*10	+0.42063	*y*10	+0.38786
*x*11	+0.26322	*x*11	+0.17101	*x*11	+0.08230	*x*11	0.00000	*x*11	−0.07452	*x*11	−0.14087	*x*11	−0.19920
*y*11	+0.42511	*y*11	+0.46985	*y*11	+0.49318	*y*11	+0.50000	*y*11	+0.49442	*y*11	+0.47975	*y*11	+0.45861
*x*12	+0.39901	*x*12	+0.32139	*x*12	+0.23797	*x*12	+0.15451	*x*12	+0.07452	*x*12	0.00000	*x*12	−0.06808
*y*12	+0.30132	*y*12	+0.38302	*y*12	+0.43974	*y*12	+0.47553	*y*12	+0.49442	*y*12	+0.50000	*y*12	+0.49534
*x*13	+0.48091	*x*13	+0.43301	*x*13	+0.36786	*x*13	+0.29389	*x*13	+0.21694	*x*13	+0.14087	*x*13	+0.06808
*y*13	+0.13683	*y*13	+0.25000	*y*13	+0.33864	*y*13	+0.40451	*y*13	+0.45048	*y*13	+0.47975	*y*13	+0.49534
*x*14	+0.49787	*x*14	+0.49240	*x*14	+0.45789	*x*14	+0.40451	*x*14	+0.34009	*x*14	+0.27032	*x*14	+0.19920
*y*14	−0.04613	*y*14	+0.08682	*y*14	+0.20085	*y*14	+0.29389	*y*14	+0.36653	*y*14	+0.42063	*y*14	+0.45861
*x*15	+0.44758	*x*15	+0.49240	*x*15	+0.49829	*x*15	+0.47553	*x*15	+0.43301	*x*15	+0.37787	*x*15	+0.31554
*y*15	−0.22287	*y*15	−0.08682	*y*15	+0.04129	*y*15	+0.15451	*y*15	+0.25000	*y*15	+0.32743	*y*15	+0.38786
*x*16	+0.33685	*x*16	+0.43301	*x*16	+0.48470	*x*16	+0.50000	*x*16	+0.48746	*x*16	+0.45482	*x*16	+0.40848
*y*16	−0.36950	*y*16	−0.25000	*y*16	−0.12274	*y*16	0.00000	*y*16	+0.11126	*y*16	+0.20771	*y*16	+0.28834
*x*17	+0.18062	*x*17	+0.32139	*x*17	+0.41858	*x*17	+0.47553	*x*17	+0.49860	*x*17	+0.49491	*x*17	+0.47113
*y*17	−0.46624	*y*17	−0.38302	*y*17	−0.27347	*y*17	−0.15451	*y*17	−0.03737	*y*17	+0.07116	*y*17	+0.16744
		*x*18	+0.17101	*x*18	+0.30711	*x*18	+0.40451	*x*18	+0.46544	*x*18	+0.49491	*x*18	+0.49883
		*y*18	−0.46985	*y*18	−0.39457	*y*18	−0.29389	*y*18	−0.18267	*y*18	−0.07116	*y*18	+0.03412
				*x*19	+ 0.16235	*x*19	+0.29389	*x*19	+0.39092	*x*19	+0.45482	*x*19	+0.48954
				*y*19	−0.47291	*y*19	−0.40451	*y*19	−0.31174	*y*19	−0.20771	*y*19	−0.10173
						*x*20	+0.15451	*x*20	+0.28166	*x*20	+0.37787	*x*20	+0.44394
						*y*20	−0.47553	*y*20	−0.41312	*y*20	−0.32743	*y*20	−0.23003
								*x*21	+0.14738	*x*21	+0.27032	*x*21	+0.36542
								*y*21	−0.47779	*y*21	−0.42063	*y*21	−0.34128
										*x*22	+0.14087	*x*22	+0.25979
										*y*22	−0.47975	*y*22	−0.42721
												*x*23	+0.13490
												*y*23	−0.48146

24 Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000	*x*1	0.00000
*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000	*y*1	−0.50000
*x*2	−0.12941	*x*2	−0.12434	*x*2	−0.11966	*x*2	−0.11531	*x*2	−0.11126
*y*2	−0.48296	*y*2	−0.48429	*y*2	−0.48547	*y*2	−0.48652	*y*2	−0.48746
*x*3	−0.25000	*x*3	−0.24088	*x*3	−0.23236	*x*3	−0.22440	*x*3	−0.21694
*y*3	− 0.43301	*y*3	−0.43815	*y*3	−0.44273	*y*3	−0.44682	*y*3	−0.45048

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "A" Hole Circles, Central Coordinates** (English or Metric Units)



The diagram shows a type "A" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

24 Holes		25 Holes		26 Holes		27 Holes		28 Holes	
*x*4	−0.35355	*x*4	−0.34227	*x*4	−0.33156	*x*4	−0.32139	*x*4	−0.31174
*y*4	−0.35355	*y*4	−0.36448	*y*4	−0.37426	*y*4	−0.38302	*y*4	−0.39092
*x*5	−0.43301	*x*5	−0.42216	*x*5	−0.41149	*x*5	−0.40106	*x*5	−0.39092
*y*5	−0.25000	*y*5	−0.26791	*y*5	−0.28403	*y*5	−0.29858	*y*5	−0.31174
*x*6	−0.48296	*x*6	−0.47553	*x*6	−0.46751	*x*6	−0.45911	*x*6	−0.45048
*y*6	−0.12941	*y*6	−0.15451	*y*6	−0.17730	*y*6	−0.19804	*y*6	−0.21694
*x*7	−0.50000	*x*7	−0.49901	*x*7	−0.49635	*x*7	−0.49240	*x*7	−0.48746
*y*7	0.00000	*y*7	−0.03140	*y*7	−0.06027	*y*7	−0.08682	*y*7	−0.11126
*x*8	−0.48296	*x*8	−0.49114	*x*8	−0.49635	*x*8	−0.49915	*x*8	−0.50000
*y*8	+0.12941	*y*8	+0.09369	*y*8	+0.06027	*y*8	+0.02907	*y*8	0.00000
*x*9	−0.43301	*x*9	−0.45241	*x*9	−0.46751	*x*9	−0.47899	*x*9	−0.48746
*y*9	+0.25000	*y*9	+0.21289	*y*9	+0.17730	*y*9	+0.14340	*y*9	+0.11126
*x*10	−0.35355	*x*10	−0.38526	*x*10	−0.41149	*x*10	−0.43301	*x*10	−0.45048
*y*10	+0.35355	*y*10	+0.31871	*y*10	+0.28403	*y*10	+0.25000	*y*10	+0.21694
*x*11	−0.25000	*x*11	−0.29389	*x*11	−0.33156	*x*11	−0.36369	*x*11	−0.39092
*y*11	+0.43301	*y*11	+0.40451	*y*11	+0.37426	*y*11	+0.34312	*y*11	+0.31174
*x*12	−0.12941	*x*12	−0.18406	*x*12	−0.23236	*x*12	−0.27475	*x*12	−0.31174
*y*12	+0.48296	*y*12	+0.46489	*y*12	+0.44273	*y*12	+0.41774	*y*12	+0.39092
*x*13	0.00000	*x*13	−0.06267	*x*13	−0.11966	*x*13	−0.17101	*x*13	−0.21694
*y*13	+0.50000	*y*13	+0.49606	*y*13	+0.48547	*y*13	+0.46985	*y*13	+0.45048
*x*14	+0.12941	*x*14	+0.06267	*x*14	0.00000	*x*14	−0.05805	*x*14	−0.11126
*y*14	+0.48296	*y*14	+0.49606	*y*14	+0.50000	*y*14	+0.49662	*y*14	+0.48746
*x*15	+0.25000	*x*15	+0.18406	*x*15	+0.11966	*x*15	+0.05805	*x*15	0.00000
*y*15	+0.43301	*y*15	+0.46489	*y*15	+0.48547	*y*15	+0.49662	*y*15	+0.50000
*x*16	+0.35355	*x*16	+0.29389	*x*16	+0.23236	*x*16	+0.17101	*x*16	+0.11126
*y*16	+0.35355	*y*16	+0.40451	*y*16	+0.44273	*y*16	+0.46985	*y*16	+0.48746
*x*17	+0.43301	*x*17	+ 0.38526	*x*17	+0.33156	*x*17	+0.27475	*x*17	+0.21694
*y*17	+0.25000	*y*17	+0.31871	*y*17	+0.37426	*y*17	+0.41774	*y*17	+0.45048
*x*18	+0.48296	*x*18	+0.45241	*x*18	+0.41149	*x*18	+0.36369	*x*18	+0.31174
*y*18	+0.12941	*y*18	+0.21289	*y*18	+0.28403	*y*18	+0.34312	*y*18	+0.39092
*x*19	+0.50000	*x*19	+0.49114	*x*19	+0.46751	*x*19	+0.43301	*x*19	+0.39092
*y*19	0.00000	*y*19	+0.09369	*y*19	+0.17730	*y*19	+0.25000	*y*19	+0.31174
*x*20	+0.48296	*x*20	+0.49901	*x*20	+0.49635	*x*20	+0.47899	*x*20	+0.45048
*y*20	−0.12941	*y*20	−0.03140	*y*20	+0.06027	*y*20	+0.14340	*y*20	+0.21694
*x*21	+0.43301	*x*21	+0.47553	*x*21	+0.49635	*x*21	+0.49915	*x*21	+0.48746
*y*21	−0.25000	*y*21	−0.15451	*y*21	−0.06027	*y*21	+0.02907	*y*21	+0.11126
*x*22	+0.35355	*x*22	+0.42216	*x*22	+0.46751	*x*22	+0.49240	*x*22	+0.50000
*y*22	−0.35355	*y*22	−0.26791	*y*22	−0.17730	*y*22	−0.08682	*y*22	0.00000
*x*23	+0.25000	*x*23	+0.34227	*x*23	+0.41149	*x*23	+0.45911	*x*23	+0.48746
*y*23	−0.43301	*y*23	−0.36448	*y*23	−0.28403	*y*23	−0.19804	*y*23	−0.11126
*x*24	+0.12941	*x*24	+0.24088	*x*24	+0.33156	*x*24	+0.40106	*x*24	+0.45048
*y*24	−0.48296	*y*24	−0.43815	*y*24	−0.37426	*y*24	−0.29858	*y*24	−0.21694
		*x*25	+0.12434	*x*25	+0.23236	*x*25	+0.32139	*x*25	+0.39092
		*y*25	−0.48429	*y*25	−0.44273	*y*25	−0.38302	*y*25	−0.31174
				*x*26	+0.11966	*x*26	+0.22440	*x*26	+0.31174
				*y*26	−0.48547	*y*26	−0.44682	*y*26	−0.39092
						*x*27	+0.11531	*x*27	+0.21694
						*y*27	−0.48652	*y*27	−0.45048
								*x*28	+0.11126
								*y*28	−0.48746

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles Central Coordinates (English or Metric units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

3 Holes		4 Holes		5 Holes		6 Holes		7 Holes		8 Holes		9 Holes	
*x*1	−0.43301	*x*1	−0.35355	*x*1	−0.29389	*x*1	−0.25000	*x*1	−0.21694	*x*1	−0.19134	*x*1	−0.17101
*y*1	−0.25000	*y*1	−0.35355	*y*1	−0.40451	*y*1	−0.43301	*y*1	−0.45048	*y*1	−0.46194	*y*1	−0.46985
*x*2	0.00000	*x*2	−0.35355	*x*2	−0.47553	*x*2	−0.50000	*x*2	−0.48746	*x*2	−0.46194	*x*2	−0.43301
*y*2	+0.50000	*y*2	+0.35355	*y*2	+0.15451	*y*2	0.00000	*y*2	−0.11126	*y*2	−0.19134	*y*2	−0.25000
*x*3	+0.43301	*x*3	+0.35355	*x*3	0.00000	*x*3	−0.25000	*x*3	−0.39092	*x*3	−0.46194	*x*3	−0.49240
*y*3	−0.25000	*y*3	+0.35355	*y*3	+0.50000	*y*3	+0.43301	*y*3	+0.31174	*y*3	+0.19134	*y*3	+0.08682
		*x*4	+0.35355	*x*4	+0.47553	*x*4	+0.25000	*x*4	0.00000	*x*4	−0.19134	*x*4	−0.32139
		*y*4	−0.35355	*y*4	+0.15451	*y*4	+0.43301	*y*4	+0.50000	*y*4	+0.46194	*y*4	+0.38302
				*x*5	+0.29389	*x*5	+0.50000	*x*5	+0.39092	*x*5	+0.19134	*x*5	0.00000
				*y*5	−0.40451	*y*5	0.00000	*y*5	+0.31174	*y*5	+0.46194	*y*5	+0.50000
						*x*6	+0.25000	*x*6	+0.48746	*x*6	+0.46194	*x*6	+0.32139
						*y*6	−0.43301	*y*6	−0.11126	*y*6	+0.19134	*y*6	+0.38302
								*x*7	+0.21694	*x*7	+0.46194	*x*7	+0.49240
								*y*7	−0.45048	*y*7	−0.19134	*y*7	+0.08682
										*x*8	+0.19134	*x*8	+0.43301
										*y*8	−0.46194	*y*8	−0.25000
												*x*9	+0.17101
												*y*9	−0.46985

10 Holes		11 Holes		12 Holes		13 Holes		14 Holes		15 Holes		16 Holes	
*x*1	−0.15451	*x*1	−0.14087	*x*1	−0.12941	*x*1	−0.11966	*x*1	−0.11126	*x*1	−0.10396	*x*1	−0.09755
*y*1	−0.47553	*y*1	−0.47975	*y*1	−0.48296	*y*1	−0.48547	*y*1	−0.48746	*y*1	−0.48907	*y*1	−0.49039
*x*2	−0.40451	*x*2	−0.37787	*x*2	−0.35355	*x*2	−0.33156	*x*2	−0.31174	*x*2	−0.29389	*x*2	−0.27779
*y*2	−0.29389	*y*2	−0.32743	*y*2	−0.35355	*y*2	−0.37426	*y*2	−0.39092	*y*2	−0.40451	*y*2	−0.41573
*x*3	−0.50000	*x*3	−0.49491	*x*3	−0.48296	*x*3	−0.46751	*x*3	−0.45048	*x*3	−0.43301	*x*3	−0.41573
*y*3	0.00000	*y*3	−0.07116	*x*3	−0.12941	*y*3	−0.17730	*y*3	−0.21694	*y*3	−0.25000	*y*3	−0.27779
*x*4	−0.40451	*x*4	−0.45482	*x*4	−0.48296	*x*4	−0.49635	*x*4	−0.50000	*x*4	−0.49726	*x*4	−0.49039
*y*4	+0.29389	*y*4	+0.20771	*y*4	+0.12941	*y*4	+0.06027	*y*4	0.00000	*y*4	−0.05226	*y*4	−0.09755
*x*5	−0.15451	*x*5	−0.27032	*x*5	−0.35355	*x*5	−0.41149	*x*5	−0.45048	*x*5	−0.47553	*x*5	−0.49039
*y*5	+0.47553	*y*5	+0.42063	*y*5	+0.35355	*y*5	+0.28403	*y*5	+0.21694	*y*5	+0.15451	*y*5	+0.09755
*x*6	+0.15451	*x*6	0.00000	*x*6	−0.12941	*x*6	−0.23236	*x*6	−0.31174	*x*6	−0.37157	*x*6	−0.41573
*y*6	+0.47553	*y*6	+0.50000	*y*6	+0.48296	*y*6	+0.44273	*y*6	+0.39092	*y*6	+0.33457	*y*6	+0.27779
*x*7	+0.40451	*x*7	+0.27032	*x*7	+0.12941	*x*7	0.00000	*x*7	−0.11126	*x*7	−0.20337	*x*7	−0.27779
*y*7	+0.29389	*y*7	+0.42063	*y*7	+0.48296	*y*7	+ 0.50000	*y*7	+0.48746	*y*7	+0.45677	*y*7	+0.41573
*x*8	+0.50000	*x*8	+0.45482	*x*8	+0.35355	*x*8	+0.23236	*x*8	+0.11126	*x*8	0.00000	*x*8	−0.09755
*y*8	0.00000	*y*8	+0.20771	*y*8	+0.35355	*y*8	+0.44273	*y*8	+0.48746	*y*8	+0.50000	*y*8	+0.49039
*x*9	+0.40451	*x*9	+0.49491	*x*9	+0.48296	*x*9	+0.41149	*x*9	+0.31174	*x*9	+0.20337	*x*9	+0.09755
*y*9	−0.29389	*y*9	−0.07116	*y*9	+0.12941	*y*9	+0.28403	*y*9	+0.39092	*y*9	+0.45677	*y*9	+0.49039
*x*10	+0.15451	*x*10	+0.37787	*x*10	+0.48296	*x*10	+0.49635	*x*10	+0.45048	*x*10	+0.37157	*x*10	+0.27779
*y*10	−0.47553	*y*10	−0.32743	*y*10	−0.12941	*y*10	+0.06027	*y*10	+0.21694	*y*10	+0.33457	*y*10	+0.41573
		*x*11	+0.14087	*x*11	+0.35355	*x*11	+0.46751	*x*11	+0.50000	*x*11	+0.47553	*x*11	+0.41573
		*y*11	−0.47975	*y*11	−0.35355	*y*11	−0.17730	*y*11	0.00000	*y*11	+0.15451	*y*11	+0.27779
				*x*12	+0.12941	*x*12	+0.33156	*x*12	+0.45048	*x*12	+0.49726	*x*12	+0.49039
				*y*12	−0.48296	*y*12	−0.37426	*y*12	−0.21694	*y*12	−0.05226	*y*12	+0.09755
						*x*13	+0.11966	*x*13	+0.31174	*x*13	+0.43301	*x*13	+0.49039
						*y*13	−0.48547	*y*13	−0.39092	*y*13	−0.25000	*y*13	−0.09755
								*x*14	+0.11126	*x*14	+0.29389	*x*14	+0.41573
								*y*14	− 0.48746	*y*14	−0.40451	*y*14	−0.27779
										*x*15	+0.10396	*x*15	+0.27779
										*y*15	−0.48907	*y*15	−0.41573
												*x*16	+0.09755
												*y*16	−0.49039

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles Central Coordinates** (English or Metric units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

17 Holes	18 Holes	19 Holes	20 Holes	21 Holes	22 Holes	23 Holes
x1 −0.09187	x1 −0.08682	x1 −0.08230	x1 −0.07822	x1 −0.07452	x1 −0.07116	x1 −0.06808
y1 − 0.49149	y1 −0.49240	y1 −0.49318	y1 −0.49384	y1 −0.49442	y1 −0.49491	y1 −0.49534
x2 −0.26322	x2 −0.25000	x2 −0.23797	x2 −0.22700	x2 −0.21694	x2 −0.20771	x2 −0.19920
y2 −0.42511	y2 −0.43301	y2 −0.43974	y2 −0.44550	y2 −0.45048	y2 −0.45482	y2 −0.45861
x3 − 0.39901	x3 −0.38302	x3 −0.36786	x3 −0.35355	x3 −0.34009	x3 −0.32743	x3 −0.31554
y3 −0.30132	y3 −0.32139	y3 −0.33864	y3 −0.35355	y3 −0.36653	y3 −0.37787	y3 −0.38786
x4 −0.48091	x4 −0.46985	x4 −0.45789	x4 −0.44550	x4 −0.43301	x4 −0.42063	x4 −0.40848
y4 −0.13683	y4 −0.17101	y4 −0.20085	y4 −0.22700	y4 −0.25000	y4 −0.27032	y4 −0.28834
x5 −0.49787	x5 −0.50000	x5 −0.49829	x5 −0.49384	x5 −0.48746	x5 −0.47975	x5 −0.47113
y5 +0.04613	y5 0.00000	y5 −0.04129	y5 −0.07822	y5 −0.11126	y5 −0.14087	y5 −0.16744
x6 −0.44758	x6 −0.46985	x6 −0.48470	x6 −0.49384	x6 −0.49860	x6 −0.50000	x6 −0.49883
y6 +0.22287	y6 +0.17101	y6 +0.12274	y6 +0.07822	y6 +0.03737	y6 0.00000	y6 −0.03412
x7 −0.33685	x7 −0.38302	x7 −0.41858	x7 −0.44550	x7 −0.46544	x7 −0.47975	x7 −0.48954
y7 +0.36950	y7 +0.32139	y7 +0.27347	y7 +0.22700	y7 +0.18267	y7 +0.14087	y7 +0.10173
x8 −0.18062	x8 −0.25000	x8 −0.30711	x8 −0.35355	x8 −0.39092	x8 −0.42063	x8 −0.44394
y8 +0.46624	y8 +0.43301	y8 +0.39457	y8 +0.35355	y8 +0.31174	y8 +0.27032	y8 +0.23003
x9 0.00000	x9 −0.08682	x9 −0.16235	x9 −0.22700	x9 −0.28166	x9 −0.32743	x9 −0.36542
y9 +0.50000	y9 +0.49240	y9 +0.47291	y9 +0.44550	y9 +0.41312	y9 +0.37787	y9 +0.34128
x10 +0.18062	x10 +0.08682	x10 0.00000	x10 −0.07822	x10 −0.14738	x10 −0.20771	x10 −0.25979
y10 +0.46624	y10 +0.49240	y10 +0.50000	y10 +0.49384	y10 +0.47779	y10 +0.45482	y10 +0.42721
x11 +0.33685	x11 +0.25000	x11 +0.16235	x11 +0.07822	x11 0.00000	x11 −0.07116	x11 −0.13490
y11 +0.36950	y11 +0.43301	y11 +0.47291	y11 +0.49384	y11 +0.50000	y11 +0.49491	y11 +0.48146
x12 +0.44758	x12 +0.38302	x12 +0.30711	x12 +0.22700	x12 +0.14738	x12 + 0.07116	x12 0.00000
y12 +0.22287	y12 +0.32139	y12 +0.39457	y12 +0.44550	y12 +0.47779	y12 +0.49491	y12 +0.50000
x13 +0.49787	x13 +0.46985	x13 +0.41858	x13 +0.35355	x13 +0.28166	x13 +0.20771	x13 +0.13490
y13 +0.04613	y13 +0.17101	y13 +0.27347	y13 +0.35355	y13 +0.41312	y13 +0.45482	y13 +0.48146
x14 +0.48091	x14 +0.50000	x14 +0.48470	x14 +0.44550	x14 +0.39092	x14 +0.32743	x14 +0.25979
y14 −0.13683	y14 0.00000	y14 +0.12274	y14 +0.22700	y14 +0.31174	y14 +0.37787	y14 +0.42721
x15 +0.39901	x15 +0.46985	x15 +0.49829	x15 +0.49384	x15 +0.46544	x15 +0.42063	x15 +0.36542
y15 −0.30132	y15 −0.17101	y15 −0.04129	y15 +0.07822	y15 +0.18267	y15 +0.27032	y15 +0.34128
x16 +0.26322	x16 +0.38302	x16 +0.45789	x16 +0.49384	x16 +0.49860	x16 +0.47975	x16 +0.44394
y16 −0.42511	y16 −0.32139	y16 −0.20085	y16 −0.07822	y16 +0.03737	y16 +0.14087	y16 +0.23003
x17 +0.09187	x17 +0.25000	x17 +0.36786	x17 +0.44550	x17 +0.48746	x17 +0.50000	x17 +0.48954
y17 − 0.49149	y17 −0.43301	y17 −0.33864	y17 −0.22700	y17 −0.11126	y17 0.00000	y17 +0.10173
	x18 +0.08682	x18 +0.23797	x18 +0.35355	x18 +0.43301	x18 +0.47975	x18 +0.49883
	y18 −0.49240	y18 −0.43974	y18 −0.35355	y18 −0.25000	y18 −0.14087	y18 −0.03412
		x19 +0.08230	x19 +0.22700	x19 +0.34009	x19 +0.42063	x19 +0.47113
		y19 −0.49318	y19 −0.44550	y19 −0.36653	y19 −0.27032	y19 −0.16744
			x20 +0.07822	x20 +0.21694	x20 +0.32743	x20 +0.40848
			y20 −0.49384	y20 −0.45048	y20 −0.37787	y20 −0.28834
				x21 +0.07452	x21 +0.20771	x21 +0.31554
				y21 −0.49442	y21 −0.45482	y21 −0.38786
					x22 +0.07116	x22 +0.19920
					y22 −0.49491	y22 −0.45861
						x23 +0.06808
						y23 −0.49534

24 Holes	25 Holes	26 Holes	27 Holes	28 Holes
x1 −0.06526	x1 −0.06267	x1 −0.06027	x1 −0.05805	x1 −0.05598
y1 −0.49572	y1 −0.49606	y1 −0.49635	y1 −0.49662	y1 −0.49686
x2 −0.19134	x2 −0.18406	x2 −0.17730	x2 −0.17101	x2 −0.16514
y2 −0.46194	y2 −0.46489	y2 −0.46751	y2 −0.46985	y2 −0.47194
x3 −0.30438	x3 −0.29389	x3 −0.28403	x3 −0.27475	x3 −0.26602
y3 −0.39668	y3 −0.40451	y3 −0.41149	y3 −0.41774	y3 −0.42336

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. ***(Continued)*** **Hole Coordinate Dimension Factors for Jig Boring — Type "B" Hole Circles Central Coordinates** (English or Metric units)



The diagram shows a type "B" circle for a 5-hole circle. Coordinates *x*, *y* are given in the table for hole circles of from 3 to 28 holes. Dimensions are for holes numbered in a counterclockwise direction (as shown). Dimensions given are based upon a hole circle of unit diameter. For a hole circle of, say, 3-inch or 3-centimeter diameter, multiply table values by 3.

24 Holes	25 Holes	26 Holes	27 Holes	28 Holes
*x*4 −0.39668	*x*4 −0.38526	*x*4 −0.37426	*x*4 −0.36369	*x*4 −0.35355
*y*4 −0.30438	*y*4 −0.31871	*y*4 −0.33156	*y*4 −0.34312	*y*4 −0.35355
*x*5 −0.46194	*x*5 −0.45241	*x*5 −0.44273	*x*5 −0.43301	*x*5 −0.42336
*y*5 −0.19134	*y*5 −0.21289	*y*5 −0.23236	*y*5 − 0.25000	*y*5 −0.26602
*x*6 −0.49572	*x*6 −0.49114	*x*6 −0.48547	*x*6 −0.47899	*x*6 −0.47194
*y*6 −0.06526	*y*6 −0.09369	*y*6 −0.11966	*y*6 −0.14340	*y*6 −0.16514
*x*7 −0.49572	*x*7 −0.49901	*x*7 −0.50000	*x*7 −0.49915	*x*7 −0.49686
*y*7 +0.06526	*y*7 +0.03140	*y*7 0.00000	*y*7 − 0.02907	*y*7 −0.05598
*x*8 −0.46194	*x*8 −0.47553	*x*8 −0.48547	*x*8 −0.49240	*x*8 −0.49686
*y*8 +0.19134	*y*8 +0.15451	*y*8 +0.11966	*y*8 +0.08682	*y*8 +0.05598
*x*9 −0.39668	*x*9 −0.42216	*x*9 −0.44273	*x*9 −0.45911	*x*9 −0.47194
*y*9 +0.30438	*y*9 +0.26791	*y*9 +0.23236	*y*9 +0.19804	*y*9 +0.16514
*x*10 −0.30438	*x*10 −0.34227	*x*10 −0.37426	*x*10 −0.40106	*x*10 −0.42336
*y*10 +0.39668	*y*10 + 0.36448	*y*10 +0.33156	*y*10 +0.29858	*y*10 +0.26602
*x*11 −0.19134	*x*11 −0.24088	*x*11 −0.28403	*x*11 −0.32139	*x*11 −0.35355
*y*11 +0.46194	*y*11 +0.43815	*y*11 +0.41149	*y*11 +0.38302	*y*11 +0.35355
*x*12 −0.06526	*x*12 −0.12434	*x*12 −0.17730	*x*12 −0.22440	*x*12 −0.26602
*y*12 +0.49572	*y*12 +0.48429	*y*12 +0.46751	*y*12 +0.44682	*y*12 +0.42336
*x*13 +0.06526	*x*13 0.00000	*x*13 −0.06027	*x*13 −0.11531	*x*13 −0.16514
*y*13 +0.49572	*y*13 +0.50000	*y*13 +0.49635	*y*13 +0.48652	*y*13 +0.47194
*x*14 +0.19134	*x*14 +0.12434	*x*14 +0.06027	*x*14 0.00000	*x*14 −0.05598
*y*14 +0.46194	*y*14 +0.48429	*y*14 +0.49635	*y*14 +0.50000	*y*14 +0.49686
*x*15 +0.30438	*x*15 +0.24088	*x*15 +0.17730	*x*15 +0.11531	*x*15 +0.05598
*y*15 +0.39668	*y*15 +0.43815	*y*15 +0.46751	*y*15 +0.48652	*y*15 +0.49686
*x*16 +0.39668	*x*16 +0.34227	*x*16 +0.28403	*x*16 +0.22440	*x*16 +0.16514
*y*16 +0.30438	*y*16 +0.36448	*y*16 +0.41149	*y*16 +0.44682	*y*16 +0.47194
*x*17 +0.46194	*x*17 +0.42216	*x*17 +0.37426	*x*17 +0.32139	*x*17 +0.26602
*y*17 +0.19134	*y*17 +0.26791	*y*17 +0.33156	*y*17 +0.38302	*y*17 +0.42336
*x*18 +0.49572	*x*18 +0.47553	*x*18 +0.44273	*x*18 +0.40106	*x*18 +0.35355
*y*18 +0.06526	*y*18 +0.15451	*y*18 +0.23236	*y*18 + 0.29858	*y*18 +0.35355
*x*19 +0.49572	*x*19 +0.49901	*x*19 +0.48547	*x*19 +0.45911	*x*19 +0.42336
*y*19 −0.06526	*y*19 +0.03140	*y*19 +0.11966	*y*19 +0.19804	*y*19 +0.26602
*x*20 +0.46194	*x*20 +0.49114	*x*20 +0.50000	*x*20 +0.49240	*x*20 +0.47194
*y*20 −0.19134	*y*20 −0.09369	*y*20 0.00000	*y*20 +0.08682	*y*20 +0.16514
*x*21 +0.39668	*x*21 +0.45241	*x*21 + 0.48547	*x*21 +0.49915	*x*21 +0.49686
*y*21 −0.30438	*y*21 −0.21289	*y*21 −0.11966	*y*21 −0.02907	*y*21 +0.05598
*x*22 +0.30438	*x*22 +0.38526	*x*22 +0.44273	*x*22 +0.47899	*x*22 +0.49686
*y*22 −0.39668	*y*22 −0.31871	*y*22 −0.23236	*y*22 − 0.14340	*y*22 −0.05598
*x*23 +0.19134	*x*23 +0.29389	*x*23 +0.37426	*x*23 +0.43301	*x*23 +0.47194
*y*23 −0.46194	*y*23 −0.40451	*y*23 −0.33156	*y*23 −0.25000	*y*23 −0.16514
*x*24 +0.06526	*x*24 +0.18406	*x*24 +0.28403	*x*24 +0.36369	*x*24 +0.42336
*y*24 −0.49572	*y*24 −0.46489	*y*24 −0.41149	*y*24 −0.34312	*y*24 −0.26602
	*x*25 +0.06267	*x*25 +0.17730	*x*25 +0.27475	*x*25 +0.35355
	*y*25 −0.49606	*y*25 −0.46751	*y*25 −0.41774	*y*25 −0.35355
		*x*26 +0.06027	*x*26 +0.17101	*x*26 +0.26602
		*y*26 −0.49635	*y*26 −0.46985	*y*26 −0.42336
			*x*27 +0.05805	*x*27 +0.16514
			*y*27 −0.49662	*y*27 −0.47194
				*x*28 +0.05598
				*y*28 −0.49686

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINING OPERATIONS

CUTTING SPEEDS AND FEEDS

1009 Indroduction to Speeds and Feeds
1009 Cutting Tool Materials
1013 Cutting Speeds
1014 Cutting Conditions
1014 Selecting Cutting Conditions
1014 Tool Troubleshooting
1016 Cutting Speed Formulas
1018 RPM for Various Cutting Speeds and Diameter

SPEED AND FEED TABLES

1022 How to Use the Tables
1022 Principal Speed andFeed Tables
1026 Speed and Feed Tables for Turning
1027 Plain Carbon and Alloy Steels
1031 Tool Steels
1032 Stainless Steels
1033 Ferrous Cast Metals
1035 Speed and Tool Life Adjustments
1037 Copper Alloys
1038 Titanium and Titanium Alloys
1039 Superalloys
1040 Speed and Feed Tables for Milling
1043 Slit Milling
1044 Aluminium Alloys
1045 Plain Carbon and Alloy Steels
1049 Tool Steels
1050 Stainless Steels
1052 Ferrous Cast Metals
1054 High Speed Steel Cutters
1056 Speed Adjustment Factors
1057 Radial Depth of Cut Adjustments
1059 Tool Life Adjustments
1060 Drilling, Reaming, and Threading
1061 Plain Carbon and Alloy Steels
1066 Tool Steels
1067 Stainless Steels
1068 Ferrous Cast Metals
1070 Light Metals
1071 Adjustment Factors for HSS
1072 Copper Alloys
1072 Tapping and Threading
1074 Cutting Speed for Broaching
1075 Spade Drills
1075 Spade Drill Geometry
1077 Spade Drilling
1079 Feed Rates
1080 Power Consumption
1081 Trepanning

ESTIMATING SPEEDS AND MACHINING POWER

1082 Planer Cutting Speeds
1082 Cutting Speed and Time
1082 Planing Time
1082 Speeds for Metal-Cutting Saws
1082 Turning Unusual Material
1084 Estimating Machining Power
1084 Power Constants
1085 Feed Factors
1085 Tool Wear Factors
1088 Metal Removal Rates
1090 Estimating Drilling Thrust, Torque, and Power
1090 Work Material Factor
1091 Chisel Edge Factors
1091 Feed Factors
1091 Drill Diameter Factors

MACHINING ECONOMETRICS

1093 Tool Wear And Tool Life Relationships
1093 Equivalent Chip Thickness (ECT)
1094 Tool-life Relationships
1098 The G- and H-curves
1099 Tool-life Envelope
1102 Forces and Tool-life
1104 Surface Finish and Tool-life
1106 Shape of Tool-life Relationships
1107 Minimum Cost
1108 Production Rate
1108 The Cost Function
1109 Global Optimum
1110 Economic Tool-life
1113 Machine Settings and Cost Calculations
1113 Nomenclature
1114 Cutting Formulas
1118 Tooling And Total Cost
1119 Optimized Data
1122 High-speed Machining Econometrics
1123 Chip Geometry in Milling
1125 Chip Thickness
1127 Forces and Tool-life
1128 High-speed Milling
1129 Econometrics Comparison

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINING OPERATIONS

SCREW MACHINE FEEDS AND SPEEDS

1131 Automatic Screw Machine Tools
1131 Knurling
1131 Revolution for Knurling
1131 Cams for Threading
1132 Cutting Speeds and Feeds
1134 Spindle Revolutions
1135 Practical Points on Cam
1136 Stock for Screw Machine Products
1138 Band Saw Blade Selection
1139 Tooth Forms
1139 Types of Blades
1140 Band Saw Speed and Feed Rate
1141 Bimetal Band Saw Speeds
1142 Band Saw Blade Break-In

CUTTING FLUIDS

1144 Types of Fluids
1144 Cutting Oils
1144 Water-Miscible Fluids
1145 Selection of Cutting Fluids
1146 Turning, Milling, Drilling and Tapping
1147 Machining
1148 Machining Magnesium
1149 Metalworking Fluids
1149 Classes of Metalworking Fluids
1149 Occupational Exposures
1150 Fluid Selection, Use, and Application
1151 Fluid Maintenance
1152 Respiratory Protection

MACHINING NONFERROUS METALS AND NON-METALLIC MATERIALS

1153 Machining Nonferrous Metals
1153 Aluminium
1154 Magnesium
1155 Zinc Alloy Die-Castings
1155 Monel and Nickel Alloys
1156 Copper Alloys
1156 Machining Non-metals
1156 Hard Rubber
1156 Formica Machining
1157 Micarta Machining
1157 Ultrasonic Machining

GRINDING FEEDS AND SPEEDS

1158 Basic Rules
1158 Wheel life T and Grinding Ratio
1159 ECT in Grinding
1160 Optimum Grinding Data
1162 Surface Finish, Ra
1163 Spark-out Time
1164 Grinding Cutting Forces
1165 Grinding Data
1166 Grindability Groups
1166 Side Feed, Roughing and Finishing
1167 Relative Grindability
1168 Grindability Overview
1168 Procedure to Determine Data
1174 Calibration of Recommendations
1176 Optimization

GRINDING AND OTHER ABRASIVE PROCESSES

1177 Grinding Wheels
1177 Abrasive Materials
1178 Bond Properties
1178 Structure
1179 ANSI Markings
1179 Sequence of Markings
1180 ANSI Shapes and Sizes
1180 Selection of Grinding Wheel
1181 Standard Shapes Ranges
1188 Grinding Wheel Faces
1189 Classification of Tool Steels
1190 Hardened Tool Steels
1194 Constructional Steels
1195 Cubic Boron Nitride
1196 Dressing and Truing
1196 Tools and Methods for Dressing and Truing
1198 Guidelines for Truing and Dressing
1199 Diamond Truing and Crossfeeds
1200 Size Selection Guide
1200 Minimum Sizes for Single-Point Truing Diamonds

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINING OPERATIONS

GRINDING AND OTHER ABRASIVE PROCESSES

(Continued)

1201 Diamond Wheels
1201 Shapes
1202 Core Shapes and Designations
1202 Cross-sections and Designations
1203 Designations for Location
1204 Composition
1205 Designation Letters
1206 Selection of Diamond Wheels
1206 Abrasive Specification
1207 Handling and Operation
1207 Speeds and Feeds
1207 Grinding Wheel Safety
1207 Safety in Operating
1208 Handling, Storage and Inspection
1208 Machine Conditions
1208 Grinding Wheel Mounting
1209 Safe Operating Speeds
1210 Portable Grinders
1212 Cylindrical Grinding
1212 Plain, Universal, and Limited-Purpose Machines
1212 Traverse or Plunge Grinding
1212 Work Holding on Machines
1213 Work-Holding Methods
1213 Selection of Grinding Wheels
1214 Wheel Recommendations
1214 Operational Data
1215 Basic Process Data
1215 High-Speed
1216 Areas and Degrees of Automation
1216 Troubles and Their Correction
1220 Centerless Grinding
1221 Through-feed Method of Grinding
1221 In-feed Method
1221 End-feed Method
1221 Automatic Centerless Method
1221 Centerless Grinding
1222 Surface Grinding
1223 Principal Systems
1225 Grinding Wheel Recommendations
1226 Process Data for Surface Grinding
1226 Basic Process Data
1227 Faults and Possible Causes

GRINDING AND OTHER ABRASIVE PROCESSES

(Continued)

1229 Offhand Grinding
1229 Floor- and Bench-Stand Grinding
1229 Portable Grinding
1229 Swing-Frame Grinding
1230 Abrasive Belt Grinding
1230 Application of Abrasive Belts
1230 Selection Contact Wheels
1230 Abrasive Cutting
1233 Cutting-Off Difficulties
1233 Honing Process
1233 Rate of Stock Removal
1234 Formula for Rotative Speeds
1234 Factors in Rotative Speed Formulas
1235 Eliminating Undesirable Honing Conditions
1235 Tolerances
1235 Laps and Lapping
1235 Material for Laps
1236 Laps for Flat Surfaces
1236 Grading Abrasives
1237 Charging Laps
1237 Rotary Diamond Lap
1237 Grading Diamond Dust
1238 Cutting Properties
1238 Cutting Qualities
1238 Wear of Laps
1238 Lapping Abrasives
1238 Effect on Lapping Lubricants
1239 Lapping Pressures
1239 Wet and Dry Lapping
1239 Lapping Tests

KNURLS AND KNURLING

1240 Knurls and Knurling
1240 ANSI Standard
1240 Preferred Sizes
1240 Specifications
1241 Cylindrical Tools
1242 Flat Tools
1242 Specifications for Flat Dies
1242 Formulas to Knurled Work
1243 Tolerances
1244 Marking on Knurls and Dies
1244 Concave Knurls

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINING OPERATIONS

MACHINE TOOL ACCURACY

1248 Degrees of Accuracy Expected with NC Machine Tool
1249 Part Tolerances

NUMERICAL CONTROL

1254 Introduction
1254 CNC Technology
1254 Numerical Control vs. Manual Operations
1255 Numerical Control Standards
1258 Programmable Controller
1262 Closed-Loop System
1262 Open-Loop System
1262 Adaptive Control
1263 Flexible Manufacturing Systems
1264 Flexible Manufacturing Cell
1264 Flexible Manufacturing Module
1264 Axis Nomenclature
1267 Total Indicator Reading

NUMERICAL CONTROL PROGRAMMING

1269 Programming
1272 Postprocessors
1272 G-Code Programming
1272 Format Classification
1272 Letter Addresses
1274 Sequence Number (N-Word)
1274 Preparatory Word (G-Word)
1278 Miscellaneous Functions
1279 Feed Function (F-Word)
1280 Spindle Function (S-Word)
1280 Tool Function (T-Word)
1282 Linear Interpolation
1283 Circular Interpolation
1284 Helical and Parabolic Interpolation
1285 Subroutine
1287 Conditional Expressions
1287 Fixed (Canned) Cycles
1291 Turning Cycles
1291 Thread Cutting

NUMERICAL CONTROL PROGRAMMING *(Continued)*

1292 APT Programming
1294 APT Computational Statements
1294 APT Geometry Statements
1295 Points, Lines and Circles
1299 APT Motion Statements
1300 Contouring Cutter Movements
1301 Circles and Planes
1303 3-D Geometry
1304 APT Postprocessor Statements
1306 APT Example Program
1307 APT for Turning
1309 Indexable Insert Holders for NC
1310 Insert Radius Compensation
1312 Threading Tool Insert Radius
1313 V-Flange Tool Shanks
1314 Retention Knobs

CAD/CAM

1315 CAD/CAM
1317 Drawing Projections
1318 Drawing Tips and Traps
1322 Sizes of Lettering on Drawing
1322 Drawing Exchange Standards
1324 Rapid Automated Prototyping
1324 DNC
1325 Machinery Noise
1325 Measuring Machinery Noise

Copyright 2004, Industrial Press, Inc., New York, NY

CUTTING SPEEDS AND FEEDS

Indroduction to Speeds and Feeds

Work Materials.— The large number of work materials that are commonly machined vary greatly in their basic structure and the ease with which they can be machined. Yet it is possible to group together certain materials having similar machining characteristics, for the purpose of recommending the cutting speed at which they can be cut. Most materials that are machined are metals and it has been found that the most important single factor influencing the ease with which a metal can be cut is its microstructure, followed by any cold work that may have been done to the metal, which increases its hardness. Metals that have a similar, but not necessarily the same microstructure, will tend to have similar machining characteristics. Thus, the grouping of the metals in the accompanying tables has been done on the basis of their microstructure.

With the exception of a few soft and gummy metals, experience has shown that harder metals are more difficult to cut than softer metals. Furthermore, any given metal is more difficult to cut when it is in a harder form than when it is softer. It is more difficult to penetrate the harder metal and more power is required to cut it. These factors in turn will generate a higher cutting temperature at any given cutting speed, thereby making it necessary to use a slower speed, for the cutting temperature must always be kept within the limits that can be sustained by the cutting tool without failure. Hardness, then, is an important property that must be considered when machining a given metal. Hardness alone, however, cannot be used as a measure of cutting speed. For example, if pieces of AISI 11L17 and AISI 1117 steel both have a hardness of 150 Bhn, their recommended cutting speeds for high-speed steel tools will be 140 fpm and 130 fpm, respectively. In some metals, two entirely different microstructures can produce the same hardness. As an example, a fine pearlite microstructure and a tempered martensite microstructure can result in the same hardness in a steel. These microstructures will not machine alike. For practical purposes, however, information on hardness is usually easier to obtain than information on microstructure; thus, hardness alone is usually used to differentiate between different cutting speeds for machining a metal. In some situations, the hardness of a metal to be machined is not known. When the hardness is not known, the material condition can be used as a guide.

The surface of ferrous metal castings has a scale that is more difficult to machine than the metal below. Some scale is more difficult to machine than others, depending on the foundry sand used, the casting process, the method of cleaning the casting, and the type of metal cast. Special electrochemical treatments sometimes can be used that almost entirely eliminate the effect of the scale on machining, although castings so treated are not frequently encountered. Usually, when casting scale is encountered, the cutting speed is reduced approximately 5 or 10 per cent. Difficult-to-machine surface scale can also be encountered when machining hot-rolled or forged steel bars.

Metallurgical differences that affect machining characteristics are often found within a single piece of metal. The occurrence of hard spots in castings is an example. Different microstructures and hardness levels may occur within a casting as a result of variations in the cooling rate in different parts of the casting. Such variations are less severe in castings that have been heat treated. Steel bar stock is usually harder toward the outside than toward the center of the bar. Sometimes there are slight metallurgical differences along the length of a bar that can affect its cutting characteristics.

Cutting Tool Materials.— The recommended cutting feeds and speeds in the accompanying tables are given for high-speed steel, coated and uncoated carbides, ceramics, cermets, and polycrystalline diamonds. More data are available for HSS and carbides because these materials are the most commonly used. Other materials that are used to make cutting tools are cemented oxides or ceramics, cermets, cast nonferrous alloys (Stellite), single-crystal diamonds, polycrystalline diamonds, and cubic boron nitride.

Copyright 2004, Industrial Press, Inc., New York, NY

Carbon Tool Steel: It is used primarily to make the less expensive drills, taps, and reamers. It is seldom used to make single-point cutting tools. Hardening in carbon steels is very shallow, although some have a small amount of vanadium and chromium added to improve their hardening quality. The cutting speed to use for plain carbon tool steel should be approximately one-half of the recommended speed for high-speed steel.

High-Speed Steel: This designates a number of steels having several properties that enhance their value as cutting tool material. They can be hardened to a high initial or room-temperature hardness ranging from 63 Rc to 65 Rc for ordinary high-speed steels and up to 70 Rc for the so-called superhigh-speed steels. They can retain sufficient hardness at temperatures up to 1,000 to 1,100°F to enable them to cut at cutting speeds that will generate these tool temperatures, and they will return to their original hardness when cooled to room temperature. They harden very deeply, enabling high-speed steels to be ground to the tool shape from solid stock and to be reground many times without sacrificing hardness at the cutting edge. High-speed steels can be made soft by annealing so that they can be machined into complex cutting tools such as drills, reamers, and milling cutters and then hardened.

The principal alloying elements of high-speed steels are tungsten (W), molybdenum (Mo), chromium (Cr), vanadium (V), together with carbon (C). There are a number of grades of high-speed steel that are divided into two types: tungsten high-speed steels and molybdenum high-speed steels. Tungsten high-speed steels are designated by the prefix T before the number that designates the grade. Molybdenum high-speed steels are designated by the prefix letter M. There is little performance difference between comparable grades of tungsten or molybdenum high-speed steel.

The addition of 5 to 12 per cent cobalt to high-speed steel increases its hardness at the temperatures encountered in cutting, thereby improving its wear resistance and cutting efficiency. Cobalt slightly increases the brittleness of high-speed steel, making it susceptible to chipping at the cutting edge. For this reason, cobalt high-speed steels are primarily made into single-point cutting tools that are used to take heavy roughing cuts in abrasive materials and through rough abrasive surface scales.

The M40 series and T15 are a group of high-hardness or so-called super high-speed steels that can be hardened to 70 Rc; however, they tend to be brittle and difficult to grind. For cutting applications, they are usually heat treated to 67–68 Rc to reduce their brittleness and tendency to chip. The M40 series is appreciably easier to grind than T15. They are recommended for machining tough die steels and other difficult-to-cut materials; they are not recommended for applications where conventional high-speed steels perform well. High-speed steels made by the powder-metallurgy process are tougher and have an improved grindability when compared with similar grades made by the customary process. Tools made of these steels can be hardened about 1 Rc higher than comparable high-speed steels made by the customary process without a sacrifice in toughness. They are particularly useful in applications involving intermittent cutting and where tool life is limited by chipping. All these steels augment rather than replace the conventional high-speed steels.

Cemented Carbides: They are also called sintered carbides or simply carbides. They are harder than high-speed steels and have excellent wear resistance. Information on cemented carbides and other hard metal tools is included in the section *CEMENTED CARBIDES* starting on page 773.

Cemented carbides retain a very high degree of hardness at temperatures up to 1400°F and even higher; therefore, very fast cutting speeds can be used. When used at fast cutting speeds, they produce good surface finishes on the workpiece. Carbides are more brittle than high-speed steel and, therefore, must be used with more care.

Hundreds of grades of carbides are available and attempts to classify these grades by area of application have not been entirely successful.

There are four distinct types of carbides: 1) straight tungsten carbides; 2) crater-resistant carbides; 3) titanium carbides; and 4) coated carbides.

Copyright 2004, Industrial Press, Inc., New York, NY

Straight Tungsten Carbide: This is the most abrasion-resistant cemented carbide and is used to machine gray cast iron, most nonferrous metals, and nonmetallic materials, where abrasion resistance is the primary criterion. Straight tungsten carbide will rapidly form a crater on the tool face when used to machine steel, which reduces the life of the tool. Titanium carbide is added to tungsten carbide in order to counteract the rapid formation of the crater. In addition, tantalum carbide is usually added to prevent the cutting edge from deforming when subjected to the intense heat and pressure generated in taking heavy cuts.

Crater-Resistant Carbides: These carbides, containing titanium and tantalum carbides in addition to tungsten carbide, are used to cut steels, alloy cast irons, and other materials that have a strong tendency to form a crater.

Titanium Carbides: These carbides are made entirely from titanium carbide and small amounts of nickel and molybdenum. They have an excellent resistance to cratering and to heat. Their high hot hardness enables them to operate at higher cutting speeds, but they are more brittle and less resistant to mechanical and thermal shock. Therefore, they are not recommended for taking heavy or interrupted cuts. Titanium carbides are less abrasion-resistant and not recommended for cutting through scale or oxide films on steel. Although the resistance to cratering of titanium carbides is excellent, failure caused by crater formation can sometimes occur because the chip tends to curl very close to the cutting edge, thereby forming a small crater in this region that may break through.

Coated Carbides: These are available only as indexable inserts because the coating would be removed by grinding. The principal coating materials are titanium carbide (TiC), titanium nitride (TiN), and aluminum oxide (Al_2O_3). A very thin layer (approximately 0.0002 in.) of coating material is deposited over a cemented carbide insert; the material below the coating is called the substrate. The overall performance of the coated carbide is limited by the substrate, which provides the required toughness and resistance to deformation and thermal shock. With an equal tool life, coated carbides can operate at higher cutting speeds than uncoated carbides. The increase may be 20 to 30 per cent and sometimes up to 50 per cent faster. Titanium carbide and titanium nitride coated carbides usually operate in the medium (200–800 fpm) cutting speed range, and aluminum oxide coated carbides are used in the higher (800–1600 fpm) cutting speed range.

Carbide Grade Selection: The selection of the best grade of carbide for a particular application is very important. An improper grade of carbide will result in a poor performance—it may even cause the cutting edge to fail before any significant amount of cutting has been done. Because of the many grades and the many variables that are involved, the carbide producers should be consulted to obtain recommendations for the application of their grades of carbide. A few general guidelines can be given that are useful to form an orientation. Metal cutting carbides usually range in hardness from about 89.5 Ra (Rockwell A Scale) to 93.0 Ra with the exception of titanium carbide, which has a hardness range of 90.5 Ra to 93.5 Ra. Generally, the harder carbides are more wear-resistant and more brittle, whereas the softer carbides are less wear-resistant but tougher. A choice of hardness must be made to suit the given application. The very hard carbides are generally used for taking light finishing cuts. For other applications, select the carbide that has the highest hardness with sufficient strength to prevent chipping or breaking. Straight tungsten carbide grades should always be used unless cratering is encountered. Straight tungsten carbides are used to machine gray cast iron, ferritic malleable iron, austenitic stainless steel, high-temperature alloys, copper, brass, bronze, aluminum alloys, zinc alloy die castings, and plastics. Crater-resistant carbides should be used to machine plain carbon steel, alloy steel, tool steel, pearlitic malleable iron, nodular iron, other highly alloyed cast irons, ferritic stainless steel, martensitic stainless steel, and certain high-temperature alloys. Titanium carbides are recommended for taking high-speed finishing and semifinishing cuts on steel, especially the low-carbon, low-alloy steels, which are less abrasive and have a strong tendency to form a crater. They are also used to take light cuts on alloy cast iron and on

Copyright 2004, Industrial Press, Inc., New York, NY

some high-nickel alloys. Nonferrous materials, such as some aluminum alloys and brass, that are essentially nonabrasive may also be machined with titanium carbides. Abrasive materials and others that should not be machined with titanium carbides include gray cast iron, titanium alloys, cobalt- and nickel-base superalloys, stainless steel, bronze, many aluminum alloys, fiberglass, plastics, and graphite. The feed used should not exceed about 0.020 inch per revolution.

Coated carbides can be used to take cuts ranging from light finishing to heavy roughing on most materials that can be cut with these carbides. The coated carbides are recommended for machining all free-machining steels, all plain carbon and alloy steels, tool steels, martensitic and ferritic stainless steels, precipitation-hardening stainless steels, alloy cast iron, pearlitic and martensitic malleable iron, and nodular iron. They are also recommended for taking light finishing and roughing cuts on austenitic stainless steels. Coated carbides should not be used to machine nickel- and cobalt-base superalloys, titanium and titanium alloys, brass, bronze, aluminum alloys, pure metals, refractory metals, and nonmetals such as fiberglass, graphite, and plastics.

Ceramic Cutting Tool Materials: These are made from finely powdered aluminum oxide particles sintered into a hard dense structure without a binder material. Aluminum oxide is also combined with titanium carbide to form a composite, which is called a cermet. These materials have a very high hot hardness enabling very high cutting speeds to be used. For example, ceramic cutting tools have been used to cut AISI 1040 steel at a cutting speed of 18,000 fpm with a satisfactory tool life. However, much lower cutting speeds, in the range of 1000 to 4000 fpm and lower, are more common because of limitations placed by the machine tool, cutters, and chucks. Although most applications of ceramic and cermet cutting tool materials are for turning, they have also been used successfully for milling. Ceramics and cermets are relatively brittle and a special cutting edge preparation is required to prevent chipping or edge breakage. This preparation consists of honing or grinding a narrow flat land, 0.002 to 0.006 inch wide, on the cutting edge that is made about 30 degrees with respect to the tool face. For some heavy-duty applications, a wider land is used. The setup should be as rigid as possible and the feed rate should not normally exceed 0.020 inch, although 0.030 inch has been used successfully. Ceramics and cermets are recommended for roughing and finishing operations on all cast irons, plain carbon and alloy steels, and stainless steels. Materials up to a hardness of 60 Rockwell C Scale can be cut with ceramic and cermet cutting tools. These tools should not be used to machine aluminum and aluminum alloys, magnesium alloys, titanium, and titanium alloys.

Cast Nonferrous Alloy: Cutting tools of this alloy are made from tungsten, tantalum, chromium, and cobalt plus carbon. Other alloying elements are also used to produce materials with high temperature and wear resistance. These alloys cannot be softened by heat treatment and must be cast and ground to shape. The room-temperature hardness of cast nonferrous alloys is lower than for high-speed steel, but the hardness and wear resistance is retained to a higher temperature. The alloys are generally marketed under trade names such as Stellite, Crobalt, and Tantung. The initial cutting speed for cast nonferrous tools can be 20 to 50 per cent greater than the recommended cutting speed for high-speed steel as given in the accompanying tables.

Diamond Cutting Tools: These are available in three forms: single-crystal natural diamonds shaped to a cutting edge and mounted on a tool holder on a boring bar; polycrystalline diamond indexable inserts made from synthetic or natural diamond powders that have been compacted and sintered into a solid mass, and chemically vapor-deposited diamond. Single-crystal and polycrystalline diamond cutting tools are very wear-resistant, and are recommended for machining abrasive materials that cause other cutting tool materials to wear rapidly. Typical of the abrasive materials machined with single-crystal and polycrystalline diamond tools and cutting speeds used are the following: fiberglass, 300 to 1000 fpm; fused silica, 900 to 950 fpm; reinforced melamine plastics, 350 to 1000 fpm; reinforced phenolic plastics, 350 to 1000 fpm; thermosetting plastics, 300 to 2000 fpm; Teflon,

Copyright 2004, Industrial Press, Inc., New York, NY

600 fpm; nylon, 200 to 300 fpm; mica, 300 to 1000 fpm; graphite, 200 to 2000 fpm; babbitt bearing metal, 700 fpm; and aluminum-silicon alloys, 1000 to 2000 fpm. Another important application of diamond cutting tools is to produce fine surface finishes on soft nonferrous metals that are difficult to finish by other methods. Surface finishes of 1 to 2 microinches can be readily obtained with single-crystal diamond tools, and finishes down to 10 microinches can be obtained with polycrystalline diamond tools. In addition to babbitt and the aluminum-silicon alloys, other metals finished with diamond tools include: soft aluminum, 1000 to 2000 fpm; all wrought and cast aluminum alloys, 600 to 1500 fpm; copper, 1000 fpm; brass, 500 to 1000 fpm; bronze, 300 to 600 fpm; oilite bearing metal, 500 fpm; silver, gold, and platinum, 300 to 2500 fpm; and zinc, 1000 fpm. Ferrous alloys, such as cast iron and steel, should not be machined with diamond cutting tools because the high cutting temperatures generated will cause the diamond to transform into carbon.

Chemically Vapor-Deposited (CVD) Diamond: This is a new tool material offering performance characteristics well suited to highly abrasive or corrosive materials, and hard-to-machine composites. CVD diamond is available in two forms: thick-film tools, which are fabricated by brazing CVD diamond tips, approximately 0.020 inch (0.5 mm) thick, to carbide substrates; and thin-film tools, having a pure diamond coating over the rake and flank surfaces of a ceramic or carbide substrate.

CVD is pure diamond, made at low temperatures and pressures, with no metallic binder phase. This diamond purity gives CVD diamond tools extreme hardness, high abrasion resistance, low friction, high thermal conductivity, and chemical inertness. CVD tools are generally used as direct replacements for PCD (polycrystalline diamond) tools, primarily in finishing, semifinishing, and continuous turning applications of extremely wear-intensive materials. The small grain size of CVD diamond (ranging from less than 1 μm to 50 μm) yields superior surface finishes compared with PCD, and the higher thermal conductivity and better thermal and chemical stability of pure diamond allow CVD tools to operate at faster speeds without generating harmful levels of heat. The extreme hardness of CVD tools may also result in significantly longer tool life.

CVD diamond cutting tools are recommended for the following materials: aluminum and other ductile; nonferrous alloys such as copper, brass, and bronze; and highly abrasive composite materials such as graphite, carbon-carbon, carbon-filled phenolic, fiberglass, and honeycomb materials.

Cubic Boron Nitride (CBN): Next to diamond, CBN is the hardest known material. It will retain its hardness at a temperature of 1800°F and higher, making it an ideal cutting tool material for machining very hard and tough materials at cutting speeds beyond those possible with other cutting tool materials. Indexable inserts and cutting tool blanks made from this material consist of a layer, approximately 0.020 inch thick, of polycrystalline cubic boron nitride firmly bonded to the top of a cemented carbide substrate. Cubic boron nitride is recommended for rough and finish turning hardened plain carbon and alloy steels, hardened tool steels, hard cast irons, all hardness grades of gray cast iron, and superalloys. As a class, the superalloys are not as hard as hardened steel; however, their combination of high strength and tendency to deform plastically under the pressure of the cut, or gumminess, places them in the class of hard-to-machine materials. Conventional materials that can be readily machined with other cutting tool materials should not be machined with cubic boron nitride. Round indexable CBN inserts are recommended when taking severe cuts in order to provide maximum strength to the insert. When using square or triangular inserts, a large lead angle should be used, normally 15°, and whenever possible, 45°. A negative rake angle should always be used, which for most applications is negative 5°. The relief angle should be 5° to 9°. Although cubic boron nitride cutting tools can be used without a coolant, flooding the tool with a water-soluble type coolant is recommended.

Cutting Speed, Feed, Depth of Cut, Tool Wear, and Tool Life.— The cutting conditions that determine the rate of metal removal are the cutting speed, the feed rate, and the depth of cut. These cutting conditions and the nature of the material to be cut determine the

Copyright 2004, Industrial Press, Inc., New York, NY

power required to take the cut. The cutting conditions must be adjusted to stay within the power available on the machine tool to be used. Power requirements are discussed in Estimating Machining Power later in this section.

The cutting conditions must also be considered in relation to the tool life. Tool life is defined as the cutting time to reach a predetermined amount of wear, usually flank wear. Tool life is determined by assessing the time—the tool life—at which a given predetermined flank wear is reached (0.01, 0.015, 0.025, 0.03 inch, for example). This amount of wear is called the tool wear criterion, and its size depends on the tool grade used. Usually, a tougher grade can be used with a bigger flank wear, but for finishing operations, where close tolerances are required, the wear criterion is relatively small. Other wear criteria are a predetermined value of the machined surface roughness and the depth of the crater that develops on the rake face of the tool.

The ANSI standard, Specification For Tool Life Testing With Single-Point Tools (ANSI B94.55M-1985), defines the end of tool life as a given amount of wear on the flank of a tool. This standard is followed when making scientific machinability tests with single-point cutting tools in order to achieve uniformity in testing procedures so that results from different machinability laboratories can be readily compared. It is not practicable or necessary to follow this standard in the shop; however, it should be understood that the cutting conditions and tool life are related.

Tool life is influenced most by cutting speed, then by the feed rate, and least by the depth of cut. When the depth of cut is increased to about 10 times greater than the feed, a further increase in the depth of cut will have no significant effect on the tool life. This characteristic of the cutting tool performance is very important in determining the operating or cutting conditions for machining metals. Conversely, if the cutting speed or the feed is decreased, the increase in the tool life will be proportionately greater than the decrease in the cutting speed or the feed.

Tool life is reduced when either feed or cutting speed is increased. For example, the cutting speed and the feed may be increased if a shorter tool life is accepted; furthermore, the reduction in the tool life will be proportionately greater than the increase in the cutting speed or the feed. However, it is less well understood that a higher feed rate (feed/rev × speed) may result in a longer tool life if a higher feed/rev is used in combination with a lower cutting speed. This principle is well illustrated in the speed tables of this section, where two sets of feed and speed data are given (labeled *optimum* and *average*) that result in the same tool life. The *optimum* set results in a greater feed rate (i.e., increased productivity) although the feed/rev is higher and cutting speed lower than the *average* set. Complete instructions for using the speed tables and for estimating tool life are given in *How to Use the Feeds and Speeds Tables* starting on page 1022.

Selecting Cutting Conditions.— The first step in establishing the cutting conditions is to select the depth of cut. The depth of cut will be limited by the amount of metal that is to be machined from the workpiece, by the power available on the machine tool, by the rigidity of the workpiece and the cutting tool, and by the rigidity of the setup. The depth of cut has the least effect upon the tool life, so the heaviest possible depth of cut should always be used.

The second step is to select the feed (feed/rev for turning, drilling, and reaming, or feed/tooth for milling). The available power must be sufficient to make the required depth of cut at the selected feed. The maximum feed possible that will produce an acceptable surface finish should be selected.

The third step is to select the cutting speed. Although the accompanying tables provide recommended cutting speeds and feeds for many materials, experience in machining a certain material may form the best basis for adjusting the given cutting speeds to a particular job. However, in general, the depth of cut should be selected first, followed by the feed, and last the cutting speed.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. Tool Troubleshooting Check List

Problem	Tool Material	Remedy
Excessive flank wear—Tool life too short	Carbide	1. Change to harder, more wear-resistant grade 2. Reduce the cutting speed 3. Reduce the cutting speed and increase the feed to maintain production 4. Reduce the feed 5. For work-hardenable materials—increase the feed 6. Increase the lead angle 7. Increase the relief angles
	HSS	1. Use a coolant 2. Reduce the cutting speed 3. Reduce the cutting speed and increase the feed to maintain production 4. Reduce the feed 5. For work-hardenable materials — increase the feed 6. Increase the lead angle 7. Increase the relief angle
Excessive cratering	Carbide	1. Use a crater-resistant grade 2. Use a harder, more wear-resistant grade 3. Reduce the cutting speed 4. Reduce the feed 5. Widen the chip breaker groove
	HSS	1. Use a coolant 2. Reduce the cutting speed 3. Reduce the feed 4. Widen the chip breaker groove
Cutting edge chipping	Carbide	1. Increase the cutting speed 2. Lightly hone the cutting edge 3. Change to a tougher grade 4. Use negative-rake tools 5. Increase the lead angle 6. Reduce the feed 7. Reduce the depth of cut 8. Reduce the relief angles 9. If low cutting speed must be used, use a high-additive EP cutting fluid
	HSS	1. Use a high additive EP cutting fluid 2. Lightly hone the cutting edge before using 3. Increase the lead angle 4. Reduce the feed 5. Reduce the depth of cut 6. Use a negative rake angle 7. Reduce the relief angles
	Carbide and HSS	1. Check the setup for cause if chatter occurs 2. Check the grinding procedure for tool overheating 3. Reduce the tool overhang
Cutting edge deformation	Carbide	1. Change to a grade containing more tantalum 2. Reduce the cutting speed 3. Reduce the feed
Poor surface finish	Carbide	1. Increase the cutting speed 2. If low cutting speed must be used, use a high additive EP cutting fluid 4. For light cuts, use straight titanium carbide grade 5. Increase the nose radius 6. Reduce the feed 7. Increase the relief angles 8. Use positive rake tools

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. ***(Continued)*** **Tool Troubleshooting Check List**

Problem	Tool Material	Remedy
Poor surface finish *(Continued)*	HSS	1. Use a high additive EP cutting fluid 2. Increase the nose radius 3. Reduce the feed 4. Increase the relief angles 5. Increase the rake angles
	Diamond	1. Use diamond tool for soft materials
Notching at the depth of cut line	Carbide and HSS	1. Increase the lead angle 2. Reduce the feed

Cutting Speed Formulas

Most machining operations are conducted on machine tools having a rotating spindle. Cutting speeds are usually given in feet or meters per minute and these speeds must be converted to spindle speeds, in revolutions per minute, to operate the machine. Conversion is accomplished by use of the following formulas:

For U.S. units:

$$N = \frac{12V}{\pi D} = 3.82\frac{V}{D} \text{ rpm}$$

For metric units:

$$N = \frac{1000V}{\pi D} = 318.3\frac{V}{D} \text{ rpm}$$

where N is the spindle speed in revolutions per minute (rpm); V is the cutting speed in feet per minute (fpm) for U.S. units and meters per minute (m/min) for metric units. In turning, D is the diameter of the workpiece; in milling, drilling, reaming, and other operations that use a rotating tool, D is the cutter diameter in inches for U.S. units and in millimeters for metric units. $\pi = 3.1416$.

Example: The cutting speed for turning a 4-inch (101.6-mm) diameter bar has been found to be 575 fpm (175.3 m/min). Using both the inch and metric formulas, calculate the lathe spindle speed.

$$N = \frac{12V}{\pi D} = \frac{12 \times 575}{3.1416 \times 4} = 549 \text{ rpm} \qquad N = \frac{1000V}{\pi D} = \frac{1000 \times 175.3}{3.1416 \times 101.6} = 549 \text{ rpm}$$

When the cutting tool or workpiece diameter and the spindle speed in rpm are known, it is often necessary to calculate the cutting speed in feet or meters per minute. In this event, the following formulas are used.

For U.S. units:

$$V = \frac{\pi DN}{12} \text{ fpm}$$

For metric units:

$$V = \frac{\pi DN}{1000} \text{ m/min}$$

As in the previous formulas, N is the rpm and D is the diameter in inches for the U.S. unit formula and in millimeters for the metric formula.

Example: Calculate the cutting speed in feet per minute and in meters per minute if the spindle speed of a $\frac{3}{4}$-inch (19.05-mm) drill is 400 rpm.

$$V = \frac{\pi DN}{12} = \frac{\pi \times 0.75 \times 400}{12} = 78.5 \text{ fpm}$$

$$V = \frac{\pi DN}{1000} = \frac{\pi \times 19.05 \times 400}{1000} = 24.9 \text{ m/min}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Cutting Speeds and Equivalent RPM for Drills of Number and Letter Sizes

Size	Cutting Speed, Feet per Minute										
	30′	40′	50′	60′	70′	80′	90′	100′	110′	130′	150′
No.	Revolutions per Minute for Number Sizes										
1	503	670	838	1005	1173	1340	1508	1675	1843	2179	2513
2	518	691	864	1037	1210	1382	1555	1728	1901	2247	2593
4	548	731	914	1097	1280	1462	1645	1828	2010	2376	2741
6	562	749	936	1123	1310	1498	1685	1872	2060	2434	2809
8	576	768	960	1151	1343	1535	1727	1919	2111	2495	2879
10	592	790	987	1184	1382	1579	1777	1974	2171	2566	2961
12	606	808	1010	1213	1415	1617	1819	2021	2223	2627	3032
14	630	840	1050	1259	1469	1679	1889	2099	2309	2728	3148
16	647	863	1079	1295	1511	1726	1942	2158	2374	2806	3237
18	678	904	1130	1356	1582	1808	2034	2260	2479	2930	3380
20	712	949	1186	1423	1660	1898	2135	2372	2610	3084	3559
22	730	973	1217	1460	1703	1946	2190	2433	2676	3164	3649
24	754	1005	1257	1508	1759	2010	2262	2513	2764	3267	3769
26	779	1039	1299	1559	1819	2078	2338	2598	2858	3378	3898
28	816	1088	1360	1631	1903	2175	2447	2719	2990	3534	4078
30	892	1189	1487	1784	2081	2378	2676	2973	3270	3864	4459
32	988	1317	1647	1976	2305	2634	2964	3293	3622	4281	4939
34	1032	1376	1721	2065	2409	2753	3097	3442	3785	4474	5162
36	1076	1435	1794	2152	2511	2870	3228	3587	3945	4663	5380
38	1129	1505	1882	2258	2634	3010	3387	3763	4140	4892	5645
40	1169	1559	1949	2339	2729	3118	3508	3898	4287	5067	5846
42	1226	1634	2043	2451	2860	3268	3677	4085	4494	5311	6128
44	1333	1777	2221	2665	3109	3554	3999	4442	4886	5774	6662
46	1415	1886	2358	2830	3301	3773	4244	4716	5187	6130	7074
48	1508	2010	2513	3016	3518	4021	4523	5026	5528	6534	7539
50	1637	2183	2729	3274	3820	4366	4911	5457	6002	7094	8185
52	1805	2406	3008	3609	4211	4812	5414	6015	6619	7820	9023
54	2084	2778	3473	4167	4862	5556	6251	6945	7639	9028	10417
Size	Revolutions per Minute for Letter Sizes										
A	491	654	818	982	1145	1309	1472	1636	1796	2122	2448
B	482	642	803	963	1124	1284	1445	1605	1765	2086	2407
C	473	631	789	947	1105	1262	1420	1578	1736	2052	2368
D	467	622	778	934	1089	1245	1400	1556	1708	2018	2329
E	458	611	764	917	1070	1222	1375	1528	1681	1968	2292
F	446	594	743	892	1040	1189	1337	1486	1635	1932	2229
G	440	585	732	878	1024	1170	1317	1463	1610	1903	2195
H	430	574	718	862	1005	1149	1292	1436	1580	1867	2154
I	421	562	702	842	983	1123	1264	1404	1545	1826	2106
J	414	552	690	827	965	1103	1241	1379	1517	1793	2068
K	408	544	680	815	951	1087	1223	1359	1495	1767	2039
L	395	527	659	790	922	1054	1185	1317	1449	1712	1976
M	389	518	648	777	907	1036	1166	1295	1424	1683	1942
N	380	506	633	759	886	1012	1139	1265	1391	1644	1897
O	363	484	605	725	846	967	1088	1209	1330	1571	1813
P	355	473	592	710	828	946	1065	1183	1301	1537	1774
Q	345	460	575	690	805	920	1035	1150	1266	1496	1726
R	338	451	564	676	789	902	1014	1127	1239	1465	1690
S	329	439	549	659	769	878	988	1098	1207	1427	1646
T	320	426	533	640	746	853	959	1066	1173	1387	1600
U	311	415	519	623	727	830	934	1038	1142	1349	1557
V	304	405	507	608	709	810	912	1013	1114	1317	1520
W	297	396	495	594	693	792	891	989	1088	1286	1484
X	289	385	481	576	672	769	865	962	1058	1251	1443
Y	284	378	473	567	662	756	851	945	1040	1229	1418
Z	277	370	462	555	647	740	832	925	1017	1202	1387

For fractional drill sizes, use the following table.

Copyright 2004, Industrial Press, Inc., New York, NY

Revolutions per Minute for Various Cutting Speeds and Diameters

Dia., Inches	Cutting Speed, Feet per Minute											
	40	50	60	70	80	90	100	120	140	160	180	200
	Revolutions per Minute											
1/4	611	764	917	1070	1222	1376	1528	1834	2139	2445	2750	3056
5/16	489	611	733	856	978	1100	1222	1466	1711	1955	2200	2444
3/8	408	509	611	713	815	916	1018	1222	1425	1629	1832	2036
7/16	349	437	524	611	699	786	874	1049	1224	1398	1573	1748
1/2	306	382	459	535	611	688	764	917	1070	1222	1375	1528
9/16	272	340	407	475	543	611	679	813	951	1086	1222	1358
5/8	245	306	367	428	489	552	612	736	857	979	1102	1224
11/16	222	273	333	389	444	500	555	666	770	888	999	1101
3/4	203	254	306	357	408	458	508	610	711	813	914	1016
13/16	190	237	284	332	379	427	474	569	664	758	853	948
7/8	175	219	262	306	349	392	438	526	613	701	788	876
15/16	163	204	244	285	326	366	407	488	570	651	733	814
1	153	191	229	267	306	344	382	458	535	611	688	764
1 1/16	144	180	215	251	287	323	359	431	503	575	646	718
1 1/8	136	170	204	238	272	306	340	408	476	544	612	680
1 3/16	129	161	193	225	258	290	322	386	451	515	580	644
1 1/4	123	153	183	214	245	274	306	367	428	490	551	612
1 5/16	116	146	175	204	233	262	291	349	407	466	524	582
1 3/8	111	139	167	195	222	250	278	334	389	445	500	556
1 7/16	106	133	159	186	212	239	265	318	371	424	477	530
1 1/2	102	127	153	178	204	230	254	305	356	406	457	508
1 9/16	97.6	122	146	171	195	220	244	293	342	390	439	488
1 5/8	93.9	117	141	165	188	212	234	281	328	374	421	468
1 11/16	90.4	113	136	158	181	203	226	271	316	362	407	452
1 3/4	87.3	109	131	153	175	196	218	262	305	349	392	436
1 7/8	81.5	102	122	143	163	184	204	244	286	326	367	408
2	76.4	95.5	115	134	153	172	191	229	267	306	344	382
2 1/8	72.0	90.0	108	126	144	162	180	216	252	288	324	360
2 1/4	68.0	85.5	102	119	136	153	170	204	238	272	306	340
2 3/8	64.4	80.5	96.6	113	129	145	161	193	225	258	290	322
2 1/2	61.2	76.3	91.7	107	122	138	153	184	213	245	275	306
2 5/8	58.0	72.5	87.0	102	116	131	145	174	203	232	261	290
2 3/4	55.6	69.5	83.4	97.2	111	125	139	167	195	222	250	278
2 7/8	52.8	66.0	79.2	92.4	106	119	132	158	185	211	238	264
3	51.0	63.7	76.4	89.1	102	114	127	152	178	203	228	254
3 1/8	48.8	61.0	73.2	85.4	97.6	110	122	146	171	195	219	244
3 1/4	46.8	58.5	70.2	81.9	93.6	105	117	140	164	188	211	234
3 3/8	45.2	56.5	67.8	79.1	90.4	102	113	136	158	181	203	226
3 1/2	43.6	54.5	65.5	76.4	87.4	98.1	109	131	153	174	196	218
3 5/8	42.0	52.5	63.0	73.5	84.0	94.5	105	126	147	168	189	210
3 3/4	40.8	51.0	61.2	71.4	81.6	91.8	102	122	143	163	184	205
3 7/8	39.4	49.3	59.1	69.0	78.8	88.6	98.5	118	138	158	177	197
4	38.2	47.8	57.3	66.9	76.4	86.0	95.6	115	134	153	172	191
4 1/4	35.9	44.9	53.9	62.9	71.8	80.8	89.8	108	126	144	162	180
4 1/2	34.0	42.4	51.0	59.4	67.9	76.3	84.8	102	119	136	153	170
4 3/4	32.2	40.2	48.2	56.3	64.3	72.4	80.4	96.9	113	129	145	161
5	30.6	38.2	45.9	53.5	61.1	68.8	76.4	91.7	107	122	138	153
5 1/4	29.1	36.4	43.6	50.9	58.2	65.4	72.7	87.2	102	116	131	145
5 1/2	27.8	34.7	41.7	48.6	55.6	62.5	69.4	83.3	97.2	111	125	139
5 3/4	26.6	33.2	39.8	46.5	53.1	59.8	66.4	80.0	93.0	106	120	133
6	25.5	31.8	38.2	44.6	51.0	57.2	63.6	76.3	89.0	102	114	127
6 1/4	24.4	30.6	36.7	42.8	48.9	55.0	61.1	73.3	85.5	97.7	110	122
6 1/2	23.5	29.4	35.2	41.1	47.0	52.8	58.7	70.4	82.2	93.9	106	117
6 3/4	22.6	28.3	34.0	39.6	45.3	50.9	56.6	67.9	79.2	90.6	102	113
7	21.8	27.3	32.7	38.2	43.7	49.1	54.6	65.5	76.4	87.4	98.3	109
7 1/4	21.1	26.4	31.6	36.9	42.2	47.4	52.7	63.2	73.8	84.3	94.9	105
7 1/2	20.4	25.4	30.5	35.6	40.7	45.8	50.9	61.1	71.0	81.4	91.6	102
7 3/4	19.7	24.6	29.5	34.4	39.4	44.3	49.2	59.0	68.9	78.7	88.6	98.4
8	19.1	23.9	28.7	33.4	38.2	43.0	47.8	57.4	66.9	76.5	86.0	95.6

Copyright 2004, Industrial Press, Inc., New York, NY

Revolutions per Minute for Various Cutting Speeds and Diameters

Dia., Inches	Cutting Speed, Feet per Minute											
	225	250	275	300	325	350	375	400	425	450	500	550
	Revolutions per Minute											
1/4	3438	3820	4202	4584	4966	5348	5730	6112	6493	6875	7639	8403
5/16	2750	3056	3362	3667	3973	4278	4584	4889	5195	5501	6112	6723
3/8	2292	2546	2801	3056	3310	3565	3820	4074	4329	4584	5093	5602
7/16	1964	2182	2401	2619	2837	3056	3274	3492	3710	3929	4365	4802
1/2	1719	1910	2101	2292	2483	2675	2866	3057	3248	3439	3821	4203
9/16	1528	1698	1868	2037	2207	2377	2547	2717	2887	3056	3396	3736
5/8	1375	1528	1681	1834	1987	2139	2292	2445	2598	2751	3057	3362
11/16	1250	1389	1528	1667	1806	1941	2084	2223	2362	2501	2779	3056
3/4	1146	1273	1401	1528	1655	1783	1910	2038	2165	2292	2547	2802
13/16	1058	1175	1293	1410	1528	1646	1763	1881	1998	2116	2351	2586
7/8	982	1091	1200	1310	1419	1528	1637	1746	1855	1965	2183	2401
15/16	917	1019	1120	1222	1324	1426	1528	1630	1732	1834	2038	2241
1	859	955	1050	1146	1241	1337	1432	1528	1623	1719	1910	2101
1 1/16	809	899	988	1078	1168	1258	1348	1438	1528	1618	1798	1977
1 1/8	764	849	933	1018	1103	1188	1273	1358	1443	1528	1698	1867
1 3/16	724	804	884	965	1045	1126	1206	1287	1367	1448	1609	1769
1 1/4	687	764	840	917	993	1069	1146	1222	1299	1375	1528	1681
1 5/16	654	727	800	873	946	1018	1091	1164	1237	1309	1455	1601
1 3/8	625	694	764	833	903	972	1042	1111	1181	1250	1389	1528
1 7/16	598	664	730	797	863	930	996	1063	1129	1196	1329	1461
1 1/2	573	636	700	764	827	891	955	1018	1082	1146	1273	1400
1 9/16	550	611	672	733	794	855	916	978	1039	1100	1222	1344
1 5/8	528	587	646	705	764	822	881	940	999	1057	1175	1293
1 11/16	509	566	622	679	735	792	849	905	962	1018	1132	1245
1 3/4	491	545	600	654	709	764	818	873	927	982	1091	1200
1 13/16	474	527	579	632	685	737	790	843	895	948	1054	1159
1 7/8	458	509	560	611	662	713	764	815	866	917	1019	1120
1 15/16	443	493	542	591	640	690	739	788	838	887	986	1084
2	429	477	525	573	620	668	716	764	811	859	955	1050
2 1/8	404	449	494	539	584	629	674	719	764	809	899	988
2 1/4	382	424	468	509	551	594	636	679	721	764	849	933
2 3/8	362	402	442	482	522	563	603	643	683	724	804	884
2 1/2	343	382	420	458	496	534	573	611	649	687	764	840
2 5/8	327	363	400	436	472	509	545	582	618	654	727	800
2 3/4	312	347	381	416	451	486	520	555	590	625	694	763
2 7/8	299	332	365	398	431	465	498	531	564	598	664	730
3	286	318	350	381	413	445	477	509	541	572	636	700
3 1/8	274	305	336	366	397	427	458	488	519	549	611	672
3 1/4	264	293	323	352	381	411	440	470	499	528	587	646
3 3/8	254	283	311	339	367	396	424	452	481	509	566	622
3 1/2	245	272	300	327	354	381	409	436	463	490	545	600
3 5/8	237	263	289	316	342	368	395	421	447	474	527	579
3 3/4	229	254	280	305	331	356	382	407	433	458	509	560
3 7/8	221	246	271	295	320	345	369	394	419	443	493	542
4	214	238	262	286	310	334	358	382	405	429	477	525
4 1/4	202	224	247	269	292	314	337	359	383	404	449	494
4 1/2	191	212	233	254	275	297	318	339	360	382	424	466
4 3/4	180	201	221	241	261	281	301	321	341	361	402	442
5	171	191	210	229	248	267	286	305	324	343	382	420
5 1/4	163	181	199	218	236	254	272	290	308	327	363	399
5 1/2	156	173	190	208	225	242	260	277	294	312	347	381
5 3/4	149	166	182	199	215	232	249	265	282	298	332	365
6	143	159	174	190	206	222	238	254	270	286	318	349
6 1/4	137	152	168	183	198	213	229	244	259	274	305	336
6 1/2	132	146	161	176	190	205	220	234	249	264	293	322
6 3/4	127	141	155	169	183	198	212	226	240	254	283	311
7	122	136	149	163	177	190	204	218	231	245	272	299
7 1/4	118	131	144	158	171	184	197	210	223	237	263	289
7 1/2	114	127	139	152	165	178	190	203	216	229	254	279
7 3/4	111	123	135	148	160	172	185	197	209	222	246	271
8	107	119	131	143	155	167	179	191	203	215	238	262

Copyright 2004, Industrial Press, Inc., New York, NY

Revolutions per Minute for Various Cutting Speeds and Diameters (Metric Units)

Dia., mm	Cutting Speed, Meters per Minute											
	5	6	8	10	12	16	20	25	30	35	40	45
	Revolutions per Minute											
5	318	382	509	637	764	1019	1273	1592	1910	2228	2546	2865
6	265	318	424	530	637	849	1061	1326	1592	1857	2122	2387
8	199	239	318	398	477	637	796	995	1194	1393	1592	1790
10	159	191	255	318	382	509	637	796	955	1114	1273	1432
12	133	159	212	265	318	424	531	663	796	928	1061	1194
16	99.5	119	159	199	239	318	398	497	597	696	796	895
20	79.6	95.5	127	159	191	255	318	398	477	557	637	716
25	63.7	76.4	102	127	153	204	255	318	382	446	509	573
30	53.1	63.7	84.9	106	127	170	212	265	318	371	424	477
35	45.5	54.6	72.8	90.9	109	145	182	227	273	318	364	409
40	39.8	47.7	63.7	79.6	95.5	127	159	199	239	279	318	358
45	35.4	42.4	56.6	70.7	84.9	113	141	177	212	248	283	318
50	31.8	38.2	51	63.7	76.4	102	127	159	191	223	255	286
55	28.9	34.7	46.3	57.9	69.4	92.6	116	145	174	203	231	260
60	26.6	31.8	42.4	53.1	63.7	84.9	106	133	159	186	212	239
65	24.5	29.4	39.2	49	58.8	78.4	98	122	147	171	196	220
70	22.7	27.3	36.4	45.5	54.6	72.8	90.9	114	136	159	182	205
75	21.2	25.5	34	42.4	51	68	84.9	106	127	149	170	191
80	19.9	23.9	31.8	39.8	47.7	63.7	79.6	99.5	119	139	159	179
90	17.7	21.2	28.3	35.4	42.4	56.6	70.7	88.4	106	124	141	159
100	15.9	19.1	25.5	31.8	38.2	51	63.7	79.6	95.5	111	127	143
110	14.5	17.4	23.1	28.9	34.7	46.2	57.9	72.3	86.8	101	116	130
120	13.3	15.9	21.2	26.5	31.8	42.4	53.1	66.3	79.6	92.8	106	119
130	12.2	14.7	19.6	24.5	29.4	39.2	49	61.2	73.4	85.7	97.9	110
140	11.4	13.6	18.2	22.7	27.3	36.4	45.5	56.8	68.2	79.6	90.9	102
150	10.6	12.7	17	21.2	25.5	34	42.4	53.1	63.7	74.3	84.9	95.5
160	9.9	11.9	15.9	19.9	23.9	31.8	39.8	49.7	59.7	69.6	79.6	89.5
170	9.4	11.2	15	18.7	22.5	30	37.4	46.8	56.2	65.5	74.9	84.2
180	8.8	10.6	14.1	17.7	21.2	28.3	35.4	44.2	53.1	61.9	70.7	79.6
190	8.3	10	13.4	16.8	20.1	26.8	33.5	41.9	50.3	58.6	67	75.4
200	8	39.5	12.7	15.9	19.1	25.5	31.8	39.8	47.7	55.7	63.7	71.6
220	7.2	8.7	11.6	14.5	17.4	23.1	28.9	36.2	43.4	50.6	57.9	65.1
240	6.6	8	10.6	13.3	15.9	21.2	26.5	33.2	39.8	46.4	53.1	59.7
260	6.1	7.3	9.8	12.2	14.7	19.6	24.5	30.6	36.7	42.8	49	55.1
280	5.7	6.8	9.1	11.4	13.6	18.2	22.7	28.4	34.1	39.8	45.5	51.1
300	5.3	6.4	8.5	10.6	12.7	17	21.2	26.5	31.8	37.1	42.4	47.7
350	4.5	5.4	7.3	9.1	10.9	14.6	18.2	22.7	27.3	31.8	36.4	40.9
400	4	4.8	6.4	8	9.5	12.7	15.9	19.9	23.9	27.9	31.8	35.8
450	3.5	4.2	5.7	7.1	8.5	11.3	14.1	17.7	21.2	24.8	28.3	31.8
500	3.2	3.8	5.1	6.4	7.6	10.2	12.7	15.9	19.1	22.3	25.5	28.6

Copyright 2004, Industrial Press, Inc., New York, NY

Revolutions per Minute for Various Cutting Speeds and Diameters (Metric Units)

Dia., mm	Cutting Speed, Meters per Minute											
	50	55	60	65	70	75	80	85	90	95	100	200
	Revolutions per Minute											
5	3183	3501	3820	4138	4456	4775	5093	5411	5730	6048	6366	12,732
6	2653	2918	3183	3448	3714	3979	4244	4509	4775	5039	5305	10,610
8	1989	2188	2387	2586	2785	2984	3183	3382	3581	3780	3979	7958
10	1592	1751	1910	2069	2228	2387	2546	2706	2865	3024	3183	6366
12	1326	1459	1592	1724	1857	1989	2122	2255	2387	2520	2653	5305
16	995	1094	1194	1293	1393	1492	1591	1691	1790	1890	1989	3979
20	796	875	955	1034	1114	1194	1273	1353	1432	1512	1592	3183
25	637	700	764	828	891	955	1019	1082	1146	1210	1273	2546
30	530	584	637	690	743	796	849	902	955	1008	1061	2122
35	455	500	546	591	637	682	728	773	819	864	909	1818
40	398	438	477	517	557	597	637	676	716	756	796	1592
45	354	389	424	460	495	531	566	601	637	672	707	1415
50	318	350	382	414	446	477	509	541	573	605	637	1273
55	289	318	347	376	405	434	463	492	521	550	579	1157
60	265	292	318	345	371	398	424	451	477	504	530	1061
65	245	269	294	318	343	367	392	416	441	465	490	979
70	227	250	273	296	318	341	364	387	409	432	455	909
75	212	233	255	276	297	318	340	361	382	403	424	849
80	199	219	239	259	279	298	318	338	358	378	398	796
90	177	195	212	230	248	265	283	301	318	336	354	707
100	159	175	191	207	223	239	255	271	286	302	318	637
110	145	159	174	188	203	217	231	246	260	275	289	579
120	133	146	159	172	186	199	212	225	239	252	265	530
130	122	135	147	159	171	184	196	208	220	233	245	490
140	114	125	136	148	159	171	182	193	205	216	227	455
150	106	117	127	138	149	159	170	180	191	202	212	424
160	99.5	109	119	129	139	149	159	169	179	189	199	398
170	93.6	103	112	122	131	140	150	159	169	178	187	374
180	88.4	97.3	106	115	124	133	141	150	159	168	177	354
190	83.8	92.1	101	109	117	126	134	142	151	159	167	335
200	79.6	87.5	95.5	103	111	119	127	135	143	151	159	318
220	72.3	79.6	86.8	94	101	109	116	123	130	137	145	289
240	66.3	72.9	79.6	86.2	92.8	99.5	106	113	119	126	132	265
260	61.2	67.3	73.4	79.6	85.7	91.8	97.9	104	110	116	122	245
280	56.8	62.5	68.2	73.9	79.6	85.3	90.9	96.6	102	108	114	227
300	53.1	58.3	63.7	69	74.3	79.6	84.9	90.2	95.5	101	106	212
350	45.5	50	54.6	59.1	63.7	68.2	72.8	77.3	81.8	99.1	91	182
400	39.8	43.8	47.7	51.7	55.7	59.7	63.7	67.6	71.6	75.6	79.6	159
450	35.4	38.9	42.4	46	49.5	53.1	56.6	60.1	63.6	67.2	70.7	141
500	31.8	35	38.2	41.4	44.6	47.7	50.9	54.1	57.3	60.5	63.6	127

Copyright 2004, Industrial Press, Inc., New York, NY

SPEED AND FEED TABLES

How to Use the Feeds and Speeds Tables

Introduction to the Feed and Speed Tables.— The principal tables of feed and speed values are listed in the table below. In this section, Tables 1 through 9 give data for turning, Tables 10 through 15e give data for milling, and Tables 17 through 23 give data for reaming, drilling, threading.

The materials in these tables are categorized by description, and Brinell hardness number (Bhn) range or material condition. So far as possible, work materials are grouped by similar machining characteristics. The types of cutting tools (HSS end mill, for example) are identified in one or more rows across the tops of the tables. Other important details concerning the use of the tables are contained in the footnotes to Tables 1, 10 and 17. Information concerning specific cutting tool grades is given in notes at the end of each table.

Principal Speed andFeed Tables

Feeds and Speeds for Turning
Table 1. Cutting Feeds and Speeds for Turning Plain Carbon and Alloy Steels
Table 2. Cutting Feeds and Speeds for Turning Tool Steels
Table 3. Cutting Feeds and Speeds for Turning Stainless Steels
Table 4a. Cutting Feeds and Speeds for Turning Ferrous Cast Metals
Table 4b. Cutting Feeds and Speeds for Turning Ferrous Cast Metals
Table 5c. Cutting-Speed Adjustment Factors for Turning with HSS Tools
Table 5a. Turning-Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle
Table 5b. Tool Life Factors for Turning with Carbides, Ceramics, Cermets, CBN, and Polycrystalline Diamond
Table 6. Cutting Feeds and Speeds for Turning Copper Alloys
Table 7. Cutting Feeds and Speeds for Turning Titanium and Titanium Alloys
Table 8. Cutting Feeds and Speeds for Turning Light Metals
Table 9. Cutting Feeds and Speeds for Turning Superalloys
Feeds and Speeds for Milling
Table 10. Cutting Feeds and Speeds for Milling Aluminum Alloys
Table 11. Cutting Feeds and Speeds for Milling Plain Carbon and Alloy Steels
Table 12. Cutting Feeds and Speeds for Milling Tool Steels
Table 13. Cutting Feeds and Speeds for Milling Stainless Steels
Table 14. Cutting Feeds and Speeds for Milling Ferrous Cast Metals
Table 15a. Recommended Feed in Inches per Tooth (ft) for Milling with High Speed Steel Cutters
Table 15b. End Milling (Full Slot) Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle
Table 15c. End, Slit, and Side Milling Speed Adjustment Factors for Radial Depth of Cut
Table 15d. Face Milling Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle
Table 15e. Tool Life Adjustment Factors for Face Milling, End Milling, Drilling, and Reaming
Table 16. Cutting Tool Grade Descriptions and Common Vendor Equivalents
Feeds and Speeds for Drilling, Reaming, and Threading
Table 17. Feeds and Speeds for Drilling, Reaming, and Threading Plain Carbon and Alloy Steels
Table 18. Feeds and Speeds for Drilling, Reaming, and Threading Tool Steels
Table 19. Feeds and Speeds for Drilling, Reaming, and Threading Stainless Steels
Table 20. Feeds and Speeds for Drilling, Reaming, and Threading Ferrous Cast Metals
Table 21. Feeds and Speeds for Drilling, Reaming, and Threading Light Metals
Table 22. Feed and Diameter Speed Adjustment Factors for HSS Twist Drills and Reamers
Table 23. Feeds and Speeds for Drilling and Reaming Copper Alloys

Copyright 2004, Industrial Press, Inc., New York, NY

Each of the cutting speed tables in this section contains two distinct types of cutting speed data. The speed columns at the left of each table contain traditional Handbook cutting speeds for use with high-speed steel (HSS) tools. For many years, this extensive collection of cutting data has been used successfully as starting speed values for turning, milling, drilling, and reaming operations. Instructions and adjustment factors for use with these speeds are given in Table 5c (feed and depth-of-cut factors) for turning, and in Table 15a (feed, depth of cut, and cutter diameter) for milling. Feeds for drilling and reaming are discussed in Using the Feed and Speed Tables for Drilling, Reaming, and Threading. With traditional speeds and feeds, tool life may vary greatly from material to material, making it very difficult to plan efficient cutting operations, in particular for setting up unattended jobs on CNC equipment where the tool life must exceed cutting time, or at least be predictable so that tool changes can be scheduled. This limitation is reduced by using the combined feed/speed data contained in the remaining columns of the speed tables.

The combined feed/speed portion of the speed tables gives two sets of feed and speed data for each material represented. These feed/speed pairs are the *optimum* and *average* data (identified by *Opt.* and *Avg.*); the *optimum* set is always on the left side of the column and the *average* set is on the right. The *optimum* feed/speed data are approximate values of feed and speed that achieve minimum-cost machining by combining a high productivity rate with low tooling cost at a fixed tool life. The *average* feed/speed data are expected to achieve approximately the same tool life and tooling costs, but productivity is usually lower, so machining costs are higher. The data in this portion of the tables are given in the form of two numbers, of which the first is the feed in thousandths of an inch per revolution (or per tooth, for milling) and the second is the cutting speed in feet per minute. For example, the feed/speed set 15/215 represents a feed of 0.015 in./rev at a speed of 215 fpm. Blank cells in the data tables indicate that feed/speed data for these materials were not available at the time of publication.

Generally, the feed given in the *optimum* set should be interpreted as the maximum safe feed for the given work material and cutting tool grade, and the use of a greater feed may result in premature tool wear or tool failure before the end of the expected tool life. The primary exception to this rule occurs in milling, where the feed may be greater than the *optimum* feed if the radial depth of cut is less than the value established in the table footnote; this topic is covered later in the milling examples. Thus, except for milling, the speed and tool life adjustment tables, to be discussed later, do not permit feeds that are greater than the *optimum* feed. On the other hand, the speed and tool life adjustment factors often result in cutting speeds that are well outside the given *optimum* to *average* speed range.

The combined feed/speed data in this section were contributed by Dr. Colding of Colding International Corp., Ann Arbor, MI. The speed, feed, and tool life calculations were made by means of a special computer program and a large database of cutting speed and tool life testing data. The COMP computer program uses tool life equations that are extensions of the F. W. Taylor tool life equation, first proposed in the early 1900s. The Colding tool life equations use a concept called equivalent chip thickness (*ECT*), which simplifies cutting speed and tool life predictions, and the calculation of cutting forces, torque, and power requirements. *ECT* is a basic metal cutting parameter that combines the four basic turning variables (depth of cut, lead angle, nose radius, and feed per revolution) into one basic parameter. For other metal cutting operations (milling, drilling, and grinding, for example), *ECT* also includes additional variables such as the number of teeth, width of cut, and cutter diameter. The *ECT* concept was first presented in 1931 by Prof. R. Woxen, who showed that equivalent chip thickness is a basic metal cutting parameter for high-speed cutting tools. Dr. Colding later extended the theory to include other tool materials and metal cutting operations, including grinding.

The equivalent chip thickness is defined by $ECT = A/CEL$, where A is the cross-sectional area of the cut (approximately equal to the feed times the depth of cut), and CEL is the cutting edge length or tool contact rubbing length. *ECT* and several other terms related to tool

Copyright 2004, Industrial Press, Inc., New York, NY

geometry are illustrated in Figs. 1 and 2. Many combinations of feed, lead angle, nose radius and cutter diameter, axial and radial depth of cut, and numbers of teeth can give the same value of *ECT*. However, for a constant cutting speed, no matter how the depth of cut, feed, or lead angle, etc., are varied, if a constant value of *ECT* is maintained, the tool life will also remain constant. A constant value of *ECT* means that a constant cutting speed gives a constant tool life and an increase in speed results in a reduced tool life. Likewise, if *ECT* were increased and cutting speed were held constant, as illustrated in the generalized cutting speed vs. *ECT* graph that follows, tool life would be reduced.



a = depth of cut
$A = A'$ = chip cross-sectional area
$CEL = CELe$ = engaged cutting edge length
ECT = equivalent chip thickness $= A'/CEL$
f = feed/rev
r = nose radius
LA = lead angle (U.S.)
$LA(ISO)$ = 90–LA

Fig. 1. Cutting Geometry, Equivalent Chip Thickness, and Cutting Edge Length



Fig. 2. Cutting Geometry for Turning

In the tables, the *optimum* feed/speed data have been calculated by COMP to achieve a fixed tool life based on the maximum *ECT* that will result in successful cutting, without premature tool wear or early tool failure. The same tool life is used to calculate the *average* feed/speed data, but these values are based on one-half of the maximum *ECT*. Because the data are not linear except over a small range of values, both *optimum* and *average* sets are required to adjust speeds for feed, lead angle, depth of cut, and other factors.

Copyright 2004, Industrial Press, Inc., New York, NY

Tool life is the most important factor in a machining system, so feeds and speeds cannot be selected as simple numbers, but must be considered with respect to the many parameters that influence tool life. The accuracy of the combined feed/speed data presented is believed to be very high. However, machining is a variable and complicated process and use of the feed and speed tables requires the user to follow the instructions carefully to achieve good predictability. The results achieved, therefore, may vary due to material condition, tool material, machine setup, and other factors, and cannot be guaranteed.

The feed values given in the tables are valid for the standard tool geometries and fixed depths of cut that are identified in the table footnotes. If the cutting parameters and tool geometry established in the table footnotes are maintained, turning operations using either the *optimum* or *average* feed/speed data (Tables 1 through 9) should achieve a constant tool life of approximately 15 minutes; tool life for milling, drilling, reaming, and threading data (Tables 10 through 14 and Tables 17 through 22) should be approximately 45 minutes. The reason for the different economic tool lives is the higher tooling cost associated with milling-drilling operations than for turning. If the cutting parameters or tool geometry are different from those established in the table footnotes, the same tool life (15 or 45 minutes) still may be maintained by applying the appropriate speed adjustment factors, or tool life may be increased or decreased using tool life adjustment factors. The use of the speed and tool life adjustment factors is described in the examples that follow.

Both the *optimum* and *average* feed/speed data given are reasonable values for effective cutting. However, the *optimum* set with its higher feed and lower speed (always the left entry in each table cell) will usually achieve greater productivity. In Table 1, for example, the two entries for turning 1212 free-machining plain carbon steel with uncoated carbide are 17⁄805 and 8⁄1075. These values indicate that a feed of 0.017 in./rev and a speed of 805 ft/min, or a feed of 0.008 in./rev and a speed of 1075 ft/min can be used for this material. The tool life, in each case, will be approximately 15 minutes. If one of these feed and speed pairs is assigned an arbitrary cutting time of 1 minute, then the relative cutting time of the second pair to the first is equal to the ratio of their respective feed × speed products. Here, the same amount of material that can be cut in 1 minute, at the higher feed and lower speed (17⁄805), will require 1.6 minutes at the lower feed and higher speed (8⁄1075) because 17 × 805/(8 × 1075) = 1.6 minutes.



Cutting Speed versus Equivalent Chip Thickness with Tool Life as a Parameter

Copyright 2004, Industrial Press, Inc., New York, NY

Speed and Feed Tables for Turning.— Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text.

Examples Using the Feed and Speed Tables for Turning: The examples that follow give instructions for determining cutting speeds for turning. In general, the same methods are also used to find cutting speeds for milling, drilling, reaming, and threading, so reading through these examples may bring some additional insight to those other metalworking processes as well. The first step in determining cutting speeds is to locate the work material in the left column of the appropriate table for turning, milling, or drilling, reaming, and threading.

Example 1, Turning: Find the cutting speed for turning SAE 1074 plain carbon steel of 225 to 275 Brinell hardness, using an uncoated carbide insert, a feed of 0.015 in./rev, and a depth of cut of 0.1 inch.

In Table 1, feed and speed data for two types of uncoated carbide tools are given, one for hard tool grades, the other for tough tool grades. In general, use the speed data from the tool category that most closely matches the tool to be used because there are often significant differences in the speeds and feeds for different tool grades. From the uncoated carbide hard grade values, the *optimum* and *average* feed/speed data given in Table 1 are 17⁄615 and 8⁄815, or 0.017 in./rev at 615 ft/min and 0.008 in./rev at 815 ft/min. Because the selected feed (0.015 in./rev) is different from either of the feeds given in the table, the cutting speed must be adjusted to match the feed. The other cutting parameters to be used must also be compared with the general tool and cutting parameters given in the speed tables to determine if adjustments need to be made for these parameters as well. The general tool and cutting parameters for turning, given in the footnote to Table 1, are depth of cut = 0.1 inch, lead angle = 15°, and tool nose radius = $\frac{3}{64}$ inch.

Table 5a is used to adjust the cutting speeds for turning (from Tables 1 through 9) for changes in feed, depth of cut, and lead angle. The new cutting speed V is found from $V = V_{opt} \times F_f \times F_d$, where V_{opt} is the *optimum* speed from the table (always the lower of the two speeds given), and F_f and F_d are the adjustment factors from Table 5a for feed and depth of cut, respectively.

To determine the two factors F_f and F_d, calculate the ratio of the selected feed to the *optimum* feed, 0.015⁄0.017 = 0.9, and the ratio of the two given speeds V_{avg} and V_{opt}, 815⁄615 = 1.35 (approximately). The feed factor $F_d = 1.07$ is found in Table 5a at the intersection of the feed ratio row and the speed ratio column. The depth-of-cut factor $F_d = 1.0$ is found in the same row as the feed factor in the column for depth of cut = 0.1 inch and lead angle = 15°, or for a tool with a 45° lead angle, $F_d = 1.18$. The final cutting speed for a 15° lead angle is $V = V_{opt} \times F_f \times F_d = 615 \times 1.07 \times 1.0 = 658$ fpm. Notice that increasing the lead angle tends to permit higher cutting speeds; such an increase is also the general effect of increasing the tool nose radius, although nose radius correction factors are not included in this table. Increasing lead angle also increases the radial pressure exerted by the cutting tool on the workpiece, which may cause unfavorable results on long, slender workpieces.

Example 2, Turning: For the same material and feed as the previous example, what is the cutting speed for a 0.4-inch depth of cut and a 45° lead angle?

As before, the feed is 0.015 in./rev, so F_f is 1.07, but $F_d = 1.03$ for depth of cut equal to 0.4 inch and a 45° lead angle. Therefore, $V = 615 \times 1.07 \times 1.03 = 676$ fpm. Increasing the lead angle from 15° to 45° permits a much greater (four times) depth of cut, at the same feed and nearly constant speed. Tool life remains constant at 15 minutes. *(Continued on page 1036)*

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Cutting Feeds and Speeds for Turning Plain Carbon and Alloy Steels

Material AISI/SAE Designation	Brinell Hardness	Tool Material															
		HSS	Uncoated Carbide				Coated Carbide				Ceramic				Cermet	
			Hard		Tough		Hard		Tough		Hard		Tough			
		Speed (fpm)	**f** = feed (0.001 in./rev), **s** = speed (ft/min)													
			Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Free-machining plain carbon steels (resulfurized): 1212, 1213, 1215	100–150	150	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	805	1075	405	555	1165	1295	850	1200	3340	4985	1670	2500	1610	2055
	150–200	160	**f**	17	8	36	17	28	13	28	13	15	8	15	8	7	3
			s	745	935	345	470	915	1130	785	1110	1795	2680	1485	2215	1490	1815
1108, 1109, 1115, 1117, 1118, 1120, 1126, 1211	100–150	130	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
	150–200	120	**s**	730	990	300	430	1090	1410	780	1105	1610	2780	1345	2005	1355	1695
	175–225	120	**f**	17	8	36	17	17	8	28	13	13	7	13	7		
			s	615	815	300	405	865	960	755	960	1400	1965	1170	1640		
1132, 1137, 1139, 1140, 1144, 1146, 1151	275–325	75															
	325–375	50	**f**	17	8	36	17	17	8	28	13	10	5	10	5		
			s	515	685	235	340	720	805	650	810	1430	1745	1070	1305		
	375–425	40															
(Leaded): 11L17, 11L18, 12L13, 12L14	100–150	140															
	150–200	145	**f**	17	8	36	17	28	13	28	13	15	8	15	8	7	3
			s	745	935	345	470	915	1130	785	1110	1795	2680	1485	2215	1490	1815
	200–250	110	**f**	17	8	36	17	17	8	28	13	13	7	13	7		
			s	615	815	300	405	865	960	755	960	1400	1965	1170	1640		
Plain carbon steels: 1006, 1008, 1009, 1010, 1012, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1513, 1514	100–125	120	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	805	1075	405	555	1165	1295	850	1200	3340	4985	1670	2500	1610	2055
	125–175	110	**f**	17	8	36	17	28	13	28	13	15	8	15	8	7	3
			s	745	935	345	470	915	1130	785	1110	1795	2680	1485	2215	1490	1815
	175–225	90		17	8	36	17	17	8	28	13	13	7	13	7		
				615	815	300	405	865	960	755	960	1400	1965	1170	1640		
	225–275	70	**f**														
			s														

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Cutting Feeds and Speeds for Turning Plain Carbon and Alloy Steels**

Material AISI/SAE Designation	Brinell Hardness	Speed (fpm)	Tool Material													
			HSS	Uncoated Carbide				Coated Carbide				Ceramic				Cermet	
				Hard		Tough		Hard		Tough		Hard		Tough			
			f = feed (0.001 in./rev), **s** = speed (ft/min)														
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Plain carbon steels *(continued)*: 1027, 1030, 1033, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1045, 1046, 1048, 1049, 1050, 1052, 1524, 1526, 1527, 1541	125–175	100	**f**	17	8	36	17	28	13	28	13	15	8	15	8	7	3
			s	745	935	345	470	915	1130	785	1110	1795	2680	1485	2215	1490	1815
	175–225	85	**f**	17	8	36	17	17	8	28	13	13	7	13	7		
	225–275	70	**s**	615	815	300	405	865	960	755	960	1400	1965	1170	1640		
	275–325	60															
	325–375	40	**f**	17	8	36	17	17	8	28	13	10	5	10	5		
	375–425	30	**s**	515	685	235	340	720	805	650	810	1430	1745	1070	1305		
Plain carbon steels *(continued)*: 1055, 1060, 1064, 1065, 1070, 1074, 1078, 1080, 1084, 1086, 1090, 1095, 1548, 1551, 1552, 1561, 1566	125–175	100															
	175–225	80	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	730	990	300	430	1090	1410	780	1105	1610	2780	1345	2005	1355	1695
	225–275	65	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
			s	615	815	300	405	865	960	755	960	1400	1965	1170	1640	1365	1695
	275–325	50															
	325–375	35	**f**	17	8	36	17	17	8	28	13	10	5	10	5		
	375–425	30	**s**	515	685	235	340	720	805	650	810	1430	1745	1070	1305		
Free-machining alloy steels, (resulfurized): 4140, 4150	175–200	110															
	200–250	90	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	525	705	235	320	505	525	685	960	1490	2220	1190	1780	1040	1310
	250–300	65	**f**	17	8	36	17	17	8	28	13	10	5	10	5	7	3
			s	355	445	140	200	630	850	455	650	1230	1510	990	1210	715	915
	300–375	50															
	375–425	40	**f**	17	8	36	17	17	8	28	13	8	4	8	4	7	3
			s	330	440	125	175	585	790	125	220	1200	1320	960	1060	575	740

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Cutting Feeds and Speeds for Turning Plain Carbon and Alloy Steels**

Material AISI/SAE Designation	Brinell Hardness	Speed (fpm)		Tool Material													
				Uncoated Carbide				Coated Carbide				Ceramic					
		HSS		Hard		Tough		Hard		Tough		Hard		Tough		Cermet	
				f = feed (0.001 in./rev), **s** = speed (ft/min)													
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Free-machining alloy steels: (leaded): 41L30, 41L40, 41L47, 41L50, 43L47, 51L32, 52L100, 86L20, 86L40	150–200	120	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	730	990	300	430	1090	1410	780	1105	1610	2780	1345	2005	1355	1695
	200–250	100	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
			s	615	815	300	405	865	960	755	960	1400	1965	1170	1640	1355	1695
	250–300	75															
	300–375	55	**f**	17	8	36	17	17	8	28	13	10	5	10	5		
			s	515	685	235	340	720	805	650	810	1430	1745	1070	1305		
	375–425	50															
Alloy steels: 4012, 4023, 4024, 4028, 4118, 4320, 4419, 4422, 4427, 4615, 4620, 4621, 4626, 4718, 4720, 4815, 4817, 4820, 5015, 5117, 5120, 6118, 8115, 8615, 8617, 8620, 8622, 8625, 8627, 8720, 8822, 94B17	125–175	100															
	175–225	90	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	525	705	235	320	505	525	685	960	1490	2220	1190	1780	1040	1310
	225–275	70	**f**	17	8	36	1	17	8	28	13	10	5	10	5	7	3
			s	355	445	140	200	630	850	455	650	1230	1510	990	1210	715	915
	275–325	60	**f**	17	8	36	17	17	8	28	13	9	5	8	5	7	3
			s	330	440	135	190	585	790	240	350	1230	1430	990	1150	655	840
	325–35	50															
	375–425	30 (20)	**f**	17	8	36	17	17	8	28	13	8	4	8	4	7	3
			s	330	440	125	175	585	790	125	220	1200	1320	960	1060	575	740
Alloy steels: 1330, 1335, 1340, 1345, 4032, 4037, 4042, 4047, 4130, 4135, 4137, 4140, 4142, 4145, 4147, 4150, 4161, 4337, 4340, 50B44, 50B46, 50B50, 50B60, 5130, 5132, 5140, 5145, 5147, 5150, 5160, 51B60, 6150, 81B45, 8630, 8635, 8637, 8640, 8642, 8645, 8650, 8655, 8660, 8740, 9254, 9255, 9260, 9262, 94B30 E51100, E52100 use (HSS Speeds)	175–225	85 (70)	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	525	705	235	320	505	525	685	960	1490	2220	1190	1780	1020	1310
	225–275	70 (65)	**f**	17	8	36	17	17	8	28	13	10	5	10	5	7	3
			s	355	445	140	200	630	850	455	650	1230	1510	990	1210	715	915
	275–325	60 (50)	**f**	17	8	36	17	17	8	28	13	9	5	8	5	7	3
			s	330	440	135	190	585	790	240	350	1230	1430	990	1150	655	840
	325–375	40 (30)															
	375–425	30 (20)	**f**	17	8	36	17	17	8	28	13	8	4	8	4	7	3
			s	330	440	125	175	585	790	125	220	1200	1320	960	1060	575	740

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Cutting Feeds and Speeds for Turning Plain Carbon and Alloy Steels**

Material AISI/SAE Designation	Brinell Hardness	Tool Material: HSS Speed (fpm)		Uncoated Carbide Hard Opt.	Uncoated Carbide Hard Avg.	Uncoated Carbide Tough Opt.	Uncoated Carbide Tough Avg.	Coated Carbide Hard Opt.	Coated Carbide Hard Avg.	Coated Carbide Tough Opt.	Coated Carbide Tough Avg.	Ceramic Hard Opt.	Ceramic Hard Avg.	Ceramic Tough Opt.	Ceramic Tough Avg.	Cermet Opt.	Cermet Avg.
				f = feed (0.001 in./rev), **s** = speed (ft/min)													
Ultra-high-strength steels (not ASI): AMS alloys 6421 (98B37 Mod.), 6422 (98BV40), 6424, 6427, 6428, 6430, 6432, 6433, 6434, 6436, and 6442; 300M and D6ac	220–300	65	**f**	17	8	36	17	20	10	28	13			10	5	7	3
	300–350	50	**s**	220	295	100	150	355	525	600	865			660	810	570	740
	350–400	35	**f**	17	8	36	17	17	8	28	13			8	4	7	3
			s	165	185	55	105	325	350	175	260			660	730	445	560
	43–48 Rc	25	**f**			17	8					7	3	10	5		
	48–52 Rc	10	**s**			55†	90					385	645	270	500		
Maraging steels (not AISI): 18% Ni, Grades 200, 250, 300, and 350	250–325	60	**f**	17	8	36	17	20	10	28	13	660	810	10	5	7	3
			s	220	295	100	150	355	525	600	865			570	740		
	50–52 Rc	10	**f**			17	8					7	3	10	5		
			s			55†	90					385‡	645	270	500		
Nitriding steels (not AISI): Nitralloy 125, 135, 135 Mod., 225, and 230, Nitralloy N, Nitralloy EZ, Nitrex 1	200–250	70	**f**	17	8	36	17	17	8	28	13	15	8	15	8	7	3
			s	525	705	235	320	505	525	685	960	1490	2220	1190	1780	1040	1310
	300–350	30	**f**	17	8	36	17	17	8	28	13	8	4	8	4	7	3
			s	330	440	125	175	585	790	125	220	1200	1320	960	1060	575	740

Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text.

The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbides, hard = 17, tough = 19, † = 15; coated carbides, hard = 11, tough = 14; ceramics, hard = 2, tough = 3, ‡ = 4; cermet = 7 .

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Cutting Feeds and Speeds for Turning Tool Steels

Material AISI Designation	Brinell Hardness	Tool Material: Uncoated HSS Speed (fpm)	Uncoated Carbide Hard Opt.	Uncoated Carbide Hard Avg.	Uncoated Carbide Tough Opt.	Uncoated Carbide Tough Avg.	Coated Carbide Hard Opt.	Coated Carbide Hard Avg.	Coated Carbide Tough Opt.	Coated Carbide Tough Avg.	Ceramic Hard Opt.	Ceramic Hard Avg.	Ceramic Tough Opt.	Ceramic Tough Avg.	Cermet Opt.	Cermet Avg.
			f = feed (0.001 in./rev), **s** = speed (ft/min)													
Water hardening: W1, W2, W5	150–200	100	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
Shock resisting: S1, S2, S5, S6, S7	175–225	70	**s**	455	610	210	270	830	1110	575	805	935	1310	790	1110	915	1150
Cold work, oil hardening: O1, O2, O6, O7	175–225	70															
Cold work, high carbon, high chromium: D2, D3, D4, D5, D7	200–250	45															
Cold work, air hardening: A2, A3, A8, A9, A10	200–250	70															
A4, A6	200–250	55	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
A7	225–275	45	**s**	445	490	170	235	705	940	515	770	660	925	750	1210	1150	1510
Hot work, chromium type: H10, H11, H12, H13, H14, H19	150–200	80															
	200–250	65															
	325–375	50	**f**	17	8	36	17	17	8	28	13			8	4	7	3
			s	165	185	55	105	325	350	175	260			660	730	445	560
	48–50 Rc	20	**f**			17	8					7	3	10	5		
	50–52 Rc	10	**s**			55†	90					385‡	645	270	500		
	52–56 Rc	—															
Hot work, tungsten type: H21, H22, H23, H24, H25, H26	150–200	60															
	200–250	50	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
Hot work, molybdenum type: H41, H42, H43	150–200	55	**s**	445	490	170	235	705	940	515	770	660	925	750	1210	1150	1510
	200–250	45															
Special purpose, low alloy: L2, L3, L6	150–200	75	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
			s	445	610	210	270	830	1110	575	805	935	1310	790	1110	915	1150
Mold: P2, P3, P4, P5, P6, P26, P21	100–150	90	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
	150–200	80	**s**	445	610	210	270	830	1110	575	805	935	1310	790	1110	915	1150
High-speed steel: M1, M2, M6, M10, T1, T2,T6	200–250	65															
M3-1, M4 M7, M30, M33, M34, M36, M41, M42, M43, M44, M46, M47, T5, T8	225–275	55	**f**	17	8	36	17	17	8	28	13	13	7	13	7	7	3
			s	445	490	170	235	705	940	515	770	660	925	750	1210	1150	1510
T15, M3-2	225–275	45															

Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text.The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbides, hard = 17, tough = 19, † = 15; coated carbides, hard = 11, tough = 14; ceramics, hard = 2, tough = 3, ‡ = 4; cermet = 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Cutting Feeds and Speeds for Turning Stainless Steels

Material	Brinell Hardness	Tool Material: Uncoated HSS Speed (fpm)		Uncoated Carbide Hard *Opt.*	Uncoated Carbide Hard *Avg.*	Uncoated Carbide Tough *Opt.*	Uncoated Carbide Tough *Avg.*	Coated Carbide Hard *Opt.*	Coated Carbide Hard *Avg.*	Coated Carbide Tough *Opt.*	Coated Carbide Tough *Avg.*	Cermet *Opt.*	Cermet *Avg.*
				f = feed (0.001 in./rev), **s** = speed (ft/min)									
Free-machining stainless steel (Ferritic): 430F, 430FSe	135–185	110	**f**	20	10	36	17	17	8	28	13	7	3
			s	480	660	370	395	755	945	640	810	790	995
(Austenitic): 203EZ, 303, 303Se, 303MA, 303Pb, 303Cu, 303 Plus X	135–185	100	**f**	13	7	36	17			28	13	7	3
	225–275	80	**s**	520	640	310	345			625	815	695	875
(Martensitic): 416, 416Se, 416 Plus X, 420F, 420FSe, 440F, 440FSe	135–185	110	**f**	13	7	36				28	13	7	3
	185–240	100	**s**	520	640	310				625	815	695	875
	275–325	60	**f**	13	7	36	17			28	13		
	375–425	30	**s**	210	260	85	135			130	165		
Stainless steels (Ferritic): 405, 409 429, 430, 434, 436, 442, 446, 502	135–185	90	**f**	20	10	36	17	17	8	28	13	7	3
			s	480	660	370	395	755	945	640	810	790	995
(Austenitic): 201, 202, 301, 302, 304, 304L, 305, 308, 321, 347, 348	135–185	75											
	225–275	65											
(Austenitic): 302B, 309, 309S, 310, 310S, 314, 316, 316L, 317, 330	135–185	70	**f**	13	7	36	17			28	13	7	3
			s	520	640	310	345			625	165	695	875
(Martensitic): 403, 410, 420, 501	135–175	95											
	175–225	85											
	275–325	55											
	375–425	35											
(Martensitic): 414, 431, Greek Ascoloy, 440A, 440B, 440C	225–275	55–60	**f**	13	7	36	17			28	13	13	7
	275–325	45–50	**s**	210	260	85	135			130	165	200†	230
	375–425	30											
(Precipitation hardening):15-5PH, 17-4PH, 17-7PH, AF-71, 17-14CuMo, AFC-77, AM-350, AM-355, AM-362, Custom 455, HNM, PH13-8, PH14-8Mo, PH15-7Mo, Stainless W	150–200	60	**f**	13	7	36	17			28	13	13	7
	275–325	50	**s**	520	640	310	345			625	815	695	875
	325–375	40	**f**	13	7	36	17						
	375–450	25	**s**	195	240	85	155						

See footnote to Table 1 for more information. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbides, hard = 17, tough = 19; coated carbides, hard = 11, tough = 14; cermet = 7, † = 18.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. Cutting Feeds and Speeds for Turning Ferrous Cast Metals

Material	Brinell Hardness	Tool Material: HSS Speed (fpm)		Uncoated Carbide Tough		Coated Carbide Hard		Coated Carbide Tough		Ceramic Hard		Ceramic Tough		Cermet		CBN	
				f = feed (0.001 in./rev), **s** = speed (ft/min)													
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Gray Cast Iron																	
ASTM Class 20	120–150	120	**f**	28	13	28	13	28	13	15	8	15	8	8	4	24	11
ASTM Class 25	160–200	90	**s**	240	365	665	1040	585	945	1490	2220	1180	1880	395	510	8490	36380
ASTM Class 30, 35, and 40	190–220	80															
ASTM Class 45 and 50	220–260	60	**f**	28	13	28	13	28	13	11	6	11	6	8	4	24	11
ASTM Class 55 and 60	250–320	35	**s**	160	245	400	630	360	580	1440	1880	1200	1570	335	420	1590	2200
ASTM Type 1, 1b, 5 (Ni resist)	100–215	70															
ASTM Type 2, 3, 6 (Ni resist)	120–175	65	**f**	28	13			28	13	15	8	15	8	8	4		
ASTM Type 2b, 4 (Ni resist)	150–250	50	**s**	110	175			410	575	1060	1590	885	1320	260	325		
Malleable Iron																	
(Ferritic): 32510, 35018	110–160	130	**f**	28	13	28	13	28	13	15	8	15	8				
			s	180	280	730	940	660	885	1640	2450	1410	2110				
(Pearlitic): 40010, 43010, 45006, 45008, 48005, 50005	160–200	95	**f**	28	13	28	13	28	13	13	7	13	7				
	200–240	75	**s**	125	200	335	505	340	510	1640	2310	1400	1970				
(Martensitic): 53004, 60003, 60004	200–255	70															
(Martensitic): 70002, 70003	220–260	60	**f**	28	13			28	13	11	6	11	6				
(Martensitic): 80002	240–280	50	**s**	100	120			205	250	1720	2240	1460	1910				
(Martensitic): 90001	250–320	30															

Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust the given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text.

The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbides, tough = 15; Coated carbides, hard = 11, tough = 14; ceramics, hard = 2, tough = 3; cermet = 7; CBN = 1.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. Cutting Feeds and Speeds for Turning Ferrous Cast Metals

Material	Brinell Hardness	Tool Material: Uncoated HSS Speed (fpm)		Uncoated Carbide Hard Opt.	Uncoated Carbide Hard Avg.	Uncoated Carbide Tough Opt.	Uncoated Carbide Tough Avg.	Coated Carbide Hard Opt.	Coated Carbide Hard Avg.	Coated Carbide Tough Opt.	Coated Carbide Tough Avg.	Ceramic Hard Opt.	Ceramic Hard Avg.	Ceramic Tough Opt.	Ceramic Tough Avg.	Cermet Opt.	Cermet Avg.
				f = feed (0.001 in./rev), **s** = speed (ft/min)													
Nodular (Ductile) Iron																	
(Ferritic): 60-40-18, 65-45-12	140–190	100	**f**			28	13	28	13	28	13	15	8	15	8	8	4
			s			200	325	490	700	435	665	970	1450	845	1260	365	480
(Ferritic-Pearlitic): 80-55-06	190–225	80	**f**			28	13	28	13	28	13	11	6	11	6	8	4
	225–260	65	**s**			130	210	355	510	310	460	765	995	1260	1640	355	445
(Pearlitic-Martensitic): 100-70-03	240–300	45															
(Martensitic): 120-90-02	270–330	30	**f**			28	13			28	13	10	5	10	5	8	4
	300–400	15	**s**			40	65			145	175	615	750	500	615	120	145
Cast Steels																	
(Low-carbon): 1010, 1020	100–150	110	**f**	17	8	36	17	17	8	28	13	15	8			7	3
	125–175	100	**s**	370	490	230	285	665	815	495	675	2090	3120			625	790
(Medium-carbon): 1030, 1040, 1050	175–225	90															
	225–300	70															
(Low-carbon alloy): 1320, 2315, 2320, 4110, 4120, 4320, 8020, 8620	150–200	90	**f**	17	8	36	17	17	8	28	13	15	8			7	3
	200–250	80	**s**	370	490	150	200	595	815	410	590	1460	2170			625	790
	250–300	60															
(Medium-carbon alloy): 1330, 1340, 2325, 2330, 4125, 4130, 4140, 4330, 4340, 8030, 80B30, 8040, 8430, 8440, 8630, 8640, 9525, 9530, 9535	175–225	80	**f**	17	8	36	17	17	8			15	8				
	225–250	70	**s**	310	415	115	150	555	760			830	1240				
	250–300	55	**f**			28	13					15	8				
	300–350	45	**s**			70†	145					445	665				
	350–400	30	**f**			28	13			28	13			15	8		
			s			115†	355			335	345			955	1430		

The combined feed/speed data in this table are based on tool grades (identified in Table 16) as shown: uncoated carbides, hard = 17; tough = 19, † = 15; coated carbides, hard = 11; tough = 14; ceramics, hard = 2; tough = 3; cermet = 7. Also, see footnote to Table 4a.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5a. Turning-Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle

Ratio of Chosen Feed to *Optimum* Feed	Ratio of the two cutting speeds given in the tables V_{avg}/V_{opt}							Depth of Cut and Lead Angle									
								1 in. (25.4 mm)		0.4 in. (10.2 mm)		0.2 in. (5.1 mm)		0.1 in. (2.5 mm)		0.04 in. (1.0 mm)	
	1.00	1.10	1.25	1.35	1.50	1.75	2.00	15°	45°	15°	45°	15°	45°	15°	45°	15°	45°
	Feed Factor, F_f							Depth of Cut and Lead Angle Factor, F_d									
1.00	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0.74	1.0	0.79	1.03	0.85	1.08	1.0	1.18	1.29	1.35
0.90	1.00	1.02	1.05	1.07	1.09	1.10	1.12	0.75	1.0	0.80	1.03	0.86	1.08	1.0	1.17	1.27	1.34
0.80	1.00	1.03	1.09	1.10	1.15	1.20	1.25	0.77	1.0	0.81	1.03	0.87	1.07	1.0	1.15	1.25	1.31
0.70	1.00	1.05	1.13	1.22	1.22	1.32	1.43	0.77	1.0	0.82	1.03	0.87	1.08	1.0	1.15	1.24	1.30
0.60	1.00	1.08	1.20	1.25	1.35	1.50	1.66	0.78	1.0	0.82	1.03	0.88	1.07	1.0	1.14	1.23	1.29
0.50	1.00	1.10	1.25	1.35	1.50	1.75	2.00	0.78	1.0	0.82	1.03	0.88	1.07	1.0	1.14	1.23	1.28
0.40	1.00	1.09	1.28	1.44	1.66	2.03	2.43	0.78	1.0	0.84	1.03	0.89	1.06	1.0	1.13	1.21	1.26
0.30	1.00	1.06	1.32	1.52	1.85	2.42	3.05	0.81	1.0	0.85	1.02	0.90	1.06	1.0	1.12	1.18	1.23
0.20	1.00	1.00	1.34	1.60	2.07	2.96	4.03	0.84	1.0	0.89	1.02	0.91	1.05	1.0	1.10	1.15	1.19
0.10	1.00	0.80	1.20	1.55	2.24	3.74	5.84	0.88	1.0	0.91	1.01	0.92	1.03	1.0	1.06	1.10	1.12

Use with Tables 1 through 9. Not for HSS tools. Tables 1 through 9 data, except for HSS tools, are based on depth of cut = 0.1 inch, lead angle = 15 degrees, and tool life = 15 minutes. For other depths of cut, lead angles, or feeds, use the two feed/speed pairs from the tables and calculate the ratio of desired (new) feed to *optimum* feed (largest of the two feeds given in the tables), and the ratio of the two cutting speeds (V_{avg}/V_{opt}). Use the value of these ratios to find the feed factor F_f at the intersection of the feed ratio row and the speed ratio column in the left half of the table. The depth-of-cut factor F_d is found in the same row as the feed factor in the right half of the table under the column corresponding to the depth of cut and lead angle. The adjusted cutting speed can be calculated from $V = V_{opt} \times F_f \times F_d$, where V_{opt} is the smaller (*optimum*) of the two speeds from the speed table (from the left side of the column containing the two feed/speed pairs). See the text for examples.

Table 5b. Tool Life Factors for Turning with Carbides, Ceramics, Cermets, CBN, and Polycrystalline Diamond

Tool Life, T (minutes)	Turning with Carbides: Workpiece < 300 Bhn			Turning with Carbides: Workpiece > 300 Bhn; Turning with Ceramics: Any Hardness			Turning with Mixed Ceramics: Any Workpiece Hardness		
	f_s	f_m	f_l	f_s	f_m	f_l	f_s	f_m	f_l
15	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
45	0.86	0.81	0.76	0.80	0.75	0.70	0.89	0.87	0.84
90	0.78	0.71	0.64	0.70	0.63	0.56	0.82	0.79	0.75
180	0.71	0.63	0.54	0.61	0.53	0.45	0.76	0.72	0.67

Except for HSS speed tools, feeds and speeds given in Tables 1 through 9 are based on 15-minute tool life. To adjust speeds for another tool life, multiply the cutting speed for 15-minute tool life V_{15} by the tool life factor from this table according to the following rules: for small feeds where feed $\leq \frac{1}{2} f_{opt}$, the cutting speed for desired tool life is $V_T = f_s \times V_{15}$; for medium feeds where $\frac{1}{2} f_{opt} <$ feed $< \frac{3}{4} f_{opt}$, $V_T = f_m \times V_{15}$; and for larger feeds where $\frac{3}{4} f_{opt} \leq$ feed $\leq f_{opt}$, $V_T = f_l \times V_{15}$. Here, f_{opt} is the largest (*optimum*) feed of the two feed/speed values given in the speed tables.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5c. Cutting-Speed Adjustment Factors for Turning with HSS Tools

Feed		Feed Factor	Depth of Cut		Depth-of-Cut Factor
in.	mm	F_f	in.	mm	F_d
0.002	0.05	1.50	0.005	0.13	1.50
0.003	0.08	1.50	0.010	0.25	1.42
0.004	0.10	1.50	0.016	0.41	1.33
0.005	0.13	1.44	0.031	0.79	1.21
0.006	0.15	1.34	0.047	1.19	1.15
0.007	0.18	1.25	0.062	1.57	1.10
0.008	0.20	1.18	0.078	1.98	1.07
0.009	0.23	1.12	0.094	2.39	1.04
0.010	0.25	1.08	0.100	2.54	1.03
0.011	0.28	1.04	0.125	3.18	1.00
0.012	0.30	1.00	0.150	3.81	0.97
0.013	0.33	0.97	0.188	4.78	0.94
0.014	0.36	0.94	0.200	5.08	0.93
0.015	0.38	0.91	0.250	6.35	0.91
0.016	0.41	0.88	0.312	7.92	0.88
0.018	0.46	0.84	0.375	9.53	0.86
0.020	0.51	0.80	0.438	11.13	0.84
0.022	0.56	0.77	0.500	12.70	0.82
0.025	0.64	0.73	0.625	15.88	0.80
0.028	0.71	0.70	0.688	17.48	0.78
0.030	0.76	0.68	0.750	19.05	0.77
0.032	0.81	0.66	0.812	20.62	0.76
0.035	0.89	0.64	0.938	23.83	0.75
0.040	1.02	0.60	1.000	25.40	0.74
0.045	1.14	0.57	1.250	31.75	0.73
0.050	1.27	0.55	1.250	31.75	0.72
0.060	1.52	0.50	1.375	34.93	0.71

For use with HSS tool data only from Tables 1 through 9. Adjusted cutting speed $V = V_{HSS} \times F_f \times F_d$, where V_{HSS} is the tabular speed for turning with high-speed tools.

Example 3, Turning: Determine the cutting speed for turning 1055 steel of 175 to 225 Brinell hardness using a hard ceramic insert, a 15° lead angle, a 0.04-inch depth of cut and 0.0075 in./rev feed.

The two feed/speed combinations given in Table 5a for 1055 steel are 15/1610 and 8/2780, corresponding to 0.015 in./rev at 1610 fpm and 0.008 in./rev at 2780 fpm, respectively. In Table 5a, the feed factor $F_f = 1.75$ is found at the intersection of the row corresponding to feed/$f_{opt} = 7.5/15 = 0.5$ and the column corresponding to $V_{avg}/V_{opt} = 2780/1610 = 1.75$ (approximately). The depth-of-cut factor $F_d = 1.23$ is found in the same row, under the column heading for a depth of cut = 0.04 inch and lead angle = 15°. The adjusted cutting speed is $V = 1610 \times 1.75 \times 1.23 = 3466$ fpm.

Example 4, Turning: The cutting speed for 1055 steel calculated in Example 3 represents the speed required to obtain a 15-minute tool life. Estimate the cutting speed needed to obtain a tool life of 45, 90, and 180 minutes using the results of Example 3.

To estimate the cutting speed corresponding to another tool life, multiply the cutting speed for 15-minute tool life V_{15} by the adjustment factor from the Table 5b, Tool Life Factors for Turning. This table gives three factors for adjusting tool life based on the feed used, f_s for feeds less than or equal to $\frac{1}{2}f_{opt}$, $\frac{3}{4}f_{fm}$ for midrange feeds between $\frac{1}{2}$ and $\frac{3}{4}f_{opt}$ and f_l for large feeds greater than or equal to $\frac{3}{4}f_{opt}$ and less than f_{opt}. In Example 3, f_{opt} is 0.015 in./rev and the selected feed is 0.0075 in./rev = $\frac{1}{2}f_{opt}$. The new cutting speeds for the various tool lives are obtained by multiplying the cutting speed for 15-minute tool life V_{15} by the factor

Copyright 2004, Industrial Press, Inc., New York, NY

for small feeds f_s from the column for turning with ceramics in Table 5b. These calculations, using the cutting speed obtained in Example 3, follow.

Tool Life	*Cutting Speed*
15 min	$V_{15} = 3466$ fpm
45 min	$V_{45} = V_{15} \times 0.80 = 2773$ fpm
90 min	$V_{90} = V_{15} \times 0.70 = 2426$ fpm
180 min	$V_{180} = V_{15} \times 0.61 = 2114$ fpm

Depth of cut, feed, and lead angle remain the same as in Example 3. Notice, increasing the tool life from 15 to 180 minutes, a factor of 12, reduces the cutting speed by only about one-third of the V_{15} speed.

Table 6. Cutting Feeds and Speeds for Turning Copper Alloys

Group 1
Architectural bronze (C38500); Extra-high-headed brass (C35600); Forging brass (C37700); Free-cutting phosphor bronze, B2 (C54400); Free-cutting brass (C36000); Free-cutting Muntz metal (C37000); High-leaded brass (C33200; C34200); High-leaded brass tube (C35300); Leaded commercial bronze (C31400); Leaded naval brass (C48500); Medium-leaded brass (C34000)
Group 2
Aluminum brass, arsenical (C68700); Cartridge brass, 70% (C26000); High-silicon bronze, B (C65500); Admiralty brass (inhibited) (C44300, C44500); Jewelry bronze, 87.5% (C22600); Leaded Muntz metal (C36500, C36800); Leaded nickel silver (C79600); Low brass, 80% (C24000); Low-leaded brass (C33500); Low-silicon bronze, B (C65100); Manganese bronze, A (C67500); Muntz metal, 60% (C28000); Nickel silver, 55-18 (C77000); Red brass, 85% (C23000); Yellow brass (C26800)
Group 3
Aluminum bronze, D (C61400); Beryllium copper (C17000, C17200, C17500); Commercial-bronze, 90% (C22000); Copper nickel, 10% (C70600); Copper nickel, 30% (C71500); Electrolytic tough pitch copper (C11000); Guilding, 95% (C21000); Nickel silver, 65-10 (C74500); Nickel silver, 65-12 (C75700); Nickel silver, 65-15 (C75400); Nickel silver, 65-18 (C75200); Oxygen-free copper (C10200) ; Phosphor bronze, 1.25% (C50200); Phosphor bronze, 10% D (C52400) Phosphor bronze, 5% A (C51000); Phosphor bronze, 8% C (C52100); Phosphorus deoxidized copper (C12200)

Wrought Alloys Description and UNS Alloy Numbers	Material Condition	HSS	Uncoated Carbide			Polycrystalline Diamond	
		Speed (fpm)	**f** = feed (0.001 in./rev), **s** = speed (ft/min)				
				Opt.	*Avg.*	*Opt.*	*Avg.*
Group 1	A	300	**f**	28	13		
	CD	350	**s**	1170	1680		
Group 2	A	200	**f**	28	13		
	CD	250	**s**	715	900		
Group 3	A	100	**f**	28	13	7	13
	CD	110	**s**	440	610	1780	2080

Abbreviations designate: A, annealed; CD, cold drawn.

The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide, 15; diamond, 9. See the footnote to Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Cutting Feeds and Speeds for Turning Titanium and Titanium Alloys

Material	Brinell Hardness	Tool Material: HSS Speed (fpm)	Uncoated Carbide (Tough): **f** = feed (0.001 in./rev), **s** = speed (ft/min)	*Opt.*	*Avg.*
Commercially Pure and Low Alloyed					
99.5Ti, 99.5Ti-0.15Pd	110–150	100–105	**f**	28	13
			s	55	190
99.1Ti, 99.2Ti, 99.2Ti-0.15Pd, 98.9Ti-0.8Ni-0.3Mo	180–240	85–90	**f**	28	13
			s	50	170
99.0 Ti	250–275	70	**f**	20	10
			s	75	210
Alpha Alloys and Alpha-Beta Alloys					
5Al-2.5Sn, 8Mn, 2Al-11Sn-5Zr-1Mo, 4Al-3Mo-1V, 5Al-6Sn-2Zr-1Mo, 6Al-2Sn-4Zr-2Mo, 6Al-2Sn-4Zr-6Mo, 6Al-2Sn-4Zr-2Mo-0.25Si	300–350	50			
6Al-4V	310–350	40			
6Al-6V-2Sn, Al-4Mo,	320–370	30	**f**	17	8
8V-5Fe-IAl	320–380	20	**s**	95	250
6Al-4V, 6Al-2Sn-4Zr-2Mo, 6Al-2Sn-4Zr-6Mo, 6Al-2Sn-4Zr-2Mo-0.25Si	320–380	40			
4Al-3Mo-1V, 6Al-6V-2Sn, 7Al-4Mo	375–420	20			
I Al-8V-5Fe	375–440	20			
Beta Alloys					
13V-11Cr-3Al, 8Mo-8V-2Fe-3Al, 3Al-8V-6Cr-4Mo-4Zr, 11.5Mo-6Zr-4.5Sn	275–350	25	**f**	17	8
	375–440	20	**s**	55	150

The speed recommendations for turning with HSS (high-speed steel) tools may be used as starting speeds for milling titanium alloys, using Table 15a to estimate the feed required. Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide, 15.

Table 8. Cutting Feeds and Speeds for Turning Light Metals

Material Description	Material Condition	Tool Material: HSS Speed (fpm)	Uncoated Carbide (Tough): **f** = feed (0.001 in./rev), **s** = speed (ft/min)	*Opt.*	*Avg.*	Polycrystalline Diamond: *Opt.*	*Avg.*
All wrought and cast magnesium alloys	A, CD, ST, and A	800					
All wrought aluminum alloys, including 6061-T651, 5000, 6000, and 7000 series	CD	600					
	ST and A	500	**f**	36	17		
			s	2820	4570		
All aluminum sand and permanent mold casting alloys	AC	750					
	ST and A	600					
Aluminum Die-Casting Alloys							
Alloys 308.0 and 319.0	—	—	**f**	36	17	11	8
			s	865	1280	5890[a]	8270
Alloys 390.0 and 392.0	AC	80	**f**	24	11	8	4
	ST and A	60	**s**	2010	2760	4765	5755
Alloy 413	—	—	**f**	32	15	10	5
			s	430	720	5085	6570
All other aluminum die-casting alloys including alloys 360.0 and 380.0	ST and A	100					
	AC	125	**f**	36	17	11	6
			s	630	1060	7560	9930

Copyright 2004, Industrial Press, Inc., New York, NY

[a] The feeds and speeds for turning Al alloys 308.0 and 319.0 with (polycrystalline) diamond tooling represent an expected tool life $T = 960$ minutes = 16 hours; corresponding feeds and speeds for 15-minute tool life are 11⁄28600 and 6⁄37500.

Abbreviations for material condition: A, annealed; AC, as cast; CD, cold drawn; and ST and A, solution treated and aged, respectively. Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the HSS speeds for other feeds and depths of cut. The combined feed/speed data are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. The data are based on tool grades (identified in Table 16) as follows: uncoated carbide, 15; diamond, 9.

Table 9. Cutting Feeds and Speeds for Turning Superalloys

	Tool Material									
	HSS Turning		Uncoated Carbide	Ceramic				CBN	
	Rough	Finish	Tough	Hard		Tough			
	Speed (fpm)		**f** = feed (0.001 in./rev), **s** = speed (ft/min)						
Material Description			*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
T-D Nickel	70–80	80–100								
Discalloy	15–35	35–40								
19-9DL, W-545	25–35	30–40	**f** 24	11					20	10
16-25-6, A-286, Incoloy 800, 801, and 802, V-57	30–35	35–40	**s** 90	170					365	630
Refractaloy 26	15–20	20–25	**f** 20	10					20	10
J1300	15–25	20–30	**s** 75	135					245	420
Inconel 700 and 702, Nimonic 90 and 95	10–12	12–15								
S-816, V-36	10–15	15–20								
S-590	10–20	15–30								
Udimet 630		20–25								
N-155		15–25								
Air Resist 213; Hastelloy B, C, G and X (wrought); Haynes 25 and 188; J1570; M252 (wrought); Mar-M905 and M918; Nimonic 75 and 80	15–20	20–25	**f** 20 **s** 75	10 125	11 1170	6 2590	11 405	6 900	20 230	10 400
CW-12M; Hastelloy B and C (cast); N-12M	8–12	10–15								
Rene 95 (Hot Isostatic Pressed)	—	—								
HS 6, 21, 2, 31 (X 40), 36, and 151; Haynes 36 and 151; Mar-M302, M322, and M509, WI-52	10–12	10–15								
Rene 41	10–15	12–20								
Incoloy 901	10–20	20–35								
Waspaloy	10–30	25–35	**f** 28	13	11	6	10	5	20	10
Inconel 625, 702, 706, 718 (wrought), 721, 722, X750, 751, 901, 600, and 604	15–20	20–35	**s** 20	40	895	2230	345	815	185	315
AF2-1DA, Unitemp 1753	8–10	10–15								
Colmonoy, Inconel 600, 718, K-Monel, Stellite	—	—								
Air Resist 13 and 215, FSH-H14, Nasa C-W-Re, X-45	10–12	10–15								
Udimet 500, 700, and 710	10–15	12–20								
Astroloy	5–10	5–15	**f** 28	13	11	6	10	5	20	10
Mar-M200, M246, M421, and Rene 77, 80, and 95 (forged)		10–12 10–15	**s** 15	15	615	1720	290	700	165	280
B-1900, GMR-235 and 235D, IN 100 and 738, Inconel 713C and 718 (cast), M252 (cast)	8–10	8–10								

The speed recommendations for rough turning may be used as starting values for milling and drilling with HSS tools. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 15; ceramic, hard = 4, tough = 3; CBN = 1.

Copyright 2004, Industrial Press, Inc., New York, NY

Speeds for HSS (high-speed steel) tools are based on a feed of 0.012 inch/rev and a depth of cut of 0.125 inch; use Table 5c to adjust the given speeds for other feeds and depths of cut. The combined feed/speed data in the remaining columns are based on a depth of cut of 0.1 inch, lead angle of 15 degrees, and nose radius of $\frac{3}{64}$ inch. Use Table 5a to adjust given speeds for other feeds, depths of cut, and lead angles; use Table 5b to adjust given speeds for increased tool life up to 180 minutes. Examples are given in the text.

Speed and Feed Tables for Milling.— Tables 10 through 14 give feeds and speeds for milling. The data in the first speed column can be used with high-speed steel tools using the feeds given in Table 15a; these are the same speeds contained in previous editions of the Handbook. The remaining data in Tables 10 through 14 are combined feeds and speeds for end, face, and slit, slot, and side milling that use the speed adjustment factors given in Tables 15b, 15c, and 15d. Tool life for the combined feed/speed data can also be adjusted using the factors in Table 15e. Table 16 lists cutting tool grades and vendor equivalents.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter D of 4.0 inch, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes.

Using the Feed and Speed Tables for Milling: The basic feed for milling cutters is the feed per tooth (f), which is expressed in inches per tooth. There are many factors to consider in selecting the feed per tooth and no formula is available to resolve these factors. Among the factors to consider are the cutting tool material; the work material and its hardness; the width and the depth of the cut to be taken; the type of milling cutter to be used and its size; the surface finish to be produced; the power available on the milling machine; and the rigidity of the milling machine, the workpiece, the workpiece setup, the milling cutter, and the cutter mounting.

The cardinal principle is to always use the maximum feed that conditions will permit. Avoid, if possible, using a feed that is less than 0.001 inch per tooth because such low feeds reduce the tool life of the cutter. When milling hard materials with small-diameter end mills, such small feeds may be necessary, but otherwise use as much feed as possible. Harder materials in general will require lower feeds than softer materials. The width and the depth of cut also affect the feeds. Wider and deeper cuts must be fed somewhat more slowly than narrow and shallow cuts. A slower feed rate will result in a better surface finish; however, always use the heaviest feed that will produce the surface finish desired. Fine chips produced by fine feeds are dangerous when milling magnesium because spontaneous combustion can occur. Thus, when milling magnesium, a fast feed that will produce a relatively thick chip should be used. Cutting stainless steel produces a work-hardened layer on the surface that has been cut. Thus, when milling this material, the feed should be large enough to allow each cutting edge on the cutter to penetrate below the work-hardened

Copyright 2004, Industrial Press, Inc., New York, NY

layer produced by the previous cutting edge. The heavy feeds recommended for face milling cutters are to be used primarily with larger cutters on milling machines having an adequate amount of power. For smaller face milling cutters, start with smaller feeds and increase as indicated by the performance of the cutter and the machine.

When planning a milling operation that requires a high cutting speed and a fast feed, always check to determine if the power required to take the cut is within the capacity of the milling machine. Excessive power requirements are often encountered when milling with cemented carbide cutters. The large metal removal rates that can be attained require a high horsepower output. An example of this type of calculation is given in the section on Machining Power that follows this section. If the size of the cut must be reduced in order to stay within the power capacity of the machine, start by reducing the cutting speed rather than the feed in inches per tooth.

The formula for calculating the table feed rate, when the feed in inches per tooth is known, is as follows:

$$f_m = f_t n_t N$$

where f_m = milling machine table feed rate in inches per minute (ipm)

f_t = feed in inch per tooth (ipt)

n_t = number of teeth in the milling cutter

N = spindle speed of the milling machine in revolutions per minute (rpm)

Example: Calculate the feed rate for milling a piece of AISI 1040 steel having a hardness of 180 Bhn. The cutter is a 3-inch diameter high-speed steel plain or slab milling cutter with 8 teeth. The width of the cut is 2 inches, the depth of cut is 0.062 inch, and the cutting speed from Table 11 is 85 fpm. From Table 15a, the feed rate selected is 0.008 inch per tooth.

$$N = \frac{12V}{\pi D} = \frac{12 \times 85}{3.14 \times 3} = 108 \text{ rpm}$$

$$f_m = f_t n_t N = 0.008 \times 8 \times 108$$

$$= 7 \text{ ipm (approximately)}$$

Example 1, Face Milling: Determine the cutting speed and machine operating speed for face milling an aluminum die casting (alloy 413) using a 4-inch polycrystalline diamond cutter, a 3-inch width of cut, a 0.10-inch depth of cut, and a feed of 0.006 inch/tooth.

Table 10 gives the feeds and speeds for milling aluminum alloys. The feed/speed pairs for face milling die cast alloy 413 with polycrystalline diamond (PCD) are 8⁄2320 (0.008 in./tooth feed at 2320 fpm) and 4⁄4755 (0.004 in./tooth feed at 4755 fpm). These speeds are based on an axial depth of cut of 0.10 inch, an 8-inch cutter diameter D, a 6-inch radial depth (width) of cut ar, with the cutter approximately centered above the workpiece, i.e., eccentricity is low, as shown in Fig. 3. If the preceding conditions apply, the given feeds and speeds can be used without adjustment for a 45-minute tool life. The given speeds are valid for all cutter diameters if a radial depth of cut to cutter diameter ratio (ar/D) of ¾ is maintained (i.e., ⅝ = ¾). However, if a different feed or axial depth of cut is required, or if the ar/D ratio is not equal to ¾, the cutting speed must be adjusted for the conditions. The adjusted cutting speed V is calculated from $V = V_{opt} \times F_f \times F_d \times F_{ar}$, where V_{opt} is the lower of the two speeds given in the speed table, and F_f, F_d, and F_{ar} are adjustment factors for feed, axial depth of cut, and radial depth of cut, respectively, obtained from Table 15d (face milling); except, when cutting near the end or edge of the workpiece as in Fig. 4, Table 15c (side milling) is used to obtain F_f.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3.



Fig. 4.

In this example, the cutting conditions match the standard conditions specified in the speed table for radial depth of cut to cutter diameter (3 in./4 in.), and depth of cut (0.01 in), but the desired feed of 0.006 in./tooth does not match either of the feeds given in the speed table (0.004 or 0.008). Therefore, the cutting speed must be adjusted for this feed. As with turning, the feed factor F_f is determined by calculating the ratio of the desired feed f to maximum feed f_{opt} from the speed table, and from the ratio V_{avg}/V_{opt} of the two speeds given in the speed table. The feed factor is found at the intersection of the feed ratio row and the speed ratio column in Table 15d. The speed is then obtained using the following equation:

$$\frac{\text{Chosen feed}}{Optimum\ \text{feed}} = \frac{f}{f_{opt}} = \frac{0.006}{0.008} = 0.75 \qquad \frac{Average\ \text{speed}}{Optimum\ \text{speed}} = \frac{V_{avg}}{V_{opt}} = \frac{4755}{2320} \approx 2.0$$

$$F_f = (1.25 + 1.43)/2 = 1.34 \qquad F_d = 1.0 \qquad F_{ar} = 1.0$$

$$V = 2320 \times 1.34 \times 1.0 \times 1.0 = 3109 \text{ fpm, and } 3.82 \times 3109/4 = 2970 \text{ rpm}$$

Example 2, End Milling: What cutting speed should be used for cutting a full slot (i.e., a slot cut from the solid, in one pass, that is the same width as the cutter) in 5140 steel with hardness of 300 Bhn using a 1-inch diameter coated carbide (insert) 0° lead angle end mill, a feed of 0.003 in./tooth, and a 0.2-inch axial depth of cut?

The feed and speed data for end milling 5140 steel, Brinell hardness = 275–325, with a coated carbide tool are given in Table 11 as 15/80 and 8/240 for *optimum* and *average* sets, respectively. The speed adjustment factors for feed and depth of cut for full slot (end milling) are obtained from Table 15b. The calculations are the same as in the previous examples: $f/f_{opt} = 3/15 = 0.2$ and $V_{avg}/V_{opt} = 240/80 = 3.0$, therefore, $F_f = 6.86$ and $F_d = 1.0$. The cutting speed for a 45-minute tool life is $V = 80 \times 6.86 \times 1.0 = 548.8$, approximately 550 ft/min.

Example 3, End Milling: What cutting speed should be used in Example 2 if the radial depth of cut *ar* is 0.02 inch and axial depth of cut is 1 inch?

In end milling, when the radial depth of cut is less than the cutter diameter (as in Fig. 4), first obtain the feed factor F_f from Table 15c, then the axial depth of cut and lead angle factor F_d from Table 15b. The radial depth of cut to cutter diameter ratio ar/D is used in Table 15c to determine the maximum and minimum feeds that guard against tool failure at high feeds and against premature tool wear caused by the tool rubbing against the work at very low feeds. The feed used should be selected so that it falls within the minimum to maximum feed range, and then the feed factor F_f can be determined from the feed factors at minimum and maximum feeds, F_{f1} and F_{f2} as explained below.

Copyright 2004, Industrial Press, Inc., New York, NY

The maximum feed f_{max} is found in Table 15c by multiplying the *optimum* feed from the speed table by the maximum feed factor that corresponds to the *ar*/*D* ratio, which in this instance is 0.02/1 = 0.02; the minimum feed f_{min} is found by multiplying the *optimum* feed by the minimum feed factor. Thus, $f_{max} = 4.5 \times 0.015 = 0.0675$ in./tooth and $f_{min} = 3.1 \times 0.015 = 0.0465$ in./tooth. If a feed between these maximum and minimum values is selected, 0.050 in./tooth for example, then for $ar/D = 0.02$ and $V_{avg}/V_{opt} = 3.0$, the feed factors at maximum and minimum feeds are $F_{f1} = 7.90$ and $F_{f2} = 7.01$, respectively, and by interpolation, $F_f = 7.01 + (0.050 - 0.0465)(0.0675 - 0.0465) \times (7.90 - 7.01) = 7.16$, approximately 7.2.

The depth of cut factor F_d is obtained from Table 15b, using f_{max} from Table 15c instead of the *optimum* feed f_{opt} for calculating the feed ratio (chosen feed/*optimum* feed). In this example, the feed ratio = chosen feed/f_{max} = 0.050/0.0675 = 0.74, so the feed factor is F_d = 0.93 for a depth of cut = 1.0 inch and 0° lead angle. Therefore, the final cutting speed is 80 × 7.2 × 0.93 = 587 ft/min. Notice that f_{max} obtained from Table 15c was used instead of the *optimum* feed from the speed table, in determining the feed ratio needed to find F_d.

Slit Milling.— The tabular data for slit milling is based on an 8-tooth, 10-degree helix angle cutter with a width of 0.4 inch, a diameter *D* of 4.0 inch, and a depth of cut of 0.6 inch. The given feeds and speeds are valid for any diameters and tool widths, as long as sufficient machine power is available. Adjustments to cutting speeds for other feeds and depths of cut are made using Table 15c or 15d, depending on the orientation of the cutter to the work, as illustrated in Case 1 and Case 2 of Fig. 5. The situation illustrated in Case 1 is approximately equivalent to that illustrated in Fig. 3, and Case 2 is approximately equivalent to that shown in Fig. 4.

Case 1: If the cutter is fed directly into the workpiece, i.e., the feed is perpendicular to the surface of the workpiece, as in cutting off, then Table 15d (face milling) is used to adjust speeds for other feeds. The depth of cut portion of Table 15d is not used in this case (F_d = 1.0), so the adjusted cutting speed $V = V_{opt} \times F_f \times F_{ar}$. In determining the factor F_{ar} from Table 15d, the radial depth of cut *ar* is the length of cut created by the portion of the cutter engaged in the work.

Case 2: If the cutter feed is parallel to the surface of the workpiece, as in slotting or side milling, then Table 15c (side milling) is used to adjust the given speeds for other feeds. In Table 15c, the cutting depth (slot depth, for example) is the radial depth of cut *ar* that is used to determine maximum and minimum allowable feed/tooth and the feed factor F_f. These minimum and maximum feeds are determined in the manner described previously, however, the axial depth of cut factor F_d is not required. The adjusted cutting speed, valid for cutters of any thickness (width), is given by $V = V_{opt} \times F_f$.



Fig. 5. Determination of Radial Depth of Cut or in Slit Milling

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Cutting Feeds and Speeds for Milling Aluminum Alloys

Material	Material Condition*		End Milling				Face Milling				Slit Milling			
			HSS		Indexable Insert Uncoated Carbide		Indexable Insert Uncoated Carbide		Polycrystalline Diamond		HSS		Indexable Insert Uncoated Carbide	
			f = feed (0.001 in./tooth), **s** = speed (ft/min)											
			Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
All wrought aluminum alloys, 6061-T651, 5000, 6000, 7000 series	CD ST and A	**f**	15	8	15	8	39	20	8	4	16	8	39	20
		s	165	850	620	2020	755	1720	3750	8430	1600	4680	840	2390
All aluminum sand and permanent mold casting alloys	CD ST and A	**f**												
		s												
Aluminum Die-Casting Alloys														
Alloys 308.0 and 319.0	—	**f**	15	8	15	8	39	20			16	8	39	20
		s	30	100	620	2020	755	1720			160	375	840	2390
Alloys 360.0 and 380.0	—	**f**	15	8	15	8	39	20	8	4	16	8	39	20
		s	30	90	485	1905	555	1380	3105	7845	145	355	690	2320
Alloys 390.0 and 392.0	—	**f**					39	20						
		s					220	370						
Alloy 413	—	**f**			15	8	39	20	8	4			39	20
	ST and A	**s**			355	1385	405	665	2320	4755			500	1680
All other aluminum die-casting alloys	AC	**f**	15	8	15	8	39	20	8	4	16	8	39	20
		s	30	90	485	1905	555	1380	3105	7845	145	335	690	2320

Abbreviations designate: A, annealed; AC, as cast; CD, cold drawn; and ST and A, solution treated and aged, respectively.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter *D* of 4.0 inch, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 15; diamond = 9.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Cutting Feeds and Speeds for Milling Plain Carbon and Alloy Steels

Material	Brinell Hardness	HSS Speed (fpm)	End Milling						Face Milling				Slit Milling			
			HSS				Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide	
			f = feed (0.001 in./tooth), **s** = speed (ft/min)															
			Opt.		*Avg.*		*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Free-machining plain carbon steels (resulfurized): 1212, 1213, 1215	100–150	140	**f**	7	4		7	4	7	4	39	20	39	20	39	20	39	20
			s	45	125		465	735	800	1050	225	335	415	685	265	495	525	830
	150–200	130	**f**	7	4								39	20				
			s	35	100								215	405				
(Resulfurized): 1108, 1109, 1115, 1117, 1118, 1120, 1126, 1211	100–150	130	**f**	7		4	7	4	7	4	39	20	39	20	39	20	39	20
	150–200	115	**s**	30		85	325	565	465	720	140	220	195	365	170	350	245	495
	175–225	115	**f**	7		4									39	20		
			s	30		85									185	350		
(Resulfurized): 1132, 1137, 1139, 1140, 1144, 1146, 1151	275–325	70																
	325–375	45	**f**	7	4		7	4	7	4	39	20	39	20	39	20	39	20
	375–425	35	**s**	25	70		210	435	300	560	90	170	175	330	90	235	135	325
(Leaded): 11L17, 11L18, 12L13, 12L14	100–150	140	**f**	7	4								39	20				
	150–200	130	**s**	35	100								215	405				
	200–250	110	**f**	7	4								39	20				
			s	30	85								185	350				
Plain carbon steels: 1006, 1008, 1009, 1010, 1012, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1513, 1514	100–125	110	**f**	7	4		7	4	7	4	39	20	39	20	39	20	39	20
			s	45	125		465	735	800	1050	225	335	415	685	265	495	525	830
	125–175	110	**f**	7	4								39	20				
			s	35	100								215	405				
	175–225	90	**f**	7	4								39	20				
	225–275	65	**s**	30	85								185	350				

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ***(Continued)*** **Cutting Feeds and Speeds for Milling Plain Carbon and Alloy Steels**

Material	Brinell Hardness	HSS Speed (fpm)		End Milling						Face Milling				Slit Milling			
				HSS		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide	
				f = feed (0.001 in./tooth), **s** = speed (ft/min)													
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Plain carbon steels: 1027, 1030, 1033, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1045, 1046, 1048, 1049, 1050, 1052, 1524, 1526, 1527, 1541	125–175	100	**f**	7	4							39	20				
			s	35	100							215	405				
	175–225	85	**f**	7	4							39	20				
	225–275	70	**s**	30	85							185	350				
	275–325	55															
	325–375	35	**f**	7	4	7	4	7	4	39	20	39	20	39	20	39	20
	375–425	25	**s**	25	70	210	435	300	560	90	170	175	330	90	235	135	325
Plain carbon steels: 1055, 1060, 1064, 1065, 1070, 1074, 1078, 1080, 1084, 1086, 1090, 1095, 1548, 1551, 1552, 1561, 1566	125–175	90															
	175–225	75	**f**	7	4	7	4	7	4	39	20	39	20	39	20	39	20
			s	30	85	325	565	465	720	140	220	195	365	170	350	245	495
	225–275	60	**f**	7	4							39	20				
			s	30	85							185	350				
	275–325	45															
	325–375	30	**f**	7	4	7	4	7	4	39	20	39	20	39	20	39	20
	375–425	15	**s**	25	70	210	435	300	560	90	170	175	330	90	235	135	325
Free-machining alloy steels (Resulfurized): 4140, 4150	175–200	100															
	200–250	90	**f**	15	8	15	8	15	8			39	20	39	20	7	4
			s	7	30	105	270	270	450			295	475	135	305	25	70
	250–300	60	**f**	15	8	15	8	15	8			39	20	39	20	7	4
			s	6	25	50	175	85	255			200	320	70	210	25	70
	300–375	45	**f**	15	8	15	8	15	8			39	20				
	375–425	35	**s**	5	20	40	155	75	225			175	280				

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ***(Continued)*** **Cutting Feeds and Speeds for Milling Plain Carbon and Alloy Steels**

Material	Brinell Hardness	HSS Speed (fpm)		End Milling						Face Milling				Slit Milling			
				HSS		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide	
				f = feed (0.001 in./tooth), **s** = speed (ft/min)													
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Free-machining alloy steels (Leaded): 41L30, 41L40, 41L47, 41L50, 43L47, 51L32, 52L100, 86L20, 86L40	150–200	115	**f**	7	4	7	4	7	4	39	20	39	20	39	20	39	20
			s	30	85	325	565	465	720	140	220	195	365	170	350	245	495
	200–250	95	**f**	7	4							39	20				
			s	30	85							185	350				
	250–300	70	**f**	7	4	7	4	7	4	39	20	39	20	39	20	39	20
	300–375	50	**s**	25	70	210	435	300	560	90	170	175	330	90	235	135	325
	375–425	40															
Alloy steels: 4012, 4023, 4024, 4028, 4118, 4320, 4419, 4422, 4427, 4615, 4620, 4621, 4626, 4718, 4720, 4815, 4817, 4820, 5015, 5117, 5120, 6118, 8115, 8615, 8617, 8620, 8622, 8625, 8627, 8720, 8822, 94B17	125–175	100	**f**	15	8	15	8	15	8			39	20	39	20	39	20
	175–225	90	**s**	7	30	105	270	220	450			295	475	135	305	265	495
	225–275	60	**f**	15	8	15	8	15	8			39	20	39	20	39	20
			s	6	25	50	175	85	255			200	320	70	210	115	290
	275–325	50	**f**	15	8	15	8	15	8			39	20				
			s	5	20	45	170	80	240			190	305				
	325–375	40	**f**	15	8	15	8	15	8			39	20				
	375–425	25	**s**	5	20	40	155	75	225			175	280				
Alloy steels: 1330, 1335, 1340, 1345, 4032, 4037, 4042, 4047, 4130, 4135, 4137, 4140, 4142, 4145, 4147, 4150, 4161, 4337, 4340, 50B44, 50B46, 50B50, 50B60, 5130, 5132, 5140, 5145, 5147, 5150, 5160, 51B60, 6150, 81B45, 8630, 8635, 8637, 8640, 8642, 8645, 8650, 8655, 8660, 8740, 9254, 9255, 9260, 9262, 94B30 E51100, E52100: use (HSS speeds)	175–225	75 (65)	**f**	15	8	15	8	15	8			39	20	39	20	39	20
			s	5	30	105	270	220	450			295	475	135	305	265	495
	225–275	60	**f**	15	8	15	8	15	8			39	20	39	20	39	20
			s	5	25	50	175	85	255			200	320	70	210	115	290
	275–325	50 (40)	**f**	15	8	15	8	15	8			39	20				
			s	5	25	45	170	80	240			190	305				
	325–375	35 (30)	**f**	15	8	15	8	15	8			39	20				
	375–425	20	**s**	5	20	40	155	75	225			175	280				

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ***(Continued)*** **Cutting Feeds and Speeds for Milling Plain Carbon and Alloy Steels**

Material	Brinell Hardness	HSS Speed (fpm)		End Milling						Face Milling				Slit Milling			
				HSS				Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide	
				f = feed (0.001 in./tooth), **s** = speed (ft/min)															
				Opt.		*Avg.*		*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Ultra-high-strength steels (not AISI): AMS 6421 (98B37 Mod.), 6422 (98BV40), 6424, 6427, 6428, 6430, 6432, 6433, 6434, 6436, and 6442; 300M, D6ac	220–300	60	**f**					8	4	8	4								
	300–350	45	**s**					165	355	300	480								
	350–400	20	**f**	8	4			8	4					39	20	39	20		
			s	15	45			150	320					130	235	75	175		
	43–52 Rc	—	**f**					5	3							39	20		
			s					20†	55							5	15		
Maraging steels (not AISI): 18% Ni Grades 200, 250, 300, and 350	250–325	50	**f**					8	4	8	4								
			s					165	355	300	480								
	50–52 Rc	—	**f**					5	3							39	20		
			s					20†	55							5	15		
Nitriding steels (not AISI): Nitralloy 125, 135, 135 Mod., 225, and 230, Nitralloy N, Nitralloy EZ, Nitrex 1	200–250	60	**f**	15	8			15	8	15	8			39	20	39	20	39	20
			s	7	30			105	270	220	450			295	475	135	305	265	495
	300–350	25	**f**	15	8			15	8	15	8			39	20				
			s	5	20			40	155	75	225			175	280				

For HSS (high-speed steel) tools in the first speed column only, use Table 15a for recommended feed in inches per tooth and depth of cut.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter *D* of 4.0 inches, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: end and slit milling uncoated carbide = 20 except † = 15; face milling uncoated carbide = 19; end, face, and slit milling coated carbide = 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Cutting Feeds and Speeds for Milling Tool Steels

Material	Brinell Hardness	HSS Speed (fpm)	End Milling						Face Milling				Slit Milling			
			HSS		Uncoated Carbide		Coated Carbide		Uncoated Carbide		CBN		Uncoated Carbide		Coated Carbide	
			f = feed (0.001 in./tooth), **s** = speed (ft/min)													
			Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Water hardening: W1, W2, W5	150–200	85														
Shock resisting: S1, S2, S5, S6, S7	175–225	55														
Cold work, oil hardening: O1, O2, O6, O7	175–225	50	**f**	8	4	8	4	8	4	39	20			39	20	39	20
			s	25	70	235	455	405	635	235	385			115	265	245	445
Cold work, high carbon, high chromium: D2, D3, D4, D5, D7	200–250	40														
Cold work, air hardening: A2, A3, A8, A9, A10	200–250	50														
A4, A6	200–250	45	**f**							39	20						
A7	225–275	40	**s**							255	385						
Hot work, chromium type: H10, H11, H12, H13, H14, H19	150–200	60														
	200–250	50														
	325–375	30	**f**	8	4	8	4			39	20			39	20		
			s	15	45	150	320			130	235			75	175		
	48–50 Rc	—															
	50–52 Rc	—	**f**			5	3					39	20	39	20		
	52–56 Rc	—	**s**			20†	55					50	135	5†	15		
Hot work, tungsten and molybdenum types: H21, H22, H23, H24, H25, H26, H41, H42, H43	150–200	55														
	200–250	45	**f**							39	20						
			s							255	385						
Special-purpose, low alloy: L2, L3, L6	150–200	65														
Mold: P2, P3, P4, P5, P6 P20, P21	100–150	75	**f**	8	4	8	4	8	4	39	20			39	20	39	20
	150–200	60	**s**	25	70	235	455	405	635	235	385			115	265	245	445
High-speed steel: M1, M2, M6, M10, T1, T2, T6	200–250	50														
M3-1, M4, M7, M30, M33, M34, M36, M41, M42, M43, M44, M46, M47, T5, T8	225–275	40	**f**							39	20						
			s							255	385						
T15, M3-2	225–275	30															

Copyright 2004, Industrial Press, Inc., New York, NY

For HSS (high-speed steel) tools in the first speed column only, use Table 15a for recommended feed in inches per tooth and depth of cut.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter *D* of 4.0 inches, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 20, † = 15; coated carbide = 10; CBN = 1.

Table 13. Cutting Feeds and Speeds for Milling Stainless Steels

Material	Brinell Hardness	HSS Speed (fpm)	End Milling								Face Milling		Slit Milling			
			HSS			Uncoated Carbide		Coated Carbide			Coated Carbide		Uncoated Carbide		Coated Carbide	
			f = feed (0.001 in./tooth), **s** = speed (ft/min)													
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*		*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Free-machining stainless steels (Ferritic): 430F, 430FSe	135–185	110	**f**	7	4	7	4	7	4		39	20	39	20	39	20
			s	30	80	305	780	420	1240		210	385	120	345	155	475
(Austenitic): 203EZ, 303, 303Se, 303MA, 303Pb, 303Cu, 303 Plus X	135–185	100	**f**	7	4	7	4						39	20		
	225–275	80	**s**	20	55	210	585						75	240		
(Martensitic): 416, 416Se, 416 Plus X, 420F, 420FSe, 440F, 440FSe	135–185	110														
	185–240	100														
	275–325	60														
	375–425	30														
Stainless steels (Ferritic): 405, 409, 429, 430, 434, 436, 442, 446, 502	135–185	90	**f**	7	4	7	4	7	4		39	20	39	20	39	20
			s	30	80	305	780	420	1240		210	385	120	345	155	475
(Austenitic): 201, 202, 301, 302, 304, 304L, 305, 308, 321, 347, 348	135–185	75	**f**	7	4	7	4						39	20		
	225–275	65	**s**	20	55	210	585						75	240		
(Austenitic): 302B, 309, 309S, 310, 310S, 314, 316, 316L, 317, 330	135–185	70														
(Martensitic): 403, 410, 420, 501	135–175	95														
	175–225	85														
	275–325	55														
	375–425	35														

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **Cutting Feeds and Speeds for Milling Stainless Steels**

Material	Brinell Hardness	HSS Speed (fpm)	End Milling						Face Milling		Slit Milling			
			HSS		Uncoated Carbide		Coated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide	
			f = feed (0.001 in./tooth), **s** = speed (ft/min)											
			Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Stainless Steels (Martensitic): 414, 431, Greek Ascoloy, 440A, 440B, 440C	225–275	55–60												
	275–325	45–50												
	375–425	30												
(Precipitation hardening): 15-5PH, 17-4PH, 17-7PH, AF-71, 17-14CuMo, AFC-77, AM-350, AM-355, AM-362, Custom 455, HNM, PH13-8, PH14-8Mo, PH15-7Mo, Stainless W	150–200	60	**f** 7 **s** 20	4 55	7 210	4 585					39 75	20 240		
	275–325	50												
	325–375	40												
	375–450	25												

For HSS (high-speed steel) tools in the first speed column only, use Table 15a for recommended feed in inches per tooth and depth of cut.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter *D* of 4.0 inch, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 20; coated carbide = 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Cutting Feeds and Speeds for Milling Ferrous Cast Metals

Material	Brinell Hardness	Speed (fpm)		End Milling						Face Milling								Slit Milling			
		HSS		HSS		Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Ceramic		CBN		Uncoated Carbide		Coated Carbide	
				f = feed (0.001 in./tooth), **s** = speed (ft/min)																	
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Gray Cast Iron																					
ASTM Class 20	120–150	100	**f**	5	3	5	3			39	20	39	20	39	20	39	20	39	20		
ASTM Class 25	160–200	80	**s**	35	90	520	855			140	225	285	535	1130	1630	200	530	205	420		
ASTM Class 30, 35, and 40	190–220	70																			
ASTM Class 45 and 50	220–260	50	**f**	5	3	5	3			39	20	39	20	39	20	39	20	39	20		
ASTM Class 55 and 60	250–320	30	**s**	30	70	515	1100			95	160	185	395	845	1220	150	400	145	380		
ASTM Type 1, 1b, 5 (Ni resist)	100–215	50																			
ASTM Type 2, 3, 6 (Ni resist)	120–175	40																			
ASTM Type 2b, 4 (Ni resist)	150–250	30																			
Malleable Iron																					
(Ferritic): 32510, 35018	110–160	110	**f**	5	3	5	3			39	20	39	20	39	20			39	20		
			s	30	70	180	250			120	195	225	520	490	925			85	150		
(Pearlitic): 40010, 43010, 45006, 45008, 48005, 50005	160–200	80	**f**	5	3	5	3			39	20	39	20	39	20			39	20		
	200–240	65	**s**	25	65	150	215			90	150	210	400	295	645			70	125		
(Martensitic): 53004, 60003, 60004	200–255	55																			
(Martensitic): 70002, 70003	220–260	50																			
(Martensitic): 80002	240–280	45																			
(Martensitic): 90001	250–320	25																			
Nodular (Ductile) Iron																					
(Ferritic): 60-40-18, 65-45-12	140–190	75	**f**	7	4	7	4			39	20	39	20	39	20			39	20		
			s	15	35	125	240			100	155	120	255	580	920			60	135		
(Ferritic-Pearlitic): 80-55-06	190–225	60	**f**	7	4	7	4			39	20	39	20	39	20			39	20		
	225–260	50	**s**	10	30	90	210			95	145	150	275	170	415			40	100		
(Pearlitic-Martensitic): 100-70-03	240–300	40																			
(Martensitic): 120-90-02	270–330	25																			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Cutting Feeds and Speeds for Milling Ferrous Cast Metals**

Material	Brinell Hardness	Speed (fpm)		End Milling HSS Opt.	End Milling HSS Avg.	End Milling Uncoated Carbide Opt.	End Milling Uncoated Carbide Avg.	End Milling Coated Carbide Opt.	End Milling Coated Carbide Avg.	Face Milling Uncoated Carbide Opt.	Face Milling Uncoated Carbide Avg.	Face Milling Coated Carbide Opt.	Face Milling Coated Carbide Avg.	Face Milling Ceramic Opt.	Face Milling Ceramic Avg.	Face Milling CBN Opt.	Face Milling CBN Avg.	Slit Milling Uncoated Carbide Opt.	Slit Milling Uncoated Carbide Avg.	Slit Milling Coated Carbide Opt.	Slit Milling Coated Carbide Avg.
		HSS				Uncoated Carbide		Coated Carbide		Uncoated Carbide		Coated Carbide		Ceramic		CBN		Uncoated Carbide		Coated Carbide	
				f = feed (0.001 in./tooth), **s** = speed (ft/min)																	
Cast Steels																					
(Low carbon): 1010, 1020	100–150	100	**f**	7	4	7	4	7	4			39	20					39	20	39	20
	125–175	95	**s**	25	70	245†	410	420	650			265‡	430					135†	260	245	450
(Medium carbon): 1030, 1040 1050	175–225	80																			
	225–300	60																			
	150–200	85	**f**	7	4	7	4	7	4			39	20					39	20	39	20
	200–250	75	**s**	20	55	160†	400	345	560			205‡	340					65†	180	180	370
(Low-carbon alloy): 1320, 2315, 2320, 4110, 4120, 4320, 8020, 8620	250–300	50																			
	175–225	70	**f**	7	4	7	4											39	20		
(Medium-carbon alloy): 1330, 1340, 2325, 2330, 4125, 4130, 4140, 4330,	225–250	65	**s**	15	45	120†	310											45†	135		
4340, 8030, 80B30, 8040, 8430, 8440, 8630, 8640, 9525, 9530, 9535	250–300	50	**f**							39	20										
	300–350	30	**s**							25	40										

For HSS (high-speed steel) tools in the first speed column only, use Table 15a for recommended feed in inches per tooth and depth of cut.

End Milling: Table data for end milling are based on a 3-tooth, 20-degree helix angle tool with a diameter of 1.0 inch, an axial depth of cut of 0.2 inch, and a radial depth of cut of 1 inch (full slot). Use Table 15b to adjust speeds for other feeds and axial depths of cut, and Table 15c to adjust speeds if the radial depth of cut is less than the tool diameter. Speeds are valid for all tool diameters.

Face Milling: Table data for face milling are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). These speeds are valid if the cutter axis is above or close to the center line of the workpiece (eccentricity is small). Under these conditions, use Table 15d to adjust speeds for other feeds and axial and radial depths of cut. For larger eccentricity (i.e., when the cutter axis to workpiece center line offset is one half the cutter diameter or more), use the end and side milling adjustment factors (Tables 15b and 15c) instead of the face milling factors.

Slit and Slot Milling: Table data for slit milling are based on an 8-tooth, 10-degree helix angle tool with a cutter width of 0.4 inch, diameter *D* of 4.0 inches, and a depth of cut of 0.6 inch. Speeds are valid for all tool diameters and widths. See the examples in the text for adjustments to the given speeds for other feeds and depths of cut.

Tool life for all tabulated values is approximately 45 minutes; use Table 15e to adjust tool life from 15 to 180 minutes. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 15 except † = 20; end and slit milling coated carbide = 10; face milling coated carbide = 11 except ‡ = 10. ceramic = 6; CBN = 1.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15a. Recommended Feed in Inches per Tooth (f_t) for Milling with High Speed Steel Cutters

Material	Hardness, HB	End Mills							Plain or Slab Mills	Form Relieved Cutters	Face Mills and Shell End Mills	Slotting and Side Mills
		Depth of Cut, .250 in			Depth of Cut, .050 in							
		Cutter Diam., in			Cutter Diam., in							
		½	¾	1 and up	¼	½	¾	1 and up				
		Feed per Tooth, inch										
Free-machining plain carbon steels	100–185	.001	.003	.004	.001	.002	.003	.004	.003–.008	.005	.004–.012	.002–.008
Plain carbon steels, AISI 1006 to 1030; 1513 to 1522	100–150	.001	.003	.003	.001	.002	.003	.004	.003–.008	.004	.004–.012	.002–.008
	150–200	.001	.002	.003	.001	.002	.002	.003	.003–.008	.004	.003–.012	.002–.008
AISI 1033 to 1095; 1524 to 1566	120–180	.001	.003	.003	.001	.002	.003	.004	.003–.008	.004	.004–.012	.002–.008
	180–220	.001	.002	.003	.001	.002	.002	.003	.003–.008	.004	.003–.012	.002–.008
	220–300	.001	.002	.002	.001	.001	.002	.003	.002–.006	.003	.002–.008	.002–.006
Alloy steels having less than 3% carbon. Typical examples: AISI 4012, 4023, 4027, 4118, 4320 4422, 4427, 4615, 4620, 4626, 4720, 4820, 5015, 5120, 6118, 8115, 8620 8627, 8720, 8820, 8822, 9310, 93B17	125–175	.001	.003	.003	.001	.002	.003	.004	.003–.008	.004	.004–.012	.002–.008
	175–225	.001	.002	.003	.001	.002	.003	.003	.003–.008	.004	.003–.012	.002–.008
	225–275	.001	.002	.003	.001	.001	.002	.003	.002–.006	.003	.003–.008	.002–.006
	275–325	.001	.002	.002	.001	.001	.002	.002	.002–.005	.003	.002–.008	.002–.005
Alloy steels having 3% carbon or more. Typical examples: AISI 1330, 1340, 4032, 4037, 4130, 4140, 4150, 4340, 50B40, 50B60, 5130, 51B60, 6150, 81B45, 8630, 8640, 86B45, 8660, 8740, 94B30	175–225	.001	.002	.003	.001	.002	.003	.004	.003–.008	.004	.003–.012	.002–.008
	225–275	.001	.002	.003	.001	.001	.002	.003	.002–.006	.003	.003–.010	.002–.006
	275–325	.001	.002	.002	.001	.001	.002	.003	.002–.005	.003	.002–.008	.002–.005
	325–375	.001	.002	.002	.001	.001	.002	.002	.002–.004	.002	.002–.008	.002–.005
Tool steel	150–200	.001	.002	.002	.001	.002	.003	.003	.003–.008	.004	.003–.010	.002–.006
	200–250	.001	.002	.002	.001	.002	.002	.003	.002–.006	.003	.003–.008	.002–.005
Gray cast iron	120–180	.001	.003	.004	.002	.003	.004	.004	.004–.012	.005	.005–.016	.002–.010
	180–225	.001	.002	.003	.001	.002	.003	.003	.003–.010	.004	.004–.012	.002–.008
	225–300	.001	.002	.002	.001	.001	.002	.002	.002–.006	.003	.002–.008	.002–.005
Free malleable iron	110–160	.001	.003	.004	.002	.003	.004	.004	.003–.010	.005	.005–.016	.002–.010

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15a. ***(Continued)*** **Recommended Feed in Inches per Tooth (f_t) for Milling with High Speed Steel Cutters**

Material*(Continued)*	Hardness, HB	End Mills							Plain or Slab Mills	Form Relieved Cutters	Face Mills and Shell End Mills	Slotting and Side Mills
		Depth of Cut, .250 in			Depth of Cut, .050 in							
		Cutter Diam., in			Cutter Diam., in							
		1/2	3/4	1 and up	1/4	1/2	3/4	1 and up				
		Feed per Tooth, inch										
Pearlitic-Martensitic malleable iron	160–200	.001	.003	.004	.001	.002	.003	.004	.003–.010	.004	.004–.012	.002–.018
	200–240	.001	.002	.003	.001	.002	.003	.003	.003–.007	.004	.003–.010	.002–.006
	240–300	.001	.002	.002	.001	.001	.002	.002	.002–.006	.003	.002–.008	.002–.005
Cast steel	100–180	.001	.003	.003	.001	.002	.003	.004	.003–.008	.004	.003–.012	.002–.008
	180–240	.001	.002	.003	.001	.002	.003	.003	.003–.008	.004	.003–.010	.002–.006
	240–300	.001	.002	.002	.005	.002	.002	.002	.002–.006	.003	.003–.008	.002–.005
Zinc alloys (die castings)	…	.002	.003	.004	.001	.003	.004	.006	.003–.010	.005	.004–.015	.002–.012
Copper alloys (brasses & bronzes)	100–150	.002	.004	.005	.002	.003	.005	.006	.003–.015	.004	.004–.020	.002–.010
	150–250	.002	.003	.004	.001	.003	.004	.005	.003–.015	.004	.003–.012	.002–.008
Free cutting brasses & bronzes	80–100	.002	.004	.005	.002	.003	.005	.006	.003–.015	.004	.004–.015	.002–.010
Cast aluminum alloys—as cast	…	.003	.004	.005	.002	.004	.005	.006	.005–.016	.006	.005–.020	.004–.012
Cast aluminum alloys—hardened	…	.003	.004	.005	.002	.003	.004	.005	.004–.012	.005	.005–.020	.004–.012
Wrought aluminum alloys— cold drawn	…	.003	.004	.005	.002	.003	.004	.005	.004–.014	.005	.005–.020	.004–.012
Wrought aluminum alloys—hardened	…	.002	.003	.004	.001	.002	.003	.004	.003–.012	.004	.005–.020	.004–.012
Magnesium alloys	…	.003	.004	.005	.003	.004	.005	.007	.005–.016	.006	.008–.020	.005–.012
Ferritic stainless steel	135–185	.001	.002	.003	.001	.002	.003	.003	.002–.006	.004	.004–.008	.002–.007
Austenitic stainless steel	135–185	.001	.002	.003	.001	.002	.003	.003	.003–.007	.004	.005–.008	.002–.007
	185–275	.001	.002	.003	.001	.002	.002	.002	.003–.006	.003	.004–.006	.002–.007
Martensitic stainless steel	135–185	.001	.002	.002	.001	.002	.003	.003	.003–.006	.004	.004–.010	.002–.007
	185–225	.001	.002	.002	.001	.002	.002	.003	.003–.006	.004	.003–.008	.002–.007
	225–300	.0005	.002	.002	.0005	.001	.002	.002	.002–.005	.003	.002–.006	.002–.005
Monel	100–160	.001	.003	.004	.001	.002	.003	.004	.002–.006	.004	.002–.008	.002–.006

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15b. End Milling (Full Slot) Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle

Cutting Speed, $V = V_{opt} \times F_f \times F_d$																
Ratio of Chosen Feed to *Optimum* Feed	Ratio of the two cutting speeds (*average*/*optimum*) given in the tables V_{avg}/V_{opt}							Depth of Cut and Lead Angle								
								1 in	(25.4 mm)	0.4 in	(10.2 mm)	0.2 in	(5.1 mm)	0.1 in	(2.4 mm)	0.04 in	(1.0 mm)
	1.00	1.25	1.50	2.00	2.50	3.00	4.00	0°	45°	0°	45°	0°	45°	0°	45°	0°	45°
	Feed Factor, F_f							Depth of Cut and Lead Angle Factor, F_d									
1.00	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0.91	1.36	0.94	1.38	1.00	0.71	1.29	1.48	1.44	1.66
0.90	1.00	1.06	1.09	1.14	1.18	1.21	1.27	0.91	1.33	0.94	1.35	1.00	0.72	1.26	1.43	1.40	1.59
0.80	1.00	1.12	1.19	1.31	1.40	1.49	1.63	0.92	1.30	0.95	1.32	1.00	0.74	1.24	1.39	1.35	1.53
0.70	1.00	1.18	1.30	1.50	1.69	1.85	2.15	0.93	1.26	0.95	1.27	1.00	0.76	1.21	1.35	1.31	1.44
0.60	1.00	1.20	1.40	1.73	2.04	2.34	2.89	0.94	1.22	0.96	1.25	1.00	0.79	1.18	1.28	1.26	1.26
0.50	1.00	1.25	1.50	2.00	2.50	3.00	4.00	0.95	1.17	0.97	1.18	1.00	0.82	1.14	1.21	1.20	1.21
0.40	1.00	1.23	1.57	2.29	3.08	3.92	5.70	0.96	1.11	0.97	1.12	1.00	0.86	1.09	1.14	1.13	1.16
0.30	1.00	1.14	1.56	2.57	3.78	5.19	8.56	0.98	1.04	0.99	1.04	1.00	0.91	1.04	1.07	1.05	1.09
0.20	1.00	0.90	1.37	2.68	4.49	6.86	17.60	1.00	0.85	1.00	0.95	1.00	0.99	0.97	0.93	0.94	0.88
0.10	1.00	0.44	0.80	2.08	4.26	8.00	20.80	1.05	0.82	1.00	0.81	1.00	1.50	0.85	0.76	0.78	0.67

For HSS (high-speed steel) tool speeds in the first speed column of Tables 10 through 14, use Table 15a to determine appropriate feeds and depths of cut.

Cutting feeds and speeds for end milling given in Tables 11 through 14 (except those for high-speed steel in the first speed column) are based on milling a 0.20-inch deep full slot (i.e., radial depth of cut = end mill diameter) with a 1-inch diameter, 20-degree helix angle, 0-degree lead angle end mill. For other depths of cut (axial), lead angles, or feed, use the two feed/speed pairs from the tables and calculate the ratio of desired (new) feed to *optimum* feed (largest of the two feeds are given in the tables), and the ratio of the two cutting speeds (V_{avg}/V_{opt}). Find the feed factor F_f at the intersection of the feed ratio row and the speed ratio column in the left half of the Table. The depth of cut factor F_d is found in the same row as the feed factor, in the right half of the table under the column corresponding to the depth of cut and lead angle. The adjusted cutting speed can be calculated from $V = V_{opt} \times F_f \times F_d$, where V_{opt} is the smaller (*optimum*) of the two speeds from the speed table (from the left side of the column containing the two feed/speed pairs). See the text for examples.

If the radial depth of cut is less than the cutter diameter (i.e., for cutting less than a full slot), the feed factor F_f in the previous equation and the maximum feed f_{max} must be obtained from Table 15c. The axial depth of cut factor F_d can then be obtained from this table using f_{max} in place of the *optimum* feed in the feed ratio. Also see the footnote to Table 15c.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15c. End, Slit, and Side Milling Speed Adjustment Factors for Radial Depth of Cut

Ratio of Radial Depth of Cut to Diameter	Cutting Speed, $V = V_{opt} \times F_f \times F_d$														
	Maximum Feed/Tooth Factor	V_{avg}/V_{opt}						Maximum Feed/Tooth Factor	V_{avg}/V_{opt}					
		1.25	1.50	2.00	2.50	3.00	4.00		1.25	1.50	2.00	2.50	3.00	4.00
		Feed Factor F_f at Maximum Feed per Tooth, F_{f1}							Feed Factor F_f at Minimum Feed per Tooth, F_{f2}					
1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.70	1.18	1.30	1.50	1.69	1.85	2.15
0.75	1.00	1.15	1.24	1.46	1.54	1.66	1.87	0.70	1.24	1.48	1.93	2.38	2.81	3.68
0.60	1.00	1.23	1.40	1.73	2.04	2.34	2.89	0.70	1.24	1.56	2.23	2.95	3.71	5.32
0.50	1.00	1.25	1.50	2.00	2.50	3.00	4.00	0.70	1.20	1.58	2.44	3.42	4.51	6.96
0.40	1.10	1.25	1.55	2.17	2.83	3.51	4.94	0.77	1.25	1.55	2.55	3.72	5.08	8.30
0.30	1.35	1.20	1.57	2.28	3.05	3.86	5.62	0.88	1.23	1.57	2.64	4.06	5.76	10.00
0.20	1.50	1.14	1.56	2.57	3.78	5.19	8.56	1.05	1.40	1.56	2.68	4.43	6.37	11.80
0.10	2.05	0.92	1.39	2.68	4.46	6.77	13.10	1.44	0.92	1.29	2.50	4.66	7.76	17.40
0.05	2.90	0.68	1.12	2.50	4.66	7.75	17.30	2.00	0.68	1.12	2.08	4.36	8.00	20.80
0.02	4.50	0.38	0.71	1.93	4.19	7.90	21.50	3.10	0.38	0.70	1.38	3.37	7.01	22.20

This table is for side milling, end milling when the radial depth of cut (width of cut) is less than the tool diameter (i.e., less than full slot milling), and slit milling when the feed is parallel to the work surface (slotting). The radial depth of cut to diameter ratio is used to determine the recommended maximum and minimum values of feed/tooth, which are found by multiplying the feed/tooth factor from the appropriate column above (maximum or minimum) by feed$_{opt}$ from the speed tables. For example, given two feed/speed pairs $^{7}/_{15}$ and $^{4}/_{45}$ for end milling cast, medium-carbon, alloy steel, and a radial depth of cut to diameter ratio ar/D of 0.10 (a 0.05-inch width of cut for a $^{1}/_{2}$-inch diameter end mill, for example), the maximum feed $f_{max} = 2.05 \times 0.007 = 0.014$ in./tooth and the minimum feed $f_{min} = 1.44 \times 0.007 = 0.010$ in./tooth. The feed selected should fall in the range between f_{min} and f_{max}. The feed factor F_d is determined by interpolating between the feed factors F_{f1} and F_{f2} corresponding to the maximum and minimum feed per tooth, at the appropriate ar/D and speed ratio. In the example given, $ar/D = 0.10$ and $V_{avg}/V_{opt} = 45/15 = 3$, so the feed factor F_{f1} at the maximum feed per tooth is 6.77, and the feed factor F_{f2} at the minimum feed per tooth is 7.76. If a working feed of 0.012 in./tooth is chosen, the feed factor F_f is half way between 6.77 and 7.76 or by formula, $F_f = F_{f1} + (\text{feed} - f_{min})/(f_{max} - f_{min}) \times (f_{f2} - f_{f1}) = 6.77 + (0.012 - 0.010)/(0.014 - 0.010) \times (7.76 - 6.77) = 7.27$. The cutting speed is $V = V_{opt} \times F_f \times F_d$, where F_d is the depth of cut and lead angle factor from Table 15b that corresponds to the feed ratio (chosen feed)/f_{max}, not the ratio (chosen feed)/*optimum* feed. For a feed ratio = 0.012/0.014 = 0.86 (chosen feed/f_{max}), depth of cut = 0.2 inch and lead angle = 45°, the depth of cut factor F_d in Table 15b is between 0.72 and 0.74. Therefore, the final cutting speed for this example is $V = V_{opt} \times F_f \times F_d = 15 \times 7.27 \times 0.73 = 80$ ft/min.

Slit and Side Milling: This table only applies when feed is parallel to the work surface, as in slotting. If feed is perpendicular to the work surface, as in cutting off, obtain the required speed-correction factor from Table 15d (face milling). The minimum and maximum feeds/tooth for slit and side milling are determined in the manner described above, however, the axial depth of cut factor F_d is not required. The adjusted cutting speed, valid for cutters of any thickness (width), is given by $V = V_{opt} \times F_f$. Examples are given in the text.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15d. Face Milling Speed Adjustment Factors for Feed, Depth of Cut, and Lead Angle

Cutting Speed $V = V_{opt} \times F_f \times F_d \times F_{ar}$																								
Ratio of Chosen Feed to *Optimum* Feed	Ratio of the two cutting speeds (*average*/*optimum*) given in the tables V_{avg}/V_{opt}							Depth of Cut, inch (mm), and Lead Angle										Ratio of Radial Depth of Cut/Cutter Diameter, *ar*/*D*						
								1 in (25.4 mm)		0.4 in (10.2 mm)		0.2 in (5.1 mm)		0.1 in (2.4 mm)		0.04 in (1.0 mm)								
	1.00	1.10	1.25	1.35	1.50	1.00	2.00	15°	45°	15°	45°	15°	45°	15°	45°	15°	45°	1.00	0.75	0.50	0.40	0.30	0.20	0.10
	Feed Factor, F_f							Depth of Cut Factor, F_d										Radial Depth of Cut Factor, F_{ar}						
1.00	1.0	1.0	1.0	1.0	1.0	1.0	1.0	0.78	1.11	0.94	1.16	0.90	1.10	1.00	1.29	1.47	1.66	0.72	1.00	1.53	1.89	2.43	3.32	5.09
0.90	1.00	1.02	1.05	1.07	1.09	1.10	1.12	0.78	1.10	0.94	1.16	0.90	1.09	1.00	1.27	1.45	1.58	0.73	1.00	1.50	1.84	2.24	3.16	4.69
0.80	1.00	1.03	1.09	1.10	1.15	1.20	1.25	0.80	1.10	0.94	1.14	0.91	1.08	1.00	1.25	1.40	1.52	0.75	1.00	1.45	1.73	2.15	2.79	3.89
0.70	1.00	1.05	1.13	1.22	1.22	1.32	1.43	0.81	1.09	0.95	1.14	0.91	1.08	1.00	1.24	1.39	1.50	0.75	1.00	1.44	1.72	2.12	2.73	3.77
0.60	1.00	1.08	1.20	1.25	1.35	1.50	1.66	0.81	1.09	0.95	1.13	0.92	1.08	1.00	1.23	1.38	1.48	0.76	1.00	1.42	1.68	2.05	2.61	3.52
0.50	1.00	1.10	1.25	1.35	1.50	1.75	2.00	0.81	1.09	0.95	1.13	0.92	1.08	1.00	1.23	1.37	1.47	0.76	1.00	1.41	1.66	2.02	2.54	3.39
0.40	1.00	1.09	1.28	1.44	1.66	2.03	2.43	0.82	1.08	0.95	1.12	0.92	1.07	1.00	1.21	1.34	1.43	0.78	1.00	1.37	1.60	1.90	2.34	2.99
0.30	1.00	1.06	1.32	1.52	1.85	2.42	3.05	0.84	1.07	0.96	1.11	0.93	1.06	1.00	1.18	1.30	1.37	0.80	1.00	1.32	1.51	1.76	2.10	2.52
0.20	1.00	1.00	1.34	1.60	2.07	2.96	4.03	0.86	1.06	0.96	1.09	0.94	1.05	1.00	1.15	1.24	1.29	0.82	1.00	1.26	1.40	1.58	1.79	1.98
0.10	1.00	0.80	1.20	1.55	2.24	3.74	5.84	0.90	1.04	0.97	1.06	0.96	1.04	1.00	1.10	1.15	1.18	0.87	1.00	1.16	1.24	1.31	1.37	1.32

For HSS (high-speed steel) tool speeds in the first speed column, use Table 15a to determine appropriate feeds and depths of cut.

Tabular feeds and speeds data for face milling in Tables 11 through 14 are based on a 10-tooth, 8-inch diameter face mill, operating with a 15-degree lead angle, $\frac{3}{64}$-inch cutter insert nose radius, axial depth of cut = 0.1 inch, and radial depth (width) of cut = 6 inches (i.e., width of cut to cutter diameter ratio = $\frac{3}{4}$). For other depths of cut (radial or axial), lead angles, or feed, calculate the ratio of desired (new) feed to *optimum* feed (largest of the two feeds given in the speed table), and the ratio of the two cutting speeds (V_{avg}/V_{opt}). Use these ratios to find the feed factor F_f at the intersection of the feed ratio row and the speed ratio column in the left third of the table. The depth of cut factor F_d is found in the same row as the feed factor, in the center third of the table, in the column corresponding to the depth of cut and lead angle. The radial depth of cut factor F_{ar} is found in the same row as the feed factor, in the right third of the table, in the column corresponding to the radial depth of cut to cutter diameter ratio *ar*/*D*. The adjusted cutting speed can be calculated from $V = V_{opt} \times F_f \times F_d \times F_{ar}$, where V_{opt} is the smaller (*optimum*) of the two speeds from the speed table (from the left side of the column containing the two feed/speed pairs).

The cutting speeds as calculated above are valid if the cutter axis is centered above or close to the center line of the workpiece (eccentricity is small). For larger eccentricity (i.e., the cutter axis is offset from the center line of the workpiece by about one-half the cutter diameter or more), use the adjustment factors from Tables 15b and 15c (end and side milling) instead of the factors from this table. Use Table 15e to adjust end and face milling speeds for increased tool life up to 180 minutes.

Slit and Slot Milling: Tabular speeds are valid for all tool diameters and widths. Adjustments to the given speeds for other feeds and depths of cut depend on the circumstances of the cut. *Case 1:* If the cutter is fed directly into the workpiece, i.e., the feed is perpendicular to the surface of the workpiece, as in cutting off, then this table (face milling) is used to adjust speeds for other feeds. The depth of cut factor is not used for slit milling ($F_d = 1.0$), so the adjusted cutting speed $V = V_{opt} \times F_f \times F_{ar}$. For determining the factor F_{ar}, the radial depth of cut *ar* is the length of cut created by the portion of the cutter engaged in the work. *Case 2:* If the cutter is fed parallel to the surface of the workpiece, as in slotting, then Tables 15b and 15c are used to adjust the given speeds for other feeds. See Fig. 5.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15e. Tool Life Adjustment Factors for Face Milling, End Milling, Drilling, and Reaming

Tool Life, T (minutes)	Face Milling with Carbides and Mixed Ceramics			End Milling with Carbides and HSS			Twist Drilling and Reaming with HSS		
	f_s	f_m	f_l	f_s	f_m	f_l	f_s	f_m	f_l
15	1.69	1.78	1.87	1.10	1.23	1.35	1.11	1.21	1.30
45	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
90	0.72	0.70	0.67	0.94	0.89	0.83	0.93	0.89	0.85
180	0.51	0.48	0.45	0.69	0.69	0.69	0.87	0.80	0.72

The feeds and speeds given in Tables 11 through 14 and Tables 17 through 23 (except for HSS speeds in the first speed column) are based on a 45-minute tool life. To adjust the given speeds to obtain another tool life, multiply the adjusted cutting speed for the 45-minute tool life V_{45} by the tool life factor from this table according to the following rules: for small feeds, where feed $\leq \frac{1}{2} f_{opt}$, the cutting speed for the desired tool life T is $V_T = f_s \times V_{15}$; for medium feeds, where $\frac{1}{2} f_{opt} <$ feed $< \frac{3}{4} f_{opt}$, $V_T = f_m \times V_{15}$; and for larger feeds, where $\frac{3}{4} f_{opt} \leq$ feed $\leq f_{opt}$, $V_T = f_l \times V_{15}$. Here, f_{opt} is the largest (*optimum*) feed of the two feed/speed values given in the speed tables or the maximum feed f_{max} obtained from Table 15c, if that table was used in calculating speed adjustment factors.

Table 16. Cutting Tool Grade Descriptions and Common Vendor Equivalents

Grade Description	Tool Identification Code	Approximate Vendor Equivalents			
		Sandvik Coromant	Kennametal	Seco	Valenite
Cubic boron nitride	1	CB50	KD050	CBN20	VC721
Ceramics	2	CC620	K060	480	—
	3	CC650	K090	480	Q32
	4 (Whiskers)	CC670	KYON2500	—	—
	5 (Sialon)	CC680	KYON2000	480	—
	6	CC690	KYON3000	—	Q6
Cermets	7	CT515	KT125	CM	VC605
	8	CT525	KT150	CR	VC610
Polycrystalline	9	CD10	KD100	PAX20	VC727
Coated carbides	10	GC-A	—	—	—
	11	GC3015	KC910	TP100	SV310
	12	GC235	KC9045	TP300	SV235
	13	GC4025	KC9025	TP200	SV325
	14	GC415	KC950	TP100	SV315
Uncoated carbides	15	H13A	K8, K4H	883	VC2
	16	S10T	K420, K28	CP20	VC7
	17	S1P	K45	CP20	VC7
	18	S30T	—	CP25	VC5
	19	S6	K21, K25	CP50	VC56
	20	SM30	KC710	CP25	VC35M

See Table 2 on page 779 and the section *Cemented Carbides and Other Hard Materials* for more detailed information on cutting tool grades.

The identification codes in column two correspond to the grade numbers given in the footnotes to Tables 1 to 4b, 6 to 14, and 17 to 23.

Copyright 2004, Industrial Press, Inc., New York, NY

Using the Feed and Speed Tables for Drilling, Reaming, and Threading.— The first two speed columns in Tables 17 through 23 give traditional Handbook speeds for drilling and reaming. The following material can be used for selecting feeds for use with the traditional speeds.

The remaining columns in Tables 17 through 23 contain combined feed/speed data for drilling, reaming, and threading, organized in the same manner as in the turning and milling tables. Operating at the given feeds and speeds is expected to result in a tool life of approximately 45 minutes, except for indexable insert drills, which have an expected tool life of approximately 15 minutes per edge. Examples of using this data follow.

Adjustments to HSS drilling speeds for feed and diameter are made using Table 22; Table 5a is used for adjustments to indexable insert drilling speeds, where one-half the drill diameter D is used for the depth of cut. Tool life for HSS drills, reamers, and thread chasers and taps may be adjusted using Table 15e and for indexable insert drills using Table 5b.

The feed for drilling is governed primarily by the size of the drill and by the material to be drilled. Other factors that also affect selection of the feed are the workpiece configuration, the rigidity of the machine tool and the workpiece setup, and the length of the chisel edge. A chisel edge that is too long will result in a very significant increase in the thrust force, which may cause large deflections to occur on the machine tool and drill breakage.

For ordinary twist drills, the feed rate used is 0.001 to 0.003 in /rev for drills smaller than $\frac{1}{8}$ in, 0.002 to 0.006 in./rev for $\frac{1}{8}$- to $\frac{1}{4}$-in drills; 0.004 to 0.010 in./rev for $\frac{1}{4}$- to $\frac{1}{2}$-in drills; 0.007 to 0.015 in./rev for $\frac{1}{2}$- to 1-in drills; and, 0.010 to 0.025 in./rev for drills larger than 1 inch.

The lower values in the feed ranges should be used for hard materials such as tool steels, superalloys, and work-hardening stainless steels; the higher values in the feed ranges should be used to drill soft materials such as aluminum and brass.

Example 1, Drilling: Determine the cutting speed and feed for use with HSS drills in drilling 1120 steel.

Table 15a gives two sets of feed and speed parameters for drilling 1120 steel with HSS drills. These sets are 16⁄50 and 8⁄95, i.e., 0.016 in./rev feed at 50 ft/min and 0.008 in./rev at 95 fpm, respectively. These feed/speed sets are based on a 0.6-inch diameter drill. Tool life for either of the given feed/speed settings is expected to be approximately 45 minutes.

For different feeds or drill diameters, the cutting speeds must be adjusted and can be determined from $V = V_{opt} \times F_f \times F_d$, where V_{opt} is the minimum speed for this material given in the speed table (50 fpm in this example) and F_f and F_d are the adjustment factors for feed and diameter, respectively, found in Table 22.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. Feeds and Speeds for Drilling, Reaming, and Threading Plain Carbon and Alloy Steels

Material	Brinell Hardness	Drilling Speed (fpm) HSS	Reaming Speed (fpm) HSS		Drilling HSS Opt.	Drilling HSS Avg.	Drilling Indexable Insert Coated Carbide Opt.	Drilling Indexable Insert Coated Carbide Avg.	Reaming HSS Opt.	Reaming HSS Avg.	Threading HSS Opt.	Threading HSS Avg.
					f = feed (0.001 in./rev), **s** = speed (ft/min)							
Free-machining plain carbon steels (Resulfurized): 1212, 1213, 1215	100–150	120	80	**f**	21	11	8	4	36	18	83	20
				s	55	125	310	620	140	185	140	185
	150–200	125	80									
(Resulfurized): 1108, 1109, 1115, 1117, 1118, 1120, 1126, 1211	100–150	110	75	**f**	16	8	8	4	27	14	83	20
	150–200	120	80	**s**	50	95	370	740	105	115	90	115
(Resulfurized): 1132, 1137, 1139, 1140, 1144, 1146, 1151	175–225	100	65	**f**			8	4				
				s			365	735				
	275–325	70	45									
	325–375	45	30									
	375–425	35	20									
(Leaded): 11L17, 11L18, 12L13, 12L14	100–150	130	85									
	150–200	120	80									
	200–250	90	60	**f**			8	4				
				s			365	735				
Plain carbon steels: 1006, 1008, 1009, 1010, 1012, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1513, 1514	100–125	100	65	**f**	21	11	8	4	36	18	83	20
				s	55	125	310	620	140	185	140	185
	125–175	90	60									
	175–225	70	45	**f**			8	4				
	225–275	60	40	**s**			365	735				
Plain carbon steels: 1027, 1030, 1033, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1045, 1046, 1048, 1049, 1050, 1052, 1524, 1526, 1527, 1541	125–175	90	60									
	175–225	75	50									
	225–275	60	40	**f**			8	4				
	275–325	50	30	**s**			365	735				
	325–375	35	20									
	375–425	25	15									

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. ***(Continued)*** **Feeds and Speeds for Drilling, Reaming, and Threading Plain Carbon and Alloy Steels**

Material	Brinell Hardness	Drilling HSS Speed (fpm)		Reaming HSS Speed (fpm)		Drilling HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)				Drilling Indexable Insert Coated Carbide				Reaming HSS				Threading HSS			
						Opt.		*Avg.*		*Opt.*		*Avg.*		*Opt.*		*Avg.*		*Opt.*		*Avg.*	
Plain carbon steels *(Continued):* 1055, 1060, 1064, 1065, 1070, 1074, 1078, 1080, 1084, 1086, 1090, 1095, 1548, 1551, 1552, 1561, 1566	125–175	85		55	**f**	16		8		8		4		27		14		83		20	
	175–225	70		45	**s**	50		95		370		740		105		115		90		115	
	225–275	50		30	**f**					8		4									
					s					365		735									
	275–325	40		25																	
	325–375	30		20																	
	375–425	15		10																	
Free-machining alloy steels (Resulfurized): 4140, 4150	175–200	90		60	**f**	16		8		8		4		26		13		83		20	
	200–250	80		50	**s**	75		140		410		685		150		160		125		160	
	250–300	55		30	**f**					8		4									
					s					355		600									
	300–375	40		25	**f**					8		4									
	375–425	30		15	**s**					310		525									
(Leaded): 41L30, 41L40, 41L47, 41L50, 43L47, 51L32, 52L100, 86L20, 86L40	150–200	100		65	**f**	16		8		8		4		27		14		83		20	
					s	50		95		370		740		105		115		90		115	
	200–250	90		60	**f**					8		4									
					s					365		735									
	250–300	65		40																	
	300–375	45		30																	
	375–425	30		15																	
Alloy steels: 4012, 4023, 4024, 4028, 4118, 4320, 4419, 4422, 4427, 4615, 4620, 4621, 4626, 4718, 4720, 4815, 4817, 4820, 5015, 5117, 5120, 6118, 8115, 8615, 8617, 8620, 8622, 8625, 8627, 8720, 8822, 94B17	125–175	85		55	**f**	16		8		8		4		26		13		83		20	
	175–225	70		45	**s**	75		140		410		685		150		160		125		160	
	225–275	55		35	**f**					8		4									
					s					355		600									
	275–325	50		30	**f**	11		6		8		4		19		10		83		20	
					s	50		85		335		570		95		135		60		95	
	325–375	35		25	**f**					8		4									
	375–425	25		15	**s**					310		525									

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. ***(Continued)*** **Feeds and Speeds for Drilling, Reaming, and Threading Plain Carbon and Alloy Steels**

Material	Brinell Hardness	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)	Drilling HSS		Drilling Indexable Insert Coated Carbide		Reaming HSS		Threading HSS	
				f = feed (0.001 in./rev), **s** = speed (ft/min)							
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Alloy steels: 1330, 1335, 1340, 1345, 4032, 4037, 4042, 4047, 4130, 4135, 4137, 4140, 4142, 4145, 4147, 4150, 4161, 4337, 4340, 50B44, 50B46, 50B50, 50B60, 5130, 5132, 5140, 5145, 5147, 5150, 5160, 51B60, 6150, 81B45, 8630, 8635, 8637, 8640, 8642, 8645, 8650, 8655, 8660, 8740, 9254, 9255, 9260, 9262, 94B30 E51100, E52100: use (HSS speeds)	175–225	75 (60)	50 (40)	**f** 16 **s** 75	8 140	8 410	4 685	26 150	13 160	83 125	20 160
	225–275	60 (50)	40 (30)	**f** **s**		8 355	4 600				
	275–325	45 (35)	30 (25)	**f** 11 **s** 50	6 85	8 335	4 570	19 95	10 135	83 60	20 95
	325–375	30 (30)	15 (20)	**f** **s**		8 310	4 525				
	375–425	20 (20)	15 (10)								
Ultra-high-strength steels (not AISI): AMS 6421 (98B37 Mod.), 6422 (98BV40), 6424, 6427, 6428, 6430, 6432, 6433, 6434, 6436, and 6442; 300M, D6ac	220–300	50	30	**f** **s**		8 325	4 545				
	300–350	35	20								
	350–400	20	10	**f** **s**		8 270	4 450				
Maraging steels (not AISI): 18% Ni Grade 200, 250, 300, and 350	250–325	50	30	**f** **s**		8 325	4 545				
Nitriding steels (not AISI): Nitralloy 125, 135, 135 Mod., 225, and 230, Nitralloy N, Nitralloy EZ, Nitrex I	200–250	60	40	**f** 16 **s** 75	8 140	8 410	4 685	26 150	13 160	83 125	20 160
	300–350	35	20	**f** **s**		8 310	4 525				

The two leftmost speed columns in this table contain traditional Handbook speeds for drilling and reaming with HSS steel tools. The section Feed Rates for Drilling and Reaming contains useful information concerning feeds to use in conjunction with these speeds.

HSS Drilling and Reaming: The combined feed/speed data for drilling are based on a 0.60-inch diameter HSS drill with standard drill point geometry (2-flute with 118° tip angle). Speed adjustment factors in Table 22 are used to adjust drilling speeds for other feeds and drill diameters. Examples of using this data are given in the text. The given feeds and speeds for reaming are based on an 8-tooth, $^{25}/_{32}$-inch diameter, 30° lead angle reamer, and a 0.008-inch radial depth of cut. For other feeds, the correct speed can be obtained by interpolation using the given speeds if the desired feed lies in the recommended range (between the given values of *optimum* and *average* feed). If a feed lower than the given *average* value is chosen, the speed should be maintained at the corresponding *average* speed (i.e., the highest of the two speed values given). The cutting speeds for reaming do not require adjustment for tool diameters for standard ratios of radical depth of cut to reamer diameter (i.e., f_d = 1.00). Speed adjustment factors to modify tool life are found in Table 15e.

Copyright 2004, Industrial Press, Inc., New York, NY

Indexable Insert Drilling: The feed/speed data for indexable insert drilling are based on a tool with two cutting edges, an insert nose radius of $\frac{3}{64}$ inch, a 10-degree lead angle, and diameter $D = 1$ inch. Adjustments to cutting speed for feed and depth of cut are made using Table 5aAdjustment Factors) using a depth of cut of $D/2$, or one-half the drill diameter. Expected tool life at the given feeds and speeds is approximately 15 minutes for short hole drilling (i.e., where maximum hole depth is about $2D$ or less). Speed adjustment factors to increase tool life are found in Table 5b.

Tapping and Threading: The data in this column are intended for use with thread chasers and for tapping. The feed used for tapping and threading must be equal to the lead (feed = lead = pitch) of the thread being cut. The two feed/speed pairs given for each material, therefore, are representative speeds for two thread pitches, 12 and 50 threads per inch (1/0.083 = 12, and 1/0.020 = 50). Tool life is expected to be approximately 45 minutes at the given feeds and speeds. When cutting fewer than 12 threads per inch (pitch ≥ 0.08 inch), use the lower (*optimum*) speed; for cutting more than 50 threads per inch (pitch ≤ 0.02 inch), use the larger (*average*) speed; and, in the intermediate range between 12 and 50 threads per inch, interpolate between the given *average* and *optimum* speeds.

The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: coated carbide = 10.

Example 2, Drilling: If the 1120 steel of Example 1 is to be drilled with a 0.60-inch drill at a feed of 0.012 in./rev, what is the cutting speed in ft/min? Also, what spindle rpm of the drilling machine is required to obtain this cutting speed?

To find the feed factor F_d in Table 22, calculate the ratio of the desired feed to the *optimum* feed and the ratio of the two cutting speeds given in the speed tables. The desired feed is 0.012 in./rev and the *optimum* feed, as explained above is 0.016 in./rev, therefore, feed/f_{opt} = 0.012/0.016 = 0.75 and V_{avg}/V_{opt} = 95/50 = 1.9, approximately 2.

The feed factor F_f is found at the intersection of the feed ratio row and the speed ratio column. $F_f = 1.40$ corresponds to about halfway between 1.31 and 1.50, which are the feed factors that correspond to $V_{avg}/V_{opt} = 2.0$ and feed/f_{opt} ratios of 0.7 and 0.8, respectively. F_d, the diameter factor, is found on the same row as the feed factor (halfway between the 0.7 and 0.8 rows, for this example) under the column for drill diameter = 0.60 inch. Because the speed table values are based on a 0.60-inch drill diameter, $F_d = 1.0$ for this example, and the cutting speed is $V = V_{opt} \times F_f \times F_d = 50 \times 1.4 \times 1.0 = 70$ ft/min. The spindle speed in rpm is $N = 12 \times V/(\pi \times D) = 12 \times 70/(3.14 \times 0.6) = 445$ rpm.

Example 3, Drilling: Using the same material and feed as in the previous example, what cutting speeds are required for 0.079-inch and 4-inch diameter drills? What machine rpm is required for each?

Because the feed is the same as in the previous example, the feed factor is $F_f = 1.40$ and does not need to be recalculated. The diameter factors are found in Table 22 on the same row as the feed factor for the previous example (about halfway between the diameter factors corresponding to feed/f_{opt} values of 0.7 and 0.8) in the column corresponding to drill diameters 0.079 and 4.0 inches, respectively. Results of the calculations are summarized below.

Drill diameter = 0.079 inch	*Drill diameter = 4.0 inches*
$F_f = 1.40$	$F_f = 1.40$
$F_d = (0.34 + 0.38)/2 = 0.36$	$F_d = (1.95 + 1.73)/2 = 1.85$
$V = 50 \times 1.4 \times 0.36 = 25.2$ fpm	$V = 50 \times 1.4 \times 1.85 = 129.5$ fpm
$12 \times 25.2/(3.14 \times 0.079) = 1219$ rpm	$12 \times 129.5/(3.14 \times 4) = 124$ rpm

Copyright 2004, Industrial Press, Inc., New York, NY

Drilling Difficulties: A drill split at the web is evidence of too much feed or insufficient lip clearance at the center due to improper grinding. Rapid wearing away of the extreme outer corners of the cutting edges indicates that the speed is too high. A drill chipping or breaking out at the cutting edges indicates that either the feed is too heavy or the drill has been ground with too much lip clearance. Nothing will "check" a high-speed steel drill quicker than to turn a stream of cold water on it after it has been heated while in use. It is equally bad to plunge it in cold water after the point has been heated in grinding. The small checks or cracks resulting from this practice will eventually chip out and cause rapid wear or breakage. Insufficient speed in drilling small holes with hand feed greatly increases the risk of breakage, especially at the moment the drill is breaking through the farther side of the work, due to the operator's inability to gage the feed when the drill is running too slowly.

Small drills have heavier webs and smaller flutes in proportion to their size than do larger drills, so breakage due to clogging of chips in the flutes is more likely to occur. When drilling holes deeper than three times the diameter of the drill, it is advisable to withdraw the drill (peck feed) at intervals to remove the chips and permit coolant to reach the tip of the drill.

Drilling Holes in Glass: The simplest method of drilling holes in glass is to use a standard, tungsten-carbide-tipped masonry drill of the appropriate diameter, in a gun-drill. The edges of the carbide in contact with the glass should be sharp. Kerosene or other liquid may be used as a lubricant, and a light force is maintained on the drill until just before the point breaks through. The hole should then be started from the other side if possible, or a very light force applied for the remainder of the operation, to prevent excessive breaking of material from the sides of the hole. As the hard particles of glass are abraded, they accumulate and act to abrade the hole, so it may be advisable to use a slightly smaller drill than the required diameter of the finished hole.

Alternatively, for holes of medium and large size, use brass or copper tubing, having an outside diameter equal to the size of hole required. Revolve the tube at a peripheral speed of about 100 feet per minute, and use carborundum (80 to 100 grit) and light machine oil between the end of the pipe and the glass. Insert the abrasive under the drill with a thin piece of soft wood, to avoid scratching the glass. The glass should be supported by a felt or rubber cushion, not much larger than the hole to be drilled. If practicable, it is advisable to drill about halfway through, then turn the glass over, and drill down to meet the first cut. Any fin that may be left in the hole can be removed with a round second-cut file wetted with turpentine.

Smaller-diameter holes may also be drilled with triangular-shaped cemented carbide drills that can be purchased in standard sizes. The end of the drill is shaped into a long tapering triangular point. The other end of the cemented carbide bit is brazed onto a steel shank. A glass drill can be made to the same shape from hardened drill rod or an old three-cornered file. The location at which the hole is to be drilled is marked on the workpiece. A dam of putty or glazing compound is built up on the work surface to contain the cutting fluid, which can be either kerosene or turpentine mixed with camphor. Chipping on the back edge of the hole can be prevented by placing a scrap plate of glass behind the area to be drilled and drilling into the backup glass. This procedure also provides additional support to the workpiece and is essential for drilling very thin plates. The hole is usually drilled with an electric hand drill. When the hole is being produced, the drill should be given a small circular motion using the point as a fulcrum, thereby providing a clearance for the drill in the hole.

Very small round or intricately shaped holes and narrow slots can be cut in glass by the ultrasonic machining process or by the abrasive jet cutting process.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. Feeds and Speeds for Drilling, Reaming, and Threading Tool Steels

Material	Brinell Hardness	Drilling Speed (fpm) HSS	Reaming Speed (fpm) HSS	Drilling HSS f = feed (0.001 in./rev), s = speed (ft/min)		Drilling Indexable Insert Uncoated Carbide f = feed (0.001 in./rev), s = speed (ft/min)		Reaming HSS f = feed (0.001 in./rev), s = speed (ft/min)		Threading HSS f = feed (0.001 in./rev), s = speed (ft/min)	
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Water hardening: W1, W2, W5	150–200	85	55								
Shock resisting: S1, S2, S5, S6, S7	175–225	50	35								
Cold work (oil hardening): O1, O2, O6, O7	175–225	45	30								
(High carbon, high chromium): D2, D3, D4, D5, D7	200–250	30	20								
(Air hardening): A2, A3, A8, A9, A10	200–250	50	35	**f**	15	8	4	24	12	83	20
A4, A6	200–250	45	30	**s**	45	360	605	90	95	75	95
A7	225–275	30	20		85						
Hot work (chromium type): H10, H11, H12, H13, H14, H19	150–200	60	40								
	200–250	50	30								
	325–375	30	20	**f**		8	4				
				s		270	450				
(Tungsten type): H21, H22, H23, H24, H25, H26	150–200	55	35								
	200–250	40	25								
(Molybdenum type): H41, H42, H43	150–200	45	30								
	200–250	35	20								
Special-purpose, low alloy: L2, L3, L6	150–200	60	40	**f**	15	8	4	24	12	83	20
Mold steel: P2, P3, P4, P5, P6P20, P21	100–150	75	50	**s**	45	360	605	90	95	75	95
	150–200	60	40		85						
High-speed steel: M1, M2, M6, M10, T1, T2, T6	200–250	45	30								
M3-1, M4, M7, M30, M33, M34, M36, M41, M42, M43, M44, M46, M47, T5, T8	225–275	35	20								
T15, M3-2	225–275	25	15								

See the footnote to Table 17 for instructions concerning the use of this table. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: coated carbide = 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. Feeds and Speeds for Drilling, Reaming, and Threading Stainless Steels

Material	Brinell Hardness	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)	Drilling HSS f = feed (0.001 in./rev), s = speed (ft/min) Opt.	Drilling HSS Avg.	Drilling Indexable Insert Coated Carbide Opt.	Drilling Indexable Insert Coated Carbide Avg.	Reaming HSS Opt.	Reaming HSS Avg.	Threading HSS Opt.	Threading HSS Avg.
Free-machining stainless steels (Ferritic): 430F, 430FSe	135–185	90	60	f 15 s 25	7 45	8 320	4 540	24 50	12 50	83 40	20 51
(Austenitic): 203EZ, 303, 303Se, 303MA, 303Pb, 303Cu, 303 Plus X	135–185	85	55								
	225–275	70	45	f 15 s 20	7 40	8 250	4 425	24 40	12 40	83 35	20 45
(Martensitic): 416, 416Se, 416 Plus X, 420F, 420FSe, 440F, 440FSe	135–185	90	60								
	185–240	70	45								
	275–325	40	25								
	375–425	20	10								
Stainless steels (Ferritic): 405, 409, 429, 430, 434	135–185	65	45	f 15 s 25	7 45	8 320	4 540	24 50	12 50	83 40	20 51
(Austenitic): 201, 202, 301, 302, 304, 304L, 305, 308, 321, 347, 348	135–185	55	35								
	225–275	50	30	f 15 s 20	7 40	8 250	4 425	24 40	12 40	83 35	20 45
(Austenitic): 302B, 309, 309S, 310, 310S, 314, 316	135–185	50	30								
(Martensitic): 403, 410, 420, 501	135–175	75	50								
	175–225	65	45								
	275–325	40	25								
	375–425	25	15								
(Martensitic): 414, 431, Greek Ascoloy	225–275	50	30								
	275–325	40	25								
	375–425	25	15								
(Martensitic): 440A, 440B, 440C	225–275	45	30								
	275–325	40	25								
	375–425	20	10								
(Precipitation hardening): 15–5PH, 17–4PH, 17–7PH, AF–71, 17–14CuMo, AFC–77, AM–350, AM–355, AM–362, Custom 455, HNM, PH13–8, PH14–8Mo, PH15–7Mo, Stainless W	150–200	50	30	f 15 s 20	7 40	8 250	4 425	24 40	12 40	83 35	20 45
	275–325	45	25								
	325–375	35	20								
	375–450	20	10								

See the footnote to Table 17 for instructions concerning the use of this table. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: coated carbide = 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 20. Feeds and Speeds for Drilling, Reaming, and Threading Ferrous Cast Metals

Material	Brinell Hardness	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)		Drilling HSS *Opt.*	Drilling HSS *Avg.*	Drilling Indexable Carbide Insert Uncoated *Opt.*	Drilling Indexable Carbide Insert Uncoated *Avg.*	Drilling Indexable Carbide Insert Coated *Opt.*	Drilling Indexable Carbide Insert Coated *Avg.*	Reaming HSS *Opt.*	Reaming HSS *Avg.*	Threading HSS *Opt.*	Threading HSS *Avg.*
					f = feed (0.001 in./rev), **s** = speed (ft/min)									
ASTM Class 20	120–150	100	65	**f**	16	8	11	6	11	6	26	13	83	20
ASTM Class 25	160–200	90	60	**s**	80	90	85	180	235	485	85	65	90	80
ASTM Class 30, 35, and 40	190–220	80	55											
ASTM Class 45 and 50	220–260	60	40	**f**	13	6	11	6	11	6	21	10	83	20
ASTM Class 55 and 60	250–320	30	20	**s**	50	50	70	150	195	405	50	30	55	45
ASTM Type 1, 1b, 5 (Ni resist)	100–215	50	30											
ASTM Type 2, 3, 6 (Ni resist)	120–175	40	25											
ASTM Type 2b, 4 (Ni resist)	150–250	30	20											
Malleable Iron														
(Ferritic): 32510, 35018	110–160	110	75	**f**	19	10	11	6	11	6	30	16	83	20
				s	80	100	85	180	270	555	95	80	100	85
(Pearlitic): 40010, 43010, 45006, 45008, 48005, 50005	160–200	80	55	**f**	14	7			11	6	22	11	83	20
	200–240	70	45	**s**	65	65			235	485	65	45	70	60
(Martensitic): 53004, 60003, 60004	200–255	55	35											
(Martensitic): 70002, 70003	220–260	50	30											
(Martensitic): 80002	240–280	45	30											
(Martensitic): 90001	250–320	25	15											
Nodular (Ductile) Iron														
(Ferritic): 60-40-18, 65-45-12	140–190	100	65	**f**	17	9	11	6	11	6	28	14	83	20
				s	70	80	85	180	235	485	80	60	80	70

Copyright 2004, Industrial Press, Inc., New York, NY

Table 20. ***(Continued)*** **Feeds and Speeds for Drilling, Reaming, and Threading Ferrous Cast Metals**

Material	Brinell Hardness	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)	Drilling HSS		Drilling Indexable Carbide Insert Uncoated		Drilling Indexable Carbide Insert Coated		Reaming HSS		Threading HSS	
				f = feed (0.001 in./rev), **s** = speed (ft/min)									
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
(Martensitic): 120-90-02	270–330	25	15										
	330–400	10	5										
(Ferritic-Pearlitic): 80-55-06	190–225	70	45	**f**	13	6	11	6	11	6	21	11	83	20
	225–260	50	30	**s**	60	60	70	150	195	405	55	40	60	55
(Pearlitic-Martensitic): 100-70-03	240–300	40	25										
Cast Steels													
(Low carbon): 1010, 1020	100–150	100	65	**f**	18	9					29	15	83	20
				s	35	70					75	85	65	85
(Medium carbon): 1030, 1040, 1050	125–175	90	60											
	175–225	70	45											
	225–300	55	35	**f**	15	7			8	4	24	12	83	20
				s	35	60			195†	475	65	70	55	70
(Low-carbon alloy): 1320, 2315, 2320, 4110, 4120, 4320, 8020, 8620	150–200	75	50											
	200–250	65	40											
	250–300	50	30											
(Medium-carbon alloy): 1330, 1340, 2325, 2330, 4125, 4130, 4140, 4330, 4340, 8030, 80B30, 8040, 8430, 8440, 8630, 8640, 9525, 9530, 9535	175–225	70	45	**f**					8	4				
	225–250	60	35	s					130†	315				
	250–300	45	30											
	300–350	30	20											
	350–400	20	10											

See the footnote to Table 17 for instructions concerning the use of this table. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated = 15; coated carbide = 11, † = 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. Feeds and Speeds for Drilling, Reaming, and Threading Light Metals

Material	Brinell Hardness	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)	Drilling HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)		Drilling Indexable Insert Uncoated Carbide **f** = feed (0.001 in./rev), **s** = speed (ft/min)		Reaming HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)		Threading HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)	
				Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
All wrought aluminum alloys, 6061-T651, 5000, 6000, 7000 series	CD	400	400								
	ST and A	350	350	**f** 31 **s** 390	16 580	11 3235	6 11370	52 610	26 615	83 635	20 565
All aluminum sand and permanent mold casting alloys	AC	500	500								
	ST and A	350	350								
Aluminum Die-Casting Alloys											
Alloys 308.0 and 319.0	—	—	—	**f** 23 **s** 110	11 145	11 945	6 3325	38 145	19 130	83 145	20 130
Alloys 360.0 and 380.0	—	—	—	**f** 27 **s** 90	14 125	11 855	6 3000	45 130	23 125	83 130	20 115
Alloys 390.0 and 392.0 {	AC	300	300								
	ST and A	70	70								
Alloys 413		—	—	**f** 24 **s** 65	12 85	11 555	6 1955	40 85	20 80	83 85	20 80
	ST and A	45	40								
All other aluminum die-casting alloys {	AC	125	100	**f** 27 **s** 90	14 125	11 855	6 3000	45 130	23 125	83 130	20 115
Magnesium Alloys											
All wrought magnesium alloys	A,CD,ST and A	500	500								
All cast magnesium alloys	A,AC, ST and A	450	450								

Abbreviations designate: A, annealed; AC, as cast; CD, cold drawn; and ST and A, solution treated and aged, respectively. See the footnote to Table 17 for instructions concerning the use of this table. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows; uncoated carbide = 15.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 22. Feed and Diameter Speed Adjustment Factors for HSS Twist Drills and Reamers

Cutting Speed, $V = V_{opt} \times F_f \times F_d$																
Ratio of Chosen Feed to *Optimum* Feed	Ratio of the two cutting speeds (*average*/*optimum*) given in the tables V_{avg}/V_{opt}							Tool Diameter								
								0.08 in	0.15 in	0.25 in	0.40 in	0.60 in	1.00 in	2.00 in	3.00 in	4.00 in
	1.00	1.25	1.50	2.00	2.50	3.00	4.00	(2 mm)	(4 mm)	(6 mm)	(10 mm)	(15 mm)	(25 mm)	(50 mm)	(75 mm)	(100 mm)
	Feed Factor, F_f							Diameter Factor, F_d								
1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.30	0.44	0.56	0.78	1.00	1.32	1.81	2.11	2.29
0.90	1.00	1.06	1.09	1.14	1.18	1.21	1.27	0.32	0.46	0.59	0.79	1.00	1.30	1.72	1.97	2.10
0.80	1.00	1.12	1.19	1.31	1.40	1.49	1.63	0.34	0.48	0.61	0.80	1.00	1.27	1.64	1.89	1.95
0.70	1.00	1.15	1.30	1.50	1.69	1.85	2.15	0.38	0.52	0.64	0.82	1.00	1.25	1.52	1.67	1.73
0.60	1.00	1.23	1.40	1.73	2.04	2.34	2.89	0.42	0.55	0.67	0.84	1.00	1.20	1.46	1.51	1.54
0.50	1.00	1.25	1.50	2.00	2.50	3.00	5.00	0.47	0.60	0.71	0.87	1.00	1.15	1.30	1.34	1.94
0.40	1.00	1.23	1.57	2.29	3.08	3.92	5.70	0.53	0.67	0.77	0.90	1.00	1.10	1.17	1.16	1.12
0.30	1.00	1.14	1.56	2.57	3.78	5.19	8.56	0.64	0.76	0.84	0.94	1.00	1.04	1.02	0.96	0.90
0.20	1.00	0.90	1.37	2.68	4.49	6.86	17.60	0.83	0.92	0.96	1.00	1.00	0.96	0.81	0.73	0.66
0.10	1.00	1.44	0.80	2.08	4.36	8.00	20.80	1.29	1.26	1.21	1.11	1.00	0.84	0.60	0.46	0.38

This table is specifically for use with the combined feed/speed data for HSS twist drills in Tables 17 through 23; use Tables 5a and 5b to adjust speed and tool life for indexable insert drilling with carbides. The combined feed/speed data for HSS twist drilling are based on a 0.60-inch diameter HSS drill with standard drill point geometry (2-flute with 118° tip angle). To adjust the given speeds for different feeds and drill diameters, use the two feed/speed pairs from the tables and calculate the ratio of desired (new) feed to *optimum* feed (largest of the two feeds from the speed table), and the ratio of the two cutting speeds V_{avg}/V_{opt}. Use the values of these ratios to find the feed factor F_f at the intersection of the feed ratio row and the speed ratio column in the left half of the table. The diameter factor F_d is found in the same row as the feed factor, in the right half of the table, under the column corresponding to the drill diameter. For diameters not given, interpolate between the nearest available sizes. The adjusted cutting speed can be calculated from $V = V_{opt} \times F_f \times F_d$, where V_{opt} is the smaller (*optimum*) of the two speeds from the speed table (from the left side of the column containing the two feed/speed pairs). Tool life using the selected feed and the adjusted speed should be approximately 45 minutes. Speed adjustment factors to modify tool life are found in Table 15e.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 23. Feeds and Speeds for Drilling and Reaming Copper Alloys

Group 1
Architectural bronze(C38500); Extra-high-leaded brass (C35600); Forging brass (C37700); Free-cutting phosphor bronze (B-2) (C54400); Free-cutting brass (C36000); Free-cutting Muntz metal (C37000); High-leaded brass (C33200, C34200); High-leaded brass tube (C35300); Leaded commercial bronze (C31400); Leaded naval brass (C48500); Medium-leaded brass (C34000)
Group 2
Aluminum brass, arsenical (C68700); Cartridge brass, 70% (C26000); High-silicon bronze, B (C65500); Admiralty brass (inhibited) (C44300, C44500); Jewelry bronze, 87.5% (C22600); Leaded Muntz metal (C36500, C36800); Leaded nickel silver (C79600); Low brass, 80% (C24000); Low-leaded brass (C33500); Low-silicon bronze, B (C65100); Manganese bronze, A (C67500); Muntz metal, 60% (C28000); Nickel silver, 55–18 (C77000); Red brass, 85% (C23000); Yellow brass (C26800)
Group 3
Aluminum bronze, D (C61400); Beryllium copper (C17000, C17200, C17500); Commercial bronze, 90% (C22000); Copper nickel, 10% (C70600); Copper nickel, 30% (C71500);Electrolytic tough-pitch copper (C11000); Gilding, 95% (C21000); Nickel silver, 65–10 (C74500); Nickel silver, 65–12 (C75700); Nickel silver, 65–15 (C75400); Nickel silver, 65–18 (C75200); Oxygen-free copper (C10200); Phosphor bronze, 1.25% (C50200); Phosphor bronze, 10% D (C52400); Phosphor bronze, 5% A (C51000); Phosphor bronze, 8% C (C52100); Phosphorus deoxidized copper (C12200)

Alloy Description and UNS Alloy Numbers	Material Condition	Drilling HSS Speed (fpm)	Reaming HSS Speed (fpm)	Drilling HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)			Drilling Indexable Insert Uncoated Carbide **f** = feed (0.001 in./rev), **s** = speed (ft/min)		Reaming HSS **f** = feed (0.001 in./rev), **s** = speed (ft/min)	
					Opt.	*Avg.*	*Opt.*	*Avg.*	*Opt.*	*Avg.*
Wrought Alloys										
Group 1	A	160	160	**f**	21	11	11	6	36	18
	CD	175	175	**s**	210	265	405	915	265	230
Group 2	A	120	110	**f**	24	12	11	6	40	20
	CD	140	120	**s**	100	130	205	455	130	120
Group 3	A	60	50	**f**	23	11	11	6	38	19
	CD	65	60	**s**	155	195	150	340	100	175

Abbreviations designate: A, annealed; CD, cold drawn. The two leftmost speed columns in this table contain traditional Handbook speeds for HSS steel tools. The text contains information concerning feeds to use in conjunction with these speeds.

HSS Drilling and Reaming: The combined feed/speed data for drilling and Table 22 are used to adjust drilling speeds for other feeds and drill diameters. Examples are given in the text. The given feeds and speeds for reaming are based on an 8-tooth, $^{25}/_{32}$-inch diameter, 30° lead angle reamer, and a 0.008-inch radial depth of cut. For other feeds, the correct speed can be obtained by interpolation using the given speeds if the desired feed lies in the recommended range (between the given values of *optimum* and *average* feed). The cutting speeds for reaming do not require adjustment for tool diameter as long as the radial depth of cut does not become too large. Speed adjustment factors to modify tool life are found in Table 15e.

Indexable Insert Drilling: The feed/speed data for indexable insert drilling are based on a tool with two cutting edges, an insert nose radius of $^{3}/_{64}$ inch, a 10-degree lead angle, and diameter *D* of 1 inch. Adjustments for feed and depth of cut are made using Table 5a (Turning Speed Adjustment Factors) using a depth of cut of D/2, or one-half the drill diameter. Expected tool life at the given feeds and speeds is 15 minutes for short hole drilling (i.e., where hole depth is about *2D* or less). Speed adjustment factors to increase tool life are found in Table 5b. The combined feed/speed data in this table are based on tool grades (identified in Table 16) as follows: uncoated carbide = 15.

Using the Feed and Speed Tables for Tapping and Threading.— The feed used in tapping and threading is always equal to the pitch of the screw thread being formed. The

Copyright 2004, Industrial Press, Inc., New York, NY

threading data contained in the tables for drilling, reaming, and threading (Tables 17 through 23) are primarily for tapping and thread chasing, and do not apply to thread cutting with single-point tools.

The threading data in Tables 17 through 23 give two sets of feed (pitch) and speed values, for 12 and 50 threads/inch, but these values can be used to obtain the cutting speed for any other thread pitches. If the desired pitch falls between the values given in the tables, i.e., between 0.020 inch (50 tpi) and 0.083 inch (12 tpi), the required cutting speed is obtained by interpolation between the given speeds. If the pitch is less than 0.020 inch (more than 50 tpi), use the *average* speed, i.e., the largest of the two given speeds. For pitches greater than 0.083 inch (fewer than 12 tpi), the *optimum* speed should be used. Tool life using the given feed/speed data is intended to be approximately 45 minutes, and should be about the same for threads between 12 and 50 threads per inch.

Example: Determine the cutting speed required for tapping 303 stainless steel with a ½–20 coated HSS tap.

The two feed/speed pairs for 303 stainless steel, in Table 19, are 83⁄35 (0.083 in./rev at 35 fpm) and 20⁄45 (0.020 in./rev at 45 fpm). The pitch of a ½–20 thread is 1⁄20 = 0.05 inch, so the required feed is 0.05 in./rev. Because 0.05 is between the two given feeds (Table 19), the cutting speed can be obtained by interpolation between the two given speeds as follows:

$$V = 35 + \frac{0.05 - 0.02}{0.083 - 0.02}(45 - 35) = 40 \text{ fpm}$$

The cutting speed for coarse-pitch taps must be lower than for fine-pitch taps with the same diameter. Usually, the difference in pitch becomes more pronounced as the diameter of the tap becomes larger and slight differences in the pitch of smaller-diameter taps have little significant effect on the cutting speed. Unlike all other cutting tools, the feed per revolution of a tap cannot be independently adjusted—it is always equal to the lead of the thread and is always greater for coarse pitches than for fine pitches. Furthermore, the thread form of a coarse-pitch thread is larger than that of a fine-pitch thread; therefore, it is necessary to remove more metal when cutting a coarse-pitch thread.

Taps with a long chamfer, such as starting or tapper taps, can cut faster in a short hole than short chamfer taps, such as plug taps. In deep holes, however, short chamfer or plug taps can run faster than long chamfer taps. Bottoming taps must be run more slowly than either starting or plug taps. The chamfer helps to start the tap in the hole. It also functions to involve more threads, or thread form cutting edges, on the tap in cutting the thread in the hole, thus reducing the cutting load on any one set of thread form cutting edges. In so doing, more chips and thinner chips are produced that are difficult to remove from deeper holes. Shortening the chamfer length causes fewer thread form cutting edges to cut, thereby producing fewer and thicker chips that can easily be disposed of. Only one or two sets of thread form cutting edges are cut on bottoming taps, causing these cutting edges to assume a heavy cutting load and produce very thick chips.

Spiral-pointed taps can operate at a faster cutting speed than taps with normal flutes. These taps are made with supplementary angular flutes on the end that push the chips ahead of the tap and prevent the tapped hole from becoming clogged with chips. They are used primarily to tap open or through holes although some are made with shorter supplementary flutes for tapping blind holes.

The tapping speed must be reduced as the percentage of full thread to be cut is increased. Experiments have shown that the torque required to cut a 100 per cent thread form is more than twice that required to cut a 50 per cent thread form. An increase in the percentage of full thread will also produce a greater volume of chips.

The tapping speed must be lowered as the length of the hole to be tapped is increased. More friction must be overcome in turning the tap and more chips accumulate in the hole.

Copyright 2004, Industrial Press, Inc., New York, NY

It will be more difficult to apply the cutting fluid at the cutting edges and to lubricate the tap to reduce friction. This problem becomes greater when the hole is being tapped in a horizontal position.

Cutting fluids have a very great effect on the cutting speed for tapping. Although other operating conditions when tapping frequently cannot be changed, a free selection of the cutting fluid usually can be made. When planning the tapping operation, the selection of a cutting fluid warrants a very careful consideration and perhaps an investigation.

Taper threaded taps, such as pipe taps, must be operated at a slower speed than straight thread taps with a comparable diameter. All the thread form cutting edges of a taper threaded tap that are engaged in the work cut and produce a chip, but only those cutting edges along the chamfer length cut on straight thread taps. Pipe taps often are required to cut the tapered thread from a straight hole, adding to the cutting burden.

The machine tool used for the tapping operation must be considered in selecting the tapping speed. Tapping machines and other machines that are able to feed the tap at a rate of advance equal to the lead of the tap, and that have provisions for quickly reversing the spindle, can be operated at high cutting speeds. On machines where the feed of the tap is controlled manually—such as on drill presses and turret lathes—the tapping speed must be reduced to allow the operator to maintain safe control of the operation.

There are other special considerations in selecting the tapping speed. Very accurate threads are usually tapped more slowly than threads with a commercial grade of accuracy. Thread forms that require deep threads for which a large amount of metal must be removed, producing a large volume of chips, require special techniques and slower cutting speeds. Acme, buttress, and square threads, therefore, are generally cut at lower speeds.

Cutting Speed for Broaching.— Broaching offers many advantages in manufacturing metal parts, including high production rates, excellent surface finishes, and close dimensional tolerances. These advantages are not derived from the use of high cutting speeds; they are derived from the large number of cutting teeth that can be applied consecutively in a given period of time, from their configuration and precise dimensions, and from the width or diameter of the surface that can be machined in a single stroke. Most broaching cutters are expensive in their initial cost and are expensive to sharpen. For these reasons, a long tool life is desirable, and to obtain a long tool life, relatively slow cutting speeds are used. In many instances, slower cutting speeds are used because of the limitations of the machine in accelerating and stopping heavy broaching cutters. At other times, the available power on the machine places a limit on the cutting speed that can be used; i.e., the cubic inches of metal removed per minute must be within the power capacity of the machine.

The cutting speeds for high-speed steel broaches range from 3 to 50 feet per minute, although faster speeds have been used. In general, the harder and more difficult to machine materials are cut at a slower cutting speed and those that are easier to machine are cut at a faster speed. Some typical recommendations for high-speed steel broaches are: AISI 1040, 10 to 30 fpm; AISI 1060, 10 to 25 fpm; AISI 4140, 10 to 25 fpm; AISI 41L40, 20 to 30 fpm; 201 austenitic stainless steel, 10 to 20 fpm; Class 20 gray cast iron, 20 to 30 fpm; Class 40 gray cast iron, 15 to 25 fpm; aluminum and magnesium alloys, 30 to 50 fpm; copper alloys, 20 to 30 fpm; commercially pure titanium, 20 to 25 fpm; alpha and beta titanium alloys, 5 fpm; and the superalloys, 3 to 10 fpm. Surface broaching operations on gray iron castings have been conducted at a cutting speed of 150 fpm, using indexable insert cemented carbide broaching cutters. In selecting the speed for broaching, the cardinal principle of the performance of all metal cutting tools should be kept in mind; i.e., increasing the cutting speed may result in a proportionately larger reduction in tool life, and reducing the cutting speed may result in a proportionately larger increase in the tool life. When broaching most materials, a suitable cutting fluid should be used to obtain a good surface finish and a better tool life. Gray cast iron can be broached without using a cutting fluid although some shops prefer to use a soluble oil.

Copyright 2004, Industrial Press, Inc., New York, NY

Spade Drills

Spade drills are used to produce holes ranging in size from about 1 inch to 6 inches diameter, and even larger. Very deep holes can be drilled and blades are available for core drilling, counterboring, and for bottoming to a flat or contoured shape. There are two principal parts to a spade drill, the blade and the holder. The holder has a slot into which the blade fits; a wide slot at the back of the blade engages with a tongue in the holder slot to locate the blade accurately. A retaining screw holds the two parts together. The blade is usually made from high-speed steel, although cast nonferrous metal and cemented carbide-tipped blades are also available. Spade drill holders are classified by a letter symbol designating the range of blade sizes that can be held and by their length. Standard stub, short, long, and extra long holders are available; for very deep holes, special holders having wear strips to support and guide the drill are often used. Long, extra long, and many short length holders have coolant holes to direct cutting fluid, under pressure, to the cutting edges. In addition to its function in cooling and lubricating the tool, the cutting fluid also flushes the chips out of the hole. The shank of the holder may be straight or tapered; special automotive shanks are also used. A holder and different shank designs are shown in Fig. 1; Figs. 2a through Fig. 2f show some typical blades.



Fig. 1. Spade Drill Blade Holder

Spade Drill Geometry.— Metal separation from the work is accomplished in a like manner by both twist drills and spade drills, and the same mechanisms are involved for each. The two cutting lips separate the metal by a shearing action that is identical to that of chip formation by a single-point cutting tool. At the chisel edge, a much more complex condition exists. Here the metal is extruded sideways and at the same time is sheared by the rotation of the blunt wedge-formed chisel edge. This combination accounts for the very high thrust force required to penetrate the work. The chisel edge of a twist drill is slightly rounded, but on spade drills, it is a straight edge. Thus, it is likely that it is more difficult for the extruded metal to escape from the region of the chisel edge with spade drills. However, the chisel edge is shorter in length than on twist drills and the thrust for spade drilling is less.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Spade Drill Blades


Fig. 2a. Standard blade


Fig. 2b. Standard blade with corner chamfer


Fig. 2c. Core drilling blade


Fig. 2d. Center cutting facing or bottoming blade


Fig. 2e. Standard blade with split point or crankshaft point


Fig. 2f. Center cutting radius blade

Basic spade drill geometry is shown in Fig. 3. Normally, the point angle of a standard tool is 130 degrees and the lip clearance angle is 18 degrees, resulting in a chisel edge angle of 108 degrees. The web thickness is usually about $\frac{1}{4}$ to $\frac{5}{16}$ as thick as the blade thickness. Usually, the cutting edge angle is selected to provide this web thickness and to provide the necessary strength along the entire length of the cutting lip. A further reduction of the chisel edge length is sometimes desirable to reduce the thrust force in drilling. This reduction can be accomplished by grinding a secondary rake surface at the center or by grinding a split point, or crankshaft point, on the point of the drill.

The larger point angle of a standard spade drill—130 degrees as compared with 118 degrees on a twist drill—causes the chips to flow more toward the periphery of the drill, thereby allowing the chips to enter the flutes of the holder more readily. The rake angle facilitates the formation of the chip along the cutting lips. For drilling materials of average hardness, the rake angle should be 10 to 12 degrees; for hard or tough steels, it should be 5 to 7 degrees; and for soft and ductile materials, it can be increased to 15 to 20 degrees. The rake surface may be flat or rounded, and the latter design is called radial rake. Radial rake is usually ground so that the rake angle is maximum at the periphery and decreases uniformly toward the center to provide greater cutting edge strength at the center. A flat rake surface is recommended for drilling hard and tough materials in order to reduce the tendency to chipping and to reduce heat damage.

A most important feature of the cutting edge is the chip splitters, which are also called chip breaker grooves. Functionally, these grooves are chip dividers; instead of forming a single wide chip along the entire length of the cutting edge, these grooves cause formation of several chips that can be readily disposed of through the flutes of the holder. Chip splitters must be carefully ground to prevent the chips from packing in the grooves, which greatly reduces their effectiveness. Splitters should be ground perpendicular to the cutting lip and parallel to the surface formed by the clearance angle. The grooves on the two cut-

Copyright 2004, Industrial Press, Inc., New York, NY

ting lips must not overlap when measured radially along the cutting lip. Fig. 4 and the accompanying table show the groove form and dimensions.



Fig. 3. Spade Drill Blade

On spade drills, the front lip clearance angle provides the relief. It may be ground on a drill grinding machine but usually it is ground flat. The normal front lip clearance angle is 8 degrees; in some instances, a secondary relief angle of about 14 degrees is ground below the primary clearance. The wedge angle on the blade is optional. It is generally ground on thicker blades having a larger diameter to prevent heel dragging below the cutting lip and to reduce the chisel edge length. The outside-diameter land is circular, serving to support and guide the blade in the hole. Usually it is ground to have a back taper of 0.001 to 0.002 inch per inch per side. The width of the land is approximately 20 to 25 per cent of the blade thickness. Normally, the outside-diameter clearance angle behind the land is 7 to 10 degrees. On many spade drill blades, the outside-diameter clearance surface is stepped about 0.030 inch below the land.



Blade dia.	A (Max.)
1.00 – 2.31	0.050
2.32 – 3.00	0.070
3.01 – 4.00	0.090
4.00 – UP	0.120

Enlarged view and dimensions of chip splitter

Fig. 4. Spade Drill Chip Splitter Dimensions

Spade Drilling.— Spade drills are used on drilling machines and other machine tools where the cutting tool rotates; they are also used on turning machines where the work

Copyright 2004, Industrial Press, Inc., New York, NY

rotates and the tool is stationary. Although there are some slight operational differences, the methods of using spade drills are basically the same. An adequate supply of cutting fluid must be used, which serves to cool and lubricate the cutting edges; to cool the chips, thus making them brittle and more easily broken; and to flush chips out of the hole. Flood cooling from outside the hole can be used for drilling relatively shallow holes, of about one to two and one-half times the diameter in depth. For deeper holes, the cutting fluid should be injected through the holes in the drill. When drilling very deep holes, it is often helpful to blow compressed air through the drill in addition to the cutting fluid to facilitate ejection of the chips. Air at full shop pressure is throttled down to a pressure that provides the most efficient ejection. The cutting fluids used are light and medium cutting oils, water-soluble oils, and synthetics, and the type selected depends on the work material.

Starting a spade drill in the workpiece needs special attention. The straight chisel edge on the spade drill has a tendency to wander as it starts to enter the work, especially if the feed is too light. This wander can result in a mispositioned hole and possible breakage of the drill point. The best method of starting the hole is to use a stub or short-length spade drill holder and a blade of full size that should penetrate at least ⅛ inch at full diameter. The holder is then changed for a longer one as required to complete the hole to depth. Difficulties can be encountered if spotting with a center drill or starting drill is employed because the angles on these drills do not match the 130-degree point angle of the spade drill. Longer spade drills can be started without this starting procedure if the drill is guided by a jig bushing and if the holder is provided with wear strips.

Chip formation warrants the most careful attention as success in spade drilling is dependent on producing short, well-broken chips that can be easily ejected from the hole. Straight, stringy chips or chips that are wound like a clock spring cannot be ejected properly; they tend to pack around the blade, which may result in blade failure. The chip splitters must be functioning to produce a series of narrow chips along each cutting edge. Each chip must be broken, and for drilling ductile materials they should be formed into a “C” or “figure 9” shape. Such chips will readily enter the flutes on the holder and flow out of the hole.

Proper chip formation is dependent on the work material, the spade drill geometry, and the cutting conditions. Brittle materials such as gray cast iron seldom pose a problem because they produce a discontinuous chip, but austenitic stainless steels and very soft and ductile materials require much attention to obtain satisfactory chip control. Thinning the web or grinding a split point on the blade will sometimes be helpful in obtaining better chip control, as these modifications allow use of a heavier feed. Reducing the rake angle to obtain a tighter curl on the chip and grinding a corner chamfer on the tool will sometimes help to produce more manageable chips.

In most instances, it is not necessary to experiment with the spade drill blade geometry to obtain satisfactory chip control. Control usually can be accomplished by adjusting the cutting conditions; i.e., the cutting speed and the feed rate.

Normally, the cutting speed for spade drilling should be 10 to 15 per cent lower than that for an equivalent twist drill, although the same speed can be used if a lower tool life is acceptable. The recommended cutting speeds for twist drills on Tables 17 through 23, starting on page 1061, can be used as a starting point; however, they should be decreased by the percentage just given. It is essential to use a heavy feed rate when spade drilling to produce a thick chip. and to force the chisel edge into the work. In ductile materials, a light feed will produce a thin chip that is very difficult to break. The thick chip on the other hand, which often contains many rupture planes, will curl and break readily. Table 1 gives suggested feed rates for different spade drill sizes and materials. These rates should be used as a starting point and some adjustments may be necessary as experience is gained.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Feed Rates for Spade Drilling

Material	Hardness, Bhn	Feed—Inches per Revolution					
		Spade Drill Diameter—Inches					
		1–1¼	1¼-2	2–3	3–4	4–5	5–8
Free Machining Steel	100–240	0.014	0.016	0.018	0.022	0.025	0.030
	240–325	0.010	0.014	0.016	0.020	0.022	0.025
Plain Carbon Steels	100–225	0.012	0.015	0.018	0.022	0.025	0.030
	225–275	0.010	0.013	0.015	0.018	0.020	0.025
	275–325	0.008	0.010	0.013	0.015	0.018	0.020
Free Machining Alloy Steels	150–250	0.014	0.016	0.018	0.022	0.025	0.030
	250–325	0.012	0.014	0.016	0.018	0.020	0.025
Alloy Steels	325–375	0.010	0.010	0.014	0.016	0.018	0.020
	125–180	0.012	0.015	0.018	0.022	0.025	0.030
	180–225	0.010	0.012	0.016	0.018	0.022	0.025
	225–325	0.009	0.010	0.013	0.015	0.018	0.020
	325–400	0.006	0.008	0.010	0.012	0.014	0.016
Tool Steels							
Water Hardening	150–250	0.012	0.014	0.016	0.018	0.020	0.022
Shock Resisting	175–225	0.012	0.014	0.015	0.016	0.017	0.018
Cold Work	200–250	0.007	0.008	0.009	0.010	0.011	0.012
Hot Work	150–250	0.012	0.013	0.015	0.016	0.018	0.020
Mold	150–200	0.010	0.012	0.014	0.016	0.018	0.018
Special-Purpose	150–225	0.010	0.012	0.014	0.016	0.016	0.018
High-Speed	200–240	0.010	0.012	0.013	0.015	0.017	0.018
	110–160	0.020	0.022	0.026	0.028	0.030	0.034
Gray Cast Iron	160–190	0.015	0.018	0.020	0.024	0.026	0.028
	190–240	0.012	0.014	0.016	0.018	0.020	0.022
	240–320	0.010	0.012	0.016	0.018	0.018	0.018
Ductile or Nodular Iron	140–190	0.014	0.016	0.018	0.020	0.022	0.024
	190–250	0.012	0.014	0.016	0.018	0.018	0.020
	250–300	0.010	0.012	0.016	0.018	0.018	0.018
Malleable Iron							
Ferritic	110–160	0.014	0.016	0.018	0.020	0.022	0.024
Pearlitic	160–220	0.012	0.014	0.016	0.018	0.020	0.020
	220–280	0.010	0.012	0.014	0.016	0.018	0.018
Free Machining Stainless Steel							
Ferritic	…	0.016	0.018	0.020	0.024	0.026	0.028
Austenitic	…	0.016	0.018	0.020	0.022	0.024	0.026
Martensitic	…	0.012	0.014	0.016	0.016	0.018	0.020
Stainless Steel							
Ferritic	…	0.012	0.014	0.018	0.020	0.020	0.022
Austenitic	…	0.012	0.014	0.016	0.018	0.020	0.020
Martensitic	…	0.010	0.012	0.012	0.014	0.016	0.018
Aluminum Alloys	…	0.020	0.022	0.024	0.028	0.030	0.040
Copper Alloys	(Soft)	0.016	0.018	0.020	0.026	0.028	0.030
	(Hard)	0.010	0.012	0.014	0.016	0.018	0.018
Titanium Alloys	…	0.008	0.010	0.012	0.014	0.014	0.016
High-Temperature Alloys	…	0.008	0.010	0.012	0.012	0.014	0.014

Copyright 2004, Industrial Press, Inc., New York, NY

Power Consumption and Thrust for Spade Drilling.— In each individual setup, there are factors and conditions influencing power consumption that cannot be accounted for in a simple equation; however, those given below will enable the user to estimate power consumption and thrust accurately enough for most practical purposes. They are based on experimentally derived values of unit horsepower, as given in Table 2. As a word of caution, these values are for sharp tools. In spade drilling, it is reasonable to estimate that a dull tool will increase the power consumption and the thrust by 25 to 50 per cent. The unit horsepower values in the table are for the power consumed at the cutting edge, to which must be added the power required to drive the machine tool itself, in order to obtain the horsepower required by the machine tool motor. An allowance for power to drive the machine is provided by dividing the horsepower at the cutter by a mechanical efficiency factor, e_m. This factor can be estimated to be 0.90 for a direct spindle drive with a belt, 0.75 for a back gear drive, and 0.70 to 0.80 for geared head drives. Thus, for spade drilling the formulas are

$$\text{hp}_c = \text{uhp}\left(\frac{\pi D^2}{4}\right)fN$$

$$B_s = 148{,}500\ \text{uhp}\,fD$$

$$\text{hp}_m = \frac{hp_c}{e_m}$$

$$f = \frac{f_m}{N}$$

where hp_c = horsepower at the cutter hp_m = horsepower at the motor
B_s = thrust for spade drilling in pounds
uhp = unit horsepower
D = drill diameter in inches
f = feed in inches per revolution
f_m = feed in inches per minute
N = spindle speed in revolutions per minute
e_m = mechanical efficiency factor

Table 2. Unit Horsepower for Spade Drilling

Material	Hardness	uhp	Material	Hardness	uhp
Plain Carbon and Alloy Steel	85–200 Bhn	0.79	Titanium Alloys	250–375 Bhn	0.72
	200–275	0.94	High-Temp Alloys	200–360 Bhn	1.44
	275–375	1.00	Aluminum Alloys	…	0.22
	375–425	1.15	Magnesium Alloys	…	0.16
Cast Irons	45–52 Rc	1.44	Copper Alloys	20–80 Rb	0.43
	110–200 Bhn	0.5		80–100 Rb	0.72
	200–300	1.08			
Stainless Steels	135–275 Bhn	0.94			
	30–45 Rc	1.08			

Example: Estimate the horsepower and thrust required to drive a 2-inch diameter spade drill in AISI 1045 steel that is quenched and tempered to a hardness of 275 Bhn. From Table 17 on page 1061, the cutting speed, V, for drilling this material with a twist drill is 50 feet per minute. This value is reduced by 10 per cent for spade drilling and the speed selected is thus $0.9 \times 50 = 45$ feet per minute. The feed rate (from Table 1, page 1079) is 0.015 in/rev. and the unit horsepower from Table 2 above is 0.94. The machine efficiency factor is estimated to be 0.80 and it will be assumed that a 50 per cent increase in the unit horsepower must be allowed for dull tools.

Copyright 2004, Industrial Press, Inc., New York, NY

Step 1. Calculate the spindle speed from the following formula:

$$N = \frac{12V}{\pi D}$$

where: N = spindle speed in revolutions per minute

V = cutting speed in feet per minute

D = drill diameter in inches

Thus, $N = \frac{12 \times 45}{\pi \times 2} = 86$ revolutions per minute

Step 2. Calculate the horsepower at the cutter:

$$\text{hp}_c = \text{uhp}\left(\frac{\pi D^2}{4}\right)fN = 0.94\left(\frac{\pi \times 2^2}{4}\right)0.015 \times 86 = 3.8$$

Step 3. Calculate the horsepower at the motor and provide for a 50 per cent power increase for the dull tool:

$$\text{hp}_m = \frac{\text{hp}_c}{e_m} = \frac{3.8}{0.80} = 4.75 \text{ horsepower}$$

$$\text{hp}_m \text{ (with dull tool)} = 1.5 \times 4.75 = 7.125 \text{ horsepower}$$

Step 4. Estimate the spade drill thrust:

$B_s = 148{,}500 \times \text{uhp} \times fD = 148{,}500 \times 0.94 \times 0.015 \times 2 = 4188$ lb (for sharp tool)

$B_s = 1.5 \times 4188 = 6282$ lb (for dull tool)

Trepanning.— Cutting a groove in the form of a circle or boring or cutting a hole by removing the center or core in one piece is called trepanning. Shallow trepanning, also called face grooving, can be performed on a lathe using a single-point tool that is similar to a grooving tool but has a curved blade. Generally, the minimum outside diameter that can be cut by this method is about 3 inches and the maximum groove depth is about 2 inches. Trepanning is probably the most economical method of producing deep holes that are 2 inches, and larger, in diameter. Fast production rates can be achieved. The tool consists of a hollow bar, or stem, and a hollow cylindrical head to which a carbide or high-speed steel, single-point cutting tool is attached. Usually, only one cutting tool is used although for some applications a multiple cutter head must be used; e.g., heads used to start the hole have multiple tools. In operation, the cutting tool produces a circular groove and a residue core that enters the hollow stem after passing through the head. On outside-diameter exhaust trepanning tools, the cutting fluid is applied through the stem and the chips are flushed around the outside of the tool; inside-diameter exhaust tools flush the chips out through the stem with the cutting fluid applied from the outside. For starting the cut, a tool that cuts a starting groove in the work must be used, or the trepanning tool must be guided by a bushing. For holes less than about five diameters deep, a machine that rotates the trepanning tool can be used. Often, an ordinary drill press is satisfactory; deeper holes should be machined on a lathe with the work rotating. A hole diameter tolerance of ±0.010 inch can be obtained easily by trepanning and a tolerance of ±0.001 inch has sometimes been held. Hole runout can be held to ±0.003 inch per foot and, at times, to ±0.001 inch per foot. On heat-treated metal, a surface finish of 125 to 150 μm AA can be obtained and on annealed metals 100 to 250 μm AA is common.

Copyright 2004, Industrial Press, Inc., New York, NY

ESTIMATING SPEEDS AND MACHINING POWER

Estimating Planer Cutting Speeds.— Whereas most planers of modern design have a means of indicating the speed at which the table is traveling, or cutting, many older planers do not. Thus, the following formulas are useful for planers that do not have a means of indicating the table or cutting speed. It is not practicable to provide a formula for calculating the exact cutting speed at which a planer is operating because the time to stop and start the table when reversing varies greatly. The formulas below will, however, provide a reasonable estimate.

$$V_c \cong S_c L$$

$$S_c \cong \frac{V_c}{L}$$

where V_c = cutting speed; fpm or m/min
S_c = number of cutting strokes per minute of planer table
L = length of table cutting stroke; ft or m

Cutting Speed for Planing and Shaping.— The traditional HSS cutting tool speeds in Tables 1 through 4b and Tables 6 through 9 can be used for planing and shaping. The feed and depth of cut factors in Tables 5c should also be used, as explained previously. Very often, other factors relating to the machine or the setup will require a reduction in the cutting speed used on a specific job.

Cutting Time for Turning, Boring, and Facing.— The time required to turn a length of metal can be determined by the following formula in which T = time in minutes, L = length of cut in inches, f = feed in inches per revolution, and N = lathe spindle speed in revolutions per minute.

$$T = \frac{L}{fN}$$

When making job estimates, the time required to load and to unload the workpiece on the machine, and the machine handling time, must be added to the cutting time for each length cut to obtain the floor-to-floor time.

Planing Time.— The approximate time required to plane a surface can be determined from the following formula in which T = time in minutes, L = length of stroke in feet, V_c = cutting speed in feet per minute, V_r = return speed in feet per minute; W = width of surface to be planed in inches, F = feed in inches, and 0.025 = approximate reversal time factor per stroke in minutes for most planers:

$$T = \frac{W}{F}\left[L \times \left(\frac{1}{V_c} + \frac{1}{V_r}\right) + 0.025\right]$$

Speeds for Metal-Cutting Saws.— The following speeds and feeds for solid-tooth, high-speed-steel, circular, metal-cutting saws are recommended by Saws International, Inc. (sfpm = surface feet per minute = 3.142 × blade diameter in inches × rpm of saw shaft ÷ 12).

Speeds for Turning Unusual Materials.— *Slate*, on account of its peculiarly stratified formation, is rather difficult to turn, but if handled carefully, can be machined in an ordinary lathe. The cutting speed should be about the same as for cast iron. A sheet of fiber or pressed paper should be interposed between the chuck or steadyrest jaws and the slate, to protect the latter. Slate rolls must not be centered and run on the tailstock. A satisfactory method of supporting a slate roll having journals at the ends is to bore a piece of lignum vitae to receive the turned end of the roll, and center it for the tailstock spindle.

Rubber can be turned at a peripheral speed of 200 feet per minute, although it is much easier to grind it with an abrasive wheel that is porous and soft. For cutting a rubber roll in

Copyright 2004, Industrial Press, Inc., New York, NY

Speeds, Feeds, and Tooth Angles for Sawing Various Materials



α = Cutting angle
β = Relief angle

Materials	Front Rake Angle α (deg)	Back Rake Angle β (deg)	Stock Diameters (inches)			
			¼–¾	¾–1½	1½–2½	2½–3½
Aluminum	24	12	6500 sfpm 100 in/min	6200 sfpm 85 in/min	6000 sfpm 80 in/min	5000 sfpm 75 in/min
Light Alloys with Cu, Mg, and Zn	22	10	3600 sfpm 70 in/min	3300 sfpm 65 in/min	3000 sfpm 63 in/min	2600 sfpm 60 in/min
Light Alloys with High Si	20	8	650 sfpm 16 in/min	600 sfpm 16 in/min	550 sfpm 14 in/min	550 sfpm 12 in/min
Copper	20	10	1300 sfpm 24 in/min	1150 sfpm 24 in/min	1000 sfpm 22 in/min	800 sfpm 22 in/min
Bronze	15	8	1300 sfpm 24 in/min	1150 sfpm 24 in/min	1000 sfpm 22 in/min	800 sfpm 20 in/min
Hard Bronze	10	8	400 sfpm 6.3 in/min	360 sfpm 6 in/min	325 sfpm 5.5 in/min	300 sfpm 5.1 in/min
Cu-Zn Brass	16	8	2000 sfpm 43 in/min	2000 sfpm 43 in/min	1800 sfpm 39 in/min	1800 sfpm 35 in/min
Gray Cast Iron	12	8	82 sfpm 4 in/min	75 sfpm 4 in/min	72 sfpm 3.5 in/min	66 sfpm 3 in/min
Carbon Steel	20	8	160 sfpm 6.3 in/min	150 sfpm 5.9 in/min	150 sfpm 5.5 in/min	130 sfpm 5.1 in/min
Medium Hard Steel	18	8	100 sfpm 5.1 in/min	100 sfpm 4.7 in/min	80 sfpm 4.3 in/min	80 sfpm 4.3 in/min
Hard Steel	15	8	66 sfpm 4.3 in/min	66 sfpm 4.3 in/min	60 sfpm 4 in/min	57 sfpm 3.5 in/min
Stainless Steel	15	8	66 sfpm 2 in/min	63 sfpm 1.75 in/min	60 sfpm 1.75 in/min	57 sfpm 1.5 in/min

two, the ordinary parting tool should not be used, but a tool shaped like a knife; such a tool severs the rubber without removing any material.

Gutta percha can be turned as easily as wood, but the tools must be sharp and a good soap-and-water lubricant used.

Copper can be turned easily at 200 feet per minute.

Limestone such as is used in the construction of pillars for balconies, etc., can be turned at 150 feet per minute, and the formation of ornamental contours is quite easy. *Marble* is a treacherous material to turn. It should be cut with a tool such as would be used for brass, but

Copyright 2004, Industrial Press, Inc., New York, NY

at a speed suitable for cast iron. It must be handled very carefully to prevent flaws in the surface.

The foregoing speeds are for high-speed steel tools. Tools tipped with tungsten carbide are adapted for cutting various non-metallic products which cannot be machined readily with steel tools, such as slate, marble, synthetic plastic materials, etc. In drilling slate and marble, use flat drills; and for plastic materials, tungsten-carbide-tipped twist drills. Cutting speeds ranging from 75 to 150 feet per minute have been used for drilling slate (without coolant) and a feed of 0.025 inch per revolution for drills $\frac{3}{4}$ and 1 inch in diameter.

Estimating Machining Power.— Knowledge of the power required to perform machining operations is useful when planning new machining operations, for optimizing existing machining operations, and to develop specifications for new machine tools that are to be acquired. The available power on any machine tool places a limit on the size of the cut that it can take. When much metal must be removed from the workpiece it is advisable to estimate the cutting conditions that will utilize the maximum power on the machine. Many machining operations require only light cuts to be taken for which the machine obviously has ample power; in this event, estimating the power required is a wasteful effort. Conditions in different shops may vary and machine tools are not all designed alike, so some variations between the estimated results and those obtained on the job are to be expected. However, by using the methods provided in this section a reasonable estimate of the power required can be made, which will suffice in most practical situations.

The measure of power in customary inch units is the horsepower; in SI metric units it is the kilowatt, which is used for both mechanical and electrical power. The power required to cut a material depends upon the rate at which the material is being cut and upon an experimentally determined power constant, K_p, which is also called the unit horsepower, unit power, or specific power consumption. The power constant is equal to the horsepower required to cut a material at a rate of one cubic inch per minute; in SI metric units the power constant is equal to the power in kilowatts required to cut a material at a rate of one cubic centimeter per second, or 1000 cubic millimeters per second ($1 \text{ cm}^3 = 1000 \text{ mm}^3$). Different values of the power constant are required for inch and for metric units, which are related as follows: to obtain the SI metric power constant, multiply the inch power constant by 2.73; to obtain the inch power constant, divide the SI metric power constant by 2.73. Values of the power constant in Tables 3a, and 3b can be used for all machining operations except drilling and grinding. Values given are for sharp tools.

Table 3a. Power Constants, K_p, Using Sharp Cutting Tools

Material	Brinell Hardness	K_p Inch Units	K_p Metric Units	Material	Brinell Hardness	K_p Inch Units	K_p Metric Units
Ferrous Cast Metals							
	100–120	0.28	0.76	Malleable Iron			
	120–140	0.35	0.96	Ferritic	150–175	0.42	1.15
	140–160	0.38	1.04				
Gray Cast Iron	160–180	0.52	1.42		175–200	0.57	1.56
	180–200	0.60	1.64	Pearlitic	200–250	0.82	2.24
	200–220	0.71	1.94		250–300	1.18	3.22
	220–240	0.91	2.48				
					150–175	0.62	1.69
	150–175	0.30	0.82	Cast Steel	175–200	0.78	2.13
Alloy Cast Iron	175–200	0.63	1.72		200–250	0.86	2.35
	200–250	0.92	2.51	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3a. ***(Continued)*** **Power Constants, K_p, Using Sharp Cutting Tools**

Material	Brinell Hardness	K_p Inch Units	K_p Metric Units	Material	Brinell Hardness	K_p Inch Units	K_p Metric Units
High-Temperature Alloys, Tool Steel, Stainless Steel, and Nonferrous Metals							
High-Temperature Alloys					150-175	0.60	1.64
A286	165	0.82	2.24	Stainless Steel {	175-200	0.72	1.97
A286	285	0.93	2.54		200-250	0.88	2.40
Chromoloy	200	0.78	3.22	Zinc Die Cast Alloys	…	0.25	0.68
Chromoloy	310	1.18	3.00	Copper (pure)	…	0.91	2.48
Inco 700	330	1.12	3.06	Brass			
Inco 702	230	1.10	3.00	Hard	…	0.83	2.27
Hastelloy-B	230	1.10	3.00	Medium	…	0.50	1.36
M-252	230	1.10	3.00	Soft	…	0.25	0.68
M-252	310	1.20	3.28	Leaded	…	0.30	0.82
Ti-150A	340	0.65	1.77				
U-500	375	1.10	3.00	Bronze			
				Hard	…	0.91	2.48
Monel Metal	…	1.00	2.73	Medium	…	0.50	1.36
	175-200	0.75	2.05	Aluminum			
	200-250	0.88	2.40	Cast	…	0.25	0.68
Tool Steel {	250-300	0.98	2.68	Rolled (hard)	…	0.33	0.90
	300-350	1.20	3.28				
	350-400	1.30	3.55	Magnesium Alloys	…	0.10	0.27

The value of the power constant is essentially unaffected by the cutting speed, the depth of cut, and the cutting tool material. Factors that do affect the value of the power constant, and thereby the power required to cut a material, include the hardness and microstructure of the work material, the feed rate, the rake angle of the cutting tool, and whether the cutting edge of the tool is sharp or dull. Values are given in the power constant tables for different material hardness levels, whenever this information is available. Feed factors for the power constant are given in Table 4. All metal cutting tools wear but a worn cutting edge requires more power to cut than a sharp cutting edge.

Factors to provide for tool wear are given in Table 5. In this table, the extra-heavy-duty category for milling and turning occurs only on operations where the tool is allowed to wear more than a normal amount before it is replaced, such as roll turning. The effect of the rake angle usually can be disregarded. The rake angle for which most of the data in the power constant tables are given is positive 14 degrees. Only when the deviation from this angle is large is it necessary to make an adjustment. Using a rake angle that is more positive reduces the power required approximately 1 per cent per degree; using a rake angle that is more negative increases the power required; again approximately 1 per cent per degree.

Many indexable insert cutting tools are formed with an integral chip breaker or other cutting edge modifications, which have the effect of reducing the power required to cut a material. The extent of this effect cannot be predicted without a test of each design. Cutting fluids will also usually reduce the power required, when operating in the lower range of cutting speeds. Again, the extent of this effect cannot be predicted because each cutting fluid exhibits its own characteristics.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. Power Constants, K_p, Using Sharp Cutting Tools

Material	Brinell Hardness	K_p Inch Units	K_p Metric Units	Material	Brinell Hardness	K_p Inch Units	K_p SI Metric Units
Wrought Steels							
Plain Carbon Steels							
All Plain Carbon Steels	80–100	0.63	1.72	All Plain Carbon Steels	220–240	0.89	2.43
	100–120	0.66	1.80		240–260	0.92	2.51
	120–140	0.69	1.88		260–280	0.95	2.59
	140–160	0.74	2.02		280–300	1.00	2.73
	160–180	0.78	2.13		300–320	1.03	2.81
	180–200	0.82	2.24		320–340	1.06	2.89
	200–220	0.85	2.32		340–360	1.14	3.11
Free Machining Steels							
AISI 1108, 1109, 1110, 1115, 1116, 1117, 1118, 1119, 1120, 1125, 1126, 1132	100–120	0.41	1.12	AISI 1137, 1138, 1139, 1140, 1141, 1144, 1145, 1146, 1148, 1151	180–200	0.51	1.39
	120–140	0.42	1.15		200–220	0.55	1.50
	140–160	0.44	1.20		220–240	0.57	1.56
	160–180	0.48	1.31		240–260	0.62	1.69
	180–200	0.50	1.36		…	…	…
Alloy Steels							
AISI 4023, 4024, 4027, 4028, 4032, 4037, 4042, 4047, 4137, 4140, 4142, 4145, 4147, 4150, 4340, 4640, 4815, 4817, 4820, 5130, 5132, 5135, 5140, 5145, 5150, 6118, 6150, 8637, 8640, 8642, 8645, 8650, 8740	140–160	0.62	1.69	AISI 4130, 4320, 4615, 4620, 4626, 5120, 8615, 8617, 8620, 8622, 8625, 8630, 8720	140–160	0.56	1.53
	160–180	0.65	1.77		160–180	0.59	1.61
	180–200	0.69	1.88		180–200	0.62	1.69
	200–220	0.72	1.97		200–220	0.65	1.77
	220–240	0.76	2.07		220–240	0.70	1.91
	240–260	0.80	2.18		240–260	0.74	2.02
	260–280	0.84	2.29		260–280	0.77	2.10
	280–300	0.87	2.38		280–300	0.80	2.18
	300–320	0.91	2.48		300–320	0.83	2.27
	320–340	0.96	2.62		320–340	0.89	2.43
	340–360	1.00	2.73		…	…	…
AISI 1330, 1335, 1340, E52100	160–180	0.79	2.16		…	…	…
	180–200	0.83	2.27		…	…	…
	200–220	0.87	2.38		…	…	…

The machine tool transmits the power from the driving motor to the workpiece, where it is used to cut the material. The effectiveness of this transmission is measured by the machine tool efficiency factor, E. Average values of this factor are given in Table 6. Formulas for calculating the metal removal rate, Q, for different machining operations are given in Table 7. These formulas are used together with others given below. The following formulas can be used with either customary inch or with SI metric units.

$$P_c = K_p C Q W \tag{1}$$

$$P_m = \frac{P_c}{E} = \frac{K_p C Q W}{E} \tag{2}$$

where P_c = power at the cutting tool; hp, or kW

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Feed Factors, *C*, for Power Constants

Inch Units				SI Metric Units			
Feed in.[a]	*C*	Feed in.[a]	*C*	Feed mm[b]	*C*	Feed mm[b]	*C*
0.001	1.60	0.014	0.97	0.02	1.70	0.35	0.97
0.002	1.40	0.015	0.96	0.05	1.40	0.38	0.95
0.003	1.30	0.016	0.94	0.07	1.30	0.40	0.94
0.004	1.25	0.018	0.92	0.10	1.25	0.45	0.92
0.005	1.19	0.020	0.90	0.12	1.20	0.50	0.90
0.006	1.15	0.022	0.88	0.15	1.15	0.55	0.88
0.007	1.11	0.025	0.86	0.18	1.11	0.60	0.87
0.008	1.08	0.028	0.84	0.20	1.08	0.70	0.84
0.009	1.06	0.030	0.83	0.22	1.06	0.75	0.83
0.010	1.04	0.032	0.82	0.25	1.04	0.80	0.82
0.011	1.02	0.035	0.80	0.28	1.01	0.90	0.80
0.012	1.00	0.040	0.78	0.30	1.00	1.00	0.78
0.013	0.98	0.060	0.72	0.33	0.98	1.50	0.72

[a] Turning, in/rev; milling, in/tooth; planing and shaping, in/stroke; broaching, in/tooth.
[b] Turning, mm/rev; milling, mm/tooth; planing and shaping, mm/stroke; broaching, mm/tooth.

Table 5. Tool Wear Factors, *W*

Type of Operation		*W*
For all operations with sharp cutting tools		1.00
Turning:	Finish turning (light cuts)	1.10
	Normal rough and semifinish turning	1.30
	Extra-heavy-duty rough turning	1.60–2.00
Milling:	Slab milling	1.10
	End milling	1.10
	Light and medium face milling	1.10–1.25
	Extra-heavy-duty face milling	1.30–1.60
Drilling:	Normal drilling	1.30
	Drilling hard-to-machine materials and drilling with a very dull drill	1.50
Broaching:	Normal broaching	1.05–1.10
	Heavy-duty surface broaching	1.20–1.30
Planing and Shaping	Use values given for turning	

P_m = power at the motor; hp, or kW
K_p = power constant (see Tables 3a and 3b)
Q = metal removal rate; in ^{3}/min or cm^3/s (see Table 7)
C = feed factor for power constant (see Table 4)
W = tool wear factor (see Table 5)
E = machine tool efficiency factor (see Table 6)
V = cutting speed, fpm, or m/min
N = cutting speed, rpm
f = feed rate for turning; in/rev or mm/rev

Copyright 2004, Industrial Press, Inc., New York, NY

f = feed rate for planing and shaping; in/stroke, or mm/stroke
f_t = feed per tooth; in/tooth, or mm/tooth
f_m = feed rate; in/min or mm/min
d_t = maximum depth of cut per tooth: inch, or mm
d = depth of cut; inch, or mm
n_t = number of teeth on milling cutter
n_c = number of teeth engaged in work
w = width of cut; inch, or mm

Table 6. Machine Tool Efficiency Factors, *E*

Type of Drive	*E*	Type of Drive	*E*
Direct Belt Drive	0.90	Geared Head Drive	0.70–0.80
Back Gear Drive	0.75	Oil-Hydraulic Drive	0.60–0.90

Table 7. Formulas for Calculating the Metal Removal Rate, *Q*

Operation	Metal Removal Rate	
	For Inch Units Only Q = in³/min	For SI Metric Units Only Q = cm³/s
Single-Point Tools (Turning, Planing, and Shaping)	$12Vfd$	$\frac{V}{60}fd$
Milling	$f_m wd$	$\frac{f_m wd}{60,000}$
Surface Broaching	$12Vwn_c d_t$	$\frac{V}{60}un_c d_t$

Example: A 180–200 Bhn AISI 4130 shaft is to be turned on a geared head lathe using a cutting speed of 350 fpm (107 m/min), a feed rate of 0.016 in/rev (0.40 mm/rev), and a depth of cut of 0.100 inch (2.54 mm). Estimate the power at the cutting tool and at the motor, using both the inch and metric data.

Inch units:

$K_p = 0.62$ (from Table 3b)
$C = 0.94$ (from Table 4)
$W = 1.30$ (from Table 5)
$E = 0.80$ (from Table 6)
$Q = 12\,Vfd = 12 \times 350 \times 0.016 \times 0.100$ (from Table 7)
$Q = 6.72$ in³/min

$$P_c = K_p CQW = 0.62 \times 0.94 \times 6.72 \times 1.30 = 5.1 \text{ hp}$$

$$P_m = \frac{P_c}{E} = \frac{5}{0.80} = 6.4 \text{ hp}$$

SI metric units:

$K_p = 1.69$ (from Table 3b)
$C = 0.94$ (from Table 4)
$W = 1.30$ (from Table 5)
$E = 0.80$ (from Table 6)

Copyright 2004, Industrial Press, Inc., New York, NY

$$Q = \frac{V}{60} fd = \frac{107}{60} \times 0.40 \times 2.54 = 1.81 \text{ cm}^3/\text{s} \text{ (from Table 7)}$$

$$P_c = K_p CQW = 1.69 \times 0.94 \times 1.81 \times 1.30 = 3.74 \text{ kW}$$

$$P_m = \frac{P_c}{E} = \frac{3.74}{0.80} = 4.677 \text{ kW}$$

Whenever possible the maximum power available on a machine tool should be used when heavy cuts must be taken.

The cutting conditions for utilizing the maximum power should be selected in the following order: 1) select the maximum depth of cut that can be used; 2) select the maximum feed rate that can be used; and 3) estimate the cutting speed that will utilize the maximum power available on the machine. This sequence is based on obtaining the longest tool life of the cutting tool and at the same time obtaining as much production as possible from the machine.

The life of a cutting tool is most affected by the cutting speed, then by the feed rate, and least of all by the depth of cut. The maximum metal removal rate that a given machine is capable of machining from a given material is used as the basis for estimating the cutting speed that will utilize all the power available on the machine.

Example: A 0.125 inch deep cut is to be taken on a 200–210 Bhn AISI 1050 steel part using a 10 hp geared head lathe. The feed rate selected for this job is 018 in./rev. Estimate the cutting speed that will utilize the maximum power available on the lathe.

$K_p = 0.85$ (From Table 3b)
$C = 0.92$ (From Table 4)
$W = 1.30$ (From Table 5)
$E = 0.80$ (From Table 6)

$$Q_{max} = \frac{P_m E}{K_p CW} = \frac{10 \times 0.80}{0.85 \times 0.92 \times 1.30} \qquad \left(P_m = \frac{K_p CQW}{E}\right)$$

$$= 7.87 \text{ in}^3/\text{min}$$

$$V = \frac{Q_{max}}{12fd} = \frac{7.87}{12 \times 0.018 \times 0.125} \qquad (Q = 12Vfd)$$

$$= 291 \text{ fpm}$$

Example: A 160-180 Bhn gray iron casting that is 6 inches wide is to have ⅛ inch stock removed on a 10 hp milling machine, using an 8 inch diameter, 10 tooth, indexable insert cemented carbide face milling cutter. The feed rate selected for this cutter is 0.012 in/tooth, and all the stock (0.125 inch) will be removed in one cut. Estimate the cutting speed that will utilize the maximum power available on the machine.

$K_p = 0.52$ (From Table 3a)
$C = 1.00$ (From Table 4)
$W = 1.20$ (From Table 5)
$E = 0.80$ (From Table 6)

Copyright 2004, Industrial Press, Inc., New York, NY

$$Q_{max} = \frac{P_m E}{K_p C W} = \frac{10 \times 0.80}{0.52 \times 1.00 \times 1.20} = 12.82 \text{ in}^3/\text{min} \qquad \left(P_m = \frac{K_p C Q W}{E}\right)$$

$$f_m = \frac{Q_{max}}{wd} = \frac{12.82}{6 \times 0.125} = 17.1 \text{ in/min} \qquad (Q = f_m w d)$$

$$N = \frac{f_{max}}{f_t n_t} = \frac{17}{0.012 \times 10} = 142.4 \text{ rpm} \qquad (f_m = f_t n_t N)$$

$$V = \frac{\pi D N}{12} = \frac{\pi \times 8 \times 142}{12} = 298.3 \text{ fpm} \qquad \left(N = \frac{12V}{\pi D}\right)$$

Estimating Drilling Thrust, Torque, and Power.— Although the lips of a drill cut metal and produce a chip in the same manner as the cutting edges of other metal cutting tools, the chisel edge removes the metal by means of a very complex combination of extrusion and cutting. For this reason a separate method must be used to estimate the power required for drilling. Also, it is often desirable to know the magnitude of the thrust and the torque required to drill a hole. The formulas and tabular data provided in this section are based on information supplied by the National Twist Drill Division of Regal-Beloit Corp. The values in Tables 8 through 11 are for sharp drills, and tool wear factors are given in Table 5. For most ordinary drilling operations 1.30 can be used as the tool wear factor. When drilling most difficult-to-machine materials and when the drill is allowed to become very dull, 1.50 should be used as the value of this factor. It is usually more convenient to measure the web thickness at the drill point than the length of the chisel edge; for this reason, the approximate *w*/*d* ratio corresponding to each *c*/*d* ratio for a correctly ground drill is provided in Table 9. For most standard twist drills the *c*/*d* ratio is 0.18, unless the drill has been ground short or the web has been thinned. The *c*/*d* ratio of split point drills is 0.03. The formulas given below can be used for spade drills, as well as for twist drills. Separate formulas are required for use with customary inch units and for SI metric units.

Table 8. Work Material Factor, K_d, for Drilling with a Sharp Drill

Work Material	Material Constant, K_d
AISI 1117 (Resulfurized free machining mild steel)	12,000
Steel, 200 Bhn	24,000
Steel, 300 Bhn	31,000
Steel, 400 Bhn	34,000
Cast Iron, 150 Bhn	14,000
Most Aluminum Alloys	7,000
Most Magnesium Alloys	4,000
Most Brasses	14,000
Leaded Brass	7,000
Austenitic Stainless Steel (Type 316)	24,000[a] for Torque 35,000[a] for Thrust
Titanium Alloy Ti6Al4V 40R_c	18,000[a] for Torque 29,000[a] for Thrust
René 41 40R_c	40,000[ab] min.
Hastelloy-C	30,000[a] for Torque 37,000[a] for Thrust

[a] Values based upon a limited number of tests.
[b] Will increase with rapid wear.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Chisel Edge Factors for Torque and Thrust

c/d	Approx. w/d	Torque Factor A	Thrust Factor B	Thrust Factor J	c/d	Approx. w/d	Torque Factor A	Thrust Factor B	Thrust Factor J
0.03	0.025	1.000	1.100	0.001	0.18	0.155	1.085	1.355	0.030
0.05	0.045	1.005	1.140	0.003	0.20	0.175	1.105	1.380	0.040
0.08	0.070	1.015	1.200	0.006	0.25	0.220	1.155	1.445	0.065
0.10	0.085	1.020	1.235	0.010	0.30	0.260	1.235	1.500	0.090
0.13	0.110	1.040	1.270	0.017	0.35	0.300	1.310	1.575	0.120
0.15	0.130	1.080	1.310	0.022	0.40	0.350	1.395	1.620	0.160

For drills of standard design, use $c/d = 0.18$; for split point drills, use $c/d = 0.03$
c/d = Length of Chisel Edge ÷ Drill Diameter.
w/d = Web Thickness at Drill Point ÷ Drill Diameter.

For inch units only:

$$T = 2K_d F_f F_T BW + K_d D^2 JW \quad (1)$$

$$M = K_d F_f F_M AW \quad (2)$$

$$P_c = MN/63{,}025 \quad (3)$$

For SI metric units only:

$$T = 0.05\, K_d F_f F_T BW + 0.007\, K_d D^2 JW \quad (4)$$

$$M = \frac{K_d F_f F_M AW}{40{,}000} = 0.000025\, K_d F_f F_M AW \quad (5)$$

$$P_c = MN/9550 \quad (6)$$

Use with either inch or metric units:

$$P_m = \frac{P_c}{E} \quad (7)$$

where P_c = Power at the cutter; hp, or kW P_m = Power at the motor; hp, or kW
M = Torque; in. lb, or N.m
T = Thrust; lb, or N
K_d = Work material factor (See Table 8)
F_f = Feed factor (See Table 10)
F_T = Thrust factor for drill diameter (See Table 11)
F_M = Torque factor for drill diameter (See Table 11)
A = Chisel edge factor for torque (See Table 9)
B = Chisel edge factor for thrust (See Table 9)
J = Chisel edge factor for thrust (See Table 9)
W = Tool wear factor (See Table 5)
N = Spindle speed; rpm
E = Machine tool efficiency factor (See Table 6)
D = Drill diameter; in., or mm
c = Chisel edge length; in., or mm (See Table 9)
w = Web thickness at drill point; in., or mm (See Table 9)

Example: A standard $\frac{7}{8}$ inch drill is to drill steel parts having a hardness of 200 Bhn on a drilling machine having an efficiency of 0.80. The spindle speed to be used is 350 rpm and the feed rate will be 0.008 in./rev. Calculate the thrust, torque, and power required to drill these holes:

$K_d = 24{,}000$ (From Table 8) $F_f = 0.021$ (From Table 10)
$F_T = 0.899$ (From Table 11) $F_M = 0.786$ (From Table 11)
$A = 1.085$ (From Table 9) $B = 1.355$ (From Table 9) $J = 0.030$ (From Table 9)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Feed Factors F_f for Drilling

Inch Units				SI Metric Units			
Feed, in./rev	F_f	Feed, in./rev	F_f	Feed, mm/rev	F_f	Feed, mm/rev	F_f
0.0005	0.0023	0.012	0.029	0.01	0.025	0.30	0.382
0.001	0.004	0.013	0.031	0.03	0.060	0.35	0.432
0.002	0.007	0.015	0.035	0.05	0.091	0.40	0.480
0.003	0.010	0.018	0.040	0.08	0.133	0.45	0.528
0.004	0.012	0.020	0.044	0.10	0.158	0.50	0.574
0.005	0.014	0.022	0.047	0.12	0.183	0.55	0.620
0.006	0.017	0.025	0.052	0.15	0.219	0.65	0.708
0.007	0.019	0.030	0.060	0.18	0.254	0.75	0.794
0.008	0.021	0.035	0.068	0.20	0.276	0.90	0.919
0.009	0.023	0.040	0.076	0.22	0.298	1.00	1.000
0.010	0.025	0.050	0.091	0.25	0.330	1.25	1.195

Table 11. Drill Diameter Factors: F_T for Thrust, F_M for Torque

Inch Units						SI Metric Units					
Drill Dia., in.	F_T	F_M	Drill Dia., in.	F_T	F_M	Drill Dia., mm	F_T	F_M	Drill Dia., mm	F_T	F_M
0.063	0.110	0.007	0.875	0.899	0.786	1.60	1.46	2.33	22.00	11.86	260.8
0.094	0.151	0.014	0.938	0.950	0.891	2.40	2.02	4.84	24.00	12.71	305.1
0.125	0.189	0.024	1.000	1.000	1.000	3.20	2.54	8.12	25.50	13.34	340.2
0.156	0.226	0.035	1.063	1.050	1.116	4.00	3.03	12.12	27.00	13.97	377.1
0.188	0.263	0.049	1.125	1.099	1.236	4.80	3.51	16.84	28.50	14.58	415.6
0.219	0.297	0.065	1.250	1.195	1.494	5.60	3.97	22.22	32.00	16.00	512.0
0.250	0.330	0.082	1.375	1.290	1.774	6.40	4.42	28.26	35.00	17.19	601.6
0.281	0.362	0.102	1.500	1.383	2.075	7.20	4.85	34.93	38.00	18.36	697.6
0.313	0.395	0.124	1.625	1.475	2.396	8.00	5.28	42.22	42.00	19.89	835.3
0.344	0.426	0.146	1.750	1.565	2.738	8.80	5.96	50.13	45.00	21.02	945.8
0.375	0.456	0.171	1.875	1.653	3.100	9.50	6.06	57.53	48.00	22.13	1062
0.438	0.517	0.226	2.000	1.741	3.482	11.00	6.81	74.90	50.00	22.86	1143
0.500	0.574	0.287	2.250	1.913	4.305	12.50	7.54	94.28	58.00	25.75	1493
0.563	0.632	0.355	2.500	2.081	5.203	14.50	8.49	123.1	64.00	27.86	1783
0.625	0.687	0.429	2.750	2.246	6.177	16.00	9.19	147.0	70.00	29.93	2095
0.688	0.741	0.510	3.000	2.408	7.225	17.50	9.87	172.8	76.00	31.96	2429
0.750	0.794	0.596	3.500	2.724	9.535	19.00	10.54	200.3	90.00	36.53	3293
0.813	0.847	0.689	4.000	3.031	12.13	20.00	10.98	219.7	100.00	39.81	3981

$W = 1.30$ (From Table 5)

$$T = 2K_d F_f F_T BW + K_d d^2 JW$$
$$= 2 \times 24{,}000 \times 0.21 \times 0.899 \times 1.355 \times 1.30 + 24{,}000 \times 0.875^2 \times 0.030 \times 1.30$$
$$= 2313 \text{ lb}$$

$$M = K_d F_f F_M AW$$
$$= 24{,}000 \times 0.021 \times 0.786 \times 1.085 \times 1.30 = 559 \text{ in. lb}$$

$$P_c = \frac{MN}{63{,}025} = \frac{559 \times 350}{63{,}025} = 3.1 \text{ hp} \qquad P_m = \frac{P_c}{E} = \frac{3.1}{0.80} = 3.9 \text{ hp}$$

Twist drills are generally the most highly stressed of all metal cutting tools. They must not only resist the cutting forces on the lips, but also the drill torque resulting from these forces and the very large thrust force required to push the drill through the hole. Therefore, often when drilling smaller holes, the twist drill places a limit on the power used and for very large holes, the machine may limit the power.

Copyright 2004, Industrial Press, Inc., New York, NY

MACHINING ECONOMETRICS

Tool Wear And Tool Life Relationships

Tool wear.— Tool-life is defined as the cutting time to reach a predetermined wear, called the tool wear criterion. The size of tool wear criterion depends on the grade used, usually a tougher grade can be used at bigger flank wear. For finishing operations, where close tolerances are required, the wear criterion is relatively small. Other alternative wear criteria are a predetermined value of the surface roughness, or a given depth of the crater which develops on the rake face of the tool. The most appropriate wear criteria depends on cutting geometry, grade, and materials.

Tool-life is determined by assessing the time — the tool-life — at which a given predetermined flank wear is reached, 0.25, 0.4, 0.6, 0.8 mm etc. Fig. 1 depicts how flank wear varies with cutting time (approximately straight lines in a semi-logarithmic graph) for three combinations of cutting speeds and feeds. Alternatively, these curves may represent how variations of machinability impact on tool-life, when cutting speed and feed are constant. All tool wear curves will sooner or later bend upwards abruptly and the cutting edge will break, i.e., catastrophic failure as indicated by the white arrows in Fig. 1.



Fig. 1. Flank Wear as a Function of Cutting Time

The maximum deviation from the average tool-life 60 minutes in Fig. 1 is assumed to range between 40 and 95 minutes, i.e. –33% and +58% variation. The positive deviation from the average (longer than expected tool-life) is not important, but the negative one (shorter life) is, as the edge may break before the scheduled tool change after 60 minutes, when the flank wear is 0.6 mm.

It is therefore important to set the wear criterion at a safe level such that tool failures due to "normal" wear become negligible. This is the way machinability variations are mastered.

Equivalent Chip Thickness (*ECT*).— *ECT* combines the four basic turning variables, depth of cut, lead angle, nose radius and feed per revolution into one basic parameter. For all other metal cutting operations such as drilling, milling and grinding, additional variables such as number of teeth, width of cut, and cutter diameter are included in the parameter *ECT*. In turning, milling, and drilling, according to the *ECT* principle, when the product of feed times depth of cut is constant the tool-life is constant no matter how the depth of cut or feed is selected, provided that the cutting speed and cutting edge length are maintained constant. By replacing the geometric parameters with *ECT*, the number of tool-life tests to evaluate cutting parameters can be reduced considerably, by a factor of 4 in turning, and in milling by a factor of 7 because radial depth of cut, cutter diameter and number of teeth are additional parameters.

Copyright 2004, Industrial Press, Inc., New York, NY

The introduction of the *ECT* concept constitutes a major simplification when predicting tool-life and calculating cutting forces, torque, and power. *ECT* was first presented in 1931 by Professor R. Woxen, who both theoretically and experimentally proved that *ECT* is a basic metal cutting parameter for high-speed cutting tools. Dr. Colding later proved that the concept also holds for carbide tools, and extended the calculation of *ECT* to be valid for cutting conditions when the depth of cut is smaller than the tool nose radius, or for round inserts. Colding later extended the concept to all other metal cutting operations, including the grinding process.

The definition of *ECT* is:

$$ECT = \frac{Area}{CEL} \text{ (mm or inch)}$$

where A = cross sectional area of cut (approximately = feed × depth of cut), (mm^2 or inch^2)

CEL = cutting edge length (tool contact rubbing length), (mm or inch), see Fig.9.

An exact value of A is obtained by the product of *ECT* and *CEL*. In turning, milling, and drilling, *ECT* varies between 0.05 and 1 mm, and is always less than the feed/rev or feed/tooth; its value is usually about 0.7 to 0.9 times the feed.

Example 1: For a feed of 0.8 mm/rev, depth of cut a = 3 mm, and a cutting edge length $CEL = 4$ mm^2, the value of *ECT* is approximately $ECT = 0.8 \times 3 \div 4 = 0.6$ mm.

The product of *ECT*, *CEL*, and cutting speed V (m/min or ft/min) is equal to the metal removal rate, *MRR*, which is measured in terms of the volume of chips removed per minute:

$$MRR = 1000V \times Area = 1000V \times ECT \times CEL \text{ mm}^3\text{/min}$$
$$= V \times Area \text{ cm}^3\text{/min or inch}^3\text{/min}$$

The specific metal removal rate *SMRR* is the metal removal rate per mm cutting edge length *CEL*, thus:

$$SMMR = 1000V \times ECT \text{ mm}^3\text{/min/mm}$$
$$= V \times ECT \text{ cm}^3\text{/min/mm or inch}^3\text{/min/inch}$$

Example 2: Using above data and a cutting speed of $V = 250$ m/min specific metal removal rate becomes $SMRR = 0.6 \times 250 = 150$ (cm^3/min/mm).

ECT in Grinding: In grinding *ECT* is defined as in the other metal cutting processes, and is approximately equal to $ECT = Vw \times ar \div V$, where Vw is the work speed, ar is the depth of cut, and $A = Vw \times ar$. Wheel life is constant no matter how depth ar, or work speed Vw, is selected at V = constant (usually the influence of grinding contact width can be neglected). This translates into the same wheel life as long as the specific metal removal rate is constant, thus:

$$SMMR = 1000Vw \times ar \text{ mm}^3\text{/min/mm}$$

In grinding, *ECT* is much smaller than in the other cutting processes, ranging from about 0.0001 to 0.001 mm (0.000004 to 0.00004 inch). The grinding process is described in a separate chapter *GRINDING FEEDS AND SPEEDS* starting on page 1158.

Tool-life Relationships.— Plotting the cutting times to reach predetermined values of wear typically results in curves similar to those shown in Fig. 2 (cutting time versus cutting speed at constant feed per tooth) and Fig. 3 (cutting time versus feed per tooth at constant cutting speed). These tests were run in 1993 with mixed ceramics turn-milling hard steel, 82 R_C, at the Technische Hochschule Darmstadt.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Influence of feed per tooth on cutting time



Fig. 3. Influence of cutting speed on tool-life

Tool-life has a maximum value at a particular setting of feed and speed. Economic and productive cutting speeds always occur on the right side of the curves in Figs. 2 and 4, which are called Taylor curves, represented by the so called Taylor's equation.

The variation of tool-life with feed and speed constitute complicated relationships, illustrated in Figs. 6a, 6b, and 6c.

Taylor's Equation.— Taylor's equation is the most commonly used relationship between tool-life T, and cutting speed V. It constitutes a straight line in a log-log plot, one line for each feed, nose radius, lead angle, or depth of cut, mathematically represented by:

$$V \times T^n = C \tag{1a}$$

where $n =$ is the slope of the line

C = is a constant equal to the cutting speed for $T = 1$ minute

By transforming the equation to logarithmic axes, the Taylor lines become straight lines with slope = n. The constant C is the cutting speed on the horizontal (V) axis at tool-life $T =$ 1 minute, expressed as follows

$$\ln V + n \times \ln T = \ln C \tag{1b}$$

For different values of feed or ECT, log-log plots of Equation (1a) form approximately straight lines in which the slope decreases slightly with a larger value of feed or ECT. In practice, the Taylor lines are usually drawn parallel to each other, i.e., the slope n is assumed to be constant.

Fig. 4 illustrates the Taylor equation, tool-life T versus cutting speed V, plotted in log-log coordinates, for four values of $ECT = 0.1, 0.25, 0.5$ and 0.7 mm.

In Fig. 4, starting from the right, each T–V line forms a generally straight line that bends off and reaches its maximum tool-life, then drops off with decreasing speed (see also Figs. 2 and 3. When operating at short tool-lives, approximately when T is less than 5 minutes, each line bends a little so that the cutting speed for 1 minute life becomes less than the value calculated by constant C.

The Taylor equation is a very good approximation of the right hand side of the real tool-life curve (slightly bent). The portion of the curve to the left of the maximum tool-life gives shorter and shorter tool-lives when decreasing the cutting speed starting from the point of maximum tool-life. Operating at the maximum point of maximum tool-life, or to the left of it, causes poor surface finish, high cutting forces, and sometimes vibrations.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Definition of slope *n* and constant C in Taylor's equation

Evaluation of Slope *n*, and Constant C.— When evaluating the value of the Taylor slope based on wear tests, care must be taken in selecting the tool-life range over which the slope is measured, as the lines are slightly curved.

The slope *n* can be found in three ways:

- Calculate *n* from the formula $n = (\ln C - \ln V)/\ln T$, reading the values of C and *V* for any value of *T* in the graph.
- Alternatively, using two points on the line, (V_1, T_1) and (V_2, T_2), calculate *n* using the relationship $V_1 \times T_1^n = V_2 \times T_2^n$. Then, solving for *n*,

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)}$$

- Graphically, *n* may be determined from the graph by measuring the distances "a" and "b" using a mm scale, and *n* is the ratio of *a* and *b*, thus, *n* = a/b

Example: Using Fig. 4, and a given value of *ECT*= 0.7 mm, calculate the slope and constant of the Taylor line.

On the Taylor line for *ECT*= 0.7, locate points corresponding to tool-lives $T_1 = 15$ minutes and $T_2 = 60$ minutes. Read off the associated cutting speeds as, approximately, $V_1 = 110$ m/min and $V_2 = 65$ m/min.

The slope *n* is then found to be $n = \ln(110/65)/\ln(60/15) = 0.38$

The constant C can be then determined using the Taylor equation and either point (T_1, V_1) or point (T_2, V_2), with equivalent results, as follows:

$$C = V \times T^n = 110 \times 15^{0.38} = 65 \times 60^{0.38} = 308 \text{ m/min (1027 fpm)}$$

The Generalized Taylor Equation.— The above calculated slope and constant C define tool-life at one particular value of feed *f*, depth of cut *a*, lead angle *LA*, nose radius *r*, and other relevant factors.

The generalized Taylor equation includes these parameters and is written

$$T^n = A \times f^m \times a^p \times LA^q \times r^s \qquad (2)$$

where *A* = area; and, *n*, *m*, *p*, *q*, and *s* = constants.

There are two problems with the generalized equation: 1) a great number of tests have to be run in order to establish the constants *n*, *m*, *p*, *q*, *s*, etc.; and 2) the accuracy is not very good because Equation (2) yields straight lines when plotted versus *f*, *a*, *LA*, and *r*, when in reality, they are parabolic curves..

Copyright 2004, Industrial Press, Inc., New York, NY

The Generalized Taylor Equation using Equivalent Chip Thickness (ECT): Due to the compression of the aforementioned geometrical variables (f, a, LA, r, etc.) into ECT, Equation (2) can now be rewritten:

$$V \times T^n = A \times ECT^m \tag{3}$$

Experimental data confirms that the Equation (3) holds, approximately, within the range of the test data, but as soon as the equation is extended beyond the test results, the error can become very great because the *V–ECT* curves are represented as straight lines by Equation (3)and the real curves have a parabolic shape.

The Colding Tool-life Relationship.— This relationship contains 5 constants H, K, L, M, and N_0, which attain different values depending on tool grade, work material, and the type of operation, such as longitudinal turning versus grooving, face milling versus end milling, etc.

This tool-life relationship is proven to describe, with reasonable accuracy, how tool-life varies with ECT and cutting speed for any metal cutting and grinding operation. It is expressed mathematically as follows either as a generalized Taylor equation (4a), or, in logarithmic coordinates (4b):

$$V \times T^{(N_0 - L \times \ln ECT)} \times ECT^{\left(-\frac{H}{2M} + \frac{\ln ECT}{4M}\right)} = e^{\left(K - \frac{H}{4M}\right)} \tag{4a}$$

$$y = K - \frac{x - H}{4M} - z(N_0 - L_x) \tag{4b}$$

where $x = \ln ECT \quad y = \ln V \quad z = \ln T$

M = the vertical distance between the maximum point of cutting speed (ECT_H, V_H) for $T = 1$ minute and the speed V_G at point (ECT_G, V_G), as shown in Fig. 5.

$2M$ = the horizontal distance between point (ECT_H, V_G) and point (V_G, ECT_G)

H and K = the logarithms of the coordinates of the maximum speed point (ECT_H, V_H) at tool-life $T = 1$ minute, thus $H = \ln(ECT_H)$ and $K = \ln(V_H)$

N_0 and L = the variation of the Taylor slope n with ECT: $n = N_0 - L \times \ln(ECT)$



Fig. 5. Definitions of the constants H, K, L, M, and N_0 for tool-life equation in the V-ECT plane with tool-life constant

The constants L and N_0 are determined from the slopes n_1 and n_2 of two Taylor lines at ECT_1 and ECT_2, and the constant M from 3 *V–ECT* values at any constant tool-life. Constants H and K are then solved using the tool-life equation with the above-calculated values of L, N_0 and M.

Copyright 2004, Industrial Press, Inc., New York, NY

The *G*- and *H*-curves.— The *G*-curve defines the longest possible tool-life for any given metal removal rate, *MRR*, or specific metal removal rate, *SMRR*. It also defines the point where the total machining cost is minimum, after the economic tool-life T_E, or optimal tool-life T_O, has been calculated, see *Optimization Models, Economic Tool-life when Feed is Constant* starting on page 1110.

The tool-life relationship is depicted in the 3 planes: *T*–*V*, where *ECT* is the plotted parameter (the Taylor plane); *T*–*ECT*, where *V* is plotted; and, *V*–*ECT*, where *T* is a parameter. The latter plane is the most useful because the optimal cutting conditions are more readily understood when viewing in the *V*–*ECT* plane. Figs. 6a, 6b, and 6c show how the tool-life curves look in these 3 planes in log-log coordinates.



Fig. 6a. Tool-life vs. cutting sped *T*–*V*, *ECT* plotted

Fig. 6a shows the Taylor lines, and Fig. 6b illustrates how tool-life varies with *ECT* at different values of cutting speed, and shows the *H*-curve. Fig. 6c illustrates how cutting speed varies with *ECT* at different values of tool-life. The *H*- and *G*-curves are also drawn in Fig. 6c.



Fig. 6b. Tool-life vs. *ECT*, *T*–*ECT*, cutting speed plotted

A simple and practical method to ascertain that machining is not done to the left of the *H*-curve is to examine the chips. When *ECT* is too small, about 0.03-0.05 mm, the chips tend to become irregular and show up more or less as dust.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6c. Cutting speed vs. *ECT*, *V–ECT*, tool-life plotted

The *V–ECT–T* Graph and the Tool-life Envelope.— The tool-life envelope, in Fig. 7, is an area laid over the *V–ECT–T* graph, bounded by the points A, B, C, D, and E, within which successful cutting can be realized. The H- and *G*-curves represent two borders, lines $\overline{AE}$ and $\overline{BC}$. The border curve, line $\overline{AB}$, shows a lower limit of tool-life, $T_{MIN} = 5$ minutes, and border curve, line $\overline{DE}$, represents a maximum tool-life, $T_{MAX} = 300$ minutes.

T_{MIN} is usually 5 minutes due to the fact that tool-life versus cutting speed does not follow a straight line for short tool-lives; it decreases sharply towards one minute tool-life. T_{MAX} varies with tool grade, material, speed and *ECT* from 300 minutes for some carbide tools to 10000 minutes for diamond tools or diamond grinding wheels, although systematic studies of maximum tool-lives have not been conducted.

Sometimes the metal cutting system cannot utilize the maximum values of the *V–ECT–T* envelope, that is, cutting at optimum *V–ECT* values along the *G*-curve, due to machine power or fixture constraints, or vibrations. Maximum ECT values, ECT_{MAX}, are related to the strength of the tool material and the tool geometry, and depend on the tool grade and material selection, and require a relatively large nose radius.



Fig. 7. Cutting speed vs. *ECT*, *V–ECT*, tool-life plotted

Minimum *ECT* values, ECT_{MIN}, are defined by the conditions at which surface finish suddenly deteriorates and the cutting edge begins rubbing rather than cutting. These conditions begin left of the *H*-curve, and are often accompanied by vibrations and built-up edges on the tool. If feed or *ECT* is reduced still further, excessive tool wear with sparks and tool breakage, or melting of the edge occurs. For this reason, values of *ECT* lower than approx-

Copyright 2004, Industrial Press, Inc., New York, NY

imately 0.03 mm should not be allowed. In Fig. 7, the ECT_{MIN} boundary is indicated by contour line $\overline{A'E'}$.

In milling the minimum feed/tooth depends on the ratio ar/D, of radial depth of cut ar, and cutter diameter D. For small ar/D ratios, the chip thickness becomes so small that it is necessary to compensate by increasing the feed/tooth. See *High-speed Machining Econometrics* starting on page 1122 for more on this topic.

Fig. 7 demonstrates, in principle, minimum cost conditions for roughing at point $\mathbf{O_R}$, and for finishing at point $\mathbf{O_F}$, where surface finish or tolerances have set a limit. Maintaining the speed at $\mathbf{O_R}$, 125 m/min, and decreasing feed reaches a maximum tool-life = 300 minutes at $ECT = 0.2$, and a further decrease of feed will result in shorter lives.

Similarly, starting at point X ($V = 150, ECT = 0.5, T = 15$) and reducing feed, the H-curve will be reached at point E ($ECT = 0.075, T = 300$). Continuing to the left, tool-life will decrease and serious troubles occur at point E′ ($ECT = 0.03$).

Starting at point $\mathbf{O_F}$ ($V = 300, ECT = 0.2, T = 15$) and reducing feed the H-curve will be reached at point E ($ECT = 0.08, T = 15$). Continuing to the left, life will decrease and serious troubles occur at $ECT = 0.03$.

Starting at point X ($V = 400, ECT = 0.2, T = 5$) and reducing feed the H-curve will be reached at point E ($ECT = 0.09, T = 7$). Continuing to the left, life will decrease and serious troubles occur at point A′ ($ECT = 0.03$), where $T = 1$ minute.

Cutting Forces and Chip Flow Angle.— There are three cutting forces, illustrated in Fig. 8, that are associated with the cutting edge with its nose radius r, depth of cut a, lead angle LA, and feed per revolution f, or in milling feed per tooth f_z. There is one drawing for roughing and one for finishing operations.



Fig. 8. Definitions of equivalent chip thickness, ECT, and chip flow angle, CFA.

The cutting force F_C, or tangential force, is perpendicular to the paper plane. The other two forces are the feed or axial force F_A, and the radial force F_R directed towards the work piece. The resultant of F_A and F_R is called F_H. When finishing, F_R is bigger than F_A, while in roughing F_A is usually bigger than F_R. The direction of F_H, measured by the chip flow angle CFA, is perpendicular to the rectangle formed by the cutting edge length CEL and ECT (the product of ECT and CEL constitutes the cross sectional area of cut, A). The important task of determining the direction of F_H, and calculation of F_A and F_R, are shown in the formulas given in the Fig. 8.

The method for calculating the magnitudes of F_H, F_A, and F_R is described in the following. The first thing is to determine the value of the cutting force F_C. Approximate formulas

Copyright 2004, Industrial Press, Inc., New York, NY

to calculate the tangential cutting force, torque and required machining power are found in the section *ESTIMATING SPEEDS AND MACHINING POWER* starting on page 1082.

Specific Cutting Force, Kc: The specific cutting force, or the specific energy to cut, Kc, is defined as the ratio between the cutting force F_C and the chip cross sectional area, A. thus, $Kc = F_C \div A$ N/mm^2.

The value of Kc decreases when ECT increases, and when the cutting speed V increases. Usually, Kc is written in terms of its value at $ECT = 1$, called Kc_1, and neglecting the effect of cutting speed, thus $Kc = Kc_1 \times ECT^B$, where B = slope in log-log coordinates



Fig. 9. Kc vs. ECT, cutting speed plotted

A more accurate relationship is illustrated in Fig. 9, where Kc is plotted versus ECT at 3 different cutting speeds. In Fig. 9, the two dashed lines represent the aforementioned equation, which each have different slopes, B. For the middle value of cutting speed, Kc varies with ECT from about 1900 to 1300 N/mm^2 when ECT increases from 0.1 to 0.7 mm. Generally the speed effect on the magnitude of Kc is approximately 5 to 15 percent when using economic speeds.



Fig. 10. F_H/F_C vs. ECT, cutting speed plotted

Determination of Axial, F_A, and Radial, F_R, Forces: This is done by first determining the resultant force F_H and then calculating F_A and F_R using the Fig. 8 formulas. F_H is derived

Copyright 2004, Industrial Press, Inc., New York, NY

from the ratio F_H/F_C, which varies with *ECT* and speed in a fashion similar to *Kc*. Fig. 10 shows how this relationship may vary.

As seen in Fig. 10, F_H/F_C is in the range 0.3 to 0.6 when *ECT* varies from 0.1 to 1 mm, and speed varies from 200 to 250 m/min using modern insert designs and grades. Hence, using reasonable large feeds F_H/F_C is around 0.3 – 0.4 and when finishing about 0.5 – 0.6.

Example: Determine F_A and F_R, based on the chip flow angle *CFA* and the cutting force F_C, in turning.

Using a value of $Kc = 1500$ N/mm^2 for roughing, when $ECT = 0.4$, and the cutting edge length $CEL = 5$ mm, first calculate the area $A = 0.4 \times 5 = 2$ mm^2. Then, determine the cutting force $F_C = 2 \times 1500 = 3000$ Newton, and an approximate value of $F_H = 0.5 \times 3000 = 1500$ Newton.

Using a value of $Kc = 1700$ N/mm^2 for finishing, when $ECT = 0.2$, and the cutting edge length $CEL = 2$ mm, calculate the area $A = 0.2 \times 2 = 0.4$ mm^2. The cutting force $F_C = 0.4 \times 1700 = 680$ Newton and an approximate value of $F_H = 0.35 \times 680 = 238$ Newton.

Fig. 8 can be used to estimate *CFA* for rough and finish turning. When the lead angle *LA* is 15 degrees and the nose radius is relatively large, an estimated value of the chip flow angle becomes about 30 degrees when roughing, and about 60 degrees in finishing. Using the formulas for F_A and F_R relative to F_H gives:

Roughing:
$F_A = F_H \times \cos(CFA) = 1500 \times \cos 30 = 1299$ Newton
$F_R = F_H \times \sin(CFA) = 1500 \times \sin 30 = 750$ Newton

Finishing:
$F_A = F_H \times \cos(CFA) = 238 \times \cos 60 = 119$ Newton
$F_R = F_H \times \sin(CFA) = 238 \times \sin 60 = 206$ Newton

The force ratio F_H/F_C also varies with the tool rake angle and increases with negative rakes. In grinding, F_H is much larger than the grinding cutting force F_C; generally F_H/F_C is approximately 2 to 4, because grinding grits have negative rakes of the order –35 to –45 degrees.

Forces and Tool-life.— Forces and tool life are closely linked. The ratio F_H/F_C is of particular interest because of the unique relationship of F_H/F_C with tool-life.



Fig. 11a. F_H/F_C vs. *ECT*

The results of extensive tests at Ford Motor Company are shown in Figs. 11a and 11b, where F_H/F_C and tool-life *T* are plotted versus *ECT* at different values of cutting speed *V*.

Copyright 2004, Industrial Press, Inc., New York, NY

For any constant speed, tool-life has a maximum at approximately the same values of *ECT* as has the function F_H/F_C.

LIVE GRAPH
Click here to view



Fig. 11b. Tool-life vs. *ECT*

The Force Relationship: Similar tests performed elsewhere confirm that the F_H/F_C function can be determined using the 5 tool-life constants (H, K, M, L, N_0) introduced previously, and a new constant (L_F/L).

$$\ln\left(\frac{1}{a}\cdot\frac{F_H}{F_C}\right) = \frac{K - y - \dfrac{(x-H)^2}{4M}}{\dfrac{L_F}{L}(N_0 - Lx)} \tag{5}$$

The constant a depends on the rake angle; in turning a is approximately 0.25 to 0.5 and L_F/L is 10 to 20. F_C attains it maximum values versus *ECT* along the *H*-curve, when the tool-life equation has maxima, and the relationships in the three force ratio planes look very similar to the tool-life functions shown in the tool-life planes in Figs. 6a, 6b, and 6c.

LIVE GRAPH
Click here to view



Fig. 12. Tool-life vs. F_H/F_C

Tool-life varies with F_H/F_C with a simple formula according to Equation (5) as follows:

Copyright 2004, Industrial Press, Inc., New York, NY

$$T = \left(\frac{F_H}{aF_C}\right)^{\frac{L_F}{L}}$$

where L is the constant in the tool-life equation, Equation (4a) or (4b), and L_F is the corresponding constant in the force ratio equation, Equation (5). In Fig. 12 this function is plotted for $a = 0.5$ and for $L_F/L = 5, 10,$ and 20.

Accurate calculations of aforementioned relationships require elaborate laboratory tests, or better, the design of a special test and follow-up program for parts running in the ordinary production. A software machining program, such as Colding International Corp. *COMP* program can be used to generate the values of all 3 forces, torque and power requirements both for sharp and worn tools

Surface Finish R_a and Tool-life.— It is well known that the surface finish in turning decreases with a bigger tool nose radius and increases with feed; usually it is assumed that R_a increases with the square of the feed per revolution, and decreases inversely with increasing size of the nose radius. This formula, derived from simple geometry, gives rise to great errors. In reality, the relationship is more complicated because the tool geometry must taken into account, and the work material and the cutting conditions also have a significant influence.



Fig. 13. R_a vs. *ECT*, nose radius r constant

Fig. 13 shows surface finish R_a versus *ECT* at various cutting speeds for turning cast iron with carbide tools and a nose radius r = 1.2 mm. Increasing the cutting speed leads to a smaller R_a value.

Fig. 14 shows how the finish improves when the tool nose radius, r, increases at a constant cutting speed (168 m/min) in cutting nodular cast iron.

In Fig. 15, R_a is plotted versus *ECT* with cutting speed V for turning a 4310 steel with carbide tools, for a nose radius $r = 1.2$ mm, illustrating that increasing the speed also leads to a smaller R_a value for steel machining.

A simple rule of thumb for the effect of increasing nose radius r on decreasing surface finish R_a, regardless of the ranges of *ECT* or speeds used, albeit within common practical values, is as follows. In finishing,

$$\frac{R_{a1}}{R_{a2}} = \left(\frac{r_2}{r_1}\right)^{0.5} \quad (6)$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 14. R_a vs. ECT
cutting speed constant, nose radius r varies



Fig. 15. R_a vs. ECT,
cutting speed and nose radius r constant

In roughing, multiply the finishing values found using Equation (6) by 1.5, thus, $R_{a\,(\text{Rough})} = 1.5 \times R_{a\,(\text{Finish})}$ for each ECT and speed.

Example 1: Find the decrease in surface roughness resulting from a tool nose radius change from $r = 0.8$ mm to $r = 1.6$ mm in finishing. Also, find the comparable effect in roughing.

For finishing, using $r_2 = 1.6$ and $r_1 = 0.8$, $R_{a1}/R_{a2} = (1.6/0.8)^{0.5} = 1.414$, thus, the surface roughness using the larger tool radius is $R_{a2} = R_{a1} \div 1.414 = 0.7R_{a1}$

In roughing, at the same ECT and speed, $R_a = 1.5 \times R_{a2} = 1.5 \times 0.7R_{a1} = 1.05R_{a1}$

Example 2: Find the decrease in surface roughness resulting from a tool nose radius change from $r = 0.8$ mm to $r = 1.2$ mm

For finishing, using $r_2 = 1.2$ and $r_1 = 0.8$, $R_{a1}/R_{a2} = (1.2/0.8)^{0.5} = 1.224$, thus, the surface roughness using the larger tool radius is $R_{a2} = R_{a1} \div 1.224 = 0.82R_{a1}$

In roughing, at the same ECT and speed, $R_a = 1.5 \times R_{a2} = 1.5 \times 0.82R_{a1} = 1.23R_{a1}$

It is interesting to note that, at a given ECT, the R_a curves have a minimum, see Figs. 13 and 15, while tool-life shows a maximum, see Figs. 6b and 6c. As illustrated in Fig. 16, R_a increases with tool-life T when ECT is constant, in principle in the same way as does the force ratio.



Fig. 16. R_a vs. T, holding ECT constant

The Surface Finish Relationship: R_a is determined using the same type of mathematical relationship as for tool-life and force calculations:

$$y = K_{Ra} - \frac{x - H_{Ra}{}^2}{4M_{Ra}} - (N_{0Ra} - L_{Ra})\ln(R_a)$$

where $K_{RA}, H_{RA}, M_{RA}, N_{ORA}$, and L_{RA} are the 5 surface finish constants.

Copyright 2004, Industrial Press, Inc., New York, NY

Shape of Tool-life Relationships for Turning, Milling, Drilling and Grinding Operations—Overview.— A summary of the general shapes of tool-life curves (*V–ECT–T* graphs) for the most common machining processes, including grinding, is shown in double logarithmic coordinates in Fig. 17a through Fig. 17h.



Fig. 17a. Tool-life for turning cast iron using coated carbide



Fig. 17b. Tool-life for turning low-alloy steel using coated carbide



Fig. 17c. Tool-life for end-milling AISI 4140 steel using high-speed steel



Fig. 17d. Tool-life for end-milling low-allow steel using uncoated carbide

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 17e. Tool-life for end-milling low-alloy steel using coated carbide



Fig. 17f. Tool-life for face-milling SAE 1045 steel using coated carbide



Fig. 17g. Tool-life for solid carbide drill



Fig. 17h. Wheel-life in grinding M4 tool-steel

Calculation Of Optimized Values Of Tool-life, Feed And Cutting Speed

Minimum Cost.— Global optimum is defined as the absolute minimum cost considering all alternative speeds, feeds and tool-lives, and refers to the determination of optimum tool-life T_O, feed f_O, and cutting speed V_O, for either minimum cost or maximum production rate. When using the tool-life equation, $T = f(V, ECT)$, determine the corresponding feed, for given values of depth of cut and operation geometry, from optimum equivalent chip thickness, ECT_O. Mathematically the task is to determine minimum cost, employing the cost function C_{TOT} = cost of machining time + tool changing cost + tooling cost. Minimum cost optima occur along the so-called *G*-curve, identified in Fig. 6c.

Another important factor when optimizing cutting conditions involves choosing the proper cost values for cost per edge C_E, replacement time per edge T_{RPL}, and not least, the hourly rate H_R that should be applied. H_R is defined as the portion of the hourly shop rate that is applied to the operations and machines in question. If optimizing all operations in the portion of the shop for which H_R is calculated, use the full rate; if only one machine is involved, apply a lower rate, as only a portion of the general overhead rate should be used, otherwise the optimum, and anticipated savings, are erroneous.

Copyright 2004, Industrial Press, Inc., New York, NY

Production Rate.— The production rate is defined as the cutting time or the metal removal rate, corrected for the time required for tool changes, but neglecting the cost of tools.

The result of optimizing production rate is a shorter tool-life, higher cutting speed, and a higher feed compared to minimum cost optimization, and the tooling cost is considerably higher. Production rates optima also occur along the *G*-curve.

The Cost Function.— There are a number of ways the total machining cost C_{TOT} can be plotted, for example, versus feed, *ECT*, tool-life, cutting speed or other parameter. In Fig. 18a, cost for a face milling operation is plotted versus cutting time, holding feed constant, and using a range of tool-lives, *T*, varying from 1 to 240 minutes.

LIVE GRAPH
Click here to view

	t_c	C_{TOOL}	C_{TOT}	T	V
	5.85	0.487	0.569	1	598
	6.91	0.192	0.288	3	506
	7.47	0.125	0.228	5	468
	8.30	0.069	0.185	10	421
	8.83	0.049	0.172	15	396
Minimum cost	**9.81**	**0.027**	**0.164**	**30**	**356**
	10.91	0.015	0.167	60	321
	11.60	0.011	0.172	90	302
	12.12	0.008	0.177	120	289
	13.47	0.005	0.192	240	260



Fig. 18a. Variation of tooling cost C_{TOOL}, and total cost C_C, with cutting time t_c, including minimum cost cutting time

The tabulated values show the corresponding cutting speeds determined from the tool-life equation, and the influence of tooling on total cost. Tooling cost, C_{TOOL} = sum of tool cost + cost of replacing worn tools, decreases the longer the cutting time, while the total cost, C_{TOT}, has a minimum at around 10 seconds of cutting time. The dashed line in the graph represents the cost of machining time: the product of hourly rate H_R, and the cutting time t_c divided by 60. The slope of the line defines the value of H_R.



Fig. 18b. Total cost vs. cutting time for simultaneously cutting with 1, 2, and 4 tools

Copyright 2004, Industrial Press, Inc., New York, NY

The cutting time for minimum cost varies with the ratio of tooling cost and H_R. Minimum cost moves towards a longer cutting time (longer tool-life) when either the price of the tooling increases, or when several tools cut simultaneously on the same part. In Fig. 18b, this is exemplified by running 2 and 4 cutters simultaneously on the same work piece, at the same feed and depth of cut, and with a similar tool as in Fig. 18a. As the tooling cost goes up 2 and 4 times, respectively, and H_R is the same, the total costs curves move up, but also moves to the right, as do the points of minimum cost and optimal cutting times. This means that going somewhat slower, with more simultaneously cutting tools, is advantageous.

Global Optimum.— Usually, global optimum occurs for large values of feed, heavy roughing, and in many cases the cutting edge will break trying to apply the large feeds required. Therefore, true optima cannot generally be achieved when roughing, in particular when using coated and wear resistant grades; instead, use the maximum values of feed, ECT_{max}, along the tool-life envelope, see Fig. 7.

As will be shown in the following, the first step is to determine the optimal tool-life T_O, and then determine the optimum values of feeds and speeds.

Optimum Tool-life $T_O = 22$ minutes

	fz	V_{22}	t_c, sec.	C_{TOOL}	C_{TOT}
	0.03	416	28.067	0.1067	0.4965
	0.08	397	11.017	0.0419	0.1949
	0.10	374	9.357	0.0356	0.1655
	0.17	301	6.831	0.0260	0.1208
	0.20	276	6.334	0.0241	0.1120
	0.40	171	5.117	0.0194	0.0905
Minimum Cost	**0.60**	**119**	**4.903**	**0.0186**	**0.0867**
	0.70	91	4.924	0.0187	0.0871

Maximum Production Rate, $T = 5$ minutes

fz	V_5	t_c	C_{TOOL}	C_{TOT}
0.7	163	3.569	0.059	0.109

T Varies between 1 and 240 minutes

$f_z = 0.10$		ECT= 0.26		
t_c secs.	C_{TOOL}	C_{TOT}	T	V
5.850	0.487	0.569	1	598
6.914	0.192	0.288	3	506
7.473	0.125	0.228	5	468
8.304	0.069	0.185	10	421
8.832	0.049	0.172	15	396
9.815	**0.027**	**0.164**	**30**	**357**
10.906	0.015	0.167	60	321
11.600	0.011	0.172	90	302
12.119	0.008	0.177	120	289
13.467	0.005	0.192	240	260

Minimum Cost



Fig. 19. Variation of tooling and total cost with cutting time, comparing global optimum with minimum cost at $fz = 0.1$ mm

The example in Fig. 19 assumes that $T_O = 22$ minutes and the feed and speed optima were calculated as $f_O = 0.6$ mm/tooth, $V_O = 119$ m/min, and cutting time $t_{cO} = 4.9$ secs.

The point of maximum production rate corresponds to $f_O = 0.7$ mm/tooth, $V_O = 163$ m/min, at tool-life $T_O = 5$ minutes, and cutting time $t_{cO} = 3.6$ secs. The tooling cost is approximately 3 times higher than at minimum cost (0.059 versus 0.0186), while the piece cost is only slightly higher: \$0.109 versus \$0.087.

When comparing the global optimum cost with the minimum at feed = 0.1 mm/tooth the graph shows it to be less than half (0.087 versus 0.164), but also the tooling cost is about 1/3 lower (0.0186 versus 0.027). The reason why tooling cost is lower depends on the tooling cost term $t_c \times C_E/T$ (see *Calculation of Cost of Cutting and Grinding Operations* on page

Copyright 2004, Industrial Press, Inc., New York, NY

1115). In this example, cutting times t_c= 4.9 and 9.81 seconds, at T = 22 and 30 minutes respectively, and the ratios are proportional to 4.9/22 = 0.222 and 9.81/30 = 0.327 respectively.

The portions of the total cost curve for shorter cutting times than at minimum corresponds to using feeds and speeds right of the *G*-curve, and those on the other side are left of this curve.

Optimization Models, Economic Tool-life when Feed is Constant.— Usually, optimization is performed versus the parameters tool-life and cutting speed, keeping feed at a constant value. The cost of cutting as function of cutting time is a straight line with the slope = H_R = hourly rate. This cost is independent of the values of tool change and tooling. Adding the cost of tool change and tooling, gives the variation of total cutting cost which shows a minimum with cutting time that corresponds to an economic tool-life, T_E. Economic tool-life represents a local optima (minimum cost) at a given constant value of feed, feed/tooth, or *ECT*.

Using the Taylor Equation: $V \times T = C$ and differentiating C_{TOT} with respect to T yields:

Economic tool-life:
$T_E = T_V \times (1/n - 1)$, minutes

Economic cutting speed:
$V_E = C/T_E{}^n$, m/min, or sfm

In these equations, n and C are constants in the Taylor equation for the given value of feed. Values of Taylor slopes, n, are estimated using the speed and feed Tables 1 through 23 starting on page 1027 and handbook Table 5b on page 1035 for turning, and Table 15e on page 1059 for milling and drilling; and T_V is the equivalent tooling-cost time. $T_V = T_{RPL} + 60 \times C_E \div H_R$, minutes, where T_{RPL} = time for replacing a worn insert, or a set of inserts in a milling cutter or inserted drill, or a twist drill, reamer, thread chaser, or tap. T_V is described in detail, later; C_E = cost per edge, or set of edges, or cost per regrind including amortized price of tool;

and H_R = hourly shop rate, or that rate that is impacted by the changes of cutting conditions .

In two dimensions, Fig. 20a shows how economic tool-life varies with feed per tooth. In this figure, the equivalent tooling-cost time T_V is constant, however the Taylor constant n varies with the feed per tooth.



Fig. 20a. Economic tool-life, T_E vs. feed per tooth, fz

Copyright 2004, Industrial Press, Inc., New York, NY

Economic tool-life increases with greater values of T_V, either when T_{RPL} is longer, or when cost per edge C_E is larger for constant H_R, or when H_R is smaller and T_{RPL} and C_E are unchanged. For example, when using an expensive machine (which makes H_R bigger) the value of T_V gets smaller, as does the economic tool-life, $T_E = T_V \times (1/n - 1)$. Reducing T_E results in an increase in the economic cutting speed, V_E. This means raising the cutting speed, and illustrates the importance, in an expensive system, of utilizing the equipment better by using more aggressive machining data.



Fig. 20b. Tool-life vs. cutting speed, constant *ECT*

As shown in Fig. 20a for a face milling operation, economic tool-life T_E varies considerably with feed/tooth f_z, in spite of the fact that the Taylor lines have only slightly different slopes ($ECT = 0.51, 0.6, 1.54$), as shown in Fig. 20b. The calculation is based on the following cost data: $T_V = 6$, hourly shop rate H_R = \$60/hour, cutter diameter D = 125 mm with number of teeth $z = 10$, and radial depth of cut $ar = 40$ mm.

The conclusion relating to the determination of economic tool-life is that both hourly rate H_R and slope n must be evaluated with reasonable accuracy in order to arrive at good values. However, the method shown will aid in setting the trend for general machining economics evaluations.

Global Optimum, Graphical Method.— There are several ways to demonstrate in graphs how cost varies with the production parameters including optimal conditions. In all cases, tool-life is a crucial parameter.

Cutting time t_c is inversely proportional to the specific metal removal rate, $SMRR = V \times ECT$, thus, $1/t_c = V \times ECT$. Taking the log of both sides,

$$\ln V = -\ln ECT - \ln t_c + C \tag{7}$$

where C is a constant.

Equation (7) is a straight line with slope (– 1) in the *V–ECT* graph when plotted in a log-log graph. This means that a constant cutting time is a straight 45-degree line in the *V–ECT* graph, when plotted in log-log coordinates with the same scale on both axis (a square graph).

The points at which the constant cutting time lines (at 45 degrees slope) are tangent to the tool-life curves define the *G*-curve, along which global optimum cutting occurs.

Note: If the ratio *a*/*CEL* is not constant when *ECT* varies, the constant cutting time lines are not straight, but the cutting time deviation is quite small in most cases.

Copyright 2004, Industrial Press, Inc., New York, NY

In the *V–ECT* graph, Fig. 21, 45-degree lines have been drawn tangent to each tool-life curve: *T*=1, 5, 15, 30, 60, 100 and 300 minutes. The tangential points define the *G*-curve, and the 45-degree lines represent different constant cutting times: 1, 2, 3, 10 minutes, etc. Following one of these lines and noting the intersection points with the tool-life curves *T*= 1, 5, etc., many different speed and feed combinations can be found that will give the same cutting time. As tool-life gets longer (tooling cost is reduced), *ECT* (feed) increases but the cutting speed has to be reduced.

LIVE GRAPH
Click here to view



Fig. 21. Constant cutting time in the *V-ECT* plane, tool-life constant

Global Optimum, Mathematical Method.— Global optimization is the search for extremum of C_{TOT} for the three parameters: *T*, *ECT*, and *V*. The results, in terms of the tool-life equation constants, are:

Optimum tool-life:

$$T_O = T_V \times \left(\frac{1}{n_O} - 1\right)$$

$$n_O = 2M \times (L \times \ln T_O)^2 + 1 - N_0 + L \times (2M + H)$$

where n_O = slope at optimum *ECT*.

The same approach is used when searching for maximum production rate, but without the term containing tooling cost.

Optimum cutting speed:

$$V_O = e^{-M + K + (H \times L - N_0) \times \ln T_O + M \times L^2 \times (\ln T_O)^2}$$

Optimum *ECT*:

$$ECT_O = e^{H + 2M \times (L \times \ln(T_O) + 1)}$$

Global optimum is not reached when face milling for very large feeds, and C_{TOT} decreases continually with increasing feed/tooth, but can be reached for a cutter with many teeth, say 20 to 30. In end milling, global optimum can often be achieved for big feeds and for 3 to 8 teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

Determination Of Machine Settings And Calculation Of Costs

Based on the rules and knowledge presented in Chapters 1 and 2, this chapter demonstrates, with examples, how machining times and costs are calculated.

Additional formulas are given, and the speed and feed tables given in *SPEED AND FEED TABLES* starting on page 1022 should be used. Finally the selection of feeds, speeds and tool-lives for optimized conditions are described with examples related to turning, end milling, and face milling.

There are an infinite number of machine settings available in the machine tool power train producing widely different results. In practice only a limited number of available settings are utilized. Often, feed is generally selected independently of the material being cut, however, the influence of material is critical in the choice of cutting speed. The tool-life is normally not known or directly determined, but the number of pieces produced before the change of worn tools is better known, and tool-life can be calculated using the formula for piece cutting time t_c given in this chapter.

It is well known that increasing feeds or speeds reduces the number of pieces cut between tool changes, but not how big are the changes in the basic parameter tool-life. Therefore, there is a tendency to select "safe" data in order to get a long tool-life. Another common practice is to search for a tool grade yielding a longer life using the current speeds and feeds, or a 10–20% increase in cutting speed while maintaining the current tool-life. The reason for this old-fashioned approach is the lack of knowledge about the opportunities the metal cutting process offers for increased productivity.

For example, when somebody wants to calculate the cutting time, he/she can select a value of the feed rate (product of feed and rpm), and easily find the cutting time by dividing cutting distance by the feed rate. The number of pieces obtained out of a tool is a guesswork, however. This problem is very common and usually the engineers find desired tool-lives after a number of trial and error runs using a variety of feeds and speeds. If the user is not well familiar with the material cut, the tool-life obtained could be any number of seconds or minutes, or the cutting edge might break.

There are an infinite number of feeds and speeds, giving the same feed rate, producing equal cutting time. The same cutting time per piece t_c is obtained independent of the selection of feed/rev f and cutting speed V, (or rpm), as long as the feed rate F_R remains the same: $F_R = f_1 \times \text{rpm}_1 = f_2 \times \text{rpm}_2 = f_3 \times \text{rpm}_3 \ldots$, etc. However, the number of parts before tool change N_{ch} will vary considerably including the tooling cost c_{tool} and the total cutting cost c_{tot}.

The dilemma confronting the machining-tool engineer or the process planner is how to set feeds and speeds for either desired cycle time, or number of parts between tool changes, while balancing the process versus other operations or balancing the total times in one cell with another. These problems are addressed in this section.

Nomenclature

f = feed/rev or tooth, mm f_E = economic feed f_O = optimum feed
T = tool-life, minutes T_E = economic tool-life T_O = optimum tool-life
V = cutting speed, m/min V_E = economic cutting speed V_O = optimum cutting speed, m/min

Similarly, economic and optimum values of:

c_{tool} = piece cost of tooling, \$ C_{TOOL} = cost of tooling per batch, \$
c_{tot} = piece total cost of cutting, \$ C_{TOT} = total cost of cutting per batch, \$
F_R = feed rate measured in the feeding direction, mm/rev
N = batch size
N_{ch} = number of parts before tool change
t_c = piece cutting time, minutes T_C = cutting time per batch, minutes
t_{cyc} = piece cycle time, minutes T_{CYC} = cycle time before tool change, minutes

Copyright 2004, Industrial Press, Inc., New York, NY

t_i = idle time (tool "air" motions during cycle), minutes
z = cutter number of teeth

The following variables are used for calculating the per batch cost of cutting:

C_C = cost of cutting time per batch, $
C_{CH} = cost of tool changes per batch, $
C_E = cost per edge, for replacing or regrinding, $
H_R = hourly rate, $
T_V = equivalent tooling-cost time, minutes
T_{RPL} = time for replacing worn edge(s), or tool for regrinding, minutes

Note: In the list above, when two variables use the same name, one in capital letters and one lower case, T_C and t_c for example, the variable name in capital letters refers to batch processing and lowercase letters to per piece processing, such as $T_C = N_{ch} \times t_c$, $C_{TOT} = N_{ch} \times c_{tot}$, etc.

Formulas Valid For All Operation Types Including Grinding

Calculation of Cutting Time and Feed Rate

Feed Rate:

$F_R = f \times$ rpm (mm/min), where f is the feed in mm/rev along the feeding direction,

rpm is defined in terms of work piece or cutter diameter D in mm, and cutting speed V in m/min, as follows:

$$\text{rpm} = \frac{1000V}{\pi D} = \frac{318V}{D}$$

Cutting time per piece:

Note: Constant cutting time is a straight 45-degree line in the *V–ECT* graph, along which tool-life varies considerably, as is shown in Chapter 2.

$$t_c = \frac{Dist}{F_R} = \frac{Dist}{f \times \text{rpm}} = \frac{Dist \times \pi D}{1000V \times f}$$

where the units of distance cut $Dist$, diameter D, and feed f are mm, and V is in m/min.

In terms of ECT, cutting time per piece, t_c, is as follows:

$$t_c = \frac{Dist \times \pi D}{1000V} \times \frac{a}{CEL \times ECT}$$

where a = depth of cut, because feed × cross sectional chip area = $f \times a = CEL \times ECT$.

Example 3, Cutting Time: Given $Dist$ = 105 mm, D = 100 mm, f = 0.3 mm, V = 300 m/min, rpm = 700, F_R = 210 mm/min, find the cutting time.

Cutting time = $t_c = 105 \times 3.1416 \times 100 \div (1000 \times 300 \times 0.3) = 0.366$ minutes = 22 seconds

Scheduling of Tool Changes

Number of parts before tool change:

$N_{ch} = T \div t_c$

Cycle time before tool change:

$T_{CYC} = N_{ch} \times (t_c + t_i)$, where $t_{cyc} = t_c + t_i$, where t_c = cutting time per piece, t_i = idle time per piece

Tool-life:

$T = N_{ch} \times t_c$

Example 4: Given tool-life T = 90 minutes, cutting time t_c = 3 minutes, and idle time t_i = 3 minutes, find the number of parts produced before a tool change is required and the time until a tool change is required.

Copyright 2004, Industrial Press, Inc., New York, NY

Number of parts before tool change = $N_{ch} = 90/3 = 30$ parts.

Cycle time before tool change = $T_{CYC} = 30 \times (3 + 3) = 180$ minutes

Example 5: Given cutting time, $t_c = 1$ minute, idle time $t_i = 1$ minute, $N_{ch} = 100$ parts, calculate the tool-life T required to complete the job without a tool change, and the cycle time before a tool change is required.

Tool-life = $T = N_{ch} \times t_c = 100 \times 1 = 100$ minutes.

Cycle time before tool change = $T_{CYC} = 100 \times (1 + 1) = 200$ minutes.

Calculation of Cost of Cutting and Grinding Operations.— When machining data varies, the cost of cutting, tool changing, and tooling will change, but the costs of idle and slack time are considered constant.

Cost of Cutting per Batch:

$C_C = H_R \times T_C/60$

T_C = cutting time per batch = (number of parts) × t_c, minutes, or when determining time for tool change $T_{Cch} = N_{ch} \times t_c$ minutes = cutting time before tool change.

t_c = Cutting time/part, minutes

H_R = Hourly Rate

Cost of Tool Changes per Batch:

$$C_{CH} = \frac{H_R}{60} \times T_C \times \frac{T_{RPL}}{T} \qquad \frac{\$}{min} \cdot min = \$$$

where T = tool-life, minutes, and T_{RPL} = time for replacing a worn edge(s), or tool for regrinding, minutes

Cost of Tooling per Batch:

Including cutting tools and holders, but without tool changing costs,

$$C_{TOOL} = \frac{H_R}{60} \times T_C \times \frac{\frac{60C_E}{H_R}}{T} \qquad \frac{\$}{min} \cdot min \cdot \frac{\frac{min}{hr} \cdot \$ \cdot \frac{hr}{\$}}{min} = \$$$

Cost of Tooling + Tool Changes per Batch:

Including cutting tools, holders, and tool changing costs,

$$(C_{TOOL} + C_{CH}) = \frac{H_R}{60} \times T_C \times \frac{T_{RPL} + \frac{60C_E}{H_R}}{T}$$

Total Cost of Cutting per Batch:

$$C_{TOT} = \frac{H_R}{60} \times T_C \left(1 + \frac{T_{RPL} + \frac{60C_E}{H_R}}{T} \right)$$

Equivalent Tooling-cost Time, T_V:

The two previous expressions can be simplified by using $T_V = T_{RPL} + \frac{60C_E}{H_R}$

thus:

$$(C_{TOOL} + C_{CH}) = \frac{H_R}{60} \times T_C \times \frac{T_V}{T}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$C_{TOT} = \frac{H_R}{60} \times T_C\left(1 + \frac{T_V}{T}\right)$$

C_E = cost per edge(s) is determined using two alternate formulas, depending on whether tools are reground or inserts are replaced:

Cost per Edge, Tools for Regrinding

$$C_E = \frac{\text{cost of tool} + (\text{number of regrinds} \times \text{cost/regrind})}{1 + \text{number of regrinds}}$$

Cost per Edge, Tools with Inserts:

$$C_E = \frac{\text{cost of insert(s)}}{\text{number of edges per insert}} + \frac{\text{cost of cutter body}}{\text{cutter body life in number of edges}}$$

Note: In practice allow for insert failures by multiplying the insert cost by 4/3, that is, assuming only 3 out of 4 edges can be effectively used.

Example 6, Cost per Edge–Tools for Regrinding: Use the data in the table below to calculate the cost per edge(s) C_E, and the equivalent tooling-cost time T_V, for a drill.

Time for cutter replacement T_{RPL}, minute	Cutter Price, $	Cost per regrind, $	Number of regrinds	Hourly shop rate, $	Batch size	Taylor slope, n	Economic cutting time, t_{cE} minute
1	40	6	5	50	1000	0.25	1.5

Using the cost per edge formula for reground tools, $C_E = (40 + 5 \times 6) \div (1 + 5) = \$6.80$

When the hourly rate is \$50/hr, $T_V = T_{RPL} + \frac{60C_E}{H_R} = 1 + \frac{60(6.8)}{50} = 9.16$ minutes

Calculate economic tool-life using $T_E = T_V \times \left(\frac{1}{n} - 1\right)$ thus, $T_E = 9.17 \times (1/0.25 - 1) =$ $9.16 \times 3 = 27.48$ minutes.

Having determined, elsewhere, the economic cutting time per piece to be $t_{cE} = 1.5$ minutes, for a batch size = 1000 calculate:

Cost of Tooling + Tool Change per Batch:

$$(C_{TOOL} + C_{CH}) = \frac{H_R}{60} \times T_C \times \frac{T_V}{T} = \frac{50}{60} \times 1000 \times 1.5 \times \frac{9.16}{27.48} = \$\ 417$$

Total Cost of Cutting per Batch:

$$C_{TOT} = \frac{H_R}{60} \times T_C\left(1 + \frac{T_V}{T}\right) = \frac{50}{60} \times 1000 \times 1.5 \times \left(1 + \frac{9.16}{27.48}\right) = \$\ 1617$$

Example 7, Cost per Edge–Tools with Inserts: Use data from the table below to calculate the cost of tooling and tool changes, and the total cost of cutting.

For face milling, multiply insert price by safety factor 4/3 then calculate the cost per edge: $C_E = 10 \times (5/3) \times (4/3) + 750/500 = 23.72$ per set of edges

When the hourly rate is \$50, equivalent tooling-cost time is $T_V = 2 + 23.72 \times 60/50 =$ 30.466 minutes (first line in table below). The economic tool-life for Taylor slope $n =$ 0.333 would be $T_E = 30.466 \times (1/0.333 - 1) = 30.466 \times 2 = 61$ minutes.

When the hourly rate is \$25, equivalent tooling-cost time is $T_V = 2 + 23.72 \times 60/25 =$ 58.928 minutes (second line in table below). The economic tool-life for Taylor slope $n =$ 0.333 would be $T_E = 58.928 \times (1/0.333 - 1) = 58.928 \times 2 = 118$ minutes.

Copyright 2004, Industrial Press, Inc., New York, NY

Time for replacement of inserts T_{RPL}, minutes	Number of inserts	Price per insert	Edges per insert	Cutter Price	Edges per cutter	Cost per set of edges, C_E	Hourly shop rate	T_V minutes
Face mill								
2	10	5	3	750	500	23.72	50	30.466
2	10	5	3	750	500	23.72	25	58.928
End mill								
1	3	6	2	75	200	4.375	50	6.25
Turning								
1	1	5	3	50	100	2.72	30	6.44

With above data for the face mill, and after having determined the economic cutting time as $t_{cE} = 1.5$ minutes, calculate for a batch size = 1000 and $50 per hour rate:

Cost of Tooling + Tool Change per Batch:

$$(C_{TOOL} + C_{CH}) = \frac{H_R}{60} \times T_C \times \frac{T_V}{T} = \frac{50}{60} \times 1000 \times 1.5 \times \frac{30.466}{61} = \$\ 624$$

Total Cost of Cutting per Batch:

$$C_{TOT} = \frac{H_R}{60} \times T_C\left(1 + \frac{T_V}{T}\right) = \frac{50}{60} \times 1000 \times 1.5 \times \left(1 + \frac{30.466}{61}\right) = \$\ 1874$$

Similarly, at the $25/hour shop rate, $(C_{TOOL} + C_{CH})$ and C_{TOT} are $312 and $937, respectively.

Example 8, Turning: Production parts were run in the shop at feed/rev = 0.25 mm. One series was run with speed $V_1 = 200$ m/min and tool-life was $T_1 = 45$ minutes. Another was run with speed $V_2 = 263$ m/min and tool-life was $T_2 = 15$ minutes. Given idle time $t_i = 1$ minute, cutting distance $Dist = 1000$ mm, work diameter $D = 50$ mm.

First, calculate Taylor slope, n, using Taylor's equation $V_1 \times T_1{}^n = V_2 \times T_2{}^n$, as follows:

$$n = \ln\frac{V_1}{V_2} \div \ln\frac{T_2}{T_1} = \ln\frac{200}{263} \div \ln\frac{15}{45} = 0.25$$

Economic tool-life T_E is next calculated using the equivalent tooling-cost time T_V, as described previously. Assuming a calculated value of $T_V = 4$ minutes, then T_E can be calculated from

$$T_E = T_V \times \left(\frac{1}{n} - 1\right) = 4 \times \left(\frac{1}{0.25} - 1\right) = 12 \text{ minutes}$$

Economic cutting speed, V_E can be found using Taylor's equation again, this time using the economic tool-life, as follows,

$$V_{E1} \times (T_E)^n = V_2 \times (T_2)^n$$

$$V_{E1} = V_2 \times \left(\frac{T_2}{T_E}\right)^n = 263 \times \left(\frac{15}{12}\right)^{0.25} = 278 \text{ m/min}$$

Using the process data, the remaining economic parameters can be calculated as follows:
Economic spindle rpm, $\text{rpm}_E = (1000V_E)/(\pi D) = (1000 \times 278)/(3.1416 \times 50) = 1770$ rpm
Economic feed rate, $F_{RE} = f \times \text{rpm}_E = 0.25 \times 1770 = 443$ mm/min
Economic cutting time, $t_{cE} = Dist/F_{RE} = 1000/443 = 2.259$ minutes
Economic number of parts before tool change, $N_{chE} = T_E \div t_{cE} = 12 \div 2.259 = 5.31$ parts
Economic cycle time before tool change, $T_{CYCE} = N_{chE} \times (t_c + t_i) = 5.31 \times (2.259 + 1) =$ 17.3 minutes.

Copyright 2004, Industrial Press, Inc., New York, NY

Variation Of Tooling And Total Cost With The Selection Of Feeds And Speeds

It is a well-known fact that tool-life is reduced when either feed or cutting speed is increased. When a higher feed/rev is selected, the cutting speed must be decreased in order to maintain tool-life. However, a higher feed rate (feed rate = feed/rev × rpm, mm/min) can result in a longer tool-life if proper cutting data are applied. Optimized cutting data require accurate machinability databases and a computer program to analyze the options. Reasonably accurate optimized results can be obtained by selecting a large feed/rev or tooth, and then calculating the economic tool-life T_E. Because the cost versus feed or *ECT* curve is shallow around the true minimum point, i.e., the global optimum, the error in applying a large feed is small compared with the exact solution.

Once a feed has been determined, the economic cutting speed V_E can be found by calculating the Taylor slope, and the time/cost calculations can be completed using the formulas described in last section.

The remainder of this section contains examples useful for demonstrating the required procedures. Global optimum may or may not be reached, and tooling cost may or may not be reduced, compared to currently used data. However, the following examples prove that significant time and cost reductions are achievable in today's industry.

Note: Starting values of reasonable feeds in mm/rev can be found in the Handbook speed and feed tables, see *Principal Speed andFeed Tables* on page 1022, by using the f_{avg} values converted to mm as follows: feed (mm/rev) = feed (inch/rev) × 25.4 (mm/inch), thus 0.001 inch/rev = 0.001× 25.4 = 0.0254 mm/rev. When using speed and feed Tables 1 through 23, where feed values are given in thousandths of inch per revolution, simply multiply the given feed by 25.4/1000 = 0.0254, thus feed (mm/rev) = feed (0.001 inch/rev) × 0.0254 (mm/ 0.001inch).

Example 9, Converting Handbook Feed Values From Inches to Millimeters: Handbook tables give feed values f_{opt} and f_{avg} for 4140 steel as 17 and 8 × (0.001 inch/rev) = 0.017 and 0.009 inch/rev, respectively. Convert the given feeds to mm/rev.

feed = 0.017 × 25.4 = 17 × 0.0254 = 0.4318 mm/rev

feed = 0.008 × 25.4 = 8 × 0.0254 = 0.2032 mm/rev

Example 10, Using Handbook Tables to Find the Taylor Slope and Constant: Calculate the Taylor slope and constant, using cutting speed data for 4140 steel in Table 1 starting on page 1027, and for ASTM Class 20 grey cast iron using data from Table 4a on page 1033, as follows:

For the 175–250 Brinell hardness range, and the hard tool grade,

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)} = \frac{\ln(525/705)}{\ln(15/45)} = 0.27 \qquad C = V_1 \times (T_1)^n = 1458$$

For the 175–250 Brinell hardness range, and the tough tool grade,

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)} = \frac{\ln(235/320)}{\ln(15/45)} = 0.28 \qquad C = V_1 \times (T_1)^n = 685$$

For the 300–425 Brinell hardness range, and the hard tool grade,

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)} = \frac{\ln(330/440)}{\ln(15/45)} = 0.26 \qquad C = V_1 \times (T_1)^n = 894$$

For the 300–425 Brinell hardness range, and the tough tool grade,

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)} = \frac{\ln(125/175)}{\ln(15/45)} = 0.31 \qquad C = V_1 \times (T_1)^n = 401$$

For ASTM Class 20 grey cast iron, using hard ceramic,

Copyright 2004, Industrial Press, Inc., New York, NY

$$n = \frac{\ln(V_1/V_2)}{\ln(T_2/T_1)} = \frac{\ln(1490/2220)}{\ln(15/45)} = 0.36 \qquad C = V_1 \times (T_1)^n = 5932$$

Selection of Optimized Data.— Fig. 22 illustrates cutting time, cycle time, number of parts before a tool change, tooling cost, and total cost, each plotted versus feed for a constant tool-life. Approximate minimum cost conditions can be determined using the formulas previously given in this section.

First, select a large feed/rev or tooth, and then calculate economic tool-life T_E, and the economic cutting speed V_E, and do all calculations using the time/cost formulas as described previously.



Fig. 22. Cutting time, cycle time, number of parts before tool change, tooling cost, and total cost vs. feed for tool-life = 15 minutes, idle time = 10 s, and batch size = 1000 parts

Example 11, Step by Step Procedure: Turning – Facing out: 1) Select a big feed/rev, in this case $f = 0.9$ mm/rev (0.035 inch/rev). A Taylor slope n is first determined using the Handbook tables and the method described in Example 10. In this example, use $n = 0.35$ and C = 280.

2) Calculate T_V from the tooling cost parameters:

If cost of insert = \$7.50; edges per insert = 2; cost of tool holder = \$100; life of holder = 100 insert sets; and for tools with inserts, allowance for insert failures = cost per insert by 4/3, assuming only 3 out of 4 edges can be effectively used.

Then, cost per edge = C_E is calculated as follows:

$$C_E = \frac{\text{cost of insert(s)}}{\text{number of edges per insert}} + \frac{\text{cost of cutter body}}{\text{cutter body life in number of edges}}$$

$$= \frac{7.50 \times 4/3}{2} + \frac{100}{100} = \$6.00$$

The time for replacing a worn edge of the facing insert $= T_{RPL} = 2.24$ minutes. Assuming an hourly rate H_R = \$50/hour, calculate the equivalent tooling-cost time T_V

$$T_V = T_{RPL} + 60 \times C_E/H_R = 2.24 + 60 \times 6/50 = 9.44 \text{ minutes}$$

3) Determine economic tool-life T_E

$$T_E = T_V \times (1/n - 1) = 9.44 \times (1/0.35 - 1) = 17.5 \text{ minutes}$$

4) Determine economic cutting speed using the Handbook tables using the method shown in Example 10,

$$V_E = C/T_E^n \text{ m/min} = 280 / 17.5^{0.35} = 103 \text{ m/min}$$

Copyright 2004, Industrial Press, Inc., New York, NY

5) Determine cost of tooling per batch (cutting tools, holders and tool changing) then total cost of cutting per batch:

$$C_{TOOL} = H_R \times T_C \times (C_E/T)/60$$
$$(C_{TOOL}+C_{CH}) = H_R \times T_C \times ((T_{RPL}+C_E/T)/60$$
$$C_{TOT} = H_R \times T_C (1 + (T_{RPL}+C_E)/T)$$

Example 12, Face Milling – Minimum Cost : This example demonstrates how a modern firm, using the formulas previously described, can determine optimal data. It is here applied to a face mill with 10 teeth, milling a 1045 type steel, and the radial depth versus the cutter diameter is 0.8. The *V–ECT–T* curves for tool-lives 5, 22, and 120 minutes for this operation are shown in Fig. 23a.



Fig. 23a. Cutting speed vs. ECT, tool-life constant

The global cost minimum occurs along the *G*-curve, see Fig. 6c and Fig. 23a, where the 45-degree lines defines this curve. Optimum *ECT* is in the range 1.5 to 2 mm.

For face and end milling operations, $ECT = z \times f_z \times ar/D \times aa/CEL \div \pi$. The ratio $aa/CEL = 0.95$ for lead angle $LA = 0$, and for $ar/D = 0.8$ and 10 teeth, using the formula to calculate the feed/tooth range gives for $ECT = 1.5, f_z = 0.62$ mm and for $ECT = 2, f_z = 0.83$ mm.



Fig. 23b. Cutting time per part vs. feed per tooth

Using computer simulation, the minimum cost occurs approximately where Fig. 23a indicates it should be. Total cost has a global minimum at f_z around 0.6 to 0.7 mm and a speed of around 110 m/min. *ECT* is about 1.9 mm and the optimal cutter life is $T_O = 22$ minutes. Because it may be impossible to reach the optimum feed value due to tool breakage,

Copyright 2004, Industrial Press, Inc., New York, NY

the maximum practical feed f_{max} is used as the optimal value. The difference in costs between a global optimum and a practical minimum cost condition is negligible, as shown in Figs. 23c and 23e. A summary of the results are shown in Figs. 23a through 23e, and Table 1.



Fig. 23c. Total cost vs. feed/tooth

When plotting cutting time/part, t_c, versus feed/tooth, f_z, at $T = 5, 22, 120$ in Figs. 23b, tool-life $T = 5$ minutes yields the shortest cutting time, but total cost is the highest; the minimum occurs for f_z about 0.75 mm, see Figs. 23c. The minimum for $T = 120$ minutes is about 0.6 mm and for $T_O = 22$ minutes around 0.7 mm.



Fig. 23d. Tooling cost versus feed/tooth

Fig. 23d shows that tooling cost drop off quickly when increasing feed from 0.1 to 0.3 to 0.4 mm, and then diminishes slowly and is almost constant up to 0.7 to 0.8 mm/tooth. It is generally very high at the short tool-life 5 minutes, while tooling cost of optimal tool-life 22 minutes is about 3 times higher than when going slow at T =120 minutes.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 23e. Total cost vs. cutting speed at 3 constant tool-lives, feed varies

The total cost curves in Fig. 23e. were obtained by varying feed and cutting speed in order to maintain constant tool-lives at 5, 22 and 120 minutes. Cost is plotted as a function of speed V instead of feed/tooth. Approximate optimum speeds are $V = 150$ m/min at $T = 5$ minutes, $V = 180$ m/min at $T = 120$ minutes, and the global optimum speed is $V_O = 110$ m/min for $T_O = 22$ minutes.

Table 1 displays the exact numerical values of cutting speed, tooling cost and total cost for the selected tool-lives of 5, 22, and 120 minutes, obtained from the software program.

Table 1. Face Milling, Total and Tooling Cost versus *ECT*, Feed/tooth *fz*, and Cutting Speed *V*, at Tool-lives 5, 22, and 120 minutes

		$T = 5$ minutes			$T = 22$ minutes			$T = 120$ minutes		
fz	*ECT*	*V*	C_{TOT}	C_{TOOL}	*V*	C_{TOT}	C_{TOOL}	*V*	C_{TOT}	C_{TOOL}
0.03	0.08	489	0.72891	0.39759	416	0.49650	0.10667	344	0.49378	0.02351
0.08	0.21	492	0.27196	0.14834	397	0.19489	0.04187	311	0.20534	0.00978
0.10	0.26	469	0.22834	0.12455	374	0.16553	0.03556	289	0.17674	0.00842
0.17	0.44	388	0.16218	0.08846	301	0.12084	0.02596	225	0.13316	0.00634
0.20	0.51	359	0.14911	0.08133	276	0.11204	0.02407	205	0.12466	0.00594
0.40	1.03	230	0.11622	0.06339	171	0.09051	0.01945	122	0.10495	0.00500
0.60	1.54	164	0.10904	0.05948	119	0.08672	0.01863	83	0.10301	0.00491
0.70	1.80	141	0.10802	0.05892	102	0.08665	0.01862	70	0.10393	0.00495
0.80	2.06	124	0.10800	0.05891	89	0.08723	0.01874	60	0.10547	0.00502
1.00	2.57	98	0.10968	0.05982	69	0.08957	0.01924	47	0.10967	0.00522

High-speed Machining Econometrics

High-speed Machining – No Mystery.— This section describes the theory and gives the basic formulas for any milling operation and high-speed milling in particular, followed by several examples on high-speed milling econometrics. These rules constitute the basis on which selection of milling feed factors is done. Selection of cutting speeds for general milling is done using the Handbook Table 10 through 14, starting on page 1044.

High-speed machining is no mystery to those having a good knowledge of metal cutting. Machining materials with very good machinability, such as low-alloyed aluminum, have for ages been performed at cutting speeds well below the speed values at which these materials should be cut. Operating at these low speeds often results in built-up edges and poor surface finish, because the operating conditions selected are on the wrong side of the Taylor curve, i.e. to the left of the *H*-curve representing maximum tool-life values (see Fig. 4 on page 1096).

Copyright 2004, Industrial Press, Inc., New York, NY

In the 1950's it was discovered that cutting speed could be raised by a factor of 5 to 10 when hobbing steel with HSS cutters. This is another example of being on the wrong side of the Taylor curve.

One of the first reports on high-speed end milling using high-speed steel (HSS) and carbide cutters for milling 6061-T651 and A356-T6 aluminum was reported in a study funded by Defense Advanced Research Project Agency (DARPA). Cutting speeds of up to 4400 m/min (14140 fpm) were used. Maximum tool-lives of 20 through 40 minutes were obtained when the feed/tooth was 0.2 through 0.25 mm (0.008 to 0.01 inch), or measured in terms of *ECT* around 0.07 to 0.09 mm. Lower or higher feed/tooth resulted in shorter cutter lives. The same types of previously described curves, namely *T–ECT* curves with maximum tool-life along the *H*-curve, were produced.

When examining the influence of *ECT*, or feed/rev, or feed/tooth, it is found that too small values cause chipping, vibrations, and poor surface finish. This is caused by inadequate (too small) chip thickness, and as a result the material is not cut but plowed away or scratched, due to the fact that operating conditions are on the wrong (left) side of the tool-life versus *ECT* curve (*T-ECT* with constant speed plotted).

There is a great difference in the thickness of chips produced by a tooth traveling through the cutting arc in the milling process, depending on how the center of the cutter is placed in relation to the workpiece centerline, in the feed direction. Although end and face milling cut in the same way, from a geometry and kinematics standpoint they are in practice distinguished by the cutter center placement away from, or close to, the work centerline, respectively, because of the effect of cutter placement on chip thickness. This is the criteria used to distinguishing between the end and face milling processes in the following.

Depth of Cut/Cutter Diameter, ar/D is the ratio of the radial depth of cut *ar* and the cutter diameter *D*. In face milling when the cutter axis points approximately to the middle of the work piece axis, eccentricity is close to zero, as illustrated in Figs. 3 and 4, page 1042, and Fig. 5 on page 1043. In end milling, $ar/D = 1$ for full slot milling.

Mean Chip Thickness, hm is a key parameter that is used to calculate forces and power requirements in high-speed milling. If the mean chip thickness *hm* is too small, which may occur when feed/tooth is too small (this holds for all milling operations), or when *ar/D* decreases (this holds for ball nose as well as for straight end mills), then cutting occurs on the left (wrong side) of the tool-life versus *ECT* curve, as illustrated in Figs. 6b and 6c.

In order to maintain a given chip thickness in end milling, the feed/tooth has to be increased, up to 10 times for very small *ar/D* values in an extreme case with no run out and otherwise perfect conditions. A 10 times increase in feed/tooth results in 10 times bigger feed rates (F_R) compared to data for full slot milling (valid for $ar/D = 1$), yet maintain a given chip thickness. The cutter life at any given cutting speed will not be the same, however.

Increasing the number of teeth from say 2 to 6 increases equivalent chip thickness *ECT* by a factor of 3 while the mean chip thickness *hm* remains the same, but does not increase the feed rate to 30 (3×10) times bigger, because the cutting speed must be reduced. However, when the *ar/D* ratio matches the number of teeth, such that one tooth enters when the second tooth leaves the cutting arc, then $ECT = hm$. Hence, *ECT* is proportional to the number of teeth. Under ideal conditions, an increase in number of teeth z from 2 to 6 increases the feed rate by, say, 20 times, maintaining tool-life at a reduced speed. In practice about 5 times greater feed rates can be expected for small *ar/D* ratios (0.01 to 0.02), and up to 10 times with 3 times as many teeth. So, high-speed end milling is no mystery.

Chip Geometry in End and Face Milling.— Fig. 24 illustrates how the chip forming process develops differently in face and end milling, and how mean chip thickness *hm* varies with the angle of engagement *AE*, which depends on the *ar/D* ratio. The pertinent chip geometry formulas are given in the text that follows.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 24.

Comparison of face milling and end milling geometry

High-speed end milling refers to values of ar/D that are less than 0.5, in particular to ar/D ratios which are considerably smaller. When $ar/D = 0.5$ ($AE = 90$ degrees) and diminishing in end milling, the chip thickness gets so small that poor cutting action develops, including plowing or scratching. This situation is remedied by increasing the feed/tooth, as shown in Table 2a as an increasing f_z/f_{z0} ratio with decreasing ar/D. For end milling, the f_z/f_{z0} feed ratio is 1.0 for $ar/D = 1$ and also for $ar/D = 0.5$. In order to maintain the same hm as at $ar/D = 1$, the feed/tooth should be increased, by a factor of 6.38 when ar/D is 0.01 and by more than 10 when ar/D is less than 0.01. Hence high-speed end milling could be said to begin when ar/D is less than 0.5

In end milling, the ratio $f_z/f_{z0} = 1$ is set at $ar/D = 1.0$ (full slot), a common value in vendor catalogs and handbooks, for $hm = 0.108$ mm.

The face milling chip making process is exactly the same as end milling when face milling the side of a work piece and $ar/D = 0.5$ or less. However, when face milling close to and along the work centerline (eccentricity is close to zero) chip making is quite different, as shown in Fig. 24. When $ar/D = 0.74$ ($AE = 95$ degrees) in face milling, the f_z/f_{z0} ratio = 1 and increases up to 1.4 when the work width is equal to the cutter diameter ($ar/D = 1$). The face milling f_z/f_{z0} ratio continues to diminish when the ar/D ratio decreases below $ar/D = 0.74$, but very insignificantly, only about 11 percent when $ar/D = 0.01$.

In face milling $f_z/f_{z0} = 1$ is set at $ar/D = 0.74$, a common value recommended in vendor catalogs and handbooks, for $hm = 0.151$ mm.

Fig. 25 shows the variation of the feed/tooth-ratio in a graph for end and face milling.



Fig. 25. Feed/tooth versus ar/D for face and end milling

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2a. Variation of Chip Thickness and f_z/f_{z0} with *ar/D*

	Face Milling					End Milling (straight)				
	eccentricity $e = 0$ $z = 8$ $f_{z0} = 0.017$ $\cos AE = 1 - 2 \times (ar/D)^2$					$z = 2$ $f_{z0} = 0.017$ $\cos AE = 1 - 2 \times (ar/D)$				
ar/D	*AE*	hm/f_z	*hm*	*ECT/hm*	f_z/f_{z0}	*AE*	hm/f_z	*hm*	*ECT/hm*	f_z/f_{z0}
1.0000	180.000	0.637	0.108	5.000	1.398	180.000	0.637	0.108	1.000	1.000
0.9000	128.316	0.804	0.137	3.564	1.107	143.130	0.721	0.122	0.795	0.884
0.8000	106.260	0.863	0.147	2.952	1.032	126.870	0.723	0.123	0.711	0.881
0.7355	94.702	0.890	0.151	2.631	1.000	118.102	0.714	0.122	0.667	0.892
0.6137	75.715	0.929	0.158	1.683	0.958	103.144	0.682	0.116	0.573	0.934
0.5000	60.000	0.162	0.932	0.216	0.202	90.000	0.674	0.115	0.558	1.000
0.3930	46.282	0.973	0.165	1.028	0.915	77.643	0.580	0.099	0.431	1.098
0.2170	25.066	0.992	0.169	0.557	0.897	55.528	0.448	0.076	0.308	1.422
0.1250	14.361	0.997	0.170	0.319	0.892	41.410	0.346	0.059	0.230	1.840
0.0625	7.167	0.999	0.170	0.159	0.891	28.955	0.247	0.042	0.161	2.574
0.0300	3.438	1.000	0.170	0.076	0.890	19.948	0.172	0.029	0.111	3.694
0.0100	1.146	1.000	0.170	0.025	0.890	11.478	0.100	0.017	0.064	6.377
0.0010	0.115	1.000	0.000	0.000	0.890	3.624	0.000	0.000	0.000	20.135

In Table 2a, a standard value $f_{z0} = 0.17$ mm/tooth (commonly recommended average feed) was used, but the f_z/f_{z0} values are independent of the value of feed/tooth, and the previously mentioned relationships are valid whether $f_{z0} = 0.17$ or any other value.

In both end and face milling, $hm = 0.108$ mm for $f_{z0} = 0.17$mm when $ar/D = 1$. When the f_z/f_{z0} ratio = 1, $hm = 0.15$ for face milling, and 0.108 in end milling both at $ar/D = 1$ and 0.5. The tabulated data hold for perfect milling conditions, such as, zero run-out and accurate sharpening of all teeth and edges.

Mean Chip Thickness *hm* and Equivalent Chip Thickness *ECT*.— The basic formula for equivalent chip thickness *ECT* for any milling process is:

$ECT = f_z \times z/\pi \times (ar/D) \times aa/CEL$, where f_z = feed/tooth, z = number of teeth, D = cutter diameter, ar = radial depth of cut, aa = axial depth of cut, and CEL = cutting edge length. As a function of mean chip thickness *hm*:

$ECT = hm \times (z/2) \times (AE/180)$, where AE = angle of engagement.

Both terms are exactly equal when one tooth engages as soon as the preceding tooth leaves the cutting section. Mathematically, $hm = ECT$ when $z = 360/AE$; thus:

for face milling, $AE = \arccos(1 - 2 \times (ar/D)^2)$

for end milling, $AE = \arccos(1 - 2 \times (ar/D))$

Calculation of Equivalent Chip Thickness (ECT) versus Feed/tooth and Number of teeth.: Table 2b is a continuation of Table 2a, showing the values of *ECT* for face and end milling for decreasing values *ar/D*, and the resulting *ECT* when multiplied by the f_z/f_{z0} ratio $f_{z0} = 0.17$ (based on $hm = 0.108$).

Small *ar/D* ratios produce too small mean chip thickness for cutting chips. In practice, minimum values of *hm* are approximately 0.02 through 0.04 mm for both end and face milling.

Formulas.— Equivalent chip thickness can be calculated for other values of f_z and z by means of the following formulas:

Face milling: $ECT_F = ECT_{0F} \times (z/8) \times (f_z/0.17) \times (aa/CEL)$

or, if ECT_F is known calculate f_z using:

$f_z = 0.17 \times (ECT_F/ECT_{0F}) \times (8/z) \times (CEL/aa)$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Variation of *ECT*, Chip Thickness and f_z/f_{z0} with *ar*/*D*

	Face Milling				End Milling (straight)			
ar/*D*	*hm*	f_z/f_{z0}	*ECT*	ECT_0 corrected for f_z/f_{z0}	*hm*	f_z/f_{z0}	*ECT*	ECT_0 corrected for f_z/f_{z0}
1.0000	0.108	1.398	0.411	0.575	0.108	1.000	0.103	0.103
0.9000	0.137	1.107	0.370	0.410	0.122	0.884	0.093	0.082
0.8080	0.146	1.036	0.332	0.344	0.123	0.880	0.083	0.073
0.7360	0.151	1.000	0.303	0.303	0.121	0.892	0.076	0.067
0.6137	0.158	0.958	0.252	0.242	0.116	0.934	0.063	0.059
0.5900	0.159	0.952	0.243	0.231	0.115	0.945	0.061	0.057
0.5000	0.162	0.932	0.206	0.192	0.108	1.000	0.051	0.051
0.2170	0.169	0.897	0.089	0.080	0.076	1.422	0.022	0.032
0.1250	0.170	0.892	0.051	0.046	0.059	1.840	0.013	0.024
0.0625	0.170	0.891	0.026	0.023	0.042	2.574	0.006	0.017
0.0300	0.170	0.890	0.012	0.011	0.029	3.694	0.003	0.011
0.0100	0.170	0.890	0.004	0.004	0.017	6.377	0.001	0.007
0.0010	0.170	0.890	0.002	0.002	0.005	20.135	0.001	0.005

In face milling, the approximate values of $aa/CEL = 0.95$ for lead angle $LA = 0°$ (90° in the metric system); for other values of LA, $aa/CEL = 0.95 \times \sin(LA)$, and $0.95 \times \cos(LA)$ in the metric system.

Example, Face Milling: For a cutter with $D = 250$ mm and $ar = 125$ mm, calculate ECT_F for $f_z = 0.1$, $z = 12$, and $LA = 30$ degrees. First calculate $ar/D = 0.5$, and then use Table 2b and find $ECT_{0F} = 0.2$.

Calculate ECT_F with above formula:

$ECT_F = 0.2 \times (12/8) \times (0.1/0.17) \times 0.95 \times \sin 30 = 0.084$ mm.

End milling: $ECT_E = ECT_{0E} \times (z/2) \times (f_z/0.17) \times (aa/CEL)$,

or if ECT_E is known calculate f_z from:

$f_z = 0.17 \times (ECT_E/ECT_{0E}) \times (2/z)) \times (CEL/aa)$

The approximate values of $aa/CEL = 0.95$ for lead angle $LA = 0°$ (90° in the metric system).

Example, High-speed End Milling: For a cutter with $D = 25$ mm and $ar = 3.125$ mm, calculate ECT_E for $f_z = 0.1$ and $z = 6$. First calculate $ar/D = 0.125$, and then use Table 2b and find $ECT_{0E} = 0.0249$.

Calculate ECT_E with above formula:

$ECT_E = 0.0249 \times (6/2) \times (0.1/0.17) \times 0.95 \times 1 = 0.042$ mm.

Example, High-speed End Milling: For a cutter with $D = 25$ mm and $ar = 0.75$ mm, calculate ECT_E for $f_z = 0.17$ and $z = 2$ and 6. First calculate $ar/D = 0.03$, and then use Table 2b and find $f_z/f_{z0} = 3.694$

Then, $f_z = 3.694 \times 0.17 = 0.58$ mm/tooth and $ECT_E = 0.0119 \times 0.95 = 0.0113$ mm and $0.0357 \times 0.95 = 0.0339$ mm for 2 and 6 teeth respectively. These cutters are marked HS2 and HS6 in Figs. 26a, 26d, and 26e.

Example, High-speed End Milling: For a cutter with $D = 25$ mm and $ar = 0.25$ mm, calculate ECT_E for $f_z = 0.17$ and $z = 2$ and 6. First calculate $ar/D = 0.01$, and then use Table 2b and find $ECT_{0E} = 0.0069$ and 0.0207 for 2 and 6 teeth respectively. When obtaining such small values of *ECT*, there is a great danger to be far on the left side of the *H*-curve, at least when there are only 2 teeth. Doubling the feed would be the solution if cutter design and material permit.

Example, Full Slot Milling: For a cutter with $D = 25$ mm and $ar = 25$ mm, calculate ECT_E for $f_z = 0.17$ and $z = 2$ and 6. First calculate $ar/D = 1$, and then use Table 2b and find $ECT_E =$

Copyright 2004, Industrial Press, Inc., New York, NY

$0.108 \times 0.95 = 0.103$ and $3 \times 0.108 \times 0.95 = 0.308$ for 2 and 6 teeth, respectively. These cutters are marked SL2 and SL6 in Figs. 26a, 26d, and 26e.

Physics behind *hm* and *ECT*, Forces and Tool-life (*T*).— The *ECT* concept for all metal cutting and grinding operations says that the more energy put into the process, by increasing feed/rev, feed/tooth, or cutting speed, the life of the edge decreases. When increasing the number of teeth (keeping everything else constant) the work and the process are subjected to a higher energy input resulting in a higher rate of tool wear.

In high-speed milling when the angle of engagement *AE* is small the contact time is shorter compared to slot milling ($ar/D = 1$) but the chip becomes shorter as well. Maintaining the same chip thickness as in slot milling has the effect that the energy consumption to remove the chip will be different. Hence, maintaining a constant chip thickness is a good measure when calculating cutting forces (keeping speed constant), but not when determining tool wear. Depending on cutting conditions the wear rate can either increase or decrease, this depends on whether cutting occurs on the left or right side of the *H*-curve.

Fig. 26a shows an example of end milling of steel with coated carbide inserts, where cutting speed *V* is plotted versus *ECT* at 5, 15, 45 and 180 minutes tool-lives. Notice that the *ECT* values are independent of *ar/D* or number of teeth or feed/tooth, or whether f_z or f_{z0} is used, as long as the corresponding f_z/f_{z0}-ratio is applied to determine ECT_E. The result is one single curve per tool-life. Had cutting speed been plotted versus f_{z0}, *ar/D*, or *z* values (number of teeth), several curves would be required at each constant tool-life, one for each of these parameters This illustrates the advantage of using the basic parameter *ECT* rather than f_z, or *hm*, or *ar/D* on the horizontal axis.



Fig. 26a. Cutting speed vs. ECT, tool-life plotted, for end milling

Example: The points (HS2, HS6) and (SL2, SL6) on the 45-minute curve in Fig. 26a relate to the previous high-speed and full slot milling examples for 2 and 6 teeth, respectively.

Running a slot at $f_{z0} = 0.17$ mm/tooth ($hm = 0.108$, $ECT_E = 0.103$ mm) with 2 teeth and for a tool-life 45 minutes, the cutting speed should be selected at $V = 340$ m/min at point SL2 and for six teeth ($hm = 0.108$ mm, $ECT_E = 0.308$) at $V = 240$ m/min at point SL6.

When high-speed milling for $ar/D = 0.03$ at $f_z = 3.394 \times 0.17 = 0.58$ mm/tooth = 0.58 mm/tooth, *ECT* is reduced to 0.011 mm ($hm = 0.108$) the cutting speed is 290 m/min to maintain $T = 45$ minutes, point HS2. This point is far to the left of the *H*-curve in Fig.26b, but if the number of teeth is increased to 6 ($ECT_E = 3 \times 0.103 = 0.3090$), the cutting speed is 360 m/min at $T = 45$ minutes and is close to the *H*-curve, point HS6. Slotting data using 6 teeth are on the right of this curve at point SL6, approaching the *G*-curve, but at a lower slotting speed of 240 m/min.

Copyright 2004, Industrial Press, Inc., New York, NY

Depending on the starting f_z value and on the combination of cutter grade - work material, the location of the *H*-curve plays an important role when selecting high-speed end milling data.

Feed Rate and Tool-life in High-speed Milling, Effect of *ECT* and Number of Teeth.— Calculation of feed rate is done using the formulas in previously given:

Feed Rate:

$F_R = z \times f_z \times \text{rpm}$, where $z \times f_z = f$ (feed/rev of cutter). Feed is measured along the feeding direction.

$\text{rpm} = 1000 \times V/3.1416/D$, where D is diameter of cutter.



Fig. 26b. High speed feed rate and cutting speed versus *ar*/*D* at $T = 5, 15, 45$, and 180 minutes



Fig. 26c. High speed feed rate and cutting speed versus *ECT*, *ar*/*D* plotted at $T = 5, 15, 45$, and 180 minutes

Fig. 26b shows the variation of feed rate F_R plotted versus *ar*/*D* for tool-lives 5, 15, 45 and 180 minutes with a 25 mm diameter cutter and 2 teeth. Fig. 26c shows the variation of feed rate F_R when plotted versus *ECT*. In both graphs the corresponding cutting speeds are also plotted. The values for $ar/D = 0.03$ in Fig. 26b correspond to $ECT = 0.011$ in Fig. 26c.

Feed rates have minimum around values of $ar/D = 0.8$ and $ECT = 0.75$ and not along the *H*-curve. This is due to the fact that the f_z/f_{z0} ratio to maintain a mean chip thickness = 0.108 mm changes F_R in a different proportion than the cutting speed.



Fig. 26d. Feed rate versus *ECT* comparison of slot milling ($ar/D = 1$) and high-speed milling at ($ar/D = 0.03$) for 2, 4, and 6 teeth at $T = 45$ minutes

Copyright 2004, Industrial Press, Inc., New York, NY

A comparison of feed rates for full slot (ar/D = 1) and high-speed end milling (ar/D = 0.03 and $f_z = 3.69 \times f_{z0} = 0.628$ mm) for tool-life 45 minutes is shown in Fig. 26d. The points SL2, SL4, SL6 and HS2, HS4, HS6, refer to 2, 4, and 6 teeth (2 to 6 teeth are commonly used in practice). Feed rate is also plotted versus number of teeth z in Fig. 26e, for up to 16 teeth, still at $f_z = 0.628$ mm.

Comparing the effect of using 2 versus 6 teeth in high-speed milling shows that feed rates increase from 5250 mm/min (413 ipm) up to 18000 mm/min (1417ipm) at 45 minutes tool-life. The effect of using 2 versus 6 teeth in full slot milling is that feed rate increases from 1480 mm/min (58 ipm) up to 3230 mm/min (127 ipm) at tool-life 45 minutes. If 16 teeth could be used at $ar/D = 0.03$, the feed rate increases to $F_R = 44700$ mm/min (1760 ipm), and for full slot milling $F_R = 5350$ mm/min (210 ipm).



Fig. 26e. Feed rate versus number of teeth comparison of slot milling ($ar/D = 1$) and high-speed milling at ($ar/D = 0.03$) for 2, 4, and 6 teeth at $T = 45$ minutes

Comparing the feed rates that can be obtained in steel cutting with the one achieved in the earlier referred DARPA investigation, using HSS and carbide cutters milling 6061-T651 and A356-T6 aluminum, it is obvious that aluminium end milling can be run at 3 to 6 times higher feed rates. This requires 3 to 6 times higher spindle speeds (cutter diameter 25 mm, radial depth of cut ar = 12.5 mm, 2 teeth). Had these tests been run with 6 teeth, the feed rates would increase up to 150000-300000 mm/min, when feed/tooth = 3.4 × 0.25 = 0.8 mm/tooth at $ar/D = 0.03$.

Process Econometrics Comparison of High-speed and Slot End Milling .— When making a process econometrics comparison of high-speed milling and slot end milling use the formulas for total cost c_{tot} (*Determination Of Machine Settings And Calculation Of Costs* starting on page 1113). Total cost is the sum of the cost of cutting, tool changing, and tooling:

$$c_{tot} = H_R \times (Dist/F_R) \times (1 + T_V/T)/60$$

where $T_V = T_{RPL} + 60 \times C_E/H_R$ = equivalent tooling-cost time, minutes

T_{RPL} = replacement time for a set of edges or tool for regrinding

C_E = cost per edge(s)

H_R = hourly rate, $

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. 27. compares total cost c_{tot}, using the end milling cutters of the previous examples, for full slot milling with high-speed milling at ar/D =0.03, and versus ECT at T =45 minutes.



Fig. 27. Cost comparison of slot milling (ar/D = 1) and high-speed milling at (ar/D = 0.03) for 2, 4, and 6 teeth at T = 45 minutes

The feed/tooth for slot milling is $f_{z0} = 0.17$ and for high-speed milling at $ar/D = 0.03$ the feed is $f_z = 3.69 \times f_{z0} = 0.628$ mm.

The calculations for total cost are done according to above formula using tooling cost at T_V = 6, 10, and 14 minutes, for z = 2, 4, and 6 teeth respectively. The distance cut is $Dist$ = 1000 mm. Full slot milling costs are,

at feed rate $F_R = 3230$ and $z = 6$

$c_{tot} = 50 \times (1000/3230) \times (1 + 14/45)/60 = \$0.338$ per part

at feed rate F_R =1480 and $z = 2$

$c_{tot} = 50 \times (1000/1480) \times (1 + 6/45)/60 = \$0.638$ per part

High-speed milling costs,

at F_R=18000, $z = 6$

$c_{tot} = 50 \times (1000/18000) \times (1 + 14/45)/60 = \$0.0606$ per part

at F_R= 5250, $z = 2$

$c_{tot} = 50 \times (1000/5250) \times (1 + 6/45)/60 = \$0.180$ per part

The cost reduction using high-speed milling compared to slotting is enormous. For high-speed milling with 2 teeth, the cost for high-speed milling with 2 teeth is 61 percent (0.208/0.338) of full slot milling with 6 teeth (z = 6). The cost for high-speed milling with 6 teeth is 19 percent (0.0638/0.338) of full slot for z = 6.

Aluminium end milling can be run at 3 to 6 times lower costs than when cutting steel. Costs of idle (non-machining) and slack time (waste) are not considered in the example. These data hold for perfect milling conditions such as zero run-out and accurate sharpening of all teeth and edges.

Copyright 2004, Industrial Press, Inc., New York, NY

SCREW MACHINE FEEDS AND SPEEDS

Feeds and Speeds for Automatic Screw Machine Tools.— Approximate feeds and speeds for standard screw machine tools are given in the accompanying table.

Knurling in Automatic Screw Machines.— When knurling is done from the cross slide, it is good practice to feed the knurl gradually to the center of the work, starting to feed when the knurl touches the work and then passing off the center of the work with a quick rise of the cam. The knurl should also dwell for a certain number of revolutions, depending on the pitch of the knurl and the kind of material being knurled. See also *KNURLS AND KNURLING* starting on page 1240.

When two knurls are employed for spiral and diamond knurling from the turret, the knurls can be operated at a higher rate of feed for producing a spiral than they can for producing a diamond pattern. The reason for this is that in the first case the knurls work in the same groove, whereas in the latter case they work independently of each other.

Revolutions Required for Top Knurling.— The depth of the teeth and the feed per revolution govern the number of revolutions required for top knurling from the cross slide. If R is the radius of the stock, d is the depth of the teeth, c is the distance the knurl travels from the point of contact to the center of the work at the feed required for knurling, and r is the radius of the knurl; then

$$c = \sqrt{(R + r)^2 - (R + r - d)^2}$$

For example, if the stock radius R is $\frac{5}{32}$ inch, depth of teeth d is 0.0156 inch, and radius of knurl r is 0.3125 inch, then

$$c = \sqrt{(0.1562 + 0.3125)^2 - (0.1562 + 0.3125 - 0.0156)^2}$$
$$= 0.120 \text{ inch} = \text{cam rise required}$$

Assume that it is required to find the number of revolutions to knurl a piece of brass $\frac{5}{16}$ inch in diameter using a 32 pitch knurl. The included angle of the teeth for brass is 90 degrees, the circular pitch is 0.03125 inch, and the calculated tooth depth is 0.0156 inch. The distance c (as determined in the previous example) is 0.120 inch. Referring to the accompanying table of feeds and speeds, the feed for top knurling brass is 0.005 inch per revolution. The number of revolutions required for knurling is, therefore, 0.120 ÷ 0.005 = 24 revolutions. If conditions permit, the higher feed of 0.008 inch per revolution given in the table may be used, and 15 revolutions are then required for knurling.

Cams for Threading.— The table *Spindle Revolutions and Cam Rise for Threading* on page 1134 gives the revolutions required for threading various lengths and pitches and the corresponding rise for the cam lobe. To illustrate the use of this table, suppose a set of cams is required for threading a screw to the length of $\frac{3}{8}$ inch in a Brown & Sharpe machine. Assume that the spindle speed is 2400 revolutions per minute; the number of revolutions to complete one piece, 400; time required to make one piece, 10 seconds; pitch of the thread, $\frac{1}{32}$ inch or 32 threads per inch. By referring to the table, under 32 threads per inch, and opposite $\frac{3}{8}$ inch (length of threaded part), the number of revolutions required is found to be 15 and the rise required for the cam, 0.413 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Approximate Cutting Speeds and Feeds for Standard Automatic Screw Machine Tools—Brown and Sharpe

Tool	Cut: Width or Depth, Inches	Cut: Dia. of Hole, Inches	Material to be Machined: Brass[a] Feed, Inches per Rev.	Mild or Soft Steel: Feed, Inches per Rev.	Mild or Soft Steel: Surface Speed, Feet per Min. Carbon Tools	Mild or Soft Steel: Surface Speed, Feet per Min. H.S.S. Tools	Tool Steel, 0.80–1.00% C: Feed, Inches per Rev.	Tool Steel, 0.80–1.00% C: Surface Speed, Feet per Min. Carbon Tools	Tool Steel, 0.80–1.00% C: Surface Speed, Feet per Min. H.S.S. Tools
Boring tools	0.005	…	…	0.008	50	110	0.004	30	60
Box tools, roller rest, Single chip finishing	1/32	…	0.012	0.010	70	150	0.005	40	75
	1/16	…	0.010	0.008	70	150	0.004	40	75
	1/8	…	0.008	0.007	70	150	0.003	40	75
	3/16	…	0.008	0.006	70	150	0.002	40	75
	1/4	…	0.006	0.005	70	150	0.0015	40	75
Finishing	0.005	…	0.010	0.010	70	150	0.006	40	75
Center drills	…	Under 1/8	0.003	0.0015	50	110	0.001	30	75
	…	Over 1/8	0.006	0.0035	50	110	0.002	30	75
Cutoff tools, Angular	…	…	0.0015	0.0006	80	150	0.0004	50	85
Cutoff tools, Circular	3/64–1/8	…	0.0035	0.0015	80	150	0.001	50	85
Cutoff tools, Straight	1/16–1/8	…	0.0035	0.0015	80	150	0.001	50	85
Stock diameter under 1/8 in.	…	…	0.002	0.0008	80	150	0.0005	50	85
Dies, Button	…	…	…	…	30	…	…	14	…
Dies, Chaser	…	…	…	…	30	40	…	16	20
Drills, twist cut	…	0.02	0.0014	0.001	40	60	0.0006	30	45
	…	0.04	0.002	0.0014	40	60	0.0008	30	45
	…	1/16	0.004	0.002	40	60	0.0012	30	45
	…	3/32	0.006	0.0025	40	60	0.0016	30	45
	…	1/8	0.009	0.0035	40	75	0.002	30	60
	…	3/16	0.012	0.004	40	75	0.003	30	60
	…	1/4	0.014	0.005	40	75	0.003	30	60
	…	5/16	0.016	0.005	40	75	0.0035	30	60
	…	3/8–5/8	0.016	0.006	40	85	0.004	30	60
Form tools, circular	1/8	…	0.002	0.0009	80	150	0.0006	50	85
	1/4	…	0.002	0.0008	80	150	0.0005	50	85
	3/8	…	0.0015	0.0007	80	150	0.0004	50	85
	1/2	…	0.0012	0.0006	80	150	0.0004	50	85
	5/8	…	0.001	0.0005	80	150	0.0003	50	85
	3/4	…	0.001	0.0005	80	150	0.0003	50	85
	1	…	0.001	0.0004	80	150	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Approximate Cutting Speeds and Feeds for Standard Automatic Screw Machine Tools—Brown and Sharpe *(Continued)*

Tool	Cut: Width or Depth, Inches	Cut: Dia. of Hole, Inches	Material to be Machined: Brass[a] Feed, Inches per Rev.	Mild or Soft Steel: Feed, Inches per Rev.	Mild or Soft Steel: Surface Speed, Feet per Min. Carbon Tools	Mild or Soft Steel: Surface Speed, Feet per Min. H.S.S. Tools	Tool Steel, 0.80–1.00% C: Feed, Inches per Rev.	Tool Steel, 0.80–1.00% C: Surface Speed, Feet per Min. Carbon Tools	Tool Steel, 0.80–1.00% C: Surface Speed, Feet per Min. H.S.S. Tools
Hollow mills and balance turning tools { Turned diam. under 5/32 in. {	1/32	…	0.012	0.010	70	150	0.008	40	85
	1/16	…	0.010	0.009	70	150	0.006	40	85
Hollow mills and balance turning tools { Turned diam. over 5/32 in. {	1/32	…	0.017	0.014	70	150	0.010	40	85
	1/16	…	0.015	0.012	70	150	0.008	40	85
	1/8	…	0.012	0.010	70	150	0.008	40	85
	3/16	…	0.010	0.008	70	150	0.006	40	85
	1/4	…	0.009	0.007	70	150	0.0045	40	85
Knee tools	1/32	…	…	0.010	70	150	0.008	40	85
Knurling tools { Turret {	On	…	0.020	0.015	150	…	0.010	105	…
	Off	…	0.040	0.030	150	…	0.025	105	…
Knurling tools { Side or swing {	…	…	0.004	0.002	150	…	0.002	105	…
	…	…	0.006	0.004	150	…	0.003	105	…
Knurling tools { Top {	…	…	0.005	0.003	150	…	0.002	105	…
	…	…	0.008	0.006	150	…	0.004	105	…
Pointing and facing tools	…	…	0.001	0.0008	70	150	0.0005	40	80
	…	…	0.0025	0.002	70	150	0.0008	40	80
Reamers and bits	0.003 – 0.004	1/8 or less	0.010 – 0.007	0.008 – 0.006	70	105	0.006 – 0.004	40	60
	0.004 – 0.008	1/8 or over	0.010	0.010	70	105	0.006 – 0.008	40	60
Recessing tools { End cut {	…	… {	0.001	0.0006	70	150	0.0004	40	75
	…	…	0.005	0.003	70	150	0.002	40	75
Recessing tools { Inside cut	1/16–1/8	… {	0.0025	0.002	70	105	0.0015	40	60
	…	…	0.0008	0.0006	70	105	0.0004	40	60
Swing tools, forming	1/8	…	0.002	0.0007	70	150	0.0005	40	85
	1/4	…	0.0012	0.0005	70	150	0.0003	40	85
	3/8	…	0.001	0.0004	70	150	0.0002	40	85
	1/2	…	0.0008	0.0003	70	150	0.0002	40	85
Turning, straight and taper[b]	1/32	…	0.008	0.006	70	150	0.0035	40	85
	1/16	…	0.006	0.004	70	150	0.003	40	85
	1/8	…	0.005	0.003	70	150	0.002	40	85
	3/16	…	0.004	0.0025	70	150	0.0015	40	85
Taps	…	…	…	…	25	30	…	12	15

[a] Use maximum spindle speed on machine.

[b] For taper turning use feed slow enough for greatest depth depth of cut.

Copyright 2004, Industrial Press, Inc., New York, NY

Spindle Revolutions and Cam Rise for Threading

Length of Threaded Portion, Inch	Number of Threads per Inch														
	80	72	64	56	48	40	36	32	30	28	24	20	18	16	14
	First Line: Revolutions of Spindle for Threading. Second Line: Rise on Cam for Threading, Inch														
1/16	9.50	9.00	8.50	8.00	6.00	5.50	5.50	5.00	5.00	5.00	3.00	…	…	…	…
	0.107	0.113	0.120	0.129	0.110	0.121	0.134	0.138	0.147	0.157	0.106	…	…	…	…
1/8	14.50	13.50	12.50	11.50	9.00	8.00	7.00	7.00	7.00	6.50	4.50	4.00	3.50	3.50	…
	0.163	0.169	0.176	0.185	0.165	0.176	0.171	0.193	0.205	0.204	0.159	0.170	0.165	0.186	…
3/16	19.50	18.00	16.50	15.00	12.00	10.50	10.00	9.00	8.50	8.50	6.00	5.50	5.00	4.50	4.00
	0.219	0.225	0.232	0.241	0.220	0.231	0.244	0.248	0.249	0.267	0.213	0.234	0.236	0.239	0.243
1/4	24.50	23.508	20.50	18.50	15.00	13.00	12.00	11.00	10.50	10.00	7.50	6.50	6.00	5.50	5.00
	0.276	0.294	0.288	0.297	0.275	0.286	0.293	0.303	0.308	0.314	0.266	0.276	0.283	0.292	0.304
5/16	29.50	27.00	24.50	22.00	18.00	15.50	14.50	13.00	12.50	12.00	9.00	8.00	7.00	6.50	6.00
	0.332	0.338	0.345	0.354	0.340	0.341	0.354	0.358	0.367	0.377	0.319	0.340	0.330	0.345	0.364
3/8	34.50	31.50	28.50	25.50	21.00	18.00	16.50	15.00	14.50	13.50	10.50	9.00	8.50	7.50	7.00
	0.388	0.394	0.401	0.410	0.385	0.396	0.403	0.413	0.425	0.424	0.372	0.383	0.401	0.398	0.425
7/16	39.50	36.00	32.50	29.00	24.00	20.50	19.00	17.00	16.00	15.50	12.00	10.50	9.50	8.50	7.50
	0.444	0.450	0.457	0.466	0.440	0.451	0.464	0.468	0.469	0.487	0.425	0.446	0.448	0.451	0.455
1/2	44.50	40.50	36.50	32.50	27.00	23.00	21.00	19.00	18.00	17.00	13.50	11.50	10.50	9.50	8.50
	0.501	0.506	0.513	0.522	0.495	0.506	0.513	0.523	0.528	0.534	0.478	0.489	0.496	0.504	0.516
9/16	49.50	45.00	40.50	36.00	30.00	25.50	23.50	21.00	20.00	19.00	15.00	13.00	11.50	10.50	9.50
	0.559	0.563	0.570	0.579	0.550	0.561	0.574	0.578	0.587	0.597	0.531	0.553	0.543	0.558	0.577
5/8	54.50	49.50	44.50	39.50	33.00	28.00	25.50	23.00	22.00	20.50	16.50	14.00	13.00	11.50	10.50
	0.613	0.619	0.626	0.635	0.605	0.616	0.623	0.633	0.645	0.644	0.584	0.595	0.614	0.611	0.637
11/16	59.50	54.00	48.50	43.00	36.00	30.50	28.00	25.00	23.50	22.50	18.00	15.50	14.00	12.50	11.00
	0.679	0.675	0.682	0.691	0.660	0.671	0.684	0.688	0.689	0.707	0.638	0.659	0.661	0.664	0.668
3/4	64.50	58.50	52.50	46.50	39.00	33.00	30.00	27.00	25.50	24.00	19.50	16.50	15.00	13.50	12.00
	0.726	0.731	0.738	0.747	0.715	0.726	0.733	0.743	0.748	0.754	0.691	0.701	0.708	0.717	0.728

Copyright 2004, Industrial Press, Inc., New York, NY

Threading cams are often cut on a circular milling attachment. When this method is employed, the number of minutes the attachment should be revolved for each 0.001 inch rise, is first determined. As 15 spindle revolutions are required for threading and 400 for completing one piece, that part of the cam surface required for the actual threading operation equals 15 ÷ 400 = 0.0375, which is equivalent to 810 minutes of the circumference. The total rise, through an arc of 810 minutes is 0.413 inch, so the number of minutes for each 0.001 inch rise equals 810 ÷ 413 = 1.96 or, approximately, two minutes. If the attachment is graduated to read to five minutes, the cam will be fed laterally 0.0025 inch each time it is turned through five minutes of arc.

Practical Points on Cam and Tool Design.— The following general rules are given to aid in designing cams and special tools for automatic screw machines, and apply particularly to Brown and Sharpe machines:

1) Use the highest speeds recommended for the material used that the various tools will stand.

2) Use the arrangement of circular tools best suited for the class of work.

3) Decide on the quickest and best method of arranging the operations before designing the cams.

4) Do not use turret tools for forming when the cross-slide tools can be used to better advantage.

5) Make the shoulder on the circular cutoff tool large enough so that the clamping screw will grip firmly.

6) Do not use too narrow a cutoff blade.

7) Allow 0.005 to 0.010 inch for the circular tools to approach the work and 0.003 to 0.005 inch for the cutoff tool to pass the center.

8) When cutting off work, the feed of the cutoff tool should be decreased near the end of the cut where the piece breaks off.

9) When a thread is cut up to a shoulder, the piece should be grooved or necked to make allowance for the lead on the die. An extra projection on the forming tool and an extra amount of rise on the cam will be needed.

10) Allow sufficient clearance for tools to pass one another.

11) Always make a diagram of the cross-slide tools in position on the work when difficult operations are to be performed; do the same for the tools held in the turret.

12) Do not drill a hole the depth of which is more than 3 times the diameter of the drill, but rather use two or more drills as required. If there are not enough turret positions for the extra drills needed, make provision for withdrawing the drill clear of the hole and then advancing it into the hole again.

13) Do not run drills at low speeds. Feeds and speeds recommended in the table starting on page 1132 should be followed as far as is practicable.

14) When the turret tools operate farther in than the face of the chuck, see that they will clear the chuck when the turret is revolved.

15) See that the bodies of all turret tools will clear the side of the chute when the turret is revolved.

16) Use a balance turning tool or a hollow mill for roughing cuts.

17) The rise on the thread lobe should be reduced so that the spindle will reverse when the tap or die holder is drawn out.

18) When bringing another tool into position after a threading operation, allow clearance before revolving the turret.

19) Make provision to revolve the turret rapidly, especially when pieces are being made in from three to five seconds and when only a few tools are used in the turret. It is sometimes desirable to use two sets of tools.

20) When using a belt-shifting attachment for threading, clearance should be allowed, as it requires extra time to shift the belt.

Copyright 2004, Industrial Press, Inc., New York, NY

21) When laying out a set of cams for operating on a piece that requires to be slotted, cross-drilled or burred, allowance should be made on the lead cam so that the transferring arm can descend and ascend to and from the work without coming in contact with any of the turret tools.

22) Always provide a vacant hole in the turret when it is necessary to use the transferring arm.

23) When designing special tools allow as much clearance as possible. Do not make them so that they will just clear each other, as a slight inaccuracy in the dimensions will often cause trouble.

24) When designing special tools having intricate movements, avoid springs as much as possible, and use positive actions.

Stock for Screw Machine Products.— The amount of stock required for the production of 1000 pieces on the automatic screw machine can be obtained directly from the table *Stock Required for Screw Machine Products*. To use this table, add to the length of the work the width of the cut-off tool blade; then the number of feet of material required for 1000 pieces can be found opposite the figure thus obtained, in the column headed "Feet per 1000 Parts." Screw machine stock usually comes in bars 10 feet long, and in compiling this table an allowance was made for chucking on each bar.

The table can be extended by using the following formula, in which

F = number of feet required for 1000 pieces

L = length of piece in inches

W = width of cut-off tool blade in inches

$$F = (L + W) \times 84$$

The amount to add to the length of the work, or the width of the cut-off tool, is given in the following, which is standard in a number of machine shops:

Diameter of Stock, Inches	Width of Cut-off Tool Blade, Inches
0.000–0.250	0.045
0.251–0.375	0.062
0.376–0.625	0.093
0.626–1.000	0.125
1.001–1.500	0.156

It is sometimes convenient to know the weight of a certain number of pieces, when estimating the price. The weight of round bar stock can be found by means of the following formulas, in which

W = weight in pounds

D = diameter of stock in inches

F = length in feet

For brass stock: $W = D^2 \times 2.86 \times F$

For steel stock: $W = D^2 \times 2.675 \times F$

For iron stock: $W = D^2 \times 2.65 \times F$

Copyright 2004, Industrial Press, Inc., New York, NY

Stock Required for Screw Machine Products

The table gives the amount of stock, in feet, required for 1000 pieces, when the length of the finished part plus the thickness of the cut-off tool blade is known. Allowance has been made for chucking. To illustrate, if length of cut-off tool and work equals 0.140 inch, 11.8 feet of stock is required for the production of 1000 parts.

Length of Piece and Cut-Off Tool	Feet per 1000 Parts	Length of Piece and Cut-Off Tool	Feet per 1000 Parts	Length of Piece and Cut-Off Tool	Feet per 1000 Parts	Length of Piece and Cut-Off Tool	Feet per 1000 Parts
0.050	4.2	0.430	36.1	0.810	68.1	1.380	116.0
0.060	5.0	0.440	37.0	0.820	68.9	1.400	117.6
0.070	5.9	0.450	37.8	0.830	69.7	1.420	119.3
0.080	6.7	0.460	38.7	0.840	70.6	1.440	121.0
0.090	7.6	0.470	39.5	0.850	71.4	1.460	122.7
0.100	8.4	0.480	40.3	0.860	72.3	1.480	124.4
0.110	9.2	0.490	41.2	0.870	73.1	1.500	126.1
0.120	10.1	0.500	42.0	0.880	73.9	1.520	127.7
0.130	10.9	0.510	42.9	0.890	74.8	1.540	129.4
0.140	11.8	0.520	43.7	0.900	75.6	1.560	131.1
0.150	12.6	0.530	44.5	0.910	76.5	1.580	132.8
0.160	13.4	0.540	45.4	0.920	77.3	1.600	134.5
0.170	14.3	0.550	46.2	0.930	78.2	1.620	136.1
0.180	15.1	0.560	47.1	0.940	79.0	1.640	137.8
0.190	16.0	0.570	47.9	0.950	79.8	1.660	139.5
0.200	16.8	0.580	48.7	0.960	80.7	1.680	141.2
0.210	17.6	0.590	49.6	0.970	81.5	1.700	142.9
0.220	18.5	0.600	50.4	0.980	82.4	1.720	144.5
0.230	19.3	0.610	51.3	0.990	83.2	1.740	146.2
0.240	20.2	0.620	52.1	1.000	84.0	1.760	147.9
0.250	21.0	0.630	52.9	1.020	85.7	1.780	149.6
0.260	21.8	0.640	53.8	1.040	87.4	1.800	151.3
0.270	22.7	0.650	54.6	1.060	89.1	1.820	152.9
0.280	23.5	0.660	55.5	1.080	90.8	1.840	154.6
0.290	24.4	0.670	56.3	1.100	92.4	1.860	156.3
0.300	25.2	0.680	57.1	1.120	94.1	1.880	158.0
0.310	26.1	0.690	58.0	1.140	95.8	1.900	159.7
0.320	26.9	0.700	58.8	1.160	97.5	1.920	161.3
0.330	27.7	0.710	59.7	1.180	99.2	1.940	163.0
0.340	28.6	0.720	60.5	1.200	100.8	1.960	164.7
0.350	29.4	0.730	61.3	1.220	102.5	1.980	166.4
0.360	30.3	0.740	62.2	1.240	104.2	2.000	168.1
0.370	31.1	0.750	63.0	1.260	105.9	2.100	176.5
0.380	31.9	0.760	63.9	1.280	107.6	2.200	184.9
0.390	32.8	0.770	64.7	1.300	109.2	2.300	193.3
0.400	33.6	0.780	65.5	1.320	110.9	2.400	201.7
0.410	34.5	0.790	66.4	1.340	112.6	2.500	210.1
0.420	35.3	0.800	67.2	1.360	114.3	2.600	218.5

Copyright 2004, Industrial Press, Inc., New York, NY

Band Saw Blade Selection.— The primary factors to consider in choosing a saw blade are: the pitch, or the number of teeth per inch of blade; the tooth form; and the blade type (material and construction). Tooth pitch selection depends on the size and shape of the work, whereas tooth form and blade type depend on material properties of the workpiece and on economic considerations of the job.



Courtesy of American Saw and Manufacturing Company

The tooth selection chart above is a guide to help determine the best blade pitch for a particular job. The tooth specifications in the chart are standard variable-pitch blade sizes as specified by the Hack and Band Saw Association. The variable-pitch blades listed are designated by two numbers that refer to the approximate maximum and minimum tooth pitch. A 4/6 blade, for example, has a maximum tooth spacing of approximately $\frac{1}{4}$ inch and a minimum tooth spacing of about $\frac{1}{6}$ inch. Blades are available, from most manufacturers, in sizes within about ±10 per cent of the sizes listed.

To use the chart, locate the length of cut in inches on the outside circle of the table (for millimeters use the inside circle) and then find the tooth specification that aligns with the length, on the ring corresponding to the material shape. The length of cut is the distance that any tooth of the blade is in contact with the work as it passes once through the cut. For cutting solid round stock, use the diameter as the length of cut and select a blade from the ring with the solid circle. When cutting angles, channels, I-beams, tubular pieces, pipe, and hollow or irregular shapes, the length of cut is found by dividing the cross-sectional area of the cut by the distance the blade needs to travel to finish the cut. Locate the length of cut on the outer ring (inner ring for mm) and select a blade from the ring marked with the angle, I-beam, and pipe sections.

Example: A 4-inch pipe with a 3-inch inside diameter is to be cut. Select a variable pitch blade for cutting this material.

Copyright 2004, Industrial Press, Inc., New York, NY

The area of the pipe is $\pi/4 \times (4^2 - 3^2) = 5.5$ in.^{2} The blade has to travel 4 inches to cut through the pipe, so the average length of cut is 5.5/4 = 1.4 inches. On the tooth selection wheel, estimate the location of 1.4 inches on the outer ring, and read the tooth specification from the ring marked with the pipe, angle, and I-beam symbols. The chart indicates that a 4/6 variable-pitch blade is the preferred blade for this cut.

Tooth Forms.— Band saw teeth are characterized by a tooth form that includes the shape, spacing (pitch), rake angle, and gullet capacity of the tooth. Tooth form affects the cutting efficiency, noise level, blade life, chip-carrying capacity, and the surface finish quality of the cut. The rake angle, which is the angle between the face of the tooth and a line perpendicular to the direction of blade travel, influences the cutting speed. In general, positive rake angles cut faster. The *standard tooth* form has conventional shape teeth, evenly spaced with deep gullets and a 0° rake angle. Standard tooth blades are used for general-purpose cutting on a wide variety of materials. The *skip tooth* form has shallow, widely spaced teeth arranged in narrow bands and a 0° rake angle. Skip tooth blades are used for cutting soft metals, wood, plastics, and composite materials. The *hook tooth* form is similar to the skip tooth, but has a positive rake angle and is used for faster cutting of large sections of soft metal, wood, and plastics, as well as for cutting some metals, such as cast iron, that form a discontinuous chip. The *variable-tooth* (variable-pitch) form has a conventional tooth shape, but the tips of the teeth are spaced a variable distance (pitch) apart. The variable pitch reduces vibration of the blade and gives smoother cutting, better surface finish, and longer blade life. The *variable positive tooth* form is a variable-pitch tooth with a positive rake angle that causes the blade to penetrate the work faster. The variable positive tooth blade increases production and gives the longest blade life.

Set is the angle that the teeth are offset from the straight line of a blade. The set affects the blade efficiency (i.e., cutting rate), chip-carrying ability, and quality of the surface finish. *Alternate set* blades have adjacent teeth set alternately one to each side. Alternate set blades, which cut faster but with a poorer finish than other blades, are especially useful for rapid rough cutting. A *raker set is* similar to the alternate set, but every few teeth, one of the teeth is set to the center, not to the side (typically every third tooth, but sometimes every fifth or seventh tooth). The raker set pattern cuts rapidly and produces a good surface finish. The *vari-raker set,* or variable raker, is a variable-tooth blade with a raker set. The vari-raker is quieter and produces a better surface finish than a raker set standard tooth blade. *Wavy set* teeth are set in groups, alternately to one side, then to the other. Both wavy set and vari-raker set blades are used for cutting tubing and other interrupted cuts, but the blade efficiency and surface finish produced are better with a vari-raker set blade.

Types of Blades.— The most important band saw blade types are carbon steel, bimetal, carbide tooth, and grit blades made with embedded carbide or diamond. *Carbon steel blades* have the lowest initial cost, but they may wear out faster. Carbon steel blades are used for cutting a wide variety of materials, including mild steels, aluminum, brass, bronze, cast iron, copper, lead, and zinc, as well as some abrasive materials such as cork, fiberglass, graphite, and plastics. *Bimetal blades* are made with a high-speed steel cutting edge that is welded to a spring steel blade back. Bimetal blades are stronger and last longer, and they tend to produce straighter cuts because the blade can be tensioned higher than carbon steel blades. Because bimetal blades last longer, the cost per cut is frequently lower than when using carbon steel blades. Bimetal blades are used for cutting all ferrous and nonferrous metals, a wide range of shapes of easy to moderately machinable material, and solids and heavy wall tubing with moderate to difficult machinability. *Tungsten carbide blades* are similar to bimetal blades but have tungsten carbide teeth welded to the blade back. The welded teeth of carbide blades have greater wear and high-temperature resistance than either carbon steel or bimetal blades and produce less tooth vibration, while giving smoother, straighter, faster, and quieter cuts requiring less feed force. Carbide blades are used on tough alloys such as cobalt, nickel- and titanium-based alloys, and for nonferrous materials such as aluminum castings, fiberglass, and graphite. The *carbide grit blade*

Copyright 2004, Industrial Press, Inc., New York, NY

has tungsten carbide grit metallurgically bonded to either a gulleted (serrated) or toothless steel band. The blades are made in several styles and grit sizes. Both carbide grit and diamond grit blades are used to cut materials that conventional (carbon and bimetal) blades are unable to cut such as: fiberglass, reinforced plastics, composite materials, carbon and graphite, aramid fibers, plastics, cast iron, stellites, high-hardness tool steels, and superalloys.

Band Saw Speed and Feed Rate.— The band speed necessary to cut a particular material is measured in feet per minute (fpm) or in meters per minute (m/min), and depends on material characteristics and size of the workpiece. Typical speeds for a bimetal blade cutting 4-inch material with coolant are given in the speed selection table that follows. For other size materials or when cutting without coolant, adjust speeds according to the instructions at the bottom of the table.



Cutting Rates for Band Saws

The feed or cutting rate, usually measured in square inches or square meters per minute, indicates how fast material is being removed and depends on the speed and pitch of the blade, not on the workpiece material. The graph above, based on material provided by American Saw and Mfg., gives approximate cutting rates (in.^{2}/min) for various variable-pitch blades and cutting speeds. Use the value from the graph as an initial starting value and then adjust the feed based on the performance of the saw. The size and character of the chips being produced are the best indicators of the correct feed force. Chips that are curly, silvery, and warm indicate the best feed rate and band speed. If the chips appear burned and heavy, the feed is too great, so reduce the feed rate, the band speed, or both. If the chips are thin or powdery, the feed rate is too low, so increase the feed rate or reduce the band speed. The actual cutting rate achieved during a cut is equal to the area of the cut divided by the time required to finish the cut. The time required to make a cut is equal to the area of the cut divided by the cutting rate in square inches per minute.

Copyright 2004, Industrial Press, Inc., New York, NY

Bimetal Band Saw Speeds for Cutting 4-Inch Material with Coolant

Material	Category (AISI/SAE)	Speed (fpm)	Speed (m/min)
Aluminum Alloys	1100, 2011, 2017, 2024, 3003, 5052, 5086, 6061, 6063, 6101, 6262, 7075	500	152
Cast Iron	A536 (60-40-18)	360	110
	A47	300	91
	A220 (50005), A536 (80-55-06)	240	73
	A48 (20 ksi)	230	70
	A536 (100-70-03)	185	56
	A48 (40 ksi)	180	55
	A220 (60004)	170	52
	A436 (1B)	150	46
	A220 (70003)	145	44
	A436 (2)	140	43
	A220 (80002), A436 (2B)	125	38
	A536 (120-90-02)	120	37
	A220 (90001), A48 (60 ksi)	100	30
	A439 (D-2)	80	24
	A439 (D-2B)	60	18
Cobalt	WF-11	65	20
	Astroloy M	60	18
Copper	356, 360	450	137
	353	400	122
	187, 1452	375	114
	380, 544	350	107
	173, 932, 934	315	96
	330, 365	285	87
	623, 624	265	81
	230, 260, 272, 280, 464, 632, 655	245	75
	101, 102, 110, 122, 172, 17510, 182, 220, 510, 625, 706, 715	235	72
	630	230	70
	811	215	66
Iron Base Super Alloy	Pyromet X-15	120	37
	A286, Incoloy 800 and 801	90	27
Magnesium	AZ31B	900	274
Nickel	Nickel 200, 201, 205	85	26
Nickel Alloy	Inconel 625	100	30
	Incoloy 802, 804	90	27
	Monel R405	85	26
	20CB3	80	24
	Monel 400, 401	75	23
	Hastelloy B, B2, C, C4, C22, C276, F, G, G2, G3, G30, N, S, W, X, Incoloy 825, 926, Inconel 751, X750, Waspaloy	70	21
	Monel K500	65	20
	Incoloy 901, 903, Inconel 600, 718, Ni-Span-C902, Nimonic 263, Rene 41, Udimet 500	60	18
	Nimonic 75	50	15
Stainless Steel	416, 420	190	58
	203EZ, 430, 430F, 4302	150	46
	303, 303PB, 303SE, 410, 440F, 30323	140	43
	304	120	37
	414, 30403	115	35
	347	110	34
	316, 31603	100	30
	Greek Ascoloy	95	29
	18-18-2, 309, Ferralium	90	27
	15-5PH, 17-4PH, 17-7PH, 2205, 310, AM350, AM355, Custom 450, Custom 455, PH13-8Mo, PH14-8Mo, PH15-7Mo	80	24
	22-13-5, Nitronic 50, 60	60	18

Copyright 2004, Industrial Press, Inc., New York, NY

Bimetal Band Saw Speeds for Cutting 4-Inch Material with Coolant *(Continued)*

Material	Category (AISI/SAE)	Speed (fpm)	Speed (m/min)
Steel	12L14	425	130
	1213, 1215	400	122
	1117	340	104
	1030	330	101
	1008, 1015, 1020, 1025	320	98
	1035	310	94
	1018, 1021, 1022, 1026, 1513, A242 Cor-Ten A	300	91
	1137	290	88
	1141, 1144, 1144 Hi Stress	280	85
	41L40	275	84
	1040, 4130, A242 Cor-Ten B, (A36 Shapes)	270	82
	1042, 1541, 4140, 4142	250	76
	8615, 8620, 8622	240	73
	W-1	225	69
	1044, 1045, 1330, 4340, E4340, 5160, 8630	220	67
	1345, 4145, 6150	210	64
	1060, 4150, 8640, A-6, O-1, S-1	200	61
	H-11, H-12, H-13, L-6, O-6	190	58
	1095	185	56
	A-2	180	55
	E9310	175	53
	300M, A-10, E52100, HY-80, HY-100	160	49
	S-5	140	43
	S-7	125	38
	M-1	110	34
	HP 9-4-20, HP 9-4-25	105	32
	M-2, M-42, T1	100	30
	D-2	90	27
	T-15	70	21
Titanium	Pure, Ti-3Al-8V-6Cr-4Mo-4Z, Ti-8Mo-8V-2Fe-3Al	80	24
	Ti-2Al-11Sn-5Zr-1Mo, Ti-5Al-2.5Sn, Ti-6Al-2Sn-4Zr-2Mo	75	23
	Ti-6Al-4V	70	21
	Ti-7Al-4Mo, Ti-8Al-1Mo-1V	65	20

The speed figures given are for 4-in. material (length of cut) using a 3/4 variable-tooth bimetal blade and cutting fluid. For cutting dry, reduce speed 30–50%; for carbon steel band saw blades, reduce speed 50%. For other cutting lengths: increase speed 15% for 1/4-in. material (10/14 blade); increase speed 12% for 3/4-in. material (6/10 blade); increase speed 10% for 1 1/4-in. material (4/6 blade); decrease speed 12% for 8-in. material (2/3 blade).

Table data are based on material provided by LENOX Blades, American Saw & Manufacturing Co.

Example: Find the band speed, the cutting rate, and the cutting time if the 4-inch pipe of the previous example is made of 304 stainless steel.

The preceding blade speed table gives the band speed for 4-inch 304 stainless steel as 120 fpm (feet per minute). The average length of cut for this pipe (see the previous example) is 1.4 inches, so increase the band saw speed by about 10 per cent (see footnote on) to 130 fpm to account for the size of the piece. On the cutting rate graph above, locate the point on the 4/6 blade line that corresponds to the band speed of 130 fpm and then read the cutting rate from the left axis of the graph. The cutting rate for this example is approximately 4 in.^{2}/min. The cutting time is equal to the area of the cut divided by the cutting rate, so cutting time = 5.5/4 = 1.375 minutes.

Band Saw Blade Break-In.— A new band saw blade must be broken in gradually before it is allowed to operate at its full recommended feed rate. Break-in relieves the blade of residual stresses caused by the manufacturing process so that the blade retains its cutting ability longer. Break-in requires starting the cut at the material cutting speed with a low feed rate and then gradually increasing the feed rate over time until enough material has been cut. A blade should be broken in with the material to be cut.

Copyright 2004, Industrial Press, Inc., New York, NY

To break in a new blade, first set the band saw speed at the recommended cutting speed for the material and start the first cut at the feed indicated on the starting feed rate graph below. After the saw has penetrated the work to a distance equal to the width of the blade, increase the feed slowly. When the blade is about halfway through the cut, increase the feed again slightly and finish the cut without increasing the feed again. Start the next and each successive cut with the same feed rate that ended the previous cut, and increase the feed rate slightly again before the blade reaches the center of the cut. Repeat this procedure until the area cut by the new blade is equal to the total area required as indicated on the graph below. At the end of the break-in period, the blade should be cutting at the recommended feed rate, otherwise adjusted to that rate.





Cutting Fluids for Machining

The goal in all conventional metal-removal operations is to raise productivity and reduce costs by machining at the highest practical speed consistent with long tool life, fewest rejects, and minimum downtime, and with the production of surfaces of satisfactory accuracy and finish. Many machining operations can be performed "dry," but the proper application of a cutting fluid generally makes possible: higher cutting speeds, higher feed rates, greater depths of cut, lengthened tool life, decreased surface roughness, increased dimensional accuracy, and reduced power consumption. Selecting the proper cutting fluid for a specific machining situation requires knowledge of fluid functions, properties, and limitations. Cutting fluid selection deserves as much attention as the choice of machine tool, tooling, speeds, and feeds.

To understand the action of a cutting fluid it is important to realize that almost all the energy expended in cutting metal is transformed into heat, primarily by the deformation of the metal into the chip and, to a lesser degree, by the friction of the chip sliding against the tool face. With these factors in mind it becomes clear that the primary functions of any cut-

Copyright 2004, Industrial Press, Inc., New York, NY

ting fluid are: cooling of the tool, workpiece, and chip; reducing friction at the sliding contacts; and reducing or preventing welding or adhesion at the contact surfaces, which forms the "built-up edge" on the tool. Two other functions of cutting fluids are flushing away chips from the cutting zone and protecting the workpiece and tool from corrosion.

The relative importance of the functions is dependent on the material being machined, the cutting tool and conditions, and the finish and accuracy required on the part. For example, cutting fluids with greater lubricity are generally used in low-speed machining and on most difficult-to-cut materials. Cutting fluids with greater cooling ability are generally used in high-speed machining on easier-to-cut materials.

Types of Cutting and Grinding Fluids.— In recent years a wide range of cutting fluids has been developed to satisfy the requirements of new materials of construction and new tool materials and coatings.

There are four basic types of cutting fluids; each has distinctive features, as well as advantages and limitations. Selection of the right fluid is made more complex because the dividing line between types is not always clear. Most machine shops try to use as few different fluids as possible and prefer fluids that have long life, do not require constant changing or modifying, have reasonably pleasant odors, do not smoke or fog in use, and, most important, are neither toxic nor cause irritation to the skin. Other issues in selection are the cost and ease of disposal.

The major divisions and subdivisions used in classifying cutting fluids are:

Cutting Oils, including straight and compounded mineral oils plus additives.

Water-Miscible Fluids , including emulsifiable oils; chemical or synthetic fluids; and semichemical fluids.

Gases.

Paste and Solid Lubricants.

Since the cutting oils and water-miscible types are the most commonly used cutting fluids in machine shops, discussion will be limited primarily to these types. It should be noted, however, that compressed air and inert gases, such as carbon dioxide, nitrogen, and Freon, are sometimes used in machining. Paste, waxes, soaps, graphite, and molybdenum disulfide may also be used, either applied directly to the workpiece or as an impregnant in the tool, such as in a grinding wheel.

Cutting Oils.— Cutting oils are generally compounds of mineral oil with the addition of animal, vegetable, or marine oils to improve the wetting and lubricating properties. Sulfur, chlorine, and phosphorous compounds, sometimes called extreme pressure (EP) additives, provide for even greater lubricity. In general, these cutting oils do not cool as well as water-miscible fluids.

Water-Miscible Fluids.— *Emulsions or soluble oils* are a suspension of oil droplets in water. These suspensions are made by blending the oil with emulsifying agents (soap and soaplike materials) and other materials. These fluids combine the lubricating and rust-prevention properties of oil with water's excellent cooling properties. Their properties are affected by the emulsion concentration, with "lean" concentrations providing better cooling but poorer lubrication, and with "rich" concentrations having the opposite effect. Additions of sulfur, chlorine, and phosphorus, as with cutting oils, yield "extreme pressure" (EP) grades.

Chemical fluids are true solutions composed of organic and inorganic materials dissolved in water. Inactive types are usually clear fluids combining high rust inhibition, high cooling, and low lubricity characteristics with high surface tension. Surface-active types include wetting agents and possess moderate rust inhibition, high cooling, and moderate lubricating properties with low surface tension. They may also contain chlorine and/or sulfur compounds for extreme pressure properties.

Semichemical fluids are combinations of chemical fluids and emulsions. These fluids have a lower oil content but a higher emulsifier and surface-active-agent content than

Copyright 2004, Industrial Press, Inc., New York, NY

emulsions, producing oil droplets of much smaller diameter. They possess low surface tension, moderate lubricity and cooling properties, and very good rust inhibition. Sulfur, chlorine, and phosphorus also are sometimes added.

Selection of Cutting Fluids for Different Materials and Operations.— The choice of a cutting fluid depends on many complex interactions including the machinability of the metal; the severity of the operation; the cutting tool material; metallurgical, chemical, and human compatibility; fluid properties, reliability, and stability; and finally cost. Other factors affect results. Some shops standardize on a few cutting fluids which have to serve all purposes. In other shops, one cutting fluid must be used for all the operations performed on a machine. Sometimes, a very severe operating condition may be alleviated by applying the "right" cutting fluid manually while the machine supplies the cutting fluid for other operations through its coolant system. Several voluminous textbooks are available with specific recommendations for the use of particular cutting fluids for almost every combination of machining operation and workpiece and tool material. In general, when experience is lacking, it is wise to consult the material supplier and/or any of the many suppliers of different cutting fluids for advice and recommendations. Another excellent source is the Machinability Data Center, one of the many information centers supported by the U.S. Department of Defense. While the following recommendations represent good practice, they are to serve as a guide only, and it is not intended to say that other cutting fluids will not, in certain specific cases, also be effective.

Steels: Caution should be used when using a cutting fluid on steel that is being turned at a high cutting speed with cemented carbide cutting tools. See *Application of Cutting Fluids to Carbides* later. Frequently this operation is performed dry. If a cutting fluid is used, it should be a soluble oil mixed to a consistency of about 1 part oil to 20 to 30 parts water. A sulfurized mineral oil is recommended for reaming with carbide tipped reamers although a heavy-duty soluble oil has also been used successfully.

The cutting fluid recommended for machining steel with high speed cutting tools depends largely on the severity of the operation. For ordinary turning, boring, drilling, and milling on medium and low strength steels, use a soluble oil having a consistency of 1 part oil to 10 to 20 parts water. For tool steels and tough alloy steels, a heavy-duty soluble oil having a consistency of 1 part oil to 10 parts water is recommended for turning and milling. For drilling and reaming these materials, a light sulfurized mineral-fatty oil is used. For tough operations such as tapping, threading, and broaching, a sulfochlorinated mineral-fatty oil is recommended for tool steels and high-strength steels, and a heavy sulfurized mineral-fatty oil or a sulfochlorinated mineral oil can be used for medium- and low-strength steels. Straight sulfurized mineral oils are often recommended for machining tough, stringy low carbon steels to reduce tearing and produce smooth surface finishes.

Stainless Steel: For ordinary turning and milling a heavy-duty soluble oil mixed to a consistency of 1 part oil to 5 parts water is recommended. Broaching, threading, drilling, and reaming produce best results using a sulfochlorinated mineral-fatty oil.

Copper Alloys: Most brasses, bronzes, and copper are stained when exposed to cutting oils containing active sulfur and chlorine; thus, sulfurized and sulfochlorinated oils should not be used. For most operations a straight soluble oil, mixed to 1 part oil and 20 to 25 parts water is satisfactory. For very severe operations and for automatic screw machine work a mineral-fatty oil is used. A typical mineral-fatty oil might contain 5 to 10 per cent lard oil with the remainder mineral oil.

Monel Metal: When turning this material, an emulsion gives a slightly longer tool life than a sulfurized mineral oil, but the latter aids in chip breakage, which is frequently desirable.

Aluminum Alloys: Aluminum and aluminum alloys are frequently machined dry. When a cutting fluid is used it should be selected for its ability to act as a coolant. Soluble oils mixed to a consistency of 1 part oil to 20 to 30 parts water can be used. Mineral oil-base

Copyright 2004, Industrial Press, Inc., New York, NY

cutting fluids, when used to machine aluminum alloys, are frequently cut back to increase their viscosity so as to obtain good cooling characteristics and to make them flow easily to cover the tool and the work. For example, a mineral-fatty oil or a mineral plus a sulfurized fatty oil can be cut back by the addition of as much as 50 per cent kerosene.

Cast Iron: Ordinarily, cast iron is machined dry. Some increase in tool life can be obtained or a faster cutting speed can be used with a chemical cutting fluid or a soluble oil mixed to consistency of 1 part oil and 20 to 40 parts water. A soluble oil is sometimes used to reduce the amount of dust around the machine.

Magnesium: Magnesium may be machined dry, or with an air blast for cooling. A light mineral oil of low acid content may be used on difficult cuts. Coolants containing water should not be used on magnesium because of the danger of releasing hydrogen caused by reaction of the chips with water. Proprietary water-soluble oil emulsions containing inhibitors that reduce the rate of hydrogen generation are available.

Grinding: Soluble oil emulsions or emulsions made from paste compounds are used extensively in precision grinding operations. For cylindrical grinding, 1 part oil to 40 to 50 parts water is used. Solution type fluids and translucent grinding emulsions are particularly suited for many fine-finish grinding applications. Mineral oil-base grinding fluids are recommended for many applications where a fine surface finish is required on the ground surface. Mineral oils are used with vitrified wheels but are not recommended for wheels with rubber or shellac bonds. Under certain conditions the oil vapor mist caused by the action of the grinding wheel can be ignited by the grinding sparks and explode. To quench the grinding spark a secondary coolant line to direct a flow of grinding oil below the grinding wheel is recommended.

Broaching: For steel, a heavy mineral oil such as sulfurized oil of 300 to 500 Saybolt viscosity at 100 degrees F can be used to provide both adequate lubricating effect and a dampening of the shock loads. Soluble oil emulsions may be used for the lighter broaching operations.

Cutting Fluids for Turning, Milling, Drilling and Tapping.— The following table, *Cutting Fluids Recommended for Machining Operations*, gives specific cutting oil recommendations for common machining operations.

Soluble Oils: Types of oils paste compounds that form emulsions when mixed with water: Soluble oils are used extensively in machining both ferrous and non-ferrous metals when the cooling quality is paramount and the chip-bearing pressure is not excessive. Care should be taken in selecting the proper soluble oil for precision grinding operations. Grinding coolants should be free from fatty materials that tend to load the wheel, thus affecting the finish on the machined part. Soluble coolants should contain rust preventive constituents to prevent corrosion.

Base Oils: Various types of highly sulfurized and chlorinated oils containing inorganic, animal, or fatty materials. This "base stock" usually is "cut back" or blended with a lighter oil, unless the chip-bearing pressures are high, as when cutting alloy steel. Base oils usually have a viscosity range of from 300 to 900 seconds at 100 degrees F.

Mineral Oils: This group includes all types of oils extracted from petroleum such as paraffin oil, mineral seal oil, and kerosene. Mineral oils are often blended with base stocks, but they are generally used in the original form for light machining operations on both free-machining steels and non-ferrous metals. The coolants in this class should be of a type that has a relatively high flash point. Care should be taken to see that they are nontoxic, so that they will not be injurious to the operator. The heavier mineral oils (paraffin oils) usually have a viscosity of about 100 seconds at 100 degrees F. Mineral seal oil and kerosene have a viscosity of 35 to 60 seconds at 100 degrees F.

Copyright 2004, Industrial Press, Inc., New York, NY

Cutting Fluids Recommended for Machining Operations

Material to be Cut	Turning	Milling
Aluminum[a]	Mineral Oil with 10 Per cent Fat (or) Soluble Oil	Soluble Oil (96 Per Cent Water) (or) Mineral Seal Oil (or) Mineral Oil
Alloy Steels[b]	25 Per Cent Sulfur base Oil[b] with 75 Per Cent Mineral Oil	10 Per Cent Lard Oil with 90 Per Cent Mineral Oil
Brass	Mineral Oil with 10 Per Cent Fat	Soluble Oil (96 Per Cent Water)
Tool Steels and Low-carbon Steels	25 Per Cent Lard Oil with 75 Per Cent Mineral Oil	Soluble Oil
Copper	Soluble Oil	Soluble Oil
Monel Metal	Soluble Oil	Soluble Oil
Cast Iron[c]	Dry	Dry
Malleable Iron	Soluble Oil	Soluble Oil
Bronze	Soluble Oil	Soluble Oil
Magnesium[d]	10 Per Cent Lard Oil with 90 Per Cent Mineral Oil	Mineral Seal Oil
Material to be Cut	**Drilling**	**Tapping**
Aluminum[e]	Soluble Oil (75 to 90 Per Cent Water) (or) 10 Per Cent Lard Oil with 90 Per Cent Mineral Oil	Lard Oil (or) Sperm Oil (or) Wool Grease (or) 25 Per Cent Sulfur-base Oil[b] Mixed with Mineral Oil
Alloy Steels[b]	Soluble Oil	30 Per Cent Lard Oil with 70 Per Cent Mineral Oil
Brass	Soluble Oil (75 to 90 Per Cent Water) (or) 30 Per Cent Lard Oil with 70 Per Cent Mineral Oil	10 to 20 Per Cent Lard Oil with Mineral Oil
Tool Steels and Low-carbon Steels	Soluble Oil	25 to 40 Per Cent Lard Oil with Mineral Oil (or) 25 Per Cent Sulfur-base Oil[b] with 75 Per Cent Mineral Oil
Copper	Soluble Oil	Soluble Oil
Monel Metal	Soluble Oil	25 to 40 Per Cent Lard Oil Mixed with Mineral Oil (or) Sulfur-base Oil[b] Mixed with Mineral Oil
Cast Iron[c]	Dry	Dry (or) 25 Per Cent Lard Oil with 75 Per Cent Mineral Oil
Malleable Iron	Soluble Oil	Soluble Oil
Bronze	Soluble Oil	20 Per Cent Lard Oil with 80 Per Cent Mineral Oil
Magnesium[d]	60-second Mineral Oil	20 Per Cent Lard Oil with 80 Per Cent Mineral Oil

[a] In machining aluminum, several varieties of coolants may be used. For rough machining, where the stock removal is sufficient to produce heat, water soluble mixtures can be used with good results to dissipate the heat. Other oils that may be recommended are straight mineral seal oil; a 50–50 mixture of mineral seal oil and kerosene; a mixture of 10 per cent lard oil with 90 per cent kerosene; and a 100-second mineral oil cut back with mineral seal oil or kerosene.

[b] The sulfur-base oil referred to contains 4½ per cent sulfur compound. Base oils are usually dark in color. As a rule, they contain sulfur compounds resulting from a thermal or catalytic refinery process. When so processed, they are more suitable for industrial coolants than when they have had such compounds as flowers of sulfur added by hand. The adding of sulfur compounds by hand to the coolant reservoir is of temporary value only, and the non-uniformity of the solution may affect the machining operation.

[c] A soluble oil or low-viscosity mineral oil may be used in machining cast iron to prevent excessive metal dust.

Copyright 2004, Industrial Press, Inc., New York, NY

[d] When a cutting fluid is needed for machining magnesium, low or nonacid mineral seal or lard oils are recommended. Coolants containing water should not be used because of the fire danger when magnesium chips react with water, forming hydrogen gas.

[e] Sulfurized oils ordinarily are not recommended for tapping aluminum; however, for some tapping operations they have proved very satisfactory, although the work should be rinsed in a solvent right after machining to prevent discoloration.

Application of Cutting Fluids to Carbides.— Turning, boring, and similar operations on lathes using carbides are performed dry or with the help of soluble oil or chemical cutting fluids. The effectiveness of cutting fluids in improving tool life or by permitting higher cutting speeds to be used, is less with carbides than with high-speed steel tools. Furthermore, the effectiveness of the cutting fluid is reduced as the cutting speed is increased. Cemented carbides are very sensitive to sudden changes in temperature and to temperature gradients within the carbide. Thermal shocks to the carbide will cause thermal cracks to form near the cutting edge, which are a prelude to tool failure. An unsteady or interrupted flow of the coolant reaching the cutting edge will generally cause these thermal cracks. The flow of the chip over the face of the tool can cause an interruption to the flow of the coolant reaching the cutting edge even though a steady stream of coolant is directed at the tool. When a cutting fluid is used and frequent tool breakage is encountered, it is often best to cut dry. When a cutting fluid must be used to keep the workpiece cool for size control or to allow it to be handled by the operator, special precautions must be used. Sometimes applying the coolant from the front and the side of the tool simultaneously is helpful. On lathes equipped with overhead shields, it is very effective to apply the coolant from below the tool into the space between the shoulder of the work and the tool flank, in addition to applying the coolant from the top. Another method is not to direct the coolant stream at the cutting tool at all but to direct it at the workpiece above or behind the cutting tool.

The danger of thermal cracking is great when milling with carbide cutters. The nature of the milling operation itself tends to promote thermal cracking because the cutting edge is constantly heated to a high temperature and rapidly cooled as it enters and leaves the workpiece. For this reason, carbide milling operations should be performed dry.

Lower cutting-edge temperatures diminish the danger of thermal cracking. The cutting-edge temperatures usually encountered when reaming with solid carbide or carbide-tipped reamers are generally such that thermal cracking is not apt to occur except when reaming certain difficult-to-machine metals. Therefore, cutting fluids are very effective when used on carbide reamers. Practically every kind of cutting fluid has been used, depending on the job material encountered. For difficult surface-finish problems in holes, heavy duty soluble oils, sulfurized mineral-fatty oils, and sulfochlorinated mineral-fatty oils have been used successfully. On some work, the grade and the hardness of the carbide also have an effect on the surface finish of the hole.

Cutting fluids should be applied where the cutting action is taking place and at the highest possible velocity without causing splashing. As a general rule, it is preferable to supply from 3 to 5 gallons per minute for each single-point tool on a machine such as a turret lathe or automatic. The temperature of the cutting fluid should be kept below 110 degrees F. If the volume of fluid used is not sufficient to maintain the proper temperature, means of cooling the fluid should be provided.

Cutting Fluids for Machining Magnesium.— In machining magnesium, it is the general but not invariable practice in the United States to use a cutting fluid. In other places, magnesium usually is machined dry except where heat generated by high cutting speeds would not be dissipated rapidly enough without a cutting fluid. This condition may exist when, for example, small tools without much heat-conducting capacity are employed on automatics.

The cutting fluid for magnesium should be an anhydrous oil having, at most, a very low acid content. Various mineral-oil cutting fluids are used for magnesium.

Copyright 2004, Industrial Press, Inc., New York, NY

Occupational Exposure To Metal working Fluids

The term *metalworking fluids* (MWFs) describes coolants and lubricants used during the fabrication of products from metals and metal substitutes. These fluids are used to prolong the life of machine tools, carry away debris, and protect or treat the surfaces of the material being processed. MWFs reduce friction between the cutting tool and work surfaces, reduce wear and galling, protect surface characteristics, reduce surface adhesion or welding, carry away generated heat, and flush away swarf, chips, fines, and residues. Table 1 describes the four different classes of metal working fluids:

Table 1. Classes of Metalworking Fluids (MWFs)

MWF	Description	Dilution factor
Straight oil (neat oil or cutting oil)	Highly refined petroleum oils (lubricant-base oils) or other animal, marine, vegetable, or synthetic oils used singly or in combination with or without additives. These are lubricants, or function to improve the finish on the metal cut, and prevent corrosion.	none
Soluble oil (emulsifiable oil)	Combinations of 30% to 85% highly refined, high-viscosity lubricant-base oils and emulsifiers that may include other performance additives. Soluble oils are diluted with water before use at ratios of parts water.	1 part concentrate to 5 to 40 parts water
Semisynthetic	Contain smaller amounts of severely refined lubricant-base oil (5 to 30% in the concentrate), a higher proportion of emulsifiers that may include other performance additives, and 30 to 50% water.	1 part concentrate to 10 to 40 parts water
Synthetic[a]	Contain no petroleum oils and may be water soluble or water dispersible. The simplest synthetics are made with organic and inorganic salts dissolved in water. Offer good rust protection and heat removal but usually have poor lubricating ability. May be formulated with other performance additives. Stable, can be made bioresistant.	1 part concentrate to 10 to 40 parts water

[a] Over the last several decades major changes in the U.S. machine tool industry have increased the consumption of MWFs. Specifically, the use of synthetic MWFs increased as tool and cutting speeds increased.

Occupational Exposures to Metal Working Fluids (MWFs).— Workers can be exposed to MWFs by inhalation of aerosols (mists) or by skin contact resulting in an increased risk of respiratory (lung) and skin disease. Health effects vary based on the type of MWF, route of exposure, concentration, and length of exposure.

Skin contact usually occurs when the worker dips his/her hands into the fluid, floods the machine tool, or handling parts, tools, equipment or workpieces coated with the fluid, without the use of personal protective equipment such as gloves and apron. Skin contact can also result from fluid splashing onto worker from the machine if guarding is absent or inadequate.

Inhalation exposures result from breathing MWF mist or aerosol. The amount of mist generated (and the severity of the exposure) depends on a variety of factors: the type of MWF and its application process; the MWF temperature; the specific machining or grinding operation; the presence of splash guarding; and the effectiveness of the ventilation system. In general, the exposure will be higher if the worker is in close proximity to the machine, the operation involves high tool speeds and deep cuts, the machine is not enclosed, or if ventilation equipment was improperly selected or poorly maintained. In addition, high-pressure and/or excessive fluid application, contamination of the fluid with tramp oils, and improper fluid selection and maintenance will tend to result in higher exposure.

Copyright 2004, Industrial Press, Inc., New York, NY

Each MWF class consists of a wide variety of chemicals used in different combinations and the risk these chemicals pose to workers may vary because of different manufacturing processes, various degrees of refining, recycling, improperly reclaimed chemicals, different degrees of chemical purity, and potential chemical reactions between components.

Exposure to hazardous contaminants in MWFs may present health risks to workers. Contamination may occur from: process chemicals and ancillary lubricants inadvertently introduced; contaminants, metals, and alloys from parts being machined; water and cleaning agents used for routine housekeeping; and, contaminants from other environmental sources at the worksite. In addition, bacterial and fungal contaminants may metabolize and degrade the MWFs to hazardous end-products as well as produce endotoxins.

The improper use of biocides to manage microbial growth may result in potential health risks. Attempts to manage microbial growth solely with biocides may result in the emergence of biocide-resistant strains from complex interactions that may occur among different member species or groups within the population. For example, the growth of one species, or the elimination of one group of organisms may permit the overgrowth of another. Studies also suggest that exposure to certain biocides can cause either allergic or contact dermatitis.

Fluid Selection, Use, and Application.— The MWFs selected should be as nonirritating and nonsensitizing as possible while remaining consistent with operational requirements. Petroleum-containing MWFs should be evaluated for potential carcinogenicity using ASTM Standard E1687-98, "Determining Carcinogenic Potential of Virgin Base Oils in Metalworking Fluids". If soluble oil or synthetic MWFs are used, ASTM Standard E1497-94, "Safe Use of Water-Miscible Metalworking Fluids" should be consulted for safe use guidelines, including those for product selection, storage, dispensing, and maintenance. To minimize the potential for nitrosamine formation, nitrate-containing materials should not be added to MWFs containing ethanolamines.

Many factors influence the generation of MWF mists, which can be minimized through the proper design and operation of the MWF delivery system. ANSI Technical Report B11 TR2-1997, "Mist Control Considerations for the Design, Installation and Use of Machine Tools Using Metalworking Fluids" provides directives for minimizing mist and vapor generation. These include minimizing fluid delivery pressure, matching the fluid to the application, using MWF formulations with low oil concentrations, avoiding contamination with tramp oils, minimizing the MWF flow rate, covering fluid reservoirs and return systems where possible, and maintaining control of the MWF chemistry. Also, proper application of MWFs can minimize splashing and mist generation. Proper application includes: applying MWFs at the lowest possible pressure and flow volume consistent with provisions for adequate part cooling, chip removal, and lubrication; applying MWFs at the tool/workpiece interface to minimize contact with other rotating equipment; ceasing fluid delivery when not performing machining; not allowing MWFs to flow over the unprotected hands of workers loading or unloading parts; and using mist collectors engineered for the operation and specific machine enclosures.

Properly maintained filtration and delivery systems provide cleaner MWFs, reduce mist, and minimize splashing and emissions. Proper maintenance of the filtration and delivery systems includes: the selection of appropriate filters; ancillary equipment such as chip handling operations, dissolved air-flotation devices, belt-skimmers, chillers or plate and frame heat exchangers, and decantation tanks; guard coolant return trenches to prevent dumping of floor wash water and other waste fluids; covering sumps or coolant tanks to prevent contamination with waste or garbage (e.g., cigarette butts, food, etc.); and, keeping the machine(s) clean of debris. Parts washing before machining can be an important part of maintaining cleaner MWFs.

Since all additives will be depleted with time, the MWF and additives concentrations should be monitored frequently so that components and additives can be made up as needed. The MWF should be maintained within the pH and concentration ranges recom-

Copyright 2004, Industrial Press, Inc., New York, NY

mended by the formulator or supplier. MWF temperature should be maintained at the lowest practical level to slow the growth of microorganisms, reduce water losses and changes in viscosity, and–in the case of straight oils–reduce fire hazards.

Fluid Maintenance.— Drums, tanks, or other containers of MWF concentrates should be stored appropriately to protect them from outdoor weather conditions and exposure to low or high temperatures. Extreme temperature changes may destabilize the fluid concentrates, especially in the case of concentrates mixed with water, and cause water to seep into unopened drums encouraging bacterial growth. MWFs should be maintained at as low a temperature as is practical. Low temperatures slow the growth of microorganisms, reduce water losses and change in viscosity, and in the case of straight oils, reduce the fire hazard risks.

To maintain proper MWF concentrations, neither water nor concentrate should be used to top off the system. The MWF mixture should be prepared by first adding the concentrate to the clean water (in a clean container) and then adding the emulsion to that mixture in the coolant tank. MWFs should be mixed just before use; large amounts should not be stored, as they may deteriorate before use.

Personal Protective Clothing: Personal protective clothing and equipment should always be worn when removing MWF concentrates from the original container, mixing and diluting concentrate, preparing additives (including biocides), and adding MWF emulsions, biocides, or other potentially hazardous ingredients to the coolant reservoir. Personal protective clothing includes eye protection or face shields, gloves, and aprons which do not react with but shed MWF ingredients and additives.

System Service: Coolant systems should be regularly serviced, and the machines should be rigorously maintained to prevent contamination of the fluids by tramp oils (e.g., hydraulic oils, gear box oils, and machine lubricants leaking from the machines or total loss slideway lubrication). Tramp oils can destabilize emulsions, cause pumping problems, and clog filters. Tramp oils can also float to the top of MWFs, effectively sealing the fluids from the air, allowing metabolic products such as volatile fatty acids, mercaptols, scatols, ammonia, and hydrogen sulfide are produced by the anaerobic and facultative anaerobic species growing within the biofilm to accumulate in the reduced state.

When replacing the fluids, thoroughly clean all parts of the system to inhibit the growth of microorganisms growing on surfaces. Some bacteria secrete layers of slime that may grow in stringy configurations that resemble fungal growth. Many bacteria secrete polymers of polysaccharide and/or protein, forming a glycocalyx which cements cells together much as mortar holds bricks. Fungi may grow as masses of hyphae forming mycelial mats. The attached community of microorganisms is called a biofilm and may be very difficult to remove by ordinary cleaning procedures.

Biocide Treatment: Biocides are used to maintain the functionality and efficacy of MWFs by preventing microbial overgrowth. These compounds are often added to the stock fluids as they are formulated, but over time the biocides are consumed by chemical and biological demands Biocides with a wide spectrum of biocidal activity should be used to suppress the growth of the widely diverse contaminant population. Only the concentration of biocide needed to meet fluid specifications should be used since overdosing could lead to skin or respiratory irritation in workers, and under-dosing could lead to an inadequate level of microbial control.

Ventilation Systems: The ventilation system should be designed and operated to prevent the accumulation or recirculation of airborne contaminants in the workplace. The ventilation system should include a positive means of bringing in at least an equal volume of air from the outside, conditioning it, and evenly distributing it throughout the exhausted area.

Exhaust ventilation systems function through suction openings placed near a source of contamination. The suction opening or exhaust hood creates and air motion sufficient to overcome room air currents and any airflow generated by the process. This airflow cap-

Copyright 2004, Industrial Press, Inc., New York, NY

tures the contaminants and conveys them to a point where they can either be discharged or removed from the airstream. Exhaust hoods are classified by their position relative to the process as canopy, side draft, down draft or enclosure. ANSI Technical Report B11 TR 2-1997 contains guidelines for exhaust ventilation of machining and grinding operations. Enclosures are the only type of exhaust hood recommended by the ANSI committee. They consist of physical barriers between the process and the worker's environment. Enclosures can be further classified by the extent of the enclosure: close capture (enclosure of the point of operation, total enclosure (enclosure of the entire machine), or tunnel enclosure (continuous enclosure over several machines).

If no fresh make up air is introduced into the plant, air will enter the building through open doors and windows, potentially causing cross-contamination of all process areas. Ideally, all air exhausted from the building should be replaced by tempered air from an uncontaminated location. By providing a slight excess of make up air in relatively clean areas and s slight deficit of make up air in dirty areas, cross-contamination can be reduced. In addition, this air can be channeled directly to operator work areas, providing the cleanest possible work environment. Ideally, this fresh air should be supplied in the form of a low-velocity air shower (<100 ft/min to prevent interference with the exhaust hoods) directly above the worker.

Protective Clothing and Equipment: Engineering controls are used to reduce worker exposure to MWFs. But in the event of airborne exposures that exceed the NIOSH REL or dermal contact with the MWFs, the added protection of chemical protective clothing (CPC) and respirators should be provided. Maintenance staff may also need CPC because their work requires contact with MWFs during certain operations. All workers should be trained in the proper use and care of CPC. After any item of CPC has been in routine use, it should be examined to ensure that its effectiveness has not been compromised.

Selection of the appropriate respirator depends on the operation, chemical components, and airborne concentrations in the worker's breathing zone. Table 2. lists the NIOSH- recommended respiratory protection for workers exposed to MWF aerosol.

Table 2. Respiratory Protection for Workers Exposed to MWF Aerosols*

Concentration of MWF aerosol (mg/m^3)	Minimum respiratory protection[a]
#0.5 mg/m^3 (1 × REL)[b]	No respiratory protection required for healthy workers[c]
#5.0 mg/m^3 (10 × REL)	Any air-purifying, half-mask respirator including a disposable respirator[d,e] equipped with any P- or R-series particulate filter (P95, P99, P100, R95, R99, or R100) number
#12.5 mg/m^3 (25 × REL)	Any powered, air-purifying respirator equipped with a hood or helmet and a HEPA filter[f]

[a] Respirators with higher assigned protection factors (APFs) may be substituted for those with lower APFs [NIOSH 1987a].

[b] APF times the NIOSH REL for total particulate mass. The APF [NIOSH 1987b] is the minimum anticipated level of protection provided by each type of respirator.

[c] See text for recommendations regarding workers with asthma and for other workers affected by MWF aerosols.

[d] A respirator that should be discarded after the end of the manufacturer's recommended period of use or after a noticeable increase in breathing resistance or when physical damage, hygiene considerations, or other warning indicators render the respirator unsuitable for further use.

[e] An APF of 10 is assigned to disposable particulate respirators if they have been properly fitted.

[f] High-efficiency particulate air filter. When organic vapors are a potential hazard during metalworking operations, a combination particulate and organic vapor filter is necessary.

* Only NIOSH/MSHA-approved or NIOSH-approved (effective date July 10, 1995) respiratory equipment should be used.

Copyright 2004, Industrial Press, Inc., New York, NY

MACHINING NONFERROUS METALS AND NON-METALLIC MATERIALS

Nonferrous Metals

Machining Aluminum.— Some of the alloys of aluminum have been machined successfully without any lubricant or cutting compound, but some form of lubricant is desirable to obtain the best results. For many purposes, a soluble cutting oil is good.

Tools for aluminum and aluminum alloys should have larger relief and rake angles than tools for cutting steel. For high-speed steel turning tools the following angles are recommended: relief angles, 14 to 16 degrees; back rake angle, 5 to 20 degrees; side rake angle, 15 to 35 degrees. For very soft alloys even larger side rake angles are sometimes used. High silicon aluminum alloys and some others have a very abrasive effect on the cutting tool. While these alloys can be cut successfully with high-speed-steel tools, cemented carbides are recommended because of their superior abrasion resistance. The tool angles recommended for cemented carbide turning tools are: relief angles, 12 to 14 degrees; back rake angle, 0 to 15 degrees; side rake angle, 8 to 30 degrees.

Cut-off tools and necking tools for machining aluminum and its alloys should have from 12 to 20 degrees back rake angle and the end relief angle should be from 8 to 12 degrees. Excellent threads can be cut with single-point tools in even the softest aluminum. Experience seems to vary somewhat regarding the rake angle for single-point thread cutting tools. Some prefer to use a rather large back and side rake angle although this requires a modification in the included angle of the tool to produce the correct thread contour. When both rake angles are zero, the included angle of the tool is ground equal to the included angle of the thread. Excellent threads have been cut in aluminum with zero rake angle thread-cutting tools using large relief angles, which are 16 to 18 degrees opposite the front side of the thread and 12 to 14 degrees opposite the back side of the thread. In either case, the cutting edges should be ground and honed to a keen edge. It is sometimes advisable to give the face of the tool a few strokes with a hone between cuts when chasing the thread to remove any built-up edge on the cutting edge.

Fine surface finishes are often difficult to obtain on aluminum and aluminum alloys, particularly the softer metals. When a fine finish is required, the cutting tool should be honed to a keen edge and the surfaces of the face and the flank will also benefit by being honed smooth. Tool wear is inevitable, but it should not be allowed to progress too far before the tool is changed or sharpened. A sulphurized mineral oil or a heavy-duty soluble oil will sometimes be helpful in obtaining a satisfactory surface finish. For best results, however, a diamond cutting tool is recommended. Excellent surface finishes can be obtained on even the softest aluminum and aluminum alloys with these tools.

Although ordinary milling cutters can be used successfully in shops where aluminum parts are only machined occasionally, the best results are obtained with coarse-tooth, large helix-angle cutters having large rake and clearance angles. Clearance angles up to 10 to 12 degrees are recommended. When slab milling and end milling a profile, using the peripheral teeth on the end mill, climb milling (also called down milling) will generally produce a better finish on the machined surface than conventional (or up) milling. Face milling cutters should have a large axial rake angle. Standard twist drills can be used without difficulty in drilling aluminum and aluminum alloys although high helix-angle drills are preferred. The wide flutes and high helix-angle in these drills helps to clear the chips. Sometimes split-point drills are preferred. Carbide tipped twist drills can be used for drilling aluminum and its alloys and may afford advantages in some production applications. Ordinary hand and machine taps can be used to tap aluminum and its alloys although spiral-fluted ground thread taps give superior results. Experience has shown that such taps should have a right-hand ground flute when intended to cut right-hand threads and the helix angle should be similar to that used in an ordinary twist drill.

Copyright 2004, Industrial Press, Inc., New York, NY

Machining Magnesium.— Magnesium alloys are readily machined and with relatively low power consumption per cubic inch of metal removed. The usual practice is to employ high cutting speeds with relatively coarse feeds and deep cuts. Exceptionally fine finishes can be obtained so that grinding to improve the finish usually is unnecessary. The horsepower normally required in machining magnesium varies from 0.15 to 0.30 per cubic inch per minute. While this value is low, especially in comparison with power required for cast iron and steel, the total amount of power for machining magnesium usually is high because of the exceptionally rapid rate at which metal is removed.

Carbide tools are recommended for maximum efficiency, although high-speed steel frequently is employed. Tools should be designed so as to dispose of chips readily or without excessive friction, by employing polished chip-bearing surfaces, ample chip spaces, large clearances, and small contact areas. *Keen-edged tools should always be used.*

Feeds and Speeds for Magnesium: Speeds ordinarily range up to 5000 feet per minute for rough- and finish-turning, up to 3000 feet per minute for rough-milling, and up to 9000 feet per minute for finish-milling. For rough-turning, the following combinations of speed in feet per minute, feed per revolution, and depth of cut are recommended: Speed 300 to 600 feet per minute — feed 0.030 to 0.100 inch, depth of cut 0.5 inch; speed 600 to 1000 — feed 0.020 to 0.080, depth of cut 0.4; speed 1000 to 1500 — feed 0.010 to 0.060, depth of cut 0.3; speed 1500 to 2000 — feed 0.010 to 0.040, depth of cut 0.2; speed 2000 to 5000 — feed 0.010 to 0.030, depth of cut 0.15.

Lathe Tool Angles for Magnesium: The true or actual rake angle resulting from back and side rakes usually varies from 10 to 15 degrees. Back rake varies from 10 to 20, and side rake from 0 to 10 degrees. Reduced back rake may be employed to obtain better chip breakage. The back rake may also be reduced to from 2 to 8 degrees on form tools or other broad tools to prevent chatter.

Parting Tools: For parting tools, the back rake varies from 15 to 20 degrees, the front end relief 8 to 10 degrees, the side relief measured perpendicular to the top face 8 degrees, the side relief measured in the plane of the top face from 3 to 5 degrees.

Milling Magnesium: In general, the coarse-tooth type of cutter is recommended. The number of teeth or cutting blades may be one-third to one-half the number normally used; however, the two-blade fly-cutter has proved to be very satisfactory. As a rule, the land relief or primary peripheral clearance is 10 degrees followed by secondary clearance of 20 degrees. The lands should be narrow, the width being about $\frac{3}{64}$ to $\frac{1}{16}$ inch. The rake, which is positive, is about 15 degrees.

For rough-milling and speeds in feet per minute up to 900 — feed, inch per tooth, 0.005 to 0.025, depth of cut up to 0.5; for speeds 900 to 1500 — feed 0.005 to 0.020, depth of cut up to 0.375; for speeds 1500 to 3000 — feed 0.005 to 0.010, depth of cut up to 0.2.

Drilling Magnesium: If the depth of a hole is less than five times the drill diameter, an ordinary twist drill with highly polished flutes may be used. The included angle of the point may vary from 70 degrees to the usual angle of 118 degrees. The relief angle is about 12 degrees. The drill should be kept sharp and the outer corners rounded to produce a smooth finish and prevent burr formation. For deep hole drilling, use a drill having a helix angle of 40 to 45 degrees with large polished flutes of uniform cross-section throughout the drill length to facilitate the flow of chips. A pyramid-shaped "spur" or "pilot point" at the tip of the drill will reduce the "spiraling or run-off."

Drilling speeds vary from 300 to 2000 feet per minute with feeds per revolution ranging from 0.015 to 0.050 inch.

Reaming Magnesium: Reamers up to 1 inch in diameter should have four flutes; larger sizes, six flutes. These flutes may be either parallel with the axis or have a negative helix angle of 10 degrees. The positive rake angle varies from 5 to 8 degrees, the relief angle from 4 to 7 degrees, and the clearance angle from 15 to 20 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

Tapping Magnesium: Standard taps may be used unless Class 3B tolerances are required, in which case the tap should be designed for use in magnesium. A high-speed steel concentric type with a ground thread is recommended. The concentric form, which eliminates the radial thread relief, prevents jamming of chips while the tap is being backed out of the hole. The positive rake angle at the front may vary from 10 to 25 degrees and the "heel rake angle" at the back of the tooth from 3 to 5 degrees. The chamfer extends over two to three threads. For holes up to ¼ inch in diameter, two-fluted taps are recommended; for sizes from ½ to ¾ inch, three flutes; and for larger holes, four flutes. Tapping speeds ordinarily range from 75 to 200 feet per minute, and mineral oil cutting fluid should be used.

Threading Dies for Magnesium: Threading dies for use on magnesium should have about the same cutting angles as taps. Narrow lands should be used to provide ample chip space. Either solid or self-opening dies may be used. The latter type is recommended when maximum smoothness is required. Threads may be cut at speeds up to 1000 feet per minute.

Grinding Magnesium: As a general rule, magnesium is ground dry. The highly inflammable dust should be formed into a sludge by means of a spray of water or low-viscosity mineral oil. Accumulations of dust or sludge should be avoided. For surface grinding, when a fine finish is desirable, a low-viscosity mineral oil may be used.

Machining Zinc Alloy Die-Castings.— Machining of zinc alloy die-castings is mostly done without a lubricant. For particular work, especially deep drilling and tapping, a lubricant such as lard oil and kerosene (about half and half) or a 50-50 mixture of kerosene and machine oil may be used to advantage. A mixture of turpentine and kerosene has been found effective on certain difficult jobs.

Reaming: In reaming, tools with six straight flutes are commonly used, although tools with eight flutes irregularly spaced have been found to yield better results by one manufacturer. Many standard reamers have a land that is too wide for best results. A land about 0.015 inch wide is recommended but this may often be ground down to around 0.007 or even 0.005 inch to obtain freer cutting, less tendency to loading, and reduced heating.

Turning: Tools of high-speed steel are commonly employed although the application of Stellite and carbide tools, even on short runs, is feasible. For steel or Stellite, a positive top rake of from 0 to 20 degrees and an end clearance of about 15 degrees are commonly recommended. Where side cutting is involved, a side clearance of about 4 degrees minimum is recommended. With carbide tools, the end clearance should not exceed 6 to 8 degrees and the top rake should be from 5 to 10 degrees positive. For boring, facing, and other lathe operations, rake and clearance angles are about the same as for tools used in turning.

Machining Monel and Nickel Alloys.— These alloys are machined with high-speed steel and with cemented carbide cutting tools. High-speed steel lathe tools usually have a back rake of 6 to 8 degrees, a side rake of 10 to 15 degrees, and relief angles of 8 to 12 degrees. Broad-nose finishing tools have a back rake of 20 to 25 degrees and an end relief angle of 12 to 15 degrees. In most instances, standard commercial cemented-carbide tool holders and tool shanks can be used which provide an acceptable tool geometry. Honing the cutting edge lightly will help if chipping is encountered.

The most satisfactory tool materials for machining Monel and the softer nickel alloys, such as Nickel 200 and Nickel 230, are M2 and T5 for high-speed steel and crater resistant grades of cemented carbides. For the harder nickel alloys such as K Monel, Permanickel, Duranickel, and Nitinol alloys, the recommended tool materials are T15, M41, M42, M43, and for high-speed steel, M42. For carbides, a grade of crater resistant carbide is recommended when the hardness is less than 300 Bhn, and when the hardness is more than 300 Bhn, a grade of straight tungsten carbide will often work best, although some crater resistant grades will also work well.

Copyright 2004, Industrial Press, Inc., New York, NY

A sulfurized oil or a water-soluble oil is recommended for rough and finish turning. A sulfurized oil is also recommended for milling, threading, tapping, reaming, and broaching. Recommended cutting speeds for Monel and the softer nickel alloys are 70 to 100 fpm for high-speed steel tools and 200 to 300 fpm for cemented carbide tools. For the harder nickel alloys, the recommended speed for high-speed steel is 40 to 70 fpm for a hardness up to 300 Bhn and for a higher hardness, 10 to 20 fpm; for cemented carbides, 175 to 225 fpm when the hardness is less than 300 Bhn and for a higher hardness, 30 to 70 fpm.

Nickel alloys have a high tendency to work harden. To minimize work hardening caused by machining, the cutting tools should be provided with adequate relief angles and positive rake angles. Furthermore, the cutting edges should be kept sharp and replaced when dull to prevent burnishing of the work surface. The depth of cut and feed should be sufficiently large to ensure that the tool penetrates the work without rubbing.

Machining Copper Alloys.— Copper alloys can be machined by tooling and methods similar to those used for steel, but at higher surface speeds. Machinability of copper alloys is discussed in Table 2 on page 556 and Table 3 on page 560. Machinability is based on a rating of 100 per cent for the free-cutting alloy C35000, which machines with small, easily broken chips. As with steels, copper alloys containing lead have the best machining properties, with alloys containing tin, and lead, having machinability ratings of 80 and 70 per cent. Tellurium and sulphur are added to copper alloys to increase machinability with minimum effect on conductivity. Lead additions are made to facilitate machining, as their effect is to produce easily broken chips.

Copper alloys containing silicon, aluminum, manganese and nickel become progressively more difficult to machine, and produce long, stringy chips, the latter alloys having only 20 per cent of the machinability of the free-cutting alloys. Although copper is frequently machined dry, a cooling compound is recommended. Other lubricants that have been used include tallow for drilling, gasoline for turning, and beeswax for threading.

Machining Non-metals

Machining Hard Rubber.— Tools suitable for steel may be used for hard rubber, with no top or side rake angles and 10 to 20 degree clearance angles, of high speed steel or tungsten carbide. Without coolant, surface speeds of about 200 ft/min. are recommended for turning, boring and facing, and may be increased to 300 surface ft/min. with coolant.

Drilling of hard rubber requires high speed steel drills of 35 to 40 degree helix angle to obtain maximum cutting speeds and drill life. Feed rates for drilling range up to 0.015 in/rev. Deep-fluted taps are best for threading hard rubber, and should be 0.002 to 0.005 in. oversize if close tolerances are to be held. Machine oil is used for a lubricant. Hard rubber may be sawn with band saws having 5 to 10 teeth per inch, running at about 3000 ft/min. or cut with abrasive wheels. Use of coolant in grinding rubber gives a smoother finish.

Piercing and blanking of sheet rubber is best performed with the rubber or dies heated. Straightening of the often-distorted blanks may be carried out by dropping them into a pan of hot water.

Formica Machining.— Blanks can be cut from sheets of "Formica" either by a band saw or by trepanning tools in a boring mill or a drill press. To saw blanks, first describe a circle as a guide line, then use a 21-gage 3½-point saw running at a speed of 5000 feet per minute. The saw should be sharp, with a $\frac{1}{64}$-inch set on both sides. In drilling, use an ordinary high-speed drill whose point is ground to an included angle of 55 to 60 degrees. Another method is to grind the drill point slightly off center. The feed must be rapid and caution used to prevent the drill from lagging in its work, and the speed must be 1200 revolutions per minute. For all machining operations on "Formica" gear material, provision must be made in grinding for the tools to clear themselves. For reaming, the entry of the reamer and the reaming process must be rapid. There must not be a lag between the end of the reaming operation and the withdrawal of the reamer. In turning the outside diameter and the sides of blanks,

Copyright 2004, Industrial Press, Inc., New York, NY

the tools must be sharp and have 3 to 5 degrees more rake than is common practice for metal. A cutting speed of 750 feet per minute, which is equal to 720 revolutions per minute on a 4-inch diameter blank, is recommended. The depth of the cut can be $\frac{1}{16}$ to $\frac{1}{8}$ inch, but the feed should be 0.010 inch, regardless of the depth of the cut. Teeth may be cut on a hobbing machine, shaper, or milling machine. The speed of the cutter should be 150 feet per minute. and the feed from 0.023 to 0.040 inch per revolution. It is advisable to back up the blank to prevent fraying or breaking out of the material as the cutter comes through. The backing plates can be economically made from hard wood.

Micarta Machining.— In cutting blanks from sheets of "micarta" a band saw running at a speed of 350 revolutions per minute has been found suitable. The saw should be of the bevel-tooth type, seven teeth to the inch. For large quantities a trepanning tool should be used. In trepanning blanks, the tool should be fed so as to cut part way through all of the "layouts"; then the micarta plate should be turned over, and the cutting completed from the reverse side.

Turning tools should be of high-speed steel cutting at speeds similar to those used for bronze or cast iron. If two cuts are taken, about 0.010 inch of stock should be left for the finishing cut.

Drilling at right angles to the layers is done with a standard drill, which should be backed off sufficiently to provide plenty of clearance. When drilling parallel to layers, a "flat" or "bottom" drill should be used. In rough-drilling, the hole should preferably be drilled partly through the material from each side to prevent possible splitting as the tool protrudes. If this is impracticable, the hole can be drilled all the way through the material, provided the material is "backed up" with wood, stiff cardboard, or any other material that is sufficiently rigid to support the under surface at the point where the drill comes through.

The methods described for drilling apply as well to tapping, except that when the tapping is done parallel to the layers, it is advisable to clamp the material to equalize the stress on the layers and prevent possible splitting.

In milling, a standard tool may be used at a speed and feed corresponding to that used in working bronze or soft steel. The cutting angle of the cutter will give better results if ground with a slight rake.

While there is a wide range of practice as to feeds and speeds in cutting gears on hobbing machines, a hob speed of not less than 140 revolutions per minute, has given satisfaction. In machining gear teeth on a gear shaper, a speed of about 100 to 130 strokes per minute with a fairly fine feed has given good results. Backing-up plates should be used in machining micarta gears.

Ultrasonic Machining.— This method of cutting and engraving hard materials such as glass, precious stones, and carbides uses a transducer (vibratory unit) to obtain the necessary mechanical vibrations needed. The transducer converts the input energy, in this case electrical, into another form of energy, in this case mechanical.

A tool of the required size and shape is made of brass or other soft material and is attached to the transducer. The tool is lowered until it just barely touches the work, and current is applied. At the same time, a slurry of water and fine abrasive, usually boron carbide, is pumped over the work. The tool does not actually touch the work, but the vibrations literally hammer the particles of abrasive into the surface and chip off tiny fragments. Some wear does take place in the tool, but it is very slight and, as it is equally distributed, it does not change the shape. The method is quite commonly applied to cutting designs in the stones of signet rings, but it is also applied to cutting intricately shaped holes in carbide or hardened steel.

Copyright 2004, Industrial Press, Inc., New York, NY

GRINDING FEEDS AND SPEEDS

Grinding data are scarcely available in handbooks, which usually recommend a small range of depths and work speeds at constant wheel speed, including small variations in wheel and work material composition. Wheel life or grinding stiffness are seldom considered.

Grinding parameter recommendations typically range as follows:

- Wheel speeds are usually recommended in the 1200 to 1800 m/min (4000 to 6000 fpm) range, or in rare cases up to 3600 m/min (12000 fpm)
- Work speeds are in the range 20 to 40 m/min (70 to 140 fpm); and, depths of cut of 0.01 to 0.025 mm (0.0004 to 0.001 inch) for roughing, and around 0.005 mm (.0002 in.) for finish grinding.
- Grit sizes for roughing are around 46 to 60 for easy-to-grind materials, and for difficult-to-grind materials higher such as 80 grit. In finishing, a smaller grit size (higher grit number) is recommended. Internal grinding grit sizes for small holes are approximately 100 to 320.
- Specific metal removal rate, *SMRR*, represents the rate of material removal per unit of wheel contact width and are commonly recommended from 200 to 500 mm^3/mm width/min (0.3 to 0.75 in^3/inch width/min).
- Grinding stiffness is a major variable in determining wheel-life and spark-out time. A typical value of system stiffness in outside-diameter grinding, for 10:1 length/diameter ratio, is approximately K_{ST} = 30–50 N/μm. System stiffness K_{ST} is calculated from the stiffness of the part, K_w and the machine and fixtures, K_m. Machine values can be obtained from manufacturers, or can be measured using simple equipment along with the part stiffness.
- Generally a lower wheel hardness (soft wheel) is recommended when the system stiffness is poor or when a better finish is desired.

Basic Rules

The wheel speed V and *equivalent chip thickness* $ECT = SMRR \div V \div 1000$ are the primary parameters that determine wheel-life, forces and surface finish in grinding. The following general rules and recommendations, using *ECT*, are based on extensive laboratory and industry tests both in Europe and USA. The relationships and shapes of curves pertaining to grinding tool-life, grinding time, and cost are similar to those of any metal cutting operation such as turning, milling and drilling.

In turning and milling, the *ECT* theory says that if the product of feed times depth of cut is constant, the tool-life is constant no matter how the depth of cut or feed is varied, provided that the cutting speed and cutting edge length are maintained constant.

In grinding, wheel-life T remains constant for constant cutting speed V, regardless of how depth of cut a_r or work speed V_w are selected as long as the specific metal removal rate $SMMR = V_w \times a_r$ is held constant (neglecting the influence of grinding contact width).

ECT is much smaller in grinding than in milling, ranging from about 0.0001 to 0.001 mm (0.000004 to 0.00004 inch). See the section *MACHINING ECONOMETRICS* starting on page 1093 for a detailed explanation of the role of *ECT* in conventional machining.

Wheel life *T* and *Grinding Ratio*.— A commonly used measure of relative wheel-life in grinding is the *grinding ratio* that is used to compare grindability when varying grinding wheel composition and work material properties under otherwise constant cutting conditions.

The *grinding ratio* is defined as the slope of the wear curve versus metal removal rate: *grinding ratio* = $MRR \div W^*$, where *MRR* is the metal removal rate, and W^* is the volume wheel wear at which the wheel has to be dressed. The grinding ratio is not a measure of wheel-life, but a relationship between *grinding ratio* and wheel-life T can be obtained from

Copyright 2004, Industrial Press, Inc., New York, NY

the formula *grinding ratio* = *SMRR* × *T* ÷ *W**, where *SMRR* (specific metal removal rate) is determined from *MRR* = *SMRR* × *T* or from *ECT* = *SMRR* ÷ *V* ÷ 1000.

Thus, *grinding ratio* = 1000 × *ECT* × *V* × *T* ÷ *W**, and *T* = *grinding ratio* × *W** ÷ (1000 × *ECT* × *V*), provided that the wheel wear criterion *W** is valid for all data combinations.

Example 1: If *W** in one test is found to be 500 mm^3 for *ECT* = 0.00033 mm and *V* = 3600 m/min, and *grinding ratio* = 10, then wheel-life will vary with measured grinding ratios, wheel speed, and *ECT* as follows: *T* =500 × *grinding ratio* ÷ (*V* × *ECT*) = 4.2 minutes.

In the remainder of this section the *grinding ratio* will not used, and wheel-life is expressed in terms of *ECT* or *SMRR* and wheel speed *V*.

***ECT* in Grinding.—** In turning and milling, *ECT* is defined as the volume of chips removed per unit cutting edge length per revolution of the work or cutter. In milling specifically, *ECT* is defined as the ratio of (number of teeth z × feed per tooth f_z × radial depth of cut a_r × and axial depth of cut a_a) and (cutting edge length *CEL* divided by πD), where *D* is the cutter diameter, thus,

$$ECT = \frac{\pi D z f_z a_r a_a}{CEL}$$

In grinding, the same definition of *ECT* applies if we replace the number of teeth with the average number of grits along the wheel periphery, and replace the feed per tooth by the average feed per grit. This definition is not very practical, however, and *ECT* is better defined by the ratio of the specific metal removal rate *SMMR*, and the wheel speed *V*. Thus, *ECT* = 1000 × *SMRR* ÷ *V*. Keeping *ECT* constant when varying *SMRR* requires that the wheel speed must be changed proportionally.

In milling and turning *ECT* can also be redefined in terms of *SMRR* divided by the work and the cutter speeds, respectively, because *SMRR* is proportional to the feed rate F_R.

Work Speed and Depth of Cut Selection: Work speed V_w is determined by dividing *SMMR* by the depth of cut a_r, or by using the graph in Fig. 1.



Fig. 1. Work speed V_w vs. depth of cut a_r

Referring to Fig. 1, for depths of cuts of 0.01 and 0.0025 mm, a specific metal removal rate *SMMR* = 1000 mm^3/mm width/min is achieved at work speeds of 100 and 400 m/min, respectively, and for *SMMR* =100 mm^3/mm width/min at work speeds of 10 and 40 m/min, respectively.

Unfortunately, the common use of low values of work speed (20 to 40 m/min) in finishing cause thermal surface damage, disastrous in critical parts such as aircraft components. As the grains slide across the work they generate surface heat and fatigue-type loading may cause residual tensile stresses and severe surface cracks. Proper finish grinding conditions

Copyright 2004, Industrial Press, Inc., New York, NY

are obtained by increasing the work speed 5 to 10 times higher than the above recommendations indicate. These higher work speeds will create compressive stresses that are not detrimental to the surface. The by-product of higher work speeds is much higher *SMRR* values and thereby much shorter grinding times. Compressive stresses are also obtained by reducing the depth of cut a_r.

Wheel Life Relationships and Optimum Grinding Data.— Figs. 2a, 2b, and 2c show, in three planes, the 3-dimensional variation of wheel-life *T* with wheel speed *V* and *ECT* when grinding a hardened tool steel. Fig. 2a depicts wheel-life versus wheel speed (the *T*–*V* plane) with constant *ECT* appearing as approximately straight lines when plotted in log-log coordinates.

In grinding, the wheel-life variation follows curves similar to those obtained for conventional metal cutting processes, including a bend-off of the Taylor lines (*T*–*V* graph) towards shorter life and lower cutting speeds when a certain maximum life is achieved for each value of *ECT*. In the two other planes (*T*–*ECT*, and *V*–*ECT*) we usually find smooth curves in which the maximum values of wheel-life are defined by points along a curve called the *H*–curve.



Fig. 2a. Taylor lines: *T* vs. *V*, *ECT* plotted for grinding M4 tool steel, hardness Rc 64

Example 2: The variation of $SMRR = V \times ECT \times 1000$ and wheel-life at various wheel speeds can be obtained from Fig. 2a. Using sample values of $ECT = 33 \times 10^{-5}$ mm and $V = 1300$ and 1900 m/min, $SMRR = 1300 \times 33 \times 10^{-5} \times 1000 = 429$, and $1900 \times 33 \times 10^{-5} \times 1000 = 627$ mm³/mm width/min, respectively; the corresponding wheel lives are read off as approximately 70 and 30 minutes, respectively.



Fig. 2b. *T* vs. *ECT*, *V* plotted

Fig. 2b depicts wheel-life *T* versus *ECT* with constant wheel speed *V* shown as curves plotted in log-log coordinates, similar to those for the other cutting operations.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 3: Fig. 2b shows that maximum values of wheel-life occur along the *H*-curve. For the 3 speeds 1800, 2700, and 3600 m/min, maximum wheel lives are approximately 70, 14 and 4 minutes, respectively, at *ECT* around 17×10^{-5} through 20×10^{-5} mm along the *H*-curve. Left and right of the *H*-curve wheel-life is shorter.

Fig. 2c depicts wheel speed *V* versus *ECT* with wheel-life *T* parameter shown as curves in log-log coordinates, similar to those for the other cutting operations, with the characteristic *H*- and *G*-curves.



Fig. 2c. *V* vs. *ECT*, *T* plotted

Optimum grinding data for roughing occur along the *G*-curve, which is determined from the *V*-*ECT* graph by drawing 45-degree lines tangent to the *T*-curves, as shown in Fig. 2c, and drawing a line (the *G*-curve) through the points of tangency on the respective *T*-curves, thus the location and direction of the *G*-curve is determined. Globally optimum data correspond to the *T*-curve for which wheel-life is calculated using the corresponding equivalent tooling-cost time, T_V, calculated from $T_V = T_{RPL} + 60 \times C_E \div H_R$, minutes, where T_{RPL} is the time required to replace wheel, C_E = cost per wheel dressing = wheel cost + cost per dressing, and H_R is the hourly rate.

Minimum cost conditions occur along the *G*-curve; if optimum life T_O was determined at either 10 or 30 minutes then V_O = 1500 and 1100 m/min, respectively, and *ECT* is around $65 - 70 \times 10^{-5}$ mm in both cases. The corresponding optimum values of *SMRR* are $1000 \times 1500 \times 67 \times 10^{-5} = 1000$ and $1000 \times 1100 \times 67 \times 10^{-5} = 740$ mm³/min/mm wheel contact width (1.5 to 1.1in³/in/min).

Using Fig. 1 we find optimum work speeds for depths of cut a_r = 0.01 and 0.005 mm to be V_w = 100 and 75 m/min, and 200 and 150 m/min (330 and 250 fpm, and 660 and 500 fpm) respectively for 10- and 30-minute wheel-life.

These high work speeds are possible using proper dressing conditions, high system stiffness, good grinding fluid quality and wheel composition.

Fig. 3 shows the variation of specific metal removal rate with wheel speed for several materials and a range of *ECT*s at 10- and 30-minutes wheel-life. *ECT* decreases when moving to the left and down along each curve. The two curves for unhardened 1020 steel have the largest values of *SMRR*, and represent the most productive grinding conditions, while the heat resistant alloy Inconel yields the least productive grinding conditions. Each

Copyright 2004, Industrial Press, Inc., New York, NY

branch attains a maximum *SMRR* along the *G*-curve (compare with the same curve in the V–*ECT* graph, Fig. 2c) and a maximum speed region along the *H*-curve. When the *SMRR*-values are lower than the *H*-curve the *ECT* values for each branch decrease towards the bottom of the graph, then the speed for constant wheel-life must be reduced due to the fact that the *ECT* values are to the left of their respective *H*-curves in *V*–*ECT* graphs.



Fig. 3. Specific metal removal rate vs. cutting speed at *T*=10 and 30 minutes wheel life

In the figure, IncX is Inconel; M4, and T-15 are tool steels; and 1020 Unh is unhardened 1020 steel.

Surface Finish, *Ra*.— The finish is improved by decreasing the value of *ECT* as shown in Fig. 4, where *Ra* is plotted versus *ECT* at 3 different wheel lives 1,10 and 30 minutes at constant wheel speed. Because *ECT* is proportional to the depth of cut, a smaller depth of cut is favorable for reducing surface roughness when the work speed is constant.



Fig. 4. Surface finish, *Ra* vs. *ECT*, wheel-life *T* plotted

In Fig. 5, *Ra* is plotted versus wheel-life at 5 different *ECT*'s. Both Figs. 4 and 5 illustrate that a shorter life improves the surface finish, which means that either an increased wheel speed (wheel-life decreases) at constant *ECT*, or a smaller *ECT* at constant speed (wheel-life increases), will result in an improved finish. For a required surface finish, *ECT* and wheel-life have to be selected appropriately in order to also achieve an optimum grinding time or cost. In cylindrical grinding a reduction of side feed f_s improves *Ra* as well.

In terms of specific metal removal rate, reducing *SMRR* will improve the surface finish R_A.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Surface roughness, *Ra* vs. wheel life *T*, *ECT* plotted

Example 4, Specific Metal Removal Rates and Work Speeds in Rough and Finish Grinding: The tabulated values in the following table indicate that a decreasing *ECT* combined with a higher wheel speed for 10 minutes wheel-life will decrease the metal removal rate and thereby increasing the grinding time. This change is accompanied by a better finish in both roughing and finishing operations. Note the high work speeds when finishing.

	Tool Life T = 10 minutes		Roughing Depth a_r = 0.025 mm	Finishing Depth a_r = 0.0025 mm
ECT mm	Wheel speed V_{10} m/min	Removal Rate $SMRR_{10}$ mm³/mm/ min	Work speed V_w m/min	
0.00050	1970	985	39	390
0.00033	2580	850	34	340
0.00017	2910	500	20	200

The grit size, however, is a major parameter. Fig. 6, shows that a high wheel speed, combined with a small grit size, say 320 Mesh, can achieve R_A values as small as 0.03 microns.



Fig. 6. Wheel speed vs. wheel mesh, *Ra* plotted

Spark-out Time.— Fig. 7 shows how spark-out time varies with system stiffness. As with surface finish, when wheel-life is short (high wear rate) the spark-out time decreases.

Equivalent Diameter (Work Conformity) Factor: The difference in curvature of the work and wheel in the contact region, determined by the equivalent diameter or work conformity formula, is an important factor for calculating spark-out time and forces, but has a

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Sparkout time vs. system stiffness, wheel-life T plotted

negligible influence on wheel-life. Therefore, an equivalent diameter, $D_e = D/(1 \pm (D/D_w)$, with the minus sign for internal grinding and the plus sign for external grinding operations, is used to consider the effect of conformity when using internal and external grinding with varying work and wheel diameters. D_e is equal to the wheel diameter in surface grinding (work flat); in internal grinding, the wheel conforms closely to the work and D_e is therefore larger than in external grinding.

Grinding Cutting Forces, Torque and Power.— Formulas to calculate the tangential cutting force, torque and required machining power are found in *Estimating Machining Power* on page 1084, but the values of K_c, specific cutting force or specific energy, are approximately 30 to 40 times higher in grinding than in turning, milling and drilling. This is primarily due to the fact that the *ECT* values in grinding are 1000 to 10000 times smaller, and also due to the negative rake angles of the grit. Average grinding rake angles are around –35 to –45 degrees. K_c for grinding unhardened steel is around 50000 to 70000 N/mm^2 and up to 150000 to 200000 N/mm^2 for hardened steels and heat resistant alloys. The grinding cutting forces are relatively small because the chip area is very small.



Fig. 8. Specific grinding force *Kc* vs. *ECT*; *V* plotted

As in the other metal cutting operations, the forces vary with *ECT* and to a smaller extent with the wheel speed *V*. An example is shown in Fig. 8, where K_c, specific cutting force, is plotted versus *ECT* at wheel speeds between 1000 and 6000 m/min. The material is medium unhardened carbon steel ground by an aluminum oxide wheel. The impact of wheel speed is relatively small (2 to 5% lower with increasing speed).

Copyright 2004, Industrial Press, Inc., New York, NY

Example 5: Find the cutting force when $ECT = 0.00017$ mm, the cutting edge length (width of cut) CEL is 10 mm, and K_c=150000 N/mm^2.

The chip area is $ECT \times CEL = 0.0017$ mm^2. For K_c=150000, the cutting force is $0.0017 \times 150000 = 255$ Newton.

Another difference compared to turning is the influence of the negative rake angles, illustrated by the ratio of F_H/F_C, where F_H is the normal force and F_C the tangential grinding force acting in the wheel speed direction. F_H is much larger than the grinding cutting force, generally F_H/F_C ratio is approximately 2 to 4. An example is shown in Fig. 9, where F_H/F_C, is plotted versus ECT at wheel speeds between 1000 and 6000 m/min, under the same conditions as in Fig. 8.

LIVE GRAPH
Click here to view



Fig. 9. F_H/F_C vs. ECT; cutting speed plotted

In both Fig. 8 and Fig. 9, it is apparent that both K_c and F_H/F_C attain maximum values for given small values of ECT, in this case approximately $ECT = 0.00005$ mm. This fact illustrates that forces and wheel-life are closely linked; for example, wheel speed has a maximum for constant wheel-life at approximately the same values of ECT shown in the two graphs (compare with the trends illustrated in Figs. 2a, 2b, 2c, and 3). As a matter of fact, force relationships obey the same type of relationships as those of wheel-life. Colding's force relationship uses the same 5 constants as the tool life equation, but requires values for the specific cutting force at $ECT = 0.001$ and an additional constant, obtained by a special data base generator. This requires more elaborate laboratory tests, or better, the design of a special test and follow-up program for parts running in the ordinary production.

Grinding Data Selection Including Wheel Life

The first estimate of machine settings is based on dividing work materials into 10 groups, based on grindability, as given in Table 1. Compositions of these work materials are found in the Handbook in the section *STANDARD STEELS* starting on page 438.

Grinding wheel nomenclature is described in *American National Standard Grinding Wheel Markings* starting on page 1179. The wheel compositions are selected according to the grade recommendations in the section *The Selection of Grinding Wheels* starting on page 1180. Grinding fluid recommendations are given in *Cutting Fluids for Machining* starting on page 1143.

Note: Maximum wheel speeds should always be checked using the safety standards in the section *Safe Operating Speeds* starting on page 1209, because the recommendations will sometimes lead to speeds above safety levels.

The material in this section is based on the use of a typical standard wheel composition such as 51-A-46-L-5-V-23, with wheel grade (wheel hardness) = L or above, and mesh (grit size) = 46 or above.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Grindability Groups

Group	Examples
Group 1 Unhardened Steels	
Group 2 Stainless Steels	SAE 30201–30347, 51409–51501
Group 3 Cast Iron	
Group 4 Tool Steels	M1, M8, T1, H, O, L, F, 52100
Group 5 Tool Steels	M2, T2, T5, T6, D2, H41, H42, H43, M50
Group 6 Tool Steels	M3, M4, T3, D7
Group 7 Tool Steels	T15, M15
Group 8 Heat Resistant Steels	Inconel, Rene etc.
Group 9 Carbide Materials	P30 Diamond Wheel
Group 10 Ceramic Materials	

For each grindability group there is one table and 2 graphs (one with Taylor lines and the other with *SMRR* versus wheel speed *V*) that are used to get a first estimate of standardized machine settings, assuming a good system stiffness ($K_{ST} > 30$ N/μm). These data are then calibrated with the users own data in order to refine the estimate and optimize the grinding process, as discussed in *User Calibration of Recommendations*. The recommendations are valid for all grinding processes such as plunge grinding, cylindrical, and surface grinding with periphery or side of wheel, as well as for creep feed grinding.

The grinding data machinability system is based on the basic parameters equivalent chip thickness *ECT*, and wheel speed *V*, and is used to determine specific metal removal rates *SMRR* and wheel-life *T*, including the work speed V_w after the grinding depths for roughing and finishing are specified.

For each material group, the grinding data machinability system consists of *T*–*V* Taylor lines in log-log coordinates for 3 wheel speeds at wheel lives of 1, 10 and 100 minutes wheel-life with 4 different values of equivalent chip thickness *ECT*. The wheel speeds are designated V_1, V_{10}, and V_{100} respectively. In each table the corresponding specific metal removal rates *SMRR* are also tabulated and designated as $SMRR_1$, $SMRR_{10}$ and $SMRR_{100}$ respectively. The user can select any value of *ECT* and interpolate between the Taylor lines. These curves look the same in grinding as in the other metal cutting processes and the slope is set at n = 0.26, so each Taylor line is formulated by $V \times T^{0.26} = C$, where C is a constant tabulated at four *ECT* values, *ECT* = 17, 33, 50 and 75 × 10^{-5} mm, for each material group. Hence, for each value of *ECT*, $V_1 \times 1^{0.26} = V_{10} \times 10^{0.26} = V_{100} \times 100^{0.26} = C$.

Side Feed, Roughing and Finishing.— In cylindrical grinding, the side feed, f_s = C × Width, does not impact on the values in the tables, but on the feed rate F_R, where the fraction of the wheel width C is usually selected for roughing and in finishing operations, as shown in the following table.

Work Material	Roughing, C	Finishing, C
Unhardened Steel	2/3–3/4	1/3–3/8
Stainless Steel	1/2	1/4
Cast Iron	3/4	3/8
Hardened Steel	1/2	1/4

Finishing: The depth of cut in rough grinding is determined by the allowance and usually set at a_r = 0.01 to 0.025 mm. The depth of cut for finishing is usually set at a_r = 0.0025 mm and accompanied by higher wheel speeds in order to improve surface finish. However, the most important criterion for critical parts is to increase the work speed in order to avoid thermal damage and surface cracks. In cylindrical grinding, a reduction of side feed f_s

Copyright 2004, Industrial Press, Inc., New York, NY

improves R_a as well. Small grit sizes are very important when very small finishes are required. See Figs. 4, 5, and 6 for reference.

Terms and Definitions

a_a = depth of cut
a_r = radial depth of cut, mm
C = fraction of grinding wheel width
CEL = cutting edge length, mm
C_U = Taylor constant
D = wheel diameter, mm
$DIST$ = grinding distance, mm
d_w = work diameter, mm
ECT = equivalent chip thickness = $f(a_r, V, V_w, f_s)$, mm

$$= 1 \div (V \div V_w \div a_r + 1 \div f_s) = \frac{V_w f_s (a_r + 1)}{V}$$

= approximately $V_w \times a_r \div V = SMRR \div V \div 1000$
$= z \times f_z \times a_r \times a_a \div CEL \div (\pi D)$ mm
F_R = feed rate, mm/min
$= f_s \times RPM_w$ for cylindrical grinding
$= f_i \times RPM_w$ for plunge (in-feed) grinding
f_i = in-feed in plunge grinding, mm/rev of work
f_s = side feed or engaged wheel width in cylindrical grinding = $C \times Width$ = a_a approximately equal to the cutting edge length CEL
Grinding ratio = $MRR \div W^* = SMRR \times T \div W^* = 1000 \times ECT \times V \times T \div W^*$
MRR = metal removal rate = $SMRR \times T = 1000 \times f_s \times a_r \times V_w$ mm^3/min
$SMRR$ = specific metal removal rate obtained by dividing MRR by the engaged wheel width ($C \times Width$) = $1000 \times a_r \times V_w$ mm^3/mm width/min
Note: 100 mm^3/mm/min = 0.155 in^3/in/min, and 1 in^3/in/min = 645.16 mm^3/mm/min
T, T_U = wheel-life = *Grinding ratio* $\times W \div (1000 \times ECT \times V)$ minutes
t_c = grinding time per pass = $DIST \div F_R$ min
$= DIST \div F_R + t_{sp}$ (min) when spark-out time is included
= # Strokes $\times$ ($DIST \div F_R + t_{sp}$) (min) when spark-out time and strokes are included
t_{sp} = spark-out time, minutes
V, V_U = wheel speed, m/min
V_w, V_{wU} = work speed = $SMRR \div 1000 \div a_r$ m/min
W^* = volume wheel wear, mm^3
$Width$ = wheel width (mm)
RPM = wheel speed = $1000 \times V \div D \div \pi$ rpm
RPM_w = work speed = $1000 \times V_w \div D_w \div \pi$ rpm

Relative Grindability.— An overview of grindability of the data base, which must be based on a constant wheel wear rate, or wheel-life, is demonstrated using 10 minutes wheel-life shown in Table 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Grindability Overview

Material Group	$ECT \times 10^{-5}$	V_{10}	$SMRR_{10}$	V_w Roughing Depth $a_r = 0.025$	V_w *Finishing Depth* $a_r = 0.0025$
1 Unhardened	33	3827	1263	50	500
2 Stainless	33	1080	360	15	150
3 Cast Iron	33	4000	1320	53	530
4 Tool Steel	33	3190	1050	42	420
5 Tool Steel	33	2870	950	38	380
6 Tool Steel	33	2580	850	35	350
7Tool Steel	33	1080	360	15	150
8 Heat resistant	33	1045	345	14	140
9 Carbide with Diamond Wheel	5	$V_{600} = 1200$	$SMRR_{600} = 50$	2	20
10 Ceramics with Diamond Wheel	5	$V_{600} = 411$	$SMRR_{600} = 21$	0.84	84

Procedure to Determine Data.— The following wheel-life recommendations are designed for 4 values of $ECT = 0.00017, 0.00033, 0.00050$ and 0.00075 mm (shown as 17, 33, 50 and 75 in the tables). Lower values of ECT than 0.00010 mm (0.000004 in.) are not recommended as these may lie to the left of the H-curve.

The user selects any one of the ECT values, or interpolates between these, and selects the wheel speed for 10 or 100 minutes life, denoted by V_{10} and V_{100}, respectively. For other desired wheel lives the wheel speed can be calculated from the tabulated Taylor constants C and $n = 0.26$ as follows:

$(V \times T_{(desired)})^{0.26}$ = C, the value of which is tabulated for each ECT value. C is the value of cutting speed V at $T = 1$ minute, hence is the same as for the speed V_1 ($V_1 \times 1\text{^}0.26 = C$)

V_{10}

$$C \div 10^{0.26} = C \div 1.82$$

V_{100}

$$C \div 100^{0.26} = C \div 3.31.$$

Example 6: A tool steel in material group 6 with $ECT = 0.00033$, has constant C= 4690, $V_{10} = 2578$ m/min, and $V_{100} = 1417$ m/min. From this information, find the wheel speed for desired wheel-life of $T = 15$ minutes and $T = 45$ minutes

For $T = 15$ minutes we get $V_{15} = 4690 \div 15^{0.26} = 2319$ m/min (7730 fpm) and for $T = 45$ minutes $V_{45} = 4690 \div 45^{0.26} = 1743$ m/min (5810 fpm).

The Tables are arranged in 3 sections:

1. Speeds V_{10} and V_1 = Constant CST(standard) for 4 ECT values 0.00017, 0.00033, 0.00050 and 0.00075 mm. Values C_U and V_{10U} refer to user calibration of the standard values in each material group, explained in the following.

2. Speeds V_{100} (first row of 3), V_{10} and V_1 (last in row) corresponding to wheel lives 100, 10 and 1 minutes, for 4 ECT values 0.00017, 0.00033, 0.00050 and 0.00075 mm.

3. Specific metal removal rates $SMRR_{100}$, $SMRR_{10}$ and $SMRR_1$ corresponding to wheel lives 100, 10 and 1 minutes, for the 4 ECT values 0.00017, 0.00033, 0.00050, and 0.00075 mm

Copyright 2004, Industrial Press, Inc., New York, NY

The 2 Graphs show: wheel life versus wheel speed in double logarithmic coordinates (Taylor lines); and, *SMRR* versus wheel speed in double logarithmic coordinates for 4 *ECT* values: 0.00017, 0.00033, 0.00050 and 0.00075 mm.

Table 1. Group 1—Unhardened Steels

Tool Life T (min)	*ECT* = 0.00017 mm		*ECT* = 0.00033 mm		*ECT* = 0.00050 mm		*ECT* = 0.00075 mm	
	Constant C = 8925		Constant C = 6965		Constant C = 5385		Constant C = 3885	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	2695	460	2105	695	1625	815	1175	880
10	**4905**	**835**	**3830**	**1265**	**2960**	**1480**	**2135**	**1600**
1	8925	1520	6965	2300	5385	2695	3885	2915



Fig. 1a. *T*–*V*



Fig. 1b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Table 2. Group 2—Stainless Steels SAE 30201 – 30347, SAE 51409 – 51501

Tool Life T (min)	*ECT* = 0.00017 mm		*ECT* = 0.00033 mm		*ECT* = 0.00050 mm		*ECT* = 0.00075 mm	
	Constant C = 2270		Constant C = 1970		Constant C = 1505		Constant C = 1010	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	685	115	595	195	455	225	305	230
10	**1250**	**210**	**1080**	**355**	**825**	**415**	**555**	**415**
1	2270	385	1970	650	1505	750	1010	760



Fig. 2a. *T*–*V*



Fig. 2b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Group 3—Cast Iron

Tool Life T (min)	ECT = 0.00017 mm		ECT = 0.00033 mm		ECT = 0.00050 mm		ECT = 0.00075 mm	
	Constant C = 10710		Constant C = 8360		Constant C = 6465		Constant C = 4665	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	3235	550	2525	835	1950	975	1410	1055
10	**5885**	**1000**	**4595**	**1515**	**3550**	**1775**	**2565**	**1920**
1	10710	1820	8360	2760	6465	3230	4665	3500



Fig. 3a. T–V



Fig. 3b. *SMRR* vs. V, T = 100, 10, 1 minutes

Table 4. Group 4—Tool Steels, M1, M8, T1, H, O, L, F, 52100

Tool Life T (min)	ECT = 0.00017 mm		ECT = 0.00033 mm		ECT = 0.00050 mm		ECT = 0.00075 mm	
	Constant C = 7440		Constant C = 5805		Constant C = 4490		Constant C = 3240	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	2245	380	1755	580	1355	680	980	735
10	**4090**	**695**	**3190**	**1055**	**2465**	**1235**	**1780**	**1335**
1	7440	1265	5805	1915	4490	2245	3240	2430



Fig. 4a. T–V



Fig. 4b. *SMRR* vs. V, T = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Group 5—Tool Steels, M2, T2, T5, T6, D2, D5, H41, H42, H43, M50

Tool Life T (min)	*ECT* = 0.00017 mm		*ECT* = 0.00033 mm		*ECT* = 0.00050 mm		*ECT* = 0.00075 mm	
	Constant C = 6695		Constant C = 5224		Constant C = 4040		Constant C = 2915	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	2020	345	1580	520	1220	610	880	660
10	**3680**	**625**	**2870**	**945**	**2220**	**1110**	**1600**	**1200**
1	6695	1140	5225	1725	4040	2020	2915	2185



Fig. 5a. *T*–*V*



Fig. 5b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Table 6. Group 6—Tool Steels, M3, M4, T3, D7

Tool Life T (min)	*ECT* = 0.00017 mm		*ECT* = 0.00033 mm		*ECT* = 0.00050 mm		*ECT* = 0.00075 mm	
	Constant C = 5290		Constant C = 4690		Constant C = 3585		Constant C = 2395	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	1600	270	1415	465	1085	540	725	540
10	**2910**	**495**	**2580**	**850**	**1970**	**985**	**1315**	**985**
1	5290	900	4690	1550	3585	1795	2395	1795



Fig. 6a. Group 6 Tool Steels *T*–*V*



Fig. 6b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Group 7—Tool Steels, T15, M15

Tool Life T (min)	ECT = 0.00017 mm		ECT = 0.00033 mm		ECT = 0.00050 mm		ECT = 0.00075 mm	
	Constant C = 2270		Constant C = 1970		Constant C = 1505		Constant C = 1010	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	685	115	595	195	455	225	305	230
10	**1250**	**210**	**1080**	**355**	**825**	**415**	**555**	**415**
1	2270	385	1970	650	1505	750	1010	760

LIVE GRAPH Click here to view



Fig. 7a. T–V

LIVE GRAPH Click here to view



Fig. 7b. *SMRR* vs. V, T = 100, 10, 1 minutes

Table 8. Group 8—Heat Resistant Alloys, Inconel, Rene, etc.

Tool Life T (min)	ECT = 0.00017 mm		ECT = 0.00033 mm		ECT = 0.00050 mm		ECT = 0.00075 mm	
	Constant C = 2150		Constant C = 1900		Constant C = 1490		Constant C = 1035	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	650	110	575	190	450	225	315	235
10	**1185**	**200**	**1045**	**345**	**820**	**410**	**570**	**425**
1	2150	365	1900	625	1490	745	1035	780

LIVE GRAPH Click here to view



Fig. 8a. T–V

LIVE GRAPH Click here to view



Fig. 8b. *SMRR* vs. V, T = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Group 9—Carbide Materials, Diamond Wheel

Tool Life T (min)	ECT = 0.00002 mm		ECT = 0.00003 mm		ECT = 0.00005 mm		ECT = 0.00008 mm	
	Constant C = 9030		Constant C = 8030		Constant C = 5365		Constant C = 2880	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
4800	1395	30	1195	35	760	40	390	30
600	2140	45	1855	55	1200	60	625	50
10	4960	100	4415	130	2950	145	1580	125



Fig. 9a. *T*–*V*



Fig. 9b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Table 10. Group 10 — Ceramic Materials Al_2O_3, ZrO_2, SiC, Si_3N_4, Diamond Wheel

Tool Life T (min)	ECT = 0.00002 mm		ECT = 0.00003 mm		ECT = 0.00005 mm		ECT = 0.00008 mm	
	Constant C = 2460		Constant C = 2130		Constant C = 1740		Constant C = 1420	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
4800	395	8	335	10	265	13	210	17
600	595	12	510	15	410	20	330	25
10	1355	25	1170	35	955	50	780	60



Fig. 10a. *T*–*V*



Fig. 10b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

User Calibration of Recommendations

It is recommended to copy or redraw the standard graph for any of the material groups before applying the data calibration method described below. The method is based on the user's own experience and data. The procedure is described in the following and illustrated in Table 11 and Fig. 12.

Only one shop data set is needed to adjust all four Taylor lines as shown below. The required shop data is the user's wheel-life T_U obtained at the user's wheel speed V_U, the user's work speed V_{wU}, and depth of cut a_r.

1) First the user finds out which wheel-life T_U was obtained in the shop, and the corresponding wheel speed V_U, depth of cut a_r and work speed V_{wU}.

2) Second, calculate:

a) $ECT = V_{wU} \times ar \div V_U$

b) the user Taylor constant $C_U = V_U \times T_U^{0.26}$

$V_{10U} = C_U \div 10^{0.26}$

$V_{100U} = C_U \div 100^{0.26}$

3) Thirdly, the user Taylor line is drawn in the pertinent graph. If the user wheel-life T_U is longer than that in the standard graph the speed values will be higher, or if the user wheel-life is shorter the speeds C_U, V_{10U}, V_{100U} will be lower than the standard values C, V_{10} and V_{100}.

The results are a series of lines moved to the right or to the left of the standard Taylor lines for $ECT = 17, 33, 50$ and 75×10^{-5} mm. Each standard table contains the values $C = V_1, V_{10}$, V_{100} and empty spaces for filling out the calculated user values: $C_U = V_U \times T_U^{0.26}$, $V_{10U} = C_U \div 10^{0.26}$ and $V_{100U} = C_U \div 100^{0.26}$.

Example 7: Assume the following test results on a Group 6 material: user speed is V_U = 1800 m/min, wheel-life T_U = 7 minutes, and ECT = 0.00017 mm. The Group 6 data is repeated below for convenience.

Standard Table Data, Group 6 Material

Tool Life T (min)	ECT = 0.00017 mm		ECT = 0.00033 mm		ECT = 0.00050 mm		ECT = 0.00075 mm	
	Constant C = 5290		Constant C = 4690		Constant C = 3585		Constant C = 2395	
	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*	V_T	*SMRR*
100	1600	270	1415	465	1085	540	725	540
10	**2910**	**495**	**2580**	**850**	**1970**	**985**	**1315**	**985**
1	5290	900	4690	1550	3585	1795	2395	1795



Fig. 11a. Group 6 Tool Steels, *T*–*V*



Fig. 11b. *SMRR* vs. *V*, *T* = 100, 10, 1 minutes

Copyright 2004, Industrial Press, Inc., New York, NY

Calculation Procedure

1) Calculate V_{1U}, V_{10U}, V_{100U} and $SMRR_{1U}$, $SMRR_{10U}$, $SMRR_{100U}$ for $ECT = 0.00017$ mm

a) V_{1U} = the user Taylor constant $C_U = V_U \times T_U^{0.26} = 1800 \times 7^{0.26} = 2985$ m/min, and $SMRR_{1U} = 1000 \times 2985 \times 0.00017 = 507$ mm^3/mm width/min

$V_{10U} = C_U \div 10^{0.26} = 2985 \div 10^{0.26} = 1640$ m/min, and $SMRR_{10U} = 1000 \times 1640 \times 0.00017 = 279$ mm^3/mm width/min

$V_{100U} = C_U \div 100^{0.26} = 2985 \div 100^{0.26} = 900$ m/min, and $SMRR_{100U} = 1000 \times 900 \times 0.00017 = 153$ mm^3/mm width/min

2) For $ECT = 0.00017$ mm, calculate the ratio of user Taylor constant to standard Taylor constant from the tables $= C_U \div C_{ST} = C_U \div V_1 = 2985 \div 5290 = 0.564$ (see Table 6 for the value of $C_{ST} = V_1$ at $ECT = 0.00017$ mm).

3) For $ECT = 0.00033$, 0.00050, and 0.00075 mm calculate the user Taylor constants from $C_U = C_{ST} \times$ (the ratio calculated in step 2) $= V_1 \times 0.564 = V_{1U}$. Then, calculate V_{10U} and V_{100U} and $SMRR_{1U}$, $SMRR_{10U}$, $SMRR_{100U}$ using the method in items 1b) and 1c) above.

a) For $ECT = 0.00033$ mm

$V_{1U} = C_U = 4690 \times 0.564 = 2645$ m/min

$V_{10U} = C_U \div 10^{0.26} = 2645 \div 10^{0.26} = 1455$ m/min

$V_{100U} = C_U \div 100^{0.26} = 2645 \div 100^{0.26} = 800$ m/min

$SMRR_{1U}$, $SMRR_{10U}$, and $SMRR_{100U} = 876$, 480, and 264 mm^3/mm width/min

b) For $ECT = 0.00050$ mm

$V_{1U} = C_U = 3590 \times 0.564 = 2025$ m/min

$V_{10U} = C_U \div 10^{0.26} = 2025 \div 10^{0.26} = 1110$ m/min

$V_{100U} = C_U \div 100^{0.26} = 2025 \div 100^{0.26} = 610$ m/min

$SMRR_{1U}$, $SMRR_{10U}$, and $SMRR_{100U} = 1013$, 555, and 305 mm^3/mm width/min

c) For $ECT = 0.00075$ mm

$V_{1U} = C_U = 2395 \times 0.564 = 1350$ m/min

$V_{10U} = C_U \div 10^{0.26} = 1350 \div 10^{0.26} = 740$ m/min

$V_{100U} = C_U \div 100^{0.26} = 1350 \div 100^{0.26} = 405$ m/min

$SMRR_{1U}$, $SMRR_{10U}$, and $SMRR_{100U} = 1013$, 555, and 305 mm^3/mm width/min

Thus, the wheel speed for any desired wheel-life at a given ECT can be calculated from $V = C_U \div T^{0.26}$. For example, at $ECT = 0.00050$ mm and desired tool-life $T = 9$, $V_9 = 2025 \div 9^{0.26} = 1144$ m/min. The corresponding specific metal removal rate is $SMRR = 1000 \times 1144 \times 0.0005 = 572$ mm^3/mm width/min (0.886 in^3/inch width/min).

Table 11. User Calculated Data, Group 6 Material

Tool Life T (min)	$ECT = 0.00017$ mm		$ECT = 0.00033$ mm		$ECT = 0.00050$ mm		$ECT = 0.00075$ mm	
	User Constant $C_U = 2985$		User Constant $C_U = 2645$		User Constant $C_U = 2025$		User Constant $C_U = 1350$	
	V_T	$SMRR$	V_T	$SMRR$	V_T	$SMRR$	V_T	$SMRR$
100	900	153	800	264	610	305	405	305
10	**1640**	**279**	**1455**	**480**	**1110**	**555**	**740**	**555**
1	2985	507	2645	876	2025	1013	1350	1013

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 12. Calibration of user grinding data to standard Taylor Lines
User Input: $V_U = 1800$ m/min, $T_U = 7$ minutes, $ECT = 0.00017$ mm

Optimization.— As shown, a global optimum occurs along the *G*-curve, in selected cases for values of *ECT* around 0.00075, i.e. at high metal removal rates as in other machining operations. It is recommended to use the simple formula for economic life: $T_E = 3 \times T_V$ minutes. $T_V = T_{RPL} + 60 \times C_E \div H_R$, minutes, where T_{RPL} is the time required to replace wheel, C_E = cost per wheel dressing = wheel cost + cost per dressing, and H_R is the hourly rate.

In grinding, values of T_V range between 2 and 5 minutes in conventional grinders, which means that the economic wheel lives range between 6 and 15 minutes indicating higher metal removal rates than are commonly used. When wheels are sharpened automatically after each stroke as in internal grinding, or when grits are continually replaced as in abrasive grinding (machining), T_V may be less than one minute. This translates into wheel lives around one minute in order to achieve minimum cost grinding.

Grinding Cost, Optimization and Process Planning: More accurate results are obtained when the firm collects and systemizes the information on wheel lives, wheel and work speeds, and depths of cut from production runs. A computer program can be used to plan the grinding process and apply the rules and formulas presented in this chapter. A complete grinding process planning program, such as that developed by Colding International Corporation, can be used to optimize machine settings for various feed-speed preferences corresponding wheel-life requirements, minimum cost or maximum production rate grinding, required surface finish and sparkout time; machine and fixture requirements based on the grinding forces, torque and power for sharp and worn grinding wheels; and, detailed time and cost analysis per part and per batch including wheel dressing and wheel changing schedules.

Table 12 summarizes the time and cost savings per batch as it relates to tool life. The sensitivity of how grinding parameters are selected is obvious. Minimum cost conditions yield a 51% reduction of time and 44% reduction of cost, while maximum production rate reduces total time by 65% but, at the expense of heavy wheel consumption (continuous dressing), cost by only 18%.

Table 12. Wheel Life vs. Cost

Preferences	Time per Batch, minutes	Cost per Batch, $		Reduction from Long Life,%	
		Tooling	Total Cost	Time	Cost
Long Life	2995	39	2412	—	—
Economic Life	2433	252	2211	19	8
Minimum Cost	1465	199	1344	51	44
Max Production Rate	1041	1244	1980	65	18

Copyright 2004, Industrial Press, Inc., New York, NY

GRINDING AND OTHER ABRASIVE PROCESSES

Processes and equipment discussed under this heading use abrasive grains for shaping workpieces by means of machining or related methods. Abrasive grains are hard crystals either found in nature or manufactured. The most commonly used materials are aluminum oxide, silicon carbide, cubic boron nitride and diamond. Other materials such as garnet, zirconia, glass and even walnut shells are used for some applications. Abrasive products are used in three basic forms by industry:

a) *Bonded* to form a solid shaped tool such as disks (the basic shape of grinding wheels), cylinders, rings, cups, segments, or sticks to name a few.

b) *Coated* on backings made of paper or cloth, in the form of sheets, strips, or belts.

c) *Loose,* held in some liquid or solid carrier (for lapping, polishing, tumbling), or propelled by centrifugal force, air, or water pressure against the work surface (blast cleaning).

The applications for abrasive processes are multiple and varied. They include:

a) *Cleaning* of surfaces, also the coarse removal of excess material—such as rough off-hand grinding in foundries to remove gates and risers.

b) *Shaping,* such as in form grinding and tool sharpening.

c) *Sizing,* a general objective, but of primary importance in precision grinding.

d) *Surface finish improvement,* either primarily as in lapping, honing, and polishing or as a secondary objective in other types of abrasive processes.

e) *Separating,* as in cut-off or slicing operations.

The main field of application of abrasive processes is in metalworking, because of the capacity of abrasive grains to penetrate into even the hardest metals and alloys. However, the great hardness of the abrasive grains also makes the process preferred for working other hard materials, such as stones, glass, and certain types of plastics. Abrasive processes are also chosen for working relatively soft materials, such as wood, rubber, etc., for such reasons as high stock removal rates, long-lasting cutting ability, good form control, and fine finish of the worked surface.

Grinding Wheels

Abrasive Materials.— In earlier times, only natural abrasives were available. From about the beginning of this century, however, manufactured abrasives, primarily silicon carbide and aluminum oxide, have replaced the natural materials; even natural diamonds have been almost completely supplanted by synthetics. Superior and controllable properties, and dependable uniformity characterize the manufactured abrasives.

Both silicon carbide and aluminum oxide abrasives are very hard and brittle. This brittleness, called friability, is controllable for different applications. Friable abrasives break easily, thus forming sharp edges. This decreases the force needed to penetrate into the work material and the heat generated during cutting. Friable abrasives are most commonly used for precision and finish grinding. Tough abrasives resist fracture and last longer. They are used for rough grinding, snagging, and off-hand grinding.

As a general rule, although subject to variation:

1) Aluminum oxide abrasives are used for grinding plain and alloyed steel in a soft or hardened condition.

2) Silicon carbide abrasives are selected for cast iron, nonferrous metals, and nonmetallic materials.

3) Diamond is the best type of abrasive for grinding cemented carbides. It is also used for grinding glass, ceramics, and hardened tool steel.

Copyright 2004, Industrial Press, Inc., New York, NY

4) Cubic Boron Nitride (CBN) is known by several trade names including Borazon (General Electric Co.), ABN (De Beers), Sho-bon (Showa-Denko), and Elbor (USSR). CBN is a synthetic superabrasive used for grinding hardened steels and wear-resistant superalloys. (See *Cubic Boron Nitride (CBN)* starting on page 1013.) CBN grinding wheels have long lives and can maintain close tolerances with superior surface finishes.

Bond Properties and Grinding Wheel Grades.— The four main types of bonds used for grinding wheels are the vitrified, resinoid, rubber, and metal.

Vitrified bonds are used for more than half of all grinding wheels made, and are preferred because of their strength and other desirable qualities. Being inert, glass-like materials, vitrified bonds are not affected by water or by the chemical composition of different grinding fluids. Vitrified bonds also withstand the high temperatures generated during normal grinding operations. The structure of vitrified wheels can be controlled over a wide range of strength and porosity. Vitrified wheels, however, are more sensitive to impact than those made with organic bonds.

Resinoid bonds are selected for wheels subjected to impact, or sudden loads, or very high operating speeds. They are preferred for snagging, portable grinder uses, or roughing operations. The higher flexibility of this type of bond—essentially a filled thermosetting plastic—helps it withstand rough treatment.

Rubber bonds are even more flexible than the resinoid type, and for that reason are used for producing a high finish and for resisting sudden rises in load. Rubber bonded wheels are commonly used for wet cut-off wheels because of the nearly burr-free cuts they produce, and for centerless grinder regulating wheels to provide a stronger grip and more reliable workpiece control.

Metal bonds are used in CBN and diamond wheels. In metal bonds produced by electrodeposition, a single layer of superabrasive material (diamond or CBN) is bonded to a metal core by a matrix of metal, usually nickel. The process is so controlled that about 30–40 per cent of each abrasive particle projects above the deposited surface, giving the wheel a very aggressive and free-cutting action. With proper use, such wheels have remarkably long lives. When dulled, or worn down, the abrasive can be stripped off and the wheel renewed by a further deposit process. These wheels are also used in electrical discharge grinding and electrochemical grinding where an electrically conductive wheel is needed.

In addition to the basic properties of the various bond materials, each can also be applied in different proportions, thereby controlling the grade of the grinding wheel.

Grinding wheel grades commonly associated with hardness, express the amount of bond material in a grinding wheel, and hence the strength by which the bond retains the individual grains.

During grinding, the forces generated when cutting the work material tend to dislodge the abrasive grains. As the grains get dull and if they don't fracture to resharpen themselves, the cutting forces will eventually tear the grains from their supporting bond. For a "soft" wheel the cutting forces will dislodge the abrasive grains before they have an opportunity to fracture. When a "hard" wheel is used, the situation is reversed. Because of the extra bond in the wheel the grains are so firmly held that they never break loose and the wheel becomes glazed. During most grinding operations it is desirable to have an intermediate wheel where there is a continual slow wearing process composed of both grain fracture and dislodgement.

The grades of the grinding wheels are designated by capital letters used in alphabetical order to express increasing "hardness" from A to Z.

Grinding Wheel Structure.— The individual grains, which are encased and held together by the bond material, do not fill the entire volume of the grinding wheel; the intermediate open space is needed for several functional purposes such as heat dissipation, coolant application, and particularly, for the temporary storage of chips. It follows that the

Copyright 2004, Industrial Press, Inc., New York, NY

spacing of the grains must be greater for coarse grains which cut thicker chips and for large contact areas within which the chips have to be retained on the surface of the wheel before being disposed of. On the other hand, a wide spacing reduces the number of grains that contact the work surface within a given advance distance, thereby producing a coarser finish.

In general, denser structures are specified for grinding hard materials, for high-speed grinding operations, when the contact area is narrow, and for producing fine finishes and/or accurate forms. Wheels with open structure are used for tough materials, high stock removal rates, and extended contact areas, such as grinding with the face of the wheel. There are, however, several exceptions to these basic rules, an important one being the grinding of parts made by powder metallurgy, such as cemented carbides; although they represent one of the hardest industrial materials, grinding carbides requires wheels with an open structure.

Most kinds of general grinding operations, when carried out with the periphery of the wheel, call for medium spacing of the grains. The structure of the grinding wheels is expressed by numerals from 1 to 16, ranging from dense to open. Sometimes, "induced porosity" is used with open structure wheels. This term means that the grinding wheel manufacturer has placed filler material (which later burns out when the wheel is fired to vitrify the bond) in the grinding wheel mix. These fillers create large "pores" between grain clusters without changing the total volume of the "pores" in the grinding wheel. Thus, an A46-H12V wheel and an A46H12VP wheel will contain the same amounts of bond, abrasive, and air space. In the former, a large number of relatively small pores will be distributed throughout the wheel. The latter will have a smaller number of larger pores.

American National Standard Grinding Wheel Markings.— ANSI Standard B74.13-1990" Markings for Identifying Grinding Wheels and Other Bonded Abrasives," applies to grinding wheels and other bonded abrasives, segments, bricks, sticks, hones, rubs, and other shapes that are for removing material, or producing a desired surface or dimension. It does not apply to specialities such as sharpening stones and provides only a standard system of markings. Wheels having the same standard markings but made by different wheel manufacturers may not—and probably will not—produce exactly the same grinding action. This desirable result cannot be obtained because of the impossibility of closely correlating any measurable physical properties of bonded abrasive products in terms of their grinding action.

Symbols for designating diamond and cubic boron wheel compositions are given on page 1204.

Sequence of Markings.— The accompanying illustration taken from ANSI B74.13-1990 shows the makeup of a typical wheel or bonded abrasive marking.

Prefix	1 Abrasive Type	2 Grain Size	3 Grade	4 Structure	5 Bond Type	6 Manufacturer's Record
51	– A	– 36	– L	– 5	– V	– 23

The meaning of each letter and number in this or other markings is indicated by the following complete list.

1) *Abrasive Letters:* The letter (A) is used for aluminum oxide, (C) for silicon carbide, and (Z) for aluminum zirconium. The manufacturer may designate some particular type in any one of these broad classes, by using his own symbol as a prefix (example, 51).

2) *Grain Size:* The grain sizes commonly used and varying from coarse to very fine are indicated by the following numbers: 8, 10, 12, 14, 16, 20, 24, 30, 36, 46, 54, 60,70, 80, 90, 100, 120, 150, 180, and 220. The following additional sizes are used occasionally: 240, 280, 320, 400, 500, and 600. The wheel manufacturer may add to the regular grain number an additional symbol to indicate a special grain combination.

Copyright 2004, Industrial Press, Inc., New York, NY

3) *Grade:* Grades are indicated by letters of the alphabet from A to Z in all bonds or processes. Wheel grades from A to Z range from soft to hard.

4) *Structure:* The use of a structure symbol is optional. The structure is indicated by Nos. 1 to 16 (or higher, if necessary) with progressively higher numbers indicating a progressively wider grain spacing (more open structure).

5) *Bond or Process:* Bonds are indicated by the following letters: V, vitrified; S, silicate; E, shellac or elastic; R, rubber; RF, rubber reinforced; B, resinoid (synthetic resins); BF, resinoid reinforced; O, oxychloride.

6) *Manufacturer's Record:* The sixth position may be used for manufacturer's private factory records; this is optional.

American National Standard Shapes and Sizes of Grinding Wheels.— The ANSI Standard B74.2-1982 which includes shapes and sizes of grinding wheels, gives a wide variety of grinding wheel shape and size combinations. These are suitable for the majority of applications. Although grinding wheels can be manufactured to shapes and dimensions different from those listed, it is advisable, for reasons of cost and inventory control, to avoid using special shapes and sizes, unless technically warranted.

Standard shapes and size ranges as given in this Standard together with typical applications are shown in Table 1a for inch dimensions and in Table 1b for metric dimensions.

The operating surface of the grinding wheel is often referred to as the wheel face. In the majority of cases it is the periphery of the grinding wheel which, when not specified otherwise, has a straight profile. However, other face shapes can also be supplied by the grinding wheel manufacturers, and also reproduced during usage by appropriate truing. ANSI B74.2-1982 standard offers 13 different shapes for grinding wheel faces, which are shown in Table 2.

The Selection of Grinding Wheels.— In selecting a grinding wheel, the determining factors are the composition of the work material, the type of grinding machine, the size range of the wheels used, and the expected grinding results, in this approximate order.

The Norton Company has developed, as the result of extensive test series, a method of grinding wheel recommendation that is more flexible and also better adapted to taking into consideration pertinent factors of the job, than are listings based solely on workpiece categories. This approach is the basis for Tables 3 through 6, inclusive. Tool steels and constructional steels are considered in the detailed recommendations presented in these tables.

Table 3 assigns most of the standardized tool steels to five different grindability groups. The AISI-SAE tool steel designations are used.

After having defined the grindability group of the tool steel to be ground, the operation to be carried out is found in the first column of Table 4. The second column in this table distinguishes between different grinding wheel size ranges, because wheel size is a factor in determining the contact area between wheel and work, thus affecting the apparent hardness of the grinding wheel. Distinction is also made between wet and dry grinding.

Finally, the last two columns define the essential characteristics of the recommended types of grinding wheels under the headings of first and second choice, respectively. Where letters are used *preceding* A, the standard designation for aluminum oxide, they indicate a degree of friability different from the regular, thus: SF = semi friable (Norton equivalent 16A) and F = friable (Norton equivalent 33A and 38A). The suffix P, where applied, expresses a degree of porosity that is more open than the regular.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. Standard Shapes and Inch Size Ranges of Grinding Wheels
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Inches		
	D = Dia.	*T* = Thick.	*H* = Hole
 **Type 1. Straight Wheel** For peripheral grinding.			
CUTTING OFF (Organic bonds only)	1 to 48	1/64 to 3/8	1/16 to 6
CYLINDRICAL GRINDING Between centers	12 to 48	1/2 to 6	5 to 20
CYLINDRICAL GRINDING Centerless grinding wheels	14 to 30	1 to 20	5 or 12
CYLINDRICAL GRINDING Centerless regulating wheels	8 to 14	1 to 12	3 to 6
INTERNAL GRINDING	1/4 to 4	1/4 to 2	3/32 to 7/8
OFFHAND GRINDING Grinding on the periphery			
General purpose	6 to 36	1/2 to 4	1/2 to 3
For wet tool grinding only	30 or 36	3 or 4	20
SAW GUMMING (F-type face)	6 to 12	1/4 to 1 1/2	1/2 to 1 1/4
SNAGGING Floor stand machines	12 to 24	1 to 3	1 1/4 to 2 1/2
SNAGGING Floor stand machines (Organic bond, wheel speed over 6500 sfpm)	20 to 36	2 to 4	6 or 12
SNAGGING Mechanical grinders (Organic bond, wheel speed up to 16,500 sfpm)	24	2 to 3	12
SNAGGING Portable machines	3 to 8	1/4 to 1	3/8 to 5/8
SNAGGING Portable machines (Reinforced organic bond, 17,000 sfpm)	6 or 8	3/4 or 1	1
SNAGGING Swing frame machines	12 to 24	2 to 3	3 1/2 to 12
SURFACE GRINDING Horizontal spindle machines	6 to 24	1/2 to 6	1 1/4 to 12
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	6 to 10	1/4 to 1/2	5/8 to 5
 **Type 2. Cylindrical Wheel** Side grinding wheel — mounted on the diameter; may also be mounted in a chuck or on a plate.			
			W = Wall
SURFACE GRINDING Vertical spindle machines	8 to 20	4 or 5	1 to 4

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. ***(Continued)*** **Standard Shapes and Inch Size Ranges of Grinding Wheels**
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Inches		
	D = Dia.	*T* = Thick.	*H* = Hole
	**Type 5. Wheel,** recessed one side For peripheral grinding. Allows wider faced wheels than the available mounting thickness, also grinding clearance for the nut and flange.		
CYLINDRICAL GRINDING Between centers	12 to 36	1½ to 4	5 or 12
CYLINDRICAL GRINDING Centerless regulating wheel	8 to 14	3 to 6	3 or 5
INTERNAL GRINDING	⅜ to 4	⅜ to 2	⅛ to ⅞
SURFACE GRINDING Horizontal spindle machines	7 to 24	¾ to 6	1¼ to 12
	**Type 6. Straight-Cup Wheel** Side grinding wheel, in whose dimensioning the wall thickness (*W*) takes precedence over the diameter of the recess. Hole is ⅝-11UNC-2B threaded for the snagging wheels and ½ or 1¼″ for the tool grinding wheels.		
			W = Wall
SNAGGING Portable machines, organic bond only.	4 to 6	2	¾ to 1½
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	2 to 6	1 ¼ to 2	5/16 or ⅜
	**Type 7. Wheel,** recessed two sides Peripheral grinding. Recesses allow grinding clearance for both flanges and also narrower mounting thickness than overall thickness.		
CYLINDRICAL GRINDING Between centers	12 to 36	1½ to 4	5 or 12
CYLINDRICAL GRINDING Centerless regulating wheel	8 to 14	4 to 20	3 to 6
SURFACE GRINDING Horizontal spindle machines	12 to 24	2 to 6	5 to 12

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. ***(Continued)*** **Standard Shapes and Inch Size Ranges of Grinding Wheels**
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Inches		
	D = Dia.	*T* = Thick.	*H* = Hole
 **Type 11. Flaring-Cup Wheel** Side grinding wheel with wall tapered outward from the back; wall generally thicker in the back.			
SNAGGING Portable machines, organic bonds only, threaded hole	4 to 6	2	$\frac{5}{8}$-11 UNC-2B
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	2 to 5	1 $\frac{1}{4}$ to 2	$\frac{1}{2}$ to 1 $\frac{1}{4}$
 **Type 12. Dish Wheel** Grinding on the side or on the U-face of the wheel, the U-face being always present in this type.			
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	3 to 8	$\frac{1}{2}$ or $\frac{3}{4}$	$\frac{1}{2}$ to 1 $\frac{1}{4}$
 **Type 13. Saucer Wheel** Peripheral grinding wheel, resembling the shape of a saucer, with cross section equal throughout.			
SAW GUMMING Saw tooth shaping and sharpening	8 to 12	$\frac{1}{2}$ to 1 $\frac{3}{4}$ *U* & *E* $\frac{1}{4}$ to 1$\frac{1}{2}$	$\frac{3}{4}$ to 1 $\frac{1}{4}$
 **Type 16. Cone, Curved Side** **Type 17. Cone, Straight Side, Square Tip** **Type 17R. Cone, Straight Side, Round Tip** (Tip Radius *R* = *J*/2)			
SNAGGING Portable machine, threaded holes	1$\frac{1}{4}$ to 3	2 to 3$\frac{1}{2}$	$\frac{3}{8}$-24UNF-2B to $\frac{5}{8}$-11UNC-2B

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. ***(Continued)*** **Standard Shapes and Inch Size Ranges of Grinding Wheels**
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Inches		
	D = Dia.	*T* = Thick.	*H* = Hole
 **Type 18. Plug, Square End** **Type 18R. Plug, Round End** *R* = *D*/2			
 **Type 19. Plugs, Conical End, Square Tip** **Type 19R. Plugs, Conical End, Round Tip** (Tip Radius *R* = *J*/2)			
SNAGGING Portable machine, threaded holes	1¼ to 3	2 to 3½	⅜-24UNF-2B to ⅝-11UNC-2B
 **Type 20. Wheel, Relieved One Side** Peripheral grinding wheel, one side flat, the other side relieved to a flat.			
CYLINDRICAL GRINDING Between centers	12 to 36	¾ to 4	5 to 20
 **Type 21. Wheel, Relieved Two Sides** Both sides relieved to a flat.			
 **Type 22. Wheel, Relieved One Side, Recessed Other Side** One side relieved to a flat.			
 **Type 23. Wheel, Relieved and Recessed Same Side** The other side is straight.			
CYLINDRICAL GRINDING Between centers, with wheel periphery	20 to 36	2 to 4	12 or 20

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. ***(Continued)*** **Standard Shapes and Inch Size Ranges of Grinding Wheels**
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Inches		
	D = Dia.	*T* = Thick.	*H* = Hole
	**Type 24. Wheel, Relieved and Recessed One Side, Recessed Other Side** One side recessed, the other side is relieved to a recess.		
	**Type 25. Wheel, Relieved and Recessed One Side, Relieved Other Side** One side relieved to a flat, the other side relieved to a recess.		
	**Type 26. Wheel, Relieved and Recessed Both Sides**		
CYLINDRICAL GRINDING Between centers, with the periphery of the wheel	20 to 36	2 to 4	12 or 20
	**TYPES 27 & 27A. Wheel, Depressed Center** 27. *Portable Grinding:* Grinding normally done by contact with work at approx. a 15° angle with face of the wheel. 27A. *Cutting-off:* Using the periphery as grinding face.		
CUTTING OFF Reinforced organic bonds only	16 to 30	*U* = *E* = 5/32 to 1/4	1 or 1 1/2
SNAGGING Portable machine	3 to 9	*U* = Uniform thick. 1/8 to 3/8	3/8 or 7/8
	**Type 28. Wheel, Depressed Center (Saucer Shaped Grinding Face)** Grinding at approx. 15° angle with wheel face.		
SNAGGING Portable machine	7 or 9	*U* = Uniform thickness 1/4	7/8

Throughout table large open-head arrows indicate grinding surfaces.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Standard Shapes and Metric Size Ranges of Grinding Wheels
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Millimeters		
	D = Diam.	*T* = Thick.	*H* = Hole
Type 1. Straight Wheel[a]			
CUTTING OFF (nonreinforced and reinforced organic bonds only)	150 to 1250	0.8 to 10	16 to 152.4
CYLINDRICAL GRINDING Between centers	300 to 1250	20 to 160	127 to 508
CYLINDRICAL GRINDING Centerless grinding wheels	350 to 750	25 to 500	127 or 304.8
CYLINDRICAL GRINDING Centerless regulating wheels	200 to 350	25 to 315	76.2 to 152.4
INTERNAL GRINDING	6 to 100	6 to 50	2.5 to 25
OFFHAND GRINDING Grinding on the periphery			
General purpose	150 to 900	13 to 100	20 to 76.2
For wet tool grinding only	750 or 900	80 or 100	508
SAW GUMMING (F-type face)	150 to 300	6 to 40	32
SNAGGING Floor stand machines	300 to 600	25 to 80	32 to 76.2
SNAGGING Floor stand machines(organic bond, wheel speed over 33 meters per second)	500 to 900	50 to 100	152.4 or 304.8
SNAGGING Mechanical grinders (organic bond, wheel speed up to 84 meters per second)	600	50 to 80	304.8
SNAGGING Portable machines	80 to 200	6 to 25	10 to 16
SNAGGING Swing frame machines (organic bond)	300 to 600	50 to 80	88.9 to 304.8
SURFACE GRINDING Horizontal spindle machines	150 to 600	13 to 160	32 to 304.8
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	150 to 250	6 to 20	32 to 127
Type 2. Cylindrical Wheel[a]			
			W = Wall
SURFACE GRINDING Vertical spindle machines	200 to 500	100 or 125	25 to 100

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. ***(Continued)*** **Standard Shapes and Metric Size Ranges of Grinding Wheels**
ANSI B74.2-1982

Applications	Size Ranges of Principal Dimensions, Millimeters		
	D = Diam.	*T* = Thick.	*H* = Hole
Type 5. Wheel, recessed one side[a]			
CYLINDRICAL GRINDING Between centers	300 to 900	40 to 100	127 or 304.8
CYLINDRICAL GRINDING Centerless regulating wheels	200 to 350	80 to 160	76.2 or 127
INTERNAL GRINDING	10 to 100	10 to 50	3.18 to 25
Type 6. Straight-Cup Wheel[a]			
			W = Wall
SNAGGING Portable machines, organic bond only (hole is $\frac{5}{8}$-11 UNC-2B)	100 to 150	50	20 to 40
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc. (Hole is 13 to 32 mm)	50 to 150	32 to 50	8 or 10
Type 7. Wheel, recessed two sides[a]			
CYLINDRICAL GRINDING Between centers	300 to 900	40 to 100	127 or 304.8
CYLINDRICAL GRINDING Centerless regulating wheels	200 to 350	100 to 500	76.2 to 152.4
Type 11. Flaring-Cup Wheel[a]			
SNAGGING Portable machines, organic bonds only, threaded hole	100 to 150	50	$\frac{5}{8}$-11 UNC-2B
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	50 to 125	32 to 50	13 to 32
Type 12. Dish Wheel[a]			
TOOL GRINDING Broaches, cutters, mills, reamers, taps, etc.	80 to 200	13 or 20	13 to 32
Type 27 and 27A. Wheel, depressed center[a]			
CUTTING OFF Reinforced organic bonds only	400 to 750	*U* = *E* = 6	25.4 or 38.1
SNAGGING Portable machines	80 to 230	*U* = *E* = 3.2 to 10	9.53 or 22.23

[a] See Table 1a for diagrams and descriptions of each wheel type.
All dimensions in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Standard Shapes of Grinding Wheel Faces *ANSI B74.2-1982*



Recommendations, similar in principle, yet somewhat less discriminating have been developed by the Norton Company for *constructional steels*. These materials can be ground either in their original state (soft) or in their after-hardened state (directly or following carburization). Constructional steels must be distinguished from structural steels which are used primarily by the building industry in mill shapes, without or with a minimum of machining.

Constructional steels are either plain carbon or alloy type steels assigned in the AISI-SAE specifications to different groups, according to the predominant types of alloying elements. In the following recommendations no distinction is made because of different compositions since that factor generally, has a minor effect on grinding wheel choice in constructional steels. However, separate recommendations are made for soft (Table 5) and

Copyright 2004, Industrial Press, Inc., New York, NY

hardened (Table 6) constructional steels. For the relatively rare instance where the use of a single type of wheel for both soft and hardened steel materials is considered more important than the selection of the best suited types for each condition of the work materials, Table 5 lists "All Around" wheels in its last column.

For applications where cool cutting properties of the wheel are particularly important, Table 6 lists, as a second alternative, porous-type wheels. The sequence of choices as presented in these tables does not necessarily represent a second, or third best; it can also apply to conditions where the first choice did not provide optimum results and by varying slightly the composition of the grinding wheel, as indicated in the subsequent choices, the performance experience of the first choice might be improved.

Table 3. Classification of Tool Steels by their Relative Grindability

Relative Grindability Group	AISI-SAE Designation of Tool Steels
GROUP 1—Any area of work surface	W1, W2, W5
	S1, S2, S4, S5, S6, S7
High grindability tool and die steels	O1, O2, O6, O7
(Grindability index greater than 12)	H10, H11, H12, H13, H14
	L2, L6
GROUP 2—Small area of work surface	H19, H20, H21, H22, H23, H24, H26
(*as found in tools*)	P6, P20, P21
	T1, T7, T8
Medium grindability tool and die steels	M1, M2, M8, M10, M33, M50
(Grindability index 3 to 12)	D1, D2, D3, D4, D5, D6
	A2, A4, A6, A8, A9, A10
GROUP 3—Small area of work surface	T4, T5, T6, T8
(*as found in tools*)	M3, M6, M7, M34, M36, M41, M42, M46, M48, M52, M62
Low grindability tool and die steels	D2, D5
(Grindability index between 1.0 and 3)	A11
GROUP 4—Large area of work surface	
(as found in dies)	All steels found in Groups 2 and 3
Medium and low grindability tool and die steels	
(Grindability index between 1.0 and 12)	
GROUP 5—Any area of work surface	D3, D4, D7
	M4
Very low grindability tool and die steels	A7
(Grindability index less than 1.0)	T15

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Grinding Wheel Recommendations for Hardened Tool Steels According to their Grindability

Operation	Wheel or Rim Diameter, Inches	First-Choice Specifications	Second-Choice Specifications
Group 1 Steels			
Surfacing			
Surfacing wheels	14 and smaller	Wet FA46-I8V	SFA46-G12VP
	14 and smaller	Dry FA46-H8V	FA46-F12VP
	Over 14	Wet FA36-I8V	SFA36-I8V
Segments or Cylinders	1½ rim or less	Wet FA30-H8V	FA30-F12VP
Cups	¾ rim or less	Wet FA36-H8V	FA46-F12VP
	(for rims wider than 1½ inches, go one grade softer in available specifications)		
Cutter sharpening			
Straight wheel	…	Wet FA46-K8V	FA60-K8V
	…	Dry FA46-J8V	FA46-H12VP
Dish shape	…	Dry FA60-J8V	FA60-H12VP
Cup shape	…	Dry FA46-L8V	FA60-H12VP
	…	Wet SFA46-L5V	SFA60-L5V
Form tool grinding	8 and smaller	Wet FA60-L8V to FA100-M7V	
	8 and smaller	Dry FA60-K8V to FA100-L8V	
	10 and larger	Wet FA60-L8V to FA80-M6V	
Cylindrical	14 and smaller	Wet SFA60-L5V	…
	16 and larger	Wet SFA60-M5V	…
Centerless	…	Wet SFA60-M5V	…
Internal			
Production grinding	Under ½	Wet SPA80-N6V	SFA80-N7V
	½ to 1	Wet SFA60-M5V	SFA60-M6V
	Over 1 to 3	Wet SFA54-L5V	SFA54-L6V
	Over 3	Wet SFA46-L5V	SFA46-K5V
Tool room grinding	Under ½	Dry FA80-L6V	SFA80-L7V
	½ to 1	Dry FA70-K7V	SFA70-K7V
	Over 1 to 3	Dry FA60-J8V	FA60-H12VP
	Over 3	Dry FA46-J8V	FA54-H12VP
Group 2 Steels			
Surfacing			
Straight wheels	14 and smaller	Wet FA46-I8V	FA46-G12VP
	14 and smaller	Dry FA46-H8V	FA46-F12VP
	Over 14	Wet FA46-H8V	SFA46-I8V
Segments or Cylinders	1½ rim or less	Wet FA30-G8V	FA36-E12VP
Cups	¾ rim or less	Wet FA36-H8V	FA46-F12VP
	(for rims wider than 1½ inches, go one grade softer in available specifications)		

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Grinding Wheel Recommendations for Hardened Tool Steels According to their Grindability**

Operation	Wheel or Rim Diameter, Inches	First-Choice Specifications	Second-Choice Specifications
Cutter sharpening			
Straight wheel	…	Wet FA46-L5V	FA60-K8V
	…	Dry FA46-J8V	FA60-H12VP
Dish shape	…	Dry FA60-J5V	FA60-G12VP
Cup shape	…	Dry FA46-K5V	FA60-G12VP
	…	Wet FA46-L5V	FA60-J8V
Form tool grinding	8 and smaller	Wet FA60-K8V to FA120-L8V	
	8 and smaller	Dry FA80-K8V to FA150-K8V	
	10 and larger	Wet FA60-K8V to FA120-L8V	
Cylindrical	14 and less	Wet FA60-L5V	SFA60-L5V
	16 and larger	Wet FA60-K5V	SFA60-K5V
Centerless	…	Wet FA60-M5V	SFA60-M5V
Internal			
Production grinding	Under ½	Wet FA80-L6V	SFA80-L6V
	½ to 1	Wet FA70-K5V	SFA70-K5V
	Over 1 to 3	Wet FA60-J8V	SFA60-J7V
	Over 3	Wet FA54-J8V	SFA54-J8V
Tool room grinding	Under ½	Dry FA80-I8V	SFA80-K7V
	½ to 1	Dry FA70-J8V	SFA70-J7V
	Over 1 to 3	Dry FA60-I8V	FA60-G12VP
	Over 3	Dry FA54-I8V	FA54-G12VP
Group 3 Steels			
Surfacing			
Straight wheels	14 and smaller	Wet FA60-I8V	FA60-G12VP
	14 and smaller	Dry FA60-H8V	FA60-F12VP
	Over 14	Wet FA60-H8V	SFA60-I8V
Segments or Cylinders	1½ rim or less	Wet FA46-G8V	FA46-E12VP
Cups	¾ rim or less	Wet FA46-G8V	FA46-E12VP
	(for rims wider than 1½ inches, go one grade softer in available specifications)		
Cutter grinding			
Straight wheel	…	Wet FA46-J8V	FA60-J8V
	…	Dry FA46-I8V	FA46-G12VP
Dish shape	…	Dry FA60-H8V	FA60-F12VP
Cup shape	…	Dry FA46-I8V	FA60-F12VP
	…	Wet FA46-J8V	FA60-J8V
Form tool grinding	8 and smaller	Wet FA80-K8V to FA150-L9V	
	8 and smaller	Dry FA100-J8V to FA150-K8V	
	10 and larger	Wet FA80-J8V to FA150-J8V	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Grinding Wheel Recommendations for Hardened Tool Steels According to their Grindability**

Operation	Wheel or Rim Diameter, Inches	First-Choice Specifications	Second-Choice Specifications
Cylindrical	14 and less	Wet FA80-L5V	SFA80-L6V
	16 and larger	Wet FA60-L6V	SFA60-K5V
Centerless	…	Wet FA60-L5V	SFA60-L5V
Internal			
Production grinding	Under ½	Wet FA90-L6V	SFA90-L6V
	½ to 1	Wet FA80-L6V	SFA80-L6V
	Over 1 to 3	Wet FA70-K5V	SFA70-K5V
	Over 3	Wet FA60-J5V	SFA60-J5V
Tool room grinding	Under ½	Dry FA90-K8V	SFA90-K7V
	½ to 1	Dry FA80-J8V	SFA80-J7V
	Over 1 to 3	Dry FA70-I8V	SFA70-G12VP
	Over 3	Dry FA60-I8V	SFA60-G12VP
Group 4 Steels			
Surfacing			
Straight wheels	14 and smaller	Wet FA60-I8V	C60-JV
	14 and smaller	Wet FA60-H8V	C60-IV
	Over 14	Wet FA46-H8V	C60-HV
Segments	1 ½ rim or less	Wet FA46-G8V	C46-HV
Cylinders	1 ½ rim or less	Wet FA46-G8V	C60-HV
Cups	¾ rim or less	Wet FA46-G6V	C60-IV
	(for rims wider than 1 ½ inches, go one grade softer in available specifications)		
Form tool grinding	8 and smaller	Wet FA60-J8V to FA150-K8V	
	8 and smaller	Dry FA80-I8V to FA180-J8V	
	10 and larger	Wet FA60-J8V to FA150-K8V	
Cylindrical	14 and less	Wet FA80-K8V	C60-KV
	16 and larger	Wet FA60-J8V	C60-KV
Internal			
Production grinding	Under ½	Wet FA90-L8V	C90-LV
	½ to 1	Wet FA80-K5V	C80-KV
	Over 1 to 3	Wet FA70-J8V	C70-JV
	Over 3	Wet FA60-I8V	C60-IV
Tool room grinding	Under ½	Dry FA90-K8V	C90-KV
	½ to 1	Dry FA80-J8V	C80-JV
	Over 1 to 3	Dry FA70-I8V	C70-IV
	Over 3	Dry FA60-H8V	C60-HV

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Grinding Wheel Recommendations for Hardened Tool Steels According to their Grindability**

Operation	Wheel or Rim Diameter, Inches	First-Choice Specifications	Second-Choice Specifications	Third-Choice Specifications
Group 5 Steels				
Surfacing				
Straight wheels	14 and smaller	Wet SFA60-H8V	FA60-E12VP	C60-IV
	14 and smaller	Dry SFA80-H8V	FA80-E12VP	C80-HV
	Over 14	Wet SFA60-H8V	FA60-E12VP	C60-HV
Segments or Cylinders	1 ½ rim or less	Wet SFA46-G8V	FA46-E12VP	C46-GV
Cups	¾ rim or less	Wet SFA60-G8V	FA60-E12VP	C60-GV
	(for rims wider than 1 ½ inches, go one grade softer in available specifications)			
Cutter grinding				
Straight wheels	…	Wet SFA60-I8V	SFA60-G12VP	…
	…	Dry SFA60-H8V	SFA80-F12VP	…
Dish shape	…	Dry SFA80-H8V	SFA80-F12VP	…
Cup shape	…	Dry SFA60-I8V	SFA60-G12VP	…
	…	Wet SFA60-J8V	SFA60-H12VP	…
Form tool				
grinding	8 and smaller	Wet FA80-J8V to FA180-J9V		…
	8 and smaller	Dry FA100-I8V to FA220-J9V		…
	10 and larger	Wet FA80-J8V to FA180-J9V		…
Cylindrical	14 and less	Wet FA80-J8V	C80-KV	FA80-H12VP
	16 and larger	Wet FA80-I8V	C80-KV	FA80-G12VP
Centerless	…	Wet FA80-J5V	C80-LV	…
Internal				
Production grinding	Under ½	Wet FA100-L8V	C90-MV	…
	½ to 1	Wet FA90-K8V	C80-LV	…
	Over 1 to 3	Wet FA80-J8V	C70-KV	FA80-H12VP
	Over 3	Wet FA70-I8V	C60-JV	FA70-G12VP
Tool room grinding	Under ½	Dry FA100-K8V	C90-KV	…
	½ to 1	Dry FA90-J8V	C80-JV	…
	Over 1 to 3	Dry FA80-I8V	C70-IV	FA80-G12VP
	Over 3	Dry FA70-I8V	C60-IV	FA70-G12VP

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Grinding Wheel Recommendations for Constructional Steels (Soft)

Grinding Operation	Wheel or Rim Diameter, Inches	First Choice	Alternate Choice (Porous type)	All-Around Wheel
Surfacing				
Straight wheels	14 and smaller	Wet FA46-J8V	FA46-H12VP	FA46-J8V
	14 and smaller	Dry FA46-I8V	FA46-H12VP	FA46-I8V
	Over 14	Wet FA36-J8V	FA36-H12VP	FA36-J8V
Segments	1½ rim or less	Wet FA24-H8V	FA30-F12VP	FA24-H8V
Cylinders	1½ rim or less	Wet FA24-I8V	FA30-G12VP	FA24-H8V
Cups	¾ rim or less	Wet FA24-H8V	FA30-F12VP	FA30-H8V
	(for wider rims, go one grade softer)			
Cylindrical	14 and smaller	Wet SFA60-M5V	…	SFA60-L5V
	16 and larger	Wet SFA54-M5V	…	SFA54-L5V
Centerless	…	Wet SFA54-N5V	…	SFA60-M5V
Internal	Under ½	Wet SFA60-M5V	…	SFA80-L6V
	½ to 1	Wet SFA60-L5V	…	SFA60-K5V
	Over 1 to 3	Wet SFA54-K5V	…	SFA54-J5V
	Over 3	Wet SFA46-K5V	…	SFA46-J5V

Table 6. Grinding Wheel Recommendations for Constructional Steels (Hardened or Carburized)

Grinding Operation	Wheel or Rim Diameter, Inches	First Choice	Alternate Choice (Porous Type)
Surfacing			
Straight wheels	14 and smaller	Wet FA46-I8V	FA46-G12VP
	14 and smaller	Dry FA46-H8V	FA46-F12VP
	Over 14	Wet FA36-I8V	FA36-G12VP
Segments or Cylinders	1½ rim or less	Wet FA30-H8V	FA36-F12VP
Cups	¾ rim or less	Wet FA36-H8V	FA46-F12VP
	(for wider rims, go one grade softer)		
Forms and Radius	8 and smaller	Wet FA60-L7V to FA100-M8V	
Grinding	8 and smaller	Dry FA60-K8V to FA100-L8V	
	10 and larger	Wet FA60-L7V to FA80-M7V	
Cylindrical			
Work diameter			
1 inch and smaller	14 and smaller	Wet SFA80-L6V	…
Over 1 inch	14 and smaller	Wet SFA80-K5V	…
1 inch and smaller	16 and larger	Wet SFA60-L5V	…
Over 1 inch	16 and larger	Wet SFA60-L5V	…
Centerless	…	Wet SFA80-M6V	…
Internal	Under ½	Wet SFA80-N6V	…
	½ to 1	Wet SFA60-M5V	…
	Over 1 to 3	Wet SFA54-L5V	…
	Over 3	Wet SFA46-K5V	…
	Under ½	Dry FA80-L6V	…
	½ to 1	Dry FA70-K8V	…
	Over 1 to 3	Dry FA60-J8V	FA60-H12VP
	Over 3	Dry FA46-J8V	FA54-H12VP

Copyright 2004, Industrial Press, Inc., New York, NY

Cubic Boron Nitride (CBN) Grinding Wheels.— Although CBN is not quite as hard, strong, and wear-resistant as a diamond, it is far harder, stronger, and more resistant to wear than aluminum oxide and silicon carbide. As with diamond, CBN materials are available in different types for grinding workpieces of 50 Rc and above, and for superalloys of 35 Rc and harder. Microcrystalline CBN grinding wheels are suitable for grinding mild steels, medium-hard alloy steels, stainless steels, cast irons, and forged steels. Wheels with larger mesh size grains (up to 20/30), now available, provide for higher rates of metal removal.

Special types of CBN are produced for resin, vitrified, and electrodeposited bonds. Wheel standards and nomenclature generally conform to those used for diamond wheels (page 1201), except that the letter **B** instead of **D** is used to denote the type of abrasive. Grinding machines for CBN wheels are generally designed to take full advantage of the ability of CBN to operate at high surface speeds of 9,000–25,000 sfm. CBM is very responsive to changes in grinding conditions, and an increase in wheel speed from 5,000 to 10,000 sfm can increase wheel life by a factor of 6 or more. A change from a water-based coolant to a coolant such as a sulfochlorinated or sulfurized straight grinding oil can increase wheel life by a factor of 10 or more.

Machines designed specifically for use with CBN grinding wheels generally use either electrodeposited wheels or have special trueing systems for other CBN bond wheels, and are totally enclosed so they can use oil as a coolant. Numerical control systems are used, often running fully automatically, including loading and unloading. Machines designed for CBN grinding with electrodeposited wheels are extensively used for form and gear grinding, special systems being used to ensure rapid mounting to exact concentricity and truth in running, no trueing or dressing being required. CBN wheels can produce workpieces having excellent accuracy and finish, with no trueing or dressing for the life of the wheel, even over many hours or days of production grinding of hardened steel components.

Resin-, metal-, and vitrified-bond wheels are used extensively in production grinding, in standard and special machines. Resin-bonded wheels are used widely for dry tool and cutter resharpening on conventional hand-operated tool and cutter grinders. A typical wheel for such work would be designated 11V9 cup type, 100/120 mesh, 75 concentration, with a $\frac{1}{16}$ or $\frac{1}{8}$ in. rim section. Special shapes of resin-bonded wheels are used on dedicated machines for cutting tool manufacture. These types of wheels are usually self-dressing, and allow full machine control of the operation without the need for an operator to see, hear, or feel the action.

Metal-bonded CBN wheels are usually somewhat cheaper than those using other types of bond because only a thin layer of abrasive is present. Metal bonding is also used in manufacture of CBN honing stones. Vitrified-bond CBN wheels are a recent innovation, and high-performance bonds are still being developed. These wheels are used for grinding cams, internal diameters, and bearing components, and can be easily redressed.

An important aspect of grinding with CBN and diamond wheels is reduced heating of the workpiece, thought to result from their superior thermal conductivity compared with aluminum oxide, for instance. CBN and diamond grains also are harder, which means that they stay sharp longer than aluminum oxide grains. The superior ability to absorb heat from the workpiece during the grinding process reduces formation of untempered martensite in the ground surface, caused by overheating followed by rapid quenching. At the same time, a higher compressive residual stress is induced in the surface, giving increased fatigue resistance, compared with the tensile stresses found in surfaces ground with aluminum oxide abrasives. Increased fatigue resistance is of particular importance for gear grinding, especially in the root area.

Variations from General Grinding Wheel Recommendations.— Recommendations for the selection of grinding wheels are usually based on average values with regard to both operational conditions and process objectives. With variations from such average values,

Copyright 2004, Industrial Press, Inc., New York, NY

the composition of the grinding wheels must be adjusted to obtain optimum results. Although it is impossible to list and to appraise all possible variations and to define their effects on the selection of the best suited grinding wheels, some guidance is obtained from experience. The following tabulation indicates the general directions in which the characteristics of the initially selected grinding wheel may have to be altered in order to approach optimum performance. Variations in a sense opposite to those shown will call for wheel characteristic changes in reverse.

Conditions or Objectives	Direction of Change
To increase cutting rate	Coarser grain, softer bond, higher porosity
To retain wheel size and/or form	Finer grain, harder bond
For small or narrow work surface	Finer grain, harder bond
For larger wheel diameter	Coarser grain
To improve finish on work	Finer grain, harder bond, or resilient bond
For increased work speed or feed rate	Harder bond
For increased wheel speed	Generally, softer bond, except for high-speed grinding, which requires a harder bond for added wheel strength
For interrupted or coarse work surface	Harder bond
For thin walled parts	Softer bond
To reduce load on the machine drive motor	Softer bond

Dressing and Truing Grinding Wheels.— The perfect grinding wheel operating under ideal conditions will be self sharpening, i.e., as the abrasive grains become dull, they will tend to fracture and be dislodged from the wheel by the grinding forces, thereby exposing new, sharp abrasive grains. Although in precision machine grinding this ideal sometimes may be partially attained, it is almost never attained completely. Usually, the grinding wheel must be dressed and trued after mounting on the precision grinding machine spindle and periodically thereafter.

Dressing may be defined as any operation performed on the face of a grinding wheel that improves its cutting action. Truing is a dressing operation but is more precise, i.e., the face of the wheel may be made parallel to the spindle or made into a radius or special shape. Regularly applied truing is also needed for accurate size control of the work, particularly in automatic grinding. The tools and processes generally used in grinding wheel dressing and truing are listed and described in Table 1.

Table 1. Tools and Methods for Grinding Wheel Dressing and Truing

Designation	Description	Application
Rotating Hand Dressers	Freely rotating discs, either star-shaped with protruding points or discs with corrugated or twisted perimeter, supported in a fork-type handle, the lugs of which can lean on the tool rest of the grinding machine.	Preferred for bench- or floor-type grinding machines; also for use on heavy portable grinders (snagging grinders) where free-cutting properties of the grinding wheel are primarily sought and the accuracy of the trued profile is not critical.
Abrasive Sticks	Made of silicon carbide grains with a hard bond. Applied directly or supported in a handle. Less frequently abrasive sticks are also made of boron carbide.	Usually hand held and use limited to smaller-size wheels. Because it also shears the grains of the grinding wheel, or preshaping, prior to final dressing with, e.g., a diamond.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Tools and Methods for Grinding Wheel Dressing and Truing**

Designation	Description	Application
Abrasive Wheels (Rolls)	Silicon carbide grains in a hard vitrified bond are cemented on ball-bearing mounted spindles. Use either as hand tools with handles or rigidly held in a supporting member of the grinding machine. Generally freely rotating; also available with adjustable brake for diamond wheel dressing.	Preferred for large grinding wheels as a diamond saver, but also for improved control of the dressed surface characteristics. By skewing the abrasive dresser wheel by a few degrees out of parallel with the grinding wheel axis, the basic crushing action is supplemented with wiping and shearing, thus producing the desired degree of wheel surface smoothness.
Single-Point Diamonds	A diamond stone of selected size is mounted in a steel nib of cylindrical shape with or without head, dimensioned to fit the truing spindle of specific grinding machines. Proper orientation and retainment of the diamond point in the setting is an important requirement.	The most widely used tool for dressing and truing grinding wheels in precision grinding. Permits precisely controlled dressing action by regulating infeed and cross feed rate of the truing spindle when the latter is guided by cams or templates for accurate form truing.
Single-Point Form Truing Diamonds	Selected diamonds having symmetrically located natural edges with precisely lapped diamond points, controlled cone angles and vertex radius, and the axis coinciding with that of the nib.	Used for truing operations requiring very accurately controlled, and often steeply inclined wheel profiles, such as are needed for thread and gear grinding, where one or more diamond points participate in generating the resulting wheel periphery form. Dependent on specially designed and made truing diamonds and nibs.
Cluster-Type Diamond Dresser	Several, usually seven, smaller diamond stones are mounted in spaced relationship across the working surface of the nib. In some tools, more than a single layer of such clusters is set at parallel levels in the matrix, the deeper positioned layer becoming active after the preceding layer has worn away.	Intended for straight-face dressing and permits the utilization of smaller, less expensive diamond stones. In use, the holder is canted at a 3° to 10° angle, bringing two to five points into contact with the wheel. The multiple-point contact permits faster cross feed rates during truing than may be used with single-point diamonds for generating a specific degree of wheel-face finish.
Impregnated Matrix-Type Diamond Dressers	The operating surface consists of a layer of small, randomly distributed, yet rather uniformly spaced diamonds that are retained in a bond holding the points in an essentially common plane. Supplied either with straight or canted shaft, the latter being used to cancel the tilt of angular truing posts.	For the truing of wheel surfaces consisting of a single or several flat elements. The nib face should be held tangent to the grinding wheel periphery or parallel with a flat working surface. Offers economic advantages where technically applicable because of using less expensive diamond splinters presented in a manner permitting efficient utilization.
Form- Generating Truing Devices	Swiveling diamond holder post with adjustable pivot location, arm length, and swivel arc, mounted on angularly adjustable cross slides with controlled traverse movement, permits the generation of various straight and circular profile elements, kept in specific mutual locations.	Such devices are made in various degrees of complexity for the positionally controlled interrelation of several different profile elements. Limited to regular straight and circular sections, yet offers great flexibility of setup, very accurate adjustment, and unique versatility for handling a large variety of frequently changing profiles.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Tools and Methods for Grinding Wheel Dressing and Truing**

Designation	Description	Application
Contour-Duplicating Truing Devices	The form of a master, called cam or template, shaped to match the profile to be produced on the wheel, or its magnified version, is translated into the path of the diamond point by means of mechanical linkage, a fluid actuator, or a pantograph device.	Preferred single-point truing method for profiles to be produced in quantities warranting the making of special profile bars or templates. Used also in small- and medium-volume production when the complexity of the profile to be produced excludes alternate methods of form generation.
Grinding Wheel Contouring by Crush Truing	A hardened steel or carbide roll, which is free to rotate and has the desired form of the workpiece, is fed gradually into the grinding wheel, which runs at slow speed. The roll will, by crushing action, produce its reverse form in the wheel. Crushing produces a free-cutting wheel face with sharp grains.	Requires grinding machines designed for crush truing, having stiff spindle bearings, rigid construction, slow wheel speed for truing, etc. Due to the cost of crush rolls and equipment, the process is used for repetitive work only. It is one of the most efficient methods for precisely duplicating complex wheel profiles that are capable of grinding in the 8-microinch AA range. Applicable for both surface and cylindrical grinding.
Rotating Diamond Roll-Type Grinding Wheel Truing	Special rolls made to agree with specific profile specifications have their periphery coated with a large number of uniformly distributed diamonds, held in a matrix into which the individual stones are set by hand (for larger diamonds) or bonded by a plating process (for smaller elements).	The diamond rolls must be rotated by an air, hydraulic, or electric motor at about one-fourth of the grinding wheel surface speed and in opposite direction to the wheel rotation. Whereas the initial costs are substantially higher than for single-point diamond truing the savings in truing time warrants the method's application in large-volume production of profile-ground components.
Diamond Dressing Blocks	Made as flat blocks for straight wheel surfaces, are also available for radius dressing and profile truing. The working surface consists of a layer of electroplated diamond grains, uniformly distributed and capable of truing even closely toleranced profiles.	For straight wheels, dressing blocks can reduce dressing time and offer easy installation on surface grinders, where the blocks mount on the magnetic plate. Recommended for small- and medium-volume production for truing intricate profiles on regular surface grinders, because the higher pressure developed in crush dressing is avoided.

Guidelines for Truing and Dressing with Single-Point Diamonds.— The diamond nib should be canted at an angle of 10 to 15 degrees in the direction of the wheel rotation and also, if possible, by the same amount in the direction of the cross feed traverse during the truing (see diagram). The dragging effect resulting from this "angling," combined with the occasional rotation of the diamond nib in its holder, will prolong the diamond life by limiting the extent of wear facets and will also tend to produce a pyramid shape of the diamond tip. The diamond may also be set to contact the wheel at about $\frac{1}{8}$ to $\frac{1}{4}$ inch below its centerline.

Depth of Cut: This amount should not exceed 0.001 inch per pass for general work, and will have to be reduced to 0.0002 to 0.0004 inch per pass for wheels with fine grains used for precise finishing work.

Diamond crossfeed rate: This value may be varied to some extent depending on the required wheel surface: faster crossfeed for free cutting, and slower crossfeed for produc-

Copyright 2004, Industrial Press, Inc., New York, NY

ing fine finishes. Such variations, however, must always stay within the limits set by the grain size of the wheel. Thus, the advance rate of the truing diamond per wheel revolution should not exceed the diameter of a grain or be less than half of that rate. Consequently, the diamond crossfeed must be slower for a large wheel than for a smaller wheel having the same grain size number.

Typical crossfeed values for frequently used grain sizes are given in Table 2.



Table 2. Typical Diamond Truing and Crossfeeds

Grain Size	30	36	46	50
Crossfeed per Wheel Rev., in.	0.014–0.024	0.012–0.019	0.008–0.014	0.007–0.012
Grain Size	60	80	120	…
Crossfeed per Wheel Rev., in.	0.006–0.010	0.004–0.007	0.0025–0.004	…

These values can be easily converted into the more conveniently used inch-per-minute units, simply by multiplying them by the rpm of the grinding wheel.

Example: For a 20-inch diameter wheel, Grain No. 46, running at 1200 rpm: Crossfeed rate for roughing-cut truing—approximately 17 ipm, for finishing-cut truing—approximately 10 ipm

Coolant should be applied before the diamond comes into contact with the wheel and must be continued in generous supply while truing.

The speed of the grinding wheel should be at the regular grinding rate, or not much lower. For that reason, the feed wheels of centerless grinding machines usually have an additional speed rate higher than functionally needed, that speed being provided for wheel truing only.

The initial approach of the diamond to the wheel surface must be carried out carefully to prevent sudden contact with the diamond, resulting in penetration in excess of the selected depth of cut. It should be noted that the highest point of a worn wheel is often in its center portion and not at the edge from which the crossfeed of the diamond starts.

The general conditions of the truing device are important for best truing results and for assuring extended diamond life. A rigid truing spindle, well-seated diamond nib, and firmly set diamond point are mandatory. Sensitive infeed and smooth traverse movement at uniform speed also must be maintained.

Resetting of the diamond point.: Never let the diamond point wear to a degree where the grinding wheel is in contact with the steel nib. Such contact can damage the setting of the diamond point and result in its loss. Expert resetting of a worn diamond can repeatedly add to its useful life, even when applied to lighter work because of reduced size.

Copyright 2004, Industrial Press, Inc., New York, NY

Size Selection Guide for Single-Point Truing Diamonds.— There are no rigid rules for determining the proper size of the diamond for any particular truing application because of the very large number of factors affecting that choice. Several of these factors are related to the condition, particularly the rigidity, of the grinding machine and truing device, as well as to such characteristics of the diamond itself as purity, crystalline structure, etc. Although these factors are difficult to evaluate in a generally applicable manner, the expected effects of several other conditions can be appraised and should be considered in the selection of the proper diamond size.

The recommended sizes in Table 3 must be considered as informative only and as representing minimum values for generally favorable conditions. Factors calling for larger diamond sizes than listed are the following:

Silicon carbide wheels (Table 3 refers to aluminum oxide wheels)
Dry truing
Grain sizes coarser than No. 46
Bonds harder than M
Wheel speed substantially higher than 6500 sfm.

It is advisable to consider any single or pair of these factors as justifying the selection of one size larger diamond. As an example: for truing an SiC wheel, with grain size No. 36 and hardness P, select a diamond that is two sizes larger than that shown in Table 3 for the wheel size in use.

Table 3. Recommended Minimum Sizes for Single-Point Truing Diamonds

Diamond Size in Carats[a]	Index Number (Wheel Dia. × Width in Inches)	Examples of Max. Grinding Wheel Dimensions	
		Diameter	Width
0.25	3	4	0.75
0.35	6	6	1
0.50	10	8	1.25
0.60	15	10	1.50
0.75	21	12	1.75
1.00	30	12	2.50
1.25	48	14	3.50
1.50	65	16	4.00
1.75	80	20	4.00
2.00	100	20	5.00
2.50	150	24	6.00
3.00	200	24	8.00
3.50	260	30	8.00
4.00	350	36	10.00

[a] One carat equals 0.2 gram.

Single-point diamonds are available as loose stones, but are preferably procured from specialized manufacturers supplying the diamonds set into steel nibs. Expert setting, comprising both the optimum orientation of the stone and its firm retainment, is mandatory for assuring adequate diamond life and satisfactory truing. Because the holding devices for truing diamonds are not yet standardized, the required nib dimensions vary depending on the make and type of different grinding machines. Some nibs are made with angular heads, usually hexagonal, to permit occasional rotation of the nib either manually, with a wrench, or automatically.

Copyright 2004, Industrial Press, Inc., New York, NY

Diamond Wheels

Diamond Wheels.— A diamond wheel is a special type of grinding wheel in which the abrasive elements are diamond grains held in a bond and applied to form a layer on the operating face of a non-abrasive core. Diamond wheels are used for grinding very hard or highly abrasive materials. Primary applications are the grinding of cemented carbides, such as the sharpening of carbide cutting tools; the grinding of glass, ceramics, asbestos, and cement products; and the cutting and slicing of germanium and silicon.

Shapes of Diamond Wheels.— The industry-wide accepted Standard (ANSI B74.3-1974) specifies ten basic diamond wheel core shapes which are shown in Table 1 with the applicable designation symbols. The applied diamond abrasive layer may have different cross-sectional shapes. Those standardized are shown in Table 2. The third aspect which is standardized is the location of the diamond section on the wheel as shown by the diagrams in Table 3. Finally, modifications of the general core shape together with pertinent designation letters are given in Table 4.

The characteristics of the wheel shape listed in these four tables make up the components of the standard designation symbol for diamond wheel shapes. An example of that symbol with arbitrarily selected components is shown in Fig. 1.



Fig. 1. A Typical Diamond Wheel Shape Designation Symbol

An explanation of these components is as follows:

Basic Core Shape: This portion of the symbol indicates the basic shape of the core on which the diamond abrasive section is mounted. The shape is actually designated by a number. The various core shapes and their designations are given in Table 1.

Diamond Cross-Section Shape: This, the second component, consisting of one or two letters, denotes the cross-sectional shape of the diamond abrasive section. The various shapes and their corresponding letter designations are given in Table 2.

Diamond Section Location: The third component of the symbol consists of a number which gives the location of the diamond section, i.e., periphery, side, corner, etc. An explanation of these numbers is shown in Table 3.

Modification: The fourth component of the symbol is a letter designating some modification, such as drilled and counterbored holes for mounting or special relieving of diamond section or core. This modification position of the symbol is used only when required. The modifications and their designations are given in Table 4.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Diamond Wheel Core Shapes and Designations *ANSI B74.3-1974*

1 	9 
2	11 
3 	12 
4 	14 
6 	15

Table 2. Diamond Cross-sections and Designations
ANSI B74.3-1974

A	CH	ER	GN	LL	S
AH	D	ET	H	M	U
B	DD	F	J	P	V
BT	E	FF	K	Q	Y
C	EE	G	L	QQ	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Designations for Location of Diamond Section on Diamond Wheel *ANSI B74.3-1974*

Designation No. and Location	Description	Illustration
1 — Periphery	The diamond section shall be placed on the periphery of the core and shall extend the full thickness of the wheel. The axial length of this section may be greater than, equal to, or less than the depth of diamond, measured radially. A hub or hubs shall not be considered as part of the wheel thickness for this definition.	
2 — Side	The diamond section shall be placed on the side of the wheel and the length of the diamond section shall extend from the periphery toward the center. It may or may not include the entire side and shall be greater than the diamond depth measured axially. It shall be on that side of the wheel which is commonly used for grinding purposes.	
3 — Both Sides	The diamond sections shall be placed on both sides of the wheel and shall extend from the periphery toward the center. They may or may not include the entire sides, and the radial length of the diamond section shall exceed the axial diamond depth.	
4 — Inside Bevel or Arc	This designation shall apply to the general wheel types 2, 6, 11, 12, and 15 and shall locate the diamond section on the side wall. This wall shall have an angle or arc extending from a higher point at the wheel periphery to a lower point toward the wheel center.	
5 — Outside Bevel or Arc	This designation shall apply to the general wheel types, 2, 6, 11, and 15 and shall locate the diamond section on the side wall. This wall shall have an angle or arc extending from a lower point at the wheel periphery to a higher point toward the wheel center.	
6 — Part of Periphery	The diamond section shall be placed on the periphery of the core but shall not extend the full thickness of the wheel and shall not reach to either side.	
7 — Part of Side	The diamond section shall be placed on the side of the core and shall not extend to the wheel periphery. It may or may not extend to the center.	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Designations for Location of Diamond Section on Diamond Wheel** *ANSI B74.3-1974*

Designation No. and Location	Description	Illustration
8 — Throughout	Designates wheels of solid diamond abrasive section without cores.	
9 — Corner	Designates a location which would commonly be considered to be on the periphery except that the diamond section shall be on the corner but shall not extend to the other corner.	
10 — Annular	Designates a location of the diamond abrasive section on the inner annular surface of the wheel.	

Composition of Diamond and Cubic Boron Nitride Wheels.— According to American National Standard ANSI B74.13-1990, a series of symbols is used to designate the composition of these wheels. An example is shown below.

Prefix	Abrasive	Grain Size	Grade	Concentration	Bond Type	Bond Modification	Depth of Abrasive	Manufacturer's Identification Symbol
M	D	120	R	100	B	56	1/8	*

Fig. 2. Designation Symbols for Composition of Diamond and Cubic Boron Nitride Wheels

The meaning of each symbol is indicated by the following list:

1) *Prefix:* The prefix is a manufacturer's symbol indicating the exact kind of abrasive. Its use is optional.

2) *Abrasive Type:* The letter (B) is used for cubic boron nitride and (D) for diamond.

3) *Grain Size:* The grain sizes commonly used and varying from coarse to very fine are indicated by the following numbers: 8, 10, 12, 14, 16, 20, 24, 30, 36, 46, 54, 60, 70, 80, 90, 100, 120, 150, 180, and 220. The following additional sizes are used occasionally: 240, 280, 320, 400, 500, and 600. The wheel manufacturer may add to the regular grain number an additional symbol to indicate a special grain combination.

4) *Grade:* Grades are indicated by letters of the alphabet from A to Z in all bonds or processes. Wheel grades from A to Z range from soft to hard.

5) *Concentration:* The concentration symbol is a manufacturer's designation. It may be a number or a symbol.

6) *Bond:* Bonds are indicated by the following letters: B, resinoid; V, vitrified; M, metal.

7) *Bond Modification:* Within each bond type a manufacturer may have modifications to tailor the bond to a specific application. These modifications may be identified by either letters or numbers.

8) *Abrasive Depth:* Abrasive section depth, in inches or millimeters (inches illustrated), is indicated by a number or letter which is the amount of total dimensional wear a user may expect from the abrasive portion of the product. Most diamond and CBN wheels are made with a depth of coating on the order of $\frac{1}{16}$ in., $\frac{1}{8}$ in., or more as specified. In some cases the diamond is applied in thinner layers, as thin as one thickness of diamond grains. The L is included in the marking system to identify a layered type product.

9) *Manufacturer's Identification Symbol:* The use of this symbol is optional.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Designation Letters for Modifications of Diamond Wheels
ANSI B74.3-1974

Designation Letter[a]	Description	Illustration
B — Drilled and Counterbored	Holes drilled and counterbored in core.	
C — Drilled and Countersunk	Holes drilled and countersunk in core.	
H — Plain Hole	Straight hole drilled in core.	
M — Holes Plain and Threaded	Mixed holes, some plain, some threaded, are in core.	
P — Relieved One Side	Core relieved on one side of wheel. Thickness of core is less than wheel thickness.	
R — Relieved Two Sides	Core relieved on both sides of wheel. Thickness of core is less than wheel thickness.	
S — Segmented-Diamond Section	Wheel has segmental diamond section mounted on core. (Clearance between segments has no bearing on definition.)	
SS — Segmental and Slotted	Wheel has separated segments mounted on a slotted core.	
T — Threaded Holes	Threaded holes are in core.	
Q — Diamond Inserted	Three surfaces of the diamond section are partially or completely enclosed by the core.	
V — Diamond Inverted	Any diamond cross section, which is mounted on the core so that the interior point of any angle, or the concave side of any arc, is exposed shall be considered inverted. *Exception:* Diamond cross section AH shall be placed on the core with the concave side of the arc exposed.	

[a] Y — Diamond Inserted and Inverted. See definitions for Q and V.

Copyright 2004, Industrial Press, Inc., New York, NY

The Selection of Diamond Wheels.— Two general aspects must be defined: (a) The shape of the wheel, also referred to as the basic wheel type and (b) The specification of the abrasive portion.

Table 5. General Diamond Wheel Recommendations for Wheel Type and Abrasive Specification

Typical Applications or Operation	Basic Wheel Type	Abrasive Specification
Single Point Tools (offhand grinding)	D6A2C	*Rough:* MD100-N100-B1/8 *Finish:* MD220-P75-B1/8
Single Point Tools (machine ground)	D6A2H	*Rough:* MD180-J100-B1/8 *Finish:* MD320-L75-B1/8
Chip Breakers	D1A1	MD150-R100-B1/8
Multitooth Tools and Cutters (face mills, end mills, reamers, broaches, etc.)		
Sharpening and Backing off	D11V9	Rough: MD100-R100-B1/8 Combination: MD150-R100-B1/8 *Finish:* MD220-R100-B1/8
Fluting	D12A2	MD180-N100-B1/8
Saw Sharpening	D12A2	MD180-R100-B1/8
Surface Grinding (horizontal spindle)	D1A1	*Rough:* MD120-N100-B1/8 *Finish:* MD240-P100-B1/8
Surface Grinding (vertical spindle)	D2A2T	MD80-R75-B1/8
Cylindrical or Centertype Grinding	D1A1	MD120-P100-B1/8
Internal Grinding	D1A1	MD150-N100-B1/8
Slotting and Cutoff	D1A1R	MD150-R100-B1/4
Lapping	Disc	MD400-L50-B1/16
Hand Honing	DH1, DH2	*Rough:* MD220-B1/16 *Finish:* MD320-B1/6

General recommendations for the dry grinding, with resin bond diamond wheels, of most grades of cemented carbides of average surface to ordinary finishes at normal rates of metal removal with average size wheels, as published by Cincinnati Milacron, are listed in Table 5.

A further set of variables are *the dimensions of the wheel*, which must be adapted to the available grinding machine and, in some cases, to the configuration of the work.

The general abrasive specifications in Table 5 may be modified to suit operating conditions by the following suggestions:

Use softer wheel grades for harder grades of carbides, for grinding larger areas or larger or wider wheel faces.

Use harder wheel grades for softer grades of carbides, for grinding smaller areas, for using smaller and narrower face wheels and for light cuts.

Copyright 2004, Industrial Press, Inc., New York, NY

Use fine grit sizes for harder grades of carbides and to obtain better finishes.
Use coarser grit sizes for softer grades of carbides and for roughing cuts.
Use higher diamond concentration for harder grades of carbides, for larger diameter or wider face wheels, for heavier cuts, and for obtaining better finish.

Guidelines for the Handling and Operation of Diamond Wheels.— Grinding machines used for grinding with diamond wheels should be of the precision type, in good service condition, with true running spindles and smooth slide movements.

Mounting of Diamond Wheels: Wheel mounts should be used which permit the precise centering of the wheel, resulting in a runout of less than 0.001 inch axially and 0.0005 inch radially. These conditions should be checked with a 0.0001-inch type dial indicator. Once mounted and centered, the diamond wheel should be retained on its mount and stored in that condition when temporarily removed from the machine.

Truing and Dressing: Resinoid bonded diamond wheels seldom require dressing, but when necessary a soft silicon carbide stick may be hand-held against the wheel. Peripheral and cup type wheels may be sharpened by grinding the cutting face with a 60 to 80 grit silicon carbide wheel. This can be done with the diamond wheel mounted on the spindle of the machine, and with the silicon carbide wheel driven at a relatively slow speed by a specially designed table-mounted grinder or by a small table-mounted tool post grinder. The diamond wheel can be mounted on a special arbor and ground on a lathe with a tool post grinder; peripheral wheels can be ground on a cylindrical grinder or with a special brake-controlled truing device with the wheel mounted on the machine on which it is used. Cup and face type wheels are often lapped on a cast iron or glass plate using a 100 grit silicon carbide abrasive. Care must be used to lap the face parallel to the back, otherwise they must be ground to restore parallelism. Peripheral diamond wheels can be trued and dressed by grinding a silicon carbide block or a special diamond impregnated bronze block in a manner similar to surface grinding. Conventional diamonds must not be used for truing and dressing diamond wheels.

Speeds and Feeds in Diamond Grinding.— General recommendations are as follows:

Wheel Speeds: The generally recommended wheel speeds for diamond grinding are in the range of 5000 to 6000 surface feet per minute, with this upper limit as a maximum to avoid harmful "overspeeding." Exceptions from that general rule are diamond wheels with coarse grains and high concentration (100 per cent) where the wheel wear in dry surface grinding can be reduced by lowering the speed to 2500–3000 sfpm. However, this lower speed range can cause rapid wheel breakdown in finer grit wheels or in those with reduced diamond concentration.

Work Speeds: In diamond grinding, work rotation and table traverse are usually established by experience, adjusting these values to the selected infeed so as to avoid excessive wheel wear.

Infeed per Pass: Often referred to as downfeed and usually a function of the grit size of the wheel. The following are general values which may be increased for raising the productivity, or lowered to improve finish or to reduce wheel wear.

Wheel Grit Size Range	Infeed per Pass
100 to 120	0.001 inch
150 to 220	0.0005 inch
250 and finer	0.00025 inch

Grinding Wheel Safety

Safety in Operating Grinding Wheels.— Grinding wheels, although capable of exceptional cutting performance due to hardness and wear resistance, are prone to damage caused by improper handling and operation. Vitrified wheels, comprising the major part of grinding wheels used in industry, are held together by an inorganic bond which is actually

Copyright 2004, Industrial Press, Inc., New York, NY

a type of pottery product and therefore brittle and breakable. Although most of the organic bond types are somewhat more resistant to shocks, it must be realized that all grinding wheels are conglomerates of individual grains joined by a bond material whose strength is limited by the need of releasing the dull, abrasive grains during use.

It must also be understood that during the grinding process very substantial forces act on the grinding wheel, including the centrifugal force due to rotation, the grinding forces resulting from the resistance of the work material, and shocks caused by sudden contact with the work. To be able to resist these forces, the grinding wheel must have a substantial minimum strength throughout that is well beyond that needed to hold the wheel together under static conditions.

Finally, a damaged grinding wheel can disintegrate during grinding, liberating dormant forces which normally are constrained by the resistance of the bond, thus presenting great hazards to both operator and equipment.

To avoid breakage of the operating wheel and, should such a mishap occur, to prevent damage or injury, specific precautions must be applied. These safeguards have been formulated into rules and regulations and are set forth in the American National Standard ANSI B7.1-1988, entitled the American National Standard Safety Requirements for the Use, Care, and Protection of Abrasive Wheels.

Handling, Storage and Inspection.— Grinding wheels should be hand carried, or transported, with proper support, by truck or conveyor. A grinding wheel must not be rolled around on its periphery.

The storage area, positioned not far from the location of the grinding machines, should be free from excessive temperature variations and humidity. Specially built racks are recommended on which the smaller or thin wheels are stacked lying on their sides and the larger wheels in an upright position on two-point cradle supports consisting of appropriately spaced wooden bars. Partitions should separate either the individual wheels, or a small group of identical wheels. Good accessibility to the stored wheels reduces the need of undesirable handling.

Inspection will primarily be directed at detecting visible damage, mostly originating from handling and shipping. Cracks which are not obvious can usually be detected by "ring testing," which consists of suspending the wheel from its hole and tapping it with a nonmetallic implement. Heavy wheels may be allowed to rest vertically on a clean, hard floor while performing this test. A clear metallic tone, a "ring", should be heard; a dead sound being indicative of a possible crack or cracks in the wheel.

Machine Conditions.— The general design of the grinding machines must ensure safe operation under normal conditions. The bearings and grinding wheel spindle must be dimensioned to withstand the expected forces and ample driving power should be provided to ensure maintenance of the rated spindle speed. For the protection of the operator, stationary machines used for dry grinding should have a provision made for connection to an exhaust system and when used for off-hand grinding, a work support must be available.

Wheel guards are particularly important protection elements and their material specifications, wall thicknesses and construction principles should agree with the Standard's specifications. The exposure of the wheel should be just enough to avoid interference with the grinding operation. The need for access of the work to the grinding wheel will define the boundary of guard opening, particularly in the direction of the operator.

Grinding Wheel Mounting.— The mass and speed of the operating grinding wheel makes it particularly sensitive to imbalance. Vibrations that result from such conditions are harmful to the machine, particularly the spindle bearings, and they also affect the ground surface, i.e., wheel imbalance causes chatter marks and interferes with size control. Grinding wheels are shipped from the manufacturer's plant in a balanced condition, but retaining the balanced state after mounting the wheel is quite uncertain. Balancing of the mounted wheel is thus required, and is particularly important for medium and large size

Copyright 2004, Industrial Press, Inc., New York, NY

wheels, as well as for producing acccurate and smooth surfaces. The most common way of balancing mounted wheels is by using balancing flanges with adjustable weights. The wheel and balancing flanges are mounted on a short balancing arbor, the two concentric and round stub ends of which are supported in a balancing stand.

Such stands are of two types: 1) the parallel straight-edged, which must be set up precisely level; and 2) the disk type having two pairs of ball bearing mounted overlapping disks, which form a V for containing the arbor ends without hindering the free rotation of the wheel mounted on that arbor.

The wheel will then rotate only when it is out of balance and its heavy spot is not in the lowest position. Rotating the wheel by hand to different positions will move the heavy spot, should such exist, from the bottom to a higher location where it can reveal its presence by causing the wheel to turn. Having detected the presence and location of the heavy spot, its effect can be cancelled by displacing the weights in the circular groove of the flange until a balanced condition is accomplished.

Flanges are commonly used means for holding grinding wheels on the machine spindle. For that purpose, the wheel can either be mounted directly through its hole or by means of a sleeve which slips over a tapered section of the machine spindle. Either way, the flanges must be of equal diameter, usually not less than one-third of the new wheel's diameter. The purpose is to securely hold the wheel between the flanges without interfering with the grinding operation even when the wheel becomes worn down to the point where it is ready to be discarded. Blotters or flange facings of compressible material should cover the entire contact area of the flanges.

One of the flanges is usually fixed while the other is loose and can be removed and adjusted along the machine spindle. The movable flange is held against the mounted grinding wheel by means of a nut engaging a threaded section of the machine spindle. The sense of that thread should be such that the nut will tend to tighten as the spindle revolves. In other words, to remove the nut, it must be turned in the direction that the spindle revolves when the wheel is in operation.

Safe Operating Speeds.— Safe grinding processes are predicated on the proper use of the previously discussed equipment and procedures, and are greatly dependent on the application of adequate operating speeds.

The Standard establishes maximum speeds at which grinding wheels can be operated, assigning the various types of wheels to several classification groups. Different values are listed according to bond type and to wheel strength, distinguishing between low, medium and high strength wheels.

For the purpose of general information, the accompanying table shows an abbreviated version of the Standard's specification. However, for the governing limits, the authoritative source is the manufacturer's tag on the wheel which, particularly for wheels of lower strength, might specify speeds below those of the table.

All grinding wheels of 6 inches or greater diameter must be test run in the wheel manufacturer's plant at a speed that for all wheels having operating speeds in excess of 5000 sfpm is 1.5 times the maximum speed marked on the tag of the wheel.

The table shows the permissible wheel speeds in surface feet per minute (sfpm) units, whereas the tags on the grinding wheels state, for the convenience of the user, the maximum operating speed in revolutions per minute (rpm). The sfpm unit has the advantage of remaining valid for worn wheels whose rotational speed may be increased to the applicable sfpm value. The conversion from either one to the other of these two kinds of units is a matter of simple calculation using the formulas:

$$\text{sfpm} = \text{rpm} \times \frac{D}{12} \times \pi \qquad \text{or} \qquad \text{rpm} = \frac{\text{sfpm} \times 12}{D \times \pi}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where D = maximum diameter of the grinding wheel, in inches. Table 2, showing the conversion values from surface speed into rotational speed, can be used for the direct reading of the rpm values corresponding to several different wheel diameters and surface speeds.

Special Speeds: Continuing progress in grinding methods has led to the recognition of certain advantages that can result from operating grinding wheels above, sometimes even higher than twice, the speeds considered earlier as the safe limits of grinding wheel operations. Advantages from the application of high speed grinding are limited to specific processes, but the Standard admits, and offers code regulations for the use of wheels at special high speeds. These regulations define the structural requirements of the grinding machine and the responsibilities of the grinding wheel manufacturers, as well as of the users. High speed grinding should not be applied unless the machines, particularly guards, spindle assemblies, and drive motors, are suitable for such methods. Also, appropriate grinding wheels expressly made for special high speeds must be used and, of course, the maximum operating speeds indicated on the wheel's tag must never be exceeded.

Portable Grinders.— The above discussed rules and regulations, devised primarily for stationary grinding machines apply also to portable grinders. In addition, the details of various other regulations, specially applicable to different types of portable grinders are discussed in the Standard, which should be consulted, particularly for safe applications of portable grinding machines.

Table 1. Maximum Peripheral Speeds for Grinding Wheels Based on *ANSI B7.1–1988*

Classification No.	Types of Wheels[a]	Maximum Operating Speeds, sfpm, Depending on Strength of Bond	
		Inorganic Bonds	Organic Bonds
1	Straight wheels — Type 1, except classifications 6, 7, 9, 10, 11, and 12 below Taper Side Wheels — Type 4[b] Types 5, 7, 20, 21, 22, 23, 24, 25, 26 Dish wheels — Type 12 Saucer wheels — Type 13 Cones and plugs — Types 16, 17, 18, 19	5,500 to 6,500	6,500 to 9,500
2	Cylinder wheels — Type 2 Segments	5,000 to 6,000	5,000 to 7,000
3	Cup shape tool grinding wheels — Types 6 and 11 (for fixed base machines)	4,500 to 6,000	6,000 to 8,500
4	Cup shape snagging wheels — Types 6 and 11 (for portable machines)	4,500 to 6,500	6,000 to 9,500
5	Abrasive disks	5,500 to 6,500	5,500 to 8,500
6	Reinforced wheels — except cutting-off wheels (depending on diameter and thickness)	…	9,500 to 16,000
7	Type 1 wheels for bench and pedestal grinders, Types 1 and 5 also in certain sizes for surface grinders	5,500 to 7,550	6,500 to 9,500
8	Diamond and cubic boron nitride wheels Metal bond Steel centered cutting off	to 6,500 to 12,000 to 16,000	to 9,500 … to 16,000
9	Cutting-off wheels — Larger than 16-inch diameter (incl. reinforced organic)	…	9,500 to 14,200
10	Cutting-off wheels — 16-inch diameter and smaller (incl. reinforced organic)	…	9,500 to 16,000
11	Thread and flute grinding wheels	8,000 to 12,000	8,000 to 12,000
12	Crankshaft and camshaft grinding wheels	5,500 to 8,500	6,500 to 9,500

[a] See Tables 1a and 1b starting on page 1181.

[b] Non-standard shape. For snagging wheels, 16 inches and larger — Type 1, internal wheels — Types 1 and 5, and mounted wheels, see ANSI B7.1–1988. Under no conditions should a wheel be operated faster than the maximum operating speed established by the manufacturer.

Values in this table are for general information only.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Revolutions per Minute for Various Grinding Speeds and Wheel Diameters (Based on *ANSI B7.1–1988*)

Wheel Diameter, Inch	Peripheral (Surface) Speed, Feet per Minute																Wheel Diameter, Inch
	4,000	4,500	5,000	5,500	6,000	6,500	7,000	7,500	8,000	8,500	9,000	9,500	10,000	12,000	14,000	16,000	
	Revolutions per Minute																
1	15,279	17,189	19,099	21,008	22,918	24,828	26,738	28,648	30,558	32,468	34,377	36,287	38,197	45,837	53,476	61,115	1
2	7,639	8,594	9,549	10,504	11,459	12,414	13,369	14,324	15,279	16,234	17,189	18,144	19,099	22,918	26,738	30,558	2
3	5,093	5,730	6,366	7,003	7,639	8,276	8,913	9,549	10,186	10,823	11,459	12,096	12,732	15,279	17,825	20,372	3
4	3,820	4,297	4,775	5,252	5,730	6,207	6,685	7,162	7,639	8,117	8,594	9,072	9,549	11,459	13,369	15,279	4
5	3,056	3,438	3,820	4,202	4,584	4,966	5,348	5,730	6,112	6,494	6,875	7,257	7,639	9,167	10,695	12,223	5
6	2,546	2,865	3,183	3,501	3,820	4,138	4,456	4,775	5,093	5,411	5,730	6,048	6,366	7,639	8,913	10,186	6
7	2,183	2,456	2,728	3,001	3,274	3,547	3,820	4,093	4,365	4,638	4,911	5,184	5,457	6,548	7,639	8,731	7
8	1,910	2,149	2,387	2,626	2,865	3,104	3,342	3,581	3,820	4,058	4,297	4,536	4,775	5,730	6,685	7,639	8
9	1,698	1,910	2,122	2,334	2,546	2,759	2,971	3,183	3,395	3,608	3,820	4,032	4,244	5,093	5,942	6,791	9
10	1,528	1,719	1,910	2,101	2,292	2,483	2,674	2,865	3,056	3,247	3,438	3,629	3,820	4,584	5,348	6,112	10
12	1,273	1,432	1,592	1,751	1,910	2,069	2,228	2,387	2,546	2,706	2,865	3,024	3,183	3,820	4,456	5,093	12
14	1,091	1,228	1,364	1,501	1,637	1,773	1,910	2,046	2,183	2,319	2,456	2,592	2,728	3,274	3,820	4,365	14
16	955	1,074	1,194	1,313	1,432	1,552	1,671	1,790	1,910	2,029	2,149	2,268	2,387	2,865	3,342	3,820	16
18	849	955	1,061	1,167	1,273	1,379	1,485	1,592	1,698	1,804	1,910	2,016	2,122	2,546	2,971	3,395	18
20	764	859	955	1,050	1,146	1,241	1,337	1,432	1,528	1,623	1,719	1,814	1,910	2,292	2,674	3,056	20
22	694	781	868	955	1,042	1,129	1,215	1,302	1,389	1,476	1,563	1,649	1,736	2,083	2,431	2,778	22
24	637	716	796	875	955	1,035	1,114	1,194	1,273	1,353	1,432	1,512	1,592	1,910	2,228	2,546	24
26	588	661	735	808	881	955	1,028	1,102	1,175	1,249	1,322	1,396	1,469	1,763	2,057	2,351	26
28	546	614	682	750	819	887	955	1,023	1,091	1,160	1,228	1,296	1,364	1,637	1,910	2,183	28
30	509	573	637	700	764	828	891	955	1,019	1,082	1,146	1,210	1,273	1,528	1,783	2,037	30
32	477	537	597	657	716	776	836	895	955	1,015	1,074	1,134	1,194	1,432	1,671	1,910	32
34	449	506	562	618	674	730	786	843	899	955	1,011	1,067	1,123	1,348	1,573	1,798	34
36	424	477	531	584	637	690	743	796	849	902	955	1,008	1,061	1,273	1,485	1,698	36
38	402	452	503	553	603	653	704	754	804	854	905	955	1,005	1,206	1,407	1,608	38
40	382	430	477	525	573	621	668	716	764	812	859	907	955	1,146	1,337	1,528	40
42	364	409	455	500	546	591	637	682	728	773	819	864	909	1,091	1,273	1,455	42
44	347	391	434	477	521	564	608	651	694	738	781	825	868	1,042	1,215	1,389	44
46	332	374	415	457	498	540	581	623	664	706	747	789	830	996	1,163	1,329	46
48	318	358	398	438	477	517	557	597	637	676	716	756	796	955	1,114	1,273	48
53	288	324	360	396	432	468	504	541	577	613	649	685	721	865	1,009	1,153	53
60	255	286	318	350	382	414	446	477	509	541	573	605	637	764	891	1,019	60
72	212	239	265	292	318	345	371	398	424	451	477	504	531	637	743	849	72

Copyright 2004, Industrial Press, Inc., New York, NY

Cylindrical Grinding

Cylindrical grinding designates a general category of various grinding methods that have the common characteristic of rotating the workpiece around a fixed axis while grinding outside surface sections in controlled relation to that axis of rotation.

The form of the part or section being ground in this process is frequently cylindrical, hence the designation of the general category. However, the shape of the part may be tapered or of curvilinear profile; the position of the ground surface may also be perpendicular to the axis; and it is possible to grind concurrently several surface sections, adjacent or separated, of equal or different diameters, located in parallel or mutually inclined planes, etc., as long as the condition of a common axis of rotation is satisfied.

Size Range of Workpieces and Machines: Cylindrical grinding is applied in the manufacture of miniature parts, such as instrument components and, at the opposite extreme, for grinding rolling mill rolls weighing several tons. Accordingly, there are cylindrical grinding machines of many different types, each adapted to a specific work-size range. Machine capacities are usually expressed by such factors as maximum work diameter, work length and weight, complemented, of course, by many other significant data.

Plain, Universal, and Limited-Purpose Cylindrical Grinding Machines.— The plain cylindrical grinding machine is considered the basic type of this general category, and is used for grinding parts with cylindrical or slightly tapered form.

The universal cylindrical grinder can be used, in addition to grinding the basic cylindrical forms, for the grinding of parts with steep tapers, of surfaces normal to the part axis, including the entire face of the workpiece, and for internal grinding independently or in conjunction with the grinding of the part's outer surfaces. Such variety of part configurations requiring grinding is typical of work in the tool room, which constitutes the major area of application for universal cylindrical grinding machines.

Limited-purpose cylindrical grinders are needed for special work configurations and for high-volume production, where productivity is more important than flexibility of adaptation. Examples of limited-purpose cylindrical grinding machines are crankshaft and camshaft grinders, polygonal grinding machines, roll grinders, etc.

Traverse or Plunge Grinding.— In traverse grinding, the machine table carrying the work performs a reciprocating movement of specific travel length for transporting the rotating workpiece along the face of the grinding wheel. At each or at alternate stroke ends, the wheel slide advances for the gradual feeding of the wheel into the work. The length of the surface that can be ground by this method is generally limited only by the stroke length of the machine table. In large roll grinders, the relative movement between work and wheel is accomplished by the traverse of the wheel slide along a stationary machine table.

In plunge grinding, the machine table, after having been set, is locked and, while the part is rotating, the wheel slide continually advances at a preset rate, until the finish size of the part is reached. The width of the grinding wheel is a limiting factor of the section length that can be ground in this process. Plunge grinding is required for profiled surfaces and for the simultaneous grinding of multiple surfaces of different diameters or located in different planes.

When the configuration of the part does not make use of either method mandatory, the choice may be made on the basis of the following general considerations: traverse grinding usually produces a better finish, and the productivity of plunge grinding is generally higher.

Work Holding on Cylindrical Grinding Machines.— The manner in which the work is located and held in the machine during the grinding process determines the configuration of the part that can be adapted for cylindrical grinding and affects the resulting accuracy of the ground surface. The method of work holding also affects the attainable production rate, because the mounting and dismounting of the part can represent a substantial portion of the total operating time.

Copyright 2004, Industrial Press, Inc., New York, NY

Whatever method is used for holding the part on cylindrical types of grinding machines, two basic conditions must be satisfied: 1) the part should be located with respect to its correct axis of rotation; and 2) the work drive must cause the part to rotate, at a specific speed, around the established axis.

The lengthwise location of the part, although controlled, is not too critical in traverse grinding; however, in plunge grinding, particularly when shoulder sections are also involved, it must be assured with great accuracy.

Table 1 presents a listing, with brief discussions, of work-holding methods and devices that are most frequently used in cylindrical grinding.

Table 1. Work-Holding Methods and Devices for Cylindrical Grinding

Designation	Description	Discussion
Centers, nonrotating ("dead"), with drive plate	Headstock with nonrotating spindle holds the center. Around the spindle, an independently supported sleeve carries the drive plate for rotating the work. Tailstock for opposite center.	The simplest method of holding the work between two opposite centers is also the potentially most accurate, as long as correctly prepared and located center holes are used in the work.
Centers, driving type	Word held between two centers obtains its rotation from the concurrently applied drive by the live headstock spindle and live tailstock spindle.	Eliminates the drawback of the common center-type grinding with driver plate, which requires a dog attached to the workpiece. Driven spindles permit the grinding of the work up to both ends.
Chuck, geared, or cam-actuated	Two, three, or four jaws moved radially through mechanical elements, hand-, or power-operated, exert concentrically acting clamping force on the workpiece.	Adaptable to workpieces of different configurations and within a generally wide capacity of the chuck. Flexible in uses that, however, do not include high-precision work.
Chuck, diaphragm	Force applied by hand or power of a flexible diaphragm causes the attached jaws to deflect temporarily for accepting the work, which is held when force is released.	Rapid action and flexible adaptation to different work configurations by means of special jaws offer varied uses for the grinding of disk-shaped and similar parts.
Collets	Holding devices with externally or internally acting clamping force, easily adaptable to power actuation, assuring high centering accuracy.	Limited to parts with previously machined or ground holding surfaces, because of the small range of clamping movement of the collet jaws.
Face plate	Has four independently actuated jaws, any or several of which may be used, or entirely removed, using the base plate for supporting special clamps.	Used for holding bulky parts, or those of awkward shape, which are ground in small quantities not warranting special fixtures.
Magnetic plate	Flat plates, with pole distribution adapted to the work, are mounted on the spindle like chucks and may be used for work with the locating face normal to the axis.	Applicable for light cuts such as are frequent in tool making, where the rapid clamping action and easy access to both the O.D. and the exposed face are sometimes of advantage.
Steady rests	Two basic types are used: (a) the two-jaw type supporting the work from the back (back rest), leaving access by the wheel; (b) the three-jaw type (center rest).	A complementary work-holding device, used in conjunction with primary work holders, to provide additional support, particularly to long and/or slender parts.
Special fixtures	Single-purpose devices, designed for a particular workpiece, primarily for providing special locating elements.	Typical workpieces requiring special fixturing are, as examples, crankshafts where the holding is combined with balancing functions; or internal gears located on the pitch circle of the teeth for O.D. grinding.

Selection of Grinding Wheels for Cylindrical Grinding.— For cylindrical grinding, as for grinding in general, the primary factor to be considered in wheel selection is the work material. Other factors are the amount of excess stock and its rate of removal (speeds and feeds), the desired accuracy and surface finish, the ratio of wheel and work diameter, wet or dry grinding, etc. In view of these many variables, it is not practical to set up a complete

Copyright 2004, Industrial Press, Inc., New York, NY

list of grinding wheel recommendations with general validity. Instead, examples of recommendations embracing a wide range of typical applications and assuming common practices are presented in Table 2. This is intended as a guide for the starting selection of grinding-wheel specifications which, in case of a not entirely satisfactory performance, can be refined subsequently. The content of the table is a version of the grinding-wheel recommendations for cylindrical grinding by the Norton Company using, however, non-proprietary designations for the abrasive types and bonds.

Table 2. Wheel Recommendations for Cylindrical Grinding

Material	Wheel Marking	Material	Wheel Marking
Aluminum	SFA46-18V	Forgings	A46-M5V
Armatures (laminated)	SFA100-18V	Gages (plug)	SFA80-K8V
Axles (auto & railway)	A54-M5V	General-purpose grinding	SFA54-L5V
Brass	C36-KV	Glass	BFA220-011V
Bronze		Gun barrels	
Soft	C36-KV	Spotting and O.D.	BFA60-M5V
Hard	A46-M5V	Nitralloy	
Bushings (hardened steel)	BFA60-L5V	Before nitriding	A60-K5V
Bushings (cast iron)	C36-JV	After nitriding	
Cam lobes (cast alloy)		Commercial finish	SFA60-18V
Roughing	BFA54-N5V	High finish	C100-1V
Finishing	A70-P6B	Reflective finish	C500-19E
Cam lobes (hardened steel)		Pistons (aluminum)	SFA46-18V
Roughing	BFA54-L5V	(cast iron)	C36-KV
Finishing	BFA80-T8B	Plastics	C46-JV
Cast iron	C36-JV	Rubber	
Chromium plating		Soft	SFA20-K5B
Commercial finish	SFA60-J8V	Hard	C36-KB
High finish	A150-K5E	Spline shafts	SFA60-N5V
Reflective finish	C500-I9E	Sprayed metal	C60-JV
Commutators (copper)	C60-M4E	Steel	
Crankshafts (airplane)		Soft	
Pins	BFA46-K5V	1 in. dia. and smaller	SFA60-M5V
Bearings	A46-L5V	over 1 in dia.	SFA46-L5V
Crankshafts (automotive		Hardened	
pins and bearings)		1 in. dia. and smaller	SFA80-L8V
Finishing	A54-N5V	over 1 in. dia.	SFA60-K5V
Roughing & finishing	A54-O5V	300 series stainless	SFA46-K8V
Regrinding	A54-M5V	Stellite	BFA46-M5V
Regrinding, sprayed		Titanium	C60-JV
metal	C60-JV	Valve stems (automative)	BFA54-N5V
Drills	BFA54-N5V	Valve tappets	BFA54-M5V

Note: Prefixes to the standard designation "A" of aluminum oxide indicate modified abrasives as follows: BFA = Blended friable (a blend of regular and friable), SFA = Semifriable.

Operational Data for Cylindrical Grinding.— In cylindrical grinding, similarly to other metalcutting processes, the applied speed and feed rates must be adjusted to the operational conditions as well as to the objectives of the process. Grinding differs, however, from other types of metalcutting methods in regard to the cutting speed of the tool which, in grinding, is generally not a variable; it should be maintained at, or close to the optimum rate, commonly 6500 feet per minute peripheral speed.

In establishing the proper process values for grinding, of prime consideration are the work material, its condition (hardened or soft), and the type of operation (roughing or finishing). Other influencing factors are the characteristics of the grinding machine (stability, power), the specifications of the grinding wheel, the material allowance, the rigidity and

Copyright 2004, Industrial Press, Inc., New York, NY

balance of the workpiece, as well as several grinding process conditions, such as wet or dry grinding, the manner of wheel truing, etc.

Variables of the cylindrical grinding process, often referred to as *grinding data*, comprise the speed of work rotation (measured as the surface speed of the work); the infeed (in inches per pass for traverse grinding, or in inches per minute for plunge grinding); and, in the case of traverse grinding, the speed of the reciprocating table movement (expressed either in feet per minute, or as a fraction of the wheel width for each revolution of the work).

For the purpose of starting values in setting up a cylindrical grinding process, a brief listing of basic data for common cylindrical grinding conditions and involving frequently used materials, is presented in Table 3.

Table 3. Basic Process Data for Cylindrical Grinding

Traverse Grinding						
Work Material	Material Condition	Work Surface Speed, fpm	Infeed, Inch/Pass		Traverse for Each Work Revolution, In Fractions of the Wheel Width	
			Roughing	Finishing	Roughing	Finishing
Plain Carbon Steel	Annealed	100	0.002	0.0005	1/2	1/6
	Hardened	70	0.002	0.0003–0.0005	1/4	1/8
Alloy Steel	Annealed	100	0.002	0.0005	1/2	1/6
	Hardened	70	0.002	0.0002–0.0005	1/4	1/8
Tool Steel	Annealed	60	0.002	0.0005 max.	1/2	1/6
	Hardened	50	0.002	0.0001–0.0005	1/4	1/8
Copper Alloys	Annealed or Cold Drawn	100	0.002	0.0005 max.	1/3	1/6
Aluminum Alloys	Cold Drawn or Solution Treated	150	0.002	0.0005 max.	1/3	1/6

Plunge Grinding		
Work Material	Infeed per Revolution of the Work, Inch	
	Roughing	Finishing
Steel, soft	0.0005	0.0002
Plain carbon steel, hardened	0.0002	0.000050
Alloy and tool steel, hardened	0.0001	0.000025

These data, which are, in general, considered conservative, are based on average operating conditions and may be modified subsequently by: a) reducing the values in case of unsatisfactory quality of the grinding or the occurrence of failures; and b) increasing the rates for raising the productivity of the process, particularly for rigid workpieces, substantial stock allowance, etc.

High-Speed Cylindrical Grinding.— The maximum peripheral speed of the wheels in regular cylindrical grinding is generally 6500 feet per minute; the commonly used grinding wheels and machines are designed to operate efficiently at this speed. Recently, efforts were made to raise the productivity of different grinding methods, including cylindrical grinding, by increasing the peripheral speed of the grinding wheel to a substantially higher than traditional level, such as 12,000 feet per minute or more. Such methods are designated by the distinguishing term of high-speed grinding.

For high-speed grinding, special grinding machines have been built with high dynamic stiffness and static rigidity, equipped with powerful drive motors, extra-strong spindles and bearings, reinforced wheel guards, etc., and using grinding wheels expressly made and tested for operating at high peripheral speeds. The higher stock-removal rate accomplished by high-speed grinding represents an advantage when the work configuration and material permit, and the removable stock allowance warrants its application.

Copyright 2004, Industrial Press, Inc., New York, NY

CAUTION: High-speed grinding must *not* be applied on standard types of equipment, such as general types of grinding machines and regular grinding wheels. Operating grinding wheels, even temporarily, at higher than approved speed constitutes a grave safety hazard.

Areas and Degrees of Automation in Cylindrical Grinding.— Power drive for the work rotation and for the reciprocating table traverse are fundamental machine movements that, once set for a certain rate, will function without requiring additional attention. Loading and removing the work, starting and stopping the main movements, and applying infeed by hand wheel are carried out by the operator on cylindrical grinding machines in their basic degree of mechanization. Such equipment is still frequently used in tool room and jobbing-type work.

More advanced levels of automation have been developed for cylindrical grinders and are being applied in different degrees, particularly in the following principal respects:

a) *Infeed,* in which different rates are provided for rapid approach, roughing and finishing, followed by a spark-out period, with presetting of the advance rates, the cutoff points, and the duration of time-related functions.

b) *Automatic cycling* actuated by a single lever to start work rotation, table reciprocation, grinding-fluid supply, and infeed, followed at the end of the operation by wheel slide retraction, the successive stopping of the table movement, the work rotation, and the fluid supply.

c) *Table traverse dwells* (tarry) in the extreme positions of the travel, over preset periods, to assure uniform exposure to the wheel contact of the entire work section.

d) *Mechanized work loading,* clamping, and, after termination of the operation, unloading, combined with appropriate work-feeding devices such as indexing-type drums.

e) *Size control* by in-process or post-process measurements. Signals originated by the gage will control the advance movement or cause automatic compensation of size variations by adjusting the cutoff points of the infeed.

f) *Automatic wheel dressing* at preset frequency, combined with appropriate compensation in the infeed movement.

g) *Numerical control* obviates the time-consuming setups for repetitive work performed on small- or medium-size lots. As an application example: shafts with several sections of different lengths and diameters can be ground automatically in a single operation, grinding the sections in consecutive order to close dimensional limits, controlled by an in-process gage, which is also automatically set by means of the program.

The choice of the grinding machine functions to be automated and the extent of automation will generally be guided by economic considerations, after a thorough review of the available standard and optional equipment. Numerical control of partial or complete cycles is being applied to modern cylindrical and other grinding machines.

Cylindrical Grinding Troubles and Their Correction.— Troubles that may be encountered in cylindrical grinding may be classified as work defects (chatter, checking, burning, scratching, and inaccuracies), improperly operating machines (jumpy infeed or traverse), and wheel defects (too hard or soft action, loading, glazing, and breakage). The Landis Tool Company has listed some of these troubles, their causes, and corrections as follows:

Chatter: Sources of chatter include: 1) faulty coolant; 2) wheel out of balance; 3) wheel out of round; 4) wheel too hard; 5) improper dressing; 6) faulty work support or rotation; 7) improper operation; 8) faulty traverse; 9) work vibration; 10) outside vibration transmitted to machine; 11) interference; 12) wheel base; and 13) headstock.

Suggested procedures for correction of these troubles are:

1) *Faulty coolant:* Clean tanks and lines. Replace dirty or heavy coolant with correct mixture.

2) *Wheel out of balance:* Rebalance on mounting before and after dressing. Run wheel without coolant to remove excess water. Store a removed wheel on its side to keep retained

Copyright 2004, Industrial Press, Inc., New York, NY

water from causing a false heavy side. Tighten wheel mounting flanges. Make sure wheel center fits spindle.

3) *Wheel out of round:* True before and after balancing. True sides to face.

4) *Wheel too hard:* Use coarser grit, softer grade, more open bond. See *Wheel Defects* on page 1219.

5) *Improper dressing:* Use sharp diamond and hold rigidly close to wheel. It must not overhang excessively. Check diamond in mounting.

6) *Faulty work support or rotation:* Use sufficient number of work rests and adjust them more carefully. Use proper angles in centers of work. Clean dirt from footstock spindle and be sure spindle is tight. Make certain that work centers fit properly in spindles.

7) *Improper operation:* Reduce rate of wheel feed.

8) *Faulty traverse:* See *Uneven Traverse or Infeed of Wheel Head* on page 1219.

9) *Work vibration:* Reduce work speed. Check workpiece for balance.

10) *Outside vibration transmitted to machine:* Check and make sure that machine is level and sitting solidly on foundation. Isolate machine or foundation.

11) *Interference:* Check all guards for clearance.

12) *Wheel base:* Check spindle bearing clearance. Use belts of equal lengths or uniform cross-section on motor drive. Check drive motor for unbalance. Check balance and fit of pulleys. Check wheel feed mechanism to see that all parts are tight.

13) *Headstock:* Put belts of same length and cross-section on motor drive; check for correct work speeds. Check drive motor for unbalance. Make certain that headstock spindle is not loose. Check work center fit in spindle. Check wear of face plate and jackshaft bearings.

Spirals on Work (traverse lines with same lead on work as rate of traverse): Sources of spirals include: 1) machine parts out of line; and 2) truing.

Suggested procedures for correction of these troubles are:

1) *Machine parts out of line:* Check wheel base, headstock, and footstock for proper alignment.

2) *Truing:* Point truing tool down 3 degrees at the workwheel contact line. Round off wheel edges.

Check Marks on Work: Sources of check marks include: 1) improper operation; 2) improper heat treatment; 3) improper size control; 4) improper wheel; and 5) improper dressing.

Suggested procedures for correction of these troubles are:

1) *Improper operation:* Make wheel act softer. See *Wheel Defects*. Do not force wheel into work. Use greater volume of coolant and a more even flow. Check the correct positioning of coolant nozzles to direct a copious flow of clean coolant at the proper location.

2) *Improper heat treatment:* Take corrective measures in heat-treating operations.

3) *Improper size control:* Make sure that engineering establishes reasonable size limits. See that they are maintained.

4) *Improper wheel:* Make wheel act softer. Use softer-grade wheel. Review the grain size and type of abrasive. A finer grit or more friable abrasive or both may be called for.

5) *Improper dressing:* Check that the diamond is sharp, of good quality, and well set. Increase speed of the dressing cycle. Make sure diamond is not cracked.

Burning and Discoloration of Work: Sources of burning and discoloration are:improper operationand improper wheel.

Suggested procedures for correction of these troubles are:

1) *Improper operation:* Decrease rate of infeed. Don't stop work while in contact with wheel.

2) *Improper wheel:* Use softer wheel or obtain softer effect. See *Wheel Defects*. Use greater volume of coolant.

Copyright 2004, Industrial Press, Inc., New York, NY

Isolated Deep Marks on Work: Source of trouble is an unsuitable wheel. Use a finer wheel and consider a change in abrasive type.

Fine Spiral or Thread on Work: Sources of this trouble are: 1) improper operation; and 2) faulty wheel dressing.

Suggested procedures for corrections of these troubles are:

1) *Improper operation:* Reduce wheel pressure. Use more work rests. Reduce traverse with respect to work rotation. Use different traverse rates to break up pattern when making numerous passes. Prevent edge of wheel from penetrating by dressing wheel face parallel to work.

2) *Faulty wheel dressing:* Use slower or more even dressing traverse. Set dressing tool at least 3 degrees down and 30 degrees to the side from time to time. Tighten holder. Don't take too deep a cut. Round off wheel edges. Start dressing cut from wheel edge.

Narrow and Deep Regular Marks on Work: Source of trouble is that the wheel is too coarse. Use finer grain size.

Wide, Irregular Marks of Varying Depth on Work: Source of trouble is too soft a wheel. Use a harder grade wheel. See *Wheel Defects*.

Widely Spaced Spots on Work: Sources of trouble are oil spots or glazed areas on wheel face. Balance and true wheel. Keep oil from wheel face.

Irregular "Fish-tail" Marks of Various Lengths and Widths on Work: Source of trouble is dirty coolant. Clean tank frequently. Use filter for fine finish grinding. Flush wheel guards after dressing or when changing to finer wheel.

Wavy Traverse Lines on Work: Source of trouble is wheel edges. Round off. Check for loose thrust on spindle and correct if necessary.

Irregular Marks on Work: Cause is loose dirt. Keep machine clean.

Deep, Irregular Marks on Work: Source of trouble is loose wheel flanges. Tighten and make sure blotters are used.

Isolated Deep Marks on Work: Sources of trouble are: 1) grains pull out; coolant too strong; 2) coarse grains or foreign matter in wheel face; and 3) improper dressing.

Respective suggested procedures for corrections of these troubles are: 1) decrease soda content in coolant mixture; 2) dress wheel; and 3) use sharper dressing tool.

Brush wheel after dressing with stiff bristle brush.

Grain Marks on Work: Sources of trouble are: 1) improper finishing cut; 2) grain sizes of roughing and finishing wheels differ too much; 3) dressing too coarse; and 4) wheel too coarse or too soft.

Respective suggested procedures for corrections of these troubles are: start with high work and traverse speeds; finish with high work speed and slow traverse, letting wheel "spark-out" completely; finish out better with roughing wheel or use finer roughing wheel; use shallower and slower cut; and use finer grain size or harder-grade wheel.

Inaccuracies in Work: Work out-of-round, out-of-parallel, or tapered.

Sources of trouble are: 1) misalignment of machine parts; 2) work centers; 3) improper operation; 4) coolant; 5) wheel; 6) improper dressing; 7) spindle bearings; and 8) work.

Suggested procedures for corrections of these troubles are:

1) *Misalignment of machine parts:* Check headstock and tailstock for alignment and proper clamping.

2) *Work centers:* Centers in work must be deep enough to clear center point. Keep work centers clean and lubricated. Check play of footstock spindle and see that footstock spindle is clean and tightly seated. Regrind work centers if worn. Work centers must fit taper of work-center holes. Footstock must be checked for proper tension.

3) *Improper operation:* Don't let wheel traverse beyond end of work. Decrease wheel pressure so work won't spring. Use harder wheel or change feeds and speeds to make

Copyright 2004, Industrial Press, Inc., New York, NY

wheel act harder. Allow work to "spark-out." Decrease feed rate. Use proper number of work rests. Allow proper amount of tarry. Workpiece must be balanced if it is an odd shape.

4) *Coolant:* Use greater volume of coolant.

5) *Wheel:* Rebalance wheel on mounting before and after truing.

6) *Improper dressing:* Use same positions and machine conditions for dressing as in grinding.

7) *Spindle bearings:* Check clearance.

8) *Work:* Work must come to machine in reasonably accurate form.

Inaccurate Work Sizing (when wheel is fed to same position, it grinds one piece to correct size, another oversize, and still another undersize): Sources of trouble are: 1) improper work support or rotation; 2) wheel out of balance; 3) loaded wheel; 4) improper infeed; 5) improper traverse; 6) coolant; 7) misalignment; and 8) work.

Suggested procedures for corrections of these troubles are:

1) *Improper work support or rotation:* Keep work centers clean and lubricated. Regrind work-center tips to proper angle. Be sure footstock spindle is tight. Use sufficient work rests, properly spaced.

2) *Wheel out of balance:* Balance wheel on mounting before and after truing.

3) *Loaded wheel:* See *Wheel Defects*.

4) *Improper infeed:* Check forward stops of rapid feed and slow feed. When readjusting position of wheel base by means of the fine feed, move the wheel base back after making the adjustment and then bring it forward again to take up backlash and relieve strain in feed-up parts. Check wheel spindle bearings. Don't let excessive lubrication of wheel base slide cause "floating." Check and tighten wheel feed mechanism. Check parts for wear. Check pressure in hydraulic system. Set infeed cushion properly. Check to see that pistons are not sticking.

5) *Improper traverse:* Check traverse hydraulic system and the operating pressure. Prevent excessive lubrication of carriage ways with resultant "floating" condition. Check to see if carriage traverse piston rods are binding. Carriage rack and driving gear must not bind. Change length of tarry period.

6) *Coolant:* Use greater volume of clean coolant.

7) *Misalignment:* Check level and alignment of machine.

8) *Work:* Workpieces may vary too much in length, permitting uneven center pressure.

Uneven Traverse or Infeed of Wheel Head: Sources of uneven traverse or infeed of wheel head are: carriage and wheel head, hydraulic system, interference, unbalanced conditions, and wheel out of balance. Suggested procedures for correction of these troubles are:

1) *Carriage and wheel head:* Ways may be scored. Be sure to use recommended oil for both lubrication and hydraulic system. Make sure ways are not so smooth that they press out oil film. Check lubrication of ways. Check wheel feed mechanism, traverse gear, and carriage rack clearance. Prevent binding of carriage traverse cylinder rods.

2) *Hydraulic systems:* Remove air and check pressure of hydraulic oil. Check pistons and valves for oil leakage and for gumminess caused by incorrect oil. Check worn valves or pistons that permit leakage.

3) *Interference:* Make sure guard strips do not interfere.

4) *Unbalanced conditions:* Eliminate loose pulleys, unbalanced wheel drive motor, uneven belts, or high spindle keys.

5) *Wheel out of balance:* Balance wheel on mounting before and after truing.

Wheel Defects: When *wheel is acting too hard,* such defects as glazing, some loading, lack of cut, chatter, and burning of work result.

Copyright 2004, Industrial Press, Inc., New York, NY

Suggested procedures for correction of these faults are: 1) Increase work and traverse speeds as well as rate of in-feed; 2) decrease wheel speed, diameter, or width; 3) dress more sharply; 4) use thinner coolant; 5) don't tarry at end of traverse; 6) select softer wheel grade and coarser grain size; 7) avoid gummy coolant; and 8) on hardened work select finer grit, more fragile abrasive or both to get penetration. Use softer grade.

When *wheel is acting too soft,* such defects as wheel marks, tapered work, short wheel life, and not-holding-cut result.

Suggested procedures for correction of these faults are: 1) Decrease work and traverse speeds as well as rate of in-feed; 2) increase wheel speed, diameter, or width; 3) dress with little in-feed and slow traverse; 4) use heavier coolants; 5) don't let wheel run off work at end of traverse; and 6) select harder wheel or less fragile grain or both.

Wheel Loading and Glazing: Sources of the trouble of wheel loading or glazing are: 1) Incorrect wheel; 2) improper dress; 3) faulty operation; 4) faulty coolant; and 5) gummy coolant.

Suggested procedures for correction of these faults are:

1) *Incorrect wheel:* Use coarser grain size, more open bond, or softer grade.

2) *Improper dressing:* Keep wheel sharp with sharp dresser, clean wheel after dressing, use faster dressing traverse, and deeper dressing cut.

3) *Faulty operation:* Control speeds and feeds to soften action of wheel. Use less in-feed to prevent loading; more in-feed to stop glazing.

4) *Faulty coolant:* Use more, cleaner and thinner coolant, and less oily coolant.

5) *Gummy coolant:* To stop wheel glazing, increase soda content and avoid the use of soluble oils if water is hard. In using soluble oil coolant with hard water a suitable conditioner or "softener" should be added.

Wheel Breakage: Suggested procedures for the correction of a radial break with three or more pieces are: 1) Reduce wheel speed to or below rated speed; 2) mount wheel properly, use blotters, tight arbors, even flange pressure and be sure to keep out dirt between flange and wheel; 3) use plenty of coolant to prevent over-heating; 4) use less in-feed; and 5) don't allow wheel to become jammed on work.

A radial break with two pieces may be caused by excessive side strain. To prevent an irregular wheel break, don't let wheel become jammed on work; don't allow striking of wheel; and never use wheels that have been damaged in handling. In general, do not use a wheel that is too tight on the arbor since the wheel is apt to break when started. Prevent excessive hammering action of wheel. Follow rules of the American National Standard Safety Requirements for the Use, Care, and Protection of Abrasive Wheels (ANSI B7.1-1988).

Centerless Grinding

In centerless grinding the work is supported on a work rest blade and is between the grinding wheel and a regulating wheel. The regulating wheel generally is a rubber bonded abrasive wheel. In the normal grinding position the grinding wheel forces the work downward against the work rest blade and also against the regulating wheel. The latter imparts a uniform rotation to the work giving it its same peripheral speed which is adjustable.

The higher the work center is placed above the line joining the centers of the grinding and regulating wheels the quicker the rounding action. Rounding action is also increased by a high work speed and a slow rate of traverse (if a through-feed operation). It is possible to have a higher work center when using softer wheels, as their use gives decreased contact pressures and the tendency of the workpiece to lift off the work rest blade is lessened.

Long rods or bars are sometimes ground with their centers below the line-of-centers of the wheels to eliminate the whipping and chattering due to slight bends or kinks in the rods or bars, as they are held more firmly down on the blade by the wheels.

Copyright 2004, Industrial Press, Inc., New York, NY

There are three general methods of centerless grinding which may be described as through-feed, in-feed, and end-feed methods.

Through-feed Method of Grinding.— The through-feed method is applied to straight cylindrical parts. The work is given an axial movement by the regulating wheel and passes between the grinding and regulating wheels from one side to the other. The rate of feed depends upon the diameter and speed of the regulating wheel and its inclination which is adjustable. It may be necessary to pass the work between the wheels more than once, the number of passes depending upon such factors as the amount of stock to be removed, the roundness and straightness of the unground work, and the limits of accuracy required.

The work rest fixture also contains adjustable guides on either side of the wheels that directs the work to and from the wheels in a straight line.

In-feed Method of Centerless Grinding.— When parts have shoulders, heads or some part larger than the ground diameter, the in-feed method usually is employed. This method is similar to "plungecut" form grinding on a center type of grinder. The length or sections to be ground in any one operation are limited by the width of the wheel. As there is no axial feeding movement, the regulating wheel is set with its axis approximately parallel to that of the grinding wheel, there being a slight inclination to keep the work tight against the end stop.

End-feed Method of Grinding.— The end-feed method is applied only to taper work. The grinding wheel, regulating wheel, and the work rest blade are set in a fixed relation to each other and the work is fed in from the front mechanically or manually to a fixed end stop. Either the grinding or regulating wheel, or both, are dressed to the proper taper.

Automatic Centerless Grinding.— The grinding of relatively small parts may be done automatically by equipping the machine with a magazine, gravity chute, or hopper feed, provided the shape of the part will permit using these feed mechanisms.

Internal Centerless Grinding.— Internal grinding machines based upon the centerless principle utilize the outside diameter of the work as a guide for grinding the bore which is concentric with the outer surface. In addition to straight and tapered bores, interrupted and "blind" holes can be ground by the centerless method. When two or more grinding operations such as roughing and finishing must be performed on the same part, the work can be rechucked in the same location as often as required.

Centerless Grinding Troubles.— A number of troubles and some corrective measures compiled by a manufacturer are listed here for the through-feed and in-feed methods of centerless grinding.

Chattermarks are caused by having the work center too high above the line joining the centers of the grinding and regulating wheels; using too hard or too fine a grinding wheel; using too steep an angle on the work support blade; using too thin a work support blade; "play" in the set-up due to loosely clamped members; having the grinding wheel fit loosely on the spindle; having vibration either transmitted to the machine or caused by a defective drive in the machine; having the grinding wheel out-of-balance; using too heavy a stock removal; and having the grinding wheel or the regulating wheel spindles not properly adjusted.

Feed lines or spiral marks in through-feed grinding are caused by too sharp a corner on the exit side of the grinding wheel which may be alleviated by dressing the grinding wheel to a slight taper about ½ inch from the edge, dressing the edge to a slight radius, or swiveling the regulating wheel a bit.

Scored work is caused by burrs, abrasive grains, or removed material being imbedded in or fused to the work support blade. This condition may be alleviated by using a coolant with increased lubricating properties and if this does not help a softer grade wheel should be used.

Copyright 2004, Industrial Press, Inc., New York, NY

Work not ground round may be due to the work center not being high enough above the line joining the centers of the grinding and regulating wheels. Placing the work center higher and using a softer grade wheel should help to alleviate this condition.

Work not ground straight in through-feed grinding may be due to an incorrect setting of the guides used in introducing and removing the work from the wheels, and the existence of convex or concave faces on the regulating wheel. For example, if the work is tapered on the front end, the work guide on the entering side is deflected toward the regulating wheel. If tapered on the back end, then the work guide on the exit side is deflected toward the regulating wheel. If both ends are tapered, then both work guides are deflected toward the regulating wheel. The same barrel-shaped pieces are also obtained if the face of the regulating wheel is convex at the line of contact with the work. Conversely, the work would be ground with hollow shapes if the work guides were deflected toward the grinding wheel or if the face of the regulating wheel were concave at the line of contact with the work. The use of a warped work rest blade may also result in the work not being ground straight and the blade should be removed and checked with a straight edge.

In in-feed grinding, in order to keep the wheel faces straight which will insure straightness of the cylindrical pieces being ground, the first item to be checked is the straightness and the angle of inclination of the work rest blade. If this is satisfactory then one of three corrective measures may be taken: the first might be to swivel the regulating wheel to compensate for the taper, the second might be to true the grinding wheel to that angle that will give a perfectly straight workpiece, and the third might be to change the inclination of the regulating wheel (this is true only for correcting very slight tapers up to 0.0005 inch).

Difficulties in sizing the work in in-feed grinding are generally due to a worn in-feed mechanism and may be overcome by adjusting the in-feed nut.

Flat spots on the workpiece in in-feed grinding usually occur when grinding heavy work and generally when the stock removal is light. This condition is due to insufficient driving power between the work and the regulating wheel which may be alleviated by equipping the work rest with a roller that exerts a force against the workpiece; and by feeding the workpiece to the end stop using the upper slide.

Surface Grinding

The term surface grinding implies, in current technical usage, the grinding of surfaces which are essentially flat. Several methods of surface grinding, however, are adapted and used to produce surfaces characterized by parallel straight line elements in one direction, while normal to that direction the contour of the surface may consist of several straight line sections at different angles to each other (e.g., the guideways of a lathe bed); in other cases the contour may be curved or profiled (e.g., a thread cutting chaser).

Advantages of Surface Grinding.— Alternate methods for machining work surfaces similar to those produced by surface grinding are milling and, to a much more limited degree, planing. Surface grinding, however, has several advantages over alternate methods that are carried out with metal-cutting tools. Examples of such potential advantages are as follows:

1) Grinding is applicable to very hard and/or abrasive work materials, without significant effect on the efficiency of the stock removal.

2) The desired form and dimensional accuracy of the work surface can be obtained to a much higher degree and in a more consistent manner.

3) Surface textures of very high finish and—when the appropriate system is utilized—with the required lay, are generally produced.

4) Tooling for surface grinding as a rule is substantially less expensive, particularly for producing profiled surfaces, the shapes of which may be dressed into the wheel, often with simple devices, in processes that are much more economical than the making and the maintenance of form cutters.

Copyright 2004, Industrial Press, Inc., New York, NY

5) Fixturing for work holding is generally very simple in surface grinding, particularly when magnetic chucks are applicable, although the mechanical holding fixture can also be simpler, because of the smaller clamping force required than in milling or planing.

6) Parallel surfaces on opposite sides of the work are produced accurately, either in consecutive operations using the first ground surface as a dependable reference plane or, simultaneously, in double face grinding, which usually operates without the need for holding the parts by clamping.

7) Surface grinding is well adapted to process automation, particularly for size control, but also for mechanized work handling in the large volume production of a wide range of component parts.

Principal Systems of Surface Grinding.— Flat surfaces can be ground with different surface portions of the wheel, by different arrangements of the work and wheel, as well as by different interrelated movements. The various systems of surface grinding, with their respective capabilities, can best be reviewed by considering two major distinguishing characteristics:

1) *The operating surface of the grinding wheel,* which may be the periphery or the face (the side);

2) *The movement of the work during the process,* which may be traverse (generally reciprocating) or rotary (continuous), depending on the design of a particular category of surface grinders.

The accompanying Table 1 and the text that follows provides a concise review of the principal surface grinding systems, defined by the preceding characteristics. It should be noted that many surface grinders are built for specific applications, and do not fit exactly into any one of these major categories.

Operating Surface, Periphery of Wheel: Movement of Work, Reciprocating: Work is mounted on the horizontal machine table that is traversed in a reciprocating movement at a speed generally selected from a steplessly variable range. The transverse movement, called cross feed of the table or of the wheel slide, operates at the end of the reciprocating stroke and assures the gradual exposure of the entire work surface, which commonly exceeds the width of the wheel. The depth of the cut is controlled by the downfeed of the wheel, applied in increments at the reversal of the transverse movement.

Operating Surface, Periphery of Wheel: Movement of Work, Rotary: Work is mounted, usually on the full-diameter magnetic chuck of the circular machine table that rotates at a preset constant or automatically varying speed, the latter maintaining an approximately equal peripheral speed of the work surface area being ground. The wheelhead, installed on a cross slide, traverses over the table along a radial path, moving in alternating directions, toward and away from the center of the table. Infeed is by vertical movement of the saddle along the guideways of the vertical column, at the end of the radial wheelhead stroke. The saddle contains the guideways along which the wheelhead slide reciprocates.

Operating Surface, Face of Wheel: Movement of Work,Reciprocating: Operation is similar to the reciprocating table-type peripheral surface grinder, but grinding is with the face, usually with the rim of a cup-shaped wheel, or a segmental wheel for large machines. Capable of covering a much wider area of the work surface than the peripheral grinder, thus frequently no need for cross feed. Provides efficient stock removal, but is less adaptable than the reciprocating table-type peripheral grinder.

Operating Surface, Face of Wheel: Movement of Work, Rotary: The grinding wheel, usually of segmental type, is set in a position to cover either an annular area near the periphery of the table or, more commonly, to reach beyond the table center. A large circular magnetic chuck generally covers the entire table surface and facilitates the mounting of workpieces, even of fixtures, when needed. The uninterrupted passage of the work in contact with the large wheel face permits a very high rate of stock removal and the machine,

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Principal Systems of Surface Grinding — Diagrams



Reciprocating — Periphery of Wheel





Rotary — Periphery of Wheel





Reciprocating — Face (Side) of Wheel



Traverse Along Straight Line or Arcuate Path — Face (Side) of Wheel



Rotary — Face (Side) of Wheel

Copyright 2004, Industrial Press, Inc., New York, NY

with single or double wheelhead, can be adapted also to automatic operation with continuous part feed by mechanized work handling.

Operating Surface, Face of Wheel: Movement of Work, Traverse Along Straight or Arcuate Path: The grinding wheel, usually of segmental type, is set in a position to cover either an annular area near the periphery of the table or, more commonly, to reach beyond the table center. A large circular magnetic chuck generally covers the entire table surface and facilitates the mounting of workpieces, even of fixtures, when needed. The uninterrupted passage of the work in contact with the large wheel face permits a very high rate of stock removal and the machine, with single or double wheelhead, can be adapted also to automatic operation with continuous part feed by mechanized work handling.

Selection of Grinding Wheels for Surface Grinding.— The most practical way to select a grinding wheel for surface grinding is to base the selection on the work material. Table 2a gives the grinding wheel recommendations for Types 1, 5, and 7 straight wheels used on reciprocating and rotary table surface grinders with horizontal spindles. Table 2b gives the grinding wheel recommendations for Type 2 cylinder wheels, Type 6 cup wheels, and wheel segments used on vertical spindle surface grinders.

The last letters (two or three) that may follow the bond designation V (vitrified) or B (resinoid) refer to: 1) bond modification, "BE" being especially suitable for surface grinding; 2) special structure, "P" type being distinctively porous; and 3) for segments made of 23A type abrasives, the term 12VSM implies porous structure, and the letter "P" is not needed.

The wheel markings in Tables 2a and 2b are those used by the Norton Co., complementing the basic standard markings with Norton symbols. The complementary symbols used in these tables, that is, those preceding the letter designating A (aluminum oxide) or C (silicon carbide), indicate the special type of basic abrasive that has the friability best suited for particular work materials. Those preceding A (aluminum oxide) are

57—a versatile abrasive suitable for grinding steel in either a hard or soft state.
38—the most friable abrasive.
32—the abrasive suited for tool steel grinding.
23—an abrasive with intermediate grinding action, and
19—the abrasive produced for less heat-sensitive steels.

Those preceding C (silicon carbide) are

37—a general application abrasive, and
39—an abrasive for grinding hard cemented carbide.

Table 2a. Grinding Wheel Recommendations for Surface Grinding—Using Straight Wheel Types 1, 5, and 7

Material	Horizontal-spindle, reciprocating-table surface grinders		Horizontal-spindle, rotary-table surface grinders
	Wheels less than 16 inches diameter	Wheels 16 inches diameter and over	Wheels of any diameter
Cast iron	37C36-K8V or 23A46-I8VBE	23A36-I8VBE	37C36-K8V or 23A46-I8VBE
Nonferrous metal	37C36-K8V	37C36-K8V	37C36-K8V
Soft steel	23A46-J8VBE	23A36-J8VBE	23A46-J8VBE
Hardened steel, broad contact	32A46-H8VBE or 32A60-F12VBEP	32A36-H8VBE or 32A36-F12VBEP	32A46-I8VBE
Hardened steel, narrow contact or interrupted cut	32A46-I8VBE	32A36-J8VBE	32A46-J8VBE
General-purpose wheel	23A46-H8VBE	23A36-I8VBE	23A46-I8VBE
Cemented carbides	Diamond wheels[a]	Diamond wheels[a]	Diamond wheels[a]

[a] General diamond wheel recommendations are listed in Table 5 on page 1206.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Grinding Wheel Recommendations for Surface Grinding—Using Type 2 Cylinder Wheels, Type 6 Cup Wheels, and Wheel Segments

Material	Type 2 Cylinder Wheels	Type 6 Cup Wheels	Wheel Segments
High tensile cast iron and non-ferrous metals	37C24-HKV	37C24-HVK	37C24-HVK
Soft steel, malleable cast iron, steel castings, boiler plate	23A24-I8VBE or 23A30-G12VBEP	23A24-I8VBE	23A24-I8VSM or 23A30-H12VSM
Hardened steel—broad contact	32A46-G8VBE or 32A36-E12VBEP	32A46-G8VBE or 32A60-E12VBEP	32A36-G8VBE or 32A46-E12VBEP
Hardened steel—narrow contact or interrupt cut	32A46-H8VBE	32A60-H8VBE	32A46-G8VBE or 32A60-G12VBEP
General-purpose use	23A30-H8VBE or 23A30-E12VBEP	…	23A30-H8VSM or 23A30-G12VSM

Process Data for Surface Grinding.— In surface grinding, similarly to other metal-cutting processes, the speed and feed rates that are applied must be adjusted to the operational conditions as well as to the objectives of the process. Grinding differs, however, from other types of metal cutting methods in regard to the cutting speed of the tool; the peripheral speed of the grinding wheel is maintained within a narrow range, generally 5500 to 6500 surface feet per minute. Speed ranges different from the common one are used in particular processes which require special wheels and equipment.

Table 3. Basic Process Data for Peripheral Surface Grinding on Reciprocating Table Surface Grinders

Work Material	Hardness	Material Condition	Wheel Speed, fpm	Table Speed, fpm	Downfeed, in. per pass		Crossfeed per pass, fraction of wheel width
					Rough	Finish, max.	
Plain carbon steel	52 Rc max.	Annealed, cold drawn	5500–6500	50–100	0.003	0.0005	1/4
	52–65 Rc	Carburized and/or quenched and tempered	5500–6500	50–100	0.003	0.0005	1/10
Alloy steels	52 Rc max.	Annealed or quenched and tempered	5500–6500	50–100	0.003	0.001	1/4
	52–65 Rc	Carburized and/or quenched and tempered	5500–6500	50–100	0.003	0.0005	1/10
Tool steels	150–275 Bhn	Annealed	5500–6500	50–100	0.002	0.0005	1/5
	56–65 Rc	Quenched and tempered	5500–6500	50–100	0.002	0.0005	1/10
Nitriding steels	200–350 Bhn	Normalized, annealed	5500–6500	50–100	0.003	0.001	1/4
	60–65 Rc	Nitrided	5500–6500	50–100	0.003	0.0005	1/10
Cast steels	52 Rc max.	Normalized, annealed	5500–6500	50–100	0.003	0.001	1/4
	Over 52 Rc	Carburized and/or quenched and tempered	5500–6500	50–100	0.003	0.0005	1/10
Gray irons	52 Rc max.	As cast, annealed, and/or quenched and tempered	5000–6500	50–100	0.003	0.001	1/3
Ductile irons	52 Rc max.	As cast, annealed or quenched and tempered	5500–6500	50–100	0.003	0.001	1/5
Stainless steels, martensitic	135–235 Bhn	Annealed or cold drawn	5500–6500	50–100	0.002	0.0005	1/4
	Over 275 Bhn	Quenched and tempered	5500–6500	50–100	0.001	0.0005	1/8
Aluminum alloys	30–150 Bhn	As cast, cold drawn or treated	5500–6500	50–100	0.003	0.001	1/3

In establishing the proper process values for grinding, of prime consideration are the work material, its condition, and the type of operation (roughing or finishing). Table 3 gives basic process data for peripheral surface grinding on reciprocating table surface

Copyright 2004, Industrial Press, Inc., New York, NY

grinders. For different work materials and hardness ranges data are given regarding table speeds, downfeed (infeed) rates and cross feed, the latter as a function of the wheel width.

Common Faults and Possible Causes in Surface Grinding.— Approaching the ideal performance with regard to both the quality of the ground surface and the efficiency of surface grinding, requires the monitoring of the process and the correction of conditions adverse to the attainment of that goal.

Defective, or just not entirely satisfactory surface grinding may have any one or more of several causes. Exploring and determining the cause for eliminating its harmful effects is facilitated by knowing the possible sources of the experienced undesirable performance. Table 4, associating the common faults with their possible causes, is intended to aid in determining the actual cause, the correction of which should restore the desired performance level.

While the table lists the more common faults in surface grinding, and points out their frequent causes, other types of improper performance and/or other causes, in addition to those indicated, are not excluded.

Vitrified Grinding Wheels.— The term "vitrified" denotes the type of bond used in these grinding wheels. The bond in a grinding wheel is the material which holds the abrasive grains together and supports them while they cut. With a given type of bond, it is the *amount* of bond that determines the "hardness" or softness" of wheels. The abrasive itself is extremely hard in all wheels, and the terms "hard" and "soft" refer to the *strength of bonding*; the greater the percentage of bond with respect to the abrasive, the heavier the coating of bond around the abrasive grains and the stronger the bond posts, the "harder" the wheel.

Most wheels are made with a vitrified bond composed of clays and feldspar selected for their fusibility. During the "burning" process in grinding wheel manufacture, the clays are fused into a molten glass condition. Upon cooling, a span or post of this glass connects each abrasive grain to its neighbors to make a rigid, strong, grinding wheel. These wheels are porous, free cutting and unaffected by water, acids, oils, heat, or cold. Vitrified wheels are extensively used for cylindrical grinding, surface grinding, internal grinding and cutter grinding.

Silicate Bonding Process.— Silicate grinding wheels derive their name from the fact that silicate of soda or water glass is the principal ingredient used in the bond. These wheels are also sometimes referred to as *semi-vitrified* wheels. Ordinarily, they cut smoothly and with comparatively little heat, and for grinding operations requiring the lowest wheel wear, compatible with cool cutting, silicate wheels are often used. Their grade is also dependable and much larger wheels can be made by this bonding process than by the vitrified process. Some of the grinding operations for which silicate wheels have been found to be especially adapted are as follows: for grinding high-speed steel machine shop tools, such as reamers, milling cutters, etc.; for hand-grinding lathe and planer tools; for surface grinding with machines of the vertical ring-wheel type; and for operations requiring dish-shaped wheels and cool cutting. These wheels are unequaled for wet grinding on hardened steel and for wet tool grinding. They are easily recognized by their light gray color.

Oilstones.— The natural oilstones commonly used are the *Washita* and *Arkansas*. The Washita is a coarser and more rapidly cutting stone, and is generally considered the most satisfactory for sharpening woodworkers' tools. There are various grades of Washita rock, varying from the perfect crystallized and porous whetstone grit, to vitreous flint and hard sandstone. The best whetstones are porous and uniform in texture and are composed entirely of silica crystals. The poorer grades are less porous, making them vitreous or "glassy." They may also have hard spots or sand holes, or contain grains of sand among the crystals. For general work, a soft, free-grit, quick-cutting stone is required, although a fine-grit medium-hard stone is sometimes preferable. These are commonly furnished in three grits: fine, medium, and coarse, and in all required shapes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Common Faults and Possible Causes in Surface Grinding

CAUSES	FAULTS	WORK DIMENSION			METALLURGICAL DEFECTS		SURFACE QUALITY				WHEEL CONDITION			WORK RETAINMENT	
		Work not flat	Work not parallel	Poor size holding	Burnishing of work	Burning or checking	Feed lines	Chatter marks	Scratches on surface	Poor finish	Wheel loading	Wheel glazing	Rapid wheel wear	Not firmly seated	Work sliding on chuck
WORK CONDITION	Heat treat stresses	●	..	..	..	..	..	..	..	..	..	..	..	..	..
	Work too thin	●	●	..	..	..	..	..	..	..	..	..	..	..	..
	Work warped	●	..	..	..	..	..	..	..	..	..	..	..	●	..
	Abrupt section changes	●	●	..	..	..	..	..	..	..	..	..	..	..	..
GRINDING WHEEL	Grit too fine	..	..	..	●	●	..	..	..	..	●	●	..	..	..
	Grit too coarse	..	..	..	..	..	..	..	..	●	..	..	..	..	..
	Grade too hard	●	..	..	●	●	..	●	..	..	●	●	..	..	..
	Grade too soft	..	..	●	..	..	..	●	●	..	..	..	●	..	..
	Wheel not balanced	..	..	..	..	..	..	●	..	..	..	..	..	..	..
	Dense structure	..	..	..	..	..	..	..	..	..	●	●	..	..	..
TOOLING AND COOLANT	Improper coolant	..	..	..	..	..	..	..	..	..	●	..	..	..	..
	Insufficient coolant	●	●	..	●	●	..	..	..	..	..	●	..	..	..
	Dirty coolant	..	..	..	..	..	..	..	●	..	●	..	..	..	..
	Diamond loose or chipped	●	●	..	..	..	..	..	●	..	..	..	..	..	..
	Diamond dull	..	..	●	..	..	..	..	..	●	●	●	..	..	..
	No or poor magnetic force	..	..	●	..	..	..	..	●	..	..	..	..	●	●
	Chuck surface worn or burred	●	●	..	..	..	..	..	●	..	..	..	..	●	..
MACHINE AND SETUP	Chuck not aligned	●	●	..	..	..	..	..	..	..	..	..	..	..	..
	Vibrations in machine	..	..	..	..	..	..	●	..	..	..	..	..	..	..
	Plane of movement out of parallel	●	●	..	..	..	..	..	..	..	..	..	..	..	..
OPERATIONAL CONDITIONS	Too low work speed	..	..	..	..	..	..	..	..	..	●	..	..	..	..
	Too light feed	..	..	..	..	..	..	..	..	..	..	●	..	..	..
	Too heavy cut	●	..	..	●	..	..	..	..	●	..	..	..	..	..
	Chuck retained swarf	●	●	..	..	..	..	..	..	..	..	..	..	..	●
	Chuck loading improper	●	●	..	..	..	..	..	..	..	..	..	..	..	●
	Insufficient blocking of parts	..	..	..	..	..	..	..	●	..	..	..	..	..	..
	Wheel runs off the work	..	●	●	..	●	..	..	..	..	..	..	●	..	..
	Wheel dressing too fine	●	..	..	..	..	..	..	..	..	..	..	..	..	..
	Wheel edge not chamfered	..	..	..	..	..	●	..	..	..	..	..	..	..	..
	Loose dirt under guard	..	..	..	..	..	..	..	●	..	..	..	..	..	..

Copyright 2004, Industrial Press, Inc., New York, NY

Offhand Grinding

Offhand grinding consists of holding the wheel to the work or the work to the wheel and grinding to broad tolerances and includes such operations as certain types of tool sharpening, weld grinding, snagging castings and other rough grinding. Types of machines that are used for rough grinding in foundries are floor- and bench-stand machines. Wheels for these machines vary from 6 to 30 inches in diameter. Portable grinding machines (electric, flexible shaft, or air-driven) are used for cleaning and smoothing castings.

Many rough grinding operations on castings can be best done with shaped wheels, such as cup wheels (including plate mounted) or cone wheels, and it is advisable to have a good assortment of such wheels on hand to do the odd jobs the best way.

Floor- and Bench-Stand Grinding.— The most common method of rough grinding is on double-end floor and bench stands. In machine shops, welding shops, and automotive repair shops, these grinders are usually provided with a fairly coarse grit wheel on one end for miscellaneous rough grinding and a finer grit wheel on the other end for sharpening tools. The pressure exerted is a very important factor in selecting the proper grinding wheel. If grinding is to be done mostly on hard sharp fins, then durable, coarse and hard wheels are required, but if grinding is mostly on large gate and riser pads, then finer and softer wheels should be used for best cutting action.

Portable Grinding.— Portable grinding machines are usually classified as air grinders, flexible shaft grinders, and electric grinders. The electric grinders are of two types; namely, those driven by standard 60 cycle current and so-called high-cycle grinders. Portable grinders are used for grinding down and smoothing weld seams; cleaning metal before welding; grinding out imperfections, fins and parting lines in castings and smoothing castings; grinding punch press dies and patterns to proper size and shape; and grinding manganese steel castings.

Wheels used on portable grinders are of three bond types; namely, resinoid, rubber, and vitrified. By far the largest percentage is resinoid. Rubber bond is used for relatively thin wheels and where a good finish is required. Some of the smaller wheels such as cone and plug wheels are vitrified bonded.

Grit sizes most generally used in wheels from 4 to 8 inches in diameter are 16, 20, and 24. In the still smaller diameters, finer sizes are used, such as 30, 36, and 46.

The particular grit size to use depends chiefly on the kind of grinding to be done. If the work consists of sharp fins and the machine has ample power, a coarse grain size combined with a fairly hard grade should be used. If the job is more in the nature of smoothing or surfacing and a fairly good finish is required, then finer and softer wheels are called for.

Swing-Frame Grinding.— This type of grinding is employed where a considerable amount of material is to be removed as on snagging large castings. It may be possible to remove 10 times as much material from steel castings using swing-frame grinders as with portable grinders; and 3 times as much material as with high-speed floor-stand grinders.

The largest field of application for swing-frame machines is on castings which are too heavy to handle on a floor stand; but often it is found that comparatively large gates and risers on smaller castings can be ground more quickly with swing-frame grinders, even if fins and parting lines have to be ground on floor stands as a second operation.

In foundries, the swing-frame machines are usually suspended from a trolley on a jib that can be swung out of the way when placing the work on the floor with the help of an overhead crane. In steel mills when grinding billets, a number of swing-frame machines are usually suspended from trolleys on a line of beams which facilitate their use as required.

The grinding wheels used on swing-frame machines are made with coarser grit sizes and harder grades than wheels used on floor stands for the same work. The reason is that greater grinding pressures can be obtained on the swing-frame machines.

Copyright 2004, Industrial Press, Inc., New York, NY

Abrasive Belt Grinding

Abrasive belts are used in the metalworking industry for removing stock, light cleaning up of metal surfaces, grinding welds, deburring, breaking and polishing hole edges, and finish grinding of sheet steel. The types of belts that are used may be coated with aluminum oxide (the most common coating) for stock removal and finishing of all alloy steels, high-carbon steel, and tough bronzes; and silicon carbide for use on hard, brittle, and low-tensile strength metals which would include aluminum and cast irons.

Table 1 is a guide to the selection of the proper abrasive belt, lubricant, and contact wheel. This table is entered on the basis of the material used and type of operation to be done and gives the abrasive belt specifications (type of bonding andabrasive grain size and material), the range of speeds at which the belt may best be operated, the type of lubricant to use, and the type and hardness of the contact wheel to use. Table 2 serves as a guide in the selection of contact wheels. This table is entered on the basis of the type of contact wheel surface and the contact wheel material. The table gives the hardness and/or density, the type of abrasive belt grinding for which the contact wheel is intended, the character of the wheel action and such comments as the uses, and hints for best use. Both tables are intended only as guides for general shop practice; selections may be altered to suit individual requirements.

There are three types of abrasive belt grinding machines. One type employs a contact wheel behind the belt at the point of contact of the workpiece to the belt and facilitates a high rate of stock removal. Another type uses an accurate parallel ground platen over which the abrasive belt passes and facilitates the finishing of precision parts. A third type which has no platens or contact wheel is used for finishing parts having uneven surfaces or contours. In this type there is no support behind the belt at the point of contact of the belt with the workpiece. Some machines are so constructed that besides grinding against a platen or a contact wheel the workpiece may be moved and ground against an unsupported portion of the belt, thereby in effect making it a dual machine.

Although abrasive belts at the time of their introduction were used dry, since the advent of the improved waterproof abrasive belts, they have been used with coolants, oil-mists, and greases to aid the cutting action. The application of a coolant to the area of contact retards loading, resulting in a cool, free cutting action, a good finish and a long belt life.

Abrasive Cutting

Abrasive cut-off wheels are used for cutting steel, brass and aluminum bars and tubes of all shapes and hardnesses, ceramics, plastics, insulating materials, glass and cemented carbides. Originally a tool or stock room procedure, this method has developed into a high-speed production operation. While the abrasive cut-off machine and cut-off wheel can be said to have revolutionized the practice of cutting-off materials, the metal saw continues to be the more economical method for cutting-off large cross-sections of certain materials. However, there are innumerable materials and shapes that can be cut with much greater speed and economy by the abrasive wheel method. On conventional chop-stroke abrasive cutting machines using 16-inch diameter wheels, 2-inch diameter bar stock is the maximum size that can be cut with satisfactory wheel efficiency, but bar stock up to 6 inches in diameter can be cut efficiently on oscillating-stroke machines. Tubing up to 3½ inches in diameter can also be cut efficiently.

Abrasive wheels are commonly available in four types of bonds: Resinoid, rubber, shellac and fiber or fabric reinforced. In general, resinoid bonded cut-off wheels are used for dry cutting where burrs and some burn are not objectionable and rubber bonded wheels are used for wet cutting where cuts are to be smooth, clean and free from burrs. Shellac bonded wheels have a soft, free cutting quality which makes them particularly useful in the tool room where tool steels are to be cut without discoloration. Fiber reinforced bonded wheels are able to withstand severe flexing and side pressures and fabric reinforced bonded

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Guide to the Selection and Application of Abrasive Belts

Material	Type of Operation	Abrasive Belt[a]	Grit	Belt Speed, fpm	Type of Grease Lubricant	Contact Wheel	
						Type	Durometer Hardness
Hot-and Cold-Rolled Steel	Roughing	R/R Al_2O_3	24–60	4000–65000	Light-body or none	Cog-tooth, serrated rubber	70–90
	Polishing	R/G or R/R Al_2O_3	80–150	4500–7000	Light-body or none	Plain or serrated rubber, sectional or finger-type cloth wheel, free belt	20–60
	Fine Polishing	R/G or electro-coated Al_2O_3 cloth	180–500	4500–7000	Heavy or with abrasive compound	Smooth-faced rubber or cloth	20–40
Stainless Steel	Roughing	R/R Al_2O_3	50–80	3500–5000	Light-body or none	Cog-tooth, serrated rubber	70–90
	Polishing	R/G or R/R Al_2O_3	80–120	4000–5500	Light-body or none	Plain or serrated rubber, sectional or finger-type cloth wheel, free belt	30–60
	Fine Polishing	Closed-coat SiC	150–280	4500–5500	Heavy or oil mist	Smooth-faced rubber or cloth	20–40
Aluminum, Cast or Fabricated	Roughing	R/R SiC or Al_2O_3	24–80	5000–6500	Light	Cog-tooth, serrated rubber	70–90
	Polishing	R/G SiC or Al_2O_3	100–180	4500–6500	Light	Plain or serrated rubber, sectional or finger-type cloth wheel, free belt	30–50
	Fine Polishing	Closed-coat SiC or electro-coated Al_2O_3	220–320	4500–6500	Heavy or with abrasive compound	Plain faced rubber, finger-type cloth or free belt	20–50
Copper Alloys or Brass	Roughing	R/R SiC or Al_2O_3	36–80	2200–4500	Light-body	Cog-tooth, serrated rubber	70–90
	Polishing	Closed-coat SiC or electro-coated Al_2O_3 or R/G SiC or Al_2O_3	100–150	4000–6500	Light-body	Plain or serrated rubber, sectional or finger-type cloth wheel, free belt	30–50
	Fine Polishing	Closed-coat SiC or electro-coated Al_2O_3	180–320	4000–6500	Light or with abrasive compound	Same as for polishing	20–30
Non-ferrous Die-castings	Roughing	R/R SiC or Al_2O_3	24–80	4500–6500	Light-body	Hard wheel depending on application	50–70
	Polishing	R/G SiC or Al_2O_3	100–180	4500–6500	Light-body	Plain rubber, cloth or free belt	30–50
	Fine Polishing	Electro-coated Al_2O_3 or closed-coat SiC	220–320	4500–6500	Heavy or with abrasive compound	Plain or finger-type cloth wheel, or free belt	20–30
Cast Iron	Roughing	R/R Al_2O_3	24–60	2000–4000	None	Cog-tooth, serrated rubber	70–90
	Polishing	R/R Al_2O_3	80–150	4000–5500	None	Serrated rubber	30–70
	Fine Polishing	R/R Al_2O_3	120–240	4000–5500	Light-body	Smooth-faced rubber	30–40
Titanium	Roughing	R/R SiC or Al_2O_3	36–50	700–1500	Sulfur-chlorinated	Small-diameter, cog-tooth serrated rubber	70–80
	Polishing	R/R SiC	60–120	1200–2000	Light-body	Standard serrated rubber	50
	Fine Polishing	R/R SiC	120–240	1200–2000	Light-body	Smooth-faced rubber or cloth	20–40

[a] R/R indicates that both the making and sizing bond coats are resin. R/G indicates that the making coat is glue and the sizing coat is resin. The abbreviations Al_2O_3 for aluminum oxide and SiC for silicon carbide are used. Almost all R/R and R/G Al_2O_3 and SiC belts have a heavy-drill weight cloth backing. Most electro-coated Al_2O_3 and closed-coat SiC belts have a jeans weight cloth backing.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Guide to the Selection and Application of Contact Wheels

Surface	Material	Hardness and Density	Purposes	Wheel Action	Comments
Cog-tooth	Rubber	70 to 90 durometer	Roughing	Fast cutting, allows long belt life.	For cutting down projections on castings and weld beads.
Standard serrated	Rubber	40 to 50 durometer, medium density	Roughing	Leaves rough- to medium-ground surface.	For smoothing projections and face defects.
X-shaped serrations	Rubber	20 to 50 durometer	Roughing and polishing	Flexibility of rubber allows entry into contours. Medium polishing, light removal.	Same as for standard serrated wheels but preferred for soft non-ferrous metals.
Plain face	Rubber	20 to 70 durometer	Roughing and polishing	Plain wheel face allows controlled penetration of abrasive grain. Softer wheels give better finishes.	For large or small flat faces.
Flat flexible	Compressed canvas	About nine densities from very hard to very soft	Roughing and polishing	Hard wheels can remove metal, but not as quickly as cog-tooth rubber wheels. Softer wheels polish well.	Good for medium-range grinding and polishing.
Flat flexible	Solid sectional canvas	Soft, medium, and hard	Polishing	Uniform polishing. Avoids abrasive pattern on work. Adjusts to contours. Can be performed for contours.	A low-cost wheel with uniform density at the face. Handles all types of polishing.
Flat flexible	Buff section canvas	Soft	Contour polishing	For fine polishing and finishing.	Can be widened or narrowed by adding or removing sections. Low cost.
Flat flexible	Sponge rubber inserts	5 to 10 durometer, soft	Polishing	Uniform polishing and finishing. Polishes and blends contours.	Has replaceable segments. Polishes and blends contours. Segments allow density changes.
Flexible	Fingers of canvas attached to hub	Soft	Polishing	Uniform polishing and finishing.	For polishing and finishing.
Flat flexible	Rubber segments	Varies in hardness	Roughing and polishing	Grinds or polishes depending on density and hardness of inserts.	For portable machines. Uses replaceable segments that save on wheel costs and allow density changes.
Flat flexible	Inflated rubber	Air pressure controls hardness	Roughing and polishing	Uniform finishing.	Adjusts to contours.

wheels which are highly resistant to breakage caused by extreme side pressures, are fast cutting and have a low rate of wear.

The types of abrasives available in cut-off wheels are: Aluminum oxide, for cutting steel and most other metals; silicon carbide, for cutting non-metallic materials such as carbon, tile, slate, ceramics, etc.; and diamond, for cutting cemented carbides. The method of denoting abrasive type, grain size, grade, structure and bond type by using a system of markings is the same as for grinding wheels (see page 1179). Maximum wheel speeds given in the American National Standard "Safety Requirements for The Use, Care, and Protection of Abrasive Wheels" (ANSI B7.1-1988) range from 9500 to 14,200 surface feet per minute for organic bonded cut-off wheels larger than 16 inches in diameter and from 9500 to 16,000 surface feet per minute for organic bonded cut-off wheels 16 inches in diameter and smaller. Maximum wheel speeds specified by the manufacturer should never be exceeded even though they may be lower than those given in the B7.1 Standard.

There are four basic types of abrasive cutting machines: Chop-stroke, oscillating stroke, horizontal stroke and work rotating. Each of these four types may be designed for dry cutting or for wet cutting (includes submerged cutting).

Copyright 2004, Industrial Press, Inc., New York, NY

The accompanying table based upon information made available by The Carborundum Co. gives some of the probable causes of cutting off difficulties that might be experienced when using abrasive cut-off wheels.

Probable Causes of Cutting-Off Difficulties

Difficulty	Probable Cause
Angular Cuts and Wheel Breakage	(1) Inadequate clamping which allows movement of work while the wheel is in the cut. The work should be clamped on both sides of the cut. (2) Work vise higher on one side than the other causing wheel to be pinched. (3) Wheel vibration resulting from worn spindle bearings. (4) Too fast feeding into the cut when cutting wet.
Burning of Stock	(1) Insufficient power or drive allowing wheel to stall. (2) Cuts too heavy for grade of wheel being used. (3) Wheel fed through the work too slowly. This causes a heating up of the material being cut. This difficulty encountered chiefly in dry cutting.
Excessive Wheel Wear	(1) Too rapid cutting when cutting wet. (2) Grade of wheel too hard for work, resulting in excessive heating and burning out of bond. (3) Inadequate coolant supply in wet cutting. (4) Grade of wheel too soft for work. (5) Worn spindle bearings allowing wheel vibration.
Excessive Burring	(1) Feeding too slowly when cutting dry. (2) Grit size in wheel too coarse. (3) Grade of wheel too hard. (4) Wheel too thick for job.

Honing Process

The hone-abrading process for obtaining cylindrical forms with precise dimensions and surfaces can be applied to internal cylindrical surfaces with a wide range of diameters such as engine cylinders, bearing bores, pin holes, etc. and also to some external cylindrical surfaces.

The process is used to: 1) eliminate inaccuracies resulting from previous operations by generating a true cylindrical form with respect to roundness and straightness within minimum dimensional limits; 2) generate final dimensional size accuracy within low tolerances, as may be required for interchangeability of parts; 3) provide rapid and economical stock removal consistent with accomplishment of the other results; and 4) generate surface finishes of a specified degree of surface smoothness with high surface quality.

Amount and Rate of Stock Removal.— Honing may be employed to increase bore diameters by as much as 0.100 inch or as little as 0.001 inch. The amount of stock removed by the honing process is entirely a question of processing economy. If other operations are performed before honing then the bulk of the stock should be taken off by the operation that can do it most economically. In large diameter bores that have been distorted in heat treating, it may be necessary to remove as much as 0.030 to 0.040 inch from the diameter to make the bore round and straight. For out-of-round or tapered bores, a good "rule of thumb" is to leave twice as much stock (on the diameter) for honing as there is error in the bore. Another general rule is: For bores over one inch in diameter, leave 0.001 to 0.0015 inch stock per inch of diameter. For example, 0.002 to 0.003 inch of stock is left in two-inch bores and 0.010 to 0.015 inch in ten-inch bores. Where parts are to be honed for finish only, the amount of metal to be left for removing tool marks may be as little as 0.0002 to 0.015 inch on the diameter.

In general, the honing process can be employed to remove stock from bore diameters at the rate of 0.009 to 0.012 inch per minute on cast-iron parts and from 0.005 to 0.008 inch per minute on steel parts having a hardness of 60 to 65 Rockwell C. These rates are based on parts having a length equal to three or four times the diameter. Stock has been removed

Copyright 2004, Industrial Press, Inc., New York, NY

from long parts such as gun barrels, at the rate of 65 cubic inches per hour. Recommended honing speeds for cast iron range from 110 to 200 surface feet per minute of rotation and from 50 to 110 lineal feet per minute of reciprocation. For steel, rotating surface speeds range from 50 to 110 feet per minute and reciprocation speeds from 20 to 90 lineal feet per minute. The exact rotation and reciprocation speeds to be used depend upon the size of the work, the amount and characteristics of the material to be removed and the quality of the finish desired. In general, the harder the material to be honed, the lower the speed. Interrupted bores are usually honed at faster speeds than plain bores.

Formula for Rotative Speeds.— Empirical formulas for determining rotative speeds for honing have been developed by the Micromatic Hone Corp. These formulas take into consideration the type of material being honed, its hardness and its surface characteristics; the abrasive area; and the type of surface pattern and degree of surface roughness desired. Because of the wide variations in material characteristics, abrasives available, and types of finishes specified, these formulas should be considered as a guide only in determining which of the available speeds (pulley or gear combinations) should be used for any particular application.

The formula for rotative speed, S, in surface feet per minute is: $S = \frac{K \times D}{W \times N}$

The formula for rotative speed in revolutions per minute is: $\text{R.P.M} = \frac{R}{W \times N}$

where, K and R are factors taken from the table on the following page, D is the diameter of the bore in inches, W is the width of the abrasive stone or stock in inches, and N is the number of stones.

Although the actual speed of the abrasive is the resultant of both the rotative speed and the reciprocation speed, this latter quantity is seldom solved for or used. The reciprocation speed is not determined empirically but by testing under operating conditions. Changing the reciprocation speed affects the dressing action of the abrasive stones, therefore, the reciprocation speed is adjusted to provide for a desired surface finish which is usually a well lubricated bearing surface that will not scuff.

Table of Factors for Use in Rotative Speed Formulas

Character of Surface[a]	Material	Hardness[b]					
		Soft		Medium		Hard	
		Factors					
		K	*R*	*K*	*R*	*K*	*R*
Base Metal	Cast Iron	110	420	80	300	60	230
	Steel	80	300	60	230	50	190
Dressing Surface	Cast Iron	150	570	110	420	80	300
	Steel	110	420	80	300	60	230
Severe Dressing	Cast Iron	200	760	150	570	110	420
	Steel	150	570	110	420	80	300

[a] The character of the surface is classified according to its effect on the abrasive; *Base Metal* being a honed, ground or fine bored section that has little dressing action on the grit; *Dressing Surface* being a rough bored, reamed or broached surface or any surface broken by cross holes or ports; *Severe Dressing* being a surface interrupted by keyways, undercuts or burrs that dress the stones severely. If over half of the stock is to be removed after the surface is cleaned up, the speed should be computed using the *Base Metal* factors for *K* and *R*.

[b] Hardness designations of soft, medium and hard cover the following ranges on the Rockwell " C" hardness scale, respectively: 15 to 45, 45 to 60 and 60 to 70.

Copyright 2004, Industrial Press, Inc., New York, NY

Possible Adjustments for Eliminating Undesirable Honing Conditions

Undesirable Condition	Adjustment Required to Correct Condition[a]								
	Abrasive[b]				Other				
	Friability	Grain Size	Hardness	Structure	Feed Pressure	Reciprocation	R.P.M.	Runout Time	Stroke Length
Abrasive Glazing	+	– –	– –	+	+ +	+ +	– –	–	0
Abrasive Loading	0	– –	–	–	+ +	+	– –	0	0
Too Rough Surface Finish	0	+ +	+ +	–	–	–	+ +	+	0
Too Smooth Surface Finish	0	– –	– –	+	+	+	– –	–	0
Poor Stone Life	–	+	+ +	–	–	–	+	0	0
Slow Stock Removal	+	– –	–	+	+ +	+ +	– –	0	0
Taper — Large at Ends	0	0	0	0	0	0	0	0	–
Taper — Small at Ends	0	0	0	0	0	0	0	0	+

[a] The + and + + symbols generally indicate that there should be an increase or addition while the – and – – symbols indicate that there should be a reduction or elimination. In each case, the double symbol indicates that the contemplated change would have the greatest effect. The 0 symbol means that a change would have no effect.

[b] For the abrasive adjustments the + and + + symbols indicate a more friable grain, a finer grain, a harder grade or a more open structure and the – and – – symbols just the reverse.

Compiled by Micromatic Hone Corp.

Abrasive Stones for Honing.— Honing stones consist of aluminum oxide, silicon carbide, CBN or diamond abrasive grits, held together in stick form by a vitrified clay, resinoid or metal bond. CBN metal-bond stones are particularly suitable and widely used for honing. The grain and grade of abrasive to be used in any particular honing operation depend upon the quality of finish desired, the amount of stock to be removed, the material being honed and other factors.

The following general rules may be followed in the application of abrasive for honing: 1) Silicon-carbide abrasive is commonly used for honing cast iron, while aluminum-oxide abrasive is generally used on steel; 2) The harder the material being honed, the softer the abrasive stick used; 3) A rapid reciprocating speed will tend to make the abrasive cut fast because the dressing action on the grits will be severe; and 4) To improve the finish, use a finer abrasive grit, incorporate more multi-direction action, allow more "run-out" time after honing to size, or increase the speed of rotation.

Surface roughnesses ranging from less than 1 micro-inch r.m.s. to a relatively coarse roughness can be obtained by judicious choice of abrasive and honing time but the most common range is from 3 to 50 micro-inches r.m.s.

Adjustments for Eliminating Undesirable Honing Conditions.— The accompanying table indicates adjustments that may be made to correct certain undesirable conditions encountered in honing. Only one change should be made at a time and its effect noted before making other adjustments.

Tolerances.— For bore diameters above 4 inches the tolerance of honed surfaces with respect to roundness and straightness ranges from 0.0005 to 0.001 inch; for bore diameters from 1 to 4 inches, 0.0003 to 0.0005 inch; and for bore diameters below 1 inch, 0.00005 to 0.0003 inch.

Laps and Lapping

Material for Laps.— Laps are usually made of soft cast iron, copper, brass or lead. In general, the best material for laps to be used on very accurate work is soft, close-grained cast iron. If the grinding, prior to lapping, is of inferior quality, or an excessive allowance has been left for lapping, copper laps may be preferable. They can be charged more easily and cut more rapidly than cast iron, but do not produce as good a finish. Whatever material is

Copyright 2004, Industrial Press, Inc., New York, NY

used, the lap should be softer than the work, as, otherwise, the latter will become charged with the abrasive and cut the lap, the order of the operation being reversed. A common and inexpensive form of lap for holes is made of lead which is cast around a tapering steel arbor. The arbor usually has a groove or keyway extending lengthwise, into which the lead flows, thus forming a key that prevents the lap from turning. When the lap has worn slightly smaller than the hole and ceases to cut, the lead is expanded or stretched a little by the driving in of the arbor. When this expanding operation has been repeated two or three times, the lap usually must be trued or replaced with a new one, owing to distortion.

The tendency of lead laps to lose their form is an objectionable feature. They are, however, easily molded, inexpensive, and quickly charged with the cutting abrasive. A more elaborate form for holes is composed of a steel arbor and a split cast-iron or copper shell which is sometimes prevented from turning by a small dowel pin. The lap is split so that it can be expanded to accurately fit the hole being operated upon. For hardened work, some toolmakers prefer copper to either cast iron or lead. For holes varying from $\frac{1}{4}$ to $\frac{1}{2}$ inch in diameter, copper or brass is sometimes used; cast iron is used for holes larger than $\frac{1}{2}$ inch in diameter. The arbors for these laps should have a taper of about $\frac{1}{4}$ or $\frac{3}{8}$ inch per foot. The length of the lap should be somewhat greater than the length of the hole, and the thickness of the shell or lap proper should be from $\frac{1}{8}$ to $\frac{1}{6}$ its diameter.

External laps are commonly made in the form of a ring, there being an outer ring or holder and an inner shell which forms the lap proper. This inner shell is made of cast iron, copper, brass or lead. Ordinarily the lap is split and screws are provided in the holder for adjustment. The length of an external lap should at least equal the diameter of the work, and might well be longer. Large ring laps usually have a handle for moving them across the work.

Laps for Flat Surfaces.— Laps for producing plane surfaces are made of cast iron. In order to secure accurate results, the lapping surface must be a true plane. A flat lap that is used for roughing or "blocking down" will cut better if the surface is scored by narrow grooves. These are usually located about $\frac{1}{2}$ inch apart and extend both lengthwise and crosswise, thus forming a series of squares similar to those on a checker-board. An abrasive of No. 100 or 120 emery and lard oil can be used for charging the roughing lap. For finer work, a lap having an unscored surface is used, and the lap is charged with a finer abrasive. After a lap is charged, all loose abrasive should be washed off with gasoline, for fine work, and when lapping, the surface should be kept moist, preferably with kerosene. Gasoline will cause the lap to cut a little faster, but it evaporates so rapidly that the lap soon becomes dry and the surface caked and glossy in spots. Loose emery should not be applied while lapping, for if the lap is well charged with abrasive in the beginning, is kept well moistened and not crowded too hard, it will cut for a considerable time. The pressure upon the work should be just enough to insure constant contact. The lap can be made to cut only so fast, and if excessive pressure is applied it will become "stripped" in places. The causes of scratches are: Loose abrasive on the lap; too much pressure on the work, and poorly graded abrasive. To produce a perfectly smooth surface free from scratches, the lap should be charged with a very fine abrasive.

Grading Abrasives for Lapping.— For high-grade lapping, abrasives can be evenly graded as follows: A quantity of flour-emery or other abrasive is placed in a heavy cloth bag, which is gently tapped, causing very fine particles to be sifted through. When a sufficient quantity has been obtained in this way, it is placed in a dish of lard or sperm oil. The largest particles will then sink to the bottom and in about one hour the oil should be poured into another dish, care being taken not to disturb the sediment at the bottom. The oil is then allowed to stand for several hours, after which it is poured again, and so on, until the desired grade is obtained.

Copyright 2004, Industrial Press, Inc., New York, NY

Charging Laps.— To charge a flat cast-iron lap, spread a very thin coating of the prepared abrasive over the surface and press the small cutting particles into the lap with a hard steel block. There should be as little rubbing as possible. When the entire surface is apparently charged, clean and examine for bright spots; if any are visible, continue charging until the entire surface has a uniform gray appearance. When the lap is once charged, it should be used without applying more abrasive until it ceases to cut. If a lap is over-charged and an excessive amount of abrasive is used, there is a rolling action between the work and lap which results in inaccuracy. The surface of a flat lap is usually finished true, prior to charging, by scraping and testing with a standard surface-plate, or by the well-known method of scraping-in three plates together, in order to secure a plane surface. In any case, the bearing marks or spots should be uniform and close together. These spots can be blended by covering the plates evenly with a fine abrasive and rubbing them together. While the plates are being ground in, they should be carefully tested and any high spots which may form should be reduced by rubbing them down with a smaller block.

To charge cylindrical laps for internal work, spread a thin coating of prepared abrasive over the surface of a hard steel block, preferably by rubbing lightly with a cast-iron or copper block; then insert an arbor through the lap and roll the latter over the steel block, pressing it down firmly to embed the abrasive into the surface of the lap. For external cylindrical laps, the inner surface can be charged by rolling-in the abrasive with a hard steel roller that is somewhat smaller in diameter than the lap. The taper cast-iron blocks which are sometimes used for lapping taper holes can also be charged by rolling-in the abrasive, as previously described; there is usually one roughing and one finishing lap, and when charging the former, it may be necessary to vary the charge in accordance with any error which might exist in the taper.

Rotary Diamond Lap.— This style of lap is used for accurately finishing very small holes, which, because of their size, cannot be ground. While the operation is referred to as lapping, it is, in reality, a grinding process, the lap being used the same as a grinding wheel. Laps employed for this work are made of mild steel, soft material being desirable because it can be charged readily. Charging is usually done by rolling the lap between two hardened steel plates. The diamond dust and a little oil is placed on the lower plate, and as the lap revolves, the diamond is forced into its surface. After charging, the lap should be washed in benzine. The rolling plates should also be cleaned before charging with dust of a finer grade. It is very important not to force the lap when in use, especially if it is a small size. The lap should just make contact with the high spots and gradually grind them off. If a diamond lap is lubricated with kerosene, it will cut freer and faster. These small laps are run at very high speeds, the rate depending upon the lap diameter. Soft work should never be ground with diamond dust because the dust will leave the lap and charge the work.

When using a diamond lap, it should be remembered that such a lap will not produce sparks like a regular grinding wheel; hence, it is easy to crowd the lap and "strip" some of the diamond dust. To prevent this, a sound intensifier or "harker" should be used. This is placed against some stationary part of the grinder spindle, and indicates when the lap touches the work, the sound produced by the slightest contact being intensified.

Grading Diamond Dust.— The grades of diamond dust used for charging laps are designated by numbers, the fineness of the dust increasing as the numbers increase. The diamond, after being crushed to powder in a mortar, is thoroughly mixed with high-grade olive oil. This mixture is allowed to stand five minutes and then the oil is poured into another receptacle. The coarse sediment which is left is removed and labeled No. 0, according to one system. The oil poured from No. 0 is again stirred and allowed to stand ten minutes, after which it is poured into another receptacle and the sediment remaining is labeled No. 1. This operation is repeated until practically all of the dust has been recovered from the oil, the time that the oil is allowed to stand being increased as shown by the following table. This is done in order to obtain the smaller particles that require a longer time for precipitation:

Copyright 2004, Industrial Press, Inc., New York, NY

To obtain No. 1 — 10 minutes	To obtain No. 4 — 2 hours
To obtain No. 2 — 30 minutes	To obtain No. 5 — 10 hours
To obtain No. 3 — 1 hour	To obtain No. 6 — until oil is clear

The No. 0 or coarse diamond which is obtained from the first settling is usually washed in benzine, and re-crushed unless very coarse dust is required. This No. 0 grade is sometimes known as "ungraded" dust. In some places the time for settling, in order to obtain the various numbers, is greater than that given in the table.

Cutting Properties of Laps and Abrasives.— In order to determine the cutting properties of abrasives when used with different lapping materials and lubricants, a series of tests was conducted, the results of which were given in a paper by W. A. Knight and A. A. Case, presented before the American Society of Mechanical Engineers. In connection with these tests, a special machine was used, the construction being such that quantitative results could be obtained with various combinations of abrasive, lubricant, and lap material. These tests were confined to surface lapping.

It was not the intention to test a large variety of abrasives, three being selected as representative; namely, Naxos emery, carborundum, and alundum. Abrasive No. 150 was used in each case, and seven different lubricants, five different pressures, and three different lap materials were employed. The lubricants were lard oil, machine oil, kerosene, gasoline, turpentine, alcohol, and soda water.

These tests indicated throughout that there is, for each different combination of lap and lubricant, a definite size of grain that will give the maximum amount of cutting. With all the tests, except when using the two heavier lubricants, some reduction in the size of the grain below that used in the tests (No. 150) seemed necessary before the maximum rate of cutting was reached. This reduction, however, was continuous and soon passed below that which gave the maximum cutting rate.

Cutting Qualities with Different Laps.— The surfaces of the steel and cast-iron laps were finished by grinding. The hardness of the different laps, as determined by the scleroscope was, for cast-iron, 28; steel, 18; copper, 5. The total amount ground from the test-pieces with each of the three laps showed that, taking the whole number of tests as a standard, there is scarcely any difference between the steel and cast iron, but that copper has somewhat better cutting qualities, although, when comparing the laps on the basis of the highest and lowest values obtained with each lap, steel and cast iron are as good for all practical purposes as copper, when the proper abrasive and lubricant are used.

Wear of Laps.— The wear of laps depends upon the material from which they are made and the abrasive used. The wear on all laps was about twice as fast with carborundum as with emery, while with alundum the wear was about one and one-fourth times that with emery. On an average, the wear of the copper lap was about three times that of the cast-iron lap. This is not absolute wear, but wear in proportion to the amount ground from the test-pieces.

Lapping Abrasives.— As to the qualities of the three abrasives tested, it was found that carborundum usually began at a lower rate than the other abrasives, but, when once started, its rate was better maintained. The performance gave a curve that was more nearly a straight line. The charge or residue as the grinding proceeded remained cleaner and sharper and did not tend to become pasty or mucklike, as is so frequently the case with emery. When using a copper lap, carborundum shows but little gain over the cast-iron and steel laps, whereas, with emery and alundum, the gain is considerable.

Effect of Different Lapping Lubricants.— The action of the different lubricants, when tested, was found to depend upon the kind of abrasive and the lap material.

Lard and Machine Oil: The test showed that lard oil, without exception, gave the higher rate of cutting, and that, in general, the initial rate of cutting is higher with the lighter lubri-

Copyright 2004, Industrial Press, Inc., New York, NY

cants, but falls off more rapidly as the test continues. The lowest results were obtained with machine oil, when using an emery-charged, cast-iron lap. When using lard oil and a carborundum-charged steel lap, the highest results were obtained.

Gasoline and Kerosene: On the cast-iron lap, gasoline was superior to any of the lubricants tested. Considering all three abrasives, the relative value of gasoline, when applied to the different laps, is as follows: Cast iron, 127; copper, 115; steel, 106. Kerosene, like gasoline, gives the best results on cast iron and the poorest on steel. The values obtained by carborundum were invariably higher than those obtained with emery, except when using gasoline and kerosene on a copper lap.

Turpentine and Alcohol: Turpentine was found to do good work with carborundum on any lap. With emery, turpentine did fair work on the copper lap, but, with the emery on cast-iron and steel laps, it was distinctly inferior. Alcohol gives the lowest results with emery on the cast-iron and steel laps.

Soda Water: Soda water gives medium results with almost any combination of lap and abrasives, the best work being on the copper lap and the poorest on the steel lap. On the cast-iron lap, soda water is better than machine or lard oil, but not so good as gasoline or kerosene. Soda water when used with alundum on the copper lap, gave the highest results of any of the lubricants used with that particular combination.

Lapping Pressures.— Within the limits of the pressures used, that is, up to 25 pounds per square inch, the rate of cutting was found to be practically proportional to the pressure. The higher pressures of 20 and 25 pounds per square inch are not so effective on the copper lap as on the other materials.

Wet and Dry Lapping.— With the "wet method" of using a surface lap, there is a surplus of oil and abrasive on the surface of the lap. As the specimen being lapped is moved over it, there is more or less movement or shifting of the abrasive particles. With the "dry method," the lap is first charged by rubbing or rolling the abrasive into its surface. All surplus oil and abrasive are then washed off, leaving a clean surface, but one that has embedded uniformly over it small particles of the abrasive. It is then like the surface of a very fine oilstone and will cut away hardened steel that is rubbed over it. While this has been termed the dry method, in practice, the lap surface is kept moistened with kerosene or gasoline.

Experiments on dry lapping were carried out on the cast-iron, steel, and copper laps used in the previous tests, and also on one of tin made expressly for the purpose. Carborundum alone was used as the abrasive and a uniform pressure of 15 pounds per square inch was applied to the specimen throughout the tests. In dry lapping, much depends upon the manner of charging the lap. The rate of cutting decreased much more rapidly after the first 100 revolutions than with the wet method. Considering the amounts ground off during the first 100 revolutions, and the best result obtained with each lap taken as the basis of comparison, it was found that with a tin lap, charged by rolling No. 150 carborundum into the surface, the rate of cutting, when dry, approached that obtained with the wet method. With the other lap materials, the rate with the dry method was about one-half that of the wet method.

Summary of Lapping Tests.— The initial rate of cutting does not greatly differ for different abrasives. There is no advantage in using an abrasive coarser than No. 150. The rate of cutting is practically proportional to the pressure. The wear of the laps is in the following proportions: cast iron, 1.00; steel, 1.27; copper, 2.62. In general, copper and steel cut faster than cast iron, but, where permanence of form is a consideration, cast iron is the superior metal. Gasoline and kerosene are the best lubricants to use with a cast-iron lap. Machine and lard oil are the best lubricants to use with copper or steel laps. They are, however, least effective on a cast-iron lap. In general, wet lapping is from 1.2 to 6 times as fast as dry lapping, depending upon the material of the lap and the manner of charging.

Copyright 2004, Industrial Press, Inc., New York, NY

KNURLS AND KNURLING

ANSI Standard Knurls and Knurling.— The ANSI/ASME Standard B94.6-1984 covers knurling tools with standardized diametral pitches and their dimensional relations with respect to the work in the production of straight, diagonal, and diamond knurling on cylindrical surfaces having teeth of uniform pitch parallel to the cylinder axis or at a helix angle not exceeding 45 degrees with the work axis.

These knurling tools and the recommendations for their use are equally applicable to general purpose and precision knurling. The advantage of this ANSI Standard system is the provision by which good tracking (the ability of teeth to mesh as the tool penetrates the work blank in successive revolutions) is obtained by tools designed on the basis of diametral pitch instead of TPI (teeth per inch) when used with work blank diameters that are multiples of 1/64 inch for 64 and 128 diametral pitch or 1/32 inch for 96 and 160 diametral pitch. The use of knurls and work blank diameters which will permit good tracking should improve the uniformity and appearance of knurling, eliminate the costly trial and error methods, reduce the failure of knurling tools and production of defective work, and decrease the number of tools required. Preferred sizes for cylindrical knurls are given in Table 1 and detailed specifications appear in Table 2.

Table 1. ANSI Standard Preferred Sizes for Cylindrical Type Knurls
ANSI/ASME B94.6-1984

Nominal Outside Diameter D_{nt}	Width of Face F	Diameter of Hole A	Standard Diametral Pitches, P			
			64	96	128	160
			Number of Teeth, N_r, for Standard Pitches			
1/2	3/16	3/16	32	48	64	80
5/8	1/4	1/4	40	60	80	100
3/4	3/8	1/4	48	72	96	120
7/8	3/8	1/4	56	84	112	140
Additional Sizes for Bench and Engine Lathe Tool Holders						
5/8	5/16	7/32	40	60	80	100
3/4	5/8	1/4	48	72	96	120
1	3/8	5/16	64	96	128	160

The 96 diametral pitch knurl should be given preference in the interest of tool simplification. Dimensions D_{nt}, F, and A are in inches.

Table 2. ANSI Standard Specifications for Cylindrical Knurls with Straight or Diagonal Teeth *ANSI/ASME B94.6-1984*

Diametral Pitch P	Nominal Diameter, D_{nt}					Tracking Correction Factor Q	Tooth Depth, h, +0.0015, −0.0000		Radius at Root R
	1/2	5/8	3/4	7/8	1		Straight	Diagonal	
	Major Diameter of Knurl, D_{ot}, +0.0000, −0.0015								
64	0.4932	0.6165	0.7398	0.8631	0.9864	0.0006676	0.024	0.021	0.0070 0.0050
96	0.4960	0.6200	0.7440	0.8680	0.9920	0.0002618	0.016	0.014	0.0060 0.0040
128	0.4972	0.6215	0.7458	0.8701	0.9944	0.0001374	0.012	0.010	0.0045 0.0030
160	0.4976	0.6220	0.7464	0.8708	0.9952	0.00009425	0.009	0.008	0.0040 0.0025

All dimensions except diametral pitch are in inches.

Approximate angle of space between sides of adjacent teeth for both straight and diagonal teeth is 80 degrees. The permissible eccentricity of teeth for all knurls is 0.002 inch maximum (total indicator reading).

Number of teeth in a knurl equals diametral pitch multiplied by nominal diameter.

Diagonal teeth have 30-degree helix angle, ψ.

Copyright 2004, Industrial Press, Inc., New York, NY

The term *Diametral Pitch* applies to the quotient obtained by dividing the total number of teeth in the circumference of the work by the basic blank diameter; in the case of the knurling tool it would be the total number of teeth in the circumference divided by the *nominal* diameter. In the Standard the diametral pitch and number of teeth are always measured in a transverse plane which is perpendicular to the axis of rotation for diagonal as well as straight knurls and knurling.

Cylindrical Knurling Tools.— The cylindrical type of knurling tool comprises a tool holder and one or more knurls. The knurl has a centrally located mounting hole and is provided with straight or diagonal teeth on its periphery. The knurl is used to reproduce this tooth pattern on the work blank as the knurl and work blank rotate together.

**Formulas for Cylindrical Knurls*

$$P = \text{diametral pitch of knurl} = N_t \div D_{nt} \quad (1)$$

$$D_{nt} = \text{nominal diameter of knurl} = N_t \div P \quad (2)$$

$$N_t = \text{no. of teeth on knurl} = P \times D_{nt} \quad (3)$$

$$^*P_{nt} = \text{circular pitch on nominal diameter} = \pi \div P \quad (4)$$

$$^*P_{ot} = \text{circular pitch on major diameter} = \pi D_{ot} \div N_t \quad (5)$$

$$D_{ot} = \text{major diameter of knurl} = D_{nt} - (N_t Q \div \pi) \quad (6)$$

$$Q = P_{nt} - P_{ot} = \text{tracking correction factor in Formula} \quad (7)$$

Tracking Correction Factor Q: Use of the preferred pitches for cylindrical knurls, Table 2, results in good tracking on all fractional work-blank diameters which are multiples of $\frac{1}{64}$ inch for 64 and 128 diametral pitch, and $\frac{1}{32}$ inch for 96 and 160 diametral pitch; an indication of good tracking is evenness of marking on the work surface during the first revolution of the work.

The many variables involved in knurling practice require that an empirical correction method be used to determine what actual circular pitch is needed at the major diameter of the knurl to produce good tracking and the required circular pitch on the workpiece. The empirical tracking correcton factor, Q, in Table 2 is used in the calculation of the major diameter of the knurl, Formula (6).



Cylindrical Knurl

* *Note:* For diagonal knurls, P_{nt} and P_{ot} are the transverse circular pitches which are measured in the plane perpendicular to the axis of rotation.

Copyright 2004, Industrial Press, Inc., New York, NY

Flat Knurling Tools.— The flat type of tool is a knurling die, commonly used in reciprocating types of rolling machines. Dies may be made with either single or duplex faces having either straight or diagonal teeth. No preferred sizes are established for flat dies.

Flat Knurling Die with Straight Teeth:



R = radius at root

P = diametral pitch = $N_w \div D_w$ (8)

D_w = work blank (pitch) diameter = $N_w \div P$ (9)

N_w = number of teeth on work = $P \times D_w$ (10)

h = tooth depth

Q = tracking correction factor (see Table 2)

P_l = linear pitch on die

= circular pitch on work pitch diameter = $P - Q$ (11)

Table 3. ANSI Standard Specifications for Flat Knurling Dies
ANSI/ASME B94.6-1984

Diametral Pitch, P	Linear Pitch,[a] P_l	Tooth Depth, h		Radius at Root, R	Diametral Pitch, P	Linear Pitch,[a] P_l	Tooth Depth, h		Radius at Root, R
		Straight	Diagonal				Straight	Diagonal	
64	0.0484	0.024	0.021	0.0070 0.0050	128	0.0244	0.012	0.010	0.0045 0.0030
96	0.0325	0.016	0.014	0.0060 0.0040	160	0.0195	0.009	0.008	0.0040 0.0025

[a] The linear pitches are theoretical. The exact linear pitch produced by a flat knurling die may vary slightly from those shown depending upon the rolling condition and the material being rolled.

All dimensions except diametral pitch are in inches.



Teeth on Knurled Work

Formulas Applicable to Knurled Work.— The following formulas are applicable to knurled work with straight, diagonal, and diamond knurling.

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Straight or Diagonal Knurling with Straight or Diagonal Tooth Cylindrical Knurling Tools Set with Knurl Axis Parallel with Work Axis:

$$P = \text{diametral pitch} = N_w \div D_w \quad (12)$$

$$D_w = \text{work blank diameter} = N_w \div P \quad (13)$$

$$N_w = \text{no. of teeth on work} = P \times D_w \quad (14)$$

$$a = \text{"addendum" of tooth on work} = (D_{ow} - D_w) \div 2 \quad (15)$$

h = tooth depth (see Table 2)

$$D_{ow} = \text{knurled diameter (outside diameter after knurling)} = D_w + 2a \quad (16)$$

Formulas for Diagonal and Diamond Knurling with Straight Tooth Knurling Tools Set at an Angle to the Work Axis:

If, ψ = angle between tool axis and work axis

P = diametral pitch on tool

P_ψ = diametral pitch produced on work blank (as measured in the transverse plane) by setting tool axis at an angle ψ with respect to work blank axis

D_w = diameter of work blank; and

N_w = number of teeth produced on work blank (as measured in the transverse plane)

then, $P_\psi = P \cos \psi$ (17)

and, $N = D_w P \cos \psi$ (18)

For example, if 30 degree diagonal knurling were to be produced on 1-inch diameter stock with a 160 pitch straight knurl:

$$N_w = D_w P \cos 30^\circ = 1.000 \times 160 \times 0.86603 = 138.56 \text{ teeth}$$

Good tracking is theoretically possible by changing the helix angle as follows to correspond to a whole number of teeth (138):

$$\cos \psi = N_w \div D_w P = 138 \div (1 \times 160) = 0.8625$$

$$\psi = 30\tfrac{1}{2} \text{ degrees, approximately}$$

Whenever it is more practical to machine the stock, good tracking can be obtained by reducing the work blank diameter as follows to correspond to a whole number of teeth (138):

$$D_w = \frac{N_w}{P \cos \psi} = \frac{138}{160 \times 0.866} = 0.996 \text{ inch}$$

Table 4. ANSI Standard Recommended Tolerances on Knurled Diameters
ANSI/ASME B94.6-1984

Tolerance Class	Diametral Pitch							
	64	96	128	160	64	96	128	160
	Tolerance on Knurled Outside Diameter				Tolerance on Work-Blank Diameter Before Knurling			
I	+0.005 −0.012	+0.004 −0.010	+0.003 −0.008	+0.002 −0.006	±0.0015	±0.0010	±0.0007	±0.0005
II	+0.000 −0.010	+0.000 −0.009	+0.000 −0.008	+0.000 −0.006	±0.0015	±0.0010	±0.0007	±0.0005
III	+0.000 −0.006	+0.000 −0.005	+0.000 −0.004	+0.000 −0.003	+0.000 −0.0015	+0.0000 −0.0010	+0.000 −0.0007	+0.0000 −0.0005

Copyright 2004, Industrial Press, Inc., New York, NY

Recommended Tolerances on Knurled Outside Diameters.— The recommended applications of the tolerance classes shown in Table 4 are as follows:

Class I: Tolerances in this classification may be applied to straight, diagonal and raised diamond knurling where the knurled outside diameter of the work need not be held to close dimensional tolerances. Such applications include knurling for decorative effect, grip on thumb screws, and inserts for moldings and castings.

Class II: Tolerances in this classification may be applied to straight knurling only and are recommended for applications requiring closer dimensional control of the knurled outside diameter than provided for by Class I tolerances.

Class III: Tolerances in this classification may be applied to straight knurling only and are recommended for applications requiring closest possible dimensional control of the knurled outside diameter. Such applications include knurling for close fits.

Note: The width of the knurling should not exceed the diameter of the blank, and knurling wider than the knurling tool cannot be produced unless the knurl starts at the end of the work.

Marking on Knurls and Dies.— Each knurl and die should be marked as follows: *a*. when straight to indicate its diametral pitch; *b*. when diagonal, to indicate its diametral pitch, helix angle, and hand of angle.

Concave Knurls.— The radius of a concave knurl should not be the same as the radius of the piece to be knurled. If the knurl and the work are of the same radius, the material compressed by the knurl will be forced down on the shoulder *D* and spoil the appearance of the work. A design of concave knurl is shown in the accompanying illustration, and all the important dimensions are designated by letters. To find these dimensions, the pitch of the knurl required must be known, and also, approximately, the throat diameter *B*. This diameter must suit the knurl holder used, and be such that the circumference contains an even number of teeth with the required pitch. When these dimensions have been decided upon, all the other unknown factors can be found by the following formulas: Let R = radius of piece to be knurled; r = radius of concave part of knurl; C = radius of cutter or hob for cutting the teeth in the knurl; B = diameter over concave part of knurl (throat diameter); A = outside diameter of knurl; d = depth of tooth in knurl; P = pitch of knurl (number of teeth per inch circumference); p = circular pitch of knurl; then $r = R + \frac{1}{2}d$; $C = r + d$; $A = B + 2r - (3d + 0.010 \text{ inch})$; and $d = 0.5 \times p \times \cot \alpha/2$, where α is the included angle of the teeth.



As the depth of the tooth is usually very slight, the throat diameter *B* will be accurate enough for all practical purposes for calculating the pitch, and it is not necessary to take into consideration the pitch circle. For example, assume that the pitch of a knurl is 32, that the throat diameter *B* is 0.5561 inch, that the radius *R* of the piece to be knurled is $\frac{1}{16}$ inch, and that the angle of the teeth is 90 degrees; find the dimensions of the knurl. Using the notation given:

$$p = \frac{1}{P} = \frac{1}{32} = 0.03125 \text{ inch} \qquad d = 0.5 \times 0.03125 \times \cot 45° = 0.0156 \text{ inch}$$

$$r = \frac{1}{16} + \frac{0.0156}{2} = 0.0703 \text{ inch} \qquad C = 0.0703 + 0.0156 = 0.0859 \text{ inch}$$

$$A = 0.5561 + 0.1406 - (0.0468 + 0.010) = 0.6399 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

MACHINE TOOL ACCURACY

Accuracy, Repeatability, and Resolution: In machine tools, accuracy is the maximum spread in measurements made of slide movements during successive runs at a number of target points, as discussed below. Repeatability is the spread of the normal curve at the target point that has the largest spread. A rule of thumb says that repeatability is approximately half the accuracy value, or twice as good as the accuracy, but this rule is somewhat nullified due to the introduction of error-compensation features on NC machines. Resolution refers to the smallest units of measurement that the system (controller plus servo) can recognize. Resolution is an electronic/electrical term and the unit is usually smaller than either the accuracy or the repeatability. Low values for resolution are usually, though not necessarily, applied to machines of high accuracy. In addition to high cost, a low-resolution-value design usually has a low maximum feed rate and the use of such designs is usually restricted to applications requiring high accuracy.

*Positioning Accuracy:*The positioning accuracy of a numerically controlled machine tool refers to the ability of an NC machine to place the tip of a tool at a preprogrammed target. Although no metal cutting is involved, this test is very significant for a machine tool and the cost of an NC machine will rise almost geometrically with respect to its positioning accuracy. Care, therefore, should be taken when deciding on the purchase of such a machine, to avoid paying the premium for unneeded accuracy but instead to obtain a machine that will meet the tolerance requirements for the parts to be produced.

Accuracy can be measured in many ways. A tool tip on an NC machine could be moved, for example, to a target point whose *X*-coordinate is 10.0000 inches. If the move is along the *X*-axis, and the tool tip arrives at a point that measures 10.0001 inches, does this mean that the machine has an accuracy of 0.0001 inch? What if a repetition of this move brought the tool tip to a point measuring 10.0003 inches, and another repetition moved the tool to a point that measured 9.9998 inches? In practice, it is expected that there would be a scattering or distribution of measurements and some kind of averaging is normally used.



Fig. 1. In a Normal Distribution, Plotted Points Cluster Around the Mean.

Although averaging the results of several runs is an improvement over a single run, the main problem with averaging is that it does not consider the extent or width of the spread of readings. For example, if one measurement to the 10.0000-inch target is 9.9000 inches and another is 10.1000 inches, the difference of the two readings is 0.2000 inch, and the accuracy is poor. However, the readings average a perfect 10 inches. Therefore, the average and the spread of several readings must both be considered in determining the accuracy.

Plotting the results of a large number of runs generates a *normal distribution curve,* as shown in Fig. 1. In this example, the readings are plotted along the *X*-axis in increments of

Copyright 2004, Industrial Press, Inc., New York, NY

0.0001 inch (0.0025 mm). Usually, five to ten such readings are sufficient. The distance of any one reading from the target is called the *positional deviation* of the point. The distance of the mean, or average, for the normal distribution from the target is called the *mean positional deviation*.

The spread for the normal curve is determined by a mathematical formula that calculates the distance from the mean that a certain percentage of the readings fall into. The mathematical formula used calculates one *standard deviation,* which represents approximately 32 per cent of the points that will fall within the normal curve, as shown in Fig. 2. One standard deviation is also called one sigma, or 1σ. Plus or minus one sigma (±1σ) represents 64 per cent of all the points under the normal curve. A wider range on the curve, ±2σ, means that 95.44 per cent of the points are within the normal curve, and ±3σ means that 99.74 per cent of the points are within the normal curve. If an infinite number of runs were made, almost all the measurements would fall within the ±3σ range.



Fig. 2. Percentages of Points Falling in the ±1σ (64%), ±2σ (95.44%), and ±3σ (99.74%) Ranges

The formula for calculating one standard deviation is

$$1\sigma = \sqrt{\frac{1}{n-1}\sum_{i=1}^{n}(X_{ij} - \overline{X}_j)^2}$$

where n = number of runs to the target; i = identification for any one run; X_{ij} = positional deviation for any one run (see Fig. 1); and, $\overline{X}_j$ = mean positional deviation (see Fig. 1).

The bar over the $\overline{X}$ in the formula indicates that the value is the mean or average for the normal distribution.

Example: From Fig. 3, five runs were made at a target point that is 10.0000 inches along the X-axis and the positional deviations for each run were: $x_{1j} = -0.0002, x_{2j} = +0.0002, x_{3j} = +0.0005, x_{4j} = +0.0007$, and $x_{5j} = +0.0008$ inch. The algebraic total of these five runs is +0.0020, and the mean positional deviation = $\overline{X}_j = 0.0020/5 = 0.0004$.

The calculations for one standard deviation are:

$$1\sigma = \sqrt{\frac{1}{n-1}[(X_{1j} - \overline{X}_j)^2 + (X_{2j} - \overline{X}_j)^2 + (X_{3j} - \overline{X}_j)^2 + (X_{4j} - \overline{X}_j)^2 + (X_{5j} - \overline{X}_j)^2]}$$

$$1\sigma = \sqrt{\frac{1}{5-1}[(-0.0002 - 0.0004)^2 + (0.0002 - 0.0004)^2 + (0.0005 - 0.0004)^2 + (0.0007 - 0.0004)^2 + (0.0008 - 0.0004)^2]}$$

$$= \sqrt{\frac{1}{4}(0.00000066)} = \sqrt{0.17 \times 10^{-6}} = 0.0004$$

Three sigma variations or 3σ, is 3 times sigma, equal to 0.0012 for the example.

Copyright 2004, Industrial Press, Inc., New York, NY

If an infinite number of trials were made to the target position of 10.0000 inches for the ongoing example, 99.74 per cent of the points would fall between 9.9992 and 10.0016 inches, giving a spread of ± 3σ, or 0.0024 inch. This spread alone is not considered as the *accuracy* but rather the repeatability for the target point 10.0000.



Fig. 3. Readings for Five Runs to Target Points P_1, P_2, P_3, P_4, and P_5 Result in a Mean Positional Deviation of 0.0004

To calculate the accuracy, it is not sufficient to make a number of runs to one target point along a particular axis, but rather to a number of points along the axis, the number depending on the length of axis travel provided. For example, a travel of about 3 ft requires 5, and a travel of 6 ft requires 10 target points. The standard deviation and spread for the normal curve must be determined at each target point, as shown in Fig. 4. The *accuracy* for the axis would then be the spread between the normal curve with the most negative position and the normal curve with the most positive position. Technically, the accuracy is a spread rather than a ± figure, but it is often referred to as a ± figure and it may be assumed that a ±0.003, for expediency, is equal to a spread of 0.006.

The above description for measuring accuracy considers unidirectional approaches to target points. Bidirectional movements (additional movements to the same target point from either direction) will give different results, mostly due to backlash in the lead-screw, though backlash is small with ballnut leadscrews. Measurements made with bidirectional movements will show greater spreads and somewhat less accuracy than will unidirectional movements.



Fig. 4. Two Ways of Plotting Five Target Point Spreads

Rules for determining accuracy were standardized in guidelines last revised by the Association for Manufacturing Technology (AMT) in 1972. Some European machine tool builders use the VDI/DGQ 3441 (German) guidelines, which are similar to those of the

Copyright 2004, Industrial Press, Inc., New York, NY

AMT in that normal distributions are used and a number of target points are selected along an axis. Japanese standards JIS B6201, JIS B6336, and JIS B6338 are somewhat simpler and consider only the spread of the readings, so that the final accuracy figure may be almost double that given by the AMT or VDI methods. The International Standards Organization (ISO), in 1988, issued ISO 230-2, which follows the procedures discussed above, but is somewhat less strict than the AMT recommendations. Table 1 lists some types of NC machines and the degree of accuracy that they normally provide.

Table 1. Degrees of Accuracy Expected with NC Machine Tools

Type of NC Machine	Accuracy	
	inches	mm
Large boring machines or boring mills	0.0010–0.0020	0.025–0.050
Small milling machines	0.0006–0.0010	0.015–0.025
Large machining centers	0.0005–0.0008	0.012–0.020
Small and medium-sized machining centers	0.0003–0.0006	0.008–0.015
Lathes, slant bed, small and medium sizes	0.0002–0.0005	0.006–0.012
Lathes, small precision	0.0002–0.0003	0.004–0.008
Horizontal jigmill	0.0002–0.0004	0.004–0.010
Vertical jig boring machines	0.0001–0.0002	0.002–0.005
Vertical jig grinding machines	0.0001–0.0002	0.002–0.005
Cylindrical grinding machines, small to medium sizes	0.00004–0.0003	0.001–0.007
Diamond turning lathes	0.00002–0.0001	0.0005–0.003

*Significance of Accuracy:*Numerically controlled machines are generally considered to be more accurate and more consistent in their movements than their conventional counterparts. CNC controllers have improved the accuracy by providing the ability to compensate for mechanical inaccuracies. Thus, compensation for errors in the lead-screw, parallelism and squareness of the machine ways, and for the effects of heating can be made automatically on NC machines. Some machine tool types are expected to be more accurate than others; for instance, grinding machines are more accurate than milling machines, and lathes for diamond turning are more accurate than normal slant-bed lathes.

Accuracy of machine tools depends on temperature, air pressure, local vibrations, and humidity. ISO standard 230-2 requires that, where possible, the ambient temperature for conducting such tests be held between 67.1 and 68.9 degrees F (19.5 and 20.5 degrees C).

*Autocollimation:*Checks on movements of slides and spindles, and alignment and other characteristics of machine tools are performed with great accuracy by means of an autocollimator, which is an optical, noncontact, angle-measuring instrument. Flatness, straightness, perpendicularity, and runout can also be checked by autocollimation. The instrument is designed to project a beam of light from a laser or an incandescent bulb onto an optically flat mirror. When the light beam is reflected back to the instrument, the distance traveled by the beam, also deviations from a straight line, can be detected by the projector and calculated electronically or measured by the scale.

Autocollimators have a small angular measuring range and are usually calibrated in arcseconds. One arc-second is an angle of 4.85 millionths of an inch (0.00000485 in.) per inch of distance from the vertex, and is often rounded to 5 millionths of an inch per inch. Angles can also be described in terms of radians and 1 arc-second is equal to 4.85 microradians, or 0.0000573 deg.

In practice, the interferometer or autocollimator is fixed to a rigid structure and the optical mirror, which should have a flatness of one-quarter wavelength of the light used (see page 723), is fixed to the workpiece to be measured. The initial reading is taken, and then

Copyright 2004, Industrial Press, Inc., New York, NY

the workpiece is moved to another position. Readings of movement can be made to within a few millionths of an inch. Angular displacements, corresponding to successive positions, of about 1 arc-second can be taken from most autocollimators, in azimuth or elevation or a combination of the two. Generally, the line width of the reticle limits the accuracy of reading such instruments.

Laser interferometers are designed to allow autocollimation readings to be taken by a photodetector instead of the eye, and some designs can measure angles to 0.001 arc-second, closer than is required for most machine shop applications. Output from an electronic autocollimator is usually transferred to a computer for recording or analysis if required. The computer calculates, lists, and plots the readings for the target points automatically, under control of the inspection program.

A typical plot from such a setup is seen in Fig. 5, where the central line connects the averages for the normal distributions at each target point. The upper line connects the positive outer limits and the lower line the negative outer limits for the normal distributions. The normal spread, indicating the accuracy of positioning, is 0.00065 inch (0.016 mm), for the *Y*-axis along which the measurements were taken.



Fig. 5. Laser Interferometer Plots of Movements of Slides on a Large Horizontal Machining Center Showing an Accuracy of 0.00065 inch (0.016 mm) for the *y* Axis

Effect of Machine Accuracy on Part Tolerances

Part tolerances are usually shown on prints, usually in a control block to ANSI Standard 14.5M-1994 (see *Geometric Dimensioning and Tolerancing* starting on page 630.) Table 2 shows some part tolerance symbols that relate to machine tool positioning accuracy. The accuracy of a part is affected by machine and cutting tool dynamics, alignment, fixture accuracy, operator settings, and accuracies of the cutting tools, holders, and collets, but the positioning accuracy of the machine probably has the greatest influence. Spindle rotation accuracy, or runout, also has a large influence on part accuracy.

The ratio of the attainable part accuracy to the no-load positioning accuracy can vary from 1.7:1 to 8.31:1, depending on the type of cutting operation. For instance, making a hole by drilling, followed by a light boring or reaming operation, produces a quite accurate result in about the 1.7:1 range, whereas contour milling on hard material could be at the higher end of the range. A good average for part accuracy versus machine positioning accuracy is 3.3:1, which means that the part accuracy is 3.3 times the positioning accuracy.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Symbols and Feature Control Frames *ANSI Y14.5M-1994*

Symbol	Characteristic	Meaning of Characteristic	Relationship to the Machine Tool
⌖	Position	The allowable true position tolerance of a feature from a datum (assume feature to be a drilled hole). Feature control block might appear as: ⌖ | Ø 0.005 | A. A is the datum, which can be another surface, another hole, or other feature	Assume tolerance is 0.005 mm. Machine positioning accuracy would be at least 0.005 × 0.707 = 0.0035 mm even if it is assumed that the hole accuracy is the same as the positioning accuracy. Machine could be milling, drilling, or machining center. 
	Position	Assume feature to be a turned circumference, the axis of which has to be within a tolerance to another feature. Feature control block would appear as follows if feature A were the axis of hole 1: ⌖ | Ø 0.005 | A	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Symbols and Feature Control Frames *ANSI Y14.5M-1994*

Symbol	Characteristic	Meaning of Characteristic	Relationship to the Machine Tool
○	Roundness	The roundness tolerance establishes a band. 	This tolerance would apply to turning and would be the result of radial spindle runout.
⌀	Diameter	Usually expressed as a ± tolerance attached to the dimension.	Diametral accuracy of the part would depend on the positioning accuracy of the cross-slide of lathe or grinder. Positioning accuracy would be from ½ to ¼ of part accuracy, depending chiefly on the rigidity of the tool, depth of cut, and material being cut.
⌓	Profile of a surface	Specifies a uniform boundary, along a true profile.  Feature control block might appear as: 	Affected by positioning accuracy of machine. There would be side and/or end forces on the tool so expect part to machine positioning accuracy to be high, say, 5:1

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Symbols and Feature Control Frames *ANSI Y14.5M-1994*

Symbol	Characteristic	Meaning of Characteristic	Relationship to the Machine Tool
//	Parallelism	A feature (surface) parallel to a datum plane or datum axis.  Feature control block might appear as: // | Ø 0.010 | A	Affected by positioning accuracy, machine alignment, and fixturing.
◎	Concentricity	Applies to turning. The axis of the feature must lie within the tolerance zone of another axis.  Feature control block might appear as follows: ◎ | Ø 0.005 | A	Affected by positioning accuracy, most likely along Z axis.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Symbols and Feature Control Frames *ANSI Y14.5M-1994*

Symbol	Characteristic	Meaning of Characteristic	Relationship to the Machine Tool
	Runout	Applies to the runout (both radial and axial) of a circular feature at any one position around the circumference or flat, perpendicular to the axis.  Runout at a Point (Radial)	Radial runout on part is not affected by spindle radial runout unless whole machine is untrue. Axial runout on part is affected by axial runout on machine. Feature would normally be perpendicular to datum. Feature control block might appear as: 
	Total runout	Similar to runout but applies to total surface and therefore consider both radial and axial runout. 	Would be affected by either radial or axial runout, or both, machine misalignment, or setup.
	Perpendicularity	A feature is perpendicular to a datum plane or axis.  	Affected principally by misalignment of machine or fixturing.

Copyright 2004, Industrial Press, Inc., New York, NY

NUMERICAL CONTROL

Introduction.— The Electronic Industries Association (EIA) defines numerical control as "a system in which actions are controlled by the direct insertion of numerical data at some point." More specifically, numerical control, or NC as it will be called here, involves machines controlled by electronic systems designed to accept numerical data and other instructions, usually in a coded form. These instructions may come directly from some source such as a punched tape, a floppy disk, directly from a computer, or from an operator.

The key to the success of numerical control lies in its flexibility. To machine a different part, it is only necessary to "play" a different tape. NC machines are more productive than conventional equipment and consequently produce parts at less cost even when the higher investment is considered. NC machines also are more accurate and produce far less scrap than their conventional counterparts. By 1985, over 110,000 NC machine tools were operating in the United States. Over 80 per cent of the dollars being spent on the most common types of machine tools, namely, drilling, milling, boring, and turning machines, are going into NC equipment.

NC is a generic term for the whole field of numerical control and encompasses a complete field of endeavor. Sometimes CNC, which stands for Computer Numerical Control and applies only to the control system, is used erroneously as a replacement term for NC. Albeit a monumental development, use of the term CNC should be confined to installations where the older hardware control systems have been replaced.

Metal cutting is the most popular application, but NC is being applied successfully to other equipment, including punch presses, EDM wire cutting machines, inspection machines, laser and other cutting and torching machines, tube bending machines, and sheet metal cutting and forming machines.

State of the CNC Technology Today.— Early numerical control machines were ordinary machines retrofitted with controls and motors to drive tools and tables. The operations performed were the same as the operations were on the machines replaced. Over the years, NC machines began to combine additional operations such as automatically changing tools and workpieces. The structure of the machines has been strengthened to provide more rigid platforms. These changes have resulted in a class of machine that can outperform its predecessors in both speed and accuracy. Typical capabilities of a modern machining center are accuracy better than ±0.00035 inch; spindle speeds in the range up to 25,000 rpm or more, and increasing; feed rates up to 400 inches per minute and increasing; tool change times hovering between 2 and 4 seconds and decreasing. Specialized machines have been built that can achieve accuracy better than one millionth (0.000001) of an inch.

Computer numerical control of machines has undergone a great deal of change in the last decade, largely as a result of rapid increases in computer capability. Development of new and improved materials for tooling and bearings, improvements in tool geometry, and the added structural stiffness of the new machines have made it possible to perform cutting operations at speeds and feeds that were formerly impossible to attain.

Numerical Control vs. Manual Operations.— The initial cost of a CNC machine is generally much higher than a manual machine of the same nominal capacity, and the higher initial cost leads to a higher overall cost of the machine per hour of its useful life. However, the additional cost of a CNC machine has to be considered against potential savings that the machine may make possible. Some of the individual factors that make NC and CNC machining attractive are considered below.

Labor is usually one of the highest costs in the production of a part, but the labor rate paid to a CNC machine operator may be lower than the rate paid to the operator of conventional machines. This statement is particularly true when there is a shortage of operators with specialized skills necessary for setting up and operating a manual machine. However, it should not be assumed that skilled CNC machine operators are not needed because most CNCs have manual overrides that allow the operator to adjust feeds and speeds and to manually edit or enter programs as necessary. Also, skilled setup personnel and operators are

Copyright 2004, Industrial Press, Inc., New York, NY

likely to promote better production rates and higher efficiency in the shop. In addition, the labor rate for setting up and operating a CNC machine can sometimes be divided between two or more machines, further reducing the labor costs and cost per part produced.

The quantity and quality requirements for an order of parts often determines what manufacturing process will be used to produce them. CNC machines are probably most effective when the jobs call for a small to medium number of components that require a wide range of operations to be performed. For example, if a large number of parts are to be machined and the allowable tolerances are large, then manual or automatic fixed-cycle machines may be the most viable process. But, if a large quantity of high quality parts with strict tolerances are required, then a CNC machine will probably be able to produce the parts for the lowest cost per piece because of the speed and accuracy of CNC machines. Moreover, if the production run requires designing and making a lot of specialized form tools, cams, fixtures, or jigs, then the economics of CNC machining improves even more because much of the preproduction work is not required by the nature of the CNC process.

CNC machines can be effective for producing one-of-a-kind jobs if the part is complicated and requires a lot of different operations that, if done manually, would require specialized setups, jigs, fixtures, etc. On the other hand, a single component requiring only one or two setups might be more practical to produce on a manual machine, depending on the tolerances required. When a job calls for a small to medium number of components that require a wide range of operations, CNC is usually preferable. CNC machines are also especially well suited for batch jobs where small numbers of components are produced from an existing part program, as inventory is needed. Once the part program has been tested, a batch of the parts can be run whenever necessary. Design changes can be incorporated by changing the part program as required. The ability to process batches also has an additional benefit of eliminating large inventories of finished components.

CNC machining can help reduce machine idle time. Surveys have indicated that when machining on manual machines, the average time spent on material removal is only about 40 per cent of the time required to complete a part. On particularly complicated pieces, this ratio can drop to as low as 10 per cent or even less. The balance of the time is spent on positioning the tool or work, changing tools, and similar activities. On numerically controlled machines, the metal removal time frequently has been found to be in excess of 70 per cent of the total time spent on the part. CNC nonmachining time is lower because CNC machines perform quicker tool changes and tool or work positioning than manual machines. CNC part programs require a skilled programmer and cost additional preproduction time, but specialized jigs and fixtures that are frequently required with manual machines are not usually required with CNC machines, thereby reducing setup time and cost considerably.

Additional advantages of CNC machining are reduced lead time; improved cutting efficiency and longer tool life, as a result of better control over the feeds and speeds; improved quality and consistently accurate parts, reduced scrap, and less rework; lower inspection costs after the first part is produced and proven correct; reduced handling of parts because more operations can be performed per setup; and faster response to design changes because most part changes can be made by editing the CNC program.

Numerical Control Standards.— Standards for NC hardware and software have been developed by many organizations, and copies of the latest standards may be obtained from the following: Electronic Industries Association (EIA), 2001 Pennsylvania Avenue NW, Washington, DC 20006 (EIA and ANSI/EIA); American Society of Mechanical Engineers (ASME), 345 East 47th Street, New York, NY 10017 (ANSI/ASME); American National Standards Institute (ANSI), 25 West 43rd Street, New York, NY 10036 (ANSI, ANSI/EIA, ANSI/ASME, and ISO); National Standards Association, Inc. (NSA), 1200 Quince Orchard Boulevard, Gaithersburg, MD 20878; NMTBA The Association for Manufacturing Technology, 7901 Westpark Drive, McLean, VA 22102. Some of the standards and their contents are listed briefly in the accompanying table.

Copyright 2004, Industrial Press, Inc., New York, NY

Numerical Control Standards

Standard Title	Description
ANSI/CAM-I 101-1990	Dimensional Measuring Interface Specification
ANSI/ASME B5.50	V-Flange Tool Shanks for Machining Centers with Automatic Tool Changers
ANSI/ASME B5.54-1992	Methods for Performance Evaluation of Computer Numerically Controlled Machining Centers
ANSI/ASME B89.1.12M	Methods for Performance Evaluation of Coordinate Measuring Machines
ANSI/EIA 227-A	1-inch Perforated Tape
ANSI/EIA 232-D	Interface Between Data Terminal Equipment and Data Circuit-Terminating Equipment Employing Serial Binary Data Interchange
ANSI/EIA 267-B	Axis and Motion Nomenclature for Numerically Controlled Machines
ANSI/EIA 274-D	Interchangeable Variable Block Data Format for Positioning, Contouring and Contouring/Positioning Numerically Controlled Machines
ANSI/EIA 358-B	Subset of American National Standarde Code for Information Interchange for Numerical Machine Control Perforated Tape
ANSI/EIA 408	Interface Between NC Equipment and Data Terminal Equipment Employing Parallel Binary Data Interchange
ANSI/EIA 423-A	Electrical Characteristics of Unbalanced Voltage Digital Interface Circuits
ANSI/EIA 431	Electrical Interface Between Numerical Control and Machine Tools
ANSI/EIA 441	Operator Interface Function of Numerical Controls
ANSI/EIA 449	General Purpose 37-position and 9-position Interface for Data Terminal Equipment and Data Circuit-Terminating Equipment Employing Serial Binary Data Interchange
ANSI/EIA 484	Electrical and Mechanical Interface Characteristics and Line Control Protocol Using Communication Control Characters for Serial Data Link between a Direct Numerical Control System and Numerical Control Equipment Employing Asynchronous Full Duplex Transmission
ANSI/EIA 491-A -1990	Interface between a Numerical Control Unit and Peripheral Equipment Employing Asynchronous Binary Data Interchange over Circuits having EIA-423-A Electrical Characteristics
ANSI/EIA 494	32-bit Binary CL Interchange (BCL) Input Format for Numerically Controlled Machines
EIA AB3-D	Glossary of Terms for Numerically Controlled Machines
EIA Bulletin 12	Application Notes on Interconnection between Interface Circuits Using RS-449 and RS-232-C
ANSI X 3.94	Programming Aid for Numerically Controlled Manufacturing
ANSI X 3.37	Programming Language APT
ANSI X 3.20	1-inch Perforated Tape Take-up Reels for Information Interchange
ANSI X 3.82	One-sided Single Density Unformatted 5.25 inch Flexible Disc Cartridges

Copyright 2004, Industrial Press, Inc., New York, NY

Numerical Control Standards *(Continued)*

Standard Title	Description
ISO 841	Numerical Control of Machines—Axis and Motion Nomenclature
ISO 2806	Numerical Control of Machines—Bilingual Vocabulary
ISO 2972	Numerical Control of Machines—Symbols
ISO 3592	Numerical Control of Machines—Numerical Control Processor Output, Logical Structure and Major Words
ISO 4336	Numerical Control of Machines—Specification of Interface Signals between the Numerical Control Unit and the Electrical Equipment of a Numerically Controlled Machine
ISO 4343	Numerical Control of Machines—NC Processor Output— Minor Elements of 2000-type Records (Post Processor Commands)
ISO TR 6132	Numerical Control of Machines—Program Format and Definition of Address Words—Part 1: Data Format for Positioning, Line Motion and Contouring Control Systems
ISO 230-1	Geometric Accuracy of Machines Operating Under No-Load or Finishing Conditions
ISO 230-2	Determination of Accuracy and Repeatability of Positioning of Numerically Controlled Machine Tools
NAS 911	Numerically Controlled Skin/Profile Milling Machines
NAS 912	Numerically Controlled Spar Milling Machines
NAS 913	Numerically Controlled Profiling and Contouring Milling Machines
NAS 914	Numerically Controlled Horizontal Boring, Drilling and Milling Machines
NAS 960	Numerically Controlled Drilling Machines
NAS 963	Computer Numerically Controlled Vertical and Horizontal Jig Boring Machines
NAS 970	Basic Tool Holders for Numerically Controlled Machine Tools
NAS 971	Precision Numerically Controlled Measuring/Inspection Machines
NAS 978	Numerically Controlled Machining Centers
NAS 990	Numerically Controlled Composite Filament Tape Laying Machines
NAS 993	Direct Numerical Control System
NAS 994	Adaptive Control System for Numerically Controlled Milling Machines
NAS 995	Specification for Computerized Numerical Control (CNC)
NMTBA	Common Words as They Relate to Numerical Control Software
NMTBA	Definition and Evaluation of Accuracy and Repeatability of Numerically Controlled Machine Tools
NMTBA	Numerical Control Character Code Cross Reference Chart
NMTBA	Selecting an Appropriate Numerical Control Programming Method
NEMA 1A1	Industrial Cell Controller Classification Concepts and Selection Guide

Copyright 2004, Industrial Press, Inc., New York, NY

Programmable Controller.— Frequently referred to as a PC or PLC (the latter term meaning Programmable Logic Controller), a programmable controller is an electronic unit or small computer. PLCs are used to control machinery, equipment, and complete processes, and to assist CNC systems in the control of complex NC machine tools and flexible manufacturing modules and cells. In effect, PLCs are the technological replacements for electrical relay systems.



Fig. 1. Programmable Controllers' Four Basic Elements

As shown in Fig. 1, a PLC is composed of four basic elements: the equipment for handling input and output (I/O) signals, the central processing unit (CPU), the power supply, and the memory. Generally, the CPU is a microprocessor and the brain of the PLC. Early PLCs used hardwired special-purpose electronic logic circuits, but most PLCs now being offered are based on microprocessors and have far more logic and control capabilities than was possible with hardwired systems. The CPU scans the status of the input devices continuously, correlates these inputs with the control logic in the memory, and produces the appropriate output responses needed to control the machine or equipment.

Input to a PLC is either discrete or continuous. Discrete inputs may come from push buttons, micro switches, limit switches, photocells, proximity switches or pressure switches, for instance. Continuous inputs may come from sources such as thermocouples, potentiometers, or voltmeters. Outputs from a PLC normally are directed to actuating hardware such as solenoids, solenoid valves, and motor starters. The function of a PLC is to examine the status of an input or set of inputs and, based on this status, actuate or regulate an output or set of outputs.

Digital control logic and sensor input signals are stored in the memory as a series of binary numbers (zeros and ones). Each memory location holds only one “bit” (either 0 or 1) of binary information; however, most of the data in a PLC are used in groups of 8 bits, or bytes. A word is a group of bytes that is operated on at one time by the PLC. The word size in modern PLCs ranges from 8 to 32 bits (1 to 4 bytes), depending on the design of the PLC. In general, the larger the word size that a system is able to operate on (that is, to work on at one time), the faster the system is going to perform. New systems are now beginning to appear that can operate on 64 bits of information at a time.

There are two basic categories of memory: volatile and nonvolatile. Volatile memory loses the stored information when the power is turned off, but nonvolatile memory retains its logic even when power is cut off. A backup battery must be used if the information stored in volatile memory is to be retained. There are six commonly used types of memory. Of these six, random-access memory (RAM) is the most common type because it is the easiest to program and edit. RAM is also the only one of the six common types that is vola-

Copyright 2004, Industrial Press, Inc., New York, NY

tile memory. The five nonvolatile memory types are: core memory, read-only memory (ROM), programmable read-only memory (PROM), electronically alterable programmable read-only memory (EAPROM), and electronically erasable programmable read-only memory (EEPROM). EEPROMs are becoming more popular due to their relative ease of programming and their nonvolatile characteristic. ROM is often used as a generic term to refer to the general class of read-only memory types and to indicate that this type of memory is not usually reprogrammed.

More than 90 per cent of the microprocessor PLCs now in the field use RAM memory. RAM is primarily used to store data, which are collected or generated by a process, and to store programs that are likely to change frequently. For example, a part program for machining a workpiece on a CNC machining center is loaded into and stored in RAM. When a different part is to be made, a different program can be loaded in its place. The nonvolatile memory types are usually used to store programs and data that are not expected to be changed. Programs that directly control a specific piece of equipment and contain specific instructions that allow other programs (such as a part program stored in RAM) to access and operate the hardware are usually stored in nonvolatile memory or ROM. The benefit of ROM is that stored programs and data do not have to be reloaded into the memory after the power has been turned off.

PLCs are used primarily with handling systems such as conveyors, automatic retrieval and storage systems, robots, and automatic guided vehicles (AGV), such as are used in flexible manufacturing cells, modules, and systems (see *Flexible Manufacturing Systems (FMS)*, *Flexible Manufacturing Cell*, and *Flexible Manufacturing Module*). PLCs are also to be found in applications as diverse as combustion chamber control, chemical process control, and printed-circuit-board manufacturing.

Types of Programmable Controllers

Type	No. of I/Os	General Applications	Math Capability
Mini	32	Replaces relays, timers, and counters.	Yes
Micro	32–64	Replaces relays, timers, and counters.	Yes
Small	64–128	Replaces relays, timers, and counters. Used for materials handling, and some process control.	Yes
Medium	128–512	Replaces relays, timers, and counters. Used for materials handling, process control, and data collection.	Yes
Large	512+	Replaces relays, timers, and counters. Master control for other PLCs and cells and for generation of reports. High-level network capability	Yes

Types of PLCs may be divided into five groups consisting of micro, mini, small, medium, and large according to the number of I/Os, functional capabilities, and memory capacity. The smaller the number of I/Os and memory capacity, and the fewer the functions, the simpler the PLC. Micro and mini PLCs are usually little more than replacements for relay systems, but larger units may have the functional capabilities of a small computer and be able to handle mathematical functions, generate reports, and maintain high-level communications.

Copyright 2004, Industrial Press, Inc., New York, NY

The preceding guidelines have some gray areas because mini, micro, and small PLCs are now available with large memory sizes and functional capacities normally reserved for medium and large PLCs. The accompanying table compares the various types of PLCs and their applications.

Instructions that are input to a PLC are called programs. Four major programming languages are used with PLCs, comprising ladder diagrams, Boolean mnemonics, functional blocks, and English statements. Some PLC systems even support high-level programming languages such as BASIC and PASCAL. Ladder diagrams and Boolean mnemonics are the basic control-level languages. Functional blocks and English statements are considered high-level languages. Ladder diagrams were used with electrical relay systems before these systems were replaced by PLCs and are still the most popular programming method, so they will be discussed further.



Fig. 2. One Rung on a Ladder Diagram

A ladder diagram consists of symbols, or ladder logic elements, that represent relay contacts or switches and other elements in the control system. One of the more basic symbols represents a normally open switch and is described by the symbol ┤ ├. Another symbol is the normally closed switch, described by the symbol ┤\├. When the normally open switch is activated, it will close, and when the normally closed switch is activated, it will open. Fig. 2 shows one rung (line) on a ladder diagram. Switch 1001 is normally open and switch 1002 is closed. A symbol for a coil (0001) is shown at the right. If switch 1001 is actuated, it will close. If switch 1002 is not activated, it will stay closed. With the two switches closed, current will flow through the line and energize coil 0001. The coil will activate some mechanism such as an electric motor, a robot, or an NC machine tool, for instance.

As an example, Fig. 3 shows a flexible manufacturing module (FMM), consisting of a turning center (NC lathe), an infeed conveyor, an outfeed conveyor, a robot that moves workpieces between the infeed conveyor, the turning center, and the outfeed conveyor, and a PLC. The arrowed lines show the signals going to and coming from the PLC.

Fig. 4 shows a ladder diagram for a PLC that would control the operations of the FMM by:

1) Activating the infeed conveyor to move the workpiece to a position where the robot can pick it up

2) Activating the robot to pick up the workpiece and load it into the chuck on the NC lathe

3) Activating the robot to remove the finished workpiece and place it on the outfeed conveyor

4) Activating the outfeed conveyor to move the workpiece to the next operation

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Layout of a Flexible Manufacturing Module



Fig. 4. Portion of a Typical Ladder Diagram for Control of a Flexible Manufacturing Module Including a Turning Center, Conveyors, a Robot, and a Programmable Controller

In Rung 1 of Fig. 4, a request signal for a workpiece from the NC lathe closes the normally open switch 1001. Switch 1002 will remain closed if photocell 1 is not activated, i.e., if it does not detect a workpiece. The signal therefore closes the circuit, energizes the coil, and starts the conveyor motor to bring the next workpiece into position for the robot to grasp.

Copyright 2004, Industrial Press, Inc., New York, NY

In Rung 2, switch 1002 (which has been changed in the program of the PLC from a normally closed to a normally open switch) closes when it is activated as photocell 1 detects the workpiece. The signal thus produced, together with the closing of the now normally open switch 1001, energizes the coil, causing the robot to pick up the workpiece from the infeed conveyor.

In Rung 3, switch 1004 on the lathe closes when processing of the part is completed and it is ready to be removed by the robot. Photocell 2 checks to see if there is a space on the conveyor to accept the completed part. If no part is seen by photocell 2, switch 1003 will remain closed, and with switch 1004 closed, the coil will be energized, activating the robot to transfer the completed part to the outfeed conveyor.

Rung 4 shows activation of the output conveyor when a part is to be transferred. Normally open switch 1004 was closed when processing of the part was completed. Switch 1003 (which also was changed from a normally closed to a normally open switch by the program) closes if photocell 2 detects a workpiece. The circuit is then closed and the coil is energized, starting the conveyor motor to move the workpiece clear to make way for the succeeding workpiece.

Closed-Loop System.— Also referred to as a servo or feedback system, a closed-loop system is a control system that issues commands to the drive motors of an NC machine. The system then compares the results of these commands as measured by the movement or location of the machine component, such as the table or spindlehead. The feedback devices normally used for measuring movement or location of the component are called resolvers, encoders, Inductosyns, or optical scales. The resolver, which is a rotary analog mechanism, is the least expensive, and has been the most popular since the first NC machines were developed. Resolvers are normally connected to the lead-screws of NC machines. Linear measurement is derived from monitoring the angle of rotation of the leadscrew and is quite accurate.

Encoders also are normally connected to the leadscrew of the NC machine, and measurements are in digital form. Pulses, or a binary code in digital form, are generated by rotation of the encoder, and represent turns or partial turns of the leadscrew. These pulses are well suited to the digital NC system, and encoders have therefore become very popular with such systems. Encoders generally are somewhat more expensive than resolvers.

The Inductosyn (a trade name of Farrand Controls, Inc.) also produces analog signals, but is attached to the slide or fixed part of a machine to measure the position of the table, spindlehead, or other component. The Inductosyn provides almost twice the measurement accuracy of the resolver, but is considerably more expensive, depending on the length of travel to be measured.

Optical scales generally produce information in digital form and, like the Inductosyn, are attached to the slide or fixed part of the machine. Optical scale measurements are more accurate than either resolvers or encoders and, because of their digital nature, are well suited to the digital computer in a CNC system. Like the Inductosyn, optical scales are more costly than either resolvers or encoders.

Open-Loop System.— A control system that issues commands to the drive motors of an NC machine and has no means of assessing the results of these commands is known as an open-loop system. In such a system, no provision is made for feedback of information concerning movement of the slide(s), or rotation of the leadscrew(s). Stepping motors are popular as drives for open-loop systems.

Adaptive Control.— Measuring performance of a process and then adjusting the process to obtain optimum performance is called adaptive control. In the machine tool field, adaptive control is a means of adjusting the feed and/or speed of the cutting tool, based on sensor feedback information, to maintain optimum cutting conditions. A typical arrangement is seen in Fig. 5. Adaptive control is used primarily for cutting higher-strength materials

Copyright 2004, Industrial Press, Inc., New York, NY

such as titanium, although the concept is applicable to the cutting of any material. The costs of the sensors and software have restricted wider use of the feature.



Fig. 5.

The sensors used for adaptive control are generally mounted on the machine drive shafts, tools, or even built into the drive motor. Typically, sensors are used to provide information such as the temperature at the tip of the cutting tool and the cutting force exerted by the tool. The information measured by the sensors is used by the control system computer to analyze the cutting process and adjust the feeds and speeds of the machine to maximize the material removal rate or to optimize another process variable such as surface finish. For the computer to effectively evaluate the process in real time (i.e., while cutting is in progress), details such as maximum allowable tool temperature, maximum allowable cutting force, and information about the drive system need to be integrated into the computer program monitoring the cutting process.

Adaptive control can be used to detect worn, broken, or dull tooling. Ordinarily, the adaptive control system monitors the cutting process to keep the process variables (cutting speed and feed rate, for example) within the proper range. Because the force required to machine a workpiece is lowest when the tool is new or recently resharpened, a steady increase in cutting force during a machining operation, assuming that the feed remains the same, is an indication that the tool is becoming dull (temperature may increase as well). Upon detecting cutting forces that are greater than a predetermined maximum allowable force, the control system causes the feed rate, the cutting speed, or both to be adjusted to maintain the cutting force within allowable limits. If the cutting force cannot be maintained without causing the speed and/or feed rate to be adjusted outside its allowable limits, the machine will be stopped, indicating that the tool is too dull and must be resharpened or replaced.

On some systems, the process monitoring equipment can interface directly with the machine control system, as discussed above. On other systems, the adaptive control is implemented by a separate monitoring system that is independent of the machine control system. These systems include instrumentation to monitor the operations of the machine tool, but do not have the capability to directly change operating parameters, such as feeds and speeds. In addition, this type of control does not require any modification of the existing part programs for control of the machine.

Flexible Manufacturing Systems (FMS).— A flexible manufacturing system (FMS) is a computer-controlled machining arrangement that can perform a variety of continuous metal-cutting operations on a range of components without manual intervention. The objective of such a system is to produce components at the lowest possible cost, especially components of which only small quantities are required. Flexibility, or the ability to switch from manufacture of one type of component to another, or from one type of machining to another, without interrupting production, is the prime requirement of such a system. In general, FMS are used for production of numbers of similar parts between 200 and 2000,

Copyright 2004, Industrial Press, Inc., New York, NY

although larger quantities are not uncommon. An FMS involves almost all the departments in a company, including engineering, methods, tooling and part programming, planning and scheduling, purchasing, sales and customer service, accounting, maintenance, and quality control. Initial costs of an FMS are estimated as being borne (percentages in parentheses) by machine tools (46.2), materials handling systems (7.7), tooling and fixtures (5.9), pallets (1.9), computer hardware (3.7), computer software (2.2), wash stations (2.8), automatic storage and retrieval systems (6.8), coolant and chip systems (2.4), spares (2), and others (18.4).

FMS are claimed to bring reductions in direct labor (80–90), production planning and control (65), and inspection (70). Materials handling and shop supervision are reduced, and individual productivity is raised. In the materials field, savings are made in tooling (35), scrap and rework (65), and floor space (50). Inventory is reduced and many other costs are avoided. Intangible savings claimed to result from FMS include reduced tooling changeover time, ability to produce complex parts, to incorporate engineering changes more quickly and efficiently than with other approaches, and to make special designs, so that a company can adapt quickly to changing market conditions. Requirements for spare parts with good fit are easily met, and the lower costs combine with higher quality to improve market share. FMS also are claimed to improve morale among workers, leading to higher productivity, with less paper work and more orderly shop operations. Better control of costs and improved cost data help to produce more accurate forecasts of sales and manpower requirements. Response to surges in demand and more economical materials ordering are other advantages claimed with FMS.

Completion of an FMS project is said to average 57 months, including 20 months from the time of starting investigations to the placing of the purchase order. A further 13 months are needed for delivery and a similar period for installation. Debugging and building of production takes about another 11 months before production is running smoothly. FMS are expensive, requiring large capital outlays and investments in management time, software, engineering, and shop support. Efficient operation of FMS also require constant workflow because gaps in the production cycle are very costly.

Flexible Manufacturing Cell.— A flexible manufacturing cell usually consists of two or three NC machines with some form of pallet-changing equipment or an industrial robot. Prismatic-type parts, such as would be processed on a machining center, are usually handled on pallets. Cylindrical parts, such as would be machined on an NC lathe, usually are handled with an overhead type of robot. The cell may be controlled by a computer, but is often run by programmable controllers. The systems can be operated without attendants, but the mixture of parts usually must be less than with a flexible manufacturing system (FMS).

Flexible Manufacturing Module.— A flexible manufacturing module is defined as a single machining center (or turning center) with some type of automatic materials handling equipment such as multiple pallets for machining centers, or robots for manipulating cylindrical parts and chucks for turning centers. The entire module is usually controlled by one or more programmable logic controllers.

Axis Nomenclature.— To distinguish among the different motions, or axes, of a machine tool, a system of letter addresses has been developed. A letter is assigned, for example, to the table of the machine, another to the saddle, and still another to the spindle head. These letter addresses, or axis designations, are necessary for the electronic control system to assign movement instructions to the proper machine element. The assignment of these letter addresses has been standardized on a worldwide basis and is contained in three standards, all of which are in agreement. These standards are EIA RS-267-B, issued by the Electronics Industries Association; AIA NAS-938, issued by the Aerospace Industries Association; and ISO/R 841, issued by the International Organization for Standardization.

Copyright 2004, Industrial Press, Inc., New York, NY

The standards are based on a "right-hand rule," which describes the orientation of the motions as well as whether the motions are positive or negative. If a right hand is laid palm up on the table of a vertical milling machine, as shown in Fig. 1, for example, the thumb will point in the positive *X*-direction, the forefinger in the positive *Y*-direction, and the erect middle finger in the positive *Z*-direction, or up. The direction signs are based on the motion of the cutter relative to the workpiece. The movement of the table shown in Fig. 2 is therefore positive, even though the table is moving to the left, because the motion of the cutter relative to the workpiece is to the right, or in the positive direction. The motions are considered from the part programmer's viewpoint, which assumes that the cutter always moves around the part, regardless of whether the cutter or the part moves. The right-hand rule also holds with a horizontal-spindle machine and a vertical table, or angle plate, as shown in Fig. 3. Here, spindle movement back and away from the angle plate, or workpiece, is a positive *Z*-motion, and movement toward the angle plate is a negative *Z*-motion.

Rotary motions also are governed by a right-hand rule, but the fingers are joined and the thumb is pointed in the positive direction of the axis. Fig. 4 shows the designations of the rotary motions about the three linear axes, *X*, *Y*, and *Z*. Rotary motion about the *X*-axis is designated as *A*; rotary motion about the *Y*-axis is *B*; and rotary motion about the *Z*-axis is *C*. The fingers point in the positive rotary directions. Movement of the rotary table around the *Y*-axis shown in Fig. 4 is a *B* motion and is common with horizontal machining centers. Here, the view is from the spindle face looking toward the rotary table. Referring, again, to linear motions, if the spindle is withdrawn axially from the work, the motion is a positive *Z*. A move toward the work is a negative *Z*.

When a second linear motion is parallel to another linear motion, as with the horizontal boring mill seen in Fig. 5, the horizontal motion of the spindle, or quill, is designated as *Z* and a parallel motion of the angle plate is *W*. A movement parallel to the *X*-axis is *U* and a movement parallel to the *Y*-axis is *V*. Corresponding motions are summarized as follows:

Linear	Rotary	Linear and Parallel
X	*A*	*U*
Y	*B*	*V*
Z	*C*	*W*



Fig. 1.

Table movement to the left in effect moves the cutter to the right, relative to the workpiece, or in the + direction



Fig. 2.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3.



Fig. 4.

Axis designations for a lathe are shown in Fig. 6. Movement of the cross-slide away from the workpiece, or the centerline of the spindle, is noted as a plus *X*. Movement toward the workpiece is a minus *X*. The middle finger points in the positive *Z*-direction; therefore, movement away from the headstock is positive and movement toward the headstock is negative. Generally, there is no *Y*-movement.

The machine shown in Fig. 6 is of conventional design, but most NC lathes look more like that shown in Fig. 7. The same right-hand rule applies to this four-axis lathe, on which each turret moves along its own two independent axes. Movement of the outside-diameter or upper turret, up and away from the workpiece, or spindle centerline, is a positive *X*-motion, and movement toward the workpiece is a negative *X*-motion. The same rules apply to the *U*-movement of the inside-diameter, or boring, turret. Movement of the lower turret parallel to the *Z*-motion of the outside-diameter turret is called the *W*-motion. A popular lathe configuration is to have both turrets on one slide, giving a two-axis system rather than the four-axis system shown. *X*- and *Z*-motions may be addressed for either of the two heads. Upward movement of the boring head therefore is a positive *X*-motion.



Fig. 5.



Fig. 6.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7.

Axis nomenclature for other machine configurations is shown in Fig. 9. The letters with the prime notation (e.g., X', Y', Z', W', A', and B') mean that the motion shown is positive, because the movement of the cutter with respect to the work is in a positive direction. In these instances, the workpiece is moving rather than the cutter.

Total Indicator Reading (TIR).— Total indicator reading is used as a measure of the range of machine tool error. TIR is particularly useful for describing the error in a machine tool spindle, referred to as runout. As shown in Fig. 8, there are two types of runout: axial and radial, which can be measured with a dial indicator. Axial runout refers to the wobble of a spindle and is measured at the spindle face. Radial runout is the range of movement of the spindle centerline and is measured on the side of the spindle or quill.



Fig. 8.

Copyright 2004, Industrial Press, Inc., New York, NY



Profile and contour milling machines, horizontal spindle and 5-axis machines



Vertical knee-type milling, drilling, or jig-boring machines



Turret type punch presses



Profiling and contour milling machines



Tilting table, profile and contour milling and 5-axis machines



Bridge profilers



Gantry profilers

Fig. 9.

Copyright 2004, Industrial Press, Inc., New York, NY

NUMERICAL CONTROL PROGRAMMING

Programming.— A numerical control (NC) program is a list of instructions (commands) that completely describes, in sequence, every operation to be carried out by a machine. When a program is run, each instruction is interpreted by the machine controller, which causes an action such as starting or stopping of a spindle or coolant, changing of spindle speed or rotation, or moving a table or slide a specified direction, distance, or speed. The form that program instructions can take, and how programs are stored and/or loaded into the machine, depends on the individual machine/control system. However, program instructions must be in a form (language) that the machine controller can understand.

A programming language is a system of symbols, codes, and rules that describes the manner in which program instructions can be written. One of the earliest and most widely recognized numerical control programming languages is based on the Standard ANSI/EIA RS-274-D-1980. The standard defines a recommended data format and codes for sending instructions to machine controllers. Although adherence to the standard is not mandatory, most controller manufacturers support it and most NC machine controllers (especially controllers on older NC machines using tape input) can accept data in a format that conforms, at least in part, with the recommended codes described in the RS-274-D standard. Most newer controllers also accept instructions written in proprietary formats offered (specified) by the controller's manufacturer.

One of the primary benefits of a standardized programming format is easy transfer of programs from one machine to another, but even standardized code formats such as RS-274-D are implemented differently on different machines. Consequently, a program written for one machine may not operate correctly on another machine without some modification of the program. On the other hand, proprietary formats are attractive because of features that are not available using the standardized code formats. For example, a proprietary format may make available certain codes that allow a programmer, with only a few lines of code, to program complex motions that would be difficult or even impossible to do in the standard language. The disadvantage of proprietary formats is that transferring programs to another machine may require a great deal of program modification or even complete rewriting. Generally, with programs written in a standardized format, the modifications required to get a program written for one machine to work on another machine are not extensive.

In programming, before describing the movement of any machine part, it is necessary to establish a coordinate system(s) as a reference frame for identifying the type and direction of the motion. A description of accepted terminology used worldwide to indicate the types of motion and the orientation of machine axes is contained in a separate section (Axis Nomenclature). Part geometry is programmed with reference to the same axes as are used to describe motion.

Manual data input (MDI) permits the machine operator to insert machining instructions directly into the NC machine control system via push buttons, pressure pads, knobs, or other arrangements. MDI has been available since the earliest NC machines were designed, but the method was less efficient than tape for machining operations and was used primarily for setting up the NC machine. Computer numerical control (CNC) systems, with their canned cycles and other computing capabilities, have now made the MDI concept more feasible and for some work MDI may be more practical than preparing a program. The choice depends very much on the complexity of the machining work to be done and, to a lesser degree, on the skill of the person who prepares the program.

Conversational part programming is a form of MDI that requires the operator or programmer to answer a series of questions displayed on the control panel of the CNC. The operator replies to questions that describe the part, material, tool and machine settings, and machining operations by entering numbers that identify the material, blank size and thickness or diameter, tool definitions, and other required data. Depending on capability, some

Copyright 2004, Industrial Press, Inc., New York, NY

controls can select the required spindle speed and feed rate automatically by using a materials look-up table; other systems request the appropriate feed and speed data. Tool motions needed to machine a part are described by selecting a linear or circular motion programming mode and entering endpoint and intersection coordinates of lines and radius, diameter, tangent points, and directions of arcs and circles (with some controllers, intersection and tangent points are calculated automatically). Machined elements such as holes, slots, and bolt circles are entered by selecting the appropriate tool and describing its action, or with "canned routines" built into the CNC to perform specific machining operations. On some systems, if a feature is once described, it can be copied and/or moved by: translation (copy and/or move), rotation about a point, mirror image (copy and rotate about an axis), and scaling (copy and change size). On many systems, as each command is entered, a graphic image of the part or operation gives a visual check that the program is producing the intended results. When all the necessary data have been entered, the program is constructed and can be run immediately or saved on tape, floppy disk, or other storage media for later use.

Conversational programming gives complete control of machine operations to the shop personnel, taking advantage of the experience and practical skills of the machine operator/programmer. Control systems that provide conversational programming usually include many built-in routines (fixed or canned cycles) for commonly used machining operations and may also have routines for specialized operations. Built-in routines speed programming because one command may replace many lines of program code that would take considerable time to write. Some built-in cycles allow complex machining operations to be programmed simply by specifying the final component profile and the starting stock size, handling such details as developing tool paths, depth of cut, number of roughing passes, and cutter speed automatically. On turning machines, built-in cycles for reducing diameters, chamfer and radius turning, and cutting threads automatically are common. Although many CNC machines have a conversational programming mode, the programming methods used and the features available are not standardized. Some control systems cannot be programmed from the control panel while another program is running (i.e., while a part is being machined), but those systems that can be thus programmed are more productive because programming does not require the machine to be idle. Conversational programming is especially beneficial In reducing programming time in shops that do most of their part programming from the control panel of the machine.

Manual part programming describes the preparation of a part program by manually writing the part program in word addressed format. In the past, this method implied programming without using a computer to determine tool paths, speeds and feeds, or any of the calculations normally required to describe the geometry of a part. Today, however, computers are frequently used for writing and storing the program on disk, as well as for calculations required to program the part. Manual part programming consists of writing codes, in a format appropriate to the machine controller, that instruct the controller to perform a specific action. The most widely accepted form of coding the instructions for numerically controlled machines uses the codes and formats suggested in the ANSI/EIA RS-274-D-1980, standard. This type of programming is sometimes called G-code programming, referring to a commonly used word address used in the RS-274-D standard. Basic details of programming in this format, using the various codes available, are discussed in the next section (G-Code Programming).

Computer-assisted part programming (CAPP) uses a computer to help in the preparation of the detailed instructions for operating an NC machine. In the past, defining a curve or complicated surface profile required a series of complex calculationsto describe the features in intimate detail. However, with the introduction of the microprocessor as an integral part of the CNC machine, the process of defining many complex shapes has been reduced to the simple task of calling up a canned cycle to calculate the path of the cutter. Most new CNC systems have some graphic programming capability, and many use

Copyright 2004, Industrial Press, Inc., New York, NY

graphic images of the part "drawn" on a computer screen. The part programmer moves a cutter about the part to generate the part program or the detailed block format instructions required by the control system. Machining instructions, such as the speed and feed rate, are entered via the keyboard. Using the computer as an assistant is faster and far more accurate than the manual part programming method.

Computer-assisted part programming methods generally can be characterized as either language-based or graphics-based, the distinction between the two methods being primarily in the manner by which the tool paths are developed. Some modern-language-based programming systems, such as Compact II, use interactive alphanumeric input so that programming errors are detected as soon as they are entered. Many of these programming systems are completely integrated with computer graphics and display an image of the part or operation as soon as an instruction is entered. The language-based programming systems are usually based on, or are a variation of, the APT programming language, which is discussed separately within this section (APT Programming).

The choice between computer-assisted part programming and manual part programming depends on the complexity of the part (particularly its geometry) and how many parts need to be programmed. The more complicated the part, the more benefit to be gained by CAPP, and if many parts are to be programmed, even if they are simple ones, the benefits of a computer-aided system are substantial. If the parts are not difficult to program but involve much repetition, computer-assisted part programming may also be preferred. If parts are to be programmed for several different control systems, a high-level part programming language such as APT will make writing the part programs easier. Because almost all machines have some deviations from standard practices, and few control systems use exactly the same programming format, a higher-level language allows the programmer to concentrate primarily on part geometry and machining considerations. The postprocessors (see *Postprocessors* below) for the individual control systems accommodate most of the variations in the programming required. The programmer only needs to write the program; the postprocessor deals with the machine specifics.

Graphical programming involves building a two- or three-dimensional model of a part on a computer screen by graphically defining the geometric shapes and surfaces of the part using the facilities of a CAD program. In many cases, depending on features of the CAD software package, the same computer drawing used in the design and drafting stage of a project can also be used to generate the program to produce the part. The graphical entities, such as holes, slots, and surfaces, are linked with additional information required for the specific machining operations needed. Most of the cutter movements (path of the cutter), such as those needed for the generation of pockets and lathe roughing cuts, are handled automatically by the computer. The program may then sort the various machining operations into an efficient sequence so that all operations that can be performed with a particular tool are done together, if possible. The output of graphical part programming is generally an alphanumeric part programming language output file, in a format such as an APT or Compact II file.

The part programming language file can be manually checked, and modified, as necessary before being run, and to help detect errors, many graphics programming systems also include some form of part verification software that simulates machining the part on the computer screen. Nongraphic data, such as feed rates, spindle speeds and coolant on/off, must be typed in by the part programmer or entered from acomputer data base at the appropriate points in the program, although some programs prompt for this information when needed. When the part program language file is run or compiled, the result is a center line data (CL data) file describing the part. With most computer-aided part programming output files, the CL data file needs to be processed through a postprocessor (see *Postprocessors* below) to tailor the final code produced to the actual machine being used. Postprocessor output is in a form that can be sent directly to the control system, or can be saved on tape or magnetic media and transferred to the machine tool when necessary. The

Copyright 2004, Industrial Press, Inc., New York, NY

graphic image of the part and the alphanumeric output files are saved in separate files so that either can be edited in the future if changes in the part become necessary. Revised files must be run and processed again for the part modifications to be included in the part program. Software for producing part programs is discussed further in the CAD/CAM section.

Postprocessors.— A postprocessor is computer software that contains a set of computer instructions designed to tailor the cutter center line location data (CL data), developed by a computerized part programming language, to meet the requirements of a particular machine tool/system combination. Generally, when a machine tool is programmed in a graphical programming environment or any high-level language such as APT, a file is created that describes all movements required of a cutting tool to make the part. The file thus created is run, or compiled, and the result is a list of coordinates (CL data) that describes the successive positions of the cutter relative to the origin of the machine's coordinate system. The output of the program must be customized to fit the input requirements of the machine controller that will receive the instructions. Cutter location data must be converted into a format recognized by the control system, such as G codes and M codes, or into another language or proprietary format recognized by the controller. Generally, some instructions are also added or changed by the programmer at this point.

The lack of standardization among machine tool control systems means that almost all computerized part programming languages require a postprocessor to translate the computer-generated language instructions into a form that the machine controller recognizes. Postprocessors are software and are generally prepared for a fee by the machine tool builder, the control system builder, a third party vendor, or by the user.

G-Code Programming

Programs written to operate numerical control (NC) machines with control systems that comply with the ANSI/EIA RS-274-D-1980, Standard consist of a series of data blocks, each of which is treated as a unit by the controller and contains enough information for a complete command to be carried out by the machine. Each block is made up of one or more words that indicate to the control system how its corresponding action is to be performed. A word is an ordered set of characters, consisting of a letter plus some numerical digits, that triggers a specific action of a machine tool. The first letter of the word is called the letter address of the word, and is used to identify the word to the control system. For example, X is the letter address of a dimension word that requires a move in the direction of the X-axis, Y is the letter address of another dimension word; and F is the letter address of the feed rate. The assigned letter addresses and their meanings, as listed in ANSI/EIA RS-274-D, are shown in Table 1.

Format Classification.— The *format classification sheet* completely describes the format requirements of a control system and gives other important information required to program a particular control including: the type of machine, the format classification shorthand and format detail, a listing of specific letter address codes recognized by the system (for example, G-codes: G01, G02, G17, etc.) and the range of values the available codes may take (S range: 10 to 1800 rpm, for example), an explanation of any codes not specifically assigned by the Standard, and any other unique features of the system.

The format classification shorthand is a nine- or ten-digit code that gives the type of system, the number of motion and other words available, the type and format of dimensional data required by the system, the number of motion control channels, and the number of numerically controlled axes of the system. The *format detail* verysuccinctly summarizes details of the machine and control system. This NC shorthand gives the letter address words and word lengths that can be used to make up a block. The format detail defines the basic features of the control system and the type of machine tool to which it refers. For example, the format detail

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Letter Addresses Used in Numerical Control

Letter Address	Description	Refers to
A	Angular dimension about the *X*-axis. Measured in decimal parts of a degree	Axis nomenclature
B	Angular dimension about the *Y*-axis. Measured in decimal parts of a degree	Axis nomenclature
C	Angular dimension about the *Z*-axis. Measured in decimal parts of a degree	Axis nomenclature
D	Angular dimension about a special axis, or third feed function, or tool function for selection of tool compensation	Axis nomenclature
E	Angular dimension about a special axis or second feed function	Axis nomenclature
F	Feed word (code)	Feed words
G	Preparatory word (code)	Preparatory words
H	Unassigned	
I	Interpolation parameter or thread lead parallel to the *X*-axis	Circular interpolation and threading
J	Interpolation parameter or thread lead parallel to the *Y*-axis	Circular interpolation and threading
K	Interpolation parameter or thread lead parallel to the *Z*-axis	Circular interpolation and threading
L	Unassigned	
M	Miscellaneous or auxilliary function	Miscellaneous functions
N	Sequence number	Sequence number
O	Sequence number for secondary head only	Sequence number
P	Third rapid-traverse dimension or tertiary-motion dimension parallel to *X*	Axis nomenclature
Q	Second rapid-traverse dimension or tertiary-motion dimension parallel to *Y*	Axis nomenclature
R	First rapid-traverse dimension or tertiary-motion dimension parallel to *Z* or radius for constant surface-speed calculation	Axis nomenclature
S	Spindle-speed function	Spindle speed
T	Tool function	Tool function
U	Secondary-motion dimension parallel to *X*	Axis nomenclature
V	Secondary-motion dimension parallel to *Y*	Axis nomenclature
W	Secondary-motion dimension parallel to *Z*	Axis nomenclature
X	Primary *X*-motion dimension	Axis nomenclature
Y	Primary *Y*-motion dimension	Axis nomenclature
Z	Primary *Z*-motion dimension	Axis nomenclature

N4G2X + 24Y + 24Z + 24B24I24J24F31T4M2

specifies that the NC machine is a machining center (has *X*-, *Y*-, and *Z*-axes) and a tool changer with a four-digit tool selection code (T4); the three linear axes are programmed with two digits before the decimal point and four after the decimal point (X + 24Y + 24Z + 24) and can be positive or negative; probably has a horizontal spindle and rotary table (B24

Copyright 2004, Industrial Press, Inc., New York, NY

= rotary motion about the *Y*-axis); has circular interpolation (I24J24); has a feed rate range in which there are three digits before and one after the decimal point (F31); and can handle a four-digit sequence number (N4), two-digit G-words (G2), and two-digit miscellaneous words (M2). The sequence of letter addresses in the format detail is also the sequence in which words with those addresses should appear when used in a block.

The information given in the format shorthand and format detail is especially useful when programs written for one machine are to be used on different machines. Programs that use the variable block data format described in RS-274-D can be used interchangeably on systems that have the same format classification, but for complete program compatibility between machines, other features of the machine and control system must also be compatible, such as the relationships of the axes and the availability of features and control functions.

Control systems differ in the way that the numbers may be written. Most newer CNC machines accept numbers written in a decimal-point format, however, some systems require numbers to be in a fixed-length format that does not use an explicit decimal point. In the latter case, the control system evaluates a number based on the number of digits it has, including zeros. *Zero suppression* in a control system is an arrangement that allows zeros before the first significant figure to be dropped (leading zero suppression) or allows zeros after the last significant figure to be dropped (trailing zero suppression). An *X*-axis movement of 05.3400, for example, could be expressed as 053400 if represented in the full field format, 53400 (leading zero suppression), or 0534 (trailing zero suppression). With decimal-point programming, the above number is expressed simply as 5.34. To ensure program compatibility between machines, all leading and trailing zeros should be included in numbers unless decimal-point programming is used.

Sequence Number (N-Word).— A block normally starts with a sequence number that identifies the block within the part program. Most control systems use a four-digit sequence number allowing step numbers up to N9999. The numbers are usually advanced by fives or tens in order to leave spaces for additional blocks to be inserted later if required. For example, the first block in a program would be N0000, the next block N0005; the next N0010; and so on. The slash character, /, placed in a block, before the sequence number, is called an *optional stop* and causes the block to be skipped over when actuated by the operator. The block that is being worked on by the machine is often displayed on a digital readout so that the operator may know the precise operation being performed.

Preparatory Word (G-Word).— A preparatory word (also referred to as a preparatory function or G-code) consists of the letter address G and usually two digits. The preparatory word is placed at the beginning of a block, normally following the sequence number. Most newer CNC machines allow more than one G-code to be used in a single block, although many of the older systems do not. To ensure compatability with older machines and with the RS-274-D Standard, only one G-code per block should be used.

The G-word indicates to the control system how to interpret the remainder of theblock. For example, G01 refers to linear interpolation and indicates that the words following in the block will move the cutter in a straight line. The G02 code indicates that the words following in the block will move the cutter in a clockwise circular path. A G-word can completely change the normal meaning of other words in a block. For example, X is normally a dimension word that describes a distance or position in the *X*-direction. However, if a block contains the G04 word, which is the code for a dwell, the X word represents the time, in seconds, that the machine is to dwell.

The majority of G-codes are designated as modal, which means that once used, the code remains in effect for succeeding blocks unless it is specifically changed or canceled. Therefore, it is not necessary to include modal G-codes in succeeding blocks except to change or cancel them. Unless a G-code is modal, it is only effective within its designated block for the operation it defines. Table 2, G-Code Addresses, lists standardized G-code addresses and modality.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. G-Code Addresses

Code		Description	Code		Description
G00	ab*	Rapid traverse, point to point (M,L)	G34	ab*	Thread cutting, increasing lead (L)
G01	abc	Linear interpolation (M,L)	G35	abc	Thread cutting, decreasing lead (L)
G02	abc	Circular interpolation — clockwise movement (M,L)	G36-G39	ab	Permanently unassigned
			G36	c	Used for automatic acceleration and deceleration when the blocks are short (M,L)
G03	abc	Circular interpolation—counter-clockwise movement (M,L)			
G04	ab	Dwell—a programmed time delay (M,L)	G37, G37.1, G37.2, G37.3		Used for tool gaging (M,L)
G05	ab	Unassigned	G37.4		
G06	abc	Parabolic interpolation (M,L)	G38		Used for probing to measure the diameter and center of a hole (M)
G07	c	Used for programming with cylindrical diameter values (L)	G38.1		Used with a probe to measure the parallelness of a part with respect to an axis (M)
G08	ab	Programmed acceleration (M,L). [d] Also for lathe programming with cylindrical diameter values			
			G39, G39.1		Generates a nonprogrammed block to improve cycle time and corner cutting quality when used with cutter compensation (M)
G09	ab	Programmed deceleration (M,L). [d] Used to stop the axis movement at a precise location (M,L)	G39		Tool tip radius compensation used with linear generated block (L)
G10–G12	ab	Unassigned. [d]Sometimes used for machine lock and unlock devices	G39.1		Tool tip radius compensation used used with circular generated block (L)
G13–G16	ac	Axis selection (M,L)	G40	abc	Cancel cutter compensation/ offset (M)
G13–G16	b	Unassigned	G41	abc	Cutter compensation, left (M)
G13		Used for computing lines and circle intersections (M,L)	G42	abc	Cutter compensation, right (M)
G14, G14.1	c	Used for scaling (M,L)	G43	abc	Cutter offset, inside corner (M,L)
G15–G16	c	Polar coordinate programming (M)	G44	abc	Cutter offset, outside corner (M,L)
G15, G16.1	c	Cylindrical interpolation—C axis (L)	G45–G49	ab	Unassigned
G16.2	c	End face milling—C axis (L)	G50–G59	a	Reserved for adaptive control (M,L)
G17–G19	abc	*X-Y*, *X-Z*, *Y-Z* plane selection, respectively (M,L)	G50	bb	Unassigned
G20		Unassigned	G50.1	c	Cancel mirror image (M,L)
G22–G32	ab	Unassigned	G51.1	c	Program mirror image (M,L)
G22–G23	c	Defines safety zones in which the machine axis may not enter (M,L)	G52	b	Unassigned
G22.1, G233.1	c	Defines safety zones in which the cutting tool may not exit (M,L)	G52		Used to offset the axes with respect to the coordinate zero point (see G92) (M,L)
G24	c	Single-pass rough-facing cycle (L)	G53	bc	Datum shift cancel
G27–G29		Used for automatically moving to and returning from home position (M,L)	G53	c	Call for motion in the machine coordinate system (M,L)
			G54–G59	bc	Datum shifts (M,L)
G30		Return to an alternate home position (M,L)	G54–G59.3	c	Allows for presetting of work coordinate systems (M,L)
G31, G31.1, G31.2, G31.3, G31.4		External skip function, moves an axis on a linear path until an external signal aborts the move (M,L)	G60–G62	abc	Unassigned
G33	abc	Thread cutting, constant lead (L)			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **G-Code Addresses**

Code		Description	Code		Description
G61	c	Modal equivalent of G09 except that rapid moves are not taken to a complete stop before the next motion block is executed (M,L)	G80	abc	Cancel fixed cycles
			G81	abc	Drill cycle, no dwell and rapid out (M,L)
G62	c	Automatic corner override, reduces the feed rate on an inside corner cut (M,L)	G82	abc	Drill cycle, dwell and rapid out (M,L)
G63	a	Unassigned	G83	abc	Deep hole peck drilling cycle (M,L)
G63	bc	Tapping mode (M,L)	G84	abc	Right-hand tapping cycle (M,L)
G64–G69	abc	Unassigned	G84.1	c	Left-hand tapping cycle (M,L)
G64	c	Cutting mode, usually set by the system installer (M,L)	G85	abc	Boring cycle, no dwell, feed out (M,L)
G65	c	Calls for a parametric macro (M,L)	G86	abc	Boring cycle, spindle stop, rapid out (M,L)
G66	c	Calls for a parametric macro. Applies to motion blocks only (M,L)	G87	abc	Boring cycle, manual retraction (M,L)
			G88	abc	Boring cycle, spindle stop, manual retraction (M,L)
G66.1	c	Same as G66 but applies to all blocks (M,L)	G88.1		Pocket milling (rectangular and circular), roughing cycle (M)
G67	c	Stop the modal parametric macro (see G65, G66, G66.1) (M,L)	G88.2		Pocket milling (rectangular and circular), finish cycle (M)
G68	c	Rotates the coordinate system (i.e., the axes) (M)	G88.3		Post milling, roughs out material around a specified area (M)
G69	c	Cancel axes rotation (M)	G88.4		Post milling, finish cuts material around a post (M)
G70	abc	Inch programming (M,L)	G88.5		Hemisphere milling, roughing cycle (M)
G71	abc	Metric programming (M,L)			
G72	ac	Circular interpolation CW (three-dimensional) (M)	G88.6		Hemisphere milling, finishing cycle (M)
G72	b	Unassigned			
G72	c	Used to perform the finish cut on a turned part along the Z-axis after the roughing cuts initiated under G73, G74, or G75 codes (L)	G89	abc	Boring cycle, dwell and feed out (M,L)
			G89.1		Irregular pocket milling, roughing cycle (M)
G73	b	Unassigned			
G73	c	Deep hole peck drilling cycle (M); OD and ID roughing cycle, running parallel to the Z-axis (L)	G89.2		Irregular pocket milling, finishing cycle (M)
G74	ac	Cancel multiquadrant circular interpolation (M,L)	G90	abc	Absolute dimension input (M,L)
G74	bc	Move to home position (M,L)	G91	abc	Incremental dimension input (M,L)
G74	c	Left-hand tapping cycle (M)	G92	abc	Preload registers, used to shift the coordinate axes relative to the current tool position (M,L)
G74		Rough facing cycle (L)	G93	abc	Inverse time feed rate (velocity/distance) (M,L)
G75	ac	Multiquadrant circular interpolation (M,L)	G94	c	Feed rate in inches or millimeters per minute (ipm or mpm) (M,L)
G75	b	Unassigned	G95	abc	Feed rate given directly in inches or millimeters per revolution (ipr or mpr) (M,L)
G75		Roughing routine for castings or forgings (L)			
G76–G79	ab	Unassigned	G96	abc	Maintains a constant surface speed, feet (meters) per minute (L)
			G97	abc	Spindle speed programmed in rpm (M,L)
			G98–99	ab	Unassigned

Copyright 2004, Industrial Press, Inc., New York, NY

[a] Adheres to ANSI/EIA RS-274-D;

[b] Adheres to ISO 6983/1,2,3 Standards; where both symbols appear together, the ANSI/EIA and ISO standard codes are comparable;

[c] This code is modal. All codes that are not identified as modal are nonmodal, when used according to the corresponding definition.

[d] Indicates a use of the code that does not conform with the Standard.

Symbols following a description: (M) indicates that the code applies to a mill or machining center; (L) indicates that the code applies to turning machines; (M,L) indicates that the code applies to both milling and turning machines.

Codes that appear more than once in the table are codes that are in common use, but are not defined by the Standard or are used in a manner that is different than that designated by the Standard (e.g., see G61).

Most systems that support the RS-274-D Standard codes do not use all the codes available in the Standard. Unassigned G-words in the Standard are often used by builders of machine tool control systems for a variety of special purposes, sometimes leading to confusion as to the meanings of unassigned codes. Even more confusing, some builders of systems and machine tools use the less popular standardized codes for other than the meaning listed in the Standard. For these reasons, machine code written specifically for one machine/controller will not necessarily work correctly on another machine controller without modification.

Dimension words contain numerical data that indicate either a distance or a position. The dimension units are selected by using G70 (inch programming) or G71 (metric programming) code. G71 is canceled by a G70 command, by miscellaneous functions M02 (end of program), or by M30 (end of data). The dimension words immediately follow the G-word in a block and on multiaxis machines should be placed in the following order: X, Y, Z, U, V, W, P, Q, R, A, B, C, D, and E.

Absolute programming (G90) is a method of defining the coordinate locations of points to which the cutter (or workpiece) is to move based on the fixed machine zero point. In Fig. 1, the $X - Y$ coordinates of P1 are $X = 1.0$, $Y = 0.5$ and the coordinates of P2 are $X = 2.0$, $Y = 1.1$. To indicate the movement of the cutter from one point to another when using the absolute coordinate system, only the coordinates of the destination point P2 are needed.

Incremental programming (G91) is a method of identifying the coordinates of a particular location in terms of the distance of the new location from the current location. In the example shown in Fig. 2, a move from P1 to P2 is written as X + 1.0, Y + 0.6. If there is no movement along the Z-axis, Z is zero and normally is not noted. An $X - Y$ incremental move from P2 to P3 in Fig. 2 is written as X + 1.0, Y – 0.7.



Fig. 1.



Fig. 2.

Most CNC systems offer both absolute and incremental part programming. The choice is handled by G-code G90 for absolute programming and G91 for incremental programming. G90 and G91 are both modal, so they remain in effect until canceled.

Copyright 2004, Industrial Press, Inc., New York, NY

The G92 word is used to preload the registers in the control system with desired values. A common example is the loading of the axis-position registers in the control system for a lathe. Fig. 3 shows a typical home position of the tool tip with respect to the zero point on the machine. The tool tip here is registered as being 15.0000 inches in the *Z*-direction and 4.5000 inches in the *X*-direction from machine zero. No movement of the tool is required. Although it will vary with different control system manufacturers, the block to accomplish the registration shown in Fig. 3 will be approximately:

N0050 G92 X4.5 Z15.0

Miscellaneous Functions (M-Words).— Miscellaneous functions, or M-codes, also referred to as auxiliary functions, constitute on-off type commands. M functions are used to control actions such as starting and stopping of motors, turning coolant on and off, changing tools, and clamping and unclamping parts. M functions are made up of the letter M followed by a two-digit code. Table 3 lists the standardized M-codes, however, the functions available will vary from one control system to another. Most systems provide fewer M functions than the complete list and may use some of the unassigned codes to provide additional functions that are not covered by the Standard. If an M-code is used in a block, it follows the T-word and is normally the last word in the block.

Table 3. Miscellaneous Function Words from *ANSI/EIA RS-274-D*

Code	Description
M00	Automatically *stops* the machine. The operator must push a button to continue with the remainder of the program.
M01	An *optional stop* acted upon only when the operator has previously signaled for this command by pushing a button. The machine will automatically stop when the control system senses the M01 code.
M02	This *end-of-program* code stops the machine when all commands in the block are completed. May include rewinding of tape.
M03	Start *spindle rotation* in a *clockwise* direction—looking out from the spindle face.
M04	Start *spindle rotation* in a *counterclockwise* direction—looking out from the spindle face.
M05	*Stop* the spindle in a normal and efficient manner.
M06	Command to *change a tool* (or tools) manually or automatically. Does not cover tool selection, as is possible with the T-words.
M07 to M08	M07 (coolant 2) and M08 (coolant 1) are codes to *turn on coolant*. M07 may control *flood* coolant and M08 *mist* coolant.
M09	Shuts off the coolant.
M10 to M11	M10 applies to automatic *clamping* of the machine slides, workpiece, fixture spindle, etc. M11 is an unclamping code.
M12	An inhibiting code used to synchronize multiple sets of axes, such as a four-axis lathe having two independently operated heads (turrets).
M13	Starts *CW spindle* motion and *coolant on* in the same command.
M14	Starts *CCW spindle* motion and *coolant on* in the same command.
M15 to M16	Rapid traverse of feed motion in either the +(M15) or –(M16) direction.
M17 to M18	Unassigned.
M19	Oriented spindle stop. Causes the spindle to stop at a predetermined angular position.
M20 to M29	Permanently unassigned.
M30	An *end-of-tape* code similar to M02, but M30 will also rewind the tape; also may switch automatically to a second tape reader.
M31	A command known as *interlock bypass* for temporarily circumventing a normally provided interlock.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Miscellaneous Function Words from** *ANSI/EIA RS-274-D*

Code	Description
M32 to M35	Unassigned.
M36 to M39	Permanently unassigned.
M40 to M46	Used to signal gear changes if required at the machine; otherwise, unassigned.
M47	Continues program execution from the start of the program unless inhibited by an interlock signal.
M48 to M49	M49 deactivates a manual spindle or feed override and returns the parameter to the programmed value; M48 cancels M49.
M50 to M57	Unassigned.
M58 to M59	Holds the rpm constant at the value in use when M59 is initiated; M58 cancels M59.
M60 to M89	Unassigned.
M90 to M99	Reserved for use by the machine user.

Feed Function (F-Word).— F-word stands for feed-rate word or feed rate. The meaning of the feed word depends on the system of units in use and the feed mode. For example, F15 could indicate a feed rate of 0.15 inch (or millimeter) per revolution or 15 inches (or millimeters) per minute, depending on whether G70 or G71 is used to indicate inch or metric programming and whether G94 or G95 is used to specify feed rate expressed as inches (or mm) per minute or revolution. The G94 word is used to indicate inches/minute (ipm) or millimeters/minute (mmpm) and G95 is used for inches/revolution (ipr) or millimeters/revolution (mmpr). The default system of units is selected by G70 (inch programming) or G71 (metric programming) prior to using the feed function. The feed function is modal, so it stays in effect until it is changed by setting a new feed rate. In a block, the feed function is placed immediately following the dimension word of the axis to which it applies or immediately following the last dimension word to which it applies if it is used for more than one axis.



Fig. 3.

In turning operations, when G95 is used to set a constant feed rate per revolution, the spindle speed is varied to compensate for the changing diameter of the work — the spindle speed increases as the working diameter decreases. To prevent the spindle speed from increasing beyond a maximum value, the S-word, see *Spindle Function (S-Word)*, is used to specify the maximum allowable spindle speed before issuing the G95 command. If the spindle speed is changed after the G95 is used, the feed rate is also changed accordingly. If G94 is used to set a constant feed per unit of time (inches or millimeters per minute), changes in the spindle speed do not affect the feed rate.

Feed rates expressed in inches or millimeters per revolution can be converted to feed rates in inches or millimeters per minute by multiplying the feed rate by the spindle speed in revolutions per minute: feed/minute = feed/revolution × spindle speed in rpm. Feed rates for milling cutters are sometimes given in inches or millimeters per tooth. To convert feed

Copyright 2004, Industrial Press, Inc., New York, NY

per tooth to feed per revolution, multiply the feed rate per tooth by the number of cutter teeth: feed/revolution = feed/tooth × number of teeth.

For certain types of cuts, some systems require an inverse-time *feed command* that is the reciprocal of the time in minutes required to complete the block of instructions. The feed command is indicated by a G93 code followed by an F-word value found by dividing the feed rate, in inches (millimeters) or degrees per minute, by the distance moved in the block: feed command = feed rate/distance = (distance/time)/distance = 1/time.

Feed-rate override refers to a control, usually a rotary dial on the control system panel, that allows the programmer or operator to override the programmed feed rate. Feed-rate override does not change the program; permanent changes can only be made by modifying the program. The range of override typically extends from 0 to 150 per cent of the programmed feed rate on CNC machines; older hardwired systems are more restrictive and most cannot be set to exceed 100 per cent of the preset rate.

Spindle Function (S-Word).— An S-word specifies the speed of rotation of the spindle. The spindle function is programmed by the address S followed by the number of digits specified in the format detail (usually a four-digit number). Two G-codes control the selection of spindle speed input: G96 selects a constant cutting speed in surface feet per minute (sfm) or meters per minute (mpm) and G97 selects a constant spindle speed in revolutions per minute (rpm).

In turning, a constant spindle speed (G97) is applied for threading cycles and for machining parts in which the diameter remains constant. Feed rate can be programmed with either G94 (inches or millimeters per minute) or G95 (inches or millimeters per revolution) because each will result in a constant cutting speed to feed relationship.

G96 is used to select a constant cutting speed (i.e., a constant surface speed) for facing and other cutting operations in which the diameter of the workpiece changes. The spindle speed is set to an initial value specified by the S-word and then automatically adjusted as the diameter changes so that a constant surface speed is maintained. The control system adjusts spindle speed automatically, as the working diameter of the cutting tool changes, decreasing spindle speed as the working diameter increasesor increasing spindle speed as the working diameter decreases. When G96 is used for a constant cutting speed, G95 in a succeeding block maintains a constant feed rate per revolution.

Speeds given in surface feet or meters per minute can be converted to speeds in revolutions per minute (rpm) by the formulas:

$$\text{rpm} = \frac{\text{sfm} \times 12}{\pi \times d} \qquad \text{rpm} = \frac{\text{mpm} \times 1000}{\pi \times d}$$

where d is the diameter, in inches or millimeters, of the part on a lathe or of the cutter on a milling machine; and π is equal to 3.14159.

Tool Function (T-Word).— The T-word calls out the tool that is to be selected on a machining center or lathe having an automatic tool changer or indexing turret. On machines without a tool changer, this word causes the machine to stop and request a tool change. This word also specifies the proper turret face on a lathe. The word usually is accompanied by several numbers, as in T0101, where the first pair of numbers refers to the tool number (and carrier or turret if more than one) and the second pair of numbers refers to the tool offset number. Therefore, T0101 refers to tool 1, offset 1.

Information about the tools and the tool setups is input to the CNC system in the form of a *tool data table*. Details of specific tools are transferred from the table to the part program via the T-word. The tool nose radius of a lathe tool, for example, is recorded in the tool data table so that the necessary tool path calculations can be made by the CNC system. The miscellaneous code M06 can also be used to signal a tool change, either manually or automatically.

Copyright 2004, Industrial Press, Inc., New York, NY

Compensation for variations in the tool nose radius, particularly on turning machines, allows the programmer to program the part geometry from the drawing and have the tool follow the correct path in spite of variations in the tool nose shape. Typical of the data required, as shown in Fig. 4, are the nose radius of the cutter, the *X* and *Z* distances from the gage point to some fixed reference point on the turret, and the orientation of the cutter (tool tip orientation code), as shown in Fig. 5. Details of nose radius compensation for numerical control is given in a separate section (Indexable Insert Holders for NC).



Fig. 4.



Fig. 5.

Tool offset, also called cutter offset, is the amount of cutter adjustment in a direction parallel to the axis of a tool. Tool offset allows the programmer to accommodate the varying dimensions of different tooling by assuming (for the sake of the programming) that all the tools are identical. The actual size of the tool is totally ignored by the programmer who programs the movement of the tools to exactly follow the profile of theworkpiece shape. Once tool geometry is loaded into the tool data table and the cutter compensation controls of the machine activated, the machine automatically compensates for the size of the tools in the programmed movements of the slide. In gage length programming, the tool length and tool radius or diameter are included in the program calculations. Compensation is then used only to account for minor variations in the setup dimensions and tool size.



Fig. 6.

Customarily, the tool offset is used in the beginning of a program to initialize each individual tool. Tool offset also allows the machinist to correct for conditions, such as tool wear, that would cause the location of the cutting edge to be different from the programmed location. For example, owing to wear, the tool tip in Fig. 6 is positioned a distance of 0.0065 inch from the location required for the work to be done. To compensate for this wear, the operator (or part programmer), by means of the CNC control panel, adjusts the tool tip with reference to the *X*- and *Z*-axes, moving the tool closer to the work by

Copyright 2004, Industrial Press, Inc., New York, NY

0.0065 inch throughout its traverse. The tool offset number causes the position of the cutter to be displaced by the value assigned to that offset number.



Fig. 7.



Fig. 8.

Changes to the programmed positions of cutting tool tip(s) can be made by *tool length offset* programs included in the control system. A dial or other means is generally provided on milling, drilling, and boring machines, and machining centers, allowing the operator or part programmer to override the programmed axial, or *Z*-axis, position. This feature is particularly helpful when setting the lengths of tools in their holders or setting a tool in a turret, as shown in Fig. 7, because an exact setting is not necessary. The tool can be set to an approximate length and the discrepancy eliminated by the control system.

The amount of offset may be determined by noting the amount by which the cutter is moved manually to a fixed point on the fixture or on the part, from the programmed *Z*-axis location. For example, in Fig. 7, the programmed *Z*-axis motion results in the cutter being moved to position A, whereas the required location for the tool is at B. Rather than resetting the tool or changing the part program, the tool length offset amount of 0.0500 inch is keyed into the control system. The 0.0500-inch amount is measured by moving the cutter tip manually to position B and reading the distance moved on the readout panel. Thereafter, every time that cutter is brought into the machining position, the programmed *Z*-axis location will be overridden by 0.0500 inch.

Manual adjustment of the cutter center path to correct for any variance between nominal and actual cutter radius is called *cutter compensation*. The net effect is to move the path of the center of the cutter closer to, or away from, the edge of the workpiece, as shown in Fig. 8. The compensation may also be handled via a tool data table.

When cutter compensation is used, it is necessary to include in the program a G41 code if the cutter is to be to the left of the part and a G42 code if to the right of the part, as shown in Fig. 8. A G40 code cancels cutter compensation. Cutter compensation with earlier hardwire systems was expensive, very limited, and usually held to ±0.0999 inch. The range for cutter compensation with CNC control systems can go as high as ±999.9999 inches, although adjustments of this magnitude are unlikely to be required.



Fig. 9.

Linear Interpolation.— The ability of the control system to guide the workpiece along a straight-line path at an angle to the slide movements is called linear interpolation. Move-

Copyright 2004, Industrial Press, Inc., New York, NY

ments of the slides are controlled through simultaneous monitoring of pulses by the control system. For example, if monitoring of the pulses for the *X*-axis of a milling machine is at the same rate as for the *Y*-axis, the cutting tool will move at a 45-degree angle relative to the *X*-axis. However, if the pulses are monitored at twice the rate for the *X*-axis as for the *Y*-axis, the angle that the line of travel will make with the *X*-axis will be 26.57 degrees (tangent of 26.57 degrees = ½), as shown in Fig. 9. The data required are the distances traveled in the *X*- and *Y*-directions, and from these data, the control system will generate the straight line automatically. This monitoring concept also holds for linear motions along three axes. The required G-code for linear interpolation blocks is G01. The code is modal, which means that it will hold for succeeding blocks until it is changed.

Circular Interpolation.— A simplified means of programming circular arcs in one plane, using one block of data, is called circular interpolation. This procedure eliminates the need to break the arc into straight-line segments. Circular interpolation is usually handled in one plane, or two dimensions, although three-dimensional circular interpolation is described in the Standards. The plane to be used is selected by a G or preparatory code. In Fig. 10, G17 is used if the circle is to be formed in the *X*–*Y* plane,



Fig. 10.



Fig. 11.

G18 if in the *X*–*Z* plane, and G19 if in the *Y*–*Z* plane. Often the control system is preset for the circular interpolation feature to operate in only one plane (e.g., the *X*–*Y* plane for milling machines or machining centers or the *X*–*Z* plane for lathes), and for these machines, the G-codes are not necessary.

A circular arc may be described in several ways. Originally, the RS-274 Standard specified that, with incremental programming, the block should contain:

1) A G-code describing the direction of the arc, G02 for clockwise (CW), and G03 for counterclockwise (CCW).

2) Directions for the component movements around the arc parallel to the axes. In the example shown in Fig. 11, the directions are *X* = +1.1 inches and *Y* = +1.0 inch. The signs are determined by the direction in which the arc is being generated. Here, both *X* and *Y* are positive.

3) The I dimension, which is parallel to the *X*-axis with a value of 1.3 inches, and the J dimension, which is parallel to the *Y*-axis with a value of 0.3 inch. These values, which locate point A with reference to the center of the arc, are called offset dimensions. The block for this work would appear as follows:

N0025 G02 X011000 Y010000 I013000 J003000

(The sequence number, N0025, is arbitrary.)

The block would also contain the plane selection (i.e., G17, G18, or G19), if this selection is not preset in the system. Most of the newer control systems allow duplicate words in the

Copyright 2004, Industrial Press, Inc., New York, NY

same block, but most of the older systems do not. In these older systems, it is necessary to insert the plane selection code in a separate and prior block, for example, N0020 G17.

Another stipulation in the Standard is that the arc is limited to one quadrant. Therefore, four blocks would be required to complete a circle. Four blocks would also be required to complete the arc shown in Fig. 12, which extends into all four quadrants.

When utilizing absolute programming, the coordinates of the end point are described. Again from Fig. 11, the block, expressed in absolute coordinates, appears as:

N0055 G02 X01800 Y019000 I013000 J003000

where the arc is continued from a previous block; the starting point for the arc in this block would be the end point of the previous block.



Fig. 12.



Fig. 13.

The Standard still contains the format discussed, but simpler alternatives have been developed. The latest version of the Standard (RS-274-D) allows *multiple quadrant programming* in one block, by inclusion of a G75 word. In the absolute-dimension mode (G90), the coordinates of the arc center are specified. In the incremental-dimension mode (G91), the signed (plus or minus) incremental distances from the beginning point of the arc to the arc center are given. Most system builders have introduced some variations on this format. One system builder utilizes the center and the end point of the arc when in an absolute mode, and might describe the block for going from A to B in Fig. 13 as:

N0065 G75 G02 X2.5 Y0.7 I2.2 J1.6

The I and the J words are used to describe the coordinates of the arc center. Decimal-point programming is also used here. A block for the same motion when programmed incrementally might appear as:

N0075 G75 G02 X1.1 Y – 1.6 I0.7 J0.7

This approach is more in conformance with the RS-274-D Standard in that the *X* and *Y* values describe the displacement between the starting and ending points (points A and B), and the I and J indicate the offsets of the starting point from the center. Another and even more convenient way of formulating a circular motion block is to note the coordinates of the ending point and the radius of the arc. Using absolute programming, the block for the motion in Fig. 13 might appear as:

N0085 G75 G02 X2.5 Y0.7 R10.0

The starting point is derived from the previous motion block. Multiquadrant circular interpolation is canceled by a G74 code.

Helical and Parabolic Interpolation.— Helical interpolation is used primarily for milling large threads and lubrication grooves, as shown in Fig. 14. Generally, helical interpolation involves motion in all three axes (*X*, *Y*, *Z*) and is accomplished by using circular

Copyright 2004, Industrial Press, Inc., New York, NY

interpolation (G02 or G03) while changing the third dimension. Parabolic interpolation (G06) is simultaneous and coordinated control of motion-such that the resulting cutter path describes part of a parabola. The RS-274-D Standard provides further details.

Subroutine.— A subroutine is a set of instructions or blocks that can be inserted into a program and repeated whenever required. Parametric subroutines permit letters or symbols to be inserted into the program in place of numerical values (see *Parametric Expressions and Macros*). Parametric subroutines can be called during part programming and values assigned to the letters or symbols. This facility is particularly helpful when dealing with families of parts.

A subprogram is similar to a subroutine except that a subprogram is not wholly contained within another program, as is a subroutine. Subprograms are used when it is necessary to perform the same task frequently, in different programs. The advantage of subprograms over subroutines is that subprograms may be called by any other program, whereas the subroutine can only be called by the program that contains the subroutine.

There is no standard subroutine format; however, the example below is typical of a program that might be used for milling the three pockets shown in Fig. 15. In the example, the beginning and end of the subroutine are indicated by the codes M92 and M93, respectively, and M94 is the code that is used to call the subroutine. The codes M92, M93, and M94 are not standardized (M-codes M90 through M99 are reserved for the user) and may be different from control system to control system. The subroutine functions may use different codes or may not be available at all on other systems.

N0010 G00 X.6 Y.85	Cutter is moved at a rapid traverse rate to a position over the corner of the first pocket to be cut.
N0020 M92	Tells the system that the subroutine is to start in the next block.
N0030 G01 Z–.25 F2.0	Cutter is moved axially into the workpiece 0.25 inch at 2.0 ipm.
N0040 X.8	Cutter is moved to the right 0.8 inch.
N0050 Y.2	Cutter is moved laterally up 0.2 inch.
N0060 X–.8	Cutter is moved to the left 0.8 inch.
N0070 Y.2	Cutter is moved laterally up 0.2 inch.



Fig. 14.



Fig. 15.

Copyright 2004, Industrial Press, Inc., New York, NY

N0080 X.8	Cutter is moved to the right 0.8 inch.
N0090 G00 Z.25 M93	Cutter is moved axially out of pocket at rapid traverse rate. Last block of subroutine is signaled by word M93.
N0100 X.75 Y.5	Cutter is moved to bottom left-hand corner of second pocket at rapid traverse rate.
N0110 M94 N0030	Word M94 calls for repetition of the subroutine that starts at sequence number N0030 and ends at sequence number N0090.
N0120 G00 X.2 Y–I.3	After the second pocket is cut by repetition of sequence numbers N0030 through N0090, the cutter is moved to start the third pocket.
N0130 M94 N0030	Repetition of subroutine is called for by word M94 and the third pocket is cut.

Parametric Expressions and Macros.— Parametric programming is a method whereby a variable or replaceable parameter representing a value is placed in the machining code instead of using the actual value. In this manner, a section of code can be used several or many times with different numerical values, thereby simplifying the programming and reducing the size of the program. For example, if the values of X and Y in lines N0040 to N0080 of the previous example are replaced as follows:

N0040 X#1

N0050 Y#2

N0060 X#3

N0070 Y#4

then the subroutine starting at line N0030 is a parametric subroutine. That is, the numbers following the # signs are the variables or parameters that will be replaced with actual values when the program is run. In this example, the effect of the program changes is to allow the same group of code to be used for milling pockets of different sizes. If on the other hand, lines N0010, N0100, and N0120 of the original example were changed in a similar manner, the effect would be to move the starting location of each of the slots to the location specified by the replaceable parameters.

Before the program is run, the values that are to be assigned to each of the parameters or variables are entered as a list at the start of the part program in this manner:

#1 = .8

#2 = .2

#3 = .8

#4 = .2

All that is required to repeat the same milling process again, but this time creating a different size pocket, is to change the values assigned to each of the parameters #1, #2, #3, and #4 as necessary. Techniques for using parametric programming are not standardized and are not recognized by all control systems. For this reason, consult the programming manual of the particular system for specific details.

Copyright 2004, Industrial Press, Inc., New York, NY

As with a parametric subroutine, macro describes a type of program that can be recalled to allow insertion of finite values for letter variables. The difference between a macro and a parametric subroutine is minor. The term macro normally applies toa source program that is used with computer-assisted part programming; the parametric subroutine is a feature of the CNC system and can be input directly into that system.

Conditional Expressions.— It is often useful for a program to make a choice between two or more options, depending on whether or not a certain condition exists. A program can contain one or more blocks of code that are not needed every time the program is run, but are needed some of the time. For example, refer to the previous program for milling three slots. An occasion arises that requires that the first and third slots be milled, but not the second one. If the program contained the following block of code, the machine could be easily instructed to skip the milling of the second slot:

N0095 IF [#5 EQ 0] GO TO N0120

In this block, #5 is the name of a variable; EQ is a conditional expression meaning *equals;* and GO TO is a branch statement meaning resume execution of the program at the following line number. The block causes steps N0100 and N0110 of the program to be skipped if the value of #5 (a dummy variable) is set equal to zero. If the value assigned to #5 is any number other than zero, the expression (#5 EQ 0) is not true and the remaining instructions in block N0095 are not executed. Program execution continues with the next step, N0100, and the second pocket is milled. For the second pocket to be milled, parameter #5 is initialized at the beginning of the program with a statement such as #5 = 1 or #5 = 2. Initializing #5 = 0 guarantees that the pocket is not machined. On control systems that automatically initialize all variables to zero whenever the system is reset or a program is loaded, the second slot will not be machined unless the #5 is assigned a nonzero value each time the program is run.

Other conditional expressions are: NE = not equal to; GT = greater than; LT = less than; GE = greater than or equal to; and LE = less than or equal to. As with parametric expressions, conditional expressions may not be featured on all machines and techniques and implementation will vary. Therefore, consult the control system programming manual for the specific command syntax.

Fixed (Canned) Cycles.— Fixed (canned) cycles comprise sets of instructions providing for a preset sequence of events initiated by a single command or a block of data. Fixed cycles generally are offered by the builder of the control system or machine tool as part of the software package that accompanies the CNC system. Limited numbers of canned cycles began to appear on hardwire control systems shortly before their demise. The canned cycles offered generally consist of the standard G-codes covering driling, boring, and tapping operations, plus options that have been developed by the system builder such as thread cutting and turning cycles. (See *Thread Cutting* and *Turning Cycles*.) Some standard canned cycles included in RS-274-D are shown herewith. A block of data that might be used to generate the cycle functions is also shown above each illustration. Although the G-codes for the functions are standardized, the other words in the block and the block format are not, and different control system builders have different arrangements. The blocks shown are reasonable examples of fixed cycles and do not represent those of any particular system builder.

Copyright 2004, Industrial Press, Inc., New York, NY

The G81 block for a simple drilling cycle is:

N_____G81 X_____Y_____C_____D_____F_____EOB

N_____X_____Y_____EOB



This G81 drilling cycle will move the drill point from position A to position B and then down to C at a rapid traverse rate; the drill point will next be fed from C to D at the programmed feed rate, then returned to C at the rapid traverse rate. If the cycle is to be repeated at a subsequent point, such as point E in the illustration, it is necessary Only to give the required X and Y coordinates. This repetition capability is typical of canned cycles.

The G82 block for a spotfacing or drilling cycle with a dwell is:

N_____G82 X_____Y_____C_____D_____T_____F_____EOB



This G82 code produces a cycle that is very similar to the cycle of the G81 code except for the dwell period at point D. The dwell period allows the tool to smooth out the bottom of the counterbore or spotface. The time for the dwell, in seconds, is noted as a T-word.

The G83 block for a peck-drilling cyle is:

N_____G83 X_____Y_____C_____D_____K_____F_____EOB



In the G83 peck-drilling cycle, the drill is moved from point A to point B and then to point C at the rapid traverse rate; the drill is then fed the incremental distance K, followed by

Copyright 2004, Industrial Press, Inc., New York, NY

rapid return to C. Down feed again at the rapid traverse rate through the distance K is next, after which the drill is fed another distance K. The drill is thenrapid traversed back to C, followed by rapid traverse for a distance of K + K; down feed to D follows before the drill is rapid traversed back to C, to end the cycle.

The G84 block for a tapping cycle is:

N_____G84 X_____Y_____C_____D_____F_____EOB



The G84 canned tapping cycle starts with the end of the tap being moved from point A to point B and then to point C at the rapid traverse rate. The tap is then fed to point D, reversed, and moved back to point C.

The G85 block for a boring cycle with tool retraction at the feed rate is:

N_____G85 X_____Y_____C_____D_____F_____EOB



In the G85 boring cycle, the tool is moved from point A to point B and then to point C at the rapid traverse rate. The tool is next fed to point D and then, while still rotating, is moved back to point C at the same feed rate.

The G86 block for a boring cycle with rapid traverse retraction is:

N_____G86 X_____Y_____C_____D_____F_____EOB



The G86 boring cycle is similar to the G85 cycle except that the tool is withdrawn at the rapid traverse rate.

Copyright 2004, Industrial Press, Inc., New York, NY

The G87 block for a boring cycle with manual withdrawal of the tool is:

N_____G87 X_____Y_____C_____D_____F_____EOB



In the G87 canned boring cycle, the cutting tool is moved from A to B and then to C at the rapid traverse rate. The tool is then fed to D. The cycle is identical to the other boring cycles except that the tool is withdrawn manually.

The G88 block for a boring cycle with dwell and manual withdrawal is:

N_____G88 X_____Y_____C_____D_____T_____F_____EOB



In the G88 dwell cycle, the tool is moved from A to B to C at the rapid traverse rate and then fed at the prescribed feed rate to D. The tool dwells at D, then stops rotating and is withdrawn manually.

The G89 block for a boring cycle with dwell and withdrawal at the feed rate is:

N_____G89 X_____Y_____C_____D_____T_____F_____EOB



Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 16.

Turning Cycles.— Canned turning cycles are available from most system builders and are designed to allow the programmer to describe a complete turning operation in one or a few blocks. There is no standard for this type of operation, so a wide variety of programs have developed. Fig. 16 shows a hypothetical sequence in which the cutter is moved from the start point to depth for the first pass. If incremental programming is in effect, this distance is specified as D1. The depths of the other cuts will also be programmed as D2, D3, and so on. The length of the cut will be set by the W-word, and will remain the same with each pass. The preparatory word that calls for the roughing cycle is G77. The roughing feed rate is 0.03 ipr (inch per revolution), and the finishing feed rate (last pass) is 0.005 ipr. The block appears as follows:

N0054 G77 W = 3.1 D1 = .4 D2 = .3 D3 = .3 D4 = .1 F1 = .03 F2 = .005

Thread Cutting.— Most NC lathes can produce a variety of thread types including constant-lead threads, variable-lead threads (increasing), variable-lead threads (decreasing), multiple threads, taper threads, threads running parallel to the spindle axis, threads (spiral groove) perpendicular to the spindle axis, and threads containing a combination of the preceding. Instead of the feed rate, the lead is specified in the threading instruction block, so that the feed rate is made consistent with, and dependent upon, the selected speed (rpm) of the spindle.

The thread lead is generally noted by either an I- or a K-word. The I-word is used if the thread is parallel to the *X*-axis and the K-word if the thread is parallel to the *Z*-axis, the latter being by far the most common. The G-word for a constant-lead thread is G33, for an increasing variable-lead thread is G34, and for a decreasing variable-lead thread is G35. Taper threads are obtained by noting the *X*- and *Z*-coordinates of the beginning and end points of the thread if the G90 code is in effect (absolute programming), or the incremental movement from the beginning point to the end point of the thread if the G91 code (incremental programming) is in effect.

N0001 G91	(Incremental programming)
N0002 G00 X–.1000	(Rapid traverse to depth)
N0003 G33 Z–1.0000 K.0625	(Produce a thread with a constant lead of 0.625 inch)
N0004 G00 X.1000	(Withdraw at rapid traverse)
N0005 Z1.0000	(Move back to start point)

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 17.



Fig. 18.

Multiple threads are specified by a code in the block that spaces the start of the threads equally around the cylinder being threaded. For example, if a triple thread is to be cut, the threads will start 120 degrees apart. Typical single-block thread cutting utilizing a plunge cut is illustrated in Fig. 17 and shows two passes. The passes areidentical except for the distance of the plunge cut. Builders of control systems and machine tools use different codewords for threading, but those shown below can be considered typical. For clarity, both zeros and decimal points are shown.

The only changes in the second pass are the depth of the plunge cut and the withdrawal. The blocks will appear as follows:

N0006 X – .1050
N0007 G33 Z – 1.0000 K.0625
N0008 G00 X.1050
N0009 Z1.000

Compound thread cutting, rather than straight plunge thread cutting, is possible also, and is usually used on harder materials. As illustrated in Fig. 18, the starting point for the thread is moved laterally in the -Z direction by an amount equal to the depth of the cut times the tangent of an angle that is slightly less than 30 degrees. The program for the second pass of the example shown in Fig. 18 is as follows:

N0006 X – .1050 Z – .0028
N0007 G33 Z – 1.0000 K.0625
N0008 G00 X.1050
N0009 Z1.0000

Fixed (canned), one-block cycles also have been developed for CNC systems to produce the passes needed to complete a thread. These cycles may be offered by the builder of the control system or machine tool as standard or optional features. Subroutines also can generally be prepared by the user to accomplish the same purpose (see Subroutine). A one-block fixed threading cycle might look something like:

N0048 G98 X – .2000 Z – 1.0000 D.0050 F.0010

where G98 = preparatory code for the threading cycle
X–.2000 = total distance from the starting point to the bottom of the thread
Z–1.0000 = length of the thread
D.0050 = depths of successive cuts
F.0010 = depth(s) of the finish cut(s)

APT Programming

APT.— APT stands for Automatically Programmed Tool and is one of many computer languages designed for use with NC machine tools. The selection of a computer-assisted part-programming language depends on the type and complexity of the parts being machined more than on any other factor. Although some of the other languages may be easier to use, APT has been chosen to be covered in this book because it is a nonproprietary

Copyright 2004, Industrial Press, Inc., New York, NY

language in the public domain, has the broadest range of capability, and is one of the most advanced and universally accepted NC programming languages available. APT (or a variation thereof) is also one of the languages that is output by many computer programs that produce CNC part programs directly from drawings produced with CAD systems.

APT is suitable for use in programming part geometry from simple to exceptionally complex shapes. APT was originally designed and used on mainframe computers, however, it is now available, in many forms, on mini- and microcomputers as well. APT has also been adopted as ANSI Standard X3.37and by the International Organization for Standardization (ISO) as a standardized language for NC programming. APT is a very dynamic program and is continually being updated. APT is being used as a processor for part-programming graphic systems, some of which have the capability of producing an APT program from a graphic screen display or CAD drawing and of producing a graphic display on the CAD system from an APT program.

APT is a high-level programming language. One difference between APT and the ANSI/EIA RS-274-D (G-codes) programming format discussed in the last section is that APT uses English like words and expressions to describe the motion of the tool or workpiece. APT has the capability of programming the machining of parts in up to five axes, and also allows computations and variables to be included in the programming statements so that a whole family of similar parts can be programmed easily. This section describes the general capabilities of the APT language and includes a ready reference guide to the basic geometry and motion statements of APT, which is suitable for use in programming the machining of the majority of cubic type parts involving two-dimensional movements. Some of the three-dimensional geometry capability of APT and a description of its five-dimensional capability are also included.



As shown above, the APT system can be thought of comprising the input program, the five sections 0 through IV, and the output program. The input program shown on the left progresses through the first four sections and all four are controlled by the fifth, section 0. Section IV, the postprocessor, is the software package that is added to sections II and III to customize the output and produce the necessary program format (including the G-words, M-words, etc.) so that the coded instructions will be recognizable by the control system. The postprocessor is software that is separate from the main body of the APT program, but for purposes of discussion, it may be easier to consider it as a unit within the APT program.

Copyright 2004, Industrial Press, Inc., New York, NY

APT Computational Statements.— Algebraic and trigonometric functions and computations can be performed with the APT system as follows:

Arithmetic Form	APT Form	Arithmetic Form	APT Form	Arithmetic Form	APT Form
25×25	25*25	25^2	25**2	$\cos\theta$	COSF(θ)
$25 \div 25$	25/25	25^n	25**n	$\tan\theta$	TANF(θ)
$25 + 25$	25 + 25	$\sqrt{25}$	SQRTF (25)	arctan .5000	ATANF(.5)
$25 - 25$	25 – 25	$\sin\theta$	SINF(θ)		

Computations may be used in the APT system in two ways. One way is to let a factor equal the computation and then substitute the factor in a statement; the other is to put the computation directly into the statement. The following is a series of APT statements illustrating the first approach.

```
P1 = POINT/0,0,1
 T = (25*2/3 + (3**2 – 1))
P2 = POINT/T,0,0
```

The second way would be as follows;

```
P1 = POINT/0,0,1
P2 = POINT/(25*2/3 + (3**2 – 1)),0,0
```

Note: The parentheses have been used as they would be in an algebraic formula so that the calculations will be carried out in proper sequence. The operations within the inner parentheses would be carried out first. It is important for the total number of left-hand parentheses to equal the total number of right-hand parentheses; otherwise, the program will fail.

APT Geometry Statements.— Before movements around the geometry of a part can be described, the geometry must be defined. For example, in the statement GOTO/P1, the computer must know where P1 is located before the statement can be effective. P1 therefore must be described in a geometry statement, prior to its use in the motion statement GOTO/P1. The simplest and most direct geometry statement for a point is

```
P1 = POINT/X ordinate, Y ordinate, Z ordinate
```

If the *Z* ordinate is zero and the point lies on the *X*–*Y* plane, the *Z* location need not be noted. There are other ways of defining the position of a point, such as at the intersection of two lines or where a line is tangent to a circular arc. These alternatives are described below, together with ways to define lines and circles. Referring to the preceding statement, P1 is known as a symbol. Any combination of letters and numbers may be used as a symbol providing the total does not exceed six characters and at least one of them is a letter. MOUSE2 would be an acceptable symbol, as would CAT3 or FRISBE. However, it is sensible to use symbols that help define the geometry. For example, C1 or CIR3 would be good symbols for a circle. A good symbol for a vertical line would be VL5.

Next, and after the equal sign, the particular geometry is noted. Here, it is a POINT. This word is a vocabulary word and must be spelled exactly as prescribed. Throughout, the designers of APT have tried to use words that are as close to English as possible. A slash follows the vocabulary word and is followed by a specific description of the particular geometry, such as the coordinates of the point P1. A usable statement for P1 might appear as P1 = POINT/1,5,4. The 1 would be the *X* ordinate; the 5, the *Y* ordinate; and the 4, the *Z* ordinate.

Lines as calculated by the computer are infinitely long, and circles consist of 360 degrees. As the cutter is moved about the geometry under control of the motion statements, the lengths of the lines and the amounts of the arcs are "cut" to their proper size. (Some of the geometry statements shown in the accompanying illustrations for defining POINTS, LINES, CIRCLES, TABULATED CYLINDERS, CYLINDERS, CONES, and SPHERES, in the APT language, may not be included in some two-dimensional [ADAPT] systems.)

Copyright 2004, Industrial Press, Inc., New York, NY

Points

Point in space



P1 = POINT/4, 5, 2
P2 = POINT/2, 2

Intersection of two lines



P3 = POINT/INTOF, L1, L2

Intersection of line and circle
(two possibilities)



P1 = POINT/XLARGE, INTOF, L1, C1
or
P1 = POINT/YLARGE, INTOF, L1, C1
P2 = POINT/XSMALL, INTOF, L1, C1
or
P2 = POINT/YSMALL, INTOF, L1, C1

The *X* and *Y* ordinates of P1 are larger than the *X* and *Y* ordinates of P2

Intersection of two circles
(two possibilities)



P1 = POINT/XSMALL, INTOF, C1, C2
or
P1 = POINT/YLARGE, INTOF, C1, C2
P2 = POINT/XLARGE, INTOF, C1, C2
or
P2 = POINT/YSMALL, INTOF, C1, C2

Intersection of a radial
line and a circle



P1 = POINT/C1, ATANGL, 20

Center of a circle



P1 = POINT/CENTER, C1

Copyright 2004, Industrial Press, Inc., New York, NY

Lines

Through two points



L1 = LINE/P1, P2

The coordinates of two points



L1 = LINE/5, 7, 10, 4

Through a point and parallel to another line



L1 = LINE/P1, PARLEL, L2

Through a point and perpendicular to another line



L1 = LINE/P1, PERPTO, L2

A parallel line and a perpendicular distance



L1 = LINE/PARLEL, L2, XSMALL, 3.50
or
L1 = LINE/PARLEL, L2, YLARGE, 3.50
L2 = LINE/PARLEL, L1, XLARGE, 3.50
or
L2 = LINE/PARLEL, L1, YSMALL, 3.50

Through a point and at an angle with X-axis



L1 = LINE/P1, ATANGL, 30

Copyright 2004, Industrial Press, Inc., New York, NY

Lines *(Continued)*

Through a point and at an angle with another line



L2 = LINE/P1, ATANGL, 35.5, L1

By an angle with the X-axis and the intercept with the X-axis or the Y-axis



L1 = LINE/ATANGL, 20, INTERC, XAXIS, 5
L1 = LINE/ATANGL, 20, INTERC, YAXIS, 2

Through a point and tangent to a circle. Looking from the point towards the circle (two possibilities)



L1 = LINE/P1, LEFT, TANTO, C1
L2 = LINE/P1, RIGHT, TANTO, C1

Tangent to two circles. Looking from the first circle noted in the statement towards the second circle noted (four possibilities)



L1 = LINE/RIGHT, TANTO, C2, LEFT, TANTO, C1
or
L1 = LINE/RIGHT, TANTO, C1, LEFT, TANTO, C2
L2 = LINE/LEFT, TANTO, C1, LEFT, TANTO, C2
or
L2 = LINE/RIGHT, TANTO, C2, RIGHT, TANTO, C1
L3 = LINE/RIGHT, TANTO, C1, RIGHT, TANTO, C2
or
L3 = LINE/LEFT, TANTO, C2, LEFT, TANTO, C1
L4 = LINE/LEFT, TANTO, C2, RIGHT, TANTO, C1
or
L4 = LINE/LEFT, TANTO, C1, RIGHT, TANTO, C2

Through a point and tangent or perpendicular to a tabulated cylinder



L1 = LINE/P1, TANTO, TAB1, P3
L1 = LINE/P1, PERPTO, TAB1, P3

P2 and P3 are points close to the tangent points of L1 and the intersection point of L2, therefore cannot be end points of the tabulated cylinder

Copyright 2004, Industrial Press, Inc., New York, NY

Circles

The center of the circle and the radius



C1 = CIRCLE/5, 6, 2
or
C1 = CIRCLE/5, 6, 0, 2
(where 0 = Z ordinate)
or
C1 = CIRCLE/CENTER, P1, RADIUS, 2

The center of a circle and a tangent line



C1 = CIRCLE/CENTER, P1, TANTO, L1

The center of a circle and a point on the circumference



C1 = CIRCLE/CENTER, P1, P2

Three points on a circle



C1 = CIRCLE/P1, P2, P3

The center and a tangent circle (two possibilities)



C1 = CIRCLE/CENTER, P1, SMALL, TANTO, C2
or
C3 = CIRCLE/CENTER, P1, LARGE, TANTO, C2

The center and a tangent circle (two possibilities)



C1 = CIRCLE/CENTER, P1, SMALL, TANTO, C2
or
C3 = CIRCLE/CENTER, LARGE, TANTO, C2

Copyright 2004, Industrial Press, Inc., New York, NY

Circles

Tangent to two intersecting lines, given the radius (four possibilities)



C1 = CIRCLE/XLARGE, L2, YSMALL, L1, RADIUS, .75
or
C2 = CIRCLE/XLARGE, L2, YLARGE, L1, RADIUS, .75
or
C3 = CIRCLE/XSMALL, L2, YLARGE, L1, RADIUS, .75
or
C4 = CIRCLE/XSMALL, L2, YSMALL, L1, RADIUS, .75

The modifiers (XLARGE, etc.) are used to indicate which of the four circles is wanted.

Tangent to a line and a point on the circumference, given the radius (two possibilities)



C1 = CIRCLE/TANTO, L1, XSMALL, P1, RADIUS, .5
or
C2 = CIRCLE/TANTO, L1, XLARGE, P1, RADIUS, .5
if the point lies on the line, then:
C3 = CIRCLE/TANTO, L1, YLARGE, P2, RADIUS, .5
or
C4 = CIRCLE/TANTO, L1, YSMALL, P2, RADIUS, .5

APT Motion Statements.— APT is based on the concept that a milling cutter is guided by two surfaces when in a contouring mode. Examples of these surfaces are shown in Fig. 1, and they are called the "part" and the "drive" surfaces. Usually, the partsurface guides the bottom of the cutter and the drive surface guides the side of the cutter. These surfaces may or may not be actual surfaces on the part, and although they may be imaginary to the part programmer, they are very real to the computer. The cutter is either stopped or redirected by a third surface called a check surface. If one were to look directly down on these surfaces, they would appear as lines, as shown in Figs. 2a through 2c.



Fig. 1. Contouring Mode Surfaces

When the cutter is moving toward the check surface, it may move to it, onto it, or past it, as illustrated in Fig. 2a. When the cutter meets the check surface, it may go right, denoted by the APT command GORGT, or go left, denoted by the command GOLFT, in Fig. 2b.

Copyright 2004, Industrial Press, Inc., New York, NY

Alternatively, the cutter may go forward, instructed by the command GOFWD, as in Fig. 2c. The command GOFWD is used when the cutter is moving either onto or off a tangent circular arc. These code instructions are part of what are called motion commands. Fig. 3 shows a cutter moving along a drive surface, L1, toward a check surface, L2. When it arrives at L2, the cutter will make a right turn and move along L2 and past the new check surface L3. Note that L2 changes from a check surface to a drive surface the moment the cutter begins to move along it. The APT motion statement for this move is:

GORGT/L2,PAST,L3

Contouring Cutter Movements



Fig. 2a.



Fig. 2b.



Fig. 2c.



Fig. 3. Motion Statements for Movements Around a Workpiece

Still referring to Fig. 3, the cutter moves along L3 until it comes to L4. L3 now becomes the drive surface and L4 the check surface. The APT statement is:

GORGT/L3,TO,L4

The next statement is:

GOLFT/L4,TANTO,C1

Even though the cutter is moving to the right, it makes a left turn if one is looking in the direction of travel of the cutter. In writing the motion statements, the part programmers must imagine they are steering the cutter. The drive surface now becomes L4 and the check surface, C1. The next statement will therefore be:

GOFWD/C1,TANTO,L5

This movement could continue indefinitely, with the cutter being guided by the drive, part, and check surfaces.

Start-Up Statements: For the cutter to move along them, it must first be brought into contact with the three guiding surfaces by means of a start-up statement. There are three different start-up statements, depending on how many surfaces are involved.

A three-surface start-up statement is one in which the cutter is moved to the drive, part, and check surfaces, as seen in Fig. 4a. A two-surface start-up is one in which the cutter is

Copyright 2004, Industrial Press, Inc., New York, NY

moved to the drive and part surfaces, as in Fig. 4b. A one-surface start-up is one in which the cutter is moved to the drive surface and the *X*–*Y* plane, where *Z* = 0, as in Fig. 4c. With the two- and one-surface start-up statements, the cutter moves in the most direct path, or perpendicular to the surfaces. Referring to Fig. 4a(three-surface start-up), the move is initiated from a point P1. The two statements that will move the cutter from P1 to the three surfaces are:

FROM/P1
GO/TO,DS,TO,PS,TO,CS

Circles

Tangent to a line and a circle, given the radius (eight possibilities)



C1 = CIRCLE/YSMALL, L1, XLARGE, OUT, C12, RADIUS, .5
C2 = CIRCLE/YLARGE, L1, XLARGE, OUT, C12, RADIUS, .5
C3 = CIRCLE/YLARGE, L1, XLARGE, IN, C12, RADIUS, .5
C4 = CIRCLE/YSMALL, L1, XLARGE, IN, C12, RADIUS, .5
C5 = CIRCLE/YLARGE, L1, XSMALL, OUT, C12, RADIUS, .5
C6 = CIRCLE/XLARGE, L1, XSMALL, OUT, C12, RADIUS, .5
C7 = CIRCLE/YSMALL, L1, XSMALL, OUT, C12, RADIUS, .5
C8 = CIRCLE/YSMALL, L1, XSMALL, IN, C12, RADIUS, .5

Recommendations:
1. Note which side of line circle is on (e.g., YSMALL, L1).
2. Note whether the circle being defined is inside (IN), or outside (OUT), the known circle.
3. Of the two remaining circles, note whether the circle to be defined is XLARGE, XSMALL, or YLARGE or YSMALL, to arrive at the second modifier in the statement.

Tangent to two circles, given the radius (eight possibilities)



C1 = CIRCLE/YSMALL, OUT, C10, OUT, C11, RADIUS, .75
C2 = CIRCLE/YSMALL, OUT, C10, IN, C11, RADIUS, .75
C3 = CIRCLE/YSMALL, IN, C10, IN, C11, RADIUS, .75
C4 = CIRCLE/YSMALL, IN, C10, OUT, C11, RADIUS, .75
C5 = CIRCLE/YLARGE, IN, C10, IN, C11, RADIUS, .75
C6 = CIRCLE/YLARGE, OUT, C10, IN, C11, RADIUS, .75
C7 = CIRCLE/YLARGE, OUT, C10, OUT, C11, RADIUS, .75
C8 = CIRCLE/YLARGE, IN, C10, OUT, C11, RADIUS, .75

Recommendations
1. Apply IN, OUT modifiers.
2. Apply XLARGE, etc., modifiers.

Copyright 2004, Industrial Press, Inc., New York, NY

DS is used as the symbol for the Drive Surface; PS as the symbol for the Part Surface; and CS as the symbol for the Check Surface. The surfaces must be denoted in this sequence. The drive surface is the surface that the cutter will move along after coming in contact with the three surfaces. The two statements applicable to the two-surface start-up (Fig. 4b) are:

```
FROM/P1
GO/TO,DS,TO,PS
```

The one-surface start-up (Fig. 4c) is:

```
FROM/P1
GO/TO,DS
```

Planes



Planes are often used as the part surface, and are defined by three points not lying in a straight line

PL1 = PLANE/P1, P2, P3



A plane that is horizontal, or parallel to the *X-Y* plane, may be defined as:

PL1 = PLANE/0, 0, 1, 5 (0, 0, 1 does not change)

Alternatively, PL2 may be defined as a plane parallel to PL1

PL2 = PLANE/PARLEL, PL1, ZLARGE, 10

Cutter Movement Surfaces



Fig. 4a.



Fig. 4b.



Fig. 4c.

Copyright 2004, Industrial Press, Inc., New York, NY

Tabulated Cylinder



A tabulated cylinder is the line that is formed when an irregular cylinder intersects a plane. The plane intersected in the figure at the left is the *X*–*Y* plane.

A section of the line can be defined by a series of points on the line, as seen at the right. This line is called a TABCYL. The line must pass through all the points, therefore, it is best not to use too many. The statement to the computer would read:

TAB1 = TABCYL/NOZ, SPLINE, P1, P2, P3, P4, P5, P6

or

TAB1 = TABCYL/NOZ, SPLINE, X., Y., X2, Y2, X3, Y3, X4, Y4, X5, Y5, X6, Y6
(where *X* and *Y* are the coordinates of the points)

3-D Geometry

Cylinder



Length of vector = 1

A cylinder is defined by a vector, a point on the centerline, and the radius

CL1 = CYLNDR/P1, V2, 1.5

where V2 is a unit vector in line with the cylinder centerline, and is described by the *X*, *Y*, and *Z* components. The cylinder centerline lies on the *X*–*Y* plane and is parallel to the *Y*-axis. The statement for the vector is therefore:

V2 = VECTOR/*X* component, *Y* component, *Z* component

V2 = VECTOR/0, 1, 0

Cone



A cone is defined by its vertex, its axis as a unit vector, and the half angle (refer to cylinder for an example of a vector statement)

CON1 = CONE/P1,V1,45

Sphere



A sphere is defined by the center and the radius

SP1 = SPHERE/P1, RADIUS, 2.5

or

SP1 = SPHERE/5, 5, 3, 2.5 (where 5, 5, and 3 are the *X*, *Y*, and *Z* coordinates or P1, and 2.5 is the radius)

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. A Completed Two-Surface Start-Up

Note that, in all three motion statements, the slash mark (/) lies between the GO and the TO. When the cutter is moving to a point rather than to surfaces, such as in a start-up, the statement is GOTO/ rather than GO/TO. A two-surface start-up, Fig. 3, when completed, might appear as shown in Fig. 5, which includes the motion statements needed. The motion statements, as they would appear in a part program, are shown at the left, below:

FROM/P1	FROM/P1
GO/TO,L1,TO,PS	GOTO/P2
GORGT/L1,TO,L2	GOTO/P3
GORGT/L2,PAST,L3	GOTO/P4
GORGT/L3,TO,L4	GOTO/P5
GOLFT/L4,TANTO,C1	GOTO/P6
GOFWD/C1,TANTO,L5	GOTO/P7
GOFWD/L5,PAST,L1	
GOTO/P2	

GOTO statements can move the cutter throughout the range of the machine, as shown in Fig. 6. APT statements for such movements are shown at the right in the preceding example. The cutter may also be moved incrementally, as shown in Fig. 7. Here, the cutter is to move 2 inches in the + *X* direction, 1 inch in the + *Y* direction, and 1.5 inches in the + *Z* direction. The incremental move statement (indicated by DLTA) is:

GODLTA/2,1,1.5

The first position after the slash is the *X* movement; the second the *Y* movement, and the third, the *Z* movement.

Five-Axis Machining: Machining on five axes is achieved by causing the APT program to generate automatically a unit vector that is normal to the surface being machined, as shown in Fig. 8. The vector would be described by its *X*, *Y*, and *Z* components. These components, along with the *X*, *Y*, and *Z* coordinate positions of the tool tip, are fed into the postprocessor, which determines the locations and angles for the machine tool head and/or table.

APT Postprocessor Statements.— Statements that refer to the operation of the machine rather than to the geometry of the part or the motion of the cutter about the part are called postprocessor statements. APT postprocessor statements have been standardized internationally. Some common statements and an explanation of their meaning follow:

Copyright 2004, Industrial Press, Inc., New York, NY

MACHIN/ Specifies the postprocessor that is to be used. Every postprocessor has an identity code, and this code must follow the slash mark (/). For example: MACHIN/LATH,82

FEDRATE/ Denotes the feed rate. If in inches per minute (ipm), only the number



Fig. 6. A Series of GOTO Statements



Fig. 7. Incremental Cutter Movements



Fig. 8. Five-Axis Machining

need be shown. If in inches per revolution (ipr), IPR must be shown, for example: FEDRAT/.005,IPR

RAPID Means rapid traverse and applies only to the statement that immediately follows it

SPINDL/ Refers to spindle speed. If in revolutions per minute (rpm), only the number need be shown. If in surface feet per minute (sfm), the letters SFM need to be shown, for example: SPINDL/ 100SFM

COOLNT/ Means cutting fluid and can be subdivided into: COOLNT/ON, COOLNT/MIST, COOLNT/FLOOD, COOLNT/OFF

TURRET/ Used to call for a selected tool or turret position

CYCLE/ Specifies a cycle operation such as a drilling or boring cycle. An example of a drilling cycle is: CYCLE/DRILL,RAPTO,.45,FEDTO,0,IPR,.004. The next statement might be GOTO/PI and the drill will then move to P1 and perform the cycle operation. The cycle will repeat until the CYCLE/OFF statement is read

Copyright 2004, Industrial Press, Inc., New York, NY

END Stops the machine but does not turn off the control system



Fig. 9. Symbols for Geometrical Elements

APT Example Program.— A dimensioned drawing of a part and a drawing with the symbols for the geometry elements are shown in Fig. 9. A complete APT program for this part, starting with the statement PARTNO 47F36542 and ending with FINI, is shown at the left below.

The numbers at the left of the statements are for reference purposes only, and are not part of the program. The cutter is set initially at a point represented by the symbol SP, having coordinates $X = -0.5$, $Y = -0.5$, $Z = 0.75$, and moves to L1 (extended) with a one-surface start-up so that the bottom of the cutter rests on the X–Y plane. The cutter then moves counterclockwise around the part, past L1 (extended), and returns to SP. The coordinates of P1 are $X = 0$, $Y = 0$, and $Z = 1$.

```
(1)  PARTNO
(2)  CUTTER/.25
(3)  FEDRAT/5
(4)  SP = POINT/–.5, –.5, .75
(5)  P1 = POINT/0, 0, 1
(6)  L1 = LINE/P1, ATANGL, 0
(7)  C1 = CIRCLE/(1.700 + 1.250),
     .250, .250
(8)  C2 = CIRCLE/1.700, 1.950, .5
(9)  L2 = LINE/RIGHT, TANTO, C1,
     RIGHT, TANTO, C2
(10) L3 = LINE/P1, LEFT, TANTO, C2
(11) FROM/SP
(12) GO/TO, L1
(13) GORGT/L1, TANTO, C1
(14) GOFWD/C1, TANTO, L2
(15) GOFWD/L2, TANTO, C2
(16) GOFWD/C2, TANTO, L3
(17) GOFWD/L3, PAST, L1
(18) GOTO/SP
```

```
(1)  PARTNO
(2)  CUTTER/.25
(3)  FEDRAT/5
(4)  SP = POINT/–.5, –.5, .75
(5)  P1 = POINT/0, 0, 1
(6)  L1 = LINE/P1, ATANGL, 0
(7)  C1 = CIRCLE/(1.700 + 1.250), .250, .250
(8)  C2 = CIRCLE/1.700, 1.950, .5
(9)  L2 = LINE/RIGHT, TANTO, C1, RIGHT,
     TANTO, C2
(10) L3 = LINE/P1, LEFT, TANTO, C2
(11) FROM/SP
(12) FRO    –.500      –.5000      .7500
     M
(13) GO/TO/, L1
(14) GT     –.5000     –.1250      .0000
(15) GORGT/L1, TANTO, C1
(16) GT     2.9500     –.1250      .0000
(17) GOFWD/C1, TANTO, L2
(18) CIR    2.9500     .2500       .3750 CCLW
```

Copyright 2004, Industrial Press, Inc., New York, NY

```
(19) FINI                    (19)        3.2763      .4348        .0000
                             (20) GOFWD/L2, TANTO, C2
                             (21) GT     2.2439      2.2580       .0000
                             (22) GOFWD/C2, TANTO, L3
                             (23) CIR    1.700       1.9500   .6250 CCLW
                             (24)        1.1584      2.2619       .0000
                             (25) GOFWD/L3, PAST, L1
                             (26) GT     –.2162      –.1250       .0000
                             (27) GOTO/SP
                             (28) GT     –.5000      –.5000       .7500
                             (29) FINI
```

Referring to the numbers at the left of the program:

(1) PARTNO must begin every program. Any identification can follow.

(2) The diameter of the cutter is specified. Here it is 0.25 inch.

(3) The feed rate is given as 5 inches per minute, which is contained in a postprocessor statement.

(4)–(10) Geometry statements.

(11)–(18) Motion statements.

(19) All APT programs end with FINI.

A computer printout from section II of the APT program is shown at the right, above. This program was run on a desktop personal computer. Lines (1) through (10) repeat the geometry statements from the original program. The motion statements are also repeated, and below each motion statement are shown the *X*, *Y*, and *Z* coordinates of the end points of the center-line (CL) movements for the cutter. Two lines of data follow those for the circular movements. For example, Line (18), which follows Line (17), GOFWD/C1,TANTO,L2, describes the *X* coordinate of the center of the arc, 2.9500, the *Y* coordinate of the center of the arc, 0.2500, and the radius of the arc required to be traversed by the cutter.

This radius is that of the arc shown on the part print, plus the radius of the cutter (0.2500 + 0.1250 = 0.3750). Line (18) also shows that the cutter is traveling in a counterclockwise (CCLW) motion. A circular motion is described in Lines (22), (23), and (24). Finally, the cutter is directed to return to the starting point, SP, and this command is noted in Line (27). The *X*, *Y*, and *Z* coordinates of SP are shown in Line (28).

APT for Turning.— In its basic form, APT is not a good program for turning. Although APT is probably the most suitable program for three-, four-, and five-axis machining, it is awkward for the simple two-axis geometry required for lathe operations. To overcome this problem, preprocessors have been developed especially for lathe part programming. The statements in the lathe program are automatically converted to basic APT statements in the computer and processed by the regular APT processor. An example of a lathe program, based on the APT processor and made available by the McDonnell Douglas Automation Co., is shown below. The numbers in parentheses are not part of the program, but are used only for reference. Fig. 10 shows the general set-up for the part, and Fig. 11 shows an enlarged view of the part profile with dimensions expressed along what would be the *X*- and *Y*-axes on the part print.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 10. Setup for APT Turning



Fig. 11.

```
(1)   PARTNO LATHE EXAMPLE
(2)   MACHIN/MODEL LATHE
(3)         T1 =  TOOL/FACE, 1, XOFF, –1, YOFF, –6, RADIUS, .031
(4)  BLANK1 =  SHAPE/FACE, 3.5, TURN, 2
(5)    PART1 =  SHAPE/FACE, 3.5, TAPER, 3.5, .5, ATANGL, – 45, TURN, 1,$
                FILLET, .25 FACE, 1.5 TURN, 2
(6)             FROM/(20–1), (15–6)
(7)             LATHE/ROUGH, BLANK1, PART1, STEP, .1, STOCK, .05,$
                SFM, 300, IPR, .01, T1
(8)             LATHE/FINISH, PART1, SFM, 400, IPR, .005, T1
(9)             END
(10)            FINI
```

Copyright 2004, Industrial Press, Inc., New York, NY

Line (3) describes the tool. Here, the tool is located on face 1 of the turret and its tip is –1 inch "off" (offset) in the *X* direction and –6 inches "off" in the *Y* direction, when considering *X*–*Y* rather than *X*–*Z* axes. The cutting tool tip radius is also noted in this statement. Line (4) describes the dimensions of the rough material, or blank. Lines parallel to the *X*-axis are noted as FACE lines, and lines parallel to the *Z*-axis are noted as TURN lines. The FACE line (LN1) is located 3.5 inches along the *Z*-axis and parallel to the *X*-axis. The TURN line (LN2) is located 2 inches above the *Z*-axis and parallel to it. Note that in Figs. 10 and 11, the *X*-axis is shown in a vertical position and the *Z*-axis in a horizontal position. Line (5) describes the shape of the finished part. The term FILLET is used in this statement to describe a circle that is tangent to the line described by TURN, 1 and the line that is described by FACE, 1.5. The $ sign means that the statement is continued on the next line. These geometry elements must be contiguous and must be described in sequence. Line (6) specifies the position of the tool tip at the start of the operation, relative to the point of origin. Line (7) describes the roughing operation and notes that the material to be roughed out lies between BLANK1 and PART1; that the STEP, or depth of roughing cuts, is to be 0.1 inch; that 0.05 inch is to be left for the finish cut; that the speed is to be 300 sfm and the feed rate is to be 0.01 ipr; and that the tool to be used is identified by the symbol T1. Line (8) describes the finish cut, which is to be along the contour described by PART1.

Indexable Insert Holders for NC.— Indexable insert holders for numerical control lathes are usually made to more precise standards than ordinary holders. Where applicable, reference should be made to American National Standard B212.3-1986, Precision Holders for Indexable Inserts. This standard covers the dimensional specifications, styles, and designations of precision holders for indexable inserts, which are defined as tool holders that locate the gage insert (a combination of shim and insert thicknesses) from the back or front and end surfaces to a specified dimension with a ±0.003 inch (±0.08 mm) tolerance. In NC programming, the programmed path is that followed by the center of the tool tip, which is the center of the point, or nose radius, of the insert. The surfaces produced are the result of the path of the nose and the major cutting edge, so it is necessary to compensate for the nose or point radius and the lead angle when writing the program. Table 1, from B212.3, gives the compensating dimensions for different holder styles. The reference point is determined by the intersection of extensions from the major and minor cutting edges, which would be the location of the point of a sharp pointed tool. The distances from this point to the nose radius are *L*1 and *D*1; *L*2 and *D*2 are the distances from the sharp point to the center of the nose radius. Threading tools have sharp corners and do not require a radius compensation. Other dimensions of importance in programming threading tools are also given in Table 2; the data were developed by Kennametal, Inc.

The *C* and *F* characters are tool holder dimensions other than the shank size. In all instances, the *C* dimension is parallel to the length of the shank and the *F* dimension is parallel to the side dimension; actual dimensions must be obtained from the manufacturer. For all *K* style holders, the *C* dimension is the distance from the end of the shank to the tangent point of the nose radius and the end cutting edge of the insert. For all other holders, the *C* dimension is from the end of the shank to a tangent to the nose radius of the insert. The *F* dimension on all B, D, E, M, P, and V style holders is measured from the back side of the shank to the tangent point of the nose radius and the side cutting edge of the insert. For all A, F, G, J, K, and L style holders, the *F* dimension is the distance from the back side of the shank to the tangent of the nose radius of the insert. In all these designs, the nose radius is the standard radius corresponding to those given in the paragraph *Cutting Point Configuration* on page 758.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Insert Radius Compensation *ANSI B212.3-1986*

Square Profile						
B Style[a] Also applies to R Style		Turning 15° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0035	.0191	.0009	.0110
		1/32	.0070	.0383	.0019	.0221
		3/64	.0105	.0574	.0028	.0331
		1/16	.0140	.0765	.0038	.0442
D Style[a] Also applies to S Style		Turning 45° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0065	.0221	.0065	0
		1/32	.0129	.0442	.0129	0
		3/64	.0194	.0663	.0194	0
		1/16	.0259	.0884	.0259	0
K Style[a]		Facing 15° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0009	.0110	.0035	.0191
		1/32	.0019	.0221	.0070	.0383
		3/64	.0028	.0331	.0105	.0574
		1/16	.0038	.0442	.0140	.0765
Triangle Profile						
G Style[a]		Turning 0° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0114	.0271	0	.0156
		1/32	.0229	.0541	0	.0312
		3/64	.0343	.0812	0	.0469
		1/16	.0458	.1082	0	.0625
B Style[a] Also applies to R Style		Turning and Facing 15° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0146	.0302	.0039	.0081
		1/32	.0291	.0604	.0078	.0162
		3/64	.0437	.0906	.0117	.0243
		1/16	.0582	.1207	.0156	.0324
F Style[a]		Facing 90° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	0	.0156	.0114	.0271
		1/32	0	.0312	.0229	.0541
		3/64	0	.0469	.0343	.0812
		1/16	0	.0625	.0458	.1082

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Insert Radius Compensation** *ANSI B212.3-1986*

Triangle Profile *(continued)*						
		Turning & Facing 3° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
J Style[a]		1/64	.0106	.0262	.0014	.0170
		1/32	.0212	.0524	.0028	.0340
		3/64	.0318	.0786	.0042	.0511
		1/16	.0423	.1048	.0056	.0681
80° Diamond Profile						
		Turning & Facing 0° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
G Style[a]		1/64	.0030	.0186	0	.0156
		1/32	.0060	.0312	0	.0312
		3/64	.0090	.0559	0	.0469
		1/16	.0120	.0745	0	.0625
		Turning & Facing 5° Reverse Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
L Style[a]		1/64	.0016	.0172	.0016	.0172
		1/32	.0031	.0344	.0031	.0344
		3/64	.0047	.0516	.0047	.0516
		1/16	.0062	.0688	.0062	.0688
		Facing 0° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
F Style[a]		1/64	0	.0156	.0030	.0186
		1/32	0	.0312	.0060	.0372
		3/64	0	.0469	.0090	.0559
		1/16	0	.0625	.0120	.0745
		Turning 15° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
R Style[a]		1/64	.0011	.0167	.0003	.0117
		1/32	.0022	.0384	.0006	.0234
		3/64	.0032	.0501	.0009	.0351
		1/16	.0043	.0668	.0012	.0468
		Facing 15° Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
K Style[a]		1/64	.0003	.0117	.0011	.0167
		1/32	.0006	.0234	.0022	.0334
		3/64	.0009	.0351	.0032	.0501
		1/16	.0012	.0468	.0043	.0668

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Insert Radius Compensation** *ANSI B212.3-1986*

55° Profile						
J Style[a]		Profiling 3° Reverse Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0135	.0292	.0015	.0172
		1/32	.0271	.0583	.0031	.0343
		3/64	.0406	.0875	.0046	.0519
		1/16	.0541	.1166	.0062	.0687
35° Profile						
J Style[a] Negative rake holders have 6° back rake and 6° side rake		Profiling 3° Reverse Lead Angle				
		Rad.	*L*-1	*L*-2	*D*-1	*D*-2
		1/64	.0330	.0487	.0026	.0182
		1/32	.0661	.0973	.0051	.0364
		3/64	.0991	.1460	.0077	.0546
		1/16	.1322	.1947	.0103	.0728
L Style[a]		Profiling 5° Lead Angle				
		Rad.	*L*-1	*L* -2	*D*-1	*D*-2
		1/64	.0324	.0480	.0042	.0198
		1/32	.0648	.0360	.0086	.0398
		3/64	.0971	.1440	.0128	.0597
		1/16	.1205	.1920	.0170	.0795

[a] *L*-1 and *D*-1 over sharp point to nose radius; and *L*-2 and *D*-2 over sharp point to center of nose radius. The *D*-1 dimension for the *B*, *E*, *D*, *M*, *P*, *S*, *T*, and *V* style tools are over the sharp point of insert to a sharp point at the intersection of a line on the lead angle on the cutting edge of the insert and the *C* dimension. The *L*-1 dimensions on *K* style tools are over the sharp point of insert to sharp point intersection of lead angle and *F* dimensions.

All dimensions are in inches.

Table 2. Threading Tool Insert Radius Compensation for NC Programming

Threading						
Insert Size	T	R	U	Y	X	Z
2	5/32 Wide	.040	.075	.040	.024	.140
3	3/16 Wide	.046	.098	.054	.031	.183
4	1/4 Wide	.053	.128	.054	.049	.239
5	3/8 Wide	.099	.190	…	…	…



All dimensions are given in inches. Courtesy of Kennametal, Inc.

Copyright 2004, Industrial Press, Inc., New York, NY

V-Flange Tool Shanks and Retention Knobs.— Dimensions of ANSI B5.18-1972 (R1998) standard tool shanks and corresponding spindle noses are detailed on pages 940 through 944, and are suitable for spindles used in milling and associated machines. Corresponding equipment for higher-precision numerically controlled machines, using retention knobs instead of drawbars, is usually made to the ANSI/ASME B5.50-1985 standard.

Essential Dimensions of V-Flange Tool Shanks *ANSI/ASME B5.50-1985*



	A	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*J*	*K*
	Tolerance	±0.005	±0.010	Min.	+0.015 −0.000	UNC 2B	±0.010	±0.002	+0.000 −0.015	+0.000 −0.015
Size	Gage Dia.									
30	1.250	1.875	0.188	1.00	0.516	0.500-13	1.531	1.812	0.735	0.640
40	1.750	2.687	0.188	1.12	0.641	0.625-11	2.219	2.500	0.985	0.890
45	2.250	3.250	0.188	1.50	0.766	0.750-10	2.969	3.250	1.235	1.140
50	2.750	4.000	0.250	1.75	1.031	1.000-8	3.594	3.875	1.485	1.390
60	4.250	6.375	0.312	2.25	1.281	1.250-7	5.219	5.500	2.235	2.140

	A	*L*	*M*	*N*	*P*	*R*	*S*	*T*	*Z*
	Tolerance	±0.001	±0.005	+0.000 −0.015	Min.	±0.002	±0.010	Min. Flat	+0.000 −0.005
Size	Gage Dia.								
30	1.250	0.645	1.250	0.030	1.38	2.176	0.590	0.650	1.250
40	1.750	0.645	1.750	0.060	1.38	2.863	0.720	0.860	1.750
45	2.250	0.770	2.250	0.090	1.38	3.613	0.850	1.090	2.250
50	2.750	1.020	2.750	0.090	1.38	4.238	1.125	1.380	2.750
60	4.250	1.020	4.250	0.120 0.200	1.500	5.683	1.375	2.04	4.250

Notes: Taper tolerance to be 0.001 in. in 12 in. applied in direction that increases rate of taper. Geometric dimensions symbols are to ANSI Y14.5M-1982. Dimensions are in inches. Deburr all sharp edges. Unspecified fillets and radii to be $0.03 \pm 0.010R$, or $0.03 \pm 0.010 \times 45$ degrees. Data for size 60 are not part of Standard. For all sizes, the values for dimensions *U* (tol. ± 0.005) are 0.579: for *V* (tol. ± 0.010), 0.440; for *W* (tol. ± 0.002), 0.625; for *X* (tol. ± 0.005), 0.151; and for *Y* (tol. ± 0.002), 0.750.

Copyright 2004, Industrial Press, Inc., New York, NY

Essential Dimensions of V-Flange Tool Shank Retention Knobs
ANSI/ASME B5.50-1985



Size	A	B	C	D	E	F
30	0.500-13	0.520	0.385	1.10	0.460	0.320
40	0.625-11	0.740	0.490	1.50	0.640	0.440
45	0.750-10	0.940	0.605	1.80	0.820	0.580
50	1.000-8	1.140	0.820	2.30	1.000	0.700
60	1.250-7	1.460	1.045	3.20	1.500	1.080
Tolerances	UNC- 2A	±0.005	±0.005	±0.040	±0.005	±0.005

Size	G	H	J	K	L	M	R
30	0.04	0.10	0.187	0.65 0.64	0.53	0.19	0.094
40	0.06	0.12	0.281	0.94 0.92	0.75	0.22	0.094
45	0.08	0.16	0.375	1.20 1.18	1.00	0.22	0.094
50	0.10	0.20	0.468	1.44 1.42	1.25	0.25	0.125
60	0.14	0.30	0.500	2.14 2.06	1.50	0.31	0.125
Tolerances	±0.010	±0.010	±0.010		+0.000 −0.010	±0.040	+0.010 −0.005

Notes: Dimensions are in inches. Material: low-carbon steel. Heat treatment: carburize and harden to 0.016 to 0.028 in. effective case depth. Hardness of noted surfaces to be Rockwell 56-60; core hardness Rockwell C35-45. Hole *J* shall not be carburized. Surfaces *C* and *R* to be free from tool marks. Deburr all sharp edges. Geometric dimension symbols are to ANSI Y14.5M-1982.

Data for size 60 are not part of Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

CAD/CAM

CAD/CAM.— CAD in engineering means computer-aided design using a computer graphics system to develop mechanical, electrical/electronic, and architectural designs. A second D (CADD) is sometimes added (computer-aided drafting and design) and simply indicates a mechanical drafting or drawing program. CAD technology is the foundation for a wide variety of engineering, design, drafting, analysis, and manufacturing activities. Often a set of drawings initially developed in the design phase of a project is also used for analyzing and optimizing the design, creating mechanical drawings of parts and assemblies and for generating NC/CNC part programs that control machining operations. Formerly, after a component had been designed with CAD, the design was passed to a part programmer who developed a program for machining the components, either manually or directly on the computer (graphic) screen, but the process often required redefining and reentering part geometry. This procedure is often regarded as the CAM part of CAD/CAM, although CAM (for computer-aided manufacturing) has a much broader meaning and involves the computer in many other manufacturing activities such as factory simulation and planning analyses. Improvements in the speed and capability of computers, operating systems, and programs (including, but not limited to CAD) have simplified the process of integrating the manufacturing process and passing drawings (revised, modified, and translated, as necessary) through the design, analysis, simulation, and manufacturing stages.

A CAD drawing is a graphic representation of part geometry data stored in a drawing database file. The drawing database generally contains the complete list of entity (line, arc, etc.) and coordinate information required to build the CAD drawing, and additional information that may be required to define solid surfaces and other model characteristics. The format of data in a drawing file depends on the CAD program used to create the file. Generally, drawings are not directly interchangeable between drawing programs, however, drawings created in one system can usually be translated into an intermediate format or file type, such as DXF, that allows some of the drawing information to be exchanged between different programs. Translation frequently results in some loss of detail or loss of other drawing information because the various drawing programs do not all have the same features. The section Drawing Exchange Standards covers some of the available methods of transferring drawing data between different CAD programs.



Fig. 1. Simple Wireframe Cube with Hidden Lines Automatically Removed

The simplest CAD drawings are two-dimensional and conform to normal engineering drafting practice showing orthographic (front, top, and side views, for example), exploded, isometric, or other views of a component. Depending on the complexity of the part and machining requirements, two-dimensional drawings are often sufficient for use in developing NC/CNC part programs. If a part can be programmed within a two-dimensional

Copyright 2004, Industrial Press, Inc., New York, NY

CAD framework, a significant cost saving may be realized because 3-D drawings require considerably more time, drawing skill, and experience to produce than 2-D drawings.

Wireframes are the simplest two- and three-dimensional forms of drawing images and are created by defining all edges of a part and, where required, lines defining surfaces. Wireframe drawing elements consist primarily of lines and arcs that can be used in practically any combination. A wireframe drawing of a cube, as in Fig. 1, consists of 12 lines of equal length (some are hidden and thus not shown), each perpendicular to the others. Information about the interior of the cube and the character of the surfaces is not included in the drawing. With such a system, if a 1-inch cube is drawn and a 0.5-inch cylinder is required to intersect the cube's surface at the center of one of its faces, the intersection points cannot be determined because nothing is known about the area between the edges. A wireframe model of this type is ambiguous if the edges overlap or do not meet where they should. Hidden-line removal can be used to indicate the relative elevations of the drawing elements, but normally a drawing cannot be edited when hidden lines have been removed. Hidden lines can be shown dashed or can be omitted from the view.

Two-dimensional drawing elements, such as lines, arcs, and circles, are constructed by directly or indirectly specifying point coordinates, usually x and y, that identify the location, size, and orientation of the entities. Three-dimensional drawings are also made up of a collection of lines, arcs, circles, and other drawing elements and are stored in a similar manner. A third point coordinate, z, indicates the elevation of a point in 3-D drawings. On the drawing screen, working in the x-y plane, the elevation is commonly thought of as the distance of a point or object into the screen (away from the observer) or out of the viewing screen (toward the observer). Coordinate axes are oriented according to the right-hand rule: If the fingers of the right hand point in the direction from the positive x-axis to the positive y-axis, the thumb of the right hand points in the direction of the positive z-axis.

Assigning a thickness (or extruding) to objects drawn in two dimensions quickly gives some 3-D characteristics to an object and can be used to create simple prismatic 3-D shapes, such as cubes and cylinders. Usually, the greatest difficulty in creating 3-D drawings is in picking and visualizing the three-dimensional points in a two-dimensional workspace (the computer display screen). To assist in the selection of 3-D points, many CAD programs use a split or windowed screen drawing area that can simultaneously show different views of a drawing. Changes made in the current or active window are reflected in each of the other windows. A typical window setup might show three orthogonal (mutually perpendicular) views of the drawing and a perspective or 3-D view. Usually, the views shown can be changed as required to suit the needs of the operator.

If carefully constructed, wireframe images may contain enough information to completely define the external geometry of simple plane figures. Wireframe images are especially useful for visualization of 3-D objects and are effectively used during the design process to check fits, clearances, and dimensional accuracy. Parts designed to be used together can be checked for accuracy of fit by bringing them together in a drawing, superimposing the images, and graphically measuring clearances. If the parts have been designed or drawn incorrectly, the errors will frequently be obvious and appropriate corrections can be made.

A more complicated level of 3-D drawing involves solids, with sections of the part being depicted on the screen as solid geometrical structures called primitives, such as cylinders, spheres, and cubes. Primitives can be assembled on a drawing to show more complex parts. Three distinct forms of image may be generated by 3-D systems, although not all systems make use of all three.

Surface Images: A surface image defines not only the edges of the part, but also the "skin" of each face or surface. For the example mentioned previously, the intersection for the 0.5-inch cylinder would be calculated and drawn in position. Surface models are necessary for designing free-form objects such as automotive body panels and plastics injection moldings used in consumer goods. For a surface model, the computer must be provided

Copyright 2004, Industrial Press, Inc., New York, NY

with much more information about the part in addition to the x, y, z coordinates defining each point, as in a wireframe. This information may include tangent vectors, surface normals, and weighting that determines how much influence one point has on another, twists, and other mathematical data that define abstract curves, for instance. Fig. 2 shows a typical 3-D surface patch.

Shaded images may be constructed using simulated light sources, reflections, colors, and textures to make renderings more lifelike. Surface images are sometimes ambiguous, with surfaces that overlap or miss each other entirely. Information about the interior of the part, such as the center of gravity or the volume, also may not be available, depending on the CAD package.



Fig. 2. A 3-D Surface Patch



Fig. 3. Isometric Drawing Showing Orientation of Principle Drawing Axes

Solid Images: A solid image is the ultimate electronic representation of a part, containing all the necessary information about edges, surfaces, and the interior. Most solid-imaging programs can calculate volume, center of mass, centroid, and moment of inertia. Several methods are available for building a solid model. One method is to perform Boolean operations on simple shapes such as cylinders, cones, cubes, and blocks. Boolean operations are used to union (join), difference (subtract one from another), and intersect (find the common volume between two objects). Thus, making a hole in a part requires subtracting a cylinder from a rectangular block. This type of program is called constructive solid geometry (CSG).

The boundary representation type of imaging program uses profiles of 2-D shapes that it extrudes, rotates, and otherwise translates in 3-D space to create the required solid. Sometimes combinations of the above two programs are used to attain a blend of flexibility, accuracy, and performance. For more precision, greatly increased time is needed for calculations, so compromises sometimes are needed to maintain reasonable productivity. Solid images may be sliced or sectioned on the screen to provide a view of the interior. This type of image is also useful for checking fit and assembly of one part with another.

Solid images provide complete, unambiguous representation of a part, but the programs require large amounts of computer memory. Each time a Boolean operation is performed, the list of calculations that must be done to define the model becomes longer, so that computation time increases.

Drawing Projections.— Several different techniques are used to display objects on paper or a computer screen to give an accurate three-dimensional appearance. Several of these methods are commonly used in CAD drawings.

Isometric drawings, as in Fig. 3, can be used to good effect for visualizing a part because they give the impression of a 3-D view and are often much faster to create. Isometric drawings are created in 2-D space, with the x- and y-axes being inclined at 30 degrees to the horizontal, as shown in Fig. 3, and the z-axis as vertical. Holes and cylinders in isometric drawings become elliptical. Because of the orientation of the x-, y-, and z-axes, the true length of lines may not be accurately represented in isometric drawings and dimensions

Copyright 2004, Industrial Press, Inc., New York, NY

should not be taken directly from a print. Some CAD programs have a special set of predefined drawing axes to facilitate creating isometric drawings.

In *parallel projections*, lines that are parallel in an object, assembly, or part being portrayed remain parallel in the drawing. Parallel projections show 3-D objects in a dimensionally correct manner, so that relative and scaled dimensions may be taken directly from a drawing. However, drawings may not appear as realistic as isometric or perspective drawings.

A characteristic of *perspective drawings* is that parallel lines converge (see Fig. 4) so that objects that are farther away from the observer appear smaller. Perspective drawing techniques are used in some three-dimensional drawings to convey the true look of an object, or group of objects. Because objects in perspective drawings are not drawn to scale, dimensional information cannot be extracted from the drawings of a part. Some 3-D drawing packages have a true perspective drawing capability, and others use a simulation technique to portray a 3-D perspective.

An *axonometric projection* is a 3-D perpendicular projection of an object onto a surface, such that the object is tilted relative to its normal orientation. An axonometric projection of a cube, as in Fig. 1, shows three faces of the cube. CAD systems are adept at using this type of view, making it easy to see an object from any angle.



Fig. 4. Perspective Drawing of Three Equal-Size Cubes and Construction Lines



Fig. 5. A Common Positioning Error

Drawing Tips and Traps.— Images sometimes appear correct on the screen but contain errors that show up when the drawing is printed or used to produce NC/CNC part programs. In Fig. 5, the two lines within the smaller circle appear to intersect at a corner, but when the view of the intersection is magnified, as in the larger circle, it is clear that the lines actually do not touch. Although an error of this type may not be easily visible, other parts placed in the drawing relative to this part will be out of position.

A common problem that shows up in plotting, but is difficult to detect on the screen, comes from placing lines in the same spot. When two or more lines occupy exactly the same location on the screen, there is usually no noticeable effect on the display. However, when the drawing is plotted, each line is plotted separately, causing the single line visible to become thicker and darker. Likewise, if a line that appears continuous on the screen is actually made up of several segments, plotting the line will frequently result in a broken, marred, or blotted appearance to the line because the individual segments are plotted separately, and at different times. To avoid these problems and to get cleaner looking plots, replace segmented lines with single lines and avoid constructions that place one line directly on top of another.

Exact decimal values should be used when entering point coordinates from the keyboard, if possible; fractional sizes should be entered as fractions, not truncated decimals. For example, $5/16$ should be entered as 0.3125 or $5/16$, not 0.313. Accumulated rounding errors and surprises later on when parts do not fit are thus reduced. Drawing dimensions, on the

Copyright 2004, Industrial Press, Inc., New York, NY

other hand, should not have more significant digits or be more precise than necessary. Unnecessary precision in dimensioning leads to increased difficulty in the production stage because the part has to be made according to the accuracy indicated on the drawing.

Snap and *object snap* commands make selecting lines, arcs, circles, or other drawing entities faster, easier, and more accurate when picking and placing objects on the screen. Snap permits only points that are even multiples of the snap increment to be selected by the pointer. A $\frac{1}{8}$-inch snap setting, for example, will allow points to be picked at exactly $\frac{1}{8}$-inch intervals. Set the *snap increment* to the smallest distance increment (1 in., $\frac{1}{4}$ in., 1 ft., etc.) being used in the area of the drawing under construction and reset the snap increment frequently, if necessary. The snap feature can be turned off during a command to override the setting or to select points at a smaller interval than the snap increment allows. Some systems permit setting a different snap value for each coordinate axis.

The *object snap* selection mode is designed to select points on a drawing entity according to predefined characteristics of the entity. For example, if end-point snap is in effect, picking a point anywhere along a line will select the end point of the line nearest the point picked. Object snap modes include point, intersection, midpoint, center and quadrants of circles, tangency point (allows picking a point on an arc or circle that creates a tangent to a line), and perpendicular point (picks a point that makes a perpendicular from the base point to the object selected). When two or more object snap modes are used together, the nearest point that meets the selection criteria will be chosen. Using object snap will greatly reduce the frequency of the type of problem shown in Fig. 5.

Copy: Once drawn, avoid redrawing the same object. It is almost always faster to copy and modify a drawing than to draw it again. The basic copy commands are: copy, array, offset, and mirror. Use these, along with move and rotate and the basic editing commands, to modify existing objects. Copy and move should be the most frequently used commands. If possible, create just one instance of a drawing object and then copy and move it to create others.

To create multiple copies of an object, use the *copy, multiple* feature to copy selected objects as many times as required simply by indicating the destination points. The *array* command makes multiple copies of an object according to a regular pattern. The rectangular array produces rows and columns, and the polar array puts the objects into a circular pattern, such as in a bolt circle. *Offset* copies an entity and places the new entity a specified distance from the original and is particularly effective at placing parallel lines and curves, and for creating concentric copies of closed shapes. *Mirror* creates a mirror image copy of an object, and is useful for making right- and left-hand variations of an object as well as for copying objects from one side of an assembly to the other. In some CAD programs, a system variable controls whether text is mirrored along with other objects.

Many manufacturers distribute drawings of their product lines in libraries of CAD drawings, usually as DXF files, that can be incorporated into existing drawings. The suitability of such drawings depends on the CAD program and drawing format being used, the skill of the technician who created the drawings, and the accuracy of the drawings. A typical example, Fig. 6, shows a magnetically coupled actuator drawing distributed by Tol-O-Matic, Inc. Libraries of frequently used drawing symbols and blocks are also available from commercial sources.

Create Blocks of Frequently Used Objects: Once created, complete drawings or parts of drawings can be saved and later recalled, as needed, into another drawing. Such objects can be scaled, copied, stretched, mirrored, rotated, or otherwise modified without changing the original. When shapes are initially drawn in unit size (i.e., fitting within a 1×1 square) and saved, they can be inserted into any drawing and scaled very easily. One or more individual drawing elements can be saved as a group element, or *block*, that can be manipulated in a drawing as a single element. Block properties vary, depending on the drawing program, but are among the most powerful features of CAD. Typically, blocks are uniquely named

Copyright 2004, Industrial Press, Inc., New York, NY

and, as with simple objects, may be saved in a file on the disk. Blocks are ideal for creating libraries of frequently used drawing symbols. Blocks can be copied, moved, scaled very easily, rotated, arrayed, and inserted as many times as is required in a drawing and manipulated as one object. When scaled, each object within the block is also scaled to the same degree.



Fig. 6. Manufacturer's Drawing of a Magnetically Coupled Actuator (*Courtesy of Tol-O-Matic, Inc.*)

When a family of parts is to be drawn, create and block a single drawing of the part that fits within a unit cube of convenient size, such as 1 × 1 × 1. When the block is inserted in a drawing, it is scaled appropriately in the *x*-, *y*-, and *z*-directions. For example, $\frac{3}{8}$-inch bolts can be drawn 1 inch long in the *x*-direction and $\frac{3}{8}$-inch in diameter in the *y*-*z* plane. If a 5-inch bolt is needed, insert the "bolt" block with a scale of 5 in the *x*-direction and a scale of 1 in the *y*- and *z*-directions.

Once blocked, the individual components of a block (lines, arcs, circles, surfaces, and text, for example) cannot be individually changed or edited. To edit a block, a copy (instance) of the block must be *exploded* (unblocked) to divide it into its original components. Once exploded, all the individual elements of the block (except other blocks) can be edited. When the required changes have been made, the block must be redefined (redeclared as a block by giving it a name and identifying its components). If the block is redefined using the same name, any previous references to the block in the drawing will be updated to match the redefined block. For example, an assembly drawing is needed that shows a mechanical frame with 24 similar control panels attached to it. Once one of the panels is drawn and defined as a block (using the name *PANEL*, for instance), the block can be inserted (or copied) into the drawing 24 times. Later, if changes need to be made to the panel design, one instance of the block *PANEL* can be exploded, modified, and redefined with the name *PANEL*. When *PANEL* is redefined, every other copy of the *PANEL* block in the drawing is also redefined, so every copy of *PANEL* in the drawing is updated. On the other hand, if the block was redefined with a different name, say, *PANEL1*, existing copies of *PANEL* remain unchanged. When redefining a block that already exists in the drawing, be sure to use the same insertion point that was used for the original definition of the block; otherwise, the positions of existing blocks with the same name will be changed.

Use of Text Attributes to Request Drawing Information Automatically: Text attributes are a useful method for attaching textual information to a particular part or feature of a drawing. An attribute is basically a text variable that has a name and can be assigned a value. Attributes are created by defining attribute characteristics such as a name, location in the drawing, text size and style, and default value. The attribute value is assigned when the attribute is inserted into a drawing as part of a block.

Fig. 7 shows two views of a title block for size A to C drawing sheets. The upper figure includes the title block dimensions (included only for reference) and the names and locations of the attributes (COMPANY, TITLE1, TITLE2, etc.). When a block containing text

Copyright 2004, Industrial Press, Inc., New York, NY

attributes is inserted in a drawing, the operator is asked to enter the value of each attribute. To create this title block, first draw the frame of the title block and define the attributes (name, location and default value for: company name and address, drawing titles [2 lines], drawing size, drawing number, revision number, scale, and sheet number). Finally, create and name a block containing the title frame and all the attribute definitions (do not include the dimensions).



Fig. 7. Title Block for A to C Size Drawing Sheets Showing the Placement of Text Attributes. The Lower Figure Shows the Completed Block

When the block is inserted into a drawing, the operator is asked to enter the attribute values (such as company name, drawing title, etc.), which are placed into the title block at the predetermined location. The lower part of Fig. 7 shows a completed title block as it might appear inserted in a drawing. A complete drawing sheet could include several additional blocks, such as a sheet frame, a revision block, a parts list block, and any other supplementary blocks needed. Some of these blocks, such as the sheet frame, title, and parts list blocks, might be combined into a single block that could be inserted into a drawing at one time.

Define a Default Drawing Configuration: Drawing features that are commonly used in a particular type of drawing can be set up in a template file so that frequently used settings, such as text and dimension styles, text size, drawing limits, initial view, and other default settings, are automatically set up when a new drawing is started. Different configurations can be defined for each frequently used drawing type, such as assembly, parts, or printed circuit drawings. When creating a new drawing, use one of the template files as a pattern or open a template file and use it to create the new drawing, saving it with a new name.

Scaling Drawings: Normally, for fast and accurate drawing, it is easiest to draw most objects full scale, or with a 1:1 scale. This procedure greatly simplifies creation of the initial drawing, and ensures accuracy, because scale factors do not need to be calculated. If it becomes necessary to fit a large drawing onto a small drawing sheet (for example, to fit a 15 × 30 inch assembly onto a 11 × 17 inch, B-sized, drawing sheet), the drawing sheet can be scaled larger to fit the assembly size. Likewise, large drawing sheets can be scaled down to fit small drawings. The technique takes some practice, but it permits the drawing assembly to be treated full scale. If editing is required at a later date (to move something or add a hole in a particular location, for example), changes can be made without rescaling and dimensions can be taken directly from the unscaled drawing on the computer.

Scaling Text on Drawing Sheets: It is usually desirable that text, dimensions, and a few other features on drawings stay a consistent size on each sheet, even when the drawing size is very different. The following procedure ensures that text and dimensions (other features

Copyright 2004, Industrial Press, Inc., New York, NY

as well, if desired) will be the same size, from drawing to drawing without resorting to scaling the drawing to fit onto the drawing sheet.

Create a drawing sheet having the exact dimensions of the actual sheet to be output (A, B, C, D, or E size, for example). Use text attributes, such as the title block illustrated in Fig. 7, to include any text that needs to be entered each time the drawing sheet is used. Create a block of the drawing sheet, including the text attributes, and save the block to disk. Repeat for each size drawing sheet required.

Establish the nominal text and dimension size requirements for the drawing sheet when it is plotted full size (1:1 scale). This is the size text that will appear on a completed drawing. Use Table 1 as a guide to recommended text sizes of various drawing features.

Table 1. Standard Sizes of Mechanical Drawing Lettering *ANSI Y14.2M–1992*

Use For	Inch		Metric	
	Min. Letter Heights, (in)	Drawing Size	Min. Letter Heights, (mm)	Drawing Size
Drawing title, drawing size, CAGE Code, drawing number, and revision letter[a]	0.24	D, E, F, H, J, K	6	A0, A1
	0.12	A, B, C, G	3	A2, A3, A4
Section and view letters	0.24	All	6	All
Zone letters and numerals in borders	0.24	All	6	All
Drawing block headings	0.10	All	2.5	All
All other characters	0.12	All	3	All

[a] When used within the title block.

Test the sheet by setting the text size and dimension scale variables to their nominal values (established above) and place some text and dimensions onto the drawing sheet. Plot a copy of the drawing sheet and check that text and dimensions are the expected size.

To use the drawing sheet, open a drawing to be placed on the sheet and insert the sheet block into the drawing. Scale and move the sheet block to locate the sheet relative to the drawing contents. When scaling the sheet, try to use whole-number scale factors (3:1, 4:1, etc.), if possible; this will make setting text size and dimension scale easier later on. Set the text-size variable equal to the nominal text size multiplied by the drawing sheet insertion scale (for example, for 0.24 text height on a drawing sheet scaled 3:1, the text-size variable will be set to $3 \times 0.24 = 0.72$). Likewise, set the dimension-scale variable equal to the nominal dimension size multiplied by the drawing sheet insertion scale.

Once the text size and dimensions scale variables have been set, enter all the text and dimensions into the drawing. If text of another size is needed, multiply the *new* nominal text size by the sheet scale to get the actual size of the text to use in the drawing.

Use Appropriate Detail: Excessive detail may reduce the effectiveness of the drawing, increase the drawing time on individual commands and the overall time spent on a drawing, and reduce performance and speed of the CAD program. Whenever possible, symbolic drawing elements should be used to represent more complicated parts of a drawing unless the appearance of that particular component is essential to the drawing.

Drawing everything to scale often serves no purpose but to complicate a drawing and increase drawing time. The importance of detail depends on the purpose of a drawing, but detail in one drawing is unnecessary in another. For example, the slot size of a screw head (length and width) varies with almost every size of screw. If the purpose of a drawing is to show the type and location of the hardware, a symbolic representation of a screw is usually all that is required. The same is generally true of other screw heads, bolt threads, bolt head diameters and width across the flats, wire diameters, and many other hardware features.

Drawing Exchange Standards.— The ability to transfer working data between different CAD, CAD/CAM, design analysis, and NC/CNC programs is one of the most important requirements of engineering drawing programs. Once an engineer, designer, draftsman, or machinist enters relevant product data into his or her machine (computer or machine tool), the information defining the characteristics of the product should be available to the others

Copyright 2004, Industrial Press, Inc., New York, NY

involved in the project without recreating or reentering it. In view of manufacturing goals of reducing lead time and increasing productivity, concurrent engineering, and improved product performance, interchangeable data are a critical component in a CAD/CAM program. Depending on the requirements of a project, it may be entirely possible to transfer most if not all of the necessary product drawings from one drawing system to another.

IGES stands for Initial Graphics Exchange Specification and is a means of exchanging or converting drawings and CAD files for use in a different computer graphics system. The concept is shown diagrammatically in Fig. 8. Normally, a drawing prepared on the computer graphics system supplied by company A would have to be redrawn before it would operate on the computer graphics system supplied by company B. However, with IGES, the drawing can be passed through a software package called a preprocessor that converts it into a standardized IGES format that can be stored on a magnetic disk. A postprocessor at company B is then used to convert the standard IGES format to that required for their graphics system. Both firms would be responsible for purchasing or developing their own preprocessors and postprocessors, to suit their own machines and control systems. Almost all the major graphics systems manufacturing companies today either have or are developing IGES preprocessor and postprocessor programs to convert software from one system to another.



Fig. 8.

DXF stands for Drawing Exchange Format and is a pseudo-standard file format used for exchanging drawings and associated information between different CAD and design analysis programs. Nearly all two- and three-dimensional CAD programs support some sort of drawing exchange through the use of DXF files, and most can read and export DXF files. There are, however, differences in the drawing features supported and the manner in which the DXF files are handled by each program. For example, if a 3-D drawing is exported in the DXF format and imported into a 2-D CAD program, some loss of information results because all the 3-D features are not supported by the 2-D program, so that most attempts to make a transfer between such programs fail completely. Most common drawing entities (lines, arcs, etc.) will transfer successfully, although other problems may occur. For example, drawing entities that are treated as a single object in an original drawing (such as blocks, hatch patterns, and symbols) may be divided into hundreds of individual components when converted into a DXF file. Consequently, such a drawing may become much more difficult to edit after it is transferred to another drawing program.

ASCII stands for American Standard Code for Information Interchange. ASCII is a code system that describes the manner in which character-based information is stored in a computer system. Files stored in the ASCII format can be transferred easily between computers, even those using different operating systems. Although ASCII is not a drawing file format, many CAD drawing formats (DXF and IGES, for example) are ASCII files. In these files, the drawing information is stored according to a specific format using ASCII characters. ASCII files are often referred to as pure text files because they can be read and edited by simple text editors.

HPGL, for Hewlett-Packard Graphics Language, is a format that was first developed for sending vector- (line-) based drawing information to pen plotters. The format is commonly used for sending drawing files to printers and plotters for printing. Because HPGL is a character-based format (ASCII), it can be transferred between computers easily. Normally, devices that recognize the HPGL format can print the files without using the program on which the file (a drawing, for example) was created.

Copyright 2004, Industrial Press, Inc., New York, NY

STL is a CAD drawing format that is primarily used to send CAD drawings to *rapid automated prototyping* machines. STL is a mnemonic abbreviation for stereo-lithography, the technique that is used to create three-dimensional solid models directly from computer-generated drawings and for which the drawing format was originally developed. Most prototyping machines use 3-D CAD drawing files in STL format to create a solid model of the part represented by a drawing.

STEP stands for Standard for Exchange of Product Model Data and is a series of existing and proposed ISO standards written to allow access to all the data that surround a product. It extends the IGES idea of providing a geometric data transfer to include all the other data that would need to be communicated about a product over its lifetime, and facilitates the use and accessibility of the product data. Although STEP is a new standard, software tools have been developed for converting data from the IGES to STEP format and from STEP to IGES.

Rapid Automated Prototyping.— Rapid automated prototyping is a method of quickly creating an accurate three-dimensional physical model directly from a computerized conception of the part. The process is accomplished without machining or the removal of any material, but rather is a method of building up the model in three-dimensional space. The process makes it possible to easily and automatically create shapes that would be difficult or impossible to produce by any other method. Currently, production methods are able to produce models with an accuracy tolerance of ± 0.005 inch. Models are typically constructed of photoreactive polymer resins, nylon, polycarbonate or other thermoplastics, and investment casting wax. The model size is limited by the capability of the modeling machines to about 1 cubic foot at the present, however, large models can be built in sections and glued or otherwise fastened together.

Much of the work and a large part of the cost associated with creating a physical model by rapid prototyping are in the initial creation of the CAD model. The model needs to be a 3-D design model, built using wireframe, surface, or solid CAD modeling techniques. Many full-featured CAD systems support translation of drawing files into the STL format, which is the preferred file format for downloading CAD models to rapid prototyping machines. CAD programs without STL file format capability can use the IGES or DXF file format. This process can be time-consuming and expensive because additional steps may have to be taken by the service bureau to recreate features lost in converting the IGES or DXF file into STL format. If the design file has to be edited by a service bureau to recreate surfaces lost in the translation, unwanted changes to the model may occur, unnoticed. The safest route is to create a CAD model and export it directly into the STL format, leaving little chance for unexpected errors. Reverse STL generators are also available that will display a file saved in STL format or convert it into a form that can be imported into a CAD program.

DNC.— DNC stands for Direct Numerical Control and refers to a method of controlling numerical control machines from a remote location by means of a link to a computer or computer network. In its simplest form, DNC consists of one NC or CNC machine linked by its serial port to a computer. The computer may be used to develop and store CNC part programs and to transfer part programs to the machine as required. DNC links are normally two-directional, meaning that the NC/CNC can be operated from a computer terminal and the computer can be operated or ordered to supply data to the NC/CNC from the machine's control panel.

The number of machines that can be connected to a DNC network depends on the network's capability; in theory, any number of machines can be attached, and controlled. The type of network depends on the individual DNC system, but most industry standard network protocols are supported, so DNC nodes can be connected to existing networks very easily. Individual NC/CNC machines on a network can be controlled locally, from a network terminal in another building, or even from a remote location miles away through phone or leased lines.

Copyright 2004, Industrial Press, Inc., New York, NY

Machinery Noise.— Noise from machinery or mechanical systems can be controlled to some degree in the design or development stage if quantified noise criteria are provided the designer. Manufacturers and consumers may also use the same information in deciding whether the noise generated by a machine will be acceptable for a specific purpose.

Noise criteria for may be classified as follows: 1) relating to the degree of interference with speech communications; 2) relating to physiological damage to humans, especially hearing; and 3) those relating to psychological disturbances in people exposed to noise.

Sound Level Specifications: Noise criteria generally are specified in some system of units representing sound levels. One commonly used system specifies sound levels in units called decibels on the "A" scale, written dBA. The dBA scale designates a sound level system weighted to match human hearing responses to various frequencies and loudness. For example, to permit effective speech communication, typical criteria for indoor maximum noise levels are: meeting and conference rooms, 42 dBA; private offices and small meeting rooms, 38 to 47 dBA; supervisors' offices and reception rooms, 38 to 52 dBA; large offices and cafeterias, 42 to 52 dBA; laboratories, drafting rooms, and general office areas, 47 to 56 dBA; maintenance shops, computer rooms, and washrooms, 52 to 61 dBA; control and electrical equipment rooms, 56 to 66 dBA; and manufacturing areas and foremen's offices, 66 dBA. Similarly, there are standards and recommendations for daily permissible times of exposure at various steady sound levels to avoid hearing damage. For a working shift of 8 hours, a steady sound level of 90 dBA is the maximum generally permitted, with marked reduction in allowable exposure times for higher sound levels.*

Measuring Machinery Noise.— The noise level produced by a single machine can be measured by using a standard sound level meter of the handheld type set to the dBA scale. However, when other machines are running at the same time, or when there are other background noises, the noise of the machine cannot be measured directly. In such cases, two measurements, taken as follows, can be used to calculate the noise level of the individual machine. The meter should be held at arm's length and well away from any bystanders to avoid possible significant error up to 5 dBA.

Step 1. At the point of interest, measure the total noise, T, in decibels; that is, measure the noise of the shop and the machine in question when all machines are running; Step 2. Turn off the machine in question and measure B, the remaining background noise level; Step 3. Calculate M, the noise of the machine alone, $M = 10\log_{10}[10^{(T/10)} - 10^{(B/10)}]$.

$$M = 10\log\left(10^{\frac{T}{10}} - 10^{\frac{B}{10}}\right)$$

Example 1: With a machine running, the sound level meter reads 51 decibels as the total shop noise T; and with the machine shut off the meter reads 49 decibels as the remaining background noise B. What is the noise level M of the machine alone?

$$M = 10\log\left(10^{\frac{51}{10}} - 10^{\frac{49}{10}}\right) = 46.7 \text{ decibels dBA}$$

Example 2: If in Example 1 the remaining background noise level B was 41 decibels instead of 49, what is the noise level of the machine alone?

$$M = 10\log\left(10^{\frac{51}{10}} - 10^{\frac{41}{10}}\right) = 50.5 \text{ decibels dBA}$$

Note: From this example it is evident that when the background noise level B is approximately 10 or more decibels lower than the total noise level T measured at the machine in question, then the background noise does not contribute significantly to the sound level at the machine and, for practical purposes, $M = T$ and no calculation is required.

* After April 1983, if employee noise exposures equal or exceed an 8-hour, time-weighted average sound level of 85 dB, OSHA requires employers to administer an effective hearing conservation program.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MANUFACTURING PROCESSES

PUNCHES, DIES, AND PRESS WORK

1329 Punches and Dies
1329 Clearance
1330 Lubricants for Press Work
1330 Annealing Drawn Shells
1330 Drawing Rectangular Shapes
1330 Speeds and Pressures for Presses
1331 Pressure Required for Punching
1331 Shut Height of Press
1331 Drawn Shells
1331 Diameters of Shell Blanks
1333 Drawn Cylindrical Shells
1334 Depth and Diameter Reductions
1335 Sheet Metal
1335 Lengths of Straight Stock
1339 Other Bending Allowance Formulas
1339 Joining and Edging
1344 Fine Blanking
1346 Steel Rule Dies
1347 Making Steel Rule Dies

ELECTRICAL DISCHARGE MACHINING

1349 EDM Terms
1351 EDM Process
1354 Electrical Control Adjustments
1355 Workpiece Materials
1355 Characteristics of Materials
1355 Electrode Materials
1356 Types of Electrodes
1357 Making Electrodes
1359 Wire EDM

IRON AND STEEL CASTINGS

1360 Material Properties
1360 Gray Cast Iron
1360 White Cast Iron
1360 Chilled Cast Iron
1360 Alloy Cast Iron
1361 Malleable-iron Castings
1361 Ductile Cast Iron
1362 Steel Castings
1362 Carbon Steel Castings
1363 Mechanical Properties
1363 Alloy Steel Castings
1364 Heat-Resistant Steel Castings

IRON AND STEEL CASTINGS (Continued)

1364 Corrosion-Resistant Steel Castings
1365 Casting of Metals
1367 Removal of Gates and Risers
1368 Blast Cleaning of Castings
1368 Heat Treatment of Steel Castings
1368 Estimating Casting Weight
1368 Woods for Patterns
1369 Selection of Wood
1369 Pattern Varnish
1369 Shrinkage Allowances
1369 Metal Patterns
1370 Weight of Casting
1370 Die Casting
1371 Porosity
1371 Designing Die Castings
1371 Alloys Used for Die Casting
1372 Aluminum-Base Alloys
1372 Zinc-Base Alloys
1372 Copper-Base Alloys
1372 Magnesium-Base Alloys
1373 Tin-Base Alloys
1373 Lead-Base Alloys
1373 Dies for Die-Casting Machines
1373 Die-Casting Bearing Metal
1374 Injection Molding of Metal
1374 Precision Investment Casting
1374 Casting Materials
1375 Master Mold
1375 Shrinkage Allowances
1375 Casting Dimensions
1375 Investment Materials
1376 Casting Operations
1376 Investment Removal
1376 Investment Castings
1376 Casting Weights and Sizes
1376 Design for Investment Casting
1377 Casting Milling Cutters
1377 Extrusion of Metals
1377 Basic Process
1379 Powder Metallurgy
1379 Advantages of Powder Metallurgy
1379 Limiting Factors
1379 Design of Briquetting Tools

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MANUFACTURING PROCESSES

SOLDERING AND BRAZING

1380 Soldering
1380 Forms Available
1380 Fluxes for Soldering
1380 Methods of Application
1382 Ultrasonic Fluxless Soldering
1382 Brazing
1382 Filler Metals
1382 Brazing Filler Metals
1382 Brazing Filler Metals
1382 Selection of Filler Metals
1386 Fluxes for Brazing
1387 Steadying Work
1387 Supplying Heat
1387 Symbol Application

WELDING

1389 Welding Electrodes and Fluxes
1389 Processes
1390 Gas Metal Arc Welding (GMAW)
1390 Electrode Diameters
1391 Maximum Deposition Rates
1391 GMAW Welding of Sheet Steel
1391 Application of Shielding Gases
1393 Welding Controls
1395 GMAW Spray Transfer
1395 Deposition Rates of Electrodes
1397 Optimum Settings for GMAW
1397 Spray Transfer Voltage
1398 Flux-Cored Arc Welding
1398 Flux-Cored Welding Electrodes
1398 Gas-Shielded Electrodes
1399 Settings for FCAW Electrodes
1399 Weld Requirements
1399 Selecting an FCAW Electrode
1400 FCAW Electrodes
1401 Contact Tip Recess
1401 Porosity and Worm Tracks
1401 Welding with Various Diameter
1402 High-Deposition Electrodes
1403 Deposition Rates for Vertical Up Welding
1403 Deposition Rates of Flat and Horizontal Welds
1403 Electrode Diameters and Deposition Rates
1404 Shielding Gases and FCAW Electrodes

WELDING

(Continued)

1405 Shielded Metal Arc Welding
1406 ANSI/AWS Standard
1406 AWS E60XX Electrodes
1408 AWS E70XX Electrodes
1409 Gas Tungsten Arc Welding
1409 GTAW Welding Current
1411 Tungsten Electrode Type
1412 Selection of GTAW
1412 Tungsten Electrode Compositions
1412 Electrode and Current Selection
1413 Current Ranges for GTAW Electrodes
1413 Current Ranges for EWP and EWZ and GTAW Electrodes
1414 Filler Metals
1414 Shielding Gases
1414 Plasma Arc Welding (PAW)
1414 Gases for Plasma Arc Welding
1415 Shielding Gases
1415 PAW Welding Equipment
1416 Applications
1416 Welding Aluminum
1417 Plasma Arc Surface Coating
1418 Plasma Arc Cutting of Metals
1418 Precision Plasma Arc Cutting
1418 Flame Cutting of Metals
1418 Arc Cutting
1419 The Cutting Torch
1419 Adjustment of Cutting Torch
1419 Metals That Can Be Cut
1419 Cutting Stainless Steel
1419 Cutting Cast Iron
1419 Mechanically Guided Torches
1419 Cutting Steel Castings
1420 Thickness of Metal
1420 Hard Facing
1420 Hard-Facing Materials
1420 High-Speed Steels
1421 Austenitic Manganese Steels
1421 Austenitic High-Chromium Irons
1421 Cobalt-Base Alloys
1422 Copper-Base Alloys
1423 Nickel-Chromium-Boron Alloys
1424 Chromium Plating
1424 Electron-Beam (EB) Welding
1425 Pipe Welding
1428 Use of Flux-cored Electrodes
1428 Complete Weld Fusion
1429 Other Methods

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MANUFACTURING PROCESSES

WELDING

(Continued)

1429 Pipe Welding Procedure
1429 Thick-Walled, Carbon-Steel Pipes, Root Welding
1430 Thick-Walled, Carbon-Steel Pipes, Fill and Cover Welds
1431 Thin-Walled Carbon Steel Pipes, Root, Fill and Cover Pass
1432 Weld and Welding Symbols
1432 ANSI Weld and Welding Symbols
1433 Basic Weld Symbols
1434 Supplementary Weld Symbols
1434 Welding Codes, Rules, Regulations, and Specifications
1435 Letter Designations for Welding
1436 ANSI Welding Symbols
1441 Nondestructive Testing
1441 Symbols

LASERS

1443 Introduction
1443 Laser Light
1443 Laser Beams
1444 Beam Focusing
1445 Types of Industrial Lasers
1445 Industrial Laser Systems
1446 Safety
1446 Laser Beam/Material Interaction
1447 Thermal Properties of Workpieces
1447 Cutting Metal with Lasers
1448 Beam Assistance Techniques
1448 Cut Edge Roughness
1449 Heat-Affected Zones
1450 Cutting of Nonmetals
1451 Welding with Lasers
1451 Laser Welding Theory
1452 Welded Joint Design
1452 Welding Rates
1452 Processing Gas
1453 Drilling with Lasers
1453 Laser Drilling Theory
1453 Direct Drilling
1453 Percussive Drilling
1454 Trepanning
1454 Drilling Rates

LASERS

(Continued)

1454 Heat Treatment with Lasers
1454 Materials Applicability
1454 Hardening Rates
1454 Cladding with Lasers
1455 Marking with Lasers
1455 Mask Marking
1455 Scanned-Beam Marking

FINISHING OPERATIONS

1456 Power Brush Finishing
1456 Description of Brushes
1456 Use of Brushes
1456 Deburring and Producing a Radius
1457 Eliminating Undesirable Conditions
1457 Characteristics in Power Brush
1457 Polishing and Buffing
1457 Polishing Wheels
1460 Polishing Operations and Abrasives
1460 Buffing Wheels
1460 Speed of Polishing Wheels
1461 Grain Numbers of Emery
1461 Grades of Emery Cloth
1461 Etching and Etching Fluids
1461 Etching Fluids
1462 Conversion Coatings and the Coloring of Metals
1462 Passivation of Copper
1462 Coloring of Copper Alloys
1463 Coloring of Iron and Steel
1463 Anodizing Aluminum Alloys
1464 Magnesium Alloys
1464 Titanium Alloys
1464 Plating
1464 Surface Coatings
1472 Flame Spraying Process

Copyright 2004, Industrial Press, Inc., New York, NY

PUNCHES, DIES, AND PRESS WORK

Clearance between Punches and Dies.— The amount of clearance between a punch and die for blanking and perforating is governed by the thickness and kind of stock to be operated upon. For thin material, the punch should be a close sliding fit to prevent ragged edges, but for heavier stock, there should be some clearance. The clearance between the punch and die in cutting heavy material reduces the pressure required for the punching operation and the danger of breaking the punch.

Meaning of the Term "Clearance".— There is a difference of opinion among diemakers as to the method of designating clearance. The prevailing practice of fifteen firms specializing in die work is as follows: Ten of these firms define clearance as the space between the punch and die on *one side*, or one-half the difference between the punch and die sizes. The remaining five firms consider clearance as the total difference between the punch and die sizes; for example, if the die is round, clearance equals die diameter minus punch diameter. The advantage of designating clearance as the space on each side is particularly evident with dies of irregular form or of angular shape. Although the practice of designating clearance as the difference between the punch and die diameters may be satisfactory for round dies, it leads to confusion when the dies are of unsymmetrical forms. The term "clearance" should not be used in specifications without indicating clearly just what it means. According to one die manufacturer, the term "cutting clearance" is used to indicate the space between the punch and die on each side, and the term "die clearance" refers to the angular clearance provided below the cutting edge so that the parts will fall easily through the die. The term "clearance" as here used means the space on one side only; hence, for round dies, clearance equals die radius minus punch radius.

Clearances Generally Allowed.— For brass and soft steel, most dies are given a clearance on one side equal to the stock thickness multiplied by 0.05 or 0.06; but one-half of this clearance is preferred for some classes of work, and a clearance equal to the stock thickness multiplied by 0.10 may give the cleanest fracture for certain other operations such as punching holes in ductile steel boiler plate.

Where Clearance Is Applied.— Whether clearance is deducted from the diameter of the punch or added to the diameter of the die depends upon the nature of the work. If a blank of given size is required, the die is made to that size and the punch is made smaller. Inversely, when holes of a given size are required, the punch is made to the diameter wanted and the die is made larger. Therefore, for blanking to a given size, the clearance is deducted from the size of the punch, and for perforating, the clearance is added to the size of the die.

Effect of Clearance on Working Pressure.— Clearance affects not only the smoothness of the fracture, but also the pressure required for punching or blanking. This pressure is greatest when the punch diameter is small compared to the thickness of the stock. In one test, for example, a punching pressure of about 32,000 pounds was required to punch $\frac{3}{4}$-inch holes into $\frac{5}{16}$-inch mild steel plate when the clearance was about 10 per cent. With a clearance of about 4.5 per cent, the pressure increased to 33,000 pounds and a clearance of 2.75 per cent resulted in a pressure of 34,500 pounds.

Soft ductile metal requires more clearance than hard metal, although it has been common practice to increase the clearance for harder metals. In punching holes in fairly hard steel, a clean fracture was obtained with a clearance of only 0.03 times stock thickness.

Angular Clearance for Dies.— The angular clearance ordinarily used in a blanking die varies from 1 to 2 degrees, although dies intended for producing a comparatively small number of blanks are sometimes given a clearance angle of 4 or 5 degrees to facilitate making the die quickly. When large numbers of blanks are required, a clearance of about 1 degree is used.

Copyright 2004, Industrial Press, Inc., New York, NY

There are two methods of giving clearance to dies: In one method, the clearance extends to the top face of the die; and in the other, there is a space about 1/8 inch below the cutting edge that is left practically straight, or having a very small amount of clearance.

For very soft metal, such as soft, thin brass, the first method is employed, but for harder material, such as hard brass, steel, etc., it is better to have a very small clearance for a short distance below the cutting edge. When a die is made in this way, thousands of blanks can be cut with little variation in their size, as grinding the die face will not enlarge the hole to any appreciable extent.

Lubricants for Press Work.— Blanking dies used for carbon and low-alloy steels are often run with only residual mill lubricant, but will last longer if lightly oiled. Higher alloy and stainless steels require thicker lubricants. Kerosene is usually used with aluminum. Lubricant thickness needs to be about 0.0001 in. and can be obtained with about 1 pint of fluid to cover 500 sq. ft of material. During successive strokes, metal debris adheres to the punch and may accelerate wear, but damage may be reduced by application of the lubricant to the sheet or strip by means of rollers or spray. High-speed blanking may require heavier applications or a continuous airless spraying of oil. For sheet thicker than 1/8 in. and for stainless steel, high-pressure lubricants containing sulfurs and chlorines are often used.

Shallow drawing and forming of steel can be done with low-viscosity oils and soap solutions, but deeper draws require light- to medium-viscosity oils containing fats and such active elements as sulfur or phosphorus, and mineral fillers such as chalk or mica. Deep drawing often involves ironing or thinning of the walls by up to 35 per cent, and thick oils containing high proportions of chemically active compounds are used. Additives used in drawing compounds are selected for their ability to maintain a physical barrier between the tool surfaces and the metal being shaped. Dry soaps and polymer films are frequently used for these purposes. Aluminum can be shallow drawn with oils of low to medium viscosity, and for deep drawing, tallow may be added, also wax or soap suspensions for very large reductions.

Annealing Drawn Shells.— When drawing steel, iron, brass, or copper, annealing is necessary after two or three draws have been made, because the metal is hardened by the drawing process. For steel and brass, anneal between alternate reductions, at least. Tin plate or stock that cannot be annealed without spoiling the finish must ordinarily be drawn to size in one or two operations. Aluminum can be drawn deeper and with less annealing than the other commercial metals, provided the proper grade is used. If it is necessary to anneal aluminum, it should be heated in a muffle furnace, care being taken to see that the temperature does not exceed 700 degrees F.

Drawing Brass.— When drawing brass shells or cup-shaped articles, it is usually possible to make the depth of the first draw equal to the diameter of the shell. By heating brass to a temperature just below what would show a dull red in a dark room, it is possible to draw difficult shapes, otherwise almost impossible, and to produce shapes with square corners.

Drawing Rectangular Shapes.— When square or rectangular shapes are to be drawn, the radius of the corners should be as large as possible, because defects usually occur in the corners when drawing. Moreover, the smaller the radius, the less the depth that can be obtained in the first draw.

The maximum depths that can be drawn with corners of a given radii are approximately as follows: With a radius of 3/32 to 3/16 inch, depth of draw, 1 inch; radius 3/16 to 3/8 inch, depth 1½ inches; radius 3/8 to ½ inch, depth 2 inches; and radius ½ to ¾ inch, depth 3 inches.

These figures are taken from actual practice and can doubtless be exceeded slightly when using metal prepared for the process. If the box needs to be quite deep and the radius is quite small, two or more drawing operations will be necessary.

Speeds and Pressures for Presses.— The speeds for presses equipped with cutting dies depend largely upon the kind of material being worked, and its thickness. For punching

Copyright 2004, Industrial Press, Inc., New York, NY

and shearing ordinary metals not over ¼ inch thick, the speeds usually range between 50 and 200 strokes per minute, 100 strokes per minute being a fair average. For punching metal over ¼ inch thick, geared presses with speeds ranging from 25 to 75 strokes per minute are commonly employed.

The cutting pressures required depend upon the shearing strength of the material, and the actual area of the surface being severed. For round holes, the pressure required equals the circumference of the hole × the thickness of the stock × the shearing strength.

To allow for some excess pressure, the tensile strength may be substituted for the shearing strength; the tensile strength for these calculations may be roughly assumed as follows: Mild steel, 60,000; wrought iron, 50,000; bronze, 40,000; copper, 30,000; aluminum, 20,000; zinc, 10,000; and tin and lead, 5,000 pounds per square inch.

Pressure Required for Punching.— The formula for the force in tons required to punch a circular hole in sheet steel is $\pi DST/2000$, where S = the shearing strength of the material in lb/in.^{2}, T = thickness of the steel in inches, and 2000 is the number of lb in 1 ton. An approximate formula is DT × 80, where D and T are the diameter of the hole and the thickness of the steel, respectively, both in inches, and 80 is a factor for steel. The result is the force in tons.

Example: Find the pressure required to punch a hole, 2 inches in diameter, through ¼-in. thick steel. By applying the approximate formula, $2 \times \frac{1}{4} \times 80 = 40$ tons.

If the hole is not circular, replace the hole diameter with the value of one-third of the perimeter of the hole to be punched.

Example: Find the pressure required to punch a 1-inch square hole in ¼-in. thick steel. The total length of the hole perimeter is 4 in. and one-third of 4 in. is 1⅓ in., so the force is $1\frac{1}{3} \times \frac{1}{4} \times 80 = 26\frac{2}{3}$ tons.

The corresponding factor for punching holes in brass is 65 instead of 80. So, to punch a hole measuring 1 by 2 inches in ¼-in. thick brass sheet, the factor for hole size is the perimeter length $6 \div 3 = 2$, and the formula is $2 \times \frac{1}{4} \times 65 = 32\frac{1}{2}$ tons.

Shut Height of Press.— The term "shut height," as applied to power presses, indicates the die space when the slide is at the bottom of its stroke and the slide connection has been adjusted upward as far as possible. The "shut height" is the distance from the lower face of the slide, either to the top of the bed or to the top of the bolster plate, there being two methods of determining it; hence, this term should always be accompanied by a definition explaining its meaning. According to one press manufacturer, the safest plan is to define "shut height" as the distance from the top of the bolster to the bottom of the slide, with the stroke down and the adjustment up, because most dies are mounted on bolster plates of standard thickness, and a misunderstanding that results in providing too much die space is less serious than having insufficient die space. It is believed that the expression "shut height" was applied first to dies rather than to presses, the shut height of a die being the distance from the bottom of the lower section to the top of the upper section or punch, excluding the shank, and measured when the punch is in the lowest working position.

Diameters of Shell Blanks.— The diameters of blanks for drawing plain cylindrical shells can be obtained from Table 1 on the following pages, which gives a very close approximation for thin stock. The blank diameters given in this table are for sharp-cornered shells and are found by the following formula in which D = diameter of flat blank; d = diameter of finished shell; and h = height of finished shell.

$$D = \sqrt{d^2 + 4dh} \quad (1)$$

Example: If the diameter of the finished shell is to be 1.5 inches, and the height, 2 inches, the trial diameter of the blank would be found as follows:

Copyright 2004, Industrial Press, Inc., New York, NY

$$D = \sqrt{1.5^2 + 4 \times 1.5 \times 2} = \sqrt{14.25} = 3.78 \text{ inches}$$

For a round-cornered cup, the following formula, in which r equals the radius of the corner, will give fairly accurate diameters, provided the radius does not exceed, say, ¼ the height of the shell:

$$D = \sqrt{d^2 + 4dh} - r \tag{2}$$

These formulas are based on the assumption that the thickness of the drawn shell is the same as the original thickness of the stock, and that the blank is so proportioned that its area will equal the area of the drawn shell. This method of calculating the blank diameter is quite accurate for thin material, when there is only a slight reduction in the thickness of the metal incident to drawing; but when heavy stock is drawn and the thickness of the finished shell is much less than the original thickness of the stock, the blank diameter obtained from Formula (1) or (2) will be too large, because when the stock is drawn thinner, there is an increase in area. When an appreciable reduction in thickness is to be made, the blank diameter can be obtained by first determining the "mean height" of the drawn shell by the following formula. This formula is only approximately correct, but will give results sufficiently accurate for most work:

$$M = \frac{ht}{T} \tag{3}$$

where M = approximate mean height of drawn shell; h = height of drawn shell; t = thickness of shell; and T = thickness of metal before drawing.

After determining the mean height, the blank diameter for the required shell diameter is obtained from the table previously referred to, the mean height being used instead of the actual height.

Example: Suppose a shell 2 inches in diameter and 3 ¾ inches high is to be drawn, and that the original thickness of the stock is 0.050 inch, and the thickness of drawn shell, 0.040 inch. To what diameter should the blank be cut? Obtain the mean height from Formula (3):

$$M = \frac{ht}{T} = \frac{3.75 \times 0.040}{0.050} = 3 \text{ inches}$$

According to the table, the blank diameter for a shell 2 inches in diameter and 3 inches high is 5.29 inches. Formula (3) is accurate enough for all practical purposes, unless the reduction in the thickness of the metal is greater than about one-fifth the original thickness. When there is considerable reduction, a blank calculated by this formula produces a shell that is too long. However, the error is in the right direction, as the edges of drawn shells are ordinarily trimmed.

If the shell has a rounded corner, the radius of the corner should be deducted from the figures given in the table. For example, if the shell referred to in the foregoing example had a corner of ¼-inch radius, the blank diameter would equal 5.29 – 0.25 = 5.04 inches.

Another formula that is sometimes used for obtaining blank diameters for shells, when there is a reduction in the thickness of the stock, is as follows:

$$D = \sqrt{a^2 + (a^2 - b^2)\frac{h}{t}} \tag{4}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Diameters of Blanks for Drawn Cylindrical Shells

Diam. of Shell	Height of Shell																			
	¼	½	¾	1	1 ¼	1 ½	1 ¾	2	2 ¼	2 ½	2 ¾	3	3 ¼	3 ½	3 ¾	4	4 ½	5	5 ½	6
¼	0.56	0.75	0.90	1.03	1.14	1.25	1.35	1.44	1.52	1.60	1.68	1.75	1.82	1.89	1.95	2.01	2.14	2.25	2.36	2.46
½	0.87	1.12	1.32	1.50	1.66	1.80	1.94	2.06	2.18	2.29	2.40	2.50	2.60	2.69	2.78	2.87	3.04	3.21	3.36	3.50
¾	1.14	1.44	1.68	1.89	2.08	2.25	2.41	2.56	2.70	2.84	2.97	3.09	3.21	3.33	3.44	3.54	3.75	3.95	4.13	4.31
1	1.41	1.73	2.00	2.24	2.45	2.65	2.83	3.00	3.16	3.32	3.46	3.61	3.74	3.87	4.00	4.12	4.36	4.58	4.80	5.00
1 ¼	1.68	2.01	2.30	2.56	2.79	3.01	3.21	3.40	3.58	3.75	3.91	4.07	4.22	4.37	4.51	4.64	4.91	5.15	5.39	5.62
1 ½	1.94	2.29	2.60	2.87	3.12	3.36	3.57	3.78	3.97	4.15	4.33	4.50	4.66	4.82	4.98	5.12	5.41	5.68	5.94	6.18
1 ¾	2.19	2.56	2.88	3.17	3.44	3.68	3.91	4.13	4.34	4.53	4.72	4.91	5.08	5.26	5.41	5.58	5.88	6.17	6.45	6.71
2	2.45	2.83	3.16	3.46	3.74	4.00	4.24	4.47	4.69	4.90	5.10	5.29	5.48	5.66	5.83	6.00	6.32	6.63	6.93	7.21
2 ¼	2.70	3.09	3.44	3.75	4.04	4.31	4.56	4.80	5.03	5.25	5.46	5.66	5.86	6.05	6.23	6.41	6.75	7.07	7.39	7.69
2 ½	2.96	3.36	3.71	4.03	4.33	4.61	4.87	5.12	5.36	5.59	5.81	6.02	6.22	6.42	6.61	6.80	7.16	7.50	7.82	8.14
2 ¾	3.21	3.61	3.98	4.31	4.62	4.91	5.18	5.44	5.68	5.92	6.15	6.37	6.58	6.79	6.99	7.18	7.55	7.91	8.25	8.58
3	3.46	3.87	4.24	4.58	4.90	5.20	5.48	5.74	6.00	6.25	6.48	6.71	6.93	7.14	7.35	7.55	7.94	8.31	8.66	9.00
3 ¼	3.71	4.13	4.51	4.85	5.18	5.48	5.77	6.04	6.31	6.56	6.80	7.04	7.27	7.49	7.70	7.91	8.31	8.69	9.06	9.41
3 ½	3.97	4.39	4.77	5.12	5.45	5.77	6.06	6.34	6.61	6.87	7.12	7.36	7.60	7.83	8.05	8.26	8.67	9.07	9.45	9.81
3 ¾	4.22	4.64	5.03	5.39	5.73	6.05	6.35	6.64	6.91	7.18	7.44	7.69	7.92	8.16	8.38	8.61	9.03	9.44	9.83	10.20
4	4.47	4.90	5.29	5.66	6.00	6.32	6.63	6.93	7.21	7.48	7.75	8.00	8.25	8.49	8.72	8.94	9.38	9.80	10.20	10.58
4 ¼	4.72	5.15	5.55	5.92	6.27	6.60	6.91	7.22	7.50	7.78	8.05	8.31	8.56	8.81	9.04	9.28	9.72	10.15	10.56	10.96
4 ½	4.98	5.41	5.81	6.19	6.54	6.87	7.19	7.50	7.79	8.08	8.35	8.62	8.87	9.12	9.37	9.60	10.06	10.50	10.92	11.32
4 ¾	5.22	5.66	6.07	6.45	6.80	7.15	7.47	7.78	8.08	8.37	8.65	8.92	9.18	9.44	9.69	9.93	10.40	10.84	11.27	11.69
5	5.48	5.92	6.32	6.71	7.07	7.42	7.75	8.06	8.37	8.66	8.94	9.22	9.49	9.75	10.00	10.25	10.72	11.18	11.62	12.04
5 ¼	5.73	6.17	6.58	6.97	7.33	7.68	8.02	8.34	8.65	8.95	9.24	9.52	9.79	10.05	10.31	10.56	11.05	11.51	11.96	12.39
5 ½	5.98	6.42	6.84	7.23	7.60	7.95	8.29	8.62	8.93	9.23	9.53	9.81	10.08	10.36	10.62	10.87	11.37	11.84	12.30	12.74
5 ¾	6.23	6.68	7.09	7.49	7.86	8.22	8.56	8.89	9.21	9.52	9.81	10.10	10.38	10.66	10.92	11.18	11.69	12.17	12.63	13.08
6	6.48	6.93	7.35	7.75	8.12	8.49	8.83	9.17	9.49	9.80	10.10	10.39	10.68	10.95	11.23	11.49	12.00	12.49	12.96	13.42

Copyright 2004, Industrial Press, Inc., New York, NY

In this formula, D = blank diameter; a = outside diameter; b = inside diameter; t = thickness of shell at bottom; and h = depth of shell. This formula is based on the volume of the metal in the drawn shell. It is assumed that the shells are cylindrical, and no allowance is made for a rounded corner at the bottom, or for trimming the shell after drawing. To allow for trimming, add the required amount to depth h. When a shell is of irregular cross-section, if its weight is known, the blank diameter can be determined by the following formula:

$$D = 1.1284\sqrt{\frac{W}{wt}} \quad (5)$$

where D = blank diameter in inches; W = weight of shell; w = weight of metal per cubic inch; and t = thickness of the shell.

In the construction of dies for producing shells, especially of irregular form, a common method to be used is to make the drawing tool first. The actual blank diameter then can be determined by trial. One method is to cut a trial blank as near to size and shape as can be estimated. The outline of this blank is then scribed on a flat sheet, after which the blank is drawn. If the finished shell shows that the blank is not of the right diameter or shape, a new trial blank is cut either larger or smaller than the size indicated by the line previously scribed, this line acting as a guide. If a model shell is available, the blank diameter can also be determined as follows:

First, cut a blank somewhat large, and from the same material used for making the model; then, reduce the size of the blank until its weight equals the weight of the model.

Depth and Diameter Reductions of Drawn Cylindrical Shells.— The depth to which metal can be drawn in one operation depends upon the quality and kind of material, its thickness, the slant or angle of the dies, and the amount that the stock is thinned or "ironed" in drawing. A general rule for determining the depth to which cylindrical shells can be drawn in one operation is as follows: The depth or length of the first draw should never be greater than the diameter of the shell. If the shell is to have a flange at the top, it may not be practicable to draw as deeply as is indicated by this rule, unless the metal is extra good, because the stock is subjected to a higher tensile stress, owing to the larger blank needed to form the flange. According to another rule, the depth given the shell on the first draw should equal one-third the diameter of the blank. Ordinarily, it is possible to draw sheet steel of any thickness up to ¼ inch, so that the diameter of the first shell equals about six-tenths of the blank diameter. When drawing plain shells, the amount that the diameter is reduced for each draw must be governed by the quality of the metal and its susceptibility to drawing. The reduction for various thicknesses of metal is about as follows:

Approximate thickness of sheet steel	1/16	1/8	3/16	1/4	5/16
Possible reduction in diameter for each succeeding step, per cent	20	15	12	10	8

For example, if a shell made of 1/16-inch stock is 3 inches in diameter after the first draw, it can be reduced 20 per cent on the next draw, and so on until the required diameter is obtained. These figures are based upon the assumption that the shell is annealed after the first drawing operation, and at least between every two of the following operations. Necking operations—that is, the drawing out of a short portion of the lower part of the cup into a long neck—may be done without such frequent annealings. In double-action presses, where the inside of the cup is supported by a bushing during drawing, the reductions possible may be increased to 30, 24, 18, 15, and 12 per cent, respectively. (The latter figures may also be used for brass in single-action presses.)

When a hole is to be pierced at the bottom of a cup and the remaining metal is to be drawn after the hole has been pierced or punched, always pierce from the opposite direction to

Copyright 2004, Industrial Press, Inc., New York, NY

that in which the stock is to be drawn after piercing. It may be necessary to machine the metal around the pierced hole to prevent the starting of cracks or flaws in the subsequent drawing operations.

The foregoing figures represent conservative practice and it is often possible to make greater reductions than are indicated by these figures, especially when using a good drawing metal. Taper shells require smaller reductions than cylindrical shells, because the metal tends to wrinkle if the shell to be drawn is much larger than the punch. The amount that the stock is "ironed" or thinned out while being drawn must also be considered, because a reduction in gage or thickness means greater force will be exerted by the punch against the bottom of the shell; hence the amount that the shell diameter is reduced for each drawing operation must be smaller when much ironing is necessary. The extent to which a shell can be ironed in one drawing operation ranges between 0.002 and 0.004 inch per side, and should not exceed 0.001 inch on the final draw, if a good finish is required.

Allowances for Bending Sheet Metal.— In bending steel, brass, bronze, or other metals, the problem is to find the length of straight stock required for each bend; these lengths are added to the lengths of the straight sections to obtain the total length of the material before bending.

If L = length in inches, of straight stock required before bending; T = thickness in inches; and R = inside radius of bend in inches:

For 90° bends in soft brass and soft copper see Table 2 or:

$$L = (0.55 \times T) + (1.57 \times R) \quad (1)$$

For 90° bends in half-hard copper and brass, soft steel, and aluminum see Table 3 or:

$$L = (0.64 \times T) + (1.57 \times R) \quad (2)$$

For 90° bends in bronze, hard copper, cold-rolled steel, and spring steel see Table 4 or:

$$L = (0.71 \times T) + (1.57 \times R) \quad (3)$$

Angle of Bend Other Than 90 Degrees: For angles other than 90 degrees, find length L, using tables or formulas, and multiply L by angle of bend, in degrees, divided by 90 to find length of stock before bending. In using this rule, note that *angle of bend* is the angle through which the material has actually been bent; hence, it is not always the angle as given on a drawing. To illustrate, in Fig. 1, the angle on the drawing is 60 degrees, but the angle of bend A is 120 degrees (180 − 60 = 120); in Fig. 2, the angle of bend A is 60 degrees; in Fig. 3, angle A is 90 − 30 = 60 degrees. Formulas (1), (2), and (3) are based on extensive experiments of the Westinghouse Electric Co. They apply to parts bent with simple tools or on the bench, where limits of ± 1/64 inch are specified. If a part has two or more bends of the same radius, it is, of course, only necessary to obtain the length required for one of the bends and then multiply by the number of bends, to obtain the total allowance for the bent sections.



Fig. 1.



Fig. 2.



Fig. 3.

Example, Showing Application of Formulas: Find the length before bending of the part illustrated by Fig. 4. Soft steel is to be used.

For bend at left-hand end (180-degree bend)

$$L = [(0.64 \times 0.125) + (1.57 \times 0.375)] \times \frac{180}{90} = 1.338$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Lengths of Straight Stock Required for 90-Degree Bends in Soft Copper and Soft Brass

Radius *R* of Bend, Inches	Thickness *T* of Material, Inch												
	1/64	1/32	3/64	1/16	5/64	3/32	1/8	5/32	3/16	7/32	1/4	9/32	5/16
1/32	0.058	0.066	0.075	0.083	0.092	0.101	0.118	0.135	0.152	0.169	0.187	0.204	0.221
3/64	0.083	0.091	0.100	0.108	0.117	0.126	0.143	0.160	0.177	0.194	0.212	0.229	0.246
1/16	0.107	0.115	0.124	0.132	0.141	0.150	0.167	0.184	0.201	0.218	0.236	0.253	0.270
3/32	0.156	0.164	0.173	0.181	0.190	0.199	0.216	0.233	0.250	0.267	0.285	0.302	0.319
1/8	0.205	0.213	0.222	0.230	0.239	0.248	0.265	0.282	0.299	0.316	0.334	0.351	0.368
5/32	0.254	0.262	0.271	0.279	0.288	0.297	0.314	0.331	0.348	0.365	0.383	0.400	0.417
3/16	0.303	0.311	0.320	0.328	0.337	0.346	0.363	0.380	0.397	0.414	0.432	0.449	0.466
7/32	0.353	0.361	0.370	0.378	0.387	0.396	0.413	0.430	0.447	0.464	0.482	0.499	0.516
1/4	0.401	0.409	0.418	0.426	0.435	0.444	0.461	0.478	0.495	0.512	0.530	0.547	0.564
9/32	0.450	0.458	0.467	0.475	0.484	0.493	0.510	0.527	0.544	0.561	0.579	0.596	0.613
5/16	0.499	0.507	0.516	0.524	0.533	0.542	0.559	0.576	0.593	0.610	0.628	0.645	0.662
11/32	0.549	0.557	0.566	0.574	0.583	0.592	0.609	0.626	0.643	0.660	0.678	0.695	0.712
3/8	0.598	0.606	0.615	0.623	0.632	0.641	0.658	0.675	0.692	0.709	0.727	0.744	0.761
13/32	0.646	0.654	0.663	0.671	0.680	0.689	0.706	0.723	0.740	0.757	0.775	0.792	0.809
7/16	0.695	0.703	0.712	0.720	0.729	0.738	0.755	0.772	0.789	0.806	0.824	0.841	0.858
15/32	0.734	0.742	0.751	0.759	0.768	0.777	0.794	0.811	0.828	0.845	0.863	0.880	0.897
1/2	0.794	0.802	0.811	0.819	0.828	0.837	0.854	0.871	0.888	0.905	0.923	0.940	0.957
9/16	0.892	0.900	0.909	0.917	0.926	0.935	0.952	0.969	0.986	1.003	1.021	1.038	1.055
5/8	0.990	0.998	1.007	1.015	1.024	1.033	1.050	1.067	1.084	1.101	1.119	1.136	1.153
11/16	1.089	1.097	1.106	1.114	1.123	1.132	1.149	1.166	1.183	1.200	1.218	1.235	1.252
3/4	1.187	1.195	1.204	1.212	1.221	1.230	1.247	1.264	1.281	1.298	1.316	1.333	1.350
13/16	1.286	1.294	1.303	1.311	1.320	1.329	1.346	1.363	1.380	1.397	1.415	1.432	1.449
7/8	1.384	1.392	1.401	1.409	1.418	1.427	1.444	1.461	1.478	1.495	1.513	1.530	1.547
15/16	1.481	1.489	1.498	1.506	1.515	1.524	1.541	1.558	1.575	1.592	1.610	1.627	1.644
1	1.580	1.588	1.597	1.605	1.614	1.623	1.640	1.657	1.674	1.691	1.709	1.726	1.743
1 1/16	1.678	1.686	1.695	1.703	1.712	1.721	1.738	1.755	1.772	1.789	1.807	1.824	1.841
1 1/8	1.777	1.785	1.794	1.802	1.811	1.820	1.837	1.854	1.871	1.888	1.906	1.923	1.940
1 3/16	1.875	1.883	1.892	1.900	1.909	1.918	1.935	1.952	1.969	1.986	2.004	2.021	2.038
1 1/4	1.972	1.980	1.989	1.997	2.006	2.015	2.032	2.049	2.066	2.083	2.101	2.118	2.135

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Lengths of Straight Stock Required for 90-Degree Bends in Half-Hard Brass and Sheet Copper, Soft Steel, and Aluminum

Radius *R* of Bend, Inches	Thickness *T* of Material, Inch												
	1/64	1/32	3/64	1/16	5/64	3/32	1/8	5/32	3/16	7/32	1/4	9/32	5/16
1/32	0.059	0.069	0.079	0.089	0.099	0.109	0.129	0.149	0.169	0.189	0.209	0.229	0.249
3/64	0.084	0.094	0.104	0.114	0.124	0.134	0.154	0.174	0.194	0.214	0.234	0.254	0.274
1/16	0.108	0.118	0.128	0.138	0.148	0.158	0.178	0.198	0.218	0.238	0.258	0.278	0.298
3/32	0.157	0.167	0.177	0.187	0.197	0.207	0.227	0.247	0.267	0.287	0.307	0.327	0.347
1/8	0.206	0.216	0.226	0.236	0.246	0.256	0.276	0.296	0.316	0.336	0.356	0.376	0.396
5/32	0.255	0.265	0.275	0.285	0.295	0.305	0.325	0.345	0.365	0.385	0.405	0.425	0.445
3/16	0.305	0.315	0.325	0.335	0.345	0.355	0.375	0.395	0.415	0.435	0.455	0.475	0.495
7/32	0.354	0.364	0.374	0.384	0.394	0.404	0.424	0.444	0.464	0.484	0.504	0.524	0.544
1/4	0.403	0.413	0.423	0.433	0.443	0.453	0.473	0.493	0.513	0.533	0.553	0.573	0.593
9/32	0.452	0.462	0.472	0.482	0.492	0.502	0.522	0.542	0.562	0.582	0.602	0.622	0.642
5/16	0.501	0.511	0.521	0.531	0.541	0.551	0.571	0.591	0.611	0.631	0.651	0.671	0.691
11/32	0.550	0.560	0.570	0.580	0.590	0.600	0.620	0.640	0.660	0.680	0.700	0.720	0.740
3/8	0.599	0.609	0.619	0.629	0.639	0.649	0.669	0.689	0.709	0.729	0.749	0.769	0.789
13/32	0.648	0.658	0.668	0.678	0.688	0.698	0.718	0.738	0.758	0.778	0.798	0.818	0.838
7/16	0.697	0.707	0.717	0.727	0.737	0.747	0.767	0.787	0.807	0.827	0.847	0.867	0.887
15/32	0.746	0.756	0.766	0.776	0.786	0.796	0.816	0.836	0.856	0.876	0.896	0.916	0.936
1/2	0.795	0.805	0.815	0.825	0.835	0.845	0.865	0.885	0.905	0.925	0.945	0.965	0.985
17/32	0.844	0.854	0.864	0.874	0.884	0.894	0.914	0.934	0.954	0.974	0.994	1.014	1.034
9/16	0.894	0.904	0.914	0.924	0.934	0.944	0.964	0.984	1.004	1.024	1.044	1.064	1.084
5/8	0.992	1.002	1.012	1.022	1.032	1.042	1.062	1.082	1.102	1.122	1.42	1.162	1.182
11/16	1.090	1.100	1.110	1.120	1.130	1.140	1.160	1.180	1.200	1.220	1.240	1.260	1.280
3/4	1.188	1.198	1.208	1.218	1.228	1.238	1.258	1.278	1.298	1.318	1.338	1.358	1.378
13/16	1.286	1.296	1.306	1.316	1.326	1.336	1.356	1.376	1.396	1.416	1.436	1.456	1.476
7/8	1.384	1.394	1.404	1.414	1.424	1.434	1.454	1.474	1.494	1.514	1.534	1.554	1.574
15/16	1.483	1.493	1.503	1.513	1.523	1.553	1.553	1.573	1.693	1.613	1.633	1.653	1.673
1	1.581	1.591	1.601	1.611	1.621	1.631	1.651	1.671	1.691	1.711	1.731	1.751	1.771
1 1/16	1.697	1.689	1.699	1.709	1.719	1.729	1.749	1.769	1.789	1.809	1.829	1.849	1.869
1 1/8	1.777	1.787	1.797	1.807	1.817	1.827	1.847	1.867	1.887	1.907	1.927	1.947	1.967
1 3/16	1.875	1.885	1.895	1.905	1.915	1.925	1.945	1.965	1.985	1.005	2.025	2.045	2.065
1 1/4	1.973	1.983	1.993	1.003	2.013	2.023	2.043	2.063	2.083	2.103	2.123	2.143	2.163

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Lengths of Straight Stock Required for 90-Degree Bends in Hard Copper, Bronze, Cold-Rolled Steel, and Spring Steel

Radius *R* of Bend, Inches	Thickness *T* of Material, Inch												
	1/64	1/32	3/64	1/16	5/64	3/32	1/8	5/32	3/16	7/32	1/4	9/32	5/16
1/32	0.060	0.071	0.082	0.093	0.104	0.116	0.138	0.160	0.182	0.204	0.227	0.249	0.271
3/64	0.085	0.096	0.107	0.118	0.129	0.141	0.163	0.185	0.207	0.229	0.252	0.274	0.296
1/16	0.109	0.120	0.131	0.142	0.153	0.165	0.187	0.209	0.231	0.253	0.276	0.298	0.320
3/32	0.158	0.169	0.180	0.191	0.202	0.214	0.236	0.258	0.280	0.302	0.325	0.347	0.369
1/8	0.207	0.218	0.229	0.240	0.251	0.263	0.285	0.307	0.329	0.351	0.374	0.396	0.418
5/32	0.256	0.267	0.278	0.289	0.300	0.312	0.334	0.356	0.378	0.400	0.423	0.445	0.467
3/16	0.305	0.316	0.327	0.338	0.349	0.361	0.383	0.405	0.427	0.449	0.472	0.494	0.516
7/32	0.355	0.366	0.377	0.388	0.399	0.411	0.433	0.455	0.477	0.499	0.522	0.544	0.566
1/4	0.403	0.414	0.425	0.436	0.447	0.459	0.481	0.503	0.525	0.547	0.570	0.592	0.614
9/32	0.452	0.463	0.474	0.485	0.496	0.508	0.530	0.552	0.574	0.596	0.619	0.641	0.663
5/16	0.501	0.512	0.523	0.534	0.545	0.557	0.579	0.601	0.623	0.645	0.668	0.690	0.712
11/32	0.551	0.562	0.573	0.584	0.595	0.607	0.629	0.651	0.673	0.695	0.718	0.740	0.762
3/8	0.600	0.611	0.622	0.633	0.644	0.656	0.678	0.700	0.722	0.744	0.767	0.789	0.811
13/32	0.648	0.659	0.670	0.681	0.692	0.704	0.726	0.748	0.770	0.792	0.815	0.837	0.859
7/16	0.697	0.708	0.719	0.730	0.741	0.753	0.775	0.797	0.819	0.841	0.864	0.886	0.908
15/32	0.736	0.747	0.758	0.769	0.780	0.792	0.814	0.836	0.858	0.880	0.903	0.925	0.947
1/2	0.796	0.807	0.818	0.829	0.840	0.852	0.874	0.896	0.918	0.940	0.963	0.985	1.007
9/16	0.894	0.905	0.916	0.927	0.938	0.950	0.972	0.994	1.016	1.038	1.061	1.083	1.105
5/8	0.992	1.003	1.014	1.025	1.036	1.048	1.070	1.092	1.114	1.136	1.159	1.181	1.203
11/16	1.091	1.102	1.113	1.124	1.135	1.147	1.169	1.191	1.213	1.235	1.258	1.280	1.302
3/4	1.189	1.200	1.211	1.222	1.233	1.245	1.267	1.289	1.311	1.333	1.356	1.378	1.400
13/16	1.288	1.299	1.310	1.321	1.332	1.344	1.366	1.388	1.410	1.432	1.455	1.477	1.499
7/8	1.386	1.397	1.408	1.419	1.430	1.442	1.464	1.486	1.508	1.530	1.553	1.575	1.597
15/16	1.483	1.494	1.505	1.516	1.527	1.539	1.561	1.583	1.605	1.627	1.650	1.672	1.694
1	1.582	1.593	1.604	1.615	1.626	1.638	1.660	1.682	1.704	1.726	1.749	1.771	1.793
1 1/16	1.680	1.691	1.702	1.713	1.724	1.736	1.758	1.780	1.802	1.824	1.847	1.869	1.891
1 1/8	1.779	1.790	1.801	1.812	1.823	1.835	1.857	1.879	1.901	1.923	1.946	1.968	1.990
1 3/16	1.877	1.888	1.899	1.910	1.921	1.933	1.955	1.977	1.999	2.021	2.044	2.066	2.088
1 1/4	1.974	1.985	1.996	2.007	2.018	2.030	2.052	2.074	2.096	2.118	2.141	2.163	2.185

Copyright 2004, Industrial Press, Inc., New York, NY

For bend at right-hand end (60-degree bend)

$$L = [(0.64 \times 0.125) + (1.57 \times 0.625)] \times \frac{60}{90} = 0.707$$

Total length before bending = 3.5 + 1.338 + 0.707 = 5.545 inches



Fig. 4.



Fig. 5.

Other Bending Allowance Formulas.— When bending sheet steel or brass, add from ⅓ to ½ of the thickness of the stock, for *each bend,* to the sum of the inside dimensions of the finished piece, to get the length of the straight blank. The harder the material the greater the allowance (⅓ of the thickness is added for soft stock and ½ of the thickness for hard material). The data given in the table, *Allowances for Bends in Sheet Metal* on page 1340, refer more particularly to the bending of sheet metal for counters, bank fittings and general office fixtures, for which purpose it is not absolutely essential to have the sections of the bends within very close limits. Absolutely accurate data for this work cannot be deduced, as the stock varies considerably as to hardness, etc. The figures given apply to sheet steel, aluminum, brass and bronze. Experience has demonstrated that for the semisquare corners, such as are formed in a V-die, the amount to be deducted from the sum of the outside bend dimensions, as shown in Fig. 5 by the sum of the letters from *a* to *e*, is as follows: $X = 1.67\,BG$, where X = the amount to be deducted; B = the number of bends; and G = the decimal equivalent of the gage. The values of X for different gages and numbers of bends are given in the table. Its application may be illustrated by an example: A strip having two bends is to have outside dimensions of 2, 1½ and 2 inches, and is made of stock 0.125 inch thick. The sum of the outside dimensions is thus 5½ inches, and from the table the amount to be deducted is found to be 0.416; hence the blank will be 5.5 – 0.416 = 5.084 inches long.

The lower part of the table applies to square bends which are either drawn through a block of steel made to the required shape, or else drawn through rollers in a drawbench. The pressure applied not only gives a much sharper corner, but it also elongates the material more than in the V-die process. In this case, the deduction is $X = 1.33\,BG$.

Joining and Edging

A duct system is an assembly whose main function is to convey air. Elements of the duct system are sheets, transverse joints, longitudinal seams, and reinforcements.The sheets must be able to withstand deflection caused by both internal pressure and vibration due to turbulent air flow. Transverse joints must be able to withstand 1.5 times the maximum operating pressure without failure. Transverse joint designs should be consistent with the static pressure class, sealing requirements, materials involved, and support interval distances. Notching, bending, folding, and fit up tolerances shall be appropriate for the proper class. Longitudinal seams also must be able to withstand 1.5 times the operating pressure without deformation. Seams shall be formed and assembled with proper dimension and proportion for tight and secure fit up. Seams may be a butt, corner, plug, or spot weld design. Seams shall be selected based on material and pressure. A duct section between adjacent hangers must be able to carry its own weight and to resist external loads for which

Copyright 2004, Industrial Press, Inc., New York, NY

Allowances for Bends in Sheet Metal

Square Bends	Gage	Thickness Inches	Amount to be Deducted from the Sum of the Outside Bend Dimensions, Inches						
			1 Bend	2 Bends	3 Bends	4 Bends	5 Bends	6 Bends	7 Bends
Formed in a Press by a V-die	18	0.0500	0.083	0.166	0.250	0.333	0.416	0.500	0.583
	16	0.0625	0.104	0.208	0.312	0.416	0.520	0.625	0.729
	14	0.0781	0.130	0.260	0.390	0.520	0.651	0.781	0.911
	13	0.0937	0.156	0.312	0.468	0.625	0.781	0.937	1.093
	12	0.1093	0.182	0.364	0.546	0.729	0.911	1.093	1.276
	11	0.1250	0.208	0.416	0.625	0.833	1.041	1.250	1.458
	10	0.1406	0.234	0.468	0.703	0.937	1.171	1.406	1.643
Rolled or Drawn in a Draw-bench	18	0.0500	0.066	0.133	0.200	0.266	0.333	0.400	0.466
	16	0.0625	0.083	0.166	0.250	0.333	0.416	0.500	0.583
	14	0.0781	0.104	0.208	0.312	0.416	0.521	0.625	0.729
	13	0.0937	0.125	0.250	0.375	0.500	0.625	0.750	0.875
	12	0.1093	0.145	0.291	0.437	0.583	0.729	0.875	1.020
	11	0.1250	0.166	0.333	0.500	0.666	0.833	1.000	1.166
	10	0.1406	0.187	0.375	0.562	0.750	0.937	1.125	1.312

it is constructed. The reinforcing members must be able to resist the deflection of the sheet, and its own deflection.

There is a relationship between duct width, reinforcement spacing, reinforcement size, pressure, and sheet thickness. For constant pressure and constant duct size, the thicker sheet allows more distance between reinforcements. The higher the pressure the shorter the spacing between reinforcements. Joints and intermediate reinforcements are labor intensive and may be more costly than the savings gained by a reduction in wall thickness. Thicker duct wall and stronger joints are more cost effective than using more reinforcement.

The following material illustrates various joint designs, used both in duct work and other sheet metal asseblies.

Sheet Metal Joints

Plain Lap and Flush Lap:

Fig. 6. Plain Lap



Fig. 7. Flush Lap

The *plain lap* (Fig. 6) and *flush lap* (Fig. 7) are both used for various materials such as galvanized or black iron, copper, stainless steel, aluminum, or other metals, and may be soldered, and/or riveted, as well as spot, tack, or solid-welded. Lap dimensions vary with the particular application, and since it is the duty of the draftsman to specify straight joints in lengths that use full-sheet sizes, transverse lap dimensions must be known.

Raw and Flange Corner:



Fig. 8. Raw and Flange Corner

The *raw and flange corner* (Fig. 8) is generally spot-welded, but may be riveted or soldered. For heavy gages it is tack-welded or solid-welded.

Copyright 2004, Industrial Press, Inc., New York, NY

Flange and Flange Corner:



Fig. 9. Flange and Flange Corner

The *flange and flange corner* (Fig. 9) is a refinement of the raw and flange corner. It is particularly useful for heavy-gage duct sections which require flush outside corners and must be field-erected.

Standing Seam:

Fig. 10. Standing Seam

The *standing seam* (Fig. 10) is often used for large plenums, or casings. Before the draftsman is able to lay out a casing drawing, one of the items of information needed is seam allowance measurements, so that panel sizes can be detailed for economical use of standard sheets. Considering velocity levels, standing seams are considered for duct interiors: 1″ seam is normally applied for duct widths up to 42″, and 1½″ for bigger ducts.

Groove Seam:

Fig. 11. Groove Seam

The *groove seam* (Fig. 11) is often used for rectangular or round duct straight joints, or to join some sheets for fittings that are too large to be cut out from standard sheets. It is also known as the pipelock, or flat lock seam.

Corner Standing Seam:



Fig. 12. Corner Standing Seam

The *corner standing seam* (Fig. 12) has similar usage to the standing seam, and also can be used for straight-duct sections. This type of seams are mostly applied at the ends at 8″ intervals.

Double Seam:



Fig. 13. Double Corner Seam

The *double corner seam* (Fig. 13) at one time was the most commonly used method for duct fitting fabrication. However, although it is seldom used because of the hand operations required for assembly, the double seam can be used advantageously for duct fittings with compound curves. It is called the slide lock seam. Machines are available to automatically close this seam.

Slide-Corner:

Fig. 14. Slide Corner

The *slide-corner* (Fig. 14) is a large version of the double seam. It is often used for field assembly of straight joints, such as in an existing ceiling space, or other restricted working area where ducts must be built in place. To assemble the duct segments, opposite ends of each seam are merely "entered" and then pushed into position. Ducts are sent to job sites "knocked-down" for more efficient use of shipping space.

Button Punch Snap Lock:

Fig. 15. Button Punch Snap Lock

The *button punch snap lock* (Fig. 15) is a flush-type seam which may be soldered or caulked. This seam can be modified slightly for use as a "snap lock". This types of seam is not applicable for aluminum or other soft metals. This seam may be used up to 4″ w.g. by using screws at the ends. The pocket depth should not be smaller than ⅝″ for 20, 22 and 26 gage.

Copyright 2004, Industrial Press, Inc., New York, NY

Pittsburg:



Fig. 16. Pittsburgh

The *Pittsburg* (Fig. 16) is the most commonly used seam for standard gage duct construction. The common pocket depths are 5⁄16″ and 5⁄8″ depending on the thickness of sheet.

Flange:

Fig. 17. Flange

The *flange* (Fig. 17) is an end edge stiffener. The draftsman must indicate size of the flange, direction of bend, degree of bend (if other than 90°) and when full corners are desired. Full corners are generally advisable for collar connections to concrete or masonry wall openings at louvers.

Hem:

Fig. 18. Hem

The *hem edge* (Fig. 18) is a flat, finished edge. As with the flange, this must be designated by the draftsman. For example, drawing should show: 3⁄4″ hem out.

Flat Drive Slip:

Fig. 19. Drive Slip

This is one of the simplest transverse joints. It is applicable where pressure is less than 2″ w.g. This is a slide type connection generally used on small ducts in combination of "S" slips. Service above 2″ inches w.g. is not applicable.

Standing Drive Slip:



Fig. 20. Standing Drive Slip

This is also a slide type connection. It is made by elongating flat drive slip, fasten standing portions 2″ from each end. It is applicable for any length in 2″ w.g, 36″ for 3″ inch w.g., and 30″ inches at 4″ w.g. service.

Flat Drive Slip Reinforced:

Fig. 21. Drive Slip Reinforced

This is the reinforcement on flat drive slip by adding a transverse angle section after a fixed interval.

Double "S" Slip Reinforced:

Fig. 22. Double "S" Slip

The double "S" slip is applied, to eliminate the problem of notching and bending, especially for large ducts. Apply 24 gage sheet for 30″ width or less, 22 gage sheet over 30″ width.

Flat "S" Slip:

Fig. 23. Plain "S" Slip

Normally the "S" slip is used for small ducts. However, it is also useful if the connection of a large duct is tight to a beam, column or other object, and an "S" slip is substituted for the shop standard slip. Service above 2″ inches w.g. is not applicable. Gage shall not be less than 24, and shall not 2 gage less than the duct gage. When it is applied on all four edges, fasten within 2″ of the corners and at 12″ maximum interval.

Copyright 2004, Industrial Press, Inc., New York, NY

Hemmed "S" Slip:

Fig. 24. Hemmed "S" Slip

This is the modified "S" slip, by adding hem and an angle for reinforcing. The hem edge is a flat, and finished edge. Hemmed "S" slip is mostly applied with angle. The drive is generally 16 gage, formed a 1 inch height slip pocket and screws at the end. Notching and bending operations on an "S" slip joints can be cumbersome and costly, especially for large sizes. Tied each section of the duct within 2″ from the corner at maximum 6-inch interval.

Other Types of Duct Connections

Clinch-bar Slip and Flange:

Fig. 25. Clinch-bar Slip and Flange

The *clinch-bar slip and flange* (Fig. 25), uses the principle of the standing seam, but with a duct lap in the direction of airflow. These slips are generally assembled as a framed unit with full corners either riveted or spot-welded, which adds to the duct cross-section rigidity. Reinforcement may be accomplished by spot welding the flat-bar to the flange of the large end. Accessibility to all four sides of the duct is required because the flange of the slip must be folded over the flange on the large end after the ducts are connected.

Clinch-bar Slip and Angle :



Fig. 26. Clinch-bar Slip and Angle

The *clinch bar slip and angle* (Fig. 26), is similar to clinch bar slip (Fig. 25), but it has a riveted or spot-welded angle on the large end. This connection can also have a raw large end which is inserted into the space between the angle and the shop-fabricated slip. Matched angles (minimum of 16 ga) are riveted or spot welded to the smaller sides of the ducts, to pull the connection "home."

Flanged Duct Connections

Angle Frame, or Ring:



Fig. 27. Raw Ends and Matched ∠s

Any of the following flanged connections may have gaskets. The draftsman should not allow for gasket thicknesses in calculations for running length dimensions, nor should he indicate angle sizes, bolt centers, etc., as these items are established in job specifications and approved shop standards. Generally, angles are fastened to the duct sections in the shop. If conditions at the job site require consideration for length contingencies, the draftsman should specify "loose angles" such as at a connection to equipment which may be located later. The most common matched angle connection is the *angle frame*, or *ring* (Fig. 27). The angles are fastened flush to the end of the duct.

Flanged End and Angle:



Fig. 28. Flanged Ends and Matched ∠s

The *flanged end and angle* (Fig. 28), is often used for ducts 16 ga or lighter, as the flange provides a metal-to-metal gasket and holds the angle frame or ring on the duct without additional fastening. The draftsman may indicate in a field note that a round-duct fitting is to be "rotated as required". This type of angle-ring-connection is convenient for such a condition.

Formed Flanges:



Fig. 29. Formed Flanges

Double flanges (Fig. 29), are similar to Fig. 21, except that the connecting flange has a series of matched bolt holes. This connection, caulked airtight, is ideal for single-wall apparatus casings or plenums. The flanges are formed at the ends of the duct, after assembly they will form a T shape. Mating flanges shall be locked together by long clips. In order to form effective seal, gasket is used with suitable density and resiliency. At the corners 16 gage thickness steel corner are used with $\frac{3}{8}$″ diameter bolts.

Copyright 2004, Industrial Press, Inc., New York, NY

Double Flanges and Cleat:



Fig. 30. Double Flanges and Cleat

Double Flanges and Cleat (Fig. 30) is identical to (Fig. 29), but has an air seal cleat. The reinforcements is attached to the duct wall on both sides of the joint.

Clinch-type Flanged Connections:



Fig. 31. Bead Clinch and **Z** Rings

Clinch-type flanged connections for round ducts, 16 ga or lighter, are shown in Fig. 31. The angles or rings can be loose, as explained in *Flanged End and Angle*, (Fig. 28). The draftsman should indicate flange sizes, bend direction, and type of assembly. An example such as the flange lap for a field assembly of a 10-gage casing corner would be written: 1 ½″ flange out square on side with $\frac{9}{32}$″∅ bolt holes 12″ CC. At the beginning and ending angles are connected by rivets or welding. The bolt will be $\frac{5}{16}$″ ∅ at 6″ maximum spacing 4″ w.g..

Fine Blanking

The process called fine blanking uses special presses and tooling to produce flat components from sheet metal or plate, with high dimensional accuracy. According to Hydrel A. G., Romanshorn, Switzerland, fine-blanking presses can be powered hydraulically or mechanically, or by a combination of these methods, but they must have three separate and distinct movements. These movements serve to clamp the work material, to perform the blanking operation, and to eject the finished part from the tool. Forces of 1.5–2.5 times those used in conventional stamping are needed for fine blanking, so machines and tools must be designed and constructed accordingly. In mechanical fine-blanking presses the clamping and ejection forces are exerted hydraulically. Such presses generally are of toggle-type design and are limited to total forces of up to about 280 tons. Higher forces generally require all-hydraulic designs. These presses are also suited to embossing, coining, and impact extrusion work.

Cutting elements of tooling for fine blanking generally are made from 12 per cent chromium steel, although high speed steel and tungsten carbide also are used for long runs or improved quality. Cutting clearances between the intermediate punch and die are usually held between 0.0001 and 0.0003 in. The clamping elements are sharp projections of 90-degree V-section that follow the outline of the workpiece and that are incorporated into each tool as part of the stripper plate with thin material and also as part of the die plate when material thicker than 0.15 in. is to be blanked. Pressure applied to the elements containing the V-projections prior to the blanking operation causes the sharp edges to enter the material surface, preventing sideways movement of the blank. The pressure applied as the projections bite into the work surface near the contour edges also squeezes the material, causing it to flow toward the cutting edges, reducing the usual rounding effect at the cut edge. When small details such as gear teeth are to be produced, V-projections are often used on both sides of the work, even with thin materials, to enhance the flow effect. With suitable tooling, workpieces can be produced with edges that are perpendicular to top and bottom surfaces within 0.004 in. on thicknesses of 0.2 in., for instance. V-projection dimensions for various material thicknesses are shown in the table *Dimensions for V-projections Used in Fine-Blanking Tools*.

Fine-blanked edges are free from the fractures that result from conventional tooling, and can have surface finishes down to 80 µin. Ra with suitable tooling. Close tolerances can be

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions for V-projections Used in Fine-Blanking Tools



V-Projections On Stripper Plate Only



V-Projections On Both Stripper and Die Plate

Material Thickness	*A*	*h*	*r*	*H*	*R*
V-Projections On Stripper Plate Only					
0.040-0.063	0.040	0.012	0.008	…	…
0.063-0.098	0.055	0.015	0.008	…	…
0.098-0.125	0.083	0.024	0.012	…	…
0.125-0.157	0.098	0.028	0.012	…	…
0.157-0.197	0.110	0.032	0.012	…	…
V-Projections On Both Stripper and Die Plate					
0.157–0.197	0.098	0.020	0.008	0.032	0.032
0.197–0.248	0.118	0.028	0.008	0.040	0.040
0.248–0.315	0.138	0.032	0.008	0.047	0.047
0.315–0.394	0.177	0.040	0.020	0.060	0.060
0.394–0.492	0.217	0.047	0.020	0.070	0.080
0.492–0.630	0.276	0.063	0.020	0.087	0.118

All units are in inches.

held on inner and outer forms, and on hole center distances. Flatness of fine-blanked components is better than that of parts made by conventional methods, but distortion may occur with thin materials due to release of internal stresses. Widths must be slightly greater than are required for conventional press working. Generally, the strip width must be 2–3 times the thickness, plus the width of the part measured transverse to the feed direction. Other factors to be considered are shape, material quality, size and shape of the V-projection in relation to the die outline, and spacing between adjacent blanked parts. Holes and slots can be produced with ratios of width to material thickness down to 0.7, compared with the 1:1 ratio normally specified for conventional tooling. Operations such as countersinking, coining, and bending up to 60 degrees can be incorporated in fine-blanking tooling.

The cutting force in lb exerted in fine blanking is 0.9 times the length of the cut in inches times the material thickness in inches, times the tensile strength in $lb_f/in.^2$. Pressure in lb exerted by the clamping element(s) carrying the V-projections is calculated by multiplying the length of the V-projection, which depends on its shape, in inches by its height (h), times the material tensile strength in $lb_f/in.^2$, times an empirical factor f. Factor f has been determined to be 2.4–4.4 for a tensile strength of 28,000–113,000 $lb_f/in.^2$. The clamping pressure is approximately 30 per cent of the cutting force, calculated as above. Dimensions and positioning of the V-projection(s) are related to the material thickness, quality, and tensile strength. A small V-projection close to the line of cut has about the same effect as a large V-projection spaced away from the cut. However, if the V-projection is too close to the cut, it may move out of the material at the start of the cutting process, reducing its effectiveness.

Copyright 2004, Industrial Press, Inc., New York, NY

Positioning the V-projection at a distance from the line of cut increases both material and blanking force requirements. Location of the V-projection relative to the line of cut also affects tool life.

Steel Rule Dies

Steel rule dies (or knife dies) were patented by Robert Gair in 1879, and, as the name implies, have cutting edges made from steel strips of about the same proportions as the steel strips used in making graduated rules for measuring purposes. According to J. A. Richards, Sr., of the J. A. Richards Co., Kalamazoo, MI, a pioneer in the field, these dies were first used in the printing and shoemaking industries for cutting out shapes in paper, cardboard, leather, rubber, cork, felt, and similar soft materials. Steel rule dies were later adopted for cutting upholstery material for the automotive and other industries, and for cutting out simple to intricate shapes in sheet metal, including copper, brass, and aluminum. A typical steel rule die, partially cut away to show the construction, is shown in Fig. 1, and is designed for cutting a simple circular shape. Such dies generally cost 25 to 35 per cent of the cost of conventional blanking dies, and can be produced in much less time. The die shown also cuts a rectangular opening in the workpiece, and pierces four holes, all in one press stroke.



Fig. 1. Steel Rule Die for Cutting a Circular Shape, Sectioned to Show the Construction

The die blocks that hold the steel strips on edge on the press platen or in the die set may be made from plaster, hot lead or type metal, or epoxy resin, all of which can be poured to shape. However, the material most widely used for light work is ¾-in. thick, five- or seven-ply maple or birch wood. Narrow slots are cut in this wood with a jig saw to hold the strips vertically. Where greater forces are involved, as with operations on metal sheets, the blocks usually are made from Lignostone densified wood or from metal. In the ¾-in. thickness mostly used, medium- and high-density grades of Lignostone are available. The ¾-in. thickness is made from about 35 plies of highly compressed lignite wood, bonded with

Copyright 2004, Industrial Press, Inc., New York, NY

phenolformaldehyde resin, which imparts great density and strength. The material is made in thicknesses up to 6 in., and in various widths and lengths.

Steel rule die blocks can carry punches of various shapes to pierce holes in the stock, also projections designed to form strengthening ribs and other shapes in material such as aluminum, at the same time as the die cuts the component to shape. Several dies can be combined or nested, and operated together in a large press, to produce various shapes simultaneously from one sheet of material.

As shown in Fig. 1, the die steel is held in the die block slot on its edge, usually against the flat platen of a die set attached to the moving slide of the press. The sharp, free end of the rule faces toward the workpiece, which is supported by the face of the other die half. This other die half may be flat or may have a punch attached to it, as shown, and it withstands the pressure exerted in the cutting or forming action when the press is operated. The closed height of the die is adjusted to permit the cutting edge to penetrate into the material to the extent needed, or, if there is a punch, to carry the cutting edges just past the punch edges for the cutting operation. After the sharp edge has penetrated it, the material often clings to the sides of the knife. Ejector inserts made from rubber, combinations of cork and rubber, and specially compounded plastics material, or purpose-made ejectors, either spring- or positively actuated, are installed in various positions alongside the steel rules and the punch. These ejectors are compressed as the dies close, and when the dies open, they expand, pushing the material clear of the knives or the punch.

The cutting edges of the steel rules can be of several shapes, as shown in profile in Fig. 2, to suit the material to be cut, or the type of cutting operation. Shape *A* is used for shearing in the punch in making tools for blanking and piercing operations, the sharp edge later being modified to a flat, producing a 90° cutting edge, *B*. The other shapes in Fig. 2 are used for cutting various soft materials that are pressed against a flat surface for cutting. The shape at *C* is used for thin, and the shape at *D* for thicker materials.



Fig. 2. Cutting Edges for Steel Rule Dies

Steel rule die steel is supplied in lengths of 30 and 50 in., or in coils of any length, with the edges ground to the desired shape, and heat treated, ready for use. The rule material width is usually referred to as the height, and material can be obtained in heights of 0.95, 1, 1⅛, 1¼, and 1½ in. Rules are available in thicknesses of 0.055, 0.083, 0.11, 0.138, 0.166, and 0.25 in. (4 to 18 points in printers' measure of 72 points = 1 in.). Generally, stock thicknesses of 0.138 or 0.166 in. (10 and 12 points) are preferred, the thinner rules being used mainly for dies requiring intricate outlines. The stock can be obtained in soft or hard temper. The standard edge bevel is 46°, but bevels of 40 to 50° can be used. Thinner rule stock is easiest to form to shape and is often used for short runs of 50 pieces or thereabouts. The thickness and hardness of the material to be blanked also must be considered when choosing rule thickness.

Making of Steel Rule Dies.— Die making begins with a drawing of the shape required. Saw cutting lines may be marked directly on the face of the die block in a conventional layout procedure using a height gage, or a paper drawing may be pasted to or drawn on the die

Copyright 2004, Industrial Press, Inc., New York, NY

board. Because paper stretches and shrinks, Mylar or other nonshrink plastics sheets may be preferred for the drawing. A hole is drilled off the line to allow a jig saw to be inserted, and jig saw or circular saw cuts are then made under manual control along the drawing lines to produce the slots for the rules. Jig saw blades are available in a range of sizes to suit various thicknesses of rule and for sawing medium-density Lignostone, a speed of 300 strokes/min is recommended, the saw having a stroke of about 2 in. To make sure the rule thickness to be used will be a tight fit in the slot, trials are usually carried out on scrap pieces of die block before cuts are made on a new block.

During slot cutting, the saw blade must always be maintained vertical to the board being cut, and magnifying lenses are often used to keep the blade close to the line. Carbide or carbide-tipped saw blades are recommended for clean cuts as well as for long life. To keep any "islands" (such as the center of a circle) in position, various places in the sawn line are cut to less than full depth for lengths of $\frac{1}{4}$ to $\frac{1}{2}$ in., and to heights of $\frac{5}{8}$ to $\frac{3}{4}$ in. to bridge the gaps. Slots of suitable proportions must be provided in the steel rules, on the sides away from the cutting edges, to accommodate these die block bridges.

Rules for steel rule dies are bent to shape to fit the contours called for on the drawing by means of small, purpose-built bending machines, fitted with suitable tooling. For bends of small radius, the tooling on these machines is arranged to perform a peening or hammering action to force the steel rule into close contact with the radius-forming component of the machine so that quite small radii, as required for jig saw puzzles, for instance, can be produced with good accuracy. Some forms are best made in two or more pieces, then joined by welding or brazing. The edges to be joined are mitered for a perfect fit, and are clamped securely in place for joining. Electrical resistance or a gas heating torch is used to heat the joint. Wet rags are applied to the steel at each side of the joint to keep the material cool and the hardness at the preset level, as long as possible.

When shapes are to be blanked from sheet metal, the steel rule die is arranged with flat, 90° edges (*B*, in Fig. 2), which cut by pushing the work past a close-fitting counter-punch. This counterpunch, shown in Fig. 1, may be simply a pad of steel or other material, and has an outline corresponding to the shape of the part to be cut. Sometimes the pad may be given a gradual, slight reduction in height to provide a shearing action as the moving tool pushes the work material past the pad edges. As shown in Fig. 1, punches can be incorporated in the die to pierce holes, cut slots, or form ribs and other details during the blanking operation. These punches are preferably made from high-carbon, high-vanadium, alloy steel, heat treated to Rc 61 to 63, with the head end tempered to Rc 45 to 50.

Heat treatment of the high-carbon-steel rules is designed to produce a hardness suited to the application. Rules in dies for cutting cartons and similar purposes, with mostly straight cuts, are hardened to Rc 51 to 58. For dies requiring many intricate bends, lower-carbon material is used, and is hardened to Rc 38 to 45. And for dies to cut very intricate shapes, a steel in dead-soft condition with hardness of about Rb 95 is recommended. After the intricate bends are made, this steel must be carburized before it is hardened and tempered. For this material, heat treatment uses an automatic cycle furnace, and consists of carburizing in a liquid compound heated to 1500°F and quenching in oil, followed by "tough" tempering at 550°F and cooling in the furnace.

After the hardened rule has been reinstalled in the die block, the tool is loaded into the press and the sharp die is used with care to shear the sides of the pad to match the die contours exactly. A close fit, with clearances of about half those used in conventional blanking dies, is thus ensured between the steel rule and the punch. Adjustments to the clearances can be made at this point by grinding the die steel or the punch. After the adjustment work is done, the sharp edges of the rule steel are ground flat to produce a land of about $\frac{1}{64}$ in. wide (*A* in Fig. 2), for the working edges of the die. Clearances for piercing punches should be similar to those used on conventional piercing dies.

Copyright 2004, Industrial Press, Inc., New York, NY

ELECTRICAL DISCHARGE MACHINING

Generally called EDM, electrical discharge machining uses an electrode to remove metal from a workpiece by generating electric sparks between conducting surfaces. The two main types of EDM are termed sinker or plunge, used for making mold or die cavities, and wire, used to cut shapes such as are needed for stamping dies. For die sinking, the electrode usually is made from copper or graphite and is shaped as a positive replica of the shape to be formed on or in the workpiece. A typical EDM sinker machine, shown diagrammatically in Fig. 1, resembles a vertical milling machine, with the electrode attached to the vertical slide. The slide is moved down and up by an electronic, servo-controlled drive unit that controls the spacing between the electrode and the workpiece on the table. The table can be adjusted in three directions, often under numerical control, to positions that bring a workpiece surface to within 0.0005 to 0.030 in. from the electrode surface, where a spark is generated.



Fig. 1. Sinker or Plunge Type EDM Machines Are Used to Sink Cavities in Molds and Dies



Fig. 2. Wire Type EDM Machines Are Used to Cut Stamping Die Profiles.

Wire EDM, shown diagrammatically in Fig. 2, are numerically controlled and somewhat resemble a bandsaw with the saw blade replaced by a fine brass or copper wire, which forms the electrode. This wire is wound off one reel, passed through tensioning and guide rollers, then through the workpiece and through lower guide rollers before being wound onto another reel for storage and eventual recycling. One set of guide rollers, usually the lower, can be moved on two axes at 90 degrees apart under numerical control to adjust the angle of the wire when profiles of varying angles are to be produced. The table also is movable in two directions under numerical control to adjust the position of the workpiece relative to the wire. Provision must be made for the cut-out part to be supported when it is freed from the workpiece so that it does not pinch and break the wire.

EDM applied to grinding machines is termed EDG. The process uses a graphite wheel as an electrode, and wheels can be up to 12 in. in diameter by 6 in. wide. The wheel periphery is dressed to the profile required on the workpiece and the wheel profile can then be transferred to the workpiece as it is traversed past the wheel, which rotates but does not touch the work. EDG machines are highly specialized and are mainly used for producing complex profiles on polycrystaline diamond cutting tools and for shaping carbide tooling such as form tools, thread chasers, dies, and crushing rolls.

EDM Terms*.— *Anode:* The positive terminal of an electrolytic cell or battery. In EDM, incorrectly applied to the tool or electrode.

* *Source:* Hansvedt Industries

Copyright 2004, Industrial Press, Inc., New York, NY

Barrel effect: In wire EDM, a condition where the center of the cut is wider than the entry and exit points of the wire, due to secondary discharges caused by particles being pushed to the center by flushing pressure from above and beneath the workpiece.

Capacitor: An electrical component that stores an electric charge. In some EDM power supplies, several capacitors are connected across the machining gap and the current for the spark comes directly from the capacitors when they are discharged.

Cathode: The negative terminal in an electrolytic cell or battery. In EDM incorrectly applied to the workpiece.

Colloidal suspension: Particles suspended in a liquid that are too fine to settle out. In EDM, the tiny particles produced in the sparking action form a colloidal suspension in the dielectric fluid.

Craters: Small cavities left on an EDM surface by the sparking action, also known as pits.

Dielectric filter : A filter that removes particles from 5 μm (0.00020 in.) down to as fine as 1 μm (0.00004 in) in size, from dielectric fluid.

Dielectric fluid : The non-conductive fluid that circulates between the electrode and the workpiece to provide the dielectric strength across which an arc can occur, to act as a coolant to solidify particles melted by the arc, and to flush away the solidified particles.

Dielectric strength: In EDM, the electrical potential (voltage) needed to break down (ionize) the dielectric fluid in the gap between the electrode and the workpiece.

Discharge channel: The conductive pathway formed by ionized dielectric and vapor between the electrode and the workpiece.

Dither: A slight up and down movement of the machine ram and attached electrode, used to improve cutting stability.

Duty cycle: The percentage of a pulse cycle during which the current is turned on (on time), relative to the total duration of the cycle.

EDG: Electrical discharge grinding using a machine that resembles a surface grinder but has a wheel made from electrode material. Metal is removed by an EDM process rather than by grinding.

Electrode growth: A plating action that occurs at certain low-power settings, whereby workpiece material builds up on the electrode, causing an increase in size.

Electrode wear: Amount of material removed from the electrode during the EDM process. This removal can be end wear or corner wear, and is measured linearly or volumetrically but is most often expressed as end wear per cent, measured linearly.

Electro-forming: An electro-plating process used to make metal EDM electrodes.

Energy: Measured in joules, is the equivalent of volt-coulombs or volt-ampere- seconds.

Farad: Unit of electrical capacitance, or the energy-storing capacity of a capacitor.

Gap: The closest point between the electrode and the workpiece where an electrical discharge will occur. (See *Overcut*)

Gap current: The average amperage flowing across the machining gap.

Gap voltage: The voltage across the gap while current is flowing. The voltage across the electrode/workpiece before current flows is called the open gap voltage. Heat-affected zone. The layer below the recast layer, which has been subjected to elevated temperatures that have altered the properties of the workpiece metal.

Ion: An atom or group of atoms that has lost or gained one or more electrons and is therefore carrying a positive or negative electrical charge, and is described as being ionized.

Ionization: The change in the dielectric fluid that is subjected to a voltage potential whereby it becomes electrically conductive, allowing it to conduct the arc.

Low-wear: An EDM process in which the volume of electrode wear is between 2 and 15 per cent of the volume of workpiece wear. Normal negative polarity wear ratios are 15 to 40 per cent.

Negative electrode: The electrode voltage potential is negative relative to the workpiece.

No-wear: An EDM process in which electrode wear is virtually eliminated and the wear ratio is usually less than 2 per cent by volume.

Copyright 2004, Industrial Press, Inc., New York, NY

Orbit: A programmable motion between the electrode and the workpiece, produced by a feature built in to the machine, or an accessory, that produces a cavity or hole larger than the electrode. The path can be planetary (circular), vectorial, or polygonal (trace). These motions can often be performed in sequence, and combined with x-axis movement of the electrode.

Overcut: The distance between one side of an electrode and the adjacent wall of the workpiece cavity.

Overcut taper: The difference between the overcut dimensions at the top (entrance) and at the bottom of the cavity.

Plasma: A superheated, highly ionized gas that forms in the discharge channel due to the applied voltage.

Positive electrode: The electrode voltage potential is positive with respect to the workpiece. is the opposite of this condition.

Power parameters: A set of power supply, servo, electrode material, workpiece material, and flushing settings that are selected to produce a desired metal removal rate and surface finish.

Quench: The rapid cooling of the EDM surface by the dielectric fluid, which is partially responsible for metallurgical changes in the recast layer and in the heat- affected zone.

Recast layer: A layer created by the solidification of molten metal on the workpiece surface after it has been melted by the EDM process.

Secondary discharge: A discharge that occurs as conductive particles are carried out along the side of the electrode by the dielectric fluid.

Spark in: A method of locating an electrode with respect to the workpiece, using high frequency, low amperage settings so that there is no cutting action. The electrode is advanced toward the workpiece until contact is indicated and this point is used as the basis for setting up the job.

Spark out: A technique used in orbiting, which moves the electrode in the same path until sparking ceases.

Square wave: An electrical wave shape generated by a solid state power supply.

Stroke: The distance the ram travels under servo control.

UV axis: A mechanism that provides for movement of the upper head of a wire EDM machine to allow inclined surfaces to be generated.

White layer: The surface layer of an EDM cut that is affected by the heat generated during the process. The characteristics of the layer depend on the material, and may be extremely hard martensite or an annealed layer.

Wire EDM: An EDM machine or process in which the electrode is a continuously unspooling, conducting wire that moves in preset patterns in relation to the workpiece.

Wire guide: A replaceable precision round diamond insert, sized to match the wire, that guides the wire at the entrance and exit points of a wire cut.

Wire speed: The rate at which the wire is fed axially through the workpiece (not the rate at which cutting takes place), adjusted so that clean wire is maintained in the cut but slow enough to minimize waste.

The EDM Process.— During the EDM process, energy from the sparks created between the electrode and the workpiece is dissipated by the melting and vaporizing of the workpiece material preferentially, only small amounts of material being lost from the electrode. When current starts to flow between the electrode and the work, the dielectric fluid in the small area in which the gap is smallest, and in which the spark will occur, is transformed into a plasma of hydrogen, carbon, and various oxides. This plasma forms a conducting passageway, consisting of ionized or electrically charged particles, through which the spark can form between the electrode and the workpiece. After current starts to flow, to heat and vaporize a tiny area, the striking voltage is reached, the voltage drops, and the field of ionized particles loses its energy, so that the spark can no longer be sustained. As the voltage then begins to rise again with the increase in resistance, the electrical supply is

Copyright 2004, Industrial Press, Inc., New York, NY

cut off by the control, causing the plasma to implode and creating a low-pressure pulse that draws in dielectric fluid to flush away metallic debris and cool the impinged area. Such a cycle typically lasts a few microseconds (millionths of a second, or μs), and is repeated continuously in various places on the workpiece as the electrode is moved into the work by the control system.

Flushing: An insulating dielectric fluid is made to flow in the space between the workpiece and the electrode to prevent premature spark discharge, cool the workpiece and the electrode, and flush away the debris. For sinker machines, this fluid is paraffin, kerosene, or a silicon-based dielectric fluid, and for wire machines, the dielectric fluid is usually deionized water. The dielectric fluid can be cooled in a heat exchanger to prevent it from rising above about 100°F, at which cooling efficiency may be reduced. The fluid must also be filtered to remove workpiece particles that would prevent efficient flushing of the spark gaps. Care must be taken to avoid the possibility of entrapment of gases generated by sparking. These gases may explode, causing danger to life, breaking a valuable electrode or workpiece, or causing a fire.

Flushing away of particles generated during the process is vital to successful EDM operations. A secondary consideration is the heat transferred to the side walls of a cavity, which may cause the workpiece material to expand and close in around the electrode, leading to formation of dc arcs where conductive particles are trapped. Flushing can be done by forcing the fluid to pass through the spark gap under pressure, by sucking it through the gap, or by directing a side nozzle to move the fluid in the tank surrounding the workpiece. In pressure flushing, fluid is usually pumped through strategically placed holes in the electrode or in the workpiece. Vacuum flushing is used when side walls must be accurately formed and straight, and is seldom needed on numerically controlled machines because the table can be programmed to move the workpiece sideways.

Flushing needs careful consideration because of the forces involved, especially where fluid is pumped or sucked through narrow passageways, and large hydraulic forces can easily be generated. Excessively high pressures can lead to displacement of the electrode, the workpiece, or both, causing inaccuracy in the finished product. Many low-pressure flushing holes are preferable to a few high-pressure holes. Pressure-relief valves in the system are recommended.

Electronic Controls: The electrical circuit that produces the sparks between the electrode and the workpiece is controlled electronically, the length of the extremely short on and off periods being matched by the operator or the programmer to the materials of the electrode and the workpiece, the dielectric, the rate of flushing, the speed of metal removal, and the quality of surface finish required. The average current flowing between the electrode and the workpiece is shown on an ammeter on the power source, and is the determining factor in machining time for a specific operation. The average spark gap voltage is shown on a voltmeter.

EDM machines can incorporate provision for orbiting the electrode so that flushing is easier, and cutting is faster and increased on one side. Numerical control can also be used to move the workpiece in relation to the electrode with the same results. Numerical control can also be used for checking dimensions and changing electrodes when necessary. The clearance on all sides between the electrode and the workpiece, after the machining operation, is called the overcut or overburn. The overcut becomes greater with increases in the on time, the spark energy, or the amperage applied, but its size is little affected by voltage changes. Allowances must be made for overcut in the dimensioning of electrodes. Sidewall encroachment and secondary discharge can take up parts of these allowances, and electrodes must always be made smaller to avoid making a cavity or hole too large.

Polarity: Polarity can affect processing speed, finish, wear, and stability of the EDM operation. On sinker machines, the electrode is generally, made positive to protect the electrode from excessive wear and preserve its dimensional accuracy. This arrangement

Copyright 2004, Industrial Press, Inc., New York, NY

removes metal at a slower rate than electrode negative, which is mostly used for high-speed metal removal with graphite electrodes. Negative polarity is also used for machining carbides, titanium, and refractory alloys using metallic electrodes. Metal removal with graphite electrodes can be as much as 50 per cent faster with electrode negative polarity than with electrode positive, but negative polarity results in much faster electrode wear, so it is generally restricted to electrode shapes that can be redressed easily.

Newer generators can provide less than 1 per cent wear with either copper or graphite electrodes during roughing operations. Roughing is typically done with a positive-polarity electrode using elevated on times. Some electrodes, particularly micrograin graphites, have a high resistance to wear. Fine-grain, high-density graphites provide better wear characteristics than coarser, less dense grades, and copper-tungsten resists wear better than pure copper electrodes.

Machine Settings: For vertical machines, a rule of thumb for power selection on graphite and copper electrodes is 50 to 65 amps per square inch of electrode engagement. For example, an electrode that is ½ in. square might use $0.5 \times 0.5 \times 50 = 12.5$ amps. Although each square inch of electrode surface may be able to withstand higher currents, lower settings should be used with very large jobs or the workpiece may become overheated and it may be difficult to clean up the recast layer. Lower amperage settings are required for electrodes that are thin or have sharp details. The voltage applied across the arc gap between the electrode and the workpiece is ideally about 35 volts, but should be as small as possible to maintain stability of the process.

Spark Frequency: Spark frequency is the number of times per second that the current is switched on and off. Higher frequencies are used for finishing operations and for work on cemented carbide, titanium, and copper alloys. The frequency of sparking affects the surface finish produced, low frequencies being used with large spark gaps for rapid metal removal with a rough finish, and higher frequencies with small gaps for finer finishes. High frequency usually increases, and low frequency reduces electrode wear.

The Duty Cycle: Electronic units on modern EDM machines provide extremely close control of each stage in the sparking cycle, down to millionths of a second (μs). A typical EDM cycle might last 100 μs. Of this time, the current might be on for 40 μs and off for 60 μs. The relationship between the lengths of the on and off times is called the duty cycle and it indicates the degree of efficiency of the operation. The duty cycle states the on time as a percentage of the total cycle time and in the previous example it is 40 per cent. Although reducing the off time will increase the duty cycle, factors such as flushing efficiency, electrode and workpiece material, and dielectric condition control the minimum off time. Some EDM units incorporate sensors and fuzzy logic circuits that provide for adaptive control of cutting conditions for unattended operation. Efficiency is also reported as the amount of metal removed, expressed as $in.^3/hr$.

In the EDM process, work is done only during the on time, and the longer the on time, the more material is removed in each sparking cycle. Roughing operations use extended on time for high metal-removal rates, resulting in fewer cycles per second, or lower frequency. The resulting craters are broader and deeper so that the surface is rougher and the heat-affected zone (HAZ) on the workpiece is deeper. With positively charged electrodes, the spark moves from the electrode toward the workpiece and the maximum material is removed from the workpiece. However, every spark takes a minute particle from the electrode so that the electrode also is worn away. Finishing electrodes tend to wear much faster than roughing electrodes because more sparks are generated in unit time.

The part of the cycle needed for reionizing the dielectric (the off time) greatly affects the operating speed. Although increasing the off time slows the process, longer off times can increase stability by providing more time for the ejected material to be swept away by the flow of the dielectric fluid, and for deionization of the fluid, so that erratic cycling of the servo-mechanisms that advance and retract the electrode is avoided. In any vertical EDM

Copyright 2004, Industrial Press, Inc., New York, NY

operation, if the overcut, wear, and finish are satisfactory, machining speed can best be adjusted by slowly decreasing the off time setting in small increments of 1 to 5 μs until machining becomes erratic, then returning to the previous stable setting. As the off time is decreased, the machining gap or gap voltage will slowly fall and the working current will rise. The gap voltage should not be allowed to drop below 35 to 40 volts.

Metal Removal Rates (MRR): Amounts of metal removed in any EDM process depend largely on the length of the on time, the energy/spark, and the number of sparks/second. The following data were provided by Poco Graphite, Inc., in their *EDM Technical Manual*. For a typical roughing operation using electrode positive polarity on high-carbon steel, a 67 per cent duty cycle removed 0.28 in.^{3}/hr. For the same material, a 50 per cent duty cycle removed 0.15 in.^{3}/hr, and a 33 per cent duty cycle for finishing removed 0.075 in.^{3}/hr.

In another example, shown in the top data row in Table 1, a 40 per cent duty cycle with a frequency of 10 kHz and peak current of 50 amps was run for 5 minutes of cutting time. Metal was removed at the rate of 0.8 in.^{3}/hr with electrode wear of 2.5 per cent and a surface finish of 400 μin. R_a. When the on and off times in this cycle were halved, as shown in the second data row in Table 1, the duty cycle remained at 40 per cent, but the frequency doubled to 20 kHz. The result was that the peak current remained unaltered, but with only half the on time the MRR was reduced to 0.7 in.^{3}/hr, the electrode wear increased to 6.3 per cent, and the surface finish improved to 300 μin. R_a. The third and fourth rows in Table 1 show other variations in the basic cycle and the results.

Table 1. Effect of Electrical Control Adjustments on EDM Operations

On Time (μs)	Off Time (μs)	Frequency (kHz)	Peak Current (Amps)	Metal Removal Rate (in.^{3}/hr)	Electrode Wear (%)	Surface Finish (μ in. R_a)
40	60	10	50	0.08	2.5	400
20	30	20	50	0.7	6.3	300
40	10	20	50	1.2	1.4	430
40	60	10	25	0.28	2.5	350

The Recast Layer: One drawback of the EDM process when used for steel is the recast layer, which is created wherever sparking occurs. The oil used as a dielectric fluid causes the EDM operation to become a random heat-treatment process in which the metal surface is heated to a very high temperature, then quenched in oil. The heat breaks down the oil into hydrocarbons, tars, and resins, and the molten metal draws out the carbon atoms and traps them in the resolidified metal to form the very thin, hard, brittle surface called the recast layer that covers the heat-affected zone (HAZ). This recast layer has a white appearance and consists of particles of material that have been melted by the sparks, enriched with carbon, and drawn back to the surface or retained by surface tension. The recast layer is harder than the parent metal and can be as hard as glass, and must be reduced or removed by vapor blasting with glass beads, polishing, electrochemical or abrasive flow machining, after the shaping process is completed, to avoid cracking or flaking of surface layers that may cause failure of the part in service.

Beneath the thin recast layer, the HAZ, in steel, consists of martensite that usually has been hardened by the heating and cooling sequences coupled with the heat-sink cooling effect of a thick steel workpiece. This martensite is hard and its rates of expansion and contraction are different from those of the parent metal. If the workpiece is subjected to heating and cooling cycles in use, the two layers are constantly stressed and these stresses may cause formation of surface cracks. The HAZ is usually much deeper in a workpiece cut on a sinker than on a wire machine, especially after roughing, because of the increased heating effect caused by the higher amounts of energy applied.

Copyright 2004, Industrial Press, Inc., New York, NY

The depth of the HAZ depends on the amperage and the length of the on time, increasing as these values increase, to about 0.012 to 0.015 in. deep. Residual stress in the HAZ can range up to 650 N/mm^2. The HAZ cannot be removed easily, so it is best avoided by programming the series of cuts taken on the machine so that most of the HAZ produced by one cut is removed by the following cut. If time is available, cut depth can be reduced gradually until the finishing cuts produce an HAZ having a thickness of less than 0.0001 in.

Workpiece Materials.— Most homogeneous materials used in metalworking can be shaped by the EDM process. Some data on typical workpiece materials are given in Table 2. Sintered materials present some difficulties caused by the use of a cobalt or other binder used to hold the carbide or other particles in the matrix. The binder usually melts at a lower temperature than the tungsten, molybdenum, titanium, or other carbides, so it is preferentially removed by the sparking sequence and the carbide particles are thus loosened and freed from the matrix. The structures of sintered materials based on tungsten, cobalt, and molybdenum require higher EDM frequencies with very short on times, so that there is less danger of excessive heat buildup, leading to melting. Copper-tungsten electrodes are recommended for EDM of tungsten carbides. When used with high frequencies for powdered metals, graphite electrodes often suffer from excessive wear.

Workpieces of aluminum, brass, and copper should be processed with metallic electrodes of low melting points such as copper or copper-tungsten. Workpieces of carbon and stainless steel that have high melting points should be processed with graphite electrodes. The melting points and specific gravities of the electrode material and of the workpiece should preferably be similar.

Table 2. Characteristics of Common Workpiece Materials for EDM

Material	Specific Gravity	Melting Point °F	Melting Point °C	Vaporization Temperature °F	Vaporization Temperature °C	Conductivity (Silver = 100)
Aluminum	2.70	1220	660	4442	2450	63.00
Brass	8.40	1710	930	…		…
Cobalt	8.71	2696	1480	5520	2900	16.93
Copper	8.89	1980	1082	4710	2595	97.61
Graphite	2.07	N/A		6330	3500	70.00
Inconel	…	2350	1285	…		…
Magnesium	1.83	1202	650	2025	1110	39.40
Manganese	7.30	2300	1260	3870	2150	15.75
Molybdenum	10.20	4748	2620	10,040	5560	17.60
Nickel	8.80	2651	1455	4900	2730	12.89
Carbon Steel	7.80	2500	1371	…		12.00
Tool Steel	…	2730	1500	…		…
Stainless Steel	…	2750	1510	…		…
Titanium	4.50	3200	1700	5900	3260	13.73
Tungsten	18.85	6098	3370	10,670	5930	14.00
Zinc	6.40	790	420	1663	906	26.00

Electrode Materials.— Most EDM electrodes are made from graphite, which provides a much superior rate of metal removal than copper because of the ability of graphite to resist thermal damage. Graphite has a density of 1.55 to 1.85 g/cm^3, lower than most metals. Instead of melting when heated, graphite sublimates, that is, it changes directly from a solid to a gas without passing through the liquid stage. Sublimation of graphite occurs at a temperature of 3350°C (6062°F). EDM graphite is made by sintering a compressed mixture of fine graphite powder (1 to 100 micron particle size) and coal tar pitch in a furnace. The open structure of graphite means that it is eroded more rapidly than metal in the EDM process. The electrode surface is also reproduced on the surface of the workpiece. The sizes of individual surface recesses may be reduced during sparking when the work is moved under numerical control of workpiece table movements.

Copyright 2004, Industrial Press, Inc., New York, NY

The fine grain sizes and high densities of graphite materials that are specially made for high-quality EDM finishing provide high wear resistance, better finish, and good reproduction of fine details, but these fine grades cost more than graphite of larger grain sizes and lower densities. Premium grades of graphite cost up to five times as much as the least expensive and about three times as much as copper, but the extra cost often can be justified by savings during machining or shaping of the electrode.

Graphite has a high resistance to heat and wear at lower frequencies, but will wear more rapidly when used with high frequencies or with negative polarity. Infiltrated graphites for EDM electrodes are also available as a mixture of copper particles in a graphite matrix, for applications where good machinability of the electrode is required. This material presents a trade-off between lower arcing and greater wear with a slower metal-removal rate, but costs more than plain graphite.

EDM electrodes are also made from copper, tungsten, silver-tungsten, brass, and zinc, which all have good electrical and thermal conductivity. However, all these metals have melting points below those encountered in the spark gap, so they wear rapidly. Copper with 5 per cent tellurium, added for better machining properties, is the most commonly used metal alloy. Tungsten resists wear better than brass or copper and is more rigid when used for thin electrodes but is expensive and difficult to machine. Metal electrodes, with their more even surfaces and slower wear rates, are often preferred for finishing operations on work that requires a smooth finish. In fine-finishing operations, the arc gap between the surfaces of the electrode and the workpiece is very small and there is a danger of dc arcs being struck, causing pitting of the surface. This pitting is caused when particles dislodged from a graphite electrode during fine-finishing cuts are not flushed from the gap. If struck by a spark, such a particle may provide a path for a continuous discharge of current that will mar the almost completed work surface.

Some combinations of electrode and workpiece material, electrode polarity, and likely amounts of corner wear are listed in Table 3. Corner wear rates indicate the ability of the electrode to maintain its shape and reproduce fine detail. The column headed Capacitance refers to the use of capacitors in the control circuits to increase the impact of the spark without increasing the amperage. Such circuits can accomplish more work in a given time, at the expense of surface-finish quality and increased electrode wear.

Table 3. Types of Electrodes Used for Various Workpiece Materials

Electrode	Electrode Polarity	Workpiece Material	Corner Wear (%)	Capacitance
Copper	+	Steel	2–10	No
Copper	+	Inconel	2–10	No
Copper	+	Aluminum	<3	No
Copper	–	Titanium	20–40	Yes
Copper	–	Carbide	35–60	Yes
Copper	–	Copper	34–45	Yes
Copper	–	Copper-tungsten	40–60	Yes
Copper-tungsten	+	Steel	1–10	No
Copper-tungsten	–	Copper	20–40	Yes
Copper-tungsten	–	Copper-tungsten	30–50	Yes
Copper-tungsten	–	Titanium	15–25	Yes
Copper-tungsten	–	Carbide	35–50	Yes
Graphite	+	Steel	<1	No
Graphite	–	Steel	30–40	No
Graphite	+	Inconel	<1	No
Graphite	–	Inconel	30–40	No
Graphite	+	Aluminum	<1	No
Graphite	–	Aluminum	10–20	No
Graphite	–	Titanium	40–70	No
Graphite	–	Copper	N/A	Yes

Copyright 2004, Industrial Press, Inc., New York, NY

Electrode Wear: Wear of electrodes can be reduced by leaving the smallest amounts of finishing stock possible on the workpiece and using no-wear or low-wear settings to remove most of the remaining material so that only a thin layer remains for finishing with the redressed electrode. The material left for removal in the finishing step should be only slightly more than the maximum depth of the craters left by the previous cut. Finishing operations should be regarded as only changing the quality of the finish, not removing metal or sizing. Low power with very high frequencies and minimal amounts of offset for each finishing cut are recommended.

On manually adjusted machines, fine finishing is usually carried out by several passes of a full-size finishing electrode. Removal of a few thousandths of an inch from a cavity with such an arrangement requires the leading edge of the electrode to recut the cavity over the entire vertical depth. By the time the electrode has been sunk to full depth, it is so worn that precision is lost. This problem sometimes can be avoided on a manual machine by use of an orbiting attachment that will cause the electrode to traverse the cavity walls, providing improved speed, finish, and flushing, and reducing corner wear on the electrode.

Selection of Electrode Material: Factors that affect selection of electrode material include metal-removal rate, wear resistance (including volumetric, corner, end, and side, with corner wear being the greatest concern), desired surface finish, costs of electrode manufacture and material, and characteristics of the material to be machined. A major factor is the ability of the electrode material to resist thermal damage, but the electrode's density, the polarity, and the frequencies used are all important factors in wear rates. Copper melts at about 1085°C (1985°F) and spark-gap temperatures must generally exceed 3800°C (6872°F), so use of copper may be made unacceptable because of its rapid wear rates. Graphites have good resistance to heat and wear at low frequencies, but will wear more with high frequency, negative polarity, or a combination of these.

Making Electrodes.— Electrodes made from copper and its alloys can be machined conventionally by lathes, and milling and grinding machines, but copper acquires a burr on run-off edges during turning and milling operations. For grinding copper, the wheel must often be charged with beeswax or similar material to prevent loading of the surface. Flat grinding of copper is done with wheels having open grain structures (46-J, for instance) to contain the wax and to allow room for the soft, gummy, copper chips. For finish grinding, wheels of at least 60 and up to 80 grit should be used for electrodes requiring sharp corners and fine detail. These wheels will cut hot and load up much faster, but are necessary to avoid rapid breakdown of sharp corners.

Factors to be considered in selection of electrode materials are: the electrode material cost cost/in^3; the time to manufacture electrodes; difficulty of flushing; the number of electrodes needed to complete the job; speed of the EDM; amount of electrode wear during EDM; and workpiece surface-finish requirements.

Copper electrodes have the advantage over graphite in their ability to be discharge-dressed in the EDM, usually under computer numerical control (CNC). The worn electrode is engaged with a premachined dressing block made from copper-tungsten or carbide. The process renews the original electrode shape, and can provide sharp, burr-free edges. Because of its higher vaporization temperature and wear resistance, discharge dressing of graphite is slow, but graphite has the advantage that it can be machined conventionally with ease.

Machining Graphite: Graphites used for EDM are very abrasive, so carbide tools are required for machining them. The graphite does not shear away and flow across the face of the tool as metal does, but fractures or is crushed by the tool pressure and floats away as a fine powder or dust. Graphite particles have sharp edges and, if allowed to mix with the machine lubricant, will form an abrasive slurry that will cause rapid wear of machine guiding surfaces. The dust may also cause respiratory problems and allergic reactions, espe-

Copyright 2004, Industrial Press, Inc., New York, NY

cially if the graphite is infiltrated with copper, so an efficient exhaust system is needed for machining.

Compressed air can be used to flush out the graphite dust from blind holes, for instance, but provision must be made for vacuum removal of the dust to avoid hazards to health and problems with wear caused by the hard, sharp-edged particles. Air velocities of at least 500 ft/min are recommended for flushing, and of 2000 ft/min in collector ducts to prevent settling out. Fluids can also be used, but small-pore filters are needed to keep the fluid clean. High-strength graphite can be clamped or chucked tightly but care must be taken to avoid crushing. Collets are preferred for turning because of the uniform pressure they apply to the workpiece. Sharp corners on electrodes made from less dense graphite are liable to chip or break away during machining.

For conventional machining of graphite, tools of high-quality tungsten carbide or polycrystaline diamond are preferred and must be kept sharp. Recommended cutting speeds for high-speed steel tools are 100 to 300, tungsten carbide 500 to 750, and polycrystaline diamond, 500 to 2000 surface ft/min. Tools for turning should have positive rake angles and nose radii of $\frac{1}{64}$ to $\frac{1}{32}$ in. Depths of cut of 0.015 to 0.020 in. produce a better finish than light cuts such as 0.005 in. because of the tendency of graphite to chip away rather than flow across the tool face. Low feed rates of 0.005 in./rev for rough- and 0.001 to 0.003 in./rev for finish-turning are preferred. Cutting off is best done with a tool having an angle of 20°.

For bandsawing graphite, standard carbon steel blades can be run at 2100 to3100 surface ft/min. Use low power feed rates to avoid overloading the teeth and the feed rate should be adjusted until the saw has a very slight speed up at the breakthrough point. Milling operations require rigid machines, short tool extensions, and firm clamping of parts. Milling cutters will chip the exit side of the cut, but chipping can be reduced by use of sharp tools, positive rake angles, and low feed rates to reduce tool pressure. Feed/tooth for two-flute end mills is 0.003 to 0.005 in. for roughing and 0.001 to 0.003 in. for finishing.

Standard high-speed steel drills can be used for drilling holes but will wear rapidly, causing holes that are tapered or undersized, or both. High-spiral, tungsten carbide drills should be used for large numbers of holes over $\frac{1}{16}$ in. diameter, but diamond-tipped drills will last longer. Pecking cycles should be used to clear dust from the holes. Compressed air can be passed through drills with through coolant holes to clear dust. Feed rates for drilling are 0.0015 to 0.002 in./rev for drills up to $\frac{1}{32}$, 0.001 to 0.003 in./rev for $\frac{1}{32}$- to $\frac{1}{8}$-in. drills, and 0.002 to 0.005 in./rev for larger drills. Standard taps without fluid are best used for through holes, and for blind holes, tapping should be completed as far as possible with a taper tap before the bottoming tap is used.

For surface grinding of graphite, a medium (60) grade, medium-open structure, vitreous-bond, green-grit, silicon-carbide wheel is most commonly used. The wheel speed should be 5300 to 6000 surface ft/min, with traversing feed rates at about 56 ft/min. Roughing cuts are taken at 0.005 to 0.010 in./pass, and finishing cuts at 0.001 to 0.003 in./pass. Surface finishes in the range of 18 to 32 μin. R_a are normal, and can be improved by longer spark-out times and finer grit wheels, or by lapping. Graphite can be centerless ground using a silicon-carbide, resinoid-bond work wheel and a regulating wheel speed of 195 ft/min.

Wire EDM, orbital abrading, and ultrasonic machining are also used to shape graphite electrodes. Orbital abrading uses a die containing hard particles to remove graphite, and can produce a fine surface finish. In ultrasonic machining, a water-based abrasive slurry is pumped between the die attached to the ultrasonic transducer and the graphite workpiece on the machine table. Ultrasonic machining is rapid and can reproduce small details down to 0.002 in. in size, with surface finishes down to 8 μin. R_a. If coolants are used, the graphite should be dried for 1 hour at over 400°F (but not in a microwave oven) to remove liquids before used.

Copyright 2004, Industrial Press, Inc., New York, NY

Wire EDM.— In the wire EDM process, with deionized water as the dielectric fluid, carbon is extracted from the recast layer, rather than added to it. When copper-base wire is used, copper atoms migrate into the recast layer, softening the surface slightly so that wire-cut surfaces are sometimes softer than the parent metal. On wire EDM machines, very high amperages are used with very short on times, so that the heat-affected zone (HAZ) is quite shallow. With proper adjustment of the on and off times, the depth of the HAZ can be held below 1 micron (0.00004 in.).

The cutting wire is used only once, so that the portion in the cut is always cylindrical and has no spark-eroded sections that might affect the cut accuracy. The power source controls the electrical supply to the wire and to the drive motors on the table to maintain the preset arc gap within 0.1 micron (0.000004 in.) of the programmed position. On wire EDM machines, the water used as a dielectric fluid is deionized by a deionizer included in the cooling system, to improve its properties as an insulator. Chemical balance of the water is also important for good dielectric properties.

Drilling Holes for Wire EDM: Before an aperture can be cut in a die plate, a hole must be provided in the workpiece. Such holes are often "drilled" by EDM, and the wire threaded through the workpiece before starting the cut. The "EDM drill" does not need to be rotated, but rotation will help in flushing and reduce electrode wear. The EDM process can drill a hole 0.04 in. in diameter through 4-in. thick steel in about 3 minutes, using an electrode made from brass or copper tubing. Holes of smaller diameter can be drilled, but the practical limit is 0.012 in. because of the overcut, the lack of rigidity of tubing in small sizes, and the excessive wear on such small electrodes. The practical upper size limit on holes is about 0.12 in. because of the comparatively large amounts of material that must be eroded away for larger sizes. However, EDM is commonly used for making large or deep holes in such hard materials as tungsten carbide. For instance, a 0.2-in. hole has been made in carbide 2.9 in. thick in 49 minutes by EDM. Blind holes are difficult to produce with accuracy, and must often be made with cut-and-try methods.

Deionized water is usually used for drilling and is directed through the axial hole in the tubular electrode to flush away the debris created by the sparking sequence. Because of the need to keep the extremely small cutting area clear of metal particles, the dielectric fluid is often not filtered but is replaced continuously by clean fluid that is pumped from a supply tank to a disposal tank on the machine.

Wire Electrodes: Wire for EDM generally is made from yellow brass containing copper 63 and zinc 37 per cent, with a tensile strength of 50,000 to 145,000 $lb_f/in.^2$, and may be from 0.002 to 0.012 in. diameter.

In addition to yellow brass, electrode wires are also made from brass alloyed with aluminum or titanium for tensile strengths of 140,000 to 160,000 $lb_f/in.^2$. Wires with homogeneous, uniform electrolytic coatings of alloys such as brass or zinc are also used. Zinc is favored as a coating on brass wires because it gives faster cutting and reduced wire breakage due to its low melting temperature of 419°C, and vaporization temperature of 906°C. The layer of zinc can boil off while the brass core, which melts at 930°C, continues to deliver current.

Some wires for EDM are made from steel for strength, with a coating of brass, copper, or other metal. Most wire machines use wire negative polarity (the wire is negative) because the wire is constantly renewed and is used only once, so wear is not important. Important qualities of wire for EDM include smooth surfaces, free from nicks, scratches and cracks, precise diameters to ±0.00004 in. for drawn and ±0.00006 in. for plated, high tensile strength, consistently good ductility, uniform spooling, and good protective packaging.

Copyright 2004, Industrial Press, Inc., New York, NY

IRON AND STEEL CASTINGS

Material Properties

Cast irons and cast steels encompass a large family of ferrous alloys, which, as the name implies, are cast to shape rather than being formed by working in the solid state. In general, cast irons contain more than 2 per cent carbon and from 1 to 3 per cent silicon. Varying the balance between carbon and silicon, alloying with different elements, and changing melting, casting, and heat-treating practices can produce a broad range of properties. In most cases, the carbon exists in two forms: free carbon in the form of graphite and combined carbon in the form of iron carbide (cementite). Mechanical and physical properties depend strongly on the shape and distribution of the free graphite and the type of matrix surrounding the graphite particles.

The four basic types of cast iron are white iron, gray iron, malleable iron, and ductile iron. In addition to these basic types, there are other specific forms of cast iron to which special names have been applied, such as chilled iron, alloy iron, and compacted graphite cast iron.

Gray Cast Iron.— Gray cast iron may easily be cast into any desirable form and it may also be machined readily. It usually contains from 1.7 to 4.5 per cent carbon, and from 1 to 3 per cent silicon. The excess carbon is in the form of graphite flakes and these flakes impart to the material the dark-colored fracture which gives it its name. Gray iron castings are widely used for such applications as machine tools, automotive cylinder blocks, cast-iron pipe and fittings and agricultural implements.

The American National Standard Specifications for Gray Iron Castings—ANSI/ASTM A48-76 groups the castings into two categories. Gray iron castings in Classes 20A, 20B, 20C, 25A, 25B, 25C, 30A, 30B, 30C, 35A, 35B, and 35C are characterized by excellent machinability, high damping capacity, low modulus of elasticity, and comparative ease of manufacture. Castings in Classes 40B, 40C, 45B, 45C, 50B, 50C, 60B, and 60C are usually more difficult to machine, have lower damping capacity, a higher modulus of elasticity, and are more difficult to manufacture. The prefix number is indicative of the minimum tensile strength in pounds per square inch, i.e., 20 is 20,000 psi, 25 is 25,000 psi, 30 is 30,000 psi, etc.

High-strength iron castings produced by the Meehanite-controlled process may have various combinations of physical properties to meet different requirements. In addition to a number of general engineering types, there are heat-resisting, wear-resisting and corrosion-resisting Meehanite castings.

White Cast Iron.— When nearly all of the carbon in a casting is in the combined or cementite form, it is known as white cast iron. It is so named because it has a silvery-white fracture. White cast iron is very hard and also brittle; its ductility is practically zero. Castings of this material need particular attention with respect to design since sharp corners and thin sections result in material failures at the foundry. These castings are less resistant to impact loading than gray iron castings, but they have a compressive strength that is usually higher than 200,000 pounds per square inch as compared to 65,000 to 160,000 pounds per square inch for gray iron castings. Some white iron castings are used for applications that require maximum wear resistance but most of them are used in the production of malleable iron castings.

Chilled Cast Iron.— Many gray iron castings have wear-resisting surfaces of white cast iron. These surfaces are designated by the term "chilled cast iron" since they are produced in molds having metal chills for cooling the molten metal rapidly. This rapid cooling results in the formation of cementite and white cast iron.

Alloy Cast Iron.— This term designates castings containing alloying elements such as nickel, chromium, molybdenum, copper, and manganese in sufficient amounts to appreciably change the physical properties. These elements may be added either to increase the strength or to obtain special properties such as higher wear resistance, corrosion resistance,

Copyright 2004, Industrial Press, Inc., New York, NY

or heat resistance. Alloy cast irons are used extensively for such parts as automotive cylinders, pistons, piston rings, crankcases, brake drums; for certain machine tool castings, for certain types of dies, for parts of crushing and grinding machinery, and for application where the casting must resist scaling at high temperatures. Machinable alloy cast irons having tensile strengths up to 70,000 pounds per square inch or even higher may be produced.

Malleable-iron Castings.— Malleable iron is produced by the annealing or graphitization of white iron castings. The graphitization in this case produces temper carbon which is graphite in the form of compact rounded aggregates. Malleable castings are used for many industrial applications where strength, ductility, machinability, and resistance to shock are important factors. In manufacturing these castings, the usual procedure is to first produce a hard, brittle white iron from a charge of pig iron and scrap. These hard white-iron castings are then placed in stationary batch-type furnaces or car-bottom furnaces and the graphitization (malleablizing) of the castings is accomplished by means of a suitable annealing heat treatment. During this annealing period the temperature is slowly (50 hours) increased to as much as 1650 or 1700 degrees F, after which time it is slowly (60 hours) cooled. The American National Standard Specifications for Malleable Iron Castings—ANSI/ASTM A47-77 specifies the following grades and their properties: No. 32520, having a minimum tensile strength of 50,000 pounds per square inch, a minimum yield strength of 32,500 psi., and a minimum elongation in 2 inches of 10 per cent; and No. 35018, having a minimum tensile strength of 53,000 psi., a minimum yield strength of 35,000 psi., and a minimum elongation in 2 inches of 18 per cent.

Cupola Malleable Iron: Another method of producing malleable iron involves initially the use of a cupola or a cupola in conjunction with an air furnace. This type of malleable iron, called cupola malleable iron, exhibits good fluidity and will produce sound castings. It is used in the making of pipe fittings, valves, and similar parts and possesses the useful property of being well suited to galvanizing. The American National Standard Specifications for Cupola Malleable Iron — ANSI/ASTM 197-79 calls for a minimum tensile strength of 40,000 pounds per square inch; a minimum yield strength of 30.000 psi.; and a minimum elongation in 2 inches of 5 per cent.

Pearlitic Malleable Iron: This type of malleable iron contains some combined carbon in various forms. It may be produced either by stopping the heat treatment of regular malleable iron during production before the combined carbon contained therein has all been transformed to graphite or by reheating regular malleable iron above the transformation range. Pearlitic malleable irons exhibit a wide range of properties and are used in place of steel castings or forgings or to replace malleable iron when a greater strength or wear resistance is required. Some forms are made rigid to resist deformation while others will undergo considerable deformation before breaking. This material has been used in axle housings, differential housings, camshafts, and crankshafts for automobiles; machine parts; ordnance equipment; and tools. Tension test requirements of pearlitic malleable iron castings called for in ASTM Specification A 220–79 are given in the accompanying table.

Tension Test Requirements of Pearlitic Malleable Iron Castings *ASTM A220-79*

Casting Grade Numbers		40010	45008	45006	50005	60004	70003	80002	90001
Min. Tensile Strength	1000s Lbs. per Sq. In.	60	65	65	70	80	85	95	105
Min. Yield Strength		40	45	45	50	60	70	80	90
Min. Elong. in 2 In., Per Cent		10	8	6	5	4	3	2	1

Ductile Cast Iron.— A distinguishing feature of this widely used type of cast iron, also known as spheroidal graphite iron or nodular iron, is that the graphite is present in ball-like form instead of in flakes as in ordinary gray cast iron. The addition of small amounts of magnesium- or cerium-bearing alloys together with special processing produces this sphe-

Copyright 2004, Industrial Press, Inc., New York, NY

roidal graphite structure and results in a casting of high strength and appreciable ductility. Its toughness is intermediate between that of cast iron and steel, and its shock resistance is comparable to ordinary grades of mild carbon steel. Melting point and fluidity are similar to those of the high-carbon cast irons. It exhibits good pressure tightness under high stress and can be welded and brazed. It can be softened by annealing or hardened by normalizing and air cooling or oil quenching and drawing.

Five grades of this iron are specified in ASTM A 536-80—Standard Specification for Ductile Iron Castings. The grades and their corresponding matrix microstructures and heat treatments are as follows: Grade 60-40-18, ferritic, may be annealed; Grade 65-45-12, mostly ferritic, as-cast or annealed; Grade 80-55-06, ferritic/pearlitic, as-cast; Grade 100-70-03, mostly pearlitic, may be normalized; Grade 120-90-02, martensitic, oil quenched and tempered. The grade nomenclature identifies the minimum tensile strength, on per cent yield strength, and per cent elongation in 2 inches. Thus, Grade 60–40–18 has a minimum tensile strength of 60,000 psi, a minimum 0.2 per cent yield strength of 40,000 psi, and minimum elongation in 2 inches of 18 per cent. Several other types are commercially available to meet specific needs. The common grades of ductile iron can also be specified by only Brinell hardness, although the appropriate microstructure for the indicated hardness is also a requirement. This method is used in SAE Specification J434C for automotive castings and similar applications. Other specifications not only specify tensile properties, but also have limitations in composition. Austenitic types with high nickel content, high corrosion resistance, and good strength at elevated temperatures, are specified in ASTM A439-80.

Ductile cast iron can be cast in molds containing metal chills if wear-resisting surfaces are desired. Hard carbide areas will form in a manner similar to the forming of areas of chilled cast iron in gray iron castings. Surface hardening by flame or induction methods is also feasible. Ductile cast iron can be machined with the same ease as gray cast iron. It finds use as crankshafts, pistons, and cylinder heads in the automotive industry; forging hammer anvils, cylinders, guides, and control levers in the heavy machinery field; and wrenches, clamp frames, face-plates, chuck bodies, and dies for forming metals in the tool and die field. The production of ductile iron castings involves complex metallurgy, the use of special melting stock, and close process control. The majority of applications of ductile iron have been made to utilize its excellent mechanical properties in combination with the castability, machinability, and corrosion resistance of gray iron.

Steel Castings.— Steel castings are especially adapted for machine parts that must withstand shocks or heavy loads. They are stronger than either wrought iron, cast iron, or malleable iron and are very tough. The steel used for making steel castings may be produced either by the open-hearth, electric arc, side-blow converter, or electric induction methods. The raw materials used are steel scrap, pig iron, and iron ore, the materials and their proportions varying according to the process and the type of furnace used. The open-hearth method is used when large tonnages are continually required while a small electric furnace might be used for steels of widely differing analyses, which are required in small lot production. The high frequency induction furnace is used for small quantity production of expensive steels of special composition such as high-alloy steels. Steel castings are used for such parts as hydroelectric turbine wheels, forging presses, gears, railroad car frames, valve bodies, pump casings, mining machinery, marine equipment, engine casings, etc.

Steel castings can generally be made from any of the many types of carbon and alloy steels produced in wrought form and respond similarly to heat treatment; they also do not exhibit directionality effects that are typical of wrought steel. Steel castings are classified into two general groups: carbon steel and alloy steel.

Carbon Steel Castings.— Carbon steel castings may be designated as low-carbon medium-carbon, and high-carbon. Low-carbon steel castings have a carbon content of less than 0.20 per cent (most are produced in the 0.16 to 0.19 per cent range). Other elements present are: manganese, 0.50 to 0.85 per cent; silicon, 0.25 to 0.70 per cent; phosphorus,

Copyright 2004, Industrial Press, Inc., New York, NY

0.05 per cent max.; and sulfur, 0.06 per cent max. Their tensile strengths (annealed condition) range from 40,000 to 70,000 pounds per square inch. Medium-carbon steel castings have a carbon content of from 0.20 to 0.50 per cent. Other elements present are: manganese, 0.50 to 1.00 per cent; silicon, 0.20 to 0.80 per cent; phosphorus, 0.05 per cent max.; and sulfur, 0.06 per cent max. Their tensile strengths range from 65,000 to 105,000 pounds per square inch depending, in part, upon heat treatment. High-carbon steel castings have a carbon content of more than 0.50 per cent and also contain: manganese, 0.50 to 1.00 per cent; silicon, 0.20 to 0.70 per cent; and phosphorus and sulfur, 0.05 per cent max. each. Fully annealed high-carbon steel castings exhibit tensile strengths of from 95,000 to 125,000 pounds per square inch. See Table 1 for grades and properties of carbon steel castings.

Table 1. Mechanical Properties of Steel Castings

Tensile Strength, Lbs. per Sq. In.	Yield Point, Lbs. per Sq. In.	Elongation in 2 In., Per Cent	Brinell Hardness Number	Type of Heat Treatment	Application Indicating Properties
Structural Grades of Carbon Steel Castings					
60,000	30,000	32	120	Annealed	Low electric resistivity. Desirable magnetic properties. Carburizing and case hardening grades. Weldability.
65,000	35,000	30	130	Normalized	Good weldability. Medium strength with good machinability and high ductility.
70,000	38,000	28	140	Normalized	
80,000	45,000	26	160	Normalized and tempered	High strength carbon steels with good machinability, toughness and good fatigue resistance.
85,000	50,000	24	175		
100,000	70,000	20	200	Quenched and tempered	Wear resistance. Hardness.
Engineering Grades of Low Alloy Steel Castings					
70,000	45,000	26	150	Normalized and tempered	Good weldability. Medium strength with high toughness and good machinability. For high temperature service.
80,000	50,000	24	170		
90,000	60,000	22	190	Normalized and tempered[a]	Certain steels of these classes have good high temperature properties and deep hardening properties. Toughness.
100,000	68,000	20	209		
110,000	85,000	20	235	Quenched and tempered	Impact resistance. Good low temperature properties for certain steels. Deep hardening. Good combination of strength and toughness.
120,000	95,000	16	245		
150,000	125,000	12	300	Quenched and tempered	Deep hardening. High strength. Wear and fatigue resistance.
175,000	148,000	8	340	Quenched and tempered	High strength and hardness. Wear resistance. High fatigue resistance.
200,000	170,000	5	400		

For general information only. Not for use as design or specification limit values. The values listed above have been compiled by the Steel Founders' Society of America as those normally expected in the production of steel castings. The castings are classified according to tensile strength values which are given in the first column. Specifications covering steel castings are prepared by the American Society for Testing and Materials, the Association of American Railroads, the Society of Automotive Engineers, the United States Government (Federal and Military Specifications), etc. These specifications appear in publications issued by these organizations.

[a] Quench and temper heat treatments may also be employed for these classes.

Alloy Steel Castings.— Alloy cast steels are those in which special alloying elements such as manganese, chromium, nickel, molybdenum, vanadium have been added in sufficient quantities to obtain or increase certain desirable properties. Alloy cast steels are comprised of two groups—the low-alloy steels with their alloy content totaling less than 8 per cent and the high-alloy steels with their alloy content totaling 8 per cent or more. The addition of these various alloying elements in conjunction with suitable heat-treatments, makes it possible to secure steel castings having a wide range of properties. The three accompanying tables give information on these steels. The lower portion of Table 1 gives the engi-

Copyright 2004, Industrial Press, Inc., New York, NY

neering grades of low-alloy cast steels grouped according to tensile strengths and gives properties normally expected in the production of steel castings. Tables 2 and 3 give the standard designations and nominal chemical composition ranges of high-alloy castings which may be classified according to heat or corrosion resistance. The grades given in these tables are recognized in whole or in part by the Alloy Casting Institute (ACI), the American Society for Testing and Materials (ASTM), and the Society of Automotive Engineers (SAE).

Table 2. Nominal Chemical Composition and Mechanical Properties of Heat-Resistant Steel Castings *ASTM A297-81*

Grade	Nominal Chemical Composition, Per Cent[a]	Tensile Strength, min		0.2 Per Cent Yield Strength, min		Per Cent Elongation in 2 in., or 50 mm, min.
		ksi	MPa	ksi	MPa	
HF	19 Chromium, 9 Nickel	70	485	35	240	25
HH	25 Chromium, 12 Nickel	75	515	35	240	10
HI	28 Chromium, 15 Nickel	70	485	35	240	10
HK	25 Chromium, 20 Nickel	65	450	35	240	10
HE	29 Chromium, 9 Nickel	85	585	40	275	9
HT	15 Chromium, 35 Nickel	65	450	…	…	4
HU	19 Chromium, 39 Nickel	65	450	…	…	4
HW	12 Chromium, 60 Nickel	60	415	…	…	…
HX	17 Chromium, 66 Nickel	60	415	…	…	…
HC	28 Chromium	55	380	…	…	…
HD	28 Chromium, 5 Nickel	75	515	35	240	8
HL	29 Chromium, 20 Nickel	65	450	35	240	10
HN	20 Chromium, 25 Nickel	63	435	…	…	8
HP	26 Chromium, 35 Nickel	62.5	430	34	235	4.5

ksi = kips per square inch = 1000s of pounds per square inch; MPa = megapascals.

[a] Remainder is iron.

The specifications committee of the Steel Founders Society issues a *Steel Castings Handbook* with supplements. Supplement 1 provides design rules and data based on the fluidity and solidification of steel, mechanical principles involved in production of molds and cores, cleaning of castings, machining, and functionality and weight aspects. Data and examples are included to show how these rules are applied. Supplement 2 summarizes the standard steel castings specification issued by the ASTM SAE, Assoc. of Am. Railroads (AAR), Am. Bur of Shipping (ABS), and Federal authorities, and provides guidance as to their applications. Information is included for carbon and alloy cast steels, high alloy cast steels, and centrifugally cast steel pipe. Details are also given of standard test methods for steel castings, including mechanical, non-destructive (visual, liquid penetrant, magnetic particle, radiographic, and ultrasonic), and testing of qualifications of welding procedures and personnel. Other supplements cover such subjects as tolerances, drafting practices, properties, repair and fabrication welding, of carbon, low alloy and high alloy castings, foundry terms, and hardenability and heat treatment.

Austenitic Manganese Cast Steel: Austenitic manganese cast steel is an important high-alloy cast steel which provides a high degree of shock and wear resistance. Its composition normally falls within the following ranges: carbon, 1.00 to 1.40 per cent; manganese, 10.00 to 14.00 per cent; silicon, 0.30 to 1.00 per cent; sulfur, 0.06 per cent max.; phosphorus, 0.10 per cent, max. In the as-cast condition, austenitic manganese steel is quite brittle. In order to strengthen and toughen the steel, it is heated to between 1830 and 1940 degrees F and quenched in cold water. Physical properties of quenched austenitic manganese steel that has been cast to size are as follows: tensile strength, 80,000 to 100,000 pounds per square inch; shear strength (single shear), 84,000 pounds per square inch; elongation in 2 inches, 15 to 35 per cent; reduction in area, 15 to 35 per cent; and Brinell hardness number,

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Nominal Chemical Composition and Mechanical Properties of Corrosion-Resistant Steel Castings *ASTM A743-81a*

Grade	Nominal Chemical Composition, Per Cent[a]	Tensile Strength, min		0.2% Yield Strength, min		Per Cent Elongation in 2 in., or 50 mm, min	Per Cent Reduction of Area, min
		ksi	MPa	ksi	MPa		
CF-8	9 Chromium, 9 Nickel	70[b]	485[b]	30[b]	205[b]	35	…
CG-12	22 Chromium, 12 Nickel	70	485	28	195	35	…
CF-20	19 Chromium, 9 Nickel	70	485	30	205	30	…
CF-8M	19 Chromium, 10 Nickel, with Molybdenum	70	485	30	205	30	…
CF-8C	19 Chromium, 10 Nickel with Niobium	70	485	30	205	30	…
CF-16, CF-16Fa	19 Chromium, 9 Nickel, Free Machining	70	485	30	205	25	…
CH-20, CH-10	25 Chromium, 12 Nickel	70	485	30	205	30	…
CK-20	25 Chromium, 20 Nickel	65	450	28	195	30	…
CE-30	29 Chromium, 9 Nickel	80	550	40	275	10	…
CA-15, CA-15M	12 Chromium	90	620	65	450	18	30
CB-30	20 Chromium	65	450	30	205	…	…
CC-50	28 Chromium	55	380	…	…	…	…
CA-40	12 Chromium	100	690	70	485	15	25
CF-3	19 Chromium, 9 Nickel	70	485	30	205	35	…
CF-3M	19 Chromium, 10 Nickel, with Molybdenum	70	485	30	205	30	…
CG6MMN	Chromium-Nickel-Manganese -Molybdenum	75	515	35	240	30	…
CG-8M	19 Chromium, 11 Nickel, with Molybdenum	75	520	35	240	25	…
CN-7M	20 Chromium, 29 Nickel, with Copper and Molybdenum	62	425	25	170	35	…
CN-7MS	19 Chromium, 24 Nickel, with Copper and Molybdenum	70	485	30	205	35	…
CW-12M	Nickel, Molybdenum, Chromium	72	495	46	315	4.0	…
CY-40	Nickel, Chromium, Iron	70	485	28	195	30	…
CZ-100	Nickel Alloy	50	345	18	125	10	…
M-35-1	Nickel-Copper Alloy	65	450	25	170	25	…
M-35-2	Nickel-Copper Alloy	65	450	30	205	25	…
CA-6NM	12 Chromium, 4 Nickel	110	755	80	550	15	35
CD-4MCu	25 Chromium, 5 Nickel, 2 Molybdenum, 3 Copper	100	690	70	485	16	…
CA-6N	11 Chromium, 7 Nickel	140	965	135	930	15	50

[a] Remainder is iron.

[b] For low ferrite or non-magnetic castings of this grade, the following values shall apply: tensile strength, min, 65 ksi (450 MPa); yield point, min, 28 ksi (195 MPa).

180 to 220. When cold worked, the surface of such a casting increases to a Brinell hardness of from 450 to 550. In many cases the surfaces are cold worked to maximum hardness to assure immediate hardness in use. Heat-treated austenitic manganese steel is machined only with great difficulty since it hardens at and slightly ahead of the point of contact of the cutting tool. Grinding wheels mounted on specially adapted machines are used for boring, planing, keyway cutting, and similar operations on this steel. Where grinding cannot be employed and machining must be resorted to, high-speed tool steel or cemented carbide tools are used with heavy, rigid equipment and slow, steady operation. In any event, this procedure tends to be both tedious and expensive. Austenitic manganese cast steel can be arc-welded with manganese-nickel steel welding rods containing from 3 to 5 per cent nickel, 10 to 15 per cent manganese, and, usually, 0.60 to 0.80 per cent carbon.

Casting of Metals

Molten metals are shaped by pouring (casting) into a mold of the required form, which they enter under gravity, centrifugal force, or various degrees of pressure. Molds are made of refractory materials like sand, plaster, graphite, or metal. Sand molds are formed around a pattern or replica of the part to be made, usually of wood though plastics or metal may be used when large numbers of molds for similar parts are to be made.

Copyright 2004, Industrial Press, Inc., New York, NY

Green-sand molding is used for most sand castings, sand mixed with a binder being packed around the pattern by hand, with power tools, or in a vibrating machine which may also exert a compressive force to pack the grains more closely. The term "green-sand" implies that the binder is not cured by heating or chemical reactions. The pattern is made in two "halves," which usually are attached to opposite sides of a flat plate. Shaped bars and other projections are fastened to the plate to form connecting channels and funnels in the sand for entry of the molten metal into the casting cavities. The sand is supported at the plate edges by a box-shaped frame or flask, with locating tabs that align the two mold halves when they are later assembled for the pouring operation.

Hollows and undercut surfaces in the casting are produced by cores, also made from sand, that are placed in position before the mold is closed, and held in place by tenons in grooves (called prints) formed in the sand by pattern projections. An *undercut surface* is one from which the pattern cannot be withdrawn in a straight line, so must be formed by a core in the mold. When the poured metal has solidified, the frame is removed and the sand falls or is cleaned off, leaving the finished casting(s) ready to be cut from the runners.

Gray iron is easily cast in complex shapes in green-sand and other molds and can be machined readily. The iron usually contains carbon, 1.7–4.5, and silicon, 1–3 per cent by weight. Excess carbon in the form of graphite flakes produces the gray surface from which the name is derived, when a casting is fractured.

Shell molding: invented by a German engineer, Croning, uses a resin binder to lock the grains of sand in a $\frac{1}{4}$- to $\frac{3}{8}$-in.-thick layer of sand/resin mixture, which adheres to a heated pattern plate after the mass of the mixture has been dumped back into the container. The hot resin quickly hardens enough to make the shell thus formed sufficiently rigid to be removed from the pattern, producing a half mold. The other half mold is produced on another plate by the same method. Pattern projections form runner channels, basins, core prints, and locating tenons in each mold half. Cores are inserted to form internal passages and undercuts. The shell assembly is placed in a molding box and supported with some other material such as steel shot or a coarse sand, when the molten metal is to be poured in. Some shell molds are strong enough to be filled without backup, and the two mold halves are merely clamped together for metal to be poured in to make the casting(s).

V-Process is a method whereby dry, unbonded sand is held to the shape of a pattern by a vacuum. The pattern is provided with multiple vent passages that terminate in various positions all over its surface, and are connected to a common plenum chamber. A heat-softened, 0.002–0.005-in.-thick plastics film is draped over the pattern and a vacuum of 200–400 mm of mercury is applied to the chamber, sucking out the air beneath the film so that the plastics is drawn into close contact with the pattern. A sand box or flask with walls that also contain hollow chambers and a flat grid that spans the central area is placed on the pattern plate to confine the dry unbonded sand that is allowed to fall through the grid on to the pattern.

After vibration to compact the sand around the pattern, a former is used to shape a sprue cup into the upper surface of the sand, connecting with a riser on the pattern, and the top surface of the sand is covered with a plastics film that extends over the flask sides. The hollow chambers in the flask walls are then connected to the vacuum source. The vacuum is sufficient to hold the sand grains in their packed condition between the plastics films above and beneath, firmly in the shape defined by the pattern, so that the flask and the sand half-mold can be lifted from the pattern plate. Matching half molds made by these procedures are assembled into a complete mold, with cores inserted if needed. With both mold halves still held by vacuum, molten metal is poured through the sprue cup into the mold, the plastics film between the mold surfaces being melted and evaporated by the hot metal. After solidification, the vacuum is released and the sand, together with the casting(s), falls from the mold flasks. The castings emerge cleanly, and the sand needs only to be cooled before reuse.

Copyright 2004, Industrial Press, Inc., New York, NY

Permanent mold, or gravity die, casting is mainly used for nonferrous metals and alloys. The mold (or die) is usually iron or steel, or graphite, and is cooled by water channels or by air jets on the outer surfaces. Cavity surfaces in metal dies are coated with a thin layer of heat-resistant material. The mold or die design is usually in two halves, although many multiple-part molds are in use, with loose sand or metal cores to form undercut surfaces. The cast metal is simply poured into a funnel formed in the top of the mold, although elaborate tilting mechanisms are often used to control the passage of metal into (and emergence of air from) the remote portions of die cavities.

Because the die temperature varies during the casting cycle, its dimensions vary correspondingly. The die is opened and ejectors push the casting(s) out as soon as its temperature is low enough for sufficient strength to build up. During the period after solidification and before ejection, cooling continues but shrinkage of the casting(s) is restricted by the die. The alloy being cast must be sufficiently ductile to accommodate these restrictions without fracturing. An alloy that tears or splits during cooling in the die is said to be *hot short* and cannot be cast in rigid molds. Dimensions of the casting(s) at shop temperatures will be related to the die temperature and the dimensions at ejection. Rules for casting shrinkage that apply to friable (sand) molds do not hold for rigid molds. Designers of metal molds and dies rely on temperature-based calculations and experience in evolving shrinkage allowances.

Low-pressure casting uses mold or die designs similar to those for gravity casting. The container (crucible) for the molten metal has provision for an airtight seal with the mold, and when gas or air pressure (6–10 lb/in.^{2}) is applied to the bath surface inside the crucible, the metal is forced up a hollow refractory tube (stalk) projecting from the die underside. This stalk extends below the bath level so that metal entering the die is free from oxides and impurities floating on the surface. The rate of filling is controlled so that air can be expelled from the die by the entering metal. With good design and control, high-quality, nonporous castings are made by both gravity and low-pressure methods, though the extra pressure in low-pressure die casting may increase the density and improve the reproduction of fine detail in the die.

Squeeze casting uses a metal die, of which one half is clamped to the bed of a large (usually) hydraulic press and the other to the vertically moving ram of the press. Molten metal is poured into the lower die and the upper die is brought down until the die is closed. The amount of metal in the die is controlled to produce a slight overflow as the die closes to ensure complete filling of the cavity. The heated dies are lubricated with graphite and pressures up to 25 tons per square inch may be applied by the press to squeeze the molten metal into the tiniest recesses in the die. When the press is opened, the solidified casting is pushed out by ejectors.

Finishing Operations for Castings

Removal of Gates and Risers from Castings.— After the molten iron or steel has solidified and cooled, the castings are removed from their molds, either manually or by placing them on vibratory machines and shaking the sand loose from the castings. The gates and risers that are not broken off in the shake-out are removed by impact, sawing, shearing, or burning-off methods. In the impact method, a hammer is used to knock off the gates and risers. Where the possibility exists that the fracture would extend into the casting itself, the gates or risers are first notched to assure fracture in the proper place. Some risers have a necked-down section at which the riser breaks off when struck. Sprue-cutter machines are also used to shear off gates. These machines facilitate the removal of a number of small castings from a central runner. Band saws, power saws. and abrasive cut-off wheel machines are also used to remove gates and risers. The use of band saws permits following the contour of the casting when removing unwanted appendages. Abrasive cut-off wheels are used when the castings are too hard or difficult to saw. Oxyacetylene cutting torches are used to cut off gates and risers and to gouge out or remove surface defects on castings.

Copyright 2004, Industrial Press, Inc., New York, NY

These torches are used on steel castings where the gates and risers are of a relatively large size. Surface defects are subsequently repaired by conventional welding methods.

Any unwanted material in the form of fins, gates, and riser pads that come above the casting surface, chaplets, parting-line flash, etc., is removed by chipping with pneumatic hammers, or by grinding with such equipment as floor or bench-stand grinders, portable grinders, and swing-frame grinders.

Blast Cleaning of Castings.— Blast cleaning of castings is performed to remove adhering sand, to remove cores, to improve the casting appearance, and to prepare the castings for their final finishing operation, which includes painting, machining, or assembling. Scale produced as a result of heat treating can also be removed. A variety of machines are used to handle all sizes of casting. The methods employed include blasting with sand, metal shot, or grit; and hydraulic cleaning or tumbling. In blasting, sharp sand, shot, or grit is carried by a stream of compressed air or water or by centrifugal force (gained as a result of whirling in a rapidly rotating machine) and directed against the casting surface by means of nozzles. The operation is usually performed in cabinets or enclosed booths. In some setups the castings are placed on a revolving table and the abrasive from the nozzles that are either mechanically or hand-held is directed against all the casting surfaces. Tumbling machines are also employed for cleaning, the castings being placed in large revolving drums together with slugs, balls, pins, metal punchings, or some abrasive, such as sandstone or granite chips, slag, silica, sand, or pumice. Quite frequently, the tumbling and blasting methods are used together, the parts then being tumbled and blasted simultaneously. Castings may also be cleaned by hydroblasting. This method uses a water-tight room in which a mixture of water and sand under high pressure is directed at the castings by means of nozzles. The action of the water and sand mixture cleans the castings very effectively.

Heat Treatment of Steel Castings.— Steel castings can be heat treated to bring about diffusion of carbon or alloying elements, softening, hardening, stress-relieving, toughening, improved machinability, increased wear resistance, and removal of hydrogen entrapped at the surface of the casting. Heat treatment of steel castings of a given composition follows closely that of wrought steel of similar composition. For discussion of types of heat treatment refer to the "Heat Treatment of Steel" section of this Handbook.

Estimating Casting Weight.— Where no pattern or die has yet been made, as when preparing a quotation for making a casting, the weight of a cast component can be estimated with fair accuracy by calculating the volume of each of the casting features, such as box- or rectangular-section features, cylindrical bosses, housings, ribs, and other parts, and adding them together. Several computer programs, also measuring mechanisms that can be applied to a drawing, are available to assist with these calculations. When the volume of metal has been determined it is necessary only to multiply by the unit weight of the alloy to be used, to arrive at the weight of the finished casting. The cost of the metal in the finished casting can then be estimated by multiplying the weight in lb by the cost/lb of the alloy. Allowances for melting losses, and for the extra metal used in risers and runners, and the cost of melting and machining may also be added to the cost/lb. Estimates of the costs of pattern- or die-making, molding, pouring and finishing of the casting(s), may also be added, to complete the quotation estimate.

Pattern Materials—Shrinkage, Draft, and Finish Allowances

Woods for Patterns.— Woods commonly used for patterns are white pine, mahogany, cherry, maple, birch, white wood, and fir. For most patterns, white pine is considered superior because it is easily worked, readily takes glue and varnish, and is fairly durable. For medium- and small-sized patterns, especially if they are to be used extensively, a harder wood is preferable. Mahogany is often used for patterns of this class, although many prefer cherry. As mahogany has a close grain, it is not as susceptible to atmospheric changes as a wood of coarser grain. Mahogany is superior in this respect to cherry, but is more expen-

Copyright 2004, Industrial Press, Inc., New York, NY

sive. In selecting cherry, never use young timber. Maple and birch are employed quite extensively, especially for turned parts, as they take a good finish. White wood is sometimes substituted for pine, but it is inferior to the latter in being more susceptible to atmospheric changes.

Selection of Wood.— It is very important to select well-seasoned wood for patterns; that is, it should either be kiln-dried or kept 1 or 2 years before using, the time depending upon the size of the lumber. During the seasoning or drying process, the moisture leaves the wood cells and the wood shrinks, the shrinkage being almost entirely across the grain rather than in a lengthwise direction. Naturally, after this change takes place, the wood is less liable to warp, although it will absorb moisture in damp weather. Patterns also tend to absorb moisture from the damp sand of molds, and to minimize troubles from this source they are covered with varnish. Green or water-soaked lumber should not be put in a drying room, because the ends will dry out faster than the rest of the log, thus causing cracks. In a log, there is what is called "sap wood" and "heart wood." The outer layers form the sap wood, which is not as firm as the heart wood and is more likely to warp; hence, it should be avoided, if possible.

Pattern Varnish.— Patterns intended for repeated use are varnished to protect them against moisture, especially when in the damp molding sand. The varnish used should dry quickly to give a smooth surface that readily draws from the sand. Yellow shellac varnish is generally used. It is made by dissolving gum shellac in grain alcohol. Wood alcohol is sometimes substituted, but is inferior. The color of the varnish is commonly changed for covering core prints, in order that the prints may be readily distinguished from the body of the pattern. Black shellac varnish is generally used. At least three coats of varnish should be applied to patterns, the surfaces being rubbed down with sandpaper after applying the preliminary coats, in order to obtain a smooth surface.

Shrinkage Allowances.— The shrinkage allowances ordinarily specified for patterns to compensate for the contraction of castings in cooling are as follows: cast iron, $\frac{3}{32}$ to $\frac{1}{8}$ inch per foot; common brass, $\frac{3}{16}$ inch per foot; yellow brass, $\frac{7}{32}$ inch per foot; bronze, $\frac{5}{32}$ inch per foot; aluminum, $\frac{1}{8}$ to $\frac{5}{32}$ inch per foot; magnesium, $\frac{1}{8}$ to $\frac{11}{64}$ inch per foot; steel, $\frac{3}{16}$ inch per foot. These shrinkage allowances are approximate values only because the exact allowance depends upon the size and shape of the casting and the resistance of the mold to the normal contraction of the casting during cooling. It is, therefore, possible that more than one shrinkage allowance will be required for different parts of the same pattern. Another factor that affects shrinkage allowance is the molding method, which may vary to such an extent from one foundry to another, that different shrinkage allowances for each would have to be used for the same pattern. For these reasons it is recommended that patterns be made at the foundry where the castings are to be produced to eliminate difficulties due to lack of accurate knowledge of shrinkage requirements.

An example of how casting shape can affect shrinkage allowance is given in the Steel Castings Handbook. In this example a straight round steel bar required a shrinkage allowance of approximately $\frac{9}{32}$ inch per foot. The same bar but with a large knob on each end required a shrinkage allowance of only $\frac{3}{16}$ inch per foot. A third steel bar with large flanges at each end required a shrinkage allowance of only $\frac{7}{64}$ inch per foot. This example would seem to indicate that the best practice in designing castings and making patterns is to obtain shrinkage values from the foundry that is to make the casting because there can be no fixed allowances.

Metal Patterns.— Metal patterns are especially adapted to molding machine practice, owing to their durability and superiority in retaining the required shape. The original master pattern is generally made of wood, the casting obtained from the wood pattern being finished to make the metal pattern. The materials commonly used are brass, cast iron, aluminum, and steel. Brass patterns should have a rather large percentage of tin, to improve

Copyright 2004, Industrial Press, Inc., New York, NY

the casting surface. Cast iron is generally used for large patterns because it is cheaper than brass and more durable. Cast-iron patterns are largely used on molding machines. Aluminum patterns are light but they require large shrinkage allowances. White metal is sometimes used when it is necessary to avoid shrinkage. The gates for the mold may be cast or made of sheet brass. Some patterns are made of vulcanized rubber, especially for light match-board work.

Obtaining Weight of Casting from Pattern Weight.— To obtain the approximate weight of a casting, multiply the weight of the pattern by the factor given in the accompanying table. For example, if the weight of a white-pine pattern is 4 pounds what is the weight of a solid cast-iron casting obtained from that pattern? Casting weight = $4 \times 16 = 64$ pounds. If the casting is cored, fill the core-boxes with dry sand, and multiply the weight of the sand by one of the following factors: For cast iron, 4; for brass, 4.65; for aluminum, 1.4. Then subtract the product of the sand weight and the factor just given from the weight of the solid casting, to obtain the weight of the cored casting. The weight of wood varies considerably, so the results obtained by the use of the table are only approximate, the factors being based on the average weight of the woods listed. For metal patterns, the results may be more accurate.

Factors for Obtaining Weight of Casting from Pattern Weight

	Factors				
Pattern Material	Cast Iron	Aluminum	Copper	Zinc	Brass, 70% Copper, 30% Zinc
White pine	16.00	5.70	19.60	15.00	19.00
Mahogany, Honduras	12.00	4.50	14.70	11.50	14.00
Cherry	10.50	3.80	13.00	10.00	12.50
Cast Iron	1.00	0.35	1.22	0.95	1.17
Aluminum	2.85	1.00	3.44	2.70	3.30

Die Casting

Die casting is a method of producing finished castings by forcing molten metal into a hard metal die, which is arranged to open after the metal has solidified so that the casting can be removed. The die-casting process makes it possible to secure accuracy and uniformity in castings, and machining costs are either eliminated altogether or are greatly reduced. The greatest advantage of the die-casting process is that parts are accurately and often completely finished when taken from the die. When the dies are properly made, castings may be accurate within 0.001 inch or even less and a limit of 0.002 or 0.003 inch per inch of casting dimension can be maintained on many classes of work.

Die castings are used extensively in the manufacture of such products as cash registers, meters, time-controlling devices, small housings, washing machines, and parts for a great variety of mechanisms. Lugs and gear teeth are cast in place and both external and internal screw threads can be cast. Holes can be formed within about 0.001 inch of size and the most accurate bearings require only a finish-reaming operation. Figures and letters may be cast sunken or in relief on wheels for counting or printing devices, and with ingenious die designs, many shapes that formerly were believed too intricate for die casting are now produced successfully by this process.

Die casting uses hardened steel molds (dies) into which the molten metal is injected at high speed, reaching pressures up to 10 tons/in.^{2}, force being applied by a hydraulically actuated plunger moving in a cylindrical pressure chamber connected to the die cavity(s). If the plan area of the casting and its runner system cover 50 in.^{2}, the total power applied is 10 tons/in.^{2} of pressure on the metal $\times$ 50 in.^{2} of projected area, producing a force of 500

Copyright 2004, Industrial Press, Inc., New York, NY

tons, and the die-casting machine must hold the die shut against this force. Massive toggle mechanisms stretch the heavy (6-in. diameter) steel tie bars through about 0.045 in. on a typical (500-ton) machine to generate this force. Although the die is hot, metal entering the die cavity is cooled quickly, producing layers of rapidly chilled, dense material about 0.015 in. thick in the metal having direct contact with the die cavity surfaces. Because the high injection forces allow castings to be made with thin walls, these dense layers form a large proportion of the total wall thickness, producing high casting strength. This phenomenon is known as the skin effect, and should be taken into account when considering the tensile strengths and other properties measured in (usually thicker) test bars.

As to the limitations of the die-casting process it may be mentioned that the cost of dies is high, and, therefore, die casting is economical only when large numbers of duplicate parts are required. The stronger and harder metals cannot be die cast, so that the process is not applicable for casting parts that must necessarily be made of iron or steel, although special alloys have been developed for die casting that have considerable tensile and compressive strength.

Many die castings are produced by the hot-chamber method in which the pressure chamber connected to the die cavity is immersed permanently in the molten metal and is automatically refilled through a hole that is uncovered as the (vertical) pressure plunger moves back after filling the die. This method can be used for alloys of low melting point and high fluidity such as zinc, lead, tin, and magnesium. Other alloys requiring higher pressure, such as brass, or that can attack and dissolve the ferrous pressure chamber material, such as aluminum, must use the slower cold-chamber method with a water-cooled (horizontal) pressure chamber outside the molten metal.

Porosity.— Molten metal injected into a die cavity displaces most of the air, but some of the air is trapped and is mixed with the metal. The high pressure applied to the metal squeezes the pores containing the air to very small size, but subsequent heating will soften the casting so that air in the surface pores can expand and cause blisters. Die castings are seldom solution heat treated or welded because of this blistering problem. The chilling effect of the comparatively cold die causes the outer layers of a die casting to be dense and relatively free of porosity. Vacuum die casting, in which the cavity atmosphere is evacuated before metal is injected, is sometimes used to reduce porosity. Another method is to displace the air by filling the cavity with oxygen just prior to injection. The oxygen is burned by the hot metal so that porosity does not occur.

When these special methods are not used, machining depths must be limited to 0.020–0.035 inch if pores are not to be exposed, but as-cast accuracy is usually good enough for only light finishing cuts to be needed. Special pore-sealing techniques must be used if pressure tightness is required.

Designing Die Castings.— Die castings are best designed with uniform wall thicknesses (to reduce cooling stresses) and cores of simple shapes (to facilitate extraction from the die). Heavy sections should be avoided or cored out to reduce metal concentrations that may attract trapped gases and cause porosity concentrations. Designs should aim at arranging for metal to travel through thick sections to reach thin ones if possible. Because of the high metal injection pressures, conventional sand cores cannot be used, so cored holes and apertures are made by metal cores that form part of the die. Small and slender cores are easily bent or broken, so should be avoided in favor of piercing or drilling operations on the finished castings. Ribbing adds strength to thin sections, and fillets should be used on all inside corners to avoid high stress concentrations in the castings. Sharp outside corners should be avoided. Draft allowances on a die casting are usually from 0.5 to 1.5 degrees per side to permit the castings to be pushed off cores or out of the cavity.

Alloys Used for Die Casting.— The alloys used in modern die-casting practice are based on aluminum, zinc, and copper, with small numbers of castings also being made from magnesium-, tin-, and lead-based alloys.

Copyright 2004, Industrial Press, Inc., New York, NY

Aluminum-Base Alloys.— Aluminum-base die-casting alloys are used more extensively than any other base metal alloy because of their superior strength combined with ease of castability. Linear shrinkage of aluminum alloys on cooling is about 12.9 to 15.5 × 10^{-6} in./in.-°F. Casting temperatures are of the order of 1200 deg. F. Most aluminum die castings are produced in aluminum-silicon-copper alloys such as the Aluminum Association (AA) No. 380 (ASTM SC84A; UNS A038000), containing silicon 7.5 to 9.5 and copper 3 to 4 per cent. Silicon increases fluidity for complete die filling, but reduces machinability, and copper adds hardness but reduces ductility in aluminum alloys. A less-used alloy having slightly greater fluidity is AA No. 384 (ASTM SC114A; UNS A03840) containing silicon 10.5 to 12.0 and copper 3.0 to 4.5 per cent. For marine applications, AA 360 (ASTM 100A; UNS A03600) containing silicon 9 to 10 and copper 0.6 per cent is recommended, the copper content being kept low to reduce susceptibility to corrosion in salt atmospheres. The tensile strengths of AA 380, 384, and 360 alloys are 47,000, 48,000, and 46,000 lb/in.^{2}, respectively. Although 380, 384, and 360 are the most widely used die-castable alloys, several other aluminum alloys are used for special applications. For instance, the AA 390 alloy, with its high silicon content (16 to 18 per cent), is used for internal combustion engine cylinder castings, to take advantage of the good wear resistance provided by the hard silicon grains. No. 390 alloy also contains 4 to 5 per cent copper, and has a hardness of 120 Brinell with low ductility, and a tensile strength of 41,000 lb/in.^{2}.

Zinc-Base Alloys.— In the molten state, zinc is extremely fluid and can therefore be cast into very intricate shapes. The metal also is plentiful and has good mechanical properties. Zinc die castings can be made to closer dimensional limits and with thinner walls than aluminum. Linear shrinkage of these alloys on cooling is about 9 to 13 × 10^{-6} in./in.-°F. The low casting temperatures (750–800 deg. F) and the hot-chamber process allow high production rates with simple automation. Zinc die castings can be produced with extremely smooth surfaces, lending themselves well to plating and other finishing methods. The established zinc alloys numbered 3, 5 and 7 [ASTM B86 (AG40A; UNS Z33520), AG41A (UNS Z35531), and AG40B (UNS Z33522)] each contains 3.5 to 4.3 per cent of aluminum, which adds strength and hardness, plus carefully controlled amounts of other elements. Recent research has brought forward three new alloys of zinc containing 8, 12, and 27 per cent of aluminum, which confer tensile strength of 50,000–62,000 lb/in.^{2} and hardness approaching that of cast iron (105–125 Brinell). These alloys can be used for gears and racks, for instance, and as housings for shafts that run directly in reamed or bored holes, with no need for bearing bushes.

Copper-Base Alloys.— Brass alloys are used for plumbing, electrical, and marine components where resistance to corrosion must be combined with strength and wear resistance. With the development of the cold-chamber casting process, it became possible to make die castings from several standard alloys of copper and zinc such as yellow brass (ASTM B176-Z30A; UNS C85800) containing copper 58, zinc 40, tin 1, and lead 1 per cent. Tin and lead are included to improve corrosion resistance and machinability, respectively, and this alloy has a tensile strength of 45,000 lb/in^2. Silicon brass (ASTM B176-ZS331A; UNS C87800) with copper 65 and zinc 34 per cent also contains 1 per cent silicon, giving it more fluidity for castability and with higher tensile strength (58,000 psi) and better resistance to corrosion. High silicon brass or tombasil (ASTM B176-ZS144A), containing copper 82, zinc 14, and silicon 4 per cent, has a tensile strength of 70,000 lb/in.2 and good wear resistance, but at the expense of machinability.

Magnesium-Base Alloys.— Light weight combined with good mechanical properties and excellent damping characteristics are principal reasons for using magnesium die castings. Magnesium has a low specific heat and does not dissolve iron so it may be die cast by the cold- or hot-chamber methods. For the same reasons, die life is usually much longer than for aluminum. The lower specific heat and more rapid solidification make production about 50 per cent faster than with aluminum. To prevent oxidation, an atmosphere of CO_2

Copyright 2004, Industrial Press, Inc., New York, NY

and air, containing about 0.5 per cent of SF_6 gas, is used to exclude oxygen from the surface of the molten metal. The most widely used alloy is AZ91D (ASTM B94; UNS 11916), a high-purity alloy containing aluminum 9 and zinc 0.7 per cent, and having a yield strength of 23,000 lb/in.^{2} (Table 8a on page 587). AZ91D has a corrosion rate similar to that of 380 aluminum (see *Aluminum-Base Alloys* on page 1372).

Tin-Base Alloys.— In this group tin is alloyed with copper, antimony, and lead. SAE Alloy No. 10 contains, as the principal ingredients, in percentages, tin, 90; copper, 4 to 5; antimony, 4 to 5; lead, maximum, 0.35. This high-quality babbitt mixture is used for mainshaft and connecting-rod bearings or bronze-backed bearings in the automotive and aircraft industries. SAE No. 110 contains tin, 87.75; antimony, 7.0 to 8.5; copper, maximum, 2.25 to 3.75 per cent and other constituents the same as No. 10. SAE No. 11, which contains a little more copper and antimony and about 4 per cent less tin than No. 10, is also used for bearings or other applications requiring a high-class tin-base alloy. These tin-base compositions are used chiefly for automotive bearings but they are also used for milking machines, soda fountains, syrup pumps, and similar apparatus requiring resistance against the action of acids, alkalies, and moisture.

Lead-Base Alloys.— These alloys are employed usually where a cheap noncorrosive metal is needed and strength is relatively unimportant. Such alloys are used for parts of lead-acid batteries, for automobile wheel balancing weights, for parts that must withstand the action of strong mineral acids and for parts of X-ray apparatus. SAE Composition No. 13 contains (in percentages) lead, 86; antimony, 9.25 to 10.75; tin, 4.5 to 5.5 per cent. SAE Specification No. 14 contains less lead and more antimony and copper. The lead content is 76; antimony, 14 to 16; and tin, 9.25 to 10.75 per cent. Alloys Nos. 13 and 14 are inexpensive owing to the high lead content and may be used for bearings that are large and subjected to light service.

Dies for Die-Casting Machines.— Dies for die-casting machines are generally made of steel although cast iron and nonmetallic materials of a refractory nature have been used, the latter being intended especially for bronze or brass castings, which, owing to their comparatively high melting temperatures, would damage ordinary steel dies. The steel most generally used is a low-carbon steel. Chromium-vanadium and tungsten steels are used for aluminum, magnesium, and brass alloys, when dies must withstand relatively high temperatures.

Making die-casting dies requires considerable skill and experience. Dies must be so designed that the metal will rapidly flow to all parts of the impression and at the same time allow the air to escape through shallow vent channels, 0.003 to 0.005 inch deep, cut into the parting of the die. To secure solid castings, the gates and vents must be located with reference to the particular shape to be cast. Shrinkage is another important feature, especially on accurate work. The amount usually varies from 0.002 to 0.007 inch per inch, but to determine the exact shrinkage allowance for an alloy containing three or four elements is difficult except by experiment.

Die-Casting Bearing Metals in Place.— Practically all the metals that are suitable for bearings can be die cast in place. Automobile connecting rods are an example of work to which this process has been applied sucessfully. After the bearings are cast in place, they are finished by boring or reaming. The best metals for the bearings, and those that also can be die cast most readily, are the babbitts containing about 85 per cent tin with the remainder copper and antimony. These metals should not contain over 9 per cent copper. The copper constitutes the hardening element in the bearing. A recommended composition for a high-class bearing metal is 85 per cent tin, 10 per cent antimony, and 5 per cent copper. The antimony may vary from 7 to 10 per cent and the copper from 5 to 8 per cent. To reduce costs, some bearing metals use lead instead of tin. One bearing alloy contains from 95 to 98 per cent lead. The die-cast metal becomes harder upon seasoning a few days. In die-casting bearings, the work is located from the bolt holes that are drilled previous to die casting. It is

Copyright 2004, Industrial Press, Inc., New York, NY

important that the bolt holes be drilled accurately with relation to the remainder of the machined surfaces.

Injection Molding of Metal.— The die casting and injection molding processes have been combined to make possible the injection molding of many metal alloys by mixing powdered metal, of 5 to 10 μm (0.0002 to 0.0004 in.) particle size with thermoplastic binders. These binders are chosen for maximum flow characteristics to ensure that the mixture can penetrate to the most remote parts of the die/mold cavities. Moderate pressures and temperatures are used for the injection molding of these mixtures, and the molded parts harden as they cool so that they can be removed as solids from the mold. Shrinkage allowances for the cavities are greater than are required for the die casting process, because the injection molded parts are subject to a larger shrinkage (10 to 35 per cent) after removal from the die, due to evaporation of the binder and consolidation of the powder.

Binder removal may take several days because of the need to avoid distortion, and when it is almost complete the molded parts are sintered in a controlled atmosphere furnace at high temperatures to remove the remaining binder and consolidate the powdered metal component that remains. Density can thus be increased to about 95 per cent of the density of similar material produced by other processes. Tolerances are similar to those in die casting, and some parts are sized by a coining process for greater accuracy. The main limitation of the process is size, parts being restricted to about a 1.5-in. cube.

Precision Investment Casting

Investment casting is a highly developed process that is capable of great casting accuracy and can form extremely intricate contours. The process may be utilized when metals are too hard to machine or otherwise fabricate; when it is the only practical method of producing a part; or when it is more economical than any other method of obtaining work of the quality required. Precision investment casting is especially applicable in producing either exterior or interior contours of intricate form with surfaces so located that they could not be machined readily if at all. The process provides efficient, accurate means of producing such parts as turbine blades, airplane, or other parts made from alloys that have high melting points and must withstand exceptionally high temperatures, and many other products. The accuracy and finish of precision investment castings may either eliminate machining entirely or reduce it to a minimum. The quantity that may be produced economically may range from a few to thousands of duplicate parts.

Investment casting uses an expendable pattern, usually of wax or injection-molded plastics. Several wax replicas or patterns are usually joined together or to bars of wax that are shaped to form runner channels in the mold. Wax shapes that will produce pouring funnels also are fastened to the runner bars. The mold is formed by dipping the wax assembly (tree) into a thick slurry containing refractory particles. This process is known as investing. After the coating has dried, the process is repeated until a sufficient thickness of material has been built up to form a one-piece mold shell. Because the mold is in one piece, undercuts, apertures, and hollows can be produced easily. As in shell molding, this invested shell is baked to increase its strength, and the wax or plastics pattern melts and runs out or evaporates (lost-wax casting). Some molds are backed up with solid refractory material that is also dried and baked to increase the strength. Molds for lighter castings are often treated similarly to shell molds described before. Filling of the molds may take place in the atmosphere, in a chamber filled with inert gas or under vacuum, to suit the metal being cast.

Materials That May Be Cast.— The precision investment process may be applied to a wide range of both ferrous and nonferrous alloys. In industrial applications, these include alloys of aluminum and bronze, Stellite, Hastelloys, stainless and other alloy steels, and iron castings, especially where thick and thin sections are encountered. In producing investment castings, it is possible to control the process in various ways so as to change the porosity or density of castings, obtain hardness variations in different sections, and vary the corrosion resistance and strength by special alloying.

Copyright 2004, Industrial Press, Inc., New York, NY

General Procedure in Making Investment Castings.— Precision investment casting is similar in principle to the "lost-wax" process that has long been used in manufacturing jewelry, ornamental pieces, and individual dentures, inlays, and other items required in dentistry, which is not discussed here. When this process is employed, both the pattern and mold used in producing the casting are destroyed after each casting operation, but they may both be replaced readily. The "dispensable patterns" (or cluster of duplicate patterns) is first formed in a permanent mold or die and is then used to form the cavity in the mold or "investment" in which the casting (or castings) is made. The investment or casting mold consists of a refractory material contained within a reinforcing steel flask. The pattern is made of wax, plastics, or a mixture of the two. The material used is evacuated from the investment to form a cavity (without parting lines) for receiving the metal to be cast. Evacuation of the pattern (by the application of sufficient heat to melt and vaporize it) and the use of a master mold or die for reproducing it quickly and accurately in making duplicate castings are distinguishing features of this casting process. Modern applications of the process include many developments such as variations in the preparation of molds, patterns, investments, etc., as well as in the casting procedure. Application of the process requires specialized knowledge and experience.

Master Mold for Making Dispensable Patterns.— Duplicate patterns for each casting operation are made by injecting the wax, plastics, or other pattern material into a master mold or die that usually is made either of carbon steel or of a soft metal alloy. Rubber, alloy steels, and other materials may also be used. The mold cavity commonly is designed to form a cluster of patterns for multiple castings. The mold cavity is not, as a rule, an exact duplicate of the part to be cast because it is necessary to allow for shrinkage and perhaps to compensate for distortion that might affect the accuracy of the cast product. In producing master pattern molds there is considerable variation in practice. One general method is to form the cavity by machining; another is by pouring a molten alloy around a master pattern that usually is made of monel metal or of a high-alloy stainless steel. If the cavity is not machined, a master pattern is required. Sometimes, a sample of the product itself may be used as a master pattern, when, for example, a slight reduction in size due to shrinkage is not objectionable. The dispensable pattern material, which may consist of waxes, plastics, or a combination of these materials, is injected into the mold by pressure, by gravity, or by the centrifugal method. The mold is made in sections to permit removal of the dispensable pattern. The mold while in use may be kept at the correct temperature by electrical means, by steam heating, or by a water jacket.

Shrinkage Allowances for Patterns.— The shrinkage allowance varies considerably for different materials. In casting accurate parts, experimental preliminary casting operations may be necessary to determine the required shrinkage allowance and possible effects of distortion. Shrinkage allowances, in inches per inch, usually average about 0.022 for steel, 0.012 for gray iron, 0.016 for brass, 0.012 to 0.022 for bronze, 0.014 for aluminum and magnesium alloys. (See also *Shrinkage Allowances* on page 1369.)

Casting Dimensions and Tolerances.— Generally, dimensions on investment castings can be held to ±0.005 in. and on specified dimensions to as low as ±0.002 in. Many factors, such as the grade of refractory used for the initial coating on the pattern, the alloy composition, and the pouring temperature, affect the cast surface finish. Surface discontinuities on the as-cast products therefore can range from 30 to 300 microinches in height.

Investment Materials.— For investment casting of materials having low melting points, a mixture of plaster of Paris and powdered silica in water may be used to make the molds, the silica forming the refractory and the plaster acting as the binder. To cast materials having high melting points, the refractory may be changed to sillimanite, an alumina-silicate material having a low coefficient of expansion that is mixed with powdered silica as the binder. Powdered silica is then used as the binder. The interior surfaces of the mold are reproduced on the casting so, when fine finishes are needed, a first coating of fine sillimanite sand and a silicon ester such as ethyl silicate with a small amount of piperidine, is

Copyright 2004, Industrial Press, Inc., New York, NY

applied and built up to a thickness of about 0.06 in. This investment is covered with a coarser grade of refractory that acts to improve bonding with the main refractory coatings, before the back up coatings are applied.

With light castings, the invested material may be used as a shell, without further reinforcement. With heavy castings the shell is placed in a larger container which may be of thick waxed paper or card, and further slurry is poured around it to form a thicker mold of whatever proportions are needed to withstand the forces generated during pouring and solidification. After drying in air for several hours, the invested mold is passed through an oven where it is heated to a temperature high enough to cause the wax to run out. When pouring is to take place, the mold is pre-heated to between 700 and 1000°C, to get rid of any remaining wax, to harden the binder and prepare for pouring the molten alloy. Pouring metal into a hot mold helps to ensure complete filling of intricate details in the castings. Pouring may be done under gravity, under a vacuum under pressure, or with a centrifuge. When pressure is used, attention must be paid to mold permeability to ensure gases can escape as the metal enters the cavities.

Casting Operations.— The temperature of the flask for casting may range all the way from a chilled condition up to 2000 degrees F or higher, depending upon the metal to be cast, the size and shape of the casting or cluster, and the desired metallurgical conditions. During casting, metals are nearly always subjected to centrifugal force vacuum, or other pressure. The procedure is governed by the kind of alloy, the size of the investment cavity, and its contours or shape.

Investment Removal.— When the casting has solidified, the investment material is removed by destroying it. Some investments are soluble in water, but those used for ferrous castings are broken by using pneumatic tools, hammers, or by shot or abrasive blasting and tumbling to remove all particles. Gates, sprues, and runners may be removed from the castings by an abrasive cutting wheel or a band saw according to the shape of the cluster and machinability of the material.

Accuracy of Investment Castings.— The accuracy of precision investment castings may, in general, compare favorably with that of many machined parts. The overall tolerance varies with the size of the work, the kind of metal and the skill and experience of the operators. Under normal conditions, tolerances may vary from ±0.005 or ±0.006 inch per inch, down to ±0.0015 to ±0.002 inch per inch, and even smaller tolerances are possible on very small dimensions. Where tolerances applying to a lengthwise dimension must be smaller than would be normal for the casting process, the casting gate may be placed at one end to permit controlling the length by a grinding operation when the gate is removed.

Casting Weights and Sizes.— Investment castings may vary in weight from a fractional part of an ounce up to 75 pounds or more. Although the range of weights representing the practice of different firms specializing in investment casting may vary from about ½ pound up to 10 or 20 pounds, a practical limit of 10 or 15 pounds is common. The length of investment castings ordinarily does not exceed 12 or 15 inches, but much longer parts may be cast. It is possible to cast sections having a thickness of only a few thousandths of an inch, but the preferred minimum thickness, as a general rule, is about 0.020 inch for alloys of high castability and 0.040 inch for alloys of low castability.

Design for Investment Casting.— As with most casting processes, best results from investment casting are achieved when uniform wall thicknesses between 0.040 and 0.375 in. are used for both cast components and channels forming runners in the mold. Gradual transition from thick to thin sections is also desirable. It is important that molten metal should not have to pass through a thin section to fill a thick part of the casting. Thin edges should be avoided because of the difficulty of producing them in the wax pattern. Fillets should be used in all internal corners to avoid stress concentrations that usually accompany sharp angles. Thermal contraction usually causes distortion of the casting, and should be allowed for if machining is to be minimized. Machining allowances vary from 0.010 in. on

Copyright 2004, Industrial Press, Inc., New York, NY

small, to 0.040 in. on large parts. With proper arrangement of castings in the mold, grain size and orientation can be controlled and directional solidification can often be used to advantage to ensure desired physical properties in the finished components.

Casting Milling Cutters by Investment Method.— Possible applications of precision investment casting in tool manufacture and in other industrial applications are indicated by its use in producing high-speed steel milling cutters of various forms and sizes. Removal of the risers, sand blasting to improve the appearance, and grinding the cutting edges are the only machining operations required. The bore is used as cast. Numerous tests have shown that the life of these cutters compares favorably with high-speed steel cutters made in the usual way.

Extrusion of Metals

The Basic Process.— Extrusion is a metalworking process used to produce long, straight semifinished products such as bars, tubes, solid and hollow sections, wire and strips by squeezing a solid slug of metal, either cast or wrought, from a closed container through a die. An analogy to the process is the dispensing of toothpaste from a collapsible tube.

During extrusion, compressive and shear, but no tensile, forces are developed in the stock, thus allowing the material to be heavily deformed without fracturing. The extrusion process can be performed at either room or high temperature, depending on the alloy and method. Cross sections of varying complexity can also be produced, depending on the materials and dies used.

In the specially constructed presses used for extrusion, the load is transmitted by a ram through an intermediate dummy block to the stock. The press container is usually fitted with a wear-resistant liner and is constructed to withstand high radial loads. The die stack consists of the die, die holder, and die backer, all of which are supported in the press end housing or platen, which resists the axial loads.

The following are characteristics of different extrusion methods and presses: 1) The movement of the extrusion relative to the ram. In "direct extrusion," the ram is advanced toward the die stack; in "indirect extrusion," the die moves down the container bore; 2) The position of the press axis, which is either horizontal or vertical; 3) The type of drive, which is either hydraulic or mechanical; and 4) The method of load application, which is either conventional or hydrostatic.

In forming a hollow extrusion, such as a tube, a mandrel integral with the ram is pushed through the previously pierced raw billet.

Cold Extrusion: Cold extrusion has often been considered a separate process from hot extrusion; however, the only real difference is that cold or only slightly warm billets are used as starting stock. Cold extrusion is not limited to certain materials; the only limiting factor is the stresses in the tooling. In addition to the soft metals such as lead and tin, aluminum alloys, copper, zirconium, titanium, molybdenum, beryllium, vanadium, niobium, and steel can be extruded cold or at low deformation temperatures. Cold extrusion has many advantages, such as no oxidation or gas/metal reactions; high mechanical properties due to cold working if the heat of deformation does not initiate recrystallization; narrow tolerances; good surface finish if optimum lubrication is used; fast extrusion speeds can be used with alloys subject to hot shortness.

Examples of cold extruded parts are collapsible tubes, aluminum cans, fire extinguisher cases, shock absorber cylinders, automotive pistons, and gear blanks.

Hot Extrusion: Most hot extrusion is performed in horizontal hydraulic presses rated in size from 250 to 12,000 tons. The extrusions are long pieces of uniform cross sections, but complex cross sections are also produced. Most types of alloys can be hot extruded.

Owing to the temperatures and pressures encountered in hot extrusion, the major problems are the construction and the preservation of the equipment. The following are approximate temperature ranges used to extrude various types of alloys: magnesium, 650–850

Copyright 2004, Industrial Press, Inc., New York, NY

degrees F; aluminum, 650–900 degrees F; copper, 1200–2000 degrees F; steel, 2200–2400 degrees F; titanium, 1300–2100 degrees F; nickel 1900–2200 degrees F; refractory alloys, up to 4000 degrees F. In addition, pressures range from as low as 5000 to over 100,000 psi. Therefore, lubrication and protection of the chamber, ram, and die are generally required. The use of oil and graphite mixtures is often sufficient at the lower temperatures; while at higher temperatures, glass powder, which becomes a molten lubricant, is used.

Extrusion Applications: The stress conditions in extrusion make it possible to work materials that are brittle and tend to crack when deformed by other primary metalworking processes. The most outstanding feature of the extrusion process, however, is its ability to produce a wide variety of cross-sectional configurations; shapes can be extruded that have complex, nonuniform, and nonsymmetrical sections that would be difficult or impossible to roll or forge. Extrusions in many instances can take the place of bulkier, more costly assemblies made by welding, bolting, or riveting. Many machining operations may also be reduced through the use of extruded sections. However, as extrusion temperatures increase, processing costs also increase, and the range of shapes and section sizes that can be obtained becomes narrower.

While many asymmetrical shapes are produced, symmetry is the most important factor in determining extrudability. Adjacent sections should be as nearly equal as possible to permit uniform metal flow through the die. The length of their protruding legs should not exceed 10 times their thickness.

The size and weight of extruded shapes are limited by the section configuration and properties of the material extruded. The maximum size that can be extruded on a press of a given capacity is determined by the "circumscribing circle," which is defined as the smallest diameter circle that will enclose the shape. This diameter controls the die size, which in turn is limited by the press size. For instance, the larger presses are generally capable of extruding aluminum shapes with a 25-in.-diameter circumscribing circle and steel and titanium shapes with about 22-in.-diameter circle.

The minimum cross-sectional area and minimum thickness that can be extruded on a given size press are dependent on the properties of the material, the extrusion ratio (ratio of the cross-sectional area of the billet to the extruded section), and the complexity of shape. As a rule thicker sections are required with increased section size.

The following table gives the approximate minimum cross section and minimum thickness of some commonly extruded metals.

Material	Minimum Cross Section (sq in.)	Minimum Thickness (in.)
Carbon and alloy steels	0.40	0.120
Stainless steels	0.45-0.70	0.120-0.187
Titanium	0.50	0.150
Aluminum	<0.40	0.040
Magnesium	<0.40	0.040

Extruded shapes minimize and sometimes eliminate the need for machining; however, they do not have the dimensional accuracy of machined parts. Smooth surfaces with finishes better than 30 µin. rms are attainable in magnesium and aluminum; an extruded finish of 125 µin. rms is generally obtained with most steels and titanium alloys. Minimum corner and fillet radii of $\frac{1}{64}$ in. are preferred for aluminum and magnesium alloys; while for steel, minimum corner radii of 0.030 in. and fillet radii of 0.125 in. are typical.

Extrusion of Tubes: In tube extrusion, the metal passes through a die, which determines its outer diameter, and around a central mandrel, which determines its inner diameter. Either solid or hollow billets may be used, with the solid billet being used most often. When a solid billet is extruded, the mandrel must pierce the billet by pushing axially through it before the metal can pass through the annular gap between the die and the man-

Copyright 2004, Industrial Press, Inc., New York, NY

drel. Special presses are used in tube extrusion to increase the output and improve the quality compared to what is obtained using ordinary extrusion presses. These special hydraulic presses independently control ram and mandrel positioning and movement.

Powder Metallurgy

Powder metallurgy is a process whereby metal parts in large quantities can be made by the compressing and sintering of various powdered metals such as brass, bronze, aluminum, and iron. Compressing of the metal powder into the shape of the part to be made is done by accurately formed dies and punches in special types of hydraulic or mechanical presses. The "green" compressed pieces are then sintered in an atmosphere controlled furnace at high temperatures, causing the metal powder to be bonded together into a solid mass. A subsequent sizing or pressing operation and supplementary heat treatments may also be employed. The physical properties of the final product are usually comparable to those of cast or wrought products of the same composition. Using closely controlled conditions, steel of high hardness and tensile strength has also been made by this process.

Any desired porosity from 5 to 50 per cent can be obtained in the final product. Large quantities of porous bronze and iron bearings, which are impregnated with oil for self-lubrication, have been made by this process. Other porous powder metal products are used for filtering liquids and gases. Where continuous porosity is desired in the final product, the voids between particles are kept connected or open by mixing one per cent of zinc stearate or other finely powdered metallic soap throughout the metal powder before briquetting and then boiling this out in a low temperature baking before the piece is sintered.

The dense type of powdered metal products include refractory metal wire and sheet, cemented carbide tools, and electrical contact materials (products which could not be made as satisfactorily by other processes) and gears or other complex shapes which might also have been made by die casting or the precise machining of wrought or cast metal.

Advantages of Powder Metallurgy.— Parts requiring irregular curves, eccentrics, radial projections, or recesses often can be produced only by powder metallurgy. Parts that require irregular holes, keyways, flat sides, splines or square holes that are not easily machined, can usually be made by this process. Tapered holes and counter-bores are easily produced. Axial projections can be formed but the permissible size depends on the extent to which the powder will flow into the die recesses. Projections not more than one-quarter the length of the part are practicable. Slots, grooves, blind holes, and recesses of varied depths are also obtainable.

Limiting Factors in Powdered Metal Process.— The number and variety of shapes that may be obtained are limited by lack of plastic flow of powders, i.e., the difficulty with which they can be made to flow around corners. Tolerances in diameter usually cannot be held closer than 0.001 inch and tolerances in length are limited to 0.005 inch. This difference in diameter and length tolerances may be due to the elasticity of the powder and spring of the press.

Factors Affecting Design of Briquetting Tools.— High-speed steel is recommended for dies and punches and oil-hardening steel for strippers and knock-outs. One manufacturer specifies dimensional tolerances of 0.0002 inch and super-finished surfaces for these tools. Because of the high pressures employed and the abrasive character of certain refractory materials used in some powdered metal composition, there is frequently a tendency toward severe wear of dies and punches. In such instances, carbide inserts, chrome plating, or highly resistant die steels are employed. With regard to the shape of the die, corner radii, fillets, and bevels should be used to avoid sharp corners. Feather edges, threads, and reentrant angles are usually impracticable. The making of punches and dies is particularly exacting because allowances must be made for changes in dimensions due to growth after pressing and shrinkage or growth during sintering.

Copyright 2004, Industrial Press, Inc., New York, NY

SOLDERING AND BRAZING

Metals may be joined without using fasteners by employing soldering, brazing, and welding. Soldering involves the use of a non-ferrous metal whose melting point is below that of the base metal and in all cases below 800 degrees F. Brazing entails the use of a non-ferrous filler metal with a melting point below that of the base metal but above 800 degrees F. In fusion welding, abutting metal surfaces are made molten, are joined in the molten state, and then allowed to cool. The use of a filler metal and the application of pressure are considered to be optional in the practice of fusion welding.

Soldering

Soldering employs lead- or tin-base alloys with melting points below 800 degrees F and is commonly referred to as soft soldering. Use of hard solders, silver solders and spelter solders which have silver, copper, or nickel bases and have melting points above 800 degrees F is known as brazing. Soldering is used to provide a convenient joint that does not require any great mechanical strength. It is used in a great many instances in combination with mechanical staking, crimping or folding, the solder being used only to seal against leakage or to assure electrical contact. The accompanying table, page 1381, gives some of the properties and uses of various solders that are generally available.

Forms Available.— Soft solders can be obtained in bar, cake, wire, pig, slab ingot, ribbon, segment, powder, and foil-form for various uses to which they are put. In bar form they are commonly used for hand soldering. The pigs, ingots, and slabs are used in operations that employ melting kettles. The ribbon, segment, powder and foil forms are used for special applications and the cake form is used for wiping. Wire forms are either solid or they contain acid or rosin cores for fluxing. These wire forms, both solid and core containing, are used in hand and automatic machine applications. Prealloyed powders, suspended in a fluxing medium, are frequently applied by brush and, upon heating, consistently wet the solderable surfaces to produce a satisfactory joint.

Fluxes for Soldering.— The surfaces of the metals being joined in the soldering operation must be clean in order to obtain an efficient joint. Fluxes clean the surfaces of the metal in the joint area by removing the oxide coating present, keep the area clean by preventing formation of oxide films, and lower the surface tension of the solder thereby increasing its wetting properties. Rosin, tallow, and stearin are mild fluxes which prevent oxidation but are not too effective in removing oxides present. Rosin is used for electrical applications since the residue is non-corrosive and non-conductive. Zinc chloride and ammonium chloride (sal ammoniac), used separately or in combination, are common fluxes that remove oxide films readily. The residue from these fluxes may in time cause trouble, due to their corrosive effects, if they are not removed or neutralized. Washing with water containing about 5 ounces of sodium citrate (for non-ferrous soldering) or 1 ounce of trisodium phosphate (for ferrous and non-ferrous soldering) per gallon followed by a clear water rinse or washing with commercial water-soluble detergents are methods of inactivating and removing this residue.

Methods of Application.— Solder is applied using a soldering iron, a torch, a solder bath, electric induction or resistance heating, a stream of hot neutral gas or by wiping. Clean surfaces which are hot enough to melt the solder being applied or accept molten solder are necessary to obtain a good clean bond. Parts being soldered should be free of oxides, dirt, oil, and scale. Scraping and the use of abrasives as well as fluxes are resorted to for preparing surfaces for soldering. The procedures followed in soldering aluminum, magnesium and stainless steel differ somewhat from conventional soldering techniques and are indicated in the material which follows

Soldering Aluminum: Two properties of aluminum which tend to make it more difficult to solder are its high thermal conductivity and the tenacity of its ever-present oxide film.

Copyright 2004, Industrial Press, Inc., New York, NY

Properties of Soft Solder Alloys *Appendix, ASTM:B 32-70*

Nominal Composition[a] Per Cent				Specific Gravity[b]	Melting Ranges,[c] Degrees Fahrenheit		Uses
Sn	Pb	Sb	Ag		Solidus	Liquidus	
70	30	…	…	8.32	361	378	For coating metals.
63	37	…	…	8.40	361	361	As lowest melting solder for dip and hand soldering methods.
60	40	…	…	8.65	361	374	"Fine Solder." For general purposes, but particularly where the temperature requirements are critical.
50	50	…	…	8.85	361	421	For general purposes. Most popular of all.
45	55	…	…	8.97	361	441	For automobile radiator cores and roofing seams.
40	60	…	…	9.30	361	460	Wiping solder for joining lead pipes and cable sheaths. For automobile radiator cores and heating units.
35	65	…	…	9.50	361	477	General purpose and wiping solder.
30	70	…	…	9.70	361	491	For machine and torch soldering.
25	75	…	…	10.00	361	511	For machine and torch soldering.
20	80	…	…	10.20	361	531	For coating and joining metals. For filling dents or seams in automobile bodies.
15	85	…	…	10.50	440[d]	550	For coating and joining metals.
10	90	…	…	10.80	514[d]	570	For coating and joining metals.
5	95	…	…	11.30	518	594	For coating and joining metals.
40	58	2	…	9.23	365	448	Same uses as (50-50) tin-lead but not recommended for use on galvanized iron.
35	63.2	1.8	…	9.44	365	470	For wiping and all uses except on galvanized iron.
30	68.4	1.6	…	9.65	364	482	For torch soldering or machine soldering, except on galvanized iron.
25	73.7	1.3	…	9.96	364	504	For torch and maching soldering, except on galvanized iron.
20	79	1	…	10.17	363	517	For machine soldering and coating of metals, tipping, and like uses, but not recommended for use on galvanized iron.
95	…	5	…	7.25	452	464	For joints on copper in electrical, plumbing and heating work.
…	97.5	…	2.5	11.35	579	579	For use on copper, brass, and similar metals with torch heating. Not recommended in humid environments due to its known susceptibility to corrosion.
1	97.5	…	1.5	11.28	588	588	For use on copper, brass, and similar metals with torch heating.

[a] Abbreviations of alloying elements are as follows: Sn, tin; Pb, lead; Sb, antimony; and Ag, silver.

[b] The specific gravity multiplied by 0.0361 equals the density in pounds per cubic inch.

[c] The alloys are completely solid below the lower point given, designated "solidus," and completely liquid above the higher point given, designated "liquidus." In the range of temperatures between these two points the alloys are partly solid and partly liquid.

[d] For some engineering design purposes, it is well to consider these alloys as having practically no mechanical strength above 360 degrees F.

Aluminum soldering is performed in a temperature range of from 550 to 770 degrees F, compared to 375 to 400 degrees F temperature range for ordinary metals, because of the metal's high thermal conductivity. Two methods can be used, one using flux and one using abrasion. The method employing flux is most widely used and is known as flow soldering. In this method flux dissolves the aluminum oxide and keeps it from re-forming. The flux should be fluid at soldering temperatures so that the solder can displace it in the joint. In the friction method the oxide film is mechanically abraded with a soldering iron, wire brush, or multi-toothed tool while being covered with molten solder. The molten solder keeps the oxygen in the atmosphere from reacting with the newly-exposed aluminum surface; thus wetting of the surface can take place.

The alloys that are used in soldering aluminum generally contain from 50 to 75 per cent tin with the remainder zinc.

The following aluminum alloys are listed in order of ease of soldering: commercial and high-purity aluminum; wrought alloys containing not more than 1 per cent manganese or magnesium; and finally the heat-treatable alloys which are the most difficult.

Copyright 2004, Industrial Press, Inc., New York, NY

Cast and forged aluminum parts are not generally soldered.

Soldering Magnesium: Magnesium is not ordinarily soldered to itself or other metals. Soldering is generally used for filling small surface defects, voids or dents in castings or sheets where the soldered area is not to be subjected to any load. Two solders can be used: one with a composition of 60 per cent cadmium, 30 per cent zinc, and 10 per cent tin has a melting point of 315 degrees F; the other has a melting point of 500 degrees F and has a nominal composition of 90 per cent cadmium and 10 per cent zinc.

The surfaces to be soldered are cleaned to a bright metallic luster by abrasive methods before soldering. The parts are preheated with a torch to the approximate melting temperature of the solder being used. The solder is applied and the surface under the molten solder is rubbed vigorously with a sharp pointed tool or wire brush. This action results in the wetting of the magnesium surface. To completely wet the surface, the solder is kept molten and the rubbing action continued. The use of flux is not recommended.

Soldering Stainless Steel: Stainless steel is somewhat more difficult to solder than other common metals. This is true because of a tightly adhering oxide film on the surface of the metal and because of its low thermal conductivity. The surface of the stainless steel must be thoroughly cleaned. This can be done by abrasion or by clean white pickling with acid. Muriatic (hydrochloric) acid saturated with zinc or combinations of this mixture and 25 per cent additional muriatic acid, or 10 per cent additional acetic acid, or 10 to 20 per cent additional water solution of orthophosphoric acid may all be used as fluxes for soldering stainless steel. Tin-lead solder can be used successfully. Because of the low thermal conductivity of stainless steel, a large soldering iron is needed to bring the surfaces to the proper temperature. The proper temperature is reached when the solder flows freely into the area of the joint. Removal of the corrosive flux is important in order to prevent joint failure. Soap and water or a commercial detergent may be used to remove the flux residue.

Ultrasonic Fluxless Soldering.— This more recently introduced method of soldering makes use of ultrasonic vibrations which facilitates the penetration of surface films by the molten solder thus eliminating the need for flux. The equipment offered by one manufacturer consists of an ultrasonic generator, ultrasonic soldering head which includes a transducer coupling, soldering tip, tip heater, and heating platen. Metals that can be soldered by this method include aluminum, copper, brass, silver, magnesium, germanium, and silicon.

Brazing

Brazing is a metal joining process which uses a non-ferrous filler metal with a melting point below that of the base metals but above 800 degrees F. The filler metal wets the base metal when molten in a manner similar to that of a solder and its base metal. There is a slight diffusion of the filler metal into the hot, solid base metal or a surface alloying of the base and filler metal. The molten metal flows between the close-fitting metals because of capillary forces.

Filler Metals for Brazing Applications.— Brazing filler metals have melting points that are lower than those of the base metals being joined and have the ability when molten to flow readily into closely fitted surfaces by capillary action. The commonly used brazing metals may be considered as grouped into the seven standard classifications shown in Tables 1a and 1b. These are aluminum-silicon; copper-phosphorus; silver; nickel; copper and copper-zinc; magnesium; and precious metals.

The solidus and liquidus are given in Tables 1a and 1b instead of the melting and flow points in order to avoid confusion. The solidus is the highest temperature at which the metal is completely solid or, in other words, the temperature above which the melting starts. The liquidus is the lowest temperature at which the metal is completely liquid, that is, the temperature below which the solidification starts.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. Brazing Filler Metals [Based on Specification and Appendix of *American Welding Society AWS A5.8–81*]

AWS Classification[a]	Nominal Composition,[b] Per Cent						Temperature, Degrees F			Standard Form[c]	Uses
	Ag	Cu	Zn	Al	Ni	Other	Solidus	Liquidus	Brazing Range		
BAlSi-2	…	…	…	92.5	…	Si, 7.5	1070	1135	1110–1150	7	For joining the following aluminum alloys: 1060, EC, 1100, 3003, 3004, 5005, 5050, 6053, 6061, 6062, 6063, 6951 and cast alloys A612 and C612. All of these filler metals are suitable for furnace and dip brazing. BAlSi-3, -4 and -5 are suitable for torch brazing. Used with lap and tee joints rather than butt joints. Joint clearances run from .006 to .025 inch.
BAlSi-3	…	4	…	86	…	Si, 10	970	1085	1160–1120	2, 3, 5	
BAlSi-4	…	…	…	88	…	Si, 12	1070	1080	1080–1120	2, 3, 4, 5	
BAlSi-5	…	…	…	90	…	Si, 10	1070	1095	1090–1120	7	
BAlSi-6	…	…	…	90	…	Si, 7.5; Mg. 2.5	1038	1125	1110–1150	7	BAlSi-6 through -11 are vacuum brazing filler metals. Magnesium is present as an O_2 getter. When used in vacuum, solidus & liquidus temperatures are different from those shown.
BAlSi-7	…	…	…	88.5	…	Si, 10; Mg, 1.5	1038	1105	1090–1120	7	
BAlSi-8	…	…	…	86.5	…	Si, 12; Mg, 1.5	1038	1075	1080–1120	2, 7	
BAlSi-9	…	…	…	87	…	Si, 12; Mg, 0.3	1044	1080	1080–1120	7	
BAlSi-10	…	…	…	86.5	…	Si, 11; Mg, 2.5	1038	1086	1080–1120	2	
BAlSi-11	…	…	…	88.4	…	Si, 10 Mg, 1.5; Bi, 0.1	1038	1105	1090–1120	7	
BCuP-1	…	95	…	…	…	P, 5	1310	1695	1450–1700	1	For joining copper and its alloys with some limited use on silver, tungsten and molybdenum. Not for use on ferrous or nickel-base alloys. Are used for cupro-nickels but caution should be exercised when nickel content is greater than 30 per cent. Suitable for all brazing processes. Lap joints recommended but butt joints may be used. Clearances used range from .001 to .005 inch.
BCuP-2	…	93	…	…	…	P, 7	1310	1460	1350–1550	2, 3, 4	
BCuP-3	5	89	…	…	…	P, 6	1190	1485	1300–1500	2, 3, 4	
BCuP-4	6	87	…	…	…	P, 7	1190	1335	1300–1450	2, 3, 4	
BCuP-5	15	80	…	…	…	P, 5	1190	1475	1300–1500	1, 2, 3, 4	
BCuP-6	2	91	…	…	…	P, 7	1190	1450	1350–1500	2, 3, 4	
BCuP-7	5	88	…	…	…	P, 6.8	1190	1420	1300–1500	2, 3, 4	
BAg-1	45	15	16	…	…	Cd, 24	1125	1145	1145–1400	1, 2, 4	For joining most ferrous and nonferrous metals except aluminum and magnesium. These filler metals have good brazing properties and are suitable for preplacement in the joint or for manual feeding into the joint. All methods of heating may be used. Lap joints are generally used; however, butt joints may be used. Joint clearances of .002 to .005 inch are recommended. Flux is generally required.
BAg-1a	50	15.5	16.5	…	…	Cd, 18	1160	1175	1175–1400	1, 2, 4	
BAg-2	35	26	21	…	…	Cd, 18	1125	1295	1295–1550	1, 2, 4, 7	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. ***(Continued)*** **Brazing Filler Metals [Based on Specification and Appendix of** *American Welding Society AWS A5.8–81*]

AWS Classification[a]	Nominal Composition,[b] Per Cent						Temperature, Degrees F			Standard Form[c]	Uses
	Ag	Cu	Zn	Al	Ni	Other	Solidus	Liquidus	Brazing Range		
BAg-2a	30	27	23	…	…	Cd, 20	1125	1310	1310–1550	1, 2, 4	For joining most ferrous and nonferrous metals except aluminum and magnesium. These filler metals have good brazing properties and are suitable for preplacement in the joint or for manual feeding into the joint. All methods of heating may be used. Lap joints are generally used; however, butt joints may be used. Joint clearances of .002 to .005 inch are recommended. Flux is generally required.
BAg-3	50	15.5	15.5	…	3	Cd, 16	1170	1270	1270–1500	1, 2, 4, 7	
BAg-4	40	30	28	…	2	…	1240	1435	1435–1650	1, 2	
BAg-5	45	30	25	…	…	…	1250	1370	1370–1550	1, 2	
BAg-6	50	34	16	…	…	…	1270	1425	1425–1600	1, 2	
BAg-7	56	22	17	…	…	Sn, 5	1145	1205	1205–1400	1, 2	
BAg-8	72	28	…	…	…	…	1435	1435	1435–1650	1, 2, 4	
BAg-8a	72	27.8	…	…	…	Li, 2.	1410	1410	1410–1600	1, 2	
BAg-13	54	40	5	…	1	…	1325	1575	1575–1775	1, 2	
BAg-13a	56	42	…	…	2	…	1420	1640	1600–1800	1, 2	
BAg-18	60	30	…	…	…	Sn, 10	1115	1325	1325–1550	1, 2	
BAg-19	92.5	7.3	…	…	…	Li, 2	1435	1635	1610–1800	1, 2	
BAg-20	30	38	32	…	…	…	1250	1410	1410–1600	1, 2, 4	
BAg-21	63	28.5	…	…	2.5	Sn, 6	1275	1475	1475–1650	1, 2, 4	
BAg-22	49	16	23	…	4.5	Mn, 7.5	1260	1290	1290–1525	1, 2, 4, 7	
BAg-23	85	…	…	…	…	Mn, 15	1760	1780	1780–1900	1, 2, 4	
BAg-24	50	20	28	…	2	…	1220	1305	1305–1550	1, 2	
BAg-25	20	40	35	…	…	Mn, 5	1360	1455	1455–1555	2, 4	
BAg-26	25	38	33	…	2	Mn, 2	1305	1475	1475–1600	1, 2, 4, 7	
BAg-27	25	35	26.5	…	…	Cd, 13.5	1125	1375	1375–1575	1, 2, 4	
BAg-28	40	30	28	…	…	Sn, 2	1200	1310	1310–1550	1, 2, 4	

[a] These classifications contain chemical symbols preceded by "B" which stands for brazing filler metal.

[b] These are nominal compositions. Trace elements may be present in small amounts and are not shown. Abbreviations used are: Ag, silver; Cu, copper; Zn, zinc; Al, aluminum; Ni, nickel; Ot, other; Si, silicon; P, phosphorus; Cd, cadmium; Sn, tin; Li, lithium; Cr, chromium; B, boron; Fe, iron; O, oxygen; Mg, magnesium; W, tungsten; Pd, palladium; and Au, gold.

[c] Numbers specify standard forms as follows: 1, strip; 2, wire; 3, rod; 4, powder; 5, sheet; 6, paste; 7, clad sheet or strip; and 8, transfer tape.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Brazing Filler Metals [Based on Specification and Appendix of *American Welding Society AWS A5.8–81*]

AWS Classification[a]	Nominal Composition,[b] Per Cent						Temperature, Degrees F			Standard Form[c]	Uses
	Ni	Cu	Cr	B	Si	Other	Solidus	Liquidus	Brazing Range		
BNi-1	74	…	14	3.5	4	Fe, 4.5	1790	1900	1950–2200	1, 2, 3, 4, 8	For brazing AISI 300 and 400 series stainless steels, and nickel- and cobalt-base alloys. Particularly suited to vacuum systems and vacuum tube applications because of their very low vapor pressure. The limiting element is chromium in those alloys in which it is employed. Special brazing procedures required with filler metal containing manganese.
BNi-2	82.5	…	7	3	4.5	Fe, 3	1780	1830	1850–2150	1, 2, 3, 4, 8	
BNi-3	91	…	…	3	4.5	Fe, 1.5	1800	1900	1850–2150	1, 2, 3, 4, 8	
BNi-4	93.5	…	…	1.5	3.5	Fe, 1.5	1800	1950	1850–2150	1, 2, 3, 4, 8	
BNi-5	71	…	19	…	10	…	1975	2075	2100–2200	1, 2, 3, 4, 8	
BNi-6	89	…	…	…	…	P, 11	1610	1610	1700–1875	1, 2, 3, 4, 8	
BNi-7	77	…	13	…	…	P, 10	1630	1630	1700–1900	1, 2, 3, 4, 8	
BNi-8	65.5	4.5	…	…	7	Mn, 23	1800	1850	1850–2000	1, 2, 3, 4, 8	
BCu-1	…	100	…	…	…	…	1980	1980	2000–2100	1, 2	For joining various ferrous and nonferrous metals. They can also be used with various brazing processes. Avoid overheating the Cu-Zn alloys. Lap and butt joints are commonly used.
BCu-1a	…	99	…	…	…	Ot, 1	1980	1980	2000–2100	4	
BCu-2	…	86.5	…	…	…	O, 13.5	1980	1980	2000–2100	6	
RBCuZn-A	…	59	…	…	…	Zn, 41	1630	1650	1670–1750	1, 2, 3	
RBCuZn-C	…	58	…	…	0.1	Zn, 40; Fe, 0.7; Mn, 0.3; Sn, 1	1590	1630	1670–1750	2	
RBCuZn-D	10	48	…	…	0.2	Zn, 42	1690	1715	1720–1800	1, 2, 3	
BCuZn-E	…	50	…	…	…	Zn, 50	1595	1610	1610–1725	1, 2, 3, 4, 5	
BCuZn-F	…	50	…	…	…	Zn, 46.5; Sn, 3.5	1570	1580	1580–1700	1, 2, 3, 4, 5	
BCuZn-G	…	70	…	…	…	Zn, 30	1680	1750	1750–1850	1, 2, 3, 4, 5	
BCuZn-H	…	80	…	…	…	Zn, 20	1770	1830	1830–1950	1, 2, 3, 4, 5	
BMg-1	…	…	…	…	…	[a]	830	1100	1120–1160	2, 3	BMg-1 is used for joining AZ10A, K1A, and M1A magnesium-base metals.
BAu-1	…	63	…	…	…	Au, 37	1815	1860	1860–2000	1, 2, 4	For brazing of iron, nickel, and cobalt-base metals where resistance to oxidation or corrosion is required. Low rate of interaction with base metal facilitates use on thin base metals. Used with induction, furnace, or resistance heating in a reducing atmosphere or in a vacuum and with no flux. For other applications, a borax-boric acid flux is used.
BAu-2	…	20.5	…	…	…	Au, 79.5	1635	1635	1635–1850	1, 2, 4	
BAu-3	3	62.5	…	…	…	Au, 34.5	1785	1885	1885–1995	1, 2, 4	
BAu-4	18.5	…	…	…	…	Au, 81.5	1740	1740	1740–1840	1, 2, 4	
BAu-5	36	…	…	…	…	Au, 30; Pd, 34	2075	2130	2130–2250	1, 2, 4	
BAu-6	22	…	…	…	…	Au, 70; Pd, 8	1845	1915	1915–2050	1, 2, 4	
BCo-1	17	…	…	…	8	Cr, 19; W, 4; B, 0.8; C, 0.4; Co, 59	2050	2100	2100–2250	1, 3, 4, 8	Generally used for high temperature properties and compatability with cobalt-base metals.

[a] Al, 9; Zn, 2; Mg, 89.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Guide to Selection of Brazing Filler Metals and Fluxes

Base Metals Being Brazed	Filler Metals Recommended[a]	AWS Brazing Flux Type No.	Effective Temperature Range, Degrees F	Flux Ingredients	Flux Supplied As	Flux Method of Use[b]
All brazeable aluminum alloys	BA1Si	1	700 to 1190	Chlorides, Fluorides	Powder	1, 2 3, 4
All brazeable magnesium alloys	BMg	2	900 to 1200	Chloides, Fluorides	Powder	3, 4
Alloys such as aluminum-bronze; aluminum- brass containing additions of aluminum of 0.5 per cent or more	BCuZn, BCuP	4[c]	1050 to 1800	Chlorides, Fluorides, Borates, Wetting agent	Paste or Powder	1, 2, 3
Titanium and zirconium in base alloys	BAg	6	700 to 1600	Chlorides, Fluorides, Wetting agent	Paste or Powder	1, 2, 3
Any other brazeable alloys not listed above	All brazing filler metals except BA1Si and BMg	3	700 to 2000	Boric acid, Borates, Fluorides, Fluooates, Wetting agent *Must contain fluorine compound*	Paste, Powder, or Liquid	1, 2, 3
	All brazing filler metals except BA1Si, BMg, and BAg 1 through BAg 7	5	1000 to 2200	Borax, Boric acid Borates, Wetting agent *No fluorine in any form*	Paste, Powder, or Liquid	1, 2, 3

[a] Abbreviations used in this column are as follows: B, brazing filler metal; Al, aluminum; Si, silicon; Mg, magnesium; Cu, copper; Zn, zinc; P, phosphorus; and Ag, silver.

[b] Explanation of numbering system used is as follows: 1—dry powder is sprinkled in joint region; 2—heated metal filler rod is dipped into powder or paste; 3—flux is mixed with alcohol, water, monochlorobenzene, etc., to form a paste or slurry; 4—flux is used molten in a bath.

[c] Types 1 and 3 fluxes, alone or in combination, may be used with some of these base metals also.

Fluxes for Brazing.— In order to obtain a sound joint the surfaces in and adjacent to the joint must be free from dirt, oil, and oxides or other foreign matter at the time of brazing. Cleaning may be achieved by chemical or mechanical means. Some of the mechanical means employed are filing, grinding, scratch brushing and machining. The chemical means include the use of trisodium phosphate, carbon tetrachloride, and trichloroethylene for removing oils and greases.

Fluxes are used mainly to prevent the formation of oxides and to remove any oxides on the base and filler metals. They also promote free flow of the filler metal during the course of the brazing operation.

They are made available in the following forms: powders; pastes or solutions; gases or vapors; and as coatings on the brazing rods.

In the powder form a flux can be sprinkled along the joint, provided that the joint has been preheated sufficiently to permit the sprinkled flux to adhere and not be blown away by the torch flame during brazing. A thin paste or solution is easily applied and when spread on evenly, with no bare spots, gives a very satisfactory flux coating. Gases or vapors are used in controlled atmosphere furnace brazing where large amounts of assemblies are mass-brazed. Coatings on the brazing rods protect the filler metal from becoming oxidized and eliminate the need for dipping rods into the flux, but it is recommended that flux be applied to the base metal since it may become oxidized in the heating operation. No matter which flux is used, it performs its task only if it is chemically active at the brazing temperature.

Chemical compounds incorporated into brazing fluxes include borates (sodium, potassium, lithium, etc.), fused borax, fluoborates (potassium, sodium, etc.), fluorides (sodium,

Copyright 2004, Industrial Press, Inc., New York, NY

potassium, lithium, etc.), chlorides (sodium, potassium, lithium), acids (boric, calcined boric acid), alkalies (potassium hydroxide, sodium hydroxide), wetting agents, and water (either as water of crystallization or as an addition for paste fluxes). Table 2 provides a guide which will aid in the selection of brazing fluxes that are available commercially.

Methods of Steadying Work for Brazing.— Pieces to be joined by brazing after being properly jointed may be held in a stable position by means of clamping devices, spot welds, or mechanical means such as crimping, staking, or spinning. When using clamping devices care must be taken to avoid the use of devices containing springs for applying pressure because springs tend to lose their properties under the influence of heat. Care must also be taken to be sure that the clamping devices are no larger than is necessary for strength considerations, because a large metal mass in contact with the base metal near the brazing area would tend to conduct heat away from the area too quickly and result in an inefficient braze. Thin sections that are to be brazed are frequently held together by spot welds. It must be remembered that these spot welds may interfere with the flow of the molten brazing alloy and appropriate steps must be taken to be sure that the alloy is placed where it can flow into all portions of the joint.

Methods of Supplying Heat for Brazing.— The methods of supplying heat for brazing form the basis of the classification of the different brazing methods and are as follows.

Torch or Blowpipe Brazing: Air-gas, oxy-acetylene, air-acetylene, and oxy-other fuel gas blowpipes are used to bring the areas of the joint and the filler material to the proper heat for brazing. The flames should generally be neutral or slightly reducing but in some instances some types of bronze welding require a slightly oxidizing flame.

Dip Brazing: Baths of molten alloy, covered with flux, or baths of molten salts are used for dip brazing. The parts to be brazed are first assembled, usually with the aid of jigs, and are dipped into the molten metal, then raised and allowed to drain. The molten alloy enters the joint by capillary action. When the salt bath is used, the filler metal is first inserted between the parts being joined, or, in the form of wire, is wrapped around the area of the joint. The brazing metal melts and flows into the joint, again by capillary action.

Furnace Brazing: Furnaces that are heated electrically or by gas or oil with auxiliary equipment that maintains a reducing or protective atmosphere and controlled temperatures therein are used for brazing large numbers of units, usually without flux.

Resistance Brazing: Heat is supplied by means of hot or incandescent electrodes. The heat is produced by the resistance of the electrodes to the flow of electricity and the filler metal is frequently used as an insert between the parts being joined.

Induction Brazing: Parts to be joined are heated by being placed near a coil carrying an electric current. Eddy current losses of the induced electric current are dissipated in the form of heat raising the temperature of the work to a point higher than the melting point of the brazing alloy. This method is both quick and clean.

Vacuum Furnace Brazing: Cold-wall vacuum furnaces, with electrical-resistance radiant heaters, and pumping systems capable of evacuating a conditioned chamber to moderate vacuum (about 0.01 micron) in 5 minutes are recommended for vacuum brazing. Metals commonly brazed in vacuum are the stainless steels, heat-resistant alloys, titanium, refractory metals, and aluminum. Fluxes and filler metals containing alloying elements with low boiling points or high vapor pressure are not used.

Brazing Symbol Application.— ANSI/AWS A2.4-79 symbols for brazing are also used for welding with the exception of the symbol for a scarf joint (see the diagram at the top of page 1388, and the symbol for a scarf joint in the table *Basic Weld Symbols* on page 1433, for applications of brazing symbols). The second, third and fourth figures from the top of the next page show how joint clearances are indicated. If no special joint preparation is required, only the arrow is used with the brazing process indicated In the tail.

Copyright 2004, Industrial Press, Inc., New York, NY



Typical Applications of Standard Brazing Symbols

Copyright 2004, Industrial Press, Inc., New York, NY

WELDING

Welding of metals requires that they be heated to a molten state so that they fuse together. A filler wire or rod is held in the heated zone to add material that will replace metal consumed by the process and to produce a slightly raised area that can be dressed down to make a level surface if needed. Most welding operations today use an electric arc, though the autogenous method using a torch that burns a mixture of (usually) acetylene and oxygen gases to heat the components is still used for certain work. Lasers are also used as the heating medium for some welding operations. In arc welding, a low-voltage, high-current arc is struck between the end of an electrode in a holder and the work, generating intense heat that immediately melts tile surface.

Welding Electrodes, Fluxes, and Processes

Electrodes for welding may be made of a tungsten or other alloy that does not melt at welding temperatures (nonconsumable) or of an alloy similar to that of the work so that it melts and acts as the filler wire (consumable). In welding with a nonconsumable electrode, filler metal is added to the pool as welding proceeds. Filler metals that will produce welds having strength properties similar to those of the work are used where high-strength welds are specified.

Briefly, the effects of the main alloying elements in welding filler wires and electrodes are: carbon adds strength but may cause brittle weld metal if cooling is rapid, so low-carbon wire is preferred; silicon adds strength and reduces oxidation, changes fluidity, and gives a flatter weld bead; manganese strengthens and assists deoxidation, plus it reduces effects of sulfur, lowering the risk of hot cracking; sulfur may help form iron sulfide, which increases the risk of hot cracking; and phosphorus, may contribute to hot cracking.

Fluxes in (usually) granular form are added to the weld zone, as coatings on the filler wire or as a core in the tube that forms the (consumable) electrode. The flux melts and flows in the weld zone, shielding the arc from the oxygen in the atmosphere, and often contains materials that clean impurities from the molten metal and prevent grain growth during recrystallization.

Processes.— There are approximately 100 welding and allied welding processes but the four manual arc welding processes: gas metal arc welding (GMAW) (which is also commonly known as MIG for metal inert gas), flux-cored arc (FCAW), shielded metal arc (SMAW), gas tungsten arc welding (GTAW), account for over 90 per cent of the arc welding used in production, fabrication, structural, and repair applications. FCAW and SMAW use fluxes to shield the arc and FCAW uses fluxes and gases to protect the weld from oxygen and nitrogen. GMAW and GTAW use mixtures of gases to protect the weld.

There are two groups of weld types, groove and fillet, which are self-explanatory. Each type of weld may be made with the work at any angle from horizontal (flat) to inverted (overhead). In a vertical orientation, the electrode tip may move down the groove or fillet (vertical down), or up (vertical up). In any weld other than flat, skill is needed to prevent the molten metal falling from the weld area.

Because of the many variables, such as material to be welded and its thickness, equipment, fluxes, gases, electrodes, degree of skill, and strength requirements for the finished welds, it is not practicable to set up a complete list of welding recommendations that would have general validity. Instead, examples embracing a wide range of typical applications, and assuming common practices, are presented here for the most-used welding processes. The recommendations given are intended as a guide to finding the best approach to any welding job, and are to be varied by the user to fit the conditions encountered in the specific welding situation.

Copyright 2004, Industrial Press, Inc., New York, NY

Gas Metal Arc Welding (GMAW)

The two most cost-effective manual arc welding processes are GMAW and FCAW. These two welding processes are used with more than 50 per cent of the arc welding consumable electrodes purchased. Gas metal arc welding modes extend from short-circuit welding, where the consumable electrode wire is melted into the molten pool in a rapid succession of short circuits during which the arc is extinguished, to pulsed and regular spray transfer, where a stream of fine drops and vaporized weld metal is propelled across the continuous arc gap by electromagnetic forces in the arc.

GMAW is the most-used welding process and the two most common GMAW low-carbon steel electrodes used for production welding in North America are the E70S-3 and E70S-6 from the ANSI/AWS Standard A5 series of specifications for arc welding. The E70S-3 contains manganese and silicon as deoxidants and is mainly used for welding low-carbon steels, using argon mixtures as shielding gases. The wire used in the E70S-6 electrodes has more silicon than wire used for the E70S-3 electrodes, and is preferred where straight CO_2 or argon mixes are used as the shielding gas or if the metal to be welded is contaminated. The deoxidizing properties of the E70S-6 electrode also may be beneficial for high-current, deep-penetration welds, and welds in which higher than normal impact-strength properties are required.

E80S-D2 wire contains more manganese and silicon, plus 0.5 per cent molybdenum for welding such steels as AISI 4130, and steels for high-temperature service. The argon + CO_2 mixture is preferred to exert the influence of argon's inertness over the oxidizing action of CO_2. E70S-2 electrodes contain aluminum, titanium, and zirconium to provide greater deoxidation action and are valuable for welding contaminated steel plate.

When the GMAW welding process is used for galvanized steels, minute welding cracks may be caused by the reaction of the zinc coating on the work with silicon in the electrode. Galvanized steel should be welded with an electrode having the lowest possible silicon content such as the E70S-3. For welding low-carbon and low-alloy steels with conventional argon mixture shielding gases, there is little difference between the E70S-3 and E70S-6.

Electrode Diameters.— One of the most important welding decisions is selecting the optimum GMAW electrode diameter. Selection of electrode diameters should be based on the material thickness, as shown for carbon and stainless steels in Table 1, the compatibility of the electrode current requirements with the material thickness, the mode of weld metal transfer, and the deposition rate potential shown in Table 2. The two most popular GMAW electrode sizes are 0.035 in. (1.0 mm) and 0.045 in. (1.2 mm). Diameters of electrodes used for GMAW exert a strong influence on cost of welding. Table 2 also shows how the weld deposition rate varies in short-circuit and spray transfer modes in welding carbon and stainless steels.

Table 1. GMAW Electrode Sizes for Welding Carbon and Stainless Steels

	Electrode Diameter			
Material Thickness	0.030 in. (0.8 mm)	0.035 in. (1.0 mm)	0.045 in. (1.2 mm)	0.062 in. (1.6 mm)
25 to 21 gage (0.020 to 0.032 in.)	yes	…	…	…
20 gage to ¼ in. (0.036 to 0.25 in.)	…	yes	…	…
3/16 to 7/16 in. flat and horizontal	…	…	yes	…
½ in. and up	…	…	…	yes

The table is based on suitability of the electrode size to mode of weld transfer, material thickness, and cost effectiveness. If a smaller electrode size is selected, the lower deposition rates could increase welding costs by 20 to 60 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Typical Maximum GMAW Deposition Rates for Carbon and Stainless Steels. Constant-Voltage 450-amp Power Source and Standard Wire Feeder

Weld transfer mode	Electrode Diameter			
	0.030 in. (0.8 mm)	0.035 in. (1.0 mm)	0.045 in. (1.2 mm)	0.062 in. (1.6 mm)
Short circuit	5 lb/h (2.3 kg/h)	7 lb/h (3.2 kg/h)	9 lb/h (4 kg/h)	…
Spray transfer	9 lb/h (4 kg/h)	11 lb/h (5 kg/h)	19 lb/h (8.6 kg/h)	21 lb/h (9.5 kg/h)

For the lowest-cost welds with GMAW electrodes larger than 0.030 in. in diameter, the power source should provide a minimum of 350 amps. The compatibility of the optimum current range of the 0.035-in. (1.0-mm) electrode and its deposition potential make it the first choice for welding of 20 gage to ¼ in. (0.88 to 6.4 mm) thicknesses. For welding thinner sheet metals of 25 to 21 gage, the optimum electrode diameter is 0.030 in. (0.8 mm). The 0.045-in. (1.2-mm) electrode is the most practical choice for spray transfer applications on materials over ¼ in. (6.4 mm) thick and thicker.

As an example, when welding ¼-in. (6.4-mm) thick steel, with 100 per cent arc-on time and a labor cost of $15/h, the deposition rate with a 0.035-in. (0.9-mm) electrode is approximately 11 lb/h (5 kg/h). The labor cost per lb at $15/h ÷ 11 lb/h = $1.36/lb ($3.00/kg). If an electrode of 0.045-in. (1.2-mm) diameter is used for the same application, the deposition rate is 16 lb/h (7.2 kg/h) and at a $15/h labor rate, the cost of weld metal deposited = $15/h ÷ 16 lb/h = $0.93/lb ($2.00/kg). The 0.045-in. diameter electrode would also cost less per pound than a smaller wire, and the weld time with the 0.045-in. electrode would be reduced, so less shielding gas also would be consumed.

GMAW Welding of Sheet Steel.— In GMAW, the short-circuit transfer mode is used to weld carbon steel, low-alloy steel, and stainless steel sheet of 24 gage (0.023 in., or 0.6 mm) to 11 gage (0.12 in., or 3 mm). The most common gage sizes welded with short-circuit transfer are 20 gage to 11 gage (0.88 to 3 mm) and the best GMAW electrode for these thin, sheet metal gages is the 0.035-in. (1-mm) diameter electrode. The short-circuit current requirements for these operations are typically 50 to 200 amps with voltages in the range of 14 to 22 volts. The optimum short-circuit voltage for the majority of applications is 16 to 18 volts.

Shielding Gases for Welding Carbon and Low-Alloy Steels.— With more than 40 GMAW gas mixtures available for welding carbon steels, low-alloy steels, and stainless steels, selection is often confusing. Reactive oxygen and carbon dioxide (CO_2) are added to argon to stabilize the arc and add energy to the weld. CO_2 can provide more energy to the weld than oxygen. As the CO_2 content in a shielding gas mixture is increased to certain levels, the voltage requirements are increased. Argon + oxygen mixtures will require lower voltages than mixtures containing argon with 10 to 25 per cent CO_2. Helium may also be added to argon if increased weld energy is required.

Shielding Gases for Short-Circuit Welding of Carbon Steels.— GMAW short-circuit transfer (SCT) is used mainly for welding thin metals of less than 10 gage, and gaps. With the SCT mode of weld metal transfer, the arc short circuits many times each second. The numerous short circuits switch the arc energy on and off. The short circuits and low current cause the transferred weld to freeze rapidly. Short-circuit transfer on carbon steel gage metals thicker than 1/16 in. (1.6 mm) requires a shielding gas that will provide substantial weld energy. For these applications, argon with 15–25 per cent CO_2 is recommended.

If short-circuit transfer is used on metals thinner than 18 gage (0.047 in., 1.2 mm), melt-through and distortion often occur. Melt-through and distortion can be reduced on very thin-gage carbon and low-alloy steels by using a shielding gas that provides less weld energy than argon + 15 to 25 per cent CO_2 mixes. Argon + oxygen mixtures can utilize

Copyright 2004, Industrial Press, Inc., New York, NY

lower voltages to sustain the arc. Argon mixed with 2 to 5 per cent oxygen is a practical mixture for thin carbon steel of less than 16 gage, where there is sensitivity to heat.

Shielding Gases for Spray Transfer Welding of Carbon Steels.— With GMAW spray transfer, all traditional argon gas mixtures will provide spatter-free spray weld transfer, depending on the electrode diameter and welding parameters used. The electrode diameter and the electrode current density influence the formation of the weld metal to be transferred. For example, with a 0.035-in. diameter electrode using a mixture containing argon 75 + CO_2 25 per cent, a small globular weld droplet is formed on the end of the electrode tip in the conventional spray transfer parameter range. With the same gas mixture, a 0.045-in. (1.2-mm) diameter electrode, and current above 330 amps, the globular formation disappears and the metal transfers in the spray mode.

Spatter potential stemming from shielding gas, with 0.035-in. (1.0-mm) and smaller diameter electrodes can be controlled by reducing the CO_2 content in the argon mixture to less than 21 per cent. Each different shielding gas will primarily influence the open arc spray transfer mode by variations in the weld energy provided through the welding voltage requirements.

Gas selection in spray transfer must be given careful consideration. In welding of clean cold-rolled carbon steel or low-alloy steel less than $\frac{3}{8}$ in. (9.5 mm) thick, the energy potential of the arc is less important than it is for welding of steels thicker than $\frac{1}{4}$ in. (13 mm) or steels with mill scale. The energy level of the arc is also a key factor in welding steels for which higher than normal impact properties are specified.

A simple, practical multipurpose gas mixture for carbon and low-alloy steels is argon + 15 to 20 per cent CO_2, and a mixture of argon + 17 per cent CO_2 would be ideal. This two-part argon/CO_2 mixture provides higher weld energy than two-component argon + CO_2 mixtures having less than 10 per cent CO_2, argon + oxygen mixtures, or argon + CO_2 + oxygen tri-component mixtures. The argon + 17 per cent CO_2 mixture will provide an arc slightly less sensitive to mill scale than the other mixtures mentioned.

The argon + 17 per cent CO_2 mixture also has practical benefits in that it provides sufficient weld energy for all GMAW short-circuit and spray transfer applications with cylinder or bulk gases. The argon + 17 per cent CO_2 mixture may also be used for all-position FCAW electrodes in welding carbon steels, low-alloy steels, and stainless steels.

Shielding Gases for GMAW Welding of Stainless Steels.— The major problems encountered when using GMAW on stainless steels of thinner than 14 gage include controlling potential melt-through, controlling distortion, and black oxidation on the weld surface. These three welding problems have a common denominator, which is heat. The key to welding thin stainless steel is to minimize the potential heat when welding, by appropriate choice of gas mixture.

A popular gas mixture that is often recommended for GMAW welding of thin-gage stainless steel is the three-part helium gas mixture containing helium 90 + argon 7.5 + CO_2 2.5 per cent. In contrast to gas mixtures without helium, the helium tri-mixture requires the use of higher voltages to sustain the arc, which adds unnecessary heat to the heat-sensitive thin-gage welds.

A practical and lower-cost alternative for GMAW short-circuit transfer on stainless steels is an argon mixture with 2 to 4 per cent CO_2. The argon + CO_2 mixture allows use of lower voltages than is practical with argon/helium mixtures, and the lower voltages resulting from the argon + CO_2 mixture will help to reduce distortion and oxidation, and decrease the melt-through potential. The mixture that works with short-circuit transfer is also a logical practical choice for spray transfer welding of stainless steel because it is less oxidizing than argon/oxygen mixtures. Table 3 provides practical gas mixture recommendations for specific applications.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Shielding Gases for Welding Carbon Steels and Stainless Steels

Application	Gas mixtures					
	Argon + Oxygen	Argon + CO_2 + Oxygen	Argon + 2–4% CO_2	Argon + 6–10% CO_2	Argon + 13–20% CO_2	Argon + 25% CO_2
Short-circuit melt-through problems; less than 20 gage	1	1	1	1	2	3
Short-circuit 18 to 11 gage	…	…	…	…	1	1
Spray if mill scale or surface problems; carbon steels	…	…	…	…	1	2
Spray if low energy required; carbon steel	1	1	1	1	…	…
Spray, best impact strengths, lowest porosity; carbon steels	…	…	…	…	1	…
Best single gas mixture for carbon steels	…	…	…	…	1	…
Short-circuit; stainless steels	…	…	1	…	…	…
Spray; stainless steels	2	…	1	…	…	…
Best single gas mixture for stainless and duplex steels	…	…	1	…	…	…

Preferred choice of shielding gas is 1, followed by 2 and 3.

For GMAW spray transfer welding of stainless steels thicker than 11 gage, the traditional GMAW shielding gas has been argon 98 + oxygen 2 per cent. The argon + oxygen mixture provides excellent, stable, spray transfer, but the oxygen promotes oxidation, leaving the weld with a black surface. To reduce the oxidation, the 2 per cent oxygen can be replaced with the less oxidizing 2–4 per cent CO_2.

Shielding Gases for GMAW Welding of Aluminum.— For GMAW welding of aluminum, helium is added to argon to provide additional weld energy, increasing penetration width, and reducing porosity potential. A gas mixture that has worked well in practice and can be used on the majority of aluminum applications is argon + 25 to 35 per cent helium. Mixtures with higher helium content, of 50 to 90 per cent, require voltages and flow rates that may be excessive for many established aluminum applications.

Welding Controls.— The two primary controls for welding with GMAW are the electrode wire feed control on the wire feeder and the voltage control on the power source. As shown in Fig. 1, these controls typically consist of switches and knobs but do not have the scales, seen enlarged at the upper left, that indicate combinations of wire feed rate, wire gage, volts, and amps. These scales have been added here to allow clearer explanation of the functioning of the wire feed control.

The typical wire feed unit provides maximum feed rates of 600 to 800 in./min. The scale surrounding the setting knob on a wire feed control unit usually has only 10 unnumbered graduations, somewhat like the hour markers on a clock face. On most machines, each of these graduations represents an adjustment of the feed rate of approximately 70 in./min.

Copyright 2004, Industrial Press, Inc., New York, NY

For each increase in the wire feed rate of 70 in./min, depending on the voltage, the welding current increases by approximately 20 to 40 amps, depending on the wire diameter and wire feed positions.

In Fig. 1, a black sector has been drawn in on the wire feed rate adjustment knob to indicate the range of wire feed rates usable with the gas mixture and the electrode diameter (gage) specified. The wire feed and voltage settings shown are for welding thin-gage carbon, low-alloy, or stainless steels with a 0.030- or 0.035-in. (0.8- or 1-mm) diameter electrode. The left edge of the sector on the wire feed knob is set to the eight o'clock position, corresponding to 70 in./min. The optimum voltage for this wire feed rate is 15. If a setting is too low, the knob is turned to the second (nine o'clock) or third (ten o'clock) position to increase the current. The voltage typically increases or decreases by 1 volt for each graduation of the wire feed quadrant.

The short-circuit transfer current range of 50 to 200 amps corresponds to a wire feed rate of 70 to 420 in./min, and is typically found between the eight and one o'clock positions on the scale, as indicated by the black sector on the knob in Fig. 1.

Diagrammatic quadrants have been added at the left in Fig. 1, to show the material thickness, voltage, and current that correspond to the setting of the wire feed rate adjustment knob. Optimum settings are easily made for short-circuit welding of sheet metals. When using a 0.030-in. (0.8-mm) or 0.035-in. (1-mm) diameter GMAW electrode, for instance, to weld 16-gage carbon or stainless steel with a conventional 200-to 450-amp constant-voltage power source and wire feeder, the wire feed control is set to the ten o'clock position for a feed rate of 210 in./min. With digital wire feed units, the short-circuit current range is typically between 100 and 400 in./min, so a good starting point is to set the wire feeder at 210 in./min. The welding voltage is set to 17.



Fig. 1. Wire Feed Settings for Short-Circuit Welding of Carbon, Low-Alloy, and Stainless Steel Sheet.

Many welders set their parameters by an established mark on the equipment or by the sound of the arc as the weld is being made. The sound of the arc, influenced by the optimum current and voltage set, should be a consistent, smooth, crackling noise. If the SCT sound is harsh, the voltage should be increased slightly. If the sound is soft, the voltage should be decreased in volt increments until the sound becomes a smooth crackle. For welding metals thicker than 16 gage but less than 10 gage, the wire feed control should be moved to the eleven o'clock position (280 in./min), and the voltage reset to 18.

Copyright 2004, Industrial Press, Inc., New York, NY

Welding of thicknesses less than 16 gage should be started with the wire feed control at the nine o'clock position (140 in./min) and the voltage control set to 16. The parameters discussed above apply when using argon mixtures containing 15 to 25 per cent CO_2.

GMAW Spray Transfer.— In the spray transfer mode, spatter is often caused by the voltage being set so low that the electrode runs into the weld, resulting in expulsion of molten metal from the weld pool. GMAW spray transfer is normally used for welding carbon, low-alloy, and stainless steels of a minimum thickness of $\frac{1}{8}$ in. (3.2 mm).

In Table 4, typical deposition rates with a 0.045-in. (1.2-mm) carbon steel electrode are compared with rates for larger carbon steel GMAW and flux-cored electrodes. These welds are typically carried out in the flat and horizontal positions. The practical GMAW electrode diameters commonly used for spray transfer are 0.035-in. (1-mm), 0.045-in. (1.2-mm), and 0.062-in. (1.6-mm) diameter. The most cost-effective GMAW electrode that also has the greatest range of applications on metals over $\frac{3}{16}$ in. thick is the 0.045-in. (1.2-mm) diameter size.

Table 4. Typical Deposition Rates for Carbon Steel Welding Electrodes

Electrode Diameter				Deposit Rates	
in.	(mm)	Electrode Type	Amperage[a]	lb/h	(kg/h)
0.035	(1.0)	GMAW	350	11	(5)
0.045	(1.2)	GMAW	380	13	(6)
0.062	(1.6)	GMAW	400	14	(6.4)
$\frac{1}{16}$	(1.6)	FCAW	350	15	(7)
$\frac{3}{32}$	(2.4)	FCAW	450	16	(7.3)

[a] The optimum ampere value for the electrode type is shown. The 0.045 GMAW electrode is the most versatile and cost-effective electrode for welding material of 14 gage to 1 in. thick.

GMAW Spray Transfer Welding of Metal Thicknesses Less than $\frac{1}{4}$ in. (6.4 mm).— The most versatile GMAW electrode for a welding shop that welds carbon, low-alloy, and stainless steels from 20 gage to $\frac{1}{4}$ in. (6.4 mm) thick is the 0.035-in. (1.0-mm) diameter electrode. The traditional practical spray transfer current range of between 200 and 350 amps for the 0.035-in. electrode is well suited for welding thicknesses from 10 gage to $\frac{1}{4}$ in. (6.4 mm).

The correct parameters for a 0.035-in. (1-mm) electrode and spray transfer welding are found on the wire feed unit between the one and five o'clock positions, or, on a digital wire feeder, between 420 and 700 in./min. In the drawing at the left in Fig. 2, the spray transfer wire feed range is shaded. When the wire feed rate has been set, the voltage should be fine-tuned so that the electrode wire tip is just touching the weld and a smooth crackling sound without spatter is produced.

An optimum single spray transfer mode current setting for a 0.035-in. (1-mm) diameter electrode for most welding applications is approximately 280 amps with the wire feed set at the three o'clock position for 560 in./min. Manual or high-speed mechanized welds on material of 10 gage to $\frac{1}{4}$ in. thick can be made at the three o'clock wire feed position with only an adjustment for voltage, which should be set initially at 31 volts, when using an argon + CO_2 mixture.

GMAW Spray Transfer for Metal Thicknesses $\frac{1}{4}$ in. (6.4 mm) and Up.— The 0.45-in. (1.2-mm) diameter is the most cost-effective GMAW electrode for spray transfer welding of carbon, low-alloy, and stainless steels $\frac{1}{4}$ in. and thicker. A $\frac{7}{16}$-in. (11.2-mm) single-pass, no-weave, fillet weld can be produced with this electrode. If larger single-pass welds are required, use of flux-cored electrodes should be considered.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. GMAW Spray Transfer Parameters with 0.035-in. (0.9-mm) Diameter Electrodes

A 400-amp power source is a practical cost-effective unit to use with the 0.045-in. diameter electrode. Globular spray transfer, obtained at the ten o'clock position on the wire feed adjustment knob, starts at current levels of approximately 230 amps and requires a wire feed rate of approximately 210 in./min (90 mm/s). Most spray applications are carried out in the higher-energy, deeper-penetrating 270- to 380-amp range, or between twelve and two o'clock wire feed positions giving 350 to 490 in./rain (150 to 210 mm/s). In this range, in which there is minimum weld spatter, the weld deposits are in the form of minute droplets and vaporized weld metal.

The quadrants at the top in Fig. 3 show some typical settings for feed rate, voltage, and current, with different shielding gases. An ideal starting point with a 0.045-in. (1.2-mm) diameter electrode is to set the wire feed rate knob at the one o'clock position, or 420 in./min, at which rate the current drawn, depending on the power source used, should be about 320 to 350 amps. The best starting voltage for the 0.045-in. (1.2-mm) electrode is 30 volts. The arc length should then be set as indicated in Fig. 4. With current over 400 amps at 560 in./min, the 0.045-in. diameter electrode may produce a turbulent weld puddle and a digging arc, which can lead to lack of fusion, porosity, and cracks.

GMAW Spray Transfer with 0.062-in. (1.6-mm) Diameter Electrodes.— Electrode wire of 0.062-in. (1.6-mm) diameter is the largest size in normal use and is often chosen for its high deposition rates. Due to the high-current requirements for the spray transfer mode, use of these thicker electrodes is generally restricted to metal thicknesses of ½ in. (13 mm) and thicker. The high-current requirement reduces ease of welding. This electrode size is suitable for mechanized welding in which fillet welds greater than ⅜ in. (9.6 mm) are required.

As indicated at the lower left in Fig. 3, the current range for 0.062-in. (1.6-mm) electrodes is narrow and most welds are made in the range of 360 to 420 amps, or between the ten and eleven o'clock positions on the wire feed control unit for 210 to 280 in./min (90 to 120 mm/s). The quadrants at the lower center and lower right in Fig. 3 show deposition rates in lb/h and kg/h for 0.045-in. (1.2-mm) and 0.062-in. (1.6-mm) diameter electrodes.

Some optimum settings for GMAW welding with a mixture of argon + 15 to 20 per cent CO_2 gases are given in Table 5.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. GMAW Spray Transfer Parameters for Various Electrodes and Gases.

Table 5. Optimum Settings for GMAW with Argon + 15–20 per cent CO_2

Diameters			Wire Feed Rates			
in.	mm	Mode	in./min	m/min	Amps	Volts
0.035	1.0	short circuit	210	5.3	140	17
		spray transfer	560	14.2	280	29–30
0.045	1.2	short circuit	210	5.3	190	18
		spray transfer	420	10.7	380	30–31
0.052	1.4	spray transfer	280	7.1	370	31–32
0.062	1.6	spray transfer	280	7.1	410	31–32

Note: If argon + oxygen gas mixtures are used, voltage should be lowered by 1 to 4 volts for the spray transfer mode. The faster the weld travel speed, the lower the voltage required.

Spray Transfer Voltage.— The usual setting for spray transfer welding with commonly used electrode diameters is between 25 and 35 volts (see Fig. 4A). To set the optimum voltage for GMAW spray transfer, set the voltage initially so that it is too high, usually between 30 and 35 volts. With excess voltage, there should be a visible gap between the tip of the electrode and the weld, and the arc sound should be free from crackle. With the sequence shown in Fig. 4, the voltage should now be reduced until a consistent smooth crackle sound is produced. If the voltage is lowered too much, the electrode will run into the weld, making a harsh crackling sound, and the resulting weld expulsion will cause spatter.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Setting Optimum Voltage for GMAW Spray Transfer Welding.

Flux-Cored Arc Welding

FCAW welding offers unique benefits for specific applications, but flux-cored consumable electrodes cost more than the solid electrodes used in gas metal arc welding, so users need to be aware of FCAW benefits and disadvantages compared with those of GMAW welding. Generally, flux-cored electrodes designed for use without a shielding gas are intended for welding outdoors. Most indoor FCAW welding is done with gas-shielded FCAW welding electrode wire. Some Standards for gas-shielded FCAW electrodes for various countries are listed in Table 6.

Table 6. Standards for Gas-Shielded, Flux-Cored Welding Electrodes

Steel Type	Country	Standard
Low-Carbon Steels	USA	AWS A5.20
	Canada	CSA W48.5
	Japan	JIS Z3313
	Germany	DIN 8559
Low-Alloy Steels	USA	AWS A5.29
	Canada	CSA W48.3-M
	United Kingdom	BS 639-2492
Stainless Steels	USA	AWS A5.22

All-Position, Gas-Shielded Electrodes.— The term “all-position” does not necessarily mean that these electrodes are the best choice for all positions. Also, flux-cored electrodes may meet all standard specifications, but there will inevitably be subtle differences in weld transfer characteristics and recommended current, voltage, and other settings between electrodes made by different manufacturers. The chemistry and slag of the electrodes developed for welding in the flat and horizontal positions (E70T-X) typically provide superior results when they are used for flat and horizontal applications where the surface conditions of the plate are suspect or large, deep-penetrating welds are required. All-posi-

Copyright 2004, Industrial Press, Inc., New York, NY

tion electrodes are intended for, and best used in, vertical and overhead welds. For extensive welding in flat or horizontal positions, the welder is better served with the electrodes designed for these specific positions.

All-position, gas-shielded FCAW electrodes provide unique benefits and potential for cost savings. In contrast with short-circuit GMAW, or pulsed GMAW, the all-position FCAW electrodes used for vertical up welding of carbon, low-alloy, or stainless steels are simpler to operate, are capable of greater weld quality, and will provide two to three times the rate of weld deposition. The electrode most commonly used in the USA for vertical up welding on carbon steels is the type E71T-1. The equivalent to the E71T-1 standardized electrode specification now in use in other countries include: Canada, E4801T9; Germany, SGR1; and Japan, YFW 24.

If the end user selects the correct all-position electrode diameter, the routine weaving of the electrode during vertical up and overhead applications may be minimized. Keeping the weld weave to a minimum reduces the skill level needed by the welder and increases the potential for consistent side-wall fusion and minimum porosity. If weaving is necessary, a straight-line oscillation technique is often preferred. Typical settings for welding with various sizes of gas-shielded FCAW electrodes are shown in Table 7.

Table 7. Typical Settings for Welding with Gas-Shielded FCAW Electrodes

Electrode Diameter		Vertical Up Welds		Flat and Horizontal Welds	
in.	(mm)				
0.035	(1)	Feed rate Current Voltage	450 ipm 165 amps 28 volts	Feed rate Current Voltage	630 ipm 250 amps 30 volts
0.045	(1.2)	Feed rate Current Voltage	350 ipm 200 amps 25 volts	Feed rate Current Voltage	560 ipm 280 amps 26 Volts
0.052	(1.4)	Feed rate Current Voltage	240 ipm 200 amps 25 volts	Feed rate Current Voltage	520 ipm 300 amps 30 volts
0.062	(1.6)	Feed rate Current Voltage	210 ipm 240 amps 25 volts	Feed rate Current Voltage	350 ipm 340 amps 29 volts
3/32	(2.4)	…		Feed rate Current Voltage	210 ipm 460 amps 32 volts

Material Condition and Weld Requirements.— Practical considerations for selecting a gas-shielded, flux-cored electrode depend on the material condition and weld requirements. FCAW electrodes are beneficial if the surface of the material to be welded is contaminated with mill scale, rust, oil, or paint; the fillet weld size is to be over 3/8 in. (9.6 mm) wide (a GMAW single-pass fillet weld with an electrode size of 0.045 in. is typically 3/8 in. wide); the weld is vertical up, or overhead; the required impact strengths and other mechanical properties are above normal levels; crack resistance needs to be high; and increased penetration is required.

Selecting an FCAW Electrode.— Selection of FCAW electrodes is simplified by matching the characteristics of flux-cored types with the material and weld requirements listed above. Once the correct electrode type is selected, the next step is to choose the optimum size. In selecting an all-position, flux-cored electrode for vertical up or overhead welding, the steel thickness is the prime consideration. Selecting the optimum electrode diameter allows the high current capability of the electrode to be fully used to attain maximum deposition rates and allows use of the highest penetrating current without concern for excessive heat-related problems during welding. When used in the optimum current range, the

Copyright 2004, Industrial Press, Inc., New York, NY

deposited filler metal matches the required amount of filler metal for the specific size of the weld, determined by the plate thickness.

The following suggestions and recommendations are made for FCAW welding of carbon, low-alloy, and stainless steels having flat surfaces. For vertical up welds on steels of thicknesses from 1/8 to 3/16 in. (3.2 to 4.8 mm) and for vertical up welds on pipe in the thickness range of 1/4 to 1/2 in. (6.4 to 13 mm), consider the 0.035-in. (1.0-mm) diameter E71T-1 electrode. For vertical up welds on steels in the range of 1/4 to 3/8 in. (6.4 to 9.6 mm) thickness, consider the 0.045-in. (1.2-mm) diameter E71T-1 electrode or, in nonheat-sensitive applications, the 0.062-in. (1.6-mm) diameter E71T-1 electrode. For vertical up welds on steels of over 3/8 in. (9.6 mm) thickness, consider the 0.062-in. (1.6-mm) diameter E71T-1 electrodes for optimum deposition rates. For flat and horizontal welds on steels of 3/8 to 3/4 in. (9.6 to 19 mm) thickness, consider the 1/16-in. (1.6-mm) diameter E70T-X electrodes. For flat and horizontal welds on steels over 3/4 in. (19 mm) in thickness, consider the 3/32-in. (2.4-mm) E70T-X electrodes.

FCAW Welding of Low-Carbon Steels.— Low-carbon steel is usually called carbon steel or mild steel. The most-used FCAW electrode for welding carbon steels in the flat or horizontal welding positions is the type E70T-1. which is suited to welding of reasonably clean steel using single-pass or multi-pass welds. Type E70T-2 has added deoxidizers and is suited to surfaces with mill scale or other contamination. This type is used when no more than two layers of weld are to be applied. Type E70T-5 is used for single-pass or multi-pass welds where superior impact properties or improved crack resistance are required. The E70T-X electrodes typically range in size from 0.045 to 3/32 in. (1.2 to 2.4 mm) in diameter. Type E71T-1 all-position electrodes are available in diameters of 0.035 in. (1 mm) to 0.062 in. (1.6 mm). With the FCAW process, multi-pass welds are defined as a condition where three or more weld passes are placed on top of each other.

Settings for Gas-Shielded, All-Position, FCAW Electrodes.— The optimum setting range (volts and amps) for vertical up welding with all-position FCAW electrodes is rather narrow. The welder usually obtains the greatest degree of weld puddle control at the recommended low to medium current settings. The electrode manufacturers' recommended current range for an E71T-1 electrode of 0.045-in. (1.2-mm) diameter for vertical up welding may be approximately 130 to 250 amps. Using the 0.045-in. (1.2-mm) diameter electrode at 250 amps for a vertical up weld in 1/4-in. (6.4-mm) thick steel, the welder may find that after 3 to 4 inches (75–100 mm) of weld, the weld heat built up in the steel being welded is sufficient to make the weld puddle fluidity increasingly difficult to control. Reducing the current to 160–220 amps will make it possible to maintain control over the weld puddle.

A typical optimum setting for a vertical up weld with an E71T-1, 0.035-in. (1.2-mm) diameter, all-position electrode is as follows. First, set the wire feed rate. If the wire feeder maximum rate is 650 to 750 in./min, the setting mark on the adjustment knob should be set between the one and two o'clock positions on the dial to obtain a feed rate of 450 in./min. If the wire feeder has a digital readout, the rate setting should be the same. At the 450-in./min setting, the welding current with the 0.035-in. all-position electrode should be optimized at between 160 and 170 amps. The welding voltage should be set at 27 to 28 volts with the electrode tip just touching the weld. If there is a gap causing the weld puddle to become too fluid, the voltage should be lowered. If the electrode runs into the weld, causing spatter, the voltage needs to be increased.

With the above conditions, welding steel of 1/8 to 1/4 in. thickness will deposit 5 to 7 lb/h (2.2 to 3 kg/h). The 0.035-in. electrode is also ideal for welding steel pipe with wall thicknesses of less than 1/2 in. (13 mm). The thickness of the pipe after bevelling controls the size

Copyright 2004, Industrial Press, Inc., New York, NY

of electrode to be used. The 0.035-in. (6.4-mm) electrode can produce a ¼-in. (6.4-mm) vertical up fillet weld on such a pipe without weaving.

Contact Tip Recess.— The dimension labeled contact tip recess in Fig. 2, and indicated as ⅛ in., should be about ½ in. (13 mm) for a minimum electrode extension of ¾ in. (19 mm), for FCAW welding. This dimension is critical for obtaining high-quality welds with all-position electrodes because they have a fast-freezing slag and operate with low to medium current and voltage. If the recess dimension is less than the optimum, the voltage may be lower than the minimum recommended, and if the settings are less than the minimum, the fast-freezing slag may solidify too rapidly, causing excess porosity or "worm tracks" on the weld surface.

The recommended length of electrode extension for all-position FCAW, E71T-1 electrodes is ¾ to 1 in. (19 to 25 mm). The size of this extension not only affects the minimum required parameters, but a long electrode extension also ensures preheating of the electrode and allows lower current to be used. Preheating the electrode is further beneficial as it reduces moisture on the electrode surface, and in the electrode flux. When a change is made from the GMAW to the FCAW process, welders must be aware of the influence on weld quality of the electrode extension in the FCAW process.

Porosity and Worm Tracks.— As mentioned above, porosity and worm tracks typically result from a combination of incorrect electrode extension, incorrect welding settings, humidity, electrode moisture, refill scale, rust, paint, oils, or poor welding technique. Where humidity levels are high, potential for porosity and worm tracks increases. The FCAW process is less sensitive to mill scale than the GMAW spray transfer mode but mill scale will often cause excess weld porosity. The best way to avoid the effects of mill scale, rust, oil, and surface contaminants is to grind the area to be welded.

Another way to reduce porosity is to keep weaving to a minimum. If the correct size flux-cored electrode is used, weaving can be kept to a minimum for most flux-cored applications. The forehand technique produces the best weld bead surface on fillet weld beads up to ¾ in. (19 mm) steel thickness in the flat and horizontal weld positions. On larger single-pass fillet welds, the backhand technique is beneficial because the voltage directed at the weld provides additional weld puddle control to the fluid welds. The backhand technique used for flat and horizontal welds produces a more convex weld bead, reduces potential for porosity, and increases penetration.

If porosity or worm tracks occur, the prime solution is in weld practices that increase heat at the weld, but the following remedies can also be tried. Grind clean the surface to be welded; use recommended electrode extensions; increase current (wire feed rate) decrease voltage; use the backhand welding technique; slow down travel speed, consider use of a different electrode formulation containing increased deoxidizers, avoid weaving; change from argon + CO_2 mixture to straight CO_2; and provide a protective cover to keep the electrode spool clean and dry.

Welding with 0.045-in. (1.2-mm) Diameter All-Position Electrodes.— Fig. 5 shows wire feed settings for welding of steel with 0.045-in. (1.2-mm) diameter, E71T-1 all-position electrodes using a mixture of argon + 15 to 25 per cent CO_2 as the shielding gas, and an electrode extension of ¾ in. (18 mm). Parameters for vertical up welding, shown at the left in Fig. 5, include setting the wire feed rate at the twelve o'clock position, or about 350 in./min, using 200 to 190 amps, and setting the voltage between 24 and 25 volts. Optimum parameters for flat welding, shown at the right in Fig. 5 include setting the wire feed rate at three o'clock position, or 560 in./min (240 mm/s), and 270 amps at 25 to 27 volts.

Welding with 0.052-in. (1.3-mm) Diameter All-Position Electrodes.— Settings for vertical up and flat welding with all-position E71T-1 electrodes of 0.052-in. (1.3-mm) diameter are seen at the left in Fig. 6. These electrodes are suited to welding steel having

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Wire Feed and Voltage Settings for FCAW Welding with 0.045-in. (1.2-mm) Diameter E71T-1 Electrodes. Optimum settings are circled.

thicknesses of ¼ in. (6 mm) and thicker. For vertical up welding, the wire feed rate is set between the ten and eleven o'clock positions, or 250 in./min (106 mm/s), with about 200 amps at 25 volts. Flat welding with these electrodes is best done with the wire feed rate set between the two and three o'clock positions, or 490 to 560 in./min (207 to 237 mm/s), giving approximately 300 amps at 28 volts.

Settings for all-position E71T-1 electrodes of 0.062-in. (1.6-mm) diameter, shown at the right in Fig. 6, for vertical up welding are just before the ten o'clock position, or 190 in./min, giving 230 to 240 amps with voltage adjusted to 24–25 volts. For flat welding, the wire feed is set to the twelve o'clock position, giving 340–350 amps with a voltage of 29–30 volts.

High-Deposition, All-Position Electrodes.— Vertical up weld deposition rates of 10 to 14 lb/h can be achieved with the E71T-1, 0.062-in. (1.6-mm) and 0.045-in. (1.2-mm) flux-cored electrodes. Settings are shown in Fig. 6 for E71T-1, FCAW electrodes of 0.052- and 0.062-in. (1.4- and 1.6-mm) diameter. These electrodes are suited to applications in which the steel thickness is ¼ in. and thicker, and are the most cost-effective diameter for all-position welds on carbon and stainless steels of ¼ in. (6.35 mm) thickness and thicker. In contrast, vertical up welds, using GMAW or SMAW, may deposit an average of 2 to 4 lb/h (1 to 2 kg/h). Deposition rates are based on welding 60 minutes of each hour. Pulsed GMAW provides deposition rates of 3 to 6 lb/h (1.3-2.7 kg/h). Average rates for vertical up welding with all-position, flux-cored electrodes are shown in Table 8.



Fig. 6. Wire Feed and Voltage Settings for Vertical Up Welding with 0.052- and 0.062-in. Diameter Electrodes

Copyright 2004, Industrial Press, Inc., New York, NY

The average deposition rates in Table 9 are to be expected with FCAW electrodes available today. Special electrodes are also available that are specifically designed to provide higher deposition rates. A typical manual welder, welding on steel of ¼ to ⅜ in. thickness for 30 minutes of each hour with an all-position flux-cored 0.062-in. (1.6-mm) or 0.045-in. (1.2-mm) diameter electrode would deposit about 4–5 lb/h.

Table 8. Deposition Rates for Vertical Up Welding with All-Position, Flux-Cored Electrodes (ET71T-1)

Electrode Diameter		Typical Deposition Rate Range		Average Deposition Rate	
in.	(mm)	lb/h	(kg/h)	lb/h	(kg/h)
0.035	(1)	2.7–6.5	(1.2–3)	5	(2.3)
0.045	(1.2)	5–11	(2.3–5)	8	(3.6)
0.052	(1.4)	4–8	(1.8–3.6)	6.5	(3)
0.062	(1.6)	4–11	(1.8–5)	8.5	(4)

Table 9. Average Deposition Rates for Flat and Horizontal Welds

Process	Electrode Size		Cost-Effective Current Range	Optimum Current	Deposition Rate	
	in.	(mm)	(amps)	(amps)	lb/h	(kg/h)
GMAW spray transfer	0.035	(1)	250–350	285	9	(4)
	0.045	(1.2)	300–400	385	13	(5.9)
	0.052	(1.4)	350–470	410	11	(5)
	0.062	(1.6)	375–500	450	17	(7.7)
FCAW	0.045	(1.2)	225–310	300	14	(6.4)
	0.052	(1.4)	260–350	310	15	(6.8)
	0.062	(1.6)	300–400	340	15	(6.8)
	3/32	(2.4)	380–560	460	17	(7.7)

The average deposition rates of pulsed GMAW and FCAW for vertical up welds are similar for applications where the steel thickness is ⅛ in. (3.2 mm) or less. On steels thicker than ⅛ in., where the current may be increased, and larger-diameter all-position FCAW electrodes may be used, deposition rates will be much greater than with pulsed GMAW. Compared with GMAW electrodes for pulsed welding, FCAW all-position electrodes require less costly equipment, less welding skill, and have potential for increased weld fusion with less porosity than with GMAW pulsed techniques.

Electrode Diameters and Deposition Rates.— A cost-effective welding shop can achieve deposition rates on flat and horizontal welds of 12 to 15 lb/h (5 to 7 kg/h) with both the GMAW 0.045-in. wire and the 0.062-in. flux-cored wire electrodes, without welder discomfort, and with welds of consistent quality.

The first consideration in selecting the optimum size of gas-shielded FCAW E70T-X electrode for manual flat and horizontal welds on steels thicker than ¼ in. (6.4 mm) is the current requirements needed to achieve deposition rates of 12 to 15 lb/h (5 to 7 kg/h). Large-size electrodes of 3/32-in. (2.4-mm) diameter require 500 amps or more to attain optimum deposition rates. These 3/32-in. diameter electrodes are often used with power sources in the 300–400 amp range, but even when the power source provides 500 to 600 amps, welding is often performed at the low end of the electrode's current requirements. With the large, 3/32-in. diameter electrodes, welder appeal is low, smoke is often excessive, and deposition rates are often only comparable with smaller, easier-to-operate FCAW electrodes.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical deposition rates for flat and horizontal welds with various electrode sizes and weld settings are shown in Table 9. In connection with this table, it may be noted that high deposition rates in welding steel plate thicker than ¼ in. require use of currents above the minimum shown for the various sizes of electrodes. The optimum current requirements for the most popular electrode sizes indicate that a 450-amp power source is the most suitable for welding steel of more than ¼ in. thickness. The two most cost-effective and versatile consumables for thin and thick steel sections are the 0.045 in. for GMAW and the 0.062 in. for FCAW electrodes.

The approach to a welding application is critical to achievement of optimum weld quality at minimum cost. In many applications, minimal consideration is given to weld costs. Half of every man-hour of welding in many shops could be saved with selection of the correct electrode diameter used with optimum parameter settings. A practical point that is often overlooked in selection of FCAW electrodes is that the larger the electrode diameter, the more restricted is the application thickness range. Large FCAW electrodes such as the 3/32 in. (2.4 mm) are neither suitable nor cost-effective for the common steel thickness range of ¼ to ½ in. (6.4 to 13 mm). Smaller FCAW electrodes such as the 1/16-in. (1.6-mm) diameter, are suitable for both thin and thick applications. A 1/16-in. diameter FCAW electrode used in the 300- to 350-amp range provides excellent deposition rates with superior welder appeal and negligible smoke.

Large-diameter 3/32-in. (2.4-mm) electrodes are popular for manual applications. However, from a practical point of view, this electrode size is often better suited to mechanized high-current welding in which the high currents required for optimum deposition rates may be safely used without health risks. Use of an electrode at 60 to 80 per cent of its welding current capability indicates that the correct diameter electrode has been selected for the application. When an electrode is used at its maximum-current capability, it shows that the next size larger electrode should be preferred, and when the low end of the current capability is in use, the electrode selected is typically too large.

The 0.062-in. (1.6-mm) Diameter, E70T-X Electrode.— The 0.062-in. (1.6-mm) diameter FCAW electrode is the most practical size of its type and will provide excellent deposition rate potential with a practical current range and the broadest application range. Settings for the common 1/16-in. diameter E70T-1 electrode are shown in Fig. 7. With the GMAW process, a 3/8- to 7/16-in. (9.6- to 11-mm) minimum-weave fillet weld is typically the maximum size that can be made in a single pass. The 0.062-in. (1/16-in, 1.6-mm) FCAW electrode can easily produce a 3/4-in. (19-mm), nonweave, single-pass fillet weld. This size of electrode is also a practical choice for welding steel of ¼ in. (6.4 mm) or greater thickness. From a cost perspective, FCAW consumable electrodes should be used whenever the GMAW process is not suitable.

The average deposition efficiency of a flux-cored electrode is 85 per cent, which means that for every 100 lb or kg of electrode material used, 85 lb or kg ends up as weld material. In contrast, the average deposition efficiency of a GMAW electrode used with argon mixtures and correct equipment settings should be a minimum of 99 per cent.

Shielding Gases and FCAW Electrodes.— The E70T-X flux-cored electrodes that are recommended for flat and horizontal welds use CO_2 gas shielding. Because of new OSHA welding smoke restrictions, manufacturers of FCAW electrodes now provide E70T-X consumable electrodes that can be used with less reactive argon + CO_2 mixtures to reduce smoke levels. The fast-freezing slag, all-position, E71T-1 flux-cored electrodes can use either CO_2 or argon + 15 to 25 per cent CO_2 mixtures for welding carbon, low-alloy, or stainless steels. The argon + CO_2 mixture is often selected because it provides the highest energy from a reactive gas mixture with a compatible voltage range.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Settings for $\frac{1}{16}$-in. (1.6-mm) FCAW, E70T-X Electrodes.

Instead of CO_2, welders often prefer the arc characteristics, lower smoke levels, and lower voltage requirements of the argon + CO_2 mixtures for all-position welding. However, if lower reactive argon mixtures such as argon + oxygen, or argon with less than 13 per cent CO_2, are used, the weld voltage requirements and the arc plasma energy are reduced, adding to the possibility of changing the mechanical properties significantly, increasing the porosity, and raising the potential for forming worm tracks.

Shielded Metal Arc Welding

With the shielded metal arc welding (SMAW) process, commonly known as stick welding, it is most important to select an electrode that is suited to the application. For welding austenitic stainless or high-alloy steels, the electrode is first selected to match the mechanical and chemical requirements of the metal to be welded. Secondary requirements such as the welding position, penetration potential, deposition capabilities, and ease of slag removal are then considered. Many electrodes for SMAW welding of low- to medium-carbon steels have unique characteristics making them the most suitable and cost-effective for a specific welding application.

In interpreting the ANSI/AWS Standard specification code for SMAW electrodes shown in Table 10, for example, E60XX, the E stands for a low-carbon steel, metal arc welding electrode. The next two digits, such as 60 or 70, indicate the approximate tensile strength of the weld deposit in thousands of psi.

Of the last two digits, the first indicates the usability as follows: 1 = usable in all welding positions; 2 = usable for flat or horizontal positions; and 3 = usable in flat position only.

The final digit, combined with the above, indicates the type of flux coating, as shown in Table 10.

British Standard BS 639:1986 defines requirements for covered carbon- and carbon-manganese-steel electrodes for manual metal arc welding, depositing weld metal having a tensile strength of not more than 650 N/mm^2. Appendix A of this standard lists minimum mandatory and optional characteristics of these electrodes. The extensive classifications provide for electrodes to be rated for strength, toughness, and covering (STC), with codes such as E 51 5 4 BB [160 3 0 H]. In this series, E indicates that the electrode is covered and is for manual metal arc welding. The next two digits (51) indicate the strength (tensile, yield, and elongation) properties. The next digits (5 and 4) give the temperatures at which minimum average impact strengths of 28J (at –40°C) and 47J (at –30°C), using Charpy V-notch test specimens, are required. The next group is for the covering and the BB stands for basic, high efficiency. Other letters are B for basic; C for cellulosic; R for rutile, RR for rutile, heavy coated; and S for other.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Significance of Digits in ANSI/AWS A5.18-1979 Standard

Third and Fourth Digits	Flux Type and Characteristics, SMAW Electrodes
10	High-cellulose coating bonded with sodium silicate. Deep penetration, energetic spray-type arc. All-positional, DCEP[a] only
11	Similar to 10 but bonded with potassium silicate to permit use with AC or DCEP
12	High-rutile coating, bonded with sodium silicate. Quiet arc, medium penetration, all-positional, AC or DCEN
13	Similar to 12 but bonded with sodium silicate and with easily ionized materials added. Gives steady arc on low voltage. All-positional, AC or DCEN
14	Similar to 12 with addition of medium amount of iron powder. All-positional, AC or DC
15	Lime-fluoride coating (basic low-hydrogen) bonded with sodium silicate. All-positional. For welding high-tensile steels. DCEP only
16	Similar to 15 but bonded with potassium silicate. AC or DCEP
18	Similar to 15 but with addition of iron powder. All-positional, AC or DC
20	High iron-oxide coating bonded with sodium silicate. Flat or HV positions. Good X-ray quality. AC or DC
24	Heavy coating containing high percentage of iron powder for fast deposition rates. Flat and horizontal positions only. AC or DC
27	Very heavy coating with ingredients similar to 20 and high percentage of iron powder. Flat or horizontal positions. High X-ray quality. AC or DC
28	Similar to 18 but heavier coating and suited for use in flat and HV positions only. AC or DC
30	High-iron-oxide-type coating but produces less fluid slag than 20. For use in flat position only (primarily narrow-groove butt welds). Good X-ray quality. AC or DC

[a] DC = direct current, AC = alternating current, EP = electrode positive, EN = electrode negative.

The letters in brackets are optional, and the first group indicates the efficiency, which is the ratio of the mass of weld metal to the mass of nominal diameter core wire consumed with the largest diameter electrode, rounded up to the nearest multiple of 10. The next digit (3) is the maker's advice for the position(s) to be used. Codes for this category include 1, all positions; 2, all positions except vertical down; 3, flat, and for fillet welds, horizontal/vertical; 4, flat; 5, flat, vertical/down; and for fillet welds, horizontal/vertical; and 9, other. The digit at (0), which may have numbers from 0 to 9, shows the polarity, and the minimum open-circuit voltage to be used for that electrode. A 0 here indicates that the electrode is not suited for use with AC. The (H) is included only for hydrogen-controlled electrodes that will deposit not more than 15 ml of diffusible hydrogen for each 100 g of deposited weld metal. The corresponding ISO Standard for BS 639 is ISO 2560. Low-alloy steel electrodes and chromium and chromium nickel steel electrodes are covered in BS 2493 and BS 2926.

The most common electrodes used for the SMAW process are the AWS types E60XX and E70XX. SMAW welding electrode Standards are issued by the American Welding Society (AWS), the British Standards Institute (BS), Canada (CSA), Germany (DIN), and Japan (JIS) and are shown in Table 11.

AWS E60XX Electrodes.— Characteristics of the E60XX electrodes influence the weld position capability, ease of slag removal, penetration potential, weld travel speed capability, and weld deposition rates. These electrodes are designed for welding low-carbon steels and they provide welds with typical tensile strength in the range of 58,000 to 65,000 lb_f/in^2,

Copyright 2004, Industrial Press, Inc., New York, NY

depending on the specific electrode utilized, the base metal condition and chemistry, and the amount of weld dilution. In selecting an electrode for SMAW welding, knowing that the mechanical and chemical requirements have been matched, it is necessary to choose electrodes with characteristics that influence the features required, as shown in Table 11.

Table 11. Characteristics of SMAW Welding Electrodes Made to Standards of Various Countries

Standard	Description
AWS E6010 CSA E41010 BS E4343C10 DIN E4343C4 JIS	Designed for welding pipe and general structures. Excellent for all-position and vertical down welding. Slag is light and easy to remove. Deep, penetrating arc. Low deposition rates. Polarity DC + (electrode positive).
AWS E6011 CSA E41011 BS E4343C13 DIN E4343C4 JIS D4311	Similar to E6010 but modified to allow use of AC. Excellent for welding sheet metal corner joints vertical down. Polarity AC or DC + (electrode positive).
AWS 6012 CSA E41012 BS E4332R12 DIN E4332R(C) JIS D4313	Designed for welding sheet metal and light structural steels. Medium penetration suitable for gaps or where minimum weld dilution is needed. Ideal for flat, horizontal, or vertical down welding. Will weld faster than the E6010-11 electrode. Polarity AC or DC—(electrode negative).
AWS E6013 CSA E41013 BS E4332R21 DIN E4332R3 JIS D4313	Excellent AC or DC—performance. All-position. Shallow penetration. Good choice for low open-circuit welding machines. AC or DC both excellent on thin structural applications. Polarity AC or DC (DC both polarities).
AWS 6027 CSA 41027 BSE4343A13035 DIN 4343AR11 JIS D4327	Iron powder is added to the flux to provide higher deposition rates. Ideal for multipass groove and fillet welding in flat and horizontal positions. Polarity AC or DC (both polarities).

Table 12 shows approximate current requirements for AWS E60XX electrodes for welding sheet metal carbon steels. The current ranges specified vary slightly with different electrode manufacturers. For welding sheet metal start at the low end of the given current requirements with electrodes of $\frac{3}{16}$-in (5-mm) diameter or smaller. For metals thicker than 10 gage (0.134 in.), start in the center of the current range, then adjust to suit. A high DC current may result in arc blow, and improved results may then be obtained with AC.

Table 12. Diameters of AWS E6010/E6011 SMAW Electrodes for Welding Low-Carbon Steel Sheet Metal

SWG of Sheet Metal to be Welded	Electrode Diameter		Current Starting Level
	in.	(mm)	(amps)
18	$\frac{3}{32}$	(2.5)	45–60
16–14	$\frac{1}{8}$	(3.2)	80–110
12	$\frac{5}{32}$	(4)	125–135
10	$\frac{3}{16}$	(5)	135–150

For welding thicker materials, a good starting setting is in the middle of the current range shown in Table 12. In welding material less than $\frac{1}{4}$-in. (6.4-mm) thick, vertically, with an E6010 electrode, try a $\frac{1}{8}$-in. (3.2-mm) electrode at 90 to 100 amps. For welding thicknesses between $\frac{3}{16}$ and $\frac{5}{16}$ in. (5 and 8 mm) with the E6010 electrode, vertically, try the $\frac{5}{16}$-in. (8-mm) diameter electrode at 100 to 125 amps. For thicknesses of $\frac{3}{8}$ to 1 in. (9.5 to 25 mm), try a $\frac{3}{16}$-in. (5-mm) diameter electrode at 155 to 165 amps.

Copyright 2004, Industrial Press, Inc., New York, NY

Recommended current ranges, shown in Table 13 for the various sizes of AWS E60XX electrodes most commonly used for welding carbon steel, will give optimum results with SMAW electrodes. An ideal starting point for the current setting for any SMAW electrode diameter is in the middle of the range. The current ranges shown are average values taken from literature of electrode manufacturers in three different countries.

Table 13. Current Ranges for AWS E60XX SMAW Electrodes

Electrode Diameter		E6010/E6011	E6012	E6013	E6027
in.	(mm)	(amps)	(amps)	(amps)	(amps)
1/16	(1.6)	…	25–50	20–40	…
3/32	(2.5)	40–75	40–100	50–100	…
1/8	(3.2)	75–130	85–140	75–135	120–180
5/32	(4)	90–170	115–185	110–185	155–245
3/16	(5)	135–220	145–240	150–235	200–300
1/4	(6.4)	205–325	250–390	240–340	300–410
5/16	(8)	260–420	290–480	310–425	370–480

AWS E70XX Electrodes.— Information on the most commonly used AWS E70XX electrodes is given in Table 15. For critical welding applications, low-hydrogen electrodes are typically used. It is most important that manufacturers' instructions regarding storage requirements for keeping low-hydrogen electrodes free from moisture are followed. Current ranges for welding low-carbon steel sheet metal with E70XX electrodes of diameters from 3/32 to 3/16 in. (2.5 to 5 mm) are shown in Table 14. The optimum starting point is in the middle of the current range indicated.

Table 14. Current Ranges for SMAW E70XX Welding Electrodes

Electrode Diameter		E7014	E7018	E7024
in.	(mm)	(amps)	(amps)	(amps)
3/32	(2.5)	75–120	70–105	85–135
1/8	(3.2)	110–155	110–160	130–180
5/32	(4)	145–210	150–215	175–240
3/16	(5)	190–280	180–275	230–315
7/32	(5.5)	255–335	255–350	280–370
1/4	(6.4)	330–415	295–360	325–450
5/16	(8)	380–490	370–480	390–530

In using AWS E7018 electrodes for vertical up welding of plate thicknesses of 3/16 to 5/16 in. (5 to 8 mm), try a 1/8-in. (3.2-mm) diameter electrode. For vertical up welding of thicknesses greater than 5/16 in. (8 mm), try a 5/32-in. (4-mm) electrode. With AWS E7018 electrodes, to make horizontal fillet welds in plate thicknesses of 10 swg (0.135 in., 3.4 mm), try a 3/16-in. (5-mm) electrode, for 1/4-in. (6.4-mm) plate, try the 7/32-in. (5.5-mm) electrode, and for steel plate thicker than 1/4 in., try the 1/4-in. (6.4-mm) diameter electrode.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Characteristics of AWS Electrodes for SMAW Welding

Standard	Description
AWS E7014 CSA E48014 BS E5121RR11011 DIN E5121RR8 JIS D4313	An iron-powder, all-position electrode for shallow penetration. Excellent for vertical down and applications with poor fit. Similar to AWS E6012-E6013 with added iron powder. For welding mild and low-alloy steels. Polarity AC or DC, + or –.
AWS E7018 CSA E48018 BS E5154B11026(H) DIN E5154B(R)10 JIS D5016	An iron-powder, low-hydrogen, all-position electrode. Excellent for rigid, highly stressed structures of low- to medium-carbon steel. Can also be used for welding mild and high-strength steels, high-carbon steels, and alloy steels. Polarity AC or DC + reverse polarity.
AWS 7024 CSA E48024 BS E5122RR13034 DIN E5122RR11 JIS D4324	An iron-powder electrode with low hydrogen, usable in all positions. Excellent for high-amperage, large, fillet welds in flat and horizontal positions. Polarity AC or DC, + or –.
AWS E7028 CSA E48028 BS E514B12036(H) DIN E5143B(R)12 JIS D5026	An iron-powder, low-hydrogen electrode suitable for horizontal fillets and grooved flat position welding. Higher deposition rates. More cost-effective than the AWS E7018 electrode. Polarity AC or DC + reverse polarity.

The E7024 electrode is suggested for horizontal fillet welds. For 10-gage (0.135-in, 3.4-mm) material, try the $\frac{1}{8}$-in. (3.2-mm) diameter electrode; for above 10-gage to $\frac{3}{16}$-in. (5-mm) material, try the $\frac{5}{32}$-in. (4-mm) diameter electrode. For plate of $\frac{3}{16}$- to $\frac{1}{4}$-in. thickness, try the $\frac{3}{16}$-in. size, and for plate thicker than $\frac{1}{4}$ in., try the $\frac{1}{4}$-in. (6.4-mm) electrode.

Gas Tungsten Arc Welding

Often called TIG (for tungsten inert gas) welding, gas tungsten arc welding (GTAW) uses a nonconsumable tungsten electrode with a gas shield, and was, until the development of plasma arc welding (PAW), the most versatile of all common manual welding processes. Plasma arc welding is a modified GTAW process. In contrast to GTAW, plasma arc welding has less sensitivity to arc length variations, superior low-current arc stability, greater potential tungsten life, and the capability for single-pass, full-penetration welds on thick sections.

In examining a potential welding application, the three primary considerations are: achieving a quality weld, ease of welding, and cost. Selecting the optimum weld process becomes more complex as sophisticated electronic technology is applied to conventional welding equipment and consumable electrodes. Rapid advances in gas metal arc and PAW welding power source technology, and the development of many new flux-cored electrodes, have made selection of the optimum welding process or weld consumable more difficult. When several manual welding processes are available, the logical approach in considering GTAW for production welding is to first examine whether the job can be welded by gas metal arc or flux-cored methods.

GTAW Welding Current.— A major benefit offered by GTAW, compared with GMAW, FCAW, or SMAW, is the highly concentrated, spatter-free, inert heat from the tungsten arc, which is beneficial for many applications. The GTAW process can use any of three types of welding current, including: direct-current straight polarity, electrode negative (DC–), direct-current reverse polarity, electrode positive (DC+), alternating current with high frequency for arc stabilization (ACHF). Each of the different current types provides benefits that can be used for a specific application.

Copyright 2004, Industrial Press, Inc., New York, NY

GTAW Direct-Current Straight Polarity (DC–): The most common GTAW current is straight polarity, where the electrode is connected to the negative terminal on the power source and the ground is connected to the positive terminal. Gas tungsten arc welding is used with inert gases such as argon, and argon + helium to weld most metals. During a DC– straight-polarity weld, electrons flow from the negative tungsten electrode tip and pass through the electric field in the arc plasma to the positive workpiece, as shown in Fig. 8.

Plasma is a high-temperature, ionized, gaseous column that is formed when electrons in the arc collide with the shielding gas molecules. The gas atoms lose one or more electrons, leaving them positively charged. The electrons and the resulting plasma are concentrated at the electrode tip, where they cause the plasma pressure to be at its greatest. The electron density thins out as the electrons travel from the straight-polarity, negatively charged, tungsten electrode across the open arc. As the electrons traverse the arc to the work, the resulting arc column width increases slightly, controlled in part by the electromagnetic forces generated by the current. With the increase in the arc column width, the density and pressure of the plasma decrease. The electrons collide with the work, liberating much heat. The downward pressure of the plasma is exerted against the surface of the weld pool. The gas ions in the plasma are positively charged and greater in mass than the electrons.

In DC–, straight-polarity welding, the positive gas ions are drawn to the negative electrode. The electron flow to the weld ensures that most of the arc heat is generated at the positive work side of the arc. This current setup provides maximum penetration potential, as indicated in Fig. 8. With DC–, straight polarity, the tungsten electrode can carry a higher current and operate at lower temperatures than with the other current arrangements.

Direct-Current Reverse Polarity (DC+): With direct-current positive polarity (DC+), the tungsten electrode is connected to the power-source positive terminal so that the electrons flow from the negative work to the positive electrode. As illustrated in Fig. 9, the electrons impinging on the electrode tip reverse the direction of the heat concentration that occurs with straight polarity, as described above. Approximately two-thirds of the heat generated with DC+ reverse polarity is at the electrode tip, and the electrode becomes very hot, even with low current levels. DC+ reverse polarity requires large-diameter electrodes.



Fig. 8. Straight Polarity (DC–) Provides Highest Electrode Current Capacity and Deepest Penetration Potential.

In the current range of 100 to 150 amps, DC+ reverse polarity requires a $\frac{1}{4}$-in. (6.4-mm) diameter electrode. This larger electrode produces a weld puddle almost twice as wide as that produced by a 120-amp, $\frac{1}{16}$-in. (1.6-mm) diameter, DC– straight polarity electrode. Most of the heat is generated at the electrode tip with DC+ reverse polarity, so penetration is much less than with DC– straight polarity. With DC+ reverse polarity, the positive gas ions in the arc plasma are drawn to the negative workpiece where they bombard and break up the surface oxides that form on metals such as aluminum and magnesium. However, the best welding method for aluminum and magnesium is to use alternating current (AC), which combines the benefits of DC– straight and DC+ reverse polarity.

Copyright 2004, Industrial Press, Inc., New York, NY

Alternating Current (AC): The surface oxides formed on metals such as aluminum and magnesium disturb the arc and reduce the weld quality. Welding of these metals requires DC+ reverse or AC polarity to break up the surface oxides. An alternating current (AC) cycle consists of one-half cycle of straight polarity and one-half cycle of reverse polarity. With alternating current, the cleaning action benefits of the reverse-polarity arc can be combined with the electrode current-carrying capacity of the straight-polarity arc. In welding aluminum and magnesium, the half cycles of AC polarity may become unbalanced. During the AC cycle, the reverse electrode-positive portion of the cycle is restricted by the oxides on the surfaces of these materials. The surface oxides are poor conductors and make it difficult for the electrons generated by the reverse-polarity part of the cycle to flow from the work to the electrode tip, but they do not upset the straight polarity in which the electrons flow from the electrode to the work.



Fig. 9. Direct-Current (DC+) Reverse Polarity Provides a Shallow, Wide, Weld Pool.

DC Component: The part of the reverse-polarity cycle of alternating current (AC) that is upset by the poor conductivity of the oxides is changed into direct-current, straight polarity (DC–) and is directed back to the power source where it may cause overheating. The feedback is referred to as the DC component and its characteristics are important in deciding which process to use because, if an AC power source designed for shielded metal arc welding is to be used to weld aluminum by the GTAW process, the power source must be derated to protect the equipment. The power-source manufacturer will provide information on the level of derating required.

Power sources are available for GTAW that provide a balanced AC wave, and manufacturers will provide information about the benefits of balanced wave versus unbalanced wave, GTAW power sources, and equipment to protect against the DC component.

High Frequency and AC: To maintain the stability of the alternating-current (AC) arc when the positive cycle of the arc is upset by the aluminum oxide, and to avoid contamination of the tungsten electrode, high-frequency current is used to assist in arc ignition during each AC cycle. In direct-current, straight-polarity (DC–) welding of carbon and stainless steels, the high-frequency current is typically selected by the HF arc start-only switch. During AC welding of steels without oxide problems, the HF switch may be left on the arc start-only setting. When AC is used on aluminum, magnesium, or other metals with poor electron-conductive oxides, the HF switch should be moved to the continuous setting.

High-frequency current is also beneficial in that it promotes gas ionization. The more positively charged molecules produced, the more cleaning action takes place in the direct-current, reverse-polarity (DCRP) cycle.

Selecting the Tungsten Electrode Type.— Use of the correct tungsten electrode composition is vital to producing good-quality GTAW welds. Tungsten has the highest melting temperature of all metals. Pure tungsten provides a low-current capacity and requires addi-

Copyright 2004, Industrial Press, Inc., New York, NY

tion of such alloying elements as thorium or zirconium to increase the current-carrying capability. The electrode diameter and the electrode tip configuration also require consideration as both have a great influence on the performance and application potential of GTAW welding.

Table 17 shows typical compositions of commonly used GTAW tungsten electrode materials from the American Welding Society AWS A5.12 Standard. New electrode compositions have been designed that utilize other alloys and rare-earth metals. These electrodes are designed for longer lives in both GTAW and plasma welding.

Pure Tungsten: Pure tungsten electrode material provides good arc stability with alternating current (AC). Tungsten has low current capacity and low resistance to electrode contamination. Pure tungsten is good for low-amperage welding of aluminum and magnesium alloys. On medium- to high-current ferrous applications, there is a potential for tungsten inclusions in the weld.

With DC, the current capacity of pure tungsten is lower than with the alloyed tungsten electrodes. During AC welding, a molten ball shape forms at the pure tungsten electrode tip, and this formation is desirable for welding aluminum.

Table 16. Selection of Gas Tungsten Arc Welding (GTAW) Electrodes

Base Metal	Electrode	Current	Recommendations
Carbon, low-alloy, stainless, and nickel steels	Thoriated	DCEN	Use EWZr electrodes with AC on thin materials
Aluminum	Zirconium or pure tungsten	AC	Use EWZr on critical applications
Aluminum	Thoriated zirconium	DCEP	Use EWZr or EWP electrodes with DCEP on thin sections
Copper and copper alloys	Thoriated	DCEN	Use EWZr or EWP with AC on thin sections
Magnesium	Zirconium	AC	Use DCEP with same electrode on thin sections
Titanium	Thoriated	DCEN	…

Table 17. Common Tungsten Electrode Compositions

Classification	Color	Tungsten (%)	Thorium Oxide (%)	Zirconium Oxide (%)
EWP	Green	99.50	…	…
EWTh-1	Yellow	98.50	0.8–1.2	…
EWTh-2	Red	97.50	1.7–2.2	…
EWTh-3	Blue	98.95	0.35–0.55	…
EWZr	Brown	99.20	…	0.15–0.4

In the classification column, E = electrode; W = tungsten; P = pure; Th = thoriated (thorium oxide); Zr = zirconiated (zirconium oxide). The colors are codes used by manufacturers to identify the material. Tungsten percentages are minimum requirements. The EWTh-3 is also called striped tungsten because it is made with a strip of thoriated material along the length. This electrode needs to be preheated by striking an arc to melt the tip, providing for the thorium and the tungsten to combine before welding is started.

The electrode recommendations in Table 16 are a guide to attaining good-quality GTAW welds from the venous types of polarities available.

Electrode and Current Selection.— Tables 18 and 19 show approximate current recommendations for common electrode types and diameters. The GTAW electrode size should be selected so that its midrange current provides the energy required for the intended application. If the electrode is too thin, excess current may be required, causing the electrode to wear too quickly or melt and contaminate the weld. If the electrodes used are found to be constantly at the top end of the current range, a change should be made to the next larger size. Tables 20 and 21 show recommended sizes of electrodes and filler metal rods or wires for welding various thicknesses of carbon, low-alloy, and stainless steels and aluminum.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. Recommended Current Ranges for Thoriated GTAW Electrodes

Electrode		Current Range (amps)
1/16 in.	(1.6 mm)	60–150
3/32 in.	(2.4 mm)	150–250
1/8 in.	(3.2 mm)	250–400
5/32 in.	(4 mm)	400–500

The electrode selected must suit the application and the current capacity of the power source.

Table 19. Current Ranges for EWP and EWZr GTAW Electrodes

Electrode		Ampere Range AC Balanced		Ampere Range AC Unbalanced	
in.	(mm)	EWP	EWZr	EWP	EWZr
1/16	(1.6)	30–80	60–120	50–100	70–150
3/32	(2.4)	60–130	100–180	100–160	140–235
1/8	(3.2)	100–180	160–250	150–210	225–325
5/32	(4)	160–240	200–320	200–275	300–400

Table 20. Electrode and Current Recommendations for Carbon, Low-Alloy, and Stainless Steels

Material Thickness		Electrode Diameter		Filler Rod Diameter		Current Range (amps)
in.	(mm)	in.	(mm)	in.	(mm)	DCEN EWTh
1/16	(1.6)	1/16	(1.6)	1/16	(1.6)	60–100
1/8	(3.2)	3/32	(2.4)	3/32	(2.4)	150–170
3/16	(4.8)	3/32	(2.4)	1/8	(3.2)	180–220
1/4	(6.4)	1/8	(3.2)	5/32	(7.2)	260–300

Note: The shielding gas is argon at 15 to 20 cu ft/h (CFH). For stainless steel, reduce the current by approximately 10 per cent.

Table 21. Recommendations for GTAW Welding of Aluminum with EWP Electrodes Using AC and High-Frequency Current

Material Thickness		Electrode Diameter		Filler Rod Diameter		AC Current Range
in.	(mm)	in.	(mm)	in.	(mm)	(amps)
1/16	(1.6)	1/16	(1.6)	1/16	(1.6)	40–70
1/8	(3.2)	3/32	(2.4)	3/32	(2.4)	70–125
3/16	(4.8)	1/8	(3.2)	1/8	(3.2)	110–170
1/4	(6.4)	5/32	(4)	3/16	(4.8)	170–220

Thoriated Electrodes: In contrast with the pure EWP electrodes, thoriated electrodes have a higher melting temperature and up to about 50 per cent more current-carrying capacity, with superior arc starting and arc stability. These electrodes are typically the first choice for critical DC welding applications, but do not have the potential to maintain a rounded ball shape at the tip. The best welding mode for these electrodes is with the tip ground to a tapered or fine point.

Zirconiated Electrodes: Tungsten electrodes with zirconium are practical for critical applications and have less sensitivity to contamination and superior current capacity than pure tungsten electrodes.

Protecting and Prolonging Electrode Life: To improve tungsten electrode life, the tip should be tapered in accordance with the manufacturer's recommendations. There must also be preflow, postflow shielding gas coverage to protect the electrode before and after

Copyright 2004, Industrial Press, Inc., New York, NY

the weld. When possible, high frequency should be used to avoid scratch starts, which contaminate the electrode. The shortest possible electrode extension should be employed, to avoid the possibility of the electrode touching the filler or weld metal. The grinding wheel used to sharpen the tungsten must not be contaminated from grinding other metals or with dirt.

Filler Metals.— Specifications covering composition and mechanical properties for GTAW filler metal are published by the American Welding Society under the following classifications: A5.7, copper and copper alloys; A5.9, chromium and chromium nickel; A5.10, aluminum; A5.14, nickel; A5.16, titanium; A5.18, carbon steels; A5.19, magnesium; and A5.28, low-alloy steels.

Filler metals must be kept dry and clean if they are to be used satisfactorily.

Shielding Gases.— Inert gases such as argon, and argon + helium mixtures are most commonly used for GTAW. Helium provides greater thermal conductivity and additional arc voltage potential than argon, and is normally added to argon when more weld energy is required for improved penetration and increased mechanized welding travel speeds. Argon gas mixtures containing 30 to 75 per cent helium provide benefits for manual welding of aluminum over $\frac{3}{8}$ in. (9.6 mm) thick; mechanized welding of aluminum where high speeds are required; mechanized welding of carbon and stainless steels where good penetration is needed; mechanized welding of stainless steel where good penetration and faster speeds are required; and for copper of $\frac{1}{4}$ in. (6.4 mm) thickness and thicker.

Shielding gas purity for GTAW welding is important. Welding-grade argon is supplied at a purity of at least 99.996 per cent and helium is produced to a minimum purity of 99.995 per cent. However, shielding gases may be contaminated due to poor cylinder filling practices. If impure gas is suspected, the following test is suggested. With the HF and power on, create an arc without welding and hold the arc for about 30 seconds. Examine the electrode tip for signs of unusual coloration, oxidation, or contamination, which result from impurities in the shielding gas.

Plasma Arc Welding (PAW)

When an electric current passes between two electrodes through certain gases, the energy of the gas molecules is increased so that they accelerate and collide with each other more often. With increases in energy, the binding forces between the nuclei and the electrons are exceeded, and electrons are released from the nuclei. The gas now consists of neutral molecules, positively charged atoms, and negatively charged electrons. The plasma gas is said to be ionized, so that it is capable of conducting electric current. Plasma forms in all welding arcs but in plasma arc welding it is generated by a series of events that begins with inert gas passing through the welding torch nozzle. High-frequency current is then generated between the tungsten electrode (cathode) and the torch nozzle (anode), forming a low-current pilot arc. The ionized path of this nontransferred arc is then transferred from the tungsten electrode to the work, and a preset plasma current is generated.

The above sequence of events provides the ionized path for the plasma current between the electrode and the work so that arcing between the electrode and the nozzle ceases. (Nontransferred arcs may be used for metal spraying or nonmetallic welds.) Forcing the ionized gas through the small orifice in the nozzle increases both the level of ionization and the arc velocity, and arc temperatures between 30,000 and 50,000°F (16,650 and 27,770°C) are generated.

Gases for Plasma Arc Welding.— Argon is the preferred gas for plasma arc welding (PAW) as it is easily ionized and the plasma column formed by argon can be sustained by a low voltage. The low thermal conductivity of argon produces a plasma column with a narrow, concentrated hot core surrounded by a cooler outer zone. Argon plasmas are suited to welding steel up to $\frac{1}{8}$ in. (3.2 mm). For thicker materials, requiring a hotter arc and using

Copyright 2004, Industrial Press, Inc., New York, NY

higher current melt-in technique, a mixture of argon 25 + helium 75 per cent may be used. Additions of helium and hydrogen to the gas mixture improve heat transfer, reduce porosity, and increase weld travel speed. For welding materials thinner than ⅛ in. thick by the plasma gas keyhole method (full penetration welds), gases may contain up to 15 per cent hydrogen with the remainder argon. Good results are obtained with argon + 5 per cent hydrogen in welding stainless and nickel steels over ⅛ in. thick.

Shielding Gases.— A shielding gas is needed to protect the narrow plasma arc column and the weld pool, and generally is provided by mixtures of argon, argon + hydrogen, argon + helium, or argon + O_2 + CO_2, depending on compatibility with the material being welded. Shielding gas flow rates vary from 5 to 35 cu ft/h (2.4 to 17 l/min). However, if argon is used for both plasma and shielding, the plasma gas will become less concentrated. The normally tight plasma arc column will expand in contact with the colder shielding gas, reducing ionization and thus concentration and intensity of the plasma column. With no shielding gas, the tight column is unaffected by the surrounding oxygen and nitrogen of the atmosphere, which are not easily ionized.

Hydrogen is added to the shielding gas when welding low-alloy steels of less than 1/16 in. (1.6 mm) thickness, or stainless and nickel steels, with many benefits. The hydrogen molecules dissociate in contact with the arc at temperatures of about 7,000°F (3,870°C) and the energy thus created is released when the hydrogen molecules recombine on contact with the work surface. The diatomic molecular action creates a barrier around the plasma, maintaining column stiffness. Hydrogen in the shielding gas combines with oxygen in the weld zone, releasing it into the atmosphere and keeping the weld clean. Hydrogen reduces the surface tension of the weld pool, increasing fluidity, and the added energy increases penetration.

Helium mixed with the argon shielding gas is beneficial for all metals as it increases the ionization potential, allowing use of higher voltages that give increased welding temperatures. Flow rates are in the range of 15 to 50 cu ft/h (7 to 24 l/min). Arc-starting efficiency is reduced with pure helium, but adding 25 per cent of argon helps both arc starting and stability. Helium additions of 25 to 75 per cent are made to obtain increased thermal benefits.

Argon + CO_2 shielding gas mixtures are beneficial in fusion welding of carbon steels. A mixture of argon with 20 to 30 per cent CO_2 improves weld fluidity. Shielding gas mixtures of argon + CO_2 with an argon + 5 per cent hydrogen plasma should be considered for welding carbon steel of 1/16 to ¼ in. thickness. Steels with higher amounts of carbon have higher heat conductivity and need application of more heat than is needed with stainless steels. Manufacturers usually make recommendations on types of gas mixtures to use with their equipment.

PAW Welding Equipment.— The PAW process uses electrode negative (DCEN) polarity in a current range from 25 to 400 amps, and equipment is offered by many manufacturers. Solid-state inverter units are available with nonmechanical contactors. Most PAW units contain a high-frequency generator, a small DC power supply, controls for welding and shielding gas mixtures, and a torch coolant control. A weld sequencer is recommended, especially for keyhole mode welding, but it is also useful in automated fusion welding. The sequencer provides control of up-slope and down-slope conditions for gas mixtures and current, so that it is possible to make welds without run-on and run-off tabs, as is necessary with circumferential welds.

Generally, plasma arc torches are liquid-cooled using deionized water in the coolant lines to the torch to avoid effects of electrolysis. Electrodes are usually tungsten with 2 per cent thorium. If the welding shop already has a constant-current power supply and a coolant recirculator, plasma arc welding may be used by addition of a pilot arc welding console and a torch.

Copyright 2004, Industrial Press, Inc., New York, NY

Applications.— Fusion welding is the main use for plasma arc welding. The process is used for high-volume, repetitive, high-duty cycle, manual and automated operations on lap, flange, butt, and corner fusion welds, in all positions. Joint design for materials less than 0.01 in. (0.254 mm) thick may require a flange type joint for rigidity and to allow use of extra, weld metal reinforcement. Filler metal may be added during fusion welding, and automated hot or cold wire feeders can be used. Fusion welding uses a soft, less-restricted arc with low gas flows, and the current level may vary from approximately 25 to 200 amps. The soft arc is obtained by setting the end of the tungsten electrode level with the face of the torch nozzle, in which position lower currents and gas flows are required. With these conditions, the weld bead is slightly wider than a bead produced with a recessed electrode.

Low-Current Plasma Fusion Welding: With the reduced consumption of gas and electric current, the low-current plasma fusion welding method is ideal for welding metals down to 0.001 in. (0.025 mm) in thickness, as the low-current plasma pilot arc allows arcs to be started consistently with currents of less than 1 amp. With currents below 1 amp, the pilot arc is usually left in the continuous mode to maintain the arc. In the conditions described, arc stability is improved and the process is much less sensitive to variations in the distance of the torch from the workpiece. Given this height tolerance, setting up is simplified, and with the smaller torches required, it is often easier to see the weld pool than with the GTAW process. Some plasma welding units incorporate gas flow meters that are designed for low flow rates, and currents in the range of 0.1 to 15 amps can be selected.

Low-current plasma arc welding is more economical than other gas tungsten arc welding methods, especially with solid-state inverter systems and smaller torches. The process is useful for sealing type welds where joint access is good, and for welding components of office furniture, household items, electronic and aerospace parts, metallic screening, and thin-wall tubing.

Keyhole mode welding describes a method whereby abutting edges of two plates are melted simultaneously, forming a vapor capillary (or keyhole) and the resulting molten-walled hole moves along the joint line. This method requires the end of the tungsten electrode to be positioned well back inside the torch nozzle to produce a high-velocity, restricted arc column with sufficient energy to pierce the workpiece. This mode is also used for the plasma cutting process, but the major difference is that welding uses very low plasma flow rates of the order of 1 to 3 cu ft/h (0.5 to 1.4 l/min) for work thicknesses of $\frac{1}{16}$ to $\frac{5}{32}$ in. (1.6 to 4 mm). These low rates avoid unwanted displacement of the weld metal. After the arc pierces the workpiece, the torch moves along the weld line and the thin layer of molten metal is supported by surface tension as it flows to the rear of the line of movement, where it solidifies and forms the weld.

As it passes through the keyhole, the high-velocity plasma gas column flushes the molten weld pool and carries away trapped gases and contaminants that otherwise would be trapped in the weld. Plasma arc keyhole welding is affected less by surface and internal defects in the work material than is the GTAW process. Most metals that can be welded by the gas tungsten arc method can be plasma arc welded with the conventional DC electrode, negative keyhole method, except aluminum, which requires a variable polarity keyhole method.

Plasma keyhole welding is usually automated because it requires consistent travel speed and torch height above the work. A typical operation is welding steel with square abutting edges (no bevels) in thicknesses of 0.09 to 0.375 in. (2.3 to 9 mm), where 100 per cent penetration in a single pass is required. Producing square-groove butt welds in materials thicker than $\frac{1}{2}$ in. by the plasma arc keyhole process requires some edge preparation and several filler passes. The finished weld is uniformly narrow and the even distribution of heat means that distortion is minimized.

Welding Aluminum.— The variable polarity plasma arc (VPPA) process was developed for welding metals that form an oxide skin, such as aluminum. Electrode negative

Copyright 2004, Industrial Press, Inc., New York, NY

(straight) polarity is necessary for the plasma arc to provide sufficient heat to the workpiece and minimize heat buildup in the tungsten electrode. With electrode negative polarity, electrons move rapidly from the negative cathode tungsten electrode to the positive anode workpiece, generating most of the heat in the workpiece. Because of the oxide skin on aluminum, however, straight polarity produces an erratic arc, poor weld fluidity, and an irregularly shaped weld bead. The oxide skin must be broken up if the metal flow is to be controlled, and this breakup is effected by a power supply that constantly switches from negative to positive polarity.

A typical cycle uses a 20-ms pulse of electrode negative polarity and a 3-ms pulse of electrode positive polarity. The pulses are generated as square waves and the positive (cleaning) pulse is set at 30 to 80 amps higher than the negative pulse for greater oxide-breaking action. The tenacious oxide skin is thus broken constantly and the rapid cycle changes result in optimum cathode cleaning with minimum deterioration of the tungsten electrode and consistent arc stability. Varying polarity has advantages in both gas metal arc and plasma arc welding, but with the keyhole process it allows single-pass, square-groove, full-penetration welds in materials up to ½ in. (12.7 mm) thick.

The VPPA process ensures extremely low levels of porosity in weld areas in aluminum. VPPA welding is often used in the vertical up position for aluminum because it provides superior control of root reinforcement, which tends to be excessive when welding is done in the flat position. Pulsing in the VPPA process when welding aluminum of ⅛ to ¼ in. thickness in the flat position gives satisfactory root profiles. Pulsing gives improved arc control in keyhole welds in both ferrous and nonferrous metals and is beneficial with melt-in fusion welding of thin materials as it provides better control of heat input to the workpiece.

Plasma Arc Surface Coating

Plasma Arc Surfacing uses an arc struck between the electrode and the workpiece, or transferred arc, to apply coatings of other metals or alloys to the workpiece surface. This high-temperature process produces homogeneous welds in which the ionized plasma gas stream melts both the work surface and a stream of powdered alloy or filler wire fed into the arc. Dilution of the base metal can be held below 5 per cent if required. With arc temperatures between 25,000 and 50,000°F (14,000 and 28,000°C), deposition occurs rapidly, and a rate of 15 lb/h (6.8 kg/h) of powdered alloy is not unusual. Deposition from wire can be performed at rates up to 28 lb/h (12.7 kg/h), much higher than with oxygen/fuel or gas metal/arc methods.

In the nontransferred arc process used for coating of surfaces, the arc is struck between the electrode and the torch nozzle, so that it does not attach to the work surface. This process is sometimes called metal spraying, and is used for building up surfaces for hard facing, and for application of anticorrosion and barrier layers. Argon is frequently used as the plasma gas. As the coating material in the form of powder or wire enters the plasma, it is melted thoroughly by the plasma column and is propelled toward the work at high velocity to form a mechanical bond with the work surface. Some 500 different powder combinations are available for this process, so that a variety of requirements can be fulfilled, and deposition rates up to 100 lb/h (45 kg/h) can be achieved.

The plasma arc process allows parts to be modified or recovered if worn, and surfaces with unique properties can be provided on new or existing components. Low levels of porosity in the deposited metal can be achieved. Metal spraying can be performed manually or automatically, and its use depends primarily on whether a mechanical bond is acceptable. Other factors include the volume of parts to be treated, the time needed for the process and for subsequent finishing, the quality requirements for the finished parts, rejection rates, and costs of consumable materials and energy.

Copyright 2004, Industrial Press, Inc., New York, NY

Some systems are available that can use either metal powder or wire as the spray material, and can be operated at higher voltage settings that result in longer plasma arc lengths at temperatures over 10,000°F (5,537°C). With these systems, the plasma velocity is increased to about 12,000 ft/s (3,658 m/s), giving an extremely dense coating with less than 1 per cent porosity. Current ranges of 30 to 500 amps are available, and nitrogen is frequently used as the plasma gas, coupled with CO_2, nitrogen, or compressed air as the shielding gas. Gas flow rates are between 50 and 350 cu ft/h (24 and 165 l/min). Large or small surface areas can be coated at low cost, with minimum heat input, if other aspects of the process are compatible with the product being made.

Plasma Arc Cutting of Metals

Plasma Arc Cutting.— Higher current and gas flow rates than for plasma arc welding are used for the plasma arc cutting (PAC) process, which operates on DC straight polarity, and uses a transferred arc to melt through the material to be cut. The nozzle is positioned close to the work surface and the velocity of the plasma jet is greatly increased by a restricting nozzle orifice so that it blows away the metal as it is melted to make the cut. The higher energy level makes the process much faster than cutting with an oxygen/fuel torch on cutting steel of less than ½ in. thick, but the process produces kerfs with some variation in the width and in the bevel angle, affecting the precision of the part. Some of the molten metal may recast itself on the edges of the cut and may be difficult to remove.

Factors that affect plasma cutting include the type and pressure of the gas, its flow pattern, the current, the size and shape of the nozzle orifice, and its closeness to the work surface. To reduce noise and fumes, mechanized plasma arc cutting is often performed with the workpiece submerged in water. Oxidation of cut surfaces is almost nonexistent with the underwater method.

Precision Plasma Arc Cutting.— A later development of the above process uses a magnetic field in the cutter head to stabilize the plasma arc by means of Lorentz forces that cause it to spin faster and tighter on the electrode tip. The magnetic field also confines the spinning plasma so that a narrower kerf is produced without adverse effect on cutting speed. Results from this process are somewhat comparable with those from laser cutting and, with numerical control of machine movements, it is used for production of small batches of blanks for stamping and similar applications. With galvanized and aluminized steel, edges are clean and free from burrs, but some slag may cling to edges of mild-steel parts.

Cutting Metals with an Oxidizing Flame

The oxyhydrogen and oxyacetylene flames are especially adapted to cutting metals. When iron or steel is heated to a high temperature, it has a great affinity for oxygen and readily combines with it to form various oxides, and causing the metal to be disintegrated and burned with great rapidity. The metal-cutting or burning torch operates on this principle. A torch tip is designed to preheat the metal, which is then burned or oxidized by a jet of pure oxygen. The kerf or path left by the flame is suggestive of a saw cut when the cutting torch has been properly adjusted and used. The traversing motion of the torch along the work may be controlled either by hand or mechanically.

Arc Cutting.— According to the *Procedure Handbook of Arc-Welding Design & Practice,* published by The Lincoln Electric Co., a steel may be cut easily, and with great accuracy by means of the oxyacetylene torch. All metals, however, do not cut as easily as steel. Cast iron, stainless steels, manganese steels, and nonferrous materials are not as readily cut and shaped with the oxyacetylene cutting process because of their reluctance to oxidize. For these materials, arc cutting is often used to good advantage.

The cutting of steel is a chemical action. The oxygen combines readily with the iron to form iron oxide. In cast iron, this action is hindered by the presence of carbon in graphite

Copyright 2004, Industrial Press, Inc., New York, NY

form. Thus, cast iron cannot be cut as readily as steel; higher temperatures are necessary and cutting is slower. In steel, the action starts at bright red heat, whereas in cast iron, the temperature must be nearer to the melting point to obtain a sufficient reaction.

The Cutting Torch.— The ordinary cutting torch consists of a heating jet using oxygen and acetylene, oxygen and hydrogen, or, in fact, any other gas that, when combined with oxygen, will produce sufficient heat. By the use of this heating jet, the metal is first brought to a sufficiently high temperature, and an auxiliary jet of pure oxygen is then turned onto the red-hot metal, and the action just referred to takes place. Some cutting torches have a number of preheating flame ports surrounding the central oxygen port, so that a preheating flame will precede the oxygen regardless of the direction in which the torch is moved. This arrangement has been used to advantage in mechanically guided torches. The rate of cutting varies with the thickness of the steel, the size of the tip, and the oxygen pressure.

Adjustment and Use of Cutting Torch.— When using the cutting torch for the cutting of steel plate, the preheating flame first comes into contact with the edge of the plate and quickly raises it to a white-hot temperature. The oxygen valve is then opened, and as the pure oxygen comes into contact with the heated metal, the latter is burned or oxidized.

Metals That Can Be Cut.— Metals such as wrought iron and steels of comparatively low-carbon content can be cut readily with the cutting torch. High-carbon steels may be cut successfully if preheated to a temperature that depends somewhat on the carbon content. The higher the carbon content, the greater the degree of preheating required. A black heat is sufficient for ordinary tool steel, but a low red heat may be required for some alloy tool steels. Brass and bronze plates have been cut by interposing them between steel plates.

Cutting Stainless Steel.— Stainless steel can be cut readily by the flux-injection method. The elements that give stainless steels their desirable properties produce oxides that reduce the flame cutting operation to a slow melting-away process when the conventional oxy-acetylene cutting equipment is used. By injecting a suitable flux directly into the stream of cutting oxygen before it enters the torch, the obstructing oxides can be removed. Portable flux feeding units are designed to inject a predetermined amount of the flux powder. The rate of flux flow is accurately regulated by a vibrator type of dispenser with rheostat control. The flux-injection method is applicable either to machine cutting or to a hand-controlled torch. The operating procedure and speed of cutting are practically the same as in cutting mild steel.

Cutting Cast Iron.— The cutting of cast iron with the oxyacetylene torch is practicable, although it cannot be cut as readily as steel. The ease of cutting seems to depend largely on the physical character of the cast iron, very soft cast iron being more difficult to cut than harder varieties. The cost is much higher than that for cutting the same thickness of steel, because of the larger preheating flame necessary and the larger oxygen consumption. In spite of this extra cost, however, this method is often economical. The slag from a cast-iron cut contains considerable melted cast iron, whereas in steel, the slag is practically free from particles of the metal, indicating that cast-iron cutting is partly a melting operation. Increased speed and decreased cost often can be obtained by feeding a steel rod, about ¼ inch in diameter, into the top of the cut, beneath the torch tip. This rod furnishes a large amount of slag that flows over the cut and increases the temperature of the cast iron. Special tips are used because of the larger amounts of heat and oxygen required.

Mechanically Guided Torches.— Cutting torches used for cutting openings in plates or blocks or for cutting parts to some definite outline are often guided mechanically or by numerical control. Torches guided by pantograph mechanisms are especially adapted for tracing the outline to be cut from a pattern or drawing. Other designs are preferable for straight-line cutting and one type is designed for circular cutting.

Cutting Steel Castings.— When cutting steel castings, care should be taken to prevent burning pockets in the metal when the flame strikes a blowhole. If a blowhole is pene-

Copyright 2004, Industrial Press, Inc., New York, NY

trated, the molten oxide will splash into the cavity and the flame will be diverted. The presence of the blowhole is generally indicated by excessive sparks. The operator should immediately move the torch back along the cut and direct it at an angle so as to strike the metal beneath the blowhole and burn it away if possible beyond the cavity. Cutting in the normal position then may be resumed.

Thickness of Metal That Can Be Cut.— The maximum thickness of metal that can be cut by these high-temperature flames depends largely upon the gases used and the pressure of the oxygen, which may be as high as 150 lb/in.^{2} The thicker the metal, the higher the pressure required. When using an oxyacetylene flame, it might be practicable to cut iron or steel up to 12 or 14 inches in thickness, whereas an oxyhydrogen flame has been used to cut steel plates 24 inches thick. The oxyhydrogen flame will cut thicker material principally because it is longer than the oxyacetylene flame and can penetrate to the full depth of the cut, thus keeping all the oxide in a molten condition so that it can be easily blown out by the oxygen cutting jet. A mechanically guided torch will cut thick material more satisfactorily than a hand-guided torch, because the flame is directed straight into the cut and does not wobble, as it tends to do when the torch is held by hand. With any flame, the cut is less accurate and the kerf wider, as the thickness of the metal increases. When cutting light material, the kerf might be $\frac{1}{16}$ inch wide, whereas for heavy stock, it might be $\frac{1}{4}$ or $\frac{3}{8}$ inch wide.

Hard Facing

Hard facing is a method of adding a coating, edge, or point, of a metal or alloy capable of resisting abrasion, corrosion, heat, or impact, to a metal component. The process can be applied equally well to new parts or old worn parts. The most common welding methods used to apply hard-facing materials include the oxyacetylene gas, shielded-metal arc, submerged arc, plasma arc, and inert-gas-shielded arc (consuming and nonconsuming electrode). Such coatings can also be applied by a spraying process, using equipment designed to handle the coating material in the form of a wire or a powder.

Hard-Facing Materials.— The first thing to be considered in the selection of a hard-facing material is the type of service the part in question is to undergo. Other considerations include machinability, cost of hard-facing material, porosity of the deposit, appearance in use, and ease of application. Only generalized information can be given here to guide the selection of a material as the choice is dependent upon experience with a particular type of service. Generally, the greater the hardness of the facing material, the greater is its resistance to abrasion and shock or impact wear. Many hardenable materials may be used for hard facing such as carbon steels, low-alloy steels, medium-alloy steels, and medium-high alloys but none of these is outstanding. Some of the materials that might be considered to be preferable are high-speed steel, austenitic manganese steel, austenitic high-chromium iron, cobalt-chromium alloy, copper-base alloy, and nickel-chromium-boron alloy.

High-Speed Steels.— These steels are available in the form of welding rods (RFe5) and electrodes (EFe5) for hard facing where hardness is required at service temperatures up to 1100 degrees F and where wear resistance and toughness are also required. Typical surfacing operations are done on cutting tools, shear blades, reamers, forming dies, shearing dies, guides, ingot tongs, and broaches using these metals.

Hardness: These steels have a hardness of 55 to 60 on the Rockwell C scale in the as-welded condition and a hardness of 30 Rockwell C in the annealed condition. At a temperature of 1100 degrees F, the as-deposited hardness of 60 Rockwell C falls off very slowly to 47 Rockwell C. At about 1200 degrees F, the maximum Rockwell C hardness is 30.

Resistance Properties: As deposited, the alloys can withstand only medium impact, but when tempered, the impact resistance is increased appreciably. Deposits of these alloys will oxidize readily because of their high molybdenum content but can withstand atmospheric corrosion. They do not withstand liquid corrosives.

Copyright 2004, Industrial Press, Inc., New York, NY

Other Properties or Characteristics: The metals are well suited for metal-to-metal wear especially at elevated temperatures. They retain their hardness at elevated temperatures and can take a high polish. For machining, these alloys must first be annealed. Full hardness may be regained by a subsequent heat treatment of the metal.

Austenitic Manganese Steels.— These metals are available in the form of electrodes (EFeMn) for hard facing when dealing with metal-to-metal wear and impact. Uses include facing rock-crushing equipment and railway frogs and crossings.

Hardness: Hardness of the as-deposited metals are 170 to 230 Bhn, but they can be work-hardened to 450 to 550 Bhn very readily. For all practical purposes, these metals have no hot hardness as they become brittle when reheated above 500 to 600 degrees F.

Resistance Properties: These metals have high impact resistance. Their corrosion and oxidation resistance are similar to those of ordinary carbon steels. Their resistance to abrasion is only mediocre compared with hard abrasives like quartz.

Other Properties or Characteristics: The yield strength of the deposited metal in compression is low, but any compressive deformation rapidly raises it until plastic flow ceases. This property is an asset in impact wear situations. Machining is difficult with ordinary tools and equipment; finished surfaces are usually ground.

Austenitic High-Chromium Irons.— These metals are available in rod (RFeCr-A) and electrode (EFeCr-A) form and are used for facing agricultural machinery parts, coke chutes, steel mill guides, sand-blasting equipment, and brick-making machinery.

Hardness: The as-welded deposit ranges in hardness from 51 to 62 Rockwell C. Under impact, the deposit work hardens somewhat, but the resulting deformation also leads to cracking and impact service is therefore avoided. Hot hardness decreases slowly at temperatures up to 800 and 900 degrees F. At 900 degrees F, the instantaneous hardness is 43 Rockwell C. In 3 minutes under load, the hardness drops to 37 Rockwell C. At 1200 degrees F, the instantaneous hardness is 5 Rockwell C. The decrease in hardness during hot testing is practically recovered on cooling to ambient temperatures.

Resistance Properties: Deposits will withstand only light impact without cracking. Dynamic compression stresses above 60,000 pounds per square inch should be avoided. These metals exhibit good oxidation resistance up to 1800 degrees F and can be considered for hot wear applications where hot plasticity is not objectionable. They are not very resistant to corrosion from liquids and will rust in moist air, but are more stable than ordinary iron and steel. Resistance to low-stress scratching is outstanding and is related to the amount of hard carbides present. However, under high-stress grinding abrasion, performance is only mediocre and they are not deemed suitable for such service.

Other Properties or Characteristics: The deposited metals have a yield strength (0.1 per cent offset) of between 80,000 and 140,000 pounds per square inch in compression and an ultimate strength of from 150,000 to 280,000 pounds per square inch. Their tensile strength is low and therefore tension uses are avoided in design. These deposits are considered to be commercially unmachinable and are also very difficult to grind. When ground, a grinding wheel of aluminum oxide abrasive with a 24-grit size and a hard (Q) and medium-spaced resinoid bond is recommended for off-hand high-speed work and a slightly softer (P) vitrified bond for off-hand low-speed work.

Cobalt-Base Alloys.— These metals are available in both rod (RCoCr) and electrode (ECoCr) form and are frequently used to surface the contact surfaces of exhaust valves in aircraft, truck, and bus engines. Other uses include parts such as valve trim in steam engines, and on pump shafts, where conditions of corrosion and erosion are encountered. Several metals with a greater carbon content are available (CoCr-B, CoCr-C) and are used in applications requiring greater hardness and abrasion resistance but where impact resistance is not mandatory or expected to be a factor.

Copyright 2004, Industrial Press, Inc., New York, NY

Hardness: Hardness ranges on the Rockwell C scale for gas-welded deposits are as follows: CoCr-A, 38 to 47; CoCr-B, 45 to 49; and CoCr-C, 48 to 58. For arc-welded deposits, hardness ranges (Rockwell C) as follows: CoCr-A, 23 to 47; CoCr-B, 34 to 47; and CoCr-C, 43 to 58. The values for arc-weld deposits depend for the most part on the base metal dilution. The greater the dilution, the lower the hardness. Many surfacing alloys are softened permanently by heating to elevated temperatures, however, these metals are exceptional. They do exhibit lower hardness values when hot but return to their approximate original hardness values upon cooling. Elevated-temperature strength and hardness are outstanding properties of this group. Their use at 1200 degrees F and above is considered advantageous but between 1000 and 1200 degrees F, their advantages are not definitely established, and at temperatures below 1000 degrees F, other surfacing metals may prove better.

Resistance Properties: In the temperature range from 1000 to 1200 degrees F, weld deposits of these metals have a great resistance to creep. Tough martensitic steel deposits are considered superior to cobalt-base deposits in both flow resistance and toughness. The chromium in the deposited metal promotes the formation of a thin, tightly adherent scale that provides a scaling resistance to combustion products of internal combustion engines, including deposits from leaded fuels. These metals are corrosion-resistant in such media as air, food, and certain acids. It is advisable to conduct field tests to determine specific corrosion resistance for the application being considered.

Other Properties or Characteristics: Deposits are able to take a high polish and have a low coefficient of friction and therefore are well suited for metal-to-metal wear resistance. Machining of these deposits is difficult; the difficulty increases in proportion to the increase in carbon content. CoCr-A alloys are preferably machined with sintered carbide tools. CoCr-C deposits are finished by grinding.

Copper-Base Alloys.— These metals are available in rod (RCuA1-A2, RCuA1-B, RCuA1-C, RCuA1-D, RCuA1-E, RCuSi-A, RCuSn, RCuSn-D, RCuSn-E, and RCuZn-E) and electrode (ECuA1-A2, ECuA1-B, ECuA1-C, ECuA1-D, ECuA1-E, ECuSi, ECuSn-A, ECuSn-C, ECuSn-E, and ECuZn-E) forms and are used in depositing overlays and inlays for bearing, corrosion-resistant, and wear-resistant surfaces. The CuA1-A2 rods and electrodes are used for surfacing bearing surfaces between the hardness ranges of 130 to 190 Bhn as well as for corrosion-resistant surfaces. The CuA1-B and CuA1-C rods and electrodes are used for surfacing bearing surfaces of hardness ranges 140 to 290 Bhn. The CuA1-D and CuA1-E rods and electrodes are used on bearing and wear-resistant surfaces requiring the higher hardnesses of 230 to 390 Bhn such as are found on gears, cams, wear plates, and dies. The copper-tin (CuSn) metals are used where a lower hardness is required for surfacing, for corrosion-resistant surfaces, and sometimes for wear-resistant applications.

Hardness: Hardness of a deposit depends upon the welding process employed and the manner of depositing the metal. Deposits made by the inert-gas metal-arc process (both consumable and nonconsumable electrode) will be higher in hardness than deposits made with the gas, metal-arc, and carbon-arc processes because lower losses of aluminum, tin, silicon, and zinc are achieved due to the better shielding from oxidation. Copper-base alloys are not recommended for use at elevated temperatures because their hardness and mechanical properties decrease consistently as the temperature goes above 400 degrees F.

Resistance Properties: The highest impact resistance of the copper-base alloy metals is exhibited by CuA1-A2 deposits. As the aluminum content increases, the impact resistance decreases markedly. CuSi weld deposits have good impact properties. CuSn metals as deposited have low impact resistance and CuZn-E deposits have a very low impact resistance. Deposits of the CuA1 filler metals form a protective oxide coating upon exposure to the atmosphere. Oxidation resistance of CuSi deposits is fair and that of CuSn deposits are comparable to pure copper. With the exception of the CuSn-E and CuZn-E alloys, these

Copyright 2004, Industrial Press, Inc., New York, NY

metals are widely used to resist many acids, mild alkalies, and salt water. Copper-base alloy deposits are not recommended for use where severe abrasion is encountered in service. CuA1 filler metals are used to overlay surfaces subjected to excessive wear from metal-to-metal contact such as gears, cams, sheaves, wear plates, and dies.

Other Properties or Characteristics: All copper-base alloy metals are used for overlays and inlays for bearing surfaces with the exception of the CuSi metals. Metals selected for bearing surfaces should have a Brinell hardness of 50 to 75 units below that of the mating metal surface. Slight porosity is generally acceptable in bearing service as a porous deposit is able to retain oil for lubricating purposes. CuA1 deposits in compression have elastic limits ranging from 25,000 TO 65,000 lb/in.^{2} and ultimate strengths of 120,000 to 171,000 lb/in.^{2} The elastic limit and ultimate strength of CuSi deposits in compression are 22,000 lb/in.^{2} and 60,000 lb/in.^{2}, respectively. CuZn-E deposits in compression have an elastic limit of only about 5000 lb/in.^{2} and an ultimate strength of 20,000 lb/in.^{2} All copper-base alloy deposits can be machined.

Nickel-Chromium-Boron Alloys.— These metals are available in both rod (RNiCr) and electrode (ENiCr) form and their deposits have good metal-to-metal wear resistance, good low-stress, scratch-abrasion resistance, corrosion resistance, and retention of hardness at elevated temperatures. These properties make the alloys suitable for use on seal rings, cement pump screws, valves, screw conveyors, and cams. Three different formulations of these metals are recognized (NiCr-A, NiCr-B, and NiCr-C).

Hardness: Hardness of the deposited NiCr-A from rods range from 35 to 40 Rockwell C; of NiCr-B rods, 45 to 50 Rockwell C; of NiCr-C rods, 56 to 62 Rockwell C. Hardness of the deposited NiCr-A from electrodes ranges from 24 to 35 Rockwell C; of NiCr-B from electrodes, 30 to 45 Rockwell C; and of NiCr-C electrodes, 35 to 56. The lower hardness values and greater ranges of hardness values of the electrode deposits are attributed to the dilution of deposit and base metals. Hot Rockwell C hardness values of NiCr-A electrode deposits range from 30 to 19 in the temperature range from 600 to 1000 degrees F from instantaneous loading to a 3-minute loading interval. NiCr-A rod deposits range from 34 to 24 in the same temperature range and under the same load conditions. Hot Rockwell C hardness values of NiCr-B electrode deposits range from 41 to 26 in the temperature range from 600 to 1000 degrees F from instantaneous loading to a 3-minute loading interval. NiCr-B rod deposits range from 46 to 37 in the same temperature range and under the same load conditions. Hot Rockwell C hardness values of NiCr-C electrode deposits range from 49 to 31 in the temperature range from 600 to 1000 degrees F from instantaneous loading to a 3-minute loading interval. NiCr-C rod deposits range from 55 to 40 in the same temperature range and under the same load conditions.

Resistance Properties: Deposits of these metal alloys will withstand light impact fairly well. When plastic deformation occurs, cracks are more likely to appear in the NiCr-C deposit than in the NiCr-A and NiCr-B deposits. NiCr deposits are oxidation-resistant up to 1800 degrees F. Their use above 1750 degrees F is not recommended because fusion may begin near this temperature. NiCr deposits are completely resistant to atmospheric, steam, salt water, and salt spray corrosion and to the milder acids and many common corrosive chemicals. It is advisable to conduct field tests when a corrosion application is contemplated. These metals are not recommended for high-stress grinding abrasion. NiCr deposits have good metal-to-metal wear resistance, take a high polish under wearing conditions, and are particularly resistant to galling. These properties are especially evident in the NiCr-C alloy.

Other Properties or Characteristics: In compression, these alloys have an elastic limit of 42,000 lb/in.^{2} Their yield strength in compression is 92,000 lb/in.^{2} (0.01 per cent offset), 150,000 lb/in.^{2} (0.10 per cent offset), and 210,000 lb/in.^{2} (0.20 per cent offset). Deposits of NiCr filler metals may be machined with tungsten carbide tools using slow speeds, light

Copyright 2004, Industrial Press, Inc., New York, NY

feeds, and heavy tool shanks. They are also finished by grinding using a soft-to-medium vitrified silicon carbide wheel.

Chromium Plating.— Chromium plating is an electrolytic process of depositing chromium on metals either as a protection against corrosion or to increase the surface-wearing qualities. The value of chromium-plating plug and ring gages has probably been more thoroughly demonstrated than any other single application of this treatment. Chromium-plated gages not only wear longer, but when worn, the chromium may be removed and the gage replated and reground to size.

In general, chromium-plated tools have operated well, giving greatly improved performance on nearly all classes of materials such as brass, bronze, copper, nickel, aluminum, cast iron, steel, plastics, asbestos compositions, and similar materials. Increased cutting life has been obtained with chromium-plated drills, taps, reamers, files, broaches, tool tips, saws, thread chasers, and the like. Dies for stamping, drawing, hot forging, die casting, and for molding plastics materials have shown greatly increased life after being plated with hard chromium.

Special care is essential in grinding and lapping tools preparatory to plating the cutting edges, because the chromium deposit is influenced materially by the grain structure and hardness of the base metal. The thickness of the plating may vary from 0.0001 to 0.001 or 0.002 inch, the thicker platings being used to build up undersize tools such as taps and reamers. A common procedure in the hard chromium plating of tools, as well as for parts to be salvaged by depositing chromium to increase diameters, is as follows:

1) Degrease with solvent; 2) Mount the tools on racks; 3) Clean in an anodic alkali bath held at a temperature of 82 degrees C for from 3 to 5 minutes; 4) Rinse in boiling water; 5) Immerse in a 20 per cent hydrochloric acid solution for 2 to 3 seconds; 6) Rinse in cold water; 7) Rinse in hot water; 8) Etch in a reverse-current chromic acid bath for 2 to 5 minutes; 9) Place work immediately in the chromium plating bath; and 10) Remove hydrogen embrittlement, if necessary, by immersing the plated tools for 2 hours in an oil bath maintained at 177 degrees C.

Chromium has a very low coefficient of friction. The static coefficient of friction for steel on chromium-plated steel is 0.17, and the sliding coefficient of friction is 0.16. This value may be compared with the static coefficient of friction for steel on steel of 0.30 and a sliding coefficient of friction of 0.20. The static coefficient of friction for steel on babbitt is 0.25, and the sliding coefficient of friction 0.20, whereas for chromium-plated steel on babbitt, the static coefficient of friction is 0.15, and the sliding coefficient of friction is 0.13. These figures apply to highly polished bearing surfaces. Articles that are to be chromium plated in order to resist frictional wear should be highly polished before plating so that full advantage can be taken of the low coefficient of friction that is characteristic of chromium. Chromium resists attack by almost all organic and inorganic compounds, except muriatic and sulfuric acids. The melting point of chromium is 2930 degrees F, and it remains bright up to 1200 degrees F. Above 1200 degrees F, a light adherent oxide forms and does not readily become detached. For this reason, chromium has been used successfully for protecting articles that must resist high temperatures, even above 2000 degrees F.

Electron-Beam (EB) Welding

Heat for melting of metals in electron-beam welding is obtained by generating electrons, concentrating them into a beam, and accelerating them to between 30 and 70 per cent of the speed of light, using voltages between 25 and 200 kV. The apparatus used is called an electron-beam gun, and it is provided with electrical coils to focus and deflect the beam as needed for the welding operation. Energy input depends on the number of electrons impinging on the work in unit time, their velocity, the degree of concentration of the beam, and the traveling speed of the workpiece being welded. Some 6.3×10^{15} electrons/s are generated in a 1-mA current stream. With beam diameters of 0.01 to 0.03 in. (0.25 to 0.76

Copyright 2004, Industrial Press, Inc., New York, NY

mm), beam power can reach 100 kW and power density can be as high as 10^7 W/in^2 (1.55×10^4 W/mm^2), higher than most arc welding levels.

At these power densities, an electron beam can penetrate steel up to 4 in thick and form a vapor capillary or keyhole, as described earlier. Although patterns can be traced by deflecting the beam, the method used in welding is to move the electron gun or the workpiece. A numerical control, or computer numerical control, program is used because of the accuracy required to position the narrow beam in relation to the weld line.

Equipment is available for electron-beam welding under atmospheric pressure or at various degrees of vacuum. The process is most efficient (produces the narrowest width and deepest penetration welds) at high levels of vacuum, of the order of 10^{-6} to 10^{-3} torr or lower (standard atmospheric pressure is about 760 torr, or 760 mm of mercury), so that a vacuum chamber large enough to enclose the work is needed. Operation in a vacuum minimizes contamination of the molten weld material by oxygen and nitrogen. Gases produced during welding are also extracted rapidly by the vacuum pump so that welding of reactive metals is eased. However, the pumping time and the size of many workpieces restrict the use of high-vacuum enclosures.

At atmospheric pressures, scattering of the beam electrons by gas molecules is increased in relation to the number of stray molecules and the distance traveled, so that penetration depth is less and the beam spread is greater. In the atmosphere, the gun-to-work distance must be less than about 1.5 in. (38 mm). Electron-beam welding at atmospheric pressure requires beam-accelerating voltages above 150 kV, but lower values can be used with a protective gas. Helium is preferred because it is lighter than air and permits greater penetration. Argon, which is heavier than air and allows less penetration, can also be used to prevent contamination.

Required safety precautions, such as radiation shields to guard workers against the effects of X-rays when the electron beam strikes the work, are essential when electron-beam welding is done at atmospheric pressure. Such barriers are usually built into enclosures that are designed specifically for electron-beam welding in a partial vacuum. Adequate ventilation is also required to remove ozone and other gases generated when the process is used in the atmosphere.

Carbon, low-alloy, and stainless steels; high-temperature and refractory alloys; copper and aluminum alloys can be electron-beam welded, and single-pass, reasonably square, butt welds can be made in materials up to 1 in. (25.4 mm) thick at good speeds with nonvacuum equipment rated at 60 kW. Edges of thick material to be electron-beam welded require precision machining to provide good joint alignment and minimize the joint gap. Dissimilar metals usually may be welded without problems.

Because of the heat-sink effect, electron-beam welds solidify and cool very rapidly, causing cracking in certain materials such as low-ferrite stainless steel. Although capital costs for electron-beam welding are generally higher than for other methods, welding of large numbers of parts and the high welding travel rates make the process competitive.

Pipe Welding

Pipe Welding.— Welding of (usually steel) pipe is commonly performed manually, with the pipe joint stationary, or held in a fixture whereby rotation can be used to keep the weld location in a fixed, downhand, position. Alternatively, pipe may need to be welded on site, without rotation, and the welder then has to exert considerable skill to produce a satisfactory, pressure-tight joint. Before welding stationary pipe, a welder must be proficient in welding in the four basic positions: 1G flat, 2G horizontal, 3G vertical and 4G overhead, depicted at the top in Figs. 1a, 1b, 1c, and 1d.

Copyright 2004, Industrial Press, Inc., New York, NY

Positioning of Joint Components in Pipe Welding



Fig. 1a. Flat Position 1G



Fig. 1b. Horizontal Position 2G



Fig. 1c. Vertical Position 3G



Fig. 1d. Overhead Position 4G



Fig. 1e. Horizontal position 2G Pipe Axis Vertical



Fig. 1f. Position 5G Pipe Fixed, Axis Horizontal



Fig. 1g. Position 6G Pipe Fixed, Axis Inclined

At the bottom are shown pipe joints in three positions, the first of which, Fig. 1e, corresponds to the 2G horizontal (non-rotational) position in the upper row. The remaining two are respectively 5G, Fig. 1f, that represents pipe with the weld in a fixed vertical (non-rotational) position; and 6G, Fig. 1g, that typifies pipe to be welded at an angle and not rotated during welding.

For satisfactory pipe welding, consideration must be given to the chemical composition and thickness of the metal to be welded; selection of a suitable electrode material composition and size; determination of the current, voltage and wire feed rate to be used; preparation of the joint or edges of the pipes; and ways of holding the pipes in the positions needed while welding is carried out. High-quality tack welds, each about 1.5 inches (38 mm) long, and projecting about $\frac{1}{16}$ inch (1.6 mm) beyond the inner wall of the pipe, are usually made to hold the parts of the assembly in position during welding.

SMAW (stick) welding was used almost exclusively for pipe welding until the advent of MIG welding with its potential for much greater rates of deposition. It cannot be emphasized too strongly that practices suitable for SMAW cannot be transferred to MIG welding, for which greater expertise is required if satisfactory welds are to be produced. MIG short-circuit, globular, and spray transfer, and pulsed MIG, with flux or metal-cored consumables (electrodes) can now all be used for pipe welding. Use of all-position, flux-cored, MIG consumables in particular, can reduce skill requirements, improve weld quality, and hold down costs in pipe welding.

Among the important items involved in the change to the MIG process is the automatic wire feeder. With today's wire feeding equipment, an increase of one increment on the dial, say from the 9 to the 10 o'clock position, can increase the wire feed rate by 70 in/min. As an example, such an increase could raise the weld current from 110 to 145 amps and the weld voltage from 16 to 17, resulting in an increase of 40 per cent in the energy supplied to the weld. Another vital parameter is the amount that the wire sticks out from the contact tip. In low-parameter, short-circuit welding, a small change in the wire stick-out can alter the energy supplied to the weld by 20 to 30 per cent.

Root passes: Whatever welding process is selected, the most important step in pipe welding, as in other types of welding, is the root pass, which helps to determine the degree of penetration of the weld metal, and affects the amount of lack of fusion in the finished weld. During the root pass, the action of the arc in the weld area should reshape the gap between

Copyright 2004, Industrial Press, Inc., New York, NY

the adjacent sides of the joint into a pear-shaped opening, often called a "keyhole." As the work proceeds, this keyhole opening is continuously being filled, on the trailing side of the weld, by the metal being deposited from the electrode. The keyhole travels along with the weld so that the root pass produces a weld that penetrates slightly through the inner wall of the pipe.

MIG short-circuit root welding of carbon steel pipe requires a gap of $\frac{5}{32} \pm \frac{1}{32}$ (4 ± 0.8 mm), between the ends of the pipe, and the width of the root faces (at the base of the bevels) should be $\frac{1}{16}$ to $\frac{3}{32}$ inch (1.6 to 2.4 mm). The recommended bevel angle for MIG pipe welding is 40E (80E included angle) and the maximum root gap is $\frac{3}{16}$ inch (4.8 mm). The root pass in 1G welds should be made in the vertical-down direction with the electrode held between the 2 and 3 o'clock positions. When an 0.035-inch (0.9-mm) diameter E70S-3 MIG wire is used with the above root dimensions, weaving is not needed for the root pass except when welding over tack welds.

Fill passes: In welding carbon steel pipe in the 1G position with an 0.035-inch diameter electrode wire, MIG short circuit fill passes should use a minimum of 135 amps and be done in the vertical-up position. Fill passes should deposit a maximum thickness of no more than $\frac{1}{8}$ inch (3.2 mm). Inclusion of CO_2 gas in the mixture will improve weld fusion. With flux-cored electrodes, the minimum amount of wire stick out is $\frac{3}{4}$ inch (19 mm). Weld fusion can be improved in welding pipe of 0.4 inch (10 mm) wall thickness and thicker by preheating the work to a temperature between 400 and 500°F.

Horizontal Pipe Welding: In 1G welds (see Fig. 1a), the pipe should be rotated in the direction that moves the solidifying area away from the wire tip, to minimize penetration and resulting breakthrough. Welding of pipe in the 2G, horizontal position is made more difficult by the tendency for the molten metal to drip from the weld pool. Such dripping may cause an excessively large keyhole to form during the root-welding pass, and in subsequent passes electrode metal may be lost. Metal may also be lost from the edge of the upper pipe, causing an undercut at that side of the weld.

Vertical-down welding: With the pipe axis horizontal (as in the 5G position in Fig. 1f), vertical-down welding is usually started at the top or 12 o'clock location, and proceeds until the 6 o'clock location is reached. Welding then starts again at the 12 o'clock location and continues in the opposite direction until the 6 o'clock location is reached. Vertical-down welding is mainly used for thin-walled, low-carbon steel pipe of $\frac{1}{8}$ to $\frac{5}{16}$ inch (3.2 to 7.9 mm) wall thickness, which has low heat-retaining capacity so that the weld metal cools slowly, producing a soft and ductile structure. The slow rate of cooling also permits faster weld deposition, and, when several beads are deposited, causes an annealing effect that may refine the entire weld structure.

Vertical-up welding: In the 5G position, vertical-up welding normally begins at the 6 o'clock location and continues up to the 12 o'clock location, the weld then being completed by starting at the 6 o'clock location on the other side of the pipe and traversing up to the 12 o'clock location again. Vertical-up welding is more suited to pipe with thick walls and to alloy steels. However, the greater heat sink effect of the heavy-walled pipe may result in a faster cooling rate and embrittlement of the material, especially in alloy steels. The cooling rate can be reduced by slowing the rate of traverse and depositing a heavier bead of metal, both facilitated by welding in the vertical-up direction.

Using a thicker electrode and higher current for thicker-walled pipe to reduce the number of beads required may result in dripping from the molten puddle of metal. Defects such as pin holes, lack of fusion, and cold lap, may then appear in the weld. Vertical-up welding of pipe in the 5G, fixed, horizontal position, Fig. 1f, used for thick-walled pipe, is probably the most difficult for a welder, but once mastered will form the basis for other methods of pipe welding. Starting at the 6 o'clock location, the arc for the root pass is struck overhead, with the electrode at an angle of 5 to 10° from the vertical, on the joint, not on the tack weld.

Copyright 2004, Industrial Press, Inc., New York, NY

A long arc should be maintained for a short-period while weaving the electrode to pre-heat the area ahead of the weld. Only small amounts of filler metal will be transferred while this long arc is maintained in the overhead position. The electrode tip is then advanced to establish the correct arc length and held in position long enough for the keyhole to form before starting to lay down the root bead, moving up toward the 12 o'clock location.

Thin-wall pipe: The optimum globular/spray parameters for welding rotated, (1G position) thin-wall pipe of less than 12 inch diameter are 0.035-inch electrode wire fed at 380 to 420 in/min with a protective gas mixture of argon 80 to 85, CO_2 15 to 20 per cent, and current of 190 to 210 amps. These conditions will provide deposition rates of about 6 lb/hr (3 kg/hr).

Use of Flux-cored Electrodes.— Small diameter, flux cored electrodes developed in the eighties are still a rarity in many pipe welding shops, but flux cored welding can produce consistent, high-quality, low-cost welds on carbon steel or stainless pipe. Flux cored E71T-1, 035-inch (1 mm) diameter wire provides a continuous, medium energy, open arc, with a practical current range of 135 to 165 amps for welding pipe. This current range is similar to the optimum MIG short-circuit current range, and is 25 to 30 percent less current than the minimum open arc spray transfer current for an 0.035-inch diameter MIG wire.

In contrast to MIG short circuit welding, FCAW works with an open arc and no short circuits. The FCAW arc energy is continuous, and, in contrast to short-circuit transfer, provides increased weld fusion potential. The weld metal from the flux-cored tubular wire is transferred from the periphery and the center of the wire, resulting in broad coverage of the weld. The plasma in the flux cored arc is wider than MIG plasma, and the flux-cored arc is less focused and easier to control than the MIG spray arc.

Open arc, gas shielded, flux-cored welding can produce spray type transfer at lower currents than open arc MIG spray transfer. With FCAW, the current density is high because the electrode wire cross-sectional area is less than that of the same size MIG solid wire due to the central core of flux. This higher density provides for improved weld penetration potential. The FCAW process produces slag, which serves as a mold to hold the fluid molten metal in place, an ideal arrangement for vertical-up and overhead welds.

All position, flux-cored wires require less operator skill for vertical-up and overhead welds than MIG, SMAW, and TIG processes. Fill passes can also be completed in 30 to 50 percent less time with all-position, flux-cored wires than with MIG short circuit and SMAW wires.

For good quality FCAW, welders need to know the best root and bevel dimensions, and the importance of maintaining those dimensions for continuous weld fusion; the preferred direction of pipe rotation; the diameter of flux cored electrode best suited for welding thin wall pipe; the optimum parameter range for that electrode on 1G and 5G welds; the preferred amount of wire stick out (typically 0.7 inch or 18 mm); and how to fine tune the voltage. When flux-cored welding is to be used for the fill passes, MIG short circuit welding is recommended for the root welds to reduce the possibility of slag from the flux being trapped in the weld. Higher weld deposit rates are provided with flux-cored, vertical-up welding, and there is the temptation to weld faster with a process that's easy to use. Conservative wire feed setting are recommended unless the high deposition rates are shown to provide consistent weld fusion. Wire feed settings should allow the welder time to control and direct the weave into the critical groove locations.

Complete Weld Fusion.— It is essential that new weld metal deposits be completely fused with the pipe components, and with metal laid down in successive passes. Factors that can prevent complete fusing are too numerous to list here. Some basic rules that, if followed, will improve weld fusion and quality in MIG welding in the 1G and 5G positions are:

1) The maximum gap at the root should be $\frac{3}{16}$ inch (5 mm)

2) The root land should be $\frac{1}{16}$ to $\frac{3}{32}$ inch (1.6 to 2.4 mm) wide

Copyright 2004, Industrial Press, Inc., New York, NY

3) A bevel angle of 80° inclusive should be used for MIG and flux-cored welding of pipe to provide width for weaving and improve fusion.
4) An 0.035-in MIG electrode should have a minimum short circuit current of 135 amps for fill passes
5) Tack and root welds should be made in the vertical-down position.
6) Tack welds should be about 1.5 in (38 mm) long by 1/16 to 3/32 inch (1.6 to 2.4 mm) thick.
7) Short circuit fill passes should be made in the vertical-up position.
8) With flux-cored electrodes, a minimum of 0.7 inch (18 mm) wire stick out from the contact tip must be maintained.
9) Current and voltage must be related to the pipe wall thickness
10) Argon+25 per cent CO_2 is recommended for short circuit welding of pipe roots.
11) Use of undiluted CO_2 gas will improve MIG weld fusion in fill passes because of the "digging" action of the arc, and the increased weld energy
12) With pipe wall thicknesses of 0.4 in (10 mm) or greater, preheating to between 400 and 500° F (205 and 260°C), will help make fusion complete

Other Methods.— Pulsed MIG is a viable alternative to flux-cored for all-position welds on 5G pipe, but requires more costly equipment. The pulsed MIG process however, has few advantages over conventional MIG and flux-cored when the latter are used correctly. Pulsed MIG may have some advantage on mechanized 5G welds, and on welding of stainless steel, pipe in the 5G position.

Metal-cored electrode wire also has few advantages for pipe welds because they work best with low-energy gas welds, which cancels out the increased current density claimed for them.

On most manual pipe welds, the welder needs time to control and direct the weave to ensure even heating and avoid lack of fusion. Satisfactory welds are often performed at travel speeds of 4 to 12 in/min giving deposit rates of 3 to 5 lb/hr.

Pipe Welding Procedure

Because of the variety of parameter combinations that can be used in pipe welding, it is suggested that charts be prepared and displayed in welding booths to remind welders of the basic settings to be used. Examples of such charts for tack, root, fill and cover passes, are included in what follows:

FCAW 5G (Non-rotated) MIG Welding of Thick-Walled, Carbon-steel Pipes, Procedure for Root Welding.— This procedure can be applied to most pipe sizes, and should be given special consideration for 5G (non-rotated) welds on carbon steel pipe with 3/8 inch (10 mm) wall thickness and thicker.

Pipe and Weld Data

Pipe bevel included angle = 80°
Root face land = 3/32 ± 1/32 inch (2.4 ± 0.8 mm)
Root gap between faces = 5/32 ± 1/32 inch (4 ± 0.8 mm)
Electrode for root weld = 0.035-inch (0.9 mm) diameter, E70S-3 flux-cored.
Gas = argon with 15–25% CO_2
Gas flow rates = 30 to 40 cubic ft/hr

Set wire feeder to 210–280 in/min(10 to 11 o'clock position on many feeders) for current of 140–170 amps, 17–18 volts.

Wire extension: For MIG root weld, set contact tip to stick outside the nozzle, 1/16 to 1/8 inch (1.6 to 3 mm). Maintain 3/8 to 5/8 inch (10 to 16 mm) maximum wire stick out from contact tip.

Copyright 2004, Industrial Press, Inc., New York, NY

Tack Welding Procedures for FCAW 5G Pipe Welds: Make tack welds 1.5 to 2 inches (38 to 50 mm) long. After welding, grind full length of tack to thickness of approximately 1/16 inch (1.6 mm). Feather tack ends back 3/8 to 1/2 inches (9.5 to 13 mm).

On pipes of less than 6 inches (15 cm) outside diameter, use three tack welds, equally spaced, starting at 12 o'clock.

On pipes over 6 inches outside diameter use 4 tack welds. Locate tack welds at 12, 3, 6, and 9 o'clock.

Root Welding Procedures for FCAW 5G Pipe Welds: Root weld MIG vertical-down. Weld sequence: 12 to 3, 9 to 6, 3 to 6, and 12 to 9 o'clock positions.

Start and finish MIG root welds at tack centers. Use slight weave oscillation over tacks. No weave necessary if 1/8- to 5/32-inch root gap is maintained. Weaving may be required if root gap is less than 1/8 inch (3 mm). Weaving is also beneficial for root welds between 7 and 6 o'clock, and between 5 and 6 o'clock. After each root pass, blend the starts and stops back to the original tack thickness.

To complete the root, ensure that the weld stops and starts on the last tack, and that the root weld center is ground flat or slightly concave. Remove any slag islands.

FCAW 5G (Non-rotated) MIG Welding of Thick-Walled, Carbon-steel Pipes, Procedure for Fill and Cover Welds.— This procedure can be applied to most common pipe sizes, and should be given special consideration for 5G (non-rotated) welds on carbon steel pipe with 3/8 inch (10 mm) wall thickness and thicker.

Pipe and Weld Data

Electrode for fill and cover passes = 0.035 inch (0.9 mm) diameter, 71T-1 flux-cored

Gas = argon with 15–25% CO_2

Gas flow rates = 30 to 40 cubic ft/hr

Set an initial wire feed rate of 350 to 450 in/min (12 to 1 o'clock position on typical wire feed unit), 135–165 amps, 25–28 volts. Alternatively, use a wire feed setting of 350 in/min (12 o'clock on wire feed unit), which should result in about 135–145 amps, 25–26 volts. If the weld pool and weld heat build up permit, increase the wire feed rate to 380 in/min (between the 12 and 1 o'clock positions), 150 amps, 27 volts. Try also a wire feed setting of 420 in/min (1 o'clock on the wire feeder), 165 amps, 28 volts. Determine the low and maximum wire feed rates to be used by examination of the weld fusion obtained in sectioned test samples.

Wire extension: Adjust contact tip so it is recessed 1/2 inch within the nozzle to provide a total wire stick out from the contact tip of 0.7 to 1 inch (18 to 25 mm).

Fill and Cover Pass Procedures for FCAW 5G Pipe Welds: Weld vertical-up. If the pipe diameter allows the fill pass to be made in two passes, start at the 7 o'clock position and weld to the 1 o'clock position. This approach is preferable to starting and finishing on the root tacks. Starting at the 7 o'clock position will ensure that optimum weld energy is achieved as the first pass welds over the initial 6 o'clock root tack location. Use the grinder to feather the first 1 inch (25 mm) of the weld start and stop of the first pass, before applying the second vertical-up weld pass. Use a slight weave action for the fill pass.

Remove all flux-cored slag between weld passes. Make sure no fill pass is greater in depth than 1/8 inch (3 mm). Use a straight weave across the root face. At the bevel edge use a slight upward motion with the gun. The motion should be no greater than the wire diameter. Then use a slight back step for added bevel fusion and to avoid undercuts.

Leave 1/32 to 1/16 inch (0.8 to 1.6 mm) of the groove depth to provide for the optimum cover pass profile. The bevel edge will act as a guide for the cover pass weld. If more weld fusion is required for pipe thicker than 3/8 inch (10 mm), after the root weld is complete, preheat the

Copyright 2004, Industrial Press, Inc., New York, NY

pipe to between 400 and 600°F (200–300°C) before welding. Preheating is typically not necessary for a cover pass.

For pipe diameters on which the welder needs more than two passes for the vertical-up welds, the recommended sequence for vertical-up welding is:

1) First pass, weld from the 7 to the 4 o'clock position. Start with a slight forehand nozzle angle. At the 4 o'clock position, the gun should be at the same angle as the pipe.
2) Second pass, weld from the 10 to the 1 o'clock position, then grind all stops and start again at the 1-inch (25 mm) position.
3) Third pass, weld from the 4 to the 1 o'clock position.
4) Fourth pass, weld from the 7 to the 10 o'clock position.

FCAW 5G (Non-rotated) Welding of Thin-Walled Carbon Steel Pipes, Procedure for Root, Fill and Cover Pass Welding.— This procedure can be applied to most common pipe sizes, and should be given special consideration for 5G (non-rotated) welding of carbon steel pipe with wall thicknesses up to $\frac{3}{8}$ inch (10 mm).

Pipe and Weld Data

Electrode for root weld = 0.035 inch diameter, E70S-6 flux cored.

Gas = argon with 15–25% CO_2

Gas flow rates = 30 to 40 cubic ft/hr

Root Welding Procedure for 5G Welds: Use root welding data from *Root Welding Procedures for FCAW 5G Pipe Welds*, above.

Fill and Cover Pass Procedures for 5G Welds: Use MIG short-circuit, vertical-up for fill and cover passes. Electrode wire and gas, same as for root weld.

Weld vertical-up. If the vertical-up fill pass can be made in two passes, weld from the 7 to the 1 o'clock position, to avoid starting and finishing on the root tacks. Starting just past 6 o'clock ensures that optimum weld energy is achieved as the first pass welds over the initial 6 o'clock root tack location. Feather 1 inch (25 mm) of the weld start and stop on the first pass with the grinder before applying the second vertical-up weld pass. Use a slight weave action.

Use MIG short-circuit wire feed, 200–230 in/min 125–135 amps, 19–22 volts. Start at optimum 210 in/min (10 o'clock on the wire feeder) for 130 amps, 21–22 volts. Fine tune voltage by listening to arc sound to obtain a consistent rapid crackle sound.

Electrode sticks out $\frac{1}{2}$ to $\frac{5}{8}$ inch, contact tip flush with nozzle end.

Remove MIG surface slag islands between weld passes. No fill pass should be thicker than $\frac{1}{8}$ inch (3 mm). Use straight weave across the root face. At the bevel, use a slight upward motion with the gun. The motion should be no greater than the wire diameter. Then use a slight back step for added bevel fusion and to avoid possibility of undercut.

For the cover pass, leave $\frac{1}{32}$ to $\frac{1}{16}$ inch of the groove depth for the optimum cover pass profile. The bevel edge will act as a guide for the cover pass weld.

If more weld fusion is required after the root is complete and between fill passes, pre-heat pipe to 200 to 400°F.

For pipe diameters on which more than two passes are required for the circumference the weld sequence is:

1) First pass, weld from the 7 to the 4 o'clock position. Start with a slight forehand nozzle angle. At the 4 o'clock position the gun should point straight at the joint; 2) Second pass, weld from the 10 to the 1 o'clock position, then grind all stops and starts for at least 1 inch (25 mm); 3) Third pass, weld from the 4 to the 1 o'clock position; and 4) Fourth pass, weld from the 7 to the 10 o'clock position.

Copyright 2004, Industrial Press, Inc., New York, NY

Weld and Welding Symbols

American National Standard Weld and Welding Symbols.— Graphical symbols for welding provide a means of conveying complete welding information from the designer to the welder by means of drawings. The symbols and their method of use (examples of which are given in the table following this section) are part of the American National Standard ANSI/AWS A2.4-79 sponsored by the American Welding Society.

In the Standard a distinction is made between the terms *weld symbol* and *welding symbol*. Weld symbols, shown in the table *Basic Weld Symbols*, are ideographs used to indicate the type of weld desired, whereas welding symbol denotes a symbol made up of as many as eight elements conveying explicit welding instructions.

The eight elements which may appear in a welding symbol are: reference line; arrow; basic weld symbols; dimensions and other data; supplementary symbols; finish symbols; tail and specification; and process or other reference.

The standard location of elements of a welding symbol are shown in Fig. 1.



Fig. 1. Standard Location of Elements of a Welding Symbol

Reference Line: This is the basis of the welding symbol. All other elements are oriented with respect to this line. The arrow is affixed to one end and a tail, when necessary, is affixed to the other.

Arrow: This connects the reference line to one side of the joint in the case of groove, fillet, flange, and flash or upset welding symbols. This side of the joint is known as the *arrow side* of the joint. The opposite side is known as the *other side* of the joint. In the case of plug, slot, projection, and seam welding symbols, the arrow connects the reference line to the outer surface of one of the members of the joint at the center line of the weld. In this case the member to which the arrow points is the *arrow side* member: the other member is the *other side* member. In the case of bevel and J-groove weld symbols, a two-directional arrow pointing toward a member indicates that the member is to be chamfered.

Basic Weld Symbols: These designate the type of welding to be performed. The basic symbols which are shown in the table *Basic Weld Symbols* are placed approximately in the

Copyright 2004, Industrial Press, Inc., New York, NY

center of the reference line, either above or below it or on both sides of it as shown in Fig. 1. Welds on the arrow side of the joint are shown by placing the weld symbols on the side of the reference line towards the reader (lower side). Welds on the other side of the joint are shown by placing the weld symbols on the side of the reference line away from the reader (upper side).

Supplementary Symbols: These convey additional information relative to the extent of the welding, where the welding is to be performed, and the contour of the weld bead. The "weld-all-around" and "field" symbols are placed at the end of the reference line at the base of the arrow as shown in Fig. 1 and the table *Supplementary Weld Symbols*.

Dimensions: These include the size, length, spacing, etc., of the weld or welds. The size of the weld is given to the left of the basic weld symbol and the length to the right. If the length is followed by a dash and another number, this number indicates the center-to-center spacing of intermittent welds. Other pertinent information such as groove angles, included angle of countersink for plug welds and the designation of the number of spot or projection welds are also located above or below the weld symbol. The number designating the number of spot or projection welds is always enclosed in parentheses.

Contour and Finish Symbols: The contour symbol is placed above or below the weld symbol. The finish symbol always appears above or below the contour symbol (see Fig. 1).

The following finish symbols indicate the method, not the degrees of finish: C—chipping; G—grinding; M—machining; R—rolling; and H—hammering.

For indication of surface finish refer to the section *SURFACE TEXTURE* starting on page 724.

Tail: The tail which appears on the end of the reference line opposite to the arrow end is used when a specification, process, or other reference is made in the welding symbol. When no specification, process, or other reference is used with a welding symbol, the tail may be omitted.

Table 1. Basic Weld Symbols

Groove Weld Symbols							
Square	Scarf[a]	V	Bevel	U	J	Flare V	Flare bevel
							
Other Weld Symbols							
Fillet	Plug or slot	Spot or projection	Seam	Back or backing	Surfacing	Flange	
						Edge	Corner
							

[a] This scarf symbol used for brazing only (see page 1388).

For examples of basic weld symbol applications see starting on page 1436.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Supplementary Weld Symbols

Weld all around	Field weld	Melt-thru	Backing or spacer material	Countour		
				Flush	Convex	Concave
						

Melt-Thru Symbol: The melt-thru symbol is used only where 100 per cent joint or member penetration plus reinforcement are required.

Specification, Process, or Other Designation: These are placed in the tail of the welding symbol and are in accordance with the American National Standard. They do not have to be used if a note is placed on the drawing indicating that the welding is to be done to some specification or that instructions are given elsewhere as to the welding procedure to be used.

Letter Designations: American National Standard letter designations for welding and allied processes are shown in the table on page 1435.

Further Information: For complete information concerning welding specification by the use of standard symbols, reference should be made to American National Standard ANSI/AWS A2.4-79, which may be obtained from either the American National Standards Institute or the American Welding Society listed below.

Welding Codes, Rules, Regulations, and Specifications.— Codes recommending procedures for obtaining specified results in the welding of various structures have been established by societies, institutes, bureaus, and associations, as well as state and federal departments.

The latest codes, rules, etc., may be obtained from these agencies, whose names and addresses are listed as follows: PV = Pressure Vessels; P = Piping; T = Tanks; SB = Structural and Bridges; S = Ships; AC = Aircraft Construction; and EWM = Electrical Welding Machinery.

Air Force/LGM, Department of the Air Force, Washington, DC 20330. (AC)

American Bureau of Shipping, 45 Eisenhower Drive, Paramus, NJ 07652. (S)

American Institute of Steel Construction., 1 E. Wacker Drive, Chicago, IL 60601. (SB)

American National Standards Institute, 25 W. 43rd St. NY, NY 10036. (PV, P, EWM)

American Petroleum Institute, 1220 L St., NW, Washington, DC 20005. (PV)

American Society of Mechanical Engineers, 3 Park Avenue, NY, NY 10016. (PV)

American Welding Society, 550 LeJeune Road, Miami, FL 33135. (T, S, SB, AC)

Federal Aviation Administration, 800 Independence Avenue, S.W. Washington DC 20591. (AC)

Insurance Services Office, 545 Washington Blvd., Jersey City, NJ 07310. (PV)

Lloyd's Register of Shipping, 17 Battery Place, NY, NY 10004. (S)

Mechanical Contractors Association., 1385 Piccard Drive, Rockville, MD 20850. (P)

National Electrical Manufacturers. Association., 2100 North Street, Rosslyn, VA 22209. (EWM)

Naval Facilities Engineering Command, 1322 Patterson Ave., Washington Navy Yard, DC 20374. (SB)

Naval Ship Engineering Center, Dept. of the Navy, Hyattsville, MD 20782. (PV, S)

U.S. Government Printing Office, Washington, 732 N. Capitol St, N.W. DC 20402. (PV)

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Letter Designations for Welding and Allied Processes
ANSI/AWS A2.4-91

Letter Designation	Welding and Allied Processes	Letter Designation	Welding and Allied Processes
AAC	air carbon arc cutting	HPW	hot pressure welding
AAW	air acetylene welding	IB	induction brazing
AB	arc brazing	INS	iron soldering
ABD	adhesive bonding	IRB	infrared brazing
AC	arc cutting	IRS	infrared soldering
AHW	atomic hydrogen welding	IS	induction soldering
AOC	oxygen arc cutting	IW	induction welding
ASP	arc spraying	LBC	laser beam cutting
AW	carbon arc welding	LBC-A	laser beam cutting—air
B	brazing	LBC-EV	laser beam cutting—evaporative
BB	block brazing		
BMAW	bare metal arc welding	LBC-IG	laser beam cutting—inert gas
CAB	carbon arc brazing		
CAC	carbon arc cutting	LBC-O	laser beam cutting—oxygen
CAW	carbon arc welding	LBW	laser beam welding
CAW-G	gas carbon arc welding	LOC	oxygen lance cutting
CAW-S	shielded carbon arc welding	MAC	metal arc cutting
CAW-T	twin carbon arc welding	OAW	oxyacetylene welding
CEW	coextrusion welding	OC	oxygen cutting
CW	cold welding	OFC	oxyfuel gas cutting
DB	dip brazing	OFC-A	oxyacetylene cutting
DFB	diffusion brazing	OFC-H	oxyhydrogen cutting
DFW	diffusion welding	OFC-N	oxynatural gas cutting
DS	dip soldering	OFC-P	oxypropane cutting
EBC	electron beam cutting	OFW	oxyfuel gas cutting
EBW	electron beam welding	OHW	oxyhydrogen welding
EBW-HV	electron beam welding—high vacuum	PAC	plasma arc cutting
		PAW	plasma arc welding
EBW-MV	electron beam welding—medium vacuum	PEW	percussion welding
		PGW	pressure gas welding
EBW-NV	electron beam welding—nonvacuum	POC	metal powder cutting
		PSP	plasma spraying
EGW	electrogas welding	PW	projection welding
ESW	electroslag welding	RB	resistance brazing
EXW	explosion welding	RS	resistance soldering
FB	furnace brazing	RSEW	resistance seam welding
FCAW	flux-cored arc welding	RSEW-HF	resistance seam welding—high frequency
FLB	flow brazing		
FLOW	flow welding	RSEW-I	resistance seam welding—induction
FLSP	flame spraying		
FOC	chemical flux cutting	RSW	resistance spot welding
FOW	forge welding	ROW	roll welding
FRW	friction welding	RW	resistance welding
FS	furnace soldering	S	soldering
FW	flash welding	SAW	submerged arc welding
GMAC	gas metal arc cutting	SAW-S	series submerged arc welding
GMAW	gas metal arc welding		
GMAW-P	gas metal arc welding—pulsed arc	SMAC	shielded metal arccutting
GMAW-S	gas metal arc welding—short-circuiting arc	SMAW	shielded metal arc welding
GTAC	gas tungsten arc cutting	SSW	solid state welding
GTAW	gas tungsten arc welding	SW	stud arc welding
GTAW-P	gas tungsten arc welding—pulsed arc		

Copyright 2004, Industrial Press, Inc., New York, NY

Application of AmercanNational StandardWelding Symbols

Desired Weld	Symbol	Symbol Meaning
		Symbol indicates fillet weld on *arrow side* of the joint.
		Symbol indicates square-groove weld on *other side* of the joint.
		Symbol indicates bevel-groove weld on both sides of joint. Breaks in arrow indicate bevels on upper member of joint. Breaks in arrows are used on symbols designating bevel and J-groove welds.
		Symbol indicates plug weld on *arrow side* of joint.
		Symbol indicates resistance-seam weld. Weld symbol appears on both sides of reference line pointing up the fact that *arrow* and *other side* of joint references have no significance.
		Symbol indicates electron beam seam weld on *other side* of joint.

Copyright 2004, Industrial Press, Inc., New York, NY

Application of AmercanNational StandardWelding Symbols *(Continued)*

Desired Weld	Symbol	Symbol Meaning
		Symbol indicates single-pass back weld.
		Symbol indicates a built-up surface $\frac{1}{8}$ inch thick.
		Symbol indicates a bead-type back weld on the *other side* of joint, and a J-groove grooved horizontal member (shown by break in arrow) and fillet weld on *arrow side* of the joint.
		Symbol indicates two fillet welds, both with $\frac{1}{2}$-inch leg dimensions.
		Symbol indicates a $\frac{1}{2}$-inch fillet weld on *arrow side* of the joint and a $\frac{1}{4}$-inch fillet weld on *far side* of the joint.
		Symbol indicates a fillet weld on *arrow side* of joint with $\frac{1}{4}$- and $\frac{1}{2}$-inch legs. Orientation of legs must be shown on drawing.

Copyright 2004, Industrial Press, Inc., New York, NY

Application of AmercanNational StandardWelding Symbols *(Continued)*

Desired Weld	Symbol	Symbol Meaning
		Symbol indicates a 24-inch long fillet weld on the *arrow side* of the joint.
Locate Welds at Ends of Joint 		Symbol indicates a series of intermittent fillet welds each 2 inches long and spaced 5 inches apart on centers directly opposite each other on both sides of the joint.
Locate Welds at Ends of Joint 		Symbol indicates a series of intermittent fillet welds each 3 inches long and spaced 10 inches apart on centers. The centers of the welds on one side of the joint are displaced from those on the other.
		Symbol indicates a fillet weld around the perimeter of the member.
		Symbol indicates a $\frac{1}{4}$-inch V-groove weld with a $\frac{1}{8}$-inch root penetration.
		Symbol indicates a $\frac{1}{4}$-inch bevel weld with a $\frac{5}{16}$-inch root penetration plus a subsequent $\frac{3}{8}$-inch fillet weld.

Copyright 2004, Industrial Press, Inc., New York, NY

Application of AmercanNational StandardWelding Symbols *(Continued)*

Desired Weld	Symbol	Symbol Meaning
		Symbol indicates a bevel weld with a root opening of $\frac{3}{16}$ inch.
		Symbol indicates a V-groove weld with a groove angle of 65 degrees on the *arrow side* and 90 degrees on the *other side*.
		Symbol indicates a flush surface with the reinforcement removed by chipping on the *other side* of the joint and a smooth grind on the *arrow side*. The symbols *C* and *G* should be the user's standard finish symbols.
		Symbol indicates a 2-inch U-groove weld with a 25-degree groove angle and no root opening for both sides of the joint.
		Symbol indicates plug welds of 1-inch diameter, a depth of filling of $\frac{1}{2}$ inch and a 60-degree angle of countersink spaced 6 inches apart on centers.
Preparation 		Symbol indicates all-around bevel and square-groove weld of these studs.

Copyright 2004, Industrial Press, Inc., New York, NY

Application of AmercanNational StandardWelding Symbols *(Continued)*

Desired Weld	Symbol	Symbol Meaning
Min. Acceptable Shear Strength 200 lb/lin. in. 		Symbol indicates an electron beam seam weld with a minimum acceptable joint strength of 200 pounds per lineal inch.
		Symbol indicates four 0.10-inch diameter electron beam spot welds located at random.
		Symbol indicates a fillet weld on the *other side* of joint and a flare-bevel-groove weld and a fillet weld on the *arrow side* of the joint.
		Symbol indicates gas tungsten-arc seam weld on *arrow side* of joint.
		Symbol indicates edge-flange weld on *arrow side* of joint and flare-V-groove weld on *other side* of joint.
		Symbol indicates melt-thru weld. By convention, this symbol is placed on the opposite side of the reference line from the corner-flange symbol.

Copyright 2004, Industrial Press, Inc., New York, NY

Nondestructive Testing

Nondestructive testing (NDT) is aimed at examination of a component or assembly, usually for surface or internal cracks or other nonhomogeneities, to determine the structure, or to measure thickness, by some means that will not impair its use for the intended purpose. Traditional methods include use of radiography, ultrasonic vibration, dye penetrants, magnetic particles, acoustic emission, leakage, and eddy currents. These methods are simple to use but some thought needs to be given to their application and to interpretation of the results. Space limitations preclude a full discussion of NDT here, but the nature of the welding process makes these methods particularly useful, so some information on use of NDT for testing welds is given below.

Nondestructive Testing Symbol Application.— The application of nondestructive testing symbols is also covered in American National Standard ANSI/AWS A2.4-79.

Basic Testing Symbols: These are shown in the following table.

ANSI Basic Symbols for Nondestructive Testing *ANSI/AWS A2.4-79*

Symbol	Type of Test	Symbol	Type of Test
AET	Acoustic Emission	PT	Penetrant
ET	Eddy Current	PRT	Proof
LT	Leak	RT	Radiographic
MT	Magnetic Particle	UT	Ultrasonic
NRT	Neutron Radiographic	VT	Visual

Testing Symbol Elements: The testing symbol consists of the following elements: Reference Line, Arrow, Basic Testing Symbol, Test-all-around Symbol, (N) Number of Tests, Test in Field, Tail, and Specification or other reference.

The standard location of the testing symbol elements are shown in the following figure.



Locations of Testing Symbol Elements

The arrow connects the reference line to the part to be tested. The side of the part to which the arrow points is considered to be the *arrow side*. The side opposite the arrow side is considered to be the *other side*.

Location of Testing Symbol: Tests to be made on the arrow side of the part are indicated by the basic testing symbol on the side of the reference line toward the reader.

Copyright 2004, Industrial Press, Inc., New York, NY

Tests to be made on the other side of the part are indicated by the basic testing symbol on the side of the reference line away from the reader.

To specify where only a certain length of a section is to be considered, the actual length or percentage of length to be tested is shown to the right of the basic test symbol. To specify the number of tests to be taken on a joint or part, the number of tests is shown in parentheses.

Tests to be made on both sides of the part are indicated by test symbols on both sides of the reference line. Where nondestructive symbols have no arrow or other significance, the testing symbols are centered in the reference line.

Combination of Symbols: Nondestructive basic testing symbols may be combined and nondestructive and welding symbols may be combined.

Direction of Radiation: When specified, the direction of radiation may be shown in conjunction with the radiographic or neutron radiographic basic testing symbols by means of a radiation symbol located on the drawing at the desired angle.



Tests Made All Around the Joint: To specify tests to be made all around a joint a circular test-all-around symbol is used.

Areas of Revolution: For nondestructive testing of areas of revolution, the area is indicated by the test-all-around symbol and appropriate dimensions.

Plane Areas: The area to be examined is enclosed by straight broken lines having a small circle around the angle apex at each change in direction.

Copyright 2004, Industrial Press, Inc., New York, NY

LASERS

Introduction

Lasers are used for cutting, welding, drilling, surface treatment, and marking. The word laser stands for Light Amplification by Stimulated Emission of Radiation, and a laser is a unit that produces optical-frequency radiation in intense, controllable quantities of energy. When directed against the surface of a material, this quantity of energy is high enough to cause a localized effect. Heating by a laser is controlled to produce only the desired result in a specific area, ensuring low part distortion.

The four basic components of a laser, shown in Fig. 1, are an amplifying medium, a means to excite this medium, mirrors arranged to form an optical resonator, and an output transmission device to cause beam energy to exit from the laser. The laser output wavelength is controlled by the type of amplifying medium used. The most efficient industrial lasers use optical excitation or electrical discharge to stimulate the medium and start the lasing action.

Solid-state lasers, in which the medium is a solid crystal of an optically pure material such as glass or yttrium aluminum garnet (YAG) doped with neodymium (Nd), are excited by a burst of light from a flashlamp(s) arranged in a reflective cavity that acts to concentrate the excitation energy into the crystal. Neodymium lasers emit radiation at 1.06 μm (1 μm = 0.00004 in.), in the near infrared portion of the spectrum.

The carbon dioxide (CO_2) laser uses a gaseous mixture of helium, nitrogen, and carbon dioxide. The gas molecules are energized by an electric discharge between strategically placed cathodes and anodes. The light produced by CO_2 lasers has a wavelength of approximately 10.6 μm.

Laser Light.— The characteristics of light emitted from a laser are determined by the medium and the design of the optical resonator. Photons traveling parallel to the optical axis are amplified and the design provides for a certain portion of this light energy to be transmitted from the resonator. This amplifier/resonator action determines the wavelength and spatial distribution of the laser light.

The transmitted laser light beam is monochromatic (one color) and coherent (parallel rays), with low divergence and high brightness, characteristics that distinguish coherent laser light from ordinary incoherent light and set the laser apart as a beam source with high energy density. A typical industrial laser operating in a very narrow wavelength band determined by the laser medium is called monochromatic because it emits light in a specific segment of the optical spectrum. The wavelength is important for beam focusing and material absorption effects.

Coherent laser light can be 100,000 times higher in energy density than equivalent-power incoherent light. The most important aspect of coherent light for industrial laser applications is directionality. which reduces dispersion of energy as the beam is directed over comparatively long distances to the workpiece.

Laser Beams.— The slight tendency of a laser beam to expand in diameter as it moves away from its source is called beam divergence, and is important in determining the size of the spot where it is focused on the work surface. The beam-divergence angle for high-power lasers used in processing industrial materials is larger than the diffraction-limited value because the divergence angle tends to increasewith increasing laser output power. The amount of divergence thus is a major factor in concentration of energy in the work.

The power emitted per unit area per unit solid angle is called brightness. Because the laser can produce very high levels of power in very narrowly collimated beams, it is a source of high brightness energy. This brightness factor is a major characteristic of solid-state lasers. Other important beam characteristics in industrial lasers include spatial mode and depth of focus. Ideally, the output beam of the laser selected should have a mode structure, divergence, and wavelength sufficient to process the application in optimum time and

Copyright 2004, Industrial Press, Inc., New York, NY

with a minimum of heat input. A beam-quality factor, M^2, is commonly used to define the productive performance of a laser. This factor is a measure of the ratio between the spot diameter of a given laser to that of a theoretically perfect beam. Beam quality is expressed as "times diffraction" and is always greater than 1. For CO_2 lasers at the 1-kW level, M^2 = 1.5, and for YAG lasers at 500 W, M^2 = 12.0 is typical.

The mode of a laser beam is described by the power distribution profile over its cross-section. Called transverse modes, these profiles are represented by the term TEM_{mn}, where TEM stands for transverse electromagnetic, and *m* and *n* are small integers indicating that power distribution is bell-shaped (Gaussian) TEM_{00}, or donut-shaped TEM_{01}*.



Fig. 1. Basic Components of a Laser



Fig. 2. Spatial Intensity Distribution in Laser Beams

Fig. 2 shows various transverse electromagnetic modes commonly used in materials processing applications. For such applications, it is helpful to determine the peak and total power generated by the laser. Diffraction in Gaussian beams is inherently limited and other modes of operation may have larger beam-divergence angles, causing less power to be delivered to the workpiece. The selection process for industrial applications should consider only those lasers that produce the lowest-order mode beam, in a Gaussian-shaped energy profile (see Fig. 2), with a narrow beam divergence. Solid-state lasers do not meet all these criteria, and with high-power CO_2 lasers, it is sometimes necessary to compromise because of reduced output power, large physical size, and complexity of the laser design.

Although a laser with a TEM_{00} output beam is preferred for optimum performance, the application may not always require such a beam. For example, many CO_2 laser cutting operations are performed with a TEM_{01}* beam and welding is often done with a mixture of each of these modes. Lasers can be operated in three temporal modes, continuous wave (CW), pulsed, and superpulsed (called Q-switched for YAG lasers), depending on the materials being processed.

The smallest focused spot diameter that will provide the highest energy intensity can be produced by a TEM_{00} laser. The fundamental mode output of CO_2 lasers is limited to 2500 watts. Complex spatial patterns are often caused by inhomogeneities in solid-state laser crystals and are controlled by insertion of apertures that greatly reduce output power. However, standard lasers suit the needs of most industrial users as beam divergence is only one factor in laser design.

Beam Focusing.— The diameter of a focused laser beam spot can be estimated by multiplying the published beam divergence value by the focal length of the lensor by the relationship of the wavelength to the unfocused beam diameter. Thus, the beam from a CO_2

Copyright 2004, Industrial Press, Inc., New York, NY

laser operating at a 10.6-μm wavelength, using the same focal length lens, will produce a focused spot ten times larger than the beam from a Nd:YAG laser operating at a 1.06-μm wavelength.



Spot Diameter, $d = f\theta = 4\lambda F/\pi D$

Power Density, $H = 4P/d^2$

Depth of Focus, $Z = \pm d^2/4\pi$

Fig. 3. Focus Characteristics of a Laser Beam.



Fig. 4. Typical Laser Systems.

Effects of various beam spot sizes and depths of focus are shown in Fig. 3. High-power density is required for most focused beam applications such as cutting, welding, drilling, and scribing, so these applications generally require a tightly focused beam. The peak power density of a Gaussian beam is found by dividing the power at the workpiece by the area of the focused spot. Power density varies with the square of the area, so that a change in the focused spot size can influence power density by a factor of 4 and careful attention must be given to maintaining beam focus.

Another factor of concern in laser processing is depth of focus, defined as the range of depth over which the focused spot varies by ±5 per cent. This relationship is extremely important in cutting sheet metal, where it is affected by variations in surface flatness. Cutting heads that adapt automatically to maintain constant surface-to-nozzle spacing are used to reduce this effect.

Types of Industrial Lasers.— Specific types of lasers are suited to specific applications, and Fig. 1 lists the most common lasers used in processing typical industrial materials. Solid-state lasers are typically used for drilling, cutting, spot and seam welding, and marking on thin sheet metal. CO_2 lasers are used to weld, cut, surface treat, and mark both metals and nonmetals. For example, CO_2 lasers are suited to ceramic scribing and Nd:YAG lasers for drilling turbine blades. Factors that affect suitability include wavelength, power density, and spot size. Some applications can use more than one laser type. Cutting sheet metal, an established kilowatt-level CO_2 laser application, can also be done with kilowatt-level Nd:YAG lasers. For some on-line applications that require multiaxis beam motion, the Nd:YAG laser may have advantages in close coupling the laser beam to the workpiece through fiber optics.

Table 1. Common Industrial Laser Applications

Type	Wavelength (μm)	Operating Mode	Power Range (watts)	Applications
Nd:YAG	1.06	Pulsed	10–2,000	A, B, D, E, F
Nd: YAG	1.06	Continuous	500–3,000	A, B, C
Nd: YAG	1.06	Q-switched	5–150	D, E, F
CO_2	10.6	Pulsed	5–3,000	A, B, D, E
CO_2	10.6	Superpulsed	1,000–5,000	A
CO_2	10.6	Continuous	100–25,000	A, B, C

Applications: A = cutting, B = welding, C = surface treatment, D =drilling, E = marking, F = micromachining.

Industrial Laser Systems.— The laser should be located as close as possible to the workpiece to minimize beam-handling problems. Ability to locate the beam source away from

Copyright 2004, Industrial Press, Inc., New York, NY

its power supply and ancillary equipment, and to arrange the beam source at an angle to the workpiece allows the laser to be used in many automatic and numerically controlled set ups. Fig. 4 shows typical laser system arrangements.

Lasers require power supplies and controllers for lasers are usually housed in industrial grade enclosures suited to factory floor conditions. Because the laser is a relatively inefficient converter of electrical energy to electromagnetic energy (light), the waste heat from the beam source must be removed by heat exchangers located away from the processing area. Flowing gas CO_2 lasers require a source of laser gas, used to make up any volume lost in the normal recycling process. Gas can be supplied from closely linked tanks or piped from remote bulk storage.

Delivery of a high-quality beam from the laser to the workpiece often requires subsystems that change the beam path by optical means or cause the beam to be directed along two or more axes. Five-axis beam motion systems, for example, using multiple optical elements to move the beam in X, Y, Z, and rotation/tilt, are available.

Solid-state laser beams can be transmitted through flexible optical fibers. If there is no beam motion, the workpiece must be moved. The motion systems used can be as simple as an XY or rotary table, or as complex as a multistation, dual-feed table. Hybrid systems offer a combination of beam and workpiece motion and are frequently used in multiaxis cutting applications. All motions are controlled by an auxiliary unit such as a CNC, NC, paper tape, or programmable controller. Newer types of controllers interface with the beam source to control the entire process. Gas jet nozzles, wire feed, or seam tracking equipment are often used, and processing may be monitored and controlled by signals from height sensors, ionized by-product (plasma) detectors, and other systems.

Safety.— Safety for lasers is covered in ANSI Z136.1-2000: Safe Use Of Lasers. Most industrial lasers require substantial electrical input at high-voltage and -amperage conditions. Design of the beam source and the associated power supply should be to accepted industry electrical standards. Protective shielding is advised where an operator could interact, physically, with the laser beam, and would be similar to safety shields provided on other industrial equipment.

Radiation from a laser is intense light concentrated in tight bundles of energy. The high energy density and selective absorption characteristics of the laser beam have the potential to cause serious damage to the eye. For this reason, direct viewing of the beam from the laser should be restricted. Safety eyewear is commercially available to provide protection for each type of laser used. Certain lasers, such as the 1.06-μm solid-state units, should be arranged in a system such that workers are shielded from direct and indirect radiation. Other types of lasers, such as the 10.6-μm CO_2 laser, when operated without shielding, should meet industry standards for maximum permissible exposure levels. Much information is published on laser radiation safety, so that the subject is highly documented. Laser suppliers are very familiar with local regulations and are a good source for prepurchase information. Certain materials, notably many plastics compositions, when vaporized, will produce potentially harmful fumes.Precautionary measures such as workstation exhaust systems typically handle this problem.

Laser Beam/Material Interaction.— Industrial lasers fall into categories of effectiveness because the absorption of laser light by industrial materials depends on the specific wavelength. However, at room temperature, CO_2 laser light at 10.6 μm wavelength is fully absorbed by most organic and inorganic nonmetals.

Both CO_2 and YAG can be used in metalworking applications, although YAG laser light at 1.06 μm is absorbed to a higher degree in metals. Compensation for the lower absorption of CO: light by metals is afforded by high-energy-density beams, which create small amounts of surface temperature change that tend to increase the beam-coupling coefficient.

Copyright 2004, Industrial Press, Inc., New York, NY

At CO_2 power densities in excess of 10^6 W/cm^2, effective absorptivity in metals approaches that of nonmetals. Above certain temperatures, metals will absorb more infrared energy. In steel at 400°C, for instance, the absorption rate is increased by 50 per cent. In broad-area beam processing, where the energy density (10^4 W/cm^2) is low, some form of surface coating may be required to couple the beam energy into a metal surface.



Fig. 5. Laser Energy Absorption Intensity vs. Temperature



Fig. 6. Factors in Laser Cutting.

Thermal Properties of Workpieces.— When a laser beam is coupled to a workpiece, initial conversion of energy to work, in the form of heat, is confined to a very thin layer (100-200 Ångstroms) of surface material. The absorbed energy converted to heat will change the physical state of the workpiece, and depending on the energy intensity of the beam, a material will heat, melt, or vaporize. Fig. 5 shows percentage of energy absorption versus temperature for various phase changes in materials.

Heating, melting, and vaporization of a material by laser radiation depends on the thermal conductivity and specific heat of the material. The heating rate is inversely proportional to the specific heat per unit volume, so that the important factor for heat flow is the thermal diffusivity of the work material. This value determines how rapidly a material will accept and conduct thermal energy, and a high thermal diffusivity will allow a greater depth of fusion penetration with less risk of thermal cracking.

Heat produced by a laser in surface layers is rapidly quenched into the material and the complementary cooling rate is also rapid. In some metals, the rate is 10^6 C°/s. This rapid cooling results in minimum residual heat effects, due to the slower thermal diffusivity of heat spreading from the processed area. However, rapid cooling may produce undesired effects in some metals. Cooling that is too rapid prevents chemical mixing and may result in brittle welds.

Thermosetting plastics are specifically sensitive to reheating, which may produce a gummy appearance or a charred, ashlike residue. Generally, the sensitivity of a material to heat from a laser is as apparent as with any other localized heating process. Any literature describing the behavior of materials when exposed to heat will apply to laser processing.

Cutting Metal with Lasers

The energy in a laser beam is absorbed by the surface of the impinged material, and the energy is converted into work in the form of heat, which raises the temperature to the melting or vaporization point. A jet of gas is arranged to expel excess molten metal and vapor from the molten area. Moving the resulting molten-walled hole along a path with continuous or rapidly pulsed beam power produces a cut. The width of this cut (kerf), the quality of

Copyright 2004, Industrial Press, Inc., New York, NY

the cut edges, and the appearance of the underside of the cut (where the dross collects) are determined by choice of laser, beam quality, delivered power, and type of motion employed (beam, workpiece, or combination). Fig. 6 identifies the factors involved in producing a high-quality cut.

Power versus penetration and cutting rate are essentially straight-line functions for most ferrous metals cut with lasers. A simple relationship states that process depth is proportional to power and inversely proportional to speed. Thus, for example, doubling power will double penetration depth. The maximum possible thickness that can be cut is, therefore, a function of power, cutting rate, and compromise on cut quality. Currently, 25 mm (1 in.) is considered the maximum thickness of steel alloys that can be cut. The most economically efficient range of thicknesses is up to 12.5 mm (0.49 in.).

Metals reflect laser light at increasing percentages with increasing wavelength. The high-energy densities generated by high-power CO_2 lasers overcome these reflectivity effects. Shorter-wavelength lasers such as Nd:YAG do not suffer these problems because more of their beam energy is absorbed.

Beam Assistance Techniques.— In cutting ferrous alloys, a jet of oxygen concentric with the laser beam is directed against the heated surface of the metal. The heat of the molten puddle of steel produced by the laser power causes the oxygen to combine with the metal, so that the jet burns through the entire thickness of the steel. This melt ablation process also uses the gas pressure to eject the molten metal from the cut kerf. Control of the gas pressure, shape of the gas stream, and positioning of the gas nozzle orifice above the metal surface are critical factors. A typical gas jet nozzle is shown in Fig. 7. Cutting highly alloyed steels, such as stainless steel, is done with pulsed CO_2 laser beams. High-pressure gas jets with the nozzle on the surface of the metal and nonoxidizing gas assistance can be used to minimize or eliminate clinging dross.



Fig. 7. Laser Gas Cutting Nozzle for Steel.

The narrow kerf produced by the laser allows cut patterns to be nested as close as one beam diameter apart, and sharply contoured and profiled cuts can be made, even in narrow angle locations. For this type of work and for other reasons, confining the kerf width to a dimension equal to, or slightly greater than, the diameter of the laser beam is important. Kerf width is a function of beam quality, focus, focus position, gas pressure, gas nozzle to surface spacing, and processing rate. Table 2 shows typical kerf widths.

Cut Edge Roughness.— Cutting with a continuous-wave (CW) output CO_2 laser can produce surface roughness values of 8–15 μm (315–590 μin) in 1.6-mm (0.063-in) cold-rolled steel and 30-35 μm (1180–1380 μin) in mild steel. Surface roughness of 30–50 μm (1180–1970 μin) in thin-gage stainless steel sheets is routine when using oxygen to assist cutting. Table 3 lists some surface roughness values.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Typical Kerf Widths in CO_2 Laser Cutting

Material	Thickness		Kerf	
	mm	in.	mm	in.
Carbon Steel	1.5	0.06	0.05	0.002
	2.25	0.09	0.12	0.005
	3.12	0.12	0.2	0.008
	6.25	0.25	0.3	0.012
Aluminum	2.25	0.09	0.25	0.01
Plastics	<4.0	<0.16	2 × beam diameter	

Table 3. Surface Roughness Values for Laser Cutting with Oxygen

Material	Thickness		Surface Finish	
	mm	in.	μm	μin
Stainless Steel	1	0.04	30	1200
	2	0.08	35	1400
	3	0.12	50	2000
Cold-Rolled Steel	1	0.04	8	320
	2	0.08	10	400
	3	0.12	15	600
Mild Steel	1	0.04	30	1200
	2	0.08	30	1200
	3	0.12	35	1400

Heat-Affected Zones.— Control of beam focus, focus position, assist gas conditions, and processing rates produces differences in hardness that are barely discernible in steels up to 2 mm (0.078 in.) thick. Small increases in hardness to a depth of 0.1–0.2 mm (0.004–0.008 in.) are common. Cutting with a pulsed CO_2 laser reduces these values to less than 0.1 mm (0.004 in.), making this mode of operation beneficial for some end-use applications. Table 4 shows typical values for the heat-affected zone in mild steels.

Table 4. Heat-Affected Zone in Mild Steels

Material Thickness		CW HAZ		Pulsed HAZ	
mm	in.	mm	in.	mm	in.
4	0.157	0.50	0.020	0.15	0.006
3	0.118	0.37	0.015	0.15	0.006
2	0.078	0.10	0.004	0.12	0.005
1	0.039	0.75	0.030	0.07	0.003

Rates for laser cutting of metals are typically reported as data developed under ideal conditions, that is, in a controlled development laboratory environment using technician-operated equipment. Rates achieved on the shop floor using semiskilled system operators to produce complicated shapes may vary dramatically from published data. Speed versus thickness for cutting steel is shown in Fig. 8 for 1000- and 1500-W power levels, and cutting performance for several other metals of various thicknesses is shown in Table 5. Cutting rate data for pulsed and CW Nd:YAG lasers for steel also are shown in Fig. 8, and for Nd:YAG cutting of other metals in Table 5.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. CO_2 and Nd: YAG Cutting Speeds for Nonferrous Metals

Material	CO_2 (1500 watts)				Nd: YAG				
	Thickness		Speed		Thickness		Speed		Power
	mm	in.	m/min	ft/min	mm	in.	m/min	ft/min	watts
Copper	1	0.04	2.25	7.4	…		…		…
	2	0.08	0.75	2.5	…		…		…
	3	0.12	0.35	1.15	…		…		…
Aluminum	1	0.04	8	26.2	1.5	0.06	2.5	8.2	1000
	2	0.08	4	13.1	2.5	0.1	1.0	3.3	1000
	3	0.12	1.5	4.9	3.5	0.14	0.5	1.6	1000
Titanium	1	0.04	6	19.7	0.4	0.016	1.0	3.3	150
	2	0.08	3	9.8	…		…		…
Tungsten	…		…		0.08	0.003	0.03	0.1	250
Brass	1	0.04	3	9.8	…		…		…
	2	0.08	1.5	4.9	…		…		…
Hastalloy	2.5	0.1	2.8	9.2	…		…		…
Hastalloy X	…		…		0.08	0.003	0.5	1.6	150
Inconel 718	4	0.16	1.1	3.6	…		…		…



Fig. 8. Typical Cutting Rates for CO_2 and YAG Lasers.

Cutting of Nonmetals.— Laser cutting of nonmetals has three requirements: a focused beam of energy at a wavelength that will be absorbed easily by the material so that melting or vaporization can occur; a concentric jet of gas, usually compressed air, to remove the by-products from the cut area; and a means to generate cuts in straight or curved outlines. Residual thermal effects resulting from the process present a greater problem than in cutting of metals and limit applications of lasers in nonmetal processing.

When subjected to a laser beam, paper, wood, and other cellular materials undergo vaporization caused by combustion. The cutting speed depends on laser power, material thickness, and water and air content of the material. Thermoplastic polymer materials are cut by melting and gas jet expulsion of the melted material from the cut area. The cutting speed is governed by laser power, material thickness, and pressure of gas used to eject the displaced material.

Polymers that may be cut by combustion or chemical degradation include the thermosetting plastics, for example, epoxies and phenolics. Cutting speed is determined by the laser

Copyright 2004, Industrial Press, Inc., New York, NY

power and is higher for thermosets than for other polymers due to the phase change to vapor.

Composite materials are generally easy to cut, but the resulting cut may not be of the highest quality, depending on the heat sensitivity of the composite materials. High-pressure cutting processes such as fluid jets have proven to be more effective than lasers for cutting many composite materials.

Nonmetal cutting processes require moderate amounts of power, so the only limitation on cut thickness is the quality of the cut. In practice, the majority of cutting applications are to materials less than 12 mm thick. Cutting rates for some commonly used nonmetals are shown in Table 6. Nonmetal cutting applications require a gas jet to remove molten, vaporized, or chemically degraded matter from the cut area.

Compressed air is used for many plastics cutting applications because it is widely available and cheap to produce, so it is a small cost factor in nonmetal cutting. A narrow kerf is a feature of nonmetal cutting, and it is especially important in the cutting of compactly nested parts such as those produced in cutting of fabrics. Nonmetals react in a variety of ways to laser-generated heat, so that it is difficult to generalize on edge roughness, but thermally sensitive materials will usually show edge effects.

Table 6. CO_2 Laser Cutting Rates for Nonmetals

	Thickness		Speed		Power		Thickness		Speed		Power
Material	mm	in	m/min	ft/min	watts	Material	mm	in	m/min	ft/min	watts
Polythene	1	0.04	11	36	500	Fiberglass	1.6	0.063	5.2	17	450
Polypropylene	1	0.04	17	56	500	Glass	1	0.04	1.5	4.9	500
Polystyrene	1	0.04	19	62	500	Alumina	1	0.04	1.4	4.6	500
Nylon	1	0.04	20	66	500	Hardwood	10	0.39	2.6	8.5	500
ABS	1	0.04	21	69	500	Plywood	12	0.47	4.8	15.7	1000
Polycarbonate	1	0.04	21	69	500	Cardboard	4.6	0.18	9.0	29.5	350
PVC	1	0.04	28	92	500						

Welding with Lasers

Laser Welding Theory.— Conversion of absorbed laser energy into heat causes metals to undergo a phase change from solid to liquid and, as energy is removed, back to solid. This fusion welding process is used to produce selective area spot welds or linear continuous seam welds. The two types of laser welding processes, conduction and deep penetration, or keyhole, are shown in Fig. 9.

Conduction welding: relies on the thermal diffusivity characteristics of the metal to conduct heat into the joint area. By concentrating heat into the focused beam diameter and programming this heat input for short time periods, more heat is conducted into the joint than is radiated outward from the joint. Conduction welds are generally used for spot welding and partial penetration seam welding.

Deep penetration keyhole welding: is produced by beam energy converted to heat that causes a hole to be produced through the thickness of the metal. Vapor pressure of evaporated metal holds a layer of molten metal in place against the hole wall.

Movement of the hole, by beam or workpiece motion, causes the molten metal to flow around the hole and solidify behind the beam interaction point. The resolidified metal has a different structure than the base metal. Maximum practical penetration limits are approximately 25 mm (2 in.) with today's available laser power technology.

If the physical change from solid to liquid to solid does not produce a ductile fusion zone, and if the brittleness of the resolidified metal cannot be reduced easily by postweld annealing, then the laser welding process, as with other fusion welding processes, may not be viable. If the metal-to-metal combination does not produce an effective weld, other

Copyright 2004, Industrial Press, Inc., New York, NY

considerations such as filler metal additions to modify fusion zone chemistry should be considered.



Fig. 9. Types of Laser Welds.

Welded Joint Design.— For optimum results, the edges of parts to be laser beam welded should be in close contact. When a part is being designed and there is a choice of welding process, designers should design joints and joint tolerances to the optimum for laser welding. Fig. 10 shows suitable joint designs for the laser fusion welding process. Joint tolerances are one of the more important parameters influencing part weldability, and for corner, tee, and lap joints, gaps should be not more than 25 per cent of the thickness of the thinnest section. For butt and edge joints, the percentage is reduced to 10. Addition of filler metal to compensate for large joint gaps is becoming popular.



Fig. 10. Examples of Laser Weld Joint Designs.

Welding Rates.— The information presented in Fig. 11 for welding with CO_2 and Nd:YAG lasers should be considered as typical for the specific lasers shown and is for use in optimum conditions. These data are provided only as guidelines.

Processing Gas.— The proper choice of processing gas is important for both conduction and keyhole welding. Gases that ionize easily should not be used to shield the beam/material interaction point. Energy intensities of 10^6 W/cm^2 or higher can occur in the zone where incident and reflected laser light overlap and gases can vaporize, producing a plasma that attenuates further beam transmission.

One of the most important advantages of laser welding is the low total heat input characteristic of the focused high-energy density beam. Heat concentration resulting from the beam energy conversion at the workpiece surface causes most conduction to be perpendicular to the direction of motion. With the beam (or workpiece) moving faster than the speed of thermal conduction, there is significant heat flow only in the perpendicular direction. Thus, material solid to solid, or solid to liquid, changes tend to occur only in the narrow

Copyright 2004, Industrial Press, Inc., New York, NY

path of heat conduction, and the amount of heat necessary to penetrate a given material thickness is reduced to only that needed to fuse the joint. With limited excess heat through the low total heat mechanism, parts can be produced by laser welding with minimum thermal distortion.

Helium is the ideal gas for laser welding, but other gases such as CO_2 and argon have been used. Neither CO_2 nor argon produces a clean, perfectly smooth weld, but weld integrity seems sufficient to suggest them as alternatives. The cost of welding assistance gas can be greater than for laser gases in CO_2 laser welding and may be a significant factor in manufacturing cost per welded part.



Fig. 11. Rates for CO_2 and Nd:YAG Laser Welding.

Drilling with Lasers

Laser Drilling Theory.— Laser drilling is performed by direct, percussive, and trepanning methods that produce holes of increasing quality respectively, using increasingly more sophisticated equipment. The drilling process occurs when the localized heating of the material by a focused laser beam raises the surface temperature above the melting temperature for metal or, for nonmetals, above the vaporization temperature.

Direct Drilling.— The single-pulse, single-hole process is called direct drilling. The process hole size is determined by the thermal characteristics of the material, the beam spot size, the power density, the beam quality, and the focus location. Of these parameters, beam quality, in terms of beam divergence, is an important criterion because of its effect on the hole size. Single-pulse drilled holes are usually limited to a depth of 1.5 mm (0.06 in.) in metals and up to 8 mm (0.315 in.) in nonmetals. Maximum hole diameter for pulsed solid-state laser metal drilling is in the 0.5-to 0.75-mm (0.02- to 0.03-in) range, and CO_2 direct drilling can produce holes up to 1.0 mm (0.04 in.) in diameter. The aspect ratio (depth to midhole diameter) is typically under 10:1 in metals and for many nonmetals it can be 15:1. Hole taper is usually present in direct drilling of metals. The amount of taper (entrance hole to exit hole diameter change) can be as much as 25 per cent in many metals. Direct drilling produces a recast layer with a depth of about 0.1 mm (0.004 in.). Diameter tolerances are ±10 per cent for the entrance hole, depending on beam quality and assist gas pressure.

Percussive Drilling.— Firing a rapid sequence of pulses produces a hole of higher quality than direct drilling in metal thicknesses up to 25 mm (1 in.). This process is known as percussive drilling. Multiple pulses may be necessary, depending on the metal thickness. Typical results using percussion drilled holes are: maximum depth achievable, 25 mm (1 in.); maximum hole diameter, 1.5 mm (0.06 in.); aspect ratio, 50:1; recast layer, 0.5 mm (0.02 in.); taper under 10 per cent; and hole diameter tolerance ±5 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Trepanning.— To improve hole quality, some companies use the trepanning method to cut a hole. In this process, a focused beam is moved around the circumference of the hole to be drilled by a rotating mirror assembly. The closeness of spacing of the beam pulses that need to be overlapped to produce the hole depends on the quality requirements. Typical results are: maximum hole depth, 10 mm (0.39 in.); maximum hole diameter, 2.5 mm (0.1 in.); and recast layer thickness, 25 μm (985 μin).

Drilling Rates.— Laser drilling is a fast process but is very dependent on the above-mentioned process factors. It is difficult to generalize on laser drilling rates because of the large number of combinations of material, hole diameter, depth, number of holes per part, and part throughput. With Nd:YAG lasers, direct drilling rates of 1 ms are typical.

Heat Treatment with Lasers

The defocused beam from a CO_2 laser impinging on a metal surface at room temperature will have 90 per cent or more of its power reflected. In steels, the value is about 93 per cent. Compared with focused beam processing, which uses power densities greater than 10^5 W/cm^2, the power density of laser beams designed for heat treatment, at less than 10^4 W/cm^2, is insufficient to overcome reflectivity effects. Therefore, the metal surface needs to be prepared by one of several processes that will enhance absorption characteristics. Surface roughening can be used to produce tiny craters that can trap portions of the beam long enough to raise the surface temperature to a point where more beam energy is absorbed. Coating the metal surface is a common expedient. Black enamel paint is easy to apply and the laser beam causes the enamel to vaporize, leaving a clean surface.

The absorbed laser beam energy, converted to heat, raises the temperature of the metal in the beam pattern for as long as the beam remains in one place. The length of the dwell time is used to control the depth of the heat treatment and is an extremely effective means for control of case depth in hardening.

Materials Applicability.— Hardenable ferrous metals, such as medium- and high-carbon steels, tool steels, low-alloy steels and cast irons, and steels with fine-carbide dispersion, are good candidates for laser heat treating. Marginally hardenable metals include annealed carbon steels, spheroidized carbon steels, mild-carbon steels (0.2 per cent C), and ferritic nodular cast irons. Low-carbon steels (<0.1 per cent C), austenitic stainless steels, and nonferrous alloys and metals are not hardenable.

The effect of the metal microstructure on depth of hardening is an important factor. Cast iron, with a graphite and tempered martensite structure, presents a low carbon-diffusion distance that favors deep-hardened cases. The same is true for steel with a tempered martensite or bainite structure. On the other hand, cast iron with a graphite/ferrite structure and spheroidized iron (Fe_3C plus ferrite) structures have large carbon-diffusion patterns and therefore produce very shallow or no case depths.

Hardening Rates.— Laser hardening is typically slower than conventional techniques such as induction heating. However, by limiting the area to be hardened, the laser can prove to be cost-effective through the elimination of residual heat effects that cause part distortion. A typical hardening rate is 130 cm^2/min. (20 in^2/min.) for a 1-mm (0.039-in) case depth in 4140 steel.

Cladding with Lasers

In laser cladding, for applying a coating of a hard metal to a softer alloy, for instance, a shaped or defocused laser beam is used to heat either preplaced or gravity-fed powdered alloys. The cladding alloy melts and flows across the surface of the substrate, rapidly solidifying when laser power is removed. Control of laser power, beam or part travel speed, clad thickness, substrate thickness, powder feed rate, and shielding gas are process variables that are determined for each part.

Copyright 2004, Industrial Press, Inc., New York, NY

Many of the alloys currently used in plasma arc or metal inert gas cladding techniques can be used with the laser cladding process. Among these materials, Stellites, Colmonoys, and other alloys containing carbides are included, plus Inconel, Triballoy, Fe-Cr-C-X alloys, and tungsten and titanium carbides.

Controlled minimal dilution may be the key technical advantage of the laser cladding process. Dilution is defined as the total volume of the surface layer contributed by melting of the substrate, and it increases with increasing power, but decreases with either increasing travel speed or increasing beam width transverse to the direction of travel. Tests comparing laser dilution to other cladding techniques show the laser at <2 per cent compared to 5–15 per cent for plasma arc and 20–25 per cent for stick electrode processes.

The laser cladding process results in a dense, homogenous, nonporous clad layer that is metallurgically bonded to the substrate. These qualities are in contrast to the mechanically bonded, more porous layer produced by other methods.

Marking with Lasers

Laser marking technology can be divided into two groups; those that produce a repetitive mark are listed as mask marking, and those that involve rapid changes of mark characteristics are classified as scanned beam marking. The amount of data that can be marked in a unit of time (writing speed) depends on laser energy density, galvanometer speed, computer control, and the dimensions of the mark. Heat-type marks have been made at rates up to 2500 mm/s (100 in/s) and engraved marks at rates of 500–800 mm/s (20–30 in/s). Writing fields are of various sizes, but a typical field measures 100 × 100 mm (4 × 4 in.).

Mask Marking.— In mask marking, the beam from a CO_2 laser is projected through a reflective mask that passes beam energy only through uncoated areas. The beam energy is reimaged by a wide field lens onto the material's surface where the absorbed heat changes the molecular structure of the material to produce a visible mark. Examples are clouding PVC or acrylics, effecting a change in a colored surface (usually by adjusting proportions of pigment dyes), or by ablating a surface layer to expose a sublayer of a different color.

CO_2 lasers can be pulsed at high rates and have produced legible marks at line speeds of 20,000 marks/h. These lasers produce energy densities in the 1–20 J/cm^2 range, which corresponds to millions of watts/cm^2 of power density and allows marking to be performed in areas covering 0.06 to 6 cm^2. The minimum width of an individual line is 0.1 mm (0.004 in.). Mask marking is done by allowing the beam from a laser to be projected through a mask containing the mark to be made. Reimaging the beam by optics onto the workpiece causes a visible change in the material, resulting in a permanent mark. Mask marking is used for materials that are compatible with the wavelength of the laser used.

Scanned-Beam Marking.— Focusing a pulsed laser beam to a small diameter concentrates the power and produces high-energy density that will cause a material to change its visual character. Identified by several names (spot, stroke, pattern generation, or engraving), this application is best known as scanned beam.

In the scanned-beam method, the beam from a pulsed YAG or CO_2 laser is directed onto the surface of a part by a controlled mirror oscillation that changes the beam path in a preprogrammed manner. The programming provides virtually unlimited choice of patterns to be traced on the part. The pulsed laser output can be sequenced with beam manipulation to produce a continuous line or a series of discrete spots that visually suggest a pattern (dot matrix).

The energy density in the focused beam is sufficient to produce a physical or chemical change in most materials. For certain highly reflective metals, such as aluminum, better results are obtained by pretreating the surface (anodizing). Not all scanned beam applications result in removal of base metal. Some remove only a coating or produce a discoloration, caused by heating, that serves as a mark.

Copyright 2004, Industrial Press, Inc., New York, NY

FINISHING OPERATIONS

Power Brush Finishing

Power brush finishing is a production method of metal finishing that employs wire, elastomer bonded wire, or non-metallic (cord, natural fiber or synthetic) brushing wheels in automatic machines, semi-automatic machines and portable air tools to smooth or roughen surfaces, remove surface oxidation and weld scale or remove burrs.

Description of Brushes.— Brushes work in the following ways: the wire points of a brush can be considered to act as individual culling tools so that the brush, in effect, is a multiple-tipped cutting tool. The fill material, as it is rotated, contacts the surface of the work and imparts an impact action which produces a coldworking effect. The type of finish produced depends upon the wheel material, wheel speed, and how the wheel is applied.

Brushes differ in the following ways 1) fill material (wire—carbon steel, stainless steel; synthetic; Tampico; and cord); 2) length of fill material (or trim); and 3) the density of the fill material.

To aid in wheel selection and use, the accompanying table made up from information supplied by *The Osborn Manufacturing Company* lists the characteristics and mayor uses of brushing wheels.

Use of Brushes.— The brushes should be located so as to bring the full face of the brush in contact with the work. Full face contact is necessary to avoid grooving the brush. Operations that are set up with the brush face not in full contact with the work require some provision for dressing the brush face. When the tips of a brush, used with full face contact, become dull during use with subsequent loss of working clearance, reconditioning and resharpening is necessary. This is accomplished simply and efficiently by alternately reversing the direction of rotation during use.

Deburring and Producing a Radius on the Tooth Profile of Gears.— The brush employed for deburring and producing a radius on the tooth profile of gears is a short trim, dense, wire-fill radial brush. The brush should be set up so as to brush across the edge as shown in Fig. 1A. Line contact brushing, as shown in Fig. 1B should be avoided because the Crisis face will wear non-uniformly; and the wire points, being flexible, tend to flare to the side, thus minimizing the effectiveness of the brushing operation. When brushing gears, the brushes are spaced and contact the tooth profile on the center line of the gear as shown in Fig. 2. This facilitates using brush reversal to maintain the wire brushing points at their maximum cutting efficiency.

The setup for brushing spline bores differs from brushing gears in that the brushes are located off-center, as illustrated in Fig. 3. When helical gears are brushed, it is sometimes necessary to favor the acute side of the gear tooth to develop a generous radius prior to shaving. This can be accomplished by locating the brushes as shown In Fig. 4. Elastomer bonded wire-filled brushes are used for deburring fine pitch gears. These brushes remove the burrs without leaving any secondary roll. The use of bonded brushes is necessary when the gears are not shaved after hobbing or gear shaping.



Fig. 1. Methods of Brushing an Edge; (A) Correct, (B) Incorrect


Fig. 2. Setup for Deburring Gears

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Setup for Brushing Broached Splines



Fig. 4. Setup for Finishing Helical Gears

Adjustments for Eliminating Undesirable Conditions in Power Brush Finishing

Undesirable Condition	Possible Adjustments for Eliminating Condition
Brush works too slowly	(1) Decrease trim length and increase fill density. (2) Increase filament diameter. (3) Increase surface speed by increasing R.P.M. or outside diameter.
Brush works too fast	(1) Reduce filament diameter. (2) Reduce surface speed by reducing R.P.M. or outside diameter. (3) Reduce fill density. (4) Increase trim length.
Action of brush peens burr to adjacent surface	(1) Decrease trim length and increase fill density. (2) If wire brush tests indicate metal too ductile (burr is peened rather than removed), change to nonmetallic brush such as a treated Tampico brush used with a burring compound.
Finer or smoother finish required	(1) Decrease trim length and increase fill density. (2) Decrease filament diameter. (3) Try treated Tampico or cord brushes with suitable compounds at recommended speeds. (4) Use auxiliary buffing compound with brush.
Finish too smooth and lustrous	(1) Increase trim length. (2) Reduce brush fill density. (3) Reduce surface speed. (4) Increase filament diameter.
Brushing action not sufficiently uniform	(1) Devise hand-held or mechanical fixture or machine which will avoid irregular off-hand manipulation. (2) Increase trim length and decrease fill density.

Polishing and Buffing

The terms "polishing" and "buffing" are sometimes applied to similar classes of work in different plants, but according to approved usage of the terms, there is the following distinction: Polishing is any operation performed with wheels having abrasive glued to the working surfaces, whereas buffing is done with wheels having the abrasive applied loosely instead of imbedding it into glue; moreover, buffing is not so harsh an operation as ordinary polishing, and it is commonly utilized to obtain very fine surfaces having a "grainless finish."

Polishing Wheels.— The principal materials from which polishing wheels are made are wood, leather, canvas, cotton cloth, plastics, felt, paper, sheepskin, impregnated rubber, canvas composition, and wool. Leather and canvas are the materials most commonly used in polishing wheel construction. Wooden wheels covered with material to which emery or some other abrasive is glued are employed extensively for polishing flat surfaces, espe-

Copyright 2004, Industrial Press, Inc., New York, NY

Characteristics and Applications of Brushes Used in Power Finishing

Brush Type	Description	Operating Speed Range, sfpm	Uses	Remarks
Radial, short trim dense wire fill	Develops very little impact action but maximum cutting action.	6500	Removal of burrs from gear teeth and sprockets. Produces blends and radii at juncture of intersecting surfaces.	Brush should be set up so as to brush across any edge. Reversal of rotation needed to maintain maximum cutting efficiency of brush points.
Radial, medium to long trim twisted knot wire fill	Normally used singly and on portable tools. Brush is versatile and provides high impact action.	7500–9500 for high speeds. 1200 for slow speeds.	For cleaning welds in the automotive and pipeline industries. Also for cleaning surfaces prior to painting, stripping rubber flash from molded products and cleaning mesh-wire conveyor belts.	Surface speed plays an important role since at low speeds the brush is very flexible and at high speeds it is extremely hard and fast cutting.
Radial, medium to long trim crimped wire fill	With the 4- to 8-inch diameter brush, part is hand held. With the 10- to 15-inch diameter brush, part is held by machine.	4500–6000	Serves as utility tool on bench grinder for removing feather grinding burrs, machining burrs, and for cleaning and producing a satin or matte finish.	Good for hand held parts as brush is soft enough to conform to irregular surfaces and hard-to-reach areas. Smaller diameter brushes are not recommended for high-production operations.
Radial, sectional, nonmetallic fill (treated and untreated Tampico or cord)	Provides means for improving finish or improving surface for plating. Works best with grease base deburring or buffing compound.	5500–6500 7500 for polishing	For producing radii and improving surface finish. Removes the sharp peaks that fixed abrasives leave on a surface so that surface will accept a uniform plating. Polishing marks and draw marks can be successfully blended.	Brush is selective to an edge which means that it removes metal from an edge but not from adjoining surfaces. It will produce a very uniform radius without peening or rolling any secondary metal.
Radial, wide-face, nonmetallic fill (natural fibers or synthetics)	Can be used with flow-through mounting which facilitates feeding of cold water and hot alkaline solutions through brush face to prevent buildup.	750–1200 for cleaning steel. 600 when used with slurries	For cleaning steel. Used in electrolytic tinplate lines, continuous galvanizing and annealing lines, and cold reduction lines. Used to produce dull or matte-type finishes on stainless steel and synthetics.	Speeds above 3600 sfpm will not appreciably improve operation as brush wear will be excessive. Avoid excessive pressures. Ammeters should be installed in drive-motor circuit to indicate brushing pressure.

Copyright 2004, Industrial Press, Inc., New York, NY

Characteristics and Applications of Brushes Used in Power Finishing *(Continued)*

Brush Type	Description	Operating Speed Range, sfpm	Uses	Remarks
Radial, wide face, metallic fill	This brush is made to customer's specifications. It is dynamically balanced at the speed at which it will operate.	2000–4000	Removes buildup of aluminum oxide from work rolls in aluminum mill. Removes lime or magnesium coatings from certain types of steel. Burnishes hot-dipped galvanized steel to produce a minimum spangled surface.	Each brush should have its own drive. An ammeter should be present in drive-motor circuit to measure brushing pressure. If strip is being brushed, a steel backup roll should be opposite the brush roll.
Radial, wide face, strip (interrupted brush face)	Performs cleaning operations that would cause a solid face brush to become loaded and unusable.	When cleaning conveyor belts, brush speed is 2 to 3 times that of conveyer belt.	Need for cleaning rubber and fabric conveyor belts of carry-back material which would normally foul snubber pulley and return idlers.	Designed for medium- to light-duty work. Brush face does not load.
Radial, Cup, Flared End, and Straight End, wire fill elastomer bonded	Extremely fast cutting with maximum operator safety. No loss of wire through fatigue. Always has uniform face.	3600–9000	For removing oxide weld scale, burrs, and insulation from wire.	Periodic reversing of brush direction will result in a brush life ten times greater than non-bonded wheels. Fast cutting action necessitates precise holding of part with respect to brush.
Cup, twisted knot wire fill	Fast cutting wheel used on portable tools to clean welds, scale, rust, and other oxides.	8000–10,000 4500–6500 for deburring and producing a radius around periphery of holes.	Used in shipyards and in structural steel industry. For cleaning outside diameter of pipe and removing burrs and producing radii on heat exchanger tube sheets and laminations for stator cores.	Fast acting brush cleans large areas economically. Setup time is short.
Radial, wire or treated Tampico or cord	For use with standard centerless grinders. Brush will not remove metal from a cylindrical surface. Parts must be ground to size before brushing.	…	For removing feather grinding burrs and improving surface finish. Parts of 24 microinches can be finished down to 15 to 10 microinches. Parts of 10 to 12 microinches can be finished down to 7 to 4 microinches.	Follows centerless grinding principles, except that accuracy in pressure and adjustment is not critical. A machine no longer acceptable for grinding can be used for brushing.

Copyright 2004, Industrial Press, Inc., New York, NY

cially when good edges must be maintained. Cloth wheels are made in various ways; wheels having disks that are cemented together are very hard and used for rough, coarse work, whereas those having sewn disks are made of varying densities by sewing together a larger or smaller number of disks into sections and gluing then.

Wheels in which the disks are held together by thread or metal stitches and which are not stiffened by the use of glue usually require metal side plates to support the canvas disks. Muslin wheels are made from sewed or stapled buffs glued together, but the outer edges of a wheel frequently are left open or free from glue to provide an open face of any desired depth. Wool felt wheels are flexible and resilient, and the density may be varied by sewing two or more disks together and then cementing to form a wheel. Solid felt wheels are quite popular for fine finishing but have little value as general utility wheels. Paper wheels are made from strawboard paper disks and are cemented together under pressure to form a very hard wheel for rough work. Softer wheels are similarly made from felt paper. The "compress" canvas wheel has a cushion of polishing material formed by pieces of leather, canvas, or felt, that are held in a crosswise radial position by two side plates attached to the wheel hub. This cushion of polishing material may be varied in density to suit the requirements; it may be readily shaped to conform to the curvature of the work and this shape can be maintained. Sheepskin polishing wheels and paper wheels are little used.

Polishing Operations and Abrasives.— Polishing operations on such parts as chisels, hammers, screwdrivers, wrenches, and similar parts that are given a fine finish but are not plated, usually require four operations, which are "roughing," "dry fining," "greasing," and "coloring." The roughing is frequently regarded as a solid grinding wheel job. Sometimes there are two steps to the greasing operation—rough and fine greasing. For some hardware, such as the cheaper screwdrivers, wrenches, etc., the operations of roughing and dry fining are considered sufficient. For knife blades and cutlery, the roughing operation is performed with solid grinding wheels and the polishing is known as fine or blue glazing, but these terms are never used when referring to the polishing of hardware parts, plumbers' supplies, etc. A term used in finishing German silver, white metal, and similar materials is "sand-buffing," which, in distinction from the ordinary buffing operation that is used only to produce a very high finish, actually removes considerable metal, as in rough polishing or flexible grinding. For sand-buffing, pumice and other abrasive powders are loosely applied.

Aluminum oxide abrasives are widely used for polishing high-tensile-strength metals such as carbon and alloy steels, tough iron, and nonferrous alloys. Silicon carbide abrasives are recommended for hard, brittle substances such as grey iron, cemented carbide tools, and materials of low tensile strength such as brass, aluminum, and copper.

Buffing Wheels.— Buffing wheels are manufactured from disks (either whole or pieced) of bleached or unbleached cotton or woolen cloth, and they are used as the agent for carrying abrasive powders, such as tripoli, crocus, rouge, lime, etc., which are mixed with waxes or greases as a bond. There are two main classes of buffs, one of which is known as the "pieced-sewed" buffs, and is made from various weaves and weights of cloth. The other is the "full-disk" buffs, which are made from specially woven material. Bleached cloth is harder and stiffer than unbleached cloth, and is used for the faster cutting buffs. Coarsely woven unbleached cloth is recommended for highly colored work on soft metals, and the finer woven unbleached cloths are better adapted for harder metals. When working at the usual speed, a stiff buff is not suitable for "cutting down" soft metal or for light plated ware, but is used on harder metals and for heavy nickel-plated articles.

Speed of Polishing Wheels.— The proper speed for polishing is governed to some extent by the nature of the work, but for ordinary operations, the polishing wheel should have a peripheral speed of about 7500 ft/min. If run at a lower speed, the work tends to tear the polishing material from the wheel too readily, and the work is not as good in quality. Muslin, felt, or leather polishing wheels having wood or iron centers should be run at peripheral speeds varying from 300 to 7000 ft/min. It is rarely necessary to exceed 6000 ft/min, and

Copyright 2004, Industrial Press, Inc., New York, NY

for most purposes, 4000 ft/min is sufficient. If the wheels are kept in good condition, in perfect balance, and are suitably mounted on substantial buffing lathes, they can be used safely at speeds within the limits given. However, manufacturers' recommendations concerning wheel speeds should be followed, where they apply.

Grain Numbers of Emery.— The numbers commonly used in designating the different grains of emery, corundum, and other abrasives are 10, 12, 14, 16, 18, 20, 24, 30, 36, 40, 46, 54, 60, 70, 80, 90, 100, 120, 150, 180, and 200, ranging from coarse to fine, respectively. These numbers represent the number of meshes per linear inch in the grading sieve. An abrasive finer than No. 200 is known as "flour" and the degree of fineness is designated by the letters CF, F, FF, FFF, FFFF, and PCF or SF, ranging from coarse to fine. The methods of grading flour-emery adopted by different manufacturers do not exactly agree, the letters differing somewhat for the finer grades. Again, manufacturers' recommendations should be followed.

Grades of Emery Cloth.— The coarseness of emery cloth is indicated by letters and numbers corresponding to the grain number of the loose emery used in the manufacture of the cloth. The letters and numbers for grits ranging from fine to coarse are as follows: FF, F, 120, 100, 90, 80, 70, 60, 54, 46, and 40. For large work roughly filed, use coarse cloth such as numbers 46 or 54, and then finer grades to obtain the required polish. If the work has been carefully filed, a good polish can be obtained with numbers 60 and 90 cloth, and a brilliant polish can be achieved by finishing with number 120 and flour-emery.

Mixture for Cementing Emery Cloth to a Lapping Wheel.— Many proprietary adhesives are available for application of emery cloth to the periphery of a buffing or lapping wheel, and generally are supplied with application instructions. In the absence of such instructions, clean the wheel thoroughly before applying the adhesive, and then rub the emery cloth down so as to exclude all air from between the surface of the wheel and the cloth.

Etching and Etching Fluids

Etching Fluids for Different Metals.— A common method of etching names or simple designs upon steel is to apply a thin, even coating of beeswax or some similar substance which will resist acid; then mark the required lines or letters in the wax with a sharp-pointed scriber, thus exposing the steel (where the wax has been removed by the scriber point) to the action of an acid, which is finally applied. To apply a very thin coating of beeswax, place the latter in a silk cloth, warm the piece to be etched, and tub the pad over it. Regular coach varnish is also used instead of wax, as a "resist."

An etching fluid ordinarily used for carbon steel consists of nitric acid, 1 part; water, 4 parts. It may be necessary to vary the amount of water, as the exact proportion depends upon the carbon content and whether the steel is hard or soft. For hard steel, use nitric acid, 2 parts; acetic acid, 1 part. For high-speed steel, nickel or brass, use nitro-hydrochloric acid (nitric, 1 part; hydrochloric, 4 parts). For high-speed steel it is sometimes better to add a little more nitric acid. For etching bronze, use nitric acid, 100 parts; muriatic acid, 5 parts. For brass, nitric acid, 16 parts; water, 160 parts, dissolve 6 parts potassium chlorate in 100 parts of water; then mix the two solutions and apply.

A fluid which may be used either for producing a frosted effect or for deep etching (depending upon the time it is allowed to act) is composed of 1 ounce sulphate of copper (blue vitriol); ¼ ounce alum; ½ teaspoonful of salt; 1 gill of vinegar, and 20 drops of nitric acid. For aluminum, use a solution composed of alcohol, 4 ounces; acetic acid, 6 ounces; antimony chloride, 4 ounces; water, 40 ounces.

Various acid-resisting materials are used for covering the surfaces of steel rules etc., prior to marking off the lines on a graduating machine. When the graduation lines are fine and very closely spaced, as on machinists' scales which are divided into hundredths or sixty-fourths, it is very important to use a thin resist that will cling to the metal and prevent

Copyright 2004, Industrial Press, Inc., New York, NY

any under-cutting of the acid: the resist should also enable fine lines to be drawn without tearing or crumbling as the tool passes through it. One resist that has been extensively used is composed of about 50 per cent of asphaltum, 25 per cent of beeswax, and, in addition, a small percentage of Burgundy pitch, black pitch, and turpentine. A thin covering of this resisting material is applied to the clean polished surface to be graduated and, after it is dry, the work is ready for the graduating machine. For some classes of work, paraffin is used for protecting the surface surrounding the graduation lines which are to be etched. The method of application consists in melting the paraffin and raising its temperature high enough so that it will flow freely; then the work is held at a slight angle and the paraffin is poured on its upper surface. The melted paraffin forms a thin protective coating.

Conversion Coatings and the Coloring of Metals

Conversion Coatings.— Conversion coatings are thin, adherent chemical compounds that are produced on metallic surfaces by chemical or electrochemical treatment. These coatings are insoluble, passive, and protective, and are divided into two basic systems: oxides or mixtures of oxides with other compounds, usually chromates or phosphates. Conversion coatings are used for corrosion protection, as an adherent paint base; and for decorative purposes because of their inherent color and because they can absorb dyes and colored sealants.

Conversion coatings are produced in three or four steps. First there is a pretreatment, which often involves mechanical surface preparation followed by decreasing and/or chemical or electrochemical cleaning or etching. Then thermal, chemical, or electrochemical surface conversion processes take place in acid or alkaline solutions applied by immersion spraying, or brushing. A post treatment follows, which includes rinsing and drying, and may also include sealing or dyeing. If coloring is the main purpose of the coating, then oiling, waxing, or lacquering may be required.

Passivation of Copper.— The blue-green patina that forms on copper alloys during atmospheric exposure is a passivated film; i.e., it prevents corrosion. This patina may be produced artificially or its growth may be accelerated by a solution of ammonium sulfate, 6 pounds; copper sulfate, 3 ounces; ammonia (technical grade, 0.90 specific gravity), 1.34 fluid ounces; and water, 6.5 gallons. This solution is applied as a fine spray to a chemically cleaned surface and is allowed to dry between each of five or six applications. In about 6 hours a patina somewhat bluer than natural begins to develop and continues after exposure to weathering.

Small copper parts can be coated with a passivated film by immersion in or brushing with a solution consisting of the following weight proportions: copper, 30; nitric acid, concentrated, 60; acetic acid (6%), 600; ammonium chloride, 11; and ammonium hydroxide (technical grade, 0.90 specific gravity), 20. To prepare the solution, the copper is dissolved in the nitric acid before the remaining chemicals are added, and the solution is allowed to stand for several days before use. A coating of linseed oil is applied to the treated parts.

Coloring of Copper Alloys.— Metals are colored to enhance their appearance, to produce an undercoat for an organic finish, or to reduce light reflection. Copper alloys can be treated to produce a variety of colors, with the final color depending on the base metal composition, the coloring solution's composition, the immersion time, and the operator's skill. Cleaning is an important part of the pretreatment; nitric and sulfuric acid solutions are used to remove oxides and to activate the surface.

The following solutions are used to color alloys that contain 85 per cent or more of copper. A dark red color is produced by immersing the parts in molten potassium nitrate, at 1200–1300°F, for up to 20 seconds, followed by a hot water quench. The parts must then be lacquered. A steel black color can be obtained by immersing the parts in a 180°F solution of arsenious oxide (white arsenic), 4 ounces; hydrochloric acid (1.16 specific gravity), 8 fluid ounces; and water, 1 gallon. The parts are immersed until a uniform color is

Copyright 2004, Industrial Press, Inc., New York, NY

obtained; they are scratch brushed while wet, and then dried and lacquered. A light brown color is obtained using a room-temperature solution of barium sufate, 0.5 ounce; ammonium carbonate, 0.25 ounce; and water, 1 gallon.

The following solutions are used to color alloys that contain less than 85 per cent copper. To color brass black, parts are placed in an oblique tumbling barrel made of stainless steel and covered with 3 to 5 gallons of water. Three ounces of copper sulfate and 6 ounces of sodium thiosulfate are dissolved in warm water and added to the barrel's contents. After tumbling for 15 to 30 minutes to obtain the finish, the solution is drained from the barrel, and the parts are washed thoroughly in clean water, dried in sawdust or air-blasted and, if necessary, lacquered. To produce a blue-black color, the parts are immersed in a 130–175°F solution of copper carbonate 1 pound; ammonium hydroxide (0.89 specific gravity), 1 quart; and water, 3 quarts. Excess copper carbonate should be present. The proper color is obtained in 1 minute. To color brass a hardware green, immerse the parts in a 160°F solution of ferric nitrate, 1 ounce; sodium thiosulfate, 6 ounces; and water, 1 gallon. To color brass a light brown, immerse the parts in a 195–212°F solution of potassium chlorate, 5.5 ounces; nickel sulfate, 2.75 ounces; copper sulfate, 24 ounces; and water, 1 gallon.

Post treatment: The treated parts should be scratch brushed to remove any excess or loose deposits. A contrast of colors may be obtained by brushing with a slurry of fine pumice, hand nabbing with an abrasive paste, mass finishing, or buffing to remove the color from the highlights. In order to prolong the life of parts used for outdoor decorative purposes, a clear lacquer should be applied. Parts intended for indoor purposes are often used without additional protection.

Coloring of Iron and Steel.— Thin black oxide coatings are applied to steel by immersing the parts to be coated in a boiling solution of sodium hydroxide and mixtures of nitrates nitrites. These coatings serve as paint bases and, in some cases, as final finishes. When the coatings are impregnated with oil or wax, they furnish fairly good corrosion resistance. These finishes are relatively inexpensive compared to other coatings.

Phosphate Coatings: Phosphate coatings are applied to iron and steel parts by reacting them with a dilute solution of phosphoric acid and other chemicals. The surface of the metal is converted into an integral, mildly protective layer of insoluble crystalline phosphate. Small items are coated in tumbling barrels; large items are spray coated on conveyors.

The three types of phosphate coatings in general use are zinc, iron, and manganese. Zinc phosphate coatings vary from light to dark gray. The color depends on the carbon content and pretreatment of the steel's surface, as well as the composition of the solution. Zinc phosphate coatings are generally used as a base for paint or oil, as an aid in cold working, for increased wear resistance, or for rustproofing. Iron phosphate coatings were the first type to be used; they produce dark gray coatings and their chief application is as a paint base. Manganese phosphate coatings are usually dark gray; however, since they are used almost exclusively as an oil base, for break in and to prevent galling, they become black in appearance.

In general, stainless steels and certain alloy steels cannot be phosphated. Most cast irons and alloy steels accept coating with various degrees of difficulty depending on alloy content.

Anodizing Aluminum Alloys.— In the anodizing process, the aluminum object to be treated is immersed as the anode in an acid electrolyte, and a direct current is applied. Oxidation of the surface occurs, producing a greatly thickened, hard, porous film of aluminum oxide. The object is then immersed in boiling water to seal the porosity and render the film impermeable. Before sealing, the film can be colored by impregnation with dyes or pigments. Special electrolytes may also be used to produce colored anodic films directly in the anodizing bath. The anodic coatings are used primarily for corrosion protection and abrasion resistance, and as a paint base.

Copyright 2004, Industrial Press, Inc., New York, NY

The three principal types of anodizing processes are: chromic, in which the active agent is chromic acid; sulfuric, in which the active agent is sulfuric acid, and hard anodizing, in which sulfuric acid is used by itself or with additives in a low-temperature electrolyte bath. Most of the anodic coatings range in thickness from 0.2 to 0.7 mil. The hard anodizing process can produce coatings up to 2 mils. The chromic acid coating is less brittle than the sulfuric, and, since the chromic electrolyte does not attack aluminum, it does not present a corrosion problem when it is trapped in crevices. The chromic coating is less resistant to abrasion than the sulfuric, but it cannot be used with alloys containing more than 5 per cent copper due to corrosion of the base metal.

Chemical Conversion Coatings for Aluminum: Chemical conversion coatings for aluminum alloys are adherent surface layers of low volubility oxide, phosphate, or chromate compounds produced by the reaction of the metal surface with suitable reagents. The conversion coatings are much thinner and softer than anodic coatings but they are less expensive and serve as an excellent paint base.

Magnesium Alloys.— Chemical treatment of magnesium alloys is used to provide a paint base and to improve corrosion resistance. The popular conversion "dip" coatings are chrome pickle and dichromate treatments, and they are very thin. Anodic coatings are thicker and harder, and, after sealing, give the same protection against corrosion, although painting is still desirable.

Titanium Alloys.— Chemical conversion coatings are used on titanium alloys to improve lubricity by acting as a base for the retention of lubricants. The coatings are applied by immersion, spraying, or brushing. A popular coating bath is an aqueous solution of phosphates, fluorides, and hydrofluoric acid. The coating is composed primarily of titanium and potassium fluorides and phosphates.

Plating

Surface Coatings.— The following is a list of military plating and coating specifications.

Anodize (Chromic and Sulfuric), MIL-A-8625F: Conventional Types I, IB, and II anodic coatings are intended to improve surface corrosion protection under severe conditions or as a base for paint systems. Coatings can be colored with a large variety of dyes and pigments. Class 1 is non-dyed; Class 2 dyed. Color is to be specified on the contract. Prior to dying or sealing, coatings shall meet the weight requirements.

Type I and IB coatings should be used on fatigue critical components (due to thinness of coating). Type I unless otherwise specified shall not be applied to aluminum alloys with over 5% copper or 7% silicon or total alloying constituents over 7.5%. Type IC is a mineral or mixed mineral/organic acid that anodizes. It provides a non-chromate alternative for Type I and IB coatings where corrosion resistance, paint adhesion, and fatigue resistance are required. Type IIB is a thin sulfuric anodizing coating for use as non-chromate alternatives for Type I and IB coatings where corrosion resistance, paint adhesion, and fatigue resistance are required. Be sure to specify the class of anodic coating and any special sealing requirements.

Types I, IB, IC, and IIB shall have a thickness between 0.00002 and 0.0007 in. Type II shall have a thickness between 0.0007 and 0.0010 in.

Black Chrome, MIL-C-14538C: A hard, non-reflective, abrasion, heat and corrosion resistant coating approximately 0.0002 in. thick. Provides limited corrosion protection, but added protection can be obtained by specifying underplate such as nickel. Color is a dull dark gray, approaching black and may be waxed or oiled to darken.

Black chromium has poor throwing power, and conforming anodes are necessary for intricate shapes. Apply coating after heat treating and all mechanical operations are performed. Steel parts with hardness in excess of 40 Rc shall be stress relieved prior to plating by baking one hour or more (300 to 500°F) and baked after plating (375°F ± 25°F) for 3 hours.

Copyright 2004, Industrial Press, Inc., New York, NY

Black Oxide Coating, MIL-C-13924C: A uniform, mostly decorative black coating for ferrous metals used to decrease light reflection. Only very limited corrosion protection under mild corrosion conditions. Black oxide coatings should normally be given a supplementary treatment.

Used for moving parts that cannot tolerate the dimensional change of a more corrosion resistant finish. Use alkaline oxidizing for wrought iron, cast and malleable irons, plain carbon, low alloy steel and corrosion resistant steel alloys. Alkaline-chromite oxidizing may be used on certain corrosion resistant steel alloys tempered at less than 900°F Salt oxidizing is suitable for corrosion resistant steel alloys that are tempered at 900°F or higher.

Cadmium, QQ-P-416F: Cadmium plating is required to be smooth, adherent, uniform in appearance, free from blisters, pits, nodules, burning, and other defects when examined visually without magnification. Unless otherwise specified in the engineering drawing or procurement documentation, the use of brightening agents in the plating solution to modify luster is prohibited on components with a specified heat treatment of 180 ksi minimum tensile strength (or 40 Rc) and higher. Either a bright (not caused by brightening agents) or dull luster shall be acceptable. Baking on Types II and III shall be done prior to application of supplementary coatings. For Classes 1, 2, and 3 the minimum thicknesses shall be 0.0005, 0.0003, and 0.0002 in. respectively.

Type I is to be used as plated. Types II and III require supplementary chromate and phosphate treatment respectively. Chromate treatment required for type II may be colored iridescent bronze to brown including olive drab, yellow and forest green. Type II is recommended for corrosion resistance. Type III is used as a paint base and is excellent for plating stainless steels that are to be used in conjunction with aluminum to prevent galvanic corrosion. For Types II and III the minimum cadmium thickness requirement shall be met after the supplementary treatment.

Chemical Films, MIL-C-5541E: The materials that qualify produce coatings that range in color from clear to iridescent yellow or brown. Inspection difficulties may arise with clear coatings because of their invisibility.

Class 1A chemical conversion coatings are intended to provide corrosion prevention when left unpainted as well as to improve adhesion of paint finish systems on aluminum and aluminum alloys. May be used on tanks, tubings, and component structures where paint finishes are not required for the exterior surfaces but are required for the interior surfaces.

Class 3 chemical conversion coatings are intended for use as a corrosive film for electrical and electronic applications where lower resistant contacts are required. The primary difference between Class 1A and Class 3 coating is thickness.

Chemical Finish: Black, MIL-F-495E: A uniform black corrosion retardant for copper. Coating has no abrasion resistance. Used to blacken color and reduce gloss on copper-alloy surfaces other than food service and water supply items. Also used as a base for subsequent coatings such as lacquer, varnish, oil, and wax.

Chrome, QQ-C-320B: Has excellent hardness, wear resistance, and erosion resistance. In addition chrome has a low coefficient of friction, is resistant to heat, and can be rendered porous for lubrication purposes.

Types I and II have bright and satin appearances respectively.

Class 1 is used as plating for corrosion protection and Class 2, for engineering plating. Class 1 and 2 both shall have a minimum thickness of 0.00001 in. on all visible surfaces. If thickness is not specified use 0.002 in.

Class 2a will be plated to specified dimensions or processed to specified dimensions after plating. Class 2b will be used on parts below 40 Rc and subject to static loads or designed for limited life under dynamic loads. Class 2c will be used on parts below 40 Rc and designed for unlimited life under dynamic loads. Class 2d parts have hardness of 40 Rc or above, which are subject to static loads or designed for unlimited life under dynamic loads.

Copyright 2004, Industrial Press, Inc., New York, NY

Class 2e parts have hardness of 40 Rc or above, which are designed for unlimited life under dynamic loads.

All coated steel parts having a hardness of Rc 36 and higher shall be baked at a minimum of 375°F ± 25°F per the following conditions.With a tensile strength of 160-180 (ksi), the time at temperature will be 3 hr.; at 181-220 ksi, the time will be 8 hr.; and at 221 ksi and above, the time will be 12 hr.

Copper, MIL-C-14550B: Has good corrosion resistance when used as an undercoat. A number of copper processes are available, each designed for a specific purpose such as, to improve brightness (to eliminate the need for buffing), high speed (for electro-forming), and fine grain (to prevent case-hardening).

All steel parts having a hardness of Rc 35 and higher shall be baked at 375°F ± 25°F for 24 hours, within four hours after plating to provide hydrogen embrittlement relief. Plated springs and other parts subject to flexure shall not be flexed prior to baking operations.

Class 0 will have a thickness 0.001 - 0.005 in. and is used for heat treatment stop-off; Class 1 is 0.001 in. and is used to provide carburizing shield, also for plated through printed circuit boards. Class 2 is 0.0005 in. thick and is used as an undercoat for nickel and other platings. Class 3 is 0.0002 in. thick and is used to prevent basis metal migration into tin (prevents poisoning solderability). Class 4 is 0.0001 in. thick.

Tin Lead, MIL-P-81728A: It has excellent solderability. Either a matte or bright luster is acceptable. For electronics components, use only parts with a matte or flow brightened finish.

For brightened electronic components, the maximum thickness will be 0.0003 in. Tin 50 to 70% by weight and with a lead remainder, 0.0003-0.0005 in.

Magnesium Process, MIL-M-3171C: Process #1-A chrome pickle treatment for magnesium. Color varies from matte gray to yellow-red. Has only fair corrosion resistance (< 24 hours, 20% salt spray resistance).

#7-A dichromate treatment for magnesium. Color varies from light brown to gray depending on alloy. Only fair corrosion resistance (< 24 hours, 20% salt spray resistance).

#9-A galvanic anodize treatment for magnesium. Produces a dark brown to black coating. Designed to give a protective film on alloys which do not react to Dow No. 7 treatment. Only fair corrosion resistance (< 24 hours, 20% salt spray resistance).

Type/Class	Thickness (in.)	Comments
Type 1	Removes metal. (approx. 0.0006 for wrought, less for die castings.) No dimensional change	Used for protecting magnesium during shipment, storage and machining. Can be used as a paint base. NOTE: Must remove Type I coating before applying Type III and Type IV treatments.
Type III	…	*Note:* precleaning and pickling may result in dimensional changes due to metal loss.
Type IV	No dimensional change	Can be used as a paint base, and is applicable to all magnesium alloys. Used where optical properties (black) are required on close tolerance parts. NOTE: Precleaning and pickling may result in dimensional changes due to metal loss.

Magnesium Anodic Treatment, MIL-M-45202C: The HAE anodic finish is probably the hardest coating currently available for magnesium. It exhibits stability at high temperatures and has good dielectric strength. It serves as an excellent paint base. It requires resin seal or paint for maximum corrosion protection.

Copyright 2004, Industrial Press, Inc., New York, NY

Type/Class	Typical Thickness	Comments
Type I, Light coating.		
Class A	0.2 mil	Tan coating (HAE)
Grade 1	…	Without post treatment (dyed)
Grade 2	…	With biflouride-dichromate post treatment
Class C	0.3 mil	Light green coating (Dow #17)
Type II, Heavy coating		
Class A	1.5 mil	Hard brown coating (HAE)
Grade 1	…	Without post treatment
Grade 3	…	With biflouride-dichromate post treatment
Grade 4	…	With biflouride-dichromate post treatment including moist heat aging
Grade 5		With double application of biflouride-dichromate post treatment including moist heat aging.
Class D	1.2 mil	Dark green coating (Dow #17)

Coatings range from thin clear to light gray-green, to thick dark-green coatings. The clear coatings are used as a base for subsequent clear lacquers or paints to produce a final appearance similar to clear anodizing on aluminum. The light gray-green coatings are used in most applications which are to be painted. The thick, dark-green coating offers the best combination of abrasion resistance, protective value and paint base characteristics.

Electroless Nickel, AMS 2404C, AMS 2405B, AMS 2433B: Is typically used as a coating to provide a hard-ductile, wear-resistant, and corrosion-resistant surface for operation in service up to 1000°F, to provide uniform build-up on complex shapes.

AMS 2404C, is deposited directly on the basis metal without a flash coating of other metal, unless otherwise specified. AMS 2405B, is deposited directly on the basis metal except where parts fabricated from corrosion resistant steels or alloys where a "strike" coating of nickel or other suitable metal is required, unless otherwise specified. AMS 2433B, is a type of electroless nickel typically used to enhance the solderability of surfaces, but usage is not limited to such applications. Generally, the plate shall be placed directly on the basis metal. However, aluminum alloys shall be zinc immersion coated per ASTM B253 followed by copper flash; corrosion resistant steels and nickel and cobalt alloys or other basis metals may use a nickel or copper flash undercoat when the purchaser permits.

Electroless Nickel Preparation: Parts having a hardness higher than Rc 40 and have been machined or ground after heat treatment shall be suitably stress-relieved before cleaning and plating.

After treatment, parts having a hardness of Rc 33 and over shall be heated to 375°F ± 15°F for three hours. If such treatment is injurious to the parts, bake at 275°F ± 15°F for four hours.

Electroless Nickel, Low-Phosphorous

Note: If permitted by drawing, the maximum hardness and wear resistance are obtained by heating parts for 30-60 minutes, preferably in an inert atmosphere, at 750°F ± 15°F except aluminum parts shall be baked at 450°F ± 15°F for four hours. If such heating is not specified, bake at 375°F ± 15°F for three hours. If this treatment is injurious to parts or assemblies, bake at 275°F for five hours.

Plating: nickel-thallium-boron (Electroless Deposition) and nickel-boron (Electroless Deposition)

Preparation: All fabrication-type operations shall be completed.

Copyright 2004, Industrial Press, Inc., New York, NY

Post-treatment: Cold worked or heat treated parts and aluminum alloys and other parts requiring special thermal treatment shall be post treated as agreed upon by purchaser and vendor. Other plated parts within four hours after plating shall be heat treated for 90 ± 10 minutes at 675°F ± 15°F.

Electropolishing, (No MIL-SPEC No.): This process electrolytically removes or diminishes scratches, burrs, and unwanted sharp edges from most metals. Finishes from satin to mirror-bright are produced by controlling time, temperature, or both.

Typically the thickness loss is 0.0002 in. This process is not recommended for close tolerance surfaces.

Gold, MIL-G-45204C: Has a yellow to orange color depending on the proprietary process used. Will range from matte to bright finish depending on basis metal. It has good corrosive resistance and a high tarnish resistance. It provides a low contact resistance, is a good conductor of electricity, and has excellent solderability. If the hardness grade for the gold coating is not specified, Type I shall be furnished at a hardness of Grade A, and Type II furnished at a hardness of Grade C.

For soldering, a thin pure soft gold coating is preferred. A minimum and maximum thickness 0.00005 and 0.00010 in., respectively, shall be plated.

Unless otherwise specified, gold over silver underplate combinations shall be excluded from electronics hardware. Silver or copper plus silver may not be used as an underplate unless required by the item specification. When gold is applied to brass bronze or beryllium copper, or a copper plate or strike, an antidiffusion underplate such as nickel shall be applied.

Type I is 99.7% gold minimum (Grades A, B, or C); Type II is 99.0% (Grades B, C, or D); and Type III is 99.9% (Grade A only).

Grade A is 90 Knoop maximum; Grade B is 91-129 Knoop; Grade C is 130-200 Knoop; and Grade D is 201 Knoop and over.

Class 00 has a thickness of 0.00002 in. minimum; Class 0, 0.00003 in.; Class 1, 0.00005 in.; Class 2, 0.0001 in.; Class 3, 0.0002 in.; Class 4, 0.0003 in.; Class 5, 0.0005 in.; and Class 6, 0.0015 in.

Hard Anodize, MIL-A-8625F: The color will vary from light tan to black depending on alloy and thickness. Can be dyed in darker colors depending on the thickness. Coating penetrates base metal as much as builds up on the surface. The term thickness includes both the buildup and penetration. It provides a very hard ceramic type coating. Abrasion resistance will vary with alloy and thickness of coating. Has good dielectric properties.

Do not seal coatings where the main function is to obtain maximum abrasion or wear resistance. When used for exterior applications requiring corrosion resistance but permitting reduced abrasion, the coating shall be sealed (boiling deionized water or hot 5% sodium dichromate solution, or other suitable chemical solutions).

Type III will have a thickness specified on the contract or applicable drawing. If not specified use a nominal thickness of 0.002 in. Hard coatings may vary in thickness from 0.0005 - 0.0045 in.

Class 1 shall be not dyed or pigmented. Class 2 shall be dyed and the color specified on the contract. The process can be controlled to very close thickness tolerances. Where maximum serviceability or special properties are required, consult metal finisher for best alloy choice. Thick coatings (those over 0.004 in.) will tend to break down sharp edges. Can be used as an electrical insulation coating. "Flash" hard anodize may be used instead of conventional anodize for corrosion resistance and may be more economical in conjunction with other hard anodized areas.

Lubrication, Solid Film MIL-L-46010D: The Military Plating Specification establishes the requirements for three types of heat cured solid film lubricants that are intended to

Copyright 2004, Industrial Press, Inc., New York, NY

reduce wear and prevent galling, corrosion, and seizure of metals. For use on aluminum, copper, steel, stainless steel, titanium, and chromium, and nickel bearing surfaces.

Types I, II, and III have a thicknesses of 0.008 - 0.013 mm. No single reading less than 0.005 mm or greater than 0.018 mm.

Type I has a curing temperature of 150 ± 15°C and an endurance life of 250 minutes; Type II, 204 ± 15°C and 450 minutes; and Type III is a low volatile organic compound (VOC) content lubricant with cure cycles of 150 ± 15°C for two hours, or 204 ± 15°C for one hour with an endurance life of 450 minutes. Color 1 has a natural product color and Color 2 has a black color.

Nickel, QQ-N-290A: There is a nickel finish for almost any need. Nickel can be deposited soft, hard-dull, or bright, depending on process used and conditions employed in plating. Thus, hardness can range from 150-500 Vickers. Nickel can be similar to stainless steel in color, or can be a dull gray (almost white) color. Corrosion resistance is a function of thickness. Nickel has a low coefficient of thermal expansion.

All steel parts having a tensile strength of 220,000 or greater shall not be a nickel plate without specific approval of procuring agency.

Class 1 is used for corrosion protection. Plating shall be applied over an underplating of copper or yellow brass on zinc and zinc based alloys. In no case, shall the copper underplate be substituted for any part of the specified nickel thickness. Class 2 is used in engineering applications.

Grade A has a thickness of 0.0016 in.; Grade B, 0.0012 in.; Grade C, 0.001 in.; Grade D, 0.0008 in.; Grade E, 0.0006 in.; Grade F, 0.0004 in.; and Grade G, 0.002 in.

Palladium, MIL-P-45209B: A gray, dense deposit good for undercoats. Has good wear characteristics, corrosion resistance, catalytic properties, and good conductivity.

The thickness shall be 0.00005 in. unless otherwise specified.

Steel springs and other steel parts subject to flexure or repeated impact and of hardness greater than Rc 40 shall be heated to 375°F ± 25°F for three hours after plating.

Passivate, QQ-P-35C: Intended to improve the corrosion resistance of parts made from austentic, ferritic, and martensitic corrosion-resistant steels of the 200, 300, and 400 series and precipitation hardened corrosion resistant steels. 440C grades may be exempt from passivation treatments of the procuring activity.

Type II is a medium temperature nitric acid solution with sodium dichromate additive. Type VI, a low temperature nitric acid solution; Type VII, a medium temperature nitric acid solution; and Type VIII, a medium temperature high concentration nitric acid solution.

Phosphate Coating: Light, TT-C-490D: This specification covers cleaning methods and pretreatment processes.

Methods /Types	Typical Thickness (in.)	Comments
Cleaning Methods		
	–	Light coating for use as a paint base.
Method I	…	Mechanical or abrasive cleaning (for ferrous surfaces only).
Method II	…	Used for solvent cleaning.
Method III	…	Used for hot alkalines (for ferrous surfaces only).
Method IV	…	Emulsion.
Method V	…	Used for alkaline derusting (for ferrous surfaces only).
Method VI	…	Phosphoric acid.

Copyright 2004, Industrial Press, Inc., New York, NY

Pretreatment Coatings		
Type I	…	Zinc phosphate. Class 1-spray application: Class 2A and 2B-Immersion or Dip application
Type II	…	Aqueous Iron Phosphate
Type III	0.0003 – 0.0005	Is an organic pretreatment coating
Type IV	…	Non-aqueous iron phosphate
Type V	…	Zinc phosphate

Type I is intended as a general all-purpose pretreatment prior to painting. Type II and IV are intended primarily for use where metal parts are to be formed after painting. Type III is intended for use where size and shape preclude using Type I, II, or IV and where items containing mixed metal components are assembled prior to treatment.

Phosphate Coating: Heavy, DOD-P-16232-F: The primary differences are that Type M is used as a heavy manganese phosphate coating for corrosion and wear resistance and Type Z is used as a Zinc phosphate coating.

Type M has a thickness from 0.0002-0.0004 in. and Type Z, 0.0002-0.0006 in. Class 1, for both types has a supplementary preservative treatment or coating as specified; Class 2, has a supplementary treatment with lubricating oil; and Class 3, no supplementary treatment is required. For Type M, Class 4 is chemically converted (may be dyed to color as specified) with no supplementary coating or supplementary coating as specified. For Type Z, Class 4 is the same as Class 3.

This coating is for medium and low alloy steels. The coatings range from gray to black in color. The "heavy" phosphate coatings covered by this specification are intended as a base for holding/retaining supplemental coatings which provide the major portion of the corrosion resistance. "Light" phosphate coatings used for a paint base are covered by other specifications. Heavy zinc phosphate coatings may be used when paint and supplemental oil coatings are required on various parts or assemblies.

Rhodium, MIL-R-46085B: Rhodium is metallic and similar to stainless steel in color, has excellent corrosion and abrasion resistance, is almost as hard as chromium, and has a high reflectivity. Thicker coatings of Rhodium are very brittle.

Class/Types	Thickness (in.)	Comments
Type I	–	Over nickel, silver, gold, or platinum.
Type II	–	Over other metals, requires nickel undercoat.
Class 1	0.000002	Used on silver for tarnish resistance.
Class 2	0.00001	
Class 3	0.00002	Applications range from electronic to nose cones -wherever wear, corrosion resist solderability and reflectivity are important.
Class 4	0.00010	
Class 5	0.00025	

Parts having a hardness of Rc 33 or above shall be baked at 375°F for three hours prior to cleaning. Parts having hardness of 40 Rc and above shall be baked within four hours after plating at 375°F for three hours.

Silver, QQ-S-365D: Silver has an increasing use in both decorative and engineering fields, including electrical and electronic fields.

Silver is white matte to very bright in appearance. Has good corrosion resistance, depending on base metal and will tarnish easily. Its hardness varies from about 90-135 Brinell depending on process and plating conditions. Solderability is excellent, but decreases with age. Silver is the best conductor of electricity. Has excellent lubricity and

Copyright 2004, Industrial Press, Inc., New York, NY

smear characteristics for antigalling uses on static seals, bushing, etc. Stress relief steel parts at a minimum 375°F ± 25°F or more prior to cleaning and plating if they contain or are suspected of having damaging residual tensile stresses.

All types and grades will have a minimum thickness of 0.0005 in. unless otherwise specified. Type I is matte, Type II is semi-bright, and Type III is bright. Grade A has a chromate post-treatment to improve tarnish resistance. In contrast Grade B has no supplementary treatment.

Tin, MIL-T-10727C: There are two different types of coating methods used, electrodeposited (based on Use ASTM B545 standard specification for electrodeposited coatings of tin) and hot dipped.

Thickness as specified on drawing (thickness is not part of the specification) is 0.0001-0.0025 in., flash for soldering; 0.0002-0.0004 in., to prevent galling and seizing; 0.0003 in. minimum, where corrosion resistance is important; and 0.0002-0.0006 to prevent formation of case during nitriding.

Color is a gray-white color in plated condition. Tin is soft, but very ductile. It has good corrosion resistance, and has excellent solderability. Tin is not good for low temperature applications.

If a bright finish is desired to be used in lieu of fused tin, specify Bright Tin plate. Thickness can exceed that of fused tin and deposit shows excellent corrosion resistance and solderability.

Vacuum Cadmium, MIL-C-8837B: Is used primarily to provide corrosion resistance to ferrous parts free from hydrogen contamination and possible embrittlement. Recommended on steels with a strength of 2.2×10^5 psi or above.

Coating is applied after all machining, brazing, welding, and forming has been completed. Prior to coating, all steel parts shall be stress relieved by baking at 375°F ± 25 for three hours if suspected of having residual tensile stresses. Immediately prior to coating, lightly dry abrasive blast areas are to be coated.

Type I shall be as plated; and Types II and III require supplementary chromate and phosphate treatments respectively.

Classes 1, 2, and 3 have thicknesses of 0.0005, 0.0003, and 0.0002 in. respectively.

Cadmium coating shall not be used, if in service, temperature reaches 450°F.

A salt spray test is required for type II and is 96 hours.

Zinc, ASTM-B633: This specification covers requirements for electrodeposited zinc coatings applied to iron or steel articles to protect them from corrosion. It does not cover zinc-coated wire or sheets.

Type I will be as plated; Type II will have colored chromate conversion coatings; Type III will have colorless chromate conversion coatings; and Type IV will have phosphate conversion coatings.

High strength steels (tensile strength over 1700 MPa) shall not be electroplated.

Stress relief: All parts with ultimate tensile strength 1000 MPa and above at minimum 190°C for three hours or more before cleaning and plating.

Hydrogen embrittlement relief: All electroplated parts 1200 MPa or higher shall be baked at 190°C for three hours or more within four hours after electroplating.

Corrosion Resistance Requirements	
Types	Test Period Hr.
II	96
III	12

Copyright 2004, Industrial Press, Inc., New York, NY

Flame Spraying Process

In this process, the forerunner of which was called the metal spraying process, metals, alloys, ceramics, and cermets are deposited on metallic or other surfaces. The object may be to build up worn or undersize parts, provide wear-resisting or corrosion-resisting surfaces, correct defective castings, etc.

Different types of equipment are available that provide the means of depositing the coatings on the surfaces. In one, wire is fed automatically through the nozzle of the spray gun; then a combustible gas, oxygen and compressed air serve to melt and blow the atomized metal against the surface to be coated. The gas usually used is acetylene but other gases may be used. Any desired thickness of metal may be deposited and the metals include steels, ranging from low to high carbon content, various brass and bronze compositions, babbitt metal, tin, zinc, lead, nickel, copper, and aluminum. The movement of the spray gun, in covering a given surface, is controlled either mechanically or by hand. In enlarging worn or undersize shafts, spindles, etc., it is common practice to clamp the gun in a lathe toolholder and use the feed mechanism to traverse the gun at a uniform rate while the metal is being deposited upon the rotating workpiece. The spraying operation may be followed by machining or grinding to obtain a more precise dimension.

Some typical production applications using the wire process are the coating of automotive exhaust valves, refinishing of transfer ink rollers for the printing industry and the rebuilding of worn truck clutch plates. Other production applications include the metallizing of glass meter box windows, the spraying of aluminum onto cloth gauze to produce electrolytic condenser plates, and the spraying of zinc or copper for coating ceramic insulators.

With another type of equipment, metal, refractory, and ceramic powder are used instead of wire. Ordinarily this equipment employs the use of two gases, oxygen and a fuel gas. The fuel gas is usually acetylene but in some instances hydrogen may be used. When handheld, a small reservoir supplies the powder to the equipment but a larger reservoir is used for lathe-mounted equipment or for large-scale production work. The four basic types of coating powders used with this equipment are ceramics, oxidation-resistant metals and alloys, self-bonding alloys, and alloys for fused coatings. These powders are used to produce wear-resistant, corrosion-resistant, heat-resistant, and electrically conductive coatings.

Still other equipment employs the use of plasma flame with which vapors of materials are raised to a higher energy level than the ordinary gaseous state. Its use raises the temperature ceiling and provides a controlled atmosphere by permitting employment of an inert or chemically inactive gas so that chemical action, such as oxidation, during the heating and application of the spray material can be controlled. The temperatures that can be obtained with commercially available plasma equipment often exceed 30,000 degrees F but for most plasma flame spray processes the temperature range of from 12,000 to 20,000 degrees F is optimum. Plasma flame spray materials include alumina, zirconia, tungsten, molybdenum, tantalum, copper, aluminum, carbides, and nickel-base alloys.

Regardless of the equipment used, what is important is the proper preparation of the surface that will receive the sprayed coating. Preparation activities include the degreasing or solvent cleaning of the surface, undercutting of the surface to provide room for the proper coating thickness, abrasive or grit blasting the substrate to provide a roughened surface, grooving (in the case of flat surfaces) or rough threading (in the case of cylindrical work) the surface to be coated, preheating the base metal. Methods of obtaining a bond between the sprayed material and the substrate are: heating the base, roughening the base, or spraying a “self-bonding” material onto a smooth surface; however, heating alone is seldom used in machine element work as the elevated temperatures required to obtain the proper bond causes problems of warpage and surface corrosion.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

FASTENERS

NAILS, SPIKES, AND WOOD SCREWS

1476 Wire Nails and Spikes
1477 Wood Screws

RIVETS AND RIVETED JOINTS

1478 Riveted Joint Design
1478 Classes and Types of Joints
1478 General Design Considerations
1479 Failure of Riveted Joints
1480 Allowable Stresses
1480 Analysis of Joint Strength
1481 Formulas for Riveted Joint Design
1483 American National Standard Rivets
1483 ANSI Large Rivets
1483 ANSI Small Solid Rivets
1484 Rivet Lengths for Forming Heads
1485 British Standard Rivets
1485 Rivets for General Engineering
1485 Additional ANSI Rivet Tables
1485 Flat and Oval Head Countersunk
1486 Button, Cone, and Pan Head
1487 Swell Neck Rivets
1487 Dimensions for Dolly Bars
1488 Truss Head and Coopers Rivets
1489 Tinners and Belt Rivets
1490 Flat, Countersunk, Button, and Pan Head Rivets
1491 British Standard Tables
1491 General Purpose Small Rivets
1491 Dimensions of Rivets
1492 Countersunk, Snap, Universal, and Flat Head Rivets
1493 Snap, Mushroom, Flat, Countersunk, and Pan Head
1494 Snap, Pan, and Countersunk Head Rivet Dimensions and Diameters

TORQUE AND TENSION IN FASTENERS

1496 Wrench Torque
1496 Preload in Loaded Joint
1496 Preload In Shear
1497 General Application of Preload
1498 Preload Adjustments
1498 Coefficients of Friction
1499 Preload Relaxation
1499 Measuring Preload

TORQUE AND TENSION IN FASTENERS

(Continued)

1500 Bolt Preload Application Methods
1500 Elongation Measurement
1502 Tensile Stress Area
1503 Torque and Clamping Force
1505 Torque and Friction Coefficients
1506 Torque-Tension Relationships
1508 Grade Marks
1508 Grade Identification Marks
1509 Detecting Counterfeit Fasteners
1509 Mechanical Properties of Nuts
1509 Working Strength of Bolts
1510 Lengths of Engagement
1511 Breaking Force
1511 Lock Wire Procedure Detail

INCH THREADED FASTENERS

1512 Bolts, Screws, and Nuts
1513 Square and Hex Bolts
1514 ANSI Square Bolts
1515 ANSI Hex and Heavy Hex Bolts
1516 Heavy Hex Screws
1517 Square Lag Screws
1518 Hex Lag Screws
1519 Hex Nuts and Jam Nuts
1520 Heavy Hex Flat Nuts
1521 Heavy Hex Slotted Nuts
1522 Square Nuts
1523 Low and High Crown Nuts
1525 Round Head Square Neck Bolts
1525 T Head Bolts
1526 Round Head Square Neck Bolts
1526 Round Head Fin Neck Bolts
1527 Round Head Ribbed Neck Bolts
1528 Countersunk Square Neck Bolts
1529 Countersunk Bolts
1530 Wrench Openings for Nuts
1530 Wrench Clearance Dimensions
1530 Box Wrench Washers
1532 Type A Plain Washer
1533 ANSI Standard Plain Washers
1534 Type B Plain Washers
1535 Helical Spring and Tooth Lock Washers
1536 Helical Spring Lock Washer
1538 Tooth Lock Washers

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

FASTENERS

METRIC THREADED FASTENERS

1540 Comparison with ISO Standards
1541 Metric Hex Cap Screws
1542 Metric Formed Hex Screws
1543 Metric Heavy Hex Screws
1543 Metric Screw and Bolt Diameters
1544 Metric Hex Screws and Bolts
1545 Metric Hex Lag Screws
1546 Heavy Hex Flange Screws
1547 Hex Flange Screws
1547 Round Head Square Neck Bolts
1549 Heavy Hex Bolts
1549 Heavy Hex Structural Bolts
1550 Hex Bolts
1550 Mechanical Properties
1551 Identification Symbols
1551 Designation
1552 Socket Head Cap Screws
1552 Diameter-Length Combinations
1552 Metric Hex Lag Screws
1553 Cap Screws, Screws, Hex Flang
1554 Heavy Hex Structural Bolts
1554 Round Head Square Neck Bolts
1555 Socket Head Cap Screws
1556 Thread Series
1556 Clearance Holes
1557 Drill and Counterbore Sizes
1558 Drilled Head Dimensions
1559 Socket Head Cap Screws
1560 Metric Nuts
1561 Comparison with ISO Standards
1561 Tops and Bearing Surfaces
1561 Mechanical Properties
1562 Hex Nuts
1563 Slotted Hex Nuts
1563 Thread Series
1564 Hex Flange Nuts
1564 Prevailing-Torque Type Nuts
1566 Metric Hex Flange Nuts
1566 Metric Nut Identification Symbols
1566 Metric Nut Designation
1568 Metric Washers
1568 Metric Plain Washers
1568 Comparison with ISO Standards
1568 Types of Metric Plain Washers
1568 Materials and Finish
1568 Metric Plain Washer Designation

BRITISH FASTENERS

1570 British Standard Bolts and Nuts
1570 Square and Hexagon Bolts
1570 British Standard Screwed Studs
1571 Whitworth and Fine Precision Hexagon Bolts, Screws
1574 ISO Metric Precision Hexagon Bolts, Screws and Nuts
1575 Hexagon Bolts and Screws
1576 Hexagon Nuts and Thin Nuts
1577 Hexagon Slotted Nuts
1578 Hexagon Bolts, Screws and Nuts
1578 Nominal Lengths
1580 Strength and Grade Designation
1580 Bolt and Nut Combinations
1581 British Standard Studs
Washers
1582 British Standard Spring Washers
1583 Double Coil Washers
1584 Square Section Spring Washers
1584 British Standard Metric Washers

MACHINE SCREWS AND NUTS

1587 ANSI Machine Screws, Inch
1587 Square and Hexagon Nuts
1588 Slotted Flat Countersunk Head
1590 Washer Head Machine Screws
1591 Slotted Truss Head
1592 Slotted Pan Head
1593 Slotted Fillister
1594 Slotted Oval Countersunk Head
1595 Slotted Binding Head
1596 Slotted Round Head
1596 Machine Screw Cross Recesses
1596 ANSI Metric Machine Screws
1597 Thread Lengths
1598 Square Recessed Flat Countersunk Head
1599 Oval Countersunk Head
1600 Square Recessed Pan Head
1602 Hex and Hex Flange Head
1604 Nominal Screw Lengths
1605 BS Metric Machine Screws
1607 Slotted Countersunk Head
1608 Slotted Raised Countersunk Head
1610 Machine Screw Nuts
1611 Slotted Pan Head
1612 Slotted Cheese Head
1614 BS Unified Machine Screws
1617 Whitworth Machine Screws

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

FASTENERS

CAP AND SET SCREWS

1618 Cap Screws
1619 Slotted Round
1620 Hexagon and Spline Socket
1621 Drill and Counterbore Size
1622 Hexagon and Spline Socket
1624 Socket Head Shoulder Screws
1625 Slotted Headless Set Screws
1626 Screw Optional Cup Points
1627 Hexagon and Spline Sockets
1628 Square Head Set Screws
1630 Hexagon and Spline Keys and Bits
1632 Hexagon Socket Screws
1636 Button Head Screws
1637 Hexagon Socket Set Screws
1637 Holding Power of Set-screws
1638 Bright Square Head Set-Screws

SELF-THREADING SCREWS

1639 Sheet Metal, Self-Tapping, and Metallic Drive Screws
1640 Method of Designation
1641 Self-Tapping Screws
1642 Threads and Points
1642 Cross Recesses
1643 Forming Tapping Screws
1644 B and BP Thread
1645 Thread and Point Dimensions
1646 D, F, G, and T Thread
1647 Hole Sizes
1648 Types A, B, and BP Screws
1650 Types D, F, G, and T Screws
1653 Types BF and BT Screws
1654 Type U Hardened Screw
1654 Torsional Strength
1654 Self-tapping Thread Inserts
1654 Screw Thread Inserts
1654 Thread Cutting Tapping Screws
1655 Threads and Points
1656 Method of Designation
1657 Nominal Screw Lengths
1658 Types BF, BT, D, F, and T Screws
1658 Material and Heat Treatment
1659 Clearance Holes
1660 Clean-Punched Hole Sizes
1663 BF and BT Metric Thread

T-SLOTS, BOLTS, AND NUTS

1664 T-Slots
1665 T-Bolts
1666 T-Nuts

PINS AND STUDS

1667 Dowel & Cotter Pins
1668 Clevis Pins
1668 Metric Series Dowel Pins
1669 Steel Dowel Pins
1670 Hardened Ground Machine
1672 Unhardened Ground Dowel Pin
1673 ANSI Straight Pins
1674 ANSI Taper Pins
1675 Drilling Specifications
1677 ANSI Grooved Pins
1678 T-Head Cotter Pins and Round Head Grooved Drive Studs
1681 Grooved T-Head Cotter Pins
1681 Grooved Drive Studs
1682 Slotted Type Spring Pins
1682 Spring Pins
1683 Coiled Type Spring Pins

RETAINING RINGS

1684 Retaining Rings
1684 Tapered Retaining Rings
1687 Reduced Cross Section
1690 Basic Internal Series
1692 E-Type External Series
1697 Heavy Duty Internal Spiral
1699 Heavy Duty External Spiral
1701 Dimensions of Retaining Rings
1707 Inch Series Self-Locking
1709 Retaining Ring Failure
1710 Retaining Ring Standards

WING NUTS, WING SCREWS, AND THUMB SCREWS

1712 Wing Nuts
1715 Specification of Wing Nuts
1715 Threads for Wing Nuts
1716 Materials and Finish
1716 Wing Screws and Thumb Screws
1717 Types A and B Wing Screws
1718 Types C and D Wing Screws
1719 Types A and B Thumb Screws
1720 Threads for Wing Screws
1720 Points for Wing Screws

Copyright 2004, Industrial Press, Inc., New York, NY

NAILS, SPIKES, AND WOOD SCREWS

Standard Wire Nails and Spikes

(Size, Length and Approximate Number to Pound)

Size of Nail	Length, Inches	Gage	Num/lb	Gage	Num/lb	Gage	Num/lb	Gage	Num/lb	Gage	Num/lb
		Common Wire Nails and Brads		Flooring Brads		Fence Nails		Casing, Smooth and Barbed Box		Finishing Nails	
2 *d*	1	15	876	…	…	…	…	15 ½	1010	16 ½	1351
3 *d*	1 ¼	14	568	…	…	…	…	14 ½	635	15 ½	807
4 *d*	1 ½	12 ½	316	…	…	…	…	14	473	15	584
5 *d*	1 ¾	12 ½	271	…	…	10	142	14	406	15	500
6 *d*	2	11 ½	181	11	157	10	124	12 ½	236	13 ½	309
7 *d*	2 ¼	11 ½	161	11	139	9	92	12 ½	210	13	238
8 *d*	2 ½	10 ¼	106	10	99	9	82	11 ½	145	12 ½	189
9 *d*	2 ¾	10 ¼	96	10	90	8	62	11 ½	132	12 ½	172
10 *d*	3	9	69	9	69	7	50	10 ½	94	11 ½	121
12 *d*	3 ¼	9	64	8	54	6	40	10 ½	87	11 ½	113
16 *d*	3 ½	8	49	7	43	5	30	10	71	11	90
20 *d*	4	6	31	6	31	4	23	9	52	10	62
30 *d*	4 ½	5	24	…	…	…	…	9	46	…	…
40 *d*	5	4	18	…	…	…	…	8	35	…	…
50 *d*	5 ½	3	16	…	…	…	…	…	…	…	…
60 *d*	6	2	11	…	…	…	…	…	…	…	…
Size and Length		Hinge Nails, Heavy		Hinge Nails, Light		Clinch Nails		Barbed Car Nails, Heavy		Barbed Car Nails, Light	
2 *d*	1	…	…	…	…	14	710	…	…	…	…
3 *d*	1 ¼	…	…	…	…	13	429	…	…	…	…
4 *d*	1 ½	3	50	6	82	12	274	10	165	12	274
5 *d*	1 ¾	3	38	6	62	12	235	9	118	10	142
6 *d*	2	3	30	6	50	11	157	9	103	10	124
7 *d*	2 ¼	00	12	3	25	11	139	8	76	9	92
8 *d*	2 ½	00	11	3	23	10	99	8	69	9	82
9 *d*	2 ¾	00	10	3	22	10	90	7	54	8	62
10 *d*	3	00	9	3	19	9	69	7	50	8	57
12 *d*	3 ¼	…	…	…	…	9	62	6	42	7	50
16 *d*	3 ½	…	…	…	…	8	49	6	35	7	43
20 *d*	4	…	…	…	…	7	37	5	26	6	31
30 *d*	4 ½	…	…	…	…	…	…	5	24	6	28
40 *d*	5	…	…	…	…	…	…	4	18	5	21
50 *d*	5 ½	…	…	…	…	…	…	3	15	4	17
60 *d*	6	…	…	…	…	…	…	3	13	4	15

Size and Length		Boat Nails, Heavy		Boat Nails, Light		Slating Nails	
2 *d*	1	…	…	…	…	12	411
3 *d*	1 ¼	…	…	…	…	10 ½	225
4 *d*	1 ½	¼	44	3/16	82	10 ½	187
5 *d*	1 ¾	…	…	…	…	10	142
6*d*	2	¼	32	3/16	62	9	103
7 *d*	2 ¼	…	…	…	…	…	…
8 *d*	2 ½	¼	26	3/16	50	…	…
9 *d*	2 ¾	…	…	…	…	…	…
10 *d*	3	3/8	14	¼	22	…	…
12 *d*	3 ¼	3/8	13	¼	20	…	…
16 *d*	3 ½	3/8	12	¼	18	…	…
20 *d*	4	3/8	10	¼	16	…	…
30 *d*	4 ½	…	…	…	…	…	…
40 *d*	5	…	…	…	…	…	…
50 *d*	5 ½	…	…	…	…	…	…
60 *d*	6	…	…	…	…	…	…

Spikes			
Size and Length		Gage	No. to Lb
10 *d*	3	6	41
12 *d*	3 ¼	6	38
16 *d*	3 ½	5	30
20 *d*	4	4	23
30 *d*	4 ½	3	17
40 *d*	5	2	13
50 *d*	5 ½	1	10
60 *d*	6	1	8
…	7	0	7
…	8	00	6
…	9	00	5
…	10	3/8	4
…	12	3/8	3

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Flat, Pan, and Oval Head Wood Screws *ANSI B18.6.1-1981 (R1997)*



Nominal Size	Threads per inch	*D*[a] Basic Dia. of Screw	*J* Width of Slot		*A* Head Diameter		*B* Head Diameter		*P* Head Radius	*H* Height of Head
			Max.	Min.	Max., Sharp Edge	Min., Edge Rounded or Flat	Max.	Min.	Max.	Ref.
0	32	.060	.023	.016	.119	.099	.116	.104	.020	.035
1	28	.073	.026	.019	.146	.123	.142	.130	.025	.043
2	26	.086	.031	.023	.172	.147	.167	.155	.035	.051
3	24	.099	.035	.027	.199	.171	.193	.180	.037	.059
4	22	.112	.039	.031	.225	.195	.219	.205	.042	.067
5	20	.125	.043	.035	.252	.220	.245	.231	.044	.075
6	18	.138	.048	.039	.279	.244	.270	.256	.046	.083
7	16	.151	.048	.039	.305	.268	.296	.281	.049	.091
8	15	.164	.054	.045	.332	.292	.322	.306	.052	.100
9	14	.177	.054	.045	.358	.316	.348	.331	.056	.108
10	13	.190	.060	.050	.385	.340	.373	.357	.061	.116
12	11	.216	.067	.056	.438	.389	.425	.407	.078	.132
14	10	.242	.075	.064	.507	.452	.492	.473	.087	.153
16	9	.268	.075	.064	.544	.485	.528	.508	.094	.164
18	8	.294	.084	.072	.635	.568	.615	.594	.099	.191
20	8	.320	.084	.072	.650	.582	.631	.608	.121	.196
24	7	.372	.094	.081	.762	.685	.740	.716	.143	.230

[a] *Diameter Tolerance:* Equals + 0.004 in. and – 0.007 in. for cut threads. For rolled thread body diameter tolerances, see ANSI 18.6.1-1981 (R1991).

Nominal Size	Threads per Inch	*O* Tot. Hgt. of Head		*K* Height of Head		*T* Depth of Slot		*U* Depth of Slot		*V* Depth of Slot	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
0	32	.056	.041	.039	.031	.015	.010	.022	.014	.030	.025
1	28	.068	.052	.046	.038	.019	.012	.027	.018	.038	.031
2	26	.080	.063	.053	.045	.023	.015	.031	.022	.045	.037
3	24	.092	.073	.060	.051	.027	.017	.035	.027	.052	.043
4	22	.104	.084	.068	.058	.030	.020	.040	.030	.059	.049
5	20	.116	.095	.075	.065	.034	.022	.045	.034	.067	.055
6	18	.128	.105	.082	.072	.038	.024	.050	.037	.074	.060
7	16	.140	.116	.089	.079	.041	.027	.054	.041	.081	.066
8	15	.152	.126	.096	.085	.045	.029	.058	.045	.088	.072
9	14	.164	.137	.103	.092	.049	.032	.063	.049	.095	.078
10	13	.176	.148	.110	.099	.053	.034	.068	.053	.103	.084
12	11	.200	.169	.125	.112	.060	.039	.077	.061	.117	.096
14	10	.232	.197	.144	.130	.070	.046	.087	.070	.136	.112
16	9	.248	.212	.153	.139	.075	.049	.093	.074	.146	.120
18	8	.290	.249	.178	.162	.083	.054	.106	.085	.171	.141
20	8	.296	.254	.182	.166	.090	.059	.108	.087	.175	.144
24	7	.347	.300	.212	.195	.106	.070	.124	.100	.204	.168

All dimensions in inches. The edge of flat and oval head screws may be flat or rounded. Wood screws are also available with Types I, IA, and II recessed heads. Consult the standard for recessed head dimensions. *The length of the thread, L_T, on wood screws having cut threads shall be equivalent to approximately two-thirds of the nominal length of the screw. For rolled threads, L_T shall be at least four times the basic screw diameter or two-thirds of the nominal screw length, whichever is greater. Screws of nominal lengths that are too short to accommodate the minimum thread length shall have threads extending as close to the underside of the head as practicable.

Pilot Hole Drill Sizes for Wood Screws

Work Material	Wood Screw Size						
	2	4	6	8	10	12	14
Hardwood	3/64	1/16	5/64	3/32	7/64	1/8	9/64
Softwood	1/32	3/64	1/16	5/64	3/32	7/64	1/8

Copyright 2004, Industrial Press, Inc., New York, NY

RIVETS AND RIVETED JOINTS

Riveted Joint Design

Classes and Types of Riveted Joints.— Riveted joints may be classified by application as: 1) pressure vessel; 2) structural; and 3) machine member.

For information and data concerning joints for pressure vessels such as boilers, reference should be made to standard sources such as the ASME Boiler Code. The following sections will cover only structural and machine-member riveted joints.

Basically there are two kinds of riveted joints, the *lap-joint* and the *butt-joint*. In the ordinary *lap-joint*, the plates overlap each other and are held together by one or more rows of rivets. In the *butt-joint*, the plates being joined are in the same plane and are joined by means of a cover plate or butt strap, which is riveted to both plates by one or more rows of rivets. The term *single riveting* means one row of rivets in a lap-joint or one row on each side of a butt-joint; *double riveting* means two rows of rivets in a lap-joint or two rows on each side of the joint in butt riveting. Joints are also triple and quadruple riveted. Lap-joints may also be made with inside or outside cover plates. Types of lap and butt joints are illustrated in the tables on starting at page 1482.

General Design Considerations for Riveted Joints.— Factors to be considered in the design or specification of a riveted joint are: type of joint; spacing of rivets; type and size of rivet; type and size of hole; and rivet material.

Spacing of Rivets: The spacing between rivet centers is called *pitch* and between row center lines, *back pitch* or *transverse pitch*. The distance between centers of rivets nearest each other in adjacent rows is called *diagonal pitch*. The distance from the edge of the plate to the center line of the nearest row of rivets is called *margin*.

Examination of a riveted joint made up of several rows of rivets will reveal that after progressing along the joint a given distance, the rivet pattern or arrangement is repeated. (For a butt joint, the length of a *repeating section* is usually equal to the *long pitch* or pitch of the rivets in the outer row, that is the row farthest from the edge of the joint.) For structural and machine-member joints, the proper pitch may be determined by making the tensile strength of the plate over the length of the repeating section, that is the distance between rivets in the outer row, equal to the total shear strength of the rivets in the repeating section. Minimum pitch and diagonal pitch are also governed by the clearance required for the hold-on (Dolly bar) and rivet set. Dimensions for different sizes of hold-ons and rivet sets are given in the table on page 1487.

When fastening thin plate, it is particularly important to maintain accurate spacing to avoid buckling.

Size and Type of Rivets: The rivet diameter d commonly falls between $d = 1.2\sqrt{t}$ and $d = 1.4\sqrt{t}$, where t is the thickness of the plate. Dimensions for various types of American Standard large ($\frac{1}{2}$-inch diameter and up) rivets and small solid rivets are shown in tables that follow. It may be noted that countersunk heads are not as strong as other types.

Size and Type of Hole: Rivet holes may be punched, punched and reamed, or drilled. Rivet holes are usually made $\frac{1}{16}$ inch larger in diameter than the nominal diameter of the rivet although in some classes of work in which the rivet is driven cold, as in automatic machine riveting, the holes are reamed to provide minimum clearance so that the rivet fills the hole completely.

When holes are punched in heavy steel plate, there may be considerable loss of strength unless the holes are reamed to remove the inferior metal immediately surrounding them. This results in the diameter of the punched hole being increased by from $\frac{1}{16}$ to $\frac{1}{8}$ inch. Annealing after punching tends to restore the strength of the plate in the vicinity of the holes.

Copyright 2004, Industrial Press, Inc., New York, NY

Rivet Material: Rivets for structural and machine-member purposes are usually made of wrought iron or soft steel, but for aircraft and other applications where light weight or resistance to corrosion is important, copper, aluminum alloy, Monel, Inconel, etc., may be used as rivet material.

Simplified Design Assumptions: In the design of riveted joints, a simplified treatment is frequently used in which the following assumptions are made:

1) The load is carried equally by the rivets.
2) No combined stresses act on a rivet to cause failure.
3) The shearing stress in a rivet is uniform across the cross-section under question.
4) The load that would cause failure in single shear would have to be doubled to cause failure in double shear.
5) The bearing stress of rivet and plate is distributed equally over the projected area of the rivet.
6) The tensile stress is uniform in the section of metal between the rivets.

Failure of Riveted Joints.— Rivets may fail by:

1) Shearing through one cross-section (single shear)
2) Shearing through two cross-sections (double shear)
3) Crushing

Plates may fail by:

4) Shearing along two parallel lines extending from opposite sides of the rivet hole to the edge of the plate
5) Tearing along a single line from middle of rivet hole to edge of plate
6) Crushing
7) Tearing between adjacent rivets (tensile failure) in the same row or in adjacent rows

Types 4 and 5 failures are caused by rivets being placed too close to the edge of the plate. These types of failure are avoided by placing the center of the rivet at a minimum of one and one-half times the rivet diameter away from the edge.



Types of Rivet and Plate Failure

Failure due to tearing on a diagonal between rivets in adjacent rows when the pitch is four times the rivet diameter or less is avoided by making the transverse pitch one and three-quarters times the rivet diameter.

Theoretical versus Actual Riveted Joint Failure: If it is assumed that the rivets are placed the suggested distance from the edge of the plate and each row the suggested distance from another row, then the failure of a joint is most likely to occur as a result of shear failure of the rivets, bearing failure (crushing) of the plate or rivets, or tensile failure of the plate, alone or in combination depending on the makeup of the joints.

Joint failure in actuality is more complex than this. Rivets do not undergo pure shear especially in lap-joints where rivets are subjected to single shear. The rivet, in this instance, would be subject to a combination of tensile and shearing stresses and it would fail because

Copyright 2004, Industrial Press, Inc., New York, NY

of combined stresses, not a single stress. Furthermore, the shearing stress is usually considered to be distributed evenly over the cross-section, which is also not the case.

Rivets that are usually driven hot contract on cooling. This contraction in the length of the rivet draws the plates together and sets up a stress in the rivet estimated to be equal in magnitude to the yield point of the rivet steel. The contraction in the diameter of the rivet results in a little clearance between the rivetand the hole in the plate. The tightness in the plates caused by the contraction in length of the rivet gives rise to a condition in which quite a sizeable frictional force would have to be overcome before the plates would slip over one another and subject the rivets to a shearing force. It is European practice to design joints for resistance to this slipping. It has been found, however, that the strength-basis designs obtained in American and English practice are not very different from European designs.

Allowable Stresses.— The design stresses for riveted joints are usually set by codes, practices, or specifications. The American Institute of Steel Construction issues specifications for the design, fabrication, and erection of structural steel for buildings in which the allowable stress permitted in tension for structural steel and rivets is specified at 20,000 pounds per square inch, the allowable bearing stress for rivets is 40,000 psi in double shear and 32,000 psi in single shear, and the allowable shearing stress for rivets is 15,000 psi. The American Society of Mechanical Engineers in its Boiler Code lists the following ultimate stresses: tensile, 55,000 psi; shearing, 44,000 psi; compressive or bearing, 95,000 psi. The design stresses usually are one-fifth of these, that is tensile, 11,000 psi; shearing, 8800 psi; compressive or bearing, 19,000 psi. In machine design work, values close to these or somewhat lower are commonly used.

Analysis of Joint Strength.— The following examples and strength analyses of riveted joints are based on the six previously outlined *Simplified Design Assumptions*.

Example 1: Consider a 12-inch section of single-riveted lap-joint made up with plates of $\frac{1}{4}$-inch thickness and six rivets, $\frac{5}{8}$ inch in diameter. Assume that rivet holes are $\frac{1}{16}$ inch larger in diameter than the rivets. In this joint, the entire load is transmitted from one plate to the other by means of the rivets. Each plate and the six rivets carry the entire load. The safe tensile load L and the efficiency η may be determined in the following way: Design stresses of 8500 psi for shear, 20,000 psi for bearing, and 10,000 psi for tension are arbitrarily assigned and it is assumed that the rivets will not tear or shear through the plate to the edge of the joint.

a) The safe tensile load L based on single shear of the rivets is equal to the number of rivets n times the cross-sectional area of one rivet A_r times the allowable shearing stress S_s or

$$L = n \times A_r \times S_s = 6 \times \frac{\pi}{4}(0.625)^2 \times 8500 = 15,647 \text{ pounds}$$

b) The safe tensile load L based on bearing stress is equal to the number of rivets n times the projected bearing area of the rivet A_b (diameter times thickness of plate) times the allowable bearing stress S_c or $L = n \times A_b \times S_c = 6 \times (0.625 \times 0.25) \times 20,000 = 18,750$ pounds.

c) The safe load L based on the tensile stress is equal to the net cross-sectional area of the plate between rivet holes A_p times the allowable tensile stress S_t or

$$L = A_p \times S_t = 0.25[12 - 6(0.625 + 0.0625)] \times 10,000 = 19,688 \text{ pounds.}$$

The safe tensile load for the joint would be the least of the three loads just computed or 15,647 pounds and the efficiency η would be equal to this load divided by the tensile strength of the section of plate under consideration, if it were unperforated or

$$\eta = \frac{15,647}{12 \times 0.25 \times 10,000} \times 100 = 52.2 \text{ per cent}$$

Example 2: Under consideration is a 12-inch section of double-riveted butt-joint with main plates $\frac{1}{2}$ inch thick and two cover plates each $\frac{5}{16}$ inch thick. There are 3 rivets in the inner row and 2 on the outer and their diameters are $\frac{7}{8}$ inch. Assume that the diameter of the

Copyright 2004, Industrial Press, Inc., New York, NY

rivet holes is $\frac{1}{16}$ inch larger than that of the rivets. The rivets are so placed that the main plates will not tear diagonally from one rivet row to the others nor will they tear or fail in shear out to their edges. The safe tensile load L and the efficiency η may be determined in the following way: Design stresses for 8500 psi for shear, 20,000 psi for bearing, and 10,000 psi for tension are arbitrarily assigned.

a) The safe tensile load L based on double shearing of the rivets is equal to the number of rivets n times the number of shearing planes per rivet times the cross-sectional area of one rivet A_r times the allowable shearing stress S_s or

$$L = n \times 2 \times A_r \times S_s = 5 \times 2 \times \frac{\pi}{4}(0.875)^2 \times 8500 = 51{,}112 \text{ pounds}$$

b) The safe tensile load L based on bearing stress is equal to the number of rivets n times the projected bearing area of the rivet A_b (diameter times thickness of plate) times the allowable bearing stress S_c or $L = n \times A_b \times S_c = 5 \times (0.875 \times 0.5) \times 20{,}000 = 43{,}750$ pounds.

(Cover plates are not considered since their combined thickness is $\frac{1}{4}$ inch greater than the main plate thickness.)

c) The safe tensile load L based on the tensile stress is equal to the net cross-sectional area of the plate between the two rivets in the outer row A_p times the allowable tensile stress S_t or $L = A_p \times S_t = 0.5[12 - 2(0.875 + 0.0625)] \times 10{,}000 = 50{,}625$ pounds.

In completing the analysis, the sum of the load that would cause tearing between rivets in the three-hole section plus the load carried by the two rivets in the two-hole section is also investigated. The sum is necessary because if the joint is to fail, it must fail at both sections simultaneously. The least safe load that can be carried by the two rivets of the two-hole section is based on the bearing stress (see the foregoing calculations).

1) The safe tensile load L based on the bearing strength of two rivets of the two-hole section is $L = n \times A_b \times S_c = 2 \times (0.875 \times 0.5) \times 20{,}000 = 17{,}500$ pounds.

2) The safe tensile load L based on the tensile strength of the main plate between holes in the three-hole section is $L \times A_p \times S_t = 0.5[12 - 3(0.875 + 0.0625)] \times 10{,}000 = 45{,}938$ pounds.

The total safe tensile load based on this combination is $17{,}500 + 45{,}938 = 63{,}438$ pounds, which is greater than any of the other results obtained.

The safe tensile load for the joint would be the least of the loads just computed or 43,750 pounds and the efficiency η would be equal to this load divided by the tensile strength of the section of plate under consideration, if it were unperforated or

$$\eta = \frac{43{,}750}{0.5 \times 12 \times 10{,}000} \times 100 = 72.9 \text{ per cent}$$

Formulas for Riveted Joint Design.— A riveted joint may fail by shearing through the rivets (single or double shear), crushing the rivets, tearing the plate between the rivets, crushing the plate or by a combination of two or more of the foregoing causes. Rivets placed too close to the edge of the plate may tear or shear the plate out to the edge but this type of failure is avoided by placing the center of the rivet 1.5 times the rivet diameter away from the edge.

The efficiency of a riveted joint is equal to the strength of the joint divided by the strength of the unriveted plate, expressed as a percentage.

In the following formulas, let

d = diameter of holes t = thickness of plate t_c = thickness of cover plates

p = pitch of inner row of rivets P = pitch of outer row of rivets

S_s = shear stress for rivets S_t = tensile stress for plates

S_c = compressive or bearing stress for rivets or plates

Copyright 2004, Industrial Press, Inc., New York, NY

In the joint examples that follow, dimensions are usually specified in inches and stresses in pounds per square inch. See page 1480 for a discussion of allowable stresses that may be used in calculating the strengths given by the formulas. The design stresses are usually set by codes, practices, or specifications.

Single-Riveted Lap-Joint



(1) Resistance to shearing one rivet = $\frac{\pi d^2}{4} S_s$

(2) Resistance to tearing plate between rivets = $(p - D)tS_t$

(3) Resistance to crushing rivet or plate = dtS_c

Double-Riveted Lap-Joint



(1) Resistance to shearing two rivets = $\frac{2\pi d^2}{4} S_s$

(2) Resistance to tearing between two rivets = $(p - D)tS_t$

(3) Resistance to crushing in front of two rivets = $2dtS_c$

Single-Riveted Lap-Joint with Inside Cover Plate



(1) Resistance to tearing between outer row of rivets = $(P - D)tS_t$

(2) Resistance to tearing between inner row of rivets, and shearing outer row of rivets = $(P - 2D)tS_t + \frac{\pi d^2}{4} S_s$

(3) Resistance to shearing three rivets = $\frac{3\pi d^2}{4} S_s$

(4) Resistance to crushing in front of three rivets = $3tdS_c$

(5) Resistance to tearing at inner row of rivets, and crushing in front of one rivet in outer row = $(P - 2D)tS_t + tdS_c$

Double-Riveted Lap-Joint with Inside Cover Plate



(1) Resistance to tearing at outer row of rivets = $(P - D)tS_t$

(2) Resistance to shearing four rivets = $\frac{4\pi d^2}{4} S_s$

(3) Resistance to tearing at inner row and shearing outer row of rivets = $(P - 1\frac{1}{2}D)tS_t + \frac{\pi d^2}{4} S_s$

(4) Resistance to crushing in front of four rivets = $4tdS_c$ tdS_c

(5) Resistance to tearing at inner row of rivets, and crushing in front of one rivet = $\left(P - 1\frac{1}{2}D\right)tS_t + tdS_c$

Copyright 2004, Industrial Press, Inc., New York, NY

Double-Riveted Butt-Joint



(1) Resistance to tearing at outer row of rivets =	$(P-D)tS_t$
(2) Resistance to shearing two rivets in double shear and one in single shear =	$\frac{5\pi d^2}{4}S_s$
(3) Resistance to tearing at inner row of rivets and shearing one rivet of the outer row =	$(P-2D)tS_t+\frac{\pi d^2}{4}S_s$
(4) Resistance to crushing in front of three rivets =	$3tdS_c$
(5) Resistance to tearing at inner row of rivets, and crushing in front of one rivet in outer row =	$(P-2D)\,tS_t+tdS_c$

Triple-Riveted Butt-Joint



(1) Resistance to tearing at outer row of rivets =	$(P-D)tS_t$
(2) Resistance to shearing four rivets in double shear and one in single shear =	$\frac{9\pi d^2}{4}S_s$
(3) Resistance to tearing at middle row of rivets and shearing one rivet =	$(P-2D)tS_t+\frac{\pi d^2}{4}S_s$
(4) Resistance to crushing in front of four rivets and shearing one rivet =	$4dtS_c+\frac{\pi d^2}{4}S_s$
(5) Resistance to crushing in front of five rivets =	$4dtS_c+dt_cS_c$

American National Standard Rivets

Standards for rivets published by the American National Standards Institute and the British Standards Institution are as follows:

American National Standard Large Rivets.— The types of rivets covered by this standard (ANSI B18.1.2-1972 (R1995)) are shown on pages 1485, 1486, and 1487. It may be noted, however, that when specified, the swell neck included in this standard is applicable to all standard large rivets except the flat countersunk head and oval countersunk head types. Also shown are the hold-on (dolly bar) and rivet set impression dimensions (see page 1487). All standard large rivets have fillets under the head not exceeding an 0.062-inch radius. The length tolerances for these rivets are given as follows: through 6 inches in length, ½- and ⅝-inch diameters, ±0.03 inch; ¾- and ⅞-inch diameters, ±0.06-inch; and 1- through 1¾-inch diameters, ±0.09 inch. For rivets over 6 inches in length, ½- and ⅝-inch diameters, ±0.06 inch; ¾- and ⅞-inch diameters, ±0.12 inch; and 1- through 1¾-inch diameters, ±0.19 inch. Steel and wrought iron rivet materials appear in ASTM Specifications A31, A131, A152, and A502.

American National Standard Small Solid Rivets.— The types of rivets covered by this standard (ANSI/ASME B18.1.1-1972 (R1995)) are shown on pages 1488 through 1490. In addition, the standard gives the dimensions of 60-degree flat countersunk head rivets used to assemble ledger plates and guards for mower cutter bars, but these are not shown. As the heads of standard rivets are not machined or trimmed, the circumference may be somewhat irregular and edges may be rounded or flat. Rivets other than countersunk types are furnished with a definite fillet under the head, whose radius should not exceed 10 per cent of the maximum shank diameter or 0.03 inch, whichever is the smaller. With regard to head dimensions, tolerances shown in the dimensional tables are applicable to rivets pro-

Copyright 2004, Industrial Press, Inc., New York, NY

Rivet Lengths for Forming Round and Countersunk Heads[a]





Grip in Inches	To Form Round Head — Diameter of Rivet in Inches						
	½	⅝	¾	⅞	1	1⅛	1¼
	Length of Rivet in Inches						
½	1⅜	1⅞	1⅞	2	2⅛	…	…
⅝	1¾	2	2	2⅛	2¼	…	…
¾	1⅞	2⅛	2⅛	2¼	2⅜	…	…
⅞	2	2¼	2¼	2⅜	2½	…	…
1	2¼	2⅜	2⅜	2½	2⅝	2¾	2⅞
1⅛	2⅜	2½	2½	2⅝	2¾	2⅞	3
1¼	2½	2⅝	2⅝	2¾	2⅞	3	3⅛
1⅜	2⅝	2¾	2¾	2⅞	3	3⅛	3¼
1½	2⅞	3	3	3⅛	3¼	3⅜	3½
1⅝	3	3⅛	3⅛	3¼	3⅜	3½	3½
1¾	3⅛	3¼	3¼	3½	3⅝	3¾	3¾
1⅞	3¼	3⅜	3⅜	3⅝	3¾	3⅞	3⅞
2	3½	3½	3⅝	3¾	3⅞	4	4
2⅛	3⅝	3⅝	3¾	3⅞	4	4⅛	4⅛
2¼	3¾	3⅞	3⅞	4	4⅛	4¼	4¼
2⅜	4	4	4	4⅛	4¼	4⅜	4⅜
2½	4⅛	4⅛	4⅛	4¼	4⅜	4½	4½
2⅝	4¼	4¼	4¼	4⅜	4½	4⅝	4⅝
2¾	4⅜	4⅜	4⅜	4½	4⅝	4¾	4¾
2⅞	4⅝	4⅝	4⅝	4⅝	4¾	4⅞	5
3	…	4¾	4¾	4⅞	5	5	5⅛
3⅛	…	4⅞	4⅞	5	5⅛	5¼	5¼
3¼	…	5	5	5⅛	5¼	5⅜	5⅜
3⅜	…	5⅛	5⅛	5¼	5⅜	5½	5½
3½	…	5⅜	5⅜	5⅜	5½	5⅝	5⅝
3⅝	…	5½	5½	5½	5⅝	5¾	5¾
3¾	…	5⅝	5⅝	5⅝	5¾	5⅞	5⅞
3⅞	…	5¾	5¾	5¾	5⅞	6	6
4	…	…	5⅞	6	6	6⅛	6¼
4⅛	…	…	6	6⅛	6¼	6⅜	6⅜
4¼	…	…	6⅛	6¼	6½	6⅝	6½
4⅜	…	…	6⅜	6½	6½	6⅝	6⅝
4½	…	…	6½	6⅝	6⅝	6¾	6¾
4⅝	…	…	6⅝	6¾	6¾	6⅞	6⅞
4¾	…	…	6¾	6⅞	6⅞	7	7
4⅞	…	…	6⅞	7	7	7⅛	7⅛
5	…	…	…	7⅛	7⅛	7¼	7¼
5⅛	…	…	…	7¼	7¼	7⅜	7⅜
5¼	…	…	…	7⅜	7⅜	7½	7½
5⅜	…	…	…	7⅝	7⅝	7¾	7⅝
5½	…	…	…	7¾	7¾	7⅞	7⅞
5⅝	…	…	…	7⅞	7⅞	8	8
5¾	…	…	…	8	8	8⅛	8⅛
5⅞	…	…	…	8⅛	8⅛	8¼	8¼

Grip in Inches	To Form Countersunk Head — Diameter of Rivet in Inches						
	½	⅝	¾	⅞	1	1⅛	1¼
	Length of Rivet in Inches						
½	1	1	1⅛	1¼	1¼	…	…
⅝	1⅛	1¼	1¼	1⅜	1⅜	…	…
¾	1⅜	1⅜	1⅜	1½	1½	…	…
⅞	1½	1½	1½	1⅝	1⅝	…	…
1	1⅝	1⅝	1⅝	1¾	1¾	1⅞	1⅞
1⅛	1¾	1¾	1⅞	1⅞	1⅞	2	2
1¼	2	2	2	2	2	2⅛	2⅛
1⅜	2⅛	2⅛	2⅛	2¼	2¼	2⅜	2⅜
1½	2¼	2¼	2¼	2⅜	2⅜	2½	2½
1⅝	2⅜	2⅜	2⅜	2½	2½	2⅝	2⅝
1¾	2⅝	2⅝	2⅝	2⅝	2⅝	2¾	2¾
1⅞	2¾	2¾	2¾	2¾	2¾	2⅞	2⅞
2	2⅞	2⅞	2⅞	2⅞	2⅞	3	3
2⅛	3⅛	3	3	3	3	3⅛	3⅛
2¼	3¼	3⅛	3⅛	3⅛	3⅛	3¼	3¼
2⅜	3⅜	3⅜	3⅜	3⅜	3⅜	3⅜	3⅜
2½	3½	3½	3½	3½	3½	3⅝	3⅝
2⅝	3⅝	3⅝	3⅝	3⅝	3⅝	3¾	3¾
2¾	3⅞	3¾	3¾	3¾	3¾	3⅞	3⅞
2⅞	4	3⅞	3⅞	3⅞	3⅞	4	4
3	…	4⅛	4⅛	4⅛	4⅛	4⅛	4⅛
3⅛	…	4¼	4¼	4¼	4¼	4¼	4¼
3¼	…	4⅜	4⅜	4⅜	4⅜	4⅜	4⅜
3⅜	…	4½	4½	4½	4½	4½	4½
3½	…	4⅝	4⅝	4⅝	4⅝	4⅝	4⅝
3⅝	…	4¾	4¾	4¾	4¾	4⅞	4⅞
3¾	…	5	5	5	5	5	5
3⅞	…	5⅛	5⅛	5⅛	5⅛	5⅛	5⅛
4	…	…	5¼	5¼	5¼	5¼	5¼
4⅛	…	…	5⅜	5⅜	5⅜	5⅜	5⅜
4¼	…	…	5½	5½	5½	5½	5½
4⅜	…	…	5⅝	5⅝	5⅝	5⅝	5⅝
4½	…	…	5¾	5¾	5¾	5¾	5¾
4⅝	…	…	6	6	6	6	6
4¾	…	…	6⅛	6⅛	6⅛	6⅛	6⅛
4⅞	…	…	6¼	6¼	6¼	6¼	6¼
5	…	…	…	6⅜	6⅜	6⅜	6⅜
5⅛	…	…	…	6½	6½	6½	6½
5¼	…	…	…	6⅝	6⅝	6⅝	6⅝
5⅜	…	…	…	6¾	6¾	6¾	6¾
5½	…	…	…	6⅞	6⅞	6⅞	6⅞
5⅝	…	…	…	7	7	7	7
5¾	…	…	…	7¼	7¼	7¼	7¼
5⅞	…	…	…	7⅜	7⅜	7⅜	7⅜

[a] As given by the American Institute of Steel Construction. Values may vary from standard practice of individual fabricators and should be checked against the fabricator's standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. American National Standard Large Rivets *ANSI B18.1.2-1972 (R1995)*



Flat Countersunk Head



Oval Countersunk Head

Flat and Oval Countersunk Head

Body Diameter[a] *D*				Head Dia. *A*		Head Depth *H*	Oval Crown Height[a] *C*	Oval Crown Radius[a] *G*
Nominal[a]		Max.	Min.	Max.[b]	Min.[c]	Ref.		
½	0.500	0.520	0.478	0.936	0.872	0.260	0.095	1.125
⅝	0.625	0.655	0.600	1.194	1.112	0.339	0.119	1.406
¾	0.750	0.780	0.725	1.421	1.322	0.400	0.142	1.688
⅞	0.875	0.905	0.850	1.647	1.532	0.460	0.166	1.969
1	1.000	1.030	0.975	1.873	1.745	0.520	0.190	2.250
1⅛	1.125	1.160	1.098	2.114	1.973	0.589	0.214	2.531
1¼	1.250	1.285	1.223	2.340	2.199	0.650	0.238	2.812
1⅜	1.375	1.415	1.345	2.567	2.426	0.710	0.261	3.094
1½	1.500	1.540	1.470	2.793	2.652	0.771	0.285	3.375
1⅝	1.625	1.665	1.588	3.019	2.878	0.831	0.309	3.656
1¾	1.750	1.790	1.713	3.262	3.121	0.901	0.332	3.938

[a] All dimensions are given in inches. Basic dimension as manufactured. For tolerances see table footnote on page 1483. The following formulas give basic dimensions for manufactured shapes: *Flat Countersunk Head*, $A = 1.810D$; $H = 1.192(\text{Max } A - D)/2$; included angle Q of head = 78 degrees. *Oval Countersunk Head*, $A = 1.810D$; $H = 1.192(\text{Max } A - D)/2$; included angle of head = 78 degrees. Length L is measured parallel to the rivet axis, from the extreme end to the intersection of the head top surface with the head diameter for countersunk head-type rivets.

[b] Sharp edged head.

[c] Rounded or flat edged irregularly shaped head (heads are not machined or trimmed).

duced by the normal cold heading process. Unless otherwise specified, rivets should have plain sheared ends that should be at right angles within 2 degrees to the axis of the rivet and be reasonably flat. When so specified by the user, rivets may have the standard header points shown on page 1485. Rivets may be made of ASTM Specification A31, Grade A steel; or may adhere to SAE Recommended Practice, Mechanical and Chemical Requirements for Nonthreaded Fasteners—SAE J430, Grade 0. When specified, rivets may be made of other materials.

ANSI/ASME B18.1.3M-1983 (R1995), Metric Small Solid Rivets, provides data for small, solid rivets with flat, round, and flat countersunk heads in metric dimensions. The main series of rivets has body diameters, in millimeters, of 1.6, 2, 2.5, 3, 4, 5, 6, 8, 10, and 12. A secondary series (nonpreferred) consists of sizes, 1, 1.2, 1.4, 3.5, 7, 9, and 11 millimeters.

British Standard Rivets

British Standard Rivets for General Engineering.— Dimensions in metric units of rivets for general engineering purposes are given in this British Standard, BS 4620;1970, which is based on ISO Recommendation ISO/R 1051. The snap head rivet dimensions of 14 millimeters and above are taken from the German Standard DIN 124, Round Head Rivets for Steel Structures. The shapes of heads have been restricted to those in common use in

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. American National Standard Large Rivets— *ANSI B18.1.2-1972 (R1995)*



Nom. Body Dia. *D*[a]	Head Dia. *A*		Height *H*		Head Dia. *A*		Height *H*	
	Mfd.[b]	Driven[c]	Mfd.[b]	Driven[c]	Mfd.[b]	Driven[c]	Mfd.[b, d]	Driven[c, d]
	Button Head				**High Button Head (Acorn)**			
½	0.875	0.922	0.375	0.344	0.781	0.875	0.500	0.375
⅝	1.094	1.141	0.469	0.438	0.969	1.062	0.594	0.453
¾	1.312	1.375	0.562	0.516	1.156	1.250	0.688	0.531
⅞	1.531	1.594	0.656	0.609	1.344	1.438	0.781	0.609
1	1.750	1.828	0.750	0.688	1.531	1.625	0.875	0.688
1⅛	1.969	2.062	0.844	0.781	1.719	1.812	0.969	0.766
1¼	2.188	2.281	0.938	0.859	1.906	2.000	1.062	0.844
1⅜	2.406	2.516	1.031	0.953	2.094	2.188	1.156	0.938
1½	2.625	2.734	1.125	1.031	2.281	2.375	1.250	1.000
1⅝	2.844	2.969	1.219	1.125	2.469	2.562	1.344	1.094
1¾	3.062	3.203	1.312	1.203	2.656	2.750	1.438	1.172
	Cone Head				**Pan Head**			
½	0.875	0.922	0.438	0.406	0.800	0.844	0.350	0.328
⅝	1.094	1.141	0.547	0.516	1.000	1.047	0.438	0.406
¾	1.312	1.375	0.656	0.625	1.200	1.266	0.525	0.484
⅞	1.531	1.594	0.766	0.719	1.400	1.469	0.612	0.578
1	1.750	1.828	0.875	0.828	1.600	1.687	0.700	0.656
1⅛	1.969	2.063	0.984	0.938	1.800	1.891	0.788	0.734
1¼	2.188	2.281	1.094	1.031	2.000	2.094	0.875	0.812
1⅜	2.406	2.516	1.203	1.141	2.200	2.312	0.962	0.906
1½	2.625	2.734	1.312	1.250	2.400	2.516	1.050	0.984
1⅝	2.844	2.969	1.422	1.344	2.600	2.734	1.138	1.062
1¾	3.062	3.203	1.531	1.453	2.800	2.938	1.225	1.141

[a] Tolerance for diameter of body is plus and minus from nominal and for ½-in. size equals +0.020, –0.022; for sizes ⅝ to 1-in., incl., equals +0.030, –0.025; for sizes 1⅛ and 1¼-in. equals +0.035; –0.027; for sizes 1⅜ and 1½-in. equals +0.040, –0.030; for sizes 1⅝ and 1¾-in. equals +0.040, –0.037.

[b] Note 1. Basic dimensions of head as manufactured. All dimensions are given in inches. The following formulas give the basic dimensions for manufactured shapes: *Button Head*, $A = 1.750D$; $H = 0.750D$; $G = 0.885\ D$. *High Button Head*, $A = 1.500D + 0.031$; $H = 0.750D + 0.125$; $F = 0.750D + 0.281$; $G = 0.750D - 0.281$. *Cone Head*, $A = 1.750D$; $B = 0.938D$; $H = 0.875D$. *Pan Head*, $A = 1.600D$; $B = 1.000D$; $H = 0.700D$. Length L is measured parallel to the rivet axis, from the extreme end to the bearing surface plane for flat bearing surface head type rivets, or to the intersection of the head top surface with the head diameter for countersunk head-type rivets.

[c] Note 2. Dimensions of manufactured head after driving and also of driven head.

[d] Note 3. Slight flat permissible within the specified head-height tolerance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1c. American National Standard Large Rivets *ANSI B18.1.2-1972 (R1995)*



Swell Neck

Swell Neck[a]						
Body Diameter *D*				Diameter Under Head *E*		Neck Length *K*[b]
Nominal[b]		Max.	Min.	Max. (Basic)	Min.	
½	0.500	0.520	0.478	0.563	0.543	0.250
⅝	0.625	0.655	0.600	0.688	0.658	0.312
¾	0.750	0.780	0.725	0.813	0.783	0.375
⅞	0.875	0.905	0.850	0.938	0.908	0.438
1	1.000	1.030	0.975	1.063	1.033	0.500
1⅛	1.125	1.160	1.098	1.188	1.153	0.562
1¼	1.250	1.285	1.223	1.313	1.278	0.625
1⅜	1.375	1.415	1.345	1.438	1.398	0.688
1½	1.500	1.540	1.470	1.563	1.523	0.750
1⅝	1.625	1.665	1.588	1.688	1.648	0.812
1¾	1.750	1.790	1.713	1.813	1.773	0.875

[a] The swell neck is applicable to all standard forms of large rivets except the flat countersunk and oval countersunk head types.

[b] All dimensions are given in inches. The following formulas give basic dimensions for manufactured shapes: *Swell Neck*, $E = D + 0.063$; $K = 0.500D$. Length *L* is measured parallel to the rivet axis, from the extreme end to the bearing surface plane for flat bearing surface head-type rivets. Basic dimension as manufactured. For tolerances see table footnote on page 1483.

American National Standard Dimensions for Hold-On (Dolly Bar) and Rivet Set Impression *ANSI B18.1.2-1972 (R1995)*


Button Head


High Button Head


Cone Head


Pan Head

Rivet Body Dia.[a]	Button Head			High Button Head				Cone Head			Pan Head		
	A′	*H′*	*G′*	*A′*	*H′*	*F′*	*G′*	*A′*	*B′*	*H′*	*A′*	*B′*	*H′*
½	0.906	0.312	0.484	0.859	0.344	0.562	0.375	0.891	0.469	0.391	0.812	0.500	0.297
⅝	1.125	0.406	0.594	1.047	0.422	0.672	0.453	1.109	0.594	0.484	1.031	0.625	0.375
¾	1.344	0.484	0.719	1.234	0.500	0.797	0.531	1.328	0.703	0.578	1.234	0.750	0.453
⅞	1.578	0.562	0.844	1.422	0.578	0.922	0.609	1.562	0.828	0.688	1.438	0.875	0.531
1	1.812	0.641	0.953	1.609	0.656	1.031	0.688	1.781	0.938	0.781	1.641	1.000	0.609
1⅛	2.031	0.719	1.078	1.797	0.719	1.156	0.766	2.000	1.063	0.875	1.844	1.125	0.688
1¼	2.250	0.797	1.188	1.984	0.797	1.266	0.844	2.219	1.172	0.969	2.047	1.250	0.766
1⅜	2.469	0.875	1.312	2.172	0.875	1.406	0.938	2.453	1.297	1.078	2.250	1.375	0.844
1½	2.703	0.953	1.438	2.344	0.953	1.500	1.000	2.672	1.406	1.172	2.453	1.500	0.906
1⅝	2.922	1.047	1.547	2.531	1.031	1.641	1.094	2.891	1.531	1.266	2.656	1.625	0.984
1¾	3.156	1.125	1.672	2.719	1.109	1.750	1.172	3.109	1.641	1.375	2.875	1.750	1.063

[a] All dimensions are given in inches.

the United Kingdom. Table 3b shows the rivet dimensions. Table 3a shows a tentative range of preferred nominal lengths as given in an appendix to the Standard. It is stated that these lengths will be reviewed in the light of usage. The rivets are made by cold or hot forging methods from mild steel, copper, brass, pure aluminum, aluminum alloys, or other suitable metal. It is stated that the radius under the head of a rivet shall run smoothly into the face of the head and shank without step or discontinuity.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2a. American National Standard Small Solid Rivets

ANSI/ASME B18.1.1-1972 (R1995) and Appendix



Truss Head Rivets



Coopers Rivets



$P = D \times 0.818$

$Q = D \times 0.25$

Point Dimensions

Truss Head Rivets[a]

Shank Dia.,[b] *D* Nominal		Head Dimensions: Dia., *A* Max.	Dia., *A* Min.	Height, *H* Max.	Height, *H* Min.	Rad. *R* Approx.	Shank Dia.,[b] *D* Nominal		Head Dimensions: Dia., *A* Max.	Dia., *A* Min.	Height, *H* Max.	Height, *H* Min.	Rad. *R* Approx.
3/32	0.094	0.226	0.206	0.038	0.026	0.239	9/32	0.281	0.661	0.631	0.103	0.085	0.706
1/8	0.125	0.297	0.277	0.048	0.036	0.314	5/16	0.312	0.732	0.702	0.113	0.095	0.784
5/32	0.156	0.368	0.348	0.059	0.045	0.392	11/32	0.344	0.806	0.776	0.124	0.104	0.862
3/16	0.188	0.442	0.422	0.069	0.055	0.470	3/8	0.375	0.878	0.848	0.135	0.115	0.942
7/32	0.219	0.515	0.495	0.080	0.066	0.555	13/32	0.406	0.949	0.919	0.145	0.123	1.028
1/4	0.250	0.590	0.560	0.091	0.075	0.628	7/16	0.438	1.020	0.990	0.157	0.135	1.098

[a] All dimensions in inches except where otherwise noted. Length tolerance of rivets is + or − .016 inch. Approximate proportions of rivets: $A = 2.300 \times D$, $H = 0.330 \times D$, $R = 2.512 \times D$.

[b] Tolerances on the nominal shank diameter in inches are given for the following body diameter ranges: 3/32 to 5/32, plus 0.002, minus 0.004; 3/16 to 1/4, plus 0.003, minus 0.006; 9/32 to 11/32, plus 0.004, minus 0.008; and 3/8 to 7/16, plus 0.005, minus 0.010.

Coopers Rivets

Size No.[a]	Shank Diameter, *D* Max.	Shank Diameter, *D* Min.	Head Diameter, *A* Max.	Head Diameter, *A* Min.	Head Height, *H* Max.	Head Height, *H* Min.	Point Dimensions[b] Dia., *P* Nom.	Point Dimensions[b] Length, *Q* Nom.	Length, *L* Max.	Length, *L* Min.
1 lb	0.111	0.105	0.291	0.271	0.045	0.031	Not Pointed		0.249	0.219
1¼ lb	0.122	0.116	0.324	0.302	0.050	0.036	Not Pointed		0.285	0.255
1½ lb	0.132	0.126	0.324	0.302	0.050	0.036	Not Pointed		0.285	0.255
1¾ lb	0.136	0.130	0.324	0.302	0.052	0.034	Not Pointed		0.318	0.284
2 lb	0.142	0.136	0.355	0.333	0.056	0.038	Not Pointed		0.322	0.288
3 lb	0.158	0.152	0.386	0.364	0.058	0.040	0.123	0.062	0.387	0.353
4 lb	0.168	0.159	0.388	0.362	0.058	0.040	0.130	0.062	0.418	0.388
5 lb	0.183	0.174	0.419	0.393	0.063	0.045	0.144	0.062	0.454	0.420
6 lb	0.206	0.197	0.482	0.456	0.073	0.051	0.160	0.094	0.498	0.457
7 lb	0.223	0.214	0.513	0.487	0.076	0.054	0.175	0.094	0.561	0.523
8 lb	0.241	0.232	0.546	0.516	0.081	0.059	0.182	0.094	0.597	0.559
9 lb	0.248	0.239	0.578	0.548	0.085	0.063	0.197	0.094	0.601	0.563
10 lb	0.253	0.244	0.578	0.548	0.085	0.063	0.197	0.094	0.632	0.594
12 lb	0.263	0.251	0.580	0.546	0.086	0.060	0.214	0.094	0.633	0.575
14 lb	0.275	0.263	0.611	0.577	0.091	0.065	0.223	0.094	0.670	0.612
16 lb	0.285	0.273	0.611	0.577	0.089	0.063	0.223	0.094	0.699	0.641
18 lb	0.285	0.273	0.642	0.608	0.108	0.082	0.230	0.125	0.749	0.691
20 lb	0.316	0.304	0.705	0.671	0.128	0.102	0.250	0.125	0.769	0.711
3/8 in.	0.380	0.365	0.800	0.762	0.136	0.106	0.312	0.125	0.840	0.778

[a] All dimensions in inches except where otherwise noted. Size numbers in pounds refer to the approximate weight of 1000 rivets.

[b] When specified American National Standard Small Solid Rivets may be obtained with points. Point dimensions for belt and coopers rivets are given in the accompanying tables. Formulas for calculating point dimensions of other rivets are given alongside the right diagram in Table 2a.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. American National Standard Small Solid Rivets

ANSI/ASME B18.1.1-1972 (R1995)

Tinners Rivets





Belt Rivets

Size No.[a]	Tinners Rivets: Shank Diameter, *E* Max.	Shank Diameter, *E* Min.	Head Dia., *A* Max.	Head Dia., *A* Min.	Head Height, *H* Max.	Head Height, *H* Min.	Length, *L* Nom.	Length, *L* Max.	Length, *L* Min.
6 oz.	0.081	0.075	0.213	0.193	0.028	0.016	1/8	0.135	0.115
8 oz.	0.091	0.085	0.225	0.205	0.036	0.024	5/32	0.166	0.146
10 oz.	0.097	0.091	0.250	0.230	0.037	0.025	11/64	0.182	0.162
12 oz.	0.107	0.101	0.265	0.245	0.037	0.025	3/16	0.198	0.178
14 oz.	0.111	0.105	0.275	0.255	0.038	0.026	3/16	0.198	0.178
1 lb	0.113	0.107	0.285	0.265	0.040	0.028	13/64	0.213	0.193
1 1/4 lb	0.122	0.116	0.295	0.275	0.045	0.033	7/32	0.229	0.209
1 1/2 lb	0.132	0.126	0.316	0.294	0.046	0.034	15/64	0.244	0.224
1 3/4 lb	0.136	0.130	0.331	0.309	0.049	0.035	1/4	0.260	0.240
2 lb	0.146	0.140	0.341	0.319	0.050	0.036	17/64	0.276	0.256
2 1/2 lb	0.150	0.144	0.311	0.289	0.069	0.055	9/32	0.291	0.271
3 lb	0.163	0.154	0.329	0.303	0.073	0.059	5/16	0.323	0.303
3 1/2 lb	0.168	0.159	0.348	0.322	0.074	0.060	21/64	0.338	0.318
4 lb	0.179	0.170	0.368	0.342	0.076	0.062	11/32	0.354	0.334
5 lb	0.190	0.181	0.388	0.362	0.084	0.070	3/8	0.385	0.365
6 lb	0.206	0.197	0.419	0.393	0.090	0.076	25/64	0.401	0.381
7 lb	0.223	0.214	0.431	0.405	0.094	0.080	13/32	0.416	0.396
8 lb	0.227	0.218	0.475	0.445	0.101	0.085	7/16	0.448	0.428
9 lb	0.241	0.232	0.490	0.460	0.103	0.087	29/64	0.463	0.443
10 lb	0.241	0.232	0.505	0.475	0.104	0.088	15/32	0.479	0.459
12 lb	0.263	0.251	0.532	0.498	0.108	0.090	1/2	0.510	0.490
14 lb	0.288	0.276	0.577	0.543	0.113	0.095	33/64	0.525	0.505
16 lb	0.304	0.292	0.597	0.563	0.128	0.110	17/32	0.541	0.521
18 lb	0.347	0.335	0.706	0.668	0.156	0.136	19/32	0.603	0.583

[a] All dimensions in inches. Size numbers refer to the approximate weight of 1000 rivets.

Size No.[b]	Belt Rivets[a]: Shank Diameter, *E* Max.	Shank Diameter, *E* Min.	Head Dia., *A* Max.	Head Dia., *A* Min.	Head Height, *H* Max.	Head Height, *H* Min.	Point Dimensions[c] Dia., *P* Nominal	Point Dimensions[c] Length, *Q* Nominal
14	0.085	0.079	0.260	0.240	0.042	0.030	0.065	0.078
13	0.097	0.091	0.322	0.302	0.051	0.039	0.073	0.078
12	0.111	0.105	0.353	0.333	0.054	0.040	0.083	0.078
11	0.122	0.116	0.383	0.363	0.059	0.045	0.097	0.078
10	0.136	0.130	0.417	0.395	0.065	0.047	0.109	0.094
9	0.150	0.144	0.448	0.426	0.069	0.051	0.122	0.094
8	0.167	0.161	0.481	0.455	0.072	0.054	0.135	0.094
7	0.183	0.174	0.513	0.487	0.075	0.056	0.151	0.125
6	0.206	0.197	0.606	0.580	0.090	0.068	0.165	0.125
5	0.223	0.214	0.700	0.674	0.105	0.083	0.185	0.125
4	0.241	0.232	0.921	0.893	0.138	0.116	0.204	0.141

[a] All dimensions in inches. Length tolerance on belt rivets is plus 0.031 inch, minus 0 inch.

[b] Size number refers to the Stub's iron wire gage number of the stock used in the shank of the rivet.

[c] *Note:* American National Standard Small Solid Rivets may be obtained with or without points. Point proportions are given in the diagram in Table 2a.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2c. American National Standard Small Solid Rivets *ANSI/ASME B18.1.1-1972 (R1995) and Appendix*



Shank Diameter				Flat Head[a]				Flat Countersunk Head[a]			Button Head[a]					Pan Head[a]						
				Head Dimensions																		
D		*E*		Dia., *A*		Height, *H*		Dia., *A* Sharp		Height[b] *H*	Dia., *A*		Height, *H*		Radius, *R*	Dia., *A*		Height, *H*		Radii		
Nominal		Max.	Min.	Max.	Min.	Max.	Min.	Max.[c]	Min.[d]	Ref.	Max.	Min.	Max.	Min.	Approx.	Max.	Min.	Max.	Min.	*R*1	*R*2	*R*3
																				Approximate		
1/16	0.062	0.064	0.059	0.140	0.120	0.027	0.017	0.118	0.110	0.027	0.122	0.102	0.052	0.042	0.055	0.118	0.098	0.040	0.030	0.019	0.052	0.217
3/32	0.094	0.096	0.090	0.200	0.180	0.038	0.026	0.176	0.163	0.040	0.182	0.162	0.077	0.065	0.084	0.173	0.153	0.060	0.048	0.030	0.080	0.326
1/8	0.125	0.127	0.121	0.260	0.240	0.048	0.036	0.235	0.217	0.053	0.235	0.215	0.100	0.088	0.111	0.225	0.205	0.078	0.066	0.039	0.106	0.429
5/32	0.156	0.158	0.152	0.323	0.301	0.059	0.045	0.293	0.272	0.066	0.290	0.268	0.124	0.110	0.138	0.279	0.257	0.096	0.082	0.049	0.133	0.535
3/16	0.188	0.191	0.182	0.387	0.361	0.069	0.055	0.351	0.326	0.079	0.348	0.322	0.147	0.133	0.166	0.334	0.308	0.114	0.100	0.059	0.159	0.641
7/32	0.219	0.222	0.213	0.453	0.427	0.080	0.065	0.413	0.384	0.094	0.405	0.379	0.172	0.158	0.195	0.391	0.365	0.133	0.119	0.069	0.186	0.754
1/4	0.250	0.253	0.244	0.515	0.485	0.091	0.075	0.469	0.437	0.106	0.460	0.430	0.196	0.180	0.221	0.444	0.414	0.151	0.135	0.079	0.213	0.858
9/32	0.281	0.285	0.273	0.579	0.545	0.103	0.085	0.528	0.491	0.119	0.518	0.484	0.220	0.202	0.249	0.499	0.465	0.170	0.152	0.088	0.239	0.963
5/16	0.312	0.316	0.304	0.641	0.607	0.113	0.095	0.588	0.547	0.133	0.572	0.538	0.243	0.225	0.276	0.552	0.518	0.187	0.169	0.098	0.266	1.070
11/32	0.344	0.348	0.336	0.705	0.667	0.124	0.104	0.646	0.602	0.146	0.630	0.592	0.267	0.247	0.304	0.608	0.570	0.206	0.186	0.108	0.292	1.176
3/8	0.375	0.380	0.365	0.769	0.731	0.135	0.115	0.704	0.656	0.159	0.684	0.646	0.291	0.271	0.332	0.663	0.625	0.225	0.205	0.118	0.319	1.286
13/32	0.406	0.411	0.396	0.834	0.790	0.146	0.124	0.763	0.710	0.172	0.743	0.699	0.316	0.294	0.358	0.719	0.675	0.243	0.221	0.127	0.345	1.392
7/16	0.438	0.443	0.428	0.896	0.852	0.157	0.135	0.823	0.765	0.186	0.798	0.754	0.339	0.317	0.387	0.772	0.728	0.261	0.239	0.137	0.372	1.500

[a] All dimensions in inches. Length tolerance of all rivets is plus or minus 0.016 inch. Approximate proportions of rivets: flat head, $A = 2.00 \times D$, $H = 0.33\ D$; flat countersunk head, $A = 1.850 \times D$, $H = 0.425 \times D$; button head, $A = 1.750 \times D$, $H = 0.750 \times D$, $R = 0.885 \times D$; pan head, $A = 1.720 \times D$, $H = 0.570 \times D$, $R1 = 0.314 \times D$, $R2 = 0.850 \times D$, $R3 = 3.430 \times D$. *Note:* ANSI Small Solid Rivets may be obtained with or without points. Point proportions are given in the diagram in Table 2a.

[b] Given for reference purposes only. Variations in this dimension are controlled by the head and shank diameters and the included angle of the head.

[c] Tabulated maximum values calculated on basic diameter of rivet and 92° included angle extended to a sharp edge.

[d] Minimum of rounded or flat-edged irregular-shaped head. Rivet heads are not machined or trimmed and the circumference may be irregular and edges rounded or flat.

Copyright 2004, Industrial Press, Inc., New York, NY

In this Standard, Tables 3a and 3b, the following definitions apply: 1) *Nominal diameter:* The diameter of the shank; 2) *Nominal length of rivets other than countersunk or raised countersunk rivets:* The length from the underside of the head to the end of the shank; 3) *Nominal length of countersunk and raised countersunk rivets:* The distance from the periphery of the head to the end of the rivet measured parallel to the axis of the rivet; and 4) *Manufactured head:* The head on the rivet as received from the manufacturer.

Table 3a. Tentative Range of Lengths for Rivets *Appendix to BS 4620:1970 (1998)*

Nom. Shank Dia.	Nominal Length																				
	3	4	5	6	8	10	12	14	16	(18)	20	(22)	25	(28)	30	(32)	35	(38)	40	45	...
1	d	d	d	d	d	d	d	d	d	...	d	...	...	...	...	...	...	...	...	...	...
1.2	d	d	d	d	d	d	d	d	d	...	d	...	...	...	...	...	...	...	...	...	...
1.6	d	d	d	d	d	d	d	d	d	d	...	d	d	...	...	...	...	...	...	...	...
2	d	d	d	d	d	d	d	d	d	...	d	d	d	...	...	...	...	...	...	...	...
2.5	d	d	d	d	d	d	d	d	d	d	...	d	d	...	...	...	...	...	...	...	...
3	...	d	d	d	d	d	d	d	d	d	d	d	d	...	...	...	...	...	...	...	...
(3.5)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
4	...	...	...	d	d	d	d	d	d	d	...	d	d	...	...	...	...	...	...	...	...
5	...	...	...	d	d	d	d	d	d	d	d	d	d	d	d	...	d	d	...	...	...
6	...	...	...	d	d	d	d	d	d	d	d	d	d	d	d	...	d	d	...	d	...

Nom. Shank Dia.	Nominal Length																				
	10	12	14	16	(18)	20	(22)	25	(28)	30	(32)	35	(38)	40	45	50	55	60	65	70	75
(7)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
8	d	d	d	d	d	d	d	d	d	d	...	d	d	...	d	d	...	...	...	...	...
10	...	...	d	d	d	d	d	d	d	d	...	d	d	d	d	d	...	...	...	...	...
12	...	...	...	...	...	...	...	d	...	d	...	d	...	d	...	d	d	...	...	...	d
(14)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
16	...	...	...	...	...	...	...	...	...	...	...	...	...	d	d	d	d	d	d	...	d

Nom. Shank Dia.	Nominal Length																				
	45	50	55	60	65	70	75	80	85	90	(95)	100	(105)	110	(115)	120	(125)	130	140	150	160
(18)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
20	d	...	...	d	...	d	...	d	...	...	...	...	...	...	...	...	...	...	...	...	...
(22)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
24	...	...	...	...	d	...	d	...	d	d	...	d	...	...	...	...	...	...	...	...	...
(27)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
30	...	...	...	...	...	...	...	...	d	d	...	d	...	d	...	d	...	...	...	...	...
(33)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
36	...	...	...	...	...	...	...	...	...	...	...	d	...	d	...	d	...	d	...	...	...
(39)	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	d	...	d	d	d	d

All dimensions are in millimeters.

Note: Sizes and lengths shown in parenthesis are nonpreferred and should be avoided if possible.

British Standard Small Rivets for General Purposes.— Dimensions of small rivets for general purposes are given in British Standard 641:1951 and are shown in Table 4 on page 1493. In addition, the standard lists the standard lengths of these rivets, gives the dimensions of washers to be used with countersunk head rivets (140°), indicates that the rivets may be made from mild steel, copper, brass, and a range of aluminum alloys and pure aluminum specified in B.S. 1473, and gives the dimensions of Coopers' flat head rivets ½ inch in diameter and below, in an appendix. In all types of rivets, except those with countersunk heads, there is a small radius or chamfer at the junction of the head and the shank.

British Standard Dimensions of Rivets (½ to 1¾ inch diameter).— The dimensions of rivets covered in BS 275:1927 (obsolescent) are given on page 1494 and do not apply to boiler rivets. With regard to this standard the terms "nominal diameter" and "standard diameter" are synonymous. The term "tolerance" refers to the variation from the nominal diameter of the rivet and not to the difference between the diameter under the head and the diameter near the point.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. British Standard Rivets for General Engineering Purposes
BS 4620:1970 (1998)



K = 0.43 *d **(for ref. only)** **†*K* = 0.5 *d*** **(for ref. only)**

Hot Forged Rivets

Nom. Shank Dia.[a] *d*	Tol. on Dia. *d*	60° Csk. and Raised Csk. Head		Snap Head		Universal Head			
		Head Dimensions							
		Nom. Dia. *D*	Height of Raise *W*	Nom. Dia. *D*	Nom. Depth *K*	Nom. Dia. *D*	Nom. Depth *K*	Rad. *R*	Rad. *r*
(14)	±0.43	21	2.8	22	9	28	5.6	42	8.4
16		24	3.2	25	10	32	6.4	48	9.6
(18)		27	3.6	28	11.5	36	7.2	54	11
20	±0.52	30	4.0	32	13	40	8.0	60	12
(22)		33	4.4	36	14	44	8.8	66	13
24		36	4.8	40	16	48	9.6	72	14
(27)	±0.62	40	5.4	43	17	54	10.8	81	16
30		45	6.0	48	19	60	12.0	90	18
(33)		50	6.6	53	21	66	13.2	99	20
36		55	7.2	58	23	72	14.4	108	22
(39)		59	7.8	62	25	78	15.6	117	23

Cold Forged Rivets

Nom. Shank Dia.[a] *d*	Tol. on Dia. *d*	90° Csk. Head	Snap Head		Universal Head				Flat Head	
		Head Dimensions								
		Nom. Dia. *D*	Nom. Dia. *D*	Nom. Dia. *K*	Nom. Dia. *D*	Nom. Depth *K*	Rad. *R*	Rad. *r*	Nom. Dia. *D*	Nom. Depth *K*
1	±0.07	2	1.8	0.6	2	0.4	3.0	0.6	2	0.25
1.2		2.4	2.1	0.7	2.4	0.5	3.6	0.7	2.4	0.3
1.6		3.2	2.8	1.0	3.2	0.6	4.8	1.0	3.2	0.4
2		4	3.5	1.2	4	0.8	6.0	1.2	4	0.5
2.5		5	4.4	1.5	5	1.0	7.5	1.5	5	0.6
3		6	5.3	1.8	6	1.2	9.0	1.8	6	0.8
(3.5)	±0.09	7	6.1	2.1	7	1.4	10.5	2.1	7	0.9
4		8	7	2.4	8	1.6	12	2.4	8	1.0
5		10	8.8	3.0	10	2.0	15	3.0	10	1.3
6		12	10.5	3.6	12	2.4	18	3.6	12	1.5
(7)	±0.11	14	12.3	4.2	14	2.8	21	4.2	14	1.8
8		16	14	4.8	16	3.2	24	4.8	16	2
10		20	18	6.0	20	4.0	30	6	20	2.5
12	±0.14	24	21	7.2	24	4.8	36	7.2	…	…
(14)		…	25	8.4	28	5.6	42	8.4	…	…
16		…	28	9.6	32	6.4	48	9.6	…	…

[a] All dimensions are in millimeters. Sizes shown in parentheses are nonpreferred.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. British Standard Small Rivets for General Purposes

BS 641:1951 (obsolescent)



Nom. Dia.[a]	Snap (or Round Head)			Mushroom Head			Flat Head		Countersunk Head (90°)		Countersunk Head (120°)	
	Head Dimensions											
D	Dia. *A*	Ht. *H*	Rad. *R*	Dia. *A*	Ht. *H*	Rad *R*	Dia. *A*	Ht. *H*	Dia. *A*	Ht. *H*	Dia. *A*	Ht. *H*
1/16	0.109	0.047	0.055	0.141	0.031	0.095	0.125	0.016	0.125	0.031	…	…
3/32	0.164	0.070	0.083	0.211	0.047	0.142	0.188	0.023	0.188	0.047	…	…
1/8	0.219	0.094	0.111	0.281	0.063	0.189	0.250	0.031	0.250	0.063	0.250	0.036
5/32	0.273	0.117	0.138	0.352	0.078	0.237	0.313	0.039	0.313	0.078	…	…
3/16	0.328	0.141	0.166	0.422	0.094	0.284	0.375	0.047	0.375	0.094	0.375	0.054
1/4	0.438	0.188	0.221	0.563	0.125	0.379	0.500	0.063	0.500	0.125	0.500	0.073
5/16	0.547	0.234	0.277	0.703	0.156	0.474	0.625	0.078	0.625	0.156	0.625	0.091
3/8	0.656	0.281	0.332	0.844	0.188	0.568	0.750	0.094	0.750	0.188	0.750	0.109
7/16	0.766	0.328	0.387	0.984	0.219	0.663	0.875	0.109	0.875	0.219	…	…



Nominal Diameter *D*		Pan Head		Countersunk Head (60°)		Countersunk Head (140°)			Countersunk Head Reaper		Snap (or Round) Head Reaper	
		Head Dimensions										
Inch	Gage No.[b]	Dia. *A*	Ht. *H*	Dia. *A*	Ht. *H*	Dia. *A*	Ht. *C*	Dia. *E*	Dia. *A*	Ht. *H*	Dia. *A*	Ht. *H*
0.104	12	…	…	…	…	0.286	0.042	0.082	…	…	…	…
0.116	11	…	…	…	…	0.319	0.046	0.092	…	…	…	…
0.128	10	…	…	…	…	0.352	0.051	0.101	…	…	…	…
0.144	9	…	…	…	…	0.396	0.058	0.114	…	…	…	…
0.160	8	…	…	…	…	0.440	0.064	0.126	…	…	…	…
0.176	7	…	…	…	…	0.484	0.070	0.139	…	…	…	…
3/16	…	0.300	0.131	0.328	0.122	…	…	…	…	…	…	…
0.192	6	…	…	…	…	0.528	0.077	0.152	0.317	0.062	0.307	0.115
0.202	…	…	…	…	…	…	…	…	0.333	0.066	0.323	0.121
0.212	5	…	…	…	…	0.583	0.085	0.167	0.350	0.069	0.339	0.127
0.232	4	…	…	…	…	0.638	0.093	0.183	0.383	0.075	0.371	0.139
1/4	…	0.400	0.175	0.438	0.162	0.688	0.100	0.198	…	…	…	…
0.252	3	…	…	…	…	…	…	…	0.416	0.082	0.403	0.151
5/16	…	0.500	0.219	0.547	0.203	0.859	0.125	0.247	…	…	…	…
3/8	…	0.600	0.263	0.656	0.244	10.031	0.150	0.296	…	…	…	…
7/16	…	0.700	0.306	0.766	0.284	…	…	…	…	…	…	…

[a] All dimensions in inches unless specified otherwise.

[b] Gage numbers are British Standard Wire Gage (S.W.G.) numbers.

Copyright 2004, Industrial Press, Inc., New York, NY

Head Dimensions and Diameters of British Standard Rivets

BS 275:1927 (obsolescent)



Nominal Rivet Diameter,[a] *D*	Shank Diameter[b]				
	At Position *X*[c]		At Position *Y*[c]		At Position *Z*[c]
	Minimum	Maximum	Minimum	Maximum	Minimum
1/2	1/2	17/32	31/64	1/2	31/64
9/16[d]	9/16	19/32	35/64	9/16	35/64
5/8	5/8	21/32	39/64	5/8	39/64
11/16[d]	11/16	23/32	43/64	11/16	43/64
3/4	3/4	25/32	47/64	3/4	47/64
13/16[d]	13/16	27/32	51/64	13/16	51/64
7/8	7/8	29/32	55/64	7/8	55/64
15/16[d]	15/16	31/32	59/64	15/16	59/64
1	1	1 1/32	63/64	1	63/64
1 1/16[d]	1 1/16	1 3/32	1 3/64	1 1/16	1 3/64
1 1/8	1 1/8	1 5/32	1 7/64	1 1/8	1 7/64
1 3/16[d]	1 3/16	1 7/32	1 11/64	1 3/16	1 11/64
1 1/4	1 1/4	1 9/32	1 15/64	1 1/4	1 15/64
1 5/16[d]	1 5/16	1 11/32	1 19/64	1 5/16	1 19/64
1 3/8	1 3/8	1 13/32	1 23/64	1 3/8	1 23/64
1 7/16[d]	1 7/16	1 15/32	1 27/64	1 7/16	1 27/64
1 1/2	1 1/2	1 17/32	1 31/64	1 1/2	1 31/64
1 9/16[d]	1 9/16	1 19/32	1 35/64	1 9/16	1 35/64
1 5/8	1 5/8	1 21/32	1 39/64	1 5/8	1 39/64
1 11/16[d]	1 11/16	1 23/32	1 43/64	1 11/16	1 43/64
1 3/4	1 3/4	1 25/32	1 47/64	1 3/4	1 47/64

[a] All dimensions that are tabulated are given in inches. This standard does not apply to Boiler Rivets

[b] Tolerances of the rivet diameter are as follows: at position *X*, plus 1/32 inch, minus zero; at position *Y*, plus zero, minus 1/64 inch; at position *Z*, minus 1/64 inch but in no case shall the difference between the diameters at positions *X* and *Y* exceed 1/32 inch, nor shall the diameter of the shank between positions *X* and *Y* be less than the minimum diameter specified at position *Y*.

[c] The location of positions *Y* and *Z* are as follows: Position *Y* is located 1/2*D* from the end of the rivet for rivet lengths 5 diameters long and under. For longer rivets, position *Y* is located 4 1/2 *D* from the head of the rivet. Position *Z* (found only on rivets longer than 5*D*) is located 1/2*D* from the end of the rivet.

[d] At the recommendation of the British Standards Institution, these sizes are to be dispensed with wherever possible.

Copyright 2004, Industrial Press, Inc., New York, NY

TORQUE AND TENSION IN FASTENERS

Tightening Bolts: Bolts are often tightened by applying torque to the head or nut, which causes the bolt to stretch. The stretching results in bolt tension or preload, which is the force that holds a joint together. Torque is relatively easy to measure with a torque wrench, so it is the most frequently used indicator of bolt tension. Unfortunately, a torque wrench does not measure bolt tension accurately, mainly because it does not take friction into account. The friction depends on bolt, nut, and washer material, surface smoothness, machining accuracy, degree of lubrication, and the number of times a bolt has been installed. Fastener manufacturers often provide information for determining torque requirements for tightening various bolts, accounting for friction and other effects. If this information is not available, the methods described in what follows give general guidelines for determining how much tension should be present in a bolt, and how much torque may need to be applied to arrive at that tension.

High preload tension helps keep bolts tight, increases joint strength, creates friction between parts to resist shear, and improves the fatigue resistance of bolted connections. The recommended preload F_i, which can be used for either static (stationary) or fatigue (alternating) applications, can be determined from: $F_i = 0.75 \times A_t \times S_p$ for reusable connections, and $F_i = 0.9 \times A_t \times S_p$ for permanent connections. In these formulas, F_i is the bolt preload, A_t is the tensile stress area of the bolt, and S_p is the proof strength of the bolt. Determine A_t from screw-thread tables or by means of formulas in this section. Proof strength S_p of commonly used ASTM and SAE steel fasteners is given in this section and in the section on metric screws and bolts for those fasteners. For other materials, an approximate value of proof strength can be obtained from: $S_p = 0.85 \times S_y$, where S_y is the yield strength of the material. Soft materials should not be used for threaded fasteners.

Once the required preload has been determined, one of the best ways to be sure that a bolt is properly tensioned is to measure its tension directly with a strain gage. Next best is to measure the change in length (elongation) of the bolt during tightening, using a micrometer or dial indicator. Each of the following two formulas calculates the required change in length of a bolt needed to make the bolt tension equal to the recommended preload. The change in length δ of the bolt is given by:

$$\delta = F_i \times \frac{A_d \times l_t + A_t \times l_d}{A_d \times A_t \times E} \quad (1) \qquad \text{or} \qquad \delta = \frac{F_i \times l}{A \times E} \quad (2)$$

In Equation (1), F_i is the bolt preload; A_d is the major-diameter area of the bolt; A_t is the tensile-stress area of the bolt; E is the bolt modulus of elasticity; l_t is the length of the threaded portion of the fastener within the grip; and l_d is the length of the unthreaded portion of the grip. Here, the grip is defined as the total thickness of the clamped material. Equation (2) is a simplified formula for use when the area of the fastener is constant, and gives approximately the same results as Equation (1). In Equation (2), l is the bolt length; A is the bolt area; and δ, F_i, and E are as described before.

If measuring bolt elongation is not possible, the torque necessary to tighten the bolt must be estimated. If the recommended preload is known, use the following general relation for the torque: $T = K \times F_i \times d$, where T is the wrench torque, K is a constant that depends on the bolt material and size, F_i is the preload, and d is the nominal bolt diameter. A value of K = 0.2 may be used in this equation for mild-steel bolts in the size range of ¼ to 1 inch. For other steel bolts, use the following values of K: nonplated black finish, 0.3; zinc-plated, 0.2; lubricated, 0.18; cadmium-plated, 0.16. Check with bolt manufacturers and suppliers for values of K to use with bolts of other sizes and materials.

Copyright 2004, Industrial Press, Inc., New York, NY

The proper torque to use for tightening bolts in sizes up to about ½ inch may also be determined by trial. Test a bolt by measuring the amount of torque required to fracture it (use bolt, nut, and washers equivalent to those chosen for the real application). Then, use a tightening torque of about 50 to 60 per cent of the fracture torque determined by the test. The tension in a bolt tightened using this procedure will be about 60 to 70 per cent of the elastic limit (yield strength) of the bolt material.

The table that follows can be used to get a rough idea of the torque necessary to properly tension a bolt by using the bolt diameter d and the coefficients b and m from the table; the approximate tightening torque T in ft-lb for the listed fasteners is obtained by solving the equation $T = 10^{b+m \log d}$. This equation is approximate, for use with unlubricated fasteners as supplied by the mill. See the notes at the end of the table for more details on using the equation.

Wrench Torque $T = 10^{b+m \log d}$ for Steel Bolts, Studs, and Cap Screws (*see notes*)

Fastener Grade(s)	Bolt Diameter d (in.)	m	b
SAE 2, ASTM A307	¼ to 3	2.940	2.533
SAE 3	¼ to 3	3.060	2.775
ASTM A-449, A-354-BB, SAE 5	¼ to 3	2.965	2.759
ASTM A-325[a]	½ to 1½	2.922	2.893
ASTM A-354-BC	¼ to ⅝	3.046	2.837
SAE 6, SAE 7	¼ to 3	3.095	2.948
SAE 8	¼ to 3	3.095	2.983
ASTM A-354-BD, ASTM A490[a]	⅜ to 1¾	3.092	3.057
Socket Head Cap Screws	¼ to 3	3.096	3.014

[a] Values for permanent fastenings on steel structures.

Usage: Values calculated using the preceding equation are for standard, unplated industrial fasteners as received from the manufacturer; for cadmium-plated cap screws, multiply the torque by 0.9; for cadmium-plated nuts and bolts, multiply the torque by 0.8; for fasteners used with special lubricants, multiply the torque by 0.9; for studs, use cap screw values for equivalent grade.

Preload for Bolts in Loaded Joints.— The following recommendations are based on MIL-HDBK-60, a subsection of FED-STD-H28, Screw Thread Standards for Federal Service. Generally, bolt preload in joints should be high enough to maintain joint members in contact and in compression. Loss of compression in a joint may result in leakage of pressurized fluids past compression gaskets, loosening of fasteners under conditions of cyclic loading, and reduction of fastener fatigue life.

The relationship between fastener fatigue life and fastener preload is illustrated by Fig. 1. An axially loaded bolted joint in which there is no bolt preload is represented by line OAB, that is, the bolt load is equal to the joint load. When joint load varies between P_a and P_b, the bolt load varies accordingly between P_{Ba} and P_{Bb}. However, if preload P_{B1} is applied to the bolt, the joint is compressed and bolt load changes more slowly than the joint load (indicated by line P_{B1}A, whose slope is less than line OAB) because some of the load is absorbed as a reduction of compression in the joint. Thus, the axial load applied to the joint varies between $P_{Ba'}$ and $P_{Bb'}$ as joint load varies between P_a and P_b. This condition results in a considerable reduction in cyclic bolt-load variation and thereby increases the fatigue life of the fastener.

Preload for Bolts In Shear.— In shear-loaded joints, with members that slide, the joint members transmit shear loads to the fasteners in the joint and the preload must be sufficient to hold the joint members in contact. In joints that do not slide (i.e., there is no relative motion between joint members), shear loads are transmitted within the joint by frictional forces that mainly result from the preload. Therefore, preload must be great enough for the resulting friction forces to be greater than the applied shear force. With high applied shear loads, the shear stress induced in the fastener during application of the preload must also be

Copyright 2004, Industrial Press, Inc., New York, NY

considered in the bolted-joint design. Joints with combined axial and shear loads must be analyzed to ensure that the bolts will not fail in either tension or shear.



Fig. 1. Bolt Load in a Joint with Applied Axial Load

General Application of Preload.— Preload values should be based on joint requirements, as outlined before. Fastener applications are generally designed for maximum utilization of the fastener material; that is to say, the fastener size is the minimum required to perform its function and a maximum safe preload is generally applied to it. However, if a low-strength fastener is replaced by one of higher strength, for the sake of convenience or standardization, the preload in the replacement should not be increased beyond that required in the original fastener.

To utilize the maximum amount of bolt strength, bolts are sometimes tightened to or beyond the yield point of the material. This practice is generally limited to ductile materials, where there is considerable difference between the yield strength and the ultimate (breaking) strength, because low-ductility materials are more likely to fail due to unexpected overloads when preloaded to yield. Joints designed for primarily static load conditions that use ductile bolts, with a yield strain that is relatively far from the strain at fracture, are often preloaded above the yield point of the bolt material. Methods for tightening up to and beyond the yield point include tightening by feel without special tools, and the use of electronic equipment designed to compare the applied torque with the angular rotation of the fastener and detect changes that occur in the elastic properties of fasteners at yield.

Bolt loads are maintained below the yield point in joints subjected to cyclic loading and in joints using bolts of high-strength material where the yield strain is close to the strain at fracture. For these conditions, the maximum preloads generally fall within the following ranges: 50 to 80 per cent of the minimum tensile ultimate strength; 75 to 90 per cent of the minimum tensile yield strength or proof load; or 100 per cent of the observed proportional limit or onset of yield.

Bolt heads, driving recesses (in socket screws, for example), and the juncture of head and shank must be sufficiently strong to withstand the preload and any additional stress encountered during tightening. There must also be sufficient thread to prevent stripping (generally, at least three fully engaged threads). Materials susceptible to stress-corrosion cracking may require further preload limitations.

Copyright 2004, Industrial Press, Inc., New York, NY

Preload Adjustments.— Preloads may be applied directly by axial loading or indirectly by turning of the nut or bolt. When preload is applied by turning of nuts or bolts, a torsion load component is added to the desired axial bolt load. This combined loading increases the tensile stress on the bolt. It is frequently assumed that the additional torsion load component dissipates quickly after the driving force is removed and, therefore, can be largely ignored. This assumption may be reasonable for fasteners loaded near to or beyond yield strength, but for critical applications where bolt tension must be maintained below yield, it is important to adjust the axial tension requirements to include the effects of the preload torsion. For this adjustment, the combined tensile stress (*von Mises* stress) F_{tc} in psi (MPa) can be calculated from the following:

$$F_{tc} = \sqrt{F_t^2 + 3F_s^2} \tag{3}$$

where F_t is the axial applied tensile stress in psi (MPa), and F_s is the shear stress in psi (MPa) caused by the torsion load application.

Some of the torsion load on a bolt, acquired when applying a preload, may be released by springback when the wrenching torque is removed. The amount of relaxation depends on the friction under the bolt head or nut. With controlled back turning of the nut, the torsional load may be reduced or eliminated without loss of axial load, reducing bolt stress and lowering creep and fatigue potential. However, calculation and control of the back-turn angle is difficult, so this method has limited application and cannot be used for short bolts because of the small angles involved.

For relatively soft work-hardenable materials, tightening bolts in a joint slightly beyond yield will work-harden the bolt to some degree. Back turning of the bolt to the desired tension will reduce embedment and metal flow and improve resistance to preload loss.

The following formula for use with single-start Unified inch screw threads calculates the combined tensile stress, F_{tc}:

$$F_{tc} = F_t\sqrt{1 + 3\left(\frac{1.96 + 2.31\mu}{1 - 0.325P/d_2} - 1.96\right)^2} \tag{4}$$

Single-start UNJ screw threads in accordance with MIL-S-8879 have a thread stress diameter equal to the bolt pitch diameter. For these threads, F_{tc} can be calculated from:

$$F_{tc} = F_t\sqrt{1 + 3\left(\frac{0.637P}{d_2} + 2.31\mu\right)^2} \tag{5}$$

where μ is the coefficient of friction between threads, P is the thread pitch ($P = 1/n$, and n is the number of threads per inch), and d_2 is the bolt-thread pitch diameter in inches. Both Equations (2) and (3) are derived from Equation (1); thus, the quantity within the radical ($\sqrt{\ }$) represents the proportion of increase in axial bolt tension resulting from preload torsion. In these equations, tensile stress due to torsion load application becomes most significant when the thread friction, μ, is high.

Coefficients of Friction for Bolts and Nuts.— Table 1 gives examples of coefficients of friction that are frequently used in determining torque requirements. Dry threads, indicated by the words "None added" in the Lubricant column, are assumed to have some residual machine oil lubrication. Table 1 values are not valid for threads that have been cleaned to remove all traces of lubrication because the coefficient of friction of these threads may be very much higher unless a plating or other film is acting as a lubricant.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Coefficients of Friction of Bolts and Nuts

Bolt/Nut Materials	Lubricant	Coefficient of Friction, μ ± 20%
Steel[a]	Graphite in petrolatum or oil	0.07
	Molybdenum disulfide grease	0.11
	Machine oil	0.15
Steel,[a] cadmium-plated	None added	0.12
Steel,[a] zinc-plated	None added	0.17
Steel[a]/bronze	None added	0.15
Corrosion-resistant steel or nickel-base alloys/silver-plated materials	None added	0.14
Titanium/steel[a]	Graphite in petrolatum	0.08
Titanium	Molybdenum disulfide grease	0.10

[a] "Steel" includes carbon and low-alloy steels but not corrosion-resistant steels.

Where two materials are separated by a slash (/), either may be the bolt material; the other is the nut material.

Preload Relaxation.— Local yielding, due to excess bearing stress under nuts and bolt heads (caused by high local spots, rough surface finish, and lack of perfect squareness of bolt and nut bearing surfaces), may result in preload relaxation after preloads are first applied to a bolt. Bolt tension also may be unevenly distributed over the threads in a joint, so thread deformation may occur, causing the load to be redistributed more evenly over the threaded length. Preload relaxation occurs over a period of minutes to hours after the application of the preload, so retightening after several minutes to several days may be required. As a general rule, an allowance for loss of preload of about 10 per cent may be made when designing a joint.

Increasing the resilience of a joint will make it more resistant to local yielding, that is, there will be less loss of preload due to yielding. When practical, a joint-length to bolt-diameter ratio of 4 or more is recommended (e.g., a ¼-inch bolt and a 1-inch or greater joint length). Through bolts, far-side tapped holes, spacers, and washers can be used in the joint design to improve the joint-length to bolt-diameter ratio.

Over an extended period of time, preload may be reduced or completely lost due to vibration; temperature cycling, including changes in ambient temperature; creep; joint load; and other factors. An increase in the initial bolt preload or the use of thread-locking methods that prevent relative motion of the joint may reduce the problem of preload relaxation due to vibration and temperature cycling. Creep is generally a high-temperature effect, although some loss of bolt tension can be expected even at normal temperatures. Harder materials and creep-resistant materials should be considered if creep is a problem or high-temperature service of the joint is expected.

The mechanical properties of fastener materials vary significantly with temperature, and allowance must be made for these changes when ambient temperatures range beyond 30 to 200°F. Mechanical properties that may change include tensile strength, yield strength, and modulus of elasticity. Where bolts and flange materials are generically dissimilar, such as carbon steel and corrosion-resistant steel or steel and brass, differences in thermal expansion that might cause preload to increase or decrease must be taken into consideration.

Methods of Applying and Measuring Preload.— Depending on the tightening method, the accuracy of preload application may vary up to 25 per cent or more. Care must be taken to maintain the calibration of torque and load indicators. Allowance should be made for uncertainties in bolt load to prevent overstressing the bolts or failing to obtain sufficient preload. The method of tensioning should be based on the required accuracy and relative costs.

Copyright 2004, Industrial Press, Inc., New York, NY

The most common methods of bolt tension control are indirect because it is usually difficult or impractical to measure the tension produced in each fastener during assembly. Table 2 lists the most frequently used methods of applying bolt preload and the approximate accuracy of each method. For many applications, fastener tension can be satisfactorily controlled within certain limits by applying a known torque to the fastener. Laboratory tests have shown that whereas a satisfactory torque tension relationship can be established for a given set of conditions, a change of any of the variables, such as fastener material, surface finish, and the presence or absence of lubrication, may severely alter the relationship. Because most of the applied torque is absorbed in intermediate friction, a change in the surface roughness of the bearing surfaces or a change in the lubrication will drastically affect the friction and thus the torque tension relationship. Regardless of the method or accuracy of applying the preload, tension will decrease in time if the bolt, nut, or washer seating faces deform under load, if the bolt stretches or creeps under tensile load, or if cyclic loading causes relative motion between joint members.

Table 2. Accuracy of Bolt Preload Application Methods

Method	Accuracy	Method	Accuracy
By feel	±35%	Computer-controlled wrench	
Torque wrench	±25%	below yield (turn-of-nut)	±15%
Turn-of-nut	±15%	yield-point sensing	±8%
Preload indicating washer	±10%	Bolt elongation	±3–5%
Strain gages	±1%	Ultrasonic sensing	±1%

Tightening methods using power drivers are similar in accuracy to equivalent manual methods.

Elongation Measurement.— Bolt elongation is directly proportional to axial stress when the applied stress is within the elastic range of the material. If both ends of a bolt are accessible, a micrometer measurement of bolt length made before and after the application of tension will ensure the required axial stress is applied. The elongation δ in inches (mm) can be determined from the formula $\delta = F_t \times L_B \div E$, given the required axial stress F_t in psi (MPa), the bolt modulus of elasticity E in psi (MPa), and the effective bolt length L_B in inches (mm). L_B, as indicated in Fig. 2, includes the contribution of bolt area and ends (head and nut) and is calculated from:

$$L_B = \left(\frac{d_{ts}}{d}\right)^2 \times \left(L_s + \frac{H_B}{2}\right) + L_J - L_S + \frac{H_N}{2} \qquad (6)$$

where d_{ts} is the thread stress diameter, d is the bolt diameter, L_s is the unthreaded length of the bolt shank, L_j is the overall joint length, H_B is the height of the bolt head, and H_N is the height of the nut.



Fig. 2. Effective Length Applicable in Elongation Formulas

Copyright 2004, Industrial Press, Inc., New York, NY

The micrometer method is most easily and accurately applied to bolts that are essentially uniform throughout the bolt length, that is, threaded along the entire length or that have only a few threads in the bolt grip area. If the bolt geometry is complex, such as tapered or stepped, the elongation is equal to the sum of the elongations of each section with allowances made for transitional stresses in bolt head height and nut engagement length.

The direct method of measuring elongation is practical only if both ends of a bolt are accessible. Otherwise, if the diameter of the bolt or stud is sufficiently large, an axial hole can be drilled, as shown in Fig. 3, and a micrometer depth gage or other means used to determine the change in length of the hole as the fastener is tightened. A similar method uses a special indicating bolt that has a blind axial hole containing a pin fixed at the bottom. The pin is usually made flush with the bolt head surface before load application. As the bolt is loaded, the elongation causes the end of the pin to move below the reference surface. The displacement of the pin can be converted directly into unit stress by means of a calibrated gage. In some bolts of this type, the pin is set a distance above the bolt so that the pin is flush with the bolt head when the required axial load is reached.



Fig. 3. Hole Drilled to Measure Elongation When One End of Stud or Bolt Is Not Accessible

The *ultrasonic method* of measuring elongation uses a sound pulse, generated at one end of a bolt, that travels the length of a bolt, bounces off the far end, and returns to the sound generator in a measured period of time. The time required for the sound pulse to return depends on the length of the bolt and the speed of sound in the bolt material. The speed of sound in the bolt depends on the material, the temperature, and the stress level. The ultrasonic measurement system can compute the stress, load, or elongation of the bolt at any time by comparing the pulse travel time in the loaded and unstressed conditions. In a similar method, measuring round-trip transit times of longitudinal and shear wave sonic pulses allows calculation of tensile stress in a bolt without consideration of bolt length. This method permits checking bolt tension at any time and does not require a record of the ultrasonic characteristics of each bolt at zero load.

To ensure consistent results, the ultrasonic method requires that both ends of the bolt be finished square to the bolt axis. The accuracy of ultrasonic measurement compares favorably with strain gage methods, but is limited by sonic velocity variations between bolts of the same material and by corrections that must be made for unstressed portions of the bolt heads and threads.

The *turn-of-nut method* applies preload by turning a nut through an angle that corresponds to a given elongation. The elongation of the bolt is related to the angle turned by the formula: $\delta_B = \theta \times l \div 360$, where δ_B is the elongation in inches (mm), θ is the turn angle of the nut in degrees, and l is the lead of the thread helix in inches (mm). Substituting $F_t \times L_B \div E$ for elongation δ_B in this equation gives the turn-of-nut angle required to attain preload F_t:

$$\theta = 360\frac{F_t L_B}{El} \tag{7}$$

where L_B is given by Equation (6), and E is the modulus of elasticity.

Accuracy of the turn-of-nut method is affected by elastic deformation of the threads, by roughness of the bearing surfaces, and by the difficulty of determining the starting point for measuring the angle. The starting point is usually found by tightening the nut enough to seat the contact surfaces firmly, and then loosening it just enough to release any tension and twisting in the bolt. The nut-turn angle will be different for each bolt size, length, mate-

Copyright 2004, Industrial Press, Inc., New York, NY

rial, and thread lead. The preceding method of calculating the nut-turn angle also requires elongation of the bolt without a corresponding compression of the joint material. The turn-of-nut method, as just outlined, is not valid for joints with compressible gaskets or other soft material, or if there is a significant deformation of the nut and joint material relative to that of the bolt. The nut-turn angle would then have to be determined empirically using a simulated joint and a tension-measuring device.

The Japanese Industrial Standards (JIS) Handbook, *Fasteners and Screw Threads,* indicates that the turn-of-nut tightening method is applicable in both elastic and plastic region tightening. Refer to JIS B 1083 for more detail on this subject.

Heating causes a bolt to expand at a rate proportional to its coefficient of expansion. When a hot bolt and nut are fastened in a joint and cooled, the bolt shrinks and tension is developed. The temperature necessary to develop an axial stress, F_t, (when the stress is below the elastic limit) can be found as follows:

$$T = \frac{F_t}{Ee} + T_o \tag{8}$$

In this equation, T is the temperature in degrees Fahrenheit needed to develop the axial tensile stress F_t in psi, E is the bolt material modulus of elasticity in psi, e is the coefficient of linear expansion in in./in.-°F, and T_o is the temperature in degrees Fahrenheit to which the bolt will be cooled. $T - T_o$ is, therefore, the temperature change of the bolt. In finite-element simulations, heating and cooling are frequently used to preload mesh elements in tension or compression. Equation (8) can be used to determine required temperature changes in such problems.

Example: A tensile stress of 40,000 psi is required for a steel bolt in a joint operating at 70°F. If E is 30×10^6 psi and e is 6.2×10^{-6} in./in.-°F, determine the temperature of the bolt needed to develop the required stress on cooling.

$$T = \frac{40{,}000}{(30 \times 10^6)(6.2 \times 10^{-6})} + 70 = 285°\text{F}$$

In practice, the bolt is heated slightly above the required temperature (to allow for some cooling while the nut is screwed down) and the nut is tightened snugly. Tension develops as the bolt cools. In another method, the nut is tightened snugly on the bolt, and the bolt is heated in place. When the bolt has elongated sufficiently, as indicated by inserting a thickness gage between the nut and the bearing surface of the joint, the nut is tightened. The bolt develops the required tension as it cools; however, preload may be lost if the joint temperature increases appreciably while the bolt is being heated.

Calculating Thread Tensile-Stress Area.— The tensile-stress area for Unified threads is based on a diameter equivalent to the mean of the pitch and minor diameters. The pitch and the minor diameters for Unified screw threads can be found from the major (nominal) diameter, d, and the screw pitch, $P = 1/n$, where n is the number of threads per inch, by use of the following formulas: the pitch diameter $d_p = d - 0.649519 \times P$; the minor diameter $d_m = d - 1.299038 \times P$. The tensile stress area, A_s, for Unified threads can then be found as follows:

$$A_s = \frac{\pi}{4}\left(\frac{d_m + d_p}{2}\right)^2 \tag{9}$$

UNJ threads in accordance with MIL-S-8879 have a tensile thread area that is usually considered to be at the basic bolt pitch diameter, so for these threads, $A_s = \pi d_p^2/4$. The tensile stress area for Unified screw threads is smaller than this area, so the required tightening torque for UNJ threaded bolts is greater than for an equally stressed Unified threaded bolt

Copyright 2004, Industrial Press, Inc., New York, NY

in an equivalent joint. To convert tightening torque for a Unified fastener to the equivalent torque required with a UNJ fastener, use the following relationship:

$$\text{UNJ}_{\text{torque}} = \left(\frac{d \times n - 0.6495}{d \times n - 0.9743}\right)^2 \times \text{Unified}_{\text{torque}} \quad (10)$$

where d is the basic thread major diameter, and n is the number of threads per inch.

The tensile stress area for metric threads is based on a diameter equivalent to the mean of the pitch diameter and a diameter obtained by subtracting $\frac{1}{6}$ the height of the fundamental thread triangle from the external-thread minor diameter. The Japanese Industrial Standard JIS B 1082 (see also ISO 898/1) defines the stress area of metric screw threads as follows:

$$A_s = \frac{\pi}{4}\left(\frac{d_2 + d_3}{2}\right)^2 \quad (11)$$

In Equation (11), A_s is the stress area of the metric screw thread in mm^2; d_2 is the pitch diameter of the external thread in mm, given by $d_2 = d - 0.649515 \times P$; and d_3 is defined by $d_3 = d_1 - H/6$. Here, d is the nominal bolt diameter; P is the thread pitch; $d_1 = d - 1.082532 \times P$ is the minor diameter of the external thread in mm; and $H = 0.866025 \times P$ is the height of the fundamental thread triangle. Substituting the formulas for d_2 and d_3 into Equation (11) results in $A_s = 0.7854(d - 0.9382P)^2$.

The stress area, A_s, of Unified threads in mm^2 is given in JIS B 1082 as:

$$A_s = 0.7854\left(d - \frac{0.9743}{n} \times 25.4\right)^2 \quad (12)$$

Relation between Torque and Clamping Force.— The Japanese Industrial Standard JIS B 1803 defines fastener tightening torque T_f as the sum of the bearing surface torque T_w and the shank (threaded) portion torque T_s. The relationship between the applied tightening torque and bolt preload F_{ft} is as follows: $T_f = T_s + T_w = K \times F_f \times d$. In the preceding, d is the nominal diameter of the screw thread, and K is the torque coefficient defined as follows:

$$K = \frac{1}{2d}\left(\frac{P}{\pi} + \mu_s d_2 \sec\alpha' + \mu_w D_w\right) \quad (13)$$

where P is the screw thread pitch; μ_s is the coefficient of friction between threads; d_2 is the pitch diameter of the thread; μ_w is the coefficient of friction between bearing surfaces; D_w is the equivalent diameter of the friction torque bearing surfaces; and α' is the flank angle at the ridge perpendicular section of the thread ridge, defined by $\tan\alpha' = \tan\alpha \cos\beta$, where α is the thread half angle (30°, for example), and β is the thread helix, or lead, angle. β can be found from $\tan\beta = l \div 2\pi r$, where l is the thread lead, and r is the thread radius (i.e., one-half the nominal diameter d). When the bearing surface contact area is circular, D_w can be obtained as follows:

$$D_w = \frac{2}{3} \times \frac{D_o^3 - D_i^3}{D_o^2 - D_i^2} \quad (14)$$

where D_o and D_i are the outside and inside diameters, respectively, of the bearing surface contact area.

The torques attributable to the threaded portion of a fastener, T_s, and bearing surfaces of a joint, T_w, are as follows:

$$T_s = \frac{F_f}{2}\left(\frac{P}{\pi} + \mu_s d_2 \sec\alpha'\right) \quad (15) \qquad T_w = \frac{F_f}{2}\mu_w D_w \quad (16)$$

Copyright 2004, Industrial Press, Inc., New York, NY

where $F_f, P, \mu, d_2, \alpha', \mu_w$, and D_w are as previously defined.

Tables 3 and 4 give values of torque coefficient K for coarse- and fine-pitch metric screw threads corresponding to various values of μ_s and μ_w. When a fastener material yields according to the shearing-strain energy theory, the torque corresponding to the yield clamping force (see Fig. 4) is $T_{fy} = K \times F_{fy} \times d$, where the yield clamping force F_{fy} is given by:

$$F_{fy} = \frac{\sigma_y A_s}{\sqrt{1 + 3\left[\frac{2}{d_A}\left(\frac{P}{\pi} + \mu_s d_2 \sec\alpha'\right)\right]^2}} \quad (17)$$

Table 3. Torque Coefficients *K* for Metric Hexagon Head Bolt and Nut Coarse Screw Threads

Between Threads, μ_s	Coefficient of Friction, Between Bearing Surfaces, μ_w									
	0.08	0.10	0.12	0.15	0.20	0.25	0.30	0.35	0.40	0.45
0.08	0.117	0.130	0.143	0.163	0.195	0.228	0.261	0.293	0.326	0.359
0.10	0.127	0.140	0.153	0.173	0.206	0.239	0.271	0.304	0.337	0.369
0.12	0.138	0.151	0.164	0.184	0.216	0.249	0.282	0.314	0.347	0.380
0.15	0.153	0.167	0.180	0.199	0.232	0.265	0.297	0.330	0.363	0.396
0.20	0.180	0.193	0.206	0.226	0.258	0.291	0.324	0.356	0.389	0.422
0.25	0.206	0.219	0.232	0.252	0.284	0.317	0.350	0.383	0.415	0.448
0.30	0.232	0.245	0.258	0.278	0.311	0.343	0.376	0.409	0.442	0.474
0.35	0.258	0.271	0.284	0.304	0.337	0.370	0.402	0.435	0.468	0.500
0.40	0.285	0.298	0.311	0.330	0.363	0.396	0.428	0.461	0.494	0.527
0.45	0.311	0.324	0.337	0.357	0.389	0.422	0.455	0.487	0.520	0.553

Values in the table are average values of torque coefficient calculated using: Equations (13) and (14) for K and D_w; diameters d of 4, 5, 6, 8, 10, 12, 16, 20, 24, 30, and 36 mm; and selected corresponding pitches P and pitch diameters d_2 according to JIS B 0205 (ISO 724) thread standard. Dimension D_i was obtained for a Class 2 fit without chamfer from JIS B 1001, Diameters of Clearance Holes and Counterbores for Bolts and Screws (equivalent to ISO 273-1979). The value of D_o was obtained by multiplying the reference dimension from JIS B 1002, width across the flats of the hexagon head, by 0.95.



Fig. 4. The Relationship between Bolt Elongation and Axial Tightening Tension

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Torque Coefficients *K* for Metric Hexagon Head Bolt and Nut Fine-Screw Threads

Between Threads, μ_s	Coefficient of Friction: Between Bearing Surfaces, μ_w									
	0.08	0.10	0.12	0.15	0.20	0.25	0.30	0.35	0.40	0.45
0.08	0.106	0.118	0.130	0.148	0.177	0.207	0.237	0.267	0.296	0.326
0.10	0.117	0.129	0.141	0.158	0.188	0.218	0.248	0.278	0.307	0.337
0.12	0.128	0.140	0.151	0.169	0.199	0.229	0.259	0.288	0.318	0.348
0.15	0.144	0.156	0.168	0.186	0.215	0.245	0.275	0.305	0.334	0.364
0.20	0.171	0.183	0.195	0.213	0.242	0.272	0.302	0.332	0.361	0.391
0.25	0.198	0.210	0.222	0.240	0.270	0.299	0.329	0.359	0.389	0.418
0.30	0.225	0.237	0.249	0.267	0.297	0.326	0.356	0.386	0.416	0.445
0.35	0.252	0.264	0.276	0.294	0.324	0.353	0.383	0.413	0.443	0.472
0.40	0.279	0.291	0.303	0.321	0.351	0.381	0.410	0.440	0.470	0.500
0.45	0.306	0.318	0.330	0.348	0.378	0.408	0.437	0.467	0.497	0.527

Values in the table are average values of torque coefficient calculated using Equations (13) and (14) for K and D_w; diameters d of 8, 10, 12, 16, 20, 24, 30, and 36 mm; and selected respective pitches P and pitch diameters d_2 according to JIS B 0207 thread standard (ISO 724). Dimension D_i was obtained for a Class 1 fit without chamfer from JIS B 1001, Diameters of Clearance Holes and Counterbores for Bolts and Screws (equivalent to ISO 273-1979). The value of D_o was obtained by multiplying the reference dimension from JIS B 1002 (small type series), width across the flats of the hexagon head, by 0.95.

In Equation (17), σ_y is the yield point or proof stress of the bolt, A_s is the stress area of the thread, and $d_A = (4A_s/\pi)^{1/2}$ is the diameter of a circle having an area equal to the stress area of the thread. The other variables have been identified previously.

Example: Find the torque required to tighten a 10-mm coarse-threaded ($P = 1.5$) grade 8.8 bolt to yield assuming that both the thread- and bearing-friction coefficients are 0.12.

Solution: From Equation (17), calculate F_{fy} and then solve $T_{fy} = KF_{fy}d$ to obtain the torque required to stress the bolt to the yield point.

$\sigma_y = 800$ N/mm^2 (MPa) (minimum, based on 8.8 grade rating)
$A_s = 0.7854(10 - 0.9382 \times 1.5)^2 = 57.99$ mm^2
$d_A = (4A_s/\pi)^{1/2} = 8.6$ mm
$d_2 = 9.026$ mm (see JIS B 0205 or ISO 724)

Find α' from $\tan\alpha' = \tan\alpha \cos\beta$ using:

$\alpha = 30°$; $\tan\beta = l \div 2\pi r$; $l = P = 1.5$; and $r = d \div 2 = 5$ mm
$\tan\beta = 1.5 \div 10\pi = 0.048$, therefore $\beta = 2.73°$
$\tan\alpha' = \tan\alpha \cos\beta = \tan 30° \times \cos 2.73° = 0.577$, and $\alpha' = 29.97°$

Solving Equation (17) gives the yield clamping force as follows:

$$F_{fy} = \frac{800 \times 58.0}{\sqrt{1 + 3\left[\frac{2}{8.6}\left(\frac{1.5}{\pi} + 0.12 \times 9.026 \times \sec 29.97°\right)\right]^2}} = 38{,}075 \text{ N}$$

K can be determined from Tables 3 (coarse thread) and Tables 4 (fine thread) or from Equations (13) and (14). From Table 3, for μ_s and μ_w equal to 0.12, $K = 0.164$. The yield-point tightening torque can then be found from $T_{fy} = K \times F_{fy} \times d = 0.164 \times 38{,}075 \times 10 = 62.4 \times 10^3$ N-mm = 62.4 N-m.

Obtaining Torque and Friction Coefficients.— Given suitable test equipment, the torque coefficient K and friction coefficients between threads μ_s or between bearing surfaces μ_w can be determined experimentally as follows: Measure the value of the axial tight-

Copyright 2004, Industrial Press, Inc., New York, NY

ening tension and the corresponding tightening torque at an arbitrary point in the 50 to 80 per cent range of the bolt yield point or proof stress (for steel bolts, use the minimum value of the yield point or proof stress multiplied by the stress area of the bolt). Repeat this test several times and average the results. The tightening torque may be considered as the sum of the torque on the threads plus the torque on the bolt head- or nut-to-joint bearing surface. The torque coefficient can be found from $K = T_f \div F_f \times d$, where F_f is the measured axial tension, and T_f is the measured tightening torque.

To measure the coefficient of friction between threads or bearing surfaces, obtain the total tightening torque and that portion of the torque due to the thread or bearing surface friction. If only tightening torque and the torque on the bearing surfaces can be measured, then the difference between these two measurements can be taken as the thread-tightening torque. Likewise, if only the tightening torque and threaded-portion torque are known, the torque due to bearing can be taken as the difference between the known torques. The coefficients of friction between threads and bearing surfaces, respectively, can be obtained from the following:

$$\mu_s = \frac{2T_s \cos\alpha'}{d_2 F_f} - \cos\alpha' \tan\beta \qquad (18)$$

$$\mu_w = \frac{2T_w}{D_w F_f} \qquad (19)$$

As before, T_s is the torque attributable to the threaded portion of the screw, T_w is the torque due to bearing, D_w is the equivalent diameter of friction torque on bearing surfaces according to Equation (14), and F_f is the measured axial tension.

Torque-Tension Relationships.— Torque is usually applied to develop an axial load in a bolt. To achieve the desired axial load in a bolt, the torque must overcome friction in the threads and friction under the nut or bolt head. In Fig. 5, the axial load P_B is a component of the normal force developed between threads. The normal-force component perpendicular to the thread helix is $P_{N\beta}$ and the other component of this force is the torque load $P_B \tan\beta$ that is applied in tightening the fastener. Assuming the turning force is applied at the pitch diameter of the thread, the torque T_1 needed to develop the axial load is $T_1 = P_B \times \tan\beta \times d_2/2$. Substituting $\tan\beta = l \div \pi d_2$ into the previous expression gives $T_1 = P_B \times l \div 2\pi$.



Fig. 5. Free Body Diagram of Thread Helix Forces



Fig. 6. Thread Friction Force

In Fig. 6, the normal-force component perpendicular to the thread flanks is $P_{N\alpha}$. With a coefficient of friction μ_1 between the threads, the friction load is equal to $\mu_1 P_{N\alpha}$, or $\mu_1 P_B \div \cos\alpha$. Assuming the force is applied at the pitch diameter of the thread, the torque T_2 to overcome thread friction is given by:

$$T_2 = \frac{d_2 \mu_1 P_B}{2\cos\alpha} \qquad (20)$$

Copyright 2004, Industrial Press, Inc., New York, NY

With the coefficient of friction μ_2 between a nut or bolt-head pressure face and a component face, as in Fig. 7, the friction load is equal to $\mu_2 P_B$. Assuming the force is applied midway between the nominal (bolt) diameter d and the pressure-face diameter b, the torque T_3 to overcome the nut or bolt underhead friction is:

$$T_3 = \frac{d+b}{4}\mu_2 P_B \tag{21}$$

The total torque, T, required to develop axial bolt load, P_B, is equal to the sum of the torques T_1, T_2, and T_3 as follows:

$$T = P_B\left(\frac{l}{2\pi} + \frac{d_2\mu_1}{2\cos\alpha} + \frac{(d+b)\mu_2}{4}\right) \tag{22}$$

For a fastener system with 60° threads, $\alpha = 30°$ and d_2 is approximately $0.92d$. If no loose washer is used under the rotated nut or bolt head, b is approximately $1.5d$ and Equation (22) reduces to:

$$T = P_B[0.159 \times l + d(0.531\mu_1 + 0.625\mu_2)] \tag{23}$$

In addition to the conditions of Equation (23), if the thread and bearing friction coefficients, μ_1 and μ_2, are equal (which is not necessarily so), then $\mu_1 = \mu_2 = \mu$, and the previous equation reduces to:

$$T = P_B(0.159l + 1.156\mu d) \tag{24}$$

Example: Estimate the torque required to tighten a UNC ½-13 grade 8 steel bolt to a preload equivalent to 55 per cent of the minimum tensile bolt strength. Assume that the bolt is unplated and both the thread and bearing friction coefficients equal 0.15.

Solution: The minimum tensile strength for SAE grade 8 bolt material is 150,000 psi (from page 1508). To use Equation (24), find the stress area of the bolt using Equation (9) with $P = 1/13$, $d_m = d - 1.2990P$, and $d_p = d - 0.6495P$, and then calculate the necessary preload, P_B, and the applied torque, T.

$$A_s = \frac{\pi}{4}\left(\frac{0.4500 + 0.4001}{2}\right)^2 = 0.1419 \text{ in.}^2$$

$$P_B = \sigma_{allow} \times A_s = 0.55 \times 150{,}000 \times 0.1419 = 11{,}707 \text{ lb}_f$$

$$T = 11{,}707\left(\frac{0.159}{13} + 1.156 \times 0.15 \times 0.500\right) = 1158 \text{ lb-in.} = 96.5 \text{ lb-ft}$$



Fig. 7. Nut or Bolt Head Friction Force

Copyright 2004, Industrial Press, Inc., New York, NY

Grade Marks and Material Properties for Bolts and Screws.— Bolts, screws, and other fasteners are marked on the head with a symbol that identifies the grade of the fastener. The grade specification establishes the minimum mechanical properties that the fastener must meet. Additionally, industrial fasteners must be stamped with a registered head mark that identifies the manufacturer. The grade identification table identifies the grade markings and gives mechanical properties for some commonly used ASTM and SAE steel fasteners. Metric fasteners are identified by property grade marks, which are specified in ISO and SAE standards. These marks are discussed with metric fasteners.

Grade Identification Marks and Mechanical Properties of Bolts and Screws



Identifier	Grade	Size (in.)	Min. Strength (10^3 psi)			Material & Treatment
			Proof	Tensile	Yield	
A	SAE Grade 1	$\frac{1}{4}$ to $1\frac{1}{2}$	33	60	36	1
	ASTM A307	$\frac{1}{4}$ to $1\frac{1}{2}$	33	60	36	3
	SAE Grade 2	$\frac{1}{4}$ to $\frac{3}{4}$	55	74	57	1
		$\frac{7}{8}$ to $1\frac{1}{2}$	33	60	36	
	SAE Grade 4	$\frac{1}{4}$ to $1\frac{1}{2}$	65	115	100	2, a
B	SAE Grade 5	$\frac{1}{4}$ to 1	85	120	92	2,b
	ASTM A449	$1\frac{1}{8}$ to $1\frac{1}{2}$	74	105	81	
	ASTM A449	$1\frac{3}{4}$ to 3	55	90	58	
C	SAE Grade 5.2	$\frac{1}{4}$ to 1	85	120	92	4, b
D	ASTM A325, Type 1	$\frac{1}{2}$ to 1	85	120	92	2,b
		$1\frac{1}{8}$ to $1\frac{1}{2}$	74	105	81	
E	ASTM A325, Type 2	$\frac{1}{2}$ to 1	85	120	92	4, b
		$1\frac{1}{8}$ to $1\frac{1}{2}$	74	105	81	
F	ASTM A325, Type 3	$\frac{1}{2}$ to 1	85	120	92	5, b
		$1\frac{1}{8}$ to $1\frac{1}{2}$	74	105	81	
G	ASTM A354, Grade BC	$\frac{1}{4}$ to $2\frac{1}{2}$	105	125	109	5,b
		$2\frac{3}{4}$ to 4	95	115	99	
H	SAE Grade 7	$\frac{1}{4}$ to $1\frac{1}{2}$	105	133	115	7, b
I	SAE Grade 8	$\frac{1}{4}$ to $1\frac{1}{2}$	120	150	130	7, b
	ASTM A354, Grade BD	$\frac{1}{4}$ to $1\frac{1}{2}$	120	150	130	6, b
J	SAE Grade 8.2	$\frac{1}{4}$ to 1	120	150	130	4, b
K	ASTM A490, Type 1	$\frac{1}{2}$ to $1\frac{1}{2}$	120	150	130	6, b
L	ASTM A490, Type 3					5, b

Material Steel: 1—low or medium carbon; 2—medium carbon; 3—low carbon; 4—low-carbon martensite; 5—weathering steel; 6—alloy steel; 7— medium-carbon alloy. Treatment: a—cold drawn; b—quench and temper.

Copyright 2004, Industrial Press, Inc., New York, NY

Detecting Counterfeit Fasteners.— Fasteners that have markings identifying them as belonging to a specific grade or property class are counterfeit if they do not meet the standards established for that class. Counterfeit fasteners may break unexpectedly at smaller loads than expected. Generally, these fasteners are made from the wrong material or they are not properly strengthened during manufacture. Either way, counterfeit fasteners can lead to dangerous failures in assemblies. The law now requires testing of fasteners used in some critical applications. Detection of counterfeit fasteners is difficult because the counterfeits look genuine. The only sure way to determine if a fastener meets its specification is to test it. However, reputable distributors will assist in verifying the authenticity of the fasteners they sell. For important applications, fasteners can be checked to determine whether they perform according to the standard. Typical laboratory checks used to detect fakes include testing hardness, elongation, and ultimate loading, and a variety of chemical tests.

Mechanical Properties and Grade Markings of Nuts.— Three grades of hex and square nuts designated Grades 2, 5, and 8 are specified by the SAE J995 standard covering nuts in the ¼- to 1½-inch diameter range. Grades 2, 5, and 8 nuts roughly correspond to the SAE specified bolts of the same grade. Additional specifications are given for miscellaneous nuts such as hex jam nuts, hex slotted nuts, heavy hex nuts, etc. Generally speaking, use nuts of a grade equal to or greater than the grade of the bolt being used. Grade 2 nuts are not required to be marked, however, all Grades 5 and 8 nuts in the ¼- to 1½-inch range must be marked in one of three ways: Grade 5 nuts may be marked with a dot on the face of the nut and a radial or circumferential mark at 120° counterclockwise from the dot; or a dot at one corner of the nut and a radial line at 120° clockwise from the nut, or one notch at each of the six corners of the nut. Grade 8 nuts may be identified by a dot on the face of the nut with a radial or circumferential mark at 60° counterclockwise from the dot; or a dot at one corner of the nut and a radial line at 60° clockwise from the nut, or two notches at each of the six corners of the nut.

Working Strength of Bolts.— When the nut on a bolt is tightened, an initial tensile load is placed on the bolt that must be taken into account in determining its safe working strength or external load-carrying capacity. The total load on the bolt theoretically varies from a maximum equal to the sum of the initial and external loads (when the bolt is absolutely rigid and the parts held together are elastic) to a minimum equal to either the initial or external loads, whichever is the greater (where the bolt is elastic and the parts held together are absolutely rigid). No material is absolutely rigid, so in practice the total load values fall somewhere between these maximum and minimum limits, depending upon the relative elasticity of the bolt and joint members.

Some experiments made at Cornell University to determine the initial stress due to tightening nuts on bolts sufficiently to make a packed joint steam-tight showed that experienced mechanics tighten nuts with a pull roughly proportional to the bolt diameter. It was also found that the stress due to nut tightening was often sufficient to break a ½-inch (12.7-mm) bolt, but not larger sizes, assuming that the nut is tightened by an experienced mechanic. It may be concluded, therefore, that bolts smaller than ⅝ inch (15.9 mm) should not be used for holding cylinder heads or other parts requiring a tight joint. As a result of these tests, the following empirical formula was established for the working strength of bolts used for packed joints or joints where the elasticity of a gasket is greater than the elasticity of the studs or bolts.

$$W = S_t(0.55d^2 - 0.25d)$$

In this formula, W = working strength of bolt or permissible load, in pounds, after allowance is made for initial load due to tightening; S_t = allowable working stress in tension, pounds per square inch; and d = nominal outside diameter of stud or bolt, inches. A somewhat more convenient formula, and one that gives approximately the same results, is

Copyright 2004, Industrial Press, Inc., New York, NY

$$W = S_t(A - 0.25d)$$

In this formula, W, S_t, and d are as previously given, and A = area at the root of the thread, square inches.

Example: What is the working strength of a 1-inch bolt that is screwed tightly in a packed joint when the allowable working stress is 10,000 psi?

$$W = 10{,}000(0.55 \times 1 - 0.25 \times 1) = 3000 \text{ pounds approx.}$$

Formulas for Stress Areas and Lengths of Engagement of Screw Threads.— The critical areas of stress of mating screw threads are: 1) The effective cross-sectional area, or tensile-stress area, of the external thread; 2) the shear area of the external thread, which depends principally on the minor diameter of the tapped hole; and 3) the shear area of the internal thread, which depends principally on the major diameter of the external thread. The relation of these three stress areas to each other is an important factor in determining how a threaded connection will fail, whether by breakage in the threaded section of the screw (or bolt) or by stripping of either the external or internal thread.

If failure of a threaded assembly should occur, it is preferable for the screw to break rather than have either the external or internal thread strip. In other words, the length of engagement of mating threads should be sufficient to carry the full load necessary to break the screw without the threads stripping.

If mating internal and external threads are manufactured of materials having equal tensile strengths, then to prevent stripping of the external thread, the length of engagement should be not less than that given by Formula (1):

$$L_e = \frac{2 \times A_t}{3.1416 K_n \text{max}[\frac{1}{2} + 0.57735n(E_s\text{min} - K_n\text{max})]} \quad (1)$$

In this formula, the factor of 2 means that it is assumed that the area of the screw in shear must be twice the tensile-stress area to attain the full strength of the screw (this value is slightly larger than required and thus provides a small factor of safety against stripping); L_e = length of engagement, in inches; n = number of threads per inch; K_n max = maximum minor diameter of internal thread; E_s min = minimum pitch diameter of external thread for the class of thread specified; and A_t = tensile-stress area of screw thread given by Formula (2a) or (2b) or the thread tables for Unified threads, Tables 4a through 5h starting on page 1763, which are based on Formula (2a).

For steels of up to 100,000 psi ultimate tensile strength,

$$A_t = 0.7854\left(D - \frac{0.9743}{n}\right)^2 \quad (2a)$$

For steels of over 100,000 psi ultimate tensile strength,

$$A_t = 3.1416\left(\frac{E_s\text{min}}{2} - \frac{0.16238}{n}\right)^2 \quad (2b)$$

In these formulas, D = basic major diameter of the thread and the other symbols have the same meanings as before.

Stripping of Internal Thread: If the internal thread is made of material of lower strength than the external thread, stripping of the internal thread may take place before the screw breaks. To determine whether this condition exists, it is necessary to calculate the factor J for the relative strength of the external and internal threads given by Formula (3):

$$J = \frac{A_s \times \text{tensile strength of external thread material}}{A_n \times \text{tensile strength of internal thread material}} \quad (3)$$

Copyright 2004, Industrial Press, Inc., New York, NY

If J is less than or equal to 1, the length of engagement determined by Formula (1) is adequate to prevent stripping of the internal thread; if J is greater than 1, the required length of engagement Q to prevent stripping of the internal thread is obtained by multiplying the length of engagement L_e, Formula (1), by J:

$$Q = JL_e \tag{4}$$

In Formula (3), A_s and A_n are the shear areas of the external and internal threads, respectively, given by Formulas (5) and (6):

$$A_s = 3.1416nL_eK_n\text{max}\left[\frac{1}{2n} + 0.57735(E_s\text{min} - K_n\text{max})\right] \tag{5}$$

$$A_n = 3.1416nL_eD_s\text{min}\left[\frac{1}{2n} + 0.57735(D_s\text{min} - E_n\text{max})\right] \tag{6}$$

In these formulas, n = threads per inch; L_e = length of engagement from Formula (1); K_n max = maximum minor diameter of internal thread; E_s min = minimum pitch diameter of the external thread for the class of thread specified; D_s min = minimum major diameter of the external thread; and E_n max = maximum pitch diameter of internal thread.

Load to Break Threaded Portion of Screws and Bolts.— The direct tensile load P to break the threaded portion of a screw or bolt (assuming that no shearing or torsional stresses are acting) can be determined from the following formula:

$$P = SA_t$$

where P = load in pounds to break screw; S = ultimate tensile strength of material of screw or bolt in pounds per square inch; and A_t = tensile-stress area in square inches from Formula (2a), (2b), or from the screw thread tables.

Lock Wire Procedure Detail.— Wire ties are frequently used as a locking device for bolted connections to prevent loosening due to vibration and loading conditions, or tampering. The use of safety wire ties is illustrated in Figs. 1 and 2 below. The illustrations assume the use of right-hand threaded fasteners and the following additional rules apply:

1) No more that three (3) bolts may be tied together; 2) Bolt heads may be tied as shown only when the female thread receiver is captive; 3) Pre-drilled nuts may be tied in a fashion similar to that illustrated with the following conditions. a) Nuts must be heat-treated; and b) Nuts are factory drilled for use with lock wire.

4) Lock wire must fill a minimum of 75% of the drilled hole provided for the use of lock wire; and 5) Lock wire must be aircraft quality stainless steel of 0.508 mm (0.020 inch) diameter, 0.8128 mm (0.032 inch) diameter, or 1.067 mm 0.042 inch) diameter. Diameter of lock wire is determined by the thread size of the fastener to be safe-tied. a) Thread sizes of 6 mm (0.25 inch) and smaller use 0.508mm (0.020 inch) wire; b) Thread sizes of 6 mm (0.25 inch) to 12 mm (0.5 inch) use 0.8128 mm (0.032 inch) wire; c) Thread sizes > 12 mm (0.5 inch) use 1.067 mm (0.042 inch) wire; and d) The larger wire may be used in smaller bolts in cases of convenience, but smaller wire must not be used in larger fastener sizes.

Fig. 1. Three (3) Bolt Procedure



Fig. 2. Two (2) Bolt Procedure

Copyright 2004, Industrial Press, Inc., New York, NY

INCH THREADED FASTENERS

Dimensions of bolts, screws, nuts, and washers used in machine construction are given here. For data on thread forms, see the section *SCREW THREAD SYSTEMS* starting on page 1725.

American Square and Hexagon Bolts, Screws, and Nuts.— The 1941 American Standard ASA B18.2 covered head dimensions only. In 1952 and 1955 the Standard was revised to cover the entire product. Some bolt and nut classifications were simplified by elimination or consolidation in agreements reached with the British and Canadians. In 1965 ASA B18.2 was redesignated into two standards: B18.2.1 covering square and hexagon bolts and screws including hexagon cap screws and lag screws and B18.2.2 covering square and hexagon nuts. In B18.2.1-1965, hexagon head cap screws and finished hexagon bolts were consolidated into a single product heavy semifinished hexagon bolts and heavy finished hexagon bolts were consolidated into a single product; regular semifinished hexagon bolts were eliminated; a new tolerance pattern for all bolts and screws and a positive identification procedure for determining whether an externally threaded product should be designated as a bolt or screw were established. Also included in this standard are heavy hexagon bolts and heavy hexagon structural bolts. In B18.2.2-1965, regular semifinished nuts were discontinued; regular hexagon and heavy hexagon nuts in sizes $\frac{1}{4}$ through 1 inch, finished hexagon nuts in sizes larger than $1\frac{1}{2}$ inches, washer-faced semifinished style of finished nuts in sizes $\frac{5}{8}$-inch and smaller and heavy series nuts in sizes $\frac{7}{16}$-inch and smaller were eliminated.

Further revisions and refinements include the addition of askew head bolts and hex head lag screws and the specifying of countersunk diameters for the various hex nuts. Heavy hex structural bolts and heavy hex nuts were moved to a new structural applications standard. Additionally, B18.2.1 has been revised to allow easier conformance to Public Law 101-592. All these changes are reflected in ANSI/ASME B18.2.1-1996, and ANSI/ASME B18.2.2-1987 (R1999).

Unified Square and Hexagon Bolts, Screws, and Nuts.— Items that are recognized in the Standard as "unified" dimensionally with British and Canadian standards are shown in bold-face in certain tables.

The other items in the same tables are based on formulas accepted and published by the British for sizes outside the ranges listed in their standards which, as a matter of information, are BS 1768:1963 (obsolescent) for Precision (Normal Series) Unified Hexagon Bolts, Screws, Nuts (UNC and UNF Threads) and B.S. 1769 and amendments for Black (Heavy Series) Unified Hexagon Bolts, etc. Tolerances applied to comparable dimensions of American and British Unified bolts and nuts may differ because of rounding off practices and other factors.

Differentiation between Bolt and Screw.— A bolt is an externally threaded fastener designed for insertion through holes in assembled parts, and is normally intended to be tightened or released by torquing a nut.

A screw is an externally threaded fastener capable of being inserted into holes in assembled parts, of mating with a preformed internal thread or forming its own thread and of being tightened or released by torquing the head.

An externally threaded fastener which is prevented from being turned during assembly, and which can be tightened or released only by torquing a nut is a *bolt*. (*Example:* round head bolts, track bolts, plow bolts.)

An externally threaded fastener that has a thread form which prohibits assembly with a nut having a straight thread of multiple pitch length is a *screw*. (*Example:* wood screws, tapping screws.)

Copyright 2004, Industrial Press, Inc., New York, NY

An externally threaded fastener that must be assembled with a nut to perform its intended service is a *bolt*. (*Example:* heavy hex structural bolt.)

An externally threaded fastener that must be torqued by its head into a tapped or other preformed hole to perform its intended service is a *screw*. (*Example:* square head set screw.)



Fig. 1. Square Bolts (Table 1)



Fig. 2. Heavy Hex Structural Bolts (Table 2)



Fig. 3. Hex Bolts, Heavy Hex Bolts (Table 3)



Fig. 4. Hex Cap Screws, Heavy Hex Screws (Table 4)



Fig. 5. Hex Nuts, Heavy Hex Nuts (Table 7)



Fig. 6. Hex Jam Nuts, Heavy Hex Jam Nuts (Table 7)

Square and Hex Bolts, Screws, and Nuts.— The dimensions for square and hex bolts and screws given in the following tables have been taken from American National Standard ANSI/ASME B18.2.1-1996 and for nuts from American National Standard ANSI/ASME B18.2.2-1987 (R1999) Reference should be made to these Standards for information or data not found in the following text and tables:

Designation: Bolts and screws should be designated by the following data in the sequence shown: nominal size (fractional and decimal equivalent); threads per inch (omit for lag screws); product length for bolts and screws (fractional or two-place decimal equivalent); product name; material, including specification, where necessary; and protective finish, if required. Examples: (1) $\frac{3}{8}$-16 × 1$\frac{1}{2}$ Square Bolt, Steel, Zinc Plated; (2) $\frac{1}{2}$-13 × 3

Copyright 2004, Industrial Press, Inc., New York, NY

Hex Cap Screw, SAE Grade 8 Steel; and (3) .75 × 5.00 Hex Lag Screw, Steel. (4) ½-13 Square Nut, Steel, Zinc Plated; (5) ¾-16 Heavy Hex Nut, SAE J995 Grade 5 Steel; and (6) 1000-8 Hex Thick Slotted Nut, ASTM F594 (Alloy Group 1) Corrosion-Resistant Steel.

Table 1. American National Standard and Unified Standard Square Bolts
ANSI/ASME B18.2.1-1996

SQUARE BOLTS (Fig. 1)											
Nominal Size[a] or Basic Product Dia.		Body Dia.[b] *E*	Width Across Flats *F*			Width Across Corners *G*		Head Height *H*			Thread Length[c] L_T
		Max.	Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Nom.
1/4	0.2500	0.260	3/8	0.375	0.362	0.530	0.498	11/64	0.188	0.156	0.750
5/16	0.3125	0.324	1/2	0.500	0.484	0.707	0.665	13/64	0.220	0.186	0.875
3/8	0.3750	0.388	9/16	0.562	0.544	0.795	0.747	1/4	0.268	0.232	1.000
7/16	0.4375	0.452	5/8	0.625	0.603	0.884	0.828	19/64	0.316	0.278	1.125
1/2	0.5000	0.515	3/4	0.750	0.725	1.061	0.995	21/64	0.348	0.308	1.250
5/8	0.6250	0.642	15/16	0.938	0.906	1.326	1.244	27/64	0.444	0.400	1.500
3/4	0.7500	0.768	1 1/8	1.125	1.088	1.591	1.494	1/2	0.524	0.476	1.750
7/8	0.8750	0.895	1 5/16	1.312	1.269	1.856	1.742	19/32	0.620	0.568	2.000
1	1.0000	1.022	1 1/2	1.500	1.450	2.121	1.991	21/32	0.684	0.628	2.250
1 1/8	1.1250	1.149	1 11/16	1.688	1.631	2.386	2.239	3/4	0.780	0.720	2.500
1 1/4	1.2500	1.277	1 7/8	1.875	1.812	2.652	2.489	27/32	0.876	0.812	2.750
1 3/8	1.3750	1.404	2 1/16	2.602	1.994	2.917	2.738	29/32	0.940	0.872	3.000
1 1/2	1.5000	1.531	2 1/4	2.250	2.175	3.182	2.986	1	1.036	0.964	3.250

[a] Where specifying nominal size in decimals, zeros before the decimal point and in the fourth decimal place are omitted.

[b] See *Body Diameter* footnote in Table 3.

[c] Thread lengths, L_T, shown are for bolt lengths 6 inches and shorter. For longer bolt lengths add 0.250 inch to thread lengths shown.

Table 2. American National Standard Heavy Hex Structural Bolts
ANSI/ASME B18.2.1-1981 (R1992)[a]

HEAVY HEX STRUCTURAL BOLTS (Fig. 2)													
Nominal Size[a] or Basic Product Dia.		Body Dia. *E*		WidthAcross Flats *F*		Width Across Corners *G*		Height *H*		Radius of Fillet *R*		Thrd. Lgth. L_T	Transition Thrd. *Y*
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Basic	Max.
1/2	0.5000	0.515	0.482	0.875	0.850	1.010	0.969	0.323	0.302	0.031	0.009	1.00	0.19
5/8	0.6250	0.642	0.605	1.062	1.031	1.227	1.175	0.403	0.378	0.062	0.021	1.25	0.22
3/4	0.7500	0.768	0.729	1.250	1.212	1.443	1.383	0.483	0.455	0.062	0.021	1.38	0.25
7/8	0.8750	0.895	0.852	1.438	1.394	1.660	1.589	0.563	0.531	0.062	0.031	1.50	0.28
1	1.0000	1.022	0.976	1.625	1.575	1.876	1.796	0.627	0.591	0.093	0.062	1.75	0.31
1 1/8	1.1250	1.149	1.098	1.812	1.756	2.093	2.002	0.718	0.658	0.093	0.062	2.00	0.34
1 1/4	1.2500	1.277	1.223	2.000	1.938	2.309	2.209	0.813	0.749	0.093	0.062	2.00	0.38
1 3/8	1.3750	1.404	1.345	2.188	2.119	2.526	2.416	0.878	0.810	0.093	0.062	2.25	0.44
1 1/2	1.5000	1.531	1.470	2.375	2.300	2.742	2.622	0.974	0.902	0.093	0.062	2.25	0.44

[a] Heavy hex structural bolts have been removed from the latest version, ANSI/ASME B18.2.1-1996. The table has been included for reference.

All dimensions are in inches. **Bold type shows bolts unified dimensionally with British and Canadian Standards.** Threads, when rolled, shall be Unified Coarse, Fine, or 8-thread series (UNRC, UNRF, or 8 UNR Series), Class 2A. Threads produced by other methods may be Unified Coarse, Fine, or 8-thread series (UNC, UNF, or 8 UN Series), Class 2A.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard and Unified Standard Hex and Heavy Hex Bolts *ANSI/ASME B18.2.1-1996*

Nominal Size[a] or Basic Dia.		Full Size Body Dia. *E*	Width Across Flats *F*			Width Across Corners *G*		Head Height *H*			Thread Length[b] L_T
		Max.	Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Nom.
HEX BOLTS (Fig. 3)											
1/4	**0.2500**	**0.260**	**7/16**	**0.438**	**0.425**	**0.505**	**0.484**	**11/64**	**0.188**	**0.150**	0.750
5/16	**0.3125**	**0.324**	**1/2**	**0.500**	**0.484**	**0.577**	**0.552**	**7/32**	**0.235**	**0.195**	0.875
3/8	**0.3750**	**0.388**	**9/16**	**0.562**	**0.544**	**0.650**	**0.620**	**1/4**	**0.268**	**0.226**	1.000
7/16	**0.4375**	**0.452**	**5/8**	**0.625**	**0.603**	**0.722**	**0.687**	**19/64**	**0.316**	**0.272**	1.125
1/2	**0.5000**	**0.515**	**3/4**	**0.750**	**0.725**	**0.866**	**0.826**	**11/32**	**0.364**	**0.302**	1.250
5/8	**0.6250**	**0.642**	**15/16**	**0.938**	**0.906**	**1.083**	**1.033**	**27/64**	**0.444**	**0.378**	1.500
3/4	**0.7500**	**0.768**	**1 1/8**	**1.125**	**1.088**	**1.299**	**1.240**	**1/2**	**0.524**	**0.455**	1.750
7/8	**0.8750**	**0.895**	**1 5/16**	**1.312**	**1.269**	**1.516**	**1.447**	**37/64**	**0.604**	**0.531**	2.000
1	**1.0000**	**1.022**	**1 1/2**	**1.500**	**1.450**	**1.732**	**1.653**	**43/64**	**0.700**	**0.591**	2.250
1 1/8	**1.1250**	**1.149**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	**3/4**	**0.780**	**0.658**	2.500
1 1/4	**1.2500**	**1.277**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**27/32**	**0.876**	**0.749**	2.750
1 3/8	**1.3750**	**1.404**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**29/32**	**0.940**	**0.810**	3.000
1 1/2	**1.5000**	**1.531**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**1**	**1.036**	**0.902**	3.250
1 3/4	**1.7500**	**1.785**	**2 5/8**	**2.625**	**2.538**	**3.031**	**2.893**	**15/32**	**1.196**	**1.054**	3.750
2	**2.000**	**2.039**	**3**	**3.000**	**2.900**	**3.464**	**3.306**	**1 11/32**	**1.388**	**1.175**	4.250
2 1/4	2.2500	2.305	3 3/8	3.375	3.262	3.897	3.719	1 1/2	1.548	1.327	4.750
2 1/2	2.5000	2.559	3 3/4	3.750	3.625	4.330	4.133	1 21/32	1.708	1.479	5.250
2 3/4	2.7500	2.827	4 1/8	4.125	3.988	4.763	4.546	1 13/16	1.869	1.632	5.750
3	3.0000	3.081	4 1/2	4.500	4.350	5.196	4.959	2	2.060	1.815	6.250
3 1/4	3.2500	3.335	4 7/8	4.875	4.712	5.629	5.372	2 3/16	2.251	1.936	6.750
3 1/2	3.5000	3.589	5 1/4	5.250	5.075	6.062	5.786	2 5/16	2.380	2.057	7.250
3 3/4	3.7500	3.858	5 5/8	5.625	5.437	6.495	6.198	2 1/2	2.572	2.241	7.750
4	4.0000	4.111	6	6.000	5.800	6.928	6.612	2 11/16	2.764	2.424	8.250
HEAVY HEX BOLTS (Fig. 3)											
1/2	**0.5000**	**0.515**	**7/8**	**0.875**	**0.850**	**1.010**	**0.969**	11/32	0.364	0.302	1.250
5/8	**0.6250**	**0.642**	**1 1/16**	**1.062**	**1.031**	**1.227**	**1.175**	27/64	0.444	0.378	1.500
3/4	**0.7500**	**0.768**	**1 1/4**	**1.250**	**1.212**	**1.443**	**1.383**	1/2	0.524	0.455	1.750
7/8	**0.8750**	**0.895**	**1 7/16**	**1.438**	**1.394**	**1.660**	**1.589**	37/64	0.604	0.531	2.000
1	**1.0000**	**1.022**	**1 5/8**	**1.625**	**1.575**	**1.876**	**1.796**	43/64	0.700	0.591	2.250
1 1/8	**1.1250**	**1.149**	**1 13/16**	**1.812**	**1.756**	**2.093**	**2.002**	3/4	0.780	0.658	2.500
1 1/4	**1.2500**	**1.277**	**2**	**2.000**	**1.938**	**2.309**	**2.209**	27/32	0.876	0.749	2.750
1 3/8	**1.3750**	**1.404**	**2 3/16**	**2.188**	**2.119**	**2.526**	**2.416**	29/32	0.940	0.810	3.000
1 1/2	**1.5000**	**1.531**	**2 3/8**	**23.75**	**2.300**	**2.742**	**2.622**	1	1.036	0.902	3.250
1 3/4	**1.7500**	**1.785**	**2 3/4**	**2.750**	**2.662**	**3.175**	**3.035**	15/32	1.196	1.054	3.750
2	**2.0000**	**2.039**	*3 1/8*	**3.125**	**3.025**	**3.608**	**3.449**	1 11/32	1.388	1.175	4.250
2 1/4	2.2500	2.305	3 1/2	3.500	3.388	4.041	3.862	1 1/2	1.548	1.327	4.750
2 1/2	2.5000	2.559	3 7/8	3.875	3.750	4.474	4.275	1 21/32	1.708	1.479	5.250
2 3/4	2.7500	2.827	4 1/4	4.250	4.112	4.907	4.688	1 13/16	1.869	1.632	5.750
3	3.0000	3.081	4 5/8	4.625	4.475	5.340	5.102	2	2.060	1.815	6.250

[a] *Nominal Size:* Where specifying nominal size in decimals, zeros preceding the decimal point and in the fourth decimal place are omitted.

[b] Thread lengths, L_T, shown are for bolt lengths 6 inches and shorter. For longer bolt lengths add 0.250 inch to thread lengths shown.

All dimensions are in inches.

Bold type shows bolts unified dimensionally with British and Canadian Standards.

Threads: Threads, when rolled, are Unified Coarse, Fine, or 8-thread series (UNRC, UNRF, or 8 UNR Series), Class 2A. Threads produced by other methods may be Unified Coarse, Fine or 8-thread series (UNC, UNF, or 8 UN Series), Class 2A.

Body Diameter: Bolts may be obtained in "reduced diameter body." Where "reduced diameter body" is specified, the body diameter may be reduced to approximately the pitch diameter of the thread. A shoulder of full body diameter under the head may be supplied at the option of the manufacturer.

Material: Unless otherwise specified, chemical and mechanical properties of steel bolts conform to ASTM A307, Grade A. Other materials are as agreed upon by manufacturer and purchaser.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard and Unified Standard Heavy Hex Screws and Hex Cap Screws *ANSI/ASME B18.2.1-1996*

Nominal Size[a] or Basic Product Dia.	Body Dia. *E*		Width Across Flats *F*			Width Across Corners *G*		Height *H*			Thread Length[b] L_T
	Max.	Min.	Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Basic
HEAVY HEX SCREWS (Fig. 4)											
1/2	**0.5000**	**0.5000**	0.482	**7/8**	**0.875**	**.0850**	**1.010**	**0.969**	**5/16**	0.323	0.302	1.250
5/8	**0.6250**	**0.6250**	0.605	**1 1/16**	**1.062**	**1.031**	**1.227**	**1.175**	**25/64**	0.403	0.378	1.500
3/4	**0.7500**	**0.7500**	0.729	**1 1/4**	**1.250**	**1.212**	**1.443**	**1.383**	**15/32**	0.483	0.455	1.750
7/8	**0.8750**	**0.8750**	0.852	**1 7/16**	**1.438**	**1.394**	**1.660**	**1.589**	**35/64**	0.563	0.531	2.000
1	**1.0000**	**1.0000**	0.976	**1 5/8**	**1.625**	**1.575**	**1.876**	**1.796**	**39/64**	0.627	0.591	2.250
1 1/8	**1.1250**	**1.1250**	1.098	**1 13/16**	**1.812**	**1.756**	**2.093**	**2.002**	**11/16**	0.718	0.658	2.500
1 1/4	**1.2500**	**1.2500**	1.223	**2**	**2.000**	**1.938**	**2.309**	**2.209**	**25/32**	0.813	0.749	2.750
1 3/8	**1.3750**	**1.3750**	1.345	**2 3/16**	**2.188**	**2.119**	**2.526**	**2.416**	**27/32**	0.878	0.810	3.000
1 1/2	**1.5000**	**1.5000**	1.470	**2 3/8**	**2.375**	**2.300**	**2.742**	**2.622**	**15/16**	0.974	0.902	3.250
1 3/4	**1.7500**	**1.7500**	1.716	**2 3/4**	**2.750**	**2.662**	**3.175**	**3.035**	**1 3/32**	1.134	1.054	3.750
2	**2.0000**	**2.0000**	1.964	**3 1/8**	**3.125**	**3.025**	**3.608**	**3.449**	**1 7/32**	1.263	1.175	4.250
2 1/4	2.2500	2.2500	2.214	3 1/2	3.500	3.388	4.041	3.862	1 3/8	1.423	1.327	5.000[c]
2 1/2	2.5000	2.5000	2.461	3 7/8	3.875	3.750	4.474	4.275	1 17/32	1.583	1.479	5.500[c]
2 3/4	2.7500	2.7500	2.711	4 1/4	4.250	41.112	4.907	4.688	1 11/16	1.744	1.632	6.000[c]
3	3.0000	3.0000	2.961	4 5/8	4.625	4.475	5.340	5.102	1 7/8	1.935	1.815	6.500[c]
HEX CAP SCREWS (Finished Hex Bolts) (Fig. 4)												
1/4	**0.2500**	**0.2500**	**0.2450**	**7/16**	**0.438**	**0.428**	**0.505**	**0.488**	**5/32**	**0.163**	**0.150**	0.750
5/16	**0.3125**	**0.3125**	**0.3065**	**1/2**	**0.500**	**0.489**	**0.577**	**0.557**	**13/64**	**0.211**	**0.195**	0.875
3/8	**0.3750**	**0.3750**	**0.3690**	**9/16**	**0.562**	**0.551**	**0.650**	**0.628**	**15/64**	**0.243**	**0.226**	1.000
7/16	**0.4375**	**0.4375**	**0.4305**	**5/8**	**0.625**	**0.612**	**0.722**	**0.698**	**9/32**	**0.291**	**0.272**	1.125
1/2	**0.5000**	**0.5000**	**0.4930**	**3/4**	**0.750**	**0.736**	**0.866**	**0.840**	**5/16**	**0.323**	**0.302**	1.250
9/16	**0.5625**	**0.5625**	**0.5545**	**13/16**	**0.812**	**0.798**	**0.938**	**0.910**	**23/64**	**0.371**	**0.348**	1.375
5/8	**0.6250**	**0.6250**	**0.6170**	**15/16**	**0.938**	**0.922**	**1.083**	**1.051**	**25/64**	**0.403**	**0.378**	1.500
3/4	**0.7500**	**0.7500**	**0.7410**	**1 1/8**	**1.125**	**1.100**	**1.299**	**1.254**	**15/32**	**0.483**	**0.455**	1.750
7/8	**0.8750**	**0.8750**	**0.8660**	**1 5/16**	**1.312**	**1.285**	**1.516**	**1.465**	**35/64**	**0.563**	**0.531**	2.000
1	**1.0000**	**1.0000**	**0.9900**	**1 1/2**	**1.500**	**1.469**	**1.732**	**1.675**	**39/64**	**0.627**	**0.591**	2.250
1 1/8	**1.1250**	**1.1250**	**1.1140**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	**11/16**	**0.718**	**0.658**	2.500
1 1/4	**1.2500**	**1.2500**	**1.2390**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**25/35**	**0.813**	**0.749**	2.750
1 3/8	**1.3750**	**1.3750**	**1.3630**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**27/32**	**0.878**	**0.810**	3.000
1 1/2	**1.5000**	**1.5000**	**1.4880**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**15/16**	**0.974**	**0.902**	3.250
1 3/4	**1.7500**	**1.7500**	**1.7380**	**2 5/8**	**2.625**	**2.538**	**3.031**	**2.893**	**1 3/32**	**1.134**	**1.054**	3.750
2	**2.0000**	**2.0000**	**1.9880**	**3**	**3.000**	**2.900**	**3.464**	**3.306**	**1 7/32**	**1.263**	**1.175**	4.250
2 1/4	2.2500	2.2500	2.2380	3 3/8	3.375	3.262	3.897	3.719	1 3/8	1.423	1.327	5.000[c]
2 1/2	2.5000	2.5000	2.4880	3 3/4	3.750	3.625	4.330	4.133	1 17/32	1.583	1.479	5.500[c]
2 3/4	2.7500	2.7500	2.7380	4 1/8	4.125	3.988	4.763	4.546	1 11/16	1.744	1.632	6.000[c]
3	3.0000	3.0000	2.9880	4 1/2	4.500	4.350	5.196	4.959	1 7/8	1.935	1.815	6.500[c]

[a] *Nominal Size:* Where specifying nominal size in decimals, zeros preceding the decimal and in the fourth decimal place are omitted.

[b] Thread lengths, L_T, shown are for bolt lengths 6 inches and shorter. For longer bolt lengths add 0.250 inch to thread lengths shown.

[c] Thread lengths, L_T, shown are for bolt lengths over 6 inches.

All dimensions are in inches.

Unification: **Bold type indicates product features unified dimensionally with British and Canadian Standards.** Unification of fine thread products is limited to sizes 1 inch and smaller.

Bearing Surface: Bearing surface is flat and washer faced. Diameter of bearing surface is equal to the maximum width across flats within a tolerance of minus 10 per cent.

Threads Series: Threads, when rolled, are Unified Coarse, Fine, or 8-thread series (UNRC, UNRF, or 8 UNR Series), Class 2A. Threads produced by other methods shall preferably be UNRC, UNRF or 8 UNR but, at manufacturer's option, may be Unified Coarse, Fine or 8-thread series (UNC, UNF, or 8 UN Series), Class 2A.

Material: Chemical and mechanical properties of steel screws normally conform to Grades 2, 5, or 8 of SAE J429, ASTM A449 or ASTM A354 Grade BD. Where specified, screws may also be made from brass, bronze, corrosion-resisting steel, aluminum alloy or other materials.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Square Lag Screws *ANSI/ASME B18.2.1-1996*



Nominal Size[a] or Basic Product Dia.		Body or Shoulder Dia. *E*		Width Across Flats *F*			Width Across Corners *G*		Height *H*			Shoulder Length *S*	Radius of Fillet *R*	Thds. per Inch	Thread Dimensions			
		Max.	Min.	Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Min.	Max.		Pitch *P*	Flat at Root *B*	Depth of Thd. *T*	Root Dia. D_1
No. 10	0.1900	0.199	0.178	9/32	0.281	0.271	0.398	0.372	1/8	0.140	0.110	0.094	0.03	11	0.091	0.039	0.035	0.120
1/4	0.2500	0.260	0.237	3/8	0.375	0.362	0.530	0.498	11/64	0.188	0.156	0.094	0.03	10	0.100	0.043	0.039	0.173
5/16	0.3125	0.324	0.298	1/2	0.500	0.484	0.707	0.665	13/64	0.220	0.186	0.125	0.03	9	0.111	0.048	0.043	0.227
3/8	0.3750	0.388	0.360	9/16	0.562	0.544	0.795	0.747	1/4	0.268	0.232	0.125	0.03	7	0.143	0.062	0.055	0.265
7/16	0.4375	0.452	0.421	5/8	0.625	0.603	0.884	0.828	19/64	0.316	0.278	0.156	0.03	7	0.143	0.062	0.055	0.328
1/2	0.5000	0.515	0.482	3/4	0.750	0.725	1.061	0.995	21/64	0.348	0.308	0.156	0.03	6	0.167	0.072	0.064	0.371
5/8	0.6250	0.642	0.605	15/16	0.938	0.906	1.326	1.244	27/64	0.444	0.400	0.312	0.06	5	0.200	0.086	0.077	0.471
3/4	0.7500	0.768	0.729	1 1/8	1.125	1.088	1.591	1.494	1/2	0.524	0.476	0.375	0.06	4 1/2	0.222	0.096	0.085	0.579
7/8	0.8750	0.895	0.852	1 5/16	1.312	1.269	1.856	1.742	19/42	0.620	0.568	0.375	0.06	4	0.250	0.108	0.096	0.683
1	1.0000	1.022	0.976	1 1/2	1.500	1.450	2.121	1.991	21/32	0.684	0.628	0.625	0.09	3 1/2	0.286	0.123	0.110	0.780
1 1/8	1.1250	1.149	1.098	1 11/16	1.688	1.631	2.386	2.239	3/4	0.780	0.720	0.625	0.09	3 1/4	0.308	0.133	0.119	0.887
1 1/4	1.2500	1.277	1.223	1 7/8	1.875	1.812	2.652	2.489	27/32	0.876	0.812	0.625	0.09	3 1/4	0.308	0.133	0.119	1.012

[a] When specifying decimal nominal size, zeros before decimal point and in fourth decimal place are omitted.

All dimensions in inches.

Minimum thread length is ½ length of screw plus 0.50 inch, or 6.00 inches, whichever is shorter. Screws too short for the formula thread length shall be threaded as close to the head as practicable.

Thread formulas: Pitch = 1 ÷ thds. per inch. Flat at root = 0.4305 × pitch. Depth of single thread = 0.385 × pitch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Hex Lag Screws *ANSI/ASME B18.2.1-1996*



Nominal Size[a] or Basic Product Dia.		Body or Shoulder Dia. *E*		Width Across Flats *F*			Width Across Corners *G*		Height *H*			Shoulder Length *S*	Radius of Fillet *R*	Thds. per Inch	Thread Dimensions			
		Max.	Min.	Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Min.	Max.		Pitch *P*	Flat at Root *B*	Depth of Thd. *T*	Root Dia. D_1
No. 10	0.1900	0.199	0.178	9/32	0.281	0.271	0.323	0.309	1/8	0.140	0.110	0.094	0.03	11	0.091	0.039	0.035	0.120
1/4	0.2500	0.260	0.237	3/8	0.438	0.425	0.505	0.484	11/64	0.188	0.150	0.094	0.03	10	0.100	0.043	0.039	0.173
5/16	0.3125	0.324	0.298	1/2	0.500	0.484	0.577	0.552	7/32	0.235	0.195	0.125	0.03	9	0.111	0.048	0.043	0.227
3/8	0.3750	0.388	0.360	9/16	0.562	0.544	0.650	0.620	1/4	0.268	0.226	0.125	0.03	7	0.143	0.062	0.055	0.265
7/16	0.4375	0.452	0.421	5/8	0.625	0.603	0.722	0.687	19/64	0.316	0.272	0.156	0.03	7	0.143	0.062	0.055	0.328
1/2	0.5000	0.515	0.482	3/4	0.750	0.725	0.866	0.826	11/32	0.364	0.302	0.156	0.03	6	0.167	0.072	0.064	0.371
5/8	0.6250	0.642	0.605	15/16	0.938	0.906	1.083	1.033	27/64	0.444	0.378	0.312	0.06	5	0.200	0.086	0.077	0.471
3/4	0.7500	0.768	0.729	1 1/8	1.125	1.088	1.299	1.240	1/2	0.524	0.455	0.375	0.06	4 1/2	0.222	0.096	0.085	0.579
7/8	0.8750	0.895	0.852	1 5/16	1.312	1.269	1.516	1.447	37/64	0.604	0.531	0.375	0.06	4	0.250	0.108	0.096	0.683
1	1.0000	1.022	0.976	1 1/2	1.500	1.450	1.732	1.653	43/64	0.700	0.591	0.625	0.09	3 1/2	0.286	0.123	0.110	0.780
1 1/8	1.1250	1.149	1.098	1 11/16	1.688	1.631	1.949	1.859	3/4	0.780	0.658	0.625	0.09	3 1/4	0.308	0.133	0.119	0.887
1 1/4	1.2500	1.277	1.223	1 7/8	1.875	1.812	2.165	2.066	27/32	0.876	0.749	0.625	0.09	3 1/4	0.308	0.133	0.119	1.012

[a] When specifying decimal nominal size, zeros before decimal point and in fourth decimal place are omitted.

All dimensions in inches.

Minimum thread length is ½ length of screw plus 0.50 inch, or 6.00 inches, whichever is shorter. Screws too short for the formula thread length shall be threaded as close to the head as practicable.

Thread formulas: Pitch = 1 ÷ thds. per inch. Flat at root = 0.4305 × pitch. Depth of single thread = 0.385 × pitch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard and Unified Standard Hex Nuts and Jam Nuts and Heavy Hex Nuts and Jam Nuts *ANSI/ASME B18.2.2-1987 (R1999)*

Nominal Size or Basic Major Dia. of Thread		Width Across Flats *F*			Width Across Corners *G*		Thickness, Nuts *H*			Thickness Jam Nuts H_1		
		Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Basic	Max.	Min.
Hex Nuts (Fig. 5) and Hex Jam Nuts (Fig. 6)												
1/4	**0.2500**	**7/16**	**0.438**	**0.428**	**0.505**	**0.488**	**7/32**	**0.226**	**0.212**	**5/32**	**0.163**	**0.150**
5/16	**0.3125**	**1/2**	**0.500**	**0.489**	**0.577**	**0.557**	**17/64**	**0.273**	**0.258**	**3/16**	**0.195**	**0.180**
3/8	**0.3750**	**9/16**	**0.562**	**0.551**	**0.650**	**0.628**	**21/64**	**0.337**	**0.320**	**7/32**	**0.227**	**0.210**
7/16	**0.4375**	**11/16**	**0.688**	**0.675**	**0.794**	**0.768**	**3/8**	**0.385**	**0.365**	**1/4**	**0.260**	**0.240**
1/2	**0.5000**	**3/4**	**0.750**	**0.736**	**0.866**	**0.840**	**7/16**	**0.448**	**0.427**	**5/16**	**0.323**	**0.302**
9/16	**0.5625**	**7/8**	**0.875**	**0.861**	**1.010**	**0.982**	**31/64**	**0.496**	**0.473**	**5/16**	**0.324**	**0.301**
5/8	**0.6250**	**15/16**	**0.938**	**0.922**	**1.083**	**1.051**	**35/64**	**0.559**	**0.535**	**3/8**	**0.387**	**0.363**
3/4	**0.7500**	**1 1/8**	**1.125**	**1.088**	**1.299**	**1.240**	**41/64**	**0.665**	**0.617**	**27/64**	**0.446**	**0.398**
7/8	**0.8750**	**1 5/16**	**1.312**	**1.269**	**1.516**	**1.447**	**3/4**	**0.776**	**0.724**	**31/64**	**0.510**	**0.458**
1	**1.0000**	**1 1/2**	**1.500**	**1.450**	**1.732**	**1.653**	**55/64**	**0.887**	**0.831**	**35/64**	**0.575**	**0.519**
1 1/8	**1.1250**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	**31/32**	**0.999**	**0.939**	**39/64**	**0.639**	**0.579**
1 1/4	**1.2500**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**1 1/16**	**1.094**	**1.030**	**23/32**	**0.751**	**0.687**
1 3/8	**1.3750**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**1 11/64**	**1.206**	**1.138**	**25/32**	**0.815**	**0.747**
1 1/2	**1.5000**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**1 9/32**	**1.317**	**1.245**	**27/32**	**0.880**	**0.808**
Heavy Hex Nuts (Fig. 5) and Heavy Hex Jam Nuts (Fig. 6)												
1/4	0.2500	1/2	0.500	0.488	0.577	0.556	15/64	0.250	0.218	11/64	0.188	0.156
5/16	0.3125	9/16	0.562	0.546	0.650	0.622	19/64	0.314	0.280	13/64	0.220	0.186
3/8	0.3750	11/16	0.688	0.669	0.794	0.763	23/64	0.377	0.341	15/64	0.252	0.216
7/16	0.4375	3/4	0.750	0.728	0.866	0.830	27/64	0.441	0.403	17/64	0.285	0.247
1/2	**0.5000**	**7/8**	**0.875**	**0.850**	**1.010**	**0.969**	**31/64**	**0.504**	**0.464**	**19/64**	**0.317**	**0.277**
9/16	0.5625	15/16	0.938	0.909	1.083	1.037	35/64	0.568	0.526	21/64	0.349	0.307
5/8	**0.6250**	**1 1/16**	**1.062**	**1.031**	**1.227**	**1.1175**	**39/64**	**0.631**	**0.587**	**23/64**	**0.381**	**0.337**
3/4	**0.7500**	**1 1/4**	**1.250**	**1.212**	**1.443**	**1.382**	**47/64**	**0.758**	**0.710**	**27/64**	**0.446**	**0.398**
7/8	**0.8750**	**1 7/16**	**1.438**	**1.394**	**1660**	**1.589**	**55/64**	**0.885**	**0.833**	**31/64**	**0.510**	**0.458**
1	**1.0000**	**1 5/8**	**1.625**	**1.575**	**1.876**	**1.796**	**63/64**	**1.012**	**0.956**	**35/64**	**0.575**	**0.519**
1 1/8	**1.1250**	**1 13/16**	**1.812**	**1.756**	**2.093**	**2.002**	**1 7/64**	**1.139**	**1.079**	**39/64**	**0.639**	**0.579**
1 1/4	**1.2500**	**2**	**2.000**	**1.938**	**2.309**	**2.209**	**1 7/32**	**1.251**	**1.187**	**23/32**	**0.751**	**0.687**
1 3/8	**1.3750**	**2 3/16**	**2.188**	**2.119**	**2.526**	**2.416**	**1 11/32**	**1.378**	**1.310**	**25/32**	**0.815**	**0.747**
1 1/2	**1.5000**	**2 3/8**	**2.375**	**2.300**	**2.742**	**2.622**	**1 15/32**	**1.505**	**1.433**	**27/32**	**0.880**	**0.808**
1 5/8	1.6250	2 9/16	2.562	2.481	2.959	2.828	1 19/32	1.632	1.556	29/32	0.944	0.868
1 3/4	**1.7500**	**2 3/4**	**2.750**	**2.662**	**3.175**	**3.035**	**1 23/32**	**1.759**	**1.679**	**31/32**	**1.009**	**0.929**
1 7/8	1.8750	2 15/16	2.938	2.844	3.392	3.242	1 27/32	1.886	1.802	1 1/32	1.073	0.989
2	**2.0000**	**3 1/8**	**3.125**	**3.025**	**3.608**	**3.449**	**1 31/32**	**2.013**	**1.925**	**1 3/32**	**1.138**	**1.050**
2 1/4	2.2500	3 1/2	3.500	3.388	4.041	3.862	2 1/64	2.251	2.155	1 13/64	1.251	1.155
2 1/2	2.5000	3 7/8	3.875	3.750	4.474	4.275	2 29/64	2.505	2.401	1 29/64	1.505	1.401
2 3/4	2.7500	4 1/4	4.250	4.112	4.907	4.688	2 45/64	2.759	2.647	1 37/64	1.634	1.522
3	3.0000	4 5/8	4.625	4.475	5.340	5.102	2 61/64	3.013	2.893	1 45/64	1.763	1.643
3 1/4	3.2500	5	5.000	4.838	5.774	5.515	3 3/16	3.252	3.124	1 13/16	1.876	1.748
3 1/2	3.5000	5 3/8	5.375	5.200	6.207	5.928	3 7/16	3.506	3.370	1 15/16	2.006	1.870
3 3/4	3.7500	5 3/4	5.750	5.562	6.640	6.341	3 11/16	3.760	3.616	2 1/16	2.134	1.990
4	4.0000	6 1/8	6.125	5.925	7.073	6.755	3 15/16	4.014	3.862	2 3/16	2.264	2.112

All dimensions are in inches.

Bold type shows nuts unified dimensionally with British and Canadian Standards.

Threads are Unified Coarse-, Fine-, or 8-thread series (UNC, UNF or 8UN), Class 2B. Unification of fine-thread nuts is limited to sizes 1 inch and under.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. American National Standard and Unified Standard Hex Flat Nuts and Flat Jam Nuts and Heavy Hex Flat Nuts and Flat Jam Nuts
ANSI/ASME B18.2.2-1987 (R1999)

Nominal Size or Basic Major Dia. of Thread		Width Across Flats F			Width Across Corners G		Thickness, Flat Nuts H			Thickness, Flat Jam Nuts H_1		
		Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Basic	Max.	Min.
Hex Flat Nuts and Hex Flat Jam Nuts (Fig. 7)												
1 1/8	**1.1250**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	**1**	**1.030**	**0.970**	**5/8**	**0.655**	**0.595**
1 1/4	**1.2500**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**1 3/32**	**1.126**	**1.062**	**3/4**	**0.782**	**0.718**
1 3/8	**1.3750**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**1 13/64**	**1.237**	**1.169**	**13/16**	**0.846**	**0.778**
1 1/2	**1.5000**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**1 5/16**	**1.348**	**1.276**	**7/8**	**0.911**	**0.839**
Heavy Hex Flat Nuts and Heavy Hex Flat Jam Nuts (Fig. 7)												
1 1/8	**1.1250**	**1 13/16**	**1.812**	**1.756**	**2.093**	**2.002**	**1 1/8**	**1.155**	**1.079**	**5/8**	**0.655**	**0.579**
1 1/4	**1.2500**	**2**	**2.000**	**1.938**	**2.309**	**2.209**	**1 1/4**	**1.282**	**1.187**	**3/4**	**0.782**	**0.687**
1 3/8	**1.3750**	**2 3/16**	**2.188**	**2.119**	**2.526**	**2.416**	**1 3/8**	**1.409**	**1.310**	**13/16**	**0.846**	**0.747**
1 1/2	**1.5000**	**2 3/8**	**2.375**	**2.300**	**2.742**	**2.622**	**1 1/2**	**1.536**	**1.433**	**7/8**	**0.911**	**0.808**
1 3/4	**1.7500**	**2 3/4**	**2.750**	**2.662**	**3.175**	**3.035**	**1 3/4**	**1.790**	**1.679**	**1**	**1.040**	**0.929**
2	**2.0000**	**3 1/8**	**3.125**	**3.025**	**3.608**	**3.449**	**2**	**2.044**	**1.925**	**1 1/8**	**1.169**	**1.050**
2 1/4	2.2500	3 1/2	3.500	3.388	4.041	3.862	2 1/4	2.298	2.155	1 1/4	1.298	1.155
2 1/2	2.5000	3 7/8	3.875	3.750	4.474	4.275	2 1/2	2.552	2.401	1 1/2	1.552	1.401
2 3/4	2.7500	4 1/4	4.250	4.112	4.907	4.688	2 3/4	2.806	2.647	1 5/8	1.681	1.522
3	3.0000	4 5/8	4.625	4.475	5.340	5.102	3	3.060	2.893	1 3/4	1.810	1.643
3 1/4	3.2500	5	5.000	4.838	5.774	5.515	3 1/4	3.314	3.124	1 7/8	1.939	1.748
3 1/2	3.5000	5 3/8	5.375	5.200	6.207	5.928	3 1/2	3.568	3.370	2	2.068	1.870
3 3/4	3.7500	5 3/4	5.750	5.562	6.640	6.341	3 3/4	3.822	3.616	2 1/4	2.197	1.990
4	4.0000	6 1/8	6.125	5.925	7.073	6.755	4	4.076	3.862	2 1/4	2.326	2.112

All dimensions are in inches.

Bold type indicates nuts unified dimensionally with British and Canadian Standards.

Threads are Unified Coarse-thread series (UNC), Class 2B.



Fig. 7. Hex Flat Nuts, Heavy Hex Flat Nuts, Hex Flat Jam Nuts, and Heavy Hex Flat Jam Nuts (Table 8)



Fig. 8. Hex Slotted Nuts, Heavy Hex Slotted Nuts, and Hex Thick Slotted Nuts (Table 9)



Fig. 9. Hex Thick Nuts (Table 10)



Fig. 10. Square Nuts, Heavy Square Nuts (Table 10)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National and Unified Standard Hex Slotted Nuts, Heavy Hex Slotted Nuts, and Hex Thick Slotted Nuts *ANSI/ASME B18.2.2-1987 (R1999)*

Nominal Size or Basic Major Dia. of Thread		Width Across Flats *F*			Width Across Corners *G*		Thickness *H*			Unslotted Thickness *T*		Width of Slot *S*	
		Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.	Max.	Min.	Max.	Min.
Hex Slotted Nuts (Fig. 8)													
1/4	**0.2500**	7/16	**0.438**	**0.428**	**0.505**	**0.488**	7/32	**0.226**	**0.212**	0.14	0.12	0.10	0.07
5/16	**0.3125**	1/2	**0.500**	**0.489**	**0.577**	**0.557**	17/64	**0.273**	**0.258**	0.18	0.16	0.12	0.09
3/8	**0.3750**	9/16	**0.562**	**0.551**	**0.650**	**0.628**	21/64	**0.337**	**0.320**	0.21	0.19	0.15	0.12
7/16	**0.4375**	11/16	**0.688**	**0.675**	**0.794**	**0.768**	3/8	**0.385**	**0.365**	0.23	0.21	0.15	0.12
1/2	**0.5000**	3/4	**0.750**	**0.736**	**0.866**	**0.840**	7/16	**0.448**	**0.427**	0.29	0.27	0.18	0.15
9/16	**0.5625**	7/8	**0.875**	**0.861**	**1.010**	**0.982**	31/64	**0.496**	**0.473**	0.31	0.29	0.18	0.15
5/8	**0.6250**	15/16	**0.938**	**0.922**	**1.083**	**1.051**	35/64	**0.559**	**0.535**	0.34	0.32	0.24	0.18
3/4	**0.7500**	**1 1/8**	**1.125**	**1.088**	**1.299**	**1.240**	41/64	**0.665**	**0.617**	0.40	0.38	0.24	0.18
7/8	**0.8750**	**1 5/16**	**1.312**	**1.269**	**1.516**	**1.447**	3/4	**0.776**	**0.724**	0.52	0.49	0.24	0.18
1	**1.0000**	**1 1/2**	**1.500**	**1.450**	**1.732**	**1.653**	55/64	**0.887**	**0.831**	0.59	0.56	0.30	0.24
1 1/8	**1.1250**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	31/32	**0.999**	**0.939**	0.64	0.61	0.33	0.24
1 1/4	**1.2500**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**1 1/16**	**1.094**	**1.030**	0.70	0.67	0.40	0.31
1 3/8	**1.3750**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**1 11/64**	**1.206**	**1.138**	0.82	0.78	0.40	0.31
1 1/2	**1.5000**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**1 9/32**	**1.317**	**1.245**	0.86	0.82	0.46	0.37
Heavy Hex Slotted Nuts (Fig. 8)													
1/4	0.2500	1/2	0.500	0.488	0.577	0.556	15/64	0.250	0.218	0.15	0.13	0.10	0.07
5/16	0.3125	9/16	0.562	0.546	0.650	0.622	19/64	0.314	0.280	0.21	0.19	0.12	0.09
3/8	0.3750	11/16	0.688	0.669	0.794	0.763	23/64	0.377	0.341	0.24	0.22	0.15	0.12
7/16	0.4375	3/4	0.750	0.728	0.866	0.830	27/64	0.441	0.403	0.28	0.26	0.15	0.12
1/2	**0.5000**	7/8	**0.875**	**0.850**	**1.010**	**0.969**	31/64	**0.504**	**0.464**	0.34	0.32	0.18	0.15
9/16	0.5625	15/16	0.938	0.909	1.083	1.037	35/64	0.568	0.526	0.37	0.35	0.18	0.15
5/8	**0.6250**	**1 1/16**	**1.062**	**1.031**	**1.227**	**1.175**	39/64	**0.631**	**0.587**	0.40	0.38	0.24	0.18
3/4	**0.7500**	**1 1/4**	**1.250**	**1.212**	**1.443**	**1.382**	47/64	**0.758**	**0.710**	0.49	0.47	0.24	0.18
7/8	**0.8750**	**1 7/16**	**1.438**	**1.394**	**1.660**	**1.589**	55/64	**0.885**	**0.833**	0.62	0.59	0.24	0.18
1	**1.0000**	**1 5/8**	**1.625**	**1.575**	**1.876**	**1.796**	63/64	**1.012**	**0.956**	0.72	0.69	0.30	0.24
1 1/8	**1.1250**	**1 13/16**	**1.812**	**1.756**	**2.093**	**2.002**	**1 7/64**	**1.139**	**1.079**	0.78	0.75	0.33	0.24
1 1/4	**1.2500**	**2**	**2.000**	**1.938**	**2.309**	**2.209**	**1 7/32**	**1.251**	**1.187**	0.86	0.83	0.40	0.31
1 3/8	**1.3750**	**2 3/16**	**2.188**	**2.119**	**2.526**	**2.416**	**1 11/32**	**1.378**	**1.310**	0.99	0.95	0.40	0.31
1 1/2	**1.5000**	**2 3/8**	**2.375**	**2.300**	**2.742**	**2.622**	**1 15/32**	**1.505**	**1.433**	1.05	1.01	0.46	0.37
1 3/4	**1.7500**	**2 3/4**	**2.750**	**2.662**	**3.175**	**3.035**	**1 23/32**	**1.759**	**1.679**	1.24	1.20	0.52	0.43
2	**2.0000**	**3 1/8**	**3.125**	**3.025**	**3.608**	**3.449**	**1 31/32**	**2.013**	**1.925**	1.43	1.38	0.52	0.43
2 1/4	2.2500	3 1/2	3.500	3.388	4.041	3.862	2 13/64	2.251	2.155	1.67	1.62	0.52	0.43
2 1/2	2.5000	3 7/8	3.875	3.750	4.474	4.275	2 29/64	2.505	2.401	1.79	1.74	0.64	0.55
2 3/4	2.7500	4 1/4	4.250	4.112	4.907	4.688	2 45/64	2.759	2.647	2.05	1.99	0.64	0.55
3	3.0000	4 5/8	4.625	4.475	5.340	5.102	2 61/64	3.013	2.893	2.23	2.17	0.71	0.62
3 1/4	3.2500	5	5.000	4.838	5.774	5.515	3 3/16	3.252	3.124	2.47	2.41	0.71	0.62
3 1/2	3.5000	5 3/8	5.375	5.200	6.207	5.928	3 7/16	3.506	3.370	2.72	2.65	0.71	0.62
3 3/4	3.7500	5 3/4	5.750	5.562	6.640	6.341	3 11/16	3.760	3.616	2.97	2.90	0.71	0.62
4	4.0000	6 1/8	6.125	5.925	7.073	6.755	3 15/16	4.014	3.862	3.22	3.15	0.71	0.62
Hex Thick Slotted Nuts (Fig. 8)													
1/4	**0.2500**	7/16	**0.438**	**0.428**	**0.505**	**0.488**	9/32	**0.288**	**0.274**	0.20	0.18	0.10	0.07
5/16	**0.3125**	1/2	**0.500**	**0.489**	**0.577**	**0.557**	21/64	**0.336**	**0.320**	0.24	0.22	0.12	0.09
3/8	**0.3750**	9/16	**0.562**	**0.551**	**0.650**	**0.628**	13/32	**0.415**	**0.398**	0.29	0.27	0.15	0.12
7/16	**0.4375**	11/16	**0.688**	**0.675**	**0.794**	**0.768**	29/64	**0.463**	**0.444**	0.31	0.29	0.15	0.12
1/2	**0.5000**	3/4	**0.750**	**0.736**	**0.866**	**0.840**	9/16	**0.573**	**0.552**	0.42	0.40	0.18	0.15
9/16	**0.5625**	7/8	**0.875**	**0.861**	**1.010**	**0.982**	39/64	**0.621**	**0.598**	0.43	0.41	0.18	0.15
5/8	**0.6250**	15/16	**0.938**	**0.922**	**1.083**	**1.051**	23/32	**0.731**	**0.706**	0.51	0.49	0.24	0.18
3/4	**0.7500**	**1 1/8**	**1.125**	**1.088**	**1.299**	**1.240**	13/16	**0.827**	**0.798**	0.57	0.55	0.24	0.18
7/8	**0.8750**	**1 5/16**	**1.312**	**1.269**	**1.516**	**1.447**	29/32	**0.922**	**0.890**	0.67	0.64	0.24	0.18
1	**1.0000**	**1 1/2**	**1.500**	**1.450**	**1.732**	**1.653**	**1**	**1.018**	**0.982**	0.73	0.70	0.30	0.24
1 1/8	**1.1250**	**1 11/16**	**1.688**	**1.631**	**1.949**	**1.859**	**1 5/32**	**1.176**	**1.136**	0.83	0.80	0.33	0.24
1 1/4	**1.2500**	**1 7/8**	**1.875**	**1.812**	**2.165**	**2.066**	**1 1/4**	**1.272**	**1.228**	0.89	0.86	0.40	0.31
1 3/8	**1.3750**	**2 1/16**	**2.062**	**1.994**	**2.382**	**2.273**	**1 3/8**	**1.399**	**1.351**	1.02	0.98	0.40	0.31
1 1/2	**1.5000**	**2 1/4**	**2.250**	**2.175**	**2.598**	**2.480**	**1 1/2**	**1.526**	**1.474**	1.08	1.04	0.46	0.37

All dimensions are in inches.

Bold type indicates nuts unified dimensionally with British and Canadian Standards.

Threads are Unified Coarse-, Fine-, or 8-thread series (UNC, UNF, or 8UN), Class 2B.

Unification of fine-thread nuts is limited to sizes 1 inch and under.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. American National and Unified Standard Square Nuts and Heavy Square Nuts and American National Standard Hex Thick Nuts

ANSI/ASME B18.2.2-1987 (R1999)

Nominal Size or Basic Major Dia. of Thread		Width Across Flats *F*			Width Across Corners *G*		Thickness *H*		
		Basic	Max.	Min.	Max.	Min.	Basic	Max.	Min.
Square Nuts[a] (Fig. 10)									
1/4	**0.2500**	**7/16**	**0.438**	**0.425**	**0.619**	**0.554**	**7/32**	**0.235**	**0.203**
5/16	**0.3125**	**9/16**	**0.562**	**0.547**	**0.795**	**0.721**	**17/64**	**0.283**	**0.249**
3/8	**0.3750**	**5/8**	**0.625**	**0.606**	**0.884**	**0.802**	**21/64**	**0.346**	**0.310**
7/16	**0.4375**	**3/4**	**0.750**	**0.728**	**1.061**	**0.970**	**3/8**	**0.394**	**0.356**
1/2	**0.5000**	**13/16**	**0.812**	**0.788**	**1.149**	**1.052**	**7/16**	**0.458**	**0.418**
5/8	**0.6250**	**1**	**1.000**	**0.969**	**1.414**	**35/64**	**0.569**	**0.525**	
3/4	**0.7500**	**1 1/8**	**1.125**	**1.088**	**1.591**	**1.464**	**21/32**	**0.680**	**0.632**
7/8	**0.8750**	**1 5/16**	**1.312**	**1.269**	**1.856**	**1.712**	**49/64**	**0.792**	**0.740**
1	**1.0000**	**1 1/2**	**1.500**	**1.450**	**2.121**	**1.961**	**7/8**	**0.903**	**0.847**
1 1/8	**1.1250**	**1 11/16**	**1.688**	**1.631**	**2.386**	**2.209**	**1**	**1.030**	**0.970**
1 1/4	**1.2500**	**1 7/8**	**1.875**	**1.812**	**2.652**	**2.458**	**1 3/32**	**1.126**	**1.062**
1 3/8	**1.3750**	**2 1/16**	**2.062**	**1.994**	**2.917**	**2.708**	**1 13/64**	**1.237**	**1.169**
1 1/2	**1.5000**	**2 1/4**	**2.250**	**2.175**	**3.182**	**2.956**	**1 5/16**	**1.348**	**1.276**
Heavy Square Nuts[a] (Fig. 10)									
1/4	0.2500	1/2	0.500	0.488	0.707	0.640	1/4	0.266	0.218
5/16	0.3125	9/16	0.562	0.546	0.795	0.720	5/16	0.330	0.280
3/8	0.3750	11/16	0.688	0.669	0.973	0.889	3/8	0.393	0.341
7/16	0.4375	3/4	0.750	0.728	1.060	0.970	7/16	0.456	0.403
1/2	0.5000	7/8	0.875	0.850	1.237	1.137	1/2	0.520	0.464
5/8	0.6250	1 1/16	1.062	1.031	1.503	1.386	5/8	0.647	0.587
3/4	0.7500	1 1/4	1.250	1.212	1.768	1.635	3/4	0.774	0.710
7/8	0.8750	1 7/16	1.438	1.394	2.033	1.884	7/8	0.901	0.833
1	1.0000	1 5/8	1.625	1.575	2.298	2.132	1	1.028	0.956
1 1/8	1.1250	1 13/16	1.812	1.756	2.563	2.381	1 1/8	1.155	1.079
1 1/4	1.2500	2	2.000	1.938	2.828	2.631	1 1/4	1.282	1.187
1 3/8	1.3750	2 3/16	2.188	2.119	3.094	2.879	1 3/8	1.409	1.310
1 1/2	1.5000	2 3/8	2.375	2.300	3.359	3.128	1 1/2	1.536	1.433
Hex Thick Nuts[b] (Fig. 10)									
1/4	0.2500	7/16	0.438	0.428	0.505	0.488	9/32	0.288	0.274
5/16	0.3125	1/2	0.500	0.489	0.577	0.557	21/64	0.336	0.320
3/8	0.3750	9/16	0.562	0.551	0.650	0.628	13/32	0.415	0.398
7/16	0.4375	11/16	0.688	0.675	0.794	0.768	29/64	0.463	0.444
1/2	0.5000	3/4	0.750	0.736	0.866	0.840	9/16	0.573	0.552
9/16	0.5625	7/8	0.875	0.861	1.010	0.982	37/64	0.621	0.598
5/8	0.6250	15/16	0.938	0.922	1.083	1.051	23/32	0.731	0.706
3/4	0.7500	1 1/8	1.125	1.088	1.299	1.240	13/16	0.827	0.798
7/8	0.8750	1 5/16	1.312	1.269	1.516	1.447	29/32	0.922	0.890
1	1.0000	1 1/2	1.500	1.450	1.732	1.653	1	1.018	0.982
1 1/8	1.1250	1 11/16	1.688	1.631	1.949	1.859	1 5/32	1.176	1.136
1 1/4	1.2500	1 7/8	1.875	1.812	2.165	2.066	1 1/4	1.272	1.228
1 3/8	1.3750	2 1/16	2.062	1.994	2.382	2.273	1 3/8	1.399	1.351
1 1/2	1.5000	2 1/4	2.250	2.175	2.598	2.480	1 1/2	1.526	1.474

[a] Coarse-thread series, Class 2B.

[b] Unified Coarse-, Fine-, or 8-thread series (8 UN), Class 2B.

All dimensions are in inches.

Bold type indicates nuts unified dimensionally with British and Canadian Standards.

Copyright 2004, Industrial Press, Inc., New York, NY

Low and High Crown (Blind, Acorn) Nuts *SAE Recommended Practice J483a*



Low Crown

Nom. Size[a] or Basic Major Dia. of Thread		Width Across Flats, *F*			WidthAcross Corners, *G*		Body Dia., *A*	Over-all Hgt., *H*	Hexa-gon Hgt., *Q*	Nose Rad., *R*	Body Rad., *S*	Drill Dep., *T*	Full Thd., *U*
		Max.	(Basic)	Min.	Max.	Min.						Max.	Min.
6	0.1380	5/16	0.3125	0.302	0.361	0.344	0.30	0.34	0.16	0.08	0.17	0.25	0.16
8	0.1640	5/16	0.3125	0.302	0.361	0.344	0.30	0.34	0.16	0.08	0.17	0.25	0.16
10	0.1900	3/8	0.3750	0.362	0.433	0.413	0.36	0.41	0.19	0.09	0.22	0.28	0.19
12	0.2160	3/8	0.3750	0.362	0.433	0.413	0.36	0.41	0.19	0.09	0.22	0.31	0.22
1/4	0.2500	7/16	0.4375	0.428	0.505	0.488	0.41	0.47	0.22	0.11	0.25	0.34	0.25
5/16	0.3125	1/2	0.5000	0.489	0.577	0.557	0.47	0.53	0.25	0.12	0.28	0.41	0.31
3/8	0.3750	9/16	0.5625	0.551	0.650	0.628	0.53	0.62	0.28	0.14	0.33	0.45	0.38
7/16	0.4375	5/8	0.6250	0.612	0.722	0.698	0.59	0.69	0.31	0.16	0.36	0.52	0.44
1/2	0.5000	3/4	0.7500	0.736	0.866	0.840	0.72	0.81	0.38	0.19	0.42	0.59	0.50
9/16	0.5625	7/8	0.8750	0.861	1.010	0.982	0.84	0.94	0.44	0.22	0.50	0.69	0.56
5/8	0.6250	15/16	0.9375	0.922	1.083	1.051	0.91	1.00	0.47	0.23	0.53	0.75	0.62
3/4	0.7500	1 1/16	1.0625	1.045	1.227	1.191	1.03	1.16	0.53	0.27	0.59	0.88	0.75
7/8	0.8750	1 1/4	1.2500	1.231	1.443	1.403	1.22	1.36	0.62	0.31	0.70	1.00	0.88
1	1.0000	1 7/16	1.4375	1.417	1.660	1.615	1.41	1.55	0.72	0.36	0.81	1.12	1.00
1 1/8	1.1250	1 5/8	1.6250	1.602	1.876	1.826	1.59	1.75	0.81	0.41	0.92	1.31	1.12
1 1/4	1.2500	1 13/16	1.8125	1.788	2.093	2.038	1.78	1.95	0.91	0.45	1.03	1.44	1.25

High Crown

Nom. Size[a] or Basic Major Dia. of Thread		Width Across Flats, *F*			Width Across-Corners, *G*		Body Dia., *A*	Over-all Hgt., *H*	Hexa-gon Hgt. *Q*	Nose Rad., *R*	Body Rad., *S*	Drill Dep., *T*	Full Thd., *U*
		Max.	(Basic)	Min.	Max.	Min.						Max.	Min.
6	0.1380	5/16	0.3125	0.302	0.361	0.344	0.30	0.42	0.17	0.05	0.25	0.28	0.19
8	0.1640	5/16	0.3125	0.302	0.361	0.344	0.30	0.42	0.17	0.05	0.25	0.28	0.19
10	0.1900	3/8	0.3750	0.362	0.433	0.413	0.36	0.52	0.20	0.06	0.30	0.34	0.25
12	0.2160	3/8	0.3750	0.362	0.433	0.413	0.36	0.52	0.20	0.06	0.30	0.38	0.28
1/4	0.2500	7/16	0.4375	0.428	0.505	0.488	0.41	0.59	0.23	0.06	0.34	0.41	0.31
5/16	0.3125	1/2	0.5000	0.489	0.577	0.557	0.47	0.69	0.28	0.08	0.41	0.47	0.38
3/8	0.3750	9/16	0.5625	0.551	0.650	0.628	0.53	0.78	0.31	0.09	0.44	0.56	0.47
7/16	0.4375	5/8	0.6250	0.612	0.722	0.698	0.59	0.88	0.34	0.09	0.50	0.62	0.53
1/2	0.5000	3/4	0.7500	0.736	0.866	0.840	0.72	1.03	0.42	0.12	0.59	0.75	0.62
9/16	0.5625	7/8	0.8750	0.861	1.010	0.982	0.84	1.19	0.48	0.16	0.69	0.81	0.69
5/8	0.6250	15/16	0.9375	0.922	1.083	1.051	0.91	1.28	0.53	0.16	0.75	0.91	0.78
3/4	0.7500	1 1/16	1.0625	1.045	1.227	1.191	1.03	1.45	0.59	0.17	0.84	1.06	0.94
7/8	0.8750	1 1/4	1.12500	1.231	1.443	1.403	1.22	1.72	0.70	0.20	0.98	1.22	1.09
1	1.0000	1 7/16	1.4375	1.417	1.660	1.615	1.41	1.97	0.81	0.23	1.14	1.38	1.25
1 1/8	1.1250	1 5/8	1.6250	1.602	1.876	1.826	1.59	2.22	0.92	0.27	1.28	1.59	1.41
1 1/4	1.2500	1 13/16	1.8125	1.788	2.093	2.038	1.78	2.47	1.03	0.28	1.44	1.75	1.56

[a] When specifying a nominal size in decimals, any zero in the fourth decimal place is omitted.

Reprinted with permission. Copyright © 1990, Society of Automotive Engineers, Inc. All rights reserved.

All dimensions are in inches. Threads are Unified Standard Class 2B, UNC or UNF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Hex High and Hex Slotted High Nuts *SAE Standard J482a*



Nominal Size[a] or Basic Major Diameter of Thread		Width Across Flats, *F*			Width Across Corners, *G*		Slot Width, *S*	
		Basic	Max.	Min.	Max.	Min.	Min.	Max.
1/4	0.2500	7/16	0.4375	0.428	0.505	0.488	0.07	0.10
5/16	0.3125	1/2	0.5000	0.489	0.577	0.557	0.09	0.12
3/8	0.3750	9/16	0.5625	0.551	0.650	0.628	0.12	0.15
7/16	0.4375	11/16	0.6875	0.675	0.794	0.768	0.12	0.15
1/2	0.5000	3/4	0.7500	0.736	0.866	0.840	0.15	0.18
9/16	0.5625	7/8	0.8750	0.861	1.010	0.982	0.15	0.18
5/8	0.6250	15/16	0.9375	0.922	1.083	1.051	0.18	0.24
3/4	0.7500	1 1/8	1.1250	1.088	1.299	1.240	0.18	0.24
7/8	0.8750	1 5/16	1.3125	1.269	1.516	1.447	0.18	0.24
1	1.0000	1 1/2	1.5000	1.450	1.732	1.653	0.24	0.30
1 1/8	1.1250	1 11/16	1.6875	1.631	1.949	1.859	0.24	0.33
1 1/4	1.2500	1 7/8	1.8750	1.812	2.165	2.066	0.31	0.40

Nominal Size[a] or Basic Major Diameter of Thread		Thickness, *H*			Unslotted Thickness, *T*		Counterbore (Optional)	
		Basic	Max.	Min.	Max.	Min.	Dia., *A*	Depth, *D*
1/4	0.2500	3/8	0.382	0.368	0.29	0.27	0.266	0.062
5/16	0.3125	29/64	0.461	0.445	0.37	0.35	0.328	0.078
3/8	0.3750	1/2	0.509	0.491	0.38	0.36	0.391	0.094
7/16	0.4375	39/64	0.619	0.599	0.46	0.44	0.453	0.109
1/2	0.5000	21/32	0.667	0.645	0.51	0.49	0.516	0.125
9/16	0.5625	49/64	0.778	0.754	0.59	0.57	0.594	0.141
5/8	0.6250	27/32	0.857	0.831	0.63	0.61	0.656	0.156
3/4	0.7500	1	1.015	0.985	0.76	0.73	0.781	0.188
7/8	0.8750	1 5/32	1.172	1.140	0.92	0.89	0.906	0.219
1	1.0000	1 5/16	1.330	1.292	1.05	1.01	1.031	0.250
1 1/8	1.1250	1 1/2	1.520	1.480	1.18	1.14	1.156	0.281
1 1/4	1.2500	1 11/16	1.710	1.666	1.34	1.29	1.281	0.312

[a] When specifying a nominal size in decimals, any zero in the fourth decimal place is omitted.

Reprinted with permission. Copyright © 1990, *Society of Automotive Engineers, Inc. All rights reserved.*

All dimensions are in inches. Threads are Unified Standard Class 2B, UNC or UNF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Round Head and Round Head Square Neck Bolts

ANSI/ASME B18.5 –1990



Nominal Size	Body Dia., *E*		Dia. of Head, *A*		Height of Head, *H*		Fillet Rad., *R*	Width of Square, *O*		Depth of Square, *P*		Corner Rad. on Square, *Q*
	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Min.	Max.	Min.	Max.
No. 10	0.199	.182	.469	.438	.114	.094	.031	.199	.185	.125	.094	.031
1/4	0.260	.237	.594	.563	.145	.125	.031	.260	.245	.156	.125	.031
5/16	0.324	.298	.719	.688	.176	.156	.031	.324	.307	.187	.156	.031
3/8	0.388	.360	.844	.782	.208	.188	.031	.388	.368	.219	.188	.047
7/16	0.452	.421	.969	.907	.239	.219	.031	.452	.431	.250	.219	.047
1/2	0.515	.483	1.094	1.032	.270	.250	.031	.515	.492	.281	.250	.047
5/8	0.642	.605	1.344	1.219	.344	.313	.062	.642	.616	.344	.313	.078
3/4	0.768	.729	1.594	1.469	.406	.375	.062	.768	.741	.406	.375	.078
7/8	0.895	.852	1.844	1.719	.469	.438	.062	.895	.865	.469	.438	.094
1	1.022	.976	2.094	1.969	.531	.500	.062	1.022	.990	.531	.500	.094

All dimensions are in inches unless otherwise specified.

Threads are Unified Standard, Class 2A, UNC Series, in accordance with ANSI B1.1. For threads with additive finish, the maximum diameters of Class 2A shall apply before plating or coating, whereas the basic diameters (Class 2A maximum diameters plus the allowance) shall apply to a bolt after plating or coating.

Bolts are designated in the sequence shown: nominal size (number, fraction or decimal equivalent); threads per inch; nominal length (fraction or decimal equivalent); product name; material; and protective finish, if required.

i.e.: 1/2-13 × 3 Round Head Square Neck Bolt, Steel .375-16 × 2.50 Step Bolt, Steel, Zinc Plated

American National Standard T-Head Bolts *ANSI/ASME B18.5 –1990*



Nom. Size[a] or Basic Bolt Dia.		Body Dia., *E*		Head Length, *A*		Head Width, *B*		Head Height, *H*		Head Rad., *K*	Fillet Rad., *R*
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Basic	Max.
1/4	0.2500	.260	.237	.500	.488	.280	.245	.204	.172	.438	.031
5/16	0.3125	.324	.298	.625	.609	.342	.307	.267	.233	.500	.031
3/8	0.3750	.388	.360	.750	.731	.405	.368	.331	.295	.625	.031
7/16	0.4375	.452	.421	.875	.853	.468	.431	.394	.356	.875	.031
1/2	0.5000	.515	.483	1.000	.975	.530	.492	.458	.418	.875	.031
5/8	0.6250	.642	.605	1.250	1.218	.675	.616	.585	.541	1.062	.062
3/4	0.7500	.768	.729	1.500	1.462	.800	.741	.649	.601	1.250	.062
7/8	0.8750	.895	.852	1.750	1.706	.938	.865	.776	.724	1.375	.062
1	1.0000	1.022	.976	2.000	1.950	1.063	.990	.903	.847	1.500	.062

[a] Where specifying nominal size in decimals, zeros preceding the decimal point and in the fourth decimal place are omitted. For information as to threads and method of bolt designation, see footnotes to preceding table.

All dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Round Head Short Square Neck Bolts
ANSI/ASME B18.5-1990



Nominal Size	Body Dia., *E*		Head Dia., *A*		Head Height, *H*		Square Width, *O*		Squre Depth, *P*		Cor. Rad. on Sq., *Q*	Fillet Rad., *R*
	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Max
1/4	0.260	0.213	0.594	0.563	0.145	0.125	0.260	0.245	0.124	0.093	0.031	0.031
5/16	0.324	0.272	0.719	0.688	0.176	0.156	0.324	0.307	0.124	0.093	0.031	0.031
3/8	0.388	0.329	0.844	0.782	0.208	0.188	0.388	0.368	0.156	0.125	0.047	0.031
7/16	0.452	0.385	0.969	0.907	0.239	0.219	0.452	0.431	0.156	0.125	0.047	0.031
1/2	0.515	0.444	1.094	1.032	0.270	0.250	0.515	0.492	0.156	0.125	0.047	0.031
5/8	0.642	0.559	1.344	1.219	0.344	0.313	0.642	0.616	0.218	0.187	0.078	0.062
3/4	0.768	0.678	1.594	1.469	0.406	0.375	0.768	0.741	0.218	0.187	0.078	0.062

All dimensions are given in inches.

Threads are Unified Standard, Class 2A, UNC Series, in accordance with ANSI B1.1. For threads with additive finish, the maximum diameters of Class 2A apply before plating or coating, whereas the basic diameters (Class 2A maximum diameters plus the allowance) apply to a bolt after plating or coating.

Bolts are designated in the sequence shown: nominal size (number, fraction or decimal equivalent); threads per inch; nominal length (fraction or decimal equivalent); product name; material; and protective finish, if required. For example,

1/2-13 × 3 Round Head Short Square Neck Bolt, Steel

.375-16 × 2.50 Round Head Short Square Neck Bolt, Steel, Zinc Plated

American National Standard Round Head Fin Neck Bolts *ANSI/ASME B18.5-1990*



Nominal Size	Body Dia., *E*		Head Dia., *A*		Head Height, *H*		Fin Thick., *M*		Dist.Across Fins, *O*		Fin Depth, *P*	
	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min
No. 10	0.199	0.182	0.469	0.438	0.114	0.094	0.098	0.078	0.395	0.375	0.088	0.078
1/4	0.260	0.237	0.594	0.563	0.145	0.125	0.114	0.094	0.458	0.438	0.104	0.094
5/16	0.324	0.298	0.719	0.688	0.176	0.156	0.145	0.125	0.551	0.531	0.135	0.125
3/8	0.388	0.360	0.844	0.782	0.208	0.188	0.161	0.141	0.645	0.625	0.151	0.141
7/16	0.452	0.421	0.969	0.907	0.239	0.219	0.192	0.172	0.739	0.719	0.182	0.172
1/2	0.515	0.483	1.094	1.032	0.270	0.250	0.208	0.188	0.833	0.813	0.198	0.188

All dimensions are given in inches unless otherwise specified.

*Maximum fillet radius *R* is 0.031 inch for all sizes.

For information as to threads and method of bolt designation, see foonotes to the preceding table.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Round Head Ribbed Neck Bolts *ANSI/ASME B18.5–1990*



Nominal Size[a] or Basic Bolt Diameter		Body Diameter, *E*		Head Diameter, *A*		Head Height, *H*		Head to Ribs, *M*		Number of Ribs, *N*	Dia. Over Ribs, *O*	Depth Over Ribs, *P*			Fillet Radius, *R*
								For Lengths of				For Lengths of			
		Max	Min	Max	Min	Max	Min	⅞ in. and Shorter	1 in. and Longer	Approx	Min	⅞ in. and Shorter	1 in. and 1⅛ in.	¼ in. and Longer	Max[c]
								±0.031[b]				±0.031			
No. 10	0.1900	0.199	0.182	0.469	0.438	0.114	0.094	0.031†	0.063	9	0.210	0.250	0.407	0.594	0.031
¼	0.2500	0.260	0.237	0.594	0.563	0.145	0.125	0.031†	0.063	10	0.274	0.250	0.407	0.594	0.031
5/16	0.3125	0.324	0.298	0.719	0.688	0.176	0.156	0.031†	0.063	12	0.340	0.250	0.407	0.594	0.031
⅜	0.3750	0.388	0.360	0.844	0.782	0.208	0.188	0.031†	0.063	12	0.405	0.250	0.407	0.594	0.031
7/16	0.4375	0.452	0.421	0.969	0.907	0.239	0.219	0.031†	0.063	14	0.470	0.250	0.407	0.594	0.031
½	0.5000	0.515	0.483	1.094	1.032	0.270	0.250	0.031†	0.063	16	0.534	0.250	0.407	0.594	0.031
⅝	0.6250	0.642	0.605	1.344	1.219	0.344	0.313	0.094	0.094	19	0.660	0.313	0.438	0.625	0.062
¾	0.7500	0.768	0.729	1.594	1.469	0.406	0.375	0.094	0.094	22	0.785	0.313	0.438	0.625	0.062

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place shall be omitted.

[b] Tolerance on the No. 10 through ½ in. sizes for nominal lengths ⅞ in. and shorter shall be + 0.031 and – 0.000.

[c] The minimum radius is one half of the value shown.

All dimensions are given in inches unless otherwise specified.

For information as to threads and method of designating bolts, see following table.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Step and 114 Degree Countersunk Square Neck Bolts

ANSI/ASME B18.5 –1990





Nominal Size	Step & 114° Countersunk Bolts					Step Bolts							114° Countersunk Square Neck Bolts						
	Body Dia., *E*		Corner Rad. on Square, *Q*	Width of Square, *O*		Depth of Square, *P*		Dia. of Head, *A*		Height of Head, *H*		Fillet Radius, *R*	Depth of Square, *P*		Dia. of Head, *A*		Flat on Head, *F*	Height of Head, *H*	
	Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Min.	Max.	Min.	Min.	Max.	Min.
No. 10	0.199	0.182	0.031	0.199	0.185	0.125	0.094	0.656	0.625	0.114	0.094	0.031	0.125	0.094	0.548	0.500	0.015	0.131	0.112
1/4	0.260	0.237	0.031	0.260	0.245	0.156	0.125	0.844	0.813	0.145	0.125	0.031	0.156	0.125	0.682	0.625	0.018	0.154	0.135
5/16	0.324	0.298	0.031	0.324	0.307	0.187	0.156	1.031	1.000	0.176	0.156	0.031	0.219	0.188	0.821	0.750	0.023	0.184	0.159
3/8	0.388	0.360	0.047	0.388	0.368	0.219	0.188	1.219	1.188	0.208	0.188	0.031	0.250	0.219	0.960	0.875	0.027	0.212	0.183
7/16	0.452	0.421	0.047	0.452	0.431	0.250	0.219	1.406	1.375	0.239	0.219	0.031	0.281	0.250	1.093	1.000	0.030	0.235	0.205
1/2	0.515	0.483	0.047	0.515	0.492	0.281	0.250	1.594	1.563	0.270	0.250	0.031	0.312	0.281	1.233	1.125	0.035	0.265	0.229
5/8[a]	.642	0.605	0.078	0.642	0.616	…	…	…	…	…	…	…	0.406	0.375	1.495	1.375	0.038	0.316	0.272
3/4[a]	0.768	0.729	0.078	0.768	0.741	…	…	…	…	…	…	…	0.500	0.469	10.754	1.625	0.041	0.368	0.314

[a] These sizes pertain to 114 degree countersunk square neck bolts only. Dimensions given in last seven columns to the right are for these bolts only.

All dimensions are in inches unless otherwise specified.

Threads are Unified Standard, Class 2A, UNC Series, in accordance with ANSI B1.1. For threads with additive finish, the maximum diameters of Class 2A shall apply before plating or coating, whereas the basic diameters (Class 2A maximum diameters plus the allowance) shall apply to a bolt after plating or coating.

Bolts are designated in the sequence shown: nominal size (number, fraction or decimal equivalent); threads per inch; nominal length (fraction or decimal equivalent); product name; material; and protective finish, if required. For example

1/2-13 × 3 Round Head Square Neck Bolt, Steel .375-16 × 2.50 Step Bolt, Steel, Zinc Plated

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Countersunk Bolts and Slotted Countersunk Bolts

ANSI/ASME B18.5–1990



Nominal Size[a] or Basic Bolt Diameter		Body Diameter, *E*		Head Diameter, *A*			Flat on Min Dia. Head, *F*[b]
		Max	Min	Max Edge Sharp	Min Edge Sharp	Absolute Min Edge Rounded or Flat	Max
1/4	0.2500	0.260	0.237	0.493	0.477	0.445	0.018
5/16	0.3125	0.324	0.298	0.618	0.598	0.558	0.023
3/8	0.3750	0.388	0.360	0.740	0.715	0.668	0.027
7/16	0.4375	0.452	0.421	0.803	0.778	0.726	0.030
1/2	0.5000	0.515	0.483	0.935	0.905	0.845	0.035
5/8	0.6250	0.642	0.605	1.169	1.132	1.066	0.038
3/4	0.7500	0.768	0.729	1.402	1.357	1.285	0.041
7/8	0.8750	0.895	0.852	1.637	1.584	1.511	0.042
1	1.0000	1.022	0.976	1.869	1.810	1.735	0.043
1 1/8	1.1250	1.149	1.098	2.104	2.037	1.962	0.043
1 1/4	1.2500	1.277	1.223	2.337	2.262	2.187	0.043
1 3/8	1.3750	1.404	1.345	2.571	2.489	2.414	0.043
1 1/2	1.5000	1.531	1.470	2.804	2.715	2.640	0.043

Nom. Size or Basic Bolt Dia.		Head Height, *H*		Slot Width, *J*		Slot Depth, *T*	
		Max[c]	Min[d]	Max	Min	Max	Min
1/4	0.2500	0.150	0.131	0.075	0.064	0.068	0.045
5/16	0.3125	0.189	0.164	0.084	0.072	0.086	0.057
3/8	0.3750	0.225	0.196	0.094	0.081	0.103	0.068
7/16	0.4375	0.226	0.196	0.094	0.081	0.103	0.068
1/2	0.5000	0.269	0.233	0.106	0.091	0.103	0.068
5/8	0.6250	0.336	0.292	0.133	0.116	0.137	0.091
3/4	0.7500	0.403	0.349	0.149	0.131	0.171	0.115
7/8	0.8750	0.470	0.408	0.167	0.147	0.206	0.138
1	1.0000	0.537	0.466	0.188	0.166	0.240	0.162
1 1/8	1.1250	0.604	0.525	0.196	0.178	0.257	0.173
1 1/4	1.2500	0.671	0.582	0.211	0.193	0.291	0.197
1 3/8	1.3750	0.738	0.641	0.226	0.208	0.326	0.220
1 1/2	1.5000	0.805	0.698	0.258	0.240	0.360	0.244

[a] Where specifying size in decimals, zeros preceding decimal and in fourth decimal place are omitted.

[b] Flat on minimum diameter head calculated on minimum sharp and absolute minimum head diameters and 82° head angle.

[c] Maximum head height calculated on maximum sharp head diameter, basic bolt diameter, and 78° head angle.

[d] Minimum head height calculated on minimum sharp head diameter, basic bolt diameter, and 82° head angle.

All dimensions are given in inches.

For thread information and method of bolt designation see foonotes to previous table.

Heads are unslotted unless otherwise specified. For slot dimensions see Table 1 in Slotted Head Cap Screw section.

Copyright 2004, Industrial Press, Inc., New York, NY

Wrench Openings for Nuts *ANSI/ASME B18.2.2-1987 (R1999), Appendix*

Max. [a] Width Across Flats of Nut	Wrench Opening[b]		Max. [a] Width Across Flats of Nut	Wrench Opening[b]		Max. [a] Width Across Flats of Nut	Wrench Opening[b]	
	Min.	Max.		Min.	Max.		Min.	Max.
5/32	0.158	0.163	1 1/4	1.257	1.267	2 15/16	2.954	2.973
3/16	0.190	0.195	1 5/16	1.320	1.331	*3*	*3.016*	*3.035*
7/32	0.220	0.225	*1 3/8*	*1.383*	*1.394*	3 1/8	3.142	3.162
1/4	0.252	0.257	1 7/16	1.446	1.457	*3 3/8*	*3.393*	*3.414*
9/32	0.283	0.288	1 1/2	1.508	1.520	3 1/2	3.518	3.540
5/16	0.316	0.322	1 5/8	1.634	1.646	*3 3/4*	*3.770*	*3.793*
11/32	0.347	0.353	1 11/16	1.696	1.708	3 7/8	3.895	3.918
3/8	0.378	0.384	1 13/16	1.822	1.835	*4 1/8*	*4.147*	*4.172*
7/16	0.440	0.446	1 7/8	1.885	1.898	4 1/4	4.272	4.297
1/2	0.504	0.510	2	2.011	2.025	4 1/2	4.524	4.550
9/16	0.556	0.573	2 1/16	2.074	2.088	4 5/8	4.649	4.676
5/8	0.629	0.636	2 3/16	2.200	2.215	*4 7/8*	*4.900*	*4.928*
11/16	0.692	0.699	2 1/4	2.262	2.277	5	5.026	5.055
3/4	0.755	0.763	2 3/8	2.388	2.404	*5 1/4*	*5.277*	*5.307*
13/16	0.818	0.826	*2 7/16*	*2.450*	*2.466*	5 3/8	5.403	5.434
7/8	0.880	0.888	2 9/16	2.576	2.593	*5 5/8*	*5.654*	*5.686*
15/16	0.944	0.953	*2 5/8*	*2.639*	*2.656*	5 3/4	5.780	5.813
1	1.006	1.015	2 3/4	2.766	2.783	*6*	*6.031*	6.157
1/16	1.068	1.077	*2 13/16*	*2.827*	*2.845*	6 1/8	6.065	6.192
1 1/8	1.132	1.142						

[a] Wrenches are marked with the "Nominal Size of Wrench," which is equal to the basic or maximum width across flats of the corresponding nut. Minimum wrench opening is (1.005W + 0.001). Tolerance on wrench opening is (0.005W + 0.004) from minimum, where W equals nominal size of wrench.

[b] Openings for 5/32 to 3/8 widths from old ASA B18.2-1960 and italic values are from former ANSI B18.2.2-1972.

All dimensions given in inches.

Wrench Clearance Dimensions.— Wrench clearances are given in Tables 1 and 2. They are based on a wrench opening corresponding to the dimensions across the flats of the fastener. The listed values were obtained from a composite study of the alloy steel wrenches that are commercially available and military specifications. They are suitable for general use as minimum requirements.

Table 1. Wrench Clearances for Box Wrench—12 Point
From SAE Aeronautical Drafting Manual





Wrench Opening	A Min.	B Min.	C Ref.	D Max.	E Min.	Wrench Opening	A Min.	B Min.	C Ref.	D Max.	E Min.
0.156	0.190	0.280	0.030	0.156	100	0.781	0.690	1.140	0.030	0.594	2600
0.188	0.200	0.309	0.030	0.172	150	0.812	0.720	1.190	0.030	0.594	3000
0.250	0.270	0.410	0.030	0.250	150	0.875	0.750	1.260	0.030	0.594	3300
0.312	0.300	0.480	0.030	0.281	210	0.938	0.780	1.320	0.030	0.656	4100
0.344	0.300	0.500	0.030	0.281	250	1.000	0.810	1.390	0.030	0.718	4900
0.375	0.340	0.560	0.030	0.344	370	1.062	0.840	1.450	0.030	0.781	5400
0.438	0.400	0.650	0.030	0.359	650	1.125	0.950	1.600	0.030	0.844	5900
0.500	0.450	0.740	0.030	0.375	1020	1.250	0.980	1.700	0.030	0.875	7200
0.562	0.500	0.830	0.030	0.406	1200	1.312	1.090	1.850	0.030	0.906	8000
0.594	0.530	0.870	0.030	0.469	1200	1.438	1.220	2.050	0.030	1.000	8400
0.625	0.560	0.920	0.030	0.469	2000	1.500	1.270	2.140	0.030	1.062	10450
0.688	0.590	0.990	0.030	0.531	2300	1.625	1.340	2.280	0.030	1.156	11750
0.750	0.660	1.090	0.030	0.594	2600	…	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Wrench Clearances for Open End Engineers Wrench 15° and Socket Wrench (Regular Length)
From SAE Aeronautical Drafting Manual; © Society of Automotive Engineers, Inc.



Wrench Opening	Open End Engineers Wrench 15°									Socket (Regular Length)													Wrench Opening
												Q = .250			Q = .375			Q = .500			Q = .750		
	A Min.	B Max.	C Min.	D Min.	E Min.	F Max.	G Ref.	H Max.	J Min.	K Min.	L Ref.	M Max.	N Max.	P Min.	M Max.	N Max.	P Min.	M Max.	N Max.	P Min.	M Max.	N Max.	P Min.	
.156	.220	.250	.390	.160	.250	.200	.030	.094	25	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…
.188	.250	.280	.430	.190	.270	.230	.030	.172	40	.370	.030	1.000	.510	125	…	…	…	…	…	…	…	…	…	.188
.250	.280	.340	.530	.270	.310	.310	.030	.172	60	.470	.030	1.000	.510	200	1.250	.690	250	…	…	…	…	…	…	.250
.312	.380	.470	.660	.280	.390	.390	.050	.203	125	.550	.030	1.000	.510	300	1.250	.690	400	…	…	…	…	…	…	.312
.344	.420	.500	.750	.340	.450	.450	.050	.203	175	.580	.030	1.000	.519	450	1.250	.690	675	…	…	…	…	…	…	.344
.375	.420	.500	.780	.360	.450	.520	.050	.219	250	.620	.030	1.000	.580	550	1.250	.690	900	1.500	.880	1600	…	…	…	.375
.438	.470	.590	.890	.420	.520	.640	.050	.250	375	.750	.030	1.000	.683	550	1.250	.880	1250	1.500	.940	1700	…	…	…	.438
.500	.520	.640	1.000	.470	.580	.660	.050	.266	490	.810	.030	1.000	.692	600	1.250	.880	1450	1.500	.940	2000	…	…	…	.500
.562	.590	.770	1.130	.520	.660	.700	.050	.297	700	.870	.030	…	…	…	1.250	.932	1600	1.500	.940	2700	…	…	…	.562
.594	.640	.830	1.210	.530	.700	.700	.050	.344	800	.920	.030	…	…	…	1.250	.963	1750	1.562	.970	3000	…	…	…	.594
.625	.640	.830	1.230	.550	.700	.700	.050	.344	935	.950	.030	…	…	…	1.250	.995	2000	1.562	1.000	3600	…	…	…	.625
.688	.770	.920	1.470	.660	.880	.800	.060	.375	1250	1.030	.030	…	…	…	1.250	1.058	2000	1.562	1.065	4300	…	…	…	.688
.750	.770	.920	1.510	.670	.880	.800	.060	.375	1500	1.120	.030	…	…	…	1.250	1.120	2000	1.562	1.130	5000	…	…	…	.750
.781	.830	.950	1.550	.690	.890	.840	.060	.375	1615	1.150	.030	…	…	…	1.250	1.126	2000	1.625	1.130	5000	…	…	…	.781
.812	.910	1.120	1.660	.720	.970	.860	.060	.406	1710	1.200	.030	…	…	…	1.250	1.213	2000	1.625	1.222	5000	…	…	…	.812
.875	.970	1.150	1.810	.800	1.060	.910	.060	.438	2250	1.280	.030	…	…	…	…	…	…	1.750	1.285	5000	…	…	…	.875
.938	.970	1.150	1.850	.810	1.060	.950	.060	.438	2750	1.370	.030	…	…	…	…	…	…	1.750	1.410	5000	…	…	…	.938
1.000	1.050	1.230	2.000	.880	1.160	1.060	.060	.500	3250	1.470	.030	…	…	…	…	…	…	1.750	1.410	5000	…	…	…	1.000
1.062	1.090	1.250	2.100	.970	1.200	1.200	.080	.500	3500	1.550	.030	…	…	…	…	…	…	1.844	1.505	5000	…	…	…	1.062
1.125	1.140	1.370	2.210	1.000	1.270	1.230	.080	.500	4000	1.610	.030	…	…	…	…	…	…	1.938	1.567	5000	…	…	…	1.125
1.250	1.270	1.420	2.440	1.080	1.390	1.310	.080	.562	5250	1.890	.030	…	…	…	…	…	…	2.000	1.723	5000	2.375	1.855	7250	1.250
1.312	1.390	1.690	2.630	1.170	1.520	1.340	.080	.562	6000	1.980	.030	…	…	…	…	…	…	…	…	…	2.500	1.920	8000	1.312
1.438	1.470	1.720	2.800	1.250	1.590	1.340	.090	.641	7500	2.140	.030	…	…	…	…	…	…	…	…	…	2.625	2.075	9550	1.438
1.500	1.470	1.720	2.840	1.270	1.590	1.450	.090	.641	8250	2.200	.030	…	…	…	…	…	…	…	…	…	2.625	2.170	10450	1.500
1.625	1.560	1.880	3.100	1.380	1.750	1.560	.090	.641	9000	2.390	.030	…	…	…	…	…	…	…	…	…	2.750	2.325	11750	1.625

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. American National Standard Type A Plain Washers—Preferred Sizes *ANSI/ASME B18.22.1-1965 (R1998)*

Nominal Washer Size[a]		Series	Inside Diameter			Outside Diameter			Thickness		
				Tolerance			Tolerance				
			Basic	Plus	Minus	Basic	Plus	Minus	Basic	Max.	Min.
—	—		0.078	0.000	0.005	0.188	0.000	0.005	0.020	0.025	0.016
—	—		0.094	0.000	0.005	0.250	0.000	0.005	0.020	0.025	0.016
—	—		0.125	0.008	0.005	0.312	0.008	0.005	0.032	0.040	0.025
No. 6	0.138		0.156	0.008	0.005	0.375	0.015	0.005	0.049	0.065	0.036
No. 8	0.164		0.188	0.008	0.005	0.438	0.015	0.005	0.049	0.065	0.036
No. 10	0.190		0.219	0.008	0.005	0.500	0.015	0.005	0.049	0.065	0.036
3/16	0.188		0.250	0.015	0.005	0.562	0.015	0.005	0.049	0.065	0.036
No. 12	0.216		0.250	0.015	0.005	0.562	0.015	0.005	0.065	0.080	0.051
1/4	0.250	N	0.281	0.015	0.005	0.625	0.015	0.005	0.065	0.080	0.051
1/4	0.250	W	0.312	0.015	0.005	0.734[b]	0.015	0.007	0.065	0.080	0.051
5/16	0.312	N	0.344	0.015	0.005	0.688	0.015	0.007	0.065	0.080	0.051
5/16	0.312	W	0.375	0.015	0.005	0.875	0.030	0.007	0.083	0.104	0.064
3/8	0.375	N	0.406	0.015	0.005	0.812	0.015	0.007	0.065	0.080	0.051
3/8	0.375	W	0.438	0.015	0.005	1.000	0.030	0.007	0.083	0.104	0.064
7/16	0.438	N	0.469	0.015	0.005	0.922	0.015	0.007	0.065	0.080	0.051
7/16	0.438	W	0.500	0.015	0.005	1.250	0.030	0.007	0.083	0.104	0.064
1/2	0.500	N	0.531	0.015	0.005	1.062	0.030	0.007	0.095	0.121	0.074
1/2	0.500	W	0.562	0.015	0.005	1.375	0.030	0.007	0.109	0.132	0.086
9/16	0.562	N	0.594	0.015	0.005	1.156[b]	0.030	0.007	0.095	0.121	0.074
9/16	0.562	W	0.625	0.015	0.005	1.469[b]	0.030	0.007	0.109	0.132	0.086
5/8	0.625	N	0.656	0.030	0.007	1.312	0.030	0.007	0.095	0.121	0.074
5/8	0.625	W	0.688	0.030	0.007	1.750	0.030	0.007	0.134	0.160	0.108
3/4	0.750	N	0.812	0.030	0.007	1.469	0.030	0.007	0.134	0.160	0.108
3/4	0.750	W	0.812	0.030	0.007	2.000	0.030	0.007	0.148	0.177	0.122
7/8	0.875	N	0.938	0.030	0.007	1.750	0.030	0.007	0.134	0.160	0.108
7/8	0.875	W	0.938	0.030	0.007	2.250	0.030	0.007	0.165	0.192	0.136
1	1.000	N	1.062	0.030	0.007	2.000	0.030	0.007	0.134	0.160	0.108
1	1.000	W	1.062	0.030	0.007	2.500	0.030	0.007	0.165	0.192	0.136
1 1/8	1.125	N	1.250	0.030	0.007	2.250	0.030	0.007	0.134	0.160	0.108
1 1/8	1.125	W	1.250	0.030	0.007	2.750	0.030	0.007	0.165	0.192	0.136
1 1/4	1.250	N	1.375	0.030	0.007	2.500	0.030	0.007	0.165	0.192	0.136
1 1/4	1.250	W	1.375	0.030	0.007	3.000	0.030	0.007	0.165	0.192	0.136
1 3/8	1.375	N	1.500	0.030	0.007	2.750	0.030	0.007	0.165	0.192	0.136
1 3/8	1.375	W	1.500	0.045	0.010	3.250	0.045	0.010	0.180	0.213	0.153
1 1/2	1.500	N	1.625	0.030	0.007	3.000	0.030	0.007	0.165	0.192	0.136
1 1/2	1.500	W	1.625	0.045	0.010	3.500	0.045	0.010	0.180	0.213	0.153
1 5/8	1.625		1.750	0.045	0.010	3.750	0.045	0.010	0.180	0.213	0.153
1 3/4	1.750		1.875	0.045	0.010	4.000	0.045	0.010	0.180	0.213	0.153
1 7/8	1.875		2.000	0.045	0.010	4.250	0.045	0.010	0.180	0.213	0.153
2	2.000		2.125	0.045	0.010	4.500	0.045	0.010	0.180	0.213	0.153
2 1/4	2.250		2.375	0.045	0.010	4.750	0.045	0.010	0.220	0.248	0.193
2 1/2	2.500		2.625	0.045	0.010	5.000	0.045	0.010	0.238	0.280	0.210
2 3/4	2.750		2.875	0.065	0.010	5.250	0.065	0.010	0.259	0.310	0.228
3	3.000		3.125	0.065	0.010	5.500	0.065	0.010	0.284	0.327	0.249

[a] Nominal washer sizes are intended for use with comparable nominal screw or bolt sizes.

[b] The 0.734-inch, 1.156-inch, and 1.469-inch outside diameters avoid washers which could be used in coin operated devices.

All dimensions are in inches.

Preferred sizes are for the most part from series previously designated "Standard Plate" and "SAE." Where common sizes existed in the two series, the SAE size is designated "N" (narrow) and the Standard Plate "W" (wide). These sizes as well as all other sizes of Type A Plain Washers are to be ordered by ID, OD, and thickness dimensions.

Additional selected sizes of Type A Plain Washers are shown in Table 1b.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. American National Standard Type A Plain Washers — Additional Selected Sizes *ANSI/ASME B18.22.1-1965 (R1998)*

Inside Diameter			Outside Diameter			Thickness		
	Tolerance			Tolerance				
Basic	Plus	Minus	Basic	Plus	Minus	Basic	Max.	Min.
0.094	0.000	0.005	0.219	0.000	0.005	0.020	0.025	0.016
0.125	0.000	0.005	0.250	0.000	0.005	0.022	0.028	0.017
0.156	0.008	0.005	0.312	0.008	0.005	0.035	0.048	0.027
0.172	0.008	0.005	0.406	0.015	0.005	0.049	0.065	0.036
0.188	0.008	0.005	0.375	0.015	0.005	0.049	0.065	0.036
0.203	0.008	0.005	0.469	0.015	0.005	0.049	0.065	0.036
0.219	0.008	0.005	0.438	0.015	0.005	0.049	0.065	0.036
0.234	0.008	0.005	0.531	0.015	0.005	0.049	0.065	0.036
0.250	0.015	0.005	0.500	0.015	0.005	0.049	0.065	0.036
0.266	0.015	0.005	0.625	0.015	0.005	0.049	0.065	0.036
0.312	0.015	0.005	0.875	0.015	0.007	0.065	0.080	0.051
0.375	0.015	0.005	0.734[a]	0.015	0.007	0.065	0.080	0.051
0.375	0.015	0.005	1.125	0.015	0.007	0.065	0.080	0.051
0.438	0.015	0.005	0.875	0.030	0.007	0.083	0.104	0.064
0.438	0.015	0.005	1.375	0.030	0.007	0.083	0.104	0.064
0.500	0.015	0.005	1.125	0.030	0.007	0.083	0.104	0.064
0.500	0.015	0.005	1.625	0.030	0.007	0.083	0.104	0.064
0.562	0.015	0.005	1.250	0.030	0.007	0.109	0.132	0.086
0.562	0.015	0.005	1.875	0.030	0.007	0.109	0.132	0.086
0.625	0.015	0.005	1.375	0.030	0.007	0.109	0.132	0.086
0.625	0.015	0.005	2.125	0.030	0.007	0.134	0.160	0.108
0.688	0.030	0.007	1.469[a]	0.030	0.007	0.134	0.160	0.108
0.688	0.030	0.007	2.375	0.030	0.007	0.165	0.192	0.136
0.812	0.030	0.007	1.750	0.030	0.007	0.148	0.177	0.122
0.812	0.030	0.007	2.875	0.030	0.007	0.165	0.192	0.136
0.938	0.030	0.007	2.000	0.030	0.007	0.165	0.192	0.136
0.938	0.030	0.007	3.375	0.045	0.010	0.180	0.213	0.153
1.062	0.030	0.007	2.250	0.030	0.007	0.165	0.192	0.136
1.062	0.045	0.010	3.875	0.045	0.010	0.238	0.280	0.210
1.250	0.030	0.007	2.500	0.030	0.007	0.165	0.192	0.136
1.375	0.030	0.007	2.750	0.030	0.007	0.165	0.192	0.136
1.500	0.045	0.010	3.000	0.045	0.010	0.180	0.213	0.153
1.625	0.045	0.010	3.250	0.045	0.010	0.180	0.213	0.153
1.688	0.045	0.010	3.500	0.045	0.010	0.180	0.213	0.153
1.812	0.045	0.010	3.750	0.045	0.010	0.180	0.213	0.153
1.938	0.045	0.010	4.000	0.045	0.010	0.180	0.213	0.153
2.062	0.045	0.010	4.250	0.045	0.010	0.180	0.213	0.153

[a] The 0.734-inch and 1.469-inch outside diameters avoid washers which could be used in coin operated devices.

All dimensions are in inches.

The above sizes are to be ordered by ID, OD, and thickness dimensions.

Preferred Sizes of Type A Plain Washers are shown in Table 1a.

ANSI Standard Plain Washers.— The Type A plain washers were originally developed in a light, medium, heavy and extra heavy series. These series have been discontinued and the washers are now designated by their nominal dimensions.

The Type B plain washers are available in a narrow, regular and wide series with proportions designed to distribute the load over larger areas of lower strength materials.

Plain washers are made of ferrous or non-ferrous metal, plastic or other material as specified. The tolerances indicated in the tables are intended for metal washers only.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Type B Plain Washers —

Nominal Washer Size[a]		Series[b]	Inside Diameter			Outside Diameter			Thickness		
			Basic	Tolerance		Basic	Tolerance		Basic	Max.	Min.
				Plus	Minus		Plus	Minus			
No. 0	0.060	N	0.068	0.000	0.005	0.125	0.000	0.005	0.025	0.028	0.022
		R	0.068	0.000	0.005	0.188	0.000	0.005	0.025	0.028	0.022
		W	0.068	0.000	0.005	0.250	0.000	0.005	0.025	0.028	0.022
No. 1	0.073	N	0.084	0.000	0.005	0.156	0.000	0.005	0.025	0.028	0.022
		R	0.084	0.000	0.005	0.219	0.000	0.005	0.025	0.028	0.022
		W	0.084	0.000	0.005	0.281	0.000	0.005	0.032	0.036	0.028
No. 2	0.086	N	0.094	0.000	0.005	0.188	0.000	0.005	0.025	0.028	0.022
		R	0.094	0.000	0.005	0.250	0.000	0.005	0.032	0.036	0.028
		W	0.094	0.000	0.005	0.344	0.000	0.005	0.032	0.036	0.028
No. 3	0.099	N	0.109	0.000	0.005	0.219	0.000	0.005	0.025	0.028	0.022
		R	0.109	0.000	0.005	0.312	0.000	0.005	0.032	0.036	0.028
		W	0.109	0.008	0.005	0.406	0.008	0.005	0.040	0.045	0.036
No. 4	0.112	N	0.125	0.000	0.005	0.250	0.000	0.005	0.032	0.036	0.028
		R	0.125	0.008	0.005	0.375	0.008	0.005	0.040	0.045	0.036
		W	0.125	0.008	0.005	0.438	0.008	0.005	0.040	0.045	0.036
No. 5	0.125	N	0.141	0.000	0.005	0.281	0.000	0.005	0.032	0.036	0.028
		R	0.141	0.008	0.005	0.406	0.008	0.005	0.040	0.045	0.036
		W	0.141	0.008	0.005	0.500	0.008	0.005	0.040	0.045	0.036
No. 6	0.138	N	0.156	0.000	0.005	0.312	0.000	0.005	0.032	0.036	0.028
		R	0.156	0.008	0.005	0.438	0.008	0.005	0.040	0.045	0.036
		W	0.156	0.008	0.005	0.562	0.008	0.005	0.040	0.045	0.036
No. 8	0.164	N	0.188	0.008	0.005	0.375	0.008	0.005	0.040	0.045	0.036
		R	0.188	0.008	0.005	0.500	0.008	0.005	0.040	0.045	0.036
		W	0.188	0.008	0.005	0.625	0.015	0.005	0.063	0.071	0.056
No. 10	0.190	N	0.203	0.008	0.005	0.406	0.008	0.005	0.040	0.045	0.036
		R	0.203	0.008	0.005	0.562	0.008	0.005	0.040	0.045	0.036
		W	0.203	0.008	0.005	0.734[c]	0.015	0.007	0.063	0.071	0.056
No. 12	0.216	N	0.234	0.008	0.005	0.438	0.008	0.005	0.040	0.045	0.036
		R	0.234	0.008	0.005	0.625	0.015	0.005	0.063	0.071	0.056
		W	0.234	0.008	0.005	0.875	0.015	0.007	0.063	0.071	0.056
1/4	0.250	N	0.281	0.015	0.005	0.500	0.015	0.005	0.063	0.071	0.056
		R	0.281	0.015	0.005	0.734[c]	0.015	0.007	0.063	0.071	0.056
		W	0.281	0.015	0.005	1.000	0.015	0.007	0.063	0.071	0.056
5/16	0.312	N	0.344	0.015	0.005	0.625	0.015	0.005	0.063	0.071	0.056
		R	0.344	0.015	0.005	0.875	0.015	0.007	0.063	0.071	0.056
		W	0.344	0.015	0.005	1.125	0.015	0.007	0.063	0.071	0.056
3/8	0.375	N	0.406	0.015	0.005	0.734[c]	0.015	0.007	0.063	0.071	0.056
		R	0.406	0.015	0.005	1.000	0.015	0.007	0.063	0.071	0.056
		W	0.406	0.015	0.005	1.250	0.030	0.007	0.100	0.112	0.090
7/16	0.438	N	0.469	0.015	0.005	0.875	0.015	0.007	0.063	0.071	0.056
		R	0.469	0.015	0.005	1.125	0.015	0.007	0.063	0.071	0.056
		W	0.469	0.015	0.005	1.469[c]	0.030	0.007	0.100	0.112	0.090
1/2	0.500	N	0.531	0.015	0.005	1.000	0.015	0.007	0.063	0.071	0.056
		R	0.531	0.015	0.005	1.250	0.030	0.007	0.100	0.112	0.090
		W	0.531	0.015	0.005	1.750	0.030	0.007	0.100	0.112	0.090
9/16	0.562	N	0.594	0.015	0.005	1.125	0.015	0.007	0.063	0.071	0.056
		R	0.594	0.015	0.005	1.469[c]	0.030	0.007	0.100	0.112	0.090
		W	0.594	0.015	0.005	2.000	0.030	0.007	0.100	0.112	0.090
5/8	0.625	N	0.656	0.030	0.007	1.250	0.030	0.007	0.100	0.112	0.090
		R	0.656	0.030	0.007	1.750	0.030	0.007	0.100	0.112	0.090
		W	0.656	0.030	0.007	2.250	0.030	0.007	0.160	0.174	0.146

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **American National Standard Type B Plain Washers —**

Nominal Washer Size[a]		Series[b]	Inside Diameter			Outside Diameter			Thickness		
			Basic	Tolerance		Basic	Tolerance		Basic	Max.	Min.
				Plus	Minus		Plus	Minus			
		N	0.812	0.030	0.007	1.375	0.030	0.007	0.100	0.112	0.090
3/4	0.750	R	0.812	0.030	0.007	2.000	0.030	0.007	0.100	0.112	0.090
		W	0.812	0.030	0.007	2.500	0.030	0.007	0.160	0.174	0.146
		N	0.938	0.030	0.007	1.469[c]	0.030	0.007	0.100	0.112	0.090
7/8	0.875	R	0.938	0.030	0.007	2.250	0.030	0.007	0.160	0.174	0.146
		W	0.938	0.030	0.007	2.750	0.030	0.007	0.160	0.174	0.146
		N	1.062	0.030	0.007	1.750	0.030	0.007	0.100	0.112	0.090
1	1.000	R	1.062	0.030	0.007	2.500	0.030	0.007	0.160	0.174	0.146
		W	1.062	0.030	0.007	3.000	0.030	0.007	0.160	0.174	0.146
		N	1.188	0.030	0.007	2.000	0.030	0.007	0.100	0.112	0.090
1 1/8	1.125	R	1.188	0.030	0.007	2.750	0.030	0.007	0.160	0.174	0.146
		W	1.188	0.030	0.007	3.250	0.030	0.007	0.160	0.174	0.146
		N	1.312	0.030	0.007	2.250	0.030	0.007	0.160	0.174	0.146
1 1/4	1.250	R	1.312	0.030	0.007	3.000	0.030	0.007	0.160	0.174	0.146
		W	1.312	0.045	0.010	3.500	0.045	0.010	0.250	0.266	0.234
		N	1.438	0.030	0.007	2.500	0.030	0.007	0.160	0.174	0.146
1 3/8	1.375	R	1.438	0.030	0.007	3.250	0.030	0.007	0.160	0.174	0.146
		W	1.438	0.045	0.010	3.750	0.045	0.010	0.250	0.266	0.234
		N	1.562	0.030	0.007	2.750	0.030	0.007	0.160	0.174	0.146
1 1/2	1.500	R	1.562	0.045	0.010	3.500	0.045	0.010	0.250	0.266	0.234
		W	1.562	0.045	0.010	4.000	0.045	0.010	0.250	0.266	0.234
		N	1.750	0.030	0.007	3.000	0.030	0.007	0.160	0.174	0.146
1 5/8	1.625	R	1.750	0.045	0.010	3.750	0.045	0.010	0.250	0.266	0.234
		W	1.750	0.045	0.010	4.250	0.045	0.010	0.250	0.266	0.234
		N	1.875	0.030	0.007	3.250	0.030	0.007	0.160	0.174	0.146
1 3/4	1.750	R	1.875	0.045	0.010	4.000	0.045	0.010	0.250	0.266	0.234
		W	1.875	0.045	0.010	4.500	0.045	0.010	0.250	0.266	0.234
		N	2.000	0.045	0.010	3.500	0.045	0.010	0.250	0.266	0.234
1 7/8	1.875	R	2.000	0.045	0.010	4.250	0.045	0.010	0.250	0.266	0.234
		W	2.000	0.045	0.010	4.750	0.045	0.010	0.250	0.266	0.234
		N	2.125	0.045	0.010	3.750	0.045	0.010	0.250	0.266	0.234
2	2.000	R	2.125	0.045	0.010	4.500	0.045	0.010	0.250	0.266	0.234
		W	2.125	0.045	0.010	5.000	0.045	0.010	0.250	0.266	0.234

[a] Nominal washer sizes are intended for use with comparable nominal screw or bolt sizes.

[b] N indicates Narrow; R, Regular; and W, Wide Series.

[c] The 0.734-inch and 1.469-inch outside diameter avoids washers which could be used in coin operated devices.

All dimensions are in inches.

Inside and outside diameters shall be concentric within at least the inside diameter tolerance.

Washers shall be flat within 0.005-inch for basic outside diameters up through 0.875-inch and within 0.010 inch for larger outside diameters.

For 2 1/4, 2 1/2, 2 3/4, and 3-inch sizes see ANSI/ASME B18.22.1-1965 (R1998).

American National Standard Helical Spring and Tooth Lock Washers ANSI/ASME B18.21.1-1994.— This standard covers helical spring lock washers of carbon steel; boron steel; corrosion resistant steel, Types 302 and 305; aluminum-zinc alloy; phosphor-bronze; silicon-bronze; and K-Monel; in various series. Tooth lock washers of carbon steel having internal teeth, external teeth, and both internal and external teeth, of two constructions, designated as Type A and Type B. Washers intended for general industrial application are also covered. American National Standard Lock Washers (Metric Series) ANSI/ASME B18.21.2M-1994 covers metric sizes for helical spring and tooth lock washers.

Copyright 2004, Industrial Press, Inc., New York, NY

Helical spring lock washers: These washers are used to provide: 1) good bolt tension per unit of applied torque for tight assemblies; 2) hardened bearing surfaces to create uniform torque control; 3) uniform load distribution through controlled radii—section—cutoff; and 4) protection against looseness resulting from vibration and corrosion.

Nominal washer sizes are intended for use with comparable nominal screw or bolt sizes. These washers are designated by the following data in the sequence shown: Product name; nominal size (number, fraction or decimal equivalent); series; material;and protective finish, if required. For example: Helical Spring Lock Washer, 0.375 Extra Duty, Steel, Phosphate Coated.

Helical spring lock washers are available in four series: Regular, heavy, extra duty and hi-collar as given in Tables 2 and 1. Helical spring lock washers made of materials other than carbon steel are available in the regular series as given in Table 2.

Table 1. American National Standard Hi-Collar Helical Spring Lock Washers
ANSI/ASME B18.21.1-1994

Nominal Washer Size		Inside Diameter		Outside Diameter	Washer Section	
					Width	Thickness[a]
		Min.	Max.	Max.	Min.	Min.
No. 4	0.112	0.114	0.120	0.173	0.022	0.022
No. 5	0.125	0.127	0.133	0.202	0.030	0.030
No. 6	0.138	0.141	0.148	0.216	0.030	0.030
No. 8	0.164	0.167	0.174	0.267	0.042	0.047
No. 10	0.190	0.193	0.200	0.294	0.042	0.047
1/4	0.250	0.252	0.260	0.363	0.047	0.078
5/16	0.3125	0.314	0.322	0.457	0.062	0.093
3/8	0.375	0.377	0.385	0.550	0.076	0.125
7/16	0.4375	0.440	0.450	0.644	0.090	0.140
1/2	0.500	0.502	0.512	0.733	0.103	0.172
5/8	0.625	0.628	0.640	0.917	0.125	0.203
3/4	0.750	0.753	0.765	1.105	0.154	0.218
7/8	0.875	0.878	0.890	1.291	0.182	0.234
1	1.000	1.003	1.015	1.478	0.208	0.250
1 1/8	1.125	1.129	1.144	1.663	0.236	0.313
1 1/4	1.250	1.254	1.272	1.790	0.236	0.313
1 3/8	1.375	1.379	1.399	2.031	0.292	0.375
1 1/2	1.500	1.504	1.524	2.159	0.292	0.375
1 3/4	1.750	1.758	1.778	2.596	0.383	0.469
2	2.000	2.008	2.028	2.846	0.383	0.469
2 1/4	2.250	2.262	2.287	3.345	0.508	0.508
2 1/2	2.500	2.512	2.537	3.559	0.508	0.508
2 3/4	2.750	2.762	2.787	4.095	0.633	0.633
3	3.000	3.012	3.037	4.345	0.633	0.633

[a] Mean section thickness = (inside thickness + outside thickness) ÷ 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Helical Spring Lock Washers *ANSI/ASME B18.21.1-1994*



Nominal Washer Size		Inside Diameter, *A*		Regular			Heavy			Extra Duty		
		Max.	Min.	O.D., *B* Max.	Section Width, *W*	Section Thickness, *T*[a]	O.D., *B* Max.	Section Width, *W*	Section Thickness, *T*[a]	O.D., *B* Max.	Section Width, *W*	Section Thickness, *T*[a]
No. 2	0.086	0.094	0.088	0.172	0.035	0.020	0.182	0.040	0.025	0.208	0.053	0.027
No. 3	0.099	0.107	0.101	0.195	0.040	0.025	0.209	0.047	0.031	0.239	0.062	0.034
No. 4	0.112	0.120	0.114	0.209	0.040	0.025	0.223	0.047	0.031	0.253	0.062	0.034
No. 5	0.125	0.133	0.127	0.236	0.047	0.031	0.252	0.055	0.040	0.300	0.079	0.045
No. 6	0.138	0.148	0.141	0.250	0.047	0.031	0.266	0.055	0.040	0.314	0.079	0.045
No. 8	0.164	0.174	0.167	0.293	0.055	0.040	0.307	0.062	0.047	0.375	0.096	0.057
No. 10	0.190	0.200	0.193	0.334	0.062	0.047	0.350	0.070	0.056	0.434	0.112	0.068
No. 12	0.216	0.227	0.220	0.377	0.070	0.056	0.391	0.077	0.063	0.497	0.130	0.080
1/4	0.250	0.260	0.252	0.487	0.109	0.062	0.489	0.110	0.077	0.533	0.132	0.084
5/16	0.3125	0.322	0.314	0.583	0.125	0.078	0.293	0.130	0.097	0.619	0.143	0.108
3/8	0.375	0.385	0.377	0.680	0.141	0.094	0.688	0.145	0.115	0.738	0.170	0.123
7/16	0.4375	0.450	0.440	0.776	0.156	0.109	0.784	0.160	0.133	0.836	0.186	0.143
1/2	0.500	0.512	0.502	0.869	0.171	0.125	0.879	0.176	0.151	0.935	0.204	0.162
9/16	0.5625	0.574	0.564	0.965	0.188	0.141	0.975	0.193	0.170	1.035	0.223	0.182
5/8	0.625	0.641	0.628	1.073	0.203	0.156	1.087	0.210	0.189	1.151	0.242	0.202
11/16	0.6875	0.704	0.691	1.170	0.219	0.172	1.186	0.227	0.207	1.252	0.260	0.221
3/4	0.750	0.766	0.753	1.265	0.234	0.188	1.285	0.244	0.226	1.355	0.279	0.241
13/16	0.8125	0.832	0.816	1.363	0.250	0.203	1.387	0.262	0.246	1.458	0.298	0.261
7/8	0.875	0.894	0.878	1.459	0.266	0.219	1.489	0.281	0.266	1.571	0.322	0.285
15/16	0.9375	0.958	0.941	1.556	0.281	0.234	1.590	0.298	0.284	1.684	0.345	0.308
1	1.000	1.024	1.003	1.656	0.297	0.250	1.700	0.319	0.306	1.794	0.366	0.330
1 1/16	1.0625	1.087	1.066	1.751	0.312	0.266	1.803	0.338	0.326	1.905	0.389	0.352
1 1/8	1.125	1.153	1.129	1.847	0.328	0.281	1.903	0.356	0.345	2.013	0.411	0.375
1 3/16	1.1875	1.217	1.192	1.943	0.344	0.297	2.001	0.373	0.364	2.107	0.431	0.396
1 1/4	1.250	1.280	1.254	2.036	0.359	0.312	2.104	0.393	0.384	2.222	0.452	0.417
1 5/16	1.3125	1.344	1.317	2.133	0.375	0.328	2.203	0.410	0.403	2.327	0.472	0.438
1 3/8	1.375	1.408	1.379	2.219	0.391	0.344	2.301	0.427	0.422	2.429	0.491	0.458
1 7/16	1.4375	1.472	1.442	2.324	0.406	0.359	2.396	0.442	0.440	2.530	0.509	0.478
1 1/2	1.500	1.534	1.504	2.419	0.422	0.375	2.491	0.458	0.458	2.627	0.526	0.496

[a] T = mean section thickness $= (t_i + t_o) \div 2$.

Copyright 2004, Industrial Press, Inc., New York, NY

All dimensions are given in inches.*See ANSI/ASME B18.21.1-1994 standard for sizes over 1½ to 3, inclusive, for regular and heavy helical spring lock washers and over 1½ to 2, inclusive, for extra-duty helical spring lock washers.

When carbon steel helical spring lock washers are to be hot-dipped galvanized for use with hot-dipped galvanized bolts or screws, they are to be coiled to limits onto inch in excess of those specified in Tables 2 and 1 for minimum inside diameter and maximum outside diameter. Galvanizing washers under ¼ inch nominal size are not recommended.

Tooth lock washers: These washers serve to lock fasteners, such as bolts and nuts, to the component parts of an assembly, or increase the friction between the fasteners and the assembly. They are designated in a manner similar to helical spring lock washers, and are available in carbon steel. Dimensions are given in Tables 3 and 4.

Table 3. American National Standard Internal-External Tooth Lock Washers
ANSI/ASME B18.21.1-1994

All dimensions are given in inches except whole numbers under "Size"



Size	A Inside Diameter Max.	A Inside Diameter Min.	B Outside Diameter Max.	B Outside Diameter Min.	C Thickness Max.	C Thickness Min.
			.475	.460	.021	.016
No. 4	.123	.115	.510	.495	.021	.017
			.610	.580	.021	.017
			.510	.495	.028	.023
No. 6	.150	.141	.610	.580	.028	.023
			.690	.670	.028	.023
			.610	.580	.034	.028
No. 8	.176	.168	.690	.670	.034	.028
			.760	.740	.034	.028
			.610	.580	.034	.028
No. 10	.204	.195	.690	.670	.040	.032
			.760	.740	.040	.032
			.900	.880	.040	.032
			.690	.670	.040	.032
No. 12	.231	.221	.760	.725	.040	.032
			.900	.880	.040	.032
			.985	.965	.045	.037
			.760	.725	.040	.032
¼	.267	.256	.900	.880	.045	.037
			.985	.965	.045	.037
			1.070	1.045	.045	.037
			.900	.865	.040	.032
5/16	.332	.320	.985	.965	.045	.037
			1.070	1.045	.050	.042
			1.155	1.130	.050	.042
			.985	.965	.045	.037
3/8	.398	.384	1.070	1.045	.050	.042
			1.070	1.130	.050	.042
			1.260	1.220	.050	.042
			1.070	1.045	.050	.042
7/16	.464	.448	1.155	1.130	.050	.042
			1.260	1.220	.055	.047
			1.315	1.290	.055	.047
			1.260	1.220	.055	.047
½	.530	.512	1.315	1.290	.055	.047
			1.410	1.380	.060	.052
			1.620	1.590	.067	.059
			1.315	1.290	.055	.047
9/16	.596	.576	1.430	1.380	.060	.052
			1.620	1.590	.067	.059
			1.830	1.797	.067	.059
			1.410	1.380	.060	.052
5/8	.663	.640	1.620	1.590	.067	.059
			1.830	1.797	.067	.059
			1.975	1.935	.067	.059

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Internal and External Tooth Lock Washers *ANSI/ASME B18.21.1-1994*



Internal Tooth



External Tooth



Countersunk External Tooth

Internal Tooth Lock Washers

	Size	#2	#3	#4	#5	#6	#8	#10	#12	1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	1	1 1/8	1 1/4
A	Max	0.095	0.109	0.123	0.136	0.150	0.176	0.204	0.231	0.267	0.332	0.398	0.464	0.530	0.596	0.663	0.728	0.795	0.861	0.927	1.060	1.192	1.325
	Min	0.089	0.102	0.115	0.129	0.141	0.168	0.195	0.221	0.256	0.320	0.384	0.448	0.512	0.576	0.640	0.704	0.769	0.832	0.894	1.019	1.144	1.275
B	Max	0.200	0.232	0.270	0.280	0.295	0.340	0.381	0.410	0.478	0.610	0.692	0.789	0.900	0.985	1.071	1.166	1.245	1.315	1.410	1.637	1.830	1.975
	Min	0.175	0.215	0.245	0.255	0.275	0.325	0.365	0.394	0.460	0.594	0.670	0.740	0.867	0.957	1.045	1.130	1.220	1.290	1.364	1.590	1.799	1.921
C	Max	0.015	0.019	0.019	0.021	0.021	0.023	0.025	0.025	0.028	0.034	0.040	0.040	0.045	0.045	0.050	0.050	0.055	0.055	0.060	0.067	0.067	0.067
	Min	0.010	0.012	0.015	0.017	0.017	0.018	0.020	0.020	0.023	0.028	0.032	0.032	0.037	0.037	0.042	0.042	0.047	0.047	0.052	0.059	0.059	0.059

External Tooth Lock Washers

A	Max	…	0.109	0.123	0.136	0.150	0.176	0.204	0.231	0.267	0.332	0.398	0.464	0.530	0.596	0.663	0.728	0.795	0.861	0.927	1.060	…	…
	Min	…	0.102	0.115	0.129	0.141	0.168	0.195	0.221	0.256	0.320	0.384	0.448	0.513	0.576	0.641	0.704	0.768	0.833	0.897	1.025	…	…
B	Max	…	0.235	0.260	0.285	0.320	0.381	0.410	0.475	0.510	0.610	0.694	0.760	0.900	0.985	1.070	1.155	1.260	1.315	1.410	1.620	…	…
	Min	…	0.220	0.245	0.270	0.305	0.365	0.395	0.460	0.494	0.588	0.670	0.740	0.880	0.960	1.045	1.130	1.220	1.290	1.380	1.590	…	…
C	Max	…	0.015	0.019	0.019	0.022	0.023	0.025	0.028	0.028	0.034	0.040	0.040	0.045	0.045	0.050	0.050	0.055	0.055	0.060	0.067	…	…
	Min	…	0.012	0.014	0.015	0.016	0.018	0.020	0.023	0.023	0.028	0.032	0.032	0.037	0.037	0.042	0.042	0.047	0.047	0.052	0.059	…	…

Heavy Internal Tooth Lock Washers

	Size	1/4	5/16	3/8	7/16	1/2	9/16	5/8	3/4	7/8
A	Max	0.267	0.332	0.398	0.464	0.530	0.596	0.663	0.795	0.927
	Min	0.256	0.320	0.384	0.448	0.512	0.576	0.640	0.768	0.894
B	Max	0.536	0.607	0.748	0.858	0.924	1.034	1.135	1.265	1.447
	Min	0.500	0.590	0.700	0.800	0.880	0.990	1.100	1.240	1.400
C	Max	0.045	0.050	0.050	0.067	0.067	0.067	0.067	0.084	0.084
	Min	0.035	0.040	0.042	0.050	0.055	0.055	0.059	0.070	0.075

Countersunk External Tooth Lock Washers[a]

	Size	#4	#6	#8	#10	#12	1/4	#16	5/16	3/8	7/16	1/2
A	Max	0.123	0.150	0.177	0.205	0.231	0.267	0.287	0.333	0.398	0.463	0.529
	Min	0.113	0.140	0.167	0.195	0.220	0.255	0.273	0.318	0.383	0.448	0.512
C	Max	0.019	0.021	0.021	0.025	0.025	0.025	0.028	0.028	0.034	0.045	0.045
	Min	0.015	0.017	0.017	0.020	0.020	0.020	0.023	0.023	0.028	0.037	0.037
D	Max	0.065	0.092	0.105	0.099	0.128	0.128	0.147	0.192	0.255	0.270	0.304
	Min	0.050	0.082	0.088	0.083	0.118	0.113	0.137	0.165	0.242	0.260	0.294

[a] Starting with #4, approx. O.D.'s are: 0.213, 0.289, 0.322, 0.354, 0.421 0.454, 0.505, 0.599, 0.765, 0.867, and 0.976.

All dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

METRIC THREADED FASTENERS

A number of American National Standards covering metric bolts, screws, nuts, and washers have been established in cooperation with the Department of Defense in such a way that they could be used by the Government for procurement purposes. Extensive information concerning these metric fasteners is given in the following text and tables, but for additional manufacturing and acceptance specifications reference should be made to the respective Standards which may be obtained by nongovernmental agencies from the American National Standards Institute, 25 West 43rd Street, New York, N.Y. 10036. These Standards are:

ANSI B18.2.3.1M-1979 (R1989) Metric Hex Cap Screws	Table 1
ANSI B18.2.3.2M-1979 (R1989) Metric Formed Hex Screws	Table 2
ANSI B18.2.3.3M-1979 (R1989) Metric Heavy Hex Screws	Table 3
ANSI B18.2.3.8M-1981 (R1991) Metric Hex Lag Screws	Table 5
ANSI B18.2.3.9M-1984 Metric Heavy Hex Flange Screws	Table 6
ANSI B18.2.3.4M-1984 Metric Hex Flange Screws	Table 7
ANSI B18.5.2.2M-1982 Metric Round Head Square Neck Bolts	Table 9
ANSI B18.2.3.6M-1979 (R1989) Metric Heavy Hex Bolts	Table 10
ANSI B18.2.3.7M-1979 (R1989) Metric Heavy Hex Structural Bolts	Table 11
ANSI B18.2.3.5M-1979 (R1989) Metric Hex Bolts	Table 12
ANSI B18.3.1M-1986 Socket Head Cap Screws (Metric Series)	Table 24
ANSI B18.2.4.1M-1979 (R1989) Metric Hex Nuts, Style 1	Table 26
ANSI B18.2.4.2M-1979 (R1989) Metric Hex Nuts, Style 2	Table 26
ANSI B18.2.4.3M-1979 (R1989) Metric Slotted Hex Nuts	Table 27
ANSI B18.2.4.4M-1982 Metric Hex Flange Nuts	Table 28
ANSI B18.16.3M-1998 Prevailing-Torque Metric Hex Nuts	Table 29
ANSI B18.16.3M-1998 Prevailing-Torque Metric Hex Flange Nuts	Table 30
ANSI B18.2.4.5M-1979 Metric Hex Jam Nuts	Table 31
ANSI B18.2.4.6M-1979 (R1990) Metric Heavy Hex Nuts	Table 31
ANSI B18.22M-1981 (R1990) Metric Plain Washers	Table 32

Manufacturers should be consulted concerning which items and sizes are in stock production.

Comparison with ISO Standards.— American National Standards for metric bolts, screws and nuts have been coordinated to the extent possible with the comparable ISO Standards or proposed Standards. The dimensional differences between the ANSI and the comparable ISO Standards or proposed Standards are few, relatively minor, and none will affect the functional interchangeability of bolts, screws, and nuts manufactured to the requirements of either.

Where no comparable ISO Standard had been developed, as was the case when the ANSI Standards for Metric Heavy Hex Screws, Metric Heavy Hex Bolts, and Metric Hex Lag Screws were adopted, nominal diameters, thread pitches, body diameters, widths across flats, head heights, thread lengths, thread dimensions, and nominal lengths are in accord with ISO Standards for related hex head screws and bolts. At the time of ANSI adoption (1982) there was no ISO Standard for round head square neck bolts.

The following functional characteristics of hex head screws and bolts are in agreement between the respective ANSI Standard and the comparable ISO Standard or proposed Standard: diameters and thread pitches, body diameters, widths across flats (see exception below), bearing surface diameters (except for metric hex bolts), flange diameters (for metric hex flange screws), head heights, thread lengths, thread dimensions, and nominal lengths.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard Metric Hex Cap Screws
ANSI/ASME B18.2.3.1M-1979 (R1995)



Nominal Screw Dia., D, and Thread Pitch	Body Dia., D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1	Washer Face Thick., C		Washer Face Dia., D_w
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Min
M5 × 0.8	5.00	4.82	8.00	7.78	9.24	8.79	3.65	3.35	2.4	0.5	0.2	7.0
M6 × 1	6.00	5.82	10.00	9.78	11.55	11.05	4.15	3.85	2.8	0.5	0.2	8.9
M8 × 1.25	8.00	7.78	13.00	12.73	15.01	14.38	5.50	5.10	3.7	0.6	0.3	11.6
[a]M10 × 1.5	10.00	9.78	15.00	14.73	17.32	16.64	6.63	6.17	4.5	0.6	0.3	13.6
M10 × 1.5	10.00	9.78	16.00	15.73	18.48	17.77	6.63	6.17	4.5	0.6	0.3	14.6
M12 × 1.75	12.00	11.73	18.00	17.73	20.78	20.03	7.76	7.24	5.2	0.6	0.3	16.6
M14 × 2	14.00	13.73	21.00	20.67	24.25	23.35	9.09	8.51	6.2	0.6	0.3	19.6
M16 × 2	16.00	15.73	24.00	23.67	27.71	26.75	10.32	9.68	7.0	0.8	0.4	22.5
M20 × 2.5	20.00	19.67	30.00	29.16	34.64	32.95	12.88	12.12	8.8	0.8	0.4	27.7
M24 × 3	24.00	23.67	36.00	35.00	41.57	39.55	15.44	14.56	10.5	0.8	0.4	33.2
M30 × 3.5	30.00	29.67	46.00	45.00	53.12	50.85	19.48	17.92	13.1	0.8	0.4	42.7
M36 × 4	36.00	35.61	55.00	53.80	63.51	60.79	23.38	21.62	15.8	0.8	0.4	51.1
M42 × 4.5	42.00	41.38	65.00	62.90	75.06	71.71	26.97	25.03	18.2	1.0	0.5	59.8
M48 × 5	48.00	47.38	75.00	72.60	86.60	82.76	31.07	28.93	21.0	1.0	0.5	69.0
M56 × 5.5	56.00	55.26	85.00	82.20	98.15	93.71	36.20	33.80	24.5	1.0	0.5	78.1
M64 × 6	64.00	63.26	95.00	91.80	109.70	104.65	41.32	38.68	28.0	1.0	0.5	87.2
M72 × 6	72.00	71.26	105.00	101.40	121.24	115.60	46.45	43.55	31.5	1.2	0.6	96.3
M80 × 6	80.00	79.26	115.00	111.00	132.72	126.54	51.58	48.42	35.0	1.2	0.6	105.4
M90 × 6	90.00	89.13	130.00	125.50	150.11	143.07	57.74	54.26	39.2	1.2	0.6	119.2
M100 × 6	100.00	99.13	145.00	140.00	167.43	159.60	63.90	60.10	43.4	1.2	0.6	133.0

[a] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 hex cap screws with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

Basic thread lengths, B, are the same as given in Table 12.

Transition thread length, X, includes the length of incomplete threads and tolerances on grip gaging length and body length. It is intended for calculation purposes.

For additional manufacturing and acceptance specifications, reference should be made to the ANSI/ASME B18.2.3.1M-1979 (R1995).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Metric Formed Hex Screws
ANSI/ASME B18.2.3.2M-1979 (R1995)



Nominal Screw Dia., D, and Thread Pitch	Body Dia., D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1	Washer Face Thick., C		Washer Face Dia., D_w
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max
M5 × 0.8	5.00	4.82	8.00	7.64	9.24	8.56	3.65	3.35	2.4	0.5	0.2	6.9
M6 × 1	6.00	5.82	10.00	9.64	11.55	10.80	4.15	3.85	2.0	0.5	0.2	8.9
M8 × 1.25	8.00	7.78	13.00	12.57	15.01	14.08	5.50	5.10	3.7	0.6	0.3	11.6
[a]M10 × 1.5	10.00	9.78	15.00	14.57	17.32	16.32	6.63	6.17	4.5	0.6	0.3	13.6
M10 × 1.5	10.00	9.78	16.00	15.57	18.48	17.43	6.63	6.17	4.5	0.6	0.3	14.6
M12 × 1.75	12.00	11.73	18.00	17.57	20.78	19.68	7.76	7.24	5.2	0.6	0.3	16.6
M14 × 2	14.00	13.73	21.00	20.16	24.25	22.58	9.09	8.51	6.2	0.6	0.3	19.6
M16 × 2	16.00	15.73	24.00	23.16	27.71	25.94	10.32	9.68	7.0	0.8	0.4	22.5
M20 × 2.5	20.00	19.67	30.00	29.16	34.64	32.66	12.88	12.12	8.8	0.8	0.4	27.7
M24 × 3	24.00	23.67	36.00	35.00	41.57	39.20	15.44	14.56	10.5	0.8	0.4	33.2

[a]This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 formed hex screws with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

†Basic thread lengths, B, are the same as given in Table 12.

‡Transition thread length, X, includes the length of incomplete threads and tolerances on the grip gaging length and body length. It is intended for calculation purposes.

For additional manufacturing and acceptance specifications, reference should be made to the Standard.

Socket head cap screws ANSI B18.3.1M-1986 are functionally interchangeable with screws which conform to ISO R861-1968 or ISO 4762-1977. However, the thread lengths specified in the ANSI Standard are equal to or longer than required by either ISO Standard. Consequently the grip lengths also vary on screws where the North American thread length practice differs. Minor variations in head diameter, head height, key engagement and wall thickness are due to diverse tolerancing practice and will be found documented in the ANSI Standard.

One exception with respect to width across flats for metric hex cap screws, formed hex screws, and hex bolts is the M10 size. These are currently being produced in the United States with a width across flats of 15 mm. This size, however, is not an ISO Standard. Unless these M10 screws and bolts with 15 mm width across flats are specifically ordered, the M10 size with 16 mm across flats will be furnished.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Metric Heavy Hex Screws
ANSI B18.2.3.3M-1979 (R1995)



Nominal Screw Dia., D, and Thread Pitch	Body Diameter., D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1	Washer Face Thickness, C		Washer Face Dia., D_w
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Min
M12 × 1.75	12.00	11.73	21.00	20.67	24.25	23.35	7.76	7.24	5.2	0.6	0.3	19.6
M14 × 2	14.00	13.73	24.00	23.67	27.71	26.75	9.09	8.51	6.2	0.6	0.3	22.5
M16 × 2	16.00	15.73	27.00	26.67	31.18	30.14	10.32	9.68	7.0	0.8	0.4	25.3
M20 × 2.5	20.00	19.67	34.00	33.00	39.26	37.29	12.88	12.12	8.8	0.8	0.4	31.4
M24 × 3	24.00	23.67	41.00	40.00	47.34	45.20	15.44	14.56	10.5	0.8	0.4	38.0
M30 × 3.5	30.00	29.67	50.00	49.00	57.74	55.37	19.48	17.92	13.1	0.8	0.4	46.6
M36 × 4	36.00	35.61	60.00	58.80	69.28	66.44	23.38	21.72	15.8	0.8	0.4	55.9

All dimensions are in millimeters.

Basic thread lengths, B, are the same as given in Table 12.

Transition thread length, X, includes the length of incomplete threads and tolerances on grip gaging length and body length. It is intended for calculation purposes.

For additional manufacturing and acceptance specifications, reference should be made to the Standard.

ANSI letter symbols designating dimensional characteristics are in accord with those used in ISO Standards except capitals have been used for data processing convenience instead of the lower case letters used in the ISO Standards.

Metric Screw and Bolt Diameters.— Metric screws and bolts are furnished with full diameter body within the limits shown in the respective dimensional tables, or are threaded to the head (see *Metric Screw and Bolt Thread Lengths* on page 1551) unless the purchaser specifies "reduced body diameter." Metric formed hex screws (Table 4), hex flange screws (Table 4), hex bolts (Table 4), heavy hex bolts (Table 4), hex lag screws (Table 5), heavy hex flange screws (Table 6), and round head square neck bolts (Table 8) may be obtained with reduced diameter body, if so specified; however, formed hex screws, hex flange screws, heavy hex flange screws, hex bolts, or heavy hex bolts with nominal lengths shorter than $4D$, where D is the nominal diameter, are not recommended. Metric formed hex screws, hex flange screws, heavy hex flange screws, and hex lag screws with reduced body diameter will be furnished with a shoulder under the head. For metric hex bolts and heavy hex bolts this is optional with the manufacturer.

For bolts and lag screws there may be a reasonable swell, fin, or die seam on the body adjacent to the head not exceeding the nominal bolt diameter by: 0.50 mm for M5, 0.65 mm for M6, 0.75 mm for M8 through M14, 1.25 mm for M16, 1.50 mm for M20 through M30, 2.30 mm for M36 through M48, 3.00 mm for M56 through M72, and 4.80 mm for M80 through M100.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Metric Hex Screws and Bolts — Reduced Body Diameters



Nominal Dia., *D*, and Thread Pitch	Shoulder Diameter,[a] D_s		Body Diameter, D_{si}		Shoulder Length,[a] L_{sh}		Nominal Dia., *D*, and Thread Pitch	Shoulder Diameter,[a] D_s		Body Diameter, D_{si}		Shoulder Length,[a] L_{sh}	
	Max	Min	Max	Min	Max	Min		Max	Min	Max	Min	Max	Min
Metric Formed Hex Screws (ANSI B18.2.3.2M–1979, R1989)													
M5 × 0.8	5.00	4.82	4.46	4.36	3.5	2.5	M14 × 2	14.00	13.73	12.77	12.50	8.0	7.0
M6 × 1	6.00	5.82	5.39	5.21	4.0	3.0	M16 × 2	16.00	15.73	14.77	14.50	9.0	8.0
M8 × 1.25	8.00	7.78	7.26	7.04	5.0	4.0	M20 × 2.5	20.00	19.67	18.49	18.16	11.0	10.0
M10 × 1.5	10.00	9.78	9.08	8.86	6.0	5.0	M24 × 3	24.00	23.67	22.13	21.80	13.0	12.0
M12 × 1.75	12.00	11.73	10.95	10.68	7.0	6.0	…	…	…	…	…	…	…
Metric Hex Flange Screws (ANSI B18.2.3.4M–1984)													
M5 × 0.8	5.00	4.82	4.46	4.36	3.5	2.5	M12 × 1.75	12.00	11.73	10.95	10.68	7.0	6.0
M6 × 1	6.00	5.82	5.39	5.21	4.0	3.0	M14 × 2	14.00	13.73	12.77	12.50	8.0	7.0
M8 × 1.25	8.00	7.78	7.26	7.04	5.0	4.0	M16 × 2	16.00	15.73	14.77	14.50	9.0	8.0
M10 × 1.5	10.00	9.78	9.08	8.86	6.0	5.0	…	…	…	…	…	…	…
Metric Hex Bolts (ANSI B18.2.3.5M–1979, R1989)													
M5 × 0.8	5.48	4.52	4.46	4.36	3.5	2.5	M14 × 2	14.70	13.30	12.77	12.50	8.0	7.0
M6 × 1	6.48	5.52	5.39	5.21	4.0	3.0	M16 × 2	16.70	15.30	14.77	14.50	9.0	8.0
M8 × 1.25	8.58	7.42	7.26	7.04	5.0	4.0	M20 × 2.5	20.84	19.16	18.49	18.16	11.0	10.0
M10 × 1.5	10.58	9.42	9.08	8.86	6.0	5.0	M24 × 3	24.84	23.16	22.13	21.80	13.0	12.0
M12 × 1.75	12.70	11.30	10.95	10.68	7.0	6.0	…	…	…	…	…	…	…
Metric Heavy Hex Bolts (ANSI B18.2.3.6M–1979, R1989)													
M12 × 1.75	12.70	11.30	10.95	10.68	7.0	6.0	M20 × 2.5	20.84	19.16	18.49	18.16	11.0	10.0
M14 × 2	14.70	13.30	12.77	12.50	8.0	7.0	M24 × 3	24.84	23.16	22.13	21.80	13.0	12.0
M16 × 2	16.70	15.30	14.77	14.50	9.0	8.0	…	…	…	…	…	…	…
Metric Heavy Hex Flange Screws (ANSI B18.2.3.9M–1984)													
M10 × 1.5	10.00	9.78	9.08	8.86	6.0	5.0	M16 × 2	16.00	15.73	14.77	14.50	9.0	8.0
M12 × 1.75	12.00	11.73	10.95	10.68	7.0	6.0	M20 × 2.5	20.00	19.67	18.49	18.16	11.0	10.0
M14 × 2	14.00	13.73	12.77	12.50	8.0	7.0	…	…	…	…	…	…	…

[a] Shoulder is mandatory for formed hex screws, hex flange screws, and heavy hex flange screws. Shoulder is optional for hex bolts and heavy hex bolts.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Metric Hex Lag Screws
ANSI B18.2.3.8M–1981, R1991



Nominal Screw Dia., *D*	Body Diameter, D_s		Width Across Flats, *S*		Width Across Corners, *E*		Head Height, *K*		Wrenching Height, K_1
	Max	Min	Max	Min	Max	Min	Max	Min	Min
5	5.48	4.52	8.00	7.64	9.24	8.63	3.9	3.1	2.4
6	6.48	5.52	10.00	9.64	11.55	10.89	4.4	3.6	2.8
8	8.58	7.42	13.00	12.57	15.01	14.20	5.7	4.9	3.7
10	10.58	9.42	16.00	15.57	18.48	17.59	6.9	5.9	4.5
12	12.70	11.30	18.00	17.57	20.78	19.85	8.0	7.0	5.2
16	16.70	15.30	24.00	23.16	27.71	26.17	10.8	9.3	7.0
20	20.84	19.16	30.00	29.16	34.64	32.95	13.4	11.6	8.8
24	24.84	23.16	36.00	35.00	41.57	39.55	15.9	14.1	10.5

Nominal Screw Dia., *D*	Thread Dimensions				Nominal Screw Dia., *D*	Thread Dimensions			
	Thread Pitch, *P*	Flat at Root, *V*	Depth of Thread, *T*	Root Dia., D_1		Thread Pitch, *P*	Flat at Root, *V*	Depth of Thread, *T*	Root Dia., D_1
5	2.3	1.0	0.9	3.2	12	4.2	1.8	1.6	8.7
6	2.5	1.1	1.0	4.0	16	5.1	2.2	2.0	12.0
8	2.8	1.2	1.1	5.8	20	5.6	2.4	2.2	15.6
10	3.6	1.6	1.4	7.2	24	7.3	3.1	2.8	18.1

REDUCED BODY DIAMETER



Nominal Screw Dia., *D*	Shoulder Diameter, D_s		Shoulder Length, L_{sh}		Nominal Screw Dia., *D*	Shoulder Diameter, D_s		Shoulder Length, L_{sh}	
	Max	Min	Max	Min		Max	Min	Max	Min
5	5.48	4.52	3.5	2.5	12	12.70	11.30	7.0	6.0
6	6.48	5.52	4.0	3.0	16	16.70	15.30	9.0	8.0
8	8.58	7.42	5.0	4.0	20	20.84	19.16	11.0	10.0
10	10.58	9.42	6.0	5.0	24	24.84	23.16	13.0	12.0

All dimensions are in millimeters. Reduced body diameter, D_{si}, is the blank diameter before rolling. Shoulder is mandatory when body diameter is reduced.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Metric Heavy Hex Flange Screws *ANSI/ASME B18.2.3.9M-1984*



Nominal Screw Dia., D, and Thread Pitch	Body Dia., D_s		Width Across Flats, S		Width Across Corners, E		Flange Dia., D_c	Bearing Circle Dia., D_w	Flange Edge Thickness, C	Head Height, K	Wrenching Height K_1	Fillet Radius, R
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max
M10 × 1.5	10.00	9.78	15.00	14.57	17.32	16.32	22.3	19.6	1.5	8.6	3.70	0.6
M12 × 1.75	12.00	11.73	18.00	17.57	20.78	19.68	26.6	23.8	1.8	10.4	4.60	0.7
M14 × 2	14.00	13.73	21.00	20.48	24.25	22.94	30.5	27.6	2.1	12.4	5.50	0.9
M16 × 2	16.00	15.73	24.00	23.16	27.71	25.94	35.0	31.9	2.4	14.1	6.20	1.0
M20 × 2.5	20.00	19.67	30.00	29.16	34.64	32.66	43.0	39.9	3.0	17.7	7.90	1.2

All dimensions are in millimeters. Basic thread lengths, B, are as given in Table 12. Transition thread length, x, includes the length of incomplete threads and tolerances on grip gaging length and body length. It is intended for calculation purposes. For additional manufacturing and acceptance specifications, reference should be made to ANSI/ASME B18.2.3.9M-1984 standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Metric Hex Flange Screws
ANSI/ASME B18.2.3.4M-1984



Nominal Screw Dia., D, and Thread Pitch	Body Dia., D_s		Width Across Flats, S		Width Across Corners, E		Flange Dia., D_c	Bearing Circle Dia., D_w	Flange Edge Thickness, C	Head Height, K	Wrenching Height, K_1	Fillet Radius, R
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max
M5 × 0.8	5.00	4.82	7.00	6.64	8.08	7.44	11.4	9.4	1.0	5.6	2.30	0.3
M6 × 1	6.00	5.82	8.00	7.64	9.24	8.56	13.6	11.6	1.1	6.8	2.90	0.4
M8 × 1.25	8.00	7.78	10.00	9.64	11.55	10.80	17.0	14.9	1.2	8.5	3.80	0.5
M10 × 1.5	10.00	9.78	13.00	12.57	15.01	14.08	20.8	18.7	1.5	9.7	4.30	0.6
M12 × 1.75	12.00	11.73	15.00	14.57	17.32	16.32	24.7	22.0	1.8	11.9	5.40	0.7
M14 × 2	14.00	13.73	18.00	17.57	20.78	19.68	28.6	25.9	2.1	12.9	5.60	0.8
M16 × 2	16.00	15.73	21.00	20.48	24.25	22.94	32.8	30.1	2.4	15.1	6.70	1.0

All dimensions are in millimeters. Basic thread lengths, B, are the same as given in Table 12. Transition thread length, x, includes the length of incomplete threads and tolerances on grip gaging length and body length. This dimension is intended for calculation purposes only. For additional manufacturing and acceptance specifications, reference should be made to ANSI/ASME B18.2.3.4M-1984 standard.

Table 8. American National Standard Metric Round Head Square Neck Bolts Reduced Body Diameters *ANSI/ASME B18.5.2.2M-1982 (R1993)*



Nominal Bolt Dia., D and Thread Pitch	Diameter of Reduced Body D_r		Nominal Bolt Dia., D and Thread Pitch	Diameter of Reduced Body D_r	
	Max	Min		Max	Min
M5 × 0.8	5.00	4.36	M14 × 2	14.00	12.50
M6 × 1	6.00	5.21	M16 × 2	16.00	14.50
M8 × 1.25	8.00	7.04	M20 × 2.5	20.00	18.16
M10 × 1.5	10.00	8.86	M24 × 3	24.00	21.80
M12 × 1.75	12.00	10.68	…	…	…

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Metric Round Head Square Neck Bolts *ANSI B18.2.3.7M–1979 (R1989)*



Nominal Bolt Dia., *D* and Thread Pitch	Diameter of Full Body, D_s		Head Radius, (R_k)	Head height, *K*		Head Edge Thickness, *C*		Head Dia., D_c	Bearing Surface Dia., D_w	Square Depth, *F*		Square Corner Depth, F_1	Square Width Across Flats, *V*		Square Width Across Corners, *E*	
	Max	Min	Ref.	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max	Min
M5 × 0.8	5.48	4.52	8.8	3.1	2.5	1.8	1.0	11.8	9.8	3.1	2.5	1.6	5.48	4.88	7.75	6.34
M6 × 1	6.48	5.52	10.7	3.6	3.0	1.9	1.1	14.2	12.2	3.6	3.0	1.9	6.48	5.88	9.16	7.64
M8 × 1.25	8.58	7.42	12.5	4.8	4.0	2.2	1.2	18.0	15.8	4.8	4.0	2.5	8.58	7.85	12.13	10.20
M10 × 1.5	10.58	9.42	15.5	5.8	5.0	2.5	1.5	22.3	19.6	5.8	5.0	3.2	10.58	9.85	14.96	12.80
M12 × 1.75	12.70	11.30	19.0	6.8	6.0	2.8	1.8	26.6	23.8	6.8	6.0	3.8	12.70	11.82	17.96	15.37
M14 × 2	14.70	13.30	21.9	7.9	7.0	3.3	2.1	30.5	27.6	7.9	7.0	4.4	14.70	13.82	20.79	17.97
M16 × 2	16.70	15.30	25.5	8.9	8.0	3.6	2.4	35.0	31.9	8.9	8.0	5.0	16.70	15.82	23.62	20.57
M20 × 2.5	20.84	19.16	31.9	10.9	10.0	4.2	3.0	43.0	39.9	10.9	10.0	6.3	20.84	19.79	29.47	25.73
M24 × 3	24.84	23.16	37.9	13.1	12.0	5.1	3.6	51.0	47.6	13.1	12.0	7.6	24.84	23.79	35.13	30.93

All dimensions are in millimeters.

†L_g is the grip gaging length which controls the length of thread *B*.

‡*B* is the basic thread length and is a reference dimension (see Table 13).

For additional manufacturing and acceptance specifications, see ANSI/ASME B18.5.2.2M-1982, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ANSI Heavy Hex Bolts *ANSI B18.2.3.6M–1979 (R1989)*



Nominal Dia., D and Thread Pitch	Body Diameter, D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1
	Max	Min	Max	Min	Max	Min	Max	Min	Min
M12 × 1.75	12.70	11.30	21.00	20.16	24.25	22.78	7.95	7.24	5.2
M14 × 2	14.70	13.30	24.00	23.16	27.71	26.17	9.25	8.51	6.2
M16 × 2	16.70	15.30	27.00	26.16	31.18	29.56	10.75	9.68	7.0
M20 × 2.5	20.84	19.16	34.00	33.00	39.26	37.29	13.40	12.12	8.8
M24 × 3	24.84	23.16	41.00	40.00	47.34	45.20	15.90	14.56	10.5
M30 × 3.5	30.84	29.16	50.00	49.00	57.74	55.37	19.75	17.92	13.1
M36 × 4	37.00	35.00	60.00	58.80	69.28	66.44	23.55	21.72	15.8

All dimensions are in millimeters.*Basic thread lengths, B, are the same as given in Table 12.For additional manufacturing and acceptance specifications, reference should be made to the ANSI B18.2.3.6M–1979, R1989 standard.

Table 11. ANSI Metric Heavy Hex Structural Bolts *ANSI B18.2.3.7M–1979 (R1989)*



Dia. D, and Thread Pitch	Body Diameter, D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1	Washer Face Dia., D_w	Washer Face Thickness, C		Thread Length, B[a]		Transition Thread Length, X[b]
													Lengths ≤ 100	Lengths > 100	
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Min	Max	Min	Basic		Max
M16 × 2	16.70	15.30	27.00	26.16	31.18	29.56	10.75	9.25	6.5	24.9	0.8	0.4	31	38	6.0
M20 × 2.5	20.84	19.16	34.00	33.00	39.26	37.29	13.40	11.60	8.1	31.4	0.8	0.4	36	43	7.5
M22 × 2.5	22.84	21.16	36.00	35.00	41.57	39.55	14.90	13.10	9.2	33.3	0.8	0.4	38	45	7.5
M24 × 3	24.84	23.16	41.00	40.00	47.34	45.20	15.90	14.10	9.9	38.0	0.8	0.4	41	48	9.0
M27 × 3	27.84	26.16	46.00	45.00	53.12	50.85	17.90	16.10	11.3	42.8	0.8	0.4	44	51	9.0
M30 × 3.5	30.84	29.16	50.00	49.00	57.74	55.37	19.75	17.65	12.4	46.5	0.8	0.4	49	56	10.5
M36 × 4	37.00	35.00	60.00	58.80	69.28	66.44	23.55	21.45	15.0	55.9	0.8	0.4	56	63	12.0

[a] Basic thread length, B, is a reference dimension.

[b] Transition thread length, X, includes the length of incomplete threads and tolerances on grip gaging length and body length. It is intended for calculation purposes.

All dimensions are in millimeters.

For additional manufacturing and acceptance specifications, reference should be made to the ANSI B18.2.3.7M-1979 (R1995) standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. American National Standard Metric Hex Bolts
ANSI/ASME B18.2.3.5M-1989



Nominal Bolt Dia., D and Thread Pitch	Body Diameter, D_s		Width Across Flats, S		Width Across Corners, E		Head Height, K		Wrenching Height, K_1	For Bolt Lengths		
										< 125 mm	> 125 and < 200 mm	> 200 mm
	Max	Min	Max	Min	Max	Min	Max	Min	Min	Basic Thread Length,[a] B		
M5 × 0.8	5.48	4.52	8.00	7.64	9.24	8.63	3.58	3.35	2.4	16	22	35
M6 × 1	6.19	5.52	10.00	9.64	11.55	10.89	4.38	3.55	2.8	18	24	37
M8 × 1.25	8.58	7.42	13.00	12.57	15.01	14.20	5.68	5.10	3.7	22	28	41
[b]M10 × 1.5	10.58	9.42	15.00	14.57	17.32	16.46	6.85	6.17	4.5	26	32	45
M10 × 1.5	10.58	9.42	16.00	15.57	18.48	17.59	6.85	6.17	4.5	26	32	45
M12 × 1.75	12.70	11.30	18.00	17.57	20.78	19.85	7.95	7.24	5.2	30	36	49
M14 × 2	14.70	13.30	21.00	20.16	24.25	22.78	9.25	8.51	6.2	34	40	53
M16 × 2	16.70	15.30	24.00	23.16	27.71	26.17	10.75	9.68	7.0	38	44	57
M20 × 2.5	20.84	19.16	30.00	29.16	34.64	32.95	13.40	12.12	8.8	46	52	65
M24 × 3	24.84	23.16	36.00	35.00	41.57	39.55	15.90	14.56	10.5	54	60	73
M30 × 3.5	30.84	29.16	46.00	45.00	53.12	50.55	19.75	17.92	13.1	66	72	85
M36 × 4	37.00	35.00	55.00	53.80	63.51	60.79	23.55	21.72	15.8	78	84	97
M42 × 4.5	43.00	41.00	65.00	62.90	75.06	71.71	27.05	25.03	18.2	90	96	109
M48 × 5	49.00	47.00	75.00	72.60	86.60	82.76	31.07	28.93	21.0	102	108	121
M56 × 5.5	57.20	54.80	85.00	82.20	98.15	93.71	36.20	33.80	24.5	…	124	137
M64 × 6	65.52	62.80	95.00	91.80	109.70	104.65	41.32	38.68	28.0	…	140	153
M72 × 6	73.84	70.80	105.00	101.40	121.24	115.60	46.45	43.55	31.5	…	156	169
M80 × 6	82.16	78.80	115.00	111.00	132.79	126.54	51.58	48.42	35.0	…	172	185
M90 × 6	92.48	88.60	130.00	125.50	150.11	143.07	57.74	54.26	39.2	…	192	205
M100 × 6	102.80	98.60	145.00	140.00	167.43	159.60	63.90	60.10	43.4	…	212	225

[a] Basic thread length, B, is a reference dimension.

[b] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 hex bolts with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

For additional manufacturing and acceptance specifications, reference should be made to the ANSI B18.2.3.5M-1979 (R1995) standard.

Materials and Mechanical Properties.— Unless otherwise specified, steel metric screws and bolts, with the exception of heavy hex structural bolts, hex lag screws, and socket head cap screws, conform to the requirements specified in SAE J1199 or ASTM F568. Steel heavy hex structural bolts conform to ASTM A325M or ASTM A490M. Alloy steel socket head cap screws conform to ASTM A574M, property class 12.9, where the numeral 12 represents approximately one-hundredth of the minimum tensile strength in megapascals and the decimal .9 approximates the ratio of the minimum yield stress to the minimum tensile stress. This is in accord with ISO designation practice. Screws and bolts

Copyright 2004, Industrial Press, Inc., New York, NY

of other materials, and all materials for hex lag bolts, have properties as agreed upon by the purchaser and the manufacturer.

Except for socket head cap screws, metric screws and bolts are furnished with a natural (as processed) finish, unplated or uncoated unless otherwise specified.

Alloy steel socket head cap screws are furnished with an oiled black oxide coating (thermal or chemical) unless a protective plating or coating is specified by the purchaser.

Metric Screw and Bolt Identification Symbols.— Screws and bolts are identified on the top of the head by property class symbols and manufacturer's identification symbol.

Metric Screw and Bolt Designation.— Metric screws and bolts with the exception of socket head cap screws are designated by the following data, preferably in the sequence shown: product name, nominal diameter and thread pitch (except for hex lag screws), nominal length, steel property class or material identification, and protective coating, if required.

Example: Hex cap screw, M10 × 1.5 × 50, class 9.8, zinc plated

Heavy hex structural bolt, M24 × 3 × 80, ASTM A490M

Hex lag screw, 6 × 35, silicon bronze.

Socket head cap screws (metric series) are designated by the following data in the order shown: ANSI Standard number, nominal size, thread pitch, nominal screw length, name of product (may be abbreviated SHCS), material and property class (alloy steel screws are supplied to property class 12.9 as specified in ASTM A574M: corrosion-resistant steel screws are specified to the property class and material requirements in ASTM F837M), and protective finish, if required.

Example: B18.3.1M—6 × 1 × 20 Hexagon Socket Head Cap Screw, Alloy Steel

B18.3.1M—10 × 1.5 × 40 SHCS, Alloy Steel Zinc Plated.

Metric Screw and Bolt Thread Lengths.— The length of thread on metric screws and bolts (except for metric lag screws) is controlled by the grip gaging length, L_g max. This is the distance measured parallel to the axis of the screw or bolt, from under the head bearing surface to the face of a noncounterbored or noncountersunk standard GO thread ring gage assembled by hand as far as the thread will permit. The maximum grip gaging length, as calculated and rounded to one decimal place, is equal to the nominal screw length, L, minus the basic thread length, B, or in the case of socket head cap screws, minus the minimum thread length L_T. B and L_T are reference dimensions intended for calculation purposes only and will be found in Tables 12 and 14, respectively.

Table 13. Basic Thread Lengths for Metric Round Head Square Neck Bolts
ANSI/ASME B18.5.2.2M-1982, R1993

Nom. Bolt Dia., D and Thread Pitch	Bolt Length, L			Nom. Bolt Dia., D and Thread Pitch	Bolt Length, L		
	≤ 125	> 125 and ≤ 200	> 200		≤ 125	> 125 and ≤ 200	> 200
	Basic Thread Length, B				Basic Thread length, B		
M5 × 0.8	16	22	35	M14 × 2	34	40	53
M6 × 1	18	24	37	M16 × 2	38	44	57
M8 × 1.25	22	28	41	M20 × 2.5	46	52	65
M10 × 1.5	26	32	45	M24 × 3	54	60	73
M12 × 1.75	30	36	49	…	…	…	…

All dimensions are in millimeters

Basic thread length B is a reference dimension intended for calculation purposes only.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Socket Head Cap Screws (Metric Series)—Length of Complete Thread
ANSI/ASME B18.3.1M-1986

Nominal Size	Length of Complete Thread, L_T	Nominal Size	Length of Complete Thread, L_T	Nominal Size	Length of Complete Thread, L_T
M1.6	15.2	M6	24.0	M20	52.0
M2	16.0	M8	28.0	M24	60.0
M2.5	17.0	M10	32.0	M30	72.0
M3	18.0	M12	36.0	M36	84.0
M4	20.0	M14	40.0	M42	96.0
M5	22.0	M16	44.0	M48	108.0

Grip length, L_G equals screw length, L, minus L_T. Total length of thread L_{TT} equals L_T plus 5 times the pitch of the coarse thread for the respective screw size. Body length L_B equals L minus L_{TT}.

The minimum thread length for hex lag screws is equal to one-half the nominal screw length plus 12 mm, or 150 mm, whichever is shorter. Screws too short for this formula to apply are threaded as close to the head as practicable.

Metric Screw and Bolt Diameter-Length Combinations.— For a given diameter, the recommended range of lengths of metric cap screws, formed hex screws, heavy hex screws, hex flange screws, and heavy hex flange screws can be found in Table 16, for heavy hex structural bolts in Table 17, for hex lag screws in Table 15, for round head square neck bolts in Table 18, and for socket head cap screws in Table 19. No recommendations for diameter-length combinations are given in the Standards for hex bolts and heavy hex bolts.

Hex bolts in sizes M5 through M24 and heavy hex bolts in sizes M12 through M24 are standard only in lengths longer than 150 mm or 10D, whichever is shorter. When shorter lengths of these sizes are ordered, hex cap screws are normally supplied in place of hex bolts and heavy hex screws in place of heavy hex bolts. Hex bolts in sizes M30 and larger and heavy hex bolts in sizes M30 and M36 are standard in all lengths; however, at manufacturer's option, hex cap screws may be substituted for hex bolts and heavy hex screws for heavy hex bolts for any diameter-length combination.

Table 15. Recommended Diameter-Length Combinations for Metric Hex Lag Screws *ANSI B18.2.3.8M-1981 (R1999)*

Nominal Length, L	Nominal Screw Diameter								Nominal Length, L	Nominal Screw Diameter				
	5	6	8	10	12	16	20	24		10	12	16	20	24
8	d	…	…	…	…	…	…	…	90	d	d	d	d	d
10	d	d	…	…	…	…	…	…	100	d	d	d	d	d
12	d	d	d	…	…	…	…	…	110	…	d	d	d	d
14	d	d	d	…	…	…	…	…	120	…	d	d	d	d
16	d	d	d	d	…	…	…	…	130	…	…	d	d	d
20	d	d	d	d	d	…	…	…	140	…	…	d	d	d
25	d	d	d	d	d	d	…	…	150	…	…	d	d	d
30	d	d	d	d	d	d	d	…	160	…	…	d	d	d
35	d	d	d	d	d	d	d	d	180	…	…	…	d	d
40	d	d	d	d	d	d	d	d	200	…	…	…	d	d
45	d	d	d	d	d	d	d	d	220	…	…	…	…	d
50	d	d	d	d	d	d	d	d	240	…	…	…	…	d
60	…	d	d	d	d	d	d	d	260	…	…	…	…	d
70	…	…	d	d	d	d	d	d	280	…	…	…	…	d
80	…	…	d	d	d	d	d	d	300	…	…	…	…	d

All dimensions are in millimeters.

Recommended diameter-length combinations are indicated by the symbol d.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. Rec'd Diameter-Length Combinations for Metric Hex Cap Screws, Formed Hex and Heavy Hex Screws, Hex Flange and Heavy Hex Flange Screws

	Diameter—Pitch										
Nominal Length[a]	M5 ×0.8	M6 ×1	M8 ×1.25	M10 ×1.5	M12 ×1.75	M14 ×2	M16 ×2	M20 ×2.5	M24 ×3	M30 ×3.5	M36 ×4
8	d	…	…	…	…	…	…	…	…	…	…
10	d	d	…	…	…	…	…	…	…	…	…
12	d	d	d	…	…	…	…	…	…	…	…
14	d	d	d	d[b]	…	…	…	…	…	…	…
16	d	d	d	d	d[b]	d[b]	…	…	…	…	…
20	d	d	d	d	d	d	…	…	…	…	…
25	d	d	d	d	d	d	d	…	…	…	…
30	d	d	d	d	d	d	d	d	…	…	…
35	d	d	d	d	d	d	d	d	d	…	…
40	d	d	d	d	d	d	d	d	d	d	…
45	d	d	d	d	d	d	d	d	d	d	…
50	d	d	d	d	d	d	d	d	d	d	d
(55)	…	d	d	d	d	d	d	d	d	d	d
60	…	d	d	d	d	d	d	d	d	d	d
(65)	…	…	d	d	d	d	d	d	d	d	d
70	…	…	d	d	d	d	d	d	d	d	d
(75)	…	…	d	d	d	d	d	d	d	d	d
80	…	…	d	d	d	d	d	d	d	d	d
(85)	…	…	…	d	d	d	d	d	d	d	d
90	…	…	…	d	d	d	d	d	d	d	d
100	…	…	…	d	d	d	d	d	d	d	d
110	…	…	…	…	d	d	d	d	d	d	d
120	…	…	…	…	d	d	d	d	d	d	d
130	…	…	…	…	…	d	d	d	d	d	d
140	…	…	…	…	…	d	d	d	d	d	d
150	…	…	…	…	…	…	d	d	d	d	d
160	…	…	…	…	…	…	d	d	d	d	d
(170)	…	…	…	…	…	…	…	d	d	d	d
180	…	…	…	…	…	…	…	d	d	d	d
(190)	…	…	…	…	…	…	…	d	d	d	d
200	…	…	…	…	…	…	…	d	d	d	d
220	…	…	…	…	…	…	…	…	d	d	d
240	…	…	…	…	…	…	…	…	d	d	d
260	…	…	…	…	…	…	…	…	…	d	d
280	…	…	…	…	…	…	…	…	…	d	d
300	…	…	…	…	…	…	…	…	…	d	d

[a] Lengths in parentheses are not recommended. Recommended lengths of formed hex screws, hex flange screws, and heavy hex flange screws do not extend above 150 mm. Recommended lengths of heavy hex screws do not extend below 20 mm. Standard sizes for government use. Recommended diameter-length combinations are indicated by the symbol d. Screws with lengths above heavy cross lines are threaded full length.

[b] Does not apply to hex flange screws and heavy hex flange screws.

All dimensions are in millimeters.

For available diameters of each type of screw, see respective dimensional table.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. Recommended Diameter-Length Combinations for Metric Heavy Hex Structural Bolts

Nominal Length, *L*	Nominal Diameter and Thread Pitch						
	M16 × 2	M20 × 2.5	M22 × 2.5	M24 × 3	M27 × 3	M30 × 3.5	M36 × 4
45	d	…	…	…	…	…	…
50	d	d	…	…	…	…	…
55	d	d	d	…	…	…	…
60	d	d	d	d	…	…	…
65	d	d	d	d	d	…	…
70	d	d	d	d	d	d	…
75	d	d	d	d	d	d	…
80	d	d	d	d	d	d	d
85	d	d	d	d	d	d	d
90	d	d	d	d	d	d	d
95	d	d	d	d	d	d	d
100	d	d	d	d	d	d	d
110	d	d	d	d	d	d	d
120	d	d	d	d	d	d	d
130	d	d	d	d	d	d	d
140	d	d	d	d	d	d	d
150	d	d	d	d	d	d	d
160	d	d	d	d	d	d	d
170	d	d	d	d	d	d	d
180	d	d	d	d	d	d	d
190	d	d	d	d	d	d	d
200	d	d	d	d	d	d	d
210	d	d	d	d	d	d	d
220	d	d	d	d	d	d	d
230	d	d	d	d	d	d	d
240	d	d	d	d	d	d	d
250	d	d	d	d	d	d	d
260	d	d	d	d	d	d	d
270	d	d	d	d	d	d	d
280	d	d	d	d	d	d	d
290	d	d	d	d	d	d	d
300	d	d	d	d	d	d	d

All dimensions are in millimeters.
Recommended diameter-length combinations are indicated by the symbol d.
Bolts with lengths above the heavy cross lines are threaded full length.

Table 18. Recommended Diameter-Length Combinations for Metric Round Head Square Neck Bolts

Nominal Length,[a] *L*	Nominal Diameter and Thread Pitch								
	M5 × 0.8	M6 × 1	M8 × 1.25	M10 × 1.5	M12 × 1.75	M14 × 2	M16 × 2	M20 × 2.5	M24 × 3
10	d	…	…	…	…	…	…	…	…
12	d	d	…	…	…	…	…	…	…
(14)	d	d	…	…	…	…	…	…	…
16	d	d	d	…	…	…	…	…	…
20	d	d	d	d	…	…	…	…	…
25	d	d	d	d	d	…	…	…	…
30	d	d	d	d	d	d	d	…	…
35	d	d	d	d	d	d	d	…	…
40	d	d	d	d	d	d	d	d	…
45	d	d	d	d	d	d	d	d	d
50	d	d	d	d	d	d	d	d	d
(55)	…	d	d	d	d	d	d	d	d
60	…	d	d	d	d	d	d	d	d
(65)	…	…	d	d	d	d	d	d	d
70	…	…	d	d	d	d	d	d	d
(75)	…	…	d	d	d	d	d	d	d
80	…	…	d	d	d	d	d	d	d

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. *(Continued)* Recommended Diameter-Length Combinations for Metric Round Head Square Neck Bolts

Nominal Length,[a] *L*	Nominal Diameter and Thread Pitch								
	M5 × 0.8	M6 × 1	M8 × 1.25	M10 × 1.5	M12 × 1.75	M14 × 2	M16 × 2	M20 × 2.5	M24 × 3
(85)	…	…	…	d	d	d	d	d	d
90	…	…	…	d	d	d	d	d	d
100	…	…	…	d	d	d	d	d	d
110	…	…	…	…	d	d	d	d	d
120	…	…	…	…	d	d	d	d	d
130	…	…	…	…	…	d	d	d	d
140	…	…	…	…	…	d	d	d	d
150	…	…	…	…	…	…	d	d	d
160	…	…	…	…	…	…	d	d	d
(170)	…	…	…	…	…	…	…	d	d
180	…	…	…	…	…	…	…	d	d
(190)	…	…	…	…	…	…	…	d	d
200	…	…	…	…	…	…	…	d	d
220	…	…	…	…	…	…	…	…	d
240	…	…	…	…	…	…	…	…	d

[a] Bolts with lengths above the heavy cross lines are threaded full length. Lengths in ( ) are not recommended.

All dimensions are in millimeters. Recommended diameter-length combinations are indicated by the symbol d. Standard sizes for government use.

Table 19. Diameter-Length Combinations for Socket Head Cap Screws (Metric Series)

Nominal Length, *L*	Nominal Size													
	M1.6	M2	M2.5	M3	M4	M5	M6	M8	M10	M12	M14	M16	M20	M24
20	d	d												
25	d	d	d	d										
30	d	d	d	d	d									
35	…	d	d	d	d	d	d							
40	…	d	d	d	d	d	d							
45	…	…	d	d	d	d	d	d						
50	…	…	d	d	d	d	d	d	d					
55	…	…	…	d	d	d	d	d	d					
60	…	…	…	d	d	d	d	d	d	d				
65	…	…	…	d	d	d	d	d	d	d	d			
70	…	…	…	…	d	d	d	d	d	d	d	d		
80	…	…	…	…	d	d	d	d	d	d	d	d		
90	…	…	…	…	…	d	d	d	d	d	d	d	d	
100	…	…	…	…	…	d	d	d	d	d	d	d	d	d
110	…	…	…	…	…	…	d	d	d	d	d	d	d	d
120	…	…	…	…	…	…	d	d	d	d	d	d	d	d
130	…	…	…	…	…	…	…	d	d	d	d	d	d	d
140	…	…	…	…	…	…	…	d	d	d	d	d	d	d
150	…	…	…	…	…	…	…	d	d	d	d	d	d	d
160	…	…	…	…	…	…	…	d	d	d	d	d	d	d
180	…	…	…	…	…	…	…	…	d	d	d	d	d	d
200	…	…	…	…	…	…	…	…	d	d	d	d	d	d
220	…	…	…	…	…	…	…	…	…	d	d	d	d	d
240	…	…	…	…	…	…	…	…	…	d	d	d	d	d
260	…	…	…	…	…	…	…	…	…	…	d	d	d	d
300	…	…	…	…	…	…	…	…	…	…	…	d	d	d

All dimensions are in millimeters. Screws with lengths above heavy cross lines are threaded full length. Diameter-length combinations are indicated by the symbol d. Standard sizes for government use. In addition to the lengths shown, the following lengths are standard: 3, 4, 5, 6, 8, 10, 12, and 16 mm. No diameter-length combinations are given in the Standard for these lengths. Screws larger than M24 with lengths equal to or shorter than L_{TT} (see Table 14 footnote) are threaded full length.

Copyright 2004, Industrial Press, Inc., New York, NY

Metric Screw and Bolt Thread Series.— Unless otherwise specified, metric screws and bolts, except for hex lag screws, are furnished with metric coarse threads conforming to the dimensions for general purpose threads given in ANSI B1.13M (see *American National Standard Metric Screw Threads M Profile* on page 1783). Except for socket head cap screws, the tolerance class is 6g, which applies to plain finish (unplated or uncoated) screws or bolts and to plated or coated screws or bolts before plating or coating. For screws with additive finish, the 6g diameters may be exceeded by the amount of the allowance, i.e. the basic diameters apply to the screws or bolts after plating or coating. For socket head cap screws, the tolerance class is 4g6g, but for plated screws, the allowance g may be consumed by the thickness of plating so that the maximum limit of size after plating is tolerance class 4h6h. Thread limits are in accordance with ANSI B1.13M. Metric hex lag screws have a special thread which is covered in Table 5.

Metric Screw and Bolt Clearance Holes.— Clearance holes for screws and bolts with the exception of hex lag screws, socket head cap screws, and round head square neck bolts are given in Table 20. Clearance holes for round head square neck bolts are given in Table 8 and drill and counterbore sizes for socket head cap screws are given in Table 21.

Table 20. Recommended Clearance Holes for Metric Hex Screws and Bolts

Nominal Dia., *D* and Thread Pitch	Clearance Hole Dia., Basic, D_h			Nominal Dia., *D* and Thread Pitch	Clearance Hole Dia., Basic, D_h		
	Close	Normal, Preferred	Loose		Close	Normal, Preferred	Loose
M5 × 0.8	5.3	5.5	5.8	M30 × 3.5	31.0	33.0	35.0
M6 × 1	6.4	6.6	7.0	M36 × 4	37.0	39.0	42.0
M8 × 1.25	8.4	9.0	10.0	M42 × 4.5	43.0	45.0	48.0
M10 × 1.5	10.5	11.0	12.0	M48 × 5	50.0	52.0	56.0
M12 × 1.75	13.0	13.5	14.5	M56 × 5.5	58.0	62.0	66.0
M14 × 2	15.0	15.5	16.5	M64 × 6	66.0	70.0	74.0
M16 × 2	17.0	17.5	18.5	M72 × 6	74.0	78.0	82.0
M20 × 2.5	21.0	22.0	24.0	M80 × 6	82.0	86.0	91.0
M22 × 2.5[a]	23.0	24.0	26.0	M90 × 6	93.0	96.0	101.0
M24 × 3	25.0	26.0	28.0	M100 × 6	104.0	107.0	112.0
M27 × 3[a]	28.0	30.0	32.0	…	…	…	…

[a] Applies only to heavy hex structural bolts.

All dimensions are in millimeters.

Does not apply to hex lag screws, hex socket head cap screws, or round head square neck bolts.

Normal Clearance: This is preferred for general purpose applications and should be specified unless special design considerations dictate the need for either a close or loose clearance hole.

Close Clearance: This should be specified only where conditions such as critical alignment of assembled parts, wall thickness or other limitations necessitate use of a minimum hole. When close clearance holes are specified, special provision (e.g. countersinking) must be made at the screw or bolt entry side to permit proper seating of the screw or bolt head.

Loose Clearance: This should be specified only for applications where maximum adjustment capability between components being assembled is necessary.

Recommended Tolerances: The clearance hole diameters given in this table are minimum size. Recommended tolerances are: for screw or bolt diameter M5, +0.2 mm; for M6 through M16, +0.3 mm; for M20 through M42, +0.4 mm; for M48 through M72, +0.5 mm; and for M80 through M100, +0.6 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. Drill and Counterbore Sizes for Metric Socket Head Cap Screws



Nominal Size or Basic Screw Diameter	Nominal Drill Size, *A*		Counterbore Diameter, *X*	Countersink Diameter,[a] *Y*
	Close Fit[b]	Normal Fit[c]		
M1.6	1.80	1.95	3.50	2.0
M2	2.20	2.40	4.40	2.6
M2.5	2.70	3.00	5.40	3.1
M3	3.40	3.70	6.50	3.6
M4	4.40	4.80	8.25	4.7
M5	5.40	5.80	9.75	5.7
M6	6.40	6.80	11.25	6.8
M8	8.40	8.80	14.25	9.2
M10	10.50	10.80	17.25	11.2
M12	12.50	12.80	19.25	14.2
M14	14.50	14.75	22.25	16.2
M16	16.50	16.75	25.50	18.2
M20	20.50	20.75	31.50	22.4
M24	24.50	24.75	37.50	26.4
M30	30.75	31.75	47.50	33.4
M36	37.00	37.50	56.50	39.4
M42	43.00	44.00	66.00	45.6
M48	49.00	50.00	75.00	52.6

[a] *Countersink:* It is considered good practice to countersink or break the edges of holes which are smaller than *B* Max. (see Table 24) in parts having a hardness which approaches, equals, or exceeds the screw hardness. If such holes are not countersunk, the heads of screws may not seat properly or the sharp edges on holes may deform the fillets on screws, thereby making them susceptible to fatigue in applications involving dynamic loading. The countersink or corner relief, however, should not be larger than is necessary to ensure that the fillet on the screw is cleared. Normally, the diameter of countersink does not have to exceed *B* Max. Countersinks or corner reliefs in excess of this diameter reduce the effective bearing area and introduce the possibility of embedment where the parts to be fastened are softer than the screws or of brinnelling or flaring the heads of the screws where the parts to be fastened are harder than the screws.

[b] *Close Fit:* The close fit is normally limited to holes for those lengths of screws which are threaded to the head in assemblies where only one screw is to be used or where two or more screws are to be used and the mating holes are to be produced either at assembly or by matched and coordinated tooling.

[c] *Normal Fit:* The normal fit is intended for screws of relatively long length or for assemblies involving two or more screws where the mating holes are to be produced by conventional tolerancing methods. It provides for the maximum allowable eccentricity of the longest standard screws and for certain variations in the parts to be fastened, such as: deviations in hole straightness, angularity between the axis of the tapped hole and that of the hole for shank, differences in center distances of the mating holes, etc.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 22. Recommended Clearance Holes for Metric Round Head Square Neck Bolts



Nom. Bolt Dia., *D* and Thd. Pitch	Clearance			Corner Radius R_h	Nom. Bolt Dia., *D* and Thd. Pitch	Clearance			Corner Radius R_h
	Close[a]	Normal[b]	Loose[c]			Close[a]	Normal[b]	Loose[c]	
	Minimum Hole Diameter or Square Width, *H*					Minimum Hole Diameter or Square Width, *H*			
M5 × 0.8	5.5	…	5.8	0.2	M14 × 2	15.0	15.5	16.5	0.6
M6 × 1	6.6	…	7.0	0.3	M16 × 2	17.0	17.5	18.5	0.6
M8 × 1.25	…	9.0	10.0	0.4	M20 × 2.5	21.0	22.0	24.0	0.8
M10 × 1.5	…	11.0	12.0	0.4	M24 × 3	25.0	26.0	28.0	1.0
M12 × 1.75	13.0	13.5	14.5	0.6	…	…	…	…	…

[a] *Close Clearance:* Close clearance should be specified only for square holes in very thin and/or soft material, or for slots, or where conditions such as critical alignment of assembled parts, wall thickness, or other limitations necessitate use of a minimal hole. Allowable swell or fins on the bolt body and/or fins on the corners of the square neck may interfere with close clearance round or square holes.

[b] *Normal Clearance:* Normal clearance hole sizes are preferred for general purpose applications and should be specified unless special design considerations dictate the need for either a close or loose clearance hole.

[c] *Loose Clearance:* Loose clearance hole sizes should be specified only for applications where maximum adjustment capability between components being assembled is necessary. Loose clearance square hole or slots may not prevent bolt turning during wrenching.

All dimensions are in millimeters.

Table 23. Drilled Head Dimensions for Metric Hex Socket Head Cap Screws



Nominal Size or Basic Screw Diameter	Hole Center Location, *W*		Drilled Hole Diameter, *X*		Hole Alignment Check Plug Diameter
	Max	Min	Max	Min	Basic
M3	1.20	0.80	0.95	0.80	0.75
M4	1.60	1.20	1.35	1.20	0.90
M5	2.00	1.50	1.35	1.20	0.90
M6	2.30	1.80	1.35	1.20	0.90
M8	2.70	2.20	1.35	1.20	0.90
M10	3.30	2.80	1.65	1.50	1.40
M12	4.00	3.50	1.65	1.50	1.40
M16	5.00	4.50	1.65	1.50	1.40
M20	6.30	5.80	2.15	2.00	1.80
M24	7.30	6.80	2.15	2.00	1.80
M30	9.00	8.50	2.15	2.00	1.80
M36	10.50	10.00	2.15	2.00	1.80

Copyright 2004, Industrial Press, Inc., New York, NY

All dimensions are in millimeters.

Drilled head metric hexagon socket head cap screws normally are not available in screw sizes smaller than M3 nor larger than M36. The M3 and M4 nominal screw sizes have two drilled holes spaced 180 degrees apart. Nominal screw sizes M5 and larger have six drilled holes spaced 60 degrees apart unless the purchaser specifies two drilled holes. The positioning of holes on opposite sides of the socket should be such that the hole alignment check plug will pass completely through the head without any deflection. When so specified by the purchaser, the edges of holes on the outside surface of the head will be chamfered 45 degrees to a depth of 0.30 to 0.50 mm.

Table 24. American National Standard Socket Head Cap Screws—Metric Series *ANSI/ASME B18.3.1M-1986*



Nom. Size and Thread Pitch	Body Diameter, *D*		Head Diameter *A*		Head Height *H*		Chamfer or Radius *S*	Hexagon Socket Size[a] *J*	Spline Socket Size[a] *M*	Key Engagement *T*	Transition Dia. *B*[a]
	Max	Min	Max	Min	Max	Min	Max	Nom.	Nom.	Min	Max
M1.6 × 0.35	1.60	1.46	3.00	2.87	1.60	1.52	0.16	1.5	1.829	0.80	2.0
M2 × 0.4	2.00	1.86	3.80	3.65	2.00	1.91	0.20	1.5	1.829	1.00	2.6
M2.5 × 0.45	2.50	2.36	4.50	4.33	2.50	2.40	0.25	2.0	2.438	1.25	3.1
M3 × 0.5	3.00	2.86	5.50	5.32	3.00	2.89	0.30	2.5	2.819	1.50	3.6
M4 × 0.7	4.00	3.82	7.00	6.80	4.00	3.88	0.40	3.0	3.378	2.00	4.7
M5 × 0.8	5.00	4.82	8.50	8.27	5.00	4.86	0.50	4.0	4.648	2.50	5.7
M6 × 1	6.00	5.82	10.00	9.74	6.00	5.85	0.60	5.0	5.486	3.00	6.8
M8 × 1.25	8.00	7.78	13.00	12.70	8.00	7.83	0.80	6.0	7.391	4.00	9.2
M10 × 1.5	10.00	9.78	16.00	15.67	10.00	9.81	1.00	8.0	…	5.00	11.2
M12 × 1.75	12.00	11.73	18.00	17.63	12.00	11.79	1.20	10.0	…	6.00	14.2
M14 × 2[b]	14.00	13.73	21.00	20.60	14.00	13.77	1.40	12.0	…	7.00	16.2
M16 × 2	16.00	15.73	24.00	23.58	16.00	15.76	1.60	14.0	…	8.00	18.2
M20 × 2.5	20.00	19.67	30.00	29.53	20.00	19.73	2.00	17.0	…	10.00	22.4
M24 × 3	24.00	23.67	36.00	35.48	24.00	23.70	2.40	19.0	…	12.00	26.4
M30 × 3.5	30.00	29.67	45.00	44.42	30.00	29.67	3.00	22.0	…	15.00	33.4
M36 × 4	36.00	35.61	54.00	53.37	36.00	35.64	3.60	27.0	…	18.00	39.4
M42 × 4.5	42.00	41.61	63.00	62.31	42.00	41.61	4.20	32.0	…	21.00	45.6
M48 × 5	48.00	47.61	72.00	71.27	48.00	47.58	4.80	36.0	…	24.00	52.6

Copyright 2004, Industrial Press, Inc., New York, NY

[a] See also Table 25.
[b] The M14 × 2 size is not recommended for use in new designs.
All dimensions are in millimeters
L_G is grip length and L_B is body length (see Table 14). For length of complete thread, see Table 14.
For additional manufacturing and acceptance specifications, see ANSI/ASME B18.3.1M-1986.

Table 25. American National Standard Hexagon and Spline Sockets for Socket Head Cap Screws—Metric Series *ANSI/ASME B18.3.1M-1986*



METRIC HEXAGON SOCKETS



METRIC SPLINE SOCKET

See Table 24

See Table 24

Nominal Hexagon Socket Size	Socket Width Across Flats, *J*		Socket Width Across Corners, *C*	Nominal Hexagon Socket Size	Socket Width Across Flats, *J*		Socket Width Across Corners, *C*
Metric Hexagon Sockets							
	Max	Min	Min		Max	Min	Min
1.5	1.545	1.520	1.73	12	12.146	12.032	13.80
2	2.045	2.020	2.30	14	14.159	14.032	16.09
2.5	2.560	2.520	2.87	17	17.216	17.050	19.56
3	3.071	3.020	3.44	19	19.243	19.065	21.87
4	4.084	4.020	4.58	22	22.319	22.065	25.31
5	5.084	5.020	5.72	24	24.319	24.065	27.60
6	6.095	6.020	6.86	27	27.319	27.065	31.04
8	8.115	8.025	9.15	32	32.461	32.080	36.80
10	10.127	10.025	11.50	36	36.461	36.080	41.38

Metric Spline Sockets[a]						
Nominal Spline Socket Size	Socket Major Diameter, *M*		Socket Minor Diameter, *N*		Width of Tooth, *P*	
	Max	Min	Max	Min	Max	Min
1.829	1.8796	1.8542	1.6256	1.6002	0.4064	0.3810
2.438	2.4892	2.4638	2.0828	2.0320	0.5588	0.5334
2.819	2.9210	2.8702	2.4892	2.4384	0.6350	0.5842
3.378	3.4798	3.4290	2.9972	2.9464	0.7620	0.7112
4.648	4.7752	4.7244	4.1402	4.0894	0.9906	0.9398
5.486	5.6134	5.5626	4.8260	4.7752	1.2700	1.2192
7.391	7.5692	7.5184	6.4516	6.4008	1.7272	2.6764

[a] The tabulated dimensions represent direct metric conversions of the equivalent inch size spline sockets shown in American National Standard Socket Cap, Shoulder and Set Screws — Inch Series ANSI B18.3. Therefore, the spline keys and bits shown therein are applicable for wrenching the corresponding size metric spline sockets.

Metric Nuts

The American National Standards covering metric nuts have been established in cooperation with the Department of Defense in such a way that they could be used by the Government for procurement purposes. Extensive information concerning these nuts is given in the following text and tables, but for more complete manufacturing and acceptance specifications, reference should be made to the respective Standards, which may be obtained by

Copyright 2004, Industrial Press, Inc., New York, NY

non-governmental agencies from the American National Standards Institute, 25 West 43rd Street, New York, N.Y. 10036. Manufacturers should be consulted concerning items and sizes which are in stock production.

Comparison with ISO Standards.— American National Standards for metric nuts have been coordinated to the extent possible with comparable ISO Standards or proposed Standards, thus: ANSI B18.2.4.1M Metric Hex Nuts, Style 1 with ISO 4032; B18.2.4.2M Metric Hex Nuts, Style 2 with ISO 4033; B18.2.4.4M Metric Hex Flange Nuts with ISO 4161; B18.2.4.5M Metric Hex Jam Nuts with ISO 4035; and B18.2.4.3M Metric Slotted Hex Nuts, B18.2.4.6M Metric Heavy Hex Nuts in sizes M12 through M36, and B18.16.3M Prevailing-Torque Type Steel Metric Hex Nuts and Hex Flange Nuts with comparable draft ISO Standards. The dimensional differences between each ANSI Standard and the comparable ISO Standard or draft Standard are very few, relatively minor, and none will affect the interchangeability of nuts manufactured to the requirements of either.

At its meeting in Varna, May 1977, ISO/TC2 studied several technical reports analyzing design considerations influencing determination of the best series of widths across flats for hex bolts, screws, and nuts. A primary technical objective was to achieve a logical ratio between under head (nut) bearing surface area (which determines the magnitude of compressive stress on the bolted members) and the tensile stress area of the screw thread (which governs the clamping force that can be developed by tightening the fastener). The series of widths across flats in the ANSI Standards agree with those which were selected by ISO/TC2 to be ISO Standards.

One exception for width across flats of metric hex nuts, styles 1 and 2, metric slotted hex nuts, metric hex jam nuts, and prevailing-torque metric hex nuts is the M10 size. These nuts in M10 size are currently being produced in the United States with a width across flats of 15 mm. This width, however, is not an ISO Standard. Unless these M10 nuts with width across flats of 15 mm are specifically ordered, the M10 size with 16 mm width across flats will be furnished.

In ANSI Standards for metric nuts, letter symbols designating dimensional characteristics are in accord with those used in ISO Standards, except capitals have been used for data processing convenience instead of lower case letters used in ISO Standards.

Metric Nut Tops and Bearing Surfaces.— Metric hex nuts, styles 1 and 2, slotted hex nuts, and hex jam nuts are double chamfered in sizes M16 and smaller and in sizes M20 and larger may either be double chamfered or have a washer-faced bearing surface and a chamfered top at the option of the manufacturer. Metric heavy hex nuts are optional either way in all sizes. Metric hex flange nuts have a flange bearing surface and a chamfered top and prevailing-torque type metric hex nuts have a chamfered bearing surface. Prevailing-torque type metrix hex flange nuts have a flange bearing surface. All types of metric nuts have the tapped hole countersunk on the bearing face and metric slotted hex nuts, hex flange nuts, and prevailing-torque type hex nuts and hex flange nuts may be countersunk on the top face.

Materials and Mechanical Properties.— Nonheat-treated carbon steel metric hex nuts, style 1 and slotted hex nuts conform to material and property class requirements specified for property class 5 nuts; hex nuts, style 2 and hex flange nuts to property class 9 nuts; hex jam nuts to property class 04 nuts, and nonheat-treated carbon and alloy steel heavy hex nuts to property classes 5, 9, 8S, or 8S3 nuts; all as covered in ASTM A563M. Carbon steel metric hex nuts, style 1 and slotted hex nuts that have specified heat treatment conform to material and property class requirements specified for property class 10 nuts; hex nuts, style 2 to property class 12 nuts; hex jam nuts to property class 05 nuts; hex flange nuts to property classes 10 and 12 nuts; and carbon or alloy steel heavy hex nuts to property classes 10S, 10S3, or 12 nuts, all as covered in ASTM A563M. Carbon steel prevailing-torque type hex nuts and hex flange nuts conform to mechanical and property class requirements as given in ANSI B18.16.1M.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 26. American National Standard Metric Hex Nuts, Styles 1 and 2
ANSI/ASME B18.2.4.1M and B18.2.4.2M-1979 (R1995)



Nominal Nut Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Thickness, *M*		Bearing Face Dia., D_w	Washer Face Thickness, *C*	
	Max	Min	Max	Min	Max	Min	Min	Max	Min
Metric Hex Nuts — Style 1									
M1.6 × 0.35	3.20	3.02	3.70	3.41	1.30	1.05	2.3	…	…
M2 × 0.4	4.00	3.82	4.62	4.32	1.60	1.35	3.1	…	…
M2.5 × 0.45	5.00	4.82	5.77	5.45	2.00	1.75	4.1	…	…
M3 × 0.5	5.50	5.32	6.35	6.01	2.40	2.15	4.6	…	…
M3.5 × 0.6	6.00	5.82	6.93	6.58	2.80	2.55	5.1	…	…
M4 × 0.7	7.00	6.78	8.08	7.66	3.20	2.90	6.0	…	…
M5 × 0.8	8.00	7.78	9.24	8.79	4.70	4.40	7.0	…	…
M6 × 1	10.00	9.78	11.55	11.05	5.20	4.90	8.9	…	…
M8 × 1.25	13.00	12.73	15.01	14.38	6.80	6.44	11.6	…	…
[a]M10 × 1.5	15.00	14.73	17.32	16.64	9.1	8.7	13.6	0.6	0.3
M10 × 1.5	16.00	15.73	18.48	17.77	8.40	8.04	14.6	…	…
M12 × 1.75	18.00	17.73	20.78	20.03	10.80	10.37	16.6	…	…
M14 × 2	21.00	20.67	24.25	23.36	12.80	12.10	19.4	…	…
M16 × 2	24.00	23.67	27.71	26.75	14.80	14.10	22.4	…	…
M20 × 2.5	30.00	29.16	34.64	32.95	18.00	16.90	27.9	0.8	0.4
M24 × 3	36.00	35.00	41.57	39.55	21.50	20.20	32.5	0.8	0.4
M30 × 3.5	46.00	45.00	53.12	50.85	25.60	24.30	42.5	0.8	0.4
M36 × 4	55.00	53.80	63.51	60.79	31.00	29.40	50.8	0.8	0.4
Metric Hex Nuts — Style 2									
M3 × 0.5	5.50	5.32	6.35	6.01	2.90	2.65	4.6	…	…
M3.5 × 0.6	6.00	5.82	6.93	6.58	3.30	3.00	5.1	…	…
M4 × 0.7	7.00	6.78	8.08	7.66	3.80	3.50	5.9	…	…
M5 × 0.8	8.00	7.78	9.24	8.79	5.10	4.80	6.9	…	…
M6 × 1	10.00	9.78	11.55	11.05	5.70	5.40	8.9	…	…
M8 × 1.25	13.00	12.73	15.01	14.38	7.50	7.14	11.6	…	…
[a]M10 × 1.5	15.00	14.73	17.32	16.64	10.0	9.6	13.6	0.6	0.3
M10 × 1.5	16.00	15.73	18.48	17.77	9.30	8.94	14.6	…	…
M12 × 1.75	18.00	17.73	20.78	20.03	12.00	11.57	16.6	…	…
M14 × 2	21.00	20.67	24.25	23.35	14.10	13.40	19.6	…	…
M16 × 2	24.00	23.67	27.71	26.75	16.40	15.70	22.5	…	…
M20 × 2.5	30.00	29.16	34.64	32.95	20.30	19.00	27.7	0.8	0.4
M24 × 3	36.00	35.00	41.57	39.55	23.90	22.60	33.2	0.8	0.4
M30 × 3.5	46.00	45.00	53.12	50.85	28.60	27.30	42.7	0.8	0.4
M36 × 4	55.00	53.80	63.51	60.79	34.70	33.10	51.1	0.8	0.4

[a] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 hex nuts with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 27. American National Standard Metric Slotted Hex Nuts
ANSI B18.2.4.4M-1982 (R1999)



Nominal Nut Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Thickness, *M*		Bearing Face Dia., D_w	Unslotted Thickness, *F*		Width of Slot, *N*		Washer Face Thickness *C*	
	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max	Min	Max	Min
M5 × 0.8	8.00	7.78	9.24	8.79	5.10	4.80	6.9	3.2	2.9	2.0	1.4	…	…
M6 × 1	10.00	9.78	11.55	11.05	5.70	5.40	8.9	3.5	3.2	2.4	1.8	…	…
M8 × 1.25	13.00	12.73	15.01	14.38	7.50	7.14	11.6	4.4	4.1	2.9	2.3	…	…
[a]M10 × 1.5	15.00	14.73	17.32	16.64	10.0	9.6	13.6	5.7	5.4	3.4	2.8	0.6	0.3
M10 × 1.5	16.00	15.73	18.48	17.77	9.30	8.94	14.6	5.2	4.9	3.4	2.8	…	…
M12 × 1.75	18.00	17.73	20.78	20.03	12.00	11.57	16.6	7.3	6.9	4.0	3.2	…	…
M14 × 2	21.00	20.67	24.25	23.35	14.10	13.40	19.6	8.6	8.0	4.3	3.5	…	…
M16 × 2	24.00	23.67	27.71	26.75	16.40	15.70	22.5	9.9	9.3	5.3	4.5	…	…
M20 × 2.5	30.00	29.16	34.64	32.95	20.30	19.00	27.7	13.3	12.2	5.7	4.5	0.8	0.4
M24 × 3	36.00	35.00	41.57	39.55	23.90	22.60	33.2	15.4	14.3	6.7	5.5	0.8	0.4
M30 × 3.5	46.00	45.00	53.12	50.85	28.60	27.30	42.7	18.1	16.8	8.5	7.0	0.8	0.4
M36 × 4	55.00	53.80	63.51	60.79	34.70	33.10	51.1	23.7	22.4	8.5	7.0	0.8	0.4

[a] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 slotted hex nuts with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

Metric nuts of other materials, such as stainless steel, brass, bronze, and aluminum alloys, have properties as agreed upon by the manufacturer and purchaser. Properties of nuts of several grades of non-ferrous materials are covered in ASTM F467M.

Unless otherwise specified, metric nuts are furnished with a natural (unprocessed) finish, unplated or uncoated.

Metric Nut Thread Series.— Metric nuts have metric coarse threads with class 6H tolerances in accordance with ANSI B1.13M (see *Metric Screw and Bolt Diameter-Length Combinations*Metric Screw Threads in index). For prevailing-torque type metric nuts this condition applies before introduction of the prevailing torque feature. Nuts intended for use with externally threaded fasteners which are plated or coated with a plating or coating thickness (e.g., hot dip galvanized) requiring overtapping of the nut thread to permit assembly, have over-tapped threads in conformance with requirements specified in ASTM A563M.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 28. American National Standard Metric Hex Flange Nuts
ANSI B18.2.4.4M-1982 (R1999)



Nominal Nut Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Flange Dia., D_c	Bearing Circle Dia., D_w	Flange Edge Thickness, *C*	Thickness, *M*		Flange Top Fillet Radius, *R*
	Max	Min	Max	Min	Max	Min	Min	Max	Min	Max
M5 × 0.8	8.00	7.78	9.24	8.79	11.8	9.8	1.0	5.00	4.70	0.3
M6 × 1	10.00	9.78	11.55	11.05	14.2	12.2	1.1	6.00	5.70	0.4
M8 × 1.25	13.00	12.73	15.01	14.38	17.9	15.8	1.2	8.00	7.60	0.5
M10 × 1.5	15.00	14.73	17.32	16.64	21.8	19.6	1.5	10.00	9.60	0.6
M12 × 1.75	18.00	17.73	20.78	20.03	26.0	23.8	1.8	12.00	11.60	0.7
M14 × 2	21.00	20.67	24.25	23.35	29.9	27.6	2.1	14.00	13.30	0.9
M16 × 2	24.00	23.67	27.71	26.75	34.5	31.9	2.4	16.00	15.30	1.0
M20 × 2.5	30.00	29.16	34.64	32.95	42.8	39.9	3.0	20.00	18.90	1.2

All dimensions are in millimeters.

Types of Metric Prevailing-Torque Type Nuts.— There are three basic designs for prevailing-torque type nuts:

1) All-metal, one-piece construction nuts which derive their prevailing-torque characteristics from controlled distortion of the nut thread and/or body.

2) Metal nuts which derive their prevailing-torque characteristics from addition or fusion of a nonmetallic insert, plug. or patch in their threads.

3) Top insert, two-piece construction nuts which derive their prevailing-torque characteristics from an insert, usually a full ring of non-metallic material, located and retained in the nut at its top surface.

The first two designs are designated in Tables 29 and 30 as "all-metal" type and the third design as "top-insert" type.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 29. American National Standard Prevailing-Torque Metric Hex Nuts — Property Classes 5, 9, and 10 *ANSI/ASME B18.16.3M-1998*



Nominal Nut Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Property Classes 5 and 10 Nuts				Property Class 9 Nuts				Property Class		Bearing Face Dia., D_w
					All Metal[a] Type		Top Insert Type		All Metal Type		Top Insert Type		5 and 10 Nuts	9 Nuts	
					Thickness, *M*								Wrenching Height, M_1		
	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Min	Min	Min
M3 × 0.5	5.50	5.32	6.35	6.01	3.10	2.65	4.50	3.90	3.10	2.65	4.50	3.90	1.4	1.4	4.6
M3.5 × 0.6	6.00	5.82	6.93	6.58	3.50	3.00	5.00	4.30	3.50	3.00	5.00	4.30	1.7	1.7	5.1
M4 × 0.7	7.00	6.78	8.08	7.66	4.00	3.50	6.00	5.30	4.00	3.50	6.00	5.30	1.9	1.9	5.9
M5 × 0.8	8.00	7.78	9.24	8.79	5.30	4.80	6.80	6.00	5.30	4.80	7.20	6.40	2.7	2.7	6.9
M6 × 1	10.00	9.78	11.55	11.05	5.90	5.40	8.00	7.20	6.70	5.40	8.50	7.70	3.0	3.0	8.9
M8 × 1.25	13.00	12.73	15.01	14.38	7.10	6.44	9.50	8.50	8.00	7.14	10.20	9.20	3.7	4.3	11.6
[b]M10 × 1.5	15.00	14.73	17.32	16.64	9.70	8.70	12.50	11.50	11.20	9.60	13.50	12.50	5.6	6.2	13.6
M10 × 1.5	16.00	15.73	18.48	17.77	9.00	8.04	11.90	10.90	10.50	8.94	12.80	11.80	4.8	5.6	14.6
M12 × 1.75	18.00	17.73	20.78	20.03	11.60	10.37	14.90	13.90	13.30	11.57	16.10	15.10	6.7	7.7	16.6
M14 × 2	21.00	20.67	24.25	23.35	13.20	12.10	17.00	15.80	15.40	13.40	18.30	17.10	7.8	8.9	19.6
M16 × 2	24.00	23.67	27.71	26.75	15.20	14.10	19.10	17.90	17.90	15.70	20.70	19.50	9.1	10.5	22.5
M20 × 2.5	30.00	29.16	34.64	32.95	19.00	16.90	22.80	21.50	21.80	19.00	25.10	23.80	10.9	12.7	27.7
M24 × 3	36.00	35.00	41.57	39.55	23.00	20.20	27.10	25.60	26.40	22.60	29.50	28.00	13.0	15.1	33.2
M30 × 3.5	46.00	45.00	53.12	50.85	26.90	24.30	32.60	30.60	31.80	27.30	35.60	33.60	15.7	18.2	42.7
M36 × 4	55.00	53.80	63.51	60.79	32.50	29.40	38.90	36.90	38.50	33.10	42.60	40.60	19.0	22.1	51.1

[a] Also includes metal nuts with non-metallic inserts, plugs, or patches in their threads.

[b] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 slotted hex nuts with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 30. American National Standard Prevailing-Torque Metric Hex Flange Nuts *ANSI B18.16.3M-1998*



Nominal Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Thickness, *M* (All Nut Property Classes) All Metal Type[a]		Thickness, *M* (All Nut Property Classes) Top Insert Type		Flange Dia., D_c	Bearing Circle Dia., D_w	Flange Edge Thickness, *C*	Flange Top Fillet Radius, *R*
	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Min	Max
M6 × 1	10.00	9.78	11.55	11.05	7.30	5.70	8.80	8.00	14.2	12.2	1.1	0.4
M8 × 1.25	13.00	12.73	15.01	14.38	9.40	7.60	10.70	9.70	17.9	15.8	1.2	0.5
M10 × 1.5	15.00	14.73	17.32	16.64	11.40	9.60	13.50	12.50	21.8	19.6	1.5	0.6
M12 × 1.75	18.00	17.73	20.78	20.03	13.80	11.60	16.10	15.10	26.0	23.8	1.8	0.7
M14 × 2	21.00	20.67	24.25	23.35	15.90	13.30	18.20	17.00	29.9	27.6	2.1	0.9
M16 × 2	24.00	23.67	27.71	26.75	18.30	15.30	20.30	19.10	34.5	31.9	2.4	1.0
M20 × 2.5	30.00	29.16	34.64	32.95	22.40	18.90	24.80	23.50	42.8	39.9	3.0	1.2

[a] Also includes metal nuts with nonmetallic inserts, plugs, or patches in their threads.

All dimensions are in millimeters.

Metric Nut Identification Symbols.— Carbon steel hex nuts, styles 1 and 2, hex flange nuts, and carbon and alloy steel heavy hex nuts are marked to identify the property class and manufacturer in accordance with requirements specified in ASTM A563M. The aforementioned nuts when made of other materials, as well as slotted hex nuts and hex jam nuts, are marked to identify the property class and manufacturer as agreed upon by manufacturer and purchaser. Carbon steel prevailing-torque type hex nuts and hex flange nuts are marked to identify property class and manufacturer as specified in ANSI B18.16.1M. Prevailing-torque type nuts of other materials are identified as agreed upon by the manufacturer and purchaser.

Metric Nut Designation.— Metric nuts are designated by the following data, preferably in the sequence shown: product name, nominal diameter and thread pitch, steel property class or material identification, and protective coating, if required. (Note: It is common practice in ISO Standards to omit thread pitch from the product designation when the nut threads are the metric coarse thread series, e.g., M10 stands for M10 × 1.5).

Example: Hex nut, style 1, M10 × 1.5, ASTM A563M class 10, zinc plated
Heavy hex nut, M20 × 2.5, silicon bronze, ASTM F467, grade 651
Slotted hex nut, M20, ASTM A563M class 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 31. American National Standard Metric Hex Jam Nuts and Heavy Hex Nuts
ANSI B18.2.4.5M **and** *B18.2.4.6M-1979 (R1998)*



Nominal Nut Dia. and Thread Pitch	Width Across Flats, *S*		Width Across Corners, *E*		Thickness, *M*		Bearing Face Dia., D_w	Washer Face Thickness, *C*	
	Max	Min	Max	Min	Max	Min	Min	Max	Min
Metric Hex Jam Nuts									
M5 × 0.8	8.00	7.78	9.24	8.79	2.70	2.45	6.9	…	…
M6 × 1	10.00	9.78	11.55	11.05	3.20	2.90	8.9	…	…
M8 × 1.25	13.00	12.73	15.01	14.38	4.00	3.70	11.6	…	…
[a]M10 × 1.5	15.00	14.73	17.32	16.64	5.00	4.70	13.6	…	…
M10 × 1.5	16.00	15.73	18.48	17.77	5.00	4.70	14.6	…	…
M12 × 1.75	18.00	17.73	20.78	20.03	6.00	5.70	16.6	…	…
M14 × 2	21.00	20.67	24.25	23.35	7.00	6.42	19.6	…	…
M16 × 2	24.00	23.67	27.71	26.75	8.00	7.42	22.5	…	…
M20 × 2.5	30.00	29.16	34.64	32.95	10.00	9.10	27.7	0.8	0.4
M24 × 3	36.00	35.00	41.57	39.55	12.00	10.90	33.2	0.8	0.4
M30 × 3.5	46.00	45.00	53.12	50.85	15.00	13.90	42.7	0.8	0.4
M36 × 4	55.00	53.80	63.51	60.79	18.00	16.90	51.1	0.8	0.4
Metric Heavy Hex Nuts									
M12 × 1.75	21.00	20.16	24.25	22.78	12.3	11.9	19.2	0.8	0.4
M14 × 2	24.00	23.16	27.71	26.17	14.3	13.6	22.0	0.8	0.4
M16 × 2	27.00	26.16	31.18	29.56	17.1	16.4	24.9	0.8	0.4
M20 × 2.5	34.00	33.00	39.26	37.29	20.7	19.4	31.4	0.8	0.4
M22 × 2.5	36.00	35.00	41.57	39.55	23.6	22.3	33.3	0.8	0.4
M24 × 3	41.00	40.00	47.34	45.20	24.2	22.9	38.0	0.8	0.4
M27 × 3	46.00	45.00	53.12	50.85	27.6	26.3	42.8	0.8	0.4
M30 × 3.5	50.00	49.00	57.74	55.37	30.7	29.1	46.6	0.8	0.4
M36 × 4	60.00	58.80	69.28	66.44	36.6	35.0	55.9	0.8	0.4
M42 × 4.5	70.00	67.90	80.83	77.41	42.0	40.4	64.5	1.0	0.5
M48 × 5	80.00	77.60	92.38	88.46	48.0	46.4	73.7	1.0	0.5
M56 × 5.5	90.00	87.20	103.92	99.41	56.0	54.1	82.8	1.0	0.5
M64 × 6	100.00	96.80	115.47	110.35	64.0	62.1	92.0	1.0	0.5
M72 × 6	110.00	106.40	127.02	121.30	72.0	70.1	101.1	1.2	0.6
M80 × 6	120.00	116.00	138.56	132.24	80.0	78.1	110.2	1.2	0.6
M90 × 6	135.00	130.50	155.88	148.77	90.0	87.8	124.0	1.2	0.6
M100 × 6	150.00	145.00	173.21	165.30	100.0	97.8	137.8	1.2	0.6

[a] This size with width across flats of 15 mm is not standard. Unless specifically ordered, M10 hex jam nuts with 16 mm width across flats will be furnished.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Metric Washers

Metric Plain Washers.— American National Standard ANSI B18.22M-1981 (R1990) covers general specifications and dimensions for flat, round-hole washers, both soft (as fabricated) and hardened, intended for use in general-purpose applications. Dimensions are given in the following table. Manufacturers should be consulted for current information on stock sizes.

Comparison with ISO Standards.— The washers covered by this ANSI Standard are nominally similar to those covered in various ISO documents. Outside diameters were selected, where possible, from ISO/TC2/WG6/N47 "General Plan for Plain Washers for Metric Bolts, Screws, and Nuts." The thicknesses given in the ANSI Standard are similar to the nominal ISO thicknesses, however the tolerances differ. Inside diameters also differ.

ISO metric washers are currently covered in ISO 887, "Plain Washers for Metric Bolts, Screws, and Nuts – General Plan."

Types of Metric Plain Washers.— Soft (as fabricated) washers are generally available in nominal sizes 1.6 mm through 36 mm in a variety of materials. They are normally used in low-strength applications to distribute bearing load, to provide a uniform bearing surface, and to prevent marring of the work surface.

Hardened steel washers are normally available in sizes 6 mm through 36 mm in the narrow and regular series. They are intended primarily for use in high-strength joints to minimize embedment, to provide a uniform bearing surface, and to bridge large clearance holes and slots.

Metric Plain Washer Materials and Finish.— Soft (as fabricated) washers are made of nonhardened steel unless otherwise specified by the purchaser. Hardened washers are made of through-hardened steel tempered to a hardness of 38 to 45 Rockwell C.

Unless otherwise specified, washers are furnished with a natural (as fabricated) finish, unplated or uncoated with a light film of oil or rust inhibitor.

Metric Plain Washer Designation.— When specifying metric plain washers, the designation should include the following data in the sequence shown: description, nominal size, series, material type, and finish, if required.

Example: Plain washer, 6 mm, narrow, soft, steel, zinc plated
Plain washer, 10 mm, regular, hardened steel.



Copyright 2004, Industrial Press, Inc., New York, NY

Table 32. American National Standard Metric Plain Washers
ANSI B18.22M-1981, R1990

Nominal Washer Size[a]	Washer Series	Inside Diameter, *A*		Outside Diameter, *B*		Thickness, *C*	
		Max	Min	Max	Min	Max	Min
1.6	Narrow	2.09	1.95	4.00	3.70	0.70	0.50
	Regular	2.09	1.95	5.00	4.70	0.70	0.50
	Wide	2.09	1.95	6.00	5.70	0.90	0.60
2	Narrow	2.64	2.50	5.00	4.70	0.90	0.60
	Regular	2.64	2.50	6.00	5.70	0.90	0.60
	Wide	2.64	2.50	8.00	7.64	0.90	0.60
2.5	Narrow	3.14	3.00	6.00	5.70	0.90	0.60
	Regular	3.14	3.00	8.00	7.64	0.90	0.60
	Wide	3.14	3.00	10.00	9.64	1.20	0.80
3	Narrow	3.68	3.50	7.00	6.64	0.90	0.60
	Regular	3.68	3.50	10.00	9.64	1.20	0.80
	Wide	3.68	3.50	12.00	11.57	1.40	1.00
3.5	Narrow	4.18	4.00	9.00	8.64	1.20	0.80
	Regular	4.18	4.00	10.00	9.64	1.40	1.00
	Wide	4.18	4.00	15.00	14.57	1.75	1.20
4	Narrow	4.88	4.70	10.00	9.64	1.20	0.80
	Regular	4.88	4.70	12.00	11.57	1.40	1.00
	Wide	4.88	4.70	16.00	15.57	2.30	1.60
5	Narrow	5.78	5.50	11.00	10.57	1.40	1.00
	Regular	5.78	5.50	15.00	14.57	1.75	1.20
	Wide	5.78	5.50	20.00	19.48	2.30	1.60
6	Narrow	6.87	6.65	13.00	12.57	1.75	1.20
	Regular	6.87	6.65	18.80	18.37	1.75	1.20
	Wide	6.87	6.65	25.40	24.88	2.30	1.60
8	Narrow	9.12	8.90	18.80[b]	18.37[b]	2.30	1.60
	Regular	9.12	8.90	25.40[b]	24.48[b]	2.30	1.60
	Wide	9.12	8.90	32.00	31.38	2.80	2.00
10	Narrow	11.12	10.85	20.00	19.48	2.30	1.60
	Regular	11.12	10.85	28.00	27.48	2.80	2.00
	Wide	11.12	10.85	39.00	38.38	3.50	2.50
12	Narrow	13.57	13.30	25.40	24.88	2.80	2.00
	Regular	13.57	13.30	34.00	33.38	3.50	2.50
	Wide	13.57	13.30	44.00	43.38	3.50	2.50
14	Narrow	15.52	15.25	28.00	27.48	2.80	2.00
	Regular	15.52	15.25	39.00	38.38	3.50	2.50
	Wide	15.52	15.25	50.00	49.38	4.00	3.00
16	Narrow	17.52	17.25	32.00	31.38	3.50	2.50
	Regular	17.52	17.25	44.00	43.38	4.00	3.00
	Wide	17.52	17.25	56.00	54.80	4.60	3.50
20	Narrow	22.32	21.80	39.00	38.38	4.00	3.00
	Regular	22.32	21.80	50.00	49.38	4.60	3.50
	Wide	22.32	21.80	66.00	64.80	5.10	4.00
24	Narrow	26.12	25.60	44.00	43.38	4.60	3.50
	Regular	26.12	25.60	56.00	54.80	5.10	4.00
	Wide	26.12	25.60	72.00	70.80	5.60	4.50
30	Narrow	33.02	32.40	56.00	54.80	5.10	4.00
	Regular	33.02	32.40	72.00	70.80	5.60	4.50
	Wide	33.02	32.40	90.00	88.60	6.40	5.00
36	Narrow	38.92	38.30	66.00	64.80	5.60	4.50
	Regular	38.92	38.30	90.00	88.60	6.40	5.00
	Wide	38.92	38.30	110.00	108.60	8.50	7.00

[a] Nominal washer sizes are intended for use with comparable screw and bolt sizes.

[b] The 18.80/18.37 and 25.40/24.48 mm outside diameters avoid washers which could be used in coin-operated devices.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

BRITISH FASTENERS

British Standard Square and Hexagon Bolts, Screws and Nuts.— Important dimensions of precision hexagon bolts, screws and nuts (BSW and BSF threads) as covered by British Standard 1083:1965 are given in Tables 1 and 2. The use of fasteners in this standard will decrease as fasteners having Unified inch and ISO metric threads come into increasing use.

Dimensions of Unified precision hexagon bolts, screws and nuts (UNC and UNF threads) are given in BS 1768:1963 (obsolescent); of Unified black hexagon bolts, screws and nuts (UNC and UNF threads) in BS 1769:1951 (obsolescent); and of Unified black square and hexagon bolts, screws and nuts (UNC and UNF threads) in BS 2708:1956 (withdrawn). Unified nominal and basic dimensions in these British Standards are the same as the comparable dimensions in the American Standards, but the tolerances applied to these basic dimensions may differ because of rounding-off practices and other factors. For Unified dimensions of square and hexagon bolts and nuts as given in ANSI/ASME B18.2.1-1996 and ANSI/ASME B18.2.2-1987 (R1999) see Tables 1 through 4 starting on page 1514, and 7 to 10 starting on page 1519.

ISO metric precision hexagon bolts, screws and nuts are specified in the British Standard BS 3692:1967 (obsolescent) (see *British Standard ISO Metric Precision Hexagon Bolts, Screws and Nuts* starting on page 1578), and ISO metric black hexagon bolts, screws and nuts are covered by British Standard BS 4190:1967 (obsolescent).

See the section *MACHINE SCREWS AND NUTS* starting on page 1587 for information on British Standard metric, Unified, Whitworth, and BSF machine screws and nuts.

British Standard Screwed Studs.— General purpose screwed studs are covered in British Standard 2693: Part 1:1956. The aim in this standard is to provide for a stud having tolerances which would not render it expensive to manufacture and which could be used in association with standard tapped holes for most purposes. Provision has been made for the use of both Unified Fine threads, Unified Coarse threads, British Standard Fine threads, and British Standard Whitworth threads as shown in the table on page 1573.

Designations: The *metal end* of the stud is the end which is screwed into the component. The *nut end* is the end of the screw of the stud which is not screwed into the component. The *plain portion* of the stud is the unthreaded length.

Recommended Fitting Practices for Metal End of Stud: It is recommended that holes tapped to Class 3B limits (see Table 3 starting on page 1736) in accordance with B.S. 1580 "Unified Screw Threads" or to Close Class limits in accordance with B.S. 84 "Screw Threads of Whitworth Form" as appropriate, be used in association with the metal end of the stud specified in this standard. Where fits are not critical, however, holes may be tapped to Class 2B limits (see table on page 1736) in accordance with B.S. 1580 or Normal Class limits in accordance with B.S. 84.

It is recommended that the B.A. stud specified in this standard be associated with holes tapped to the limits specified for nuts in B.S. 93, 1919 edition. Where fits for these studs are not critical, holes may be tapped to limits specified for nuts in the current edition of B.S. 93.

In general, it will be found that the amount of oversize specified for the studs will produce a satisfactory fit in conjunction with the standard tapping as above. Even when interference is not present, locking will take place on the thread runout which has been carefully controlled for this purpose. Where it is considered essential to assure a true interference fit, higher grade studs should be used. It is recommended that standard studs be used even under special conditions where selective assembly may be necessary.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Whitworth (BSW) and Fine (BSF) Precision Hexagon Bolts, Screws, and Nuts



Hexagon Head Bolt, Washer Faced



Hexagon Head Screw, Washer Faced



Alternative Full-Bearing Head



Rounded End Rolled Thread End

Alternative Hexagon Ordinary Nuts



Hexagon Nut, Full



Ordinary Bearing



Double Chamfered



Washer Faced



Hexagon Lock-Nut



Enlarged View of Nut Countersink

Alternative Hexagon Slotted Nuts





Hexagon Slotted Nut, Full Bearing



Double Chamfered



Washer Faced

Alternate Hexagon Castle Nuts





Hexagon Castle Nut, Full Bearing



Double Chamfered



Washer Faced

For dimensions, see Tables 1 and 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. British Standard Whitworth (BSW) and Fine (BSF) Precision Hexagon Slotted and Castle Nuts *BS 1083:1965 (obsolescent)*

Nominal Size *D*	Number of Threads per Inch		Bolts, Screws, and Nuts					Bolts and Screws						Nuts			
			Width			Diameter of Washer Face *G*		Radius Under Head *R*		Diameter of Unthreaded Portion of Shank *B*		Thickness		Thickness			
			Across Flats *A*		Across Corners *C*							Head *F*		Ordinary *E*		Lock *H*	
	BSW	BSF	Max.	Min.[a]	Max.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
1/4	20	26	0.445	0.438	0.51	0.428	0.418	0.025	0.015	0.2500	0.2465	0.176	0.166	0.200	0.190	0.185	0.180
5/16	18	22	0.525	0.518	0.61	0.508	0.498	0.025	0.015	0.3125	0.3090	0.218	0.208	0.250	0.240	0.210	0.200
3/8	16	20	0.600	0.592	0.69	0.582	0.572	0.025	0.015	0.3750	0.3715	0.260	0.250	0.312	0.302	0.260	0.250
7/16	14	18	0.710	0.702	0.82	0.690	0.680	0.025	0.015	0.4375	0.4335	0.302	0.292	0.375	0.365	0.275	0.265
1/2	12	16	0.820	0.812	0.95	0.800	0.790	0.025	0.015	0.5000	0.4960	0.343	0.333	0.437	0.427	0.300	0.290
9/16	12	16	0.920	0.912	1.06	0.900	0.890	0.045	0.020	0.5625	0.5585	0.375	0.365	0.500	0.490	0.333	0.323
5/8	11	14	1.010	1.000	1.17	0.985	0.975	0.045	0.020	0.6250	0.6190	0.417	0.407	0.562	0.552	0.375	0.365
3/4	10	12	1.200	1.190	1.39	1.175	1.165	0.045	0.020	0.7500	0.7440	0.500	0.480	0.687	0.677	0.458	0.448
7/8	9	11	1.300	1.288	1.50	1.273	1.263	0.065	0.040	0.8750	0.8670	0.583	0.563	0.750	0.740	0.500	0.490
1	8	10	1.480	1.468	1.71	1.453	1.443	0.095	0.060	1.0000	0.9920	0.666	0.636	0.875	0.865	0.583	0.573
1 1/8	7	9	1.670	1.640	1.93	1.620	1.610	0.095	0.060	1.1250	1.1170	0.750	0.710	1.000	0.990	0.666	0.656
1 1/4	7	9	1.860	1.815	2.15	1.795	1.785	0.095	0.060	1.2500	1.2420	0.830	0.790	1.125	1.105	0.750	0.730
1 3/8[b]	…	8	2.050	2.005	2.37	1.985	1.975	0.095	0.060	1.3750	1.3650	0.920	0.880	1.250	1.230	0.833	0.813
1 1/2	6	8	2.220	2.175	2.56	2.155	2.145	0.095	0.060	1.5000	1.4900	1.000	0.960	1.375	1.355	0.916	0.896
1 3/4	5	7	2.580	2.520	2.98	2.495	2.485	0.095	0.060	1.7500	1.7400	1.170	1.110	1.625	1.605	1.083	1.063
2	4.5	7	2.760	2.700	3.19	2.675	2.665	0.095	0.060	2.0000	1.9900	1.330	1.270	1.750	1.730	1.166	1.146

[a] When bolts from 1/4 to 1 inch are hot forged, the tolerance on the width across flats shall be two and a half times the tolerance shown in the table and shall be unilaterally minus from maximum size. For dimensional notation, see diagram on page 1571.

[b] Noted standard with BSW thread.

All dimensions in inches except where otherwise noted.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. British Standard Whitworth (BSW) and Fine (BSF) Precision Hexagon Slotted and Castle Nuts *BS 1083:1965 (obsolescent)*

Nominal Size *D*	Number of Threads per Inch		Slotted Nuts				Castle Nuts						Slotted and Castle Nuts		
			Thickness *P*		Lower Face to Bottom of Slot *H*		Total Thickness *J*		Lower Face to Bottom of Slot *K*		Castellated Portion		Slots		
											Diameter *L*		Width *M*		Depth *N*
	BSW	BSF	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Approx.
1/4	20	26	0.200	0.190	0.170	0.160	0.290	0.280	0.200	0.190	0.430	0.425	0.100	0.090	0.090
5/16	18	22	0.250	0.240	0.190	0.180	0.340	0.330	0.250	0.240	0.510	0.500	0.100	0.090	0.090
3/8	16	20	0.312	0.302	0.222	0.212	0.402	0.392	0.312	0.302	0.585	0.575	0.100	0.090	0.090
7/16	14	18	0.375	0.365	0.235	0.225	0.515	0.505	0.375	0.365	0.695	0.685	0.135	0.125	0.140
1/2	12	16	0.437	0.427	0.297	0.287	0.577	0.567	0.437	0.427	0.805	0.795	0.135	0.125	0.140
9/16	12	16	0.500	0.490	0.313	0.303	0.687	0.677	0.500	0.490	0.905	0.895	0.175	0.165	0.187
5/8	11	14	0.562	0.552	0.375	0.365	0.749	0.739	0.562	0.552	0.995	0.985	0.175	0.165	0.187
3/4	10	12	0.687	0.677	0.453	0.443	0.921	0.911	0.687	0.677	1.185	1.165	0.218	0.208	0.234
7/8	9	11	0.750	0.740	0.516	0.506	0.984	0.974	0.750	0.740	1.285	1.265	0.218	0.208	0.234
1	8	10	0.875	0.865	0.595	0.585	1.155	1.145	0.875	0.865	1.465	1.445	0.260	0.250	0.280
1 1/8	7	9	1.000	0.990	0.720	0.710	1.280	1.270	1.000	0.990	1.655	1.635	0.260	0.250	0.280
1 1/4	7	9	1.125	1.105	0.797	0.777	1.453	1.433	1.125	1.105	1.845	1.825	0.300	0.290	0.328
1 3/8[a]	…	8	1.250	1.230	0.922	0.902	1.578	1.558	1.250	1.230	2.035	2.015	0.300	0.290	0.328
1 1/2	6	8	1.375	1.355	1.047	1.027	1.703	1.683	1.375	1.355	2.200	2.180	0.300	0.290	0.328
1 3/4	5	7	1.625	1.605	1.250	1.230	2.000	1.980	1.625	1.605	2.555	2.535	0.343	0.333	0.375
2	4.5	7	1.750	1.730	1.282	1.262	2.218	2.198	1.750	1.730	2.735	2.715	0.426	0.416	0.468

[a] Not standard with BSW thread. For widths across flats, widths across corners, and diameter of washer face see Table 1. For dimensional notation, see diagram on page 1571.

All dimensions in inches except where otherwise noted.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. British Standard ISO Metric Precision Hexagon Bolts, Screws and Nuts
BS 3692:1967 (obsolescent)



Washer-Faced Hexagon Head Bolt



Washer-Faced Hexagon Head Screw



Full Bearing Head (Alternative Permissible on Bolts and Screws)



Rounded End



Rolled Thread End

Alternative Types of End Permissible on Bolts and Screws



Normal Thickness Nut



Thin Nut



Enlarged View of Nut Countersink



Slotted Nut (Six Slots) Sizes M4 to M39 Only



Castle Nut (Six Slots) Sizes M12 to M39 Only



Castle Nut (Eight Slots) Sizes M42 to M68 Only

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. British Standard ISO Metric Precision Hexagon Bolts and Screws *BS 3692:1967 (obsolescent)*

Nom.Size and Thread Dia.[a] *d*	Pitch of Thread (Coarse Pitch-Series)	Thread Runout *a*	Dia. of Unthreaded Shank *d*		Width Across Flats *s*		Width Across Corners *e*		Dia. of Washer Face d_l		Depth of Washer Face *c*	Transition Dia.[b] d_a	Radius Under Head[b] *r*		Height of Head *k*		Eccentricity of Head	Eccentricity of Shank and Split Pin Hole to the Thread
		Max.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.		Max.	Max.	Min.	Max.	Min.	Max.	Max.
M1.6	0.35	0.8	1.6	1.46	3.2	3.08	3.7	3.48	…	…	…	2.0	0.2	0.1	1.225	0.975	0.18	0.14
M2	0.4	1.0	2.0	1.86	4.0	3.88	4.6	4.38	…	…	…	2.6	0.3	0.1	1.525	1.275	0.18	0.14
M2.5	0.45	1.0	2.5	2.36	5.0	4.88	5.8	5.51	…	…	…	3.1	0.3	0.1	2.125	1.875	0.18	0.14
M3	0.5	1.2	3.0	2.86	5.5	5.38	6.4	6.08	5.08	4.83	0.1	3.6	0.3	0.1	2.125	1.875	0.18	0.14
M4	0.7	1.6	4.0	3.82	7.0	6.85	8.1	7.74	6.55	6.30	0.1	4.7	0.35	0.2	2.925	2.675	0.22	0.18
M5	0.8	2.0	5.0	4.82	8.0	7.85	9.2	8.87	7.55	7.30	0.2	5.7	0.35	0.2	3.650	3.35	0.22	0.18
M6	1	2.5	6.0	5.82	10.0	9.78	11.5	11.05	9.48	9.23	0.3	6.8	0.4	0.25	4.15	3.85	0.22	0.18
M8	1.25	3.0	8.0	7.78	13.0	12.73	15.0	14.38	12.43	12.18	0.4	9.2	0.6	0.4	5.65	5.35	0.27	0.22
M10	1.5	3.5	10.0	9.78	17.0	16.73	19.6	18.90	16.43	16.18	0.4	11.2	0.6	0.4	7.18	6.82	0.27	0.22
M12	1.75	4.0	12.0	11.73	19.0	18.67	21.9	21.10	18.37	18.12	0.4	14.2	1.1	0.6	8.18	7.82	0.33	0.27
(M14)	2	5.0	14.0	13.73	22.0	21.67	25.4	24.49	21.37	21.12	0.4	16.2	1.1	0.6	9.18	8.82	0.33	0.27
M16	2	5.0	16.0	15.73	24.0	23.67	27.7	26.75	23.27	23.02	0.4	18.2	1.1	0.6	10.18	9.82	0.33	0.27
(M18)	2.5	6.0	18.0	17.73	27.0	26.67	31.2	30.14	26.27	26.02	0.4	20.2	1.1	0.6	12.215	11.785	0.33	0.27
M20	2.5	6.0	20.0	19.67	30.0	29.67	34.6	33.53	29.27	28.80	0.4	22.4	1.2	0.8	13.215	12.785	0.33	0.33
(M22)	2.5	6.0	22.0	21.67	32.0	31.61	36.9	35.72	31.21	30.74	0.4	24.4	1.2	0.8	14.215	13.785	0.39	0.33
M24	3	7.0	24.0	23.67	36.0	35.38	41.6	39.98	34.98	34.51	0.5	26.4	1.2	0.8	15.215	14.785	0.39	0.33
(M27)	3	7.0	27.0	26.67	41.0	40.38	47.3	45.63	39.98	39.36	0.5	30.4	1.7	1.0	17.215	16.785	0.39	0.33
M30	3.5	8.0	30.0	29.67	46.0	45.38	53.1	51.28	44.98	44.36	0.5	33.4	1.7	1.0	19.26	18.74	0.39	0.33
(M33)	3.5	8.0	33.0	32.61	50.0	49.38	57.7	55.80	48.98	48.36	0.5	36.4	1.7	1.0	21.26	20.74	0.39	0.39
M36	4	10.0	36.0	35.61	55.0	54.26	63.5	61.31	53.86	53.24	0.5	39.4	1.7	1.0	23.26	22.74	0.46	0.39
(M39)	4	10.0	39.0	38.61	60.0	59.26	69.3	66.96	58.86	58.24	0.6	42.4	1.7	1.0	25.26	24.74	0.46	0.39
M42	4.5	11.0	42.0	41.61	65.0	64.26	75.1	72.61	63.76	63.04	0.6	45.6	1.8	1.2	26.26	25.74	0.46	0.39
(M45)	4.5	11.0	45.0	44.61	70.0	69.26	80.8	78.26	68.76	68.04	0.6	48.6	1.8	1.2	28.26	27.74	0.46	0.39
M48	5	12.0	48.0	47.61	75.0	74.26	86.6	83.91	73.76	73.04	0.6	52.6	2.3	1.6	30.26	29.74	0.46	0.39
(M52)	5	12.0	52.0	51.54	80.0	79.26	92.4	89.56	…	…	…	56.6	2.3	1.6	33.31	32.69	0.46	0.46
M56	5.5	19.0	56.0	55.54	85.0	84.13	98.1	95.07	…	…	…	63.0	3.5	2.0	35.31	34.69	0.54	0.46
(M60)	5.5	19.0	60.0	59.54	90.0	89.13	103.9	100.72	…	…	…	67.0	3.5	2.0	38.31	37.69	0.54	0.46
M64	6	21.0	64.0	63.54	95.0	94.13	109.7	106.37	…	…	…	71.0	3.5	2.0	40.31	39.69	0.54	0.46
(M68)	6	21.0	68.0	67.54	100.0	99.13	115.5	112.02	…	…	…	75.0	3.5	2.0	43.31	42.69	0.54	0.46

[a] Sizes shown in parentheses are non-preferred.

[b] A true radius is not essential provided that the curve is smooth and lies wholly within the maximum radius, determined from the maximum transitional diameter, and the minimum radius specified.

All dimensions are in millimeters. For illustration of bolts and screws see Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. British Standard ISO Metric Precision Hexagon Nuts and Thin Nuts *BS 3692:1967 (obsolescent)*

Nominal Size and Thread Diameter[a] *d*	Pitch of Thread (Coarse Pitch Series)	Width Across Flats *s*		Width Across Corners *e*		Thickness of Normal Nut *m*		Tolerance on Squareness of Thread to Face of Nut[b]	Eccentricity of Hexagon	Thickness of Thin Nut *t*	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Max.	Min.
M1.6	0.35	3.20	3.08	3.70	3.48	1.30	1.05	0.05	0.14	…	…
M2	0.4	4.00	3.88	4.60	4.38	1.60	1.35	0.06	0.14	…	…
M2.5	0.45	5.00	4.88	5.80	5.51	2.00	1.75	0.08	0.14	…	…
M3	0.5	5.50	5.38	6.40	6.08	2.40	2.15	0.09	0.14	…	…
M4	0.7	7.00	6.85	8.10	7.74	3.20	2.90	0.11	0.18	…	…
M5	0.8	8.00	7.85	9.20	8.87	4.00	3.70	0.13	0.18	…	…
M6	1	10.00	9.78	11.50	11.05	5.00	4.70	0.17	0.18	…	…
M8	1.25	13.00	12.73	15.00	14.38	6.50	6.14	0.22	0.22	5.0	4.70
M10	1.5	17.00	16.73	19.60	18.90	8.00	7.64	0.29	0.22	6.0	5.70
M12	1.75	19.00	18.67	21.90	21.10	10.00	9.64	0.32	0.27	7.0	6.64
(M14)	2	22.00	21.67	25.4	24.49	11.00	10.57	0.37	0.27	8.0	7.64
M16	2	24.00	23.67	27.7	6.75	13.00	12.57	0.41	0.27	8.0	7.64
(M18)	2.5	27.00	26.67	31.20	30.14	15.00	14.57	0.46	0.27	9.0	8.64
M20	2.5	30.00	29.67	34.60	33.53	16.00	15.57	0.51	0.33	9.0	8.64
(M22)	2.5	32.00	31.61	36.90	35.72	18.00	17.57	0.54	0.33	10.0	9.64
M24	3	36.00	35.38	41.60	39.98	19.00	18.48	0.61	0.33	10.0	9.64
(M27)	3	41.00	40.38	47.3	45.63	22.00	21.48	0.70	0.33	12.0	11.57
M30	3.5	46.00	45.38	53.1	51.28	24.00	23.48	0.78	0.33	12.0	11.57
(M33)	3.5	50.00	49.38	57.70	55.80	26.00	25.48	0.85	0.39	14.0	13.57
M36	4	55.00	54.26	63.50	61.31	29.00	28.48	0.94	0.39	14.0	13.57
(M39)	4	60.00	59.26	69.30	66.96	31.00	30.38	1.03	0.39	16.0	15.57
M42	4.5	65.00	64.26	75.10	72.61	34.00	33.38	1.11	0.39	16.0	15.57
(M45)	4.5	70.00	69.26	80.80	78.26	36.00	35.38	1.20	0.39	18.0	17.57
M48	5	75.00	74.26	86.60	83.91	38.00	37.38	1.29	0.39	18.0	17.57
(M52)	5	80.00	79.26	92.40	89.56	42.00	41.38	1.37	0.46	20.0	19.48
M56	5.5	85.00	84.13	98.10	95.07	45.00	44.38	1.46	0.46	…	…
(M60)	5.5	90.00	89.13	103.90	100.72	48.00	47.38	1.55	0.46	…	…
M64	6	95.00	94.13	109.70	106.37	51.00	50.26	1.63	0.46	…	…
(M68)	6	100.00	99.13	115.50	112.02	54.00	53.26	1.72	0.46	…	…

[a] Sizes shown in parentheses are non-preferred.

[b] As measured with the nut squareness gage described in the text and illustrated in Appendix A of the Standard and a feeler gage.

All dimensions are in millimeters. For illustration of hexagon nuts and thin nuts see Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. British Standard ISO Metric Precision Hexagon Slotted Nuts and Castle Nuts *BS 3692:1967 (obsolescent)*

Nominal Size and Thread Diameter[a] *d*	Width Across Flats *s*		Width Across Corners *e*		Diameter d_2		Thickness *h*		Lower Face of Nut to Bottom of Slot *m*		Width of Slot *n*		Radius (0.25 *n*) *r*	Eccentricity of the Slots
	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Min.	Max.
M4	7.00	6.85	8.10	7.74	…	…	5	4.70	3.2	2.90	1.45	1.2	0.3	0.18
M5	8.00	7.85	9.20	8.87	…	…	6	5.70	4.0	3.70	1.65	1.4	0.35	0.18
M6	10.00	9.78	11.50	11.05	…	…	7.5	7.14	5	4.70	2.25	2	0.5	0.18
M8	13.00	12.73	15.00	14.38	…	…	9.5	9.14	6.5	6.14	2.75	2.5	0.625	0.22
M10	17.00	16.73	19.60	18.90	…	…	12	11.57	8	7.64	3.05	2.8	0.70	0.22
M12	19.00	18.67	21.90	21.10	17	16.57	15	14.57	10	9.64	3.80	3.5	0.875	0.27
(M14)	22.00	21.67	25.4	24.49	19	18.48	16	15.57	11	10.57	3.80	3.5	0.875	0.27
M16	24.00	23.67	27.7	26.75	22	21.48	19	18.48	13	12.57	4.80	4.5	1.125	0.27
(M18)	27.00	26.67	31.20	30.14	25	24.48	21	20.48	15	14.57	4.80	4.5	1.125	0.27
M20	30.00	29.67	34.60	33.53	28	27.48	22	21.48	16	15.57	4.80	4.5	1.125	0.33
(M22)	32.00	31.61	36.90	35.72	30	29.48	26	25.48	18	17.57	5.80	5.5	1.375	0.33
M24	36.00	35.38	41.60	39.98	34	33.38	27	26.48	19	18.48	5.80	5.5	1.375	0.33
(M27)	41.00	40.38	47.3	45.63	38	37.38	30	29.48	22	21.48	5.80	5.5	1.375	0.33
M30	46.00	45.38	53.1	51.28	42	41.38	33	32.38	24	23.48	7.36	7	1.75	0.33
(M33)	50.00	49.38	57.70	55.80	46	45.38	35	34.38	26	25.48	7.36	7	1.75	0.39
M36	55.00	54.26	63.50	61.31	50	49.38	38	37.38	29	28.48	7.36	7	1.75	0.39
(M39)	60.00	59.26	69.30	66.96	55	54.26	40	39.38	31	30.38	7.36	7	1.75	0.39
M42	65.00	64.26	75.10	72.61	58	57.26	46	45.38	34	33.38	9.36	9	2.25	0.39
(M45)	70.00	69.26	80.80	78.26	62	61.26	48	47.38	36	35.38	9.36	9	2.25	0.39
M48	75.00	74.26	86.60	83.91	65	64.26	50	49.38	38	37.38	9.36	9	2.25	0.39
(M52)	80.00	79.26	92.40	89.56	70	69.26	54	53.26	42	41.38	9.36	9	2.25	0.46
M56	85.00	84.13	98.10	95.07	75	74.26	57	56.26	45	44.38	9.36	9	2.25	0.46
(M60)	90.00	89.13	103.90	100.72	80	79.26	63	62.26	48	47.38	11.43	11	2.75	0.46
M64	95.00	94.13	109.70	106.37	85	84.13	66	65.26	51	50.26	11.43	11	2.75	0.46
(M68)	100.00	99.13	115.50	112.02	90	89.13	69	68.26	54	53.26	11.43	11	2.75	0.46

[a] Sizes shown in parentheses are non-preferred.

All dimensions are in millimeters. For illustration of hexagon slotted nuts and castle nuts see Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

After several years of use of BS 2693:Part 1:1956 (obsolescent), it was recognized that it would not meet the requirements of all stud users. The thread tolerances specified could result in clearance of interference fits because locking depended on the run-out threads. Thus, some users felt that true interference fits were essential for their needs. As a result, the British Standards Committee has incorporated the Class 5 interference fit threads specified in American Standard ASA B1.12 into the BS 2693:Part 2:1964, "Recommendations for High Grade Studs."

British Standard ISO Metric Precision Hexagon Bolts, Screws and Nuts.— This British Standard BS 3692:1967 (obsolescent) gives the general dimensions and tolerances of precision hexagon bolts, screws and nuts with ISO metric threads in diameters from 1.6 to 68 mm. It is based on the following ISO recommendations and draft recommendations: R 272, R 288, DR 911, DR 947, DR 950, DR 952 and DR 987. Mechanical properties are given only with respect to carbon or alloy steel bolts, screws and nuts, which are not to be used for special applications such as those requiring weldability, corrosion resistance or ability to withstand temperatures above 300°C or below – 50°C. The dimensional requirements of this standard also apply to non-ferrous and stainless steel bolts, screws and nuts.

Finish: Finishes may be dull black which results from the heat-treating operation or may be bright finish, the result of bright drawing. Other finishes are possible by mutual agreement between purchaser and producer. It is recommended that reference be made to BS 3382 "Electroplated Coatings on Threaded Components" in this respect.

General Dimensions: The bolts, screws and nuts conform to the general dimensions given in Tables 3, 4, 5 and 6.

Nominal Lengths of Bolts and Screws: The nominal length of a bolt or screw is the distance from the underside of the head to the extreme end of the shank including any chamfer or radius. Standard nominal lengths and tolerances thereon are given in Table 7.

Table 7. British Standard ISO Metric Bolt and Screw Nominal Lengths
BS 3692:1967 (obsolescent)

Nominal Length[a] *l*	Tolerance	Nominal Length[a] *l*	Tolerance	Nominal Length[a] *l*	Tolerance	Nominal Length[a] *l*	Tolerance
5	± 0.24	30	± 0.42	90	± 0.70	200	± 0.925
6	± 0.24	(32)	± 0.50	(95)	± 0.70	220	± 0.925
(7)	± 0.29	35	± 0.50	100	± 0.70	240	± 0.925
8	± 0.29	(38)	± 0.50	(105)	± 0.70	260	± 1.05
(9)	± 0.29	40	± 0.50	110	± 0.70	280	± 1.05
10	± 0.29	45	± 0.50	(115)	± 0.70	300	± 1.05
(11)	± 0.35	50	± 0.50	120	± 0.70	325	± 1.15
12	± 0.35	55	± 0.60	(125)	± 0.80	350	± 1.15
14	± 0.35	60	± 0.60	130	± 0.80	375	± 1.15
16	± 0.35	65	± 0.60	140	± 0.80	400	± 1.15
(18)	± 0.35	70	± 0.60	150	± 0.80	425	± 1.25
20	± 0.42	75	± 0.60	160	± 0.80	450	± 1.25
(22)	± 0.42	80	± 0.60	170	± 0.80	475	± 1.25
25	± 0.42	85	± 0.70	180	± 0.80	500	± 1.25
(28)	± 0.42	…	…	190	± 0.925	…	…

[a] Nominal lengths shown in parentheses are non-preferred.

All dimensions are in millimeters.

Bolt and Screw Ends: The ends of bolts and screws may be finished with either a 45-degree chamfer to a depth slightly exceeding the depth of thread or a radius approximately

Copyright 2004, Industrial Press, Inc., New York, NY

equal to 1¼ times the nominal diameter of the shank. With rolled threads, the lead formed at the end of the bolt by the thread rolling operation may be regarded as providing the necesssary chamfer to the end; the end being reasonably square with the center line of the shank.

Screw Thread Form: The form of thread and diameters and associated pitches of standard ISO metric bolts, screws, and nuts are in accordance with BS 3643:Part 1:1981 (1998), "Principles and Basic Data" The screw threads are made to the tolerances for the medium class of fit (6*H*/6*g*) as specified in BS 3643:Part 2:1981 (1998), "Specification for Selected Limits of Size."

Length of Thread on Bolts: The length of thread on bolts is the distance from the end of the bolt (including any chamfer or radius) to the leading face of a screw ring gage which has been screwed as far as possible onto the bolt by hand. Standard thread lengths of bolts are $2d + 6$ mm for a nominal length of bolt up to and including 125 mm, $2d + 12$ mm for a nominal bolt length over 125 mm up to and including 200 mm, and $2d + 25$ mm for a nominal bolt length over 200 mm. Bolts that are too short for minimum thread lengths are threaded as screws and designated as screws. The tolerance on bolt thread lengths are plus two pitches for all diameters.

Length of Thread on Screws: Screws are threaded to permit a screw ring gage being screwed by hand to within a distance from the underside of the head not exceeding two and a half times the pitch for diameters up to and including 52 mm and three and a half times the pitch for diameters over 52 mm.

Angularity and Eccentricity of Bolts, Screws and Nuts: The axis of the thread of the nut is square to the face of the nut subject to the "squareness tolerance" given in Table 5.

In gaging, the nut is screwed by hand onto a gage, having a truncated taper thread, until the thread of the nut is tight on the thread of the gage. A sleeve sliding on a parallel extension of the gage, which has a face of diameter equal to the minimum distance across the flats of the nut and exactly at 90 degrees to the axis of the gage, is brought into contact with the leading face of the nut. With the sleeve in this position, it should not be possible for a feeler gage of thickness equal to the "squareness tolerance" to enter anywhere between the leading nut face and sleeve face.

The hexagon flats of bolts, screws and nuts are square to the bearing face, and the angularity of the head is within the limits of 90 degrees, plus or minus 1 degree. The eccentricity of the hexagon flats of nuts relative to the thread diameter should not exceed the values given in Table 5 and the eccentricity of the head relative to the width across flats and eccentricity between the shank and thread of bolts and screws should not exceed the values given in Table 4.

Chamfering, Washer Facing and Countersinking: Bolt and screw heads have a chamfer of approximately 30 degrees on their upper faces and, at the option of the manufacturer, a washer face or full bearing face on the underside. Nuts are countersunk at an included angle of 120 degrees plus or minus 10 degrees at both ends of the thread. The diameter of the countersink should not exceed the nominal major diameter of the thread plus 0.13 mm up to and including 12 mm diameter, and plus 0.25 mm above 12 mm diameter. This stipulation does not apply to slotted, castle or thin nuts.

Strength Grade Designation System for Steel Bolts and Screws: This Standard includes a strength grade designation system consisting of two figures. The first figure is one tenth of the minimum tensile strength in kgf/mm^2, and the second figure is one tenth of the ratio between the minimum yield stress (or stress at permanent set limit, $R_{0.2}$) and the minimum tensile strength, expressed as a percentage. For example with the strength designation grade 8.8, the first figure 8 represents $\frac{1}{10}$ the minimum tensile strength of 80 kgf/mm^2 and the second figure 8 represents $\frac{1}{10}$ the ratio

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{\text{stress at permanent set limit } R_{0.2}\%}{\text{minimum tensile strength}} = \frac{1}{10} \times \frac{64}{80} \times \frac{100}{1}$$

the numerical values of stress and strength being obtained from the accompanying table.

Strength Grade Designations of Steel Bolts and Screws

Strength Grade Designation	4.6	4.8	5.6	5.8	6.6	6.8	8.8	10.9	12.9	14.9
Tensile Strength (R_m), Min.	40	40	50	50	60	60	80	100	120	140
Yield Stress (R_e), Min.	24	32	30	40	36	48	…	…	…	…
Stress at Permanent Set Limit ($R_{0.2}$), Min.	…	…	…	…	…	…	64	90	108	126
All stress and strength values are in kgf/mm^2 units.										

Strength Grade Designation System for Steel Nuts: The strength grade designation system for steel nuts is a number which is one-tenth of the specified proof load stress in kgf/mm^2. The proof load stress corresponds to the minimum tensile strength of the highest grade of bolt or screw with which the nut can be used.

Strength Grade Designations of Steel Nuts

Strength Grade Designation	4	5	6	8	12	14
Proof Load Stress (kgf/mm^2)	40	50	60	80	120	140

Recommended Bolt and Nut Combinations

Grade of Bolt	4.6	4.8	5.6	5.8	6.6	6.8	8.8	10.9	12.9	14.9
Recommended Grade of Nut	4	4	5	5	6	6	8	12	12	14
Note: Nuts of a higher strength grade may be substituted for nuts of a lower strength grade.										

Marking: The marking and identification requirements of this Standard are only mandatory for steel bolts, screws and nuts of 6 mm diameter and larger; manufactured to strength grade designations 8.8 (for bolts or screws) and 8 (for nuts) or higher. Bolts and screws are identified as ISO metric by either of the symbols "ISO M" or "M", embossed or indented on top of the head. Nuts may be indented or embossed by alternative methods depending on their method of manufacture.

Designation: Bolts 10 mm diameter, 50 mm long manufactured from steel of strength grade 8.8, would be designated:

"Bolts M10 × 50 to BS 3692 — 8.8."

Brass screws 8 mm diameter, 20 mm long would be designated:

"Brass screws M8 × 20 to BS 3692."

Nuts 12 mm diameter, manufactured from steel of strength grade 6, cadmium plated could be designated:

"Nuts M12 to BS 3692 — 6, plated to BS 3382: Part 1."

Miscellaneous Information: The Standard also gives mechanical properties of steel bolts, screws and nuts [i.e., tensile strengths; hardnesses (Brinell, Rockwell, Vickers); stresses (yield, proof load); etc.], material and manufacture of steel bolts, screws and nuts; and information on inspection and testing. Appendices to the Standard give information on gaging; chemical composition; testing of mechanical properties; examples of marking of bolts, screws and nuts; and a table of preferred standard sizes of bolts and screws, to name some.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard General Purpose Studs *BS 2693:Part 1:1956 (obsolescent)*

Nom. Dia. *D*	Limits for End Screwed into Component (All threads except BA)												
	Major Dia.	Thds. per In.	Major Dia.	Effective Diameter		Minor Diameter		Thds. per In.	Major Dia.	Effective Diameter		Minor Dia.	
	Max.		Min.	Max.	Min.	Max.	Min.		Min.	Max.	Min.	Max.	Min.
UN THREADS				UNF THREADS						UNC THREADS			
1/4	0.2500	28	0.2435	0.2294	0.2265	0.2088	0.2037	20	0.2419	0.2201	0.2172	0.1913	0.1849
5/16	0.3125	24	0.3053	0.2883	0.2852	0.2643	0.2586	18	0.3038	0.2793	0.2762	0.2472	0.2402
3/8	0.3750	24	0.3678	0.3510	0.3478	0.3270	0.3211	16	0.3656	0.3375	0.3343	0.3014	0.2936
7/16	0.4375	20	0.4294	0.4084	0.4050	0.3796	0.3729	14	0.4272	0.3945	0.3911	0.3533	0.3447
1/2	0.5000	20	0.4919	0.4712	0.4675	0.4424	0.4356	13	0.4891	0.4537	0.4500	0.4093	0.4000
9/16	0.5625	18	0.5538	0.5302	0.5264	0.4981	0.4907	12	0.5511	0.5122	0.5084	0.4641	0.4542
5/8	0.6250	18	0.6163	0.5929	0.5889	0.5608	0.5533	11	0.6129	0.5700	0.5660	0.5175	0.5069
3/4	0.7500	16	0.7406	0.7137	0.7094	0.6776	0.6693	10	0.7371	0.6893	0.6850	0.6316	0.6200
7/8	0.8750	14	0.8647	0.8332	0.8286	0.7920	0.7828	9	0.8611	0.8074	0.8028	0.7433	0.7306
1	1.0000	12	0.9886	0.9510	0.9459	0.9029	0.8925	8	0.9850	0.9239	0.9188	0.8517	0.8376
1 1/8	1.1250	12	1.1136	1.0762	1.0709	1.0281	1.0176	7	1.1086	1.0375	1.0322	0.9550	0.9393
1 1/4	1.2500	12	1.2386	1.2014	1.1959	1.1533	1.1427	7	1.2336	1.1627	1.1572	1.0802	1.0644
1 3/8	1.3750	12	1.3636	1.3265	1.3209	1.2784	1.2677	6	1.3568	1.2723	1.2667	1.1761	1.1581
1 1/2	1.5000	12	1.4886	1.4517	1.4459	1.4036	1.3928	6	1.4818	1.3975	1.3917	1.3013	1.2832
BS THREADS				BSF THREADS						BSW THREADS			
1/4	0.2500	26	0.2455	0.2280	0.2251	0.2034	0.1984	20	0.2452	0.2206	0.2177	0.1886	0.1831
5/16	0.3125	22	0.3077	0.2863	0.2832	0.2572	0.2517	18	0.3073	0.2798	0.2767	0.2442	0.2383
3/8	0.3750	20	0.3699	0.3461	0.3429	0.3141	0.3083	16	0.3695	0.3381	0.3349	0.0981	0.2919
7/16	0.4375	18	0.4320	0.4053	0.4019	0.3697	0.3635	14	0.4316	0.3952	0.3918	0.3495	0.3428
1/2	0.5000	16	0.4942	0.4637	0.4600	0.4237	0.4172	12	0.4937	0.4503	0.4466	0.3969	0.3897
9/16	0.5625	16	0.5566	0.5263	0.5225	0.4863	0.4797	12	0.5560	0.5129	0.5091	0.4595	0.4521
5/8	0.6250	14	0.6187	0.5833	0.5793	0.5376	0.5305	11	0.6183	0.5708	0.5668	0.5126	0.5050
3/4	0.7500	12	0.7432	0.7009	0.6966	0.6475	0.6398	10	0.7428	0.6903	0.6860	0.6263	0.6182
7/8	0.8750	11	0.8678	0.8214	0.8168	0.7632	0.7551	9	0.8674	0.8085	0.8039	0.7374	0.7288
1	1.0000	10	0.9924	0.9411	0.9360	0.8771	0.8686	8	0.9920	0.9251	0.9200	0.8451	0.8360
1 1/8	1.1250	9	1.1171	1.0592	1.0539	0.9881	0.9792	7	1.1164	1.0388	1.0335	0.9473	0.9376
1 1/4	1.2500	9	1.2419	1.1844	1.1789	1.1133	1.1042	7	1.2413	1.1640	1.1585	1.0725	1.0627
1 3/8	1.3750	8	1.3665	1.3006	1.2950	1.2206	1.2110	6	1.4906	1.3991	1.3933	1.2924	1.2818
1 1/2	1.5000	8	1.4913	1.4258	1.4200	1.3458	1.3360	…	…	…	…	…	…

Designation No.	Limits for End Screwed into Component (BA Threads)[a]					
	Pitch	Major Diameter		Effective Diameter		Minor Diameter	
		Max.	Min.	Max.	Min.	Max.	Min.
2	0.8100 mm 0.03189 in.	4.700 mm 0.1850 in.	4.580 mm 0.1803 in.	4.275 mm 0.1683 in.	4.200 mm 0.1654 in.	3.790 mm 0.1492 in.	3.620 mm 0.1425 in.
4	0.6600 mm 0.2598 in.	3.600 mm 0.1417 in.	3.500 mm 0.1378 in.	3.260 mm 0.1283 in.	3.190 mm 0.1256 in.	2.865 mm 0.1128 in.	2.720 mm 0.1071 in.

[a] Approximate inch equivalents are shown below the dimensions given in mm.

Nom. Stud. Dia.	Minimum Nominal Lengths of Studs[a]							
	For Thread Length (Component End) of		Nom. Stud. Dia.	For Thread Length (Component End) of		Nom. Stud Dia.	For Thread Length (Component End) of	
	1*D*	1.5*D*		1*D*	1.5*D*		1*D*	1.5*D*
1/4	7/8	1	9/16	2	2 3/8	1 1/8	4	4 5/8
5/16	1 1/8	1 3/8	5/8	2 1/4	2 5/8	1 1/4	4 3/4	5 1/2
3/8	1 3/8	1 5/8	3/4	2 5/8	3	1 3/8	5	5 3/4
7/16	1 5/8	1 7/8	7/8	3 1/8	3 5/8	1 1/2	5 1/4	6
1/2	1 3/4	2	1	3 1/2	4	…	…	…

[a] The standard also gives preferred and standard lengths of studs: *Preferred* lengths of studs: 7/8, 1, 1 1/8, 1 1/4, 1 3/8, 1 1/2, 1 3/4, 2, 2 1/4, 2 1/2, 2 3/4, 3, 3 1/4, 3 1/2 and for lengths above 3 1/2 the preferred increment is 1/2. *Standard* lengths of studs: 7/8, 1, 1 1/8, 1 1/4, 1 3/8, 1 1/2, 1 5/8, 1 3/4, 1 7/8, 2, 2 1/8, 2 1/4, 2 3/8, 2 1/2, 2 5/8, 2 3/4, 2 7/8, 3, 3 1/8, 3 1/4, 3 3/8, 3 1/2 and for lengths above 3 1/2 the standard increment is 1/4.

All dimensions are in inches except where otherwise noted.

See page 1877 for interference-fit threads.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Single Coil Rectangular Section Spring Washers
Metric Series — Types B and BP *BS 4464:1969 (1998)*



Nom. Size &Thread Dia., *d*	Inside Dia., d_1		Width, *b*	Thickness, *s*	Outside Dia., d_2 Max	Radius, *r* Max	*k* (Type BP Only)
	Max	Min					
M1.6	1.9	1.7	0.7 ± 0.1	0.4 ± 0.1	3.5	0.15	…
M2	2.3	2.1	0.9 ± 0.1	0.5 ± 0.1	4.3	0.15	…
(M2.2)	2.5	2.3	1.0 ± 0.1	0.6 ± 0.1	4.7	0.2	…
M2.5	2.8	2.6	1.0 ± 0.1	0.6 ± 0.1	5.0	0.2	…
M3	3.3	3.1	1.3 ± 0.1	0.8 ± 0.1	6.1	0.25	…
(M3.5)	3.8	3.6	1.3 ± 0.1	0.8 ± 0.1	6.6	0.25	0.15
M4	4.35	4.1	1.5 ± 0.1	0.9 ± 0.1	7.55	0.3	0.15
M5	5.35	5.1	1.8 ± 0.1	1.2 ± 0.1	9.15	0.4	0.15
M6	6.4	6.1	2.5 ± 0.15	1.6 ± 0.1	11.7	0.5	0.2
M8	8.55	8.2	3 ± 0.15	2 ± 0.1	14.85	0.65	0.3
M10	10.6	10.2	3.5 ± 0.2	2.2 ± 0.15	18.0	0.7	0.3
M12	12.6	12.2	4 ± 0.2	2.5 ± 0.15	21.0	0.8	0.4
(M14)	14.7	14.2	4.5 ± 0.2	3 ± 0.15	24.1	1.0	0.4
M16	16.9	16.3	5 ± 0.2	3.5 ± 0.2	27.3	1.15	0.4
(M18)	19.0	18.3	5 ± 0.2	3.5 ± 0.2	29.4	1.15	0.4
M20	21.1	20.3	6 ± 0.2	4 ± 0.2	33.5	1.3	0.4
(M22)	23.3	22.4	6 ± 0.2	4 ± 0.2	35.7	1.3	0.4
M24	25.3	24.4	7 ± 0.25	5 ± 0.2	39.8	1.65	0.5
(M27)	28.5	27.5	7 ± 0.25	5 ± 0.2	43.0	1.65	0.5
M30	31.5	30.5	8 ± 0.25	6 ± 0.25	48.0	2.0	0.8
(M33)	34.6	33.5	10 ± 0.25	6 ± 0.25	55.1	2.0	0.8
M36	37.6	36.5	10 ± 0.25	6 ± 0.25	58.1	2.0	0.8
(M39)	40.8	39.6	10 ± 0.25	6 ± 0.25	61.3	2.0	0.8
M42	43.8	42.6	12 ± 0.25	7 ± 0.25	68.3	2.3	0.8
(M45)	46.8	45.6	12 ± 0.25	7 ± 0.25	71.3	2.3	0.8
M48	50.0	48.8	12 ± 0.25	7 ± 0.25	74.5	2.3	0.8
(M52)	54.1	52.8	14 ± 0.25	8 ± 0.25	82.6	2.65	1.0
M56	58.1	56.8	14 ± 0.25	8 ± 0.25	86.6	2.65	1.0
(M60)	62.3	60.9	14 ± 0.25	8 ± 0.25	90.8	2.65	1.0
M64	66.3	64.9	14 ± 0.25	8 ± 0.25	93.8	2.65	1.0
(M68)	70.5	69.0	14 ± 0.25	8 ± 0.25	99.0	2.65	1.0

All dimensions are given in millimeters. Sizes shown in parentheses are non-preferred, and are not usually stock sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Double Coil Rectangular Section Spring Washers; Metric Series — Type D *BS 4464:1969 (1998)*



Nom. Size, d	Inside Dia., d_1		Width, b	Thickness, s	O.D., d_2 Max	Radius, r Max
	Max	Min				
M2	2.4	2.1	0.9 ± 0.1	0.5 ± 0.05	4.4	0.15
(M2.2)	2.6	2.3	1.0 ± 0.1	0.6 ± 0.05	4.8	0.2
M2.5	2.9	2.6	1.2 ± 0.1	0.7 ± 0.1	5.5	0.23
M3.0	3.6	3.3	1.2 ± 0.1	0.8 ± 0.1	6.2	0.25
(M3.5)	4.1	3.8	1.6 ± 0.1	0.8 ± 0.1	7.5	0.25
M4	4.6	4.3	1.6 ± 0.1	0.8 ± 0.1	8.0	0.25
M5	5.6	5.3	2 ± 0.1	0.9 ± 0.1	9.8	0.3
M6	6.6	6.3	3 ± 0.15	1 ± 0.1	12.9	0.33
M8	8.8	8.4	3 ± 0.15	1.2 ± 0.1	15.1	0.4
M10	10.8	10.4	3.5 ± 0.20	1.2 ± 0.1	18.2	0.4
M12	12.8	12.4	3.5 ± 0.2	1.6 ± 0.1	20.2	0.5
(M14)	15.0	14.5	5 ± 0.2	1.6 ± 0.1	25.4	0.5
M16	17.0	16.5	5 ± 0.2	2 ± 0.1	27.4	0.65
(M18)	19.0	18.5	5 ± 0.2	2 ± 0.1	29.4	0.65
M20	21.5	20.8	5 ± 0.2	2 ± 0.1	31.9	0.65
(M22)	23.5	22.8	6 ± 0.2	2.5 ± 0.15	35.9	0.8
M24	26.0	25.0	6.5 ± 0.2	3.25 ± 0.15	39.4	1.1
(M27)	29.5	28.0	7 ± 0.25	3.25 ± 0.15	44.0	1.1
M30	33.0	31.5	8 ± 0.25	3.25 ± 0.15	49.5	1.1
(M33)	36.0	34.5	8 ± 0.25	3.25 ± 0.15	52.5	1.1
M36	40.0	38.0	10 ± 0.25	3.25 ± 0.15	60.5	1.1
(M39)	43.0	41.0	10 ± 0.25	3.25 ± 0.15	63.5	1.1
M42	46.0	44.0	10 ± 0.25	4.5 ± 0.2	66.5	1.5
M48	52.0	50.0	10 ± 0.25	4.5 ± 0.2	72.5	1.5
M56	60.0	58.0	12 ± 0.25	4.5 ± 0.2	84.5	1.5
M64	70.0	67.0	12 ± 0.25	4.5 ± 0.2	94.5	1.5

All dimensions are given in millimeters. Sizes shown in parentheses are non-preferred, and are not usually stock sizes. The free height of double coil washers before compression is normally approximately five times the thickness but, if required, washers with other free heights may be obtained by arrangement with manufacturer.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Single Coil Square Section Spring Washers; Metric Series — Type A-1 *BS 4464:1969 (1998)*



British Standard Single Coil Square Section Spring Washers; Metric Series — Type A-2 *BS 4464:1969 (1998)*

Nom. Size, d	Inside Dia., d_1		Thickness & Width, s	O.D., d_2	Radius, r
	Max	Min		Max	Max
M3	3.3	3.1	1 ± 0.1	5.5	0.3
(M3.5)	3.8	3.6	1 ± 0.1	6.0	0.3
M4	4.35	4.1	1.2 ± 0.1	6.95	0.4
M5	5.35	5.1	1.5 ± 0.1	8.55	0.5
M6	6.4	6.1	1.5 ± 0.1	9.6	0.5
M8	8.55	8.2	2 ± 0.1	12.75	0.65
M10	10.6	10.2	2.5 ± 0.15	15.9	0.8
M12	12.6	12.2	2.5 ± 0.15	17.9	0.8
(M14)	14.7	14.2	3 ± 0.2	21.1	1.0
M16	16.9	16.3	3.5 ± 0.2	24.3	1.15
(M18)	19.0	18.3	3.5 ± 0.2	26.4	1.15
M20	21.1	20.3	4.5 ± 0.2	30.5	1.5
(M22)	23.3	22.4	4.5 ± 0.2	32.7	1.5
M24	25.3	24.4	5 ± 0.2	35.7	1.65
(M27)	28.5	27.5	5 ± 0.2	38.9	1.65
M30	31.5	30.5	6 ± 0.2	43.9	2.0
(M33)	34.6	33.5	6 ± 0.2	47.0	2.0
M36	37.6	36.5	7 ± 0.25	52.1	2.3
(M39)	40.8	39.6	7 ± 0.25	55.3	2.3
M42	43.8	42.6	8 ± 0.25	60.3	2.65
(M45)	46.8	45.6	8 ± 0.25	63.3	2.65
M48	50.0	48.8	8 ± 0.25	66.5	2.65

All dimensions are in millimeters. Sizes shown in parentheses are nonpreferred and are not usually stock sizes.

British Standard for Metric Series Metal Washers.— BS 4320:1968 (1998) specifies bright and black metal washers for general engineering purposes.

Bright Metal Washers: These washers are made from either CS4 cold-rolled strip steel BS 1449:Part 3B or from CZ 108 brass strip B.S. 2870: 1980, both in the hard condition. However, by mutual agreement between purchaser and supplier, washers may be made available with the material in any other condition, or they may be made from another material, or may be coated with a protective or decorative finish to some appropriate British Standard. Washers are reasonably flat and free from burrs and are normally supplied unchamfered. They may, however, have a 30-degree chamfer on one edge of the external diameter. These washers are made available in two size categories, normal and large diameter, and in two thicknesses, normal (Form A or C) and light (Form B or D). The thickness of a light-range washer is from ½ to ⅔ the thickness of a normal range washer.

Black Metal Washers: These washers are made from mild steel, and can be supplied in three size categories designated normal, large, and extra large diameters. The normal-diameter series is intended for bolts ranging from M5 to M68 (Form E washers), the large-diameter series for bolts ranging from M8 to M39 (Form F washers), and the extra large series for bolts from M5 to M39 (Form G washers). A protective finish can be specified by the purchaser in accordance with any appropriate British Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Washer Designations: The Standard specifies the details that should be given when ordering or placing an inquiry for washers. These details are the general description, namely, bright or black washers; the nominal size of the bolt or screw involved, for example, M5; the designated form, for example, Form A or Form E; the dimensions of any chamfer required on bright washers; the number of the Standard BS 4320:1968 (1998), and coating information if required, with the number of the appropriate British Standard and the coating thickness needed. As an example, in the use of this information, the designation for a chamfered, normal-diameter series washer of normal-range thickness to suit a 12-mm diameter bolt would be: Bright washers M12 (Form A) chamfered to B.S. 4320.

British Standard Bright Metal Washers — Metric Series *BS 4320:1968 (1998)*

NORMAL DIAMETER SIZES													
Nominal Size of Bolt or Screw	Inside Diameter			Outside Diameter			Thickness					
							Form A (Normal Range)			Form B (Light Range)		
	Nom	Max	Min	Nom	Max	Min	Nom	Max	Min	Nom	Max	Min
M 1.0	1.1	1.25	1.1	2.5	2.5	2.3	0.3	0.4	0.2	…	…	…
M 1.2	1.3	1.45	1.3	3.0	3.0	2.8	0.3	0.4	0.2	…	…	…
(M 1.4)	1.5	1.65	1.5	3.0	3.0	2.8	0.3	0.4	0.2	…	…	…
M 1.6	1.7	1.85	1.7	4.0	4.0	3.7	0.3	0.4	0.2	…	…	…
M 2.0	2.2	2.35	2.2	5.0	5.0	4.7	0.3	0.4	0.2	…	…	…
(M 2.2)	2.4	2.55	2.4	5.0	5.0	4.7	0.5	0.6	0.4	…	…	…
M 2.5	2.7	2.85	2.7	6.5	6.5	6.2	0.5	0.6	0.4	…	…	…
M3	3.2	3.4	3.2	7	7	6.7	0.5	0.6	0.4	…	…	…
(M 3.5)	3.7	3.9	3.7	7	7	6.7	0.5	0.6	0.4	…	…	…
M4	4.3	4.5	4.3	9	9	8.7	0.8	0.9	0.7	…	…	…
(M 4.5)	4.8	5.0	4.8	9	9	8.7	0.8	0.9	0.7	…	…	…
M 5	5.3	5.5	5.3	10	10	9.7	1.0	1.1	0.9	…	…	…
M 6	6.4	6.7	6.4	12.5	12.5	12.1	1.6	1.8	1.4	0.8	0.9	0.7
(M 7)	7.4	7.7	7.4	14	14	13.6	1.6	1.8	1.4	0.8	0.9	0.7
M 8	8.4	8.7	8.4	17	17	16.6	1.6	1.8	1.4	1.0	1.1	0.9
M 10	10.5	10.9	10.5	21	21	20.5	2.0	2.2	1.8	1.25	1.45	1.05
M 12	13.0	13.4	13.0	24	24	23.5	2.5	2.7	2.3	1.6	1.80	1.40
(M 14)	15.0	15.4	15.0	28	28	27.5	2.5	2.7	2.3	1.6	1.8	1.4
M 16	17.0	17.4	17.0	30	30	29.5	3.0	3.3	2.7	2.0	2.2	1.8
(M 18)	19.0	19.5	19.0	34	34	33.2	3.0	3.3	2.7	2.0	2.2	1.8
M 20	21	21.5	21	37	37	36.2	3.0	3.3	2.7	2.0	2.2	1.8
(M 22)	23	23.5	23	39	39	38.2	3.0	3.3	2.7	2.0	2.2	1.8
M24	25	25.5	25	44	44	43.2	4.0	4.3	3.7	2.5	2.7	2.3
(M 27)	28	28.5	28	50	50	49.2	4.0	4.3	3.7	2.5	2.7	2.3
M30	31	31.6	31	56	56	55.0	4.0	4.3	3.7	2.5	2.7	2.3
(M 33)	34	34.6	34	60	60	59.0	5.0	5.6	4.4	3.0	3.3	2.7
M 36	37	37.6	37	66	66	65.0	5.0	5.6	4.4	3.0	3.3	2.7
(M 39)	40	40.6	40	72	72	71.0	6.0	6.6	5.4	3.0	3.3	2.7

LARGE DIAMETER SIZES												
Nominal Size of Bolt or Screw	Inside Diameter			Outside Diameter			Thickness					
							Form C (Normal Range)			Form D (Light Range)		
	Nom	Max	Min	Nom	Max	Min	Nom	Max	Min	Nom	Max	Min
M 4	4.3	4.5	4.3	10.0	10.0	9.7	0.8	0.9	0.7	…	…	…
M 5	5.3	5.5	5.3	12.5	12.5	12.1	1.0	1.1	0.9	…	…	…
M 6	6.4	6.7	6.4	14	14	13.6	1.6	1.8	1.4	0.8	0.9	0.7
M 8	8.4	8.7	8.4	21	21	20.5	1.6	1.8	1.4	1.0	1.1	0.9
M 10	10.5	10.9	10.5	24	24	23.5	2.0	2.2	1.8	1.25	1.45	1.05
M 12	13.0	13.4	13.0	28	28	27.5	2.5	2.7	2.3	1.6	1.8	1.4
(M 14)	15.0	15.4	15	30	30	29.5	2.5	2.7	2.3	1.6	1.8	1.4
M 16	17.0	17.4	17	34	34	33.2	3.0	3.3	2.7	2.0	2.2	1.8
(M 18)	19.0	19.5	19	37	37	36.2	3.0	3.3	2.7	2.0	2.2	1.8
M 20	21	21.5	21	39	39	38.2	3.0	3.3	2.7	2.0	2.2	1.8
(M 22)	23	23.5	23	44	44	43.2	3.0	3.3	2.7	2.0	2.2	1.8
M 24	25	25.5	25	50	50	49.2	4.0	4.3	3.7	2.5	2.7	2.3
(M 27)	28	28.5	28	56	56	55	4.0	4.3	3.7	2.5	2.7	2.3
M 30	31	31.6	31	60	60	59	4.0	4.3	3.7	2.5	2.7	2.3
(M 33)	34	34.6	34	66	66	65	5.0	5.6	4.4	3.0	3.3	2.7
M 36	37	37.6	37	72	72	71	5.0	5.6	4.4	3.0	3.3	2.7
(M 39)	40	40.6	40	77	77	76	6.0	6.6	5.4	3.0	3.3	2.7

All dimensions are in millimeters.

Nominal bolt or screw sizes shown in parentheses are nonpreferred.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Black Metal Washers — Metric Series *BS 4320:1968 (1998)*

Nom Bolt or Screw Size	Inside Diameter			Outside Diameter			Thickness		
	Nom	Max	Min	Nom	Max	Min	Nom	Max	Min
NORMAL DIAMETER SIZES (Form E)									
M 5	5.5	5.8	5.5	10.0	10.0	9.2	1.0	1.2	0.8
M 6	6.6	7.0	6.6	12.5	12.5	11.7	1.6	1.9	1.3
(M 7)	7.6	8.0	7.6	14.0	14.0	13.2	1.6	1.9	1.3
M 8	9.0	9.4	9.0	17	17	16.2	1.6	1.9	1.3
M 10	11.0	11.5	11.0	21	21	20.2	2.0	2.3	1.7
M 12	14	14.5	14	24	24	23.2	2.5	2.8	2.2
(M 14)	16	16.5	16	28	28	27.2	2.5	2.8	2.2
M 16	18	18.5	18	30	30	29.2	3.0	3.6	2.4
(M 18)	20	20.6	20	34	34	32.8	3.0	3.6	2.4
M 20	22	22.6	22	37	37	35.8	3.0	3.6	2.4
(M 22)	24	24.6	24	39	39	37.8	3.0	3.6	2.4
M 24	26	26.6	26	44	44	42.8	4	4.6	3.4
(M 27)	30	30.6	30	50	50	48.8	4	4.6	3.4
M 30	33	33.8	33	56	56	54.5	4	4.6	3.4
(M 33)	36	36.8	36	60	60	58.5	5	6.0	4.0
M 36	39	39.8	39	66	66	64.5	5	6.0	4.0
(M 39)	42	42.8	42	72	72	70.5	6	7.0	5.0
M 42	45	45.8	45	78	78	76.5	7	8.2	5.8
(M 45)	48	48.8	48	85	85	83	7	8.2	5.8
M 48	52	53	52	92	92	90	8	9.2	6.8
(M 52)	56	57	56	98	98	96	8	9.2	6.8
M 56	62	63	62	105	105	103	9	10.2	7.8
(M 60)	66	67	66	110	110	108	9	10.2	7.8
M 64	70	71	70	115	115	113	9	10.2	7.8
(M 68)	74	75	74	120	120	118	10	11.2	8.8
LARGE DIAMETER SIZES (Form F)									
M 8	9	9.4	9.0	21	21	20.2	1.6	1.9	1.3
M 10	11	11.5	11	24	24	23.2	2	2.3	1.7
M 12	14	14.5	14	28	28	27.2	2.5	2.8	2.2
(M 14)	16	16.5	16	30	30	29.2	2.5	2.8	2.2
M 16	18	18.5	18	34	34	32.8	3	3.6	2.4
(M 18)	20	20.6	20	37	37	35.8	3	3.6	2.4
M 20	22	22.6	22	39	39	37.8	3	3.6	2.4
(M 22)	24	24.6	24	44	44	42.8	3	3.6	2.4
M 24	26	26.6	26	50	50	48.8	4	4.6	3.4
(M 27)	30	30.6	30	56	56	54.5	4	4.6	3.4
M 30	33	33.8	33	60	60	58.5	4	4.6	3.4
(M 33)	36	36.8	36	66	66	64.5	5	6.0	4
M 36	39	39.8	39	72	72	70.5	5	6.0	4
(M 39)	42	42.8	42	77	77	75.5	6	7	5
EXTRA LARGE DIAMETER SIZES (Form G)									
M 5	5.5	5.8	5.5	15	15	14.2	1.6	1.9	1.3
M 6	6.6	7.0	6.6	18	18	17.2	2	2.3	1.7
(M 7)	7.6	8.0	7.6	21	21	20.2	2	2.3	1.7
M 8	9	9.4	9.0	24	24	23.2	2	2.3	1.7
M 10	11	11.5	11.0	30	30	29.2	2.5	2.8	2.2
M 12	14	14.5	14.0	36	36	34.8	3	3.6	2.4
(M 14)	16	16.5	16.0	42	42	40.8	3	3.6	2.4
M 16	18	18.5	18	48	48	46.8	4	4.6	3.4
(M 18)	20	20.6	20	54	54	52.5	4	4.6	3.4
M 20	22	22.6	22	60	60	58.5	5	6.0	4
(M 22)	24	24.6	24	66	66	64.5	5	6.0	4
M 24	26	26.6	26	72	72	70.5	6	7	5
(M 27)	30	30.6	30	81	81	79	6	7	5
M 30	33	33.8	33	90	90	88	8	9.2	6.8
(M 33)	36	36.8	36	99	99	97	8	9.2	6.8
M 36	39	39.8	39	108	108	106	10	11.2	8.8
(M39)	42	42.8	42	117	117	115	10	11.2	8.8

All dimensions are in millimeters.

Nominal bolt or screw sizes shown in parentheses are nonpreferred.

Copyright 2004, Industrial Press, Inc., New York, NY

MACHINE SCREWS AND NUTS

American National Standard Machine Screws and Machine Screw Nuts.— This Standard ANSI B18.6.3 covers both slotted and recessed head machine screws. Dimensions of various types of slotted machine screws, machine screw nuts, and header points are given in Tables 1 through 12. The Standard also covers flat trim head, oval trim head and drilled fillister head machine screws and gives cross recess dimensions and gaging dimensions for all types of machine screw heads. Information on metric machine screws B18.6.7M is given beginning on page 1596.

Threads: Except for sizes 0000, 000, and 00, machine screw threads may be either Unified Coarse (UNC) and Fine thread (UNF) Class 2A (see *American Standard for Unified Screw Threads* starting on page 1732) or UNRC and UNRF Series, at option of manufacturer. Thread dimensions for sizes 0000, 000, and 00 are given in Table 7 on page 1592.

Threads for hexagon machine screw nuts may be either UNC or UNF, Class 2B, and for square machine screw nuts are UNC Class 2B.

Length of thread: Machine screws of sizes No. 5 and smaller with nominal lengths equal to 3 diameters and shorter have full form threads extending to within 1 pitch (thread) of the bearing surface of the head, or closer, if practicable. Nominal lengths greater than 3 diameters, up to and including 1⅛ inch, have full form threads extending to within two pitches (threads) of the bearing surface of the head, or closer, if practicable. Unless otherwise specified, screws of longer nominal length have a minimum length of full form thread of 1.00 inch.Machine screws of sizes No. 6 and larger with nominal length equal to 3 diameters and shorter have full form threads extending to within 1 pitch (thread) of the bearing surface of the head, or closer, if practicable. Nominal lengths greater than 3 diameters, up to and including 2 inches, have full form threads extending to within 2 pitches (threads) of the bearing surface of the head, or closer, if practicable. Screws of longer nominal length, unless otherwise specified, have a minimum length of full form thread of 1.50 inches.

Table 1. Square and Hexagon Machine Screw Nuts *ANSI B18.6.3-1972 (R1991)*



Nom. Size	Basic Dia.	Basic F	Max. F	Min. F	Max. G	Min. G	Max. G_1	Min. G_1	Max. H	Min. H
0	0.0600	5/32	0.156	0.150	0.221	0.206	0.180	0.171	0.050	0.043
1	0.0730	5/32	0.156	0.150	0.221	0.206	0.180	0.171	0.050	0.043
2	0.0860	3/16	0.188	0.180	0.265	0.247	0.217	0.205	0.066	0.057
3	0.0990	3/16	0.188	0.180	0.265	0.247	0.217	0.205	0.066	0.057
4	0.1120	1/4	0.250	0.241	0.354	0.331	0.289	0.275	0.098	0.087
5	0.1250	5/16	0.312	0.302	0.442	0.415	0.361	0.344	0.114	0.102
6	0.1380	5/16	0.312	0.302	0.442	0.415	0.361	0.344	0.114	0.102
8	0.1640	11/32	0.344	0.332	0.486	0.456	0.397	0.378	0.130	0.117
10	0.1900	3/8	0.375	0.362	0.530	0.497	0.433	0.413	0.130	0.117
12	0.2160	7/16	0.438	0.423	0.619	0.581	0.505	0.482	0.161	0.148
1/4	0.2500	7/16	0.438	0.423	0.619	0.581	0.505	0.482	0.193	0.178
5/16	0.3125	9/16	0.562	0.545	0.795	0.748	0.650	0.621	0.225	0.208
3/8	0.3750	5/8	0.625	0.607	0.884	0.833	0.722	0.692	0.257	0.239

All dimensions in inches. Hexagon machine screw nuts have tops flat and chamfered. Diameter of top circle should be the maximum width across flats within a tolerance of minus 15 per cent. Bottoms are flat but may be chamfered if so specified. Square machine screw nuts have tops and bottoms flat without chamfer.

Copyright 2004, Industrial Press, Inc., New York, NY

Diameter of body: The diameter of machine screw bodies is not less than Class 2A thread minimum pitch diameter nor greater than the basic major diameter of the thread. Cross-recessed trim head machine screws not threaded to the head have an 0.062 in. minimum length shoulder under the head with diameter limits as specified in the dimensional tables in the standard.

Designation: Machine screws are designated by the following data in the sequence shown: Nominal size (number, fraction, or decimal equivalent); threads per inch; nominal length (fraction or decimal equivalent); product name, including head type and driving provision; header point, if desired; material; and protective finish, if required. For example:

1/4 – 20 × 1 1/4 Slotted Pan Head Machine Screw, Steel, Zinc Plated

6 – 32 × 3/4 Type IA Cross Recessed Fillister Head Machine Screw, Brass

Machine screw nuts are designated by the following data in the sequence shown: Nominal size (number, fraction, or decimal equivalent); threads per inch; product name; material; and protective finish, if required. For example:

10 – 24 Hexagon Machine Screw Nut, Steel, Zinc Plated

0.138 – 32 Square Machine Screw Nut, Brass

Table 2. American National Standard Slotted 100-Degree Flat Countersunk Head Machine Screws *ANSI B18.6.3-1972 (R1977)*



Nominal Size[a] or Basic Screw Dia.		Head Dia., *A*		Head Height, *H*	Slot Width, *J*		Slot Depth, *T*	
		Max., Edge Sharp	Min., Edge Rounded or Flat	Ref.	Max.	Min.	Max.	Min.
0000	0.0210	0.043	0.037	0.009	0.008	0.005	0.008	0.004
000	0.0340	0.064	0.058	0.014	0.012	0.008	0.011	0.007
00	0.0470	0.093	0.085	0.020	0.017	0.010	0.013	0.008
0	0.0600	0.119	0.096	0.026	0.023	0.016	0.013	0.008
1	0.0730	0.146	0.120	0.031	0.026	0.019	0.016	0.010
2	0.0860	0.172	0.143	0.037	0.031	0.023	0.019	0.012
3	0.0990	0.199	0.167	0.043	0.035	0.027	0.022	0.014
4	0.1120	0.225	0.191	0.049	0.039	0.031	0.024	0.017
6	0.1380	0.279	0.238	0.060	0.048	0.039	0.030	0.022
8	0.1640	0.332	0.285	0.072	0.054	0.045	0.036	0.027
10	0.1900	0.385	0.333	0.083	0.060	0.050	0.042	0.031
1/4	0.2500	0.507	0.442	0.110	0.075	0.064	0.055	0.042
5/16	0.3125	0.635	0.556	0.138	0.084	0.072	0.069	0.053
3/8	0.3750	0.762	0.670	0.165	0.094	0.081	0.083	0.065

[a] When specifying nominal size in decimals, zeros preceding the decimal point and in the fourth decimal place are omitted.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Slotted Flat Countersunk Head and Close Tolerance 100-Degree Flat Countersunk Head Machine Screws
ANSI B18.6.3-1972 (R1991)



SLOTTED FLAT COUNTERSUNK HEAD TYPE									
Nominal Size[a] or Basic Screw Dia.		Max., L[b]	Head Dia., A		Head Height, H	Slot Width, J		Slot Depth, T	
			Max., Edge Sharp	Min., Edge[c]	Ref.	Max.	Min.	Max.	Min.
0000	0.0210	....	0.043	0.037	0.011	0.008	0.004	0.007	0.003
000	0.0340	....	0.064	0.058	0.016	0.011	0.007	0.009	0.005
00	0.0470	....	0.093	0.085	0.028	0.017	0.010	0.014	0.009
0	0.0600	1/8	0.119	0.099	0.035	0.023	0.016	0.015	0.010
1	0.0730	1/8	0.146	0.123	0.043	0.026	0.019	0.019	0.012
2	0.0860	1/8	0.172	0.147	0.051	0.031	0.023	0.023	0.015
3	0.0990	1/8	0.199	0.171	0.059	0.035	0.027	0.027	0.017
4	0.1120	3/16	0.225	0.195	0.067	0.039	0.031	0.030	0.020
5	0.1250	3/16	0.252	0.220	0.075	0.043	0.035	0.034	0.022
6	0.1380	3/16	0.279	0.244	0.083	0.048	0.039	0.038	0.024
8	0.1640	1/4	0.332	0.292	0.100	0.054	0.045	0.045	0.029
10	0.1900	5/16	0.385	0.340	0.116	0.060	0.050	0.053	0.034
12	0.2160	3/8	0.438	0.389	0.132	0.067	0.056	0.060	0.039
1/4	0.2500	7/16	0.507	0.452	0.153	0.075	0.064	0.070	0.046
5/16	0.3125	1/2	0.635	0.568	0.191	0.084	0.072	0.088	0.058
3/8	0.3750	9/16	0.762	0.685	0.230	0.094	0.081	0.106	0.070
7/16	0.4375	5/8	0.812	0.723	0.223	0.094	0.081	0.103	0.066
1/2	0.5000	3/4	0.875	0.775	0.223	0.106	0.091	0.103	0.065
9/16	0.5625	…	1.000	0.889	0.260	0.118	0.102	0.120	0.077
5/8	0.6250	…	1.125	1.002	0.298	0.133	0.116	0.137	0.088
3/4	0.7500	…	1.375	1.230	0.372	0.149	0.131	0.171	0.111

[a] When specifying nominal size in decimals, zeros preceding the decimal point and in the fourth decimal place are omitted.

[b] These lengths or shorter are undercut.

[c] May be rounded or flat.

CLOSE TOLERANCE 100-DEGREE FLAT COUNTERSUNK HEAD TYPE								
Nominal Size[a] or Basic Screw Dia.		Head Diameter, A		Head Height, H	Slot Width, J		Slot Depth, T	
		Max., Edge Sharp	Min., Edge[c]	Ref.	Max.	Min.	Max.	Min.
4	0.1120	0.225	0.191	0.049	0.039	0.031	0.024	0.017
6	0.1380	0.279	0.238	0.060	0.048	0.039	0.030	0.022
8	0.1640	0.332	0.285	0.072	0.054	0.045	0.036	0.027
10	0.1900	0.385	0.333	0.083	0.060	0.050	0.042	0.031
1/4	0.2500	0.507	0.442	0.110	0.075	0.064	0.055	0.042
5/16	0.3125	0.635	0.556	0.138	0.084	0.072	0.069	0.053
3/8	0.3750	0.762	0.670	0.165	0.094	0.081	0.083	0.065
7/16	0.4375	0.890	0.783	0.193	0.094	0.081	0.097	0.076
1/2	0.5000	1.017	0.897	0.221	0.106	0.091	0.111	0.088
9/16	0.5625	1.145	1.011	0.249	0.118	0.102	0.125	0.099
5/8	0.6250	1.272	1.124	0.276	0.133	0.116	0.139	0.111

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Slotted Undercut Flat Countersunk Head and Plain and Slotted Hex Washer Head Machine Screws *ANSI B18.6.3-1972 (R1991)*

SLOTTED UNDERCUT FLAT COUNTERSUNK HEAD TYPE



Nominal Size[a] or Basic Screw Dia.		Max., *L*[b]	Head Dia., *A*		Head Height, *H*		Slot Width, *J*		Slot Depth, *T*	
			Max., Edge Sharp	Min., Edge Rnded. or Flat	Max.	Min.	Max.	Min.	Max.	Min.
0	0.0600	1/8	0.119	0.099	0.025	0.018	0.023	0.016	0.011	0.007
1	0.0730	1/8	0.146	0.123	0.031	0.023	0.026	0.019	0.014	0.009
2	0.0860	1/8	0.172	0.147	0.036	0.028	0.031	0.023	0.016	0.011
3	0.0990	1/8	0.199	0.171	0.042	0.033	0.035	0.027	0.019	0.012
4	0.1120	3/16	0.225	0.195	0.047	0.038	0.039	0.031	0.022	0.014
5	0.1250	3/16	0.252	0.220	0.053	0.043	0.043	0.035	0.024	0.016
6	0.1380	3/16	0.279	0.244	0.059	0.048	0.048	0.039	0.027	0.017
8	0.1640	1/4	0.332	0.292	0.070	0.058	0.054	0.045	0.032	0.021
10	0.1900	5/16	0.385	0.340	0.081	0.068	0.060	0.050	0.037	0.024
12	0.2160	3/8	0.438	0.389	0.092	0.078	0.067	0.056	0.043	0.028
1/4	0.2500	7/16	0.507	0.452	0.107	0.092	0.075	0.064	0.050	0.032
5/16	0.3125	1/2	0.635	0.568	0.134	0.116	0.084	0.072	0.062	0.041
3/8	0.3750	9/16	0.762	0.685	0.161	0.140	0.094	0.081	0.075	0.049
7/16	0.4375	5/8	0.812	0.723	0.156	0.133	0.094	0.081	0.072	0.045
1/2	0.5000	3/4	0.875	0.775	0.156	0.130	0.106	0.091	0.072	0.046

[a] When specifying nominal size in decimals, zeros preceding the decimal point and in the fourth decimal place are omitted.

[b] These lengths or shorter are undercut.

PLAIN AND SLOTTED HEX WASHER HEAD TYPES



Nominal Size[a] or Basic Screw Dia.		Width Across Flats, *A*		Width Across-Corn., *W*	Head Height, *H*		Washer Dia., *B*		Washer Thick., *U*		Slot[a] Width, *J*		Slot[a] Depth, *T*	
		Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
2	0.0860	0.125	0.120	0.134	0.050	0.040	0.166	0.154	0.016	0.010	....	....	....	....
3	0.0990	0.125	0.120	0.134	0.055	0.044	0.177	0.163	0.016	0.010	....	....	....	....
4	0.1120	0.188	0.181	0.202	0.060	0.049	0.243	0.225	0.019	0.011	0.039	0.031	0.042	0.025
5	0.1250	0.188	0.181	0.202	0.070	0.058	0.260	0.240	0.025	0.015	0.043	0.035	0.049	0.030
6	0.1380	0.250	0.244	0.272	0.093	0.080	0.328	0.302	0.025	0.015	0.048	0.039	0.053	0.033
8	0.1640	0.250	0.244	0.272	0.110	0.096	0.348	0.322	0.031	0.019	0.054	0.045	0.074	0.052
10	0.1900	0.312	0.305	0.340	0.120	0.105	0.414	0.384	0.031	0.019	0.060	0.050	0.080	0.057
12	0.2160	0.312	0.305	0.340	0.155	0.139	0.432	0.398	0.039	0.022	0.067	0.056	0.103	0.077
1/4	0.2500	0.375	0.367	0.409	0.190	0.172	0.520	0.480	0.050	0.030	0.075	0.064	0.111	0.083
5/16	0.3125	0.500	0.489	0.545	0.230	0.208	0.676	0.624	0.055	0.035	0.084	0.072	0.134	0.100
3/8	0.3750	0.562	0.551	0.614	0.295	0.270	0.780	0.720	0.063	0.037	0.094	0.081	0.168	0.131

[a] Unless otherwise specified, hexagon washer head machine screws are not slotted.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Slotted Truss Head and Plain and Slotted Hexagon Head Machine Screws *ANSI B18.6.3-1972 (R1991)*

SLOTTED TRUSS HEAD TYPE



Nominal Size[a] or Basic Screw Dia.		Head Dia., *A*		Head Height, *H*		Head Radius, *R*	Slot Width, *J*		Slot Depth, *T*	
		Max.	Min.	Max.	Min.	Max.	Max.	Min.	Max.	Min.
0000	0.0210	0.049	0.043	0.014	0.010	0.032	0.009	0.005	0.009	0.005
000	0.0340	0.077	0.071	0.022	0.018	0.051	0.013	0.009	0.013	0.009
00	0.0470	0.106	0.098	0.030	0.024	0.070	0.017	0.010	0.018	0.012
0	0.0600	0.131	0.119	0.037	0.029	0.087	0.023	0.016	0.022	0.014
1	0.0730	0.164	0.149	0.045	0.037	0.107	0.026	0.019	0.027	0.018
2	0.0860	0.194	0.180	0.053	0.044	0.129	0.031	0.023	0.031	0.022
3	0.0990	0.226	0.211	0.061	0.051	0.151	0.035	0.027	0.036	0.026
4	0.1120	0.257	0.241	0.069	0.059	0.169	0.039	0.031	0.040	0.030
5	0.1250	0.289	0.272	0.078	0.066	0.191	0.043	0.035	0.045	0.034
6	0.1380	0.321	0.303	0.086	0.074	0.211	0.048	0.039	0.050	0.037
8	0.1640	0.384	0.364	0.102	0.088	0.254	0.054	0.045	0.058	0.045
10	0.1900	0.448	0.425	0.118	0.103	0.283	0.060	0.050	0.068	0.053
12	0.2160	0.511	0.487	0.134	0.118	0.336	0.067	0.056	0.077	0.061
1/4	0.2500	0.573	0.546	0.150	0.133	0.375	0.075	0.064	0.087	0.070
5/16	0.3125	0.698	0.666	0.183	0.162	0.457	0.084	0.072	0.106	0.085
3/8	0.3750	0.823	0.787	0.215	0.191	0.538	0.094	0.081	0.124	0.100
7/16	0.4375	0.948	0.907	0.248	0.221	0.619	0.094	0.081	0.142	0.116
1/2	0.5000	1.073	1.028	0.280	0.250	0.701	0.106	0.091	0.161	0.131
9/16	0.5625	1.198	1.149	0.312	0.279	0.783	0.118	0.102	0.179	0.146
5/8	0.6250	1.323	1.269	0.345	0.309	0.863	0.133	0.116	0.196	0.162
3/4	0.7500	1.573	1.511	0.410	0.368	1.024	0.149	0.131	0.234	0.182

[a] Where specifying nominal size in decimals, zeros preceding decimal points and in the fourth decimal place are omitted.

PLAIN AND SLOTTED HEXAGON HEAD TYPES



Nominal Size[a] or Basic Screw Dia.		Regular Head			Large Head			Head Height, *H*		Slot[a] Width, *J*		Slot[a] Depth, *T*	
		Width Across Flats, *A*		Across Corn., *W*	Width Across Flats, *A*		Across Corn., *W*						
		Max.	Min.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
1	.0730	.125	.120	.134	....	....	....	.044	.036	....	....	....	…
2	0.0860	.125	.120	.134	....	....	....	.050	.040	....	....	....	…
3	0.0990	.188	.181	.202	....	....	....	.055	.044	....	....	....	…
4	0.1120	.188	.181	.202	.219	.213	.238	.060	.049	.039	.031	.036	.02
5	0.1250	.188	.181	.202	.250	.244	.272	.070	.058	.043	.035	.042	.03
6	0.1380	.250	.244	.272	....	....	....	.093	.080	.048	.039	.046	.03
8	0.1640	.250	.244	.272	.312	.305	.340	.110	.096	.054	.045	.066	.05
10	0.1900	.312	.305	.340	....	....	....	.120	.105	.060	.050	.072	.057
12	0.2160	.312	.305	.340	.375	.367	.409	.155	.139	.067	.056	.093	.07
1/4	0.2500	.375	.367	.409	.438	.428	.477	.190	.172	.075	.064	.101	.08
5/16	0.3125	.500	.489	.545	....	....	....	.230	.208	.084	.072	.122	.10
3/8	0.3750	.562	.551	.614	....	....	....	.295	.270	.094	.081	.156	.13

[a] Unless otherwise specified, hexagon head machine screws are not slotted.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Slotted Pan Head Machine Screws
ANSI B18.6.3-1972 (R1991)



Nominal Size[a] or Basic Screw Dia.		Head Dia., A		Head Height, H		Head Radius, R	Slot Width, J		Slot Depth, T	
		Max.	Min.	Max.	Min.	Max.	Max.	Min.	Max.	Min.
0000	0.0210	.042	.036	.016	.010	.007	.008	.004	.008	.004
000	0.0340	.066	.060	.023	.017	.010	.012	.008	.012	.008
00	0.0470	.090	.082	.032	.025	.015	.017	.010	.016	.010
0	0.0600	.116	.104	.039	.031	.020	.023	.016	.022	.014
1	0.0730	.142	.130	.046	.038	.025	.026	.019	.027	.018
2	0.0860	.167	.155	.053	.045	.035	.031	.023	.031	.022
3	0.0990	.193	.180	.060	.051	.037	.035	.027	.036	.026
4	0.1120	.219	.205	.068	.058	.042	.039	.031	.040	.030
5	0.1250	.245	.231	.075	.065	.044	.043	.035	.045	.034
6	0.1380	.270	.256	.082	.072	.046	.048	.039	.050	.037
8	0.1640	.322	.306	.096	.085	.052	.054	.045	.058	.045
10	0.1900	.373	.357	.110	.099	.061	.060	.050	.068	.053
12	0.2160	.425	.407	.125	.112	.078	.067	.056	.077	.061
1/4	0.2500	.492	.473	.144	.130	.087	.075	.064	.087	.070
5/16	0.3125	.615	.594	.178	.162	.099	.084	.072	.106	.085
3/8	0.3750	.740	.716	.212	.195	.143	.094	.081	.124	.100
7/16	0.4375	.863	.837	.247	.228	.153	.094	.081	.142	.116
1/2	0.5000	.987	.958	.281	.260	.175	.106	.091	.161	.131
9/16	0.5625	1.041	1.000	.315	.293	.197	.118	.102	.179	.146
5/8	0.6250	1.172	1.125	.350	.325	.219	.133	.116	.197	.162
3/4	0.7500	1.435	1.375	.419	.390	.263	.149	.131	.234	.192

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place are omitted.

All dimensions are in inches.

Table 7. Nos. 0000, 000 and 00 Threads *ANSI B18.6.3-1972 (R1991) Appendix*

Nominal Size[a] and Threads Per Inch	Series Designat.	External[b]						Internal[c]				
		Class	Major Diameter		Pitch Diameter			Minor Dia.	Class	Pitch Diameter			Major Dia.
			Max.	Min.	Max.	Min.	Tol.			Min.	Max.	Tol.	Min.
0000-160 or 0.0210-160	NS	2	.0210	.0195	.0169	.0158	.0011	.0128	2	.0169	.0181	.0012	.0210
000-120 or 0.0340-120	NS	2	.0340	.0325	.0286	.0272	.0014	.0232	2	.0286	.0300	.0014	.034
00-90 or 0.0470-90	NS	2	.0470	.0450	.0398	.0382	.0016	.0326	2	.0398	.0414	.0016	.047
00-96 or 0.0470-96	NS	2	.0470	.0450	.0402	.0386	.0016	.0334	2	.0402	.0418	.0016	.047

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place are omitted.

[b] There is no allowance provided on the external threads.

[c] The minor diameter limits for internal threads are not specified, they being determined by the amount of thread engagement necessary to satisfy the strength requirements and tapping performance in the intended application.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. American National Standard Slotted Fillister and Slotted Drilled Fillister Head Machine Screws *ANSI B18.6.3-1972 (R1991)*



SLOTTED FILLISTER HEAD TYPE											
Nominal Size[1] or Basic Screw Dia.		Head Dia., *A*		Head Side Height, *H*		Total Head Height, *O*		Slot Width, *J*		Slot Depth, *T*	
		Max.	Min.	Max.	Min.	Max.	Min.	Max	Min.	Max.	Min.
0000	0.0210	.038	.032	.019	.011	.025	.15	.008	.004	.012	.006
000	0.0340	.059	.053	.029	.021	.035	.027	.012	.006	.017	.011
00	0.0470	.082	.072	.037	.028	.047	.039	.017	.010	.022	.015
0	0.0600	.096	.083	.043	.038	.055	.047	.023	.016	.025	.015
1	0.0730	.118	.104	.053	.045	.066	.058	.026	.019	.031	.020
2	0.0860	.140	.124	.062	.053	.083	.066	.031	.023	.037	.025
3	0.0990	.161	.145	.070	.061	.095	.077	.035	.027	.043	.030
4	0.1120	.183	.166	.079	.069	.107	.088	.039	.031	.048	.035
5	0.1250	.205	.187	.088	.078	.120	.100	.043	.035	.054	.040
6	0.1380	.226	.208	.096	.086	.132	.111	.048	.039	.060	.045
8	0.1640	.270	.250	.113	.102	.156	.133	.054	.045	.071	.054
10	0.1900	.313	.292	.130	.118	.180	.156	.060	.050	.083	.064
12	0.2160	.357	.334	.148	.134	.205	.178	.067	.056	.094	.074
1/4	0.2500	.414	.389	.170	.155	.237	.207	.075	.064	.109	.087
5/16	0.3125	.518	.490	.211	.194	.295	.262	.084	.072	.137	.110
3/8	0.3750	.622	.590	.253	.233	.355	.315	.094	.081	.164	.133
7/16	0.4375	.625	.589	.265	.242	.368	.321	.094	.081	.170	.135
1/2	0.5000	.750	.710	.297	.273	.412	.362	.106	.091	.190	.151
9/16	0.5625	.812	.768	.336	.308	.466	.410	.118	.102	.214	.172
5/8	0.6250	.875	.827	.375	.345	.521	.461	.133	.116	.240	.193
3/4	0.7500	1.000	.945	.441	.406	.612	.542	.149	.131	.281	.226

SLOTTED DRILLED FILLISTER HEAD TYPE													
Nominal Size[1] or Basic Screw Dia.		Head Dia., *A*		Head Side Height, *H*		Total Head Height, *O*		Slot Width, *J*		Slot Depth, *T*		Drilled Hole Locat., *E*	Drilled Hole. Dia., *F*
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Basic	Basic
2	0.0860	.140	.124	.062	.055	.083	.070	.031	.023	.030	.022	.026	.031
3	0.0990	.161	.145	.070	.064	.095	.082	.035	.027	.034	.026	.030	.037
4	0.1120	.183	.166	.079	.072	.107	.094	.039	.031	.038	.030	.035	.037
5	0.1250	.205	.187	.088	.081	.120	.106	.043	.035	.042	.033	.038	.046
6	0.1380	.226	.208	.096	.089	.132	.118	.048	.039	.045	.035	.043	.046
8	0.1640	.270	.250	.113	.106	.156	.141	.054	.045	.065	.054	.043	.046
10	0.1900	.313	.292	.130	.123	.180	.165	.060	.050	.075	.064	.043	.046
12	0.2160	.357	.334	.148	.139	.205	.188	.067	.056	.087	.074	.053	.046
1/4	0.2500	.414	.389	.170	.161	.237	.219	.075	.064	.102	.087	.062	.062
5/16	0.3125	.518	.490	.211	.201	.295	.276	.084	.072	.130	.110	.078	.070
3/8	0.3750	.622	.590	.253	.242	.355	.333	.094	.081	.154	.134	.094	.070

All dimensions are in inches.

[1]Where specifying nominal size in decimals, zeros preceding decimal points and in the fourth decimal place are omitted.

[2]Drilled hole shall be approximately perpendicular to the axis of slot and may be permitted to break through bottom of the slot. Edges of the hole shall be free from burrs.

[3]A slight rounding of the edges at periphery of head is permissible provided the diameter of the bearing circle is equal to no less than 90 per cent of the specified minimum head diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Slotted Oval Countersunk Head Machine Screws *ANSI B18.6.3-1972 (R1991)*



Nominal Size[a] or Basic Screw Dia.		Max *L*[b]	Head Dia., *A*		Head Side Height, *H*,	Total Head Height, *O*		Slot Width, *J*		Slot Depth, *T*	
			Max., Edge Sharp	Min., Edge Rnded. or Flat	Ref.	Max.	Min.	Max.	Min.	Max.	Min.
00	0.0470	…	.093	.085	.028	.042	.034	.017	.010	.023	.016
0	0.0600	1/8	.119	.099	.035	.056	.041	.023	.016	.030	.025
1	0.0730	1/8	.146	.123	.043	.068	.052	.026	.019	.038	.031
2	0.0860	1/8	.172	.147	.051	.080	.063	.031	.023	.045	.037
3	0.0990	1/8	.199	.171	.059	.092	.073	.035	.027	.052	.043
4	0.1120	3/16	.225	.195	.067	.104	.084	.039	.031	.059	.049
5	0.1250	3/16	.252	.220	.075	.116	.095	.043	.035	.067	.055
6	0.1380	3/16	.279	.244	.083	.128	.105	.048	.039	.074	.060
8	0.1640	1/4	.332	.292	.100	.152	.126	.054	.045	.088	.072
10	0.1900	5/16	.385	.340	.116	.176	.148	.060	.050	.103	.084
12	0.2160	3/8	.438	.389	.132	.200	.169	.067	.056	.117	.096
1/4	0.2500	7/16	.507	.452	.153	.232	.197	.075	.064	.136	.112
5/16	0.3125	1/2	.635	.568	.191	.290	.249	.084	.072	.171	.141
3/8	0.3750	9/16	.762	.685	.230	.347	.300	.094	.081	.206	.170
7/16	0.4375	5/8	.812	.723	.223	.345	.295	.094	.081	.210	.174
1/2	0.5000	3/4	.875	.775	.223	.354	.299	.106	.091	.216	.176
9/16	0.5625	…	1.000	.889	.260	.410	.350	.118	.102	.250	.207
5/8	0.6250	…	1.125	1.002	.298	.467	.399	.133	.116	.285	.235
3/4	0.7500	…	1.375	1.230	.372	.578	.497	.149	.131	.353	.293

[a] When specifying nominal size in decimals, zeros preceding decimal points and in the fourth decimal place are omitted.

[b] These lengths or shorter are undercut.

All dimensions are in inches.

Table 10. American National Standard Header Points for Machine Screws before Threading *ANSI B18.6.3-1972 (R1991)*



Nom. Size	Threads per Inch	Max. *P*	Min. *P*	Max. *L*
2	56	0.057	0.050	1/2
	64	0.060	0.053	
4	40	0.074	0.065	1/2
	48	0.079	0.070	
5	40	0.086	0.076	1/2
	44	0.088	0.079	
6	32	0.090	0.080	3/4
	40	0.098	0.087	
8	32	0.114	0.102	1
	36	0.118	0.106	

Nom. Size	Threads per Inch	Max. *P*	Min. *P*	Max. *L*
10	24	0.125	0.112	1 1/4
	32	0.138	0.124	
12	24	0.149	0.134	1 3/8
	28	0.156	0.141	
1/4	20	0.170	0.153	1 1/2
	28	0.187	0.169	
5/16	18	0.221	0.200	1 1/2
	24	0.237	0.215	
3/8	16	0.270	0.244	1 1/2
	24	0.295	0.267	
7/16	14	0.316	0.287	1 1/2
	20	0.342	0.310	
1/2	13	0.367	0.333	1 1/2
	20	0.399	0.362	

All dimensions in inches. Edges of point may be rounded and end of point need not be flat nor perpendicular to shank. Machine screws normally have plain sheared ends but when specified may have header points, as shown above.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. American National Standard Slotted Binding Head and Slotted Undercut Oval Countersunk Head Machine Screws *ANSI B18.6.3-1972 (R1991)*



SLOTTED BINDING HEAD TYPE															
Nominal Size[a] or Basic Screw Dia.		Head Dia., *A*		Total Head Height, *O*		Head Oval Height, *F*		Slot Width, *J*		Slot Depth, *T*		Undercut[b] Dia., *U*		Undercut[b] Depth, *X*	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
0000	0.0210	.046	.040	.014	.009	.006	.003	.008	.004	.009	.005	…	…	…	…
000	0.0340	.073	.067	.021	.015	.008	.005	.012	.006	.013	.009	…	…	…	…
00	0.0470	.098	.090	.028	.023	.011	.007	.017	.010	.018	.012	…	…	…	…
0	0.0600	.126	.119	.032	.026	.012	.008	.023	.016	.018	.009	.098	.086	.007	.002
1	0.0730	.153	.145	.041	.035	.015	.011	.026	.019	.024	.014	.120	.105	.008	.003
2	0.0860	.181	.171	.050	.043	.018	.013	.031	.023	.030	.020	.141	.124	.010	.005
3	0.0990	.208	.197	.059	.052	.022	.016	.035	.027	.036	.025	.162	.143	.011	.006
4	0.1120	.235	.223	.068	.061	.025	.018	.039	.031	.042	.030	.184	.161	.012	.007
5	0.1250	.263	.249	.078	.069	.029	.021	.043	.035	.048	.035	.205	.180	.014	.009
6	0.1380	.290	.275	.087	.078	.032	.024	.048	.039	.053	.040	.226	.199	.015	.010
8	0.1640	.344	.326	.105	.095	.039	.029	.054	.045	.065	.050	.269	.236	.017	.012
10	0.1900	.399	.378	.123	.112	.045	.034	.060	.050	.077	.060	.312	.274	.020	.015
12	0.2160	.454	.430	.141	.130	.052	.039	.067	.056	.089	.070	.354	.311	.023	.018
1/4	0.2500	.525	.498	.165	.152	.061	.046	.075	.064	.105	.084	.410	.360	.026	.021
5/16	0.3125	.656	.622	.209	.194	.077	.059	.084	.072	.134	.108	.513	.450	.032	.027
3/8	0.3750	.788	.746	.253	.235	.094	.071	.094	.081	.163	.132	.615	.540	.039	.034

[a] Where specifying nominal size in decimals, zeros preceding decimal points and in the fourth decimal place are omitted.

[b] Unless otherwise specified, slotted binding head machine screws are not undercut.

SLOTTED UNDERCUT OVAL COUNTERSUNK HEAD TYPES											
Nominal Size[a] or Basic Screw Dia.		Max. *L*[a]	Head Dia., *A*		Head Side Height, *H*	Total Head Height, *O*		Slot Width, *J*		Slot Depth, *T*	
			Max., Edge Sharp	Min., Edge Rnded. or Flat	Ref.	Max.	Min.	Max.	Min.	Max.	Min.
0	0.0600	1/8	.119	.099	.025	.046	.033	.023	.016	.028	.022
1	0.0730	1/8	.146	.123	.031	.056	.042	.026	.019	.034	.027
2	0.0860	1/8	.172	.147	.036	.065	.050	.031	.023	.040	.033
3	0.0990	1/8	.199	.171	.042	.075	.059	.035	.027	.047	.038
4	0.1120	3/16	.225	.195	.047	.084	.067	.039	.031	.053	.043
5	0.1250	3/16	.252	.220	.053	.094	.076	.043	.035	.059	.048
6	0.1380	3/16	.279	.244	.059	.104	.084	.048	.039	.065	.053
8	0.1640	1/4	.332	.292	.070	.123	.101	.054	.045	.078	.064
10	0.1900	5/16	.385	.340	.081	.142	.118	.060	.050	.090	.074
12	0.2160	3/8	.438	.389	.092	.161	.135	.067	.056	.103	.085
1/4	0.2500	7/16	.507	.452	.107	.186	.158	.075	.064	.119	.098
5/16	0.3125	1/2	.635	.568	.134	.232	.198	.084	.072	.149	.124
3/8	0.3750	9/16	.762	.685	.161	.278	.239	.094	.081	.179	.149
7/16	0.4375	5/8	.812	.723	.156	.279	.239	.094	.081	.184	.154
1/2	0.5000	3/4	.875	.775	.156	.288	.244	.106	.091	.204	.169

[a] These lengths or shorter are undercut.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Slotted Round Head Machine Screws
ANSI B18.6.3-1972 (R1991) Appendix



Nominal Size[a] or Basic Screw Dia.		Head Diameter, A		Head Height, H		Slot Width, J		Slot Depth, T	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
0000	0.0210	.041	.035	.022	.016	.008	.004	.017	.013
000	0.0340	.062	.056	.031	.025	.012	.008	.018	.012
00	0.0470	.089	.080	.045	.036	.017	.010	.026	.018
0	0.0600	.113	.099	.053	.043	.023	.016	.039	.029
1	0.0730	.138	.122	.061	.051	.026	.019	.044	.033
2	0.0860	.162	.146	.069	.059	.031	.023	.048	.037
3	0.0990	.187	.169	.078	.067	.035	.027	.053	.040
4	0.1120	.211	.193	.086	.075	.039	.031	.058	.044
5	0.1250	.236	.217	.095	.083	.043	.035	.063	.047
6	0.1380	.260	.240	.103	.091	.048	.039	.068	.051
8	0.1640	.309	.287	.120	.107	.054	.045	.077	.058
10	0.1900	.359	.334	.137	.123	.060	.050	.087	.065
12	0.2160	.408	.382	.153	.139	.067	.056	.096	.073
1/4	0.2500	.472	.443	.175	.160	.075	.064	.109	.082
5/16	0.3125	.590	.557	.216	.198	.084	.072	.132	.099
3/8	0.3750	.708	.670	.256	.237	.094	.081	.155	.117
7/16	0.4375	.750	.707	.328	.307	.094	.081	.196	.148
1/2	0.5000	.813	.766	.355	.332	.106	.091	.211	.159
9/16	0.5625	.938	.887	.410	.385	.118	.102	.242	.183
5/8	0.6250	1.000	.944	.438	.411	.133	.116	.258	.195
3/4	0.7500	1.250	1.185	.547	.516	.149	.131	.320	.242

[a] When specifying nominal size in decimals, zeros preceding decimal point and in the fourth decimal place are omitted.

All dimensions are in inches.

Not recommended, use Pan Head machine screws.

ANSI Cross References for Machine Screws and Metric Machine Screw



Type I Cross Recess | Type IA Cross Recess | Type II Cross Recess | Type III Square Center

Machine Screw Cross Recesses.— Four cross recesses, Types I, IA, II, and III, may be used in lieu of slots in machine screw heads. Dimensions for recess diameter *M*, width *N*, and depth *T* (not shown above) together with recess penetration gaging depths are given in American National Standard ANSI B18.6.3-1972 (R1991) for machine screws, and in ANSI/ASME B18.6.7M-1985 for metric machine screws.

American National Standard Metric Machine Screws.— This Standard B18.6.7M covers metric flat and oval countersunk and slotted and recessed pan head machine screws and metric hex head and hex flange head machine screws. Dimensions are given in Tables 1 through 4 and 6.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard Thread Lengths for Metric Machine Screws
ANSI/ASME B18.6.7M-1985



Pan, Hex, and Hex Flange Head Screws



Flat and Oval Countersunk Head Screws



Heat-Treated Recessed Flat Countersunk Head Screws

Nominal Screw Size and Thread Pitch	L	L_{US}	L_U	L		L_{US}	L_UL	L	B
	Nominal Screw Length Equal to or Shorter than[a]	Unthreaded Length[b]		Nominal Screw Length[a]		Unthreaded Length[b]		Nominal Screw Length Longer than[a]	Full Form Thread Length[c]
		Max[d]	Max[e]	Over	To and Including	Max[d]	Max[e]		Min
M2 × 0.4	6	1.0	0.4	6	30	1.0	0.8	30	25.0
M2.5 × 0.45	8	1.1	0.5	8	30	1.1	0.9	30	25.0
M3 × 0.5	9	1.2	0.5	9	30	1.2	1.0	30	25.0
M3.5 × 0.6	10	1.5	0.6	10	50	1.5	1.2	50	38.0
M4 × 0.7	12	1.8	0.7	12	50	1.8	1.4	50	38.0
M5 × 0.8	15	2.0	0.8	15	50	2.0	1.6	50	38.0
M6 × 1	18	2.5	1.0	18	50	2.5	2.0	50	38.0
M8 × 1.25	24	3.1	1.2	24	50	3.1	2.5	50	38.0
M10 × 1.5	30	3.8	1.5	30	50	3.8	3.0	50	38.0
M12 × 1.75	36	4.4	1.8	36	50	4.4	3.5	50	38.0

[a] The length tolerances for metric machine screws are: up to 3 mm, incl., ± 0.2 mm; over 3 to 10 mm, incl., ± 0.3 mm; over 10 to 16 mm, incl., ± 0.4 mm; over 16 to 50 mm, incl., ± 0.5 mm; over 50 mm, ± 1.0 mm.

[b] Unthreaded lengths L_U and L_{US} represent the distance, measured parallel to the axis of screw, from the underside of the head to the face of a nonchamfered or noncounterbored standard GO thread ring gage assembled by hand as far as the thread will permit.

[c] Refer to the illustrations for respective screw head styles.

[d] The L_{US} values apply only to heat treated recessed flat countersunk head screws.

[e] The L_U values apply to all screws except heat treated recessed flat countersunk head screws.

All dimensions in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Slotted, Cross and Square Recessed Flat Countersunk Head Metric Machine Screws

ANSI/ASME B18.6.7M-1985



Nominal Screw Size and Thread Pitch	Slotted and Style A		Style B															
	D_S		D_{SH}[a]		D_S	L_{SH}[a]		D_K			K	R		N		T	
	Body Diameter		Body and Shoulder Diameter	Shoulder Diameter	Body Diameter	Shoulder Length		Head Diameter			Head Height	Underhead Fillet Radius		Slot Width		Slot Depth	
								Theoretical Sharp		Actual							
	Max	Min	Max	Min	Min	Max	Min	Max	Min	Min	Max Ref	Max	Min	Max	Min	Max	Min
M2 × 0.4[b]	2.00	1.65	2.00	1.86	1.65	0.50	0.30	4.4	4.1	3.5	1.2	0.8	0.4	0.7	0.5	0.6	0.4
M2.5 × 0.45	2.50	2.12	2.50	2.36	2.12	0.55	0.35	5.5	5.1	4.4	1.5	1.0	0.5	0.8	0.6	0.7	0.5
M3 × 0.5	3.00	2.58	3.00	2.86	2.58	0.60	0.40	6.3	5.9	5.2	1.7	1.2	0.6	1.0	0.8	0.9	0.6
M3.5 × 0.6	3.50	3.00	3.50	3.32	3.00	0.70	0.50	8.2	7.7	6.9	2.3	1.4	0.7	1.2	1.0	1.2	0.9
M4 × 0.7	4.00	3.43	4.00	3.82	3.43	0.80	0.60	9.4	8.9	8.0	2.7	1.6	0.8	1.5	1.2	1.3	1.0
M5 × 0.8	5.00	4.36	5.00	4.82	4.36	0.90	0.70	10.4	9.8	8.9	2.7	2.0	1.0	1.5	1.2	1.4	1.1
M6 × 1	6.00	5.21	6.00	5.82	5.21	1.10	0.90	12.6	11.9	10.9	3.3	2.4	1.2	1.9	1.6	1.6	1.2
M8 × 1.25	8.00	7.04	8.00	7.78	7.04	1.40	1.10	17.3	16.5	15.4	4.6	3.2	1.6	2.3	2.0	2.3	1.8
M10 × 1.5	10.00	8.86	10.00	9.78	8.86	1.70	1.30	20.0	19.2	17.8	5.0	4.0	2.0	2.8	2.5	2.6	2.0

[a] All recessed head heat-treated steel screws of property class 9.8 or higher strength have the Style B head form. Recessed head screws other than those specifically designated to be Style B have the Style A head form. The underhead shoulder on the Style B head form is mandatory and all other head dimensions are common to both the Style A and Style B head forms.

[b] This size is not specified for Type III square recessed flat countersunk heads; Type II cross recess is not specified for any size.

All dimensions in millimeters.

For dimension *B*, see Table 1.

For dimension *L*, see Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Slotted, Cross and Square Recessed Oval Countersunk Head Metric Machine Screws
ANSI/ASME B18.6.7M-1985



Nominal Screw Size and Thread Pitch	D_S		D_K			K	F	R_F	R		N		T	
	Body Diameter		Head Diameter			Head Side Height	Raised Head Height	Head Top Radius	Underhead Fillet Radius		Slot Width		Slot Depth	
			Theoretical Sharp		Actual									
	Max	Min	Max	Min	Min	Max Ref	Max	Approx	Max	Min	Max	Min	Max	Min
M2 × 0.4[a]	2.00	1.65	4.4	4.1	3.5	1.2	0.5	5.0	0.8	0.4	0.7	0.5	1.0	0.8
M2.5 × 0.45	2.50	2.12	5.5	5.1	4.4	1.5	0.6	6.6	1.0	0.5	0.8	0.6	1.2	1.0
M3 × 0.5	3.00	2.58	6.3	5.9	5.2	1.7	0.7	7.4	1.2	0.6	1.0	0.8	1.5	1.2
M3.5 × 0.6	3.50	3.00	8.2	7.7	6.9	2.3	0.8	10.9	1.4	0.7	1.2	1.0	1.7	1.4
M4 × 0.7	4.00	3.43	9.4	8.9	8.0	2.7	1.0	11.6	1.6	0.8	1.5	1.2	1.9	1.6
M5 × 0.8	5.00	4.36	10.4	9.8	8.9	2.7	1.2	11.9	2.0	1.0	1.5	1.2	2.4	2.0
M6 × 1	6.00	5.21	12.6	11.9	10.9	3.3	1.4	14.9	2.4	1.2	1.9	1.6	2.8	2.4
M8 × 1.25	8.00	7.04	17.3	16.5	15.4	4.6	2.0	19.7	3.2	1.6	2.3	2.0	3.7	3.2
M10 × 1.5	10.00	8.86	20.0	19.2	17.8	5.0	2.3	22.9	4.0	2.0	2.8	2.5	4.4	3.8

[a] This size is not specified for Type III square recessed oval countersunk heads; Type II cross recess is not specified for any size.

All dimensions in millimeters.
For dimension *B*, see Table 1.
For dimension *L*, see Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Slotted and Cross and Square Recessed Pan Head Metric Machine Screws

ANSI/ASME B18.6.7M-1985



Nominal Screw Size and Thread Pitch	D_s		D_K		Slotted			Cross and Square Recess			D_A	R	N		T	W
					K		R_1	K		R_1	Underhead Fillet					
	Body Diameter		Head Diameter		Head Height		Head Radius	Head Height		Head Radius	Transition Dia	Radius	Slot Width		Slot Depth	Unslotted Head Thickness
	Max	Min	Max	Min	Max	Min	Max	Max	Min	Ref	Max	Min	Max	Min	Min	Min
M2 × 0.4[a]	2.00	1.65	4.0	3.7	1.3	1.1	0.8	1.6	1.4	3.2	2.6	0.1	0.7	0.5	0.5	0.4
M2.5 × 0.45	2.50	2.12	5.0	4.7	1.5	1.3	1.0	2.1	1.9	4.0	3.1	0.1	0.8	0.6	0.6	0.5
M3 × 0.5	3.00	2.58	5.6	5.3	1.8	1.6	1.2	2.4	2.2	5.0	3.6	0.1	1.0	0.8	0.7	0.7
M3.5 × 0.6	3.50	3.00	7.0	6.6	2.1	1.9	1.4	2.6	2.3	6.0	4.1	0.1	1.2	1.0	0.8	0.8
M4 × 0.7	4.00	3.43	8.0	7.6	2.4	2.2	1.6	3.1	2.8	6.5	4.7	0.2	1.5	1.2	1.0	0.9
M5 × 0.8	5.00	4.36	9.5	9.1	3.0	2.7	2.0	3.7	3.4	8.0	5.7	0.2	1.5	1.2	1.2	1.2
M6 × 1	6.00	5.21	12.0	11.5	3.6	3.3	2.5	4.6	4.3	10.0	6.8	0.3	1.9	1.6	1.4	1.4
M8 × 1.25	8.00	7.04	16.0	15.5	4.8	4.5	3.2	6.0	5.6	13.0	9.2	0.4	2.3	2.0	1.9	1.9
M10 × 1.5	10.00	8.86	20.0	19.4	6.0	5.7	4.0	7.5	7.1	16.0	11.2	0.4	2.8	2.5	2.4	2.4

[a] This size not specified for Type III square recessed pan heads; Type II cross recess is not specified for any size.

All dimensions in millimeters.

For dimension *B*, see Table 1.

For dimension *L*, see Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Header Points for Metric Machine Screws Before Threading *ANSI/ASME B18.6.7M-1985*



Nominal Screw Size and Thread Pitch	D_P Point Diameter		L^a Nominal Screw Length
	Max	Min	Max
M2 × 0.4	1.33	1.21	13
M2.5 × 0.45	1.73	1.57	13
M3 × 0.5	2.12	1.93	16
M3.5 × 0.6	2.46	2.24	20
M4 × 0.7	2.80	2.55	25
M5 × 0.8	3.60	3.28	30
M6 × 1	4.25	3.85	40
M8 × 1.25	5.82	5.30	40
M10 × 1.5	7.36	6.71	40
M12 × 1.75	8.90	8.11	45

[a] Header points apply to these nominal lengths or shorter. The pointing of longer lengths may require machining to the dimensions specified.

All dimensions in millimeters.

The edge of the point may be rounded and the end of point need not be flat nor perpendicular to the axis of screw shank.

Threads: Threads for metric machine screws are coarse M profile threads, as given in ANSI B1.13M (see page 1783), unless otherwise specified.

Length of Thread: The lengths of threads on metric machine screws are given in Table 1 for the applicable screw type, size, and length.

Diameter of Body: The body diameters of metric machine screws are within the limits specified in the dimensional tables (Tables 3 through 4 and 6).

Designation: Metric machine screws are designated by the following data in the sequence shown: Nominal size and thread pitch; nominal length; product name, including head type and driving provision; header point if desired; material (including property class, if steel); and protective finish, if required. For example:

M8 × 1.25 × 30 Slotted Pan Head Machine Screw, Class 4.8 Steel, Zinc Plated

M3.5 × 0.6 × 20 Type IA Cross Recessed Oval Countersunk Head Machine Screw, Header Point, Brass

It is common ISO practice to omit the thread pitch from the product size designation when screw threads are the metric coarse thread series, e.g., M10 stands for M10 × 1.5.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Hex and Hex Flange Head Metric Machine Screws *ANSI/ASME B18.6.7M-1985*

Hex Head



Nominal Screw Size and Thread Pitch	D_S Body Diameter		S^a Hex Width Across Flats		E^a Hex Width Across Corners	K Head Height		D_A Underhead Fillet Transition Dia	R Underhead Fillet Radius
	Max	Min	Max	Min	Min	Max	Min	Max	Min
M2 × 0.4	2.00	1.65	3.20	3.02	3.38	1.6	1.3	2.6	0.1
M2.5 × 0.45	2.50	2.12	4.00	3.82	4.28	2.1	1.8	3.1	0.1
M3 × 0.5	3.00	2.58	5.00	4.82	5.40	2.3	2.0	3.6	0.1
M3.5 × 0.6	3.50	3.00	5.50	5.32	5.96	2.6	2.3	4.1	0.1
M4 × 0.7	4.00	3.43	7.00	6.78	7.59	3.0	2.6	4.7	0.2
M5 × 0.8	5.00	4.36	8.00	7.78	8.71	3.8	3.3	5.7	0.2
M6 × 1	6.00	5.21	10.00	9.78	10.95	4.7	4.1	6.8	0.3
M8 × 1.25	8.00	7.04	13.00	12.73	14.26	6.0	5.2	9.2	0.4
M10 × 1.5	10.00	8.86	16.00	15.73	17.62	7.5	6.5	11.2	0.4
M12 × 1.75	12.00	10.68	18.00	17.73	19.86	9.0	7.8	13.2	0.4
M10 × 1.5[b]	10.00	8.86	15.00	14.73	16.50	7.5	6.5	11.2	0.4

[a] Dimensions across flats and across corners of the head are measured at the point of maximum metal. Taper of sides of head (angle between one side and the axis) shall not exceed 2° or 0.10 mm, whichever is greater, the specified width across flats being the large dimension.

[b] The M10 size screws having heads with 15 mm width across flats are not ISO Standard. Unless M10 size screws with 15 mm width across flats are specifically ordered, M10 size screws with 16 mm width across flats shall be furnished.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ***(Continued)*** **American National Standard Hex and Hex Flange Head Metric Machine Screws ANSI/ASME B18.6.7M-1985**

Hex Flange Head



Nominal Screw Size and Thread Pitch	Body Diameter, D_S		Hex Width Across Flats, S[a]		Hex Width Across Corners, E[a]	Flange Diameter, D_C		Overall Head Height, K	Hex Height, K_1	Flange Edge Thickness, C[b]	Flange Top Fillet Radius, R_1	Underhead Fillet	
	Max	Min	Max	Min	Min	Max	Min		Min,	Min	Max	Max Transition Dia, D_A	Min Radius, R
M2 × 0.4	2.00	1.65	3.00	2.84	3.16	4.5	4.1	2.2	1.3	0.3	0.1	2.6	0.1
M2.5 × 0.45	2.50	2.12	3.20	3.04	3.39	5.4	5.0	2.7	1.6	0.3	0.2	3.1	0.1
M3 × 0.5	3.00	2.58	4.00	3.84	4.27	6.4	5.9	3.2	1.9	0.4	0.2	3.6	0.1
M3.5 × 0.6	3.50	3.00	5.00	4.82	5.36	7.5	6.9	3.8	2.4	0.5	0.2	4.1	0.1
M4 × 0.7	4.00	3.43	5.50	5.32	5.92	8.5	7.8	4.3	2.8	0.6	0.2	4.7	0.2
M5 × 0.8	5.00	4.36	7.00	6.78	7.55	10.6	9.8	5.4	3.5	0.7	0.3	5.7	0.2
M6 × 1	6.00	5.21	8.00	7.78	8.66	12.8	11.8	6.7	4.2	1.0	0.4	6.8	0.3
M8 × 1.25	8.00	7.04	10.00	9.78	10.89	16.8	15.5	8.6	5.6	1.2	0.5	9.2	0.4
M10 × 1.5	10.00	8.86	13.00	12.72	14.16	21.0	19.3	10.7	7.0	1.4	0.6	11.2	0.4
M12 × 1.75	12.00	10.68	15.00	14.72	16.38	24.8	23.3	13.7	8.4	1.8	0.7	13.2	0.4

[a] Dimensions across flats and across corners of the head are measured at the point of maximum metal. Taper of sides of head (angle between one side and the axis) shall not exceed 2° or 0.10 mm, whichever is greater, the specified width across flats being the large dimension.

[b] The contour of the edge at periphery of flange is optional provided the minimum flange thickness is maintained at the minimum flange diameter. The top surface of flange may be straight or slightly rounded (convex) upward.

All dimensions in millimeters.

A slight rounding of all edges of the hexagon surfaces of indented hex heads is permissible provided the diameter of the bearing circle is not less than the equivalent of 90 per cent of the specified minimum width across flats dimension.

Heads may be indented, trimmed, or fully upset at the option of the manufacturer.

For dimension *B*, see Table 1.

For dimension *L*, see Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Recommended Nominal Screw Lengths for Metric Machine Screws

Nominal Screw Length	Nominal Screw Size									
	M2	M2.5	M3	M3.5	M4	M5	M6	M8	M10	M12
2.5	PH									
3	A	PH								
4	A	A	PH							
5	A	A	A	PH	PH					
6	A	A	A	A	A	PH				
8	A	A	A	A	A	A	A			
10	A	A	A	A	A	A	A	A		
13	A	A	A	A	A	A	A	A	A	
16	A	A	A	A	A	A	A	A	A	H
20	A	A	A	A	A	A	A	A	A	H
25		A	A	A	A	A	A	A	A	H
30			A	A	A	A	A	A	A	H
35				A	A	A	A	A	A	H
40					A	A	A	A	A	H
45						A	A	A	A	H
50						A	A	A	A	H
55							A	A	A	H
60							A	A	A	H
65								A	A	H
70								A	A	H
80								A	A	H
90									A	H

All dimensions in millimeters.

[1]The nominal screw lengths included between the heavy lines are recommended for the respective screw sizes and screw head styles as designated by the symbols.

A — Signifies screws of all head styles covered in this standard.

P — Signifies pan head screws.

H — Signifies hex and hex flange head screws.

Table 8. Clearance Holes for Metric Machine Screws
ANSI/ASME B18.6.7M-1985 **Appendix**

Nominal Screw Size	Basic Clearance Hole Diameter[a]		
	Close Clearance[b]	Normal Clearance (Preferred)[b]	Loose Clearance[b]
M2	2.20	2.40	2.60
M2.5	2.70	2.90	3.10
M3	3.20	3.40	3.60
M3.5	3.70	3.90	4.20
M4	4.30	4.50	4.80
M5	5.30	5.50	5.80
M6	6.40	6.60	7.00
M8	8.40	9.00	10.00
M10	10.50	11.00	12.00
M12	13.00	13.50	14.50

[a] The values given in this table are minimum limits. The recommended plus tolerances are as follows: for clearance hole diameters over 1.70 to and including 5.80 mm, plus 0.12, 0.20, and 0.30 mm for close, normal, and loose clearances, respectively; for clearance hole diameters over 5.80 to 14.50 mm, plus 0.18, 0.30, and 0.45 mm for close, normal, and loose clearances, respectively.

[b] Normal clearance hole sizes are preferred. Close clearance hole sizes are for situations such as critical alignment of assembled components, wall thickness, or other limitations which necessitate the use of a minimal hole. Countersinking or counterboring at the fastener entry side may be necessary for the proper seating of the head. Loose clearance hole sizes are for applications where maximum adjustment capability between the components being assembled is necessary.

All dimensions in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

British Machine Screws.— Many of these classifications of fasteners are covered in British Standards B.S. 57:1951, "B.A. Screws, Bolts and Nuts"; BS 450:1958 (obsolescent), "Machine Screws and Machine Screw Nuts (BSW and BSF Threads)"; B.S. 1981:1953, "Unified Machine Screws and Machine Screw Nuts"; BS 2827:1957 (obsolescent):1957, "Machine Screw Nuts, Pressed Type (B.A. and Whitworth Form Threads)"; B.S. 3155:1960, "American Machine Screws and Nuts in Sizes Below ¼ inch Diameter"; and BS 4183:1967 (obsolescent), "Machine Screws and Machine Screw Nuts, Metric Series." At a conference organized by the British Standards Institution in 1965 at which the major sectors of British industry were represented, a policy statement was approved that urged British firms to regard the traditional screw thread systems—Whitworth, B.A. and BSF—as obsolescent, and to make the internationally-agreed ISO metric thread their first choice (with ISO Unified thread as second choice) for all future designs. It is recognized that some sections of British industry already using ISO inch (Unified) screw threads may find it necessary, for various reasons, to continue with their use for some time: Whitworth and B.A. threads should, however, be superseded by ISO metric threads in preference to an intermediate change to ISO inch threads. Fasteners covered by B.S. 57, B.S. 450 and BS 2827:1957 (obsolescent) eventually would be superseded and replaced by fasteners specified by B.S. 4183.

British Standard Whitworth (BSW) and Fine (BSF) Machine Screws.— British Standard BS 450:1958 (obsolescent) covers machine screws and nuts with British Standard Whit-worth and British Standard Fine threads. All the various heads in common use in both slotted and recessed forms are covered. Head shapes are shown on page 1614 and dimensions on page 1617. It is intended that this standard will eventually be superseded by B.S. 4183, "Machine Screws and Machine Screw Nuts, Metric Series."

British Standard Machine Screws and Machine Screw Nuts, Metric Series.— British Standard BS 4183:1967 (obsolescent) gives dimensions and tolerances for: countersunk head, raised countersunk head, and cheese head slotted head screws in a diameter range from M1 (1 mm) to M20 (20 mm); pan head slotted head screws in a diameter range from M2.5 (2.5 mm) to M10 (10 mm); countersunk head and raised countersunk head recessed head screws in a diameter range from M2.5 (2.5 mm) to M12 (12 mm); pan head recessed head screws in a diameter range from M2.5 (2.5 mm) to M10 (10 mm); and square and hexagon machine screw nuts in a diameter range from M1.6 (1.6 mm) to M10 (10 mm). Mechanical properties are also specified for steel, brass and aluminum alloy machine screws and machine screw nuts in this standard.

Material: The materials from which the screws and nuts are manufactured have a tensile strength not less than the following: steel, 40 kgf/mm^2 (392 N/mm^2); brass, 32 kgf/mm^2 (314 N/mm^2); and aluminum alloy, 32 kgf/mm^2 (314 N/mm^2). The unit, kgf/mm^2 is in accordance with ISO DR 911 and the unit in parentheses has the relationship, 1 kgf = 9.80665 Newtons. These minimum strengths are applicable to the finished products. Steel machine screws conform to the requirements for strength grade designation 4.8. The strength grade designation system for machine screws consists of two figures, the first is $\frac{1}{10}$ of the minimum tensile strength in kgf/mm^2, the second is $\frac{1}{10}$ of the ratio between the yield stress and the minimum tensile strength expressed as a percentage: $\frac{1}{10}$ minimum tensile strength of 40 kgf/mm^2 gives the symbol "4"; $\frac{1}{10}$ ratio $\frac{\text{yield stress}}{\text{minimum tensile strength}}\% = \frac{1}{10} \times \frac{32}{40} \times 100/1 =$ "8"; giving the strength grade designation "4.8." Multiplication of these two figures gives the minimum yield stress in kgf/mm^2.

Coating of Screws and Nuts: It is recommended that the coating comply with the appropriate part of BS 3382. "Electroplated Coatings on Threaded Components."

Copyright 2004, Industrial Press, Inc., New York, NY

Screw Threads: Screw threads are ISO metric coarse pitch series threads in accordance with B.S. 3643. "ISO Metric Screw Threads," Part 1, "Thread Data and Standard Thread Series." The external threads used for screws conform to tolerance Class 6g limits (medium fit) as given in B.S. 3643, "ISO Metric Screw Threads," Part 2, "Limits and Tolerances for Coarse Pitch Series Threads." The internal threads used for nuts conform to tolerance Class 6H limits (medium fit) as given in B.S. 3643: Part 2.

Nominal Lengths of Screws: For countersunk head screws the nominal length is the distance from the upper surface of the head to the extreme end of the shank, including any chamfer, radius, or cone point. For raised countersunk head screws the nominal length is the distance from the upper surface of the head (excluding the raised portion) to the extreme end of the shank, including any chamfer, radius, or cone point. For pan and cheese head screws the nominal length is the distance from the underside of the head to the extreme end of the shank, including any chamfer, radius, or cone point. Standard nominal lengths and tolerances are given in Table 5.

Lengths of Thread on Screws: The length of thread is the distance from the end of the screw (including any chamfer, radius, or cone point) to the leading face of a nut without countersink which has been screwed as far as possible onto the screw by hand. The minimum thread length is shown in the following table:

Nominal Thread Dia., *d*[a]	M1	M1.2	(M1.4)	M1.6	M2	(M2.2)	M2.5	M3	(M3.5)	M4
Thread Length *b* (Min.)	[b]	[b]	[b]	15	16	17	18	19	20	22
Nominal Thread Dia., *d*[a]	(M4.5)	M5	M6	M8	M10	M12	(M14)	M16	(M18)	M20
Thread Length *b* (Min.)	24	25	28	34	40	46	52	58	64	70

[a] Items shown in parentheses are non-preferred.

[b] Threaded up to the head.

All dimensions are in millimeters.

Screws of nominal thread diameter M1, M1.2 and M1.4 and screws of larger diameters that are too short for the above thread lengths are threaded as far as possible up to the head.

In these screws the length of unthreaded shank under the head does not exceed $1\frac{1}{2}$ pitches for lengths up to twice the diameter and 2 pitches for longer lengths, and is defined as the distance from the leading face of a nut that has been screwed as far as possible onto the screw by hand to: 1) the junction of the basic major diameter and the countersunk portion of the head on countersunk and raised countersunk heads; and 2) the underside of the head on other types of heads.

Diameter of Unthreaded Shank on Screws: The diameter of the unthreaded portion of the shank on screws is not greater than the basic major diameter of the screw thread and not less than the minimum effective diameter of the screw thread. The diameter of the unthreaded portion of shank is closely associated with the method of manufacture; it will generally be nearer the major diameter of the thread for turned screws and nearer the effective diameter for those produced by cold heading.

Radius Under the Head of Screws: The radius under the head of pan and cheese head screws runs smoothly into the face of the head and shank without any step or discontinuity. A true radius is not essential providing that the curve is smooth and lies wholly within the maximum radius. Any radius under the head of countersunk head screws runs smoothly into the conical bearing surface of the head and the shank without any step or discontinuity. The radius values given in Tables 1 and 2 are regarded as the maximum where the shank diameter is equal to the major diameter of the thread and minimum where the shank diameter is approximately equal to the effective diameter of the thread.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. British Standard Slotted Countersunk Head Machine Screws—Metric Series *BS 4183:1967 (obsolescent)*

Nominal Size d[a]	Head Diameter D		Head Height k		Radius r[b]	Thread Length b	Thread Run-out a	Flushness Tolerance[c]	Slot Width n		Slot Depth t	
	Max. (Theor. Sharp) $2d$	Min. $1.75d$	Max. $0.5d$	Min. $0.45d$		Min.	Max. $2p$[d]	Max.	Max.	Min.	Max. $0.3d$	Min. $0.2d$
M1	2.00	1.75	0.50	0.45	0.1	[e]	0.50	....	0.45	0.31	0.30	0.20
M1.2	2.40	2.10	0.60	0.54	0.1	[e]	0.50	....	0.50	0.36	0.36	0.24
(M1.4)	2.80	2.45	0.70	0.63	0.1	[e]	0.60	....	0.50	0.36	0.42	0.28
M1.6	3.20	2.80	0.80	0.72	0.1	15.0	0.70	....	0.60	0.46	0.48	0.32
M2.0	4.00	3.50	1.00	0.90	0.1	16.0	0.80	....	0.70	0.56	0.60	0.40
(M2.2)	4.40	3.85	1.10	0.99	0.1	17.0	0.90	....	0.80	0.66	0.66	0.44
M2.5	5.00	4.38	1.25	1.12	0.1	18.0	0.90	0.10	0.80	0.66	0.75	0.50
M3	6.00	5.25	1.50	1.35	0.1	19.0	1.00	0.12	1.00	0.86	0.90	0.60
(M3.5)	7.00	6.10	1.75	1.57	0.2	20.0	1.20	0.13	1.00	0.86	1.05	0.70
M4	8.00	7.00	2.00	1.80	0.2	22.0	1.40	0.15	1.20	1.06	1.20	0.80
(M4.5)	9.00	7.85	2.25	2.03	0.2	24.0	1.50	0.17	1.20	1.06	1.35	0.90
M5	10.00	8.75	2.50	2.25	0.2	25.0	1.60	0.19	1.51	1.26	1.50	1.00
M6	12.00	10.50	3.00	2.70	0.25	28.0	2.00	0.23	1.91	1.66	1.80	1.20
M8	16.00	14.00	4.00	3.60	0.4	34.0	2.50	0.29	2.31	2.06	2.40	1.60
M10	20.00	17.50	5.00	4.50	0.4	40.0	3.00	0.37	2.81	2.56	3.00	2.00
M12	24.00	21.00	6.00	5.40	0.6	46.0	3.50	0.44	3.31	3.06	3.60	2.40
(M14)	28.00	24.50	7.00	6.30	0.6	52.0	4.00	0.52	3.31	3.06	4.20	2.80
M16	32.00	28.00	8.00	7.20	0.6	58.0	4.00	0.60	4.37	4.07	4.80	3.20
(M18)	36.00	31.50	9.00	8.10	0.6	64.0	5.00	0.67	4.37	4.07	5.40	3.60
M20	40.00	35.00	10.00	9.00	0.8	70.0	5.00	0.75	5.37	5.07	6.00	4.00

[a] Nominal sizes shown in parentheses are non-preferred.
[b] See *Radius Under the Head of Screws* description in text.
[c] See *Dimensions of 90-Degree Countersunk Head Screws* description in text.
[d] See text following table in *Lengths of Thread on Screws* description in text.
[e] Threaded up to head.

All dimensions are given in millimeters. For dimensional notation, see diagram on page 1610. Recessed head screws are also standard and are available. For dimensions see British Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. British Standard Slotted Raised Countersunk Head Machine Screws—Metric Series *BS 4183:1967 (obsolescent)*

Nominal Size *d*[a]	Head Diameter *D*		Head Height *k*		Radius Under Head *r*[b]	Thread Length *b*	Thread Run-out *a*	Height of Raised Portion *f*	Head Radius *R*	Slot Width *n*		Slot Depth *t*	
	Max. (Theor. Sharp) 2*d*	Min. 1.75*d*	Max. 0.5*d*	Min. 0.45*d*		Min.	Max. 2*p*[c]	Nom. 0.25*d*	Nom.	Max.	Min.	Max. 0.5*d*	Min. 0.4*d*
M1	2.00	1.75	0.50	0.45	0.1	[d]	0.50	0.25	2.0	0.45	0.31	0.50	0.40
M1.2	2.40	2.10	0.60	0.54	0.1	[d]	0.50	0.30	2.5	0.50	0.36	0.60	0.48
(M1.4)	2.80	2.45	0.70	0.63	0.1	[d]	0.60	0.35	2.5	0.50	0.36	0.70	0.56
M1.6	3.20	2.80	0.80	0.72	0.1	15.0	0.70	0.40	3.0	0.60	0.46	0.80	0.64
M2.0	4.00	3.50	1.00	0.90	0.1	16.0	0.80	0.50	4.0	0.70	0.56	1.00	0.80
(M2.2)	4.40	3.85	1.10	0.99	0.1	17.0	0.90	0.55	4.0	0.80	0.66	1.10	0.88
M2.5	5.00	4.38	1.25	1.12	0.1	18.0	0.90	0.60	5.0	0.80	0.66	1.25	1.00
M3	6.00	5.25	1.50	1.35	0.1	19.0	1.00	0.75	6.0	1.00	0.86	1.50	1.20
(M3.5)	7.00	6.10	1.75	1.57	0.2	20.0	1.20	0.90	6.0	1.00	0.86	1.75	1.40
M4	8.00	7.00	2.00	1.80	0.2	22.0	1.40	1.00	8.0	1.20	1.06	2.00	1.60
(M4.5)	9.00	7.85	2.25	2.03	0.2	24.0	1.50	1.10	8.0	1.20	1.06	2.25	1.80
M5	10.00	8.75	2.50	2.25	0.2	25.0	1.60	1.25	10.0	1.51	1.26	2.50	2.00
M6	12.00	10.50	3.00	2.70	0.25	28.0	2.00	1.50	12.0	1.91	1.66	3.00	2.40
M8	16.00	14.00	4.00	3.60	0.4	34.0	2.50	2.00	16.0	2.31	2.06	4.00	3.20
M10	20.00	17.50	5.00	4.50	0.4	40.0	3.00	2.50	20.0	2.81	2.56	5.00	4.00
M12	24.00	21.00	6.00	5.40	0.6	46.0	3.50	3.00	25.0	3.31	3.06	6.00	4.80
(M14)	28.00	24.50	7.00	6.30	0.6	52.0	4.00	3.50	25.0	3.31	3.06	7.00	5.60
M16	32.00	28.00	8.00	7.20	0.6	58.0	4.00	4.00	32.0	4.37	4.07	8.00	6.40
(M18)	36.00	31.50	9.00	8.10	0.6	64.0	5.00	4.50	32.0	4.37	4.07	9.00	7.20
M20	40.00	35.00	10.00	9.00	0.8	70.0	5.00	5.00	40.0	5.37	5.07	10.00	8.00

[a] Nominal sizes shown in parentheses are non-preferred.
[b] See *Radius Under the Head of Screws* description in text.
[c] See text following table in *Lengths of Thread on Screws* description in text.
[d] Threaded up to head.

All dimensions are given in millimeters. For dimensional notation see diagram on page 1610. Recessed head screws are also standard and available. For dimensions see British Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Ends of Screws: When screws are made with rolled threads, the "lead" formed by the thread rolling operation is normally regarded as providing the necessary chamfer and no other machining is necessary. The ends of screws with cut threads are normally finished with a chamfer conforming to the dimension in Fig. 1a through Fig. 1d. At the option of the manufacturer, the ends of screws smaller than M6 (6-mm diameter) may be finished with a radius approximately equal to 1¼ times the nominal diameter of the shank. When cone point ends are required, they should have the dimensions given in Fig. 1a through Fig. 1d.



Fig. 1a. Rolled Thread End (Approximate Form as Rolled)



Fig. 1b. Chamfer to Extend to Slightly Below the Minor Dia.



Fig. 1c. Cut Thread Radiused End (Permissible on Sizes Below M6 Dia.)



Fig. 1d. Cone Pointed End (Permissible on Cut or Rolled Thread Screws, but Regarded as "Special")

Dimensions of 90-Degree Countersunk Head Screws: One of the appendices to this British Standard states that countersunk head screws should fit into the countersunk hole with as great a degree of flushness as possible. To achieve this condition, it is necessary for the dimensions of both the head of the screw and the countersunk hole to be controlled within prescribed limits. The maximum or design size of the head is controlled by a theoretical diameter to a sharp corner and the minimum head angle of 90 degrees. The minimum head size is controlled by a minimum head diameter, the maximum head angle of 92 degrees and a flushness tolerance (see Fig. 2). The edge of the head may be flat or rounded, as shown in Fig. 3.



Fig. 2. Head Configuration



Fig. 3. Edge Configuration

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Machine Screws and Machine Screw Nuts—Metric Series



Slotted Countersunk Head Machine Screws



Slotted Raised Countersunk Head Machine Screws



Slotted Pan Head Machine Screws



Slotted Cheese Head Machine Screws



Machine Screw Nuts, Pressed Type, Square and Hexagon

For dimensions, see Tables 1 through 5.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. British Standard Slotted Pan Head Machine Screws—Metric Series *BS 4183:1967 (obsolescent)*

Nominal Size d[a]	Head Diameter D		Head Height k		Head Radius R	Radius Under Head r	Transition Diameter d_a
	Max. $2d$	Min.	Max. $0.6d$	Min.	Max $0.4d$	Min.	Max.
M2.5	5.00	4.70	1.50	1.36	1.00	0.10	3.10
M3	6.00	5.70	1.80	1.66	1.20	0.10	3.60
(M3.5)	7.00	6.64	2.10	1.96	1.40	0.20	4.30
M4	8.00	7.64	2.40	2.26	1.60	0.20	4.70
(M4.5)	9.00	8.64	2.70	2.56	1.80	0.20	5.20
M5	10.00	9.64	3.00	2.86	2.00	0.20	5.70
M6	12.00	11.57	3.60	3.42	2.50	0.25	6.80
M8	16.00	15.57	4.80	4.62	3.20	0.40	9.20
M10	20.00	19.48	6.00	5.82	4.00	0.40	11.20

[a] Nominal sizes shown in parentheses are non-preferred.

Nominal Size d[a]	Thread Length b	Thread Run-out a	Slot Width n		Slot Depth t	
	Min.	Max. $2p$[b]	Max.	Min.	Max. $0.6k$	Min. $0.4k$
M2.5	18.00	0.90	0.80	0.66	0.90	0.60
M3	19.00	1.00	1.00	0.86	1.08	0.72
(M3.5)	20.00	1.20	1.00	0.86	1.26	0.84
M4	22.00	1.40	1.20	1.06	1.44	0.96
(M4.5)	24.00	1.50	1.20	1.06	1.62	1.08
M5	25.00	1.60	1.51	1.26	1.80	1.20
M6	28.00	2.00	1.91	1.66	2.16	1.44
M8	34.00	2.50	2.31	2.06	2.88	1.92
M10	40.00	3.00	2.81	2.56	3.60	2.40

[a] Nominal sizes shown in parentheses are non-preferred.

[b] See *Lengths of Thread on Screws* on page 1606.

All dimensions are in millimeters. For dimensional notation, see diagram on page 1610. Recessed head screws are also standard and available. For dimensions, see British Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. British Standard Slotted Cheese Head Machine Screws—Metric Series *BS 4183:1967 (obsolescent)*

Nominal Size d[a]	Head Diameter D		Head Height k		Radius r[b]	Transition Diameter d_a	Thread Length b	Thread Run-out a	Slot Width n		Slot Depth t	
	Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.[c]	Max.	Min.	Max.	Min.
M1	2.00	1.75	0.70	0.56	0.10	1.30	[b]	0.50	0.45	0.31	0.44	0.30
M1.2	2.30	2.05	0.80	0.66	0.10	1.50	[b]	0.50	0.50	0.36	0.49	0.35
(M1.4)	2.60	2.35	0.90	0.76	0.10	1.70	[b]	0.60	0.50	0.36	0.60	0.40
M1.6	3.00	2.75	1.00	0.86	0.10	2.00	15.00	0.70	0.60	0.46	0.65	0.45
M2	3.80	3.50	1.30	1.16	0.10	2.60	16.00	0.80	0.70	0.56	0.85	0.60
(M2.2)	4.00	3.70	1.50	1.36	0.10	2.80	17.00	0.90	0.80	0.66	1.00	0.70
M2.5	4.50	4.20	1.60	1.46	0.10	3.10	18.00	0.90	0.80	0.66	1.00	0.70
M3	5.50	5.20	2.00	1.86	0.10	3.60	19.00	1.00	1.00	0.86	1.30	0.90
(M3.5)	6.00	5.70	2.40	2.26	0.10	4.10	20.00	1.20	1.00	0.86	1.40	1.00
M4	7.00	6.64	2.60	2.46	0.20	4.70	22.00	1.40	1.20	1.06	1.60	1.20
(M4.5)	8.00	7.64	3.10	2.92	0.20	5.20	24.00	1.50	1.20	1.06	1.80	1.40
M5	8.50	8.14	3.30	3.12	0.20	5.70	25.00	1.60	1.51	1.26	2.00	1.50
M6	10.00	9.64	3.90	3.72	0.25	6.80	28.00	2.00	1.91	1.66	2.30	1.80
M8	13.00	12.57	5.00	4.82	0.40	9.20	34.00	2.50	2.31	2.06	2.80	2.30
M10	16.00	15.57	6.00	5.82	0.40	11.20	40.00	3.00	2.81	2.56	3.20	2.70
M12	18.00	17.57	7.00	6.78	0.60	14.20	46.00	3.50	3.31	3.06	3.80	3.20
(M14)	21.00	20.48	8.00	7.78	0.60	16.20	52.00	4.00	3.31	3.06	4.20	3.60
M16	24.00	23.48	9.00	8.78	0.60	18.20	58.00	4.00	4.37	4.07	4.60	4.00
(M18)	27.00	26.48	10.00	9.78	0.60	20.20	64.00	5.00	4.37	4.07	5.10	4.50
M20	30.00	29.48	11.00	10.73	0.80	22.40	70.00	5.00	5.27	5.07	5.60	5.00

[a] Nominal sizes shown in parentheses are non-preferred.
[b] Threaded up to head.
[c] See text following table in *Lengths of Thread on Screws* description in text.

All dimensions are given in millimeters. For dimensional notation, see diagram on page 1610.

General Dimensions: The general dimensions and tolerances for screws and nuts are given in the accompanying tables. Although slotted screw dimensions are given, recessed head screws are also standard and available. Dimensions of recessed head screws are given in BS 4183:1967 (obsolescent).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. British Standard Machine Screws and Nuts — Metric Series *BS 4183:1967 (obsolescent)*

Concentricity Tolerances



Nominal Size d^a	Head to Shank and Slot to Head (IT 13)	
	Countersunk, Raised Csk., and Pan Heads	Cheese Heads
M1, M1.2, (M1.4)	0.14	0.14
M1.6	0.18	0.14
M2, (M2.2), M2.5, M3	0.18	0.18
(M3.5)	0.22	0.18
M4, (M4.5), M5	0.22	0.22
M6	0.27	0.22
M8	0.27	0.27
M10, M12	0.33	0.27
(M14)	0.33	0.33
M16, (M18), M20	0.39	0.33

Nominal Lengths and Tolerances on Length for Machine Screws

Nominal Length[a]	Tolerance	Nominal Length[a]	Tolerance
1.5	±0.12	45	±0.50
2	±0.12	50	±0.060
2.5	±0.20	55	±0.60
3	±0.20	60	±0.60
4	±0.24	65	±0.60
5	±0.24	70	±0.60
6	±0.24	75	±0.60
(7)	±0.29	80	±0.60
8	±0.29	85	±0.70
(9)	±0.29	90	±0.70
10	±0.29	(95)	±0.70
(11)	±0.35	100	±0.70
12	±0.35	(105)	±0.70
14	±0.35	110	±0.70
16	±0.35	(115)	±0.70
(18)	±0.35	120	±0.70
20	±0.42	(125)	±0.70
(22)	±0.42	130	±0.80
25	±0.42	140	±0.80
(28)	±0.42	150	±0.80
30	±0.42	160	±0.80
(38)	±0.50	190	±0.925
40	±0.50	200	±0.925

Dimensions of Machine Screw Nuts, Pressed Type, Square and Hexagon

Nominal Size d^a	Width Across		
	Flats s		Corners e
	Max.	Min.	Square
M1.6	3.2	3.02	4.5
M2	4.0	3.82	5.7
(M2.2)	4.5	4.32	6.4
(M2.5)	5.0	4.82	7.1
M3	5.5	5.32	7.8
(M3.5)	6.0	5.82	8.5
M4	7.0	6.78	9.9
M5	8.0	7.78	11.3
M6	10.0	9.78	14.1
M8	13.0	12.73	18.4
M10	17.0	16.73	24.0

Nominal Size d^a	Width Across Corners e	Thickness m	
	Hexagon	Max.	Min
M1.6	3.7	1.0	0.75
M2	4.6	1.2	0.95
(M2.2)	5.2	1.2	0.95
M2.5	5.8	1.6	1.35
M3	6.4	1.6	1.35
(M3.5)	6.9	2.0	1.75
M4	8.1	2.0	1.75
M5	9.2	2.5	2.25
M6	11.5	3.0	2.75
M8	15.0	4.0	3.70
M10	19.6	5.0	4.70
M8	13.0	12.73	18.4
M10	17.0	16.73	24.0

[a] Nominal sizes and lengths shown in parentheses are non-preferred.

All dimensions are given in millimeters. For dimensional notation, see diagram on page 1610.

Copyright 2004, Industrial Press, Inc., New York, NY

British Unified Machine Screws and Nuts.— British Standard B.S. 1981:1953 covers certain types of machine screws and machine screw nuts for which agreement has been reached with the United States and Canada as to general dimensions for interchangeability. These types are: countersunk, raised-countersunk, pan, and raised-cheese head screws with slotted or recessed heads; small hexagon head screws; and precision and pressed nuts. All have Unified threads. Head shapes are shown on page 1614 and dimensions are given on page 1616.

Identification: As revised by Amendment No. 1 in February 1955, this standard now requires that the above-mentioned screws and nuts that conform to this standard should have a distinguishing feature applied to identify them as Unified. All *recessed head screws* are to be identified as Unified by a groove in the form of four arcs of a circle in the upper surface of the head. All *hexagon head screws* are to be identified as Unified by: 1) a circular recess in the upper surface of the head; 2) a continuous line of circles indented on one or more of the flats of the hexagon and parallel to the screw axis; and 3) at least two contiguous circles indented on the upper surface of the head. All *machine screw* nuts of the pressed type shall be identified as Unified by means of the application of a groove indented in one face of the nut approximately midway between the major diameter of the thread and flats of the square or hexagon. *Slotted head screws* shall be identified as Unified either by a circular recess or by a circular platform or raised portion on the upper surface of the head. *Machine screw nuts* of the *precision type* shall be identified as Unified by either a groove indented on one face of the front approximately midway between the major diameter of the thread and the flats of the hexagon or a continuous line of circles indented on one or more of the flats of the hexagon and parallel to the nut axis.



Identification Markings for British Standard Unified Machine Screws

British Standard Machine Screws and Nuts
ricc:1958 (obsolescent) and B.S. 1981:1953



80° Countersunk head screw (Unified)
90° Countersink head screw (BSW & BSF)

Round head screw (BSW & BSF)

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Machine Screws and Nuts *(Continued)*
ricc:1958 (obsolescent) and B.S. 1981:1953



80° Raised countersunk head screw (Unified)
90° Raised countersunk head screw (BSW & BSF)



Mushroom head screw (BSW & BSF)



Pan head screw (Unified, BSW & BSF)



Hexagon head screw (Unified)



Cheese head screw (BSW & BSF)



Hexagon head screw (Unified) alternate design



Raised cheese head screw (Unified)



Hexagon machine screw nut (Unified)

*Countersinks to suit the screws should have a maximum angle of 80° (Unified) or 90° (BSF and BSW) with a negative tolerance.

†Unified countersunk and raised countersunk head screws 2 inches long and under are threaded right up to the head. Other Unified, BSW and BSF machine screws 2 inches long and under have an unthread shank equal to twice the pitch. All Unified, BSW and BSF machine screws longer than 2 inches have a minimum thread length of $1\frac{3}{4}$ inches.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Unified Machine Screws and Nuts *B.S. 1981:1953*

Nom.Size of Screw	Basic Dia. *D*	Threads per Inch UNC	Threads per Inch UNF	Dia. of Head *A* Max.	Dia. of Head *A* Min.	Depth of Head *B* Max.	Depth of Head *B* Min.	Width of Slot *H* Max.	Width of Slot *H* Min.	Depth of Slot *J*
80° Countersunk Head Screws[a,b]										
4	0.112	40	…	0.211	0.194	0.067	…	0.039	0.031	0.025
6	0.138	32	…	0.260	0.242	0.083	…	0.048	0.039	0.031
8	0.164	32	…	0.310	0.291	0.100	…	0.054	0.045	0.037
10	0.190	24[c]	32	0.359	0.339	0.116	…	0.060	0.050	0.044
1/4	0.250	20	28	0.473	0.450	0.153	…	0.075	0.064	0.058
5/16	0.3125	18	24	0.593	0.565	0.191	…	0.084	0.072	0.073
3/8	0.375	16	24	0.712	0.681	0.230	…	0.094	0.081	0.086
7/16	0.4375	14	20	0.753	0.719	0.223	…	0.094	0.081	0.086
1/2	0.500	13	20	0.808	0.770	0.223	…	0.106	0.091	0.086
5/8	0.625	11	18	1.041	0.996	0.298	…	0.133	0.116	0.113
3/4	0.750	10	16	1.275	1.223	0.372	…	0.149	0.131	0.141
Pan Head Screws[b]										
4	0.112	40	…	0.219	0.205	0.068	0.058	0.039	0.031	0.036
6	0.138	32	…	0.270	0.256	0.082	0.072	0.048	0.039	0.044
8	0.164	32	…	0.322	0.306	0.096	0.085	0.054	0.045	0.051
10	0.190	24[c]	32	0.373	0.357	0.110	0.099	0.060	0.050	0.059
1/4	0.250	20	28	0.492	0.473[d]	0.144	0.130	0.075	0.064	0.079
5/16	0.3125	18	24	0.615	0.594	0.178	0.162	0.084	0.072	0.101
3/8	0.375	16	24	0.740	0.716	0.212	0.195	0.094	0.081	0.122
7/16	0.4375	14	20	0.863	0.838	0.247	0.227	0.094	0.081	0.133
1/2	0.500	13	20	0.987	0.958	0.281	0.260	0.106	0.091	0.152
5/8	0.625	11	18	1.125	1.090	0.350	0.325	0.133	0.116	0.189
3/4	0.750	10	16	1.250	1.209	0.419	0.390	0.149	0.131	0.226
Raised Cheese-Head Screws[b]										
4	0.112	40	…	0.183	0.166	0.107	0.088	0.039	0.031	0.042
6	0.138	32	…	0.226	0.208	0.132	0.111	0.048	0.039	0.053
8	0.164	32	…	0.270	0.250	0.156	0.133	0.054	0.045	0.063
10	0.190	24[c]	32	0.313	0.292	0.180	0.156	0.060	0.050	0.074
1/4	0.250	20	28	0.414	0.389	0.237	0.207	0.075	0.064	0.098
5/16	0.3125	18	24	0.518	0.490	0.295	0.262	0.084	0.072	0.124
3/8	0.375	16	24	0.622	0.590	0.355	0.315	0.094	0.081	0.149
7/16	0.4375	14	20	0.625	0.589	0.368	0.321	0.094	0.081	0.153
1/2	0.500	13	20	0.750	0.710	0.412	0.362	0.106	0.091	0.171
5/8	0.625	11	18	0.875	0.827	0.521	0.461	0.133	0.116	0.217
3/4	0.750	10	16	1.000	0.945	0.612	0.542	0.149	0.131	0.254

[a] All dimensions, except *J*, given for the No. 4 to 3/8-inch sizes, incl., also apply to all the 80° Raised Countersunk Head Screws given in the Standard.

[b] Also available with recessed heads.

[c] Non-preferred.

[d] By arrangement may also be 0.468.

Nom. Size	Basic Dia. *D*	Threads per Inch UNC	Threads per Inch UNF	Width Across Flats *A* Max.	Width Across Flats *A* Min.	Width Across Corners *C* Max.	H'd Depth *B* Nut Thick. *E* Max.	H'd Depth *B* Nut Thick. *E* Min.	Wash. Face Dia. *F* Max.	Wash. Face Dia. *F* Min.
Hexagon Head Screws										
4	0.112	40	…	0.1875	0.1835	0.216	0.060	0.055	0.183	0.173
6	0.138	32	…	0.2500	0.2450	0.289	0.080	0.074	0.245	0.235
8	0.164	32	…	0.2500	0.2450	0.289	0.110	0.104	0.245	0.235
10	0.190	24[c]	32	0.3125	0.3075	0.361	0.120	0.113	0.307	0.297
Hexagon Machine Screw Nuts—Precision Type										
4	0.112	40	…	0.1875	0.1835	0.216	0.098	0.087	…	…
6	0.138	32	…	0.2500	0.2450	0.269	0.114	0.102	…	…
8	0.164	32	…	0.3125	0.3075	0.361	0.130	0.117	…	…
10	0.190	24[c]	…	0.3125	0.3075	0.361	0.130	0.117	…	…
Hexagon Machine Screw Nuts—Pressed Type										
4	0.112	40	…	0.2500	0.2410	0.289	0.087	0.077	…	…
6	0.138	32	…	0.3125	0.3020	0.361	0.114	0.102	…	…
8	0.164	32	…	0.3438	0.3320	0.397	0.130	0.117	…	…
10	0.190	24[c]	32	0.3750	0.3620	0.433	0.130	0.117	…	…
1/4	0.250	20	28	0.4375	0.4230	0.505	0.193	0.178	…	…
5/16	0.3125	18	24	0.5625	0.5450	0.649	0.225	0.208	…	…
3/8	0.375	16	24	0.6250	0.6070	0.722	0.257	0.239	…	…

All dimensions in inches. See page 1614 for a pictorial representation and letter dimensions.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Whitworth (BSW) and Fine (BSF) Machine Screws

BS 450:1958 (obsolescent)

	Nom. Size of Screw	Basic Dia. *D*	Threads per Inch		Dia. of Head *A*		Depth of Head *B*		Width of Slot *H*		Depth of Slot *J*
			BSW	BSF	Max.	Min.	Max.	Min.	Max.	Min.	
90° Countersunk Head Screws[a,b]	1/8	0.1250	40	…	0.219	0.201	0.056	…	0.039	0.032	0.027
	3/16	0.1875	24	32[c]	0.328	0.307	0.084	…	0.050	0.042	0.041
	7/32	0.2188	…	28[c]	0.383	0.360	0.098	…	0.055	0.046	0.048
	1/4	0.2500	20	26	0.438	0.412	0.113	…	0.061	0.051	0.055
	5/16	0.3125	18	22	0.547	0.518	0.141	…	0.071	0.061	0.069
	3/8	0.3750	16	20	0.656	0.624	0.169	…	0.082	0.072	0.083
	7/16	0.4375	14	18	0.766	0.729	0.197	…	0.093	0.082	0.097
	1/2	0.5000	12	16	0.875	0.835	0.225	…	0.104	0.092	0.111
	9/16	0.5625	12[c]	16[c]	0.984	0.941	0.253	…	0.115	0.103	0.125
	5/8	0.6250	11	14	1.094	1.046	0.281	…	0.126	0.113	0.138
	3/4	0.7500	10	12	1.312	1.257	0.338	…	0.148	0.134	0.166
Round Head Screws[b]	1/8	0.1250	40	…	0.219	0.206	0.087	0.082	0.039	0.032	0.048
	3/16	0.1875	24	32[c]	0.328	0.312[d]	0.131	0.124	0.050	0.042	0.072
	7/32	0.2188	…	28[c]	0.383	0.365	0.153	0.145	0.055	0.046	0.084
	1/4	0.2500	20	26	0.438	0.417	0.175	0.165	0.061	0.051	0.096
	5/16	0.3125	18	22	0.547	0.524	0.219	0.207	0.071	0.061	0.120
	3/8	0.3750	16	20	0.656	0.629	0.262	0.249	0.082	0.072	0.144
	7/16	0.4375	14	18	0.766	0.735	0.306	0.291	0.093	0.082	0.168
	1/2	0.5000	12	16	0.875	0.840	0.350	0.333	0.104	0.092	0.192
	9/16	0.5625	12[c]	16[c]	0.984	0.946	0.394	0.375	0.115	0.103	0.217
	5/8	0.6250	11	14	1.094	1.051	0.437	0.417	0.126	0.113	0.240
	3/4	0.7500	10	12	1.312	1.262	0.525	0.500	0.148	0.134	0.288
Pan Head Screws[b]	1/8	0.1250	40	…	0.245	0.231	0.075	0.065	0.039	0.032	0.040
	3/16	0.1875	24	32[c]	0.373	0.375	0.110	0.099	0.050	0.042	0.061
	7/32	0.2188	…	28[c]	0.425	0.407	0.125	0.112	0.055	0.046	0.069
	1/4	0.2500	20	26	0.492	0.473[e]	0.144	0.130	0.061	0.051	0.078
	5/16	0.3125	18	22	0.615	0.594	0.178	0.162	0.071	0.061	0.095
	3/8	0.3750	16	20	0.740	0.716	0.212	0.195	0.082	0.072	0.112
	7/16	0.4375	14	18	0.863	0.838	0.247	0.227	0.093	0.082	0.129
	1/2	0.5000	12	16	0.987	0.958	0.281	0.260	0.104	0.092	0.145
	9/16	0.5625	12[c]	16[c]	1.031	0.999	0.315	0.293	0.115	0.103	0.162
	5/8	0.6250	11	14	1.125	1.090	0.350	0.325	0.126	0.113	0.179
	3/4	0.7500	10	12	1.250	1.209	0.419	0.390	0.148	0.134	0.213
Cheese Head Screws[b]	1/8	0.1250	40	…	0.188	0.180	0.087	0.082	0.039	0.032	0.039
	3/16	0.1875	24	32[c]	0.281	0.270	0.131	0.124	0.050	0.042	0.059
	7/32	0.2188	…	28[c]	0.328	0.315	0.153	0.145	0.055	0.046	0.069
	1/4	0.2500	20	26	0.375	0.360	0.175	0.165	0.061	0.051	0.079
	5/16	0.3125	18	22	0.469	0.450	0.219	0.207	0.071	0.061	0.098
	3/8	0.3750	16	20	0.562	0.540	0.262	0.249	0.082	0.072	0.118
	7/16	0.4375	14	18	0.656	0.630	0.306	0.291	0.093	0.082	0.138
	1/2	0.5000	12	16	0.750	0.720	0.350	0.333	0.104	0.092	0.157
	9/16	0.5625	12[c]	16[c]	0.844	0.810	0.394	0.375	0.115	0.103	0.177
	5/8	0.6250	11	14	0.938	0.900	0.437	0.417	0.126	0.113	0.197
	3/4	0.7500	10	12	1.125	1.080	0.525	0.500	0.148	0.134	0.236
Mushroom Head Screws[b]	1/8	0.1250	40	…	0.289	0.272	0.078	0.066	0.043	0.035	0.040
	3/16	0.1875	24	32[c]	0.448	0.425	0.118	0.103	0.060	0.050	0.061
	1/4	0.2500	20	26	0.573	0.546	0.150	0.133	0.075	0.064	0.079
	5/16	0.3125	18	22	0.698	0.666	0.183	0.162	0.084	0.072	0.096
	3/8	0.3750	16	20	0.823	0.787	0.215	0.191	0.094	0.081	0.112

[a] All dimensions, except *J*, given for the 1/8-through 3/8-inch sizes also apply to all the 90° Raised Countersunk Head Screw dimensions given in the Standard.

[b] These screws are also available with recessed heads; dimensions of recess are not given here but may be found in the Standard.

[c] Non-preferred size; avoid use whenever possible.

[d] By arrangement may also be 0.309.

[e] By arrangement may also be 0.468.

All dimensions in inches.

See diagram on page 1614 for a pictorial representation of screws and letter dimensions.

Copyright 2004, Industrial Press, Inc., New York, NY

CAP AND SET SCREWS

Slotted Head Cap Screws.— American National Standard ANSI/ASME B18.6.2-1998 is intended to cover the complete general and dimensional data for the various styles of slotted head cap screws as well as square head and slotted headless set screws (see page 1625). Reference should be made to this Standard for information or data not found in the following text or tables.

Length of Thread: The length of complete (full form) thread on cap screws is equal to twice the basic screw diameter plus 0.250 in. with a plus tolerance of 0.188 in. or an amount equal to 2½ times the pitch of the thread, whichever is greater. Cap screws of lengths too short to accommodate the minimum thread length have full form threads extending to within a distance equal to 2½ pitches (threads) of the head.

Designation: Slotted head cap screws are designated by the following data in the sequence shown: Nominal size (fraction or decimal equivalent); threads per inch; screw length (fraction or decimal equivalent); product name; material; and protective finish, if required. Examples: ½-13 × 3 Slotted Round Head Cap Screw, SAE Grade 2 Steel, Zinc Plated. .750-16 × 2.25 Slotted Flat Countersunk Head Cap Screw, Corrosion Resistant Steel.

Table 1. American National Standard Slotted Flat Countersunk Head Cap Screws
ANSI/ASME B18.6.2-1998



Nominal Size[a] or Basic Screw Dia.		Body Dia., *E*		Head Dia., *A* Edge Sharp		Edge Rnd'd. or Flat	Head Hgt., *H*	Slot Width, *J*		Slot Depth, *T*		Filet Rad., *U*
		Max.	Min.	Max.		Min.	Ref.	Max.	Min.	Max.	Min.	Max.
¼	0.2500	.2500	.2450	.500		.452	.140	.075	.064	.068	.045	.100
5/16	0.3125	.3125	.3070	.625		.567	.177	.084	.072	.086	.057	.125
⅜	0.3750	.3750	.3690	.750		.682	.210	.094	.081	.103	.068	.150
7/16	0.4375	.4375	.4310	.812		.736	.210	.094	.081	.103	.068	.175
½	0.5000	.5000	.4930	.875		.791	.210	.106	.091	.103	.068	.200
9/16	0.5625	.5625	.5550	1.000		.906	.244	.118	.102	.120	.080	.225
⅝	0.6250	.6250	.6170	1.125		1.020	.281	.133	.116	.137	.091	.250
¾	0.7500	.7500	.7420	1.375		1.251	.352	.149	.131	.171	.115	.300
⅞	0.8750	.8750	.8660	1.625		1.480	.423	.167	.147	.206	.138	.350
1	1.0000	1.0000	.9900	1.875		1.711	.494	.188	.166	.240	.162	.400
1⅛	1.1250	1.1250	1.1140	2.062		1.880	.529	.196	.178	.257	.173	.450
1¼	1.2500	1.2500	1.2390	2.312		2.110	.600	.211	.193	.291	.197	.500
1⅜	1.3750	1.3750	1.3630	2.562		2.340	.665	.226	.208	.326	.220	.550
1½	1.5000	1.5000	1.4880	2.812		2.570	.742	.258	.240	.360	.244	.600

[a] When specifying a nominal size in decimals, the zero preceding the decimal point is omitted as is any zero in the fourth decimal place.

All dimensions are in inches.

Threads: Threads are Unified Standard Class 2A; UNC, UNF and 8 UN Series or UNRC, UNRF, and 8 UNR Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Slotted Round Head Cap Screws
ANSI/ASME B18.6.2-1998



Nom. Size[a] or Basic Screw Diameter		Body Diameter, *E*		Head Diameter, *A*		Head Height, *H*		Slot Width, *J*		Slot Depth, *T*	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
1/4	0.2500	.2500	.2450	.437	.418	.191	.175	.075	.064	.117	.097
5/16	0.3125	.3125	.3070	.562	.540	.245	.226	.084	.072	.151	.126
3/8	0.3750	.3750	.3690	.625	.603	.273	.252	.094	.081	.168	.138
7/16	0.4375	.4375	.4310	.750	.725	.328	.302	.094	.081	.202	.167
1/2	0.5000	.5000	.4930	.812	.786	.354	.327	.106	.091	.218	.178
9/16	0.5625	.5625	.5550	.937	.909	.409	.378	.118	.102	.252	.207
5/8	0.6250	.6250	.6170	1.000	.970	.437	.405	.133	.116	.270	.220
3/4	0.7500	.7500	.7420	1.250	1.215	.546	.507	.149	.131	.338	.278

[a] When specifying a nominal size in decimals, the zero preceding the decimal point is omitted as is any zero in the fourth decimal place.

All dimensions are in inches.

Fillet Radius, U: For fillet radius see foonote to table below.

Threads: Threads are Unified Standard Class 2A; UNC, UNF and 8 UN Series or UNRC, UNRF and 8 UNR Series.

Table 3. American National Standard Slotted Fillister Head Cap Screws
ANSI/ASME B18.6.2-1998



Nom. Size[a] or Basic Screw Dia.		Body Dia.., *E*		Head Dia.., *A*		Head Side Height, *H*		Total Head Height, *O*		Slot Width, *J*		Slot Depth, *T*	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
1/4	0.2500	.2500	.2450	.375	.363	.172	.157	.216	.194	.075	.064	.097	.077
5/16	0.3125	.3125	.3070	.437	.424	.203	.186	.253	.230	.084	.072	.115	.090
3/8	0.3750	.3750	.3690	.562	.547	.250	.229	.314	.284	.094	.081	.142	.112
7/16	0.4375	.4375	.4310	.625	.608	.297	.274	.368	.336	.094	.081	.168	.133
1/2	0.5000	.5000	.4930	.750	.731	.328	.301	.413	.376	.106	.091	.193	.153
9/16	0.5625	.5625	.5550	.812	.792	.375	.346	.467	.427	.118	.102	.213	.168
5/8	0.6250	.6250	.6170	.875	.853	.422	.391	.521	.478	.133	.116	.239	.189
3/4	0.7500	.7500	.7420	1.000	.976	.500	.466	.612	.566	.149	.131	.283	.223
7/8	0.8750	.8750	.8660	1.125	1.098	.594	.556	.720	.668	.167	.147	.334	.264
1	1.0000	1.0000	.9900	1.312	1.282	.656	.612	.803	.743	.188	.166	.371	.291

[a] When specifying nominal size in decimals, the zero preceding the decimal point is omitted as is any zero in the fourth decimal place.

All dimensions are in inches.

Fillet Radius, U: The fillet radius is as follows: For screw sizes 1/4 to 3/8 incl., .031 max. and .016 min.; 7/16 to 9/16, incl., .047 max., .016 min.; and for 5/8 to 1, incl., .062 max., .031 min.

Threads: Threads are Unified Standard Class 2A; UNC, UNF and 8 UN Series or UNRC, UNRF and 8 UNR Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Hexagon and Spline Socket Head Cap Screws *ANSI/ASME B18.3-1998*



Nominal Size	Body Diameter, *D*		Head Diameter, *A*		Head Height, *H*		Spline Socket[a] Size, *M*	Nom. Hex. Socket Size, *J*		Fillet Ext., *F*	Key Engagement[a], *T*
	Max	Min	Max	Min	Max	Min				Max	
0	0.0600	0.0568	0.096	0.091	0.060	0.057	0.060	0.050		0.007	0.025
1	0.0730	0.0695	0.118	0.112	0.073	0.070	0.072	1/16	0.062	0.007	0.031
2	0.0860	0.0822	0.140	0.134	0.086	0.083	0.096	5/64	0.078	0.008	0.038
3	0.0990	0.0949	0.161	0.154	0.099	0.095	0.096	5/64	0.078	0.008	0.044
4	0.1120	0.1075	0.183	0.176	0.112	0.108	0.111	3/32	0.094	0.009	0.051
5	0.1250	0.1202	0.205	0.198	0.125	0.121	0.111	3/32	0.094	0.010	0.057
6	0.1380	0.1329	0.226	0.218	0.138	0.134	0.133	7/64	0.109	0.010	0.064
8	0.1640	0.1585	0.270	0.262	0.164	0.159	0.168	9/64	0.141	0.012	0.077
10	0.1900	0.1840	0.312	0.303	0.190	0.185	0.183	5/32	0.156	0.014	0.090
1/4	0.2500	0.2435	0.375	0.365	0.250	0.244	0.216	3/16	0.188	0.014	0.120
5/16	0.3125	0.3053	0.469	0.457	0.312	0.306	0.291	1/4	0.250	0.017	0.151
3/8	0.3750	0.3678	0.562	0.550	0.375	0.368	0.372	5/16	0.312	0.020	0.182
7/16	0.4375	0.4294	0.656	0.642	0.438	0.430	0.454	3/8	0.375	0.023	0.213
1/2	0.5000	0.4919	0.750	0.735	0.500	0.492	0.454	3/8	0.375	0.026	0.245
5/8	0.6250	0.6163	0.938	0.921	0.625	0.616	0.595	1/2	0.500	0.032	0.307
3/4	0.7500	0.7406	1.125	1.107	0.750	0.740	0.620	5/8	0.625	0.039	0.370
7/8	0.8750	0.8647	1.312	1.293	0.875	0.864	0.698	3/4	0.750	0.044	0.432
1	1.0000	0.9886	1.500	1.479	1.000	0.988	0.790	3/4	0.750	0.050	0.495
1 1/8	1.1250	1.1086	1.688	1.665	1.125	1.111	…	7/8	0.875	0.055	0.557
1 1/4	1.2500	1.2336	1.875	1.852	1.250	1.236	…	7/8	0.875	0.060	0.620
1 3/8	1.3750	1.3568	2.062	2.038	1.375	1.360	…	1	1.000	0.065	0.682
1 1/2	1.5000	1.4818	2.250	2.224	1.500	1.485	…	1	1.000	0.070	0.745
1 3/4	1.7500	1.7295	2.625	2.597	1.750	1.734	…	1 1/4	1.250	0.080	0.870
2	2.0000	1.9780	3.000	2.970	2.000	1.983	…	1 1/2	1.500	0.090	0.995
2 1/4	2.2500	2.2280	3.375	3.344	2.250	2.232	…	1 3/4	1.750	0.100	1.120
2 1/2	2.5000	2.4762	3.750	3.717	2.500	2.481	…	1 3/4	1.750	0.110	1.245
2 3/4	2.7500	2.7262	4.125	4.090	2.750	2.730	…	2	2.000	0.120	1.370
3	3.0000	2.9762	4.500	4.464	3.000	2.979	…	2 1/4	2.250	0.130	1.495
3 1/4	3.2500	3.2262	4.875	4.837	3.250	3.228	…	2 1/4	2.250	0.140	1.620
3 1/2	3.5000	3.4762	5.250	5.211	3.500	3.478	…	2 3/4	2.750	0.150	1.745
3 3/4	3.7500	3.7262	5.625	5.584	3.750	3.727	…	2 3/4	2.750	0.160	1.870
4	4.0000	3.9762	6.000	5.958	4.000	3.976	…	3	3.000	0.170	1.995

[a] Key engagement depths are minimum. Spline socket sizes are nominal.

All dimensions in inches. The body length L_B of the screw is the length of the unthreaded cylindrical portion of the shank. The length of thread, L_T, is the distance from the extreme point to the last complete (full form) thread. Standard length increments for screw diameters up to 1 inch are 1/16 inch for lengths 1/8 through 1/4 inch, 1/8 inch for lengths 1/4 through 1 inch, 1/4 inch for lengths 1 through 3 1/2 inches, 1/2 inch for lengths 3 1/2 through 7 inches, 1 inch for lengths 7 through 10 inches and for diameters over 1 inch are 1/2 inch for lengths 1 through 7 inches, 1 inch for lengths 7 through 10 inches, and 2 inches for lengths over 10 inches.

Heads may be plain or knurled, and chamfered to an angle E of 30 to 45 degrees with the surface of the flat. The thread conforms to the Unified Standard with radius root, Class 3A UNRC and UNRF for screw sizes No. 0 through 1 inch inclusive, Class 2A UNRC and UNRF for over 1 inch through 1 1/2 inches inclusive, and Class 2A UNRC for larger sizes. Socket dimensions are given in Table 11. For details not shown, including materials, see ANSI/ASME B18.3-1998.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Drill and Counterbore Sizes For Socket Head Cap Screws (1960 Series)



Nominal Size or Basic Screw Diameter		Nominal Drill Size				Counterbore Diameter	Countersink Diameter[a]
		Close Fit[b]		Normal Fit[c]			
		Number or Fractional Size	Decimal Size	Number or Fractional Size	Decimal Size		
		A				*B*	*C*
0	0.0600	51	0.067	49	0.073	1/8	0.074
1	0.0730	46	0.081	43	0.089	5/32	0.087
2	0.0860	3/32	0.094	36	0.106	3/16	0.102
3	0.0990	36	0.106	31	0.120	7/32	0.115
4	0.1120	1/8	0.125	29	0.136	7/32	0.130
5	0.1250	9/64	0.141	23	0.154	1/4	0.145
6	0.1380	23	0.154	18	0.170	9/32	0.158
8	0.1640	15	0.180	10	0.194	5/16	0.188
10	0.1900	5	0.206	2	0.221	3/8	0.218
1/4	0.2500	17/64	0.266	9/32	0.281	7/16	0.278
5/16	0.3125	21/64	0.328	11/32	0.344	17/32	0.346
3/8	0.3750	25/64	0.391	13/32	0.406	5/8	0.415
7/16	0.4375	29/64	0.453	15/32	0.469	23/32	0.483
1/2	0.5000	33/64	0.516	17/32	0.531	13/16	0.552
5/8	0.6250	41/64	0.641	21/32	0.656	1	0.689
3/4	0.7500	49/64	0.766	25/32	0.781	1 3/16	0.828
7/8	0.8750	57/64	0.891	29/32	0.906	1 3/8	0.963
1	1.0000	1 1/64	1.016	1 1/32	1.031	1 5/8	1.100
1 1/4	1.2500	1 9/32	1.281	1 5/16	1.312	2	1.370
1 1/2	1.5000	1 17/32	1.531	1 9/16	1.562	2 3/8	1.640
1 3/4	1.7500	1 25/32	1.781	1 13/16	1.812	2 3/4	1.910
2	2.0000	2 1/32	2.031	2 1/16	2.062	3 1/8	2.180

[a] *Countersink:* It is considered good practice to countersink or break the edges of holes which are smaller than (*D* Max + 2*F* Max) in parts having a hardness which approaches, equals or exceeds the screw hardness. If such holes are not countersunk, the heads of screws may not seat properly or the sharp edges on holes may deform the fillets on screws thereby making them susceptible to fatigue in applications involving dynamic loading. The countersink or corner relief, however, should not be larger than is necessary to insure that the fillet on the screw is cleared.

[b] *Close Fit:* The close fit is normally limited to holes for those lengths of screws which are threaded to the head in assemblies where only one screw is to be used or where two or more screws are to be used and the mating holes are to be produced either at assembly or by matched and coordinated tooling.

[c] *Normal Fit:* The normal fit is intended for screws of relatively long length or for assemblies involving two or more screws where the mating holes are to be produced by conventional tolerancing methods. It provides for the maximum allowable eccentricity of the longest standard screws and for certain variations in the parts to be fastened, such as: deviations in hole straightness, angularity between the axis of the tapped hole and that of the hole for the shank, differences in center distances of the mating holes, etc.

All dimensions in inches.

Source: Appendix to American National Standard ANSI/ASME B18.3-1998.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Hexagon and Spline Socket Flat Countersunk Head Cap Screws *ANSI/ASME B18.3-1998*



Nominal Size	Body Diameter Max.	Body Diameter Min.	Head Diameter Theoretical Sharp Max.	Head Diameter Abs. Min.	Head-Height Reference	Spline Socket Size	Hexagon Socket Size Nom.	Key Engagement Min.
	D		*A*		*H*	*M*	*J*	*T*
0	0.0600	0.0568	0.138	0.117	0.044	0.048	0.035	0.025
1	0.0730	0.0695	0.168	0.143	0.054	0.060	0.050	0.031
2	0.0860	0.0822	0.197	0.168	0.064	0.060	0.050	0.038
3	0.0990	0.0949	0.226	0.193	0.073	0.072	1/16	0.044
4	0.1120	0.1075	0.255	0.218	0.083	0.072	1/16	0.055
5	0.1250	0.1202	0.281	0.240	0.090	0.096	5/64	0.061
6	0.1380	0.1329	0.307	0.263	0.097	0.096	5/64	0.066
8	0.1640	0.1585	0.359	0.311	0.112	0.111	3/32	0.076
10	0.1900	0.1840	0.411	0.359	0.127	0.145	1/8	0.087
1/4	0.2500	0.2435	0.531	0.480	0.161	0.183	5/32	0.111
5/16	0.3125	0.3053	0.656	0.600	0.198	0.216	3/16	0.135
3/8	0.3750	0.3678	0.781	0.720	0.234	0.251	7/32	0.159
7/16	0.4375	0.4294	0.844	0.781	0.234	0.291	1/4	0.159
1/2	0.5000	0.4919	0.938	0.872	0.251	0.372	5/16	0.172
5/8	0.6250	0.6163	1.188	1.112	0.324	0.454	3/8	0.220
3/4	0.7500	0.7406	1.438	1.355	0.396	0.454	1/2	0.220
7/8	0.8750	0.8647	1.688	1.604	0.468	…	9/16	0.248
1	1.0000	0.9886	1.938	1.841	0.540	…	5/8	0.297
1 1/8	1.1250	1.1086	2.188	2.079	0.611	…	3/4	0.325
1 1/4	1.2500	1.2336	2.438	2.316	0.683	…	7/8	0.358
1 3/8	1.3750	1.3568	2.688	2.553	0.755	…	7/8	0.402
1 1/2	1.5000	1.4818	2.938	2.791	0.827	…	1	0.435

All dimensions in inches.

The body of the screw is the unthreaded cylindrical portion of the shank where not threaded to the head; the shank being the portion of the screw from the point of juncture of the conical bearing surface and the body to the flat of the point. The length of thread L_T is the distance measured from the extreme point to the last complete (full form) thread.

Standard length increments of No. 0 through 1-inch sizes are as follows: 1/16 inch for nominal screw lengths of 1/8 through 1/4 inch; 1/8 inch for lengths of 1/4 through 1 inch; 1/4 inch for lengths of 1 inch through 3 1/2 inches; 1/2 inch for lengths of 3 1/2 through 7 inches; and 1 inch for lengths of 7 through 10 inches, incl. For screw sizes over 1 inch, length increments are: 1/2 inch for nominal screw lengths of 1 inch through 7 inches; 1 inch for lengths of 7 through 10 inches; and 2 inches for lengths over 10 inches.

Threads shall be Unified external threads with radius root; Class 3A UNRC and UNRF series for sizes No. 0 through 1 inch and Class 2A UNRC and UNRF series for sizes over 1 inch to 1 1/2 inches, incl.

For manufacturing details not shown, including materials, see American National Standard ANSI/ASME B18.3-1998 Socket dimensions are given in Table 11.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Hexagon Socket and Spline Socket Button Head Cap Screws *ANSI/ASME B18.3-1998*



Nominal Size	Screw Diameter	Head Diameter		Head Height		Head Side Height	Spline Socket Size[a]	Hexagon Socket Size[a]	Standard Length
	Basic	Max.	Min.	Max.	Min.	Ref.	Nom.	Nom.	Max.
	D	*A*		*H*		*S*	*M*	*J*	*L*
0	0.0600	0.114	0.104	0.032	0.026	0.010	0.048	0.035	1/2
1	0.0730	0.139	0.129	0.039	0.033	0.010	0.060	0.050	1/2
2	0.0860	0.164	0.154	0.046	0.038	0.010	0.060	0.050	1/2
3	0.0990	0.188	0.176	0.052	0.044	0.010	0.072	1/16	1/2
4	0.1120	0.213	0.201	0.059	0.051	0.015	0.072	1/16	1/2
5	0.1250	0.238	0.226	0.066	0.058	0.015	0.096	5/64	1/2
6	0.1380	0.262	0.250	0.073	0.063	0.015	0.096	5/64	5/8
8	0.1640	0.312	0.298	0.087	0.077	0.015	0.111	3/32	3/4
10	0.1900	0.361	0.347	0.101	0.091	0.020	0.145	1/8	1
1/4	0.2500	0.437	0.419	0.132	0.122	0.031	0.183	5/32	1
5/16	0.3125	0.547	0.527	0.166	0.152	0.031	0.216	3/16	1
3/8	0.3750	0.656	0.636	0.199	0.185	0.031	0.251	7/32	1 1/4
1/2	0.5000	0.875	0.851	0.265	0.245	0.046	0.372	5/16	2
5/8	0.6250	1.000	0.970	0.331	0.311	0.062	0.454	3/8	2

[a] Socket dimensions are given in Table 11.

All dimensions in inches.

These cap screws have been designed and recommended for light fastening applications. They are not suggested for use in critical high-strength applications where socket head cap screws should normally be used.

Standard length increments for socket button head cap screws are as follows: 1/16 inch for nominal screw lengths of 1/8 through 1/4 inch, 1/8 inch for nominal screw lengths of 1/4 through 1 inch, and 1/4 inch for nominal screw lengths of 1 inch through 2 inches. Tolerances on lengths are –0.03 inch for lengths up to 1 inch inclusive. For lengths from 1 through 2 inches, inclusive, length tolerances are –0.04 inch.

The thread conforms to the Unified standard, Class 3A, with radius root, UNRC and UNRF.

To prevent interference, American National Standard ANSI/ASME B18.3.4M-1986 gives metric dimensional and general requirements for a lower head profile hexagon socket button head cap screw. Because of its design, wrenchability and other design factors are reduced; therefore, B18.3.4M should be reviewed carefully. Available only in metric sizes and with metric threads.

For manufacturing details, including materials, not shown, see American National Standard ANSI/ASME B18.3-1998

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. American National Standard Hexagon Socket Head Shoulder Screws
ANSI/ASME B18.3-1998



Nominal Size	Shoulder Diameter Max.	Shoulder Diameter Min.	Head Diameter Max.	Head Diameter Min.	Head Height Max.	Head Height Min.	Head Side Height Min.	Nominal Thread Size	Thread Length
	D		*A*		*H*		*S*	D_1	*E*
1/4	0.2480	0.2460	0.375	0.357	0.188	0.177	0.157	10–24	0.375
5/16	0.3105	0.3085	0.438	0.419	0.219	0.209	0.183	1/4-20	0.438
3/8	0.3730	0.3710	0.562	0.543	0.250	0.240	0.209	5/16-18	0.500
1/2	0.4980	0.4960	0.750	0.729	0.312	0.302	0.262	3/8-16	0.625
5/8	0.6230	0.6210	0.875	0.853	0.375	0.365	0.315	1/2-13	0.750
3/4	0.7480	0.7460	1.000	0.977	0.500	0.490	0.421	5/8-11	0.875
1	0.9980	0.9960	1.312	1.287	0.625	0.610	0.527	3/4-10	1.000
1 1/4	1.2480	1.2460	1.750	1.723	0.750	0.735	0.633	7/8-9	1.125
1 1/2	1.4980	1.4960	2.125	2.095	1.000	0.980	0.842	1 1/8-7	1.500
1 3/4	1.7480	1.7460	2.375	2.345	1.125	1.105	0.948	1 1/4-7	1.750
2	1.9980	1.9960	2.750	2.720	1.250	1.230	1.054	1 1/2-6	2.000

Nominal Size	Thread Neck Diameter Max.	Thread Neck Diameter Min.	Thread Neck Width Max.	Shoulder Neck Dia. Min.	Shoulder Neck Width Max.	Thread Neck Fillet Max.	Thread Neck Fillet Min.	Head Fillet Extension Above *D* Max.	Hexagon Socket Size Nom.
	G		*I*	*K*	*F*	*N*		*M*	*J*
1/4	0.142	0.133	0.083	0.227	0.093	0.023	0.017	0.014	1/8
5/16	0.193	0.182	0.100	0.289	0.093	0.028	0.022	0.017	5/32
3/8	0.249	0.237	0.111	0.352	0.093	0.031	0.025	0.020	3/16
1/2	0.304	0.291	0.125	0.477	0.093	0.035	0.029	0.026	1/4
5/8	0.414	0.397	0.154	0.602	0.093	0.042	0.036	0.032	5/16
3/4	0.521	0.502	0.182	0.727	0.093	0.051	0.045	0.039	3/8
1	0.638	0.616	0.200	0.977	0.125	0.055	0.049	0.050	1/2
1 1/4	0.750	0.726	0.222	1.227	0.125	0.062	0.056	0.060	5/8
1 1/2	0.964	0.934	0.286	1.478	0.125	0.072	0.066	0.070	7/8
1 3/4	1.089	1.059	0.286	1.728	0.125	0.072	0.066	0.080	1
2	1.307	1.277	0.333	1.978	0.125	0.102	0.096	0.090	1 1/4

All dimensions are in inches. The shoulder is the enlarged, unthreaded portion of the screw. Standard length increments for shoulder screws are: 1/8 inch for nominal screw lengths of 1/4 through 3/4 inch; 1/4 inch for lengths above 3/4 through 5 inches; and 1/2 inch for lengths over 5 inches. The thread conforms to the Unified Standard Class 3A, UNC. Hexagon socket sizes for the respective shoulder screw sizes are the same as for set screws of the same nominal size (see Table 7) except for shoulder screw size 1 inch, socket size is 1/2 inch, for screw size 1 1/2 inches, socket size is 7/8 inch, and for screw size 2 inches, socket size is 1 1/4 inches. For details not shown, including materials, see ANSI/ASME B18.3-1998.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Slotted Headless Set Screws
ANSI/ASME B18.6.2-1998



FLAT POINT DOG POINT HALF DOG POINT

CUP POINT OVAL POINT CONE POINT

Nominal Size[a] or Basic Screw Diameter		Slot Width, *J*		Slot Depth, *T*		Cup and Flat Point Dia., *C*		Dog Point Dia., *P*		Point Length			
										Dog, *Q*		Half Dog, *Q*1	
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
0	0.0600	.014	.010	.020	.016	.033	.027	.040	.037	.032	.028	.017	.013
1	0.0730	.016	.012	.020	.016	.040	.033	.049	.045	.040	.036	.021	.017
2	0.0860	.018	.014	.025	.019	.047	.039	.057	.053	.046	.042	.024	.020
3	0.0990	.020	.016	.028	.022	.054	.045	.066	.062	.052	.048	.027	.023
4	0.1120	.024	.018	.031	.025	.061	.051	.075	.070	.058	.054	.030	.026
5	0.1250	.026	.020	.036	.026	.067	.057	.083	.078	.063	.057	.033	.027
6	0.1380	.028	.022	.040	.030	.074	.064	.092	.087	.073	.067	.038	.032
8	0.1640	.032	.026	.046	.036	.087	.076	.109	.103	.083	.077	.043	.037
10	0.1900	.035	.029	.053	.043	.102	.088	.127	.120	.095	.085	.050	.040
12	0.2160	.042	.035	.061	.051	.115	.101	.144	.137	.115	.105	.060	.050
1/4	0.2500	.049	.041	.068	.058	.132	.118	.156	.149	.130	.120	.068	.058
5/16	0.3125	.055	.047	.083	.073	.172	.156	.203	.195	.161	.151	.083	.073
3/8	0.3750	.068	.060	.099	.089	.212	.194	.250	.241	.193	.183	.099	.089
7/16	0.4375	.076	.068	.114	.104	.252	.232	.297	.287	.224	.214	.114	.104
1/2	0.5000	.086	.076	.130	.120	.291	.270	.344	.334	.255	.245	.130	.120
9/16	0.5625	.096	.086	.146	.136	.332	.309	.391	.379	.287	.275	.146	.134
5/8	0.6250	.107	.097	.161	.151	.371	.347	.469	.456	.321	.305	.164	.148
3/4	0.7500	.134	.124	.193	.183	.450	.425	.562	.549	.383	.367	.196	.180

[a] When specifying a nominal size in decimals a zero preceding the decimal point or any zero in the fourth decimal place is omitted.

All dimensions are in inches.

Crown Radius, I: The crown radius has the same value as the basic screw diameter to three decimal places.

Oval Point Radius, R: Values of the oval point radius according to nominal screw size are: For a screw size of 0, a radius of .045; 1, .055; 2, .064; 3, .074; 4, .084; 5, .094; 6, .104; 8, .123; 10, .142; 12, .162; 1/4, .188; 5/16, .234; 3/8, .281; 7/16, .328; 1/2, .375; 9/16, .422; 5/8, .469; and for 3/4, .562.

Cone Point Angle, Y: The cone point angle is 90° ± 2° for the following nominal lengths, or longer, shown according to screw size: For nominal size 0, a length of 5/64; 1, 3/32; 2, 7/64; 3, 1/8; 4, 5/32; 5, 3/16; 6, 3/16; 8, 1/4; 10, 1/4; 12, 5/16; 1/4, 5/16; 5/16, 3/8; 3/8, 7/16; 7/16, 1/2; 1/2, 9/16; 9/16, 5/8; 5/8, 3/4; and for 3/4, 7/8. For shorter screws, the cone point angle is 118° ± 2°.

Point Angle X: The point angle is 45°, + 5°, – 0°, for screws of nominal lengths, or longer, as given just above for cone point angle, and 30°, min. for shorter screws.

Threads: are Unified Standard Class 2A; UNC and UNF Series or UNRC and UNRF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. American National Standard Hexagon and Spline Socket Set Screw Optional Cup Points *ANSI/ASME B18.3-1998*



TYPE A



TYPE B



TYPE C



TYPE D

* This diameter may be counterbored.



TYPE E



TYPE F



TYPE G

Nom. Size	Point Dia.		Point Dia.		Point Dia.		Point Length	
	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
	C		*C*1		*C*2		*S*	
0	0.033	0.027	0.032	0.027	0.027	0.022	0.007	0.004
1	0.040	0.033	0.038	0.033	0.035	0.030	0.008	0.005
2	0.047	0.039	0.043	0.038	0.043	0.038	0.010	0.007
3	0.054	0.045	0.050	0.045	0.051	0.046	0.011	0.007
4	0.061	0.051	0.056	0.051	0.059	0.054	0.013	0.008
5	0.067	0.057	0.062	0.056	0.068	0.063	0.014	0.009
6	0.074	0.064	0.069	0.062	0.074	0.068	0.017	0.012
8	0.087	0.076	0.082	0.074	0.090	0.084	0.021	0.016
10	0.102	0.088	0.095	0.086	0.101	0.095	0.024	0.019
1/4	0.132	0.118	0.125	0.114	0.156	0.150	0.027	0.022
5/16	0.172	0.156	0.156	0.144	0.190	0.185	0.038	0.033
3/8	0.212	0.194	0.187	0.174	0.241	0.236	0.041	0.036
7/16	0.252	0.232	0.218	0.204	0.286	0.281	0.047	0.042
1/2	0.291	0.270	0.250	0.235	0.333	0.328	0.054	0.049
5/8	0.371	0.347	0.312	0.295	0.425	0.420	0.067	0.062
3/4	0.450	0.425	0.375	0.357	0.523	0.518	0.081	0.076
7/8	0.530	0.502	0.437	0.418	…	…	…	…
1	0.609	0.579	0.500	0.480	…	…	…	…
1 1/8	0.689	0.655	0.562	0.542	…	…	…	…
1 1/4	0.767	0.733	0.625	0.605	…	…	…	…
1 3/8	0.848	0.808	0.687	0.667	…	…	…	…
1 1/2	0.926	0.886	0.750	0.730	…	…	…	…
1 3/4	1.086	1.039	0.875	0.855	…	…	…	…
2	1.244	1.193	1.000	0.980	…	…	…	…

All dimensions are in inches.

The cup point types shown are those available from various manufacturers.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. American National Standard Hexagon and Spline Sockets
ANSI/ASME B18.3-1998

BROACHED SOCKET

HEXAGON SOCKETS

Nominal Socket Size	Socket Width Across Flats J Max.	Socket Width Across Flats J Min.	Nominal Socket Size	Socket Width Across Flats J Max.	Socket Width Across Flats J Min.	Nominal Socket Size	Socket Width Across Flats J Max.	Socket Width Across Flats J Min.	Nominal Socket Size	Socket Width Across Flats J Max.	Socket Width Across Flats J Min.
0.028	0.0285	0.0280	9/64	0.1426	0.1406	7/16	0.4420	0.4375	1 1/4	1.2750	1.2500
0.035	0.0355	0.0350	5/32	0.1587	0.1562	1/2	0.5050	0.5000	1 1/2	1.5300	1.5000
0.050	0.0510	0.0500	3/16	0.1900	0.1875	9/16	0.5680	0.5625	1 3/4	1.7850	1.7500
1/16	0.0635	0.0625	7/32	0.2217	0.2187	5/8	0.6310	0.6250	2	2.0400	2.0000
5/64	0.0791	0.0781	1/4	0.2530	0.2500	3/4	0.7570	0.7500	2 1/4	2.2950	2.2500
3/32	0.0952	0.0937	5/16	0.3160	0.3125	7/8	0.8850	0.8750	2 3/4	2.8050	2.7500
7/64	0.1111	0.1094	3/8	0.3790	0.3750	1	1.0200	1.0000	3	3.0600	3.0000
1/8	0.1270	0.1250	…	…	…	…	…	…	…	…	…



SPLINE SOCKETS

Nominal Socket Size	Number of Teeth	Socket Major Diameter M Max.	Socket Major Diameter M Min.	Socket Minor Diameter N Max.	Socket Minor Diameter N Min.	Width of Tooth P Max.	Width of Tooth P Min.
0.033	4	0.0350	0.0340	0.0260	0.0255	0.0120	0.0115
0.048	6	0.050	0.049	0.041	0.040	0.011	0.010
0.060	6	0.062	0.061	0.051	0.050	0.014	0.013
0.072	6	0.074	0.073	0.064	0.063	0.016	0.015
0.096	6	0.098	0.097	0.082	0.080	0.022	0.021
0.111	6	0.115	0.113	0.098	0.096	0.025	0.023
0.133	6	0.137	0.135	0.118	0.116	0.030	0.028
0.145	6	0.149	0.147	0.128	0.126	0.032	0.030
0.168	6	0.173	0.171	0.150	0.147	0.036	0.033
0.183	6	0.188	0.186	0.163	0.161	0.039	0.037
0.216	6	0.221	0.219	0.190	0.188	0.050	0.048
0.251	6	0.256	0.254	0.221	0.219	0.060	0.058
0.291	6	0.298	0.296	0.254	0.252	0.068	0.066
0.372	6	0.380	0.377	0.319	0.316	0.092	0.089
0.454	6	0.463	0.460	0.386	0.383	0.112	0.109
0.595	6	0.604	0.601	0.509	0.506	0.138	0.134
0.620	6	0.631	0.627	0.535	0.531	0.149	0.145
0.698	6	0.709	0.705	0.604	0.600	0.168	0.164
0.790	6	0.801	0.797	0.685	0.681	0.189	0.185

All dimensions are in inches.

* Socket depths, *T*, for various screw types are given in the standard but are not shown here.

Where sockets are chamfered, the depth of chamfer shall not exceed 10 per cent of the nominal socket size for sizes up to and including 1/16 inch for hexagon sockets and 0.060 for spline sockets, and 7.5 per cent for larger sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. American National Standard Square Head Set Screws
ANSI/ASME B18.6.2-1998



Nominal Size* or Basic Screw Diameter		Cup and Flat Point Diams., *C*		Dog and Half Dog Point Diams., *P*		Point Length				Oval Point Rad., *R*
						Dog, *Q*		Half Dog, *Q*1		
		Max.	Min	Max.	Min.	Max.	Min.	Max.	Min.	+.031 −.000
10	0.1900	.102	.088	.127	.120	.095	.085	.050	.040	.142
1/4	0.2500	.132	.118	.156	.149	.130	.120	.068	.058	.188
5/16	0.3125	.172	.156	.203	.195	.161	.151	.083	.073	.234
3/8	0.3750	.212	.194	.250	.241	.193	.183	.099	.089	.281
7/16	0.4375	.252	.232	.297	.287	.224	.214	.114	.104	.328
1/2	0.500	.291	.270	.344	.334	.255	.245	.130	.120	.375
9/16	0.5625	.332	.309	.391	.379	.287	.275	.146	.134	.422
5/8	0.6250	.371	.347	.469	.456	.321	.305	.164	.148	.469
3/4	0.7500	.450	.425	.562	.549	.383	.367	.196	.180	.562
7/8	0.8750	.530	.502	.656	.642	.446	.430	.227	.211	.656
1	1.0000	.609	.579	.750	.734	.510	.490	.260	.240	.750
1 1/8	1.1250	.689	.655	.844	.826	.572	.552	.291	.271	.844
1 1/4	1.2500	.767	.733	.938	.920	.635	.615	.323	.303	.938
1 3/8	1.3750	.848	.808	1.031	1.011	.698	.678	.354	.334	1.031
1 1/2	1.5000	.926	.886	1.125	1.105	.760	.740	.385	.365	1.125

All dimensions are in inches.

**Threads:* Threads are Unified Standard Class 2A; UNC, UNF and 8 UN Series or UNRC, UNRF and 8 UNR Series.

Length of Thread: Square head set screws have complete (full form) threads extending over that portion of the screw length which is not affected by the point. For the respective constructions, threads extend into the neck relief, to the conical underside of head, or to within one thread (as measured with a thread ring gage) from the flat underside of the head. Threads through angular or crowned portions of points have fully formed roots with partial crests.

* When specifying a nominal size in decimals, the zero preceding the decimal point is omitted as is any zero in the fourth decimal place.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. American National Standard Square Head Set Screws
ANSI/ASME B18.6.2-1998



OPTIONAL HEAD CONSTRUCTIONS

Nominal Size or Basic Screw Diameter		Width Across Flats, *F*		Width Across Corners, *G*		Head Height, *H*		Neck Relief Diameter, *K*		Neck Relief Fillet Rad., *S*	Neck Relief Width, *U*	Head Rad., *W*
		Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Min.
10	0.1900	.188	.180	.265	.247	.148	.134	.145	.140	.027	.083	0.48
1/4	0.2500	.250	.241	.354	.331	.196	.178	.185	.170	.032	.100	0.62
5/16	0.3125	.312	.302	.442	.415	.245	.224	.240	.225	.036	.111	0.78
3/8	0.3750	.375	.362	.530	.497	.293	.270	.294	.279	.041	.125	0.94
7/16	0.4375	.438	.423	.619	.581	.341	.315	.345	.330	.046	.143	1.09
1/2	0.5000	.500	.484	.707	.665	.389	.361	.400	.385	.050	.154	1.25
9/16	0.5625	.562	.545	.795	.748	.437	.407	.454	.439	.054	.167	1.41
5/8	0.6250	.625	.606	.884	.833	.485	.452	.507	.492	.059	.182	1.56
3/4	0.7500	.750	.729	1.060	1.001	.582	.544	.620	.605	.065	.200	1.88
7/8	0.8750	.875	.852	1.237	1.170	.678	.635	.731	.716	.072	.222	2.19
1	1.0000	1.000	.974	1.414	1.337	.774	.726	.838	.823	.081	.250	2.50
1 1/8	1.1250	1.125	1.096	1.591	1.505	.870	.817	.939	.914	.092	.283	2.81
1 1/4	1.2500	1.250	1.219	1.768	1.674	.966	.908	1.064	1.039	.092	.283	3.12
1 3/8	1.3750	1.375	1.342	1.945	1.843	1.063	1.000	1.159	1.134	.109	.333	3.44
1 1/2	1.5000	1.500	1.464	2.121	2.010	1.159	1.091	1.284	1.259	.109	.333	3.75

Designation: Square head set screws are designated by the following data in the sequence shown: Nominal size (number, fraction or decimal equivalent); threads per inch; screw length (fraction or decimal equivalent); product name; point style; material; and protective finish, if required. Examples: 1/4 - 20 × 3/4 Square Head Set Screw, Flat Point, Steel, Cadmium Plated. .500 – 13 × 1.25 Square Head Set Screw, Cone Point, Corrosion Resistant Steel.

Cone Point Angle, Y: For the following nominal lengths, or longer, shown according to nominal size, the cone point angle is 90° ± 2°: For size No. 10, 1/4, 1/4, 5/16, 5/16, 3/8, 3/8, 7/16, 7/16, 1/2, 1/2, 9/16, 9/16, 5/8, 5/8, 3/4, 3/4, 7/8, 7/8, 1; 1, 1 1/8; 1 1/8, 1 1/4; 1 1/4, 1 1/2; 1 3/8, 1 5/8; and for 1 1/2, 1 3/4. For shorter screws the cone point angle is 118° ± 2°.

Point Types: Unless otherwise specified, square head set screws are supplied with cup points. Cup points as furnished by some manufacturers may be externally or internally knurled. Where so specified by the purchaser, screws have cone, dog, half-dog, flat or oval points as given on the following page.

Point Angle, X: The point angle is 45°, + 5°, – 0° for screws of the nominal lengths, or longer, given just above for cone point angle, and 30° min. for shorter lengths.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Applicability of Hexagon and Spline Keys and Bits

Nominal Key or Bit Size		Cap Screws 1960 Series	Flat Countersunk Head Cap Screws	Button Head Cap Screws	Shoulder Screws	Set Screws
		Nominal Screw Sizes				
HEXAGON KEYS AND BITS						
	0.028	…	…	…	…	0
	0.035	…	0	0	…	1 & 2
	0.050	0	1 & 2	1 & 2	…	3 & 4
1/16	0.062	1	3 & 4	3 & 4	…	5 & 6
5/64	0.078	2 & 3	5 & 6	5 & 6	…	8
3/32	0.094	4 & 5	8	8	…	10
7/64	0.109	6	…	…	…	…
1/8	0.125	…	10	10	1/4	1/4
9/64	0.141	8	…	…	…	…
5/32	0.156	10	1/4	1/4	5/16	5/16
3/16	0.188	1/4	5/16	5/16	3/8	3/8
7/32	0.219	…	3/8	3/8	…	7/16
1/4	0.250	5/16	7/16	…	1/2	1/2
5/16	0.312	3/8	1/2	1/2	5/8	5/8
3/8	0.375	7/16 & 1/2	5/8	5/8	3/4	3/4
7/16	0.438	…	…	…	…	…
1/2	0.500	5/8	3/4	…	1	7/8
9/16	0.562	…	7/8	…	…	1 & 1 1/8
5/8	0.625	3/4	1	…	1 1/4	1 1/4 & 1 3/8
3/4	0.750	7/8 & 1	1 1/8	…	…	1 1/2
7/8	0.875	1 1/8 & 1 1/4	1 1/4 & 1 3/8	…	1 1/2	…
1	1.000	1 3/8 & 1 1/2	1 1/2	…	1 3/4	1 3/4 & 2
1 1/4	1.250	1 3/4	…	…	2	…
1 1/2	1.500	2	…	…	…	…
1 3/4	1.750	2 1/4 & 2 1/2	…	…	…	…
2	2.000	2 3/4	…	…	…	…
2 1/4	2.250	3 & 3 1/4	…	…	…	…
2 3/4	2.750	3 1/2 & 3 3/4	…	…	…	…
3	3.000	4	…	…	…	…
SPLINE KEYS AND BITS						
	0.033	…	…	…	…	0 & 1
	0.048	…	0	0	…	2 & 3
	0.060	0	1 & 2	1 & 2	…	4
	0.072	1	3 & 4	3 & 4	…	5 & 6
	0.096	2 & 3	5 & 6	5 & 6	…	8
	0.111	4 & 5	8	8	…	10
	0.133	6	…	…	…	…
	0.145	…	10	10	…	1/4
	0.168	8	…	…	…	…
	0.183	10	1/4	1/4	…	5/16
	0.216	1/4	5/16	5/16	…	3/8
	0.251	…	3/8	3/8	…	7/16
	0.291	5/16	7/16	…	…	1/2
	0.372	3/8	1/2	1/2	…	5/8
	0.454	7/16 & 1/2	5/8 & 3/4	5/8	…	3/4
	0.595	5/8	…	…	…	7/8
	0.620	3/4	…	…	…	…
	0.698	7/8	…	…	…	…
	0.790	1	…	…	…	…

Source: Appendix to American National Standard ANSI/ASME B18.3-1998.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. ANSI Hexagon and Spline Socket Set Screws *ANSI/ASME B18.3-1998*



For optional cup points and their dimensions see Table 10.

Nominal Size or Basic Screw Diameter		Socket Size		Cup and Flat Point Diameters		Half Dog Point		Oval Point Radius	Min. Key Engagement Depth		Lgth. Limit for Angle
		Hex.	Spl.			Dia.	Lgth.		Hex.	Spl.	
		Nom.	Nom.	Max.	Min.	Max.	Max.	Basic			
		J	*M*	*C*		*P*	*Q*	*R*	T_H[a]	T_S[a]	Y[b]
0	0.0600	0.028	0.033	0.033	0.027	0.040	0.017	0.045	0.050	0.026	0.09
1	0.0730	0.035	0.033	0.040	0.033	0.049	0.021	0.055	0.060	0.035	0.09
2	0.0860	0.035	0.048	0.047	0.039	0.057	0.024	0.064	0.060	0.040	0.13
3	0.0990	0.050	0.048	0.054	0.045	0.066	0.027	0.074	0.070	0.040	0.13
4	0.1120	0.050	0.060	0.061	0.051	0.075	0.030	0.084	0.070	0.045	0.19
5	0.1250	1/16	0.072	0.067	0.057	0.083	0.033	0.094	0.080	0.055	0.19
6	0.1380	1/16	0.072	0.074	0.064	0.092	0.038	0.104	0.080	0.055	0.19
8	0.1640	5/64	0.096	0.087	0.076	0.109	0.043	0.123	0.090	0.080	0.25
10	0.1900	3/32	0.111	0.102	0.088	0.127	0.049	0.142	0.100	0.080	0.25
1/4	0.2500	1/8	0.145	0.132	0.118	0.156	0.067	0.188	0.125	0.125	0.31
5/16	0.3125	5/32	0.183	0.172	0.156	0.203	0.082	0.234	0.156	0.156	0.38
3/8	0.3750	3/16	0.216	0.212	0.194	0.250	0.099	0.281	0.188	0.188	0.44
7/16	0.4375	7/32	0.251	0.252	0.232	0.297	0.114	0.328	0.219	0.219	0.50
1/2	0.5000	1/4	0.291	0.291	0.270	0.344	0.130	0.375	0.250	0.250	0.57
5/8	0.6250	5/16	0.372	0.371	0.347	0.469	0.164	0.469	0.312	0.312	0.75
3/4	0.7500	3/8	0.454	0.450	0.425	0.562	0.196	0.562	0.375	0.375	0.88
7/8	0.8750	1/2	0.595	0.530	0.502	0.656	0.227	0.656	0.500	0.500	1.00
1	1.0000	9/16	…	0.609	0.579	0.750	0.260	0.750	0.562	…	1.13
1 1/8	1.1250	9/16	…	0.689	0.655	0.844	0.291	0.844	0.562	…	1.25
1 1/4	1.2500	5/8	…	0.767	0.733	0.938	0.323	0.938	0.625	…	1.50
1 3/8	1.3750	5/8	…	0.848	0.808	1.031	0.354	1.031	0.625	…	1.63
1 1/2	1.5000	3/4	…	0.926	0.886	1.125	0.385	1.125	0.750	…	1.75
1 3/4	1.7500	1	…	1.086	1.039	1.312	0.448	1.321	1.000	…	2.00
2	2.0000	1	…	1.244	1.193	1.500	0.510	1.500	1.000	…	2.25

[a] Reference should be made to the Standard for shortest optimum nominal lengths to which the minimum key engagement depths T_H and T_S apply.

[b] Cone point angle *Y* is 90 degrees plus or minus 2 degrees for these nominal lengths or longer and 118 degrees plus or minus 2 degrees for shorter nominal lengths.

All dimensions are in inches. The thread conforms to the Unified Standard, Class 3A, UNC and UNF series. The socket depth *T* is included in the Standard and some are shown here. The nominal length *L* of all socket type set screws is the total or overall length. For nominal screw lengths of 1/16 through 3/16 inch (0 through 3 sizes incl.) the standard length increment is 0.06 inch; for lengths 1/8 through 1 inch the increment is 1/8 inch; for lengths 1 through 2 inches the increment is 1/4 inch; for lengths 2 through 6 inches the increment is 1/2 inch; for lengths 6 inches and longer the increment is 1 inch. Socket dimensions are given in Table 11.

Length Tolerance: The allowable tolerance on length *L* for all set screws of the socket type is ± 0.01 inch for set screws up to 5/8 inch long; ± 0.02 inch for screws over 5/8 to 2 inches long; ± 0.03 inch for screws over 2 to 6 inches long and ± 0.06 inch for screws over 6 inches long. Socket dimensions are given in Table 11.

For manufacturing details, including materials, not shown, see American National Standard ANSI/ASME B18.3-1998.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Hexagon Socket Screws — Metric Series.— The first five parts of British Standard BS 4168: 1981 provide specifications for hexagon socket head cap screws and hexagon socket set screws.

Hexagon Socket Head Cap Screws: The dimensional data in Table 1 are based upon BS 4168: Part 1: 1981. These screws are available in stainless steel and alloy steel, the latter having class 12.9 properties as specified in BS 6104:Part 1. When ordering these screws, the designation "Hexagon socket head cap screw BS 4168 M5 × 20-12.9" would mean, as an example, a cap screw having a thread size of d = M5, nominal length l = 20 mm, and property class 12.9. Alloy steel cap screws are furnished with a black oxide finish (thermal or chemical); stainless steel cap screws with a plain finish. Combinations of thread size, nominal length, and length of thread are shown in Table 2; the screw threads in these combinations are in the ISO metric coarse pitch series specified in BS 3643 with tolerances in the 5g6g class. (See Metric Screw Threads in Index.)

Hexagon Socket Set Screws: Part 2 of B.S. 4168:1981 specifies requirements for hexagon socket set screws with fiat point having ISO metric threads, and diameters from 1.6 mm up to and including 24 mm. The dimensions of these set screws along with those of cone-point, dog-point, and cup-point set screws in accord, respectively, with Parts 3, 4, and 5 of the Standard are given in Table 3 and the accompanying illustration. All of these set screws are available in either steel processed to mechanical properties class 45H B.S. 6104:Part 3; or stainless steel processed to mechanical properties described in B.S. 6105. Steel set screws are furnished with black oxide (thermal or chemical) finish; stainless steel set screws are furnished plain. The tolerances applied to the threads of these set screws are for ISO product grade A, based on ISO 4759/1-1978 "Tolerances for fasteners — Part 1: Bolts, screws, and nuts with thread diameters greater than or equal to 1.6 mm and less than or equal to 150 mm and product grades A, B, and C."

Hexagon socket set screws are designated by the type, the thread size, nominal length, and property class. As an example, for a flat-point set screw of thread size d = M6, nominal length l = 12 mm, and property class 45H:

Hexagon socket set screw flat point BS 4168 M6 × 12-45H

British Standard Hexagon Socket Countersunk and Button Head Screws — Metric Series: British Standard BS 4168:1967 provides a metric series of hexagon socket countersunk and button head screws. The dimensions of these screws are given in Table 4. The revision of this Standard will constitute Parts 6 and 8 of BS 4168.

British Standards for Mechanical Properties of Fasteners: B.S. 6104: Part 1:1981 specifies mechanical properties for bolts, screws, and studs with nominal diameters up to and including 39 mm of any triangular ISO thread and made of carbon or alloy steel. It does not apply to set screws and similar threaded fasteners. Part 2 of this Standard specifies the mechanical properties of set screws and similar fasteners, not under tensile stress, in the range from M1.6 up to and including M39 and made of carbon or alloy steel.

B.S. 6105:1981 provides specifications for bolts, screws, studs, and nuts made from austenitic, ferritic, and martensitic grades of corrosion-resistant steels. This Standard applies only to fastener components after completion of manufacture with nominal diameters from M1.6 up to and including M39. These Standards are not described further here. Copies may be obtained from the British Standards Institution, 2 Park Street, London W1A 2BS and also from the American National Standards Institute, 25 West 43rd Street, New York, N.Y. 10036.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. British Standard Hexagon Socket Head Cap Screws—Metric Series

BS 4168:Part 1:1981 (obsolescent)



Nominal Size,[a] d	Body Diameter, D		Head Diameter, A			Head Height, H		Hexagon Socket Size, J[b]	Key Engagement, K	Wall Thickness, W	Fillet	
											Rad., F	Dia., d_a
	Max	Min	Max[c]	Max[d]	Min	Max	Min	Nom	Min	Min	Min	Max
M1.6	1.6	1.46	3	3.14	2.86	1.6	1.46	1.5	0.7	0.55	0.1	2
M2	2	1.86	3.8	3.98	3.62	2	1.86	1.5	1	0.55	0.1	2.6
M2.5	2.5	2.36	4.5	4.68	4.32	2.5	2.36	2	1.1	0.85	0.1	3.1
M3	3	2.86	5.5	5.68	5.32	3	2.86	2.5	1.3	1.15	0.1	3.6
M4	4	3.82	7	7.22	6.78	4	3.82	3	2	1.4	0.2	4.7
M5	5	4.82	8.5	8.72	8.28	5	4.82	4	2.5	1.9	0.2	5.7
M6	6	5.82	10	10.22	9.78	6	5.70	5	3	2.3	0.25	6.8
M8	8	7.78	13	13.27	12.73	8	7.64	6	4	3.3	0.4	9.2
M10	10	9.78	16	16.27	15.73	10	9.64	8	5	4	0.4	11.2
M12	12	11.73	18	18.27	17.73	12	11.57	10	6	4.8	0.6	14.2
(M14)	14	13.73	21	21.33	20.67	14	13.57	12	7	5.8	0.6	16.2
M16	16	15.73	24	24.33	23.67	16	15.57	14	8	6.8	0.6	18.2
M20	20	19.67	30	30.33	29.67	20	19.48	17.	10	8.6	0.8	22.4
M24	24	23.67	36	36.39	35.61	24	23.48	19	12	10.4	0.8	26.4
M30	30	29.67	45	45.39	44.61	30	29.48	22	15.5	13.1	1	33.4
M36	36	35.61	54	54.46	53.54	36	35.38	27	19	15.3	1	39.4

[a] The size shown in ( ) is non-preferred.
[b] See Table 2 for min/max.
[c] For plain heads.
[d] For knurled heads.

All dimensions are given in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. British Standard Hexagon Socket Screws — Metric Series

BS 4168:Part 1:1981 (obsolescent)

Dimensions of Hexagon Sockets



Nominal Socket Size	Socket Width Across Flats, *J*		Nominal Socket Size	Socket Width Across Flats, *J*	
	Max.	Min.		Max.	Min.
1.5	1.545	1.52	6	6.095	6.02
2.0	2.045	2.02	8	8.115	8.025
2.5	2.56	2.52	10	10.115	10.025
3	3.08	3.02	12	12.142	12.032
4	4.095	4.02	14	14.142	14.032
5	5.095	5.02	17	17.23	17.05
…	…	…	19	19.275	19.065

Association of Nominal and Thread Lengths for Each Thread Size

Nominal Length, *L*	Nominal Thread Size, *D*							
	M1.6	M2	M2.5	M3	M4	M5	M6	M8
2.5								
3								
4								
5								
6								
8								
10								
12								
16								
20								
25								
30								
35								
40								
45								
50								
55								
60								
65								
70								
80								
…	…	…	…	…	…	…	…	…
…	…	…	…	…	…	…	…	…
b (ref)	15	16	17	18	20	22	24	28

Nominal Length, *L*	Nominal Thread Size, *D*							
	M10	M12	(M14)	M16	M20	M24	M30	M36
16								
20								
25								
30								
35								
40								
45								
50								
55								
60								
65								
70								
80								
90								
100								
110								
120								
130								
140								
150								
160								
180								
200								
b (ref)	32	36	40	44	52	60	72	84

All dimensions are in millimeters.

The popular lengths are those between the stepped solid lines. Lengths above the shaded areas are threaded to the head within 3 pitch lengths (3*P*). Lengths within and below the shaded areas have values of L_g and L_s (see Table 1) given by the formulas: $L_g\text{max} = L\,\text{nom} - b\,\text{ref}$, and $L_s\text{min} = L_g\text{max} - 5P$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. British Standard Hexagon Socket Set Screws — Metric Series
BS 4168:Parts 2, 3, 4, and 5:1994

Nom. Size, *d*	Pitch, *P*	Socket Size, *s*	Depth of Key Engagement, *t*[a]		Range of Popular Lengths				Length of Dog on Dog Point Screws[b]					End Diameters			
					Flat Point	Cone Point	Dog Point	Cup Point	Short Dog, *z*		Long Dog, *z*			Flat Point, d_z	Cone Point d_t	Dog Point, d_p	Cup Point, d_z
		nom	min	min	*l*	*l*	*l*	*l*	min	max	min	max	b	max	max	max	max
M1.6	0.35	0.7	0.7	1.5	2–8	2–8	2–8	2–8	0.4	0.65	0.8	1.05	2.5	0.8	0	0.8	0.8
M2	0.4	0.9	0.8	1.7	2–10	2–10	2.5–10	2–10	0.5	0.75	1.0	1.25	3.0	1.0	0	1.0	1.0
M2.5	0.45	1.3	1.2	2.0	2–12	2.5–12	3–12	2–12	0.63	0.88	1.25	1.5	4	1.5	0	1.5	1.2
M3	0.5	1.5	1.2	2.0	2–16	2.5–16	4–16	2.5–16	0.75	1.0	1.5	1.75	5	2.0	0	2.0	1.4
M4	0.7	2.0	1.5	2.5	2.5–20	3–20	5–20	3–20	1.0	1.25	2.0	2.25	6	2.5	0	2.5	2.0
M5	0.8	2.5	2.0	3.0	3–25	4–25	6–25	4–25	1.25	1.5	2.5	2.75	6	3.5	0	3.5	2.5
M6	1.0	3.0	2.0	3.5	4–30	5–30	8–30	5–30	1.5	1.75	3.0	3.25	8	4.0	1.5	4.0	3.0
M8	1.25	4.0	3.0	5.0	5–40	6–40	8–40	6–40	2.0	2.25	4.0	4.3	10	5.5	2.0	5.5	5.0
M10	1.5	5.0	4.0	6.0	6–50	8–50	10–50	8–50	2.5	2.75	5.0	5.3	12	7.0	2.5	7.0	6.0
M12	1.75	6.0	4.8	8.0	8–60	10–60	12–60	10–60	3.0	3.25	6.0	6.3	16	8.5	3.0	8.5	8.0
M16	2.0	8.0	6.4	10.0	10–60	12–60	16–60	12–60	4.0	4.3	8.0	8.36	20	12.0	4.0	12.0	10.0
M20	2.5	10.0	8.0	12.0	12–60	16–60	20–60	16–60	5.0	5.3	10.0	10.36	25	15.0	5.0	15.0	14.0
M24	3.0	12.0	10.0	15.0	16–60	20–60	25–60	20–60	6.0	6.3	12.0	12.43	30	18.0	6.0	18.0	16.0

[a] The smaller of the two *t* min. values applies to certain short-length set screws. These short-length screws are those whose length is approximately equal to the diameter of the screw. The larger *t* min. values apply to longer-length screws.

[b] A dog point set screw having a nominal length equal to or less than the length shown in the (*) column of the table is supplied with length *z* shown in the short dog column. For set screws of lengths greater than shown in the (*) column, *z* for long dogs applies.

All dimensions are in millimeters. For dimensional notation, see diagram, page 1637.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. British Standard Hexagon Socket Countersunk and Button Head Screws — Metric Series *BS 4168:1967*



COUNTERSUNK HEADSCREWS

Nom. Size[a]	Body Diameter, *D* Max.	Body Diameter, *D* Min.	Head Diameter, *A* Theor. Sharp Max.	Head Diameter, *A* Absolute Min.	Head Height, *H* Ref.	Head Height, *H* Flushness Tolerance	Hexagon Socket Size, *J* Nom.	Key Engagement, *K* Min.	Fillet Radius, *F* Max.
M3	3.00	2.86	6.72	5.82	1.86	0.20	2.00	1.05	0.40
M4	4.00	3.82	8.96	7.78	2.48	0.20	2.50	1.49	0.40
M5	5.00	4.82	11.20	9.78	3.10	0.20	3.00	1.86	0.40
M6	6.00	5.82	13.44	11.73	3.72	0.20	4.00	2.16	0.60
M8	8.00	7.78	17.92	15.73	4.96	0.24	5.00	2.85	0.70
M10	10.00	9.78	22.40	19.67	6.20	0.30	6.00	3.60	0.80
M12	12.00	11.73	26.88	23.67	7.44	0.36	8.00	4.35	1.10
(M14)	14.00	13.73	30.24	26.67	8.12	0.40	10.00	4.65	1.10
M16	16.00	15.73	33.60	29.67	8.80	0.45	10.00	4.89	1.10
(M18)	18.00	17.73	36.96	32.61	9.48	0.50	12.00	5.25	1.10
M20	20.00	19.67	40.32	35.61	10.16	0.54	12.00	5.45	1.10

[a] Sizes shown in parentheses are non-preferred.



BUTTON HEADSCREWS

Nom. Size, *D*	Head Diameter, *A* Max.	Head Diameter, *A* Min.	Head Height, *H* Max.	Head Height, *H* Min.	Head Side Height, *S* Ref.	Hexagon Socket Size, *J* Nom.	Key Engagement, *K* Min.	Fillet Radius *F* Min.	Fillet Radius d_a Max.
M3	5.50	5.32	1.60	1.40	0.38	2.00	1.04	0.10	3.60
M4	7.50	7.28	2.10	1.85	0.38	2.50	1.30	0.20	4.70
M5	9.50	9.28	2.70	2.45	0.50	3.00	1.56	0.20	5.70
M6	10.50	10.23	3.20	2.95	0.80	4.00	2.08	0.25	6.80
M8	14.00	13.73	4.30	3.95	0.80	5.00	2.60	0.40	9.20
M10	18.00	17.73	5.30	4.95	0.80	6.00	3.12	0.40	11.20
M12	21.00	20.67	6.40	5.90	0.80	8.00	4.16	0.60	14.20

All dimensions are given in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard Hexagon Socket Set Screws — Metric Series
BS 4168:Parts 2, 3, 4, and 5:1994



*The 120° angle is mandatory for short-length screws shown in the Standard. Short-length screws are those whose length is, approximately, equal to the diameter of the screw.

**The 45° angle applies only to that portion of the point below the root diameter, *df*, of the thread.

***The cone angle applies only to the portion of the point below the root diameter, *df*, of the thread and shall be 120° for certain short lengths listed in the Standard. All other lengths have a 90° cone angle.

†The popular length ranges of these set screws are listed in Table 3. These lengths have been selected from the following nominal lengths: 2, 2.5, 3, 4, 6, 8, 10, 12, 16, 20, 25, 30, 35, 40, 45, 50, 55, and 60 millimeters.

Holding Power of Set-screws.— While the amount of power a set-screw of given size will transmit without slipping (when used for holding a pulley, gear, or other part from turning relative to a shaft) varies somewhat according to the physical properties of both set-screw and shaft and other variable factors, experiments have shown that the safe holding force in pounds for different diameters of set-screws should be approximately as follows: For ¼-inch diameter set-screws the safe holding force is 100 pounds, for ⅜-inch

Copyright 2004, Industrial Press, Inc., New York, NY

diameter set-screws the safe holding force is 250 pounds, for ½-inch diameter set-screws the safe holding force is 500 pounds, for ¾-inch diameter set-screws the safe holding force is 1300 pounds, and for 1-inch diameter set-screws the safe holding force is 2500 pounds.

The power or torque that can be safely transmitted by a set-screw may be determined from the formulas, $P = (DNd^{2.3}) \div 50$; or $T = 1250Dd^{2.3}$ in which P is the horsepower transmitted; T is the torque in inch-pounds transmitted; D is the shaft diameter in inches; N is the speed of the shaft in revolutions per minute; and d is the diameter of the set-screw in inches.

Example: How many ½-inch diameter set-screws would be required to transmit 3 horsepower at a shaft speed of 1000 rpm if the shaft diameter is 1 inch?

Using the first formula given above, the power transmitted by a single ½-inch diameter set-screw is determined: $P = [1 \times 1000 \times (\frac{1}{2})^{2.3}] \div 50 = 4.1$ hp. Therefore a single ½-inch diameter set-screw is sufficient.

Example: In the previous example, how many ⅜-inch diameter set-screws would be required? $P = [1 \times 1000 \times (\frac{3}{8})^{2.3}] \div 50 = 2.1$ hp. Therefore two ⅜-inch diameter set-screws are required.

Table 5. British Standard Whitworth (BSW) and British Standard Fine (BSF) Bright Square Head Set-Screws (With Flat Chamfered Ends)



Nominal Size and Max. Dia., Inches	Number of Threads per Inch		No. 1 Standard		No. 2 Standard		No. 3 Standard	
	BSW	BSF	Width Across Flats *A*	Depth of Head *B*	Width Across Flats *C*	Depth of Head *D*	Width Across Flats *E*	Depth of Head *F*
¼	20	26	0.250	0.250	0.313	0.250	0.375	0.250
5/16	18	22	0.313	0.313	0.375	0.313	0.438	0.313
⅜	16	20	0.375	0.375	0.438	0.375	0.500	0.375
7/16	14	18	0.438	0.438	0.500	0.438	0.625	0.438
½	12	16	0.500	0.500	0.563	0.500	0.750	0.500
5/8	11	14	0.625	0.625	0.750	0.625	0.875	0.625
¾	10	12	0.750	0.750	0.875	0.750	1.000	0.750
⅞	9	11	0.875	0.875	1.000	0.875	1.125	0.875
1	8	10	1.000	1.000	1.125	1.000	1.250	1.000

* Depth of Head *B*, *D* and *F* same as for Width Across Flats, No. 1 Standard.

Dimensions *A*, *B*, *C*, *D*, *E*, and *F* are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

SELF-THREADING SCREWS

ANSI Standard Sheet Metal, Self-Tapping, and Metallic Drive Screws.— Table 1 shows the various types of "self-tapping" screw threads covered by the ANSI B18.6.4-1981 (R1991) standard. (Metric thread forming and thread cutting tapping screws are discussed beginning on page 1654). ANSI designations are also shown. Types A, AB, B, BP and C when turned into a hole of proper size form a thread by a displacing action. Types D, F, G, T, BF and BT when turned into a hole of proper size form a thread by a cutting action. Type U when driven into a hole of proper size forms a series of multiple threads by a displacing action. These screws have the following descriptions and applications:

Type A: Spaced-thread screw with gimlet point primarily for use in light sheet metal, resin-impregnated plywood, and asbestos compositions. This type is no longer recommended. Use Type AB in new designs and whenever possible substitute for Type A in existing designs.

Type AB: Spaced-thread screw with same pitches as Type B but with gimlet point, primarily for similar uses as for Type A.

Type B: Spaced-thread screw with a blunt point with pitches generally somewhat finer than Type A. Used for thin metal, non-ferrous castings, plastics, resin-impregnated plywood, and asbestos compositions.

Type BP: Spaced-thread screw, the same as Type B but having a conical point extending beyond incomplete entering threads. Used for piercing fabrics or in assemblies where holes are misaligned.

Type C: Screws having machine screw diameter-pitch combinations with threads approximately Unified Form and with blunt tapered points. Used where a machine screw thread is preferable to the spaced-thread types of thread forming screws. Also useful when chips from machine screw thread-cutting screws are objectionable. In view of the declining use of Type C screws, which in general require high driving torques, in favor of more efficient designs of thread tapping screws, they are not recommended for new designs.

Types D, F, G, and T: Thread-cutting screws with threads approximating machine screw threads, with blunt point, and with tapered entering threads having one or more cutting edges and chip cavities. The tapered threads of the Type F may be complete or incomplete at the producer's option; all other types have incomplete tapered threads. These screws can be used in materials such as aluminum, zinc, and lead die-castings; steel sheets and shapes; cast iron; brass; and plastics.

Types BF and BT: Thread-cutting screws with spaced threads as in Type B, with blunt points, and one or more cutting grooves. Used in plastics, asbestos, and other similar compositions.

Type U: Multiple-threaded drive screw with large helix angle, having a pilot point, for use in metal and plastics. This screw is forced into the work by pressure and is intended for making permanent fastenings.

ANSI Standard Head Types for Tapping and Metallic Drive Screws: Many of the head types used with "self-tapping" screw threads are similar to the head types of American National Standard machine screws shown in the section with that heading.

Round Head: The round head has a semi-elliptical top surface and a flat bearing surface. Because of the superior slot driving characteristics of pan head screws over round head screws, and the overlap in dimensions of cross recessed pan heads and round heads, it is recommended that pan head screws be used in new designs and wherever possible substituted in existing designs.

Undercut Flat and Oval Countersunk Heads: For short lengths, 82-degree and oval countersunk head tapping screws have heads undercut to 70 per cent of normal side height to afford greater length of thread on the screws.

Copyright 2004, Industrial Press, Inc., New York, NY

Flat Countersunk Head: The flat countersunk head has a flat top surface and a conical bearing surface with a head angle for one design of approximately 82 degrees and for another design of approximately 100 degrees. Because of its limited usage and in the interest of curtailing product varieties, the 100-degree flat countersunk head is considered nonpreferred.

Oval Countersunk Head: The oval countersunk head has a rounded top surface and a conical bearing surface with a head angle of approximately 82 degrees.

Flat and Oval Countersunk Trim Heads: Flat and oval countersunk trim heads are similar to the 82-degree flat and oval countersunk heads except that the size of head for a given size screw is one (large trim head) or two (small trim head) sizes smaller than the regular flat and oval countersunk head size. Oval countersunk trim heads have a definite radius where the curved top surface meets the conical bearing surface. Trim heads are furnished only in cross recessed types.

Pan Head: The slotted pan head has a flat top surface rounded into cylindrical sides and a flat bearing surface. The recessed pan head has a rounded top and a flat bearing surface. This head type is now preferred to the round head.

Fillister Head: The fillister head has a rounded top surface, cylindrical sides, and a flat bearing surface.

Hex Head: The hex head has a flat or indented top surface, six flat sides, and a flat bearing surface. Because the slotted hex head requires a secondary operation in manufacture which often results in burrs at the extremity of the slot that interfere with socket wrench engagement and the wrenching capability of the hex far exceeds that of the slot, it is not recommended for new designs.

Hex Washer Head: The hex washer head has an indented top surface and six flat sides formed integrally with a flat washer that projects beyond the sides and provides a flat bearing surface. Because the slotted hex washer head requires a secondary operation in manufacture which often results in burrs at the extremity of the slot that often interferes with socket wrench engagement and because the wrenching capability of the hex far exceeds that of the slot in the indented head, it is not recommended for new designs.

Truss Head: The truss head has a low rounded top surface with a flat bearing surface, the diameter of which for a given screw size is larger than the diameter of the corresponding round head. In the interest of product simplification and recognizing that the truss head is an inherently weak design, it is not recommended for new designs.

Method of Designation.— Tapping screws are designated by the following data in the sequence shown: Nominal size (number, fraction or decimal equivalent); threads per inch; nominal length (fraction or decimal equivalent); point type; product name, including head type and driving provision; material; and protective finish, if required.
Examples:

$\frac{1}{4}$–14 × 1$\frac{1}{2}$ Type AB Slotted Pan Head Tapping Screw, Steel, Nickel Plated

6–32 × $\frac{3}{4}$ Type T, Type 1A Cross Recessed Pan Head Tapping Screw, Corrosion Resistant Steel

0.375–16 × 1.50 Type D, Washer Head Tapping Screw, Steel

Metallic Drive Screws: Type U metallic drive screws are designated by the following data in the sequence shown: Nominal size (number, fraction, or decimal equivalent); nominal length (fraction or decimal equivalent); product name, including head type; material; and protective finish, if required. Examples:

10 × $\frac{5}{16}$ Round Head Metallic Drive Screw, Steel

0.312 × 0.50 Round Head Metallic Drive Screw, Steel, Zinc Plated

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Standard Threads and Points for Thread Forming Self-Tapping Screws *ANSI B18.6.4-1981 (R1991)*



See Tables 3, 5, and 6 for thread data.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Standard Threads and Points for Thread Cutting Self-Tapping Screws *ANSI B18.6.4-1981 (R1991)*



See Tables 5 and 7 for thread data.

Cross Recesses.— Type I cross recess has a large center opening, tapered wings, and blunt bottom, with all edges relieved or rounded. Type IA cross recess has a large center opening, wide straight wings, and blunt bottom, with all edges relieved or rounded. Type II consists of two intersecting slots with parallel sides converging to a slightly truncated apex at the bottom of the recess. Type III has a square center opening, slightly tapered side walls, and a conical bottom, with top edges relieved or rounded.

Table 3. ANSI Standard Cross Recesses for Self-Tapping Screws *ANSI B18.6.4-1981 (R1991)* **and Metric Thread Forming and Thread Cutting Tapping Screws** *ANSI/ASME B18.6.5M-1986*



Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ANSI Standard Thread and Point Dimensions for Types AB, A and U Thread Forming Tapping Screws *ANSI B18.6.4-1981 (R1991)*

Type AB (Formerly BA)								
Nominal Size or Basic Screw Diameter		Threads per inch	D Major Diameter Max.	D Major Diameter Min.	d Minor Diameter Max.	d Minor Diameter Min.	L Minimum Practical Screw Lengths 90° Heads	L Minimum Practical Screw Lengths Csk. Heads
0	0.0600	48	0.060	0.054	0.036	0.033	1/8	5/32
1	0.0730	42	0.075	0.069	0.049	0.046	5/32	3/16
2	**0.0860**	**32**	**0.088**	**0.082**	**0.064**	**0.060**	3/16	7/32
3	0.0990	28	0.101	0.095	0.075	0.071	3/16	1/4
4	**0.1120**	**24**	**0.114**	**0.108**	**0.086**	**0.082**	7/32	9/32
5	0.1250	20	0.130	0.123	0.094	0.090	1/4	5/16
6	**0.1380**	**20**	**0.139**	**0.132**	**0.104**	**0.099**	9/32	11/32
7	0.1510	19	0.154	0.147	0.115	0.109	5/16	3/8
8	**0.1640**	**18**	**0.166**	**0.159**	**0.122**	**0.116**	5/16	3/8
10	**0.1900**	**16**	**0.189**	**0.182**	**0.141**	**0.135**	3/8	7/16
12	0.2160	14	0.215	0.208	0.164	0.157	7/16	21/32
1/4	**0.2500**	**14**	**0.246**	**0.237**	**0.192**	**0.185**	1/2	19/32
5/16	0.3125	12	0.315	0.306	0.244	0.236	5/8	3/4
3/8	0.3750	12	0.380	0.371	0.309	0.299	3/4	29/32
7/16	0.4375	10	0.440	0.429	0.359	0.349	7/8	1 1/32
1/2	0.5000	10	0.504	0.493	0.423	0.413	1	1 5/32

Type A								
Nominal Size[a] Basic Screw Diameter		Threads per inch	D Major Diameter Max.	D Major Diameter Min.	d Minor Diameter Max.	d Minor Diameter Min.	L These Lengths or Shorter — Use Type AB 90° Heads	L These Lengths or Shorter — Use Type AB Csk. Heads
0	0.0600	40	0.060	0.057	0.042	0.039	1/8	3/16
1	0.0730	32	0.075	0.072	0.051	0.048	1/8	3/16
2	0.0860	32	0.088	0.084	0.061	0.056	5/32	3/16
3	0.0990	28	0.101	0.097	0.076	0.071	3/16	7/32
4	0.1120	24	0.114	0.110	0.083	0.078	3/16	1/4
5	0.1250	20	0.130	0.126	0.095	0.090	3/16	1/4
6	0.1380	18	0.141	0.136	0.102	0.096	1/4	5/16
7	0.1510	16	0.158	0.152	0.114	0.108	5/16	3/8
8	0.1640	15	0.168	0.162	0.123	0.116	3/8	7/16
10	0.1900	12	0.194	0.188	0.133	0.126	3/8	1/2
12	0.2160	11	0.221	0.215	0.162	0.155	7/16	9/16
14	0.2420	10	0.254	0.248	0.185	0.178	1/2	5/8
16	0.2680	10	0.280	0.274	0.197	0.189	9/16	3/4
18	0.2940	9	0.306	0.300	0.217	0.209	5/8	13/16
20	0.3200	9	0.333	0.327	0.234	0.226	11/16	13/16
24	0.3720	9	0.390	0.383	0.291	0.282	3/4	1

[a] Where specifying nominal size in decimals, zeros preceding decimal and in fourth place are omitted.

Type U Metallic Drive Screws											
Nom. Size	No. of Starts	Out. Dia. Max.	Out. Dia. Min.	Pilot Dia. Max.	Pilot Dia. Min.	Nom. Size	No. of Starts	Out. Dia. Max.	Out. Dia. Min.	Pilot Dia. Max.	Pilot Dia. Min.
00	6	0.060	0.057	0.049	0.046	8	8	0.167	0.162	0.136	0.132
0	6	0.075	0.072	0.063	0.060	10	8	0.182	0.177	0.150	0.146
2	8	0.100	0.097	0.083	0.080	12	8	0.212	0.206	0.177	0.173
4	7	0.116	0.112	0.096	0.092	14	9	0.242	0.236	0.202	0.198
6	7	0.140	0.136	0.116	0.112	5/16	11	0.315	0.309	0.272	0.267
7	8	0.154	0.150	0.126	0.122	3/8	12	0.378	0.371	0.334	0.329

All dimensions are in inches. See Table 1 for thread diagrams.

Sizes shown in bold face type are preferred. Type A screws are no longer recommended.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ANSI Standard Thread and Point Dimensions for B and BP Thread Forming and BF and BT Thread Cutting Tapping Screws *ANSI B18.6.4-1981 (R1991)*

THREAD FORMING TYPES B AND BP														
Nominal Size[a] or Basic Screw Diameter		Thds per Inch[b]	D		d		P		S		L			
			Major Diameter		Minor Diameter		Point Diameter[c]		Point Taper Length[d]		Minimum Practical Nominal Screw Lengths			
											Type B		Type BP	
			Max	Min	Max	Min	Max	Min	Max	Min	90° Heads	Csk Heads	90° Heads	Csk Heads
0	0.0600	48	0.060	0.054	0.036	0.033	0.031	0.027	0.042	0.031	1/8	1/8	5/32	3/16
1	0.0730	42	0.075	0.069	0.049	0.046	0.044	0.040	0.048	0.036	1/8	5/32	3/16	7/32
2	0.0860	32	0.088	0.082	0.064	0.060	0.058	0.054	0.062	0.047	5/32	3/16	1/4	9/32
3	0.0990	28	0.101	0.095	0.075	0.071	0.068	0.063	0.071	0.054	3/16	7/32	9/32	5/16
4	0.1120	24	0.114	0.108	0.086	0.082	0.079	0.074	0.083	0.063	3/16	1/4	5/16	11/32
5	0.1250	20	0.130	0.123	0.094	0.090	0.087	0.082	0.100	0.075	7/32	9/32	11/32	13/32
6	0.1380	20	0.139	0.132	0.104	0.099	0.095	0.089	0.100	0.075	1/4	9/32	3/8	7/16
7	0.1510	19	0.154	0.147	0.115	0.109	0.105	0.099	0.105	0.079	1/4	5/16	13/32	15/32
8	0.1640	18	0.166	0.159	0.122	0.116	0.112	0.106	0.111	0.083	9/32	11/32	7/16	1/2
10	0.1900	16	0.189	0.182	0.141	0.135	0.130	0.123	0.125	0.094	5/16	3/8	1/2	19/32
12	0.2160	14	0.215	0.208	0.164	0.157	0.152	0.145	0.143	0.107	11/32	7/16	9/16	21/32
1/4	0.2500	14	0.246	0.237	0.192	0.185	0.179	0.171	0.143	0.107	3/8	1/2	21/32	3/4
5/16	0.3125	12	0.315	0.306	0.244	0.236	0.230	0.222	0.167	0.125	15/32	19/32	27/32	31/32
3/8	0.3750	12	0.380	0.371	0.309	0.299	0.293	0.285	0.167	0.125	17/32	11/16	15/16	1 1/8
7/16	0.4375	10	0.440	0.429	0.359	0.349	0.343	0.335	0.200	0.150	5/8	25/32	1 1/8	1 1/4
1/2	0.5000	10	0.504	0.493	0.423	0.413	0.407	0.399	0.200	0.150	11/16	27/32	1 1/4	1 13/32

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place shall be omitted.

[b] The width of flat at crest of thread shall not exceed 0.004 inch for sizes up to No. 8, inclusive, and 0.006 inch for larger sizes.

[c] Point diameters specified apply to screw threads before roll threading.

[d] Points of screws are tapered and fluted or slotted. The flute on Type BT screws has an included angle of 90 to 95 degrees and the thread cutting edge is located above the axis of the screw. Flutes and slots extend through first full form thread beyond taper except for Type BF screw on which tapered threads may be complete at manufacturer's option and flutes may be one pitch short of first full form thread.

THREAD CUTTING TYPES BF AND BT[d]												
Nominal Size[a] or Basic Screw Diameter		Thds per Inch[b]	D		d		P		S		L	
			Major Diameter		Minor Diameter		Point Diameter[c]		Point Taper Length[d]		Minimum Practical Nominal Screw Lengths	
											90° Heads	Csk Heads
			Max	Min	Max	Min	Max	Min	Max	Min		
0	0.0600	48	0.060	0.054	0.036	0.033	0.031	0.027	0.042	0.031	1/8	1/8
1	0.0730	42	0.075	0.069	0.049	0.046	0.044	0.040	0.048	0.036	1/8	5/32
2	0.0860	32	0.088	0.082	0.064	0.060	0.058	0.054	0.062	0.047	5/32	3/16
3	0.0990	28	0.101	0.095	0.075	0.071	0.068	0.063	0.071	0.054	3/16	7/32
4	0.1120	24	0.114	0.108	0.086	0.082	0.079	0.074	0.083	0.063	3/16	1/4
5	0.1250	20	0.130	0.123	0.094	0.090	0.087	0.082	0.100	0.075	7/32	9/32
6	0.1380	20	0.139	0.132	0.104	0.099	0.095	0.089	0.100	0.075	1/4	9/32
7	0.1510	19	0.154	0.147	0.115	0.109	0.105	0.099	0.105	0.079	1/4	5/16
8	0.1640	18	0.166	0.159	0.122	0.116	0.112	0.106	0.111	0.083	9/32	11/32
10	0.1900	16	0.189	0.182	0.141	0.135	0.130	0.123	0.125	0.094	5/16	3/8
12	0.2160	14	0.215	0.208	0.164	0.157	0.152	0.145	0.143	0.107	11/32	7/16
1/4	0.2500	14	0.246	0.237	0.192	0.185	0.179	0.171	0.143	0.107	3/8	1/2
5/16	0.3125	12	0.315	0.306	0.244	0.236	0.230	0.222	0.167	0.125	15/32	19/32
3/8	0.3750	12	0.380	0.371	0.309	0.299	0.293	0.285	0.167	0.125	17/32	11/16
7/16	0.4375	10	0.440	0.429	0.359	0.349	0.343	0.335	0.200	0.150	5/8	25/32
1/2	0.5000	10	0.504	0.493	0.423	0.413	0.407	0.399	0.200	0.150	11/16	27/32

All dimensions are in inches. See Tables 1 and 2 for thread diagrams.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Thread and Point Dimensions for Type C Thread Forming Tapping Screws (ANSI B18.6.4–1981, R1991 Appendix)

Nominal Size[a] or Basic Screw Diameter		Threads per inch	D		P		S				L			
			Major Diameter		Point Diameter[b]		Point Taper Length[c]				Determinant Lengths for Point Taper[c]		Minimum Practical Nominal Screw Lengths	
							For Short Screws		For Long Screws					
			Max	Min	Max	Min	Max	Min	Max	Min	90° Heads	Csk Heads	90° Heads	Csk Heads
2	0.0860	56	0.0860	0.0813	0.068	0.061	0.062	0.045	0.080	0.062	5/32	3/16	5/32	3/16
2	0.0860	64	0.0860	0.0816	0.070	0.064	0.055	0.039	0.070	0.055	1/8	3/16	1/8	5/32
3	0.0990	48	0.0990	0.0938	0.078	0.070	0.073	0.052	0.094	0.073	3/16	7/32	5/32	7/32
3	0.0990	56	0.0990	0.0942	0.081	0.074	0.062	0.045	0.080	0.062	5/32	3/16	5/32	3/16
4	0.1120	40	0.1120	0.1061	0.087	0.078	0.088	0.062	0.112	0.088	7/32	1/4	3/16	1/4
4	0.1120	48	0.1120	0.1068	0.091	0.083	0.073	0.052	0.094	0.073	3/16	7/32	5/32	7/32
5	0.1250	40	0.1250	0.1191	0.100	0.091	0.088	0.062	0.112	0.088	7/32	9/32	3/16	1/4
5	0.1250	44	0.1250	0.1195	0.102	0.094	0.080	0.057	0.102	0.080	3/16	1/4	3/16	1/4
6	0.1380	32	0.1380	0.1312	0.107	0.096	0.109	0.078	0.141	0.109	1/4	5/16	1/4	5/16
6	0.1380	40	0.1380	0.1321	0.113	0.104	0.088	0.062	0.112	0.088	7/32	9/32	3/16	1/4
8	0.1640	32	0.1640	0.1571	0.132	0.122	0.109	0.078	0.141	0.109	1/4	11/32	1/4	5/16
8	0.1640	36	0.1640	0.1577	0.136	0.126	0.097	0.069	0.125	0.097	7/32	5/16	7/32	9/32
10	0.1900	24	0.1900	0.1818	0.148	0.135	0.146	0.104	0.188	0.146	11/32	7/16	5/16	13/32
10	0.1900	32	0.1900	0.1831	0.158	0.148	0.109	0.078	0.141	0.109	1/4	11/32	1/4	5/16
12	0.2160	24	0.2160	0.2078	0.174	0.161	0.146	0.104	0.188	0.146	11/32	7/16	5/16	13/32
12	0.2160	28	0.2160	0.2085	0.180	0.168	0.125	0.089	0.161	0.125	5/16	13/32	9/32	3/8
1/4	0.2500	20	0.2500	0.2408	0.200	0.184	0.175	0.125	0.225	0.175	13/32	17/32	3/8	1/2
1/4	0.2500	28	0.2500	0.2425	0.214	0.202	0.125	0.089	0.161	0.125	5/16	13/32	9/32	3/8
5/16	0.3125	18	0.3125	0.3026	0.257	0.239	0.194	0.139	0.250	0.194	15/32	19/32	7/16	9/16
5/16	0.3125	24	0.3125	0.3042	0.271	0.257	0.146	0.104	0.188	0.146	11/32	15/32	5/16	15/32
3/8	0.3750	16	0.3750	0.3643	0.312	0.293	0.219	0.156	0.281	0.219	1/2	11/16	15/32	5/8
3/8	0.3750	24	0.3750	0.3667	0.333	0.319	0.146	0.104	0.188	0.146	11/32	1/2	5/16	1/2
7/16	0.4375	14	0.4375	0.4258	0.366	0.344	0.250	0.179	0.321	0.250	19/32	3/4	9/16	23/32
7/16	0.4375	20	0.4375	0.4281	0.387	0.371	0.175	0.125	0.225	0.175	13/32	9/16	3/8	17/32
1/2	0.5000	13	0.5000	0.4876	0.423	0.399	0.269	0.192	0.346	0.269	5/8	25/32	19/32	3/4
1/2	0.5000	20	0.5000	0.4906	0.450	0.433	0.175	0.125	0.225	0.175	13/32	9/16	3/8	17/32

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place shall be omitted.

[b] The tabulated values apply to screw blanks before roll threading.

[c] Screws of these nominal lengths and shorter shall have point taper length specified above for short screws. Longer lengths shall have point taper length specified for long screws.

All dimensions are in inches. See Table 1 for thread diagrams. Type C is not recommended for new designs.

Tapered threads shall have unfinished crests.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. ANSI Standard Thread and Point Dimensions for Types D, F, G, and T Thread Cutting Tapping Screws *ANSI B18.6.4-1981 (R1991)*

Nominal Size[a] or Basic Screw Diameter	Threads per inch	D Major Diameter Max	D Major Diameter Min	P Point Diameter[b] Max	P Point Diameter[b] Min	S Point Taper Length[c] For Short Screws Max	S Point Taper Length[c] For Short Screws Min	S Point Taper Length[c] For Long Screws Max	S Point Taper Length[c] For Long Screws Min	L Determinant Lengths for Point Taper[c] 90° Heads	L Determinant Lengths for Point Taper[c] Csk Heads	L Minimum Practical Nominal Screw Lengths 90° Heads	L Minimum Practical Nominal Screw Lengths Csk Heads
2 0.0860	56	0.0860	0.0813	0.068	0.061	0.062	0.045	0.080	0.062	5/32	3/16	5/32	3/16
2 0.0860	64	0.0860	0.0816	0.070	0.064	0.055	0.039	0.070	0.055	1/8	3/16	1/8	5/32
3 0.0990	48	0.0990	0.0938	0.078	0.070	0.073	0.052	0.094	0.073	3/16	7/32	5/32	7/32
3 0.0990	56	0.0990	0.0942	0.081	0.074	0.062	0.045	0.080	0.062	5/32	3/16	5/32	3/16
4 0.1120	40	0.1120	0.1061	0.087	0.078	0.088	0.062	0.112	0.088	7/32	1/4	3/16	1/4
4 0.1120	48	0.1120	0.1068	0.091	0.083	0.073	0.052	0.094	0.073	3/16	7/32	5/32	7/32
5 0.1250	40	0.1250	0.1191	0.100	0.091	0.088	0.062	0.112	0.088	7/32	9/32	3/16	1/4
5 0.1250	44	0.1250	0.1195	0.102	0.094	0.080	0.057	0.102	0.080	3/16	1/4	3/16	1/4
6 0.1380	32	0.1380	0.1312	0.107	0.096	0.109	0.078	0.141	0.109	1/4	5/16	1/4	5/16
6 0.1380	40	0.1380	0.1321	0.113	0.104	0.088	0.062	0.112	0.088	7/32	9/32	3/16	1/4
8 0.1640	32	0.1640	0.1571	0.132	0.122	0.109	0.078	0.141	0.109	1/4	11/32	1/4	5/16
8 0.1640	36	0.1640	0.1577	0.136	0.126	0.097	0.069	0.125	0.097	7/32	5/16	7/32	9/32
10 0.1900	24	0.1900	0.1818	0.148	0.135	0.146	0.104	0.188	0.146	11/32	7/16	5/16	13/32
10 0.1900	32	0.1900	0.1831	0.158	0.148	0.109	0.078	0.141	0.109	1/4	11/32	1/4	5/16
12 0.2160	24	0.2160	0.2078	0.174	0.161	0.146	0.104	0.188	0.146	11/32	7/16	5/16	13/32
12 0.2160	28	0.2160	0.2085	0.180	0.168	0.125	0.089	0.161	0.125	5/16	13/32	9/32	3/8
1/4 0.2500	20	0.2500	0.2408	0.200	0.184	0.175	0.125	0.225	0.175	13/32	17/32	3/8	1/2
1/4 0.2500	28	0.2500	0.2425	0.214	0.202	0.125	0.089	0.161	0.125	5/16	13/32	9/32	3/8
5/16 0.3125	18	0.3125	0.3026	0.257	0.239	0.194	0.139	0.250	0.194	15/32	19/32	7/16	9/16
5/16 0.3125	24	0.3125	0.3042	0.271	0.257	0.146	0.104	0.188	0.146	11/32	15/32	5/16	15/32
3/8 0.3750	16	0.3750	0.3643	0.312	0.293	0.219	0.156	0.281	0.219	1/2	11/16	15/32	5/8
3/8 0.3750	24	0.3750	0.3667	0.333	0.319	0.146	0.104	0.188	0.146	11/32	1/2	5/16	1/2
7/16 0.4375	14	0.4375	0.4258	0.366	0.344	0.250	0.179	0.321	0.250	19/32	3/4	9/16	21/32
7/16 0.4375	20	0.4375	0.4281	0.387	0.371	0.175	0.125	0.225	0.175	13/32	9/16	3/8	17/32
1/2 0.5000	13	0.5000	0.4876	0.423	0.399	0.269	0.192	0.346	0.269	5/8	25/32	19/32	3/4
1/2 0.5000	20	0.5000	0.4906	0.450	0.433	0.175	0.125	0.225	0.175	13/32	9/16	3/8	17/32

[a] Where specifying nominal size in decimals, zeros preceding decimal and in the fourth decimal place shall be omitted.

[b] The tabulated values apply to screw blanks before roll threading.

[c] Screws of these nominal lengths and shorter shall have point taper length specified above for short screws. Longer lengths shall have point taper length specified for long screws.

All dimensions are in inches. See Table 2 for thread diagrams.

Type "Type D" otherwise designated "Type 1."

Type "Type T" otherwise designated "Type 23."

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Approximate Hole Sizes for Type A Steel Thread Forming Screws

In Steel, Stainless Steel, Monel Metal, Brass, and Aluminum Sheet Metal									
Screw Size	Metal Thickness	Hole Size: Pierced or Extruded	Hole Size: Drilled or Clean Punched	Drill Size	Screw Size	Metal Thickness	Hole Size: Pierced or Extruded	Hole Size: Drilled or Clean Punched	Drill Size
4	0.015	…	0.086	44	8	0.024	0.136	0.125	1/8
	0.018	…	0.086	44		0.030	0.136	0.125	1/8
	0.024	0.098	0.094	42		0.036	0.136	0.125	1/8
	0.030	0.098	0.094	42		0.048	0.136	0.128	30
	0.036	0.098	0.098	40	10	0.018	…	0.136	29
6	0.015	…	0.104	37		0.024	0.157	0.136	29
	0.018	…	0.104	37		0.030	0.157	0.136	29
	0.024	0.111	0.104	37		0.036	0.157	0.136	29
	0.030	0.111	0.104	37		0.048	0.157	0.149	25
	0.036	0.111	0.106	36	12	0.024	…	0.161	20
7	0.015	…	0.116	32		0.030	0.185	0.161	20
	0.018	…	0.116	32		0.036	0.185	0.161	20
	0.024	0.120	0.116	32		0.048	0.185	0.161	20
	0.030	0.120	0.116	32	14	0.024	…	0.185	13
	0.036	0.120	0.116	32		0.030	0.209	0.189	12
	0.048	0.120	0.120	31		0.036	0.209	0.191	11
8	0.018	…	0.125	1/8		0.048	0.209	0.196	9

In Plywood (Resin Impregnated)						In Asbestos Compositions					
Screw Size	Hole Size	Drill Size	Min. Mat'l Thickness	Penetration in Blind Holes: Min.	Penetration in Blind Holes: Max.	Screw Size	Hole Size	Drill Size	Min. Mat'l Thickness	Penetration in Blind Holes: Min.	Penetration in Blind Holes: Max.
4	0.098	40	0.188	0.250	0.750	4	0.094	42	0.188	0.250	0.750
6	0.110	35	0.188	0.250	0.750	6	0.106	36	0.188	0.250	0.750
7	0.128	30	0.250	0.312	0.750	7	0.125	1/8	0.250	0.312	0.750
8	0.140	28	0.250	0.312	0.750	8	0.136	29	0.250	0.312	0.750
10	0.170	18	0.312	0.375	1.000	10	0.161	20	0.312	0.375	1.000
12	0.189	12	0.312	0.375	1.000	12	0.185	13	0.312	0.375	1.000
14	0.228	1	0.438	0.500	1.000	14	0.213	3	0.438	0.500	1.000

Type A is not recommended, use Type AB.

See footnote at bottom of Table 9.

Table 9. Approximate Hole Sizes for Type C Steel Thread Forming Screws

In Sheet Steel											
Screw Size	Metal Thickness	Hole Size	Drill Size	Screw Size	Metal Thickness	Hole Size	Drill Size	Screw Size	Metal Thickness	Hole Size	Drill Size
4–40	0.037	0.094	42	10-24	0.037	0.154	23	1/4–20	0.037	0.221	2
	0.048	0.094	42		0.048	0.161	20		0.048	0.221	2
	0.062	0.096	41		0.062	0.166	19		0.062	0.228	1
	0.075	0.100	39		0.075	0.170	18		0.075	0.234	A
	0.105	0.102	38		0.105	0.173	17		0.105	0.234	A
	0.134	0.102	38		0.134	0.177	16		0.134	0.236	6mm
6–32	0.037	0.113	33	10–32	0.037	0.170	18	1/4–28	0.037	0.224	5.7mm
	0.048	0.116	32		0.048	0.170	18		0.048	0.228	1
	0.062	0.116	32		0.062	0.170	18		0.062	0.232	5.9mm
	0.075	0.122	3.1mm		0.075	0.173	17		0.075	0.234	A
	0.105	0.125	1/8		0.105	0.177	16		0.105	0.238	B
	0.134	0.125	1/8		0.134	0.177	16		0.134	0.238	B
8–32	0.037	0.136	29	12–24	0.037	0.189	12	5/16–18	0.037	0.290	L
	0.048	0.144	27		0.048	0.194	10		0.048	0.290	L
	0.062	0.144	27		0.062	0.194	10		0.062	0.290	L
	0.075	0.147	26		0.075	0.199	8		0.075	0.295	M
	0.105	0.150	25		0.105	0.199	8		0.105	0.295	M
	0.134	0.150	25		0.134	0.199	8		0.134	0.295	M

All dimensions are in inches except drill sizes. It may be necessary to vary the hole size to suit a particular application.

Type C is not recommended for new designs.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Approximate Pierced or Extruded Hole Sizes for Types AB, B, and BP Steel Thread Forming Screws

Screw Size	Metal Thickness	Pierced or Extruded Hole Size	Screw Size	Metal Thickness	Pierced or Extruded Hole Size	Screw Size	Metal Thickness	Pierced or Extruded Hole Size
In Steel, Stainless Steel, Monel Metal, and Brass Sheet Metal								
4	0.015	0.086	7	0.024	0.120	10	0.030	0.157
	0.018	0.086		0.030	0.120		0.036	0.157
	0.024	0.098		0.036	0.120		0.048	0.157
	0.030	0.098		0.048	0.120	12	0.024	0.185
	0.036	0.098	8	0.018	0.136		0.030	0.185
6	0.015	0.111		0.024	0.136		0.036	0.185
	0.018	0.111		0.030	0.136		0.048	0.185
	0.024	0.111		0.036	0.136	1/4	0.030	0.209
	0.030	0.111		0.048	0.136		0.036	0.209
	0.036	0.111	10	0.018	0.157		0.048	0.209
7	0.018	0.120		0.024	0.157	…	…	…
In Aluminum Alloy Sheet Metal								
4	0.024	0.086	6	0.048	0.111	8	0.036	0.136
	0.030	0.086	7	0.024	0.120		0.048	0.136
	0.036	0.086		0.030	0.120	10	0.024	0.157
	0.048	0.086		0.036	0.120		0.030	0.157
6	0.024	0.111		0.048	0.120		0.036	0.157
	0.030	0.111	8	0.024	0.136		0.048	0.157
	0.036	0.111		0.030	0.136	…	…	…

All dimensions are in inches except whole number screw and drill sizes.

Since conditions differ widely, it may be necessary to vary the hole size to suit a particular application.

Table 11. Drilled Hole Sizes for Types AB, B, and BP Steel Thread Forming Screws

Screw Size	Hole Size	Drill Size	Min. Mat'l Thickness	Penetration in Blind Holes		Screw Size	Hole Size	Drill Size	Min. Mat'l Thickness	Penetration in Blind Holes	
				Min.	Max.					Min.	Max.
In Plywood (Resin Impregnated)						In Asbestos Compositions					
2	0.073	49	0.125	0.188	0.500	2	0.076	48	0.125	0.188	0.500
4	0.100	39	0.188	0.250	0.625	4	0.101	38	0.188	0.250	0.625
6	0.125	1/8	0.188	0.250	0.625	6	0.120	31	0.188	0.250	0.625
7	0.136	29	0.188	0.250	0.750	7	0.136	29	0.250	0.312	0.750
8	0.144	27	0.188	0.250	0.750	8	0.147	26	0.312	0.375	0.750
10	0.173	17	0.250	0.312	1.000	10	0.166	19	0.312	0.375	1.000
12	0.194	10	0.312	0.375	1.000	12	0.196	9	0.312	0.375	1.000
1/4	0.228	1	0.312	0.375	1.000	1/4	0.228	1	0.438	0.500	1.000
In Aluminum, Magnesium, Zinc, Brass, and Bronze Castings[a]						In Phenol Formaldehyde Plastics[a]					
2	0.078	47	…	0.125	…	2	0.078	47	…	0.188	…
4	0.104	37	…	0.188	…	4	0.100	39	…	0.250	…
6	0.128	30	…	0.250	…	6	0.128	30	…	0.250	…
7	0.144	27	…	0.250	…	7	0.136	29	…	0.250	…
8	0.152	24	…	0.250	…	8	0.150	25	…	0.312	…
10	0.177	16	…	0.250	…	10	0.177	16	…	0.312	…
12	0.199	8	…	0.281	…	12	0.199	8	…	0.375	…
1/4	0.234	15/64	…	0.312	…	1/4	0.234	15/64	…	0.375	…
In Cellulose Acetate and Nitrate, and Acrylic and Styrene Resins[a]											
2	0.078	47	…	0.188	…	8	0.144	27	…	0.312	…
4	0.094	42	…	0.250	…	10	0.170	18	…	0.312	…
6	0.120	31	…	0.250	…	12	0.191	11	…	0.375	…
7	0.128	30	…	0.250	…	1/4	0.221	2	…	0.375	…

[a] Data below apply to Types B and BP only.

All dimensions are in inches except whole number screw and drill sizes.

Since conditions differ widely, it may be necessary to vary the hole size to suit a particular application.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12a. Approximate Drilled or Clean-Punched Hole Sizes for Types AB, B, and BP Steel Thread Forming Screws

Screw Size	Metal Thickness	Hole Size	Drill Size	Screw Size	Metal Thickness	Hole Size	Drill Size	Screw Size	Metal Thickness	Hole Size	Drill Size
In Steel, Stainless Steel, Monel Metal, and Brass Sheet Metal											
	0.015	0.064	52		0.018	0.116	32		0.125	0.170	18
	0.018	0.064	52		0.024	0.116	32	10	0.135	0.170	18
	0.024	0.067	51		0.030	0.116	32		0.164	0.173	17
2	0.030	0.070	50	7	0.036	0.116	32		0.024	0.166	19
	0.036	0.073	49		0.048	0.120	31		0.030	0.166	19
	0.048	0.073	49		0.060	0.128	30		0.036	0.166	19
	0.060	0.076	48		0.075	0.136	29		0.048	0.170	18
	0.015	0.086	44		0.105	0.140	28		0.060	0.177	16
	0.018	0.086	44		0.024	0.125	1/8	12	0.075	0.182	14
	0.024	0.089	43		0.030	0.125	1/8		0.105	0.185	13
4	0.030	0.094	42		0.036	0.125	1/8		0.125	0.196	9
	0.036	0.094	42		0.048	0.128	30		0.135	0.196	9
	0.048	0.096	41	8	0.060	0.136	29		0.164	0.201	7
	0.060	0.100	39		0.075	0.140	28		0.030	0.194[a]	10[a]
	0.075	0.102	38		0.105	0.150	25		0.036	0.194[a]	10[a]
	0.015	0.104	37		0.125	0.150	25		0.048	0.194[a]	10[a]
	0.018	0.104	37		0.135	0.152	24		0.060	0.199[a]	8[a]
	0.024	0.106	36		0.024	0.144	27		0.075	0.204[a]	6[a]
	0.030	0.106	36		0.030	0.144	27	1/4	0.105	0.209	4
6	0.036	0.110	35		0.036	0.147	26		0.125	0.228	1
	0.048	0.111	34	10	0.048	0.152[a]	24[a]		0.135	0.228	1
	0.060	0.116	32		0.060	0.152[a]	24[a]		0.164	0.234	15/64
	0.075	0.120	31		0.075	0.157	22		0.187	0.234	15/64
	0.105	0.128	30		0.105	0.161	20		0.194	0.234	15/64
In Aluminum Alloy Sheet Metal											
	0.024	0.064	52		0.060	0.120	31		0.164	0.159	21
	0.030	0.064	52		0.075	0.128	30	10	0.200		
2	0.036	0.064	52	7	0.105	0.136	29		to	0.166	19
	0.048	0.067	51		0.128				0.375		
	0.060	0.070	50		to	0.136	29		0.048	0.161	20
	0.030	0.086	44		0.250				0.060	0.166	19
	0.036	0.086	44		0.030	0.116	32		0.075	0.173	17
	0.048	0.086	44		0.036	0.120	31		0.105	0.180	15
4	0.060	0.089	43		0.048	0.128	30	12	0.125	0.182	14
	0.075	0.089	43		0.060	0.136	29		0.135	0.182	14
	0.105	0.094	42		0.075	0.140	28		0.164	0.189	12
	0.030	0.104	37	8	0.105	0.147	26		0.200		
	0.036	0.104	37		0.125	0.147	26		to	0.196	9
	0.048	0.104	37		0.135	0.149	25		0.375		
	0.060	0.106	36		0.162				0.060	0.199	8
6	0.75	0.110	35		to	0.152	24		0.075	0.201	7
	0.105	0.111	34		0.375				0.105	0.204	6
	0.128				0.036	0.144	27		0.125	0.209	4
	to	120	31		0.048	0.144	27		0.135	0.209	4
	250				0.060	0.144	27	1/4	0.164	0.213	3
	0.030	0.113	33	10	0.075	0.147	26		0.187	0.213	3
7	0.036	0.113	33		0.105	0.147	26		0.194	0.221	2
	0.048	0.116	32		0.125	0.154	23		0.200		
					0.135	0.154	23		to	228	1
									0.375		

[a] For Types B and BP only; for Type AB see concluded Table 12b following.

Since conditions differ widely, it may be necessary to vary the hole size to suit a particular application. Hole sizes for metal thicknesses above 0.075 inch are for Types B and BP only.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12b. Supplementary Data for Types AB Thread Forming Screws in Steel, Stainless Steel, Monel Metal, and Brass Sheet Metal

Screw Size	Metal Thick-ness	Hole Size	Drill Size	Screw Size	Metal Thick-ness	Hole Size	Drill Size	Screw Size	Metal Thick-ness	Hole Size	Drill Size
In Steel, Stainless Steel, Monel Metal, and Brass Sheet Metal											
10	0.018	0.144	27	1/4	0.018	0.196	9	1/4	0.048	0.205	5
10	0.048	0.149	25	1/4	0.024	0.196	9	1/4	0.060	0.228	1
10	0.060	0.154	23	1/4	0.030	0.196	9	1/4	0.075	0.232	5.9 mm
…	…	…	…	1/4	0.036	0.196	9	…	…	…	…

All dimensions are in inches except numbered screw and drill sizes.

Table 13. Approximate Hole Sizes for Types D, F, G, and T Steel Thread Cutting Screws in Sheet Metals

		Steel		Aluminum Alloy				Steel		Aluminum Alloy	
Screw Size	Thick-ness	Hole Size	Drill Size	Hole Size	Drill Size	Screw Size	Thick-ness	Hole Size	Drill Size	Hole Size	Drill Size
2–56	0.050	0.073	49	0.070	50	8–32	0.187	0.150	25	0.147	26
	0.060	0.073	49	0.073	49		0.250	0.150	25	0.150	25
	0.083	0.073	49	0.073	49		0.312	0.150	25	0.150	25
	0.109	0.073	49	0.073	49	10–24	0.050	0.152	24	0.150	25
	0.125	0.076	48	0.073	49		0.060	0.154	23	0.152	24
	0.140	0.076	48	0.073	49		0.083	0.161	20	0.154	23
3–48	0.050	0.081	46	0.078	5/64		0.109	0.161	20	0.157	22
	0.060	0.081	46	0.081	46		0.125	0.166	19	0.159	21
	0.083	0.082	45	0.082	45		0.140	0.170	18	0.161	20
	0.109	0.086	44	0.082	45		0.187	0.173	17	0.166	19
	0.125	0.086	44	0.082	45		0.250	0.173	17	0.172	11/64
	0.140	0.086	44	0.086	44		0.312	0.173	17	0.173	17
	0.187	0.089	43	0.086	44		0.375	0.173	17	0.173	17
4–40	0.050	0.089	43	0.089	43	10–32	0.050	0.159	21	0.161	20
	0.060	0.089	43	0.089	43		0.060	0.166	19	0.161	20
	0.083	0.094	42	0.089	43		0.083	0.166	19	0.161	20
	0.109	0.096	41	0.094	42		0.109	0.170	18	0.166	19
	0.125	0.098	40	0.094	42		0.125	0.170	18	0.166	19
	0.140	0.098	40	0.094	3/32		0.140	0.170	18	0.166	19
	0.187	0.102	38	0.098	40		0.187	0.177	16	0.172	11/64
5–40	0.050	0.106	36	0.102	38		0.250	0.177	16	0.177	16
	0.060	0.106	36	0.102	38		0.312	0.177	16	0.177	16
	0.083	0.106	36	0.104	37		0.375	0.177	16	0.177	16
	0.109	0.106	36	0.104	37	12–24	0.060	0.180	15	0.177	16
	0.125	0.109	7/64	0.106	36		0.083	0.182	14	0.180	15
	0.140	0.110	35	0.106	36		0.109	0.188	3/16	0.182	14
	0.187	0.116	32	0.110	35		0.125	0.191	11	0.185	13
	0.250	0.116	32	0.113	33		0.140	0.191	11	0.188	3/16
6–32	0.050	0.110	35	0.109	7/64		0.187	0.199	8	0.191	11
	0.060	0.113	33	0.109	7/64		0.250	0.199	8	0.199	8
	0.083	0.116	32	0.111	34		0.312	0.199	8	0.199	8
	0.109	0.116	32	0.113	33		0.375	0.199	8	0.199	8
	0.125	0.116	32	0.116	32		0.500	0.199	8	0.199	8
	0.140	0.120	31	0.116	32	1/4–20	0.083	0.213	3	0.206	5
	0.187	0.125	1/8	0.120	31		0.109	0.219	7/32	0.209	4
	0.250	0.125	1/8	0.125	1/8		0.125	0.221	2	0.213	3
8–32	0.050	0.136	29	0.136	29		0.140	0.221	2	0.213	3
	0.060	0.140	28	0.136	29		0.187	0.228	1	0.221	2
	0.083	0.140	28	0.136	29		0.250	0.228	1	0.228	1
	0.109	0.144	27	0.140	28		0.312	0.228	1	0.228	1
	0.125	0.144	27	0.140	28		0.375	0.228	1	0.228	1
	0.140	0.147	26	0.144	27		0.500	0.228	1	0.228	1

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **Approximate Hole Sizes for Types D, F, G, and T Steel Thread Cutting Screws in Sheet Metals**

Screw Size	Thick-ness	Steel		Aluminum Alloy		Screw Size	Thick-ness	Steel		Aluminum Alloy	
		Hole Size	Drill Size	Hole Size	Drill Size			Hole Size	Drill Size	Hole Size	Drill Size
1/4–28	0.083	0.221	2	0.219	7/32	5/16–24	0.187	0.295	M	0.290	L
	0.109	0.228	1	0.221	2		0.250	0.295	M	0.295	M
	0.125	0.228	1	0.221	2		0.312	0.295	M	0.295	M
	0.140	0.234	A	0.221	2		0.375	0.295	M	0.295	M
	0.187	0.234	15/64	0.228	1		0.500	0.295	M	0.295	M
	0.250	0.234	15/64	0.234	15/64	3/8–16	0.125	0.339	R	0.328	21/64
	0.312	0.234	15/64	0.234	15/64		0.140	0.339	R	0.332	Q
	0.375	0.234	15/64	0.234	15/64		0.187	0.348	S	0.339	R
	0.500	0.234	15/64	0.234	15/64		0.250	0.358	T	0.348	S
5/16–18	0.109	0.277	J	0.266	H		0.312	0.358	T	0.348	S
	0.125	0.277	J	0.272	I		0.375	0.358	T	0.348	S
	0.140	0.281	9/32	0.272	I		0.500	0.358	T	0.348	S
	0.187	0.290	L	0.281	K	3/8–24	0.125	0.348	S	0.344	11/32
	0.250	0.290	L	0.290	L		0.140	0.348	S	0.344	11/32
	0.312	0.290	L	0.290	L		0.187	0.358	T	0.348	S
	0.375	0.290	L	0.290	L		0.250	0.358	T	0.358	T
	0.500	0.290	L	0.290	L		0.312	0.358	T	0.358	T
5/16–24	0.109	0.290	L	0.281	K		0.375	0.358	T	0.358	T
	0.125	0.290	L	0.281	9/32		0.500	0.358	T	0.358	T
	0.140	0.290	L	0.281	9/32		…	…	…	…	…

All dimensions are in inches except numbered drill and screw sizes. It may be necessary to vary the hole size to suit a particular application.

Table 14. Approximate Hole Sizes for Types D, F, G, and T Steel Thread Cutting Screws in Cast Metals and Plastics

Screw Size	Thick-ness	Cast Iron		Zinc and Aluminum[a]		Screw Size	Thick-ness	Cast Iron		Zinc and Aluminum[a]	
		Hole Size	Drill Size	Hole Size	Drill Size			Hole Size	Drill Size	Hole Size	Drill Size
2–56	0.050	0.076	48	0.073	49	5–40	0.083	0.113	33	0.106	36
	0.060	0.076	48	0.073	49		0.109	0.113	33	0.110	35
	0.083	0.076	48	0.076	48		0.125	0.116	32	0.110	35
	0.109	0.078	5/64	0.076	48		0.140	0.116	32	0.110	35
	0.125	0.078	5/64	0.076	48		0.187	0.116	32	0.111	34
	0.140	0.078	5/64	0.076	48		0.250	0.116	32	0.113	33
3–48	0.050	0.089	43	0.082	45	6–32	0.050	0.120	31	0.116	32
	0.060	0.089	43	0.082	45		0.060	0.120	31	0.120	31
	0.083	0.089	43	0.082	45		0.083	0.125	1/8	0.120	31
	0.109	0.089	43	0.086	44		0.109	0.125	1/8	0.120	31
	0.125	0.089	43	0.089	43		0.125	0.125	1/8	0.120	31
	0.140	0.094	42	0.089	43		0.140	0.125	1/8	0.120	31
	0.187	0.094	42	0.089	43		0.187	0.128	30	0.120	31
4–40	0.050	0.100	39	0.090	41		0.250	0.128	30	0.120	31
	0.060	0.100	39	0.096	41	8–32	0.050	0.147	26	0.144	27
	0.083	0.102	38	0.096	41		0.060	0.150	25	0.144	27
	0.109	0.102	38	0.096	41		0.083	0.150	25	0.144	27
	0.125	0.102	38	0.100	39		0.109	0.150	25	0.144	27
	0.140	0.102	38	0.100	39		0.125	0.150	25	0.147	26
	0.187	0.104	37	0.100	39		0.140	0.150	25	0.147	26
5–40	0.050	0.111	34	0.106	36		0.187	0.154	23	0.147	26
	0.060	0.111	34	0.106	36		0.250	0.154	23	0.150	25
							0.312	0.154	23	0.150	25

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. *(Continued)* Approximate Hole Sizes for Types D, F, G, and T Steel Thread Cutting Screws in Cast Metals and Plastics

Screw Size	Thick-ness	Cast Iron		Zinc and Aluminum[a]	
		Hole Size	Drill Size	Hole Size	Drill Size
10–24	0.050	0.170	18	0.161	20
	0.060	0.170	18	0.166	19
	0.083	0.172	11/64	0.166	19
	0.109	0.173	17	0.166	19
	0.125	0.173	17	0.166	19
	0.140	0.173	17	0.166	19
	0.187	0.177	16	0.170	18
	0.250	0.177	16	0.170	18
	0.312	0.177	16	0.172	11/64
	0.375	0.177	16	0.172	11/64
10–32	0.050	0.173	17	0.170	18
	0.060	0.173	17	0.170	18
	0.083	0.177	16	0.172	11/64
	0.109	0.177	16	0.172	11/64
	0.125	0.177	16	0.172	11/64
	0.140	0.177	16	0.172	11/64
	0.187	0.180	15	0.172	11/64
	0.250	0.180	15	0.173	17
	0.312	0.180	15	0.173	17
	0.375	0.180	15	0.177	16
12–24	0.060	0.196	9	0.189	12
	0.083	0.199	8	0.191	11
	0.109	0.199	8	0.191	11
	0.125	0.199	8	0.191	11
	0.140	0.199	8	0.194	10
	0.187	0.203	13/64	0.194	10
	0.250	0.204	6	0.196	9
	0.312	0.204	6	0.196	9
	0.375	0.204	6	0.199	8
	0.500	0.204	6	0.199	8
1/4–20	0.083	0.228	1	0.219	7/32
	0.109	0.228	1	0.219	7/32
	0.125	0.228	1	0.221	2
	0.140	0.228	1	0.221	2
	0.187	0.234	15/64	0.221	2
	0.250	0.234	15/64	0.228	1
	0.312	0.234	15/64	0.228	1
	0.375	0.234	15/64	0.228	1
	0.500	0.234	15/64	0.228	1
1/4–28	0.083	0.234	A	0.228	1
	0.109	0.234	15/64	0.228	1
	0.125	0.234	15/64	0.228	1
	0.140	0.234	15/64	0.228	1
	0.187	0.238	B	0.228	1
	0.250	0.238	B	0.234	A
	0.312	0.238	B	0.234	A
	0.375	0.238	B	0.234	15/64
	0.500	0.238	B	0.234	15/64
5/16–18	0.109	0.290	L	0.277	J
	0.125	0.290	L	0.281	K
	0.140	0.290	L	0.281	K
	0.187	0.295	M	0.281	9/32
	0.250	0.295	M	0.281	9/32
	0.312	0.295	M	0.290	L
	0.375	0.295	M	0.290	L
	0.500	0.295	M	0.290	L
5/16–24	0.109	0.295	M	0.290	L
	0.125	0.295	M	0.290	L
	0.140	0.295	M	0.290	L
	0.187	0.302	N	0.290	L
	0.250	0.302	N	0.290	L
	0.312	0.302	N	0.295	M
	0.375	0.302	N	0.295	M
	0.500	0.302	N	0.295	M
3/8–16	0.125	0.348	S	0.339	R
	0.140	0.348	S	0.339	R
	0.187	0.348	S	0.339	R
	0.250	0.348	S	0.344	11/32
	0.312	0.348	S	0.344	11/32
	0.375	0.348	S	0.348	S
	0.500	0.348	S	0.348	S
3/8–24	0.125	0.358	T	0.348	S
	0.140	0.358	T	0.348	S
	0.187	0.358	T	0.348	S
	0.250	0.358	T	0.358	T
	0.312	0.358	T	0.358	T
	0.375	0.358	T	0.358	T
	0.500	0.358	T	0.358	T

[a] Die Castings

Screw Size	Phenol Formaldehyde[a]				Cellulose Acetate, Cellulose Nitrate, Acrylic Resin, and Styrene Resin[a]			
	Hole Size	Drill Size	Depth of Penetration		Hole Size	Drill Size	Depth of Penetration	
			Min	Max			Min	Max
2–56	0.078	5/64	0.219	0.375	0.076	48	0.219	0.375
3–48	0.089	43	0.219	0.375	0.086	44	0.219	0.375
4–40	0.098	40	0.250	0.312	0.093	42	0.250	0.312
5–40	0.113	33	0.250	0.438	0.110	35	0.250	0.438
6–32	0.116	32	0.250	0.312	0.116	32	0.250	0.312
8–32	0.144	27	0.312	0.500	0.144	27	0.312	0.500
10–24	0.161	20	0.375	0.500	0.161	20	0.375	0.500
10–32	0.166	19	0.375	0.500	0.166	19	0.375	0.500
1/4–20	0.228	1	0.375	0.625	0.228	1	0.375	1.000

[a] Plastics

For footnotes see Table 13.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Approximate Hole Sizes for Types BF and BT Steel Thread Cutting Screws in Cast Metals

In Die Cast Zinc and Aluminum							
Screw Size	Thickness	Hole Size	Drill Size	Screw Size	Thickness	Hole Size	Drill Size
2	0.060	0.073	49	10	0.125	0.166	19
	0.083	0.073	49		0.140	0.166	19
	0.109	0.076	48		0.188	0.166	19
	0.125	0.076	48		0.250	0.170	18
	0.140	0.076	48		0.312	0.172	11/64
3	0.060	0.086	44		0.375	0.172	11/64
	0.083	0.086	44	12	0.125	0.191	11
	0.109	0.086	44		0.140	0.191	11
	0.125	0.086	44		0.188	0.191	11
	0.140	0.089	43		0.250	0.196	9
	0.188	0.089	43		0.312	0.196	9
4	0.109	0.098	40		0.375	0.196	9
	0.125	0.100	39	1/4	0.125	0.221	2
	0.140	0.100	39		0.140	0.221	2
	0.188	0.100	39		0.188	0.221	2
	0.250	0.102	38		0.250	0.228	1
5	0.109	0.111	34		0.312	0.228	1
	0.125	0.111	34		0.375	0.228	1
	0.140	0.113	33	5/16	0.125	0.281	K
	0.188	0.113	33		0.140	0.281	K
	0.250	0.116	32		0.188	0.281	K
6	0.125	0.120	31		0.250	0.281	K
	0.140	0.120	31		0.312	0.290	L
	0.188	0.120	31		0.375	0.290	L
	0.250	0.125	1/8	3/8	0.125	0.344	11/32
	0.312	0.125	1/8		0.140	0.344	11/32
8	0.125	0.149	25		0.188	0.344	11/32
	0.140	0.149	25		0.250	0.344	11/32
	0.188	0.149	25		0.312	0.348	S
	0.250	0.152	24		0.375	0.348	S
	0.312	0.152	24		…	…	…

All dimensions are in inches except numbered drill and screw sizes. It may be necessary to vary the hole size to suit a particular application.

Table 16. Approximate Hole Size for Types BF and BT Steel Thread Cutting Screws in Plastics

	Phenol Formaldehyde				Cellulose Acetate, Cellulose Nitrate, Acrylic Resin and Styrene Resin			
Screw Size	Hole Size	Drill Size	Depth of Penetration		Hole Size	Drill Size	Depth of Penetration	
			Min	Max			Min	Max
2	0.078	5/64	0.094	0.250	0.076	48	0.094	0.250
3	0.089	43	0.125	0.312	0.089	43	0.125	0.312
4	0.104	37	0.125	0.312	0.100	39	0.125	0.312
5	0.116	32	0.188	0.375	0.113	33	0.188	0.375
6	0.125	1/8	0.188	0.375	0.120	31	0.188	0.375
8	0.147	26	0.250	0.500	0.144	27	0.250	0.500
10	0.170	18	0.312	0.625	0.166	19	0.312	0.625
12	0.194	10	0.375	0.625	0.189	12	0.375	0.625
1/4	0.228	1	0.375	0.750	0.221	2	0.375	0.750

For footnotes see above table.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. Approximate Hole Sizes for Type U Hardened Steel Metallic Drive Screws

In Ferrous and Non-Ferrous Castings, Sheet Metals, Plastics, Plywood (Resin-Impregnated) and Fiber								
Screw Size	Hole Size	Drill Size	Screw Size	Hole Size	Drill Size	Screw Size	Hole Size	Drill Size
00	.052	55	6	.120	31	12	.191	11
0	.067	51	7	.136	29	14	.221	2
2	.086	44	8	.144	27	5/16	.295	M
4	.104	37	10	.161	20	3/8	.358	T

All dimensions are in inches except whole number screw and drill sizes and letter drill sizes.

Table 18. ANSI Standard Torsional Strength Requirements for Tapping Screws
ANSI B18.6.4-1981 (R1991)

Nom. Screw Size	Type A	Types AB,B,BF, BP,andBT	Types C, D, F, G, and T		Nom-Screw Size	Type A	Types AB, B, BF, BP, and BT	Types C, D, F, G, and T	
			Coarse Thread	Fine Thread				Coarse Thread	Fine Thread
2	4	4	5	6	1/4	…	142	140	179
3	9	9	9	10	16	152	…	…	…
4	12	13	13	15	18	196	…	…	…
5	18	18	18	20	5/16	…	290	306	370
6	24	24	23	27	20	250	…	…	…
7	30	30	…	…	24	492	…	…	…
8	39	39	42	47	3/8	…	590	560	710
10	48	56	56	74	7/16	…	620	700	820
12	83	88	93	108	1/2	…	1020	1075	1285
14	125	…	…	…	…	…	…	…	…

Torsional strength data are in pound-inches.

Self-tapping Thread Inserts.— Self-tapping screw thread inserts are essentially hard bushings with internal and external threads. The internal threads conform to Unified and American standard classes 2B and 3B, depending on the type of insert used. The external thread has cutting edges on the end that provide the self-tapping feature. These inserts may be used in magnesium, aluminum, cast iron, zinc, plastics, and other materials. Self-tapping inserts are made of case-hardened carbon steel, stainless steel, and brass, the brass type being designed specifically for installation in wood.

Screw Thread Inserts.— Screw thread inserts are helically formed coils of diamond-shaped stainless steel or phosphor bronze wire that screw into a threaded hole to form a mating internal thread for a screw or stud. These inserts provide a convenient means of repairing stripped-out threads and are also used to provide stronger threads in soft materials such as aluminum, zinc die castings, wood, magnesium, etc. than can be obtained by direct tapping of the base metal involved.

According to the Heli-Coil Corp., conventional design practice in specifying boss diameters or edge distances can usually be applied since the major diameter of a hole tapped to receive a thread insert is not much larger than the major diameter of thread the insert provides.

Screw thread inserts are available in thread sizes from 4–40 to 1½–6 inch National and Unified Coarse Thread Series and in 6–40 to 1½–12 sizes in the fine-thread series. When used in conjunction with appropriate taps and gages, screw thread inserts will meet requirements of 2, 2B, 3, and 3B thread classes.

ANSI Standard Metric Thread Forming and Thread Cutting Tapping Screws.—

Table 1 shows the various types of metric thread forming and thread cutting screw threads covered by the standard ANSI/ASME B18.6.5M-1986. The designations of the American National Standards Institute are shown.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Standard Threads and Points for Metric Thread Forming and Thread Cutting Tapping Screws *ANSI/ASME B18.6.5M-1986*



See Tables 3 and 4 for thread data.

Thread Forming Tapping Screws: These types are generally for application in materials where large internal stresses are permissible or desirable, to increase resistance to loosening. These screws have the following descriptions and applications:

Copyright 2004, Industrial Press, Inc., New York, NY

Type AB: Spaced thread screw with gimlet point primarily intended for use in thin metal, resin impregnated plywood, and asbestos compositions.

Type B: Spaced thread screw with a blunt point that has tapered entering threads with unfinished crests and same pitches as Type AB. Used for thin metal, nonferrous castings, resin impregnated plywood, certain resilient plastics, and asbestos compositions.

Thread Cutting Tapping Screws: These screws are generally for application in materials where disruptive internal stresses are undesirable or where excessive driving torques are encountered with thread forming tapping screws. These screws have the following descriptions and applications:

Types BF and BT: Spaced threads with blunt point and tapered entering threads having unfinished crests, as on Type B, with one or more cutting edges or chip cavities, intended for use in plastics, asbestos compositions, and other similar materials.

Types D, F, and T: Tapping screws with threads of machine screw diameter-pitch combinations (metric coarse thread series) approximating a 60 degree basic thread form (not necessarily conforming to any standard thread profile) with a blunt point and tapered entering threads with unfinished crests and having one or more cutting edges and chip cavities, intended for use in materials such as aluminum, zinc, and lead die castings; steel sheets and shapes; cast iron; brass; and plastics.

ANSI Standard Head Types for Metric Thread Forming and Cutting Tapping Screws.— The head types covered by ANSI/ASME B18.6.5M-1986 include those commonly applicable to metric tapping screws and are described as follows:

Flat Countersunk Head: The flat countersunk head has a flat top surface and a conical bearing surface with a head angle of 90 to 92 degrees.

Oval Countersunk Head: The oval countersunk head has a rounded top surface and a conical bearing surface with a head angle of 90 to 92 degrees.

Pan Head: The slotted pan head has a flat top surface rounding into cylindrical sides and a flat bearing surface. The recessed pan head has a rounded top surface blending into cylindrical sides and a flat bearing surface.

Hex Head: The hex head has a flat or indented top surface, six flat sides, and a flat bearing surface.

Hex Flange Head: The hex flange head has a flat or indented top surface and six flat sides formed integrally with a frustroconical or slightly rounded (convex) flange that projects beyond the sides and provides a flat bearing surface.

Method of Designation.— Metric tapping screws are designated with the following data, preferably in the sequence shown: Nominal size; thread pitch; nominal length; thread and point type; product name, including head style and driving provision; material; and protective finish, if required.

Examples:

$6.3 \times 1.8 \times 30$ Type AB, Slotted Pan Head Tapping Screw, Steel, Zinc Plated

$6 \times 1 \times 20$ Type T, Type 1A Cross Recessed Pan Head Tapping Screw, Corrosion Resistant Steel

$4.2 \times 1.4 \times 13$ Type BF, Type 1 Cross Recessed Oval Countersunk Head Tapping Screw, Steel, Chromium Plated

$10 \times 1.5 \times 40$ Type D, Hex Flange Head Tapping Screw, Steel

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Recommended Nominal Screw Lengths for Metric Tapping Screws
ANSI/ASME B18.6.5M-1986

Nominal Screw Length	Nominal Screw Size for Types AB, B, BF, and BT									
	2.2	-	2.9	3.5	4.2	4.8	5.5	6.3	8	9.5
	Nominal Screw Size for Types D, F, and T									
	2	2.5	3	3.5	4	5	-	6	8	10
4	PH	PH								
5	PH	PH								
6	A	A	PH							
8	A	A	A	PH	PH					
10	A	A	A	A	A	PH				
13	A	A	A	A	A	A	A	PH		
16		A	A	A	A	A	A	A	PH	
20				A	A	A	A	A	A	PH
25				A	A	A	A	A	A	A
30						A	A	A	A	A
35						A	A	A	A	A
40							A	A	A	A
45									A	A
50									A	A
55										A
60										A

Table 3. ANSI Standard Thread and Point Dimensions for Types AB and B Metric Thread Forming Tapping Screws *ANSI/ASME B18.6.5M-1986*

Nominal Screw Size and Thread Pitch[a]	Basic Screw Diameter	Basic Thread Pitch	D_1		D_2		D_3		Y		Z	L			
			Thread Major Diameter		Thread Minor Diameter		Point Diameter[b]		Point Taper Length Type B[c]		Point Length Factor TypeAB	Min. Practical Nominal Screw Length[d]			
												Type AB		Type B	
	Ref[e]	Ref[e]	Max	Min	Max	Min	Max	Min	Max	Min	Ref[f]	Note 7	Note 8	Note 7	Note 8
2.2 × 0.8	2.184	0.79	2.24	2.10	1.63	1.52	1.47	1.37	1.6	1.2	2.0	4	6	4	5
2.9 × 1	2.845	1.06	2.90	2.76	2.18	2.08	2.01	1.88	2.1	1.6	2.6	6	7	5	7
3.5 × 1.3	3.505	1.27	3.53	3.35	2.64	2.51	2.41	2.26	2.5	1.9	3.2	7	9	6	8
4.2 × 1.4	4.166	1.41	4.22	4.04	3.10	2.95	2.84	2.69	2.8	2.1	3.7	8	10	7	10
4.8 × 1.6	4.826	1.59	4.80	4.62	3.58	3.43	3.30	3.12	3.2	2.4	4.3	9	12	8	11
5.5 × 1.8	5.486	1.81	5.46	5.28	4.17	3.99	3.86	3.68	3.6	2.7	5.0	11	14	9	12
6.3 × 1.8	6.350	1.81	6.25	6.03	4.88	4.70	4.55	4.34	3.6	2.7	6.0	12	16	10	13
8 × 2.1	7.938	2.12	8.00	7.78	6.20	5.99	5.84	5.64	4.2	3.2	7.5	16	20	12	17
9.5 × 2.1	9.525	2.12	9.65	9.43	7.85	7.59	7.44	7.24	4.2	3.2	8.0	19	24	14	19

[a] The body diameter (unthreaded portion) is not less than the minimum minor diameter nor greater than the maximum major diameter of the thread.

[b] The tabulated values shall apply to screw blanks prior to roll threading.

[c] The tabulated maximum limits are equal to approximately two times the thread pitch.

[d] Lengths shown are theoretical minimums and are intended to assist the user in the selection of appropriate short screw lengths. Refer to Table 2 for recommended diameter-length combinations.

[e] Basic screw diameter and basic thread pitch shall be used for calculation purposes wherever these factors appear in formulations for dimensions.

[f] The minimum effective grip length on Type AB tapping screws shall be determined by subtracting the point length factor from the minimum screw length.

All dimensions are in millimeters. See Table 1 for thread diagrams.

[7] Pan, hex, and hex flange heads.

[8] Flat and oval countersunk heads.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ANSI Standard Thread and Point Dimensions for Types BF, BT, D, F, and T Metric Thread Cutting Tapping Screws *ANSI/ASME B18.6.5M-1986*

Types BF and BT												
Nominal Screw Size and Thread Pitch	Basic Screw Diameter	Basic Thread Pitch	D_1 Thread Major Diameter		D_2 Thread Minor Diameter		D_3 Point Diameter[a]		Y Point Taper Length Type B[b]		L Minimal Practical Nominal Screw Length[c]	
	Ref[d]	Ref[d]	Max	Min	Max	Min	Max	Min	Max	Min	Pan, Hex and Hex Flange Heads	Flat and Oval Csunk Heads
2.2 × 0.8	2.184	0.79	2.24	2.10	1.63	1.52	1.47	1.37	1.6	1.2	4	5
2.9 × 1	2.845	1.06	2.90	2.76	2.18	2.08	2.01	1.88	2.1	1.6	5	7
3.5 × 1.3	3.505	1.27	3.53	3.35	2.64	2.51	2.41	2.26	2.5	1.9	6	8
4.2 × 1.4	4.166	1.41	4.22	4.04	3.10	2.95	2.84	2.69	2.8	2.1	7	10
4.8 × 1.6	4.826	1.59	4.80	4.62	3.58	3.43	3.30	3.12	3.2	2.4	8	11
5.5 × 1.8	5.486	1.81	5.46	5.28	4.17	3.99	3.86	3.68	3.6	2.7	9	12
6.3 × 1.8	6.350	1.81	6.25	6.03	4.88	4.70	4.55	4.34	3.6	2.7	10	13
8 × 2.1	7.938	2.12	8.00	7.78	6.20	5.99	5.84	5.64	4.2	3.2	12	17
9.5 × 2.1	9.525	2.12	9.65	9.43	7.85	7.59	7.44	7.24	4.2	3.2	14	19

[a] The tabulated values apply to screw blanks prior to roll threading.

[b] The tabulated maximum limits are equal to approximately two times the thread pitch.

[c] Lengths shown are theoretical minimums and are intended to assist in the selection of appropriate short screw lengths. See Table 2 for recommended length-diameter combinations. For Types D, F, and T, shorter screws are available with the point length reduced to the limits tabulated for short screws.

[d] Basic screw diameter and basic thread pitch are used for calculation purposes whenever these factors appear in formulations for dimensions.

Types D, F, T										
Nominal Screw Size and Thread Pitch	D_1 Thread Major Diameter		D_3 Point Diameter[a]		D_S Body Diameter[a]	Y Point Taper Length				L Minimum Practical Nominal Screw Length[c]	
						For Short Screws		For Long Screws[b]		Pan, Hex and Hex Flange Heads	Flat and Oval Csunk Heads
	Max	Min	Max	Min	Min	Max	Min	Max	Min		
2 × 0.4	2.00	1.88	1.45	1.39	1.65	1.4	1.0	1.8	1.4	4	5
2.5 × 0.45	2.50	2.37	1.88	1.82	2.12	1.6	1.1	2.0	1.6	4	6
3 × 0.5	3.00	2.87	2.32	2.26	2.58	1.8	1.3	2.3	1.8	5	6
3.5 × 0.6	3.50	3.35	2.68	2.60	3.00	2.1	1.5	2.7	2.1	5	8
4 × 0.7	4.00	3.83	3.07	2.97	3.43	2.5	1.8	3.2	2.5	6	9
5 × 0.8	5.00	4.82	3.94	3.84	4.36	2.8	2.0	3.6	2.8	7	10
6 × 1	6.00	5.79	4.69	4.55	5.21	3.5	2.5	4.5	3.5	9	12
8 × 1.25	8.00	7.76	6.40	6.24	7.04	4.4	3.1	5.6	4.4	11	16
10 × 1.5	10.00	9.73	8.08	7.88	8.86	5.3	3.8	6.8	5.3	13	18

[a] Minimum limits for body diameter (unthreaded portion) are tabulated for convenient reference. For Types BF and BT, the body diameter is not less than the minimum minor diameter nor greater than the maximum major diameter of the thread.

[b] Long screws are screws of nominal lengths equal to or longer than those listed under L.

All dimensions are in millimeters. See Table 1 for thread diagrams.

Material and Heat Treatment.— Tapping screws are normally fabricated from carbon steel and are suitably processed to meet the performance and test requirements outlined in the standard, B18.6.5M. Tapping screws may also be made from corrosion resistant steel, Monel, brass, and aluminum alloys. The materials, properties, and performance characteristics applicable to such screws should be mutually agreed upon between the manufacturer and the purchaser.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Clearance Holes for Metric Tapping Screws
ANSI/ASME B18.6.5M-1986 **Appendix**

Nominal Screw Size and Thread Pitch	Basic Clearance Hole Diameter[a]			Nominal Screw Size and Thread Pitch	Basic Clearance Hole Diameter[a]		
	Close Clearance[b]	Normal Clearance (Preferred)[b]	Loose Clearance[b]		Close Clearance[b]	Normal Clearance (Preferred)[b]	Loose Clearance[b]
	Types AB, B, BF, and BT				Types D, F, and T		
2.2 ×0.8	2.40	2.60	2.80	2 ×0.4	2.20	2.40	2.60
2.9 ×1	3.10	3.30	3.50	2.5 ×0.45	2.70	2.90	3.10
3.5 ×1.3	3.70	3.90	4.20	3 ×0.5	3.20	3.40	3.60
4.2 ×1.4	4.50	4.70	5.00	3.5 ×0.6	3.70	3.90	4.20
4.8 ×1.6	5.10	5.30	5.60	4 ×0.7	4.30	4.50	4.80
5.5 ×1.8	5.90	6.10	6.50	5 ×0.8	5.30	5.50	5.80
6.3×1.8	6.70	6.90	7.30	6 ×1	6.40	6.60	7.00
8 ×2.1	8.40	9.00	10.00	8 ×1.25	8.40	9.00	10.00
9.5 ×2.1	10.00	10.50	11.50	10 ×1.5	10.50	11.00	12.00

[a] The values given in this table are minimum limits. The recommended plus tolerances are as follows: for clearance hole diameters over 1.70 to and including 5.80 mm, plus 0.12, 0.20, and 0.30 mm for close, normal, and loose clearances, respectively; over 5.80 to and including 14.50 mm, plus 0.18, 0.30, and 0.45 mm for close, normal, and loose clearances, respectively.

[b] Normal clearance hole sizes are preferred. Close clearance hole sizes are for situations such as critical alignment of assembled components, wall thickness, or other limitations that necessitate the use of a minimal hole. Countersinking or counterboring at the fastener entry side may be necessary for the proper seating of the head. Loose clearance hole sizes are for applications where maximum adjustment capability between the components being assembled is necessary.

All dimensions are in millimeters.

Approximate Installation Hole Sizes for Metric Tapping Screws.— The approximate hole sizes given in Tables 7 through 9 provide general guidance in selecting holes for installing the respective types of metric thread forming and thread cutting tapping screws in various commonly used materials. Types AB, B, BF, and BT metric tapping screws are covered in these tables; hole sizes for Types D, F, and T metric thread cutting tapping screws are still under development.

Table 6. Approximate Pierced or Extruded Hole Sizes for Steel Types AB and B Metric Thread Forming Tapping Screws

Nominal Screw Size andThread Pitch	Metal Thickness	Hole Size	Nominal Screw Size andThread Pitch	Metal Thickness	Hole Size	Nominal Screw Size andThread Pitch	Metal Thickness	Hole Size
In Steel, Stainless Steel, Monel, and Brass Sheet Metal								
	0.38	2.18		0.46	3.45		0.61	4.70
	0.46	2.18		0.61	3.45		0.76	4.70
2.9 × 1	0.61	2.49	4.2 × 1.4	0.76	3.45	5.5 × 1.8	0.91	4.70
	0.76	2.49		0.91	3.45		1.22	4.70
	0.91	2.49		1.22	3.45		…	…
	0.38	2.82		0.46	3.99		0.76	5.31
	0.46	2.82		0.61	3.99		0.91	5.31
3.5 × 1.3	0.61	2.82	4.8 × 1.6	0.76	3.99	6.3 × 1.8	1.22	5.31
	0.76	2.82		0.91	3.99		…	…
	0.91	2.82		1.22	3.99		…	…
In Aluminum Alloy								
	0.61	2.18	3.5 × 1.3	0.91	2.82		0.61	3.99
2.9 × 1	0.76	2.18		1.22	2.82		0.76	3.99
	0.91	2.18		0.61	3.45	4.8 × 1.6	0.91	3.99
	1.22	2.18	4.2 × 1.4	0.76	3.45		1.22	3.99
3.5 × 1.3	0.61	2.82		0.91	3.45		…	…
	0.76	2.82		1.22	3.45		…	…

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Approximate Drilled or Clean-Punched Hole Sizes for Steel Type AB Metric Thread Forming Tapping Screws in Sheet Metal

Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]	Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]	Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]
In Steel, Stainless Steel, Monel, and Brass Sheet Metal											
2.2 × 0.8	0.38	1.63	52	3.5 × 1.3	0.61	2.69	36	4.8 × 1.6	1.22	3.78	25
	0.46	1.63	52		0.76	2.69	36		1.52	3.91	23
	0.61	1.70	51		0.91	2.79	35		1.90	3.99	22
	0.76	1.78	50		1.22	2.82	34	5.5 × 1.8	0.46	…	…
	0.91	1.85	49		1.52	2.95	32		0.61	4.22	19
	1.22	1.85	49		1.90	3.05	31		0.76	4.22	19
	1.52	1.93	48	4.2 × 1.4	0.46	…	…		0.91	4.22	19
2.9 × 1	0.38	2.18	44		0.61	3.18	…		1.22	4.32	18
	0.46	2.18	44		0.76	3.18	…		1.52	4.50	16
	0.61	2.26	43		0.91	3.18	…		1.90	4.62	14
	0.76	2.39	42		1.22	3.25	30	6.3 × 1.8	0.46	4.98	9
	0.91	2.39	42		1.52	3.45	29		0.61	4.98	9
	1.22	2.44	41		1.90	3.56	28		0.76	4.98	9
	1.52	2.54	39	4.8 × 1.6	0.46	3.66	27		0.91	4.98	9
	1.90	2.59	38		0.61	3.66	27		1.22	5.21	W
3.5 × 1.3	0.38	2.64	37		0.76	3.66	27		1.52	5.79	1
	0.46	2.64	37		0.91	3.73	26		1.90	5.89	…
In Aluminum Alloy Sheet Metal											
2.2 × 0.8	0.38	…	…	3.5 × 1.3	0.61	…	…	4.8 × 1.6	1.22	3.66	27
	0.46	…	…		0.76	2.64	37		1.52	3.66	27
	0.61	1.63	52		0.91	2.64	37		1.90	3.73	26
	0.76	1.63	52		1.22	2.64	37	5.5 × 1.8	0.46	…	…
	0.91	1.63	52		1.52	2.69	36		0.61	…	…
	1.22	1.70	51		1.90	2.79	35		0.76	…	…
	1.52	1.78	50	4.2 × 1.4	0.46	…	…		0.91	…	…
2.9 × 1	0.38	…	…		0.61	…	…		1.22	4.09	20
	0.46	…	…		0.76	2.95	32		1.52	4.22	19
	0.61	…	…		0.91	3.05	31		1.90	4.39	17
	0.76	2.18	44		1.22	3.25	30	6.3 × 1.8	0.46	…	…
	0.91	2.18	44		1.52	3.45	29		0.61	…	…
	1.22	2.18	44		1.90	3.56	28		0.76	…	…
	1.52	2.26	43	4.8 × 1.6	0.46	…	…		0.91	…	…
	1.90	2.26	43		0.61	…	…		1.22	…	…
3.5 × 1.3	0.38	…	…		0.76	…	…		1.52	5.05	8
	0.46	…	…		0.91	3.66	27		1.90	5.11	7

[a] Customary drill size references have been retained where the metric hole diameters are direct conversions of their decimal inch equivalents.

All dimensions are in millimeters except drill sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Approximate Hole Sizes for Steel Type AB Metric Thread Forming Tapping Screws in Plywoods and Asbestos

Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Mat'l Thickness	Penetration in Blind Holes		Hole Size	Drill Size[a]	Min Mat'l Thickness	Penetration in Blind Holes	
				Min	Max				Min	Max
	In Plywood (Resin Impregnated)					In Asbestors Compositions				
2.2 ×0.8	1.85	49	3.18	4.78	12.70	1.93	48	3.18	4.78	12.70
2.9 ×1	2.54	39	4.78	6.35	15.88	2.57	38	4.78	6.35	15.88
3.5 ×1.3	3.18	…	4.78	6.35	15.88	3.05	31	4.78	6.35	15.88
4.2 ×1.4	3.66	27	4.78	6.35	19.05	3.73	26	7.92	9.52	19.05
4.8 ×1.6	4.39	17	6.35	7.92	25.40	4.22	19	7.92	9.52	25.40
5.5 ×1.8	4.93	10	7.92	9.52	25.40	4.98	9	7.92	9.52	25.40
6.3 ×1.8	5.79	1	7.92	9.52	25.40	5.79	1	11.13	12.70	25.40

[a] Customary drill size references have been retained where the metric hole diameters are direct conversions of their decimal inch equivalents.

All dimensions are in millimeters except drill sizes.

Table 9. Approximate Hole Sizes for Steel Type B Metric Thread Forming Tapping Screws in Plywoods, Asbestos, and Plastics

Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Mat'l Thick-ness	Penetration in Blind Holes		Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Mat'l Thick-ness	Penetration in Blind Holes	
				Min	Max					Min	Max
	In Plywood (Resin Impregnated)										
2.2 × 0.8	1.85	49	3.18	4.78	12.70	4.8 × 1.6	4.39	17	6.35	7.92	25.40
2.9 × 1	2.54	39	4.78	6.35	15.88	5.5 × 1.8	4.93	10	7.92	9.52	25.40
3.5 × 1.3	3.18	…	4.78	6.35	15.88	6.3 × 1.8	5.79	1	7.92	9.52	25.40
4.2 × 1.4	3.66	27	4.78	6.35	19.05	…	…	…	…	…	…

[a] Customary drill size references have been retained where the metric hole diameters are direct conversions of their decimal inch equivalents.

Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Mat'l Thickness	Penetration in Blind Holes	
				Min	Max
	In Asbestos Compositions				
2.2 × 0.8	1.93	48	3.18	4.78	12.70
2.9 × 1	2.57	38	4.78	6.35	15.88
3.5 × 1.3	3.05	31	4.78	6.35	15.88
4.2 × 1.4	3.73	26	7.92	9.52	19.05
4.8 × 1.6	4.22	19	7.92	9.52	25.40
5.5 × 1.8	4.98	9	7.92	9.52	25.40
6.3 × 1.8	5.79	1	11.13	12.70	25.40

Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Penetration in Blind Holes	Hole Size	Drill Size[a]	Min Penetration in Blind Holes
	In Phenol Formaldehyde			In Cellulose Acetate & Nitrate, Acrylic and Styrene Resins		
2.2 × 0.8	1.98	47	4.78	1.98	47	4.78
2.9 × 1	2.54	39	6.35	2.39	42	6.35
3.5 × 1.3	3.25	30	6.35	3.05	32	6.35
4.2 × 1.4	3.81	25	7.92	3.66	27	7.92
4.8 × 1.6	4.50	16	7.92	4.32	18	7.92
5.5 × 1.8	5.05	8	9.52	4.85	11	9.52
6.3 × 1.8	5.94	…	9.52	5.61	2	9.52

All dimensions are in millimeters except drill sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Approximate Drilled or Clean-Punched Hole Sizes for Steel Type B Metric Thread Forming Tapping Screws in Sheet Metal and Cast Metals

Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]	Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]	Nominal Screw Size and Thread Pitch	Metal Thick-ness	Hole Size	Drill Size[a]
In Steel, Stainless Steel, Monel, and Brass Sheet Metal											
	0.38	1.63	52	3.5 × 1.3	1.90	3.05	31		0.61	4.22	19
	0.46	1.63	52		2.67	3.25	30		0.76	4.22	19
	0.61	1.70	51		0.61	3.18	…		0.91	4.22	19
2.2 × 0.8	0.76	1.78	50		0.76	3.18	…		1.22	4.32	18
	0.91	1.85	49		0.91	3.18	…	5.5 × 1.8	1.52	4.50	16
	1.22	1.85	49		1.22	3.25	30		1.90	4.62	14
	1.52	1.93	48	4.2 × 1.4	1.52	3.45	29		2.67	4.70	13
	0.38	2.18	44		1.90	3.56	28		3.18	4.98	9
	0.46	2.18	44		2.67	3.81	25		3.43	4.98	9
	0.61	2.26	43		3.18	3.81	25		4.17	5.11	7
2.9 × 1	0.76	2.39	42		3.43	3.86	24		0.76	4.93	10
	0.91	2.39	42		0.61	3.66	27		0.91	4.93	10
	1.22	2.44	41		0.76	3.66	27		1.22	4.93	10
	1.52	2.54	39		0.91	3.73	26		1.52	5.05	8
	1.90	2.59	38		1.22	3.86	24		1.90	5.18	6
	0.38	2.64	37		1.52	3.86	24	6.3 × 1.8	2.67	5.31	4
	0.46	2.64	37	4.8 × 1.6	1.90	3.99	22		3.18	5.79	1
	0.61	2.69	36		2.67	4.09	20		3.43	5.79	1
3.5 × 1.3	0.76	2.69	36		3.18	4.32	18		4.17	5.94	…
	0.91	2.79	35		3.43	4.32	18		4.75	5.94	…
	1.22	2.82	34		4.17	4.39	17		4.93	5.94	…
	1.52	2.95	32								
In Aluminum Alloy Sheet Metal											
	0.61	1.63	52		0.76	2.95	32		1.22	4.09	20
	0.76	1.63	52		0.91	3.05	31		1.52	4.22	19
2.2 × 0.8	0.91	1.63	52		1.22	3.25	30		1.90	4.39	17
	1.22	1.70	51		1.52	3.45	29		2.67	4.57	15
	1.52	1.78	50		1.90	3.56	28	5.5 × 1.8	3.18	4.62	14
	0.76	2.18	44	4.2 × 1.4	2.67	3.73	26		3.43	4.62	14
	0.91	2.18	44		3.18	3.73	26		4.17	4.80	12
2.9 × 1	1.22	2.18	44		3.43	3.78	25		5.08		
	1.52	2.26	43		4.11				to		
	1.90	2.26	43		to				9.52	4.98	9
	2.67	2.39	42		9.52	3.86	24		1.52	5.05	8
	0.76	2.64	37		0.91	3.66	27		1.90	5.11	7
	0.91	2.64	37		1.22	3.66	27		2.67	5.18	6
	1.22	2.64	37		1.52	3.66	27		3.18	5.31	4
	1.52	2.69	36		1.90	3.73	26		3.43	5.31	4
3.5 × 1.3	1.90	2.79	35		2.67	3.73	26	6.3 × 1.8	4.17	5.41	3
	2.67	2.82	34	4.8 × 1.6	3.18	3.91	23		4.75	5.41	3
	3.25				3.43	3.91	23		4.93	5.61	2
	to				4.17	4.04	21		5.08		
	6.25	3.05	31		5.08				to		
					to				9.52	5.79	1
					9.52	4.22	19				

[a] Customary drill size references have been retained where the metric hole diameters are direct conversions of their decimal inch equivalents.

In Aluminum, Magnesium, Zinc, Brass, and Bronze Cast Metals							
Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Penetration in Blind Holes	Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Min Penetration in Blind Holes
2.2 × 0.8	1.98	47	3.18	4.8 × 1.6	4.50	16	6.35
2.9 × 1	2.64	37	4.78	5.5 × 1.8	5.05	8	7.14
3.5 × 1.3	3.25	30	6.35	6.3 × 1.8	5.94	4	7.92
4.2 × 1.4	3.86	24	6.35	…	…	…	…

All dimensions are in millimeters, except drill sizes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Approximate Hole Sizes for Steel Types BF and BT Metric Thread Cutting Tapping Screws for Cast Metals and Plastics

Nominal Screw Size and Thread Pitch	Material Thickness	Hole Size	Drill Size[a]	Nominal Screw Size and Thread Pitch	Material Thickness	Hole Size	Drill Size[a]
In Die Cast Zinc and Aluminum							
2.2 × 0.8	1.52	1.85	49	3.5 × 1.3	3.18	3.05	31
	2.11	1.85	49		3.56	3.05	31
	2.77	1.93	48		4.78	3.05	31
	3.18	1.93	48		6.35	3.18	…
	3.56	1.93	48		7.92	3.18	…
2.9 × 1	2.77	2.49	40	4.2 × 1.4	3.18	3.78	25
	3.18	2.54	39		3.56	3.78	25
	3.56	2.54	39		4.78	3.78	25
	4.78	2.54	39		6.35	3.86	24
	6.35	2.59	38		7.92	3.86	24
4.8 × 1.6	3.18	4.22	19	6.3 × 1.8	6.35	5.79	I
	3.56	4.22	19		7.92	5.79	I
	4.78	4.22	19		9.52	5.79	I
	6.35	4.32	18	8 × 2.1	3.18	7.14	K
	7.92	4.37	…		3.56	7.14	K
	9.52	4.37	…		4.78	7.14	K
5.5 × 1.8	3.18	4.85	11		6.35	7.14	K
	3.56	4.85	11		7.92	7.37	L
	4.78	4.85	11		9.52	7.37	L
	6.35	4.98	9	9.5 × 2.1	3.18	8.74	…
	7.92	4.98	9		3.56	8.74	…
	9.52	4.98	9		4.78	8.74	…
6.3 × 1.8	3.18	5.61	2		6.35	8.74	…
	3.56	5.61	2		7.92	8.84	S
	4.78	5.61	2		9.52	8.84	S

Nominal Screw Size and Thread Pitch	Hole Size	Drill Size[a]	Depth of Penetration	
			Min	Max
In Phenol Formaldehyde				
2.2 × 0.8	1.98	…	2.39	6.35
2.9 × 1.0	2.64	37	3.18	7.92
3.5 × 1.3	3.18	…	4.78	9.52
4.2 × 1.4	3.73	26	6.35	12.70
4.8 × 1.6	4.32	18	7.92	15.88
5.5 × 1.8	4.93	10	9.52	15.88
6.3 × 1.8	5.79	1	9.52	19.05
In Cellulose Acetate and Nitrate, Acrylic and Styrene Resins				
2.2 × 0.8	1.93	48	2.39	6.35
2.9 × 1.0	2.54	39	3.18	7.92
3.5 × 1.3	3.05	31	4.78	9.52
4.2 × 1.4	3.66	27	6.35	12.70
4.8 × 1.6	4.22	19	7.92	15.88
5.5 × 1.8	4.80	12	9.52	15.88
6.3 × 1.8	5.61	2	9.52	19.05

[a] Customary drill size references have been retained where the metric hole sizes are direct conversions of their decimal inch equivalents.

All dimensions are in millimeters except drill sizes.

The finish (plating or coating) on metric tapping screws and the material composition and hardness of the mating component are factors that affect assembly torques in individual applications. Although the recommended installation hole sizes given in Tables 7 through 9 were based on the use of plain unfinished carbon steel metric tapping screws, experience has shown that the specified holes are also suitable for screws having most types of commercial finishes. However, owing to various finishes providing different degrees of lubricity, some adjustment of installation torques may be necessary to suit individual applications. Also, where exceptionally heavy finishes are involved or screws are to be assembled into materials of higher hardness, some deviation from the specified hole sizes may be required to provide optimum assembly. The necessity and extent of such deviations can best be determined by experiment in the particular assembly environment.

Copyright 2004, Industrial Press, Inc., New York, NY

T-SLOTS, BOLTS, AND NUTS

Table 1. American National Standard T-Slots *ANSI/ASME B5.1M-1985 (R1998)*

T-SLOTS



Basic Dimensions



Suggested Approximate Dimensions For Rounding Or Breaking Of Corners

Nominal T-Bolt Size[a]		Width of Throat A_1[b]		Width of Headspace B_1				Depth of Headspace C_1				Depth of Throat D_1				Rounding or Breaking of Corners[c]					
				inch		mm		inch		mm		inch		mm		inch			mm		
inch	mm	inch	mm	min	max	min	max	min	max	min	max	min	max	min	max	R_1 max	W_1 max	U_1 max	R_1 max	W_1 max	U_1 max
	4		5			10	11			3	3.5			4.5	7				0.5	0.8	0.8
	5		6			11	12.5			5	6			5	8				0.5	0.8	0.8
0.250	6	0.282	8	0.500	0.562	14.5	16	0.203	0.234	7	8	0.125	0.375	7	11	0.02	0.02	0.03	0.5	0.8	0.8
0.312	8	0.344	10	0.594	0.656	16	18	0.234	0.266	7	8	0.156	0.438	9	14	0.02	0.03	0.03	0.5	0.8	0.8
0.375	10	0.438	12	0.719	0.781	19	21	0.297	0.328	8	9	0.219	0.562	11	17	0.02	0.03	0.03	0.5	0.8	0.8
0.500	12	0.562	14	0.906	0.969	23	25	0.359	0.391	9	11	0.312	0.688	12	19	0.02	0.03	0.03	0.5	0.8	0.8
0.625	16	0.688	18	1.188	1.250	30	32	0.453	0.484	12	14	0.438	0.875	16	24	0.03	0.03	0.05	0.8	0.8	1.3
0.750	20	0.812	22	1.375	1.469	37	40	0.594	0.625	16	18	0.562	1.062	20	29	0.03	0.03	0.05	0.8	0.8	1.3
1.000	24	1.062	28	1.750	1.844	46	50	0.781	0.828	20	22	0.750	1.250	26	36	0.03	0.06	0.05	0.8	1.5	1.3
1.250	30	1.312	36	2.125	2.219	56	60	1.031	1.094	25	28	1.000	1.562	33	46	0.03	0.06	0.05	0.8	1.5	1.3
1.500	36	1.562	42	2.562	2.656	68	72	1.281	1.344	32	35	1.250	1.938	39	53	0.03	0.06	0.05	0.8	1.5	1.3
	42		48			80	85			36	40			44	59				1.5	2.5	2
	48		54			90	95			40	44			50	66				1.5	2.5	2

[a] Width of tongue (tenon) to be used with the above T-Slots will be found in the complete standard, B5.1M.

[b] Throat dimensions are basic. When slots are intended to be used for holding only, tolerances can be 0.0 + 0.010 inch or H12 Metric (ISO/R286); when intended for location, tolerance can be 0.0 + 0.001 inch or H8 Metric (see page 670).

[c] Corners of T-Slots may be square or may be rounded or broken to the indicated maximum dimensions at the manufacturer's option.

For the dimensions of tongue seats, inserted tongues, and solid tongues refer to the complete standard, B5.1M.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard T-Bolts *ANSI/ASME B5.1M-1985 (R1998)*

T-BOLTS



Nominal T-Bolt Size and Thread A_2[ab]		Bolt Head Dimensions										Rounding of Corners[c]			
		Width Across Flats B_2				Width Across Corners		Height C_2				R_2		W_2	
inch	metric	inch		mm		inch	mm	inch		mm		inch	mm	inch	mm
UNC-2A	ISO[d]	max	min	max	min	max	max	max	min	max	min	max	max	max	max
	M4			9	8.5		12.7			2.5	2.1		0.3		0.5
	M5			10	9.5		14.1			4	3.6		0.3		0.5
0.250–20	M6	0.469	0.438	13	12	0.663	18.4	0.156	0.141	6	5.6	0.02	0.5	0.03	0.8
0.312–18	M8	0.562	0.531	15	14	0.796	21.2	0.188	0.172	6	5.6	0.02	0.5	0.03	0.8
0.375–16	M10	0.688	0.656	18	17	0.972	25.5	0.250	0.234	7	6.6	0.02	0.5	0.03	0.8
0.500–13	M12	0.875	0.844	22	21	1.238	31.1	0.312	0.297	8	7.6	0.02	0.5	0.06	1.5
0.625–11	M16	1.125	1.094	28	27	1.591	39.6	0.406	0.391	10	9.6	0.03	0.8	0.06	1.5
0.750–10	M20	1.312	1.281	34	33	1.856	48.1	0.531	0.500	14	13.2	0.03	0.8	0.06	1.5
1.000–8	M24	1.688	1.656	43	42	2.387	60.8	0.688	0.656	18	17.2	0.03	0.8	0.06	1.5
1.250–7	M30	2.062	2.031	53	52	2.917	75	0.938	0.906	23	22.2	0.03	0.8	0.06	1.5
1.500–6	M36	2.500	2.469	64	63	3.536	90.5	1.188	1.156	28	27.2	0.03	0.8	0.06	1.5
	M42			75	74		106.1			32	30.5		1		2
	M48			85	84		120.2			36	34.5		1		2

[a] For inch tolerances for thread diameters of bolts or studs and for threads see page 1736.
[b] T-slots to be used with these bolts will be found in Table 1.
[c] Corners of T-bolts may be square or may be rounded or broken to the indicated maximum dimensions at the manufacturer's option.
[d] Metric thread grade and tolerance position is 5g 6g (see page 1790).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard T-Nuts *ANSI/ASME B5.1M-1985 (R1998)*

T-NUTS



Nominal T-Bolt Size[a]		Width of Tongue A_3				Tap for Stud[b] E_3		Width of Nut B_3				Height of Nut C_3				Total Thickness Including Tongue[c] K_3		Length of Nut[c] L_3		Rounding of Corners			
		inch		mm		inch	mm	inch		mm		inch		mm						R_3		W_3	
inch	mm	max	min	max	min	UNC-3B	ISO[d]	max	min	max	min	max	min	max	min	inch	mm	inch	mm	inch max	mm max	inch max	mm max
	4		…		…		…		…	…	…			…	…		…		…		…		…
	5		…		…		…		…	…	…			…	…		…		…		…		…
0.250	6	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…
0.312	8	0.330	0.320	8.7	8.5	0.250–20	M6	0.562	0.531	15	14	0.188	0.172	6	5.6	0.281	9	0.562	18	0.02	0.5	0.03	0.8
0.375	10	0.418	0.408	11	10.75	0.312–18	M8	0.688	0.656	18	17	0.250	0.234	7	6.6	0.375	10.5	0.688	20	0.02	0.5	0.03	0.8
0.500	12	0.543	0.533	13.5	13.25	0.375–1	6M10	0.875	0.844	22	21	0.312	0.297	8	7.6	0.531	12	0.875	23	0.02	0.5	0.06	1.5
0.625	16	0.668	0.658	17.25	17	0.500–13	M12	1.125	1.094	28	27	0.406	0.391	10	9.6	0.625	15	1.125	27	0.03	0.8	0.06	1.5
0.750	20	0.783	0.773	20.5	20.25	0.625–11	M16	1.312	1.281	34	33	0.531	0.500	14	13.2	0.781	21	1.312	35	0.03	0.8	0.06	1.5
1.000	24	1.033	1.018	26.5	26	0.750–10	M20	1.688	1.656	43	42	0.688	0.656	18	17.2	1.000	27	1.688	46	0.03	0.8	0.06	1.5
1.250	30	1.273	1.258	33	32.5	1.000–8	M24	2.062	2.031	53	52	0.938	0.906	23	22.2	1.312	34	2.062	53	0.03	0.8	0.06	1.5
1.500	36	1.523	1.508	39.25	38.75	1.250–7	M30	2.500	2.469	64	63	1.188	1.156	28	27.2	1.625	42	2.500	65	0.03	0.8	0.06	1.5
	42			46.75	46.25		M36			75	74			32	30.5		48		75		1		2
	48			52.5	51.75		M42			85	84			36	34.5		54		85		1		2

[a] T-slot dimensions to fit the above nuts will be found in Table 1.

[b] For tolerances of inch threads see page 1736.

[c] No tolerances are given for "Total Thickness" or "Nut Length" as they need not be held to close limits.

[d] Metric tapped thread grade and tolerance position is 5H (see page 1790).

Copyright 2004, Industrial Press, Inc., New York, NY

PINS AND STUDS

Dowel-Pins.— Dowel-pins are used either to retain parts in a fixed position or to preserve alignment. Under normal conditions a properly fitted dowel-pin is subjected solely to shearing strain, and this strain occurs only at the junction of the surfaces of the two parts which are being held by the dowel-pin. It is seldom necessary to use more than two dowel-pins for holding two pieces together and frequently one is sufficient. For parts that have to be taken apart frequently, and where driving out of the dowel-pins would tend to wear the holes, and also for very accurately constructed tools and gages that have to be taken apart, or that require to be kept in absolute alignment, the taper dowel-pin is preferable. The taper dowel-pin is most commonly used for average machine work, but the straight type is given the preference on tool and gage work, except where extreme accuracy is required, or where the tool or gage is to be subjected to rough handling.

The size of the dowel-pin is governed by its application. For locating nests, gage plates, etc., pins from 1/8 to 3/16 inch in diameter are satisfactory. For locating dies, the diameter of the dowel-pin should never be less than 1/4 inch; the general rule is to use dowel-pins of the same size as the screws used in fastening the work. The length of the dowel-pin should be about one and one-half to two times its diameter in each plate or part to be doweled.

When hardened cylindrical dowel-pins are inserted in soft parts, ream the hole about 0.001 inch smaller than the dowel-pin. If the doweled parts are hardened, grind (or lap) the hole 0.0002 to 0.0003 inch under size. The hole should be ground or lapped straight, that is, without taper or "bell-mouth."

American National Standard Cotter Pins *ANSI B18.8.1-1972 (R1994)*



Nom. Size	Dia. *A*[a] & Width *B* Max.	Wire Width *B* Min.	Head Dia. *C* Min.	Prong Length *D* Min.	Hole Size	Nom. Size	Dia. *A*[a] & Width *B* Max.	Wire Width *B* Min.	Head Dia. *C* Min.	Prong Length *D* Min.	Hole Size
1/32	0.032	0.022	0.06	0.01	0.047	3/16	0.176	0.137	0.38	0.09	0.203
3/64	0.048	0.035	0.09	0.02	0.062	7/32	0.207	0.161	0.44	0.10	0.234
1/16	0.060	0.044	0.12	0.03	0.078	1/4	0.225	0.176	0.50	0.11	0.266
5/64	0.076	0.057	0.16	0.04	0.094	5/16	0.280	0.220	0.62	0.14	0.312
3/32	0.090	0.069	0.19	0.04	0.109	3/8	0.335	0.263	0.75	0.16	0.375
7/64	0.104	0.080	0.22	0.05	0.125	7/16	0.406	0.320	0.88	0.20	0.438
1/8	0.120	0.093	0.25	0.06	0.141	1/2	0.473	0.373	1.00	0.23	0.500
9/64	0.134	0.104	0.28	0.06	0.156	5/8	0.598	0.472	1.25	0.30	0.625
5/32	0.150	0.116	0.31	0.07	0.172	3/4	0.723	0.572	1.50	0.36	0.750

[a] Tolerances are: –0.004 inch for the 1/32- to 3/16-inch sizes, incl.; –0.005 inch for the 7/32- to 5/16-inch sizes, incl.; –0.006 inch for the 3/8- to 1/2-inch sizes, incl.; and –0.008 inch for the 5/8- and 3/4-inch sizes. Note: Tolerances for length are: up to 1 inch ± 0.030 inch, over 1 inch ±0.060 inch.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Clevis Pins *ANSI B18.8.1-1972 (R1994)*



Nom.Size (Basic Pin Dia.)	Shank Dia.*A* Max	Head Dia.*B* Max.[a]	Head Hgt.*C* Max.[b]	Head Chamfer *D* Nom.[c]	Hole Dia.*E* Max.[d]	Point Dia.*F* Max.[e]	Pin Lgth.*G* Basic[f]	Head to HoleCenter *H* Max.[g]	Point Length *L* Max.	Point Length *L* Min.	Cotter Pin Size for Hole
3/16	0.186	0.32	0.07	0.02	0.088	0.15	0.58	0.504	0.055	0.035	1/16
1/4	0.248	0.38	0.10	0.03	0.088	0.21	0.77	0.692	0.055	0.035	1/16
5/16	0.311	0.44	0.10	0.03	0.119	0.26	0.94	0.832	0.071	0.049	3/32
3/8	0.373	0.51	0.13	0.03	0.119	0.33	1.06	0.958	0.071	0.049	3/32
7/16	0.436	0.57	0.16	0.04	0.119	0.39	1.19	1.082	0.071	0.049	3/32
1/2	0.496	0.63	0.16	0.04	0.151	0.44	1.36	1.223	0.089	0.063	1/8
5/8	0.621	0.82	0.21	0.06	0.151	0.56	1.61	1.473	0.089	0.063	1/8
3/4	0.746	0.94	0.26	0.07	0.182	0.68	1.91	1.739	0.110	0.076	5/32
7/8	0.871	1.04	0.32	0.09	0.182	0.80	2.16	1.989	0.110	0.076	5/32
1	0.996	1.19	0.35	0.10	0.182	0.93	2.41	2.239	0.110	0.076	5/32

[a] Tolerance is –0.05 inch.
[b] Tolerance is –0.02 inch.
[c] Tolerance is ±0.01 inch.
[d] Tolerance is –0.015 inch.
[e] Tolerance is –0.01 inch.
[f] Lengths tabulated are intended for use with standard clevises, without spacers. When other lengths are required, it is recommended that they be limited wherever possible to nominal lengths in 0.06-inch increments.
[g] Tolerance is –0.020 inch.

All dimensions are in inches.

British Standard for Metric Series Dowel Pins.— Steel parallel dowel pins specified in British Standard 1804:Part 2:1968 are divided into three grades which provide different degrees of pin accuracy.

Grade 1 is a precision ground pin made from En 32A or En 32B low carbon steel (BS 970) or from high carbon steel to BS 1407 or BS 1423. Pins below 4 mm diameter are unhardened. Those of 4 mm diameter and above are hardened to a minimum of 750 HV 30 in accordance with BS 427, but if they are made from steels to BS 1407 or BS 1423 then the hardness shall be within the range 600 to 700 HV 30, in accordance with BS 427. The values of other hardness scales may be used in accordance with BS 860.

Grade 2 is a ground pin made from any of the steels used for Grade 1. The pins are normally supplied unhardened, unless a different condition is agreed on between the purchaser and supplier.

Grade 3 pins are made from En 1A free cutting steel (BS 970) and are supplied with a machined, bright rolled or drawn finish. They are normally supplied unhardened unless a different condition is agreed on between the purchaser and supplier.

Pins of any grade may be made from different steels in accordance with BS 970, by mutual agreement between the purchaser and manufacturer. If steels other than those in the

Copyright 2004, Industrial Press, Inc., New York, NY

standard range are used, the hardness of the pins shall also be decided on by mutual agreement between purchaser and supplier. As shown in the illustration at the head of the accompanying table, one end of each pin is chamfered to provide a lead. The other end may be similarly chamfered, or domed.

British Standard Parallel Steel Dowel Pins — Metric Series *BS 1804: Part 2: 1968*



Nom. Length *L*, mm	Nominal Diameter *D*, mm													
	1	1.5	2	2.5	3	4	5	6	8	10	12	16	20	25
	Chamfer *a* max, mm													
	0.3	0.3	0.3	0.4	0.45	0.6	0.75	0.9	1.2	1.5	1.8	2.5	3	4
	Standard Sizes													
4	d	d												
6	d	d	d	d										
8	d	d	d	d	d									
10		d	d	d	d	d								
12		d	d	d	d	d	d							
16			d	d	d	d	d	d	d					
20				d	d	d	d	d	d	d				
25					d	d	d	d	d	d	d			
30						d	d	d	d	d	d	d		
35							d	d	d	d	d	d		
40							d	d	d	d	d	d	d	
45								d	d	d	d	d	d	
50									d	d	d	d	d	d
60									d	d	d	d	d	d
70										d	d	d	d	d
80										d	d	d	d	d
90											d	d	d	d
100												d	d	d
110												d	d	d
120													d	d

Limits of Tolerance on Diameter							
Grade[a]		1		2		3	
Tolerance Zone		m5		h7		h11	
Nom. Dia., mm							
Over	To & Incl.	Limits of Tolerance, 0.001 mm					
	3	+7	+2	0	−12[b]	0	−60
3	6	+9	+4	0	−12	0	−75
6	10	+12	+6	0	−15	0	−90
10	14	+15	+7	0	−18	0	−110
14	18	+15	+7	0	−18	0	−110
18	24	+17	+8	0	−21	0	−130
24	30	+17	+8	0	−21	0	−130

[a] The limits of tolerance for grades 1 and 2 dowel pins have been chosen to provide satisfactory assembly when used in standard reamed holes (H7 and H8 tolerance zones). If the assembly is not satisfactory, refer to B.S. 1916: Part 1, Limits and Fits for Engineering, and select a different class of fit.

[b] This tolerance is larger than that given in BS 1916, and has been included because the use of a closer tolerance would involve precision grinding by the manufacturer, which is uneconomic for a grade 2 dowel pin.

The tolerance limits on the overall length of all grades of dowel pin up to and including 50 mm long are +0.5, –0.0 mm, and for pins over 50 mm long are +0.8, –0.0 mm. The Standard specifies that the roughness of the cylindrical surface of grades 1 and 2 dowel pins, when assessed in accordance with BS 1134, shall not be greater than 0.4 μm CLA (16 CLA).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard Hardened Ground Machine Dowel Pins *ANSI/ASME B18.8.2-1995*



Nominal Size[a] or Nominal Pin Diameter		Pin Diameter, *A*						Point Diameter, *B*		Crown Height, *C*	Crown Radius, *R*	Range of Preferred Lengths,[b] *L*	Single Shear Load, for Carbon or Alloy Steel, Calculated lb	Suggested Hole Diameter[c]	
		Standard Series Pins			Oversize Series Pins										
		Basic	Max	Min	Basic	Max	Min	Max	Min	Max	Min			Max	Min
1/16	0.0625	0.0627	0.0628	0.0626	0.0635	0.0636	0.0634	0.058	0.048	0.020	0.008	3/16–3/4	400	0.0625	0.0620
5/64[d]	0.0781	0.0783	0.0784	0.0782	0.0791	0.0792	0.0790	0.074	0.064	0.026	0.010	…	620	0.0781	0.0776
3/32	0.0938	0.0940	0.0941	0.0939	0.0948	0.0949	0.0947	0.089	0.079	0.031	0.012	5/16–1	900	0.0937	0.0932
1/8	0.1250	0.1252	0.1253	0.1251	0.1260	0.1261	0.1259	0.120	0.110	0.041	0.016	3/8–2	1,600	0.1250	0.1245
5/32[d]	0.1562	0.1564	0.1565	0.1563	0.1572	0.1573	0.1571	0.150	0.140	0.052	0.020	…	2,500	0.1562	0.1557
3/16	0.1875	0.1877	0.1878	0.1876	0.1885	0.1886	0.1884	0.180	0.170	0.062	0.023	1/2–2	3,600	0.1875	0.1870
1/4	0.2500	0.2502	0.2503	0.2501	0.2510	0.2511	0.2509	0.240	0.230	0.083	0.031	1/2–2 1/2	6,400	0.2500	0.2495
5/16	0.3125	0.3127	0.3128	0.3126	0.3135	0.3136	0.3134	0.302	0.290	0.104	0.039	1/2–2 1/2	10,000	0.3125	0.3120
3/8	0.3750	0.3752	0.3753	0.3751	0.3760	0.3761	0.3759	0.365	0.350	0.125	0.047	1/2–3	14,350	0.3750	0.3745
7/16	0.4375	0.4377	0.4378	0.4376	0.4385	0.4386	0.4384	0.424	0.409	0.146	0.055	7/8–3	19,550	0.4375	0.4370
1/2	0.5000	0.5002	0.5003	0.5001	0.5010	0.5011	0.5009	0.486	0.471	0.167	0.063	3/4–1–4	25,500	0.5000	0.4995
5/8	0.6250	0.6252	0.6253	0.6251	0.6260	0.6261	0.6259	0.611	0.595	0.208	0.078	1 1/4–5	39,900	0.6250	0.6245
3/4	0.7500	0.7502	0.7503	0.7501	0.7510	0.7511	0.7509	0.735	0.715	0.250	0.094	1 1/2–6	57,000	0.7500	0.7495
7/8	0.8750	0.8752	0.8753	0.8751	0.8760	0.8761	0.8759	0.860	0.840	0.293	0.109	2,2 1/2–6	78,000	0.8750	0.8745
1	1.0000	1.0002	1.0003	1.0001	1.0010	1.0011	1.0009	0.980	0.960	0.333	0.125	2,2 1/2–5,6	102,000	1.0000	0.9995

[a] Where specifying nominal size as basic diameter, zeros preceding decimal and in the fourth decimal place are omitted.

[b] Lengths increase in 1/16-inch steps up to 3/8 inch, in 1/8-inch steps from 3/8 inch to 1 inch, in 1/4-inch steps from 1 inch to 2 1/2 inches, and in 1/2-inch steps above 2 1/2 inches. Tolerance on length is ±0.010 inch.

[c] These hole sizes have been commonly used for press fitting Standard Series machine dowel pins into materials such as mild steels and cast iron. In soft materials such as aluminum or zinc die castings, hole size limits are usually decreased by 0.0005 inch to increase the press fit.

[d] Nonpreferred sizes, not recommended for use in new designs.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

If a dowel pin is driven into a blind hole where no provision is made for releasing air, the worker assembling the pin may be endangered, and damage may be caused to the associated component, or stresses may be set up. The appendix of the Standard describes one method of overcoming this problem by providing a small flat surface along the length of a pin to permit the release of air.

For purposes of marking, the Standard states that each package or lot of dowel pins shall bear the manufacturer's name or trademark, the BS number, and the grade of pin.

American National Standard Hardened Ground Machine Dowel Pins.— Hardened ground machine dowel pins are furnished in two diameter series: Standard Series having basic diameters 0.0002 inch over the nominal diameter, intended for initial installations; and Oversize Series having basic diameters 0.001 inch over the nominal diameter, intended for replacement use.

Preferred Lengths and Sizes: The preferred lengths and sizes in which these pins are normally available are given in Table 1. Other sizes and lengths are produced as required by the purchaser.

Effective Length: The effective length, L_e, must not be less than 75 per cent of the overall length of the pin.

Shear Strength: Single shear strength values are listed in Table 1. Prior versions of ANSI/ASME B18.8.2-1995 had listed double shear load minimum values and had specified a minimum single shear strength of 130,000 psi. See ANSI/ASME B18.8.2-1995, Appendix B for a description of the double shear test.

Designation: These pins are designated by the following data in the sequence shown: Product name (noun first), including pin series, nominal pin diameter (fraction or decimal equivalent), length (fraction or decimal equivalent), material, and protective finish, if required.

Examples: Pins, Hardened Ground Machine Dowel — Standard Series, $\frac{3}{8} \times 1\frac{1}{2}$, Steel, Phosphate Coated.
Pins, Hardened Ground Machine Dowel — Oversize Series, 0.625 × 2.500, Steel

Installation Precaution: Pins should not be installed by striking or hammering and when installing with a press, a shield should be used and safety glasses worn.

American National Standard Hardened Ground Production Dowel Pins.— Hardened ground production dowel pins have basic diameters that are 0.0002 inch over the nominal pin diameter.

Preferred Lengths and Sizes: The preferred lengths and sizes in which these pins are available are given in Table 2. Other sizes and lengths are produced as required by the purchaser.

Shear Strength: Single shear strength values are listed in Table 2. Prior versions of ANSI/ASME B18.8.2-1995 had listed double shear load minimum values and had specified a minimum single shear strength of 102,000 psi. See ANSI/ASME B18.8.2-1995, Appendix B for a description of the double shear test.

Ductility: These standard pins are sufficiently ductile to withstand being pressed into holes 0.0005 inch smaller than the nominal pin diameter in hardened steel without cracking or shattering.

Designation: These pins are designated by the following data in the sequence shown: Product name (noun first), nominal pin diameter (fraction or decimal equivalent), length (fraction or decimal equivalent), material, and protective finish, if required.

Examples: Pins, Hardened Ground Production Dowel, $\frac{1}{8} \times \frac{3}{4}$, Steel, Phosphate Coated
Pins, Hardened Ground Production Dowel, 0.375 × 1.500, Steel

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Hardened Ground Production Dowel Pins
ANSI/ASME B18.8.2-1995



Nominal Size[a] or Nominal Pin Diameter		Pin Diameter, A			Corner Radius, R		Range of Preferred Lengths,[b] L	Single Shear Load, Calculated,lb	Suggested Hole Diameter[c]	
		Basic	Max	Min	Max	Min			Max	Min
1/16	0.0625	0.0627	0.0628	0.0626	0.020	0.010	3/16–1	395	0.0625	0.0620
3/32	0.0938	0.0939	0.0940	0.0938	0.020	0.010	3/16–2	700	0.0937	0.0932
7/64	0.1094	0.1095	0.1096	0.1094	0.020	0.010	3/16–2	950	0.1094	0.1089
1/8	0.1250	0.1252	0.1253	0.1251	0.020	0.010	3/16–2	1,300	0.1250	0.1245
5/32	0.1562	0.1564	0.1565	0.1563	0.020	0.010	3/16–2	2,050	0.1562	0.1557
3/16	0.1875	0.1877	0.1878	0.1876	0.020	0.010	3/16–2	2,950	0.1875	0.1870
7/32	0.2188	0.2189	0.2190	0.2188	0.020	0.010	1/4–2	3,800	0.2188	0.2183
1/4	0.2500	0.2502	0.2503	0.2501	0.020	0.010	1/4–1 1/2, 1 3/4, 2–2 1/2	5,000	0.2500	0.2495
5/16	0.3125	0.3127	0.3128	0.3126	0.020	0.010	5/16–1 1/2, 1 3/4, 2–2 1/2	8,000	0.3125	0.3120
3/8	0.3750	0.3752	0.3753	0.3751	0.020	0.010	3/8–1 1/2, 1 3/4, 2–3	11,500	0.3750	0.3745

[a] Where specifying nominal pin size in decimals, zeros preceding decimal and in the fourth decimal place are omitted.

[b] Lengths increase in 1/16-inch steps up to 1 inch, in 1/8-inch steps from 1 inch to 2 inches and then are 2 1/4, 2 1/2, and 3 inches.

[c] These hole sizes have been commonly used for press fitting production dowel pins into materials such as mild steels and cast iron. In soft materials such as aluminum or zinc die castings, hole size limits are usually decreased by 0.0005 inch to increase the press fit.

All dimensions are in inches.

American National Standard Unhardened Ground Dowel Pins.— Unhardened ground dowel pins are normally produced by grinding the outside diameter of commercial wire or rod material to size. Consequently, the maximum diameters of the pins, as specified in Table 3, are below the minimum commercial stock sizes by graduated amounts from 0.0005 inch on the 1/16-inch nominal pin size to 0.0028 inch on the 1-inch nominal pin size.

Preferred Lengths and Sizes: The preferred lengths and sizes in which unhardened ground pins are normally available are given in Table 3. Other sizes and lengths are produced as required by the purchaser.

Shear Strength: These pins must have a single shear strength of 64,000 psi minimum for pins made from steel and 40,000 psi minimum for pins made from brass and must be capable of withstanding the minimum double shear loads given in Table 3 when tested in accordance with the procedure outlined in ANSI/ASME B18.8.2-1995, Appendix B.

Designation: These pins are designated by the following data in the order shown: Product name (noun first), nominal pin diameter (fraction or decimal equivalent), length (fraction or decimal equivalent), material, and protective finish, if required.

Examples: Pins, Unhardened Ground Dowel, 1/8 × 3/4, Steel

Pins, Unhardened Ground Dowel, 0.250 × 2.500, Steel, Zinc Plated

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Unhardened Ground Dowel Pins
ANSI/ASME B18.8.2-1995



Nominal Size[a] or Basic Pin Diameter		Pin Diameter, *A*		Chamfer Length, *C*		Range of Preferred Lengths,[b] *L*	Suggested Hole Diameter[c]		Double Shear Load Min, lb.	
		Max	Min	Max	Min		Max	Min	Carbon-Steel	Brass
1/16	0.0625	0.0600	0.0595	0.025	0.005	1/4–1	0.0595	0.0580	350	220
3/32	0.0938	0.0912	0.0907	0.025	0.005	1/4–1 1/2	0.0907	0.0892	820	510
d7/64	0.1094	0.1068	0.1063	0.025	0.005	…	0.1062	0.1047	1,130	710
1/8	0.1250	0.1223	0.1218	0.025	0.005	1/4–2	0.1217	0.1202	1,490	930
5/32	0.1562	0.1535	0.1530	0.025	0.005	1/4–2	0.1528	0.1513	2,350	1,470
3/16	0.1875	0.1847	0.1842	0.025	0.005	1/4–2	0.1840	0.1825	3,410	2,130
7/32	0.2188	0.2159	0.2154	0.025	0.005	1/4–2	0.2151	0.2136	4,660	2,910
1/4	0.2500	0.2470	0.2465	0.025	0.005	1/4–1 1/2, 1 3/4, 2–2 1/2	0.2462	0.2447	6,120	3,810
5/16	0.3125	0.3094	0.3089	0.040	0.020	5/16–1 1/2, 1 3/4, 2–2 1/2	0.3085	0.3070	9,590	5,990
3/8	0.3750	0.3717	0.3712	0.040	0.020	3/8–1 1/2, 1 3/4, 2–2 1/2	0.3708	0.3693	13,850	8,650
7/16	0.4375	0.4341	0.4336	0.040	0.020	7/16–5/8, 3/4, 7/8–1 1/2, 1 3/4, 2–2 1/2	0.4331	0.4316	18,900	11,810
1/2	0.5000	0.4964	0.4959	0.040	0.020	1/2, 5/8, 3/4, 7/8, 1–1 1/2, 1 3/4, 2–3	0.4954	0.4939	24,720	15,450
5/8	0.6250	0.6211	0.6206	0.055	0.035	5/8, 3/4, 7/8, 1–1 1/2, 1 3/4, 2, 2 1/2–4	0.6200	0.6185	38,710	24,190
3/4	0.7500	0.7458	0.7453	0.055	0.035	3/4, 7/8, 1, 1 1/4, 1 1/2, 1 3/4, 2, 2 1/2–4	0.7446	0.7431	55,840	34,900
7/8	0.8750	0.8705	0.8700	0.070	0.050	7/8, 1, 1 1/4, 1 1/2, 1 3/4, 2, 2 1/2–4	0.8692	0.8677	76,090	47,550
1	1.0000	0.9952	0.9947	0.070	0.050	1, 1 1/4, 1 1/2, 1 3/4, 2, 2 1/2–4	0.9938	0.9923	99,460	62,160

[a] Where specifying pin size in decimals, zeros preceding decimal and in the fourth decimal place are omitted.

[b] Lengths increase in 1/16-inch increments from 1/4 to 1 inch, in 1/8-inch increments from 1 inch to 2 inches, and in 1/4-inch increments from 2 to 2 1/2 inches, and in 1/2-inch increments from 2 1/2 to 4 inches.

[c] These hole sizes have been found to be satisfactory for press fitting pins into mild steel and cast and malleable irons. In soft materials such as aluminum alloys or zinc die castings, hole size limits are usually decreased by 0.0005 inch to increase the press fit.

[d] Nonpreferred size, not recommended for use in new designs.

All dimensions are in inches.

American National Standard Straight Pins.— The diameter of both chamfered and square end straight pins is that of the commercial wire or rod from which the pins are made. The tolerances shown in Table 4 are applicable to carbon steel and some deviations in the diameter limits may be necessary for pins made from other materials.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Chamfered and Square End Straight Pins
ANSI/ASME B18.8.2-1995



CHAMFERED STRAIGHT PIN — SQUARE END STRAIGHT PIN

Nominal Size[a] or Basic Pin Diameter		Pin Diameter, *A*		Chamfer Length, *C*		Nominal Size[b] or Basic Pin Diameter		Pin Diameter, *A*		Chamfer Length, *C*	
		Max	Min	Max	Min			Max	Min	Max	Min
1/16	0.062	0.0625	0.0605	0.025	0.005	5/16	0.312	0.3125	0.3105	0.040	0.020
3/32	0.094	0.0937	0.0917	0.025	0.00	3/8	0.375	0.3750	0.3730	0.040	0.020
7/64	0.109	0.1094	0.1074	0.025	0.005	7/16	0.438	0.4375	0.4355	0.040	0.020
1/8	0.125	0.1250	0.1230	0.025	0.005	1/2	0.500	0.5000	0.4980	0.040	0.020
5/32	0.156	0.1562	0.1542	0.025	0.005	5/8	0.625	0.6250	0.6230	0.055	0.035
3/16	0.188	0.1875	0.1855	0.025	0.005	3/4	0.750	0.7500	0.7480	0.055	0.035
7/32	0.219	0.2187	0.2167	0.025	0.005	7/8	0.875	0.8750	0.8730	0.055	0.035
1/4	0.250	0.2500	0.2480	0.025	0.005	1	1.000	1.0000	0.9980	0.055	0.035

[a] Where specifying nominal size in decimals, zeros preceding decimal point are omitted.
[b] Where specifying nominal size in decimals, zeros preceding decimal point are omitted.

All dimensions are in inches.

Length Increments: Lengths are as specified by the purchaser; however, it is recommended that nominal pin lengths be limited to increments of not less than 0.062 inch.

Material: Straight pins are normally made from cold drawn steel wire or rod having a maximum carbon content of 0.28 per cent. Where required, pins may also be made from corrosion resistant steel, brass, or other metals.

Designation: Straight pins are designated by the following data, in the sequence shown: Product name (noun first), nominal size (fraction or decimal equivalent), material, and protective finish, if required.

Examples: Pin, Chamfered Straight, $\frac{1}{8} \times 1.500$, Steel
Pin, Square End Straight, 0.250×2.250, Steel, Zinc Plated

American National Standard Taper Pins.— Taper pins have a uniform taper over the pin length with both ends crowned. Most sizes are supplied in commercial and precision classes, the latter having generally tighter tolerances and being more closely controlled in manufacture.

Diameters: The major diameter of both commercial and precision classes of pins is the diameter of the large end and is the basis for pin size. The diameter at the small end is computed by multiplying the nominal length of the pin by the factor 0.02083 and subtracting the result from the basic pin diameter. See also Table 5.

Taper: The taper on commercial class pins is 0.250 ± 0.006 inch per foot and on the precision class pins is 0.250 ± 0.004 inch per foot of length.

Materials: Unless otherwise specified, taper pins are made from SAE 1211 steel or cold drawn SAE 1212 or 1213 steel or equivalents, and no mechanical property requirements apply.

Hole Sizes: Under most circumstances, holes for taper pins require taper reaming. Sizes and lengths of taper pins for which standard reamers are available are given in Table 6. Drilling specifications for taper pins are given below.

Copyright 2004, Industrial Press, Inc., New York, NY

Designation: Taper pins are designated by the following data in the sequence shown: Product name (noun first), class, size number (or decimal equivalent), length (fraction or three-place decimal equivalent), material, and protective finish, if required.

Examples: Pin, Taper (Commercial Class) No. 0 × ¾, Steel

Pin, Taper (Precision Class) 0.219 × 1.750, Steel, Zinc Plated

Table 5. Nominal Diameter at Small Ends of Standard Taper Pins

Pin Length in inches	Pin Number and Small End Diameter for Given Length										
	0	1	2	3	4	5	6	7	8	9	10
¾	0.140	0.156	0.177	0.203	0.235	0.273	0.325	0.393	0.476	0.575	0.690
1	0.135	0.151	0.172	0.198	0.230	0.268	0.320	0.388	0.471	0.570	0.685
1¼	0.130	0.146	0.167	0.192	0.224	0.263	0.315	0.382	0.466	0.565	0.680
1½	0.125	0.141	0.162	0.187	0.219	0.258	0.310	0.377	0.460	0.560	0.675
1¾	0.120	0.136	0.157	0.182	0.214	0.252	0.305	0.372	0.455	0.554	0.669
2	0.114	0.130	0.151	0.177	0.209	0.247	0.299	0.367	0.450	0.549	0.664
2¼	0.109	0.125	0.146	0.172	0.204	0.242	0.294	0.362	0.445	0.544	0.659
2½	0.104	0.120	0.141	0.166	0.198	0.237	0.289	0.356	0.440	0.539	0.654
2¾	0.099	0.115	0.136	0.161	0.193	0.232	0.284	0.351	0.434	0.534	0.649
3	0.094	0.110	0.131	0.156	0.188	0.227	0.279	0.346	0.429	0.528	0.643
3¼	…	…	…	0.151	0.182	0.221	0.273	0.340	0.424	0.523	0.638
3½	…	…	…	0.146	0.177	0.216	0.268	0.335	0.419	0.518	0.633
3¾	…	…	…	0.141	0.172	0.211	0.263	0.330	0.414	0.513	0.628
4	…	…	…	0.136	0.167	0.206	0.258	0.326	0.409	0.508	0.623
4¼	…	…	…	0.131	0.162	0.201	0.253	0.321	0.403	0.502	0.617
4½	…	…	…	0.125	0.156	0.195	0.247	0.315	0.398	0.497	0.612
5	…	…	…	…	0.146	0.185	0.237	0.305	0.389	0.487	0.602
5½	…	…	…	…	…	…	…	0.294	0.377	0.476	0.591
6	…	…	…	…	…	…	…	0.284	0.367	0.466	0.581

Drilling Specifications for Taper Pins.— When helically fluted taper pin reamers are used, the diameter of the through hole drilled prior to reaming is equal to the diameter at the small end of the taper pin. (See Table 5.) However, when straight fluted taper reamers are to be used, it may be necessary, for long pins, to step drill the hole before reaming, the number and sizes of the drills to be used depending on the depth of the hole (pin length).

To determine the number and sizes of step drills required: Find the length of pin to be used at the top of the chart on page 1676 and follow this length down to the intersection with that heavy line which represents the size of taper pin (see taper pin numbers at the right-hand end of each heavy line). If the length of pin falls between the first and second dots, counting from the left, only one drill is required. Its size is indicated by following the nearest horizontal line from the point of intersection (of the pin length) on the heavy line over to the drill diameter values at the left. If the intersection of pin length comes between the second and third dots, then two drills are required. The size of the smaller drill then corresponds to the intersection of the pin length and the heavy line and the larger is the corresponding drill diameter for the intersection of one-half this length with the heavy line. Should the pin length fall between the third and fourth dots, three drills are required. The smallest drill will have a diameter corresponding to the intersection of the total pin length with the heavy line, the next in size will have a diameter corresponding to the intersection of two-thirds of this length with the heavy line and the largest will have a diameter corresponding to the intersection of one-third of this length with the heavy line. Where the intersection falls between two drill sizes, use the smaller.

Copyright 2004, Industrial Press, Inc., New York, NY

Chart to Facilitate Selection of Number and Sizes of Drills for Step-Drilling Prior to Taper Reaming



Copyright 2004, Industrial Press, Inc., New York, NY



Examples: For a No. 10 taper pin 6-inches long, three drills would be used, of the sizes and for the depths shown in the accompanying diagram.

For a No. 10 taper pin 3-inches long, two drills would be used because the 3-inch length falls between the second and third dots. The first or through drill will be 0.6406 inch and the second drill, 0.6719 inch for a depth of 1½ inches.

Table 6. American National Standard Taper Pins *ANSI/ASME B18.8.2-1995*



Pin Size Number and Basic Pin Dia.[a]		Major Diameter (Large End), *A*				End Crown Radius, *R*		Range of Lengths,[b] *L*	
		Commercial Class		Precision Class					
		Max	Min	Max	Min	Max	Min	Stand. Reamer Avail.[c]	Other
7/0	0.0625	0.0638	0.0618	0.0635	0.0625	0.072	0.052	…	¼–1
6/0	0.0780	0.0793	0.0773	0.0790	0.0780	0.088	0.068	…	¼–½
5/0	0.0940	0.0953	0.0933	0.0950	0.0940	0.104	0.084	¼–1	1¼, 1½
4/0	0.1090	0.1103	0.1083	0.1100	0.1090	0.119	0.099	¼–1	1½–2
3/0	0.1250	0.1263	0.1243	0.1260	0.1250	0.135	0.115	¼–1	1¼–2
2/0	0.1410	0.1423	0.1403	0.1420	0.1410	0.151	0.131	½–1¼	1½–2½
0	0.1560	0.1573	0.1553	0.1570	0.1560	0.166	0.146	½–1¼	1½–3
1	0.1720	0.1733	0.1713	0.1730	0.1720	0.182	0.162	¾–1¼	1½–3
2	0.1930	0.1943	0.1923	0.1940	0.1930	0.203	0.183	¾–1½	1¾–3
3	0.2190	0.2203	0.2183	0.2200	0.2190	0.229	0.209	¾–1¾	2–4
4	0.2500	0.2513	0.2493	0.2510	0.2500	0.260	0.240	¾–2	2¼–4
5	0.2890	0.2903	0.2883	0.2900	0.2890	0.299	0.279	1–2½	2¾–6
6	0.3410	0.3423	0.3403	0.3420	0.3410	0.351	0.331	1¼–3	3¼–6
7	0.4090	0.4103	0.4083	0.4100	0.4090	0.419	0.399	1¼–3¾	4–8
8	0.4920	0.4933	0.4913	0.4930	0.4920	0.502	0.482	1¼–4½	4¾–8
9	0.5910	0.5923	0.5903	0.5920	0.5910	0.601	0.581	1½–5¼	5½–8
10	0.7060	0.7073	0.7053	0.7070	0.7060	0.716	0.696	1½–6	6¼–8
11	0.8600	0.8613	0.8593	…	…	0.870	0.850	…	2–8
12	1.0320	1.0333	1.0313	…	…	1.042	1.022	…	2–9
13	1.2410	1.2423	1.2403	…	…	1.251	1.231	…	3–11
14	1.5210	1.5223	1.5203	…	…	1.531	1.511	…	3–13

[a] When specifying nominal pin size in decimals, zeros preceding the decimal and in the fourth decimal place are omitted.

[b] Lengths increase in ⅛-inch steps up to 1 inch and in ¼-inch steps above 1 inch.

[c] Standard reamers are available for pin lengths in this column.

All dimensions are in inches.

For nominal diameters, B, see Table 5.

American National Standard Grooved Pins.— These pins have three equally spaced longitudinal grooves and an expanded diameter over the crests of the ridges formed by the material displaced when the grooves are produced. The grooves are aligned with the axes of the pins. There are seven types of grooved pins as shown in the illustration on page 1679.

Standard Sizes and Lengths: The standard sizes and lengths in which grooved pins are normally available are given in Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Materials: Grooved pins are normally made from cold drawn low carbon steel wire or rod. Where additional performance is required, carbon steel pins may be supplied surface hardened and heat treated to a hardness consistent with the performance requirements. Pins may also be made from alloy steel, corrosion resistant steel, brass, Monel and other non-ferrous metals having chemical properties as agreed upon between manufacturer and purchaser.

Performance Requirements: Grooved pins are required to withstand the minimum double shear loads given in Table 7 for the respective materials shown, when tested in accordance with the Double Shear Testing of Pins as set forth in ANSI/ASME B18.8.2-1995, Appendix B.

Hole Sizes: To obtain maximum product retention under average conditions, it is recommended that holes for the installation of grooved pins be held as close as possible to the limits shown in Table 7. The minimum limits correspond to the drill size, which is the same as the basic pin diameter. The maximum limits are generally suitable for length-diameter ratios of not less than 4 to 1 nor greater than 10 to 1. For smaller length-to-diameter ratios, the hole should be held closer to the minimum limits where retention is critical. Conversely for larger ratios where retention requirements are less important, it may be desirable to increase the hole diameters beyond the maximum limits shown.

Designation: Grooved pins are designated by the following data in the sequence shown: Product name (noun first) including type designation, nominal size (number, fraction or decimal equivalent), length (fraction or decimal equivalent), material, including specification or heat treatment where necessary, protective finish, if required.

Examples: Pin, Type A Grooved, 3/32 × 3/4, Steel, Zinc Plated

Pin, Type F Grooved, 0.250 × 1.500, Corrosion Resistant Steel

American National Standard Grooved T-Head Cotter Pins and Round Head Grooved Drive Studs.— The cotter pins have a T-head and the studs a round head. Both pins and studs have three equally spaced longitudinal grooves and an expanded diameter over the crests of the raised ridges formed by the material displaced when the grooves are formed.

Standard Sizes and Lengths: The standard sizes and range of standard lengths are given in Tables 8 and 9.

Material: Unless otherwise specified these pins are made from low carbon steel. Where so indicated by the purchaser they may be made from corrosion resistant steel, brass or other non-ferrous alloys.

Hole Sizes: To obtain optimum product retention under average conditions, it is recommended that holes for the installation of grooved T-head cotter pins and grooved drive studs be held as close as possible to the limits tabulated. The minimum limits given correspond to the drill size, which is equivalent to the basic shank diameter. The maximum limits shown are generally suitable for length-diameter ratios of not less than 4 to 1 and not greater than 10 to 1. For smaller length-to-diameter ratios, the holes should be held closer to minimum limits where retention is critical. Conversely, for larger length-to-diameter ratios or where retention requirements are not essential, it may be desirable to increase the hole diameter beyond the maximum limits shown.

Designation: Grooved T-head cotter pins and round head grooved drive studs are designated by the following data, in the order shown: Product name (noun first), nominal size (number, fraction or decimal equivalent), length (fraction or decimal equivalent), material including specification or heat treatment where necessary, and protective finish, if required.

Examples: Pin, Grooved T-Head Cotter, 1/4 × 1 1/4, Steel, Zinc Plated

Drive Stud, Round Head Grooved, No. 10 × 1/2, Corrosion Resistant Steel

Copyright 2004, Industrial Press, Inc., New York, NY



Types of American National Standard Grooved Pins, ANSI/ASME B18.8.2-1995 (For notes see bottom of Table 7.)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Grooved Pins *ANSI/ASME B18.8.2-1995*

Nominal Size or Basic Pin Diameter		Pin Diameter,[a] *A*		Pilot Length, *C*	Chamfer Length,[b] *D*	Crown Height,[b] *E*		Crown Radius,[b] *F*		Neck Width, *G*		Shoulder Length, *H*		Neck Radius, *J*	Neck Diameter, *K*		Range of Standard Lengths[c]
		Max	Min	Ref	Min	Max	Min	Max	Min	Max	Min	Max	Min	Ref	Max	Min	
1/32[d]	0.0312	0.0312	0.0302	0.015	…	…	…	…	…	…	…	…	…	…	…	…	1/8–1/2
3/64[d]	0.0469	0.0469	0.0459	0.031	…	…	…	…	…	…	…	…	…	…	…	…	1/8–5/8
1/16	0.0625	0.0625	0.0615	0.031	0.016	0.0115	0.0015	0.088	0.068	…	…	…	…	…	…	…	1/8–1
5/64[d]	0.0781	0.0781	0.0771	0.031	0.016	0.0137	0.0037	0.104	0.084	…	…	…	…	…	…	…	1/4–1
3/32	0.0938	0.0938	0.0928	0.031	0.016	0.0141	0.0041	0.135	0.115	0.038	0.028	0.041	0.031	0.016	0.067	0.057	1/4–1 1/4
7/64[d]	0.1094	0.1094	0.1074	0.031	0.016	0.0160	0.0060	0.150	0.130	0.038	0.028	0.041	0.031	0.016	0.082	0.072	1/4–1 1/4
1/8	0.1250	0.1250	0.1230	0.031	0.016	0.0180	0.0080	0.166	0.146	0.069	0.059	0.041	0.031	0.031	0.088	0.078	1/4–1 1/2
5/32	0.1563	0.1563	0.1543	0.062	0.031	0.0220	0.0120	0.198	0.178	0.069	0.059	0.057	0.047	0.031	0.109	0.099	3/8–2
3/16	0.1875	0.1875	0.1855	0.062	0.031	0.0230	0.0130	0.260	0.240	0.069	0.059	0.057	0.047	0.031	0.130	0.120	3/8–2 1/4
7/32	0.2188	0.2188	0.2168	0.062	0.031	0.0270	0.0170	0.291	0.271	0.101	0.091	0.072	0.062	0.047	0.151	0.141	1/2–3
1/4	0.2500	0.2500	0.2480	0.062	0.031	0.0310	0.0210	0.322	0.302	0.101	0.091	0.072	0.062	0.047	0.172	0.162	1/2–3 1/4
5/16	0.3125	0.3125	0.3105	0.094	0.047	0.0390	0.0290	0.385	0.365	0.132	0.122	0.104	0.094	0.062	0.214	0.204	5/8–3 1/2
3/8	0.3750	0.3750	0.3730	0.094	0.047	0.0440	0.0340	0.479	0.459	0.132	0.122	0.135	0.125	0.062	0.255	0.245	3/4–4 1/4
7/16	0.4375	0.4375	0.4355	0.094	0.047	0.0520	0.0420	0.541	0.521	0.195	0.185	0.135	0.125	0.094	0.298	0.288	7/8–4 1/2
1/2	0.5000	0.5000	0.4980	0.094	0.047	0.0570	0.0470	0.635	0.615	0.195	0.185	0.135	0.125	0.094	0.317	0.307	1–4 1/2

[a] For expanded diameters, *B*, see ANSI/ASME B18.8.2-1995.

[b] Pins in 1/32- and 3/64-inch sizes of any length and all sizes of 1/4-inch nominal length or shorter are not crowned or chamfered.

[c] Standard lengths increase in 1/8-inch steps from 1/8 to 1 inch, and in 1/4-inch steps above 1 inch. Standard lengths for the 1/32-, 3/64-, 1/16-, and 5/64-inch sizes and the 1/4-inch length for the 3/32-, 7/64-, and 1/8-inch sizes do not apply to Type G grooved pins.

[d] Non-stock items, not recommended for new designs.

Pin Material	Nominal Pin Size														
	1/32	3/64	1/16	5/64	3/32	7/64	1/8	5/32	3/16	7/32	1/4	5/16	3/8	7/16	1/2
Steels	Double Shear Load, Min, lb														
Low Carbon	100	220	410	620	890	1,220	1,600	2,300	3,310	4,510	5,880	7,660	11,000	15,000	19,600
Alloy (R_c 40 – 48 hardness)	180	400	720	1,120	1,600	2,180	2,820	4,520	6,440	8,770	11,500	17,900	26,000	35,200	46,000
Corrosion Resistant	140	300	540	860	1,240	1,680	2,200	3,310	4,760	6,480	8,460	12,700	18,200	24,800	32,400
Brass	60	140	250	390	560	760	990	1,540	2,220	3,020	3,950	6,170	9,050	12,100	15,800
	Recommended Hole Sizes for Unplated Pins (The minimum drill size is the same as the pin size. See also text on page 1678.)														
Maximum Diameter	0.0324	0.0482	0.0640	0.0798	0.0956	0.1113	0.1271	0.1587	0.1903	0.2219	0.2534	0.3166	0.3797	0.4428	0.5060
Minimum Diameter	0.0312	0.0469	0.0625	0.0781	0.0938	0.1094	0.1250	0.1563	0.1875	0.2188	0.2500	0.3125	0.3750	0.4375	0.5000

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. American National Standard Grooved T-Head Cotter Pins
ANSI/ASME B18.8.2-1995



Nominal Size[a] or Basic Shank Dia.		Shank Diameter, *A*		Length, *N*	Head Dia., *O*		Head Height, *P*		Head Width, *Q*		Range of Standard Lengths,[b] *L*	Recommended Hole Size	
		Max	Min	Max	Max	Min	Max	Min	Max	Min		Max	Min
5/32	0.156	0.154	0.150	0.08	0.26	0.24	0.11	0.09	0.18	0.15	3/4–1 1/8	0.161	0.156
3/16	0.187	0.186	0.182	0.09	0.30	0.28	0.13	0.11	0.22	0.18	3/4–1 1/4	0.193	0.187
1/4	0.250	0.248	0.244	0.12	0.40	0.38	0.17	0.15	0.28	0.24	1–1 1/2	0.257	0.250
5/16	0.312	0.310	0.305	0.16	0.51	0.48	0.21	0.19	0.34	0.30	1 1/8–2	0.319	0.312
23/64	0.359	0.358	0.353	0.18	0.57	0.54	0.24	0.22	0.38	0.35	1 1/4–2	0.366	0.359
1/2	0.500	0.498	0.493	0.25	0.79	0.76	0.32	0.30	0.54	0.49	2–3	0.508	0.500

[a] When specifying nominal size in decimals, zeros preceding decimal point and in the fourth decimal place are omitted.

[b] Lengths increase in 1/8-inch steps from 3/4 to 1 1/4 inch and in 1/4-inch steps above 1 1/4 inches. For groove length, *M*, dimensions see ANSI/ASME B18.8.2-1995.

All dimensions are in inches.

For expanded diameter, *B*, dimensions, see ANSI/ASME B18.8.2-1995.

Table 9. American National Standard Round Head Grooved Drive Studs
ANSI/ASME B18.8.2-1995



Stud Size Number and Basic Shank Diameter[a]		Shank Diameter, *A*		Head Diameter, *O*		Head Height, *P*		Range of Standard Lengths,[b] *L*	Recommended Hole Size		Drill Size
		Max	Min	Max	Min	Max	Min		Max	Min	
0	0.067	0.067	0.065	0.130	0.120	0.050	0.040	1/8–1/4	0.0686	0.0670	51
2	0.086	0.086	0.084	0.162	0.146	0.070	0.059	1/8–1/4	0.0877	0.0860	44
4	0.104	0.104	0.102	0.211	0.193	0.086	0.075	3/16–5/16	0.1059	0.1040	37
6	0.120	0.120	0.118	0.260	0.240	0.103	0.091	1/4–3/8	0.1220	0.1200	31
7	0.136	0.136	0.134	0.309	0.287	0.119	0.107	5/16–1/2	0.1382	0.1360	29
8	0.144	0.144	0.142	0.309	0.287	0.119	0.107	3/8–5/8	0.1463	0.1440	27
10	0.161	0.161	0.159	0.359	0.334	0.136	0.124	3/8–5/8	0.1636	0.1610	20
12	0.196	0.196	0.194	0.408	0.382	0.152	0.140	1/2–3/4	0.1990	0.1960	9
14	0.221	0.221	0.219	0.457	0.429	0.169	0.156	1/2–3/4	0.2240	0.2210	2
16	0.250	0.250	0.248	0.472	0.443	0.174	0.161	1/2	0.2534	0.2500	1/4

[a] Where specifying nominal size in decimals, zeros preceding decimal point and in the fourth decimal place are omitted.

[b] Lengths increase in 1/16-inch steps from 1/8 to 3/8 inch and in 1/8-inch steps above 3/8 inch.

All dimensions are in inches.

For pilot length, *M*, and expanded diameter, *B*, dimensions see ANSI/ASME B18.8.2-1995.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. American National Standard Slotted Type Spring Pins
ANSI/ASME B18.8.2-1995



STYLE 1 STYLE 2

Nominal Size[a] or Basic Pin Diameter		Average Pin Diameter, A		Chamfer Dia., B	Chamfer Length, C		Stock Thickness, F	Recommended Hole Size		Material: SAE 1070 – 1095 and SAE 51420	Material: SAE 30302 and 30304	Material: Beryllium Copper	Range of Practical Lengths[b]
		Max	Min	Max	Max	Min	Basic	Max	Min	Double Shear Load, Min, lb			
1/16	0.062	0.069	0.066	0.059	0.028	0.007	0.012	0.065	0.062	430	250	270	3/16–1
5/64	0.078	0.086	0.083	0.075	0.032	0.008	0.018	0.081	0.078	800	460	500	3/16–1 1/2
3/32	0.094	0.103	0.099	0.091	0.038	0.008	0.022	0.097	0.094	1,150	670	710	3/16–1 1/2
1/8	0.125	0.135	0.131	0.122	0.044	0.008	0.028	0.129	0.125	1,875	1,090	1,170	5/16–2
9/64	0.141	0.149	0.145	0.137	0.044	0.008	0.028	0.144	0.140	2,175	1,260	1,350	3/8–2
5/32	0.156	0.167	0.162	0.151	0.048	0.010	0.032	0.160	0.156	2,750	1,600	1,725	7/16–2 1/2
3/16	0.188	0.199	0.194	0.182	0.055	0.011	0.040	0.192	0.187	4,150	2,425	2,600	1/2–2 1/2
7/32	0.219	0.232	0.226	0.214	0.065	0.011	0.048	0.224	0.219	5,850	3,400	3,650	1/2–3
1/4	0.250	0.264	0.258	0.245	0.065	0.012	0.048	0.256	0.250	7,050	4,100	4,400	1/2–3 1/2
5/16	0.312	0.330	0.321	0.306	0.080	0.014	0.062	0.318	0.312	10,800	6,300	6,750	3/4–4
3/8	0.375	0.395	0.385	0.368	0.095	0.016	0.077	0.382	0.375	16,300	9,500	10,200	3/4, 7/8, 1, 1 1/4, 1 1/2, 1 3/4, 2–4
7/16	0.438	0.459	0.448	0.430	0.095	0.017	0.077	0.445	0.437	19,800	11,500	12,300	1, 1 1/4, 1 1/2, 1 3/4, 2–4
1/2	0.500	0.524	0.513	0.485	0.110	0.025	0.094	0.510	0.500	27,100	15,800	17,000	1 1/4, 1 1/2, 1 3/4, 2–4
5/8	0.625	0.653	0.640	0.608	0.125	0.030	0.125	0.636	0.625	46,000	18,800	…	2–6
3/4	0.750	0.784	0.769	0.730	0.150	0.030	0.150	0.764	0.750	66,000	23,200	…	2–6

[a] Where specifying nominal size in decimals, zeros preceding decimal point are omitted.
[b] Length increments are 1/16 inch from 1/8 to 1 inch; 1/8 from 1 inch to 2 inches; and 1/4 inch from 2 inches to 6 inches.

All dimensions are in inches.

American National Standard Spring Pins.— These pins are made in two types: one type has a slot throughout its length; the other is shaped into a coil.

Preferred Lengths and Sizes: The preferred lengths and sizes in which these pins are normally available are given in Tables 10 and 11.

Materials: Spring pins are normally made from SAE 1070–1095 carbon steel, SAE 6150H alloy steel, SAE types 51410 through 51420, 30302 and 30304 corrosion resistant steels, and beryllium copper alloy, heat treated or cold worked to attain the hardness and performance characteristics set forth in ANSI/ASME B18.8.2-1995.

Designation: Spring pins are designated by the following data in the sequence shown:

Examples: Pin, Coiled Spring, 1/4 × 1 1/4, Standard Duty, Steel, Zinc Plated

Pin, Slotted Spring, 1/2 × 3, Steel, Phosphate Coated

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. American National Standard Coiled Type Spring Pins *ANSI/ASME B18.8.2-1995*



Nominal Size or Basic Pin Diameter	Pin Diameter, *A*						Chamfer		Recommended Hole Size		SAE Material Number					
	Standard Duty		Heavy Duty		Light Duty		Dia., *B*	Length, *C*			1070–1095 and 51420	30302 and 30304	1070–1095 and 51420	30302 and 30304	1070–1095 and 51420	30302 and 30304
											Double Shear Load, Min, lb					
	Max	Min	Max	Min	Max	Min	Max	Ref	Max	Min	Standard Duty		Heavy Duty		Light Duty	
1/32 0.031	0.035	0.033	…	…	…	…	0.029	0.024	0.032	0.031	90[a]	65	…	…	…	…
0.039	0.044	0.041	…	…	…	…	0.037	0.024	0.040	0.039	135[a]	100	…	…	…	…
3/64 0.047	0.052	0.049	…	…	…	…	0.045	0.024	0.048	0.046	190[a]	145	…	…	…	…
0.052	0.057	0.054	…	…	…	…	0.050	0.024	0.053	0.051	250[a]	190	…	…	…	…
1/16 0.062	0.072	0.067	0.070	0.066	0.073	0.067	0.059	0.028	0.065	0.061	330	265	475	360	205	160
5/64 0.078	0.088	0.083	0.086	0.082	0.089	0.083	0.075	0.032	0.081	0.077	550	425	800	575	325	250
3/32 0.094	0.105	0.099	0.103	0.098	0.106	0.099	0.091	0.038	0.097	0.093	775	600	1,150	825	475	360
7/64 0.109	0.120	0.114	0.118	0.113	0.121	0.114	0.106	0.038	0.112	0.108	1,050	825	1,500	1,150	650	500
1/8 0.125	0.138	0.131	0.136	0.130	0.139	0.131	0.121	0.044	0.129	0.124	1,400	1,100	2,000	1,700	825	650
5/32 0.156	0.171	0.163	0.168	0.161	0.172	0.163	0.152	0.048	0.160	0.155	2,200	1,700	3,100	2,400	1,300	1,000
3/16 0.188	0.205	0.196	0.202	0.194	0.207	0.196	0.182	0.055	0.192	0.185	3,150	2,400	4,500	3,500	1,900	1,450
7/32 0.219	0.238	0.228	0.235	0.226	0.240	0.228	0.214	0.065	0.224	0.217	4,200	3,300	5,900	4,600	2,600	2,000
1/4 0.250	0.271	0.260	0.268	0.258	0.273	0.260	0.243	0.065	0.256	0.247	5,500	4,300	7,800	6,200	3,300	2,600
5/16 0.312	0.337	0.324	0.334	0.322	0.339	0.324	0.304	0.080	0.319	0.308	8,700	6,700	12,000	9,300	5,200	4,000
3/8 0.375	0.403	0.388	0.400	0.386	0.405	0.388	0.366	0.095	0.383	0.370	12,600	9,600	18,000	14,000	…	…
7/16 0.438	0.469	0.452	0.466	0.450	0.471	0.452	0.427	0.095	0.446	0.431	17,000	13,300	23,500	18,000	…	…
1/2 0.500	0.535	0.516	0.532	0.514	0.537	0.516	0.488	0.110	0.510	0.493	22,500	17,500	32,000	25,000	…	…
5/8 0.625	0.661	0.642	0.658	0.640	…	…	0.613	0.125	0.635	0.618	35,000[b]	…	48,000[b]	…	…	…
3/4 0.750	0.787	0.768	0.784	0.766	…	…	0.738	0.150	0.760	0.743	50,000[b]	…	70,000[b]	…	…	…

[a] Sizes 1/32 inch through 0.052 inch are not available in SAE 1070–1095 carbon steel.

[b] Sizes 5/8 inch and larger are produced from SAE 6150H alloy steel, not SAE 1070–1095 carbon steel. Practical lengths, *L*, for sizes 1/32 through 0.052 inch are 1/8 through 5/8 inch and for the 7/64-inch size, 1/4 through 1 3/4 inches. For lengths of other sizes see Table 10.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

RETAINING RINGS

Retaining Rings.— The purpose of a retaining ring is to act as an artificial shoulder that will retain an object in a housing (internal ring), as shown in Fig. 1, or on a shaft (external ring). Two types of retaining ring are common, the stamped ring and the spiral-wound ring. The stamped type of retaining ring, or snap ring, is stamped from tempered sheet metal and has a nonuniform cross-section. The typical spiral-wound retaining ring has a uniform cross-section and is made up of two or more turns of coiled, spring-tempered steel, although one-turn spiral-wound rings are common. Spiral-wound retaining rings provide a continuous gapless shoulder to a housing or shaft. Most stamped rings can only be installed at or near the end of a shaft or housing. The spiral-wound design generally requires installation from the end of a shaft or housing. Both types, stamped and spiral, are usually installed into grooves on the shaft or housing.



Fig. 1. Typical Retaining Ring Installation Showing Maximum Total Radius or Chamfer (*Courtesy Spirolox Retaining Rings*)

In the section that follows, Tables 1 through 6 give dimensions and data on general-purpose tapered and reduced cross-section metric retaining rings (stamped type) covered by ANSI B27.7-1977, R1993. Tables 1 and 4 cover Type 3AM1 tapered external retaining rings, Tables 2 and 5 cover Type 3BM1 tapered internal rings, and Tables 3 and 6 cover Type 3CM1 reduced cross-section external rings. Tables 7 through 10 cover inch sizes of internal and external spiral retaining rings corresponding to MIL-R-27426 Types A (external) and B (internal), Class 1 (medium duty) and Class 2 (heavy duty). Tables 11 through 17 cover stamped retaining rings in inch sizes.

Table 1. American National Standard Metric Tapered Retaining Rings — Basic External Series — 3AM1 *ANSI B27.7-1977, R1993*



Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **American National Standard Metric Tapered Retaining Rings — Basic External Series — 3AM1 ANSI B27.7-1977, R1993**

Shaft Dia.	Ring		Groove				Shaft Diam	Ring		Groove			
	Free Dia.	Thick ness	Dia.	Width	Depth	Edge Margin		Free Dia.	Thick ness	Dia.	Width	Depth	Edge Margin
S	*D*	*t*	*G*	*W*	*d* ref	*Z* min	*S*	*D*	*t*	*G*	*W*	*d* ref	*Z* min
4	3.60	0.25	3.80	0.32	0.1	0.3	36	33.25	1.3	33.85	1.4	1.06	3.2
5	4.55	0.4	4.75	0.5	0.13	0.4	38	35.20	1.3	35.8	1.4	1.10	3.3
6	5.45	0.4	5.70	0.5	0.15	0.5	40	36.75	1.6	37.7	1.75	1.15	3.4
7	6.35	0.6	6.60	0.7	0.20	0.6	42	38.80	1.6	39.6	1.75	1.20	3.6
8	7.15	0.6	7.50	0.7	0.25	0.8	43	39.65	1.6	40.5	1.75	1.25	3.8
9	8.15	0.6	8.45	0.7	0.28	0.8	45	41.60	1.6	42.4	1.75	1.30	3.9
10	9.00	0.6	9.40	0.7	0.30	0.9	46	42.55	1.6	43.3	1.75	1.35	4.0
11	10.00	0.6	10.35	0.7	0.33	1.0	48	44.40	1.6	45.2	1.75	1.40	4.2
12	10.85	0.6	11.35	0.7	0.33	1.0	50	46.20	1.6	47.2	1.75	1.40	4.2
13	11.90	0.9	12.30	1.0	0.35	1.0	52	48.40	2.0	49.1	2.15	1.45	4.3
14	12.90	0.9	13.25	1.0	0.38	1.2	54	49.9	2.0	51.0	2.15	1.50	4.5
15	13.80	0.9	14.15	1.0	0.43	1.3	55	50.6	2.0	51.8	2.15	1.60	4.8
16	14.70	0.9	15.10	1.0	0.45	1.4	57	52.9	2.0	53.8	2.15	1.60	4.8
17	15.75	0.9	16.10	1.0	0.45	1.4	58	53.6	2.0	54.7	2.15	1.65	4.9
18	16.65	1.1	17.00	1.2	0.50	1.5	60	55.8	2.0	56.7	2.15	1.65	4.9
19	17.60	1.1	17.95	1.2	0.53	1.6	62	57.3	2.0	58.6	2.15	1.70	5.1
20	18.35	1.1	18.85	1.2	0.58	1.7	65	60.4	2.0	61.6	2.15	1.70	5.1
21	19.40	1.1	19.80	1.2	0.60	1.8	68	63.1	2.0	64.5	2.15	1.75	5.3
22	20.30	1.1	20.70	1.2	0.65	1.9	70	64.6	2.4	66.4	2.55	1.80	5.4
23	21.25	1.1	21.65	1.2	0.67	2.0	72	66.6	2.4	68.3	2.55	1.85	5.5
24	22.20	1.1	22.60	1.2	0.70	2.1	75	69.0	2.4	71.2	2.55	1.90	5.7
25	23.10	1.1	23.50	1.2	0.75	2.3	78	72.0	2.4	74.0	2.55	2.00	6.0
26	24.05	1.1	24.50	1.2	0.75	2.3	80	74.2	2.4	75.9	2.55	2.05	6.1
27	24.95	1.3	25.45	1.4	0.78	2.3	82	76.4	2.4	77.8	2.55	2.10	6.3
28	25.80	1.3	26.40	1.4	0.80	2.4	85	78.6	2.4	80.6	2.55	2.20	6.6
30	27.90	1.3	28.35	1.4	0.83	2.5	88	81.4	2.8	83.5	2.95	2.25	6.7
32	29.60	1.3	30.20	1.4	0.90	2.7	90	83.2	2.8	85.4	2.95	2.30	6.9
34	31.40	1.3	32.00	1.4	1.00	3.0	95	88.1	2.8	90.2	2.95	2.40	7.2
35	32.30	1.3	32.90	1.4	1.05	3.1	100	92.5	2.8	95.0	2.95	2.50	7.5

All dimensions are in millimeters. Sizes –4, –5, and –6 are available in beryllium copper only.

These rings are designated by series symbol and shaft diameter, thus: for a 4 mm diameter shaft, 3AM1-4; for a 20 mm diameter shaft, 3AM1-20; etc.

Ring Free Diameter Tolerances: For ring sizes –4 through –6, +0.05, –0.10 mm; for sizes –7 through –12, +0.05, –0.15 mm; for sizes –13 through – 26, +0.15, –0.25 mm; for sizes –27 through –38, +0.25, –0.40 mm; for sizes –40 through –50, +0.35, –0.50 mm; for sizes –52 through –62, +0.35, –0.65 mm; and for sizes –65 through –100, +0.50, –0.75 mm.

Groove Diameter Tolerances: For ring sizes –4 through –6, –0.08 mm; for sizes –7 through –10, –0.10 mm; for sizes –11 through –15, –0.12 mm; for sizes –16 through –26, –0.15 mm; for sizes –27 through – 36, –0.20 mm; for sizes –38 through –55, –0.30 mm; and for sizes –57 through –100, –0.40 mm.

Groove Diameter F.I.M. (full indicator movement) or maximum allowable deviation of concentricity between groove and shaft: For ring sizes –4 through –6, 0.03 mm; for ring sizes –7 through –12, 0.05 mm; for sizes –13 through –28, 0.10 mm; for sizes –30 through –55, 0.15 mm; and for sizes –57 through – 00, 0.20 mm.

Groove Width Tolerances: For ring size –4, +0.05 mm; for sizes –5 and –6, +0.10 mm, for sizes –7 through –38, +0.15 mm; and for sizes –40 through – 100, +0.20 mm.

Groove Maximum Bottom Radii,R: For ring sizes –4 through –6, none; for sizes –7 through –18, 0.1 mm; for sizes –19 through –30, 0.2 mm; for sizes –32 through –50, 0.3 mm; and for sizes –52 through –100, 0.4 mm. For manufacturing details not shown, including materials, see ANSI B27.7-1977, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Metric Tapered Retaining Rings — Basic Internal Series — 3BM1 *ANSI B27.7-1977, R1993*



Shaft Dia.	Ring		Groove				Shaft Dia.	Ring		Groove			
	Free Dia.	Thickness	Dia.	Width	Depth	Edge Margin		Free Dia.	Thickness	Dia.	Width	Depth	Edge Margin
S	*D*	*t*	*G*	*W*	*d* ref	*Z* min	*S*	*D*	*t*	*G*	*W*	*d* ref	*Z* min
8	8.80	0.4	8.40	0.5	0.2	0.6	65	72.2	2.4	69.0	2.55	2.00	6.0
9	10.00	0.6	9.45	0.7	0.23	0.7	68	75.7	2.4	72.2	2.55	2.10	6.3
10	11.10	0.6	10.50	0.7	0.25	0.8	70	77.5	2.4	74.4	2.55	2.20	6.6
11	12.20	0.6	11.60	0.7	0.3	0.9	72	79.6	2.4	76.5	2.55	2.25	6.7
12	13.30	0.6	12.65	0.7	0.33	1.0	75	83.3	2.4	79.7	2.55	2.35	7.1
13	14.25	0.9	13.70	1.0	0.35	1.1	78	86.8	2.8	82.8	2.95	2.40	7.2
14	15.45	0.9	14.80	1.0	0.40	1.2	80	89.1	2.8	85.0	2.95	2.50	7.5
15	16.60	0.9	15.85	1.0	0.43	1.3	82	91.1	2.8	87.2	2.95	2.60	7.8
16	17.70	0.9	16.90	1.0	0.45	1.4	85	94.4	2.8	90.4	2.95	2.70	8.1
17	18.90	0.9	18.00	1.0	0.50	1.5	88	97.9	2.8	93.6	2.95	2.80	8.4
18	20.05	0.9	19.05	1.0	0.53	1.6	90	100.0	2.80	95.7	2.95	2.85	8.6
19	21.10	0.9	20.10	1.0	0.55	1.7	92	102.2	2.8	97.8	2.95	2.90	8.7
20	22.25	0.9	21.15	1.0	0.57	1.7	95	105.6	2.8	101.0	2.95	3.00	9.0
21	23.30	0.9	22.20	1.0	0.60	1.8	98	109.0	2.8	104.2	2.95	3.10	9.3
22	24.40	1.1	23.30	1.2	0.65	1.9	100	110.7	2.8	106.3	2.95	3.15	9.5
23	25.45	1.1	24.35	1.2	0.67	2.0	102	112.4	2.8	108.4	2.95	3.20	9.6
24	26.55	1.1	25.4	1.2	0.70	2.1	105	115.8	2.8	111.5	2.95	3.25	9.8
25	27.75	1.1	26.6	1.2	0.80	2.4	108	119.2	2.8	114.6	2.95	3.30	9.9
26	28.85	1.1	27.7	1.2	0.85	2.6	110	120.8	2.8	116.7	2.95	3.35	10.1
27	29.95	1.3	28.8	1.4	0.90	2.7	115	126.0	2.8	121.9	2.95	3.45	10.4
28	31.10	1.3	29.8	1.4	0.90	2.7	120	132.4	2.8	127.0	2.95	3.50	10.5
30	33.40	1.3	31.9	1.4	0.95	2.9	125	137.1	2.8	132.1	2.95	3.55	10.7
32	35.35	1.3	33.9	1.4	0.95	2.9	130	142.5	2.8	137.2	2.95	3.60	10.8
34	37.75	1.3	36.1	1.4	1.05	3.2	135	148.5	3.2	142.3	3.40	3.65	11.0
35	38.75	1.3	37.2	1.4	1.10	3.3	140	154.1	3.2	147.4	3.40	3.70	11.1
36	40.00	1.3	38.3	1.4	1.15	3.5	145	159.5	3.2	152.5	3.40	3.75	11.3
37	41.05	1.3	39.3	1.4	1.15	3.5	150	164.5	3.2	157.6	3.40	3.80	11.4
38	42.15	1.3	40.4	1.4	1.20	3.6	155	168.8	3.2	162.7	3.40	3.85	11.6
40	44.25	1.6	42.4	1.75	1.20	3.6	160	175.1	4.0	167.8	4.25	3.90	11.7
42	46.60	1.6	44.5	1.75	1.25	3.7	165	180.3	4.0	172.9	4.25	3.95	11.9
45	49.95	1.6	47.6	1.75	1.30	3.9	170	185.6	4.0	178.0	4.25	4.00	12.0
46	51.05	1.6	48.7	1.75	1.35	4.0	175	191.3	4.0	183.2	4.25	4.10	12.3
47	52.15	1.6	49.8	1.75	1.40	4.2	180	196.6	4.0	188.4	4.25	4.20	12.6
48	53.30	1.6	50.9	1.75	1.45	4.3	185	202.7	4.8	193.6	5.10	4.30	12.9
50	55.35	1.6	53.1	1.75	1.55	4.6	190	207.7	4.8	198.8	5.10	4.40	13.2
52	57.90	2.0	55.3	2.15	1.65	5.0	200	217.8	4.8	209.0	5.10	4.50	13.5
55	61.10	2.0	58.4	2.15	1.70	5.1	210	230.3	4.8	219.4	5.10	4.70	14.1
57	63.25	2.0	60.5	2.15	1.75	5.3	220	240.5	4.8	230.0	5.10	5.00	15.0
58	64.4	2.0	61.6	2.15	1.80	5.4	230	251.4	4.8	240.6	5.10	5.30	15.9
60	66.8	2.0	63.8	2.15	1.90	5.7	240	262.3	4.8	251.0	5.10	5.50	16.5
62	68.6	2.0	65.8	2.15	1.90	5.7	250	273.3	4.8	261.4	5.10	5.70	17.1
63	69.9	2.0	66.9	2.15	1.95	5.9	…	…	…	…	…	…	…

All dimensions are in millimeters.

These rings are designated by series symbol and shaft diameter, thus: for a 9 mm diameter shaft, 3BM1-9; for a 22 mm diameter shaft, 3BM1-22; etc.

Ring Free Diameter Tolerances: For ring sizes –8 through –20, +0.25, –0.13 mm; for sizes –21 through –26, +0.40, –0.25 mm; for sizes –27 through –38, +0.65, –0.50 mm; for sizes –40 through –50, +0.90, –0.65 mm; for sizes –52 through –75, +1.00, –0.75 mm; for sizes –78 through –92, +1.40,

Copyright 2004, Industrial Press, Inc., New York, NY

–1.40 mm; for sizes –95 through –155, +1.65, –1.65 mm; for sizes –160 through –180, +2.05, –2.05 mm; and for sizes –185 through –250, +2.30, –2.30 mm.

Groove Diameter Tolerances: For ring sizes –8 and –9, +0.06 mm; for sizes –10 through –18, +0.10 mm; for sizes –19 through – 28, +0.15 mm; for sizes –30 through –50, +0.20 mm; for sizes – 52 through –98, +0.30; for sizes –100 through –160, +0.40 mm; and for sizes –165 through –250, +0.50 mm.

Groove Diameter F.I.M. (full indicator movement) or maximum allowable deviation of concentricity between groove and shaft: For ring sizes –8 through –10, 0.03 mm; for sizes –11 through –15, 0.05 mm; for sizes –16 through –25, 0.10 mm; for sizes –26 through –45, 0.15 mm; for sizes –46 through –80, 0.20 mm; for sizes –82 through –150, 0.25 mm; and for sizes –155 through –250, 0.30 mm.

Groove Width Tolerances: For ring size –8, +0.10 mm; for sizes –9 through –38, +0.15 mm; for sizes –40 through –130, +0.20 mm; and for sizes –135 through –250, +0.25 mm.

Groove Maximum Bottom Radii: For ring sizes –8 through –17, 0.1 mm; for sizes –18 through – 30, 0.2 mm; for sizes –32 through –55, 0.3 mm; and for sizes –56 through –250, 0.4 mm.

For manufacturing details not shown, including materials, see ANSI B27.7-1977, R1993.

Table 3. American National Standard Metric Reduced Cross Section Retaining Rings — E Ring External Series —3CM1 *ANSI B27.7-1977, R1993*



Shaft Dia.	Ring			Groove				Shaft Dia.	Ring			Groove			
	Free Dia.	Thickness	Outer Dia.	Dia.	Width	Depth	Edge Margin		Free Dia.	Thickness	Outer Dia.	Dia.	Width	Depth	Edge Margin
S	*D*	*t*	*Y* nom	*G*	*W*	*d* ref	*Z* min	*S*	*D*	*t*	*Y* nom	*G*	*W*	*d* ref	*Z* min
1	0.64	0.25	2.0	0.72	0.32	0.14	0.3	11	8.55	0.9	17.4	8.90	1.0	1.05	2.1
2	1.30	0.25	4.0	1.45	0.32	0.28	0.6	12	9.20	1.1	18.6	9.60	1.2	1.20	2.4
3	2.10	0.4	5.6	2.30	0.5	0.35	0.7	13	9.95	1.1	20.3	10.30	1.2	1.35	2.7
4	2.90	0.6	7.2	3.10	0.7	0.45	0.9	15	11.40	1.1	22.8	11.80	1.2	1.60	3.2
5	3.70	0.6	8.5	3.90	0.7	0.55	1.1	16	12.15	1.1	23.8	12.50	1.2	1.75	3.5
6	4.70	0.6	11.1	4.85	0.7	0.58	1.2	18	13.90	1.3	27.2	14.30	1.4	1.85	3.7
7	5.25	0.6	13.4	5.55	0.7	0.73	1.5	20	15.60	1.3	30.0	16.00	1.4	2.00	4.0
8	6.15	0.6	14.6	6.40	0.7	0.80	1.6	22	17.00	1.3	33.0	17.40	1.4	2.30	4.6
9	6.80	0.9	15.8	7.20	1.0	0.90	1.8	25	19.50	1.3	37.1	20.00	1.4	2.50	5.0
10	7.60	0.9	16.8	8.00	1.0	1.00	2.0	…	…	…	…	…	…	…	…

All dimensions are in millimeters. Size –1 is available in beryllium copper only.

These rings are designated by series symbol and shaft diameter, thus: for a 2 mm diameter shaft, 3CM1-2; for a 13 mm shaft, 3CMI -13; etc.

Ring Free Diameter Tolerances: For ring sizes – 1 through –7, +0.03, –0.08 mm; for sizes –8 through –13, +0.05, –0.10 mm; and for sizes –15 through –25, +0.10, –0.15 mm.

Groove Diameter Tolerances: For ring sizes –1 and –2, –0.05 mm; for sizes –3 through –6, –0.08; for sizes –7 through –11, –0.10 mm; for sizes –12 through –18, – 0.15 mm; and for sizes –20 through –25, – 0.20 mm.

Groove Diameter F.I.M. (Full Indicator Movement) or maximum allowable deviation of concentricity between groove and shaft: For ring sizes –1 through –3, 0.04 mm; for –4 through –6, 0.05 mm; for –7 through –10, 0.08 mm; for –11 through –25, 0.10 mm.

Groove Width Tolerances: For ring sizes – 1 and –2, +0.05 mm; for size –3, +0.10 mm; and for sizes –4 through – 25, +0.15 mm.

Groove Maximum Bottom Radii: For ring sizes –1 and –2, 0.05 mm; for –3 through –7, 0.15 mm; for –8 through –13, 0.25 mm; and for –15 through –25, 0.4 mm.

For manufacturing details not shown, including materials, see ANSI B27.7-1977, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY



Ring Expanded over Shaft



Ring Seated in Groove

Table 4. American National Standard Metric Basic External Series 3AM1 Retaining Rings, Checking and Performance Data *ANSI B27.7-1977, R1993*

Ring Series and Size No.	Clearance Dia.		Gaging Diameter[a]	Allowable Thrust Loads Sharp Corner Abutment		Maximum Allowable Corner Radii and Chamfers		Allowable Assembly Speed[b]
	Ring Over Shaft	Ring in Groove						
3AM1	C_1	C_2	K max	P_r[c]	P_g[d]	R max	Ch max	…
No.	mm	mm	mm	kN	kN	mm	mm	rpm
–4[a]	7.0	6.8	4.90	0.6	0.2	0.35	0.25	70 000
–5[a]	8.2	7.9	5.85	1.1	0.3	0.35	0.25	70 000
–6[a]	9.1	8.8	6.95	1.4	0.4	0.35	0.25	70 000
–7	12.3	11.8	8.05	2.6	0.7	0.45	0.3	60 000
–8	13.6	13.0	9.15	3.1	1.0	0.5	0.35	55 000
–9	14.5	13.8	10.35	3.5	1.2	0.6	0.35	48 000
–10	15.5	14.7	11.50	3.9	1.5	0.7	0.4	42 000
–11	16.4	15.6	12.60	4.3	1.8	0.75	0.45	38 000
–12	17.4	16.6	13.80	4.7	2.0	0.8	0.45	34 000
–13	19.7	18.8	15.05	7.5	2.2	0.8	0.5	31 000
–14	20.7	19.7	15.60	8.1	2.6	0.9	0.5	28 000
–15	21.7	20.6	17.20	8.7	3.2	1.0	0.6	27 000
–16	22.7	21.6	18.35	9.3	3.5	1.1	0.6	25 000
–17	23.7	22.6	19.35	9.9	4.0	1.1	0.6	24 000
–18	26.2	25.0	20.60	16.0	4.4	1.2	0.7	23 000
–19	27.2	25.9	21.70	16.9	4.9	1.2	0.7	21 500
–20	28.2	26.8	22.65	17.8	5.7	1.2	0.7	20 000
–21	29.2	27.7	23.80	18.6	6.2	1.3	0.7	19 000
–22	30.3	28.7	24.90	19.6	7.0	1.3	0.8	18 500
–23	31.3	29.6	26.00	20.5	7.6	1.3	0.8	18 000
–24	34.1	32.4	27.15	21.4	8.2	1.4	0.8	17 500
–25	35.1	33.3	28.10	22.3	9.2	1.4	0.8	17 000
–26	36.0	34.2	29.25	23.2	9.6	1.5	0.9	16 500
–27	37.8	35.9	30.35	28.4	10.3	1.5	0.9	16 300
–28	38.8	36.9	31.45	28.4	11.0	1.6	1.0	15 800
–30	40.8	38.8	33.6	31.6	12.3	1.6	1.0	15 000
–32	42.8	40.7	35.9	33.6	14.1	1.7	1.0	14 800
–34	44.9	42.5	37.9	36	16.7	1.7	1.1	14 000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **American National Standard Metric Basic External Series 3AM1 Retaining Rings, Checking and Performance Data** *ANSI B27.7-1977, R1993*

Ring Series and Size No.	Clearance Dia.		Gaging Diameter[a]	Allowable Thrust Loads Sharp Corner Abutment		Maximum Allowable Corner Radii and Chamfers		Allowable Assembly Speed[b]
	Ring Over Shaft	Ring in Groove						
3AM1	C_1	C_2	K max	P_r[c]	P_g[d]	R max	Ch max	…
No.	mm	mm	mm	kN	kN	mm	mm	rpm
–35	45.9	43.4	39.0	37	18.1	1.8	1.1	13 500
–36	48.6	46.1	40.2	38	18.9	1.9	1.2	13 300
–38	50.6	48.0	42.5	40	20.5	2.0	1.2	12 700
–40	54.0	51.3	44.5	52	22.6	2.1	1.2	12 000
–42	56.0	53.2	46.9	54	24.8	2.2	1.3	11 000
–43	57.0	54.0	47.9	55	26.4	2.3	1.4	10 800
–45	59.0	55.9	50.0	58	28.8	2.3	1.4	10 000
–46	60.0	56.8	50.9	59	30.4	2.4	1.4	9 500
–48	62.4	59.1	53.0	62	33	2.4	1.4	8 800
–50	64.4	61.1	55.2	64	35	2.4	1.4	8 000
–52	67.6	64.1	57.4	84	37	2.5	1.5	7 700
–54	69.6	66.1	59.5	87	40	2.5	1.5	7 500
–55	70.6	66.9	60.4	89	44	2.5	1.5	7 400
–57	72.6	68.9	62.7	91	45	2.6	1.5	7 200
–58	73.6	69.8	63.6	93	46	2.6	1.6	7 100
–60	75.6	71.8	65.8	97	49	2.6	1.6	7 000
–62	77.6	73.6	67.9	100	52	2.7	1.6	6 900
–65	80.6	76.6	71.2	105	54	2.8	1.7	6 700
–68	83.6	79.5	74.5	110	58	2.9	1.7	6 500
–70	88.1	83.9	76.4	136	62	2.9	1.7	6 400
–72	90.1	85.8	78.5	140	65	2.9	1.7	6 200
–75	93.1	88.7	81.7	147	69	3.0	1.8	5 900
–78	95.4	92.1	84.6	151	76	3.0	1.8	5 600
–80	97.9	93.1	87.0	155	80	3.1	1.9	5 400
–82	100.0	95.1	89.0	159	84	3.2	1.9	5 200
–85	103.0	97.9	92.1	165	91	3.2	1.9	5 000
–88	107.0	100.8	95.1	199	97	3.2	1.9	4 800
–90	109.0	103.6	97.1	204	101	3.2	1.9	4 500
–95	114.0	108.6	102.7	215	112	3.4	2.1	4 350
–100	119.5	113.7	108.0	227	123	3.5	2.1	4 150

[a] For checking when ring is seated in groove.

[b] These values have been calculated for steel rings.

[c] These values apply to rings made from SAE 1060–1090 steels and PH 15-7 Mo stainless steel used on shafts hardened to R_c 50 minimum, with the exception of sizes –4, –5, and –6 which are supplied in beryllium copper only. Values for other sizes made from beryllium copper can be calculated by multiplying the listed values by 0.75. The values listed include a safety factor of 4.

[d] These values are for all standard rings used on low carbon steel shafts. They include a safety factor of 2.

Maximum allowable assembly loads with R max or Ch max are: For rings sizes –4, 0.2 kN; for sizes –5 and –6, 0.5 kN; for sizes –7 through –12, 2.1 kN; for sizes –13 through –17, 4.0 kN; for sizes –18 through –26, 6.0 kN; for sizes –27 through –38, 8.6 kN; for sizes –40 through – 50, 13.2 kN; for sizes –52 through –68, 22.0 kN; for sizes –70 through –85, 32 kN; and for sizes –88 through –100, 47 kN.

Source: Appendix to American National Standard ANSI B27.7-1977, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Metric Basic Internal Series 3BMI Retaining Rings — Checking and Performance Data *ANSI B27.7-1977, R1993*



Ring Compressed in Bore



Ring Seated in Groove

Max Allowable Radius of Retained Part



Max Allowable Chamfer of Retained Part

Ring Series and Size No.	Clearance Dia.		Gaging Diameter[a]	Allowable Thrust Loads Sharp Corner Abutment		Maximum Allowable Corner Radii and Chamfers	
	Ring in Bore	Ring in Groove					
3BMI	C_1	C_2	A min	P_r[b]	P_g[c]	R max	Ch max
No.	mm	mm	mm	kN	kN	mm	mm
–8	4.4	4.8	1.40	2.4	1.0	0.4	0.3
–9	4.6	5.0	1.50	4.4	1.2	0.5	0.35
–10	5.5	6.0	1.85	4.9	1.5	0.5	0.35
–11	5.7	6.3	1.95	5.4	2.0	0.6	0.4
–12	6.7	7.3	2.25	5.8	2.4	0.6	0.4
–13	6.8	7.5	2.35	8.9	2.6	0.7	0.5
–14	6.9	7.7	2.65	9.7	3.2	0.7	0.5
–15	7.9	8.7	2.80	10.4	3.7	0.7	0.5
–16	8.8	9.7	2.80	11.0	4.2	0.7	0.5
–17	9.8	10.8	3.35	11.7	4.9	0.75	0.6
–18	10.3	11.3	3.40	12.3	5.5	0.75	0.6
–19	11.4	12.5	3.40	13.1	6.0	0.8	0.65
–20	11.6	12.7	3.8	13.7	6.6	0.9	0.7
–21	12.6	13.8	4.2	14.5	7.3	0.9	0.7
–22	13.5	14.8	4.3	22.5	8.3	0.9	0.7
–23	14.5	15.9	4.9	23.5	8.9	1.0	0.8
–24	15.5	16.9	5.2	24.8	9.7	1.0	0.8
–25	16.5	18.1	6.0	25.7	11.6	1.0	0.8
–26	17.5	19.2	5.7	26.8	12.7	1.2	1.0
–27	17.4	19.2	5.9	33	14.0	1.2	1.0
–28	18.2	20.0	6.0	34	14.6	1.2	1.0
–30	20.0	21.9	6.0	37	16.5	1.2	1.0
–32	22.0	23.9	7.3	39	17.6	1.2	1.0
–34	24.0	26.1	7.6	42	20.6	1.2	1.0
–35	25.0	27.2	8.0	43	22.3	1.2	1.0
–36	26.0	28.3	8.3	44	23.9	1.2	1.0
–37	27.0	29.3	8.4	45	24.6	1.2	1.0
–38	28.0	30.4	8.6	46	26.4	1.2	1.0
–40	29.2	31.6	9.7	62	27.7	1.7	1.3
–42	29.7	32.2	9.0	65	30.2	1.7	1.3
–45	32.3	34.9	9.6	69	33.8	1.7	1.3
–46	33.3	36.0	9.7	71	36	1.7	1.3
–47	34.3	37.1	10.0	72	38	1.7	1.3
–48	35.0	37.9	10.5	74	40	1.7	1.3
–50	36.9	40.0	12.1	77	45	1.7	1.3
–52	38.6	41.9	11.7	99	50	2.0	1.6
–55	40.8	44.2	11.9	105	54	2.0	1.6
–57	42.2	45.7	12.5	109	58	2.0	1.6

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **American National Standard Metric Basic Internal Series 3BMI**

–58	43.2	46.8	13.0	111	60	2.0	1.6
–60	45.5	49.3	12.7	115	66	2.0	1.6
–62	47.0	50.8	14.0	119	68	2.0	1.6
–63	47.8	51.7	14.2	120	71	2.0	1.6
–65	49.4	53.4	14.2	149	75	2.0	1.6
–68	52.0	56.2	14.4	156	82	2.3	1.8
–70	53.8	58.2	16.1	161	88	2.3	1.8
–72	55.9	60.4	17.4	166	93	2.3	1.8
–75	58.2	62.9	16.8	172	101	2.3	1.8
–78	61.2	66.0	17.6	209	108	2.5	2.0
–80	63.0	68.0	17.2	215	115	2.5	2.0
–82	63.5	68.7	18.8	220	122	2.6	2.1
–85	66.8	72.2	19.1	228	131	2.6	2.1
–88	69.6	75.2	20.4	236	141	2.8	2.2
–90	71.6	77.3	21.4	241	147	2.8	2.2
–92	73.6	79.4	22.2	247	153	2.9	2.4
–95	76.7	82.7	22.6	255	164	3.0	2.5
–98	78.3	84.5	22.6	263	174	3.0	2.5
–100	80.3	86.6	24.1	269	181	3.1	2.5
–102	82.2	88.6	25.5	273	187	3.2	2.6
–105	85.1	91.6	26.0	281	196	3.3	2.6
–108	88.1	94.7	26.4	290	205	3.5	2.7
–110	88.4	95.1	27.5	295	212	3.6	2.8
–115	93.2	100.1	29.4	309	227	3.7	2.9
–120	98.2	105.2	27.2	321	241	3.9	3.1
–125	103.1	110.2	30.3	335	255	4.0	3.2
–130	108.0	115.2	31.0	349	269	4.0	3.2
–135	110.4	117.7	30.4	415	283	4.3	3.4
–140	115.3	122.7	30.4	429	298	4.3	3.4
–145	120.4	127.9	31.6	444	313	4.3	3.4
–150	125.3	132.9	33.5	460	327	4.3	3.4
–155	130.4	138.1	37.0	475	343	4.3	3.4
–160	133.8	141.6	35.0	613	359	4.5	3.6
–165	138.7	146.6	33.1	632	374	4.6	3.7
–170	143.6	151.6	38.2	651	390	4.6	3.7
–175	146.0	154.2	37.7	670	403	4.8	3.8
–180	151.4	159.8	39.0	690	434	5.0	4.0
–185	154.7	163.3	37.3	851	457	5.1	4.1
–190	159.5	168.3	35.0	873	480	5.3	4.3
–200	169.2	178.2	43.9	919	517	5.4	4.3
–210	177.5	186.9	40.6	965	566	5.8	4.6
–220	184.1	194.1	38.3	1000	608	6.1	4.9
–230	194.0	204.6	49.0	1060	686	6.3	5.1
–240	200.4	211.4	45.4	1090	725	6.6	5.3
–250	210.0	221.4	53.0	1150	808	6.7	5.4

[a] For checking when ring is seated in groove.

[b] These values apply to rings made from SAE 1060-1090 steels and PH 15-7 Mo stainless steel used in bores hardened to R_c 50 minimum. Values for rings made from beryllium copper can be calculated by multiplying the listed values by 0.75. The values listed include a safety factor of 4.

[c] These values are for standard rings used in low carbon steel bores. They include a safety factor of 2. Maximum allowable assembly loads for *R* max or *Ch* max are: For ring size –8, 0.8 kN; for sizes –9 through –12, 2.0 kN; for sizes –13 through –21, 4.0 kN; for sizes –22 through –26, 7.4 kN; for sizes –27 through –38, 10.8 kN; for sizes –40 through –50, 17.4 kN; for sizes –52 through –63, 27.4 kN; for size –65, 42.0 kN; for sizes –68 through –72, 39 kN; for sizes –75 through –130, 54 kN; for sizes –135 through –155, 67 kN; for sizes –160 through –180, 102 kN; and for sizes –185 through –250, 151 kN.

Source: Appendix to American National Standard ANSI B27.7-1977, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Metric E-Type External Series 3CM1 Retaining Rings — Checking and Performance Data *ANSI B27.7-1977, R1993*



Ring Seated in Groove

Max. Allowable Radius of Retained Part



Max. Allowable Chamfer of Retained Part

Ring Series and Size No.	Clearance Diameter Ring in Groove	Allowable Thrust Loads Sharp Corner Abutment		Maximum Allowable Corner Radii and Chamfers		Allowable Assembly Speed[a]
3CM1	C_2	P_t[b]	P_g[c]	R max	Ch max	…
No.	mm	kN	kN	mm	mm	rpm
–1	2.2	0.06	0.02	0.4	0.25	40 000
–2	4.3	0.13	0.09	0.8	0.5	40 000
–3	6.0	0.3	0.17	1.1	0.7	34 000
–4	7.6	0.7	0.3	1.6	1.2	31 000
–5	8.9	0.9	0.4	1.6	1.2	27 000
–6	11.5	1.1	0.6	1.6	1.2	25 000
–7	14.0	1.2	0.8	1.6	1.2	23 000
–8	15.1	1.4	1.0	1.7	1.3	21 500
–9	16.5	3.0	1.3	1.7	1.3	19 500
–10	17.5	3.4	1.6	1.7	1.3	18 000
–11	18.0	3.7	1.9	1.7	1.3	16 500
–12	19.3	4.9	2.3	1.9	1.4	15 000
–13	21.0	5.4	2.9	2.0	1.5	13 000
–15	23.5	6.2	4.0	2.0	1.5	11 500
–16	24.5	6.6	4.5	2.0	1.5	10 000
–18	27.9	8.7	5.4	2.1	1.6	9 000
–20	30.7	9.8	6.5	2.2	1.7	8 000
–22	33.7	10.8	8.1	2.2	1.7	7 000
–25	37.9	12.2	10.1	2.4	1.9	5 000

[a] These values have been calculated for steel rings.

[b] These values apply to rings made from SAE 1060-1090 steels and PH 15-7 Mo stainless steel used on shafts hardened to R_c 50 minimum, with the exception of size –1 which is supplied in beryllium copper only. Values for other sizes made from beryllium copper can be calculated by multiplying the listed values by 0.75. The values listed include a safety factor of 4.

[c] These values apply to all standard rings used on low carbon steel shafts. They include a safety factor of 2.

Maximum allowable assembly loads with R max or Ch max are as follows:

Ring Size No.	Maximum Allowable Load,kN	Ring Size No.	Maximum AllowableLoad, kN	Ring Size No.	Maximum AllowableLoad, kN
–1	0.06	–8	1.4	–16	6.6
–2	0.13	–9	3.0	–18	8.7
–3	0.3	–10	3.4	–20	9.8
–4	0.7	–11	3.7	–22	10.8
–5	0.9	–12	4.9	–25	12.2
–6	1.1	–13	5.4	…	…
–7	1.2	–15	6.2	…	…

Source: Appendix to American National Standard ANSI B27.7-1977, R1993.

Copyright 2004, Industrial Press, Inc., New York, NY



Table 7. Medium Duty Internal Spiral Retaining Rings *MIL-R-27426*

Bore Dia. A	Ring		Groove		Static Thrust Load (lb)		Bore Dia. A	Ring		Groove		Static Thrust Load (lb)	
	Dia. G	Wall E	Dia. C	Width D	Ring	Groove		Dia. G	Wall E	Dia. C	Width D	Ring	Groove
0.500	0.532	0.045	0.526	0.030	2000	405	3.437	3.574	0.188	3.543	0.068	27660	18240
0.512	0.544	0.045	0.538	0.030	2050	420	3.500	3.636	0.188	3.606	0.068	28170	18575
0.531	0.564	0.045	0.557	0.030	2130	455	3.543	3.684	0.198	3.653	0.068	28520	19515
0.562	0.594	0.045	0.588	0.030	2250	495	3.562	3.703	0.198	3.672	0.068	28670	19620
0.594	0.626	0.045	0.619	0.030	2380	535	3.625	3.769	0.198	3.737	0.068	29180	20330
0.625	0.658	0.045	0.651	0.030	2500	610	3.687	3.832	0.198	3.799	0.068	29680	20675
0.656	0.689	0.045	0.682	0.030	2630	670	3.740	3.885	0.198	3.852	0.068	30100	20975
0.687	0.720	0.045	0.713	0.030	2750	725	3.750	3.894	0.198	3.862	0.068	30180	21030
0.718	0.751	0.045	0.744	0.030	2870	790	3.812	3.963	0.208	3.930	0.068	30680	22525
0.750	0.790	0.065	0.782	0.036	3360	800	4.437	4.611	0.238	4.573	0.068	35710	30215
0.777	0.817	0.065	0.808	0.036	3480	835	4.500	4.674	0.238	4.636	0.068	36220	30645
0.781	0.821	0.065	0.812	0.036	3500	840	4.527	4.701	0.238	4.663	0.068	36440	30830
0.812	0.853	0.065	0.843	0.036	3640	915	4.562	4.737	0.238	4.698	0.079	36720	31065
0.843	0.889	0.065	0.880	0.036	3780	1155	4.625	4.803	0.250	4.765	0.079	43940	32420
0.866	0.913	0.065	0.903	0.036	3880	1250	4.687	4.867	0.250	4.827	0.079	44530	32855
0.875	0.922	0.065	0.912	0.036	3920	1250	4.724	4.903	0.250	4.864	0.079	44880	33115
0.906	0.949	0.065	0.939	0.036	4060	1335	4.750	4.930	0.250	4.890	0.079	45130	33300
0.938	0.986	0.065	0.975	0.036	4200	1430	4.812	4.993	0.250	4.952	0.079	45710	33735
0.968	1.025	0.075	1.015	0.042	4340	1950	4.875	5.055	0.250	5.015	0.079	46310	34175
0.987	1.041	0.075	1.030	0.042	4420	1865	4.921	5.102	0.250	5.061	0.079	46750	34495
1.000	1.054	0.075	1.043	0.042	4480	1910	4.937	5.122	0.250	5.081	0.079	46900	35595
1.023	1.078	0.075	1.066	0.042	5470	1660	5.000	5.185	0.250	5.144	0.079	47500	36050
1.031	1.084	0.075	1.074	0.042	5510	1650	5.118	5.304	0.250	5.262	0.079	48620	36905
1.062	1.117	0.075	1.104	0.042	5680	1745	5.125	5.311	0.250	5.269	0.079	48690	36955
1.093	1.147	0.075	1.135	0.042	5840	1820	5.250	5.436	0.250	5.393	0.079	49880	37590
1.125	1.180	0.075	1.167	0.042	6010	1935	5.375	5.566	0.250	5.522	0.079	51050	39565
1.156	1.210	0.075	1.198	0.042	6180	2020	5.500	5.693	0.250	5.647	0.079	52250	40485
1.188	1.249	0.085	1.236	0.048	7380	2115	5.511	5.703	0.250	5.658	0.079	52350	40565
1.218	1.278	0.085	1.266	0.048	7570	2195	5.625	5.818	0.250	5.772	0.079	53440	41405
1.250	1.312	0.085	1.298	0.048	7770	2510	5.708	5.909	0.250	5.861	0.079	54230	43730
1.281	1.342	0.085	1.329	0.048	7960	2425	5.750	5.950	0.250	5.903	0.079	54630	44050
1.312	1.374	0.085	1.360	0.048	8150	2532	5.875	6.077	0.250	6.028	0.079	55810	45010
1.343	1.408	0.085	1.395	0.048	8340	2875	5.905	6.106	0.250	6.058	0.079	56100	45240
1.375	1.442	0.095	1.427	0.048	8540	3070	6.000	6.202	0.312	6.153	0.079	57000	45965
1.406	1.472	0.095	1.458	0.048	8740	3180	6.125	6.349	0.312	6.297	0.094	69500	52750
1.437	1.504	0.095	1.489	0.048	8930	3330	6.250	6.474	0.312	6.422	0.094	70920	53825
1.456	1.523	0.095	1.508	0.048	9050	3410	6.299	6.524	0.312	6.471	0.094	71480	54250
1.468	1.535	0.095	1.520	0.048	9120	3460	6.375	6.601	0.312	6.547	0.094	72340	54905
1.500	1.567	0.095	1.552	0.048	9320	3605	6.500	6.726	0.312	6.672	0.094	73760	55980
1.562	1.634	0.108	1.617	0.056	10100	3590	6.625	6.863	0.312	6.807	0.094	75180	60375
1.574	1.649	0.108	1.633	0.056	10180	3640	6.692	6.931	0.312	6.874	0.094	75940	60985
1.625	1.701	0.108	1.684	0.056	10510	3875	6.750	6.987	0.312	6.932	0.094	76590	61515
1.653	1.730	0.108	1.712	0.056	10690	4020	6.875	7.114	0.312	7.057	0.094	78010	62655
1.687	1.768	0.118	1.750	0.056	10910	4510	7.000	7.239	0.312	7.182	0.094	79430	63790
1.750	1.834	0.118	1.813	0.056	11310	4895	7.086	7.337	0.312	7.278	0.094	80410	68125
1.813	1.894	0.118	1.875	0.056	11720	5080	7.125	7.376	0.312	7.317	0.094	80850	68500

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. ***(Continued)*** **Medium Duty Internal Spiral Retaining Rings** *MIL-R-27426*

Bore Dia.	Ring		Groove		Static Thrust Load (lb)		Bore Dia.	Ring		Groove		Static Thrust Load (lb)	
A	Dia. G	Wall E	Dia. C	Width D	Ring	Groove	A	Dia. G	Wall E	Dia. C	Width D	Ring	Groove
1.850	1.937	0.118	1.917	0.056	11960	5735	7.250	7.501	0.312	7.442	0.094	82270	69700
1.875	1.960	0.118	1.942	0.056	12120	5825	7.375	7.628	0.312	7.567	0.094	83690	70900
1.938	2.025	0.118	2.005	0.056	12530	6250	7.480	7.734	0.312	7.672	0.094	84880	71910
2.000	2.091	0.128	2.071	0.056	12930	7090	7.500	7.754	0.312	7.692	0.094	85110	72105
2.047	2.138	0.128	2.118	0.056	13230	7275	7.625	7.890	0.312	7.827	0.094	86520	77125
2.062	2.154	0.128	2.132	0.056	13330	7225	7.750	8.014	0.312	7.952	0.094	87940	78390
2.125	2.217	0.128	2.195	0.056	13740	7450	7.875	8.131	0.312	8.077	0.094	89360	79655
2.165	2.260	0.138	2.239	0.056	14000	8020	8.000	8.266	0.312	8.202	0.094	90780	80920
2.188	2.284	0.138	2.262	0.056	14150	8105	8.250	8.528	0.375	8.462	0.094	93620	87575
2.250	2.347	0.138	2.324	0.056	14550	8335	8.267	8.546	0.375	8.479	0.094	93810	87755
2.312	2.413	0.138	2.390	0.056	14950	9030	8.464	8.744	0.375	8.676	0.094	96040	89850
2.375	2.476	0.138	2.453	0.056	15350	9275	8.500	8.780	0.375	8.712	0.094	96450	90230
2.437	2.543	0.148	2.519	0.056	15760	10005	8.750	9.041	0.375	8.972	0.094	99290	97265
2.440	2.546	0.148	2.522	0.056	15780	10015	8.858	9.151	0.375	9.080	0.094	100520	98465
2.500	2.606	0.148	2.582	0.056	16160	10625	9.000	9.293	0.375	9.222	0.094	102130	100045
2.531	2.641	0.148	2.617	0.056	16360	10900	9.055	9.359	0.375	9.287	0.094	102750	105190
2.562	2.673	0.148	2.648	0.056	16560	11030	9.250	9.555	0.375	9.482	0.094	104960	107455
2.625	2.736	0.148	2.711	0.056	16970	11305	9.448	9.755	0.375	9.680	0.094	107210	109755
2.677	2.789	0.158	2.767	0.056	17310	12065	9.500	9.806	0.375	9.732	0.094	107800	110360
2.688	2.803	0.158	2.778	0.056	17380	12115	9.750	10.068	0.375	9.992	0.094	110640	118145
2.750	2.865	0.158	2.841	0.056	17780	12530	10.000	10.320	0.375	10.242	0.094	113470	121175
2.813	2.929	0.158	2.903	0.056	18190	12675	10.250	10.582	0.375	10.502	0.094	116310	129340
2.834	2.954	0.168	2.928	0.056	18320	13340	10.500	10.834	0.375	10.752	0.094	119150	132490
2.875	2.995	0.168	2.969	0.056	18590	13530	10.750	11.095	0.375	11.012	0.094	121980	141030
2.937	3.058	0.168	3.031	0.056	18990	13825	11.000	11.347	0.375	11.262	0.094	124820	144310
2.952	3.073	0.168	3.046	0.056	19090	13890	3.875	4.025	0.208	3.993	0.068	30680	22525
3.000	3.122	0.168	3.096	0.068	24150	14420	3.938	4.089	0.208	4.056	0.068	31700	23265
3.062	3.186	0.168	3.158	0.068	24640	14720	4.000	4.157	0.218	5.124	0.068	32190	24835
3.125	3.251	0.178	3.223	0.068	25150	15335	4.063	4.222	0.218	4.187	0.068	32700	25225
3.149	3.276	0.178	3.247	0.068	25340	15450	4.125	4.284	0.218	4.249	0.068	33200	25610
3.187	3.311	0.178	3.283	0.068	25650	15640	4.188	4.347	0.218	4.311	0.068	33710	25795
3.250	3.379	0.178	3.350	0.068	26160	16270	4.250	4.416	0.228	4.380	0.068	34210	27665
3.312	3.446	0.188	3.416	0.068	26660	17245	4.312	4.479	0.228	4.442	0.068	34710	28065
3.346	3.479	0.188	3.450	0.068	26930	17425	4.330	4.497	0.228	4.460	0.068	34850	28185
3.375	3.509	0.188	3.479	0.068	27160	17575	4.375	4.543	0.228	4.505	0.068	32210	28475

Source: Spirolox Retaining Rings, RR Series. All dimensions are in inches. Depth of groove $d = (C - A)/2$. Standard material: carbon spring steel (SAE 1070-1090).

Ring Thickness, F: For shaft sizes 0.500 through 0.718, 0.025; for sizes 0.750 through 0.938, 0.031; for sizes 0.968 through 1.156, 0.037; for sizes 1.188 through 1.500, 0.043; for sizes 1.562 through 2.952, 0.049; for sizes 3.000 through 4.562, 0.061; for sizes 4.625 through 6.000, 0.072; for sizes 6.125 through 11.000, 0.086.

Ring Free Diameter Tolerances: For housing sizes 0.500 through 1.031, +0.013, –0.000; for sizes 1.062 through 1.500, +0.015, –0.000; for sizes 1.562 through 2.047, +0.020, –0.000; for sizes 2.062 through 3.000, +0.025, –0.000; for sizes 3.062 through 4.063, +0.030, –0.000; for sizes 4.125 through 5.125, +0.035, –0.000; for sizes 5.250 through 6.125, +0.045, –0.000; for sizes 6.250 through 7.125, +0.055, –0.000; for sizes 7.250 through 11.000, +0.065, –0.000.

Ring Thickness Tolerances: Thickness indicated is for unplated rings; add 0.002 to upper thickness tolerance for plated rings. For housing sizes 0.500 through 1.500, ±0.002; for sizes 1.562 through 4.562, ±0.003; for sizes 4.625 through 11.000, ±0.004.

Groove Diameter Tolerances: For housing sizes 0.500 through 0.750, ±0.002; for sizes 0.777 through 1.031, ±0.003; for sizes 1.062 through 1.500, ±0.004; for sizes 1.562 through 2.047, ±0.005; for sizes 2.062 through 5.125, ±0.006; for sizes 5.250 through 6.000, ±0.007; for sizes 6.125 through 11.000, ±0.008.

Groove Width Tolerances: For housing sizes 0.500 through 1.156, +0.003, –0.000; for sizes 1.188 through 2.952, +0.004, –0.000; for sizes 3.000 through 6.000, +0.005, –0.000; for sizes 6.125 through 11.000, +0.006, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Medium Duty External Spiral Retaining Rings *MIL-R-27426*



Shaft Dia.	Ring		Groove		Static Thrust Load (lb)		Shaft Dia.	Ring		Groove		Static Thrust Load (lb)	
	Dia.	Wall	Dia.	Width				Dia.	Wall	Dia.	Width		
A	G	E	C	D	Ring	Groove	A	G	E	C	D	Ring	Groove
0.500	0.467	0.045	0.474	0.030	2000	550	3.343	3.210	0.188	3.239	0.068	26910	17410
0.531	0.498	0.045	0.505	0.030	2130	640	3.375	3.242	0.188	3.271	0.068	27160	17570
0.551	0.518	0.045	0.525	0.030	2210	700	3.437	3.301	0.188	3.331	0.068	27660	18240
0.562	0.529	0.045	0.536	0.030	2250	730	3.500	3.363	0.188	3.394	0.068	28170	18580
0.594	0.561	0.045	0.569	0.030	2380	740	3.543	3.402	0.198	3.433	0.068	28520	19510
0.625	0.585	0.055	0.594	0.030	2500	970	3.562	3.422	0.198	3.452	0.068	28670	19620
0.656	0.617	0.055	0.625	0.030	2630	1020	3.625	3.483	0.198	3.515	0.068	29180	19970
0.669	0.629	0.055	0.638	0.030	2680	1040	3.687	3.543	0.198	3.575	0.068	29680	20680
0.687	0.647	0.055	0.656	0.030	2750	1060	3.740	3.597	0.198	3.628	0.068	30100	20970
0.718	0.679	0.055	0.687	0.030	2870	1110	3.750	3.606	0.198	3.638	0.068	30180	21030
0.750	0.710	0.065	0.719	0.036	3360	1100	3.812	3.668	0.198	3.700	0.068	30680	21380
0.781	0.741	0.065	0.750	0.036	3500	1210	3.875	3.724	0.208	3.757	0.068	31190	22890
0.812	0.771	0.065	0.781	0.036	3640	1260	3.938	3.784	0.208	3.820	0.068	31700	23270
0.843	0.803	0.065	0.812	0.036	3780	1310	4.000	3.842	0.218	3.876	0.068	32190	24840
0.875	0.828	0.065	0.838	0.036	3920	1620	4.063	3.906	0.218	3.939	0.068	32700	25230
0.906	0.860	0.065	0.869	0.036	4060	1680	4.125	3.967	0.218	4.000	0.068	33200	25820
0.937	0.889	0.065	0.900	0.036	4200	1740	4.134	3.975	0.218	4.010	0.068	33270	25670
0.968	0.916	0.075	0.925	0.042	5180	2080	4.188	4.030	0.218	4.058	0.068	33710	27260
0.984	0.930	0.075	0.941	0.042	5260	2120	4.250	4.084	0.228	4.120	0.068	34210	27660
1.000	0.946	0.075	0.957	0.042	5350	2150	4.312	4.147	0.218	4.182	0.068	34710	28070
1.023	0.968	0.075	0.980	0.042	5470	2200	4.331	4.164	0.218	4.200	0.068	34860	28410
1.031	0.978	0.075	0.988	0.042	5510	2220	4.375	4.208	0.218	4.245	0.068	35210	28480
1.062	1.007	0.075	1.020	0.042	5680	2230	4.437	4.271	0.218	4.307	0.068	35710	28880
1.093	1.040	0.075	1.051	0.042	5840	2300	4.500	4.326	0.238	4.364	0.068	36220	30640
1.125	1.070	0.075	1.083	0.042	6010	2370	4.562	4.384	0.250	4.422	0.079	43340	31980
1.156	1.102	0.075	1.114	0.042	6180	2430	4.625	4.447	0.250	4.485	0.079	43940	32420
1.188	1.127	0.085	1.140	0.048	7380	2850	4.687	4.508	0.250	4.457	0.079	44530	32860
1.218	1.159	0.085	1.170	0.048	7570	2930	4.724	4.546	0.250	4.584	0.079	44880	33120
1.250	1.188	0.085	1.202	0.048	7770	3000	4.750	4.571	0.250	4.610	0.079	45130	33300
1.281	1.221	0.085	1.233	0.048	7960	3080	4.812	4.633	0.250	4.672	0.079	45710	33730
1.312	1.251	0.095	1.264	0.048	8150	3150	4.875	4.695	0.250	4.735	0.079	46310	34170
1.343	1.282	0.095	1.295	0.048	8340	3230	4.937	4.757	0.250	4.797	0.079	46900	34610
1.375	1.308	0.095	1.323	0.048	8540	3580	5.000	4.820	0.250	4.856	0.079	47500	36050
1.406	1.340	0.095	1.354	0.048	8740	3660	5.118	4.934	0.250	4.974	0.079	48620	36900
1.437	1.370	0.095	1.385	0.048	8930	3740	5.125	4.939	0.250	4.981	0.079	48690	36950
1.468	1.402	0.095	1.416	0.048	9120	3820	5.250	5.064	0.250	5.107	0.079	49880	37590
1.500	1.433	0.095	1.448	0.048	9320	3910	5.375	5.187	0.250	5.228	0.079	51060	39560
1.562	1.490	0.108	1.507	0.056	10100	4300	5.500	5.308	0.250	5.353	0.079	52250	40480
1.575	1.503	0.108	1.520	0.056	10190	4340	5.511	5.320	0.250	5.364	0.079	52350	40560
1.625	1.549	0.108	1.566	0.056	10510	4800	5.625	5.433	0.250	5.478	0.079	53440	41400

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. ***(Continued)*** **Medium Duty External Spiral Retaining Rings** *MIL-R-27426*

1.687	1.610	0.118	1.628	0.056	10910	4980	5.750	5.550	0.250	5.597	0.079	54630	44050
1.750	1.673	0.118	1.691	0.056	11310	5170	5.875	5.674	0.250	5.722	0.079	55810	45010
1.771	1.690	0.118	1.708	0.056	11450	5590	5.905	5.705	0.250	5.752	0.079	56100	45240
1.813	1.730	0.118	1.749	0.056	11720	5810	6.000	5.798	0.250	5.847	0.079	57000	45970
1.875	1.789	0.128	1.808	0.056	12120	6290	6.125	5.903	0.312	5.953	0.094	69500	52750
1.938	1.844	0.128	1.861	0.056	12530	7470	6.250	6.026	0.312	6.078	0.094	70920	53830
1.969	1.882	0.128	1.902	0.056	12730	6610	6.299	6.076	0.312	6.127	0.094	71480	54250
2.000	1.909	0.128	1.992	0.056	12930	7110	6.375	6.152	0.312	6.203	0.094	72340	54900
2.062	1.971	0.128	2.051	0.056	13330	7870	6.500	6.274	0.312	6.328	0.094	73760	55980
2.125	2.029	0.128	2.082	0.056	13740	7990	6.625	6.390	0.312	6.443	0.094	75180	60380
2.156	2.060	0.138	2.091	0.056	13940	8020	6.750	6.513	0.312	6.568	0.094	76590	61515
2.188	2.070	0.138	2.113	0.056	14150	8220	6.875	6.638	0.312	6.693	0.094	78010	62650
2.250	2.092	0.138	2.176	0.056	14550	8340	7.000	6.761	0.312	6.818	0.094	79430	63790
2.312	2.153	0.138	2.234	0.056	14950	9030	7.125	6.877	0.312	6.933	0.094	80850	68500
2.362	2.211	0.138	2.284	0.056	15270	9230	7.250	6.999	0.312	7.058	0.094	82270	69700
2.375	2.273	0.138	2.297	0.056	15350	9280	7.375	7.125	0.312	7.183	0.094	83690	70900
2.437	2.331	0.148	2.355	0.056	15760	10000	7.500	7.250	0.312	7.308	0.094	85110	72100
2.500	2.394	0.148	2.418	0.056	16160	10260	7.625	7.363	0.312	7.423	0.094	86520	77120
2.559	2.449	0.148	2.473	0.056	16540	11020	7.750	7.486	0.312	7.548	0.094	87940	78390
2.562	2.452	0.148	2.476	0.056	16560	11030	7.875	7.611	0.312	7.673	0.094	89360	79650
2.625	2.514	0.148	2.539	0.056	16970	11300	8.000	7.734	0.312	7.798	0.094	90780	80920
2.688	2.572	0.158	2.597	0.056	17380	12250	8.250	7.972	0.375	8.038	0.094	93620	87580
2.750	2.635	0.158	2.660	0.056	17780	12390	8.500	8.220	0.375	8.288	0.094	96450	90230
2.813	2.696	0.168	2.722	0.056	18190	12820	8.750	8.459	0.375	8.528	0.094	99290	97270
2.875	2.755	0.168	2.781	0.056	18590	13530	9.000	8.707	0.375	8.778	0.094	102130	100050
2.937	2.817	0.168	2.843	0.056	18990	13820	9.250	8.945	0.375	9.018	0.094	104960	107560
2.952	2.831	0.168	2.858	0.056	19090	13890	9.500	9.194	0.375	9.268	0.094	107800	110360
3.000	2.877	0.168	2.904	0.068	24150	14420	9.750	9.432	0.375	9.508	0.094	110640	118150
3.062	2.938	0.168	2.966	0.068	24640	14720	10.000	9.680	0.375	9.758	0.094	113470	121180
3.125	3.000	0.178	3.027	0.068	25150	15335	10.250	9.918	0.375	9.998	0.094	116310	129340
3.149	3.023	0.178	3.051	0.068	25340	15450	10.500	10.166	0.375	10.248	0.094	119150	132490
3.187	3.061	0.178	3.089	0.068	25650	15640	10.750	10.405	0.375	10.488	0.094	121980	141030
3.250	3.121	0.178	3.150	0.068	26160	16270	11.000	10.653	0.375	10.738	0.094	124820	144310
3.312	3.180	0.188	3.208	0.068	26660	17250							

Source: Spirolox Retaining Rings, RS Series. All dimensions are in inches. Depth of groove $d = (A - C)/2$. Standard material: carbon spring steel (SAE 1070–1090).

Ring Thickness, F: For shaft sizes 0.500 through 0.718, 0.025; for sizes 0.750 through 0.937, 0.031; for sizes 0.968 through 1.156, 0.037; for sizes 1.188 through 1.500, 0.043; for sizes 1.562 through 2.952, 0.049; for sizes 3.000 through 4.500, 0.061; for sizes 4.562 through 6.000, 0.072; for sizes 6.125 through 11.000, 0.086.

Ring Free Diameter Tolerances: For shaft sizes 0.500 through 1.031, +0.000, + 0.000, –0.013; for sizes 1.062 through 1.500, +0.000, –0.015; for sizes 1.562 through 2.125, +0.000, –0.020; for sizes 2.156 through 2.688, +0.000, –0.025; for sizes 2.750 through 3.437, +0.000, –0.030; for sizes 3.500 through 5.125, +0.000, –0.040; for sizes 5.250 through 6.125, +0.000, –0.050; for sizes 6.250 through 7.375, +0.000, –0.060; for sizes 7.500 through 11.000, +0.000, –0.070.

Ring Thickness Tolerances: Thickness indicated is for unplated rings; add 0.002 to upper tolerance for plated rings. For shaft sizes 0.500 through 1.500, ± 0.002; for sizes 1.562 through 4.500, ± 0.003; for sizes 4.562 through 11.000, ± 0.004.

Groove Diameter Tolerances: For shaft sizes 0.500 through 0.562, ±0.002; for sizes 0.594 through 1.031, ± 0.003; for sizes 1.062 through 1.500, ± 0.004; for sizes 1.562 through 2.000, ± 0.005; for sizes 2.062 through 5.125, ±0.006; for sizes 5.250 through 6.000, ± 0.007; for sizes 6.125 through 11.000, ± 0.008.

Groove Width Tolerances: For shaft sizes 0.500 through 1.156, +0.003, –0.000; for sizes 1.188 through 2.952, +0.004, –0.000; for sizes 3.000 through 6.000, +0.005, –0.000; for sizes 6.125 through 11.000, +0.006, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY



Table 9. Heavy Duty Internal Spiral Retaining Rings *MIL-R-27426*

Bore Dia. A	Ring		Groove		Static Thrust Load (lb)		Bore Dia. A	Ring		Groove		Static Thrust Load (lb)	
	Dia. G	Wall E	Dia. C	Width D	Ring	Groove		Dia. G	Wall E	Dia. C	Width D	Ring	Groove
0.500	0.538	0.045	0.530	0.039	2530	310	3.543	3.781	0.281	3.755	0.120	49420	28250
0.512	0.550	0.045	0.542	0.039	2590	325	3.562	3.802	0.281	3.776	0.120	49680	28815
0.562	0.605	0.055	0.596	0.039	2840	455	3.625	3.868	0.281	3.841	0.120	50560	30160
0.625	0.675	0.055	0.655	0.039	3160	655	3.750	4.002	0.312	3.974	0.120	52310	33720
0.688	0.743	0.065	0.732	0.039	3480	965	3.875	4.136	0.312	4.107	0.120	54050	37250
0.750	0.807	0.065	0.796	0.039	3790	1065	3.938	4.203	0.312	4.174	0.120	54930	39045
0.777	0.836	0.075	0.825	0.046	4720	1026	4.000	4.270	0.312	4.240	0.120	55790	41025
0.812	0.873	0.075	0.862	0.046	4930	1150	4.125	4.369	0.312	4.339	0.120	57540	38495
0.866	0.931	0.075	0.920	0.046	5260	1395	4.250	4.501	0.312	4.470	0.120	59280	41955
0.875	0.943	0.085	0.931	0.046	5310	1520	4.330	4.588	0.312	4.556	0.120	60400	44815
0.901	0.972	0.085	0.959	0.046	5470	1675	4.500	4.768	0.312	4.735	0.120	62770	50290
0.938	1.013	0.085	1.000	0.046	5690	1925	4.625	4.899	0.312	4.865	0.120	64510	54155
1.000	1.080	0.085	1.066	0.046	6070	2310	4.750	5.030	0.312	4.995	0.120	66260	58270
1.023	1.105	0.085	1.091	0.046	6210	2480	5.000	5.297	0.312	5.260	0.120	69740	65095
1.062	1.138	0.103	1.130	0.056	7010	1940	5.250	5.559	0.350	5.520	0.139	83790	68315
1.125	1.205	0.103	1.197	0.056	7420	2280	5.375	5.690	0.350	5.650	0.139	85780	72840
1.188	1.271	0.103	1.262	0.056	7840	2615	5.500	5.810	0.350	5.770	0.139	87780	74355
1.250	1.339	0.103	1.330	0.056	8250	3110	5.750	6.062	0.350	6.020	0.139	91770	77735
1.312	1.406	0.118	1.396	0.056	8650	3650	6.000	6.314	0.350	6.270	0.139	95760	81120
1.375	1.471	0.118	1.461	0.056	9070	4075	6.250	6.576	0.380	6.530	0.174	122520	80655
1.439	1.539	0.118	1.528	0.056	9490	4670	6.500	6.838	0.380	6.790	0.174	127420	90295
1.456	1.559	0.118	1.548	0.056	9600	4890	6.625	6.974	0.380	6.925	0.174	129870	92060
1.500	1.605	0.118	1.594	0.056	9900	5275	6.750	7.105	0.380	7.055	0.174	132320	102475
1.562	1.675	0.128	1.658	0.068	12780	4840	7.000	7.366	0.380	7.315	0.174	137220	110410
1.625	1.742	0.128	1.725	0.068	13290	5415	7.250	7.628	0.418	7.575	0.209	170370	103440
1.653	1.772	0.128	1.755	0.068	13520	5695	7.500	7.895	0.418	7.840	0.209	176240	115780
1.688	1.810	0.128	1.792	0.068	13810	6070	7.750	8.157	0.418	8.100	0.209	182120	127270
1.750	1.876	0.128	1.858	0.068	14320	7635	8.000	8.419	0.418	8.360	0.209	187990	139370
1.812	1.940	0.128	1.922	0.068	14820	7305	8.250	8.680	0.437	8.620	0.209	193870	152695
1.850	1.981	0.158	1.962	0.068	15130	7960	8.500	8.942	0.437	8.880	0.209	199740	161735
1.875	2.008	0.158	1.989	0.068	15340	8305	8.750	9.209	0.437	9.145	0.209	205620	173065
1.938	2.075	0.158	2.056	0.068	15850	9125	9.000	9.471	0.437	9.405	0.209	211490	182515
2.000	2.142	0.158	2.122	0.068	16360	10040	9.250	9.737	0.437	9.669	0.209	217370	194070
2.062	2.201	0.168	2.186	0.086	21220	8280	9.500	10.000	0.500	9.930	0.209	223240	204550

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ***(Continued)*** **Heavy Duty Internal Spiral Retaining Rings** *MIL-R-27426*

Bore Dia. A	Ring		Groove		Static Thrust Load (lb)		Bore Dia. A	Ring		Groove		Static Thrust Load (lb)	
	Dia. G	Wall E	Dia. C	Width D	Ring	Groove		Dia. G	Wall E	Dia. C	Width D	Ring	Groove
2.125	2.267	0.168	2.251	0.086	21870	8935	9.750	10.260	0.500	10.189	0.209	229120	214325
2.188	2.334	0.168	2.318	0.086	22520	9745	10.000	10.523	0.500	10.450	0.209	234990	225330
2.250	2.399	0.168	2.382	0.086	23160	10455	10.250	10.786	0.500	10.711	0.209	240870	236605
2.312	2.467	0.200	2.450	0.086	23790	11700	10.500	11.047	0.500	10.970	0.209	246740	247110
2.357	2.535	0.200	2.517	0.086	24440	12715	10.750	11.313	0.500	11.234	0.209	252620	260530
2.440	2.602	0.200	2.584	0.086	25110	13550	11.000	11.575	0.500	11.495	0.209	258490	272645
2.500	2.667	0.200	2.648	0.086	25730	14640	11.250	11.838	0.500	11.756	0.209	264360	285040
2.531	2.700	0.200	2.681	0.086	26050	15185	11.500	12.102	0.562	12.018	0.209	270240	298285
2.562	2.733	0.225	2.714	0.103	29940	12775	11.750	12.365	0.562	12.279	0.209	276120	311240
2.625	2.801	0.225	2.781	0.103	30680	13780	12.000	12.628	0.562	12.540	0.209	281990	324475
2.688	2.868	0.225	2.848	0.103	31410	14775	12.250	12.891	0.562	12.801	0.209	287860	337980
2.750	2.934	0.225	2.914	0.103	32140	15790	12.500	13.154	0.562	13.063	0.209	293740	352390
2.813	3.001	0.225	2.980	0.103	32870	16845	12.750	13.417	0.562	13.324	0.209	299610	366460
2.834	3.027	0.225	3.006	0.103	33120	17595	13.000	13.680	0.662	13.585	0.209	305490	380805
2.875	3.072	0.225	3.051	0.103	33600	18505	13.250	13.943	0.662	13.846	0.209	311360	395430
3.000	3.204	0.225	3.182	0.103	35060	20795	13.500	14.207	0.662	14.108	0.209	317240	411000
3.062	3.271	0.281	3.248	0.120	42710	18735	13.750	14.470	0.662	14.369	0.209	323110	426185
3.125	3.338	0.281	3.315	0.120	43590	19865	14.000	14.732	0.662	14.630	0.209	328990	441645
3.157	3.371	0.281	3.348	0.120	44020	20345	14.250	14.995	0.662	14.891	0.209	334860	457380
3.250	3.470	0.281	3.446	0.120	45330	22120	14.500	15.259	0.750	15.153	0.209	340740	474120
3.346	3.571	0.281	3.546	0.120	46670	23905	14.750	15.522	0.750	15.414	0.209	346610	490415
3.469	3.701	0.281	3.675	0.120	48390	26405	15.000	15.785	0.750	15.675	0.209	352490	506990
3.500	3.736	0.281	3.710	0.120	48820	27370							

Source: Spirolox Retaining Rings, RRN Series. All dimensions are in inches. Depth of groove $d = (C - A)/2$. Thickness indicated is for unplated rings; add 0.002 to upper thickness tolerance for plated rings. Standard material: carbon spring steel (SAE 1070–1090).

Ring Thickness, F: For housing sizes 0.500 through 0.750, 0.035; for sizes 0.777 through 1.023, 0.042; for sizes 1.062 through 1.500, 0.050; for sizes 1.562 through 2.000, 0.062; for sizes 2.062 through 2.531, 0.078; for sizes 2.562 through 3.000, 0.093; for sizes 3.062 through 5.000, 0.111; for sizes 5.250 through 7.000, 0.156; for sizes 7.250 through 15.000, 0.187.

Ring Free Diameter Tolerances: For housing sizes 0.500 through 1.500, +0.013, –0.000; for sizes 1.562 through 2.000, +0.020, –0.000; for sizes 2.062 through 2.531, + 0.025, –0.000; for sizes 2.562 through 3.000, +0.030, –0.000; for sizes 3.062 through 5.000, +0.035, –0.000; for sizes 5.250 through 6.000, +0.050, –0.000; for sizes 6.250 through 7.000, +0.055. –0.000; for sizes 7.250 through 10.500, +0.070, –0.000; for sizes 10.750 through 12.750, +0.120, –0.000; for sizes 13.000 through 15.000, +0.140, –0.000.

Ring Thickness Tolerances: For housing sizes 0.500 through 1.500, ± 0.002; for sizes 1.562 through 5.000, ± 0.003; for sizes 5.250 through 6.000, ± 0.004; for sizes 6.250 through 15.000, ± 0.005.

Groove Diameter Tolerances: For housing sizes 0.500 through 0.750, ± 0.002; for sizes 0.777 through 1.023, ± 0.003; for sizes 1.062 through 1.500, ± 0.004; for sizes 1.562 through 2.000, ± 0.005; for sizes 2.062 through 5.000, ± 0.006; for sizes 5.250 through 6.000, ± 0.007; for sizes 6.250 through 10.500, ± 0.008; for sizes 10.750 through 12.500, ± 0.010; for sizes 12.750 through 15.000, ± 0.012.

Groove Width Tolerances: For housing sizes 0.500 through 1.023, +0.003, –0.000; for sizes 1.062 through 2.000, +0.004, –0.000; for sizes 2.062 through 5.000, +0.005, –0.000; for sizes 5.250 through 6.000, +0.006, –0.000; for sizes 6.250 through 7.000, +0.008, –0.000; for sizes 7.250 through 15.000, +0.008, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY



Table 10. Heavy Duty External Spiral Retaining Rings *MIL-R-27426*

Shaft Dia.	Ring		Groove		Static Thrust Load (lb)		Shaft Dia.	Ring		Groove		Static Thrust Load (lb)	
	Dia.	Wall	Dia.	Width				Dia.	Wall	Dia.	Width		
A	G	E	C	D	Ring	Groove	A	G	E	C	D	Ring	Groove
0.469	0.439	0.045	0.443	0.029	1880	510	3.500	3.293	0.270	3.316	0.120	48820	32250
0.500	0.464	0.050	0.468	0.039	2530	440	3.543	3.333	0.270	3.357	0.120	49420	33000
0.551	0.514	0.050	0.519	0.039	2790	540	3.625	3.411	0.270	3.435	0.120	50560	34490
0.562	0.525	0.050	0.530	0.039	2840	560	3.687	3.469	0.270	3.493	0.120	51430	35820
0.594	0.554	0.050	0.559	0.039	3000	700	3.750	3.527	0.270	3.552	0.120	52310	37180
0.625	0.583	0.055	0.588	0.039	3160	820	3.875	3.647	0.270	3.673	0.120	54050	39190
0.669	0.623	0.055	0.629	0.039	3380	1070	3.938	3.708	0.270	3.734	0.120	54930	40230
0.688	0.641	0.065	0.646	0.046	4170	960	4.000	3.765	0.270	3.792	0.120	55790	41660
0.750	0.698	0.065	0.704	0.046	4550	1250	4.250	4.037	0.270	4.065	0.120	59280	39370
0.781	0.727	0.065	0.733	0.046	4740	1430	4.375	4.161	0.270	4.190	0.120	61020	40530
0.812	0.756	0.065	0.762	0.046	4930	1620	4.500	4.280	0.270	4.310	0.120	62770	42810
0.875	0.814	0.075	0.821	0.046	5310	2000	4.750	4.518	0.270	4.550	0.120	66260	47570
0.938	0.875	0.075	0.882	0.046	5690	2440	5.000	4.756	0.270	4.790	0.120	69740	52580
0.984	0.919	0.085	0.926	0.046	5970	2790	5.250	4.995	0.350	5.030	0.139	83790	57830
1.000	0.932	0.085	0.940	0.046	6070	2950	5.500	5.228	0.350	5.265	0.139	87780	64720
1.023	0.953	0.085	0.961	0.046	6210	3170	5.750	5.466	0.350	5.505	0.139	91770	70540
1.062	0.986	0.103	0.998	0.056	7010	2810	6.000	5.705	0.350	5.745	0.139	95760	76610
1.125	1.047	0.103	1.059	0.056	7420	2890	6.250	5.938	0.418	5.985	0.174	122520	82930
1.188	1.105	0.103	1.118	0.056	7840	3450	6.500	6.181	0.418	6.225	0.174	127420	89510
1.250	1.163	0.103	1.176	0.056	8250	4110	6.750	6.410	0.418	6.465	0.174	132320	96330
1.312	1.218	0.118	1.232	0.056	8650	4810	7.000	6.648	0.418	6.705	0.174	137220	103400
1.375	1.277	0.118	1.291	0.056	9070	5650	7.250	6.891	0.418	6.942	0.174	142130	111810
1.438	1.336	0.118	1.350	0.056	9490	6340	7.500	7.130	0.437	7.180	0.209	176240	120170
1.500	1.385	0.118	1.406	0.056	9900	7060	7.750	7.368	0.437	7.420	0.209	182120	128060
1.562	1.453	0.128	1.468	0.068	12780	6600	8.000	7.606	0.437	7.660	0.209	187990	136200
1.625	1.513	0.128	1.529	0.068	13290	7330	8.250	7.845	0.437	7.900	0.209	193870	144590
1.687	1.573	0.128	1.589	0.068	13800	8190	8.500	8.083	0.437	8.140	0.209	199740	153220
1.750	1.633	0.128	1.650	0.068	14320	8760	8.750	8.324	0.437	8.383	0.209	205620	160800
1.771	1.651	0.128	1.669	0.068	14490	9040	9.000	8.560	0.500	8.620	0.209	211490	171250
1.812	1.690	0.128	1.708	0.068	14820	9440	9.250	8.798	0.500	8.860	0.209	217370	180640
1.875	1.751	0.158	1.769	0.068	15340	9950	9.500	9.036	0.500	9.100	0.209	223240	190280
1.969	1.838	0.158	1.857	0.068	16110	11040	9.750	9.275	0.500	9.338	0.209	229120	201140
2.000	1.867	0.158	1.886	0.068	16360	11420	10.000	9.508	0.500	9.575	0.209	234990	212810
2.062	1.932	0.168	1.946	0.086	21220	11820	10.250	9.745	0.500	9.814	0.209	240870	223780
2.125	1.989	0.168	2.003	0.086	21870	12980	10.500	9.984	0.500	10.054	0.209	246740	234490
2.156	2.018	0.168	2.032	0.086	22190	13390	10.750	10.221	0.500	10.293	0.209	252620	246000
2.250	2.105	0.168	2.120	0.086	23160	14650	11.000	10.459	0.500	10.533	0.209	258490	257230
2.312	2.163	0.168	2.178	0.086	23790	15510	11.250	10.692	0.500	10.772	0.209	264360	269270
2.375	2.223	0.200	2.239	0.086	24440	16170	11.500	10.934	0.562	11.011	0.209	270240	281590
2.437	2.283	0.200	2.299	0.086	25080	16840	11.750	11.171	0.562	11.250	0.209	276120	294180
2.500	2.343	0.200	2.360	0.086	25730	17530	12.000	11.410	0.562	11.490	0.209	281990	306450
2.559	2.402	0.200	2.419	0.086	26340	17940	12.250	11.647	0.562	11.729	0.209	287860	319580
2.625	2.464	0.200	2.481	0.086	27020	18930	12.500	11.885	0.562	11.969	0.209	293740	332360
2.687	2.523	0.200	2.541	0.086	27650	19640	12.750	12.124	0.562	12.208	0.209	299610	346030

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **Heavy Duty External Spiral Retaining Rings** *MIL-R-27426*

Shaft Dia. A	Ring		Groove		Static Thrust Load (lb)		Shaft Dia. A	Ring		Groove		Static Thrust Load (lb)	
	Dia. G	Wall E	Dia. C	Width D	Ring	Groove		Dia. G	Wall E	Dia. C	Width D	Ring	Groove
2.750	2.584	0.225	2.602	0.103	32140	20380	13.000	12.361	0.662	12.448	0.209	305490	359330
2.875	2.702	0.225	2.721	0.103	33600	22170	13.250	12.598	0.662	12.687	0.209	311360	373530
2.937	2.760	0.225	2.779	0.103	34320	23240	13.500	12.837	0.662	12.927	0.209	317240	387340
3.000	2.818	0.225	2.838	0.103	35060	24340	13.750	13.074	0.662	13.166	0.209	323110	402090
3.062	2.878	0.225	2.898	0.103	35780	25140	14.000	13.311	0.662	13.405	0.209	328990	417110
3.125	2.936	0.225	2.957	0.103	36520	26290	14.250	13.548	0.662	13.644	0.209	334860	432410
3.156	2.965	0.225	2.986	0.103	36880	26860	14.500	13.787	0.750	13.884	0.209	340740	447250
3.250	3.054	0.225	3.076	0.103	37980	28320	14.750	14.024	0.750	14.123	0.209	346610	463090
3.344	3.144	0.225	3.166	0.103	39080	29800	15.000	14.262	0.750	14.363	0.209	352490	478450
3.437	3.234	0.225	3.257	0.103	40170	30980							

Source: Spirolox Retaining Rings, RSN Series. All dimensions are in inches. Depth of groove $d = (A - C)/2$. Thickness indicated is for unplated rings; add 0.002 to upper tolerance for plated rings. Standard material: carbon spring steel (SAE 1070-1090).

Ring Thickness, F: For shaft size 0.469, 0.025; for sizes 0.500 through 0.669, 0.035; for sizes 0.688 through 1.023, 0.042; for sizes 1.062 through 1.500, 0.050; for sizes 1.562 through 2.000, 0.062; for sizes 2.062 through 2.687, 0.078; for sizes 2.750 through 3.437, 0.093; for sizes 3.500 through 5.000, 0.111; for sizes 5.250 through 6.000, 0.127; for sizes 6.250 through 7.250, 0.156; for sizes 7.500 through 15.000, 0.187.

Ring Free Diameter Tolerances: For shaft sizes 0.469 through 1.500, +0.000, –0.013; for sizes 1.562 through 2.000, +0.000, –0.020; for sizes 2.062 through 2.687, + 0.000, –0.025; for sizes 2.750 through 3.437, +0.000, –0.030; for sizes 3.500 through 5.000, +0.000, –0.035; for sizes 5.250 through 6.000, +0.000, –0.050; for sizes 6.250 through 7.000, +0.000, –0.060; for sizes 7.250 through 10.000, +0.000, –0.070; for sizes 10.250 through 12.500, +0.000, –0.090; for sizes 12.750 through 15.000, +0.000, –0.110.

Ring Thickness Tolerances: For shaft sizes 0.469 through 1.500, ±0.002; for sizes 1.562 through 5.000, ±0.003; for sizes 5.250 through 6.000, ±0.004; for sizes 6.250 through 15.000, ±0.005.

Groove Diameter Tolerances: For shaft sizes 0.469 through 0.562, ±0.002; for sizes 0.594 through 1.023, ±0.003; for sizes 1.062 through 1.500, ±0.004; for sizes 1.562 through 2.000, ±0.005; for sizes 2.062 through 5.000, ±0.006; for sizes 5.250 through 6.000, ±0.007; for sizes 6.250 through 10.000, ±0.008; for sizes 10.250 through 12.500, ±0.010; for sizes 12.750 through 15.000, ±0.012.

Groove Width Tolerances: For shaft sizes 0.469 through 1.023, +0.003, –0.000; for sizes 1.062 through 2.000, +0.004, –0.000; for sizes 2.062 through 5.000, +0.005, –0.000; for sizes 5.250 through 6.000, +0.006; –0.000; for sizes 6.250 through 7.250, + 0.008, –0.000; for sizes 7.500 through 15.000, +0.008, –0.000.

Thrust Load Capacity: The most important criterion in determining which ring is best suited for a specific application is thrust load capacity. The strength of the retaining ring and groove must both be considered when analyzing the thrust load capacity of an application to determine whether the groove or the retaining ring is likely to fail first. When a retaining ring application fails, the fault will usually be with the groove, unless the groove material is of very high strength.

Ring Material: The standard materials for spiral-wound retaining rings are SAE 1070 to 1090 carbon spring steels and 18-8 type 302 stainless steels. The 1070 to 1090 carbon spring steels provide high-strength retaining rings at low cost. Type 302 stainless steel withstands ordinary rusting. Other materials are used for specialized applications, such as the type 316 stainless frequently used in the food industry. For high-temperature use, superalloy A286 rings can be used at up to 900°F and Inconel X-750 at up to 1200°F. Other materials, such as 316 stainless steel, 17-7PH and Inconel stainless steels are sometimes used for special-purpose and custom-made rings. Standard ring are typically supplied uncoated, however, special finishes such as cadmium, phosphate, zinc, or black oxide coatings for carbon spring steel rings and passivation of stainless steel rings are available.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Important Dimensions of Inch Series External Retaining Rings
MS 16624



Lugs: D = 0.125 to 0.236 **Lugs: D = 4.25 to 8.00**

Shaft	Ring		Groove			Shaft	Ring		Groove		
Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E	Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E
0.125	0.112	0.010	0.117	0.012	0.012	1.812	1.675	0.062	1.708	0.068	0.156
0.156	0.142	0.010	0.146	0.012	0.015	1.875	1.735	0.062	1.769	0.068	0.159
0.188	0.168	0.015	0.175	0.018	0.018	1.969	1.819	0.062	1.857	0.068	0.168
0.197	0.179	0.015	0.185	0.018	0.018	2.000	1.850	0.062	1.886	0.068	0.171
0.219	0.196	0.015	0.205	0.018	0.021	2.062	1.906	0.078	1.946	0.086	0.174
0.236	0.215	0.015	0.222	0.018	0.021	2.125	1.964	0.078	2.003	0.086	0.183
0.250	0.225	0.025	0.230	0.029	0.030	2.156	1.993	0.078	2.032	0.086	0.186
0.276	0.250	0.025	0.255	0.029	0.030	2.250	2.081	0.078	2.120	0.086	0.195
0.281	0.256	0.025	0.261	0.029	0.030	2.312	2.139	0.078	2.178	0.086	0.201
0.312	0.281	0.025	0.290	0.029	0.033	2.375	2.197	0.078	2.239	0.086	0.204
0.344	0.309	0.025	0.321	0.029	0.033	2.438	2.255	0.078	2.299	0.086	0.207
0.354	0.320	0.025	0.330	0.029	0.036	2.500	2.313	0.078	2.360	0.086	0.210
0.375	0.338	0.025	0.352	0.029	0.036	2.559	2.377	0.078	2.419	0.086	0.210
0.394	0.354	0.025	0.369	0.029	0.036	2.625	2.428	0.078	2.481	0.086	0.216
0.406	0.366	0.025	0.382	0.029	0.036	2.688	2.485	0.078	2.541	0.086	0.219
0.438	0.395	0.025	0.412	0.029	0.039	2.750	2.543	0.093	2.602	0.103	0.222
0.469	0.428	0.025	0.443	0.029	0.039	2.875	2.659	0.093	2.721	0.103	0.231
0.500	0.461	0.035	0.468	0.039	0.048	2.938	2.717	0.093	2.779	0.103	0.237
0.551	0.509	0.035	0.519	0.039	0.048	3.000	2.775	0.093	2.838	0.103	0.243
0.562	0.521	0.035	0.530	0.039	0.048	3.062	2.832	0.093	2.898	0.103	0.246
0.594	0.550	0.035	0.559	0.039	0.051	3.125	2.892	0.093	2.957	0.103	0.252
0.625	0.579	0.035	0.588	0.039	0.054	3.156	2.920	0.093	2.986	0.103	0.255
0.669	0.621	0.035	0.629	0.039	0.060	3.250	3.006	0.093	3.076	0.103	0.261
0.672	0.621	0.035	0.631	0.039	0.060	3.346	3.092	0.093	3.166	0.103	0.270
0.688	0.635	0.042	0.646	0.046	0.063	3.438	3.179	0.093	3.257	0.103	0.270
0.750	0.693	0.042	0.704	0.046	0.069	3.500	3.237	0.109	3.316	0.120	0.276
0.781	0.722	0.042	0.733	0.046	0.072	3.543	3.277	0.109	3.357	0.120	0.279
0.812	0.751	0.042	0.762	0.046	0.075	3.625	3.352	0.109	3.435	0.120	0.285
0.844	0.780	0.042	0.791	0.046	0.080	3.688	3.410	0.109	3.493	0.120	0.291
0.875	0.810	0.042	0.821	0.046	0.081	3.750	3.468	0.109	3.552	0.120	0.297
0.938	0.867	0.042	0.882	0.046	0.084	3.875	3.584	0.109	3.673	0.120	0.303
0.984	0.910	0.042	0.926	0.046	0.087	3.938	3.642	0.109	3.734	0.120	0.306
1.000	0.925	0.042	0.940	0.046	0.090	4.000	3.700	0.109	3.792	0.120	0.312
1.023	0.946	0.042	0.961	0.046	0.093	4.250	3.989	0.109	4.065	0.120	0.276
1.062	0.982	0.050	0.998	0.056	0.096	4.375	4.106	0.109	4.190	0.120	0.276
1.125	1.041	0.050	1.059	0.056	0.099	4.500	4.223	0.109	4.310	0.120	0.285
1.188	1.098	0.050	1.118	0.056	0.105	4.750	4.458	0.109	4.550	0.120	0.300
1.250	1.156	0.050	1.176	0.056	0.111	5.000	4.692	0.109	4.790	0.120	0.315
1.312	1.214	0.050	1.232	0.056	0.120	5.250	4.927	0.125	5.030	0.139	0.330
1.375	1.272	0.050	1.291	0.056	0.126	5.500	5.162	0.125	5.265	0.139	0.351
1.438	1.333	0.050	1.350	0.056	0.132	5.750	5.396	0.125	5.505	0.139	0.366
1.500	1.387	0.050	1.406	0.056	0.141	6.000	5.631	0.125	5.745	0.139	0.381
1.562	1.446	0.062	1.468	0.068	0.141	6.250	5.866	0.156	5.985	0.174	0.396
1.625	1.503	0.062	1.529	0.068	0.144	6.500	6.100	0.156	6.225	0.174	0.411
1.687	1.560	0.062	1.589	0.068	0.147	6.750	6.335	0.156	6.465	0.174	0.426
1.750	1.618	0.062	1.650	0.068	0.150	7.000	6.570	0.156	6.705	0.174	0.441
1.772	1.637	0.062	1.669	0.068	0.153	7.500	7.009	0.187	7.180	0.209	0.480

Copyright 2004, Industrial Press, Inc., New York, NY

Source: Industrial Retaining Rings, 3100 Series. All dimensions are in inches. Depth of groove $d = (D - G)/2$. Thickness indicated is for unplated rings; for most plated rings, the maximum ring thickness will not exceed the minimum groove width (W) minus 0.0002 inch. Standard material: carbon spring steel (SAE 1060-1090).

Ring Free Diameter Tolerances: For shaft sizes 0.125 through 0.250, +0.002, –0.004; for sizes 0.276 through 0.500, +0.002, –0.005; for sizes 0.551 through 1.023, +0.005, –0.010; for sizes 1.062 through 1.500, +0.010, –0.015; for sizes 1.562 through 2.000, +0.013, –0.020; for sizes 2.062 through 2.500, +0.015, –0.025; for sizes 2.559 through 5.000, +0.020, –0.030; for sizes 5.250 through 6.000, +0.020, –0.040; for sizes 6.250 through 6.750, +0.020, –0.050; for sizes 7.000 and 7.500, +0.050, –0.130.

Ring Thickness Tolerances: For shaft sizes 0.125 and 0.156, ±0.001; for sizes 0.188 through 1.500, ±0.002; for sizes 1.562 through 5.000, ±0.003; for sizes 5.250 through 6.000, ±0.004; for sizes 6.250 through 7.500, ±0.005.

Groove Diameter Tolerances: For shaft sizes 0.125 through 0.250, ±0.0015; for sizes 0.276 through 0.562, ±0.002; for sizes 0.594 through 1.023, ±0.003; for sizes 1.062 though 1.500, ±0.004; for sizes 1.562 through 2.000, ±0.005; for sizes 2.062 through 5.000, ±0.006; for sizes 5.250 through 6.000, ±0.007; for sizes 6.250 through 7.500, ±0.008.

Groove Width Tolerances: For shaft sizes 0.125 through 0.236, +0.002, –0.000; for sizes 0.250 through 1.023, +0.003, –0.000; for sizes 1.062 through 2.000, +0.004, –0.000; for sizes 2.062 through 5.000, +0.005, –0.000; for sizes 5.250 through 6.000, +0.006, –0.000; for sizes 6.250 through 7.500, +0.008, –0.000.



Table 12. Important Dimensions of Inch Series Internal Retaining Rings

Housing	Ring		Groove			Housing	Ring		Groove		
Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E	Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E
0.250	0.280	0.015	0.268	0.018	0.027	2.500	2.775	0.078	2.648	0.086	0.222
0.312	0.346	0.015	0.330	0.018	0.027	2.531	2.775	0.078	2.681	0.086	0.225
0.375	0.415	0.025	0.397	0.029	0.033	2.562	2.844	0.093	2.714	0.103	0.228
0.438	0.482	0.025	0.461	0.029	0.036	2.625	2.910	0.093	2.781	0.103	0.234
0.453	0.498	0.025	0.477	0.029	0.036	2.677	2.980	0.093	2.837	0.103	0.240
0.500	0.548	0.035	0.530	0.039	0.045	2.688	2.980	0.093	2.848	0.103	0.240
0.512	0.560	0.035	0.542	0.039	0.045	2.750	3.050	0.093	2.914	0.103	0.246
0.562	0.620	0.035	0.596	0.039	0.051	2.812	3.121	0.093	2.980	0.103	0.252
0.625	0.694	0.035	0.665	0.039	0.060	2.835	3.121	0.093	3.006	0.103	0.255
0.688	0.763	0.035	0.732	0.039	0.066	2.875	3.191	0.093	3.051	0.103	0.264
0.750	0.831	0.035	0.796	0.039	0.069	2.953	3.325	0.093	3.135	0.103	0.273
0.777	0.859	0.042	0.825	0.046	0.072	3.000	3.325	0.093	3.182	0.103	0.273
0.812	0.901	0.042	0.862	0.046	0.075	3.062	3.418	0.109	3.248	0.120	0.279
0.866	0.961	0.042	0.920	0.046	0.081	3.125	3.488	0.109	3.315	0.120	0.285
0.875	0.971	0.042	0.931	0.046	0.084	3.149	3.523	0.109	3.341	0.120	0.288
0.901	1.000	0.042	0.959	0.046	0.087	3.156	3.523	0.109	3.348	0.120	0.288
0.938	1.041	0.042	1.000	0.046	0.093	3.250	3.623	0.109	3.446	0.120	0.294
1.000	1.111	0.042	1.066	0.046	0.099	3.346	3.734	0.109	3.546	0.120	0.300
1.023	1.136	0.042	1.091	0.046	0.102	3.469	3.857	0.109	3.675	0.120	0.309
1.062	1.180	0.050	1.130	0.056	0.102	3.500	3.890	0.109	3.710	0.120	0.315

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Important Dimensions of Inch Series Internal Retaining Rings**

Housing	Ring		Groove			Housing	Ring		Groove		
Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E	Dia. D	Dia. A	Thick. T	Dia. G	Width W	Margin E
1.125	1.249	0.050	1.197	0.056	0.108	3.543	3.936	0.109	3.755	0.120	0.318
1.181	1.319	0.050	1.255	0.056	0.111	3.562	3.936	0.109	3.776	0.120	0.321
1.188	1.319	0.050	1.262	0.056	0.111	3.625	4.024	0.109	3.841	0.120	0.324
1.250	1.388	0.050	1.330	0.056	0.120	3.740	4.157	0.109	3.964	0.120	0.336
1.259	1.388	0.050	1.339	0.056	0.120	3.750	4.157	0.109	3.974	0.120	0.336
1.312	1.456	0.050	1.396	0.056	0.126	3.875	4.291	0.109	4.107	0.120	0.348
1.375	1.526	0.050	1.461	0.056	0.129	3.938	4.358	0.109	4.174	0.120	0.354
1.378	1.526	0.050	1.464	0.056	0.129	4.000	4.424	0.109	4.240	0.120	0.360
1.438	1.596	0.050	1.528	0.056	0.135	4.125	4.558	0.109	4.365	0.120	0.360
1.456	1.616	0.050	1.548	0.056	0.138	4.250	4.691	0.109	4.490	0.120	0.360
1.500	1.660	0.050	1.594	0.056	0.141	4.331	4.756	0.109	4.571	0.120	0.360
1.562	1.734	0.062	1.658	0.068	0.144	4.500	4.940	0.109	4.740	0.120	0.360
1.575	1.734	0.062	1.671	0.068	0.144	4.625	5.076	0.109	4.865	0.120	0.360
1.625	1.804	0.062	1.725	0.068	0.150	4.724	5.213	0.109	4.969	0.120	0.366
1.653	1.835	0.062	1.755	0.068	0.153	4.750	5.213	0.109	4.995	0.120	0.366
1.688	1.874	0.062	1.792	0.068	0.156	5.000	5.485	0.109	5.260	0.120	0.390
1.750	1.942	0.062	1.858	0.068	0.162	5.250	5.770	0.125	5.520	0.139	0.405
1.812	2.012	0.062	1.922	0.068	0.165	5.375	5.910	0.125	5.650	0.139	0.405
1.850	2.054	0.062	1.962	0.068	0.168	5.500	6.066	0.125	5.770	0.139	0.405
1.875	2.054	0.062	1.989	0.068	0.171	5.750	6.336	0.125	6.020	0.139	0.405
1.938	2.141	0.062	2.056	0.068	0.177	6.000	6.620	0.125	6.270	0.139	0.405
2.000	2.210	0.062	2.122	0.068	0.183	6.250	6.895	0.156	6.530	0.174	0.420
2.047	2.280	0.078	2.171	0.086	0.186	6.500	7.170	0.156	6.790	0.174	0.435
2.062	2.280	0.078	2.186	0.086	0.186	6.625	7.308	0.156	6.925	0.174	0.450
2.125	2.350	0.078	2.251	0.086	0.189	6.750	7.445	0.156	7.055	0.174	0.456
2.165	2.415	0.078	2.295	0.086	0.195	7.000	7.720	0.156	7.315	0.174	0.471
2.188	2.415	0.078	2.318	0.086	0.195	7.250	7.995	0.187	7.575	0.209	0.486
2.250	2.490	0.078	2.382	0.086	0.198	7.500	8.270	0.187	7.840	0.209	0.510
2.312	2.560	0.078	2.450	0.086	0.207	7.750	8.545	0.187	8.100	0.209	0.525
2.375	2.630	0.078	2.517	0.086	0.213	8.000	8.820	0.187	8.360	0.209	0.540
2.440	2.702	0.078	2.584	0.086	0.216	8.250	9.095	0.187	8.620	0.209	0.555

Source: Industrial Retaining Rings, 3000 Series. All dimensions are in inches. Depth of groove $d = (G - D)/2$. Thickness indicated is for unplated rings. Standard material: carbon spring steel (SAE 1060-1090).

Ring Free Diameter Tolerances: For housing sizes 0.250 through 0.777, +0.010, –0.005; for sizes 0.812 through 1.023, +0.015, – 0.010; for sizes 1.062 through 1.500, + 0.025, – 0.020; for sizes 1.562 through 2.000, +0.035, –0.025; for sizes 2.047 through 3.000, +0.040, –0.030; for sizes 3.062 through 3.625, ±0.055; for sizes 3.740 through 6.000, ±0.065; for sizes 6.250 through 7.000, ±0.080; for sizes 7.250 through 8.250, ±0.090.

Ring Thickness Tolerances: For housing sizes 0.250 through 1.500, ±0.002; for sizes 1.562 through 5.000, ±0.003; for sizes 5.250 through 6.000, ±0.004; for sizes 6.250 through 8.250, ±0.005.

Groove Diameter Tolerances: For housing sizes 0.250 and 0.312, ±0.001; for sizes 0.375 through 0.750, ±0.002; for sizes 0.777 through 1.023 ±0.003; for sizes 1.062 through 1.500, ±0.004; for sizes 1.562 through 2.000, ±0.005; for sizes 2.047 through 5.000 ±0.006; for sizes 5.250 through 6.000, ±0.007; for sizes 6.250 through 8.250, ±0.008.

Groove Width Tolerances: For housing sizes 0.250 and 0.312, +0.002, – 0.000; for sizes 0.375 through 1.023, +0.003, –0.000; for sizes 1.062 through 2.000, +0.004, –0.000; for sizes 2.047 through 5.000, +0.005; –0.000; for sizes 5.250 through 6.000, +0.006, –0.000; for sizes 6.250 through 8.250, +0.008, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Important Dimensions of Inch Series External Retaining Rings *MS16632*



Shaft Diameter D	Ring			Groove			[a]Static Thrust Load (lb)	
	Free Dia. A	Thickness T	Diameter B	Diameter G	Width W	Margin E	Ring	Groove
0.125	0.102	0.015	0.164	0.106	0.018	0.020	85	40
0.156	0.131	0.015	0.205	0.135	0.018	0.020	110	55
0.188	0.161	0.015	0.245	0.165	0.018	0.022	130	70
0.219	0.187	0.025	0.275	0.193	0.029	0.026	260	100
0.236	0.203	0.025	0.295	0.208	0.029	0.028	280	115
0.250	0.211	0.025	0.311	0.220	0.029	0.030	295	130
0.281	0.242	0.025	0.344	0.247	0.029	0.034	330	170
0.312	0.270	0.025	0.376	0.276	0.029	0.036	370	200
0.375	0.328	0.025	0.448	0.335	0.029	0.040	440	265
0.406	0.359	0.025	0.485	0.364	0.029	0.042	480	300
0.437	0.386	0.025	0.516	0.393	0.029	0.044	515	340
0.500	0.441	0.035	0.581	0.450	0.039	0.050	825	440
0.562	0.497	0.035	0.653	0.507	0.039	0.056	930	550
0.625	0.553	0.035	0.715	0.563	0.039	0.062	1030	690
0.687	0.608	0.042	0.780	0.619	0.046	0.068	1700	820
0.750	0.665	0.042	0.845	0.676	0.046	0.074	1850	985
0.812	0.721	0.042	0.915	0.732	0.046	0.080	2010	1150
0.875	0.777	0.042	0.987	0.789	0.046	0.086	2165	1320
0.937	0.830	0.042	1.054	0.843	0.046	0.094	2320	1550
1.000	0.887	0.042	1.127	0.900	0.046	0.100	2480	1770
1.125	0.997	0.050	1.267	1.013	0.056	0.112	3300	2200
1.188	1.031	0.050	1.321	1.047	0.056	0.140	3500	2900
1.250	1.110	0.050	1.410	1.126	0.056	0.124	3600	2700
1.375	1.220	0.050	1.550	1.237	0.056	0.138	4000	3300
1.500	1.331	0.050	1.691	1.350	0.056	0.150	4400	4000
1.750	1.555	0.062	1.975	1.576	0.068	0.174	6400	5300
2.000	1.777	0.062	2.257	1.800	0.068	0.200	7300	7000

[a] *Thrust Load Safety Factors:* Ring, 4; groove, 2. Groove wall thrust loads are for grooves machined in cold-rolled steel with a tensile yield strength of 45,000 psi; for other shaft materials, the thrust load varies proportionally with the yield strength.

Source: Industrial Retaining Rings, 2000 Series. All dimensions are in inches. Depth of groove $d = (D - G)/2$. Standard material: carbon spring steel (SAE 1060-1090). Thickness indicated is for unplated rings; for most plated rings with shaft sizes less than 1.000 inch, the maximum thickness will not exceed the minimum groove width (W) minus 0.0002 inch; for larger rings, the ring thickness may increase by 0.002 inch.

Groove Maximum Bottom Radii: For shaft diameters less than 0.500 inch, 0.005 inch; for shaft sizes 0.500 through 1.000 inch, 0.010 inch; all larger sizes, 0.015 inch.

Ring Free Diameter Tolerances: For shaft sizes 0.125 through 0.188, +0.002, –0.004; for sizes 0.219 through 0.437, +0.003, –0.005; for sizes 0.500 through 0.625, ±0.006; for sizes 0.687 through 1.000, ±0.007; for sizes 1.125 through 1.500, ±0.008; for sizes 1.750 and 2.000, ±0.010.

Ring Thickness Tolerances: For shaft sizes 0.125 through 1.500, ±0.002; for sizes 1.750 and 2.000, ±0.003.

Groove Diameter Tolerances: For shaft sizes 0.125 through 0.188, ±0.0015; for sizes 0.219 through 0.437, ±0.002; for sizes 0.500 through 1.000, ±0.003; for sizes 1.125 through 1.500, ±0.004; for sizes 1.750 and 2.000, ±0.005.

Groove Width Tolerances: For shaft sizes 0.125 through 0.188, +0.002, –0.000; for sizes 0.219 through 1.000, +0.003, –0.000; for sizes 1.125 through 2.000, +0.004, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Important Dimensions of Inch Series External Retaining Rings *MS16633*



Shaft Diameter D	Ring			Groove			[a]Static Thrust Load (lb)	
	Free Dia. A	Thickness T	Diameter B	Diameter G	Width W	Margin E	Ring	Groove
0.040	0.025	0.010	0.079	0.026	0.012	0.014	13	7
0.062	0.051	0.010	0.140	0.052	0.012	0.010	20	7
0.062[a]	0.051	0.010	0.156	0.052	0.012	0.010	20	7
0.062[b]	0.051	0.020	0.187	0.052	0.023	0.010	40	7
0.094	0.073	0.015	0.187	0.074	0.018	0.020	45	20
0.094	0.069	0.015	0.230	0.074	0.018	0.020	45	20
0.110	0.076	0.015	0.375	0.079	0.018	0.030	55	40
0.125	0.094	0.015	0.230	0.095	0.018	0.030	65	45
0.140	0.100	0.015	0.203	0.102	0.018	0.038	70	60
0.140[c]	0.108	0.015	0.250	0.110	0.018	0.030	70	45
0.140[d]	0.102	0.025	0.270	0.105	0.029	0.034	150	55
0.156	0.114	0.025	0.282	0.116	0.029	0.040	165	70
0.172	0.125	0.025	0.312	0.127	0.029	0.044	180	90
0.188	0.145	0.025	0.335	0.147	0.029	0.040	195	90
0.188	0.122	0.025	0.375	0.125	0.029	0.062	195	135
0.218	0.185	0.025	0.437	0.188	0.029	0.030	225	75
0.250	0.207	0.025	0.527	0.210	0.029	0.040	260	115
0.312	0.243	0.025	0.500	0.250	0.029	0.062	325	225
0.375	0.300	0.035	0.660	0.303	0.039	0.072	685	315
0.437	0.337	0.035	0.687	0.343	0.039	0.094	800	485
0.437	0.375	0.035	0.600	0.380	0.039	0.058	800	290
0.500	0.392	0.042	0.800	0.396	0.046	0.104	1100	600
0.625	0.480	0.042	0.940	0.485	0.046	0.140	1370	1040
0.744	0.616	0.050	1.000	0.625	0.056	0.118	1940	1050
0.750	0.616	0.050	1.000	0.625	0.056	0.124	1960	1100
0.750	0.574	0.050	1.120	0.580	0.056	0.170	1960	1500
0.875	0.668	0.050	1.300	0.675	0.056	0.200	2200	2050
0.985	0.822	0.050	1.500	0.835	0.056	0.148	2570	1710
1.000	0.822	0.050	1.500	0.835	0.056	0.164	2620	1900
1.188	1.066	0.062	1.626	1.079	0.068	0.108	3400	1500
1.375	1.213	0.062	1.875	1.230	0.068	0.144	4100	2300

[a] *Thrust Load Safety Factors:* Ring 3; groove, 2.

Source: Industrial Retaining Rings, 1000 Series. All dimensions are in inches. Depth of groove $d = (D - G)/2$. Standard material: carbon spring steel (SAE 1060 –1090). Thickness indicated is for unplated rings; for most plated rings with shaft sizes less than 0.625, the maximum ring thickness will not exceed the minimum groove width (W) minus 0.0002 inch; for larger rings, the thickness may increase by 0.002 inch.

Groove Maximum Bottom Radii: For shaft sizes 0.040 and 0.062, 0.003 inch; for sizes 0.094 through 0.250, 0.005 inch; for sizes 0.312 through 0.437, 0.010 inch; for sizes 0.500 through 1.375, 0.015 inch.

Ring Free Diameter Tolerances: For shaft sizes 0.040 through 0.250, +0.001, –0.003; for sizes 0.312 through 0.500, +0.002, –0.004; for sizes 0.625 through 1.000, +0.003, –0.005; for sizes 1.188 and 1.375, +0.006, –0.010.

Ring Thickness Tolerances: For shaft sizes 0.040 and 0.062[a], ±0.001; for sizes 0.062[b] through 1.000, ±0.002; for sizes 1.188 and 1.375, ±0.003.

Groove Diameter Tolerances: For shaft sizes 0.040 through 0.218, +0.002, –0.000; for sizes 0.250 through 1.000, +0.003, –0.000; for sizes 1.188 and 1.375, +0.005, –0.000.

Grove Width Tolerances: For shaft sizes 0.040 through 0.140[c], +0.002, –0.000; for sizes 0.140[d] through 1.000, +0.003, –0.000; for sizes 1.188 and 1.375, +0.004, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Dimensions of Inch Series External Retaining Rings *MS3215*



Shaft Diameter D	Ring			Groove			[a]Static Thrust Load (lb)	
	Free Dia. A	Thickness T	Diameter B	Diameter G	Width W	Margin E	Ring	Groove
0.094	0.072	0.015	0.206	0.074	0.018	0.020	55	13
0.125	0.093	0.015	0.270	0.095	0.018	0.030	75	25
0.156	0.113	0.025	0.335	0.116	0.029	0.040	150	40
0.188	0.143	0.025	0.375	0.147	0.029	0.040	180	50
0.219	0.182	0.025	0.446	0.188	0.029	0.031	215	50
0.250	0.204	0.025	0.516	0.210	0.029	0.040	250	75
0.312	0.242	0.025	0.588	0.250	0.029	0.062	300	135
0.312	0.242	0.035	0.588	0.250	0.039	0.062	420	135
0.375	0.292	0.035	0.660	0.303	0.039	0.072	520	190
0.438	0.332	0.035	0.746	0.343	0.039	0.096	600	285
0.500	0.385	0.042	0.810	0.396	0.046	0.104	820	360
0.562	0.430	0.042	0.870	0.437	0.046	0.124	930	480

[a] *Thrust Load Safety Factors:* Ring, 3; groove, 2.

Source: Industrial Retaining Rings, 1200 Series. All dimensions are in inches. Depth of groove $d = (D - G)/2$. Standard material: carbon spring steel (SAE 1060-1090). Thickness indicated is for unplated rings; for most plated rings the maximum thickness will not exceed the minimum groove width (W) minus 0.0002 inch.

Groove Maximum Bottom Radii: For shaft sizes 0.250 and smaller, 0.005 inch; for sizes 0.312 through 0.438, 0.010 inch; for sizes 0.500 and 0.562, 0.015 inch. *Ring Free Diameter Tolerances:* For shaft sizes 0.094 through 0.156, +0.001, –0.003; for sizes 0.188 through 0.312, ±0.003; for sizes 0.375 through 0.562, ±0.004. *Ring Thickness Tolerances:* For all shaft sizes, ±0.002. *Groove Diameter Tolerances:* For shaft sizes 0.094 through 0.188, +0.002, –0.000; for sizes 0.219 and 0.250, ±0.002; for sizes 0.312 through 0.562, ±0.003. *Groove Width Tolerances:* For shaft sizes 0.094 and 0.125, +0.002, – 0.000; for sizes 0.156 through 0.562, +0.003, –0.000.

The thrust load capacities shown in the tables of this section include safety factors. Usually, a safety factor of 2 is used for groove thrust load calculations when the load is applied through a retained part and groove with both having sharp corners and where the minimum side clearance exists between the retained part and the shaft or bore. Groove thrust load values in the tables of this section are based on these conditions. A safety factor of 3 is usual for calculations of thrust load capacity based on ring shear.

Ideally, the corner of a retained part in contact with a retaining ring should have square corners and contact the ring as closely as possible to the shaft or housing. The tabulated thrust capacities assume that minimum clearances exist between the retained part and shaft or housing, that the groove and retained part have square corners, and that contact between the retained part and the ring occurs close to the shaft or housing. If these conditions apply, the tabulated thrust loads apply. If the application does not meet the previous conditions but the side clearances, radii, and chamfers are less than the maximum total radius or chamfer of Fig. 1, then the thrust load capacity must be reduced by dividing the tabulated value by 2. The maximum total radius is given by $0.5(b - d)$ and the maximum total chamfer by $0.375(b - d)$, where b is the radial wall thickness, and d is the groove depth. The recommended maximum total radius or chamfer specifications are intended to be used as guidelines by the designer, and to ensure the ring application will withstand published and calculated values of static thrust loads.

Copyright 2004, Industrial Press, Inc., New York, NY

In analyzing the retaining ring loading conditions, a static, uniformly applied load is usually assumed. Dynamic and eccentric loads, however, are frequently encountered. Eccentric loading occurs when the load is concentrated on a small portion of the ring, such as may be caused by incorrectly machined surfaces, cocking of the retained part, and axial misalignment of parts. Conditions leading to eccentric loading on the ring should be avoided. In addition to the factors that affect the static thrust capacity, applications in which shock or impact loading occurs must be evaluated very carefully and tested in service to assess the effect of the mass and velocity of the retained part striking the ring. Vibration caused by impact loading can also cause the ring to fail if the resonant frequency of the system (retaining ring application) coincides with the resonant frequency of the retaining ring.

Table 16. Dimensions of Inch Series Self-Locking External Retaining Rings



Shaft Diameter		Ring		Optical Groove			[a]Static Thrust Load (lb)	
Min. D	Max. D	Free Dia. A	Thickness T	Diameter G	Width W	Margin E	Ring	Groove
0.078	0.080	0.074	0.025	The use of grooves with these shaft sizes is not suggested.			10	0
0.092	0.096	0.089	0.025				10	0
0.123	0.127	0.120	0.025				20	0
0.134	0.138	0.130	0.025				20	0
0.154	0.158	0.150	0.025				22	0
0.185	0.189	0.181	0.035				25	0
0.248	0.252	0.238	0.035	0.240	0.041	0.030	35	90
0.310	0.316	0.298	0.042	0.303	0.048	0.030	50	110
0.373	0.379	0.354	0.042	0.361	0.048	0.030	55	185
0.434	0.440	0.412	0.050	0.419	0.056	0.030	60	280
0.497	0.503	0.470	0.050	0.478	0.056	0.040	65	390
0.622	0.628	0.593	0.062	0.599	0.069	0.045	85	570
0.745	0.755	0.706	0.062	0.718	0.069	0.050	90	845

[a] *Thrust Load Safety Factors:* Ring, 1; groove, 2.

Source: Industrial Retaining Rings, 7100 Series. All dimensions are in inches. Depth of groove $d = (D - G)/2$. Standard material: carbon spring steel (SAE 1060-1090). Thickness indicated is for unplated rings; for plated, phosphate coated, and stainless steel rings, the maximum ring thickness may be exceeded by 0.002 inch.

Ring Free Diameter Tolerances: For shaft sizes 0.078 through 0.138, +0.002, –0.003; for sizes 0.154 through 0.252, +0.002, –0.004; for sizes 0.310 through 0.440, +0.003, –0.005; for sizes 0.497 through 0.755, +0.004, –0.006. *Ring Thickness Tolerances:* For shaft sizes 0.078 through 0.158, ±0.002; for sizes 0.185 through 0.503, ±0.003; for sizes 0.622 through 0.755, ±0.004. *Groove Diameter Tolerances:* For shaft sizes less than 0.248, grooves are not recommended; for other sizes, grooves are optional. For shaft sizes 0.248 through 0.316, +0.005, –0.0015; for sizes 0.373 through 0.628, +0.001, –0.002; for sizes 0.745 and 0.755, +0.002, –0.003. *Groove Width Tolerances:* For shaft sizes 0.248 through 0.379, +0.003, –0.000; for sizes 0.434 through 0.755, +0.004, –0.000.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. Inch Series Internal and External Self-Locking Retaining Rings





Housing		Ring Dimensions			Static	Shaft		Ring Dimensions			Static
Min. D	Max. D	Thick. T	Dia. D	Margin E	Thrust Load	Min. D	Max. D	Thick. T	Dia. D	Margin E	Thrust Load
0.311	0.313	0.010	0.136	0.040	80	0.093	0.095	0.010	0.250	0.040	15
0.374	0.376	0.010	0.175	0.040	75	0.124	0.126	0.010	0.325	0.040	20
0.437	0.439	0.010	0.237	0.040	70	0.155	0.157	0.010	0.356	0.040	25
0.498	0.502	0.010	0.258	0.040	60	0.187	0.189	0.010	0.387	0.040	35
0.560	0.564	0.010	0.312	0.040	50	0.218	0.220	0.010	0.418	0.040	35
0.623	0.627	0.010	0.390	0.040	45	0.239	0.241	0.015	0.460	0.060	35
0.748	0.752	0.015	0.500	0.060	75	0.249	0.251	0.010	0.450	0.040	40
0.873	0.877	0.015	0.625	0.060	70	0.311	0.313	0.010	0.512	0.040	40
0.936	0.940	0.015	0.687	0.060	70	0.374	0.376	0.010	0.575	0.040	40
0.998	1.002	0.015	0.750	0.060	70	0.437	0.440	0.015	0.638	0.060	50
1.248	1.252	0.015	0.938	0.060	60	0.498	0.502	0.015	0.750	0.060	50
1.436	1.440	0.015	1.117	0.060	60	0.560	0.564	0.015	0.812	0.060	50
1.498	1.502	0.015	1.188	0.060	60	0.623	0.627	0.015	0.875	0.060	50
						0.748	0.752	0.015	1.000	0.060	50
						0.873	0.877	0.015	1.125	0.060	55
						0.998	1.002	0.015	1.250	0.060	60

Source: Industrial Retaining Rings, 6000 Series (internal) and 6100 Series (external). All dimensions are in inches, thrust loads are in pounds. Thickness indicated is for unplated rings. Standard material: carbon spring steel (SAE 1060-1090).

Internal Rings: Thrust loads are for rings made of standard material inserted into cold-rolled, low-carbon housing. *Ring Thickness Tolerances:* For housing sizes 0.311 through 0.627, ±0.001; for sizes 0.748 through 1.502, ±0.002. *Ring Diameter Tolerances:* For housing sizes 0.311 through 0.439, ±0.005; for sizes 0.498 through 1.502, ±0.010.

External Rings: Thrust loads are for rings made of standard material installed onto cold-rolled, low-carbon shafts. *Ring Thickness Tolerances:* For shaft sizes 0.093 through 0.220, ±0.001; for size 0.239, ±0.002; for sizes 0.249 through 0.376, ±0.001; for sizes 0.437 through 1.002, ±0.002. *Ring Diameter Tolerances:* For shaft sizes 0.093 through 0.502, ±0.005; for sizes 0.560 through 1.002, ±0.010.

Centrifugal Capacity: Proper functioning of a retaining ring depends on the ring remaining seated on the groove bottom. External rings "cling" to the groove bottom because the ring ID is slightly smaller than the diameter at the bottom of the groove. Ring speed should be kept below the allowable steady-state speed of the ring, or self-locking rings specially designed for high-speed applications should be used, otherwise an external ring can lose its grip on the groove. Applications of large retaining rings that tend to spin in their grooves when subjected to sudden acceleration or deceleration of the retained part can benefit from a ring with more "cling" (i.e., a smaller interior diameter) as long as the stress of installation is within permissible limits. Special rings are also available that lock into a hole in the bottom of the groove, thereby preventing rotation. The following equation can be used to determine the allowable steady-state speed N of an external spiral retaining ring:

Copyright 2004, Industrial Press, Inc., New York, NY

$$N = \sqrt{\frac{0.466 C_1 E^3 \times 10^{12}}{R_n^3 (1 + C_1)(R_o^3 - R_i^3)}} \quad (1)$$

where the speed N is in revolutions per minute, C_1 is the minimum ring cling to groove bottom, E is the ring radial wall, R_n is the free neutral ring radius, R_o is the free outside ring radius, and R_i is the free inside ring radius, all in inches. For external spiral rings, the minimum ring cling is given by: $C_1 = (C - G)/G$, where C is the mean groove diameter in inches, and G is the maximum ring free ID in inches.



Fig. 2. Localized Groove Yielding under Load. (a) Groove Profile before Loading; (b) Localized Yielding of Retained Part and Groove under Load; (c) Groove Profile after Loading beyond Thrust Capacity (*Courtesy Spirolox Retaining Rings*)

Rotation between Parts: The use of spiral-wound rings to retain a rotating part should be limited to applications with rotation in only one direction. The ring should be matched so that the rotation tends to wind the spring into the groove. External rings should be wound in the direction of rotation of the retained part but internal rings should be wound against the direction of rotation of the rotating part. Failure to observe these precautions will cause the ring to wind out of the groove. Spiral-wound rings can be obtained with either right-hand (normal rotation) or left-hand (reverse rotation) wound configurations. Stamped retaining rings do not have these limitations, and may be used for applications that require rotation of the retained part, regardless of the direction of rotation.

Retaining Ring Failure.— Failure of a retaining ring application can result from failure of the ring itself, failure of the groove, or both. If a ring fails, the cause is likely to be from shearing of the ring. Shear failure occurs when a ring is installed in a groove and loaded by a retained part with both the groove and the retained part having a compressive yield strength greater than 45,000 psi; or when the load is applied through a retained part and groove, both having sharp corners and line-to-line contact; or when the ring is too thin in section compared with its diameter. To examine the possibility of ring shear, the allowable thrust P_s, based on the shear strength of the ring material, is given by

$$P_s = \frac{\pi D t S_s}{K} \quad (2)$$

where P_s is in lb_f, D is the shaft or housing diameter in inches, t is the ring thickness in inches, S_s is the shear strength of the ring material in lb/in.^{2}, and K is the factor of safety.

Groove Failure: The most common type of groove failure is yielding of the groove material that occurs when the thrust load, applied through the retaining ring against the corner of the groove, exceeds the compressive yield strength of the groove. This yielding of the groove results from a low compressive yield strength of the groove material, and allows the ring to tilt and come out of the groove, as illustrated in Fig. 2(b).

When dishing of a ring occurs as a result of yielding in the groove material, a bending moment across the cross-section of the ring generates a tensile stress that is highest at the

Copyright 2004, Industrial Press, Inc., New York, NY

interior diameter of the ring. If the maximum stress is greater than the yield strength of the ring material, the ring ID will grow and the ring will become permanently dished in shape. To determine the thrust load capacity of a ring based on groove deformation, the allowable angle of ring deflection must be calculated, then the thrust load based on groove yield can be determined. However, for spiral-wound rings, the thrust load P_G that initiates the onset of groove deformation can be estimated from the following:

$$P_G = \frac{\pi D d S_y}{K} \tag{3}$$

where P_G is given in lb_f, D is the shaft or housing diameter in inches, d is the groove depth in inches, S_y is the yield strength of the groove material, and K is the safety factor. For stamped rings, estimate P_G by multiplying Equation (3) by the fraction of the groove circumference that contacts the ring.

The thrust load capacity of a particular retaining ring application can be increased by changing the workpiece material that houses the groove. Increasing the yield strength of the groove material increases the thrust load capacity of the retaining ring application. However, increasing the strength of the groove material may cause the failure mechanism to shift from groove deformation to ring shear. Therefore, use the lower of the values obtained from Equations (2) and (3) for the allowable thrust load.

Groove Design and Machining: In most applications, grooves are located near the end of a shaft or housing bore to facilitate installation and removal of the rings. The groove is normally located a distance at least two to three times the groove depth from the end of the shaft or bore. If the groove is too close to the end of the shaft or bore, the groove may shear or yield. The following equation can be used to determine the minimum safe distance Y of a groove from the end of a shaft or housing:

$$Y = \frac{K P_t}{\pi D S_c} \tag{4}$$

where K is the factor of safety, P_t is the thrust load on the groove in pounds, S_c is the shear strength of the groove material in psi, and D is the shaft or housing diameter in inches.

A properly designed and machined groove is just as important in a retaining ring application as the ring itself. The walls of grooves should be perpendicular to the shaft or bore diameter; the grooves should have square corners on the top edges, and radii at the bottom, within the tolerances specified by the manufacturers, as shown in Fig. 1 (page 1684). Test data indicate that the ultimate thrust capacity for both static and dynamic loading conditions is greatly affected if these groove requirements are not met. For spiral-wound rings, the maximum bottom groove radius is 0.005 inch for rings up to 1.000 inch free diameter and 0.010 inch for larger rings, internal or external. For stamped rings, the maximum bottom groove radius varies with ring size and style.

Table 18. Retaining Ring Standards

Military	
MIL-R-21248B	MS-16633 Open-type external uniform cross-section
	MS-16634 Open-type external uniform cross-section cylindrically
	MS-3215 Open-type external tapered cross-section
	MS-16632 Crescent-type external
	MS-16625 Internal
	MS-16629 Internal cylindrically bowed
	MS-16624 Closed-type external tapered cross-section

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. Retaining Ring Standards *(Continued)*

Military	
MIL-R-21248B	MS-16628 Closed-type external tapered cross-section cylindrically bowed
	MS-16627 Internal inverted
	MS-16626 Closed-type external tapered cross-section
	MS-90707 Self-locking external tapered cross-section
	MS-3217 External heavy-duty tapered cross-section
MIL-R-27426	Uniform cross-section spiral retaining rings, Type 1-External, Type 2-Internal
Acrospace Standard	
AS 3215	Ring, Retaining—Spiral, Internal, Heavy Duty, Stainless Steel
AS 3216	Ring, Retaining—Spiral, External, Heavy Duty, Stainless Steel
AS 3217	Ring, Retaining—Spiral, Internal, Light Duty, Stainless Steel
AS 3218	Ring, Retaining—Spiral, External, Light Duty, Stainless Steel
AS 3219	Ring, Wound, Dimensional and Acceptance Standard for Spiral Wound Retaining Rings
ANSI	
B27.6-1972, R1983	General Purpose Uniform Cross-Section Spiral Retaining Rings
B27.7-1977, R1983	General Purpose Tapered and Reduced Cross-Section Retaining Rings (Metric)
B27.8M-1977, R1983	General Purpose Metric Tapered and Reduced Cross-Section Retaining Rings
	Type 3DM1—Heavy Duty External Rings
	Type 3EM1—Reinforced “E” Rings
	Type 3FM1—“C” Type Rings
ANSI/SAE	
MA4016	Ring, Retaining—External Spiral Wound, Heavy and Medium Duty, Crescent, Metric
MA4017	Ring, Retaining—External Spiral Wound, Heavy and Medium Duty, Crescent, Metric
MA4020	Ring, Retaining—External Tapered, Type 1, Class 2, AMS 5520, Metric
MA4021	Ring, Retaining—Internal Tapered, Type 1, Class 1, AMS 5520, Metric
MA4029	Ring, Retaining—Internal, Beveled, Tapered, Type 2, Class 1, AMS 5520, Metric
MA4030	Ring, Retaining—External, Reinforced E-Ring, Type 1, Class 3, AMS 5520, Metric
MA4035	Rings, Retaining—Spiral Wound, Uniform Section, Corrosion Resistant, Procurement Specification for, Metric
MA4036	Ring, Retaining—Tapered Width, Uniform Thickness, Corrosion Resistant, Procurement Specification for, Metric
DIN	
DIN 471, 472, 6799, 984, 5417, 7993	Standards for normal and heavy type, internal and external retaining rings and retaining washers
LN 471, 472, 6799	Aerospace standards for internal and external retaining rings

Copyright 2004, Industrial Press, Inc., New York, NY

WING NUTS, WING SCREWS, AND THUMB SCREWS

Wing Nuts.— A wing nut is a nut having wings designed for manual turning without driver or wrench. As covered by ANSI B18.17-1968 (R1983) wing nuts are classified first, by type on the basis of the method of manufacture; and second, by style on the basis of design characteristics. They consist of:

Type A: Type A wing nuts are cold forged or cold formed solid nuts having wings of moderate height. In some sizes they are produced in regular, light, and heavy series to best suit the requirements of specific applications. Dimensions are given in Table 1.

Table 1. American National Standard Type A Wing Nuts
ANSI B18.17-1968, R1983



Nominal Size or Basic Major Diameter of Thread[a]	Thds. per Inch	Series[b]	Nut Blank Size (Ref)	A Wing Spread		B Wing Height		C Wing Thick.		D Between Wings		E Boss Dia.		G Boss Height	
				Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min
3 (0.0990)	48, 56	Hvy.	AA	0.72	0.59	0.41	0.28	0.11	0.07	0.21	0.17	0.33	0.29	0.14	0.10
4 (0.1120)	40, 38	Hvy.	AA	0.72	0.59	0.41	0.28	0.11	0.07	0.21	0.17	0.33	0.29	0.14	0.10
5 (0.1250)	40, 44	**Lgt.**	**AA**	**0.72**	**0.59**	**0.41**	**0.28**	**0.11**	**0.07**	**0.21**	**0.17**	**0.33**	**0.29**	**0.14**	**0.10**
		Hvy.	A	0.91	0.78	0.47	0.34	0.14	0.10	0.27	0.22	0.43	0.39	0.18	0.14
6 (0.1380)	32, 40	Lgt.	AA	0.72	0.59	0.41	0.28	0.11	0.07	0.21	0.17	0.33	0.29	0.14	0.10
		Hvy.	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.27**	**0.22**	**0.43**	**0.39**	**0.18**	**0.14**
8 (0.1640)	32, 36	**Lgt.**	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.27**	**0.22**	**0.43**	**0.39**	**0.18**	**0.14**
		Hvy.	B	1.10	0.97	0.57	0.43	0.18	0.14	0.33	0.26	0.50	0.45	0.22	0.17
10 (0.1900)	24, 32	**Lgt.**	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.27**	**0.22**	**0.43**	**0.39**	**0.18**	**0.14**
		Hvy.	B	1.10	0.97	0.57	0.43	0.18	0.14	0.33	0.26	0.50	0.45	0.22	0.17
12 (0.2160)	24, 28	**Lgt.**	**B**	**1.10**	**0.97**	**0.57**	**0.43**	**0.18**	**0.14**	**0.33**	**0.26**	**0.50**	**0.45**	**0.22**	**0.17**
		Hvy.	C	1.25	1.12	0.66	0.53	0.21	0.17	0.39	0.32	0.58	0.51	0.25	0.20
1/4 (0.2500)	20, 28	**Lgt.**	**B**	**1.10**	**0.97**	**0.57**	**0.43**	**0.18**	**0.14**	**0.39**	**0.26**	**0.50**	**0.45**	**0.22**	**0.17**
		Reg.	C	1.25	1.12	0.66	0.53	0.21	0.17	0.39	0.32	0.58	0.51	0.25	0.20
		Hvy.	D	1.44	1.31	0.79	0.65	0.24	0.20	0.48	0.42	0.70	0.64	0.30	0.26
5/16 (0.3125)	18, 24	**Lgt.**	**C**	**1.25**	**1.12**	**0.66**	**0.53**	**0.21**	**0.17**	**0.39**	**0.32**	**0.58**	**0.51**	**0.25**	**0.20**
		Reg.	D	1.44	1.31	0.79	0.65	0.24	0.20	0.48	0.42	0.70	0.64	0.30	0.26
		Hvy.	E	1.94	1.81	1.00	0.87	0.33	0.26	0.65	0.54	0.93	0.86	0.39	0.35
3/8 (0.3750)	16, 24	**Lgt.**	**D**	**1.44**	**1.31**	**0.79**	**0.65**	**0.24**	**0.20**	**0.48**	**0.42**	**0.70**	**0.64**	**0.30**	**0.26**
		Reg.	E	1.94	1.81	1.00	0.87	0.33	0.26	0.65	0.54	0.93	0.86	0.39	0.35
7/16 (0.4375)	14, 20	**Lgt.**	**E**	**1.94**	**1.81**	**1.00**	**0.87**	**0.33**	**0.26**	**0.65**	**0.54**	**0.93**	**0.86**	**0.39**	**0.35**
		Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	0.90	0.80	1.19	1.13	0.55	0.51
1/2 (0.5000)	13, 20	**Lgt.**	**E**	**1.94**	**1.81**	**1.00**	**0.87**	**0.33**	**0.26**	**0.65**	**0.54**	**0.93**	**0.86**	**0.39**	**0.35**
		Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	0.90	0.80	1.19	1.13	0.55	0.51
9/16 (0.5625)	12, 18	Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	0.90	0.80	1.19	1.13	0.55	0.51
5/8 (0.6250)	11, 18	Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	0.90	0.80	1.19	1.13	0.55	0.51
3/4 (0.7500)	10, 16	Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	0.90	0.80	1.19	1.13	0.55	0.51

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.

[b] Lgt. = Light; Hvy. = Heavy; Reg. = Regular. Sizes shown in **bold face** are preferred.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Type B: Type B wing nuts are hot forged solid nuts available in two wing styles: Style 1, having wings of moderate height; and Style 2, having high wings. Dimensions are given in Table 2.

Table 2. American National Standard Type B Wing Nuts
ANSI B18.17-1968, R1983



STYLE 1 STYLE 2

Nominal Size or Basic Major Diameter of Thread[a]	Thds. per Inch	*A* Wing Spread		*B* Wing Height		*C* Wing Thick.		*D* Between Wings		*E* Boss Dia.		*G* Boss Height	
		Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min
Type B, Style 1													
5 (0.1250)	40	0.78	0.72	0.36	0.30	0.13	0.10	0.28	0.22	0.31	0.28	0.22	0.16
10 (0.1900)	24	0.97	0.91	0.45	0.39	0.15	0.12	0.34	0.28	0.39	0.36	0.28	0.22
1/4 (0.2500)	20	1.16	1.09	0.56	0.50	0.17	0.14	0.41	0.34	0.47	0.44	0.34	0.28
5/16 (0.3125)	18	1.44	1.38	0.67	0.61	0.18	0.15	0.50	0.44	0.55	0.52	0.41	0.34
3/8 (0.3750)	16	1.72	1.66	0.80	0.73	0.20	0.17	0.59	0.53	0.63	0.60	0.47	0.41
7/16 (0.4375)	14	2.00	1.94	0.91	0.84	0.21	0.18	0.69	0.62	0.71	0.68	0.53	0.47
1/2 (0.5000)	13	2.31	2.22	1.06	0.94	0.23	0.20	0.78	0.69	0.79	0.76	0.62	0.50
9/16 (0.5625)	12	2.59	2.47	1.17	1.05	0.25	0.21	0.88	0.78	0.88	0.84	0.69	0.56
5/8 (0.6250)	11	2.84	2.72	1.31	1.19	0.27	0.23	0.94	0.84	0.96	0.92	0.75	0.62
3/4 (0.7500)	10	3.31	3.19	1.52	1.39	0.29	0.25	1.10	1.00	1.12	1.08	0.88	0.75
Type B, Style 2													
5 (0.1250)	40	0.81	0.75	0.62	0.56	0.12	0.09	0.28	0.22	0.31	0.28	0.22	0.16
10 (0.1900)	24	1.01	0.95	0.78	0.72	0.14	0.11	0.35	0.29	0.39	0.36	0.28	0.22
1/4 (0.2500)	20	1.22	1.16	0.94	0.88	0.16	0.13	0.41	0.35	0.47	0.44	0.34	0.28
5/16 (0.3125)	18	1.43	1.37	1.09	1.03	0.17	0.14	0.48	0.42	0.55	0.52	0.41	0.34
3/8 (0.3750)	16	1.63	1.57	1.25	1.19	0.18	0.15	0.55	0.49	0.63	0.60	0.47	0.41
7/16 (0.4375)	14	1.90	1.84	1.42.	1.36	0.19	0.16	0.62	0.56	0.71	0.68	0.53	0.47
1/2 (0.5000)	13	2.13	2.04	1.58	1.45	0.20	0.17	0.69	0.60	0.79	0.76	0.62	0.50
9/16 (0.5625)	12	2.40	2.28	1.75	1.62	0.22	0.18	0.76	0.67	0.88	0.84	0.69	0.56
5/8 (0.6250)	11	2.60	2.48	1.91	1.78	0.23	0.19	0.83	0.74	0.96	0.92	0.75	0.62
3/4 (0.7500)	10	3.02	2.90	2.22	2.09	0.24	0.20	0.97	0.88	1.12	1.08	0.88	0.75

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Type C Wing Nuts *ANSI B18.17-1968, R1983*



STYLE 1



STYLE 2



STYLE 3

Nominal Size or Basic Major Diameter of Thread[a]	Thds. per Inch	Series	Nut Blank Size (Ref)	*A* Wing Spread		*B* Wing Height		*C* Wing Thick.		*D* Between Wings		*E* Boss Dia.		*F* Boss Dia.		*G* Boss Height	
				Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min
Type C, Style 1																	
4 (0.1120)	40	Reg.	AA	0.66	0.64	0.36	0.35	0.11	0.09	0.18	0.16	0.27	0.25	0.32	0.30	0.16	0.14
5 (0.1250)	40	Reg.	AA	0.66	0.64	0.36	0.35	0.11	0.09	0.18	0.16	0.27	0.25	0.32	0.30	0.16	0.14
6 (0.1380)	32	**Reg.**	**AA**	**0.66**	**0.64**	**0.36**	**0.35**	**0.11**	**0.09**	**0.18**	**0.16**	**0.27**	**0.25**	**0.32**	**0.30**	**0.16**	**0.14**
		Hvy.	A	0.85	0.83	0.43	0.42	0.14	0.12	0.29	0.27	0.38	0.36	0.41	0.40	0.20	0.18
8 (0.1640)	32	Reg.	A	0.85	0.83	0.43	0.42	0.14	0.12	0.29	0.27	0.38	0.36	0.41	0.40	0.20	0.18
10 (0.1900)	24, 32	Reg.	A	0.85	0.83	0.43	0.42	0.14	0.12	0.29	0.27	0.38	0.36	0.41	0.40	0.20	0.18
12 (0.2160)	24	**Reg.**	A	**0.85**	**0.83**	**0.43**	**0.42**	**0.14**	**0.12**	**0.29**	**0.27**	**0.38**	**0.36**	**0.41**	**0.40**	**0.20**	**0.18**
		Hvy.	B	1.08	1.05	0.57	0.53	0.16	0.14	0.32	0.30	0.44	0.42	0.48	0.46	0.23	0.21
¼ (0.2500)	20, 28	Reg.	B	1.08	1.05	0.57	0.53	0.16	0.14	0.32	0.30	0.44	0.42	0.48	0.46	0.23	0.21
5/16 (0.3125)	18, 24	Reg.	C	1.23	1.20	0.64	0.62	0.20	0.18	0.39	0.35	0.50	0.49	0.57	0.55	0.26	0.24
⅜ (0.3750)	16, 24	Reg.	D	1.45	1.42	0.74	0.72	0.23	0.21	0.46	0.42	0.62	0.60	0.69	0.67	0.29	0.27
7/16 (0.4375)	14, 20	**Reg.**	**E**	**1.89**	**1.86**	**0.91**	**0.90**	**0.29**	**0.28**	**0.67**	**0.65**	**0.75**	**0.73**	**0.83**	**0.82**	**0.38**	**0.37**
		Hvy.	EH	1.89	1.86	0.93	0.91	0.34	0.33	0.63	0.62	0.81	0.79	0.89	0.87	0.42	0.40
½ (0.5000)	13, 20	**Reg.**	**E**	**1.89**	**1.86**	**0.91**	**0.90**	**0.29**	**0.28**	**0.67**	**0.65**	**0.75**	**0.73**	**0.83**	**0.82**	**0.38**	**0.37**
		Hvy.	EH	1.89	1.86	0.93	0.91	0.34	0.33	0.63	0.62	0.81	0.79	0.89	0.87	0.42	0.40
Type C, Style 2																	
5 (0.1250)	40	…	…	0.82	0.80	0.25	0.23	0.09	0.08	0.21	0.19	0.26	0.24	…	…	0.17	0.15
6 (0.1380)	32	…	…	0.82	0.80	0.25	0.23	0.09	0.08	0.21	0.19	0.26	0.24	…	…	0.17	0.15
8 (0.1640)	32	…	…	1.01	0.99	0.28	0.27	0.11	0.09	0.29	0.28	0.36	0.34	…	…	0.19	0.18
10 (0.1900)	24, 32	…	…	1.01	0.99	0.28	0.27	0.11	0.09	0.29	0.28	0.36	0.34	…	…	0.19	0.18
12 (0.2160)	24	…	…	1.20	1.18	0.32	0.31	0.12	0.11	0.38	0.37	0.44	0.43	…	…	0.22	0.20
¼ (0.2500)	20	…	…	1.20	1.18	0.32	0.31	0.12	0.11	0.38	0.37	0.44	0.43	…	…	0.22	0.20
5/16 (0.3125)	18	…	…	1.51	1.49	0.36	0.35	0.14	0.12	0.44	0.43	0.51	0.49	…	…	0.24	0.23
⅜ (0.3750)	16	…	…	1.89	1.86	0.58	0.55	0.20	0.17	0.44	0.43	0.63	0.62	…	…	0.37	0.35
Type C, Style 3																	
5 (0.1250)	40	…	…	0.92	0.89	0.70	0.67	0.16	0.15	0.26	0.24	0.38	0.36	…	…	0.25	0.24
6 (0.1380)	32	…	…	0.92	0.89	0.70	0.67	0.16	0.15	0.26	0.24	0.38	0.36	…	…	0.25	0.24
8 (0.1640)	32	…	…	0.92	0.89	0.70	0.67	0.16	0.15	0.26	0.24	0.38	0.36	…	…	0.25	0.24
10 (0.1900)	24, 32	…	…	1.14	1.12	0.85	0.83	0.19	0.17	0.32	0.30	0.44	0.42	…	…	0.29	0.27
12 (0.2160)	24	…	…	1.14	1.12	0.85	0.83	0.19	0.17	0.32	0.30	0.44	0.42	…	…	0.29	0.27
¼ (0.2500)	20	…	…	1.14	1.12	0.85	0.83	0.19	0.17	0.32	0.30	0.44	0.42	…	…	0.29	0.27
5/16 (0.3125)	18	…	…	1.29	1.27	1.04	1.02	0.23	0.22	0.39	0.36	0.50	0.49	…	…	0.35	0.34
⅜ (0.3750)	16	…	…	1.51	1.49	1.20	1.18	0.27	0.25	0.45	0.42	0.62	0.60	…	…	0.43	0.42

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.

All dimensions in inches. Sizes shown in **bold face** are preferred.

Type C: Type C wing nuts are die cast solid nuts and are available in three wing styles: Style 1, having wings of moderate height; Style 2, having low wings; and Style 3, having high wings. In some sizes, the Style 1 nuts are produced in regular, light, and heavy series to best suit the requirements of specific applications. Dimensions are given in Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Type D Wing Nuts *ANSI B18.17-1968, R1983*



Nominal Size or Basic Major Diameter of Thread[a]	Thds. per Inch	Series[b]	*A* Wing Spread		*B* Wing Height		*C* Wing Thick.		*D* Between Wings	*E* Boss Dia.		*G* Boss Hgt.	*H* Wall Hgt.	*T* Stock Thick.	
			Max	Min	Max	Min	Max	Min	Min	Max	Min	Min	Min	Max	Min
Type D, Style 1															
8 (0.1640)	32, 36	…	0.78	0.72	0.40	0.34	0.18	0.14	0.25	0.41	0.35	0.08	0.12	0.04	0.03
10 (0.1900)	24, 32	…	0.91	0.85	0.47	0.41	0.21	0.17	0.34	0.53	0.47	0.10	0.12	0.04	0.03
12 (0.2160)	24, 28	…	1.09	1.03	0.47	0.41	0.21	0.17	0.34	0.53	0.47	0.10	0.12	0.05	0.04
1/4 (0.2500)	20, 28	…	1.11	1.05	0.50	0.44	0.25	0.21	0.34	0.62	0.56	0.11	0.12	0.05	0.04
5/16 (0.3125)	18, 24	…	1.30	1.24	0.59	0.53	0.30	0.26	0.46	0.73	0.67	0.14	0.18	0.06	0.05
3/8 (0.3750)	16, 24	…	1.41	1.34	0.67	0.61	0.34	0.30	0.69	0.83	0.77	0.16	0.18	0.06	0.05
Type D, Style 2															
5 (0.1250)	40	Reg.	1.03	0.97	0.25	0.19	0.19	0.13	0.30	0.40	0.34	0.07	0.09	0.04	0.03
6 (0.1380)	32	Reg.	1.03	0.97	0.25	0.19	0.19	0.13	0.30	0.40	0.34	0.08	0.09	0.04	0.03
8 (0.1640)	32	Reg.	1.03	0.97	0.25	0.19	0.19	0.13	0.30	0.40	0.34	0.08	0.09	0.04	0.03
10 (0.1900)	24, 32	Reg.	1.40	1.34	0.34	0.28	0.25	0.18	0.32	0.53	0.47	0.09	0.16	0.05	0.04
		Hvy.	1.21	1.16	0.28	0.26	0.31	0.25	0.60	0.61	0.55	0.09	0.13	0.05	0.04
12 (0.2160)	24	Reg.	1.21	1.16	0.28	0.26	0.31	0.25	0.60	0.61	0.55	0.11	0.13	0.05	0.04
1/4 (0.2500)	20	Reg.	1.21	1.16	0.28	0.26	0.31	0.25	0.60	0.61	0.55	0.11	0.13	0.05	0.04
Type D, Style 3															
10 (0.1900)	24, 32	Lgt.	1.31	1.25	0.48	0.42	0.29	0.23	0.47	0.65	0.59	0.08	0.12	0.04	0.03
		Reg.	1.40	1.34	0.53	0.47	0.25	0.19	0.50	0.75	0.69	0.08	0.14	0.04	0.03
12 (0.2160)	24	Reg.	1.28	1.22	0.40	0.34	0.23	0.17	0.59	0.73	0.67	0.11	0.12	0.04	0.03
1/4 (0.2500)	20	Lgt.	1.28	1.22	0.40	0.34	0.23	0.17	0.59	0.73	0.67	0.11	0.12	0.04	0.03
		Reg.	1.78	1.72	0.66	0.60	0.31	0.25	0.70	1.03	0.97	0.14	0.17	0.06	0.04
		Hvy.	1.47	1.40	0.50	0.44	0.37	0.31	0.66	1.03	0.97	0.14	0.14	0.08	0.06
5/16 (0.3125)	18	Reg.	1.78	1.72	0.66	0.60	0.31	0.25	0.70	1.03	0.97	0.14	0.17	0.06	0.04
		Hvy.	1.47	1.40	0.50	0.44	0.37	0.31	0.66	1.03	0.97	0.14	0.14	0.08	0.06

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.
[b] Lgt. = Light; Hvy. = Heavy; Reg. = Regular.

All dimensions in inches.

Type D: Type D wing nuts are stamped sheet metal nuts and are available in three styles: Style 1, having wings of moderate height; Style 2, having low wings; and Style 3, having wings of moderate height and a larger bearing surface. In some sizes, Styles 2 and 3 are produced in regular, light, and heavy series to best suit the requirements of specific applications. Dimensions are given in Table 4.

Specification of Wing Nuts.— When specifying wing nuts, the following data should be included in the designation and should appear in the following sequence: nominal size (number, fraction or decimal equivalent), threads per inch, type, style and/or series, material, and finish.

Examples: 10—32 Type A Wing Nut, Regular Series, Steel, Zinc Plated.
0.250—20 Type C Wing Nut, Style 1, Zinc Alloy, Plain.

Threads for Wing Nuts.— Threads are in conformance with the ANSI Standard Unified Thread, Class 2B for all types of wing nuts except type D which have a modified Class 2B thread. Because of the method of manufacture, the minor diameter of the thread in type D

Copyright 2004, Industrial Press, Inc., New York, NY

nuts may be somewhat larger than the Unified Thread Class 2B maximum but shall in no case exceed the minimum pitch diameter.

Materials and Finish for Wing Nuts.— Types A, B, and D wing nuts are normally supplied as specified by the user in carbon steel, brass or corrosion resistant steel of good quality and adaptable to the manufacturing process. Type C wing nuts are made from die cast zinc alloy. Unless otherwise specified, wing nuts are supplied with a plain (unplated or uncoated) finish.

Wing Screws.— A wing screw is a screw having a wing-shaped head designed for manual turning without a driver or wrench. As covered by ANSI B18.17-1968 (R1983) wing screws are classified first, by type on the basis of the method of manufacture, and second, by style on the basis of design characteristics. They consist of the following:

Type A: Type A wing screws are of two-piece construction having cold formed or cold forged wing portions of moderate height. In some sizes they are produced in regular, light, and heavy series to best suit the requirements of specific applications. Dimensions are given in Table 5.

Type B: Type B wing screws are of hot forged one-piece construction available in two wing styles: Style 1, having wings of moderate height; and Style 2, having high wings. Dimensions are given in Table 5.

Type C: Type C wing screws are available in two styles: Style 1, of a one-piece die cast construction having wings of moderate height; and Style 2, of a two-piece construction having a die cast wing portion of moderate height. Dimensions are given in Table 6.

Type D: Type D wing screws are of two-piece welded construction having stamped sheet metal wing portions of moderate height. Dimensions are given in Table 6.

Materials for Wing Screws and Thumb Screws: Type A wing screws are normally supplied in carbon steel with the shank portion case hardened. When so specified, they also may be made from corrosion resistant steel, brass or other materials as agreed upon by the manufacturer and user.

Type B wing screws are normally made from carbon steel but also may be made from corrosion resistant steel, brass or other materials.

Type C, Style 1, wing screws are supplied only in die cast zinc alloy. Type C, Style 2, wing screws have the wing portion made from die cast zinc alloy with the shank portion normally made from carbon steel. Where so specified, the shank portion may be made from corrosion resistant steel, brass or other materials as agreed upon by the manufacturer and user.

Type D wing screws are normally supplied in carbon steel but also may be made from corrosion resistant steel, brass or other materials.

Thumb screws of all types are normally made from a good commercial quality of carbon steel having a maximum ultimate tensile strength of 48,000 psi. Where so specified, carbon steel thumb screws are case hardened. They are also made from corrosion resistant steel, brass, and other materials as agreed upon by the manufacturer and user.

Unless otherwise specified, wing screws and thumb screws are supplied with a plain (unplated or uncoated) finish.

Thumb Screws.— A thumb screw is a screw having a flattened head designed for manual turning without a driver or wrench. As covered by ANSI B18.17-1968 (R1983) thumb screws are classified by type on the basis of design characteristics. They consist of the following:

Type A: Type A thumb screws are forged one-piece screws having a shoulder under the head and are available in two series: regular and heavy. Dimensions are given in Table 7.

Type B: Type B thumb screws are forged one-piece screws without a shoulder and are available in two series: regular and heavy. Dimensions are given in Table 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Types A and B Wing Screws

ANSI B18.17-1968, R1983



TYPE A



TYPE B

Nominal Size or Basic Major Diameter[a]	Thds. per Inch	Series[b]	Head Blank size (Ref)	*A* Wing Spread Max	*A* Wing Spread Min	*B* Wing Height Max	*B* Wing Height Min	*C* Wing Thick. Max	*C* Wing Thick. Min	*E* Boss Dia. Max	*E* Boss Dia. Min	*G* Boss Height. Max	*G* Boss Height. Min	*L* Practical Screw Lengths Max	*L* Practical Screw Lengths Min
Type A															
4 (0.1120)	40	Hvy.	AA	0.72	0.59	0.41	0.28	0.11	0.07	0.33	0.29	0.14	0.10	0.75	0.25
6 (0.1380)	32	Lgt.	AA	0.72	0.59	0.41	0.28	0.11	0.07	0.33	0.29	0.14	0.10	} 0.75	0.25
		Hvy.	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.43**	**0.39**	**0.18**	**0.14**		
8 (0.1640)	32	**Lgt.**	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.43**	**0.39**	**0.18**	**0.14**	} 0.75	0.38
		Hvy.	B	1.10	0.97	0.57	0.43	0.18	0.14	0.50	0.45	0.22	0.17		
10 (0.1900)	24, 32	**Lgt.**	**A**	**0.91**	**0.78**	**0.47**	**0.34**	**0.14**	**0.10**	**0.43**	**0.39**	**0.18**	**0.14**	} 1.00	0.38
		Hvy.	B	1.10	0.97	0.57	0.43	0.18	0.14	0.50	0.45	0.22	0.17		
12 (0.2160)	24	**Lgt.**	**B**	**1.10**	**0.97**	**0.57**	**0.43**	**0.18**	**0.14**	**0.50**	**0.45**	**0.22**	**0.17**	} 1.00	0.38
		Hvy.	C	1.25	1.12	0.66	0.53	0.21	0.17	0.58	0.51	0.25	0.20		
1/4 (0.2500)	20	**Lgt.**	**B**	**1.10**	**0.97**	**0.57**	**0.43**	**0.18**	**0.14**	**0.50**	**0.45**	**0.22**	**0.17**	} 1.50	0.50
		Reg.	C	1.25	1.12	0.66	0.53	0.21	0.17	0.58	0.51	0.25	0.20		
		Hvy.	D	1.44	1.31	0.79	0.65	0.24	0.20	0.70	0.64	0.30	0.26		
5/16 (0.3125)	18	**Lgt.**	**C**	**1.25**	**1.12**	**0.66**	**0.53**	**0.21**	**0.17**	**0.58**	**0.51**	**0.25**	**0.20**	} 1.50	0.50
		Reg.	D	1.44	1.31	0.79	0.65	0.24	0.20	0.70	0.64	0.30	0.26		
		Hvy.	E	1.94	1.81	1.00	0.87	0.33	0.26	0.93	0.86	0.39	0.35		
3/8 (0.3750)	16	**Lgt.**	**D**	**1.44**	**1.31**	**0.79**	**0.65**	**0.24**	**0.20**	**0.70**	**0.64**	**0.30**	**0.26**	} 2.00	0.75
		Reg.	E	1.94	1.81	1.00	0.87	0.33	0.26	0.93	0.86	0.39	0.35		
		Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	1.19	1.13	0.55	0.51		
7/16 (0.4375)	14	**Lgt.**	**E**	**1.94**	**1.81**	**1.00**	0.87	**0.33**	**0.26**	**0.93**	**0.86**	**0.39**	**0.35**	} 4.00	1.00
		Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	1.19	1.13	0.55	0.51		
1/2 (0.5000)	13	**Lgt.**	**E**	**1.94**	**1.81**	**1.00**	**0.87**	**0.33**	**0.26**	**0.93**	**0.86**	**0.39**	**0.35**	} 4.00	1.00
		Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	1.19	1.13	0.55	0.51		
5/8 (0.6250)	11	Hvy.	F	2.76	2.62	1.44	1.31	0.40	0.34	1.19	1.13	0.55	0.51	4.00	1.25
Type B, Style 1															
10 (0.1900)	24	…	…	0.97	0.91	0.45	0.39	0.15	0.12	0.39	0.36	0.28	0.22	2.00	0.50
1/4 (0.2500)	20	…	…	1.16	1.09	0.56	0.50	0.17	0.14	0.47	0.44	0.34	0.28	3.00	0.50
5/16 (0.3125)	18	…	…	1.44	1.38	0.67	0.61	0.18	0.15	0.55	0.52	0.41	0.34	3.00	0.50
3/8 (0.3750)	16	…	…	1.72	1.66	0.80	0.73	0.20	0.17	0.63	0.60	0.47	0.41	4.00	0.50
7/16 (0.4375)	14	…	…	2.00	1.94	0.91	0.84	0.21	0.18	0.71	0.68	0.53	0.47	3.00	1.00
1/2 (0.5000)	13	…	…	2.31	2.22	1.06	0.94	0.23	0.20	0.79	0.76	0.62	0.50	3.00	1.00
5/8 (0.6250)	11	…	…	2.84	2.72	1.31	1.19	0.27	0.23	0.96	0.92	0.75	0.62	2.50	1.00
Type B, Style 2															
10 (0.1900)	24	…	…	1.01	0.95	0.78	0.72	0.14	0.11	0.39	0.36	0.28	0.22	1.25	0.50
1/4 (0.2500)	20	…	…	1.22	1.16	0.94	0.88	0.16	0.13	0.47	0.44	0.34	0.28	2.00	0.50
5/16 (0.3125)	18	…	…	1.43	1.37	1.09	1.03	0.17	0.14	0.55	0.52	0.41	0.34	2.00	0.50
3/8 (0.3750)	16	…	…	1.63	1.57	1.25	1.19	0.18	0.15	0.63	0.60	0.47	0.41	2.00	0.50

All dimensions in inches. Sizes shown in **bold face** are preferred.

[1]Plain point, unless alternate point from styles shown in Table 8 is specified by user.

[a] Where specifyin nominal size in decimals, zeros in the fourth decimal place are omitted.

[b] Hvy. = Heavy; Lgt. = Light; Reg. = Regular.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Types C and D Wing Screws
ANSI B18.17-1968, R1983



Style 1 Style 2

TYPE C



TYPE D

Nominal Size or Basic Screw Diameter[a]	Thds. per Inch	A Wing Spread Max	A Wing Spread Min	B Wing Height Max	B Wing Height Min	C Wing Thick. Max	C Wing Thick. Min	E Boss Dia. Max	E Boss Dia. Min	F Boss Dia. Max	F Boss Dia. Min	G Height Max	G Height Min	L Practical Screw Lengths Max	L Practical Screw Lengths Min
Type C, Style 1															
6 (0.1380)	32	0.85	0.83	0.45	0.43	0.15	0.12	…	…	0.41	0.39	0.12	0.07	0.75	0.25
8 (0.1640)	32	0.85	0.83	0.45	0.43	0.15	0.12	…	…	0.41	0.39	0.12	0.07	1.00	0.38
10 (0.1900)	24, 32	0.85	0.83	0.45	0.43	0.15	0.12	…	…	0.41	0.39	0.12	0.07	1.25	0.38
1/4 (0.2500)	20	1.08	1.05	0.56	0.53	0.17	0.14	…	…	0.46	0.44	0.12	0.07	1.50	0.50
5/16 (0.3125)	18	1.23	1.20	0.64	0.62	0.22	0.19	…	…	0.51	0.49	0.14	0.10	1.50	0.50
3/8 (0.3750)	16	1.45	1.42	0.74	0.72	0.24	0.21	…	…	0.63	0.62	0.15	0.12	1.50	0.50
Type C, Style 2															
6 (0.1380)	32	0.85	0.83	0.43	0.42	0.14	0.12	0.38	0.36	0.41	0.40	0.20	0.18	1.00	0.25
8 (0.1640)	32	0.85	0.83	0.43	0.42	0.14	0.12	0.38	0.36	0.41	0.40	0.20	0.18	1.00	0.38
10 (0.1900)	24, 32	0.85	0.83	0.43	0.42	0.14	0.12	0.38	0.36	0.41	0.40	0.20	0.18	2.00	0.38
1/4 (0.2500)	20	1.08	1.05	0.57	0.53	0.16	0.14	0.44	0.42	0.48	0.46	0.23	0.21	2.50	0.50
5/16 (0.3125)	18	1.23	1.20	0.64	0.62	0.20	0.18	0.50	0.49	0.57	0.55	0.26	0.24	3.00	0.50
3/8 (0.3750)	16	1.45	1.42	0.74	0.72	0.23	0.21	0.62	0.60	0.69	0.67	0.29	0.27	3.00	0.75
7/16 (0.4375)	14	1.89	1.86	0.91	0.90	0.29	0.28	0.75	0.73	0.83	0.82	0.38	0.37	4.00	1.00
1/2 (0.5000)	13	1.89	1.86	0.91	0.90	0.29	0.28	0.75	0.73	0.83	0.82	0.38	0.37	4.00	1.00
Type D															
6 (0.1380)	32	0.78	0.72	0.40	0.34	0.18	0.12	0.35	0.31	0.40	0.34	0.21	0.14	0.75	0.25
8 (0.1640)	32	0.78	0.72	0.40	0.34	0.18	0.12	0.35	0.31	0.40	0.34	0.21	0.14	0.75	0.38
10 (0.1900)	24	0.90	0.84	0.46	0.40	0.21	0.15	0.35	0.31	0.53	0.47	0.22	0.16	1.00	0.38
12 (0.2160)	24	1.09	1.03	0.46	0.40	0.26	0.20	0.44	0.39	0.61	0.55	0.24	0.18	1.00	0.38
1/4 (0.2500)	20	1.09	1.03	0.46	0.40	0.26	0.20	0.47	0.43	0.61	0.55	0.24	0.18	1.50	0.50
5/16 (0.3125)	18	1.31	1.25	0.62	0.56	0.29	0.23	0.57	0.53	0.68	0.62	0.29	0.23	1.50	0.50
3/8 (0.3750)	16	1.31	1.25	0.62	0.56	0.29	0.23	0.63	0.59	0.68	0.62	0.29	0.23	2.00	0.75

All dimensions in inches.

[1]Plain point, unless alternate point from styles shown in Table 8 is specified by user.

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.

Wing Screw and Thumb Screw Designation.— When specifying wing and thumb screws, the following data should be included in the designation and should appear in the following sequence: nominal size (number, fraction or decimal equivalent), threads per inch, length (fractions or decimal equivalents), type, style and/or series, point (if other than plain point), materials, and finish.

Copyright 2004, Industrial Press, Inc., New York, NY

Examples: 10—32 × 1¼, Thumb Screw, Type A, Regular, Steel, Zinc Plated.
0.375—16 × 2.00, Wing Screw, Type B, Style 2, Steel, Cadmium Plated.
0.250—20 × 1.50, Wing Screw, Type C, Style 2, Zinc Alloy Wings, Steel Shank, Brass Plated.

Table 7. American National Standard Types A and B Thumb Screws
ANSI B18.17-1968, R1983



TYPE A TYPE B

Nominal Size or Basic Screw Diameter[a]	Thds. per Inch	A Head Width Max	A Head Width Min	B Head Height Max	B Head Height Min	C Head Thick. Max	C Head Thick. Min	C′ Head Thick. Max	C′ Head Thick. Min	E Shoulder Diameter Max	E Shoulder Diameter Min	L Practical Screw Lengths Max	L Practical Screw Lengths Min
Type A, Regular													
6 (0.1380)	32	0.31	0.29	0.33	0.31	0.05	0.04	…	…	0.25	0.23	0.75	0.25
8 (0.1640)	32	0.36	0.34	0.38	0.36	0.06	0.05	…	…	0.31	0.29	0.75	0.38
10 (0.1900)	24, 32	0.42	0.40	0.48	0.46	0.06	0.05	…	…	0.35	0.32	1.00	0.38
12 (0.2160)	24	0.48	0.46	0.54	0.52	0.06	0.05	…	…	0.40	0.38	1.00	0.38
¼ (0.2500)	20	0.55	0.52	0.64	0.61	0.07	0.05	…	…	0.47	0.44	1.50	0.50
5/16 (0.3125)	18	0.70	0.67	0.78	0.75	0.09	0.07	…	…	0.59	0.56	1.50	0.50
⅜ (0.3750)	16	0.83	0.80	0.95	0.92	0.11	0.09	…	…	0.76	0.71	2.00	0.75
Type A, Heavy													
10 (0.1900)	24	0.89	0.83	0.84	0.72	0.18	0.16	0.10	0.08	0.33	0.31	2.00	0.50
¼ (0.2500)	20	1.05	0.99	0.94	0.81	0.24	0.22	0.10	0.08	0.40	0.38	3.00	0.50
5/16 (0.3125)	18	1.21	1.15	1.00	0.88	0.27	0.25	0.11	0.09	0.46	0.44	4.00	0.50
⅜ (0.3750)	16	1.41	1.34	1.16	1.03	0.30	0.28	0.11	0.09	0.55	0.53	4.00	0.50
7/16 (0.4375)	14	1.59	1.53	1.22	1.09	0.36	0.34	0.13	0.11	0.71	0.69	2.50	1.00
½ (0.5000)	13	1.81	1.72	1.28	1.16	0.40	0.38	0.14	0.12	0.83	0.81	3.00	1.00
Type B, Regular													
6 (0.1380)	32	0.45	0.43	0.28	0.26	0.08	0.06	0.03	0.02	…	…	1.00	0.25
8 (0.1640)	32	0.51	0.49	0.32	0.30	0.09	0.07	0.04	0.02	…	…	1.00	0.38
10 (0.1900)	24, 32	0.58	0.54	0.39	0.36	0.10	0.08	0.05	0.03	…	…	2.00	0.38
12 (0.2160)	24	0.71	0.67	0.45	0.43	0.11	0.09	0.05	0.03	…	…	2.00	0.38
¼ (0.2500)	20	0.83	0.80	0.52	0.48	0.16	0.14	0.06	0.03	…	…	2.50	0.50
5/16 (0.3125)	18	0.96	0.91	0.64	0.60	0.17	0.14	0.09	0.06	…	…	3.00	0.50
⅜ (0.3750)	16	1.09	1.03	0.71	0.67	0.22	0.18	0.11	0.08	…	…	3.00	0.75
7/16 (0.4375)	14	1.40	1.35	0.96	0.91	0.27	0.24	0.14	0.11	…	…	4.00	1.00
½ (0.5000)	13	1.54	1.46	1.09	1.03	0.33	0.29	0.15	0.11	…	…	4.00	1.00
Type B, Heavy													
10 (0.1900)	24	0.89	0.83	0.78	0.66	0.18	0.16	0.08	0.06	…	…	2.00	0.50
¼ (0.2500)	20	1.05	0.99	0.81	0.72	0.24	0.22	0.11	0.09	…	…	3.00	0.50
5/16 (0.3125)	18	1.21	1.15	0.88	0.78	0.27	0.25	0.11	0.09	…	…	4.00	0.50
⅜ (0.3750)	16	1.41	1.34	0.94	0.84	0.30	0.28	0.14	0.12	…	…	4.00	0.50
7/16 (0.4375)	14	1.59	1.53	1.00	0.91	0.36	0.34	0.14	0.12	…	…	3.00	1.00
½ (0.5000)	13	1.81	1.72	1.09	0.97	0.40	0.38	0.18	0.16	…	…	3.00	1.00

[a] Where specifying nominal size in decimals, zeroes in fourth decimal place are omitted.
All dimensions in inches.
[1] Plain point, unless alternate point from styles shown in Table 8 is specified by user.

Lengths of Wing and Thumb Screws.— The length of wing or thumb screws is measured parallel to the axis of the screw from the intersection of the head or shoulder with the shank to the extreme point of the screw. Standard length increments are as follows: For

Copyright 2004, Industrial Press, Inc., New York, NY

sizes No. 4 through ¼ inch and for nominal lengths of 0.25 to 0.75 inch, 0.12-inch increments; from 0.75- to 1.50-inch lengths, 0.25-inch increments; and for 1.50- to 3.00-inch lengths, 0.50-inch increments. For sizes 5/16 through ½ inch and for 0.50- to 1.50-inch lengths, 0.25-inch increments; for 1.50- to 3.00-inch lengths, 0.50-inch increments; and for 3.00- to 4.00-inch lengths, 1.00-inch increments.

Threads for Wing Screws and Thumb Screws.— Threads for all types of wing screws and thumb screws are in conformance with ANSI Standard Unified Thread, Class 2A. For threads with an additive finish the Class 2A maximum diameters apply to an unplated screw or to a screw before plating, whereas the basic diameters (Class 2A maximum diameters plus the allowance) apply to a screw after plating. All types of wing and thumb screws should have complete (full form) threads extending as close to the head or shoulder as practicable.

Points for Wing and Thumb Screws.— Wing and thumb screws are normally supplied with plain points (sheared ends). Where so specified, these screws may be obtained with cone, cup, dog, flat or oval points as shown in Table 8.

Table 8. American National Standard Alternate Points for Wing and Thumb Screws
ANSI B18.17-1968, R1983



CUP POINT



CONE POINT



OVAL POINT



FLAT POINT



DOG POINT

Nominal Size or Basic Screw Diamter[a]	O		P		Q		R	
	Cup and Flat Point Diameter		Dog Point[b]				Oval Point Radius	
			Diameter		Length			
	Max	Min	Max	Min	Max	Min	Max	Min
4 (0.1120)	0.061	0.051	0.075	0.070	0.061	0.051	0.099	0.084
6 (0.1380)	0.074	0.064	0.092	0.087	0.075	0.065	0.140	0.109
8 (0.1640)	0.087	0.076	0.109	0.103	0.085	0.075	0.156	0.125
10 (0.1900)	0.102	0.088	0.127	0.120	0.095	0.085	0.172	0.141
12 (0.2160)	0.115	0.101	0.144	0.137	0.115	0.105	0.188	0.156
¼ (0.2500)	0.132	0.118	0.156	0.149	0.130	0.120	0.219	0.188
5/16 (0.3125)	0.172	0.156	0.203	0.195	0.161	0.151	0.256	0.234
3/8 (0.3750)	0.212	0.194	0.250	0.241	0.193	0.183	0.312	0.281
7/16 (0.4375)	0.252	0.232	0.297	0.287	0.224	0.214	0.359	0.328
½ (0.5000)	0.291	0.270	0.344	0.334	0.255	0.245	0.406	0.375
5/8 (0.6250)	0.371	0.347	0.469	0.456	0.321	0.305	0.500	0.469

[a] Where specifying nominal size in decimals, zeros in the fourth decimal place are omitted.

[b] The axis of dog points shall not be eccentric with the axis of the screw by more than 3 per cent of the basic screw diameter or 0.005 in., whichever is the smaller.

All dimensions in inches.

[1] The external point angles specified shall apply to those portions of the angles which lie below the thread root diameter, it being recognized the angle within the thread profile may be varied due to the manufacturing processes.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

THREADS AND THREADING

SCREW THREAD SYSTEMS

1725 Screw Thread Forms
1725 V-Thread, Sharp V-thread
1725 US Standard Screw Thread
1725 Unified Screw Thread Forms
1726 International Metric Thread
1727 Definitions of Screw Threads

UNIFIED SCREW THREADS

1732 American Standard for Unified Screw Threads
1732 Revised Standard
1732 Advantages of Unified Threads
1732 Thread Form
1733 Internal and External Screw Thread Design Profile
1733 Thread Series
1734 Inch Screw Thread
1735 Diameter-Pitch Combination
1736 Standard Series Combinations
1763 Coarse-Thread Series
1764 Fine-Thread Series
1764 Extra-Fine-Thread Series
1765 Constant Pitch Series
1766 4-Thread Series
1767 6-Thread Series
1768 8-Thread Series
1769 12-Thread Series
1770 16-Thread Series
1771 20-Thread Series
1772 28-Thread Series
1773 Thread Classes
1773 Coated 60-deg. Threads
1775 Screw Thread Selection
1775 Pitch Diameter Tolerance
1775 Screw Thread Designation
1776 Designating Coated Threads
1776 Designating UNS Threads
1776 Hole Sizes for Tapping
1776 Minor Diameter Tolerance
1777 Unified Miniature Screw Thread
1777 Basic Thread Form
1778 Design Thread Form
1779 Design Form Dimensions
1779 Formulas for Basic Dimensions
1780 Limits of Size and Tolerances
1781 Minimum Root Flats
1782 British Standard Unified Screw Threads UNJ Profile

METRIC SCREW THREADS

1783 American Standard Metric Screw Threads M Profile
1783 Comparison with Inch Threads
1783 Interchangeability
1783 Definitions
1784 Basic M Profile
1784 M Crest and Root Form
1785 General Symbols
1785 M Profile Screw Thread Series
1785 Mechanical Fastener Coarse Pitch
1786 M Profile Data
1787 Limits and Fits
1793 Dimensional Effect of Coating
1793 Formulas for M Profile
1797 Tolerance Grade Comparisons
1797 M Profile Limiting Dimension
1798 Internal Metric Thread
1800 External Metric Thread
1804 American Standard Metric Screw Threads MJ Profile
1804 Diameter-Pitch Combinations
1807 Trapezoidal Metric Thread
1807 Comparison of ISO and DIN Standards
1813 Trapezoidal Metric Thread
1814 ISO Miniature Screw Threads
1814 British Standard ISO Metric Screw Threads
1814 Basic Profile Dimensions
1815 Tolerance System
1815 Fundamental Deviations
1816 Tolerance Grades
1816 Tolerance Positions
1816 Tolerance Classes
1817 Lengths of Thread Engagements
1817 Design Profiles
1817 Designation
1818 Fundamental Deviation Formulas
1819 Crest Diameter Tolerance Formulas
1819 Limits and Tolerances
1822 Diameter/Pitch Combinations
1822 Limits and Tolerances for Finished Uncoated Threads
1823 Diameter/Pitch Combinations
1824 Comparison of Various Metric Thread Systems
1824 Comparison of Maximum Metal Dimension

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

THREADS AND THREADING

ACME SCREW THREADS

1825 General Purpose Acme Threads
1825 Acme Thread Form
1827 Acme Thread Abbreviations
1827 Designation
1827 Basic Dimensions
1827 Formulas for Diameters
1827 Limiting Dimensions
1827 Single-Start Screw Thread Data
1827 Pitch Diameter Allowances
1827 Multiple Start Acme Threads
1832 Pitch Diameter Tolerances
1832 Centralizing Acme Threads
1834 Basic Dimensions
1836 Formulas for Diameters
1836 Limiting Dimensions
1836 Screw Thread Data
1836 Pitch Diameter Allowances
1837 Pitch Diameter Tolerances
1837 Tolerances and Allowances
1843 Designation
1843 Acme Centralizing Thread
1843 Stub Acme Threads
1843 Basic Dimensions
1843 Formulas for Diameters
1843 Limiting Dimensions
1846 Stub Acme Thread Designations
1846 Alternative Stub Acme Threads
1846 Former 60-Degree Stub Thread
1848 Square Thread
1848 10-Degree Square Thread

BUTTRESS THREADS

1849 Threads of Buttress Form
1849 British Standard Buttress Threads
1849 Lowenherz or Löwenherz Thread
1850 Buttress Inch Screw Threads
1850 American National Standard Buttress Inch Screw Threads
1850 Pitch Combinations
1850 Basic Dimensions
1850 Buttress Thread
1850 Symbols and Form
1851 Buttress Thread Tolerances
1851 Class 2 Tolerances
1855 Allowances for Easy Assembly
1855 External Thread Allowances
1856 Buttress Thread Designations
1856 Designation Sequence

WHITWORTH THREADS

1857 British Standard Whitworth (BSW) and Fine (BSF) Threads
1857 Standard Thread Form
1857 Whitworth Standard Thread Form
1857 Tolerance Formulas
1858 Basic Dimensions

PIPE AND HOSE THREADS

1860 American National Standard Pipe Threads
1860 Thread Designation and Notation
1860 Taper Pipe Thread
1861 Basic Dimensions
1862 Engagement
1862 Tolerances on Thread Elements
1863 Limits on Crest and Root
1864 Pipe Couplings
1864 Railing Joint
1864 Straight Pipe Threads
1864 Mechanical Joints
1866 Dryseal Pipe Thread
1866 Limits on Crest and Root
1866 Types of Dryseal Pipe Thread
1866 Limitation of Assembly
1868 Tap Drill Sizes
1868 Special Dryseal Threads
1869 Limitations for Combinations
1869 British Standard Pipe Threads
1869 Non-pressure-tight Joints
1870 Basic Sizes
1870 Pressure-tight Joints
1871 Limits of Size
1872 Hose Coupling Screw Threads
1872 ANSI Standard
1873 Hose Coupling Threads
1874 Screw Thread Length
1874 Fire Hose Connection
1875 Basic Dimensions
1876 Limits of Size

OTHER THREADS

1877 Interference-Fit Threads
1878 Design and Application Data
1879 External Thread Dimension
1879 Internal Thread Dimension
1880 Engagement Lengths
1881 Allowances for Coarse Thread
1881 Tolerances for Coarse Thread

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

THREADS AND THREADING

OTHER THREADS

(Continued)

1882 Variations in Lead and Diameter
1883 Spark Plug Threads
1883 BS Spark Plugs
1883 SAE Spark Plugs
1884 Lamp Base and Socket Threads
1885 Instrument and Microscope Threads
1885 British Association Thread
1886 Instrument Makers' Screw Thread
1886 Microscope Objective Thread
1889 Swiss Screw Thread
1890 Historical and Miscellaneous
1890 Aero-Thread
1890 Briggs Pipe Thread
1890 Casing Thread
1891 Cordeaux Thread
1891 Dardelet Thread
1891 "Drunken" Thread
1891 Echols Thread
1891 French Thread (S.F.)
1891 Harvey Grip Thread
1892 Lloyd & Lloyd Thread
1892 Lock-Nut Pipe Thread
1892 Philadelphia Carriage Bolt Thread
1892 SAE Standard Screw Thread
1892 Sellers Screw Thread

MEASURING SCREW THREADS

1893 Measuring Screw Threads
1893 Pitch and Lead of Screw Threads
1893 Thread Micrometers
1894 Ball-point Micrometers
1894 Three-wire Method
1895 Classes of Formulas
1895 Screw Thread Profiles
1895 Accuracy of Formulas
1896 Best Wire Sizes
1897 Measuring Wire Accuracy
1897 Measuring or Contact Pressure
1897 Three-Wire Formulas
1898 NIST General Formula
1899 Formulas for Pitch Diameters
1899 Effect of Small Thread Angle
1901 Dimensions Over Wires
1901 Formula Including Lead Angle
1902 Measuring Whitworth Threads
1903 Buckingham Exact Formula
1904 Accuracy of Formulas
Acme and Stub Acme Thread

MEASURING SCREW THREADS

(Continued)

1905 Checking Pitch Diameter
1905 Checking Thread Thickness
1906 Wire Sizes
1906 Checking Thread Angle
1907 Best Wire Diameters
1909 Taper Screw Threads
1910 Buttress Threads
1911 Thread Gages
1911 Thread Gage Classification
1911 Gages for Unified Inch Threads
1914 Thread Forms of Gages
1914 Thread Gage Tolerances
1916 Tolerances for Cylindrical Gages
1918 Formulas for Limits

TAPPING AND THREAD CUTTING

1919 Selection of Taps
1921 Tap Rake Angles
1921 Cutting Speed
1921 Tapping Specific Materials
1924 Diameter of Tap Drill
1925 Hole Size Limits
1933 Tap Drill Sizes
1934 Tap Drills and Clearance Drills
1934 Tolerances of Tapped Holes
1935 Hole Sizes before Tapping
1936 Miniature Screw Threads
1937 Tapping Drill Sizes
1937 ISO Metric Threads
1938 Clearance Holes
1939 Cold Form Tapping
1940 Core Hole Sizes
1941 Tap Drill Sizes
1941 Removing a Broken Tap
1941 Tap Drills for Pipe Taps
1941 Power for Pipe Taps
1942 High-Speed CNC Tapping
1943 Coolant for Tapping
1943 Combined Drilling and Tapping
1944 Relief Angles for Cutting Tools
1946 Lathe Change Gears
1946 Change Gears for Thread Cutting
1946 Compound Gearing
1946 Fractional Threads
1947 Change Gears for Metric Pitches
1947 Change Gears for Fractional Ratios

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

THREADS AND THREADING

TAPPING AND THREAD CUTTING

(Continued)

1948 Quick-Change Gearbox Output
1950 Finding Accurate Gear Ratios
1950 Lathe Change-gears
1951 Relieving Helical-Fluted Hobs

THREAD ROLLING

1952 Thread-Rolling Machine
1952 Flat-Die Type
1952 Cylindrical-Die Type
1952 Rate of Production
1953 Precision Thread Rolling
1953 Steels for Thread Rolling
1953 Diameter of Blank
1953 Automatic Screw Machines
1954 Factors Governing the Diameter
1954 Diameter of Threading Roll
1954 Kind of Thread on Roll
1955 Application of Thread Roll
1955 Thread Rolling Speeds and Feeds

THREAD GRINDING

1957 Thread Grinding
1957 Wheels for Thread Grinding
1957 Single-Edge Wheel
1958 Edges for Roughing and Finishing
1958 Multi-ribbed Wheels
1959 Ribbed Wheel for Fine Pitches
1959 Solid Grinding Threads
1959 Number of Wheel Passes
1959 Wheel and Work Rotation
1960 Wheel Speeds
1960 Work Speeds
1960 Truing Grinding Wheels
1960 Wheel Hardness or Grade
1961 Grain Size
1961 Grinding by Centerless Method

THREAD MILLING

1962 Thread Milling
1962 Single-cutter Method
1962 Multiple-cutter Method
1963 Planetary Method
1963 Classes of Work
1964 Pitches of Die-cut Threads
1964 Changing Pitch of Screw
1964 Helical Milling
1964 Lead of a Milling Machine

THREAD MILLING

(Continued)

1965 Change Gears for Helical Milling
1965 Short-lead Milling
1965 Helix
1966 Helix Angles
1967 Change Gears for Different Leads
1977 Lead of Helix
1980 Change Gears and Angles
Determining Helix Angle
1981 For Given Lead and Diameter
1982 For Given Angle
1982 For Given Lead
1982 And Lead Given DP and Teeth
1982 Lead of Tooth Given Pitch Radius and Helix Angle

SIMPLE, COMPOUND, DIFFERENTIAL, AND BLOCK INDEXING

1983 Milling Machine Indexing
1983 Hole Circles
1983 Holes in Brown & Sharpe
1983 Holes in Cincinnati
1983 Simple Indexing
1984 Compound Indexing
1985 Simple and Compound Indexing
1990 Angular Indexing
1990 Tables for Angular Indexing
1991 Angular Values of Cincinnati Index
1992 Accurate Angular Indexing
2007 Indexing for Small Angles
2008 Differential Indexing
2008 Ratio of Gearing
2009 To Find the Indexing Movement
2009 Use of Idler Gears
2009 Compound Gearing
2010 Check Number of Divisions
2011 Simple and Different Indexing
2017 Indexing Movements of Plate
2018 Indexing Movements for High Numbers
2021 Indexing Tables
2021 Block or Multiple Indexing
2023 Indexing Movements for 60-Tooth
2024 Linear Indexing for Rack Cutting
2024 Linear Indexing Movements
2025 Counter Milling

Copyright 2004, Industrial Press, Inc., New York, NY

SCREW THREAD SYSTEMS

Screw Thread Forms

Of the various screw thread forms which have been developed, the most used are those having symmetrical sides inclined at equal angles with a vertical center line through the thread apex. Present-day examples of such threads would include the Unified, the Whitworth and the Acme forms. One of the early forms was the Sharp V which is now used only occasionally. Symmetrical threads are relatively easy to manufacture and inspect and hence are widely used on mass-produced general-purpose threaded fasteners of all types. In addition to general-purpose fastener applications, certain threads are used to repeatedly move or translate machine parts against heavy loads. For these so-called translation threads a stronger form is required. The most widely used translation thread forms are the square, the Acme, and the buttress. Of these, the square thread is the most efficient, but it is also the most difficult to cut owing to its parallel sides and it cannot be adjusted to compensate for wear. Although less efficient, the Acme form of thread has none of the disadvantages of the square form and has the advantage of being somewhat stronger. The buttress form is used for translation of loads in one direction only because of its non-symmetrical form and combines the high efficiency and strength of the square thread with the ease of cutting and adjustment of the Acme thread.

V-Thread, Sharp V-thread.— The sides of the thread form an angle of 60 degrees with each other. The top and bottom or root of this thread form are theoretically sharp, but in actual practice the thread is made with a slight flat, owing to the difficulty of producing a perfectly sharp edge and because of the tendency of such an edge to wear away or become battered. This flat is usually equal to about one twenty-fifth of the pitch, although there is no generally recognized standard.



Owing to the difficulties connected with the V-thread, the tap manufacturers agreed in 1909 to discontinue the making of sharp V-thread taps, except when ordered. One advantage of the V-thread is that the same cutting tool may be used for all pitches, whereas, with the American Standard form, the width of the point or the flat varies according to the pitch.

The V-thread is regarded as a good form where a steam-tight joint is necessary, and many of the taps used on locomotive work have this form of thread. Some modified V-threads, for locomotive boiler taps particularly, have a depth of 0.8 × pitch.

The American Standard screw thread is used largely in preference to the sharp V-thread because it has several advantages; see *American Standard for Unified Screw Threads*. If p = pitch of thread, and d depth of thread, then

$$d = p \times \cos 30 \text{ deg.} = 0.866 \times p = \frac{0.866}{\text{No. of threads per inch}}$$

United States Standard Screw Thread.— William Sellers of Philadelphia, in a paper read before the Franklin Institute in 1864, originally proposed the screw thread system that later became known as the U. S. Standard system for screw threads. A report was made to the United States Navy in May, 1868, in which the Sellers system was recommended as a standard for the Navy Department, which accounts for the name of U. S. Standard. The American Standard Screw Thread system is a further development of the United States Standard. The thread form which is known as the American (National) form is the same as the United States Standard form. See *American Standard for Unified Screw Threads*.

American National and Unified Screw Thread Forms.— The American National form (formerly known as the United States Standard) was used for many years for most screws, bolts, and miscellaneous threaded products produced in the United States. The American

Copyright 2004, Industrial Press, Inc., New York, NY

National Standard for Unified Screw Threads now in use includes certain modifications of the former standard as is explained below and on page 1732. The basic profile is shown in Fig. 1 and is identical for both UN and UNR screw threads. In this figure H is the height of a sharp V-thread, P is the pitch, D and d are the basic major diameters, D_2 and d_2 are the basic pitch diameters, and D_1 and d_1 are the basic minor diameters. Capital letters are used to designate the internal thread dimensions (D, D_2, D_1), and lowercase letters to designate the external thread dimensions (d, d_2, d_1). Definitions of *Basic Size* and *Basic Profile of Thread* are given on page 1727.



Fig. 1. Basic Profile of UN and UNF Screw Threads

In the past, other symbols were used for some of the thread dimensions illustrated above. These symbols were changed to conform with current practice in nomenclature as defined in ANSI/ASME B1.7M, "Nomenclature, Definitions, and Letter Symbols for Screw Threads." The symbols used above are also in accordance with termonology and symbols used for threads of the ISO metric thread system.

International Metric Thread System.— The Système Internationale (S.I.) Thread was adopted at the International Congress for the standardization of screw threads held in Zurich in 1898. The thread form is similar to the American standard (formerly U.S. Standard), excepting the depth which is greater. There is a clearance between the root and mating crest fixed at a maximum of $\frac{1}{16}$ the height of the fundamental triangle or 0.054 × pitch. A rounded root profile is recommended. The angle in the plane of the axis is 60 degrees and the crest has a flat like the American standard equal to 0.125 × pitch. This system formed the basis of the normal metric series (ISO threads) of many European countries, Japan, and many other countries, including metric thread standards of the United States.

Depth $d = 0.7035\,P$ max.; $0.6855\,P$ min.
Flat $f = 0.125\,P$
Radius $r = 0.0633\,P$ max.; $0.054\,P$ min.
Tap drill dia = major dia.– pitch



International Metric Fine Thread: The International Metric Fine Thread form of thread is the same as the International system but the pitch for a given diameter is smaller.

German Metric Thread Form: The German metric thread form is like the International Standard but the thread depth = $0.6945\,P$. The root radius is the same as the maximum for the International Standard or $0.0633\,P$.

Copyright 2004, Industrial Press, Inc., New York, NY

ISO Metric Thread System.— ISO refers to the International Organization for Standardization, a worldwide federation of national standards bodies (for example, the American National Standards Institute is the ISO national body representing the United States) that develops standards on a very wide variety of subjects.

The basic profile of ISO metric threads is specified in ISO 68 and shown in Fig. 2. The basic profile of this thread is very similar to that of the Unified thread, and as previously discussed, H is the height of a sharp V-thread, P is the pitch, D and d are the basic major diameters, D_2 and d_2 are the basic pitch diameters, and D_1 and d_1 are the basic minor diameters. Here also, capital letters designate the internal thread dimensions (D, D_2, D_1), and lowercase letters designate the external thread dimensions (d, d_2, d_1). This metric thread is discussed in detail in the section *METRIC SCREW THREADS* starting on page 1783.



$$H = \frac{\sqrt{3}}{2} \times P = 0.866025404P$$

$0.125H = 0.108253175P$ $0.250H = 0.216506351P$ $0.375H = 0.324759526P$ $0.625H = 0.541265877P$

Fig. 2. ISO 68 Basic Profile

Definitions of Screw Threads

The following definitions are based on American National Standard ANSI/ASME B1.7M-1984 (R2001) "Nomenclature, Definitions, and Letter Symbols for Screw Threads," and refer to both straight and taper threads.

Actual Size: An actual size is a measured size.

Allowance: An allowance is the prescribed difference between the design (maximum material) size and the basic size. It is numerically equal to the absolute value of the ISO term *fundamental deviation*.

Axis of Thread: Thread axis is coincident with the axis of its pitch cylinder or cone.

Basic Profile of Thread: The basic profile of a thread is the cyclical outline, in an axial plane, of the permanently established boundary between the provinces of the external and internal threads. All deviations are with respect to this boundary.

Basic Size: The basic size is that size from which the limits of size are derived by the application of allowances and tolerances.

Bilateral Tolerance: This is a tolerance in which variation is permitted in both directions from the specified dimension.

Black Crest Thread: This is a thread whose crest displays an unfinished cast, rolled, or forged surface.

Blunt Start Thread: "Blunt start" designates the removal of the incomplete thread at the starting end of the thread. This is a feature of threaded parts that are repeatedly assembled

Copyright 2004, Industrial Press, Inc., New York, NY

by hand, such as hose couplings and thread plug gages, to prevent cutting of hands and crossing of threads. It was formerly known as a Higbee cut.

Chamfer: This is a conical surface at the starting end of a thread.

Class of Thread: The class of a thread is an alphanumerical designation to indicate the standard grade of tolerance and allowance specified for a thread.

Clearance Fit: This is a fit having limits of size so prescribed that a clearance always results when mating parts are assembled at their maximum material condition.

Complete Thread: The complete thread is that thread whose profile lies within the size limits. (See also *Effective Thread* and *Length of Complete Thread*.) *Note:* Formerly in pipe thread terminology this was referred to as "the perfect thread" but that term is no longer considered desirable.

Crest: This is that surface of a thread which joins the flanks of the thread and is farthest from the cylinder or cone from which the thread projects.

Crest Truncation: This is the radial distance between the sharp crest (crest apex) and the cylinder or cone that would bound the crest.

Depth of Thread Engagement: The depth (or height) of thread engagement between two coaxially assembled mating threads is the radial distance by which their thread forms overlap each other.

Design Size: This is the basic size with allowance applied, from which the limits of size are derived by the application of a tolerance. If there is no allowance, the design size is the same as the basic size.

Deviation: Deviation is a variation from an established dimension, position, standard, or value. In ISO usage, it is the algebraic difference between a size (actual, maximum, or minimum) and the corresponding basic size. The term deviation does not necessarily indicate an error. (See also *Error*.)

Deviation, Fundamental (ISO term): For standard threads, the fundamental deviation is the upper or lower deviation closer to the basic size. It is the upper deviation *es* for an external thread and the lower deviation *EI* for an internal thread. (See also *Allowance* and *Tolerance Position*.)

Deviation, Lower (ISO term): The algebraic difference between the minimum limit of size and the basic size. It is designated *EI* for internal and *ei* for external thread diameters.

Deviation, Upper (ISO term): The algebraic difference between the maximum limit of size and the basic size. It is designated *ES* for internal and *es* for external thread diameters.

Dimension: A numerical value expressed in appropriate units of measure and indicated on drawings along with lines, symbols, and notes to define the geometrical characteristic of an object.

Effective Size: See *Pitch Diameter, Functional Diameter*.

Effective Thread: The effective (or useful) thread includes the complete thread, and those portions of the incomplete thread which are fully formed at the root but not at the crest (in taper pipe threads it includes the so-called black crest threads); thus excluding the vanish thread.

Error: The algebraic difference between an observed or measured value beyond tolerance limits, and the specified value.

External Thread: A thread on a cylindrical or conical external surface.

Fit: Fit is the relationship resulting from the designed difference, before assembly, between the sizes of two mating parts which are to be assembled.

Flank: The flank of a thread is either surface connecting the crest with the root. The flank surface intersection with an axial plane is theoretically a straight line.

Flank Angle: The flank angles are the angles between the individual flanks and the perpendicular to the axis of the thread, measured in an axial plane. A flank angle of a symmetrical thread is commonly termed the half-angle of thread.

Flank Diametral Displacement: In a boundary profile defined system, flank diametral displacement is twice the radial distance between the straight thread flank segments of the

Copyright 2004, Industrial Press, Inc., New York, NY

maximum and minimum boundary profiles. The value of flank diametral displacement is equal to pitch diameter tolerance in a pitch line reference thread system.

Height of Thread: The height (or depth) of thread is the distance, measured radially, between the major and minor cylinders or cones, respectively.

Helix Angle: On a straight thread, the helix angle is the angle made by the helix of the thread and its relation to the thread axis. On a taper thread, the helix angle at a given axial position is the angle made by the conical spiral of the thread with the axis of the thread. The helix angle is the complement of the lead angle. (See also page 1966 for diagram.)

Higbee Cut: See *Blunt Start Thread*.

Imperfect Thread: See *Incomplete Thread*.

Included Angle: This is the angle between the flanks of the thread measured in an axial plane.

Incomplete Thread: A threaded profile having either crests or roots or both, not fully formed, resulting from their intersection with the cylindrical or end surface of the work or the vanish cone. It may occur at either end of the thread.

Interference Fit: A fit having limits of size so prescribed that an interference always results when mating parts are assembled.

Internal Thread: A thread on a cylindrical or conical internal surface.

Lead: Lead is the axial distance between two consecutive points of intersection of a helix by a line parallel to the axis of the cylinder on which it lies, i.e., the axial movement of a threaded part rotated one turn in its mating thread.

Lead Angle: On a straight thread, the lead angle is the angle made by the helix of the thread at the pitch line with a plane perpendicular to the axis. On a taper thread, the lead angle at a given axial position is the angle made by the conical spiral of the thread with the perpendicular to the axis at the pitch line.

Lead Thread: That portion of the incomplete thread that is fully formed at the root but not fully formed at the crest that occurs at the entering end of either an external or internal thread.

Left-hand Thread: A thread is a left-hand thread if, when viewed axially, it winds in a counterclockwise and receding direction. Left-hand threads are designated LH.

Length of Complete Thread: The axial length of a thread section having full form at both crest and root but also including a maximum of two pitches at the start of the thread which may have a chamfer or incomplete crests.

Length of Thread Engagement: The length of thread engagement of two mating threads is the axial distance over which the two threads, each having full form at both crest and root, are designed to contact. (See also *Length of Complete Thread*.)

Limits of Size: The applicable maximum and minimum sizes.

Major Clearance: The radial distance between the root of the internal thread and the crest of the external thread of the coaxially assembled designed forms of mating threads.

Major Cone: The imaginary cone that would bound the crests of an external taper thread or the roots of an internal taper thread.

Major Cylinder: The imaginary cylinder that would bound the crests of an external straight thread or the roots of an internal straight thread.

Major Diameter: On a straight thread the major diameter is that of the major cylinder. On a taper thread the major diameter at a given position on the thread axis is that of the major cone at that position. (See also *Major Cylinder* and *Major Cone*.)

Maximum Material Condition: (*MMC*): The condition where a feature of size contains the maximum amount of material within the stated limits of size. For example, minimum internal thread size or maximum external thread size.

Minimum Material Condition: (*Least Material Condition* (*LMC*)): The condition where a feature of size contains the least amount of material within the stated limits of size. For example, maximum internal thread size or minimum external thread size.

Minor Clearance: The radial distance between the crest of the internal thread and the root of the external thread of the coaxially assembled design forms of mating threads.

Copyright 2004, Industrial Press, Inc., New York, NY

Minor Cone: The imaginary cone that would bound the roots of an external taper thread or the crests of an internal taper thread.

Minor Cylinder: The imaginary cylinder that would bound the roots of an external straight thread or the crests of an internal straight thread.

Minor Diameter: On a straight thread the minor diameter is that of the minor cylinder. On a taper thread the minor diameter at a given position on the thread axis is that of the minor cone at that position. (See also *Minor Cylinder* and *Minor Cone*.)

Multiple-Start Thread: A thread in which the lead is an integral multiple, other than one, of the pitch.

Nominal Size: Designation used for general identification.

Parallel Thread: See *Screw Thread*.

Partial Thread: See *Vanish Thread*.

Pitch: The pitch of a thread having uniform spacing is the distance measured parallel with its axis between corresponding points on adjacent thread forms in the same axial plane and on the same side of the axis. Pitch is equal to the lead divided by the number of thread starts.

Pitch Cone: The pitch cone is an imaginary cone of such apex angle and location of its vertex and axis that its surface would pass through a taper thread in such a manner as to make the widths of the thread ridge and the thread groove equal. It is, therefore, located equidistantly between the sharp major and minor cones of a given thread form. On a theoretically perfect taper thread, these widths are equal to one-half the basic pitch. (See also *Axis of Thread* and *Pitch Diameter*.)

Pitch Cylinder: The pitch cylinder is an imaginary cylinder of such diameter and location of its axis that its surface would pass through a straight thread in such a manner as to make the widths of the thread ridge and groove equal. It is, therefore, located equidistantly between the sharp major and minor cylinders of a given thread form. On a theoretically perfect thread these widths are equal to one-half the basic pitch. (See also *Axis of Thread* and *Pitch Diameter*.)

Pitch Diameter: On a straight thread the pitch diameter is the diameter of the pitch cylinder. On a taper thread the pitch diameter at a given position on the thread axis is the diameter of the pitch cone at that position. *Note:* When the crest of a thread is truncated beyond the pitch line, the pitch diameter and pitch cylinder or pitch cone would be based on a theoretical extension of the thread flanks.

Pitch Diameter, Functional Diameter: The functional diameter is the pitch diameter of an enveloping thread with perfect pitch, lead, and flank angles and having a specified length of engagement. It includes the cumulative effect of variations in lead (pitch), flank angle, taper, straightness, and roundness. Variations at the thread crest and root are excluded. Other, nonpreferred terms are *virtual diameter, effective size, virtual effective diameter,* and *thread assembly diameter*.

Pitch Line: The generator of the cylinder or cone specified in *Pitch Cylinder* and *Pitch Cone*.

Right-hand Thread: A thread is a fight-hand thread if, when viewed axially, it winds in a clockwise and receding direction. A thread is considered to be right-hand unless specifically indicated otherwise.

Root: That surface of the thread which joins the flanks of adjacent thread forms and is immediately adjacent to the cylinder or cone from which the thread projects.

Root Truncation: The radial distance between the sharp root (root apex) and the cylinder or cone that would bound the root. See also *Sharp Root (Root Apex)*.

Runout: As applied to screw threads, unless otherwise specified, runout refers to circular runout of major and minor cylinders with respect to the pitch cylinder. Circular runout, in accordance with ANSI Y14.5M, controls cumulative variations of circularity and coaxiality. Runout includes variations due to eccentricity and out-of-roundness. The amount of runout is usually expressed in terms of full indicator movement (FIM).

Copyright 2004, Industrial Press, Inc., New York, NY

Screw Thread: A screw thread is a continuous and projecting helical ridge usually of uniform section on a cylindrical or conical surface.

Sharp Crest (Crest Apex): The apex formed by the intersection of the flanks of a thread when extended, if necessary, beyond the crest.

Sharp Root (Root Apex): The apex formed by the intersection of the adjacent flanks of adjacent threads when extended, if necessary, beyond the root.

Standoff: The axial distance between specified reference points on external and internal taper thread members or gages, when assembled with a specified torque or under other specified conditions.

Straight Thread: A straight thread is a screw thread projecting from a cylindrical surface.

Taper Thread: A taper thread is a screw thread projecting from a conical surface.

Tensile Stress Area: The tensile stress area is an arbitrarily selected area for computing the tensile strength of an externally threaded fastener so that the fastener strength is consistent with the basic material strength of the fastener. It is typically defined as a function of pitch diameter and/or minor diameter to calculate a circular cross section of the fastener correcting for the notch and helix effects of the threads.

Thread: A thread is a portion of a screw thread encompassed by one pitch. On a single-start thread it is equal to one turn. (See also *Threads per Inch* and *Turns per Inch*.)

Thread Angle: See *Included Angle*.

Thread Runout: See *Vanish Thread*.

Thread Series: Thread Series are groups of diameter/pitch combinations distinguished from each other by the number of threads per inch applied to specific diameters.

Thread Shear Area: The thread shear area is the total ridge cross-sectional area intersected by a specified cylinder with diameter and length equal to the mating thread engagement. Usually the cylinder diameter for external thread shearing is the minor diameter of the internal thread and for internal thread shearing it is the major diameter of the external thread.

Threads per Inch: The number of threads per inch is the reciprocal of the axial pitch in inches.

Tolerance: The total amount by which a specific dimension is permitted to vary. The tolerance is the difference between the maximum and minimum limits.

Tolerance Class: (*metric*): The tolerance class (metric) is the combination of a tolerance position with a tolerance grade. It specifies the allowance (fundamental deviation), pitch diameter tolerance (flank diametral displacement), and the crest diameter tolerance.

Tolerance Grade: (*metric*): The tolerance grade (metric) is a numerical symbol that designates the tolerances of crest diameters and pitch diameters applied to the design profiles.

Tolerance Limit: The variation, positive or negative, by which a size is permitted to depart from the design size.

Tolerance Position: (*metric*): The tolerance position (metric) is a letter symbol that designates the position of the tolerance zone in relation to the basic size. This position provides the allowance (fundamental deviation).

Total Thread: Includes the complete and all the incomplete thread, thus including the vanish thread and the lead thread.

Transition Fit: A fit having limits of size so prescribed that either a clearance or an interference may result when mating parts are assembled.

Turns per Inch: The number of turns per inch is the reciprocal of the lead in inches.

Unilateral Tolerance: A tolerance in which variation is permitted in one direction from the specified dimension.

Vanish Thread: (*Partial Thread, Washout Thread,* or *Thread Runout*): That portion of the incomplete thread which is not fully formed at the root or at crest and root. It is produced by the chamfer at the starting end of the thread forming tool.

Virtual Diameter: See *Pitch Diameter, Functional Diameter*.

Washout Thread: See *Vanish Thread*.

Copyright 2004, Industrial Press, Inc., New York, NY

UNIFIED SCREW THREADS

American Standard for Unified Screw Threads

American Standard B1.1-1949 was the first American standard to cover those Unified Thread Series agreed upon by the United Kingdom, Canada, and the United States to obtain screw thread interchangeability among these three nations. These Unified threads are now the basic American standard for fastening types of screw threads. In relation to previous American practice, Unified threads have substantially the same thread form and are mechanically interchangeable with the former American National threads of the same diameter and pitch.

The principal differences between the two systems lie in: 1) application of allowances; 2) variation of tolerances with size; 3) difference in amount of pitch diameter tolerance on external and internal threads; and 4) differences in thread designation.

In the Unified system an allowance is provided on both the Classes 1A and 2A external threads whereas in the American National system only the Class I external thread has an allowance. Also, in the Unified system, the pitch diameter tolerance of an internal thread is 30 per cent greater than that of the external thread, whereas they are equal in the American National system.

Revised Standard.— The revised screw thread standard ANSI/ASME B1.1-1989 (R2001) is much the same as that of ANSI B1.1-1982. The latest symbols in accordance with ANSI/ASME B1.7M-1984 (R2001) Nomenclature, are used. Acceptability criteria are described in ANSI/ASME B1.3M-1992 (R2001), Screw Thread Gaging Systems for Dimensional Acceptability, Inch or Metric Screw Threads (UN, UNR, UNJ, M, and MJ).

Where the letters U, A or B do not appear in the thread designations, the threads conform to the outdated American National screw threads.

Advantages of Unified Threads.— The Unified standard is designed to correct certain production difficulties resulting from the former standard. Often, under the old system, the tolerances of the product were practically absorbed by the combined tool and gage tolerances, leaving little for a working tolerance in manufacture. Somewhat greater tolerances are now provided for nut threads. As contrasted with the old "classes of fit" 1, 2, and 3, for each of which the pitch diameter tolerance on the external and internal threads were equal, the Classes 1B, 2B, and 3B (internal) threads in the new standard have, respectively, a 30 per cent larger pitch diameter tolerance than the 1A, 2A, and 3A (external) threads. Relatively more tolerance is provided for fine threads than for coarse threads of the same pitch. Where previous tolerances were more liberal than required, they were reduced.

Thread Form.— The Design Profiles for Unified screw threads, shown on page 1733, define the maximum material condition for external and internal threads with no allowance and are derived from the Basic Profile, shown on page 1726.

UN External Screw Threads: A flat root contour is specified, but it is necessary to provide for some threading tool crest wear, hence a rounded root contour cleared beyond the $0.25P$ flat width of the Basic Profile is optional.

UNR External Screw Threads: To reduce the rate of threading tool crest wear and to improve fatigue strength of a flat root thread, the Design Profile of the UNR thread has a smooth, continuous, non-reversing contour with a radius of curvature not less than $0.108P$ at any point and blends tangentially into the flanks and any straight segment. At the maximum material condition, the point of tangency is specified to be at a distance not less than $0.625H$ (where H is the height of a sharp V-thread) below the basic major diameter.

UN and UNR External Screw Threads: The Design Profiles of both UN and UNR external screw threads have flat crests. However, in practice, product threads are produced with partially or completely rounded crests. A rounded crest tangent at $0.125P$ flat is shown as an option on page 1733.

Copyright 2004, Industrial Press, Inc., New York, NY

UN Internal Screw Thread: In practice it is necessary to provide for some threading tool crest wear, therefore the root of the Design Profile is rounded and cleared beyond the 0.125*P* flat width of the Basic Profile.There is no internal UNR screw thread.

American National Standard Unified Internal and External Screw Thread Design Profiles (Maximum Material Condition) .—



Thread Series.— Thread series are groups of diameter-pitch combinations distinguished from each other by the numbers of threads per inch applied to a specific diameter. The various diameter-pitch combinations of eleven standard series are shown in Table 2. The limits of size of threads in the eleven standard series together with certain selected combinations of diameter and pitch, as well as the symbols for designating the various threads, are given in Table 3. *(Text continues on page 1763)*

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American Standard Unified Inch Screw Thread Form Data

Threads per Inch	Pitch	Depth of Sharp V-Thread	Depth of Int. Thd. and UN Ext. Thd.[a]	Depth of UNR Ext. Thd.	Truncation of Ext. Thd. Root	Truncation of UNR Ext. Thd. Root[b]	Truncation of Ext. Thd. Crest	Truncation of Int. Thd. Root	Truncation of Int. Thd. Crest	Flat at Ext. Thd. Crest and Int. Thd. Root	Basic Flat at Int. Thd. Crest[c]	Maximum Ext. Thd. Root Radius	Addendum of Ext. Thd.
n	*P*	0.86603*P*	0.54127*P*	0.59539*P*	0.21651*P*	0.16238*P*	0.10825*P*	0.10825*P*	0.2165*P*	0.125*P*	0.25*P*	0.14434*P*	0.32476*P*
80	0.01250	0.01083	0.00677	0.00744	0.00271	0.00203	0.00135	0.00135	0.00271	0.00156	0.00312	0.00180	0.00406
72	0.01389	0.01203	0.00752	0.00827	0.00301	0.00226	0.00150	0.00150	0.00301	0.00174	0.00347	0.00200	0.00451
64	0.01563	0.01353	0.00846	0.00930	0.00338	0.00254	0.00169	0.00169	0.00338	0.00195	0.00391	0.00226	0.00507
56	0.01786	0.01546	0.00967	0.01063	0.00387	0.00290	0.00193	0.00193	0.00387	0.00223	0.00446	0.00258	0.00580
48	0.02083	0.01804	0.01128	0.01240	0.00451	0.00338	0.00226	0.00226	0.00451	0.00260	0.00521	0.00301	0.00677
44	0.02273	0.01968	0.01230	0.01353	0.00492	0.00369	0.00246	0.00246	0.00492	0.00284	0.00568	0.00328	0.00738
40	0.02500	0.02165	0.01353	0.01488	0.00541	0.00406	0.00271	0.00271	0.00541	0.00312	0.00625	0.00361	0.00812
36	0.02778	0.02406	0.01504	0.01654	0.00601	0.00451	0.00301	0.00301	0.00601	0.00347	0.00694	0.00401	0.00902
32	0.03125	0.02706	0.01691	0.01861	0.00677	0.00507	0.00338	0.00338	0.00677	0.00391	0.00781	0.00451	0.01015
28	0.03571	0.03093	0.01933	0.02126	0.00773	0.00580	0.00387	0.00387	0.00773	0.00446	0.00893	0.00515	0.01160
27	0.03704	0.03208	0.02005	0.02205	0.00802	0.00601	0.00401	0.00401	0.00802	0.00463	0.00926	0.00535	0.01203
24	0.04167	0.03608	0.02255	0.02481	0.00902	0.00677	0.00451	0.00451	0.00902	0.00521	0.01042	0.00601	0.01353
20	0.05000	0.04330	0.02706	0.02977	0.01083	0.00812	0.00541	0.00541	0.01083	0.00625	0.01250	0.00722	0.01624
18	0.05556	0.04811	0.03007	0.03308	0.01203	0.00902	0.00601	0.00601	0.01203	0.00694	0.01389	0.00802	0.01804
16	0.06250	0.05413	0.03383	0.03721	0.01353	0.01015	0.00677	0.00677	0.01353	0.00781	0.01562	0.00902	0.02030
14	0.07143	0.06186	0.03866	0.04253	0.01546	0.01160	0.00773	0.00773	0.01546	0.00893	0.01786	0.01031	0.02320
13	0.07692	0.06662	0.04164	0.04580	0.01655	0.01249	0.00833	0.00833	0.01665	0.00962	0.01923	0.01110	0.02498
12	0.08333	0.07217	0.04511	0.04962	0.01804	0.01353	0.00902	0.00902	0.01804	0.01042	0.02083	0.01203	0.02706
11½	0.08696	0.07531	0.04707	0.05177	0.01883	0.01412	0.00941	0.00941	0.01883	0.01087	0.02174	0.01255	0.02824
11	0.09091	0.07873	0.04921	0.05413	0.01968	0.01476	0.00984	0.00984	0.01968	0.01136	0.02273	0.01312	0.02952
10	0.10000	0.08660	0.05413	0.05954	0.02165	0.01624	0.01083	0.01083	0.02165	0.01250	0.02500	0.01443	0.03248
9	0.11111	0.09623	0.06014	0.06615	0.02406	0.01804	0.01203	0.01203	0.02406	0.01389	0.02778	0.01604	0.03608
8	0.12500	0.10825	0.06766	0.07442	0.02706	0.02030	0.01353	0.01353	0.02706	0.01562	0.03125	0.01804	0.04059
7	0.14286	0.12372	0.07732	0.08506	0.03093	0.02320	0.01546	0.01546	0.03093	0.01786	0.03571	0.02062	0.04639
6	0.16667	0.14434	0.09021	0.09923	0.03608	0.02706	0.01804	0.01804	0.03608	0.02083	0.04167	0.02406	0.05413
5	0.20000	0.17321	0.10825	0.11908	0.04330	0.03248	0.02165	0.02165	0.04330	0.02500	0.05000	0.02887	0.06495
4½	0.22222	0.19245	0.12028	0.13231	0.04811	0.03608	0.02406	0.02406	0.04811	0.02778	0.05556	0.03208	0.07217
4	0.25000	0.21651	0.13532	0.14885	0.05413	0.04059	0.02706	0.02706	0.05413	0.03125	0.06250	0.03608	0.08119

[a] Also depth of thread engagement.

[b] Design profile.

[c] Also basic flat at external UN thread root.

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Diameter-Pitch Combinations for Standard Series of Threads (UN/UNR)

Sizes[a] No. or Inches	Basic Major Dia. Inches	Threads per Inch										
		Series with Graded Pitches			Series with Uniform (Constant) Pitches							
		Coarse UNC	Fine[b] UNF	Extra fine[c] UNEF	4-UN	6-UN	8-UN	12-UN	16-UN	20-UN	28-UN	32-UN
0	0.0600	…	80	Series designation shown indicates the UN thread form; however, the UNR thread form may be specified by substituting UNR in place of UN in all designations for external threads.								
(1)	0.0730	64	72									
2	0.0860	56	64									
(3)	0.0990	48	56									
4	0.1120	40	48									
5	0.1250	40	44	…	…	…	…	…	…	…	…	…
6	0.1380	32	40	…	…	…	…	…	…	…	…	UNC
8	0.1640	32	36	…	…	…	…	…	…	…	…	UNC
10	0.1900	24	32	…	…	…	…	…	…	…	…	UNF
(12)	0.2160	24	28	32	…	…	…	…	…	…	UNF	UNEF
1/4	0.2500	20	28	32	…	…	…	…	…	UNC	UNF	UNEF
5/16	0.3125	18	24	32	…	…	…	…	…	20	28	UNEF
3/8	0.3750	16	24	32	…	…	…	…	UNC	20	28	UNEF
7/16	0.4375	14	20	28	…	…	…	…	16	UNF	UNEF	32
1/2	0.5000	13	20	28	…	…	…	…	16	UNF	UNEF	32
9/16	0.5625	12	18	24	…	…	…	UNC	16	20	28	32
5/8	0.6250	11	18	24	…	…	…	12	16	20	28	32
(11/16)	0.6875	…	…	24	…	…	…	12	16	20	28	32
3/4	0.7500	10	16	20	…	…	…	12	UNF	UNEF	28	32
(13/16)	0.8125	…	…	20	…	…	…	12	16	UNEF	28	32
7/8	0.8750	9	14	20	…	…	…	12	16	UNEF	28	32
(15/16)	0.9375	…	…	20	…	…	…	12	16	UNEF	28	32
1	1.0000	8	12	20	…	…	UNC	UNF	16	UNEF	28	32
(1 1/16)	1.0625	…	…	18	…	…	8	12	16	20	28	…
1 1/8	1.1250	7	12	18	…	…	8	UNF	16	20	28	…
(1 3/16)	1.1875	…	…	18	…	…	8	12	16	20	28	…
1 1/4	1.2500	7	12	18	…	…	8	UNF	16	20	28	…
1 5/16	1.3125	…	…	18	…	…	8	12	16	20	28	…
1 3/8	1.3750	6	12	18	…	UNC	8	UNF	16	20	28	…
(1 7/16)	1.4375	…	…	18	…	6	8	12	16	20	28	…
1 1/2	1.5000	6	12	18	…	UNC	8	UNF	16	20	28	…
(1 9/16)	1.5625	…	…	18	…	6	8	12	16	20	…	…
1 5/8	1.6250	…	…	18	…	6	8	12	16	20	…	…
(1 11/16)	1.6875	…	…	18	…	6	8	12	16	20	…	…
1 3/4	1.7500	5	…	…	…	6	8	12	16	20	…	…
(1 13/16)	1.8125	…	…	…	…	6	8	12	16	20	…	…
1 7/8	1.8750	…	…	…	…	6	8	12	16	20	…	…
(1 15/16)	1.9375	…	…	…	…	6	8	12	16	20	…	…
2	2.0000	4½	…	…	…	6	8	12	16	20	…	…
(2 1/8)	2.1250	…	…	…	…	6	8	12	16	20	…	…
2 1/4	2.2500	4 ½	…	…	…	6	8	12	16	20	…	…
(2 3/8)	2.3750	…	…	…	…	6	8	12	16	20	…	…
2 1/2	2.5000	4	…	…	UNC	6	8	12	16	20	…	…
(2 5/8)	2.6250	…	…	…	4	6	8	12	16	20	…	…
2 3/4	2.7500	4	…	…	UNC	6	8	12	16	20	…	…
(2 7/8)	2.8750	…	…	…	4	6	8	12	16	20	…	…
3	3.0000	4	…	…	UNC	6	8	12	16	20	…	…
(3 1/8)	3.1250	…	…	…	4	6	8	12	16	…	…	…
3 1/4	3.2500	4	…	…	UNC	6	8	12	16	…	…	…
(3 3/8)	3.3750	…	…	…	4	6	8	12	16	…	…	…
3 1/2	3.5000	4	…	…	UNC	6	8	12	16	…	…	…
(3 5/8)	3.6250	…	…	…	4	6	8	12	16	…	…	…
3 3/4	3.7500	4	…	…	UNC	6	8	12	16	…	…	…
(3 7/8)	3.8750	…	…	…	4	6	8	12	16	…	…	…
4	4.0000	4	…	…	UNC	6	8	12	16	…	…	…

[a] Sizes shown in parentheses are secondary sizes. Primary sizes of 4 1/4, 4 1/2, 4 3/4, 5, 5 1/4, 5 1/2, 5 3/4 and 6 inches also are in the 4, 6, 8, 12, and 16 thread series; secondary sizes of 4 1/8, 4 3/8, 4 5/8, 4 7/8, 5 1/8, 5 3/8, 5 5/8, and 5 7/8 also are in the 4, 6, 8, 12, and 16 thread series.

[b] For diameters over 1 1/2 inches, use 12-thread series.

[c] For diameters over 1 11/16 inches, use 16-thread series.

For UNR thread form substitute UNR for UN for external threads only.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Standard Series and Selected Combinations — Unified Screw Threads

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max (Ref.)		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min		Class	Min	Max	Min	Max	Min
0–80 UNF	**2A**	**0.0005**	**0.0595**	**0.0563**	—	**0.0514**	**0.0496**	**0.0446**	**2B**	**0.0465**	**0.0514**	**0.0519**	**0.0542**	**0.0600**
	3A	**0.0000**	**0.0600**	**0.0568**	—	**0.0519**	**0.0506**	**0.0451**	**3B**	**0.0465**	**0.0514**	**0.0519**	**0.0536**	**0.0600**
1–64 UNC	**2A**	**0.0006**	**0.0724**	**0.0686**	—	**0.0623**	**0.0603**	**0.0538**	**2B**	**0.0561**	**0.0623**	**0.0629**	**0.0655**	**0.0730**
	3A	**0.0000**	**0.0730**	**0.0692**	—	**0.0629**	**0.0614**	**0.0544**	**3B**	**0.0561**	**0.0623**	**0.0629**	**0.0648**	**0.0730**
1–72 UNF	**2A**	**0.0006**	**0.0724**	**0.0689**	—	**0.0634**	**0.0615**	**0.0559**	**2B**	**0.0580**	**0.0635**	**0.0640**	**0.0665**	**0.0730**
	3A	**0.0000**	**0.0730**	**0.0695**	—	**0.0640**	**0.0626**	**0.0565**	**3B**	**0.0580**	**0.0635**	**0.0640**	**0.0659**	**0.0730**
2–56 UNC	**2A**	**0.0006**	**0.0854**	**0.0813**	—	**0.0738**	**0.0717**	**0.0642**	**2B**	**0.0667**	**0.0737**	**0.0744**	**0.0772**	**0.0860**
	3A	**0.0000**	**0.0860**	**0.0819**	—	**0.0744**	**0.0728**	**0.0648**	**3B**	**0.0667**	**0.0737**	**0.0744**	**0.0765**	**0.0860**
2–64 UNF	**2A**	**0.0006**	**0.0854**	**0.0816**	—	**0.0753**	**0.0733**	**0.0668**	**2B**	**0.0691**	**0.0753**	**0.0759**	**0.0786**	**0.0860**
	3A	**0.0000**	**0.0860**	**0.0822**	—	**0.0759**	**0.0744**	**0.0674**	**3B**	**0.0691**	**0.0753**	**0.0759**	**0.0779**	**0.0860**
3–48 UNC	**2A**	**0.0007**	**0.0983**	**0.0938**	—	**0.0848**	**0.0825**	**0.0734**	**2B**	**0.0764**	**0.0845**	**0.0855**	**0.0885**	**0.0990**
	3A	**0.0000**	**0.0990**	**0.0945**	—	**0.0855**	**0.0838**	**0.0741**	**3B**	**0.0764**	**0.0845**	**0.0855**	**0.0877**	**0.0990**
3–56 UNF	**2A**	**0.0007**	**0.0983**	**0.0942**	—	**0.0867**	**0.0845**	**0.0771**	**2B**	**0.0797**	**0.0865**	**0.0874**	**0.0902**	**0.0990**
	3A	**0.0000**	**0.0990**	**0.0949**	—	**0.0874**	**0.0858**	**0.0778**	**3B**	**0.0797**	**0.0865**	**0.0874**	**0.0895**	**0.0990**
4–40 UNC	**2A**	**0.0008**	**0.1112**	**0.1061**	—	**0.0950**	**0.0925**	**0.0814**	**2B**	**0.0849**	**0.0939**	**0.0958**	**0.0991**	**0.1120**
	3A	**0.0000**	**0.1120**	**0.1069**	—	**0.0958**	**0.0939**	**0.0822**	**3B**	**0.0849**	**0.0939**	**0.0958**	**0.0982**	**0.1120**
4–48 UNF	**2A**	**0.0007**	**0.1113**	**0.1068**	—	**0.0978**	**0.0954**	**0.0864**	**2B**	**0.0894**	**0.0968**	**0.0985**	**0.1016**	**0.1120**
	3A	**0.0000**	**0.1120**	**0.1075**	—	**0.0985**	**0.0967**	**0.0871**	**3B**	**0.0894**	**0.0968**	**0.0985**	**0.1008**	**0.1120**
5–40 UNC	**2A**	**0.0008**	**0.1242**	**0.1191**	—	**0.1080**	**0.1054**	**0.0944**	**2B**	**0.0979**	**0.1062**	**0.1088**	**0.1121**	**0.1250**
	3A	**0.0000**	**0.1250**	**0.1199**	—	**0.1088**	**0.1069**	**0.0952**	**3B**	**0.0979**	**0.1062**	**0.1088**	**0.1113**	**0.1250**
5–44 UNF	**2A**	**0.0007**	**0.1243**	**0.1195**	—	**0.1095**	**0.1070**	**0.0972**	**2B**	**0.1004**	**0.1079**	**0.1102**	**0.1134**	**0.1250**
	3A	**0.0000**	**0.1250**	**0.1202**	—	**0.1102**	**0.1083**	**0.0979**	**3B**	**0.1004**	**0.1079**	**0.1102**	**0.1126**	**0.1250**
6–32 UNC	**2A**	**0.0008**	**0.1372**	**0.1312**	—	**0.1169**	**0.1141**	**0.1000**	**2B**	**0.104**	**0.114**	**0.1177**	**0.1214**	**0.1380**
	3A	**0.0000**	**0.1380**	**0.1320**	—	**0.1177**	**0.1156**	**0.1008**	**3B**	**0.1040**	**0.1140**	**0.1177**	**0.1204**	**0.1380**
6–40 UNF	**2A**	**0.0008**	**0.1372**	**0.1321**	—	**0.1210**	**0.1184**	**0.1074**	**2B**	**0.111**	**0.119**	**0.1218**	**0.1252**	**0.1380**
	3A	**0.0000**	**0.1380**	**0.1329**	—	**0.1218**	**0.1198**	**0.1082**	**3B**	**0.1110**	**0.1186**	**0.1218**	**0.1243**	**0.1380**
8–32 UNC	**2A**	**0.0009**	**0.1631**	**0.1571**	—	**0.1428**	**0.1399**	**0.1259**	**2B**	**0.130**	**0.139**	**0.1437**	**0.1475**	**0.1640**
	3A	**0.0000**	**0.1640**	**0.1580**	—	**0.1437**	**0.1415**	**0.1268**	**3B**	**0.1300**	**0.1389**	**0.1437**	**0.1465**	**0.1640**
8–36 UNF	**2A**	**0.0008**	**0.1632**	**0.1577**	—	**0.1452**	**0.1424**	**0.1301**	**2B**	**0.134**	**0.142**	**0.1460**	**0.1496**	**0.1640**
	3A	**0.0000**	**0.1640**	**0.1585**	—	**0.1460**	**0.1439**	**0.1309**	**3B**	**0.1340**	**0.1416**	**0.1460**	**0.1487**	**0.1640**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
10–24 UNC	**2A**	**0.0010**	**0.1890**	**0.1818**	**—**	**0.1619**	**0.1586**	**0.1394**	**2B**	**0.145**	**0.156**	**0.1629**	**0.1672**	**0.1900**
	3A	**0.0000**	**0.1900**	**0.1828**	**—**	**0.1629**	**0.1604**	**0.1404**	**3B**	**0.1450**	**0.1555**	**0.1629**	**0.1661**	**0.1900**
10–28 UNS	**2A**	**0.0010**	**0.1890**	**0.1825**	**—**	**0.1658**	**0.1625**	**0.1464**	**2B**	**0.151**	**0.160**	**0.1668**	**0.1711**	**0.1900**
10–32 UNF	**2A**	**0.0009**	**0.1891**	**0.1831**	**—**	**0.1688**	**0.1658**	**0.1519**	**2B**	**0.156**	**0.164**	**0.1697**	**0.1736**	**0.1900**
	3A	**0.0000**	**0.1900**	**0.1840**	**—**	**0.1697**	**0.1674**	**0.1528**	**3B**	**0.1560**	**0.1641**	**0.1697**	**0.1726**	**0.1900**
10–36 UNS	**2A**	**0.0009**	**0.1891**	**0.1836**	**—**	**0.1711**	**0.1681**	**0.1560**	**2B**	**0.160**	**0.166**	**0.1720**	**0.1759**	**0.1900**
10–40 UNS	**2A**	**0.0009**	**0.1891**	**0.1840**	**—**	**0.1729**	**0.1700**	**0.1592**	**2B**	**0.163**	**0.169**	**0.1738**	**0.1775**	**0.1900**
10–48 UNS	**2A**	**0.0008**	**0.1892**	**0.1847**	**—**	**0.1757**	**0.1731**	**0.1644**	**2B**	**0.167**	**0.172**	**0.1765**	**0.1799**	**0.1900**
10–56 UNS	**2A**	**0.0007**	**0.1893**	**0.1852**	**—**	**0.1777**	**0.1752**	**0.1681**	**2B**	**0.171**	**0.175**	**0.1784**	**0.1816**	**0.1900**
12–24 UNC	**2A**	**0.0010**	**0.2150**	**0.2078**	**—**	**0.1879**	**0.1845**	**0.1654**	**2B**	**0.171**	**0.181**	**0.1889**	**0.1933**	**0.2160**
	3A	**0.0000**	**0.2160**	**0.2088**	**—**	**0.1889**	**0.1863**	**0.1664**	**3B**	**0.1710**	**0.1807**	**0.1889**	**0.1922**	**0.2160**
12–28 UNF	**2A**	**0.0010**	**0.2150**	**0.2085**	**—**	**0.1918**	**0.1886**	**0.1724**	**2B**	**0.177**	**0.186**	**0.1928**	**0.1970**	**0.2160**
	3A	**0.0000**	**0.2160**	**0.2095**	**—**	**0.1928**	**0.1904**	**0.1734**	**3B**	**0.1770**	**0.1857**	**0.1928**	**0.1959**	**0.2160**
12–32 UNEF	**2A**	**0.0009**	**0.2151**	**0.2091**	**—**	**0.1948**	**0.1917**	**0.1779**	**2B**	**0.182**	**0.190**	**0.1957**	**0.1998**	**0.2160**
	3A	**0.0000**	**0.2160**	**0.2100**	**—**	**0.1957**	**0.1933**	**0.1788**	**3B**	**0.1820**	**0.1895**	**0.1957**	**0.1988**	**0.2160**
12–36 UNS	**2A**	**0.0009**	**0.2151**	**0.2096**	**—**	**0.1971**	**0.1941**	**0.1821**	**2B**	**0.186**	**0.192**	**0.1980**	**0.2019**	**0.2160**
12–40 UNS	**2A**	**0.0009**	**0.2151**	**0.2100**	**—**	**0.1989**	**0.1960**	**0.1835**	**2B**	**0.189**	**0.195**	**0.1998**	**0.2035**	**0.2160**
12–48 UNS	**2A**	**0.0008**	**0.2152**	**0.2107**	**—**	**0.2017**	**0.1991**	**0.1904**	**2B**	**0.193**	**0.198**	**0.2025**	**0.2059**	**0.2160**
12–56 UNS	**2A**	**0.0007**	**0.2153**	**0.2112**	**—**	**0.2037**	**0.2012**	**0.1941**	**2B**	**0.197**	**0.201**	**0.2044**	**0.2076**	**0.2160**
1/4–20 UNC	**1A**	**0.0011**	**0.2489**	**0.2367**	**—**	**0.2164**	**0.2108**	**0.1894**	**1B**	**0.196**	**0.207**	**0.2175**	**0.2248**	**0.2500**
	2A	**0.0011**	**0.2489**	**0.2408**	**0.2367**	**0.2164**	**0.2127**	**0.1894**	**2B**	**0.196**	**0.207**	**0.2175**	**0.2224**	**0.2500**
	3A	**0.0000**	**0.2500**	**0.2419**	**—**	**0.2175**	**0.2147**	**0.1905**	**3B**	**0.1960**	**0.2067**	**0.2175**	**0.2211**	**0.2500**
1/4–24 UNS	**2A**	**0.0011**	**0.2489**	**0.2417**	**—**	**0.2218**	**0.2181**	**0.1993**	**2B**	**0.205**	**0.215**	**0.2229**	**0.2277**	**0.2500**
1/4–27 UNS	**2A**	**0.0010**	**0.2490**	**0.2423**	**—**	**0.2249**	**0.2214**	**0.2049**	**2B**	**0.210**	**0.219**	**0.2259**	**0.2304**	**0.2500**
1/4–28 UNF	**1A**	**0.0010**	**0.2490**	**0.2392**	**—**	**0.2258**	**0.2208**	**0.2064**	**1B**	**0.211**	**0.220**	**0.2268**	**0.2333**	**0.2500**
	2A	**0.0010**	**0.2490**	**0.2425**	**—**	**0.2258**	**0.2225**	**0.2064**	**2B**	**0.211**	**0.220**	**0.2268**	**0.2311**	**0.2500**
	3A	**0.0000**	**0.2500**	**0.2435**	**—**	**0.2268**	**0.2243**	**0.2074**	**3B**	**0.2110**	**0.2190**	**0.2268**	**0.2300**	**0.2500**
1/4–32 UNEF	**2A**	**0.0010**	**0.2490**	**0.2430**	**—**	**0.2287**	**0.2255**	**0.2118**	**2B**	**0.216**	**0.224**	**0.2297**	**0.2339**	**0.2500**
	3A	**0.0000**	**0.2500**	**0.2440**	**—**	**0.2297**	**0.2273**	**0.2128**	**3B**	**0.2160**	**0.2229**	**0.2297**	**0.2328**	**0.2500**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1/4–36 UNS	**2A**	**0.0009**	**0.2491**	**0.2436**	—	**0.2311**	**0.2280**	**0.2161**	**2B**	**0.220**	**0.226**	**0.2320**	**0.2360**	**0.2500**
1/4–40 UNS	**2A**	**0.0009**	**0.2491**	**0.2440**	—	**0.2329**	**0.2300**	**0.2193**	**2B**	**0.223**	**0.229**	**0.2338**	**0.2376**	**0.2500**
1/4–48 UNS	**2A**	**0.0008**	**0.2492**	**0.2447**	—	**0.2357**	**0.2330**	**0.2243**	**2B**	**0.227**	**0.232**	**0.2365**	**0.2401**	**0.2500**
1/4–56 UNS	**2A**	**0.0008**	**0.2492**	**0.2451**	—	**0.2376**	**0.2350**	**0.2280**	**2B**	**0.231**	**0.235**	**0.2384**	**0.2417**	**0.2500**
5/16–18 UNC	**1A**	**0.0012**	**0.3113**	**0.2982**	—	**0.2752**	**0.2691**	**0.2452**	**1B**	**0.252**	**0.265**	**0.2764**	**0.2843**	**0.3125**
	2A	**0.0012**	**0.3113**	**0.3026**	**0.2982**	**0.2752**	**0.2712**	**0.2452**	**2B**	**0.252**	**0.265**	**0.2764**	**0.2817**	**0.3125**
	3A	**0.0000**	**0.3125**	**0.3038**	—	**0.2764**	**0.2734**	**0.2464**	**3B**	**0.2520**	**0.2630**	**0.2764**	**0.2803**	**0.3125**
5/16–20 UN	**2A**	**0.0012**	**0.3113**	**0.3032**	—	**0.2788**	**0.2748**	**0.2518**	**2B**	**0.258**	**0.270**	**0.2800**	**0.2852**	**0.3125**
	3A	**0.0000**	**0.3125**	**0.3044**	—	**0.2800**	**0.2770**	**0.2530**	**3B**	**0.2580**	**0.2680**	**0.2800**	**0.2839**	**0.3125**
5/16–24 UNF	**1A**	**0.0011**	**0.3114**	**0.3006**	—	**0.2843**	**0.2788**	**0.2618**	**1B**	**0.267**	**0.277**	**0.2854**	**0.2925**	**0.3125**
	2A	**0.0011**	**0.3114**	**0.3042**	—	**0.2843**	**0.2806**	**0.2618**	**2B**	**0.267**	**0.277**	**0.2854**	**0.2902**	**0.3125**
	3A	**0.0000**	**0.3125**	**0.3053**	—	**0.2854**	**0.2827**	**0.2629**	**3B**	**0.2670**	**0.2754**	**0.2854**	**0.2890**	**0.3125**
5/16–27 UNS	**2A**	**0.0010**	**0.3115**	**0.3048**	—	**0.2874**	**0.2839**	**0.2674**	**2B**	**0.272**	**0.281**	**0.2884**	**0.2929**	**0.3125**
5/16–28 UN	**2A**	**0.0010**	**0.3115**	**0.3050**	—	**0.2883**	**0.2849**	**0.2689**	**2B**	**0.274**	**0.282**	**0.2893**	**0.2937**	**0.3125**
	3A	**0.0000**	**0.3125**	**0.3060**	—	**0.2893**	**0.2867**	**0.2699**	**3B**	**0.2740**	**0.2807**	**0.2893**	**0.2926**	**0.3125**
5/16–32 UNEF	**2A**	**0.0010**	**0.3115**	**0.3055**	—	**0.2912**	**0.2880**	**0.2743**	**2B**	**0.279**	**0.286**	**0.2922**	**0.2964**	**0.3125**
	3A	**0.0000**	**0.3125**	**0.3065**	—	**0.2922**	**0.2898**	**0.2753**	**3B**	**0.2790**	**0.2847**	**0.2922**	**0.2953**	**0.3125**
5/16–36 UNS	**2A**	**0.0009**	**0.3116**	**0.3061**	—	**0.2936**	**0.2905**	**0.2785**	**2B**	**0.282**	**0.289**	**0.2945**	**0.2985**	**0.3125**
5/16–40 UNS	**2A**	**0.0009**	**0.3116**	**0.3065**	—	**0.2954**	**0.2925**	**0.2818**	**2B**	**0.285**	**0.291**	**0.2963**	**0.3001**	**0.3125**
5/16–48 UNS	**2A**	**0.0008**	**0.3117**	**0.3072**	—	**0.2982**	**0.2955**	**0.2869**	**2B**	**0.290**	**0.295**	**0.2990**	**0.3026**	**0.3125**
3/8–16 UNC	**1A**	**0.0013**	**0.3737**	**0.3595**	—	**0.3331**	**0.3266**	**0.2992**	**1B**	**0.307**	**0.321**	**0.3344**	**0.3429**	**0.3750**
	2A	**0.0013**	**0.3737**	**0.3643**	**0.3595**	**0.3331**	**0.3287**	**0.2992**	**2B**	**0.307**	**0.321**	**0.3344**	**0.3401**	**0.3750**
	3A	**0.0000**	**0.3750**	**0.3656**	—	**0.3344**	**0.3311**	**0.3005**	**3B**	**0.3070**	**0.3182**	**0.3344**	**0.3387**	**0.3750**
3/8–18 UNS	**2A**	**0.0013**	**0.3737**	**0.3650**	—	**0.3376**	**0.3333**	**0.3076**	**2B**	**0.315**	**0.328**	**0.3389**	**0.3445**	**0.3750**
3/8–20 UN	**2A**	**0.0012**	**0.3738**	**0.3657**	—	**0.3413**	**0.3372**	**0.3143**	**2B**	**0.321**	**0.332**	**0.3425**	**0.3479**	**0.3750**
	3A	**0.0000**	**0.3750**	**0.3669**	—	**0.3425**	**0.3394**	**0.3155**	**3B**	**0.3210**	**0.3297**	**0.3425**	**0.3465**	**0.3750**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
3/8–24 UNF	**1A**	**0.0011**	**0.3739**	**0.3631**	**—**	**0.3468**	**0.3411**	**0.3243**	**1B**	**0.330**	**0.340**	**0.3479**	**0.3553**	**0.3750**
	2A	**0.0011**	**0.3739**	**0.3667**	**—**	**0.3468**	**0.3430**	**0.3243**	**2B**	**0.330**	**0.340**	**0.3479**	**0.3528**	**0.3750**
3/8–24 UNF	**3A**	**0.0000**	**0.3750**	**0.3678**	**—**	**0.3479**	**0.3450**	**0.3254**	**3B**	**0.3300**	**0.3372**	**0.3479**	**0.3516**	**0.3750**
3/8–27 UNS	**2A**	**0.0011**	**0.3739**	**0.3672**	**—**	**0.3498**	**0.3462**	**0.3298**	**2B**	**0.335**	**0.344**	**0.3509**	**0.3556**	**0.3750**
3/8–28 UN	**2A**	**0.0011**	**0.3739**	**0.3674**	**—**	**0.3507**	**0.3471**	**0.3313**	**2B**	**0.336**	**0.345**	**0.3518**	**0.3564**	**0.3750**
	3A	**0.0000**	**0.3750**	**0.3685**	**—**	**0.3518**	**0.3491**	**0.3324**	**3B**	**0.3360**	**0.3426**	**0.3518**	**0.3553**	**0.3750**
3/8–32 UNEF	**2A**	**0.0010**	**0.3740**	**0.3680**	**—**	**0.3537**	**0.3503**	**0.3368**	**2B**	**0.341**	**0.349**	**0.3547**	**0.3591**	**0.3750**
	3A	**0.0000**	**0.3750**	**0.3690**	**—**	**0.3547**	**0.3522**	**0.3378**	**3B**	**0.3410**	**0.3469**	**0.3547**	**0.3580**	**0.3750**
3/8–36 UNS	**2A**	**0.0010**	**0.3740**	**0.3685**	**—**	**0.3560**	**0.3528**	**0.3409**	**2B**	**0.345**	**0.352**	**0.3570**	**0.3612**	**0.3750**
3/8–40 UNS	**2A**	**0.0009**	**0.3741**	**0.3690**	**—**	**0.3579**	**0.3548**	**0.3443**	**2B**	**0.348**	**0.354**	**0.3588**	**0.3628**	**0.3750**
0.390–27 UNS	**2A**	**0.0011**	**0.3889**	**0.3822**	**—**	**0.3648**	**0.3612**	**0.3448**	**2B**	**0.350**	**0.359**	**0.3659**	**0.3706**	**0.3900**
7/16–14 UNC	**1A**	**0.0014**	**0.4361**	**0.4206**	**—**	**0.3897**	**0.3826**	**0.3511**	**1B**	**0.360**	**0.376**	**0.3911**	**0.4003**	**0.4375**
	2A	**0.0014**	**0.4361**	**0.4258**	**0.4206**	**0.3897**	**0.3850**	**0.3511**	**2B**	**0.360**	**0.376**	**0.3911**	**0.3972**	**0.4375**
	3A	**0.0000**	**0.4375**	**0.4272**	**—**	**0.3911**	**0.3876**	**0.3525**	**3B**	**0.3600**	**0.3717**	**0.3911**	**0.3957**	**0.4375**
7/16–16 UN	**2A**	**0.0014**	**0.4361**	**0.4267**	**—**	**0.3955**	**0.3909**	**0.3616**	**2B**	**0.370**	**0.384**	**0.3969**	**0.4028**	**0.4375**
	3A	**0.0000**	**0.4375**	**0.4281**	**—**	**0.3969**	**0.3935**	**0.3630**	**3B**	**0.3700**	**0.3800**	**0.3969**	**0.4014**	**0.4375**
7/16–18 UNS	**2A**	**0.0013**	**0.4362**	**0.4275**	**—**	**0.4001**	**0.3958**	**0.3701**	**2B**	**0.377**	**0.390**	**0.4014**	**0.4070**	**0.4375**
7/16–20 UNF	**1A**	**0.0013**	**0.4362**	**0.4240**	**—**	**0.4037**	**0.3975**	**0.3767**	**1B**	**0.383**	**0.395**	**0.4050**	**0.4131**	**0.4375**
	2A	**0.0013**	**0.4362**	**0.4281**	**—**	**0.4037**	**0.3995**	**0.3767**	**2B**	**0.383**	**0.395**	**0.4050**	**0.4104**	**0.4375**
	3A	**0.0000**	**0.4375**	**0.4294**	**—**	**0.4050**	**0.4019**	**0.3780**	**3B**	**0.3830**	**0.3916**	**0.4050**	**0.4091**	**0.4375**
7/16–24 UNS	**2A**	**0.0011**	**0.4364**	**0.4292**	**—**	**0.4093**	**0.4055**	**0.3868**	**2B**	**0.392**	**0.402**	**0.4104**	**0.4153**	**0.4375**
7/16–27 UNS	**2A**	**0.0011**	**0.4364**	**0.4297**	**—**	**0.4123**	**0.4087**	**0.3923**	**2B**	**0.397**	**0.406**	**0.4134**	**0.4181**	**0.4375**
7/16–28 UNEF	**2A**	**0.0011**	**0.4364**	**0.4299**	**—**	**0.4132**	**0.4096**	**0.3938**	**2B**	**0.399**	**0.407**	**0.4143**	**0.4189**	**0.4375**
	3A	**0.0000**	**0.4375**	**0.4310**	**—**	**0.4143**	**0.4116**	**0.3949**	**3B**	**0.3990**	**0.4051**	**0.4143**	**0.4178**	**0.4375**
7/16–32 UN	**2A**	**0.0010**	**0.4365**	**0.4305**	**—**	**0.4162**	**0.4128**	**0.3993**	**2B**	**0.404**	**0.411**	**0.4172**	**0.4216**	**0.4375**
	3A	**0.0000**	**0.4375**	**0.4315**	**—**	**0.4172**	**0.4147**	**0.4003**	**3B**	**0.4040**	**0.4094**	**0.4172**	**0.4205**	**0.4375**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1/2–12 UNS	**2A**	**0.0016**	**0.4984**	**0.4870**	—	**0.4443**	**0.4389**	**0.3992**	**2B**	**0.410**	**0.428**	**0.4459**	**0.4529**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4886**	—	**0.4459**	**0.4419**	**0.4008**	**3B**	**0.4100**	**0.4223**	**0.4459**	**0.4511**	**0.5000**
1/2–13 UNC	**1A**	**0.0015**	**0.4985**	**0.4822**	—	**0.4485**	**0.4411**	**0.4069**	**1B**	**0.417**	**0.434**	**0.4500**	**0.4597**	**0.5000**
	2A	**0.0015**	**0.4985**	**0.4876**	**0.4822**	**0.4485**	**0.4435**	**0.4069**	**2B**	**0.417**	**0.434**	**0.4500**	**0.4565**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4891**	—	**0.4500**	**0.4463**	**0.4084**	**3B**	**0.4170**	**0.4284**	**0.4500**	**0.4548**	**0.5000**
1/2–14 UNS	**2A**	**0.0015**	**0.4985**	**0.4882**	—	**0.4521**	**0.4471**	**0.4135**	**2B**	**0.423**	**0.438**	**0.4536**	**0.4601**	**0.5000**
1/2–16 UN	**2A**	**0.0014**	**0.4986**	**0.4892**	—	**0.4580**	**0.4533**	**0.4241**	**2B**	**0.432**	**0.446**	**0.4594**	**0.4655**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4906**	—	**0.4594**	**0.4559**	**0.4255**	**3B**	**0.4320**	**0.4419**	**0.4594**	**0.4640**	**0.5000**
1/2–18 UNS	**2A**	**0.0013**	**0.4987**	**0.4900**	—	**0.4626**	**0.4582**	**0.4326**	**2B**	**0.440**	**0.453**	**0.4639**	**0.4697**	**0.5000**
1/2–20 UNF	**1A**	**0.0013**	**0.4987**	**0.4865**	—	**0.4662**	**0.4598**	**0.4392**	**1B**	**0.446**	**0.457**	**0.4675**	**0.4759**	**0.5000**
	2A	**0.0013**	**0.4987**	**0.4906**	—	**0.4662**	**0.4619**	**0.4392**	**2B**	**0.446**	**0.457**	**0.4675**	**0.4731**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4919**	—	**0.4675**	**0.4643**	**0.4405**	**3B**	**0.4460**	**0.4537**	**0.4675**	**0.4717**	**0.5000**
1/2–24 UNS	**2A**	**0.0012**	**0.4988**	**0.4916**	—	**0.4717**	**0.4678**	**0.4492**	**2B**	**0.455**	**0.465**	**0.4729**	**0.4780**	**0.5000**
1/2–27 UNS	**2A**	**0.0011**	**0.4989**	**0.4922**	—	**0.4748**	**0.4711**	**0.4548**	**2B**	**0.460**	**0.469**	**0.4759**	**0.4807**	**0.5000**
1/2–28 UNEF	**2A**	**0.0011**	**0.4989**	**0.4924**	—	**0.4757**	**0.4720**	**0.4563**	**2B**	**0.461**	**0.470**	**0.4768**	**0.4816**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4935**	—	**0.4768**	**0.4740**	**0.4574**	**3B**	**0.4610**	**0.4676**	**0.4768**	**0.4804**	**0.5000**
1/2–32 UN	**2A**	**0.0010**	**0.4990**	**0.4930**	—	**0.4787**	**0.4752**	**0.4618**	**2B**	**0.466**	**0.474**	**0.4797**	**0.4842**	**0.5000**
	3A	**0.0000**	**0.5000**	**0.4940**	—	**0.4797**	**0.4771**	**0.4628**	**3B**	**0.4660**	**0.4719**	**0.4797**	**0.4831**	**0.5000**
9/16–12 UNC	**1A**	**0.0016**	**0.5609**	**0.5437**	—	**0.5068**	**0.4990**	**0.4617**	**1B**	**0.472**	**0.490**	**0.5084**	**0.5186**	**0.5625**
	2A	**0.0016**	**0.5609**	**0.5495**	**0.5437**	**0.5068**	**0.5016**	**0.4617**	**2B**	**0.472**	**0.490**	**0.5084**	**0.5152**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5511**	—	**0.5084**	**0.5045**	**0.4633**	**3B**	**0.4720**	**0.4843**	**0.5084**	**0.5135**	**0.5625**
9/16–14 UNS	**2A**	**0.0015**	**0.5610**	**0.5507**	—	**0.5146**	**0.5096**	**0.4760**	**2B**	**0.485**	**0.501**	**0.5161**	**0.5226**	**0.5625**
9/16–16 UN	**2A**	**0.0014**	**0.5611**	**0.5517**	—	**0.5205**	**0.5158**	**0.4866**	**2B**	**0.495**	**0.509**	**0.5219**	**0.5280**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5531**	—	**0.5219**	**0.5184**	**0.4880**	**3B**	**0.4950**	**0.5040**	**0.5219**	**0.5265**	**0.5625**
9/16–18 UNF	**1A**	**0.0014**	**0.5611**	**0.5480**	—	**0.5250**	**0.5182**	**0.4950**	**1B**	**0.502**	**0.515**	**0.5264**	**0.5353**	**0.5625**
	2A	**0.0014**	**0.5611**	**0.5524**	—	**0.5250**	**0.5205**	**0.4950**	**2B**	**0.502**	**0.515**	**0.5264**	**0.5323**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5538**	—	**0.5264**	**0.5230**	**0.4964**	**3B**	**0.5020**	**0.5106**	**0.5264**	**0.5308**	**0.5625**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
9/16–20 UN	**2A**	**0.0013**	**0.5612**	**0.5531**	**—**	**0.5287**	**0.5245**	**0.5017**	**2B**	**0.508**	**0.520**	**0.5300**	**0.5355**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5544**	**—**	**0.5300**	**0.5268**	**0.5030**	**3B**	**0.5080**	**0.5162**	**0.5300**	**0.5341**	**0.5625**
9/16–24 UNEF	**2A**	**0.0012**	**0.5613**	**0.5541**	**—**	**0.5342**	**0.5303**	**0.5117**	**2B**	**0.517**	**0.527**	**0.5354**	**0.5405**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5553**	**—**	**0.5354**	**0.5325**	**0.5129**	**3B**	**0.5170**	**0.5244**	**0.5354**	**0.5392**	**0.5625**
9/16–27 UNS	**2A**	**0.0011**	**0.5614**	**0.5547**	**—**	**0.5373**	**0.5336**	**0.5173**	**2B**	**0.522**	**0.531**	**0.5384**	**0.5432**	**0.5625**
9/16–28 UN	**2A**	**0.0011**	**0.5614**	**0.5549**	**—**	**0.5382**	**0.5345**	**0.5188**	**2B**	**0.524**	**0.532**	**0.5393**	**0.5441**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5560**	**—**	**0.5393**	**0.5365**	**0.5199**	**3B**	**0.5240**	**0.5301**	**0.5393**	**0.5429**	**0.5625**
9/16–32 UN	**2A**	**0.0010**	**0.5615**	**0.5555**	**—**	**0.5412**	**0.5377**	**0.5243**	**2B**	**0.529**	**0.536**	**0.5422**	**0.5467**	**0.5625**
	3A	**0.0000**	**0.5625**	**0.5565**	**—**	**0.5422**	**0.5396**	**0.5253**	**3B**	**0.5290**	**0.5344**	**0.5422**	**0.5456**	**0.5625**
5/8–11 UNC	**1A**	**0.0016**	**0.6234**	**0.6052**	**—**	**0.5644**	**0.5561**	**0.5152**	**1B**	**0.527**	**0.546**	**0.5660**	**0.5767**	**0.6250**
	2A	**0.0016**	**0.6234**	**0.6113**	**0.6052**	**0.5644**	**0.5589**	**0.5152**	**2B**	**0.527**	**0.546**	**0.5660**	**0.5732**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6129**	**—**	**0.5660**	**0.5619**	**0.5168**	**3B**	**0.5270**	**0.5391**	**0.5660**	**0.5714**	**0.6250**
5/8–12 UN	**2A**	**0.0016**	**0.6234**	**0.6120**	**—**	**0.5693**	**0.5639**	**0.5242**	**2B**	**0.535**	**0.553**	**0.5709**	**0.5780**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6136**	**—**	**0.5709**	**0.5668**	**0.5258**	**3B**	**0.5350**	**0.5463**	**0.5709**	**0.5762**	**0.6250**
5/8–14 UNS	**2A**	**0.0015**	**0.6235**	**0.6132**	**—**	**0.5771**	**0.5720**	**0.5385**	**2B**	**0.548**	**0.564**	**0.5786**	**0.5852**	**0.6250**
5/8–16 UN	**2A**	**0.0014**	**0.6236**	**0.6142**	**—**	**0.5830**	**0.5782**	**0.5491**	**2B**	**0.557**	**0.571**	**0.5844**	**0.5906**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6156**	**—**	**0.5844**	**0.5808**	**0.5505**	**3B**	**0.5570**	**0.5662**	**0.5844**	**0.5890**	**0.6250**
5/8–18 UNF	**1A**	**0.0014**	**0.6236**	**0.6105**	**—**	**0.5875**	**0.5805**	**0.5575**	**1B**	**0.565**	**0.578**	**0.5889**	**0.5980**	**0.6250**
	2A	**0.0014**	**0.6236**	**0.6149**	**—**	**0.5875**	**0.5828**	**0.5575**	**2B**	**0.565**	**0.578**	**0.5889**	**0.5949**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6163**	**—**	**0.5889**	**0.5854**	**0.5589**	**3B**	**0.5650**	**0.5730**	**0.5889**	**0.5934**	**0.6250**
5/8–20 UN	**2A**	**0.0013**	**0.6237**	**0.6156**	**—**	**0.5912**	**0.5869**	**0.5642**	**2B**	**0.571**	**0.582**	**0.5925**	**0.5981**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6169**	**—**	**0.5925**	**0.5893**	**0.5655**	**3B**	**0.5710**	**0.5787**	**0.5925**	**0.5967**	**0.6250**
5/8–24 UNEF	**2A**	**0.0012**	**0.6238**	**0.6166**	**—**	**0.5967**	**0.5927**	**0.5742**	**2B**	**0.580**	**0.590**	**0.5979**	**0.6031**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6178**	**—**	**0.5979**	**0.5949**	**0.5754**	**3B**	**0.5800**	**0.5869**	**0.5979**	**0.6018**	**0.6250**
5/8–27 UNS	**2A**	**0.0011**	**0.6239**	**0.6172**	**—**	**0.5998**	**0.5960**	**0.5798**	**2B**	**0.585**	**0.594**	**0.6009**	**0.6059**	**0.6250**
5/8–28 UN	**2A**	**0.0011**	**0.6239**	**0.6174**	**—**	**0.6007**	**0.5969**	**0.5813**	**2B**	**0.586**	**0.595**	**0.6018**	**0.6067**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6185**	**—**	**0.6018**	**0.5990**	**0.5824**	**3B**	**0.5860**	**0.5926**	**0.6018**	**0.6055**	**0.6250**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
5/8–32 UN	**2A**	**0.0011**	**0.6239**	**0.6179**	—	**0.6036**	**0.6000**	**0.5867**	**2B**	**0.591**	**0.599**	**0.6047**	**0.6093**	**0.6250**
	3A	**0.0000**	**0.6250**	**0.6190**	—	**0.6047**	**0.6020**	**0.5878**	**3B**	**0.5910**	**0.5969**	**0.6047**	**0.6082**	**0.6250**
11/16–12 UN	**2A**	**0.0016**	**0.6859**	**0.6745**	—	**0.6318**	**0.6264**	**0.5867**	**2B**	**0.597**	**0.615**	**0.6334**	**0.6405**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6761**	—	**0.6334**	**0.6293**	**0.5883**	**3B**	**0.5970**	**0.6085**	**0.6334**	**0.6387**	**0.6875**
11/16–16 UN	**2A**	**0.0014**	**0.6861**	**0.6767**	—	**0.6455**	**0.6407**	**0.6116**	**2B**	**0.620**	**0.634**	**0.6469**	**0.6531**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6781**	—	**0.6469**	**0.6433**	**0.6130**	**3B**	**0.6200**	**0.6284**	**0.6469**	**0.6515**	**0.6875**
11/16–20 UN	**2A**	**0.0013**	**0.6862**	**0.6781**	—	**0.6537**	**0.6494**	**0.6267**	**2B**	**0.633**	**0.645**	**0.6550**	**0.6606**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6794**	—	**0.6550**	**0.6518**	**0.6280**	**3B**	**0.6330**	**0.6412**	**0.6550**	**0.6592**	**0.6875**
11/16–24 UNEF	**2A**	**0.0012**	**0.6863**	**0.6791**	—	**0.6592**	**0.6552**	**0.6367**	**2B**	**0.642**	**0.652**	**0.6604**	**0.6656**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6803**	—	**0.6604**	**0.6574**	**0.6379**	**3B**	**0.6420**	**0.6494**	**0.6604**	**0.6643**	**0.6875**
11/16–28 UN	**2A**	**0.0011**	**0.6864**	**0.6799**	—	**0.6632**	**0.6594**	**0.6438**	**2B**	**0.649**	**0.657**	**0.6643**	**0.6692**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6810**	—	**0.6643**	**0.6615**	**0.6449**	**3B**	**0.6490**	**0.6551**	**0.6643**	**0.6680**	**0.6875**
11/16–32 UN	**2A**	**0.0011**	**0.6864**	**0.6804**	—	**0.6661**	**0.6625**	**0.6492**	**2B**	**0.654**	**0.661**	**0.6672**	**0.6718**	**0.6875**
	3A	**0.0000**	**0.6875**	**0.6815**	—	**0.6672**	**0.6645**	**0.6503**	**3B**	**0.6540**	**0.6594**	**0.6672**	**0.6707**	**0.6875**
3/4–10 UNC	**1A**	**0.0018**	**0.7482**	**0.7288**	—	**0.6832**	**0.6744**	**0.6291**	**1B**	**0.642**	**0.663**	**0.6850**	**0.6965**	**0.7500**
	2A	**0.0018**	**0.7482**	**0.7353**	**0.7288**	**0.6832**	**0.6773**	**0.6291**	**2B**	**0.642**	**0.663**	**0.6850**	**0.6927**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7371**	—	**0.6850**	**0.6806**	**0.6309**	**3B**	**0.6420**	**0.6545**	**0.6850**	**0.6907**	**0.7500**
3/4–12 UN	**2A**	**0.0017**	**0.7483**	**0.7369**	—	**0.6942**	**0.6887**	**0.6491**	**2B**	**0.660**	**0.678**	**0.6959**	**0.7031**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7386**	—	**0.6959**	**0.6918**	**0.6508**	**3B**	**0.6600**	**0.6707**	**0.6959**	**0.7013**	**0.7500**
3/4–14 UNS	**2A**	**0.0015**	**0.7485**	**0.7382**	—	**0.7021**	**0.6970**	**0.6635**	**2B**	**0.673**	**0.688**	**0.7036**	**0.7103**	**0.7500**
3/4–16 UNF	**1A**	**0.0015**	**0.7485**	**0.7343**	—	**0.7079**	**0.7004**	**0.6740**	**1B**	**0.682**	**0.696**	**0.7094**	**0.7192**	**0.7500**
	2A	**0.0015**	**0.7485**	**0.7391**	—	**0.7079**	**0.7029**	**0.6740**	**2B**	**0.682**	**0.696**	**0.7094**	**0.7159**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7406**	—	**0.7094**	**0.7056**	**0.6755**	**3B**	**0.6820**	**0.6908**	**0.7094**	**0.7143**	**0.7500**
3/4–18 UNS	**2A**	**0.0014**	**0.7486**	**0.7399**	—	**0.7125**	**0.7079**	**0.6825**	**2B**	**0.690**	**0.703**	**0.7139**	**0.7199**	**0.7500**
3/4–20 UNEF	**2A**	**0.0013**	**0.7487**	**0.7406**	—	**0.7162**	**0.7118**	**0.6892**	**2B**	**0.696**	**0.707**	**0.7175**	**0.7232**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7419**	—	**0.7175**	**0.7142**	**0.6905**	**3B**	**0.6960**	**0.7037**	**0.7175**	**0.7218**	**0.7500**
3/4–24 UNS	**2A**	**0.0012**	**0.7488**	**0.7416**	—	**0.7217**	**0.7176**	**0.6992**	**2B**	**0.705**	**0.715**	**0.7229**	**0.7282**	**0.7500**
3/4–24 UNS	**2A**	**0.0012**	**0.7488**	**0.7421**	—	**0.7247**	**0.7208**	**0.7047**	**2B**	**0.710**	**0.719**	**0.7259**	**0.7310**	**0.7500**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
3/4–28 UN	**2A**	**0.0012**	**0.7488**	**0.7423**	—	**0.7256**	**0.7218**	**0.7062**	**2B**	**0.711**	**0.720**	**0.7268**	**0.7318**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7435**	—	**0.7268**	**0.7239**	**0.7074**	**3B**	**0.7110**	**0.7176**	**0.7268**	**0.7305**	**0.7500**
3/4–32 UN	**2A**	**0.0011**	**0.7489**	**0.7429**	—	**0.7286**	**0.7250**	**0.7117**	**2B**	**0.716**	**0.724**	**0.7297**	**0.7344**	**0.7500**
	3A	**0.0000**	**0.7500**	**0.7440**	—	**0.7297**	**0.7270**	**0.7128**	**3B**	**0.7160**	**0.7219**	**0.7297**	**0.7333**	**0.7500**
13/16–12 UN	**2A**	**0.0017**	**0.8108**	**0.7994**	—	**0.7567**	**0.7512**	**0.7116**	**2B**	**0.722**	**0.740**	**0.7584**	**0.7656**	**0.8125**
	3A	**0.0000**	**0.8125**	**0.8011**	—	**0.7584**	**0.7543**	**0.7133**	**3B**	**0.7220**	**0.7329**	**0.7584**	**0.7638**	**0.8125**
13/16–16 UN	**2A**	**0.0015**	**0.8110**	**0.8016**	—	**0.7704**	**0.7655**	**0.7365**	**2B**	**0.745**	**0.759**	**0.7719**	**0.7782**	**0.8125**
	3A	**0.0000**	**0.8125**	**0.8031**	—	**0.7719**	**0.7683**	**0.7380**	**3B**	**0.7450**	**0.7533**	**0.7719**	**0.7766**	**0.8125**
13/16–20 UNEF	**2A**	**0.0013**	**0.8112**	**0.8031**	—	**0.7787**	**0.7743**	**0.7517**	**2B**	**0.758**	**0.770**	**0.7800**	**0.7857**	**0.8125**
	3A	**0.0000**	**0.8125**	**0.8044**	—	**0.7800**	**0.7767**	**0.7530**	**3B**	**0.7580**	**0.7662**	**0.7800**	**0.7843**	**0.8125**
13/16–28 UN	**2A**	**0.0012**	**0.8113**	**0.8048**	—	**0.7881**	**0.7843**	**0.7687**	**2B**	**0.774**	**0.782**	**0.7893**	**0.7943**	**0.8125**
	3A	**0.0000**	**0.8125**	**0.8060**	—	**0.7893**	**0.7864**	**0.7699**	**3B**	**0.7740**	**0.7801**	**0.7893**	**0.7930**	**0.8125**
13/16–32 UN	**2A**	**0.0011**	**0.8114**	**0.8054**	—	**0.7911**	**0.7875**	**0.7742**	**2B**	**0.779**	**0.786**	**0.7922**	**0.7969**	**0.8125**
	3A	**0.0000**	**0.8125**	**0.8065**	—	**0.7922**	**0.7895**	**0.7753**	**3B**	**0.7790**	**0.7844**	**0.7922**	**0.7958**	**0.8125**
7/8–9 UNC	**1A**	**0.0019**	**0.8731**	**0.8523**	—	**0.8009**	**0.7914**	**0.7408**	**1B**	**0.755**	**0.778**	**0.8028**	**0.8151**	**0.8750**
	2A	**0.0019**	**0.8731**	**0.8592**	**0.8523**	**0.8009**	**0.7946**	**0.7408**	**2B**	**0.755**	**0.778**	**0.8028**	**0.8110**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8611**	—	**0.8028**	**0.7981**	**0.7427**	**3B**	**0.7550**	**0.7681**	**0.8028**	**0.8089**	**0.8750**
7/8–10 UNS	**2A**	**0.0018**	**0.8732**	**0.8603**	—	**0.8082**	**0.8022**	**0.7542**	**2B**	**0.767**	**0.788**	**0.8100**	**0.8178**	**0.8750**
7/8–12 UN	**2A**	**0.0017**	**0.8733**	**0.8619**	—	**0.8192**	**0.8137**	**0.7741**	**2B**	**0.785**	**0.803**	**0.8209**	**0.8281**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8636**	—	**0.8209**	**0.8168**	**0.7758**	**3B**	**0.7850**	**0.7948**	**0.8209**	**0.8263**	**0.8750**
7/8–14 UNF	**1A**	**0.0016**	**0.8734**	**0.8579**	—	**0.8270**	**0.8189**	**0.7884**	**1B**	**0.798**	**0.814**	**0.8286**	**0.8392**	**0.8750**
	2A	**0.0016**	**0.8734**	**0.8631**	—	**0.8270**	**0.8216**	**0.7884**	**2B**	**0.798**	**0.814**	**0.8286**	**0.8356**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8647**	—	**0.8286**	**0.8245**	**0.7900**	**3B**	**0.7980**	**0.8068**	**0.8286**	**0.8339**	**0.8750**
7/8–16 UN	**2A**	**0.0015**	**0.8735**	**0.8641**	—	**0.8329**	**0.8280**	**0.7900**	**2B**	**0.807**	**0.821**	**0.8344**	**0.8407**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8656**	—	**0.8344**	**0.8308**	**0.8005**	**3B**	**0.8070**	**0.8158**	**0.8344**	**0.8391**	**0.8750**
7/8–18 UNS	**2A**	**0.0014**	**0.8736**	**0.8649**	—	**0.8375**	**0.8329**	**0.8075**	**2B**	**0.815**	**0.828**	**0.8389**	**0.8449**	**0.8750**
7/8–20 UNEF	**2A**	**0.0013**	**0.8737**	**0.8656**	—	**0.8412**	**0.8368**	**0.8142**	**2B**	**0.821**	**0.832**	**0.8425**	**0.8482**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8669**	—	**0.8425**	**0.8392**	**0.8155**	**3B**	**0.8210**	**0.8287**	**0.8425**	**0.8468**	**0.8750**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
7/8–24 UNS	**2A**	**0.0012**	**0.8738**	**0.8666**	**—**	**0.8467**	**0.8426**	**0.8242**	**2B**	**0.830**	**0.840**	**0.8479**	**0.8532**	**0.8750**
7/8–27 UNS	**2A**	**0.0012**	**0.8738**	**0.8671**	**—**	**0.8497**	**0.8458**	**0.8297**	**2B**	**0.835**	**0.844**	**0.8509**	**0.8560**	**0.8750**
7/8–28 UN	**2A**	**0.0012**	**0.8738**	**0.8673**	**—**	**0.8506**	**0.8468**	**0.8312**	**2B**	**0.836**	**0.845**	**0.8518**	**0.8568**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8685**	**—**	**0.8518**	**0.8489**	**0.8324**	**3B**	**0.8360**	**0.8426**	**0.8518**	**0.8555**	**0.8750**
7/8–32 UN	**2A**	**0.0011**	**0.8739**	**0.8679**	**—**	**0.8536**	**0.8500**	**0.8367**	**2B**	**0.841**	**0.849**	**0.8547**	**0.8594**	**0.8750**
	3A	**0.0000**	**0.8750**	**0.8690**	**—**	**0.8547**	**0.8520**	**0.8378**	**3B**	**0.8410**	**0.8469**	**0.8547**	**0.8583**	**0.8750**
15/16–12 UN	**2A**	**0.0017**	**0.9358**	**0.9244**	**—**	**0.8817**	**0.8760**	**0.8366**	**2B**	**0.847**	**0.865**	**0.8834**	**0.8908**	**0.9375**
	3A	**0.0000**	**0.9375**	**0.9261**	**—**	**0.8834**	**0.8793**	**0.8383**	**3B**	**0.8470**	**0.8575**	**0.8834**	**0.8889**	**0.9375**
15/16–16 UN	**2A**	**0.0015**	**0.9360**	**0.9266**	**—**	**0.8954**	**0.8904**	**0.8615**	**2B**	**0.870**	**0.884**	**0.8969**	**0.9034**	**0.9375**
	3A	**0.0000**	**0.9375**	**0.9281**	**—**	**0.8969**	**0.8932**	**0.8630**	**3B**	**0.8700**	**0.8783**	**0.8969**	**0.9018**	**0.9375**
15/16–20 UNEF	**2A**	**0.0014**	**0.9361**	**0.9280**	**—**	**0.9036**	**0.8991**	**0.8766**	**2B**	**0.883**	**0.895**	**0.9050**	**0.9109**	**0.9375**
	3A	**0.0000**	**0.9375**	**0.9294**	**—**	**0.9050**	**0.9016**	**0.8780**	**3B**	**0.8830**	**0.8912**	**0.9050**	**0.9094**	**0.9375**
15/16–28 UN	**2A**	**0.0012**	**0.9363**	**0.9298**	**—**	**0.9131**	**0.9091**	**0.8937**	**2B**	**0.899**	**0.907**	**0.9143**	**0.9195**	**0.9375**
	3A	**0.0000**	**0.9375**	**0.9310**	**—**	**0.9143**	**0.9113**	**0.8949**	**3B**	**0.8990**	**0.9051**	**0.9143**	**0.9182**	**0.9375**
15/16–32 UN	**2A**	**0.0011**	**0.9364**	**0.9304**	**—**	**0.9161**	**0.9123**	**0.8992**	**2B**	**0.904**	**0.911**	**0.9172**	**0.9221**	**0.9375**
	3A	**0.0000**	**0.9375**	**0.9315**	**—**	**0.9172**	**0.9144**	**0.9003**	**3B**	**0.9040**	**0.9094**	**0.9172**	**0.9209**	**0.9375**
1–8 UNC	**1A**	**0.0020**	**0.9980**	**0.9755**	**—**	**0.9168**	**0.9067**	**0.8492**	**1B**	**0.865**	**0.890**	**0.9188**	**0.9320**	**1.0000**
	2A	**0.0020**	**0.9980**	**0.9830**	**0.9755**	**0.9168**	**0.9100**	**0.8492**	**2B**	**0.865**	**0.890**	**0.9188**	**0.9276**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9850**	**—**	**0.9188**	**0.9137**	**0.8512**	**3B**	**0.8650**	**0.8797**	**0.9188**	**0.9254**	**1.0000**
1–10 UNS	**2A**	**0.0018**	**0.9982**	**0.9853**	**—**	**0.9332**	**0.9270**	**0.8792**	**2B**	**0.892**	**0.913**	**0.9350**	**0.9430**	**1.0000**
1–12 UNF	**1A**	**0.0018**	**0.9982**	**0.9810**	**—**	**0.9441**	**0.9353**	**0.8990**	**1B**	**0.910**	**0.928**	**0.9459**	**0.9573**	**1.0000**
	2A	**0.0018**	**0.9982**	**0.9868**	**—**	**0.9441**	**0.9382**	**0.8990**	**2B**	**0.910**	**0.928**	**0.9459**	**0.9535**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9886**	**—**	**0.9459**	**0.9415**	**0.9008**	**3B**	**0.9100**	**0.9198**	**0.9459**	**0.9516**	**1.0000**
1–14 UNS[f]	**1A**	**0.0017**	**0.9983**	**0.9828**	**—**	**0.9519**	**0.9435**	**0.9132**	**1B**	**0.923**	**0.938**	**0.9536**	**0.9645**	**1.0000**
	2A	**0.0017**	**0.9983**	**0.9880**	**—**	**0.9519**	**0.9463**	**0.9132**	**2B**	**0.923**	**0.938**	**0.9536**	**0.9609**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9897**	**—**	**0.9536**	**0.9494**	**0.9149**	**3B**	**0.9230**	**0.9315**	**0.9536**	**0.9590**	**1.0000**
1–16 UN	**2A**	**0.0015**	**0.9985**	**0.9891**	**—**	**0.9579**	**0.9529**	**0.9240**	**2B**	**0.932**	**0.946**	**0.9594**	**0.9659**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9906**	**—**	**0.9594**	**0.9557**	**0.9255**	**3B**	**0.9320**	**0.9408**	**0.9594**	**0.9643**	**1.0000**
1–18 UNS	**2A**	**0.0014**	**0.9986**	**0.9899**	**—**	**0.9625**	**0.9578**	**0.9325**	**2B**	**0.940**	**0.953**	**0.9639**	**0.9701**	**1.0000**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1–20 UNEF	**2A**	**0.0014**	**0.9986**	**0.9905**	**—**	**0.9661**	**0.9616**	**0.9391**	**2B**	**0.946**	**0.957**	**0.9675**	**0.9734**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9919**	**—**	**0.9675**	**0.9641**	**0.9405**	**3B**	**0.9460**	**0.9537**	**0.9675**	**0.9719**	**1.0000**
1–24 UNS	**2A**	**0.0013**	**0.9987**	**0.9915**	**—**	**0.9716**	**0.9674**	**0.9491**	**2B**	**0.955**	**0.965**	**0.9729**	**0.9784**	**1.0000**
1–27 UNS	**2A**	**0.0012**	**0.9988**	**0.9921**	**—**	**0.9747**	**0.9707**	**0.9547**	**2B**	**0.960**	**0.969**	**0.9759**	**0.9811**	**1.0000**
1–28 UN	**2A**	**0.0012**	**0.9988**	**0.9923**	**—**	**0.9756**	**0.9716**	**0.9562**	**2B**	**0.961**	**0.970**	**0.9768**	**0.9820**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9935**	**—**	**0.9768**	**0.9738**	**0.9574**	**3B**	**0.9610**	**0.9676**	**0.9768**	**0.9807**	**1.0000**
1–32 UN	**2A**	**0.0011**	**0.9989**	**0.9929**	**—**	**0.9786**	**0.9748**	**0.9617**	**2B**	**0.966**	**0.974**	**0.9797**	**0.9846**	**1.0000**
	3A	**0.0000**	**1.0000**	**0.9940**	**—**	**0.9797**	**0.9769**	**0.9628**	**3B**	**0.9660**	**0.9719**	**0.9797**	**0.9834**	**1.0000**
1 1/16–8 UN	**2A**	**0.0020**	**1.0605**	**1.0455**	**—**	**0.9793**	**0.9725**	**0.9117**	**2B**	**0.927**	**0.952**	**0.9813**	**0.9902**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0475**	**—**	**0.9813**	**0.9762**	**0.9137**	**3B**	**0.9270**	**0.9422**	**0.9813**	**0.9880**	**1.0625**
1 1/16–12 UN	**2A**	**0.0017**	**1.0608**	**1.0494**	**—**	**1.0067**	**1.0010**	**0.9616**	**2B**	**0.972**	**0.990**	**1.0084**	**1.0158**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0511**	**—**	**1.0084**	**1.0042**	**0.9633**	**3B**	**0.9720**	**0.9823**	**1.0084**	**1.0139**	**1.0625**
1 1/16–16 UN	**2A**	**0.0015**	**1.0610**	**1.0516**	**—**	**1.0204**	**1.0154**	**0.9865**	**2B**	**0.995**	**1.009**	**1.0219**	**1.0284**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0531**	**—**	**1.0219**	**1.0182**	**0.9880**	**3B**	**0.9950**	**1.0033**	**1.0219**	**1.0268**	**1.0625**
1 1/16–18 UNEF	**2A**	**0.0014**	**1.0611**	**1.0524**	**—**	**1.0250**	**1.0203**	**0.9950**	**2B**	**1.002**	**1.015**	**1.0264**	**1.0326**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0538**	**—**	**1.0264**	**1.0228**	**0.9964**	**3B**	**1.0020**	**1.0105**	**1.0264**	**1.0310**	**1.0625**
1 1/16–20 UN	**2A**	**0.0014**	**1.0611**	**1.0530**	**—**	**1.0286**	**1.0241**	**1.0016**	**2B**	**1.008**	**1.020**	**1.0300**	**1.0359**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0544**	**—**	**1.0300**	**1.0266**	**1.0030**	**3B**	**1.0080**	**1.0162**	**1.0300**	**1.0344**	**1.0625**
1 1/16–28 UN	**2A**	**0.0012**	**1.0613**	**1.0548**	**—**	**1.0381**	**1.0341**	**1.0187**	**2B**	**1.024**	**1.032**	**1.0393**	**1.0445**	**1.0625**
	3A	**0.0000**	**1.0625**	**1.0560**	**—**	**1.0393**	**1.0363**	**1.0199**	**3B**	**1.0240**	**1.0301**	**1.0393**	**1.0432**	**1.0625**
1 1/8–7 UNC	**1A**	**0.0022**	**1.1228**	**1.0982**	**—**	**1.0300**	**1.0191**	**0.9527**	**1B**	**0.970**	**0.998**	**1.0322**	**1.0463**	**1.1250**
	2A	**0.0022**	**1.1228**	**1.1064**	**1.0982**	**1.0300**	**1.0228**	**0.9527**	**2B**	**0.970**	**0.998**	**1.0322**	**1.0416**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1086**	**—**	**1.0322**	**1.0268**	**0.9549**	**3B**	**0.9700**	**0.9875**	**1.0322**	**1.0393**	**1.1250**
1 1/8–8 UN	**2A**	**0.0021**	**1.1229**	**1.1079**	**1.1004**	**1.0417**	**1.0348**	**0.9741**	**2B**	**0.990**	**1.015**	**1.0438**	**1.0528**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1100**	**—**	**1.0438**	**1.0386**	**0.9762**	**3B**	**0.9900**	**1.0047**	**1.0438**	**1.0505**	**1.1250**
1 1/8–10 UNS	**2A**	**0.0018**	**1.1232**	**1.1103**	**—**	**1.0582**	**1.0520**	**1.0042**	**2B**	**1.017**	**1.038**	**1.0600**	**1.0680**	**1.1250**
1 1/8–12 UNF	**1A**	**0.0018**	**1.1232**	**1.1060**	**—**	**1.0691**	**1.0601**	**1.0240**	**1B**	**1.035**	**1.053**	**1.0709**	**1.0826**	**1.1250**
	2A	**0.0018**	**1.1232**	**1.1118**	**—**	**1.0691**	**1.0631**	**1.0240**	**2B**	**1.035**	**1.053**	**1.0709**	**1.0787**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1136**	**—**	**1.0709**	**1.0664**	**1.0258**	**3B**	**1.0350**	**1.0448**	**1.0709**	**1.0768**	**1.1250**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1⅛–14 UNS	**2A**	**0.0016**	**1.1234**	**1.1131**	—	**1.0770**	**1.0717**	**1.0384**	**2B**	**1.048**	**1.064**	**1.0786**	**1.0855**	**1.1250**
1⅛–16 UN	**2A**	**0.0015**	**1.1235**	**1.1141**	—	**1.0829**	**1.0779**	**1.0490**	**2B**	**1.057**	**1.071**	**1.0844**	**1.0909**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1156**	—	**1.0844**	**1.0807**	**1.0505**	**3B**	**1.0570**	**1.0658**	**1.0844**	**1.0893**	**1.1250**
1⅛–18 UNEF	**2A**	**0.0014**	**1.1236**	**1.1149**	—	**1.0875**	**1.0828**	**1.0575**	**2B**	**1.065**	**1.078**	**1.0889**	**1.0951**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1163**	—	**1.0889**	**1.0853**	**1.0589**	**3B**	**1.0650**	**1.0730**	**1.0889**	**1.0935**	**1.1250**
1⅛–20 UN	**2A**	**0.0014**	**1.1236**	**1.1155**	—	**1.0911**	**1.0866**	**1.0641**	**2B**	**1.071**	**1.082**	**1.0925**	**1.0984**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1169**	—	**1.0925**	**1.0891**	**1.0655**	**3B**	**1.0710**	**1.0787**	**1.0925**	**1.0969**	**1.1250**
1⅛–24 UNS	**2A**	**0.0013**	**1.1237**	**1.1165**	—	**1.0966**	**1.0924**	**1.0742**	**2B**	**1.080**	**1.090**	**1.0979**	**1.1034**	**1.1250**
1⅛–28 UN	**2A**	**0.0012**	**1.1238**	**1.1173**	—	**1.1006**	**1.0966**	**1.0812**	**2B**	**1.086**	**1.095**	**1.1018**	**1.1070**	**1.1250**
	3A	**0.0000**	**1.1250**	**1.1185**	—	**1.1018**	**1.0988**	**1.0824**	**3B**	**1.0860**	**1.0926**	**1.1018**	**1.1057**	**1.1250**
1 3/16–8 UN	**2A**	**0.0021**	**1.1854**	**1.1704**	—	**1.1042**	**1.0972**	**1.0366**	**2B**	**1.052**	**1.077**	**1.1063**	**1.1154**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1725**	—	**1.1063**	**1.1011**	**1.0387**	**3B**	**1.0520**	**1.0672**	**1.1063**	**1.1131**	**1.1875**
1 3/16–12 UN	**2A**	**0.0017**	**1.1858**	**1.1744**	—	**1.1317**	**1.1259**	**1.0866**	**2B**	**1.097**	**1.115**	**1.1334**	**1.1409**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1761**	—	**1.1334**	**1.1291**	**1.0883**	**3B**	**1.0970**	**1.1073**	**1.1334**	**1.1390**	**1.1875**
1 3/16–16 UN	**2A**	**0.0015**	**1.1860**	**1.1766**	—	**1.1454**	**1.1403**	**1.1115**	**2B**	**1.120**	**1.134**	**1.1469**	**1.1535**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1781**	—	**1.1469**	**1.1431**	**1.1130**	**3B**	**1.1200**	**1.1283**	**1.1469**	**1.1519**	**1.1875**
1 3/16–18 UNEF	**2A**	**0.0015**	**1.1860**	**1.1773**	—	**1.1499**	**1.1450**	**1.1199**	**2B**	**1.127**	**1.140**	**1.1514**	**1.1577**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1788**	—	**1.1514**	**1.1478**	**1.1214**	**3B**	**1.1270**	**1.1355**	**1.1514**	**1.1561**	**1.1875**
1 3/16–20 UN	**2A**	**0.0014**	**1.1861**	**1.1780**	—	**1.1536**	**1.1489**	**1.1266**	**2B**	**1.133**	**1.145**	**1.1550**	**1.1611**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1794**	—	**1.1550**	**1.1515**	**1.1280**	**3B**	**1.1330**	**1.1412**	**1.1550**	**1.1595**	**1.1875**
1 3/16–28 UN	**2A**	**0.0012**	**1.1863**	**1.1798**	—	**1.1631**	**1.1590**	**1.1437**	**2B**	**1.149**	**1.157**	**1.1643**	**1.1696**	**1.1875**
	3A	**0.0000**	**1.1875**	**1.1810**	—	**1.1643**	**1.1612**	**1.1449**	**3B**	**1.1490**	**1.1551**	**1.1643**	**1.1683**	**1.1875**
1¼–7 UNC	**1A**	**0.0022**	**1.2478**	**1.2232**	—	**1.1550**	**1.1439**	**1.0777**	**1B**	**1.095**	**1.123**	**1.1572**	**1.1716**	**1.2500**
	2A	**0.0022**	**1.2478**	**1.2314**	**1.2232**	**1.1550**	**1.1476**	**1.0777**	**2B**	**1.095**	**1.123**	**1.1572**	**1.1668**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2336**	—	**1.1572**	**1.1517**	**1.0799**	**3B**	**1.0950**	**1.1125**	**1.1572**	**1.1644**	**1.2500**
1¼–8 UN	**2A**	**0.0021**	**1.2479**	**1.2329**	**1.2254**	**1.1667**	**1.1597**	**1.0991**	**2B**	**1.115**	**1.140**	**1.1688**	**1.1780**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2350**	—	**1.1688**	**1.1635**	**1.1012**	**3B**	**1.1150**	**1.1297**	**1.1688**	**1.1757**	**1.2500**
1¼–10 UNS	**2A**	**0.0019**	**1.2481**	**1.2352**	—	**1.1831**	**1.1768**	**1.1291**	**2B**	**1.142**	**1.163**	**1.1850**	**1.1932**	**1.2500**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1¼–12 UNF	**1A**	**0.0018**	**1.2482**	**1.2310**	**—**	**1.1941**	**1.1849**	**1.1490**	**1B**	**1.160**	**1.178**	**1.1959**	**1.2079**	**1.2500**
	2A	**0.0018**	**1.2482**	**1.2368**	**—**	**1.1941**	**1.1879**	**1.1490**	**2B**	**1.160**	**1.178**	**1.1959**	**1.2039**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2386**	**—**	**1.1959**	**1.1913**	**1.1508**	**3B**	**1.1600**	**1.1698**	**1.1959**	**1.2019**	**1.2500**
1¼–14 UNS	**2A**	**0.0016**	**1.2484**	**1.2381**	**—**	**1.2020**	**1.1966**	**1.1634**	**2B**	**1.173**	**1.188**	**1.2036**	**1.2106**	**1.2500**
1¼–16 UN	**2A**	**0.0015**	**1.2485**	**1.2391**	**—**	**1.2079**	**1.2028**	**1.1740**	**2B**	**1.182**	**1.196**	**1.2094**	**1.2160**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2406**	**—**	**1.2094**	**1.2056**	**1.1755**	**3B**	**1.1820**	**1.1908**	**1.2094**	**1.2144**	**1.2500**
1¼–18 UNEF	**2A**	**0.0015**	**1.2485**	**1.2398**	**—**	**1.2124**	**1.2075**	**1.1824**	**2B**	**1.190**	**1.203**	**1.2139**	**1.2202**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2413**	**—**	**1.2139**	**1.2103**	**1.1839**	**3B**	**1.1900**	**1.1980**	**1.2139**	**1.2186**	**1.2500**
1¼–20 UN	**2A**	**0.0014**	**1.2486**	**1.2405**	**—**	**1.2161**	**1.2114**	**1.1891**	**2B**	**1.196**	**1.207**	**1.2175**	**1.2236**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2419**	**—**	**1.2175**	**1.2140**	**1.1905**	**3B**	**1.1960**	**1.2037**	**1.2175**	**1.2220**	**1.2500**
1¼–24 UNS	**2A**	**0.0013**	**1.2487**	**1.2415**	**—**	**1.2216**	**1.2173**	**1.1991**	**2B**	**1.205**	**1.215**	**1.2229**	**1.2285**	**1.2500**
1¼–28 UN	**2A**	**0.0012**	**1.2488**	**1.2423**	**—**	**1.2256**	**1.2215**	**1.2062**	**2B**	**1.211**	**1.220**	**1.2268**	**1.2321**	**1.2500**
	3A	**0.0000**	**1.2500**	**1.2435**	**—**	**1.2268**	**1.2237**	**1.2074**	**3B**	**1.2110**	**1.2176**	**1.2268**	**1.2308**	**1.2500**
1⅝–8 UN	**2A**	**0.0021**	**1.3104**	**1.2954**	**—**	**1.2292**	**1.2221**	**1.1616**	**2B**	**1.177**	**1.202**	**1.2313**	**1.2405**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.2975**	**—**	**1.2313**	**1.2260**	**1.1637**	**3B**	**1.1770**	**1.1922**	**1.2313**	**1.2382**	**1.3125**
1⅝–12 UN	**2A**	**0.0017**	**1.3108**	**1.2994**	**—**	**1.2567**	**1.2509**	**1.2116**	**2B**	**1.222**	**1.240**	**1.2584**	**1.2659**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.3011**	**—**	**1.2584**	**1.2541**	**1.2133**	**3B**	**1.2220**	**1.2323**	**1.2584**	**1.2640**	**1.3125**
1⅝–16 UN	**2A**	**0.0015**	**1.3110**	**1.3016**	**—**	**1.2704**	**1.2653**	**1.2365**	**2B**	**1.245**	**1.259**	**1.2719**	**1.2785**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.3031**	**—**	**1.2719**	**1.2681**	**1.2380**	**3B**	**1.2450**	**1.2533**	**1.2719**	**1.2769**	**1.3125**
1⅝–18 UNEF	**2A**	**0.0015**	**1.3110**	**1.3023**	**—**	**1.2749**	**1.2700**	**1.2449**	**2B**	**1.252**	**1.265**	**1.2764**	**1.2827**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.3038**	**—**	**1.2764**	**1.2728**	**1.2464**	**3B**	**1.2520**	**1.2605**	**1.2764**	**1.2811**	**1.3125**
1⅝–20 UN	**2A**	**0.0014**	**1.3111**	**1.3030**	**—**	**1.2786**	**1.2739**	**1.2516**	**2B**	**1.258**	**1.270**	**1.2800**	**1.2861**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.3044**	**—**	**1.2800**	**1.2765**	**1.2530**	**3B**	**1.2580**	**1.2662**	**1.2800**	**1.2845**	**1.3125**
1⅝–28 UN	**2A**	**0.0012**	**1.3113**	**1.3048**	**—**	**1.2881**	**1.2840**	**1.2687**	**2B**	**1.274**	**1.282**	**1.2893**	**1.2946**	**1.3125**
	3A	**0.0000**	**1.3125**	**1.3060**	**—**	**1.2893**	**1.2862**	**1.2699**	**3B**	**1.2740**	**1.2801**	**1.2893**	**1.2933**	**1.3125**
1⅜–6 UNC	**1A**	**0.0024**	**1.3726**	**1.3453**	**—**	**1.2643**	**1.2523**	**1.1742**	**1B**	**1.195**	**1.225**	**1.2667**	**1.2822**	**1.3750**
	2A	**0.0024**	**1.3726**	**1.3544**	**1.3453**	**1.2643**	**1.2563**	**1.1742**	**2B**	**1.195**	**1.225**	**1.2667**	**1.2771**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3568**	**—**	**1.2667**	**1.2607**	**1.1766**	**3B**	**1.1950**	**1.2146**	**1.2667**	**1.2745**	**1.3750**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$1\frac{3}{8}$–8 UN	**2A**	**0.0022**	**1.3728**	**1.3578**	**1.3503**	**1.2916**	**1.2844**	**1.2240**	**2B**	**1.240**	**1.265**	**1.2938**	**1.3031**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3600**	—	**1.2938**	**1.2884**	**1.2262**	**3B**	**1.2400**	**1.2547**	**1.2938**	**1.3008**	**1.3750**
$1\frac{3}{8}$–10 UNS	**2A**	**0.0019**	**1.3731**	**1.3602**	—	**1.3081**	**1.3018**	**1.2541**	**2B**	**1.267**	**1.288**	**1.3100**	**1.3182**	**1.3750**
$1\frac{3}{8}$–12 UNF	**1A**	**0.0019**	**1.3731**	**1.3559**	—	**1.3190**	**1.3096**	**1.2739**	**1B**	**1.285**	**1.303**	**1.3209**	**1.3332**	**1.3750**
	2A	**0.0019**	**1.3731**	**1.3617**	—	**1.3190**	**1.3127**	**1.2739**	**2B**	**1.285**	**1.303**	**1.3209**	**1.3291**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3636**	—	**1.3209**	**1.3162**	**1.2758**	**3B**	**1.2850**	**1.2948**	**1.3209**	**1.3270**	**1.3750**
$1\frac{3}{8}$–14 UNS	**2A**	**0.0016**	**1.3734**	**1.3631**	—	**1.3270**	**1.3216**	**1.2884**	**2B**	**1.298**	**1.314**	**1.3286**	**1.3356**	**1.3750**
$1\frac{3}{8}$–16 UN	**2A**	**0.0015**	**1.3735**	**1.3641**	—	**1.3329**	**1.3278**	**1.2990**	**2B**	**1.307**	**1.321**	**1.3344**	**1.3410**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3656**	—	**1.3344**	**1.3306**	**1.3005**	**3B**	**1.3070**	**1.3158**	**1.3344**	**1.3394**	**1.3750**
$1\frac{3}{8}$–18 UNEF	**2A**	**0.0015**	**1.3735**	**1.3648**	—	**1.3374**	**1.3325**	**1.3074**	**2B**	**1.315**	**1.328**	**1.3389**	**1.3452**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3663**	—	**1.3389**	**1.3353**	**1.3089**	**3B**	**1.3150**	**1.3230**	**1.3389**	**1.3436**	**1.3750**
$1\frac{3}{8}$–20 UN	**2A**	**0.0014**	**1.3736**	**1.3655**	—	**1.3411**	**1.3364**	**1.3141**	**2B**	**1.321**	**1.332**	**1.3425**	**1.3486**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3669**	—	**1.3425**	**1.3390**	**1.3155**	**3B**	**1.3210**	**1.3287**	**1.3425**	**1.3470**	**1.3750**
$1\frac{3}{8}$–24 UNS	**2A**	**0.0013**	**1.3737**	**1.3665**	—	**1.3466**	**1.3423**	**1.3241**	**2B**	**1.330**	**1.340**	**1.3479**	**1.3535**	**1.3750**
$1\frac{3}{8}$–28 UN	**2A**	**0.0012**	**1.3738**	**1.3673**	—	**1.3506**	**1.3465**	**1.3312**	**2B**	**1.336**	**1.345**	**1.3518**	**1.3571**	**1.3750**
	3A	**0.0000**	**1.3750**	**1.3685**	—	**1.3518**	**1.3487**	**1.3324**	**3B**	**1.3360**	**1.3426**	**1.3518**	**1.3558**	**1.3750**
$1\frac{7}{16}$–6 UN	**2A**	**0.0024**	**1.4351**	**1.4169**	—	**1.3268**	**1.3188**	**1.2367**	**2B**	**1.257**	**1.288**	**1.3292**	**1.3396**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4193**	—	**1.3292**	**1.3232**	**1.2391**	**3B**	**1.2570**	**1.2771**	**1.3292**	**1.3370**	**1.4375**
$1\frac{7}{16}$–8 UN	**2A**	**0.0022**	**1.4353**	**1.4203**	—	**1.3541**	**1.3469**	**1.2865**	**2B**	**1.302**	**1.327**	**1.3563**	**1.3657**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4225**	—	**1.3563**	**1.3509**	**1.2887**	**3B**	**1.3020**	**1.3172**	**1.3563**	**1.3634**	**1.4375**
$1\frac{7}{16}$–12 UN	**2A**	**0.0018**	**1.4357**	**1.4243**	—	**1.3816**	**1.3757**	**1.3365**	**2B**	**1.347**	**1.365**	**1.3834**	**1.3910**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4261**	—	**1.3834**	**1.3790**	**1.3383**	**3B**	**1.3470**	**1.3573**	**1.3834**	**1.3891**	**1.4375**
$1\frac{7}{16}$–16 UN	**2A**	**0.0016**	**1.4359**	**1.4265**	—	**1.3953**	**1.3901**	**1.3614**	**2B**	**1.370**	**1.384**	**1.3969**	**1.4037**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4281**	—	**1.3969**	**1.3930**	**1.3630**	**3B**	**1.3700**	**1.3783**	**1.3969**	**1.4020**	**1.4375**
$1\frac{7}{16}$–18 UNEF	**2A**	**0.0015**	**1.4360**	**1.4273**	—	**1.3999**	**1.3949**	**1.3699**	**2B**	**1.377**	**1.390**	**1.4014**	**1.4079**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4288**	—	**1.4014**	**1.3977**	**1.3714**	**3B**	**1.3770**	**1.3855**	**1.4014**	**1.4062**	**1.4375**
$1\frac{7}{16}$–20 UN	**2A**	**0.0014**	**1.4361**	**1.4280**	—	**1.4036**	**1.3988**	**1.3766**	**2B**	**1.383**	**1.395**	**1.4050**	**1.4112**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4294**	—	**1.4050**	**1.4014**	**1.3780**	**3B**	**1.3830**	**1.3912**	**1.4050**	**1.4096**	**1.4375**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$1\frac{7}{16}$–28 UN	**2A**	**0.0013**	**1.4362**	**1.4297**	—	**1.4130**	**1.4088**	**1.3936**	**2B**	**1.399**	**1.407**	**1.4143**	**1.4198**	**1.4375**
	3A	**0.0000**	**1.4375**	**1.4310**	—	**1.4143**	**1.4112**	**1.3949**	**3B**	**1.3990**	**1.4051**	**1.4143**	**1.4184**	**1.4375**
$1\frac{1}{2}$–6	**1A**	**0.0024**	**1.4976**	**1.4703**	—	**1.3893**	**1.3772**	**1.2992**	**1B**	**1.320**	**1.350**	**1.3917**	**1.4075**	**1.5000**
	2A	**0.0024**	**1.4976**	**1.4794**	**1.4703**	**1.3893**	**1.3812**	**1.2992**	**2B**	**1.320**	**1.350**	**1.3917**	**1.4022**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4818**	—	**1.3917**	**1.3856**	**1.3016**	**3B**	**1.3200**	**1.3396**	**1.3917**	**1.3996**	**1.5000**
$1\frac{1}{2}$–8 UN	**2A**	**0.0022**	**1.4978**	**1.4828**	**1.4753**	**1.4166**	**1.4093**	**1.3490**	**2B**	**1.365**	**1.390**	**1.4188**	**1.4283**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4850**	—	**1.4188**	**1.4133**	**1.3512**	**3B**	**1.3650**	**1.3797**	**1.4188**	**1.4259**	**1.5000**
$1\frac{1}{2}$–10 UNS	**2A**	**0.0019**	**1.4981**	**1.4852**	—	**1.4331**	**1.4267**	**1.3791**	**2B**	**1.392**	**1.413**	**1.4350**	**1.4433**	**1.5000**
$1\frac{1}{2}$–12 UNF	**1A**	**0.0019**	**1.4981**	**1.4809**	—	**1.4440**	**1.4344**	**1.3989**	**1B**	**1.410**	**1.428**	**1.4459**	**1.4584**	**1.5000**
	2A	**0.0019**	**1.4981**	**1.4867**	—	**1.4440**	**1.4376**	**1.3989**	**2B**	**1.410**	**1.428**	**1.4459**	**1.4542**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4886**	—	**1.4459**	**1.4411**	**1.4008**	**3B**	**1.4100**	**1.4198**	**1.4459**	**1.4522**	**1.5000**
$1\frac{1}{2}$–14 UNS	**2A**	**0.0017**	**1.4983**	**1.4880**	—	**1.4519**	**1.4464**	**1.4133**	**2B**	**1.423**	**1.438**	**1.4536**	**1.4608**	**1.5000**
$1\frac{1}{2}$–16 UN	**2A**	**0.0016**	**1.4984**	**1.4890**	—	**1.4578**	**1.4526**	**1.4239**	**2B**	**1.432**	**1.446**	**1.4594**	**1.4662**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4906**	—	**1.4594**	**1.4555**	**1.4255**	**3B**	**1.4320**	**1.4408**	**1.4594**	**1.4645**	**1.5000**
$1\frac{1}{2}$–18 UNEF	**2A**	**0.0015**	**1.4985**	**1.4898**	—	**1.4624**	**1.4574**	**1.4324**	**2B**	**1.440**	**1.452**	**1.4639**	**1.4704**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4913**	—	**1.4639**	**1.4602**	**1.4339**	**3B**	**1.4400**	**1.4480**	**1.4639**	**1.4687**	**1.5000**
$1\frac{1}{2}$–20 UN	**2A**	**0.0014**	**1.4986**	**1.4905**	—	**1.4661**	**1.4613**	**1.4391**	**2B**	**1.446**	**1.457**	**1.4675**	**1.4737**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4919**	—	**1.4675**	**1.4639**	**1.4405**	**3B**	**1.4460**	**1.4537**	**1.4675**	**1.4721**	**1.5000**
$1\frac{1}{2}$–24 UNS	**2A**	**0.0013**	**1.4987**	**1.4915**	—	**1.4716**	**1.4672**	**1.4491**	**2B**	**1.455**	**1.465**	**1.4729**	**1.4787**	**1.5000**
$1\frac{1}{2}$–28 UN	**2A**	**0.0013**	**1.4987**	**1.4922**	—	**1.4755**	**1.4713**	**1.4561**	**2B**	**1.461**	**1.470**	**1.4768**	**1.4823**	**1.5000**
	3A	**0.0000**	**1.5000**	**1.4935**	—	**1.4768**	**1.4737**	**1.4574**	**3B**	**1.4610**	**1.4676**	**1.4768**	**1.4809**	**1.5000**
$1\frac{9}{16}$–6 UN	**2A**	**0.0024**	**1.5601**	**1.5419**	—	**1.4518**	**1.4436**	**1.3617**	**2B**	**1.382**	**1.413**	**1.4542**	**1.4648**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5443**	—	**1.4542**	**1.4481**	**1.3641**	**3B**	**1.3820**	**1.4021**	**1.4542**	**1.4622**	**1.5625**
$1\frac{9}{16}$–8 UN	**2A**	**0.0022**	**1.5603**	**1.5453**	—	**1.4791**	**1.4717**	**1.4115**	**2B**	**1.427**	**1.452**	**1.4813**	**1.4909**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5475**	—	**1.4813**	**1.4758**	**1.4137**	**3B**	**1.4270**	**1.4422**	**1.4813**	**1.4885**	**1.5625**
$1\frac{9}{16}$–12 UN	**2A**	**0.0018**	**1.5607**	**1.5493**	—	**1.5066**	**1.5007**	**1.4615**	**2B**	**1.472**	**1.490**	**1.5084**	**1.5160**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5511**	—	**1.5084**	**1.5040**	**1.4633**	**3B**	**1.4720**	**1.4823**	**1.5084**	**1.5141**	**1.5625**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$1\frac{9}{16}$–16 UN	**2A**	**0.0016**	**1.5609**	**1.5515**	—	**1.5203**	**1.5151**	**1.4864**	**2B**	**1.495**	**1.509**	**1.5219**	**1.5287**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5531**	—	**1.5219**	**1.5180**	**1.4880**	**3B**	**1.4950**	**1.5033**	**1.5219**	**1.5270**	**1.5625**
$1\frac{9}{16}$–18 UNEF	**2A**	**0.0015**	**1.5610**	**1.5523**	—	**1.5249**	**1.5199**	**1.4949**	**2B**	**1.502**	**1.515**	**1.5264**	**1.5329**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5538**	—	**1.5264**	**1.5227**	**1.4964**	**3B**	**1.5020**	**1.5105**	**1.5264**	**1.5312**	**1.5625**
$1\frac{9}{16}$–20 UN	**2A**	**0.0014**	**1.5611**	**1.5530**	—	**1.5286**	**1.5238**	**1.5016**	**2B**	**1.508**	**1.520**	**1.5300**	**1.5362**	**1.5625**
	3A	**0.0000**	**1.5625**	**1.5544**	—	**1.5300**	**1.5264**	**1.5030**	**3B**	**1.5080**	**1.5162**	**1.5300**	**1.5346**	**1.5625**
$1\frac{5}{8}$–6 UN	**2A**	**0.0025**	**1.6225**	**1.6043**	—	**1.5142**	**1.5060**	**1.4246**	**2B**	**1.445**	**1.475**	**1.5167**	**1.5274**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6068**	—	**1.5167**	**1.5105**	**1.4271**	**3B**	**1.4450**	**1.4646**	**1.5167**	**1.5247**	**1.6250**
$1\frac{5}{8}$–8 UN	**2A**	**0.0022**	**1.6228**	**1.6078**	**1.6003**	**1.5416**	**1.5342**	**1.4784**	**2B**	**1.490**	**1.515**	**1.5438**	**1.5535**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6100**	—	**1.5438**	**1.5382**	**1.4806**	**3B**	**1.4900**	**1.5047**	**1.5438**	**1.5510**	**1.6250**
$1\frac{5}{8}$–10 UNS	**2A**	**0.0019**	**1.6231**	**1.6102**	—	**1.5581**	**1.5517**	**1.5041**	**2B**	**1.517**	**1.538**	**1.5600**	**1.5683**	**1.6250**
$1\frac{5}{8}$–12 UN	**2A**	**0.0018**	**1.6232**	**1.6118**	—	**1.5691**	**1.5632**	**1.5240**	**2B**	**1.535**	**1.553**	**1.5709**	**1.5785**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6136**	—	**1.5709**	**1.5665**	**1.5258**	**3B**	**1.5350**	**1.5448**	**1.5709**	**1.5766**	**1.6250**
$1\frac{5}{8}$–14 UNS	**2A**	**0.0017**	**1.6233**	**1.6130**	—	**1.5769**	**1.5714**	**1.5383**	**2B**	**1.548**	**1.564**	**1.5786**	**1.5858**	**1.6250**
$1\frac{5}{8}$–16 UN	**2A**	**0.0016**	**1.6234**	**1.6140**	—	**1.5828**	**1.5776**	**1.5489**	**2B**	**1.557**	**1.571**	**1.5844**	**1.5912**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6156**	—	**1.5844**	**1.5805**	**1.5505**	**3B**	**1.5570**	**1.5658**	**1.5844**	**1.5895**	**1.6250**
$1\frac{5}{8}$–18 UNEF	**2A**	**0.0015**	**1.6235**	**1.6148**	—	**1.5874**	**1.5824**	**1.5574**	**2B**	**1.565**	**1.578**	**1.5889**	**1.5954**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6163**	—	**1.5889**	**1.5852**	**1.5589**	**3B**	**1.5650**	**1.5730**	**1.5889**	**1.5937**	**1.6250**
$1\frac{5}{8}$–20 UN	**2A**	**0.0014**	**1.6236**	**1.6155**	—	**1.5911**	**1.5863**	**1.5641**	**2B**	**1.571**	**1.582**	**1.5925**	**1.5987**	**1.6250**
	3A	**0.0000**	**1.6250**	**1.6169**	—	**1.5925**	**1.5889**	**1.5655**	**3B**	**1.5710**	**1.5787**	**1.5925**	**1.5971**	**1.6250**
$1\frac{5}{8}$–24 UNS	**2A**	**0.0013**	**1.6237**	**1.6165**	—	**1.5966**	**1.5922**	**1.5741**	**2B**	**1.580**	**1.590**	**1.5979**	**1.6037**	**1.6250**
$1\frac{11}{16}$–6 UN	**2A**	**0.0025**	**1.6850**	**1.6668**	—	**1.5767**	**1.5684**	**1.4866**	**2B**	**1.507**	**1.538**	**1.5792**	**1.5900**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6693**	—	**1.5792**	**1.5730**	**1.4891**	**3B**	**1.5070**	**1.5271**	**1.5792**	**1.5873**	**1.6875**
$1\frac{11}{16}$–8 UN	**2A**	**0.0022**	**1.6853**	**1.6703**	—	**1.6041**	**1.5966**	**1.5365**	**2B**	**1.552**	**1.577**	**1.6063**	**1.6160**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6725**	—	**1.6063**	**1.6007**	**1.5387**	**3B**	**1.5520**	**1.5672**	**1.6063**	**1.6136**	**1.6875**
$1\frac{11}{16}$–12 UN	**2A**	**0.0018**	**1.6857**	**1.6743**	—	**1.6316**	**1.6256**	**1.5865**	**2B**	**1.597**	**1.615**	**1.6334**	**1.6412**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6761**	—	**1.6334**	**1.6289**	**1.5883**	**3B**	**1.5970**	**1.6073**	**1.6334**	**1.6392**	**1.6875**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
1 11/16–16 UN	**2A**	**0.0016**	**1.6859**	**1.6765**	—	**1.6453**	**1.6400**	**1.6114**	**2B**	**1.620**	**1.634**	**1.6469**	**1.6538**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6781**	—	**1.6469**	**1.6429**	**1.6130**	**3B**	**1.6200**	**1.6283**	**1.6469**	**1.6521**	**1.6875**
1 11/16–18 UNEF	**2A**	**0.0015**	**1.6860**	**1.6773**	—	**1.6499**	**1.6448**	**1.6199**	**2B**	**1.627**	**1.640**	**1.6514**	**1.6580**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6788**	—	**1.6514**	**1.6476**	**1.6214**	**3B**	**1.6270**	**1.6355**	**1.6514**	**1.6563**	**1.6875**
1 11/16–20 UN	**2A**	**0.0015**	**1.6860**	**1.6779**	—	**1.6535**	**1.6487**	**1.6265**	**2B**	**1.633**	**1.645**	**1.6550**	**1.6613**	**1.6875**
	3A	**0.0000**	**1.6875**	**1.6794**	—	**1.6550**	**1.6514**	**1.6280**	**3B**	**1.6330**	**1.6412**	**1.6550**	**1.6597**	**1.6875**
1 3/4–5 UNC	**1A**	**0.0027**	**1.7473**	**1.7165**	—	**1.6174**	**1.6040**	**1.5092**	**1B**	**1.534**	**1.568**	**1.6201**	**1.6375**	**1.7500**
	2A	**0.0027**	**1.7473**	**1.7268**	**1.7165**	**1.6174**	**1.6085**	**1.5092**	**2B**	**1.534**	**1.568**	**1.6201**	**1.6317**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7295**	—	**1.6201**	**1.6134**	**1.5119**	**3B**	**1.5340**	**1.5575**	**1.6201**	**1.6288**	**1.7500**
1 3/4–6 UN	**2A**	**0.0025**	**1.7475**	**1.7293**	—	**1.6392**	**1.6309**	**1.5491**	**2B**	**1.570**	**1.600**	**1.6417**	**1.6525**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7318**	—	**1.6417**	**1.6354**	**1.5516**	**3B**	**1.5700**	**1.5896**	**1.6417**	**1.6498**	**1.7500**
1 3/4–8 UN	**2A**	**0.0023**	**1.7477**	**1.7327**	**1.7252**	**1.6665**	**1.6590**	**1.5989**	**2B**	**1.615**	**1.640**	**1.6688**	**1.6786**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7350**	—	**1.6688**	**1.6632**	**1.6012**	**3B**	**1.6150**	**1.6297**	**1.6688**	**1.6762**	**1.7500**
1 3/4–10 UNS	**2A**	**0.0019**	**1.7481**	**1.7352**	—	**1.6831**	**1.6766**	**1.6291**	**2B**	**1.642**	**1.663**	**1.6850**	**1.6934**	**1.7500**
1 3/4–12 UN	**2A**	**0.0018**	**1.7482**	**1.7368**	—	**1.6941**	**1.6881**	**1.6490**	**2B**	**1.660**	**1.678**	**1.6959**	**1.7037**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7386**	—	**1.6959**	**1.6914**	**1.6508**	**3B**	**1.6600**	**1.6698**	**1.6959**	**1.7017**	**1.7500**
1 3/4–14 UNS	**2A**	**0.0017**	**1.7483**	**1.7380**	—	**1.7019**	**1.6963**	**1.6632**	**2B**	**1.673**	**1.688**	**1.7036**	**1.7109**	**1.7500**
1 3/4–16 UN	**2A**	**0.0016**	**1.7484**	**1.7390**	—	**1.7078**	**1.7025**	**1.6739**	**2B**	**1.682**	**1.696**	**1.7094**	**1.7163**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7406**	—	**1.7094**	**1.7054**	**1.6755**	**3B**	**1.6820**	**1.6908**	**1.7094**	**1.7146**	**1.7500**
1 3/4–18 UNS	**2A**	**0.0015**	**1.7485**	**1.7398**	—	**1.7124**	**1.7073**	**1.6824**	**2B**	**1.690**	**1.703**	**1.7139**	**1.7205**	**1.7500**
1 3/4–20 UN	**2A**	**0.0015**	**1.7485**	**1.7404**	—	**1.7160**	**1.7112**	**1.6890**	**2B**	**1.696**	**1.707**	**1.7175**	**1.7238**	**1.7500**
	3A	**0.0000**	**1.7500**	**1.7419**	—	**1.7175**	**1.7139**	**1.6905**	**3B**	**1.6960**	**1.7037**	**1.7175**	**1.7222**	**1.7500**
1 13/16–6 UN	**2A**	**0.0025**	**1.8100**	**1.7918**	—	**1.7017**	**1.6933**	**1.6116**	**2B**	**1.632**	**1.663**	**1.7042**	**1.7151**	**1.8125**
	3A	**0.0000**	**1.8125**	**1.7943**	—	**1.7042**	**1.6979**	**1.6141**	**3B**	**1.6320**	**1.6521**	**1.7042**	**1.7124**	**1.8125**
1 13/16–8 UN	**2A**	**0.0023**	**1.8102**	**1.7952**	—	**1.7290**	**1.7214**	**1.6614**	**2B**	**1.677**	**1.702**	**1.7313**	**1.7412**	**1.8125**
	3A	**0.0000**	**1.8125**	**1.7975**	—	**1.7313**	**1.7256**	**1.6637**	**3B**	**1.6770**	**1.6922**	**1.7313**	**1.7387**	**1.8125**
1 13/16–12 UN	**2A**	**0.0018**	**1.8107**	**1.7993**	—	**1.7566**	**1.7506**	**1.7115**	**2B**	**1.722**	**1.740**	**1.7584**	**1.7662**	**1.8125**
	3A	**0.0000**	**1.8125**	**1.8011**	—	**1.7584**	**1.7539**	**1.7133**	**3B**	**1.7220**	**1.7323**	**1.7584**	**1.7642**	**1.8125**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$1\frac{13}{16}$–16 UN	**2A**	**0.0016**	**1.8109**	**1.8015**	**—**	**1.7703**	**1.7650**	**1.7364**	**2B**	**1.745**	**1.759**	**1.7719**	**1.7788**	**1.8125**
	3A	**0.0000**	**1.8125**	**1.8031**	**—**	**1.7719**	**1.7679**	**1.7380**	**3B**	**1.7450**	**1.7533**	**1.7719**	**1.7771**	**1.8125**
$1\frac{13}{16}$–20 UN	**2A**	**0.0015**	**1.8110**	**1.8029**	**—**	**1.7785**	**1.7737**	**1.7515**	**2B**	**1.758**	**1.770**	**1.7800**	**1.7863**	**1.8125**
	3A	**0.0000**	**1.8125**	**1.8044**	**—**	**1.7800**	**1.7764**	**1.7530**	**3B**	**1.7580**	**1.7662**	**1.7800**	**1.7847**	**1.8125**
$1\frac{7}{8}$–6 UN	**2A**	**0.0025**	**1.8725**	**1.8543**	**—**	**1.7642**	**1.7558**	**1.6741**	**2B**	**1.695**	**1.725**	**1.7667**	**1.7777**	**1.8750**
	3A	**0.0000**	**1.8750**	**1.8568**	**—**	**1.7667**	**1.7604**	**1.6766**	**3B**	**1.6950**	**1.7146**	**1.7667**	**1.7749**	**1.8750**
$1\frac{7}{8}$–8 UN	**2A**	**0.0023**	**1.8727**	**1.8577**	**1.8502**	**1.7915**	**1.7838**	**1.7239**	**2B**	**1.740**	**1.765**	**1.7938**	**1.8038**	**1.8750**
	3A	**0.0000**	**1.8750**	**1.8600**	**—**	**1.7938**	**1.7881**	**1.7262**	**3B**	**1.7400**	**1.7547**	**1.7938**	**1.8013**	**1.8750**
$1\frac{7}{8}$–10 UNS	**2A**	**0.0019**	**1.8731**	**1.8602**	**—**	**1.8081**	**1.8016**	**1.7541**	**2B**	**1.767**	**1.788**	**1.8100**	**1.8184**	**1.8750**
$1\frac{7}{8}$–12 UN	**2A**	**0.0018**	**1.8732**	**1.8618**	**—**	**1.8191**	**1.8131**	**1.7740**	**2B**	**1.785**	**1.803**	**1.8209**	**1.8287**	**1.8750**
	3A	**0.0000**	**1.8750**	**1.8636**	**—**	**1.8209**	**1.8164**	**1.7758**	**3B**	**1.7850**	**1.7948**	**1.8209**	**1.8267**	**1.8750**
$1\frac{7}{8}$–14 UNS	**2A**	**0.0017**	**1.8733**	**1.8630**	**—**	**1.8269**	**1.8213**	**1.7883**	**2B**	**1.798**	**1.814**	**1.8286**	**1.8359**	**1.8750**
$1\frac{7}{8}$–16 UN	**2A**	**0.0016**	**1.8734**	**1.8640**	**—**	**1.8328**	**1.8275**	**1.7989**	**2B**	**1.807**	**1.821**	**1.8344**	**1.8413**	**1.8750**
	3A	**0.0000**	**1.8750**	**1.8656**	**—**	**1.8344**	**1.8304**	**1.8005**	**3B**	**1.8070**	**1.8158**	**1.8344**	**1.8396**	**1.8750**
$1\frac{7}{8}$–18 UNS	**2A**	**0.0015**	**1.8735**	**1.8648**	**—**	**1.8374**	**1.8323**	**1.8074**	**2B**	**1.815**	**1.828**	**1.8389**	**1.8455**	**1.8750**
$1\frac{7}{8}$–20 UN	**2A**	**0.0015**	**1.8735**	**1.8654**	**—**	**1.8410**	**1.8362**	**1.8140**	**2B**	**1.821**	**1.832**	**1.8425**	**1.8488**	**1.8750**
	3A	**0.0000**	**1.8750**	**1.8669**	**—**	**1.8425**	**1.8389**	**1.8155**	**3B**	**1.8210**	**1.8287**	**1.8425**	**1.8472**	**1.8750**
$1\frac{15}{16}$–6 UN	**2A**	**0.0026**	**1.9349**	**1.9167**	**—**	**1.8266**	**1.8181**	**1.7365**	**2B**	**1.757**	**1.788**	**1.8292**	**1.8403**	**1.9375**
	3A	**0.0000**	**1.9375**	**1.9193**	**—**	**1.8292**	**1.8228**	**1.7391**	**3B**	**1.7570**	**1.7771**	**1.8292**	**1.8375**	**1.9375**
$1\frac{15}{16}$–8 UN	**2A**	**0.0023**	**1.9352**	**1.9202**	**—**	**1.8540**	**1.8463**	**1.7864**	**2B**	**1.802**	**1.827**	**1.8563**	**1.8663**	**1.9375**
	3A	**0.0000**	**1.9375**	**1.9225**	**—**	**1.8563**	**1.8505**	**1.7887**	**3B**	**1.8020**	**1.8172**	**1.8563**	**1.8638**	**1.9375**
$1\frac{15}{16}$–12 UN	**2A**	**0.0018**	**1.9357**	**1.9243**	**—**	**1.8816**	**1.8755**	**1.8365**	**2B**	**1.847**	**1.865**	**1.8834**	**1.8913**	**1.9375**
	3A	**0.0000**	**1.9375**	**1.9261**	**—**	**1.8834**	**1.8789**	**1.8383**	**3B**	**1.8470**	**1.8573**	**1.8834**	**1.8893**	**1.9375**
$1\frac{15}{16}$–16 UN	**2A**	**0.0016**	**1.9359**	**1.9265**	**—**	**1.8953**	**1.8899**	**1.8614**	**2B**	**1.870**	**1.884**	**1.8969**	**1.9039**	**1.9375**
	3A	**0.0000**	**1.9375**	**1.9281**	**—**	**1.8969**	**1.8929**	**1.8630**	**3B**	**1.8700**	**1.8783**	**1.8969**	**1.9021**	**1.9375**
$1\frac{15}{16}$–20 UN	**2A**	**0.0015**	**1.9360**	**1.9279**	**—**	**1.9035**	**1.8986**	**1.8765**	**2B**	**1.883**	**1.895**	**1.9050**	**1.9114**	**1.9375**
	3A	**0.0000**	**1.9375**	**1.9294**	**—**	**1.9050**	**1.9013**	**1.8780**	**3B**	**1.8830**	**1.8912**	**1.9050**	**1.9098**	**1.9375**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
2–4½ UNC	**1A**	**0.0029**	**1.9971**	**1.9641**	—	**1.8528**	**1.8385**	**1.7324**	**1B**	**1.759**	**1.795**	**1.8557**	**1.8743**	**2.0000**
	2A	**0.0029**	**1.9971**	**1.9751**	**1.9641**	**1.8528**	**1.8433**	**1.7324**	**2B**	**1.759**	**1.795**	**1.8557**	**1.8681**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9780**	—	**1.8557**	**1.8486**	**1.7353**	**3B**	**1.7590**	**1.7861**	**1.8557**	**1.8650**	**2.0000**
2–6 UN	**2A**	**0.0026**	**1.9974**	**1.9792**	—	**1.8891**	**1.8805**	**1.7990**	**2B**	**1.820**	**1.850**	**1.8917**	**1.9028**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9818**	—	**1.8917**	**1.8853**	**1.8016**	**3B**	**1.8200**	**1.8396**	**1.8917**	**1.9000**	**2.0000**
2–8 UN	**2A**	**0.0023**	**1.9977**	**1.9827**	**1.9752**	**1.9165**	**1.9087**	**1.8489**	**2B**	**1.865**	**1.890**	**1.9188**	**1.9289**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9850**	—	**1.9188**	**1.9130**	**1.8512**	**3B**	**1.8650**	**1.8797**	**1.9188**	**1.9264**	**2.0000**
2–10 UNS	**2A**	**0.0020**	**1.9980**	**1.9851**	—	**1.9330**	**1.9265**	**1.8790**	**2B**	**1.892**	**1.913**	**1.9350**	**1.9435**	**2.0000**
2–12 UN	**2A**	**0.0018**	**1.9982**	**1.9868**	—	**1.9441**	**1.9380**	**1.8990**	**2B**	**1.910**	**1.928**	**1.9459**	**1.9538**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9886**	—	**1.9459**	**1.9414**	**1.9008**	**3B**	**1.9100**	**1.9198**	**1.9459**	**1.9518**	**2.0000**
2–14 UNS	**2A**	**0.0017**	**1.9983**	**1.9880**	—	**1.9519**	**1.9462**	**1.9133**	**2B**	**1.923**	**1.938**	**1.9536**	**1.9610**	**2.0000**
2–16 UN	**2A**	**0.0016**	**1.9984**	**1.9890**	—	**1.9578**	**1.9524**	**1.9239**	**2B**	**1.932**	**1.946**	**1.9594**	**1.9664**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9906**	—	**1.9594**	**1.9554**	**1.9255**	**3B**	**1.9320**	**1.9408**	**1.9594**	**1.9646**	**2.0000**
2–18 UNS	**2A**	**0.0015**	**1.9985**	**1.9898**	—	**1.9624**	**1.9573**	**1.9324**	**2B**	**1.940**	**1.953**	**1.9639**	**1.9706**	**2.0000**
2–20 UN	**2A**	**0.0015**	**1.9985**	**1.9904**	—	**1.9660**	**1.9611**	**1.9390**	**2B**	**1.946**	**1.957**	**1.9675**	**1.9739**	**2.0000**
	3A	**0.0000**	**2.0000**	**1.9919**	—	**1.9675**	**1.9638**	**1.9405**	**3B**	**1.9460**	**1.9537**	**1.9675**	**1.9723**	**2.0000**
2 1/16–16 UNS	**2A**	**0.0016**	**2.0609**	**2.0515**	—	**2.0203**	**2.0149**	**1.9864**	**2B**	**1.995**	**2.009**	**2.0219**	**2.0289**	**2.0625**
	3A	**0.0000**	**2.0625**	**2.0531**	—	**2.0219**	**2.0179**	**1.9880**	**3B**	**1.9950**	**2.0033**	**2.0219**	**2.0271**	**2.0625**
2⅛–6 UN	**2A**	**0.0026**	**2.1224**	**2.1042**	—	**2.0141**	**2.0054**	**1.9240**	**2B**	**1.945**	**1.975**	**2.0167**	**2.0280**	**2.1250**
	3A	**0.0000**	**2.1250**	**2.1068**	—	**2.0167**	**2.0102**	**1.9266**	**3B**	**1.9450**	**1.9646**	**2.0167**	**2.0251**	**2.1250**
2⅛–8 UN	**2A**	**0.0024**	**2.1226**	**2.1076**	**2.1001**	**2.0414**	**2.0335**	**1.9738**	**2B**	**1.990**	**2.015**	**2.0438**	**2.0540**	**2.1250**
	3A	**0.0000**	**2.1250**	**2.1100**	—	**2.0438**	**2.0379**	**1.9762**	**3B**	**1.9900**	**2.0047**	**2.0438**	**2.0515**	**2.1250**
2⅛–12 UN	**2A**	**0.0018**	**2.1232**	**2.1118**	—	**2.0691**	**2.0630**	**2.0240**	**2B**	**2.035**	**2.053**	**2.0709**	**2.0788**	**2.1250**
	3A	**0.0000**	**2.1250**	**2.1136**	—	**2.0709**	**2.0664**	**2.0258**	**3B**	**2.0350**	**2.0448**	**2.0709**	**2.0768**	**2.1250**
2⅛–16 UN	**2A**	**0.0016**	**2.1234**	**2.1140**	—	**2.0828**	**2.0774**	**2.0489**	**2B**	**2.057**	**2.071**	**2.0844**	**2.0914**	**2.1250**
	3A	**0.0000**	**2.1250**	**2.1156**	—	**2.0844**	**2.0803**	**2.0505**	**3B**	**2.0570**	**2.0658**	**2.0844**	**2.0896**	**2.1250**
2⅛–20 UN	**2A**	**0.0015**	**2.1235**	**2.1154**	—	**2.0910**	**2.0861**	**2.0640**	**2B**	**2.071**	**2.082**	**2.0925**	**2.0989**	**2.1250**
	3A	**0.0000**	**2.1250**	**2.1169**	—	**2.0925**	**2.0888**	**2.0655**	**3B**	**2.0710**	**2.0787**	**2.0925**	**2.0973**	**2.1250**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$2\frac{3}{16}$–16 UNS	**2A**	**0.0016**	**2.1859**	**2.1765**	—	**2.1453**	**2.1399**	**2.1114**	**2B**	**2.120**	**2.134**	**2.1469**	**2.1539**	**2.1875**
	3A	**0.0000**	**2.1875**	**2.1781**	—	**2.1469**	**2.1428**	**2.1130**	**3B**	**2.1200**	**2.1283**	**2.1469**	**2.1521**	**2.1875**
$2\frac{1}{4}$–$4\frac{1}{2}$ UNC	**1A**	**0.0029**	**2.2471**	**2.2141**	—	**2.1028**	**2.0882**	**1.9824**	**1B**	**2.009**	**2.045**	**2.1057**	**2.1247**	**2.2500**
	2A	**0.0029**	**2.2471**	**2.2251**	**2.2141**	**2.1028**	**2.0931**	**1.9824**	**2B**	**2.009**	**2.045**	**2.1057**	**2.1183**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2280**	—	**2.1057**	**2.0984**	**1.9853**	**3B**	**2.0090**	**2.0361**	**2.1057**	**2.1152**	**2.2500**
$2\frac{1}{4}$–6 UN	**2A**	**0.0026**	**2.2474**	**2.2292**	—	**2.1391**	**2.1303**	**2.0490**	**2B**	**2.070**	**2.100**	**2.1417**	**2.1531**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2318**	—	**2.1417**	**2.1351**	**2.0516**	**3B**	**2.0700**	**2.0896**	**2.1417**	**2.1502**	**2.2500**
$2\frac{1}{4}$–8 UN	**2A**	**0.0024**	**2.2476**	**2.2326**	**2.2251**	**2.1664**	**2.1584**	**2.0988**	**2B**	**2.115**	**2.140**	**2.1688**	**2.1792**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2350**	—	**2.1688**	**2.1628**	**2.1012**	**3B**	**2.1150**	**2.1297**	**2.1688**	**2.1766**	**2.2500**
$2\frac{1}{4}$–10 UNS	**2A**	**0.0020**	**2.2480**	**2.2351**	—	**2.1830**	**2.1765**	**2.1290**	**2B**	**2.142**	**2.163**	**2.1850**	**2.1935**	**2.2500**
$2\frac{1}{4}$–12 UN	**2A**	**0.0018**	**2.2482**	**2.2368**	—	**2.1941**	**2.1880**	**2.1490**	**2B**	**2.160**	**2.178**	**2.1959**	**2.2038**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2386**	—	**2.1959**	**2.1914**	**2.1508**	**3B**	**2.1600**	**2.1698**	**2.1959**	**2.2018**	**2.2500**
$2\frac{1}{4}$–14 UNS	**2A**	**0.0017**	**2.2483**	**2.2380**	—	**2.2019**	**2.1962**	**2.1633**	**2B**	**2.173**	**2.188**	**2.2036**	**2.2110**	**2.2500**
$2\frac{1}{4}$–16 UN	**2A**	**0.0016**	**2.2484**	**2.2390**	—	**2.2078**	**2.2024**	**2.1739**	**2B**	**2.182**	**2.196**	**2.2094**	**2.2164**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2406**	—	**2.2094**	**2.2053**	**2.1755**	**3B**	**2.1820**	**2.1908**	**2.2094**	**2.2146**	**2.2500**
$2\frac{1}{4}$–18 UNS	**2A**	**0.0015**	**2.2485**	**2.2398**	—	**2.2124**	**2.2073**	**2.1824**	**2B**	**2.190**	**2.203**	**2.2139**	**2.2206**	**2.2500**
$2\frac{1}{4}$–20 UN	**2A**	**0.0015**	**2.2485**	**2.2404**	—	**2.2160**	**2.2111**	**2.1890**	**2B**	**2.196**	**2.207**	**2.2175**	**2.2239**	**2.2500**
	3A	**0.0000**	**2.2500**	**2.2419**	—	**2.2175**	**2.2137**	**2.1905**	**3B**	**2.1960**	**2.2037**	**2.2175**	**2.2223**	**2.2500**
$2\frac{5}{16}$–16 UNS	**2A**	**0.0017**	**2.3108**	**2.3014**	—	**2.2702**	**2.2647**	**2.2363**	**2B**	**2.245**	**2.259**	**2.2719**	**2.2791**	**2.3125**
	3A	**0.0000**	**2.3125**	**2.3031**	—	**2.2719**	**2.2678**	**2.2380**	**3B**	**2.2450**	**2.2533**	**2.2719**	**2.2773**	**2.3125**
$2\frac{3}{8}$–6 UN	**2A**	**0.0027**	**2.3723**	**2.3541**	—	**2.2640**	**2.2551**	**2.1739**	**2B**	**2.195**	**2.226**	**2.2667**	**2.2782**	**2.3750**
	3A	**0.0000**	**2.3750**	**2.3568**	—	**2.2667**	**2.2601**	**2.1766**	**3B**	**2.1950**	**2.2146**	**2.2667**	**2.2753**	**2.3750**
$2\frac{3}{8}$–8 UN	**2A**	**0.0024**	**2.3726**	**2.3576**	—	**2.2914**	**2.2833**	**2.2238**	**2B**	**2.240**	**2.265**	**2.2938**	**2.3043**	**2.3750**
	3A	**0.0000**	**2.3750**	**2.3600**	—	**2.2938**	**2.2878**	**2.2262**	**3B**	**2.2400**	**2.2547**	**2.2938**	**2.3017**	**2.3750**
$2\frac{3}{8}$–12 UN	**2A**	**0.0019**	**2.3731**	**2.3617**	—	**2.3190**	**2.3128**	**2.2739**	**2B**	**2.285**	**2.303**	**2.3209**	**2.3290**	**2.3750**
	3A	**0.0000**	**2.3750**	**2.3636**	—	**2.3209**	**2.3163**	**2.2758**	**3B**	**2.2850**	**2.2948**	**2.3209**	**2.3269**	**2.3750**
$2\frac{3}{8}$–16 UN	**2A**	**0.0017**	**2.3733**	**2.3639**	—	**2.3327**	**2.3272**	**2.2988**	**2B**	**2.307**	**2.321**	**2.3344**	**2.3416**	**2.3750**
	3A	**0.0000**	**2.3750**	**2.3656**	—	**2.3344**	**2.3303**	**2.3005**	**3B**	**2.3070**	**2.3158**	**2.3344**	**2.3398**	**2.3750**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
2⅜–20 UN	**2A**	**0.0015**	**2.3735**	**2.3654**	—	**2.3410**	**2.3359**	**2.3140**	**2B**	**2.321**	**2.332**	**2.3425**	**2.3491**	**2.3750**
	3A	**0.0000**	**2.3750**	**2.3669**	—	**2.3425**	**2.3387**	**2.3155**	**3B**	**2.3210**	**2.3287**	**2.3425**	**2.3475**	**2.3750**
2 7/16–16 UNS	**2A**	**0.0017**	**2.4358**	**2.4264**	—	**2.3952**	**2.3897**	**2.3613**	**2B**	**2.370**	**2.384**	**2.3969**	**2.4041**	**2.4375**
	3A	**0.0000**	**2.4375**	**2.4281**	—	**2.3969**	**2.3928**	**2.3630**	**3B**	**2.3700**	**2.3783**	**2.3969**	**2.4023**	**2.4375**
2½–4 UNC	**1A**	**0.0031**	**2.4969**	**2.4612**	—	**2.3345**	**2.3190**	**2.1992**	**1B**	**2.229**	**2.267**	**2.3376**	**2.3578**	**2.5000**
	2A	**0.0031**	**2.4969**	**2.4731**	**2.4612**	**2.3345**	**2.3241**	**2.1992**	**2B**	**2.229**	**2.267**	**2.3376**	**2.3511**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4762**	—	**2.3376**	**2.3298**	**2.2023**	**3B**	**2.2290**	**2.2594**	**2.3376**	**2.3477**	**2.5000**
2½–6 UN	**2A**	**0.0027**	**2.4973**	**2.4791**	—	**2.3890**	**2.3800**	**2.2989**	**2B**	**2.320**	**2.350**	**2.3917**	**2.4033**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4818**	—	**2.3917**	**2.3850**	**2.3016**	**3B**	**2.3200**	**2.3396**	**2.3917**	**2.4004**	**2.5000**
2½–8 UN	**2A**	**0.0024**	**2.4976**	**2.4826**	**2.4751**	**2.4164**	**2.4082**	**2.3488**	**2B**	**2.365**	**2.390**	**2.4188**	**2.4294**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4850**	—	**2.4188**	**2.4127**	**2.3512**	**3B**	**2.3650**	**2.3797**	**2.4188**	**2.4268**	**2.5000**
2½–10 UNS	**2A**	**0.0020**	**2.4980**	**2.4851**	—	**2.4330**	**2.4263**	**2.3790**	**2B**	**2.392**	**2.413**	**2.4350**	**2.4437**	**2.5000**
2½–12 UN	**2A**	**0.0019**	**2.4981**	**2.4867**	—	**2.4440**	**2.4378**	**2.3989**	**2B**	**2.410**	**2.428**	**2.4459**	**2.4540**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4886**	—	**2.4459**	**2.4413**	**2.4008**	**3B**	**2.4100**	**2.4198**	**2.4459**	**2.4519**	**2.5000**
2½–14 UNS	**2A**	**0.0017**	**2.4983**	**2.4880**	—	**2.4519**	**2.4461**	**2.4133**	**2B**	**2.423**	**2.438**	**2.4536**	**2.4612**	**2.5000**
2½–16 UN	**2A**	**0.0017**	**2.4983**	**2.4889**	—	**2.4577**	**2.4522**	**2.4238**	**2B**	**2.432**	**2.446**	**2.4594**	**2.4666**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4906**	—	**2.4594**	**2.4553**	**2.4255**	**3B**	**2.4320**	**2.4408**	**2.4594**	**2.4648**	**2.5000**
2½–18 UNS	**2A**	**0.0016**	**2.4984**	**2.4897**	—	**2.4623**	**2.4570**	**2.4323**	**2B**	**2.440**	**2.453**	**2.4639**	**2.4708**	**2.5000**
2½–20 UN	**2A**	**0.0015**	**2.4985**	**2.4904**	—	**2.4660**	**2.4609**	**2.4390**	**2B**	**2.446**	**2.457**	**2.4675**	**2.4741**	**2.5000**
	3A	**0.0000**	**2.5000**	**2.4919**	—	**2.4675**	**2.4637**	**2.4405**	**3B**	**2.4460**	**2.4537**	**2.4675**	**2.4725**	**2.5000**
2⅝–6 UN	**2A**	**0.0027**	**2.6223**	**2.6041**	—	**2.5140**	**2.5050**	**2.4239**	**2B**	**2.445**	**2.475**	**2.5167**	**2.5285**	**2.6250**
	3A	**0.0000**	**2.6250**	**2.6068**	—	**2.5167**	**2.5099**	**2.4266**	**3B**	**2.4450**	**2.4646**	**2.5167**	**2.5255**	**2.6250**
2⅝–8 UN	**2A**	**0.0025**	**2.6225**	**2.6075**	—	**2.5413**	**2.5331**	**2.4737**	**2B**	**2.490**	**2.515**	**2.5438**	**2.5545**	**2.6250**
	3A	**0.0000**	**2.6250**	**2.6100**	—	**2.5438**	**2.5376**	**2.4762**	**3B**	**2.4900**	**2.5047**	**2.5438**	**2.5518**	**2.6250**
2⅝–12 UN	**2A**	**0.0019**	**2.6231**	**2.6117**	—	**2.5690**	**2.5628**	**2.5239**	**2B**	**2.535**	**2.553**	**2.5709**	**2.5790**	**2.6250**
	3A	**0.0000**	**2.6250**	**2.6136**	—	**2.5709**	**2.5663**	**2.5258**	**3B**	**2.5350**	**2.5448**	**2.5709**	**2.5769**	**2.6250**
2⅝–16 UN	**2A**	**0.0017**	**2.6233**	**2.6139**	—	**2.5827**	**2.5772**	**2.5488**	**2B**	**2.557**	**2.571**	**2.5844**	**2.5916**	**2.6250**
	3A	**0.0000**	**2.6250**	**2.6156**	—	**2.5844**	**2.5803**	**2.5505**	**3B**	**2.5570**	**2.5658**	**2.5844**	**2.5898**	**2.6250**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$2\frac{5}{8}$–20 UN	**2A**	**0.0015**	**2.6235**	**2.6154**	—	**2.5910**	**2.5859**	**2.5640**	**2B**	**2.571**	**2.582**	**2.5925**	**2.5991**	**2.6250**
	3A	**0.0000**	**2.6250**	**2.6169**	—	**2.5925**	**2.5887**	**2.5655**	**3B**	**2.5710**	**2.5787**	**2.5925**	**2.5975**	**2.6250**
$2\frac{3}{4}$–4 UNC	**1A**	**0.0032**	**2.7468**	**2.7111**	—	**2.5844**	**2.5686**	**2.4491**	**1B**	**2.479**	**2.517**	**2.5876**	**2.6082**	**2.7500**
	2A	**0.0032**	**2.7468**	**2.7230**	**2.7111**	**2.5844**	**2.5739**	**2.4491**	**2B**	**2.479**	**2.517**	**2.5876**	**2.6013**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7262**	—	**2.5876**	**2.5797**	**2.4523**	**3B**	**2.4790**	**2.5094**	**2.5876**	**2.5979**	**2.7500**
$2\frac{3}{4}$–6 UN	**2A**	**0.0027**	**2.7473**	**2.7291**	—	**2.6390**	**2.6299**	**2.5489**	**2B**	**2.570**	**2.600**	**2.6417**	**2.6536**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7318**	—	**2.6417**	**2.6349**	**2.5516**	**3B**	**2.5700**	**2.5896**	**2.6417**	**2.6506**	**2.7500**
$2\frac{3}{4}$–8 UN	**2A**	**0.0025**	**2.7475**	**2.7325**	**2.7250**	**2.6663**	**2.6580**	**2.5987**	**2B**	**2.615**	**2.640**	**2.6688**	**2.6796**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7350**	—	**2.6688**	**2.6625**	**2.6012**	**3B**	**2.6150**	**2.6297**	**2.6688**	**2.6769**	**2.7500**
$2\frac{3}{4}$–10 UNS	**2A**	**0.0020**	**2.7480**	**2.7351**	—	**2.6830**	**2.6763**	**2.6290**	**2B**	**2.642**	**2.663**	**2.6850**	**2.6937**	**2.7500**
$2\frac{3}{4}$–12 UN	**2A**	**0.0019**	**2.7481**	**2.7367**	—	**2.6940**	**2.6878**	**2.6489**	**2B**	**2.660**	**2.678**	**2.6959**	**2.7040**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7386**	—	**2.6959**	**2.6913**	**2.6508**	**3B**	**2.6600**	**2.6698**	**2.6959**	**2.7019**	**2.7500**
$2\frac{3}{4}$–14 UNS	**2A**	**0.0017**	**2.7483**	**2.7380**	—	**2.7019**	**2.6961**	**2.6633**	**2B**	**2.673**	**2.688**	**2.7036**	**2.7112**	**2.7500**
$2\frac{3}{4}$–16 UN	**2A**	**0.0017**	**2.7483**	**2.7389**	—	**2.7077**	**2.7022**	**2.6738**	**2B**	**2.682**	**2.696**	**2.7094**	**2.7166**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7406**	—	**2.7094**	**2.7053**	**2.6755**	**3B**	**2.6820**	**2.6908**	**2.7094**	**2.7148**	**2.7500**
$2\frac{3}{4}$–18 UNS	**2A**	**0.0016**	**2.7484**	**2.7397**	—	**2.7123**	**2.7070**	**2.6823**	**2B**	**2.690**	**2.703**	**2.7139**	**2.7208**	**2.7500**
$2\frac{3}{4}$–20 UN	**2A**	**0.0015**	**2.7485**	**2.7404**	—	**2.7160**	**2.7109**	**2.6890**	**2B**	**2.696**	**2.707**	**2.7175**	**2.7241**	**2.7500**
	3A	**0.0000**	**2.7500**	**2.7419**	—	**2.7175**	**2.7137**	**2.6905**	**3B**	**2.6960**	**2.7037**	**2.7175**	**2.7225**	**2.7500**
$2\frac{7}{8}$–6 UN	**2A**	**0.0028**	**2.8722**	**2.8540**	—	**2.7639**	**2.7547**	**2.6738**	**2B**	**2.695**	**2.725**	**2.7667**	**2.7787**	**2.8750**
	3A	**0.0000**	**2.8750**	**2.8568**	—	**2.7667**	**2.7598**	**2.6766**	**3B**	**2.6950**	**2.7146**	**2.7667**	**2.7757**	**2.8750**
$2\frac{7}{8}$–8 UN	**2A**	**0.0025**	**2.8725**	**2.8575**	—	**2.7913**	**2.7829**	**2.7237**	**2B**	**2.740**	**2.765**	**2.7938**	**2.8048**	**2.8750**
	3A	**0.0000**	**2.8750**	**2.8600**	—	**2.7938**	**2.7875**	**2.7262**	**3B**	**2.7400**	**2.7547**	**2.7938**	**2.8020**	**2.8750**
$2\frac{7}{8}$–12 UN	**2A**	**0.0019**	**2.8731**	**2.8617**	—	**2.8190**	**2.8127**	**2.7739**	**2B**	**2.785**	**2.803**	**2.8209**	**2.8291**	**2.8750**
	3A	**0.0000**	**2.8750**	**2.8636**	—	**2.8209**	**2.8162**	**2.7758**	**3B**	**2.7850**	**2.7948**	**2.8209**	**2.8271**	**2.8750**
$2\frac{7}{8}$–16 UN	**2A**	**0.0017**	**2.8733**	**2.8639**	—	**2.8327**	**2.8271**	**2.7988**	**2B**	**2.807**	**2.821**	**2.8344**	**2.8417**	**2.8750**
	3A	**0.0000**	**2.8750**	**2.8656**	—	**2.8344**	**2.8302**	**2.8005**	**3B**	**2.8070**	**2.8158**	**2.8344**	**2.8399**	**2.8750**
$2\frac{7}{8}$–20 UN	**2A**	**0.0016**	**2.8734**	**2.8653**	—	**2.8409**	**2.8357**	**2.8139**	**2B**	**2.821**	**2.832**	**2.8425**	**2.8493**	**2.8750**
	3A	**0.0000**	**2.8750**	**2.8669**	—	**2.8425**	**2.8386**	**2.8155**	**3B**	**2.8210**	**2.8287**	**2.8425**	**2.8476**	**2.8750**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
3–4 UNC	**1A**	**0.0032**	**2.9968**	**2.9611**	**—**	**2.8344**	**2.8183**	**2.6991**	**1B**	**2.729**	**2.767**	**2.8376**	**2.8585**	**3.0000**
	2A	**0.0032**	**2.9968**	**2.9730**	**2.9611**	**2.8344**	**2.8237**	**2.6991**	**2B**	**2.729**	**2.767**	**2.8376**	**2.8515**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9762**	**—**	**2.8376**	**2.8296**	**2.7023**	**3B**	**2.7290**	**2.7594**	**2.8376**	**2.8480**	**3.0000**
3–6 UN	**2A**	**0.0028**	**2.9972**	**2.9790**	**—**	**2.8889**	**2.8796**	**2.7988**	**2B**	**2.820**	**2.850**	**2.8917**	**2.9038**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9818**	**—**	**2.8917**	**2.8847**	**2.8016**	**3B**	**2.8200**	**2.8396**	**2.8917**	**2.9008**	**3.0000**
3–8 UN	**2A**	**0.0026**	**2.9974**	**2.9824**	**2.9749**	**2.9162**	**2.9077**	**2.8486**	**2B**	**2.865**	**2.890**	**2.9188**	**2.9299**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9850**	**—**	**2.9188**	**2.9124**	**2.8512**	**3B**	**2.8650**	**2.8797**	**2.9188**	**2.9271**	**3.0000**
3–10 UNS	**2A**	**0.0020**	**2.9980**	**2.9851**	**—**	**2.9330**	**2.9262**	**2.8790**	**2B**	**2.892**	**2.913**	**2.9350**	**2.9439**	**3.0000**
3–12 UN	**2A**	**0.0019**	**2.9981**	**2.9867**	**—**	**2.9440**	**2.9377**	**2.8989**	**2B**	**2.910**	**2.928**	**2.9459**	**2.9541**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9886**	**—**	**2.9459**	**2.9412**	**2.9008**	**3B**	**2.9100**	**2.9198**	**2.9459**	**2.9521**	**3.0000**
3–14 UNS	**2A**	**0.0018**	**2.9982**	**2.9879**	**—**	**2.9518**	**2.9459**	**2.9132**	**2B**	**2.923**	**2.938**	**2.9536**	**2.9613**	**3.0000**
3–16 UN	**2A**	**0.0017**	**2.9983**	**2.9889**	**—**	**2.9577**	**2.9521**	**2.9238**	**2B**	**2.932**	**2.946**	**2.9594**	**2.9667**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9906**	**—**	**2.9594**	**2.9552**	**2.9255**	**3B**	**2.9320**	**2.9408**	**2.9594**	**2.9649**	**3.0000**
3–18 UNS	**2A**	**0.0016**	**2.9984**	**2.9897**	**—**	**2.9623**	**2.9569**	**2.9323**	**2B**	**2.940**	**2.953**	**2.9639**	**2.9709**	**3.0000**
3–20 UN	**2A**	**0.0016**	**2.9984**	**2.9903**	**—**	**2.9659**	**2.9607**	**2.9389**	**2B**	**2.946**	**2.957**	**2.9675**	**2.9743**	**3.0000**
	3A	**0.0000**	**3.0000**	**2.9919**	**—**	**2.9675**	**2.9636**	**2.9405**	**3B**	**2.9460**	**2.9537**	**2.9675**	**2.9726**	**3.0000**
3⅛–6 UN	**2A**	**0.0028**	**3.1222**	**3.1040**	**—**	**3.0139**	**3.0045**	**2.9238**	**2B**	**2.945**	**2.975**	**3.0167**	**3.0289**	**3.1250**
	3A	**0.0000**	**3.1250**	**3.1068**	**—**	**3.0167**	**3.0097**	**2.9266**	**3B**	**2.9450**	**2.9646**	**3.0167**	**3.0259**	**3.1250**
3⅛–8 UN	**2A**	**0.0026**	**3.1224**	**3.1074**	**—**	**3.0412**	**3.0326**	**2.9736**	**2B**	**2.990**	**3.015**	**3.0438**	**3.0550**	**3.1250**
	3A	**0.0000**	**3.1250**	**3.1100**	**—**	**3.0438**	**3.0374**	**2.9762**	**3B**	**2.9900**	**3.0047**	**3.0438**	**3.0522**	**3.1250**
3⅛–12 UN	**2A**	**0.0019**	**3.1231**	**3.1117**	**—**	**3.0690**	**3.0627**	**3.0239**	**2B**	**3.035**	**3.053**	**3.0709**	**3.0791**	**3.1250**
	3A	**0.0000**	**3.1250**	**3.1136**	**—**	**3.0709**	**3.0662**	**3.0258**	**3B**	**3.0350**	**3.0448**	**3.0709**	**3.0771**	**3.1250**
3⅛–16 UN	**2A**	**0.0017**	**3.1233**	**3.1139**	**—**	**3.0827**	**3.0771**	**3.0488**	**2B**	**3.057**	**3.071**	**3.0844**	**3.0917**	**3.1250**
	3A	**0.0000**	**3.1250**	**3.1156**	**—**	**3.0844**	**3.0802**	**3.0505**	**3B**	**3.0570**	**3.0658**	**3.0844**	**3.0899**	**3.1250**
3¼–4 UNC	**1A**	**0.0033**	**3.2467**	**3.2110**	**—**	**3.0843**	**3.0680**	**2.9490**	**1B**	**2.979**	**3.017**	**3.0876**	**3.1088**	**3.2500**
	2A	**0.0033**	**3.2467**	**3.2229**	**3.2110**	**3.0843**	**3.0734**	**2.9490**	**2B**	**2.979**	**3.017**	**3.0876**	**3.1017**	**3.2500**
	3A	**0.0000**	**3.2500**	**3.2262**	**—**	**3.0876**	**3.0794**	**2.9523**	**3B**	**2.9790**	**3.0094**	**3.0876**	**3.0982**	**3.2500**
3¼–6 UN	**2A**	**0.0028**	**3.2472**	**3.2290**	**—**	**3.1389**	**3.1294**	**3.0488**	**2B**	**3.070**	**3.100**	**3.1417**	**3.1540**	**3.2500**
	3A	**0.0000**	**3.2500**	**3.2318**	**—**	**3.1417**	**3.1346**	**3.0516**	**3B**	**3.0700**	**3.0896**	**3.1417**	**3.1509**	**3.2500**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$3\frac{1}{4}$–8 UN	**2A**	**0.0026**	**3.2474**	**3.2324**	**3.2249**	**3.1662**	**3.1575**	**3.0986**	**2B**	**3.115**	**3.140**	**3.1688**	**3.1801**	**3.2500**
	3A	**0.0000**	**3.2500**	**3.2350**	—	**3.1688**	**3.1623**	**3.1012**	**3B**	**3.1150**	**3.1297**	**3.1688**	**3.1773**	**3.2500**
$3\frac{1}{4}$–10 UNS	**2A**	**0.0020**	**3.2480**	**3.2351**	—	**3.1830**	**3.1762**	**3.1290**	**2B**	**3.142**	**3.163**	**3.1850**	**3.1939**	**3.2500**
$3\frac{1}{4}$–12 UN	**2A**	**0.0019**	**3.2481**	**3.2367**	—	**3.1940**	**3.1877**	**3.1489**	**2B**	**3.160**	**3.178**	**3.1959**	**3.2041**	**3.2500**
	3A	**0.0000**	**3.2500**	**3.2386**	—	**3.1959**	**3.1912**	**3.1508**	**3B**	**3.1600**	**3.1698**	**3.1959**	**3.2041**	**3.2500**
$3\frac{1}{4}$–14 UNS	**2A**	**0.0018**	**3.2482**	**3.2379**	—	**3.2018**	**3.1959**	**3.1632**	**2B**	**3.173**	**3.188**	**3.2036**	**3.2113**	**3.2500**
$3\frac{1}{4}$–16 UN	**2A**	**0.0017**	**3.2483**	**3.2389**	—	**3.2077**	**3.2021**	**3.1738**	**2B**	**3.182**	**3.196**	**3.2094**	**3.2167**	**3.2500**
	3A	**0.0000**	**3.2500**	**3.2406**	—	**3.2094**	**3.2052**	**3.1755**	**3B**	**3.1820**	**3.1908**	**3.2094**	**3.2149**	**3.2500**
$3\frac{1}{4}$–18 UNS	**2A**	**0.0016**	**3.2484**	**3.2397**	—	**3.2123**	**3.2069**	**3.1823**	**2B**	**3.190**	**3.203**	**3.2139**	**3.2209**	**3.2500**
$3\frac{3}{8}$–6 UN	**2A**	**0.0029**	**3.3721**	**3.3539**	—	**3.2638**	**3.2543**	**3.1737**	**2B**	**3.195**	**3.225**	**3.2667**	**3.2791**	**3.3750**
	3A	**0.0000**	**3.3750**	**3.3568**	—	**3.2667**	**3.2595**	**3.1766**	**3B**	**3.1950**	**3.2146**	**3.2667**	**3.2760**	**3.3750**
$3\frac{3}{8}$–8 UN	**2A**	**0.0026**	**3.3724**	**3.3574**	—	**3.2912**	**3.2824**	**3.2236**	**2B**	**3.240**	**3.265**	**3.2938**	**3.3052**	**3.3750**
	3A	**0.0000**	**3.3750**	**3.3600**	—	**3.2938**	**3.2872**	**3.2262**	**3B**	**3.2400**	**3.2547**	**3.2938**	**3.3023**	**3.3750**
$3\frac{3}{8}$–12 UN	**2A**	**0.0019**	**3.3731**	**3.3617**	—	**3.3190**	**3.3126**	**3.2739**	**2B**	**3.285**	**3.303**	**3.3209**	**3.3293**	**3.3750**
	3A	**0.0000**	**3.3750**	**3.3636**	—	**3.3209**	**3.3161**	**3.2758**	**3B**	**3.2850**	**3.2948**	**3.3209**	**3.3272**	**3.3750**
$3\frac{3}{8}$–16 UN	**2A**	**0.0017**	**3.3733**	**3.3639**	—	**3.3327**	**3.3269**	**3.2988**	**2B**	**3.307**	**3.321**	**3.3344**	**3.3419**	**3.3750**
	3A	**0.0000**	**3.3750**	**3.3656**	—	**3.3344**	**3.3301**	**3.3005**	**3B**	**3.3070**	**3.3158**	**3.3344**	**3.3400**	**3.3750**
$3\frac{1}{2}$–4 UNC	**1A**	**0.0033**	**3.4967**	**3.4610**	—	**3.3343**	**3.3177**	**3.1990**	**1B**	**3.229**	**3.267**	**3.3376**	**3.3591**	**3.5000**
	2A	**0.0033**	**3.4967**	**3.4729**	**3.4610**	**3.3343**	**3.3233**	**3.1990**	**2B**	**3.229**	**3.267**	**3.3376**	**3.3519**	**3.5000**
	3A	**0.0000**	**3.5000**	**3.4762**	—	**3.3376**	**3.3293**	**3.2023**	**3B**	**3.2290**	**3.2594**	**3.3376**	**3.3484**	**3.5000**
$3\frac{1}{2}$–6 UN	**2A**	**0.0029**	**3.4971**	**3.4789**	—	**3.3888**	**3.3792**	**3.2987**	**2B**	**3.320**	**3.350**	**3.3917**	**3.4042**	**3.5000**
	3A	**0.0000**	**3.5000**	**3.4818**	—	**3.3917**	**3.3845**	**3.3016**	**3B**	**3.3200**	**3.3396**	**3.3917**	**3.4011**	**3.5000**
$3\frac{1}{2}$–8 UN	**2A**	**0.0026**	**3.4974**	**3.4824**	**3.4749**	**3.4162**	**3.4074**	**3.3486**	**2B**	**3.365**	**3.390**	**3.4188**	**3.4303**	**3.5000**
	3A	**0.0000**	**3.5000**	**3.4850**	—	**3.4188**	**3.4122**	**3.3512**	**3B**	**3.3650**	**3.3797**	**3.4188**	**3.4274**	**3.5000**
$3\frac{1}{2}$–10 UNS	**2A**	**0.0021**	**3.4979**	**3.4850**	—	**3.4329**	**3.4260**	**3.3789**	**2B**	**3.392**	**3.413**	**3.4350**	**3.4440**	**3.5000**
$3\frac{1}{2}$–12 UN	**2A**	**0.0019**	**3.4981**	**3.4867**	—	**3.4440**	**3.4376**	**3.3989**	**2B**	**3.410**	**3.428**	**3.4459**	**3.4543**	**3.5000**
	3A	**0.0000**	**3.5000**	**3.4886**	—	**3.4459**	**3.4411**	**3.4008**	**3B**	**3.4100**	**3.4198**	**3.4459**	**3.4522**	**3.5000**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$3\frac{1}{2}$–14 UNS	**2A**	**0.0018**	**3.4982**	**3.4879**	—	**3.4518**	**3.4457**	**3.4132**	**2B**	**3.423**	**3.438**	**3.4536**	**3.4615**	**3.5000**
$3\frac{1}{2}$–16 UN	**2A**	**0.0017**	**3.4983**	**3.4889**	—	**3.4577**	**3.4519**	**3.4238**	**2B**	**3.432**	**3.446**	**3.4594**	**3.4669**	**3.5000**
	3A	**0.0000**	**3.5000**	**3.4906**	—	**3.4594**	**3.4551**	**3.4255**	**3B**	**3.4320**	**3.4408**	**3.4594**	**3.4650**	**3.5000**
$3\frac{1}{2}$–18 UNS	**2A**	**0.0017**	**3.4983**	**3.4896**	—	**3.4622**	**3.4567**	**3.4322**	**2B**	**3.440**	**3.453**	**3.4639**	**3.4711**	**3.5000**
$3\frac{5}{8}$–6 UN	**2A**	**0.0029**	**3.6221**	**3.6039**	—	**3.5138**	**3.5041**	**3.4237**	**2B**	**3.445**	**3.475**	**3.5167**	**3.5293**	**3.6250**
	3A	**0.0000**	**3.6250**	**3.6068**	—	**3.5167**	**3.5094**	**3.4266**	**3B**	**3.4450**	**3.4646**	**3.5167**	**3.5262**	**3.6250**
$3\frac{5}{8}$–8 UN	**2A**	**0.0027**	**3.6223**	**3.6073**	—	**3.5411**	**3.5322**	**3.4735**	**2B**	**3.490**	**3.515**	**3.5438**	**3.5554**	**3.6250**
	3A	**0.0000**	**3.6250**	**3.6100**	—	**3.5438**	**3.5371**	**3.4762**	**3B**	**3.4900**	**3.5047**	**3.5438**	**3.5525**	**3.6250**
$3\frac{5}{8}$–12 UN	**2A**	**0.0019**	**3.6231**	**3.6117**	—	**3.5690**	**3.5626**	**3.5239**	**2B**	**3.535**	**3.553**	**3.5709**	**3.5793**	**3.6250**
	3A	**0.0000**	**3.6250**	**3.6136**	—	**3.5709**	**3.5661**	**3.5258**	**3B**	**3.5350**	**3.5448**	**3.5709**	**3.5772**	**3.6250**
$3\frac{5}{8}$–16 UN	**2A**	**0.0017**	**3.6233**	**3.6139**	—	**3.5827**	**3.5769**	**3.5488**	**2B**	**3.557**	**3.571**	**3.5844**	**3.5919**	**3.6250**
	3A	**0.0000**	**3.6250**	**3.6156**	—	**3.5844**	**3.5801**	**3.5505**	**3B**	**3.5570**	**3.5658**	**3.5844**	**3.5900**	**3.6250**
$3\frac{3}{4}$–4 UNC	**1A**	**0.0034**	**3.7466**	**3.7109**	—	**3.5842**	**3.5674**	**3.4489**	**1B**	**3.479**	**3.517**	**3.5876**	**3.6094**	**3.7500**
	2A	**0.0034**	**3.7466**	**3.7228**	**3.7109**	**3.5842**	**3.5730**	**3.4489**	**2B**	**3.479**	**3.517**	**3.5876**	**3.6021**	**3.7500**
	3A	**0.0000**	**3.7500**	**3.7262**	—	**3.5876**	**3.5792**	**3.4523**	**3B**	**3.4790**	**3.5094**	**3.5876**	**3.5985**	**3.7500**
$3\frac{3}{4}$–6 UN	**2A**	**0.0029**	**3.7471**	**3.7289**	—	**3.6388**	**3.6290**	**3.5487**	**2B**	**3.570**	**3.600**	**3.6417**	**3.6544**	**3.7500**
	3A	**0.0000**	**3.7500**	**3.7318**	—	**3.6417**	**3.6344**	**3.5516**	**3B**	**3.5700**	**3.5896**	**3.6417**	**3.6512**	**3.7500**
$3\frac{3}{4}$–8 UN	**2A**	**0.0027**	**3.7473**	**3.7323**	**3.7248**	**3.6661**	**3.6571**	**3.5985**	**2B**	**3.615**	**3.640**	**3.6688**	**3.6805**	**3.7500**
	3A	**0.0000**	**3.7500**	**3.7350**	—	**3.6688**	**3.6621**	**3.6012**	**3B**	**3.6150**	**3.6297**	**3.6688**	**3.6776**	**3.7500**
$3\frac{3}{4}$–10 UNS	**2A**	**0.0021**	**3.7479**	**3.7350**	—	**3.6829**	**3.6760**	**3.6289**	**2B**	**3.642**	**3.663**	**3.6850**	**3.6940**	**3.7500**
$3\frac{3}{4}$–12 UN	**2A**	**0.0019**	**3.7481**	**3.7367**	—	**3.6940**	**3.6876**	**3.6489**	**2B**	**3.660**	**3.678**	**3.6959**	**3.7043**	**3.7500**
	3A	**0.0000**	**3.7500**	**3.7386**	—	**3.6959**	**3.6911**	**3.6508**	**3B**	**3.6600**	**3.6698**	**3.6959**	**3.7022**	**3.7500**
$3\frac{3}{4}$–14 UNS	**2A**	**0.0018**	**3.7482**	**3.7379**	—	**3.7018**	**3.6957**	**3.6632**	**2B**	**3.673**	**3.688**	**3.7036**	**3.7115**	**3.7500**
$3\frac{3}{4}$–16 UN	**2A**	**0.0017**	**3.7483**	**3.7389**	—	**3.7077**	**3.7019**	**3.6738**	**2B**	**3.682**	**3.696**	**3.7094**	**3.7169**	**3.7500**
	3A	**0.0000**	**3.7500**	**3.7406**	—	**3.7094**	**3.7051**	**3.6755**	**3B**	**3.6820**	**3.6908**	**3.7094**	**3.7150**	**3.7500**
$3\frac{3}{4}$–18 UNS	**2A**	**0.0017**	**3.7483**	**3.7396**	—	**3.7122**	**3.7067**	**3.6822**	**2B**	**3.690**	**3.703**	**3.7139**	**3.7211**	**3.7500**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
3⅞–6 UN	**2A**	**0.0030**	**3.8720**	**3.8538**	—	**3.7637**	**3.7538**	**3.6736**	**2B**	**3.695**	**3.725**	**3.7667**	**3.7795**	**3.8750**
	3A	**0.0000**	**3.8750**	**3.8568**	—	**3.7667**	**3.7593**	**3.6766**	**3B**	**3.6950**	**3.7146**	**3.7667**	**3.7763**	**3.8750**
3⅞–8 UN	**2A**	**0.0027**	**3.8723**	**3.8573**	—	**3.7911**	**3.7820**	**3.7235**	**2B**	**3.740**	**3.765**	**3.7938**	**3.8056**	**3.8750**
	3A	**0.0000**	**3.8750**	**3.8600**	—	**3.7938**	**3.7870**	**3.7262**	**3B**	**3.7400**	**3.7547**	**3.7938**	**3.8026**	**3.8750**
3⅞–12 UN	**2A**	**0.0020**	**3.8730**	**3.8616**	—	**3.8189**	**3.8124**	**3.7738**	**2B**	**3.785**	**3.803**	**3.8209**	**3.8294**	**3.8750**
	3A	**0.0000**	**3.8750**	**3.8636**	—	**3.8209**	**3.8160**	**3.7758**	**3B**	**3.7850**	**3.7948**	**3.8209**	**3.8273**	**3.8750**
3⅞–16 UN	**2A**	**0.0018**	**3.8732**	**3.8638**	—	**3.8326**	**3.8267**	**3.7987**	**2B**	**3.807**	**3.821**	**3.8344**	**3.8420**	**3.8750**
	3A	**0.0000**	**3.8750**	**3.8656**	—	**3.8344**	**3.8300**	**3.8005**	**3B**	**3.8070**	**3.8158**	**3.8344**	**3.8401**	**3.8750**
4–4 UNC	**1A**	**0.0034**	**3.9966**	**3.9609**	—	**3.8342**	**3.8172**	**3.6989**	**1B**	**3.729**	**3.767**	**3.8376**	**3.8597**	**4.0000**
	2A	**0.0034**	**3.9966**	**3.9728**	**3.9609**	**3.8342**	**3.8229**	**3.6989**	**2B**	**3.729**	**3.767**	**3.8376**	**3.8523**	**4.0000**
	3A	**0.0000**	**4.0000**	**3.9762**	—	**3.8376**	**3.8291**	**3.7023**	**3B**	**3.7290**	**3.7594**	**3.8376**	**3.8487**	**4.0000**
4–6 UN	**2A**	**0.0030**	**3.9970**	**3.9788**	—	**3.8887**	**3.8788**	**3.7986**	**2B**	**3.820**	**3.850**	**3.8917**	**3.9046**	**4.0000**
	3A	**0.0000**	**4.0000**	**3.9818**	—	**3.8917**	**3.8843**	**3.8016**	**3B**	**3.8200**	**3.8396**	**3.8917**	**3.9014**	**4.0000**
4–8 UN	**2A**	**0.0027**	**3.9973**	**3.9823**	**3.9748**	**3.9161**	**3.9070**	**3.8485**	**2B**	**3.865**	**3.890**	**3.9188**	**3.9307**	**4.0000**
	3A	**0.0000**	**4.0000**	**3.9850**	—	**3.9188**	**3.9120**	**3.8512**	**3B**	**3.8650**	**3.8797**	**3.9188**	**3.9277**	**4.0000**
4–10 UNS	**2A**	**0.0021**	**3.9979**	**3.9850**	—	**3.9329**	**3.9259**	**3.8768**	**2B**	**3.892**	**3.913**	**3.9350**	**3.9441**	**4.0000**
4–12 UN	**2A**	**0.0020**	**3.9980**	**3.9866**	—	**3.9439**	**3.9374**	**3.8988**	**2B**	**3.910**	**3.928**	**3.9459**	**3.9544**	**4.0000**
	3A	**0.0000**	**4.0000**	**3.9886**	—	**3.9459**	**3.9410**	**3.9008**	**3B**	**3.9100**	**3.9198**	**3.9459**	**3.9523**	**4.0000**
4–14 UNS	**2A**	**0.0018**	**3.9982**	**3.9879**	—	**3.9518**	**3.9456**	**3.9132**	**2B**	**3.923**	**3.938**	**3.9536**	**3.9616**	**4.0000**
4–16 UN	**2A**	**0.0018**	**3.9982**	**3.9888**	—	**3.9576**	**3.9517**	**3.9237**	**2B**	**3.932**	**3.946**	**3.9594**	**3.9670**	**4.0000**
	3A	**0.0000**	**4.0000**	**3.9906**	—	**3.9594**	**3.9550**	**3.9255**	**3B**	**3.9320**	**3.9408**	**3.9594**	**3.9651**	**4.0000**
4¼–10 UNS	**2A**	**0.0021**	**4.2479**	**4.2350**	—	**4.1829**	**4.1759**	**4.1289**	**2B**	**4.142**	**4.163**	**4.1850**	**4.1941**	**4.2500**
4¼–14 UNS	**2A**	**0.0018**	**4.2482**	**4.2379**	—	**4.2018**	**4.1956**	**4.1632**	**2B**	**4.173**	**4.188**	**4.2036**	**4.2116**	**4.2500**
4¼–12 UN	**2A**	**0.0020**	**4.2480**	**4.2366**	—	**4.1939**	**4.1874**	**4.1488**	**2B**	**4.160**	**4.178**	**4.1959**	**4.2044**	**4.2500**
	3A	**0.0000**	**4.2500**	**4.2386**	—	**4.1959**	**4.1910**	**4.1508**	**3B**	**4.1600**	**4.1698**	**4.1959**	**4.2023**	**4.2500**
4¼–16 UN	**2A**	**0.0018**	**4.2482**	**4.2388**	—	**4.2076**	**4.2017**	**4.1737**	**2B**	**4.182**	**4.196**	**4.2094**	**4.2170**	**4.2500**
	3A	**0.0000**	**4.2500**	**4.2406**	—	**4.2094**	**4.2050**	**4.1755**	**3B**	**4.1820**	**4.1900**	**4.2094**	**4.2151**	**4.2500**
4½–10 UNS	**2A**	**0.0021**	**4.4979**	**4.4850**	—	**4.4329**	**4.4259**	**4.3789**	**2B**	**4.392**	**4.413**	**4.4350**	**4.4441**	**4.5000**
4½–14 UNS	**2A**	**0.0018**	**4.4982**	**4.4879**	—	**4.4518**	**4.4456**	**4.4132**	**2B**	**4.423**	**4.438**	**4.4536**	**4.4616**	**4.5000**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Standard Series and Selected Combinations — Unified Screw Threads**

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
4½–12 UN	**2A**	**0.0020**	**4.4980**	**4.4866**	**—**	**4.4439**	**4.4374**	**4.3988**	**2B**	**4.410**	**4.428**	**4.4459**	**4.4544**	**4.5000**
	3A	**0.0000**	**4.5000**	**4.4886**	**—**	**4.4459**	**4.4410**	**4.4008**	**3B**	**4.4100**	**4.4198**	**4.4459**	**4.4523**	**4.5000**
4½–16 UN	**2A**	**0.0018**	**4.4982**	**4.4888**	**—**	**4.4576**	**4.4517**	**4.4237**	**2B**	**4.432**	**4.446**	**4.4594**	**4.4670**	**4.5000**
	3A	**0.0000**	**4.5000**	**4.4906**	**—**	**4.4594**	**4.4550**	**4.4255**	**3B**	**4.4320**	**4.4408**	**4.4594**	**4.4651**	**4.5000**
4¾–10 UNS	**2A**	**0.0022**	**4.7478**	**4.7349**	**—**	**4.6828**	**4.6756**	**4.6288**	**2B**	**4.642**	**4.663**	**4.6850**	**4.6944**	**4.7500**
4¾–14 UNS	**2A**	**0.0019**	**4.7481**	**4.7378**	**—**	**4.7017**	**4.6953**	**4.6631**	**2B**	**4.673**	**4.688**	**4.7036**	**4.7119**	**4.7500**
4¾–12 UN	**2A**	**0.0020**	**4.7480**	**4.7366**	**—**	**4.6939**	**4.6872**	**4.6488**	**2B**	**4.660**	**4.678**	**4.6959**	**4.7046**	**4.7500**
	3A	**0.0000**	**4.7500**	**4.7386**	**—**	**4.6959**	**4.6909**	**4.6508**	**3B**	**4.6600**	**4.6698**	**4.6959**	**4.7025**	**4.7500**
4¾–16 UN	**2A**	**0.0018**	**4.7482**	**4.7388**	**—**	**4.7076**	**4.7015**	**4.6737**	**2B**	**4.682**	**4.696**	**4.7094**	**4.7173**	**4.7500**
	3A	**0.0000**	**4.7500**	**4.7406**	**—**	**4.7094**	**4.7049**	**4.6755**	**3B**	**4.6820**	**4.6908**	**4.7094**	**4.7153**	**4.7500**
5.00–10 UNS	**2A**	**0.0022**	**4.9978**	**4.9849**	**—**	**4.9328**	**4.9256**	**4.8788**	**2B**	**4.892**	**4.913**	**4.9350**	**4.9444**	**5.0000**
5.00–14 UNS	**2A**	**0.0019**	**4.9981**	**4.9878**	**—**	**4.9517**	**4.9453**	**4.9131**	**2B**	**4.923**	**4.938**	**4.9536**	**4.9619**	**5.0000**
5.00–12 UN	**2A**	**0.0020**	**4.9980**	**4.9866**	**—**	**4.9439**	**4.9372**	**4.8988**	**2B**	**4.910**	**4.928**	**4.9459**	**4.9546**	**5.0000**
	3A	**0.0000**	**5.0000**	**4.9886**	**—**	**4.9459**	**4.9409**	**4.9008**	**3B**	**4.9100**	**4.9198**	**4.9459**	**4.9525**	**5.0000**
5.00–16 UN	**2A**	**0.0018**	**4.9982**	**4.9888**	**—**	**4.9576**	**4.9515**	**4.9237**	**2B**	**4.932**	**4.946**	**4.9594**	**4.9673**	**5.0000**
	3A	**0.0000**	**5.0000**	**4.9906**	**—**	**4.9594**	**4.9549**	**4.9255**	**3B**	**4.9320**	**4.9408**	**4.9594**	**4.9653**	**5.0000**
5¼–10 UNS	**2A**	**0.0022**	**5.2478**	**5.2349**	**—**	**5.1829**	**5.1756**	**5.1288**	**2B**	**5.142**	**5.163**	**5.1850**	**5.1944**	**5.2500**
5¼–14 UNS	**2A**	**0.0019**	**5.2481**	**5.2378**	**—**	**5.2017**	**5.1953**	**5.1631**	**2B**	**5.173**	**5.188**	**5.2036**	**5.2119**	**5.2500**
5¼–12 UN	**2A**	**0.0020**	**5.2480**	**5.2366**	**—**	**5.1939**	**5.1872**	**5.1488**	**2B**	**5.160**	**5.178**	**5.1959**	**5.2046**	**5.2500**
	3A	**0.0000**	**5.2500**	**5.2386**	**—**	**5.1959**	**5.1909**	**5.1508**	**3B**	**5.1600**	**5.1698**	**5.1959**	**5.2025**	**5.2500**
5¼–16 UN	**2A**	**0.0018**	**5.2482**	**5.2388**	**—**	**5.2076**	**5.2015**	**5.1737**	**2B**	**5.182**	**5.196**	**5.2094**	**5.2173**	**5.2500**
	3A	**0.0000**	**5.2500**	**5.2406**	**—**	**5.2094**	**5.2049**	**5.1755**	**3B**	**5.1820**	**5.1908**	**5.2094**	**5.2153**	**5.2500**
5½–10 UNS	**2A**	**0.0022**	**5.4978**	**5.4849**	**—**	**5.4328**	**5.4256**	**5.3788**	**2B**	**5.392**	**5.413**	**5.4350**	**5.4444**	**5.5000**
5½–14 UNS	**2A**	**0.0019**	**5.4981**	**5.4878**	**—**	**5.4517**	**5.4453**	**5.4131**	**2B**	**5.423**	**5.438**	**5.4536**	**5.4619**	**5.5000**
5½–12 UN	**2A**	**0.0020**	**5.4980**	**5.4866**	**—**	**5.4439**	**5.4372**	**5.3988**	**2B**	**5.410**	**5.428**	**5.4459**	**5.4546**	**5.5000**
	3A	**0.0000**	**5.5000**	**5.4886**	**—**	**5.4459**	**5.4409**	**5.4008**	**3B**	**5.4100**	**5.4198**	**5.4459**	**5.4525**	**5.5000**
5½–16 UN	**2A**	**0.0018**	**5.4982**	**5.4888**	**—**	**5.4576**	**5.4515**	**5.4237**	**2B**	**5.432**	**5.446**	**5.4594**	**5.4673**	**5.5000**
	3A	**0.0000**	**5.5000**	**5.4906**	**—**	**5.4594**	**5.4549**	**5.4255**	**3B**	**5.4320**	**5.4408**	**5.4594**	**5.4653**	**5.5000**

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Standard Series and Selected Combinations — Unified Screw Threads

Nominal Size, Threads per Inch, and Series Designation[a]	External[b]								Internal[b]					
			Major Diameter			Pitch Diameter		UNR Minor Dia.,[c] Max		Minor Diameter		Pitch Diameter		Major Diameter
	Class	Allowance	Max[d]	Min	Min[e]	Max[d]	Min	(Ref.)	Class	Min	Max	Min	Max	Min
$5\frac{3}{4}$–10 UNS	**2A**	**0.0022**	**5.7478**	**5.7349**	**—**	**5.6828**	**5.6754**	**5.6288**	**2B**	**5.642**	**5.663**	**5.6850**	**5.6946**	**5.7500**
$5\frac{3}{4}$–14 UNS	**2A**	**0.0020**	**5.7480**	**5.7377**	**—**	**5.7016**	**5.6951**	**5.6630**	**2B**	**5.673**	**5.688**	**5.7036**	**5.7121**	**5.7500**
$5\frac{3}{4}$–12 UN	**2A**	**0.0021**	**5.7479**	**5.7365**	**—**	**5.6938**	**5.6869**	**5.6487**	**2B**	**5.660**	**5.678**	**5.6959**	**5.7049**	**5.7500**
	3A	**0.0000**	**5.7500**	**5.7386**	**—**	**5.6959**	**5.6907**	**5.6508**	**3B**	**5.6600**	**5.6698**	**5.6959**	**5.7026**	**5.7500**
$5\frac{3}{4}$–16 UN	**2A**	**0.0019**	**5.7481**	**5.7387**	**—**	**5.7075**	**5.7013**	**5.6736**	**2B**	**5.682**	**5.696**	**5.7094**	**5.7175**	**5.7500**
	3A	**0.0000**	**5.7500**	**5.7406**	**—**	**5.7094**	**5.7047**	**5.6755**	**3B**	**5.6820**	**5.6908**	**5.7094**	**5.7155**	**5.7500**
6–10 UNS	**2A**	**0.0022**	**5.9978**	**5.9849**	**—**	**5.9328**	**5.9254**	**5.8788**	**2B**	**5.892**	**5.913**	**5.9350**	**5.9446**	**6.0000**
6–14 UNS	**2A**	**0.0020**	**5.9980**	**5.9877**	**—**	**5.9516**	**5.9451**	**5.9130**	**2B**	**5.923**	**5.938**	**5.9536**	**5.9621**	**6.0000**
6–12 UN	**2A**	**0.0021**	**5.9979**	**5.9865**	**—**	**5.9438**	**5.9369**	**5.8987**	**2B**	**5.910**	**5.928**	**5.9459**	**5.9549**	**6.0000**
	3A	**0.0000**	**6.0000**	**5.9886**	**—**	**5.9459**	**5.9407**	**5.9008**	**3B**	**5.9100**	**5.9198**	**5.9459**	**5.9526**	**6.0000**
6–16 UN	**2A**	**0.0019**	**5.9981**	**5.9887**	**—**	**5.9575**	**5.9513**	**5.9236**	**2B**	**5.932**	**5.946**	**5.9594**	**5.9675**	**6.0000**
	3A	**0.0000**	**6.0000**	**5.9906**	**—**	**5.9594**	**5.9547**	**5.9255**	**3B**	**5.9320**	**5.9408**	**5.9594**	**5.9655**	**6.0000**

[a] Use UNR designation instead of UN wherever UNR thread form is desired for external use.

[b] Regarding combinations of thread classes, see text on page 1773.

[c] UN series external thread maximum minor diameter is basic for Class 3A and basic minus allowance for Classes 1A and 2A.

[d] For Class 2A threads having an additive finish the maximum is increased, by the allowance, to the basic size, the value being the same as for Class 3A.

[e] For unfinished hot-rolled material not including standard fasteners with rolled threads.

[f] Formerly NF, tolerances and allowances are based on one diameter length of engagement.

All dimensions in inches.

Use UNS threads only if Standard Series do not meet requirements (see pages 1733, 1765, and 1776). For additional sizes above 4 inches see ASME/ANSI B1.1-1989 (R2001).

Copyright 2004, Industrial Press, Inc., New York, NY

Coarse-Thread Series: This series, UNC/UNRC, is the one most commonly used in the bulk production of bolts, screws, nuts and other general engineering applications. It is also used for threading into lower tensile strength materials such as cast iron, mild steel and softer materials (bronze, brass, aluminum, magnesium and plastics) to obtain the optimum resistance to stripping of the internal thread. It is applicable for rapid assembly or disassembly, or if corrosion or slight damage is possible.

Table 4a. Coarse-Thread Series, UNC and UNRC — Basic Dimensions

Sizes No. or Inches	Basic Major Dia., D	Thds. per Inch, n	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D\text{-}2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
	Inches		Inches	Inches	Inches	Deg.	Min	Sq. In.	Sq. In.
1 (0.073)[e]	**0.0730**	**64**	**0.0629**	**0.0544**	**0.0561**	**4**	**31**	0.00218	0.00263
2 (0.086)	**0.0860**	**56**	**0.0744**	**0.0648**	**0.0667**	**4**	**22**	0.00310	0.00370
3 (0.099)[e]	**0.0990**	**48**	**0.0855**	**0.0741**	**0.0764**	**4**	**26**	0.00406	0.00487
4 (0.112)	**0.1120**	**40**	**0.0958**	**0.0822**	**0.0849**	**4**	**45**	0.00496	0.00604
5 (0.125)	**0.1250**	**40**	**0.1088**	**0.0952**	**0.0979**	**4**	**11**	0.00672	0.00796
6 (0.138)	**0.1380**	**32**	**0.1177**	**0.1008**	**0.1042**	**4**	**50**	0.00745	0.00909
8 (0.164)	**0.1640**	**32**	**0.1437**	**0.1268**	**0.1302**	**3**	**58**	0.01196	0.0140
10 (0.190)	**0.1900**	**24**	**0.1629**	**0.1404**	**0.1449**	**4**	**39**	0.01450	0.0175
12 (0.216)[e]	**0.2160**	**24**	**0.1889**	**0.1664**	**0.1709**	**4**	**1**	0.0206	0.0242
1/4	**0.2500**	**20**	**0.2175**	**0.1905**	**0.1959**	**4**	**11**	0.0269	0.0318
5/16	**0.3125**	**18**	**0.2764**	**0.2464**	**0.2524**	**3**	**40**	0.0454	0.0524
3/8	**0.3750**	**16**	**0.3344**	**0.3005**	**0.3073**	**3**	**24**	0.0678	0.0775
7/16	**0.4375**	**14**	**0.3911**	**0.3525**	**0.3602**	**3**	**20**	0.0933	0.1063
1/2	**0.5000**	**13**	**0.4500**	**0.4084**	**0.4167**	**3**	**7**	0.1257	0.1419
9/16	**0.5625**	**12**	**0.5084**	**0.4633**	**0.4723**	**2**	**59**	0.162	0.182
5/8	**0.6250**	**11**	**0.5660**	**0.5168**	**0.5266**	**2**	**56**	0.202	0.226
3/4	**0.7500**	**10**	**0.6850**	**0.6309**	**0.6417**	**2**	**40**	0.302	0.334
7/8	**0.8750**	**9**	**0.8028**	**0.7427**	**0.7547**	**2**	**31**	0.419	0.462
1	**1.0000**	**8**	**0.9188**	**0.8512**	**0.8647**	**2**	**29**	0.551	0.606
1 1/8	**1.1250**	**7**	**1.0322**	**0.9549**	**0.9704**	**2**	**31**	0.693	0.763
1 1/4	**1.2500**	**7**	**1.1572**	**1.0799**	**1.0954**	**2**	**15**	0.890	0.969
1 3/8	**1.3750**	**6**	**1.2667**	**1.1766**	**1.1946**	**2**	**24**	1.054	1.155
1 1/2	**1.5000**	**6**	**1.3917**	**1.3016**	**1.3196**	**2**	**11**	1.294	1.405
1 3/4	**1.7500**	**5**	**1.6201**	**1.5119**	**1.5335**	**2**	**15**	1.74	1.90
2	**2.0000**	**4 1/2**	**1.8557**	**1.7353**	**1.7594**	**2**	**11**	2.30	2.50
2 1/4	**2.2500**	**4 1/2**	**2.1057**	**1.9853**	**2.0094**	**1**	**55**	3.02	3.25
2 1/2	**2.5000**	**4**	**2.3376**	**2.2023**	**2.2294**	**1**	**57**	3.72	4.00
2 3/4	**2.7500**	**4**	**2.5876**	**2.4523**	**2.4794**	**1**	**46**	4.62	4.93
3	**3.0000**	**4**	**2.8376**	**2.7023**	**2.7294**	**1**	**36**	5.62	5.97
3 1/4	**3.2500**	**4**	**3.0876**	**2.9523**	**2.9794**	**1**	**29**	6.72	7.10
3 1/4	**3.500**	**4**	**3.3376**	**3.2023**	**3.2294**	**1**	**22**	7.92	8.33
3 3/4	**3.7500**	**4**	**3.5876**	**3.4523**	**3.4794**	**1**	**16**	9.21	9.66
4	**4.0000**	**4**	**3.8376**	**3.7023**	**3.7294**	**1**	**11**	10.61	11.08

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] Secondary sizes.

Fine-Thread Series: This series, UNF/UNRF, is suitable for the production of bolts, screws, and nuts and for other applications where the Coarse series is not applicable. External threads of this series have greater tensile stress area than comparable sizes of the Coarse series. The Fine series is suitable when the resistance to stripping of both external

Copyright 2004, Industrial Press, Inc., New York, NY

and mating internal threads equals or exceeds the tensile load carrying capacity of the externally threaded member (see page 1510). It is also used where the length of engagement is short, where a smaller lead angle is desired, where the wall thickness demands a fine pitch, or where finer adjustment is needed.

Table 4b. Fine-Thread Series, UNF and UNRF — Basic Dimensions

Sizes No. or Inches	Basic Major Dia., D	Thds. per Inch, n	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at D-$2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
	Inches		Inches	Inches	Inches	Deg.	Min	Sq. In.	Sq. In.
0 (0.060)	**0.0600**	**80**	**0.0519**	**0.0451**	**0.0465**	**4**	**23**	0.00151	0.00180
1 (0.073)[e]	**0.0730**	**72**	**0.0640**	**0.0565**	**0.0580**	**3**	**57**	0.00237	0.00278
2 (0.086)	**0.0860**	**64**	**0.0759**	**0.0674**	**0.0691**	**3**	**45**	0.00339	0.00394
3 (0.099)[e]	**0.0990**	**56**	**0.0874**	**0.0778**	**0.0797**	**3**	**43**	0.00451	0.00523
4 (0.112)	**0.1120**	**48**	**0.0985**	**0.0871**	**0.0894**	**3**	**51**	0.00566	0.00661
5 (0.125)	**0.1250**	**44**	**0.1102**	**0.0979**	**0.1004**	**3**	**45**	0.00716	0.00830
6 (0.138)	**0.1380**	**40**	**0.1218**	**0.1082**	**0.1109**	**3**	**44**	0.00874	0.01015
8 (0.164)	**0.1640**	**36**	**0.1460**	**0.1309**	**0.1339**	**3**	**28**	0.01285	0.01474
10 (0.190)	**0.1900**	**32**	**0.1697**	**0.1528**	**0.1562**	**3**	**21**	0.0175	0.0200
12 (0.216)[e]	**0.2160**	**28**	**0.1928**	**0.1734**	**0.1773**	**3**	**22**	0.0226	0.258
1/4	**0.2500**	**28**	**0.2268**	**0.2074**	**0.2113**	**2**	**52**	0.0326	0.0364
5/16	**0.3125**	**24**	**0.2854**	**0.2629**	**0.2674**	**2**	**40**	0.0524	0.0580
3/8	**0.3750**	**24**	**0.3479**	**0.3254**	**0.3299**	**2**	**11**	0.0809	0.0878
7/16	**0.4375**	**20**	**0.4050**	**0.3780**	**0.3834**	**2**	**15**	0.1090	0.1187
1/2	**0.5000**	**20**	**0.4675**	**0.4405**	**0.4459**	**1**	**57**	0.1486	0.1599
9/16	**0.5625**	**18**	**0.5264**	**0.4964**	**0.5024**	**1**	**55**	0.189	0.203
5/8	**0.6250**	**18**	**0.5889**	**0.5589**	**0.5649**	**1**	**43**	0.240	0.256
3/4	**0.7500**	**16**	**0.7094**	**0.6763**	**0.6823**	**1**	**36**	0.351	0.373
7/8	**0.8750**	**14**	**0.8286**	**0.7900**	**0.7977**	**1**	**34**	0.480	0.509
1	**1.0000**	**12**	**0.9459**	**0.9001**	**0.9098**	**1**	**36**	0.625	0.663
1 1/8	**1.1250**	**12**	**1.0709**	**1.0258**	**1.0348**	**1**	**25**	0.812	0.856
1 1/4	**1.2500**	**12**	**1.1959**	**1.1508**	**1.1598**	**1**	**16**	1.024	1.073
1 3/8	**1.3750**	**12**	**1.3209**	**1.2758**	**1.2848**	**1**	**9**	1.260	1.315
1 1/2	**1.5000**	**12**	**1.4459**	**1.4008**	**1.4098**	**1**	**3**	1.521	1.581

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] Secondary sizes.

Extra-Fine-Thread Series: This series, UNEF/UNREF, is applicable where even finer pitches of threads are desirable, as for short lengths of engagement and for thin-walled tubes, nuts, ferrules, or couplings. It is also generally applicable under the conditions stated above for the fine threads. See Table 4c.

Fine Threads for Thin-Wall Tubing: Dimensions for a 27-thread series, ranging from 1/4- to 1-inch nominal size, also are included in Table 3. These threads are recommended for general use on thin-wall tubing. The minimum length of complete thread is one-third of the basic major diameter plus 5 threads (+0.185 in.).

Selected Combinations: Thread data are tabulated in Table 3 for certain additional selected special combinations of diameter and pitch, with pitch diameter tolerances based on a length of thread engagement of 9 times the pitch. The pitch diameter limits are applicable to a length of engagement of from 5 to 15 times the pitch. (This provision should not be confused with the lengths of thread on mating parts, as they may exceed the length of engagement by a considerable amount.) Thread symbols are UNS and UNRS.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4c. Extra-Fine-Thread Series, UNEF and UNREF — Basic Dimensions

Sizes No. or Inches	Basic Major Dia., D	Thds. per Inch, n	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
	Inches		Inches	Inches	Inches	Deg.	Min	Sq. In.	Sq. In.
12 (0.216)[e]	**0.2160**	**32**	**0.1957**	**0.1788**	**0.1822**	**2**	**55**	0.0242	0.0270
1/4	**0.2500**	**32**	**0.2297**	**0.2128**	**0.2162**	**2**	**29**	0.0344	0.0379
5/16	**0.3125**	**32**	**0.2922**	**0.2753**	**0.2787**	**1**	**57**	0.0581	0.0625
3/8	**0.3750**	**32**	**0.3547**	**0.3378**	**0.3412**	**1**	**36**	0.0878	0.0932
7/16	**0.4375**	**28**	**0.4143**	**0.3949**	**0.3988**	**1**	**34**	0.1201	0.1274
1/2	**0.5000**	**28**	**0.4768**	**0.4574**	**0.4613**	**1**	**22**	0.162	0.170
9/16	**0.5625**	**24**	**0.5354**	**0.5129**	**0.5174**	**1**	**25**	0.203	0.214
5/8	**0.6250**	**24**	**0.5979**	**0.5754**	**0.5799**	**1**	**16**	0.256	0.268
11/16[e]	**0.6875**	**24**	**0.6604**	**0.6379**	**0.6424**	**1**	**9**	0.315	0.329
3/4	**0.7500**	**20**	**0.7175**	**0.6905**	**0.6959**	**1**	**16**	0.369	0.386
13/16[e]	**0.8125**	**20**	**0.7800**	**0.7530**	**0.7584**	**1**	**10**	0.439	0.458
7/8	**0.8750**	**20**	**0.8425**	**0.8155**	**0.8209**	**1**	**5**	0.515	0.536
15/16[e]	**0.9375**	**20**	**0.9050**	**0.8780**	**0.8834**	**1**	**0**	0.598	0.620
1	**1.0000**	**20**	**0.9675**	**0.9405**	**0.9459**	**0**	**57**	0.687	0.711
1 1/16[e]	**1.0625**	**18**	**1.0264**	**0.9964**	**1.0024**	**0**	**59**	0.770	0.799
1 1/8	**1.1250**	**18**	**1.0889**	**1.0589**	**1.0649**	**0**	**56**	0.871	0.901
1 3/16[e]	**1.1875**	**18**	**1.1514**	**1.1214**	**1.1274**	**0**	**53**	0.977	1.009
1 1/4	**1.2500**	**18**	**1.2139**	**1.1839**	**1.1899**	**0**	**50**	1.090	1.123
1 5/16[e]	**1.3125**	**18**	**1.2764**	**1.2464**	**1.2524**	**0**	**48**	1.208	1.244
1 3/8	**1.3750**	**18**	**1.3389**	**1.3089**	**1.3149**	**0**	**45**	1.333	1.370
1 7/16[e]	**1.4375**	**18**	**1.4014**	**1.3714**	**1.3774**	**0**	**43**	1.464	1.503
1 1/2	**1.5000**	**18**	**1.4639**	**1.4339**	**1.4399**	**0**	**42**	1.60	1.64
1 9/16[e]	**1.5625**	**18**	**1.5264**	**1.4964**	**1.5024**	**0**	**40**	1.74	1.79
1 5/8	**1.6250**	**18**	**1.5889**	**1.5589**	**1.5649**	**0**	**38**	1.89	1.94
1 11/16[e]	**1.6875**	**18**	**1.6514**	**1.6214**	**1.6274**	**0**	**37**	2.05	2.10

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] Secondary sizes.

Other Threads of Special Diameters, Pitches, and Lengths of Engagement: Thread data for special combinations of diameter, pitch, and length of engagement not included in selected combinations are also given in the Standard but are not given here. Also, when design considerations require non-standard pitches or extreme conditions of engagement not covered by the tables, the allowance and tolerances should be derived from the formulas in the Standard. The thread symbol for such special threads is UNS.

Constant Pitch Series.— The various constant-pitch series, UN, with 4, 6, 8, 12, 16, 20, 28 and 32 threads per inch, given in Table 3, offer a comprehensive range of diameter-pitch combinations for those purposes where the threads in the Coarse, Fine, and Extra-Fine series do not meet the particular requirements of the design.

When selecting threads from these constant-pitch series, preference should be given wherever possible to those tabulated in the 8-, 12-, or 16-thread series.

8-Thread Series: The 8-thread series (8-UN) is a uniform-pitch series for large diameters. Although originally intended for high-pressure-joint bolts and nuts, it is now widely used as a substitute for the Coarse-Thread Series for diameters larger than 1 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

12-Thread Series: The 12-thread series (12-UN) is a uniform pitch series for large diameters requiring threads of medium-fine pitch. Although originally intended for boiler practice, it is now used as a continuation of the Fine-Thread Series for diameters larger than 1½ inches.

16-Thread Series: The 16-thread series (16-UN) is a uniform pitch series for large diameters requiring fine-pitch threads. It is suitable for adjusting collars and retaining nuts, and also serves as a continuation of the Extra-fine Thread Series for diameters larger than 1 11/16 inches.

4-, 6-, 20-, 28-, and 32-Thread Series: These thread series have been used more or less widely in industry for various applications where the Standard Coarse, Fine or Extra-fine Series were not as applicable. They are now recognized as Standard Unified Thread Series in a specified selection of diameters for each pitch (see Table 2).

Whenever a thread in a constant-pitch series also appears in the UNC, UNF, or UNEF series, the symbols and tolerances for limits of size of UNC, UNF, or UNEF series are applicable, as will be seen in Tables 2 and 3.

Table 5a. 4–Thread Series, 4–UN and 4–UNR — Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Primary	Secondary	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
2½[e]		**2.5000**	**2.3376**	**2.2023**	**2.2294**	**1**	**57**	3.72	4.00
	2⅝	**2.6250**	**2.4626**	**2.3273**	**2.3544**	**1**	**51**	4.16	4.45
2¾[e]		**2.7500**	**2.5876**	**2.4523**	**2.4794**	**1**	**46**	4.62	4.93
	2⅞	**2.8750**	**2.7126**	**2.5773**	**2.6044**	**1**	**41**	5.11	5.44
3[e]		**3.0000**	**2.8376**	**2.7023**	**2.7294**	**1**	**36**	5.62	5.97
	3⅛	**3.1250**	**2.9626**	**2.8273**	**2.8544**	**1**	**32**	6.16	6.52
3¼[e]		**3.2500**	**3.0876**	**2.9523**	**2.9794**	**1**	**29**	6.72	7.10
	3⅜	**3.3750**	**3.2126**	**3.0773**	**3.1044**	**1**	**25**	7.31	7.70
3½[e]		**3.5000**	**3.3376**	**3.2023**	**3.2294**	**1**	**22**	7.92	8.33
	3⅝	**3.6250**	**3.4626**	**3.3273**	**3.3544**	**1**	**19**	8.55	9.00
3¾[e]		**3.7500**	**3.5876**	**3.4523**	**3.4794**	**1**	**16**	9.21	9.66
	3⅞	**3.8750**	**3.7126**	**3.5773**	**3.6044**	**1**	**14**	9.90	10.36
4[e]		**4.0000**	**3.8376**	**3.7023**	**3.7294**	**1**	**11**	10.61	11.08
	4⅛	**4.1250**	**3.9626**	**3.8273**	**3.8544**	**1**	**9**	11.34	11.83
4¼		**4.2500**	**4.0876**	**3.9523**	**3.9794**	**1**	**7**	12.10	12.61
	4⅜	**4.3750**	**4.2126**	**4.0773**	**4.1044**	**1**	**5**	12.88	13.41
4½		**4.5000**	**4.3376**	**4.2023**	**4.2294**	**1**	**3**	13.69	14.23
	4⅝	**4.6250**	**4.4626**	**4.3273**	**4.3544**	**1**	**1**	14.52	15.1
4¾		**4.7500**	**4.5876**	**4.4523**	**4.4794**	**1**	**0**	15.4	15.9
	4⅞	**4.8750**	**4.7126**	**4.5773**	**4.6044**	**0**	**58**	16.3	16.8
5		**5.0000**	**4.8376**	**4.7023**	**4.7294**	**0**	**57**	17.2	17.8
	5⅛	**5.1250**	**4.9626**	**4.8273**	**4.8544**	**0**	**55**	18.1	18.7
5¼		**5.2500**	**5.0876**	**4.9523**	**4.9794**	**0**	**54**	19.1	19.7
	5⅜	**5.3750**	**5.2126**	**5.0773**	**5.1044**	**0**	**52**	20.0	20.7
5½		**5.5000**	**5.3376**	**5.2023**	**5.2294**	**0**	**51**	21.0	21.7
	5⅝	**5.6250**	**5.4626**	**5.3273**	**5.3544**	**0**	**50**	22.1	22.7
5¾		**5.7500**	**5.5876**	**5.4523**	**5.4794**	**0**	**49**	23.1	23.8
	5⅞	**5.8750**	**5.7126**	**5.5773**	**5.6044**	**0**	**48**	24.2	24.9
6		**6.0000**	**5.8376**	**5.7023**	**5.7294**	**0**	**47**	25.3	26.0

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733).
[d] Basic minor diameter.
[e] These are standard sizes of the UNC series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5b. 6–Thread Series, 6–UN and 6–UNR — Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Primary	Secondary								
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
1 3/8[e]		**1.3750**	**1.2667**	**1.1766**	**1.1946**	**2**	**24**	1.054	1.155
	1 7/16	**1.4375**	**1.3292**	**1.2391**	**1.2571**	**2**	**17**	1.171	1.277
1 1/2[e]		**1.5000**	**1.3917**	**1.3016**	**1.3196**	**2**	**11**	1.294	1.405
	1 9/16	**1.5625**	**1.4542**	**1.3641**	**1.3821**	**2**	**5**	1.423	1.54
1 5/8		**1.6250**	**1.5167**	**1.4271**	**1.4446**	**2**	**0**	1.56	1.68
	1 11/16	**1.6875**	**1.5792**	**1.4891**	**1.5071**	**1**	**55**	1.70	1.83
1 3/4		**1.7500**	**1.6417**	**1.5516**	**1.5696**	**1**	**51**	1.85	1.98
	1 13/16	**1.8125**	**1.7042**	**1.6141**	**1.6321**	**1**	**47**	2.00	2.14
1 7/8		**1.8750**	**1.7667**	**1.6766**	**1.6946**	**1**	**43**	2.16	2.30
	1 15/16	**1.9375**	**1.8292**	**1.7391**	**1.7571**	**1**	**40**	2.33	2.47
2		**2.0000**	**1.8917**	**1.8016**	**1.8196**	**1**	**36**	2.50	2.65
	2 1/8	**2.1250**	**2.0167**	**1.9266**	**1.9446**	**1**	**30**	2.86	3.03
2 1/4		**2.2500**	**2.1417**	**2.0516**	**2.0696**	**1**	**25**	3.25	3.42
	2 3/8	**2.3750**	**2.2667**	**2.1766**	**2.1946**	**1**	**20**	3.66	3.85
2 1/2		**2.5000**	**2.3917**	**2.3016**	**2.3196**	**1**	**16**	4.10	4.29
	2 5/8	**2.6250**	**2.5167**	**2.4266**	**2.4446**	**1**	**12**	4.56	4.76
2 3/4		**2.7500**	**2.6417**	**2.5516**	**2.5696**	**1**	**9**	5.04	5.26
	2 7/8	**2.8750**	**2.7667**	**2.6766**	**2.6946**	**1**	**6**	5.55	5.78
3		**3.0000**	**2.8917**	**2.8016**	**2.8196**	**1**	**3**	6.09	6.33
	3 1/8	**3.1250**	**3.0167**	**2.9266**	**2.9446**	**1**	**0**	6.64	6.89
3 1/4		**3.2500**	**3.1417**	**3.0516**	**3.0696**	**0**	**58**	7.23	7.49
	3 3/8	**3.3750**	**3.2667**	**3.1766**	**3.1946**	**0**	**56**	7.84	8.11
3 1/2		**3.5000**	**3.3917**	**3.3016**	**3.3196**	**0**	**54**	8.47	8.75
	3 5/8	**3.6250**	**3.5167**	**3.4266**	**3.4446**	**0**	**52**	9.12	9.42
3 3/4		**3.7500**	**3.6417**	**3.5516**	**3.5696**	**0**	**50**	9.81	10.11
	3 7/8	**3.8750**	**3.7667**	**3.6766**	**3.6946**	**0**	**48**	10.51	10.83
4		**4.0000**	**3.8917**	**3.8016**	**3.8196**	**0**	**47**	11.24	11.57
	4 1/8	**4.1250**	**4.0167**	**3.9266**	**3.9446**	**0**	**45**	12.00	12.33
4 1/4		**4.2500**	**4.1417**	**4.0516**	**4.0696**	**0**	**44**	12.78	13.12
	4 3/8	**4.3750**	**4.2667**	**4.1766**	**4.1946**	**0**	**43**	13.58	13.94
4 1/2		**4.5000**	**4.3917**	**4.3016**	**4.3196**	**0**	**42**	14.41	14.78
	4 5/8	**4.6250**	**4.5167**	**4.4266**	**4.4446**	**0**	**40**	15.3	15.6
4 3/4		**4.7500**	**4.6417**	**4.5516**	**4.5696**	**0**	**39**	16.1	16.5
	4 7/8	**4.8750**	**4.7667**	**4.6766**	**4.6946**	**0**	**38**	17.0	17.5
5		**5.0000**	**4.8917**	**4.8016**	**4.8196**	**0**	**37**	18.0	18.4
	5 1/8	**5.1250**	**5.0167**	**4.9266**	**4.9446**	**0**	**36**	18.9	19.3
5 1/4		**5.2500**	**5.1417**	**5.0516**	**5.0696**	**0**	**35**	19.9	20.3
	5 3/8	**5.3750**	**5.2667**	**5.1766**	**5.1946**	**0**	**35**	20.9	21.3
5 1/2		**5.5000**	**5.3917**	**5.3016**	**5.3196**	**0**	**34**	21.9	22.4
	5 5/8	**5.6250**	**5.5167**	**5.4266**	**5.4446**	**0**	**33**	23.0	23.4
5 3/4		**5.7500**	**5.6417**	**5.5516**	**5.5696**	**0**	**32**	24.0	24.5
	5 7/8	**5.8750**	**5.7667**	**5.6766**	**5.6946**	**0**	**32**	25.1	25.6
6		**6.0000**	**5.8917**	**5.8016**	**5.8196**	**0**	**31**	26.3	26.8

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733).
[d] Basic minor diameter.
[e] These are standard sizes of the UNC series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5c. 8–Thread Series, 8–UN and 8–UNR—Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext.Thds.,[c] d_3 (Ref.)	Int.Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
1[e]		1.0000	0.9188	0.8512	0.8647	2	29	0.551	0.606
	1 1/16	1.0625	0.9813	0.9137	0.9272	2	19	0.636	0.695
1 1/8		1.1250	1.0438	0.9792	0.9897	2	11	0.728	0.790
	1 3/16	1.1875	1.1063	1.0387	1.0522	2	4	0.825	0.892
1 1/4		1.2500	1.1688	1.1012	1.1147	1	57	0.929	1.000
	1 5/16	1.3125	1.2313	1.1637	1.1772	1	51	1.039	1.114
1 3/8		1.3750	1.2938	1.2262	1.2397	1	46	1.155	1.233
	1 7/16	1.4375	1.3563	1.2887	1.3022	1	41	1.277	1.360
1 1/2		1.5000	1.4188	1.3512	1.3647	1	36	1.405	1.492
	1 9/16	1.5625	1.4813	1.4137	1.4272	1	32	1.54	1.63
1 5/8		1.6250	1.5438	1.4806	1.4897	1	29	1.68	1.78
	1 11/16	1.6875	1.6063	1.5387	1.5522	1	25	1.83	1.93
1 3/4		1.7500	1.6688	1.6012	1.6147	1	22	1.98	2.08
	1 13/16	1.8125	1.7313	1.6637	1.6772	1	19	2.14	2.25
1 7/8		1.8750	1.7938	1.7262	1.7397	1	16	2.30	2.41
	1 15/16	1.9375	1.8563	1.7887	1.8022	1	14	2.47	2.59
2		2.0000	1.9188	1.8512	1.8647	1	11	2.65	2.77
	2 1/8	2.1250	2.0438	1.9762	1.9897	1	7	3.03	3.15
2 1/4		2.2500	2.1688	2.1012	2.1147	1	3	3.42	3.56
	2 3/8	2.3750	2.2938	2.2262	2.2397	1	0	3.85	3.99
2 1/2		2.5000	2.4188	2.3512	2.3647	0	57	4.29	4.44
	2 5/8	2.6250	2.5438	2.4762	2.4897	0	54	4.76	4.92
2 3/4		2.7500	2.6688	2.6012	2.6147	0	51	5.26	5.43
	2 7/8	2.8750	2.7938	2.7262	2.7397	0	49	5.78	5.95
3		3.0000	2.9188	2.8512	2.8647	0	47	6.32	6.51
	3 1/8	3.1250	3.0438	2.9762	2.9897	0	45	6.89	7.08
3 1/4		3.2500	3.1688	3.1012	3.1147	0	43	7.49	7.69
	3 3/8	3.3750	3.2938	3.2262	3.2397	0	42	8.11	8.31
3 1/2		3.5000	3.4188	3.3512	3.3647	0	40	8.75	8.96
	3 5/8	3.6250	3.5438	3.4762	3.4897	0	39	9.42	9.64
3 3/4		3.7500	3.6688	3.6012	3.6147	0	37	10.11	10.34
	3 7/8	3.8750	3.7938	3.7262	3.7397	0	36	10.83	11.06
4		4.0000	3.9188	3.8512	3.8647	0	35	11.57	11.81
	4 1/8	4.1250	4.0438	3.9762	3.9897	0	34	12.34	12.59
4 1/4		4.2500	4.1688	4.1012	4.1147	0	33	13.12	13.38
	4 3/8	4.3750	4.2938	4.2262	4.2397	0	32	13.94	14.21
4 1/2		4.5000	4.4188	4.3512	4.3647	0	31	14.78	15.1
	4 5/8	4.6250	4.5438	4.4762	4.4897	0	30	15.6	15.9
4 3/4		4.7500	4.6688	4.6012	4.6147	0	29	16.5	16.8
	4 7/8	4.8750	4.7938	4.7262	4.7397	0	29	17.4	17.7
5		5.0000	4.9188	4.8512	4.8647	0	28	18.4	18.7
	5 1/8	5.1250	5.0438	4.9762	4.9897	0	27	19.3	19.7
5 1/4		5.2500	5.1688	5.1012	5.1147	0	26	20.3	20.7
	5 3/8	5.3750	5.2938	5.2262	5.2397	0	26	21.3	21.7
5 1/2		5.5000	5.4188	5.3512	5.3647	0	25	22.4	22.7
	5 5/8	5.6250	5.5438	5.4762	5.4897	0	25	23.4	23.8
5 3/4		5.7500	5.6688	5.6012	5.6147	0	24	24.5	24.9
	5 7/8	5.8750	5.7938	5.7262	5.7397	0	24	25.6	26.0
6		6.0000	5.9188	5.8512	5.8647	0	23	26.8	27.1

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733).
[d] Basic minor diameter.
[e] This is a standard size of the UNC series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5d. 12-Thread series, 12-UN and 12-UNR—Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
				Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Primary	Secondary								
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
9/16[e]		**0.5625**	**0.5084**	**0.4633**	**0.4723**	**2**	**59**	0.162	0.182
5/8		**0.6250**	**0.5709**	**0.5258**	**0.5348**	**2**	**40**	0.210	0.232
	11/16	**0.6875**	**0.6334**	**0.5883**	**0.5973**	**2**	**24**	0.264	0.289
3/4		**0.7500**	**0.6959**	**0.6508**	**0.6598**	**2**	**11**	0.323	0.351
	13/16	**0.8125**	**0.7584**	**0.7133**	**0.7223**	**2**	**0**	0.390	0.420
7/8		**0.8750**	**0.8209**	**0.7758**	**0.7848**	**1**	**51**	0.462	0.495
	15/16	**0.9375**	**0.8834**	**0.8383**	**0.8473**	**1**	**43**	0.540	0.576
1[e]		**1.0000**	**0.9459**	**0.9008**	**0.9098**	**1**	**36**	0.625	0.663
	1 1/16	**1.0625**	**1.0084**	**0.9633**	**0.9723**	**1**	**30**	0.715	0.756
1 1/8[e]		**1.1250**	**1.0709**	**1.0258**	**1.0348**	**1**	**25**	0.812	0.856
	1 3/16	**1.1875**	**1.1334**	**1.0883**	**1.0973**	**1**	**20**	0.915	0.961
1 1/4[e]		**1.2500**	**1.1959**	**1.1508**	**1.1598**	**1**	**16**	1.024	1.073
	1 5/16	**1.3125**	**1.2584**	**1.2133**	**1.2223**	**1**	**12**	1.139	1.191
1 3/8		**1.3750**	**1.3209**	**1.2758**	**1.2848**	**1**	**9**	1.260	1.315
	1 7/16	**1.4375**	**1.3834**	**1.3383**	**1.3473**	**1**	**6**	1.388	1.445
1 1/2[e]		**1.5000**	**1.4459**	**1.4008**	**1.4098**	**1**	**3**	1.52	1.58
	1 9/16	**1.5625**	**1.5084**	**1.4633**	**1.4723**	**1**	**0**	1.66	1.72
1 5/8		**1.6250**	**1.5709**	**1.5258**	**1.5348**	**0**	**58**	1.81	1.87
	1 11/16	**1.6875**	**1.6334**	**1.5883**	**1.5973**	**0**	**56**	1.96	2.03
1 3/4		**1.7500**	**1.6959**	**1.6508**	**1.6598**	**0**	**54**	2.12	2.19
	1 13/16	**1.8125**	**1.7584**	**1.7133**	**1.7223**	**0**	**52**	2.28	2.35
1 7/8		**1.8750**	**1.8209**	**1.7758**	**1.7848**	**0**	**50**	2.45	2.53
	1 15/16	**1.9375**	**1.8834**	**1.8383**	**1.8473**	**0**	**48**	2.63	2.71
2		**2.0000**	**1.9459**	**1.9008**	**1.9098**	**0**	**47**	2.81	2.89
	2 1/8	**2.1250**	**2.0709**	**2.0258**	**2.0348**	**0**	**44**	3.19	3.28
2 1/4		**2.2500**	**2.1959**	**2.1508**	**2.1598**	**0**	**42**	3.60	3.69
	2 3/8	**2.3750**	**2.3209**	**2.2758**	**2.2848**	**0**	**39**	4.04	4.13
2 1/2		**2.5000**	**2.4459**	**2.4008**	**2.4098**	**0**	**37**	4.49	4.60
	2 5/8	**2.6250**	**2.5709**	**2.5258**	**2.5348**	**0**	**35**	4.97	5.08
2 3/4		**2.7500**	**2.6959**	**2.6508**	**2.6598**	**0**	**34**	5.48	5.59
	2 7/8	**2.8750**	**2.8209**	**2.7758**	**2.7848**	**0**	**32**	6.01	6.13
3		**3.0000**	**2.9459**	**2.9008**	**2.9098**	**0**	**31**	6.57	6.69
	3 1/8	**3.1250**	**3.0709**	**3.0258**	**3.0348**	**0**	**30**	7.15	7.28
3 1/4		**3.2500**	**3.1959**	**3.1508**	**3.1598**	**0**	**29**	7.75	7.89
	3 3/8	**3.3750**	**3.3209**	**3.2758**	**3.2848**	**0**	**27**	8.38	8.52
3 1/2		**3.5000**	**3.4459**	**3.4008**	**3.4098**	**0**	**26**	9.03	9.18
	3 5/8	**3.6250**	**3.5709**	**3.5258**	**3.5348**	**0**	**26**	9.71	9.86
3 3/4		**3.7500**	**3.6959**	**3.6508**	**3.6598**	**0**	**25**	10.42	10.57
	3 7/8	**3.8750**	**3.8209**	**3.7758**	**3.7848**	**0**	**24**	11.14	11.30
4		**4.0000**	**3.9459**	**3.9008**	**3.9098**	**0**	**23**	11.90	12.06
	4 1/8	**4.1250**	**4.0709**	**4.0258**	**4.0348**	**0**	**22**	12.67	12.84
4 1/4		**4.2500**	**4.1959**	**4.1508**	**4.1598**	**0**	**22**	13.47	13.65
	4 3/8	**4.3750**	**4.3209**	**4.2758**	**4.2848**	**0**	**21**	14.30	14.48
4 1/2		**4.5000**	**4.4459**	**4.4008**	**4.4098**	**0**	**21**	15.1	15.3
	4 5/8	**4.6250**	**4.5709**	**4.5258**	**4.5348**	**0**	**20**	16.0	16.2
4 3/4		**4.7500**	**4.6959**	**4.6508**	**4.6598**	**0**	**19**	16.9	17.1
	4 7/8	**4.8750**	**4.8209**	**4.7758**	**4.7848**	**0**	**19**	17.8	18.0
5		**5.0000**	**4.9459**	**4.9008**	**4.9098**	**0**	**18**	18.8	19.0
	5 1/8	**5.1250**	**5.0709**	**5.0258**	**5.0348**	**0**	**18**	19.8	20.0
5 1/4		**5.2500**	**5.1959**	**5.1508**	**5.1598**	**0**	**18**	20.8	21.0
	5 3/8	**5.3750**	**5.3209**	**5.2758**	**5.2848**	**0**	**17**	21.8	22.0
5 1/2		**5.5000**	**5.4459**	**5.4008**	**5.4098**	**0**	**17**	22.8	23.1
	5 5/8	**5.6250**	**5.5709**	**5.5258**	**5.5348**	**0**	**16**	23.9	24.1
5 3/4		**5.7500**	**5.6959**	**5.6508**	**5.6598**	**0**	**16**	25.0	25.2
	5 7/8	**5.8750**	**5.8209**	**5.7758**	**5.7848**	**0**	**16**	26.1	26.4
6		**6.0000**	**5.9459**	**5.9008**	**5.9098**	**0**	**15**	27.3	27.5

[a] British: Effective Diameter.

[b] See formula, pages 1502 and 1510.

[c] Design form for UNR threads. (See figure on page 1733.)

[d] Basic minor diameter.

[e] These are standard sizes of the UNC or UNF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5e. 16–Thread Series, 16–UN and 16–UNR—Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ, at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
3/8		**0.3750**	**0.3344**	**0.3005**	**0.3073**	**3**	**24**	0.0678	0.0775
7/16		**0.4375**	**0.3969**	**0.3630**	**0.3698**	**2**	**52**	0.0997	0.1114
1/2		**0.5000**	**0.4594**	**0.4255**	**0.4323**	**2**	**29**	0.1378	0.151
9/16		**0.5625**	**0.5219**	**0.4880**	**0.4948**	**2**	**11**	0.182	0.198
5/8		**0.6250**	**0.5844**	**0.5505**	**0.5573**	**1**	**57**	0.232	0.250
	11/16	**0.6875**	**0.6469**	**0.6130**	**0.6198**	**1**	**46**	0.289	0.308
3/4		**0.7500**	**0.7094**	**0.6755**	**0.6823**	**1**	**36**	0.351	0.373
	13/16	**0.8125**	**0.7719**	**0.7380**	**0.7448**	**1**	**29**	0.420	0.444
7/8		**0.8750**	**0.8344**	**0.8005**	**0.8073**	**1**	**22**	0.495	0.521
	15/16	**0.9375**	**0.8969**	**0.8630**	**0.8698**	**1**	**16**	0.576	0.604
1		**1.0000**	**0.9594**	**0.9255**	**0.9323**	**1**	**11**	0.663	0.693
	1 1/16	**1.0625**	**1.0219**	**0.9880**	**0.9948**	**1**	**7**	0.756	0.788
1 1/8		**1.1250**	**1.0844**	**1.0505**	**1.0573**	**1**	**3**	0.856	0.889
	1 3/16	**1.1875**	**1.1469**	**1.1130**	**1.1198**	**1**	**0**	0.961	0.997
1 1/4		**1.2500**	**1.2094**	**1.1755**	**1.1823**	**0**	**57**	1.073	1.111
	1 5/16	**1.3125**	**1.2719**	**1.2380**	**1.2448**	**0**	**54**	1.191	1.230
1 3/8		**1.3750**	**1.3344**	**1.3005**	**1.3073**	**0**	**51**	1.315	1.356
	1 7/16	**1.4375**	**1.3969**	**1.3630**	**1.3698**	**0**	**49**	1.445	1.488
1 1/2		**1.5000**	**1.4594**	**1.4255**	**1.4323**	**0**	**47**	1.58	1.63
	1 9/16	**1.5625**	**1.5219**	**1.4880**	**1.4948**	**0**	**45**	1.72	1.77
1 5/8		**1.6250**	**1.5844**	**1.5505**	**1.5573**	**0**	**43**	1.87	1.92
	1 11/16	**1.6875**	**1.6469**	**1.6130**	**1.6198**	**0**	**42**	2.03	2.08
1 3/4		**1.7500**	**1.7094**	**1.6755**	**1.6823**	**0**	**40**	2.19	2.24
	1 13/16	**1.8125**	**1.7719**	**1.7380**	**1.7448**	**0**	**39**	2.35	2.41
1 7/8		**1.8750**	**1.8344**	**1.8005**	**1.8073**	**0**	**37**	2.53	2.58
	1 15/16	**1.9375**	**1.8969**	**1.8630**	**1.8698**	**0**	**36**	2.71	2.77
2		**2.0000**	**1.9594**	**1.9255**	**1.9323**	**0**	**35**	2.89	2.95
	2 1/8	**2.1250**	**2.0844**	**2.0505**	**2.0573**	**0**	**33**	3.28	3.35
2 1/4		**2.2500**	**2.2094**	**2.1755**	**2.1823**	**0**	**31**	3.69	3.76
	2 3/8	**2.3750**	**2.3344**	**2.3005**	**2.3073**	**0**	**29**	4.13	4.21
2 1/2		**2.5000**	**2.4594**	**2.4255**	**2.4323**	**0**	**28**	4.60	4.67
	2 5/8	**2.6250**	**2.5844**	**2.5505**	**2.5573**	**0**	**26**	5.08	5.16
2 3/4		**2.7500**	**2.7094**	**2.6755**	**2.6823**	**0**	**25**	5.59	5.68
	2 7/8	**2.8750**	**2.8344**	**2.8005**	**2.8073**	**0**	**24**	6.13	6.22
3		**3.0000**	**2.9594**	**2.9255**	**2.9323**	**0**	**23**	6.69	6.78
	3 1/8	**3.1250**	**3.0844**	**3.0505**	**3.0573**	**0**	**22**	7.28	7.37
3 1/4		**3.2500**	**3.2094**	**3.1755**	**3.1823**	**0**	**21**	7.89	7.99
	3 3/8	**3.3750**	**3.3344**	**3.3005**	**3.3073**	**0**	**21**	8.52	8.63
3 1/2		**3.5000**	**3.4594**	**3.4255**	**3.4323**	**0**	**20**	9.18	9.29
	3 5/8	**3.6250**	**3.5844**	**3.5505**	**3.5573**	**0**	**19**	9.86	9.98
3 3/4		**3.7500**	**3.7094**	**3.6755**	**3.6823**	**0**	**18**	10.57	10.69
	3 7/8	**3.8750**	**3.8344**	**3.8005**	**3.8073**	**0**	**18**	11.30	11.43
4		**4.0000**	**3.9594**	**3.9255**	**3.9323**	**0**	**17**	12.06	12.19
	4 1/8	**4.1250**	**4.0844**	**4.0505**	**4.0573**	**0**	**17**	12.84	12.97
4 1/4		**4.2500**	**4.2094**	**4.1755**	**4.1823**	**0**	**16**	13.65	13.78
	4 3/8	**4.3750**	**4.3344**	**4.3005**	**4.3073**	**0**	**16**	14.48	14.62
4 1/2		**4.5000**	**4.4594**	**4.4255**	**4.4323**	**0**	**15**	15.34	15.5
	4 5/8	**4.6250**	**4.5844**	**4.5505**	**4.5573**	**0**	**15**	16.2	16.4
4 3/4		**4.7500**	**4.7094**	**4.6755**	**4.6823**	**0**	**15**	17.1	17.3
	4 7/8	**4.8750**	**4.8344**	**4.8005**	**4.8073**	**0**	**14**	18.0	18.2
5		**5.0000**	**4.9594**	**4.9255**	**4.9323**	**0**	**14**	19.0	19.2
	5 1/8	**5.1250**	**5.0844**	**5.0505**	**5.0573**	**0**	**13**	20.0	20.1
5 1/4		**5.2500**	**5.2094**	**5.1755**	**5.1823**	**0**	**13**	21.0	21.1
	5 3/8	**5.3750**	**5.3344**	**5.3005**	**5.3073**	**0**	**13**	22.0	22.2

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5e. ***(Continued)*** **16–Thread Series, 16–UN and 16–UNR—Basic Dimensions**

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
5 1/2		**5.5000**	**5.4594**	**5.4255**	**5.4323**	**0**	**13**	23.1	23.2
	5 5/8	**5.6250**	**5.5844**	**5.5505**	**5.5573**	**0**	**12**	24.1	24.3
5 3/4		**5.7500**	**5.7094**	**5.6755**	**5.6823**	**0**	**12**	25.2	25.4
	5 7/8	**5.8750**	**5.8344**	**5.8005**	**5.8073**	**0**	**12**	26.4	26.5
6		**6.0000**	**5.9594**	**5.9255**	**5.9323**	**0**	**11**	27.5	27.7

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733).
[d] Basic minor diamter.
[e] These are standard sizes of the UNC or UNF Series.

Table 5f. 20–Thread Series, 20–UN and 20–UNR—Basic Dimensions

Sizes		Basic Major Dia.,D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angle λ at Basic P.D.		Area of Minor Dia. at $D - 2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
1/4[e]		**0.2500**	**0.2175**	**0.1905**	**0.1959**	**4**	**11**	0.0269	0.0318
5/16		**0.3125**	**0.2800**	**0.2530**	**0.2584**	**3**	**15**	0.0481	0.0547
3/8		**0.3750**	**0.3425**	**0.3155**	**0.3209**	**2**	**40**	0.0755	0.0836
7/16[e]		**0.4375**	**0.4050**	**0.3780**	**0.3834**	**2**	**15**	0.1090	0.1187
1/2[e]		**0.5000**	**0.4675**	**0.4405**	**0.4459**	**1**	**57**	0.1486	0.160
9/16		**0.5625**	**0.5300**	**0.5030**	**0.5084**	**1**	**43**	0.194	0.207
5/8		**0.6250**	**0.5925**	**0.5655**	**0.5709**	**1**	**32**	0.246	0.261
	11/16	**0.6875**	**0.6550**	**0.6280**	**0.6334**	**1**	**24**	0.304	0.320
3/4[e]		**0.7500**	**0.7175**	**0.6905**	**0.6959**	**1**	**16**	0.369	0.386
	13/16[e]	**0.8125**	**0.7800**	**0.7530**	**0.7584**	**1**	**10**	0.439	0.458
7/8		**0.8750**	**0.8425**	**0.8155**	**0.8209**	**1**	**5**	0.515	0.536
	15/16[e]	**0.9375**	**0.9050**	**0.8780**	**0.8834**	**1**	**0**	0.0.598	0.620
1[e]		**1.0000**	**0.9675**	**0.9405**	**0.9459**	**0**	**57**	0.687	0.711
	1 1/16	**1.0625**	**1.0300**	**1.0030**	**1.0084**	**0**	**53**	0.782	0.807
1 1/8		**1.1250**	**1.0925**	**1.0655**	**1.0709**	**0**	**50**	0.882	0.910
	1 3/16	**1.1875**	**1.1550**	**1.1280**	**1.1334**	**0**	**47**	0.990	1.018
1 1/14		**1.2500**	**1.2175**	**1.1905**	**1.1959**	**0**	**45**	1.103	1.133
	1 5/16	**1.3125**	**1.2800**	**1.2530**	**1.2584**	**0**	**43**	1.222	1.254
1 3/8		**1.3750**	**1.3425**	**1.3155**	**1.3209**	**0**	**41**	1.348	1.382
	1 7/16	**1.4375**	**1.4050**	**1.3780**	**1.3834**	**0**	**39**	1.479	1.51
1 1/2		**1.5000**	**1.4675**	**1.4405**	**1.4459**	**0**	**37**	1.62	1.65
	1 9/16	**1.5625**	**1.5300**	**1.5030**	**1.5084**	**0**	**36**	1.76	1.80
1 5/8		**1.6250**	**1.5925**	**1.5655**	**1.5709**	**0**	**34**	1.91	1.95
	1 11/16	**1.6875**	**1.6550**	**1.6280**	**1.6334**	**0**	**33**	2.07	2.11
1 3/4		**1.7500**	**1.7175**	**1.6905**	**1.6959**	**0**	**32**	2.23	2.27
	1 13/16	**1.8125**	**1.7800**	**1.7530**	**1.7584**	**0**	**31**	2.40	2.44
1 7/8		**1.8750**	**1.8425**	**1.8155**	**1.8209**	**0**	**30**	2.57	2.62
	1 15/16	**1.9375**	**1.9050**	**1.8780**	**1.8834**	**0**	**29**	2.75	2.80
2		**2.0000**	**1.9675**	**1.9405**	**1.9459**	**0**	**28**	2.94	2.99
	2 1/8	**2.1250**	**2.0925**	**2.0655**	**2.0709**	**0**	**26**	3.33	3.39
2 1/4		**2.2500**	**2.2175**	**2.1905**	**2.1959**	**0**	**25**	3.75	3.81
	2 3/8	**2.3750**	**2.3425**	**2.3155**	**2.3209**	**0**	**23**	4.19	4.25
2 1/2		**2.5000**	**2.4675**	**2.4405**	**2.4459**	**0**	**22**	4.66	4.72
	2 5/8	**2.6250**	**2.5925**	**2.5655**	**2.5709**	**0**	**21**	5.15	5.21
2 3/4		**2.7500**	**2.7175**	**2.6905**	**2.6959**	**0**	**20**	5.66	5.73
	2 7/8	**2.8750**	**2.8425**	**2.8155**	**2.8209**	**0**	**19**	6.20	6.27
3		**3.0000**	**2.9675**	**2.9405**	**2.9459**	**0**	**18**	6.77	6.84

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] These are standard sizes of the UNC, UNF, or UNEF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5g. 28–Thread Series, 28–UN and 28–UNR — Basic Dimensions

Sizes		Basic Major Dia., D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angel λ at Basic P.D.		Area of Minor Dia. at D-$2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext. Thds.,[c] d_3 (Ref.)	Int. Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
	12 (0.216)[e]	**0.2160**	**0.1928**	**0.1734**	**0.1773**	**3**	**22**	0.0226	0.0258
1/4[e]		**0.2500**	**0.2268**	**0.2074**	**0.2113**	**2**	**52**	0.0326	0,0364
5/16		**0.3125**	**0.2893**	**0.2699**	**0.2738**	**2**	**15**	0.0556	0.0606
3/8		**0.3750**	**0.3518**	**0.3324**	**0.3363**	**1**	**51**	0.0848	0.0909
7/16[e]		**0.4375**	**0.4143**	**0.3949**	**0.3988**	**1**	**34**	0.1201	0.1274
1/2[e]		**0.5000**	**0.4768**	**0.4574**	**0.4613**	**1**	**22**	0.162	0.170
9/16		**0.5625**	**0.5393**	**0.5199**	**0.5238**	**1**	**12**	0.209	0.219
5/8		**0.6250**	**0.6018**	**0.5824**	**0.5863**	**1**	**5**	0.263	0.274
	11/16	**0.6875**	**0.6643**	**0.6449**	**0.6488**	**0**	**59**	0.323	0.335
3/4		**0.7500**	**0.7268**	**0.7074**	**0.7113**	**0**	**54**	0.389	0.402
	13/16	**0.8125**	**0.7893**	**0.7699**	**0.7738**	**0**	**50**	0.461	0.475
7/8		**0.8750**	**0.8518**	**0.8324**	**0.8363**	**0**	**46**	0.539	0.554
	15/16	**0.9375**	**0.9143**	**0.8949**	**0.8988**	**0**	**43**	0.624	0.640
1		**1.0000**	**0.9768**	**0.9574**	**0.9613**	**0**	**40**	0.714	0.732
	1 1/16	**1.0625**	**1.0393**	**1.0199**	**1.0238**	**0**	**38**	0.811	0.830
1 1/8		**1.1250**	**1.1018**	**1.0824**	**1.0863**	**0**	**35**	0.914	0.933
	1 3/16	**1.1875**	**1.1643**	**1.1449**	**1.1488**	**0**	**34**	1.023	1.044
1 1/4		**1.2500**	**1.2268**	**1.2074**	**1.2113**	**0**	**32**	1.138	1.160
	1 5/16	**1.3125**	**1.2893**	**1.2699**	**1.2738**	**0**	**30**	1.259	1.282
1 3/8		**1.3750**	**1.3518**	**1.3324**	**1.3363**	**0**	**29**	1.386	1.411
	1 7/16	**1.4375**	**1.4143**	**1.3949**	**1.3988**	**0**	**28**	1.52	1.55
1 1/2		**1.5000**	**1.4768**	**1.4574**	**1.4613**	**0**	**26**	1.66	1.69

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] These are standard sizes of the UNF or UNEF Series.

Table 5h. 32–Thread Series, 32–UN and 32–UNR — Basic Dimensions

Sizes		Basic Major Dia.,D	Basic Pitch Dia.,[a] D_2	Minor Diameter		Lead Angel λ at Basic P.D.		Area of Minor Dia. at D - $2h_b$	Tensile Stress Area[b]
Primary	Secondary			Ext.Thds.,[c] d_3 (Ref.)	Int.Thds.,[d] D_1				
Inches	Inches	Inches	Inches	Inches	Inches	Deg.	Min.	Sq. In.	Sq. In.
6 (0.138)[e]		**0.1380**	**0.1177**	**0.1008**	**0.1042**	**4**	**50**	0.00745	0.00909
8 (0.164)[e]		**0.1640**	**0.1437**	**0.1268**	**0.1302**	**3**	**58**	0.01196	0.0140
10 (0.190)[e]		**0.1900**	**0.1697**	**0.1528**	**0.1562**	**3**	**21**	0.01750	0.0200
	12 (0.216)[e]	**0.2160**	**0.1957**	**0.1788**	**0.1822**	**2**	**55**	0.0242	0.0270
1/4[e]		**0.2500**	**0.2297**	**0.2128**	**0.2162**	**2**	**29**	0.0344	0.0379
5/16[e]		**0.3125**	**0.2922**	**0.2753**	**0.2787**	**1**	**57**	0.0581	0.0625
3/8[e]		**0.3750**	**0.3547**	**0.3378**	**0.3412**	**1**	**36**	0.0878	0.0932
7/16		**0.4375**	**0.4172**	**0.4003**	**0.4037**	**1**	**22**	0.1237	0.1301
1/2		**0.5000**	**0.4797**	**0.4628**	**0.4662**	**1**	**11**	0.166	0.173
9/16		**0.5625**	**0.5422**	**0.5253**	**0.5287**	**1**	**3**	0.214	0.222
5/8		**0.6250**	**0.6047**	**0.5878**	**0.5912**	**0**	**57**	0.268	0.278
	11/16	**0.6875**	**0.6672**	**0.6503**	**0.6537**	**0**	**51**	0.329	0.339
3/4		**0.7500**	**0.7297**	**0.7128**	**0.7162**	**0**	**47**	0.395	0.407
	13/16	**0.8125**	**0.7922**	**0.7753**	**0.7787**	**0**	**43**	0.468	0.480
7/8		**0.8750**	**0.8547**	**0.8378**	**0.8412**	**0**	**40**	0.547	0.560
	15/16	**0.9375**	**0.9172**	**0.9003**	**0.9037**	**0**	**37**	0.632	0.646
1		**1.0000**	**0.9797**	**0.9628**	**0.9662**	**0**	**35**	0.723	0.738

[a] British: Effective Diameter.
[b] See formula, pages 1502 and 1510.
[c] Design form for UNR threads. (See figure on page 1733.)
[d] Basic minor diameter.
[e] These are standard sizes of the UNC, UNF, or UNEF Series.

Copyright 2004, Industrial Press, Inc., New York, NY

Thread Classes.— Thread classes are distinguished from each other by the amounts of tolerance and allowance. Classes identified by a numeral followed by the letters A and B are derived from certain Unified formulas (not shown here) in which the pitch diameter tolerances are based on increments of the basic major (nominal) diameter, the pitch, and the length of engagement. These formulas and the class identification or symbols apply to all of the Unified threads.

Classes 1A, 2A, and 3A apply to external threads only, and Classes 1B, 2B, and 3B apply to internal threads only. The disposition of the tolerances, allowances, and crest clearances for the various classes is illustrated on pages 1774 and 1774.

Classes 2A and 2B: Classes 2A and 2B are the most commonly used for general applications, including production of bolts, screws, nuts, and similar fasteners.

The maximum diameters of Class 2A (external) uncoated threads are less than basic by the amount of the allowance. The allowance minimizes galling and seizing in high-cycle wrench assembly, or it can be used to accommodate plated finishes or other coating. However, for threads with additive finish, the maximum diameters of Class 2A may be exceeded by the amount of the allowance, for example, the 2A maximum diameters apply to an unplated part or to a part before plating whereas the basic diameters (the 2A maximum diameter plus allowance) apply to a part after plating. The minimum diameters of Class 2B (internal) threads, whether or not plated or coated, are basic, affording no allowance or clearance in assembly at maximum metal limits.

Class 2AG: Certain applications require an allowance for rapid assembly to permit application of the proper lubricant or for residual growth due to high-temperature expansion. In these applications, when the thread is coated and the 2A allowance is not permitted to be consumed by such coating, the thread class symbol is qualified by G following the class symbol.

Classes 3A and 3B: Classes 3A and 3B may be used if closer tolerances are desired than those provided by Classes 2A and 2B. The maximum diameters of Class 3A (external) threads and the minimum diameters of Class 3B (internal) threads, whether or not plated or coated, are basic, affording no allowance or clearance for assembly of maximum metal components.

Classes 1A and 1B: Classes 1A and 1B threads replaced American National Class 1. These classes are intended for ordnance and other special uses. They are used on threaded components where quick and easy assembly is necessary and where a liberal allowance is required to permit ready assembly, even with slightly bruised or dirty threads.

Maximum diameters of Class 1A (external) threads are less than basic by the amount of the same allowance as applied to Class 2A. For the intended applications in American practice the allowance is not available for plating or coating. Where the thread is plated or coated, special provisions are necessary. The minimum diameters of Class 1B (internal) threads, whether or not plated or coated, are basic, affording no allowance or clearance for assembly with maximum metal external thread components having maximum diameters which are basic.

Coated 60-deg. Threads.— Although the Standard does not make recommendations for thicknesses of, or specify limits for coatings, it does outline certain principles that will aid mechanical interchangeability if followed whenever conditions permit.

To keep finished threads within the limits of size established in the Standard, external threads should not exceed basic size after plating and internal threads should not be below basic size after plating. This recommendation does not apply to threads coated by certain commonly used processes such as hot-dip galvanizing where it may not be required to maintain these limits.

Class 2A provides both a tolerance and an allowance. Many thread requirements call for coatings such as those deposited by electro-plating processes and, in general, the 2A allow-

Copyright 2004, Industrial Press, Inc., New York, NY



Limits of Size Showing Tolerances, Allowances (Neutral Space), and Crest Clearances for Unified Classes 1A, 2A, 1B, and 2B



Limits of Size Showing Tolerances and Crest Clearances for Unified Classes 3A and 3B and American National Classes 2 and 3

Copyright 2004, Industrial Press, Inc., New York, NY

ance provides adequate undercut for such coatings. There may be variations in thickness and symmetry of coating resulting from commercial processes but after plating the threads should be accepted by a basic Class 3A size GO gage and a Class 2A gage as a NOT-GO gage. Class 1A provides an allowance which is maintained for both coated and uncoated product, i.e., it is not available for coating.

Class 3A does not include an allowance so it is suggested that the limits of size before plating be reduced by the amount of the 2A allowance whenever that allowance is adequate.

No provision is made for overcutting internal threads as coatings on such threads are not generally required. Further, it is very difficult to deposit a significant thickness of coating on the flanks of internal threads. Where a specific thickness of coating is required on an internal thread, it is suggested that the thread be overcut so that the thread as coated will be accepted by a GO thread plug gage of basic size.

This Standard ASME/ANSI B1.1-1989 (R2001) specifies limits of size that pertain whether threads are coated or uncoated. Only in Class 2A threads is an allowance available to accommodate coatings. Thus, in all classes of internal threads and in all Class 1A, 2AG, and 3A external threads, limits of size must be adjusted to provide suitable provision for the desired coating.

For further information concerning dimensional accommodation of coating or plating for 60-degree threads, see Section 7, ASME/ANSI B1.1-1989 (R2001).

Screw Thread Selection — Combination of Classes.— Whenever possible, selection should be made from Table 2, Standard Series Unified Screw Threads, preference being given to the Coarse- and Fine- thread Series. If threads in the standard series do not meet the requirements of design, reference should be made to the selected combinations in Table 3. The third expedient is to compute the limits of size from the tolerance tables or tolerance increment tables given in the Standard. The fourth and last resort is calculation by the formulas given in the Standard.

The requirements for screw thread fits for specific applications depend on end use and can be met by specifying the proper combinations of thread classes for the components. For example, a Class 2A external thread may be used with a Class 1B, 2B, or 3B internal thread.

Pitch Diameter Tolerances, All Classes.— The pitch diameter tolerances in Table 3 for all classes of the UNC, UNF, 4-UN, 6-UN, and 8-UN series are based on a length of engagement equal to the basic major (nominal) diameter and are applicable for lengths of engagement up to 1½ diameters.

The pitch diameter tolerances used in Table 3 for all classes of the UNEF, 12-UN, 16-UN, 20-UN, 28-UN, and 32-UN series and the UNS series, are based on a length of engagement of 9 pitches and are applicable for lengths of engagement of from 5 to 15 pitches.

Screw Thread Designation.— The basic method of designating a screw thread is used where the standard tolerances or limits of size based on the standard length of engagement are applicable. The designation specifies in sequence the nominal size, number of threads per inch, thread series symbol, thread class symbol, and the gaging system number per ASME/ANSI B1.3M. The nominal size is the basic major diameter and is specified as the fractional diameter, screw number, or their decimal equivalent. Where decimal equivalents are used for size callout, they shall be interpreted as being nominal size designations only and shall have no dimensional significance beyond the fractional size or number designation. The symbol LH is placed after the thread class symbol to indicate a left-hand thread:

Examples:
¼–20 UNC-2A (21) or 0.250–20 UNC-2A (21)

Copyright 2004, Industrial Press, Inc., New York, NY

10–32 UNF-2A (22) or 0.190–32 UNF-2A (22)
7/16–20 UNRF-2A (23) or 0.4375–20 UNRF-2A (23)
2–12 UN-2A (21) or 2.000–12 UN-2A (21)
1/4–20 UNC-3A-LH (21) or 0.250–20 UNC-3A-LH (21)

For uncoated standard series threads these designations may optionally be supplemented by the addition of the pitch diameter limits of size.

Example:
1/4–20 UNC-2A (21)
PD 0.2164–0.2127 (Optional for uncoated threads)

Designating Coated Threads.— For coated (or plated) Class 2A external threads, the basic (max) major and basic (max) pitch diameters are given followed by the words AFTER COATING. The major and pitch diameter limits of size before coating are also given followed by the words BEFORE COATING.

Example: 3/4–10 UNC-2A (21)

[a]Major dia 0.7500 max PD 0.6850 max	}	AFTER COATING
[b]Major dia 0.7482–0.7353 PD 0.6832–0.6773	}	BEFORE COATING

[a] Major and PD values are equal to basic and correspond to those in Table 3 for Class 3A.
[b] Major and PD limits are those in Table 3 for Class 2A.

Certain applications require an allowance for rapid assembly, to permit application of a proper lubricant, or for residual growth due to high-temperature expansion. In such applications where the thread is to be coated and the 2A allowance is not permitted to be consumed by such coating, the thread class symbol is qualified by the addition of the letter G (symbol for allowance) following the class symbol, and the maximum major and maximum pitch diameters are reduced below basic size by the amount of the 2A allowance and followed by the words AFTER COATING. This arrangement ensures that the allowance is maintained. The major and pitch diameter limits of size before coating are also given followed by SPL and BEFORE COATING. For information concerning the designating of this and other special coating conditions reference should be made to American National Standard ASME/ANSI B1.1-1989 (R2001).

Designating UNS Threads.— UNS screw threads that have special combinations of diameter and pitch with tolerance to Unified formulation have the basic form designation set out first followed always by the limits of size.

Designating Multiple Start Threads.— If a screw thread is of multiple start, it is designated by specifying in sequence the nominal size, pitch (in decimals or threads per inch) and lead (in decimals or fractions).

Other Special Designations.— For other special designations including threads with modified limits of size or with special lengths of engagement, reference should be made to American National Standard ASME/ANSI B1.1-1989 (R2001).

Hole Sizes for Tapping.— Hole size limits for tapping Classes 1B, 2B, and 3B threads of various lengths of engagement are given in Table 2 on page 1925.

Internal Thread Minor Diameter Tolerances.— Internal thread minor diameter tolerances in Table 3 are based on a length of engagement equal to the nominal diameter. For general applications these tolerances are suitable for lengths of engagement up to 1½ diameters. However, some thread applications have lengths of engagement which are greater than 1½ diameters or less than the nominal diameter. For such applications it may be advantageous to increase or decrease the tolerance, respectively, as explained in the Tapping Section.

Copyright 2004, Industrial Press, Inc., New York, NY

American Standard for Unified Miniature Screw Threads

This American Standard (B1.10-1958, R1988) introduces a new series to be known as Unified Miniature Screw Threads and intended for general purpose fastening screws and similar uses in watches, instruments, and miniature mechanisms. Use of this series is recommended on all new products in place of the many improvised and unsystematized sizes now in existence which have never achieved broad acceptance nor recognition by standardization bodies. The series covers a diameter range from 0.30 to 1.40 millimeters (0.0118 to 0.0551 inch) and thus supplements the Unified and American thread series which begins at 0.060 inch (number 0 of the machine screw series). It comprises a total of fourteen sizes which, together with their respective pitches, are those endorsed by the American-British-Canadian Conference of April 1955 as the basis for a Unified standard among the inch-using countries, and coincide with the corresponding range of sizes in ISO (International Organization for Standardization) Recommendation No. 68. Additionally, it utilizes thread forms which are compatible in all significant respects with both the Unified and ISO basic thread profiles. Thus, threads in this series are interchangeable with the corresponding sizes in both the American-British-Canadian and ISO standardization programs.

Basic Form of Thread.— The basic profile by which the design forms of the threads covered by this standard are governed is shown in Table 1. The thread angle is 60 degrees and except for basic height and depth of engagement which are $0.52p$, instead of $0.54127p$, the basic profile for this thread standard is identical with the Unified and American basic thread form. The selection of 0.52 as the exact value of the coefficient for the height of this basic form is based on practical manufacturing considerations and a plan evolved to simplify calculations and achieve more precise agreement between the metric and inch dimensional tables.

Products made to this standard will be interchangeable with products made to other standards which allow a maximum depth of engagement (or combined addendum height) of $0.54127p$. The resulting difference is negligible (only 0.00025 inch for the coarsest pitch) and is completely offset by practical considerations in tapping, since internal thread heights exceeding $0.52p$ are avoided in these (Unified Miniature) small thread sizes in order to reduce excessive tap breakage.

Design Forms of Threads.— The design (maximum material) forms of the external and internal threads are shown in Table 2. These forms are derived from the basic profile shown in Table 1 by the application of clearances for the crests of the addenda at the roots of the mating dedendum forms. Basic and design form dimensions are given in Table 3.

Nominal Sizes: The thread sizes comprising this series and their respective pitches are shown in the first two columns of Table 5. The fourteen sizes shown in Table 5 have been systematically distributed to provide a uniformly proportioned selection over the entire range. They are separated alternately into two categories: The sizes shown in bold type are selections made in the interest of simplification and are those to which it is recommended that usage be confined wherever the circumstances of design permit. Where these sizes do not meet requirements the intermediate sizes shown in light type are available.

Table 1. Unified Miniature Screw Threads — Basic Thread Form



Formulas for Basic Thread Form Metric units (millimeters) are used in all formulas		
Thread Element	Symbol	Formula
Angle of thread	2α	60°
Half angle of thread	α	30°
Pitch of thread	p	
No. of threads per inch	n	$25.4/p$
Height of sharp V thread	H	0.86603p
Addendum of basic thread	h_{ab}	$0.32476p$
Height of basic thread	h_b	$0.52p$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Unified Miniature Screw Threads — Design Thread Form



Formulas for Design Thread Form (maximum material)[a]

External Thread			Internal Thread		
Thread Element	Symbol	Formula	Thread Element	Symbol	Formula
Addendum	h_{as}	0..32476p	Height of engagement	h_e	0.52p
Height	h_s	0.60p	Height of thread	h_n	0.556p
Flat at crest	F_{cs}	0.125p	Flat at crest	F_{cn}	0.27456p
Radius at root	r_{rs}	0.158p (approx)	Radius at root	r_{rn}	0.072p (approx)

[a] Metric units (millimeters) are used in all formulas.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Unified Miniature Screw Threads—Basic and Design Form Dimensions

Basic Thread Form					External Thread Design Form			Internal Thread Design Form		
Threads per inch n[a]	Pitch p	Height of Sharp V H = 0.86603p	Height h_s = 0.52p	Addendum h_{ab} = h_{as} = 0.32476p	Height h_s = 0.60p	Flat at Crest F_{cs} = 0.125p	Radius at Root r_{rs} = 0.158p	Height h_n = 0.556p	Flat at Crest F_{cn} = 0.27456p	Radius at Root r_{rn} = 0.072p
Millimeter Dimensions										
…	.080	.0693	.0416	.0260	.048	.0100	.0126	.0445	.0220	.0058
…	.090	.0779	.0468	.0292	.054	.0112	.0142	.0500	.0247	.0065
…	.100	.0866	.0520	.0325	.060	.0125	.0158	.0556	.0275	.0072
…	.125	.1083	.0650	.0406	.075	.0156	.0198	.0695	.0343	.0090
…	.150	.1299	.0780	.0487	.090	.0188	.0237	.0834	.0412	.0108
…	.175	.1516	.0910	.0568	.105	.0219	.0277	.0973	.0480	.0126
…	.200	.1732	.1040	.0650	.120	.0250	.0316	.1112	.0549	.0144
…	.225	.1949	.1170	.0731	.135	.0281	.0356	.1251	.0618	.0162
…	.250	.2165	.1300	.0812	.150	.0312	.0395	.1390	.0686	.0180
…	.300	.2598	.1560	.0974	.180	.0375	.0474	.1668	.0824	.0216
Inch Dimensions										
317½	.003150	.00273	.00164	.00102	.00189	.00039	.00050	.00175	.00086	.00023
282⅔	.003543	.00307	.00184	.00115	.00213	.00044	.00056	.00197	.00097	.00026
254	.003937	.00341	.00205	.00128	.00236	.00049	.00062	.00219	.00108	.00028
203⅕	.004921	.00426	.00256	.00160	.00295	.00062	.00078	.00274	.00135	.00035
169⅓	.005906	.00511	.00307	.00192	.00354	.00074	.00093	.00328	.00162	.00043
145⅐	.006890	.00597	.00358	.00224	.00413	.00086	.00109	.00383	.00189	.00050
127	.007874	.00682	.00409	.00256	.00472	.00098	.00124	.00438	.00216	.00057
112⅛	.008858	.00767	.00461	.00288	.00531	.00111	.00140	.00493	.00243	.00064
101⅗	.009843	.00852	.00512	.00320	.00591	.00123	.00156	.00547	.00270	.00071
84⅔	.011811	.01023	.00614	.00384	.00709	.00148	.00187	.00657	.00324	.00085

[a] In Tables 5 and 6 these values are shown rounded to the nearest whole number.

Table 4. Unified Miniature Screw Threads — Formulas for Basic and Design Dimensions and Tolerances

Formulas for Basic Dimensions	
D = Basic Major Diameter and Nominal Size in millimeters; p = Pitch in millimeters; E = Basic Pitch Diameter in millimeters = $D - 0.64952p$; and K = Basic Minor Diameter in millimeters = $D - 1.04p$	
Formulas for Design Dimensions (Maximum Material)	
External Thread	**Internal Thread**
D_s = Major Diameter = D	D_n = Major Diameter = $D + 0.072p$
E_s = Pitch Diameter = E	E_n = Pitch Diameter = E
K_s = Minor Diameter = $D - 1.20p$	K_n = Minor Diameter = K
Formulas for Tolerances on Design Dimensions[a]	
External Thread (–)	**Internal Thread (+)**
Major Diameter Tol., $0.12p + 0.006$	[b]Major Diameter Tol., $0.168p + 0.008$
Pitch Diameter Tol., $0.08p + 0.008$	Pitch Diameter Tol., $0.08p + 0.008$
[c]Minor Diameter Tol., $0.16p + 0.008$	Minor Diameter Tol., $0.32p + 0.012$

[a] These tolerances are based on lengths of engagement of $\frac{2}{3}D$ to $1\frac{1}{2}D$.

[b] This tolerance establishes the maximum limit of the major diameter of the internal thread. In practice, this limit is applied to the threading tool (tap) and not gaged on the product. Values for this tolerance are, therefore, not given in Table 5.

[c] This tolerance establishes the minimum limit of the minor diameter of the external thread. In practice, this limit is applied to the threading tool and only gaged on the product in confirming new tools. Values for this tolerance are, therefore, not given in Table 5.

Metric units (millimeters) apply in all formulas. Inch tolerances are not derived by direct conversion of the metric values. They are the differences between the rounded off limits of size in inch units.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Unified Miniature Screw Threads — Limits of Size and Tolerances

Size Designation[a]	Pitch	External Threads						Internal Threads						Lead Angle at Basic Pitch Diam.		Sectional Area at Minor Diam. at D − 1.28*p*
		Major Diam.		Pitch Diam.		Minor Diam.		Minor Diam.		Pitch Diam.		Major Diam.				
		Max[b]	Min	Max[b]	Min	Max[c]	Min[d]	Min[b]	Max	Min[b]	Max	Min[e]	Max[d]			
	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	deg	min	sq mm
0.30 UNM	**0.080**	**0.300**	**0.284**	**0.248**	**0.234**	**0.204**	**0.183**	**0.217**	**0.254**	**0.248**	**0.262**	**0.306**	**0.327**	**5**	**52**	**0.0307**
0.35 UNM	0.090	0.350	0.333	0.292	0.277	0.242	0.220	0.256	0.297	0.292	0.307	0.356	0.380	5	37	0.0433
0.40 UNM	**0.100**	**0.400**	**0.382**	**0.335**	**0.319**	**0.280**	**0.256**	**0.296**	**0.340**	**0.335**	**0.351**	**0.407**	**0.432**	**5**	**26**	**0.0581**
0.45 UNM	0.100	0.450	0.432	0.385	0.369	0.330	0.306	0.346	0.390	0.385	0.401	0.457	0.482	4	44	0.0814
0.50 UNM	**0.125**	**0.500**	**0.479**	**0.419**	**0.401**	**0.350**	**0.322**	**0.370**	**0.422**	**0.419**	**0.437**	**0.509**	**0.538**	**5**	**26**	**0.0908**
0.55 UNM	0.125	0.550	0.529	0.469	0.451	0.400	0.372	0.420	0.472	0.469	0.487	0.559	0.588	4	51	0.1195
0.60 UNM	**0.150**	**0.600**	**0.576**	**0.503**	**0.483**	**0.420**	**0.388**	**0.444**	**0.504**	**0.503**	**0.523**	**0.611**	**0.644**	**5**	**26**	**0.1307**
0.70 UNM	0.175	0.700	0.673	0.586	0.564	0.490	0.454	0.518	0.586	0.586	0.608	0.713	0.750	5	26	0.1780
0.80 UNM	**0.200**	**0.800**	**0.770**	**0.670**	**0.646**	**0.560**	**0.520**	**0.592**	**0.668**	**0.670**	**0.694**	**0.814**	**0.856**	**5**	**26**	**0.232**
0.90 UNM	0.225	0.900	0.867	0.754	0.728	0.630	0.586	0.666	0.750	0.754	0.780	0.916	0.962	5	26	0.294
1.00 UNM	**0.250**	**1.000**	**0.964**	**0.838**	**0.810**	**0.700**	**0.652**	**0.740**	**0.832**	**0.838**	**0.866**	**1.018**	**1.068**	**5**	**26**	**0.363**
1.10 UNM	0.250	1.100	1.064	0.938	0.910	0.800	0.752	0.840	0.932	0.938	0.966	1.118	1.168	4	51	0.478
1.20 UNM	**0.250**	**1.200**	**1.164**	**1.038**	**1.010**	**0.900**	**0.852**	**0.940**	**1.032**	**1.038**	**1.066**	**1.218**	**1.268**	**4**	**23**	**0.608**
1.40 UNM	0.300	1.400	1.358	1.205	1.173	1.040	0.984	1.088	1.196	1.205	1.237	1.422	1.480	4	32	0.811
	Thds. per in.	inch	inch	inch	inch	inch	inch	inch	inch	inch	inch	inch	inch	deg	min	sq in
0.30 UNM	**318**	**0.0118**	**0.0112**	**0.0098**	**0.0092**	**0.0080**	**0.0072**	**0.0085**	**0.0100**	**0.0098**	**0.0104**	**0.0120**	**0.0129**	**5**	**52**	**0.0000475**
0.35 UNM	282	0.0138	0.0131	0.0115	0.0109	0.0095	0.0086	0.0101	0.0117	0.0115	0.0121	0.0140	0.0149	5	37	0.0000671
0.40 UNM	**254**	**0.0157**	**0.0150**	**0.0132**	**0.0126**	**0.0110**	**0.0101**	**0.0117**	**0.0134**	**0.0132**	**0.0138**	**0.0160**	**0.0170**	**5**	**26**	**0.0000901**
0.45 UNM	254	0.0177	0.0170	0.0152	0.0145	0.0130	0.0120	0.0136	0.0154	0.0152	0.0158	0.0180	0.0190	4	44	0.0001262
0.50 UNM	**203**	**0.0197**	**0.0189**	**0.0165**	**0.0158**	**0.0138**	**0.0127**	**0.0146**	**0.0166**	**0.0165**	**0.0172**	**0.0200**	**0.0212**	**5**	**26**	**0.0001407**
0.55 UNM	203	0.0217	0.0208	0.0185	0.0177	0.0157	0.0146	0.0165	0.0186	0.0185	0.0192	0.0220	0.0231	4	51	0.0001852
0.60 UNM	**169**	**0.0236**	**0.0227**	**0.0198**	**0.0190**	**0.0165**	**0.0153**	**0.0175**	**0.0198**	**0.0198**	**0.0206**	**0.0240**	**0.0254**	**5**	**26**	**0.000203**
0.70 UNM	145	0.0276	0.0265	0.0231	0.0222	0.0193	0.0179	0.0204	0.0231	0.0231	0.0240	0.0281	0.0295	5	26	0.000276
0.80 UNM	**127**	**0.0315**	**0.0303**	**0.0264**	**0.0254**	**0.0220**	**0.0205**	**0.0233**	**0.0263**	**0.0264**	**0.0273**	**0.0321**	**0.0337**	**5**	**26**	**0.000360**
0.90 UNM	113	0.0354	0.0341	0.0297	0.0287	0.0248	0.0231	0.0262	0.0295	0.0297	0.0307	0.0361	0.0379	5	26	0.000456
1.00 UNM	**102**	**0.0394**	**0.0380**	**0.0330**	**0.0319**	**0.0276**	**0.0257**	**0.0291**	**0.0327**	**0.0330**	**0.0341**	**0.0401**	**0.0420**	**5**	**26**	**0.000563**
1.10 UNM	102	0.0433	0.0419	0.0369	0.0358	0.0315	0.0296	0.0331	0.0367	0.0369	0.0380	0.0440	0.0460	4	51	0.000741
1.20 UNM	**102**	**0.0472**	**0.0458**	**0.0409**	**0.0397**	**0.0354**	**0.0335**	**0.0370**	**0.0406**	**0.0409**	**0.0420**	**0.0480**	**0.0499**	**4**	**23**	**0.000943**
1.40 UNM	85	0.0551	0.0535	0.0474	0.0462	0.0409	0.0387	0.0428	0.0471	0.0474	0.0487	0.0560	0.0583	4	32	0.001257

[a] Sizes shown in bold type are preferred.

[b] This is also the basic dimension.

[c] This limit, in conjunction with root form shown in Table 2, is advocated for use when optical projection methods of gaging are employed. For mechanical gaging the minimum minor diameter of the internal thread is applied.

[d] This limit is provided for reference only. In practice, the form of the threading tool is relied upon for this limit.

[e] This limit is provided for reference only, and is not gaged. For gaging, the maximum major diameter of the external thread is applied.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Unified Miniature Screw Threads—Minimum Root Flats for External Threads

Pitch	No. of Threads Per Inch	Thread Height for Min. Flat at Root $0.64p$		Minimum Flat at Root $F_{rs} = 0.136p$	
mm		mm	Inch	mm	Inch
0.080	318	0.0512	0.00202	0.0109	0.00043
0.090	282	0.0576	0.00227	0.0122	0.00048
0.100	254	0.0640	0.00252	0.0136	0.00054
0.125	203	0.0800	0.00315	0.0170	0.00067
0.150	169	0.0960	0.00378	0.0204	0.00080
0.175	145	0.1120	0.00441	0.0238	0.00094
0.200	127	0.1280	0.00504	0.0272	0.00107
0.225	113	0.1440	0.00567	0.0306	0.00120
0.250	102	0.1600	0.00630	0.0340	0.00134
0.300	85	0.1920	0.00756	0.0408	0.00161



Limits of Size Showing Tolerances and Crest Clearances for UNM Threads

Copyright 2004, Industrial Press, Inc., New York, NY

Limits of Size: Formulas used to determine limits of size are given in Table 4; the limits of size are given in Table 5. The diagram on page 1781 illustrates the limits of size and Table 6 gives values for the minimum flat at the root of the external thread shown on the diagram.

Classes of Threads: The standard establishes one class of thread with zero allowance on all diameters. When coatings of a measurable thickness are required, they should be included within the maximum material limits of the threads since these limits apply to both coated and uncoated threads.

Hole Sizes for Tapping: Suggested hole sizes are given in the Tapping Section.

British Standard Unified Screw Threads of UNJ Basic Profile

This British Standard B.S. 4084: 1978 arises from a request originating from within the British aircraft industry and is based upon specifications for Unified screw threads and American military standard MIL-S-8879.

These UNJ threads, having an enlarged root radius, were introduced for applications requiring high fatigue strength where working stress levels are high, in order to minimize size and weight, as in aircraft engines, airframes, missiles, space vehicles and similar designs where size and weight are critical. To meet these requirements the root radius of external Unified threads is controlled between appreciably enlarged limits, the minor diameter of the mating internal threads being appropriately increased to insure the necessary clearance. The requirement for high strength is further met by restricting the tolerances for UNJ threads to the highest classes, Classes 3A and 3B, of Unified screw threads.

The standard, not described further here, contains both a coarse and a fine pitch series of threads.

Copyright 2004, Industrial Press, Inc., New York, NY

METRIC SCREW THREADS

American National Standard Metric Screw Threads M Profile

American National Standard ANSI/ASME B1.13M-1983 (R1995) describes a system of metric threads for general fastening purposes in mechanisms and structures. The standard is in basic agreement with ISO screw standards and resolutions, as of the date of publication, and features detailed information for diameter-pitch combinations selected as to preferred standard sizes. This Standard contains general metric standards for a 60-degree symmetrical screw thread with a basic ISO 68 designated profile.

Application Comparison with Inch Threads.— The metric M profile threads of tolerance class 6H/6g (see page 1790) are intended for metric applications where the inch class 2A/2B have been used. At the minimum material limits, the 6H/6g results in a looser fit than the 2A/2B. Tabular data are also provided for a tighter tolerance fit external thread of class 4g6g which is approximately equivalent to the inch class 3A but with an allowance applied. It may be noted that a 4H5H/4h6h fit is approximately equivalent to class 3A/3B fit in the inch system.

Interchangeability with Other System Threads.— Threads produced to this Standard ANSI/ASME B1.13M are fully interchangeable with threads conforming to other National Standards that are based on ISO 68 basic profile and ISO 965/1 tolerance practices.

Threads produced to this Standard should be mechanically interchangeable with those produced to ANSI B1.18M-1982 (R1987) "Metric Screw Threads for Commercial Mechanical Fasteners—Boundary Profile Defined," of the same size and tolerance class. However, there is a possibility that some parts may be accepted by conventional gages used for threads made to ANSI/ASME B1.13M and rejected by the Double-NOT-GO gages required for threads made to ANSI B1.18M.

Threads produced in accordance with M profile and MJ profile ANSI/ASME B1.21M design data will assemble with each other. However, external MJ threads will encounter interference on the root radii with internal M thread crests when both threads are at maximum material condition.

Definitions.— The following definitions apply to metric screw threads — M profile.

Allowance: The minimum nominal clearance between a prescribed dimension and its basic dimension. Allowance is not an ISO metric screw thread term but it is numerically equal to the absolute value of the ISO term *fundamental deviation*.

Basic Thread Profile: The cyclical outline in an axial plane of the permanently established boundary between the provinces of the external and internal threads. All deviations are with respect to this boundary. (See Figs. 1 and 5.)

Bolt Thread (External Thread): The term used in ISO metric thread standards to describe all external threads. All symbols associated with external threads are designated with lower case letters. This Standard uses the term external threads in accordance with United States practice.

Clearance: The difference between the size of the internal thread and the size of the external thread when the latter is smaller.

Crest Diameter: The major diameter of an external thread and the minor diameter of an internal thread.

Design Profiles: The maximum material profiles permitted for external and internal threads for a specified tolerance class. (See Figs. 2 and 3.)

Deviation: An ISO term for the algebraic difference between a given size (actual, measured, maximum, minimum, etc.) and the corresponding basic size. The term deviation does not necessarily indicate an error.

Copyright 2004, Industrial Press, Inc., New York, NY

Fit: The relationship existing between two corresponding external and internal threads with respect to the amount of clearance or interference which is present when they are assembled.

Fundamental Deviation: For Standard threads, the deviation (upper or lower) closer to the basic size. It is the upper deviation, *es*, for an external thread and the lower deviation, *EI*, for an internal thread. (See Fig. 5.)

Limiting Profiles: The limiting M profile for internal threads is shown in Fig. 6. The limiting M profile for external threads is shown in Fig. 7.

Lower Deviation: The algebraic difference between the minimum limit of size and the corresponding basic size.

Nut Thread (Internal Thread): A term used in ISO metric thread standards to describe all internal threads. All symbols associated with internal threads are designated with upper case letters. This Standard uses the term *internal thread* in accordance with United States practice.

Tolerance: The total amount of variation permitted for the size of a dimension. It is the difference between the maximum limit of size and the minimum limit of size (i.e., the algebraic difference between the upper deviation and the lower deviation). The tolerance is an absolute value without sign. Tolerance for threads is applied to the design size in the direction of the minimum material. On external threads the tolerance is applied negatively. On internal threads the tolerance is applied positively.

Tolerance Class: The combination of a tolerance position with a tolerance grade. It specifies the allowance (fundamental deviation) and tolerance for the pitch and major diameters of external threads and pitch and minor diameters of internal threads.

Tolerance Grade: A numerical symbol that designates the tolerances of crest diameters and pitch diameters applied to the design profiles.

Tolerance Position: A letter symbol that designates the position of the tolerance zone in relation to the basic size. This position provides the allowance (fundamental deviation).

Upper Deviation: The algebraic difference between the maximum limit of size and the corresponding basic size.

Basic M Profile.— The basic M thread profile also known as ISO 68 basic profile for metric screw threads is shown in Fig. 1 with associated dimensions listed in Table 3.

Design M Profile for Internal Thread.— The design M profile for the internal thread at maximum material condition is the basic ISO 68 profile. It is shown in Fig. 2 with associated thread data listed in Table 3.

Design M Profile for External Thread.— The design M profile for the external thread at the no allowance maximum material condition is the basic ISO 68 profile except where a rounded root is required. For the standard $0.125P$ minimum radius, the ISO 68 profile is modified at the root with a $0.17783H$ truncation blending into two arcs with radii of $0.125P$ tangent to the thread flanks as shown in Fig. 3 with associated thread data in Table 3.

M Crest and Root Form.— The form of crest at the major diameter of the external thread is flat, permitting corner rounding. The external thread is truncated $0.125H$ from a sharp crest. The form of the crest at the minor diameter of the internal thread is flat. It is truncated $0.25H$ from a sharp crest.

The crest and root tolerance zones at the major and minor diameters will permit rounded crest and root forms in both external and internal threads.

The root profile of the external thread must lie within the “section lined” tolerance zone shown in Fig. 4. For the rounded root thread, the root profile must lie within the “section lined” rounded root tolerance zone shown in Fig. 4. The profile must be a continuous, smoothly blended non-reversing curve, no part of which has a radius of less than $0.125P$, and which is tangential to the thread flank. The profile may comprise tangent flank arcs that are joined by a tangential flat at the root.

Copyright 2004, Industrial Press, Inc., New York, NY

The root profile of the internal thread must not be smaller than the basic profile. The maximum major diameter must not be sharp.

General Symbols.— The general symbols used to describe the metric screw thread forms are shown in Table 1.

Table 1. American National Standard Symbols for Metric Threads
ANSI/ASME B1.13M-1983 (R1995)

Symbol	Explanation
D	Major Diameter Internal Thread
D_1	Minor Diameter Internal Thread
D_2	Pitch Diameter Internal Thread
d	Major Diameter External Thread
d_1	Minor Diameter External Thread
d_2	Pitch Diameter External Thread
d_3	Rounded Form Minor Diameter External Thread
P	Pitch
r	External Thread Root Radius
T	Tolerance
T_{D1}, T_{D2}	Tolerances for D_1, D_2
T_d, T_{d2}	Tolerances for d, d_2
ES	Upper Deviation, Internal Thread [Equals the Allowance (Fundamental Deviation) Plus the Tolerance]. See Fig. 5.
EI	Lower Deviation, Internal Thread Allowance (Fundamental Deviation). See Fig. 5.
G, H	Letter Designations for Tolerance Positions for Lower Deviation, Internal Thread
g, h	Letter Designations for Tolerance Positions for Upper Deviation, External Thread
es	Upper Deviation, External Thread Allowance (Fundamental Deviation). See Fig. 5. In the ISO system *es* is always negative for an allowance fit or zero for no allowance.
ei	Lower Deviation, External Thread [Equals the Allowance (Fundamental Deviation) Plus the Tolerance]. See Fig. 5. In the ISO system *ei* is always negative for an allowance fit.
H	Height of Fundamental Triangle
LE	Length of Engagement
LH	Left Hand Thread

Standard M Profile Screw Thread Series.— The standard metric screw thread series for general purpose equipment's threaded components design and mechanical fasteners is a *coarse thread* series. Their diameter/pitch combinations are shown in Table 4. These diameter/pitch combinations are the preferred sizes and should be the first choice as applicable. Additional *fine pitch* diameter/pitch combinations are shown in Table 5.

Table 2. American National Standard General Purpose and Mechanical Fastener Coarse Pitch Metric Thread—M Profile Series ***ANSI/ASME B1.13M-1983 (R1995)***

Nom.Size	Pitch	Nom.Size	Pitch	Nom.Size	Pitch	Nom.Size	Pitch
1.6	0.35	6	1	22	2.5[a]	56	5.5
2	0.4	8	1.25	24	3	64	6
2.5	0.45	10	1.5	27	3[a]	72	6
3	0.5	12	1.75	30	3.5	80	6
3.5	0.6	14	2	36	4	90	6
4	0.7	16	2	42	4.5	100	6
5	0.8	20	2.5	48	5	…	…

[a] For high strength structural steel fasteners only.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Metric Thread — M Profile Data ***ANSI/ASME B1.13M-1983 (R1995)***

Pitch P	Truncation of Internal Thread Root and External Thread Crest $\frac{H}{8}$ 0.108253P	Addendum of Internal Thread and Truncation of Internal Thread $\frac{H}{4}$ 0.216506P	Dedendum of Internal Thread and Addendum External Thread $\frac{3}{8}H$ 0.324760P	Difference[a] $\frac{H}{2}$ 0.433013P	Height of Internal Thread and Depth of Thread Engagement $\frac{5}{8}H$ 0.541266P	Difference[b] 0.711325H 0.616025P	Twice the External Thread Addendum $\frac{3}{4}H$ 0.649519P	Difference[c] $\frac{11}{12}H$ 0.793857P	Height of Sharp V-Thread H 0.8660254P	Double Height of Internal Thread $\frac{5}{4}H$ 1.082532P
0.2	0.02165	0.04330	0.06495	0.08660	0.10825	0.12321	0.12990	0.15877	0.17321	0.21651
0.25	0.02706	0.05413	0.08119	0.10825	0.13532	0.15401	0.16238	0.19846	0.21651	0.27063
0.3	0.03248	0.06495	0.09743	0.12990	0.16238	0.18481	0.19486	0.23816	0.25981	0.32476
0.35	0.03789	0.07578	0.11367	0.15155	0.18944	0.21561	0.22733	0.27785	0.30311	0.37889
0.4	0.04330	0.08660	0.12990	0.17321	0.21651	0.24541	0.25981	0.31754	0.34641	0.43301
0.45	0.04871	0.09743	0.14614	0.19486	0.24357	0.27721	0.29228	0.35724	0.38971	0.48714
0.5	0.05413	0.10825	0.16238	0.21651	0.27063	0.30801	0.32476	0.39693	0.43301	0.64952
0.6	0.06495	0.12990	0.19486	0.25981	0.32476	0.36962	0.38971	0.47631	0.51962	0.64952
0.7	0.07578	0.15155	0.22733	0.30311	0.37889	0.43122	0.45466	0.55570	0.60622	0.75777
0.75	0.08119	0.16238	0.24357	0.32476	0.40595	0.46202	0.48714	0.59539	0.64952	0.81190
0.8	0.08660	0.17321	0.25981	0.34641	0.43301	0.49282	0.51962	0.63509	0.69282	0.86603
1	0.10825	0.21651	0.32476	0.43301	0.54127	0.61603	0.64952	0.79386	0.86603	1.08253
1.25	0.13532	0.27063	0.40595	0.54127	0.67658	0.77003	0.81190	0.99232	1.08253	1.35316
1.5	0.16238	0.32476	0.48714	0.64952	0.81190	0.92404	0.97428	1.19078	1.29904	1.62380
1.75	0.18944	0.37889	0.56833	0.75777	0.94722	1.07804	1.13666	1.38925	1.51554	1.89443
2	0.21651	0.43301	0.64952	0.86603	1.08253	1.23205	1.29904	1.58771	1.73205	2.16506
2.5	0.27063	0.54127	0.81190	1.08253	1.35316	1.54006	1.62380	1.98464	2.16506	2.70633
3	0.32476	0.64652	0.97428	1.29904	1.62380	1.84808	1.94856	2.38157	2.59808	3.24760
3.5	0.37889	0.75777	1.13666	1.51554	1.89443	2.15609	2.27332	2.77850	3.03109	3.78886
4	0.43301	0.86603	1.29904	1.73205	2.16506	2.46410	2.59808	3.17543	3.46410	4.33013
4.5	0.48714	0.97428	1.46142	1.94856	2.43570	2.77211	2.92284	3.57235	3.89711	4.87139
5	0.54127	1.08253	1.62380	2.16506	2.70633	3.08013	3.24760	3.96928	4.33013	5.41266
5.5	0.59539	1.19078	1.78618	2.38157	2.97696	3.38814	3.57235	4.36621	4.76314	5.95392
6	0.64952	1.29904	1.94856	2.59808	3.24760	3.69615	3.89711	4.76314	5.19615	6.49519
8	0.86603	1.73205	2.59808	3.46410	4.33013	4.92820	5.19615	6.35085	6.92820	8.66025

[a] Difference between max theoretical pitch diameter and max minor diameter of external thread and between min theoretical pitch diameter and min minor diameter of internal thread.

[b] Difference between min theoretical pitch diameter and min design minor diameter of external thread for 0.125P root radius.

[c] Difference between max major diameter and max theoretical pitch diameter of internal thread.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard General Purpose and Mechanical Fastener Coarse Pitch Metric Thread—M Profile Series ***ANSI/ASME B1.13M-1983 (R1995)***

Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch
1.6	0.35	6	1	22	2.5[a]	56	5.5
2	0.4	8	1.25	24	3	64	6
2.5	0.45	10	1.5	27	3[a]	72	6
3	0.5	12	1.75	30	3.5	80	6
3.5	0.6	14	2	36	4	90	6
4	0.7	16	2	42	4.5	100	6
5	0.8	20	2.5	48	5	…	…

[a] For high strength structural steel fasteners only.

All dimensions are in millimeters.

Table 5. American National Standard Fine Pitch Metric Thread—M Profile Series *ANSI/ASME B1.13M-1983 (R1995)*

Nom. Size	Pitch			Nom. Size	Pitch		Nom. Size	Pitch		Nom. Size	Pitch
8	1	…		27	…	2	56	…	2	105	2
10	0.75		1.25	30	1.5	2	60	1.5	…	110	2
12	1	1.5[a]	1.25	33	…	2	64	…	2	120	2
14	…		1.5	35	1.5	…	65	1.5	…	130	2
15	1	…		36	…	2	70	1.5	…	140	2
16	…		1.5	39	…	2	72	…	2	150	2
17	1	…		40	1.5	…	75	1.5	…	160	3
18	…		1.5	42	…	2	80	1.5	2	170	3
20	1		1.5	45	1.5	…	85	…	2	180	3
22	…		1.5	48	…	2	90	…	2	190	3
24	…		2	50	1.5	…	95	…	2	200	3
25	1.5	…		55	1.5	…	100	…	2		

[a] Only for wheel studs and nuts.

All dimensions are in millimeters.

Limits and Fits for Metric Screw Threads — M Profile.— The International (ISO) metric tolerance system is based on a system of limits and fits. The limits of the tolerances on the mating parts together with their allowances (fundamental deviations) determine the fit of the assembly. For simplicity the system is described for cylindrical parts (see *British Standard for Metric ISO Limits and Fits* starting on page 679) but in this Standard it is applied to screw threads. Holes are equivalent to internal threads and shafts to external threads.

Basic Size: This is the zero line or surface at assembly where the interface of the two mating parts have a common reference.*

Upper Deviation: This is the algebraic difference between the maximum limit of size and the basic size. It is designated by the French term "écart supérieur" (ES for internal and *es* for external threads).

Lower Deviation: This is the algebraic difference between the minimum limit of size and the basic size. It is designated by the French term "écart inférieur" (*EI* for internal and *ei* for external threads).

* Basic," when used to identify a particular dimension in this Standard, such as basic major diameter, refers to the h/H tolerance position (zero fundamental deviation) value.

Copyright 2004, Industrial Press, Inc., New York, NY

Fundamental Deviations (Allowances): These are the deviations which are closest to the basic size. In the accompanying figure they would be *EI* and *es*.

Fits: Fits are determined by the fundamental deviations assigned to the mating parts and may be positive or negative. The selected fits can be clearance, transition, or interference. To illustrate the fits schematically, a zero line is drawn to represent the basic size as shown in Fig. 5. By convention, the external thread lies below the zero line and the internal thread lies above it (except for interference fits). This makes the fundamental deviation negative for the external thread and equal to its upper deviation (*es*). The fundamental deviation is positive for the internal thread and equal to its lower deviation (*EI*).



$$H = \frac{\sqrt{3}}{2} \times P \quad = 0.866025P$$

$0.125H = 0.108253P \quad 0.250H = 0.216506P \quad 0.375H = 0.324760P \quad 0.625H = 0.541266P$

Fig. 1. Basic M Thread Profile (ISO 68 Basic Profile)



Fig. 2. Internal Thread Design M Profile with No Allowance (Fundamental Deviation) (Maximum Material Condition). For Dimensions see Table 3

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. External Thread Design M Profile with No Allowance (Fundamental Deviation) (Flanks at Maximum Material Condition). For Dimensions see Table 3



Fig. 4. M Profile, External Thread Root, Upper and Lower Limiting Profiles for $r_{min} = 0.125\,P$ and for Flat Root (Shown for Tolerance Position g)

Notes:

1) "Section lined" portions identify tolerance zone and unshaded portions identify allowance (fundamental deviation).

2) The upper limiting profile for rounded root is not a design profile; rather it indicates the limiting acceptable condition for the rounded root which will pass a GO thread gage.

3) $$\text{Max truncation} = \frac{H}{4} - r_{min}\left(1 - \cos\left[60° - \arccos\left(1 - \frac{T_{d2}}{4r_{min}}\right)\right]\right)$$

where H = Height of fundamental triangle
r_{min} = Minimum external thread root radius
T_{d2} = Tolerance on pitch diameter of external threasd

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Metric Tolerance System for Screw Threads

Tolerance: The tolerance is defined by a series of numerical grades. Each grade provides numerical values for the various nominal sizes corresponding to the standard tolerance for that grade.

In the schematic diagram the tolerance for the external thread is shown as negative. Thus the tolerance plus the fit define the lower deviation (*ei*). The tolerance for the mating internal thread is shown as positive. Thus the tolerance plus the fit defines the upper deviation (*ES*).

Tolerance Grade: This is indicated by a number. The system provides for a series of tolerance grades for each of the four screw thread parameters: minor diameter, internal thread, D_1; major diameter, external thread, d; pitch diameter, internal thread, D_2; and pitch diameter, external thread, d_2. The tolerance grades for this Standard ANSI B1.13M were selected from those given in ISO 965/1.

Dimension	Tolerance Grades	Table
D_1	4, 5, 6, 7, 8	Table 8
d	4, 6, 8	Table 9
D_2	4, 5, 6, 7, 8	Table 10
d_2	3, 4, 5, 6, 7, 8, 9	Table 11

Note: The underlined tolerance grades are used with normal length of thread engagement.

Tolerance Position: This position is the allowance (fundamental deviation) and is indicated by a letter. A capital letter is used for internal threads and a lower case letter for external threads. The system provides a series of tolerance positions for internal and external threads. The underlined letters are used in this Standard:

Internal threads	G, H	Table 6
External threads	e, f, g, h	Table 6

Designations of Tolerance Grade, Tolerance Position, and Tolerance Class: The tolerance grade is given first followed by the tolerance position, thus: 4g or 5H. To designate the tolerance class the grade and position of the pitch diameter is shown first followed by that for the major diameter in the case of the external thread or that for the minor diameter in the case of the internal thread, thus 4g6g for an external thread and 5H6H for an internal thread. If the two grades and positions are identical, it is not necessary to repeat the symbols, thus 4g, alone, stands for 4g4g and 5H, alone, stands for 5H5H.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Allowance (Fundamental Deviation) for Internal and External Metric Threads
ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)

Pitch P	Allowance (Fundamental Deviation)[a]					
	Internal Thread D_2, D_1		External Thread d, d_2			
	G	H	e	f	g	h
	EI	*EI*	*es*	*es*	*es*	*es*
0.2	+0.017	0	…	…	–0.017	0
0.25	+0.018	0	…	…	–0.018	0
0.3	+0.018	0	…	…	–0.018	0
0.35	+0.019	0	…	–0.034	–0.019	0
0.4	+0.019	0	…	–0.034	–0.019	0
0.45	+0.020	0	…	–0.035	–0.020	0
0.5	+0.020	0	–0.050	–0.036	–0.020	0
0.6	+0.021	0	–0.053	–0.036	–0.021	0
0.7	+0.022	0	–0.056	–0.038	–0.022	0
0.75	+0.022	0	–0.056	–0.038	–0.022	0
0.8	+0.024	0	–0.060	–0.038	–0.024	0
1	+0.026	0	–0.060	–0.040	–0.026	0
1.25	+0.028	0	–0.063	–0.042	–0.028	0
1.5	+0.032	0	–0.067	–0.045	–0.032	0
1.75	+0.034	0	–0.071	–0.048	–0.034	0
2	+0.038	0	–0.071	–0.052	–0.038	0
2.5	+0.042	0	–0.080	–0.058	–0.042	0
3	+0.048	0	–0.085	–0.063	–0.048	0
3.5	+0.053	0	–0.090	–0.070	–0.053	0
4	+0.060	0	–0.095	–0.075	–0.060	0
4.5	+0.063	0	–0.100	–0.080	–0.063	0
5	+0.071	0	–0.106	–0.085	–0.071	0
5.5	+0.075	0	–0.112	–0.090	–0.075	0
6	+0.080	0	–0.118	–0.095	–0.080	0

All dimensions are in millimeters.

[a] Allowance is the absolute value of fundamental deviation.

Lead and Flank Angle Tolerances: For acceptance of lead and flank angles of product screw threads, see Section 10 of ANSI/ASME B1.13M-1983 (R1995).

Short and Long Lengths of Thread Engagement when Gaged with Normal Length Contacts: For short lengths of thread engagement, LE, reduce the pitch diameter tolerance of the external thread by one tolerance grade number. For long lengths of thread engagement, LE, increase the allowance (fundamental deviation) at the pitch diameter of the external thread. Examples of tolerance classes required for normal, short, and long gage length contacts are given in the following table.

Normal LE	Short LE	Long LE
6g	5g6g	6e6g
4g6g	3g6g	4e6g
6h[a]	5h6h	6g6h
4h6h[a]	3h6h	4g6h

[a] Applies to maximum material functional size (GO thread gage) for plated 6g and 4g6g class threads, respectively.

For lengths of thread engagement classified as normal, short, and long, see Table 7.

Coated or Plated Threads: Coating is one or more applications of additive material to the threads, including dry-film lubricants, but excluding soft or liquid lubricants that are readily displaced in assembly or gaging. Plating is included as coating in the Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. American National Standard Length of Metric Thread Engagement
ISO 965/1 **and** *ANSI/ASME B1.13M-1983 (R1995)*

Basic Major Diameter d_{bsc}		Pitch	Length of Thread Engagement			
			Short LE	Normal LE		Long LE
Over	Up to and incl.	P	Up to and incl.	Over	Up to and incl.	Over
1.5	2.8	0.2	0.5	0.5	1.5	1.5
		0.25	0.6	0.6	1.9	1.9
		0.35	0.8	0.8	2.6	2.6
		0.4	1	1	3	3
		0.45	1.3	1.3	3.8	3.8
2.8	5.6	0.35	1	1	3	3
		0.5	1.5	1.5	4.5	4.5
		0.6	1.7	1.7	5	5
		0.7	2	2	6	6
		0.75	2.2	2.2	6.7	6.7
		0.8	2.5	2.5	7.5	7.5
5.6	11.2	0.75	2.4	2.4	7.1	7.1
		1	3	3	9	9
		1.25	4	4	12	12
		1.5	5	5	15	15
11.2	22.4	1	3.8	3.8	11	11
		1.25	4.5	4.5	13	13
		1.5	5.6	5.6	16	16
		1.75	6	6	18	18
		2	8	8	24	24
		2.5	10	10	30	30
22.4	45	1	4	4	12	12
		1.5	6.3	6.3	19	19
		2	8.5	8.5	25	25
		3	12	12	36	36
		3.5	15	15	45	45
		4	18	18	53	53
		4.5	21	21	63	63
45	90	1.5	7.5	7.5	22	22
		2	9.5	9.5	28	28
		3	15	15	45	45
		4	19	19	56	56
		5	24	24	71	71
		5.5	28	28	85	85
		6	32	32	95	95
90	180	2	12	12	36	36
		3	18	18	53	53
		4	24	24	71	71
		6	36	36	106	106
180	355	3	20	20	60	60
		4	26	26	80	80
		6	40	40	118	118

All dimensions are in millimeters.

Unless otherwise specified, size limits for standard external tolerance classes 6g and 4g6g apply prior to coating. The external thread allowance may thus be used to accommodate the coating thickness on coated parts, provided that the maximum coating thickness is no more than one-quarter of the allowance. Thus, the thread after coating is subject to acceptance using a basic (tolerance position h) size GO thread gage and tolerance position g thread gage for either minimum material, LO, or NOT-GO. Where the external thread has no allowance or the allowance must be maintained after coating, and for standard internal

Copyright 2004, Industrial Press, Inc., New York, NY

threads, sufficient allowance must be provided prior to coating to ensure that finished product threads do not exceed the maximum material limits specified. For thread classes with tolerance position H or h, coating allowances in accordance with Table 6 for position G or g, respectively, should be applied wherever possible.

Dimensional Effect of Coating.— On a cylindrical surface, the effect of coating is to change the diameter by twice the coating thickness. On a 60-degree thread, however, since the coating thickness is measured perpendicular to the thread surface while the pitch diameter is measured perpendicular to the thread axis, the effect of a uniformly coated flank on the pitch diameter is to change it by four times the thickness of the coating on the flank.

External Thread with No Allowance for Coating: To determine gaging limits before coating for a uniformly coated thread, decrease: 1) maximum pitch diameter by four times maximum coating thickness; 2) minimum pitch diameter by four times minimum coating thickness; 3) maximum major diameter by two times maximum coating thickness; and

4) minimum major diameter by two times minimum coating thickness.

External Thread with Only Nominal or Minimum Thickness Coating: If no coating thickness tolerance is given, it is recommended that a tolerance of plus 50 per cent of the nominal or minimum thickness be assumed.

Then, to determine before coating gaging limits for a uniformly coated thread, decrease:

1) maximum pitch diameter by six times coating thickness; 2) minimum pitch diameter by four times coating thickness; 3) maximum major diameter by three times coating thickness; and 4) minimum major diameter by two times coating thickness.

Adjusted Size Limits: It should be noted that the before coating material limit tolerances are less than the tolerance after coating. This is because the coating tolerance consumes some of the product tolerance. In cases there may be insufficient pitch diameter tolerance available in the before coating condition so that additional adjustments and controls will be necessary.

Strength: On small threads (5 mm and smaller) there is a possibility that coating thickness adjustments will cause base material minimum material conditions which may significantly affect strength of externally threaded parts. Limitations on coating thickness or part redesign may then be necessary.

Internal Threads: Standard internal threads provide no allowance for coating thickness.

To determine before coating, gaging limits for a uniformly coated thread, increase:

1) minimum pitch diameter by four times maximum coating thickness, if specified, or by six times minimum or nominal coating thickness when a tolerance is not specified;

2) maximum pitch diameter by four times minimum or nominal coating thickness;

3) minimum minor diameter by two times maximum coating thickness, if specified, or by three times minimum or nominal coating thickness; and 4) maximum minor diameter by two times minimum or nominal coating thickness.

Other Considerations.— It is essential to review all possibilities adequately and consider limitations in the threading and coating production processes before finally deciding on the coating process and the allowance required to accommodate the coating. A no-allowance thread after coating must not transgress the basic profile and is, therefore, subject to acceptance using a basic (tolerance position H/h) size GO thread gage.

Formulas for M Profile Screw Thread Limiting Dimensions.— The limiting dimensions for M profile screw threads are calculated from the following formulas.

Copyright 2004, Industrial Press, Inc., New York, NY

Internal Threads:

Min major dia. = basic major dia. + *EI* (Table 6)

Min pitch dia. = basic major dia. – 0.649519*P* (Table 3) + *EI* for D_2 (Table 6)

Max pitch dia. = min pitch dia. + T_{D2} (Table 10)

Max major dia. = max pitch dia. + 0.793857*P* (Table 3)

Min minor dia. = min major dia. – 1.082532*P* (Table 3)

Max minor dia. = min minor dia. + T_{D1} (Table 8)

External Threads:

Max major dia. = basic major dia. – *es* (Table 6) (Note that *es* is an absolute value.)

Min major dia. = max major dia. – T_d (Table 9)

Max pitch dia. = basic major dia. – 0.649519*P* (Table 3) – *es* for d_2 (Table 6)

Min pitch dia. = max pitch dia. – T_{d2} (Table 11)

Max flat form minor dia. = max pitch dia. – 0.433013*P* (Table 3)

Max rounded root minor dia. = max pitch dia. – 2 × max trunc. (See Fig. 4)

Min rounded root minor dia. = min pitch dia. – 0.616025*P* (Table 3)

Min root radius = 0.125*P*

Table 8. ANSI Standard Minor Diameter Tolerances of Internal Metric Threads T_{D1} *ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)*

Pitch *P*	Tolerance Grade				
	4	5	6	7	8
0.2	0.038	…	…	…	…
0.25	0.045	0.056	…	…	…
0.3	0.053	0.067	0.085	…	…
0.35	0.063	0.080	0.100	…	…
0.4	0.071	0.090	0.112	…	…
0.45	0.080	0.100	0.125	…	…
0.5	0.090	0.112	0.140	0.180	…
0.6	0.100	0.125	0.160	0.200	…
0.7	0.112	0.140	0.180	0.224	…
0.75	0.118	0.150	0.190	0.236	…
0.8	0.125	0.160	0.200	0.250	0.315
1	0.150	0.190	0.236	0.300	0.375
1.25	0.170	0.212	0.265	0.335	0.425
1.5	0.190	0.236	0.300	0.375	0.475
1.75	0.212	0.265	0.335	0.425	0.530
2	0.236	0.300	0.375	0.475	0.600
2.5	0.280	0.355	0.450	0.560	0.710
3	0.315	0.400	0.500	0.630	0.800
3.5	0.355	0.450	0.560	0.710	0.900
4	0.375	0.475	0.600	0.750	0.950
4.5	0.425	0.530	0.670	0.850	1.060
5	0.450	0.560	0.710	0.900	1.120
5.5	0.475	0.600	0.750	0.950	1.180
6	0.500	0.630	0.800	1.000	1.250

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ANSI Standard Major Diameter Tolerances of External Metric Threads, T_d *ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)*

Pitch	Tolerance Grade			Pitch	Tolerance Grade		
P	4	6	8	*P*	4	6	8
0.2	0.036	0.056	…	1.25	0.132	0.212	0.335
0.25	0.042	0.067	…	1.5	0.150	0.236	0.375
0.3	0.048	0.075	…	1.75	0.170	0.265	0.425
0.35	0.053	0.085	…	2	0.180	0.280	0.450
0.4	0.060	0.095	…	2.5	0.212	0.335	0.530
0.45	0.063	0.100	…	3	0.236	0.375	0.600
0.5	0.067	0.106	…	3.5	0.265	0.425	0.670
0.6	0.080	0.125	…	4	0.300	0.475	0.750
0.7	0.090	0.140	…	4.5	0.315	0.500	0.800
0.75	0.090	0.140	…	5	0.335	0.530	0.850
0.8	0.095	0.150	0.236	5.5	0.355	0.560	0.900
1	0.112	0.180	0.280	6	0.375	0.600	0.950

All dimensions are in millimeters.

Table 10. ANSI Standard Pitch-Diameter Tolerances of Internal Metric Threads, T_{D2} *ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)*

Basic Major Diameter, *D*			Tolerance Grade				
Over	Up to and incl.	Pitch *P*	4	5	6	7	8
1.5	2.8	0.2	0.042	…	…	…	…
		0.25	0.048	0.060	…	…	…
		0.35	0.053	0.067	0.085	…	…
		0.4	0.056	0.071	0.090	…	…
		0.45	0.060	0.075	0.095	…	…
2.8	5.6	0.35	0.056	0.071	0.090	…	…
		0.5	0.063	0.080	0.100	0.125	…
		0.6	0.071	0.090	0.112	0.140	…
		0.7	0.075	0.095	0.118	0.150	…
		0.75	0.075	0.095	0.118	0.150	…
		0.8	0.080	0.100	0.125	0.160	0.200
5.6	11.2	0.75	0.085	0.106	0.132	0.170	…
		1	0.095	0.118	0.150	0.190	0.236
		1.25	0.100	0.125	0.160	0.200	0.250
		1.5	0.112	0.140	0.180	0.224	0.280
11.2	22.4	1	0.100	0.125	0.160	0.200	0.250
		1.25	0.112	0.140	0.180	0.224	0.280
		1.5	0.118	0.150	0.190	0.236	0.300
		1.75	0.125	0.160	0.200	0.250	0.315
		2	0.132	0.170	0.212	0.265	0.335
		2.5	0.140	0.180	0.224	0.280	0.355
22.4	45	1	0.106	0.132	0.170	0.212	…
		1.5	0.125	0.160	0.200	0.250	0.315
		2	0.140	0.180	0.224	0.280	0.355
		3	0.170	0.212	0.265	0.335	0.425
		3.5	0.180	0.224	0.280	0.355	0.450
		4	0.190	0.236	0.300	0.375	0.475
		4.5	0.200	0.250	0.315	0.400	0.500
45	90	1.5	0.132	0.170	0.212	0.265	0.335
		2	0.150	0.190	0.236	0.300	0.375
		3	0.180	0.224	0.280	0.355	0.450
		4	0.200	0.250	0.315	0.400	0.500
		5	0.212	0.265	0.335	0.425	0.530
		5.5	0.224	0.280	0.355	0.450	0.560
		6	0.236	0.300	0.375	0.475	0.600

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **ANSI Standard Pitch-Diameter Tolerances of Internal Metric Threads,** T_{D2} *ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)*

Basic Major Diameter, *D*		Pitch	Tolerance Grade				
Over	Up to and incl.	*P*	4	5	6	7	8
90	180	2	0.160	0.200	0.250	0.315	0.400
		3	0.190	0.236	0.300	0.375	0.475
		4	0.212	0.265	0.335	0.425	0.530
		6	0.250	0.315	0.400	0.500	0.630
180	355	3	0.212	0.265	0.335	0.425	0.530
		4	0.236	0.300	0.375	0.475	0.600
		6	0.265	0.335	0.425	0.530	0.670

All dimensions are in millimeters.

Table 11. ANSI Standard Pitch-Diameter Tolerances of External Metric Threads, T_{d2} *ISO 965/1 ANSI/ASME B1.13M-1983 (R1995)*

Basic Major Diameter, *d*		Pitch	Tolerance Grade						
Over	Up to and incl.	*P*	3	4	5	6	7	8	9
1.5	2.8	0.2	0.025	0.032	0.040	0.050	…	…	…
		0.25	0.028	0.036	0.045	0.056	…	…	…
		0.35	0.032	0.040	0.050	0.063	0.080	…	…
		0.4	0.034	0.042	0.053	0.067	0.085	…	…
		0.45	0.036	0.045	0.056	0.071	0.090	…	…
2.8	5.6	0.35	0.034	0.042	0.053	0.067	0.085	…	…
		0.5	0.038	0.048	0.060	0.075	0.095	…	…
		0.6	0.042	0.053	0.067	0.085	0.106	…	…
		0.7	0.045	0.056	0.071	0.090	0.112	…	…
		0.75	0.045	0.056	0.071	0.090	0.112	…	…
		0.8	0.048	0.060	0.075	0.095	0.118	0.150	0.190
5.6	11.2	0.75	0.050	0.063	0.080	0.100	0.125	…	…
		1	0.056	0.071	0.090	0.112	0.140	0.180	0.224
		1.25	0.060	0.075	0.095	0.118	0.150	0.190	0.236
		1.5	0.067	0.085	0.106	0.132	0.170	0.212	0.265
11.2	22.4	1	0.060	0.075	0.095	0.118	0.150	0.190	0.236
		1.25	0.067	0.085	0.106	0.132	0.170	0.212	0.265
		1.5	0.071	0.090	0.112	0.140	0.180	0.224	0.280
		1.75	0.075	0.095	0.118	0.150	0.190	0.236	0.300
		2	0.080	0.100	0.125	0.160	0.200	0.250	0.315
		2.5	0.085	0.106	0.132	0.170	0.212	0.265	0.335
22.4	45	1	0.063	0.080	0.100	0.125	0.160	0.200	0.250
		1.5	0.075	0.095	0.118	0.150	0.190	0.236	0.300
		2	0.085	0.106	0.132	0.170	0.212	0.265	0.335
		3	0.100	0.125	0.160	0.200	0.250	0.315	0.400
		3.5	0.106	0.132	0.170	0.212	0.265	0.335	0.425
		4	0.112	0.140	0.180	0.224	0.280	0.355	0.450
		4.5	0.118	0.150	0.190	0.236	0.300	0.375	0.475
45	90	1.5	0.080	0.100	0.125	0.160	0.200	0.250	0.315
		2	0.090	0.112	0.140	0.180	0.224	0.280	0.355
		3	0.106	0.132	0.170	0.212	0.265	0.335	0.425
		4	0.118	0.150	0.190	0.236	0.300	0.375	0.475
		5	0.125	0.160	0.200	0.250	0.315	0.400	0.500
		5.5	0.132	0.170	0.212	0.265	0.335	0.425	0.530
		6	0.140	0.180	0.224	0.280	0.355	0.450	0.560
90	180	2	0.095	0.118	0.150	0.190	0.236	0.300	0.375
		3	0.112	0.140	0.180	0.224	0.280	0.355	0.450
		4	0.125	0.160	0.200	0.250	0.315	0.400	0.500
		6	0.150	0.190	0.236	0.300	0.375	0.475	0.600
180	355	3	0.125	0.160	0.200	0.250	0.315	0.400	0.500
		4	0.140	0.180	0.224	0.280	0.355	0.450	0.560
		6	0.160	0.200	0.250	0.315	0.400	0.500	0.630

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Tolerance Grade Comparisons.— The approximate ratios of the tolerance grades shown in Tables 8, 9, 10, and 11 in terms of Grade 6 are as follows:

Minor Diameter Tolerance of Internal Thread: T_{D1} (Table 8): Grade 4 is 0.63 T_{D1} (6); Grade 5 is 0.8 T_{D1} (6); Grade 7 is 1.25 T_{D1} (6); and Grade 8 is 1.6 T_{D1} (6).

Pitch Diameter Tolerance of Internal Thread: T_{D2} (Table 10): Grade 4 is 0.85 T_{d2} (6); Grade 5 is 1.06 T_{d2} (6); Grade 6 is 1.32 T_{d2} (6); Grade 7 is 1.7 T_{d2} (6); and Grade 8 is 2.12 T_{d2} (6). It should be noted that these ratios are in terms of the Grade 6 pitch diameter tolerance for the external thread.

Major Diameter Tolerance of External Thread: T_d (Table 9): Grade 4 is 0.63 T_d (6); and Grade 8 is 1.6 T_d (6).

Pitch Diameter Tolerance of External Thread: T_{d2} (Table 11): Grade 3 is 0.5 T_{d2} (6); Grade 4 is 0.63 T_{d2} (6); Grade 5 is 0.8 T_{d2} (6); Grade 7 is 1.25 T_{d2} (6); Grade 8 is 1.6 T_{d2} (6); and Grade 9 is 2 T_{d2} (6).

Standard M Profile Screw Threads, Limits of Size.— The limiting M profile for internal threads is shown in Fig. 6 with associated dimensions for standard sizes in Table 12. The limiting M profiles for external threads are shown in Fig. 7 with associated dimensions for standard sizes in Table 13.

If the required values are not listed in these tables, they may be calculated using the data in Tables 3, 6, 7, 8, 9, 10, and 11 together with the preceding formulas. If the required data are not included in any of the tables listed above, reference should be made to Sections 6 and 9.3 of ANSI/ASME B1.13M, which gives design formulas.



Fig. 6. Internal Thread — Limiting M Profile. Tolerance Position H

*This dimension is used in the design of tools, etc. For internal threads it is not normally specified. Generally, major diameter acceptance is based on maximum material condition gaging.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. External Thread — Limiting M Profile. Tolerance Position g

Table 12. Internal Metric Thread - M Profile Limiting Dimensions, *ANSI/ASME B1.13M-1983 (R1995)*

Basic Thread Designation	Toler. Class	Minor Diameter D_1		Pitch Diameter D_2			Major Diameter D	
		Min	Max	Min	Max	Tol	Min	Max[a]
M1.6 × 0.35	6H	1.221	1.321	1.373	1.458	0.085	1.600	1.736
M2 × 0.4	6H	1.567	1.679	1.740	1.830	0.090	2.000	2.148
M2.5 × 0.45	6H	2.013	2.138	2.208	2.303	0.095	2.500	2.660
M3 × 0.5	6H	2.459	2.599	2.675	2.775	0.100	3.000	3.172
M3.5 × 0.6	6H	2.850	3.010	3.110	3.222	0.112	3.500	3.699
M4 × 0.7	6H	3.242	3.422	3.545	3.663	0.118	4.000	4.219
M5 × 0.8	6H	4.134	4.334	4.480	4.605	0.125	5.000	5.240
M6 × 1	6H	4.917	5.153	5.350	5.500	0.150	6.000	6.294
M8 × 1.25	6H	6.647	6.912	7.188	7.348	0.160	8.000	8.340
M8 × 1	6H	6.917	7.153	7.350	7.500	0.150	8.000	8.294
M10 × 1.5	6H	8.376	8.676	9.026	9.206	0.180	10.000	10.396
M10 × 1.25	6H	8.647	8.912	9.188	9.348	0.160	10.000	10.340
M10 × 0.75	6H	9.188	9.378	9.513	9.645	0.132	10.000	10.240
M12 × 1.75	6H	10.106	10.441	10.863	11.063	0.200	12.000	12.453
M12 × 1.5	6H	10.376	10.676	11.026	11.216	0.190	12.000	12.406
M12 × 1.25	6H	10.647	10.912	11.188	11.368	0.180	12.000	12.360
M12 × 1	6H	10.917	11.153	11.350	11.510	0.160	12.000	12.304
M14 × 2	6H	11.835	12.210	12.701	12.913	0.212	14.000	14.501
M14 × 1.5	6H	12.376	12.676	13.026	13.216	0.190	14.000	14.406
M15 × 1	6H	13.917	14.153	14.350	14.510	0.160	15.000	15.304
M16 × 2	6H	13.835	14.210	14.701	14.913	0.212	16.000	16.501
M16 × 1.5	6H	14.376	14.676	15.026	15.216	0.190	16.000	16.406
M17 × 1	6H	15.917	16.153	16.350	16.510	0.160	17.000	17.304
M18 × 1.5	6H	16.376	16.676	17.026	17.216	0.190	18.000	18.406
M20 × 2.5	6H	17.294	17.744	18.376	18.600	0.224	20.000	20.585
M20 × 1.5	6H	18.376	18.676	19.026	19.216	0.190	20.000	20.406
M20 × 1	6H	18.917	19.153	19.350	19.510	0.160	20.000	20.304

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Internal Metric Thread - M Profile Limiting Dimensions,** *ANSI/ASME B1.13M-1983 (R1995)*

Basic Thread Designation	Toler. Class	Minor Diameter D_1		Pitch Diameter D_2			Major Diameter D	
		Min	Max	Min	Max	Tol	Min	Max[a]
M22 × 2.5	6H	19.294	19.744	20.376	20.600	0.224	22.000	22.585
M22 × 1.5	6H	20.376	20.676	21.026	21.216	0.190	22.000	22.406
M24 × 3	6H	20.752	21.252	22.051	22.316	0.265	24.000	24.698
M24 × 2	6H	21.835	22.210	22.701	22.925	0.224	24.000	24.513
M25 × 1.5	6H	23.376	23.676	24.026	24.226	0.200	25.000	25.416
M27 × 3	6H	23.752	24.252	25.051	25.316	0.265	27.000	27.698
M27 × 2	6H	24.835	25.210	25.701	25.925	0.224	27.000	27.513
M30 × 3.5	6H	26.211	26.771	27.727	28.007	0.280	30.000	30.785
M30 × 2	6H	27.835	28.210	28.701	28.925	0.224	30.000	30.513
M30 × 1.5	6H	28.376	28.676	29.026	29.226	0.200	30.000	30.416
M33 × 2	6H	30.835	31.210	31.701	31.925	0.224	33.000	33.513
M35 × 1.5	6H	33.376	33.676	34.026	34.226	0.200	35.000	35.416
M36 × 4	6H	31.670	32.270	33.402	33.702	0.300	36.000	36.877
M36 × 2	6H	33.835	34.210	34.701	34.925	0.224	36.000	36.513
M39 × 2	6H	36.835	37.210	37.701	37.925	0.224	39.000	39.513
M40 × 1.5	6H	38.376	38.676	39.026	39.226	0.200	40.000	40.416
M42 × 4.5	6H	37.129	37.799	39.077	39.392	0.315	42.000	42.965
M42 × 2	6H	39.835	40.210	40.701	40.925	0.224	42.000	42.513
M45 × 1.5	6H	43.376	43.676	44.026	44.226	0.200	45.000	45.416
M48 × 5	6H	42.587	43.297	44.752	45.087	0.335	48.000	49.057
M48 × 2	6H	45.835	46.210	46.701	46.937	0.236	48.000	48.525
M50 × 1.5	6H	48.376	48.676	49.026	49.238	0.212	50.000	50.428
M55 × 1.5	6H	53.376	53.676	54.026	54.238	0.212	55.000	55.428
M56 × 5.5	6H	50.046	50.796	52.428	52.783	0.355	56.000	57.149
M56 × 2	6H	53.835	54.210	54.701	54.937	0.236	56.000	56.525
M60 × 1.5	6H	58.376	58.676	59.026	59.238	0.212	60.000	60.428
M64 × 6	6H	57.505	58.305	60.103	60.478	0.375	64.000	65.241
M64 × 2	6H	61.835	62.210	62.701	62.937	0.236	64.000	64.525
M65 × 1.5	6H	63.376	63.676	64.026	64.238	0.212	65.000	65.428
M70 × 1.5	6H	68.376	68.676	69.026	69.238	0.212	70.000	70.428
M72 × 6	6H	65.505	66.305	68.103	68.478	0.375	72.000	73.241
M72 × 2	6H	69.835	70.210	70.701	70.937	0.236	72.000	72.525
M75 × 1.5	6H	73.376	73.676	74.026	74.238	0.212	75.000	75.428
M80 × 6	6H	73.505	74.305	76.103	76.478	0.375	80.000	81.241
M80 × 2	6H	77.835	78.210	78.701	78.937	0.236	80.000	80.525
M80 × 1.5	6H	78.376	78.676	79.026	79.238	0.212	80.000	80.428
M85 × 2	6H	82.835	83.210	83.701	83.937	0.236	85.000	85.525
M90 × 6	6H	83.505	84.305	86.103	86.478	0.375	90.000	91.241
M90 × 2	6H	87.835	88.210	88.701	88.937	0.236	90.000	90.525
M95 × 2	6H	92.835	93.210	93.701	93.951	0.250	95.000	95.539
M100 × 6	6H	93.505	94.305	96.103	96.503	0.400	100.000	101.266
M100 × 2	6H	97.835	98.210	98.701	98.951	0.250	100.000	100.539
M105 × 2	6H	102.835	103.210	103.701	103.951	0.250	105.000	105.539
M110 × 2	6H	107.835	108.210	108.701	108.951	0.250	110.000	110.539
M120 × 2	6H	117.835	118.210	118.701	118.951	0.250	120.000	120.539
M130 × 2	6H	127.835	128.210	128.701	128.951	0.250	130.000	130.539
M140 × 2	6H	137.835	138.210	138.701	138.951	0.250	140.000	140.539
M150 × 2	6H	147.835	148.210	148.701	148.951	0.250	150.000	150.539
M160 × 3	6H	156.752	157.252	158.051	158.351	0.300	160.000	160.733
M170 × 3	6H	166.752	167.252	168.051	168.351	0.300	170.000	170.733
M180 × 3	6H	176.752	177.252	178.051	178.351	0.300	180.000	180.733
M190 × 3	6H	186.752	187.252	188.051	188.386	0.335	190.000	190.768
M200 × 3	6H	196.752	197.252	198.051	198.386	0.335	200.000	200.768

[a] This reference dimension is used in design of tools, etc., and is not normally specified. Generally, major diameter acceptance is based upon maximum material condition gaging.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. External Metric Thread—M Profile Limiting Dimensions *ANSI/ASME B1.13M-1983 (R1995)*

Basic Thread Desig.	Toler. Class	Allow. *es*[a]	Major Diam.[b] *d*		Pitch Diam.[b] d_2			Minor-Diam.,d_1[b]	Minor Diam.,d_3[c]
			Max	Min	Max	Min	Tol.	Max	Min
M1.6 × 0.35	6g	0.019	1.581	1.496	1.354	1.291	0.063	1.202	1.075
M1.6 × 0.35	4g6g	0.019	1.581	1.496	1.354	1.314	0.040	1.202	1.098
M2 × 0.4	6g	0.019	1.981	1.886	1.721	1.654	0.067	1.548	1.408
M2 × 0.4	4g6g	0.019	1.981	1.886	1.721	1.679	0.042	1.548	1.433
M2.5 × 0.45	6g	0.020	2.480	2.380	2.188	2.117	0.071	1.993	1.840
M2.5 × 0.45	4g6g	0.020	2.480	2.380	2.188	2.143	0.045	1.993	1.866
M3 × 0.5	6g	0.020	2.980	2.874	2.655	2.580	0.075	2.439	2.272
M3 × 0.5	4g6g	0.020	2.980	2.874	2.655	2.607	0.048	2.439	2.299
M3.5 × 0.6	6g	0.021	3.479	3.354	3.089	3.004	0.085	2.829	2.635
M3.5 × 0.6	4g6g	0.021	3.479	3.354	3.089	3.036	0.053	2.829	2.667
M4 × 0.7	6g	0.022	3.978	3.838	3.523	3.433	0.090	3.220	3.002
M4 × 0.7	4g6g	0.022	3.978	3.838	3.523	3.467	0.056	3.220	3.036
M5 × 0.8	6g	0.024	4.976	4.826	4.456	4.361	0.095	4.110	3.869
M5 × 0.8	4g6g	0.024	4.976	4.826	4.456	4.396	0.060	4.110	3.904
M6 × 1	6g	0.026	5.974	5.794	5.324	5.212	0.112	4.891	4.596
M6 × 1	4g6g	0.026	5.974	5.794	5.324	5.253	0.071	4.891	4.637
M8 × 1.25	6g	0.028	7.972	7.760	7.160	7.042	0.118	6.619	6.272
M8 × 1.25	4g6g	0.028	7.972	7.760	7.160	7.085	0.075	6.619	6.315
M8 × 1	6g	0.026	7.974	7.794	7.324	7.212	0.112	6.891	6.596
M8 × 1	4g6g	0.026	7.974	7.794	7.324	7.253	0.071	6.891	6.637
M10 × 1.5	6g	0.032	9.968	9.732	8.994	8.862	0.132	8.344	7.938
M10 × 1.5	4g6g	0.032	9.968	9.732	8.994	8.909	0.085	8.344	7.985
M10 × 1.25	6g	0.028	9.972	9.760	9.160	9.042	0.118	8.619	8.272
M10 × 1.25	4g6g	0.028	9.972	9.760	9.160	9.085	0.075	8.619	8.315
M10 × 0.75	6g	0.022	9.978	9.838	9.491	9.391	0.100	9.166	8.929
M10 × 0.75	4g6g	0.022	9.978	9.838	9.491	9.428	0.063	9.166	8.966
M12 × 1.75	6g	0.034	11.966	11.701	10.829	10.679	0.150	10.072	9.601
M12 × 1.75	4g6g	0.034	11.966	11.701	10.829	10.734	0.095	10.072	9.656
M12 × 1.5	6g	0.032	11.968	11.732	10.994	10.854	0.140	10.344	9.930
M12 × 1.25	6g	0.028	11.972	11.760	11.160	11.028	0.132	10.619	10.258
M12 × 1.25	4g6g	0.028	11.972	11.760	11.160	11.075	0.085	10.619	10.305
M12 × 1	6g	0.026	11.974	11.794	11.324	11.206	0.118	10.891	10.590
M12 × 1	4g6g	0.026	11.974	11.794	11.324	11.249	0.075	10.891	10.633
M14 × 2	6g	0.038	13.962	13.682	12.663	12.503	0.160	11.797	11.271
M14 × 2	4g6g	0.038	13.962	13.682	12.663	12.563	0.100	11.797	11.331
M14 × 1.5	6g	0.032	13.968	13.732	12.994	12.854	0.140	12.344	11.930
M14 × 1.5	4g6g	0.032	13.968	13.732	12.994	12.904	0.090	12.344	11.980
M15 × 1	6g	0.026	14.974	14.794	14.324	14.206	0.118	13.891	13.590
M15 × 1	4g6g	0.026	14.974	14.794	14.324	14.249	0.075	13.891	13.633
M16 × 2	6g	0.038	15.962	15.682	14.663	14.503	0.160	13.797	13.271
M16 × 2	4g6g	0.038	15.962	15.682	14.663	14.563	0.100	13.797	13.331
M16 × 1.5	6g	0.032	15.968	15.732	14.994	14.854	0.140	14.344	13.930
M16 × 1.5	4g6g	0.032	15.968	15.732	14.994	14.904	0.090	14.344	13.980
M17 × 1	6g	0.026	16.974	16.794	16.324	16.206	0.118	15.891	15.590
M17 × 1	4g6g	0.026	16.974	16.794	16.324	16.249	0.075	15.891	15.633
M18 × 1.5	6g	0.032	17.968	17.732	16.994	16.854	0.140	16.344	15.930
M18 × 1.5	4g6g	0.032	17.968	17.732	16.994	16.904	0.090	16.344	15.980
M20 × 2.5	6g	0.042	19.958	19.623	18.334	18.164	0.170	17.252	16.624
M20 × 2.5	4g6g	0.042	19.958	19.623	18.334	18.228	0.106	17.252	16.688
M20 × 1.5	6g	0.032	19.968	19.732	18.994	18.854	0.140	18.344	17.930
M20 × 1.5	4g6g	0.032	19.968	19.732	18.994	18.904	0.090	18.344	17.980
M20 × 1	6g	0.026	19.974	19.794	19.324	19.206	0.118	18.891	18.590
M20 × 1	4g6g	0.026	19.974	19.794	19.324	19.249	0.075	18.891	18.633
M22 × 2.5	6g	0.042	21.9587	21.623	20.334	20.164	0.170	19.252	18.624
M22 × 1.5	6g	0.032	21.968	21.732	20.994	20.854	0.140	20.344	19.930
M22 × 1.5	4g6g	0.032	21.968	21.732	20.994	20.904	0.090	20.344	19.980

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **External Metric Thread—M Profile Limiting Dimensions** *ANSI/ASME B1.13M-1983 (R1995)*

Basic Thread Desig.	Toler. Class	Allow. *es*[a]	Major Diam.[b] *d*		Pitch Diam.[b] d_2			Minor-Diam.,d_1[b]	Minor Diam.,d_3[c]
			Max	Min	Max	Min	Tol.	Max	Min
M24 × 3	6g	0.048	23.952	23.577	22.003	21.803	0.200	20.704	19.955
M24 × 3	4g6g	0.048	23.952	23.577	22.003	21.878	0.125	20.704	20.030
M24 × 2	6g	0.038	23.962	23.682	22.663	22.493	0.170	21.797	21.261
M24 × 2	4g6g	0.038	23.962	23.682	22.663	22.557	0.106	21.797	21.325
M25 × 1.5	6g	0.032	24.968	24.732	23.994	23.844	0.150	23.344	22.920
M25 × 1.5	4g6g	0.032	24.968	24.732	23.994	23.899	0.095	23.344	22.975
M27 × 3	6g	0.048	26.952	26.577	25.003	24.803	0.200	23.704	22.955
M27 × 2	6g	0.038	26.962	26.682	25.663	25.493	0.170	24.797	24.261
M27 × 2	4g6g	0.038	26.962	26.682	25.663	25.557	0.106	24.797	24.325
M30 × 3.5	6g	0.053	29.947	29.522	27.674	27.462	0.212	26.158	25.306
M30 × 3.5	4g6g	0.053	29.947	29.522	27.674	27.542	0.132	26.158	25.386
M30 × 2	6g	0.038	29.962	29.682	28.663	28.493	0.170	27.797	27.261
M30 × 2	4g6g	0.038	29.962	29.682	28.663	28.557	0.106	27.797	27.325
M30 × 1.5	6g	0.032	29.968	29.732	28.994	28.844	0.150	28.344	27.920
M30 × 1.5	4g6g	0.032	29.968	29.732	28.994	28.899	0.095	28.344	27.975
M33 × 2	6g	0.038	32.962	32.682	31.663	31.493	0.170	30.797	30.261
M33 × 2	4g6g	0.038	32.962	32.682	31.663	31.557	0.106	30.797	30.325
M35 × 1.5	6g	0.032	34.968	34.732	33.994	33.844	0.150	33.344	33.920
M36 × 4	6g	0.060	35.940	35.465	33.342	33.118	0.224	31.610	30.654
M36 × 4	4g6g	0.060	35.940	35.465	33.342	33.202	0.140	31.610	30.738
M36 × 2	6g	0.038	35.962	35.682	34.663	34.493	0.170	33.797	33.261
M36 × 2	4g6g	0.038	35.962	35.682	34.663	34.557	0.106	33.797	33.325
M39 × 2	6g	0.038	38.962	38.682	37.663	37.493	0.170	36.797	36.261
M39 × 2	4g6g	0.038	38.962	38.682	37.663	37.557	0.106	36.797	36.325
M40 × 1.5	6g	0.032	39.968	39.732	38.994	38.844	0.150	38.344	37.920
M40 × 1.5	4g6g	0.032	39.968	39.732	38.994	38.899	0.095	38.344	37.975
M42 × 4.5	6g	0.063	41.937	41.437	39.014	38.778	0.236	37.066	36.006
M42 × 4.5	4g6g	0.063	41.937	41.437	39.014	38.864	0.150	37.066	36.092
M42 × 2	6g	0.038	41.962	41.682	40.663	40.493	0.170	39.797	39.261
M42 × 2	4g6g	0.038	41.962	41.682	40.663	40.557	0.106	39.797	39.325
M45 × 1.5	6g	0.032	44.968	44.732	43.994	43.844	0.150	43.344	42.920
M45 × 1.5	4g6g	0.032	44.968	44.732	43.994	43.899	0.095	43.344	42.975
M48 × 5	6g	0.071	47.929	47.399	44.681	44.431	0.250	42.516	41.351
M48 × 5	4g6g	0.071	47.929	47.399	44.681	44.521	0.160	42.516	41.441
M48 × 2	6g	0.038	47.962	47.682	46.663	46.483	0.180	45.797	45.251
M48 × 2	4g6g	0.038	47.962	47.682	46.663	46.551	0.112	45.797	45.319
M50 × 1.5	6g	0.032	49.968	49.732	48.994	48.834	0.160	48.344	47.910
M50 × 1.5	4g6g	0.032	49.968	49.732	48.994	48.894	0.100	48.344	47.970
M55 × 1.5	6g	0.032	54.968	54.732	53.994	53.834	0.160	53.344	52.910
M55 × 1.5	4g6g	0.032	54.968	54.732	53.994	53.894	0.100	53.344	52.970
M56 × 5.5	6g	0.075	55.925	55.365	52.353	52.088	0.265	49.971	48.700
M56 × 5.5	4g6g	0.075	55.925	55.365	52.353	52.183	0.170	49.971	48.795
M56 × 2	6g	0.038	55.962	55.682	54.663	54.483	0.180	53.797	53.251
M56 × 2	4g6g	0.038	55.962	55.682	54.663	54.551	0.112	53.797	53.319
M60 × 1.5	6g	0.032	59.968	59.732	58.994	58.834	0.160	58.344	57.910
M60 × 1.5	4g6g	0.032	59.968	59.732	58.994	58.894	0.100	58.344	57.970
M64 × 6	6g	0.080	63.920	63.320	60.023	59.743	0.280	57.425	56.047
M64 × 6	4g6g	0.080	63.920	63.320	60.023	59.843	0.180	57.425	56.147
M64 × 2	6g	0.038	63.962	63.682	62.663	62.483	0.180	61.797	61.251
M64 × 2	4g6g	0.038	63.962	63.682	62.663	62.551	0.112	61.797	61.319
M65 × 1.5	6g	0.032	64.968	64.732	63.994	63.834	0.160	63.344	62.910
M65 × 1.5	4g6g	0.032	64.968	64.732	63.994	63.894	0.100	63.344	62.970
M70 × 1.5	6g	0.032	69.968	69.732	68.994	68.834	0.160	68.344	67.910
M70 × 1.5	4g6g	0.032	69.968	69.732	68.994	68.894	0.100	68.344	67.970
M72 × 6	6g	0.080	71.920	71.320	68.023	67.743	0.280	65.425	64.047
M72 × 6	4g6g	0.080	71.920	71.320	68.023	67.843	0.180	65.425	64.147

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. ***(Continued)*** **External Metric Thread—M Profile Limiting Dimensions** *ANSI/ASME B1.13M-1983 (R1995)*

Basic Thread Desig.	Toler. Class	Allow. *es*[a]	Major Diam.[b] *d*		Pitch Diam.[b] d_2			Minor-Diam.,d_1[b]	Minor Diam.,d_3[c]
			Max	Min	Max	Min	Tol.	Max	Min
M72 × 2	6g	0.038	71.962	71.682	70.663	70.483	0.180	69.797	69.251
M72 × 2	4g6g	0.038	71.962	71.682	70.663	70.551	0.112	69.797	69.319
M75 × 1.5	6g	0.032	74.968	74.732	73.994	73.834	0.160	73.344	72.910
M75 × 1.5	4g6g	0.032	74.968	74.732	73.994	73.894	0.100	73.344	72.970
M80 × 6	6g	0.080	79.920	79.320	76.023	75.743	0.280	73.425	72.047
M80 × 6	4g6g	0.080	79.920	79.320	76.023	75.843	0.180	73.425	72.147
M80 × 2	6g	0.038	79.962	79.682	78.663	78.483	0.180	77.797	77.251
M80 × 2	4g6g	0.038	79.962	79.682	78.663	78.551	0.112	77.797	77.319
M80 × 1.5	6g	0.032	79.968	79.732	78.994	78.834	0.160	78.344	77.910
M80 × 1.5	4g6g	0.032	79.968	79.732	78.994	78.894	0.100	78.334	77.970
M85 × 2	6g	0.038	84.962	84.682	83.663	83.483	0.180	82.797	82.251
M85 × 2	4g6g	0.038	84.962	84.682	83.663	83.551	0.112	82.797	82.319
M90 × 6	6g	0.080	89.920	89.320	86.023	85.743	0.280	83.425	82.047
M90 × 6	4g6g	0.080	89.920	89.320	86.023	85.843	0.180	83.425	82.147
M90 × 2	6g	0.038	89.962	89.682	88.663	88.483	0.180	87.797	87.251
M90 × 2	4g6g	0.038	89.962	89.682	88.663	88.551	0.112	87.797	87.319
M95 × 2	6g	0.038	94.962	94.682	93.663	93.473	0.190	92.797	92.241
M95 × 2	4g6g	0.038	94.962	94.682	93.663	93.545	0.118	92.797	92.313
M100 × 6	6g	0.080	99.920	99.320	96.023	95.723	0.300	93.425	92.027
M100 × 6	4g6g	0.080	99.920	99.320	96.023	95.833	0.190	93.425	92.137
M100 × 2	6g	0.038	99.962	99.682	98.663	98.473	0.190	97.797	97.241
M100 × 2	4g6g	0.038	99.962	99.682	98.663	98.545	0.118	97.797	97.313
M105 × 2	6g	0.038	104.962	104.682	103.663	103.473	0.190	102.797	102.241
M105 × 2	4g6g	0.038	104.962	104.682	103.663	103.545	0.118	102.797	102.313
M110 × 2	6g	0.038	109.962	109.682	108.663	108.473	0.190	107.797	107.241
M110 × 2	4g6g	0.038	109.962	109.682	108.663	108.545	0.118	107.797	107.313
M120 × 2	6g	0.038	119.962	119.682	118.663	118.473	0.190	117.797	117.241
M120 × 2	4g6g	0.038	119.962	119.682	118.663	118.545	0.118	117.797	117.313
M130 × 2	6g	0.038	129.962	129.682	128.663	128.473	0.190	127.797	127.241
M130 × 2	4g6g	0.038	139.962	139.682	138.663	138.545	0.118	137.797	137.313
M140 × 2	6g	0.038	139.962	139.682	138.663	138.473	0.190	137.797	137.241
M140 × 2	4g6g	0.038	139.962	139.682	138.663	138.545	0.118	137.797	137.313
M150 × 2	6g	0.038	149.962	149.682	148.663	148.473	0.190	147.797	147.241
M150 × 2	4g6g	0.038	149.962	149.682	148.663	148.545	0.118	147.797	147.313
M160 × 3	6g	0.048	159.952	159.577	158.003	157.779	0.224	156.704	155.931
M160 × 3	4g6g	0.048	159.952	159.577	158.003	157.863	0.140	156.704	156.015
M170 × 3	6g	0.048	169.952	169.577	168.003	167.779	0.224	166.704	165.931
M170 × 3	4g6g	0.048	169.952	169.577	168.003	167.863	0.140	166.704	166.015
M180 × 3	6g	0.048	179.952	179.577	178.003	177.779	0.224	176.704	175.931
M180 × 3	4g6g	0.048	179.952	179.577	178.003	177.863	0.140	176.704	176.015
M190 × 3	6g	0.048	189.952	189.577	188.003	187.753	0.250	186.704	185.905
M190 × 3	4g6g	0.048	189.952	189.577	188.003	187.843	0.160	186.704	185.995
M200 × 3	6g	0.048	199.952	199.577	198.003	197.753	0.250	196.704	195.905
M200 × 3	4g6g	0.048	199.952	199.577	198.003	197.843	0.160	196.704	195.995

[a] *es* is an absolute value.

[b] (Flat form) For screw threads at maximum limits of tolerance position *h*, add the absolute value *es* to the maximum diameters required. For maximum major diameter this value is the basic thread size listed in Table 12 as Minimum Major Diameter (D_{min}; for maximum pitch diameter this value is the same as listed in Table 12 as Minimum Pitch Diameter ($D_{2\,min}$); and for maximum minor diameter this value is the same as listed in Table 12 as Minimum Minor Diameter ($D_{1\,min}$).

[c] (Rounded form) This reference dimension is used in the design of tools, etc. In dimensioning external threads it is not normally specified. Generally minor diameter acceptance is based upon maximum material condition gaging.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Metric Screw Thread Designations.— Metric screw threads are identified by the letter (M) for the thread form profile, followed by the nominal diameter size and the pitch expressed in millimeters, separated by the sign (×) and followed by the tolerance class separated by a dash (–) from the pitch.

The simplified international practice for designating coarse pitch M profile metric screw threads is to leave off the pitch. Thus a M14 × 2 thread is designated just M14. However, to prevent misunderstanding, it is mandatory to use the value for pitch in all designations.

Thread acceptability gaging system requirements of ANSI B1.3M may be added to the thread size designation as noted in the examples (numbers in parentheses) or as specified in pertinent documentation, such as the drawing or procurement document.

Unless otherwise specified in the designation, the screw thread is right hand.

Examples: External thread of M profile, right hand: M6 × 1 – 4g6g (22)
Internal thread of M profile, right hand: M6 × 1 – 5H6H (21)

Designation of Left Hand Thread: When a left hand thread is specified, the tolerance class designation is followed by a dash and LH.

Example: M6 × 1 – 5H6H – LH (23)

Designation for Identical Tolerance Classes: If the two tolerance class designations for a thread are identical, it is not necessary to repeat the symbols.

Example: M6 × 1 – 6H (21)

Designation Using All Capital Letters: When computer and teletype thread designations use all capital letters, the external or internal thread may need further identification. Thus the tolerance class is followed by the abbreviations EXT or INT in capital letters.

Examples: M6 × 1 – 4G6G EXT; M6 × 1 – 6H INT

Designation for Thread Fit: A fit between mating threads is indicated by the internal thread tolerance class followed by the external thread tolerance class and separated by a slash.

Examples: M6 × 1 – 6H/6g; M6 × 1 – 6H/4g6g

Designation for Rounded Root External Thread: The M profile with a minimum root radius of 0.125P on the external thread is desirable for all threads but is mandatory for threaded mechanical fasteners of ISO 898/I property class 8.8 (minimum tensile strength 800 MPa) and stronger. No special designation is required for these threads. Other parts requiring a 0.125P root radius must have that radius specified.

When a special rounded root is required, its external thread designation is suffixed by the minimum root radius value in millimeters and the letter R.

Example: M42 × 4.5 – 6g – 0.63R

Designation of Threads Having Modified Crests: Where the limits of size of the major diameter of an external thread or the minor diameter of an internal thread are modified, the thread designation is suffixed by the letters MOD followed by the modified diameter limits.

Examples:

External thread M profile, major diameter reduced 0.075 mm. M6 × 1 – 4h6h MOD Major dia = 5.745 – 5.925 MOD	Internal thread M profile, minor diameter increased 0.075 mm. M6 × 1 – 4H5H MOD Minor dia = 5.101 – 5.291 MOD

Designation of Special Threads: Special diameter-pitch threads developed in accordance with this Standard ANSI/ASME B1.13M are identified by the letters SPL following the tolerance class. The limits of size for the major diameter, pitch diameter, and minor diameter are specified below this designation.

Copyright 2004, Industrial Press, Inc., New York, NY

Examples:

External thread	Internal thread
M6.5 × 1 – 4h6h – SPL (22)	M6.5 × 1 – 4H5H – SPL (23)
Major dia = 6.320 – 6.500	Major dia = 6.500 min
Pitch dia = 5.779 – 5.850	Pitch dia = 5.850 – 5.945
Minor dia = 5.163 – 5.386	Minor dia = 5.417 – 5.607

Designation of Multiple Start Threads: When a thread is required with a multiple start, it is designated by specifying sequentially: M for metric thread, nominal diameter size, × L for lead, lead value, dash, P for pitch, pitch value, dash, tolerance class, parenthesis, script number of starts, and the word starts, close parenthesis.

Examples: M16 × L4 – P2 – 4h6h (TWO STARTS)
M14 × L6 – P2 – 6H (THREE STARTS)

Designation of Coated or Plated Threads: In designating coated or plated M threads the tolerance class should be specified as after coating or after plating. If no designation of after coating or after plating is specified, the tolerance class applies before coating or plating in accordance with ISO practice. After plating, the thread must not transgress the maximum material limits for the tolerance position H/h.

Examples: M6 × 1 – 6h AFTER COATING or AFTER PLATING
M6 × 1 – 6g AFTER COATING or AFTER PLATING

Where the tolerance position G/g is insufficient relief for the application to hold the threads within product limits, the coating or plating allowance may be specified as the maximum and minimum limits of size for minor and pitch diameters of internal threads or major and pitch diameters for external threads before coating or plating.

Example: Allowance on external thread M profile based on 0.010 mm minimum coating thickness.

M6 × 1 – 4h6h – AFTER COATING
BEFORE COATING
Major dia = 5.780 – 5.940
Pitch dia = 5.239 – 5.290

Metric Screw Threads—MJ Profile

The MJ screw thread is intended for aerospace metric threaded parts and for other highly stressed applications requiring high temperature or high fatigue strength, or for "no allowance" applications. The MJ profile thread is a hard metric version similar to the UNJ inch standards, ANSI/ASME B1.15 and MIL-S-8879. The MJ profile thread has a 0.15011*P* to 0.180424*P* controlled root radius in the external thread and the internal thread minor diameter truncated to accommodate the external thread maximum root radius.

First issued in 1978, the American National Standard ANSI/ASME B1.21M-1997 establishes the basic triangular profile for the MJ form of thread; gives a system of designations; lists the standard series of diameter-pitch combinations for diameters from 1.6 to 200 mm; and specifies limiting dimensions and tolerances. Changes included in the 1997 revision are the addition of tolerance class 4G6G and 4G5G/4g6g comparable to ANSI/ASME B1.15 (UNJ thread); the addition of tolerance class 6H/6g comparable to ANSI/ASME B1.13M; and changes in the rounding proceedure as set forth in ANSI/ASME B1.30M.

Diameter-Pitch Combinations.— This Standard includes a selected series of diameter-pitch combinations of threads taken from International Standard ISO 261 plus some additional sizes in the constant pitch series. These are given in Table 1. It also includes the standard series of diameter-pitch combinations for aerospace screws, bolts, nuts, and fluid system fittings as shown in Table 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Standard Metric Screw Threads MJ Profile Diameter-Pitch Combinations *ANSI/ASME B1.21M-1997*

Nominal Diameter Choices		Pitches		Nominal Diameter Choices		Pitches	
1st	2nd	Coarse	Fine	1st	2nd	Coarse	Fine
1.6	…	0.35	…	…	52	…	3, 2, 1.5
…	1.8	0.35	…	55	…	…	3, 2, 1.5
2.0	…	0.4	…		56	5.5	3, 2, 1.5
…	2.2	0.45	…	…	58	…	3, 2, 1.5
2.5	…	0.45	…	60		…	3, 2, 1.5
3	…	0.5	…	…	62	…	3, 2, 1.5
3.5	…	0.6	…	…	64	6	3, 2, 1.5
4	…	0.7	…	65	…	…	3, 2, 1.5
…	4.5	0.75	…	…	68	…	3, 2, 1.5
5	…	0.8	…	70	…	…	3, 2, 1.5
6	…	1	0.75	…	72	6	3, 2, 1.5
7	…	1	0.75	75	…	…	3, 2, 1.5
8	…	1.25	1, 0.75	…	76	…	3, 2, 1.5
…	9	1.25	1, 0.75	…	78	…	3[a], 2, 1.5[a]
10	…	1.5	1.25, 1, 0.75	80	…	6	3, 2, 1.5
…	11	1.5	1.25[b], 1, 0.75	…	82	…	3[a], 2, 1.5[a]
12	…	1.75	1.5, 1.25, 1	85	…	…	3, 2, 1.5[a]
14	…	2	1.5, 1.25[c], 1	90	…	6	3, 2, 1.5[a]
…	15	…	1.5, 1	95	…	…	3, 2, 1.5[a]
16	…	2	1.5, 1	100	…	6	3, 2, 1.5[a]
…	17	…	1.5, 1	105	…	…	3, 2, 1.5[a]
18	…	2.5	2, 1.5, 1	110	…	…	3, 2, 1.5[a]
20	…	2.5	2, 1.5, 1	…	115	…	3, 2, 1.5[a]
22	…	2.5	2, 1.5, 1	120	…	…	3, 2, 1.5[a]
24	…	3	2, 1.5, 1	…	125	…	3, 2, 1.5[a]
…	25	…	2, 1.5, 1	130	…	…	3, 2, 1.5[a]
…	26	…	1.5	…	135	…	3, 2, 1.5[a]
27	…	3	2, 1.5, 1	140	…	…	3, 2, 1.5[a]
…	28	…	2, 1.5, 1	…	145	…	3, 2, 1.5[a]
30	…	3.5	3, 2, 1.5, 1	150	…	…	3, 2, 1.5[a]
…	32	…	2, 1.5	…	155	…	3
33	…	…	3, 2, 1.5	160	…	…	3
…	35	…	1.5	…	165	…	3
36	…	4	3, 2, 1.5	170	…	…	3
…	38	…	1.5	…	175	…	3
39	…	…	3, 2, 1.5	180	…	…	3
…	40	…	3, 2, 1.5	…	185	…	3
.	42	4.5	3, 2, 1.5	190	…	…	3
45	…	…	3, 2, 1.5	…	195	…	3
…	48	5	3, 2, 1.5	200	…	…	3
50	…	…	3, 2, 1.5	…	…	…	…

[a] Not included in ISO 261.
[b] Only for aircraft control cable fittings.
[c] Only for spark plugs for engines.

All dimensions are in millimeters. Pitches in parentheses ( ) are to be avoided as far as possible.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Standard Metric Screw Threads MJ Profile, Diameter-Pitch Combinations for Aerospace *ANSI/ASME B1.21M-1997*

Aerospace Screws, Bolts and Nuts								Aerospace Fluid System Fittings					
Nom. Size[a]	Pitch	Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch	Nom. Size	Pitch
1.6	0.35	5	0.8	14	1.5	27	2	8	1	20	1.5	36	1.5
2	0.4	6	1	16	1.5	30	2	10	1	22	1.5	39	1.5
2.5	0.45	7	1	18	1.5	33	2	12	1.25	24	1.5	42	2
3	0.5	8	1	20	1.5	36	2	14	1.5	27	1.5	48	2
3.5	0.6	10	1.25	22	1.5	39	2	16	1.5	30	1.5	50	2
4	0.7	12	1.25	24	2	…	…	18	1.5	33	1.5	…	…

All dimensions are in millimeters.

[a] For threads smaller than 1.6 mm nominal size, use miuniature screw threads (ANSI B1.10M).



Fig. 1. Internal MJ Thread Basic and Design Profiles (Top) and External MJ Thread Basic and Design Profiles (Bottom) Showing Tolerance Zones

Copyright 2004, Industrial Press, Inc., New York, NY

Tolerances: The thread tolerance system is based on ISO 965/1, *Metric Screw thread System of Tolerance Positions and Grades*. Tolerances are positive for internal threads and negative for external threads, that is, in the direction of minimum material.

For aerospace applications, except for fluid fittings, tolerance classes 4H5H or 4G6G and 4g6g should be used. These classes approximate classes 3B/3A in the inch system. Aerospace fluid fittings use classes 4H5H or 4H6H and 4g6g.

Tolerance classes 4G5G or 4G6G and 4g6g are provided for use when thread allowances are required. These classes provide a slightly tighter fit than the inch classes 2B/2A at minimum material condition.

Additional tolerance classes 6H/6g are included in this Standard to provide appropriate product selection based on general applications. These classes and the selection of standard diameter/pitch combinations are the same as those provided for the M profile metric screw threads in ANSI/ASME B1.13M. Classes 6H/6g result in a slightly looser fit than inch classes 2B/2A at minimum material condition.

Symbols: Standard symbols appearing in Fig. 1 are:

D = Basic major diameter of internal thread

D_2 = Basic pitch diameter of internal thread

D_1 = Basic minor diameter of internal thread

d = Basic major diameter of external thread

d_2 = Basic pitch diameter of external thread

d_1 = Basic minor diameter of internal thread

d_3 = Diameter to bottom of external thread root radius

H = Height of fundamental triangle

P = Pitch

Basic Designations: The aerospace metric screw thread is designated by the letters "MJ" to identify the metric J thread form, followed by the nominal size and pitch in millimeters (separated by the sign "×") and followed by the tolerance class (separated by a dash from the pitch). Unless otherwise specified in the designation, the thread helix is right hand.

Example: MJ6 × 1 – 4h6h

For further details concerning limiting dimensions, allowances for coating and plating, modified and special threads, etc., reference should be made to the Standard.

Trapezoidal Metric Thread

Comparison of ISO and DIN Standards.— ISO metric trapezoidal screw threads standard, ISO 2904-1977, describes the system of general purpose metric threads for use in mechanisms and structures. The standard is in basic agreement with trapezoidal metric thread DIN 103. The DIN 103 standard applies a particular pitch for a particular diameter of thread, but the ISO standard applies a variety of pitchs for a particular diameter. In ISO 2904-1977, the same clearance is applied to both the major diameter and minor diameter, but in DIN 103 the clearance in the minor diameter is two or three times greater than clearance in the major diameter. A comparison of ISO 2904 and DIN 103 is given in Table 1.

Copyright 2004, Industrial Press, Inc., New York, NY



Metric Trapezoidal Thread, ISO 2904

Terminology: The term "bolt threads" is used for external screw threads, the term "nut threads" for internal screw threads.

Calculation: The value given in the International standards have been calculated by using the following formulas:

$$H_1 = 0.5P \qquad H_4 = H_1 + a_c = 0.5P + a_c \qquad H_3 = H_1 + a_c = 0.5P + a_c$$

$$D_4 = d + 2a_c \qquad Z = 0.25P = H_1/2 \qquad D_1 = d - 2H_1 = d - p$$

$$D_3 = D - 2h_3 \qquad d_2 = D_2 = d - 2Z = d - 0.5P \qquad R_{1\max.} = 0.5a_c \qquad R_{2\max.} = a_c$$

where a_c = clearance on the crest; D = major diameter for nut threads; D_2 = pitch diameter for nut threads; D_1 = minor diameter for nut threads; d = major diameter for bolt threads = nominal diameter; d_2 = pitch diameter for bolt threads; d_3 = minor diameter for bolt threads; h_1 = Height of overlapping; h_4 = height of nut threads; h_3 = height of bolt threads; and, P = pitch.

Table 1. Comparison of ISO Metric Trapezoidal Screw Thread *ISO 2904-1977* **and Trapezoidal Metric Screw Thread** *DIN 103*

	ISO 2904	DIN 103	Comment
Nominal Diameter	D	D_S	
Pitch	p	p	Same
Clearances (Bolt Circle)	a_c	b	Same
Clearances (Nut Circle)	a_c	a	Not same
Height of Overlapping	h_1	h_e	Same
Bolt Circle			
	$h_3 = 0.50P + a_c$	$h_s = 0.50P + a$	Same
	$h_{as} = 0.25p$	$z = 0.25p$	Same
Minor diameter for external thread	$D_3 = d - 2h_3$	$k_s = d - 2h_s$	Same
Pitch diameter for external thread	$D_2 = d - 2h_{as}$	$d_2 = d - 2z$	Same
Nut Circle			
Basic major diameter for nut thread	$D_4 = d + 2a_c$	$d_n = d + a + b$	Not same
Height of internal thread	$h_4 = h_3$	$h_n = h_3 + a$	Not same
Minor diameter of internal thread	$D_1 = D - 2h_1$	$K_n = D_n - 2h_n$	Not same

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ISO Metric Trapezoidal Screw Thread *ISO 2904-1977*

Nominal Diameter, d			Pitch, P	Pitch Diam. $d_2 = D_2$	Major Diam. D_4	Minor Diameter	
						d_3	D_1
8			1.5	7.250	8.300	6.200	6.500
	9		1.5	8.250	9.300	7.200	7.500
			2	8.000	9.500	6.500	7.000
10			1.5	9.250	10.300	8.200	8.500
			2	9.000	10.500	7.500	8.000
	11		2	10.000	11.500	8.500	9.000
			3	9.500	11.500	7.500	8.000
12			2	11.000	12.500	9.500	10.000
			3	10.500	12.500	8.500	9.000
	14		2	13.000	14.500	11.500	12.000
			3	12.500	14.500	10.500	11.000
16			2	15.000	16.500	13.500	14.000
			3	14.500	16.500	12.500	13.000
	18		2	17.000	18.500	15.500	16.000
			4	16.000	18.500	13.500	14.000
20			2	19.000	20.500	17.500	18.000
			4	18.000	20.500	15.500	16.000
	22		3	20.500	22.500	18.500	19.000
			5	19.500	22.500	16.500	17.000
			8	18.000	23.000	13.000	14.000
24			3	22.500	24.500	20.500	21.000
			5	21.500	24.500	18.500	19.000
			8	20.000	25.000	15.000	16.000
	26		3	24.500	26.500	22.500	23.000
			5	23.500	26.500	20.500	21.000
			8	22.000	27.000	17.000	18.000
28			3	26.500	28.500	24.500	25.000
			5	25.500	28.500	22.500	23.000
			8	24.000	29.000	19.000	20.000
	30		3	28.500	30.500	26.500	27.000
			6	27.000	31.000	23.000	24.000
			10	25.000	31.000	19.000	20.000
32			3	30.500	32.500	28.500	29.000
			6	29.000	33.000	25.000	26.000
			10	27.000	33.000	21.000	22.000
	34		3	32.500	34.500	30.500	31.000
			6	31.000	35.000	27.000	28.000
			10	29.000	35.000	23.000	24.000
36			3	34.500	36.500	32.500	33.000
			6	33.000	37.000	29.000	30.000
			10	31.000	37.000	25.000	26.000
	38		3	36.500	38.500	34.500	35.000
			7	34.500	39.000	30.000	31.000
			10	33.000	39.000	27.000	28.000
40			3	38.500	40.500	36.500	37.000
			7	36.500	41.000	32.000	33.000
			10	35.000	41.000	29.000	30.000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **ISO Metric Trapezoidal Screw Thread** *ISO 2904-1977*

Nominal Diameter, d			Pitch, P	Pitch Diam. $d_2 = D_2$	Major Diam. D_4	Minor Diameter	
						d_3	D_1
	42		3	40.500	42.500	38.500	39.000
			7	38.500	43.000	34.000	35.000
			10	37.000	43.000	31.000	32.000
44			3	42.500	44.500	40.500	41.000
			7	40.500	45.000	36.000	37.000
			12	38.000	45.000	31.000	32.000
	46		3	44.500	46.500	42.500	43.000
			8	42.000	47.000	37.000	38.000
			12	40.000	47.000	33.000	34.000
48			3	46.500	48.500	44.500	45.000
			8	44.000	49.000	39.000	40.000
			12	42.000	49.000	35.000	36.000
	50		3	48.500	50.500	46.500	47.000
			8	46.000	51.000	41.000	42.000
			12	44.000	51.000	37.000	38.000
52			3	50.500	52.500	48.500	49.000
			8	48.000	53.000	43.000	44.000
			12	46.000	53.000	39.000	40.000
	55		3	53.500	55.500	51.500	52.000
			9	50.500	56.000	45.000	46.000
			14	48.000	57.000	39.000	41.000
60			3	58.500	60.500	56.500	57.000
			9	55.500	61.000	50.000	51.000
			14	53.000	62.000	44.000	46.000
	65		4	63.000	65.500	60.500	61.000
			10	60.000	66.000	54.000	55.000
			16	57.000	67.000	47.000	49.000
70			4	68.000	70.500	65.500	66.000
			10	65.000	71.000	59.000	60.000
			16	62.000	72.000	52.000	54.000
	75		4	73.000	75.500	70.500	71.000
			10	70.000	76.000	64.000	65.000
			16	67.000	77.000	57.000	59.000
80			4	78.000	80.500	75.500	76.000
			10	75.000	81.000	69.000	70.000
			16	72.000	82.000	62.000	64.000
	85		4	83.000	85.500	80.500	81.000
			12	79.000	86.000	72.000	73.000
			18	76.000	87.000	65.000	67.000
90			4	88.000	90.500	85.500	86.000
			12	84.000	91.000	77.000	78.000
			18	81.000	92.000	70.000	72.000
	95		4	93.000	95.500	90.500	91.000
	95		12	89.000	96.000	82.000	83.000
			18	86.000	97.000	75.000	77.000
100			4	98.000	100.500	95.500	96.000
			12	94.000	101.000	87.000	88.000
			20	90.000	102.000	78.000	80.000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **ISO Metric Trapezoidal Screw Thread** *ISO 2904-1977*

Nominal Diameter, d			Pitch, P	Pitch Diam. $d_2 = D_2$	Major Diam. D_4	Minor Diameter	
						d_3	D_1
			4	103.000	105.500	100.500	101.000
		105	12	103.000	106.000	92.000	93.000
			20	95.000	107.000	83.000	85.000
			4	108.000	110.500	105.500	106.000
	110		12	104.000	111.000	97.000	98.000
			20	100.000	112.000	88.000	90.000
			6	112.000	116.000	108.000	109.000
		115	14	112.000	117.000	99.000	101.000
			22	104.000	117.000	91.000	93.000
			6	117.000	121.000	113.000	114.000
120			14	113.000	122.000	104.000	106.000
			22	109.000	122.000	96.000	98.000
			6	122.000	126.000	118.000	119.000
		125	14	122.000	127.000	109.000	111.000
			22	114.000	127.000	101.000	103.000
			6	127.000	131.000	123.000	124.000
	130		14	123.000	132.000	114.000	116.000
			22	119.000	132.000	106.000	108.000
			6	132.000	136.000	128.000	129.000
		135	14	132.000	137.000	119.000	121.000
			24	123.000	137.000	109.000	111.000
			6	137.000	141.000	133.000	134.000
140			14	133.000	142.000	124.000	126.000
			24	128.000	142.000	114.000	116.000
			6	142.000	146.000	138.000	139.000
		145	14	142.000	147.000	129.000	131.000
			24	133.000	147.000	119.000	121.000
			6	147.000	151.000	143.000	144.000
	150		16	142.000	152.000	132.000	134.000
			24	138.000	152.000	124.000	126.000
			6	152.000	156.000	148.000	149.000
		155	16	152.000	157.000	137.000	139.000
			24	143.000	157.000	129.000	131.000
			6	157.000	161.000	153.000	154.000
160			16	152.000	162.000	142.000	144.000
			28	146.000	162.000	130.000	132.000
			6	162.000	166.000	158.000	159.000
		165	16	162.000	167.000	147.000	149.000
			28	151.000	167.000	135.000	137.000
			6	167.000	171.000	163.000	164.000
	170		16	162.000	172.000	152.000	154.000
			28	156.000	172.000	140.000	142.000
			8	171.000	176.000	166.000	167.000
		175	16	171.000	177.000	157.000	159.000
			28	161.000	177.000	145.000	147.000
			8	176.000	181.000	171.000	172.000
180			18	171.000	182.000	160.000	162.000
			28	166.000	182.000	150.000	152.000

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **ISO Metric Trapezoidal Screw Thread** *ISO 2904-1977*

Nominal Diameter, d			Pitch, P	Pitch Diam. $d_2 = D_2$	Major Diam. D_4	Minor Diameter	
						d_3	D_1
			8	181.000	186.000	176.000	177.000
		185	18	181.000	187.000	165.000	167.000
			32	169.000	187.000	151.000	153.000
			8	186.000	191.000	181.000	182.000
	190		18	181.000	192.000	170.000	172.000
			32	174.000	192.000	156.000	158.000
			8	191.000	196.000	186.000	187.000
		195	18	191.000	197.000	175.000	177.000
			32	179.000	197.000	161.000	163.000
			8	196.000	201.000	191.000	192.000
200			18	191.000	202.000	180.000	182.000
			32	184.000	202.000	166.000	168.000
			8	206.000	211.000	201.000	202.000
	210		20	200.000	212.000	188.000	190.000
			36	192.000	212.000	172.000	174.000
			8	216.000	221.000	211.000	212.000
220			20	210.000	222.000	198.000	200.000
			36	202.000	222.000	182.000	184.000
			8	226.000	231.000	221.000	222.000
	230		20	220.000	232.000	208.000	210.000
			36	212.000	232.000	192.000	194.000
			8	236.000	241.000	231.000	232.000
240			22	229.000	242.000	216.000	218.000
			36	222.000	242.000	202.000	204.000
			12	244.000	251.000	237.000	238.000
	250		22	239.000	252.000	226.000	228.000
			40	230.000	252.000	208.000	210.000
			12	254.000	261.000	247.000	248.000
260			22	249.000	262.000	236.000	238.000
			40	240.000	262.000	218.000	220.000
			12	264.000	271.000	257.000	258.000
	270		24	258.000	272.000	244.000	246.000
			40	250.000	272.000	228.000	230.000
			12	274.000	281.000	267.000	268.000
280			24	268.000	282.000	254.000	256.000
			40	260.000	282.000	238.000	240.000
			12	284.000	291.000	277.000	278.000
	290		24	278.000	292.000	264.000	266.000
			44	268.000	292.000	244.000	246.000
			12	294.000	301.000	287.000	288.000
300			24	288.000	302.000	274.000	276.000
			44	278.000	302.000	254.000	256.000

All dimensions in millimeters

Copyright 2004, Industrial Press, Inc., New York, NY

Trapezoidal Metric Thread — Preferred Basic Sizes *DIN 103*

$H = 1.866P$
$h_s = 0.5P + a$
$h_e = 0.5P + a - b$
$h_n = 0.5P + 2a - b$
$h_{as} = 0.25P$



Nom. & Major Diam.of Bolt, D_s	Pitch, P	Pitch Diam., E	Depth of Engage-ment, h_e	Clearance		Bolt		Nut		
				a	b	Minor Diam., K_s	Depth of Thread, h_s	Major Diam., D_n	Minor Diam., K_n	Depth of Thread, h_n
10	3	8.5	1.25	0.25	0.5	6.5	1.75	10.5	7.5	1.50
12	3	10.5	1.25	0.25	0.5	8.5	1.75	12.5	9.5	1.50
14	4	12	1.75	0.25	0.5	9.5	2.25	14.5	10.5	2.00
16	4	14	1.75	0.25	0.5	11.5	2.25	16.5	12.5	2.00
18	4	16	1.75	0.25	0.5	13.5	2.25	18.5	14.5	2.00
20	4	18	1.75	0.25	0.5	15.5	2.25	20.5	16.5	2.00
22	5	19.5	2	0.25	0.75	16.5	2.75	22.5	18	2.00
24	5	21.5	2	0.25	0.75	18.5	2.75	24.5	20	2.25
26	5	23.5	2	0.25	0.75	20.5	2.75	26.5	22	2.25
28	5	25.5	2	0.25	0.75	22.5	2.75	28.5	24	2.25
30	6	27	2.5	0.25	0.75	23.5	3.25	30.5	25	2.75
32	6	29	2.5	0.25	0.75	25.5	3.25	32.5	27	2.75
36	6	33	2.5	0.25	0.75	29.5	3.25	36.5	31	2.75
40	7	36.5	3	0.25	0.75	32.5	3.75	40.5	34	3.25
44	7	40.5	3	0.25	0.75	36.5	3.75	44.5	38	3.25
48	8	44	3.5	0.25	0.75	39.5	4.25	48.5	41	3.75
50	8	46	3.5	0.25	0.75	41.5	4.25	50.5	43	3.75
52	8	48	3.5	0.25	0.75	43.5	4.25	52.5	45	3.75
55	9	50.5	4	0.25	0.75	45.5	4.75	55.5	47	4.25
60	9	55.5	4	0.25	0.75	50.5	4.75	60.5	52	4.25
65	10	60	4.5	0.25	0.75	54.5	5.25	65.5	56	4.75
70	10	65	4.5	0.25	0.75	59.5	5.25	70.5	61	4.75
75	10	70	4.5	0.25	0.75	64.5	5.25	75.5	66	4.75
80	10	75	4.5	0.25	0.75	69.5	5.25	80.5	71	4.75
85	12	79	5.5	0.25	0.75	72.5	6.25	85.5	74	5.75
90	12	84	5.5	0.25	0.75	77.5	6.25	90.5	79	5.75
95	12	89	5.5	0.25	0.75	82.5	6.25	95.5	84	5.75
100	12	94	5.5	0.25	0.75	87.5	6.25	100.5	89	5.75
110	12	104	5.5	0.25	0.75	97.5	6.25	110.5	99	5.75
120	14	113	6	0.5	1.5	105	7.5	121	108	6.5
130	14	123	6	0.5	1.5	115	7.5	131	118	6.5
140	14	133	6	0.5	1.5	125	7.5	141	128	6.5
150	16	142	7	0.5	1.5	133	8.5	151	136	7.5
160	16	152	7	0.5	1.5	143	8.5	161	146	7.5
170	16	162	7	0.5	1.5	153	8.5	171	156	7.5
180	18	171	8	0.5	1.5	161	9.5	181	164	8.5
190	18	181	8	0.5	1.5	171	9.5	191	174	8.5
200	18	191	8	0.5	1.5	181	9.5	201	184	8.5
210	20	200	9	0.5	1.5	189	10.5	211	192	9.5
220	20	210	9	0.5	1.5	199	10.5	221	202	9.5
230	20	220	9	0.5	1.5	209	10.5	231	212	9.5
240	22	229	10	0.5	1.5	217	11.5	241	220	10.5
250	22	239	10	0.5	1.5	227	11.5	251	230	10.5
260	22	249	10	0.5	1.5	237	11.5	261	240	10.5
270	24	258	11	0.5	1.5	245	12.5	271	248	11.5
280	24	268	11	0.5	1.5	255	12.5	281	258	11.5
290	24	278	11	0.5	1.5	265	12.5	291	268	11.5
300	26	287	12	0.5	1.5	273	13.5	301	276	12.5

All dimensions are in millimeters.

*Roots are rounded to a radius, r, equal to 0.25 mm for pitches of from 3 to 12 mm inclusive and 0.5 mm for pitches of from 14 to 26 mm inclusive for power transmission.

Copyright 2004, Industrial Press, Inc., New York, NY

ISO Miniature Screw Threads

ISO Miniature Screw Threads, Basic Form *ISO/R 1501:1970*

Pitch P	$H = 0.866025P$	$0.554256H = 0.48P$	$0.375H = 0.324760P$	$0.320744H = 0.320744P$	$0.125H = 0.108253P$
0.08	0.069282	0.038400	0.025981	0.022222	0.008660
0.09	0.077942	0.043200	0.029228	0.024999	0.009743
0.1	0.086603	0.048000	0.032476	0.027777	0.010825
0.125	0.108253	0.060000	0.040595	0.034722	0.013532
0.15	0.129904	0.072000	0.048714	0.041666	0.016238
0.175	0.151554	0.084000	0.056833	0.048610	0.018944
0.2	0.173205	0.096000	0.064952	0.055554	0.021651
0.225	0.194856	0.108000	0.073071	0.062499	0.024357
0.25	0.216506	0.120000	0.081190	0.069443	0.027063
0.3	0.259808	0.144000	0.097428	0.083332	0.032476

ISO Miniature Screw Threads, Basic Dimensions *ISO/R 1501:1970*

Nominal Diameter	Pitch P	Major Diameter D, d	Pitch Diameter D_2, d_2	Minor Diameter D_1, d_1
0.30	0.080	0.300000	0.248039	0.223200
0.35	0.090	0.350000	0.291543	0.263600
0.40	0.100	0.400000	0.335048	0.304000
0.45	0.100	0.450000	0.385048	0.354000
0.50	0.125	0.500000	0.418810	0.380000
0.55	0.125	0.550000	0.468810	0.430000
0.60	0.150	0.600000	0.502572	0.456000
0.70	0.175	0.700000	0.586334	0.532000
0.80	0.200	0.800000	0.670096	0.608000
0.90	0.225	0.900000	0.753858	0.684000
1.00	0.250	1.000000	0.837620	0.760000
1.10	0.250	1.100000	0.937620	0.860000
1.20	0.250	1.200000	1.037620	0.960000
1.40	0.300	1.400000	1.205144	1.112000

D and d dimensions refer to the nut (internal) and screw (external) threads, respectively.

British Standard ISO Metric Screw Threads

BS 3643:Part 1:1981 (1998) provides principles and basic data for ISO metric screw threads. It covers single-start, parallel screw threads of from 1 to 300 millimeters in diameter. Part 2 of the Standard gives the specifications for selected limits of size.

Basic Profile.— The ISO basic profile for triangular screw threads is shown in Fig. 1. and basic dimensions of this profile are given in Table 1.

Table 1. British Standard ISO Metric Screw Threads Basic Profile Dimensions *BS 3643:1981 (1998)*

Pitch P	$H = 0.086603P$	$\frac{5}{8}H = 0.54127P$	$\frac{3}{8}H = 0.32476P$	$H/4 = 0.21651P$	$H/8 = 0.10825P$
0.2	0.173 205	0.108 253	0.064 952	0.043 301	0.021 651
0.25	0.216 506	0.135 316	0.081 190	0.054 127	0.027 063
0.3	0.259 808	0.162 380	0.097 428	0.064 952	0.032 476
0.35	0.303 109	0.189 443	0.113 666	0.075 777	0.037 889
0.4	0.346 410	0.216 506	0.129 904	0.086 603	0.043 301
0.45	0.389 711	0.243 570	0.146 142	0.097 428	0.048 714
0.5	0.433 013	0.270 633	0.162 380	0.108 253	0.054 127
0.6	0.519 615	0.324 760	0.194 856	0.129 904	0.064 952

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **British Standard ISO Metric Screw Threads Basic Profile Dimensions** *BS 3643:1981 (1998)*

Pitch P	H = 0.086603P	$\frac{5}{8}H$ = 0.54127P	$\frac{3}{8}H$ = 0.32476P	$H/4$ = 0.21651P	$H/8$ = 0.10825P
0.7	0.606 218	0.378 886	0.227 322	0.151 554	0.075 777
0.75	0.649 519	0.405 949	0.243 570	0.162 380	0.081 190
0.8	0.692 820	0.433 013	0.259 808	0.173 205	0.086 603
1	0.866 025	0.541 266	0.324 760	0.216 506	0.108 253
1.25	1.082 532	0.676 582	0.405 949	0.270 633	0.135 316
1.5	1.299 038	0.811 899	0.487 139	0.324 760	0.162 380
1.75	1.515 544	0.947 215	0.568 329	0.378 886	0.189 443
2	1.732 051	1.082 532	0.649 519	0.433 013	0.216 506
2.5	2.165 063	1.353 165	0.811 899	0.541 266	0.270 633
3	2.598 076	1.623 798	0.974 279	0.649 519	0.324 760
3.5	3.031 089	1.894 431	1.136 658	0.757 772	0.378 886
4	3.464 102	2.165 063	1.299 038	0.866 025	0.433 013
4.5	3.897 114	2.435 696	1.461 418	0.974 279	0.487 139
5	4.330 127	2.706 329	1.623 798	1.082 532	0.541 266
5.5	4.763 140	2.976 962	1.786 177	1.190 785	0.595 392
6	5.196 152	3.247 595	1.948 557	1.299 038	0.649 519
8[a]	6.928 203	4.330 127	2.598 076	1.732 051	0.866 025

[a] This pitch is not used in any of the ISO metric standard series.
All dimensions are given in millimeters.

Tolerance System.— The tolerance system defines *tolerance classes* in terms of a combination of a *tolerance grade* (figure) and a *tolerance position* (letter). The tolerance position is defined by the distance between the basic size and the nearest end of the tolerance zone, this distance being known as the *fundamental deviation*, EI, in the case of internal threads, and es in the case of external threads. These tolerance positions with respect to the basic size (zero line) are shown in Fig. 2 and fundamental deviations for nut and bolt threads are given in Table 2.

Table 2. Fundamental Deviations for Nut Threads and Bolt Threads

Pitch P	Nut Thread D_2, D_1		Bolt Thread d, d_2				Pitch P	Nut Thread D_2, D_1		Bolt Thread d, d_2			
	Tolerance Position							Tolerance Position					
	G	H	e	f	g	h		G	H	e	f	g	h
	Fundamental Deviation							Fundamental Deviation					
	EI	EI	es	es	es	es		EI	EI	es	es	es	es
mm	µm	µm	µm	µm	µm	µm	mm	µm	µm	µm	µm	µm	µm
0.2	+17	0	…	…	−17	0	1.25	+28	0	−63	−42	−28	0
0.25	+18	0	…	…	−18	0	1.5	+32	0	−67	−45	−32	0
0.3	+18	0	…	…	−18	0	1.75	+34	0	−71	−48	−34	0
0.35	+19	0	…	−34	−19	0	2	+38	0	−71	−52	−38	0
0.4	+19	0	…	−34	−19	0	2.5	+42	0	−80	−58	−42	0
0.45	+20	0	…	−35	−20	0	3	+48	0	−85	−63	−48	0
0.5	+20	0	−50	−36	−20	0	3.5	+53	0	−90	−70	−53	0
0.6	+21	0	−53	−36	−21	0	4	+60	0	−95	−75	−60	0
0.7	+22	0	−56	−38	−22	0	4.5	+63	0	−100	−80	−63	0
0.75	+22	0	−56	−38	−22	0	5	+71	0	−106	−85	−71	0
0.8	+24	0	−60	−38	−24	0	5.5	+75	0	−112	−90	−75	0
1	+26	0	−60	−40	−26	0	6	+80	0	−118	−95	−80	0

See Figs. 1 and 2 for meaning of symbols.

Copyright 2004, Industrial Press, Inc., New York, NY

Tolerance Grades.— Tolerance grades specified in the Standard for each of the four main screw thread diameters are as follows:

Minor diameter of nut threads (D_1): tolerance grades 4, 5, 6, 7, and 8.

Major diameter of bolt threads (d): tolerance grades 4, 6, and 8.

Pitch diameter of nut threads (D_2): tolerance grades 4, 5, 6, 7, and 8.

Pitch diameter of bolt threads (d_2): tolerance grades 3, 4, 5, 6, 7, 8, and 9.

Tolerance Positions.— Tolerance positions are G and H for nut threads and e, f, g, and h for bolt threads. The relationship of these tolerance position identifying letters to the amount of fundamental deviation is shown in Table 2.



D = maj. diam. of internal thread;
d = maj. diam. of external th
D_2 = pitch diam. of internal thread;
d_2 = pitch diam. of internal thread;
D_1 = minor diam. of internal thread;
d_1 = minor diam. of external thread;
P = Pitch;
H = height of fundamental angle;

Fig. 1. Basic Profile of ISO Metric Thread

Tolerance Classes.— To reduce the number of gages and tools, the Standard specifies that the tolerance positions and classes shall be chosen from those listed in Table 3 for short, normal, and long lengths of thread engagement. The following rules apply for the choice of tolerance quality: *Fine:* for precision threads when little variation of fit character is needed; *Medium:* for general use; and *Coarse:* for cases where manufacturing difficulties can arise as, for example, when threading hot-rolled bars and long blind holes. If the actual length of thread engagement is unknown, as in the manufacturing of standard bolts, normal is recommended.

Table 3. Tolerance Classes[a,b,c] for Nuts and Bolts

Tolerance Classes for Nuts												
	Tolerance Position G						Tolerance Position H					
Tolerance Quality	Short		Normal		Long		Short		Normal		Long	
Fine	…		…		…		4H[b]		5H[b]		6H[b]	
Medium	5G[a]		6G[c]		7G[c]		5H[a]		6H[a,d]		7H[a]	
Coarse	…		7G[c]		8G[c]		…		7H[b]		8H[b]	
Tolerance Classes for Bolts												
Tolelance Quality	Tolerance Position e			Tolerance Position f			Tolerance Position g			Tolerance Position h		
	Short	Normal	Long	Short	Normal	Long	Short	Normal	Long	Short	Normal	Long
Fine	…	…	…	…	…	…	…	…	…	3h4h[c]	4h[a]	5h4h[c]
Medium	…	6e[a]	7e6e[c]	…	6f[a]	…	5g6g[c]	6g[a,d]	7g6g[c]	5h6h[c]	6h[b]	7h6h[c]
Coarse	…	…	…	…	…	…	…	8g[b]	9g8g[c]	…	…	…

[a] First choice.

[b] Second choice.

[c] Third choice; these are to be avoided.

[d] For commercial nut and bolt threads.

Note: See Table 4 for short, normal, and long categories. Any of the recommended tolerance classes for nuts can be combined with any of the recommended tolerance classes for bolts with the exception of sizes M1.4 and smaller for which the combination 5H/6h or finer shall be chosen. However, to guarantee a sufficient overlap, the finished components should preferably be made to form the fits H/g, H/h, or G/h.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Lengths of Thread Engagements for Short, Normal, and Long Categories

Basic Major Diameter *d*		Pitch *P*	Short	Normal		Long	Basic Major Diameter *d*		Pitch *P*	Short	Normal		Long
			Length of Thread Engagement							Length of Thread Engagement			
Over	Up to and Incl.		Up to and Incl.	Over	Up to and Incl.	Over	Over	Up to and Incl.		Up to and Incl.	Over	Up to and Incl.	Over
		0.2	0.5	0.5	1.4	1.4			1	4	4	12	12
0.99	1.4	0.25	0.6	0.6	1.7	1.7			1.5	6.3	6.3	19	19
		0.3	0.7	0.7	2	2			2	8.5	8.5	25	25
		0.2	0.5	0.5	1.5	1.5	22.4	45	3	12	12	36	36
		0.25	0.6	0.6	1.9	1.9			3.5	15	15	45	45
1.4	2.8	0.35	0.8	0.8	2.6	2.6			4	18	18	53	53
		0.4	1	1	3	3			4.5	21	21	63	63
		0.45	1.3	1.3	3.8	3.8			1.5	7.5	7.5	22	22
		0.35	1	1	3	3			2	9.5	9.5	28	28
		0.5	1.5	1.5	4.5	4.5			3	15	15	45	45
2.8	5.6	0.6	1.7	1.7	5	5	45	90	4	19	19	56	56
		0.7	2	2	6	6			5	24	24	71	71
		0.75	2.2	2.2	6.7	6.7			5.5	28	28	85	85
		0.8	2.5	2.5	7.5	7.5			6	32	32	95	95
		0.75	2.4	2.4	7.1	7.1			2	12	12	36	36
5.6	11.2	1	3	3	9	9	90	180	3	18	18	53	53
		1.25	4	4	12	12			4	24	24	71	71
		1.5	5	5	15	15			6	36	36	106	106
		1	3.8	3.8	11	11			3	20	20	60	60
		1.25	4.5	4.5	13	13	180	300	4	26	26	80	80
11.2	22.4	1.5	5.6	5.6	16	16			6	40	40	118	118
		1.75	6	6	18	18							
		2	8	8	24	24							
		2.5	10	10	30	30							

All dimensions are given in millimeters



Fig. 2. Tolerance Positions with Respect to Zero Line (Basic Size)

Design Profiles.— The design profiles for ISO metric internal and external screw threads are shown in Fig. 3. These represent the profiles of the threads at their maximum metal condition. It may be noted that the root of each thread is deepened so as to clear the basic flat crest of the other thread. The contact between the thread is thus confined to their sloping flanks. However, for nut threads as well as bolt threads, the actual root contours shall not at any point violate the basic profile.

Designation.— Screw threads complying with the requirements of the Standard shall be designated by the letter M followed by values of the nominal diameter and of the pitch, expressed in millimeters, and separated by the sign × . *Example:* M6 × 0.75. The absence of the indication of pitch means that a coarse pitch is specified.

The complete designation of a screw thread consists of a designation for the thread system and size, and a designation for the crest diameter tolerance. Each class designation consists of: a figure indicating the tolerance grade; and a letter indicating the tolerance

Copyright 2004, Industrial Press, Inc., New York, NY

position, capital for nuts, lower case for bolts. If the two class designations for a thread are the same (one for the pitch diameter and one for the crest diameter), it is not necessary to repeat the symbols. As examples, a bolt thread designated M10-6g signifies a thread of 10 mm nominal diameter in the Coarse Thread Series having a tolerance class 6g for both pitch and major diameters. A designation M10 × 1-5g6g signifies a bolt thread of 10 mm nominal diameter having a pitch of 1 mm, a tolerance class 5g for pitch diameter, and a tolerance class 6g for major diameter. A designation M10-6H signifies a nut thread of 10 mm diameter in the Coarse Thread Series having a tolerance class 6H for both pitch and minor diameters.



Fig. 3. Maximum Material Profiles for Internal and External Threads

A fit between mating parts is indicated by the nut thread tolerance class followed by the bolt thread tolerance class separated by an oblique stroke. *Examples:* M6-6H/6g and M20 × 2-6H/5g6g. For coated threads, the tolerances apply to the parts before coating, unless otherwise specified. After coating, the actual thread profile shall not at any point exceed the maximum material limits for either tolerance position H or h.

Fundamental Deviation Formulas.— The formulas used to calculate the fundamental deviations in Table 2 are:

$EI_G = +(15 + 11P)$
$EI_H = 0$
$es_e = -(50 + 11P)$ except for threads with P ≤ 0.45 mm
$es_f = -(30 + 11P)$
$es_g = -(15 + 11P)$
$es_h = 0$

In these formulas, EI and es are expressed in micrometers and *P* is in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Crest Diameter Tolerance Formulas.— The tolerances for the major diameter of bolt threads (T_d), grade 6, in Table 5, were calculated from the formula:

$$T_d(6) = 180\sqrt[3]{P^2} - \frac{3.15}{\sqrt{P}}$$

In this formula, $T_d(6)$ is in micrometers and P is in millimeters. For tolerance grades 4 and 8: $T_d(4) = 0.63\,T_d(6)$ and $T_d(8) = 1.6\,T_d(6)$, respectively.

The tolerances for the minor diameter of nut threads (T_{D1}), grade 6, in Table 5, were calculated as follows:

For pitches 0.2 to 0.8 mm, $T_{D1}(6) = 433P - 190P^{1.22}$.

For pitches 1 mm and coarser, $T_{D1}(6) = 230P^{0.7}$.

In these formulas, $T_{D1}(6)$ is in micrometers and P is in millimeters. For tolerance grades 4, 5, 7, and 8: $T_{D1}(4) = 0.63\,T_{D1}(6)$; $T_{D1}(5) = 0.8\,T_{D1}(6)$; $T_{D1}(7) = 1.25\,T_{D1}(6)$; and $T_{D1}(8) = 1.6\,T_{D1}(6)$, respectively.

Table 5. British Standard ISO Metric Screw Threads: Limits and Tolerances for Finished Uncoated Threads for Normal Lengths of Engagement *BS 3643: Part 2: 1981*

Nominal Diameter[a]	Pitch		External Threads (Bolts)							Internal Threads (Nuts)[b]						
	Coarse	Fine	Tol. Class	Fund dev.	Major Dia. Max	Major Dia. Tol(–)	Pitch Dia. Max	Pitch Dia. Tol(–)	Minor Dia Min	Tol. Class	Major Dia. Min	Pitch Dia. Max	Pitch Dia. Tol(–)	Minor Dia Max	Minor Dia Tol(–)
1		0.2	4h	0	1.000	0.036	0.870	0.030	0.717	4H	1.000	0.910	0.040	0.821	0.038
			6g	0.017	0.983	0.056	0.853	0.048	0.682						
	0.25		4h	0	1.000	0.042	0.838	0.034	0.649	4H	1.000	0.883	0.045	0.774	0.045
			6g	0.018	0.982	0.067	0.820	0.053	0.613	5H	1.000	0.894	0.056	0.785	0.056
1.1		0.2	4h	0	1.100	0.036	0.970	0.030	0.817	4H	1.100	1.010	0.040	0.921	0.038
			6g	0.017	1.083	0.056	0.953	0.048	0.782						
	0.25		4h	0	1.100	0.042	0.938	0.034	0.750	4H	1.100	0.983	0.045	0.874	0.045
			6g	0.018	1.082	0.067	0.920	0.053	0.713	5H	1.100	0.994	0.056	0.885	0.056
1.2		0.2	4h	0	1.200	0.036	1.070	0.030	0.917	4H	1.200	1.110	0.040	1.021	0.038
			6g	0.017	1.183	0.056	1.053	0.048	0.882						
	0.25		4h	0	1.200	0.042	1.038	0.034	0.850	4H	1.200	1.083	0.045	0.974	0.045
			6g	0.018	1.182	0.067	1.020	0.053	0.813	5H	1.200	1.094	0.056	0.985	0.056
1.4		0.2	4h	0	1.400	0.036	1.270	0.030	1.117	4H	1.400	1.310	0.040	1.221	0.038
			6g	0.017	1.383	0.056	1.253	0.048	1.082						
	0.3		4h	0	1.400	0.048	1.205	0.036	0.984	4H	1.400	1.253	0.048	1.128	0.053
			6g	0.018	1.382	0.075	1.187	0.056	0.946	5H	1.400	1.265	0.060	1.142	0.067
										6H	1.400	1.280	0.075	1.160	0.085
1.6		0.2	4h	0	1.600	0.036	1.470	0.032	1.315	4H	1.600	1.512	0.042	1.421	0.038
			6g	0.017	1.583	0.056	1.453	0.050	1.280						
	0.35		4h	0	1.600	0.053	1.373	0.040	1.117	4H	1.600	1.426	0.053	1.284	0.063
			6g	0.019	1.581	0.085	1.354	0.063	1.075	5H	1.600	1.440	0.067	1.301	0.080
										6H	1.600	1.458	0.085	1.321	0.100
1.8		0.2	4h	0	1.800	0.036	1.670	0.032	1.515	4H	1.800	1.712	0.042	1.621	0.038
			6g	0.017	1.783	0.056	1.653	0.050	1.480						
	0.35		4h	0	1.800	0.053	1.573	0.040	1.317	4H	1.800	1.626	0.053	1.484	0.063
			6g	0.019	1.781	0.085	1.554	0.063	1.275	5H	1.800	1.640	0.067	1.501	0.080
										6H	1.800	1.658	0.085	1.521	0.100
2		0.25	4h	0	2.000	0.042	1.838	0.036	1.648	4H	2.000	1.886	0.048	1.774	0.045
			6g	0.018	1.982	0.067	1.820	0.056	1.610	5H	2.000	1.898	0.060	1.785	0.056
	0.4		4h	0	2.000	0.060	1.740	0.042	1.452	4H	2.000	1.796	0.056	1.638	0.071
			6g	0.019	1.981	0.095	1.721	0.067	1.408	5H	2.000	1.811	0.071	1.657	0.090
										6H	2.000	1.830	0.090	1.679	0.112
2.2		0.25	4h	0	2.200	0.042	2.038	0.036	1.848	4H	2.200	2.086	0.048	1.974	0.045
			6g	0.018	2.182	0.067	2.020	0.056	1.810	5H	2.200	2.098	0.060	1.985	0.056
	0.45		4h	0	2.200	0.063	1.908	0.045	1.585	4H	2.200	1.968	0.060	1.793	0.080
			6g	0.020	2.180	0.100	1.888	0.071	1.539	5H	2.200	1.983	0.075	1.813	0.100
										6H	2.000	2.003	0.095	1.838	0.125

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **British Standard ISO Metric Screw Threads: Limits and Tolerances for Finished Uncoated Threads for Normal Lengths of Engagement** *BS 3643: Part 2: 1981*

Nominal Diameter[a]	Pitch		External Threads (Bolts)							Internal Threads (Nuts)[b]						
					Major Dia.		Pitch Dia.		Minor Dia		Major Dia.	Pitch Dia.		Minor Dia		
	Coarse	Fine	Tol. Class	Fund dev.	Max	Tol(−)	Max	Tol(−)	Min	Tol. Class	Min	Max	Tol(−)	Max	Tol(−)	
			4h	0	2.500	0.053	2.273	0.040	2.017	4H	2.500	2.326	0.053	2.184	0.063	
		0.35	6g	0.019	2.481	0.085	2.254	0.063	1.975	5H	2.500	2.340	0.067	2.201	0.080	
2.5										6H	2.500	2.358	0.085	2.221	0.100	
	0.45		4h	0	2.500	0.063	2.208	0.045	1.885	4H	2.500	2.268	0.060	2.093	0.080	
			6g	0.020	2.480	0.100	2.188	0.071	1.839	5H	2.500	2.283	0.075	2.113	0.100	
										6H	2.500	2.303	0.095	2.138	0.125	
			4h	0	3.000	0.053	2.773	0.042	2.515	4H	3.000	2.829	0.056	2.684	0.063	
		0.35	6g	0.019	2.981	0.085	2.754	0.067	2.471	5H	3.000	2.844	0.071	2.701	0.080	
3										6H	3.000	2.863	0.090	2.721	0.100	
			4h	0	3.000	0.067	2.675	0.048	2.319	5H	3.000	2.755	0.080	2.571	0.112	
	0.5		6g	0.020	2.980	0.106	2.655	0.075	2.272	6H	3.000	2.775	0.100	2.599	0.140	
										7H	3.000	2.800	0.125	2.639	0.180	
			4h	0	3.500	0.053	3.273	0.042	3.015	4H	3.500	3.329	0.056	3.184	0.063	
		0.35	6g	0.019	3.481	0.085	3.254	0.067	2.971	5H	3.500	3.344	0.071	3.201	0.080	
3.5										6H	3.500	3.363	0.090	3.221	0.100	
	0.6		4h	0	3.500	0.080	3.110	0.053	2.688	5H	3.500	3.200	0.090	2.975	0.125	
			6g	0.021	3.479	0.125	3.089	0.085	2.635	6H	3.500	3.222	0.112	3.010	0.160	
										7H	3.500	3.250	0.140	3.050	0.200	
			4h	0	4.000	0.067	3.675	0.048	3.319	5H	4.000	3.755	0.080	3.571	0.112	
		0.5	6g	0.020	3.980	0.106	3.655	0.075	3.272	6H	4.000	3.775	0.100	3.599	0.140	
4										7H	4.000	3.800	0.125	3.639	0.180	
	0.7		4h	0	4.000	0.090	3.545	0.056	3.058	5H	4.000	3.640	0.095	3.382	0.140	
			6g	0.022	3.978	0.140	3.523	0.090	3.002	6H	4.000	3.663	0.118	3.422	0.180	
										7H	4.000	3.695	0.150	3.466	0.224	
			4h	0	4.500	0.067	4.175	0.048	3.819	5H	4.500	4.255	0.080	4.071	0.112	
		0.5	6g	0.020	4.480	0.106	4.155	0.075	3.772	6H	4.500	4.275	0.100	4.099	0.140	
4.5										7H	4.500	4.300	0.125	4.139	0.180	
	0.75		4h	0	4.500	0.090	4.013	0.056	3.495	5H	4.500	4.108	0.095	3.838	0.150	
			6g	0.022	4.478	0.140	3.991	0.090	3.439	6H	4.500	4.131	0.118	3.878	0.190	
										7H	4.500	4.163	0.150	3.924	0.236	
			4h	0	5.000	0.067	4.675	0.048	4.319	5H	5.000	4.755	0.080	4.571	0.112	
		0.5	6g	0.020	4.980	0.106	4.655	0.075	4.272	6H	5.000	4.775	0.100	4.599	0.140	
5										7H	5.000	4.800	0.125	4.639	0.180	
	0.8		4h	0	5.000	0.095	4.480	0.060	3.927	5H	5.000	4.580	0.100	4.294	0.160	
			6g	0.024	4.976	0.150	4.456	0.095	3.868	6H	5.000	4.605	0.125	4.334	0.200	
										7H	5.000	4.640	0.160	4.384	0.250	
			4h	0	5.500	0.067	5.175	0.048	4.819	5H	5.500	5.255	0.080	5.071	0.112	
5.5		0.5	6g	0.020	5.480	0.106	5.155	0.075	4.772	6H	5.500	5.275	0.100	5.099	0.140	
										7H	5.500	5.300	0.125	5.139	0.180	
			4h	0	6.000	0.090	5.513	0.063	4.988	5H	6.000	5.619	0.106	5.338	0.150	
		0.75	6g	0.022	5.978	0.140	5.491	0.100	4.929	6H	6.000	5.645	0.132	5.378	0.190	
6										7H	6.000	5.683	0.170	5.424	0.236	
	1		4h	0	6.000	0.112	5.350	0.071	4.663	5H	6.000	5.468	0.118	5.107	0.190	
			6g	0.026	5.974	0.180	5.324	0.112	4.597	6H	6.000	5.500	0.150	5.153	0.236	
			8g	0.026	5.974	0.280	5.324	0.180	4.528	7H	6.000	5.540	0.190	5.217	0.300	
			4h	0	7.000	0.090	6.513	0.063	5.988	5H	7.000	6.619	0.106	6.338	0.150	
		0.75	6g	0.022	6.978	0.140	6.491	0.100	5.929	6H	7.000	6.645	0.132	6.378	0.190	
7										7H	7.000	6.683	0.170	6.424	0.236	
	1		4h	0	7.000	0.112	6.350	0.071	5.663	5H	7.000	6.468	0.118	6.107	0.190	
			6g	0.026	6.974	0.180	6.324	0.112	5.596	6H	7.000	6.500	0.150	6.153	0.236	
			8g	0.026	6.974	0.280	6.324	0.180	5.528	7H	7.000	6.540	0.190	6.217	0.300	
			4h	0	8.000	0.112	7.350	0.071	6.663	5H	8.000	7.468	0.118	7.107	0.190	
		1	6g	0.026	7.974	0.180	7.324	0.112	6.596	6H	8.000	7.500	0.150	7.153	0.236	
			8g	0.026	7.974	0.280	7.324	0.180	6.528	7H	8.000	7.540	0.190	7.217	0.300	
8			4h	0	8.000	0.132	7.188	0.075	6.343	5H	8.000	7.313	0.125	6.859	0.212	
	1.25		6g	0.028	7.972	0.212	7.160	0.118	6.272	6H	8.000	7.348	0.160	6.912	0.265	
			8g	0.028	7.972	0.335	7.160	0.190	6.200	7H	8.000	7.388	0.200	6.982	0.335	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **British Standard ISO Metric Screw Threads: Limits and Tolerances for Finished Uncoated Threads for Normal Lengths of Engagement** *BS 3643: Part 2: 1981*

Nominal Diameter[a]	Pitch		External Threads (Bolts)							Internal Threads (Nuts)[b]					
					Major Dia.		Pitch Dia.		Minor Dia		Major Dia.	Pitch Dia.		Minor Dia	
	Coarse	Fine	Tol. Class	Fund dev.	Max	Tol(−)	Max	Tol(−)	Min	Tol. Class	Min	Max	Tol(−)	Max	Tol(−)
			4h	0	9.000	0.132	8.188	0.075	7.343	5H	9.000	8.313	0.125	7.859	0.212
9	1.25		6g	0.028	8.972	0.212	8.160	0.008	7.272	6H	9.000	8.348	0.160	7.912	0.265
			8g	0.028	8.972	0.335	8.160	0.190	7.200	7H	9.000	8.388	0.200	7.982	0.335
			4h	0	10.000	0.132	9.188	0.075	8.343	5H	10.000	9.313	0.125	8.859	0.212
		1.25	6g	0.028	9.972	0.212	9.160	0.118	8.272	6H	10.000	9.348	0.160	8.912	0.265
10			8g	0.028	9.972	0.335	9.160	0.190	8.200	7H	10.000	9.388	0.200	8.982	0.335
	1.5		4h	0	10.000	0.150	9.026	0.085	8.018	5H	10.000	9.166	0.140	8.612	0.236
			6g	0.032	9.968	0.236	8.994	0.132	7.938	6H	10.000	9.206	0.180	8.676	0.300
			8g	0.032	9.968	0.375	8.994	0.212	7.858	7H	10.000	9.250	0.224	8.751	0.375
			4h	0	11.000	0.150	10.026	0.085	9.018	5H	11.000	10.166	0.140	9.612	0.236
11	1.5		6g	0.032	10.968	0.236	9.994	0.132	8.938	6H	11.000	10.206	0.180	9.676	0.300
			8g	0.032	10.968	0.375	9.994	0.212	8.858	7H	11.000	10.250	0.224	9.751	0.375
			4h	0	12.000	0.132	11.188	0.085	10.333	5H	12.000	11.328	0.140	10.859	0.212
		1.25	6g	0.028	11.972	0.212	11.160	0.132	10.257	6H	12.000	11.398	0.180	10.912	0.265
12			8g	0.028	11.972	0.335	11.160	0.212	10.177	7H	12.000	11.412	0.224	10.985	0.335
			4h	0	12.000	0.170	10.863	0.095	9.692	5H	12.000	11.023	0.160	10.371	0.265
	1.75		6g	0.034	11.966	0.265	10.829	0.150	9.602	6H	12.000	11.063	0.200	10.441	0.335
			8g	0.034	11.966	0.425	10.829	0.236	9.516	7H	12.000	11.113	0.250	10.531	0.425
			4h	0	14.000	0.150	13.026	0.090	12.012	5H	14.000	13.176	0.150	12.612	0.236
		1.5	6g	0.032	13.968	0.236	12.994	0.140	11.930	6H	14.000	13.216	0.190	12.676	0.300
14			8g	0.032	13.968	0.375	12.994	0.224	11.846	7H	14.000	13.262	0.236	12.751	0.375
	2		4h	0	14.000	0.180	12.701	0.100	11.369	5H	14.000	12.871	0.170	12.135	0.300
			6g	0.038	13.962	0.280	12.663	0.160	11.271	6H	14.000	12.913	0.212	12.210	0.375
			8g	0.038	13.962	0.450	12.663	0.250	11.181	7H	14.000	12.966	0.265	12.310	0.475
			4h	0	16.000	0.150	15.026	0.090	14.012	5H	16.000	15.176	0.150	14.612	0.236
		1.5	6g	0.032	15.968	0.236	14.994	0.140	13.930	6H	16.000	15.216	0.190	14.676	0.300
16			8g	0.032	15.968	0.375	14.994	0.224	13.846	7H	16.000	15.262	0.236	14.751	0.375
	2		4h	0	16.000	0.180	14.701	0.100	13.369	5H	16.000	14.871	0.170	14.135	0.300
			6g	0.038	15.962	0.280	14.663	0.160	13.271	6H	16.000	14.913	0.212	14.210	0.375
			8g	0.038	15.962	0.450	14.663	0.250	13.181	7H	16.000	14.966	0.265	14.310	0.475
			4h	0	18.000	0.150	17.026	0.090	16.012	5H	18.000	17.176	0.150	16.612	0.236
		1.5	6g	0.032	17.968	0.236	16.994	0.140	15.930	6H	18.000	17.216	0.190	16.676	0.300
18			8g	0.032	17.968	0.375	16.994	0.224	15.846	7H	18.000	17.262	0.236	16.751	0.375
	2.5		4h	0	18.000	0.212	16.376	0.106	14.730	5H	18.000	16.556	0.180	15.649	0.355
			6g	0.042	17.958	0.335	16.334	0.170	14.624	6H	18.000	16.600	0.224	15.774	0.450
			8g	0.042	17.958	0.530	16.334	0.265	14.529	7H	18.000	16.656	0.280	15.854	0.560
			4h	0	20.000	0.150	19.026	0.090	18.012	5H	20.000	19.176	0.150	18.612	0.236
		1.5	6g	0.032	19.968	0.236	18.994	0.140	17.930	6H	20.000	0.190	0.190	18.676	0.300
20			8g	0.032	19.968	0.375	18.994	0.224	17.846	7H	20.000	19.262	0.236	18.751	0.375
	2.5		4h	0	20.000	0.212	18.376	0.106	16.730	5H	20.000	18.556	0.180	17.649	0.355
			6g	0.042	19.958	0.335	18.334	0.170	16.624	6H	20.000	18.600	0.224	17.744	0.450
			8g	0.042	19.958	0.530	18.334	0.265	16.529	7H	20.000	18.650	0.280	17.854	0.560
			4h	0	22.000	0.150	21.026	0.090	20.012	5H	22.000	21.176	0.150	20.612	0.236
		1.5	6g	0.032	21.968	0.236	20.994	0.140	19.930	6H	22.000	21.216	0.190	20.676	0.300
22			8g	0.032	21.968	0.375	20.994	0.224	19.846	7H	22.000	21.262	0.236	20.751	0.375
	2.5		4h	0	22.000	0.212	20.376	0.106	18.730	5H	22.000	20.556	0.180	19.649	0.335
			6g	0.042	21.958	0.335	20.334	0.170	18.624	6H	22.000	20.600	0.224	19.744	0.450
			8g	0.042	21.958	0.530	20.334	0.265	18.529	7H	22.000	20.656	0.280	19.854	0.560
			4h	0	24.000	0.180	22.701	0.106	21.363	5H	24.000	22.881	0.180	22.135	0.300
		2	6g	0.038	23.962	0.280	22.663	0.170	21.261	6H	24.000	22.925	0.224	22.210	0.375
24			8g	0.038	23.962	0.450	22.663	0.265	21.166	7H	24.000	22.981	0.280	22.310	0.475
			4h	0	24.000	0.236	22.051	0.125	20.078	5H	24.000	22.263	0.212	21.152	0.400
	3		6g	0.048	23.952	0.375	22.003	0.200	19.955	6H	24.000	22.316	0.265	21.252	0.500
			8g	0.048	23.952	0.600	22.003	0.315	19.840	7H	24.000	22.386	0.335	21.382	0.630
			4h	0	27.000	0.180	25.701	0.106	24.363	5H	27.000	25.881	0.180	25.135	0.300
		2	6g	0.038	26.962	0.280	25.663	0.170	24.261	6H	27.000	25.925	0.224	25.210	0.375
27			8g	0.038	26.962	0.450	25.663	0.265	24.166	7H	27.000	25.981	0.280	25.310	0.475
	3		4h	0	27.000	0.236	25.051	0.125	23.078	5H	27.000	25.263	0.212	24.152	0.400
			6g	0.048	26.952	0.375	25.003	0.200	22.955	6H	27.000	25.316	0.265	24.252	0.500
			8g	0.048	26.952	0.600	25.003	0.315	22.840	7H	27.000	25.386	0.335	24.382	0.630

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ***(Continued)*** **British Standard ISO Metric Screw Threads: Limits and Tolerances for Finished Uncoated Threads for Normal Lengths of Engagement** *BS 3643: Part 2: 1981*

Nominal Diameter[a]	Pitch		External Threads (Bolts)							Internal Threads (Nuts)[b]					
					Major Dia.		Pitch Dia.		Minor Dia		Major Dia.	Pitch Dia.		Minor Dia	
	Coarse	Fine	Tol. Class	Fund dev.	Max	Tol(−)	Max	Tol(−)	Min	Tol. Class	Min	Max	Tol(−)	Max	Tol(−)
30		2	4h	0	30.000	0.180	28.701	0.106	27.363	5H	30.000	28.881	0.180	28.135	0.300
			6g	0.038	29.962	0.280	28.663	0.170	27.261	6H	30.000	27.925	0.224	28.210	0.375
			8g	0.038	29.962	0.450	28.663	0.265	27.166	7H	30.000	28.981	0.280	28.310	0.475
	3.5		4h	0	30.000	0.265	27.727	0.132	25.439	5H	30.000	27.951	0.224	26.661	0.450
			6g	0.053	29.947	0.425	27.674	0.212	25.305	6H	30.000	28.007	0.280	26.771	0.560
			8g	0.053	29.947	0.670	27.674	0.335	25.183	7H	30.000	28.082	0.355	26.921	0.710
33		2	4h	0	33.000	0.180	31.701	0.106	30.363	5H	33.000	31.881	0.180	31.135	0.300
			6g	0.038	32.962	0.280	31.663	0.170	30.261	6H	33.000	31.925	0.224	31.210	0.375
			8g	0.038	32.962	0.450	30.663	0.265	30.166	7H	33.000	31.981	0.280	31.310	0.475
	3.5		4h	0	33.000	0.265	30.727	0.132	28.438	5H	33.000	30.951	0.224	29.661	0.450
			6g	0.053	32.947	0.425	30.674	0.212	28.305	6H	33.000	31.007	0.280	29.771	0.560
			8g	0.053	32.947	0.670	30.674	0.335	28.182	7H	33.000	31.082	0.355	29.921	0.710
36	4		4h	0	36.000	0.300	33.402	0.140	30.798	5H	36.000	33.638	0.236	32.145	0.475
			6g	0.060	35.940	0.475	33.342	0.224	30.654	6H	36.000	33.702	0.300	32.270	0.600
			8g	0.060	35.940	0.750	33.342	0.355	30.523	7H	36.000	33.777	0.375	32.420	0.750
39	4		4h	0	39.000	0.300	36.402	0.140	33.798	5H	39.000	36.638	0.236	35.145	0.475
			6g	0.060	38.940	0.475	36.342	0.224	33.654	6H	39.000	36.702	0.300	35.270	0.600
			8g	0.060	38.940	0.750	36.342	0.355	33.523	7H	39.000	36.777	0.375	35.420	0.750

[a] This table provides coarse- and fine-pitch series data for threads listed in Table 6 for first, second, and third choices. For constant-pitch series and for larger sizes than are shown, refer to the Standard.

[b] The fundamental deviation for internal threads (nuts) is zero for threads in this table.

All dimensions are in millimeters.

Diameter/Pitch Combinations.— Part 1 of BS 3643 provides a choice of diameter/pitch combinations shown here in Table 6. The use of first-choice items is preferred but if necessary, second, then third choice combinations may be selected. If pitches finer than those given in Table 6 are necessary, only the following pitches should be used: 3, 2, 1.5, 1, 0.75, 0.5, 0.35, 0.25, and 0.2 mm. When selecting such pitches it should be noted that there is increasing difficulty in meeting tolerance requirements as the diameter is increased for a given pitch. It is suggested that diameters greater than the following should not be used with the pitches indicated:

Pitch, mm	0.5	0.75	1	1.5	2	3
Maximum Diameter, mm	22	33	80	150	200	300

In cases where it is necessary to use a thread with a pitch larger than 6 mm, in the diameter range of 150 to 300 mm, the 8 mm pitch should be used.

Limits and Tolerances for Finished Uncoated Threads.— Part 2 of BS 3643 specifies the fundamental deviations, tolerances, and limits of size for the tolerance classes 4H, 5H, 6H, and 7H for internal threads (nuts) and 4h, 6g, and 8g for external threads (bolts) for coarse-pitch series within the range of 1 to 68 mm; fine-pitch series within the range of 1 to 33 mm; and constant pitch series within the range of 8 to 300 mm diameter.

The data in Table 5 provide the first, second, and third choice combinations shown in Table 6 except that constant-pitch series threads are omitted. For diameters larger than shown in Table 5, and for constant-pitch series data, refer to the Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. British Standard ISO Metric Screw Threads — Diameter/Pitch Combinations *BS 3643:Part 1:1981 (1998)*

Nominal Diameter Choices			Coarse Pitch	Fine Pitch	Constant Pitch	Nominal Diameter Choices			Constant Pitch
1st	2nd	3rd				1st	2nd	3rd	
1	…	…	0.25	0.2	…	…	…	70	6, 4, 3, 2, 1.5
…	1.1	…	0.25	0.2	…	72	…	…	6, 4, 3, 2, 1.5
1.2	…	…	0.25	0.2	…	…	…	75	4, 3, 2, 1.5
…	1.4	…	0.3	0.2	…	…	76	…	6, 4, 3, 2, 1.5
1.6	…	…	0.35	0.2	…	…	…	78	2
…	1.8	…	0.35	0.2	…	80	…	…	6, 4, 3, 2, 1.5
2.0	…	…	0.4	0.25	…	…	…	82	2
…	2.2	…	0.45	0.25	…	…	85	…	6, 4, 3, 2
2.5	…	…	0.45	0.35	…	90	…	…	6, 4, 3, 2
3	…	…	0.5	0.35	…	…	95	…	6, 4, 3, 2
…	3.5	…	0.6	0.35	…	100	…	…	6, 4, 3, 2
4	…	…	0.7	0.5	…	…	105	…	6, 4, 3, 2
…	4.5	…	0.75	0.5	…	110	…	…	6, 4, 3, 2
5	…	…	0.8	0.5	…	…	115	…	6, 4, 3, 2
…	…	5.5	…	(0.5)	…	…	120	…	6, 4, 3, 2
6	…	…	1	0.75	…	125	…	…	6, 4, 3, 2
…	7	…	1	0.75	…	…	130	…	6, 4, 3, 2
8	…	…	1.25	1	0.75	…	…	135	6, 4, 3, 2
…	…	9	1.25	…	1, 0.75	140	…	…	6, 4, 3, 2
10	…	…	1.5	1.25	1, 0.75	…	…	145	6, 4, 3, 2
…	…	11	1.5	…	1, 0.75	…	150	…	6, 4, 3, 2
12	…	…	1.75	1.25	1.5, 1	…	…	155	6, 4, 3
…	14	…	2	1.5	1.25[a], 1	160	…	…	6, 4, 3
…	…	15	…	…	1.5, 1	…	…	165	6, 4, 3
16	…	…	2	1.5	1	…	170	…	6, 4, 3
…	…	17	…	…	1.5, 1	…	…	175	6, 4, 3
…	18	…	2.5	1.5	2, 1	180	…	…	6, 4, 3
20	…	…	2.5	1.5	2, 1	…	…	185	6, 4, 3
…	22	…	2.5	1.5	2, 1	…	190	…	6, 4, 3
24	…	…	3	2	1.5, 1	…	…	195	6, 4, 3
…	…	25	…	…	2, 1.5, 1	200	…	…	6, 4, 3
…	…	26	…	…	1.5	…	…	205	6, 4, 3
…	27	…	3	2	1.5, 1	…	210	…	6, 4, 3
…	…	28	…	…	2, 1.5, 1	…	…	215	6, 4, 3
30	…	…	3.5	2	(3), 1.5, 1	220	…	…	6, 4, 3
…	…	32	…	…	2, 1.5	…	…	225	6, 4, 3
…	33	…	3.5	2	(3), 1.5	…	…	230	6, 4, 3
…	…	35[b]	…	…	1.5	…	…	235	6, 4, 3
36	…	…	4	…	3, 2, 1.5	…	240	…	6, 4, 3
…	…	38	…	…	1.5	…	…	245	6, 4, 3
…	39	…	4	…	3, 2, 1.5	250	…	…	6, 4, 3
…	…	40	…	…	3, 2, 1.5	…	…	255	6, 4
42	45	…	4.5	…	4, 3, 2, 1.5	…	260	…	6, 4
48	…	…	5	…	4, 3, 2, 1.5	…	…	265	6, 4
…	…	50	…	…	3, 2, 1.5	…	…	270	6, 4
…	52	…	5	…	4, 3, 2, 1.5	…	…	275	6, 4
…	…	55	…	…	4, 3, 2, 1.5	280	…	…	6, 4
56	…	…	5.5	…	4, 3, 2, 1.5	…	…	285	6, 4
…	…	58	…	…	4, 3, 2, 1.5	…	…	290	6, 4
…	60	…	5.5	…	4, 3, 2, 1.5	…	…	295	6, 4
…	…	62	…	…	4, 3, 2, 1.5	…	300	…	6, 4
64	…	…	6	…	4, 3, 2, 1.5	…	…	…	…
…	…	65	…	…	4, 3, 2, 1.5	…	…	…	…
…	68	…	6	…	4, 3, 2, 1.5	…	…	…	…

[a] Only for spark plugs for engines.
[b] Only for locking nuts for bearings.

All dimensions are in millimeters. Pitches in parentheses ( ) are to be avoided as far as possible.

Copyright 2004, Industrial Press, Inc., New York, NY

Comparison of Various Metric Thread Systems

Metric Series Threads — A comparison of Maximum Metal Dimensions of British (*BS 1095*), French (*NF E03-104*), German (*DIN 13*), and Swiss (*VSM 12003*) Systems

Nominal Size and Major Bolt Diam.	Pitch	Pitch Diam.	Bolt				Nut				
			Minor Diameter				Major Diameter			Minor Diameter	
			British	French	German	Swiss	British & German	French	Swiss	French, German& Swiss	British
6	1	5.350	4.863	4.59	4.700	4.60	6.000	6.108	6.100	4.700	4.863
7	1	6.350	5.863	5.59	5.700	5.60	7.000	7.108	7.100	5.700	5.863
8	1.25	7.188	6.579	6.24	6.376	6.25	8.000	8.135	8.124	6.376	6.579
9	1.25	8.188	7.579	7.24	7.376	7.25	9.000	9.135	9.124	7.376	7.579
10	1.5	9.026	8.295	7.89	8.052	7.90	10.000	10.162	10.150	8.052	8.295
11	1.5	10.026	9.295	8.89	9.052	8.90	11.000	11.162	11.150	9.052	9.295
12	1.75	10.863	10.011	9.54	9.726	9.55	12.000	12.189	12.174	9.726	10.011
14	2	12.701	11.727	11.19	11.402	11.20	14.000	14.216	14.200	11.402	11.727
16	2	14.701	13.727	13.19	13.402	13.20	16.000	16.216	16.200	13.402	13.727
18	2.5	16.376	15.158	14.48	14.752	14.50	18.000	18.270	18.250	14.752	15.158
20	2.5	18.376	17.158	16.48	16.752	16.50	20.000	20.270	20.250	16.752	17.158
22	2.5	20.376	19.158	18.48	18.752	18.50	22.000	22.270	22.250	18.752	19.158
24	3	22.051	20.590	19.78	20.102	19.80	24.000	24.324	24.300	20.102[a]	20.590
27	3	25.051	23.590	22.78	23.102	22.80	27.000	27.324	27.300	23.102[b]	23.590
30	3.5	27.727	26.022	25.08	25.454	25.10	30.000	30.378	30.350	25.454	26.022
33	3.5	30.727	29.022	28.08	28.454	28.10	33.000	33.378	33.350	28.454	29.022
36	4	33.402	31.453	30.37	30.804	30.40	36.000	36.432	36.400	30.804	31.453
39	4	36.402	34.453	33.37	33.804	33.40	39.000	39.432	39.400	33.804	34.453
42	4.5	39.077	36.885	35.67	36.154	35.70	42.000	42.486	42.450	36.154	36.885
45	4.5	42.077	39.885	38.67	39.154	38.70	45.000	45.486	45.450	39.154	39.885
48	5	41.752	42.316	40.96	41.504	41.00	48.000	48.540	48.500	41.504	42.316
52	5	48.752	46.316	44.96	45.504	45.00	52.000	52.540	52.500	45.504	46.316
56	5.5	52.428	49.748	48.26	48.856	48.30	56.000	56.594	56.550	48.856	49.748
60	5.5	56.428	53.748	52.26	52.856	52.30	60.000	60.594	60.550	52.856	53.748

[a] The value shown is given in the German Standard; the value in the French Standard is 20.002; and in the Swiss Standard, 20.104.

[b] The value shown is given in the German Standard; the value in the French Standard is 23.002; and in the Swiss Standard, 23.104.

All dimensions are in mm.

Copyright 2004, Industrial Press, Inc., New York, NY

ACME SCREW THREADS

American National Standard Acme Screw Threads

This American National Standard ASME/ANSI B1.5-1997 is a revision of American Standard ANSI B1.5-1988 and provides for two general applications of Acme threads, namely, General Purpose and Centralizing.

The limits and tolerances in this standard relate to single-start Acme threads, and may be used, if considered suitable, for multi-start Acme threads, which provide fast relative traversing motion when this is necessary. For information on additional allowances for multi-start Acme threads, see later section on page 1827.

General Purpose Acme Threads.— Three classes of General Purpose threads, 2G, 3G, and 4G, are provided in the standard, each having clearance on all diameters for free movement, and may be used in assemblies with the internal thread rigidly fixed and movement of the external thread in a direction perpendicular to its axis limited by its bearing or bearings. It is suggested that external and internal threads of the same class be used together for general purpose assemblies, Class 2G being the preferred choice. If less backlash or end play is desired, Classes 3G and 4G are provided. Class 5G is not recommended for new designs.

Thread Form: The accompanying Fig. 1 shows the thread form of these General Purpose threads, and the formulas accompanying the figure determine their basic dimensions. Table 1 gives the basic dimensions for the most generally used pitches.

Angle of Thread: The angle between the sides of the thread, measured in an axial plane, is 29 degrees. The line bisecting this 29-degree angle shall be perpendicular to the axis of the screw thread.

Thread Series: A series of diameters and associated pitches is recommended in the Standard as preferred. These diameters and pitches have been chosen to meet present needs with the fewest number of items in order to reduce to a minimum the inventory of both tools and gages. This series of diameters and associated pitches is given in Table 3.

Chamfers and Fillets: General Purpose external threads may have the crest corner chamfered to an angle of 45 degrees with the axis to a maximum width of $P/15$, where P is the pitch. This corresponds to a maximum depth of chamfer fiat of $0.0945P$.

Basic Diameters: The max major diameter of the external thread is basic and is the nominal major diameter for all classes. The min pitch diameter of the internal thread is basic and is equal to the basic major diameter minus the basic height of the thread, h. The basic minor diameter is the min minor diameter of the internal thread. It is equal to the basic major diameter minus twice the basic thread height, $2h$.

Length of Engagement: The tolerances specified in this standard are applicable to lengths of engagement not exceeding twice the nominal major diameter.

Major and Minor Diameter Allowances: A minimum diametral clearance is provided at the minor diameter of all external threads by establishing the maximum minor diameter 0.020 inch below the basic minor diameter of the nut for pitches of 10 threads per inch and coarser, and 0.10 inch for finer pitches. A minimum diametral clearance at the major diameter is obtained by establishing the minimum major diameter of the internal thread 0.020 inch above the basic major diameter of the screw for pitches of 10 threads per inch and coarser, and 0.010 inch for finer pitches.

Major and Minor Diameter Tolerances: The tolerance on the external thread major diameter is $0.05P$, where P is the pitch, with a minimum of 0.005 inch. The tolerance on the internal thread major diameter is 0.020 inch for 10 threads per inch and coarser and 0.010 for finer pitches. The tolerance on the external thread minor diameter is $1.5 \times$ pitch diameter tolerance. The tolerance on the internal thread minor diameter is $0.05P$ with a minimum of 0.005 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI General Purpose Acme Thread Form *ASME/ANSI B1.5-1997*, **and Stub Acme Screw Thread Form** *ASME/ANSI B1.8-1988 (R2001)*



Fig. 1. General Purpose and Stub Acme Thread Forms

Formulas for Basic Dimensions of General Purpose and Stub Acme Screw Threads

General Purpose	Stub Acme Threads
Pitch = P = 1 ÷ No. threads per inch, n	Pitch = P = 1 ÷ No. threads per inch, n
Basic thread height $h = 0.5P$	Basic thread height $h = 0.3P$
Basic thread thickness $t = 0.5P$	Basic thread thickness $t = 0.5P$
Basic flat at crest $F_{cn} = 0.3707P$ (internal thread)	Basic flat at crest $F_{cn} = 0.4224P$ (internal thread)
Basic flat at crest $F_{cs} = 0.3707P - 0.259 \times$ (pitch dia. allowance on ext. thd.)	Basic flat at crest $F_{cs} = 0.4224P - 0.259 \times$ (pitch dia. allowance on ext. thread)
$F_{rn} = 0.3707P - 0.259 \times$ (major dia. allowance on internal thread)	$F_{rn} = 0.4224P - 0.259 \times$ (major dia. allowance on internal thread)
$F_{rs} = 0.3707P - 0.259 \times$ (minor dia. allowance on ext. thread − pitch dia. allowance on ext. thread)	$F_{rs} = 0.4224P - 0.259 \times$ (minor dia. allowance on ext. thread − pitch dia. allowance on ext. thread)

Pitch Diameter Allowances and Tolerances: Allowances on the pitch diameter of General Purpose Acme threads are given in Table 4. Pitch diameter tolerances are given in Table 5. The ratios of the pitch diameter tolerances of Classes 2G, 3G, and 4G, General Purpose threads are 3.0, 1.4, and 1, respectively.

An increase of 10 per cent in the allowance is recommended for each inch, or fraction thereof, that the length of engagement exceeds two diameters.

Application of Tolerances: The tolerances specified are designed to ensure interchangeability and maintain a high grade of product. The tolerances on diameters of the internal thread are plus, being applied from minimum sizes to above the minimum sizes. The tolerances on diameters of the external thread are minus, being applied from the maximum sizes to below the maximum sizes. The pitch diameter (or thread thickness) tolerances for an external or internal thread of a given class are the same. The thread thickness tolerance is 0.259 times the pitch diameter tolerance.

Copyright 2004, Industrial Press, Inc., New York, NY

Limiting Dimensions: Limiting dimensions of General Purpose Acme screw threads in the recommended series are given in Table 2b. These limits are based on the formulas in Table 2a.

For combinations of pitch and diameter other than those in the recommended series, the formulas in Table 2a and the data in Tables 4 and 5 make it possible to readily determine the limiting dimensions required.

A diagram showing the disposition of allowances, tolerances, and crest clearances for General Purpose Acme threads appears on page 1826.

Stress Area of General Purpose Acme Threads: For computing the tensile strength of the thread section, the minimum stress area based on the mean of the minimum pitch diameter d_2 min. and the minimum minor diameter d_1 max. of the external thread is used:

$$\text{Stress Area} = 3.1416\left(\frac{d_2 \text{ min.} + d_1 \text{ max.}}{4}\right)^2$$

where d_2 min. and d_1 max. may be computed by Formulas 4 and 6, Table 2a or taken from Table 2b.

Shear Area of General Purpose Acme Threads: For computing the shear area per inch length of engagement of the external thread, the maximum minor diameter of the internal thread D_1 max., and the minimum pitch diameter of the external thread D_2 min., Table 2b or Formulas 12 and 4, Table 2a, are used:

$$\text{Shear Area} = 3.1416 D_1 \text{ max.} [0.5 + n \tan 14\tfrac{1}{2}^\circ (D_2 \text{ min.} - D_1 \text{ max.})]$$

Acme Thread Abbreviations.— The following abbreviations are recommended for use on drawings and in specifications, and on tools and gages:

ACME = Acme threads
G = General Purpose
C = Centralizing
P = pitch
L = lead
LH = left hand

Designation of General Purpose Acme Threads.— The examples listed below are given here to show how General Purpose Acme threads are designated on drawings and tools:

1.750-4 ACME-2G indicates a General Purpose Class 2G Acme thread of 1.750-inch major diameter, 4 threads per inch, single thread, right hand. The same thread, but left hand, is designated 1.750-4 ACME-2G-LH.

2.875-0.4*P*-0.8*L*-ACME-3G indicates a General Purpose Class 3G Acme thread of 2.875-inch major diameter, pitch 0.4 inch, lead 0.8 inch, double thread, right hand.

Multiple Start Acme Threads.— The tabulated diameter-pitch data with allowances and tolerances relate to single-start threads. These data, as tabulated, may be and often are used for two-start Class 2G threads but this usage generally requires reduction of the full working tolerances to provide a greater allowance or clearance zone between the mating threads to assure satisfactory assembly.

When the class of thread requires smaller working tolerances than the 2G class or when threads with 3, 4, or more starts are required, some additional allowances or increased tolerances or both may be needed to ensure adequate working tolerances and satisfactory assembly of mating parts.

It is suggested that the allowances shown in Table 4 be used for all external threads and that allowances be applied to internal threads in the following ratios: for two-start threads, 50 per cent of the allowances shown in the Class 2G, 3G and 4G columns of Table 4; for

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard General Purpose Acme Screw Thread Form — Basic Dimensions *ASME/ANSI B1.5-1997*

Thds. per Inch n	Pitch, $P = 1/n$	Height of Thread (Basic), $h = P/2$	Total Height of Thread, $h_s = P/2 + ½$ allowance[a]	Thread Thickness (Basic), $t = P/2$	Width of Flat	
					Crest of Internal Thread (Basic), $F_{cn} = 0.3707P$	Root of Internal Thread, F_{rn} $0.3707P - 0.259 \times$ allowance[a]
16	0.06250	0.03125	0.0362	0.03125	0.0232	0.0206
14	0.07143	0.03571	0.0407	0.03571	0.0265	0.0239
12	0.08333	0.04167	0.0467	0.04167	0.0309	0.0283
10	0.010000	0.05000	0.0600	0.05000	0.0371	0.0319
8	0.12500	0.06250	0.0725	0.06250	0.0463	0.0411
6	0.16667	0.08333	0.0933	0.08333	0.0618	0.0566
5	0.20000	0.10000	0.1100	0.10000	0.0741	0.0689
4	0.25000	0.12500	0.1350	0.12500	0.0927	0.0875
3	0.33333	0.16667	0.1767	0.16667	0.1236	0.1184
2½	0.40000	0.20000	0.2100	0.20000	0.1483	0.1431
2	0.50000	0.25000	0.2600	0.25000	0.1853	0.1802
1½	0.66667	0.33333	0.3433	0.33333	0.2471	0.2419
1⅓	0.75000	0.37500	0.3850	0.37500	0.2780	0.2728
1	1.00000	0.50000	0.5100	0.50000	0.3707	0.3655

All dimensions are in inches.

[a] Allowance is 0.020 inch for 10 threads per inch and coarser, and 0.010 inch for finer threads.

Table 2a. American National Standard General Purpose Acme Single-Start Screw Threads — Formulas for Determining Diameters *ASME/ANSI B1.5-1997*

D = Basic Major Diameter and Nominal Size, in Inches.

P = Pitch = 1 ÷ Number of Threads per Inch.

E = Basic Pitch Diameter = $D - 0.5P$

K = Basic Minor Diameter = $D - P$

No.	External Threads (Screws)
1	Major Dia., Max. = D
2	Major Dia., Min. = D *minus* $0.05P$[a] but not less than 0.005.
3	Pitch Dia., Max. = E *minus* allowance from Table 4.
4	Pitch Dia., Min. = Pitch Dia., Max. (Formula 3) *minus* tolerance from Table 5.
5	Minor Dia., Max. = K *minus* 0.020 for 10 threads per inch and coarser and 0.010 for finer-pitches.
6	Minor Dia., Min. = Minor Dia., Max. (Formula 5) *minus* 1.5 × pitch diameter tolerance from Table 5.
	Internal Threads (Nuts)
7	Major Dia., Min. = D *plus* 0.020 for 10 threads per inch and coarser and 0.010 for finer pitches.
8	Major Dia., Max. = Major Dia., Min. (Formula 7) *plus* 0.020 for 10 threads per inch and coarser and 0.010 for finer pitches.
9	Pitch Dia., Min. = E
10	Pitch Dia., Max. = Pitch Dia., Min. (Formula 9) *plus* tolerance from Table 5.
11	Minor Dia., Min. = K
12	Minor Dia., Max. = Minor Dia., Min. (Formula 11) *plus* $0.05P$[a] but not less than 0.005.

[a] If P is between two recommended pitches listed in Table 3, use the coarser of the two pitches in this formula instead of the actual value of P.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Limiting Dimensions of ANSI General Purpose Acme Single-Start Screw Threads *ASME/ANSI B1.5-1988*

Nominal Diameter, D		1/4	5/16	3/8	7/16	1/2	5/8	3/4	7/8	1	1 1/8	1 1/4	1 3/8
Threads per Inch[a]		16	14	12	12	10	8	6	6	5	5	5	4
Limiting Diameters		External Threads											
Classes 2G, 3G, and 4G Major Diameter	Max (D)	0.2500	0.3125	0.3750	0.4375	0.5000	0.6250	0.7500	0.8750	1.0000	1.1250	1.2500	1.3750
	Min	0.2450	0.3075	0.3700	0.4325	0.4950	0.6188	0.7417	0.8667	0.9900	1.1150	1.2400	1.3625
Classes 2G, 3G, and 4G Minor Diameter	Max	0.1775	0.2311	0.2817	0.3442	0.3800	0.4800	0.5633	0.6883	0.7800	0.9050	1.0300	1.1050
Class 2G, Minor Diameter	Min	0.1618	0.2140	0.2632	0.3253	0.3594	0.4570	0.5372	0.6615	0.7509	0.8753	0.9998	1.0720
Class 3G, Minor Diameter	Min	0.1702	0.2231	0.2730	0.3354	0.3704	0.4693	0.5511	0.6758	0.7664	0.8912	1.0159	1.0896
Class 4G, Minor Diameter	Min	0.1722	0.2254	0.2755	0.3379	0.3731	0.4723	0.5546	0.6794	0.7703	0.8951	1.0199	1.0940
Class 2G, Pitch Diameter	Max	0.2148	0.2728	0.3284	0.3909	0.4443	0.5562	0.6598	0.7842	0.8920	1.0165	1.1411	1.2406
	Min	0.2043	0.2614	0.3161	0.3783	0.4306	0.5408	0.6424	0.7663	0.8726	0.9967	1.1210	1.2188
Class 3G, Pitch Diameter	Max	0.2158	0.2738	0.3296	0.3921	0.4458	0.5578	0.6615	0.7861	0.8940	1.0186	1.1433	1.2430
	Min	0.2109	0.2685	0.3238	0.3862	0.4394	0.5506	0.6534	0.7778	0.8849	1.0094	1.1339	1.2327
Class 4G, Pitch Diameter	Max	0.2168	0.2748	0.3309	0.3934	0.4472	0.5593	0.6632	0.7880	0.8960	1.0208	1.1455	1.2453
	Min	0.2133	0.2710	0.3268	0.3892	0.4426	0.5542	0.6574	0.7820	0.8895	1.0142	1.1388	1.2380
		Internal Threads											
Classes 2G, 3G, and 4G Major Diameter	Min	0.2600	0.3225	0.3850	0.4475	0.5200	0.6450	0.7700	0.8950	1.0200	1.1450	1.2700	1.3950
	Max	0.2700	0.3325	0.3950	0.4575	0.5400	0.6650	0.7900	0.9150	1.0400	1.1650	1.2900	1.4150
Classes 2G, 3G, and 4G Minor Diameter	Min	0.1875	0.2411	0.2917	0.3542	0.4000	0.5000	0.5833	0.7083	0.8000	0.9250	1.0500	1.1250
	Max	0.1925	0.2461	0.2967	0.3592	0.4050	0.5062	0.5916	0.7166	0.8100	0.9350	1.0600	1.1375
Class 2G, Pitch Diameter	Min	0.2188	0.2768	0.3333	0.3958	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500
	Max	0.2293	0.2882	0.3456	0.4084	0.4637	0.5779	0.6841	0.8096	0.9194	1.0448	1.1701	1.2720
Class 3G, Pitch Diameter	Min	0.2188	0.2768	0.3333	0.3958	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500
	Max	0.2237	0.2821	0.3391	0.4017	0.4564	0.5697	0.6748	0.8000	0.9091	1.0342	1.1594	1.2603
Class 4G, Pitch Diameter	Min	0.2188	0.2768	0.3333	0.3958	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500
	Max	0.2223	0.2806	0.3374	0.4000	0.4546	0.5676	0.6725	0.7977	0.9065	1.0316	1.1567	1.2573

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. ***(Continued)*** **Limiting Dimensions of ANSI General Purpose Acme Single-Start Screw Threads ASME/ANSI B1.5-1988**

Nominal Diameter, *D*		1½	1¾	2	2¼	2½	2¾	3	3½	4	4½	5
Threads per Inch[a]		4	4	4	3	3	3	2	2	2	2	2
Limiting Diameters		External Threads										
Classes 2G, 3G, and 4G Major Diameter	Max (*D*)	1.5000	1.7500	2.0000	2.2500	2.5000	2.7500	3.0000	3.5000	4.0000	4.5000	5.0000
	Min	1.4875	1.7375	1.9875	2.2333	2.4833	2.7333	2.9750	3.4750	3.9750	4.4750	4.9750
Classes 2G, 3G, and 4G Minor Diameter	Max	1.2300	1.4800	1.7300	1.8967	2.1467	2.3967	2.4800	2.9800	3.4800	3.9800	4.4800
Class 2G, Minor Diameter	Min	1.1965	1.4456	1.6948	1.8572	2.1065	2.3558	2.4326	2.9314	3.4302	3.9291	4.4281
Class 3G, Minor Diameter	Min	1.2144	1.4640	1.7136	1.8783	2.1279	2.3776	2.4579	2.9574	3.4568	3.9563	4.4558
Class 4G, Minor Diameter	Min	1.2189	1.4686	1.7183	1.8835	2.1333	2.3831	2.4642	2.9638	3.4634	3.9631	4.4627
Class 2G, Pitch Diameter	Max	1.3652	1.6145	1.8637	2.0713	2.3207	2.5700	2.7360	3.2350	3.7340	4.2330	4.7319
	Min	1.3429	1.5916	1.8402	2.0450	2.2939	2.5427	2.7044	3.2026	3.7008	4.1991	4.6973
Class 3G, Pitch Diameter	Max	1.3677	1.6171	1.8665	2.0743	2.3238	2.5734	2.7395	3.2388	3.7380	4.2373	4.7364
	Min	1.3573	1.6064	1.8555	2.0620	2.3113	2.5607	2.7248	3.2237	3.7225	4.2215	4.7202
Class 4G, Pitch Diameter	Max	1.3701	1.6198	1.8693	2.0773	2.3270	2.5767	2.7430	3.2425	3.7420	4.2415	4.7409
	Min	1.3627	1.6122	1.8615	2.0685	2.3181	2.5676	2.7325	3.2317	3.7309	4.2302	4.7294
		Internal Threads										
Classes 2G, 3G, and 4G Major Diameter	Min	1.5200	1.7700	2.0200	2.2700	2.5200	2.7700	3.0200	3.5200	4.0200	4.5200	5.0200
	Max	1.5400	1.7900	2.0400	2.2900	2.5400	2.7900	3.0400	3.5400	4.0400	4.5400	5.0400
Classes 2G, 3G, and 4G Minor Diameter	Min	1.2500	1.5000	1.7500	1.9167	2.1667	2.4167	2.5000	3.0000	3.5000	4.0000	4.5000
	Max	1.2625	1.5125	1.7625	1.9334	2.1834	2.4334	2.5250	3.0250	3.5250	4.0250	4.5250
Class 2G, Pitch Diameter	Min	1.3750	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.3973	1.6479	1.8985	2.1096	2.3601	2.6106	2.7816	3.2824	3.7832	4.2839	4.7846
Class 3G, Pitch Diameter	Min	1.3750	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.3854	1.6357	1.8860	2.0956	2.3458	2.5960	2.7647	3.2651	3.7655	4.2658	4.7662
Class 4G, Pitch Diameter	Min	1.3750	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.3824	1.6326	1.8828	2.0921	2.3422	2.5924	2.7605	3.2608	3.7611	4.2613	4.7615

[a] All other dimensions are given in inches. The selection of threads per inch is arbitrary and for the purpose of establishing a standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. General Purpose Acme Single-Start Screw Thread Data *ASME/ANSI B1.5-1988*

Identification		Basic Diameters			Thread Data							
Nominal Sizes (All Classes)	Threads per Inch,[a] n	Classes 2G, 3G, and 4G			Pitch, P	Thickness at Pitch Line, $t = P/2$	Basic Height of Thread, $h = P/2$	Basic Width of Flat, $F = 0.3707P$	Lead Angle λ at Basic Pitch Diameter[a] Classes 2G, 3G,and 4G		Shear Area[b] Class 3G	Stress Area[c] Class 3G
		Major Diameter, D	Pitch Diameter, $D_2 = D - h$	Minor Diameter, $D_1 = D - 2h$					Deg	Min		
1/4	16	0.2500	0.2188	0.1875	0.06250	0.03125	0.03125	0.0232	5	12	0.350	0.0285
5/16	14	0.3125	0.2768	0.2411	0.07143	0.03571	0.03571	0.0265	4	42	0.451	0.0474
3/8	12	0.3750	0.3333	0.2917	0.08333	0.04167	0.04167	0.0309	4	33	0.545	0.0699
7/16	12	0.4375	0.3958	0.3542	0.08333	0.04167	0.04167	0.0309	3	50	0.660	0.1022
1/2	10	0.5000	0.4500	0.4000	0.10000	0.05000	0.05000	0.0371	4	3	0.749	0.1287
5/8	8	0.6250	0.5625	0.5000	0.12500	0.06250	0.06250	0.0463	4	3	0.941	0.2043
3/4	6	0.7500	0.6667	0.5833	0.16667	0.08333	0.08333	0.0618	4	33	1.108	0.2848
7/8	6	0.8750	0.7917	0.7083	0.16667	0.08333	0.08333	0.0618	3	50	1.339	0.4150
1	5	1.0000	0.9000	0.8000	0.20000	0.10000	0.10000	0.0741	4	3	1.519	0.5354
1 1/8	5	1.1250	1.0250	0.9250	0.20000	0.10000	0.10000	0.0741	3	33	1.751	0.709
1 1/4	5	1.2500	1.1500	1.0500	0.20000	0.10000	0.10000	0.0741	3	10	1.983	0.907
1 3/8	4	1.3750	1.2500	1.1250	0.25000	0.12500	0.12500	0.0927	3	39	2.139	1.059
1 1/2	4	1.5000	1.3750	1.2500	0.25000	0.12500	0.12500	0.0927	3	19	2.372	1.298
1 3/4	4	1.7500	1.6250	1.5000	0.25000	0.12500	0.12500	0.0927	2	48	2.837	1.851
2	4	2.0000	1.8750	1.7500	0.25000	0.12500	0.12500	0.0927	2	26	3.301	2.501
2 1/4	3	2.2500	2.0833	1.9167	0.33333	0.16667	0.16667	0.1236	2	55	3.643	3.049
2 1/2	3	2.5000	2.3333	2.1667	0.33333	0.16667	0.16667	0.1236	2	36	4.110	3.870
2 3/4	3	2.7500	2.5833	2.4167	0.33333	0.16667	0.16667	0.1236	2	21	4.577	4.788
3	2	3.0000	2.7500	2.5000	0.50000	0.25000	0.25000	0.1853	3	19	4.786	5.27
3 1/2	2	3.5000	3.2500	3.0000	0.50000	0.25000	0.25000	0.1853	2	48	5.73	7.50
4	2	4.0000	3.7500	3.5000	0.50000	0.25000	0.25000	0.1853	2	26	6.67	10.12
4 1/2	2	4.5000	4.2500	4.0000	0.50000	0.25000	0.25000	0.1853	2	9	7.60	13.13
5	2	5.0000	4.7500	4.5000	0.50000	0.25000	0.25000	0.1853	1	55	8.54	16.53

[a] All other dimensions are given in inches.

[b] Per inch length of engagement of the external thread in line with the minor diameter crests of the internal thread. Figures given are the minimum shear area based on max D_1 and min d_2.

[c] Figures given are the minimum stress area based on the mean of the minimum minor and pitch diameters of the external thread. See formulas for shear area and stress area on page 1827.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard General Purpose Acme Single-Start Screw Threads — Pitch Diameter Allowances *ASME/ANSI B1.5-1988*

Nominal Size Range[a]		Allowances on External Threads [b]			Nominal Size Range[a]		Allowances on External Threads [b]		
Above	To and Including	Class 2G[c], $0.008\sqrt{D}$	Class 3G, $0.006\sqrt{D}$	Class 4G, $0.004\sqrt{D}$	Above	To and Including	Class 2G[c], $0.008\sqrt{D}$	Class 3G, $0.006\sqrt{D}$	Class 4G, $0.004\sqrt{D}$
0	3/16	0.0024	0.0018	0.0012	1 7/16	1 9/16	0.0098	0.0073	0.0049
3/16	5/16	0.0040	0.0030	0.0020	1 9/16	1 7/8	0.0105	0.0079	0.0052
5/16	7/16	0.0049	0.0037	0.0024	1 7/8	2 1/8	0.0113	0.0085	0.0057
7/16	9/16	0.0057	0.0042	0.0028	2 1/8	2 3/8	0.0120	0.0090	0.0060
9/16	11/16	0.0063	0.0047	0.0032	2 3/8	2 5/8	0.0126	0.0095	0.0063
11/16	13/16	0.0069	0.0052	0.0035	2 5/8	2 7/8	0.0133	0.0099	0.0066
13/16	15/16	0.0075	0.0056	0.0037	2 7/8	3 1/4	0.0140	0.0105	0.0070
15/16	1 1/16	0.0080	0.0060	0.0040	3 1/4	3 3/4	0.0150	0.0112	0.0075
1 1/16	1 3/16	0.0085	0.0064	0.0042	3 3/4	4 1/4	0.0160	0.0120	0.0080
1 3/16	1 5/16	0.0089	0.0067	0.0045	4 1/4	4 3/4	0.0170	0.0127	0.0085
1 5/16	1 7/16	0.0094	0.0070	0.0047	4 3/4	5 1/2	0.0181	0.0136	0.0091

All dimensions in inches. It is recommended that the sizes given in Table 3 be used whenever possible.

[a] The values in columns for Classes 2G, 3G, and 4G are to be used for any size within the nominal size range shown. These values are calculated from the mean of the range.

[b] An increase of 10 per cent in the allowance is recommended for each inch, or fraction thereof, that the length of engagement exceeds two diameters.

[c] Allowances for the 2G Class of thread in this table also apply to American National Standard Stub Acme threads ASME/ANSI B 1.8-1988.

three-start threads, 75 per cent of these allowances; and for four-start threads, 100 per cent of these same values.

These values will provide for a 0.25-16 ACME-2G thread size, 0.002, 0.003, and 0.004 inch additional clearance for 2-, 3-, and 4-start threads, respectively. For a 5-2 ACME-3G thread size the additional clearances would be 0.0091, 0.0136, and 0.0181 inch, respectively. GO thread plug gages and taps would be increased by these same values. To maintain the same working tolerances on multi-start threads, the pitch diameter of the NOT GO thread plug gage would also be increased by these same values.

For multi-start threads with more than four starts, it is believed that the 100 per cent allowance provided by the above procedures would be adequate as index spacing variables would generally be no greater than on a four-start thread.

In general, for multi-start threads of Classes 2G, 3G, and 4G the percentages would be applied, usually, to allowances for the same class, respectively. However, where exceptionally good control over lead, angle, and spacing variables would produce close to theoretical values in the product, it is conceivable that these percentages could be applied to Class 3G or Class 4G allowances used on Class 2G internally threaded product. Also, these percentages could be applied to Class 4G allowances used on Class 3G internally threaded product. It is not advocated that any change be made in externally threaded products.

Designations for gages or tools for internal threads could cover allowance requirements as follows:

GO and NOT GO thread plug gages for: 2.875-0.4*P*-0.8L-ACME-2G with 50 per cent of the 4G internal thread allowance.

Centralizing Acme Threads.— The three classes of Centralizing Acme threads in American National Standard ASME/ANSI B1.5-1988, designated as 2C, 3C, and 4C, have limited clearance at the major diameters of internal and external threads so that a bearing at the major diameters maintains approximate alignment of the thread axis and prevents wedging

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard General Purpose Acme Single-Start Screw Threads — Pitch Diameter Tolerances *ASME/ANSI B1.5-1988*

Nom. Dia.,[a] D	Class of Thread 2G[b]	3G	4G	Nom. Dia.,[a] D	Class of Thread 2G[b]	3G	4G
	Diameter Increment				Diameter Increment		
	$0.006\sqrt{D}$	$0.0028\sqrt{D}$	$0.002\sqrt{D}$		$0.006\sqrt{D}$	$0.0028\sqrt{D}$	$0.002\sqrt{D}$
1/4	.00300	.00140	.00100	1 1/2	.00735	.00343	.00245
5/16	.00335	.00157	.00112	1 3/4	.00794	.00370	.00265
3/8	.00367	.00171	.00122	2	.00849	.00396	.00283
7/16	.00397	.00185	.00132	2 1/4	.00900	.00420	.00300
1/2	.00424	.00198	.00141	2 1/2	.00949	.00443	.00316
5/8	.00474	.00221	.00158	2 3/4	.00995	.00464	.00332
3/4	.00520	.00242	.00173	3	.01039	.00485	.00346
7/8	.00561	.00262	.00187	3 1/2	.01122	.00524	.00374
1	.00600	.00280	.00200	4	.01200	.00560	.00400
1 1/8	.00636	.00297	.00212	4 1/2	.01273	.00594	.00424
1 1/4	.00671	.00313	.00224	5	.01342	.00626	.00447
1 3/8	.00704	.00328	.00235	…	…	…	…

Thds. per Inch[c], n	Class of Thread 2G[b]	3G	4G	Thds. per Inch[c], n	Class of Thread 2G[b]	3G	4G
	Pitch Increment				Pitch Increment		
	$0.030\sqrt{1/n}$	$0.014\sqrt{1/n}$	$0.010\sqrt{1/n}$		$0.030\sqrt{1/n}$	$0.014\sqrt{1/n}$	$0.010\sqrt{1/n}$
16	.00750	.00350	.00250	4	.01500	.00700	.00500
14	.00802	.00374	.00267	3	.01732	.00808	.00577
12	.00866	.00404	.00289	2 1/2	.01897	.00885	.00632
10	.00949	.00443	.00316	2	.02121	.00990	.00707
8	.01061	.00495	.00354	1 1/2	.02449	.01143	.00816
6	.01225	.00572	.00408	1 1/3	.02598	.01212	.00866
5	.01342	.00626	.00447	1	.03000	.01400	.01000

For any particular size of thread, the pitch diameter tolerance is obtained by adding the *diameter increment* from the upper half of the table to the *pitch increment* from the lower half of the table. *Example:* A 1/4-16 Acme-2G thread has a pitch diameter tolerance of 0.00300 + 0.00750 = 0.0105 inch.

The equivalent tolerance on thread thickness is 0.259 times the pitch diameter tolerance.

[a] For a nominal diameter between any two tabulated nominal diameters, use the diameter increment for the larger of the two tabulated nominal diameters.

[b] Columns for the 2G Class of thread in this table also apply to American National Standard Stub Acme threads, ASME/ANSI B1.8-1988 (R2001).

[c] All other dimensions are given in inches.

on the flanks of the thread. An alternative series having centralizing control on the *minor* diameter is described on page 1843. For any combination of the three classes of threads covered in this standard some end play or backlash will result. Classes 5C and 6C are not recommended for new designs.

Application: These three classes together with the accompanying specifications are for the purpose of ensuring the interchangeable manufacture of Centralizing Acme threaded parts. Each user is free to select the classes best adapted to his particular needs. It is suggested that external and internal threads of the same class be used together for centralizing assemblies, Class 2C providing the maximum end play or backlash. If less backlash or end play is desired, Classes 3C and 4C are provided. The requirement for a centralizing fit is that the sum of the major diameter tolerance plus the major diameter allowance on the internal thread, and the major diameter tolerance on the external thread shall equal or be less than the pitch diameter allowance on the external thread. A Class 2C external thread, which has a larger pitch diameter allowance than either a Class 3C or 4C, can be used inter-

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Disposition of Allowances, Tolerances, and Crest Clearances for General Purpose Single-start Acme Threads (All Classes)

changeably with a Class 2C, 3C, or 4C internal thread and fulfill this requirement. Similarly, a Class 3C external thread can be used interchangeably with a Class 3C or 4C internal thread, but only a Class 4C internal thread can be used with a Class 4C external thread.

Thread Form: The thread form is the same as the General Purpose Acme Thread and is shown in Fig. 3. The formulas in Table 7 determine the basic dimensions, which are given in Table 6 for the most generally used pitches.

Angle of Thread: The angle between the sides of the thread measured in an axial plane is 29 degrees. The line bisecting this 29-degree angle shall be perpendicular to the axis of the thread.

Chamfers and Fillets: External threads have the crest corners chamfered at an angle of 45 degrees with the axis to a minimum depth of $P/20$ and a maximum depth of $P/15$. These modifications correspond to a minimum width of chamfer flat of $0.0707P$ and a maximum width of $0.0945P$ (see Table 6, columns 6 and 7).

External threads for Classes 2C, 3C, and 4C may have a fillet at the minor diameter not greater than $0.1P$

Thread Series: A series of diameters and pitches is recommended in the Standard as preferred. These diameters and pitches have been chosen to meet present needs with the few-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Centralizing Acme Screw Thread Form — Basic Dimensions *ASME/ANSI B1.5-1988*

Thds per Inch, n	Pitch, P	Height of Thread (Basic), $h = P/2$	Total Height of Thread (All External Threads) $h_s = h + \frac{1}{2}$ allowance[a]	Thread Thickness (Basic), $t = P/2$	45-Deg Chamfer Crest of External Threads		Max Fillet Radius, Root of Tapped Hole, $0.06P$	Fillet Radius at Min or Diameter of Screws Max (All) $0.10P$
					Min Depth, $0.05P$	Min Width of Chamfer Flat, $0.0707P$		
16	0.06250	0.03125	0.0362	0.03125	0.0031	0.0044	0.0038	0.0062
14	0.07143	0.03571	0.0407	0.03571	0.0036	0.0050	0.0038	0.0071
12	0.08333	0.04167	0.0467	0.04167	0.0042	0.0059	0.0050	0.0083
10	0.10000	0.05000	0.0600	0.05000	0.0050	0.0071	0.0060	0.0100
8	0.12500	0.06250	0.0725	0.06250	0.0062	0.0088	0.0075	0.0125
6	0.16667	0.08333	0.0933	0.08333	0.0083	0.0119	0.0100	0.0167
5	0.20000	0.10000	0.1100	0.10000	0.0100	0.0141	0.0120	0.0200
4	0.25000	0.12500	0.1350	0.12500	0.0125	0.0177	0.0150	0.0250
3	0.33333	0.16667	0.1767	0.16667	0.0167	0.0236	0.0200	0.0333
$2\frac{1}{2}$	0.40000	0.20000	0.2100	0.20000	0.0200	0.0283	0.0240	0.0400
2	0.50000	0.25000	0.2600	0.25000	0.0250	0.0354	0.0300	0.0500
$1\frac{1}{2}$	0.66667	0.33333	0.3433	0.33333	0.0330	0.0471	0.0400	0.0667
$1\frac{1}{3}$	0.75000	0.37500	0.3850	0.37500	0.0380	0.0530	0.0450	0.0750
1	1.00000	0.50000	0.5100	0.50000	0.0500	0.0707	0.0600	0.1000

All dimensions in inches. See Fig. 3.

[a] Allowance is 0.020 inch for 10 or less threads per inch and 0.010 inch for more than 10 threads per inch.



Fig. 3. Centralizing Acme Screw Thread Form

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Formulas for Finding Basic Dimensions of Centralizing Acme Screw Threads

Pitch = $P = 1 \div$ No. threads per inch, n: Basic thread height $h = 0.5P$
Basic thread thickness $t = 0.5P$
Basic flat at crest $F_{cn} = 0.3707P + 0.259 \times$ (minor. diameter allowance on internal threads) (internal thread)
Basic flat at crest $F_{cs} = 0.3707P - 0.259 \times$ (pitch diameter allowance on external thread) (external thread)
$F_{rn} = 0.3707P - 0.259 \times$ (major dia. allowance on internal threads)
$F_{rs} = 0.3707P - 0.259 \times$ (minor dia. allowance on external thread — pitch dia. allowance on external thread)



Fig. 4. Disposition of Allowances, Tolerances, and Crest Clearances for Centralizing Single-Start Acme Threads—Classes 2C, 3C, and 4C

est number of items in order to reduce to a minimum the inventory of both tools and gages. This series of diameters and associated pitches is given in Table 9.

Basic Diameters: The maximum major diameter of the external thread is basic and is the nominal major diameter for all classes.

The minimum pitch diameter of the internal thread is basic for all classes and is equal to the basic major diameter D minus the basic height of thread, h. The minimum minor diameter of the internal thread for all classes is $0.1P$ above basic.

Length of Engagement: The tolerances specified in this Standard are applicable to lengths of engagement not exceeding twice the nominal major diameter.

Pitch Diameter Allowances: Allowances applied to the pitch diameter of the external thread for all classes are given in Table 10.

Major and Minor Diameter Allowances: A minimum diametral clearance is provided at the minor diameter of all external threads by establishing the maximum minor diameter 0.020 inch below the basic minor diameter for 10 threads per inch and coarser, and 0.010 inch for finer pitches and by establishing the minimum minor diameter of the internal thread $0.1P$ greater than the basic minor diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8a. American National Standard Centralizing Acme Single-Start Screw Threads — Formulas for Determining Diameters *ASME/ANSI B1.5-1988*

D = Nominal Size or Diameter in Inches P = Pitch = 1 ÷ Number of Threads per Inch	
No.	Classes 2C, 3C, and 4C External Threads (Screws)
1	Major Dia., Max = *D* (Basic).
2	Major Dia., Min = *D minus* tolerance from Table 12, columns 7, 8, or 10.
3	Pitch Dia., Max = Int. Pitch Dia., Min (Formula 9) *minus* allowance from the appropriate Class 2C, 3C, or 4C column of Table 10.
4	Pitch Dia., Min = Ext. Pitch Dia., Max (Formula 3) *minus* tolerance from Table 11.
5	Minor Dia., Max = *D minus P minus* allowance from Table 12, column 3.
6	Minor Dia., Min = Ext. Minor Dia., Max (Formula 5) *minus* 1.5 × Pitch Dia. tolerance from Table 11.
	Classes 2C, 3C, and 4C Internal Threads (Nuts)
7	Major Dia., Min = *D plus* allowance from Table 12, column 4.
8	Major Dia., Max = Int. Major Dia., Min (Formula 7) *plus* tolerance from Table 12, columns 7, 9, or 11.
9	Pitch Dia., Min = *D minus P*/2 (Basic).
10	Pitch Dia., Max = Int. Pitch Dia., Min (Formula 9) *plus* tolerance from Table 11.
11	Minor Dia., Min = *D minus* 0.9*P*.
12	Minor Dia., Max = Int. Minor Dia., Min (Formula 11) *plus* tolerance from Table 12, column 6.

A minimum diametral clearance at the major diameter is obtained by establishing the minimum major diameter of the internal thread $0.001\sqrt{D}$ above the basic major diameter. These allowances are shown in Table 12.

Major and Minor Diameter Tolerances: The tolerances on the major and minor diameters of the external and internal threads are listed in Table 12 and are based upon the formulas given in the column headings.

An increase of 10 per cent in the allowance is recommended for each inch or fraction thereof that the length of engagement exceeds two diameters.

For information on gages for Centralizing Acme threads the Standard ASME/ANSI B1.5 should be consulted.

Pitch Diameter Tolerances: Pitch diameter tolerances for Classes 2C, 3C and 4C for various practicable combinations of diameter and pitch are given in Table 11. The ratios of the pitch diameter tolerances of Classes 2C, 3C, and 4C are 3.0, 1.4, and 1, respectively.

Application of Tolerances: The tolerances specified are such as to insure interchangeability and maintain a high grade of product. The tolerances on the diameters of internal threads are plus, being applied from the minimum sizes to above the minimum sizes. The tolerances on the diameters of external threads are minus, being applied from the maximum sizes to below the maximum sizes. The pitch diameter tolerances for an external or internal thread of a given class are the same

Limiting Dimensions: Limiting dimensions for Centralizing Acme threads in the preferred series of diameters and pitches are given in Tables 8b and 8c. These limits are based on the formulas in Table 8a.

For combinations of pitch and diameter other than those in the preferred series the formulas in Tables 8b and 8c and the data in the tables referred to therein make it possible to readily determine the limiting dimension required.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8b. Limiting Dimensions of American National Standard Centralizing Acme Single-Start Screw Threads, Classes 2C, 3C, and 4C *ASME/ANSI B1.5-1988*

Nominal Diameter, *D*		1/2	5/8	3/4	7/8	1	1 1/8	1 1/4	1 3/8	1 1/2
Threads per Inch[a]		10	8	6	6	5	5	5	4	4
Limiting Diameters		**External Threads**								
Classes 2C, 3C, and 4C, Major Diameter	Max	0.5000	0.6250	0.7500	0.8750	1.0000	1.1250	1.2500	1.3750	1.5000
Class 2C, Major Diameter	Min	0.4975	0.6222	0.7470	0.8717	0.9965	1.1213	1.2461	1.3709	1.4957
Class 3C, Major Diameter	Min	0.4989	0.6238	0.7487	0.8736	0.9985	1.1234	1.2483	1.3732	1.4982
Class 4C, Major Diameter	Min	0.4993	0.6242	0.7491	0.8741	0.9990	1.1239	1.2489	1.3738	1.4988
Classes 2C, 3C, and 4C, Minor Diameter	Max	0.3800	0.4800	0.5633	0.6883	0.7800	0.9050	1.0300	1.1050	1.2300
Class 2C, Minor Diameter	Min	0.3594	0.4570	0.5371	0.6615	0.7509	0.8753	0.9998	1.0719	1.1965
Class 3C, Minor Diameter	Min	0.3704	0.4693	0.5511	0.6758	0.7664	0.8912	1.0159	1.0896	1.2144
Class 4C, Minor Diameter	Min	0.3731	0.4723	0.5546	0.6794	0.7703	0.8951	1.0199	1.0940	1.2188
Class 2C, Pitch Diameter	Max	0.4443	0.5562	0.6598	0.7842	0.8920	1.0165	1.1411	1.2406	1.3652
	Min	0.4306	0.5408	0.6424	0.7663	0.8726	0.9967	1.1210	1.2186	1.3429
Class 3C, Pitch Diameter	Max	0.4458	0.5578	0.6615	0.7861	0.8940	1.0186	1.1433	1.2430	1.3677
	Min	0.4394	0.5506	0.6534	0.7778	0.8849	1.0094	1.1339	1.2327	1.3573
Class 4C, Pitch Diameter	Max	0.4472	0.5593	0.6632	0.7880	0.8960	1.0208	1.1455	1.2453	1.3701
	Min	0.4426	0.5542	0.6574	0.7820	0.8895	1.0142	1.1388	1.2380	1.3627
		Internal Threads								
Classes 2C, 3C, and 4C, Major Diameter	Min	0.5007	0.6258	0.7509	0.8759	1.0010	1.1261	1.2511	1.3762	1.5012
Classes 2C and 3C, Major Diameter	Max	0.5032	0.6286	0.7539	0.8792	1.0045	1.1298	1.2550	1.3803	1.5055
Class 4C, Major Diameter	Max	0.5021	0.6274	0.7526	0.8778	1.0030	0.1282	1.2533	1.3785	1.5036
Classes 2C, 3C, and 4C, Minor Diameter	Min	0.4100	0.5125	0.6000	0.7250	0.8200	0.9450	0.0700	1.1500	1.2750
	Max	0.04150	0.5187	0.6083	0.7333	0.8300	0.9550	1.0800	1.1625	1.2875
Class 2C, Pitch Diameter	Min	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500	1.3750
	Max	0.4637	0.5779	0.6841	0.8096	0.9194	1.0448	1.1701	1.2720	1.3973
Class 3C, Pitch Diameter	Min	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500	1.3750
	Max	0.4564	0.5697	0.6748	0.8000	0.9091	1.0342	1.1594	1.2603	1.3854
Class 4C, Pitch Diameter	Min	0.4500	0.5625	0.6667	0.7917	0.9000	1.0250	1.1500	1.2500	1.3750
	Max	0.4546	0.5676	0.6725	0.7977	0.9065	1.0316	1.1567	1.2573	1.3824

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8c. Limiting Dimensions of American National Standard Centralizing Acme Single-Start Screw Threads, Classes 2C, 3C, and 4C *ASME/ANSI B1.5-1988*

Nominal Diameter, *D*		1¾	2	2¼	2½	2¾	3	3½12	4	4½	5
Threads per Inch[a]		4	4	3	3	3	2	2	2	2	2
Limiting Diameters		**External Threads**									
Classes 2C, 3C, and 4C, Major Diameter	Max	1.7500	2.0000	2.2500	2.5000	2.7500	3.0000	3.5000	4.0000	4.5000	5.0000
Class 2C, Major Diameter	Min	1.7454	1.9951	2.2448	2.4945	2.7442	2.9939	3.4935	3.9930	4.4926	4.9922
Class 3C, Major Diameter	Min	1.7480	1.9979	2.2478	2.4976	2.7475	2.9974	3.4972	3.9970	4.4968	4.9966
Class 4C, Major Diameter	Min	1.7487	1.9986	2.2485	2.4984	2.7483	2.9983	3.4981	3.9980	4.4979	4.9978
Classes 2C, 3C, and 4C, Minor Diameter	Max	1.4800	1.7300	1.8967	2.1467	2.3967	2.4800	2.9800	3.4800	3.9800	4.4800
Class 2C, Minor Diameter	Min	1.4456	1.6948	1.8572	2.1065	2.3558	2.4326	2.9314	3.4302	3.9291	4.4281
Class 3C, Minor Diameter	Min	1.4640	1.7136	1.8783	2.1279	2.3776	2.4579	2.9574	3.4568	3.9563	4.4558
Class 4C, Minor Diameter	Min	1.4685	1.7183	1.8835	2.1333	2.3831	2.4642	2.9638	3.4634	3.9631	4.4627
Class 2C, Pitch Diameter	Max	1.6145	1.8637	2.0713	2.3207	2.5700	2.7360	3.2350	3.7340	4.2330	4.7319
	Min	1.5916	1.8402	2.0450	2.2939	2.5427	2.7044	3.2026	3.7008	4.1991	4.6973
Class 3C, Pitch Diameter	Max	1.6171	1.8665	2.0743	2.3238	2.5734	2.7395	3.2388	3.7380	4.2373	4.7364
	Min	1.6064	1.8555	2.0620	2.3113	2.5607	2.7248	3.2237	3.7225	4.2215	4.7202
Class 4C, Pitch Diameter	Max	1.6198	1.8693	2.0773	2.3270	2.5767	2.7430	3.2425	3.7420	4.2415	4.7409
	Min	1.6122	1.8615	2.0685	2.3181	2.5676	2.7325	3.2317	3.7309	4.2302	4.7294
		Internal Threads									
Classes 2C, 3C, and 4C, Major Diameter	Min	1.7513	2.0014	2.2515	2.5016	2.7517	3.0017	3.5019	4.0020	4.5021	5.0022
Classes 2C and 3C, Major Diameter	Max	1.7559	2.0063	2.2567	2.5071	2.7575	3.0078	3.5084	4.0090	4.5095	5.0100
Class 4C, Major Diameter	Max	1.7539	2.0042	2.2545	2.5048	2.7550	3.0052	3.5056	4.0060	4.5063	5.0067
Classes 2C, 3C, and 4C, Minor Diameter	Min	1.5250	1.7750	1.9500	2.2000	2.4500	2.5500	3.0500	3.5500	4.0500	4.5500
	Max	1.5375	1.7875	1.9667	2.2167	2.4667	2.5750	3.0750	3.5750	4.0750	4.5750
Class 2C, Pitch Diameter	Min	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.6479	1.8985	2.1096	2.3601	2.6106	2.7816	3.2824	3.7832	4.2839	4.7846
Class 3C, Pitch Diameter	Min	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.6357	1.8860	2.0956	2.3458	2.5960	2.7647	3.2651	3.7655	4.2658	4.7662
Class 4C Pitch Diameter	Min	1.6250	1.8750	2.0833	2.3333	2.5833	2.7500	3.2500	3.7500	4.2500	4.7500
	Max	1.6326	1.8828	2.0921	2.3422	2.5924	2.7605	3.2608	3.7611	4.2613	4.7615

[a] All other dimensions are in inches. The selection of threads per inch is arbitrary and for the purpose of establishing a standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. American National Standard Centralizing Acme Single-Start Screw Thread Data *ASME/ANSI B1.5-1988*

Identification		Diameters			Thread Data					
		Centralizing, Classes 2C, 3C, and 4C							Lead Angle λ at Basic Pitch Diameter[a] Centralizing Classes 2C, 3C, and 4C,	
Nominal Sizes (All Classes)	Threads per Inch,[a] n	Basic Major Diameter, D	Pitch Diameter, $D_2 = (D - h)$	Minor Diameter, $D_1 = (D - 2h)$	Pitch, P	Thickness at Pitch Line, $t = P/2$	Basic Height of Thread, $h = P/2$	Basic Width of Flat, $F = 0.3707P$	Deg	Min
1/4	16	0.2500	0.2188	0.1875	0.06250	0.03125	0.03125	0.0232	5	12
5/16	14	0.3125	0.2768	0.2411	0.07143	0.03571	0.03571	0.0265	4	42
3/8	12	0.3750	0.3333	0.2917	0.08333	0.04167	0.04167	0.0309	4	33
7/16	12	0.4375	0.3958	0.3542	0.08333	0.04167	0.04167	0.0309	3	50
1/2	10	0.5000	0.4500	0.4000	0.10000	0.05000	0.05000	0.0371	4	3
5/8	8	0.6250	0.5625	0.5000	0.12500	0.06250	0.06250	0.0463	4	3
3/4	6	0.7500	0.6667	0.5833	0.16667	0.08333	0.08333	0.0618	4	33
7/8	6	0.8750	0.7917	0.7083	0.16667	0.08333	0.08333	0.0618	3	50
1	5	1.0000	0.9000	0.8000	0.20000	0.10000	0.10000	0.0741	4	3
1 1/8	5	1.1250	1.0250	0.9250	0.20000	0.10000	0.10000	0.0741	3	33
1 1/4	5	1.2500	1.1500	1.0500	0.20000	0.10000	0.10000	0.0741	3	10
1 3/8	4	1.3750	1.2500	1.1250	0.25000	0.12500	0.12500	0.0927	3	39
1 1/2	4	1.5000	1.3750	1.2500	0.25000	0.12500	0.12500	0.0927	3	19
1 3/4	4	1.7500	1.6250	1.5000	0.25000	0.12500	0.12500	0.0927	2	48
2	4	2.0000	1.8750	1.7500	0.25000	0.12500	0.12500	0.0927	2	26
2 1/4	3	2.2500	2.0833	1.9167	0.33333	0.16667	0.16667	0.1236	2	55
2 1/2	3	2.5000	2.3333	2.1667	0.33333	0.16667	0.16667	0.1236	2	36
2 3/4	3	2.7500	2.5833	2.4167	0.33333	0.16667	0.16667	0.1236	2	21
3	2	3.0000	2.7500	2.5000	0.50000	0.25000	0.25000	0.1853	3	19
3 1/2	2	3.5000	3.2500	3.0000	0.50000	0.25000	0.25000	0.1853	2	48
4	2	4.0000	3.7500	3.5000	0.50000	0.25000	0.25000	0.1853	2	26
4 1/2	2	4.5000	4.2500	4.0000	0.50000	0.25000	0.25000	0.1853	2	9
5	2	5.0000	4.7500	4.5000	0.50000	0.25000	0.25000	0.1853	1	55

[a] All other dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. American National Standard Centralizing Acme Single-Start Screw Threads — Pitch Diameter Allowances *ASME/ANSI B1.5-1988*

Nominal Size Range[a]		Allowances on External Threads[b]			Nominal Size Range[a]		Allowances on External Threads[b]		
		Centralizing					Centralizing		
Above	To and Including	Class 2C, $0.008\sqrt{D}$	Class 3C, $0.006\sqrt{D}$	Class 4C, $0.004\sqrt{D}$	Above	To and Including	Class 2C, $0.008\sqrt{D}$	Class 3C, $0.006\sqrt{D}$	Class 4C, $0.004\sqrt{D}$
0	3/16	0.0024	0.0018	0.0012	1 7/16	1 9/16	0.0098	0.0073	0.0049
3/16	5/16	0.0040	0.0030	0.0020	1 9/16	1 7/8	0.0105	0.0079	0.0052
5/16	7/16	0.0049	0.0037	0.0024	1 7/8	2 1/8	0.0113	0.0085	0.0057
7/16	9/16	0.0057	0.0042	0.0028	2 1/8	2 3/8	0.0120	0.0090	0.0060
9/16	11/16	0.0063	0.0047	0.0032	2 3/8	2 5/8	0.0126	0.0095	0.0063
11/16	13/16	0.0069	0.0052	0.0035	2 5/8	2 7/8	0.0133	0.0099	0.0066
13/16	15/16	0.0075	0.0056	0.0037	2 7/8	3 1/4	0.0140	0.0105	0.0070
15/16	1 1/16	0.0080	0.0060	0.0040	3 1/4	3 3/4	0.0150	0.0112	0.0075
1 1/16	1 3/16	0.0085	0.0064	0.0042	3 3/4	4 1/4	0.0160	0.0120	0.0080
1 3/16	1 5/16	0.0089	0.0067	0.0045	4 1/4	4 3/4	0.0170	0.0127	0.0085
1 5/16	1 7/16	0.0094	0.0070	0.0047	4 3/4	5 1/2	0.0181	0.0136	0.0091

All dimensions are given in inches.

It is recommended that the sizes given in Table 9 be used whenever possible.

[a] The values in columns for Classes 2C, 3C, and 4C are to be used for any size within the nominal size range columns. These values are calculated from the mean of the range.

[b] An increase of 10 per cent in the allowance is recommended for each inch, or fraction thereof, that the length of engagement exceeds two diameters.

Table 11. American National Standard Centralizing Acme Single-Start Screw Threads — Pitch Diameter Tolerances *ASME/ANSI B1.5-1988*

Nom. Dia.,[a] D	Class of Thread and Diameter Increment			Nom. Dia.,[a] D	Class of Thread and Diameter Increment		
	2C	3C	4C		2C	3C	4C
	$0.006\sqrt{D}$	$0.0028\sqrt{D}$	$0.002\sqrt{D}$		$0.006\sqrt{D}$	$0.0028\sqrt{D}$	$0.002\sqrt{D}$
1/4	.00300	.00140	.00100	1 1/2	.00735	.00343	.00245
5/16	.00335	.00157	.00112	1 3/4	.00794	.00370	.00265
3/8	.00367	.00171	.00122	2	.00849	.00396	.00283
7/16	.00397	.00185	.00132	2 1/4	.00900	.00420	.00300
1/2	.00424	.00198	.00141	2 1/2	.00949	.00443	.00316
5/8	.00474	.00221	.00158	2 3/4	.00995	.00464	.00332
3/4	.00520	.00242	.00173	3	.01039	.00485	.00346
7/8	.00561	.00262	.00187	3 1/2	.01122	.00524	.00374
1	.00600	.00280	.00200	4	.01200	.00560	.00400
1 1/8	.00636	.00297	.00212	4 1/2	.01273	.00594	.00424
1 1/4	.00671	.00313	.00224	5	.01342	.00626	.00447
1 3/8	.00704	.00328	.00235	…	…	…	…
Thds. per Inch, n	Class of Thread and Pitch Increment			Thds. per Inch, n	Class of Thread and Pitch Increment		
	2C	3C	4C		2C	3C	4C
	$0.030\sqrt{1/n}$	$0.014\sqrt{1/n}$	$0.010\sqrt{1/n}$		$0.030\sqrt{1/n}$	$0.014\sqrt{1/n}$	$0.010\sqrt{1/n}$
16	.00750	.00350	.00250	4	.01500	.00700	.00500
14	.00802	.00374	.00267	3	.01732	.00808	.00577
12	.00866	.00404	.00289	2 1/2	.01897	.00885	.00632
10	.00949	.00443	.00316	2	.02121	.00990	.00707
8	.01061	.00495	.00354	1 1/2	.02449	.01143	.00816
6	.01225	.00572	.00408	1 1/3	.02598	.01212	.00866
5	.01342	.00626	.00447	1	.03000	.01400	.01000

All dimensions are given in inches.

For any particular size of thread, the pitch diameter tolerance is obtained by adding the *diameter increment* from the upper half of the table to the *pitch increment* from the lower half of the table. *Example:* A 0.250-16-ACME-2C thread has a pitch diameter tolerance of 0.00300 + 0.00750 = 0.0105 inch.

The equivalent tolerance on thread thickness is 0.259 times the pitch diameter tolerance.

[a] For a nominal diameter between any two tabulated nominal diameters, use the diameter increment for the larger of the two tabulated nominal diameters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. American National Standard Centralizing Acme Single-Start Screw Threads — Tolerances and Allowances for Major and Minor Diameters *ASME/ANSI B1.5-1988*

Size (Nom.)	Thds[a] per Inch	Allowance From Basic Major and Minor Diameters (All Classes)			Tolerance on Minor Diam., [b, c] All Internal Threads, (Plus 0.05*P*)	Tolerance on Major Diameter Plus on Internal, Minus on External Threads				
			Internal Thread			Class 2C	Class 3C		Class 4C	
		Minor Diam., [d] All External Threads (Minus)	Major Diam., [e] (Plus $0.0010\sqrt{D}$)	Minor Diam., [d] (Plus 0.1*P*)		External and Internal Threads, $0.0035\sqrt{D}$	External Thread, $0.0015\sqrt{D}$	Internal Thread, $0.0035\sqrt{D}$	External Thread, $0.0010\sqrt{D}$	Internal Thread, $0.0020\sqrt{D}$
1/4	16	0.010	0.0005	0.0062	0.0050	0.0017	0.0007	0.0017	0.0005	0.0010
5/16	14	0.010	0.0006	0.0071	0.0050	0.0020	0.0008	0.0020	0.0006	0.0011
3/8	12	0.010	0.0006	0.0083	0.0050	0.0021	0.0009	0.0021	0.0006	0.0012
7/16	12	0.010	0.0007	0.0083	0.0050	0.0023	0.0010	0.0023	0.0007	0.0013
1/2	10	0.020	0.0007	0.0100	0.0050	0.0025	0.0011	0.0025	0.0007	0.0014
5/8	8	0.020	0.0008	0.0125	0.0062	0.0028	0.0012	0.0028	0.0008	0.0016
3/4	6	0.020	0.0009	0.0167	0.0083	0.0030	0.0013	0.0030	0.0009	0.0017
7/8	6	0.020	0.0009	0.0167	0.0083	0.0033	0.0014	0.0033	0.0009	0.0019
1	5	0.020	0.0010	0.0200	0.0100	0.0035	0.0015	0.0035	0.0010	0.0020
1 1/8	5	0.020	0.0011	0.0200	0.0100	0.0037	0.0016	0.0037	0.0011	0.0021
1 1/4	5	0.020	0.0011	0.0200	0.0100	0.0039	0.0017	0.0039	0.0011	0.0022
1 3/8	4	0.020	0.0012	0.0250	0.0125	0.0041	0.0018	0.0041	0.0012	0.0023
1 1/2	4	0.020	0.0012	0.0250	0.0125	0.0043	0.0018	0.0043	0.0012	0.0024
1 3/4	4	0.020	0.0013	0.0250	0.0125	0.0046	0.0020	0.0046	0.0013	0.0026
2	4	0.020	0.0014	0.0250	0.0125	0.0049	0.0021	0.0049	0.0014	0.0028
2 1/4	3	0.020	0.0015	0.0333	0.0167	0.0052	0.0022	0.0052	0.0015	0.0030
2 1/2	3	0.020	0.0016	0.0333	0.0167	0.0055	0.0024	0.0055	0.0016	0.0032
2 3/4	3	0.020	0.0017	0.0333	0.0167	0.0058	0.0025	0.0058	0.0017	0.0033
3	2	0.020	0.0017	0.0500	0.0250	0.0061	0.0026	0.0061	0.0017	0.0035
3 1/2	2	0.020	0.0019	0.0500	0.0250	0.0065	0.0028	0.0065	0.0019	0.0037
4	2	0.020	0.0020	0.0500	0.0250	0.0070	0.0030	0.0070	0.0020	0.0040
4 1/2	2	0.020	0.0021	0.0500	0.0250	0.0074	0.0032	0.0074	0.0021	0.0042
5	2	0.020	0.0022	0.0500	0.0250	0.0078	0.0034	0.0078	0.0022	0.0045

[a] All other dimensions are given in inches. Intermediate pitches take the values of the next coarser pitch listed. Values for intermediate diameters should be calculated from the formulas in column headings, but ordinarily may be interpolated.

[b] To avoid a complicated formula and still provide an adequate tolerance, the pitch factor is used as a basis, with the minimum tolerance set at 0.005 in.

[c] Tolerance on minor diameter of all external threads is 1.5 × pitch diameter tolerance.

[d] The minimum clearance at the minor diameter between the internal and external thread is the sum of the values in columns 3 and 5.

[e] The minimum clearance at the major diameter between the internal and external thread is equal to column 4.

Copyright 2004, Industrial Press, Inc., New York, NY

Designation of Centralizing Acme Threads.— The following examples are given to show how these Acme threads are designated on drawings, in specifications, and on tools and gages:

Example, 1.750-6-ACME-4C: Indicates a Centralizing Class 4C Acme thread of 1.750-inch major diameter, 0.1667-inch pitch, single thread, right-hand.

Example, 1.750-6-ACME-4C-LH: Indicates the same thread left-hand.

Example, 2.875-0.4P-0.8L-ACME-3C (Two Start): Indicates a Centralizing Class 3C Acme thread with 2.875-inch major diameter, 0.4-inch pitch, 0.8-inch lead, double thread, right-hand.

Example, 2.500-0.3333P-0.6667L-ACME-4C (Two Start): Indicates a Centralizing Class 4C Acme thread with 2.500-inch nominal major diameter (basic major diameter 2.500 inches), 0.3333-inch pitch, 0.6667-inch lead, double thread, right-hand. The same thread left-hand would have LH at the end of the designation.

Acme Centralizing Threads—Alternative Series with Minor Diameter Centralizing Control.— When Acme centralizing threads are produced in single units or in very small quantities (and principally in sizes larger than the range of commercial taps and dies) where the manufacturing process employs cutting tools (such as lathe cutting), it may be economically advantageous and therefore desirable to have the centralizing control of the mating threads located at the *minor diameters*.

Particularly under the above-mentioned type of manufacturing, the two advantages cited for minor diameter centralizing control over centralizing control at the major diameters of the mating threads are: 1) Greater ease and faster checking of machined thread dimensions. It is much easier to measure the minor diameter (root) of the external thread and the mating minor diameter (crest or bore) of the internal thread than it is to determine the major diameter (root) of the internal thread and the major diameter (crest or turn) of the external thread; and 2) better manufacturing control of the machined size due to greater ease of checking.

In the event that minor diameter centralizing is necessary, recalculate all thread dimensions, reversing major and minor diameter allowances, tolerances, radii, and chamfer.

American National Standard Stub Acme Threads.— This American National Standard ASME/ANSI B1.8-1988 (R2001) provides a Stub Acme screw thread for those unusual applications where, due to mechanical or metallurgical considerations, a coarse-pitch thread of shallow depth is required. The fit of Stub Acme threads corresponds to the Class 2G General Purpose Acme thread in American National Standard ANSI B1.5-1988. For a fit having less backlash, the tolerances and allowances for Classes 3G or 4G General Purpose Acme threads may be used.

Thread Form: The thread form and basic formulas for Stub Acme threads are given on page 1826 and the basic dimensions in Table 13.

Allowances and Tolerances: The major and minor diameter allowances for Stub Acme threads are the same as those given for General Purpose Acme threads on page 1825.

Pitch diameter allowances for Stub Acme threads are the same as for Class 2G General Purpose Acme threads and are given in Table 4. Pitch diameter tolerances for Stub Acme threads are the same as for Class 2G General Purpose Acme threads given in Table 5.

Limiting Dimensions: Limiting dimensions of American Standard Stub Acme threads may be determined by using the formulas given in Table 14a, or directly from Table 14b. The diagram below shows the limits of size for Stub Acme threads.

Thread Series: A preferred series of diameters and pitches for General Purpose Acme threads (Table 15) is recommended for Stub Acme threads.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. American National Standard Stub Acme Screw Thread Form — Basic Dimensions *ASME/ANSI B1.8-1988 (R2001)*

Thds. per Inch[a] n	Pitch, $P = 1/n$	Height of Thread (Basic), $0.3P$	Total Height of Thread, $0.3P + \frac{1}{2}$ allowance[b]	Thread Thickness (Basic), $P/2$	Width of Flat	
					Crest of InternalThread (Basic), $0.4224P$	Root of Internal Thread, $0.4224P$ –0.259 ×allowance[b]
16	0.06250	0.01875	0.0238	0.03125	0.0264	0.0238
14	0.07143	0.02143	0.0264	0.03571	0.0302	0.0276
12	0.08333	0.02500	0.0300	0.04167	0.0352	0.0326
10	0.10000	0.03000	0.0400	0.05000	0.0422	0.0370
9	0.11111	0.03333	0.0433	0.05556	0.0469	0.0417
8	0.12500	0.03750	0.0475	0.06250	0.0528	0.0476
7	0.14286	0.04285	0.0529	0.07143	0.0603	0.0551
6	0.16667	0.05000	0.0600	0.08333	0.0704	0.0652
5	0.20000	0.06000	0.0700	0.10000	0.0845	0.0793
4	0.25000	0.07500	0.0850	0.12500	0.1056	0.1004
3½	0.28571	0.08571	0.0957	0.14286	0.1207	0.1155
3	0.33333	0.10000	0.1100	0.16667	0.1408	0.1356
2½	0.40000	0.12000	0.1300	0.20000	0.1690	0.1638
2	0.50000	0.15000	0.1600	0.25000	0.2112	0.2060
1½	0.66667	0.20000	0.2100	0.33333	0.2816	0.2764
1⅓	0.75000	0.22500	0.2350	0.37500	0.3168	0.3116
1	1.00000	0.30000	0.3100	0.50000	0.4224	0.4172

[a] All other dimensions in inches. See Fig. 1, page 1826.

[b] Allowance is 0.020 inch for 10 or less threads per inch and 0.010 inch for more than 10 threads per inch.

Table 14a. American National Standard Stub Acme Single-Start Screw Threads — Formulas for Determining Diameters *ASME/ANSI B1.8-1988 (R2001)*

D = Basic Major Diameter and Nominal Size in Inches

D_2 = Basic Pitch Diameter = $D - 0.3P$

D_1 = Basic Minor Diameter = $D - 0.6P$

No.	External Threads (Screws)
1	Major Dia., Max = D.
2	Major Dia., Min. = D *minus* $0.05P$.
3	Pitch Dia., Max. = D_2 *minus* allowance from the appropriate Class 2G column, Table 4.
4	Pitch Dia., Min. = Pitch Dia., Max. (Formula 3) *minus* Class 2G tolerance from Table 5.
5	Minor Dia., Max. = D_1 *minus* 0.020 for 10 threads per inch and coarser and 0.010 for finer pitches.
6	Minor Dia., Min. = Minor Dia., Max. (Formula 5) *minus* Class 2G pitch diameter tolerance from Table 5.
	Internal Threads (Nuts)
7	Major Dia., Min. = D *plus* 0.020 for 10 threads per inch and coarser and 0.010 for finer pitches.
8	Major Dia., Max.= Major Dia., Min. (Formula 7) *plus* Class 2G pitch diameter tolerance from Table 5.
9	Pitch Dia., Min. = $D_2 = D - 0.3P$
10	Pitch Dia., Max. = Pitch Dia., Min. (Formula 9) *plus* Class 2G tolerance from Table 5.
11	Minor Dia., Min. = $D_1 = D - 0.6P$
12	Minor Dia., Max = Minor Dia., Min. (Formula 11) *plus* $0.05P$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14b. Limiting Dimensions for American National Standard Stub Acme Single-Start Screw Threads *ASME/ANSI B1.8-1988 (R2001)*

Nominal Diameter, D		1/4	5/16	3/8	7/16	1/2	5/8	3/4	7/8	1	1 1/8	1 1/4	1 3/8
Threads per Inch[a]		16	14	12	12	10	8	6	6	5	5	5	4
Limiting Diameters		**External Threads**											
Major Dia.	Max (D)	0.2500	0.3125	0.3750	0.4375	0.5000	0.6250	0.7500	0.8750	1.0000	1.1250	1.2500	1.3750
	Min	0.2469	0.3089	0.3708	0.4333	0.4950	0.6188	0.7417	0.8667	0.9900	1.1150	1.2400	1.3625
Pitch Dia.	Max	0.2272	0.2871	0.3451	0.4076	0.4643	0.5812	0.6931	0.8175	0.9320	1.0565	1.1811	1.2906
	Min	0.2167	0.2757	0.3328	0.3950	0.4506	0.5658	0.6757	0.7996	0.9126	1.0367	1.1610	1.2686
Minor Dia.	Max	0.2024	0.2597	0.3150	0.3775	0.4200	0.5300	0.6300	0.7550	0.8600	0.9850	1.1100	1.2050
	Min	0.1919	0.2483	0.3027	0.3649	0.4063	0.5146	0.6126	0.7371	0.8406	0.9652	1.0899	1.1830
		Internal Threads											
Major Dia.	Min	0.2600	0.3225	0.3850	0.4475	0.5200	0.6450	0.7700	0.8950	1.0200	1.1450	1.2700	1.3950
	Max	0.2705	0.3339	0.3973	0.4601	0.5337	0.6604	0.7874	0.9129	1.0394	1.1648	1.2901	1.4170
Pitch Dia.	Min	0.2312	0.2911	0.3500	0.4125	0.4700	0.5875	0.7000	0.8250	0.9400	1.0650	1.1900	1.3000
	Max	0.2417	0.3025	0.3623	0.4251	0.4837	0.6029	0.7174	0.8429	0.9594	1.0848	1.2101	1.3220
Minor Dia.	Min	0.2125	0.2696	0.3250	0.3875	0.4400	0.5500	0.6500	0.7750	0.8800	1.0050	1.1300	1.2250
	Max	0.2156	0.2732	0.3292	0.3917	0.4450	0.5562	0.6583	0.7833	0.8900	1.0150	1.1400	1.2375

Nominal Diameter, D		1 1/2	1 3/4	2	2 1/4	2 1/2	2 3/4	3	3 1/2	4	4 1/2	5
Threads per Inch[a]		4	4	4	3	3	3	2	2	2	2	2
Limiting Diameters		**External Threads**										
Major Dia.	Max (D)	1.5000	1.7500	2.0000	2.2500	2.5000	2.7500	3.0000	3.5000	4.0000	4.5000	5.0000
	Min	1.4875	1.7375	1.9875	2.2333	2.4833	2.7333	2.9750	3.4750	3.9750	4.4750	4.9750
Pitch Dia.	Max	1.4152	1.6645	1.9137	2.1380	2.3874	2.6367	2.8360	3.3350	3.8340	4.3330	4.8319
	Min	1.3929	1.6416	1.8902	2.1117	2.3606	2.6094	2.8044	3.3026	3.8008	4.2991	4.7973
Minor Dia.	Max	1.3300	1.5800	1.8300	2.0300	2.2800	2.5300	2.6800	3.1800	3.6800	4.1800	4.6800
	Min	1.3077	1.5571	1.8065	2.0037	2.2532	2.5027	2.6484	3.1476	3.6468	4.1461	4.6454
		Internal Threads										
Major Dia.	Min	1.5200	1.7700	2.0200	2.2700	2.5200	2.7700	3.0200	3.5200	4.0200	4.5200	5.0200
	Max	1.5423	1.7929	2.0435	2.2963	2.5468	2.7973	3.0516	3.5524	4.0532	4.5539	5.0546
Pitch Dia.	Min	1.4250	1.6750	1.9250	2.1500	2.4000	2.6500	2.8500	3.3500	3.8500	4.3500	4.8500
	Max	1.4473	1.6979	1.9485	2.1763	2.4268	2.6773	2.8816	3.3824	3.8832	4.3839	4.8846
Minor Dia.	Min	1.3500	1.6000	1.8500	2.0500	2.3000	2.5500	2.7000	3.2000	3.7000	4.2000	4.7000
	Max	1.3625	1.6125	1.8625	2.0667	2.3167	2.5667	2.7250	3.2250	3.7250	4.2250	4.7250

[a] All other dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY



Limits of Size, Allowances, Tolerances, and Crest Clearances for American National Standard Stub Acme Threads

Stub Acme Thread Designations.— The method of designation for Standard Stub Acme threads is illustrated in the following examples: 0.500-20 Stub Acme indicates a ½-inch major diameter, 20 threads per inch, right hand, single thread, Standard Stub Acme thread. The designation 0.500-20 Stub Acme-LH indicates the same thread except that it is left hand.

Alternative Stub Acme Threads.— Since one Stub Acme thread form may not meet the requirements of all applications, basic data for two of the other commonly used forms are included in the appendix of the American Standard for Stub Acme Threads. These so-called Modified Form 1 and Modified Form 2 threads utilize the same tolerances and allowances as Standard Stub Acme threads and have the same major diameter and basic thread thickness at the pitchline (0.5*P*). The basic height of Form 1 threads, *h*, is 0.375*P*; for Form 2 it is 0.250*P*. The basic width of flat at the crest of the internal thread is 0.4030*P* for Form 1 and 0.4353*P* for Form 2.

The pitch diameter and minor diameter for Form 1 threads will be smaller than similar values for the Standard Stub Acme Form and for Form 2 they will be larger owing to the differences in basic thread height *h*. Therefore, in calculating the dimensions of Form 1 and Form 2 threads using Formulas 1 through 12 in Table 14a, it is only necessary to substitute the following values in applying the formulas: For Form 1, $D_2 = D - 0.375P$, $D_1 = D - 0.75P$; for Form 2, $D_2 = D - 0.25\text{P}$, $D_1 = D - 0.5P$.

Thread Designation: These threads are designated in the same manner as Standard Stub Acme threads except for the insertion of either M1 or M2 after "Acme." Thus, 0.500-20 Stub Acme M1 for a Form 1 thread; and 0.500-20 Stub Acme M2 for a Form 2 thread.

Former 60-Degree Stub Thread.— Former American Standard B1.3-1941 included a 60-degree stub thread for use where design or operating conditions could be better satisfied by the use of this thread, or other modified threads, than by Acme threads. Data for 60-Degree Stub thread form are given in the accompanying diagram.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Stub Acme Screw Thread Data *ASME/ANSI B1.8-1988* **(R2001)**

Identification		Basic Diameters			Thread Data					
Nominal Sizes	Threads per Inch,[a] n	Major Diameter, D	Pitch Diameter, $D_2 = D - h$	Minor Diameter, $D_1 = D - 2h$	Pitch, P	Thread Thickness at Pitch Line, $t = P/2$	Basic Thread Height, $h = 0.3P$	Basic Width of Flat, $0.4224P$	Lead Angle at Basic Pitch Diameter	
									Deg	Min
1/4	16	0.2500	0.2312	0.2125	0.06250	0.03125	0.01875	0.0264	4	54
5/16	14	0.3125	0.2911	0.2696	0.07143	0.03572	0.02143	0.0302	4	28
3/8	12	0.3750	0.3500	0.3250	0.08333	0.04167	0.02500	0.0352	4	20
7/16	12	0.4375	0.4125	0.3875	0.08333	0.04167	0.02500	0.0352	3	41
1/2	10	0.5000	0.4700	0.4400	0.10000	0.05000	0.03000	0.0422	3	52
5/8	8	0.6250	0.5875	0.5500	0.12500	0.06250	0.03750	0.0528	3	52
3/4	6	0.7500	0.7000	0.6500	0.16667	0.08333	0.05000	0.0704	4	20
7/8	6	0.8750	0.8250	0.7750	0.16667	0.08333	0.05000	0.0704	3	41
1	5	1.0000	0.9400	0.8800	0.20000	0.10000	0.06000	0.0845	3	52
1 1/8	5	1.1250	1.0650	1.0050	0.20000	0.10000	0.06000	0.0845	3	25
1 1/4	5	1.2500	1.1900	1.1300	0.20000	0.10000	0.06000	0.0845	3	4
1 3/8	4	1.3750	1.3000	1.2250	0.25000	0.12500	0.07500	0.1056	3	30
1 1/2	4	1.5000	1.4250	1.3500	0.25000	0.12500	0.07500	0.1056	3	12
1 3/4	4	1.7500	1.6750	1.6000	0.25000	0.12500	0.07500	0.1056	2	43
2	4	2.0000	1.9250	1.8500	0.25000	0.12500	0.07500	0.1056	2	22
2 1/4	3	2.2500	2.1500	2.0500	0.33333	0.16667	0.10000	0.1408	2	50
2 1/2	3	2.5000	2.4000	2.3000	0.33333	0.16667	0.10000	0.1408	2	32
2 3/4	3	2.7500	2.6500	2.5500	0.33333	0.16667	0.10000	0.1408	2	18
3	2	3.0000	2.8500	2.7000	0.50000	0.25000	0.15000	0.2112	3	12
3 1/2	2	3.5000	3.3500	3.2000	0.50000	0.25000	0.15000	0.2112	2	43
4	2	4.0000	3.8500	3.7000	0.50000	0.25000	0.15000	0.2112	2	22
4 1/2	2	4.5000	4.3500	4.2000	0.50000	0.25000	0.15000	0.2112	2	6
5	2	5.0000	4.8500	4.7000	0.50000	0.25000	0.15000	0.2112	1	53

[a] All other dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY



60-Degree Stub Thread

A clearance of at least 0.02 × pitch is added to depth *h* to produce extra depth, thus avoiding interference with threads of mating part at minor or major diameters.

Basic thread thickness at pitch line = 0.5 × pitch *p*; basic depth *h* = 0.433 × pitch; basic width of flat at crest = 0.25 × pitch; width of flat at root of screw thread = 0.227 × pitch; basic pitch diameter = basic major diameter – 0.433 × pitch; basic minor diameter = basic major diameter – 0.866 × pitch.

Square Thread.— The square thread is so named because the section is square, the depth, in the case of a screw, being equal to the width or one-half the pitch. The thread groove in a square-threaded nut is made a little greater than one-half the pitch in order to provide a slight clearance for the screw; hence, the tools used for threading square-threaded taps are a little less in width at the point than one-half the pitch. The pitch of a square thread is usually twice the pitch of an American Standard thread of corresponding diameter. The square thread has been superseded quite largely by the Acme form which has several advantages. See *ACME SCREW THREADS*.

10-Degree Modified Square Thread: The included angle between the sides of the thread is 10 degrees (see accompanying diagram). The angle of 10 degrees results in a thread which is the practical equivalent of a "square thread," and yet is capable of economical production. Multiple thread milling cutters and ground thread taps should not be specified for modified square threads of the larger lead angles without consulting the cutting tool manufacturer.



In the following formulas, *D* = basic major diameter; *E* = basic pitch diameter; *K* = basic minor diameter; *p* = pitch; *h* = basic depth of thread on screw depth when there is no clearance between root of screw and crest of thread on nut; *t* = basic thickness of thread at pitch line; *F* = basic width of flat at crest of screw thread; *G* = basic width of flat at root of screw thread; *C* = clearance between root of screw and crest of thread on nut: $E = D - 0.5p$; $K = D - p$; $h = 0.5p$ (see Note); $t = 0.5p$; $F = 0.4563p$; $G = 0.4563p - (0.17 \times C)$.

Note: A clearance should be added to depth *h* to avoid interference with threads of mating parts at minor or major diameters.

Copyright 2004, Industrial Press, Inc., New York, NY

BUTTRESS THREADS

Threads of Buttress Form

The buttress form of thread has certain advantages in applications involving exceptionally high stresses along the thread axis in one direction only. The contacting flank of the thread, which takes the thrust, is referred to as the *pressure flank* and is so nearly perpendicular to the thread axis that the radial component of the thrust is reduced to a minimum. Because of the small radial thrust, this form of thread is particularly applicable where tubular members are screwed together, as in the case of breech mechanisms of large guns and airplane propeller hubs.

Fig. 1a shows a common form. The front or load-resisting face is perpendicular to the axis of the screw and the thread angle is 45 degrees. According to one rule, the pitch $P = 2 \times$ screw diameter $\div 15$. The thread depth d may equal $\frac{3}{4} \times$ pitch, making the flat $f = \frac{1}{8} \times$ pitch. Sometimes depth d is reduced to $\frac{2}{3} \times$ pitch, making $f = \frac{1}{6} \times$ pitch.



Fig. 1a.



Fig. 1b.



Fig. 1c.

The load-resisting side or flank may be inclined an amount (Fig. 1b) ranging usually from 1 to 5 degrees to avoid cutter interference in milling the thread. With an angle of 5 degrees and an included thread angle of 50 degrees, if the width of the flat f at both crest and root equals $\frac{1}{8} \times$ pitch, then the thread depth equals $0.69 \times$ pitch or $\frac{3}{4} d_1$.

The saw-tooth form of thread illustrated by Fig. 1c is known in Germany as the "Sägengewinde" and in Italy as the "Fillettatura a dente di Sega." Pitches are standardized from 2 millimeters up to 48 millimeters in the German and Italian specifications. The front face inclines 3 degrees from the perpendicular and the included angle is 33 degrees.

The thread depth d for the screw $= 0.86777 \times$ pitch P. The thread depth g for the nut $= 0.75 \times$ pitch. Dimension $h = 0.341 \times P$. The width f of flat at the crest of the thread on the screw $= 0.26384 \times$ pitch. Radius r at the root $= 0.12427 \times$ pitch. The clearance space $e = 0.11777 \times$ pitch.

British Standard Buttress Threads BS 1657: 1950.— Specifications for buttress threads in this standard are similar to those in the American Standard (see page 1850) except: 1) A basic depth of thread of $0.4p$ is used instead of $0.6p$; 2) Sizes below 1 inch are not included; 3) Tolerances on major and minor diameters are the same as the pitch diameter tolerances, whereas in the American Standard separate tolerances are provided; however, provision is made for smaller major and minor diameter tolerances when crest surfaces of screws or nuts are used as datum surfaces, or when the resulting reduction in depth of engagement must be limited; and 4) Certain combinations of large diameters with fine pitches are provided that are not encouraged in the American Standard.

Lowenherz or Löwenherz Thread.— The Lowenherz thread is intended for the fine screws of instruments and is based on the metric system. The Löwenherz thread has flats at the top and bottom the same as the U.S. standard buttress form, but the angle is 53 degrees 8 minutes. The depth equals $0.75 \times$ the pitch, and the width of the flats at the top and bottom is equal to $0.125 \times$ the pitch. This screw thread used for measuring instruments, optical apparatus, etc., especially in Germany.

Copyright 2004, Industrial Press, Inc., New York, NY

Löwenherz Thread

Diameter		Pitch, Millimeters	Approximate No. of Threads per Inch	Diameter		Pitch, Millimeters	Approximate No. of Threads per Inch
Millimeters	Inches			Millimeters	Inches		
1.0	0.0394	0.25	101.6	9.0	0.3543	1.30	19.5
1.2	0.0472	0.25	101.6	10.0	0.3937	1.40	18.1
1.4	0.0551	0.30	84.7	12.0	0.4724	1.60	15.9
1.7	0.0669	0.35	72.6	14.0	0.5512	1.80	14.1
2.0	0.0787	0.40	63.5	16.0	0.6299	2.00	12.7
2.3	0.0905	0.40	63.5	18.0	0.7087	2.20	11.5
2.6	0.1024	0.45	56.4	20.0	0.7874	2.40	10.6
3.0	0.1181	0.50	50.8	22.0	0.8661	2.80	9.1
3.5	0.1378	0.60	42.3	24.0	0.9450	2.80	9.1
4.0	0.1575	0.70	36.3	26.0	1.0236	3.20	7.9
4.5	0.1772	0.75	33.9	28.0	1.1024	3.20	7.9
5.0	0.1968	0.80	31.7	30.0	1.1811	3.60	7.1
5.5	0.2165	0.90	28.2	32.0	1.2599	3.60	7.1
6.0	0.2362	1.00	25.4	36.0	1.4173	4.00	6.4
7.0	0.2756	1.10	23.1	40.0	1.5748	4.40	5.7
8.0	0.3150	1.20	21.1	…	…	…	…

American National Standard Buttress Inch Screw Threads

The buttress form of thread has certain advantages in applications involving exceptionally high stresses along the thread axis in one direction only. As the thrust side (load flank) of the standard buttress thread is made very nearly perpendicular to the thread axis, the radial component of the thrust is reduced to a minimum. On account of the small radial thrust, the buttress form of thread is particularly applicable when tubular members are screwed together. Examples of actual applications are the breech assemblies of large guns, airplane propeller hubs, and columns for hydraulic presses.

7°/45° Buttress Thread Form.— In selecting the form of thread recommended as standard, ANSI B1.9-1973 (R1992), manufacture by milling, grinding, rolling, or other suitable means, has been taken into consideration. All dimensions are in inches.

Form of Thread: The form of the buttress thread is shown in the accompanying Figs. 2a and 2b, and has the following characteristics:

a) A load flank angle, measured in an axial plane, of 7 degrees from the normal to the axis.

b) A clearance flank angle, measured in an axial plane, of 45 degrees from the normal to the axis.

c) Equal truncations at the crests of the external and internal threads such that the basic height of thread engagement (assuming no allowance) is equal to 0.6 of the pitch

d) Equal radii, at the roots of the external and internal basic thread forms tangential to the load flank and the clearance flank. (There is, in practice, almost no chance that the thread forms will be achieved strictly as basically specified, that is, as true radii.) When specified, equal flat roots of the external and internal thread may be supplied.

Table 1. American National Standard Diameter—Pitch Combinations for 7°/45° Buttress Threads *ANSI B1.9-1973 (R1992)*

Preferred Nominal Major Diameters, Inches	Threads per Inch[a]	Preferred Nominal Major Diameters, Inches	Threads per Inch[a]
0.5, 0.625, 0.75	(20, 16, 12)	4.5, 5, 5.5, 6	12, 10, 8, (6, 5, 4), 3
0.875, 1.0	(16, 12, 10)	7, 8, 9, 10	10, 8, 6, (5, 4, 3), 2.5, 2
1.25, 1.375, 1.5	16, (12, 10, 8), 6	11, 12, 14, 16	10, 8, 6, 5, (4, 3, 2.5), 2, 1.5, 1.25
1.75, 2, 2.25, 2.5	16, 12, (10, 8, 6), 5, 4	18, 20, 22, 24	8, 6, 5, 4, (3, 2.5, 2), 1.5, 1.25, 1
2.75, 3, 3.5, 4	16, 12, 10, (8, 6, 5), 4		

[a] Preferred threads per inch are in parentheses.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Inch Buttress Screw Threads—Basic Dimensions *ANSI B1.9-1973 (R1992)*

Thds.[a] per Inch	Pitch, p	Basic Height of Thread, $h = 0.6p$	Height of Sharp-V Thread, $H = 0.89064p$	Crest Truncation, $f = 0.14532p$	Height of Thread, h_s or $h_n = 0.66271p$	Max. Root Truncation,[b] $s = 0.0826p$	Max. Root Radius,[c] $r = 0.0714p$	Width of Flat at Crest, $F = 0.16316p$
20	0.0500	0.0300	0.0445	0.0073	0.0331	0.0041	0.0036	0.0082
16	0.0625	0.0375	0.0557	0.0091	0.0414	0.0052	0.0045	0.0102
12	0.0833	0.0500	0.0742	0.0121	0.0552	0.0069	0.0059	0.0136
10	0.1000	0.0600	0.0891	0.0145	0.0663	0.0083	0.0071	0.0163
8	0.1250	0.0750	0.1113	0.0182	0.0828	0.0103	0.0089	0.0204
6	0.1667	0.1000	0.1484	0.0242	0.1105	0.0138	0.0119	0.0271
5	0.2000	0.1200	0.1781	0.0291	0.1325	0.0165	0.0143	0.0326
4	0.2500	0.1500	0.2227	0.0363	0.1657	0.0207	0.0179	0.0408
3	0.3333	0.2000	0.2969	0.0484	0.2209	0.0275	0.0238	0.0543
2½	0.4000	0.2400	0.3563	0.0581	0.2651	0.0330	0.0286	0.0653
2	0.5000	0.3000	0.4453	0.0727	0.3314	0.0413	0.0357	0.0816
1½	0.6667	0.4000	0.5938	0.0969	0.4418	0.0551	0.0476	0.1088
1¼	0.8000	0.4800	0.7125	0.1163	0.5302	0.0661	0.0572	0.1305
1	1.0000	0.6000	0.8906	0.1453	0.6627	0.0826	0.0714	0.1632

[a] All other dimensions are in inches.
[b] Minimum root truncation is one-half of maximum.
[c] Minimum root radius is one-half of maximum.

Buttress Thread Tolerances.— Tolerances from basic size on external threads are applied in a minus direction and on internal threads in a plus direction.

Pitch Diameter Tolerances: The following formula is used for determining the pitch diameter product tolerance for Class 2 (standard grade) external or internal threads:

$$\text{PD tolerance} = 0.002\sqrt[3]{D} + 0.00278\sqrt{L_e} + 0.00854\sqrt{p}$$

where D = basic major diameter of external thread (assuming no allowance)
L_e = length of engagement
p = pitch of thread

When the length of engagement is taken as $10p$, the formula reduces to

$$0.002\sqrt[3]{D} + 0.0173\sqrt{p}$$

It is to be noted that this formula relates specifically to Class 2 (standard grade) PD tolerances. Class 3 (precision grade) PD tolerances are two-thirds of Class 2 PD tolerances. Pitch diameter tolerances based on this latter formula, for various diameter pitch combinations, are given in Table 4.

Functional Size: Deviations in lead and flank angle of product threads increase the functional size of an external thread and decrease the functional size of an internal thread by the cumulative effect of the diameter equivalents of these deviations. The functional size of all buttress product threads shall not exceed the maximum-material limit.

Tolerances on Major Diameter of External Thread and Minor Diameter of Internal Thread: Unless otherwise specified, these tolerances should be the same as the pitch diameter tolerance for the class used.

Tolerances on Minor Diameter of External Thread and Major Diameter of Internal Thread: It will be sufficient in most instances to state only the maximum minor diameter of the external thread and the minimum major diameter of the internal thread without any tol-

Copyright 2004, Industrial Press, Inc., New York, NY

Form of American National Standard 7°/45° Buttress Thread with 0.6*p* Basic Height of Thread Engagement



Fig. 2a. Round Root External Thread

Heavy Line Indicates Basic Form



Fig. 2b. Flat Root External Thread

Heavy Line Indicates Basic Form

erance. However, the root truncation from a sharp V should not be greater than 0.0826*p* nor less than 0.0413*p*.

Lead and Flank Angle Deviations for Class 2: The deviations in lead and flank angles may consume the entire tolerance zone between maximum and minimum material product limits given in Table 4.

Diameter Equivalents for Variations in Lead and Flank Angles for Class 3: The combined diameter equivalents of variations in lead (including helix deviations), and flank

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. American National Standard Buttress Inch Screw Thread Symbols and Form

Thread Element	Max. Material (Basic)	Min. Material
Pitch	p	
Height of sharp-V thread	$H = 0.89064p$	
Basic height of thread engagement	$h = 0.6p$	
Root radius (theoretical)(see footnote [a])	$r = 0.07141p$	Min. $r = 0.0357p$
Root truncation	$s = 0.0826p$	Min. $s = 0.5$; Max. $s = 0.0413p$
Root truncation for flat root form	$s = 0.0826p$	Min. $s = 0.5$; Max. $s = 0.0413p$
Flat width for flat root form	$S = 0.0928p$	Min. $S = 0.0464p$
Allowance	G (see text)	
Height of thread engagement	$h_e = h - 0.5G$	Min. h_e = Max. h_e – [0.5 tol. on major dia. external thread + 0.5 tol. on minor dia. internal thread].
Crest truncation	$f = 0.14532p$	
Crest width	$F = 0.16316p$	
Major diameter	D	
Major diameter of internal thread	$D_n = D + 0.12542p$	Max. D_n = Max. pitch dia.of internal thread + $0.80803p$
Major diameter of external thread	$D_s = D - G$	Min. $D_s = D - G - D$ tol.
Pitch diameter	E	
Pitch diameter of internal thread (see footnote [b])	$E_n = D - h$	Max. $E_n = D - h + PD$ tol.
Pitch diameter of external thread (see footnote [c])	$E_s = D - h - G$	Min. $E_s = D - h - G - PD$ tol.
Minor diameter	K	
Minor diameter of external thread	$K_s = D - 1.32542p - G$	Min. K_s = Min. pitch dia. of external thread – $0.80803p$
Minor diameter of internal thread	$K_n = D - 2h$	Min. $K_n = D - 2h + K$ tol.
Height of thread of internal thread	$h_n = 0.66271p$	
Height of thread ofexternal thread	$h_s = 0.66271p$	
Pitch diameter increment for lead	ΔEl	
Pitch diameter increment for 45° clearance flank angle	$\Delta E\alpha_1$	
Pitch diameter increment for 7° load flank angle	$\Delta E\alpha_2$	
Length of engagement	L_e	

[a] Unless the flat root form is specified, the rounded root form of the external and internal thread shall be a continuous, smoothly blended curve within the zone defined by $0.07141p$ maximum to $0.0357p$ minimum radius. The resulting curve shall have no reversals or sudden angular variations, and shall be tangent to the flanks of the thread. There is, in practice, almost no chance that the rounded thread form will be achieved strictly as basically specified, that is, as a true radius.

[b] The pitch diameter X tolerances for GO and NOT GO threaded plug gages are applied to the internal product limits for E_n and Max. E_n.

[c] The pitch diameter W tolerances for GO and NOT GO threaded setting plug gages are applied to the external product limits for E_s and Min. E_s.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Buttress Inch Screw Threads Tolerances Class 2 (Standard Grade) and Class 3 (Precision Grade) *ANSI B1.9-1973 (R1992)*

Thds. per Inch	Pitch,[a] p Inch	Basic Major Diameter, Inch: From 0.5 thru 0.7	Over 0.7 thru 1.0	Over 1.0 thru 1.5	Over 1.5 thru 2.5	Over 2.5 thru 4	Over 4 thru 6	Over 6 thru 10	Over 10 thru 16	Over 16 thru 24	Pitch[b] Increment, $0.0173\sqrt{p}$ Inch
		Tolerance on Major Diameter of External Thread, Pitch Diameter of External and Internal Threads, and Minor Diameter of Internal Thread, Inch									
Class 2, Standard Grade											
20	0.0500	.0056	....	....	....	....	....	....	....	....	.00387
16	0.0625	.0060	.0062	.0065	.0068	.0073	....	....	....	....	.00432
12	0.0833	.0067	.0069	.0071	.0075	.0080	.0084	....	....	....	.00499
10	0.1000	....	.0074	.0076	.0080	.0084	.0089	.0095	.0102	....	.00547
8	0.1250	....	....	.0083	.0086	.0091	.0095	.0101	.0108	.0115	.00612
6	0.1667	....	....	.0092	.0096	.0100	.0105	.0111	.0118	.0125	.00706
5	0.2000	....	....	....	.0103	.0107	.0112	.0117	.0124	.0132	.00774
4	0.2500	....	....	....	.0112	.0116	.0121	.0127	.0134	.0141	.00865
3	0.3333	....	....	....	....	....	.0134	.0140	.0147	.0154	.00999
2.5	0.4000	....	....	....	....	....	....	.0149	.0156	.0164	.01094
2.0	0.5000	....	....	....	....	....	....	.0162	.0169	.0177	.01223
1.5	0.6667	....	....	....	....	....	....	....	.0188	.0196	.01413
1.25	0.8000	....	....	....	....	....	....	....	.0202	.0209	.01547
1.0	1.0000	....	....	....	....	....	....	....	....	.0227	.01730
Diameter Increment,[c] $0.002\sqrt[3]{D}$		.00169	.00189	.00215	.00252	.00296	.00342	.00400	.00470	.00543	
Class 3, Precision Grade											
20	0.0500	.0037	....	....	....	....	....	....	....	....	
16	0.0625	.0040	.0042	.0043	.0046	.0049	....	....	....	....	
12	0.0833	.0044	.0046	.0048	.0050	.0053	.0056	....	....	....	
10	0.1000	....	.0049	.0051	.0053	.0056	.0059	.0063	.0068	....	
8	0.1250	....	....	.0055	.0058	.0061	.0064	.0067	.0072	.0077	
6	0.1667	....	....	.0061	.0064	.0067	.0070	.0074	.0078	.0083	
5	.02000	....	....	....	.0068	.0071	.0074	.0078	.0083	.0088	
4	0.2500	....	....	....	.0074	.0077	.0080	.0084	.0089	.0094	
3	.03333	....	....	....	....	....	.0089	.0093	.0098	.0103	
2.5	0.4000	....	....	....	....	....	....	.0100	.0104	.0109	
2.0	0.5000	....	....	....	....	....	....	.0108	.0113	.0118	
1.5	0.6667	....	....	....	....	....	....	....	.0126	.0130	
1.25	0.8000	....	....	....	....	....	....	....	.0135	.0139	
1.0	1.0000	....	....	....	....	....	....	....	....	.0152	

[a] For threads with pitches not shown in this table, pitch increment to be used in tolerance formula is to be determined by use of formula PD Tolerance $= 0.002\sqrt[3]{D} + 0.00278\sqrt{L_e} + 0.00854\sqrt{p}$, where: D = basic major diameter of external thread (assuming no allowance), L_e = length of engagement, and p = pitch of thread. This formula relates specifically to Class 2 (standard grade) PD tolerances. Class 3 (precision grade) PD tolerances are two-thirds of Class 2 PD tolerances. See text

[b] When the length of engagement is taken as $10p$, the formula reduces to: $0.002\sqrt[3]{D} + 0.0173\sqrt{p}$

[c] Diameter D, used in diameter increment formula, is based on the average of the range.

angle for Class 3, shall not exceed 50 percent of the Class 2 pitch diameter tolerances given in Table 4.

Tolerances on Taper and Roundness: There are no requirements for taper and roundness for Class 2 buttress screw threads.

Copyright 2004, Industrial Press, Inc., New York, NY

The major and minor diameters of Class 3 buttress threads shall not taper nor be out of round to the extent that specified limits for major and minor diameter are exceeded. The taper and out-of-roundness of the pitch diameter for Class 3 buttress threads shall not exceed 50 per cent of the pitch-diameter tolerances.

Allowances for Easy Assembly.— An allowance (clearance) should be provided on all external threads to secure easy assembly of parts. The amount of the allowance is deducted from the nominal major, pitch, and minor diameters of the external thread when the maximum material condition of the external thread is to be determined.

The minimum internal thread is basic.

The amount of the allowance is the same for both classes and is equal to the Class 3 pitch-diameter tolerance as calculated by the formulas previously given. The allowances for various diameter-pitch combinations are given in Table 5.

Table 5. American National Standard External Thread Allowances for Classes 2 and 3 Buttress Inch Screw Threads *ANSI B1.9-1973 (R1992)*

Threads per Inch	Pitch, *p* Inch	Basic Major Diameter, Inch								
		From 0.5 thru 0.7	Over 0.7 thru 1.0	Over 1.0 thru 1.5	Over 1.5 thru 2.5	Over 2.5 thru 4	Over 4 thru 6	Over 6 thru 10	Over 10 thru 16	Over 16 thru 24
		Allowance on Major, Minor and Pitch Diameters of External Thread, Inch								
20	0.0500	.0037	....	....	....	....	....	....	....	....
16	0.0625	.0040	.0042	.0043	.0046	.0049	....	....	....	....
12	0.0833	.0044	.0046	.0048	.0050	.0053	.0056	....	....	....
10	0.1000	....	.0049	.0051	.0053	.0056	.0059	.0063	.0068	....
8	0.1250	....	....	.0055	.0058	.0061	.0064	.0067	.0072	.0077
6	0.1667	....	....	.0061	.0064	.0067	.0070	.0074	.0078	.0083
5	0.2000	....	....	....	.0068	.0071	.0074	.0078	.0083	.0088
4	0.2500	....	....	....	.0074	.0077	.0080	.0084	.0089	.0094
3	0.3333	....	....	....	....	....	.0089	.0093	.0098	.0103
2.5	0.4000	....	....	....	....	....	....	.0100	.0104	.0109
2.0	0.5000	....	....	....	....	....	....	.0108	.0113	.0118
1.5	0.6667	....	....	....	....	....	....	....	.0126	.0130
1.25	0.8000	....	....	....	....	....	....	....	.0135	.0139
1.0	1.0000	....	....	....	....	....	....	....	....	.0152

Example Showing Dimensions for a Typical Buttress Thread.— The dimensions for a 2-inch diameter, 4 threads per inch, Class 2 buttress thread with flank angles of 7 degrees and 45 degrees are

h = basic thread height = 0.1500 (Table 2)

$h_s = h_n$ = height of thread in external and internal threads = 0.1657 (Table 2)

G = pitch-diameter allowance on external thread = 0.0074 (Table 5)

Tolerance on PD of external and internal threads = 0.0112 (Table 4)

Tolerance on major diameter of external thread and minor diameter of internal thread = 0.0112 (Table 4)

Internal Thread:

Basic Major Diameter: $D = 2.0000$

Min. Major Diameter: $D - 2h + 2h_n = 2.0314$ (see Table 2)

Min. Pitch Diameter: $D - h = 1.8500$ (see Table 2)

Max. Pitch Diameter: $D - h + PD$ Tolerance = 1.8612 (see Table 4)

Min. Minor Diameter: $D - 2h = 1.7000$ (see Table 2)

Max. Minor Diameter: $D - 2h$ + Minor Diameter Tolerance = 1.7112 (see Table 4)

Copyright 2004, Industrial Press, Inc., New York, NY

External Thread:

Max. Major Diameter: $D - G = 1.9926$ (see Table 5)

Min. Major Diameter: $D - G$ – Major Diameter Tolerance = 1.9814 (see Tables 4 and 5)

Max. Pitch Diameter: $D - h - G = 1.8426$ (see Tables 2 and 5)

Min. Pitch Diameter: $D - h - G - PD$ Tolerance = 1.8314 (see Table 4)

Max. Minor Diameter: $D - G - 2h_s = 1.6612$ (see Tables 2 and 5)

Buttress Thread Designations.— When only the designation, BUTT is used, the thread is "pull" type buttress (external thread pulls) with the clearance flank leading and the 7-degree pressure flank following. When the designation, PUSH-BUTT is used, the thread is a push type buttress (external thread pushes) with the 7-degree load flank leading and the 45-degree clearance flank following. Whenever possible this description should be confirmed by a simplified view showing thread angles on the drawing of the product that has the buttress thread.

Standard Buttress Threads: A buttress thread is considered to be standard when: 1) opposite flank angles are 7-degrees and 45-degrees; 2) basic thread height is $0.6p$; 3) tolerances and allowances are as shown in Tables 4 and 5; and 4) length of engagement is $10p$ or less.

Thread Designation Abbreviations: In thread designations on drawings, tools, gages, and in specifications, the following abbreviations and letters are to be used:

BUTT	for buttress thread, pull type
PUSH-BUTT	for buttress thread, push type
LH	for left-hand thread (Absence of LH indicates that the thread is a right-hand thread.)
P	for pitch
L	for lead
A	for external thread
B	for internal thread
Le	for length of thread engagement
SPL	for special
FL	for flat root thread
E	for pitch diameter
TPI	for threads per inch
THD	for thread

Note: Absence of A or B after thread class indicates that designation covers both the external and internal threads.

Designation Sequence for Buttress Inch Screw Threads.— When designating single-start standard buttress threads the nominal size is given first, the threads per inch next, then PUSH if the internal member is to push, but nothing if it is to pull, then the class of thread (2 or 3), then whether external (A) or internal (B), then LH if left-hand, but nothing if right-hand, and finally FL if a flat root thread, but nothing if a radiused root thread; thus, 2.5-8 BUTT-2A indicates a 2.5 inch, 8 threads per inch buttress thread, Class 2 external, right-hand, internal member to pull, with radiused root of thread. The designation 2.5-8 PUSH-BUTT-2A-LH-FL signifies a 2.5 inch size, 8 threads per inch buttress thread with internal member to push, Class 2 external, left-hand, and flat root.

A multiple-start standard buttress thread is similarly designated but the pitch is given instead of the threads per inch, followed by the lead and the number of starts is indicated in parentheses after the class of thread. Thus, 10-0.25P–0.5L – BUTT-3B (2 start) indicates a 10-inch thread with 4 threads per inch, 0.5 inch lead, buttress form with internal member to pull, Class 3 internal, 2 starts, with radiused root of thread.

Copyright 2004, Industrial Press, Inc., New York, NY

WHITWORTH THREADS

British Standard Whitworth (BSW) and British Standard Fine (BSF) Threads

The BSW is the Coarse Thread series and the BSF is the Fine Thread series of British Standard 84:1956—Parallel Screw Threads of Whitworth Form. The dimensions given in the tables on the following pages for the major, effective, and minor diameters are, respectively, the maximum limits of these diameters for bolts and the minimum limits for nuts. Formulas for the tolerances on these diameters are given in the table below.

Whitworth Standard Thread Form.— This thread form is used for the British Standard Whitworth (BSW) and British Standard Fine (BSF) screw threads. More recently, both threads have been known as parallel screw threads of Whitworth form.

With standardization of the Unified thread, the Whitworth thread form is expected to be used only for replacements or spare parts. Tables of British Standard Parallel Screw Threads of Whitworth Form will be found on the following pages; tolerance formulas are given in the table below. The form of the thread is shown by the diagram. If p = pitch, d = depth of thread, r = radius at crest and root, and n = number of threads per inch, then

$$d = \tfrac{1}{3}p \times \cot 27^\circ 30' = 0.640327p = 0.640327 \div n$$

$$r = 0.137329p = 0.137329 \div n$$



It is recommended that stainless steel bolts of nominal size ¾ inch and below should not be made to Close Class limits but rather to Medium or Free Class limits. Nominal sizes above ¾ inch should have maximum and minimum limits 0.001 inch smaller than the values obtained from the table.

Tolerance Classes : Close Class bolts. Applies to screw threads requiring a fine snug fit, and should be used only for special work where refined accuracy of pitch and thread form are particularly required. *Medium Class bolts and nuts*. Applies to the better class of ordinary interchangeable screw threads. *Free Class bolts*. Applies to the majority of bolts of ordinary commercial quality. *Normal Class nuts*. Applies to ordinary commercial quality nuts; this class is intended for use with Medium or Free Class bolts.

Table 1. Tolerance Formulas for BSW and BSF Threads

	Class or Fit	Tolerance in inches[a] (+ for nuts, – for bolts)		
		Major Dia.	Effective Dia.	Minor Dia.
Bolts	Close	$\frac{2}{3}T + 0.01\sqrt{p}$	$\frac{2}{3}T$	$\frac{2}{3}T + 0.013\sqrt{p}$
	Medium	$T + 0.01\sqrt{p}$	T	$T + 0.02\sqrt{p}$
	Free	$\frac{3}{2}T + 0.01\sqrt{p}$	$\frac{3}{2}T$	$\frac{3}{2}T + 0.02\sqrt{p}$
Nuts	Close	…	$\frac{2}{3}T$	$0.2p + 0.004$[b]
	Medium	…	T	$0.2p + 0.005$[c]
	Normal	…	$\frac{3}{2}T$	$0.2p + 0.007$[d]

[a] The symbol $T = 0.002\sqrt[3]{D} + 0.003\sqrt{L} + 0.005\sqrt{p}$, where D = major diameter of thread in inches; L = length of engagement in inches; p = pitch in inches. The symbol p signifies pitch.

[b] For 26 threads per inch and finer.

[c] For 24 and 22 threads per inch.

[d] For 20 threads per inch and coarser.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Threads of Whitworth Form—Basic Dimensions

$p = 1 \div n$
$H = 0.960491p$
$H/6 = 0.160082p$
$h = 0.640327p$
$e = 0.0739176p$
$r = 0.137329p$



Threads per Inch	Pitch	Triangular Height	Shortening	Depth of Thread	Depth of Rounding	Radius
n	*p*	*H*	*H*/6	*h*	*e*	*r*
72	0.013889	0.013340	0.002223	0.008894	0.001027	0.001907
60	0.016667	0.016009	0.002668	0.010672	0.001232	0.002289
56	0.017857	0.017151	0.002859	0.011434	0.001320	0.002452
48	0.020833	0.020010	0.003335	0.013340	0.001540	0.002861
40	0.025000	0.024012	0.004002	0.016008	0.0011848	0.003433
36	0.027778	0.026680	0.004447	0.017787	0.002053	0.003815
32	0.031250	0.030015	0.005003	0.020010	0.002310	0.004292
28	0.035714	0.034303	0.005717	0.022869	0.002640	0.004905
26	0.038462	0.036942	0.006157	0.024628	0.002843	0.005282
24	0.041667	0.040020	0.006670	0.026680	0.003080	0.005722
22	0.045455	0.043659	0.007276	0.029106	0.003366	0.006242
20	0.050000	0.048025	0.008004	0.032016	0.003696	0.006866
19	0.052632	0.050553	0.008425	0.033702	0.003890	0.007228
18	0.055556	0.053361	0.008893	0.035574	0.004107	0.007629
16	0.062500	0.060031	0.010005	0.040020	0.004620	0.008583
14	0.071429	0.068607	0.011434	0.045738	0.005280	0.009809
12	0.083333	0.080041	0.013340	0.053361	0.006160	0.011444
11	0.090909	0.087317	0.014553	0.058212	0.006720	0.012484
10	0.100000	0.096049	0.016008	0.064033	0.007392	0.013733
9	0.111111	0.106721	0.017787	0.071147	0.008213	0.015259
8	0.125000	0.120061	0.020010	0.080041	0.009240	0.017166
7	0.142857	0.137213	0.022869	0.091475	0.010560	0.019618
6	0.166667	0.160082	0.026680	0.106721	0.012320	0.022888
5	0.20000	0.192098	0.032016	0.128065	0.014784	0.027466
4.5	0.222222	0.213442	0.035574	0.142295	0.016426	0.030518
4	0.250000	0.240123	0.040020	0.160082	0.018479	0.034332
3.5	0.285714	0.274426	0.045738	0.182951	0.021119	0.039237
3.25	0.307692	0.295536	0.049256	0.197024	0.022744	0.042255
3	0.333333	0.320164	0.053361	0.213442	0.024639	0.045776
2.875	0.347826	0.334084	0.055681	0.222722	0.025710	0.047767
2.75	0.363636	0.349269	0.058212	0.232846	0.026879	0.049938
2.625	0.380952	0.365901	0.060984	0.243934	0.028159	0.052316
2.5	0.400000	0.384196	0.064033	0.256131	0.029567	0.054932

Dimensions are in inches.

Allowances: Only Free Class and Medium Class bolts have an allowance. For nominal sizes of ¾ inch down to ¼ inch, the allowance is 30 per cent of the Medium Class bolt effective-diameter tolerance (0.3*T*); for sizes less than ¼ inch, the allowance for the ¼-inch size applies. Allowances are applied minus from the basic bolt dimensions; the tolerances are then applied to the reduced dimensions.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. British Standard Whitworth (BSW) and British Standard Fine (BSF) Screw Thread Series—Basic Dimensions ***BS 84:1956 (obsolescent)***

Nominal Size, Inches	Threads per Inch	Pitch, Inches	Depth of Thread, Inches	Major Diameter, Inches	Effective Diameter, Inches	Minor Diameter, Inches	Area at Bottom of Thread, Sq. in.	Tap Drill Dia.
Coarse Thread Series (BSW)								
1/8 [a]	40	0.02500	0.0160	0.1250	0.1090	0.9030	0.0068	2.55 mm
3/16	24	0.04167	0.0267	0.1875	0.1608	0.1341	0.0141	3.70 mm
1/4	20	0.05000	0.0320	0.2500	0.2180	0.1860	0.0272	5.10 mm
5/16	18	0.05556	0.0356	0.3125	0.2769	0.2413	0.0457	6.50 mm
3/8	16	0.06250	0.0400	0.3750	0.3350	0.2950	0.0683	7.90 mm
7/16	14	0.07143	0.0457	0.4375	0.3918	0.3461	0.0941	9.30 mm
1/2	12	0.08333	0.0534	0.5000	0.4466	0.3932	0.1214	10.50 mm
9/16 [a]	12	0.08333	0.0534	0.5625	0.5091	0.4557	0.1631	12.10. mm
5/8	11	0.09091	0.0582	0.6250	0.5668	0.5086	0.2032	13.50 mm
11/16 [a]	11	0.09091	0.0582	0.6875	0.6293	0.5711	0.2562	15.00 mm
3/4	10	0.10000	0.0640	0.7500	0.6860	0.6220	0.3039	16.25 mm
7/8	9	0.11111	0.0711	0.8750	0.8039	0.7328	0.4218	19.25 mm
1	8	0.12500	0.0800	1.0000	0.9200	0.8400	0.5542	22.00 mm
1 1/8	7	0.14286	0.0915	1.1250	1.0335	0.9420	0.6969	24.75 mm
1 1/4	7	0.14286	0.0915	1.2500	1.1585	1.0670	0.8942	28.00 mm
1 1/2	6	0.16667	0.1067	1.5000	1.3933	1.2866	1.3000	33.50 mm
1 3/4	5	0.20000	0.1281	1.7500	1.6219	1.4938	1.7530	39.00 mm
2	4.5	0.22222	0.1423	2.0000	1.8577	1.7154	2.3110	44.50 mm
2 1/4	4	0.25000	0.1601	2.2500	2.0899	1.9298	2.9250	
2 1/2	4	0.25000	0.1601	2.5000	2.3399	2.1798	3.7320	
2 3/4	3.5	0.28571	0.1830	2.7500	2.5670	2.3840	4.4640	Tap drill diameters shown in this column are recommended sizes listed in BS 1157:1975 and provide from 77 to 87% of full thread.
3	3.5	0.28571	0.1830	3.0000	2.8170	2.6340	5.4490	
3 1/4 [a]	3.25	0.30769	0.1970	3.2500	3.0530	2.8560	6.4060	
3 1/2	3.25	0.30769	0.1970	3.5000	3.3030	3.1060	7.5770	
3 3/4 [a]	3	0.33333	0.2134	3.7500	3.5366	3.3232	8.6740	
4	3	0.33333	0.2134	4.0000	3.7866	3.5732	10.0300	
4 1/2	2.875	0.34783	0.2227	4.5000	4.2773	4.0546	12.9100	
5	2.75	0.36364	0.2328	5.0000	4.7672	4.5344	16.1500	
5 1/2	2.625	0.38095	0.2439	5.5000	5.2561	5.0122	19.7300	
6	2.5	0.40000	0.2561	6.0000	5.7439	5.4878	23.6500	
Fine Thread Series (BSF)								
3/16 [a, b]	32	0.03125	0.0200	0.1875	0.1675	0.1475	0.0171	4.00 mm
7/32 [a]	28	0.03571	0.0229	0.2188	0.1959	0.1730	0.0235	4.60 mm
1/4	26	0.03846	0.0246	0.2500	0.2254	0.2008	0.0317	5.30 mm
9/32 [a]	26	0.03846	0.0246	0.2812	0.2566	0.2320	0.0423	6.10 mm
5/16	22	0.04545	0.0291	0.3125	0.2834	0.2543	0.0508	6.80 mm
3/8	20	0.05000	0.0320	0.3750	0.3430	0.3110	0.0760	8.30 mm
7/16	18	0.05556	0.0 356	0.4375	0.4019	0.3363	0.1054	9.70 mm
1/2	16	0.06250	0.0400	0.5000	0.4600	0.4200	0.1385	11.10 mm
9/16	16	0.06250	0.0400	0.5625	0.5225	0.4825	0.1828	12.70 mm
5/8	14	0.07143	0.0457	0.6250	0.5793	0.5336	0.2236	14.00 mm
11/16 [a]	14	0.07143	0.0457	0.6875	0.6418	0.5961	0.2791	15.50 mm
3/4	12	0.08333	0.0534	0.7500	0.6966	0.6432	0.3249	16.75 mm
7/8	11	0.09091	0.0582	0.8750	0.8168	0.7586	0.4520	19.75 mm
1	10	0.10000	0.0640	1.0000	0.9360	0.8720	0.5972	22.75 mm
1 1/8	9	0.11111	0.0711	1.1250	1.0539	0.9828	0.7586	25.50 mm
1 1/4	9	0.11111	0.0711	1.2500	1.1789	1.1078	0.9639	28.50 mm
1 3/8 [a]	8	0.12500	0.0800	1.3750	1.2950	1.2150	1.1590	31.50 mm
1 1/2	8	0.12500	0.0800	1.5000	1.4200	1.3400	1.4100	34.50 mm
1 5/8 [a]	8	0.12500	0.0800	1.6250	1.5450	1.4650	1.6860	
1 3/4	7	0.14286	0.0915	1.7500	1.6585	1.5670	1.9280	
2	7	0.14286	0.0915	2.0000	1.9085	1.8170	2.5930	Tap drill sizes listed in this column are recommended sizes shown in BS 1157:1975 and provide from 78 to 88% of full thread.
2 1/4	6	0.16667	0.1067	2.2500	2.1433	2.0366	3.2580	
2 1/2	6	0.16667	0.1067	2.5000	2.3933	2.2866	4.1060	
2 3/4	6	0.16667	0.1067	2.7500	2.6433	2.5366	5.0540	
3	5	0.20000	0.1281	3.0000	2.8719	2.7438	5.9130	
3 1/4	5	0.20000	0.1281	3.2500	3.1219	2.9938	7.0390	
3 1/2	4.5	0.22222	0.1423	3.5000	3.3577	3.2154	8.1200	
3 3/4	4.5	0.22222	0.1423	3.7500	3.6077	3.4654	9.4320	
4	4.5	0.22222	0.1423	4.0000	3.8577	3.7154	10.8400	
4 1/4	4	0.25000	0.1601	4.2500	4.0899	3.9298	12.1300	

[a] To be dispensed with wherever possible.

[b] The use of number 2 BA threads is recommended in place of 3/16-inch BSF thread, see page 1885.

Copyright 2004, Industrial Press, Inc., New York, NY

PIPE AND HOSE THREADS

The types of threads used on pipe and pipe fittings may be classed according to their intended use: 1) threads that when assembled with a sealer will produce a pressure-tight joint; 2) threads that when assembled without a sealer will produce a pressure-tight joint; 3) threads that provide free- and loose-fitting mechanical joints without pressure tightness; and 4) threads that produce rigid mechanical joints without pressure tightness.

American National Standard Pipe Threads

American National Standard pipe threads described in the following paragraphs provide taper and straight pipe threads for use in various combinations and with certain modifications to meet these specific needs.

Thread Designation and Notation.— American National Standard Pipe Threads are designated by specifying in sequence the nominal size, number of threads per inch, and the symbols for the thread series and form, as: ⅜—18 NPT. The symbol designations are as follows: NPT—American National Standard Taper Pipe Thread; NPTR—American National Standard Taper Pipe Thread for Railing Joints; NPSC—American National Standard Straight Pipe Thread for Couplings; NPSM—American National Standard Straight Pipe Thread for Free-fitting Mechanical Joints; NPSL—American National Standard Straight Pipe Thread for Loose-fitting Mechanical Joints with Locknuts; and NPSH—American National Standard Straight Pipe Thread for Hose Couplings.

American National Standard Taper Pipe Threads.— The basic dimensions of the ANSI Standard taper pipe thread are given in Table 1a.

Form of Thread: The angle between the sides of the thread is 60 degrees when measured in an axial plane, and the line bisecting this angle is perpendicular to the axis. The depth of the truncated thread is based on factors entering into the manufacture of cutting tools and the making of tight joints and is given by the formulas in Table 1a or the data in Table 2 obtained from these formulas. Although the standard shows flat surfaces at the crest and root of the thread, some rounding may occur in commercial practice, and it is intended that the pipe threads of product shall be acceptable when crest and root of the tools or chasers lie within the limits shown in Table 2.

Pitch Diameter Formulas: In the following formulas, which apply to the ANSI Standard taper pipe thread, E_0 = pitch diameter at end of pipe; E_1 = pitch diameter at the large end of the internal thread and at the gaging notch; D = outside diameter of pipe; L_1 = length of hand-tight or normal engagement between external and internal threads; L_2 = basic length of effective external taper thread; and p = pitch = 1 ÷ number of threads per inch.

$$E_0 = D - (0.05D + 1.1)p$$

$$E_1 = E_0 + 0.0625L_1$$

Thread Length: The formula for L_2 determines the length of the effective thread and includes approximately two usable threads that are slightly imperfect at the crest. The normal length of engagement, L_1, between external and internal taper threads, when assembled by hand, is controlled by the use of the gages.

$$L_2 = (0.80D + 6.8)p$$

Taper: The taper of the thread is 1 in 16, or 0.75 inch per foot, measured on the diameter and along the axis. The corresponding half-angle of taper or angle with the center line is 1 degree, 47 minutes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. Basic Dimensions, American National Standard Taper Pipe Threads, NPT
ANSI/ASME B1.20.1-1983 (R2001)



For all dimensions, see corresponding reference letter in table.

Angle between sides of thread is 60 degrees. Taper of thread, on diameter, is ¾ inch per foot. Angle of taper with center line is 1°47′.

The basic maximum thread height, h, of the truncated thread is 0.8 × pitch of thread. The crest and root are truncated a minimum of 0.033 × pitch for all pitches. For maximum depth of truncation, see Table 2.

Nominal Pipe Size	Outside Dia. of Pipe, D	Threads per Inch, n	Pitch of Thread, p	Pitch Diameter at Beginning of External Thread, E_0	Handtight Engagement		Effective Thread, External	
					Length,[a] L_1	Dia.,[b] E_1	Length,[c] L_2	Dia., E_2
					Inch		Inch	
1/16	0.3125	27	0.03704	0.27118	0.160	0.28118	0.2611	0.28750
1/8	0.405	27	0.03704	0.36351	0.1615	0.37360	0.2639	0.38000
1/4	0.540	18	0.05556	0.47739	0.2278	0.49163	0.4018	0.50250
3/8	0.675	18	0.05556	0.61201	0.240	0.62701	0.4078	0.63750
1/2	0.840	14	0.07143	0.75843	0.320	0.77843	0.5337	0.79179
3/4	1.050	14	0.07143	0.96768	0.339	0.98887	0.5457	1.00179
1	1.315	11½	0.08696	1.21363	0.400	1.23863	0.6828	1.25630
1¼	1.660	11½	0.08696	1.55713	0.420	1.58338	0.7068	1.60130
1½	1.900	11½	0.08696	1.79609	0.420	1.82234	0.7235	1.84130
2	2.375	11½	0.08696	2.26902	0.436	2.29627	0.7565	2.31630
2½	2.875	8	0.12500	2.71953	0.682	2.76216	1.1375	2.79062
3	3.500	8	0.12500	3.34062	0.766	3.38850	1.2000	3.41562
3½	4.000	8	0.12500	3.83750	0.821	3.88881	1.2500	3.91562
4	4.500	8	0.12500	4.33438	0.844	4.38712	1.3000	4.41562
5	5.563	8	0.12500	5.39073	0.937	5.44929	1.4063	5.47862
6	6.625	8	0.12500	6.44609	0.958	6.50597	1.5125	6.54062
8	8.625	8	0.12500	8.43359	1.063	8.50003	1.7125	8.54062
10	10.750	8	0.12500	10.54531	1.210	10.62094	1.9250	10.66562
12	12.750	8	0.12500	12.53281	1.360	12.61781	2.1250	12.66562
14 OD	14.000	8	0.12500	13.77500	1.562	13.87262	2.2500	13.91562
16 OD	16.000	8	0.12500	15.76250	1.812	15.87575	2.4500	15.91562
18 OD	18.000	8	0.12500	17.75000	2.000	17.87500	2.6500	17.91562
20 OD	20.000	8	0.12500	19.73750	2.125	19.87031	2.8500	19.91562
24 OD	24.000	8	0.12500	23.71250	2.375	23.86094	3.2500	23.91562

[a] Also length of thin ring gage and length from gaging notch to small end of plug gage.
[b] Also pitch diameter at gaging notch (handtight plane).
[c] Also length of plug gage.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Basic Dimensions, American National Standard Taper Pipe Threads, NPT
ANSI/ASME B1.20.1-1983 (R2001)

Nominal Pipe Size	Wrench Makeup Length for Internal Thread		Vanish Thread, (3.47 thds.), V	Overall Length External Thread, L_4	Nominal Perfect External Threads[a]		Height of Thread, h	Basic Minor Dia. at Small End of Pipe,[b] K_0
	Length,[c] L_3	Dia., E_3			Length, L_5	Dia., E_5		
1/16	0.1111	0.26424	0.1285	0.3896	0.1870	0.28287	0.02963	0.2416
1/8	0.1111	0.35656	0.1285	0.3924	0.1898	0.37537	0.02963	0.3339
1/4	0.1667	0.46697	0.1928	0.5946	0.2907	0.49556	0.04444	0.4329
3/8	0.1667	0.60160	0.1928	0.6006	0.2967	0.63056	0.04444	0.5676
1/2	0.2143	0.74504	0.2478	0.7815	0.3909	0.78286	0.05714	0.7013
3/4	0.2143	0.95429	0.2478	0.7935	0.4029	0.99286	0.05714	0.9105
1	0.2609	1.19733	0.3017	0.9845	0.5089	1.24543	0.06957	1.1441
1 1/4	0.2609	1.54083	0.3017	1.0085	0.5329	1.59043	0.06957	1.4876
1 1/2	0.2609	1.77978	0.3017	1.0252	0.5496	1.83043	0.06957	1.7265
2	0.2609	2.25272	0.3017	1.0582	0.5826	2.30543	0.06957	2.1995
2 1/2	0.2500[d]	2.70391	0.4337	1.5712	0.8875	2.77500	0.100000	2.6195
3	0.2500[d]	3.32500	0.4337	1.6337	0.9500	3.40000	0.100000	3.2406
3 1/2	0.2500	3.82188	0.4337	1.6837	1.0000	3.90000	0.100000	3.7375
4	0.2500	4.31875	0.4337	1.7337	1.0500	4.40000	0.100000	4.2344
5	0.2500	5.37511	0.4337	1.8400	1.1563	5.46300	0.100000	5.2907
6	0.2500	6.43047	0.4337	1.9462	1.2625	6.52500	0.100000	6.3461
8	0.2500	8.41797	0.4337	2.1462	1.4625	8.52500	0.100000	8.3336
10	0.2500	10.52969	0.4337	2.3587	1.6750	10.65000	0.100000	10.4453
12	0.2500	12.51719	0.4337	2.5587	1.8750	12.65000	0.100000	12.4328
14 OD	0.2500	13.75938	0.4337	2.6837	2.0000	13.90000	0.100000	13.6750
16 OD	0.2500	15.74688	0.4337	2.8837	2.2000	15.90000	0.100000	15.6625
18 OD	0.2500	17.73438	0.4337	3.0837	2.4000	17.90000	0.100000	17.6500
20 OD	0.2500	19.72188	0.4337	3.2837	2.6000	19.90000	0.100000	19.6375
24 OD	0.2500	23.69688	0.4337	3.6837	3.0000	23.90000	0.100000	23.6125

[a] The length L_5 from the end of the pipe determines the plane beyond which the thread form is imperfect at the crest. The next two threads are perfect at the root. At this plane the cone formed by the crests of the thread intersects the cylinder forming the external surface of the pipe. $L_5 = L_2 - 2p$.

[b] Given as information for use in selecting tap drills.

[c] Three threads for 2-inch size and smaller; two threads for larger sizes.

[d] Military Specification MIL—P—7105 gives the wrench makeup as three threads for 3 in. and smaller. The E_3 dimensions are then as follows: Size 2½ in., 2.69609 and size 3 in., 3.31719.

All dimensions given in inches.

Increase in diameter per thread is equal to $0.0625/n$.

The basic dimensions of the ANSI Standard Taper Pipe Thread are given in inches to four or five decimal places. While this implies a greater degree of precision than is ordinarily attained, these dimensions are the basis of gage dimensions and are so expressed for the purpose of eliminating errors in computations.

Engagement Between External and Internal Taper Threads.— The normal length of engagement between external and internal taper threads when screwed together handtight is shown as L_1 in Table 1a. This length is controlled by the construction and use of the pipe thread gages. It is recognized that in special applications, such as flanges for high-pressure work, longer thread engagement is used, in which case the pitch diameter E_1 (Table 1a) is maintained and the pitch diameter E_0 at the end of the pipe is proportionately smaller.

Tolerances on Thread Elements.— The maximum allowable variation in the commercial product (manufacturing tolerance) is one turn large or small from the basic dimensions.

The permissible variations in thread elements on steel products and all pipe made of steel, wrought iron, or brass, exclusive of butt-weld pipe, are given in Table 3. This table is a

Copyright 2004, Industrial Press, Inc., New York, NY

guide for establishing the limits of the thread elements of taps, dies, and thread chasers. These limits may be required on product threads.

On pipe fittings and valves (not steel) for steam pressures 300 pounds and below, it is intended that plug and ring gage practice as set up in the Standard ANSI/ASME B1.20.1 will provide for a satisfactory check of accumulated variations of taper, lead, and angle in such product. Therefore, no tolerances on thread elements have been established for this class.

For service conditions where a more exact check is required, procedures have been developed by industry to supplement the regulation plug and ring method of gaging.

Table 2. Limits on Crest and Root of American National Standard External and Internal Taper Pipe Threads, NPT ***ANSI/ASME B1.20.1-1983 (R2001)***



Threads per Inch	Height of Sharp V Thread, *H*	Height of Pipe Thread, *h*		Truncation, *f*		Width of Flat, *F*, Equivalent to Truncation	
		Max.	Min.	Min.	Max.	Min.	Max.
27	0.03208	0.02963	0.02496	0.0012	0.0036	0.0014	0.0041
18	0.04811	0.04444	0.03833	0.0018	0.0049	0.0021	0.0057
14	0.06186	0.05714	0.05071	0.0024	0.0056	0.0027	0.0064
11½	0.07531	0.06957	0.06261	0.0029	0.0063	0.0033	0.0073
8	0.10825	0.10000	0.09275	0.0041	0.0078	0.0048	0.0090

All dimensions are in inches and are given to four or five decimal places only to avoid errors in computations, not to indicate required precision.

Table 3. Tolerances on Taper, Lead, and Angle of Pipe Threads of Steel Products and All Pipe of Steel, Wrought Iron, or Brass ***ANSI/ASME B1.20.1-1983 (R2001)*** **(Exclusive of Butt-Weld Pipe)**

Nominal Pipe Size	Threads per Inch	Taper on Pitch Line (¾ in./ft)		Lead in Length of Effective Threads	60 Degree Angle of Threads, Degrees
		Max.	Min.		
1/16, 1/8	27	+1/8	−1/16	±0.003	± 2½
¼, ⅜	18	+1/8	−1/16	±0.003	±2
½, ¾	14	+1/8	−1/16	±0.003[a]	±2
1, 1¼, 1½, 2	11½	+1/8	−1/16	±0.003[a]	±1½
2½ and larger	8	+1/8	−1/16	±0.003[a]	±1½

[a] The tolerance on lead shall be ± 0.003 in. per inch on any size threaded to an effective thread length greater than 1 in.

For tolerances on height of thread, see Table 2.

The limits specified in this table are intended to serve as a guide for establishing limits of the thread elements of taps, dies, and thread chasers. These limits may be required on product threads.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Internal Threads in Pipe Couplings, NPSC for Pressuretight Joints with Lubricant or Sealer *ANSI/ASME B1.20.1-1983 (R2001)*

Nom.Pipe-Size	Thds.per Inch	Minor[a] Dia.	Pitch Diameter[b]		Nom. Pipe	Thds. per Inch	Minor[a] Dia.	Pitch Diameter[b]	
		Min.	Min.	Max.			Min.	Min.	Max.
1/8	27	0.340	0.3701	0.3771	1½	11½	1.745	1.8142	1.8305
1/4	18	0.442	0.4864	0.4968	2	11½	2.219	2.2881	2.3044
3/8	18	0.577	0.6218	0.6322	2½	8	2.650	2.7504	2.7739
1/2	14	0.715	0.7717	0.7851	3	8	3.277	3.3768	3.4002
3/4	14	0.925	0.9822	0.9956	3½	8	3.777	3.8771	3.9005
1	11½	1.161	1.2305	1.2468	4	8	4.275	4.3754	4.3988
1¼	11½	1.506	1.5752	1.5915	…	…	…	…	…

[a] As the ANSI Standard Pipe Thread form is maintained, the major and minor diameters of the internal thread vary with the pitch diameter. All dimensions are given in inches.

[b] The actual pitch diameter of the straight tapped hole will be slightly smaller than the value given when gaged with a taper plug gage as called for in ANSI/ASME B1.20.1.

Railing Joint Taper Pipe Threads, NPTR.— Railing joints require a rigid mechanical thread joint with external and internal taper threads. The external thread is basically the same as the ANSI Standard Taper Pipe Thread, except that sizes ½ through 2 inches are shortened by 3 threads and sizes 2½ through 4 inches are shortened by 4 threads to permit the use of the larger end of the pipe thread. A recess in the fitting covers the last scratch or imperfect threads on the pipe.

Straight Pipe Threads in Pipe Couplings, NPSC.— Threads in pipe couplings made in accordance with the ANSI/ASME B1.20.1 specifications are straight (parallel) threads of the same thread form as the ANSI Standard Taper Pipe Thread. They are used to form pressuretight joints when assembled with an ANSI Standard external taper pipe thread and made up with lubricant or sealant. These joints are recommended for comparatively low pressures only.

Straight Pipe Threads for Mechanical Joints, NPSM, NPSL, and NPSH.— While external and internal taper pipe threads are recommended for pipe joints in practically every service, there are mechanical joints where straight pipe threads are used to advantage. Three types covered by ANSI/ASME B1.20.1 are:

Loose-fitting Mechanical Joints With Locknuts (External and Internal), NPSL: This thread is designed to produce a pipe thread having the largest diameter that it is possible to cut on standard pipe. The dimensions of these threads are given in Table 5. It will be noted that the maximum major diameter of the external thread is slightly greater than the nominal outside diameter of the pipe. The normal manufacturer's variation in pipe diameter provides for this increase.

Loose-fitting Mechanical Joints for Hose Couplings (External and Internal), NPSH:

Hose coupling joints are ordinarily made with straight internal and external loose-fitting threads. There are several standards of hose threads having various diameters and pitches. One of these is based on the ANSI Standard pipe thread and by the use of this thread series, it is possible to join small hose couplings in sizes ½ to 4 inches, inclusive, to ends of standard pipe having ANSI Standard External Pipe Threads, using a gasket to seal the joints. For the hose coupling thread dimensions see *ANSI Standard Hose Coupling Screw Threads* starting on page 1872.

Free-fitting Mechanical Joints for Fixtures (External and Internal), NPSM: Standard iron, steel, and brass pipe are often used for special applications where there are no internal pressures. Where straight thread joints are required for mechanical assemblies, straight pipe threads are often found more suitable or convenient. Dimensions of these threads are given in Table 5.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. American National Standard Straight Pipe Threads for Mechanical Joints, NPSM and NPSL *ANSI/ASME B1.20.1-1983 (R2001)*

Nominal Pipe Size	Threads per Inch	External Thread					Internal Thread			
			Major Diameter		Pitch Diameter		Minor Diameter		Pitch Diameter	
		Allowance	Max.[a]	Min.	Max.	Min.	Min.[a]	Max.	Min.[b]	Max.
Free-fitting Mechanical Joints for Fixtures—NPSM										
1/8	27	0.0011	0.397	0.390	0.3725	0.3689	0.358	0.364	0.3736	0.3783
1/4	18	0.0013	0.526	0.517	0.4903	0.4859	0.468	0.481	0.4916	0.4974
3/8	18	0.0014	0.662	0.653	0.6256	0.6211	0.603	0.612	0.6270	0.6329
1/2	14	0.0015	0.823	0.813	0.7769	0.7718	0.747	0.759	0.7784	0.7851
3/4	14	0.0016	1.034	1.024	0.9873	0.9820	0.958	0.970	0.9889	0.9958
1	11½	0.0017	1.293	1.281	1.2369	1.2311	1.201	1.211	1.2386	1.2462
1¼	11½	0.0018	1.638	1.626	1.5816	1.5756	1.546	1.555	1.5834	1.5912
1½	11½	0.0018	1.877	1.865	1.8205	1.8144	1.785	1.794	1.8223	1.8302
2	11½	0.0019	2.351	2.339	2.2944	2.2882	2.259	2.268	2.2963	2.3044
2½	8	0.0022	2.841	2.826	2.7600	2.7526	2.708	2.727	2.7622	2.7720
3	8	0.0023	3.467	3.452	3.3862	3.3786	3.334	3.353	3.3885	3.3984
3½	8	0.0023	3.968	3.953	3.8865	3.8788	3.835	3.848	3.8888	3.8988
4	8	0.0023	4.466	4.451	4.3848	4.3771	4.333	4.346	4.3871	4.3971
5	8	0.0024	5.528	5.513	5.4469	5.4390	5.395	5.408	5.4493	5.4598
6	8	0.0024	6.585	6.570	6.5036	6.4955	6.452	6.464	6.5060	6.5165
Loose-fitting Mechanical Joints for Locknut Connections—NPSL										
1/8	27	…	0.409	…	0.3840	0.3805	0.362	…	0.3863	0.3898
1/4	18	…	0.541	…	0.5038	0.4986	0.470	…	0.5073	0.5125
3/8	18	…	0.678	…	0.6409	0.6357	0.607	…	0.6444	0.6496
1/2	14	…	0.844	…	0.7963	0.7896	0.753	…	0.8008	0.8075
3/4	14	…	1.054	…	1.0067	1.0000	0.964	…	1.0112	1.0179
1	11½	…	1.318	…	1.2604	1.2523	1.208	…	1.2658	1.2739
1¼	11½	…	1.663	…	1.6051	1.5970	1.553	…	1.6106	1.6187
1½	11½	…	1.902	…	1.8441	1.8360	1.792	…	1.8495	1.8576
2	11½	…	2.376	…	2.3180	2.3099	2.265	…	2.3234	2.3315
2½	8	…	2.877	…	2.7934	2.7817	2.718	…	2.8012	2.8129
3	8	…	3.503	…	3.4198	3.4081	3.344	…	3.4276	3.4393
3½	8	…	4.003	…	3.9201	3.9084	3.845	…	3.9279	3.9396
4	8	…	4.502	…	4.4184	4.4067	4.343	…	4.4262	4.4379
5	8	…	5.564	…	5.4805	5.4688	5.405	…	5.4884	5.5001
6	8	…	6.620	…	6.5372	6.5255	6.462	…	6.5450	6.5567
8	8	…	8.615	…	8.5313	8.5196	8.456	…	8.5391	8.5508
10	8	…	10.735	…	10.6522	10.6405	10.577	…	10.6600	10.6717
12	8	…	12.732	…	12.6491	12.6374	12.574	…	12.6569	12.6686

[a] As the ANSI Standard Straight Pipe Thread form of thread is maintained, the major and the minor diameters of the internal thread and the minor diameter of the external thread vary with the pitch diameter. The major diameter of the external thread is usually determined by the diameter of the pipe. These theoretical diameters result from adding the depth of the truncated thread ($0.666025 \times p$) to the maximum pitch diameters, and it should be understood that commercial pipe will not always have these maximum major diameters.

[b] This is the same as the pitch diameter at end of internal thread, E_1 *Basic*. (See Table 1a.)

All dimensions are given in inches.

Notes for Free-fitting Fixture Threads: The minor diameters of external threads and major diameters of internal threads are those as produced by commercial straight pipe dies and commercial ground straight pipe taps.

The major diameter of the external thread has been calculated on the basis of a truncation of $0.10825p$, and the minor diameter of the internal thread has been calculated on the basis of a truncation of $0.21651p$, to provide no interference at crest and root when product is gaged with gages made in accordance with the Standard.

Notes for Loose-fitting Locknut Threads: The locknut thread is established on the basis of retaining the greatest possible amount of metal thickness between the bottom of the thread and the inside of the pipe. In order that a locknut may fit loosely on the externally threaded part, an allowance equal to the "increase in pitch diameter per turn" is provided, with a tolerance of 1½ turns for both external and internal threads.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard Dryseal Pipe Threads for Pressure-Tight Joints.— Dryseal pipe threads are based on the USA (American) pipe thread; however, they differ in that they are designed to seal pressure-tight joints without the necessity of using sealing compounds. To accomplish this, some modification of thread form and greater accuracy in manufacture is required. The roots of both the external and internal threads are truncated slightly more than the crests, i.e., roots have wider flats than crests so that metal-to-metal contact occurs at the crests and roots coincident with, or prior to, flank contact. Thus, as the threads are assembled by wrenching, the roots of the threads crush the sharper crests of the mating threads. This sealing action at both major and minor diameters tends to prevent spiral leakage and makes the joints pressure-tight without the necessity of using sealing compounds, provided that the threads are in accordance with standard specifications and tolerances and are not damaged by galling in assembly. The control of crest and root truncation is simplified by the use of properly designed threading tools. Also, it is desirable that both external and internal threads have full thread height for the length of hand engagement. Where not functionally objectionable, the use of a compatible lubricant or sealant is permissible to minimize the possibility of galling. This is desirable in assembling Dryseal pipe threads in refrigeration and other systems to effect a pressure-tight seal. The crest and root of Dryseal pipe threads may be slightly rounded, but are acceptable if they lie within the truncation limits given in Table 6.

Table 6. American National Standard Dryseal Pipe Threads—Limits on Crest and Root Truncation *ANSI B1.20.3-1976 (R1998)*

Threads Per Inch	Height of Sharp V Thread (*H*)	Truncation							
		Minimum				Maximum			
		At Crest		At Root		At Crest		At Root	
		Formula	Inch	Formula	Inch	Formula	Inch	Formula	Inch
27	0.03208	0.047*p*	0.0017	0.094*p*	0.0035	0.094*p*	0.0035	0.140*p*	0.0052
18	0.04811	0.047*p*	0.0026	0.078*p*	0.0043	0.078*p*	0.0043	0.109*p*	0.0061
14	0.06180	0.036*p*	0.0026	0.060*p*	0.0043	0.060*p*	0.0043	0.085*p*	0.0061
11½	0.07531	0.040*p*	0.0035	0.060*p*	0.0052	0.060*p*	0.0052	0.090*p*	0.0078
8	0.10825	0.042*p*	0.0052	0.055*p*	0.0069	0.055*p*	0.0069	0.076*p*	0.0095

All dimensions are given in inches. In the formulas, p = pitch.

Types of Dryseal Pipe Thread.— American National Standard ANSI B1.20.3-1976 (R1998) covers four types of standard Dryseal pipe threads:

NPTF, Dryseal USA (American) Standard Taper Pipe Thread
PTF-SAE SHORT, Dryseal SAE Short Taper Pipe Thread
NPSF, Dryseal USA (American) Standard Fuel Internal Straight Pipe Thread
NPSI, Dryseal USA (American) Standard Intermediate Internal Straight Pipe Thread

Table 7. Recommended Limitation of Assembly among the Various Types of Dryseal Threads

External Dryseal Thread		For Assembly with Internal Dryseal Thread	
Type	Description	Type	Description
1	NPTF (tapered), ext thd	1	NPTF (tapered), int thd
		2[a,b]	PTF-SAE SHORT (tapered), int thd
		3[a,c]	NPSF (straight), int thd
		4[a,c,d]	NPSI (straight), int thd
2[a,e]	PTF-SAE SHORT (tapered) ext thd	4	NPSI (straight), int thd
		1	NPTF (tapered), int thd

[a] Pressure-tight joints without the use of a sealant can best be ensured where both components are threaded with NPTF (full length threads), since theoretically interference (sealing) occurs at all threads, but there are two less threads engaged than for NPTF assemblies. When straight internal threads are used, there is interference only at one thread depending on ductility of materials.

Copyright 2004, Industrial Press, Inc., New York, NY

[b] PTF-SAE SHORT internal threads are primarily intended for assembly with type 1-NPTF external threads. They are not designed for, and at extreme tolerance limits may not assemble with, type 2-PTF-SAE SHORT external threads.

[c] There is no external straight Dryseal thread.

[d] NPSI internal threads are primarily intended for assembly with type 2-PTF-SAE SHORT external threads but will also assemble with full length type 1 NPTF external threads.

[e] PTF-SAE SHORT external threads are primarily intended for assembly with type 4-NPSI internal threads but can also be used with type 1-NPTF internal threads. They are not designed for, and at extreme tolerance limits may not assemble with, type 2-PTF-SAE SHORT internal threads or type 3-NPSF internal threads.

An assembly with straight internal pipe threads and taper external pipe threads is frequently more advantageous than an all taper thread assembly, particularly in automotive and other allied industries where economy and rapid production are major considerations. Dryseal threads are not used in assemblies in which both components have straight pipe threads.

NPTF Threads: This type applies to both external and internal threads and is suitable for pipe joints in practically every type of service. Of all Dryseal pipe threads, NPTF external and internal threads mated are generally conceded to be superior for strength and seal since they have the longest length of thread and, theoretically, interference (sealing) occurs at every engaged thread root and crest. Use of tapered internal threads, such as NPTF or PTF-SAE SHORT in hard or brittle materials having thin sections will minimize the possibility of fracture.

There are two classes of NTPF threads. Class 1 threads are made to interfere (seal) at root and crest when mated, but inspection of crest and root truncation is not required. Consequently, Class 1 threads are intended for applications where close control of tooling is required for conformance of truncation or where sealing is accomplished by means of a sealant applied to the threads.

Class 2 threads are theoretically identical to those made to Class 1, however, inspection of root and crest truncation is required. Consequently, where a sealant is not used, there is more assurance of a pressure-tight seal for Class 2 threads than for Class 1 threads.

PTF-SAE SHORT Threads: External threads of this type conform in all respects with NPTF threads except that the thread length has been shortened by eliminating one thread from the small (entering) end. These threads are designed for applications where clearance is not sufficient for the full length of the NPTF threads or for economy of material where the full thread length is not necessary.

Internal threads of this type conform in all respects with NPTF threads, except that the thread length has been shortened by eliminating one thread from the large (entry) end. These threads are designed for thin materials where thickness is not sufficient for the full thread length of the NPTF threads or for economy in tapping where the full thread length is not necessary.

Pressure-tight joints without the use of lubricant or sealer can best be ensured where mating components are both threaded with NPTF threads. This should be considered before specifying PTF-SAE SHORT external or internal threads.

NPSF Threads: Threads of this type are straight (cylindrical) instead of tapered and are internal only. They are more economical to produce than tapered internal threads, but when assembled do not offer as strong a guarantee of sealing since root and crest interference will not occur for all threads. NPSF threads are generally used with soft or ductile materials which will tend to adjust at assembly to the taper of external threads, but may be used in hard or brittle materials where the section is thick.

NPSI Threads: Threads of this type are straight (cylindrical) instead of tapered, are internal only and are slightly larger in diameter than NPSF threads but have the same tolerance and thread length. They are more economical to produce than tapered threads and may be used in hard or brittle materials where the section is thick or where there is little expansion at assembly with external taper threads. As with NPSF threads, NPSI threads when assembled do not offer as strong a guarantee of sealing as do tapered internal threads.

Copyright 2004, Industrial Press, Inc., New York, NY

For more complete specifications for production and acceptance of Dryseal pipe threads, see ANSI B1.20.3 (Inch) and ANSI B1.20.4 (Metric Translation), and for gaging and inspection, see ANSI B1.20.5 (Inch) and ANSI B1.20.6M (Metric Translation).

Designation of Dryseal Pipe Threads: The standard Dryseal pipe threads are designated by specifying in sequence nominal size, thread series symbol, and class:

Examples: 1/8-27 NPTF-1; 1/8-27 PTF-SAE SHORT; and 3/8-18 NPTF-1 AFTER PLATING.

Table 8. Suggested Tap Drill Sizes for Internal Dryseal Pipe Threads



Size	Probable Drill Oversize Cut (Mean)	Taper Pipe Thread: Minor Diameter At Distance L_1 From Large End	Taper Pipe Thread: Minor Diameter At Distance $L_1 + L_3$ From Large End	Taper Pipe Thread: Drill Size[a] Without Reamer	Taper Pipe Thread: Drill Size[a] With Reamer	Straight Pipe Thread: Minor Diameter NPSF	Straight Pipe Thread: Minor Diameter NPSI	Straight Pipe Thread: Drill Size[a]
1/16–27	0.0038	0.2443	0.2374	"C" (0.242)	"A" (0.234)	0.2482	0.2505	"D" (0.246)
1/8–27	0.0044	0.3367	0.3298	"Q" (0.332)	21/64 (0.328)	0.3406	0.3429	"R" (0.339)
1/4–18	0.0047	0.4362	0.4258	7/16 (0.438)	27/64 (0.422)	0.4422	0.4457	7/16 (0.438)
3/8–18	0.0049	0.5708	0.5604	9/16 (0.562)	9/16 (0.563)	0.5776	0.5811	37/64 (0.578)
1/2–14	0.0051	0.7034	0.6901	45/64 (0.703)	11/16 (0.688)	0.7133	0.7180	45/64 (0.703)
3/4–14	0.0060	0.9127	0.8993	29/32 (0.906)	57/64 (0.891)	0.9238	0.9283	59/64 (0.922)
1–11½	0.0080	1.1470	1.1307	1 9/64 (1.141)	1 1/8 (1.125)	1.1600	1.1655	1 5/32 (1.156)
1¼–11½	0.0100	1.4905	1.4742	1 31/64 (1.484)	1 15/32 (1.469)	…	…	…
1½–11½	0.0120	1.7295	1.7132	1 23/32 (1.719)	1 45/64 (1.703)	…	…	…
2–11½	0.0160	2.2024	2.1861	2 3/16 (2.188)	2 11/64 (2.172)	…	…	…
2½–8	0.0180	2.6234	2.6000	2 39/64 (2.609)	2 37/64 (2.578)	…	…	…
3–8	0.0200	3.2445	3.2211	3 15/64 (3.234)	3 13/64 (3.203)	…	…	…

[a] Some drill sizes listed may not be standard drills.

All dimensions are given in inches.

Special Dryseal Threads.— Where design limitations, economy of material, permanent installation, or other limiting conditions prevail, consideration may be given to using a special Dryseal thread series.

Dryseal Special Short Taper Pipe Thread, PTF-SPL SHORT: Threads of this series conform in all respects to PTF-SAE SHORT threads except that the full thread length has been further shortened by eliminating one thread at the small end of internal threads or one thread at the large end of external threads.

Copyright 2004, Industrial Press, Inc., New York, NY

Dryseal Special Extra Short Taper Pipe Thread, PTF-SPL EXTRA SHORT: Threads of this series conform in all respects to PTF-SAE SHORT threads except that the full thread length has been further shortened by eliminating two threads at the small end of internal threads or two threads at the large end of external threads.

Limitations of Assembly: Table 9 applies where Dryseal Special Short or Extra Short Taper Pipe Threads are to be assembled as special combinations.

Table 9. Assembly Limitations for Special Combinations of Dryseal Threads

Thread	May Assemble with[a]	May Assemble with[b]
PTF SPL SHORT EXTERNAL PTF SPL EXTRA SHORT EXTERNAL	PTF-SAE SHORT INTERNAL NPSF INTERNAL PTF SPL SHORT INTERNAL PTF SPL EXTRA SHORT INTERNAL	NPTF or NPSI INTERNAL
PTF SPL SHORT INTERNAL PTF SPL EXTRA SHORT INTERNAL	PTF-SAE SHORT EXTERNAL	NPTF EXTERNAL

[a] Only when the external thread or the internal thread or both are held closer than the standard tolerance, the external thread toward the minimum and the internal thread toward the maximum pitch diameter to provide a minimum of one turn hand engagement. At extreme tolerance limits the shortened full-thread lengths reduce hand engagement and the threads may not start to assemble.

[b] Only when the internal thread or the external thread or both are held closer than the standard tolerance, the internal thread toward the minimum and the external thread toward the maximum pitch diameter to provide a minimum of two turns for wrench make-up and sealing. At extreme tolerance limits the shortened full-thread lengths reduce wrench make-up and the threads may not seal.

Dryseal Fine Taper Thread Series, F-PTF: The need for finer pitches for nominal pipe sizes has brought into use applications of 27 threads per inch to $\frac{1}{4}$- and $\frac{3}{8}$-inch pipe sizes. There may be other needs that require finer pitches for larger pipe sizes. It is recommended that the existing threads per inch be applied to the next larger pipe size for a fine thread series, thus: $\frac{1}{4}$-27, $\frac{3}{8}$-27, $\frac{1}{2}$-18, $\frac{3}{4}$-18, 1-14, $1\frac{1}{4}$-14, $1\frac{1}{2}$-14, and 2-14. This series applies to external and internal threads of full length and is suitable for applications where threads finer than NPTF are required.

Dryseal Special Diameter-Pitch Combination Series, SPL-PTF: Other applications of diameter-pitch combinations have come into use where taper pipe threads are applied to nominal size thin wall tubing. These combinations are: $\frac{1}{2}$-27, $\frac{5}{8}$-27, $\frac{3}{4}$-27, $\frac{7}{8}$-27, and 1-27. This series applies to external and internal threads of full length and is applicable to thin wall nominal diameter outside tubing.

Designation of Special Dryseal Pipe Threads: The designations used for these special dryseal pipe threads are as follows:

$\frac{1}{8}$-27 PTF-SPL SHORT

$\frac{1}{8}$-27 PTF-SPL EXTRA SHORT

$\frac{1}{2}$-27 SPL PTF, OD 0.500

Note that in the last designation the OD of tubing is given.

British Standard Pipe Threads

British Standard Pipe Threads for Non-pressure-tight Joints.— The threads in BS 2779:1973, "Specifications for Pipe Threads where Pressure-tight Joints are not Made on the Threads", are Whitworth form parallel fastening threads that are generally used for fastening purposes such as the mechanical assembly of component parts of fittings, cocks and valves. They are not suitable where pressure-tight joints are made on the threads.

The crests of the basic Whitworth thread form may be truncated to certain limits of size given in the Standard except on internal threads, when they are likely to be assembled with external threads conforming to the requirements of BS 21 "British Standard Pipe Threads for Pressure-tight Joints" (see page 1870).

Copyright 2004, Industrial Press, Inc., New York, NY

For external threads two classes of tolerance are provided and for internal, one class. The two classes of tolerance for external threads are Class A and Class B. For economy of manufacture the class B fit should be chosen whenever possible. The class A is reserved for those applications where the closer tolerance is essential. Class A tolerance is an entirely negative value, equivalent to the internal thread tolerance. Class B tolerance is an entirely negative value twice that of class A tolerance. Tables showing limits and dimensions are given in the Standard.

The thread series specified in this Standard shall be designated by the letter "G". A typical reference on a drawing might be "G½", for internal thread; "G½A", for external thread, class A: and "G ½ B", for external thread, class B. Where no class reference is stated for external threads, that of class B will be assumed. The designation of truncated threads shall have the addition of the letter "T" to the designation, i.e., G ½T and G ½BT.

British Standard Pipe Threads (Non-pressure-tight Joints)
Metric and Inch Basic Sizes *BS 2779:1973*

Nominal Size, Inches	Threads per Inch[a]	Depth of Thread	Major Diameter	Pitch Diameter	Minor Diameter	Nominal Size, Inches	Threads per Inch[a]	Depth of Thread	Major Diameter	Pitch Diameter	Minor Diameter
1/16	28	0.581	7.723	7.142	6.561	1¾	11	1.479	53.746	52.267	50.788
		0.0229	*0.3041*	*0.2812*	*0.2583*			*0.0582*	*2.1160*	*2.0578*	*1.9996*
⅛	28	0.581	9.728	9.147	8.566	2	11	1.479	59.614	58.135	56.656
		0.0229	*0.3830*	*0.3601*	*0.3372*			*0.0582*	*2.3470*	*2.2888*	*2.2306*
¼	19	0.856	13.157	12.301	11.445	2¼	11	1.479	65.710	64.231	62.752
		0.0337	*0.5180*	*0.4843*	*0.4506*			*0.0582*	*2.5870*	*2.5288*	*2.4706*
⅜	19	0.856	16.662	15.806	14.950	2½	11	1.479	75.184	73.705	72.226
		0.0337	*0.6560*	*0.6223*	*0.5886*			*0.0582*	*2.9600*	*2.9018*	*2.8436*
½	14	1.162	20.955	19.793	18.631	2¾	11	1.479	81.534	80.055	78.576
		0.0457	*0.8250*	*0.7793*	*0.7336*			*0.0582*	*3.2100*	*3.1518*	*3.0936*
⅝	14	1.162	22.911	21.749	20.587	3	11	1.479	87.884	86.405	84.926
		0.0457	*0.9020*	*0.8563*	*0.8106*			*0.0582*	*3.4600*	*3.4018*	*3.3436*
¾	14	1.162	26.441	25.279	24.117	3½	11	1.479	100.330	98.851	97.372
		0.0457	*1.0410*	*0.9953*	*0.9496*			*0.0582*	*3.9500*	*3.8918*	*3.8336*
⅞	14	1.162	30.201	29.039	27.877	4	11	1.479	113.030	111.551	110.072
		0.0457	*1.1890*	*1.1433*	*1.0976*			*0.0582*	*4.4500*	*4.3918*	*4.3336*
1	11	1.479	33.249	31.770	30.291	4½	11	1.479	125.730	124.251	122.772
		0.0582	*1.3090*	*1.2508*	*1.1926*			*0.0582*	*4.9500*	*4.8918*	*4.8336*
1⅛	11	1.479	37.897	36.418	34.939	5	11	1.479	138.430	136.951	135.472
		0.0582	*1.4920*	*1.4338*	*1.3756*			*0.0582*	*5.4500*	*5.3918*	*5.3336*
1¼	11	1.479	41.910	40.431	38.952	5½	11	1.479	151.130	149.651	148.172
		0.0582	*1.6500*	*1.5918*	*1.5336*			*0.0582*	*5.9500*	*5.8918*	*5.8336*
1½	11	1.479	47.803	46.324	44.845	6	11	1.479	163.830	162.351	160.872
		0.0582	*1.8820*	*1.8238*	*1.7656*			*0.0582*	*6.4500*	*6.3918*	*6.3336*

[a] The thread pitches in millimeters are as follows: 0.907 for 28 threads per inch. 1.337 for 19 threads per inch, 1.814 for 14 threads per inch, and 2.309 for 11 threads per inch.

Each basic metric dimension is given in roman figures (nominal sizes excepted) and each basic inch dimension is shown in italics directly beneath it.

British Standard Pipe Threads for Pressure-tight Joints.— The threads in BS 21:1973, "Specification for Pipe Threads where Pressure-tight Joints are Made on the Threads", are based on the Whitworth thread form and are specified as:

1) *Jointing threads:* These relate to pipe threads for joints made pressure-tight by the mating of the threads; they include taper external threads for assembly with either taper or parallel internal threads (parallel external pipe threads are not suitable as jointing threads)

2) *Longscrew threads:* These relate to parallel external pipe threads used for longscrews (connectors) specified in BS 1387 where a pressure-tight joint is achieved by the compression of a soft material onto the surface of the external thread by tightening a back nut against a socket

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard External and Internal Pipe Threads (Pressure-tight Joints)
Metric and Inch Dimensions and Limits of Size *BS 21:1973*

Nominal Size	No. of Threads per Inch[a]		Basic Diameters at Gage Plane			Gage Length		Number of Useful Threads on Pipe for Basic Gage Length[b]	Tolerance + and −	
			Major	Pitch	Minor	Basic	Tolerance (+ and −)		Gage Plane to Face of Int. Taper Thread	On Diameter of Parallel Int. Threads
1/16	28	{	7.723	7.142	6.561	(3/8)	(1)	(7/8)	(1/4)	0.071
			0.304	*0.2812*	*0.2583*	4.0	0.9	6.5	1.1	*0.0028*
1/8	28	{	9.728	9.147	8.566	(3/8)	(1)	(7/8)	(1/4)	0.071
			0.383	*0.3601*	*0.3372*	4.0	0.9	6.5	1.1	*0.0028*
1/4	19	{	13.157	12.301	11.445	(4/2)	(1)	(7/4)	(1/4)	0.104
			0.518	*0.4843*	*0.4506*	6.0	1.3	9.7	1.7	*0.0041*
3/8	19	{	16.662	15.806	14.950	(4/4)	(1)	(7/2)	(1/4)	0.104
			0.656	0.6223	0.5886	6.4	1.3	10.1	1.7	0.0041
1/2	14	{	20.955	19.793	18.631	(4/2)	(1)	(7/4)	(1/4)	0.142
			0.825	*0.7793*	*0.7336*	8.2	1.8	13.2	2.3	*0.0056*
3/4	14	{	26.441	25.279	24.117	(5/4)	(1)	(8)	(1/4)	0.142
			1.041	*0.9953*	*0.9496*	9.5	1.8	14.5	2.3	*0.0056*
1	11	{	33.249	31.770	30.291	(4/2)	(1)	(7/4)	(1/4)	0.180
			1.309	*1.2508*	*1.1926*	10.4	2.3	16.8	2.9	*0.0071*
1 1/4	11	{	41.910	40.431	38.952	(5/2)	(1)	(8/4)	(1/4)	0.180
			1.650	*1.5918*	*1.5336*	12.7	2.3	19.1	2.9	*0.0071*
1 1/2	11	{	47.803	46.324	44.845	(5/2)	(1)	(8/4)	(1/4)	0.180
			1.882	*1.8238*	*1.7656*	12.7	2.3	19.1	2.9	*0.0071*
2	11	{	59.614	58.135	56.656	(6/8)	(1)	(10/8)	(1/4)	0.180
			2.347	*2.2888*	*2.2306*	15.9	2.3	23.4	2.9	*0.0071*
2 1/2	11	{	75.184	73.705	72.226	(7 9/16)	(1/2)	(11 9/16)	(1/2)	0.216
			2.960	*2.9018*	*2.8436*	17.5	3.5	26.7	3.5	*0.0085*
3	11	{	87.884	86.405	84.926	(8 15/16)	(1/2)	(12 15/16)	(1/2)	0.216
			3.460	*3.4018*	*3.3436*	20.6	3.5	29.8	3.5	*0.0085*
4	11	{	113.030	111.551	110.072	(11)	(1/2)	(15/2)	(1/2)	0.216
			4.450	*4.3918*	*4.3336*	25.4	3.5	35.8	3.5	*0.0085*
5	11	{	138.430	136.951	135.472	(12 3/8)	(1/2)	(17 3/8)	(1/2)	0.216
			5.450	*5.3918*	*5.3336*	28.6	3.5	40.1	3.5	*0.0085*
6	11	{	163.830	162.351	160.872	(12 3/8)	(1/2)	(17 3/8)	(1/2)	0.216
			6.450	*6.3918*	*6.3336*	28.6	3.5	40.1	3.5	*0.0085*

[a] In the Standard BS 21:1973 the thread pitches in millimeters are as follows: 0.907 for 28 threads per inch, 1.337 for 19 threads per inch, 1.814 for 14 threads per inch, and 2.309 for 11 threads per inch.

[b] This is the minimum number of useful threads on the pipe for the basic gage length; for the maximum and minimum gage lengths, the minimum numbers of useful threads are, respectively, greater and less by the amount of tolerance in the column to the left. The design of internally threaded parts shall make allowance for receiving pipe ends of up to the minimum number of useful threads corresponding to the maximum gage length; the minimum number of useful *internal* threads shall be no less than 80 per cent of the minimum number of useful external threads for the minimum gage length.

Each basic metric dimension is given in roman figures (nominal sizes excepted) and each basic inch dimension is shown in italics directly beneath it. Figures in ( ) are numbers of turns of thread with metric linear equivalents given beneath. Taper of taper thread is 1 in 16 on diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

Hose Coupling Screw Threads

ANSI Standard Hose Coupling Screw Threads.— Threads for hose couplings, valves, and all other fittings used in direct connection with hose intended for domestic, industrial, and general service in sizes ½, ⅝, ¾, 1, 1¼, 1½, 2, 2½, 3, 3½, and 4 inches are covered by American National Standard ANSI/ASME B1.20.7-1991 These threads are designated as follows:

NH — Standard hose coupling threads of full form as produced by cutting or rolling.

NHR — Standard hose coupling threads for garden hose applications where the design utilizes thin walled material which is formed to the desired thread.

NPSH — Standard straight hose coupling thread series in sizes ½ to 4 inches for joining to American National Standard taper pipe threads using a gasket to seal the joint.

Thread dimensions are given in Table 1 and thread lengths in Table 2.



Fig. 1. Thread Form for ANSI Standard Hose Coupling Threads, NPSH, NH, and NHR. Heavy Line Shows Basic Size.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Standard Hose Coupling Threads for NPSH, NH, and NHR Nipples and Coupling Swivels *ANSI/ASME B1.20.7-1991*

Nominal Size of Hose	Threads per Inch	Thread Designation	Pitch	Basic Height of Thread	Nipple (External) Thread					Coupling (Internal) Thread				
					Major Dia.		Pitch Dia.		Minor Dia.	Minor Dia.		Pitch Dia.		Major Dia.
					Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.
½, ⅝, ¾	11.5	.75-11.5NH	.08696	.05648	1.0625	1.0455	1.0060	0.9975	0.9495	0.9595	0.9765	1.0160	1.0245	1.0725
½, ⅝, ¾	11.5	.75-11.5NHR	.08696	.05648	1.0520	1.0350	1.0100	0.9930	0.9495	0.9720	0.9930	1.0160	1.0280	1.0680
½	14	.5-14NPSH	.07143	.04639	0.8248	0.8108	0.7784	0.7714	0.7320	0.7395	0.7535	0.7859	0.7929	0.8323
¾	14	.75-14NPSH	.07143	.04639	1.0353	1.0213	0.9889	0.9819	0.9425	0.9500	0.9640	0.9964	1.0034	1.0428
1	11.5	1-11.5NPSH	.08696	.05648	1.2951	1.2781	1.2396	1.2301	1.1821	1.1921	1.2091	1.2486	1.2571	1.3051
1¼	11.5	1.25-11.5NPSH	.08696	.05648	1.6399	1.6229	1.5834	1.5749	1.5269	1.5369	1.5539	1.5934	1.6019	1.6499
1½	11.5	1.5-11.5 NPSH	.08696	.05648	1.8788	1.8618	1.8223	1.8138	1.7658	1.7758	1.7928	1.8323	1.8408	1.8888
2	11.5	2-11.5NPSH	.08696	.05648	2.3528	2.3358	2.2963	2.2878	2.2398	2.2498	2.2668	2.3063	2.3148	2.3628
2½	8	2.5-8NPSH	.12500	.08119	2.8434	2.8212	2.7622	2.7511	2.6810	2.6930	2.7152	2.7742	2.7853	2.8554
3	8	3-8NPSH	.12500	.08119	3.4697	3.4475	3.3885	3.3774	3.3073	3.3193	3.3415	3.4005	3.4116	3.4817
3½	8	3.5-8NPSH	.12500	.08119	3.9700	3.9478	3.8888	3.8777	3.8076	3.8196	3.8418	3.9008	3.9119	3.9820
4	8	4-8NPSH	.12500	.08119	4.4683	4.4461	4.3871	4.3760	4.3059	4.3179	4.3401	4.3991	4.4102	4.4803
4	6	4-6NH (SPL)	.16667	.10825	4.9082	4.8722	4.7999	4.7819	4.6916	4.7117	4.7477	4.8200	4.8380	4.9283

All dimensions are given in inches.

Dimensions given for the maximum minor diameter of the nipple are figured to the intersection of the worn tool arc with a centerline through crest and root. The minimum minor diameter of the nipple shall be that corresponding to a flat at the minor diameter of the minimum nipple equal to $\frac{1}{24}p$, and may be determined by subtracting $0.7939p$ from the minimum pitch diameter of the nipple. (See Fig. 1)

Dimensions given for the minimum major diameter of the coupling correspond to the basic flat, $\frac{1}{8}p$, and the profile at the major diameter produced by a worn tool must not fall below the basic outline. The maximum major diameter of the coupling shall be that corresponding to a flat at the major diameter of the maximum coupling equal to $\frac{1}{24}p$ and may be determined by adding $0.7939p$ to the maximum pitch diameter of the coupling. (See Fig. 1)

NH and NHR threads are used for garden hose applications. NPSH threads are used for steam, air and all other hose connections to be made up with standard pipe threads. NH (SPL) threads are used for marine applications.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Standard Hose Coupling Screw Thread Lengths
ANSI/ASME B1.20.7-1991



Nominal Size of Hose	Threads per Inch	I.D. of Nipple, *C*	Approx. O.D. of Ext. Thd.	Length of Nipple, *L*	Length of Pilot, *I*	Depth of Coupl., *H*	Coupl. Thd. Length, *T*	Approx. No. Thds. in Length *T*
½, ⅝, ¾	11.5	25/32	1 1/16	9/16	1/8	17/32	3/8	4¼
½, ⅝, ¾	11.5	25/32	1 1/16	9/16	1/8	17/32	3/8	4¼
½	14	17/32	13/16	½	1/8	15/32	5/16	4¼
¾	14	25/32	1 1/32	9/16	1/8	17/32	3/8	5¼
1	11.5	1 1/32	1 9/32	9/16	5/32	17/32	3/8	4¼
1¼	11.5	1 9/32	1 5/8	5/8	5/32	19/32	15/32	5½
1½	11.5	1 17/32	1 7/8	5/8	5/32	19/32	15/32	5½
2	11.5	2 1/32	2 11/32	¾	3/16	23/32	19/32	6¾
2½	8	2 17/32	2 27/32	1	¼	15/16	11/16	5½
3	8	3 1/32	3 15/32	1 1/8	¼	1 1/16	13/16	6½
3½	8	3 17/32	3 31/32	1 1/8	¼	1 1/16	13/16	6½
4	8	4 1/32	4 15/32	1 1/8	¼	1 1/16	13/16	6½
4	6	4	4 29/32	1 1/8	5/16	1 1/16	¾	4½

All dimensions are given in inches. For thread designation see Table 1.

American National Fire Hose Connection Screw Thread.— This thread is specified in the National Fire Protection Association's Standard NFPA No. 194-1974. It covers the dimensions for screw thread connections for fire hose couplings, suction hose couplings, relay supply hose couplings, fire pump suctions, discharge valves, fire hydrants, nozzles, adaptors, reducers, caps, plugs, wyes, siamese connections, standpipe connections, and sprinkler connections.

Form of Thread: The basic form of thread is as shown in Fig. 1. It has an included angle of 60 degrees and is truncated top and bottom. The flat at the root and crest of the basic thread form is equal to ⅛(0.125) times the pitch in inches. The height of the thread is equal to 0.649519 times the pitch. The outer ends of both external and internal threads are terminated by the blunt start or "Higbee Cut" on full thread to avoid crossing and mutilation of thread.

Thread Designation: The thread is designated by specifying in sequence the nominal size of the connection, number of threads per inch followed by the thread symbol NH.

Copyright 2004, Industrial Press, Inc., New York, NY

Thus, .75-8NH indicates a nominal size connection of 0.75 inch diameter with 8 threads per inch.

Basic Dimensions: The basic dimensions of the thread are as given in Table 1.

Table 1. Basic Dimensions of NH Threads ***NFPA 1963–1993 Edition***

Nom. Size	Threads per Inch (tpi)	Thread Designation	Pitch, *p*	Basic Thread Height, *h*	Minimum Internal Thread Dimensions		
					Min. Minor Dia.	Basic Pitch Dia.	Basic Major Dia.
¾	8	0.75-8 NH	0.12500	0.08119	1.2246	1.3058	1.3870
1	8	1-8 NH	0.12500	0.08119	1.2246	1.3058	1.3870
1½	9	1.5-9 NH	0.11111	0.07217	1.8577	1.9298	2.0020
2½	7.5	2.5-7.5 NH	0.13333	0.08660	2.9104	2.9970	3.0836
3	6	3-6 NH	0.16667	0.10825	3.4223	3.5306	3.6389
3½	6	3.5-6 NH	0.16667	0.10825	4.0473	4.1556	4.2639
4	4	4-4 NH	0.25000	0.16238	4.7111	4.8735	5.0359
4½	4	4.5-4 NH	0.25000	0.16238	5.4611	5.6235	5.7859
5	4	5-4 NH	0.25000	0.16238	5.9602	6.1226	6.2850
6	4	6-4 NH	0.25000	0.16238	6.7252	6.8876	7.0500
Nom. Size	Threads per Inch (tpi)	Thread Designation	Pitch, *p*	External Thread Dimensions (Nipple)			
				Allowance	Max.Major Dia.	Max. Pitch Dia.	Max Minor Dia.
¾	8	0.75-8 NH	0.12500	0.0120	1.3750	1.2938	1.2126
1	8	1-8 NH	0.12500	0.0120	1.3750	1.2938	1.2126
1½	9	1.5-9 NH	0.11111	0.0120	1.9900	1.9178	1.8457
2½	7.5	2.5-7.5 NH	0.13333	0.0150	3.0686	2.9820	2.8954
3	6	3-6 NH	0.16667	0.0150	3.6239	3.5156	3.4073
3½	6	3.5-6 NH	0.16667	0.0200	4.2439	4.1356	4.0273
4	4	4-4 NH	0.25000	0.0250	5.0109	4.8485	4.6861
4½	4	4.5-4 NH	0.25000	0.0250	5.7609	5.5985	5.4361
5	4	5-4 NH	0.25000	0.0250	6.2600	6.0976	5.9352
6	4	6-4 NH	0.25000	0.0250	7.0250	6.8626	6.7002

All dimensions are in inches.

Thread Limits of Size: Limits of size for NH external threads are given in Table 2. Limits of size for NH internal threads are given in Table 3.

Tolerances: The pitch-diameter tolerances for mating external and internal threads are the same. Pitch-diameter tolerances include lead and half-angle deviations. Lead deviations consuming one-half of the pitch-diameter tolerance are 0.0032 inch for ¾-, 1-, and 1½-inch sizes; 0.0046 inch for 2½-inch size; 0.0052 inch for 3-, and 3½-inch sizes; and 0.0072 inch for 4-, 4½-, 5-, and 6-inch sizes. Half-angle deviations consuming one-half of the pitch-diameter tolerance are 1 degree, 42 minutes for ¾- and 1-inch sizes; 1 degree, 54 minutes for 1½-inch size; 2 degrees, 17 minutes for 2½-inch size; 2 degrees, 4 minutes for 3- and 3½-inch size; and 1 degree, 55 minutes for 4-, 4½-, 5-, and 6-inch sizes.

Tolerances for the external threads are:
Major diameter tolerance = 2 × pitch-diameter tolerance
Minor diameter tolerance = pitch-diameter tolerance + 2*h*/9

The minimum minor diameter of the external thread is such as to result in a flat equal to one-third of the *p*/8 basic flat, or *p*/24, at the root when the pitch diameter of the external thread is at its minimum value. The maximum minor diameter is basic, but may be such as results from the use of a worn or rounded threading tool. The maximum minor diameter is shown in Fig. 1 and is the diameter upon which the minor diameter tolerance formula shown above is based.

Tolerances for the internal threads are:

Copyright 2004, Industrial Press, Inc., New York, NY

Minor diameter tolerance = 2 × pitch-diameter tolerance

The minimum minor diameter of the internal thread is such as to result in a basic flat, $p/8$, at the crest when the pitch diameter of the thread is at its minimum value.

Major diameter tolerance = pitch-diameter tolerance - $2h/9$

Table 2. Limits of Size and Tolerances for NH External Threads (Nipples)
NFPA 1963, 1993 Edition

Nom. Size	Threads per Inch (tpi)	External Thread (Nipple)						
		Major Diameter			Pitch Diameter			Minor[a] Dia.
		Max.	Min.	Toler.	Max.	Min.	Toler.	Max.
¾	8	1.3750	1.3528	0.0222	1.2938	1.2827	0.0111	1.2126
1	8	1.3750	1.3528	0.0222	1.2938	1.2827	0.0111	1.2126
1½	9	1.9900	1.9678	0.0222	1.9178	1.9067	0.0111	1.8457
2½	7.5	3.0686	3.0366	0.0320	2.9820	2.9660	0.0160	2.8954
3	6	3.6239	3.5879	0.0360	3.5156	3.4976	0.0180	3.4073
3½	6	4.2439	4.2079	0.0360	4.1356	4.1176	0.0180	4.0273
4	4	5.0109	4.9609	0.0500	4.8485	4.8235	0.0250	4.6861
4½	4	5.7609	5.7109	0.0500	5.5985	5.5735	0.0250	5.4361
5	4	6.2600	6.2100	0.0500	6.0976	6.0726	0.0250	5.9352
6	4	7.0250	6.9750	0.0500	6.8626	6.8376	0.0250	6.7002

[a] Dimensions given for the maximum minor diameter of the nipple are figured to the intersection of the worn tool arc with a center line through crest and root. The minimum minor diameter of the nipple shall be that corresponding to a flat at the minor diameter of the minimum nipple equal to $p/24$ and may be determined by subtracting $11h/9$ (or $0.7939p$) from the minimum pitch diameter of the nipple.

All dimensions are in inches.

Table 3. Limits of Size and Tolerances for NH Internal Threads (Couplings)
NFPA 1963, 1993 Edition

Nom. Size	Threads per Inch (tpi)	Internal Thread (Coupling)						
		Minor Diameter			Pitch Diameter			Major[a] Dia.
		Min.	Max.	Toler.	Min.	Max.	Toler.	Min.
¾	8	1.2246	1.2468	0.0222	1.3058	1.3169	0.0111	1.3870
1	8	1.2246	1.2468	0.0222	1.3058	1.3169	0.0111	1.3870
1½	9	1.8577	1.8799	0.0222	1.9298	1.9409	0.0111	2.0020
2½	7.5	2.9104	2.9424	0.0320	2.9970	3.0130	0.0160	3.0836
3	6	3.4223	3.4583	0.0360	3.5306	3.5486	0.0180	3.6389
3½	6	4.0473	4.0833	0.0360	4.1556	4.1736	0.0180	4.2639
4	4	4.7111	4.7611	0.0500	4.8735	4.8985	0.0250	5.0359
4½	4	5.4611	5.5111	0.0500	5.6235	5.6485	0.0250	5.7859
5	4	5.9602	6.0102	0.0500	6.1226	6.1476	0.0250	6.2850
6	4	6.7252	6.7752	0.0500	6.8876	6.9126	0.0250	7.0500

[a] Dimensions for the minimum major diameter of the coupling correspond to the basic flat ($p/8$), and the profile at the major diameter produced by a worn tool must not fall below the basic outline. The maximum major diameter of the coupling shall be that corresponding to a flat at the major diameter of the maximum coupling equal to $p/24$ and may be determined by adding $11h/9$ (or $0.7939p$) to the maximum pitch diameter of the coupling.

All dimensions are in inches.

Gages and Gaging: Full information on gage dimensions and the use of gages in checking the NH thread are given in NFPA Standard No. 1963, 1993 Edition, published by the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.

The information and data taken from this standard are reproduced with the permission of the NFPA.

Copyright 2004, Industrial Press, Inc., New York, NY

OTHER THREADS

Interference-Fit Threads

Interference-Fit Threads.— Interference-fit threads are threads in which the externally threaded member is larger than the internally threaded member when both members are in the free state and that, when assembled, become the same size and develop a holding torque through elastic compression, plastic movement of material, or both. By custom, these threads are designated Class 5.

The data in Tables 1, 2, and 3, which are based on years of research, testing and field study, represent an American standard for interference-fit threads that overcomes the difficulties experienced with previous interference-fit recommendations such as are given in Federal Screw Thread Handbook H28. These data were adopted as American Standard ASA B1.12-1963. Subsequently, the standard was revised and issued as American National Standard ANSI B1.12-1972. More recent research conducted by the Portsmouth Naval Shipyard has led to the current revision ASME/ANSI B1.12-1987 (R1998).

The data in Tables 1, 2, and 3 provide dimensions for external and internal interference-fit (Class 5) threads of modified American National form in the Coarse Thread series, sizes ¼ inch to 1½ inches. It is intended that interference-fit threads conforming with this standard will provide adequate torque conditions which fall within the limits shown in Table 3. The minimum torques are intended to be sufficient to ensure that externally threaded members will not loosen in service; the maximum torques establish a ceiling below which seizing, galling, or torsional failure of the externally threaded components is reduced.

Tables 1 and 2 give external and internal thread dimensions and are based on engagement lengths, external thread lengths, and tapping hole depths specified in Table 3 and in compliance with the design and application data given in the following paragraphs. Table 4 gives the allowances and Table 5 gives the tolerances for pitch, major, and minor diameters for the Coarse Thread Series.



Basic Profile of American National Standard Class 5 Interference Fit Thread

Copyright 2004, Industrial Press, Inc., New York, NY



Note: Plastic flow of interference metal into cavities at major and minor diameters is not illustrated.

Maximum and Minimum Material Limits for Class 5 Interference-Fit Thread

Design and Application Data for Class 5 Interference-Fit Threads.— Following are conditions of usage and inspection on which satisfactory application of products made to dimensions in Tables 1, 2, and 3 are based.

Thread Designations: The following thread designations provide a means of distinguishing the American Standard Class 5 Threads from the tentative Class 5 and alternate Class 5 threads, specified in Handbook H28. They also distinguish between external and internal American Standard Class 5 Threads.

Class 5 External Threads are designated as follows:

NC-5 HF—For driving in hard ferrous material of hardness over 160 BHN.

NC-5 CSF—For driving in copper alloy and soft ferrous material of 160 BHN or less.

NC-5 ONF—For driving in other nonferrous material (nonferrous materials other than copper alloys), any hardness.

Class 5 Internal Threads are designated as follows:

NC-5 IF—Entire ferrous material range.

NC-5 INF—Entire nonferrous material range.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. External Thread Dimensions for Class 5 Interference-Fit Threads
ANSI/ASME B1.12-1987 (R1998)

Nominal Size	Major Diameter, Inches						Pitch Diameter, Inches		Minor Diameter, Inches
	NC-5 HF for driving in ferrous material with hardness greater than 160 BHN $L_e = 1\frac{1}{4}$ Diam.		NC-5 CSF for driving in brass and ferrous material with hardness equal to or less than 160 BHN $L_e = 1\frac{1}{4}$ Diam.		NC-5 ONF for driving in nonferrous except brass (any hardness) $L_e = 2\frac{1}{2}$ Diam.				
	Max	Min	Max	Min	Max	Min	Max	Min	Max
0.2500–20	0.2470	0.2418	0.2470	0.2418	0.2470	0.2418	0.2230	0.2204	0.1932
0.3125–18	0.3080	0.3020	0.3090	0.3030	0.3090	0.3030	0.2829	0.2799	0.2508
0.3750–16	0.3690	0.3626	0.3710	0.3646	0.3710	0.3646	0.3414	0.3382	0.3053
0.4375–14	0.4305	0.4233	0.4330	0.4258	0.4330	0.4258	0.3991	0.3955	0.3579
0.5000–13	0.4920	0.4846	0.4950	0.4876	0.4950	0.4876	0.4584	0.4547	0.4140
0.5625–12	0.5540	0.5460	0.5575	0.5495	0.5575	0.5495	0.5176	0.5136	0.4695
0.6250–11	0.6140	0.6056	0.6195	0.6111	0.6195	0.6111	0.5758	0.5716	0.5233
0.7500–10	0.7360	0.7270	0.7440	0.7350	0.7440	0.7350	0.6955	0.6910	0.6378
0.8750– 9	0.8600	0.8502	0.8685	0.8587	0.8685	0.8587	0.8144	0.8095	0.7503
1.0000– 8	0.9835	0.9727	0.9935	0.9827	0.9935	0.9827	0.9316	0.9262	0.8594
1.1250– 7	1.1070	1.0952	1.1180	1.1062	1.1180	1.1062	1.0465	1.0406	0.9640
1.2500– 7	1.2320	1.2200	1.2430	1.2312	1.2430	1.2312	1.1715	1.1656	1.0890
1.3750– 6	1.3560	1.3410	1.3680	1.3538	1.3680	1.3538	1.2839	1.2768	1.1877
1.5000– 6	1.4810	1.4670	1.4930	1.4788	1.4930	1.4788	1.4089	1.4018	1.3127

Based on external threaded members being steel ASTM A-325 (SAE Grade 5) or better. L_e = length of engagement.

Table 2. Internal Thread Dimensions for Class 5 Interference-Fit Threads
ANSI/ASME B1.12-1987 (R1998)

Nominal Size	NC-5 IF Ferrous Material			NC-5 INF Nonferrous Material			Pitch Diameter		Major Diam.
	Minor Diam.[a]		Tap Drill	Minor Diam.[a]		Tap Drill			
	Min	Max		Min	Max		Min	Max	Min
0.2500–20	0.196	0.206	0.2031	0.196	0.206	0.2031	0.2175	0.2201	0.2532
0.3125–18	0.252	0.263	0.2610	0.252	0.263	0.2610	0.2764	0.2794	0.3161
0.3750–16	0.307	0.318	0.3160	0.307	0.318	0.3160	0.3344	0.3376	0.3790
0.4375–14	0.374	0.381	0.3750	0.360	0.372	0.3680	0.3911	0.3947	0.4421
0.5000–13	0.431	0.440	0.4331	0.417	0.429	0.4219	0.4500	0.4537	0.5050
0.5625–12	0.488	0.497	0.4921	0.472	0.485	0.4844	0.5084	0.5124	0.5679
0.6250–11	0.544	0.554	0.5469	0.527	0.540	0.5313	0.5660	0.5702	0.6309
0.7500–10	0.667	0.678	0.6719	0.642	0.655	0.6496	0.6850	0.6895	0.7565
0.8750– 9	0.777	0.789	0.7812	0.755	0.769	0.7656	0.8028	0.8077	0.8822
1.0000– 8	0.890	0.904	0.8906	0.865	0.880	0.8750	0.9188	0.9242	1.0081
1.1250– 7	1.000	1.015	1.0000	0.970	0.986	0.9844	1.0322	1.0381	1.1343
1.2500– 7	1.125	1.140	1.1250	1.095	1.111	1.1094	1.1572	1.1631	1.2593
1.3750– 6	1.229	1.247	1.2344	1.195	1.213	1.2031	1.2667	1.2738	1.3858
1.5000– 6	1.354	1.372	1.3594	1.320	1.338	1.3281	1.3917	1.3988	1.5108

[a] Fourth decimal place is 0 for all sizes.

All dimensions are in inches, unless otherwise specified.

Externally Threaded Products: Points of externally threaded components should be chamfered or otherwise reduced to a diameter below the minimum minor diameter of the thread. The limits apply to bare or metallic coated parts. The threads should be free from excessive nicks, burrs, chips, grit or other extraneous material before driving.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Torques, Interferences, and Engagement Lengths for Class 5 Interference-Fit Threads *ANSI/ASME B1.12-1987 (R1998)*

Nominal Size	Interference on Pitch Diameter		Engagement Lengths, External Thread Lengths and Tapped Hole Depths[a]						Torque at 1-½D Engagement in Ferrous Material	
			In Brass and Ferrous			In Nonferrous Except Brass				
	Max	Min	L_e	T_s	T_h min	L_e	T_s	T_h min	Max, lb-ft	Min, lb-ft
0.2500–20	.0055	.0003	0.312	0.375 + .125 – 0	0.375	0.625	0.688 + .125 – 0	0.688	12	3
0.3125–18	.0065	.0005	0.391	0.469 + .139 – 0	0.469	0.781	0.859 + .139 – 0	0.859	19	6
0.3750–16	.0070	.0006	0.469	0.562 + .156 – 0	0.562	0.938	1.031 + .156 – 0	1.031	35	10
0.4375–14	.0080	.0008	0.547	0.656 + .179 – 0	0.656	1.094	1.203 + .179 – 0	1.203	45	15
0.5000–13	.0084	.0010	0.625	0.750 + .192 – 0	0.750	1.250	1.375 + .192 – 0	1.375	75	20
0.5625–12	.0092	.0012	0.703	0.844 + .208 – 0	0.844	1.406	1.547 + .208 – 0	1.547	90	30
0.6250–11	.0098	.0014	0.781	0.938 + .227 – 0	0.938	1.562	1.719 + .227 – 0	1.719	120	37
0.7500–10	.0105	.0015	0.938	1.125 + .250 – 0	1.125	1.875	2.062 + .250 – 0	2.062	190	60
0.8750– 9	.0016	.0018	1.094	1.312 + .278 – 0	1.312	2.188	2.406 + .278 – 0	2.406	250	90
1.0000– 8	.0128	.0020	1.250	1.500 + .312 – 0	1.500	2.500	2.750 + .312 – 0	2.750	400	125
1.1250– 7	.0143	.0025	1.406	1.688 + .357 – 0	1.688	2.812	3.094 + .357 – 0	3.095	470	155
1.2500– 7	.0143	.0025	1.562	1.875 + .357 – 0	1.875	3.125	3.438 + .357 – 0	3.438	580	210
1.3750– 6	.0172	.0030	1.719	2.062 + .419 – 0	2.062	3.438	3.781 + .419 – 0	3.781	705	250
1.5000– 6	.0172	.0030	1.875	2.250 + .419 – 0	2.250	3.750	4.125 + .419 – 0	4.125	840	325

[a] L_e = Length of engagement. T_s = External thread length of full form thread. T_h = Minimum depth of full form thread in hole.

All dimensions are inches.

Materials for Externally Threaded Products: The length of engagement, depth of thread engagement and pitch diameter in Tables 1, 2, and 3 are designed to produce adequate torque conditions when heat-treated medium-carbon steel products, ASTM A-325 (SAE Grade 5) or better, are used. In many applications, case-carburized and nonheat-treated medium-carbon steel products of SAE Grade 4 are satisfactory. SAE Grades 1 and 2, may be usable under certain conditions. This standard is not intended to cover the use of products made of stainless steel, silicon bronze, brass or similar materials. When such materials are used, the tabulated dimensions will probably require adjustment based on pilot experimental work with the materials involved.

Lubrication: For driving in ferrous material, a good lubricant sealer should be used, particularly in the hole. A non-carbonizing type of lubricant (such as a rubber-in-water dispersion) is suggested. The lubricant must be applied to the hole and it may be applied to the male member. In applying it to the hole, care must be taken so that an excess amount of lubricant will not cause the male member to be impeded by hydraulic pressure in a blind hole. Where sealing is involved, the lubricant selected should be insoluble in the medium being sealed.

For driving, in nonferrous material, lubrication may not be needed. The use of medium gear oil for driving in aluminum is recommended. American research has observed that the minor diameter of lubricated tapped holes in non-ferrous materials may tend to close in, that is, be reduced in driving; whereas with an unlubricated hole the minor diameter may tend to open up.

Driving Speed: This standard makes no recommendation for driving speed. Some opinion has been advanced that careful selection and control of driving speed is desirable to obtain optimum results with various combinations of surface hardness and roughness. Experience with threads made to this standard may indicate what limitations should be placed on driving speeds.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Allowances for Coarse Thread Series *ANSI/ASME B1.12-1987 (R1998)*

TPI	Difference between Nom. Size and Max Major Diam of NC-5 HF[a]	Difference between Nom. Size and Max Major Diam. of NC-5 CSF or NC-5 ONF[a]	Difference between Basic Minor Diam. and Min Minor Diam. of NC-5 IF[a]	Difference between Basic Minor Diam. and Min Minor Diam.of NC-5 INF	Max PD Inteference or Neg Allowance, Ext Thread[b]	Difference between Max Minor Diam. and Basic Minor Diam., Ext Thread
20	0.0030	0.0030	0.000	0.000	0.0055	0.0072
18	0.0045	0.0035	0.000	0.000	0.0065	0.0080
16	0.0060	0.0040	0.000	0.000	0.0070	0.0090
14	0.0070	0.0045	0.014	0.000	0.0080	0.0103
13	0.0080	0.0050	0.014	0.000	0.0084	0.0111
12	0.0085	0.0050	0.016	0.000	0.0092	0.0120
11	0.0110	0.0055	0.017	0.000	0.0098	0.0131
10	0.0140	0.0060	0.019	0.000	0.0105	0.0144
9	0.0150	0.0065	0.022	0.000	0.0116	0.0160
8	0.0165	0.0065	0.025	0.000	0.0128	0.0180
7	0.0180	0.0070	0.030	0.000	0.0143	0.0206
6	0.0190	0.0070	0.034	0.000	0.0172	0.0241

[a] The allowances in these columns were obtained from industrial research data.

[b] Negative allowance is the difference between the basic pitch diameter and pitch diameter value at maximum material condition.

All dimensions are in inches.

The difference between basic major diameter and internal thread minimum major diameter is 0.075*H* and is tabulated in Table 5.

Table 5. Tolerances for Pitch Diameter, Major Diameter, and Minor Diameter for Coarse Thread Series *ANSI/ASME B1.12-1987 (R1998)*

TPI	PD Tolerance for Ext and Int Threads[a]	Major Diam. Tolerance for Ext Thread[b]	Minor Diam. Tolerance for Int Thread NC-5 IF	Minor Diam. Tolerance for Int Thread NC-5 INF[c]	Tolerance 0.075*H* or 0.065*P* for Tap Major Diam.
20	0.0026	0.0052	0.010	0.010	0.0032
18	0.0030	0.0060	0.011	0.011	0.0036
16	0.0032	0.0064	0.011	0.011	0.0041
14	0.0036	0.0072	0.008	0.012	0.0046
13	0.0037	0.0074	0.008	0.012	0.0050
12	0.0040	0.0080	0.009	0.013	0.0054
11	0.0042	0.0084	0.010	0.013	0.0059
10	0.0045	0.0090	0.011	0.014	0.0065
9	0.0049	0.0098	0.012	0.014	0.0072
8	0.0054	0.0108	0.014	0.015	0.0093
7	0.0059	0.0118	0.015	0.015	0.0093
6	0.0071	0.0142	0.018	0.018	0.0108

[a] National Class 3 pitch diameter tolerance from ASA B1.1-1960.

[b] Twice the NC-3 pitch diameter tolerance.

[c] National Class 3 minor diameter tolerance from ASA B1.1-1960.

All dimensions are in inches.

Relation of Driving Torque to Length of Engagement: Torques increase directly as the length of engagement and this increase is proportionately more rapid as size increases. The standard does not establish recommended breakloose torques.

Surface Roughness: Surface roughnesss is not a required measurement. Roughness between 63 and 125 µin. Ra is recommended. Surface roughness greater than 125 µin. Ra may encourage galling and tearing of threads. Surfaces with roughness less than 63 µin. Ra may hold insufficient lubricant and wring or weld together.

Copyright 2004, Industrial Press, Inc., New York, NY

Lead and Angle Variations: The lead variation values tabulated in Table 6 are the maximum variations from specified lead between any two points not farther apart than the length of the standard GO thread gage. Flank angle variation values tabulated in Table 7 are maximum variations from the basic 30° angle between thread flanks and perpendiculars to the thread axis. The application of these data in accordance with ANSI/ASME B1.3M, the screw thread gaging system for dimensional acceptability, is given in the Standard. Lead variation does not change the volume of displaced metal, but it exerts a cumulative unilateral stress on the pressure side of the thread flank. Control of the difference between pitch diameter size and functional diameter size to within one-half the pitch diameter tolerance will hold lead and angle variables to within satisfactory limits. Both the variations may produce unacceptable torque and faulty assemblies.

Table 6. Maximum Allowable Variations in Lead and Maximum Equivalent Change in Functional Diameter *ANSI/ASME B1.12-1987 (R1998)*

Nominal Size	External and Internal Threads	
	Allowable Variation in Axial Lead (Plus or Minus)	Max Equivalent Change in Functional Diam. (Plus for Ext, Minus for Int)
0.2500–20	0.0008	0.0013
0.3125–18	0.0009	0.0015
0.3750–16	0.0009	0.0016
0.4375–14	0.0010	0.0018
0.5000–13	0.0011	0.0018
0.5625–12	0.0012	0.0020
0.6250–11	0.0012	0.0021
0.7500–10	0.0013	0.0022
0.8750– 9	0.0014	0.0024
1.0000– 8	0.0016	0.0027
1.1250– 7	0.0017	0.0030
1.2500– 7	0.0017	0.0030
1.3750– 6	0.0020	0.0036
1.5000– 6	0.0020	0.0036

All dimensions are in inches.

Note: The equivalent change in functional diameter applies to total effect of form errors.

Maximum allowable variation in lead is permitted only when all other form variations are zero.

For sizes not tabulated, maximum allowable variation in lead is equal to 0.57735 times one-half the pitch diameter tolerance.

Table 7. Maximum Allowable Variation in 30° Basic Half-Angle of External and Internal Screw Threads *ANSI/ASME B1.12-1987 (R1998)*

TPI	Allowable Variation in Half-Angle of Thread (Plus or Minus)	TPI	Allowable Variation in Half-Angle of Thread (Plus or Minus)	TPI	Allowable Variation in Half-Angle of Thread (Plus or Minus)
32	1° 30′	14	0° 55′	8	0° 45′
28	1° 20′	13	0° 55′	7	0° 45′
27	1° 20′	12	0° 50′	6	0° 40′
24	1° 15′	11½	0° 50′	5	0° 40′
20	1° 10′	11	0° 50′	4½	0° 40′
18	1° 05′	10	0° 50′	4	0° 40′
16	1° 00′	9	0° 50′	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Spark Plug Threads

British Standard for Spark Plugs BS 45:1972 (withdrawn).— This revised British Standard refers solely to spark plugs used in automobiles and industrial spark ignition internal combustion engines. The basic thread form is that of the ISO metric (see page 1816). In assigning tolerances to the threads of the spark plug and the tapped holes, full consideration has been given to the desirability of achieving the closest possible measure of interchangeability between British spark plugs and engines, and those made to the standards of other ISO Member Bodies.

Basic Thread Dimensions for Spark Plug and Tapped Hole in Cylinder Head

Nom. Size	Pitch	Thread	Major Dia.		Pitch Dia.		Minor Dia.	
			Max.	Min.	Max.	Min.	Max.	Min.
14	1.25	Plug	13.937[a]	13.725	13.125	12.993	12.402	12.181
14	1.25	Hole		14.00	13.368	13.188	12.912	12.647
18	1.5	Plug	17.933[a]	17.697	16.959	16.819	16.092	15.845
18	1.5	Hole		18.00	17.216	17.026	16.676	16.376

[a] Not specified

All dimensions are given in millimeters.

The tolerance grades for finished spark plugs and corresponding tapped holes in the cylinder head are: for 14 mm size, 6e for spark plugs and 6H for tapped holes which gives a minimum clearance of 0.063 mm; and for 18 mm size, 6e for spark plugs and 6H for tapped holes which gives a minimum clearance of 0.067 mm.

These minimum clearances are intended to prevent the possibility of seizure, as a result of combustion deposits on the bare threads, when removing the spark plugs and applies to both ferrous and non-ferrous materials. These clearances are also intended to enable spark plugs with threads in accordance with this standard to be fitted into existing holes.

SAE Spark-Plug Screw Threads.— The SAE Standard includes the following sizes: $\frac{7}{8}$-inch nominal diameter with 18 threads per inch: 18-millimeter nominal diameter with a 18-millimeter nominal diameter with 1.5-millimeter pitch; 14-millimeter nominal diameter with a 1.25-millimeter pitch; 10-millimeter nominal diameter with a 1.0 millimeter pitch; $\frac{3}{8}$-inch nominal diameter with 24 threads per inch; and $\frac{1}{4}$-inch nominal diameter with 32 threads per inch. During manufacture, in order to keep the wear on the threading tools within permissible limits, the threads in the spark plug GO (ring) gage should be truncated to the maximum minor diameter of the spark plug; and in the tapped hole GO (plug) gage to the minimum major diameter of the tapped hole.

SAE Standard Threads for Spark Plugs

Size[a] Nom. × Pitch	Major Diameter		Pitch Diameter		Minor Diameter	
	Max.	Min.	Max.	Min.	Max.	Min.
Spark Plug Threads, mm (inches)						
M18 × 1.5	17.933	17.803	16.959	16.853	16.053	…
	(0.07060)	(0.7009)	(0.6677)	(0.6635)	(0.6320)	…
M14 × 1.25	13.868	13.741	13.104	12.997	12.339	…
	(0.5460)	(0.5410)	(0.5159)	(0.5117)	(0.4858)	…
M12 × 1.25	11.862	11.735	11.100	10.998	10.211	…
	(0.4670)	(0.4620)	(0.4370)	(0.4330)	(0.4020)	…
M10 × 1.0	9.974	9.794	9.324	9.212	8.747	…
	(0.3927)	(0.3856)	(0.3671)	(0.3627)	(0.3444)	…

Copyright 2004, Industrial Press, Inc., New York, NY

SAE Standard Threads for Spark Plugs *(Continued)*

Size[a] Nom. × Pitch	Major Diameter		Pitch Diameter		Minor Diameter	
	Max.	Min.	Max.	Min.	Max.	Min.
Tapped Hole Threads, mm (inches)						
M18 × 1.5	…	18.039	17.153	17.026	16.426	16.266
	…	(0.7102)	(0.6753)	(0.6703)	(0.6467)	(0.6404)
M14 × 1.25	…	14.034	13.297	13.188	12.692	12.499
	…	(0.5525)	(0.5235)	(0.5192)	(0.4997)	(0.4921)
M12 × 1.25	…	12.000	11.242	11.188	10.559	10.366
	…	(0.4724)	(0.4426)	(0.4405)	(0.4157)	(0.4081)
M10 × 1.0	…	10.000	9.500	9.350	9.153	8.917
	…	(0.3937)	(0.3740)	(0.3681)	(0,3604)	(0.3511)

[a] M14 and M18 are preferred for new applications.

In order to keep the wear on the threading tools within permissible limits, the threads in the spark plug GO (ring) gage shall be truncated to the maximum minor diameter of the spark plug, and in the tapped hole GO (plug) gage to the minimum major diameter of the tapped hole. The plain plug gage for checking the minor diameter of the tapped hole shall be the minimum specified. The thread form is that of the ISO metric (see page 1816).

Reprinted with permission © 1990 Society of Automotive Engineers, Inc.

Lamp Base and Electrical Fixture Threads

Lamp Base and Socket Shell Threads.— The "American Standard" threads for lamp base and socket shells are sponsored by the American Society of Mechanical Engineers, the National Electrical Manufacturers' Association and by most of the large manufacturers of products requiring rolled threads on sheet metal shells or parts, such as lamp bases, fuse plugs, attachment plugs, etc. There are five sizes, designated as the "miniature size," the "candelabra size," the "intermediate size," the "medium size" and the "mogul size."

Rolled Threads for Screw Shells of Electric Sockets and Lamp Bases— American Standard



Size	Threads per Inch	Pitch *P*	Depth of Thread *D*	Radius Crest Root *R*	Major Dia. Max. *A*	Major Dia. Min. *a*	Minor Diam. Max. *B*	Minor Diam. Min. *b*
Male or Base Screw Shells Before Assembly								
Miniature	14	0.07143	0.020	0.0210	0.375	0.370	0.335	0.330
Candelabra	10	0.10000	0.025	0.0312	0.465	0.460	0.415	0.410
Intermediate	9	0.11111	0.027	0.0353	0.651	0.645	0.597	0.591
Medium	7	0.14286	0.033	0.0470	1.037	1.031	0.971	0.965
Mogul	4	0.25000	0.050	0.0906	1.555	1.545	1.455	1.445
Socket Screw Shells Before Assembly								
Miniature	14	0.07143	0.020	0.0210	0.3835	0.3775	0.3435	0.3375
Candelabra	10	0.10000	0.025	0.0312	0.476	0.470	0.426	0.420
Intermediate	9	0.11111	0.027	0.0353	0.664	0.657	0.610	0.603
Medium	7	0.14286	0.033	0.0470	1.053	1.045	0.987	0.979
Mogul	4	0.25000	0.050	0.0906	1.577	1.565	1.477	1.465

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Base Screw Shell Gage Tolerances: Threaded ring gages—"Go," Max. thread size to minus 0.0003 inch; "Not Go," Min. thread size to plus 0.0003 inch. Plain ring gages—"Go," Max. thread O.D. to minus 0.0002 inch; "Not Go," Min. thread O.D. to plus 0.0002 inch.

Socket Screw Shell Gages: Threaded plug gages—"Go," Min. thread size to plus 0.0003 inch; "Not Go," Max. thread size to minus 0.0003 inch. Plain plug gages—"Go," Min. minor dia. to plus 0.0002 inch; "Not Go," Max. minor dia. to minus 0.0002 inch.

Check Gages for Base Screw Shell Gages: Threaded plugs for checking threaded ring gages—"Go," Max. thread size to minus 0.0003 inch; "Not Go," Min. thread size to plus 0.0003 inch.

Electric Fixture Thread.— The special straight electric fixture thread consists of a straight thread of the same pitches as the American standard pipe thread, and having the regular American or U. S. standard form; it is used for caps, etc. The male thread is smaller, and the female thread larger than those of the special straight-fixture pipe threads. The male thread assembles with a standard taper female thread, while the female thread assembles with a standard taper male thread. This thread is used when it is desired to have the joint "make up" on a shoulder. The gages used are straight-threaded limit gages.

Instrument and Microscope Threads

British Association Standard Thread (BA).— This form of thread is similar to the Whitworth thread in that the root and crest are rounded (see illustration). The angle, however, is only 47 degrees 30 minutes and the radius of the root and crest are proportionately larger. This thread is used in Great Britain and, to some extent, in other European countries for very small screws. Its use in the United States is practically confined to the manufacture of tools for export. This thread system was originated in Switzerland as a standard for watch and clock screws, and it is sometimes referred to as the "Swiss small screw thread standard." See also *Swiss Screw Thread*.

This screw thread system is recommended by the British Standards Institution for use in preference to the BSW and BSF systems for all screws smaller than $\frac{1}{4}$ inch except that the use of the "0" BA thread be discontinued in favor of the $\frac{1}{4}$-in. BSF. It is further recommended that in the selection of sizes, preference be given to even numbered BA sizes. The thread form is shown by the diagram.



British Association Thread

$$H = 1.13634 \times p$$
$$h = 0.60000 \times p$$
$$r = 0.18083 \times p$$
$$s = 0.26817 \times p$$

It is a symmetrical V-thread, of 47½ degree included angle, having its crests and roots rounded with equal radii, such that the basic depth of the thread is 0.6000 of the pitch. Where p = pitch of thread, H = depth of V-thread, h = depth of BA thread, r = radius at root and crest of thread, and s = root and crest truncation.

Copyright 2004, Industrial Press, Inc., New York, NY

British Association (BA) Standard Thread, Basic Dimensions
BS 93:1951 (obsolescent)

Designation Number	Pitch, mm	Depth of Thread, mm	Bolt and Nut			Radius, mm	Threads per Inch (approx.)
			Major Diameter, mm	Effective Diameter, mm	Minor Diameter, mm		
0	1.0000	0.600	6.00	5.400	4.80	0.1808	25.4
1	0.9000	0.540	5.30	4.760	4.22	0.1627	28.2
2	0.8100	0.485	4.70	4.215	3.73	0.1465	31.4
3	0.7300	0.440	4.10	3.660	3.22	0.1320	34.8
4	0.6600	0.395	3.60	3.205	2.81	0.1193	38.5
5	0.5900	0.355	3.20	2.845	2.49	0.1067	43.0
6	0.5300	0.320	2.80	2.480	2.16	0.0958	47.9
7	0.4800	0.290	2.50	2.210	1.92	0.0868	52.9
8	0.4300	0.260	2.20	1.940	1.68	0.0778	59.1
9	0.3900	0.235	1.90	1.665	1.43	0.0705	65.1
10	0.3500	0.210	1.70	1.490	1.28	0.0633	72.6
11	0.3100	0.185	1.50	1.315	1.13	0.0561	82.0
12	0.2800	0.170	1.30	1.130	0.96	0.0506	90.7
13	0.2500	0.150	1.20	1.050	0.90	0.0452	102
14	0.2300	0.140	1.00	0.860	0.72	0.0416	110
15	0.2100	0.125	0.90	0.775	0.65	0.0380	121
16	0.1900	0.115	0.79	0.675	0.56	0.0344	134

Tolerances and Allowances: Two classes of bolts and one for nuts are provided: *Close Class bolts* are intended for precision parts subject to stress, no allowance being provided between maximum bolt and minimum nut sizes. *Normal Class bolts* are intended for general commercial production and general engineering use; for sizes 0 to 10 BA, an allowance of 0.025 mm is provided.

Tolerance Formulas for British Association (BA) Screw Threads

	Class or Fit	Tolerance (+ for nuts, − for bolts)		
		Major Dia.	Effective Dia.	Minor Dia.
Bolts	Close Class 0 to 10 BA incl.	$0.15p$ mm	$0.08p + 0.02$ mm	$0.16p + 0.04$ mm
	Normal Class 0 to 10 BA incl.	$0.20p$ mm	$0.10p + 0.025$ mm	$0.20p + 0.05$ mm
	Normal Class 11 to 16 BA incl.	$0.25p$ mm	$0.10p + 0.025$ mm	$0.20p + 0.05$ mm
Nuts	All Classes		$0.12p + 0.03$ mm	$0.375p$ mm

In these formulas, p = pitch in millimeters.

Instrument Makers' Screw Thread System.— The standard screw system of the Royal Microscopical Society of London, also known as the "Society Thread," is employed for microscope objectives and the nose pieces of the microscope into which these objectives screw. The form of the thread is the standard Whitworth form. The number of threads per inch is 36. There is one size only. The maximum pitch diameter of the objective is 0.7804 inch and the minimum pitch diameter of the nose-piece is 0.7822 inch. The dimensions are as follows:

Male thread	outside dia.	max., 0.7982 inch	min., 0.7952 inch
	root dia.	max., 0.7626 inch	min., 0.7596 inch
Female thread	root of thread	max,. 0.7674 inch	min., 0.7644 inch
	top of thread	max., 0.8030 inch	min., 0.8000 inch

The Royal Photographic Society Standard Screw Thread ranges from 1-inch diameter upward. For screws less than 1 inch, the Microscopical Society Standard is used. The British Association thread is another thread system employed on instruments abroad.

American Microscope Objective Thread (AMO).— The standard, ANSI B1.11-1958 (R2001), describes the American microscope objective thread, AMO, the screw thread form used for mounting a microscope objective assembly to the body or lens turret of a microscope. This screw thread is also recommended for other microscope optical assem-

Copyright 2004, Industrial Press, Inc., New York, NY

bles as well as related applications such as photomicrographic equipment. It is based on, and intended to be interchangeable with, the screw thread produced and adopted many years ago by the Royal Microscopical Society of Great Britain, generally known as the RMS thread. While the standard is almost universally accepted as the basic standard for microscope objective mountings, formal recognition has been extremely limited.

The basic thread possesses the overall British Standard Whitworth form. (See *Whitworth Standard Thread Form* starting on page 1857). However, the actual design thread form implementation is based on the WWII era ASA B1.6-1944 "Truncated Whitworth Form" in which the rounded crests and roots are removed. ASA B1.6-1944 was withdrawn in 1951, however, ANSI B1.11-1958 (R2001) is still active for new design.

Design Requirements of Microscope Objective Threads: Due to the inherent longevity of optical equipment and the repeated use to which the objective threads are subjected, the following factors should be considered when designing microscope objective threads:

Adequate clearance to afford protection against binding due to the presence of foreign particles or minor crest damage.

Sufficient depth of thread engagement to assure security in the short lengths of engagement commonly encountered.

Allowances for limited eccentricities so that centralization and squareness of the objective are not influenced by such errors in manufacture.

Deviation from the Truncated Whitworth Thread Form: Although ANSI B1.11-1958 (R2001) is based on the withdrawn ASA B1.6-1944 truncated Whitworth standard, the previously described design requirements necessitate a deviation from the truncated Whitworth thread form. Some of the more significant modifications are:

A larger allowance on the pitch diameter of the external thread.

Smaller tolerances on the major diameter of the external thread and minor diameter of the internal thread.

The provision of allowances on the major and minor diameters of the external thread.

Thread Overview: The thread is a single start type. There is only one class of thread based on a basic major diameter of 0.800 in. and a pitch, p, of 0.027778 inch (36 threads per inch). The AMO thread shall be designated on drawings, tools and gages as "0.800–36 AMO." Thread nomenclature, definitions and terminology are based on ANSI B1.7-1965 (R1972), "Nomenclature, Threads, and Letter Symbols for Screw Threads."

It should also be noted that ISO 8038-1:1997 "Screw threads for objectives and related nosepieces" is also based on the 0.800 inch, 36 tpi RMS thread form.

Tolerances and Allowances: Tolerances are given in Table 2. A positive allowance (minimum clearance) of 0.0018 in. is provided for the pitch diamter E, major diameter D, and minor diameter, K

If interchangeability with full-form Whitworth threads is not required, the allowances for the major and minor diameters are not necessary, because the forms at the root and crest are truncated. In these cases, either both limits or only the maximum limit of the major and minor diameters may be increased by the amount of the allowance, 0.0018 inch.

Lengths of Engagement: The tolerances specified in Table 2 are applicable to lengths of engagement ranging from $\frac{1}{8}$ in. to $\frac{3}{8}$ inch, approximately 15% to 50% of the basic diameter. Microscope objective assembles generally have a length of engagement of $\frac{1}{8}$ inch. Lengths exceeding these limits are seldom employed and not covered in this standard.

Gage testing: Recommended ring and plug testing gage dimensions for the 0.800–36 AMO thread size can be found in ANSI B1.11–1958 (R2001), Appendix.

Dimensional Terminology: Because the active standard ANSI B1.11–1958 (R2001) is based on the withdrawn ASA Truncated Whitworth standard, dimensional nomenclature is described below.

Copyright 2004, Industrial Press, Inc., New York, NY



Tolerances, Allowances and Crest Clearances for Microscope Objective Thread (AMO)
ANSI B1.11–1958 (R2001)

Table 1. Definitions, Formulas, Basic and Design Dimensions
ANSI B1.11–1958 (R1994)

Symbol	Property	Formula	Dimension
	Basic Thread Form		
α	Half angle of thread	…	27°30’
2α	Included angle of thread	…	55°00’
n	Number of threads per inch	…	36
p	Pitch	$1/n$	0.027778
H	Height of fundamental triangle	$0.960491p$	0.026680
h_b	Height of basic thread	$0.640327p$	0.0178
r	Radius at crest and root of British Standard Whitworth basic thread (not used)	$0.137329p$	0.0038

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Definitions, Formulas, Basic and Design Dimensions**
ANSI B1.11–1958 (R1994)

Symbol	Property	Formula	Dimension
	Design Thread Form		
k	Height of truncated Whitworth thread	$h_b - U = 0.566410p$	0.0157
F_c	Width of flat at crest	$0.243624p$	0.0068
F_r	Width of flat at root	$0.166667p$	0.0046
U	Basic truncation of crest from basic Whitworth form	$0.073917p$	0.00205
	Basic and Design Sizes		
D	Major diameter, nominal and basic	…	0.800
D_n	Major diameter of internal thread	D	0.800
D_s	Major diameter of external thread[a]	D – 2U – G	0.7941
E	Pitch (effective) diameter, basic	$D - h_b$	0.7822
E_n	Pitch (effective) diameter of internal thread	$D - h_b$	0.7822
E_s	Pitch (effective) diameter of external thread[b]	$D - h_b$ – G	0.7804
K	Minor diameter, basic	$D - 2h_b$	0.7644
K_n	Minor diameter of internal thread	$D - 2k$	0.7685
K_s	Minor diameter of external thread[a]	$D - 2h_b$ – G	0.7626
G	Allowance at pitch (effective) diameter[a, b]	…	0.0018

[a] An allowance equal to that on the pitch diameter is also provided on the major and minor diameters of the external thread for additional clearance and centralizing.
[b] Allowance (minimum clearance) on pitch (effective) diameter is the same as the British RMS thread.
All dimensions are in inches.

Table 2. Limits of Size and Tolerances — 0.800–36 AMO Thread
ANSI B1.11–1958 (R2001)

Element	Major Diameter, D			Pitch Diameter, E			Minor Diameter, K		
	Max.	Min.	Tol.	Max.	Min.	Tol.	Max.	Min.	Tol.
External thread	0.7941	0.7911	0.0030	0.7804	0.7774	0.0030	0.7626	0.7552[a]	…
Internal thread	0.8092[b]	0.8000	…	0.7852	0.7822	0.0030	0.7715	0.7865	0.0030

[a] Extreme minimum minor diameter produced by a new threading tool having a minimum flat of $p/12 = 0.0023$ inch. This minimum diameter is not controlled by gages but by the form of the threading tool.
[b] Extreme maximum major diameter produced by a new threading tool having a minimum flat of $p/20 = 0.0014$ inch. This maximum diameter is not controlled by gages but by the form of the threading tool.

Tolerances on the internal thread are applied in a plus direction from the basic and design size and tolerances on the external thread are applied in a minus direction from its design (maximum material) size.

All dimensions are in inches.

Swiss Screw Thread.— This is a thread system originated in Switzerland as a standard for screws used in watch and clock making. The angle between the two sides of the thread is 47 degrees 30 minutes, and the top and bottom of the thread are rounded. This system has been adopted by the British Association as a standard for small screws, and is known as the British Association thread. See *British Association Standard Thread (BA)* on page 1885.

Copyright 2004, Industrial Press, Inc., New York, NY

Historical and Miscellaneous Threads

Aero-Thread.— The name "Aero-thread" has been applied to a patented screw thread system that is specially applicable in cases where the nut or internally threaded part is made from a soft material, such as aluminum or magnesium alloy, for the sake of obtaining lightness, as in aircraft construction, and where the screw is made from a high-strength steel to provide strength and good wearing qualities. The nut or part containing the internal thread has a 60-degree truncated form of thread. See Fig. 1. The screw, or stud, is provided with a semi-circular thread form, as shown. Between the screw and the nut there is an intermediary part known as a thread lining or insert, which is made in the form of a helical spring, so that it can be screwed into the nut. The stud, in turn, is then screwed into the thread formed by the semicircular part of the thread insert. When the screw is provided with a V-form of thread, like the American Standard, frequent loosening and tightening of the screw would cause rapid wear of the softer metal from which the nut is made; furthermore, all the threads might not have an even bearing on the mating threads. By using a thread insert which is screwed into the nut permanently, and which is made from a reasonably hard material like phosphor bronze, good wearing qualities are obtained. Also, the bearing or load is evenly distributed over all the threads of the nut since the insert, being in the form of a spring, can adjust itself to bear on all of the thread surfaces.



Fig. 1. The Basic Thread Form Used in the Aero-Thread System

Briggs Pipe Thread.— The Briggs pipe thread (now known as the American Standard) is used for threaded pipe joints and is the standard for this purpose in the United States. It derives its name from Robert Briggs.

Casing Thread.— The standard casing thread of the American Petroleum Institute has an included angle of 60 degrees and a taper of $\frac{3}{4}$ inch per foot.

The fourteen casing sizes listed in the 1942 revision have outside diameters ranging from $4\frac{1}{2}$ to 20 inches. All sizes have 8 threads per inch.

Rounded Thread Form: Threads for casing sizes up to $13\frac{3}{8}$ inches, inclusive, have rounded crests and roots, and the depth, measured perpendicular to the axis of the pipe, equals $0.626 \times \text{pitch} - 0.007 = 0.07125$ inch.

Truncated Form: Threads for the 16-and 20-inch casing sizes have fiat crests and roots. The depth equals $0.760 \times \text{pitch} = 0.0950$ inch. This truncated form is designated in the A.P.I. Standard as a "sharp thread."

Copyright 2004, Industrial Press, Inc., New York, NY

Cordeaux Thread.— The Cordeaux screw thread derives its name from John Henry Cordeaux, an English telegraph inspector who obtained a patent for this thread in 1877. This thread is used for connecting porcelain insulators with their stalks by means of a screw thread on the stalk and a corresponding thread in the insulator. The thread is approximately a Whitworth thread, 6 threads per inch, the diameters most commonly used being $\frac{5}{8}$ or $\frac{3}{4}$ inch outside diameter of thread; $\frac{5}{8}$ inch is almost universally used for telegraph purposes, while a limited number of $\frac{3}{4}$-inch sizes are used for large insulators.

Dardelet Thread.— The Dardelet patented self-locking thread is designed to resist vibrations and remain tight without auxiliary locking devices. The locking surfaces are the tapered root of the bolt thread and the tapered crest of the nut thread. The nut is free to turn until seated tightly against a resisting surface, thus causing it to shift from the free position (indicated by dotted lines) to the locking position. The locking is due to a wedging action between the tapered crest of the nut thread and the tapered root or binding surface of the bolt thread. This self-locking thread is also applied to set-screws and cap-screws. The holes must, of course, be threaded with Dardelet taps. The abutment sides of the Dardelet thread carry the major part of the tensile load. The nut is unlocked simply by turning it backward with a wrench. The Dardelet thread can either be cut or rolled, using standard equipment provided with tools, taps, dies, or rolls made to suit the Dardelet thread profile. The included thread angle is 29 degrees; depth $E = 0.3P$; maximum axial movement = 0.28 P. The major internal thread diameter (standard series) equals major external thread diameter plus 0.003 inch except for $\frac{1}{4}$-inch size which is plus 0.002 inch. The width of both external and internal threads at pitch line equals 0.36 P.

"Drunken" Thread.— A "drunken" thread, according to prevalent usage of this expression by machinists, etc., is a thread that does not coincide with a true helix or advance uniformly. This irregularity in a taper thread may be due to the fact that in taper turning with the tailstock set over, the work does not turn with a uniform angular velocity, while the cutting tool is advancing along the work longitudinally with a uniform linear velocity. The change in the pitch and the irregularity of the thread is so small as to be imperceptible to the eye, if the taper is slight, but as the tapers increase to, say, $\frac{3}{4}$ inch per foot or more, the errors become more pronounced. To avoid this defect, a taper attachment should be used for taper thread cutting.

Echols Thread.— Chip room is of great importance in machine taps and tapper taps where the cutting speed is high and always in one direction. The tap as well as the nut to be threaded is liable to be injured, if ample space for the chips to pass away from the cutting edges is not provided. A method of decreasing the number of cutting edges, as well as increasing the amount of chip room, is embodied in the "Echols thread," where every alternate tooth is removed. If a tap has an even number of flutes, the removal of every other tooth in the lands will be equivalent to the removal of the teeth of a continuous thread. It is, therefore, necessary that taps provided with this thread be made with an odd number of lands, so that removing the tooth in alternate lands may result in removing every other tooth in each individual land. Machine taps are often provided with the Echols thread.

French Thread (S.F.).— The French thread has the same form and proportions as the American Standard (formerly U. S. Standard). This French thread is being displaced gradually by the International Metric Thread System.

Harvey Grip Thread.— The characteristic feature of this thread is that one side inclines 44 degrees from a line at right angles to the axis, whereas the other side has an inclination of only 1 degree. This form of thread is sometimes used when there is considerable resistance or pressure in an axial direction and when it is desirable to reduce the radial or bursting pressure on the nut as much as possible. See *BUTTRESS THREADS*.

Copyright 2004, Industrial Press, Inc., New York, NY

Lloyd & Lloyd Thread.— The Lloyd & Lloyd screw thread is the same as the regular Whitworth screw thread in which the sides of the thread form an angle of 55 degrees with one another. The top and bottom of the thread are rounded.

Lock-Nut Pipe Thread.— The lock-nut pipe thread is a straight thread of the largest diameter which can be cut on a pipe. Its form is identical with that of the American or Briggs standard taper pipe thread. In general, "Go" gages only are required. These consist of a straight-threaded plug representing the minimum female lock-nut thread, and a straight-threaded ring representing the maximum male lock-nut thread. This thread is used only to hold parts together, or to retain a collar on the pipe. It is never used where a tight threaded joint is required.

Philadelphia Carriage Bolt Thread.— This is a screw thread for carriage bolts which is somewhat similar to a square thread, but having rounded corners at the top and bottom. The sides of the thread are inclined to an inclusive angle of $3\frac{1}{2}$ degrees. The width of the thread at the top is 0.53 times the pitch.

SAE Standard Screw Thread.— The screw thread standard of the Society of Automotive Engineers (SAE) is intended for use in the automotive industries of the United States. The SAE Standard includes a Coarse series, a Fine series, an 8-thread series, a 12-thread series, a 16-thread series, an Extra-fine series, and a Special-pitch series. The Coarse and Fine series, and also the 8-, 12- and 16-thread series, are exactly the same as corresponding series in the American Standard. The Extra-fine and Special-pitch series are SAE Standards only.

The American Standard thread *form* (or the form previously known as the U. S. Standard) is applied to all SAE Standard screw threads. The Extra-fine series has a total of six pitches ranging from 32 down to 16 threads per inch. The 16 threads per inch in the Extra-fine series, applies to all diameters from $1\frac{3}{4}$ up to 6 inches. This Extra-fine series is intended for use on relatively light sections; on parts requiring fine adjustment; where jar and vibration are important factors; when the thickness of a threaded section is relatively small as in tubing, and where assembly is made without the use of wrenches.

The SAE Special pitches include some which are finer than any in the Extra-fine series. The special pitches apply to a range of diameters extending from No. 10 (0.1900 inch) up to 6 inches. Each diameter has a range of pitches varying from five to eight. For example, a $\frac{1}{4}$ - inch diameter has six pitches ranging from 24 to 56 threads per inch, whereas a 6-inch diameter has eight pitches ranging from 4 to 16 threads per inch. These various SAE Standard series are intended to provide adequate screw thread specifications for all uses in the automotive industries.

Sellers Screw Thread.— The Sellers screw thread, later known as the 'United States standard thread," and now as the "American Standard," is the most commonly used screw thread in the United States. It was originated by William Sellers, of Philadelphia, and first proposed by him in a paper read before the Franklin Institute, in April, 1864. In 1868, it was adopted by the United States Navy and has since become the generally accepted standard screw thread in the United States.

Copyright 2004, Industrial Press, Inc., New York, NY

MEASURING SCREW THREADS

Measuring Screw Threads

Pitch and Lead of Screw Threads.— The *pitch* of a screw thread is the distance from the center of one thread to the center of the next thread. This applies no matter whether the screw has a single, double, triple or quadruple thread. The *lead* of a screw thread is the distance the nut will move forward on the screw if it is turned around one full revolution. In a single-threaded screw, the pitch and lead are equal, because the nut would move forward the distance from one thread to the next, if turned around once. In a double-threaded screw, the nut will move forward two threads, or twice the pitch, so that in this case the lead equals twice the pitch. In a triple-threaded screw, the lead equals three times the pitch, and so on.

The word "pitch" is often, although improperly, used to denote the *number of threads per inch*. Screws are spoken of as having a 12-pitch thread, when twelve threads per inch is what is really meant. The number of threads per inch equals 1 divided by the pitch, or expressed as a formula:

$$\text{Number of threads per inch} = \frac{1}{\text{pitch}}$$

The pitch of a screw equals 1 divided by the number of threads per inch, or:

$$\text{Pitch} = \frac{1}{\text{number of threads per inch}}$$

If the number of threads per inch equals 16, the pitch = $\frac{1}{16}$. If the pitch equals 0.05, the number of threads equals $1 \div 0.05 = 20$. If the pitch is $\frac{2}{5}$ inch, the number of threads per inch equals $1 \div \frac{2}{5} = 2\frac{1}{2}$.

Confusion is often caused by the indefinite designation of multiple-thread screws (double, triple, quadruple, etc.). The expression, "four threads per inch, triple," for example, is not to be recommended. It means that the screw is cut with four triple threads or with twelve threads per inch, if the threads are counted by placing a scale alongside the screw. To cut this screw, the lathe would be geared to cut four threads per inch, but they would be cut only to the depth required for twelve threads per inch. The best expression, when a multiple-thread is to be cut, is to say, in this case, "$\frac{1}{4}$ inch lead, $\frac{1}{12}$ inch pitch, triple thread." For single-threaded screws, only the number of threads per inch and the form of the thread are specified. The word "single" is not required.

Measuring Screw Thread Pitch Diameters by Thread Micrometers.— As the pitch or angle diameter of a tap or screw is the most important dimension, it is necessary that the pitch diameter of screw threads be measured, in addition to the outside diameter.



Fig. 1.

One method of measuring in the angle of a thread is by means of a special screw thread micrometer, as shown in the accompanying engraving, Fig. 1. The fixed anvil is W-shaped to engage two thread flanks, and the movable point is cone-shaped so as to enable it to enter the space between two threads, and at the same time be at liberty to revolve. The contact points are on the sides of the thread, as they necessarily must be in order that the pitch diam-

Copyright 2004, Industrial Press, Inc., New York, NY

eter may be determined. The cone-shaped point of the measuring screw is slightly rounded so that it will not bear in the bottom of the thread. There is also sufficient clearance at the bottom of the V-shaped anvil to prevent it from bearing on the top of the thread. The movable point is adapted to measuring all pitches, but the fixed anvil is limited in its capacity. To cover the whole range of pitches, from the finest to the coarsest, a number of fixed anvils are therefore required.

To find the theoretical pitch diameter, which is measured by the micrometer, subtract twice the addendum of the thread from the standard outside diameter. The addendum of the thread for the American and other standard threads is given in the section on screw thread systems.

Ball-point Micrometers.— If standard plug gages are available, it is not necessary to actually measure the pitch diameter, but merely to compare it with the standard gage. In this case, a ball-point micrometer, as shown in Fig. 2, may be employed. Two types of ball-point micrometers are ordinarily used. One is simply a regular plain micrometer with ball points made to slip over both measuring points. (See B, Fig. 2.) This makes a kind of combination plain and ball-point micrometer, the ball points being easily removed. These ball points, however, do not fit solidly on their seats, even if they are split, as shown, and are apt to cause errors in measurements. The best, and, in the long run, the cheapest, method is to use a regular micrometer arranged as shown at *A*. Drill and ream out both the end of the measuring screw or spindle and the anvil, and fit ball points into them as shown. Care should be taken to have the ball point in the spindle run true. The holes in the micrometer spindle and anvil and the shanks on the points are tapered to insure a good fit. The hole *H* in spindle *G* is provided so that the ball point can be easily driven out when a change for a larger or smaller size of ball point is required.



Fig. 2.

A ball-point micrometer may be used for comparing the *angle* of a screw thread, with that of a gage. This can be done by using different sizes of ball points, comparing the size first near the root of the thread, then (using a larger ball point) at about the point of the pitch diameter, and finally near the top of the thread (using in the latter case, of course, a much larger ball point). If the gage and thread measurements are the same at each of the three points referred to, this indicates that the thread angle is correct.

Measuring Screw Threads by Three-wire Method.— The *effective* or *pitch diameter* of a screw thread may be measured very accurately by means of some form of micrometer and three wires of equal diameter. This method is extensively used in checking the accuracy of threaded plug gages and other precision screw threads. Two of the wires are placed in contact with the thread on one side and the third wire in a position diametrically opposite as illustrated by the diagram, (see table "Formulas for Checking Pitch Diameters of Screw Threads") and the dimension over the wires is determined by means of a micrometer. An ordinary micrometer is commonly used but some form of "floating micrometer" is preferable, especially for measuring thread gages and other precision work. The floating micrometer is mounted upon a compound slide so that it can move freely in directions parallel or at right angles to the axis of the screw, which is held in a horizontal position between adjustable centers. With this arrangement the micrometer is held constantly at

Copyright 2004, Industrial Press, Inc., New York, NY

right angles to the axis of the screw so that only one wire on each side may be used instead of having two on one side and one on the other, as is necessary when using an ordinary micrometer. The pitch diameter may be determined accurately if the correct micrometer reading for wires of a given size is known.

Classes of Formulas for Three-Wire Measurement.— Various formulas have been established for checking the pitch diameters of screw threads by measurement over wires of known size. These formulas differ with regard to their simplicity or complexity and resulting accuracy. They also differ in that some show what measurement *M* over the wires should be to obtain a given pitch diameter *E*, whereas others show the value of the pitch diameter *E* for a given measurement *M*.

Formulas for Finding Measurement M: In using a formula for finding the value of measurement *M*, the required pitch diameter *E* is inserted in the formula. Then, in cutting or grinding a screw thread, the actual measurement *M* is made to conform to the calculated value of *M*. Formulas for finding measurement *M* may be modified so that the basic major or outside diameter is inserted in the formula instead of the pitch diameter; however, the pitch-diameter type of formula is preferable because the pitch diameter is a more important dimension than the major diameter.

Formulas for Finding Pitch Diameters E: Some formulas are arranged to show the value of the pitch diameter *E* when measurement *M* is known. Thus, the value of *M* is first determined by measurement and then is inserted in the formula for finding the corresponding pitch diameter *E*. This type of formula is useful for determining the pitch diameter of an existing thread gage or other screw thread in connection with inspection work. The formula for finding measurement *M* is more convenient to use in the shop or tool room in cutting or grinding new threads, because the pitch diameter is specified on the drawing and the problem is to find the value of measurement *M* for obtaining that pitch diameter.

General Classes of Screw Thread Profiles.— Thread profiles may be divided into three general classes or types as follows:

Screw Helicoid: Represented by a screw thread having a straight-line profile in the axial plane. Such a screw thread may be cut in a lathe by using a straight-sided single-point tool, provided the top surface lies in the axial plane.

Involute Helicoid: Represented either by a screw thread or a helical gear tooth having an involute profile in a plane perpendicular to the axis. A rolled screw thread, theoretically at least, is an exact involute helicoid.

Intermediate Profiles: An intermediate profile that lies somewhere between the screw helicoid and the involute helicoid will be formed on a screw thread either by milling or grinding with a straight-sided wheel set in alignment with the thread groove. The resulting form will approach closely the involute helicoid form. In milling or grinding a thread, the included cutter or wheel angle may either equal the standard thread angle (which is always measured in the axial plane) or the cutter or wheel angle may be reduced to approximate, at least, the thread angle in the normal plane. In practice, all these variations affect the three-wire measurement.

Accuracy of Formulas for Checking Pitch Diameters by Three-Wire Method.— The exact measurement *M* for a given pitch diameter depends upon the lead angle, the thread angle, and the profile or cross-sectional shape of the thread. As pointed out in the preceding paragraph, the profile depends upon the method of cutting or forming the thread. In a milled or ground thread, the profile is affected not only by the cutter or wheel angle, but also by the diameter of the cutter or wheel; hence, because of these variations, an absolutely exact and reasonably simple general formula for measurement *M* cannot be established; however, if the lead angle is low, as with a standard single-thread screw, and especially if the thread angle is high like a 60-degree thread, simple formulas that are not arranged to compensate for the lead angle are used ordinarily and meet most practical requirements, particularly in measuring 60-degree threads. If lead angles are large enough

Copyright 2004, Industrial Press, Inc., New York, NY

to greatly affect the result, as with most multiple threads (especially Acme or 29-degree worm threads), a formula should be used that compensates for the lead angle sufficiently to obtain the necessary accuracy.

The formulas that follow include 1) a very simple type in which the effect of the lead angle on measurement *M* is entirely ignored. This simple formula usually is applicable to the measurement of 60-degree single-thread screws, except possibly when gage-making accuracy is required; 2) formulas that do include the effect of the lead angle but, nevertheless, are approximations and not always suitable for the higher lead angles when extreme accuracy is required; and 3) formulas for the higher lead angles and the most precise classes of work.

Where approximate formulas are applied consistently in the measurement of both thread plug gages and the thread "setting plugs" for ring gages, interchangeability might be secured, assuming that such approximate formulas were universally employed.

Wire Sizes for Checking Pitch Diameters of Screw Threads.— In checking screw threads by the 3-wire method, the general practice is to use measuring wires of the so-called "best size." The "best-size" wire is one that contacts at the pitch line or midslope of the thread because then the measurement of the pitch diameter is least affected by an error in the thread angle. In the following formula for determining approximately the "best-size" wire or the diameter for pitch-line contact, A = one-half included angle of thread in the axial plane.

$$\text{Best-size wire} = \frac{0.5 \text{ pitch}}{\cos A} = 0.5 \text{ pitch} \times \sec A$$

For 60-degree threads, this formula reduces to

$$\text{Best-size wire} = 0.57735 \times \text{pitch}$$

Diameters of Wires for Measuring American Standard and British Standard Whitworth Screw Threads

Threads per Inch	Pitch, Inch	Wire Diameters for American Standard Threads			Wire Diameters for Whitworth Standard Threads		
		Max.	Min.	Pitch-Line Contact	Max.	Min.	Pitch-Line Contact
4	0.2500	0.2250	0.1400	0.1443	0.1900	0.1350	0.1409
4½	0.2222	0.2000	0.1244	0.1283	0.1689	0.1200	0.1253
5	0.2000	0.1800	0.1120	0.1155	0.1520	0.1080	0.1127
5½	0.1818	0.1636	0.1018	0.1050	0.1382	0.0982	0.1025
6	0.1667	0.1500	0.0933	0.0962	0.1267	0.0900	0.0939
7	0.1428	0.1283	0.0800	0.0825	0.1086	0.0771	0.0805
8	0.1250	0.1125	0.0700	0.0722	0.0950	0.0675	0.0705
9	0.1111	0.1000	0.0622	0.0641	0.0844	0.0600	0.0626
10	0.1000	0.0900	0.0560	0.0577	0.0760	0.0540	0.0564
11	0.0909	0.0818	0.0509	0.0525	0.0691	0.0491	0.0512
12	0.0833	0.0750	0.0467	0.0481	0.0633	0.0450	0.0470
13	0.0769	0.0692	0.0431	0.0444	0.0585	0.0415	0.0434
14	0.0714	0.0643	0.0400	0.0412	0.0543	0.0386	0.0403
16	0.0625	0.0562	0.0350	0.0361	0.0475	0.0337	0.0352
18	0.0555	0.0500	0.0311	0.0321	0.0422	0.0300	0.0313
20	0.0500	0.0450	0.0280	0.0289	0.0380	0.0270	0.0282
22	0.0454	0.0409	0.0254	0.0262	0.0345	0.0245	0.0256
24	0.0417	0.0375	0.0233	0.0240	0.0317	0.0225	0.0235
28	0.0357	0.0321	0.0200	0.0206	0.0271	0.0193	0.0201
32	0.0312	0.0281	0.0175	0.0180	0.0237	0.0169	0.0176
36	0.0278	0.0250	0.0156	0.0160	0.0211	0.0150	0.0156
40	0.0250	0.0225	0.0140	0.0144	0.0190	0.0135	0.0141

Copyright 2004, Industrial Press, Inc., New York, NY

These formulas are based upon a thread groove of zero lead angle because ordinary variations in the lead angle have little effect on the wire diameter and it is desirable to use one wire size for a given pitch regardless of the lead angle. A theoretically correct solution for finding the *exact* size for pitch-line contact involves the use of cumbersome indeterminate equations with solution by successive trials. The accompanying table gives the wire sizes for both American Standard (formerly, U.S. Standard) and the Whitworth Standard Threads. The following formulas for determining wire diameters do not give the extreme theoretical limits, but the smallest and largest practicable sizes. The diameters in the table are based upon these approximate formulas.

American Standard	Smallest wire diameter = 0.56 × pitch
	Largest wire diameter = 0.90 × pitch
	Diameter for pitch-line contact = 0.57735 × pitch
Whitworth	Smallest wire diameter = 0.54 × pitch
	Largest wire diameter = 0.76 × pitch
	Diameter for pitch-line contact = 0.56369 × pitch

Measuring Wire Accuracy.— A set of three measuring wires should have the same diameter within 0.0002 inch. To measure the pitch diameter of a screw-thread gage to an accuracy of 0.0001 inch by means of wires, it is necessary to know the wire diameters to 0.00002 inch. If the diameters of the wires are known only to an accuracy of 0.0001 inch, an accuracy better than 0.0003 inch in the measurement of pitch diameter cannot be expected. The wires should be accurately finished hardened steel cylinders of the maximum possible hardness without being brittle. The hardness should not be less than that corresponding to a Knoop indentation number of 630. A wire of this hardness can be cut with a file only with difficulty. The surface should not be rougher than the equivalent of a deviation of 3 microinches from a true cylindrical surface.

Measuring or Contact Pressure.— In measuring screw threads or screw-thread gages by the 3-wire method, variations in contact pressure will result in different readings. The effect of a variation in contact pressure in measuring threads of fine pitches is indicated by the difference in readings obtained with pressures of 2 and 5 pounds in checking a thread plug gage having 24 threads per inch. The reading over the wires with 5 pounds pressure was 0.00013 inch less than with 2 pounds pressure. For pitches finer than 20 threads per inch, a pressure of 16 ounces is recommended by the National Bureau of Standards, now National Institute of Standards and Technology (NIST). For pitches of 20 threads per inch and coarser, a pressure of 2 ½ pounds is recommended.

For Acme threads, the wire presses against the sides of the thread with a pressure of approximately twice that of the measuring instrument. To limit the tendency of the wires to wedge in between the sides of an Acme thread, it is recommended that pitch-diameter measurements be made at 1 pound on 8 threads per inch and finer, and at 2 ½ pounds for pitches coarser than 8 threads per inch.

Approximate Three-Wire Formulas That Do Not Compensate for Lead Angle.— A general formula in which the effect of lead angle is ignored is as follows (see accompanying notation used in formulas):

$$M = E - T\cot A + W(1 + \csc A) \quad (1)$$

This formula can be simplified for any given thread angle and pitch. To illustrate, because $T = 0.5P$, $M = E - 0.5P \cot 30° + W(1 + 2)$, for a 60-degree thread, such as the American Standard,

$$M = E - 0.866025P + 3W$$

Copyright 2004, Industrial Press, Inc., New York, NY

The accompanying table contains these simplified formulas for different standard threads. Two formulas are given for each. The upper one is used when the measurement over wires, M, is known and the corresponding pitch diameter, E, is required; the lower formula gives the measurement M for a specified value of pitch diameter. These formulas are sufficiently accurate for checking practically all standard 60-degree single-thread screws because of the low lead angles, which vary from 1° 11′ to 4° 31′ in the American Standard Coarse-Thread Series.

Bureau of Standards (now NIST) General Formula.— Formula (2), which follows, compensates quite largely for the effect of the lead angle. It is from the National Bureau of Standards Handbook H 28 (1944), now FED-STD-H28. The formula, however, as here given has been arranged for finding the value of M (instead of E).

$$M = E - T\cot A + W(1 + \csc A + 0.5\tan^2 B\cos A\cot A) \quad (2)$$

This expression is also found in ANSI/ASME B1.2-1983 (R2001). The Bureau of Standards uses Formula (2) in preference to Formula (1) when the value of $0.5W\tan^2 B\cos A\cot A$ exceeds 0.00015, with the larger lead angles. If this test is applied to American Standard 60-degree threads, it will show that Formula (1) is generally applicable; but for 29-degree Acme or worm threads, Formula (2) (or some other that includes the effect of lead angle) should be employed.

Notation Used in Formulas for Checking Pitch Diameters by Three-Wire Method

A = one-half included thread angle in the axial plane

A_n = one-half included thread angle in the normal plane or in plane perpendicular to sides of thread = one-half included angle of cutter when thread is milled ($\tan A_n = \tan A \times \cos B$). (Note: Included angle of milling cutter or grinding wheel may equal the nominal included angle of thread, or may be reduced to whatever normal angle is required to make the thread angle standard in the axial plane. In either case, A_n = one-half cutter angle.)

B = lead angle at pitch diameter = helix angle of thread as measured from a plane perpendicular to the axis, $\tan B = L \div 3.1416E$

D = basic major or outside diameter

E = pitch diameter (basic, maximum, or minimum) for which M is required, or pitch diameter corresponding to measurement M

F = angle required in Formulas (4b), (4d), and (4e)

G = angle required in Formula (4)

H = helix angle at pitch diameter and measured from axis = 90° − B or $\tan H = \cot B$

H_b = helix angle at R_b measured from axis

L = lead of thread = pitch P × number of threads S

M = dimension over wires

P = pitch = 1 ÷ number of threads per inch

R_b = radius required in Formulas (4) and (4e)

S = number of "starts" or threads on a multiple-threaded worm or screw

$T = 0.5\,P$ = width of thread in axial plane at diameter E

T_a = arc thickness on pitch cylinder in plane perpendicular to axis

W = wire or pin diameter

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Checking Pitch Diameters of Screw Threads



The formulas below do not compensate for the effect of the lead angle upon measurement *M*, but they are sufficiently accurate for checking standard single-thread screws unless exceptional accuracy is required. See accompanying information on effect of lead angle; also matter relating to measuring wire sizes, accuracy required for such wires, and contact or measuring pressure.

The approximate best wire size for pitch-line contact may be obtained by the formula

$$W = 0.5 \times \text{pitch} \times \sec \tfrac{1}{2} \text{ included thread angle}$$

For 60-degree threads, $W = 0.57735 \times$ pitch.

Form of Thread	Formulas for determining measurement *M* corresponding to correct pitch diameter and the pitch diameter *E* corresponding to a given measurement over wires.[a]
American National Standard Unified	When measurement *M* is known, $E = M + 0.866025P - 3W$ When pitch diameter *E* is used in formula, $M = E - 0.866025P + 3W$ The American Standard formerly was known as U.S. Standard.
British Standard Whitworth	When measurement *M* is known, $E = M + 0.9605P - 3.1657W$ When pitch diameter *E* is used in formula, $M = E - 0.9605P + 3.1657W$
British Association Standard	When measurement *M* is known, $E = M + 1.1363P - 3.4829W$ When pitch diameter *E* is used in formula, $M = E - 1.1363P + 3.4829W$
Lowenherz Thread	When measurement *M* is known, $E = M + P - 3.2359W$ When pitch diameter *E* is used in formula, $M = E - P + 3.2359W$
Sharp V-Thread	When measurement *M* is known, $E = M + 0.866025P - 3W$ When pitch diameter *E* is used in formula, $M = E - 0.866025P + 3W$
International Standard	Use the formula above for the American National Standard Unified Thread.
Pipe Thread	See accompanying paragraph on *Buckingham Exact Involute Helicoid Formula Applied to Screw Threads*.
Acme and Worm Threads	See Buckingham Formulas page 1903; also *Three-wire Measurement of Acme and Stub Acme Thread Pitch Diameter*.
Buttress Form of Thread	Different forms of buttress threads are used. See paragraph on *Three-Wire Method Applied to Buttress Threads*.

[a] The wires must be lapped to a uniform diameter and it is very important to insert in the rule or formula the wire diameter as determined by precise means of measurement. Any error will be multiplied. See paragraph on *Wire Sizes for Checking Pitch Diameters of Screw Threads* on page 1896.

Why Small Thread Angle Affects Accuracy of Three-Wire Measurement.— In measuring or checking Acme threads, or any others having a comparatively small thread angle *A*, it is particularly important to use a formula that compensates largely, if not entirely, for the effect of the lead angle, especially in all gage and precision work. The effect of the lead angle on the position of the wires and upon the resulting measurement *M* is much greater in a 29-degree thread than in a higher thread angle such, for example, as a 60-degree thread. This effect results from an increase in the cotangent of the thread angle as this angle becomes smaller. The reduction in the width of the thread groove in the normal plane due

Copyright 2004, Industrial Press, Inc., New York, NY

to the lead angle causes a wire of given size to rest higher in the groove of a thread having a small thread angle *A* (like a 29-degree thread) than in the groove of a thread with a larger angle (like a 60-degree American Standard).

Acme Threads: Three-wire measurements of high accuracy require the use of Formula (4). For most measurements, however, Formula (2) or (3) gives satisfactory results. The table on page 1906 lists suitable wire sizes for use in Formulas (2) and (4).

Values of Constants Used in Formulas for Measuring Pitch Diameters of Screws by the Three-wire System

No. of Threads per Inch	American Standard Unified and Sharp V-Thread 0.866025*P*	Whitworth Thread 0.9605*P*	No. of Threads per Inch	American Standard Unified and Sharp V-Thread 0.866025*P*	Whitworth Thread 0.9605*P*
2¼	0.38490	0.42689	18	0.04811	0.05336
2⅜	0.36464	0.40442	20	0.04330	0.04803
2½	0.34641	0.38420	22	0.03936	0.04366
2⅝	0.32992	0.36590	24	0.03608	0.04002
2¾	0.31492	0.34927	26	0.03331	0.03694
2⅞	0.30123	0.33409	28	0.03093	0.03430
3	0.28868	0.32017	30	0.02887	0.03202
3¼	0.26647	0.29554	32	0.02706	0.03002
3½	0.24744	0.27443	34	0.02547	0.02825
4	0.21651	0.24013	36	0.02406	0.02668
4½	0.19245	0.21344	38	0.02279	0.02528
5	0.17321	0.19210	40	0.02165	0.02401
5½	0.15746	0.17464	42	0.02062	0.02287
6	0.14434	0.16008	44	0.01968	0.02183
7	0.12372	0.13721	46	0.01883	0.02088
8	0.10825	0.12006	48	0.01804	0.02001
9	0.09623	0.10672	50	0.01732	0.01921
10	0.08660	0.09605	52	0.01665	0.01847
11	0.07873	0.08732	56	0.01546	0.01715
12	0.07217	0.08004	60	0.01443	0.01601
13	0.06662	0.07388	64	0.01353	0.01501
14	0.06186	0.06861	68	0.01274	0.01412
15	0.05774	0.06403	72	0.01203	0.01334
16	0.05413	0.06003	80	0.01083	0.01201

Constants Used for Measuring Pitch Diameters of Metric Screws by the Three-wire System

Pitch in mm	0.866025*P* in Inches	*W* in Inches	Pitch in mm	0.866025*P* in Inches	*W* in Inches	Pitch in mm	0.866025*P* in Inches	*W* in Inches
0.2	0.00682	0.00455	0.75	0.02557	0.01705	3.5	0.11933	0.07956
0.25	0.00852	0.00568	0.8	0.02728	0.01818	4	0.13638	0.09092
0.3	0.01023	0.00682	1	0.03410	0.02273	4.5	0.15343	0.10229
0.35	0.01193	0.00796	1.25	0.04262	0.02841	5	0.17048	0.11365
0.4	0.01364	0.00909	1.5	0.05114	0.03410	5.5	0.18753	0.12502
0.45	0.01534	0.01023	1.75	0.05967	0.03978	6	0.20457	0.13638
0.5	0.01705	0.01137	2	0.06819	0.04546	8	0.30686	0.18184
0.6	0.02046	0.01364	2.5	0.08524	0.05683	…	…	…
0.7	0.02387	0.01591	3	0.10229	0.06819	…	…	…

This table may be used for American National Standard Metric Threads. The formulas for American Standard Unified Threads on page 1899 are used. In the table above, the values of 0.866025*P* and *W* are in inches so that the values for *E* and *M* calculated from the formulas on page 1899 are also in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions Over Wires of Given Diameter for Checking Screw Threads of American National Form (U.S. Standard) and the V-Form

Dia. of Thread	No. of Threads per Inch	Wire Dia. Used	Dimension over Wires		Dia. of Thread	No. of Threads per Inch	Wire Dia. Used	Dimension over Wires	
			V-Thread	U.S. Thread				V-Thread	U.S. Thread
1/4	18	0.035	0.2588	0.2708	7/8	8	0.090	0.9285	0.9556
1/4	20	0.035	0.2684	0.2792	7/8	9	0.090	0.9525	0.9766
1/4	22	0.035	0.2763	0.2861	7/8	10	0.090	0.9718	0.9935
1/4	24	0.035	0.2828	0.2919	15/16	8	0.090	0.9910	1.0181
5/16	18	0.035	0.3213	0.3333	15/16	9	0.090	1.0150	1.0391
5/16	20	0.035	0.3309	0.3417	1	8	0.090	1.0535	1.0806
5/16	22	0.035	0.3388	0.3486	1	9	0.090	1.0775	1.1016
5/16	24	0.035	0.3453	0.3544	1 1/8	7	0.090	1.1476	1.1785
3/8	16	0.040	0.3867	0.4003	1 1/4	7	0.090	1.2726	1.3035
3/8	18	0.040	0.3988	0.4108	1 3/8	6	0.150	1.5363	1.5724
3/8	20	0.040	0.4084	0.4192	1 1/2	6	0.150	1.6613	1.6974
7/16	14	0.050	0.4638	0.4793	1 5/8	5 1/2	0.150	1.7601	1.7995
7/16	16	0.050	0.4792	0.4928	1 3/4	5	0.150	1.8536	1.8969
1/2	12	0.050	0.5057	0.5237	1 7/8	5	0.150	1.9786	2.0219
1/2	13	0.050	0.5168	0.5334	2	4 1/2	0.150	2.0651	2.1132
1/2	14	0.050	0.5263	0.5418	2 1/4	4 1/2	0.150	2.3151	2.3632
9/16	12	0.050	0.5682	0.5862	2 1/2	4	0.150	2.5170	2.5711
9/16	14	0.050	0.5888	0.6043	2 3/4	4	0.150	2.7670	2.28211
5/8	10	0.070	0.6618	0.6835	3	3 1/2	0.200	3.1051	3.1670
5/8	11	0.070	0.6775	0.6972	3 1/4	3 1/2	0.200	3.3551	3.4170
5/8	12	0.070	0.6907	0.7087	3 1/2	3 1/4	0.250	3.7171	3.7837
11/16	10	0.070	0.7243	0.7460	3 3/4	3	0.250	3.9226	3.9948
11/16	11	0.070	0.7400	0.7597	4	3	0.250	4.1726	4.2448
3/4	10	0.070	0.7868	0.8085	4 1/4	2 7/8	0.250	4.3975	4.4729
3/4	11	0.070	0.8025	0.8222	4 1/2	2 3/4	0.250	4.6202	4.6989
3/4	12	0.070	0.8157	0.8337	4 3/4	2 5/8	0.250	4.8402	4.9227
13/16	9	0.070	0.8300	0.8541	5	2 1/2	0.250	5.0572	5.1438
13/16	10	0.070	0.8493	0.8710	...	...	...	...	...

Buckingham Simplified Formula which Includes Effect of Lead Angle.— The Formula (3) which follows gives very accurate results for the lower lead angles in determining measurement *M*. However, if extreme accuracy is essential, it may be advisable to use the involute helicoid formulas as explained later.

$$M = E + W(1 + \sin A_n) \quad (3) \quad \text{where} \quad W = \frac{T \times \cos B}{\cos A_n} \quad (3a)$$

Theoretically correct equations for determining measurement *M* are complex and cumbersome to apply. Formula (3) combines simplicity with a degree of accuracy which meets all but the most exacting requirements, particularly for lead angles below 8 or 10 degrees and the higher thread angles. However, the wire diameter used in Formula (3) must conform to that obtained by Formula (3a) to permit a direct solution or one not involving indeterminate equations and successive trials.

Application of Buckingham Formula: In the application of Formula (3) to screw or worm threads, two general cases are to be considered.

Case 1: The screw thread or worm is to be milled with a cutter having an included angle equal to the nominal or standard thread angle that is assumed to be the angle in the axial plane. For example, a 60-degree cutter is to be used for milling a thread. In this case, the

Copyright 2004, Industrial Press, Inc., New York, NY

Table for Measuring Whitworth Standard Threads by the Three-wire Method

Dia. of Thread	No. of Threads per Inch	Dia. of Wire Used	Dia. Measured over Wires	Dia. of Thread	No. of Threads per Inch	Dia. of Wire Used	Dia. Measured over Wires
1/8	40	0.018	0.1420	2 1/4	4	0.150	2.3247
3/16	24	0.030	0.2158	2 3/8	4	0.150	2.4497
1/4	20	0.035	0.2808	2 1/2	4	0.150	2.5747
5/16	18	0.040	0.3502	2 5/8	4	0.150	2.6997
3/8	16	0.040	0.4015	2 3/4	3 1/2	0.200	2.9257
7/16	14	0.050	0.4815	2 7/8	3 1/2	0.200	3.0507
1/2	12	0.050	0.5249	3	3 1/2	0.200	3.1757
9/16	12	0.050	0.5874	3 1/8	3 1/2	0.200	3.3007
5/8	11	0.070	0.7011	3 1/4	3 1/4	0.200	3.3905
11/16	11	0.070	0.7636	3 3/8	3 1/4	0.200	3.5155
3/4	10	0.070	0.8115	3 1/2	3 1/4	0.200	3.6405
13/16	10	0.070	0.8740	3 5/8	3 1/4	0.200	3.7655
7/8	9	0.070	0.9187	3 3/4	3	0.200	3.8495
15/16	9	0.070	0.9812	3 7/8	3	0.200	3.9745
1	8	0.090	1.0848	4	3	0.200	4.0995
1 1/16	8	0.090	1.1473	4 1/8	3	0.200	4.2245
1 1/8	7	0.090	1.1812	4 1/4	2 7/8	0.250	4.4846
1 3/16	7	0.090	1.2437	4 3/8	2 7/8	0.250	4.6096
1 1/4	7	0.090	1.3062	4 1/2	2 7/8	0.250	4.7346
1 5/16	7	0.090	1.3687	4 5/8	2 7/8	0.250	4.8596
1 3/8	6	0.120	1.4881	4 3/4	2 3/4	0.250	4.9593
1 7/16	6	0.120	1.5506	4 7/8	2 3/4	0.250	5.0843
1 1/2	6	0.120	1.6131	5	2 3/4	0.250	5.2093
1 9/16	6	0.120	1.6756	5 1/8	2 3/4	0.250	5.3343
1 5/8	5	0.120	1.6847	5 1/4	2 5/8	0.250	5.4316
1 11/16	5	0.120	1.7472	5 3/8	2 5/8	0.250	5.5566
1 3/4	5	0.120	1.8097	5 1/2	2 5/8	0.250	5.6816
1 13/16	5	0.120	1.8722	5 5/8	2 5/8	0.250	5.8066
1 7/8	4 1/2	0.150	1.9942	5 3/4	2 1/2	0.250	5.9011
1 15/16	4 1/2	0.150	2.0567	5 7/8	2 1/2	0.250	6.0261
2	4 1/2	0.150	2.1192	6	2 1/2	0.250	6.1511
2 1/8	4 1/2	0.150	2.2442	…	…	…	…

All dimensions are given in inches.

thread angle in the plane of the axis will exceed 60 degrees by an amount increasing with the lead angle. This variation from the standard angle may be of little or no practical importance if the lead angle is small or if the mating nut (or teeth in worm gearing) is formed to suit the thread as milled.

Case 2: The screw thread or worm is to be milled with a cutter reduced to whatever normal angle is equivalent to the standard thread angle in the axial plane. For example, a 29-degree Acme thread is to be milled with a cutter having some angle smaller than 29 degrees (the reduction increasing with the lead angle) to make the thread angle standard in the plane of the axis. Theoretically, the milling cutter angle should always be corrected to suit the normal angle; but if the lead angle is small, such correction may be unnecessary.

Copyright 2004, Industrial Press, Inc., New York, NY

If the thread is cut in a lathe to the standard angle as measured in the axial plane, Case 2 applies in determining the pin size W and the overall measurement M.

In solving all problems under Case 1, angle A_n used in Formulas (3) and (3a) equals one-half the included angle of the milling cutter.

When Case 2 applies, angle A_n for milled threads also equals one-half the included angle of the cutter, but the cutter angle is reduced and is determined as follows:

$$\tan A_n = \tan A \times \cos B$$

The included angle of the cutter or the normal included angle of the thread groove = $2A_n$. Examples 1 and 2, which follow, illustrate Cases 1 and 2.

Example 1 (Case 1): Take, for example, an Acme screw thread that is milled with a cutter having an included angle of 29 degrees; consequently, the angle of the thread exceeds 29 degrees in the axial section.

The outside or major diameter is 3 inches; the pitch, ½ inch; the lead, 1 inch; the number of threads or "starts," 2. Find pin size W and measurement M.

Pitch diameter $E = 2.75$; $T = 0.25$; $L = 1.0$; $A_n = 14.50°$ tan $A_n = 0.258618$; sin $A_n = 0.25038$; and cos $A_n = 0.968148$.

$$\tan B = \frac{1.0}{3.1416 \times 2.75} = 0.115749 \qquad B = 6.6025°$$

$$W = \frac{0.25 \times 0.993368}{0.968148} = 0.25651 \text{ inch}$$

$$M = 2.75 + 0.25651 \times (1 + 0.25038) = 3.0707 \text{ inches}$$

Note: This value of M is only 0.0001 inch larger than that obtained by using the very accurate involute helicoid Formula (4) discussed on the following page.

Example 2 (Case 2): A triple-threaded worm has a pitch diameter of 2.481 inches, pitch of 1.5 inches, lead of 4.5 inches, lead angle of 30 degrees, and nominal thread angle of 60 degrees in the axial plane. Milling cutter angle is to be reduced. $T = 0.75$ inch; cos $B = 0.866025$; and tan $A = 0.57735$. Again use Formula (3) to see if it is applicable.

tan A_n = tan $A \times$ cos $B = 0.57735 \times 0.866025 = 0.5000$; hence $A_n = 26.565°$, making the included cutter angle 53.13°, thus cos $A_n = 0.89443$ and sin $A_n = 0.44721$.

$$W = \frac{0.75 \times 0.866025}{0.89443} = 0.72618 \text{ inch}$$

$$M = 2.481 + 0.72618 \times (1 + 0.44721) = 3.532 \text{ inches}$$

Note: If the value of measurement M is determined by using the following Formula (4) it will be found that $M = 3.515 +$ inches; hence the error equals $3.532 - 3.515 = 0.017$ inch approximately, which indicates that Formula (3) is not accurate enough here. The application of this simpler Formula (3) will depend upon the lead angle and thread angle (as previously explained) and upon the class of work.

Buckingham Exact Involute Helicoid Formula Applied to Screw Threads.— When extreme accuracy is required in finding measurement M for obtaining a given pitch diameter, the equations that follow, although somewhat cumbersome to apply, have the merit of providing a direct and very accurate solution; consequently, they are preferable to the indeterminate equations and successive trial solutions heretofore employed when extreme precision is required. These equations are exact for involute helical gears and, consequently, give theoretically correct results when applied to a screw thread of the involute helicoidal form; they also give very close approximations for threads having intermediate profiles.

Helical Gear Equation Applied to Screw Thread Measurement: In applying the helical gear equations to a screw thread, use either the axial or normal thread angle and the lead

Copyright 2004, Industrial Press, Inc., New York, NY

angle of the helix. To keep the solution on a practical basis, either thread angle A or A_n, as the case may be, is assumed to equal the cutter angle of a milled thread. Actually, the profile of a milled thread will have some curvature in both axial and normal sections; hence angles A and A_n represent the angular approximations of these slightly curved profiles. The equations that follow give the values needed to solve the screw thread problem as a helical gear problem.

$$M = \frac{2R_b}{\cos G} + W \tag{4}$$

$$\tan F = \frac{\tan A}{\tan B} = \frac{\tan A_n}{\sin B} \tag{4a}$$

$$R_b = \frac{E}{2}\cos F \tag{4b}$$

$$T_a = \frac{T}{\tan B} \tag{4c}$$

$$\tan H_b = \cos F \times \tan H \tag{4d}$$

$$\text{inv}\, G = \frac{T_a}{E} + \text{inv}\, F + \frac{W}{2R_b \cos H_b} - \frac{\pi}{S} \tag{4e}$$

The tables of involute functions starting on page 104 provide values for angles from 14 to 51 degrees, used for gear calculations. The formula for involute functions on page 103 may be used to extend this table as required.

Example 3: To illustrate the application of Formula (4) and the supplementary formulas, assume that the number of starts $S = 6$; pitch diameter $E = 0.6250$; normal thread angle $A_n = 20°$; lead of thread $L = 0.864$ inch; $T = 0.072$; W = 0.07013 inch.

$$\tan B = \frac{L}{\pi E} = \frac{0.864}{1.9635} = 0.44003 \qquad B = 23.751°$$

$$\text{Helix angle } H = 90° - 23.751° = 66.249°$$

$$\tan F = \frac{\tan A_n}{\sin B} = \frac{0.36397}{0.40276} = 0.90369 \qquad F = 42.104°$$

$$R_b = \frac{E}{2}\cos F = \frac{0.6250}{2} \times 0.74193 = 0.23185$$

$$T_a = \frac{T}{\tan B} = \frac{0.072}{0.44003} = 0.16362$$

$$\tan H_b = \cos F \tan H = 0.74193 \times 2.27257 = 1.68609 \qquad H_b = 59.328°$$

The involute function of G is found next by Formula (4e).

$$\text{inv}\, G = \frac{0.16362}{0.625} + 0.16884 + \frac{0.07013}{2 \times 0.23185 \times 0.51012} - \frac{3.1416}{6} = 0.20351$$

Since 0.20351 is outside the values for involute functions given in the tables on pages 104 through 107 use the formula for involute functions on page 103 to extend these tables as required. It will be found that 44 deg. 21 min. or 44.350 degrees is the angular equivalent of 0.20351; hence, $G = 44.350$ degrees.

$$M = \frac{2R_b}{\cos G} + W = \frac{2 \times 0.23185}{0.71508} + 0.07013 = 0.71859 \text{ inch}$$

Accuracy of Formulas (3) and (4) Compared.— With the involute helicoid Formula (4) any wire size that makes contact with the flanks of the thread may be used; however, in the preceding example, the wire diameter W was obtained by Formula (3a) in order to compare Formula (4) with (3) . If Example (3) is solved by Formula (3) , $M = 0.71912$; hence

Copyright 2004, Industrial Press, Inc., New York, NY

the difference between the values of M obtained with Formulas (3) and (4) equals 0.71912 - 0.71859 = 0.00053 inch. The included thread angle in this case is 40 degrees. If Formulas (3) and (4) are applied to a 29-degree thread, the difference in measurements M or the error resulting from the use of Formulas (3) will be larger. For example, with an Acme thread having a lead angle of about 34 degrees, the difference in values of M obtained by the two formulas equals 0.0008 inch.

Three-wire Measurement of Acme and Stub Acme Thread Pitch Diameter.— For single- and multiple-start Acme and Stub Acme threads having lead angles of less than 5 degrees, the approximate three-wire formula given on page 1897 and the best wire size taken from the table on page 1906 may be used.

Multiple-start Acme and Stub Acme threads commonly have a lead angle of greater than 5 degrees. For these, a direct determination of the actual pitch diameter is obtained by using the formula: $E = M - (C + c)$ in conjunction with the table on page 1907. To enter the table, the lead angle B of the thread to be measured must be known. It is found by the formula: $\tan B = L \div 3.1416E_1$ where L is the lead of the thread and E_1 is the nominal pitch diameter. The best wire size is now found by taking the value of w_1 as given in the table for lead angle B, with interpolation, and dividing it by the number of threads per inch. The value of $(C + c)_1$ given in the table for lead angle B is also divided by the number of threads per inch to get $(C + c)$. Using the best size wires, the actual measurement over wires M is made and the actual pitch diameter E found by using the formula: $E = M - (C + c)$.

Example: For a 5 tpi, 4-start Acme thread with a 13.952° lead angle, using three 0.10024-inch wires, $M = 1.1498$ inches, hence $E = 1.1498 - 0.1248 = 1.0250$ inches.

Under certain conditions, a wire may contact one thread flank at two points, and it is then advisable to substitute balls of the same diameter as the wires.

Checking Thickness of Acme Screw Threads.— In some instances it may be preferable to check the thread thickness instead of the pitch diameter, especially if there is a thread thickness tolerance.

A direct method, applicable to the larger pitches, is to use a vernier gear-tooth caliper for measuring the thickness in the *normal* plane of the thread. This measurement, for an American Standard General Purpose Acme thread, should be made at a distance below the *basic* outside diameter equal to $p/4$. The thickness at this basic pitch-line depth and in the axial plane should be $p/2 - 0.259 \times$ the pitch diameter allowance from the table on page 1827 with a tolerance of *minus* $0.259 \times$ the pitch diameter tolerance from the table on page 1832. The thickness in the normal plane or plane of measurement is equal to the thickness in the axial plane multiplied by the cosine of the helix angle. The helix angle may be determined from the formula:

$$\text{tangent of helix angle} = \text{lead of thread} \div (3.1416 \times \text{pitch diameter})$$

Three-Wire Method for Checking Thickness of Acme Threads.— The application of the 3-wire method of checking the thickness of an Acme screw thread is included in the Report of the National Screw Thread Commission. In applying the 3-wire method for checking thread thickness, the procedure is the same as in checking pitch diameter (see *Three-wire Measurement of Acme and Stub Acme Thread Pitch Diameter*), although a different formula is required. Assume that D = basic major diameter of screw; M = measurement over wires; W = diameter of wires; S = tangent of helix angle at pitch line; P = pitch; T = thread thickness at depth equal to $0.25P$.

$$T = 1.12931 \times P + 0.25862 \times (M - D) - W \times (1.29152 + 0.48407S^2)$$

This formula transposed to show the correct measurement M equivalent to a given required thread thickness is as follows:

$$M = D + \frac{W \times (1.29152 + 0.48407S^2) + T - 1.12931 \times P}{0.25862}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Wire Sizes for Three-Wire Measurement of Acme Threads with Lead Angles of Less than 5 Degrees

Threads per Inch	Best Size	Max.	Min.	Threads per Inch	Best Size	Max.	Min.
1	0.51645	0.65001	0.48726	5	0.10329	0.13000	0.09745
1⅓	0.38734	0.48751	0.36545	6	0.08608	0.10834	0.08121
1½	0.34430	0.43334	0.32484	8	0.06456	0.08125	0.06091
2	0.25822	0.32501	0.24363	10	0.05164	0.06500	0.04873
2½	0.20658	0.26001	0.19491	12	0.04304	0.05417	0.04061
3	0.17215	0.21667	0.16242	14	0.03689	0.04643	0.03480
4	0.12911	0.16250	0.12182	16	0.03228	0.04063	0.03045

Wire sizes are based upon zero helix angle. Best size = 0.51645 × pitch; maximum size = 0.650013 × pitch; minimum size = 0.487263 × pitch.

Example: An Acme General Purpose thread, Class 2G, has a 5-inch basic major diameter, 0.5-inch pitch, and 1-inch lead (double thread). Assume the wire size is 0.258 inch. Determine measurement M for a thread thickness T at the basic pitch line of 0.2454 inch. (T is the maximum thickness at the basic pitch line and equals 0.5P, the basic thickness, –0.259 × allowance from Table 4, page 1832.)

$$M = 5 + \frac{0.258 \times [1.29152 + 0.48407 \times (0.06701)^2] + 0.2454 - 1.12931 \times 0.5}{0.25862}$$

$$= 5.056 \text{ inches}$$

Testing Angle of Thread by Three-Wire Method.— The error in the angle of a thread may be determined by using sets of wires of two diameters, the measurement over the two sets of wires being followed by calculations to determine the amount of error, assuming that the angle cannot be tested by comparison with a standard plug gage, known to be correct. The diameter of the small wires for the American Standard thread is usually about 0.6 times the pitch and the diameter of the large wires, about 0.9 times the pitch. The total difference between the measurements over the large and small sets of wires is first determined. If the thread is an American Standard or any other form having an included angle of 60 degrees, the difference between the two measurements should equal three times the difference between the diameters of the wires used. Thus, if the wires are 0.116 and 0.076 inch in diameter, respectively, the difference equals 0.116 – 0.076 = 0.040 inch. Therefore, the difference between the micrometer readings for a standard angle of 60 degrees equals 3 × 0.040 = 0.120 inch for this example. If the angle is incorrect, the amount of error may be determined by the following formula, which applies to any thread regardless of angle:

$$\sin a = \frac{A}{B - A}$$

where A = difference in diameters of the large and small wires used
B = total difference between the measurements over the large and small wires
a = one-half the included thread angle

Example: The diameter of the large wires used for testing the angle of a thread is 0.116 inch and of the small wires 0.076 inch. The measurement over the two sets of wires shows a total difference of 0.122 inch instead of the correct difference, 0.120 inch, for a standard angle of 60 degrees when using the sizes of wires mentioned. The amount of error is determined as follows:

$$\sin a = \frac{0.040}{0.122 - 0.040} = \frac{0.040}{0.082} = 0.4878$$

A table of sines shows that this value (0.4878) is the sine of 29 degrees 12 minutes, approximately. Therefore, the angle of the thread is 58 degrees 24 minutes or 1 degree 36 minutes less than the standard angle.

Copyright 2004, Industrial Press, Inc., New York, NY

Best Wire Diameters and Constants for Three-wire Measurement of Acme and Stub Acme Threads with Large Lead Angles, 1–inch Axial Pitch

Lead angle, B, deg.	1-start threads		2-start threads		Lead angle, B, deg.	2-start threads		3-start threads	
	w_1	$(C+c)_1$	w_1	$(C+c)_1$		w_1	$(C+c)_1$	w_1	$(C+c)_1$
5.0	0.51450	0.64311	0.51443	0.64290	10.0	0.50864	0.63518	0.50847	0.63463
5.1	0.51442	0.64301	0.51435	0.64279	10.1	0.50849	0.63498	0.50381	0.63442
5.2	0.51435	0.64291	0.51427	0.64268	10.2	0.50834	0.63478	0.50815	0.63420
5.3	0.51427	0.64282	0.51418	0.64256	10.3	0.50818	0.63457	0.50800	0.63399
5.4	0.51419	0.64272	0.51410	0.64245	10.4	0.50802	0.63436	0.50784	0.63378
5.5	0.51411	0.64261	0.51401	0.64233	10.5	0.40786	0.63416	0.50768	0.63356
5.6	0.51403	0.64251	0.51393	0.64221	10.6	0.50771	0.63395	0.50751	0.63333
5.7	0.51395	0.64240	0.51384	0.64209	10.7	0.50755	0.63375	0.50735	0.63311
5.8	0.51386	0.64229	0.51375	0.64196	10.8	0.50739	0.53354	0.50718	0.63288
5.9	0.51377	0.64218	0.51366	0.64184	10.9	0.50723	0.63333	0.50701	0.63265
6.0	0.51368	0.64207	0.51356	0.64171	11.0	0.50707	0.63313	0.50684	0.63242
6.1	0.51359	0.64195	0.51346	0.64157	11.1	0.50691	0.63292	0.50667	0.63219
6.2	0.51350	0.64184	0.51336	0.64144	11.2	0.50674	0.63271	0.50649	0.63195
6.3	0.51340	0.64172	0.41327	0.64131	11.3	0.50658	0.63250	0.50632	0.63172
6.4	0.51330	0.64160	0.51317	0.64117	11.4	0.50641	0.63228	0.50615	0.63149
6.5	0.51320	0.64147	0.51306	0.64103	11.5	0.50623	0.63206	0.50597	0.63126
6.6	0.51310	0.64134	0.51296	0.64089	11.6	0.50606	0.63184	0.50579	0.63102
6.7	0.51300	0.64122	0.51285	0.64075	11.7	0.50589	0.63162	0.50561	0.63078
6.8	0.51290	0.64110	0.51275	0.64061	11.8	0.50571	0.63140	0.50544	0.63055
6.9	0.51280	0.64097	0.51264	0.64046	11.9	0.50553	0.63117	0.50526	0.63031
7.0	0.51270	0.64085	0.51254	0.64032	12.0	0.50535	0.63095	0.50507	0.63006
7.1	0.51259	0.64072	0.51243	0.64017	12.1	0.50517	0.63072	0.50488	0.62981
7.2	0.51249	0.64060	0.51232	0.64002	12.2	0.50500	0.63050	0.50470	0.62956
7.3	0.51238	0.64047	0.51221	0.63987	12.3	0.50482	0.63027	0.50451	0.62931
7.4	0.51227	0.64034	0.51209	0.63972	12.4	0.50464	0.63004	0.50432	0.62906
7.5	0.51217	0.64021	0.51198	0.63957	12.5	0.50445	0.62981	0.50413	0.62881
7.6	0.51206	0.64008	0.51186	0.63941	12.6	0.50427	0.62958	0.50394	0.62856
7.7	0.51196	0.63996	0.51174	0.63925	12.7	0.50408	0.62934	0.50375	0.62830
7.8	0.51186	0.63983	0.51162	0.63909	12.8	0.50389	0.62911	0.50356	0.62805
7.9	0.51175	0.63970	0.51150	0.63892	12.9	0.50371	0.62888	0.50336	0.62779
8.0	0.51164	0.63957	0.51138	0.63876	13.0	0.50352	0.62865		
8.1	0.51153	0.63944	0.51125	0.63859	13.1	0.50333	0.62841		
8.2	0.51142	0.63930	0.51113	0.63843	13.2	0.50313	0.62817		
8.3	0.51130	0.63916	0.51101	0.63827	13.3	0.50293	0.62792		
8.4	0.51118	0.63902	0.51088	0.63810	13.4	0.50274	0.62778		
8.5	0.51105	0.63887	0.51075	0.63793	13.5	0.50254	0.62743		
8.6	0.51093	0.63873	0.51062	0.63775	13.6	0.50234	0.62718		
8.7	0.51081	0.63859	0.51049	0.63758	13.7	0.50215	0.62694	For these 3-start thread values see table on following page.	
8.8	0.51069	0.63845	0.51035	0.63740	13.8	0.50195	0.62670		
8.9	0.51057	0.63831	0.51022	0.63722	13.9	0.50175	0.62645		
9.0	0.51044	0.63817	0.51008	0.63704	14.0	0.50155	0.62621		
9.1	0.51032	0.63802	0.50993	0.63685	14.1	0.50135	0.62596		
9.2	0.51019	0.63788	0.50979	0.63667	14.2	0.50115	0.62571		
9.3	0.51006	0.63774	0.50965	0.63649	14.3	0.50094	0.62546		
9.4	0.50993	0.63759	0.50951	0.63630	14.4	0.50073	0.62520		
9.5	0.50981	0.63744	0.50937	0.63612	14.5	0.50051	0.62494		
9.6	0.50968	0.63730	0.50922	0.63593	14.6	0.50030	0.62468		
9.7	0.50955	0.63715	0.50908	0.63574	14.7	0.50009	0.62442		
9.8	0.50941	0.63700	0.50893	0.63555	14.8	0.49988	0.62417		
9.9	0.50927	0.63685	0.50879	0.63537	14.9	0.49966	0.62391		
10.0	0.50913	0.63670	0.50864	0.63518	15.0	0.49945	0.62365		

All dimensions are in inches.

Values given for w_1 and $(C+c)_1$ in table are for 1-inch pitch axial threads. For other pitches, divide table values by number of threads per inch.

Courtesy of Van Keuren Co.

Copyright 2004, Industrial Press, Inc., New York, NY

Best Wire Diameters and Constants for Three-wire Measurement of Acme and Stub Acme Threads with Large Lead Angles—1-inch Axial Pitch

Lead angle, B, deg.	3-start threads		4-start threads		Lead angle, B, deg.	3-start threads		4-start threads	
	w_1	$(C+c)_1$	w_1	$(C+c)_1$		w_1	$(C+c)_1$	w_1	$(C+c)_1$
13.0	0.50316	0.62752	0.50297	0.62694	18.0	0.49154	0.61250	0.49109	0.61109
13.1	0.50295	0.62725	0.50277	0.62667	18.1	0.49127	0.61216	0.49082	0.61073
13.2	0.50275	0.62699	0.50256	0.62639	18.2	0.49101	0.61182	0.49054	0.61037
13.3	0.50255	0.62672	0.50235	0.62611	18.3	0.49074	0.61148	0.49027	0.61001
13.4	0.50235	0.62646	0.50215	0.62583	18.4	0.49047	0.61114	0.48999	0.60964
13.5	0.50214	0.62619	0.50194	0.62555	18.5	0.49020	0.61080	0.48971	0.69928
13.6	0.50194	0.62592	0.50173	0.62526	18.6	0.48992	0.61045	0.48943	0.60981
13.7	0.50173	0.62564	0.50152	0.62498	18.7	0.48965	0.61011	0.48915	0.60854
13.8	0.50152	0.62537	0.50131	0.62469	18.8	0.48938	0.60976	0.48887	0.60817
13.9	0.50131	0.62509	0.50109	0.62440	18.9	0.48910	0.60941	0.48859	0.60780
14.0	0.50110	0.62481	0.50087	0.62411	19.0	0.48882	0.60906	0.48830	0.60742
14.1	0.50089	0.62453	0.50065	0.62381	19.1	0.48854	0.60871	0.48800	0.60704
14.2	0.50068	0.62425	0.50043	0.62351	19.2	0.48825	0.60835	0.48771	0.60666
14.3	0.50046	0.62397	0.50021	0.62321	19.3	0.48797	0.60799	0.48742	0.60628
14.4	0.50024	0.62368	0.49999	0.62291	19.4	0.48769	0.60764	0.48713	0.60590
14.5	0.50003	0.62340	0.49977	0.62262	19.5	0.48741	0.60729	0.48684	0.60552
14.6	0.49981	0.62312	0.49955	0.62232	19.6	0.48712	0.60693	0.48655	0.60514
14.7	0.49959	0.62883	0.49932	0.62202	19.7	0.48638	0.60657	0.48625	0.60475
14.8	0.49936	0.62253	0.49910	0.62172	19.8	0.48655	0.60621	0.48596	0.60437
14.9	0.49914	0.62224	0.49887	0.62141	19.9	0.48626	0.60585	0.48566	0.60398
15.0	0.49891	0.62195	0.49864	0.62110	20.0	0.48597	0.60549	0.48536	0.60359
15.1	0.49869	0.62166	0.49842	0.62080	20.1	…	…	0.48506	0.60320
15.2	0.49846	0.62137	0.49819	0.62049	20.2	…	…	0.48476	0.60281
15.3	0.49824	0.62108	0.49795	0.62017	20.3	…	…	0.48445	0.60241
15.4	0.42801	0.62078	0.49771	0.61985	20.4	…	…	0.48415	0.60202
15.5	0.49778	0.62048	0.49747	0.61953	20.5	…	…	0.48384	0.60162
15.6	0.49754	0.62017	0.49723	0.61921	20.6	…	…	0.48354	0.60123
15.7	0.49731	0.61987	0.49699	0.61889	20.7	…	…	0.48323	0.60083
15.8	0.49707	0.61956	0.49675	0.61857	20.8	…	…	0.48292	0.60042
15.9	0.49683	0.61926	0.49651	0.61825	20.9	…	…	0.48261	0.60002
16.0	0.49659	0.61895	0.49627	0.61793	21.0	…	…	0.48230	0.59961
16.1	0.49635	0.61864	0.49602	0.61760	21.1	…	…	0.48198	0.49920
16.2	0.49611	0.61833	0.49577	0.61727	21.2	…	…	0.481166	0.59879
16.3	0.49586	0.61801	0.49552	0.61694	21.3	…	…	0.48134	0.59838
16.4	0.49562	0.61770	0.49527	0.61661	21.4	…	…	0.48103	0.59797
16.5	0.49537	0.61738	0.49502	0.61628	21.5	…	…	0.48701	0.59756
16.6	0.49512	0.61706	0.49476	0.61594	21.6	…	…	0.48040	0.59715
16.7	0.49488	0.61675	0.49451	0.61560	21.7	…	…	0.48008	0.59674
16.8	0.40463	0.61643	0.49425	0.61526	21.8	…	…	0.47975	0.59632
16.9	0.49438	0.61611	0.49400	0.61492	21.9	…	…	0.47943	0.59590
17.0	0.49414	0.61580	0.49375	0.61458	22.0	…	…	0.47910	0.59548
17.1	0.49389	0.61548	0.49349	0.61424	22.1	…	…	0.47878	0.59507
17.2	0.49363	0.61515	0.49322	0.61389	22.2	…	…	0.47845	0.59465
17.3	0.49337	0.61482	0.49296	0.61354	22.3	…	…	0.47812	0.59422
17.4	0.49311	0.61449	0.49269	0.61319	22.4	…	…	0.47778	0.59379
17.5	0.49285	0.61416	0.49243	0.61284	22.5	…	…	0.47745	0.59336
17.6	0.49259	0.61383	0.49217	0.61250	22.6	…	…	0.47711	0.52993
17.7	0.49233	0.61350	0.49191	0.61215	22.7	…	…	0.47677	0.59250
17.8	0.49206	0.61316	0.49164	0.61180	22.8	…	…	0.47643	0.59207
17.9	0.49180	0.61283	0.49137	0.61144	22.9	…	…	0.47610	0.59164
…	…	…	…	…	23.0	…	…	0.47577	0.59121

All dimensions are in inches.

Values given for w_1 and $(C+c)_1$ in table are for 1-inch pitch axial threads. For other pitches divide table values by number of threads per inch.

Courtesy of Van Keuren Co.

Copyright 2004, Industrial Press, Inc., New York, NY

Measuring Taper Screw Threads by Three-Wire Method.— When the 3-wire method is used in measuring a taper screw thread, the measurement is along a line that is not perpendicular to the axis of the screw thread, the inclination from the perpendicular equaling one-half the included angle of the taper. The formula that follows compensates for this inclination resulting from contact of the measuring instrument surfaces, with two wires on one side and one on the other. The taper thread is measured over the wires in the usual manner except that the single wire must be located in the thread at a point where the effective diameter is to be checked (as described more fully later). The formula shows the dimension equivalent to the correct pitch diameter at this given point. The general formula for taper screw threads follows:

$$M = \frac{E - (\cot a)/2N + W(1 + \csc a)}{\sec b}$$

where M = measurement over the 3 wires
E = pitch diameter
a = one-half the angle of the thread
N = number of threads per inch
W = diameter of wires; and
b = one-half the angle of taper.

This formula is not theoretically correct but it is accurate for screw threads having tapers of ¾ inch per foot or less. This general formula can be simplified for a given thread angle and taper. The simplified formula following (in which P = pitch) is for an American National Standard pipe thread:

$$M = \frac{E - (0.866025 \times P) + 3 \times W}{1.00049}$$

Standard pitch diameters for pipe threads will be found in the section "American Pipe Threads," which also shows the location, or distance, of this pitch diameter from the end of the pipe. In using the formula for finding dimension M over the wires,the single wire is placed in whatever part of the thread groove locates it at the point where the pitch diameter is to be checked. The wire must be accurately located at this point. The other wires are then placed on each side of the thread that is diametrically opposite the single wire. If the pipe thread is straight or without taper,

$$M = E - (0.866025 \times P) + 3 \times W$$

Application of Formula to Taper Pipe Threads: To illustrate the use of the formula for taper threads, assume that dimension M is required for an American Standard 3-inch pipe thread gage. Table 1a starting on page 1861 shows that the 3-inch size has 8 threads per inch, or a pitch of 0.125 inch, and a pitch diameter at the gaging notch of 3.3885 inches. Assume that the wire diameter is 0.07217 inch: Then when the pitch diameter is correct

$$M = \frac{3.3885 - (0.866025 \times 0.125) + 3 \times 0.07217}{1.00049} = 3.495 \text{ inches}$$

Pitch Diameter Equivalent to a Given Measurement Over the Wires: The formula following may be used to check the pitch diameter at any point along a tapering thread when measurement M over wires of a given diameter is known. In this formula, E = the effective or pitch diameter at the position occupied by the single wire. The formula is not theoretically correct but gives very accurate results when applied to tapers of ¾ inch per foot or less.

$$E = 1.00049 \times M + (0.866025 \times P) - 3 \times W$$

Example: Measurement M = 3.495 inches at the gaging notch of a 3-inch pipe thread and the wire diameter = 0.07217 inch. Then

Copyright 2004, Industrial Press, Inc., New York, NY

$$E = 1.00049 \times 3.495 + (0.866025 \times 0.125) - 3 \times 0.07217 = 3.3885 \text{ inches}$$

Pitch Diameter at Any Point Along Taper Screw Thread: When the pitch diameter in any position along a tapering thread is known, the pitch diameter at any other position may be determined as follows:

Multiply the distance (measured along the axis) between the location of the known pitch diameter and the location of the required pitch diameter, by the taper per inch or by 0.0625 for American National Standard pipe threads. Add this product to the known diameter, if the required diameter is at a large part of the taper, or subtract if the required diameter is smaller.

Example: The pitch diameter of a 3-inch American National Standard pipe thread is 3.3885 at the gaging notch. Determine the pitch diameter at the small end. The table starting on page 1861 shows that the distance between the gaging notch and the small end of a 3-inch pipe is 0.77 inch. Hence the pitch diameter at the small end = 3.3885 − (0.77 × 0.0625) = 3.3404 inches.

Three-Wire Method Applied to Buttress Threads

The angles of buttress threads vary somewhat, especially on the front or load-resisting side. Formula (1), which follows, may be applied to any angles required. In this formula, M = measurement over wires when *pitch diameter* E is correct; A = included angle of thread and thread groove; a = angle of front face or load-resisting side, measured from a line perpendicular to screw thread axis; P = pitch of thread; and W = wire diameter.

$$M = E - \left[\frac{P}{\tan a + \tan(A - a)}\right] + W\left[1 + \cos\left(\frac{A}{2} - a\right) \times \csc\frac{A}{2}\right] \quad (1)$$



For given angles A and a, this general formula may be simplified as shown by Formulas (3) and (4). These simplified formulas contain constants with values depending upon angles A and a.

Wire Diameter: The wire diameter for obtaining pitch-line contact at the back of a buttress thread may be determined by the following general Formula (2):

$$W = P\left(\frac{\cos a}{1 + \cos A}\right) \quad (2)$$

45-Degree Buttress Thread: The buttress thread shown by the diagram at the left, has a front or load-resisting side that is perpendicular to the axis of the screw. Measurement M equivalent to a correct pitch diameter E may be determined by Formula (3):

$$M = E - P + (W \times 3.4142) \quad (3)$$

Wire diameter W for pitch-line contact at back of thread = 0.586 × pitch.

Copyright 2004, Industrial Press, Inc., New York, NY

50-Degree Buttress Thread with Front-face Inclination of 5 Degrees: This buttress thread form is illustrated by the diagram at the right. Measurement M equivalent to the correct pitch diameter E may be determined by Formula (4):

$$M = E - (P \times 0.91955) + (W \times 3.2235) \quad (4)$$

Wire diameter W for pitch-line contact at back of thread = 0.606 × pitch. If the width of flat at crest and root = ⅛ × pitch, depth = 0.69 × pitch.

American National Standard Buttress Threads ANSI B1.9-1973: This buttress screw thread has an included thread angle of 52 degrees and a front face inclination of 7 degrees. Measurements M equivalent to a pitch diameter E may be determined by Formula (5):

$$M = E - 0.89064P + 3.15689W + c \quad (5)$$

The wire angle correction factor c is less than 0.0004 inch for recommended combinations of thread diameters and pitches and may be neglected. Use of wire diameter $W = 0.54147P$ is recommended.

Measurement of Pitch Diameter of Thread Ring Gages.— The application of direct methods of measurement to determine the pitch diameter of thread ring gages presents serious difficulties, particularly in securing proper contact pressure when a high degree of precision is required. The usual practice is to fit the ring gage to a master setting plug. When the thread ring gage is of correct lead, angle, and thread form, within close limits, this method is quite satisfactory and represents standard American practice. It is the only method available for small sizes of threads. For the larger sizes, various more or less satisfactory methods have been devised, but none of these have found wide application.

Screw Thread Gage Classification.— Screw thread gages are classified by their degree of accuracy, that is, by the amount of tolerance afforded the gage manufacturer and the wear allowance, if any.

There are also three classifications according to use: 1) Working gages for controlling production; 2) inspection gages for rejection or acceptance of the finished product; and 3) reference gages for determining the accuracy of the working and inspection gages.

American National Standard for Gages and Gaging for Unified Inch Screw Threads ANSI/ASME B1.2-1983 (R2001).— This standard covers gaging methods for conformance of Unified Screw threads and provides the essential specifications for applicable gages required for unified inch screw threads.

The standard includes the following gages for *Product Internal Thread:*

GO Working Thread Plug Gage for inspecting the maximum-material GO functional limit.

NOT GO (HI) Thread Plug Gage for inspecting the NOT GO (HI) functional diameter limit.

Thread Snap Gage—GO Segments or Rolls for inspecting the maximum-material GO functional limit.

Thread Snap Gage—NOT GO (HI) Segments or Rolls for inspecting the NOT GO (HI) functional diameter limit.

Thread Snap Gages—Minimum Material: Pitch Diameter Cone Type and Vee and Thread Groove Diameter Type for inspecting the minimum-material limit pitch diameter.

Thread-Setting Solid Ring Gage for setting internal thread indicating and snap gages.

Plain Plug, Snap, and Indicating Gages for checking the minor diameter of internal threads.

Snap and Indicating Gages for checking the major diameter of internal threads.

Functional Indicating Thread Gage for inspecting the maximum-material GO functional limit and size and the NOT GO (HI) functional diameter limit and size.

Copyright 2004, Industrial Press, Inc., New York, NY

Minimum-Material Indicating Thread Gage for inspecting the minimum-material limit and size.

Indicating Runout Thread Gage for inspecting runout of the minor diameter to pitch diameter.

In addition to these gages for product internal threads, the Standard also covers differential gaging and such instruments as pitch micrometers, thread-measuring balls, optical comparator and toolmaker's microscope, profile tracing instrument, surface roughness measuring instrument, and roundness measuring equipment.

The Standard includes the following gages for *Product External Thread:*

GO Working Thread Ring Gage for inspecting the maximum-material GO functional limit.

NOT GO (LO) Thread Ring Gage for inspecting the NOT GO (LO) functional diameter limit.

Thread Snap Gage—GO Segments or Rolls for inspecting the maximum-material GO functional limit.

Thread Snap Gage—NOT GO (LO) Segments or Rolls for inspecting the NOT GO (LO) functional diameter limit.

Thread Snap Gages—Cone and Vee Type and Minimum Material Thread Groove Diameter Type for inspecting the minimum-material pitch diameter limit.

Plain Ring and Snap Gages for checking the major diameter.

Snap Gage for checking the minor diameter.

Functional Indicating Thread Gage for inspecting the maximum-material GO functional limit and size and the NOT GO (LO) functional diameter limit and size.

Minimum-Material Indicating Thread Gage for inspecting the minimum-material limit and size.

Indicating Runout Gage for inspecting the runout of the major diameter to the pitch diameter.

W Tolerance Thread-Setting Plug Gage for setting adjustable thread ring gages, checking solid thread ring gages, setting thread snap limit gages, and setting indicating thread gages.

Plain Check Plug Gage for Thread Ring Gage for verifying the minor diameter limits of thread ring gages after the thread rings have been properly set with the applicable thread-setting plug gages.

Indicating Plain Diameter Gage for checking the major diameter.

Indicating Gage for checking the minor diameter.

In addition to these gages for product external threads, the Standard also covers differential gaging and such instruments as thread micrometers, thread-measuring wires, optical comparator and toolmaker's microscope, profile tracing instrument, electromechanical lead tester, helical path attachment used with GO type thread indicating gage, helical path analyzer, surface roughness measuring equipment, and roundness measuring equipment.

The standard lists the following for use of Threaded and Plain Gages for verification of product internal threads:

Tolerance: Unless otherwise specified all thread gages which directly check the product thread shall be X tolerance for all classes.

GO Thread Plug Gages: GO thread plug gages must enter and pass through the full threaded length of the product freely. The GO thread plug gage is a cumulative check of all thread elements except the minor diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

NOT GO (HI) Thread Plug Gages: NOT GO (HI) thread plug gages when applied to the product internal thread may engage only the end threads (which may not be representative of the complete thread). Entering threads on product are incomplete and permit gage to start. Starting threads on NOT GO (HI) plugs are subject to greater wear than the remaining threads. Such wear in combination with the incomplete product threads permits further entry of the gage. NOT GO (HI) functional diameter is acceptable when the NOT GO (HI) thread plug gage applied to the product internal thread does not enter more than three complete turns. The gage should not be forced. Special requirements such as exceptionally thin or ductile material, small number of threads, etc., may necessitate modification of this practice.

GO and NOT GO Plain Plug Gages for Minor Diameter of Product Internal Thread: (Recommended in Class Z tolerance.) GO plain plug gages must completely enter and pass through the length of the product without force. NOT GO cylindrical plug gage must not enter.

The standard lists the following for use of Thread Gages for verification of product external threads:

GO Thread Ring Gages: Adjustable GO thread ring gages must be set to the applicable W tolerance setting plugs to assure they are within specified limits. The product thread must freely enter the GO thread ring gage for the entire length of the threaded portion. The GO thread ring gage is a cumulative check of all thread elements except the major diameter.

NOT GO (LO) Thread Ring Gages: NOT GO (LO) thread ring gages must be set to the applicable W tolerance setting plugs to assure that they are within specified limits. NOT GO (LO) thread ring gages when applied to the product external thread may engage only the end threads (which may not be representative of the complete product thread)

Starting threads on NOT GO (LO) rings are subject to greater wear than the remaining threads. Such wear in combination with the incomplete threads at the end of the product thread permit further entry in the gage. NOT GO (LO) functional diameter is acceptable when the NOT GO (LO) thread ring gage applied to the product external thread does not pass over the thread more than three complete turns. The gage should not be forced. Special requirements such as exceptionally thin or ductile material, small number of threads, etc., may necessitate modification of this practice.

GO and NOT GO Plain Ring and Snap Gages for Checking Major Diameter of Product External Thread: The GO gage must completely receive or pass over the major diameter of the product external thread to ensure that the major diameter does not exceed the maximum-material-limit. The NOT GO gage must not pass over the major diameter of the product external thread to ensure that the major diameter is not less than the minimum-material-limit.

Limitations concerning the use of gages are given in the standard as follows:

Product threads accepted by a gage of one type may be verified by other types. It is possible, however, that parts which are near either rejection limit may be accepted by one type and rejected by another. Also, it is possible for two individual limit gages of the same type to be at the opposite extremes of the gage tolerances permitted, and borderline product threads accepted by one gage could be rejected by another. For these reasons, a product screw thread is considered acceptable when it passes a test by any of the permissible gages in ANSI B1.3 for the gaging system that are within the tolerances.

Gaging large product external and internal threads equal to above 6.25-inch nominal size with plain and threaded plug and ring gages presents problems for technical and economic reasons. In these instances, verification may be based on use of modified snap or indicating gages or measurement of thread elements. Various types of gages or measuring

Copyright 2004, Industrial Press, Inc., New York, NY

devices in addition to those defined in the Standard are available and acceptable when properly correlated to this Standard. Producer and user should agree on the method and equipment used.

Thread Forms of Gages.— Thread forms of gages for product internal and external threads are given in Table 1. The Standard ANSI/ASME B1.2-1983 (R2001) also gives illustrations of the thread forms of truncated thread setting plug gages, the thread forms of full-form thread setting plug gages, the thread forms of solid thread setting ring gages, and an illustration that shows the chip groove and removal of partial thread.

Thread Gage Tolerances.— Gage tolerances of thread plug and ring gages, thread setting plugs, and setting rings for Unified screw threads, designated as W and X tolerances, are given in Table 4. W tolerances represent the highest commercial grade of accuracy and workmanship, and are specified for thread setting gages; X tolerances are larger than W tolerances and are used for product inspection gages. Tolerances for plain gages are given in Table 2.

Determining Size of Gages: The three-wire method of determining pitch diameter size of plug gages is recommended for gages covered by American National Standard B1.2, described in Appendix B of the 1983 issue of that Standard.

Size limit adjustments of thread ring and external thread snap gages are determined by their fit on their respective calibrated setting plugs. Indicating gages and thread gages for product external threads are controlled by reference to appropriate calibrated setting plugs.

Size limit adjustments of internal thread snap gages are determined by their fit on their respective calibrated setting rings. Indicating gages and other adjustable thread gages for product internal threads are controlled by reference to appropriate calibrated setting rings or by direct measuring methods.

Interpretation of Tolerances: Tolerances on lead, half-angle, and pitch diameter are variations which may be taken independently for each of these elements and may be taken to the extent allowed by respective tabulated dimensional limits. The tabulated tolerance on any one element must not be exceeded, even though variations in the other two elements are smaller than the respective tabulated tolerances.

Direction of Tolerance on Gages: At the maximum-material limit (GO), the dimensions of all gages used for final conformance gaging are to be within limits of size of the product thread. At the functional diameter limit, using NOT GO (HI and LO) thread gages, the standard practice is to have the gage tolerance within the limits of size of the product thread.

Formulas for Limits of Gages: Formulas for limits of American National Standard Gages for Unified screw threads are given in Table 5. Some constants which are required to determine gage dimensions are tabulated in Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Thread Forms of Gages for Product Internal and External Threads









Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. American National Standard Tolerances for Plain Cylindrical Gages
ANSI/ASME B1.2-1983 (R2001)

Size Range		Tolerance Class[a]				
		XX	X	Y	Z	ZZ
Above	To and Including	Tolerance				
0.020	0.825	.00002	.00004	.00007	.00010	.00020
0.825	1.510	.00003	.00006	.00009	.00012	.00024
1.510	2.510	.00004	.00008	.00012	.00016	.00032
2.510	4.510	.00005	.00010	.00015	.00020	.00040
4.510	6.510	.000065	.00013	.00019	.00025	.00050
6.510	9.010	.00008	.00016	.00024	.00032	.00064
9.010	12.010	.00010	.00020	.00030	.00040	.00080

[a] Tolerances apply to actual diameter of plug or ring. Apply tolerances as specified in the Standard. Symbols XX, X, Y, Z, and ZZ are standard gage tolerance classes.

All dimensions are given in inches.

Table 3. Constants for Computing Thread Gage Dimensions
ANSI/ASME B1.2-1983 (R2001)

Threads per Inch	Pitch, p	$0.060\sqrt[3]{p^2} + 0.017p$	$.05p$	$.087p$	Height of Sharp V-Thread, H = $.866025p$	$H/2$ = $.43301p$	$H/4$ = $.216506p$
80	.012500	.0034	.00063	.00109	.010825	.00541	.00271
72	.013889	.0037	.00069	.00122	.012028	.00601	.00301
64	.015625	.0040	.00078	.00136	.013532	.00677	.00338
56	.017857	.0044	.00089	.00155	.015465	.00773	.00387
48	.020833	.0049	.00104	.00181	.018042	.00902	.00451
44	.022727	.0052	.00114	.00198	.019682	.00984	.00492
40	.025000	.0056	.00125	.00218	.021651	.01083	.00541
36	.027778	.0060	.00139	.00242	.024056	.01203	.00601
32	.031250	.0065	.00156	.00272	.027063	.01353	.00677
28	.035714	.0071	.00179	.00311	.030929	.01546	.00773
27	.037037	.0073	.00185	.00322	.032075	.01604	.00802
24	.041667	.0079	.00208	.00361	.036084	.01804	.00902
20	.050000	.0090	.00250	.00435	.043301	.02165	.01083
18	.055556	.0097	.00278	.00483	.048113	.02406	.01203
16	.062500	.0105	.00313	.00544	0.54127	.02706	.01353
14	.071429	.0115	.00357	.00621	.061859	.03093	.01546
13	.076923	.0122	.00385	.00669	.066617	.03331	.01665
12	.083333	.0129	.00417	.00725	.072169	.03608	.01804
11½	.086957	.0133	.00435	.00757	.075307	.03765	.01883
11	.090909	.0137	.00451	.00791	.078730	.03936	.01968
10	.100000	.0146	.00500	.00870	.086603	.04330	.02165
9	.111111	.0158	.00556	.00967	.096225	.04811	.02406
8	.125000	.0171	.00625	.01088	.108253	.05413	.02706
7	.142857	.0188	.00714	.01243	.123718	.06186	.03093
6	.166667	.0210	.00833	.01450	.144338	.07217	.03608
5	.200000	.0239	.01000	.01740	.173205	.08660	.04330
4½	.222222	.0258	.01111	.01933	.192450	.09623	.04811
4	.250000	.0281	.01250	.02175	.216506	.10825	.05413

All dimensions are given in inches unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American National Standard Tolerance for GO, HI, and LO Thread Gages for Unified Inch Screw Thread

Thds. per Inch	Tolerance on Lead[a]		Tol. on Thread Half-angle (±), minutes	Tol. on Major and Minor Diams.[b]			Tolerance on Pitch Diameter[b]				
	To & incl. ½ in. Dia.	Above ½ in. Dia.		To & incl. ½ in. Dia.	Above ½ to 4 in. Dia.	Above 4 in. Dia.	To & incl. ½ in. Dia.	Above ½ to 1½ in. Dia.	Above 1½ to 4 in. Dia.	Above 4 to 8 in. Dia.	Above 8 to 12 in.[c] Dia.
W GAGES											
80, 72	.0001	.00015	20	.0003	.0003	…	.0001	.00015	…	…	…
64	.0001	.00015	20	.0003	.0004	…	.0001	.00015	…	…	…
56	.0001	.00015	20	.0003	.0004	…	.0001	.00015	.0002	…	…
48	.0001	.00015	18	.0003	.0004	…	.0001	.00015	.0002	…	…
44, 40	.0001	.00015	15	.0003	.0004	…	.0001	.00015	.0002	…	…
36	.0001	.00015	12	.0003	.0004	…	.0001	.00015	.0002	…	…
32	.0001	.00015	12	.0003	.0005	.0007	.0001	.00015	.0002	.00025	.0003
28, 27	.00015	.00015	8	.0005	.0005	.0007	.0001	.00015	.0002	.00025	.0003
24, 20	.00015	.00015	8	.0005	.0005	.0007	.0001	.00015	.0002	.00025	.0003
18	.00015	.00015	8	.0005	.0005	.0007	.0001	.00015	.0002	.00025	.0003
16	.00015	.00015	8	.0006	.0006	.0009	.0001	.0002	.00025	.0003	.0004
14, 13	.0002	.0002	6	.0006	.0006	.0009	.00015	.0002	.00025	.0003	.0004
12	.0002	.0002	6	.0006	.0006	.0009	.00015	.0002	.00025	.0003	.0004
11½	.0002	.0002	6	.0006	.0006	.0009	.00015	.0002	.00025	.0003	.0004
11	.0002	.0002	6	.0006	.0006	.0009	.00015	.0002	.00025	.0003	.0004
10	…	.00025	6	…	.0006	.0009	…	.0002	.0025	.0003	.0004
9	…	.00025	6	…	.0007	.0011	…	.0002	.00025	.0003	.0004
8	…	.00025	5	…	.0007	.0011	…	.0002	.00025	.0003	.0004
7	…	.0003	5	…	.0007	.0011	…	.0002	.00025	.0003	.0004
6	…	.0003	5	…	.0008	.0013	…	.0002	.00025	.0003	.0004
5	…	.0003	4	…	.0008	.0013	…	…	.00025	.0003	.0004
4½	…	.0003	4	…	.0008	.0013	…	…	.00025	.0003	.0004
4	…	.0003	4	…	.0009	.0015	…	…	.00025	.0003	.0004
X GAGES											
80, 72	.0002	.0002	30	.0003	.0003	…	.0002	.0002	…	…	…
64	.0002	.0002	30	.0004	.0004	…	.0002	.0002	…	…	…
56, 48	.0002	.0002	30	.0004	.0004	…	.0002	.0002	.0003	…	…
44, 40	.0002	.0002	20	.0004	.0004	…	.0002	.0002	.0003	…	…
36	.0002	.0002	20	.0004	.0004	…	.0002	.0002	.0003	…	…
32, 28	.0003	.0003	15	.0005	.0005	.0007	.0003	.0003	.0004	.0005	.0006
27, 24	.0003	.0003	15	.0005	.0005	.0007	.0003	.0003	.0004	.0005	.0006
20	.0003	.0003	15	.0005	.0005	.0007	.0003	.0003	.0004	.0005	.0006
18	.0003	.0003	10	.0005	.0005	.0007	.0003	.0003	.0004	.0005	.0006
16, 14	.0003	.0003	10	.0006	.0006	.0009	.0003	.0003	.0004	.0006	.0008
13, 12	.0003	.0003	10	.0006	.0006	.0009	.0003	.0003	.0004	.0006	.0008
11½	.0003	.0003	10	.0006	.0006	.0009	.0003	.0003	.0004	.0006	.0008
11, 10	.0003	.0003	10	.0006	.0006	.0009	.0003	.0003	.0004	.0006	.0008
9	.0003	.0003	10	.0007	.0007	.0011	.0003	.0003	.0004	.0006	.0008
8, 7	.0004	.0004	5	.0007	.0007	.0011	.0004	.0004	.0005	.0006	.0008
6	.0004	.0004	5	.0008	.0008	.0013	.0004	.0004	.0005	.0006	.0008
5, 4½	.0004	.0004	5	.0008	.0008	.0013	…	…	.0005	.0006	.0008
4	.0004	.0004	5	.0009	.0009	.0015	…	…	.0005	.0006	.0008

[a] Allowable variation in lead between any two threads not farther apart than the length of the standard gage as shown in ANSI B47.1. The tolerance on lead establishes the width of a zone, measured parallel to the axis of the thread, within which the actual helical path must lie for the specified length of the thread. Measurements are taken from a fixed reference point, located at the start of the first full thread, to a sufficient number of positions along the entire helix to detect all types of lead variations. The amounts that these positions vary from their basic (theoretical) positions are recorded with due respect to sign. The greatest variation in each direction (±) is selected, and the sum of their values, disregarding sign, must not exceed the tolerance limits specified for W gages.

[b] Tolerances apply to designated size of thread. The application of the tolerances is specified in the Standard.

[c] Above 12 in. the tolerance is directly proportional to the tolerance given in this column below, in the ratio of the diameter to 12 in.

All dimensions are given in inches unless otherwise specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Formulas for Limits of American National Standard Gages for Unified Inch Screw Threads *ANSI/ASME B1.2-1983 (R2001)*

No.	Thread Gages for External Threads
1	GO Pitch Diameter = Maximum pitch diameter of external thread. Gage tolerance is *minus*.
2	GO Minor Diameter = Maximum pitch diameter of external thread minus *H*/2. Gage tolerance is *minus*.
3	NOT GO (LO) Pitch Diameter (for plus tolerance gage) = Minimum pitch diameter of external thread. Gage tolerance is *plus*.
4	NOT GO (LO) Minor Diameter = Minimum pitch diameter of external thread minus *H*/4. Gage tolerance is *plus*.
	Plain Gages for Major Diameter of External Threads
5	GO = Maximum major diameter of external thread. Gage tolerance is *minus*.
6	NOT GO = Minimum major diameter of external thread. Gage tolerance is *plus*.
	Thread Gages for Internal Threads
7	GO Major Diameter = Minimum major diameter of internal thread. Gage tolerance is *plus*.
8	GO Pitch Diameter = Minimum pitch diameter of internal thread. Gage tolerance is *plus*.
9	NOT GO (HI) Major Diameter = Maximum pitch diameter of internal thread plus *H*/2. Gage tolerance is *minus*.
10	NOT GO (HI) Pitch Diameter = Maximum pitch diameter of internal thread. Gage tolerance is *minus*.
	Plain Gages for Minor Diameter of Internal Threads
11	GO = Minimum minor diameter of internal thread. Gage tolerance is *plus*.
12	NOT GO = Maximum minor diameter of internal thread. Gage tolerance is *minus*.
	Full Form nd Truncated Setting Plugs
13	GO Major Diameter (Truncated Portion) = Maximum major diameter of external thread (= minimum major diameter of full portion of GO setting plug) minus $(0.060\sqrt[3]{p^2} + 0.017p)$. Gage tolerance is *minus*.
14	GO Major Diameter (Full Portion) = Maximum major diameter of external thread. Gage tolerance is *plus*.
15	GO Pitch Diameter = Maximum pitch diameter of external thread. Gage tolerance is *minus*.
16	[a]NOT GO (LO) Major Diameter (Truncated Portion) = Minimum pitch diameter of external thread plus *H*/2. Gage tolerance is *minus*.
17	NOT GO (LO) Major Diameter (Full Portion) = Maximum major diameter of external thread provided major diameter crest width shall not be less than 0.001 in. (0.0009 in. truncation). Apply W tolerance *plus* for maximum size except that for 0.001 in. crest width apply tolerance *minus*. For the 0.001 in. crest width, major diameter is equal to maximum major diameter of external thread plus 0.216506*p* minus the sum of external thread pitch diameter tolerance and 0.0017 in.
18	NOT GO (LO) Pitch Diameter = Minimum pitch diameter of external thread. Gage tolerance is *plus*.
	Solid Thread-setting Rings for Snap and Indicating Gages
19	[b]GO Pitch Diameter = Minimum pitch diameter of internal thread. W gage tolerance is *plus*.
20	GO Minor Diameter = Minimum minor diameter of internal thread. W gage tolerance is *minus*.
21	[b]NOT GO (HI) Pitch Diameter = Maximum pitch diameter of internal thread. W gage tolerance is *minus*.
22	NOT GO (HI) Minor Diameter = Maximum minor diameter of internal thread. W gage tolerance is *minus*.

[a] Truncated portion is required when optional sharp root profile is used.

[b] Tolerances greater than W tolerance for pitch diameter are acceptable when internal indicating or snap gage can accommodate a greater tolerance and when agreed upon by supplier and user.

See data in Screw Thread Systems section for symbols and dimensions of Unified Screw Threads.

Copyright 2004, Industrial Press, Inc., New York, NY

TAPPING AND THREAD CUTTING

Selection of Taps.— For most applications, a standard tap supplied by the manufacturer can be used, but some jobs may require special taps. A variety of standard taps can be obtained. In addition to specifying the size of the tap it is necessary to be able to select the one most suitable for the application at hand.

The elements of standard taps that are varied are: the number of flutes; the type of flute, whether straight, spiral pointed, or spiral fluted; the chamfer length; the relief of the land, if any; the tool steel used to make the tap; and the surface treatment of the tap.

Details regarding the nomenclature of tap elements are given in the section *TAPS AND THREADING DIES* starting on page 892, along with a listing of the standard sizes available.

Factors to consider in selecting a tap include: the method of tapping, by hand or by machine; the material to be tapped and its heat treatment; the length of thread, or depth of the tapped hole; the required tolerance or class of fit; and the production requirement and the type of machine to be used.

The diameter of the hole must also be considered, although this action is usually only a matter of design and the specification of the tap drill size.

Method of Tapping: The term *hand tap* is used for both hand and machine taps, and almost all taps can be applied by the hand or machine method. While any tap can be used for hand tapping, those having a concentric land without the relief are preferable. In hand tapping the tool is reversed periodically to break the chip, and the heel of the land of a tap with a concentric land (without relief) will cut the chip off cleanly or any portion of it that is attached to the work, whereas a tap with an eccentric or con-eccentric relief may leave a small burr that becomes wedged between the relieved portion of the land and the work. This wedging creates a pressure towards the cutting face of the tap that may cause it to chip; it tends to roughen the threads in the hole, and it increases the overall torque required to turn the tool. When tapping by machine, however, the tap is usually turned only in one direction until the operation is complete, and an eccentric or con-eccentric relief is often an advantage.

Chamfer Length: Three types of hand taps, used both for hand and machine tapping, are available, and they are distinguished from each other by the length of chamfer. *Taper taps* have a chamfer angle that reduces the height about 8–10 teeth; *plug taps* have a chamfer angle with 3–5 threads reduced in height; and *bottoming taps* have a chamfer angle with 1½ threads reduced in height. Since the teeth that are reduced in height do practically all the cutting, the chip load or chip thickness per tooth will be least for a taper tap, greater for a plug tap, and greatest for a bottoming tap.

For most through hole tapping applications it is necessary to use only a plug type tap, which is also most suitable for blind holes where the tap drill hole is deeper than the required thread. If the tap must bottom in a blind hole, the hole is usually threaded first with a plug tap and then finished with a bottoming tap to catch the last threads in the bottom of the hole. Taper taps are used on materials where the chip load per tooth must be kept to a minimum. However, taper taps should not be used on materials that have a strong tendency to work harden, such as the austenitic stainless steels.

Spiral Point Taps: Spiral point taps offer a special advantage when machine tapping through holes in ductile materials because they are designed to handle the long continuous chips that form and would otherwise cause a disposal problem. An angular gash is ground at the point or end of the tap along the face of the chamfered threads or lead teeth of the tap. This gash forms a left-hand helix in the flutes adjacent to the lead teeth which causes the chips to flow ahead of the tap and through the hole. The gash is usually formed to produce a rake angle on the cutting face that increases progressively toward the end of the tool. Since the flutes are used primarily to provide a passage for the cutting fluid, they are usu-

Copyright 2004, Industrial Press, Inc., New York, NY

ally made narrower and shallower thereby strengthening the tool. For tapping thin workpieces short fluted spiral point taps are recommended. They have a spiral point gash along the cutting teeth; the remainder of the threaded portion of the tap has no flute. Most spiral pointed taps are of plug type; however, spiral point bottoming taps are also made.

Spiral Fluted Taps: Spiral fluted taps have a helical flute; the helix angle of the flute may be between 15 and 52 degrees and the hand of the helix is the same as that of the threads on the tap. The spiral flute and the rake that it forms on the cutting face of the tap combine to induce the chips to flow backward along the helix and out of the hole. Thus, they are ideally suited for tapping blind holes and they are available as plug and bottoming types. A higher spiral angle should be specified for tapping very ductile materials; when tapping harder materials, chipping at the cutting edge may result and the spiral angle must be reduced.

Holes having a pronounced interruption such as a groove or a keyway can be tapped with spiral fluted taps. The land bridges the interruption and allows the tap to cut relatively smoothly.

Serial Taps and Close Tolerance Threads: For tapping holes to close tolerances a set of serial taps is used.

They are usually available in sets of three: the No. 1 tap is undersize and is the first rougher; the No. 2 tap is of intermediate size and is the second rougher; and the No. 3 tap is used for finishing.

The different taps are identified by one, two, and three annular grooves in the shank adjacent to the square. For some applications involving finer pitches only two serial taps are required. Sets are also used to tap hard or tough materials having a high tensile strength, deep blind holes in normal materials, and large coarse threads. A set of more than three taps is sometimes required to produce threads of coarse pitch. Threads to some commercial tolerances, such as American Standard Unified 2B, or ISO Metric 6H, can be produced in one cut using a ground tap; sometimes even closer tolerances can be produced with a single tap. Ground taps are recommended for all close tolerance tapping operations. For much ordinary work, cut taps are satisfactory and more economical than ground taps.

Tap Steels: Most taps are made from high speed steel. The type of tool steel used is determined by the tap manufacturer and is usually satisfactory when correctly applied except in a few exceptional cases. Typical grades of high speed steel used to make taps are M-1, M-2, M-3, M-42, etc. Carbon tool steel taps are satisfactory where the operating temperature of the tap is low and where a high resistance to abrasion is not required as in some types of hand tapping.

Surface Treatment: The life of high speed steel taps can sometimes be increased significantly by treating the surface of the tap. A very common treatment is oxide coating, which forms a thin metallic oxide coating on the tap that has lubricity and is somewhat porous to absorb and retain oil. This coating reduces the friction between the tap and the work and it makes the surface virtually impervious to rust. It does not increase the hardness of the surface but it significantly reduces or prevents entirely galling, or the tendency of the work material to weld or stick to the cutting edge and to other areas on the tap with which it is in contact. For this reason oxide coated taps are recommended for metals that tend to gall and stick such as non-free cutting low carbon steels and soft copper. It is also useful for tapping other steels having higher strength properties.

Nitriding provides a very hard and wear resistant case on high speed steel. Nitrided taps are especially recommended for tapping plastics; they have also been used successfully on a variety of other materials including high strength high alloy steels. However, some caution must be used in specifying nitrided taps because the nitride case is very brittle and may have a tendency to chip.

Chrome plating has been used to increase the wear resistance of taps but its application has been limited because of the high cost and the danger of hydrogen embrittlement which can cause cracks to form in the tool. A flash plate of about .0001 in. or less in thickness is

Copyright 2004, Industrial Press, Inc., New York, NY

applied to the tap. Chrome-plated taps have been used successfully to tap a variety of ferrous and nonferrous materials including plastics, hard rubber, mild steel, and tool steel. Other surface treatments that have been used successfully to a limited extent are vapor blasting and liquid honing.

Rake Angle: For the majority of applications in both ferrous and nonferrous materials the rake angle machined on the tap by the manufacturer is satisfactory. This angle is approximately 5 to 7 degrees. In some instances it may be desirable to alter the rake angle of the tap to obtain beneficial results and Table 1 provides a guide that can be used. In selecting a rake angle from this table, consideration must be given to the size of the tap and the strength of the land. Most standard taps are made with a curved face with the rake angle measured as a chord between the crest and root of the thread. The resulting shape is called a hook angle.

Table 1. Tap Rake Angles for Tapping Different Materials

Material	Rake Angle, Degrees	Material	Rake Angle, Degrees
Cast Iron	0–3	Aluminum	8–20
Malleable Iron	5–8	Brass	2–7
Steel		Naval Brass	5–8
AISI 1100 Series	5–12	Phosphor Bronze	5–12
Low Carbon (up	5–12	Tobin Bronze	5–8
to .25 per cent)		Manganese Bronze	5–12
Medium Carbon, Annealed	5–10	Magnesium	10–20
(.30 to .60 per cent)		Monel	9–12
Heat Treated, 225–283	0–8	Copper	10–18
Brinell. (.30 to .60 per cent)		Zinc Die Castings	10–15
High Carbon and	0–5	Plastic	
High Speed		Thermoplastic	5–8
Stainless	8–15	Thermosetting	0–3
Titanium	5–10	Hard Rubber	0–3

Cutting Speed.— The cutting speed for machine tapping is treated in detail on page 1072. It suffices to say here that many variables must be considered in selecting this cutting speed and any tabulation may have to be modified greatly. Where cutting speeds are mentioned in the following section, they are intended only to provide a guideline to show the possible range of speeds that could be used.

Tapping Specific Materials.— The work material has a great influence on the ease with which a hole can be tapped. For production work, in many instances, modified taps are recommended; however, for toolroom or short batch work, standard hand taps can be used on most jobs, providing reasonable care is taken when tapping. The following concerns the tapping of metallic materials; information on the tapping of plastics is given on page 623.

Low Carbon Steel (Less than 0.15% C): These steels are very soft and ductile resulting in a tendency for the work material to tear and to weld to the tap. They produce a continuous chip that is difficult to break and spiral pointed taps are recommended for tapping through holes; for blind holes a spiral fluted tap is recommended. To prevent galling and welding, a liberal application of a sulfur base or other suitable cutting fluid is essential and the selection of an oxide coated tap is very helpful.

Low Carbon Steels (0.15 to 0.30% C): The additional carbon in these steels is beneficial as it reduces the tendency to tear and to weld; their machinability is further improved by cold drawing. These steels present no serious problems in tapping provided a suitable cut-

Copyright 2004, Industrial Press, Inc., New York, NY

ting fluid is used. An oxide coated tap is recommended, particularly in the lower carbon range.

Medium Carbon Steels (0.30 to 0.60% C): These steels can be tapped without too much difficulty, although a lower cutting speed must be used in machine tapping. The cutting speed is dependent on the carbon content and the heat treatment. Steels that have a higher carbon content must be tapped more slowly, especially if the heat treatment has produced a pearlitic microstructure. The cutting speed and ease of tapping is significantly improved by heat treating to produce a spheroidized microstructure. A suitable cutting fluid must be used.

High Carbon Steels (More than 0.6% C): Usually these materials are tapped in the annealed or normalized condition although sometimes tapping is done after hardening and tempering to a hardness below 55 Rc. Recommendations for tapping after hardening and tempering are given under High Tensile Strength Steels. In the annealed and normalized condition these steels have a higher strength and are more abrasive than steels with a lower carbon content; thus, they are more difficult to tap. The microstructure resulting from the heat treatment has a significant effect on the ease of tapping and the tap life, a spheroidite structure being better in this respect than a pearlitic structure. The rake angle of the tap should not exceed 5 degrees and for the harder materials a concentric tap is recommended. The cutting speed is considerably lower for these steels and an activated sulfur-chlorinated cutting fluid is recommended.

Alloy Steels: This classification includes a wide variety of steels, each of which may be heat treated to have a wide range of properties. When annealed and normalized they are similar to medium to high carbon steels and usually can be tapped without difficulty, although for some alloy steels a lower tapping speed may be required. Standard taps can be used and for machine tapping a con-eccentric relief may be helpful. A suitable cutting fluid must be used.

High-Tensile Strength Steels: Any steel that must be tapped after being heat treated to a hardness range of 40–55 Rc is included in this classification. Low tap life and excessive tap breakage are characteristics of tapping these materials; those that have a high chromium content are particularly troublesome. Best results are obtained with taps that have concentric lands, a rake angle that is at or near zero degrees, and 6 to 8 chamfered threads on the end to reduce the chip load per tooth. The chamfer relief should be kept to a minimum. The load on the tap should be kept to a minimum by every possible means, including using the largest possible tap drill size; keeping the hole depth to a minimum; avoidance of bottoming holes; and, in the larger sizes, using fine instead of coarse pitches. Oxide coated taps are recommended although a nitrided tap can sometimes be used to reduce tap wear. An active sulfur-chlorinated oil is recommended as a cutting fluid and the tapping speed should not exceed about 10 feet per minute.

Stainless Steels: Ferritic and martensitic type stainless steels are somewhat like alloy steels that have a high chromium content, and they can be tapped in a similar manner, although a slightly slower cutting speed may have to be used. Standard rake angle oxide coated taps are recommended and a cutting fluid containing molybdenum disulphide is helpful to reduce the friction in tapping. Austenitic stainless steels are very difficult to tap because of their high resistance to cutting and their great tendency to work harden. A work-hardened layer is formed by a cutting edge of the tap and the depth of this layer depends on the severity of the cut and the sharpness of the tool. The next cutting edge must penetrate below the work-hardened layer, if it is to be able to cut. Therefore, the tap must be kept sharp and each succeeding cutting edge on the tool must penetrate below the work-hardened layer formed by the preceding cutting edge. For this reason, a taper tap should not be used, but rather a plug tap having 3–5 chamfered threads. To reduce the rubbing of the lands, an eccentric or con-eccentric relieved land should be used and a 10–15 degree rake angle is recommended. A tough continuous chip is formed that is difficult to break. To con-

Copyright 2004, Industrial Press, Inc., New York, NY

trol this chip, spiral pointed taps are recommended for through holes and low-helix angle spiral fluted taps for blind holes. An oxide coating on the tap is very helpful and a sulfur-chlorinated mineral lard oil is recommended, although heavy duty soluble oils have also been used successfully.

Free Cutting Steels: There are large numbers of free cutting steels, including free cutting stainless steels, which are also called free machining steels. Sulfur, lead, or phosphorus are added to these steels to improve their machinability. Free machining steels are always easier to tap than their counterparts that do not have the free machining additives. Tool life is usually increased and a somewhat higher cutting speed can be used. The type of tap recommended depends on the particular type of free machining steel and the nature of the tapping operation; usually a standard tap can be used.

High Temperature Alloys: These are cobalt or nickel base nonferrous alloys that cut like austenitic stainless steel, but are often even more difficult to machine. The recommendations given for austenitic stainless steel also apply to tapping these alloys but the rake angle should be 0 to 10 degrees to strengthen the cutting edge. For most applications a nitrided tap or one made from M41, M42, M43, or M44 steel is recommended. The tapping speed is usually in the range of 5 to 10 feet per minute.

Titanium and Titanium Alloys: Titanium and its alloys have a low specific heat and a pronounced tendency to weld on to the tool material; therefore, oxide coated taps are recommended to minimize galling and welding. The rake angle of the tap should be from 6 to 10 degrees. To minimize the contact between the work and the tap an eccentric or con-eccentric relief land should be used. Taps having interrupted threads are sometimes helpful. Pure titanium is comparatively easy to tap but the alloys are very difficult. The cutting speed depends on the composition of the alloy and may vary from 40 to 10 feet per minute. Special cutting oils are recommended for tapping titanium.

Gray Cast Iron: The microstructure of gray cast iron can vary, even within a single casting, and compositions are used that vary in tensile strength from about 20,000 to 60,000 psi (160 to 250 Bhn). Thus, cast iron is not a single material, although in general it is not difficult to tap. The cutting speed may vary from 90 feet per minute for the softer grades to 30 feet per minute for the harder grades. The chip is discontinuous and straight fluted taps should be used for all applications. Oxide coated taps are helpful and gray cast iron can usually be tapped dry, although water soluble oils and chemical emulsions are sometimes used.

Malleable Cast Iron: Commercial malleable cast irons are also available having a rather wide range of properties, although within a single casting they tend to be quite uniform. They are relatively easy to tap and standard taps can be used. The cutting speed for ferritic cast irons is 60–90 feet per minute, for pearlitic malleable irons 40–50 feet per minute, and for martensitic malleable irons 30–35 feet per minute. A soluble oil cutting fluid is recommended except for martensitic malleable iron where a sulfur base oil may work better.

Ductile or Nodular Cast Iron: Several classes of nodular iron are used having a tensile strength varying from 60,000 to 120,000 psi. Moreover, the microstructure in a single casting and in castings produced at different times vary rather widely. The chips are easily controlled but have some tendency to weld to the faces and flanks of cutting tools. For this reason oxide coated taps are recommended. The cutting speed may vary from 15 fpm for the harder martensitic ductile irons to 60 fpm for the softer ferritic grades. A suitable cutting fluid should be used.

Aluminum: Aluminum and aluminum alloys are relatively soft materials that have little resistance to cutting. The danger in tapping these alloys is that the tap will ream the hole instead of cutting threads, or that it will cut a thread eccentric to the hole. For these reasons, extra care must be taken when aligning the tap and starting the thread. For production tapping a spiral pointed tap is recommended for through holes and a spiral fluted tap for blind holes; preferably these taps should have a 10 to 15 degree rake angle. A lead screw tapping

Copyright 2004, Industrial Press, Inc., New York, NY

machine is helpful in cutting accurate threads. A heavy duty soluble oil or a light base mineral oil should be used as a cutting fluid.

Copper Alloys: Most copper alloys are not difficult to tap, except beryllium copper and a few other hard alloys. Pure copper offers some difficulty because of its ductility and the ductile continuous chip formed, which can be difficult to control. However, with reasonable care and the use of medium heavy duty mineral lard oil it can be tapped successfully. Red brass, yellow brass, and similar alloys containing not more than 35 per cent zinc produce a continuous chip. While straight fluted taps can be used for hand tapping these alloys, machine tapping should be done with spiral pointed or spiral fluted taps for through and blind holes respectively. Naval brass, leaded brass, and cast brasses produce a discontinuous chip and a straight fluted tap can be used for machine tapping. These alloys exhibit a tendency to close in on the tap and sometimes an interrupted thread tap is used to reduce the resulting jamming effect. Beryllium copper and the silicon bronzes are the strongest of the copper alloys. Their strength combined with their ability to work harden can cause difficulties in tapping. For these alloys plug type taps should be used and the taps should be kept as sharp as possible. A medium or heavy duty water soluble oil is recommended as a cutting fluid.

Diameter of Tap Drill.— Tapping troubles are sometimes caused by tap drills that are too small in diameter. The tap drill should not be smaller than is necessary to give the required strength to the thread as even a very small decrease in the diameter of the drill will increase the torque required and the possibility of broken taps. Tests have shown that any increase in the percentage of full thread over 60 per cent does not significantly increase the strength of the thread. Often, a 55 to 60 per cent thread is satisfactory, although 75 per cent threads are commonly used to provide an extra measure of safety. The present thread specifications do not always allow the use of the smaller thread depths. However, the specification given on a part drawing must be adhered to and may require smaller minor diameters than might otherwise be recommended.

The depth of the thread in the tapped hole is dependent on the length of thread engagement and on the material. In general, when the engagement length is more than one and one-half times the nominal diameter a 50 or 55 per cent thread is satisfactory. Soft ductile materials may permit use of a slightly larger tapping hole than brittle materials such as gray cast iron.

It must be remembered that a twist drill is a roughing tool that may be expected to drill slightly oversize and that some variations in the size of the tapping holes are almost inevitable. When a closer control of the hole size is required it must be reamed. Reaming is recommended for the larger thread diameters and for some fine pitch threads.

For threads of Unified form (see *American National and Unified Screw Thread Forms* on page 1725) the selection of tap drills is covered in the following section, Factors Influencing Minor Diameter Tolerances of Tapped Holes and the hole size limits are given in Table 2. Tables 3 and 4 give tap drill sizes for American National Form threads based on 75 per cent of full thread depth. For smaller-size threads the use of slightly larger drills, if permissible, will reduce tap breakage. The selection of tap drills for these threads also may be based on the hole size limits given in Table 2 for Unified threads that take lengths of engagement into account.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Recommended Hole Size Limits Before Tapping Unified Threads

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
0–80	0.0465	0.0500	0.0479	0.0514	0.0479	0.0514	0.0479	0.0514	0.0465	0.0500	0.0479	0.0514	0.0479	0.0514	0.0479	0.0514
1–64	0.0561	0.0599	0.0585	0.0623	0.0585	0.0623	0.0585	0.0623	0.0561	0.0599	0.0585	0.0623	0.0585	0.0623	0.0585	0.0623
1–72	0.0580	0.0613	0.0596	0.0629	0.0602	0.0635	0.0602	0.0635	0.0580	0.0613	0.0596	0.0629	0.0602	0.0635	0.0602	0.0635
2–56	0.0667	0.0705	0.0686	0.0724	0.0699	0.0737	0.0699	0.0737	0.0667	0.0705	0.0686	0.0724	0.0699	0.0737	0.0699	0.0737
2–64	0.0691	0.0724	0.0707	0.0740	0.0720	0.0753	0.0720	0.0753	0.0691	0.0724	0.0707	0.0740	0.0720	0.0753	0.0720	0.0753
3–48	0.0764	0.0804	0.0785	0.0825	0.0805	0.0845	0.0806	0.0846	0.0764	0.0804	0.0785	0.0825	0.0805	0.0845	0.0806	0.0846
3–56	0.0797	0.0831	0.0814	0.0848	0.0831	0.0865	0.0833	0.0867	0.0797	0.0831	0.0814	0.0848	0.0831	0.0865	0.0833	0.0867
4–40	0.0849	0.0894	0.0871	0.0916	0.0894	0.0939	0.0902	0.0947	0.0849	0.0894	0.0871	0.0916	0.0894	0.0939	0.0902	0.0947
4–48	0.0894	0.0931	0.0912	0.0949	0.0931	0.0968	0.0939	0.0976	0.0894	0.0931	0.0912	0.0949	0.0931	0.0968	0.0939	0.0976
5–40	0.0979	0.1020	0.1000	0.1041	0.1021	0.1062	0.1036	0.1077	0.0979	0.1020	0.1000	0.1041	0.1021	0.1062	0.1036	0.1077
5–44	0.1004	0.1042	0.1023	0.1060	0.1042	0.1079	0.1060	0.1097	0.1004	0.1042	0.1023	0.1060	0.1042	0.1079	0.1060	0.1097
6–32	0.104	0.109	0.106	0.112	0.109	0.114	0.112	0.117	0.1040	0.1091	0.1066	0.1115	0.1091	0.1140	0.1115	0.1164
6–40	0.111	0.115	0.113	0.117	0.115	0.119	0.117	0.121	0.1110	0.1148	0.1128	0.1167	0.1147	0.1186	0.1166	0.1205
8–32	0.130	0.134	0.132	0.137	0.134	0.139	0.137	0.141	0.1300	0.1345	0.1324	0.1367	0.1346	0.1389	0.1367	0.1410
8–36	0.134	0.138	0.136	0.140	0.138	0.142	0.140	0.144	0.1340	0.1377	0.1359	0.1397	0.1378	0.1416	0.1397	0.1435
10–24	0.145	0.150	0.148	0.154	0.150	0.156	0.152	0.159	0.1450	0.1502	0.1475	0.1528	0.1502	0.1555	0.1528	0.1581
10–32	0.156	0.160	0.158	0.162	0.160	0.164	0.162	0.166	0.1560	0.1601	0.1581	0.1621	0.1601	0.1641	0.1621	0.1661
12–24	0.171	0.176	0.174	0.179	0.176	0.181	0.178	0.184	0.1710	0.1758	0.1733	0.1782	0.1758	0.1807	0.1782	0.1831
12–28	0.177	0.182	0.179	0.184	0.182	0.186	0.184	0.188	0.1770	0.1815	0.1794	0.1836	0.1815	0.1857	0.1836	0.1878
12–32	0.182	0.186	0.184	0.188	0.186	0.190	0.188	0.192	0.1820	0.1858	0.1837	0.1877	0.1855	0.1895	0.1873	0.1913
$\frac{1}{4}$–20	0.196	0.202	0.199	0.204	0.202	0.207	0.204	0.210	0.1960	0.2013	0.1986	0.2040	0.2013	0.2067	0.2040	0.2094
$\frac{1}{4}$–28	0.211	0.216	0.213	0.218	0.216	0.220	0.218	0.222	0.2110	0.2152	0.2131	0.2171	0.2150	0.2190	0.2169	0.2209
$\frac{1}{4}$–32	0.216	0.220	0.218	0.222	0.220	0.224	0.222	0.226	0.2160	0.2196	0.2172	0.2212	0.2189	0.2229	0.2206	0.2246
$\frac{1}{4}$–36	0.220	0.224	0.221	0.225	0.224	0.226	0.225	0.228	0.2200	0.2243	0.2199	0.2243	0.2214	0.2258	0.2229	0.2273
$\frac{5}{16}$–18	0.252	0.259	0.255	0.262	0.259	0.265	0.262	0.268	0.2520	0.2577	0.2551	0.2604	0.2577	0.2630	0.2604	0.2657
$\frac{5}{16}$–24	0.267	0.272	0.270	0.275	0.272	0.277	0.275	0.280	0.2670	0.2714	0.2694	0.2734	0.2714	0.2754	0.2734	0.2774
$\frac{5}{16}$–32	0.279	0.283	0.281	0.285	0.283	0.286	0.285	0.289	0.2790	0.2817	0.2792	0.2832	0.2807	0.2847	0.2822	0.2862
$\frac{5}{16}$–36	0.282	0.286	0.284	0.288	0.285	0.289	0.287	0.291	0.2820	0.2863	0.2824	0.2863	0.2837	0.2877	0.2850	0.2890
$\frac{3}{8}$–16	0.307	0.314	0.311	0.318	0.314	0.321	0.318	0.325	0.3070	0.3127	0.3101	0.3155	0.3128	0.3182	0.3155	0.3209

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Recommended Hole Size Limits Before Tapping Unified Threads**

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$\frac{3}{8}$–24	0.330	0.335	0.333	0.338	0.335	0.340	0.338	0.343	0.3300	0.3336	0.3314	0.3354	0.3332	0.3372	0.3351	0.3391
$\frac{3}{8}$–32	0.341	0.345	0.343	0.347	0.345	0.349	0.347	0.351	0.3410	0.3441	0.3415	0.3455	0.3429	0.3469	0.3444	0.3484
$\frac{3}{8}$–36	0.345	0.349	0.346	0.350	0.347	0.352	0.349	0.353	0.3450	0.3488	0.3449	0.3488	0.3461	0.3501	0.3474	0.3514
$\frac{7}{16}$–14	0.360	0.368	0.364	0.372	0.368	0.376	0.372	0.380	0.3600	0.3660	0.3630	0.3688	0.3659	0.3717	0.3688	0.3746
$\frac{7}{16}$–20	0.383	0.389	0.386	0.391	0.389	0.395	0.391	0.397	0.3830	0.3875	0.3855	0.3896	0.3875	0.3916	0.3896	0.3937
$\frac{7}{16}$–28	0.399	0.403	0.401	0.406	0.403	0.407	0.406	0.410	0.3990	0.4020	0.3995	0.4035	0.4011	0.4051	0.4017	0.4067
$\frac{1}{2}$–13	0.417	0.426	0.421	0.430	0.426	0.434	0.430	0.438	0.4170	0.4225	0.4196	0.4254	0.4226	0.4284	0.4255	0.4313
$\frac{1}{2}$–12	0.410	0.414	0.414	0.424	0.414	0.428	0.424	0.433	0.4100	0.4161	0.4129	0.4192	0.4160	0.4223	0.4192	0.4255
$\frac{1}{2}$–20	0.446	0.452	0.449	0.454	0.452	0.457	0.454	0.460	0.4460	0.4498	0.4477	0.4517	0.4497	0.4537	0.4516	0.4556
$\frac{1}{2}$–28	0.461	0.467	0.463	0.468	0.466	0.470	0.468	0.472	0.4610	0.4645	0.4620	0.4660	0.4636	0.4676	0.4652	0.4692
$\frac{9}{16}$–12	0.472	0.476	0.476	0.486	0.476	0.490	0.486	0.495	0.4720	0.4783	0.4753	0.4813	0.4783	0.4843	0.4813	0.4873
$\frac{9}{16}$–18	0.502	0.509	0.505	0.512	0.509	0.515	0.512	0.518	0.5020	0.5065	0.5045	0.5086	0.5065	0.5106	0.5086	0.5127
$\frac{9}{16}$–24	0.517	0.522	0.520	0.525	0.522	0.527	0.525	0.530	0.5170	0.5209	0.5186	0.5226	0.5204	0.5244	0.5221	0.5261
$\frac{9}{16}$–28	0.524	0.528	0.526	0.531	0.528	0.532	0.531	0.535	0.5240	0.5270	0.5245	0.5285	0.5261	0.5301	0.5277	0.5317
$\frac{5}{8}$–11	0.527	0.536	0.532	0.541	0.536	0.546	0.541	0.551	0.5270	0.5328	0.5298	0.5360	0.5329	0.5391	0.5360	0.5422
$\frac{5}{8}$–12	0.535	0.544	0.540	0.549	0.544	0.553	0.549	0.558	0.5350	0.5406	0.5377	0.5435	0.5405	0.5463	0.5434	0.5492
$\frac{5}{8}$–18	0.565	0.572	0.568	0.575	0.572	0.578	0.575	0.581	0.5650	0.5690	0.5670	0.5711	0.5690	0.5730	0.5711	0.5752
$\frac{5}{8}$–24	0.580	0.585	0.583	0.588	0.585	0.590	0.588	0.593	0.5800	0.5834	0.5811	0.5851	0.5829	0.5869	0.5846	0.5886
$\frac{5}{8}$–28	0.586	0.591	0.588	0.593	0.591	0.595	0.593	0.597	0.5860	0.5895	0.5870	0.5910	0.5886	0.5926	0.5902	0.5942
$\frac{11}{16}$–12	0.597	0.606	0.602	0.611	0.606	0.615	0.611	0.620	0.5970	0.6029	0.6001	0.6057	0.6029	0.6085	0.6057	0.6113
$\frac{11}{16}$–24	0.642	0.647	0.645	0.650	0.647	0.652	0.650	0.655	0.6420	0.6459	0.6436	0.6476	0.6454	0.6494	0.6471	0.6511
$\frac{3}{4}$–10	0.642	0.653	0.647	0.658	0.653	0.663	0.658	0.668	0.6420	0.6481	0.6449	0.6513	0.6481	0.6545	0.6513	0.6577
$\frac{3}{4}$–12	0.660	0.669	0.665	0.674	0.669	0.678	0.674	0.683	0.6600	0.6652	0.6626	0.6680	0.6653	0.6707	0.6680	0.6734
$\frac{3}{4}$–16	0.682	0.689	0.686	0.693	0.689	0.696	0.693	0.700	0.6820	0.6866	0.6844	0.6887	0.6865	0.6908	0.6886	0.6929
$\frac{3}{4}$–20	0.696	0.702	0.699	0.704	0.702	0.707	0.704	0.710	0.6960	0.6998	0.6977	0.7017	0.6997	0.7037	0.7016	0.7056
$\frac{3}{4}$–28	0.711	0.716	0.713	0.718	0.716	0.720	0.718	0.722	0.7110	0.7145	0.7120	0.7160	0.7136	0.7176	0.7152	0.7192
$\frac{13}{16}$–12	0.722	0.731	0.727	0.736	0.731	0.740	0.736	0.745	0.7220	0.7276	0.7250	0.7303	0.7276	0.7329	0.7303	0.7356

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Recommended Hole Size Limits Before Tapping Unified Threads**

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$13/16$–16	0.745	0.752	0.749	0.756	0.752	0.759	0.756	0.763	0.7450	0.7491	0.7469	0.7512	0.7490	0.7533	0.7511	0.7554
$13/16$–20	0.758	0.764	0.761	0.766	0.764	0.770	0.766	0.772	0.7580	0.7623	0.7602	0.7642	0.7622	0.7662	0.7641	0.7681
$7/8$–9	0.755	0.767	0.761	0.773	0.767	0.778	0.773	0.785	0.7550	0.7614	0.7580	0.7647	0.7614	0.7681	0.7647	0.7714
$7/8$–12	0.785	0.794	0.790	0.799	0.794	0.803	0.799	0.808	0.7850	0.7900	0.7874	0.7926	0.7900	0.7952	0.7926	0.7978
$7/8$–14	0.798	0.806	0.802	0.810	0.806	0.814	0.810	0.818	0.7980	0.8022	0.8000	0.8045	0.8023	0.8068	0.8045	0.8090
$7/8$–16	0.807	0.814	0.811	0.818	0.814	0.821	0.818	0.825	0.8070	0.8116	0.8094	0.8137	0.8115	0.8158	0.8136	0.8179
$7/8$–20	0.821	0.827	0.824	0.829	0.827	0.832	0.829	0.835	0.8210	0.8248	0.8227	0.8267	0.8247	0.8287	0.8266	0.8306
$7/8$–28	0.836	0.840	0.838	0.843	0.840	0.845	0.843	0.847	0.8360	0.8395	0.8370	0.8410	0.8386	0.8426	0.8402	0.8442
$15/16$–12	0.847	0.856	0.852	0.861	0.856	0.865	0.861	0.870	0.8470	0.8524	0.8499	0.8550	0.8524	0.8575	0.8550	0.8601
$15/16$–16	0.870	0.877	0.874	0.881	0.877	0.884	0.881	0.888	0.8700	0.8741	0.8719	0.8762	0.8740	0.8783	0.8761	0.8804
$15/16$–20	0.883	0.889	0.886	0.891	0.889	0.895	0.891	0.897	0.8830	0.8873	0.8852	0.8892	0.8872	0.8912	0.8891	0.8931
1–8	0.865	0.878	0.871	0.884	0.878	0.890	0.884	0.896	0.8650	0.8722	0.8684	0.8759	0.8722	0.8797	0.8760	0.8835
1–12	0.910	0.919	0.915	0.924	0.919	0.928	0.924	0.933	0.9100	0.9148	0.9123	0.9173	0.9148	0.9198	0.9173	0.9223
1–14	0.923	0.931	0.927	0.934	0.931	0.938	0.934	0.942	0.9230	0.9271	0.9249	0.9293	0.9271	0.9315	0.9293	0.9337
1–16	0.932	0.939	0.936	0.943	0.939	0.946	0.943	0.950	0.9320	0.9366	0.9344	0.9387	0.9365	0.9408	0.9386	0.9429
1–20	0.946	0.952	0.949	0.954	0.952	0.957	0.954	0.960	0.9460	0.9498	0.9477	0.9517	0.9497	0.9537	0.9516	0.9556
1–28	0.961	0.966	0.963	0.968	0.966	0.970	0.968	0.972	0.9610	0.9645	0.9620	0.9660	0.9636	0.9676	0.9652	0.9692
$1\frac{1}{16}$–12	0.972	0.981	0.977	0.986	0.981	0.990	0.986	0.995	0.9720	0.9773	0.9748	0.9798	0.9773	0.9823	0.9798	0.9848
$1\frac{1}{16}$–16	0.995	1.002	0.999	1.055	1.002	1.009	1.055	1.013	0.9950	0.9991	0.9969	1.0012	0.9990	1.0033	1.0011	1.0054
$1\frac{1}{16}$–18	1.002	1.009	1.005	1.012	1.009	1.015	1.012	1.018	1.0020	1.0065	1.0044	1.0085	1.0064	1.0105	1.0085	1.0126
$1\frac{1}{8}$–7	0.970	0.984	0.977	0.991	0.984	0.998	0.991	1.005	0.9700	0.9790	0.9747	0.9833	0.9789	0.9875	0.9832	0.9918
$1\frac{1}{8}$–8	0.990	1.003	0.996	1.009	1.003	1.015	1.009	1.021	0.9900	0.9972	0.9934	1.0009	0.9972	1.0047	1.0010	1.0085
$1\frac{1}{8}$–12	1.035	1.044	1.040	1.049	1.044	1.053	1.049	1.058	1.0350	1.0398	1.0373	1.0423	1.0398	1.0448	1.0423	1.0473
$1\frac{1}{8}$–16	1.057	1.064	1.061	1.068	1.064	1.071	1.068	1.075	1.0570	1.0616	1.0594	1.0637	1.0615	1.0658	1.0636	1.0679
$1\frac{1}{8}$–18	1.065	1.072	1.068	1.075	1.072	1.078	1.075	1.081	1.0650	1.0690	1.0669	1.0710	1.0689	1.0730	1.0710	1.0751
$1\frac{1}{8}$–20	1.071	1.077	1.074	1.079	1.077	1.082	1.079	1.085	1.0710	1.0748	1.0727	1.0767	1.0747	1.0787	1.0766	1.0806
$1\frac{1}{8}$–28	1.086	1.091	1.088	1.093	1.091	1.095	1.093	1.097	1.0860	1.0895	1.0870	1.0910	1.0886	1.0926	1.0902	1.0942
$1\frac{3}{16}$–12	1.097	1.106	1.102	1.111	1.106	1.115	1.111	1.120	1.0970	1.1023	1.0998	1.1048	1.1023	1.1073	1.1048	1.1098

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Recommended Hole Size Limits Before Tapping Unified Threads**

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$1\frac{3}{16}$–16	1.120	1.127	1.124	1.131	1.127	1.134	1.131	1.138	1.1200	1.1241	1.1219	1.1262	1.1240	1.1283	1.1261	1.1304
$1\frac{3}{16}$–18	1.127	1.134	1.130	1.137	1.134	1.140	1.137	1.143	1.1270	1.1315	1.1294	1.1335	1.1314	1.1355	1.1335	1.1376
$1\frac{1}{4}$–7	1.095	1.109	1.102	1.116	1.109	1.123	1.116	1.130	1.0950	1.1040	1.0997	1.1083	1.1039	1.1125	1.1082	1.1168
$1\frac{1}{4}$–8	1.115	1.128	1.121	1.134	1.128	1.140	1.134	1.146	1.1150	1.1222	1.1184	1.1259	1.1222	1.1297	1.1260	1.1335
$1\frac{1}{4}$–12	1.160	1.169	1.165	1.174	1.169	1.178	1.174	1.183	1.1600	1.1648	1.1623	1.1673	1.1648	1.1698	1.1673	1.1723
$1\frac{1}{4}$–16	1.182	1.189	1.186	1.193	1.189	1.196	1.193	1.200	1.1820	1.1866	1.1844	1.1887	1.1865	1.1908	1.1886	1.1929
$1\frac{1}{4}$–18	1.190	1.197	1.193	1.200	1.197	1.203	1.200	1.206	1.1900	1.1940	1.1919	1.1960	1.1939	1.1980	1.1960	1.2001
$1\frac{1}{4}$–20	1.196	1.202	1.199	1.204	1.202	1.207	1.204	1.210	1.1960	1.1998	1.1977	1.2017	1.1997	1.2037	1.2016	1.2056
$1\frac{5}{16}$–12	1.222	1.231	1.227	1.236	1.231	1.240	1.236	1.245	1.2220	1.2273	1.2248	1.2298	1.2273	1.2323	1.2298	1.2348
$1\frac{5}{16}$–16	1.245	1.252	1.249	1.256	1.252	1.259	1.256	1.263	1.2450	1.2491	1.2469	1.2512	1.2490	1.2533	1.2511	1.2554
$1\frac{5}{16}$–18	1.252	1.259	1.256	1.262	1.259	1.265	1.262	1.268	1.2520	1.2565	1.2544	1.2585	1.2564	1.2605	1.2585	1.2626
$1\frac{3}{8}$–6	1.195	1.210	1.203	1.221	1.210	1.225	1.221	1.239	1.1950	1.2046	1.1996	1.2096	1.2046	1.2146	1.2096	1.2196
$1\frac{3}{8}$–8	1.240	1.253	1.246	1.259	1.253	1.265	1.259	1.271	1.2400	1.2472	1.2434	1.2509	1.2472	1.2547	1.2510	1.2585
$1\frac{3}{8}$–12	1.285	1.294	1.290	1.299	1.294	1.303	1.299	1.308	1.2850	1.2898	1.2873	1.2923	1.2898	1.2948	1.2923	1.2973
$1\frac{3}{8}$–16	1.307	1.314	1.311	1.318	1.314	1.321	1.318	1.325	1.3070	1.3116	1.3094	1.3137	1.3115	1.3158	1.3136	1.3179
$1\frac{3}{8}$–18	1.315	1.322	1.318	1.325	1.322	1.328	1.325	1.331	1.3150	1.3190	1.3169	1.3210	1.3189	1.3230	1.3210	1.3251
$1\frac{7}{16}$–12	1.347	1.354	1.350	1.361	1.354	1.365	1.361	1.370	1.3470	1.3523	1.3498	1.3548	1.3523	1.3573	1.3548	1.3598
$1\frac{7}{16}$–16	1.370	1.377	1.374	1.381	1.377	1.384	1.381	1.388	1.3700	1.3741	1.3719	1.3762	1.3740	1.3783	1.3761	1.3804
$1\frac{7}{16}$–18	1.377	1.384	1.380	1.387	1.384	1.390	1.387	1.393	1.3770	1.3815	1.3794	1.3835	1.3814	1.3855	1.3835	1.3876
$1\frac{1}{2}$–6	1.320	1.335	1.328	1.346	1.335	1.350	1.346	1.364	1.3200	1.3296	1.3246	1.3346	1.3296	1.3396	1.3346	1.3446
$1\frac{1}{2}$–8	1.365	1.378	1.371	1.384	1.378	1.390	1.384	1.396	1.3650	1.3722	1.3684	1.3759	1.3722	1.3797	1.3760	1.3835
$1\frac{1}{2}$–12	1.410	1.419	1.4155	1.424	1.419	1.428	1.424	1.433	1.4100	1.4148	1.4123	1.4173	1.4148	1.4198	1.4173	1.4223
$1\frac{1}{2}$–16	1.432	1.439	1.436	1.443	1.439	1.446	1.443	1.450	1.4320	1.4366	1.4344	1.4387	1.4365	1.4408	1.4386	1.4429
$1\frac{1}{2}$–18	1.440	1.446	1.443	1.450	1.446	1.452	1.450	1.456	1.4400	1.4440	1.4419	1.4460	1.4439	1.4480	1.4460	1.4501
$1\frac{1}{2}$–20	1.446	1.452	1.449	1.454	1.452	1.457	1.454	1.460	1.4460	1.4498	1.4477	1.4517	1.4497	1.4537	1.4516	1.4556
$1\frac{9}{16}$–16	1.495	1.502	1.499	1.506	1.502	1.509	1.506	1.513	1.4950	1.4991	1.4969	1.5012	1.4990	1.5033	1.5011	1.5054
$1\frac{9}{16}$–18	1.502	1.509	1.505	1.512	1.509	1.515	1.512	1.518	1.5020	1.5065	1.5044	1.5085	1.5064	1.5105	1.5085	1.5126

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Recommended Hole Size Limits Before Tapping Unified Threads**

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$1\frac{5}{8}$–8	1.490	1.498	1.494	1.509	1.498	1.515	1.509	1.521	1.4900	1.4972	1.4934	1.5009	1.4972	1.5047	1.5010	1.5085
$1\frac{5}{8}$–12	1.535	1.544	1.540	1.549	1.544	1.553	1.549	1.558	1.5350	1.5398	1.5373	1.5423	1.5398	1.5448	1.5423	1.5473
$1\frac{5}{8}$–16	1.557	1.564	1.561	1.568	1.564	1.571	1.568	1.575	1.5570	1.5616	1.5594	1.5637	1.5615	1.5658	1.5636	1.5679
$1\frac{5}{8}$–18	1.565	1.572	1.568	1.575	1.572	1.578	1.575	1.581	1.5650	1.5690	1.5669	1.5710	1.5689	1.5730	1.5710	1.5751
$1\frac{11}{16}$–16	1.620	1.627	1.624	1.631	1.627	1.634	1.631	1.638	1.6200	1.6241	1.6219	1.6262	1.6240	1.6283	1.6261	1.6304
$1\frac{11}{16}$–18	1.627	1.634	1.630	1.637	1.634	1.640	1.637	1.643	1.6270	1.6315	1.6294	1.6335	1.6314	1.6355	1.6335	1.6376
$1\frac{3}{4}$–5	1.534	1.551	1.543	1.560	1.551	1.568	1.560	1.577	1.5340	1.5455	1.5395	1.5515	1.5455	1.5575	1.5515	1.5635
$1\frac{3}{4}$–8	1.615	1.628	1.621	1.634	1.628	1.640	1.634	1.646	1.6150	1.6222	1.6184	1.6259	1.6222	1.6297	1.6260	1.6335
$1\frac{3}{4}$–12	1.660	1.669	1.665	1.674	1.669	1.678	1.674	1.683	1.6600	1.6648	1.6623	1.6673	1.6648	1.6698	1.6673	1.6723
$1\frac{3}{4}$–16	1.682	1.689	1.686	1.693	1.689	1.696	1.693	1.700	1.6820	1.6866	1.6844	1.6887	1.6865	1.6908	1.6886	1.6929
$1\frac{3}{4}$–20	1.696	1.702	1.699	1.704	1.702	1.707	1.704	1.710	1.6960	1.6998	1.6977	1.7017	1.6997	1.7037	1.7016	1.7056
$1\frac{13}{16}$–16	1.745	1.752	1.749	1.756	1.752	1.759	1.756	1.763	1.7450	1.7491	1.7469	1.7512	1.7490	1.7533	1.7511	1.7554
$1\frac{7}{8}$–8	1.740	1.752	1.746	1.759	1.752	1.765	1.759	1.771	1.7400	1.7472	1.7434	1.7509	1.7472	1.7547	1.7510	1.7585
$1\frac{7}{8}$–12	1.785	1.794	1.790	1.799	1.794	1.803	1.799	1.808	1.7850	1.7898	1.7873	1.7923	1.7898	1.7948	1.7923	1.7973
$1\frac{7}{8}$–16	1.807	1.814	1.810	1.818	1.814	1.821	1.818	1.825	1.8070	1.8116	1.8094	1.8137	1.8115	1.8158	1.8136	1.8179
$1\frac{15}{16}$–16	1.870	1.877	1.874	1.881	1.877	1.884	1.881	1.888	1.8700	1.8741	1.8719	1.8762	1.8740	1.8783	1.8761	1.8804
2–$4\frac{1}{2}$	1.759	1.777	1.768	1.786	1.777	1.795	1.786	1.804	1.7590	1.7727	1.7661	1.7794	1.7728	1.7861	1.7794	1.7927
2–8	1.865	1.878	1.871	1.884	1.878	1.890	1.884	1.896	1.8650	1.8722	1.8684	1.8759	1.8722	1.8797	1.8760	1.8835
2–12	1.910	1.919	1.915	1.924	1.919	1.928	1.924	1.933	1.9100	1.9148	1.9123	1.9173	1.9148	1.9198	1.9173	1.9223
2–16	1.932	1.939	1.936	1.943	1.939	1.946	1.943	1.950	1.9320	1.9366	1.9344	1.9387	1.9365	1.9408	1.9386	1.9429
2–20	1.946	1.952	1.949	1.954	1.952	1.957	1.954	1.960	1.9460	1.9498	1.9477	1.9517	1.9497	1.9537	1.9516	1.9556
$2\frac{1}{16}$–16	1.995	2.002	2.000	2.006	2.002	2.009	2.006	2.012	1.9950	1.9991	1.9969	2.0012	1.9990	2.0033	2.0011	2.0054
$2\frac{1}{8}$–8	1.990	2.003	1.996	2.009	2.003	2.015	2.009	2.021	1.9900	1.9972	1.9934	2.0009	1.9972	2.0047	2.0010	2.0085
$2\frac{1}{8}$–12	2.035	2.044	2.040	2.049	2.044	2.053	2.049	2.058	2.0350	2.0398	2.0373	2.0423	2.0398	2.0448	2.0423	2.0473
$2\frac{1}{8}$–16	2.057	2.064	2.061	2.068	2.064	2.071	2.068	2.075	2.0570	2.0616	2.0594	2.0637	2.0615	2.0658	2.0636	2.0679
$2\frac{3}{16}$–16	2.120	2.127	2.124	2.131	2.127	2.134	2.131	2.138	2.1200	2.1241	2.1219	2.1262	2.1240	2.1283	2.1261	2.1304
$2\frac{1}{4}$–$4\frac{1}{2}$	2.009	2.027	2.018	2.036	2.027	2.045	2.036	2.054	2.0090	2.0227	2.0161	2.0294	2.0228	2.0361	2.0294	2.0427

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Recommended Hole Size Limits Before Tapping Unified Threads**

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$2\frac{1}{4}$–8	2.115	2.128	2.121	2.134	2.128	2.140	2.134	2.146	2.1150	2.1222	2.1184	2.1259	2.1222	2.1297	2.1260	2.1335
$2\frac{1}{4}$–12	2.160	2.169	2.165	2.174	2.169	2.178	2.174	2.182	2.1600	2.1648	2.1623	2.1673	2.1648	2.1698	2.1673	2.1723
$2\frac{1}{4}$–16	2.182	2.189	2.186	2.193	2.189	2.196	2.193	2.200	2.1820	2.1866	2.1844	2.1887	2.1865	2.1908	2.1886	2.1929
$2\frac{1}{4}$–20	2.196	2.202	2.199	2.204	2.202	2.207	2.204	2.210	2.1960	2.1998	2.1977	2.2017	2.1997	2.2037	2.2016	2.2056
$2\frac{5}{16}$–16	2.245	2.252	2.249	2.256	2.252	2.259	2.256	2.263	2.2450	2.2491	2.2469	2.2512	2.2490	2.2533	2.2511	2.2554
$2\frac{3}{8}$–12	2.285	2.294	2.290	2.299	2.294	2.303	2.299	2.308	2.2850	2.2898	2.2873	2.2923	2.2898	2.2948	2.2923	2.2973
$2\frac{3}{8}$–16	2.307	2.314	2.311	2.318	2.314	2.321	2.318	2.325	2.3070	2.3116	2.3094	2.3137	2.3115	2.3158	2.3136	2.3179
$2\frac{7}{16}$–16	2.370	2.377	2.374	2.381	2.377	2.384	2.381	2.388	2.3700	2.3741	2.3719	2.3762	2.3740	2.3783	2.3761	2.3804
$2\frac{1}{2}$–4	2.229	2.248	2.238	2.258	2.248	2.267	2.258	2.277	2.2290	2.2444	2.2369	2.2519	2.2444	2.2594	2.2519	2.2669
$2\frac{1}{2}$–8	2.365	2.378	2.371	2.384	2.378	2.390	2.384	2.396	2.3650	2.3722	2.3684	2.3759	2.3722	2.3797	2.3760	2.3835
$2\frac{1}{2}$–12	2.410	2.419	2.415	2.424	2.419	2.428	2.424	2.433	2.4100	2.4148	2.4123	2.4173	2.4148	2.4198	2.4173	2.4223
$2\frac{1}{2}$–16	2.432	2.439	2.436	2.443	2.439	2.446	2.443	2.450	2.4320	2.4366	2.4344	2.4387	2.4365	2.4408	2.4386	2.4429
$2\frac{1}{2}$–20	2.446	2.452	2.449	2.454	2.452	2.457	2.454	2.460	2.4460	2.4498	2.4478	2.4517	2.4497	2.4537	2.4516	2.4556
$2\frac{5}{8}$–12	2.535	2.544	2.540	2.549	2.544	2.553	2.549	2.558	2.5350	2.5398	2.5373	2.5423	2.5398	2.5448	2.5423	2.5473
$2\frac{5}{8}$–16	2.557	2.564	2.561	2.568	2.564	2.571	2.568	2.575	2.5570	2.5616	2.5594	2.5637	2.5615	2.5658	2.5636	2.5679
$2\frac{3}{4}$–4	2.479	2.498	2.489	2.508	2.498	2.517	2.508	2.527	2.4790	2.4944	2.4869	2.5019	2.4944	2.5094	2.5019	2.5169
$2\frac{3}{4}$–8	2.615	2.628	2.621	2.634	2.628	2.640	2.634	2.644	2.6150	2.6222	2.6184	2.6259	2.6222	2.6297	2.6260	2.6335
$2\frac{3}{4}$–12	2.660	2.669	2.665	2.674	2.669	2.678	2.674	2.683	2.6600	2.6648	2.6623	2.6673	2.6648	2.6698	2.6673	2.6723
$2\frac{3}{4}$–16	2.682	2.689	2.686	2.693	2.689	2.696	2.693	2.700	2.6820	2.6866	2.6844	2.6887	2.6865	2.6908	2.6886	2.6929
$2\frac{7}{8}$–12	2.785	2.794	2.790	2.809	2.794	2.803	2.809	2.808	2.7850	2.7898	2.7873	2.7923	2.7898	2.7948	2.7923	2.7973
$2\frac{7}{8}$–16	2.807	2.814	2.811	2.818	2.814	2.821	2.818	2.825	2.8070	2.8116	2.8094	2.8137	2.8115	2.8158	2.8136	2.8179
3–4	2.729	2.748	2.739	2.758	2.748	2.767	2.758	2.777	2.7290	2.7444	2.7369	2.7519	2.7444	2.7594	2.7519	2.7669
3–8	2.865	2.878	2.871	2.884	2.878	2.890	2.884	2.896	2.8650	2.8722	2.8684	2.8759	2.8722	2.8797	2.8760	2.8835
3–12	2.910	2.919	2.915	2.924	2.919	2.928	2.924	2.933	2.9100	2.9148	2.9123	2.9173	2.9148	2.9198	2.9173	2.9223
3–16	2.932	2.939	2.936	2.943	2.939	2.946	2.943	2.950	2.9320	2.9366	2.9344	2.9387	2.9365	2.9408	2.9386	2.9429
$3\frac{1}{8}$–12	3.035	3.044	3.040	3.049	3.044	3.053	3.049	3.058	3.0350	3.0398	3.0373	3.0423	3.0398	3.0448	3.0423	3.0473
$3\frac{1}{8}$–16	3.057	3.064	3.061	3.068	3.064	3.071	3.068	3.075	3.0570	3.0616	3.0594	3.0637	3.0615	3.0658	3.0636	3.0679

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. *(Continued)* Recommended Hole Size Limits Before Tapping Unified Threads

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$3\frac{1}{4}$–4	2.979	2.998	2.989	3.008	2.998	3.017	3.008	3.027	2.9790	2.9944	2.9869	3.0019	2.9944	3.0094	3.0019	3.0169
$3\frac{1}{4}$–8	3.115	3.128	3.121	3.134	3.128	3.140	3.134	3.146	3.1150	3.1222	3.1184	3.1259	3.1222	3.1297	3.1260	3.1335
$3\frac{1}{4}$–12	3.160	3.169	3.165	3.174	3.169	3.178	3.174	3.183	3.1600	3.1648	3.1623	3.1673	3.1648	3.1698	3.1673	3.1723
$3\frac{1}{4}$–16	3.182	3.189	3.186	3.193	3.189	3.196	3.193	3.200	3.1820	3.1866	3.1844	3.1887	3.1865	3.1908	3.1886	3.1929
$3\frac{3}{8}$–12	3.285	3.294	3.290	3.299	3.294	3.303	3.299	3.299	3.2850	3.2898	3.2873	3.2923	3.2898	3.2948	3.2923	3.2973
$3\frac{3}{8}$–16	3.307	3.314	3.311	3.318	3.314	3.321	3.317	3.325	3.3070	3.3116	3.3094	3.3137	3.3115	3.3158	3.3136	3.3179
$3\frac{1}{2}$–4	3.229	3.248	3.239	3.258	3.248	3.267	3.258	3.277	3.2290	3.2444	3.2369	3.2519	3.2444	3.2594	3.2519	3.2669
$3\frac{1}{2}$–8	3.365	3.378	3.371	2.384	3.378	3.390	3.384	3.396	3.3650	3.3722	3.3684	3.3759	3.3722	3.3797	3.3760	3.3835
$3\frac{1}{2}$–12	3.410	3.419	3.415	3.424	3.419	3.428	3.424	3.433	3.4100	3.4148	3.4123	3.4173	3.4148	3.4198	3.4173	3.4223
$3\frac{1}{2}$–16	3.432	3.439	3.436	3.443	3.439	3.446	3.443	3.450	3.4320	3.4366	3.4344	3.4387	3.4365	3.4408	3.4386	3.4429
$3\frac{5}{8}$–12	3.535	3.544	3.544	3.549	3.544	3.553	3.549	3.553	3.5350	3.5398	3.5373	3.5423	3.5398	3.5448	3.5423	3.5473
$3\frac{5}{8}$–16	3.557	3.564	3.561	3.568	3.567	3.571	3.568	3.575	3.5570	3.5616	3.5594	3.5637	3.5615	3.5658	3.5636	3.5679
$3\frac{3}{4}$–4	3.479	3.498	3.489	3.508	3.498	3.517	3.508	3.527	3.4790	3.4944	3.4869	3.5019	3.4944	3.5094	3.5019	3.5169
$3\frac{3}{4}$–8	3.615	3.628	3.615	3.634	3.628	3.640	3.634	3.646	3.6150	3.6222	3.6184	3.6259	3.6222	3.6297	3.6260	3.6335
$3\frac{3}{4}$–12	3.660	3.669	3.665	3.674	3.669	3.678	3.674	3.683	3.6600	3.6648	3.6623	3.6673	3.6648	3.6698	3.6673	3.6723
$3\frac{3}{4}$–16	3.682	3.689	3.686	3.693	3.689	3.696	3.693	3.700	3.6820	3.6866	3.6844	3.6887	3.6865	3.6908	3.6886	3.6929
$3\frac{7}{8}$–12	3.785	3.794	3.790	3.799	3.794	3.803	3.799	3.808	3.7850	3.7898	3.7873	3.7923	3.7898	3.7948	3.7923	3.7973
$3\frac{7}{8}$–16	3.807	3.814	3.811	3.818	3.814	3.821	3.818	3.825	3.8070	3.8116	3.8094	3.8137	3.8115	3.8158	3.8136	3.8179
4–4	3.729	3.748	3.739	3.758	3.748	3.767	3.758	3.777	3.7290	3.7444	3.7369	3.7519	3.7444	3.7594	3.7519	3.7669
4–8	3.865	3.878	3.871	3.884	3.878	3.890	3.884	3.896	3.8650	3.8722	3.8684	3.8759	3.8722	3.8797	3.8760	3.8835
4–12	3.910	3.919	3.915	3.924	3.919	3.928	3.924	3.933	3.9100	3.9148	3.9123	3.9173	3.9148	3.9198	3.9173	3.9223
4–16	3.932	3.939	3.936	3.943	3.939	3.946	3.943	3.950	3.9320	3.9366	3.9344	3.9387	3.9365	3.9408	3.9386	3.9429
$4\frac{1}{4}$–4	3.979	3.998	3.989	4.008	3.998	4.017	4.008	4.027	3.9790	3.9944	3.9869	4.0019	3.9944	4.0094	4.0019	4.0169
$4\frac{1}{4}$–8	4.115	4.128	4.121	4.134	4.128	4.140	4.134	4.146	4.1150	4.1222	4.1184	4.1259	4.1222	4.1297	4.1260	4.1335
$4\frac{1}{4}$–12	4.160	4.169	4.165	4.174	4.169	4.178	4.174	4.183	4.1600	4.1648	4.1623	4.1673	4.1648	4.1698	4.1673	4.1723
$4\frac{1}{4}$–16	4.182	4.189	4.186	4.193	4.189	4.196	4.193	4.200	4.1820	4.1866	4.1844	4.1887	4.1865	4.1908	4.1886	4.1929
$4\frac{1}{2}$–4	4.229	4.248	4.239	4.258	4.248	4.267	4.258	4.277	4.2290	4.2444	4.2369	4.2519	4.2444	4.2594	4.2519	4.2669

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. *(Continued)* Recommended Hole Size Limits Before Tapping Unified Threads

Thread Size	Classes 1B and 2B								Class 3B							
	Length of Engagement (D = Nominal Size of Thread)															
	To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$		To and Including $\frac{1}{3}D$		Above $\frac{1}{3}D$ to $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
	Recommended Hole Size Limits															
	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max	Min[a]	Max	Min	Max	Min	Max[b]	Min	Max
$4\frac{1}{2}$–8	4.365	4.378	4.371	4.384	4.378	4.390	4.384	4.396	4.3650	4.3722	4.3684	4.3759	4.3722	4.3797	4.3760	4.3835
$4\frac{1}{2}$–12	4.410	4.419	4.419	4.424	4.419	4.428	4.424	4.433	4.4100	4.4148	4.4123	4.4173	4.4148	4.4198	4.4173	4.4223
$4\frac{1}{2}$–16	4.432	4.439	4.437	4.444	4.439	4.446	4.444	4.455	4.4320	4.4366	4.4344	4.4387	4.4365	4.4408	4.4386	4.4429
$4\frac{3}{4}$–8	4.615	4.628	4.621	4.646	4.628	4.640	4.646	4.646	4.6150	4.6222	4.6184	4.6259	4.6222	4.6297	4.6260	4.6335
$4\frac{3}{4}$–12	4.660	4.669	4.665	4.674	4.669	4.678	4.674	4.683	4.6600	4.6648	4.6623	4.6673	4.6648	4.6698	4.6673	4.6723
$4\frac{3}{4}$–16	4.682	4.689	4.686	4.693	4.689	4.696	4.693	4.700	4.6820	4.6866	4.6844	4.6887	4.6865	4.6908	4.6886	4.6929
5–8	4.865	4.878	4.871	4.884	4.878	4.890	4.884	4.896	4.8650	4.8722	4.8684	4.8759	4.8722	4.8797	4.8760	4.8835
5–12	4.910	4.919	4.915	4.924	4.919	4.928	4.924	4.933	4.9100	4.9148	4.9123	4.9173	4.9148	4.9198	4.9173	4.9223
5–16	4.932	4.939	4.936	4.943	4.939	4.946	4.943	4.950	4.9320	4.9366	4.9344	4.9387	4.9365	4.9408	4.9386	4.9429
$5\frac{1}{4}$–8	5.115	5.128	5.121	5.134	5.128	5.140	5.134	5.146	5.1150	5.1222	5.1184	5.1259	5.1222	5.1297	5.1260	5.1335
$5\frac{1}{4}$–12	5.160	5.169	5.165	5.174	5.169	5.178	5.174	5.183	5.1600	5.1648	5.1623	5.1673	5.1648	5.1698	5.1673	5.1723
$5\frac{1}{4}$–16	5.182	5.189	5.186	5.193	5.189	5.196	5.193	5.200	5.1820	5.1866	5.1844	5.1887	5.1865	5.1908	5.1886	5.1929
$5\frac{1}{2}$–8	5.365	5.378	5.371	5.384	5.378	5.390	5.384	5.396	5.3650	5.3722	5.3684	5.3759	5.3722	5.3797	5.3760	5.3835
$5\frac{1}{2}$–12	5.410	5.419	5.415	5.424	5.419	5.428	5.424	5.433	5.4100	5.4148	5.4123	5.4173	5.4148	5.4198	5.4173	5.4223
$5\frac{1}{2}$–16	5.432	5.439	5.436	5.442	5.439	5.446	5.442	5.450	5.4320	5.4366	5.4344	5.4387	5.4365	5.4408	5.4386	5.4429
$5\frac{3}{4}$–8	5.615	5.628	5.621	5.634	5.628	5.640	5.634	5.646	5.6150	5.6222	5.6184	5.6259	5.6222	5.6297	5.6260	5.6335
$5\frac{3}{4}$–12	5.660	5.669	5.665	5.674	5.669	5.678	5.674	5.683	5.6600	5.6648	5.6623	5.6673	5.6648	5.6698	5.6673	5.6723
$5\frac{3}{4}$–16	5.682	5.689	5.686	5.693	5.689	5.696	5.693	5.700	5.6820	5.6866	5.6844	5.6887	5.6865	5.6908	5.6886	5.6929
6–8	5.865	5.878	5.871	5.896	5.878	5.890	5.896	5.896	5.8650	5.8722	5.8684	5.8759	5.8722	5.8797	5.8760	5.8835
6–12	5.910	5.919	5.915	5.924	5.919	5.928	5.924	5.933	5.9100	5.9148	5.9123	5.9173	5.9148	5.9198	5.9173	5.9223
6–16	5.932	5.939	5.935	5.943	5.939	5.946	5.943	5.950	5.9320	5.9366	5.9344	5.9387	5.9365	5.9408	5.9386	5.9429

[a] This is the minimum minor diameter specified in the thread tables, page 1736.

[b] This is the maximum minor diameter specified in the thread tables, page 1736.

All dimensions are in inches.

For basis of recommended hole size limits see accompanying text.

As an aid in selecting suitable drills, see the listing of American Standard drill sizes in the twist drill section. For amount of expected drill oversize, see page 885.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Tap Drill Sizes for Threads of American National Form

Screw Thread		Commercial Tap Drills[a]		Screw Thread		Commercial Tap Drills[a]	
Outside Diam. Pitch	Root Diam.	Size or Number	Decimal Equiv.	Outside Diam. Pitch	Root Diam.	Size or Number	Decimal Equiv.
1/16–64	0.0422	3/64	0.0469	27	0.4519	15/32	0.4687
72	0.0445	3/64	0.0469	9/16–12	0.4542	31/64	0.4844
5/64–60	0.0563	1/16	0.0625	18	0.4903	33/64	0.5156
72	0.0601	52	0.0635	27	0.5144	17/32	0.5312
3/32–48	0.0667	49	0.0730	5/8–11	0.5069	17/32	0.5312
50	0.0678	49	0.0730	12	0.5168	35/64	0.5469
7/64–48	0.0823	43	0.0890	18	0.5528	37/64	0.5781
1/8–32	0.0844	3/32	0.0937	27	0.5769	19/32	0.5937
40	0.0925	38	0.1015	11/16–11	0.5694	19/32	0.5937
9/64–40	0.1081	32	0.1160	16	0.6063	5/8	0.6250
5/32–32	0.1157	1/8	0.1250	3/4–10	0.6201	21/32	0.6562
36	0.1202	30	0.1285	12	0.6418	43/64	0.6719
11/64–32	0.1313	9/64	0.1406	16	0.6688	11/16	0.6875
3/16–24	0.1334	26	0.1470	27	0.7019	23/32	0.7187
32	0.1469	22	0.1570	13/16–10	0.6826	23/32	0.7187
13/64–24	0.1490	20	0.1610	7/8–9	0.7307	49/64	0.7656
7/32–24	0.1646	16	0.1770	12	0.7668	51/64	0.7969
32	0.1782	12	0.1890	14	0.7822	13/16	0.8125
15/64–24	0.1806	10	0.1935	18	0.8028	53/64	0.8281
1/4–20	0.1850	7	0.2010	27	0.8269	27/32	0.8437
24	0.1959	4	0.2090	15/16–9	0.7932	53/64	0.8281
27	0.2019	3	0.2130	1 – 8	0.8376	7/8	0.8750
28	0.2036	3	0.2130	12	0.8918	59/64	0.9219
32	0.2094	7/32	0.2187	14	0.9072	15/16	0.9375
5/16–18	0.2403	F	0.2570	27	0.9519	31/32	0.9687
20	0.2476	17/64	0.2656	1 1/8– 7	0.9394	63/64	0.9844
24	0.2584	I	0.2720	12	1.0168	1 3/64	1.0469
27	0.2644	J	0.2770	1 1/4– 7	1.0644	1 7/64	1.1094
32	0.2719	9/32	0.2812	12	1.1418	1 11/64	1.1719
3/8–16	0.2938	5/16	0.3125	1 3/8– 6	1.1585	1 7/32	1.2187
20	0.3100	21/64	0.3281	12	1.2668	1 19/64	1.2969
24	0.3209	Q	0.3320	1 1/2– 6	1.2835	1 11/32	1.3437
27	0.3269	R	0.3390	12	1.3918	1 27/64	1.4219
7/16–14	0.3447	U	0.3680	1 5/8– 5 1/2	1.3888	1 29/64	1.4531
20	0.3726	25/64	0.3906	1 3/4– 5	1.4902	1 9/16	1.5625
24	0.3834	X	0.3970	1 7/8– 5	1.6152	1 11/16	1.6875
27	0.3894	Y	0.4040	2 – 4 1/2	1.7113	1 25/32	1.7812
1/2–12	0.3918	27/64	0.4219	2 1/4– 4 1/2	1.8363	1 29/32	1.9062
13	0.4001	27/64	0.4219	2 1/4– 4 1/2	1.9613	2 1/32	2.0312
20	0.4351	29/64	0.4531	2 3/8– 4	2.0502	2 1/8	2.1250
24	0.4459	29/64	0.4531	2 1/2– 4	2.1752	2 1/4	2.2500

[a] These tap drill diameters allow approximately 75 per cent of a full thread to be produced. For small thread sizes in the first column, the use of drills to produce the larger hole sizes shown in Table 2 will reduce defects caused by tap problems and breakage.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Tap Drills and Clearance Drills for Machine Screws with American National Thread Form

Size of Screw		No. of Threads per Inch	Tap Drills		Clearance Hole Drills			
					Close Fit		Free Fit	
No. or Diam.	Decimal Equiv.		Drill Size	Decimal Equiv.	Drill Size	Decimal Equiv.	Drill Size	Decimal Equiv.
0	.060	80	3/64	.0469	52	.0635	50	.0700
1	.073	64 72	53 53	.0595 .0595	48	.0760	46	.0810
2	.086	56 64	50 50	.0700 .0700	43	.0890	41	.0960
3	.099	48 56	47 45	.0785 .0820	37	.1040	35	.1100
4	.112	36[a] 40 48	44 43 42	.0860 .0890 .0935	32	.1160	30	.1285
5	.125	40 44	38 37	.1015 1040	30	.1285	29	.1360
6	.138	32 40	36 33	.1065 .1130	27	.1440	25	.1495
8	.164	32 36	29 29	.1360 .1360	18	.1695	16	.1770
10	.190	24 32	25 21	.1495 1590	9	.1960	7	.2010
12	.216	24 28	16 14	.1770 .1820	2	.2210	1	.2280
14	.242	20[a] 24[a]	10 7	.1935 .2010	D	.2460	F	.2570
1/4	.250	20 28	7 3	.2010 .2130	F	.2570	H	.2660
5/16	.3125	18 24	F I	.2570 .2720	P	.3230	Q	.3320
3/8	.375	16 24	5/16 Q	.3125 .3320	W	.3860	X	.3970
7/16	.4375	14 20	U 25/64	.3680 .3906	29/64	.4531	15/32	.4687
1/2	.500	13 20	27/64 29/64	.4219 .4531	33/64	.5156	17/32	.5312

[a] These screws are not in the American Standard but are from the former A.S.M.E. Standard.

The size of the tap drill hole for any desired percentage of full thread depth can be calculated by the formulas below. In these formulas the Per Cent Full Thread is expressed as a decimal; e.g., 75 per cent is expressed as .75. The tap drill size is the size nearest to the calculated hole size.

For American Unified Thread form:

$$\text{Hole Size} = \text{Basic Major Diameter} - \frac{1.08253 \times \text{Per Cent Full Thread}}{\text{Number of Threads per Inch}}$$

For ISO Metric threads (all dimensions in millimeters):

$$\text{Hole Size} = \text{Basic Major Diameter} - (1.08253 \times \text{Pitch} \times \text{Per Cent Full Thread})$$

The constant 1.08253 in the above equation represents $5H/8$ where H is the height of a sharp V-thread (see page 1725). (The pitch is taken to be 1.)

Factors Influencing Minor Diameter Tolerances of Tapped Holes.— As stated in the Unified screw thread standard, the principle practical factors that govern minor diameter tolerances of internal threads are tapping difficulties, particularly tap breakage in the small sizes, availability of standard drill sizes in the medium and large sizes, and depth (radial) of engagement. Depth of engagement is related to the stripping strength of the thread assembly, and thus also, to the length of engagement. It also has an influence on the tendency toward disengagement of the threads on one side when assembly is eccentric. The amount of possible eccentricity is one-half of the sum of the pitch diameter allowance and toler-

Copyright 2004, Industrial Press, Inc., New York, NY

ances on both mating threads. For a given pitch, or height of thread, this sum increases with the diameter, and accordingly this factor would require a decrease in minor diameter tolerance with increase in diameter. However, such decrease in tolerance would often require the use of special drill sizes; therefore, to facilitate the use of standard drill sizes, for any given pitch the minor diameter tolerance for Unified thread classes 1B and 2B threads of ¼ inch diameter and larger is constant, in accordance with a formula given in the American Standard for Unified Screw Threads.

Effect of Length of Engagement of Minor Diameter Tolerances: There may be applications where the lengths of engagement of mating threads is relatively short or the combination of materials used for mating threads is such that the maximum minor diameter tolerance given in the Standard (based on a length of engagement equal to the nominal diameter) may not provide the desired strength of the fastening. Experience has shown that for lengths of engagement less than $\frac{2}{3}D$ (the minimum thickness of standard nuts) the minor diameter tolerance may be reduced without causing tapping difficulties. In other applications the length of engagement of mating threads may be long because of design considerations or the combination of materials used for mating threads. As the threads engaged increase in number, a shallower depth of engagement may be permitted and still develop stripping strength greater than the external thread breaking strength. Under these conditions the maximum tolerance given in the Standard should be increased to reduce the possibility of tapping difficulties. The following paragraphs indicate how the aforementioned considerations were taken into account in determining the minor diameter limits for various lengths of engagement given in Table 2.

Recommended Hole Sizes before Tapping.— Recommended hole size limits before threading to provide for optimum strength of fastenings and tapping conditions are shown in Table 2 for classes 1B, 2B, and 3B. The hole size limit before threading, and the tolerances between them, are derived from the minimum and maximum minor diameters of the internal thread given in the dimensional tables for Unified threads in the screw thread section using the following rules:

1) For lengths of engagement in the range to and including $\frac{1}{3}D$, where D equals nominal diameter, the minimum hole size will be equal to the minimum minor diameter of the internal thread and the maximum hole size will be larger by one-half the minor diameter tolerance.

2) For the range from $\frac{1}{3}D$ to $\frac{2}{3}D$, the minimum and maximum hole sizes will each be one quarter of the minor diameter tolerance larger than the corresponding limits for the length of engagement to and including $\frac{1}{3}D$.

3) For the range from $\frac{2}{3}D$ to $1\frac{1}{2}D$ the minimum hole size will be larger than the minimum minor diameter of the internal thread by one-half the minor diameter tolerance and the maximum hole size will be equal to the maximum minor diameter.

4) For the range from $1\frac{1}{2}D$ to $3D$ the minimum and maximum hole sizes will each be one-quarter of the minor diameter tolerance of the internal thread larger than the corresponding limits for the $\frac{2}{3}D$ to $1\frac{1}{2}D$ length of engagement.

From the foregoing it will be seen that the difference between limits in each range is the same and equal to one-half of the minor diameter tolerance given in the Unified screw thread dimensional tables. This is a general rule, except that the minimum differences for sizes below ¼ inch are equal to the minor diameter tolerances calculated on the basis of lengths of engagement to and including $\frac{1}{3}D$. Also, for lengths of engagement greater than $\frac{1}{3}D$ and for sizes ¼ inch and larger the values are adjusted so that the difference between limits is never less than 0.004 inch.

For diameter-pitch combinations other than those given in Table 2, the foregoing rules should be applied to the tolerances given in the dimensional tables in the screw thread sec-

Copyright 2004, Industrial Press, Inc., New York, NY

tion or the tolerances derived from the formulas given in the Standard to determine the hole size limits.

Selection of Tap Drills: In selecting standard drills to produce holes within the limits given in Table 2 it should be recognized that drills have a tendency to cut oversize. The material on page 885 may be used as a guide to the expected amount of oversize.

Table 5. Unified Miniature Screw Threads—Recommended Hole Size Limits Before Tapping

Thread Size		Internal Threads		Lengths of Engagement					
		Minor Diameter Limits		To and including $\frac{2}{3}D$		Above $\frac{2}{3}D$ to $1\frac{1}{2}D$		Above $1\frac{1}{2}D$ to $3D$	
				Recommended Hole Size Limits					
	Pitch	Min	Max	Min	Max	Min	Max	Min	Max
Designation	mm	mm	mm	mm	mm	mm	mm	mm	mm
0.30 UNM	**0.080**	**0.217**	**0.254**	**0.226**	**0.240**	**0.236**	**0.254**	**0.245**	**0.264**
0.35 UNM	0.090	0.256	0.297	0.267	0.282	0.277	0.297	0.287	0.307
0.40 UNM	**0.100**	**0.296**	**0.340**	**0.307**	**0.324**	**0.318**	**0.340**	**0.329**	**0.351**
0.45 UNM	0.100	0.346	0.390	0.357	0.374	0.368	0.390	0.379	0.401
0.50 UNM	**0.125**	**0.370**	**0.422**	**0.383**	**0.402**	**0.396**	**0.422**	**0.409**	**0.435**
0.55 UNM	0.125	0.420	0.472	0.433	0.452	0.446	0.472	0.459	0.485
0.60 UNM	**0.150**	**0.444**	**0.504**	**0.459**	**0.482**	**0.474**	**0.504**	**0.489**	**0.519**
0.70 UNM	0.175	0.518	0.586	0.535	0.560	0.552	0.586	0.569	0.603
0.80 UNM	**0.200**	**0.592**	**0.668**	**0.611**	**0.640**	**0.630**	**0.668**	**0.649**	**0.687**
0.90 UNM	0.225	0.666	0.750	0.687	0.718	0.708	0.750	0.729	0.771
1.00 UNM	**0.250**	**0.740**	**0.832**	**0.763**	**0.798**	**0.786**	**0.832**	**0.809**	**0.855**
1.10 UNM	0.250	0.840	0.932	0.863	0.898	0.886	0.932	0.909	0.955
1.20 UNM	**0.250**	**0.940**	**1.032**	**0.963**	**0.998**	**0.986**	**1.032**	**1.009**	**1.055**
1.40 UNM	0.300	1.088	1.196	1.115	1.156	1.142	1.196	1.169	1.223
Designation	Thds. per in.	inch	inch	inch	inch	inch	inch	inch	inch
0.30 UNM	**318**	**0.0085**	**0.0100**	**0.0089**	**0.0095**	**0.0093**	**0.0100**	**0.0096**	**0.0104**
0.35 UNM	282	0.0101	0.0117	0.0105	0.0111	0.0109	0.0117	0.0113	0.0121
0.40 UNM	**254**	**0.0117**	**0.0134**	**0.0121**	**0.0127**	**0.0125**	**0.0134**	**0.0130**	**0.0138**
0.45 UNM	254	0.0136	0.0154	0.0141	0.0147	0.0145	0.0154	0.0149	0.0158
0.50 UNM	**203**	**0.0146**	**0.0166**	**0.0150**	**0.0158**	**0.0156**	**0.0166**	**0.0161**	**0.0171**
0.55 UNM	203	0.0165	0.0186	0.0170	0.0178	0.0176	0.0186	0.0181	0.0191
0.60 UNM	**169**	**0.0175**	**0.0198**	**0.0181**	**0.0190**	**0.0187**	**0.0198**	**0.0193**	**0.0204**
0.70 UNM	145	0.0204	0.0231	0.0211	0.0221	0.0217	0.0231	0.0224	0.0237
0.80 UNM	**127**	**0.0233**	**0.0263**	**0.0241**	**0.0252**	**0.0248**	**0.0263**	**0.0256**	**0.0270**
0.90 UNM	113	0.0262	0.0295	0.0270	0.0283	0.0279	0.0295	0.0287	0.0304
1.00 UNM	**102**	**0.0291**	**0.0327**	**0.0300**	**0.0314**	**0.0309**	**0.0327**	**0.0319**	**0.0337**
1.10 UNM	102	0.0331	0.0367	0.0340	0.0354	0.0349	0.0367	0.0358	0.0376
1.20 UNM	**102**	**0.0370**	**0.0406**	**0.0379**	**0.0393**	**0.0388**	**0.0406**	**0.0397**	**0.0415**
1.40 UNM	85	0.0428	0.0471	0.0439	0.0455	0.0450	0.0471	0.0460	0.0481

As an aid in selecting suitable drills, see the listing of American Standard drill sizes in the twist drill section. Thread sizes in heavy type are preferred sizes.

Hole Sizes for Tapping Unified Miniature Screw Threads.— Table 5 indicates the hole size limits recommended for tapping. These limits are derived from the internal thread minor diameter limits given in the American Standard for Unified Miniature Screw Threads ASA B1.10-1958 and are disposed so as to provide the optimum conditions for tapping. The maximum limits are based on providing a functionally adequate fastening for the most common applications, where the material of the externally threaded member is of a strength essentially equal to or greater than that of its mating part. In applications where, because of considerations other than the fastening, the screw is made of an appreciably

Copyright 2004, Industrial Press, Inc., New York, NY

weaker material, the use of smaller hole sizes is usually necessary to extend thread engagement to a greater depth on the external thread. Recommended minimum hole sizes are greater than the minimum limits of the minor diameters to allow for the spin-up developed in tapping.

In selecting drills to produce holes within the limits given in Table 5 it should be recognized that drills have a tendency to cut oversize. The material on page 885 may be used as a guide to the expected amount of oversize.

British Standard Tapping Drill Sizes for Screw and Pipe Threads.— British Standard BS 1157:1975 (1998) provides recommendations for tapping drill sizes for use with fluted taps for various ISO metric, Unified, British Standard fine, British Association, and British Standard Whitworth screw threads as well as British Standard parallel and taper pipe threads.

Table 6. British Standard Tapping Drill Sizes for ISO Metric Coarse Pitch Series Threads *BS 1157:1975 (1998)*

Nom. Size and Thread Diam.	Standard Drill Sizes[a]				Nom. Size and Thread Diam.	Standard Drill Sizes[a]			
	Recommended		Alternative			Recommended		Alternative	
	Size	Theoretical Radial Engagement with Ext. Thread (Per Cent)	Size	Theoretical Radial Engagement with Ext. Thread (Per Cent)		Size	Theoretical Radial Engagement with Ext. Thread (Per Cent)	Size	Theoretical Radial Engagement with Ext. Thread (Per Cent)
M 1	0.75	81.5	0.78	71.7	M 12	10.20	83.7	10.40	74.5[b]
M 1.1	0.85	81.5	0.88	71.7	M 14	12.00	81.5	12.20	73.4[b]
M 1.2	0.95	81.5	0.98	71.7	M 16	14.00	81.5	14.25	71.3[c]
M 1.4	1.10	81.5	1.15	67.9	M 18	15.50	81.5	15.75	73.4[c]
M 1.6	1.25	81.5	1.30	69.9	M 20	17.50	81.5	17.75	73.4[c]
M 1.8	1.45	81.5	1.50	69.9	M 22	19.50	81.5	19.75	73.4[c]
M 2	1.60	81.5	1.65	71.3	M 24	21.00	81.5	21.25	74.7[b]
M 2.2	1.75	81.5	1.80	72.5	M 27	24.00	81.5	24.25	74.7[b]
M 2.5	2.05	81.5	2.10	72.5	M 30	26.50	81.5	26.75	75.7[b]
M 3	2.50	81.5	2.55	73.4	M 33	29.50	81.5	29.75	75.7[b]
M 3.5	2.90	81.5	2.95	74.7	M 36	32.00	81.5	…	…
M 4	3.30	81.5	3.40	69.9[b]	M 39	35.00	81.5	…	…
M 4.5	3.70	86.8	3.80	76.1	M 42	37.50	81.5	…	…
M 5	4.20	81.5	4.30	71.3[b]	M 45	40.50	81.5	…	…
M 6	5.00	81.5	5.10	73.4	M 48	43.00	81.5	…	…
M 7	6.00	81.5	6.10	73.4	M 52	47.00	81.5	…	…
M 8	6.80	78.5	6.90	71.7[b]	M 56	50.50	81.5	…	…
M 9	7.80	78.5	7.90	71.7[b]	M 60	54.50	81.5	…	…
M 10	8.50	81.5	8.60	76.1	M 64	58.00	81.5	…	…
M 11	9.50	81.5	9.60	76.1	M 68	62.00	81.5	…	…

[a] These tapping drill sizes are for fluted taps only.
[b] For tolerance class 6H and 7H threads only.
[c] For tolerance class 7H threads only.

Drill sizes are given in millimeters.

In the accompanying Table 6, recommended and alternative drill sizes are given for producing holes for ISO metric coarse pitch series threads. These coarse pitch threads are suitable for the large majority of general-purpose applications, and the limits and tolerances for internal coarse threads are given in the table starting on page 1823. It should be noted that Table 6 is for fluted taps only since a fluteless tap will require for the same screw thread a different size of twist drill than will a fluted tap. When tapped, holes produced with drills of the recommended sizes provide for a theoretical radial engagement with the external thread of about 81 per cent in most cases. Holes produced with drills of the alternative sizes provide for a theoretical radial engagement with the external thread of about 70 to 75

Copyright 2004, Industrial Press, Inc., New York, NY

per cent. In some cases, as indicated in Table 6, the alternative drill sizes are suitable only for medium (6H) or for free (7H) thread tolerance classes.

When relatively soft material is being tapped, there is a tendency for the metal to be squeezed down towards the root of the tap thread, and in such instances, the minor diameter of the tapped hole may become smaller than the diameter of the drill employed. Users may wish to choose different tapping drill sizes to overcome this problem or for special purposes, and reference can be made to the pages mentioned above to obtain the minor diameter limits for internal pitch series threads.

Reference should be made to this standard BS 1157:1975 (1998) for recommended tapping hole sizes for other types of British Standard screw threads and pipe threads.

Table 7. British Standard Metric Bolt and Screw Clearance Holes *BS 4186: 1967*

Nominal Thread Diameter	Clearance Hole Sizes			Nominal Thread Diameter	Clearance Hole Sizes		
	Close Fit Series	Medium Fit Series	Free Fit Series		Close Fit Series	Medium Fit Series	Free Fit Series
1.6	1.7	1.8	2.0	52.0	54.0	56.0	62.0
2.0	2.2	2.4	2.6	56.0	58.0	62.0	66.0
2.5	2.7	2.9	3.1	60.0	62.0	66.0	70.0
3.0	3.2	3.4	3.6	64.0	66.0	70.0	74.0
4.0	4.3	4.5	4.8	68.0	70.0	74.0	78.0
5.0	5.3	5.5	5.8	72.0	74.0	78.0	82.0
6.0	6.4	6.6	7.0	76.0	78.0	82.0	86.0
7.0	7.4	7.6	8.0	80.0	82.0	86.0	91.0
8.0	8.4	9.0	10.0	85.0	87.0	91.0	96.0
10.0	10.5	11.0	12.0	90.0	93.0	96.0	101.0
12.0	13.0	14.0	15.0	95.0	98.0	101.0	107.0
14.0	15.0	16.0	17.0	100.0	104.0	107.0	112.0
16.0	17.0	18.0	19.0	105.0	109.0	112.0	117.0
18.0	19.0	20.0	21.0	110.0	114.0	117.0	122.0
20.0	21.0	22.0	24.0	115.0	119.0	122.0	127.0
22.0	23.0	24.0	26.0	120.0	124.0	127.0	132.0
24.0	25.0	26.0	28.0	125.0	129.0	132.0	137.0
27.0	28.0	30.0	32.0	130.0	134.0	137.0	144.0
30.0	31.0	33.0	35.0	140.0	144.0	147.0	155.0
33.0	34.0	36.0	38.0	150.0	155.0	158.0	165.0
36.0	37.0	39.0	42.0	…	…	…	…
39.0	40.0	42.0	45.0	…	…	…	…
42.0	43.0	45.0	48.0	…	…	…	…
45.0	46.0	48.0	52.0	…	…	…	…
48.0	50.0	52.0	56.0	…	…	…	…

All dimensions are given in millimeters.

British Standard Clearance Holes for Metric Bolts and Screws.— The dimensions of the clearance holes specified in this British Standard BS 4186:1967 have been chosen in such a way as to require the use of the minimum number of drills. The recommendations cover three series of clearance holes, namely close fit (H 12), medium fit (H 13), and free fit (H 14) and are suitable for use with bolts and screws specified in the following metric British Standards: BS 3692, ISO metric precision hexagon bolts, screws, and nuts; BS 4168, Hexagon socket screws and wrench keys; BS 4183, Machine screws and machine screw nuts; and BS 4190, ISO metric black hexagon bolts, screws, and nuts. The sizes are in accordance with those given in ISO Recommendation R273, and the range has been extended up to 150 millimeters diameter in accordance with an addendum to that recommendation. The selection of clearance holes sizes to suit particular design requirements

Copyright 2004, Industrial Press, Inc., New York, NY

can of course be dependent upon many variable factors. It is however felt that the medium fit series should suit the majority of general purpose applications. In the Standard, limiting dimensions are given in a table which is included for reference purposes only, for use in instances where it may be desirable to specify tolerances.

To avoid any risk of interference with the radius under the head of bolts and screws, it is necessary to countersink slightly all recommended clearance holes in the close and medium fit series. Dimensional details for the radius under the head of fasteners made according to BS 3692 are given on page 1575; those for fasteners to BS 4168 are given on page 1633; those to BS 4183 are given on pages 1607 through 1611.

Cold Form Tapping.— Cold form taps do not have cutting edges or conventional flutes; the threads on the tap form the threads in the hole by displacing the metal in an extrusion or swaging process. The threads thus produced are stronger than conventionally cut threads because the grains in the metal are unbroken and the displaced metal is work hardened. The surface of the thread is burnished and has an excellent finish. Although chip problems are eliminated, cold form tapping does displace the metal surrounding the hole and countersinking or chamfering before tapping is recommended. Cold form tapping is not recommended if the wall thickness of the hole is less than two-thirds of the nominal diameter of the thread. If possible, blind holes should be drilled deep enough to permit a cold form tap having a four thread lead to be used as this will require less torque, produce less burr surrounding the hole, and give a greater tool life.

The operation requires 0 to 50 per cent more torque than conventional tapping, and the cold form tap will pick up its own lead when entering the hole; thus, conventional tapping machines and tapping heads can be used. Another advantage is the better tool life obtained. The best results are obtained by using a good lubricating oil instead of a conventional cutting oil.

The method can be applied only to relatively ductile metals, such as low-carbon steel, leaded steels, austenitic stainless steels, wrought aluminum, low-silicon aluminum die casting alloys, zinc die casting alloys, magnesium, copper, and ductile copper alloys. A higher than normal tapping speed can be used, sometimes by as much as 100 per cent.

Conventional tap drill sizes should not be used for cold form tapping because the metal is displaced to form the thread. The cold formed thread is stronger than the conventionally tapped thread, so the thread height can be reduced to 60 per cent without much loss of strength; however, the use of a 65 per cent thread is strongly recommended. The following formula is used to calculate the theoretical hole size for cold form tapping:

$$\text{Theoretical hole size} = \text{basic tap O.D.} - \frac{0.0068 \times \text{per cent of full thread}}{\text{threads per inch}}$$

The theoretical hole size and the tap drill sizes for American Unified threads are given in Table 8, and Table 9 lists drills for ISO metric threads. Sharp drills should be used to prevent cold working the walls of the hole, especially on metals that are prone to work hardening. Such damage may cause the torque to increase, possibly stopping the machine or breaking the tap. On materials that can be die cast, cold form tapping can be done in cored holes provided the correct core pin size is used. The core pins are slightly tapered, so the theoretical hole size should be at the position on the pin that corresponds to one-half of the required engagement length of the thread in the hole. The core pins should be designed to form a chamfer on the hole to accept the vertical extrusion.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Theoretical and Tap Drill or Core Hole Sizes for Cold Form Tapping Unified Threads

Tap Size	Threads Per Inch	Percentage of Full Thread								
		75			65			55		
		Theor. Hole Size	Nearest Drill Size	Dec. Equiv.	Theor. Hole Size	Nearest Drill Size	Dec. Equiv.	Theor. Hole Size	Nearest Drill Size	Dec. Equiv.
0	80	0.0536	1.35 mm	0.0531	0.0545	…	…	0.0554	54	0.055
1	64	0.0650	1.65 mm	0.0650	0.0661	…	…	0.0672	51	0.0670
	72	0.0659	1.65 mm	0.0650	0.0669	1.7 mm	0.0669	0.0679	51	0.0670
2	56	0.0769	1.95 mm	0.0768	0.0781	5/64	0.0781	0.0794	2.0 mm	0.0787
	64	0.0780	5/64	0.0781	0.0791	2.0 mm	0.0787	0.0802	…	…
3	48	0.0884	2.25 mm	0.0886	0.0898	43	0.089	0.0913	2.3 mm	0.0906
	56	0.0889	43	0.089	0.0911	2.3 mm	0.0906	0.0924	2.35 mm	0.0925
4	40	0.0993	2.5 mm	0.0984	0.1010	39	0.0995	0.1028	2.6 mm	0.1024
	48	0.0104	38	0.1015	0.1028	2.6 mm	0.1024	0.1043	37	0.1040
5	40	0.1123	34	0.1110	0.1140	33	0.113	0.1158	32	0.1160
	44	0.1134	33	0.113	0.1150	2.9 mm	0.1142	0.1166	32	…
6	32	0.1221	3.1 mm	0.1220	0.1243	…	…	0.1264	3.2 mm	0.1260
	40	0.1253	1/8	0.1250	0.1270	3.2 mm	0.1260	0.1288	30	0.1285
8	32	0.1481	3.75 mm	0.1476	0.1503	25	0.1495	0.1524	24	0.1520
	36	0.1498	25	0.1495	0.1518	24	0.1520	0.1537	3.9 mm	0.1535
10	24	0.1688	…	…	0.1717	11/64	0.1719	0.1746	17	0.1730
	32	0.1741	17	0.1730	0.1763	…	…	0.1784	4.5 mm	0.1772
12	24	0.1948	10	0.1935	0.1977	5.0 mm	0.1968	0.2006	5.1 mm	0.2008
	28	0.1978	5.0 mm	0.1968	0.2003	8	0.1990	0.2028	…	…
1/4	20	0.2245	5.7 mm	0.2244	0.2280	1	0.2280	0.2315	…	…
	28	0.2318	…	…	0.2343	A	0.2340	0.2368	6.0 mm	0.2362
5/16	18	0.2842	7.2 mm	0.2835	0.2879	7.3 mm	0.2874	0.2917	7.4 mm	0.2913
	24	0.2912	7.4 mm	0.2913	0.2941	M	0.2950	0.2969	19/64	0.2969
3/8	16	0.3431	11/32	0.3437	0.3474	S	0.3480	0.3516	…	…
	24	0.3537	9.0 mm	0.3543	0.3566	…	…	0.3594	23/64	0.3594
7/16	14	0.4011	…	…	0.4059	13/32	0.4062	0.4108	…	…
	20	0.4120	Z	0.413	0.4154	…	…	0.4188	…	…
1/2	13	0.4608	…	…	0.4660	…	…	0.4712	12 mm	0.4724
	20	0.4745	…	…	0.4779	…	…	0.4813	…	…
9/16	12	0.5200	…	…	0.5257	…	…	0.5313	17/32	0.5312
	18	0.5342	13.5 mm	0.5315	0.5380	…	…	0.5417	…	…
5/8	11	0.5787	37/64	0.5781	0.5848	…	…	0.5910	15 mm	0.5906
	18	0.5976	19/32	0.5937	0.6004	…	…	0.6042	…	…
3/4	10	0.6990	…	…	0.7058	45/64	0.7031	0.7126	…	…
	16	0.7181	23/32	0.7187	0.7224	…	…	0.7266	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Tap Drill or Core Hole Sizes for Cold Form Tapping ISO Metric Threads

Nominal Size of Tap	Pitch	Recommended Tap Drill Size
1.6 mm	0.35 mm	1.45 mm
1.8 mm	0.35 mm	1.65 mm
2.0 mm	0.40 mm	1.8 mm
2.2 mm.	0.45 mm	2.0 mm
2.5 mm	0.45 mm	2.3 mm
3.0 mm	0.50 mm	2.8 mm[a]
3.5 mm	0.60 mm	3.2 mm
4.0 mm	0.70 mm	3.7 mm
4.5 mm	0.75 mm	4.2 mm[a]
5.0 mm	0.80 mm	4.6 mm
6.0 mm	1.00 mm	5.6 mm[a]
7.0 mm	1.00 mm	6.5 mm
8.0 mm	1.25 mm	7.4 mm
10.0 mm	1.50 mm	9.3 mm

[a] These diameters are the nearest stocked drill sizes and not the theoretical hole size, and may not produce 60 to 75 per cent full thread.

The sizes are calculated to provide 60 to 75 per cent of full thread.

Removing a Broken Tap.— Broken taps can be removed by electrodischarge machining (EDM), and this method is recommended when available. When an EDM machine is not available, broken taps may be removed by using a tap extractor, which has fingers that enter the flutes of the tap; the tap is backed out of the hole by turning the extractor with a wrench. Sometimes the injection of a small amount of a proprietary solvent into the hole will be helpful. A solvent can be made by diluting about one part nitric acid with five parts water. The action of the proprietary solvent or the diluted nitric acid on the steel loosens the tap so that it can be removed with pliers or with a tap extractor. The hole should be washed out afterwards so that the acid will not continue to work on the part. Another method is to add, by electric arc welding, additional metal to the shank of the broken tap, above the level of the hole. Care must be taken to prevent depositing metal on the threads in the tapped hole. After the shank has been built up, the head of a bolt or a nut is welded to it and then the tap may be backed out.

Tap Drills for Pipe Taps

Size of Tap	Drills for Briggs PipeTaps	Drills for Whitworth Pipe Taps	Size of Tap	Drills for Briggs Pipe Taps	Drills for Whitworth Pipe Taps	Size of Tap	Drills for Briggs Pipe Taps	Drills for Whitworth Pipe Taps
1/8	11/32	5/16	1 1/4	1 1/2	1 15/32	3 1/4	…	3 1/2
1/4	7/16	27/64	1 1/2	1 23/32	1 25/32	3 1/2	3 3/4	3 3/4
3/8	19/32	9/16	1 3/4	…	1 15/16	3 3/4	…	4
1/2	23/32	11/16	2	2 3/16	2 5/32	4	4 1/4	4 1/4
5/8	…	25/32	2 1/4	…	2 13/32	4 1/2	4 3/4	4 3/4
3/4	15/16	29/32	2 1/2	2 5/8	2 25/32	5	5 5/16	5 1/4
7/8	…	1 1/16	2 3/4	…	3 1/32	5 1/2	…	5 3/4
1	1 5/32	1 1/8	3	3 1/4	3 9/32	6	6 3/8	6 1/4

All dimensions are in inches.

To secure the best results, the hole should be reamed before tapping with a reamer having a taper of 3/4 inch per foot.

Power for Pipe Taps.— The power required for driving pipe taps is given in the following table, which includes nominal pipe tap sizes from 2 to 8 inches.

The holes to be tapped were reamed with standard pipe tap reamers before tapping. The horsepower recorded was read off just before the tap was reversed. The table gives the net horsepower, deductions being made for the power required to run the machine without a load. The material tapped was cast iron, except in two instances, where cast steel was tapped. It will be seen that nearly double the power is required for tapping cast steel. The

Copyright 2004, Industrial Press, Inc., New York, NY

power varies, of course, with the conditions. More power than that indicated in the table will be required if the cast iron is of a harder quality or if the taps are not properly relieved. The taps used in these experiments were of the inserted-blade type, the blades being made of high-speed steel.

Power Required for Pipe Taps

Nominal Tap Size	Rev. per Min.	Net H.P.	Thickness of Metal	Nominal Tap Size	Rev. per Min.	Net H.P.	Thickness of Metal
2	40	4.24	1⅛	3½	25.6	7.20	1¾
2½	40	5.15	1⅛	4	18	6.60	2
[a]2½	38.5	9.14	1⅛	5	18	7.70	2
3	40	5.75	1⅛	6	17.8	8.80	2
[a]3	38.5	9.70	1⅛	8	14	7.96	2½

[a] Tapping cast steel; other tests in cast iron.

Tap size and metal thickness are in inches.

High-Speed CNC Tapping.— Tapping speed depends on the type of material being cut, the type of cutting tool, the speed and rigidity of the machine, the rigidity of the part-holding fixture, and the proper use of coolants and cutting fluids. When tapping, each revolution of the tool feeds the tap a distance equal to the thread pitch. Both spindle speed and feed per revolution must be accurately controlled so that changes in spindle speed result in a corresponding change in feed rate. If the feed/rev is not right, a stripped thread or broken tap will result. NC/CNC machines equipped with the *synchronous tapping* feature are able to control the tap feed as a function of spindle speed. These machines can use rigid-type tap holders or automatic tapping attachments and are able to control depth very accurately. Older NC machines that are unable to reliably coordinate spindle speed and feed must use a tension-compression type tapping head that permits some variation of the spindle speed while still letting the tap feed at the required rate.

CNC machines capable of synchronous tapping accurately coordinate feed rate and rotational speed so that the tap advances at the correct rate regardless of the spindle speed. A canned tapping cycle (see *Fixed (Canned) Cycles* on page 1287 in the *NUMERICAL CONTROL* section) usually controls the operation, and feed and speed are set by the machine operator or part programmer. Synchronized tapping requires reversing the tapping spindle twice for each hole tapped, once after finishing the cut and again at the end of the cycle. Because the rotating mass is fairly large (motor, spindle, chuck or tap holder, and tap), the acceleration and deceleration of the tap are rather slow and a lot of time is lost by this process. The frequent changes in cutting speed during the cut also accelerate tap wear and reduce tap life.

A self-reversing tapping attachment has a forward drive that rotates in the same direction as the machine spindle, a reverse drive that rotates in the opposite direction, and a neutral position in between the two. When a hole is tapped, the spindle feeds at a slightly slower rate than the tap to keep the forward drive engaged until the tap reaches the bottom of the hole. Through holes are tapped by feeding to the desired depth and then retracting the spindle, which engages the tapping-head reverse drive and backs the tap out of the hole—the spindle does not need to be reversed. For tapping blind holes, the spindle is fed to a depth equal to the thread depth minus the self-feed of the tapping attachment. When the spindle is retracted (without reversing), the tap continues to feed forward a short distance (the tapping head self-feed distance) before the reverse drive engages and reverse drives the tap out of the hole. The depth can be controlled to within about ¼ revolution of the tap. The tapping cycle normally used for the self-reversing tap attachment is a standard boring cycle with feed return and no dwell. A typical programming cycle is illustrated with a G85 block on page 1289. The inward feed is set to about 95 per cent of the normal tapping feed (i.e.,

Copyright 2004, Industrial Press, Inc., New York, NY

95 per cent of the pitch per revolution). Because the tap is lightweight, tap reversal is almost instantaneous and tapping speed is very fast compared with synchronous tapping.

Tapping speeds are usually given in surface feet per minute (sfm) or the equivalent feet per minute (fpm or ft/min), so a conversion is necessary to get the spindle speed in revolutions per minute. The tapping speed in rpm depends on the diameter of the tap, and is given by the following formula:

$$\text{rpm} = \frac{\text{sfm} \times 12}{d \times 3.14159} = \frac{\text{sfm} \times 3.82}{d}$$

where d is the nominal diameter of the tap in inches. As indicated previously, the feed in in/rev is equal to the thread pitch and is independent of the cutting speed. The feed rate in inches per minute is found by dividing the tapping speed in rpm by the number of threads per inch, or by multiplying the speed in rpm by the pitch or feed per revolution:

$$\text{feed rate (in/min)} = \frac{\text{rpm}}{\text{threads per inch}} = \text{rpm} \times \text{thread pitch} = \text{rpm} \times \text{feed/rev}$$

Example: If the recommended tapping speed for 1020 steel is given as 45 to 60 sfm, find the required spindle speed and feed rate for tapping a 1/4–20 UNF thread in 1020 steel.

Assuming that the machine being used is in good condition and rigid, and the tap is sharp, use the higher rate of 60 sfm and calculate the required spindle speed and feed rate as follows:

$$\text{speed} = \frac{60 \times 3.82}{0.25} = 916.8 \approx 920 \text{ rpm} \qquad \text{feed rate} = \frac{920}{20} = 46 \text{ in/min}$$

Coolant for Tapping.— Proper use of through-the-tap high-pressure coolant/lubricant can result in increased tap life, increased speed and feed, and more accurate threads. In most chip-cutting processes, cutting fluid is used primarily as a coolant, with lubrication being a secondary but important benefit. Tapping, however, requires a cutting fluid with lubricity as the primary property and coolant as a secondary benefit. Consequently, the typical blend of 5 per cent coolant concentrate to 95 per cent water is too low for best results. An increased percentage of concentrate in the blend helps the fluid to cling to the tap, providing better lubrication at the cutting interface. A method of increasing the tap lubrication qualities without changing the concentration of the primary fluid blend is to use a cutting fluid dispenser controlled by an M code different from that used to control the high-pressure flood coolant (for example, use an M08 code in addition to M07). The secondary coolant-delivery system applies a small amount of an edge-type cutting fluid (about a drop at a time) directly onto the tap-cutting surfaces providing the lubrication needed for cutting. The edge-type fluid applied in this way clings to the tap, increasing the lubrication effect and ensuring that the cutting fluid becomes directly involved in the cutting action at the shear zone.

High-pressure coolant fed through the tap is important in many high-volume tapping applications. The coolant is fed directly through the spindle or tool holder to the cutting zone, greatly improving the process of chip evacuation and resulting in better thread quality. High-pressure through-the-tap coolant flushes blind holes before the tap enters and can remove chips from the holes after tapping is finished. The flushing action prevents chip recutting by forcing chips through the flutes and back out of the hole, improving the surface of the thread and increasing tap life. By improving lubrication and reducing heat and friction, the use of high-pressure coolant may result in increased tap life up to five times that of conventional tapping and may permit speed and feed increases that reduce overall cycle time.

Combined Drilling and Tapping.— A special tool that drills and taps in one operation can save a lot of time by reducing setup and eliminating a secondary operation in some

Copyright 2004, Industrial Press, Inc., New York, NY

applications. A combination drill and tap can be used for through holes if the length of the fluted drill section is greater than the material thickness, but cannot be used for drilling and tapping blind holes because the tip (drill point) must cut completely through the material before the tapping section begins to cut threads. Drilling and tapping depths up to twice the tool diameter are typical. Determine the appropriate speed by starting the tool at the recommended speed for the tap size and material, and adjust the speed higher or lower to suit the application. Feed during tapping is dependent on the thread pitch. NC/CNC programs can use a fast drilling speed and a slower tapping speed to combine both operations into one and minimize cutting time.

Relief Angles for Single-Point Thread Cutting Tools.— The surface finish on threads cut with single-point thread cutting tools is influenced by the relief angles on the tools. The leading and trailing cutting edges that form the sides of the thread, and the cutting edge at the nose of the tool must all be provided with an adequate amount of relief. Moreover, it is recommended that the effective relief angle, a_e, for all of these cutting edges be made equal, although the practice in some shops is to use slightly less relief at the trailing cutting edge. While too much relief may weaken the cutting edge, causing it to chip, an inadequate amount of relief will result in rough threads and in a shortened tool life. Other factors that influence the finish produced on threads include the following: the work material; the cutting speed; the cutting fluid used; the method used to cut the thread; and, the condition of the cutting edge.



Two similar diagrams showing relationships of various relief angles of thread cutting tools

Relief angles on single-point thread cutting tools are often specified on the basis of experience. While this method may give satisfactory results in many instances, better results can usually be obtained by calculating these angles, using the formulas provided further on. When special high helix angle threads are to be cut, the magnitude of the relief angles should always be calculated. These calculations are based on the effective relief angle, a_e; this is the angle between the flank of the tool and the sloping sides of the thread, measured in a direction parallel to the axis of the thread. Recommended values of this angle are 8 to 14 degrees for high speed steel tools, and 5 to 10 degrees for cemented carbide tools. The larger values are recommended for cutting threads on soft and gummy materials, and the smaller values are for the harder materials, which inherently take a better surface finish. Harder materials also require more support below the cutting edges, which is provided by using a smaller relief angle. These values are recommended for the relief angle below the cutting edge at the nose without any further modification. The angles below the leading and trailing side cutting edges are modified, using the formulas provided. The angles b and b' are the relief angles actually ground on the tool below the leading and trailing side cutting edges respectively; they are measured perpendicular to the side cutting edges. When designing or grinding the thread cutting tool, it is sometimes helpful to know the magnitude of the angle, n, for which a formula is provided. This angle would occur only in the event that the tool were ground to a sharp point. It is the angle of the edge formed by the intersection of the flank surfaces.

Copyright 2004, Industrial Press, Inc., New York, NY

$$\tan\phi = \frac{\text{lead of thread}}{\pi K} \qquad \tan\phi' = \frac{\text{lead of thread}}{\pi D}$$

$$a = a_e + \phi$$
$$a' = a_e - \phi'$$

$$\tan b = \tan a \cos \tfrac{1}{2}\omega$$
$$\tan b' = \tan a' \cos \tfrac{1}{2}\omega$$
$$\tan n = \frac{\tan a - \tan a'}{2 \tan \tfrac{1}{2}\omega}$$

where θ = helix angle of thread at minor diameter

θ' = helix angle of thread at major diameter

K = minor diameter of thread

D = major diameter of thread

a = side relief angle parallel to thread axis at leading edge of tool

a' = side relief angle parallel to thread axis at trailing edge of tool

a_e = effective relief angle

b = side relief angle perpendicular to leading edge of tool

b' = side relief angle perpendicular to trailing edge of tool

ω = included angle of thread cutting tool

n = nose angle resulting from intersection of flank surfaces

Example: Calculate the relief angles and the nose angle n for a single-point thread cutting tool that is to be used to cut a 1-inch diameter, 5-threads-per-inch, double Acme thread. The lead of this thread is $2 \times 0.200 = 0.400$ inch. The included angle ω of this thread is 29 degrees, the minor diameter K is 0.780 inch, and the effective relief angle a_e below all cutting edges is to be 10 degrees.

$$\tan\phi = \frac{\text{lead of thread}}{\pi K} = \frac{0.400}{\pi \times 0.780}$$
$$\phi = 9.27°\,(9°16')$$
$$\tan\phi' = \frac{\text{lead of thread}}{\pi D} = \frac{0.400}{\pi \times 1.000}$$
$$\phi' = 7.26°\,(7°15')$$
$$a = a_e + \phi = 10° + 9.27° = 19.27°$$
$$a' = a_e - \phi' = 10° - 7.26° = 2.74°$$
$$\tan b = \tan a \cos \tfrac{1}{2}\omega = \tan 19.27 \cos 14.5$$
$$b = 18.70°\,(18°42')$$
$$\tan b' = \tan a' \cos \tfrac{1}{2}\omega = \tan 2.74 \cos 14.5$$
$$b' = 2.65°\,(2°39')$$
$$\tan n = \frac{\tan a - \tan a'}{2 \tan \tfrac{1}{2}\omega} = \frac{\tan 19.27 - \tan 2.74}{2 \tan 14.5}$$
$$n = 30.26°\,(30°16')$$

Copyright 2004, Industrial Press, Inc., New York, NY

Lathe Change Gears

Change Gears for Thread Cutting.— To determine the change gears to use for cutting a thread of given pitch, first find what number of threads per inch will be cut when gears of the same size are placed on the lead screw and spindle stud, either by trial or by referring to the index plate; then multiply this number, called the "lathe screw constant," by some trial number to obtain the number of teeth in the gear for the spindle stud, and multiply the threads per inch to be cut by the *same* trial number to obtain the number of teeth in the gear for the lead screw. Expressing this rule as a formula:

$$\frac{\text{Trial number} \times \text{lathe screw constant}}{\text{Trial number} \times \text{threads per inch to be cut}} = \frac{\text{teeth in gear on spindle stud}}{\text{teeth in gear on lead screw}}$$

For example, suppose the available change gears supplied with the lathe have 24, 28, 32, 36 teeth, etc., the number increasing by 4 up to 100, and that 10 threads per inch are to be cut in a lathe having a lathe screw constant of 6; then, if the screw constant is written as the numerator, the number of threads per inch to be cut as the denominator of a fraction, and both numerator and denominator are multiplied by some trial number, say, 4, it is found that gears having 24 and 40 teeth can be used. Thus:

$$\frac{6}{10} = \frac{6 \times 4}{10 \times 4} = \frac{24}{40}$$

The 24-tooth gear goes on the spindle stud and the 40-toothgear on the lead screw.

The lathe screw constant is, of course, equal to the number of threads per inch on the lead screw, provided the spindle stud and spindle are geared in the ratio of 1 to 1, which, however. is not always so.

Compound Gearing.— To find the change gears used in compound gearing, place the screw constant as the numerator and the number of threads per inch to be cut as the denominator of a fraction; resolve both numerator and denominator into two factors each, and multiply each "pair" of factors by the same number, until values are obtained representing suitable numbers of teeth for the change gears. (One factor in the numerator and one in the denominator make a "pair" of factors.)

Example: —$1\frac{3}{4}$ threads per inch are to be cut in a lathe having a screw constant of 8; the available gears have 24, 28, 32, 36, 40 teeth. etc., increasing by 4 up to 100. Following the rule:

$$\frac{8}{1\frac{3}{4}} = \frac{2 \times 4}{1 \times 1\frac{3}{4}} = \frac{(2 \times 36) \times (4 \times 16)}{(1 \times 36) \times (1\frac{3}{4} \times 16)} = \frac{72 \times 64}{36 \times 28}$$

The gears having 72 and 64 teeth are the *driving* gears and those with 36 and 28 teeth are the *driven* gears.

Fractional Threads.— Sometimes the lead of a thread is given as a fraction of an inch instead of stating the number of threads per inch. For example, a thread may be required to be cut, having $\frac{3}{8}$ inch lead. The expression "$\frac{3}{8}$ inch lead" should first be transformed to "number of threads per inch." The number of threads per inch (the thread being single) equals:

$$\frac{1}{\frac{3}{8}} = 1 \div \frac{3}{8} = \frac{8}{3} = 2\frac{2}{3}$$

To find the change gears to cut $2\frac{2}{3}$ threads per inch in a lathe having a screw constant 8 and change gears ranging from 24 to 100 teeth, increasing in increments of 4, proceed as below:

$$\frac{8}{2\frac{2}{3}} = \frac{2 \times 4}{1 \times 2\frac{2}{3}} = \frac{(2 \times 36) \times (4 \times 24)}{(1 \times 36) \times (2\frac{2}{3} \times 24)} = \frac{72 \times 96}{36 \times 64}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Metric Pitches.— When screws are cut in accordance with the metric system, it is the usual practice to give the lead of the thread in millimeters, instead of the number of threads per unit of measurement. To find the change gears for cutting metric threads, when using a lathe having an inch lead screw, first determine the number of threads per inch corresponding to the given lead in millimeters. Suppose a thread of 3 millimeters lead is to be cut in a lathe having an inch lead screw and a screw constant of 6. As there are 25.4 millimeters per inch, the number of threads per inch will equal 25.4 ÷ 3. Place the screw constant as the numerator, and the number of threads per inch to be cut as the denominator:

$$\frac{6}{\frac{25.4}{3}} = 6 \div \frac{25.4}{3} = \frac{6 \times 3}{25.4}$$

The numerator and denominator of this fractional expression of the change gear ratio is next multiplied by some trial number to determine the size of the gears. The first whole number by which 25.4 can be multiplied so as to get a whole number as the result is 5. Thus, 25.4 × 5 = 127. Hence, one gear having 127 teeth is always used when cutting metric threads with an inch lead screw. The other gear required has 90 teeth. Thus:

$$\frac{6 \times 3 \times 5}{25.4 \times 5} = \frac{90}{127}$$

Therefore, the following rule can be used to find the change gears for cutting metric pitches with an inch lead screw:

Rule: Place the lathe screw constant multiplied by the lead of the required thread in millimeters multiplied by 5 as the numerator of the fraction and 127 as the denominator. The product of the numbers in the numerator equals the number of teeth for the spindle-stud gear, and 127 is the number of teeth for the lead-screw gear.

If the lathe has a metric pitch lead screw, and a screw having a given number of threads per inch is to be cut, first find the "metric screw constant" of the lathe or the lead of thread in millimeters that would be cut with change gears of equal size on the lead screw and spindle stud; then the method of determining the change gears is simply the reverse of the one already explained for cutting a metric thread with an inch lead screw.

Rule: To find the change gears for cutting inch threads with a metric lead screw, place 127 in the numerator and the threads per inch to be cut, multiplied by the metric screw constant multiplied by 5 in the denominator; 127 is the number of teeth on the spindle-stud gear and the product of the numbers in the denominator equals the number of teeth in the lead-screw gear.

Threads per Inch Obtained with a Given Combination of Gears.— To determine the number of threads per inch that will be obtained with a given combination of gearing, multiply the lathe screw constant by the number of teeth in the *driven* gear (or by the product of the numbers of teeth in both driven gears of compound gearing), and divide the product thus obtained by the number of teeth in the *driving* gear (or by the product of the two driving gears of a compound train). The quotient equals the number of threads per inch.

Change Gears for Fractional Ratios.— When gear ratios cannot be expressed exactly in whole numbers that are within the range of ordinary gearing, the combination of gearing required for the fractional ratio may be determined quite easily, often by the "cancellation method." To illustrate this method, assume that the speeds of two gears are to be in the ratio of 3.423 to 1. The number 3.423 is first changed to $^{3423}/_{1000}$ to clear it of decimals. Then, in order to secure a fraction that can be reduced, 3423 is changed to 3420;

$$\frac{3420}{1000} = \frac{342}{100} = \frac{3 \times 2 \times 57}{2 \times 50} = \frac{3 \times 57}{1 \times 50}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Then, multiplying $\frac{3}{1}$ by some trial number, say, 24, the following gear combination is obtained:

$$\frac{72}{24} \times \frac{57}{50} = \frac{4104}{1200} = \frac{3.42}{1}$$

As the desired ratio is 3.423 to I, there is an error of 0.003. When the ratios are comparatively simple, the cancellation method is not difficult and is frequently used; but by the logarithmic method to be described, more accurate results are usually possible.

Modifying the Quick-Change Gearbox Output.— On most modern lathes, the gear train connecting the headstock spindle with the lead screw contains a quick-change gearbox. Instead of using different change gears, it is only necessary to position the handles of the gearbox to adjust the speed ratio between the spindle and the lead screw in preparation for cutting a thread. However, a thread sometimes must be cut for which there is no quick-change gearbox setting. It is then necessary to modify the normal, or standard, gear ratio between the spindle and the gearbox by installing modifying change gears to replace the standard gears normally used. Metric and other odd pitch threads can be cut on lathes that have an inch thread lead screw and a quick-change gearbox having only settings for inch threads by using modifying-change gears in the gear train. Likewise, inch threads and other odd pitch threads can be cut on metric lead-screw lathes having a gearbox on which only metric thread settings can be made. Modifying-change gears also can be used for cutting odd pitch threads on lathes having a quick-change gearbox that has both inch and metric thread settings.

The sizes of the modifying-change gears can be calculated by formulas to be given later; they depend on the thread to be cut and on the setting of the quick-change gearbox. Many different sets of gears can be found for each thread to be cut. It is recommended that several calculations be made in order to find the set of gears that is most suitable for installation on the lathe. The modifying-change gear formulas that follow are based on the type of lead screw, i.e., whether the lead screw has inch or metric threads.

Metric Threads on Inch Lead-Screw Lathes: A 127-tooth translating gear must be used in the modifying-change gear train in order to be able to cut metric threads on inch lead-screw lathes. The formula for calculating the modifying change gears is:

$$\frac{5 \times \text{gearbox setting in thds/in.} \times \text{pitch in mm to be cut}}{127} = \frac{\text{driving gears}}{\text{driven gears}}$$

The numerator and denominator of this formula are multiplied by equal numbers, called trial numbers, to find the gears. If suitable gears cannot be found with one set, then another set of equal trial numbers is used. (Because these numbers are equal, such as 15/15 or 24/24, they are equal to the number one when thought of as a fraction; their inclusion has the effect of multiplying the formula by one, which does not change its value.) It is necessary to select the gearbox setting in threads per inch that must be used to cut the metric thread when using the gears calculated by the formula. One method is to select a quick-change gearbox setting that is close to the actual number of metric threads in a 1-inch length, called the equivalent threads per inch, which can be calculated by the following formula: Equivalent thds/in. = 25.4 ÷ pitch in millimeters to be cut.

Example: Select the quick-change gearbox setting and calculate the modifying change gears required to set up a lathe having an inch-thread lead screw in order to cut an M12 × 1.75 metric thread.

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Equivalent thds/in.} = \frac{25.4}{\text{pitch in mm to be cut}} = \frac{25.4}{1.75} = 1.45 \text{ (use 14 thds/in.)}$$

$$\frac{5 \times \text{gearbox setting in thds/in.} \times \text{pitch in mm to be cut}}{127} = \frac{5 \times 14 \times 1.75}{127}$$

$$= \frac{(24) \times 5 \times 14 \times 1.75}{(24) \times 127} = \frac{(5 \times 14) \times (24 \times 1.75)}{24 \times 127}$$

$$\frac{70 \times 42}{24 \times 127} = \frac{\text{driving gears}}{\text{driven gears}}$$

Odd Inch Pitch Threads: The calculation of the modifying change gears used for cutting odd pitch threads that are specified by their pitch in inches involves the sizes of the standard gears, which can be found by counting their teeth. Standard gears are those used to enable the lathe to cut the thread for which the gearbox setting is made; they are the gears that are normally used. The threads on worms used with worm gears are among the odd pitch threads that can be cut by this method. As before, it is usually advisable to calculate the actual number of threads per inch of the odd pitch thread and to select a gearbox setting that is close to this value. The following formula is used to calculate the modifying-change gears to cut odd inch pitch threads:

$$\frac{\text{Standard driving gear} \times \text{pitch to be cut in inches} \times \text{gearbox setting in thds/in.}}{\text{Standard driven gear}}$$

$$= \frac{\text{driving gears}}{\text{driven gears}}$$

Example: Select the quick-change gearbox setting and calculate the modifying change gears required to cut a thread having a pitch equal to 0.195 inch. The standard driving and driven gears both have 48 teeth. To find equivalent threads per inch:

$$\frac{\text{Thds}}{\text{in.}} = \frac{1}{\text{pitch}} = \frac{1}{0.195} = 5.13 \qquad \text{(use 5 thds/in.)}$$

$$\frac{\text{Standard driving gear} \times \text{pitch to be cut in inches} \times \text{gearbox setting in thds/in.}}{\text{Standard driven gear}}$$

$$= \frac{48 \times 0.195 \times 5}{48} = \frac{(1000) \times 0.195 \times 5}{(1000)} = \frac{195 \times 5}{500 \times 2} = \frac{39 \times 5}{100 \times 2} = \frac{39 \times 5 \times (8)}{50 \times 2 \times 2 \times (8)}$$

$$= \frac{39 \times 40}{50 \times 32} = \frac{\text{driving gears}}{\text{driven gears}}$$

It will be noted that in the second step above, 1000/1000 has been substituted for 48/48. This substitution does not change the ratio. The reason for this substitution is that $1000 \times 0.195 = 195$, a whole number. Actually, 200/200 might have been substituted because $200 \times 0.195 = 39$, also a whole number.

The procedure for calculating the modifying gears using the following formulas is the same as illustrated by the two previous examples.

Odd Threads per Inch on Inch Lead Screw Lathes:

$$\frac{\text{Standard driving gear} \times \text{gearbox setting in thds/in.}}{\text{Standard driven gear} \times \text{thds/in. to be cut}} = \frac{\text{driving gears}}{\text{driven gears}}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Inch Threads on Metric Lead Screw Lathes:

$$\frac{127}{5 \times \text{gearbox setting in mm pitch} \times \text{thds/in. to be cut}} = \frac{\text{driving gears}}{\text{driven gears}}$$

Odd Metric Pitch Threads on Metric Lead Screw Lathes:

$$\frac{\text{Standard driving gear} \times \text{mm pitch to be cut}}{\text{Standard driven gear} \times \text{gearbox setting in mm pitch}} = \frac{\text{driving gears}}{\text{driven gears}}$$

Finding Accurate Gear Ratios.— Tables included in the 23rd and earlier editions of this handbook furnished a series of logarithms of gear ratios as a quick means of finding ratios for all gear combinations having 15 to 120 teeth. The ratios thus determined could be factored into sets of 2, 4, 6, or any other even numbers of gears to provide a desired overall ratio.

Although the method of using logarithms of gear ratios provides results of suitable accuracy for many gear-ratio problems, it does not provide a systematic means of evaluating whether other, more accurate ratios are available. In critical applications, especially in the design of mechanisms using reduction gear trains, it may be desirable to find many or all possible ratios to meet a specified accuracy requirement. The methods best suited to such problems use *Continued Fractions* and *Conjugate Fractions* as explained starting on pages 11 and illustrated in the worked-out example on page 13 for a set of four change gears.

As an example, if an overall reduction of 0.31416 is required, a fraction must be found such that the factors of the numerator and denominator may be used to form a four-gear reduction train in which no gear has more than 120 teeth. By using the method of conjugate fractions discussed on page 12, the ratios listed above, and their factors are found to be successively closer approximations to the required overall gear ratio.

Ratio	Numerator Factors	Denominator	Error Factors
11/35	11	5 × 7	+0.00013
16/51	2 × 2 × 2 × 2	3 × 17	–0.00043
27/86	3 × 3 × 3	2 × 43	–0.00021
38/121	2 × 19	11 × 11	–0.00011
49/156	7 × 7	2 × 2 × 3 × 13	–0.00006
82/261	2 × 41	3 × 3 × 29	+0.00002
224/713	2 × 2 × 2 × 2 × 2 × 7	23 × 31	+0.000005
437/1391	19 × 23	13 × 107	+0.000002
721/2295	7 × 103	3 × 3 × 3 × 5 × 17	+0.000001
1360/4329	2 × 2 × 2 × 2395 × 17	3 × 3 × 13 × 53	+0.0000003
1715/5459	5 × 7 × 7 × 7	53 × 103	+0.0000001
3927/12500	3 × 7 × 11 × 17	2 × 2 × 5 × 5 × 5 × 5 × 5	0

Lathe Change-gears.— To calculate the change gears to cut any pitch on a lathe, the "constant" of the machine must be known. For any lathe, the ratio C:L = driver:driven gear, in which C = constant of machine and L = threads per inch.

For example, to find the change gears required to cut 1.7345 threads per inch on a lathe having a constant of 4, the formula:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{C}{L} = \frac{4}{1.7345} = 2.306140$$

may be used. The method of conjugate fractions shown on page 12 will find the ratio, 113⁄49 = 2.306122, which is closer than any other having suitable factors. This ratio is in error by only 2.306140 – 2.306122 = 0.000018. Therefore, the driver should have 113 teeth and the driven gear 49 teeth.

Relieving Helical-Fluted Hobs.— Relieving hobs that have been fluted at right angles to the thread is another example of approximating a required change-gear ratio. The usual method is to change the angle of the helical flutes to agree with previously calculated change-gears. The ratio between the hob and the relieving attachment is expressed in the formula:

$$\frac{N}{(C \times \cos^2\alpha)} = \frac{driver}{driven} \text{ gears}$$

and

$$\tan\alpha = \frac{P}{H_c}$$

in which: N = number of flutes in hob; α = helix angle of thread from plane perpendicular to axis; C = constant of relieving attachment; P = axial lead of hob; and H_c = hob pitch circumference, = 3.1416 times pitch diameter.

The constant of the relieving attachment is found on its index plate and is determined by the number of flutes that require equal gears on the change-gear studs. These values will vary with different makes of lathes.

For example, what four change-gears can be used to relieve a helical-fluted worm-gear hob, of 24 diametral pitch, six starts, 13 degrees, 41 minutes helix angle of thread, with eleven helical flutes, assuming a relieving attachment having a constant of 4 is to be used?

$$\frac{N}{(C \times \cos^2\alpha)} = \frac{11}{(4 \times \cos^2 13°41')} = \frac{11}{(4 \times 0.944045)} = 2.913136$$

Using the conjugate fractions method discussed on page 12, the following ratios are found to provide factors that are successively closer approximations to the required change-gear ratio 2.913136.

Numerator/Denominator	*Ratio*	*Error*
67 × 78/(39 × 46)	2.913043	–0.000093
30 × 47/(22 × 22)	2.913223	+0.000087
80 × 26/(21 × 34)	2.913165	+0.000029
27 × 82/(20 × 38)	2.913158	+0.000021
55 × 75/(24 × 59)	2.913136	+0.0000004
74 × 92/(57 × 41)	2.913136	+0.00000005

Copyright 2004, Industrial Press, Inc., New York, NY

THREAD ROLLING

Screw threads may be formed by rolling either by using some type of thread-rolling machine or by equipping an automatic screw machine or turret lathe with a suitable threading roll. If a thread-rolling machine is used, the unthreaded screw, bolt, or other "blank" is placed (either automatically or by hand) between dies having thread-shaped ridges that sink into the blank, and by displacing the metal, form a thread of the required shape and pitch. The thread-rolling process is applied where bolts, screws, studs, threaded rods, etc., are required in large quantities. Screw threads that are within the range of the rolling process may be produced more rapidly by this method than in any other way. Because of the cold-working action of the dies, the rolled thread is 10 to 20 per cent stronger than a cut or ground thread, and the increase may be much higher for fatigue resistance. Other advantages of the rolling process are that no stock is wasted in forming the thread, and the surface of a rolled thread is harder than that of a cut thread, thus increasing wear resistance.

Thread-Rolling Machine of Flat-Die Type.— One type of machine that is used extensively for thread rolling is equipped with a pair of flat or straight dies. One die is stationary and the other has a reciprocating movement when the machine is in use. The ridges on these dies, which form the screw thread, incline at an angle equal to the helix angle of the thread. In making dies for precision thread rolling, the threads may be formed either by milling and grinding after heat treatment, or by grinding "from the solid" after heat treating. A vitrified wheel is used.

In a thread-rolling machine, thread is formed in one passage of the work, which is inserted at one end of the dies, either by hand or automatically, and then rolls between the die faces until it is ejected at the opposite end. The relation between the position of the dies and a screw thread being rolled is such that the top of the thread-shaped ridge of one die, at the point of contact with the screw thread, is directly opposite the bottom of the thread groove in the other die at the point of contact. Some form of mechanism ensures starting the blank at the right time and square with the dies.

Thread-Rolling Machine of Cylindrical-Die Type.— With machines of this type, the blank is threaded while being rolled between two or three cylindrical dies (depending upon the type of machine) that are pressed into the blank at a rate of penetration adjusted to the hardness of the material, or wall thickness in threading operations on tubing or hollow parts. The dies have ground, or ground and lapped, threads and a pitch diameter that is a multiple of the pitch diameter of the thread to be rolled. As the dies are much larger in diameter than the work, a multiple thread is required to obtain the same lead angle as that of the work. The thread may be formed in one die revolution or even less, or several revolutions may be required (as in rolling hard materials) to obtain a gradual rate of penetration equivalent to that obtained with flat or straight dies if extended to a length of possibly 15 or 20 feet. Provisions for accurately adjusting or matching the thread rolls to bring them into proper alignment with each other are important features of these machines.

Two-Roll Type of Machine: With a two-roll type of machine, the work is rotated between two horizontal power-driven threading rolls and is supported by a hardened rest bar on the lower side. One roll is fed inward by hydraulic pressure to a depth that is governed automatically.

Three-Roll Type of Machine: With this machine, the blank to be threaded is held in a "floating position" while being rolled between three cylindrical dies that, through toggle arms, are moved inward at a predetermined rate of penetration until the required pitch diameter is obtained. The die movement is governed by a cam driven through change gears selected to give the required cycle of squeeze, dwell, and release.

Rate of Production.— Production rates in thread rolling depend upon the type of machine, the size of both machine and work, and whether the parts to be threaded are inserted by hand or automatically. A reciprocating flat die type of machine, applied to ordinary steels, may thread 30 or 40 parts per minute in diameters ranging from about $\frac{5}{8}$ to $1\frac{1}{8}$

Copyright 2004, Industrial Press, Inc., New York, NY

inch, and 150 to 175 per minute in machine screw sizes from No. 10 (.190) to No. 6 (.138). In the case of heat-treated alloy steels in the usual hardness range of 26 to 32 Rockwell C, the production may be 30 or 40 per minute or less. With a cylindrical die type of machine, which is designed primarily for precision work and hard metals, 10 to 30 parts per minute are common production rates, the amount depending upon the hardness of material and allowable rate of die penetration per work revolution. These production rates are intended as a general guide only. The diameters of rolled threads usually range from the smallest machine screw sizes up to 1 or 1½ inches, depending upon the type and size of machine.

Precision Thread Rolling.— Both flat and cylindrical dies are used in aeronautical and other plants for precision work. With accurate dies and blank diameters held to close limits, it is practicable to produce rolled threads for American Standard Class 3 and Class 4 fits. The blank sizing may be by centerless grinding or by means of a die in conjunction with the heading operations. The blank should be round, and, as a general rule, the diameter tolerance should not exceed ½ to ⅔ the pitch diameter tolerance. The blank diameter should range from the correct size (which is close to the pitch diameter, but should be determined by actual trial), down to the allowable minimum, the tolerance being minus to insure a correct pitch diameter, even though the major diameter may vary slightly. Precision thread rolling has become an important method of threading alloy steel studs and other threaded parts, especially in aeronautical work where precision and high-fatigue resistance are required. Micrometer screws are also an outstanding example of precision thread rolling. This process has also been applied in tap making, although it is the general practice to finish rolled taps by grinding when the Class 3 and Class 4 fits are required.

Steels for Thread Rolling.— Steels vary from soft low-carbon types for ordinary screws and bolts, to nickel, nickel-chromium and molybdenum steels for aircraft studs, bolts, etc., or for any work requiring exceptional strength and fatigue resistance. Typical SAE alloy steels are No. 2330, 3135, 3140, 4027, 4042, 4640 and 6160. The hardness of these steels after heat-treatment usually ranges from 26 to 32 Rockwell C, with tensile strengths varying from 130,000 to 150,000 pounds per square inch. While harder materials might be rolled, grinding is more practicable when the hardness exceeds 40 Rockwell C. Thread rolling is applicable not only to a wide range of steels but for non-ferrous materials, especially if there is difficulty in cutting due to "tearing" the threads.

Diameter of Blank for Thread Rolling.— The diameter of the screw blank or cylindrical part upon which a thread is to be rolled should be less than the outside screw diameter by an amount that will just compensate for the metal that is displaced and raised above the original surface by the rolling process. The increase in diameter is approximately equal to the depth of one thread. While there are rules and formulas for determining blank diameters, it may be necessary to make slight changes in the calculated size in order to secure a well-formed thread. The blank diameter should be verified by trial, especially when rolling accurate screw threads. Some stock offers greater resistance to displacement than other stock, owing to the greater hardness or tenacity of the metal. The following figures may prove useful in establishing trial sizes. The blank diameters for screws varying from ¼ to ½ are from 0.002 to 0.0025 inch larger than the pitch diameter, and for screws varying from ½ to 1 inch or larger, the blank diameters are from 0.0025 to .003 inch larger than the pitch diameter. Blanks which are slightly less than the pitch diameter are intended for bolts, screws, etc., which are to have a comparatively free fit. Blanks for this class of work may vary from 0.002 to 0.003 inch less than the pitch diameter for screw thread sizes varying from ¼ to ½ inch, and from 0.003 to 0.005 inch less than the pitch diameter for sizes above ½ inch. If the screw threads are smaller than ¼ inch, the blanks are usually from 0.001 to 0.0015 inch less than the pitch diameter for ordinary grades of work.

Thread Rolling in Automatic Screw Machines.— Screw threads are sometimes rolled in automatic screw machines and turret lathes when the thread is behind a shoulder so that

Copyright 2004, Industrial Press, Inc., New York, NY

it cannot be cut with a die. In such cases, the advantage of rolling the thread is that a second operation is avoided. A circular roll is used for rolling threads in screw machines. The roll may be presented to the work either in a tangential direction or radially, either method producing a satisfactory thread. In the former case, the roll gradually comes into contact with the periphery of the work and completes the thread as it passes across the surface to be threaded. When the roll is held in a radial position, it is simply forced against one side until a complete thread is formed. The method of applying the roll may depend upon the relation between the threading operation and other machining operations. Thread rolling in automatic screw machines is generally applied only to brass and other relatively soft metals, owing to the difficulty of rolling threads in steel. Thread rolls made of chrome-nickel steel containing from 0.15 to 0.20 per cent of carbon have given fairly good results, however, when applied to steel. A 3 per cent nickel steel containing about 0.12 per cent carbon has also proved satisfactory for threading brass.

Factors Governing the Diameter of Thread Rolling.— The threading roll used in screw machines may be about the same diameter as the screw thread, but for sizes smaller than, say, ¾ inch, the roll diameter is some multiple of the thread diameter minus a slight amount to obtain a better rolling action. When the diameters of the thread and roll are practically the same, a single-threaded roll is used to form a single thread on the screw. If the diameter of the roll is made double that of the screw, in order to avoid using a small roll, then the roll must have a double thread. If the thread roll is three times the size of the screw thread, a triple thread is used, and so on. These multiple threads are necessary when the roll diameter is some multiple of the work, in order to obtain corresponding helix angles on the roll and work.

Diameter of Threading Roll.— The pitch diameter of a threading roll having a single thread is slightly less than the pitch diameter of the screw thread to be rolled, and in the case of multiple-thread rolls, the pitch diameter is not an exact multiple of the screw thread pitch diameter but is also reduced somewhat. The amount of reduction recommended by one screw machine manufacturer is given by the formula shown at the end of this paragraph. A description of the terms used in the formula is given as follows: D = pitch diameter of threading roll, d = pitch diameter of screw thread, N = number of single threads or "starts" on the roll (this number is selected with reference to diameter of roll desired), T = single depth of thread:

$$D = N\left(d - \frac{T}{2}\right) - T$$

Example: Find, by using above formula, the pitch diameter of a double-thread roll for rolling a ½-inch American standard screw thread. Pitch diameter $d = 0.4500$ inch and thread depth $T = 0.0499$ inch.

$$D = 2\left(0.4500 - \frac{0.0499}{2}\right) - 0.0499 = 0.8001 \text{ inch}$$

Kind of Thread on Roll and Its Shape.— The thread (or threads) on the roll should be left hand for rolling a right-hand thread, and *vice versa*. The roll should be wide enough to overlap the part to be threaded, provided there are clearance spaces at the ends, which should be formed if possible. The thread on the roll should be sharp on top for rolling an American (National) standard form of thread, so that less pressure will be required to displace the metal when rolling the thread. The bottom of the thread groove on the roll may also be left sharp or it may have a flat. If the bottom is sharp, the roll is sunk only far enough into the blank to form a thread having a flat top, assuming that the thread is the American form. The number of threads on the roll (whether double, triple, quadruple, etc.) is selected, as a rule, so that the diameter of the thread roll will be somewhere between 1¼ and 2¼ inches. In making a thread roll, the ends are beveled at an angle of 45 degrees, to prevent

Copyright 2004, Industrial Press, Inc., New York, NY

the threads on the ends of the roll from chipping. Precautions should be taken in hardening, because, if the sharp edges are burnt, the roll will be useless. Thread rolls are usually lapped after hardening, by holding them on an arbor in the lathe and using emery and oil on a piece of hard wood. To give good results a thread roll should fit closely in the holder. If the roll is made to fit loosely, it will mar the threads.

Application of Thread Roll.— The shape of the work and the character of the operations necessary to produce it, govern, to a large extent, the method employed in applying the thread roll. Some of the points to consider are as follows:

1) Diameter of the part to be threaded.
2) Location of the part to be threaded.
3) Length of the part to be threaded.
4) Relation that the thread rolling operation bears to the other operations.
5) Shape of the part to be threaded, whether straight, tapered or otherwise.
6) Method of applying the support.

When the diameter to be rolled is much smaller than the diameter of the shoulder preceding it, a cross-slide knurl-holder should be used. If the part to be threaded is not behind a shoulder, a holder on the swing principle should be used. When the work is long (greater in length than two-and-one-half times its diameter) a swing roll-holder should be employed, carrying a support. When the work can be cut off after the thread is rolled, a cross-slide roll-holder should be used. The method of applying the support to the work also governs to some extent the method of applying the thread roll. When no other tool is working at the same time as the thread roll, and when there is freedom from chips, the roll can be held more rigidly by passing it under instead of over the work. When passing the roll over the work, there is a tendency to raise the cross-slide. Where the part to be threaded is tapered, the roll can best be presented to the work by holding it in a cross-slide roll-holder.

Speeds and Feeds for Thread Rolling.— When the thread roll is made from high-carbon steel and used on brass, a surface speed as high as 200 feet per minute can be used. However, better results are obtained by using a lower speed than this. When the roll is held in a holder attached to the cross-slide, and is presented either tangentially or radially to the work, a considerably higher speed can be used than if it is held in a swing tool. This is due to the lack of rigidity in a holder of the swing type. The feeds to be used when a cross-slide roll-holder is used are given in the upper half of the table "Feeds for Thread Rolling;" the lower half of the table gives the feeds for thread rolling with swing tools. These feeds are applicable for rolling threads without a support, when the root diameter of the blank is not less than five times the double depth of the thread. When the root diameter is less than this, a support should be used. A support should also be used when the width of the roll is more than two-and-one-half times the smallest diameter of the piece to be rolled, irrespective of the pitch of the thread. When the smallest diameter of the piece to be rolled is much less than the root diameter of the thread, the smallest diameter should be taken as the deciding factor for the feed to be used.

Copyright 2004, Industrial Press, Inc., New York, NY

Feeds for Thread Rolling

Root Diam. of Blank	Number of Threads per Inch													
	72	64	56	48	44	40	36	32	28	24	22	20	18	14
	Cross-slide Holders — Feed per Revolution in Inches													
1/8	0.0045	0.0040	0.0035	0.0030	0.0025	0.0020	0.0015	0.0010	.....	.....	.....	.....	.....	.....
3/16	0.0050	0.0045	0.0040	0.0035	0.0030	0.0025	0.0020	0.0015	0.0005	.....	.....	.....	.....	.....
1/4	0.0055	0.0050	0.0045	0.0040	0.0035	0.0030	0.0025	0.0020	0.0010	0.0005	0.0005	.....	.....	.....
5/16	0.0060	0.0055	0.0050	0.0045	0.0040	0.0035	0.0030	0.0025	0.0015	0.0010	0.0010	0.0005	0.0005	.....
3/8	0.0065	0.0060	0.0055	0.0050	0.0045	0.0040	0.0035	0.0030	0.0020	0.0015	0.0015	0.0010	0.0010	0.0005
7/16	0.0070	0.0065	0.0060	0.0055	0.0050	0.0045	0.0040	0.0035	0.0025	0.0020	0.0020	0.0015	0.0015	0.0010
1/2	0.0075	0.0070	0.0065	0.0060	0.0055	0.0050	0.0045	0.0040	0.0030	0.0025	0.0025	0.0020	0.0020	0.0015
5/8	0.0080	0.0075	0.0070	0.0065	0.0060	0.0055	0.0050	0.0045	0.0035	0.0030	0.0030	0.0025	0.0025	0.0020
3/4	0.0085	0.0080	0.0075	0.0070	0.0065	0.0060	0.0055	0.0050	0.0040	0.0035	0.0035	0.0030	0.0030	0.0025
7/8	0.0090	0.0085	0.0080	0.0075	0.0070	0.0065	0.0060	0.0055	0.0045	0.0040	0.0040	0.0035	0.0035	0.0030
1	0.0095	0.0090	0.0085	0.0080	0.0075	0.0070	0.0065	0.0060	0.0050	0.0045	0.0045	0.0040	0.0040	0.0035
Root Diam.	Swing Holders — Feed per Revolution in Inches													
1/8	0.0025	0.0020	0.0015	0.0010	0.0005	.....	.....	.....	.....	.....	.....	.....	.....	.....
3/16	0.0028	0.0025	0.0020	0.0015	0.0008	0.0005	.....	.....	.....	.....	.....	.....	.....	.....
1/4	0.0030	0.0030	0.0025	0.0020	0.0010	0.0010	0.0005	0.0005	0.0005	.....	.....	.....	.....	.....
5/16	0.0035	0.0035	0.0030	0.0025	0.0015	0.0015	0.0010	0.0010	0.0010	0.0005	.....	.....	.....	.....
3/8	0.0040	0.0040	0.0035	0.0030	0.0020	0.0020	0.0015	0.0015	0.0015	0.0010	0.0005	0.0005	0.0005	.....
7/16	0.0045	0.0045	0.0040	0.0035	0.0030	0.0025	0.0020	0.0020	0.0020	0.0015	0.0010	0.0010	0.0010	.....
1/2	0.0048	0.0048	0.0045	0.0040	0.0035	0.0030	0.0025	0.0025	0.0025	0.0020	0.0015	0.0015	0.0015	0.0005
5/8	0.0050	0.0050	0.0048	0.0043	0.0040	0.0035	0.0030	0.0030	0.0028	0.0025	0.0020	0.0020	0.0018	0.0010
3/4	0.0055	0.0052	0.0050	0.0045	0.0043	0.0040	0.0035	0.0035	0.0030	0.0028	0.0025	0.0022	0.0020	0.0013
7/8	0.0058	0.0055	0.0052	0.0048	0.0045	0.0043	0.0040	0.0038	0.0032	0.0030	0.0028	0.0025	0.0022	0.0015
1	0.0060	0.0058	0.0054	0.0050	0.0048	0.0047	0.0043	0.0040	0.0035	0.0032	0.0030	0.0028	0.0025	0.0018

Copyright 2004, Industrial Press, Inc., New York, NY

THREAD GRINDING

Thread grinding is employed for precision tool and gage work and also in producing certain classes of threaded parts.

Thread grinding may be utilized 1) because of the accuracy and finish obtained; 2) hardness of material to be threaded; and 3) economy in grinding certain classes of screw threads when using modern machines, wheels, and thread-grinding oils.

In some cases pre-cut threads are finished by grinding; but usually, threads are ground "from the solid," being formed entirely by the grinding process. Examples of work include thread gages and taps of steel and tungsten carbide, hobs, worms, lead-screws, adjusting or traversing screws, alloy steel studs, etc. Grinding is applied to external, internal, straight, and tapering threads, and to various thread forms.

Accuracy Obtainable by Thread Grinding.— With single-edge or single-ribbed wheels it is possible to grind threads on gages to a degree of accuracy that requires but very little lapping to produce a so-called "master" thread gage. As far as lead is concerned, some thread grinding machine manufacturers guarantee to hold the lead within 0.0001 inch per inch of thread; and while it is not guaranteed that a higher degree of accuracy for lead is obtainable, it is known that threads have been ground to closer tolerances than this on the lead. Pitch diameter accuracies for either Class 3 or Class 4 fits are obtainable according to the grinding method used; with single-edge wheels, the thread angle can be ground to an accuracy of within two or three minutes in half the angle.

Wheels for Thread Grinding.— The wheels used for steel have an aluminous abrasive and, ordinarily, either a resinoid bond or a vitrified bond. The general rule is to use resinoid wheels when extreme tolerances are not required, and it is desirable to form the thread with a minimum number of passes, as in grinding threaded machine parts, such as studs, adjusting screws which are not calibrated, and for some classes of taps. *Resinoid wheels,* as a rule, will hold a fine edge longer than a vitrified wheel but they are more flexible and, consequently, less suitable for accurate work, especially when there is lateral grinding pressure that causes wheel deflection. *Vitrified wheels* are utilized for obtaining extreme accuracy in thread form and lead because they are very rigid and not easily deflected by side pressure in grinding. This rigidity is especially important in grinding pre-cut threads on such work as gages, taps and lead-screws. The progressive lead errors in long lead-screws, for example, might cause an increasing lateral pressure that would deflect a resinoid wheel. Vitrified wheels are also recommended for internal grinding.

Diamond Wheels: Diamond wheels set in a rubber or plastic bond are also used for thread grinding, especially for grinding threads in carbide materials and in other hardened alloys. Thread grinding is now being done successfully on a commercial basis on both taps and gages made from carbides. Gear hobs made from carbides have also been tested with successful results. Diamond wheels are dressed by means of silicon-carbide grinding wheels which travel past the diamond-wheel thread form at the angle required for the flanks of the thread to be ground. The action of the dressing wheels is, perhaps, best described as a "scrubbing" of the bond which holds the diamond grits. Obviously, the silicon-carbide wheels do not dress the diamonds, but they loosen the bond until the diamonds not wanted drop out.

Thread Grinding with Single-Edge Wheel.— With this type of wheel, the edge is trued to the cross-sectional shape of the thread groove. The wheel, when new, may have a diameter of 18 or 20 inches and, when grinding a thread, the wheel is inclined to align it with the thread groove. On some machines, lead variations are obtained by means of change-gears which transmit motion from the work-driving spindle to the lead-screw. Other machines are so designed that a lead-screw is selected to suit the lead of thread to be ground and transmits motion directly to the work-driving spindle.

Copyright 2004, Industrial Press, Inc., New York, NY

Wheels with Edges for Roughing and Finishing.— The "three-ribbed" type of wheel has a roughing edge or rib which removes about two-thirds of the metal. This is followed by an intermediate rib which leaves about 0.005 inch for the third or finishing rib. The accuracy obtained with this triple-edge type compares with that of a single-edge wheel, which means that it may be used for the greatest accuracy obtainable in thread grinding.

When the accuracy required makes it necessary, this wheel can be inclined to the helix angle of the thread, the same as is the single-edge wheel.

The three-ribbed wheel is recommended not only for precision work but for grinding threads which are too long for the multi-ribbed wheel referred to later. It is also well adapted to tap grinding, because it is possible to dress a portion of the wheel adjacent to the finish rib for the purpose of grinding the outside diameter of the thread, as indicated in Fig. 1. Furthermore, the wheel can be dressed for grinding or relieving both crests and flanks at the same time.



Fig. 1. Wheel with Edges for Roughing and Finishing



Fig. 2. Multi-ribbed Type of Thread-grinding Wheel



Fig. 3. Alternate-ribbed Wheel for Grinding the Finer Pitches

Multi-ribbed Wheels.— This type of wheel is employed when rapid production is more important than extreme accuracy, which means that it is intended primarily for the grinding of duplicate parts in manufacturing. A wheel 1¼ to 2 inches wide has formed upon its face a series of annular thread-shaped ridges (see Fig. 2); hence, if the length of the thread is not greater than the wheel width, a thread may be ground in one work revolution plus about one-half revolution for feeding in and withdrawing the wheel. The principle of operation is the same as that of thread milling with a multiple type cutter. This type of wheel is not inclined to the lead angle. To obtain a Class 3 fit, the lead angle should not exceed 4 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

It is not practicable to use this form of wheel on thread pitches where the root is less than 0.007 inch wide, because of difficulties in wheel dressing. When this method can be applied, it is the fastest means known of producing threads in hardened materials. It is not recommended, however, that thread gages, taps, and work of this character be ground with multi-ribbed wheels. The single-ribbed wheel has a definite field for accurate, small-lot production.

It is necessary, in multi-ribbed grinding, to use more horsepower than is required for single-ribbed wheel grinding. Coarse threads, in particular, may require a wheel motor with two or three times more horsepower than would be necessary for grinding with a single-ribbed wheel.

Alternate-ribbed Wheel for Fine Pitches.— The spacing of ribs on this type of wheel (Fig. 3) equals twice the pitch, so that during the first revolution every other thread groove section is being ground; consequently, about two and one-half work revolutions are required for grinding a complete thread, but the better distribution of cooling oil and resulting increase in work speeds makes this wheel very efficient. This alternate-type of wheel is adapted for grinding threads of fine pitch. Since these wheels cannot be tipped to the helix angle of the thread, they are not recommended for anything closer than Class 3 fits. The "three-ribbed" wheels referred to in a previous paragraph are also made in the alternate type for the finer pitches.

Grinding Threads "from the Solid.".— The process of forming threads entirely by grinding, or without preliminary cutting, is applied both in the manufacture of certain classes of threaded parts and also in the production of precision tools, such as taps and thread gages. For example, in airplane engine manufacture, certain parts are heat-treated and then the threads are ground "from the solid," thus eliminating distortion. Minute cracks are sometimes found at the roots of threads that were cut and then hardened, or ground from the solid. Steel threads of coarse pitch that are to be surface hardened, may be rough threaded by cutting, then hardened and finally corrected by grinding. Many ground thread taps are produced by grinding from the solid after heat-treatment. Hardening high-speed steel taps before the thread is formed will make sure there are no narrow or delicate crests to interfere with the application of the high temperature required for uniform hardness and the best steel structure.

Number of Wheel Passes.— The number of cuts or passes for grinding from the solid depends upon the type of wheel and accuracy required. In general, threads of 12 or 14 per inch and finer may be ground in one pass of a single-edge wheel unless the "unwrapped" thread length is much greater than normal. Unwrapped length = pitch circumference × total number of thread turns, approximately. For example, a thread gage $1\frac{1}{4}$ inches long with 24 threads per inch would have an unwrapped length equal to 30 × pitch circumference. (If more convenient, outside circumference may be used instead of pitch circumference.) Assume that there are 6 or 7 feet of unwrapped length on a screw thread having 12 threads per inch. In this case, one pass might be sufficient for a Class 3 fit, whereas two passes might be recommended for a Class 4 fit. When two passes are required, too deep a roughing cut may break down the narrow edge of the wheel. To prevent this, try a roughing cut depth equal to about two-thirds the total thread depth, thus leaving one-third for the finishing cut.

Wheel and Work Rotation.— When a screw thread, on the side being ground, is moving *upward* or *against* the grinding wheel rotation, less heat is generated and the grinding operation is more efficient than when wheel and work are moving in the same direction on the grinding side; however, to avoid running a machine idle during its return stroke, many screw threads are ground during both the forward and return traversing movements, by reversing the work rotation at the end of the forward stroke. For this reason, thread grinders generally are equipped so that both forward and return work speeds may be changed; they may also be designed to accelerate the return movement when grinding in one direction only.

Copyright 2004, Industrial Press, Inc., New York, NY

Wheel Speeds.— Wheel speeds should always be limited to the maximum specified on the wheel by the manufacturer. According to the American National Standard Safety Code, resinoid and vitrified wheels are limited to 12,000 surface feet per minute; however, according to Norton Co., the most efficient speeds are from 9,000 to 10,000 for resinoid wheels and 7,500 to 9,500 for vitrified wheels. Only tested wheels recommended by the wheel manufacturer should be used. After a suitable surface speed has been established, it should be maintained by increasing the rpm of the wheel, as the latter is reduced in diameter by wear.

Since thread grinding wheels work close to the limit of their stock-removing capacity, some adjustment of the wheel or work speed may be required to get the best results. If the wheel speed is too slow for a given job and excessive heat is generated, try an increase in speed, assuming that such increase is within the safety limits. If the wheel is too soft and the edge wears excessively, again an increase in wheel speed will give the effect of a harder wheel and result in better form-retaining qualities.

Work Speeds.— The work speed usually ranges from 3 to 10 feet per minute. In grinding with a comparatively heavy feed, and a mininum number of passes, the speed may not exceed 2½ or 3 feet per minute. If very light feeds are employed, as in grinding hardened high-speed steel, the work speed may be much higher than 3 feet per minute and should be determined by test. If excessive heat is generated by removing stock too rapidly, a work speed reduction is one remedy. If a wheel is working below its normal capacity, an increase in work speed would prevent dulling of the grains and reduce the tendency to heat or "burn" the work. An increase in work speed and reduction in feed may also be employed to prevent burning while grinding hardened steel.

Truing Grinding Wheels.— Thread grinding wheels are trued both to maintain the required thread form and also an efficient grinding surface. Thread grinders ordinarily are equipped with precision truing devices which function automatically. One type automatically dresses the wheel and also compensates for the slight amount removed in dressing, thus automatically maintaining size control of the work. While truing the wheel, a small amount of grinding oil should be used to reduce diamond wear. Light truing cuts are advisable, especially in truing resinoid wheels which may be deflected by excessive truing pressure. A master former for controlling the path followed by the truing diamond may require a modified profile to prevent distortion of the thread form, especially when the lead angles are comparatively large. Such modification usually is not required for 60-degree threads when the pitches for a given diameter are standard because then the resulting lead angles are less than 4½ degrees. In grinding Acme threads or 29-degree worm threads having lead angles greater than 4 or 5 degrees, modified formers may be required to prevent a bulge in the thread profile. The highest point of this bulge is approximately at the pitch line. A bulge of about 0.001 inch may be within allowable limits on some commercial worms but precision worms for gear hobbers, etc., require straight flanks in the axial plane.

Crushing Method: Thread grinding wheels are also dressed or formed by the crushing method, which is used in connection with some types of thread grinding machines. When this method is used, the annular ridge or ridges on the wheel are formed by a hardened steel cylindrical dresser or crusher. The crusher has a series of smooth annular ridges which are shaped and spaced like the thread that is to be ground. During the wheel dressing operation, the crusher is positively driven instead of the grinding wheel, and the ridges on the wheel face are formed by the rotating crusher being forced inward.

Wheel Hardness or Grade.— Wheel hardness or grade selection is based upon a compromise between efficient cutting and durability of the grinding edge. Grade selection depends on the bond and the character of the work. The following general recommendations are based upon Norton grading.

Vitrified wheels usually range from J to M, and resinoid wheels from R to U. For heat-treated screws or studs and the Unified Standard Thread, try the following. For 8 to 12

Copyright 2004, Industrial Press, Inc., New York, NY

threads per inch, grade S resinoid wheel; for 14 to 20 threads per inch, grade T resinoid; for 24 threads per inch and finer, grades T or U resinoid. For high-speed steel taps 4 to 12 threads per inch, grade J vitrified or S resinoid; 14 to 20 threads per inch, grade K vitrified or T resinoid; 24 to 36 threads per inch, grade M vitrified or T resinoid.

Grain Size.— A thread grinding wheel usually operates close to its maximum stock-removing capacity, and the narrow edge which forms the root of the thread is the most vulnerable part. In grain selection, the general rule is to use the coarsest grained wheel that will hold its form while grinding a reasonable amount of work. Pitch of thread and quality of finish are two governing factors. Thus, to obtain an exceptionally fine finish, the grain size might be smaller than is needed to retain the edge profile. The usual grain sizes range from 120 to 150. For heat-treated screws and studs with Unified Standard Threads, 100 to 180 is the usual range. For precision screw threads of very fine pitch, the grain size may range from 220 to 320. For high-speed steel taps, the usual range is from 150 to 180 for Unified Standard Threads, and from 80 to 150 for pre-cut Acme threads.

Thread Grinding by Centerless Method.— Screw threads may be ground from the solid by the centerless method. A centerless thread grinder is similar in its operating principle to a centerless grinder designed for general work, in that it has a grinding wheel, a regulating or feed wheel (with speed adjustments), and a work-rest. Adjustments are provided to accommodate work of different sizes and for varying the rates of feed. The grinding wheel is a multi-ribbed type, being a series of annular ridges across the face. These ridges conform in pitch and profile with the thread to be ground. The grinding wheel is inclined to suit the helix or lead angle of the thread. In grinding threads on such work as socket type setscrews, the blanks are fed automatically and passed between the grinding and regulating wheels in a continuous stream. To illustrate production possibilities, hardened socket setscrews of $\frac{1}{4}$20 size may be ground from the solid at the rate of 60 to 70 per minute and with the wheel operating continuously for 8 hours without redressing. The lead errors of centerless ground screw threads may be limited to 0.0005 inch per inch or even less by reducing the production rate. The pitch diameter tolerances are within 0.0002 to 0.0003 inch of the basic size. The grain size for the wheel is selected with reference to the pitch of the thread, the following sizes being recommended: For 11 to 13 threads per inch, 150; for 16 threads per inch, 180; for 18 to 20 threads per inch, 220; for 24 to 28 threads per inch, 320; for 40 threads per inch, 400.

Copyright 2004, Industrial Press, Inc., New York, NY

THREAD MILLING

Single-cutter Method.— Usually, when a single point cutter is used, the axis of the cutter is inclined an amount equal to the lead angle of the screw thread, in order to locate the cutter in line with the thread groove at the point where the cutting action takes place. Tangent of lead angle = lead of screw thread ÷ pitch circumference of screw.

The helical thread groove is generated by making as many turns around the workpiece diameter as there are pitches in the length of thread to be cut. For example, a 16-pitch thread, 1 inch long, would require 16 turns of the cutter around the work. The single cutter process is especially applicable to the milling of large screw threads of coarse pitch, and either single or multiple threads.

The cutter should revolve as fast as possible without dulling the cutting edges excessively, in order to mill a smooth thread and prevent the unevenness that would result with a slow-moving cutter, on account of the tooth spaces. As the cutter rotates, the part on which a thread is to be milled is also revolved, but at a very slow rate (a few inches per minute), since this rotation of the work is practically a feeding movement. The cutter is ordinarily set to the full depth of the thread groove and finishes a single thread in one passage, although deep threads of coarse pitch may require two or even three cuts. For fine pitches and short threads, the multiple-cutter method (described in the next paragraph) usually is preferable, because it is more rapid. The milling of taper screw threads may be done on a single-cutter type of machine by traversing the cutter laterally as it feeds along in a lengthwise direction, the same as when using a taper attachment on a lathe.

Multiple-cutter Method.— The multiple cutter for thread milling is practically a series of single cutters, although formed of one solid piece of steel, at least so far as the cutter proper is concerned. The rows of teeth do not lie in a helical path, like the teeth of a hob or tap, but they are annular or without lead. If the cutter had helical teeth the same as a gear hob, it would have to be geared to revolve in a certain fixed ratio with the screw being milled, but a cutter having annular teeth may rotate at any desired cutting speed, while the screw blank is rotated slowly to provide a suitable rate of feed. (The multiple thread milling cutters used are frequently called "hobs," but the term hob should be applied only to cutters having a helical row of teeth like a gear-cutting hob.)

The object in using a multiple cutter instead of a single cutter is to finish a screw thread complete in approximately one revolution of the work, a slight amount of over-travel being allowed to insure milling the thread to the full depth where the end of cut joins the starting point. The cutter which is at least one and one half or two threads or pitches wider than the thread to be milled, is fed in to the full thread depth and then either the cutter or screw blank is moved in a lengthwise direction a distance equal to the lead of the thread during one revolution of the work.

The multiple cutter is used for milling comparatively short threads and coarse, medium or fine pitches. The accompanying illustration shows typical examples of external and internal work for which the multiple-cutter type of thread milling has proved very efficient, although its usefulness is not confined to shoulder work and "blind" holes.

In using multiple cutters either for internal or external thread milling, the axis of the cutter is set parallel with the axis of the work, instead of inclining the cutter to suit the lead angle of the thread, as when using a single cutter. Theoretically, this is not the correct position for a cutter, since each cutting edge is revolving in a plane at right angles to the screw's axis while milling a thread groove of helical form. However, as a general rule, interference between the cutter and the thread, does not result a decided change in the standard thread form.

Usually the deviation is very slight and may be disregarded except when milling threads which incline considerably relative to the axis like a thread of multiple form and large lead angle. Multiple cutters are suitable for external threads having lead angles under 3½

Copyright 2004, Industrial Press, Inc., New York, NY

degrees and for internal threads having lead angles under 2½ degrees. Threads which have steeper sides or smaller included angles than the American Standard or Whitworth forms have greater limitations on the maximum helix angle and may have to be milled with a single point cutter tilted to the helix angle, assuming that the milling process is preferable to other methods. For instance, in milling an Acme thread which has an included angle between the sides of 29 degrees, there might be considerable interference if a multiple cutter were used, unless the screw thread diameter were large enough in proportion to the pitch to prevent such interference. If an attempt were made to mill a square thread with a multiple cutter, the results would be unsatisfactory owing to the interference.



Examples of External and Internal Thread Milling with a Multiple Thread Milling Cutter

Interference between the cutter and work is more pronounced when milling internal threads, because the cutter does not clear itself so well. It is preferable to use as small a cutter as practicable, either for internal or external work, not only to avoid interference, but to reduce the strain on the driving mechanism. Some thread milling cutters, known as "topping cutters," are made for milling the outside diameter of the thread as well as the angular sides and root, but most are made non-tapping.

Planetary Method.— The planetary method of thread milling is similar in principle to planetary milling. The part to be threaded is held stationary and the thread milling cutter, while revolving about its own axis, is given a planetary movement around the work in order to mill the thread in one planetary revolution. The machine spindle and the cutter which is held by it is moved longitudinally for thread milling, an amount equal to the thread lead during one planetary revolution. This operation is applicable to both internal and external threads. Other advantages: Thread milling is frequently accompanied by milling operations on other adjoining surfaces, and may be performed with conventional and planetary methods. For example, a machine may be used for milling a screw thread and a concentric cylindrical surface simultaneously. When the milling operation begins, the cutter-spindle feeds the cutter in to the right depth and the planetary movement then begins, thus milling the thread and the cylindrical surface. Thin sharp starting edges are eliminated on threads milled by this method and the thread begins with a smooth gradual approach. One design of machine will mill internal and external threads simultaneously. These threads may be of the same hand or one may be right hand and the other left hand. The threads may also be either of the same pitch or of a different pitch, and either straight or tapered.

Classes of Work for Thread Milling Machines.— Thread milling machines are used in preference to lathes or taps and dies for certain threading operations.

Copyright 2004, Industrial Press, Inc., New York, NY

There are four general reasons why a thread milling machine may be preferred: 1) Because the pitch of the thread is too coarse for cutting with a die; 2) because the milling process is more efficient than using a single-point tool in a lathe; 3) to secure a smoother and more accurate thread than would be obtained with a tap or die; and 4) because the thread is so located relative to a shoulder or other surface that the milling method is superior, if not the only practicable way.

A thread milling machine having a single cutter is especially adapted for coarse pitches, multiple-threaded screws, or any form or size of thread requiring the removal of a relatively large amount of metal, particularly if the pitch of the thread is large in proportion to the screw diameter, since the torsional strain due to the milling process is relatively small. Thread milling often gives a higher rate of production, and a thread is usually finished by means of a single turn of the multiple thread milling cutter around the thread diameter. The multiple-cutter type of thread milling machine frequently comes into competition with dies and taps, and especially self-opening dies and collapsing taps. The use of a multiple cutter is desirable when a thread must be cut close to a shoulder or to the bottom of a shallow recess, although the usefulness of the multiple cutter is not confined to shoulder work and "blind" holes.

Maximum Pitches of Die-cut Threads.— Dies of special design could be constructed for practically any pitch, if the screw blank were strong enough to resist the cutting strains and the size and cost of the die were immaterial; but, as a general rule, when the pitch is coarser than four or five threads per inch, the difficulty of cutting threads with dies increases rapidly, although in a few cases some dies are used successfully on screw threads having two or three threads per inch or less. Much depends upon the design of the die, the finish or smoothness required, and the relation between the pitch of the thread and the diameter of the screw. When the screw diameter is relatively small in proportion to the pitch, there may be considerable distortion due to the twisting strains set up when the thread is being cut. If the number of threads per inch is only one or two less than the standard number for a given diameter, a screw blank ordinarily will be strong enough to permit the use of a die.

Changing Pitch of Screw Thread Slightly.— A very slight change in the pitch of a screw thread may be necessary as, for example, when the pitch of a tap is increased a small amount to compensate for shrinkage in hardening. One method of obtaining slight variations in pitch is by means of a taper attachment. This attachment is set at an angle and the work is located at the same angle by adjusting the tailstock center. The result is that the tool follows an angular path relative to the movement of the carriage and, consequently, the pitch of the thread is increased slightly, the amount depending upon the angle to which the work and taper attachment are set. The cosine of this angle, for obtaining a given increase in pitch, equals the standard pitch (which would be obtained with the lathe used in the regular way) divided by the increased pitch necessary to compensate for shrinkage.

Example: If the pitch of a $\frac{3}{4}$-inch American standard screw is to be increased from 0.100 to 0.1005, the cosine of the angle to which the taper attachment and work should be set is found as follows:

$$\text{Cosine of required angle} = \frac{0.100}{0.1005} = 0.9950$$

which is the cosine of 5 degrees 45 minutes, nearly.

Change Gears for Helical Milling

Lead of a Milling Machine.— If gears with an equal number of teeth are placed on the table feed-screw and the worm-gear stud, then the *lead of the milling machine* is the distance the table will travel while the index spindle makes one complete revolution. This distance is a constant used in figuring the change gears.

Copyright 2004, Industrial Press, Inc., New York, NY

The lead of a helix or "spiral" is the distance, measured along the axis of the work, in which the helix makes one full turn around the work. The lead of the milling machine may, therefore, also be expressed as the lead of the helix that will be cut when gears with an equal number of teeth are placed on the feed-screw and the worm-gear stud, and an idler of suitable size is interposed between the gears.

Rule: To find the lead of a milling machine, place equal gears on the worm-gear stud and on the feed-screw, and multiply the number of revolutions made by the feed-screw to produce one revolution of the index head spindle, by the lead of the thread on the feed-screw. Expressing the rule given as a formula:

$$\text{lead of milling machine} = \text{rev. of feed-screw for one revolution of index spindle with equal gears} \times \text{lead of feed-screw}$$

Assume that it is necessary to make 40 revolutions of the feed-screw to turn the index head spindle one complete revolution, when the gears are equal, and that the lead of the thread on the feed-screw of the milling machine is $\frac{1}{4}$ inch; then the lead of the machine equals $40 \times \frac{1}{4}$ inch = 10 inches.

Change Gears for Helical Milling.— To find the change gears to be used in the compound train of gears for helical milling, place the lead of the helix to be cut in the numerator and the lead of the milling machine in the denominator of a fraction; divide numerator and denominator into two factors each; and multiply each "pair" of factors by the *same* number until suitable numbers of teeth for the change gears are obtained. (One factor in the numerator and one in the denominator are considered as one "pair" in this calculation.)

Example: Assume that the lead of a machine is 10 inches, and that a helix having a 48-inch lead is to be cut. Following the method explained:

$$\frac{48}{10} = \frac{6 \times 8}{2 \times 5} = \frac{(6 \times 12) \times (8 \times 8)}{(2 \times 12) \times (5 \times 8)} = \frac{72 \times 64}{24 \times 40}$$

The gear having 72 teeth is placed on the worm-gear stud and meshes with the 24-tooth gear on the intermediate stud. On the same intermediate stud is then placed the gear having 64 teeth, which is driven by the gear having 40 teeth placed on the feed-screw. This makes the gears having 72 and 64 teeth the driven gears, and the gears having 24 and 40 teeth the driving gears. In general, for compound gearing, the following formula may be used:

$$\frac{\text{lead of helix to be cut}}{\text{lead of machine}} = \frac{\text{product of driven gears}}{\text{product of driving gears}}$$

Short-lead Milling.— If the lead to be milled is exceptionally short, the drive may be direct from the table feed-screw to the dividing head spindle to avoid excessive load on feed-screw and change-gears. If the table feed-screw has 4 threads per inch (usual standard), then

$$\text{Change-gear ratio} = \frac{\text{Lead to be milled}}{0.25} = \frac{\text{Driven gears}}{\text{Driving gears}}$$

For indexing, the number of teeth on the spindle change-gear should be some multiple of the number of divisions required, to permit indexing by disengaging and turning the gear.

Helix.— A helix is a curve generated by a point moving about a cylindrical surface (real or imaginary) at a constant rate in the direction of the cylinder's axis. The curvature of a screw thread is one common example of a helical curve.

Lead of Helix: The lead of a helix is the distance that it advances in an axial direction, in one complete turn about the cylindrical surface. To illustrate, the lead of a screw thread

Copyright 2004, Industrial Press, Inc., New York, NY

equals the distance that a thread advances in one turn; it also equals the distance that a nut would advance in one turn.

Development of Helix: If one turn of a helical curve were unrolled onto a plane surface (as shown by diagram), the helix would become a straight line forming the hypotenuse of a right angle triangle. The length of one side of this triangle would equal the circumference of the cylinder with which the helix coincides, and the length of the other side of the triangle would equal the lead of the helix.



Helix Angles.— The triangular development of a helix has one angle *A* subtended by the circumference of the cylinder, and another angle *B* subtended by the lead of the helix. The term "helix angle" applies to angle *A*. For example, the helix angle of a helical gear, according to the general usage of the term, is always angle *A*, because this is the angle used in helical gear-designing formulas. Helix angle *A* would also be applied in milling the helical teeth of cutters, reamers, etc. Angle *A* of a gear or cutter tooth is a measure of its inclination relative to the axis of the gear or cutter.

Lead Angle: Angle *B* is applied to screw threads and worm threads and is referred to as the lead angle of the screw thread or worm. This angle *B* is a measure of the inclination of a screw thread from a plane that is perpendicular to the screw thread axis. Angle *B* is called the "lead angle" because it is subtended by the lead of the thread, and to distinguish it from the term "helix angle" as applied to helical gears.

Finding Helix Angle of Helical Gear: A helical gear tooth has an infinite number of helix angles, but the angle at the pitch diameter or mid-working depth is the one required in gear designing and gear cutting. This angle *A*, relative to the axis of the gear, is found as follows:

$$\text{tan helix angle} = \frac{3.1416 \times \text{pitch diameter of gear}}{\text{Lead of gear tooth}}$$

Finding Lead Angle of Screw Thread: The lead or helix angle at the pitch diameter of a screw thread usually is required when, for example, a thread milling cutter must be aligned with the thread. This angle measured from a plane perpendicular to the screw thread axis, is found as follows:

$$\text{tan lead angle} = \frac{\text{Lead of screw thread}}{3.1416 \times \text{pitch diameter of screw thread}}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—0.670 Inch to 2.658 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
0.670	24	86	24	100	1.711	28	72	44	100	2.182	24	44	40	100
0.781	24	86	28	100	1.714	24	56	40	100	2.188	24	48	28	64
0.800	24	72	24	100	1.744	24	64	40	86	2.193	24	56	44	86
0.893	24	86	32	100	1.745	24	44	32	100	2.200	24	48	44	100
0.930	24	72	24	86	1.750	28	64	40	100	2.222	24	48	32	72
1.029	24	56	24	100	1.776	24	44	28	86	2.233	40	86	48	100
1.042	28	86	32	100	1.778	32	72	40	100	2.238	28	64	44	86
1.047	24	64	24	86	1.786	24	86	64	100	2.240	28	40	32	100
1.050	24	64	28	100	1.800	24	64	48	100	2.250	24	40	24	64
1.067	24	72	32	100	1.809	28	72	40	86	2.274	32	72	44	86
1.085	24	72	28	86	1.818	24	44	24	72	2.286	32	56	40	100
1.116	24	86	40	100	1.823	28	86	56	100	2.292	24	64	44	72
1.196	24	56	24	86	1.860	28	56	32	86	2.326	32	64	40	86
1.200	24	48	24	100	1.861	24	72	48	86	2.333	28	48	40	100
1.221	24	64	28	86	1.867	28	48	32	100	2.338	24	44	24	56
1.228	24	86	44	100	1.875	24	48	24	64	2.344	28	86	72	100
1.240	24	72	32	86	1.886	24	56	44	100	2.368	28	44	32	86
1.250	24	64	24	72	1.905	24	56	32	72	2.381	32	86	64	100
1.302	28	86	40	100	1.919	24	64	44	86	2.386	24	44	28	64
1.309	24	44	24	100	1.920	24	40	32	100	2.392	24	56	48	86
1.333	24	72	40	100	1.925	28	64	44	100	2.400	28	56	48	100
1.340	24	86	48	100	1.944	24	48	28	72	2.424	24	44	32	72
1.371	24	56	32	100	1.954	24	40	28	86	2.431	28	64	40	72
1.395	24	48	24	86	1.956	32	72	44	100	2.442	24	32	28	86
1.400	24	48	28	100	1.990	28	72	44	86	2.445	40	72	44	100
1.429	24	56	24	72	1.993	24	56	40	86	2.450	28	64	56	100
1.440	24	40	24	100	2.000	24	40	24	72	2.456	44	86	48	100
1.458	24	64	28	72	2.009	24	86	72	100	2.481	32	72	48	86
1.467	24	72	44	100	2.030	24	44	32	86	2.489	32	72	56	100
1.488	32	86	40	100	2.035	28	64	40	86	2.500	24	48	28	56
1.500	24	64	40	100	2.036	28	44	32	100	2.514	32	56	44	100
1.522	24	44	24	86	2.045	24	44	24	64	2.532	28	72	56	86
1.550	24	72	40	86	2.047	40	86	44	100	2.537	24	44	40	86
1.563	24	86	56	100	2.057	24	28	24	100	2.546	28	44	40	100
1.595	24	56	32	86	2.067	32	72	40	86	2.558	32	64	44	86
1.600	24	48	32	100	2.083	24	64	40	72	2.567	28	48	44	100
1.607	24	56	24	64	2.084	28	86	64	100	2.571	24	40	24	56
1.628	24	48	28	86	2.093	24	64	48	86	2.593	28	48	32	72
1.637	32	86	44	100	2.100	24	64	56	100	2.605	28	40	32	86
1.650	24	64	44	100	2.121	24	44	28	72	2.618	24	44	48	100
1.667	24	56	28	72	2.133	24	72	64	100	2.619	24	56	44	72
1.674	24	40	24	86	2.143	24	56	32	64	2.625	24	40	28	64
1.680	24	40	28	100	2.171	24	72	56	86	2.640	24	40	44	100
1.706	24	72	44	86	2.178	28	72	56	100	2.658	32	56	40	86

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—2.667 Inches to 4.040 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
2.667	40	72	48	100	3.140	24	86	72	64	3.588	72	56	24	86
2.674	28	64	44	72	3.143	40	56	44	100	3.600	72	48	24	100
2.678	24	56	40	64	3.150	28	100	72	64	3.618	56	72	40	86
2.679	32	86	72	100	3.175	32	56	40	72	3.636	24	44	32	48
2.700	24	64	72	100	3.182	28	44	32	64	3.637	48	44	24	72
2.713	28	48	40	86	3.189	32	56	48	86	3.646	40	48	28	64
2.727	24	44	32	64	3.190	24	86	64	56	3.655	40	56	44	86
2.743	24	56	64	100	3.198	40	64	44	86	3.657	64	56	32	100
2.750	40	64	44	100	3.200	28	100	64	56	3.663	72	64	28	86
2.778	32	64	40	72	3.214	24	56	48	64	3.667	40	48	44	100
2.791	28	56	48	86	3.225	24	100	86	64	3.673	24	28	24	56
2.800	24	24	28	100	3.241	28	48	40	72	3.684	44	86	72	100
2.812	24	32	24	64	3.256	24	24	28	86	3.686	86	56	24	100
2.828	28	44	32	72	3.267	28	48	56	100	3.704	32	48	40	72
2.843	40	72	44	86	3.273	24	40	24	44	3.721	24	24	32	86
2.845	32	72	64	100	3.275	44	86	64	100	3.733	48	72	56	100
2.849	28	64	56	86	3.281	24	32	28	64	3.750	24	32	24	48
2.857	24	48	32	56	3.300	44	64	48	100	3.763	86	64	28	100
2.865	44	86	56	100	3.308	32	72	64	86	3.771	44	56	48	100
2.867	86	72	24	100	3.333	32	64	48	72	3.772	24	28	44	100
2.880	24	40	48	100	3.345	28	100	86	72	3.799	56	48	28	86
2.894	28	72	64	86	3.349	40	86	72	100	3.809	24	28	32	72
2.909	32	44	40	100	3.360	56	40	24	100	3.810	64	56	24	72
2.917	24	64	56	72	3.383	32	44	40	86	3.818	24	40	28	44
2.924	32	56	44	86	3.403	28	64	56	72	3.819	40	64	44	72
2.933	44	72	48	100	3.409	24	44	40	64	3.822	86	72	32	100
2.934	32	48	44	100	3.411	32	48	44	86	3.837	24	32	44	86
2.946	24	56	44	64	3.422	44	72	56	100	3.840	64	40	24	100
2.960	28	44	40	86	3.428	24	40	32	56	3.850	44	64	56	100
2.977	40	86	64	100	3.429	40	28	24	100	3.876	24	72	100	86
2.984	28	48	44	86	3.438	24	48	44	64	3.889	32	64	56	72
3.000	24	40	28	56	3.488	40	64	48	86	3.896	24	44	40	56
3.030	24	44	40	72	3.491	64	44	24	100	3.907	56	40	24	86
3.044	24	44	48	86	3.492	32	56	44	72	3.911	44	72	64	100
3.055	28	44	48	100	3.500	40	64	56	100	3.920	28	40	56	100
3.056	32	64	44	72	3.520	32	40	44	100	3.927	72	44	24	100
3.070	24	40	44	86	3.535	28	44	40	72	3.929	32	56	44	64
3.080	28	40	44	100	3.552	56	44	24	86	3.977	28	44	40	64
3.086	24	56	72	100	3.556	40	72	64	100	3.979	44	72	56	86
3.101	40	72	48	86	3.564	56	44	28	100	3.987	24	28	40	86
3.111	28	40	32	72	3.565	28	48	44	72	4.000	24	40	32	48
3.117	24	44	32	56	3.571	24	48	40	56	4.011	28	48	44	64
3.125	28	56	40	64	3.572	48	86	64	100	4.019	72	86	48	100
3.126	48	86	56	100	3.582	44	40	28	86	4.040	32	44	40	72

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—4.059 Inches to 5.568 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
4.059	32	44	48	86	4.567	72	44	24	86	5.105	28	48	56	64
4.060	64	44	24	86	4.572	40	56	64	100	5.116	44	24	24	86
4.070	28	32	40	86	4.582	72	44	28	100	5.119	86	56	24	72
4.073	64	44	28	100	4.583	44	64	48	72	5.120	64	40	32	100
4.074	32	48	44	72	4.584	32	48	44	64	5.133	56	48	44	100
4.091	24	44	48	64	4.651	40	24	24	86	5.134	44	24	28	100
4.093	32	40	44	86	4.655	64	44	32	100	5.142	72	56	40	100
4.114	48	28	24	100	4.667	28	40	32	48	5.143	24	28	24	40
4.125	24	40	44	64	4.675	24	28	24	44	5.156	44	32	24	64
4.135	40	72	64	86	4.687	40	32	24	64	5.160	86	40	24	100
4.144	56	44	28	86	4.688	56	86	72	100	5.168	100	72	32	86
4.167	28	48	40	56	4.691	86	44	24	100	5.185	28	24	32	72
4.186	72	64	32	86	4.714	44	40	24	56	5.186	64	48	28	72
4.200	48	64	56	100	4.736	64	44	28	86	5.195	32	44	40	56
4.242	28	44	32	48	4.762	40	28	24	72	5.209	100	64	24	72
4.253	64	56	32	86	4.773	24	32	28	44	5.210	64	40	28	86
4.264	40	48	44	86	4.778	86	72	40	100	5.226	86	64	28	72
4.267	64	48	32	100	4.784	72	56	32	86	5.233	72	64	40	86
4.278	28	40	44	72	4.785	48	28	24	86	5.236	72	44	32	100
4.286	24	28	24	48	4.800	48	24	24	100	5.238	44	28	24	72
4.300	86	56	28	100	4.813	44	40	28	64	5.250	24	32	28	40
4.320	72	40	24	100	4.821	72	56	24	64	5.256	86	72	44	100
4.341	48	72	56	86	4.849	32	44	48	72	5.280	48	40	44	100
4.342	64	48	28	86	4.861	40	32	28	72	5.303	28	44	40	48
4.361	100	64	24	86	4.884	48	64	56	86	5.316	40	28	32	86
4.363	24	40	32	44	4.889	32	40	44	72	5.328	72	44	28	86
4.364	40	44	48	100	4.898	24	28	32	56	5.333	40	24	32	100
4.365	40	56	44	72	4.900	56	32	28	100	5.347	44	64	56	72
4.375	24	24	28	64	4.911	40	56	44	64	5.348	44	32	28	72
4.386	24	28	44	86	4.914	86	56	32	100	5.357	40	28	24	64
4.400	24	24	44	100	4.950	56	44	28	72	5.358	64	86	72	100
4.444	64	56	28	72	4.961	64	48	32	86	5.375	86	64	40	100
4.465	64	40	24	86	4.978	56	72	64	100	5.400	72	32	24	100
4.466	48	40	32	86	4.984	100	56	24	86	5.413	64	44	32	86
4.477	44	32	28	86	5.000	24	24	28	56	5.426	40	24	28	86
4.479	86	64	24	72	5.017	86	48	28	100	5.427	40	48	56	86
4.480	56	40	32	100	5.023	72	40	24	86	5.444	56	40	28	72
4.500	72	64	40	100	5.029	44	28	32	100	5.455	48	44	28	56
4.522	100	72	28	86	5.040	72	40	28	100	5.469	40	32	28	64
4.537	56	48	28	72	5.074	40	44	48	86	5.473	86	44	28	100
4.545	24	44	40	48	5.080	64	56	32	72	5.486	64	28	24	100
4.546	28	44	40	56	5.088	100	64	28	86	5.500	44	40	24	48
4.548	44	72	64	86	5.091	56	44	40	100	5.556	40	24	24	72
4.558	56	40	28	86	5.093	40	48	44	72	5.568	56	44	28	64

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—5.581 Inches to 7.500 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
5.581	64	32	24	86	6.172	72	28	24	100	6.825	86	56	32	72
5.582	48	24	24	86	6.202	40	24	32	86	6.857	32	28	24	40
5.600	56	24	24	100	6.222	64	40	28	72	6.875	44	24	24	64
5.625	48	32	24	64	6.234	32	28	24	44	6.880	86	40	32	100
5.657	56	44	32	72	6.250	24	24	40	64	6.944	100	48	24	72
5.698	56	32	28	86	6.255	86	44	32	100	6.945	100	56	28	72
5.714	48	28	24	72	6.279	72	64	48	86	6.968	86	48	28	72
5.730	40	48	44	64	6.286	44	40	32	56	6.977	48	32	40	86
5.733	86	48	32	100	6.300	72	32	28	100	6.982	64	44	48	100
5.756	72	64	44	86	6.343	100	44	24	86	6.984	44	28	32	72
5.759	86	56	24	64	6.350	40	28	32	72	7.000	28	24	24	40
5.760	72	40	32	100	6.364	56	44	24	48	7.013	72	44	24	56
5.788	64	72	56	86	6.379	64	28	24	86	7.040	64	40	44	100
5.814	100	64	32	86	6.396	44	32	40	86	7.071	56	44	40	72
5.818	64	44	40	100	6.400	64	24	24	100	7.104	56	44	48	86
5.833	28	24	24	48	6.417	44	40	28	48	7.106	100	72	44	86
5.847	64	56	44	86	6.429	24	28	24	32	7.111	64	40	32	72
5.848	44	28	32	86	6.450	86	64	48	100	7.130	44	24	28	72
5.861	72	40	28	86	6.460	100	72	40	86	7.143	40	28	32	64
5.867	44	24	32	100	6.465	64	44	32	72	7.159	72	44	28	64
5.893	44	32	24	56	6.482	56	48	40	72	7.163	56	40	44	86
5.912	86	64	44	100	6.512	56	24	24	86	7.167	86	40	24	72
5.920	56	44	40	86	6.515	86	44	24	72	7.176	72	28	24	86
5.926	64	48	32	72	6.534	56	24	28	100	7.200	72	24	24	100
5.952	100	56	24	72	6.545	48	40	24	44	7.268	100	64	40	86
5.954	64	40	32	86	6.548	44	48	40	56	7.272	64	44	28	56
5.969	44	24	28	86	6.563	56	32	24	64	7.273	32	24	24	44
5.972	86	48	24	72	6.578	72	56	44	86	7.292	56	48	40	64
5.980	72	56	40	86	6.600	48	32	44	100	7.310	44	28	40	86
6.000	48	40	28	56	6.645	100	56	32	86	7.314	64	28	32	100
6.016	44	32	28	64	6.667	64	48	28	56	7.326	72	32	28	86
6.020	86	40	28	100	6.689	86	72	56	100	7.330	86	44	24	64
6.061	40	44	32	48	6.697	100	56	24	64	7.333	44	24	40	100
6.077	100	64	28	72	6.698	72	40	32	86	7.334	44	40	32	48
6.089	72	44	32	86	6.719	86	48	24	64	7.347	48	28	24	56
6.109	56	44	48	100	6.720	56	40	48	100	7.371	86	56	48	100
6.112	24	24	44	72	6.735	44	28	24	56	7.372	86	28	24	100
6.122	40	28	24	56	6.750	72	40	24	64	7.400	100	44	28	86
6.125	56	40	28	64	6.757	86	56	44	100	7.408	40	24	32	72
6.137	72	44	24	64	6.766	64	44	40	86	7.424	56	44	28	48
6.140	48	40	44	86	6.784	100	48	28	86	7.442	64	24	24	86
6.143	86	56	40	100	6.806	56	32	28	72	7.465	86	64	40	72
6.160	56	40	44	100	6.818	40	32	24	44	7.467	64	24	28	100
6.171	72	56	48	100	6.822	44	24	32	86	7.500	48	24	24	64

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—7.525 Inches to 9.598 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
7.525	86	32	28	100	8.140	56	32	40	86	8.800	48	24	44	100
7.543	48	28	44	100	8.145	64	44	56	100	8.838	100	44	28	72
7.576	100	44	24	72	8.148	64	48	44	72	8.839	72	56	44	64
7.597	56	24	28	86	8.149	44	24	32	72	8.909	56	40	28	44
7.601	86	44	28	72	8.163	40	28	32	56	8.929	100	48	24	56
7.611	72	44	40	86	8.167	56	40	28	48	8.930	64	40	48	86
7.619	64	48	32	56	8.182	48	32	24	44	8.953	56	32	44	86
7.620	64	28	24	72	8.186	64	40	44	86	8.959	86	48	28	56
7.636	56	40	24	44	8.212	86	64	44	72	8.960	64	40	56	100
7.639	44	32	40	72	8.229	72	28	32	100	8.980	44	28	32	56
7.644	86	72	64	100	8.250	44	32	24	40	9.000	48	32	24	40
7.657	56	32	28	64	8.306	100	56	40	86	9.044	100	72	56	86
7.674	72	48	44	86	8.312	64	44	32	56	9.074	56	24	28	72
7.675	48	32	44	86	8.333	40	24	24	48	9.091	40	24	24	44
7.679	86	48	24	56	8.334	40	24	28	56	9.115	100	48	28	64
7.680	64	40	48	100	8.361	86	40	28	72	9.134	72	44	48	86
7.700	56	32	44	100	8.372	72	24	24	86	9.137	100	56	44	86
7.714	72	40	24	56	8.377	86	44	24	56	9.143	64	40	32	56
7.752	100	48	32	86	8.400	72	24	28	100	9.164	72	44	56	100
7.778	32	24	28	48	8.437	72	32	24	64	9.167	44	24	24	48
7.792	40	28	24	44	8.457	100	44	32	86	9.210	72	40	44	86
7.813	100	48	24	64	8.484	32	24	28	44	9.214	86	40	24	56
7.815	56	40	48	86	8.485	64	44	28	48	9.260	100	48	32	72
7.818	86	44	40	100	8.485	56	44	32	48	9.302	48	24	40	86
7.838	86	48	28	64	8.506	64	28	32	86	9.303	56	28	40	86
7.855	72	44	48	100	8.523	100	44	24	64	9.333	64	40	28	48
7.857	44	24	24	56	8.527	44	24	40	86	9.334	32	24	28	40
7.872	44	28	32	64	8.532	86	56	40	72	9.351	48	28	24	44
7.875	72	40	28	64	8.534	64	24	32	100	9.375	48	32	40	64
7.883	86	48	44	100	8.552	86	44	28	64	9.382	86	44	48	100
7.920	72	40	44	100	8.556	56	40	44	72	9.385	86	56	44	72
7.936	100	56	32	72	8.572	64	32	24	56	9.406	86	40	28	64
7.954	40	32	28	44	8.572	48	24	24	56	9.428	44	28	24	40
7.955	56	44	40	64	8.594	44	32	40	64	9.429	48	40	44	56
7.963	86	48	32	72	8.600	86	24	24	100	9.460	86	40	44	100
7.974	48	28	40	86	8.640	72	40	48	100	9.472	64	44	56	86
7.994	100	64	44	86	8.681	100	64	40	72	9.524	40	28	32	48
8.000	64	32	40	100	8.682	64	24	28	86	9.545	72	44	28	48
8.021	44	32	28	48	8.687	86	44	32	72	9.546	56	32	24	44
8.035	72	56	40	64	8.721	100	32	24	86	9.547	56	44	48	64
8.063	86	40	24	64	8.727	48	40	32	44	9.549	100	64	44	72
8.081	64	44	40	72	8.730	44	28	40	72	9.556	86	40	32	72
8.102	100	48	28	72	8.750	28	24	24	32	9.569	72	28	32	86
8.119	64	44	48	86	8.772	48	28	44	86	9.598	86	56	40	64

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—9.600 Inches to 12.375 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
9.600	72	24	32	100	10.370	64	24	28	72	11.314	72	28	44	100
9.625	44	32	28	40	10.371	64	48	56	72	11.363	100	44	24	48
9.643	72	32	24	56	10.390	40	28	32	44	11.401	86	44	28	48
9.675	86	64	72	100	10.417	100	32	24	72	11.429	32	24	24	28
9.690	100	48	40	86	10.419	64	40	56	86	11.454	72	40	28	44
9.697	64	48	32	44	10.451	86	32	28	72	11.459	44	24	40	64
9.723	40	24	28	48	10.467	72	32	40	86	11.467	86	24	32	100
9.741	100	44	24	56	10.473	72	44	64	100	11.512	72	32	44	86
9.768	72	48	56	86	10.476	44	24	32	56	11.518	86	28	24	64
9.773	86	44	24	48	10.477	48	28	44	72	11.520	72	40	64	100
9.778	64	40	44	72	10.500	56	32	24	40	11.574	100	48	40	72
9.796	64	28	24	56	10.558	86	56	44	64	11.629	100	24	24	86
9.818	72	40	24	44	10.571	100	44	40	86	11.638	64	40	32	44
9.822	44	32	40	56	10.606	56	44	40	48	11.667	56	24	24	48
9.828	86	28	32	100	10.631	64	28	40	86	11.688	72	44	40	56
9.844	72	32	28	64	10.655	72	44	56	86	11.695	64	28	44	86
9.900	72	32	44	100	10.659	100	48	44	86	11.719	100	32	24	64
9.921	100	56	40	72	10.667	64	40	48	72	11.721	72	40	56	86
9.923	64	24	32	86	10.694	44	24	28	48	11.728	86	40	24	44
9.943	100	44	28	64	10.713	40	28	24	32	11.733	64	24	44	100
9.954	86	48	40	72	10.714	48	32	40	56	11.757	86	32	28	64
9.967	100	56	48	86	10.750	86	40	24	48	11.785	72	48	44	56
9.968	100	28	24	86	10.800	72	32	48	100	11.786	44	28	24	32
10.000	56	28	24	48	10.853	56	24	40	86	11.825	86	32	44	100
10.033	86	24	28	100	10.859	86	44	40	72	11.905	100	28	24	72
10.046	72	40	48	86	10.909	72	44	32	48	11.938	56	24	44	86
10.057	64	28	44	100	10.913	100	56	44	72	11.944	86	24	24	72
10.078	86	32	24	64	10.937	56	32	40	64	11.960	72	28	40	86
10.080	72	40	56	100	10.945	86	44	56	100	12.000	48	24	24	40
10.101	100	44	32	72	10.949	86	48	44	72	12.031	56	32	44	64
10.159	64	28	32	72	10.972	64	28	48	100	12.040	86	40	56	100
10.175	100	32	28	86	11.000	44	24	24	40	12.121	40	24	32	44
10.182	64	40	28	44	11.021	72	28	24	56	12.153	100	32	28	72
10.186	44	24	40	72	11.057	86	56	72	100	12.178	72	44	64	86
10.209	56	24	28	64	11.111	40	24	32	48	12.216	86	44	40	64
10.228	72	44	40	64	11.137	56	32	28	44	12.222	44	24	32	48
10.233	48	24	44	86	11.160	100	56	40	64	12.245	48	28	40	56
10.238	86	28	24	72	11.163	72	24	32	86	12.250	56	32	28	40
10.267	56	24	44	100	11.169	86	44	32	56	12.272	72	32	24	44
10.286	48	28	24	40	11.198	86	48	40	64	12.277	100	56	44	64
10.312	48	32	44	64	11.200	56	24	48	100	12.286	86	28	40	100
10.313	72	48	44	64	11.225	44	28	40	56	12.318	86	48	44	64
10.320	86	40	48	100	11.250	72	24	24	64	12.343	72	28	48	100
10.336	100	72	64	86	11.313	64	44	56	72	12.375	72	40	44	64

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—12.403 Inches to 16.000 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
12.403	64	24	40	86	13.438	86	24	24	64	14.668	44	24	32	40
12.444	64	40	56	72	13.469	48	28	44	56	14.694	72	28	32	56
12.468	64	28	24	44	13.500	72	32	24	40	14.743	86	28	48	100
12.500	40	24	24	32	13.514	86	28	44	100	14.780	86	40	44	64
12.542	86	40	28	48	13.566	100	24	28	86	14.800	100	44	56	86
12.508	86	44	64	100	13.611	56	24	28	48	14.815	64	24	40	72
12.558	72	32	48	86	13.636	48	32	40	44	14.849	56	24	28	44
12.571	64	40	44	56	13.643	64	24	44	86	14.880	100	48	40	56
12.572	44	28	32	40	13.650	86	28	32	72	14.884	64	28	56	86
12.600	72	32	56	100	13.672	100	32	28	64	14.931	86	32	40	72
12.627	100	44	40	72	13.682	86	40	28	44	14.933	64	24	56	100
12.686	100	44	48	86	13.713	64	40	48	56	14.950	100	56	72	86
12.698	64	28	40	72	13.715	64	28	24	40	15.000	48	24	24	32
12.727	64	32	28	44	13.750	44	24	24	32	15.050	86	32	56	100
12.728	56	24	24	44	13.760	86	40	64	100	15.150	100	44	32	48
12.732	100	48	44	72	13.889	100	24	24	72	15.151	100	44	48	72
12.758	64	28	48	86	13.933	86	48	56	72	15.202	86	44	56	72
12.791	100	40	44	86	13.935	86	24	28	72	15.238	64	28	48	72
12.798	86	48	40	56	13.953	72	24	40	86	15.239	64	28	32	48
12.800	64	28	56	100	13.960	86	44	40	56	15.272	56	40	48	44
12.834	56	40	44	48	13.968	64	28	44	72	15.278	44	24	40	48
12.857	72	28	32	64	14.000	56	24	24	40	15.279	100	40	44	72
12.858	48	28	24	32	14.025	72	44	48	56	15.306	100	28	24	56
12.900	86	32	48	100	14.026	72	28	24	44	15.349	72	24	44	86
12.963	56	24	40	72	14.063	72	32	40	64	15.357	86	28	24	48
12.987	100	44	32	56	14.071	86	44	72	100	15.429	72	40	48	56
13.020	100	48	40	64	14.078	86	48	44	56	15.469	72	32	44	64
13.024	56	24	48	86	14.142	72	40	44	56	15.480	86	40	72	100
13.030	86	44	32	48	14.204	100	44	40	64	15.504	100	48	64	86
13.062	64	28	32	56	14.260	56	24	44	72	15.556	64	32	56	72
13.082	100	64	72	86	14.286	40	24	24	28	15.584	48	28	40	44
13.090	72	40	32	44	14.318	72	32	28	44	15.625	100	24	24	64
13.096	44	28	40	48	14.319	72	44	56	64	15.636	86	40	32	44
13.125	72	32	28	48	14.322	100	48	44	64	15.677	86	32	28	48
13.139	86	40	44	72	14.333	86	40	32	48	15.714	44	24	24	28
13.157	72	28	44	86	14.352	72	28	48	86	15.750	72	32	28	40
13.163	86	28	24	56	14.400	72	24	48	100	15.767	86	24	44	100
13.200	72	24	44	100	14.536	100	32	40	86	15.873	100	56	64	72
13.258	100	44	28	48	14.545	64	24	24	44	15.874	100	28	32	72
13.289	100	28	32	86	14.583	56	32	40	48	15.909	100	40	28	44
13.333	64	24	24	48	14.584	40	24	28	32	15.925	86	48	64	72
13.393	100	56	48	64	14.651	72	32	56	86	15.926	86	24	32	72
13.396	72	40	64	86	14.659	86	44	48	64	15.989	100	32	44	86
13.437	86	32	28	56	14.667	64	40	44	48	16.000	64	24	24	40

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—16.042 Inches to 21.39 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
16.042	56	24	44	64	17.442	100	32	48	86	19.350	86	32	72	100
16.043	44	24	28	32	17.454	64	40	48	44	19.380	100	24	40	86
16.071	72	32	40	56	17.500	56	24	24	32	19.394	64	24	32	44
16.125	86	32	24	40	17.550	86	28	32	56	19.444	40	24	28	24
16.204	100	24	28	72	17.677	100	44	56	72	19.480	100	28	24	44
16.233	100	44	40	56	17.679	72	32	44	56	19.531	100	32	40	64
16.280	100	40	56	86	17.778	64	24	32	48	19.535	72	24	56	86
16.288	86	44	40	48	17.858	100	24	24	56	19.545	86	24	24	44
16.296	64	24	44	72	17.917	86	24	32	64	19.590	64	28	48	56
16.327	64	28	40	56	17.918	86	24	24	48	19.635	72	40	48	44
16.333	56	24	28	40	17.959	64	28	44	56	19.642	100	40	44	56
16.364	72	24	24	44	18.000	72	24	24	40	19.643	44	28	40	32
16.370	100	48	44	56	18.181	56	28	40	44	19.656	86	28	64	100
16.423	86	32	44	72	18.182	48	24	40	44	19.687	72	32	56	64
16.456	72	28	64	100	18.229	100	32	28	48	19.710	86	40	44	48
16.500	72	40	44	48	18.273	100	28	44	86	19.840	100	28	40	72
16.612	100	28	40	86	18.285	64	28	32	40	19.886	100	44	56	64
16.623	64	28	32	44	18.333	56	28	44	48	19.887	100	32	28	44
16.667	56	28	40	48	18.367	72	28	40	56	19.908	86	24	40	72
16.722	86	40	56	72	18.428	86	28	24	40	19.934	100	28	48	86
16.744	72	24	48	86	18.476	86	32	44	64	20.00	72	24	32	48
16.752	86	44	48	56	18.519	100	24	32	72	20.07	86	24	56	100
16.753	86	28	24	44	18.605	100	40	64	86	20.09	100	56	72	64
16.797	86	32	40	64	18.663	100	64	86	72	20.16	86	48	72	64
16.800	72	24	56	100	18.667	64	24	28	40	20.20	100	44	64	72
16.875	72	32	48	64	18.700	72	44	64	56	20.35	100	32	56	86
16.892	86	40	44	56	18.750	100	32	24	40	20.36	64	40	56	44
16.914	100	44	64	86	18.750	72	32	40	48	20.41	100	28	32	56
16.969	64	44	56	48	18.770	86	28	44	72	20.42	56	24	28	32
16.970	64	24	28	44	18.812	86	32	28	40	20.45	72	32	40	44
17.045	100	32	24	44	18.858	48	28	44	40	20.48	86	48	64	56
17.046	100	44	48	64	18.939	100	44	40	48	20.57	72	40	64	56
17.062	86	28	40	72	19.029	100	44	72	86	20.63	72	32	44	48
17.101	86	44	56	64	19.048	40	24	32	28	20.74	64	24	56	72
17.102	86	32	28	44	19.090	56	32	48	44	20.78	64	28	40	44
17.141	64	32	48	56	19.091	72	24	28	44	20.83	100	32	48	72
17.143	64	28	24	32	19.096	100	32	44	72	20.90	86	32	56	72
17.144	48	24	24	28	19.111	86	40	64	72	20.93	100	40	72	86
17.188	100	40	44	64	19.136	72	28	64	86	20.95	64	28	44	48
17.200	86	32	64	100	19.197	86	32	40	56	21.00	56	32	48	40
17.275	86	56	72	64	19.200	72	24	64	100	21.12	86	32	44	56
17.361	100	32	40	72	19.250	56	32	44	40	21.32	100	24	44	86
17.364	64	24	56	86	19.285	72	32	48	56	21.33	100	56	86	72
17.373	86	44	64	72	19.286	72	28	24	32	21.39	44	24	28	24

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—21.43 Inches to 32.09 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
21.43	100	40	48	56	24.88	100	72	86	48	28.05	72	28	48	44
21.48	100	32	44	64	24.93	64	28	48	44	28.06	100	28	44	56
21.50	86	24	24	40	25.00	72	24	40	48	28.13	100	40	72	64
21.82	72	44	64	48	25.08	86	24	28	40	28.15	86	28	44	48
21.88	100	40	56	64	25.09	86	40	56	48	28.29	72	28	44	40
21.90	86	24	44	72	25.13	86	44	72	56	28.41	100	32	40	44
21.94	86	28	40	56	25.14	64	28	44	40	28.57	100	56	64	40
21.99	86	44	72	64	25.45	64	44	56	32	28.64	72	44	56	32
22.00	64	32	44	40	25.46	100	24	44	72	28.65	100	32	44	48
22.04	72	28	48	56	25.51	100	28	40	56	28.67	86	40	64	48
22.11	86	28	72	100	25.57	100	64	72	44	29.09	64	24	48	44
22.22	100	40	64	72	25.60	86	28	40	48	29.17	100	40	56	48
22.34	86	44	64	56	25.67	56	24	44	40	29.22	100	56	72	44
22.40	86	32	40	48	25.71	72	24	48	56	29.32	86	48	72	44
22.50	72	24	48	64	25.72	72	24	24	28	29.34	64	24	44	40
22.73	100	24	24	44	25.80	86	24	72	100	29.39	72	28	64	56
22.80	86	48	56	44	25.97	100	44	64	56	29.56	86	32	44	40
22.86	64	24	24	28	26.04	100	32	40	48	29.76	100	28	40	48
22.91	72	44	56	40	26.06	86	44	64	48	29.86	100	40	86	72
22.92	100	40	44	48	26.16	100	32	72	86	29.90	100	28	72	86
22.93	86	24	64	100	26.18	72	40	64	44	30.00	56	28	48	32
23.04	86	56	72	48	26.19	44	24	40	28	30.23	86	32	72	64
23.14	100	24	40	72	26.25	72	32	56	48	30.30	100	48	64	44
23.26	100	32	64	86	26.33	86	28	48	56	30.48	64	24	32	28
23.33	64	32	56	48	26.52	100	44	56	48	30.54	100	44	86	64
23.38	72	28	40	44	26.58	100	28	64	86	30.56	44	24	40	24
23.44	100	48	72	64	26.67	64	28	56	48	30.61	100	28	48	56
23.45	86	40	48	44	26.79	100	48	72	56	30.71	86	24	48	56
23.52	86	32	56	64	26.88	86	28	56	64	30.72	86	24	24	28
23.57	72	28	44	48	27.00	72	32	48	40	30.86	72	28	48	40
23.81	100	48	64	56	27.13	100	24	56	86	31.01	100	24	64	86
23.89	86	32	64	72	27.15	100	44	86	72	31.11	64	24	56	48
24.00	64	40	72	48	27.22	56	24	28	24	31.25	100	28	56	64
24.13	86	28	44	56	27.27	100	40	48	44	31.27	86	40	64	44
24.19	86	40	72	64	27.30	86	28	64	72	31.35	86	32	56	48
24.24	64	24	40	44	27.34	100	32	56	64	31.36	86	24	28	32
24.31	100	32	56	72	27.36	86	40	56	44	31.43	64	28	44	32
24.43	86	32	40	44	27.43	64	28	48	40	31.50	72	32	56	40
24.44	44	24	32	24	27.50	56	32	44	28	31.75	100	72	64	28
24.54	72	32	48	44	27.64	86	40	72	56	31.82	100	44	56	40
24.55	100	32	44	56	27.78	100	32	64	72	31.85	86	24	64	72
24.57	86	40	64	56	27.87	86	24	56	72	31.99	100	56	86	48
24.64	86	24	44	64	27.92	86	28	40	44	32.00	64	28	56	40
24.75	72	32	44	40	28.00	100	64	86	48	32.09	56	24	44	32

Copyright 2004, Industrial Press, Inc., New York, NY

Change Gears for Different Leads—32.14 Inches to 60.00 Inches

Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver	Lead in Inches	Driven	Driver	Driven	Driver
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw		Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw
32.14	100	56	72	40	38.20	100	24	44	48	46.07	86	28	72	48
32.25	86	48	72	40	38.39	100	40	86	56	46.67	64	24	56	32
32.41	100	24	56	72	38.57	72	28	48	32	46.88	100	32	72	48
32.47	100	28	40	44	38.89	56	24	40	24	47.15	72	24	44	28
32.58	86	24	40	44	38.96	100	28	48	44	47.62	100	28	64	48
32.73	72	32	64	44	39.09	86	32	64	44	47.78	86	24	64	48
32.74	100	28	44	48	39.29	100	28	44	40	47.99	100	32	86	56
32.85	86	24	44	48	39.42	86	24	44	40	48.00	72	24	64	40
33.00	72	24	44	40	39.49	86	28	72	56	48.38	86	32	72	40
33.33	100	24	32	40	39.77	100	32	56	44	48.61	100	24	56	48
33.51	86	28	48	44	40.00	72	24	64	48	48.86	100	40	86	44
33.59	100	64	86	40	40.18	100	32	72	56	48.89	64	24	44	24
33.79	86	28	44	40	40.31	86	32	72	48	49.11	100	28	44	32
33.94	64	24	56	44	40.72	100	44	86	48	49.14	86	28	64	40
34.09	100	48	72	44	40.82	100	28	64	56	49.27	86	24	44	32
34.20	86	44	56	32	40.91	100	40	72	44	49.77	100	24	86	72
34.29	72	48	64	28	40.95	86	28	64	48	50.00	100	28	56	40
34.38	100	32	44	40	40.96	86	24	32	28	50.17	86	24	56	40
34.55	86	32	72	56	41.14	72	28	64	40	50.26	86	28	72	44
34.72	100	24	40	48	41.25	72	24	44	32	51.14	100	32	72	44
34.88	100	24	72	86	41.67	100	32	64	48	51.19	86	24	40	28
34.90	100	56	86	44	41.81	86	24	56	48	51.43	72	28	64	32
35.00	72	24	56	48	41.91	64	24	44	28	51.95	100	28	64	44
35.10	86	28	64	56	41.99	100	32	86	64	52.12	86	24	64	44
35.16	100	32	72	64	42.00	72	24	56	40	52.50	72	24	56	32
35.18	86	44	72	40	42.23	86	28	44	32	53.03	100	24	56	44
35.36	72	32	44	28	42.66	100	28	86	72	53.33	64	24	56	28
35.56	64	24	32	24	42.78	56	24	44	24	53.57	100	28	72	48
35.71	100	32	64	56	42.86	100	28	48	40	53.75	86	24	48	32
35.72	100	24	24	28	43.00	86	32	64	40	54.85	100	28	86	56
35.83	86	32	64	48	43.64	72	24	64	44	55.00	72	24	44	24
36.00	72	32	64	40	43.75	100	32	56	40	55.28	86	28	72	40
36.36	100	44	64	40	43.98	86	32	72	44	55.56	100	24	32	24
36.46	100	48	56	32	44.44	64	24	40	24	55.99	100	24	86	64
36.67	48	24	44	24	44.64	100	28	40	32	56.25	100	32	72	40
36.86	86	28	48	40	44.68	86	28	64	44	56.31	86	24	44	28
37.04	100	24	64	72	44.79	100	40	86	48	57.14	100	28	64	40
37.33	100	32	86	72	45.00	72	28	56	32	57.30	100	24	44	32
37.40	72	28	64	44	45.45	100	32	64	44	57.33	86	24	64	40
37.50	100	48	72	40	45.46	100	28	56	44	58.33	100	24	56	40
37.63	86	32	56	40	45.61	86	24	56	44	58.44	100	28	72	44
37.88	100	24	40	44	45.72	64	24	48	28	58.64	86	24	72	44
38.10	64	24	40	28	45.84	100	24	44	40	59.53	100	24	40	28
38.18	72	24	56	44	45.92	100	28	72	56	60.00	72	24	64	32

Copyright 2004, Industrial Press, Inc., New York, NY

Lead of Helix for Given Helix Angle Relative to Axis, When Diameter = 1

Deg.	0′	6′	12′	18′	24′	30′	36′	42′	48′	54′	60′
0	Infin.	1800.001	899.997	599.994	449.993	359.992	299.990	257.130	224.986	199.983	179.982
1	179.982	163.616	149.978	138.438	128.545	119.973	112.471	105.851	99.967	94.702	89.964
2	89.964	85.676	81.778	78.219	74.956	71.954	69.183	66.617	64.235	62.016	59.945
3	59.945	58.008	56.191	54.485	52.879	51.365	49.934	48.581	47.299	46.082	44.927
4	44.927	43.827	42.780	41.782	40.829	39.918	39.046	38.212	37.412	36.645	35.909
5	35.909	35.201	34.520	33.866	33.235	32.627	32.040	31.475	30.928	30.400	29.890
6	29.890	29.397	28.919	28.456	28.008	27.573	27.152	26.743	26.346	25.961	25.586
7	25.586	25.222	24.868	24.524	24.189	23.863	23.545	23.236	22.934	22.640	22.354
8	22.354	22.074	21.801	21.535	21.275	21.021	20.773	20.530	20.293	20.062	19.835
9	19.835	19.614	19.397	19.185	18.977	18.773	18.574	18.379	18.188	18.000	17.817
10	17.817	17.637	17.460	17.287	17.117	16.950	16.787	16.626	16.469	16.314	16.162
11	16.162	16.013	15.866	15.722	15.581	15.441	15.305	15.170	15.038	14.908	14.780
12	14.780	14.654	14.530	14.409	14.289	14.171	14.055	13.940	13.828	13.717	13.608
13	13.608	13.500	13.394	13.290	13.187	13.086	12.986	12.887	12.790	12.695	12.600
14	12.600	12.507	12.415	12.325	12.237	12.148	12.061	11.975	11.890	11.807	11.725
15	11.725	11.643	11.563	11.484	11.405	11.328	11.252	11.177	11.102	11.029	10.956
16	10.956	10.884	10.813	10.743	10.674	10.606	10.538	10.471	10.405	10.340	10.276
17	10.276	10.212	10.149	10.086	10.025	9.964	9.904	9.844	9.785	9.727	9.669
18	9.669	9.612	9.555	9.499	9.444	9.389	9.335	9.281	9.228	9.176	9.124
19	9.124	9.072	9.021	8.971	8.921	8.872	8.823	8.774	8.726	8.679	8.631
20	8.631	8.585	8.539	8.493	8.447	8.403	8.358	8.314	8.270	8.227	8.184
21	8.184	8.142	8.099	8.058	8.016	7.975	7.935	7.894	7.855	7.815	7.776
22	7.776	7.737	7.698	7.660	7.622	7.584	7.547	7.510	7.474	7.437	7.401
23	7.401	7.365	7.330	7.295	7.260	7.225	7.191	7.157	7.123	7.089	7.056
24	7.056	7.023	6.990	6.958	6.926	6.894	6.862	6.830	6.799	6.768	6.737
25	6.737	6.707	6.676	6.646	6.617	6.586	6.557	6.528	6.499	6.470	6.441
26	6.441	6.413	6.385	6.357	6.329	6.300	6.274	6.246	6.219	6.192	6.166
27	6.166	6.139	6.113	6.087	6.061	6.035	6.009	5.984	5.959	5.933	5.908
28	5.908	5.884	5.859	5.835	5.810	5.786	5.762	5.738	5.715	5.691	5.668
29	5.668	5.644	5.621	5.598	5.575	5.553	5.530	5.508	5.486	5.463	5.441

Copyright 2004, Industrial Press, Inc., New York, NY

Lead of Helix for Given Helix Angle Relative to Axis, When Diameter = 1*(Continued)*

Deg.	0′	6′	12′	18′	24′	30′	36′	42′	48′	54′	60′
30	5.441	5.420	5.398	5.376	5.355	5.333	5.312	5.291	5.270	5.249	5.228
31	5.228	5.208	5.187	5.167	5.147	5.127	5.107	5.087	5.067	5.047	5.028
32	5.028	5.008	4.989	4.969	4.950	4.931	4.912	4.894	4.875	4.856	4.838
33	4.838	4.819	4.801	4.783	4.764	4.746	4.728	4.711	4.693	4.675	4.658
34	4.658	4.640	4.623	4.605	4.588	4.571	4.554	4.537	4.520	4.503	4.487
35	4.487	4.470	4.453	4.437	4.421	4.404	4.388	4.372	4.356	4.340	4.324
36	4.324	4.308	4.292	4.277	4.261	4.246	4.230	4.215	4.199	4.184	4.169
37	4.169	4.154	4.139	4.124	4.109	4.094	4.079	4.065	4.050	4.036	4.021
38	4.021	4.007	3.992	3.978	3.964	3.950	3.935	3.921	3.907	3.893	3.880
39	3.880	3.866	3.852	3.838	3.825	3.811	3.798	3.784	3.771	3.757	3.744
40	3.744	3.731	3.718	3.704	3.691	3.678	3.665	3.652	3.640	3.627	3.614
41	3.614	3.601	3.589	3.576	3.563	3.551	3.538	3.526	3.514	3.501	3.489
42	3.489	3.477	3.465	3.453	3.440	3.428	3.416	3.405	3.393	3.381	3.369
43	3.369	3.358	3.346	3.334	3.322	3.311	3.299	3.287	3.276	3.265	3.253
44	3.253	3.242	3.231	3.219	3.208	3.197	3.186	3.175	3.164	3.153	3.142
45	3.142	3.131	3.120	3.109	3.098	3.087	3.076	3.066	3.055	3.044	3.034
46	3.034	3.023	3.013	3.002	2.992	2.981	2.971	2.960	2.950	2.940	2.930
47	2.930	2.919	2.909	2.899	2.889	2.879	2.869	2.859	2.849	2.839	2.829
48	2.829	2.819	2.809	2.799	2.789	2.779	2.770	2.760	2.750	2.741	2.731
49	2.731	2.721	2.712	2.702	2.693	2.683	2.674	2.664	2.655	2.645	2.636
50	2.636	2.627	2.617	2.608	2.599	2.590	2.581	2.571	2.562	2.553	2.544
51	2.544	2.535	2.526	2.517	2.508	2.499	2.490	2.481	2.472	2.463	2.454
52	2.454	2.446	2.437	2.428	2.419	2.411	2.402	2.393	2.385	2.376	2.367
53	2.367	2.359	2.350	2.342	2.333	2.325	2.316	2.308	2.299	2.291	2.282
54	2.282	2.274	2.266	2.257	2.249	2.241	2.233	2.224	2.216	2.208	2.200
55	2.200	2.192	2.183	2.175	2.167	2.159	2.151	2.143	2.135	2.127	2.119
56	2.119	2.111	2.103	2.095	2.087	2.079	2.072	2.064	2.056	2.048	2.040
57	2.040	2.032	2.025	2.017	2.009	2.001	1.994	1.986	1.978	1.971	1.963
58	1.963	1.955	1.948	1.940	1.933	1.925	1.918	1.910	1.903	1.895	1.888
59	1.888	1.880	1.873	1.865	1.858	1.851	1.843	1.836	1.828	1.821	1.814

Copyright 2004, Industrial Press, Inc., New York, NY

Lead of Helix for Given Helix Angle Relative to Axis, When Diameter = 1*(Continued)*

Deg.	0′	6′	12′	18′	24′	30′	36′	42′	48′	54′	60′
60	1.814	1.806	1.799	1.792	1.785	1.777	1.770	1.763	1.756	1.749	1.741
61	1.741	1.734	1.727	1.720	1.713	1.706	1.699	1.692	1.685	1.677	1.670
62	1.670	1.663	1.656	1.649	1.642	1.635	1.628	1.621	1.615	1.608	1.601
63	1.601	1.594	1.587	1.580	1.573	1.566	1.559	1.553	1.546	1.539	1.532
64	1.532	1.525	1.519	1.512	1.505	1.498	1.492	1.485	1.478	1.472	1.465
65	1.465	1.458	1.452	1.445	1.438	1.432	1.425	1.418	1.412	1.405	1.399
66	1.399	1.392	1.386	1.379	1.372	1.366	1.359	1.353	1.346	1.340	1.334
67	1.334	1.327	1.321	1.314	1.308	1.301	1.295	1.288	1.282	1.276	1.269
68	1.269	1.263	1.257	1.250	1.244	1.237	1.231	1.225	1.219	1.212	1.206
69	1.206	1.200	1.193	1.187	1.181	1.175	1.168	1.162	1.156	1.150	1.143
70	1.143	1.137	1.131	1.125	1.119	1.112	1.106	1.100	1.094	1.088	1.082
71	1.082	1.076	1.069	1.063	1.057	1.051	1.045	1.039	1.033	1.027	1.021
72	1.021	1.015	1.009	1.003	0.997	0.991	0.985	0.978	0.972	0.966	0.960
73	0.960	0.954	0.948	0.943	0.937	0.931	0.925	0.919	0.913	0.907	0.901
74	0.901	0.895	0.889	0.883	0.877	0.871	0.865	0.859	0.854	0.848	0.842
75	0.842	0.836	0.830	0.824	0.818	0.812	0.807	0.801	0.795	0.789	0.783
76	0.783	0.777	0.772	0.766	0.760	0.754	0.748	0.743	0.737	0.731	0.725
77	0.725	0.720	0.714	0.708	0.702	0.696	0.691	0.685	0.679	0.673	0.668
78	0.668	0.662	0.656	0.651	0.645	0.639	0.633	0.628	0.622	0.616	0.611
79	0.611	0.605	0.599	0.594	0.588	0.582	0.577	0.571	0.565	0.560	0.554
80	0.554	0.548	0.543	0.537	0.531	0.526	0.520	0.514	0.509	0.503	0.498
81	0.498	0.492	0.486	0.481	0.475	0.469	0.464	0.458	0.453	0.447	0.441
82	0.441	0.436	0.430	0.425	0.419	0.414	0.408	0.402	0.397	0.391	0.386
83	0.386	0.380	0.375	0.369	0.363	0.358	0.352	0.347	0.341	0.336	0.330
84	0.330	0.325	0.319	0.314	0.308	0.302	0.297	0.291	0.286	0.280	0.275
85	0.275	0.269	0.264	0.258	0.253	0.247	0.242	0.236	0.231	0.225	0.220
86	0.220	0.214	0.209	0.203	0.198	0.192	0.187	0.181	0.176	0.170	0.165
87	0.165	0.159	0.154	0.148	0.143	0.137	0.132	0.126	0.121	0.115	0.110
88	0.110	0.104	0.099	0.093	0.088	0.082	0.077	0.071	0.066	0.060	0.055
89	0.055	0.049	0.044	0.038	0.033	0.027	0.022	0.016	0.011	0.005	0.000

Copyright 2004, Industrial Press, Inc., New York, NY

Leads, Change Gears and Angles for Helical Milling

Lead of Helix, Inches	Change Gears: Gear on Work	Change Gears: First Gear on Stud	Change Gears: Second Gear on Stud	Change Gears: Gear on Screw	Diameter of Work, Inches: 1/8	1/4	3/8	1/2	5/8	3/4	7/8	1	1 1/4	1 1/2
					Approximate Angles for Milling Machine Table									
0.67	24	86	24	100	30¼	…	…	…	…	…	…	…	…	…
0.78	24	86	28	100	26	44½	…	…	…	…	…	…	…	…
0.89	24	86	32	100	23½	41	…	…	…	…	…	…	…	…
1.12	24	86	40	100	19	34½	…	…	…	…	…	…	…	…
1.34	24	86	48	100	16	30¼	41½	…	…	…	…	…	…	…
1.46	24	64	28	72	14¾	28	38½	…	…	…	…	…	…	…
1.56	24	86	56	100	13¾	26½	37	…	…	…	…	…	…	…
1.67	24	64	32	72	12¾	25	34¾	43¼	…	…	…	…	…	…
1.94	32	64	28	72	11¼	21¾	31	39	45	…	…	…	…	…
2.08	24	64	40	72	10¼	20½	29½	37	43¼	…	…	…	…	…
2.22	32	56	28	72	9¾	19¼	27½	35	41¼	…	…	…	…	…
2.50	24	64	48	72	8¾	17	25	32	38	43¼	…	…	…	…
2.78	40	56	28	72	8	15½	23	29½	35¼	40½	44¾	…	…	…
2.92	24	64	56	72	7½	15	21¾	28¼	34	39	43¼	…	…	…
3.24	40	48	28	72	6¾	13¼	19¾	25¾	31¼	36	40½	44¼	…	…
3.70	40	48	32	72	6	11¾	17½	23	28	32½	36½	40½	…	…
3.89	56	48	24	72	5½	11¼	16¾	22	26¾	31¼	35¼	39	…	…
4.17	40	72	48	64	5¼	10½	15¾	20½	25¼	29½	33½	37	43¼	…
4.46	48	40	32	86	4¾	9¾	14¾	19¼	23¾	27¾	31½	35	41½	…
4.86	40	64	56	72	4½	9	13½	17¾	22	25¾	29½	33	39	44¼
5.33	48	40	32	72	4	8¼	12¼	16½	20¼	23¾	27¼	30½	36½	41½
5.44	56	40	28	72	4	8	12	16	20	23½	26¾	30	36	41
6.12	56	40	28	64	3½	7¼	11	14½	17¾	21	24¼	27	33	37¾
6.22	56	40	32	72	3½	7	10¾	14¼	17½	20¾	23¾	26¾	32½	37¼
6.48	56	48	40	72	3¼	6¾	10¼	13½	16¾	20	23	25¾	31½	36¼
6.67	64	48	28	56	3¼	6½	10	13¼	16½	19½	22½	25¼	30¾	35¼
7.29	56	48	40	64	3	6¼	9¼	12¼	15	18	20½	23½	28½	33
7.41	64	48	40	72	3	6	9	12	14¾	17¾	20¼	22¾	28¼	32½
7.62	64	48	32	56	2¾	5¾	8¾	11½	14½	17¼	19¾	22¼	27½	32
8.33	48	32	40	72	2½	5¼	8	10½	13¼	15¾	18¼	20½	25½	29½
8.95	86	48	28	56	2½	5	7½	10	12½	14¾	17	19¼	24	28
9.33	56	40	48	72	2¼	4¾	7¼	9½	11¾	14	16¼	18½	23	27
9.52	64	48	40	56	2¼	4½	7	9¼	11½	13¾	16	18¼	22½	26½
10.29	72	40	32	56	2	4¼	6½	8¾	10¾	12¾	15	17¼	21	24¾
10.37	64	48	56	72	2	4¼	6½	8½	10½	12¾	14¾	17	20¾	24½
10.50	48	40	56	64	2	4¼	6¼	8½	10½	12½	14½	16¾	20½	24¼
10.67	64	40	48	72	2	4	6¼	8¼	10¼	12¼	14¼	16½	20¼	24
10.94	56	32	40	64	2	4	6	8¼	10¼	12	14	16¼	20	23½
11.11	64	32	40	72	2	4	6	8	10	11¾	13¾	16	19¾	23
11.66	56	32	48	72	1¾	3¾	5¾	7½	9½	11¼	13¼	15¼	18¾	22
12.00	72	40	32	48	1¾	3¾	5½	7¼	9¼	11	12¾	15	18¼	21½
13.12	56	32	48	64	1½	3½	5¼	6¾	8½	10¼	11¾	13½	16¾	20
13.33	56	28	48	72	1½	3¼	5	6½	8¼	10	11½	13¼	16½	19½
13.71	64	40	48	56	1½	3¼	4¾	6½	8	9¾	11¼	13	16	19
15.24	64	28	48	72	1½	3	4½	5¾	7¼	8¾	10¼	11¾	14½	17¼
15.56	64	32	56	72	1¼	2¾	4¼	5¾	7¼	8¾	10	11½	14¼	17
15.75	56	64	72	40	1¼	2¾	4¼	5½	7	8½	9¾	11¼	14	16¾
16.87	72	32	48	64	1¼	2½	4	5¼	6¾	7¾	9¼	10½	13¼	15¾
17.14	64	32	48	56	1¼	2½	4	5¼	6½	7¾	9	10¼	13	15½
18.75	72	32	40	48	1	2¼	3½	4¾	6	7¼	8¼	9½	12	14¼
19.29	72	32	48	56	1	2¼	3½	4¼2	5¾	7	8	9¼	11½	13¾
19.59	64	28	48	56	1	2¼	3¼	4½	5¾	6¾	8	9¼	11½	13½
19.69	72	32	56	64	1	2¼	3¼	4½	5¾	6¾	8	9	11½	13½
21.43	72	24	40	56	1	2	3¼	4¼	5¼	6¼	7½	8½	10½	12½
22.50	72	28	56	64	1	2	3	4	5	6	7	8	10	12
23.33	64	32	56	48	1	2	3	4	5	5¾	6¾	7¾	9¾	11½
26.25	72	24	56	64	1	1¾	2¾	3½	4¼	5	6	7	8½	10¼
26.67	64	28	56	48	¾	1¾	2¾	3½	4¼	5	6	6¾	8½	10
28.00	64	32	56	40	¾	1¾	2½	3¼	4	4¾	5¾	6½	8	9½
30.86	72	28	48	40	¾	1½	2¼	3	3¾	4½	5	5¾	7¼	8¾

Copyright 2004, Industrial Press, Inc., New York, NY

Leads, Change Gears and Angles for Helical Milling

Lead of Helix, Inches	Change Gears				Diameter of Work, Inches									
	Gear on Worm	First Gear on Stud	Second Gear on Stud	Gear on Screw	1¾	2	2¼	2½	2¾	3	3¼	3½	3¾	4
					Approximate Angles for Milling Machine Table									
6.12	56	40	28	64	42	…	…	…	…	…	…	…	…	…
6.22	56	40	32	72	41½	…	…	…	…	…	…	…	…	…
6.48	56	48	40	72	40¼	44¼	…	…	…	…	…	…	…	…
6.67	64	48	28	56	39½	43½	…	…	…	…	…	…	…	…
7.29	56	48	40	64	37	41	44¼	…	…	…	…	…	…	…
7.41	64	48	40	72	36½	40¼	43¾	…	…	…	…	…	…	…
7.62	64	48	32	56	36	39½	43	…	…	…	…	…	…	…
8.33	48	32	40	72	33½	37	40½	43½	…	…	…	…	…	…
8.95	86	48	28	56	31¾	35¼	38½	41¼	44	…	…	…	…	…
9.33	56	40	48	72	30½	34	37¼	40¼	43	…	…	…	…	…
9.52	64	48	40	56	30	33½	36½	39½	42¼	45	…	…	…	…
10.29	72	40	32	56	28¼	31½	34½	37½	40	42½	45	…	…	…
10.37	64	48	56	72	28	31¼	34¼	37¼	39¾	42¼	44¾	…	…	…
10.50	48	40	56	64	27¾	31	34	36¾	39½	42	44¼	…	…	…
10.67	64	40	48	72	27¼	30½	33½	36½	39	41½	43¾	…	…	…
10.94	56	32	40	64	26¾	30	33	35¾	38¼	40¾	43	…	…	…
11.11	64	32	40	72	26½	29½	32½	35¼	38	40¼	42½	44¾	…	…
11.66	56	32	48	72	25¼	28½	31¼	34	36½	39	41¼	43½	…	…
12.00	72	40	32	48	24¾	27¾	30½	33¼	35¾	38	40¼	42½	44¾	…
13.12	56	32	48	64	22¾	25¾	28¼	31	33¼	35¾	37¾	40	42	43¾
13.33	56	28	48	72	22½	25½	28	30½	33	35¼	37½	39½	41½	43¼
13.71	64	40	48	56	22	24¾	27¼	30	32¼	34½	36½	38¾	40¾	42½
15.24	64	28	48	72	20	22½	25	27¼	29½	31¾	34	35¾	37¾	39½
15.56	64	32	56	72	19½	22	24½	27	29	31¼	33¼	35¼	37	39
15.75	56	64	72	40	19¼	21¾	24¼	26½	28¾	31	33	35	36¾	38½
16.87	72	32	48	64	18¼	20½	22¾	25	27	29¼	31¼	33¼	35	36½
17.14	64	32	48	56	17¾	20¼	22¼	24¾	26¾	29	30¾	32¾	34½	36
18.75	72	32	40	48	16¼	18½	20¾	22¾	25	26¾	28½	30¼	32	33¾
19.29	72	32	48	56	16	18¼	20¼	22¼	24	26	28	29¾	31½	33
19.59	64	28	48	56	15¾	18	20	22	23¾	25¾	27½	29¼	31	32¾
19.69	72	32	56	64	15¾	17¾	20	21¾	23¾	25½	27½	29¼	31	32½
21.43	72	24	40	56	14½	16½	18½	20¼	22	23¾	25½	27¼	29	30¼
22.50	72	28	56	64	13¾	15¾	17½	19¼	21	22¾	24½	26	27¾	29¼
23.33	64	32	56	48	13¼	15¼	17	18¾	20¼	22	23½	25¼	27	28¼
26.25	72	24	56	64	12	13½	15	16¾	18¼	19¾	21¼	22¾	24¼	25½
26.67	64	28	56	48	11¾	13¼	14¾	16½	18	19½	21	22¼	23¾	25¼
28.00	64	32	56	40	11¼	12¾	14¼	15¾	17¼	18¾	20	21½	22¾	24
30.86	72	28	48	40	10	11½	13	14¼	15½	17	18½	19½	21	22
31.50	72	32	56	40	10	11¼	12¾	14	15¼	16½	18	19¼	20½	21¾
36.00	72	32	64	40	8¾	10	11	12¼	13½	14¾	16	17	18¼	19¼
41.14	72	28	64	40	7¾	8¾	9¾	10¾	11¾	13	14	15	16	17
45.00	72	28	56	32	7	8	9	10	11	11¾	12¾	13¾	14¾	15½
48.00	72	24	64	40	6½	7½	8½	9¼	10¼	11¼	12	13	13¾	14½
51.43	72	28	64	32	6	7	7¾	8¾	9½	10½	11¼	12	12¾	13¾
60.00	72	24	64	32	5¼	6	6¾	7½	8¼	9	9½	10¼	11	11¾
68.57	72	24	64	28	4¼	5¼	5¾	6½	7¼	8	8½	9	9¾	10¼

Helix Angle for Given Lead and Diameter.— The table on this and the preceding page gives helix angles (relative to axis) equivalent to a range of leads and diameters. The expression "Diameter of Work" at the top of the table might mean pitch diameter or outside diameter, depending upon the class of work. Assume, for example, that a plain milling cutter 4 inches in diameter is to have helical teeth and a helix angle of about 25 degrees is desired. The table shows that this angle will be obtained approximately by using change-gears that will give a lead of 26.67 inches. As the outside diameter of the cutter is 4 inches,

Copyright 2004, Industrial Press, Inc., New York, NY

the helix angle of 25¼ degrees is at the top of the teeth. The angles listed for different diameters are used in setting the table of a milling machine. In milling a right-hand helix (or cutter teeth that turn to the right as seen from the end of the cutter), swivel the right-hand end of the machine table toward the rear, and, inversely, for a left-hand helix, swivel the left-hand end of the table toward the rear. The angles in the table are based upon the following formula:

$$\text{cot helix angle relative to axis} = \frac{\text{lead of helix}}{3.1416 \times \text{diameter}}$$

Lead of Helix for Given Angle.— The lead of a helix or "spiral" for given angles measured with the axis of the work is given in the table, starting on page 1977, for a diameter of 1. For other diameters, lead equals the value found in the table multiplied by the given diameter. Suppose the angle is 55 degrees, and the diameter 5 inches; what would be the lead? By referring to the table starting on page 1977, it is found that the lead for a diameter of 1 and an angle of 55 degrees 0 minutes equals 2.200. Multiply this value by 5; 5 × 2.200 = 11 inches, which is the required lead. If the lead and diameter are given, and the angle is wanted, divide the given lead by the given diameter, thus obtaining the lead for a diameter equal to 1; then find the angle corresponding to this lead in the table. If the lead and angle are given, and the diameter is wanted, divide the lead by the value in the table for the angle.

Helix Angle for Given Lead and Pitch Radius.— To determine the helix angle for a helical gear, knowing the pitch radius and the lead, use the formula:

$$\tan\psi = 2\pi R/L$$

where ψ = helix angle
R = pitch radius of gear, and
L = lead of tooth

Example:

$$R = 3.000, L = 21.000, \tan\psi = (2 \times 3.1416 \times 3.000)/21.000 = 0.89760$$
$$\therefore \psi = 41.911 \text{ degrees}$$

Helix Angle and Lead, Given Normal DP and Numbers of Teeth.— When N_1 = number of teeth in pinion, N_2 = number of teeth in gear, P_n = normal diametral pitch, C = center distance, ψ = helix angle, L_1 = lead of pinion, and L_2 = lead ofgear, then:

$$\cos\psi = \frac{N_1 + N_2}{2P_nC}, \qquad L_1 = \frac{\pi N_1}{P_n \sin\psi}, \qquad L_2 = \frac{\pi N_2}{P_n \sin\psi}$$

$$P_n = 6, \quad N_1 = 18, \quad N_2 = 30, \quad C = 4.500$$

$$\cos\psi = \frac{18 + 30}{2 \times 6 \times 4.5} = 0.88889, \therefore \psi = 27.266^\circ, \text{ and } \sin\psi = 0.45812$$

$$L_1 = \frac{3.1416 \times 18}{6 \times 0.45812} = 20.5728, \text{and } L_2 = \frac{3.1416 \times 30}{6 \times 0.45812} = 34.2880$$

Lead of Tooth Given Pitch Radius and Helix Angle.— To determine the lead of the tooth for a helical gear, given the helix angle and the pitch radius, the formula becomes: $L = 2\pi R/\tan\psi$.

$$\psi = 22.5^\circ, \qquad \therefore \tan\psi = 0.41421, \qquad R = 2.500.$$
$$L = \frac{2 \times 3.1416 \times 2.500}{0.41421} = 37.9228$$

Copyright 2004, Industrial Press, Inc., New York, NY

SIMPLE, COMPOUND, DIFFERENTIAL, AND BLOCK INDEXING

Milling Machine Indexing.— Positioning a workpiece at a precise angle or interval of rotation for a machining operation is called indexing. A dividing head is a milling machine attachment that provides this fine control of rotational positioning through a combination of a crank-operated worm and worm gear, and one or more indexing plates with several circles of evenly spaced holes to measure partial turns of the worm crank. The indexing crank carries a movable indexing pin that can be inserted into and withdrawn from any of the holes in a given circle with an adjustment provided for changing the circle that the indexing pin tracks.

Hole Circles.— The Brown & Sharpe dividing head has three standard indexing plates, each with six circles of holes as listed in the table below.

Numbers of Holes in Brown & Sharpe Standard Indexing Plates

Plate Number	Numbers of Holes					
1	15	16	17	18	19	20
2	21	23	27	29	31	33
3	37	39	41	43	47	49

Dividing heads of Cincinnati Milling Machine design have two-sided, standard, and high-number plates with the numbers of holes shown in the following table.

Numbers of Holes in Cincinnati Milling Machine Standard Indexing Plates

Side	Standard Plate										
1	24	25	28	30	34	37	38	39	41	42	43
2	46	47	49	51	53	54	57	58	59	62	66
	High-Number Plates										
A	30	48	69	91	99	117	129	147	171	177	189
B	36	67	81	97	111	127	141	157	169	183	199
C	34	46	79	93	109	123	139	153	167	181	197
D	32	44	77	89	107	121	137	151	163	179	193
E	26	42	73	87	103	119	133	149	161	175	191
F	28	38	71	83	101	113	131	143	159	173	187

Some dividing heads provide for *Direct Indexing* through the attachment of a special indexing plate directly to the main spindle where a separate indexing pin engages indexing holes in the plate. The worm is disengaged from the worm gear during this quick method of indexing, which is mostly used for common, small-numbered divisions such as six, used in machining hexagonal forms for bolt heads and nuts, for instance.

Simple Indexing.— Also called *Plain Indexing* or *Indirect Indexing*, simple indexing is based on the ratio between the worm and the worm gear, which is usually, but not always, 40:1. All the tables in this section are based on a 40:1 gear ratio, except for Table 8 on page 2023 that gives indexing movements for dividing heads utilizing a 60:1 gear ratio.

The number of turns of the indexing crank needed for each indexing movement to produce a specified number of evenly spaced divisions is equal to the number of turns of the crank that produce exactly one full turn of the main spindle, divided by the specified number of divisions required for the workpiece. The accompanying tables in this section provide data for the indexing movements to meet most division requirements, and include the simple indexing movements along with the more complex movements for divisions that are not available through simple indexing. The fractional entries in the tables are deliberately not reduced to lowest terms. Thus, the numerator represents the number of holes to be moved on the circle of holes specified by the denominator.

Copyright 2004, Industrial Press, Inc., New York, NY

Setting up for an indexing job includes setting the sector arms to the fractional part of a turn required for each indexing movement to avoid the need to count holes each time. The current location of the indexing pin in the circle of holes to be used is always hole zero when counting the number of holes to be moved. The wormshaft hub carrying the dividing plate may also carry one or two sets of sector arms, each of which can be used to define two arcs of holes. As shown at the right in the drawing of a typical dividing head at the top of the table *Simple and Differential Indexing with Browne & Sharpe Indexing Plates* on page 2011, these sector arms can make up an inner arc, A, and an outer arc, B. The inner arc is used most often, but some indexing movements require the use of the outer arc.

Example: With a worm/worm gear ratio of 40:1 making 35 divisions requires each indexing movement to be 40 ÷ 35 = 1 5/7 turns: one full turn of the indexing crank plus one-seventh of a full turn more. A full turn is easily achieved using any circle of holes, but to continue the indexing movement to completion for this example requires a circle in which the number of holes is evenly divisible by 7. The Brown & Sharpe dividing head has a 21-hole circle on plate 2 and a 49-hole circle on plate 3. Either circle could be used because 3/21 and 7/49 both equal 1/7th. The Cincinnati dividing head standard plate has a 28-hole circle on the first side and a 49-hole circle on the second side and again, either 4/28 or 7/49 could be used for the fractional part of a turn needed for 35 divisions. In selecting among equivalent indexing solutions, the one with the smallest number of holes in the fractional part of a turn is generally preferred (except that if an indexing plate with an alternate solution is already mounted on the dividing head, the alternate should be used to avoid switching indexing plates).

Compound Indexing.— Compound indexing is used to obtain divisions that are not available by simple indexing. Two simple indexing movements are used with different circles of holes on an indexing plate that is not bolted to the dividing head frame so that it is free to rotate on the worm shaft. A second, stationary indexing pin arrangement is clamped or otherwise fixed to the frame of the dividing head to hold the indexing plate in position except during the second portion of the compound indexing movement. If available, a double set of low-profile sector arms would improve the ease and reliability of this method. Sector arms for the innermost circle of an indexing movement should not reach as far as the outermost circle of the movement, and sector arms for the outermost circle should be full length. Positioning the outermost circle sector arms may have to wait until the indexing pin on the innermost circle is withdrawn, and may sometimes coincide with the position of that pin. The indexing pin on the crank is set to track the innermost of the two circles in the compound movement and the stationary indexing pin is set to track the outermost circle. Some divisions are only available using adjacent circles, so the intercircle spacing may become a constraining factor in the design or evaluation of a stationary pin arrangement.

The first part of the indexing movement is performed as in simple indexing by withdrawing the indexing pin on the crank arm from its hole in the indexing plate, rotating the crank to its next position, and reinserting the indexing pin in the new hole. For the second part of the movement, the stationary indexing pin is released from its hole in the indexing plate, and with the crank indexing pin seated in its hole, the crank is used to turn the crank arm and indexing plate together to the next position for reinserting the stationary pin into its new hole.

There are two possibilities for the separate movements in compound indexing: they may both be in the same direction of rotation, referred to as *positive compounding* and indicated in the table by a plus (+) sign between the two indexing movements, or they may be in opposite directions of rotation, referred to as *negative compounding* and indicated in the table by a minus (–) sign between the two indexing movements. In positive compounding, it does not matter whether the rotation is clockwise or counterclockwise, as long as it is the same throughout the job. In negative compounding, there will be one clockwise movement and one counterclockwise movement for each unit of the division. The mathematical difference is in whether the two fractional turns are to be added together or whether one is to

Copyright 2004, Industrial Press, Inc., New York, NY

be subtracted from the other. Operationally, this difference is important because of the backlash, or free play, between the worm and the worm gear of the dividing head. In positive compounding, this play is always taken up because the worm is turned continually in the same direction. In negative compounding, however, the direction of each turn is always opposite that of the previous turn, requiring each portion of each division to be started by backing off a few holes to allow the play to be taken up before the movement to the next position begins.

The Tables 1a and 1b, *Simple and Compound Indexing with Brown & Sharpe Plates*, gives indexing movements for all divisions up to and including 250 with plain dividing heads of the Brown & Sharpe design. All the simple indexing movements, and many of the compound indexing movements, are exact for the divisions they provide. There remains a substantial number of divisions for which the indexing movements are approximate. For these divisions, the indexing movements shown come very close to the target number, but the price of getting close is increased length and complexity of the indexing movements. The table shows all divisions that can be obtained through simple indexing and all divisions for which exact compound indexing movements are available. Approximate movements are only used when it is necessary to obtain a division that would otherwise not be available. The approximate indexing movements usually involve multiple revolutions of the workpiece, with successive revolutions filling in spaces left during earlier turns.

Table 1a. Simple and Compound Indexing with Brown & Sharpe Plates

Number of Divisions	Whole Turns	Fractions of a Turn	Number of Divisions	Whole Turns	Fractions of a Turn	Number of Divisions	Whole Turns	Fractions of a Turn
2	20	…	15	2	26/39	33	1	7 /33
3	13	5/15	16	2	8/16	34	1	3 /17
3	13	7/21	17	2	6/17	35	1	3 /21
3	13	13/39	18	2	4/18	35	1	7 /49
4	10	…	18	2	6/27	36	1	2 /18
5	8	…	19	2	2/19	36	1	3 /27
6	6	10/15	20	2	…	37	1	3 /37
6	6	14/21	21	1	19/21	38	1	1 /19
6	6	26/39	22	1	27/33	39	1	1 /39
7	5	15/21	23	1	17/23	40	1	…
8	5	…	24	1	10/15	41	…	40 /41
9	4	8/18	24	1	14/21	42	…	20 /21
9	4	12/27	24	1	26/39	43	…	40 /43
10	4	…	25	1	9/15	44	…	30 /33
11	3	21/33	26	1	21/39	45	…	16 /18
12	3	5/15	27	1	13/27	45	…	24 /27
12	3	7/21	28	1	9/21	46	…	20 /23
12	3	13/39	29	1	11/29	47	…	40 /47
13	3	3/39	30	1	5/15	48	…	15 /18
14	2	18/21	30	1	7/21	49	…	40 /49
14	2	42/49	30	1	13/39	50	…	12 /15
15	2	10/15	31	1	9/31			
15	2	14/21	32	1	4/16			

Table 1b. Simple and Compound Indexing with Brown & Sharpe Plates

Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001	Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001
51	10/15 + 2/17	1	51.00000	Exact	57	5/15 + 7/19	1	57.00000	Exact
51[a]	$7^{41}/_{47}$ + 37/49	11	51.00005	322.55	57[a]	$4^{40}/_{47}$ + 3/49	7	56.99991	205.26
52	30/39	1	52.00000	Exact	58	20/29	1	58.00000	Exact
53	26/29 + 19/31	2	52.99926	22.89	59	18/37 + 9/47	1	58.99915	22.14
53	14/43 + $4^{45}/_{47}$	7	52.99991	180.13	59	$4^{2}/_{43}$ + 1/47	6	59.00012	154.39
53[a]	$5^{43}/_{47}$ + 43/49	9	53.00006	263.90	59[a]	$7^{10}/_{47}$ + 12/49	11	58.99971	64.51
54	20/27	1	54.00000	Exact	59	$5^{15}/_{37}$ + $3^{3}/_{49}$	13	58.99994	300.09
55	24/33	1	55.00000	Exact	60	10/15	1	60.00000	Exact
56	15/21	1	56.00000	Exact	60	14/21	1	60.00000	Exact
56	35/49	1	56.00000	Exact	60	26/39	1	60.00000	Exact

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. ***(Continued)*** **Simple and Compound Indexing with Brown & Sharpe Plates**

Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001	Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001
61	$2^{3}/_{43} + 26/47$	4	60.99981	102.93	94	20/47	1	94.00000	Exact
61[a]	$3^{45}/_{47} + 2/49$	6	60.99989	175.94	95	8/19	1	95.00000	Exact
61	$4^{31}/_{41} + 2/49$	8	61.00009	204.64	96[a]	3/18 + 5/20	1	96.00000	Exact
62	20/31	1	62.00000	Exact	97	15/41 + 2/43	1	97.00138	22.45
63	11/21 + 3/27	1	63.00000	Exact	97	$1^{42}/_{43} + 4/47$	5	97.00024	128.66
63[a]	$4^{19}/_{29} + 14/33$	8	62.99938	32.49	97[a]	$3^{27}/_{41} + 43/49$	11	96.99989	281.37
64	10/16	1	64.00000	Exact	98	20/49	1	98.00000	Exact
65	24/39	1	65.00000	Exact	99[a]	6/27 + 6/33	1	99.00000	Exact
66	20/33	1	66.00000	Exact	100	6/15	1	100.00000	Exact
67	29/37 + 16/39	2	66.99942	36.75	101	$1^{33}/_{43} + 10/47$	5	100.99950	64.33
67	$2^{27}/_{41} + 16/49$	5	67.00017	127.90	101	$2^{27}/_{57} + 2/47$	7	100.99979	154.99
67	$4^{30}/_{43} + 2^{5}/_{49}$	11	67.00007	295.10	101[a]	$3^{32}/_{43} + 30/49$	11	101.00011	295.10
68	10/17	1	68.00000	Exact	102	5/15 + 1/17	1	102.00000	Exact
69	14/21 − 2/23	1	69.00000	Exact	102[a]	$3^{17}/_{43} + 45/49$	11	102.00022	147.55
69[a]	19/23 + 11/33	2	69.00000	Exact	103[a]	$1^{8}/_{43} + 18/49$	4	103.00031	107.31
70	12/21	1	70.00000	Exact	103	$2^{22}/_{57} + 21/41$	8	103.00021	154.52
70	28/49	1	70.00000	Exact	103	$4^{32}/_{57} + 9/49$	13	103.00011	300.09
71	35/37 + 32/43	3	71.00037	60.77	104	15/39	1	104.00000	Exact
71[a]	$2^{34}/_{41} + 27/49$	6	70.99985	153.48	105	8/21	1	105.00000	Exact
71	$4^{25}/_{39} + 2^{28}/_{41}$	13	70.99991	264.67	106	$1^{7}/_{39} + 29/41$	5	105.99934	50.90
72	10/18	1	72.00000	Exact	106	$2^{12}/_{41} + 15/43$	7	105.99957	78.57
72	15/27	1	72.00000	Exact	106[a]	$2^{38}/_{41} + 23/49$	9	106.00029	115.11
73	5/43 + 48/49	2	73.00130	17.88	107	23/43+ 10/47	2	107.00199	17.15
73	$2^{19}/_{43} + 14/47$	5	72.99982	128.66	107[a]	$1^{21}/_{31} + 31/33$	7	107.00037	91.18
73	$2^{28}/_{47} + 3^{48}/_{49}$	12	73.00007	351.87	107	$2^{38}/_{41} + 3/47$	8	106.99983	196.28
73[a]	$5^{28}/_{47} + 48/49$	12	73.00007	351.87	107	$3^{38}/_{39} + 22/43$	12	106.99987	256.23
74	20/37	1	74.00000	Exact	108	10/27	1	108.00000	Exact
75	8/15	1	75.00000	Exact	109	$1^{8}/_{21} + 2/23$	4	108.99859	24.60
76	10/19	1	76.00000	Exact	109	$1^{34}/_{57} + 26/47$	6	108.99974	132.85
77[a]	9/21 + 3/33	1	77.00000	Exact	109[a]	$2^{19}/_{39} + 4/49$	7	108.99980	170.32
78	20/39	1	78.00000	Exact	110	12/33	1	110.00000	Exact
79	17/37 + 26/47	2	79.00057	44.28	111	1/37 + 13/39	1	111.00000	Exact
79[a]	$2^{42}/_{43} + 3/49$	6	79.00016	160.96	111[a]	$3^{33}/_{47} + 17/49$	11	111.00011	322.55
79	$4^{34}/_{39} + 9/47$	10	79.00011	233.38	112[a]	$3^{10}/_{41} + 20/33$	11	111.99801	17.91
80	8/16	1	80.00000	Exact	112	$33/43 + 2^{21}/_{47}$	9	112.00123	28.95
81	10/43 + 37/49	2	80.99952	53.65	112	$14/37 + 4^{46}/_{47}$	15	112.00086	41.52
81	$3^{9}/_{47} + 13/49$	7	80.99987	205.26	112	$9^{14}/_{57} + 46/47$	29	112.00044	80.26
81[a]	$4^{5}/_{41} + 40/49$	10	80.99990	255.79	113	14/37 − 1/41	1	112.99814	19.32
81	$5^{11}/_{57} + 1^{6}/_{49}$	13	81.00009	300.09	113	$2^{28}/_{41} + 7/47$	8	112.99982	196.28
82	20/41	1	82.00000	Exact	113[a]	$2^{28}/_{47} + 31/49$	9	112.99986	263.90
83	$1^{11}/_{29} + 17/31$	4	83.00058	45.79	113	$4^{20}/_{57} + 3/49$	13	113.00012	300.09
83[a]	$2^{45}/_{47} + 44/49$	8	83.00034	78.19	114[a]	10/15 − 6/19	1	114.00000	Exact
83	$3^{17}/_{27} + 7/31$	8	82.99969	85.26	114	$1^{35}/_{57} + 25/49$	7	113.99955	80.79
83	$5^{1}/_{57} + 31/41$	12	83.00011	231.78	115	8/23	1	115.00000	Exact
84	10/21	1	84.00000	Exact	116	10/29	1	116.00000	Exact
85	8/17	1	85.00000	Exact	117	$1^{16}/_{41} + 15/47$	5	117.00061	61.34
86	20/43	1	86.00000	Exact	117	$7^{1}/_{47} - 9/49$	20	117.00006	586.45
87	14/21 − 6/29	1	87.00000	Exact	117[a]	$6^{1}/_{47} + 40/49$	20	117.00006	586.45
87	17/29 + 11/33	2	87.00000	Exact	118[a]	$1^{8}/_{39} + 24/49$	5	117.99938	60.83
88	15/33	1	88.00000	Exact	118	$30/41 + 2^{15}/_{47}$	9	117.99966	110.41
89	$1^{29}/_{57} + 19/41$	5	88.99971	96.58	119	15/43 + 31/47	3	118.99902	38.60
89	$2^{22}/_{57} + 5/49$	6	88.99980	138.50	119[a]	$2^{4}/_{23} + 17/33$	8	119.00049	77.31
89[a]	$2^{28}/_{39} + 43/49$	8	89.00015	194.65	119	$3^{31}/_{57} + 25/47$	13	118.99987	287.84
90	8/18	1	90.00000	Exact	120	5/15	1	120.00000	Exact
90	12/27	1	90.00000	Exact	120	7/21	1	120.00000	Exact
91[a]	6/39 +14/49	1	91.00000	Exact	120	13/39	1	120.00000	Exact
92	10/23	1	92.00000	Exact	121	8/37 + 38/49	3	121.00111	34.63
93	7/21+3/31	1	93.00000	Exact	121[a]	14/47 + 34/49	3	120.99825	21.99
93[a]	3/31 + 11/33	1	93.00000	Exact	121	$1^{4}/_{43} + 2^{10}/_{47}$	10	120.99985	257.32

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. ***(Continued)*** **Simple and Compound Indexing with Brown & Sharpe Plates**

Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001	Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001
122	$1\frac{14}{41} + 14/47$	5	122.00063	61.34	147	13/39 − 3/49	1	147.00000	Exact
122	$41/43 + 2\frac{35}{49}$	11	122.00026	147.55	147[a]	13/39 + 37/49	4	147.00000	Exact
122[a]	$2\frac{41}{43} + 32/49$	11	122.00026	147.55	148	10/37	1	148.00000	Exact
123	26/39 − 14/41	1	123.00000	Exact	149	28/41 + 6/49	3	148.99876	38.37
123[a]	$1\frac{12}{43} + 17/49$	5	123.00058	67.07	149[a]	$1\frac{7}{39} + 7/43$	5	149.00044	106.76
124	10/31	1	124.00000	Exact	149[a]	$2\frac{5}{43} + 41/49$	11	149.00032	147.55
125	41/43 +16/49	4	124.99815	21.46	149	$26/37 + 2\frac{37}{47}$	13	148.99984	287.84
125	$1\frac{33}{41} + 37/49$	8	125.00097	40.93	150	4/15	1	150.00000	Exact
125	$2\frac{5}{43} + 8/47$	7	125.00110	36.03	151	5/37 + 31/47	3	150.99855	33.21
125	$3/41 + 3\frac{31}{47}$	11	125.00074	53.98	151[a]	42/43 + 43/49	7	151.00077	62.60
126	2/21 + 6/27	1	126.00000	Exact	151	6/37 + 35/39	4	151.00065	73.49
126	$2\frac{16}{19} + 13/20$	11	125.99849	26.61	151	$2\frac{31}{43} + 20/47$	11	151.00017	283.05
127	2/39 + 42/47	3	126.99769	17.50	152	5/19	1	152.00000	Exact
127	$2\frac{6}{37} + 2/47$	7	127.00052	77.50	153	10/18 − 5/17	1	153.00000	Exact
127[a]	$2\frac{23}{39} + 12/49$	9	127.00018	218.98	153[a]	$1\frac{45}{47} + 45/49$	11	153.00015	322.55
128	5/16	1	128.00000	Exact	154[a]	1/21 + 7/33	1	154.00000	Exact
129	13/39 − 1/43	1	129.00000	Exact	155	8/31	1	155.00000	Exact
129[a]	$5\frac{34}{41} + 15/49$	19	128.99966	121.50	156	10/39	1	156.00000	Exact
130	12/39	1	130.00000	Exact	157	18/47 − 5/39	1	157.00214	23.34
131	5/37 + 8/47	1	130.99812	22.14	157	22/47 + 27/49	4	157.00043	117.29
131[a]	$2\frac{40}{43} + 21/49$	11	130.99901	42.16	157[a]	$2\frac{23}{31} + 2/33$	11	157.00035	143.28
131	$4/37 + 1\frac{18}{43}$	5	131.00041	101.29	157	$22/41 + 2\frac{38}{49}$	13	157.00030	166.27
131	$2\frac{27}{43} + 20/47$	10	130.99984	257.32	158[a]	$4\frac{5}{43} + 34/49$	19	157.99901	50.97
132	10/33	1	132.00000	Exact	158	$1\frac{4}{39} + 8/49$	5	157.99917	60.83
133	1/37 + 27/47	2	133.00191	22.14	158	$1\frac{29}{39} + 23/43$	9	158.00052	96.09
133	12/31 + 17/33	3	133.00108	39.08	159	14/37 + 27/43	4	159.00062	81.03
133[a]	$2\frac{23}{29} + 17/33$	11	133.00063	67.02	159	$1\frac{19}{43} + 15/47$	7	158.99972	180.13
133	$1\frac{23}{29} + 19/31$	8	133.00046	91.57	159[a]	$2\frac{7}{37} + 16/49$	10	159.00022	230.84
134	4/29 + 25/33	3	134.00233	18.28	160	4/16	1	160.00000	Exact
134	$1\frac{13}{43} + 37/47$	7	133.99953	90.06	161	9/23 − 3/21	1	161.00000	Exact
134[a]	$3\frac{27}{47} + 15/49$	13	134.00022	190.60	161[a]	$1\frac{10}{39} + 48/49$	9	161.00164	31.28
135	8/27	1	135.00000	Exact	162	28/47 − 15/43	1	162.00401	12.87
136	5/17	1	136.00000	Exact	162	$1\frac{30}{39} - 2/49$	7	161.99818	28.39
137	9/37 + 31/49	3	137.00252	17.31	162[a]	$\frac{30}{39} + 47/49$	7	161.99818	28.39
137	$11/41 + 1\frac{38}{49}$	7	136.99951	89.53	162	$2\frac{6}{23} + 25/29$	13	161.99907	55.20
137	$17/43 + 2\frac{40}{49}$	11	137.00015	295.10	163	18/49 − 5/41	1	163.00203	25.58
137[a]	$2\frac{17}{43} + 40/49$	11	137.00015	295.10	163	19/37 + 22/47	4	162.99941	88.57
138	7/21 − 1/23	1	138.00000	Exact	163[a]	$2\frac{7}{37} + 25/49$	11	162.99959	126.96
138[a]	18/23 + 22/33	5	138.00000	Exact	163	$2\frac{31}{47} + 26/49$	13	162.99986	381.20
139	23/41 + 13/43	3	139.00131	33.67	164	10/41	1	164.00000	Exact
139	$1\frac{31}{39} + 9/41$	7	139.00031	142.51	165	8/33	1	165.00000	Exact
139	$3\frac{14}{43} + 6/47$	12	138.99986	308.79	166	20/29 + 17/33	5	166.00173	30.46
139[a]	$2\frac{25}{37} + 24/49$	11	138.99983	253.92	166[a]	$1\frac{19}{43} + 12/49$	7	165.99887	46.95
140	6/21	1	140.00000	Exact	166	$2\frac{30}{41} + 7/43$	11	166.00043	123.46
141	29/47 − 13/39	1	141.00000	Exact	167[a]	$2\frac{1}{29} + 4/33$	9	166.99952	109.66
141[a]	$1\frac{32}{39} + 22/49$	8	141.00069	64.88	167	23/43 + 9/49	3	167.00132	40.24
142	23/39 + 12/47	3	142.00129	35.01	167	6/37 + 39/49	4	167.00058	92.34
142	$18/41 + 2\frac{33}{47}$	11	141.99967	134.94	167	$2\frac{38}{37} + 20/43$	13	167.00040	131.67
142[a]	$4\frac{1}{47} + 10/49$	15	141.99979	219.92	168	5/21	1	168.00000	Exact
143[a]	36/47 + 31/49	5	142.99907	48.87	169	1/41 + 22/49	2	169.00105	51.16
143	13/37 + 20/41	3	143.00079	57.95	169[a]	$1\frac{32}{37} + 13/49$	9	169.00052	103.88
143	$1\frac{16}{27} + 20/31$	8	143.00053	85.26	170	4/17	1	170.00000	Exact
144	5/18	1	144.00000	Exact	171	8/18 − 4/19	1	171.00000	Exact
145	8/29	1	145.00000	Exact	171[a]	$1\frac{29}{47} + 1/49$	7	170.99973	205.26
146	16/41 − 5/43	1	146.00414	11.22	172	10/43	1	172.00000	Exact
146	$3/37 + 1\frac{41}{49}$	7	145.99942	80.79	173	27/37 + 8/41	4	173.00071	77.26
146[a]	$1\frac{3}{37} + 41/49$	7	145.99942	80.79	173[a]	$1\frac{7}{43} + 11/49$	6	173.00034	160.96
146	$28/37 + 2\frac{33}{41}$	13	146.00037	125.55					

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. ***(Continued)*** **Simple and Compound Indexing with Brown & Sharpe Plates**

Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001	Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001
174	7/21 − 3/29	1	174.00000	Exact	199	16/41 + 10/47	3	199.00172	36.80
174[a]	14/29 + 22/33	5	174.00000	Exact	199	26/37 + 13/43	5	198.99937	101.29
175	3/37 + 26/43	3	174.99542	12.15	199[a]	$1\frac{12}{41}$ + 45/49	11	199.00045	140.69
175[a]	$1\frac{4}{31}$ + 8/33	6	174.99644	15.63	199	$1\frac{41}{43}$ + 31/47	13	199.00019	334.52
175	$1\frac{9}{37}$ + 5/39	6	174.99747	22.05	200	3/15	1	200.00000	Exact
175	$2\frac{8}{41}$ + 15/47	11	175.00103	53.98	201	27/37 + 13/49	5	200.99778	28.85
176[a]	$1\frac{14}{43}$ + 13/49	7	176.00239	23.47	201	$1\frac{18}{41}$ + 27/49	10	201.00050	127.90
176	$2\frac{18}{37}$ + 22/47	13	175.99844	35.98	201[a]	$2\frac{18}{47}$ + 10/49	13	201.00034	190.60
177	6/37 + 3/47	1	176.99746	22.14	201	$2\frac{5}{41}$ + 20/43	13	200.99978	291.81
177	$1\frac{17}{37}$ + 6/49	7	177.00139	40.40	202	24/37 + 14/41	5	201.99734	24.14
177[a]	$2\frac{19}{47}$ + 4/49	11	176.99913	64.51	202[a]	$3\frac{10}{41}$ + 6/49	17	201.99911	72.47
178	$1\frac{16}{39}$ + 7/43	7	177.99848	37.37	202	1/43 + $2\frac{27}{49}$	13	201.99853	43.59
178[a]	$3\frac{28}{47}$ + 11/49	17	177.99955	124.62	203	14/29 − 6/21	1	203.00000	Exact
178	$2\frac{11}{41}$ + 32/49	13	177.99966	166.27	203[a]	$1\frac{23}{39}$ + 9/49	9	202.99793	31.28
179	20/37 − 13/41	1	178.99705	19.31	204	9/17 − 5/15	1	204.00000	Exact
179	14/39 + 23/43	4	178.99933	85.41	204[a]	$2\frac{30}{41}$ + 3/49	13	203.99922	83.13
179[a]	$1\frac{34}{47}$ + 36/49	11	179.00018	322.55	205	8/41	1	205.00000	Exact
180	4/18	1	180.00000	Exact	206	1/41 + 24/43	3	205.99805	33.67
180	6/27	1	180.00000	Exact	206	$2\frac{8}{39}$ + 15/47	13	205.99957	151.70
181	20/37 + 6/49	3	180.99834	34.63	206[a]	$2\frac{34}{39}$ + 2/49	15	206.00072	91.24
181[a]	$2\frac{8}{43}$ + 12/49	11	180.99961	147.55	207	5/23 + 15/27	4	207.00000	Exact
181	39/41 + 28/47	7	180.99966	171.75	207[a]	$2\frac{8}{41}$ + 25/49	14	206.99908	71.62
181	$2\frac{8}{39}$ + 21/47	12	180.99979	280.06	208	8/43 + 38/49	5	207.99605	16.77
182[a]	3/39 + 7/49	1	182.00000	Exact	208[a]	$1\frac{19}{47}$ + 16/49	9	207.99799	32.99
183	8/29 + 5/31	2	183.00254	22.89	208	$3\frac{35}{43}$ + 11/49	21	208.00094	70.42
183	1/43 + 40/47	4	182.99943	102.93	209[a]	9/41 + 8/49	2	208.99870	51.16
183[a]	$1\frac{24}{41}$ + 8/49	8	183.00028	204.64	209	$1\frac{36}{41}$ + 18/43	12	208.99975	269.37
184	5/23	1	184.00000	Exact	210	4/21	1	210.00000	Exact
185	8/37	1	185.00000	Exact	211[a]	$1\frac{28}{39}$ + 18/49	11	211.00125	53.53
186	17/31 − 7/21	1	186.00000	Exact	211	35/37 + 9/47	6	211.00101	66.42
186[a]	3/31 + 11/33	2	186.00000	Exact	211	$1\frac{10}{37}$ + 17/39	9	210.99919	82.68
187	19/37 + 5/39	3	186.99784	27.56	211	$1\frac{33}{41}$ + 31/47	13	211.00021	318.96
187[a]	$1\frac{20}{47}$ + 14/49	8	186.99822	33.51	212	34/39 + 22/49	7	211.99683	21.29
187	21/23 + 10/27	6	187.00125	47.44	212	$1\frac{5}{43}$ + 47/49	11	212.00091	73.77
187	$1\frac{38}{43}$ + 12/47	10	186.99977	257.32	212[a]	$3\frac{4}{47}$ + 6/49	17	211.99946	124.62
188	10/47	1	188.00000	Exact	213[a]	$1\frac{18}{39}$ + 2/49	8	212.99896	64.88
189	7/27 − 1/21	1	189.00000	Exact	213	14/37 + 44/47	7	213.00087	77.50
189[a]	$1\frac{26}{41}$ + 34/49	11	189.00150	40.20	213	$2\frac{36}{37}$ + 9/41	17	213.00021	328.36
190	4/19	1	190.00000	Exact	214	7/39 + 37/49	5	213.99776	30.41
191	1/21 + 18/31	3	191.00244	24.87	214[a]	$2\frac{9}{47}$ + 30/49	15	214.00031	219.92
191[a]	$1\frac{38}{47}$ + 14/49	10	191.00145	41.89	215	8/43	1	215.00000	Exact
191	34/37 + 5/39	5	190.99934	91.86	216	5/27	1	216.00000	Exact
191	28/39 + 45/47	8	190.99967	186.71	217	12/21 − 12/31	1	217.00000	Exact
192	5/15 − 2/16	1	192.00000	Exact	217[a]	$2\frac{5}{43}$ + 16/49	13	217.00139	49.82
192[a]	$1\frac{22}{41}$ + 37/49	11	191.99826	35.17	218	14/39 + 9/47	3	217.99802	35.01
193[a]	5/37 + 34/49	4	193.00067	92.34	218[a]	22/47 + 40/49	7	217.99865	51.31
193	29/39 + 12/41	5	192.99940	101.80	218	19/37 + $1\frac{34}{39}$	13	218.00116	59.71
194	41/43 + 24/49	7	194.00197	31.30	219	24/39 + 14/47	5	218.99642	19.45
194[a]	$1\frac{22}{37}$ + 33/49	11	193.99805	31.74	219[a]	$2\frac{28}{43}$ + 39/49	19	218.99891	63.71
194	$1\frac{23}{37}$ + 11/47	9	194.00062	99.64	219	$1\frac{2}{37}$ + 11/49	7	218.99914	80.79
194	$2\frac{8}{47}$ + 25/49	13	193.99968	190.60	219	$2\frac{11}{41}$ + 41/49	17	218.99968	217.42
195	8/39	1	195.00000	Exact	220	6/33	1	220.00000	Exact
196	10/49	1	196.00000	Exact	221	26/37 + 1/47	4	221.00079	88.57
197	17/37 − 10/39	1	196.99659	18.37	221[a]	5/47 + 48/49	6	220.99960	175.94
197	19/39 + 5/41	3	197.00205	30.54	221	$3\frac{9}{41}$ + 25/43	21	220.99985	471.39
197[a]	$1\frac{39}{43}$ + 16/49	11	196.99958	147.55	222	19/37 − 13/39	1	222.00000	Exact
198[a]	3/27 + 3/33	1	198.00000	Exact	222[a]	$1\frac{8}{43}$ + 39/49	11	222.00192	36.89

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. ***(Continued)*** **Simple and Compound Indexing with Brown & Sharpe Plates**

Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001	Target Divisions	Indexing Movements	Workpiece Revolutions	Precise Number of Divisions	Diameter at Which Error = 0.001
223	6/37 + 36/49	25	223.00123	57.71	239	1/37 + 12/39	2	239.00621	12.25
223	$1^{26}/_{37}$ + 38/47	14	222.99977	309.98	239	32/39 + 9/49	6	238.99948	145.99
223[a]	$2^{26}/_{43}$ + 13/49	16	222.99983	429.23	239[a]	$1^{23}/_{43}$ + 15/49	11	238.99974	295.10
223	$3^{11}/_{41}$ + 15/47	20	223.00014	490.71	239	$2^{3}/_{41}$ + 26/43	16	239.00021	359.16
224	$1^{13}/_{37}$ + 11/43	9	223.99687	22.79	240	3/18	1	240.00000	Exact
224	$2^{16}/_{39}$ + 11/41	15	224.00187	38.17	241	4/39 + 17/43	3	241.00599	12.81
224[a]	$2^{8}/_{21}$ + 2/33	13	223.99546	15.70	241	26/41 + 17/47	6	241.00052	147.21
224	$3^{5}/_{43}$ + 13/47	19	223.99883	61.11	241[a]	$1^{1}/_{41}$ + 23/49	9	240.99967	230.21
225	1/15 + 2/18	1	225.00000	Exact	241	$1^{25}/_{37}$ + 35/43	15	240.99975	303.86
225[a]	1/18 + 6/20	2	225.00000	Exact	242	4/37 + 19/49	3	242.00222	34.63
226	28/37 + 5/39	5	225.99843	45.93	242	$1^{37}/_{39}$ + 26/49	15	242.00084	91.24
226[a]	$1^{38}/_{39}$ + 16/49	13	225.99955	158.16	242[a]	$1^{21}/_{41}$ + 45/49	15	241.99960	191.85
227	9/39 + 14/47	3	226.99690	23.34	242	$2^{22}/_{39}$ + 39/43	21	241.99966	224.20
227	$1^{11}/_{37}$ + 25/39	11	227.00036	202.10	243	22/37 + 3/47	4	243.00437	17.71
227[a]	$3^{3}/_{43}$ + 5/49	18	226.99985	482.89	243	32/41 + 2/47	5	243.00126	61.34
228	5/15 − 3/19	1	228.00000	Exact	243[a]	29/41 + 46/49	10	242.99970	255.79
229	7/39 + 34/49	5	228.99940	121.66	244	36/39 + 11/49	7	243.99453	14.19
229[a]	$1^{19}/_{41}$ + 31/49	12	229.00024	306.95	244	$1^{30}/_{37}$ + 8/39	9	244.00188	41.34
229	$2^{35}/_{41}$ + 20/43	19	229.00017	426.50	244	$2^{15}/_{31}$ + 10/33	17	243.99860	55.36
230	4/23	1	230.00000	Exact	244[a]	$1^{28}/_{37}$ + 2/43	11	244.00139	55.71
231[a]	3/21 + 1/33	1	231.00000	Exact	245	8/49	1	245.00000	Exact
232	5/29	1	232.00000	Exact	246	13/39 − 7/41	1	246.00000	Exact
233	2/37 + 31/49	4	232.99598	18.47	246[a]	6/43 + 33/49	5	246.00117	67.07
233[a]	$1^{36}/_{47}$ + 6/49	11	233.00069	107.52	247	17/37 + 21/41	6	247.00136	57.59
233	21/37 + 26/41	7	233.00055	135.21	247	15/43 + $1^{45}/_{49}$	14	247.00021	375.58
233	$1^{23}/_{37}$ + 41/43	15	232.99976	303.86	247[a]	$1^{15}/_{43}$ + 45/49	14	247.00021	375.58
234[a]	$2^{21}/_{29}$ + 6/33	17	234.00216	34.52	248	5/31	1	248.00000	Exact
234	8/41 + 31/47	5	234.00121	61.34	249	20/37 + 5/49	4	248.99571	18.47
234	$2^{17}/_{43}$ + 24/47	17	233.99966	218.72	249	10/37 + $1^{46}/_{47}$	14	249.00026	309.98
235	8/47	1	235.00000	Exact	249	4/43 + $2^{47}/_{49}$	19	249.00016	509.72
236	22/37 + 29/49	7	236.00186	40.40	249[a]	$2^{4}/_{43}$ + 47/49	19	249.00016	509.72
236[a]	$2^{30}/_{43}$ + 9/49	17	236.00066	114.02	250	$1^{8}/_{41}$ + 12/49	9	249.99654	23.02
237	$1^{7}/_{39}$ + 7/41	8	236.99861	54.29	250[a]	$1^{9}/_{37}$ + 41/49	13	250.00265	30.01
237	$1^{26}/_{37}$ + 6/39	11	236.99888	67.37	250	$2^{2}/_{43}$ + 33/49	17	250.00174	45.61
237	12/47 + $1^{46}/_{49}$	13	236.99980	381.20	250	$3^{16}/_{47}$ + 48/49	27	249.99899	79.17
237[a]	$1^{12}/_{47}$ + 46/49	13	236.99980	381.20	…	…	…	…	…
238	7/37 + 28/43	5	237.99551	16.88	…	…	…	…	…
238	1/43 + $1^{23}/_{47}$	9	237.99804	38.60	…	…	…	…	…
238[a]	$2^{3}/_{31}$ + 14/33	15	237.99922	97.69	…	…	…	…	…
238	$2^{17}/_{39}$ + 4/47	15	238.00043	175.04	…	…	…	…	…

[a] Requires only the outer most circle of holes on indexing plate.

The greater spacing between successive machining operations may be used to advantage to spread out and reduce the effects of heat generation on the workpiece. The number of workpiece revolutions required by an approximation is shown in the table in the column to the right of the indexing movements. The table gives two or three choices for each division requiring approximate movements.

Two measures of the closeness of each approximation are provided to aid in the trade-off between complexity and precision. The first measure is the precise number of divisions that a set of indexing movements produces, offering a direct comparison of the degree of approximation. However, the difference between the precise number of divisions and the target number of divisions is angular in nature, so the error introduced by an approximation depends on the size of the circle being divided. The second measure of closeness reflects this characteristic by expressing the degree of approximation as the diameter at which the error is equal to 0.001. This second measure is unitless, so that taking the error as 0.001

Copyright 2004, Industrial Press, Inc., New York, NY

inch means that the entries in that column are to be taken as diameters in inches, but the measure works as well with 0.001 centimeter and diameters in centimeters. The measure can also be used to calculate the error of approximation at a given diameter. Divide the given diameter by the value of the measure and multiply the result by 0.001 to determine the amount of error that using an approximation will introduce.

Example: A gear is to be cut with 127 teeth at 16 diametral pitch using a Brown & Sharpe plain dividing head. The indexing table gives three approximations for 127 divisions. The pitch diameter of a 16 DP gear with 127 teeth is about 7.9 inches, so the calculated error of approximation for the three choices would be about $(7.9 \div 17.5) \times 0.001 = 0.00045$ inch, $(7.9 \div 77.5) \times 0.001 = 0.00010$ inch, and $(7.9 \div 218.98) \times 0.001 = 0.000036$ inch. Considering the increased potential for operator error with longer indexing movements and such other factors as may be appropriate, assume that the first of the three approximations is selected. Plate 3 is mounted on the worm shaft of the dividing head but not bolted to the frame. A double set of sector arms is installed, if available; otherwise, the single pair of sector arms is installed. The indexing pin on the crank arm is set to track the 39-hole circle. The stationary indexing pin is installed and set to track the 47-hole circle. If only one pair of sector arms is used, it is used for the 42⁄47 movement and is set for 0-42 holes using the outer arc. Six holes should be showing in the inner arc on the 47-hole circle (the zero-hole, the 42-hole, and four extra holes). The second set of sector arms is set for 0-2 holes on the 39-hole circle using the inner arc (three holes showing). If there is no second pair of sector arms, this is a short enough movement to do freehand without adding much risk of error.

Angular Indexing.— The plain dividing head with a 40:1 gear ratio will rotate the main spindle and the workpiece 9 degrees for each full turn of the indexing crank, and therefore 1 degree for movements of 2⁄18 or 3⁄27 on Brown & Sharpe dividing heads and 6⁄54 on heads of Cincinnati design. To find the indexing movement for an angle, divide that angle, in degrees, by 9 to get the number of full turns and the remainder, if any. If the remainder, expressed in minutes, is evenly divisible by 36, 33.75, 30, 27, or 20, then the quotient is the number of holes to be moved on the 15-, 16-, 18-, 20-, or 27-hole circles, respectively, to obtain the fractional turn required (or evenly divisible by 22.5, 21.6, 18, 16.875, 15, 11.25, or 10 for the number of holes to be moved on the 24-, 25-, 30-, 32-, 36-, 48-, or 54-hole circles, respectively, for the standard and high number plates of a Cincinnati dividing head). If none of these divisions is even, it is not possible to index the angle (exactly) by this method.

Example: An angle of 61° 48′ is required. Expressed in degrees, this angle is 61.8°, which when divided by 9 equals 6 with a remainder of 7.8°, or 468′. Division of 468 by 20, 27, 30, 33.75, and 36 reveals an even division by 36, yielding 13. The indexing movement for 61° 48′ is six full turns plus 13 holes on the 15-hole circle.

Tables for Angular Indexing.— Table 2, headed *Angular Values of One-Hole Moves*, provides the angular movement obtained with a move of one hole in each of the indexing circles available on standard Brown & Sharpe and Cincinnati plates, for a selection of angles that can be approximated with simple indexing.

Table 3, titled *Accurate Angular Indexing*, provides the simple and compound indexing movements to obtain the full range of fractional turns with the standard indexing plates of both the Brown & Sharpe and Cincinnati dividing heads. Compound indexing movements depend on the presence of specific indexing circles on the same indexing plate, so some movements may not be available with plates of different configurations. To use the table to index an angle, first convert the angle to seconds and then divide the number of seconds in the angle by 32,400 (the number of seconds in 9 degrees, which is one full turn of the indexing crank). The whole-number portion of the quotient gives the number of full turns of the indexing crank, and the decimal fraction of the quotient gives the fractional turn required.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Angular Values of One-Hole Moves for B&S and Cincinnati Index Plates

Holes in Circle	Angle in Minutes	Holes in Circle	Angle in Minutes	Holes in Circle	Angle in Minutes
15	36.000	53	10.189	129	4.186
16	33.750	54	10.000	131	4.122
17	31.765	57	9.474	133	4.060
18	30.000	58	9.310	137	3.942
19	28.421	59	9.153	139	3.885
20	27.000	62	8.710	141	3.830
21	25.714	66	8.182	143	3.776
23	23.478	67	8.060	147	3.673
24	22.500	69	7.826	149	3.624
25	21.600	71	7.606	151	3.576
26	20.769	73	7.397	153	3.529
27	20.000	77	7.013	157	3.439
28	19.286	79	6.835	159	3.396
29	18.621	81	6.667	161	3.354
30	18.000	83	6.506	163	3.313
31	17.419	87	6.207	167	3.234
32	16.875	89	6.067	169	3.195
33	16.364	91	5.934	171	3.158
34	15.882	93	5.806	173	3.121
36	15.000	97	5.567	175	3.086
37	14.595	99	5.455	177	3.051
38	14.211	101	5.347	179	3.017
39	13.846	103	5.243	181	2.983
41	13.171	107	5.047	183	2.951
42	12.857	109	4.954	187	2.888
43	12.558	111	4.865	189	2.857
44	12.273	113	4.779	191	2.827
46	11.739	117	4.615	193	2.798
47	11.489	119	4.538	197	2.741
48	11.250	121	4.463	199	2.714
49	11.020	123	4.390	…	…
51	10.588	127	4.252	…	…

Use Table 3 to locate the indexing movement for the decimal fraction nearest to the decimal fraction of the quotient for which there is an entry in the column for the dividing head to be used. If the decimal fraction of the quotient is close to the midpoint between two table entries, calculate the mathematical value of the two indexing movements to more decimal places to make the closeness determination.

Example: Movement through an angle of 31° 27′ 50″ is required. Expressed in seconds, this angle 113270″, which, divided by 32,400, equals 3.495987. The indexing movement is three full turns of the crank plus a fractional turn of 0.495987. The nearest Table 3 entry is for 0.4960, which requires a compound indexing movement of 8 holes on the 23-hole circle plus 4 holes on the 27-hole circle in the same direction. Checking the value of these movements shows that $^{8}/_{23} + {}^{4}/_{27} = 0.347826 + 0.148148 = 0.495974$, which, multiplied by 32,400, = 16,069.56, or 4° 27′ 49.56″ from the fractional turn. Adding the 27° from three full turns gives a total movement of 31° 27′ 49.56″.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.0010	12/49 – 10/41	15/51 – 17/58	0.0370	13/43 – 13/49	6/51 – 5/62
0.0020	24/49 – 20/41	23/51 – 22/49	0.0370	1/27	2/54
0.0030	8/23 – 10/29	7/39 – 6/34	0.0377	…	2/53
0.0040	1/41 – 1/49	4/66 – 3/53	0.0380	13/41 – 12/43	12/49 – 12/58
0.0050	4/39 – 4/41	3/24 – 3/25	0.0390	15/29 – 11/23	9/54 – 6/47
0.0060	9/29 – 7/23	18/51 – 17/49	0.0392	…	2/51
0.0070	11/31 – 8/23	5/46 – 6/59	0.0400	9/41 – 7/39	1/25
0.0080	2/41 – 2/49	10/49 – 10/51	0.0408	2/49	2/49
0.0090	1/23 – 1/29	8/24 – 12/37	0.0410	20/41 – 21/47	21/43 – 17/38
0.0100	8/39 – 8/41	6/24 – 6/25	0.0417	…	1/24
0.0110	6/39 – 7/49	11/59 – 10/57	0.0420	8/47 – 5/39	23/59 – 16/46
0.0120	9/47 – 7/39	15/49 – 15/51	0.0426	2/47	2/47
0.0130	2/33 – 1/21	3/54 – 2/47	0.0430	7/21 – 9/31	8/59 – 5/54
0.0140	19/47 – 16/41	10/46 – 12/59	0.0435	1/23	2/46
0.0150	8/29 – 6/23	9/24 – 9/25	0.0440	17/43 – 13/37	17/57 – 15/59
0.0152	…	1/66	0.0450	11/49 – 7/39	3/24 – 2/25
0.0160	18/49 – 13/37	20/49 – 20/51	0.0455	…	3/66
0.0161	…	1/62	0.0460	8/37 – 8/47	19/39 – 15/34
0.0169	…	1/59	0.0465	2/43	2/43
0.0170	15/41 – 15/43	9/49 – 11/66	0.0470	8/49 – 5/43	26/66 – 17/49
0.0172	…	1/58	0.0476	1/21	2/42
0.0175	…	1/57	0.0480	11/47 – 8/43	13/51 – 12/58
0.0180	9/39 – 10/47	11/42 – 10/41	0.0484	…	3/62
0.0185	…	1/54	0.0488	2/41	2/41
0.0189	…	1/53	0.0490	14/43 – 13/47	8/47 – 8/66
0.0190	7/37 – 8/47	6/49 – 6/58	0.0500	1/20	2/24 – 1/30
0.0196	…	1/51	0.0508	…	3/59
0.0200	16/39 – 16/41	3/30 – 2/25	0.0510	2/17 – 1/15	16/54 – 13/53
0.0204	1/49	1/49	0.0513	2/39	2/39
0.0210	3/43 – 2/41	15/46 – 18/59	0.0517	…	3/58
0.0213	1/47	1/47	0.0520	19/37 – 18/39	6/46 – 4/51
0.0217	…	1/46	0.0526	1/19	2/38
0.0220	12/37 – 13/43	22/59 – 20/57	0.0526	…	3/57
0.0230	4/37 – 4/47	3/47 – 2/49	0.0530	14/47 – 12/49	1/54 + 2/58
0.0233	1/43	1/43	0.0540	17/47 – 12/39	12/53 – 10/58
0.0238	…	1/42	0.0541	2/37	2/37
0.0240	18/47 – 14/39	23/58 – 19/51	0.0550	4/41 – 2/47	9/24 – 8/25
0.0244	1/41	1/41	0.0556	1/18	3/54
0.0250	2/16 – 2/20	2/30 – 1/24	0.0560	13/49 – 9/43	7/38 – 5/39
0.0256	1/39	1/39	0.0566	…	3/53
0.0260	4/33 – 2/21	3/46 – 2/51	0.0570	13/29 – 9/23	18/49 – 18/58
0.0263	…	1/38	0.0580	19/41 – 15/37	7/53 – 4/54
0.0270	3/23 – 3/29	6/53 – 5/58	0.0588	1/17	2/34
0.0270	1/37	1/37	0.0588	…	3/51
0.0280	17/43 – 18/49	20/46 – 24/59	0.0590	11/41 – 9/43	21/49 – 17/46
0.0290	11/37 – 11/41	4/49 – 3/57	0.0600	4/39 – 2/47	3/30 – 1/25
0.0294	…	1/34	0.0606	2/33	4/66
0.0300	2/39 – 1/47	7/25 – 6/24	0.0610	7/37 – 5/39	5/51 – 2/54
0.0303	1/33	2/66	0.0612	3/49	3/49
0.0310	13/39 – 13/43	13/34 – 13/37	0.0620	17/43 – 13/39	11/37 – 8/34
0.0320	11/37 – 13/49	8/37 – 7/38	0.0625	1/16	…
0.0323	1/31	2/62	0.0630	2/21 – 1/31	5/59 – 1/46
0.0330	11/49 – 9/47	11/49 – 9/47	0.0638	3/47	3/47
0.0333	…	1/30	0.0640	23/49 – 15/37	10/51 – 7/53
0.0339	…	2/59	0.0645	2/31	4/62
0.0340	18/49 – 13/39	18/49 – 17/51	0.0650	5/43 – 2/39	11/25 – 9/24
0.0345	1/29	2/58	0.0652	…	3/46
0.0350	13/41 – 11/39	4/25 – 3/24	0.0660	22/49 – 18/47	22/49 – 18/47
0.0351	…	2/57	0.0667	1/15	2/30
0.0357	…	1/28	0.0670	5/39 – 3/49	19/49 – 17/53
0.0360	18/39 – 20/47	21/41 – 20/42	0.0678	…	4/59

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.0680	9/39 – 7/43	23/51 – 18/47	0.0980	…	5/51
0.0690	2/29	4/58	0.0990	1/29 + 2/31	20/47 – 16/49
0.0690	12/37 – 12/47	7/66 – 2/54	0.1000	2/20	3/30
0.0698	3/43	3/43	0.1010	6/27 – 4/33	18/59 – 10/49
0.0700	8/33 – 5/29	8/25 – 6/24	0.1017	…	6/59
0.0702	…	4/57	0.1020	6/47 – 1/39	11/54 – 6/59
0.0710	17/43 – 12/37	11/58 – 7/59	0.1020	5/49	5/49
0.0714	…	2/28	0.1026	4/39	4/39
0.0714	…	3/42	0.1030	21/49 – 14/43	18/57 – 10/47
0.0720	7/47 – 3/39	10/49 – 7/53	0.1034	…	6/58
0.0730	9/37 – 8/47	1/47 + 3/58	0.1035	3/29	…
0.0732	3/41	3/41	0.1040	21/41 – 20/49	15/62 – 8/58
0.0740	23/49 – 17/43	19/42 – 14/37	0.1050	11/41 – 8/49	12/25 – 9/24
0.0741	2/27	4/54	0.1053	2/19	4/38
0.0750	2/16 – 1/20	1/24 + 1/30	0.1053	…	6/57
0.0755	…	4/53	0.1060	1/27 + 2/29	2/54 + 4/58
0.0758	…	5/66	0.1061	…	7/66
0.0760	17/47 – 14/49	24/49 – 24/58	0.1064	5/47	5/47
0.0769	3/39	3/39	0.1070	10/37 – 8/49	2/51 + 4/59
0.0770	…	9/46 – 7/59	0.1071	…	3/28
0.0771	6/37 – 4/47	…	0.1080	1/23 + 2/31	24/53 – 20/58
0.0780	13/39 – 12/47	9/46 – 6/51	0.1081	4/37	4/37
0.0784	…	4/51	0.1087	…	5/46
0.0789	…	3/38	0.1090	8/47 – 3/49	25/58 – 19/59
0.0790	20/37 – 18/39	21/39 – 17/37	0.1100	2/41 + 3/49	9/25 – 6/24
0.0800	9/37 – 8/49	2/25	0.1110	15/49 – 8/41	32/59 – 22/51
0.0806	…	5/62	0.1111	3/27	6/54
0.0810	9/23 – 9/29	17/47 – 16/57	0.1111	2/18	…
0.0811	3/37	3/37	0.1120	23/41 – 22/49	23/47 – 20/53
0.0816	4/49	4/49	0.1129	…	7/62
0.0820	5/47 – 1/41	4/38 – 1/43	0.1130	13/41 – 10/49	1/49 + 5/54
0.0830	4/23 – 3/33	8/46 – 6/66	0.1132	…	6/53
0.0833	…	2/24	0.1140	7/43 – 2/41	22/58 – 13/49
0.0840	8/43 – 5/49	8/47 – 5/58	0.1150	13/31 – 7/23	6/25 – 3/24
0.0847	…	5/59	0.1160	6/29 – 3/33	14/53 – 8/54
0.0850	9/17 – 8/18	3/24 – 1/25	0.1163	5/43	5/43
0.0851	4/47	4/47	0.1170	5/33 – 1/29	5/59 + 2/62
0.0860	13/31 – 7/21	16/59 – 10/54	0.1176	2/17	4/34
0.0862	…	5/58	0.1176	…	6/51
0.0870	2/23	4/46	0.1180	6/23 – 3/21	27/59 – 18/53
0.0870	5/33 – 2/31	21/54 – 16/53	0.1186	…	7/59
0.0877	…	5/57	0.1190	10/29 – 7/31	4/47 + 2/59
0.0880	8/37 – 5/39	28/57 – 25/62	0.1190	…	5/42
0.0882	…	3/34	0.1200	8/39 – 4/47	3/25
0.0890	6/37 – 3/41	22/53 – 15/46	0.1207	…	7/58
0.0900	22/49 – 14/39	6/24 – 4/25	0.1210	21/43 – 18/49	26/53 – 17/46
0.0909	3/33	6/66	0.1212	4/33	8/66
0.0910	23/49 – 14/37	21/51 – 17/53	0.1220	5/41	5/41
0.0920	4/31 – 1/27	4/34 – 1/39	0.1220	23/47 – 18/49	10/51 – 4/54
0.0926	…	5/54	0.1224	6/49	6/49
0.0930	15/29 – 14/33	5/34 – 2/37	0.1228	…	7/57
0.0930	4/43	4/43	0.1230	10/49 – 3/37	1/59 + 7/66
0.0940	23/47 – 17/43	15/49 – 14/66	0.1240	2/23 + 1/27	18/34 – 15/37
0.0943	…	5/53	0.1250	2/16	3/24
0.0950	5/43 – 1/47	9/24 – 7/25	0.1260	24/47 – 15/39	10/59 – 2/46
0.0952	2/21	4/42	0.1270	22/43 – 15/39	1/46 + 6/57
0.0960	11/39 – 8/43	11/39 – 8/43	0.1277	6/47	6/47
0.0968	3/31	6/62	0.1280	7/37 – 3/49	33/62 – 19/47
0.0970	22/43 – 17/41	12/59 – 5/47	0.1282	5/39	5/39
0.0976	4/41	4/41	0.1290	10/27 – 7/29	24/59 – 15/54
0.0980	7/27 – 5/31	16/47 – 16/66	0.1290	4/31	8/62

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.1296	…	7/54	0.1613	5/31	10/62
0.1300	10/43 – 4/39	6/24 – 3/25	0.1620	3/39 + 4/47	25/57 – 13/47
0.1304	3/23	6/46	0.1622	6/37	6/37
0.1310	3/43 + 3/49	8/49 – 2/62	0.1628	7/43	7/43
0.1316	…	5/38	0.1630	10/29 – 6/33	22/47 – 18/59
0.1320	11/47 – 5/49	11/47 – 5/49	0.1633	8/49	8/49
0.1321	…	7/53	0.1640	10/47 – 2/41	8/38 – 2/43
0.1330	8/29 – 3/21	2/37 + 3/38	0.1650	2/47 + 6/49	3/24 + 1/25
0.1333	2/15	4/30	0.1660	8/23 – 6/33	16/46 – 12/66
0.1340	7/17 – 5/18	19/53 – 11/49	0.1667	3/18	4/24
0.1350	10/43 – 4/41	9/24 – 6/25	0.1667	…	5/30
0.1351	5/37	5/37	0.1667	…	7/42
0.1356	…	8/59	0.1667	…	9/54
0.1360	5/16 – 3/17	11/47 – 5/51	0.1667	…	11/66
0.1364	…	9/66	0.1670	16/39 – 9/37	19/53 – 9/47
0.1370	3/41 + 3/47	10/47 – 5/66	0.1680	16/43 – 10/49	26/57 – 17/59
0.1373	…	7/51	0.1690	5/39 + 2/49	10/46 – 3/62
0.1379	4/29	8/58	0.1695	…	10/59
0.1380	23/47 – 13/37	18/39 – 11/34	0.1698	…	9/53
0.1390	28/49 – 16/37	16/38 – 11/39	0.1700	6/23 – 3/33	6/24 – 2/25
0.1395	6/43	6/43	0.1702	8/47	8/47
0.1400	8/49 – 1/43	1/25 + 3/30	0.1707	7/41	7/41
0.1404	…	8/57	0.1710	15/49 – 5/37	15/47 – 8/54
0.1410	11/47 – 4/43	12/66 – 2/49	0.1720	1/39 + 6/41	32/59 – 20/54
0.1420	8/49 – 1/47	21/57 – 12/53	0.1724	5/29	10/58
0.1429	…	4/28	0.1730	9/41 – 2/31	9/41 – 2/43
0.1429	3/21	6/42	0.1739	4/23	8/46
0.1429	7/49	7/49	0.1740	10/33 – 4/31	21/53 – 12/54
0.1430	10/47 – 3/43	24/51 – 19/58	0.1750	2/16 + 1/20	1/24 + 4/30
0.1440	19/43 – 14/47	20/49 – 14/53	0.1754	…	10/57
0.1450	9/47 – 2/43	15/24 – 12/25	0.1760	2/37 + 5/41	2/37 + 5/41
0.1452	…	9/62	0.1765	3/17	6/34
0.1460	26/49 – 15/39	2/47 + 6/58	0.1765	…	9/51
0.1463	6/41	6/41	0.1770	5/39 + 2/41	14/49 – 5/46
0.1470	4/21 – 1/23	16/41 – 9/37	0.1774	…	11/62
0.1471	…	5/34	0.1780	23/41 – 18/47	6/49 + 3/54
0.1480	4/19 – 1/16	9/37 – 4/42	0.1786	…	5/28
0.1481	4/27	8/54	0.1790	11/21 – 10/29	19/51 – 12/62
0.1489	7/47	7/47	0.1795	7/39	7/39
0.1490	12/31 – 5/21	11/49 – 4/53	0.1800	11/47 – 2/37	2/25 + 3/30
0.1500	3/20	7/30 – 2/24	0.1810	11/37 – 5/43	18/38 – 12/41
0.1509	…	8/53	0.1818	6/33	12/66
0.1510	22/47 – 13/41	25/59 – 18/66	0.1820	9/39 – 2/41	21/46 – 14/51
0.1515	5/33	10/66	0.1830	5/17 – 2/18	33/58 – 22/57
0.1520	11/41 – 5/43	16/62	0.1837	9/49	9/49
0.1522	…	7/46	0.1840	8/31 – 2/27	19/62 – 6/49
0.1525	…	9/59	0.1842	…	7/38
0.1530	10/27 – 5/23	13/54 – 5/57	0.1850	4/37 + 3/39	14/25 – 9/24
0.1538	6/39	6/39	0.1852	5/27	10/54
0.1540	10/37 – 5/43	5/58 + 4/59	0.1860	1/29 + 5/33	18/47 – 13/66
0.1550	8/37 – 3/49	7/25 – 3/24	0.1860	8/43	8/43
0.1552	…	9/58	0.1864	…	11/59
0.1560	4/21 – 1/29	1/49 + 8/59	0.1870	16/49 – 6/43	24/57 – 11/47
0.1569	…	8/51	0.1875	3/16	…
0.1570	15/47 – 6/37	31/59 – 21/57	0.1880	12/29 – 7/31	30/49 – 28/66
0.1579	3/19	6/38	0.1887	…	10/53
0.1579	…	9/57	0.1890	13/29 – 7/27	23/58 – 11/53
0.1580	3/37 + 3/39	3/34 + 3/43	0.1892	7/37	7/37
0.1590	20/43 – 15/49	3/54 + 6/58	0.1897	…	11/58
0.1600	18/37 – 16/49	4/25	0.1900	10/43 – 2/47	11/25 – 6/24
0.1610	9/39 – 3/43	9/39 – 3/43	0.1905	4/21	8/42

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.1910	17/39 – 12/49	21/57 – 11/62	0.2222	4/18	…
0.1915	9/47	9/47	0.2222	6/27	12/54
0.1920	7/41 + 1/47	12/57 – 1/54	0.2230	15/31 – 6/23	11/46 – 1/62
0.1930	…	11/57	0.2240	5/41 + 5/49	15/38 – 7/41
0.1930	10/19 – 5/15	19/59 – 8/62	0.2241	…	13/58
0.1935	6/31	12/62	0.2245	11/49	11/49
0.1940	7/41 + 1/43	14/43 – 5/38	0.2250	2/16 + 2/20	3/24 + 3/30
0.1950	1/23 + 5/33	8/25 – 3/24	0.2258	7/31	14/62
0.1951	8/41	8/41	0.2260	7/39 + 2/43	2/49 + 10/54
0.1957	…	9/46	0.2264	…	12/53
0.1960	21/49 – 10/43	34/66 – 15/47	0.2270	7/27 – 1/31	14/54 – 2/62
0.1961	…	10/51	0.2273	…	15/66
0.1970	…	13/66	0.2280	11/39 – 2/37	23/49 – 14/58
0.1970	21/39 – 14/41	11/47 – 2/54	0.2281	…	13/57
0.1980	2/29 + 4/31	17/49 – 7/47	0.2290	18/39 – 10/43	29/51 – 18/53
0.1990	5/37 + 3/47	27/59 – 15/58	0.2300	7/37 + 2/49	12/25 – 6/24
0.2000	3/15	5/25	0.2308	9/39	9/39
0.2000	4/20	6/30	0.2310	28/49 – 16/47	26/59 – 13/62
0.2010	11/39 – 3/37	8/49 + 2/53	0.2320	20/41 – 11/43	26/57 – 13/58
0.2020	23/41 – 14/39	23/41 – 14/39	0.2326	10/43	10/43
0.2030	2/37 + 7/47	19/62 – 6/58	0.2330	27/47 – 14/41	25/62 – 8/47
0.2034	…	12/59	0.2333	…	7/30
0.2037	…	11/54	0.2340	24/41 – 13/37	2/54 + 13/66
0.2040	12/47 – 2/39	18/51 – 7/47	0.2340	11/47	11/47
0.2041	10/49	10/49	0.2350	11/27 – 5/29	9/25 – 3/24
0.2050	13/37 – 6/41	3/24 + 2/25	0.2353	4/17	8/34
0.2051	8/39	8/39	0.2353	…	12/51
0.2059	…	7/34	0.2360	10/39 – 1/49	29/66 – 12/59
0.2060	15/43 – 7/49	12/53 – 1/49	0.2368	…	9/38
0.2069	6/29	12/58	0.2370	23/37 – 15/39	23/37 – 15/39
0.2070	19/41 – 10/39	19/41 – 10/39	0.2373	…	14/59
0.2075	…	11/53	0.2380	2/43 + 9/47	34/57 – 19/53
0.2080	15/31 – 8/29	13/58 – 1/62	0.2381	5/21	10/42
0.2083	…	5/24	0.2390	24/43 – 15/47	12/62 + 3/66
0.2090	16/33 – 8/29	8/46 + 2/57	0.2391	…	11/46
0.2093	9/43	9/43	0.2400	3/43 + 8/47	6/25
0.2097	…	13/62	0.2407	…	13/54
0.2100	22/37 – 15/39	6/24 – 1/25	0.2410	19/47 – 8/49	17/47 – 7/58
0.2105	4/19	8/38	0.2414	7/29	14/58
0.2105	…	12/57	0.2419	…	15/62
0.2110	22/41 – 14/43	22/41 – 14/43	0.2420	21/37 – 14/43	12/46 – 1/53
0.2120	2/27 – 4/29	4/54 + 8/58	0.2424	8/33	16/66
0.2121	7/33	14/66	0.2430	29/49 – 15/43	4/47 + 9/57
0.2128	10/47	10/47	0.2432	9/37	9/37
0.2130	23/49 – 10/39	2/30 + 6/41	0.2439	10/41	10/41
0.2140	20/37 – 16/49	12/51 – 1/47	0.2440	13/49 – 1/47	30/53 – 19/59
0.2143	…	6/28	0.2449	12/49	12/49
0.2143	…	9/42	0.2450	13/37 – 5/47	3/24 + 3/25
0.2150	11/43 – 2/49	9/24 – 4/25	0.2453	…	13/53
0.2157	…	11/51	0.2456	…	14/57
0.2160	2/23 + 4/31	25/51 – 17/62	0.2460	20/49 – 6/37	11/37 – 2/39
0.2162	8/37	8/37	0.2470	10/37 – 1/43	29/49 – 20/58
0.2170	11/41 – 2/39	28/59 – 17/66	0.2480	4/23 + 2/27	26/49 – 13/46
0.2174	5/23	10/46	0.2490	10/37 – 1/47	17/43 – 6/41
0.2180	3/31 + 4/33	21/59 – 8/58	0.2500	4/16	6/24
0.2190	11/23 – 7/27	3/47 + 9/58	0.2500	5/20	7/28
0.2195	9/41	9/41	0.2510	2/15 + 2/17	34/66 – 14/53
0.2200	4/41 + 6/49	3/25 + 3/30	0.2520	24/43 – 15/49	22/49 – 13/66
0.2203	…	13/59	0.2530	7/37 + 3/47	11/53 + 3/66
0.2210	18/49 – 6/41	21/47 – 14/62	0.2540	26/49 – 13/47	2/46 + 12/57
0.2220	25/41 – 19/49	7/51 + 5/59	0.2542	…	15/59

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.2549	…	13/51	0.2857	…	12/42
0.2550	4/21 + 2/31	9/24 – 3/25	0.2857	…	8/28
0.2553	12/47	12/47	0.2860	20/47 – 6/43	20/58 – 3/51
0.2558	11/43	11/43	0.2870	7/41 + 5/43	20/42 – 7/37
0.2560	13/33 – 4/29	9/47 + 4/62	0.2879	…	19/66
0.2564	10/39	10/39	0.2880	19/43 – 6/39	19/43 – 6/39
0.2570	20/39 – 11/43	8/53 + 7/66	0.2881	…	17/59
0.2576	…	17/66	0.2890	1/21 + 7/29	16/46 – 3/51
0.2580	15/29 – 7/27	24/54 – 11/59	0.2895	…	11/38
0.2581	8/31	16/62	0.2900	23/43 – 12/49	6/24 + 1/25
0.2586	…	15/58	0.2903	9/31	18/62
0.2590	24/49 – 9/39	16/42 – 5/41	0.2910	5/39 + 7/43	7/49 + 8/54
0.2593	7/27	14/54	0.2917	…	7/24
0.2600	20/43 – 8/39	4/25 + 3/30	0.2920	9/39 + 3/49	35/57 – 19/59
0.2609	6/23	12/46	0.2927	12/41	12/41
0.2610	15/33 – 6/31	5/53 + 9/54	0.2930	17/39 – 7/49	28/53 – 12/51
0.2619	…	11/42	0.2931	…	17/58
0.2620	18/37 – 11/49	16/51 – 3/58	0.2940	8/21 – 2/23	14/57 + 3/62
0.2630	13/41 – 2/37	13/46 – 1/51	0.2941	5/17	10/34
0.2632	5/19	10/38	0.2941	…	15/51
0.2632	…	15/57	0.2950	18/37 – 9/47	9/24 – 2/25
0.2640	22/47 – 10/49	22/47 – 10/49	0.2960	21/41 – 8/37	29/57 – 10/47
0.2642	…	14/53	0.2963	8/27	16/54
0.2647	…	9/34	0.2970	3/29 + 6/31	13/47 + 1/49
0.2650	8/37 + 2/41	15/24 – 9/25	0.2973	11/37	11/37
0.2653	13/49	13/49	0.2979	14/47	14/47
0.2660	8/27 – 1/33	28/51 – 15/53	0.2980	11/21 – 7/31	12/37 – 1/38
0.2667	…	8/30	0.2982	…	17/57
0.2670	18/37 – 9/41	19/47 – 7/51	0.2990	19/43 – 7/49	19/43 – 4/28
0.2680	8/18 – 3/17	27/49 – 15/53	0.3000	6/20	9/30
0.2683	11/41	11/41	0.3010	1/41 + 13/47	19/54 – 3/59
0.2690	2/18 + 3/19	6/54 + 9/57	0.3019	…	16/53
0.2700	16/27 – 10/31	13/25 – 6/24	0.3020	7/29 + 2/33	23/62 – 4/58
0.2703	10/37	10/37	0.3023	13/43	13/43
0.2710	2/43 + 11/49	1/28 + 8/34	0.3030	15/39 – 4/49	25/57 – 8/59
0.2712	…	16/59	0.3030	10/33	20/66
0.2720	14/37 – 5/47	17/59 – 1/62	0.3040	16/31 – 7/33	33/59 – 12/47
0.2727	9/33	18/66	0.3043	7/23	14/46
0.2730	1/16 + 4/19	18/34 – 10/39	0.3050	1/31 + 9/33	15/24 – 8/25
0.2740	6/41 + 6/47	26/59 – 9/54	0.3051	…	18/59
0.2742	…	17/62	0.3060	17/31 – 8/33	33/54 – 18/59
0.2745	…	14/51	0.3061	15/49	15/49
0.2750	2/16 + 3/20	5/24 + 2/30	0.3065	…	19/62
0.2759	8/29	16/58	0.3070	18/37 – 7/39	1/53 + 17/59
0.2760	12/31 – 3/27	13/43 – 1/38	0.3077	12/39	12/39
0.2766	13/47	13/47	0.3080	5/41 + 8/43	16/49 – 1/54
0.2770	11/27 – 3/23	18/28 – 15/41	0.3090	1/43 + 14/49	19/30 – 12/37
0.2778	5/18	15/54	0.3095	…	13/42
0.2780	5/23 + 2/33	17/39 – 6/38	0.3100	16/37 – 6/49	14/25 – 6/24
0.2790	16/29 – 9/33	14/47 – 1/53	0.3103	9/29	18/58
0.2791	12/43	12/43	0.3110	3/39 + 11/47	19/46 – 5/49
0.2800	16/49 – 2/43	7/25	0.3120	8/21 – 2/29	2/49 + 16/59
0.2807	…	16/57	0.3125	5/16	…
0.2810	3/39 + 10/49	17/57 – 1/58	0.3130	9/37 + 3/43	4/24 + 6/41
0.2820	5/27 + 3/31	24/66 – 4/49	0.3137	…	16/51
0.2821	11/39	11/39	0.3140	12/27 – 3/23	14/47 + 1/62
0.2826	…	13/46	0.3148	…	17/54
0.2830	14/43 – 2/47	15/53	0.3150	26/41 – 15/47	21/24 – 14/25
0.2840	21/47 – 7/43	37/66 – 13/47	0.3158	…	12/38
0.2850	15/43 – 3/47	3/24 + 4/25	0.3158	…	18/57
0.2857	14/49	14/49	0.3160	6/37 + 6/39	6/34 + 6/43

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.3170	11/18 – 5/17	34/59 – 14/54	0.3485	…	23/66
0.3171	13/41	13/41	0.3488	15/43	15/43
0.3180	22/37 – 13/47	6/54 + 12/58	0.3490	11/29 – 1/33	2/47 + 19/62
0.3182	…	21/66	0.3500	7/20	6/24 + 3/30
0.3190	6/27 + 3/31	3/34 + 9/39	0.3509	…	20/57
0.3191	15/47	15/47	0.3510	13/27 – 3/23	25/53 – 7/58
0.3200	16/47 – 1/49	8/25	0.3514	13/37	13/37
0.3208	…	17/53	0.3519	…	19/54
0.3210	25/49 – 7/37	10/59 + 10/66	0.3520	4/37 + 10/41	24/62 – 2/57
0.3214	…	9/28	0.3529	6/17	12/34
0.3220	18/39 – 6/43	18/39 – 6/43	0.3529	…	18/51
0.3220	…	19/59	0.3530	4/37 + 12/49	31/59 – 10/58
0.3226	10/31	20/62	0.3540	14/37 – 1/41	22/59 – 1/53
0.3230	21/41 – 7/37	21/41 – 7/37	0.3548	11/31	22/62
0.3235	…	11/34	0.3550	10/43 + 6/49	12/25 – 3/24
0.3240	3/23 + 6/31	21/47 – 7/57	0.3559	…	21/59
0.3243	12/37	12/37	0.3560	5/41 + 11/47	12/49 + 6/54
0.3250	2/16 + 4/20	3/24 + 5/25	0.3570	20/43 – 4/37	20/43 – 4/37
0.3256	14/43	14/43	0.3571	…	10/28
0.3260	21/49 – 4/39	23/59 – 3/47	0.3571	…	15/42
0.3261	…	15/46	0.3580	14/37 – 1/49	38/62 – 13/51
0.3265	16/49	16/49	0.3585	…	19/53
0.3270	24/49 – 7/43	17/58 + 2/59	0.3590	14/39	14/39
0.3276	…	19/58	0.3600	22/47 – 4/37	9/25
0.3280	26/41 – 15/49	15/51 + 2/59	0.3610	9/23 – 1/33	18/46 – 2/66
0.3290	5/21 + 3/33	23/43 – 7/34	0.3617	17/47	17/47
0.3300	4/47 + 12/49	6/24 + 2/25	0.3620	15/27 – 6/31	17/41 – 2/38
0.3310	17/31 – 5/23	23/59 – 3/51	0.3621	…	21/58
0.3320	28/43 – 15/47	30/59 – 9/51	0.3630	23/49 – 5/47	25/53 – 5/46
0.3330	7/43 + 8/47	36/51 – 22/59	0.3636	12/33	24/66
0.3333	5/15	8/24	0.3640	26/47 – 7/37	25/62 – 2/51
0.3333	6/18	10/30	0.3650	28/47 – 9/39	3/24 + 6/25
0.3333	7/21	13/39	0.3659	…	15/41
0.3333	9/27	14/42	0.3660	10/17 – 4/18	13/57 + 8/58
0.3333	11/33	17/51	0.3667	…	11/30
0.3333	13/39	18/54	0.3670	5/27 + 6/33	13/49 + 6/59
0.3333	…	19/57	0.3673	18/49	18/49
0.3333	…	22/66	0.3680	16/31 – 4/27	31/66 – 6/59
0.3340	7/41 + 8/49	29/47 – 15/53	0.3684	7/19	14/38
0.3350	21/37 – 10/43	9/24 – 1/25	0.3684	…	21/57
0.3360	28/41 – 17/49	9/46 + 8/57	0.3690	30/49 – 9/37	21/62 + 2/66
0.3370	2/39 + 14/49	33/57 – 15/62	0.3696	…	17/46
0.3380	10/23 – 3/31	25/62 – 3/46	0.3700	30/47 – 11/41	6/24 + 3/25
0.3387	…	21/62	0.3704	10/27	20/54
0.3390	19/49 – 2/41	20/59	0.3710	32/49 – 11/39	23/62
0.3396	…	18/53	0.3720	2/29 + 10/33	34/57 – 11/49
0.3400	25/49 – 8/47	6/25 + 3/30	0.3721	16/43	16/43
0.3404	16/47	16/47	0.3725	…	19/51
0.3410	12/27 – 3/29	22/46 – 7/51	0.3729	…	22/59
0.3415	14/41	14/41	0.3730	30/47 – 13/49	21/49 – 3/54
0.3420	4/21 + 5/33	25/62 – 3/49	0.3740	32/49 – 12/43	5/46 + 13/49
0.3421	…	13/38	0.3750	6/16	9/24
0.3430	13/23 – 6/27	37/57 – 15/49	0.3760	5/21 + 4/29	11/49 + 10/66
0.3440	2/39 + 12/41	14/54 + 5/59	0.3770	13/37 + 1/39	20/51 – 1/66
0.3448	…	20/58	0.3774	…	20/53
0.3450	2/23 + 8/31	15/24 – 7/25	0.3780	13/27 – 3/29	31/53 – 12/58
0.3460	18/41 – 4/43	18/41 – 4/43	0.3784	14/37	14/37
0.3469	17/49	17/49	0.3788	…	25/66
0.3470	7/31 + 4/33	7/38 + 7/43	0.3790	8/37 + 7/43	8/37 + 7/43
0.3478	8/23	16/46	0.3793	11/29	22/58
0.3480	20/33 – 8/31	31/59 – 11/62	0.3800	20/43 – 4/47	7/25 + 3/30

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.3810	8/21	16/42	0.4120	18/41 − 1/37	24/53 − 2/49
0.3810	19/47 − 1/43	8/51 + 13/58	0.4130	2/39 + 17/47	19/46
0.3820	25/49 − 5/39	40/62 − 15/57	0.4138	12/29	24/58
0.3824	…	13/34	0.4140	19/39 − 3/41	19/39 − 3/41
0.3830	18/47	18/47	0.4146	17/41	17/41
0.3830	27/43 − 12/49	37/58 − 13/51	0.4150	18/33 − 3/23	9/24 + 1/25
0.3840	27/43 − 10/41	27/43 − 10/41	0.4151	…	22/53
0.3846	15/39	15/39	0.4160	21/39 − 6/49	41/62 − 13/53
0.3850	15/37 − 1/49	15/24 − 6/25	0.4167	…	10/24
0.3860	1/37 + 14/39	22/57	0.4170	26/37 − 14/49	10/38 + 6/39
0.3870	3/17 + 4/19	16/39 − 1/43	0.4180	8/21 + 1/27	16/46 + 4/57
0.3871	12/31	24/62	0.4186	18/43	18/43
0.3878	19/49	19/49	0.4190	18/39 − 2/47	31/46 − 13/51
0.3880	14/41 + 2/43	18/53 + 3/62	0.4194	13/31	26/62
0.3889	7/18	21/54	0.4200	24/49 − 3/43	8/25 + 3/30
0.3890	17/41 − 1/39	24/53 − 3/47	0.4210	1/39 + 17/43	23/49 − 3/62
0.3898	…	23/59	0.4211	8/19	16/38
0.3900	2/23 + 10/33	16/25 − 6/24	0.4211	…	24/57
0.3902	16/41	16/41	0.4220	15/29 − 2/21	3/41 + 15/43
0.3910	14/31 − 2/33	29/66 − 3/62	0.4230	24/43 − 5/37	20/54 + 3/57
0.3913	9/23	18/46	0.4237	…	25/59
0.3920	14/33 − 1/31	17/47 + 2/66	0.4240	4/27 + 8/29	41/62 − 14/59
0.3922	…	20/51	0.4242	14/33	28/66
0.3929	…	11/28	0.4250	6/16 + 1/20	7/24 + 4/30
0.3930	1/39 + 18/49	28/46 − 11/51	0.4255	20/47	20/47
0.3939	13/33	26/66	0.4259	…	23/54
0.3940	3/39 + 13/41	24/53 − 3/51	0.4260	27/41 − 10/43	28/57 − 3/46
0.3947	…	15/38	0.4270	27/39 − 13/49	29/59 − 4/62
0.3950	26/37 − 12/39	13/25 − 3/24	0.4280	12/43 + 7/47	33/57 − 8/53
0.3953	17/43	17/43	0.4286	9/21	12/28
0.3960	4/29 + 8/31	33/47 − 15/49	0.4286	21/49	18/42
0.3962	…	21/53	0.4286	…	21/49
0.3966	…	23/58	0.4290	30/47 − 9/43	21/51 + 1/58
0.3970	25/41 − 10/47	7/57 + 17/62	0.4300	22/43 − 4/49	17/25 − 6/24
0.3980	3/16 + 4/19	28/58 − 5/59	0.4310	11/39 + 7/47	25/58
0.3990	7/39 + 9/41	6/37 + 9/38	0.4314	…	22/51
0.4000	6/15	10/25	0.4320	4/23 + 8/31	28/62 − 1/51
0.4000	8/20	12/30	0.4324	16/37	16/37
0.4010	2/37 + 17/49	27/62 − 2/58	0.4330	5/37 + 14/47	26/42 − 8/43
0.4020	5/43 + 14/49	16/49 + 4/53	0.4333	…	13/30
0.4030	26/49 − 6/47	30/47 − 12/51	0.4340	5/31 + 9/33	23/53
0.4032	…	25/62	0.4348	10/23	20/46
0.4035	…	23/57	0.4350	21/31 − 8/33	14/25 − 3/24
0.4040	11/39 + 5/41	11/39 + 5/41	0.4355	…	27/62
0.4043	19/47	19/47	0.4359	…	17/39
0.4048	…	17/42	0.4360	6/31 + 8/33	42/59 − 16/58
0.4050	29/41 − 13/43	3/24 + 7/25	0.4370	27/39 − 12/47	31/49 − 9/46
0.4054	15/37	15/37	0.4375	7/16	…
0.4060	21/47 − 2/49	17/58 + 7/62	0.4380	13/27 − 1/23	24/57 + 1/59
0.4068	…	24/59	0.4386	…	25/57
0.4070	9/19 − 1/15	7/47 + 16/62	0.4390	18/43 + 1/49	34/59 − 7/51
0.4074	11/27	22/54	0.4390	18/41	18/41
0.4080	16/37 − 1/41	2/54 + 23/62	0.4394	…	29/66
0.4082	20/49	20/49	0.4400	8/41 + 12/49	11/25
0.4090	15/39 + 1/41	15/39 + 1/41	0.4407	…	26/59
0.4091	…	27/66	0.4410	10/37 + 7/41	10/37 + 7/41
0.4100	1/37 + 18/47	6/24 + 4/25	0.4412	…	15/34
0.4103	16/39	16/39	0.4419	19/43	19/43
0.4110	9/41 + 9/47	7/34 + 8/39	0.4420	18/33 − 3/29	34/62 − 5/47
0.4118	7/17	14/34	0.4430	4/39 + 16/47	20/51 + 3/59
0.4118	…	21/51	0.4440	9/41 + 11/49	14/51 + 10/59

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.4444	12/27	24/54	0.4737	…	27/57
0.4444	8/18	…	0.4740	9/37 + 9/39	9/34 + 9/43
0.4450	7/37 + 11/43	3/24 + 8/25	0.4746	…	28/59
0.4460	11/23 − 1/31	22/46 − 2/62	0.4750	6/16 + 2/20	9/24 + 3/30
0.4468	21/47	21/47	0.4760	4/43 + 18/47	15/53 + 11/57
0.4470	6/21 + 5/31	14/49 + 10/62	0.4762	10/21	20/42
0.4474	…	17/38	0.4770	26/43 − 6/47	30/47 − 10/62
0.4480	10/41 + 10/49	27/41 − 8/38	0.4780	12/31 + 3/33	24/62 + 6/66
0.4483	13/29	26/58	0.4783	11/23	22/46
0.4490	22/49	22/49	0.4790	22/39 − 4/47	10/53 + 18/62
0.4490	20/39 − 3/47	14/57 + 12/59	0.4800	16/39 + 3/43	12/25
0.4500	9/20	6/24 + 6/30	0.4810	14/41 + 6/43	22/58 + 6/59
0.4510	…	23/51	0.4815	13/27	26/54
0.4510	5/15 + 2/17	42/62 − 12/53	0.4820	33/49 − 9/47	19/46 + 4/58
0.4516	14/31	28/62	0.4828	14/29	28/58
0.4520	14/39 + 4/43	4/49 + 20/54	0.4830	27/39 − 9/43	27/39 − 9/43
0.4524	…	19/42	0.4839	15/31	30/62
0.4528	…	24/53	0.4840	5/37 + 15/43	24/46 − 2/53
0.4530	3/23 + 10/31	16/59 + 12/66	0.4848	16/33	32/66
0.4540	14/27 − 2/31	1/54 + 27/62	0.4850	24/47 − 1/39	3/24 + 9/25
0.4545	15/33	30/66	0.4860	13/43 + 9/49	43/62 − 11/53
0.4550	25/47 − 3/39	9/24 + 2/25	0.4865	18/37	18/37
0.4560	9/37 + 10/47	17/62 + 12/66	0.4870	15/37 + 4/49	26/43 − 4/34
0.4561	…	26/57	0.4872	19/39	19/39
0.4565	…	21/46	0.4878	20/41	20/41
0.4570	4/37 + 15/43	27/39 − 8/34	0.4880	8/29 + 7/33	5/46 + 22/58
0.4576	…	27/59	0.4884	21/43	21/43
0.4580	27/49 − 4/43	20/53 + 5/62	0.4890	28/43 − 6/37	19/47 + 5/59
0.4583	…	11/24	0.4894	23/47	23/47
0.4590	35/49 − 12/47	18/51 + 7/66	0.4898	24/49	24/49
0.4595	17/37	17/37	0.4900	13/21 − 4/31	6/24 + 6/25
0.4600	16/41 + 3/43	9/25 + 3/30	0.4902	…	25/51
0.4610	13/39 + 6/47	22/34 − 8/43	0.4906	…	26/53
0.4615	18/39	18/39	0.4910	15/39 + 5/47	21/46 + 2/58
0.4620	15/47 + 7/49	36/62 − 7/59	0.4912	…	28/57
0.4630	…	25/54	0.4915	…	29/59
0.4630	…	10/46 + 14/57	0.4920	25/37 − 9/49	17/46 + 6/49
0.4631	9/21 + 1/29	…	0.4930	8/41 + 14/47	21/53 + 6/62
0.4634	19/41	19/41	0.4940	33/49 − 7/39	14/46 + 11/58
0.4640	21/43 − 1/41	32/58 − 5/57	0.4950	5/29 + 10/31	9/24 + 3/25
0.4643	…	13/28	0.4960	8/23 + 4/27	20/53 + 7/59
0.4650	21/37 − 4/39	15/24 − 4/25	0.4970	33/47 − 8/39	7/46 + 20/58
0.4651	20/43	20/43	0.4980	20/37 − 2/47	29/41 − 9/43
0.4655	…	27/58	0.4990	26/41 − 5/37	26/41 − 5/37
0.4660	13/41 + 7/47	31/47 − 12/62	0.5000	8/16	12/24
0.4667	7/15	14/30	0.5000	9/18	14/28
0.4670	19/37 − 2/43	25/34 − 11/41	0.5000	10/20	15/30
0.4677	…	29/62	0.5000	…	17/34
0.4680	11/27 + 2/33	3/49 + 24/59	0.5000	…	19/38
0.4681	22/47	22/47	0.5000	…	21/42
0.4690	8/23 + 4/33	35/49 − 13/53	0.5000	…	23/46
0.4694	23/49	23/49	0.5000	…	27/54
0.4697	…	31/66	0.5000	…	29/58
0.4700	19/29 − 5/27	18/25 − 6/24	0.5000	…	31/62
0.4706	8/17	16/34	0.5000	…	33/66
0.4706	…	24/51	0.5010	5/37 + 15/41	37/51 − 11/49
0.4710	12/39 + 8/49	12/47 + 11/51	0.5020	17/37 + 2/47	25/53 + 2/66
0.4717	…	25/53	0.5030	8/39 + 14/47	16/49 + 9/51
0.4720	20/39 − 2/49	31/53 − 7/62	0.5040	5/43 + 19/49	37/66 − 3/53
0.4730	6/39 + 15/47	29/59 − 1/54	0.5050	21/31 − 5/29	15/24 − 3/25
0.4737	9/19	18/38	0.5060	7/39 + 16/49	22/53 + 6/66

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.5070	33/47 − 8/41	28/46 − 6/59	0.5370	…	29/54
0.5080	12/37 + 9/49	41/66 − 6/53	0.5370	…	6/51 + 26/62
0.5085	…	30/59	0.5371	17/41 + 6/49	…
0.5088	…	29/57	0.5380	4/18 + 6/19	12/49 + 17/58
0.5090	24/39 − 5/47	27/51 − 1/49	0.5385	21/39	21/39
0.5094	…	27/53	0.5390	26/39 − 6/47	34/51 − 6/47
0.5098	…	26/51	0.5400	25/41 − 3/43	6/25 + 9/30
0.5100	8/21 + 4/31	18/24 − 6/25	0.5405	20/37	20/37
0.5102	25/49	25/49	0.5410	12/47 + 14/49	2/38 + 21/43
0.5106	24/47	24/47	0.5417	…	13/24
0.5110	6/37 + 15/43	26/49 − 1/51	0.5420	4/43 + 22/49	7/46 + 23/59
0.5116	22/43	22/43	0.5424	…	32/59
0.5120	21/29 − 7/33	45/66 − 9/53	0.5430	33/43 − 11/49	22/54 + 8/59
0.5122	21/41	21/41	0.5435	…	25/46
0.5128	20/39	20/39	0.5439	…	31/57
0.5130	22/37 − 4/49	30/54 − 2/47	0.5440	4/37 + 17/39	4/37 + 17/39
0.5135	19/37	19/37	0.5450	3/39 + 22/47	15/24 − 2/25
0.5140	30/43 − 9/49	33/46 − 12/59	0.5455	18/33	36/66
0.5150	1/39 + 23/47	16/25 − 3/24	0.5460	13/27 + 2/31	2/34 + 19/39
0.5152	17/33	34/66	0.5470	21/31 − 3/23	32/49 − 7/66
0.5160	28/43 − 5/37	37/59 − 6/54	0.5472	…	29/53
0.5161	16/31	32/62	0.5476	…	23/42
0.5170	13/39 + 9/49	9/49 + 17/51	0.5480	12/41 + 12/47	25/39 − 4/43
0.5172	15/29	30/58	0.5484	17/31	34/62
0.5180	9/47 + 16/49	31/41 − 10/42	0.5490	10/15 − 2/17	8/47 + 25/66
0.5185	14/27	28/54	0.5490	…	28/51
0.5190	27/41 − 6/43	6/49 + 23/58	0.5500	11/20	6/24 + 9/30
0.5200	3/41 + 21/47	13/25	0.5510	19/39 + 3/47	31/53 − 2/59
0.5210	17/39 + 4/47	41/59 − 8/46	0.5510	…	27/49
0.5217	12/23	24/46	0.5517	16/29	32/58
0.5220	19/31 − 3/33	14/47 + 13/58	0.5520	31/41 − 10/49	29/46 − 4/51
0.5230	17/43 + 6/47	14/49 + 14/59	0.5526	…	21/38
0.5238	11/21	22/42	0.5530	15/21 − 5/31	28/54 + 2/58
0.5240	29/47 − 4/43	32/51 − 6/58	0.5532	26/47	26/47
0.5250	6/16 + 3/20	7/24 + 7/30	0.5540	12/23 + 1/31	12/53 + 19/58
0.5254	…	31/59	0.5550	1/41 + 26/49	17/25 − 3/24
0.5260	28/37 − 9/39	26/46 − 2/51	0.5556	10/18	30/54
0.5263	10/19	20/38	0.5556	15/27	…
0.5263	…	30/57	0.5560	32/41 − 11/49	35/47 − 10/53
0.5270	32/47 − 6/39	6/53 + 24/58	0.5570	22/41 + 1/49	18/49 + 11/58
0.5280	19/39 + 2/49	35/59 − 3/46	0.5580	3/29 + 15/33	7/53 + 23/54
0.5283	…	28/53	0.5581	24/43	24/43
0.5290	18/37 + 2/47	30/53 − 2/54	0.5588	…	19/34
0.5294	9/17	18/34	0.5590	27/37 − 7/41	43/59 − 9/53
0.5294	…	27/51	0.5593	…	33/59
0.5300	5/27 + 10/29	6/24 + 7/25	0.5600	37/49 − 8/41	14/25
0.5303	…	35/66	0.5606	…	37/66
0.5306	26/49	26/49	0.5610	23/41	23/41
0.5310	15/23 − 4/33	24/37 − 4/34	0.5610	4/23 + 12/31	5/51 + 25/54
0.5319	25/47	25/47	0.5614	…	32/57
0.5320	7/27 + 9/33	5/51 + 23/53	0.5620	1/23 + 14/27	9/34 + 11/37
0.5323	…	33/62	0.5625	9/16	…
0.5330	18/37 + 2/43	16/46 + 10/54	0.5630	12/39 + 12/47	22/46 + 5/59
0.5333	8/15	16/30	0.5640	25/33 − 6/31	41/49 − 18/66
0.5340	28/41 − 7/47	37/51 − 9/47	0.5641	22/39	22/39
0.5345	…	31/58	0.5645	…	35/62
0.5349	23/43	23/43	0.5650	10/31 + 8/33	3/24 + 11/25
0.5350	16/37 + 4/39	9/24 + 4/25	0.5652	13/23	26/46
0.5357	…	15/28	0.5660	4/39 + 19/41	9/46 + 20/54
0.5360	1/41 + 22/43	5/49 + 23/53	0.5660	…	30/53
0.5366	22/41	22/41	0.5667	…	17/30

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.5670	33/47 − 5/37	25/47 + 2/57	0.5970	6/47 + 23/49	13/58 + 22/59
0.5676	21/37	21/37	0.5980	35/49 − 5/43	16/47 + 17/66
0.5680	23/31 − 4/23	21/47 + 8/66	0.5990	17/37 + 6/43	23/49 + 7/54
0.5686	…	29/51	0.6000	9/15	15/25
0.5690	…	33/58	0.6000	12/20	18/30
0.5690	28/39 − 7/47	42/59 − 7/49	0.6010	32/41 − 7/39	32/41 − 7/39
0.5700	21/43 + 4/49	6/24 + 8/25	0.6020	13/16 − 4/19	20/47 + 9/51
0.5710	9/43 + 17/47	39/57 − 6/53	0.6030	16/41 + 10/47	24/49 + 6/53
0.5714	12/21	16/28	0.6034	…	35/58
0.5714	28/49	24/42	0.6038	…	32/53
0.5714	…	28/49	0.6040	23/31 − 4/29	21/58 + 15/62
0.5720	31/43 − 7/47	40/58 − 6/51	0.6047	…	26/43
0.5730	12/39 + 13/49	23/57 + 10/59	0.6050	11/37 + 12/39	3/24 + 12/25
0.5740	14/41 + 10/43	23/37 − 2/42	0.6053	…	23/38
0.5741	…	31/54	0.6060	28/41 − 3/39	29/54 + 4/58
0.5745	27/47	27/47	0.6061	20/33	40/66
0.5750	3/15 + 6/16	9/24 + 6/30	0.6070	31/49 − 1/39	23/47 + 6/51
0.5758	19/33	38/66	0.6071	…	17/28
0.5760	21/29 − 4/27	24/49 + 5/58	0.6078	…	31/51
0.5763	…	34/59	0.6080	1/31 + 19/33	24/53 + 9/58
0.5770	5/37 + 19/43	32/46 − 7/59	0.6087	14/23	28/46
0.5780	2/21 + 14/29	25/49 + 4/59	0.6090	17/31 + 2/33	40/59 − 4/58
0.5789	11/19	22/38	0.6098	25/41	25/41
0.5789	…	33/57	0.6100	23/33 − 2/23	6/24 + 9/25
0.5790	26/43 − 1/39	38/62 − 2/59	0.6102	…	36/59
0.5800	3/43 + 25/49	12/25 + 3/30	0.6110	1/39 + 24/41	5/28 + 16/37
0.5806	18/31	36/62	0.6111	…	33/54
0.5810	21/39 + 2/47	18/53 + 14/58	0.6120	27/41 − 2/43	29/39 − 5/38
0.5814	25/43	25/43	0.6122	30/49	30/49
0.5820	6/21 + 8/27	23/38 − 1/43	0.6129	19/31	38/62
0.5830	11/37 + 14/49	8/46 + 27/66	0.6130	15/19 − 3/17	1/49 + 32/54
0.5833	…	14/24	0.6140	25/39 − 1/37	36/49 − 7/58
0.5840	18/39 + 6/49	13/57 + 21/59	0.6140	…	35/57
0.5849	…	31/53	0.6150	22/37 + 1/49	9/24 + 6/25
0.5850	3/23 + 15/33	15/24 − 1/25	0.6154	24/39	24/39
0.5854	24/41	24/41	0.6160	10/41 + 16/43	14/53 + 19/54
0.5860	20/39 + 3/41	17/54 + 16/59	0.6170	12/37 + 12/41	5/59 + 33/62
0.5862	17/29	34/58	0.6170	29/47	29/47
0.5870	…	27/46	0.6176	…	21/34
0.5870	30/47 − 2/39	37/53 − 6/54	0.6180	5/39 + 24/49	3/53 + 32/57
0.5880	1/37 + 23/41	28/57 + 6/62	0.6190	1/43 + 28/47	17/53 + 17/57
0.5882	10/17	20/34	0.6190	13/21	26/42
0.5882	…	30/51	0.6200	23/43 + 4/47	8/25 + 9/30
0.5890	32/41 − 9/47	8/46 + 22/53	0.6207	…	36/58
0.5897	23/39	23/39	0.6210	29/37 − 7/43	6/46 + 26/53
0.5900	29/47 − 1/37	18/24 − 4/25	0.6212	…	41/66
0.5909	…	39/66	0.6216	23/37	23/37
0.5910	24/39 − 1/41	40/59 − 4/46	0.6220	14/27 + 3/29	15/53 + 20/59
0.5918	29/49	29/49	0.6226	…	33/53
0.5920	21/37 + 1/41	21/34 − 1/39	0.6230	24/37 − 1/39	24/37 − 1/39
0.5926	16/27	32/54	0.6240	5/29 + 14/31	4/49 + 32/59
0.5930	1/15 + 10/19	22/34 − 2/37	0.6250	10/16	15/24
0.5932	…	35/59	0.6260	12/43 + 17/49	21/46 + 10/59
0.5940	6/29 + 12/31	15/49 + 19/66	0.6270	17/47 + 13/49	24/46 + 6/57
0.5946	22/37	22/37	0.6271	…	37/59
0.5950	12/41 + 13/43	18/25 − 3/24	0.6275	…	32/51
0.5952	…	25/42	0.6279	27/43	27/43
0.5957	28/47	28/47	0.6280	23/33 − 2/29	28/47 + 2/62
0.5960	28/39 − 5/41	15/51 + 16/53	0.6290	11/39 + 17/49	12/54 + 24/59
0.5965	…	34/57	0.6290	…	39/62
0.5968	…	37/62	0.6296	17/27	34/54

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.6300	11/41 + 17/47	18/24 − 3/25	0.6610	…	39/59
0.6304	…	29/46	0.6613	…	41/62
0.6310	9/37 + 19/49	8/49 + 29/62	0.6620	13/23 + 3/31	36/53 − 1/58
0.6316	12/19	24/38	0.6630	35/49 − 2/39	11/39 + 16/42
0.6316	…	36/57	0.6640	13/41 + 17/49	33/51 + 1/59
0.6320	12/37 + 12/39	12/34 + 12/43	0.6650	16/37 + 10/43	15/24 + 1/25
0.6327	31/49	31/49	0.6660	34/41 − 8/49	21/51 + 15/59
0.6330	13/27 + 5/33	14/51 + 19/53	0.6667	10/15	16/24
0.6333	…	19/30	0.6667	12/18	20/30
0.6340	7/17 + 4/18	25/37 − 1/24	0.6667	14/21	26/39
0.6341	26/41	26/41	0.6667	18/27	28/42
0.6350	9/39 + 19/47	19/25 − 3/24	0.6667	22/33	34/51
0.6360	7/37 + 21/47	12/54 + 24/58	0.6667	26/39	36/54
0.6364	21/33	42/66	0.6667	…	38/57
0.6370	5/47 + 26/49	10/47 + 28/66	0.6667	…	44/66
0.6379	…	37/58	0.6670	24/41 + 4/49	5/51 + 33/58
0.6380	12/27 + 6/31	6/34 + 18/39	0.6680	14/41 + 16/49	11/47 + 23/53
0.6383	30/47	30/47	0.6690	5/23 + 14/31	10/46 + 28/62
0.6390	14/23 + 1/33	28/39 − 3/38	0.6700	37/49 − 4/47	18/24 − 2/25
0.6400	4/37 + 25/47	16/25	0.6710	9/21 + 8/33	15/47 + 19/54
0.6410	…	45/66 − 2/49	0.6720	15/41 + 15//49	7/54 + 32//59
0.6410	25/39	25/39	0.6724	…	39/58
0.6415	…	34/53	0.6730	7/43 + 25//49	42/57 − 3//47
0.6420	23/37 + 1/49	20/59 + 20/66	0.6735	33/49	33/49
0.6429	…	18/28	0.6739	…	31/46
0.6429	…	27/42	0.6740	4/39 + 28/49	21/53 + 15/54
0.6430	41/37 − 20/43	24/51 + 10/58	0.6744	29/43	29/43
0.6440	31/43 − 3/39	31/43 − 3/39	0.6750	10/16 + 1/20	9/24 + 9/30
0.6441	…	38/59	0.6757	25/37	25/37
0.6450	33/43 − 6/49	3/24 + 13/25	0.6760	20/23 − 6/31	43/62 − 1/57
0.6452	20/31	40/62	0.6765	…	23/34
0.6460	23/37 + 1/41	2/47 + 35/58	0.6770	7/37 + 20/41	26/53 + 11/59
0.6470	8/39 + 19/43	24/47 + 9/66	0.6774	21/31	42/62
0.6471	11/17	22/34	0.6780	…	40/59
0.6471	…	33/51	0.6780	21/39 + 6/43	6/49 + 30/54
0.6480	31/41 − 4/37	43/57 − 5/47	0.6786	…	19/28
0.6481	…	35/54	0.6790	7/37 + 24/49	19/51 + 19/62
0.6486	24/37	24/37	0.6792	…	36/53
0.6490	3/23 + 14/27	8/30 + 13/34	0.6800	31/47 + 1/49	17/25
0.6491	…	37/57	0.6809	32/47	32/47
0.6500	13/20	6/24 + 12/30	0.6810	21/27 − 3/31	29/41 − 1/38
0.6510	18/29 + 1/33	25/59 + 15/66	0.6818	…	45/66
0.6512	…	28/43	0.6820	15/37 + 13/47	37/51 − 2/46
0.6515	…	43/66	0.6829	28/41	28/41
0.6520	8/31 + 13/33	46/59 − 6/47	0.6830	5/17 + 7/18	35/57 + 4/58
0.6522	15/23	30/46	0.6840	31/37 − 6/39	13/47 + 22/54
0.6530	24/31 − 4/33	22/54 + 14/57	0.6842	13/19	26/38
0.6531	32/49	32/49	0.6842	…	39/57
0.6540	23/41 + 4/43	34/58 + 4/59	0.6850	15/41 + 15/47	3/24 + 14/25
0.6550	23/31 − 2/23	9/24 + 7/25	0.6852	…	37/54
0.6552	19/29	38/58	0.6860	3/23 + 15/27	19/49 + 17/57
0.6560	29/41 − 2/39	23/24 − 13/43	0.6863	…	35/51
0.6570	10/23 + 6/27	20/46 + 12/54	0.6870	28/37 − 3/43	36/51 − 1/53
0.6579	…	25/38	0.6875	11/16	…
0.6580	10/21 + 6/33	20/34 + 3/43	0.6880	13/21 + 2/29	30/49 + 5/66
0.6585	27/41	27/41	0.6890	36/47 − 3/39	42/53 − 6/58
0.6590	15/27 + 3/29	3/54 + 35/58	0.6897	20/29	40/58
0.6596	31/47	31/47	0.6900	21/37 + 6/49	6/24 + 11/25
0.6600	8/47 + 24/49	9/25 + 9/30	0.6905	…	29/42
0.6604	…	35/53	0.6910	35/49 − 1/43	21/57 + 20/62
0.6610	2/41 + 30/49	34/57 + 4/62	0.6920	35/43 − 5/41	35/43 − 5/41

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.6923	27/39	27/39	0.7234	…	34/47
0.6930	19/37 + 7/39	19/37 + 7/39	0.7240	3/27 + 19/31	34/41 − 4/38
0.6935	…	43/62	0.7241	21/29	42/58
0.6939	34/49	34/49	0.7250	2/16 + 12/20	7/24 + 13/30
0.6940	10/23 + 7/27	14/38 + 14/43	0.7255	…	37/51
0.6949	…	41/59	0.7258	…	45/62
0.6950	24/33 − 1/31	9/24 + 8/25	0.7260	34/41 − 6/47	2/49 + 37/54
0.6957	16/23	32/46	0.7270	15/19 − 1/16	14/54 + 29/62
0.6960	15/31 + 7/33	32/47 + 1/66	0.7273	24/33	48/66
0.6970	…	46/66	0.7280	23/37 + 5/47	23/49 + 15/58
0.6970	24/39 + 4/49	24/51 + 12/53	0.7288	…	43/59
0.6977	30/43	30/43	0.7290	38/49 − 2/43	12/47 + 27/57
0.6980	22/29 − 2/33	4/47 + 38/62	0.7297	27/37	27/37
0.6981	…	37/53	0.7300	11/27 + 10/31	6/24 + 12/25
0.6990	34/47 − 1/41	14/58 + 27/59	0.7310	15/37 + 14/43	26/59 + 18/62
0.7000	14/20	21/30	0.7317	30/41	30/41
0.7010	24/43 + 7/49	28/47 + 6/57	0.7320	20/37 + 9/47	26/57 + 16/58
0.7018	…	40/57	0.7330	19/37 + 9/41	39/47 − 6/62
0.7020	10/21 + 7/31	7/37 + 20/39	0.7333	11/15	22/30
0.7021	33/47	33/47	0.7340	6/21 + 13/29	26/49 + 12/59
0.7027	26/37	26/37	0.7347	36/49	36/49
0.7030	25/31 − 3/29	23/58 + 19/62	0.7350	29/37 − 2/41	9/24 + 9/25
0.7037	19/27	38/54	0.7353	…	25/34
0.7040	8/37 + 20/41	47/59 − 5/54	0.7358	…	39/53
0.7050	19/37 + 9/47	15/24 + 2/25	0.7360	25/47 + 10/49	47/59 − 4/66
0.7059	12/17	24/34	0.7368	14/19	28/38
0.7059	…	36/51	0.7368	…	42/57
0.7060	18/37 + 9/41	38/58 + 3/59	0.7370	2/37 + 28/41	13/49 + 25/53
0.7069	…	41/58	0.7380	19/37 + 11/49	31/47 + 4/51
0.7070	6/39 + 26/47	7/30 + 18/38	0.7381	…	31/42
0.7073	29/41	29/41	0.7390	6/31 + 18/33	12/62 + 36/66
0.7080	30/39 − 3/49	13/58 + 30/62	0.7391	17/23	34/46
0.7083	…	17/24	0.7400	8/39 + 23/43	6/25 + 15/30
0.7090	34/39 − 7/43	31/46 + 2/57	0.7407	20/27	40/54
0.7097	22/31	44/62	0.7410	9/39 + 25/49	49/57 − 7/59
0.7100	20/43 + 12/49	18/24 − 1/25	0.7414	…	43/58
0.7105	…	27/38	0.7419	23/31	46/62
0.7110	22/29 − 1/21	33/39 − 5/37	0.7420	17/39 + 15/49	28/51 + 11/57
0.7119	…	42/59	0.7424	…	49/66
0.7120	6/39 + 24/43	31/54 + 8/58	0.7430	19/39 + 11/43	1/53 + 42/58
0.7121	…	47/66	0.7436	…	29/39
0.7130	27/43 + 4/47	17/30 + 6/41	0.7440	4/29 + 20/33	27/49 + 11/57
0.7140	6/43 + 27/47	45/57 − 4/53	0.7442	32/43	32/43
0.7143	15/21	20/28	0.7447	35/47	35/47
0.7143	35/49	30/42	0.7450	17/21 − 2/31	15/24 + 3/25
0.7143	…	35/49	0.7451	…	38/51
0.7150	28/43 + 3/47	21/25 − 3/24	0.7458	…	44/59
0.7160	2/47 + 33/49	25/51 + 14/62	0.7460	13/47 + 23/49	2/59 + 47/66
0.7170	…	38/53	0.7470	23/41 + 8/43	29/49 + 9/58
0.7170	29/43 + 2/47	28/59 + 16/66	0.7480	19/43 + 15/49	10/53 + 33/59
0.7174	…	33/46	0.7490	13/15 − 2/17	36/47 − 1/59
0.7179	28/39	28/39	0.7500	12/16	18/24
0.7180	22/27 − 3/31	21/58 + 21/59	0.7500	15/20	21/28
0.7190	39/49 − 3/39	12/57 + 30/59	0.7510	11/23 + 9/33	39/53 + 1/66
0.7193	…	41/57	0.7520	19/23 − 2/27	39/57 + 4/59
0.7200	2/43 + 33/49	18/25	0.7530	23/39 + 8/49	11/53 + 36/66
0.7209	31/43	31/43	0.7540	6/37 + 29/49	25/46 + 12/57
0.7210	13/29 + 9/33	21/47 + 17/62	0.7544	…	43/57
0.7220	18/23 − 2/33	13/46 + 29/66	0.7547	…	40/53
0.7222	13/18	39/54	0.7550	24/37 + 5/47	21/24 − 3/25
0.7230	6/29 + 16/31	11/46 + 30/62	0.7551	37/49	37/49

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.7560	1/47 + 36/49	9/47 + 35/62	0.7860	17/37 + 16/49	49/58 − 3/51
0.7561	31/41	31/41	0.7870	10/39 + 26/49	30/37 − 1/42
0.7568	28/37	28/37	0.7872	37/47	37/47
0.7570	15/43 + 20/49	8/53 + 40/66	0.7879	26/33	52/66
0.7576	25/33	50/66	0.7880	6/39 + 26/41	45/51 − 5/53
0.7580	16/37 + 14/43	48/59 − 3/54	0.7890	19/41 + 14/43	37/49 + 2/59
0.7581	…	47/62	0.7895	…	30/38
0.7586	22/29	44/58	0.7895	…	45/57
0.7590	28/47 + 8/49	36/41 − 5/42	0.7900	15/37 + 15/39	18/24 + 1/25
0.7593	…	41/54	0.7903	…	49/62
0.7600	39/47 − 3/43	19/25	0.7907	34/43	34/43
0.7609	…	35/46	0.7910	8/29 + 17/33	7/49 + 35/54
0.7610	19/43 + 15/47	34/51 + 5/53	0.7917	…	19/24
0.7619	16/21	32/42	0.7920	8/29 + 16/31	4/47 + 41/58
0.7620	38/47 − 2/43	16/51 + 26/58	0.7925	…	42/53
0.7627	…	45/59	0.7930	10/39 + 22/41	7/47 + 38/59
0.7630	14/37 + 15/39	36/46 − 1/51	0.7931	23/29	46/58
0.7632	…	29/38	0.7940	28/43 + 7/49	14/57 + 34/62
0.7640	29/39 + 1/49	27/57 + 18/62	0.7941	…	27/34
0.7647	13/17	26/34	0.7949	31/39	31/39
0.7647	…	39/51	0.7950	24/37 + 6/41	21/24 − 2/25
0.7650	16/27 + 5/29	3/24 + 16/25	0.7959	39/49	39/49
0.7660	36/47	36/47	0.7960	2/39 + 35/47	18/37 + 13/42
0.7660	13/37 + 17/41	4/37 + 25/38	0.7963	…	43/54
0.7667	…	23/30	0.7966	…	47/59
0.7670	14/41 + 20/47	31/38 − 2/41	0.7970	40/47 − 2/37	13/53 + 32/58
0.7674	33/43	33/43	0.7980	14/39 + 18/41	33/51 + 8/53
0.7680	21/41 + 11/43	21/41 + 11/43	0.7990	3/37 + 28/39	10/28 + 19/43
0.7690	16/47 + 21/49	15/54 + 28/57	0.8000	12/15	20/25
0.7692	30/39	30/39	0.8000	16/20	24/30
0.7700	14/23 + 5/31	6/24 + 13/25	0.8010	32/37 − 3/47	10/47 + 30/51
0.7710	21/39 + 10/43	48/59 − 2/47	0.8020	27/31 − 2/29	54/62 − 4/58
0.7719	…	44/57	0.8030	18/39 + 14/41	18/39 + 14/41
0.7720	2/37 + 28/39	2/37 + 28/39	0.8030	…	53/66
0.7727	…	51/66	0.8039	…	41/51
0.7730	20/27 + 1/31	1/34 + 29/39	0.8040	10/43 + 28/49	32/49 + 8/53
0.7736	…	41/53	0.8043	…	37/46
0.7740	32/39 − 2/43	32/39 − 2/43	0.8049	33/41	33/41
0.7742	24/31	48/62	0.8050	22/23 − 5/33	3/24 + 17/25
0.7750	6/16 + 8/20	9/24 + 12/30	0.8060	34/41 − 1/43	13/47 + 27/51
0.7755	38/49	38/49	0.8065	25/31	50/62
0.7759	…	45/58	0.8070	5/15 + 9/19	15/58 + 34/62
0.7760	36/41 − 5/49	5/51 + 40/59	0.8070	…	46/57
0.7770	6/23 + 16/31	47/59 − 1/51	0.8080	19/21 − 3/31	22/39 + 10/41
0.7778	14/18	42/54	0.8085	38/47	38/47
0.7778	21/27	…	0.8090	22/39 + 12/49	28/53 + 16/57
0.7780	16/41 + 19/49	41/47 − 5/53	0.8095	…	34/42
0.7790	6/41 + 31/49	49/57 − 5/62	0.8100	33/43 + 2/47	6/24 + 14/25
0.7797	…	46/59	0.8103	…	47/58
0.7800	28/37 + 1/43	17/25 + 3/30	0.8108	30/37	30/37
0.7805	32/41	32/41	0.8110	7/27 + 16/29	34/53 + 10/59
0.7810	12/23 + 7/27	17/57 + 28/58	0.8113	…	43/53
0.7820	28/31 − 4/33	45/49 − 9/66	0.8120	17/29 + 7/31	34/58 + 14/62
0.7826	18/23	36/46	0.8125	13/16	…
0.7830	13/31 + 12/33	23/46 + 15/53	0.8130	6/43 + 33/49	16/24 + 6/41
0.7838	29/37	29/37	0.8136	…	48/59
0.7840	21/23 − 4/31	34/47 + 4/66	0.8140	35/43	35/43
0.7843	…	40/51	0.8140	28/33 − 1/29	14/47 + 32/62
0.7850	32/43 + 2/49	15/24 + 4/25	0.8148	22/27	44/54
0.7857	…	22/28	0.8150	22/47 + 17/49	9/24 + 11/25
0.7857	…	33/42	0.8158	…	31/38

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.8160	5/37 + 32/47	23/34 + 6/43	0.8478	…	39/46
0.8163	40/49	40/49	0.8480	30/41 + 5/43	31/59 + 20/62
0.8170	12/17 + 2/18	13/54 + 34/59	0.8485	28/33	56/66
0.8180	30/39 + 2/41	33/54 + 12/58	0.8490	13/41 + 25/47	2/47 + 50/62
0.8182	27/33	54/66	0.8491	…	45/53
0.8190	26/37 + 5/43	20/34 + 9/39	0.8500	17/20	18/24 + 3/30
0.8200	28/39 + 5/49	8/25 + 15/30	0.8510	5/21 + 19/31	22/37 + 10/39
0.8205	32/39	32/39	0.8511	40/47	40/47
0.8210	10/21 + 10/29	10/59 + 43/66	0.8519	23/27	46/54
0.8214	…	23/28	0.8520	1/16 + 15/19	55/62 − 2/57
0.8220	18/41 + 18/47	11/57 + 39/62	0.8529	…	29/34
0.8226	…	51/62	0.8530	17/21 + 1/23	19/58 + 31/59
0.8230	34/39 − 2/41	4/49 + 43/58	0.8537	35/41	35/41
0.8235	14/17	28/34	0.8540	15/39 + 23/49	54/62 − 1/59
0.8235	…	42/51	0.8548	…	53/62
0.8240	15/37 + 18/43	19/53 + 27/58	0.8550	19/37 + 14/41	9/24 + 12/25
0.8246	…	47/57	0.8560	24/43 + 14/47	37/53 + 9/57
0.8250	6/16 + 9/20	7/24 + 16/30	0.8570	3/43 + 37/47	51/57 − 2/53
0.8260	4/31 + 23/33	39/62 + 13/66	0.8571	18/21	24/28
0.8261	19/23	38/46	0.8571	42/49	36/42
0.8270	32/41 + 2/43	46/58 + 2/59	0.8571	…	42/49
0.8276	24/29	48/58	0.8580	25/43 + 13/47	38/51 + 7/62
0.8280	35/41 − 1/39	35/41 − 1/39	0.8590	11/27 + 14/31	22/54 + 28/62
0.8290	5/37 + 34/49	10/34 + 23/43	0.8596	…	49/57
0.8293	34/41	34/41	0.8600	1/43 + 41/49	9/25 + 15/30
0.8298	39/47	39/47	0.8605	37/43	37/43
0.8300	17/23 + 3/33	18/24 + 2/25	0.8610	16/37 + 21/49	18/46 + 31/66
0.8302	…	44/53	0.8620	13/37 + 24/47	17/38 + 17/41
0.8305	…	49/59	0.8621	25/29	50/58
0.8310	34/39 − 2/49	39/49 + 2/57	0.8627	…	44/51
0.8320	27/43 + 10/49	27/53 + 20/62	0.8630	38/41 − 3/47	18/46 + 25/53
0.8330	9/37 + 23/39	42/47 − 4/66	0.8636	…	57/66
0.8333	15/18	20/24	0.8640	11/16 + 3/17	56/62 − 2/51
0.8333	…	25/30	0.8644	…	51/59
0.8333	…	35/42	0.8649	32/37	32/37
0.8333	…	45/54	0.8650	4/41 + 33/43	15/24 + 6/25
0.8333	…	55/66	0.8660	10/17 + 5/18	13/57 + 37/58
0.8340	15/23 + 6/33	20/38 + 12/39	0.8667	13/15	26/30
0.8350	43/49 − 2/47	21/24 − 1/25	0.8670	3/21 + 21/29	28/54 + 23/66
0.8360	2/41 + 37/47	32/46 + 8/57	0.8679	…	46/53
0.8367	41/49	41/49	0.8680	36/47 + 5/49	53/59 − 2/66
0.8370	19/29 + 6/33	33/57 + 16/62	0.8684	…	33/38
0.8372	…	36/43	0.8690	40/43 − 3/49	39/47 + 2/51
0.8378	…	31/37	0.8696	20/23	40/46
0.8380	7/39 + 27/41	20/46 + 25/62	0.8700	4/39 + 33/43	18/24 + 3/25
0.8387	26/31	52/62	0.8704	…	47/54
0.8390	30/39 + 3/43	3/49 + 42/54	0.8710	27/31	54/62
0.8400	19/37 + 16/49	21/25	0.8710	17/27 + 7/29	31/51 + 15/57
0.8410	23/43 + 15/49	44/51 − 1/46	0.8718	34/39	34/39
0.8420	34/37 − 3/39	46/49 − 6/62	0.8720	30/37 + 3/49	26/58 + 25/59
0.8421	16/19	32/38	0.8723	41/47	41/47
0.8421	…	48/57	0.8730	15/39 + 21/43	21/49 + 24/54
0.8430	6/37 + 32/47	9/47 + 43/66	0.8740	15/39 + 23/47	5/53 + 46/59
0.8431	…	43/51	0.8750	14/16	21/24
0.8440	17/21 + 1/29	41/54 + 5/59	0.8760	21/23 − 1/27	48/57 + 2/59
0.8448	…	49/58	0.8770	3/37 + 39/49	37/51 + 10/66
0.8450	29/37 + 3/49	3/24 + 18/25	0.8772	…	50/57
0.8460	27/37 + 5/43	22/54 + 25/57	0.8776	43/49	43/49
0.8462	33/39	33/39	0.8780	24/47 + 18/49	31/53 + 17/58
0.8470	5/23 + 17/27	26/38 + 7/43	0.8780	36/41	36/41
0.8475	…	50/59	0.8788	…	58/66

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.8790	22/43 + 18/49	52/58 − 1/57	0.9110	31/37 + 3/41	31/37 + 3/41
0.8793	…	51/58	0.9118	…	31/34
0.8800	31/39 + 4/47	22/25	0.9120	26/37 + 9/43	52/43 − 11/37
0.8810	…	37/42	0.9123	…	52/57
0.8810	19/29 + 7/31	8/51 + 42/58	0.9130	2/31 + 28/33	35/62 + 23/66
0.8814	…	52/59	0.9130	21/23	42/46
0.8820	20/37 + 14/41	42/57 + 9/62	0.9138	…	53/58
0.8824	15/17	30/34	0.9140	7/21 + 18/31	42/47 + 1/49
0.8824	…	45/51	0.9149	43/47	43/47
0.8830	27/41 + 11/49	7/51 + 44/59	0.9150	8/17 + 8/18	21/24 + 1/25
0.8837	38/43	38/43	0.9153	…	54/59
0.8840	23/29 + 3/33	37/47 + 6/62	0.9160	35/43 + 5/49	40/53 + 10/62
0.8850	7/23 + 18/31	3/24 + 19/25	0.9167	…	22/24
0.8860	38/41 − 2/49	38/59 + 15/62	0.9170	19/23 + 3/33	29/38 + 6/39
0.8868	…	47/53	0.9180	1/41 + 42/47	39/46 + 4/57
0.8870	28/41 + 10/49	34/51 + 13/59	0.9184	45/49	45/49
0.8871	…	55/62	0.9189	34/37	34/37
0.8880	18/41 + 22/49	28/51 + 20/59	0.9190	14/23 + 9/29	8/46 + 38/51
0.8889	16/18	48/54	0.9194	…	57/62
0.8889	24/27	…	0.9200	28/37 + 8/49	23/25
0.8890	8/41 + 34/49	53/57 − 2/49	0.9210	17/37 + 18/39	23/49 + 28/62
0.8900	39/41 − 3/49	6/24 + 16/25	0.9211	…	35/38
0.8910	29/41 + 9/49	52/57 − 1/47	0.9216	…	47/51
0.8913	…	41/46	0.9220	26/39 + 12/47	10/34 + 27/43
0.8919	33/37	33/37	0.9229	31/37 + 4/47	…
0.8920	19/41 + 21/49	17/47 + 35/66	0.9230	…	29/54 + 22/57
0.8929	…	25/28	0.9231	36/39	36/39
0.8930	27/37 + 8/49	5/46 + 40/51	0.9240	15/41 + 24/43	45/59 + 10/62
0.8936	42/47	42/47	0.9242	…	61/66
0.8939	…	59/66	0.9245	…	49/53
0.8940	27/29 − 1/27	28/49 + 20/62	0.9250	14/16 + 1/20	7/24 + 19/30
0.8947	17/19	34/38	0.9259	25/27	50/54
0.8947	…	51/57	0.9260	17/43 + 26/49	2/51 + 47/53
0.8950	30/41 + 8/49	9/24 + 13/25	0.9268	38/41	38/41
0.8960	20/41 + 20/49	8/47 + 45/62	0.9270	28/37 + 8/47	29/59 + 27/62
0.8966	26/29	52/58	0.9280	3/39 + 40/47	47/57 + 6/58
0.8970	14/43 + 28/49	7/57 + 48/62	0.9286	…	26/28
0.8974	35/39	35/39	0.9286	…	39/42
0.8980	44/49	44/49	0.9290	12/37 + 26/43	16/53 + 37/59
0.8980	1/39 + 41/47	28/57 + 24/59	0.9298	…	53/57
0.8983	…	53/59	0.9300	5/29 + 25/33	6/24 + 17/25
0.8990	8/39 + 34/49	42/51 + 4/53	0.9302	40/43	40/43
0.9000	18/20	27/30	0.9310	25/37 + 12/47	7/30 + 30/43
0.9010	28/29 − 2/31	27/58 + 27/62	0.9310	27/29	54/58
0.9020	20/27 + 5/31	46/51	0.9320	30/39 + 7/43	59/62 + 1/51
0.9020	…	29/53 + 22/62	0.9322	…	55/59
0.9024	37/41	37/41	0.9330	34/39 + 3/49	5/42 + 35/43
0.9030	17/41 + 21/43	17/41 + 21/43	0.9333	14/15	28/30
0.9032	28/31	56/62	0.9340	1/37 + 39/43	56/59 − 1/66
0.9040	17/41 + 23/47	7/53 + 44/57	0.9348	…	43/46
0.9048	19/21	38/42	0.9350	2/39 + 38/43	9/24 + 14/25
0.9050	38/43 + 1/47	15/24 + 7/25	0.9355	29/31	58/62
0.9057	…	48/53	0.9360	15/37 + 26/49	13/58 + 42/59
0.9060	17/43 + 24/47	17/58 + 38/62	0.9362	44/47	44/47
0.9070	39/43	39/43	0.9370	19/21 + 1/31	29/53 + 23/59
0.9070	14/29 + 14/33	7/47 + 47/62	0.9375	15/16	…
0.9074	…	49/54	0.9380	13/39 + 26/43	21/46 + 26/54
0.9080	1/27 + 27/31	29/54 + 23/62	0.9388	46/49	46/49
0.9090	14/37 + 26/49	8/53 + 47/62	0.9390	30/37 + 5/39	30/37 + 5/39
0.9091	30/33	60/66	0.9394	31/33	62/66
0.9100	14/39 + 27/49	18/24 + 4/25	0.9400	35/39 + 2/47	16/25 + 9/30

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* Accurate Angular Indexing

Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond	Part of a Turn	B&S, Becker, Hendey, K&T, & Rockford	Cincinnati and LeBlond
0.9410	30/41 + 9/43	25/47 + 27/66	0.9670	9/47 + 38/49	8/34 + 30/41
0.9412	16/17	32/34	0.9677	30/31	60/62
0.9412	…	48/51	0.9680	26/37 + 13/49	2/46 + 49/53
0.9420	15/37 + 22/41	42/47 + 3/62	0.9690	26/39 + 13/43	5/51 + 54/62
0.9430	9/23 + 16/29	12/49 + 37/53	0.9697	32/33	64/66
0.9434	…	50/53	0.9700	12/23 + 13/29	6/24 + 18/25
0.9440	9/43 + 36/49	26/46 + 25/66	0.9706	…	33/34
0.9444	17/18	51/54	0.9710	26/37 + 11/41	14/46 + 34/51
0.9450	37/41 + 2/47	15/24 + 8/25	0.9720	26/43 + 18/49	31/53 + 24/62
0.9459	35/37	35/37	0.9730	36/37	36/37
0.9460	12/39 + 30/47	22/46 + 29/62	0.9730	20/23 + 3/29	26/54 + 29/59
0.9470	33/47 + 12/49	14/49 + 41/62	0.9737	…	37/38
0.9474	18/19	36/38	0.9740	16/21 + 7/33	26/34 + 9/43
0.9474	…	54/57	0.9744	38/39	38/39
0.9480	18/37 + 18/39	11/38 + 27/41	0.9750	10/16 + 7/20	13/24 + 13/30
0.9483	…	55/58	0.9756	40/41	40/41
0.9487	37/39	37/39	0.9760	14/39 + 29/47	10/49 + 44/57
0.9490	1/15 + 15/17	13/47 + 39/58	0.9762	…	41/42
0.9492	…	56/59	0.9767	42/43	42/43
0.9500	19/20	6/24 + 21/30	0.9770	33/37 + 4/47	30/47 + 21/62
0.9510	29/43 + 13/47	41/53 + 11/62	0.9780	25/37 + 13/43	25/37 + 13/43
0.9512	39/41	39/41	0.9783	…	45/46
0.9516	…	59/62	0.9787	46/47	46/47
0.9520	8/43 + 36/47	30/53 + 22/57	0.9790	13/23 + 12/29	10/53 + 49/62
0.9524	20/21	40/42	0.9796	48/49	48/49
0.9530	5/43 + 41/49	16/59 + 45/66	0.9800	23/39 + 16/41	17/25 + 9/30
0.9535	41/43	41/43	0.9804	…	50/51
0.9540	29/37 + 8/47	28/54 + 27/62	0.9810	22/43 + 23/49	51/58 + 6/59
0.9545	…	63/66	0.9811	…	52/53
0.9550	7/39 + 38/49	21/24 + 2/25	0.9815	…	53/54
0.9560	13/37 + 26/43	13/37 + 26/43	0.9820	30/39 + 10/47	19/46 + 33/58
0.9565	22/23	44/46	0.9825	…	56/57
0.9570	14/21 + 9/31	21/47 + 25/49	0.9828	…	57/58
0.9574	45/47	45/47	0.9830	26/41 + 15/43	45/57 + 12/62
0.9580	5/39 + 39/47	20/53 + 36/62	0.9831	…	58/59
0.9583	…	23/24	0.9839	…	61/62
0.9590	21/41 + 21/47	18/51 + 40/66	0.9840	13/37 + 31/49	1/46 + 51/53
0.9592	47/49	47/49	0.9848	…	65/66
0.9600	7/39 + 32/41	24/25	0.9850	6/23 + 21/29	15/24 + 9/25
0.9608	…	49/51	0.9860	16/23 + 9/31	42/53 + 12/62
0.9610	11/23 + 14/29	5/34 + 35/43	0.9870	15/21 + 9/33	13/34 + 26/43
0.9620	28/41 + 12/43	52/59 + 5/62	0.9880	7/39 + 38/47	5/46 + 51/58
0.9623	…	51/53	0.9890	33/39 + 7/49	20/39 + 20/42
0.9630	26/27	52/54	0.9900	10/29 + 20/31	18/24 + 6/25
0.9630	30/43 + 13/49	1/51 + 50/53	0.9910	22/23 + 1/29	21/46 + 31/58
0.9640	21/39 + 20/47	52/57 + 3/58	0.9920	39/41 + 2/49	40/53 + 14/59
0.9643	…	27/28	0.9930	8/23 + 20/31	21/53 + 37/62
0.9649	…	55/57	0.9940	7/23 + 20/29	14/46 + 40/58
0.9650	11/39 + 28/41	3/24 + 21/25	0.9950	35/39 + 4/41	21/24 + 3/25
0.9655	28/29	56/58	0.9960	40/41 + 1/49	43/46 + 3/49
0.9660	13/39 + 31/49	15/39 + 25/43	0.9970	15/23 + 10/29	30/46 + 20/58
0.9661	…	57/59	0.9980	20/41 + 25/49	12/51 + 45/59
0.9667	…	29/30	0.9990	10/41 + 37/49	6/51 + 52/59

Approximate Indexing for Small Angles.— To find *approximate* indexing movements for small angles, such as the remainder from the method discussed in *Angular Indexing* starting on page 1990, on a dividing head with a 40:1 worm-gear ratio, divide 540 by the number of minutes in the angle, and then divide the number of holes in each of the available indexing circles by this quotient. The result that is closest to a whole number is the best approximation of the angle for a simple indexing movement and is the number of holes to

Copyright 2004, Industrial Press, Inc., New York, NY

be moved in the corresponding circle of holes. If the angle is greater than 9 degrees, the whole number will be greater than the number of holes in the circle, indicating that one or more full turns of the crank are required. Dividing by the number of holes in the indicated circle of holes will reduce the required indexing movement to the number of full turns, and the remainder will be the number of holes to be moved for the fractional turn. If the angle is less than about 11 minutes, it cannot be indexed by simple indexing with standard B & S plates (the corresponding angle for standard plates on a Cincinnati head is about 8 minutes, and for Cincinnati high number plates, 2.7 minutes. See Tables 5, 6a, and 6b for indexing movements with Cincinnati standard and high number plates).

Example: An angle of 7° 25′ is to be indexed. Expressed in minutes, it is 445′ and 540 divided by 445 equals 1.213483. The indexing circles available on standard B & S plates are 15, 16, 17, 18, 19, 20, 21, 23, 27, 29, 31, 33, 37, 39, 41, 43, 47, and 49. Each of these numbers is divided by 1.213483 and the closest to a whole number is found to be 17 ÷ 1.213483 = 14.00926. The best approximation for a simple indexing movement to obtain 7° 25′ is 14 holes on the 17-hole circle.

Differential Indexing.— This method is the same, in principle, as compound indexing (see *Compound Indexing* on page 1984), but differs from the latter in that the index plate is rotated by suitable gearing that connects it to the spiral-head spindle. This rotation or differential motion of the index plate takes place when the crank is turned, the plate moving either in the same direction as the crank or opposite to it, as may be required. The result is that the *actual* movement of the crank, at every indexing, is either greater or less than its movement with relation to the index plate. The differential method makes it possible to obtain almost any division by using only one circle of holes for that division and turning the index crank in one direction, as with plain indexing.

The gears to use for turning the index plate the required amount (when gears are required) are shown by Tables 4a and 4b, *Simple and Differential Indexing with Browne & Sharpe Indexing Plates*, which shows what divisions can be obtained by plain indexing, and when it is necessary to use gears and the differential system. For example, if 50 divisions are required, the 20-hole index circle is used and the crank is moved 16 holes, but no gears are required. For 51 divisions, a 24-tooth gear is placed on the wormshaft and a 48-tooth gear on the spindle. These two gears are connected by two idler gears having 24 and 44 teeth, respectively.

To illustrate the principle of differential indexing, suppose a dividing head is to be geared for 271 divisions. Table 4b calls for a gear on the wormshaft having 56 teeth, a spindle gear with 72 teeth, and a 24-tooth idler to rotate the index plate in the same direction as the crank. The sector arms should be set to give the crank a movement of 3 holes in the 21-hole circle. If the spindle and the index plate were not connected through gearing, 280 divisions would be obtained by successively moving the crank 3 holes in the 21-hole circle, but the gears cause the index plate to turn in the same direction as the crank at such a rate that, when 271 indexings have been made, the work is turned one complete revolution. Therefore, we have 271 divisions instead of 280, the number being reduced because the total movement of the crank, for each indexing, is equal to the movement relative to the index plate, *plus* the movement of the plate itself when, as here, the crank and plate rotate in the same direction.

If they were rotated in opposite directions, the crank would have a total movement equal to the amount it turned relative to the plate, *minus* the plate's movement. Sometimes it is necessary to use compound gearing to move the index plate the required amount for each turn of the crank. The differential method cannot be used in connection with helical or spiral milling because the spiral head is then geared to the leadscrew of the machine.

Finding Ratio of Gearing for Differential Indexing.— To find the ratio of gearing for differential indexing, first select some approximate number *A* of divisions either greater or less than the required number *N*. For example, if the required number *N* is 67, the approxi-

Copyright 2004, Industrial Press, Inc., New York, NY

mate number *A* might be 70. Then, if 40 turns of the index crank are required for 1 revolution of the spindle, the gearing ratio $R = (A - N) \times 40/A$. If the approximate number *A* is less than *N*, the formula is the same as above except that $A - N$ is replaced by $N - A$.

Example: Find the gearing ratio and indexing movement for 67 divisions.

$$\text{If } A = 70, \text{ gearing ratio} = (70 - 67) \times \frac{40}{70} = \frac{12}{7} = \frac{\text{gear on spindle (driver)}}{\text{gear on worm (driven)}}$$

The fraction 12/7 is raised to obtain a numerator and a denominator to match gears that are available. For example, 12/7 = 48/28.

Various combinations of gearing and index circles are possible for a given number of divisions. The index numbers and gear combinations in the accompanying Tables 4a and 4b apply to a given series of index circles and gear-tooth numbers. The approximate number *A* on which any combination is based may be determined by dividing 40 by the fraction representing the indexing movement. For example, the approximate number used for 109 divisions equals 40 ÷ 6/16, or 40 × 16/6 = 106 2/3. If this approximate number is inserted in the preceding formula, it will be found that the gear ratio is 7/8, as shown in the table.

Second Method of Determining Gear Ratio: In illustrating a somewhat different method of obtaining the gear ratio, 67 divisions will again be used. If 70 is selected as the approximate number, then 40/70 = 4/7 or 12/21 turn of the index crank will be required. If the crank is indexed four-sevenths of a turn, sixty-seven times, it will make 4/7 × 67 = 38 2/7 revolutions. This number is 1 5/7 turns less than the 40 required for one revolution of the work (indicating that the gearing should be arranged to rotate the index plate in the same direction as the index crank to increase the indexing movement). Hence the gear ratio 1 5/7 = 12/7.

To Find the Indexing Movement.— The indexing movement is represented by the fraction 40/*A*. For example, if 70 is the approximate number *A* used in calculating the gear ratio for 67 divisions, then, to find the required movement of the index crank, reduce 40/70 to any fraction of equal value and having as denominator any number equal to the number of holes available in an index circle.

$$\text{To illustrate, } \frac{40}{70} = \frac{4}{7} = \frac{12}{21} = \frac{\text{number of holes indexed}}{\text{number of holes in index circle}}$$

Use of Idler Gears.— In differential indexing, idler gears are used to rotate the index plate in the same direction as the index crank, thus *increasing* the resulting indexing movement, or to rotate the index plate in the opposite direction, thus *reducing* the resulting indexing movement.

Example 1: If the approximate number *A* is *greater* than the required number of divisions *N*, simple gearing will require one idler, and compound gearing, no idler. Index plate and crank rotate in the same direction.

Example 2: If the approximate number *A* is *less* than the required number of divisions *N*, simple gearing requires two idlers, and compound gearing, one idler. Index plate and crank rotate in opposite directions.

When Compound Gearing Is Required.— It is sometimes necessary, as shown in the table, to use a train of four gears to obtain the required ratio with the gear-tooth numbers that are available.

Example: Find the gear combination and indexing movement for 99 divisions, assuming that an approximate number A of 100 is used.

$$\text{Ratio} = (100 - 99) \times \frac{40}{100} = \frac{4}{10} = \frac{4 \times 1}{5 \times 2} = \frac{32}{40} \times \frac{28}{56}$$

The final numbers here represent available gear sizes. The gears having 32 and 28 teeth are the drivers (gear on spindle and first gear on stud), and gears having 40 and 56 teeth are

Copyright 2004, Industrial Press, Inc., New York, NY

driven (second gear on stud and gear on wormshaft). The indexing movement is represented by the fraction $^{40}/_{100}$, which is reduced to $^{8}/_{20}$, the 20-hole index circle being used here.

Example: Determine the gear combination to use for indexing 53 divisions. If 56 is used as an approximate number (possibly after one or more trial solutions to find an approximate number and resulting gear ratio coinciding with available gears):

$$\text{Gearing ratio} = (56 - 53) \times \frac{40}{56} = \frac{15}{7} = \frac{3 \times 5}{1 \times 7} = \frac{72 \times 40}{24 \times 56}$$

The tooth numbers above the line here represent *gear on spindle* and *first gear on stud*. The tooth numbers below the line represent *second gear on stud* and *gear on wormshaft*.

$$\text{Indexing movement} = \frac{40}{56} = \frac{5}{7} = \frac{5 \times 7}{7 \times 7} = \frac{35 \text{ holes}}{49\text{-hole circle}}$$

To Check the Number of Divisions Obtained with a Given Gear Ratio and Index Movement.— Invert the fraction representing the indexing movement. Let C = this inverted fraction and R = gearing ratio.

Example 1: If simple gearing with one idler, or compound gearing with no idler, is used: number of divisions $N = 40C - RC$.

For instance, if the gear ratio is $^{12}/_{7}$, there is simple gearing and one idler, and the indexing movement is $^{12}/_{21}$, making the inverted fraction C, $^{21}/_{12}$; find the number of divisions N.

$$N = \left(40 \times \frac{21}{12}\right) - \left(\frac{12}{7} \times \frac{21}{12}\right) = 70 - \frac{21}{7} = 67$$

Example 2: If simple gearing with two idlers, or compound gearing with one idler, is used: number of divisions $N = 40C + RC$.

For instance, if the gear ratio is $^{7}/_{8}$, two idlers are used with simple gearing, and the indexing movement is 6 holes in the 16-hole circle, then number of divisions:

$$N = \left(40 \times \frac{16}{6}\right) + \left(\frac{7}{8} \times \frac{16}{6}\right) = 109$$



Sector Graduations

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. Simple and Differential Indexing with Browne & Sharpe Indexing Plates



Geared for 107 Divisions

No. of Div.	Index Circle	No. of Turns of Crank	Graduation on Sector	No. of Div.	Index Circle	No. of Turns of Crank	Graduation on Sector
2	Any	20	…	33	33	$1\frac{7}{33}$	41
3	39	$13\frac{13}{39}$	65	34	17	$1\frac{3}{17}$	33
4	Any	10	…	35	49	$1\frac{7}{49}$	26
5	Any	8	…	36	27	$1\frac{3}{27}$	21
6	39	$6\frac{26}{39}$	132	37	37	$1\frac{3}{37}$	15
7	49	$5\frac{35}{49}$	140	38	19	$1\frac{1}{19}$	9
8	Any	5	…	39	39	$1\frac{1}{39}$	3
9	27	$4\frac{12}{27}$	88	40	Any	1	…
10	Any	4	…	41	41	40/41	3*
11	33	$3\frac{21}{33}$	126	42	21	20/21	9*
12	39	$3\frac{13}{39}$	65	43	43	40/43	12*
13	39	$3\frac{3}{39}$	14	44	33	30/33	17*
14	49	$2\frac{42}{49}$	169	45	27	24/27	21*
15	39	$2\frac{23}{39}$	132	46	23	20/23	172
16	20	$2\frac{10}{20}$	98	47	47	40/47	168
17	17	$2\frac{6}{17}$	69	48	18	15/18	165
18	27	$2\frac{6}{27}$	43	49	49	40/49	161
19	19	$2\frac{2}{19}$	19	50	20	16/20	158
20	Any	2	…	51	17	14/17	33*
21	21	$1\frac{19}{21}$	18*	52	39	30/39	152
22	33	$1\frac{27}{33}$	161	53	49	35/49	140
23	23	$1\frac{17}{23}$	147	54	27	20/27	147
24	39	$1\frac{26}{39}$	132	55	33	24/33	144
25	20	$1\frac{12}{20}$	118	56	49	35/49	140
26	39	$1\frac{21}{39}$	106	57	21	15/21	142
27	27	$1\frac{13}{27}$	95	58	29	20/29	136
28	49	$1\frac{21}{49}$	83	59	39	26/39	132
29	29	$1\frac{11}{29}$	75	60	39	26/39	132
30	39	$1\frac{13}{39}$	65	61	39	26/39	132
31	31	$1\frac{9}{31}$	56	62	31	20/31	127
32	20	$1\frac{5}{20}$	48	63	39	26/39	132

Note: The data in columns labeled Graduation on Sector refer to a graduated dial that accompanies the sector arms on some dividing heads, page 2010. The graduated sector ring eliminates the requirement of counting holes and thereby lessens the possbility of error. Graduations in table indicate setting for sector arms when index crank moves through arc *A*, except figures marked *, when crank moves through arc *B*.

Differential Indexing

Certain divisions such as 51, 53, 57, etc., require the use of differential indexing. In differential indexing, change gears are used to transmit motion from the main spindle of the dividing head to the index plate, which turns (either in the same direction as the index plate or in the opposite direction) whatever amount is required to obtain the correct indexing movement.

The numbers in the columns below represent numbers of teeth for the change gears necessary to give the divisions required. Where no numbers are shown simple indexing, which does not require change gears, is used.

Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
	First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole
Differential Gears					
24	…	…	48	24	44
…	…	…	…	…	…
56	40	24	72	…	…
…	…	…	…	…	…
…	…	…	…	…	…
…	…	…	…	…	…
…	…	…	…	…	…
…	…	…	…	…	…
56	…	…	40	24	44
…	…	…	…	…	…
48	…	…	32	44	…
…	…	…	…	…	…
48	…	…	32	24	44
…	…	…	…	…	…
24	…	…	48	24	44

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. Simple and Differential Indexing
Browne & Sharpe Indexing Plates

No. of Divisions	Index Circle	No. of Turns of Crank	Graduation on Sector[a]	Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
					First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole[b]
64	16	10/16	123	…	…	…	…	…	…
65	39	24/39	121	…	…	…	…	…	…
66	33	20/33	120	…	…	…	…	…	…
67	21	12/21	113	28	…	…	48	44	…
68	17	10/17	116	…	…	…	…	…	…
69	20	12/20	118	40	…	…	56	24	44
70	49	28/49	112	…	…	…	…	…	…
71	18	10/18	109	72	…	…	40	24	…
72	27	15/27	110	…	…	…	…	…	…
73	21	12/21	113	28	…	…	48	24	44
74	37	20/37	107	…	…	…	…	…	…
75	15	8/15	105	…	…	…	…	…	…
76	19	10/19	103	…	…	…	…	…	…
77	20	10/20	98	32	…	…	48	44	…
78	39	20/39	101	…	…	…	…	…	…
79	20	10/20	98	48	…	…	24	44	…
80	20	10/20	98	…	…	…	…	…	…
81	20	10/20	98	48	…	…	24	24	44
82	41	20/41	96	…	…	…	…	…	…
83	20	10/20	98	32	…	…	48	24	44
84	21	10/21	94	…	…	…	…	…	…
85	17	8/17	92	…	…	…	…	…	…
86	43	20/48	91	…	…	…	…	…	…
87	15	7/15	92	40	…	…	24	24	44
88	33	15/33	89	…	…	…	…	…	…
89	18	8/18	87	72	…	…	32	44	…
90	27	12/27	88	…	…	…	…	…	…
91	39	18/39	91	24	…	…	48	24	44
92	23	10/23	86	…	…	…	…	…	…
93	18	8/18	87	24	…	…	32	24	44
94	47	20/47	83	…	…	…	…	…	…
95	19	8/19	82	…	…	…	…	…	…
96	21	9/21	85	28	…	…	32	24	44
97	20	8/20	78	40	…	…	48	44	…
98	49	20/49	79	…	…	…	…	…	…
99	20	8/20	78	56	28	40	32	…	…
100	20	8/20	78	…	…	…	…	…	…
101	20	8/20	78	72	24	40	48	…	24
102	20	8/20	78	40	…	…	32	24	44
103	20	8/20	78	40	…	…	48	24	44
104	39	15/39	75	…	…	…	…	…	…
105	21	8/21	75	…	…	…	…	…	…
106	43	16/43	73	86	24	24	48	…	…
107	20	8/20	78	40	56	32	64	…	24
108	27	10/27	73	…	…	…	…	…	…
109	16	6/16	73	32	…	…	28	24	44
110	33	12/33	71	…	…	…	…	…	…
111	39	13/39	65	24	…	…	72	32	…
112	39	13/39	65	24	…	…	64	44	…
113	39	13/39	65	24	…	…	56	44	…
114	39	13/39	65	24	…	…	48	44	…
115	23	8/23	68	…	…	…	…	…	…
116	29	10/29	68	…	…	…	…	…	…
117	39	13/39	65	24	…	…	24	56	…
118	39	13/39	65	48	…	…	32	44	…
119	39	13/39	65	72	…	…	24	44	…
120	39	13/39	65	…	…	…	…	…	…
121	39	13/39	65	72	…	…	24	24	44
122	39	13/39	65	48	…	…	32	24	44
123	39	13/39	65	24	…	…	24	24	44
124	31	10/31	63	…	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. ***(Continued)*** **Simple and Differential Indexing**
Browne & Sharpe Indexing Plates

No. of Divisions	Index Circle	No. of Turns of Crank	Graduation on Sector[a]	Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
					First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole[b]
125	39	13/39	65	24	…	…	40	24	44
126	39	13/39	65	24	…	…	48	24	44
127	39	13/39	65	24	…	…	56	24	44
128	16	5/16	61	…	…	…	…	…	…
129	39	13/39	65	24	…	…	72	24	44
130	39	12/39	60	…	…	…	…	…	…
131	20	6/20	58	40	…	…	28	44	…
132	33	10/33	59	…	…	…	…	…	…
133	21	6/21	56	24	…	…	48	44	…
134	21	6/21	56	28	…	…	48	44	…
135	27	8/27	58	…	…	…	…	…	…
136	17	5/17	57	…	…	…	…	…	…
137	21	6/21	56	28	…	…	24	56	…
138	21	6/21	56	56	…	…	32	44	…
139	21	6/21	56	56	32	48	24	…	…
140	49	14/49	55	…	…	…	…	…	…
141	18	5/18	54	48	…	…	40	44	…
142	21	6/21	56	56	…	…	32	24	44
143	21	6/21	56	28	…	…	24	24	44
144	18	5/18	54	…	…	…	…	…	…
145	29	8/29	54	…	…	…	…	…	…
146	21	6/21	56	28	…	…	48	24	44
147	21	6/21	56	24	…	…	48	24	44
148	37	10/37	53	…	…	…	…	…	…
149	21	6/21	56	28	…	…	72	24	44
150	15	4/15	52	…	…	…	…	…	…
151	20	5/20	48	32	…	…	72	44	…
152	19	5/19	51	…	…	…	…	…	…
153	20	5/20	48	32	…	…	56	44	…
154	20	5/20	48	32	…	…	48	44	…
155	31	8/31	50	…	…	…	…	…	…
156	39	10/39	50	…	…	…	…	…	…
157	20	5/20	48	32	…	…	24	56	…
158	20	5/20	48	48	…	…	24	44	…
159	20	5/20	48	64	32	56	28	…	…
160	20	5/20	48	…	…	…	…	…	…
161	20	5/20	48	64	32	56	28	…	24
162	20	5/20	48	48	…	…	24	24	44
163	20	5/20	48	32	…	…	24	24	44
164	41	10/41	47	…	…	…	…	…	…
165	33	8/33	47	…	…	…	…	…	…
166	20	5/20	48	32	…	…	48	24	44
167	20	5/20	48	32	…	…	56	24	44
168	21	5/21	47	…	…	…	…	…	…
169	20	5/20	48	32	…	…	72	24	44
170	17	4/17	45	…	…	…	…	…	…
171	21	5/21	47	56	…	…	40	24	44
172	43	10/43	44	…	…	…	…	…	…
173	18	4/18	43	72	56	32	64	…	…
174	18	4/18	43	24	…	…	32	56	…
175	18	4/18	43	72	40	32	64	…	…
176	18	4/18	43	72	24	24	64	…	…
177	18	4/18	43	72	…	…	48	24	…
178	18	4/18	43	72	…	…	32	44	…
179	18	4/18	43	72	24	48	32	…	…
180	18	4/18	43	…	…	…	…	…	…
181	18	4/18	43	72	24	48	32	…	24
182	18	4/18	43	72	…	…	32	24	44
183	18	4/18	43	48	…	…	32	24	44
184	23	5/23	42	…	…	…	…	…	…
185	37	8/37	42	…	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. ***(Continued)*** **Simple and Differential Indexing**
Browne & Sharpe Indexing Plates

No. of Divisions	Index Circle	No. of Turns of Crank	Graduation on Sector[a]	Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
					First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole[b]
186	18	4/18	43	48	…	…	64	24	44
187	18	4/18	43	72	48	24	56	…	24
188	47	10/47	40	…	…	…	…	…	…
189	18	4/18	43	32	…	…	64	24	44
190	19	4/19	40	…	…	…	…	…	…
191	20	4/20	38	40	…	…	72	24	…
192	20	4/20	38	40	…	…	64	44	…
193	20	4/20	38	40	…	…	56	44	…
194	20	4/20	38	40	…	…	48	44	…
195	39	8/39	39	…	…	…	…	…	…
196	49	10/49	38	…	…	…	…	…	…
197	20	4/20	38	40	…	…	24	56	…
198	20	4/20	38	56	28	40	32	…	…
199	20	4/20	38	100	40	64	32	…	…
200	20	4/20	38	…	…	…	…	…	…
201	20	4/20	38	72	24	40	24	…	24
202	20	4/20	38	72	24	40	48	…	24
203	20	4/20	38	40	…	…	24	24	44
204	20	4/20	38	40	…	…	32	24	44
204	20	4/20	38	40	…	…	32	24	44
205	41	8/41	37	…	…	…	…	…	…
206	20	4/20	38	40	…	…	48	24	44
207	20	4/20	38	40	…	…	56	24	44
208	20	4/20	38	40	…	…	64	24	44
209	20	4/20	38	40	…	…	72	24	44
210	21	4/21	37	…	…	…	…	…	…
211	16	3/16	36	64	…	…	28	44	…
212	43	8/43	35	86	24	24	48	…	…
213	27	5/27	36	72	…	…	40	44	…
214	20	4/20	38	40	56	32	64	…	24
215	43	8/43	35	…	…	…	…	…	…
216	27	5/27	36	…	…	…	…	…	…
217	21	4/21	37	48	…	…	64	24	44
218	16	3/16	36	64	…	…	56	24	44
219	21	4/21	37	28	…	…	48	24	44
220	33	6/33	35	…	…	…	…	…	…
221	17	3/17	33	24	…	…	24	56	…
222	18	3/18	32	24	…	…	72	44	…
223	43	8/43	35	86	8	24	64	…	24
224	18	3/18	32	24	…	…	64	44	…
225	27	5/27	36	24	…	…	40	24	44
226	18	3/18	32	24	…	…	56	44	…
227	49	8/49	30	56	64	28	72	…	…
228	18	3/18	32	24	…	…	48	44	…
229	18	3/18	32	24	…	…	44	48	…
230	23	4/23	34	…	…	…	…	…	…
231	18	3/18	32	32	…	…	48	44	…
232	29	5/29	33	…	…	…	…	…	…
233	18	3/18	32	48	…	…	56	44	…
234	18	3/18	32	24	…	…	24	56	…
235	47	8/47	32	…	…	…	…	…	…
236	18	3/18	32	48	…	…	32	44	…
237	18	3/18	32	48	…	…	24	44	…
238	18	3/18	32	72	…	…	24	44	…
239	18	3/18	32	72	24	64	32	…	…
240	18	3/18	32	…	…	…	…	…	…
241	18	3/18	32	72	24	64	32	…	24
242	18	3/18	32	72	…	…	24	24	44
243	18	3/18	32	64	…	…	32	24	44
244	18	3/18	32	48	…	…	32	24	44
245	49	8/49	30	…	…	…	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. ***(Continued)*** **Simple and Differential Indexing**
Browne & Sharpe Indexing Plates

No. of Divisions	Index Circle	No. of Turns of Crank	Graduation on Sector[a]	Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
					First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole[b]
246	18	3/18	32	24	…	…	24	24	44
247	18	3/18	32	48	…	…	56	24	44
248	31	5/31	31	…	…	…	…	…	…
249	18	3/18	32	32	…	…	48	24	44
250	18	3/18	32	24	…	…	40	24	44
251	18	3/18	32	48	44	32	64	…	24
252	18	3/18	32	24	…	…	48	24	44
253	33	5/33	29	24	…	…	40	56	…
254	18	3/18	32	24	…	…	56	24	44
255	18	3/18	32	48	40	24	72	…	24
256	18	3/18	32	24	…	…	64	24	44
257	49	8/49	30	56	48	28	64	…	24
258	43	7/43	31	32	…	…	64	24	44
259	21	3/21	28	24	…	…	72	44	…
260	39	6/39	29	…	…	…	…	…	…
261	29	4/29	26	48	64	24	72	…	…
262	20	3/20	28	40	…	…	28	44	…
263	49	8/49	30	56	64	28	72	…	24
264	33	5/33	29	…	…	…	…	…	…
265	21	3/21	28	56	40	24	72	…	…
266	21	3/21	28	32	…	…	64	44	…
267	27	4/27	28	72	…	…	32	44	…
268	21	3/21	28	28	…	…	48	44	…
269	20	3/20	28	64	32	40	28	…	24
270	27	4/27	28	…	…	…	…	…	…
271	21	3/21	28	56	24	24	72	…	…
272	21	3/21	28	56	…	…	64	24	…
273	21	3/21	28	24	…	…	24	56	…
274	21	3/21	28	56	…	…	48	44	…
275	21	3/21	28	56	…	…	40	44	…
276	21	3/21	28	56	…	…	32	44	…
277	21	3/21	28	56	…	…	24	44	…
278	21	3/21	28	56	32	48	24	…	…
279	27	4/27	28	24	…	…	32	24	44
280	49	7/49	26	…	…	…	…	…	…
281	21	3/21	28	72	24	56	24	…	24
282	43	6/43	26	86	24	24	56	…	…
283	21	3/21	28	56	…	…	24	24	44
284	21	3/21	28	56	…	…	32	24	44
285	21	3/21	28	56	…	…	40	24	44
286	21	3/21	28	56	…	…	48	24	44
287	21	3/21	28	24	…	…	24	24	44
288	21	3/21	28	28	…	…	32	24	44
289	21	3/21	28	56	24	24	72	…	24
290	29	4/29	26	…	…	…	…	…	…
291	15	2/15	25	40	…	…	48	44	…
292	21	3/21	28	28	…	…	48	24	44
293	15	2/15	25	48	32	40	56	…	…
294	21	3/21	28	24	…	…	48	24	44
295	15	2/15	25	48	…	…	32	44	…
296	37	5/37	26	…	…	…	…	…	…
297	33	4/33	23	28	48	24	56	…	…
298	21	3/21	28	28	…	…	72	24	44
299	23	3/23	25	24	…	…	24	56	…
300	15	2/15	25	…	…	…	…	…	…
301	43	6/43	26	24	…	…	48	24	44
302	16	2/16	24	32	…	…	72	24	…
303	15	2/15	25	72	24	40	48	…	24
304	16	2/16	24	24	…	…	48	44	…
305	15	2/15	25	48	…	…	32	24	44
306	15	2/15	25	40	…	…	32	24	44

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. ***(Continued)*** **Simple and Differential Indexing**
Browne & Sharpe Indexing Plates

No. of Divisions	Index Circle	No. of Turns of Crank	Graduation on Sector[a]	Gear on Worm	No. 1 Hole		Gear on Spindle	Idlers	
					First Gear on Stud	Second Gear on Stud		No. 1 Hole	No. 2 Hole[b]
307	15	2/15	25	72	48	40	56	…	24
308	16	2/16	24	32	…	…	48	44	…
309	15	2/15	25	40	…	…	48	24	44
310	31	4/31	24	…	…	…	…	…	…
311	16	2/16	24	64	24	24	72	…	…
312	39	5/39	24	…	…	…	…	…	…
313	16	2/16	24	32	…	…	28	56	…
314	16	2/16	24	32	…	…	24	56	…
315	16	2/16	24	64	…	…	40	24	…
316	16	2/16	24	64	…	…	32	44	…
317	16	2/16	24	64	…	…	24	44	…
318	16	2/16	24	56	28	48	24	…	…
319	29	4/29	26	48	64	24	72	…	24
320	16	2/16	24	…	…	…	…	…	…
321	16	2/16	24	72	24	64	24	…	24
322	23	3/23	25	32	…	…	64	24	44
323	16	2/16	24	64	…	…	24	24	44
324	16	2/16	24	64	…	…	32	24	44
325	16	2/16	24	64	…	…	40	24	44
326	16	2/16	24	32	…	…	24	24	44
327	16	2/16	24	32	…	…	28	24	44
328	41	5/41	23	…	…	…	…	…	…
329	16	2/16	24	64	24	24	72	…	24
330	33	4/33	23	…	…	…	…	…	…
331	16	2/16	24	64	44	24	48	…	24
332	16	2/16	24	32	…	…	48	24	44
333	18	2/18	21	24	…	…	72	44	…
334	16	2/16	24	32	…	…	56	24	44
335	33	4/33	23	72	48	44	40	…	24
336	16	2/16	24	32	…	…	64	24	44
337	43	5/43	21	86	40	32	56	…	…
338	16	2/16	24	32	…	…	72	24	44
339	18	2/18	21	24	…	…	56	44	…
340	17	2/17	22	…	…	…	…	…	…
341	43	5/43	21	86	24	32	40	…	…
342	18	2/18	21	32	…	…	64	44	…
343	15	2/15	25	40	64	24	86	…	24
344	43	5/43	21	…	…	…	…	…	…
345	18	2/18	21	24	…	…	40	56	…
346	18	2/18	21	72	56	32	64	…	…
347	43	5/43	21	86	24	32	40	…	24
348	18	2/18	21	24	…	…	32	56	…
349	18	2/18	21	72	44	24	48	…	…
350	18	2/18	21	72	40	32	64	…	…
351	18	2/18	21	24	…	…	24	56	…
352	18	2/18	21	72	24	24	64	…	…
353	18	2/18	21	72	24	24	56	…	…
354	18	2/18	21	72	…	…	48	24	…
355	18	2/18	21	72	…	…	40	24	…
356	18	2/18	21	72	…	…	32	24	…
357	18	2/18	21	72	…	…	24	44	…
358	18	2/18	21	72	32	48	24	…	…
359	43	5/43	21	86	48	32	100	…	24
360	18	2/18	21	…	…	…	…	…	…
361	19	2/19	19	32	…	…	64	44	…
362	18	2/18	21	72	28	56	32	…	24
363	18	2/18	21	72	…	…	24	24	44
364	18	2/18	21	72	…	…	32	24	44

[a] See *Note* on page 2011.

[b] On B & S numbers 1, 1½, and 2 machines, number 2 hole is in the machine table. On numbers 3 and 4 machines, number 2 hole is in the head.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Indexing Movements for Standard Index Plate Cincinnati Milling Machine

The standard index plate indexes all numbers up to and including 60; all even numbers and those divisible by 5 up to 120; and all divisions listed below up to 400. This plate is drilled on both sides, and has holes as follows:
First side: 24, 25, 28, 30, 34, 37, 38, 39, 41, 42, 43.
Second side: 46, 47, 49, 51, 53, 54, 57, 58, 59, 62, 66.

No. of Divisions	Index Plate Circle	No. of Turns	No. of Holes	No. of Divisions	Index Plate Circle	No. of Holes	No. of Divisions	Index Plate Circle	No. of Holes	No. of Divisions	Index Plate Circle	No. of Holes
2	Any	20	…	44	66	60	104	39	15	205	41	8
3	24	13	8	45	54	48	105	42	16	210	42	8
4	Any	10	…	46	46	40	106	53	20	212	53	10
5	Any	8	…	47	47	40	108	54	20	215	43	8
6	24	6	16	48	24	20	110	66	24	216	54	10
7	28	5	20	49	49	40	112	28	10	220	66	12
8	Any	5	…	50	25	20	114	57	20	224	28	5
9	54	4	24	51	51	40	115	46	16	228	57	10
10	Any	4	…	52	39	30	116	58	20	230	46	8
11	66	3	42	53	53	40	118	59	20	232	58	10
12	24	3	8	54	54	40	120	66	22	235	47	8
13	39	3	3	55	66	48	124	62	20	236	59	10
14	49	2	42	56	28	20	125	25	8	240	66	11
15	24	2	16	57	57	40	130	39	12	245	49	8
16	24	2	12	58	58	40	132	66	20	248	62	10
17	34	2	12	59	59	40	135	54	16	250	25	4
18	54	2	12	60	42	28	136	34	10	255	51	8
19	38	2	4	62	62	40	140	28	8	260	39	6
20	Any	2	…	64	24	15	144	54	15	264	66	10
21	42	1	38	65	39	24	145	58	16	270	54	8
22	66	1	54	66	66	40	148	37	10	272	34	5
23	46	1	34	68	34	20	150	30	8	280	28	4
24	24	1	16	70	28	16	152	38	10	290	58	8
25	25	1	15	72	54	30	155	62	16	296	37	5
26	39	1	21	74	37	20	156	39	10	300	30	4
27	54	1	26	75	30	16	160	28	7	304	38	5
28	42	1	18	76	38	20	164	41	10	310	62	8
29	58	1	22	78	39	20	165	66	16	312	39	5
30	24	1	8	80	34	17	168	42	10	320	24	3
31	62	1	18	82	41	20	170	34	8	328	41	5
32	28	1	7	84	42	20	172	43	10	330	66	8
33	66	1	14	85	34	16	176	66	15	336	42	5
34	34	1	6	86	43	20	180	54	12	340	34	4
35	28	1	4	88	66	30	184	46	10	344	43	5
36	54	1	6	90	54	24	185	37	8	360	54	6
37	37	1	3	92	46	20	188	47	10	368	46	5
38	38	1	2	94	47	20	190	38	8	370	37	4
39	39	1	1	95	38	16	192	24	5	376	47	5
40	Any	1	…	96	24	10	195	39	8	380	38	4
41	41	…	40	98	49	20	196	49	10	390	39	4
42	42	…	40	100	25	10	200	30	6	392	49	5
43	43	…	40	102	51	20	204	51	10	400	30	3

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6a. Indexing Movements for High Numbers Cincinnati Milling Machine

This set of 3 index plates indexes all numbers up to and including 200; all even numbers and those divisible by 5 up to and including 400. The plates are drilled on each side, making six sides *A*, *B*, *C*, *D*, *E* and *F*.

Example:—It is required to index 35 divisions. The preferred side is *F*, since this requires the least number of holes; but should one of plates *D*, *A* or *E* be in place, either can be used, thus avoiding the changing of plates.

No. of Divisions	Side	Circle	Turns	Holes	No. of Divisions	Side	Circle	Turns	Holes	No. of Divisions	Side	Circle	Turns	Holes
2	Any	Any	20	....	15	*C*	93	2	62	28	*D*	77	1	33
3	*A*	30	13	10	15	*F*	159	2	106	28	*A*	91	1	39
3	*B*	36	13	12	16	*E*	26	2	13	29	*E*	87	1	33
3	*E*	42	13	14	16	*F*	28	2	14	30	*A*	30	1	10
3	*C*	93	13	31	16	*A*	30	2	15	30	*B*	36	1	12
3	*F*	159	13	53	16	*D*	32	2	16	30	*E*	42	1	14
4	Any	Any	10	....	16	*C*	34	2	17	30	*C*	93	1	31
5	Any	Any	8	....	16	*B*	36	2	18	30	*F*	159	1	53
6	*A*	30	6	20	17	*C*	34	2	12	31	*C*	93	1	27
6	*B*	36	6	24	17	*E*	119	2	42	32	*F*	28	1	7
6	*E*	42	6	28	17	*C*	153	2	54	32	*D*	32	1	8
6	*C*	93	6	62	17	*F*	187	2	66	32	*B*	36	1	9
6	*F*	159	6	106	18	*B*	36	2	8	32	*A*	48	1	12
7	*F*	28	5	20	18	*A*	99	2	22	33	*A*	99	1	21
7	*E*	42	5	30	18	*C*	153	2	34	34	*C*	34	1	6
7	*D*	77	5	55	19	*F*	38	2	4	34	*E*	119	1	21
7	*A*	91	5	65	19	*E*	133	2	14	34	*F*	187	1	33
8	Any	Any	5	....	19	*A*	171	2	18	35	*F*	28	1	4
9	*B*	36	4	16	20	Any	Any	2	....	35	*D*	77	1	11
9	*A*	99	4	44	21	*E*	42	1	38	35	*A*	91	1	13
9	*C*	153	4	68	21	*A*	147	1	133	35	*E*	119	1	17
10	Any	Any	4	....	22	*D*	44	1	36	36	*B*	36	1	4
11	*D*	44	3	28	22	*A*	99	1	81	36	*A*	99	1	11
11	*A*	99	3	63	22	*F*	143	1	117	36	*C*	153	1	17
11	*F*	143	3	91	23	*C*	46	1	34	37	*B*	111	1	9
12	*A*	30	3	10	23	*A*	69	1	51	38	*F*	38	1	2
12	*B*	36	3	12	23	*E*	161	1	119	38	*E*	133	1	7
12	*E*	42	3	14	24	*A*	30	1	20	38	*A*	171	1	9
12	*C*	93	3	31	24	*B*	36	1	24	39	*A*	117	1	3
12	*F*	159	3	53	24	*E*	42	1	28	40	Any	Any	1	....
13	*E*	26	3	2	24	*C*	93	1	62	41	*C*	123	....	120
13	*A*	91	3	7	24	*F*	159	1	106	42	*E*	42	....	40
13	*F*	143	3	11	25	*A*	30	1	18	42	*A*	147	....	140
13	*B*	169	3	13	25	*E*	175	1	105	43	*A*	129	....	120
14	*F*	28	2	24	26	*F*	26	1	14	44	*D*	44	....	40
14	*E*	42	2	36	26	*A*	91	1	49	44	*A*	99	....	90
14	*D*	77	2	66	26	*B*	169	1	91	44	*F*	143	....	130
14	*A*	91	2	78	27	*B*	81	1	39	45	*B*	36	....	32
15	*A*	30	2	20	27	*A*	189	1	91	45	*A*	99	....	88
15	*B*	36	2	24	28	*F*	28	1	12	45	*C*	153	....	136
15	*E*	42	2	28	28	*E*	42	1	18	46	*C*	46	....	40

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6b. Indexing Movements for High Numbers
Cincinnati Milling Machine

No. of Division	Side	Circle	Holes	No. of Divisions	Side	Circle	Holes	No. of Division	Side	Circle	Holes
46	*A*	69	60	70	*E*	119	68	96	*B*	36	15
46	*E*	161	140	71	*F*	71	40	96	*A*	48	20
47	*B*	141	120	72	*B*	36	20	97	*B*	97	40
48	*A*	30	25	72	*A*	117	65	98	*A*	147	60
48	*B*	36	30	72	*C*	153	85	99	*A*	99	40
49	*A*	147	120	73	*E*	73	40	100	*A*	30	12
50	*A*	30	24	74	*B*	111	60	100	*E*	175	70
50	*E*	175	140	75	*A*	30	16	101	*F*	101	40
51	*C*	153	120	76	*F*	38	20	102	*C*	153	60
52	*E*	26	20	76	*E*	133	70	103	*E*	103	40
52	*A*	91	70	76	*A*	171	90	104	*E*	26	10
52	*F*	143	110	77	*D*	77	40	104	*A*	91	35
52	*B*	169	130	78	*A*	117	60	104	*F*	143	55
53	*F*	159	120	79	*C*	79	40	104	*B*	169	65
54	*B*	81	60	80	*E*	26	13	105	*E*	42	16
54	*A*	189	140	80	*F*	28	14	105	*A*	147	56
55	*D*	44	32	80	*A*	30	15	106	*F*	159	60
55	*F*	143	104	80	*D*	32	16	107	*D*	107	40
56	*F*	28	20	80	*C*	34	17	108	*B*	81	30
56	*E*	42	30	80	*B*	36	18	108	*A*	189	70
56	*D*	77	55	80	*E*	42	21	109	*C*	109	40
56	*A*	91	65	81	*B*	81	40	110	*D*	44	16
57	*A*	171	120	82	*C*	123	60	110	*A*	99	36
58	*E*	87	60	83	*F*	83	40	110	*F*	143	52
59	*A*	177	120	84	*E*	42	20	111	*B*	111	40
60	*A*	30	20	84	*A*	147	70	112	*F*	28	10
60	*B*	36	24	85	*C*	34	16	112	*E*	42	15
60	*E*	42	28	85	*E*	119	56	113	*F*	113	40
60	*F*	159	106	85	*F*	187	88	114	*A*	171	60
61	*B*	183	120	86	*A*	129	60	115	*C*	46	16
62	*C*	93	60	87	*E*	87	40	115	*A*	69	24
63	*A*	189	120	88	*D*	44	20	115	*E*	161	56
64	*D*	32	20	88	*A*	99	45	116	*E*	87	30
64	*A*	48	30	88	*F*	143	65	117	*A*	117	40
65	*E*	26	16	89	*D*	89	40	118	*A*	177	60
65	*A*	91	56	90	*B*	36	16	119	*E*	119	40
65	*F*	143	88	90	*A*	99	44	120	*A*	30	10
65	*B*	169	104	90	*C*	153	68	120	*B*	36	12
66	*A*	99	60	91	*A*	91	40	120	*E*	42	14
67	*B*	67	40	92	*C*	46	20	120	*C*	93	31
68	*C*	34	20	92	*A*	69	30	120	*F*	159	53
68	*E*	119	70	92	*E*	161	70	121	*D*	121	40
68	*F*	187	110	93	*C*	93	40	122	*B*	183	60
69	*A*	69	40	94	*B*	141	60	123	*C*	123	40
70	*F*	28	16	95	*F*	38	16	124	*C*	93	30
70	*D*	42	24	95	*E*	133	56	125	*E*	175	56
70	*A*	91	52	95	*A*	171	72	126	*A*	189	60
127	*B*	127	40	160	*A*	48	12	198	*A*	99	20
128	*D*	32	10	161	*E*	161	40	199	*B*	199	40
128	*A*	48	15	162	*B*	81	20	200	*A*	30	6
129	*A*	129	40	163	*D*	163	40	200	*E*	175	35
130	*E*	26	8	164	*C*	123	30	202	*F*	101	20
130	*A*	91	28	165	*A*	99	24	204	*C*	153	30
130	*F*	143	44	166	*F*	83	20	205	*C*	123	24
130	*B*	169	52	167	*C*	167	40	206	*E*	103	20
131	*F*	131	40	168	*E*	42	10	208	*E*	26	5
132	*A*	99	30	168	*A*	147	35	210	*E*	42	8
133	*E*	133	40	169	*B*	169	40	210	*A*	147	28
134	*B*	67	20	170	*C*	34	8	212	*F*	159	30
135	*B*	81	24	170	*E*	119	28	214	*D*	107	20
135	*A*	189	56	170	*F*	187	44	215	*A*	129	24
136	*C*	34	10	171	*A*	171	40	216	*B*	81	15
136	*E*	119	35	172	*A*	129	30	216	*A*	189	35

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6b. ***(Continued)*** **Indexing Movements for High Numbers Cincinnati Milling Machine**

No. of Division	Side	Circle	Holes	No. of Divisions	Side	Circle	Holes	No. of Division	Side	Circle	Holes
137	*D*	137	40	173	*F*	173	40	218	*C*	109	20
138	*A*	69	20	174	*E*	87	20	220	*D*	44	8
139	*C*	139	40	175	*E*	175	40	220	*A*	99	18
140	*F*	28	8	176	*D*	44	10	220	*F*	143	26
140	*E*	42	12	177	*A*	177	40	222	*B*	111	20
140	*D*	77	22	178	*D*	89	20	224	*F*	28	5
140	*A*	91	26	179	*D*	179	40	226	*F*	113	20
141	*B*	141	40	180	*B*	36	8	228	*A*	171	30
142	*F*	71	20	180	*A*	99	22	230	*C*	46	8
143	*F*	143	40	180	*C*	153	34	230	*A*	69	12
144	*B*	36	10	181	*C*	181	40	230	*E*	161	28
145	*E*	87	24	182	*A*	91	20	232	*E*	87	15
146	*E*	73	20	183	*B*	183	40	234	*A*	117	20
147	*A*	147	40	184	*C*	46	10	235	*B*	141	24
148	*B*	111	30	184	*A*	69	15	236	*A*	177	30
149	*E*	149	40	184	*E*	161	35	238	*E*	119	20
150	*A*	30	8	185	*B*	111	24	240	*A*	30	5
151	*D*	151	40	186	*C*	93	20	240	*B*	36	6
152	*F*	38	10	187	*F*	187	40	240	*E*	42	7
152	*E*	133	35	188	*B*	141	30	240	*A*	48	8
152	*A*	171	45	189	*A*	189	40	242	*D*	121	20
153	*C*	153	40	190	*F*	38	8	244	*B*	183	30
154	*D*	77	20	190	*E*	133	28	245	*A*	147	24
155	*C*	93	24	190	*A*	171	36	246	*C*	123	20
156	*A*	117	30	191	*E*	191	40	248	*C*	93	15
157	*B*	157	40	192	*A*	48	10	250	*E*	175	28
158	*C*	79	20	193	*D*	193	40	252	*A*	189	30
159	*F*	159	40	194	*B*	97	20	254	*B*	127	20
160	*F*	28	7	195	*A*	117	24	255	*C*	153	24
160	*D*	32	8	196	*A*	147	30	256	*D*	32	5
160	*B*	36	9	197	*C*	197	40	258	*A*	129	20
260	*E*	26	4	304	*F*	38	5	354	*A*	177	20
260	*A*	91	14	305	*B*	183	24	355	*F*	71	8
260	*F*	143	22	306	*C*	153	20	356	*D*	89	10
260	*B*	169	26	308	*D*	77	10	358	*D*	179	20
262	*F*	131	20	310	*C*	93	12	360	*B*	36	4
264	*A*	99	15	312	*A*	117	15	360	*A*	99	11
265	*F*	159	24	314	*B*	157	20	360	*C*	153	17
266	*E*	133	20	315	*A*	189	24	362	*C*	181	20
268	*B*	67	10	316	*C*	79	10	364	*A*	91	10
270	*B*	81	12	318	*F*	159	20	365	*E*	73	8
270	*A*	189	28	320	*D*	32	4	366	*B*	183	20
272	*C*	34	5	320	*A*	48	6	368	*C*	46	5
274	*D*	137	20	322	*E*	161	20	370	*B*	111	12
276	*A*	69	10	324	*B*	81	10	372	*C*	93	10
278	*C*	139	20	326	*D*	163	20	374	*F*	187	20
280	*F*	28	4	328	*C*	123	15	376	*B*	141	15
280	*E*	42	6	330	*A*	99	12	378	*A*	189	20
280	*D*	77	11	332	*F*	83	10	380	*F*	38	4
280	*A*	91	13	334	*C*	167	20	380	*E*	133	14
282	*B*	141	20	335	*B*	67	8	380	*A*	171	18
284	*F*	71	10	336	*E*	42	5	382	*E*	191	20
285	*A*	171	24	338	*B*	169	20	384	*A*	48	5
286	*F*	143	20	340	*C*	34	4	385	*D*	77	8
288	*B*	36	5	340	*E*	119	14	386	*D*	193	20
290	*E*	87	12	340	*F*	187	22	388	*B*	97	10
292	*E*	73	10	342	*A*	171	20	390	*A*	117	12
294	*A*	147	20	344	*A*	129	15	392	*A*	147	15
295	*A*	177	24	345	*A*	69	8	394	*C*	197	20
296	*B*	111	15	346	*F*	173	20	395	*C*	79	8
298	*E*	149	20	348	*E*	87	10	396	*A*	99	10
300	*A*	30	4	350	*E*	175	20	398	*B*	199	20
302	*D*	151	20	352	*D*	44	5	400	*A*	30	3

Copyright 2004, Industrial Press, Inc., New York, NY

Indexing Tables.— Indexing tables are usually circular, with a flat, T-slotted table, 12 to 24 in. in diameter, to which workpieces can be clamped. The flat table surface may be horizontal, universal, or angularly adjustable. The table can be turned continuously through 360° about an axis normal to the surface. Rotation is through a worm drive with a graduated scale, and a means of angular readout is provided. Indexed locations to 0.25° with accuracy of ±0.1 second can be obtained from mechanical means, or greater accuracy from an autocollimator or sine-angle attachment built into the base, or under numerical control. Provision is made for locking the table at any angular position while a machining operation is being performed.

Power for rotation of the table during machining can be transmitted, as with a dividing head, for cutting a continuous, spiral scroll, for instance. The indexing table is usually more rigid and can be used with larger workpieces than the dividing head.

Block or Multiple Indexing for Gear Cutting.— With the block system of indexing, numbers of teeth are indexed at one time, instead of cutting the teeth consecutively, and the gear is revolved several times before all the teeth are finished. For example, when cutting a gear having 25 teeth, the indexing mechanism is geared to index four teeth at once (see Table 7) and the first time around, six widely separated tooth spaces are cut. The second time around, the cutter is one tooth behind the spaces originally milled. On the third indexing, the cutter has dropped back another tooth, and the gear in question is thus finished by indexing it through four cycles.

The various combinations of change gears to use for block or multiple indexing are given in the accompanying Table 7. The advantage claimed for block indexing is that the heat generated by the cutter (especially when cutting cast iron gears of coarse pitch) is distributed more evenly about the rim and is dissipated to a greater extent, thus avoiding distortion due to local heating and permitting higher speeds and feeds to be used.

Table 7 gives values for use with Brown & Sharpe automatic gear cutting machines, but the gears for any other machine equipped with a similar indexing mechanism can be calculated easily. Assume, for example, that a gear cutter requires the following change gears for indexing a certain number of teeth: driving gears having 20 and 30 teeth, respectively, and driven gears having 50 and 60 teeth.

Then if it is desired to cut, for instance, every fifth tooth, multiply the fractions 20/60 and 30/50 by 5. Then 20/60 × 30/50 × 5/1 = 1/1. In this instance, the blank could be divided so that every fifth space was cut, by using gears of equal size. The number of teeth in the gear and the number of teeth indexed in each block must not have a common factor.

Table 7. Block or Multiple Indexing for Gear Cutting

Number of Teeth to be Cut	Number Indexed at Once	1st Driver	1st Follower	2nd Driver	2nd Follower	Turns of Locking Disk	Number of Teeth to be Cut	Number Indexed at Once	1st Driver	1st Follower	2nd Driver	2nd Follower	Turns of Locking Disk
25	4	100	50	72	30	4	36	5	100	48	80	40	4
26	3	100	50	90	52	4	37	5	100	30	90	74	4
27	2	100	50	60	54	4	38	5	100	30	90	76	4
28	3	100	50	90	56	4	39	5	100	30	90	78	4
29	3	100	50	90	58	4	40	3	100	50	90	80	4
30	7	100	30	84	40	4	41	5	100	30	90	82	4
31	3	100	50	90	62	4	42	5	100	30	90	84	4
32	3	100	50	90	64	4	43	5	100	30	90	86	4
33	4	100	50	80	44	4	44	5	100	30	90	88	4
34	3	100	50	90	68	4	45	7	100	50	70	30	4
35	4	100	50	96	56	4	46	5	100	30	90	92	4

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. ***(Continued)*** **Block or Multiple Indexing for Gear Cutting**

Number of Teeth to be Cut	Number Indexed at Once	1st Driver	1st Follower	2nd Driver	2nd Follower	Turns of Locking Disk	Number of Teeth to be Cut	Number Indexed at Once	1st Driver	1st Follower	2nd Driver	2nd Follower	Turns of Locking Disk
47	5	100	30	90	94	4	119	3	100	70	72	68	2
48	5	100	30	90	96	4	120	7	100	50	70	40	2
49	5	100	30	90	98	4	121	4	60	66	96	44	2
50	7	100	50	84	40	4	123	7	100	30	84	82	2
51	4	100	30	96	68	2	124	5	100	60	90	62	2
52	5	100	30	90	52	2	125	7	100	50	84	50	2
54	5	100	30	90	54	2	126	5	100	50	50	42	2
55	4	100	50	96	44	2	128	5	100	60	90	64	2
56	5	100	30	90	56	2	129	7	100	30	84	86	2
57	4	100	30	96	76	2	130	7	100	50	84	52	2
58	5	100	30	90	58	2	132	5	100	88	80	40	2
60	7	100	30	84	40	2	133	4	100	70	96	76	2
62	5	100	30	90	62	2	134	5	100	60	90	67	2
63	5	100	30	80	56	2	135	7	100	50	84	54	2
64	5	100	30	90	64	2	136	5	100	60	90	68	2
65	4	100	50	96	52	2	138	5	100	92	80	40	2
66	5	100	44	80	40	2	140	3	50	50	90	70	2
67	5	100	30	90	67	2	141	5	100	94	80	40	2
68	5	100	30	90	68	2	143	6	90	66	96	52	2
69	5	100	46	80	40	2	144	5	100	60	90	72	2
70	3	100	50	90	70	2	145	6	100	50	72	58	2
72	5	100	30	90	72	2	147	5	100	98	80	40	2
74	5	100	30	90	74	2	148	5	100	60	90	74	2
75	7	100	30	84	50	2	150	7	100	60	84	50	2
76	5	100	30	90	76	2	152	5	100	60	90	76	2
77	4	100	70	96	44	2	153	5	100	68	80	60	2
78	5	100	30	90	78	2	154	5	100	56	72	66	2
80	3	100	50	90	80	2	155	6	100	50	72	62	2
81	7	100	30	84	52	2	156	5	100	60	90	78	2
82	5	100	30	90	82	2	160	7	100	50	84	64	2
84	5	100	30	90	84	2	161	5	100	70	60	46	2
85	4	100	50	96	68	2	162	7	100	60	84	52	2
86	5	100	30	90	86	2	164	5	100	60	90	82	2
87	7	100	30	84	58	2	165	7	100	50	84	66	2
88	5	100	30	90	88	2	168	5	100	60	90	84	2
90	7	100	30	70	50	2	169	6	96	52	90	78	2
91	3	100	70	72	52	2	170	7	100	50	84	68	2
92	5	100	30	90	92	2	171	5	70	42	80	76	2
93	7	100	30	84	62	2	172	5	100	60	90	86	2
94	5	100	30	90	94	2	174	7	100	60	84	58	2
95	4	100	50	96	76	2	175	8	100	50	96	70	2
96	5	100	30	90	96	2	176	5	100	60	90	88	2
98	5	100	30	90	98	2	180	7	100	60	70	50	2
99	10	100	30	80	44	2	182	9	90	56	96	52	2
100	7	100	50	84	40	2	184	5	100	60	90	92	2
102	5	100	30	60	68	2	185	6	100	50	72	74	2
104	5	100	60	90	52	2	186	7	100	60	84	62	2
105	4	100	70	96	60	2	187	5	100	44	48	68	2
108	7	100	30	70	60	2	188	5	100	60	90	94	2
110	7	100	50	84	44	2	189	5	100	60	80	84	2
111	5	100	74	80	40	2	190	7	100	50	84	76	2
112	5	100	60	90	56	2	192	5	100	60	90	96	2
114	7	100	30	84	76	2	195	7	100	50	84	78	2
115	8	100	50	96	46	2	196	5	100	60	90	98	2
116	5	100	60	90	58	2	198	7	100	50	70	66	2
117	8	100	30	96	78	2	200	7	60	60	84	40	2

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Indexing Movements for 60-Tooth Worm-Wheel Dividing Head

Divisions	Index Circle	No. of Turns	No. of Holes	Divisions	Index Circle	No. of Turns	No. of Holes	Divisions	Index Circle	No. of Holes	Divisions	Index Circle	No. of Holes
2	Any	30	..	50	60	1	12	98	49	30	146	73	30
3	Any	20	..	51	17	1	3	99	33	20	147	49	20
4	Any	15	..	52	26	1	4	100	60	36	148	37	15
5	Any	12	..	53	53	1	7	101	101	60	149	149	60
6	Any	10	..	54	27	1	3	102	17	10	150	60	24
7	21	8	12	55	33	1	3	103	103	60	151	151	60
8	26	7	13	56	28	1	2	104	26	15	152	76	30
9	21	6	14	57	19	1	1	105	21	12	153	51	20
10	Any	6	..	58	29	1	1	106	53	30	154	77	30
11	33	5	15	59	59	1	1	107	107	60	155	31	12
12	Any	5	..	60	Any	1	..	108	27	15	156	26	10
13	26	4	16	61	61	..	60	109	109	60	157	157	60
14	21	4	6	62	31	..	30	110	33	18	158	79	30
15	Any	4	..	63	21	..	20	111	37	20	159	53	20
16	28	3	21	64	32	..	30	112	28	15	160	32	12
17	17	3	9	65	26	..	24	113	113	60	161	161	60
18	21	3	7	66	33	..	30	114	19	10	162	27	10
19	19	3	3	67	67	..	60	115	23	12	163	163	60
20	Any	3	..	68	17	..	15	116	29	15	164	41	15
21	21	2	18	69	23	..	20	117	39	20	165	33	12
22	33	2	24	70	21	..	18	118	59	30	166	83	30
23	23	2	14	71	71	..	60	119	119	60	167	167	60
24	26	2	13	72	60	..	50	120	26	13	168	28	10
25	60	2	24	73	73	..	60	121	121	60	169	169	60
26	26	2	8	74	37	..	30	122	61	30	170	17	6
27	27	2	6	75	60	..	48	123	41	20	171	57	20
28	21	2	3	76	19	..	15	124	31	15	172	43	15
29	29	2	2	77	77	..	60	125	100	48	173	173	60
30	Any	2	..	78	26	..	20	126	21	10	174	29	10
31	31	1	29	79	79	..	60	127	127	60	175	35	12
32	32	1	28	80	28	..	21	128	32	15	176	44	15
33	33	1	27	81	27	..	20	129	43	20	177	59	20
34	17	1	13	82	41	..	30	130	26	12	178	89	30
35	21	1	15	83	83	..	60	131	131	60	179	179	60
36	21	1	14	84	21	..	15	132	33	15	180	21	7
37	37	1	23	85	17	..	12	133	133	60	181	181	60
38	19	1	11	86	43	..	30	134	67	30	182	91	30
39	26	1	14	87	29	..	20	135	27	12	183	61	20
40	26	1	13	88	44	..	30	136	68	30	184	46	15
41	41	1	19	89	89	..	60	137	137	60	185	37	12
42	21	1	9	90	21	..	14	138	23	10	186	31	10
43	43	1	17	91	91	..	60	139	139	60	187	187	60
44	33	1	12	92	23	..	15	140	21	9	188	47	15
45	21	1	7	93	31	..	20	141	47	20	189	63	20
46	23	1	7	94	47	..	30	142	71	30	190	19	6
47	47	1	13	95	19	..	12	143	143	60	191	191	60
48	28	1	7	96	32	..	20	144	60	25	192	32	10
49	49	1	11	97	97	..	60	145	29	12	193	193	60

Copyright 2004, Industrial Press, Inc., New York, NY

Linear Indexing for Rack Cutting.— When racks are cut on a milling machine, two general methods of linear indexing are used. One is by using the graduated dial on the feed-screw and the other is by using an indexing attachment. The accompanying Table 9 shows the indexing movements when the first method is employed. This table applies to milling machines having feed-screws with the usual lead of ¼ inch and 250 dial graduations each equivalent to 0.001 inch of table movement.

$$\text{Actual rotation of feed-screw} = \frac{\text{Linear pitch of rack}}{\text{Lead of feed-screw}}$$

Multiply *decimal* part of turn (obtained by above formula) by 250, to obtain dial reading for fractional part of indexing movement, assuming that dial has 250 graduations.

Table 9. Linear Indexing Movements for Cutting Rack Teeth on a Milling Machine

Pitch of Rack Teeth		Indexing, Movement		Pitch of Rack Teeth		Indexing, Movement	
Diametral Pitch	Linear or Circular	No. of Whole Turns	No. of 0.001 Inch Divisions	Diametral Pitch	Linear or Circular	No. of Whole Turns	No. of 0.001 Inch Divisions
2	1.5708	6	70.8	12	0.2618	1	11.8
2¼	1.3963	5	146.3	13	0.2417	0	241.7
2½	1.2566	5	6.6	14	0.2244	0	224.4
2¾	1.1424	4	142.4	15	0.2094	0	208.4
3	1.0472	4	47.2	16	0.1963	0	196.3
3½	0.8976	3	147.6	17	0.1848	0	184.8
4	0.7854	3	35.4	18	0.1745	0	174.8
5	0.6283	2	128.3	19	0.1653	0	165.3
6	0.5263	2	23.6	20	0.1571	0	157.1
7	0.4488	1	198.8	22	0.1428	0	142.8
8	0.3927	1	142.7	24	0.1309	0	130.9
9	0.3491	1	99.1	26	0.1208	0	120.8
10	0.3142	1	64.2	28	0.1122	0	112.2
11	0.2856	1	35.6	30	0.1047	0	104.7

These movements are for table feed-screws having the usual lead of ¼ inch

Note: The linear pitch of the rack equals the circular pitch of gear or pinion which is to mesh with the rack. The table gives both standard diametral pitches and their equivalent linear or circular pitches.

Example: Find indexing movement for cutting rack to mesh with a pinion of 10 diametral pitch.

Indexing movement equals 1 whole turn of feed-screw plus 64.2 thousandths or divisions on feed-screw dial. The feed-screw may be turned this fractional amount by setting dial back to its zero position for each indexing (without backward movement of feed-screw), or, if preferred, 64.2 (in this example) may be added to each successive dial position as shown below.

Dial reading for second position = 64.2 × 2 = 128.4 (complete movement = 1 turn × 64.2 additional divisions by turning feed-screw until dial reading is 128.4).

Third dial position = 64.2 × 3 = 192.6 (complete movement = 1 turn + 64.2 additional divisions by turning until dial reading is 192.6).

Fourth position = 64.2 × 4 – 250 = 6.8 (1 turn + 64.2 additional divisions by turning feed-screw until dial reading is 6.8 divisions past the zero mark); or, to simplify operation, set dial back to zero for fourth indexing (without moving feed-screw) and then repeat settings for the three previous indexings or whatever number can be made before making a complete turn of the dial.

Copyright 2004, Industrial Press, Inc., New York, NY

Counter Milling.— Changing the direction of a linear milling operation by a specific angle requires a linear offset before changing the angle of cut. This compensates for the radius of the milling cutters, as illustrated in Figs. 1a and 1b.



Fig. 1a. Inside Milling



Fig. 1b. Outside Milling

For inside cuts the offset is subtracted from the point at which the cutting direction changes (Fig. 1a), and for outside cuts the offset is added to the point at which the cutting direction changes (Fig. 1b). The formula for the offset is

$$x = rM$$

where x = offset distance; r = radius of the milling cutter; and, M = the multiplication factor ($M = \tan \theta/2$). The value of M for certain angles can be found in Table 10.

Table 10. Offset Multiplication Factors

Deg°	*M*	Deg°	*M*	Deg°	*M*	Deg°	*M*	Deg°	*M*
1°	0.00873	19°	0.16734	37°	0.33460	55°	0.52057	73°	0.73996
2°	0.01746	20°	0.17633	38°	0.34433	56°	0.53171	74°	0.75355
3°	0.02619	21°	0.18534	39°	0.35412	57°	0.54296	75°	0.76733
4°	0.03492	22°	0.19438	40°	0.36397	58°	0.55431	76°	0.78129
5°	0.04366	23°	0.20345	41°	0.37388	59°	0.56577	77°	0.79544
6°	0.05241	24°	0.21256	42°	0.38386	60°	0.57735	78°	0.80978
7°	0.06116	25°	0.22169	43°	0.39391	61°	0.58905	79°	0.82434
8°	0.06993	26°	0.23087	44°	0.40403	62°	0.60086	80°	0.83910
9°	0.07870	27°	0.24008	45°	0.41421	63°	0.61280	81°	0.85408
10°	0.08749	28°	0.24933	46°	0.42447	64°	0.62487	82°	0.86929
11°	0.09629	29°	0.25862	47°	0.43481	65°	0.63707	83°	0.88473
12°	0.10510	30°	0.26795	48°	0.44523	66°	0.64941	84°	0.90040
13°	0.11394	31°	0.27732	49°	0.45573	67°	0.66189	85°	0.91633
14°	0.12278	32°	0.28675	50°	0.46631	68°	0.67451	86°	0.93252
15°	0.13165	33°	0.29621	51°	0.47698	69°	0.68728	87°	0.94896
16°	0.14054	34°	0.30573	52°	0.48773	70°	0.70021	88°	0.96569
17°	0.14945	35°	0.31530	53°	0.49858	71°	0.71329	89°	0.98270
18°	0.15838	36°	0.32492	54°	0.50953	72°	0.72654	90°	1.00000

Multiply factor M by the tool radius r to determine the offset dimension

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

GEARS, SPLINES, AND CAMS

GEARS AND GEARING

2029 Definitions of Gear Terms
2033 Sizes and Shape of Gear Teeth
2033 Nomenclature of Gear Teeth
2033 Properties of the Involute Curve
2034 Diametral and Circular Pitch Systems
2035 Formulas for Spur Gear
2036 Gear Tooth Forms and Parts
2038 Gear Tooth Parts
2039 Tooth Proportions
2040 Fine Pitch Tooth Parts
2040 American Spur Gear Standards
2041 Formulas for Tooth Parts
2041 Fellows Stub Tooth
2041 Basic Gear Dimensions
2042 Formulas for Outside and Root Diameters
2045 Tooth Thickness Allowance
2045 Circular Pitch for Given Center Distance
2045 Circular Thickness of Tooth
2049 Chordal Addendum
2050 Addendums and Tooth Thicknesses
2050 Enlarged Pinion
2051 Caliper Measurement of Gear Tooth
2052 Involute Gear Milling Cutter
2052 Circular Pitch in Gears
2052 Increasing Pinion Diameter
2054 Finishing Gear Milling Cutters
2055 Increase in Dedendum
2055 Dimensions Required
2056 Tooth Proportions for Pinions
2058 Minimum Number of Teeth
2058 Gear to Mesh with Enlarged Pinion
2058 Standard Center-distance
2058 Enlarged Center-distance
2059 Contact Diameter
2060 Contact Ratio
2060 Lowest Point of Single Tooth Contact
2061 Maximum Hob Tip Radius
2061 Undercut Limit
2061 Highest Point of Single Tooth Contact
2061 True Involute Form Diameter
2062 Profile Checker Settings

GEARS AND GEARING

(Continued)

2064 Gear Blanks
2065 Spur and Helical Gear Data
2067 Backlash
2067 Determining Amount of Backlash
2068 Helical and Herringbone Gearing
2069 Bevel and Hypoid Gears
2070 Providing Backlash
2070 Excess Depth of Cut
2070 Control of Backlash Allowances
2071 Measurement of Backlash
2072 Control of Backlash
2072 Allowance and Tolerance
2073 Angular Backlash in Gears
2073 Inspection of Gears
2073 Pressure for Fine-Pitch Gears
2074 Internal Gearing
2074 Internal Spur Gears
2074 Methods of Cutting Internal Gears
2074 Formed Cutters for Internal Gears
2074 Arc Thickness of Gear Tooth
2074 Arc Thickness of Pinion Tooth
2074 Relative Sizes of Internal Gear
2075 Rules for Internal Gears
2076 British Standard for Spur and Helical Gears
2077 Addendum Modification

HYPOID AND BEVEL GEARING

2080 Hypoid Gears
2081 Bevel Gearing
2081 Types of Bevel Gears
2083 Applications of Bevel and Hypoid Gears
2083 Design of Bevel Gear Blanks
2084 Mountings for Bevel Gears
2084 Cutting Bevel Gear Teeth
2085 Nomenclature for Bevel Gears
2085 Formulas for Dimensions
2089 Numbers of Formed Cutters
2091 Selecting Formed Cutters
2092 Offset of Cutter
2093 Adjusting the Gear Blank
2094 Steels Used for Bevel Gear
2095 Circular Thickness, Chordal Thickness

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

GEARS, SPLINES, AND CAMS

WORM GEARING

2095 Standard Design for Fine-pitch
2096 Formulas for Wormgears
2098 Materials for Worm Gearing
2098 Single-thread Worms
2098 Multi-thread Worms

HELICAL GEARING

2099 Helical Gear Calculations
2099 Rules and Formulas
2099 Determining Direction of Thrust
2100 Determining Helix Angles
2100 Pitch of Cutter to be Used
2103 Shafts at Right Angles, Center Distance approx
2104 Shafts at Right Angles, Center Distance Exact
2107 Shafts at Any Angle, Center Distance Exact
2108 Selecting Cutter for Milling Helical Gears
2109 Factors for Selecting Cutters
2109 Outside and Pitch Diameters
2109 Milling the Helical Teeth
2110 Fine-Pitch Helical Gears
2111 Center Distance with no Backlash
2112 Change-gears for Hobbing
2114 Helical Gear Hobbing

OTHER GEAR TYPES

2114 Herringbone Gears
2114 General Classes of Problems
2114 Causes of Failures
2114 Elliptic Gears
2115 Planetary Gearing
2115 Direction of Rotation
2115 Compound Drive
2115 Planetary Bevel Gears
2116 Ratios of Epicyclic Gearing
2119 Ratchet Gearing
2119 Types of Ratchet Gearing
2120 Shape of Ratchet Wheel Teeth
2120 Pitch of Ratchet Wheel Teeth
2121 Module System Gear Design
2121 German Standard Tooth Form
2122 Tooth Dimensions
2123 Rules for Module System
2124 Equivalent Diametral Pitches, Circular Pitches

CHECKING GEAR SIZES

2125 Checking Externall Spur Gear Sizes
2126 Measurement Over Wires
2130 Checking Internal Spur Gear
2139 Measurements for Checking Helical Gears using Wires
2140 Checking Spur Gear Size
2142 Formula for Chordal Dimension

GEAR MATERIALS

2144 Gearing Material
2144 Classification of Gear Steels
2144 Use of Casehardening Steels
2144 Use of “Thru-Hardening” Steels
2144 Heat-Treatment for Machining
2145 Making Pinion Harder
2145 Forged and Rolled Carbon Steels
2145 Compositions
2145 Forged and Rolled Alloy Steels
2146 Compositions
2146 Steel Castings for Gears
2146 Compositions
2146 Effect of Alloying Metals
2147 Sintered Materials
2147 Steels for Industrial Gearing
2147 Bronze and Brass Gear Castings
2149 Materials for Worm Gearing
2150 Non-metallic Gears
2150 Power-Transmitting Capacity
2150 Safe Working Stresses
2151 Preferred Pitch
2151 Bore Sizes
2151 Preferred Pitches
2151 Keyway Stresses
2152 Invention of Gear Teeth
2153 Calculating Replacement
2153 Spur Gears
2155 Helical Gears

SPLINES AND SERRATIONS

2156 Involute Splines
2156 American National Standard
2157 Terms
2158 Types of involute spline
2160 Tooth Proportions
2160 Symbols
2161 Formulas for Basic Dimensions
2162 Basic Dimensions
2162 Tooth Numbers

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

GEARS, SPLINES, AND CAMS

SPLINES AND SERRATIONS

(Continued)
2162 Types and Classes of Fits
2162 Classes of Tolerances
2163 Maximum Tolerances
2164 Fillets and Chamfers
2165 Spline Variations
2165 Effect of Spline Variations
2165 Effective and Actual Dimensions
2166 Space Width and Tooth Thickness Limits
2166 Effective and Actual Dimensions
2167 Combinations of Spline Types
2167 Interchangeability
2167 Drawing Data
2169 Spline Data and Reference Dimensions
2169 Estimating Key and Spline Sizes
2170 Formulas for Torque Capacity
2171 Spline Application Factors
2171 Load Distribution Factors
2172 Fatigue-Life Factors
2172 Wear Life Factors
2172 Allowable Shear Stresses
2173 Crowned Splines for Large Misalignments
2174 Fretting Damage to Splines
2174 Inspection Methods
2175 Inspection with Gages
2175 Measurements with Pins
2176 Metric Module Splines
2177 Comparison of Symbols
2177 Formulas for Dimensions and Tolerances
2180 Tooth Thickness Modification
2180 Machining Tolerances
2180 Tooth Thickness Total Tolerance
2181 Selected Fit Classes Data
2182 Straight Splines
2182 British Standard Striaght Splines
2183 Splines Fittings
2184 Standard Splined Fittings
2185 Dimensions of Standard Splines
2186 Polygon-type Shaft Connections

CAMS AND CAM DESIGN

2188 Classes of Cams
2188 Cam Follower Systems
2189 Displacement Diagrams
2194 Cam Profile Determination
2195 Modified Constant Velocity Cam
2197 Pressure Angle and Radius of Curvature
2198 Cam Size for a Radial Follower
2200 Cam Size for Swinging Roller Follower
2201 Formulas for Calculating Pressure Angles
2203 Radius of Curvature
2205 Cam Forces, Contact Stresses, and Materials
2210 Calculation of Contact Stresses
2211 Layout of Cylinder Cams
2211 Shape of Rolls for Cylinder Cams
2212 Cam Milling
2213 Cutting Uniform Motion Cams

Copyright 2004, Industrial Press, Inc., New York, NY

GEARS AND GEARING

External spur gears are cylindrical gears with straight teeth cut parallel to the axes. Gears transmit drive between parallel shafts. Tooth loads produce no axial thrust. Excellent at moderate speeds but tend to be noisy at high speeds. Shafts rotate in opposite directions.

Internal spur gears provide compact drive arrangements for transmitting motion between parallel shafts rotating in the same direction.

Helical gears are cylindrical gears with teeth cut at an angle to the axes. Provides drive between shafts rotating in opposite directions, with superior load carrying capacity and quietness than spur gears. Tooth loads produce axial thrust.

Crossed helical gears are helical gears that mesh together on non-parallel axes.

Straight bevel gears have teeth that are radial toward the apex and are of conical form. Designed to operate on intersecting axes, bevel gears are used to connect two shafts on intersecting axes. The angle between the shafts equals the angle between the two axes of the meshing teeth. End thrust developed under load tends to separate the gears.

Spiral bevel gears have curved oblique teeth that contact each other smoothly and gradually from one end of a tooth to the other. Meshing is similar to that of straight bevel gears but is smoother and quieter in use. Left hand spiral teeth incline away from the axis in an anti-clockwise direction looking on small end of pinion or face of gear, right-hand teeth incline away from axis in clockwise direction. The hand of spiral of the pinion is always opposite to that of the gear and is used to identify the hand of the gear pair. Used to connect two shafts on intersecting axes as with straight bevel gears. The spiral angle does not affect the smoothness and quietness of operation or the efficiency but does affect the direction of the thrust loads created. A left-hand spiral pinion driving clockwise when viewed from the large end of the pinion creates an axial thrust that tends to move the pinion out of mesh.

Zerol bevel gears have curved teeth lying in the same general direction as straight bevel teeth but should be considered to be spiral bevel gears with zero spiral angle.

Hypoid bevel gears are a cross between spiral bevel gears and worm gears. The axes of hypoid bevel gears are non-intersecting and non-parallel. The distance between the axes is called the offset. The offset permits higher ratios of reduction than is practicable with other bevel gears. Hypoid bevel gears have curved oblique teeth on which contact begins gradually and continues smoothly from one end of the tooth to the other.

Worm gears are used to transmit motion between shafts at right angles, that do not lie in a common plane and sometimes to connect shafts at other angles. Worm gears have line tooth contact and are used for power transmission, but the higher the ratio the lower the efficiency.

Definitions of Gear Terms.— The following terms are commonly applied to the various classes of gears:

Active face width is the dimension of the tooth face width that makes contact with a mating gear.

Addendum is the radial or perpendicular distance between the pitch circle and the top of the tooth.

Arc of action is the arc of the pitch circle through which a tooth travels from the first point of contact with the mating tooth to the point where contact ceases.

Arc of approach is the arc of the pitch circle through which a tooth travels from the first point of contact with the mating tooth to the pitch point.

Arc of recession is the arc of the pitch circle through which a tooth travels from its contact with a mating tooth at the pitch point until contact ceases.

Axial pitch is the distance parallel to the axis between corresponding sides of adjacent teeth.

Axial plane is the plane that contains the two axes in a pair of gears. In a single gear the axial plane is any plane containing the axis and any given point.

Copyright 2004, Industrial Press, Inc., New York, NY

Axial thickness is the distance parallel to the axis between two pitch line elements of the same tooth.

Backlash is the shortest distance between the non-driving surfaces of adjacent teeth when the working flanks are in contact.

Base circle is the circle from which the involute tooth curve is generated or developed.

Base helix angle is the angle at the base cylinder of an involute gear that the tooth makes with the gear axis.

Base pitch is the circular pitch taken on the circumference of the base circles, or the distance along the line of action between two successive and corresponding involute tooth profiles. The *normal base pitch* is the base pitch in the normal plane and the *axial base pitch* is the base pitch in the axial plane.

Base tooth thickness is the distance on the base circle in the plane of rotation between involutes of the same pitch.

Bottom land is the surface of the gear between the flanks of adjacent teeth.

Center distance is the shortest distance between the non-intersecting axes of mating gears, or between the parallel axes of spur gears and parallel helical gears, or the crossed axes of crossed helical gears or worm gears.

Central plane is the plane perpendicular to the gear axis in a worm gear, which contains the common perpendicular of the gear and the worm axes. In the usual arrangement with the axes at right angles, it contains the worm axis.

Chordal addendum is the radial distance from the circular thickness chord to the top of the tooth, or the height from the top of the tooth to the chord subtending the circular thickness arc.

Chordal thickness is the length of the chord subtended by the circular thickness arc. The dimension obtained when a gear tooth caliper is used to measure the tooth thickness at the pitch circle.

Circular pitch is the distance on the circumference of the pitch circle, in the plane of rotation, between corresponding points of adjacent teeth. The length of the arc of the pitch circle between the centers or other corresponding points of adjacent teeth.

Circular thickness is the thickness of the tooth on the pitch circle in the plane of rotation, or the length of arc between the two sides of a gear tooth measured on the pitch circle.

Clearance is the radial distance between the top of a tooth and the bottom of a mating tooth space, or the amount by which the dedendum in a given gear exceeds the addendum of its mating gear.

Contact diameter is the smallest diameter on a gear tooth with which the mating gear makes contact.

Contact ratio is the ratio of the arc of action in the plane of rotation to the circular pitch, and is sometimes thought of as the average number of teeth in contact. This ratio is obtained most directly as the ratio of the length of action to the base pitch.

Contact ratio – face is the ratio of the face advance to the circular pitch in helical gears.

Contact ratio – total is the ratio of the sum of the arc of action and the face advance to the circular pitch.

Contact stress is the maximum compressive stress within the contact area between mating gear tooth profiles. Also called the Hertz stress.

Cycloid is the curve formed by the path of a point on a circle as it rolls along a straight line. When such a circle rolls along the outside of another circle the curve is called an *epicycloid*, and when it rolls along the inside of another circle it is called a *hypocycloid*. These curves are used in defining the former American Standard composite Tooth Form.

Dedendum is the radial or perpendicular distance between the pitch circle and the bottom of the tooth space.

Diametral pitch is the ratio of the number of teeth to the number of inches in the pitch diameter in the plane of rotation, or the number of gear teeth to each inch of pitch diameter. Normal diametral pitch is the diametral pitch as calculated in the normal plane, or the diametral pitch divided by the cosine of the helix angle.

Copyright 2004, Industrial Press, Inc., New York, NY

Efficiency is the torque ratio of a gear set divided by its gear ratio.
Equivalent pitch radius is the radius of curvature of the pitch surface at the pitch point in a plane normal to the pitch line element.
Face advance is the distance on the pitch circle that a gear tooth travels from the time pitch point contact is made at one end of the tooth until pitch point contact is made at the other end.
Fillet radius is the radius of the concave portion of the tooth profile where it joins the bottom of the tooth space.
Fillet stress is the maximum tensile stress in the gear tooth fillet.
Flank of tooth is the surface between the pitch circle and the bottom land, including the gear tooth fillet.
Gear ratio is the ratio between the numbers of teeth in mating gears.
Helical overlap is the effective face width of a helical gear divided by the gear axial pitch.
Helix angle is the angle that a helical gear tooth makes with the gear axis at the pitch circle, unless specified otherwise.
Hertz stress, see *Contact stress*.
Highest point of single tooth contact (HPSTC) is the largest diameter on a spur gear at which a single tooth is in contact with the mating gear.
Interference is the contact between mating teeth at some point other than along the line of action.
Internal diameter is the diameter of a circle that coincides with the tops of the teeth of an internal gear.
Internal gear is a gear with teeth on the inner cylindrical surface.
Involute is the curve generally used as the profile of gear teeth. The curve is the path of a point on a straight line as it rolls along a convex base curve, usually a circle.
Land The top land is the top surface of a gear tooth and the *bottom land* is the surface of the gear between the fillets of adjacent teeth.
Lead is the axial advance of the helix in one complete turn, or the distance along its own axis on one revolution if the gear were free to move axially.
Length of action is the distance on an involute line of action through which the point of contact moves during the action of the tooth profile.
Line of action is the portion of the common tangent to the base cylinders along which contact between mating involute teeth occurs.
Lowest point of single tooth contact (LPSTC) is the smallest diameter on a spur gear at which a single tooth is in contact with its mating gear. Gear set contact stress is determined with a load placed on the pinion at this point.
Module is the ratio of the pitch diameter to the number of teeth, normally the ratio of pitch diameter in mm to the number of teeth. Module in the inch system is the ratio of the pitch diameter in inches to the number of teeth.
Normal plane is a plane normal to the tooth surfaces at a point of contact and perpendicular to the pitch plane.
Number of teeth is the number of teeth contained in a gear.
Outside diameter is the diameter of the circle that contains the tops of the teeth of external gears.
Pitch is the distance between similar, equally-spaced tooth surfaces in a given direction along a given curve or line.
Pitch circle is the circle through the pitch point having its center at the gear axis.
Pitch diameter is the diameter of the pitch circle. The operating pitch diameter is the pitch diameter at which the gear operates.
Pitch plane is the plane parallel to the axial plane and tangent to the pitch surfaces in any pair of gears. In a single gear, the pitch plane may be any plane tangent to the pitch surfaces.
Pitch point is the intersection between the axes of the line of centers and the line of action.
Plane of rotation is any plane perpendicular to a gear axis.

Copyright 2004, Industrial Press, Inc., New York, NY

Pressure angle is the angle between a tooth profile and a radial line at its pitch point. In involute teeth, the pressure angle is often described as the angle between the line of action and the line tangent to the pitch circle. *Standard pressure angles* are established in connection with standard tooth proportions. A given pair of involute profiles will transmit smooth motion at the same velocity ratio when the center distance is changed. Changes in center distance in gear design and gear manufacturing operations may cause changes in pitch diameter, pitch and pressure angle in the same gears under different conditions. Unless otherwise specified, the pressure angle is the *standard pressure angle at the standard pitch diameter*. The *operating pressure angle* is determined by the center distance at which a pair of gears operate. In oblique teeth such as helical and spiral designs, the pressure angle is specified in the transverse, normal or axial planes.

Principle reference planes are pitch plane, axial plane and transverse plane, all intersecting at a point and mutually perpendicular.

Rack: A rack is a gear with teeth spaced along a straight line, suitable for straight line motion. A basic rack is a rack that is adopted as the basis of a system of interchangeable gears. Standard gear tooth dimensions are often illustrated on an outline of a basic rack.

Roll angle is the angle subtended at the center of a base circle from the origin of an involute to the point of tangency of a point on a straight line from any point on the same involute. The radian measure of this angle is the tangent of the pressure angle of the point on the involute.

Root diameter is the diameter of the circle that contains the roots or bottoms of the tooth spaces.

Tangent plane is a plane tangent to the tooth surfaces at a point or line of contact.

Tip relief is an arbitrary modification of a tooth profile where a small amount of material is removed from the involute face of the tooth surface near the tip of the gear tooth.

Tooth face is the surface between the pitch line element and the tooth tip.

Tooth surface is the total tooth area including the flank of the tooth and the tooth face.

Total face width is the dimensional width of a gear blank and may exceed the effective face width as with a double-helical gear where the total face width includes any distance separating the right-hand and left-hand helical gear teeth.

Transverse plane is a plane that is perpendicular to the axial plane and to the pitch plane. In gears with parallel axes, the transverse plane and the plane of rotation coincide.

Trochoid is the curve formed by the path of a point on the extension of a radius of a circle as it rolls along a curve or line. A trochoid is also the curve formed by the path of a point on a perpendicular to a straight line as the straight line rolls along the convex side of a base curve. By the first definition, a trochoid is derived from the *cycloid*, by the second definition it is derived from the *involute*.

True involute form diameter is the smallest diameter on the tooth at which the point of tangency of the involute tooth profile exists. Usually this position is the point of tangency of the involute tooth profile and the fillet curve, and is often referred to as the TIF diameter.

Undercut is a condition in generated gear teeth when any part of the fillet curve lies inside a line drawn at a tangent to the working profile at its lowest point. Undercut may be introduced deliberately to facilitate shaving operations, as in pre-shaving.

Whole depth is the total depth of a tooth space, equal to the addendum plus the dedendum and equal to the working depth plus clearance.

Working depth is the depth of engagement of two gears, or the sum of their addendums. The standard working distance is the depth to which a tooth extends into the tooth space of a mating gear when the center distance is standard.

Definitions of gear terms are given in AGMA Standards 112.05, 115.01, and 116.01 entitled "Terms, Definitions, Symbols and Abbreviations," "Reference Information—Basic Gear Geometry," and "Glossary—Terms Used in Gearing," respectively; obtainable from American Gear Manufacturers Assn., 500 Montgomery St., St., Alexandria, VA 22314.

Copyright 2004, Industrial Press, Inc., New York, NY

Comparative Sizes and Shape of Gear Teeth



Gear Teeth of Different Diametral Pitch



Shapes of Gear Teeth of Different Pressure Angles

Nomenclature of Gear Teeth



Terms Used in Gear Geometry from Table 1 on page 2035

Properties of the Involute Curve.— The involute curve is used almost exclusively for gear-tooth profiles, because of the following important properties.

1) The form or shape of an involute curve depends upon the diameter of the base circle from which it is derived. (If a taut line were unwound from the circumference of a circle—the *base circle* of the involute—the end of that line or any point on the unwound portion, would describe an involute curve.)

Copyright 2004, Industrial Press, Inc., New York, NY

2) If a gear tooth of involute curvature acts against the involute tooth of a mating gear while rotating at a uniform rate, the angular motion of the driven gear will also be uniform, even though the center-to-center distance is varied.

3) The relative rate of motion between driving and driven gears having involute tooth curves is established by the diameters of their base circles.

4) Contact between intermeshing involute teeth on a driving and driven gear is along a straight line that is tangent to the two base circles of these gears. This is the *line of action*.

5) The point where the line of action intersects the common center-line of the mating involute gears, establishes the radii of the pitch circles of these gears; hence true pitch circle diameters are affected by a change in the center distance. (Pitch diameters obtained by dividing the number of teeth by the diametral pitch apply when the center distance equals the total number of teeth on both gears divided by twice the diametral pitch.)

6) The pitch diameters of mating involute gears are directly proportional to the diameters of their respective base circles; thus, if the base circle of one mating gear is three times as large as the other, the pitch circle diameters will be in the same ratio.

7) The angle between the line of action and a line perpendicular to the common center-line of mating gears, is the *pressure angle*; hence the pressure angle is affected by any change in the center distance.

8) When an involute curve acts against a straight line (as in the case of an involute pinion acting against straight-sided rack teeth), the straight line is tangent to the involute and perpendicular to its line of action.

9) The pressure angle, in the case of an involute pinion acting against straight-sided rack teeth, is the angle between the line of action and the line of the rack's motion. If the involute pinion rotates at a uniform rate, movement of the rack will also be uniform.

Nomenclature:

ϕ = Pressure Angle
a = Addendum a_G = Addendum of Gear a_P = Addendum of Pinion
b = Dedendum
c = Clearance
C = Center Distance
D = Pitch Diameter D_G = Pitch Diameter of Gear D_P = Pitch Diameter of Pinion
D_B = Base Circle Diameter D_O = Outside Diameter D_R = Root Diameter
F = Face Width
h_k = Working Depth of Tooth h_t = Whole Depth of Tooth
m_G = Gear Ratio
N = Number of Teeth N_G = Number of Teeth in Gear N_P = Number of Teeth in Pinion
p = Circular Pitch P = Diametral Pitch

Diametral and Circular Pitch Systems.— Gear tooth system standards are established by specifying the tooth proportions of the basic rack. The diametral pitch system is applied to most of the gearing produced in the United States. If gear teeth are larger than about one diametral pitch, it is common practice to use the circular pitch system. The circular pitch system is also applied to cast gearing and it is commonly used in connection with the design and manufacture of worm gearing.

Pitch Diameters Obtained with Diametral Pitch System.— The diametral pitch system is arranged to provide a series of standard tooth sizes, the principle being similar to the standardization of screw thread pitches. Inasmuch as there must be a whole number of teeth on each gear, the increase in pitch diameter per tooth varies according to the pitch. For example, the pitch diameter of a gear having, say, 20 teeth of 4 diametral pitch, will be 5 inches; 21 teeth, 5¼ inches; and so on, the increase in diameter for each additional tooth being equal to ¼ inch for 4 diametral pitch. Similarly, for 2 diametral pitch the variations for successive numbers of teeth would equal ½ inch, and for 10 diametral pitch the varia-

Copyright 2004, Industrial Press, Inc., New York, NY

tions would equal $\frac{1}{10}$ inch, etc. Where a given center distance must be maintained and no standard diametral pitch can be used, gears should be designed with reference to the gear set center distance procedure discussed in *Gears for Given Center Distance and Ratio* starting on page 2043.

Table 1. Formulas for Dimensions of Standard Spur Gears

To Find	Formula		To Find	Formula	
Base Circle Diameter	$D_B = D\cos\phi$	(1)	Number of Teeth	$N = P \times D$	(6a)
				$N = \frac{3.1416D}{p}$	(6b)
Circular Pitch	$p = \frac{3.1416D}{N}$	(2a)			
	$p = \frac{3.1416}{P}$	(2b)	Outside Diameter (Full-depth Teeth)	$D_O = \frac{N+2}{P}$	(7a)
				$D_O = \frac{(N+2)p}{3.1416}$	(7b)
Center Distance	$C = \frac{N_P(m_G+1)}{2P}$	(3a)			
	$C = \frac{D_P + D_G}{2}$	(3b)	Outside Diameter (American Standard Stub Teeth)	$D_O = \frac{N+1.6}{P}$	(8a)
	$C = \frac{N_G + N_P}{2P}$	(3c)		$D_O = \frac{(N+1.6)p}{3.1416}$	(8b)
	$C = \frac{(N_G + N_P)p}{6.2832}$	(3d)	Outside Diameter	$D_O = D + 2a$	(9)
Diametral Pitch	$P = \frac{3.1416}{p}$	(4a)	Pitch Diameter	$D = \frac{N}{P}$	(10a)
	$P = \frac{N}{D}$	(4b)		$D = \frac{Np}{3.1416}$	(10b)
	$P = \frac{N_P(m_G+1)}{2C}$	(4c)	Root Diameter[a]	$D_R = D - 2b$	(11)
Gear Ratio	$m_G = \frac{N_G}{N_P}$	(5)	Whole Depth	$a + b$	(12)
			Working Depth	$a_G + a_P$	(13)

[a] See also formulas in Tables 2 and 4 on pages 2035 and 2039.

Table 2. Formulas for Tooth Parts, 20-and 25-degree Involute Full-depth Teeth ANSI Coarse Pitch Spur Gear Tooth Forms *ANSI B6.1-1968 (R1974)*

To Find	Diametral Pitch, P, Known	Circular Pitch, p, Known
Addendum	$a = 1.000 \div P$	$a = 0.3183 \times p$
Dedendum (Preferred)	$b = 1.250 \div P$	$b = 0.3979 \times p$
(Shaved or Ground Teeth)[a]	$b = 1.350 \div P$	$b = 0.4297 \times p$
Working Depth	$h_k = 2.000 \div P$	$h_k = 0.6366 \times p$
Whole Depth (Preferred)	$h_t = 2.250 \div P$	$h_t = 0.7162 \times p$
(Shaved or Ground Teeth)	$h_t = 2.350 \div P$	$h_t = 0.7480 \times p$
Clearance (Preferred)[b]	$c = 0.250 \div P$	$c = 0.0796 \times p$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Formulas for Tooth Parts, 20-and 25-degree Involute Full-depth Teeth ANSI Coarse Pitch Spur Gear Tooth Forms** *ANSI B6.1-1968 (R1974)*

To Find	Diametral Pitch, P, Known	Circular Pitch, p, Known
(Shaved or Ground Teeth)	$c = 0.350 \div P$	$c = 0.1114 \times p$
Fillet Radius (Rack)[c]	$r_f = 0.300 \div P$	$r_f = 0.0955 \times p$
Pitch Diameter	$D = N \div P$	$D = 0.3183 \times N_p$
Outside Diameter	$D_O = (N + 2) \div P$	$D_O = 0.3183 \times (N + 2)p$
Root Diameter (Preferred)	$D_R = (N - 2.5) \div P$	$D_R = 0.3183 \times (N - 2.5)p$
(Shaved or Ground Teeth)	$D_R = (N - 2.7) \div P$	$D_R = 0.3183 \times (N - 2.7)p$
Circular Thickness—Basic	$t = 1.5708 \div P$	$t = p \div 2$

[a] When gears are preshave cut on a gear shaper the dedendum will usually need to be increased to $1.40/P$ to allow for the higher fillet trochoid produced by the shaper cutter. This is of particular importance on gears of few teeth or if the gear blank configuration requires the use of a small diameter shaper cutter, in which case the dedendum may need to be increased to as much as $1.45/P$. This should be avoided on highly loaded gears where the consequently reduced J factor will increase gear tooth stress excessively.

[b] A minimum clearance of $0.157/P$ may be used for the basic 20-degree and 25-degree pressure angle rack in the case of shallow root sections and use of existing hobs or cutters. However, whenever less than standard clearance is used, the location of the TIF diameter should be determined by the method shown in *True Involute Form Diameter* starting on page 2061. The TIF diameter must be less than the Contact Diameter determined by the method shown on page 2059.

[c] The fillet radius of the basic rack should not exceed $0.235/P$ for a 20-degree pressure angle rack or $0.270/P$ for a 25-degree pressure angle rack for a clearance of $0.157/P$. The basic rack fillet radius must be *reduced* for teeth with a 25-degree pressure angle having a clearance in excess of $0.250/P$.

American National Standard Coarse Pitch Spur Gear Tooth Forms.— The American National Standard (ANSI B6.1-1968, R1974) provides tooth proportion information on two involute spur gear forms. These two forms are identical except that one has a pressure angle of 20 degrees and a minimum allowable tooth number of 18 while the other has a pressure angle of 25 degrees and a minimum allowable tooth number of 12. (For pinions with fewer teeth, see tooth proportions for long addendum pinions and their mating short addendum gears in Tables 7 through 9d starting on page 2050.) A gear tooth standard is established by specifying the tooth proportions of the basic rack. Gears made to this standard will thus be conjugate with the specified rack and with each other. The basic rack forms for the 20-degree and 25-degree standard are shown on the following page; basic formulas for these proportions as a function of the gear diametral pitch and also of the circular pitch are given in Table 2. Tooth parts data are given in Table 3.

In recent years the established standard of almost universal use is the ANSI 20-degree standard spur gear form. It provides a gear with good strength and without fillet undercut in pinions of as few as eighteen teeth. Some more recent applications have required a tooth form of even greater strength and fewer teeth than eighteen. This requirement has stimulated the establishment of the ANSI 25-degree standard. This 25-degree form will give greater tooth strength than the 20-degree standard, will provide pinions of as few as twelve teeth without fillet undercut and will provide a lower contact compressive stress for greater gear set surface durability.

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard and Former American Standard Gear Tooth Forms
ANSI B6.1-1968, (R1974) **and** *ASA B6.1-1932*



a = addendum
b = dedendum
c = clearance
h_k = working depth
h_t = whole depth
p = circular pitch
r_f = fillet radius of basic rack
t = circular tooth thickness — basic
ϕ = pressure angle

Basic Rack of the 20-Degree and 25-Degree Full-Depth Involute Systems



Basic Rack of the 14½-Degree Full-Depth Involute System



Basic Rack of the 20-Degree Stub Involute System



Approximation of Basic Rack for the 14½-Degree Composite System

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Gear Tooth Parts for American National Standard Coarse Pitch 20- and 25-Degree Pressure Angle Gears

Dia. Pitch	Circ. Pitch	Stand. Addend.[a]	Stand. Dedend.	Spec. Dedend.[b]	Min. Dedend.	Stand. F. Rad.	Min. F. Rad.
P	*p*	*a*	*b*	*b*	*b*	r_f	r_f
0.3142	10.	3.1831	3.9789	4.2972	3.6828	0.9549	0.4997
0.3307	9.5	3.0239	3.7799	4.0823	3.4987	0.9072	0.4748
0.3491	9.	2.8648	3.5810	3.8675	3.3146	0.8594	0.4498
0.3696	8.5	2.7056	3.3820	3.6526	3.1304	0.8117	0.4248
0.3927	8.	2.5465	3.1831	3.4377	2.9463	0.7639	0.3998
0.4189	7.5	2.3873	2.9842	3.2229	2.7621	0.7162	0.3748
0.4488	7.	2.2282	2.7852	3.0080	2.5780	0.6685	0.3498
0.4833	6.5	2.0690	2.5863	2.7932	2.3938	0.6207	0.3248
0.5236	6.	1.9099	2.3873	2.5783	2.2097	0.5730	0.2998
0.5712	5.5	1.7507	2.1884	2.3635	2.0256	0.5252	0.2749
0.6283	5.	1.5915	1.9894	2.1486	1.8414	0.4775	0.2499
0.6981	4.5	1.4324	1.7905	1.9337	1.6573	0.4297	0.2249
0.7854	4.	1.2732	1.5915	1.7189	1.4731	0.3820	0.1999
0.8976	3.5	1.1141	1.3926	1.5040	1.2890	0.3342	0.1749
1.	3.1416	1.0000	1.2500	1.3500	1.1570	0.3000	0.1570
1.25	2.5133	0.8000	1.0000	1.0800	0.9256	0.2400	0.1256
1.5	2.0944	0.6667	0.8333	0.9000	0.7713	0.2000	0.1047
1.75	1.7952	0.5714	0.7143	0.7714	0.6611	0.1714	0.0897
2.	1.5708	0.5000	0.6250	0.6750	0.5785	0.1500	0.0785
2.25	1.3963	0.4444	0.5556	0.6000	0.5142	0.1333	0.0698
2.5	1.2566	0.4000	0.5000	0.5400	0.4628	0.1200	0.0628
2.75	1.1424	0.3636	0.4545	0.4909	0.4207	0.1091	0.0571
3.	1.0472	0.3333	0.4167	0.4500	0.3857	0.1000	0.0523
3.25	0.9666	0.3077	0.3846	0.4154	0.3560	0.0923	0.0483
3.5	0.8976	0.2857	0.3571	0.3857	0.3306	0.0857	0.0449
3.75	0.8378	0.2667	0.3333	0.3600	0.3085	0.0800	0.0419
4.	0.7854	0.2500	0.3125	0.3375	0.2893	0.0750	0.0392
4.5	0.6981	0.2222	0.2778	0.3000	0.2571	0.0667	0.0349
5.	0.6283	0.2000	0.2500	0.2700	0.2314	0.0600	0.0314
5.5	0.5712	0.1818	0.2273	0.2455	0.2104	0.0545	0.0285
6.	0.5236	0.1667	0.2083	0.2250	0.1928	0.0500	0.0262
6.5	0.4833	0.1538	0.1923	0.2077	0.1780	0.0462	0.0242
7.	0.4488	0.1429	0.1786	0.1929	0.1653	0.0429	0.0224
7.5	0.4189	0.1333	0.1667	0.1800	0.1543	0.0400	0.0209
8.	0.3927	0.1250	0.1563	0.1687	0.1446	0.0375	0.0196
8.5	0.3696	0.1176	0.1471	0.1588	0.1361	0.0353	0.0185
9.	0.3491	0.1111	0.1389	0.1500	0.1286	0.0333	0.0174
9.5	0.3307	0.1053	0.1316	0.1421	0.1218	0.0316	0.0165
10.	0.3142	0.1000	0.1250	0.1350	0.1157	0.0300	0.0157
11.	0.2856	0.0909	0.1136	0.1227	0.1052	0.0273	0.0143
12.	0.2618	0.0833	0.1042	0.1125	0.0964	0.0250	0.0131
13.	0.2417	0.0769	0.0962	0.1038	0.0890	0.0231	0.0121
14.	0.2244	0.0714	0.0893	0.0964	0.0826	0.0214	0.0112
15.	0.2094	0.0667	0.0833	0.0900	0.0771	0.0200	0.0105
16.	0.1963	0.0625	0.0781	0.0844	0.0723	0.0188	0.0098
17.	0.1848	0.0588	0.0735	0.0794	0.0681	0.0176	0.0092
18.	0.1745	0.0556	0.0694	0.0750	0.0643	0.0167	0.0087
19.	0.1653	0.0526	0.0658	0.0711	0.0609	0.0158	0.0083
20.	0.1571	0.0500	0.0625	0.0675	0.0579	0.0150	0.0079

[a] When using equal addendums on pinion and gear the minimum number of teeth on the pinion is 18 and the minimum total number of teeth in the pair is 36 for 20-degree full depth involute tooth form and 12 and 24, respectively, for 25-degree full depth tooth form.

[b] The dedendum in this column is used when the gear tooth is shaved. It allows for the higher fillet cut by a protuberance hob.

The working depth is equal to twice the addendum.

The whole depth is equal to the addendum plus the dedendum.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Tooth Proportions for Fine-Pitch Involute Spur and Helical Gears of 14½-, 20-, and 25-Degree Pressure Angle *ANSI B6.7-1977*

Item	Spur	Helical
Addendum, a	$\frac{1.000}{P}$	$\frac{1.000}{P_n}$
Dedendum, b	$\frac{1.200}{P} + 0.002$ (min.)	$\frac{1.200}{P_n} + 0.002$ (min.)
Working Depth, h_k	$\frac{2.000}{P}$	$\frac{2.000}{P_n}$
Whole Depth, h_t	$\frac{2.200}{P} + 0.002$ (min.)	$\frac{2.200}{P_n} + 0.002$ (min.)
Clearance, c (Standard)	$\frac{0.200}{P} + 0.002$ (min.)	$\frac{0.200}{P_n} + 0.002$ (min.)
(Shaved or Ground Teeth)	$\frac{0.350}{P} + 0.002$ (min.)	$\frac{0.350}{P_n} + 0.002$ (min.)
Tooth Thickness, t At Pitch Diameter	$t = \frac{1.5708}{P}$	$t_n = \frac{1.5708}{P_n}$
Circular Pitch, p	$p = \frac{\pi D}{N}$ or $\frac{\pi d}{n}$ or $\frac{\pi}{P}$	$p_n = \frac{\pi}{P_n}$
Pitch Diameter Pinion, d	$\frac{n}{P}$	$\frac{n}{P_n \cos\psi}$
Gear, D	$\frac{N}{P}$	$\frac{N}{P_n \cos\psi}$
Outside Diameter Pinion, d_o	$\frac{n+2}{P}$	$\frac{1}{P_n}\left(\frac{n}{\cos\psi} + 2\right)$
Gear, D_o	$\frac{N+2}{P}$	$\frac{1}{P_n}\left(\frac{N}{\cos\psi} + 2\right)$
Center Distance, C	$\frac{N+n}{2P}$	$\frac{N+n}{2P_n \cos\psi}$

All dimensions are in inches.
P = Transverse Diametral Pitch
P_n = Normal Diametral Pitch
t_n = Normal Tooth Thickness at Pitch Diameter
p_n = Normal Circular Pitch
ψ = Helix Angle
n = Number of pinion teeth
N = Number of gear teeth

American National Standard Tooth Proportions for Fine-Pitch Involute Spur and Helical Gears.— The proportions of spur gears in this Standard (ANSI B6.7-1977) follow closely ANSI B6.1-1968, R1974, "Tooth Proportions for Coarse-Pitch Involute Spur Gears." The main difference between fine-pitch and coarse-pitch gears is the greater clearance specified for fine-pitch gears. The increased clearance provides for any foreign material that may tend to accumulate at the bottoms of the teeth and also the relatively larger fillet radius resulting from proportionately greater wear on the tips of fine-pitch cutting tools.

Pressure Angle: The standard pressure angle for fine-pitch gears is 20 degrees and is recommended for most applications. For helical gears this pressure angle applies in the *normal* plane. In certain cases, notably sintered or molded gears, or in gearing where greatest strength and wear resistance are desired, a 25-degree pressure angle may be required.

Copyright 2004, Industrial Press, Inc., New York, NY

However, pressure angles greater than 20 degrees tend to require use of generating tools having very narrow point widths, and higher pressure angles require closer control of center distance when backlash requirements are critical.

In those cases where consideration of angular position or backlash is critical and both pinion and gear contain relatively large numbers of teeth, a 14½-degree pressure angle may be desirable. In general, pressure angles less than 20 degrees require greater amounts of tooth modification to avoid undercutting problems and are limited to larger total numbers of teeth in pinion and gear when operating at a standard center distance. Information Sheet B in the Standard provides tooth proportions for both 14½- and 25-degree pressure angle fine-pitch gears. Table 4 provides tooth proportions for fine-pitch spur and helical gears with 14½-, 20-, and 25-degree pressure angles, and Table 5 provides tooth parts.

Diametral Pitches: Diametral pitches preferred are: 20, 24, 32, 40, 48, 64, 72, 80, 96, and 120.

Table 5. American National Standard Fine Pitch Standard Gear Tooth Parts—14½-, 20-, and 25-Degree Pressure Angles

Diametral Pitch	Circular Pitch	Circular Thickness	Standard Addend.	Standard Dedend.	Special Dedend.[a]
P	*p*	*t*	*a*	*b*	*b*
20	0.1571	0.0785	0.0500	0.0620	0.0695
24	0.1309	0.0654	0.0417	0.0520	0.0582
32	0.0982	0.0491	0.0313	0.0395	0.0442
40	0.0785	0.0393	0.0250	0.0320	0.0358
48	0.0654	0.0327	0.0208	0.0270	0.0301
64	0.0491	0.0245	0.0156	0.0208	0.0231
72	0.0436	0.0218	0.0139	0.0187	0.0208
80	0.0393	0.0196	0.0125	0.0170	0.0189
96	0.0327	0.0164	0.0104	0.0145	0.0161
120	0.0262	0.0131	0.0083	0.0120	0.0132

[a] Based upon clearance for shaved or ground teeth.

The working depth is equal to twice the addendum. The whole depth is equal to the addendum plus the dedendum. For minimum number of teeth see page 2058.

Other American Spur Gear Standards.— An appended information sheet in the American National Standard ANSI B6.1-1968, R1974 provides tooth proportion information for three spur gear forms with the notice that they are "not recommended for new designs." These forms are therefore considered to be obsolescent but the information is given on their proportions because they have been used widely in the past. These forms are the 14½-degree full depth form, the 20-degree stub involute form and the 14½-degree composite form which were covered in the former American Standard (ASA B6.1-1932). The basic rack for the 14½-degree full depth form is shown on page 2036; basic formulas for these proportions are given in Table 6.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Formulas for Tooth Parts—Former American Standard Spur Gear Tooth Forms *ASA B6.1-1932*

To Find	Diametral Pitch, P Known	Circular Pitch, p Known
14½-Degree Involute Full-depth Teeth		
Addendum	$a = 1.000 \div P$	$a = 0.3183 \times p$
Minimum Dedendum	$b = 1.157 \div P$	$b = 0.3683 \times p$
Working Depth	$h_k = 2.000 \div P$	$h_k = 0.6366 \times p$
Minimum Whole Depth	$h_t = 2.157 \div P$	$h_t = 0.6866 \times p$
Basic Tooth Thickness on Pitch Line	$t = 1.5708 \div P$	$t = 0.500 \times p$
Minimum Clearance	$c = 0.157 \div P$	$c = 0.050 \times p$
20-Degree Involute Stub Teeth		
Addendum	$a = 0.800 \div P$	$a = 0.2546 \times p$
Minimum Dedendum	$b = 1.000 \div P$	$b = 0.3183 \times p$
Working Depth	$h_k = 1.600 \div P$	$h_k = 0.5092 \times p$
Minimum Whole Depth	$h_t = 1.800 \div P$	$h_t = 0.5729 \times p$
Basic Tooth Thickness on Pitch Line	$t = 1.5708 \div P$	$t = 0.500 \times p$
Minimum Clearance	$c = 0.200 \div P$	$c = 0.0637 \times p$

Note: Radius of fillet equals 1⅓ × clearance for 14½-degree full-depth teeth and 1½ × clearance for 20-degree full-depth teeth.

Note: A suitable working tolerance should be considered in connection with all minimum recommendations.

Fellows Stub Tooth.— The system of stub gear teeth introduced by the Fellows Gear Shaper Co. is based upon the use of two diametral pitches. One diametral pitch, say, 8, is used as the basis for obtaining the dimensions for the addendum and dedendum, while another diametral pitch, say, 6, is used for obtaining the dimensions of the thickness of the tooth, the number of teeth, and the pitch diameter. Teeth made according to this system are designated as $^6/_8$ pitch, $^{12}/_{14}$ pitch, etc., the numerator in this fraction indicating the pitch determining the thickness of the tooth and the number of teeth, and the denominator, the pitch determining the depth of the tooth. The clearance is made greater than in the ordinary gear-tooth system and equals 0.25 ÷ denominator of the diametral pitch. The pressure angle is 20 degrees.

This type of stub gear tooth is now used infrequently. For information as to the tooth part dimensions see 18th and earlier editions of Machinery's Handbook.

Basic Gear Dimensions.— The basic dimensions for all involute spur gears may be obtained using the formulas shown in Table 1. This table is used in conjunction with Table 3 to obtain dimensions for coarse pitch gears and Table 5 to obtain dimensions for fine pitch standard spur gears. To obtain the dimensions of gears that are specified at a standard circular pitch, the equivalent diametral pitch is first calculated by using the formula in Table 1. If the required number of teeth in the pinion (N_p) is less than the minimum specified in either Table 3 or Table 5, whichever is applicable, the gears must be proportioned by the long and short addendum method shown on page 2052.

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Outside and Root Diameters of Spur Gears that are Finish-hobbed, Shaped, or Pre-shaved

Notation	
D = Pitch Diameter	a = Standard Addendum
D_O = Outside Diameter	b = Standard Minimum Dedendum
D_R = Root Diameter	b_s = Standard Dedendum
P = Diametral Pitch	b_{ps} = Dedendum for Pre-shaving

$14\frac{1}{2}$-, 20-, And 25-degree Involute Full-depth Teeth (19P and coarser)[a]	
$D_O = D + 2a = \frac{N}{P} + \left(2 \times \frac{1}{P}\right)$	
$D_R = D - 2b = \frac{N}{P} - \left(2 \times \frac{1.157}{P}\right)$	(Hobbed)[b]
$D_R = D - 2b_s = \frac{N}{P} - \left(2 \times \frac{1.25}{P}\right)$	(Shaped)[c]
$D_R = D - 2b_{ps} = \frac{N}{P} - \left(2 \times \frac{1.35}{P}\right)$	(Pre-shaved)[d]
$D_R = D - 2b_{ps} = \frac{N}{P} - \left(2 \times \frac{1.40}{P}\right)$	(Pre-shaved)[e]
20-degree Involute Fine-pitch Full-depth Teeth (20P and finer)	
$D_O = D + 2a = \frac{N}{P} + \left(2 \times \frac{1}{P}\right)$	
$D_R = D - 2b = \frac{N}{P} - 2\left(\frac{1.2}{P} + 0.002\right)$	(Hobbed or Shaped)[f]
$D_R = D - 2b_{ps} = \frac{N}{P} - 2\left(\frac{1.35}{P} + 0.002\right)$	(Pre-shaved)[g]
20-degree Involute Stub Teeth[a]	
$D_O = D + 2a = \frac{N}{P} + \left(2 \times \frac{0.8}{P}\right)$	
$D_R = D - 2b = \frac{N}{P} - \left(2 \times \frac{1}{P}\right)$	(Hobbed)
$D_R = D - 2b_{ps} = \frac{N}{P} - \left(2 \times \frac{1.35}{P}\right)$	(Pre-shaved)

[a] $14\frac{1}{2}$-degree full-depth and 20-degree stub teeth are not recommended for new designs.

[b] According to ANSI B6.1-1968 a minimum clearance of $0.157/P$ may be used for the basic 20-degree and 25-degree pressure angle rack in the case of shallow root sections and the use of existing hobs and cutters.

[c] According to ANSI B6.1-1968 the preferred clearance is $0.250/P$.

[d] According to ANSI B6.1-1968 the clearance for teeth which are shaved or ground is $0.350/P$.

[e] When gears are preshave cut on a gear shaper the dedendum will usually need to be increased to $1.40/P$ to allow for the higher fillet trochoid produced by the shaper cutter; this is of particular importance on gears of few teeth or if the gear blank configuration requires the use of a small diameter shaper cutter, in which case the dedendum may need to be increased to as much as $1.45/P$. This should be avoided on highly loaded gears where the consequently reduced J factor will increase gear tooth stress excessively.

[f] According to ANSI B6.7-1967 the standard clearance is $0.200/P + 0.002$ (min.).

[g] According to ANSI B6.7-1967 the clearance for shaved or ground teeth is $0.350/P + 0.002$ (min.).

Copyright 2004, Industrial Press, Inc., New York, NY

Gears for Given Center Distance and Ratio.— When it is necessary to use a pair of gears of given ratio at a specified center distance C_1, it may be found that no gears of standard diametral pitch will satisfy the center distance requirement. Gears of standard diametral pitch P may need to be redesigned to operate at other than their standard pitch diameter D and standard pressure angle ϕ. The diametral pitch P_1 at which these gears will operate is

$$P_1 = \frac{N_P + N_G}{2C_1} \tag{1}$$

where N_p = number of teeth in pinion
N_G = number of teeth in gear
and their operating pressure angle ϕ_1 is

$$\phi_1 = \arccos\left(\frac{P_1}{P}\cos\phi\right) \tag{2}$$

Thus although the pair of gears are cut to a diametral pitch P and a pressure angle ϕ, they operate as standard gears of diametral pitch $P1$ and pressure angle ϕ_1. The pitch P and pressure angle ϕ should be chosen so that ϕ_1 lies between about 18 and 25 degrees.

The operating pitch diameters of the pinion D_{p1} and of the gear D_{G1} are

$$D_{P1} = \frac{N_P}{P_1} \tag{3a}$$ and $$D_{G1} = \frac{N_G}{P_1} \tag{3b}$$

The base diameters of the pinion D_{PB1} and of the gear D_{GB1} are

$$D_{PB1} = D_{P1}\cos\phi_1 \tag{4a}$$ and $$D_{GB1} = D_{G1}\cos\phi_1 \tag{4b}$$

The basic tooth thickness, t_1, at the operating pitch diameter for both pinion and gear is

$$t_1 = \frac{1.5708}{P_1} \tag{5}$$

The root diameters of the pinion D_{PR1} and gear D_{GR1} and the corresponding outside diameters D_{PO1} and D_{GO1} are not standard because each gear is to be cut with a cutter that is not standard for the operating pitch diameters D_{P1} and D_{G1}.

The root diameters are

$$D_{PR_1} = \frac{N_P}{P} - 2b_{P_1} \tag{6a}$$ and $$D_{GR_1} = \frac{N_G}{P} - 2b_{G_1} \tag{6b}$$

where $$b_{P1} = b_c - \left(\frac{t_{P_2} - 1.5708/P}{2\tan\phi}\right) \tag{7a}$$

and $$b_{G1} = b_c - \frac{t_{G_2} - 1.5708/P}{2\tan\phi} \tag{7b}$$

where b_c is the hob or cutter addendum for the pinion and gear.

The tooth thicknesses of the pinion t_{P2} and the gear t_{G2} are

$$t_{P_2} = \frac{N_P}{P}\left(\frac{1.5708}{N_P} + \text{inv}\,\phi_1 - \text{inv}\,\phi\right) \tag{8a}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$t_{G2} = \frac{N_G}{P}\left(\frac{1.5708}{N_G} + \text{inv}\,\phi_1 - \text{inv}\,\phi\right) \quad (8b)$$

The outside diameter of the pinion D_{PO} and the gear D_{GO} are

$$D_{PO} = 2 \times C_1 - D_{GR1} - 2(b_c - 1/P) \quad (9a)$$

and

$$D_{GO} = 2 \times C_1 - D_{PR1} - 2(b_c - 1/P) \quad (9b)$$

Example: Design gears of 8 diametral pitch, 20-degree pressure angle, and 28 and 88 teeth to operate at 7.50-inch center distance. The gears are to be cut with a hob of 0.169-inch addendum.

$$P_1 = \frac{28 + 88}{2 \times 7.50} = 7.7333 \quad (1)$$

$$\phi_1 = \arccos\left(\frac{7.7333}{8} \times 0.93969\right) = 24.719° \quad (2)$$

$$D_{P1} = \frac{28}{7.7333} = 3.6207 \text{ in.} \quad (3a)$$

and

$$D_{G1} = \frac{88}{7.7333} = 11.3794 \text{ in.} \quad (3b)$$

$$D_{PB1} = 3.6207 \times 0.90837 = 3.2889 \text{ in.} \quad (4a)$$

and

$$D_{GB1} = 11.3794 \times 0.90837 = 10.3367 \text{ in.} \quad (4b)$$

$$t_1 = \frac{1.5708}{7.7333} = 0.20312 \text{ in.} \quad (5)$$

$$D_{PR1} = \frac{28}{8} - 2 \times 0.1016 = 3.2968 \text{ in.} \quad (6a)$$

and

$$D_{GR1} = \frac{88}{8} - 2 \times (-0.0428) = 11.0856 \text{ in.} \quad (6b)$$

$$b_{P1} = 0.169 - \left(\frac{0.2454 - 1.5708/8}{2 \times 0.36397}\right) = 0.1016 \text{ in.} \quad (7a)$$

$$b_{G1} = 0.169 - \left(\frac{0.3505 - 1.5708/8}{2 \times 0.36397}\right) = -0.0428 \text{ in.} \quad (7b)$$

$$t_{P2} = \frac{28}{8}\left(\frac{1.5708}{28} + 0.028922 - 0.014904\right) = 0.2454 \text{ in.} \quad (8a)$$

$$t_{G2} = \frac{88}{8}\left(\frac{1.5708}{88} + 0.028922 - 0.014904\right) - 0.3505 \text{ in.} \quad (8b)$$

$$D_{PO1} = 2 \times 7.50 - 11.0856 - 2(0.169 - 1/8) = 3.8264 \text{ in.} \quad (9a)$$

$$D_{GO1} = 2 \times 7.50 - 3.2968 - 2(0.169 - 1/8) = 11.6152 \text{ in.} \quad (9b)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Tooth Thickness Allowance for Shaving.— Proper stock allowance is important for good results in shaving operations. If too much stock is left for shaving, the life of the shaving tool is reduced and, in addition, shaving time is increased. The following figures represent the amount of stock to be left on the teeth for removal by shaving under average conditions: For diametral pitches of 2 to 4, a thickness of 0.003 to 0.004 inch (one-half on each side of the tooth); for 5 to 6 diametral pitch, 0.0025 to 0.0035 inch; for 7 to 10 diametral pitch, 0.002 to 0.003 inch; for 11 to 14 diametral pitch, 0.0015 to 0.0020 inch; for 16 to 18 diametral pitch, 0.001 to 0.002 inch; for 20 to 48 diametral pitch, 0.0005 to 0.0015 inch; and for 52 to 72 diametral pitch, 0.0003 to 0.0007 inch.

The thickness of the gear teeth may be measured in several ways to determine the amount of stock left on the sides of the teeth to be removed by shaving. If it is necessary to measure the tooth thickness during the preshaving operation while the gear is in the gear shaper or hobbing machine, a gear tooth caliper or pins would be employed. Caliper methods of measuring gear teeth are explained in detail on page 2051 for measurements over single teeth, and on page 2140 for measurements over two or more teeth.

When the preshaved gear can be removed from the machine for checking, the center distance method may be employed. In this method, the preshaved gear is meshed without backlash with a gear of standard tooth thickness and the increase in center distance over standard is noted. The amount of total tooth thickness over standard on the preshaved gear can then be determined by the formula: $t_2 = 2 \tan \phi \times d$, where t_2 = amount that the total thickness of the tooth exceeds the standard thickness, ϕ = pressure angle, and d = amount that the center distance between the two gears exceeds the standard center distance.

Circular Pitch for Given Center Distance and Ratio.— When it is necessary to use a pair of gears of given ratio at a specified center distance, it may be found that no gears of standard diametral pitch will satisfy the center distance requirement. Hence, circular pitch gears may be selected. To find the required circular pitch p, when the center distance C and total number of teeth N in both gears are known, use the following formula:

$$p = \frac{C \times 6.2832}{N}$$

Example: A pair of gears having a ratio of 3 is to be used at a center distance of 10.230 inches. If one gear has 60 teeth and the other 20, what must be their circular pitch?

$$p = \frac{10.230 \times 6.2832}{60 + 20} = 0.8035 \text{ inch}$$

Circular Thickness of Tooth when Outside Diameter is Standard.— For a full-depth or stub tooth gear of standard outside diameter, the tooth thickness on the pitch circle (circular thickness or arc thickness) is found by the following formula:

$$t = \frac{1.5708}{P}$$

where t = circular thickness and P = diametral pitch. In Fellows stub tooth gears the diametral pitch used is the numerator of the pitch fraction (for example, 6 if the pitch is 6/8).

Example 1: Find the tooth thickness on the pitch circle of a 14½-degree full-depth tooth of 12 diametral pitch.

$$t = \frac{1.5708}{12} = 0.1309 \text{ inch}$$

Example 2: Find the tooth thickness on the tooth circle of a 20-degree full-depth involute tooth having a diametral pitch of 5.

$$t = \frac{1.5708}{5} = 0.31416, \text{ say } 0.3142 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

The tooth thickness on the pitch circle can be determined very accurately by means of measurement over wires which are located in tooth spaces that are diametrically opposite or as nearly diametrically opposite as possible. Where measurement over wires is not feasible, the circular or arc tooth thickness can be used in determining the chordal thickness which is the dimension measured with a gear tooth caliper.

Circular Thickness of Tooth when Outside Diameter has been Enlarged.— When the outside diameter of a small pinion is not standard but is enlarged to avoid undercut and to improve tooth action, the teeth are located farther out radially relative to the standard pitch diameter and consequently the circular tooth thickness at the standard pitch diameter is increased. To find this increased arc thickness the following formula is used, where t = tooth thickness; e = amount outside diameter is increased over standard; ϕ = pressure angle; and p = circular pitch at the standard pitch diameter.

$$t = \frac{p}{2} + e\tan\phi$$

Example: The outside diameter of a pinion having 10 teeth of 5 diametral pitch and a pressure angle of 14½ degrees is to be increased by 0.2746 inch. The circular pitch equivalent to 5 diametral pitch is 0.6283 inch. Find the arc tooth thickness at the standard pitch diameter.

$$t = \frac{0.6283}{2} + (0.2746 \times \tan 14\tfrac{1}{2}^\circ)$$

$$t = 0.3142 + (0.2746 \times 0.25862) = 0.3852 \text{ inch}$$

Circular Thickness of Tooth when Outside Diameter has been Reduced.— If the outside diameter of a gear is reduced, as is frequently done to maintain the standard center distance when the outside diameter of the mating pinion is increased, the circular thickness of the gear teeth at the standard pitch diameter will be reduced.This decreased circular thickness can be found by the following formula where t = circular thickness at the standard pitch diameter; e = amount outside diameter is reduced under standard; ϕ = pressure angle; and p = circular pitch.

$$t = \frac{p}{2} - e\tan\phi$$

Example: The outside diameter of a gear having a pressure angle of 14½ degrees is to be reduced by 0.2746 inch or an amount equal to the increase in diameter of its mating pinion. The circular pitch is 0.6283 inch. Determine the circular tooth thickness at the standard pitch diameter.

$$t = \frac{0.6283}{2} - (0.2746 \times \tan 14\tfrac{1}{2}^\circ)$$

$$t = 0.3142 - (0.2746 \times 0.25862) = 0.2432 \text{ inch}$$

Chordal Thickness of Tooth when Outside Diameter is Standard.— To find the chordal or straight line thickness of a gear tooth the following formula can be used where t_c = chordal thickness; D = pitch diameter; and N = number of teeth.

$$t_c = D\sin\left(\frac{90^\circ}{N}\right)$$

Example: A pinion has 15 teeth of 3 diametral pitch; the pitch diameter is equal to 15 ÷ 3 or 5 inches. Find the chordal thickness at the standard pitch diameter.

$$t_c = 5\sin\left(\frac{90^\circ}{15}\right) = 5\sin 6^\circ = 5 \times 0.10453 = 0.5226 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Chordal Thicknesses and Chordal Addenda of Milled, Full-depth Gear Teeth and of Gear Milling Cutters



T = chordal thickness of gear tooth and cutter tooth at pitch line;
H = chordal addendum for full-depth gear tooth;
A = chordal addendum of cutter = (2.157 ÷ diametral pitch) − H
= (0.6866 × circular pitch) − H.

Diametral Pitch	Dimension	Number of Gear Cutter, and Corresponding Number of Teeth							
		No. 1 135 Teeth	No. 2 55 Teeth	No. 3 35 Teeth	No. 4 26 Teeth	No. 5 21 Teeth	No. 6 17 Teeth	No. 7 14 Teeth	No. 8 12 Teeth
1	T	1.5707	1.5706	1.5702	1.5698	1.5694	1.5686	1.5675	1.5663
	H	1.0047	1.0112	1.0176	1.0237	1.0294	1.0362	1.0440	1.0514
1½	T	1.0471	1.0470	1.0468	1.0465	1.0462	1.0457	1.0450	1.0442
	H	0.6698	0.6741	0.6784	0.6824	0.6862	0.6908	0.6960	0.7009
2	T	0.7853	0.7853	0.7851	0.7849	0.7847	0.7843	0.7837	0.7831
	H	0.5023	0.5056	0.5088	0.5118	0.5147	0.5181	0.5220	0.5257
2½	T	0.6283	0.6282	0.6281	0.6279	0.6277	0.6274	0.6270	0.6265
	H	0.4018	0.4044	0.4070	0.4094	0.4117	0.4144	0.4176	0.4205
3	T	0.5235	0.5235	0.5234	0.5232	0.5231	0.5228	0.5225	0.5221
	H	0.3349	0.3370	0.3392	0.3412	0.3431	0.3454	0.3480	0.3504
3½	T	0.4487	0.4487	0.4486	0.4485	0.4484	0.4481	0.4478	0.4475
	H	0.2870	0.2889	0.2907	0.2919	0.2935	0.2954	0.2977	0.3004
4	T	0.3926	0.3926	0.3926	0.3924	0.3923	0.3921	0.3919	0.3915
	H	0.2511	0.2528	0.2544	0.2559	0.2573	0.2590	0.2610	0.2628
5	T	0.3141	0.3141	0.3140	0.3139	0.3138	0.3137	0.3135	0.3132
	H	0.2009	0.2022	0.2035	0.2047	0.2058	0.2072	0.2088	0.2102
6	T	0.2618	0.2617	0.2617	0.2616	0.2615	0.2614	0.2612	0.2610
	H	0.1674	0.1685	0.1696	0.1706	0.1715	0.1727	0.1740	0.1752
7	T	0.2244	0.2243	0.2243	0.2242	0.2242	0.2240	0.2239	0.2237
	H	0.1435	0.1444	0.1453	0.1462	0.1470	0.1480	0.1491	0.1502
8	T	0.1963	0.1963	0.1962	0.1962	0.1961	0.1960	0.1959	0.1958
	H	0.1255	0.1264	0.1272	0.1279	0.1286	0.1295	0.1305	0.1314
9	T	0.1745	0.1745	0.1744	0.1744	0.1743	0.1743	0.1741	0.1740
	H	0.1116	0.1123	0.1130	0.1137	0.1143	0.1151	0.1160	0.1168
10	T	0.1570	0.1570	0.1570	0.1569	0.1569	0.1568	0.1567	0.1566
	H	0.1004	0.1011	0.1017	0.1023	0.1029	0.1036	0.1044	0.1051
11	T	0.1428	0.1428	0.1427	0.1427	0.1426	0.1426	0.1425	0.1424
	H	0.0913	0.0919	0.0925	0.0930	0.0935	0.0942	0.0949	0.0955
12	T	0.1309	0.1309	0.1308	0.1308	0.1308	0.1307	0.1306	0.1305
	H	0.0837	0.0842	0.0848	0.0853	0.0857	0.0863	0.0870	0.0876
14	T	0.1122	0.1122	0.1121	0.1121	0.1121	0.1120	0.1119	0.1118
	H	0.0717	0.0722	0.0726	0.0731	0.0735	0.0740	0.0745	0.0751
16	T	0.0981	0.0981	0.0981	0.0981	0.0980	0.0980	0.0979	0.0979
	H	0.0628	0.0632	0.0636	0.0639	0.0643	0.0647	0.0652	0.0657
18	T	0.0872	0.0872	0.0872	0.0872	0.0872	0.0871	0.0870	0.0870
	H	0.0558	0.0561	0.0565	0.0568	0.0571	0.0575	0.0580	0.0584
20	T	0.0785	0.0785	0.0785	0.0785	0.0784	0.0784	0.0783	0.0783
	H	0.0502	0.0505	0.0508	0.0511	0.0514	0.0518	0.0522	0.0525

Copyright 2004, Industrial Press, Inc., New York, NY

Chordal Thicknesses and Chordal Addenda of Milled, Full-depth Gear Teeth and of Gear Milling Cutters

Circular Pitch	Dimension	Number of Gear Cutter, and Corresponding Number of Teeth							
		No. 1 135 Teeth	No. 2 55 Teeth	No. 3 35 Teeth	No. 4 26 Teeth	No. 5 21 Teeth	No. 6 17 Teeth	No. 7 14 Teeth	No. 8 12 Teeth
1/4	T	0.1250	0.1250	0.1249	0.1249	0.1249	0.1248	0.1247	0.1246
	H	0.0799	0.0804	0.0809	0.0814	0.0819	0.0824	0.0830	0.0836
5/16	T	0.1562	0.1562	0.1562	0.1561	0.1561	0.1560	0.1559	0.1558
	H	0.0999	0.1006	0.1012	0.1018	0.1023	0.1030	0.1038	0.1045
3/8	T	0.1875	0.1875	0.1874	0.1873	0.1873	0.1872	0.1871	0.1870
	H	0.1199	0.1207	0.1214	0.1221	0.1228	0.1236	0.1245	0.1254
7/16	T	0.2187	0.2187	0.2186	0.2186	0.2185	0.2184	0.2183	0.2181
	H	0.1399	0.1408	0.1416	0.1425	0.1433	0.1443	0.1453	0.1464
1/2	T	0.2500	0.2500	0.2499	0.2498	0.2498	0.2496	0.2495	0.2493
	H	0.1599	0.1609	0.1619	0.1629	0.1638	0.1649	0.1661	0.1673
9/16	T	0.2812	0.2812	0.2811	0.2810	0.2810	0.2808	0.2806	0.2804
	H	0.1799	0.1810	0.1821	0.1832	0.1842	0.1855	0.1868	0.1882
5/8	T	0.3125	0.3125	0.3123	0.3123	0.3122	0.3120	0.3118	0.3116
	H	0.1998	0.2012	0.2023	0.2036	0.2047	0.2061	0.2076	0.2091
11/16	T	0.3437	0.3437	0.3436	0.3435	0.3434	0.3432	0.3430	0.3427
	H	0.2198	0.2213	0.2226	0.2239	0.2252	0.2267	0.2283	0.2300
3/4	T	0.3750	0.3750	0.3748	0.3747	0.3747	0.3744	0.3742	0.3740
	H	0.2398	0.2414	0.2428	0.2443	0.2457	0.2473	0.2491	0.2509
13/16	T	0.4062	0.4062	0.4060	0.4059	0.4059	0.4056	0.4054	0.4050
	H	0.2598	0.2615	0.2631	0.2647	0.2661	0.2679	0.2699	0.2718
7/8	T	0.4375	0.4375	0.4373	0.4372	0.4371	0.4368	0.4366	0.4362
	H	0.2798	0.2816	0.2833	0.2850	0.2866	0.2885	0.2906	0.2927
15/16	T	0.4687	0.4687	0.4685	0.4684	0.4683	0.4680	0.4678	0.4674
	H	0.2998	0.3018	0.3035	0.3054	0.3071	0.3092	0.3114	0.3137
1	T	0.5000	0.5000	0.4998	0.4997	0.4996	0.4993	0.4990	0.4986
	H	0.3198	0.3219	0.3238	0.3258	0.3276	0.3298	0.3322	0.3346
1 1/8	T	0.5625	0.5625	0.5623	0.5621	0.5620	0.5617	0.5613	0.5610
	H	0.3597	0.3621	0.3642	0.3665	0.3685	0.3710	0.3737	0.3764
1 1/4	T	0.6250	0.6250	0.6247	0.6246	0.6245	0.6241	0.6237	0.6232
	H	0.3997	0.4023	0.4047	0.4072	0.4095	0.4122	0.4152	0.4182
1 3/8	T	0.6875	0.6875	0.6872	0.6870	0.6869	0.6865	0.6861	0.6856
	H	0.4397	0.4426	0.4452	0.4479	0.4504	0.4534	0.4567	0.4600
1 1/2	T	0.7500	0.7500	0.7497	0.7495	0.7494	0.7489	0.7485	0.7480
	H	0.4797	0.4828	0.4857	0.4887	0.4914	0.4947	0.4983	0.5019
1 3/4	T	0.8750	0.8750	0.8746	0.8744	0.8743	0.8737	0.8732	0.8726
	H	0.5596	0.5633	0.5666	0.5701	0.5733	0.5771	0.5813	0.5855
2	T	1.0000	1.0000	0.9996	0.9994	0.9992	0.9986	0.9980	0.9972
	H	0.6396	0.6438	0.6476	0.6516	0.6552	0.6596	0.6644	0.6692
2 1/4	T	1.1250	1.1250	1.1246	1.1242	1.1240	1.1234	1.1226	1.1220
	H	0.7195	0.7242	0.7285	0.7330	0.7371	0.7420	0.7474	0.7528
2 1/2	T	1.2500	1.2500	1.2494	1.2492	1.2490	1.2482	1.2474	1.2464
	H	0.7995	0.8047	0.8095	0.8145	0.8190	0.8245	0.8305	0.8365
3	T	1.5000	1.5000	1.4994	1.4990	1.4990	1.4978	1.4970	1.4960
	H	0.9594	0.9657	0.9714	0.9774	0.9828	0.9894	0.9966	1.0038

Copyright 2004, Industrial Press, Inc., New York, NY

Chordal Thickness of Tooth when Outside Diameter is Special.— When the outside diameter is larger or smaller than standard the chordal thickness at the standard pitch diameter is found by the following formula where t_c = chordal thickness at the standard pitch diameter D; t = circular thickness at the standard pitch diameter of the enlarged pinion or reduced gear being measured.

$$t_c = t - \frac{t^3}{6 \times D^2}$$

Example 1: The outside diameter of a pinion having 10 teeth of 5 diametral pitch has been *enlarged* by 0.2746 inch. This enlargement has increased the circular tooth thickness at the standard pitch diameter (as determined by the formula previously given) to 0.3852 inch. Find the equivalent chordal thickness.

$$t_c = 0.3852 - \frac{0.385^3}{6 \times 2^2} = 0.3852 - 0.0024 = 0.3828 \text{ inch}$$

(The error introduced by rounding the circular thickness to three significant figures before cubing it only affects the fifth decimal place in the result.)

Example 2: A gear having 30 teeth is to mesh with the pinion in Example 1 and is *reduced* so that the circular tooth thickness at the standard pitch diameter is 0.2432 inch. Find the equivalent chordal thickness.

$$t_c = 0.2432 - \frac{0.243^3}{6 \times 6^2} = 0.2432 - 0.00007 = 0.2431 \text{ inch}$$

Chordal Addendum.— In measuring the chordal thickness, the vertical scale of a gear tooth caliper is set to the chordal or "corrected" addendum to locate the caliper jaws at the pitch line (see *Method of setting a gear tooth caliper* on page 2052). The simplified formula which follows may be used in determining the chordal addendum either when the addendum is standard for full-depth or stub teeth or when the addendum is either longer or shorter than standard as in case of an enlarged pinion or a gear which is to mesh with an enlarged pinion and has a reduced addendum to maintain the standard center distance. If a_c = chordal addendum; a = addendum; and t = circular thickness of tooth at pitch diameter D; then,

$$a_c = a + \frac{t^2}{4D}$$

Example 1: The outside diameter of an 8 diametral pitch 14-tooth pinion with 20-degree full-depth teeth is to be increased by using an enlarged addendum of 1.234 ÷ 8 = 0.1542 inch (see Table 7 on page 2050). The basic tooth thickness of the enlarged pinion is 1.741 ÷ 8 = 0.2176 inch. What is the chordal addendum?

$$\text{Chordal addendum} = 0.1542 + \frac{0.2176^2}{4 \times (14 \div 8)} = 0.1610 \text{ inch}$$

Example 2: The outside diameter of a 14½-degree pinion having 12 teeth of 2 diametral pitch is to be enlarged 0.624 inch to avoid undercut (see Table 8 on page 2050), thus increasing the addendum from 0.5000 to 0.8120 inch and the arc thickness at the pitch line from 0.7854 to 0.9467 inch. Then,

$$\text{Chordal addendum of pinion} = 0.8120 + \frac{0.9467^2}{4 \times (12 \div 2)} = 0.8493 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Addendums and Tooth Thicknesses for Coarse-Pitch Long-Addendum Pinions and their Mating Short-Addendum Gears—20- and 25-degree Pressure Angles *ANSI B6.1-1968 (R1974)*

Number of Teeth in Pinion	Addendum		Basic Tooth Thickness		Number of Teeth in Gear
	Pinion	Gear	Pinion	Gear	
N_P	a_P	a_G	t_P	t_G	N_G (min)
20-Degree Involute Full Depth Tooth Form (Less than 20 Diametral Pitch)					
10	1.468	.532	1.912	1.230	25
11	1.409	.591	1.868	1.273	24
12	1.351	.649	1.826	1.315	23
13	1.292	.708	1.783	1.358	22
14	1.234	.766	1.741	1.400	21
15	1.175	.825	1.698	1.443	20
16	1.117	.883	1.656	1.486	19
17	1.058	.942	1.613	1.529	18
25-Degree Involute Full Depth Tooth Form (Less than 20 Diametral Pitch)					
10	1.184	.816	1.742	1.399	15
11	1.095	.905	1.659	1.482	14

All values are for 1 diametral pitch. For any other sizes of teeth all linear dimensions should be divided by the diametral pitch. Basic tooth thicknesses do not include an allowance for backlash.

Table 8. Enlarged Pinion and Reduced Gear Dimensions to Avoid Interference Coarse Pitch 14½-degree Involute Full Depth Teeth

Number of Pinion Teeth	Changes in Pinion and Gear Diameters	Circular Tooth Thickness		Min. No. of Teeth in Mating Gear	
		Pinion	Mating Gear	To Avoid Undercut	For Full Involute Action
10	1.3731	1.9259	1.2157	54	27
11	1.3104	1.9097	1.2319	53	27
12	1.2477	1.8935	1.2481	52	28
13	1.1850	1.8773	1.2643	51	28
14	1.1223	1.8611	1.2805	50	28
15	1.0597	1.8449	1.2967	49	28
16	0.9970	1.8286	1.3130	48	28
17	0.9343	1.8124	1.3292	47	28
18	0.8716	1.7962	1.3454	46	28
19	0.8089	1.7800	1.3616	45	28
20	0.7462	1.7638	1.3778	44	28
21	0.6835	1.7476	1.3940	43	28
22	0.6208	1.7314	1.4102	42	27
23	0.5581	1.7151	1.4265	41	27
24	0.4954	1.6989	1.4427	40	27
25	0.4328	1.6827	1.4589	39	26
26	0.3701	1.6665	1.4751	38	26
27	0.3074	1.6503	1.4913	37	26
28	0.2447	1.6341	1.5075	36	25
29	0.1820	1.6179	1.5237	35	25
30	0.1193	1.6017	1.5399	34	24
31	0.0566	1.5854	1.5562	33	24

All dimensions are given in inches and are for 1 diametral pitch. For other pitches divide tabular values by desired diametral pitch.

Add to the standard outside diameter of the pinion the amount given in the second column of the table divided by the desired diametral pitch, and (to maintain standard center distance) subtract the same amount from the outside diameter of the mating gear. Long addendum pinions will mesh with standard gears, but the center distance will be greater than standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 3: The outside diameter of the mating gear for the pinion in Example 3 is to be reduced 0.624 inch. The gear has 60 teeth and the addendum is reduced from 0.5000 to 0.1881 inch (to maintain the standard center distance), thus reducing the arc thickness to 0.6240 inch. Then,

$$\text{Chordal addendum of gear} = 0.1881 + \frac{0.6240^2}{4 \times (60 \div 2)} = 0.1913 \text{ inch}$$

When a gear addendum is reduced as much as the mating pinion addendum is enlarged, the minimum number of gear teeth required to prevent undercutting depends upon the enlargement of the mating pinion. To illustrate, if a 14½-degree pinion with 13 teeth is enlarged 1.185 inches, then the reduced mating gear should have a minimum of 51 teeth to avoid undercut (see Table 8 on page 2050).

Tables for Chordal Thicknesses and Chordal Addenda of Milled, Full-depth Teeth.— Two convenient tables for checking gears with milled, full-depth teeth are given on pages 2047 and 2048. The first shows chordal thicknesses and chordal addenda for the lowest number of teeth cut by gear cutters Nos. 1 through 8, and for the commonly used diametral pitches. The second gives similar data for commonly used circular pitches. In each case the data shown are accurate for the number of gear teeth indicated, but are approximate for other numbers of teeth within the range of the cutter under which they appear in the table. For the higher diametral pitches and lower circular pitches, the error introduced by using the data for any tooth number within the range of the cuuter under which it appears is comparatively small. The chordal thicknesses and chordal addenda for gear cutters Nos. 1 through 8 of the more commonly used diametral and circular pitches can be obtained from the table and formulas on pages 2047 and 2048.

Caliper Measurement of Gear Tooth.— In cutting gear teeth, the general practice is to adjust the cutter or hob until it grazes the outside diameter of the blank; the cutter is then sunk to the total depth of the tooth space plus whatever slight additional amount may be required to provide the necessary play or backlash between the teeth. (For recommendations concerning backlash and excess depth of cut required, see *Backlash* starting on page 2067.) If the outside diameter of the gear blank is correct, the tooth thickness should also be correct after the cutter has been sunk to the depth required for a given pitch and backlash. However, it is advisable to check the tooth thickness by measuring it, and the vernier gear-tooth caliper (see following illustration) is commonly used in measuring the thickness.

The vertical scale of this caliper is set so that when it rests upon the top of the tooth as shown, the lower ends of the caliper jaws will be at the height of the pitch circle; the horizontal scale then shows the chordal thickness of the tooth at this point. If the gear is being cut on a milling machine or with the type of gear-cutting machine employing a formed milling cutter, the tooth thickness is checked by first taking a trial cut for a short distance at one side of the blank; then the gear blank is indexed for the next space and another cut is taken far enough to mill the full outline of the tooth. The tooth thickness is then measured.

Before the gear-tooth caliper can be used, it is necessary to determine the correct chordal thickness and also the chordal addendum (or "corrected addendum" as it is sometimes called). The vertical scale is set to the chordal addendum, thus locating the ends of the jaws at the height of the pitch circle. The rules or formulas to use in determining the chordal thickness and chordal addendum will depend upon the outside diameter of the gear; for example, if the outside diameter of a small pinion is enlarged to avoid undercut and improve the tooth action, this must be taken into account in figuring the chordal thickness and chordal addendum as shown by the accompanying rules. The detail of a gear tooth included with the gear-tooth caliper illustration, represents the chordal thickness T, the addendum S, and the chordal addendum H. For the caliper measurements over two or more teeth see *Checking Spur Gear Size by Chordal Measurement Over Two or More Teeth* starting on page 2140.

Copyright 2004, Industrial Press, Inc., New York, NY



Method of setting a gear tooth caliper

Selection of Involute Gear Milling Cutter for a Given Diametral Pitch and Number of Teeth.— When gear teeth are cut by using formed milling cutters, the cutter must be selected to suit both the pitch and the number of teeth, because the shapes of the tooth spaces vary according to the number of teeth. For instance, the tooth spaces of a small pinion are not of the same shape as the spaces of a large gear of equal pitch. Theoretically, there should be a different formed cutter for every tooth number, but such refinement is unnecessary in practice. The involute formed cutters commonly used are made in series of eight cutters for each diametral pitch (see *Series of Involute, Finishing Gear Milling Cutters for Each Pitch*). The shape of each cutter in this series is correct for a certain number of teeth only, but it can be used for other numbers within the limits given. For instance, a No. 6 cutter may be used for gears having from 17 to 20 teeth, but the tooth outline is correct only for 17 teeth or the lowest number in the range, which is also true of the other cutters listed. When this cutter is used for a gear having, say, 19 teeth, too much material is removed from the upper surfaces of the teeth, although the gear meets ordinary requirements. When greater accuracy of tooth shape is desired to ensure smoother or quieter operation, an intermediate series of cutters having half-numbers may be used provided the number of gear teeth is between the number listed for the regular cutters (see *Series of Involute, Finishing Gear Milling Cutters for Each Pitch*).

Involute gear milling cutters are designed to cut a composite tooth form, the center portion being a true involute while the top and bottom portions are cycloidal. This composite form is necessary to prevent tooth interference when milled mating gears are meshed with each other. Because of their composite form, milled gears will not mate satisfactorily enough for high grade work with those of generated, full-involute form. Composite form hobs are available, however, which will produce generated gears that mesh with those cut by gear milling cutters.

Metric Module Gear Cutters: The accompanying table for selecting the cutter number to be used to cut a given number of teeth may be used also to select metric module gear cutters except that the numbers are designated in reverse order. For example, cutter No. 1, in the metric module system, is used for 12–13 teeth, cutter No. 2 for 14–16 teeth, etc.

Increasing Pinion Diameter to Avoid Undercut or Interference.— On coarse-pitch pinions with small numbers of teeth (10 to 17 for 20-degree and 10 and 11 for 25-degree pressure angle involute tooth forms) undercutting of the tooth profile or fillet interference with the tip of the mating gear can be avoided by making certain changes from the standard tooth proportions that are specified in Table 3 on page 2038. These changes consist essen-

Copyright 2004, Industrial Press, Inc., New York, NY

Circular Pitch in Gears—Pitch Diameters, Outside Diameters, and Root Diameters

For any particular circular pitch and number of teeth, use the table as shown in the example to find the pitch diameter, outside diameter, and root diameter. *Example:* Pitch diameter for 57 teeth of 6-inch circular pitch = 10 × pitch diameter given under factor for 5 teeth plus pitch diameter given under factor for 7 teeth. (10 × 9.5493) + 13.3690 = 108.862 inches.

Outside diameter of gear equals pitch diameter plus outside diameter factor from next-to-last column in table = 108.862 + 3.8197 = 112.682 inches.

Root diameter of gear equals pitch diameter minus root diameter factor from last column in table = 108.862 − 4.4194 = 104.443 inches.

Circular Pitch in Inches	Factor for Number of Teeth									Outside Dia. Factor	Root Diameter Factor
	1	2	3	4	5	6	7	8	9		
	Pitch Diameter Corresponding to Factor for Number of Teeth										
6	1.9099	3.8197	5.7296	7.6394	9.5493	11.4591	13.3690	15.2788	17.1887	3.8197	4.4194
5½	1.7507	3.5014	5.2521	7.0028	8.7535	10.5042	12.2549	14.0056	15.7563	3.5014	4.0511
5	1.5915	3.1831	4.7746	6.3662	7.9577	9.5493	11.1408	12.7324	14.3239	3.1831	3.6828
4½	1.4324	2.8648	4.2972	5.7296	7.1620	8.5943	10.0267	11.4591	12.8915	2.8648	3.3146
4	1.2732	2.5465	3.8197	5.0929	6.3662	7.6394	8.9127	10.1859	11.4591	2.5465	2.9463
3½	1.1141	2.2282	3.3422	4.4563	5.5704	6.6845	7.7986	8.9127	10.0267	2.2282	2.5780
3	0.9549	1.9099	2.8648	3.8197	4.7746	5.7296	6.6845	7.6394	8.5943	1.9099	2.2097
2½	0.7958	1.5915	2.3873	3.1831	3.9789	4.7746	5.5704	6.3662	7.1620	1.5915	1.8414
2	0.6366	1.2732	1.9099	2.5465	3.1831	3.8197	4.4563	5.0929	5.7296	1.2732	1.4731
1⅞	0.5968	1.1937	1.7905	2.3873	2.9841	3.5810	4.1778	4.7746	5.3715	1.1937	1.3811
1¾	0.5570	1.1141	1.6711	2.2282	2.7852	3.3422	3.8993	4.4563	5.0134	1.1141	1.2890
1⅝	0.5173	1.0345	1.5518	2.0690	2.5863	3.1035	3.6208	4.1380	4.6553	1.0345	1.1969
1½	0.4775	0.9549	1.4324	1.9099	2.3873	2.8648	3.3422	3.8197	4.2972	0.9549	1.1049
1⁷⁄₁₆	0.4576	0.9151	1.3727	1.8303	2.2878	2.7454	3.2030	3.6606	4.1181	0.9151	1.0588
1⅜	0.4377	0.8754	1.3130	1.7507	2.1884	2.6261	3.0637	3.5014	3.9391	0.8754	1.0128
1⁵⁄₁₆	0.4178	0.8356	1.2533	1.6711	2.0889	2.5067	2.9245	3.3422	3.7600	0.8356	0.9667
1¼	0.3979	0.7958	1.1937	1.5915	1.9894	2.3873	2.7852	3.1831	3.5810	0.7958	0.9207
1³⁄₁₆	0.3780	0.7560	1.1340	1.5120	1.8900	2.2680	2.6459	3.0239	3.4019	0.7560	0.8747
1⅛	0.3581	0.7162	1.0743	1.4324	1.7905	2.1486	2.5067	2.8648	3.2229	0.7162	0.8286
1¹⁄₁₆	0.3382	0.6764	1.0146	1.3528	1.6910	2.0292	2.3674	2.7056	3.0438	0.6764	0.7826
1	0.3183	0.6366	0.9549	1.2732	1.5915	1.9099	2.2282	2.5465	2.8648	0.6366	0.7366
¹⁵⁄₁₆	0.2984	0.5968	0.8952	1.1937	1.4921	1.7905	2.0889	2.3873	2.6857	0.5968	0.6905
⅞	0.2785	0.5570	0.8356	1.1141	1.3926	1.6711	1.9496	2.2282	2.5067	0.5570	O.6445
¹³⁄₁₆	0.2586	0.5173	0.7759	1.0345	1.2931	1.5518	1.8104	2.0690	2.3276	0.5173	0.5985
¾	0.2387	0.4775	0.7162	0.9549	1.1937	1.4324	1.6711	1.9099	2.1486	0.4775	0.5524
¹¹⁄₁₆	0.2188	0.4377	0.6565	0.8754	1.0942	1.3130	1.5319	1.7507	1.9695	0.4377	0.5064
⅔	0.2122	0.4244	0.6366	0.8488	1.0610	1.2732	1.4854	1.6977	1.9099	0.4244	0.4910
⅝	0.1989	0.3979	0.5968	0.7958	0.9947	1.1937	1.3926	1.5915	1.7905	0.3979	0.4604
⁹⁄₁₆	0.1790	0.3581	0.5371	0.7162	0.8952	1.0743	1.2533	1.4324	1.6114	0.3581	0.4143
½	0.1592	0.3183	0.4775	0.6366	0.7958	0.9549	1.1141	1.2732	1.4324	0.3183	0.3683
⁷⁄₁₆	0.1393	0.2785	0.4178	0.5570	0.6963	0.8356	0.9748	1.1141	1.2533	0.2785	0.3222
⅜	0.1194	0.2387	0.3581	0.4775	0.5968	0.7162	0.8356	0.9549	1.0743	0.2387	0.2762
⅓	0.1061	0.2122	0.3183	0.4244	0.5305	0.6366	0.7427	0.8488	0.9549	0.2122	0.2455
⁵⁄₁₆	0.0995	0.1989	0.2984	0.3979	0.4974	0.5968	0.6963	0.7958	0.8952	0.1989	0.2302
¼	0.0796	0.1592	0.2387	0.3183	0.3979	0.4775	0.5570	0.6366	0.7162	0.1592	0.1841
³⁄₁₆	0.0597	0.1194	0.1790	0.2387	0.2984	0.3581	0.4178	0.4775	0.5371	0.1194	0.1381
⅛	0.0398	0.0796	0.1194	0.1592	0.1989	0.2387	0.2785	0.3183	0.3581	0.0796	0.0921
¹⁄₁₆	0.0199	0.0398	0.0597	0.0796	0.0995	0.1194	0.1393	0.1592	0.1790	0.0398	0.0460

tially in increasing the addendum and hence the outside diameter of the pinion and decreasing the addendum and hence the outside diameter of the mating gear. These changes in outside diameters of pinion and gear do not change the velocity ratio or the procedures in cutting the teeth on a hobbing machine or generating type of shaper or planer.

Data in Table 7 on page 2050 are taken from ANSI Standard B6.1-1968, reaffirmed 1974, and show for 20-degree and 25-degree full-depth standard tooth forms, respectively, the addendums and tooth thicknesses for long addendum pinions and their mating short

Copyright 2004, Industrial Press, Inc., New York, NY

addendum gears when the number of teeth in the pinion is as given. Similar data for former standard 14½-degree full-depth teeth (20 diametral pitch and coarser) are given in Table 8 on page 2050.

Example: A 14-tooth, 20-degree pressure angle pinion of 6 diametral pitch is to be enlarged. What will be the outside diameters of the pinion and a 60-tooth mating gear? If the mating gear is to have the minimum number of teeth to avoid undercut, what will be its outside diameter?

$$D_o(\text{ pinion}) = \frac{N_P}{P} + 2a = \frac{14}{6} + 2\left(\frac{1.234}{6}\right) = 2.745 \text{ inches}$$

$$D_o(\text{ gear}) = \frac{N_G}{P} + 2a = \frac{60}{6} + 2\left(\frac{0.766}{6}\right) = 10.255 \text{ inches}$$

For a mating gear with minimum number of teeth to avoid undercut:

$$D_o(\text{ gear}) = \frac{N_G}{P} + 2a = \frac{21}{6} + 2\left(\frac{0.766}{6}\right) = 3.755 \text{ inches}$$

Series of Involute, Finishing Gear Milling Cutters for Each Pitch

Number of Cutter	Will cut Gears from	Number of Cutter	Will cut Gears from
1	135 teeth to a rack	5	21 to 25 teeth
2	55 to 134 teeth	6	17 to 20 teeth
3	35 to 54 teeth	7	14 to 16 teeth
4	26 to 34 teeth	8	12 to 13 teeth
The regular cutters listed above are used ordinarily. The cutters listed below (an intermediate series having half numbers) may be used when greater accuracy of tooth shape is essential in cases where the number of teeth is between the numbers for which the regular cutters are intended.			
Number of Cutter	Will cut Gears from	Number of Cutter	Will cut Gears from
1½	80 to 134 teeth	5½	19 to 20 teeth
2½	42 to 54 teeth	6½	15 to 16 teeth
3½	30 to 34 teeth	7½	13 teeth
4½	23 to 25 teeth	…	…

Roughing cutters are made with No. 1 form only. Dimensions of roughing and finishing cutters are given on page 816. Dimensions of cutters for bevel gears are given on page 817.

Enlarged Fine-Pitch Pinions: American Standard ANSI B6.7–1977, Information Sheet A provides a different system for 20-degree pressure angle pinion enlargement than is used for coarse-pitch gears. Pinions with 11 through 23 teeth (9 through 14 teeth for 25-degree pressure angle) are enlarged so that a standard tooth thickness rack with addendum $1.05/P$ will start contact 5° of roll above the base circle radius. The use of $1.05/P$ for the addendum allows for center distance variation and eccentricity of the mating gear outside diameter; the 5° roll angle avoids the fabrication of the involute in the troublesome area near the base circle.

Pinions with less than 11 teeth (9 teeth for 25-degree pressure angle) are enlarged to the extent that the highest point of undercut coincides with the start of contact with the standard rack described previously. The height of undercut considered is that produced by a sharp-cornered 120 pitch hob. Pinions with less than 13 teeth (11 teeth for 25-degree pressure angle) are truncated to provide a top land of $0.275/P$. Data for enlarged pinions may be found in Tables 9a, 9b, 9c, and 9d.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9a. Increase in Dedendum, Δ for 20 -, and 25 -Degree Pressure Angle Fine-Pitch Enlarged Pinions and Reduced Gears *ANSI B6. 7-1977*

Diametral Pitch, *P*	Δ	Diametral Pitch, *P*	Δ	Diametral Pitch, *P*	Δ	Diametral Pitch, *P*	Δ	Diametral Pitch, *P*	Δ
20	0.0000	32	0.0007	48	0.0012	72	0.0015	96	0.0016
24	0.0004	40	0.0010	64	0.0015	80	0.0015	120	0.0017

Δ = increase in standard dedendum to provide increased clearance. See footnote to Table 9d.

Table 9b. Dimensions Required when Using Enlarged, Fine-pitch, 14½-Degree Pressure Angle Pinions *ANSI B6.7-1977, Information Sheet B*

Enlarged Pinion			Standard Center-distance System (Long and Short Addendum)				Enlarged Center-distance System		
			Reduced Mating Gear				Enlarged Pinion Mating with St'd. Gear	Two Equal Enlarged Mating Pinions[a]	
No. of Teeth *n*	Outside Diameter	Cir. Tooth Thickness at Standard Pitch Dia.	Decrease in Standard Outside Dia.[b]	Cir. Tooth Thickness at Standard Pitch Dia.	Recommended Minimum No. of Teeth *N*	Contact Ratio, *n* Mating with *N*	Increase over St'd. Center Distance		Contact Ratio of Two Equal Enlarged Mating Pinions
10	13.3731	1.9259	1.3731	1.2157	54	1.831	0.6866	1.3732	1.053
11	14.3104	1.9097	1.3104	1.2319	53	1.847	0.6552	1.3104	1.088
12	15.2477	1.8935	1.2477	1.2481	52	1.860	0.6239	1.2477	1.121
13	16.1850	1.8773	1.1850	1.2643	51	1.873	0.5925	1.1850	1.154
14	17.1223	1.8611	1.1223	1.2805	50	1.885	0.5612	1.2223	1.186
15	18.0597	1.8448	1.0597	1.2967	49	1.896	0.5299	1.0597	1.217
16	18.9970	1.8286	0.9970	1.3130	48	1.906	0.4985	0.9970	1.248
17	19.9343	1.8124	0.9343	1.3292	47	1.914	0.4672	0.9343	1.278
18	20.8716	1.7962	0.8716	1.3454	46	1.922	0.4358	0.8716	1.307
19	21.8089	1.7800	0.8089	1.3616	45	1.929	0.4045	0.8089	1.336
20	22.7462	1.7638	0.7462	1.3778	44	1.936	0.3731	0.7462	1.364
21	23.6835	1.7476	0.6835	1.3940	43	1.942	0.3418	0.6835	1.392
22	24.6208	1.7314	0.6208	1.4102	42	1.948	0.3104	0.6208	1.419
23	25.5581	1.7151	0.5581	1.4265	41	1.952	0.2791	0.5581	1.446
24	26.4954	1.6989	0.4954	1.4427	40	1.956	0.2477	0.4954	1.472
25	27.4328	1.6827	0.4328	1.4589	39	1.960	0.2164	0.4328	1.498
26	28.3701	1.6665	0.3701	1.4751	38	1.963	0.1851	0.3701	1.524
27	29.3074	1.6503	0.3074	1.4913	37	1.965	0.1537	0.3074	1.549
28	30.2447	1.6341	0.2448	1.5075	36	1.967	0.1224	0.2448	1.573
29	31.1820	1.6179	0.1820	1.5237	35	1.969	0.0910	0.1820	1.598
30	32.1193	1.6017	0.1193	1.5399	34	1.970	0.0597	0.1193	1.622
31	33.0566	1.5854	0.0566	1.5562	33	1.971	0.0283	0.0566	1.646

[a] If enlarged mating pinions are of unequal size, the center distance is increased by an amount equal to one-half the sum of their increase over standard outside diameters. Data in this column are not given in the standard.

[b] To maintain standard center distance when using an enlarged pinion, the mating gear diameter must be decreased by the amount of the pinion enlargement.

All dimensions are given in inches and are for 1 diametral pitch. For other pitches divide tabulated dimensions by the diametrical pitch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9c. Tooth Proportions Recommended for Enlarging Fine-Pitch Pinions of 20-Degree Pressure Angle—20 Diametral Pitch and Finer *ANSI B6.7-1977*

Enlarged Pinion Dimensions					Enlarged C.D. System Pinion Mating with Standard Gear		Standard Center Distance (Long and Short Addendums) Reduced Gear Dimensions				
Number of Teeth,[a] n	Outside Diameter, D_{oP}	Addendum, a_P	Basic Tooth Thickness, t_P	Dedendum Based on 20 Pitch,[b] b_P	Contact Ratio Two Equal Pinions	Contact Ratio with a 24-Tooth Gear	Addendum, a_G	Basic Tooth Thickness, t_G	Dedendum Based on 20 Pitch,[b] b_G	Recommended Minimum No. of Teeth, N	Contact Ratio n Mating with N
7	10.0102	1.5051	2.14114	0.4565	0.697	1.003	0.2165	1.00045	2.0235	42	1.079
8	11.0250	1.5125	2.09854	0.5150	0.792	1.075	0.2750	1.04305	1.9650	40	1.162
9	12.0305	1.5152	2.05594	0.5735	0.893	1.152	0.3335	1.08565	1.9065	39	1.251
10	13.0279	1.5140	2.01355	0.6321	0.982	1.211	0.3921	1.12824	1.8479	38	1.312
11	14.0304	1.5152	1.97937	0.6787	1.068	1.268	0.4387	1.16222	1.8013	37	1.371
12	15.0296	1.5148	1.94703	0.7232	1.151	1.322	0.4832	1.19456	1.7568	36	1.427
13	15.9448	1.4724	1.91469	0.7676	1.193	1.353	0.5276	1.22690	1.7124	35	1.457
14	16.8560	1.4280	1.88235	0.8120	1.232	1.381	0.5720	1.25924	1.6680	34	1.483
15	17.7671	1.3836	1.85001	0.8564	1.270	1.408	0.6164	1.29158	1.6236	33	1.507
16	18.6782	1.3391	1.81766	0.9009	1.323	1.434	0.6609	1.32393	1.5791	32	1.528
17	19.5894	1.2947	1.78532	0.9453	1.347	1.458	0.7053	1.35627	1.5347	31	1.546
18	20.5006	1.2503	1.75298	0.9897	1.385	1.482	0.7497	1.38861	1.4903	30	1.561
19	21.4116	1.2058	1.72064	1.0342	1.423	1.505	0.7942	1.42095	1.4458	29	1.574
20	22.3228	1.1614	1.68839	1.0786	1.461	1.527	0.8386	1.45320	1.4014	28	1.584
21	23.2340	1.1170	1.65595	1.1230	1.498	1.548	0.8830	1.48564	1.3570	27	1.592
22	24.1450	1.0725	1.62361	1.1675	1.536	1.568	0.9275	1.51798	1.3125	26	1.598
23	25.0561	1.0281	1.59127	1.2119	1.574	1.588	0.9719	1.55032	1.2681	25	1.601
24	26.0000	1.0000	1.57080	1.2400	1.602	1.602	1.0000	1.57080	1.2400	24	1.602

[a] Caution should be exercised in the use of pinions above the horizontal lines. They should be checked for suitability, particularly in the areas of contact ratio (less than 1.2 is not recommended), center distance, clearance, and tooth strength.

[b] The actual dedendum is calculated by dividing the values in this column by the desired diametral pitch and then adding to the result an amount Δ found in Table 9a. As an example, a 20-degree pressure angle 7-tooth pinion meshing with a 42-tooth gear would have, for 24 diametral pitch, a dedendum of 0.4565 ÷ 24 + 0.0004 = 0.0194. The 42-tooth gear would have a dedendum of 2.0235 ÷ 24 + 0.004 = 0.0847 inch.

All dimensions are given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9d. Tooth Proportions Recommended for Enlarging Fine-Pitch Pinions of 25-Degree Pressure Angle—20 Diametral Pitch and Finer *ANSI B6.7-1977, Information Sheet B*

Enlarged Pinion Dimensions					Enlarged C.D. System Pinion Mating with Standard Gear		Standard Center Distance (Long and Short Addendums) Reduced Gear Dimensions				
Number of Teeth,[a] n	Outside Diameter, D_{oP}	Addendum, a_P	Basic Tooth Thickness, t_P	Dedendum Based on 20 Pitch, Dedendum Based on 20 Pitch, [b] b_P	Contact Ratio Two Equal Pinions	Contact Ratio with a 15-Tooth Gear	Addendum, a_G	Basic Tooth Thickness, t_G	Dedendum Based on 20 Pitch, [b] b_G	Recommended Minimum No. of Teeth, N	Contact Ratio n Mating with N
6	8.7645	1.3822	2.18362	0.5829	0.696	0.954	0.3429	0.95797	1.8971	24	1.030
7	9.7253	1.3626	2.10029	0.6722	0.800	1.026	0.4322	1.04130	1.8078	23	1.108
8	10.6735	1.3368	2.01701	0.7616	0.904	1.094	0.5216	1.12459	1.7184	22	1.177
9	11.6203	1.3102	1.94110	0.8427	1.003	1.156	0.6029	1.20048	1.6371	20	1.234
10	12.5691	1.2846	1.87345	0.9155	1.095	1.211	0.6755	1.26814	1.5645	19	1.282
11	13.5039	1.2520	1.80579	0.9880	1.183	1.261	0.7480	1.33581	1.4920	18	1.322
12	14.3588	1.1794	1.73813	1.0606	1.231	1.290	0.8206	1.40346	1.4194	17	1.337
13	15.2138	1.1069	1.67047	1.1331	1.279	1.317	0.8931	1.47112	1.3469	16	1.347
14	16.0686	1.0343	1.60281	1.2057	1.328	1.343	0.9657	1.53878	1.2743	15	1.352
15	17.0000	1.0000	1.57030	1.2400	1.358	1.358	1.0000	1.57080	1.2400	15	1.358

[a] Caution should be exercised in the use of pinions above the horizontal lines. They should be checked for suitability, particularly in the areas of contact ratio (less than 1.2 is not recommended), center distance, clearance, and tooth strength.

[b] The actual dedendum is calculated by dividing the values in this column by the desired diametral pitch and then adding to the result an amount Δ found in Table 9a. As an example, a 20-degree pressure angle 7-tooth pinion meshing with a 42-tooth gear would have, for 24 diametral pitch, a dedendum of 0.4565 ÷ 24 + 0.0004 = 0.0194. The 42-tooth gear would have a dedendum of 2.0235 ÷ 24 + 0.004 = 0.0847 inch.

All dimensions are given in inches.

All values are for 1 diametral pitch. For any other sizes of teeth, all linear dimensions should be divided by the diametral pitch.

Note: The tables in the ANSI B6.7-1977 standard also specify Form Diameter, Roll Angle to Form Diameter, and Top Land. These are not shown here. The top land is in no case less than 0.275/P. The form diameters and the roll angles to form diameter shown in the Standard are the values which should be met with a standard hob when generating the tooth thicknesses shown in the tables. These form diameters provides more than enough length of involute profile for any mating gear smaller than a rack. However,since these form diameters are based on gear tooth generation using standard hobs, they should impose little or no hardship on manufacture except in cases of the most critical quality levels. In such cases, form diameter specifications and master gear design should be based upon actual mating conditions.

Copyright 2004, Industrial Press, Inc., New York, NY

Minimum Number of Teeth to Avoid Undercutting by Hob.— The data in the above tables give tooth proportions for low numbers of teeth to avoid interference between the gear tooth tip and the pinion tooth flank. Consideration must also be given to possible undercutting of the pinion tooth flank by the hob used to cut the pinion. The minimum number of teeth N_{min} of standard proportion that may be cut without undercut is:

$N_{min} = 2P \csc^2 \phi [a_H - r_t(1 - \sin \phi)]$ where: a_H = cutter addendum; r_t = radius at cutter tip or corners; ϕ = cutter pressure angle; and P = diametral pitch.

Gear to Mesh with Enlarged Pinion.— Data in the fifth column of Table 8 show minimum number of teeth in a mating gear which can be cut with hob or rack type cutter without undercut, when outside diameter of gear has been reduced an amount equal to the pinion enlargement to retain the standard center distance. To calculate N for the gear, insert addendum a of enlarged mating pinion in the formula $N = 2a \times \csc^2\phi$.

Example: A gear is to mesh with a 24-tooth pinion of 1 diametral pitch which has been enlarged 0.4954 inch, as shown by the table. The pressure angle is 14½ degrees. Find minimum number of teeth N for reduced gear.

Pinion addendum = 1 + (0.4954 ÷ 2) = 1.2477

Hence, $N = 2 \times 1.2477 \times 15.95 = 39.8$ (use 40)

In the case of fine pitch gears with reduced outside diameters, the recommended minimum numbers of teeth given in Tables 9b, 9c, and 9d, are somewhat more than the minimum numbers required to prevent undercutting and are based upon studies made by the *American Gear Manufacturers Association*.

Standard Center-distance System for Enlarged Pinions.— In this system, sometimes referred to as "long and short addendums," the center distance is made standard for the numbers of teeth in pinion and gear. The outside diameter of the gear is decreased by the same amount that the outside of the pinion is enlarged.

The advantages of this system are: 1) No change in center distance or ratio is required; 2) The operating pressure angle remains standard; and 3) A slightly greater contact ratio is obtained than when the center distance is increased.

The disadvantages are 1) The gears as well as the pinion must be changed from standard dimensions; 2) Pinions having fewer than the minimum number of teeth to avoid undercut cannot be satisfactorily meshed together; and 3) In most cases where gear trains include idler gears, the standard center-distance system cannot be used.

Enlarged Center-distance System for Enlarged Pinions.— If an enlarged pinion is meshed with another enlarged pinion or with a gear of standard outside diameter, the center distance must be increased. For fine-pitch gears, it is usually satisfactory to increase the center distance by an amount equal to one-half of the enlargements (see eighth column of Table 9b). This is an approximation as theoretically there is a slight increase in backlash.

The advantages of this system are: 1) Only the pinions need be changed from the standard dimensions; 2) Pinions having fewer than 18 teeth may engage other pinions in this range; 3) The pinion tooth, which is the weaker member, is made stronger by the enlargement; and 4) The tooth contact stress, which controls gear durability, is lowered by being moved away from the pinion base circle.

The disadvantages are: 1) Center distances must be enlarged over the standard; 2) The operating pressure angle increases slightly with different combinations of pinions and gears, which is usually not important; and 3) The contact ratio is slightly smaller than that obtained with the standard center-distance system.

This consideration is of minor importance as in the worst case the loss is approximately only 6 per cent.

Enlarged Pinions Meshing without Backlash: When two enlarged pinions are to mesh without backlash, their center distance will be greater than the standard and less than that

Copyright 2004, Industrial Press, Inc., New York, NY

for the enlarged center-distance system. This center distance may be calculated by the formulas given in the following section.

Center Distance at Which Modified Mating Spur Gears Will Mesh with No Backlash.— When the tooth thickness of one or both of a pair of mating spur gears has been increased or decreased from the standard value ($\pi \div 2P$), the center distance at which they will mesh tightly (without backlash) may be calculated from the following formulas:

$$\text{inv}\,\phi_1 = \text{inv}\,\phi + \frac{P(t+T)-\pi}{n+N}$$

$$C = \frac{n+N}{2P}$$

$$C_1 = \frac{\cos\phi}{\cos\phi_1} \times C$$

In these formulas, P = diametral pitch; n = number of teeth in pinion; N = number of teeth in gear; t and T are the actual tooth thicknesses of the pinion and gear, respectively, on their standard pitch circles; inv ϕ = involute function of standard pressure angle of gears; C = standard center distance for the gears; C_1 = center distance at which the gears mesh without backlash; and inv ϕ_1 = involute function of operating pressure angle when gears are meshed tightly at center distance C_1.

Example: Calculate the center distance for no backlash when an enlarged 10-tooth pinion of 100 diametral pitch and 20-degree pressure angle is meshed with a standard 30-tooth gear, the circular tooth thickness of the pinion and gear, respectively, being 0.01873 and 0.015708 inch.

$$\text{inv}\,\phi_1 = \text{inv}\,20^\circ + \frac{100(0.01873+0.015708)-\pi}{(10+30)}$$

From the table of involute functions, inv 20-degrees = 0.014904. Therefore,

$$\text{inv}\,\phi_1 = 0.014904 + \frac{0.34438-0.31416}{4} = 0.022459$$

$$\phi_1 = 22^\circ 49' \text{ from page 99}$$

$$C = \frac{n+N}{2P} = \frac{10+30}{2\times 100} = 0.2000 \text{ inch}$$

$$C_1 = \frac{\cos 20^\circ}{\cos 22^\circ 49'} \times 0.2000 = \frac{0.93969}{0.92175} \times 0.2000 = 0.2039 \text{ inch}$$

Contact Diameter.— For two meshing gears it is important to know the contact diameter of each. A first gear with number of teeth, n, and outside diameter, d_0, meshes at a standard center distance with a second gear with number of teeth, N, and outside diameter, D_0; both gears have a diametral pitch, P, and pressure angle, ϕ, a, A, b, and B are unnamed angles used only in the calculations. The contact diameter, d_c, is found by a three-step calculation that can be done by hand using a trigonometric table and a logarithmic table or a desk calculator. Slide rule calculation is not recommended because it is not accurate enough to give good results. The three-step formulas to find the contact diameter, d_c, of the first gear are:

$$\cos A = \frac{N\cos\phi}{D_o \times P} \quad (1)$$

$$\tan b = \tan\phi - \frac{N}{n}(\tan A - \tan\phi) \quad (2)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$d_c = \frac{n\cos\phi}{P\cos b} \tag{3}$$

Similarly the three-step formulas to find the contact diameter, D_c, of the second gear are:

$$\cos a = \frac{n\cos\phi}{d_o \times P} \tag{4}$$

$$\tan B = \tan\phi - \frac{n}{N}(\tan a - \tan\phi) \tag{5}$$

$$D_c = \frac{N\cos\phi}{P\cos B} \tag{6}$$

Contact Ratio.— The contact ratio of a pair of mating spur gears must be well over 1.0 to assure a smooth transfer of load from one pair of teeth to the next pair as the two gears rotate under load. Because of a reduction in contact ratio due to such factors as tooth deflection, tooth spacing errors, tooth tip breakage, and outside diameter and center distance tolerances, the contact ratio of gears for power transmission as a general rule should not be less than about 1.4. A contact ratio of as low as 1.15 may be used in extreme cases, provided the tolerance effects mentioned above are accounted for in the calculation. The formula for determining the contact ratio, m_f, using the nomenclature in the previous section is:

$$m_f = \frac{N}{6.28318}(\tan A - \tan B) \tag{7a}$$

or

$$m_f = \frac{N}{6.28318}(\tan a - \tan b) \tag{7b}$$

or

$$m_f = \frac{\sqrt{R_0^2 - R_B^2} + \sqrt{r_0^2 - r_B^2} - C\sin\theta}{P\cos\theta} \tag{7c}$$

where R_0 = outside radius of first gear; R_B = base radius of first gear ; r_0 = outside radius of second gear; r_B = base radius of second gear; C = center distance; I = pressure angle; and, p = circular pitch.

Both formulas Equations (7a) and Equations (7b) should give the same answer. It is good practice to use both formulas as a check on the previous calculations.

Lowest Point of Single Tooth Contact.— This diameter on the pinion (sometimes referred to as LPSTQ is used to find the maximum contact compressive stress (sometimes called the Hertz Stress) of a pair of mating spur gears. The two-step formulas for determining this pinion diameter, d_L, using the same nomenclature as in the previous sections with c and C as unnamed angles used only in the calculations are:

$$\tan c = \tan a - \frac{6.28318}{n} \tag{8}$$

$$d_L = \frac{n\cos\phi}{P\cos c} \tag{9}$$

In some cases it is necessary to have a plot of the compressive stress over the whole cycle of contact; in this case the LPSTC for the gear is required also. The similar two-step formulas for this gear diameter are:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\tan C = \tan A - \frac{6.28318}{N} \tag{10}$$

$$D_L = \frac{N \cos \phi}{P \cos C} \tag{11}$$

Maximum Hob Tip Radius.— The standard gear tooth proportions given by the formulas in Table 2 on page 2035 provide a specified size for the rack fillet radius in the general form of (a constant) × (pitch). For any given standard this constant may vary up to a maximum which it is geometrically impossible to exceed; this maximum constant, r_c (max), is found by the formula:

$$r_c \text{ (max)} = \frac{0.785398 \cos \phi - b \sin \phi}{1 - \sin \phi} \tag{12}$$

where b is the similar constant in the specified formula for the gear dedendum. The hob tip radius of any standard hob to finish cut any standard gear may vary from zero up to this limiting value.

Undercut Limit for Hobbed Involute Gears.— It is well to avoid designing and specifying gears that will have a hobbed trochoidal fillet that undercuts the involute gear tooth profile. This should be avoided because it may cause the involute profile to be cut away up to a point above the required contact diameter with the mating gear so that involute action is lost and the contact ratio reduced to a level that may be too low for proper conjugate action. An undercut fillet will also weaken the beam strength and thus raise the fillet tensile stress of the gear tooth. To assure that the hobbed gear tooth will not have an undercut fillet, the following formula must be satisfied:

$$\frac{b - r_c}{\sin \phi} + r_c \leq 0.5 n \sin \phi \tag{13}$$

where b is the dedendum constant; r_c is the hob or rack tip radius constant; n is the number of teeth in the gear; and ϕ is the gear and hob pressure angle. If the gear is not standard or the hob does not roll at the gear pitch diameter, this formula can not be applied and the determination of the expected existence of undercut becomes a considerably more complicated procedure.

Highest Point of Single Tooth Contact.— This diameter is used to place the maximum operating load for the determination of the gear tooth fillet stress. The two-step formulas for determining this diameter, d_H, of the pinion using the same nomenclature as in the previous sections with d and D as unnamed angles used only in the calculations are:

$$\tan d = \tan b + \frac{6.28318}{n} \tag{14}$$

$$d_H = \frac{n \cos \phi}{P \cos d} \tag{15}$$

Similarly for the gear:

$$\tan D = \tan B + \frac{6.28318}{N} \tag{16}$$

$$D_H = \frac{N \cos \phi}{P \cos D} \tag{17}$$

True Involute Form Diameter.— The point on the gear tooth at which the fillet and the involute profile are tangent to each other should be determined to assure that it lies at a smaller diameter than the required contact diameter with the mating gear. If the TIF diameter is larger than the contact diameter, then fillet interference will occur with severe damage to the gear tooth profile and rough action of the gear set. This two-step calculation is

Copyright 2004, Industrial Press, Inc., New York, NY

made by using the following two formulas with e and E as unnamed angles used only in the calculations:

$$\tan e = \tan\phi - \frac{4}{n}\left(\frac{b - r_c}{\sin 2\phi} + \frac{r_c}{2\cos\phi}\right) \quad (18)$$

$$d_{TIF} = \frac{n\cos\phi}{P\cos e} \quad (19)$$

As in the previous sections, ϕ is the pressure angle of the gear; n is the number of teeth in the pinion; b is the dedendum constant, r_c is the rack or hob tip radius constant, P is the gear diametral pitch and d_{TIF} is the true involute form diameter.

Similarly, for the mating gear:

$$\tan E = \tan\phi - \frac{4}{N}\left(\frac{b - r_c}{\sin 2\phi} + \frac{r_c}{2\cos\phi}\right) \quad (20)$$

$$D_{TIF} = \frac{N\cos\phi}{P\cos E} \quad (21)$$

where N is number of teeth in this mating gear and D_{TIF} is the true involute form diameter.

Profile Checker Settings.— The actual tooth profile tolerance will need to be determined on high performance gears that operate either at high unit loads or at high pitch-line velocity. This is done on an involute checker, a machine which requires two settings, the gear base radius and the roll angle in degrees to significant points on the involute. From the smallest diameter outward these significant points are: TIF, Contact Diameter, LPSTC, Pitch Diameter, HPSTC, and Outside Diameter.

The base radius is:

$$R_b = \frac{N\cos\phi}{2P} \quad (22)$$

The roll angle, in degrees, at any point is equal to the tangent of the pressure angle at that point multiplied by 57.2958. The following table shows the tangents to be used at each significant diameter.

Significant Point on Tooth Profile	Pinion	Gear	For Computation
TIF	tan e	tan E	(See Formulas (18) & (20))
Contact Dia.	tan b	tan B	(See Formulas (2) & (5))
LPSTC	tan c	tan C	(See Formulas (8) & (10))
Pitch Dia.	tan ϕ	tan ϕ	(ϕ = Pressure angle)
HPSTC	tan d	tan D	(See Formulas (14) & (16))
Outside Dia.	tan a	tan A	(See Formulas (4) & (1))

Example: Find the significant diameters, contact ratio and hob tip radius for a 10-diametral pitch, 23-tooth, 20-degree pressure angle pinion of 2.5-inch outside diameter if it is to mesh with a 31-tooth gear of 3.3-inch outside diameter.

Thus: $n = 23$
$d_O = 2.5$
$P = 10$
$N = 31$
$D_O = 3.3$
$\phi = 20°$

Copyright 2004, Industrial Press, Inc., New York, NY

1) Pinion contact diameter, d_c

$$\cos A = \frac{31 \times 0.93969}{3.3 \times 10} \tag{1}$$
$$= 0.88274 \qquad A = 28°1'30''$$

$$\tan b = 0.36397 - \frac{31}{23}(0.53227 - 0.36397) \tag{2}$$
$$= 0.13713 \qquad b = 7°48'26''$$

$$d_c = \frac{23 \times 0.93969}{10 \times 0.99073} \tag{3}$$
$$= 2.1815 \text{ inches}$$

2) Gear contact diameter, D_c

$$\cos a = \frac{23 \times 0.93963}{2.5 \times 10} \tag{4}$$
$$= 0.86452 \qquad a = 30°10'20''$$

$$\tan B = 0.36397 - \frac{23}{31}(0.58136 - 0.36937) \tag{5}$$
$$= 0.20267 \qquad B = 11°27'26''$$

$$D_c = \frac{31 \times 0.93969}{10 \times 0.98000} \tag{6}$$
$$= 2.9725 \text{ inches}$$

3) Contact ratio, m_f

$$m_f = \frac{31}{6.28318}(0.53227 - 0.20267) \tag{7a}$$
$$= 1.626$$

$$m_f = \frac{23}{6.28318}(0.58136 - 0.13713) \tag{7b}$$
$$= 1.626$$

4) Pinion LPSTC, d_L

$$\tan c = 0.58136 - \frac{6.28318}{23} \tag{8}$$
$$= 0.30818 \qquad c = 17°7'41''$$

$$d_L = \frac{23 \times 0.93969}{10 \times 0.95565} \tag{9}$$
$$= 2.2616 \text{ inches}$$

5) Gear LPSTC, D_L

$$\tan C = 0.53227 - \frac{6.28318}{31} \tag{10}$$
$$= 0.32959 \qquad C = 18°14'30''$$

$$D_L = \frac{31 \times 0.93969}{10 \times 0.94974} \tag{11}$$
$$= 3.0672 \text{ inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

6) Maximum permissible hob tip radius, r_c (max). The dedendum factor is 1.25.

$$r_c\ (\max) = \frac{0.785398 \times 0.93969 - 1.25 \times 0.34202}{1 - 0.34202} = 0.4719 \text{ inch} \quad (12)$$

7) If the hob tip radius r_c is 0.30, determine if the pinion involute is undercut.

$$\frac{1.25 - 0.30}{0.34202} + 0.30 \le 0.5 \times 23 \times 0.34202 \quad (13)$$

$$3.0776 < 3.9332$$

8) therefore there is no involute undercut.

9) Pinion HPSTC, D_H

$$\tan d = 0.13713 + \frac{6.28318}{23} = 0.41031 \qquad d = 22°18'32'' \quad (14)$$

$$d_H = \frac{23 \times 0.93969}{10 \times 0.92515} = 2.3362 \text{ inches} \quad (15)$$

10) Gear HPSTC, D_H

$$\tan D = 0.20267 + \frac{6.28318}{31} = 0.40535 \qquad D = 22°3'55'' \quad (16)$$

$$D_H = \frac{31 \times 0.93969}{10 \times 0.92676} = 3.1433 \text{ inches} \quad (17)$$

11) Pinion TIF diameter, d_{TIF}

$$\tan e = 0.36397 - \frac{4}{23}\left(\frac{1.25 - 0.30}{0.64279} + \frac{0.30}{2 \times 0.93969}\right) = 0.07917 \qquad e = 4°31'36'' \quad (18)$$

$$d_{TIF} = \frac{23 \times 0.93969}{10 \times 0.99688} = 2.1681 \text{ inches} \quad (19)$$

12) Gear TIF diameter, D_{TIF}

$$\tan E = 0.36397 - \frac{4}{31}\left(\frac{1.25 - 0.30}{0.64279} + \frac{0.30}{2 \times 0.93969}\right) = 0.15267 \qquad E = 8°40'50'' \quad (20)$$

$$D_{TIF} = \frac{31 \times 0.93969}{10 \times 0.98855} = 2.9468 \text{ inches} \quad (21)$$

Gear Blanks for Fine-pitch Gears.— The accuracy to which gears can be produced is considerably affected by the design of the gear blank and the accuracy to which the various surfaces of the blank are machined. The following recommendations should not be regarded as inflexible rules, but rather as minimum average requirements for gear-blank quality compatible with the expected quality class of the finished gear.

Copyright 2004, Industrial Press, Inc., New York, NY

Design of Gear Blanks: The accuracy to which gears can be produced is affected by the design of the blank, so the following points of design should be noted: 1) Gears designed with a hole should have the hole large enough that the blank can be adequately supported during machining of the teeth and yet not so large as to cause distortion; 2) Face widths should be wide enough, in proportion to outside diameters, to avoid springing and to permit obtaining flatness in important surfaces; 3) Short bore lengths should be avoided wherever possible. It is feasible, however, to machine relatively thin blanks in stacks, provided the surfaces are flat and parallel to each other; 4) Where gear blanks with hubs are to be designed, attention should be given to the wall sections of the hubs. Too thin a section will not permit proper clamping of the blank during machining operations and may also affect proper mounting of the gear; and 5) Where pinions or gears integral with their shafts are to be designed, deflection of the shaft can be minimized by having the shaft length and shaft diameter well proportioned to the gear or pinion diameter. The foregoing general principles may also be useful when applied to blanks for coarser pitch gears.

Specifying Spur and Helical Gear Data on Drawings.— The data that may be shown on drawings of spur and helical gears falls into three groups: The first group consists of data basic to the design of the gear; the second group consists of data used in manufacturing and inspection; and the third group consists of engineering reference data. The accompanying table may be used as a checklist for the various data which may be placed on gear drawings and the sequence in which they should appear.

Explanation of Terms Used in Gear Specifications: 1) Number of teeth is the number of teeth in 360 deg of gear circumference. In a sector gear, both the actual number of teeth in the sector and the theoretical number of teeth in 360 deg should be given.

2) Diametral pitch is the ratio of the number of teeth in the gear to the number of inches in the standard pitch diameter. It is used in this standard as a nominal specification of tooth size.

a) Normal diametral pitch is the diametral pitch in the normal plane.

b) Transverse diametral pitch is the diametral pitch in the transverse plane.

c) Module is the ratio of the number of teeth in the gear to the number of mm in the standard pitch diameter.

d) Normal module is the module measured in the normal plane.

e) Transverse module is the module measured in the transverse plane.

3) Pressure angle is the angle between the gear tooth profile and a radial line at the pitch point. It is used in this standard to specify the pressure angle of the basic rack used in defining the gear tooth profile.

a) Normal pressure angle is the pressure angle in the normal plane.

b) Transverse pressure angle is the pressure angle in the transverse plane.

4) Helix angle is the angle between the pitch helix and an element of the pitch cylinder, unless otherwise specified.

a) Hand of helix is the direction in which the teeth twist as they recede from an observer along the axis. A right hand helix twists clockwise and a left hand helix twists counterclockwise.

5) Standard pitch diameter is the diameter of the pitch circle. It equals the number of teeth divided by the transverse diametral pitch.

6) Tooth form may be specified as standard addendum, long addendum, short addendum, modified involute or special. If a modified involute or special tooth form is required, a detailed view should be shown on the drawing. If a special tooth form is specified, roll angles must be supplied (see page 2062).

7) Addendum is the radial distance between the standard pitch circle and the outside circle. The actual value depends on the specification of outside diameter.

8) Whole depth is the total radial depth of the tooth space. The actual value is dependent on the specification of outside diameter and root diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

9) Maximum calculated circular thickness on the standard pitch circle is the tooth thickness which will provide the desired minimum backlash when the gear is assembled in mesh with its mate on minimum center distance. Control may best be exerted by testing in tight mesh with a master which integrates all errors in the several teeth in mesh through the arc of action as explained on page 2073. This value is independent of the effect of runout.

a) Maximum calculated *normal* circular thickness is the circular tooth thickness in the normal plane which satisfies requirements explained in (9).

10) Gear testing radius is the distance from its axis of rotation to the standard pitch line of a standard master when in intimate contact under recommended pressure on a variable-center-distance running gage. Maximum testing radius should be calculated to provide the maximum circular tooth thickness specified in (9) when checked as explained on page 2073. This value is affected by the runout of the gear. Tolerance on testing radius must be equal to or greater than the total composite error permitted by the quality class specified in (11).

11) Quality class is specified for convenience when talking or writing about the accuracy of the gear.

12) Maximum total composite error, and 13) Maximum tooth-to-tooth composite error. Actual tolerance values (12 and 13) permitted by the quality class (11) are specified in inches to provide machine operator or inspector with tolerances required to inspect the gear.

14) Testing pressure recommendations are given on page 2073. Incorrect testing pressure will result in incorrect measurement of testing radius.

15) Master specifications by tool or code number may be required to call for the use of a special master gear when tooth thickness deviates excessively from standard.

16) Measurement over two 0.xxxx diameter pins may be specified to assist the manufacturing department in determining size at machine for setup only.

17) Outside diameter is usually shown on the drawing of the gear together with other blank dimensions so that it will not be necessary for machine operators to search gear tooth data for this dimension. Since outside diameter is also frequently used in the manufacture and inspection of the teeth, it may be included in the data block with other tooth specifications if preferred. To permit use of topping hobs for cutting gears on which the tooth thickness has been modified from standard, the outside diameter should be related to the specified gear testing radius (10).

18) Maximum root diameter is specified to assure adequate clearance for the outside diameter of the mating gear. This dimension is usually considered acceptable if the gear is checked with a master and meets specifications (10) through (13).

19) Active profile diameter of a gear is the smallest diameter at which the mating gear tooth profile can make contact. Because of difficulties involved in checking, this specification is not recommended for gears finer than 48 pitch.

20) Surface roughness on active profile surfaces may be specified in microinches to be checked by instrument up to about 32 pitch, or by visual comparison in the finer pitch ranges. It is difficult to determine accurately the surface roughness of fine pitch gears. For many commercial applications surface roughness may be considered acceptable on gears which meet the maximum tooth-to-tooth-error specification (13).

21) Mating gear part number may be shown as a convenient reference. If the gear is used in several applications, all mating gears may be listed but usual practice is to record this information in a reference file.

22) Number of teeth in mating gear, and 23) Minimum operating center distance. This information is often specified to eliminate the necessity of getting prints of the mating gear and assemblies for checking the design specifications, interference, backlash, determination of master gear specification, and acceptance or rejection of gears made out of tolerance.

Copyright 2004, Industrial Press, Inc., New York, NY

Data for Spur and Helical Gear Drawings

Type of Data	Min. Spur Gear Data	Min. Helical Gear-Data	Add'l Optional Data	Item Number[a]	Data[a]
Basic Specifications	●	●		1	Number of teeth
	●			2	Diametral pitch or module
		●		2a	Normal diametral pitch or module
			●	2b	Transverse diametral pitch or module
	●			3	Pressure angle
		●		3a	Normal pressure angle
			●	3b	Transverse pressure angle
		●		4	Helix angle
		●		4a	Hand of helix
	●	●		5	Standard pitch diameter
	●	●		6	Tooth form
			●	7	Addendum
			●	8	Whole depth
	●			9	Max. calc. circular thickness on std. pitch circle
		●		9a	Max. calc. normal circular thickness on std.pitch circle
Manufacturing and Inspection			●	10	Roll angles
	●	●		11	A.G.M.A. quality class
	●	●		12	Max. total composite error
	●	●		13	Max. tooth-to-tooth composite error
			●	14	Testing pressure (Ounces)
	●	●		15	Master specification
			●	16	Meas. over two .xxxx dia. pins (For setup only)
	●	●		17	Outside diameter (Preferably shown on drawing of gear)
			●	18	Max. root diameter
			●	19	Active profile diameter
			●	20	Surface roughness of active profile
Engineering Reference			●	21	Mating gear part number
			●	22	Number of teeth in mating gear
			●	23	Minimum operating center distance

[a] An item-by-item explanation of the terms used in this table is given beginning on page 2065.

Backlash

In general, backlash in gears is play between mating teeth. For purposes of measurement and calculation, backlash is defined as the amount by which a tooth space exceeds the thickness of an engaging tooth. It does not include the effect of center-distance changes of the mountings and variations in bearings. When not otherwise specified, numerical values of backlash are understood to be given on the pitch circles. The general purpose of backlash is to prevent gears from jamming together and making contact on both sides of their teeth simultaneously. Lack of backlash may cause noise, overloading, overheating of the gears and bearings, and even seizing and failure.

Excessive backlash is objectionable, particularly if the drive is frequently reversing, or if there is an overrunning load as in cam drives. On the other hand, specification of an unnecessarily small amount of backlash allowance will increase the cost of gears, because errors in runout, pitch, profile, and mounting must be held correspondingly smaller. Backlash does not affect involute action and usually is not detrimental to proper gear action.

Determining Proper Amount of Backlash.— In specifying proper backlash and tolerances for a pair of gears, the most important factor is probably the maximum permissible amount of runout in both gear and pinion (or worm). Next are the allowable errors in profile, pitch, tooth thickness, and helix angle. Backlash between a pair of gears will vary as successive teeth make contact because of the effect of composite tooth errors, particularly runout, and errors in the gear center distances and bearings.

Other important considerations are speed and space for lubricant film. Slow-moving gears, in general, require the least backlash. Fast-moving fine-pitch gears are usually lubri-

Copyright 2004, Industrial Press, Inc., New York, NY

cated with relatively light oil, but if there is insufficient clearance for an oil film, and particularly if oil trapped at the root of the teeth cannot escape, heat and excessive tooth loading will occur.

Heat is a factor because gears may operate warmer, and, therefore, expand more, than the housings. The heat may result from oil churning or from frictional losses between the teeth, at bearings or oil seals, or from external causes. Moreover, for the same temperature rise, the material of the gears—for example, bronze and aluminum—may expand more than the material of the housings, usually steel or cast iron.

The higher the helix angle or spiral angle, the more transverse backlash is required for a given normal backlash. The transverse backlash is equal to the normal backlash divided by the cosine of the helix angle.

In designs employing normal pressure angles higher than 20 degrees, special consideration must be given to backlash, because more backlash is required on the pitch circles to obtain a given amount of backlash in a direction normal to the tooth profiles.

Errors in boring the gear housings, both in center distance and alignment, are of extreme importance in determining allowance to obtain the backlash desired. The same is true in the mounting of the gears, which is affected by the type and adjustment of bearings, and similar factors. Other influences in backlash specification are heat treatment subsequent to cutting the teeth, lapping operations, need for recutting, and reduction of tooth thickness through normal wear.

Minimum backlash is necessary for timing, indexing, gun-sighting, and certain instrument gear trains. If the operating speed is very low and the necessary precautions are taken in the manufacture of such gear trains, the backlash may be held to extremely small limits. However, the specification of "zero backlash," so commonly stipulated for gears of this nature, usually involves special and expensive techniques, and is difficult to obtain.

Table 1. AGMA Recommended Backlash Range for Coarse-Pitch Spur, Helical, and Herringbone Gearing

Center Distance (Inches)	Normal Diametral Pitches				
	0.5–1.99	2–3.49	3.5–5.99	6–9.99	10–19.99
	Backlash, Normal Plane, Inches[a]				
Up to 5	…	…	…	…	.005–.015
Over 5 to 10	…	…	…	.010–.020	.010–.020
Over 10 to 20	…	…	.020–.030	.015–.025	.010–.020
Over 20 to 30	…	.030–.040	.025–.030	.020–.030	…
Over 30 to 40	.040–.060	.035–.045	.030–.040	.025–.035	…
Over 40 to 50	.050–.070	.040–.055	.035–.050	.030–.040	…
Over 50 to 80	.060–.080	.045–.065	.040–.060	…	…
Over 80 to 100	.070–.095	.050–.080	…	…	…
Over 100 to 120	.080–.110	…	…	…	…

[a] Suggested backlash, on nominal centers, measured after rotating to the point of closest engagement. For helical and herringbone gears, divide above values by the cosine of the helix angle to obtain the transverse backlash.

The above backlash tolerances contain allowance for gear expansion due to differential in the operating temperature of the gearing and their supporting structure. The values may be used where the operating temperatures are up to 70 deg F higher than the ambient temperature.

For most gearing applications the recommended backlash ranges will provide proper running clearance between engaging teeth of mating gears. Deviation below the minimum or above the maximum values shown, which do not affect operational use of the gearing, should not be cause for rejection.

Definite backlash tolerances on coarse-pitch gearing are to be considered binding on the gear manufacturer only when agreed upon in writing.

Some applications may require less backlash than shown in the above table. In such cases the amount and tolerance should be by agreement between manufacturer and purchaser.

Copyright 2004, Industrial Press, Inc., New York, NY

Recommended Backlash: In the following tables American Gear Manufacturers Association recommendations for backlash ranges for various kinds of gears are given.* For purposes of measurement and calculation, backlash is defined as the amount by which a tooth space exceeds the thickness of an engaging tooth. When not otherwise specified, numerical values of backlash are understood to be measured at the tightest point of mesh on the pitch circle in a direction normal to the tooth surface when the gears are mounted in their specified position.

Coarse-Pitch Gears: Table 1 gives the recommended backlash range for coarse-pitch spur, helical and herringbone gearing. Because backlash for helical and herringbone gears is more conveniently measured in the normal plane, Table 1 has been prepared to show backlash in the normal plane for coarse-pitch helical and herringbone gearing and in the transverse plane for spur gears. To obtain backlash in the transverse plane for helical and herringbone gears, divide the normal plane backlash in Table 1 by the cosine of the helix angle.

Table 2. AGMA Recommended Backlash Range for Bevel and Hypoid Gears

Diametral Pitch	Normal Backlash, Inch		Diametral Pitch	Normal Backlash, Inch	
	Quality Numbers 7 through 13	Quality Numbers 3 through 6		Quality Numbers 7 through 13	Quality Numbers 3 through 6
1.00 to 1.25	0.020–0.030	0.045–0.065	5.00 to 6.00	0.005–0.007	0.006–0.013
1.25 to 1.50	0.018–0.026	0.035–0.055	6.00 to 8.00	0.004–0.006	0.005–0.010
1.50 to 1.75	0.016–0.022	0.025–0.045	8.00 to 10.00	0.003–0.005	0.004–0.008
1.75 to 2.00	0.014–0.018	0.020–0.040	10.00 to 16.00	0.002–0.004	0.003–0.005
2.00 to 2.50	0.012–0.016	0.020–0.030	16.00 to 20.00	0.001–0.003	0.002–0.004
2.50 to 3.00	0.010–0.013	0.015–0.025	20 to 50	0.000–0.002	0.000–0.002
3.00 to 3.50	0.008–0.011	0.012–0.022	50 to 80	0.000–0.001	0.000–0.001
3.50 to 4.00	0.007–0.009	0.010–0.020	80 and finer	0.000–0.0007	0.000–0.0007
4.00 to 5.00	0.006–0.008	0.008–0.016	…	…	…

Measured at tightest point of mesh

The backlash tolerances given in this table contain allowances for gear expansion due to a differential in the operating temperature of the gearing and their supporting structure. The values may be used where the operating temperature is up to 70 degrees F. higher than the ambient temperature. These backlash values will provide proper running clearances for most gear applications.

The following important factors must be considered in establishing backlash tolerances:

a) Center distance tolerance; b) Parallelism of gear axes; c) Side runout or wobble; d) Tooth thickness tolerance; e) Pitch line runout tolerance; f) Profile tolerance; g) Pitch tolerance; h) Lead tolerance; i) Types of bearings and subsequent wear; j) Deflection under load; k) Gear tooth wear; l) Pitch line velocity; m) Lubrication requirements; and n) Thermal expansion of gears and housing.

A tight mesh may result in objectionable gear sound, increased power losses, overheating, rupture of the lubricant film, overloaded bearings and premature gear failure. However, it is recognized that there are some gearing applications where a tight mesh (zero backlash) may be required.

Specifying unnecessarily close backlash tolerances will increase the cost of the gearing. It is obvious from the above summary that the desired amount of backlash is difficult to evaluate. It is, therefore, recommended that when a designer, user or purchaser includes a reference to backlash in a gearing specification and drawing, consultation be arranged with the manufacturer.

* Extracted from Gear Classification Manual, AGMA 390.03 with permission of the publisher, the American Gear Manufacturers Association, 1500 King St., Alexandria, VA 22314.

Copyright 2004, Industrial Press, Inc., New York, NY

Bevel and Hypoid Gears: Table 2 gives similar backlash range values for bevel and hypoid gears. These are values based upon average conditions for general purpose gearing, but may require modification to meet specific needs.

Backlash on bevel and hypoid gears can be controlled to some extent by axial adjustment of the gears during assembly. However, due to the fact that actual adjustment of a bevel or hypoid gear in its mounting will alter the amount of backlash, it is imperative that the amount of backlash cut into the gears during manufacture is not excessive. Bevel and hypoid gears must always be capable of operation without interference when adjusted for zero backlash. This requirement is imposed by the fact that a failure of the axial thrust bearing might permit the gears to operate under this condition. Therefore, bevel and hypoid gears should never be designed to operate with normal backlash in excess of $0.080/P$ where P is diametral pitch.

Fine-Pitch Gears: Table 3 gives similar backlash range values for fine-pitch spur, helical and herringbone gearing.

Providing Backlash.— In order to obtain the amount of backlash desired, it is necessary to decrease tooth thicknesses. However, because of manufacturing and assembling inaccuracies not only in the gears but also in other parts, the allowances made on tooth thickness almost always must exceed the desired amount of backlash. Since the amounts of these allowances depend on the closeness of control exercised on all manufacturing operations, no general recommendations for them can be given.

It is customary to make half the allowance for backlash on the tooth thickness of each gear of a pair, although there are exceptions. For example, on pinions having very low numbers of teeth it is desirable to provide all the allowance on the mating gear, so as not to weaken the pinion teeth. In worm gearing, ordinary practice is to provide all of the allowance on the worm which is usually made of a material stronger than that of the worm gear.

In some instances the backlash allowance is provided in the cutter, and the cutter is then operated at the standard tooth depth. In still other cases, backlash is obtained by setting the distance between two tools for cutting the two sides of the teeth, as in straight bevel gears, or by taking side cuts, or by changing the center distance between the gears in their mountings. In spur and helical gearing, backlash allowance is usually obtained by sinking the cutter deeper into the blank than the standard depth. The accompanying table gives the excess depth of cut for various pressure angles.

Excess Depth of Cut *E* to Provide Backlash Allowance

Distribution of Backlash	Pressure Angle ϕ, Degrees				
	14½	17½	20	25	30
Excess Depth of Cut E to Obtain Circular Backlash B[a]					
All on One Gear	$1.93B$	$1.59B$	$1.37B$	$1.07B$	$0.87B$
One-half on Each Gear	$0.97B$	$0.79B$	$0.69B$	$0.54B$	$0.43B$
Excess Depth of Cut E to Obtain Backlash B_b Normal to Tooth Profile[b]					
All on One Gear	$2.00B_b$	$1.66B_b$	$1.46B_b$	$1.18B_b$	$1.99B_b$
One-half on Each Gear	$1.00B_b$	$0.83B_b$	$0.73B_b$	$0.59B_b$	$0.50B_b$

[a] Circular backlash is the amount by which the width of a tooth space is greater than the thickness of the engaging tooth on the pitch circles. As described in pages 2067 and 2071 this is what is meant by backlash unless otherwise specified.

[b] Backlash measured normal to the tooth profile by inserting a feeler gage between meshing teeth; to convert to circular backlash, $B = B_b \div \cos \phi$.

Control of Backlash Allowances in Production.— Measurement of the tooth thickness of gears is perhaps the simplest way of controlling backlash allowances in production.

There are several ways in which this may be done including: 1) chordal thickness measurements as described on page 2049; 2) caliper measurements over two or more teeth as described on page 2140; and 3) measurements over wires.

Copyright 2004, Industrial Press, Inc., New York, NY

In this last method, first the theoretical measurement over wires when the backlash allowance is zero is determined by the method described on page 2125; then the amount this measurement must be reduced to obtain a desired backlash allowance is taken from the table on page 2139.

It should be understood, as explained in the section *Measurement of Backlash* that merely making tooth thickness allowances will not guarantee the amount of backlash in the ready-to-run assembly of two or more gears. Manufacturing limitations will introduce such gear errors as runout, pitch error, profile error, and lead error, and gear-housing errors in both center distance and alignment. All of these make the backlash of the assembled gears different from that indicated by tooth thickness measurements on the individual gears.

Measurement of Backlash.— Backlash is commonly measured by holding one gear of a pair stationary and rocking the other back and forth. The movement is registered by a dial indicator having its pointer or finger in a plane of rotation at or near the pitch diameter and in a direction parallel to a tangent to the pitch circle of the moving gear. If the direction of measurement is normal to the teeth, or other than as specified above, it is recommended that readings be converted to the plane of rotation and in a tangent direction at or near the pitch diameter, for purposes of standardization and comparison.

In spur gears, parallel helical gears, and bevel gears, it is immaterial whether the pinion or gear is held stationary for the test. In crossed helical and hypoid gears, readings may vary according to which member is stationary; hence, it is customary to hold the pinion stationary and measure on the gear.

In some instances, backlash is measured by thickness gages or feelers. A similar method utilizes a soft lead wire inserted between the teeth as they pass through mesh. In both methods, it is likewise recommended that readings be converted to the plane of rotation and in a tangent direction at or near the pitch diameter, taking into account the normal pressure angle, and the helix angle or spiral angle of the teeth.

Sometimes backlash in parallel helical or herringbone gears is checked by holding the gear stationary, and moving the pinion axially back and forth, readings being taken on the face or shaft of the pinion, and converted to the plane of rotation by calculation. Another method consists of meshing a pair of gears tightly together on centers and observing the variation from the specified center distance. Such readings should also be converted to the plane of rotation and in a tangent direction at or near the pitch diameter for the reasons previously given.

Measurements of backlash may vary in the same pair of gears, depending on accuracy of manufacturing and assembling. Incorrect tooth profiles will cause a change of backlash at different phases of the tooth action. Eccentricity may cause a substantial difference between maximum and minimum backlash at different positions around the gears. In stating amounts of backlash, it should always be remembered that merely making allowances on tooth thickness does not guarantee the minimum amount of backlash that will exist in assembled gears.

Fine-Pitch Gears: The measurement of backlash of fine-pitch gears, when assembled, cannot be made in the same manner and by the same techniques employed for gears of coarser pitches. In the very fine pitches, it is virtually impossible to use indicating devices for measuring backlash. Sometimes a toolmaker's microscope is used for this purpose to good advantage on very small mechanisms.

Another means of measuring backlash in fine-pitch gears is to attach a beam to one of the shafts and measure the angular displacement in inches when one member is held stationary. The ratio of the length of the beam to the nominal pitch radius of the gear or pinion to which the beam is attached gives the approximate ratio of indicator reading to circular backlash. Because of the limited means of measuring backlash between a pair of fine-pitch gears, gear centers and tooth thickness of the gears when cut must be held to very close lim-

Copyright 2004, Industrial Press, Inc., New York, NY

its. Tooth thickness of fine-pitch spur and helical gears can best be checked on a variable-center-distance fixture using a master gear. When checked in this manner, tooth thickness change = 2 × center distance change × tangent of transverse pressure angle, approximately.

Control of Backlash in Assemblies.— Provision is often made for adjusting one gear relative to the other, thereby affording complete control over backlash at initial assembly and throughout the life of the gears. Such practice is most common in bevel gearing. It is fairly common in spur and helical gearing when the application permits slight changes between shaft centers. It is practical in worm gearing only for single thread worms with low lead angles. Otherwise faulty contact results.

Another method of controlling backlash quite common in bevel gears and less common in spur and helical gears is to match the high and low spots of the runout gears of one to one ratio and mark the engaging teeth at the point where the runout of one gear cancels the runout of the mating gear.

Table 3. AGMA Backlash Allowance and Tolerance for Fine-Pitch Spur, Helical and Herringbone Gearing

Backlash Designation	Normal Diametral Pitch Range	Tooth Thinning to Obtain Backlash[a]		Resulting Approximate Backlash (per Mesh) Normal Plane[b] Inch
		Allowance, per Gear, Inch	Tolerance, per Gear, Inch	
A	20 thru 45	.002	0 to .002	.004 to .008
	46 thru 70	.0015	0 to .002	.003 to .007
	71 thru 90	.001	0 to .00175	.002 to .0055
	91 thru 200	.00075	0 to .00075	.0015 to .003
B	20 thru 60	.001	0 to .001	.002 to .004
	61 thru 120	.00075	0 to .00075	.0015 to .003
	121 thru 200	.0005	0 to .0005	.001 to .002
C	20 thru 60	.0005	0 to .0005	.001 to .002
	61 thru 120	.00035	0 to .0004	.0007 to .0015
	121 thru 200	.0002	0 to .0003	.0004 to .001
D	20 thru 60	.00025	0 to .00025	.0005 to .001
	61 thru 120	.0002	0 to .0002	.0004 to .0008
	121 thru 200	.0001	0 to .0001	.0002 to .0004
E	20 thru 60		0 to .00025	0 to .0005
	61 thru 120	Zero[c]	0 to .0002	0 to .0004
	121 thru 200		0 to .0001	0 to .0002

[a] These dimensions are shown primarily for the benefit of the gear manufacturer and represent the amount that the thickness of teeth should be reduced in the pinion and gear below the standard calculated value, to provide for backlash in the mesh. In some cases, particularly with pinions involving small numbers of teeth, it may be desirable to provide for total backlash by thinning the teeth in the gear member only by twice the allowance value shown in column (3). In this case both members will have the tolerance shown in column (4). In some cases, particularly in meshes with a small number of teeth, backlash may be achieved by an increase in basic center at distance. In such cases, neither member is reduced by the allowance shown in column (3).

[b] These dimensions indicate the approximate backlash that will occur in a mesh in which each of the mating pairs of gears have the teeth thinned by the amount referred to in Note 1, and are meshed on theoretical centers.

[c] Backlash in gear sets can also be achieved by increasing the center distance above nominal and using the teeth at standard tooth thickness. Class E backlash designation infers gear sets operating under these conditions.

Backlash in gears is the play between mating tooth surfaces. For purposes of measurement and calculation, backlash is defined as the amount by which a tooth space exceeds the thickness of an engaging tooth. When not otherwise specified, numerical values of backlash are understood to be measured at the tightest point of mesh on the pitch circle in a direction normal to the tooth surface when the gears are mounted in their specified position.

Allowance is the basic amount that a tooth is thinned from basic calculated circular tooth thickness to obtain the required backlash class.

Tolerance is the total permissible variation in the circular thickness of the teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

Angular Backlash in Gears.— When the backlash on the pitch circles of a meshing pair of gears is known, the angular backlash or angular play corresponding to this backlash may be computed from the following formulas.

$$\theta_D = \frac{6875B}{D} \text{ minutes} \qquad \theta_d = \frac{6875B}{d} \text{ minutes}$$

In these formulas, B = backlash between gears, in inches; D = pitch diameter of larger gear, in inches; d = pitch diameter of smaller gear, in inches; θ_D = angular backlash or angular movement of larger gear in minutes when smaller gear is held fixed and larger gear rocked back and forth; and θ_d = angular backlash or angular movement of smaller gear, in minutes, when the larger gear is held fixed and the smaller gear rocked back and forth.

Inspection of Gears.— Perhaps the most widely used method of determining relative accuracy in a gear is to rotate the gear through at least one complete revolution in intimate contact with a master gear of known accuracy. The gear to be tested and the master gear are mounted on a variable-center-distance fixture and the resulting radial displacements or changes in center distance during rotation of the gear are measured by a suitable device. Except for the effect of backlash, this so-called "composite check" approximates the action of the gear under operating conditions and gives the combined effect of the following errors: runout; pitch error; tooth-thickness variation; profile error; and lateral runout (sometimes called wobble).

Tooth-to-Tooth Composite Error, illustrated below, is the error that shows up as flicker on the indicator of a variable-center-distance fixture as the gear being tested is rotated from tooth to tooth in intimate contact with the master gear. Such flicker shows the combined or composite effect of circular pitch error, tooth-thickness variation, and profile error.



Diagram Showing Nature of Composite Errors

Total Composite Error, shown above, is made up of runout, wobble, and the tooth-to-tooth composite error; it is the total center-distance displacement read on the indicating device of the testing fixture, as shown in the accompanying diagram.

Pressure for Composite Checking of Fine-Pitch Gears.— In using a variable-center-distance fixture, excessive pressure on fine-pitch gears of narrow face width will result in incorrect readings due to deflection of the teeth. Based on tests, the following checking pressures are recommended for gears of 0.100-inch face width: 20 to 29 diametral pitch, 28 ounces; 30 to 39 pitch, 24 ounces; 40 to 49 pitch, 20 ounces; 50 to 59 pitch, 16 ounces; 60 to 79 pitch, 12 ounces; 80 to 99 pitch, 8 ounces, 100 to 149 pitch, 4 ounces; and 150 and finer pitches, 2 ounces, minimum. These recommended checking pressures are based on the use of antifriction mountings for the movable head of the checking fixture and include the pressure of the indicating device. For face widths less than 0.100 inch, the recommended pressures should be reduced proportionately; for larger widths, no increase is necessary although the force may be increased safely in the proper proportion.

Copyright 2004, Industrial Press, Inc., New York, NY

Internal Gearing

Internal Spur Gears.— An internal gear may be proportioned like a standard spur gear turned "outside in" or with addendum and dedendum in reverse positions; however, to avoid interference or improve the tooth form and action, the internal diameter of the gear should be increased and the outside diameter of the mating pinion is also made larger than the size based upon standard or conventional tooth proportions. The extent of these enlargements will be illustrated by means of examples given following table, *Rules for Internal Gears—20-degree Full-Depth Teeth*. The 20-degree involute full-depth tooth form is recommended for internal gears; the 20-degree stub tooth and the 14½-degree full-depth tooth are also used.

Methods of Cutting Internal Gears.— Internal spur gears are cut by methods similar in principle to those employed for external spur gears.

They may be cut by one of the following methods: 1) By a generating process, as when using a Fellows gear shaper; 2) by using a formed cutter and milling the teeth; 3) by planing, using a machine of the template or form-copying type (especially applicable to gears of large pitch); and 4) by using a formed tool that reproduces its shape and is given a planing action either on a slotting or a planing type of machine.

Internal gears frequently have a web at one side that limits the amount of clearance space at the ends of the teeth. Such gears may be cut readily on a gear shaper. The most practical method of cutting very large internal gears is on a planer of the form-copying type. A regular spur gear planer is equipped with a special tool holder for locating the tool in the position required for cutting internal teeth.

Formed Cutters for Internal Gears.— When formed cutters are used, a special cutter usually is desirable, because the tooth spaces of an internal gear are not the same shape as the tooth spaces of external gearing having the same pitch and number of teeth. This difference is because an internal gear is a spur gear "turned outside in." According to one rule, the standard No. 1 cutter for external gearing may be used for internal gears of 4 diametral pitch and finer, when there are 60 or more teeth. This No. 1 cutter, as applied to external gearing, is intended for all gears having from 135 teeth to a rack. The finer the pitch and the larger the number of teeth, the better the results obtained with a No. 1 cutter. The standard No. 1 cutter is considered satisfactory for jobbing work, and usually when the number of gears to be cut does not warrant obtaining a special cutter, although the use of the No. 1 cutter is not practicable when the number of teeth in the pinion is large in proportion to the number of teeth in the internal gear.

Arc Thickness of Internal Gear Tooth.— *Rule:* If internal diameter of an internal gear is enlarged as determined by Rules 1 and 2 for Internal Diameters (see *Rules for Internal Gears—20-degree Full-Depth Teeth*), the arc tooth thickness at the pitch circle equals 1.3888 divided by the diametral pitch, assuming a pressure angle of 20 degrees.

Arc Thickness of Pinion Tooth.— *Rule:* If the pinion for an internal gear is larger than conventional size (see Outside Diameter of Pinion for Internal Gear, under *Rules for Internal Gears—20-degree Full-Depth Teeth*), then the arc tooth thickness on the pitch circle equals 1.7528 divided by the diametral pitch, assuming a pressure angle of 20 degrees.

Note: For chordal thickness and chordal addendum, see rules and formulas for spur gears.

Relative Sizes of Internal Gear and Pinion.— If a pinion is too large or too near the size of its mating internal gear, serious interference or modification of the tooth shape may occur.

Rule: For internal gears having a 20-degree pressure angle and full-depth teeth, the difference between the numbers of teeth in gear and pinion should not be less than 12. For teeth of stub form, the smallest difference should be 7 or 8 teeth. For a pressure angle of 14½ degrees, the difference in tooth numbers should not be less than 15.

Copyright 2004, Industrial Press, Inc., New York, NY

Rules for Internal Gears—20-degree Full-Depth Teeth

To Find	Rule
Pitch Diameter	*Rule:* To find the pitch diameter of an internal gear, divide the number of internal gear teeth by the diametral pitch. The pitch diameter of the mating pinion also equals the number of pinion teeth divided by the diametral pitch, the same as for external spur gears.
Internal Diameter (Enlarged to Avoid Interference)	*Rule* 1: For internal gears to mesh with pinions having 16 teeth or more, subtract 1.2 from the number of teeth and divide the remainder by the diametral pitch. *Example:* An internal gear has 72 teeth of 6 diametral pitch and the mating pinion has 18 teeth; then $\text{Internal diameter} = \frac{72 - 1.2}{6} = 11.8 \text{ inches}$ *Rule* 2: If circular pitch is used, subtract 1.2 from the number of internal gear teeth, multiply the remainder by the circular pitch, and divide the product by 3.1416.
Internal Diameter (Based upon Spur Gear Reversed)	*Rule:* If the internal gear is to be designed to conform to a spur gear turned outside in, subtract 2 from the number of teeth and divide the remainder by the diametral pitch to find the internal diameter. *Example:* (Same as Example above.) $\text{Internal diameter} = \frac{72 - 2}{6} = 11.666 \text{ inches}$
Outside Diameter of Pinion for Internal Gear	*Note:* If the internal gearing is to be proportioned like standard spur gearing, use the rule or formula previously given for spur gears in determining the outside diameter. The rule and formula following apply to a pinion that is enlarged and intended to mesh with an internal gear enlarged as determined by the preceding Rules 1 and 2 above. *Rule:* For pinions having 16 teeth or more, add 2.5 to the number of pinion teeth and divide by the diametral pitch. *Example* 1: A pinion for driving an internal gear is to have 18 teeth (full depth) of 6 diametral pitch; then $\text{Outside diameter} = \frac{18 + 2.5}{6} = 3.416 \text{ inches}$ By using the rule for external spur gears, the outside diameter = 3.333 inches.
Center Distance	*Rule:* Subtract the number of pinion teeth from the number of internal gear teeth and divide the remainder by two times the diametral pitch.
Tooth Thickness	See paragraphs, *Arc Thickness of Internal Gear Tooth* and *Effect of Diameter of Cutting on Profile and Pressure Angle of Worms*, on previous page.

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard for Spur and Helical Gears

British Standard For Spur And Helical Gears.— BS 436: Part 1: 1967: Spur and Helical Gears, Basic Rack Form, Pitches and Accuracy for Diametral Pitch Series, now has sections concerned with basic requirements for general tooth form, standard pitches, accuracy and accuracy testing procedures, and the showing of this information on engineering drawings to make sure that the gear manufacturer receives the required data. The latest form of the standard complies with ISO agreements. The standard pitches are in accordance with ISO R54, and the basic rack form and its modifications are in accordance with the ISO R53 "Basic Rack of Cylindrical Gears for General Engineering and for Heavy Engineering Standard".

Five grades of gear accuracy in previous versions are replaced by grades 3 to 12 of the draft ISO Standard. Grades 1 and 2 cover master gears that are not dealt with here. BS 436: Part 1: 1967 is a companion to the following British Standards:

BS 235 "Gears for Traction"
BS 545 "Bevel Gears (Machine Cut)"
BS 721 "Worm Gearing"
BS 821 "Iron Castings for Gears and Gear Blanks (Ordinary, Medium and High Grade)"
BS 978 "Fine Pitch Gears"Part 1, "Involute, Spur and Helical Gears"; Part 2, "Cycloidal Gears" (with addendum 1, PD 3376: "Double Circular Arc Type Gears."; Part 3, "Bevel Gears"
BS 1807 "Gears for Turbines and Similar Drives" Part 1, "Accuracy" Part 2, "Tooth Form and Pitches"
BS 2519 "Glossary of Terms for Toothed Gearing"
BS 3027 "Dimensions for Worm Gear Units"
BS 3696 "Master Gears"

Part 1 of BS 436 applies to external and internal involute spur and helical gears on parallel shafts and having normal diametral pitch of 20 or coarser. The basic rack and tooth form are specified, also first and second preference standard pitches and fundamental tolerances that determine the grades of gear accuracy, and requirements for terminology and notation.

These requirements include:center distance a; reference circle diameter d, for pinion d_1 and wheel d_2; tip diameter d_a for pinion d_{a1} and wheel d_{a2}; center distance modification coefficient γ; face width b for pinion b_1 and wheel b_2; addendum modification coefficient x; for pinion x_1 and wheel x_2; length of arc l; diametral pitch P_t; normal diametral pitch p_n; transverse pitch p_t; number of teeth z, for pinion z_1 and wheel z_2; helix angle at reference cylinder β; pressure angle at reference cylinder α; normal pressure angle at reference cylinder α_n; transverse pressure angle at reference cylinder α_t; and transverse pressure angle, working, α_{tw}.

The basic rack tooth profile has a pressure angle of 20°. The Standard permits the total tooth depth to be varied within 2.25 to 2.40, so that the root clearance can be increased within the limits of 0.25 to 0.040 to allow for variations in manufacturing processes; and the root radius can be varied within the limits of 0.25 to 0.39. Tip relief can be varied within the limits shown at the right in the illustration.

Standard normal diametral pitches P_n, BS 436 Part 1:1967, are in accordance with ISO R54. The preferred series, rather than the second choice, should be used where possible.

Preferred normal diametral pitches for spur and helical gears (second choices in parentheses) are: 20 (18), 16 (14), 12 (11), 10 (9), 8 (7), 6 (5.5), 5 (4.5), 4 (3.5), 3 (2.75), 2.5 (2.25), 2 (1.75), 1.5, 1.25, and 1.

Information to be Given on Drawings: British Standard BS 308, "Engineering Drawing Practice", specifies data to be included on drawings of spur and helical gears. For all gears the data should include: number of teeth, normal diametral pitch, basic rack tooth form, axial pitch, tooth profile modifications, blank diameter, reference circle diameter, and helix angle at reference cylinder (0° for straight spur gears), tooth thickness at reference

Copyright 2004, Industrial Press, Inc., New York, NY

cylinder, grade of gear, drawing number of mating gear, working center distance, and backlash.

For single helical gears, the above data should be supplemented with hand and lead of the tooth helix; and for double helical gears, with the hand in relation to a specific part of the face width and the lead of tooth helix.

Inspection instructions should be included, care being taken to avoid conflicting requirements for accuracy of individual elements, and single- and dual-flank testing. Supplementary data covering specific design, manufacturing and inspection requirements or limitations may be needed, together with other dimensions and tolerances, material, heat treatment, hardness, case depth, surface texture, protective finishes, and drawing scale.

Addendum Modification to Involute Spur and Helical Gears.— The British Standards Institute guide PD 6457:1970 contains certain design recommendations aimed at making it possible to use standard cutting tools for some sizes of gears. Essentially, the guide covers addendum modification and includes formulas for both English and metric units.

Addendum Modification is an enlargement or reduction of gear tooth dimensions that results from displacement of the reference plane of the generating rack from its normal position. The displacement is represented by the coefficient X, X1 , or X2 , where X is the equivalent dimension for gears of unit module or diametral pitch. The addendum modification establishes a datum tooth thickness at the reference circle of the gear but does not necessarily establish the height of either the reference addendum or the working addendum. In any pair of gears, the datum tooth thicknesses are those that always give zero backlash at the meshing center distance. Normal practice requires allowances for backlash for all unmodified gears.

Taking full advantage of the adaptability of the involute system allows various tooth design features to be obtained. Addendum modification has the following applications: avoiding undercut tooth profiles; achieving optimum tooth proportions and control of the proportion of receding to approaching contact; adapting a gear pair to a predetermined center distance without recourse to non-standard pitches; and permitting use of a range of working pressure angles using standard geometry tools.

BS 436, Part 3:1986 "Spur and Helical Gears".— This part provides methods for calculating contact and root bending stresses for metal involute gears, and is somewhat similar to the ANSI/AGMA Standard for calculating stresses in pairs of involute spur or helical gears. Stress factors covered in the British Standard include the following:

Tangential Force is the nominal force for contact and bending stresses.

Zone Factor accounts for the influence of tooth flank curvature at the pitch point on Hertzian stress.

Contact Ratio Factor takes account of the load-sharing influence of the transverse contact ratio and the overlap ratio on the specific loading.

Elasticity Factor takes into account the influence of the modulus of elasticity of the material and of Poisson's ratio on the Hertzian stress.

Basic Endurance Limit for contact makes allowance for the surface hardness.

Material Quality covers the quality of the material used.

Lubricant Influence, Roughness, and Speed The lubricant viscosity, surface roughness and pitch line speed affect the lubricant film thickness, which in turn, affects the Hertzian stresses.

Work Hardening Factor accounts for the increase in surface durability due to the meshing action.

Size Factor covers the possible influences of size on the material quality and its response to manufacturing processes.

Life Factor accounts for the increase in permissible stresses when the number of stress cycles is less than the endurance life.

Copyright 2004, Industrial Press, Inc., New York, NY

Application Factor allows for load fluctuations from the mean load or loads in the load histogram caused by sources external to the gearing.

Dynamic Factor allows for load fluctuations arising from contact conditions at the gear mesh.

Load Distribution accounts for the increase in local load due to maldistribution of load across the face of the gear tooth caused by deflections, alignment tolerances and helix modifications.

Minimum Demanded and Actual Safety Factor The minimum demanded safety factor is agreed between the supplier and the purchaser. The actual safety factor is calculated.

Geometry Factors allow for the influence of the tooth form, the effect of the fillet and the helix angle on the nominal bending stress for the application of load at the highest point of single pair tooth contact.

Sensitivity Factor allows for the sensitivity of the gear material to the presence of notches such as the root fillet.

Surface Condition Factor accounts for reduction of the endurance limit due to flaws in the material and the surface roughness of the tooth root fillets.

ISO TC/600.— The ISO TC/600 Standard is similar to BS 436, Part 3:1986, but is far more comprehensive. For general gear design, the ISO Standard provides a complicated method of arriving at a conclusion similar to that reached by the less complex British Standard. Factors additional to the above that are included in the ISO Standard include the following

Application Factor account for dynamic overloads from sources external to the gearing.

Dynamic Factor allows for internally generated dynamic loads caused by vibrations of the pinion and wheel against each other.

Load Distribution makes allowance for the effects of non-uniform distribution of load across the face width, depending on the mesh alignment error of the loaded gear pair and the mesh stiffness.

Transverse Load Distribution Factor takes into account the effect of the load distribution on gear tooth contact stresses.

Gear Tooth Stiffness Constants are defined as the load needed to deform one or several meshing gear teeth having 1 mm face width, by an amount of 1 μm (0.00004 in).

Allowable Contact Stress is the permissible Hertzian pressure on the gear tooth face.

Minimum demanded and Calculated Safety Factors The minimum demanded safety factor is agreed between the supplier and the customer. The calculated safety factor is the actual safety factor of the gear pair.

Zone Factor accounts for the influence on the Hertzian pressure of the tooth flank curvature at the pitch point.

Elasticity Factor takes account of the influence of the material properties such as the modulus of elasticity and Poisson's ratio.

Contact Ratio Factor accounts for the influence of the transverse contact ratio and the overlap ratio on the specific surface load of the gears.

Helix Angle Factor makes allowance for influence of helix angle on surface durability.

Endurance Limit is the limit of repeated Hertzian stresses that can be permanently endured by a given material

Life Factor takes account of a higher permissible Hertzian stress if only limited durability is demanded.

Lubrication Film Factor The film of lubricant between the tooth flanks influences the surface load capacity. Factors include the oil viscosity, pitch line velocity and roughness of the tooth flanks.

Work Hardening Factor takes account of the increase in surface durability due to meshing a steel wheel with a hardened pinion having smooth tooth surfaces.

Coefficient of Friction The mean value of the local coefficient of friction depends on the lubricant, surface roughness, the lay of surface irregularities, material properties of the tooth flanks, and the force and size of tangential velocities.

Copyright 2004, Industrial Press, Inc., New York, NY

Bulk Temperature Thermal Flash Factor is dependent on moduli of elasticity and thermal contact coefficients of pinion and wheel materials and geometry of the line of action.

Welding Factor Accounts for different tooth materials and heat treatments.

Geometrical Factor is defined as a function of the gear ratio and the dimensionless parameter on the line of action.

Integral Temperature Criterion The integral temperature of the gears depends on the lubricant viscosity and tendency toward cuffing and scoring of the gear materials.

Examination of the above factors shows the similarity in the approach of the British and the ISO Standards to that of the ANSI/AGMA Standards. Slight variations in the methods used to calculate the factors will result in different allowable stress figures. Experimental work using some of the stressing formulas has shown wide variations and designers must continue to rely on experience to arrive at satisfactory results.

Standards Nomenclature

All standards are referenced and identified throughout this book by an alphanumeric prefix which designates the organization that administered the development work on the standard, and followed by a standards number.

All standards are reviewed by the relevant committees at regular time intervals, as specified by the overseeing standards organization, to determine whether the standard should be confirmed (reissued without changes other than correction of typographical errors), updated, or removed from service.

The following is for example use only. ANSI B18.8.2-1984, R1994 is a standard for Taper, Dowel, Straight, Grooved, and Spring Pins. ANSI refers to the American National Standards Institute that is responsible for overseeing the development or approval of the standard, and B18.8.2 is the number of the standard. The first date, 1984, indicates the year in which the standard was issued, and the sequence R1994 indicates that this standard was reviewed and reaffirmed in that 1994. The current designation of the standard, ANSI/ASME B18.8.2-1995, indicates that it was revised in 1995; it is ANSI approved; and, ASME (American Society of Mechanical Engineers) was the standards body responsible for development of the standard. This standard is sometimes also designated ASME B18.8.2-1995.

ISO (International Organization for Standardization) standards use a slightly different format, for example, ISO 5127-1:1983. The entire ISO reference number consists of a prefix ISO, a serial number, and the year of publication.

Aside from content, ISO standards differ from American National standards in that they often smaller focused documents, which in turn reference other standards or other parts of the same standard. Unlike the numbering scheme used by ANSI, ISO standards related to a particular topic often do not carry sequential numbers nor are they in consecutive series.

British Standards Institute standards use the following format: BS 1361: 1971 (1986). The first part is the organization prefix BS, followed by the reference number and the date of issue. The number in parenthesis is the date that the standard was most recently reconfirmed. British Standards may also be designated *withdrawn* (no longer to be used) and *obsolescent* (going out of use, but may be used for servicing older equipment).

Organization	Web Address	Organization	Web Address
ISO (International Organization for Standardization)	www.iso.ch	JIS (Japanese Industrial Standards)	www.jisc.org
IEC (International Electrotechnical Commission)	www.iec.ch	ASME (American Society of Mechanical Engineers)	www.asme.org
ANSI (American National Standards Institute)	www.ansi.org	SAE (Society of Automotive Engineers)	www.sae.org
BSI (British Standards Institute)	www.bsi-inc.org	SME (Society of Manufacturing Engineers)	www.sme.org

Copyright 2004, Industrial Press, Inc., New York, NY

HYPOID AND BEVEL GEARING

Hypoid Gears

Hypoid gears are offset and in effect, are spiral gears whose axes do not intersect but are staggered by an amount decided by the application. Due to the offset, contact between the teeth of the two gears does not occur along a surface line of the cones as it does with spiral bevels having intersecting axes, but along a curve in space inclined to the surface line. The basic solids of the hypoid gear members are not cones, as in spiral bevels, but are hyperboloids of revolution which cannot be projected into the common plane of ordinary flat gears, thus the name hypoid. The visualization of hypoid gears is based on an imaginary flat gear which is a substitute for the theoretically correct helical surface. If certain rules are observed during the calculations to fix the gear dimensions, the errors that result from the use of an imaginary flat gear as an approximation are negligible.

The staggered axes result in meshing conditions that are beneficial to the strength and running properties of the gear teeth. A uniform sliding action takes place between the teeth, not only in the direction of the tooth profile but also longitudinally, producing ideal conditions for movement of lubricants. With spiral gears, great differences in sliding motion arise over various portions of the tooth surface, creating vibration and noise. Hypoid gears are almost free from the problems of differences in these sliding motions and the teeth also have larger curvature radii in the direction of the profile. Surface pressures are thus reduced so that there is less wear and quieter operation.

The teeth of hypoid gears are 1.5 to 2 times stronger than those of spiral bevel gears of the same dimensions, made from the same material. Certain limits must be imposed on the dimensions of hypoid gear teeth so that their proportions can be calculated in the same way as they are for spiral bevel gears. The offset must not be larger than 1/7th of the ring gear outer diameter, and the tooth ratio must not be much less than 4 to 1. Within these limits, the tooth proportions can be calculated in the same way as for spiral bevel gears and the radius of lengthwise curvature can be assumed in such a way that the normal module is a maximum at the center of the tooth face width to produce stabilized tooth bearings.

If the offset is larger or the ratio is smaller than specified above, a tooth form must be selected that is better adapted to the modified meshing conditions. In particular, the curvature of the tooth length curve must be determined with other points in view. The limits are only guidelines since it is impossible to account for all other factors involved, including the pitch line speed of the gears, lubrication, loads, design of shafts and bearings, and the general conditions of operation.

Of the three different designs of hypoid bevel gears now available, the most widely used, especially in the automobile industry, is the Gleason system. Two other hypoid gear systems have been introduced by Oerlikon (Swiss) and Klingelnberg (German). All three methods use the involute gear form, but they have teeth with differing curvatures, produced by the cutting method. Teeth in the Gleason system are arc shaped and their depth tapers. Both the European systems are designed to combine rolling with the sideways motion of the teeth and use a constant tooth depth. Oerlikon uses an epicycloidal tooth form and Klingelnberg uses a true involute form.

With their circular arcuate tooth face curves, Gleason hypoid gears are produced with multi-bladed face milling cutters. The gear blank is rolled relative to the rotating cutter to make one inter-tooth groove, then the cutter is withdrawn and returned to its starting position while the blank is indexed into the position for cutting the next tooth. Both roughing and finishing cutters are kept parallel to the tooth root lines, which are at an angle to the gear pitch line. Depending on this angularity, plus the spiral angle, a correction factor must be calculated for both the leading and trailing faces of the gear tooth.

In operation, the convex faces of the teeth on one gear always bear on the concave faces of the teeth on the mating gear. For correct meshing between the pinion and gear wheel, the

Copyright 2004, Industrial Press, Inc., New York, NY

spiral angles should not vary over the full face width. The tooth form generated is a logarithmic spiral and, as a compromise, the cutter radius is made equal to the mean radius of a corresponding logarithmic spiral.

The involute tooth face curves of the Klingelnberg system gears have constant-pitch teeth cut by (usually) a single-start taper hob. The machine is set up to rotate both the cutter and the gear blank at the correct relative speeds. The surface of the hob is set tangential to a circle radius, which is the gear base circle, from which all the parallel involute curves are struck. To keep the hob size within reasonable dimensions, the cone must lie a minimum distance within the teeth and this requirement governs the size of the module.

Both the module and the tooth depth are constant over the full face width and the spiral angle varies. The cutting speed variations, especially with regard to crown wheels, over the cone surface of the hob, make it difficult to produce a uniform surface finish on the teeth, so a finishing cut is usually made with a truncated hob which is tilted to produce the required amount of crowning automatically, for correct tooth marking and finishing. The dependence of the module, spiral angle and other features on the base circle radius, and the need for suitable hob proportions restrict the gear dimensions and the system cannot be used for gears with a low or zero angle. However, gears can be cut with a large root radius giving teeth of high strength. The favorable geometry of the tooth form gives quieter running and tolerance of inaccuracies in assembly.

Teeth of gears made by the Oerlikon system have elongated epicycloidal form, produced with a face-type rotating cutter. Both the cutter and the gear blank rotate continuously, with no indexing. The cutter head has separate groups of cutters for roughing, outside cutting and inside cutting so that tooth roots and flanks are cut simultaneously, but the feed is divided into two stages. As stresses are released during cutting, there is some distortion of the blank and this distortion will usually be worse for a hollow crown wheel than for a solid pinion.

All the heavy cuts are taken during the first stages of machining with the Oerlikon system and the second stage is used to finish the tooth profile accurately, so distortion effects are minimized. As with the Klingelnberg process, the Oerlikon system produces a variation in spiral angle and module over the width of the face, but unlike the Klingelnberg method, the tooth length curve is cycloidal. It is claimed that, under load, the tilting force in an Oerlikon gear set acts at a point 0.4 times the distance from the small diameter end of the gear and not in the mid-tooth position as in other gear systems, so that the radius is obviously smaller and the tilting moment is reduced, resulting in lower loading of the bearings.

Gears cut by the Oerlikon system have tooth markings of different shape than gears cut by other systems, showing that more of the face width of the Oerlikon tooth is involved in the load-bearing pattern. Thus, the surface loading is spread over a greater area and becomes lighter at the points of contact.

Bevel Gearing

Types of Bevel Gears.— Bevel gears are conical gears, that is, gears in the shape of cones, and are used to connect shafts having intersecting axes. Hypoid gears are similar in general form to bevel gears, but operate on axes that are offset. With few exceptions, most bevel gears may be classified as being either of the straight-tooth type or of the curved-tooth type. The latter type includes spiral bevels, Zerol bevels, and hypoid gears. The following is a brief description of the distinguishing characteristics of the different types of bevel gears.

Straight Bevel Gears: The teeth of this most commonly used type of bevel gear are straight but their sides are tapered so that they would intersect the axis at a common point called the pitch cone apex if extended inward. The face cone elements of most straight bevel gears, however, are now made parallel to the root cone elements of the mating gear to obtain uniform clearance along the length of the teeth. The face cone elements of such

Copyright 2004, Industrial Press, Inc., New York, NY

gears, therefore, would intersect the axis at a point inside the pitch cone. Straight bevel gears are the easiest to calculate and are economical to produce.

Straight bevel gear teeth may be generated for full-length contact or for localized contact. The latter are slightly convex in a lengthwise direction so that some adjustment of the gears during assembly is possible and small displacements due to load deflections can occur without undesirable load concentration on the ends of the teeth. This slight lengthwise rounding of the tooth sides need not be computed in the design but is taken care of automatically in the cutting operation on the newer types of bevel gear generators.

Zerol Bevel Gears: The teeth of Zerol bevel gears are curved but lie in the same general direction as the teeth of straight bevel gears. They may be thought of as spiral bevel gears of zero spiral angle and are manufactured on the same machines as spiral bevel gears. The face cone elements of Zerol bevel gears do not pass through the pitch cone apex but instead are approximately parallel to the root cone elements of the mating gear to provide uniform tooth clearance. The root cone elements also do not pass through the pitch cone apex because of the manner in which these gears are cut. Zerol bevel gears are used in place of straight bevel gears when generating equipment of the spiral type but not the straight type is available, and may be used when hardened bevel gears of high accuracy (produced by grinding) are required.

Spiral Bevel Gears: Spiral bevel gears have curved oblique teeth on which contact begins gradually and continues smoothly from end to end. They mesh with a rolling contact similar to straight bevel gears. As a result of their overlapping tooth action, however, spiral bevel gears will transmit motion more smoothly than straight bevel or Zerol bevel gears, reducing noise and vibration that become especially noticeable at high speeds.

One of the advantages associated with spiral bevel gears is the complete control of the localized tooth contact. By making a slight change in the radii of curvature of the mating tooth surfaces, the amount of surface over which tooth contact takes place can be changed to suit the specific requirements of each job. Localized tooth contact promotes smooth, quiet running spiral bevel gears, and permits some mounting deflections without concentrating the load dangerously near either end of the tooth. Permissible deflections established by experience are given under the heading *Mountings for Bevel Gears*.

Because their tooth surfaces can be ground, spiral bevel gears have a definite advantage in applications requiring hardened gears of high accuracy. The bottoms of the tooth spaces and the tooth profiles may be ground simultaneously, resulting in a smooth blending of the tooth profile, the tooth fillet, and the bottom of the tooth space. This feature is important from a strength standpoint because it eliminates cutter marks and other surface interruptions that frequently result in stress concentrations.

Hypoid Gears: In general appearance, hypoid gears resemble spiral bevel gears, except that the axis of the pinion is offset relative to the gear axis. If there is sufficient offset, the shafts may pass one another thus permitting the use of a compact straddle mounting on the gear and pinion. Whereas a spiral bevel pinion has equal pressure angles and symmetrical profile curvatures on both sides of the teeth, a hypoid pinion properly conjugate to a mating gear having equal pressure angles on both sides of the teeth must have nonsymmetrical profile curvatures for proper tooth action. In addition, to obtain equal arcs of motion for both sides of the teeth, it is necessary to use unequal pressure angles on hypoid pinions. Hypoid gears are usually designed so that the pinion has a larger spiral angle than the gear. The advantage of such a design is that the pinion diameter is increased and is stronger than a corresponding spiral bevel pinion. This diameter increment permits the use of comparatively high ratios without the pinion becoming too small to allow a bore or shank of adequate size. The sliding action along the lengthwise direction of their teeth in hypoid gears is a function of the difference in the spiral angles on the gear and pinion. This sliding effect makes such gears even smoother running than spiral bevel gears. Grinding of hypoid gears can be accomplished on the same machines used for grinding spiral bevel and Zerol bevel gears.

Copyright 2004, Industrial Press, Inc., New York, NY

Applications of Bevel and Hypoid Gears.— Bevel and hypoid gears may be used to transmit power between shafts at practically any angle and speed. The particular type of gearing best suited for a specific job, however, depends on the mountings and the operating conditions.

Straight and Zerol Bevel Gears: For peripheral speeds up to 1000 feet per minute, where maximum smoothness and quietness are not the primary consideration, straight and Zerol bevel gears are recommended. For such applications, plain bearings may be used for radial and axial loads, although the use of antifriction bearings is always preferable. Plain bearings permit a more compact and less expensive design, which is one reason why straight and Zerol bevel gears are much used in differentials. This type of bevel gearing is the simplest to calculate and set up for cutting, and is ideal for small lots where fixed charges must be kept to a minimum.

Zerol bevel gears are recommended in place of straight bevel gears where hardened gears of high accuracy are required, because Zerol gears may be ground; and when only spiral-type equipment is available for cutting bevel gears.

Spiral Bevel and Hypoid Gears: Spiral bevel and hypoid gears are recommended for applications where peripheral speeds exceed 1000 feet per minute or 1000 revolutions per minute. In many instances, they may be used to advantage at lower speeds, particularly where extreme smoothness and quietness are desired. For peripheral speeds above 8000 feet per minute, ground gears should be used.

For large reduction ratios the use of spiral and hypoid gears will reduce the overall size of the installation because the continuous pitch line contact of these gears makes it practical to obtain smooth performance with a smaller number of teeth in the pinion than is possible with straight or Zerol bevel gears.

Hypoid gears are recommended for industrial applications: when maximum smoothness of operation is desired; for high reduction ratios where compactness of design, smoothness of operation, and maximum pinion strength are important; and for nonintersecting shafts.

Bevel and hypoid gears may be used for both speed-reducing and speed-increasing drives. In speed-increasing drives, however, the ratio should be kept as low as possible and the pinion mounted on antifriction bearings; otherwise bearing friction will cause the drive to lock.

Notes on the Design of Bevel Gear Blanks.— The quality of any finished gear is dependent, to a large degree, on the design and accuracy of the gear blank. A number of factors that affect manufacturing economy as well as performance must be considered.

A gear blank should be designed to avoid localized stresses and serious deflections within itself. Sufficient thickness of metal should be provided under the roots of gear teeth to give them proper support. As a general rule, the amount of metal under the root should equal the whole depth of the tooth; this metal depth should be maintained under the small ends of the teeth as well as under the middle. On webless-type ring gears, the minimum stock between the root line and the bottom of tap drill holes should be one-third the tooth depth. For heavily loaded gears, a preliminary analysis of the direction and magnitude of the forces is helpful in the design of both the gear and its mounting. Rigidity is also necessary for proper chucking when cutting the teeth. For this reason, bores, hubs, and other locating surfaces must be in proper proportion to the diameter and pitch of the gear. Small bores, thin webs, or any condition that necessitates excessive overhang in cutting should be avoided.

Other factors to be considered are the ease of machining and, in gears that are to be hardened, proper design to ensure the best hardening conditions. It is desirable to provide a locating surface of generous size on the backs of gears. This surface should be machined or ground square with the bore and is used both for locating the gear axially in assembly and for holding it when the teeth are cut. The front clamping surface must, of course, be flat and parallel to the back surface. In connection with cutting the teeth on Zerol bevel, spiral

Copyright 2004, Industrial Press, Inc., New York, NY

bevel, and hypoid gears, clearance must be provided for face-mill type cutters; front and rear hubs should not intersect the extended root line of the gear or they will interfere with the path of the cutter. In addition, there must be enough room in the front of the gear for the clamp nut that holds the gear on the arbor, or in the chuck, while cutting the teeth. The same considerations must be given to straight bevel gears that are to be generated using a circular-type cutter instead of reciprocating tools.

Mountings for Bevel Gears.— Rigid mountings should be provided for bevel gears to keep the displacements of the gears under operating loads within recommended limits. To align gears properly, care should be taken to ensure accurately machined mountings, properly fitted keys, and couplings that run true and square.

As a result of deflection tests on gears and their mountings, and having observed these same units in service, the *Gleason Works* recommends that the following allowable deflections be used for gears from 6 to 15 inches in diameter: neither the pinion nor the gear should lift or depress more than 0.003 inch at the center of the face width; the pinion should not yield axially more than 0.003 inch in either direction; and the gear should not yield axially more than 0.003 inch in either direction on 1 to 1 ratio gears (miter gears), or near miters, or more than 0.010 inch away from the pinion on higher ratios.

When deflections exceed these limits, additional problems are involved in obtaining satisfactory gears. It becomes necessary to narrow and shorten the tooth contacts to suit the more flexible mounting. These changes decrease the bearing area, raise the unit tooth pressure, and reduce the number of teeth in contact, resulting in increased noise and the danger of surface failure as well as tooth breakage.

Spiral bevel and hypoid gears in general should be mounted on antifriction bearings in an oil-tight case. Designs for a given set of conditions may use plain bearings for radial and thrust loads, maintaining gears in satisfactory alignment is usually more easily accomplished with ball or roller bearings.

Bearing Spacing and Shaft Stiffness: Bearing spacing and shaft stiffness are extremely important if gear deflections are to be minimized. For both straddle mounted and overhung mounted gears the spread between bearings should never be less than 70 per cent of the pitch diameter of the gear. On overhung mounted gears the spread should be at least 2½ times the overhang and, in addition, the shaft diameter should be equal to or preferably greater than the overhang to provide sufficient shaft stiffness. When two spiral bevel or hypoid gears are mounted on the same shaft, the axial thrust should be taken at one place only and near the gear where the greater thrust is developed. Provision should be made for adjusting both the gear and pinion axially in assembly. Details on how this may be accomplished are given in the *Gleason Works* booklet, "Assembling Bevel Gears."

Cutting Bevel Gear Teeth.— A correctly formed bevel gear tooth has the same sectional shape throughout its length, but on a uniformly diminishing scale from the large to the small end. The only way to obtain this correct form is by using a generating type of bevel gear cutting machine. This accounts, in part, for the extensive use of generating type gear cutting equipment in the production of bevel gears.

Bevel gears too large to be cut by generating equipment (100 inches or over in diameter) may be produced by a form-copying type of gear planer. With this method, a template or former is used to mechanically guide a single cutting tool in the proper path to cut the profile of the teeth. Since the tooth profile produced by this method is dependent on the contour of the template used, it is possible to produce tooth profiles to suit a variety of requirements.

Although generating methods are to be preferred, there are still some cases where straight bevel gears are produced by milling. Milled gears cannot be produced with the accuracy of generated gears and generally are not suitable for use in high-speed applications or where angular motion must be transmitted with a high degree of accuracy. Milled gears are used chiefly as replacement gears in certain applications, and gears which are

Copyright 2004, Industrial Press, Inc., New York, NY

subsequently to be finished on generating type equipment are sometimes roughed out by milling. Formulas and methods used for the cutting of bevel gears are given in the latter part of this section.

In producing gears by generating methods, the tooth curvature is generated from a straight-sided cutter or tool having an angle equal to the required pressure angle. This tool represents the side of a crown gear tooth. The teeth of a true involute crown gear, however, have sides which are very slightly curved. If the curvature of the cutting tool conforms to that of the involute crown gear, an involute form of bevel gear tooth will be obtained. The use of a straight-sided tool is more practical and results in a very slight change of tooth shape to what is known as the "octoid" form. Both the octoid and involute forms of bevel gear tooth give theoretically correct action.

Bevel gear teeth, like those for spur gears, differ as to pressure angle and tooth proportions. The whole depth and the addendum at the large end of the tooth may be the same as for a spur gear of equal pitch. Most bevel gears, however, both of the straight tooth and spiral-bevel types, have lengthened pinion addendums and shortened gear addendums as in the case of some spur gears, the amount of departure from equal addendums varying with the ratio of gearing. Long addendums on the pinion are used principally to avoid undercut and to increase tooth strength. In addition, where long and short addendums are used, the tooth thickness of the gear is decreased and that of the pinion increased to provide a better balance of strength. See the Gleason Works System for straight and spiral bevel gears and also the British Standard.

Nomenclature for Bevel Gears.— The accompanying diagram, Fig. 1a, *Bevel Gear Nomenclature*, illustrates various angles and dimensions referred to in describing bevel gears. In connection with the face angles shown in the diagram, it should be noted that the face cones are made parallel to the root cones of the mating gears to provide uniform clearance along the length of the teeth. See also Fig. 1b, page 2087.

American Standard for Bevel Gears.— American Standard ANSI/AGMA 2005-B88, Design Manual for Bevel Gears, replaces AGMA Standards 202.03, 208.03, 209.04, and 330.01, and provides standards for design of straight, zerol, and spiral bevel gears and hypoid gears with information on fabrication, inspection, and mounting. The information covers preliminary design, drawing formats, materials, rating, strength, inspection, lubrication, mountings, and assembly. Blanks for standard taper, uniform depth, duplex taper, and tilted root designs are included so that the material applies to users of Gleason, Klingelnberg, and Oerlikon gear cutting machines.

Formulas for Dimensions of Milled Bevel Gears.— As explained earlier, most bevel gears are produced by generating methods. Even so, there are applications for which it may be desired to cut a pair of mating bevel gears by using rotary formed milling cutters. Examples of such applications include replacement gears for certain types of equipment and gears for use in experimental developments.

The tooth proportions of milled bevel gears differ in some respects from those of generated gears, the principal difference being that for milled bevel gears the tooth thicknesses of pinion and gear are made equal, and the addendum and dedendum of the pinion are respectively the same as those of the gear. The rules and formulas in the accompanying table may be used to calculate the dimensions of milled bevel gears with shafts at a right angle, an acute angle, and an obtuse angle.

In the accompanying diagrams, Figs. 1a and 1b, and list of notations, the various terms and symbols applied to milled bevel gears are as indicated.

N = number of teeth
P = diametral pitch
p = circular pitch
α = pitch cone angle and edge angle
Σ = angle between shafts

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1a. Bevel Gear Nomenclature

D = pitch diameter
S = addendum
$S+A$ = dedendum (A = clearance)
W = whole depth of tooth
T = thickness of tooth at pitch line
C = pitch cone radius
F = width of face
s = addendum at small end of tooth
t = thickness of tooth at pitch line at small end
θ = addendum angle
ϕ = dedendum angle
γ = face angle = pitch cone angle + addendum angle
δ = angle of compound rest
ζ = cutting angle
K = angular addendum
O = outside diameter
J = vertex distance

Copyright 2004, Industrial Press, Inc., New York, NY

j = vertex distance at small end
N' = number of teeth for which to select cutter



Fig. 1b. Bevel Gear Nomenclature

The formulas for milled bevel gears should be modified to make the clearance at the bottom of the teeth uniform instead of tapering toward the vertex. If this recommendation is followed, then the cutting angle (root angle) should be determined by subtracting the *addendum* angle from the pitch cone angle instead of subtracting the dedendum angle as in the formula given in the table.

Rules and Formulas for Calculating Dimensions of Milled Bevel Gears

To Find	Rule	Formula
Pitch Cone Angle of Pinion	Divide the sine of the shaft angle by the sum of the cosine of the shaft angle and the quotient obtained by dividing the number of teeth in the gear by the number of teeth in the pinion; this gives the tangent. *Note:* For shaft angles greater than 90° the cosine is negative.	$\tan\alpha_P = \dfrac{\sin\Sigma}{\dfrac{N_G}{N_P} + \cos\Sigma}$ For 90° shaft angle, $\tan\alpha_P = \dfrac{N_P}{N_G}$
Pitch Cone Angle of Gear	Subtract the pitch cone angle of the pinion from the shaft angle.	$\alpha_G = \Sigma - \alpha_P$
Pitch Diameter	Divide the number of teeth by the diametral pitch.	$D = N \div P$

Copyright 2004, Industrial Press, Inc., New York, NY

Rules and Formulas for Calculating Dimensions of Milled Bevel Gears *(Continued)*

To Find		Rule	Formula
These dimensions are the same for both gear and pinion.	Addendum	Divide 1 by the diametral pitch.	$S = 1 \div P$
	Dedendum	Divide 1.157 by the diametral pitch.	$S + A = 1.157 \div P$
	Whole Depth of Tooth	Divide 2.157 by the diametral pitch.	$W = 2.157 \div P$
	Thickness of Tooth at Pitch Line	Divide 1.571 by the diametral pitch.	$T = 1.571 \div P$
	Pitch Cone Radius	Divide the pitch diameter by twice the sine of the pitch cone angle.	$C = \frac{D}{2 \times \sin\alpha}$
	Addendum of Small End of Tooth	Subtract the width of face from the pitch cone radius, divide the remainder by the pitch cone radius and multiply by the addendum.	$s = S \times \frac{C - F}{C}$
	Thickness of Tooth at Pitch Line at Small End	Subtract the width of face from the pitch cone radius, divide the remainder by the pitch cone radius and multiply by the thickness of the tooth at pitch line.	$t = T \times \frac{C - F}{C}$
	Addendum Angle	Divide the addendum by the pitch cone radius to get the tangent.	$\tan\theta = \frac{S}{C}$
	Dedendum Angle	Divide the dedendum by the pitch cone radius to get the tangent.	$\tan\phi = \frac{S + A}{C}$
	Face Width (Max.)	Divide the pitch cone radius by 3 or divide 8 by the diametral pitch, whichever gives the smaller value.	$F = \frac{C}{3}$ or $F = \frac{8}{P}$
	Circular Pitch	Divide 3.1416 by the diametral pitch.	$\rho = 3.1416 \div P$
Face Angle		Add the addendum angle to the pitch cone angle	$\gamma = \alpha + \theta$
Compound Rest Angle for Turning Blank		Subtract both the pitch cone angle and the addendum angle from 90 degrees.	$\delta = 90° - \alpha - \theta$
Cutting Angle		Subtract the dedendum angle from the pitch cone angle.	$\zeta = \alpha - \phi$
Angular Addendum		Multiply the addendum by the cosine of the pitch cone angle.	$K = \mathrm{S} \times \cos\alpha$
Outside Diameter		Add twice the angular addendum to the pitch diameter.	$O = D + 2K$
Vertex or Apex Distance		Multiply one-half the outside diameter by the cotangent of the face angle.	$J = \frac{O}{2} \times \cot\gamma$
Vertex Distance at Small End of Tooth		Subtract the width of face from the pitch cone radius; divide the remainder by the pitch cone radius and multiply by the apex distance.	$j = J \times \frac{C - F}{C}$
Number of Teeth for which to Select Cutter		Divide the number of teeth by the cosine of the pitch cone angle.	$N' = \frac{N}{\cos\alpha}$

Copyright 2004, Industrial Press, Inc., New York, NY

Numbers of Formed Cutters Used to Mill Teeth in Mating Bevel Gear and Pinion with Shafts at Right Angles

		Number of Teeth in Pinion																
		12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
Number of Teeth in Gear	12	7-7	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…
	13	6-7	6-6	…	…	…	…	…	…	…	…	…	…	…	…	…	…	…
	14	5-7	6-6	6-6	…	…	…	…	…	…	…	…	…	…	…	…	…	…
	15	5-7	5-6	5-6	5-5	…	…	…	…	…	…	…	…	…	…	…	…	…
	16	4-7	5-7	5-6	5-6	5-5	…	…	…	…	…	…	…	…	…	…	…	…
	17	4-7	4-7	4-6	5-6	5-5	5-5	…	…	…	…	…	…	…	…	…	…	…
	18	4-7	4-7	4-6	4-6	4-5	4-5	5-5	…	…	…	…	…	…	…	…	…	…
	19	3-7	4-7	4-6	4-6	4-6	4-5	4-5	4-4	…	…	…	…	…	…	…	…	…
	20	3-7	3-7	4-6	4-6	4-6	4-5	4-5	4-4	4-4	…	…	…	…	…	…	…	…
	21	3-8	3-7	3-7	3-6	4-6	4-5	4-5	4-5	4-4	4-4	…	…	…	…	…	…	…
	22	3-8	3-7	3-7	3-6	3-6	3-5	4-5	4-5	4-4	4-4	4-4	…	…	…	…	…	…
	23	3-8	3-7	3-7	3-6	3-6	3-5	3-5	3-5	3-4	4-4	4-4	4-4	…	…	…	…	…
	24	3-8	3-7	3-7	3-6	3-6	3-6	3-5	3-5	3-4	3-4	3-4	4-4	4-4	…	…	…	…
	25	2-8	2-7	3-7	3-6	3-6	3-6	3-5	3-5	3-5	3-4	3-4	3-4	4-4	3-3	…	…	…
	26	2-8	2-7	3-7	3-6	3-6	3-6	3-5	3-5	3-5	3-4	3-4	3-4	3-4	3-3	3-3	…	…
	27	2-8	2-7	2-7	2-6	3-6	3-6	3-5	3-5	3-5	3-4	3-4	3-4	3-4	3-4	3-3	3-3	…
	28	2-8	2-7	2-7	2-6	2-6	3-6	3-5	3-5	3-5	3-4	3-4	3-4	3-4	3-4	3-3	3-3	3-3
	29	2-8	2-7	2-7	2-7	2-6	2-6	3-5	3-5	3-5	3-4	3-4	3-4	3-4	3-4	3-3	3-3	3-3
	30	2-8	2-7	2-7	2-7	2-6	2-6	2-5	2-5	3-5	3-5	3-4	3-4	3-4	3-4	3-4	3-3	3-3
	31	2-8	2-7	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	3-4	3-4	3-4	3-4	3-4	3-3	3-3
	32	2-8	2-7	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-4	2-4	3-4	3-4	3-4	3-3	3-3
	33	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-4	2-4	2-4	3-4	3-4	3-4	3-3
	34	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	3-4	3-3
	35	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-4	2-3
	36	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-3
	37	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-3
	38	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-4
	39	2-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-4
	40	1-8	2-8	2-7	2-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-4
	41	1-8	1-8	2-7	2-7	2-6	2-6	2-6	2-6	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4	2-4
	42	1-8	1-8	2-7	2-7	2-6	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	43	1-8	1-8	1-7	2-7	2-6	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	44	1-8	1-8	1-7	1-7	2-6	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	45	1-8	1-8	1-7	1-7	1-6	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	46	1-8	1-8	1-7	1-7	1-7	2-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	47	1-8	1-8	1-7	1-7	1-7	1-6	2-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	48	1-8	1-8	1-7	1-7	1-7	1-6	1-6	2-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	49	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	50	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	2-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	51	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-5	2-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	52	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-5	1-5	2-5	2-5	2-4	2-4	2-4	2-4	2-4
	53	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-5	1-5	1-5	2-5	2-4	2-4	2-4	2-4	2-4
	54	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-5	1-5	1-5	1-5	2-4	2-4	2-4	2-4	2-4
	55	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	2-4	2-4	2-4	2-4

Copyright 2004, Industrial Press, Inc., New York, NY

Numbers of Formed Cutters Used to Mill Teeth in Mating Bevel Gear and Pinion with Shafts at Right Angles *(Continued)*

Number of Teeth in Gear	Number of Teeth in Pinion																	
		12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
	56	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	2-4	2-4	2-4
	57	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	2-4	2-4
	58	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4	2-4
	59	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	60	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	61	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	62	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	63	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	64	1-8	1-8	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	65	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	66	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	67	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	68	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	69	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	70	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	71	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	72	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	73	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	74	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	75	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	76	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	77	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	78	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	79	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	80	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	81	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	82	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	83	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	84	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	85	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	86	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	87	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	88	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	89	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	90	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	91	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	92	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	93	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	94	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	95	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	96	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	97	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	98	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	99	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4
	100	1-8	1-8	1-7	1-7	1-7	1-6	1-6	1-6	1-6	1-5	1-5	1-5	1-5	1-4	1-4	1-4	1-4

Number of cutter for gear given first, followed by number for pinion. See text, page 2091

Copyright 2004, Industrial Press, Inc., New York, NY

Selecting Formed Cutters for Milling Bevel Gears.— For milling 14½-degree pressure angle bevel gears, the standard cutter series furnished by manufacturers of formed milling cutters is commonly used. There are 8 cutters in the series for each diametral pitch to cover the full range from a 12-tooth pinion to a crown gear. The difference between formed cutters used for milling spur gears and those used for bevel gears is that bevel gear cutters are thinner because they must pass through the narrow tooth space at the small end of the bevel gear; otherwise the shape of the cutter and hence, the cutter number, are the same.

To select the proper number of cutter to be used when a bevel gear is to be milled, it is necessary, first, to compute what is called the "Number of Teeth, N' for which to Select Cutter." This number of teeth can then be used to select the proper number of bevel gear cutter from the spur gear milling cutter table on page 2054. The value of N' may be computed using the last formula in the table on page 2087.

Example 1: What numbers of cutters are required for a pair of bevel gears of 4 diametral pitch and 70 degree shaft angle if the gear has 50 teeth and the pinion 20 teeth?

The pitch cone angle of the pinion is determined by using the first formula in the table on page 2087:

$$\tan\alpha_P = \frac{\sin\Sigma}{\frac{N_G}{N_P} + \cos\Sigma} = \frac{\sin 70°}{\frac{50}{20} + \cos 70°} = 0.33064;\ \alpha_P = 18°18'$$

The pitch cone angle of the gear is determined from the second formula in the table on page 2087:

$$\alpha_G = \Sigma - \alpha_P = 70° - 18°18' = 51°42'$$

The numbers of teeth N′ for which to select the cutters for the gear and pinion may now be determined from the last formula in the table on page 2087:

$$N' \text{ for the pinion} = \frac{N_P}{\cos\alpha_P} = \frac{20}{\cos 18°18'} = 21.1 \approx 21 \text{ teeth}$$

$$N' \text{ for the gear} = \frac{N_G}{\cos\alpha_G} = \frac{50}{\cos 51°42'} = 80.7 \approx 81 \text{ teeth}$$

From the table on page 2054 the numbers of the cutters for pinion and gear are found to be, respectively, 5 and 2.

Example 2: Required the cutters for a pair of bevel gears where the gear has 24 teeth and the pinion 12 teeth. The shaft angle is 90 degrees. As in the first example, the formulas given in the table on page 2087 will be used.

$$\tan\alpha_P = N_P \div N_G = 12 \div 24 = 0.5000 \text{ and } \alpha_P = 26°34'$$

$$\alpha_G = \Sigma - \alpha_P = 90° - 26°34' = 63°26'$$

$$N' \text{ for pinion} = 12 \div \cos 26°34' = 13.4 \approx 13 \text{ teeth}$$

$$N' \text{ for gear} = 24 \div \cos 63°26' = 53.6 \approx 54 \text{ teeth}$$

And from the table on page 2054 the cutters for pinion and gear are found to be, respectively, 8 and 3.

Use of Table for Selecting Formed Cutters for Milling Bevel Gears.— The table beginning on page 2089 gives the numbers of cutters to use for milling various numbers of teeth in the gear and pinion. The table applies only to bevel gears with axes at right angles. Thus, in Example 2 given above, the numbers of the cutters could have been obtained directly by entering the table with the actual numbers of teeth in the gear, 24, and the pinion, 12.

Copyright 2004, Industrial Press, Inc., New York, NY

Offset of Cutter for Milling Bevel Gears.— When milling bevel gears with a rotary formed cutter, it is necessary to take two cuts through each tooth space with the gear blank slightly off center, first on one side and then on the other, to obtain a tooth of approximately the correct form. The gear blank is also rotated proportionately to obtain the proper tooth thickness at the large and small ends. The amount that the gear blank or cutter should be offset from the central position can be determined quite accurately by the use of the table *Factors for Obtaining Offset for Milling Bevel Gears* in conjunction with the following rule: Find the factor in the table corresponding to the number of cutter used and to the ratio of the pitch cone radius to the face width; then divide this factor by the diametral pitch and subtract the result from half the thickness of the cutter at the pitch line.

Factors for Obtaining Offset for Milling Bevel Gears

No. of Cutter	Ratio of Pitch Cone Radius to Width of Face $\left(\frac{C}{F}\right)$												
	3/1	3¼/1	3½/1	3¾/1	4/1	4¼/1	4½/1	4¾/1	5/1	5½/1	6/1	7/1	8/1
1	0.254	0.254	0.255	0.256	0.257	0.257	0.257	0.258	0.258	0.259	0.260	0.262	0.264
2	0.266	0.268	0.271	0.272	0.273	0.274	0.274	0.275	0.277	0.279	0.280	0.283	0.284
3	0.266	0.268	0.271	0.273	0.275	0.278	0.280	0.282	0.283	0.286	0.287	0.290	0.292
4	0.275	0.280	0.285	0.287	0.291	0.293	0.296	0.298	0.298	0.302	0.305	0.308	0.311
5	0.280	0.285	0.290	0.293	0.295	0.296	0.298	0.300	0.302	0.307	0.309	0.313	0.315
6	0.311	0.318	0.323	0.328	0.330	0.334	0.337	0.340	0.343	0.348	0.352	0.356	0.362
7	0.289	0.298	0.308	0.316	0.324	0.329	0.334	0.338	0.343	0.350	0.360	0.370	0.376
8	0.275	0.286	0.296	0.309	0.319	0.331	0.338	0.344	0.352	0.361	0.368	0.380	0.386

Note.—For obtaining offset by above table, use formula:

$$\text{Offset} = \frac{T}{2} - \frac{\text{factor from table}}{P}$$

P = diametral pitch of gear to be cut

T = thickness of cutter used, measured at pitch line

To illustrate, what would be the amount of offset for a bevel gear having 24 teeth, 6 diametral pitch, 30-degree pitch cone angle and 1¼-inch face or tooth length? In order to obtain a factor from the table, the ratio of the pitch cone radius to the face width must be determined. The pitch cone radius equals the pitch diameter divided by twice the sine of the pitch cone angle = 4 ÷ (2 × 0.5) = 4 inches. As the face width is 1.25, the ratio is 4 ÷ 1.25 or about 3¼ to 1. The factor in the table for this ratio is 0.280 with a No. 4 cutter, which would be the cutter number for this particular gear. The thickness of the cutter at the pitch line is measured by using a vernier gear tooth caliper. The depth $S + A$ (see Fig. 2; S = addendum; A = clearance) at which to take the measurement equals 1.157 divided by the diametral pitch; thus, 1.157 ÷ 6 = 0.1928 inch. The cutter thickness at this depth will vary with different cutters and even with the same cutter as it is ground away, because formed bevel gear cutters are commonly provided with side relief. Assuming that the thickness is 0.1745 inch, and substituting the values in the formula given, we have:

$$\text{Offset} = \frac{0.1745}{2} = \frac{0.280}{6} = 0.0406 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Adjusting the Gear Blank for Milling.— After the offset is determined, the blank is adjusted laterally by this amount, and the tooth spaces are milled around the blank. After having milled one side of each tooth to the proper dimensions, the blank is set over in the opposite direction the same amount from a position central with the cutter, and is rotated to line up the cutter with a tooth space at the small end. A trial cut is then taken, which will leave the tooth being milled a little too thick, provided the cutter is thin enough—as it should be—to pass through the small end of the tooth space of the finished gear. This trial tooth is made the proper thickness by rotating the blank toward the cutter. To test the amount of offset, measure the tooth thickness (with a vernier caliper) at the large and small ends. The caliper should be set so that the addendum at the small end is in proper proportion to the addendum at the large end; that is, in the ratio, $(C - F)/C$ (see Fig. 2).



Fig. 2.

In taking these measurements, if the thicknesses at both ends (which should be in this same ratio) are too great, rotate the tooth toward the cutter and take trial cuts until the proper thickness at either the large or small end is obtained. If the large end of the tooth is the right thickness and the small end too thick, the blank was offset too much; inversely, if the small end is correct and the large end too thick, the blank was not set enough off center, and, either way, its position should be changed accordingly. The formula and table previously referred to will enable a properly turned blank to be set accurately enough for general work. The dividing head should be set to the cutting angle β (see Fig. 2), which is found by subtracting the addendum angle θ from the pitch cone angle α. After a bevel gear is cut by the method described, the sides of the teeth at the small end should be filed as indicated by the shade lines at *E*; that is, by filing off a triangular area from the point of the tooth at the large end to the point at the small end, thence down to the pitch line and back diagonally to a point at the large end.

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Steels Used for Bevel Gear Applications

SAE or AISI No.	Type of Steel	Purchase Specifications: Preliminary Heat Treatment	Purchase Specifications: Brinell Hardness Number	Purchase Specifications: ASTM Grain Size	Remarks
Carburizing Steels					
1024	Manganese	Normalize			Low Alloy — oil quench limited to thin sections
2512	Nickel Alloy	Normalize — Anneal	163–228	5–8	Aircraft quality
3310 3312X	Nickel-Chromium	Normalize, then heat to 1450°F, cool in furnace. Reheat to1170°F — cool in air	163–228	5–8	Used for maximum resistance to wear and fatigue
4028	Molybdenum	Normalize	163–217		Low Alloy
4615 4620	Nickel-Molybdenum	Normalize — 1700°F–1750°F	163–217	5–8	Good machining qualities. Well adapted to direct quench — gives tough core with minimum distortion
4815 4820	Nickel-Molybdenum	Normalize	163–241	5–8	For aircraft and heavily loaded service
5120	Chromium	Normalize	163–217	5–8	
8615 8620 8715 8720	Chromium-Nickel-Molybdenum	Normalize — cool at hammer	163–217	5–8	Used as an alternate for 4620
Oil Hardening and Flame Hardening Steels					
1141	Sulfurized free-cutting carbon steel	Normalize Heat-treated	179–228 255–269	5 or Coarser	Free-cutting steel used for unhardened gears, oil-treated gears, and for gears to be surface hardened where stresses are low
4140 4640	Chromium-Molybdenum Nickel-Molybdenum	For oil hardening, Normalize — Anneal For surface hardening, Normalize, reheat, quench, and draw	179–212 235–269 269–302 302–341		Used for heat-treated, oil-hardened, and surface-hardened gears. Machine qualities of 4640 are superior to 4140, and it is the preferred steel for flame hardening
6145	Chromium-Vanadium	Normalize — reheat, quench, and draw	235–269 269–302 302–341		Fair machining qualities. Used for surface hardened gears when 4640 is not available
8640 8739	Chromium-Nickel-Molybdenum	Same as for 4640			Used as an alternate for 4640
Nitriding Steels					
Nitralloy H & G	Special Alloy	Anneal	163–192		Normal hardness range for cutting is 20–28 Rockwell C

Other steels with qualities equivalent to those listed in the table may also be used.

Copyright 2004, Industrial Press, Inc., New York, NY

Circular Thickness, Chordal Thickness, and Chordal Addendum of Milled Bevel Gear Teeth.— In the formulas that follow, T = circular tooth thickness on pitch circle at large end of tooth; t = circular thickness at small end; T_c and t_c = chordal thickness at large and small ends, respectively; S_c and s_c = chordal addendum at large and small ends, respectively; D = pitch diameter at large end; and C, F, P, S, s, and α are as defined on page 2085.

$$T = \frac{1.5708}{P} \qquad T_c = T - \frac{T^3}{6D^2} \qquad S_c = S + \frac{T^2 \cos\alpha}{4D}$$

$$t = \frac{T(C-F)}{C} \qquad t_c = t - \frac{t^3}{6(D-2F\sin\alpha)^2} \qquad s_c = s + \frac{t^2\cos\alpha}{4(D-2F\sin\alpha)}$$

Worm Gearing

Worm Gearing.— Worm gearing may be divided into two general classes, fine-pitch worm gearing, and coarse-pitch worm gearing. Fine-pitch worm gearing is segregated from coarse-pitch worm gearing for the following reasons:

1) Fine-pitch worms and wormgears are used largely to transmit motion rather than power. Tooth strength except at the coarser end of the fine-pitch range is seldom an important factor; durability and accuracy, as they affect the transmission of uniform angular motion, are of greater importance.

2) Housing constructions and lubricating methods are, in general, quite different for fine-pitch worm gearing.

3) Because fine-pitch worms and wormgears are so small, profile deviations and tooth bearings cannot be measured with the same accuracy as can those of coarse pitches.

4) Equipment generally available for cutting fine-pitch wormgears has restrictions which limit the diameter, the lead range, the degree of accuracy attainable, and the kind of tooth bearing obtainable.

5) Special consideration must be given to top lands in fine-pitch hardened worms and wormgear-cutting tools.

6) Interchangeability and high production are important factors in fine-pitch worm gearing; individual matching of the worm to the gear, as often practiced with coarse-pitch precision worms, is impractical in the case of fine-pitch worm drives.

American Standard Design for Fine-pitch Worm Gearing (ANSI B6.9-1977).— This standard is intended as a design procedure for fine-pitch worms and wormgears having axes at right angles. It covers cylindrical worms with helical threads, and wormgears hobbed for fully conjugate tooth surfaces. It does not cover helical gears used as wormgears.

Hobs: The hob for producing the gear is a duplicate of the mating worm with regard to tooth profile, number of threads, and lead. The hob differs from the worm principally in that the outside diameter of the hob is larger to allow for resharpening and to provide bottom clearance in the wormgear.

Pitches: Eight standard axial pitches have been established to provide adequate coverage of the pitch range normally required: 0.030, 0.040, 0.050, 0.065, 0.080, 0.100, 0.130, and 0.160 inch.

Axial pitch is used as a basis for this design standard because: 1) Axial pitch establishes lead which is a basic dimension in the production and inspection of worms; 2) the axial pitch of the worm is equal to the circular pitch of the gear in the central plane; and 3) only one set of change gears or one master lead cam is required for a given lead, regardless of lead angle, on commonly-used worm-producing equipment.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Formulas for Proportions of American Standard Fine-pitch Worms and Wormgears *ANSI B6.9-1977*

LETTER SYMBOLS

P = Circular pitch of wormgear
P = axial pitch of the worm, P_x, in the central plane
P_x = Axial pitch of worm
P_n = Normal circular pitch of worm and wormgear = $P_x \cos \lambda = P \cos \psi$
λ = Lead angle of worm
ψ = Helix angle of wormgear
n = Number of threads in worm
N = Number of teeth in wormgear
$N = nm_G$
m_G = Ratio of gearing = $N \div n$



Item	Formula	Item	Formula
WORM DIMENSIONS		WORMGEAR DIMENSIONS[a]	
Lead	$l = nP_x$	Pitch Diameter	$D = NP \div \pi = N\Pi_5 \div \pi$
Pitch Diameter	$d = l \div (\pi \tan \lambda)$	Outside Diameter	$D_o = 2C - d + 2a$
Outside Diameter	$d_o = d + 2a$	Face Width	$F_{G\min} = 1.125 \times \sqrt{(d_o + 2c)^2 - (d_o - 4a)^2}$
Safe Minimum Length of Threaded Portion of Worm[b]	$F_W = \sqrt{D_o^2 - D^2}$		
DIMENSIONS FOR BOTH WORM AND WORMGEAR			
Addendum	$a = 0.3183P_n$	Tooth thickness	$t_n = 0.5P_n$
Whole Depth	$h_t = 0.7003P_n + 0.002$	Approximate normal pressure angle[c]	$\phi_n = 20$ degrees
Working Depth	$h_k = 0.6366P_n$		
Clearance	$c = h_t - h_k$	Center distance	$C = 0.5\,(d + D)$

[a] Current practice for fine-pitch worm gearing does not require the use of throated blanks. This results in the much simpler blank shown in the diagram which is quite similar to that for a spur or helical gear. The slight loss in contact resulting from the use of non-throated blanks has little effect on the load-carrying capacity of fine-pitch worm gears. It is sometimes desirable to use topping hobs for producing wormgears in which the size relation between the outside and pitch diameters must be closely controlled. In such cases the blank is made slightly larger than D_o by an amount (usually from 0.010 to 0.020) depending on the pitch. Topped wormgears will appear to have a small throat which is the result of the hobbing operation. For all intents and purposes, the throating is negligible and a blank so made is not to be considered as being a throated blank.

[b] This formula allows a sufficient length for fine-pitch worms.

[c] As stated in the text on page 2097, the actual pressure angle will be slightly greater due to the manufacturing process.

All dimensions in inches unless otherwise indicated.

Lead Angles: Fifteen standard lead angles have been established to provide adequate coverage: 0.5, 1, 1.5, 2, 3, 4, 5, 7, 9, 11, 14, 17, 21, 25, and 30 degrees.

This series of lead angles has been standardized to: 1) Minimize tooling; 2) permit obtaining geometric similarity between worms of different axial pitch by keeping the same lead angle; and 3) take into account the production distribution found in fine-pitch worm gearing applications.

For example, most fine-pitch worms have either one or two threads. This requires smaller increments at the low end of the lead angle series. For the less frequently used thread num-

Copyright 2004, Industrial Press, Inc., New York, NY

bers, proportionately greater increments at the high end of the lead angle series are sufficient.

Pressure Angle of Worm: A pressure angle of 20 degrees has been selected as standard for cutters and grinding wheels used to produce worms within the scope of this Standard because it avoids objectionable undercutting regardless of lead angle.

Although the pressure angle of the cutter or grinding wheel used to produce the worm is 20 degrees, the normal pressure angle produced in the worm will actually be slightly greater, and will vary with the worm diameter, lead angle, and diameter of cutter or grinding wheel. A method for calculating the pressure angle change is given under the heading *Effect of Production Method on Worm Profile and Pressure Angle*.

Pitch Diameter Range of Worms: The minimum recommended worm pitch diameter is 0.250 inch and the maximum is 2.000 inches.

Tooth Form of Worm and Wormgear: The shape of the worm thread in the normal plane is defined as that which is produced by a symmetrical double-conical cutter or grinding wheel having straight elements and an included angle of 40 degrees.

Because worms and wormgears are closely related to their method of manufacture, it is impossible to specify clearly the tooth form of the wormgear without referring to the mating worm. For this reason, worm specifications should include the method of manufacture and the diameter of cutter or grinding wheel used. Similarly, for determining the shape of the generating tool, information about the method of producing the worm threads must be given to the manufacturer if the tools are to be designed correctly.

The worm profile will be a curve that departs from a straight line by varying amounts, depending on the worm diameter, lead angle, and the cutter or grinding wheel diameter. A method for calculating this deviation is given in the Standard. The tooth form of the wormgear is understood to be made fully conjugate to the mating worm thread.

Effect of Diameter of Cutting on Profile and Pressure Angle of Worms



Effect of Production Method on Worm Profile and Pressure Angle.— In worm gearing, tooth bearing is usually used as the means of judging tooth profile accuracy since direct profile measurements on fine-pitch worms or wormgears is not practical. According to AGMA 370.01, Design Manual for Fine-Pitch Gearing, a minimum of 50 per cent initial area of contact is suitable for most fine-pitch worm gearing, although in some cases, such as when the load fluctuates widely, a more restricted initial area of contact may be desirable.

Except where single-pointed lathe tools, end mills, or cutters of special shape are used in the manufacture of worms, the pressure angle and profile produced by the cutter are differ-

Copyright 2004, Industrial Press, Inc., New York, NY

ent from those of the cutter itself. The amounts of these differences depend on several factors, namely, diameter and lead angle of the worm, thickness and depth of the worm thread, and diameter of the cutter or grinding wheel. The accompanying diagram shows the curvature and pressure angle effects produced in the worm by cutters and grinding wheels, and how the amount of variation in worm profile and pressure angle is influenced by the diameter of the cutting tool used.

Materials for Worm Gearing.— Worm gearing, especially for power transmission, should have steel worms and phosphor bronze wormgears. This combination is used extensively. The worms should be hardened and ground to obtain accuracy and a smooth finish.

The phosphor bronze wormgears should contain from 10 to 12 per cent of tin. The S.A.E. phosphor gear bronze (No. 65) contains 88–90% copper, 10–12% tin, 0.50% lead, 0.50% zinc (but with a maximum total lead, zinc and nickel content of 1.0 per cent), phosphorous 0.10–0.30%, aluminum 0.005%. The S.A.E. nickel phosphor gear bronze (No. 65 + Ni) contains 87% copper, 11% tin, 2% nickel and 0.2% phosphorous.

Single-thread Worms.— The ratio of the worm speed to the wormgear speed may range from 1.5 or even less up to 100 or more. Worm gearing having high ratios are not very efficient as transmitters of power; nevertheless high as well as low ratios often are required. Since the ratio equals the number of wormgear teeth divided by the number of threads or "starts" on the worm, single-thread worms are used to obtain a high ratio. As a general rule, a ratio of 50 is about the maximum recommended for a single worm and wormgear combination, although ratios up to 100 or higher are possible. When a high ratio is required, it may be preferable to use, in combination, two sets of worm gearing of the multi-thread type in preference to one set of the single-thread type in order to obtain the same total reduction and a higher combined efficiency.

Single-thread worms are comparatively inefficient because of the effect of the low lead angle; consequently, single-thread worms are not used when the primary purpose is to transmit power as efficiently as possible but they may be employed either when a large speed reduction with one set of gearing is necessary, or possibly as a means of adjustment, especially if "mechanical advantage" or self-locking are important factors.

Multi-thread Worms.— When worm gearing is designed primarily for transmitting power efficiently, the lead angle of the worm should be as high as is consistent with other requirements and preferably between, say, 25 or 30 and 45 degrees. This means that the worm must be multi-threaded. To obtain a given ratio, some number of wormgear teeth divided by some number of worm threads must equal the ratio. Thus, if the ratio is 6, combinations such as the following might be used:

$$\frac{24}{4}, \frac{30}{5}, \frac{36}{6}, \frac{42}{7}$$

The numerators represent the number of wormgear teeth and the denominators, the number of worm threads or "starts." The number of wormgear teeth may not be an exact multiple of the number of threads on a multi-thread worm in order to obtain a "hunting tooth" action.

Number of Threads or "Starts" on Worm: The number of threads on the worm ordinarily varies from one to six or eight, depending upon the ratio of the gearing. As the ratio is increased, the number of worm threads is reduced, as a general rule. In some cases, however, the higher of two ratios may also have a larger number of threads. For example, a ratio of $6\frac{1}{5}$ would have 5 threads whereas a ratio of $6\frac{5}{6}$ would have 6 threads. Whenever the ratio is fractional, the number of threads on the worm equals the denominator of the fractional part of the ratio.

Copyright 2004, Industrial Press, Inc., New York, NY

HELICAL GEARING

Basic Rules and Formulas for Helical Gear Calculations.— The rules and formulas in the following table and elsewhere in this article are basic to helical gear calculations. The notation used in the formulas is: P_n = normal diametral pitch of cutter; D = pitch diameter; N = number of teeth; α = helix angle; γ = center angle or angle between shafts; C = center distance; N' = number of teeth for which to select a formed cutter for milled teeth; L = lead of tooth helix; S = addendum; W = whole depth; T_n = normal tooth thickness at pitch line; and O = outside diameter.

Rules and Formulas for Helical Gear Calculations



In the formulas, the symbols *D*, *N*, *L*, and α are for either the gear or the pinion. Subscripts *a* and *b* refer to the pinion or gear, respectively, in a pair of gears *a* and *b*.

No.	To Find	Rule	Formula
1	Pitch Diameter	Divide the number of teeth by the product of the normal diameter pitch and the cosine of the helix angle.	$D = \frac{N}{P_n \cos\alpha}$
2	Center Distance	Add together the two pitch diameters and divide by 2.	$C = \frac{D_a + D_b}{2}$
3	Lead of Tooth Helix	Multiply the pitch diameter by 3.1416 by the cotangent of the helix angle.	$L = \pi D \cot\alpha$
4	Addendum	Divide 1 by the normal diametral pitch.	$S = \frac{1}{P_n}$
5	Whole Depth of tooth	Divide 2.157 by the normal diametral pitch.	$W = \frac{2.157}{P_n}$
6	Normal Tooth Thickness at Pitch Line	Divide 1.5708 by the normal diametral pitch.	$T_n = \frac{1.5708}{P_n}$
7	OutsideDiameter	Add twice the addendum to the pitch diameter.	$O = D + 2S$

Determining Direction of Thrust.— The first step in helical gear design is to determine the desired direction of the thrust. When the direction of the thrust has been determined and the relative positions of the driver and driven gears are known, then the direction of helix (right- or left-hand) may be found from the accompanying thrust diagrams, *Directions of Rotation and Resulting Thrust for Parallel Shaft and 90 Degree Shaft Angle Helical Gears*. The diagrams show the directions of rotation and the resulting thrust for parallel-

Copyright 2004, Industrial Press, Inc., New York, NY

shaft and 90-degree shaft angle helical gears. The thrust bearings are located so as to take the thrust caused by the tooth loads. The direction of the thrust depends on the direction of the helix, the relative positions of driver and driven gears, and the direction of rotation. The thrust may be changed to the opposite direction by changing any one of the three conditions, namely, by changing the hand of the helix, by reversing the direction of rotation, or by exchanging of driver and driven gear positions.



Directions of Rotation and Resulting Thrust for Parallel Shaft and 90 Degree Shaft Angle Helical Gears

Determining Helix Angles.— The following rules should be observed for helical gears with shafts at any given angle. If each helix angle is less than the shaft angle, then the sum of the helix angles of the two gears will equal the angle between the shafts, and the helix angle is of the same hand for both gears; if the helix angle of one of the gears is larger than the shaft angle, then the difference between the helix angles of the two gears will be equal to the shaft angle, and the gears will be of opposite hand.

Pitch of Cutter to be Used.— The thickness of the cutter at the pitchline for cutting helical gears should equal one-half the *normal* circular pitch. The normal pitch varies with the helix angle, hence, the helix angle must be considered when selecting a cutter. The cutter should be of the same pitch as the *normal* diametral pitch of the gear. This normal pitch is found by dividing the transverse diametral pitch of the gear by the cosine of the helix angle. To illustrate, if the pitch diameter of a helical gear is 6.718 and there are 38 teeth having a helix angle of 45 degrees, the transverse diametral pitch equals 38 divided by 6.718 = 5.656; then the normal diametral pitch equals 5.656 divided by 0.707 = 8. A cutter, then, of 8 diametral pitch is the one to use for this particular gear.

Helical gears should preferably be cut on a generating-type gear cutting machine such as a hobber or shaper. Milling machines are used in some shops when hobbers or shapers are not available or when single, replacement gears are being made. In such instances, the pitch of the formed cutter used in milling a helical gear must not only conform to the normal diametral pitch of the gear, but the cutter number must also be determined. See *Selecting Cutter for Milling Helical Gears* starting on page 2108.

Copyright 2004, Industrial Press, Inc., New York, NY

1. Shafts Parallel, Center Distance Approximate.— Given or assumed:



1) Position of gear having right- or left-hand helix, depending upon rotation and direction in which thrust is to be received
2) C_a = approximate center distance
3) P_n = normal diametral pitch
4) N = number of teeth in large gear
5) n = number of teeth in small gear
6) α = angle of helix

To find:

1) D = pitch diameter of large gear = $\dfrac{N}{P_n \cos\alpha}$

2) d = pitch diameter of small gear = $\dfrac{n}{P_n \cos\alpha}$

3) O = outside diameter of large gear = $D + \dfrac{2}{P_n}$

4) o = outside diameter of small gear = $d + \dfrac{2}{P_n}$

5) T = number of teeth marked on formed milling cutter (large gear) = $\dfrac{N}{\cos^3\alpha}$

6) t = number of teeth marked on formed milling cutter (small gear) = $\dfrac{n}{\cos^3\alpha}$

7) L = lead of helix on large gear = $\pi D \cot\alpha$
8) l = lead of helix on small gear = $\pi d \cot\alpha$
9) C = center distance (if not right, vary α) = $\frac{1}{2}(D + d)$

Example: Given or assumed: 1) See illustration; 2) $C_a = 17$ inches; 3) $P_n = 2$; 4) $N = 48$; 5) $n = 20$; and 6) $\alpha = 20$.

To find:

1) $D = \dfrac{N}{P_n \cos\alpha} = \dfrac{48}{2 \times 0.9397} = 25.541$ inches

2) $d = \dfrac{n}{P_n \cos\alpha} = \dfrac{20}{2 \times 0.9397} = 10.642$ inches

3) $O = \dfrac{2}{P_n} = 25.541 + \dfrac{2}{2} = 26.541$ inches

4) $o = d + \dfrac{2}{P_n} = 10.642 + \dfrac{2}{2} = 11.642$ inches

5) $T = \dfrac{N}{\cos^3\alpha} = \dfrac{48}{(0.9397)^3} = 57.8$, say 58 teeth

6) $t = \dfrac{n}{\cos^3\alpha} = \dfrac{20}{(0.9397)^3} = 24.1$, say 24 teeth

7) $L = \pi D \cot\alpha = 3.1416 \times 25.541 \times 2.747 = 220.42$ inches
8) $l = \pi d \cot\alpha = 3.1416 \times 10.642 \times 2.747 = 91.84$ inches
9) $C = \frac{1}{2}(D + d) = \frac{1}{2}(25.541 + 10.642) = 18.091$ inches

Copyright 2004, Industrial Press, Inc., New York, NY

2. Shafts Parallel, Center Distance Exact.— Given or assumed:



1) Position of gear having right- or left-hand helix, depending upon rotation and direction in which thrust is to be received
2) C = exact center distance
3) P_n = normal diametral pitch (pitch of cutter)
4) N = number of teeth in large gear
5) n = number of teeth in small gear

To find:

1) $\cos \alpha = \dfrac{N + n}{2P_n C}$

2) D = pitch diameter of large gear = $\dfrac{N}{P_n \cos \alpha}$

3) d = pitch diameter of small gear = $\dfrac{n}{P_n \cos \alpha}$

4) O = outside diameter of large gear = $D + \dfrac{2}{P_n}$

5) o = outside diameter of small gear = $d + \dfrac{2}{P_n}$

6) T = number of teeth marked on formed milling cutter (large gear) = $\dfrac{N}{\cos^3 \alpha}$

7) t = number of teeth marked on formed milling cutter (small gear) = $\dfrac{n}{\cos^3 \alpha}$

8) L = lead of helix (large gear) = $\pi D \cot \alpha$
9) l = lead of helix (small gear) = $\pi d \cot \alpha$

Example: Given or assumed: 1) See illustration; 2) $C = 18.75$ inches; 3) $P_n = 4$; 4) $N = 96$; and 5) $n = 48$.

1) $\cos \alpha = \dfrac{N + n}{2P_n C} = \dfrac{96 + 48}{2 \times 4 \times 18.75} = 0.96$, or $\alpha = 16°16'$

2) $D = \dfrac{N}{P_n \cos \alpha} = \dfrac{96}{4 \times 0.96} = 25$ inches

3) $d = \dfrac{n}{P_n \cos \alpha} = \dfrac{48}{4 \times 0.96} = 12.5$ inches

4) $O = D + \dfrac{2}{P_n} = 25 + \dfrac{2}{4} = 25.5$ inches

5) $o = d + \dfrac{2}{P_n} = 12.5 + \dfrac{2}{4} = 13$ inches

6) $T = \dfrac{N}{\cos^3 \alpha} = \dfrac{96}{(0.96)^3} = 108$ teeth

7) $t = \dfrac{n}{\cos^3 \alpha} = \dfrac{48}{(0.96)^3} = 54$ teeth

8) $L = \pi D \cot \alpha = 3.1416 \times 25 \times 3.427 = 269.15$ inches
9) $l = \pi d \cot \alpha = 3.1416 \times 12.5 \times 3.427 = 134.57$ inches

Copyright 2004, Industrial Press, Inc., New York, NY

3. Shafts at Right Angles, Center Distance Approx.— Sum of helix angles of gear and pinion must equal 90 degrees.



Given or assumed:
1) Position of gear having right- or left-hand helix, depending on rotation and direction in which thrust is to be received
2) C_a = approximate center distance
3) P_n = normal diametral pitch (pitch of cutter)
4) R = ratio of gear to pinion size
5) n = number of teeth in pinion = $\dfrac{1.41\,C_a P_n}{R+1}$ for 45 degrees; and $\dfrac{2C_a P_n \cos\alpha \cos\beta}{R\cos\beta + \cos\alpha}$ for any angle
6) N = number of teeth in gear = nR
7) α = angle of helix of gear
8) β = angle of helix of pinion

To find:

a) When helix angles are 45 degrees,

1) D = pitch diameter of gear = $\dfrac{N}{0.70711\,P_n}$

2) d = pitch diameter of pinion = $\dfrac{n}{0.70711\,P_n}$

3) O = outside diameter of gear = $D + \dfrac{2}{P_n}$

4) o = outside diameter of pinion = $d + \dfrac{2}{P_n}$

5) T = number of formed cutter (gear) = $\dfrac{N}{0.353}$

6) t = number of formed cutter (pinion) = $\dfrac{n}{0.353}$

7) L = lead of helix of gear = πD
8) l = lead of helix of pinion = πd

9) C = center distance (exact) = $\dfrac{D+d}{2}$

b) When helix angles are other than 45 degrees

1) $D = \dfrac{N}{P_n \cos\alpha}$ 2) $d = \dfrac{n}{P_n \cos\beta}$ 3) $T = \dfrac{N}{\cos^3\alpha}$

4) $t = \dfrac{n}{\cos^3\beta}$ 5) $L = \pi D \cot\alpha$ 6) $l = \pi d \cot\beta$

Example: Given or assumed: 1) See illustration; 2) $C_a = 3.2$ inches; 3) $P_n = 10$; and 4) $R = 1.5$.

5) $n = \dfrac{1.41\,C_a P_n}{R+1} = \dfrac{1.41 \times 3.2 \times 10}{1.5+1} =$ say 18 teeth.

6) $N = nR = 18 \times 1.5 = 27$ teeth; 7) $\alpha = 45$ degrees; and 8) $\beta = 45$ degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

To find:

1) $D = \dfrac{N}{0.70711 P_n} = \dfrac{27}{0.70711 \times 10} = 3.818$ inches

2) $d = \dfrac{n}{0.70711 P_n} = \dfrac{18}{0.70711 \times 10} = 2.545$ inches

3) $O = D + \dfrac{2}{P_n} = 3.818 + \dfrac{2}{10} = 4.018$ inches

4) $o = d + \dfrac{2}{P_n} = 2.545 + \dfrac{2}{10} = 2.745$ inches

5) $T = \dfrac{N}{0.353} = \dfrac{27}{0.353} = 76.5$, say 76 teeth

6) $t = \dfrac{n}{0.353} = \dfrac{18}{0.353} = 51$ teeth

7) $L = \pi D = 3.1416 \times 3.818 = 12$ inches

8) $l = \pi d = 3.1416 \times 2.545 = 8$ inches

9) $C = \dfrac{D + d}{2} = \dfrac{3.818 + 2.545}{2} = 3.182$ inches

4A. Shafts at Right Angles, Center Distance Exact.— Gears have same direction of helix. Sum of the helix angles will equal 90 degrees.



Given or assumed:
1) Position of gear having right- or left-hand helix depending on rotation and direction in which thrust is to be received
2) P_n = normal diametral pitch (pitch of cutter)
3) R = ratio of number of teeth in large gear to number of teeth in small gear
4) α_a = approximate helix angle of large gear
5) C = exact center distance

To find:
1) n = number of teeth in small gear nearest = $2\,CP_n \sin \alpha_a \div 1 + R \tan \alpha_a$
2) N = number of teeth in large gear = Rn
3) α = exact helix angle of large gear, found by trial from $R \sec \alpha + \operatorname{cosec} \alpha = 2\,CP_n \div n$
4) β = exact helix angle of small gear = $90° - \alpha$

5) D = pitch diameter of large gear = $\dfrac{N}{P_n \cos \alpha}$

6) d = pitch diameter of small gear = $\dfrac{n}{P_n \cos \beta}$

7) O = outside diameter of large gear = $D + \dfrac{2}{P_n}$

Copyright 2004, Industrial Press, Inc., New York, NY

8) o = outside diameter of small gear = $d + \frac{2}{P_n}$

9) N' and n' = numbers of teeth marked on cuttters for large and small gears (see page 2108)

10) L = lead of helix on large gear = $\pi D \cot \alpha$

11) l = lead of helix on small gear = $\pi d \cot \beta$

Example: Given or assumed: 1) See illustration; 2) $P_n = 8$; 3) $R = 3$; 4) $\alpha_a = 45$ degrees; and 5) $C = 10$ in.

To find:

1) $n = \frac{2CP_n \sin \alpha_a}{1 + R \tan \alpha_a} = \frac{2 \times 10 \times 8 \times 0.70711}{1 + 3} = 28.25$, say 28 teeth

2) $N = Rn = 3 \times 28 = 84$ teeth

3) $R \sec \alpha + \text{cosec}\, \alpha = \frac{2CP_n}{n} = \frac{2 \times 10 \times 8}{28} = 5.714$, or $\alpha = 46°6'$

4) $\beta = 90° - \alpha = 90° - 46°6' = 43°54'$

5) $D = \frac{N}{P_n \cos \alpha} = \frac{84}{8 \times 0.6934} = 15.143$ inches

6) $d = \frac{n}{P_n \cos \beta} = \frac{28}{8 \times 0.72055} = 4.857$ inches

7) $O = D + \frac{2}{P_n} = 15.143 + 0.25 = 15.393$ inches

8) $o = d + \frac{2}{P_n} = 4.857 + 0.25 = 5.107$ inches

9) $N' = 275$; $n' = 94$ (see page 2108)

10) $L = \pi D \cot \alpha = 3.1416 \times 15.143 \times 0.96232 = 45.78$ inches

11) $l = \pi d \cot \beta = 3.1416 \times 4.857 \times 1.0392 = 15.857$ inches

4B. Shafts at Right Angles, Any Ratio, Helix Angle for Minimum Center Distance.—

Diagram similar to 4A. Gears have same direction of helix. The sum of the helix angles will equal 90 degrees.

For any given ratio of gearing R there is a helix angle α for the larger gear and a helix angle $\beta = 90° - \alpha$ for the smaller gear that will make the center distance C a minimum. Helix angle α is found from the formula $\cot \alpha = R^{1/3}$. As an example, using the data found in Case 4A, helix angles α and β for minimum center distance would be: $\cot \alpha = R^{1/3} = 1.4422$; $\alpha = 34°44'$ and $\beta = 90° - 34°44' = 55°16'$. Using these helix angles, $D = 12.777$; $d = 6.143$; and $C = 9.460$ from the formulas for D and d given under Case 4A.

Copyright 2004, Industrial Press, Inc., New York, NY



5. Shafts at Any Angle, Center Distance Approx.— The sum of the helix angles of the two gears equals the shaft angle, and the gears are of the same hand, if each angle is less than the shaft angle. The difference between the helix angles equals the shaft angle, and the gears are of opposite hand, if either angle is greater than the shaft angle.

Given or assumed:

1) Hand of helix, depending on rotation and direction in which thrust is to be received

2) C_a = center distance

3) P_n = normal diametral pitch (pitch of cutter)

4) R = ratio of gear to pinion = $\dfrac{N}{n}$

5) α = angle of helix, gear

6) β = angle of helix, pinion

7) n = number of teeth in pinion nearest $\dfrac{2C_aP_n\cos\alpha\cos\beta}{R\cos\beta + \cos\alpha}$ for any angle

and $\dfrac{2C_aP_n\cos\alpha}{R+1}$ when both angles are equal

8) N = number of teeth in gear = Rn

To find:

1) D = pitch diameter of gear = $\dfrac{N}{P_n\cos\alpha}$

2) d = pitch diameter of pinion = $\dfrac{n}{P_n\cos\beta}$

3) O = outside diameter of gear = $D + \dfrac{2}{P_n}$

4) o = outside diameter of pinion = $d + \dfrac{2}{P_n}$

5) T = number of teeth marked on cutter for gear = $\dfrac{N}{\cos^3\alpha}$

6) t = number of teeth marked on cutter for pinion = $\dfrac{n}{\cos^3\beta}$

7) L = lead of helix on gear = $\pi D\cot\alpha$

8) l = lead of helix on pinion = $\pi d\cot\beta$

9) C = actual center distance = $\dfrac{D+d}{2}$

Example: Given or assumed (angle of shafts, 60 degrees):

1) See illustration 2) $C_a = 12$ inches 3) $P_n = 8$

4) $R = 4$ 5) $\alpha = 30$ degrees 6) $\beta = 30$ degrees

7) $n = \dfrac{2C_aP_n\cos\alpha}{R+1} = \dfrac{2\times 12\times 8\times 0.86603}{4+1} = 33$ teeth

8) $N = 4\times 33 = 132$ teeth

Copyright 2004, Industrial Press, Inc., New York, NY

To find:

1) $D = \dfrac{N}{P_n \cos\alpha} = \dfrac{132}{8 \times 0.86603} = 19.052$ inches

2) $d = \dfrac{n}{P_n \cos\beta} = \dfrac{33}{8 \times 0.86603} = 4.763$ inches

3) $O = D + \dfrac{2}{P_n} = 19.052 + \dfrac{2}{8} = 19.302$ inches

4) $o = d + \dfrac{2}{P_n} = 4.763 + \dfrac{2}{8} = 5.013$ inches

5) $T = \dfrac{N}{\cos^3\alpha} = \dfrac{132}{0.65} = 203$ teeth

6) $t = \dfrac{n}{\cos^3\beta} = \dfrac{33}{0.65} = 51$ teeth

7) $L = \pi D \cot\alpha = \pi \times 19.052 \times 1.732 = 103.66$ inches

8) $l = \pi d \cot\beta = \pi \times 4.763 \times 1.732 = 25.92$ inches

9) $C = \dfrac{D + d}{2} = \dfrac{19.052 + 4.763}{2} = 11.9075$ inches

6. Shafts at Any Angle, Center Distance Exact.— The sum of the helix angles of the two gears equals the shaft angle, and the gears are of the same hand, if each angle is less than the shaft angle. The difference between the helix angles equals the shaft angle, and the gears are of opposite hand, if either angle is greater than the shaft angle.



Given or assumed:

1) Hand of helix, depending on rotation and direction in which thrust is to be received

2) C = center distance

3) P_n = normal diametral pitch (pitch of cutter)

4) α_a = approximate helix angle of gear

5) β_a = approximate helix angle of pinion

6) R = ratio of gear to pinion size = $\dfrac{N}{n}$

7) n = number of pinion teeth nearest $\dfrac{2CP_n \cos\alpha_a \cos\beta_a}{R\cos\beta_a + \cos\alpha_a}$

8) N = number of gear teeth = Rn

To find:

1) α and β, exact helix angles, found by trial from $R \sec\alpha + \sec\beta = \dfrac{2CP_n}{n}$

Copyright 2004, Industrial Press, Inc., New York, NY

2) D = pitch diameter of gear = $\dfrac{N}{P_n \cos\alpha}$

3) d = pitch diameter of pinion = $\dfrac{n}{P_n \cos\beta}$

4) O = outside diameter of gear = $D + \dfrac{2}{P_n}$

5) o = outside diameter of pinion = $d + \dfrac{2}{P_n}$

6) N' = number of teeth marked on formed cutter for gear (see below)

7) n' = number of teeth marked on formed cutter for pinion (see below)

8) L = lead of helix on gear = $\pi D \cot\alpha$

9) l = lead of helix on pinion = $\pi d \cot\beta$

Selecting Cutter for Milling Helical Gears.— The proper milling cutter to use for *spur* gears depends on the pitch of the teeth and also upon the number of teeth as explained on page 2052 but a cutter for milling helical gears is not selected with reference to the actual number of teeth in the gear, as in spur gearing, but rather with reference to a calculated number N' that takes into account the effect on the tooth profile of lead angle, normal diametral pitch, and cutter diameter.

In the helical gearing examples starting on page 2101 the number of teeth N' on which to base the selection of the cutter has been determined using the approximate formula $N' = N \div \cos^3\alpha$ or $N' = N \sec^3\alpha$, where N = the actual number of teeth in the helical gear and α = the helix angle. However, the use of this formula may, where a combination of high helix angle and low tooth number is involved, result in the selection of a higher number of cutter than should actually be used for greatest accuracy. This condition is most likely to occur when the aforementioned formula is used to calculate N' for gears of high helix angle and low number of teeth.

To avoid the possibility of error in choice of cutter number, the following formula, which gives theoretically correct results for all combinations of helix angle and tooth numbers, is to be preferred:

$$N' = N\sec^3\alpha + P_n D_c \tan^2\alpha \qquad (1)$$

where: N' = number of teeth on which to base selection of cutter number from table on page 2054; N = actual number of teeth in helical gear; α = helix angle; P_n = normal diametral pitch of gear and cutter; and D_c = pitch diameter of cutter.

To simplify calculations, Formula (1) may be written as follows:

$$N' = NK + QK' \qquad (2)$$

In this formula, K, K' and Q are constants obtained from the tables on page 2109.

Example: Helix angle = 30 degrees; number of teeth in helical gear = 15; and normal diametral pitch = 20. From the tables on page 2109 K, K', and Q are, respectively, 1.540, 0.333, and 37.80.

$$N' = (15 \times 1.540) + (37.80 \times 0.333) = 23.10 + 12.60$$
$$= 35.70, \text{ say, } 36$$

Hence, from page 2054 select a number 3 cutter. Had the approximate formula been used, then a number 5 cutter would have been selected on the basis of $N' = 23$.

Copyright 2004, Industrial Press, Inc., New York, NY

Factors for Selecting Cutters for Milling Helical Gears

Helix Angle, α	*K*	*K′*	Helix Angle, α	*K*	*K′*	Helix Angle, α	*K*	*K′*	Helix Angle, α	*K*	*K′*
0	1.000	0	16	1.127	0.082	32	1.640	0.390	48	3.336	1.233
1	1.001	0	17	1.145	0.093	33	1.695	0.422	49	3.540	1.323
2	1.002	0.001	18	1.163	0.106	34	1.755	0.455	50	3.767	1.420
3	1.004	0.003	19	1.182	0.119	35	1.819	0.490	51	4.012	1.525
4	1.007	0.005	20	1.204	0.132	36	1.889	0.528	52	4.284	1.638
5	1.011	0.008	21	1.228	0.147	37	1.963	0.568	53	4.586	1.761
6	1.016	0.011	22	1.254	0.163	38	2.044	0.610	54	4.925	1.894
7	1.022	0.015	23	1.282	0.180	39	2.130	0.656	55	5.295	2.039
8	1.030	0.020	24	1.312	0.198	40	2.225	0.704	56	5.710	2.198
9	1.038	0.025	25	1.344	0.217	41	2.326	0.756	57	6.190	2.371
10	1.047	0.031	26	1.377	0.238	42	2.436	0.811	58	6.720	2.561
11	1.057	0.038	27	1.414	0.260	43	2.557	0.870	59	7.321	2.770
12	1.068	0.045	28	1.454	0.283	44	2.687	0.933	60	8.000	3.000
13	1.080	0.053	29	1.495	0.307	45	2.828	1	61	8.780	3.254
14	1.094	0.062	30	1.540	0.333	46	2.983	1.072	62	9.658	3.537
15	1.110	0.072	31	1.588	0.361	47	3.152	1.150	63	10.687	3.852

$K = 1 \div \cos^3 \alpha = \sec^3 \alpha$; $K' = \tan^2 \alpha$

Outside and Pitch Diameters of Standard Involute-form Milling Cutters

Normal Diametral Pitch, P_n	Outside Dia., D_o	Pitch Dia., D_c	$Q = P_n D_c$	Normal Diametral Pitch, P_n	Outside Dia., D_o	Pitch Dia., D_c	$Q = P_n D_c$	Normal Diametral Pitch, P_n	Outside Dia., D_o	Pitch Dia., D_c	$Q = P_n D_c$
1	8.500	6.18	6.18	6	3.125	2.76	16.56	20	2.000	1.89	37.80
1¼	7.750	5.70	7.12	7	2.875	2.54	17.78	24	1.750	1.65	39.60
1½	7.000	5.46	8.19	8	2.875	2.61	20.88	28	1.750	1.67	46.76
1¾	6.500	5.04	8.82	9	2.750	2.50	22.50	32	1.750	1.68	53.76
2	5.750	4.60	9.20	10	2.375	2.14	21.40	36	1.750	1.69	60.84
2½	5.750	4.83	12.08	12	2.250	2.06	24.72	40	1.750	1.70	68.00
3	4.750	3.98	11.94	14	2.125	1.96	27.44	48	1.750	1.70	81.60
4	4.250	3.67	14.68	16	2.125	1.98	31.68	..	…	…	…
5	3.750	3.29	16.45	18	2.000	1.87	33.66	..	…	…	…

Pitch diameters shown in the table are computed from the formula: $D_c = D_o - 2(1.57 \div P_n)$. This same formula may be used to compute the pitch diameter of a non-standard outside diameter cutter when the normal diametral pitch P_n and the outside diameter D_o are known.

Milling the Helical Teeth.— The teeth of a helical gear are proportioned from the normal pitch and not the circular pitch. The whole depth of the tooth can be found by dividing 2.157 by the normal diametral pitch of the gear, which corresponds to the pitch of the cut-

Copyright 2004, Industrial Press, Inc., New York, NY

ter. The thickness of the tooth at the pitch line equals 1.571 divided by the normal diametral pitch. After a tooth space has been milled, the cutter should be prevented from dragging through it when being returned for another cut. This can be done by lowering the blank slightly, or by stopping the machine and turning the cutter to such a position that the teeth will not touch the work. If the gear has teeth coarser than 10 or 12 diametral pitch, it is well to take a roughing and a finishing cut. When pressing a helical gear blank on the arbor, it should be remembered that it is more likely to slip when being milled than a spur gear, because the pressure of the cut, being at an angle, tends to rotate the blank on the arbor.

Angular Position of Table: When cutting a helical gear on a milling machine, the table is set to the helix angle of the gear. If the lead of the helical gear is known, but not the helix angle, the helix angle is determined by multiplying the pitch diameter of the gear by 3.1416 and dividing this product by the lead; the result is the tangent of the lead angle which may be obtained from trigonometric tables or a calculator.

American National Standard Fine-Pitch Teeth For Helical Gears.— This Standard, ANSI B6.7-1977, provides a 20-degree tooth form for both spur and helical gears of 20 diametral pitch and finer. Formulas for tooth parts are given on page 2039.

Enlargement of Helical Pinions, 20-Degree Normal Pressure Angle: Formula (4) and the accompanying graph are based on the use of hobs having sharp corners at their top lands. Pinions cut by shaper cutters may not require as much modification as indicated by (4) or the graph. The number 2.1 appearing in (4) results from the use of a standard tooth thickness rack having an addendum of $1.05/P_n$ which will start contact at a roll angle 5 degrees above the base radius. The roll angle of 5 degrees is also reflected in Formula (4).

To avoid undercutting of the teeth and to provide more favorable contact conditions near the base of the tooth, it is recommended that helical pinions with less than 24 teeth be enlarged in accordance with the following graph and formulas. As with enlarged spur pinions, when an enlarged helical pinion is used it is necessary either to reduce the diameter of the mating gear or to increase the center distance. In the formulas that follow, ϕ_n = normal pressure angle; ϕ_t = transverse pressure angle; ψ = helix angle of pinion; P_n = normal diametral pitch; P_t = transverse diametral pitch; d = pitch diameter of pinion; d_o = outside diameter of enlarged pinion, K_h = enlargement for full depth pinions of 1 normal diametral pitch; and n = number of teeth in pinion.



Copyright 2004, Industrial Press, Inc., New York, NY

To eliminate the need for making the calculations indicated in Formulas (3) and (4), the accompanying graph may be used to obtain the value of K_h directly for full-depth pinions of 20-degree normal pressure angle.

$$P_t = P_n \cos \psi \quad (1)$$

$$d = n \div P_t \quad (2)$$

$$tan\psi_t = \tan \phi_n \div \cos \psi \quad (3)$$

$$K_h = 2.1 - \frac{n}{\cos \psi} (\sin \phi_t - \cos \phi_t \tan 5°) \sin \phi_t \quad (4)$$

$$d_o = d + \frac{2 + K_h}{P_n} \quad (5)$$

Example: Find the outside diameter of a helical pinion having 12 teeth, 32 normal diametral pitch, 20-degree pressure angle, and 18-degree helix angle.

$$P_t = P_n \cos \psi = 32 \cos 18° = 32 \times 0.95106 = 30.4339$$

$$d = n \div P_t = 12 \div 30.4339 = 0.3943 \text{ inch}$$

$$K_h = 0.851 \text{ (from graph)}$$

$$d_o = 0.3943 + \frac{2 + 0.851}{32} = 0.4834$$

Center Distance at Which Modified Mating Helical Gears Will Mesh with no Backlash.— If the helical pinion in the previous example on page 2111 had been made to standard dimensions, that is, not enlarged, and was in tight mesh with a standard 24-tooth mating gear, the center distance for tight mesh could be calculated from the formula on page 2039:

$$C = \frac{n + N}{2P_n \cos \psi} = \frac{12 + 24}{2 \times 32 \times \cos 18°} = 0.5914 \text{ inch} \quad (1)$$

However, if the pinion is enlarged as in the example and meshed with the same standard 24-tooth gear, then the center distance for tight mesh will be increased. To calculate the new center distance, the following formulas and calculations are required:

First, calculate the transverse pressure angle ϕ_t using Formula (2):

$$\tan \phi_t = \tan \phi_n \div \cos \psi = \tan 20° \div \cos 18° = 0.38270 \quad (2)$$

and from a calculator the angle ϕ_t is found to be 20° 56′ 30″. In the table on page 104, inv ϕ_t is found to be 0.017196, and the cosine from a calculator as 0.93394.

Using Formula (3), calculate the pressure angle ϕ at which the gears are in tight mesh:

$$\text{inv}\, \phi = \text{inv}\, \phi_t + \frac{(t_{nP} + t_{nG}) - \pi}{n + N} \quad (3)$$

In this formula, the value for t_{nP} for 1 diametral pitch is that found in Table 9c on page 2056, for a 12-tooth pinion, in the fourth column: 1.94703. The value of t_{nG} for 1 diametral pitch for a standard gear is always 1.5708.

$$\text{inv}\, \phi = 0.017196 + \frac{(1.94703 + 1.5708) - \pi}{12 + 24} = 0.027647$$

From the table on page 105, or a calculator, 0.027647 is the involute of 24° 22′ 7″ and the cosine corresponding to this angle is 0.91091.

Finally, using Formula (4), the center distance for tight mesh, C' is found:

$$C' = \frac{C \cos \phi_t}{\cos \phi} = \frac{0.5914 \times 0.93394}{0.91091} = 0.606 \text{ inch} \quad (4)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Change-gears for Helical Gear Hobbing.— If a gear-hobbing machine is not equipped with a differential, there is a fixed relation between the index and feed gears and it is necessary to compensate for even slight errors in the index gear ratio, to avoid excessive lead errors. This may be done readily (as shown by the example to follow) by modifying the ratio of the feed gears slightly, thus offsetting the index gear error and making very accurate leads possible.

Machine Without Differential: The formulas which follow may be applied in computing the index gear ratio.

R = index-gear ratio
L = lead of gear, inches
F = feed per gear revolution, inch
K = machine constant
T = number of threads on hob
N = number of teeth on gear
P_n = normal diametral pitch
P_{nc} = normal circular pitch
A = helix angle, relative to axis
M = feed gear constant

$$R = \frac{L \div F}{(L \div F) \pm 1} \times \frac{KT}{N} = \frac{L}{L \pm F} \times \frac{KT}{N} = \frac{\text{Driving gear sizes}}{\text{Driven gear sizes}} \quad (1)$$

Use minus (−) sign in Formulas (1) and (2) when gear and hob are the same "hand" and plus (+) sign when they are of opposite hand; when *climb* hobbing is to be used, reverse this rule.

$$R = \frac{KT}{N \pm \dfrac{P_n \times \sin A \times F}{\pi}} = \frac{KT}{N \pm \dfrac{\sin A \times F}{P_{nc}}} \quad (2)$$

$$\text{Ratio of feed gears} = \frac{F}{M} \qquad F = \frac{L(NR - KT)}{NR} \quad (3)$$

$$L = \frac{FNR}{(NR - KT)} = \text{lead obtained with available index and feed gears} \quad (4)$$

Note: If gear and hob are of opposite hand, then in Formulas (3) and (4) change $(NR - KT)$ to $(KT - NR)$. This change is also made if gear and hob are of same hand but *climb* hobbing is used.

Example: A right-hand helical gear with 48 teeth of 10 normal diametral pitch, has a lead of 44.0894 inches. The feed is to be 0.035 inch, with whatever slight adjustment may be necessary to compensate for the error in available index gears. $K = 30$ and $M = 0.075$. A single-thread right-hand hob is to be used.

$$R = \frac{44.0894}{44.0894 - 0.035} \times \frac{30 \times 1}{48} = 0.62549654$$

Using the method of *Conjugate Fractions* beginning on page 12, several suitable ratios close to 0.62549654 were found. One of these, $(34 \times 53)/(43 \times 67) = 0.625477264839$ will be used as the index ratio. Other usable ratios and their decimal values were found to be as follows:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{32 \times 38}{27 \times 72} = 0.6255144 \qquad \frac{27 \times 42}{42 \times 37} = 0.62548263$$

$$\frac{44 \times 29}{34 \times 60} = 0.6254902 \qquad \frac{26 \times 97}{96 \times 42} = 0.62549603$$

$$\frac{20 \times 41}{23 \times 57} = 0.62547674$$

Index ratio error = 0.62549654 – 0.62547726 = 0.00001928.

Now use Formula (3) to find slight change required in rate of feed. This change compensates sufficiently for the error in available index gears.

Change in Feed Rate: Insert in Formula (3) obtainable index ratio.

$$F = \frac{44.0894 \times (48 \times 0.62547726 - 30)}{48 \times 0.62547726} = 0.0336417$$

$$\text{Modified feed gear ratio} = \frac{F}{M} = \frac{0.0336417}{0.075} = 0.448556$$

$$\text{Log } 0.448556 = \bar{1}.651817 \qquad \text{log of reciprocal} = 0.348183$$

To find close approximation to modified feed gear ratio, proceed as in finding suitable gears for index ratio, thus obtaining $\frac{106}{71} \times \frac{112}{75}$. Inverting, modified feed gear ratio = $\frac{71}{106} \times \frac{75}{112} = 0.448534$.

Modified feed F = obtainable modified feed ratio × M = 0.448534 × 0.075 = 0.03364 inch. If the feed rate is not modified, even a small error in the index gear ratio may result in an excessive lead error.

Checking Accuracy of Lead: The modified feed and obtainable index ratio are inserted in Formula (4). Desired lead = 44.0894 inches. Lead obtained = 44.087196 inches; hence the computed error = 44.0894 – 44.087196 = 0.002204 inch or about 0.00005 inch per inch of lead.

Machine with Differential: If a machine is equipped with a differential, the *lead gears* are computed in order to obtain the required helix angle and lead. The instructions of the hobbing machine manufacturer should be followed in computing the lead gears, because the ratio formula is affected by the location of the differential gears. If these gears are *ahead* of the index gears, the lead gear ratio is not affected by a change in the number of teeth to be cut (see Formula (5)); hence, the same lead gears are used when, for example, a gear and pinion are cut on the same machine. In the formulas which follow, the notation is the same as previously given, with these exceptions: R_d = lead gear ratio for machine with differential; P_a = axial or linear pitch of helical gear = distance from center of one tooth to center of next tooth measured parallel to gear axis = total lead $L \div$ number of teeth N.

$$R_d = \frac{P_a \times T}{K} = \frac{L \times T}{N \times K} = \frac{\pi \times \text{cosec} A \times T}{P_n \times K} = \frac{\text{Driven gear sizes}}{\text{Driving gear sizes}} \qquad (5)$$

The number of hob threads T is included in the formula because double-thread hobs are used sometimes, especially for roughing in order to reduce the hobbing time. Lead gears having a ratio sufficiently close to the required ratio may be determined by using the table of gear ratio logarithms as previously described in connection with the non-differential type of machine. When using a machine equipped with a differential, the effect of a lead-gear ratio error upon the lead of the gear is small in comparison with the effect of an index gear error when using a non-differential type of machine. The lead obtained with a given or

Copyright 2004, Industrial Press, Inc., New York, NY

obtainable lead gear ratio may be determined by the following formula: $L = (R_d NK) \div T$. In this formula, R_d represents the ratio obtained with available gears. If the given lead is 44.0894 inches, as in the preceding example, then the desired ratio as obtained with Formula (5) would be 0.9185292 if $K = 1$. Assume that the lead gears selected by using logs of ratios have a ratio of 0.9184704; then this ratio error of 0.0000588 would result in a computed lead error of only 0.000065 inch per inch.

Formula (5), as mentioned, applies to machines having the differential located *ahead* of the index gears. If the differential is located after the index gears, it is necessary to change lead gears whenever the index gears are changed for hobbing a different number of teeth, as indicated by the following formula which gives the lead gear ratio. In this formula, D = pitch diameter.

$$R_d = \frac{L \times T}{K} = \frac{D \times \pi \times T}{K \times \tan A} = \frac{\text{Driven gear sizes}}{\text{Driving gear sizes}} \quad (6)$$

General Remarks on Helical Gear Hobbing.— In cutting teeth having large angles, it is desirable to have the direction of helix of the hob the same as the direction of helix of the gear, or in other words, the gear and the hob of the same "hand." Then the direction of the cut will come against the movement of the blank. At ordinary angles, however, one hob will cut both right- and left-hand gears. In setting up the hobbing machine for helical gears, care should be taken to see that the vertical feed does not trip until the machine has been stopped or the hob has fed down past the finished gear.

Herringbone Gears

Double helical or herringbone gears are commonly used in parallel-shaft transmissions, especially when a smooth, continuous action (due to the gradual overlapping engagement of the teeth) is essential, as in high-speed drives where the pitch-line velocity may range from about 1000 to 3000 feet per minute in commercial gearing and up to 12,000 feet per minute or higher in more specialized installations. These relatively high speeds are encountered in marine reduction gears, in certain speed-reducing and speed-increasing units, and in various other transmissions, particularly in connection with steam turbine and electric motor drives.

General Classes of Helical Gear Problems.— There are two general classes of problems. In one, the problem is to design gears capable of transmitting a given amount of power at a given speed, safely and without excessive wear; hence, the required proportions must be determined. In the second, the proportions and speed are known and the power-transmitting capacity is required. The first is the more difficult and common problem.

Causes of Herringbone Gear Failures.— Where failure occurs in a herringbone gear transmission, it is rarely due to tooth breakage but usually to excessive wear or sub-surface failures, such as pitting and spalling; hence, it is common practice to base the design of such gears upon durability, or upon tooth pressures which are within the allowable limits for wear. In this connection, it seems to have been well established by tests of both spur gears and herringbone gears, that there is a critical surface pressure value for teeth having given physical properties and coefficient of friction. According to these tests, pressures above the critical value result in rapid wear and a short gear life, whereas when pressures are below the critical, wear is negligible. The yield point or endurance limit of the material marks the critical loading point, and in practical designing a reasonable factor of safety would, of course, be employed.

Elliptic Gears

Gears of this type provide simple means of obtaining a quick-return motion but they present a rather cumbersome manufacturing problem and, as a general rule, it is preferable

Copyright 2004, Industrial Press, Inc., New York, NY

to obtain quick-return motions by some other type of mechanism. When elliptic gears are used, the two gears that mesh with each other must be equal in size, and each gear must revolve about one of the foci of the ellipse forming the pitch line, as indicated by the diagram, in Fig. 1a. By the use of elliptic gears so mounted, it is possible to obtain a variable motion of the driven shaft, because the gear on the driving shaft, while revolving one half of a revolution, will engage with only a small portion of the circumference of the driven gear, while during the other half of its revolution, the driving gear will engage with a great deal more than one-half of the total number of teeth in the driven gear; hence, the cutting stroke of a machine tool, for example, may be made to have a slow motion, while the return stroke is at a rapid rate. The ellipse has two points, each of which is called a *focus,* located as indicated at *A* and *B*. The sum of the distance between the foci and the elliptic curve is constant at all points and is equal to the longer or major axis of the ellipse. On account of this peculiarity of the ellipse, two equal ellipses can be made to mesh with each other during a complete revolution about their axes, if one is mounted on a shaft at its focus *A* and the other at its focus *B*.



Fig. 1a. General Arrangement of Elliptic Gears.

Planetary Gearing

Planetary or epicyclic gearing provides means of obtaining a compact design of transmission, with driving and driven shafts in line, and a large speed reduction when required. Typical arrangements of planetary gearing are shown by the following diagrams which are accompanied by speed ratio formulas. When planetary gears are arranged as shown by Figs. 5, 6, 9 and 12, the speed of the follower relative to the driver is increased, whereas Figs. 7, 8, 10, and 11 illustrate speed-reducing mechanisms.

Direction of Rotation.— In using the following formulas, if the final result is preceded by a minus sign (negative), this indicates that the driver and follower will rotate in opposite directions; otherwise, both will rotate in the same direction.

Compound Drive.— The formulas accompanying Figs. 19 through 22 are for obtaining the speed ratios when there are *two* driving members rotating at different speeds. For example, in Fig. 19, the central shaft with its attached link is one driver. The internal gear z, instead of being fixed, is also rotated. In Fig. 22, if $z = 24$, $B = 60$ and $S = 3\frac{1}{2}$, with both drivers rotating in the same direction, then $F = 0$, thus indicating, in this case, the point where a larger value of S will reverse follower rotation.

Planetary Bevel Gears.— Two forms of planetary gears of the bevel type are shown in Figs. 23 and 24. The planet gear in Fig. 23 rotates about a fixed bevel gear at the center of which is the driven shaft. Fig. 24 illustrates the Humpage reduction gear. This is sometimes referred to as cone-pulley back-gearing because of its use within the cone pulleys of certain types of machine tools.

Copyright 2004, Industrial Press, Inc., New York, NY

Ratios of Planetary or Epicyclic Gearing

D = rotation of *driver* per revolution of follower or driven member

F = rotation of *follower* or driven member per revolution of driver. (In Figs. 1 through 4, F = rotation of planet type follower about its axis.)

A = size of driving gear (use either number of teeth or pitch diameter). Note: When follower derives its motion both from A and from a secondary driving member, A = size of *initial* driving gear, and formula gives speed relationship between A and follower.

B = size of *driven gear or follower* (use either pitch diameter or number of teeth)

C = size of *fixed gear* (use either pitch diameter or number of teeth)

x = size of *planet gear* as shown by diagram (use either pitch diameter or number of teeth)

y = size of *planet gear* as shown by diagram (use either pitch diameter or number of teeth)

z = size of secondary or *auxiliary driving gear*, when follower derives its motion from two driving members

S = rotation of *secondary driver*, per revolution of *initial driver*. S is negative when secondary and initial drivers rotate in opposite directions. (Formulas in which S is used, give speed relationship between follower and the initial driver.)

Note: In all cases, if D is known, $F = 1 \div D$, or, if F is known, $D = 1 \div F$.



Fig. 1.

$$F = 1 + \frac{C}{B}$$



Fig. 2.

$$F = 1 - \frac{C}{B}$$



Fig. 3.

$$F = \frac{C}{B}$$



Fig. 4.

$$F = \cos E + \frac{C}{B}$$



Fig. 5.

$$F = 1 + \frac{x \times C}{y \times B}$$



Fig. 6.

$$F = 1 + \frac{y \times C}{x \times B}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Ratios of Planetary or Epicyclic Gearing *(Continued)*



Fig. 7.

$$D = 1 + \frac{x \times C}{y \times A}$$



Fig. 8.

$$D = 1 + \frac{y \times C}{x \times A}$$



Fig. 9.

$$F = 1 + \frac{C}{B}$$



Fig. 10.

$$D = 1 + \frac{C}{A}$$



Fig. 11.

$$D = 1 + \frac{C}{A}$$



Fig. 12.

$$F = 1 + \frac{C}{B}$$



Fig. 13.

$$F = 1 - \left(\frac{C \times x}{y \times B}\right)$$



Fig. 14.

$$D = \frac{1 + \frac{C}{A}}{1 - \left(\frac{C \times x}{y \times B}\right)}$$



Fig. 15.

$$D = \frac{1 + \frac{C}{A}}{1 - \left(\frac{C \times y}{x \times B}\right)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Ratios of Planetary or Epicyclic Gearing *(Continued)*



Fig. 16.

$$D = 1 - \left(\frac{C \times x}{y \times A}\right)$$



Fig. 17.

$$F = 1 - \left(\frac{C \times x}{y \times B}\right)$$



Fig. 18.

$$D = 1 - \left(\frac{C \times x}{y \times A}\right)$$



Fig. 19.

$$F = 1 + \frac{z \times (1 - S)}{B}$$



Fig. 20.

$$D = \frac{A + z}{A + (S \times z)}$$



Fig. 21.

$$D = \frac{A + z}{A + (S \times z)}$$



Fig. 22.

$$F = 1 + \frac{z \times (1 - S)}{B}$$



Fig. 23.

$$D = 1 + \frac{C}{A}$$



Fig. 24.

$$D = \frac{1 + \frac{C}{A}}{1 - \left(\frac{C \times y}{x \times B}\right)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Ratchet Gearing

Ratchet gearing may be used to transmit intermittent motion, or its only function may be to prevent the ratchet wheel from rotating backward. Ratchet gearing of this latter form is commonly used in connection with hoisting mechanisms of various kinds, to prevent the hoisting drum or shaft from rotating in a reverse direction under the action of the load.

Types of Ratchet Gearing



Fig. a. Fig. b. Fig. c.

Fig. d. Fig. e. Fig. f.

Fig. g. Fig. h. Fig. i.

Ratchet gearing in its simplest form consists of a toothed ratchet wheel *a* (see Fig. a), and a pawl or detent *b*, and it may be used to transmit intermittent motion or to prevent relative motion between two parts except in one direction. The pawl *b* is pivoted to lever *c* which, when given an oscillating movement, imparts an intermittent rotary movement to ratchet wheel *a*. Fig. b illustrates another application of the ordinary ratchet and pawl mechanism. In this instance, the pawl is pivoted to a stationary member and its only function is to prevent the ratchet wheel from rotating backward. With the stationary design, illustrated at

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. c, the pawl prevents the ratchet wheel from rotating in either direction, so long as it is in engagement with the wheel.

The principle of *multiple-pawl ratchet gearing* is illustrated at Fig. d, which shows the use of two pawls. One of these pawls is longer than the other, by an amount equal to one-half the pitch of the ratchet-wheel teeth, so that the practical effect is that of reducing the pitch one-half. By placing a number of driving pawls side byside and proportioning their lengths according to the pitch of the teeth, a very fine feed can be obtained with a ratchet wheel of comparatively coarse pitch.

This method of obtaining a fine feed from relatively coarse-pitch ratchets may be preferable to the use of single ratchets of fine pitch which, although providing the feed required, may have considerably weaker teeth.

The type of ratchet gearing shown at Fig. e is sometimes employed to impart a rotary movement to the ratchet wheel for both the forward and backward motions of the lever to which the two pawls are attached.

A simple form of *reversing ratchet* is illustrated at Fig. f. The teeth of the wheel are so shaped that either side may be used for driving by simply changing the position of the double-ended pawl, as indicated by the full and dotted lines.

Another form of reversible ratchet gearing for shapers is illustrated at Fig. g. The pawl, in this case, instead of being a pivoted latch, is in the form of a plunger which is free to move in the direction of its axis, but is normally held into engagement with the ratchet wheel by a small spring. When the pawl is lifted and turned one-half revolution, the driving face then engages the opposite sides of the teeth and the ratchet wheel is given an intermittent rotary motion in the opposite direction.

The *frictional type* of ratchet gearing differs from the designs previously referred to, in that there is no positive engagement between the driving and driven members of the ratchet mechanism, the motion being transmitted by frictional resistance. One type of frictional ratchet gearing is illustrated at Fig. h. Rollers or balls are placed between the ratchet wheel and an outer ring which, when turned in one direction, causes the rollers or balls to wedge between the wheel and ring as they move up the inclined edges of the teeth.

Fig. i illustrates one method of utilizing ratchet gearing for moving the driven member in a straight line, as in the case of a lifting jack. The pawl *g* is pivoted to the operating lever of the jack and does the lifting, whereas the pawl *h* holds the load while the lifting pawl *g* is being returned preparatory to another lifting movement.

Shape of Ratchet Wheel Teeth.— When designing ratchet gearing, it is important to so shape the teeth that the pawl will remain in engagement when a load is applied. The faces of the teeth which engage the end of the pawl should be in such relation with the center of the pawl pivot that a line perpendicular to the face of the engaging tooth will pass somewhere between the center of the ratchet wheel and the center of the pivot about which the pawl swings. This is true if the pawl *pushes* the ratchet wheel, or if the ratchet wheel *pushes* the pawl. However, if the pawl *pulls* the ratchet wheel or if the ratchet wheel *pulls* the pawl, the perpendicular from the face of the ratchet teeth should fall outside the pawl pivot center. Ratchet teeth may be either cut by a milling cutter having the correct angle, or hobbed in a gear-hobbing machine by the use of a special hob.

Pitch of Ratchet Wheel Teeth.— The pitch of ratchet wheels used for holding suspended loads may be calculated by the following formula, in which P = circular pitch, in inches, measured at the outside circumference; M = turning moment acting upon the ratchet wheel shaft, in inch-pounds; L = length of tooth face, in inches (thickness of ratchet gear); S = safe stress (for steel, 2500 pounds per square inch when subjected to shock, and 4000 pounds per square inch when not subjected to shock); N = number of teeth in ratchet wheel; F = a factor the value of which is 50 for ratchet gears with 12 teeth or less, 35 for gears having from 12 to 20 teeth, and 20 for gears having over 20 teeth:

Copyright 2004, Industrial Press, Inc., New York, NY

$$P = \sqrt[\backslash]{\frac{FM}{LSN}}$$

This formula has been used in the calculation of ratchet gears for crane design.

Gear Design Based upon Module System.— The *module* of a gear is equal to the pitch diameter divided by the number of teeth, whereas *diametral pitch* is equal to the number of teeth divided by the pitch diameter. The module system (see accompanying table and diagram) is in general use in countries that have adopted the metric system; hence, the term module is usually understood to mean the pitch diameter *in millimeters* divided by the number of teeth. The module system, however, may also be based on inch measurements and then it is known as the English module to avoid confusion with the metric module. Module is an actual dimension, whereas diametral pitch is only a ratio. Thus, if the pitch diameter of a gear is 50 millimeters and the number of teeth 25, the module is 2, which means that there are 2 millimeters of pitch diameter for each tooth. The table *Tooth Dimensions Based Upon Module System* shows the relation among module, diametral pitch, and circular pitch.

German Standard Tooth Form for Spur and Bevel Gears *DIN 867*



The flanks or sides are straight (involute system) and the pressure angle is 20 degrees. The shape of the root clearance space and the amount of clearance depend upon the method of cutting and special requirements. The amount of clearance may vary from 0.1 × module to 0.3 × module.

To Find	Module Known	Circular Pitch Known
Addendum	Equals module	0.31823 × Circular pitch
Dedendum	1.157 × module* 1.167 × module**	0.3683 × Circular pitch* 0.3714 × Circular pitch**
Working Depth	2 × module	0.6366 × Circular pitch
Total Depth	2.157 × module* 2.167 × module**	0.6866 × Circular pitch* 0.6898 × Circulate pitch**
Tooth Thickness on Pitch Line	1.5708 × module	0.5 × Circular pitch

Formulas for dedendum and total depth, marked (*) are used when clearance equals 0.157 × module. Formulas marked (**) are used when clearance equals one-sixth module. It is common practice among American cutter manufacturers to make the clearance of metric or module cutters equal to 0.157 × module.

Copyright 2004, Industrial Press, Inc., New York, NY

Tooth Dimensions Based Upon Module System

Module, *DIN* Standard Series	Equivalent Diametral Pitch	Circular Pitch		Addendum, Millimeters	Dedendum, Millimeters[a]	Whole Depth,[a] Millimeters	Whole Depth,[b] Millimeters
		Millimeters	Inches				
0.3	84.667	0.943	0.0371	0.30	0.35	0.650	0.647
0.4	63.500	1.257	0.0495	0.40	0.467	0.867	0.863
0.5	50.800	1.571	0.0618	0.50	0.583	1.083	1.079
0.6	42.333	1.885	0.0742	0.60	0.700	1.300	1.294
0.7	36.286	2.199	0.0865	0.70	0.817	1.517	1.510
0.8	31.750	2.513	0.0989	0.80	0.933	1.733	1.726
0.9	28.222	2.827	0.1113	0.90	1.050	1.950	1.941
1	25.400	3.142	0.1237	1.00	1.167	2.167	2.157
1.25	20.320	3.927	0.1546	1.25	1.458	2.708	2.697
1.5	16.933	4.712	0.1855	1.50	1.750	3.250	3.236
1.75	14.514	5.498	0.2164	1.75	2.042	3.792	3.774
2	12.700	6.283	0.2474	2.00	2.333	4.333	4.314
2.25	11.289	7.069	0.2783	2.25	2.625	4.875	4.853
2.5	10.160	7.854	0.3092	2.50	2.917	5.417	5.392
2.75	9.236	8.639	0.3401	2.75	3.208	5.958	5.932
3	8.466	9.425	0.3711	3.00	3.500	6.500	6.471
3.25	7.815	10.210	0.4020	3.25	3.791	7.041	7.010
3.5	7.257	10.996	0.4329	3.50	4.083	7.583	7.550
3.75	6.773	11.781	0.4638	3.75	4.375	8.125	8.089
4	6.350	12.566	0.4947	4.00	4.666	8.666	8.628
4.5	5.644	14.137	0.5566	4.50	5.25	9.750	9.707
5	5.080	15.708	0.6184	5.00	5.833	10.833	10.785
5.5	4.618	17.279	0.6803	5.50	6.416	11.916	11.864
6	4.233	18.850	0.7421	6.00	7.000	13.000	12.942
6.5	3.908	20.420	0.8035	6.50	7.583	14.083	14.021
7	3.628	21.991	0.8658	7.	8.166	15.166	15.099
8	3.175	25.132	0.9895	8.	9.333	17.333	17.256
9	2.822	28.274	1.1132	9.	10.499	19.499	19.413
10	2.540	31.416	1.2368	10.	11.666	21.666	21.571
11	2.309	34.558	1.3606	11.	12.833	23.833	23.728
12	2.117	37.699	1.4843	12.	14.000	26.000	25.884
13	1.954	40.841	1.6079	13.	15.166	28.166	28.041
14	1.814	43.982	1.7317	14.	16.332	30.332	30.198
15	1.693	47.124	1.8541	15.	17.499	32.499	32.355
16	1.587	50.266	1.9790	16.	18.666	34.666	34.512
18	1.411	56.549	2.2263	18.	21.000	39.000	38.826
20	1.270	62.832	2.4737	20.	23.332	43.332	43.142
22	1.155	69.115	2.7210	22.	25.665	47.665	47.454
24	1.058	75.398	2.9685	24.	28.000	52.000	51.768
27	0.941	84.823	3.339	27.	31.498	58.498	58.239
30	0.847	94.248	3.711	30.	35.000	65.000	64.713
33	0.770	103.673	4.082	33.	38.498	71.498	71.181
36	0.706	113.097	4.453	36.	41.998	77.998	77.652
39	0.651	122.522	4.824	39.	45.497	84.497	84.123
42	0.605	131.947	5.195	42.	48.997	90.997	90.594
45	0.564	141.372	5.566	45.	52.497	97.497	97.065
50	0.508	157.080	6.184	50.	58.330	108.330	107.855
55	0.462	172.788	6.803	55.	64.163	119.163	118.635
60	0.423	188.496	7.421	60.	69.996	129.996	129.426
65	0.391	204.204	8.040	65.	75.829	140.829	140.205
70	0.363	219.911	8.658	70.	81.662	151.662	150.997
75	0.339	235.619	9.276	75.	87.495	162.495	161.775

[a] Dedendum and total depth when clearance = 0.1666 × module, or one-sixth module.
[b] Total depth equivalent to American standard full-depth teeth. (Clearance = 0.157 × module.)

Copyright 2004, Industrial Press, Inc., New York, NY

Rules for Module System of Gearing

To Find	Rule
Metric Module	*Rule 1:* To find the metric module, divide the pitch diameter in millimeters by the number of teeth. *Example 1:* The pitch diameter of a gear is 200 millimeters and the number of teeth, 40; then $\text{Module} = \frac{200}{40} = 5$ *Rule 2:* Multiply circular pitch in millimeters by 0.3183. *Example 2:* (Same as Example 1. Circular pitch of this gear equals 15.708 millimeters.) $\text{Module} = 15.708 \times 0.3183 = 5$ *Rule 3:* Divide outside diameter in millimeters by the number of teeth plus 2.
English Module	*Note:* The module system is usually applied when gear dimensions are expressed in millimeters, but module may also be based on inch measurements. *Rule:* To find the English module, divide pitch diameter in inches by the number of teeth. *Example:* A gear has 48 teeth and a pitch diameter of 12 inches. $\text{Module} = \frac{12}{48} = \frac{1}{4}$ module or 4 diametral pitch
Metric Module Equivalent to Diametral Pitch	*Rule:* To find the metric module equivalent to a given diametral pitch, divide 25.4 by the diametral pitch. *Example:* Determine metric module equivalent to 10 diameteral pitch. $\text{Equivalent module} = \frac{25.4}{10} = 2.54$ *Note:* The nearest standard module is 2.5.
Diametral Pitch Equivalent to Metric Module	*Rule:* To find the diametral pitch equivalent to a given module, divide 25.4 by the module. (25.4 = number of millimeters per inch.) *Example:* The module is 12; determine equivalent diametral pitch. $\text{Equivalent diametral pitch} = \frac{25.4}{12} = 2.117$ *Note:* A diametral pitch of 2 is the nearest *standard* equivalent.
Pitch Diameter	*Rule:* Multiply number of teeth by module. *Example:* The metric module is 8 and the gear has 40 teeth; then $D = 40 \times 8 = 320$ millimeters $= 12.598$ inches
OutsideDiameter	*Rule:* Add 2 to the number of teeth and multiply sum by the module. *Example:* A gear has 40 teeth and module is 6. Find outside or blank diameter. $\text{Outside diameter} = (40 + 2) \times 6 = 252$ millimeters

For tooth dimensions, see table *Tooth Dimensions Based Upon Module System*; also formulas in *German Standard Tooth Form for Spur and Bevel Gears DIN 867*.

Copyright 2004, Industrial Press, Inc., New York, NY

Equivalent Diametral Pitches, Circular Pitches, and Metric Modules
Commonly Used Pitches and Modules in Bold Type

Diametral Pitch	Circular Pitch, Inches	Module Millimeters	Diametral Pitch	Circular Pitch, Inches	Module Millimeters	Diametral Pitch	Circular Pitch, Inches	Module Millimeters
1/2	6.2832	50.8000	2.2848	**1 3/8**	11.1170	10.0531	5/16	2.5266
0.5080	6.1842	**50**	2.3091	1.3605	**11**	10.1600	0.3092	**2 1/2**
0.5236	**6**	48.5104	**2 1/2**	1.2566	10.1600	**11**	0.2856	2.3091
0.5644	5.5658	**45**	2.5133	**1 1/4**	10.1063	**12**	0.2618	2.1167
0.5712	**5 1/2**	44.4679	2.5400	1.2368	**10**	12.5664	1/4	2.0213
0.6283	**5**	40.4253	**2 3/4**	1.1424	9.2364	12.7000	0.2474	**2**
0.6350	4.9474	**40**	2.7925	**1 1/8**	9.0957	**13**	0.2417	1.9538
0.6981	**4 1/2**	36.3828	2.8222	1.1132	**9**	**14**	0.2244	1.8143
0.7257	4.3290	**35**	**3**	1.0472	8.4667	**15**	0.2094	1.6933
3/4	4.1888	33.8667	3.1416	**1**	8.0851	**16**	0.1963	1.5875
0.7854	**4**	32.3403	3.1750	0.9895	**8**	16.7552	3/16	1.5160
0.8378	**3 3/4**	30.3190	3.3510	15/16	7.5797	16.9333	0.1855	**1 1/2**
0.8467	3.7105	**30**	**3 1/2**	0.8976	7.2571	**17**	0.1848	1.4941
0.8976	**3 1/2**	28.2977	3.5904	7/8	7.0744	**18**	0.1745	1.4111
0.9666	**3 1/4**	26.2765	3.6286	0.8658	**7**	**19**	0.1653	1.3368
1	3.1416	25.4000	3.8666	13/16	6.5691	**20**	0.1571	1.2700
1.0160	3.0921	**25**	3.9078	0.8040	**6 1/2**	**22**	0.1428	1.1545
1.0472	**3**	24.2552	**4**	0.7854	6.3500	**24**	0.1309	1.0583
1.1424	**2 3/4**	22.2339	4.1888	3/4	6.0638	**25**	0.1257	1.0160
1 1/4	2.5133	20.3200	4.2333	0.7421	**6**	25.1328	1/8	1.0106
1.2566	**2 1/2**	20.2127	4.5696	11/16	5.5585	25.4000	0.1237	**1**
1.2700	2.4737	**20**	4.6182	0.6803	**5 1/2**	**26**	0.1208	0.9769
1.3963	**2 1/4**	18.1914	**5**	0.6283	5.0800	**28**	0.1122	0.9071
1.4111	2.2263	**18**	5.0265	5/8	5.0532	**30**	0.1047	0.8467
1 1/2	2.0944	16.9333	5.0800	0.6184	**5**	**32**	0.0982	0.7937
1.5708	**2**	16.1701	5.5851	9/16	4.5478	**34**	0.0924	0.7470
1.5875	1.9790	**16**	5.6443	0.5566	**4 1/2**	**36**	0.0873	0.7056
1.6755	**1 7/8**	15.1595	**6**	0.5236	4.2333	**38**	0.0827	0.6684
1.6933	1.8553	**15**	6.2832	1/2	4.0425	**40**	0.0785	0.6350
1 3/4	1.7952	14.5143	6.3500	0.4947	**4**	**42**	0.0748	0.6048
1.7952	**1 3/4**	14.1489	**7**	0.4488	3.6286	**44**	0.0714	0.5773
1.8143	1.7316	**14**	7.1808	7/16	3.5372	**46**	0.0683	0.5522
1.9333	**1 5/8**	13.1382	7.2571	0.4329	**3 1/2**	**48**	0.0654	0.5292
1.9538	1.6079	**13**	**8**	0.3927	3.1750	**50**	0.0628	0.5080
2	1.5708	12.7000	8.3776	3/8	3.0319	50.2656	1/16	0.5053
2.0944	**1 1/2**	12.1276	8.4667	0.3711	**3**	50.8000	0.0618	1/2
2.1167	1.4842	**12**	**9**	0.3491	2.8222	**56**	0.0561	0.4536
2 1/4	1.3963	11.2889	**10**	0.3142	2.5400	**60**	0.0524	0.4233

The module of a gear is the pitch diameter divided by the number of teeth. The module may be expressed in any units; but when no units are stated, it is understood to be in millimeters. The metric module, therefore, equals the pitch diameter in millimeters divided by the number of teeth. To find the metric module equivalent to a given diametral pitch, divide 25.4 by the diametral pitch. To find the diametral pitch equivalent to a given module, divide 25.4 by the module. (25.4 = number of millimeters per inch.)

Copyright 2004, Industrial Press, Inc., New York, NY

CHECKING GEAR SIZES

Checking Gear Size by Measurement Over Wires or Pins

The wire or pin method of checking gear sizes is accurate, easily applied, and especially useful in shops with limited inspection equipment. Two cylindrical wires or pins of predetermined diameter are placed in diametrically opposite tooth spaces (see diagram). If the gear has an odd number of teeth, the wires are located as nearly opposite as possible, as shown by the diagram at the right. The overall measurement *M* is checked by using any sufficiently accurate method of measurement. The value of measurement *M* when the pitch diameter is correct can be determined easily and quickly by means of the calculated values in the accompanying tables.

Measurements for Checking External Spur Gears when Wire Diameter Equals 1.728 Divided by Diametral Pitch.— Tables 1 and 2 give measurements *M*, in inches, for checking the pitch diameters of external spur gears of 1 diametral pitch. For any other diametral pitch, divide the measurement given in the table by whatever diametral pitch is required. The result shows what measurement *M* should be when the pitch diameter is correct *and there is no allowance for backlash*. The procedure for obtaining a given amount of backlash will be explained later. Tables 1 through 4 inclusive are based on wire sizes conforming to the Van Keuren standard. For external spur gears, the wire size equals 1.728 divided by the diametral pitch. The wire diameters for various diametral pitches will be found in the left-hand section of Table 5.



Even Number of Teeth: Table 1 is for even numbers of teeth. To illustrate the use of the table, assume that a spur gear has 32 teeth of 4 diametral pitch and a pressure angle of 20 degrees. Table 1 shows that the measurement for 1 diametral pitch is 34.4130; hence, for 4 diametral pitch, the measurement equals 34.4130 ÷ 4 = 8.6032 inches. This dimension is the measurement over the wires when the pitch diameter is correct, provided there is no allowance for backlash. The wire diameter here equals 1.728 ÷ 4 = 0.432 inch (Table 5).

Measurement for even numbers of teeth above 170 and not in Table 1 may be determined as shown by the following example: Assume that number of teeth = 240 and pressure angle = 14½ degrees; then, for 1 diametral pitch, figure at left of decimal point = given No. of teeth + 2 = 240 + 2 = 242. Figure at right of decimal point lies between decimal values given in table for 200 teeth and 300 teeth and is obtained by interpolation. Thus, 240 – 200 = 40 (change to 0.40); 0.5395 – 0.5321 = 0.0074 = difference between decimal values for 300 and 200 teeth; hence, decimal required = 0.5321 + (0.40 × 0.0074) = 0.53506. Total dimension = 242.53506 divided by the diametral pitch required.

Odd Number of Teeth: Table 2 is for odd numbers of teeth. Measurement for odd numbers above 171 and not in Table 2 may be determined as shown by the following example: Assume that number of teeth = 335 and pressure angle = 20 degrees; then, for 1 diametral

Copyright 2004, Industrial Press, Inc., New York, NY

pitch, figure at left of decimal point = given No. of teeth + 2 = 335 + 2 = 337. Figure at right of decimal point lies between decimal values given in table for 301 and 401 teeth. Thus, 335 − 301 = 34 (change to 0.34); 0.4565 − 0.4538 = 0.0027; hence, decimal required = 0.4538 + (0.34 × 0.0027) = 0.4547. Total dimension = 337.4547.

Table 1. Checking External Spur Gear Sizes by Measurement Over Wires

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.728}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
6	8.2846	8.2927	8.3032	8.3340	8.3759
8	10.3160	10.3196	10.3271	10.3533	10.3919
10	12.3399	12.3396	12.3445	12.3667	12.4028
12	14.3590	14.3552	14.3578	14.3768	14.4108
14	16.3746	16.3677	16.3683	16.3846	16.4169
16	18.3877	18.3780	18.3768	18.3908	18.4217
18	20.3989	20.3866	20.3840	20.3959	20.4256
20	22.4087	22.3940	22.3900	22.4002	22.4288
22	24.4172	24.4004	24.3952	24.4038	24.4315
24	26.4247	26.4060	26.3997	26.4069	26.4339
26	28.4314	28.4110	28.4036	28.4096	28.4358
28	30.4374	30.4154	30.4071	30.4120	30.4376
30	32.4429	32.4193	32.4102	32.4141	32.4391
32	34.4478	34.4228	34.4130	34.4159	34.4405
34	36.4523	36.4260	36.4155	36.4176	36.4417
36	38.4565	38.4290	38.4178	38.4191	38.4428
38	40.4603	40.4317	40.4198	40.4205	40.4438
40	42.4638	42.4341	42.4217	42.4217	42.4447
42	44.4671	44.4364	44.4234	44.4228	44.4455
44	46.4701	46.4385	46.4250	46.4239	46.4463
46	48.4729	48.4404	48.4265	48.4248	48.4470
48	50.4756	50.4422	50.4279	50.4257	50.4476
50	52.4781	52.4439	52.4292	52.4265	52.4482
52	54.4804	54.4454	54.4304	54.4273	54.4487
54	56.4826	56.4469	56.4315	56.4280	56.4492
56	58.4847	58.4483	58.4325	58.4287	58.4497
58	60.4866	60.4496	60.4335	60.4293	60.4501
60	62.4884	62.4509	62.4344	62.4299	62.4506
62	64.4902	64.4520	64.4352	64.4304	64.4510
64	66.4918	66.4531	66.4361	66.4309	66.4513
66	68.4933	68.4542	68.4369	68.4314	68.4517
68	70.4948	70.4552	70.4376	70.4319	70.4520
70	72.4963	72.4561	72.4383	72.4323	72.4523
72	74.4977	74.4570	74.4390	74.4327	74.4526
74	76.4990	76.4578	76.4396	76.4331	76.4529
76	78.5002	78.4586	78.4402	78.4335	78.4532
78	80.5014	80.4594	80.4408	80.4339	80.4534
80	82.5026	82.4601	82.4413	82.4342	82.4536
82	84.5037	84.4608	84.4418	84.4345	84.4538
84	86.5047	86.4615	86.4423	86.4348	86.4540
86	88.5057	88.4621	88.4428	88.4351	88.4542
88	90.5067	90.4627	90.4433	90.4354	90.4544

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Checking External Spur Gear Sizes by Measurement Over Wires**

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.728}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
90	92.5076	92.4633	92.4437	92.4357	92.4546
92	94.5085	94.4639	94.4441	94.4359	94.4548
94	96.5094	96.4644	96.4445	96.4362	96.4550
96	98.5102	98.4649	98.4449	98.4364	98.4552
98	100.5110	100.4655	100.4453	100.4367	100.4554
100	102.5118	102.4660	102.4456	102.4369	102.4555
102	104.5125	104.4665	104.4460	104.4370	104.4557
104	106.5132	106.4669	106.4463	106.4372	106.4558
106	108.5139	108.4673	108.4466	108.4374	108.4560
108	110.5146	110.4678	110.4469	110.4376	110.4561
110	112.5152	112.4682	112.4472	112.4378	112.4562
112	114.5159	114.4686	114.4475	114.4380	114.4563
114	116.5165	116.4690	116.4478	116.4382	116.4564
116	118.5171	118.4693	118.4481	118.4384	118.4565
118	120.5177	120.4697	120.4484	120.4385	120.4566
120	122.5182	122.4701	122.4486	122.4387	122.4567
122	124.5188	124.4704	124.4489	124.4388	124.4568
124	126.5193	126.4708	126.4491	126.4390	126.4569
126	128.5198	128.4711	128.4493	128.4391	128.4570
128	130.5203	130.4714	130.4496	130.4393	130.4571
130	132.5208	132.4717	132.4498	132.4394	132.4572
132	134.5213	134.4720	134.4500	134.4395	134.4573
134	136.5217	136.4723	136.4502	136.4397	136.4574
136	138.5221	138.4725	138.4504	138.4398	138.4575
138	140.5226	140.4728	140.4506	140.4399	140.4576
140	142.5230	142.4730	142.4508	142.4400	142.4577
142	144.5234	144.4733	144.4510	144.4401	144.4578
144	146.5238	146.4736	146.4512	146.4402	146.4578
146	148.5242	148.4738	148.4513	148.4403	148.4579
148	150.5246	150.4740	150.4515	150.4404	150.4580
150	152.5250	152.4742	152.4516	152.4405	152.4580
152	154.5254	154.4745	154.4518	154.4406	154.4581
154	156.5257	156.4747	156.4520	156.4407	156.4581
156	158.5261	158.4749	158.4521	158.4408	158.4582
158	160.5264	160.4751	160.4523	160.4409	160.4582
160	162.5267	162.4753	162.4524	162.4410	162.4583
162	164.5270	164.4755	164.4526	164.4411	164.4584
164	166.5273	166.4757	166.4527	166.4411	166.4584
166	168.5276	168.4759	168.4528	168.4412	168.4585
168	170.5279	170.4760	170.4529	170.4413	170.4585
170	172.5282	172.4761	172.4531	172.4414	172.4586
180	182.5297	182.4771	182.4537	182.4418	182.4589
190	192.5310	192.4780	192.4542	192.4421	192.4591
200	202.5321	202.4786	202.4548	202.4424	202.4593
300	302.5395	302.4831	302.4579	302.4443	302.4606
400	402.5434	402.4854	402.4596	402.4453	402.4613
500	502.5458	502.4868	502.4606	502.4458	502.4619

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Checking External Spur Gear Sizes by Measurement Over Wires

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.728}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
7	9.1116	9.1172	9.1260	9.1536	9.1928
9	11.1829	11.1844	11.1905	11.2142	11.2509
11	13.2317	13.2296	13.2332	13.2536	13.2882
13	15.2677	15.2617	15.2639	15.2814	15.3142
15	17.2957	17.2873	17.2871	17.3021	17.3329
17	19.3182	19.3072	19.3053	19.3181	19.3482
19	21.3368	21.3233	21.3200	21.3310	21.3600
21	23.3524	23.3368	23.3321	23.3415	23.3696
23	25.3658	25.3481	25.3423	25.3502	25.3775
25	27.3774	27.3579	27.3511	27.3576	27.3842
27	29.3876	29.3664	29.3586	29.3640	29.3899
29	31.3966	31.3738	31.3652	31.3695	31.3948
31	33.4047	33.3804	33.3710	33.3743	33.3991
33	35.4119	35.3863	35.3761	35.3786	35.4029
35	37.4185	37.3916	37.3807	37.3824	37.4063
37	39.4245	39.3964	39.3849	39.3858	39.4094
39	41.4299	41.4007	41.3886	41.3889	41.4120
41	43.4348	43.4047	43.3920	43.3917	43.4145
43	45.4394	45.4083	45.3951	45.3942	45.4168
45	47.4437	47.4116	47.3980	47.3965	47.4188
47	49.4477	49.4147	49.4007	49.3986	49.4206
49	51.4514	51.4175	51.4031	51.4006	51.4223
51	53.4547	53.4202	53.4053	53.4024	53.4239
53	55.4579	55.4227	55.4074	55.4041	55.4254
55	57.4609	57.4249	57.4093	57.4056	57.4267
57	59.4637	59.4271	59.4111	59.4071	59.4280
59	61.4664	61.4291	61.4128	61.4084	61.4292
61	63.4689	63.4310	63.4144	63.4097	63.4303
63	65.4712	65.4328	65.4159	65.4109	65.4313
65	67.4734	67.4344	67.4173	67.4120	67.4323
67	69.4755	69.4360	69.4186	69.4130	69.4332
69	71.4775	71.4375	71.4198	71.4140	71.4341
71	73.4795	73.4389	73.4210	73.4150	73.4349
73	75.4813	75.4403	75.4221	75.4159	75.4357
75	77.4830	77.4416	77.4232	77.4167	77.4364
77	79.4847	79.4428	79.4242	79.4175	79.4371
79	81.4863	81.4440	81.4252	81.4183	81.4378
81	83.4877	83.4451	83.4262	83.4190	83.4384
83	85.4892	85.4462	85.4271	85.4196	85.4390
85	87.4906	87.4472	87.4279	87.4203	87.4395
87	89.4919	89.4481	89.4287	89.4209	89.4400
89	91.4932	91.4490	91.4295	91.4215	91.4405
91	93.4944	93.4499	93.4303	93.4221	93.4410
93	95.4956	95.4508	95.4310	95.4227	95.4415

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Checking External Spur Gear Sizes by Measurement Over Wires**

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.728}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
95	97.4967	97.4516	97.4317	97.4232	97.4420
97	99.4978	99.4524	99.4323	99.4237	99.4424
99	101.4988	101.4532	101.4329	101.4242	101.4428
101	103.4998	103.4540	103.4335	103.4247	103.4432
103	105.5008	105.4546	105.4341	105.4252	105.4436
105	107.5017	107.4553	107.4346	107.4256	107.4440
107	109.5026	109.4559	109.4352	109.4260	109.4443
109	111.5035	111.4566	111.4357	111.4264	111.4447
111	113.5044	113.4572	113.4362	113.4268	113.4450
113	115.5052	115.4578	115.4367	115.4272	115.4453
115	117.5060	117.4584	117.4372	117.4275	117.4456
117	119.5068	119.4589	119.4376	119.4279	119.4459
119	121.5075	121.4594	121.4380	121.4282	121.4462
121	123.5082	123.4599	123.4384	123.4285	123.4465
123	125.5089	125.4604	125.4388	125.4288	125.4468
125	127.5096	127.4609	127.4392	127.4291	127.4471
127	129.5103	129.4614	129.4396	129.4294	129.4473
129	131.5109	131.4619	131.4400	131.4297	131.4476
131	133.5115	133.4623	133.4404	133.4300	133.4478
133	135.5121	135.4628	135.4408	135.4302	135.4480
135	137.5127	137.4632	137.4411	137.4305	137.4483
137	139.5133	139.4636	139.4414	139.4307	139.4485
139	141.5139	141.4640	141.4418	141.4310	141.4487
141	143.5144	143.4644	143.4421	143.4312	143.4489
143	145.5149	145.4648	145.4424	145.4315	145.4491
145	147.5154	147.4651	147.4427	147.4317	147.4493
147	149.5159	149.4655	149.4430	149.4319	149.4495
149	151.5164	151.4658	151.4433	151.4321	151.4497
151	153.5169	153.4661	153.4435	153.4323	153.4498
153	155.5174	155.4665	155.4438	155.4325	155.4500
155	157.5179	157.4668	157.4440	157.4327	157.4502
157	159.5183	159.4671	159.4443	159.4329	159.4504
159	161.5188	161.4674	161.4445	161.4331	161.4505
161	163.5192	163.4677	163.4448	163.4333	163.4507
163	165.5196	165.4680	165.4450	165.4335	165.4508
165	167.5200	167.4683	167.4453	167.4337	167.4510
167	169.5204	169.4686	169.4455	169.4338	169.4511
169	171.5208	171.4688	171.4457	171.4340	171.4513
171	173.5212	173.4691	173.4459	173.4342	173.4514
181	183.5230	183.4704	183.4469	183.4350	183.4520
191	193.5246	193.4715	193.4478	193.4357	193.4526
201	203.5260	203.4725	203.4487	203.4363	203.4532
301	303.5355	303.4790	303.4538	303.4402	303.4565
401	403.5404	403.4823	403.4565	403.4422	403.4582
501	503.5433	503.4843	503.4581	503.4434	503.4592

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Checking Internal Spur Gear Sizes by Measurement Between Wires

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.44}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
10	8.8337	8.7383	8.6617	8.5209	8.3966
12	10.8394	10.7404	10.6623	10.5210	10.3973
14	12.8438	12.7419	12.6627	12.5210	12.3978
16	14.8474	14.7431	14.6630	14.5210	14.3982
18	16.8504	16.7441	16.6633	16.5210	16.3985
20	18.8529	18.7449	18.6635	18.5211	18.3987
22	20.8550	20.7456	20.6636	20.5211	20.3989
24	22.8569	22.7462	22.6638	22.5211	22.3991
26	24.8585	24.7467	24.6639	24.5211	24.3992
28	26.8599	26.7471	26.6640	26.5211	26.3993
30	28.8612	28.7475	28.6641	28.5211	28.3994
32	30.8623	30.7478	30.6642	30.5211	30.3995
34	32.8633	32.7481	32.6642	32.5211	32.3995
36	34.8642	34.7483	34.6643	34.5212	34.3996
38	36.8650	36.7486	36.6642	36.5212	36.3996
40	38.8658	38.7488	38.6644	38.5212	38.3997
42	40.8665	40.7490	40.6644	40.5212	40.3997
44	42.8672	42.7492	42.6645	42.5212	42.3998
46	44.8678	44.7493	44.6645	44.5212	44.3998
48	46.8683	46.7495	46.6646	46.5212	46.3999
50	48.8688	48.7496	48.6646	48.5212	48.3999
52	50.8692	50.7497	50.6646	50.5212	50.3999
54	52.8697	52.7499	52.6647	52.5212	52.4000
56	54.8701	54.7500	54.6647	54.5212	54.4000
58	56.8705	56.7501	56.6648	56.5212	56.4001
60	58.8709	58.7502	58.6648	58.5212	58.4001
62	60.8712	60.7503	60.6648	60.5212	60.4001
64	62.8715	62.7504	62.6648	62.5212	62.4001
66	64.8718	64.7505	64.6649	64.5212	64.4001
68	66.8721	66.7505	66.6649	66.5212	66.4001
70	68.8724	68.7506	68.6649	68.5212	68.4001
72	70.8727	70.7507	70.6649	70.5212	70.4002
74	72.8729	72.7507	72.6649	72.5212	72.4002
76	74.8731	74.7508	74.6649	74.5212	74.4002
78	76.8734	76.7509	76.6649	76.5212	76.4002
80	78.8736	78.7509	78.6649	78.5212	78.4002
82	80.8738	80.7510	80.6649	80.5212	80.4002
84	82.8740	82.7510	82.6649	82.5212	82.4002
86	84.8742	84.7511	84.6650	84.5212	84.4002
88	86.8743	86.7511	86.6650	86.5212	86.4003
90	88.8745	88.7512	88.6650	88.5212	88.4003
92	90.8747	90.7512	90.6650	90.5212	90.4003
94	92.8749	92.7513	92.6650	92.5212	92.4003

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ***(Continued)*** **Checking Internal Spur Gear Sizes by Measurement Between Wires**

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.44}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
96	94.8750	94.7513	94.6650	94.5212	94.4003
98	96.8752	96.7513	96.6650	96.5212	96.4003
100	98.8753	98.7514	98.6650	98.5212	98.4003
102	100.8754	100.7514	100.6650	100.5212	100.4003
104	102.8756	102.7514	102.6650	102.5212	102.4003
106	104.8757	104.7515	104.6650	104.5212	104.4003
108	106.8758	106.7515	106.6650	106.5212	106.4003
110	108.8759	108.7515	108.6651	108.5212	108.4004
112	110.8760	110.7516	110.6651	110.5212	110.4004
114	112.8761	112.7516	112.6651	112.5212	112.4004
116	114.8762	114.7516	114.6651	114.5212	114.4004
118	116.8763	116.7516	116.6651	116.5212	116.4004
120	118.8764	118.7517	118.6651	118.5212	118.4004
122	120.8765	120.7517	120.6651	120.5212	120.4004
124	122.8766	122.7517	122.6651	122.5212	122.4004
126	124.8767	124.7517	124.6651	124.5212	124.4004
128	126.8768	126.7518	126.6651	126.5212	126.4004
130	128.8769	128.7518	128.6652	128.5212	128.4004
132	130.8769	130.7518	130.6652	130.5212	130.4004
134	132.8770	132.7518	132.6652	132.5212	132.4004
136	134.8771	134.7519	134.6652	134.5212	134.4004
138	136.8772	136.7519	136.6652	136.5212	136.4004
140	138.8773	138.7519	138.6652	138.5212	138.4004
142	140.8773	140.7519	140.6652	140.5212	140.4004
144	142.8774	142.7519	142.6652	142.5212	142.4004
146	144.8774	144.7520	144.6652	144.5212	144.4004
148	146.8775	146.7520	146.6652	146.5212	146.4004
150	148.8775	148.7520	148.6652	148.5212	148.4005
152	150.8776	150.7520	150.6652	150.5212	150.4005
154	152.8776	152.7520	152.6652	152.5212	152.4005
156	154.8777	154.7520	154.6652	154.5212	154.4005
158	156.8778	156.7520	156.6652	156.5212	156.4005
160	158.8778	158.7520	158.6652	158.5212	158.4005
162	160.8779	160.7520	160.6652	160.5212	160.4005
164	162.8779	162.7521	162.6652	162.5212	162.4005
166	164.8780	164.7521	164.6652	164.5212	164.4005
168	166.8780	166.7521	166.6652	166.5212	166.4005
170	168.8781	168.7521	168.6652	168.5212	168.4005
180	178.8783	178.7522	178.6652	178.5212	178.4005
190	188.8785	188.7522	188.6652	188.5212	188.4005
200	198.8788	198.7523	198.6652	198.5212	198.4005
300	298.8795	298.7525	298.6654	298.5212	298.4005
400	398.8803	398.7527	398.6654	398.5212	398.4006
500	498.8810	498.7528	498.6654	498.5212	498.4006

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Checking Internal Spur Gear Sizes by Measurement Between Wires

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimensions in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.44}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
7	5.6393	5.5537	5.4823	5.3462	5.2232
9	7.6894	7.5976	7.5230	7.3847	7.2618
11	9.7219	9.6256	9.5490	9.4094	9.2867
13	11.7449	11.6451	11.5669	11.4265	11.3040
15	13.7620	13.6594	13.5801	13.4391	13.3167
17	15.7752	15.6703	15.5902	15.4487	15.3265
19	17.7858	17.6790	17.5981	17.4563	17.3343
21	19.7945	19.6860	19.6045	19.4625	19.3405
23	21.8017	21.6918	21.6099	21.4676	21.3457
25	23.8078	23.6967	23.6143	23.4719	23.3501
27	25.8130	25.7009	25.6181	25.4755	25.3538
29	27.8176	27.7045	27.6214	27.4787	27.3571
31	29.8216	29.7076	29.6242	29.4814	29.3599
33	31.8251	31.7104	31.6267	31.4838	31.3623
35	33.8282	33.7128	33.6289	33.4860	33.3645
37	35.8311	35.7150	35.6310	35.4879	35.3665
39	37.8336	37.7169	37.6327	37.4896	37.3682
41	39.8359	39.7187	39.6343	39.4911	39.3698
43	41.8380	41.7203	41.6357	41.4925	41.3712
45	43.8399	43.7217	43.6371	43.4938	43.3725
47	45.8416	45.7231	45.6383	45.4950	45.3737
49	47.8432	47.7243	47.6394	47.4960	47.3748
51	49.8447	49.7254	49.6404	49.4970	49.3758
53	51.8461	51.7265	51.6414	51.4979	51.3768
55	53.8474	53.7274	53.6422	53.4988	53.3776
57	55.8486	55.7283	55.6431	55.4996	55.3784
59	57.8497	57.7292	57.6438	57.5003	57.3792
61	59.8508	59.7300	59.6445	59.5010	59.3799
63	61.8517	61.7307	61.6452	61.5016	61.3806
65	63.8526	63.7314	63.6458	63.5022	63.3812
67	65.8535	65.7320	65.6464	65.5028	65.3818
69	67.8543	67.7327	67.6469	67.5033	67.3823
71	69.8551	69.7332	69.6475	69.5038	69.3828
73	71.8558	71.7338	71.6480	71.5043	71.3833
75	73.8565	73.7343	73.6484	73.5048	73.3838
77	75.8572	75.7348	75.6489	75.5052	75.3842
79	77.8573	77.7352	77.6493	77.5056	77.3846
81	79.8584	79.7357	79.6497	79.5060	79.3850
83	81.8590	81.7361	81.6501	81.5064	81.3854
85	83.8595	83.7365	83.6505	83.5067	83.3858
87	85.8600	85.7369	85.6508	85.5071	85.3861
89	87.8605	87.7373	87.6511	87.5074	87.3864
91	89.8610	89.7376	89.6514	89.5077	89.3867
93	91.8614	91.7379	91.6517	91.5080	91.3870
95	93.8619	93.7383	93.6520	93.5082	93.3873
97	95.8623	95.7386	95.6523	95.5085	95.3876
99	97.8627	97.7389	97.6526	97.5088	97.3879
101	99.8631	99.7391	99.6528	99.5090	99.3881
103	101.8635	101.7394	101.6531	101.5093	101.3883
105	103.8638	103.7397	103.6533	103.5095	103.3886
107	105.8642	105.7399	105.6535	105.5097	105.3888
109	107.8645	107.7402	107.6537	107.5099	107.3890
111	109.8648	109.7404	109.6539	109.5101	109.3893

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Checking Internal Spur Gear Sizes by Measurement Between Wires**

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and Van Keuren standard wire sizes. For any other diametral pitch, divide dimensions in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.44}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
113	111.8651	111.7406	111.6541	111.5103	111.3895
115	113.8654	113.7409	113.6543	113.5105	113.3897
117	115.8657	115.7411	115.6545	115.5107	115.3899
119	117.8660	117.7413	117.6547	117.5109	117.3900
121	119.8662	119.7415	119.6548	119.5110	119.3902
123	121.8663	121.7417	121.6550	121.5112	121.3904
125	123.8668	123.7418	123.6552	123.5114	123.3905
127	125.8670	125.7420	125.6554	125.5115	125.3907
129	127.8672	127.7422	127.6556	127.5117	127.3908
131	129.8675	129.7424	129.6557	129.5118	129.3910
133	131.8677	131.7425	131.6559	131.5120	131.3911
135	133.8679	133.7427	133.6560	133.5121	133.3913
137	135.8681	135.7428	135.6561	135.5123	135.3914
139	137.8683	137.7430	137.6563	137.5124	137.3916
141	139.8685	139.7431	139.6564	139.5125	139.3917
143	141.8687	141.7433	141.6565	141.5126	141.3918
145	143.8689	143.7434	143.6566	143.5127	143.3919
147	145.8691	145.7436	145.6568	145.5128	145.3920
149	147.8693	147.7437	147.6569	147.5130	147.3922
151	149.8694	149.7438	149.6570	149.5131	149.3923
153	151.8696	151.7439	151.6571	151.5132	151.3924
155	153.8698	153.7441	153.6572	153.5133	153.3925
157	155.8699	155.7442	155.6573	155.5134	155.3926
159	157.8701	157.7443	157.6574	157.5135	157.3927
161	159.8702	159.7444	159.6575	159.5136	159.3928
163	161.8704	161.7445	161.6576	161.5137	161.3929
165	163.8705	163.7446	163.6577	163.5138	163.3930
167	165.8707	165.7447	165.6578	165.5139	165.3931
169	167.8708	167.7448	167.6579	167.5139	167.3932
171	169.8710	169.7449	169.6580	169.5140	169.3933
181	179.8717	179.7453	179.6584	179.5144	179.3937
191	189.8721	189.7458	189.6588	189.5148	189.3940
201	199.8727	199.7461	199.6591	199.5151	199.3944
301	299.8759	299.7485	299.6612	299.5171	299.3965
401	399.8776	399.7496	399.6623	399.5182	399.3975
501	499.8786	499.7504	499.6629	499.5188	499.3981

Table 5. Van Keuren Wire Diameters for Gears

External Gears Wire Dia. = 1.728 ÷ D.P.				Internal Gears Wire Dia. = 1.44 ÷ D.P.			
D.P.	Dia.	D.P.	Dia.	D.P.	Dia.	D.P.	Dia.
2	0.86400	16	0.10800	2	0.72000	16	0.09000
2½	0.69120	18	0.09600	2½	0.57600	18	0.08000
3	0.57600	20	0.08640	3	0.48000	20	0.07200
4	0.43200	22	0.07855	4	0.36000	22	0.06545
5	0.34560	24	0.07200	5	0.28800	24	0.06000
6	0.28800	28	0.06171	6	0.24000	28	0.05143
7	0.24686	32	0.05400	7	0.20571	32	0.04500
8	0.21600	36	0.04800	8	0.18000	36	0.04000
9	0.19200	40	0.04320	9	0.16000	40	0.03600
10	0.17280	48	0.03600	10	0.14400	48	0.03000
11	0.15709	64	0.02700	11	0.13091	64	0.02250
12	0.14400	72	0.02400	12	0.12000	72	0.02000
14	0.12343	80	0.02160	14	0.10286	80	0.01800

Copyright 2004, Industrial Press, Inc., New York, NY

Measurements for Checking Internal Gears when Wire Diameter Equals 1.44 Divided by Diametral Pitch.— Tables 3 and 4 give measurements between wires for checking internal gears of 1 diametral pitch. For any other diametral pitch, divide the measurement given in the table by the diametral pitch required. These measurements are based upon the Van Keuren standard wire size, which, for internal spur gears, equals 1.44 divided by the diametral pitch (see Table 5).

Even Number of Teeth: For an even number of teeth above 170 and not in Table 3, proceed as shown by the following example: Assume that the number of teeth = 380 and pressure angle is 14½ degrees; then, for 1 diametral pitch, figure at left of decimal point = given number of teeth – 2 = 380 – 2 = 378. Figure at right of decimal point lies between decimal values given in table for 300 and 400 teeth and is obtained by interpolation. Thus, 380 – 300 = 80 (change to 0.80); 0.8803 – 0.8795 = 0.0008; hence, decimal required = 0.8795 + (0.80 × 0.0008) 0.88014. Total dimension = 378.88014.

Odd Number of Teeth: Table 4 is for internal gears having odd numbers of teeth. For tooth numbers above 171 and not in the table, proceed as shown by the following example: Assume that number of teeth = 337 and pressure angle is 14½ degrees; then, for 1 diametral pitch, figure at left of decimal point = given No. of teeth – 2 = 337 – 2 = 335. Figure at right of decimal point lies between decimal values given in table for 301 and 401 teeth and is obtained by interpolation. Thus, 337 – 301 = 36 (change to 0.36); 0.8776 – 0.8759 = 0.0017; hence, decimal required = 0.8759 + (0.36 × 0.0017) = 0.8765. Total dimension = 335.8765.

Measurements for Checking External Spur Gears when Wire Diameter Equals 1.68 Divided by Diametral Pitch.— Tables 7 and 8 give measurements *M*, in inches, for checking the pitch diameters of external spur gears of 1 diametral pitch. For any other diametral pitch, divide the measurement given in the table by whatever diametral pitch is required. The result shows what measurement *M* should be when the pitch diameter is correct and there is no allowance for backlash. The procedure for checking for a given amount of backlash when the diameter of the measuring wires equals 1.68 divided by the diametral pitch is explained under a subsequent heading. Tables 7 and 8 are based upon wire sizes equal to 1.68 divided by the diametral pitch. The corresponding wire diameters for various diametral pitches are given in Table 6.

Table 6. Wire Diameters for Spur and Helical Gears Based upon 1.68 Constant

Diametral or Normal Diametral Pitch	Wire Diameter	Diametral or Normal Diametral Pitch	Wire Diameter	Diametral or Normal Diametral Pitch	Wire Diameter	Diametral or Normal Diametral Pitch	Wire Diameter
2	0.840	8	0.210	18	0.09333	40	0.042
2½	0.672	9	0.18666	20	0.084	48	0.035
3	0.560	10	0.168	22	0.07636	64	0.02625
4	0.420	11	0.15273	24	0.070	72	0.02333
5	0.336	12	0.140	28	0.060	80	0.021
6	0.280	14	0.120	32	0.0525	…	…
7	0.240	16	0.105	36	0.04667	…	…

Pin diameter = 1.68 ÷ diametral pitch for spur gears and 1.68 ÷ normal diametral pitch for helical gears.

To find measurement *M* of an external spur gear using wire sizes equal to 1.68 inches divided by the diametral pitch, the same method is followed in using Tables 7 and 8 as that outlined for Tables 1 and 2.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Checking External Spur Gear Sizes by Measurement Over Wires

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and 1.68-inch series wire sizes (a Van Keuren standard). For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.68}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
6	8.1298	8.1442	8.1600	8.2003	8.2504
8	10.1535	10.1647	10.1783	10.2155	10.2633
10	12.1712	12.1796	12.1914	12.2260	12.2722
12	14.1851	14.1910	14.2013	14.2338	14.2785
14	16.1964	16.2001	16.2091	16.2397	16.2833
16	18.2058	18.2076	18.2154	18.2445	18.2871
18	20.2137	20.2138	20.2205	20.2483	20.2902
20	22.2205	22.2190	22.2249	22.2515	22.2927
22	24.2265	24.2235	24.2286	24.2542	24.2949
24	26.2317	26.2275	26.2318	26.2566	26.2967
26	28.2363	28.2309	28.2346	28.2586	28.2982
28	30.2404	30.2339	30.2371	30.2603	30.2996
30	32.2441	32.2367	32.2392	32.2619	32.3008
32	34.2475	34.2391	34.2412	34.2632	34.3017
34	36.2505	36.2413	36.2430	36.2644	36.3026
36	38.2533	38.2433	38.2445	38.2655	38.3035
38	40.2558	40.2451	40.2460	40.2666	40.3044
40	42.2582	42.2468	42.2473	42.2675	42.3051
42	44.2604	44.2483	44.2485	44.2683	44.3057
44	46.2624	46.2497	46.2496	46.2690	46.3063
46	48.2642	48.2510	48.2506	48.2697	48.3068
48	50.2660	50.2522	50.2516	50.2704	50.3073
50	52.2676	52.2534	52.2525	52.2710	52.3078
52	54.2691	54.2545	54.2533	54.2716	54.3082
54	56.2705	56.2555	56.2541	56.2721	56.3086
56	58.2719	58.2564	58.2548	58.2726	58.3089
58	60.2731	60.2572	60.2555	60.2730	60.3093
60	62.2743	62.2580	62.2561	62.2735	62.3096
62	64.2755	64.2587	64.2567	64.2739	64.3099
64	66.2765	66.2594	66.2572	66.2742	66.3102
66	68.2775	68.2601	68.2577	68.2746	68.3104
68	70.2785	70.2608	70.2582	70.2749	70.3107
70	72.2794	72.2615	72.2587	72.2752	72.3109
72	74.2803	74.2620	74.2591	74.2755	74.3111
74	76.2811	76.2625	76.2596	76.2758	76.3113
76	78.2819	78.2631	78.2600	78.2761	78.3115
78	80.2827	80.2636	80.2604	80.2763	80.3117
80	82.2834	82.2641	82.2607	82.2766	82.3119
82	84.2841	84.2646	84.2611	84.2768	84.3121
84	86.2847	86.2650	86.2614	86.2771	86.3123
86	88.2854	88.2655	88.2617	88.2773	88.3124
88	90.2860	90.2659	90.2620	90.2775	90.3126
90	92.2866	92.2662	92.2624	92.2777	92.3127
92	94.2872	94.2666	94.2626	94.2779	94.3129
94	96.2877	96.2670	96.2629	96.2780	96.3130
96	98.2882	98.2673	98.2632	98.2782	98.3131
98	100.2887	100.2677	100.2635	100.2784	100.3132
100	102.2892	102.2680	102.2638	102.2785	102.3134
102	104.2897	104.2683	104.2640	104.2787	104.3135

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. ***(Continued)*** **Checking External Spur Gear Sizes by Measurement Over Wires**

EVEN NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and 1.68-inch series wire sizes (a Van Keuren standard). For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.68}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17½°	20°	25°	30°
104	106.2901	106.2685	106.2642	106.2788	106.3136
106	108.2905	108.2688	108.2644	108.2789	108.3137
108	110.2910	110.2691	110.2645	110.2791	110.3138
110	112.2914	112.2694	112.2647	112.2792	112.3139
112	114.2918	114.2696	114.2649	114.2793	114.3140
114	116.2921	116.2699	116.2651	116.2794	116.3141
116	118.2925	118.2701	118.2653	118.2795	118.3142
118	120.2929	120.2703	120.2655	120.2797	120.3142
120	122.2932	122.2706	122.2656	122.2798	122.3143
122	124.2936	124.2708	124.2658	124.2799	124.3144
124	126.2939	126.2710	126.2660	126.2800	126.3145
126	128.2941	128.2712	128.2661	128.2801	128.3146
128	130.2945	130.2714	130.2663	130.2802	130.3146
130	132.2948	132.2716	132.2664	132.2803	132.3147
132	134.2951	134.2718	134.2666	134.2804	134.3147
134	136.2954	136.2720	136.2667	136.2805	136.3148
136	138.2957	138.2722	138.2669	138.2806	138.3149
138	140.2960	140.2724	140.2670	140.2807	140.3149
140	142.2962	142.2725	142.2671	142.2808	142.3150
142	144.2965	144.2727	144.2672	144.2808	144.3151
144	146.2967	146.2729	146.2674	146.2809	146.3151
146	148.2970	148.2730	148.2675	148.2810	148.3152
148	150.2972	150.2732	150.2676	150.2811	150.3152
150	152.2974	152.2733	152.2677	152.2812	152.3153
152	154.2977	154.2735	154.2678	154.2812	154.3153
154	156.2979	156.2736	156.2679	156.2813	156.3154
156	158.2981	158.2737	158.2680	158.2813	158.3155
158	160.2983	160.2739	160.2681	160.2814	160.3155
160	162.2985	162.2740	162.2682	162.2815	162.3155
162	164.2987	164.2741	164.2683	164.2815	164.3156
164	166.2989	166.2742	166.2684	166.2816	166.3156
166	168.2990	168.2744	168.2685	168.2816	168.3157
168	170.2992	170.2745	170.2686	170.2817	170.3157
170	172.2994	172.2746	172.2687	172.2818	172.3158
180	182.3003	182.2752	182.2691	182.2820	182.3160
190	192.3011	192.2757	192.2694	192.2823	192.3161
200	202.3018	202.2761	202.2698	202.2825	202.3163
300	302.3063	302.2790	302.2719	302.2839	302.3173
400	402.3087	402.2804	402.2730	402.2845	402.3178
500	502.3101	502.2813	502.2736	502.2850	502.3181

Allowance for Backlash: Tables 1, 2, 7, and 8 give measurements over wires when the pitch diameters are correct and there is no allowance for backlash or play between meshing teeth. Backlash is obtained by cutting the teeth somewhat deeper than standard, thus reducing the thickness. Usually, the teeth of both mating gears are reduced in thickness an amount equal to one-half of the total backlash desired. However, if the pinion is small, it is common practice to reduce the gear teeth the full amount of backlash and the pinion is made to standard size. The changes in measurements *M* over wires, for obtaining backlash in external spur gears, are listed in Table 9.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Checking External Spur Gear Sizes by Measurement Over Wires

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and 1.68-inch series wire sizes (a Van Keuren standard). For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.68}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17 ½°	20°	25°	30°
5	6.8485	6.8639	6.8800	6.9202	6.9691
7	8.9555	8.9679	8.9822	9.0199	9.0675
9	11.0189	11.0285	11.0410	11.0762	11.1224
11	13.0615	13.0686	13.0795	13.1126	13.1575
13	15.0925	15.0973	15.1068	15.1381	15.1819
15	17.1163	17.1190	17.1273	17.1570	17.1998
17	19.1351	19.1360	19.1432	19.1716	19.2136
19	21.1505	21.1498	21.1561	21.1832	21.2245
21	23.1634	23.1611	23.1665	23.1926	23.2334
23	25.1743	25.1707	25.1754	25.2005	25.2408
25	27.1836	27.1788	27.1828	27.2071	27.2469
27	29.1918	29.1859	29.1892	29.2128	29.2522
29	31.1990	31.1920	31.1948	31.2177	31.2568
31	33.2053	33.1974	33.1997	33.2220	33.2607
33	35.2110	35.2021	35.2041	35.2258	35.2642
35	37.2161	37.2065	37.2079	37.2292	37.2674
37	39.2208	39.2104	39.2115	39.2323	39.2702
39	41.2249	41.2138	41.2147	41.2349	41.2726
41	43.2287	43.2170	43.2174	43.2374	43.2749
43	45.2323	45.2199	45.2200	45.2396	45.2769
45	47.2355	47.2226	47.2224	47.2417	47.2788
47	49.2385	49.2251	49.2246	49.2435	49.2805
49	51.2413	51.2273	51.2266	51.2452	51.2820
51	53.2439	53.2294	53.2284	53.2468	53.2835
53	55.2463	55.2313	55.2302	55.2483	55.2848
55	57.2485	57.2331	57.2318	57.2497	57.2861
57	59.2506	59.2348	59.2333	59.2509	59.2872
59	61.2526	61.2363	61.2347	61.2521	61.2883
61	63.2545	63.2378	63.2360	63.2532	63.2893
63	65.2562	65.2392	65.2372	65.2543	65.2902
65	67.2579	67.2406	67.2383	67.2553	67.2911
67	69.2594	69.2419	69.2394	69.2562	69.2920
69	71.2609	71.2431	71.2405	71.2571	71.2928
71	73.2623	73.2442	73.2414	73.2579	73.2935
73	75.2636	75.2452	75.2423	75.2586	75.2942
75	77.2649	77.2462	77.2432	77.2594	77.2949
77	79.2661	79.2472	79.2440	79.2601	79.2955
79	81.2673	81.2481	81.2448	81.2607	81.2961
81	83.2684	83.2490	83.2456	83.2614	83.2967
83	85.2694	85.2498	85.2463	85.2620	85.2972
85	87.2704	87.2506	87.2470	87.2625	87.2977
87	89.2714	89.2514	89.2476	89.2631	89.2982
89	91.2723	91.2521	91.2482	91.2636	91.2987
91	93.2732	93.2528	93.2489	93.2641	93.2991
93	95.2741	95.2534	95.2494	95.2646	95.2996

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. ***(Continued)*** **Checking External Spur Gear Sizes by Measurement Over Wires**

ODD NUMBERS OF TEETH

Dimensions in table are for 1 diametral pitch and 1.68-inch series wire sizes (a Van Keuren standard). For any other diametral pitch, divide dimension in table by given pitch.

$$\text{Wire or pin diameter} = \frac{1.68}{\text{Diametral Pitch}}$$

No. of Teeth	Pressure Angle				
	14½°	17 ½°	20°	25°	30°
95	97.2749	97.2541	97.2500	97.2650	97.3000
97	99.2757	99.2547	99.2506	99.2655	99.3004
99	101.2764	101.2553	101.2511	101.2659	101.3008
101	103.2771	103.2558	103.2516	103.2663	103.3011
103	105.2778	105.2563	105.2520	105.2667	105.3015
105	107.2785	107.2568	107.2525	107.2671	107.3018
107	109.2791	109.2573	109.2529	109.2674	109.3021
109	111.2798	111.2578	111.2533	111.2678	111.3024
111	113.2804	113.2583	113.2537	113.2681	113.3027
113	115.2809	115.2588	115.2541	115.2684	115.3030
115	117.2815	117.2592	117.2544	117.2687	117.3033
117	119.2821	119.2596	119.2548	119.2690	119.3036
119	121.2826	121.2601	121.2552	121.2693	121.3038
121	123.2831	123.2605	123.2555	123.2696	123.3041
123	125.2836	125.2608	125.2558	125.2699	125.3043
125	127.2841	127.2612	127.2562	127.2702	127.3046
127	129.2846	129.2615	129.2565	129.2704	129.3048
129	131.2851	131.2619	131.2568	131.2707	131.3050
131	133.2855	133.2622	133.2571	133.2709	133.3053
133	135.2859	135.2626	135.2574	135.2712	135.3055
135	137.2863	137.2629	137.2577	137.2714	137.3057
137	139.2867	139.3632	139.2579	139.2716	139.3059
139	141.2871	141.2635	141.2582	141.2718	141.3060
141	143.2875	143.2638	143.2584	143.2720	143.3062
143	145.2879	145.2641	145.2587	145.2722	145.3064
145	147.2883	147.2644	147.2589	147.2724	147.3066
147	149.2887	149.2647	149.2591	149.2726	149.3068
149	151.2890	151.2649	151.2594	151.2728	151.3069
151	153.2893	153.2652	153.2596	153.2730	153.3071
153	155.2897	155.2654	155.2598	155.2732	155.3073
155	157.2900	157.2657	157.2600	157.2733	157.3074
157	159.2903	159.2659	159.2602	159.2735	159.3076
159	161.2906	161.2661	161.2604	161.2736	161.3077
161	163.2909	163.2663	163.2606	163.2738	163.3078
163	165.2912	165.2665	165.2608	165.2740	165.3080
165	167.2915	167.2668	167.2610	167.2741	167.3081
167	169.2917	169.2670	169.2611	169.2743	169.3083
169	171.2920	171.2672	171.2613	171.2744	171.3084
171	173.2922	173.2674	173.2615	173.2746	173.3085
181	183.2936	183.2684	183.2623	183.2752	183.3091
191	193.2947	193.2692	193.2630	193.2758	193.3097
201	203.2957	203.2700	203.2636	203.2764	203.3101
301	303.3022	303.2749	303.2678	303.2798	303.3132
401	403.3056	403.2774	403.2699	403.2815	403.3147
501	503.3076	503.2789	503.2711	503.2825	503.3156

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Backlash Allowances for External and Internal Spur Gears

No. of Teeth	14½°		17½°		20°		25°		30°	
	Ext.	Int.	Ext.	Int.	Ext.	Int.	Ext.	Int.	Ext.	Int.
5	.0019	.0024	.0018	.0024	.0017	.0023	.0015	.0021	.0013	.0019
10	.0024	.0029	.0022	.0027	.0020	.0026	.0017	.0022	.0015	.0018
20	.0028	.0032	.0025	.0029	.0023	.0027	.0019	.0022	.0016	.0018
30	.0030	.0034	.0026	.0030	.0024	.0027	.0020	.0022	.0016	.0018
40	.0031	.0035	.0027	.0030	.0025	.0027	.0020	.0022	.0017	.0018
50	.0032	.0036	.0028	.0031	.0025	.0027	.0020	.0022	.0017	.0018
100	.0035	.0037	.0030	.0031	.0026	.0027	.0021	.0022	.0017	.0017
200	.0036	.0038	.0031	.0031	.0027	.0027	.0021	.0022	.0017	.0017

External Gears: For each 0.001 inch reduction in pitch-line tooth thickness, *reduce* measurement over wires obtained from Tables 1, 2, 7, or 8 by the amount shown below.

Internal Gears: For each 0.001 inch reduction in pitch-line tooth thickness, *increase* measurement between wires obtained from Tables 3 or 4 by the amounts shown below.

Backlash on pitch line equals double tooth thickness reduction when teeth of *both* mating gears are reduced. If teeth of *one* gear only are reduced, backlash on pitch line equals amount of reduction.

Example: For a 30-tooth, 10-diametral pitch, 20-degree pressure angle, external gear the measurement over wires from Table 1 is 32.4102 ÷ 10. For a backlash of 0.002 this measurement must be reduced by 2 × 0.0024 to 3.2362 or (3.2410 – 0.0048).

Measurements for Checking Helical Gears using Wires or Balls.— Helical gears may be checked for size by using one wire, or ball; two wires, or balls; and three wires, depending on the case at hand. Three wires may be used for measurement of either even or odd tooth numbers provided that the face width and helix angle of the gear permit the arrangement of two wires in adjacent tooth spaces on one side of the gear and a third wire on the opposite side. The wires should be held between flat, parallel plates. The measurement between these plates, and perpendicular to the gear axis, will be the same for both even and odd numbers of teeth because the axial displacement of the wires with the odd numbers of teeth does not affect the perpendicular measurement between the plates. The calculation of measurements over three wires is the same as described for measurements over two wires for even numbers of teeth.

Measurements over One Wire or One Ball for Even or Odd Numbers of Teeth: This measurement is calculated by the method for measurement over two wires for even numbers of teeth and the result divided by two to obtain the measurement from over the wire or ball to the center of the gear mounted on an arbor.

Measurement over Two Wires or Two Balls for Even Numbers of Teeth: The measurement over two wires (or two balls kept in the same plane by holding them against a surface parallel to the face of the gear) is calculated as follows: First, calculate the pitch diameter of the helical gear from the formula D = Number of teeth divided by the product of the normal diametral pitch and the cosine of the helix angle, $D = N \div (P_n \times \cos \psi)$. Next, calculate the number of teeth, N_e, there would be in a spur gear for it to have the same tooth curvature as the helical gear has in the normal plane: $N_e = N/\cos^3 \psi$. Next, refer to Table 7 for spur gears with even tooth numbers and find, by interpolation, the *decimal* value of the constant for this number of teeth under the given *normal* pressure angle. Finally, add 2 to this decimal value and divide the sum by the normal diametral pitch P_n. The result of this calculation, added to the pitch diameter D, is the measurement over two wires or balls.

Example: A helical gear has 32 teeth of 6 normal diametral pitch, 20 degree pressure angle, and 23 degree helix angle. Determine the measurement over two wires, M, without allowance for backlash.

$D = 32 \div 6 \times \cos 23° = 5.7939$; $N_e = 32 \div \cos^3 23° = 41.027$; and in Table 7, fourth column, the decimal part of the measurement for 40 teeth is .2473 and that for 42 teeth is .2485. The

Copyright 2004, Industrial Press, Inc., New York, NY

decimal part for 41.027 teeth is, by interpolation, $\frac{(41.027 - 40)}{(42 - 40)} \times (.2485 - .2473) + .2473$ = 0.2479; (0.2479 + 2) ÷ 6 = 0.3747; and $M = 0.3747 + 5.7939 = 6.1686$.

This measurement over wires or balls is based upon the use of $1.68/P_n$ wires or balls. If measurements over $1.728/P_n$ diameter wires or balls are preferred, use Table 1 to find the decimal part described above instead of Table 7.

Measurement over Two Wires or Two Balls for Odd Numbers of Teeth: The procedure is similar to that for two wire or two ball measurement for even tooth numbers except that a correction is made in the final M value to account for the wires or balls not being diametrically opposite by one-half tooth interval. In addition, care must be taken to ensure that the balls or wires are kept in a plane of the gear's rotation as described previously.

Example: A helical gear has 13 teeth of 8 normal diametral pitch, 14½ degree pressure angle, and 45 degree helix angle. Determine measurement M without allowance for backlash based upon the use of $1.728/P_n$ balls or wires.

As before, $D = 13/8 \times \cos 45° = 2.2981$; $N_e = 13/\cos^3 45° = 36.770$; and in the second column of Table 1 the *decimal* part of the measurement for 36 teeth is .4565 and that for 38 teeth is .4603. The decimal part for 36.770 teeth is, by interpolation, $\frac{(36.770 - 36)}{(38 - 36)} \times (.4603 - .4565) + .4565 = 0.4580$; (0.4580 + 2)/8 = 0.3073; and $M = 0.3073 + 2.2981 = 2.6054$. This measurement is correct for three-wire measurements but, for two balls or wires held in the plane of rotation of the gear, M must be corrected as follows:

$$M \text{ corrected} = (M - \text{Ball Diam.}) \times \cos(90°/N) + \text{Ball Diam.}$$
$$= (2.6054 - 1.728/8) \times \cos(90°/13) + 1.728/8 = 2.5880$$

Checking Spur Gear Size by Chordal Measurement Over Two or More Teeth.— Another method of checking gear sizes, that is generally available, is illustrated by the diagram accompanying Table 10. A vernier caliper is used to measure the distance M over two or more teeth. The diagram illustrates the measurement over two teeth (or with one intervening tooth space), but three or more teeth might be included, depending upon the pitch. The jaws of the caliper are merely held in contact with the sides or profiles of the teeth and perpendicular to the axis of the gear. Measurement M for involute teeth of the correct size is determined as follows

General Formula for Checking External and Internal Spur Gears by Measurement Over Wires: The following formulas may be used for pressure angles or wire sizes not covered by the tables. In these formulas, M = measurement *over* wires for external gears or measurement *between* wires for internal gears; D = pitch diameter; T = arc tooth thickness on pitch circle; W = wire diameter; N = number of gear teeth; A = pressure angle of gear; a = angle, the cosine of which is required in Formulas (2) and (3).

First determine the involute function of angle a (inv a); then the corresponding angle a is found by referring to the tables of involute functions beginning on page 104,

$$\text{inv}\, a = \text{inv}\, A \pm \frac{T}{D} \mp \frac{W}{D\cos A} \mp \frac{\pi}{N} \quad (1)$$

$$\text{For even numbers of teeth, } M = \frac{D\cos A}{\cos a} \pm W \quad (2)$$

$$\text{For odd numbers of teeth, } M = \left(\frac{D\cos A}{\cos a}\right)\left(\cos\frac{90°}{N}\right) \pm W \quad (3)$$

Note: In Formulas (1), (2), and (3), use the upper sign for *external* and the lower sign for *internal* gears wherever a ± or ∓ appears in the formulas.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Chordal Measurements over Spur Gear Teeth of 1 Diametral Pitch

Find value of *M* under pressure angle and opposite number of teeth; divide *M* by diametral pitch of gear to be measured and then subtract one-half total backlash to obtain a measurement *M* equivalent to given pitch and backlash. The number of teeth to gage or measure over is shown by Table 11.



Number of Gear Teeth	*M* in Inches for 1 D.P.	Number of Gear Teeth	*M* in Inches for 1 D.P.	Number of Gear Teeth	*M* in Inches for 1 D.P.	Number of Gear Teeth	*M* in Inches for 1 D.P.
Pressure Angle, 14½ Degrees							
12	4.6267	37	7.8024	62	14.0197	87	20.2370
13	4.6321	38	10.8493	63	17.0666	88	23.2838
14	4.6374	39	10.8547	64	17.0720	89	23.2892
15	4.6428	40	10.8601	65	17.0773	90	23.2946
16	4.6482	41	10.8654	66	17.0827	91	23.2999
17	4.6536	42	10.8708	67	17.0881	92	23.3053
18	4.6589	43	10.8762	68	17.0934	93	23.3107
19	7.7058	44	10.8815	69	17.0988	94	23.3160
20	7.7112	45	10.8869	70	17.1042	95	23.3214
21	7.7166	46	10.8923	71	17.1095	96	23.3268
22	7.7219	47	10.8976	72	17.1149	97	23.3322
23	7.7273	48	10.9030	73	17.1203	98	23.3375
24	7.7326	49	10.9084	74	17.1256	99	23.3429
25	7.7380	50	10.9137	75	17.1310	100	23.3483
26	7.7434	51	13.9606	76	20.1779	101	26.3952
27	7.7488	52	13.9660	77	20.1833	102	26.4005
28	7.7541	53	13.9714	78	20.1886	103	26.4059
29	7.7595	54	13.9767	79	20.1940	104	26.4113
30	7.7649	55	13.9821	80	20.1994	105	26.4166
31	7.7702	56	13.9875	81	20.2047	106	26.4220
32	7.7756	57	13.9929	82	20.2101	107	26.4274
33	7.7810	58	13.9982	83	20.2155	108	26.4327
34	7.7683	59	14.0036	84	20.2208	109	26.4381
35	7.7917	60	14.0090	85	20.2262	110	26.4435
36	7.7971	61	14.0143	86	20.2316	…	…
Pressure Angle, 20 Degrees							
12	4.5963	30	10.7526	48	16.9090	66	23.0653
13	4.6103	31	10.7666	49	16.9230	67	23.0793
14	4.6243	32	10.7806	50	16.9370	68	23.0933
15	4.6383	33	10.7946	51	16.9510	69	23.1073
16	4.6523	34	10.8086	52	16.9650	70	23.1214
17	4.6663	35	10.8226	53	16.9790	71	23.1354
18	4.6803	36	10.8366	54	16.9930	72	23.1494
19	7.6464	37	13.8028	55	19.9591	73	26.1155
20	7.6604	38	13.8168	56	19.9731	74	26.1295
21	7.6744	39	13.8307	57	19.9872	75	26.1435
22	7.6884	40	13.8447	58	20.0012	76	26.1575
23	7.7024	41	13.8587	59	20.0152	77	26.1715
24	7.7165	42	13.8727	60	20.0292	78	26.1855
25	7.7305	43	13.8867	61	20.0432	79	26.1995
26	7.7445	44	13.9007	62	20.0572	80	26.2135
27	7.7585	45	13.9147	63	20.0712	81	26.2275
28	10.7246	46	16.8810	64	23.0373	…	…
29	10.7386	47	16.8950	65	23.0513	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table for Determining the Chordal Dimension: Table 10 gives the chordal dimensions for one diametral pitch when measuring over the number of teeth indicated in Table 11. To obtain any chordal dimension, it is simply necessary to divide chord *M* in the table (opposite the given number of teeth) by the diametral pitch of the gear to be measured and then subtract from the quotient one-half the total backlash between the mating pair of gears. In cases where a small pinion is used with a large gear and all of the backlash is to be obtained by reducing the gear teeth, the total amount of backlash is subtracted from the chordal dimension of the gear and nothing from the chordal dimension of the pinion. The application of the tables will be illustrated by an example.

Table 11. Number of Teeth Included in Chordal Measurement

Tooth Range for 14½° Pressure Angle	Tooth Range for 20° Pressure Angle	Number of Teeth to Gage Over	Tooth Range for 14½° Pressure Angle	Tooth Range for 20° Pressure Angle	Number of Teeth to Gage Over
12 to 18	12 to 18	2	63 to 75	46 to 54	6
19 to 37	19 to 27	3	76 to 87	55 to 63	7
38 to 50	28 to 36	4	88 to 100	64 to 72	8
51 to 62	37 to 45	5	101 to 110	73 to 81	9

This table shows the number of teeth to be included between the jaws of the vernier caliper in measuring dimension *M* as explained in connection with Table 10.

Example: Determine the chordal dimension for checking the size of a gear having 30 teeth of 5 diametral pitch and a pressure angle of 20 degrees. A total backlash of 0.008 inch is to be obtained by reducing equally the teeth of both mating gears.

Table 10 shows that chordal distance for 30 teeth of one diametral pitch and a pressure angle of 20 degrees is 10.7526 inches; one-half of the backlash equals 0.004 inch; hence,

$$\text{Chordal dimension} = \frac{10.7526}{5} - 0.004 = 2.1465 \text{ inches}$$

Table 11 shows that this is the chordal dimension when the vernier caliper spans four teeth, this being the number of teeth to gage over whenever gears of 20-degree pressure angle have any number of teeth from 28 to 36, inclusive.

If it is considered necessary to leave enough stock on the gear teeth for a shaving or finishing cut, this allowance is simply added to the chordal dimension of the finished teeth to obtain the required measurement over the teeth for the roughing operation. It may be advisable to place this chordal dimension for rough machining on the detail drawing.

Formula for Chordal Dimension *M*.— The required measurement *M* over spur gear teeth may be obtained by the following formula in which *R* = pitch radius of gear, *A* = pressure angle, *T* = tooth thickness along pitch circle, *N* = number of gear teeth, *S* = number of tooth *spaces* between caliper jaws, *F* = a factor depending on the pressure angle = 0.01109 for 14½°; = 0.01973 for 17½°; = 0.0298 for 20°; = 0.04303 for 22½°; = 0.05995 for 25°. This factor *F* equals twice the involute function of the pressure angle.

$$M = R \times \cos A \times \left(\frac{T}{R} + \frac{6.2832 \times S}{N} + F \right)$$

Example: A spur gear has 30 teeth of 6 diametral pitch and a pressure angle of 14½ degrees. Determine measurement *M* over three teeth, there being two intervening tooth spaces.

The pitch radius = 2½ inches, the arc tooth thickness equivalent to 6 diametral pitch is 0.2618 inch (if no allowance is made for backlash) and factor *F* for 14½ degrees = 0.01109 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

$$M = 2.5 \times 0.96815 \times \left(\frac{0.2618}{2.5} + \frac{6.2832 \times 2}{30} + 0.01109\right) = 1.2941 \text{ inches}$$

Checking Enlarged Pinions by Measuring Over Pins or Wires.— When the teeth of small spur gears or pinions would be undercut if generated by an unmodified straight-sided rack cutter or hob, it is common practice to make the outside diameter larger than standard. The amount of increase in outside diameter varies with the pressure angle and number of teeth, as shown by Table 7 on page 2050. The teeth are always cut to standard depth on a generating type of machine such as a gear hobber or gear shaper; and because the number of teeth and pitch are not changed, the pitch diameter also remains unchanged. The tooth thickness on the pitch circle, however, is increased and wire sizes suitable for standard gears are not large enough to extend above the tops of these enlarged gears or pinions; hence, the Van Keuren wire size recommended for these enlarged pinions equals 1.92 ÷ diametral pitch. Table 12 gives measurements over wires of this size, for checking full-depth involute gears of 1 diametral pitch. For any other pitch, merely divide the measurement given in the table by the diametral pitch. Table 12 applies to pinions that have been enlarged by the same amounts as given in tables 7 and 8, starting on page 2050. These enlarged pinions will mesh with standard gears; but if the standard center distance is to be maintained, reduce the gear diameter below the standard size by as much as the pinion diameter is increased.

Table 12. Checking Enlarged Spur Pinions by Measurement Over Wires

Measurements over wires are given in table for 1 diametral pitch. For any other diametral pitch, divide measurement in table by given pitch. Wire size equals 1.92 ÷ diametral pitch.

Number of Teeth	Outside or Major Diameter (Note 1)	Circular Tooth Thickness (Note 2)	Measurement Over Wires	Number of Teeth	Outside or Major Diameter (Note 1)	Circular Tooth Thickness (Note 2)	Measurement Over Wires
14½-degree full-depth involute teeth:				20-degree full-depth involute teeth:			
10	13.3731	1.9259	13.6186	10	12.936	1.912	13.5039
11	14.3104	1.9097	14.4966	11	13.818	1.868	14.3299
12	15.2477	1.8935	15.6290	12	14.702	1.826	15.4086
13	16.1850	1.8773	16.5211	13	15.584	1.783	16.2473
14	17.1223	1.8611	17.6244	14	16.468	1.741	17.2933
15	18.0597	1.8449	18.5260	15	17.350	1.698	18.1383
16	18.9970	1.8286	19.6075	16	18.234	1.656	19.1596
17	19.9343	1.8124	20.5156	17	19.116	1.613	20.0080
18	20.8716	1.7962	21.5806				
19	21.8089	1.7800	22.4934				
20	22.7462	1.7638	23.5451				
21	23.6835	1.7476	24.4611				
22	24.6208	1.7314	25.5018				
23	25.5581	1.7151	26.4201				
24	26.4954	1.6989	27.4515				
25	27.4328	1.6827	28.3718				
26	28.3701	1.6665	29.3952				
27	29.3074	1.6503	30.3168				
28	30.2447	1.6341	31.3333				
29	31.1820	1.6179	32.2558				
30	32.1193	1.6017	33.2661				
31	33.0566	1.5854	34.1889				

Note 1: These enlargements, which are to improve the tooth form and avoid undercut, conform to those given in Tables 7 and 8, starting on page 2050 where data will be found on the minimum number of teeth in the mating gear.

Note 2: The circular or arc thickness is at the standard pitch diameter. The corresponding chordal thickness may be found as follows: Multiply arc thickness by 90 and then divide product by 3.1416 × pitch radius; find sine of angle thus obtained and multiply it by pitch diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

GEAR MATERIALS

Classification of Gear Steels.— Gear steels may be divided into two general classes — the plain carbon and the alloy steels. Alloy steels are used to some extent in the industrial field, but heat-treated plain carbon steels are far more common. The use of untreated alloy steels for gears is seldom, if ever, justified, and then, only when heat-treating facilities are lacking. The points to be considered in determining whether to use heat-treated plain carbon steels or heat-treated alloy steels are: Does the service condition or design require the superior characteristics of the alloy steels, or, if alloy steels are not required, will the advantages to be derived offset the additional cost? For most applications, plain carbon steels, heat-treated to obtain the best of their qualities for the service intended, are satisfactory and quite economical. The advantages obtained from using heat-treated alloy steels in place of heat-treated plain carbon steels are as follows:

1) Increased surface hardness and depth of hardness penetration for the same carbon content and quench.

2) Ability to obtain the same surface hardness with a less drastic quench and, in the case of some of the alloys, a lower quenching temperature, thus giving less distortion.

3) Increased toughness, as indicated by the higher values of yield point, elongation, and reduction of area.

4) Finer grain size, with the resulting higher impact toughness and increased wear resistance.

5) In the case of some of the alloys, better machining qualities or the possibility of machining at higher hardnesses.

Use of Casehardening Steels.— Each of the two general classes of gear steels may be further subdivided as follows: 1) Casehardening steels; 2) full-hardening steels; and 3) steels that are heat-treated and drawn to a hardness that will permit machining.

The first two — casehardening and full-hardening steels — are interchangeable for some kinds of service, and the choice is often a matter of personal opinion. Casehardening steels with their extremely hard, fine-grained (when properly treated) case and comparatively soft and ductile core are generally used when resistance to wear is desired. Casehardening alloy steels have a fairly tough core, but not as tough as that of the full-hardening steels. In order to realize the greatest benefits from the core properties, casehardened steels should be double-quenched. This is particularly true of the alloy steels, because the benefits derived from their use seldom justify the additional expense, unless the core is refined and toughened by a second quench. The penalty that must be paid for the additional refinement is increased distortion, which may be excessive if the shape or design does not lend itself to the casehardening process.

Use of "Thru-Hardening" Steels.— Thru-hardening steels are used when great strength, high endurance limit, toughness, and resistance to shock are required. These qualities are governed by the kind of steel and treatment used. Fairly high surface hardnesses are obtainable in this group, though not so high as those of the casehardening steels. For that reason, the resistance to wear is not so great as might be obtained, but when wear resistance combined with great strength and toughness is required, this type of steel is superior to the others. Thru-hardening steels become distorted to some extent when hardened, the amount depending upon the steel and quenching medium used. For that reason, thru-hardening steels are not suitable for high-speed gearing where noise is a factor, or for gearing where accuracy is of paramount importance, except, of course, in cases where grinding of the teeth is practicable. The medium and high-carbon percentages require an oil quench, but a water quench may be necessary for the lower carbon contents, in order to obtain the highest physical properties and hardness. The distortion, however, will be greater with the water quench.

Heat-Treatment that Permits Machining.— When the grinding of gear teeth is not practicable and a high degree of accuracy is required, hardened steels may be drawn or tem-

Copyright 2004, Industrial Press, Inc., New York, NY

pered to a hardness that will permit the cutting of the teeth. This treatment gives a highly refined structure, great toughness, and, in spite of the low hardness, excellent wearing qualities. The lower strength is somewhat compensated for by the elimination of the increment loads due to the impacts which are caused by inaccuracies. When steels that have a low degree of hardness penetration from surface to core are treated in this manner, the design cannot be based on the physical properties corresponding to the hardness at the surface. Since the physical properties are determined by the hardness, the drop in hardness from surface to core will give lower physical properties at the root of the tooth, where the stress is greatest. The quenching medium may be either oil, water, or brine, depending on the steel used and hardness penetration desired. The amount of distortion, of course, is immaterial, because the machining is done after heat-treating.

Making Pinion Harder than Gear to Equalize Wear.— Beneficial results from a wear standpoint are obtained by making the pinion harder than the gear. The pinion, having a lesser number of teeth than the gear, naturally does more work per tooth, and the differential in hardness between the pinion and the gear (the amount being dependent on the ratio) serves to equalize the rate of wear. The harder pinion teeth correct the errors in the gear teeth to some extent by the initial wear and then seem to burnish the teeth of the gear and increase its ability to withstand wear by the greater hardness due to the cold-working of the surface. In applications where the gear ratio is high and there are no severe shock loads, a casehardened pinion running with an oil-treated gear, treated to a Brinell hardness at which the teeth may be cut after treating, is an excellent combination. The pinion, being relatively small, is distorted but little, and distortion in the gear is circumvented by cutting the teeth after treatment.

Forged and Rolled Carbon Steels for Gears.— These compositions cover steel for gears in three groups, according to heat treatment, as follows:

a) case-hardened gears

b) unhardened gears, not heat treated after machining

c) hardened and tempered gears

Forged and rolled carbon gear steels are purchased on the basis of the requirements as to chemical composition specified in Table 1. Class N steel will normally be ordered in ten point carbon ranges within these limits. Requirements as to physical properties have been omitted, but when they are called for the requirements as to carbon shall be omitted. The steels may be made by either or both the open hearth and electric furnace processes.

Table 1. Compositions of Forged and Rolled Carbon Steels for Gears

Heat Treatment	Class	Carbon	Manganese	Phosphorus	Sulfur
Case-hardened	C	0.15–0.25	0.40–0.70	0.045 max	0.055 max
Untreated	N	0.25–0.50	0.50–0.80	0.045 max	0.055 max
Hardened (or untreated)	H	0.40–0.50	0.40–0.70	0.045 max	0.055 max

Forged and Rolled Alloy Steels for Gears.— These compositions cover alloy steel for gears, in two classes according to heat treatment, as follows:

a) casehardened gears

b) hardened and tempered gears

Forged and rolled alloy gear steels are purchased on the basis of the requirements as to chemical composition specified in Table 2. Requirements as to physical properties have been omitted. The steel shall be made by either or both the open hearth and electric furnace process.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Compositions of Forged and Rolled Alloy Steels for Gears

Steel Specification	Chemical Composition[a]					
	C	Mn	Si	Ni	Cr	Mo
AISI 4130	0.28–0.30	0.40–0.60	0.20–0.35	…	0.80–1.1	0.15–0.25
AISI 4140	0.38–0.43	0.75–1.0	0.20–0.35	…	0.80–1.1	0.15–0.25
AISI 4340	0.38–0.43	0.60–0.80	0.20–0.35	1.65–2.0	0.70–90	0.20–0.30
AISI 4615	0.13–0.18	0.45–0.65	0.20–0.35	1.65–2.0	…	0.20–0.30
AISI 4620	0.17–0.22	0.45–0.65	0.20–0.35	1.65–2.0	…	0.20–0.30
AISI 8615	0.13–0.18	0.70–0.90	0.20–0.35	0.40–0.70	0.40–0.60	0.15–0.25
AISI 8620	0.18–0.23	0.70–0.90	0.20–0.35	0.40–0.70	0.40–0.60	0.15–0.25
AISI 9310	0.08–0.13	0.45–0.65	0.20–0.35	3.0–3.5	1.0–1.4	0.08–0.15
Nitralloy						
Type N[b]	0.20–0.27	0.40–0.70	0.20–0.40	3.2–3.8	1.0–1.3	0.20–0.30
135 Mod.[b]	0.38–0.45	0.40–0.70	0.20–0.40	…	1.4–1.8	0.30–0.45

[a] C = carbon; Mn = manganese; Si = silicon; Ni = nickel; Cr = chromium, and Mo = molybdenum.
[b] Both Nitralloy alloys contain aluminum 0.85–1.2%

Steel Castings for Gears.— It is recommended that steel castings for cut gears be purchased on the basis of chemical analysis and that only two types of analysis be used, one for case-hardened gears and the other for both untreated gears and those which are to be hardened and tempered. The steel is to be made by the open hearth, crucible, or electric furnace processes. The converter process is not recognized. Sufficient risers must be provided to secure soundness and freedom from undue segregation. Risers should not be broken off the unannealed castings by force. Where risers are cut off with a torch, the cut should be at least one-half inch above the surface of the castings, and the remaining metal removed by chipping, grinding, or other noninjurious method.

Steel for use in gears should conform to the requirements for chemical composition indicated in Table 3. All steel castings for gears must be thoroughly normalized or annealed, using such temperature and time as will entirely eliminate the characteristic structure of unannealed castings.

Table 3. Compositions of Cast Steels for Gears

Steel Specification	Chemical Composition[a]			
	C	Mn	Si	
SAE-0022	0.12–0.22	0.50–0.90	0.60 Max.	May be carburized
SAE-0050	0.40–0.50	0.50–0.90	0.80 Max.	Hardenable 210–250

[a] C = carbon; Mn = manganese; and Si = silicon.

Effect of Alloying Metals on Gear Steels.— The effect of the various alloying elements on steel are here summarized to assist in deciding on the particular kind of alloy steel to use for specific purposes. The characteristics outlined apply only to heat-treated steels. When the effect of the addition of an alloying element is stated, it is understood that reference is made to alloy steels of a given carbon content, compared with a plain carbon steel of the same carbon content.

Nickel: The addition of nickel tends to increase the hardness and strength, with but little sacrifice of ductility. The hardness penetration is somewhat greater than that of plain carbon steels. Use of nickel as an alloying element lowers the critical points and produces less distortion, due to the lower quenching temperature. The nickel steels of the case-hardening group carburize more slowly, but the grain growth is less.

Chromium: Chromium increases the hardness and strength over that obtained by the use of nickel, though the loss of ductility is greater. Chromium refines the grain and imparts a

Copyright 2004, Industrial Press, Inc., New York, NY

greater depth of hardness. Chromium steels have a high degree of wear resistance and are easily machined in spite of the fine grain.

Manganese: When present in sufficient amounts to warrant the use of the term alloy, the addition of manganese is very effective. It gives greater strength than nickel and a higher degree of toughness than chromium. Owing to its susceptibility to cold-working, it is likely to flow under severe unit pressures. Up to the present time, it has never been used to any great extent for heat-treated gears, but is now receiving an increasing amount of attention.

Vanadium: Vanadium has a similar effect to that of manganese—increasing the hardness, strength, and toughness. The loss of ductility is somewhat more than that due to manganese, but the hardness penetration is greater than for any of the other alloying elements. Owing to the extremely fine-grained structure, the impact strength is high; but vanadium tends to make machining difficult.

Molybdenum: Molybdenum has the property of increasing the strength without affecting the ductility. For the same hardness, steels containing molybdenum are more ductile than any other alloy steels, and having nearly the same strength, are tougher; in spite of the increased toughness, the presence of molybdenum does not make machining more difficult. In fact, such steels can be machined at a higher hardness than any of the other alloy steels. The impact strength is nearly as great as that of the vanadium steels.

Chrome-Nickel Steels: The combination of the two alloying elements chromium and nickel adds the beneficial qualities of both. The high degree of ductility present in nickel steels is complemented by the high strength, finer grain size, deep hardening, and wear-resistant properties imparted by the addition of chromium. The increased toughness makes these steels more difficult to machine than the plain carbon steels, and they are more difficult to heat treat. The distortion increases with the amount of chromium and nickel.

Chrome-Vanadium Steels: Chrome-vanadium steels have practically the same tensile properties as the chrome-nickel steels, but the hardening power, impact strength, and wear resistance are increased by the finer grain size. They are difficult to machine and become distorted more easily than the other alloy steels.

Chrome-Molybdenum Steels: This group has the same qualities as the straight molybdenum steels, but the hardening depth and wear resistance are increased by the addition of chromium. This steel is very easily heat treated and machined.

Nickel-Molybdenum Steels: Nickel-molybdenum steels have qualities similar to chrome-molybdenum steel. The toughness is said to be greater, but the steel is somewhat more difficult to machine.

Sintered Materials.— For high production of low and moderately loaded gears, significant production cost savings may be effected by the use of a sintered metal powder. With this material, the gear is formed in a die under high pressure and then sintered in a furnace. The primary cost saving comes from the great reduction in labor cost of machining the gear teeth and other gear blank surfaces. The volume of production must be high enough to amortize the cost of the die and the gear blank must be of such a configuration that it may be formed and readily ejected from the die.

Bronze and Brass Gear Castings.— These specifications cover nonferrous metals for spur, bevel, and worm gears, bushings and flanges for composition gears. This material shall be purchased on the basis of chemical composition. The alloys may be made by any approved method.

Spur and Bevel Gears: For spur and bevel gears, hard cast bronze is recommended (ASTM B-10-18; SAE No. 62; and the well-known 88-10-2 mixture) with the following limits as to composition: Copper, 86 to 89; tin, 9 to 11; zinc, 1 to 3; lead (max), 0.20; iron (max), 0.06 per cent. Good castings made from this bronze should have the following minimum physical characteristics: Ultimate strength, 30,000 pounds per square inch; yield point, 15,000 pounds per square inch; elongation in 2 inches, 14 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Steels for Industrial Gearing

Material Specification	Hardness Case Rc	Hardness Core Bhn	Typical Heat Treatment, Characteristics, and Uses
Case-Hardening Steels			
AISI 1020 AISI 1116	55–60	160–230	Carburize, harden, temper at 350°F. For gears that must be wear-resistant. Normalizedmaterial is easily machined. Core is ductile but has little strength.
AISI 4130 AISI 4140	50–55	270–370	Harden, temper at 900°F, Nitride. For parts requiring greater wear resistance than that of through-hardened steels but cannot tolerate the distortion of carburizing. Case is shallow, core is tough.
AISI 4615 AISI 4620	} 55–60	170–260	Carburize, harden, temper at 350°F. For gears requiring high fatigue resistance and strength.
AISI 8615 AISI 8620	} 55–60	200–300	The 86xx series has better machinability. The 20 point steels are used for coarser teeth.
AISI 9310	58–63	250–350	Carburize, harden, temper at 300°F. Primarily for aerospace gears that are highly loaded and operate at high pitch line velocity and for other gears requiring high reliability under extreme operating conditions. This material is not used at high temperatures.
Nitralloy N and Type 135 Mod. (15-N)	90–94	300–370	Harden, temper at 1200°F, Nitride. For gears requiring high strength and wear resistance that cannot tolerate the distortion of thecarburizing process or that operate at high temperatures. Gear teeth are usually finished before nitriding. Care must be exercised in running nitrided gears together to avoid crazing of case-hardened surfaces.
Through-Hardening Steels			
AISI 1045 AISI 1140	24–40	…	Harden and temper to required hardness. Oil quench for lower hardness and water quench for higher hardness. For gears of medium and large size requiring moderate strength and wear resistance. Gears that must have consistent, solid sections to withstand quenching.
AISI 4140 AISI 4340	24–40	…	Harden (oil quench), temper to required hardness. For gears requiring high strength and wear resistance, and high shock loading resistance. Use 41xx series for moderate sections and 43xx series for heavy sections. Gears must have consistent, solid sections to withstand quenching.

Worm Gears: For bronze worm gears, two alternative analyses of phosphor bronze are recommended, SAE No. 65 and No. 63.

SAE No. 65 (called phosphor gear bronze) has the following composition: Copper, 88 to 90; tin, 10 to 12; phosphorus, 0.1 to 0.3; lead, zinc, and impurities (max) 0.5 per cent.

Good castings made of this alloy should have the following minimum physical characteristics: Ultimate strength, 35,000 pounds per square inch; yield point, 20,000 pounds per square inch; elongation in 2 inches, 10 per cent.

The composition of SAE No. 63 (called leaded gun metal) follows: copper, 86 to 89; tin, 9 to 11; lead, 1 to 2.5; phosphorus (max), 0.25; zinc and impurities (max), 0.50 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Good castings made of this alloy should have the following minimum physical characteristics: Ultimate strength, 30,000 pounds per square inch; yield point, 12,000 pounds per square inch; elongation in 2 inches, 10 per cent.

These alloys, especially No. 65, are adapted to chilling for hardness and refinement of grain. No. 65 is to be preferred for use with worms of great hardness and fine accuracy. No. 63 is to be preferred for use with unhardened worms.

Gear Bushings: For bronze bushings for gears, SAE No. 64 is recommended of the following analysis: copper, 78.5 to 81.5; tin, 9 to 11; lead, 9 to 11; phosphorus, 0.05 to 0.25; zinc (max), 0.75; other impurities (max), 0.25 per cent. Good castings of this alloy should have the following minimum physical characteristics: Ultimate strength, 25,000 pounds per square inch; yield point, 12,000 pounds per square inch; elongation in 2 inches, 8 per cent.

Flanges for Composition Pinions: For brass flanges for composition pinions ASTM B-30-32T, and SAE No. 40 are recommended. This is a good cast red brass of sufficient strength and hardness to take its share of load and wear when the design is such that the flanges mesh with the mating gear. The composition is as follows: copper, 83 to 86; tin, 4.5 to 5.5; lead, 4.5 to 5.5; zinc, 4.5 to 5.5; iron (max) 0.35; antimony (max), 0.25 per cent; aluminum, none. Good castings made from this alloy should have the following minimum physical characteristics: ultimate strength, 27,000 pounds per square inch; yield point, 12,000 pounds per square inch; elongation in 2 inches, 16 per cent.

Materials for Worm Gearing.— The Hamilton Gear & Machine Co. conducted an extensive series of tests on a variety of materials that might be used for worm gears, to ascertain which material is the most suitable. According to these tests chill-cast nickel-phosphor-bronze ranks first in resistance to wear and deformation. This bronze is composed of approximately 87.5 per cent copper, 11 per cent tin, 1.5 per cent nickel, with from 0.1 to 0.2 per cent phosphorus. The worms used in these tests were made from SAE-2315, 3½ per cent nickel steel, case-hardened, ground, and polished. The Shore scleroscope hardness of the worms was between 80 and 90. This nickel alloy steel was adopted after numerous tests of a variety of steels, because it provided the necessary strength, together with the degree of hardness required.

The material that showed up second best in these tests was a No. 65 SAE bronze. Navy bronze (88-10-2) containing 2 per cent zinc, with no phosphorus, and not chilled, performed satisfactorily at speeds of 600 revolutions per minute, but was not sufficiently strong at lower speeds. Red brass (85-5-5) proved slightly better at from 1500 to 1800 revolutions per minute, but would bend at lower speeds, before it would show actual wear.

Non-metallic Gearing.— Non-metallic or composition gearing is used primarily where quietness of operation at high speed is the first consideration. Non-metallic materials are also applied very generally to timing gears and numerous other classes of gearing. Rawhide was used originally for non-metallic gears, but other materials have been introduced that have important advantages. These later materials are sold by different firms under various trade names, such as Micarta, Textolite, Formica, Dilecto, Spauldite, Phenolite, Fibroc, Fabroil, Synthane, Celoron, etc. Most of these gear materials consist of layers of canvas or other material that is impregnated with plastics and forced together under hydraulic pressure, which, in conjunction with the application of heat, forms a dense rigid mass.

Although phenol resin gears in general are resilient, they are self-supporting and require no side plates or shrouds unless subjected to a heavy starting torque. The phenol resinoid element protects these gears from vermin and rodents.

The non-metallic gear materials referred to are generally assumed to have the power-transmitting capacity of cast iron. Although the tensile strength may be considerably less than that of cast iron, the resiliency of these materials enables them to withstand impact and

Copyright 2004, Industrial Press, Inc., New York, NY

abrasion to a degree that might result in excessive wear of cast-iron teeth. Thus, composition gearing of impregnated canvas has often proved to be more durable than cast iron.

Application of Non-metallic Gears.— The most effective field of use for these non-metallic materials is for high-speed duty. At low speeds, when the starting torque may be high, or when the load may fluctuate widely, or when high shock loads may be encountered, these non-metallic materials do not always prove satisfactory. In general, non-metallic materials should not be used for pitch-line velocities below 600 feet per minute.

Tooth Form: The best tooth form for non-metallic materials is the 20-degree stub-tooth system. When only a single pair of gears is involved and the center distance can be varied, the best results will be obtained by making the non-metallic driving pinion of all-addendum form, and the driven metal gear with standard tooth proportions. Such a drive will carry from 50 to 75 per cent greater loads than one of standard tooth proportions.

Material for Mating Gear: For durability under load, the use of hardened steel (over 400 Brinell) for the mating metal gear appears to give the best results. A good second choice for the material of the mating member is cast iron. The use of brass, bronze, or soft steel (under 400 Brinell) as a material for the mating member of phenolic laminated gears leads to excessive abrasive wear.

Power-Transmitting Capacity of Non-metallic Gears.— The characteristics of gears made of phenolic laminated materials are so different from those of metal gears that they should be considered in a class by themselves. Because of the low modulus of elasticity, most of the effects of small errors in tooth form and spacing are absorbed at the tooth surfaces by the elastic deformation, and have but little effect on the strength of the gears.

If S = safe working stress for a given velocity
S_s = allowable static stress
V = pitch-line velocity in feet per minute

then, according to the recommended practice of the American Gear Manufacturers' Association,

$$S = S_s \times \left(\frac{150}{200 + V} + 0.25 \right)$$

The value of S_s for phenolic laminated materials is given as 6000 pounds per square inch. The accompanying table gives the safe working stresses S for different pitch-line velocities. When the value of S is known, the horsepower capacity is determined by substituting the value of S for S_s in the appropriate equations in the section on power-transmitting capacity of plastics gears starting on page 625.

Safe Working Stresses for Non-metallic Gears

Pitch-Line Velocity, Feet per Minute, V	Safe Working Stresses	Pitch-Line Velocity, Feet per Minute, V	Safe Working Stresses	Pitch-Line Velocity, Feet per Minute, V	Safe Working Stresses
600	2625	1800	1950	4000	1714
700	2500	2000	1909	4500	1691
800	2400	2200	1875	5000	1673
900	2318	2400	1846	5500	1653
1000	2250	2600	1821	6000	1645
1200	2143	2800	1800	6500	1634
1400	2063	3000	1781	7000	1622
1600	2000	3500	1743	7500	1617

Copyright 2004, Industrial Press, Inc., New York, NY

The tensile strength of the phenolic laminated materials used for gears is slightly less than that of cast iron. These materials are far softer than any metal, and the modulus of elasticity is about one-thirtieth that of steel. In other words, if the tooth load on a steel gear that causes a deformation of 0.001 inch were applied to the tooth of a similar gear made of phenolic laminated material, the tooth of the non-metallic gear would be deformed about $\frac{1}{32}$ inch. Under these conditions, several things will happen. With all gears, regardless of the theoretical duration of contact, one tooth only will carry the load until the load is sufficient to deform the tooth the amount of the error that may be present. On metal gears, when the tooth has been deformed the amount of the error, the stresses set up in the materials may approach or exceed the elastic limit of the material. Hence, for standard tooth forms and those generated from standard basic racks, it is dangerous to calculate their strength as very much greater than that which can safely be carried on a single tooth. On gears made of phenolic laminated materials, on the other hand, the teeth will be deformed the amount of this normal error without setting up any appreciable stresses in the material, so that the load is actually supported by several teeth.

All materials have their own peculiar and distinct characteristics, so that under certain specific conditions, each material has a field of its own where it is superior to any other. Such fields may overlap to some extent, and only in such overlapping fields are different materials directly competitive. For example, steel is more or less ductile, has a high tensile strength, and a high modulus of elasticity. Cast iron, on the other hand, is not ductile, has a low tensile strength, but a high compressive strength, and a low modulus of elasticity. Hence, when stiffness and high tensile strength are essential, steel is far superior to cast iron. On the other hand, when these two characteristics are unimportant, but high compressive strength and a moderate amount of elasticity are essential, cast iron is superior to steel.

Preferred Pitch for Non-metallic Gears.— The pitch of the gear or pinion should bear a reasonable relation either to the horsepower or speed or to the applied torque, as shown by the accompanying table. The upper half of this table is based upon horsepower transmitted at a given pitch-line velocity. The lower half gives the torque in pounds-feet or the torque at a 1-foot radius. This torque T for any given horsepower and speed can be obtained from the following formula:

$$T = \frac{5252 \times \text{hp}}{\text{rpm}}$$

Bore Sizes for Non-metallic Gears.— For plain phenolic laminated pinions, that is, pinions without metal end plates, a drive fit of 0.001 inch per inch of shaft diameter should be used. For shafts above 2.5 inches in diameter, the fit should be constant at 0.0025 to 0.003 inch. When metal reinforcing end plates are used, the drive fit should conform to the same standards as used for metal.

The root diameter of a pinion of phenolic laminated type should be such that the minimum distance from the edge of the keyway to the root diameter will be at least equal to the depth of tooth.

Keyway Stresses for Non-metallic Gears.— The keyway stress should not exceed 3000 pounds per square inch on a plain phenolic laminated gear or pinion. The keyway stress is calculated by the formula

$$S = \frac{33{,}000 \times \text{hp}}{V \times A}$$

where S = unit stress in pounds per square inch
hp = horsepower transmitted
V = peripheral speed of shaft in feet per minute; and
A = square inch area of keyway in pinion (length × height)

Copyright 2004, Industrial Press, Inc., New York, NY

Preferred Pitches for Non-metallic Gears

Diametral Pitch for Given Horsepower and Pitch Line Velocities			
Horsepower Transmitted	Pitch Line Velocity up to 1000 Feet per Minute	Pitch Line Velocity from 1000 to 2000 Feet per Minute	Pitch Line Velocity over 2000 Feet per Minute
¼–1	8–10	10–12	12–16
1–2	7–8	8–10	10–12
2–3	6–7	7–8	8–10
3–7½	5–6	6–7	7–8
7½–10	4–5	5–6	6–7
10–15	3–4	4–5	5–6
15–25	2½–3	3–4	4–5
25–60	2–2½	2½–3	3–4
60–100	1¾–2	2–2½	2½–3
100–150	1½–1¾	1¾–2	2–2½

Torque in Pounds-feet for Given Diametral Pitch					
Diametral Pitch	Torque in Pounds-feet		Diametral Pitch	Torque in Pounds-feet	
	Minimum	Maximum		Minimum	Maximum
16	1	2	4	50	100
12	2	4	3	100	200
10	4	8	2½	200	450
8	8	15	2	450	900
6	15	30	1½	900	1800
5	30	50	1	1800	3500

These preferred pitches are applicable both to rawhide and the phenolic laminated types of materials.

If the keyway stress formula is expressed in terms of shaft radius r and revolutions per minute, it will read

$$S = \frac{63{,}000 \times \text{hp}}{\text{rpm} \times r \times A}$$

When the design is such that the keyway stresses exceed 3000 pounds, metal reinforcing end plates may be used. Such end plates should not extend beyond the root diameter of the teeth. The distance from the outer edge of the retaining bolt to the root diameter of the teeth shall not be less than a full tooth depth. The use of drive keys should be avoided, but if required, metal end plates should be used on the pinion to take the wedging action of the key.

For phenolic laminated pinions, the face of the mating gear should be the same or slightly greater than the pinion face.

Invention of Gear Teeth.— The invention of gear teeth represents a gradual evolution from gearing of primitive form. The earliest evidence we have of an investigation of the problem of *uniform motion* from toothed gearing and the successful solution of that problem dates from the time of Olaf Roemer, the celebrated Danish astronomer, who, in the year 1674, proposed the epicycloidal form to obtain uniform motion. Evidently Robert Willis, professor at the University of Cambridge, was the first to make a practical application of the epicycloidal curve so as to provide for an interchangeable series of gears. Willis gives credit to Camus for conceiving the idea of interchangeable gears, but claims for himself its first application. The involute tooth was suggested as a theory by early scientists and mathematicians, but it remained for Willis to present it in a practical form. Perhaps the

Copyright 2004, Industrial Press, Inc., New York, NY

earliest conception of the application of this form of teeth to gears was by Philippe de Lahire, a Frenchman, who considered it, in theory, equally suitable with the epicycloidal for tooth outlines. This was about 1695 and not long after Roemer had first demonstrated the epicycloidal form. The applicability of the involute had been further elucidated by Leonard Euler, a Swiss mathematician, born at Basel, 1707, who is credited by Willis with being the first to suggest it. Willis devised the Willis odontograph for laying out involute teeth.

A pressure angle of 14½ degrees was selected for three different reasons. First, because the sine of 14½ degrees is nearly ¼, making it convenient in calculation; second, because this angle coincided closely with the pressure angle resulting from the usual construction of epicycloidal gear teeth; third, because the angle of the straight-sided involute rack is the same as the 29-degree worm thread.

Calculating Replacement-Gear Dimensions from Simple Measurements.— The following Tables 1a, 1b, and 1c, provide formulas with which to calculate the dimensions needed to produce replacement spur, bevel, and helical gears when only the number of teeth, the outside diameter, and the tooth depth of the gear to be replaced are known.

For helical gears, exact helix angles can be obtained by the following procedure.

1) Using a common protractor, measure the approximate helix angle A at the approximate pitch line.

2) Place sample or its mating gear on the arbor of a gear hobbing machine.

3) Calculate the index and lead gears differentially for the angle obtained by the measurements, and set up the machine as though a gear is to be cut.

4) Attach a dial indicator on an adjustable arm to the vertical swivel head, with the indicator plunger in a plane perpendicular to the gear axis and in contact with the tooth face. Contact may be anywhere between the top and the root of the tooth.

5) With the power shut off, engage the starting lever and traverse the indicator plunger axially by means of the handwheel.

6) If angle A is correct, the indicator plunger will not move as it traverses the face width of the gear. If it does move from 0, note the amount. Divide the amount of movement by the width of the gear to obtain the tangent of the angle by which to correct angle A, plus or minus, depending on the direction of indicator movement.

Table 1a. Formulas for Calculating Spur Gear Dimensions

Tooth Form and Pressure Angle	Diametral Pitch P	Pitch Diameter D	Circular Pitch P_c	Outside Diameter O	Addendum J	Dedendum K	Whole Tooth Depth W	Clearance $K - J$	Tooth Thickness on Pitch Circle
American Standard 14½-and 20-degree full depth	$\frac{N+2}{O}$	$\frac{N}{P}$	$\frac{3.1416}{P}$	$\frac{N+2}{P}$	$\frac{1}{P}$	$\frac{1.157}{P}$	$\frac{2.157}{P}$	$\frac{0.157}{P}$	$\frac{1.5708}{P}$
American Standard 20-degree stub	$\frac{N+1.6}{O}$	$\frac{N}{P}$	$\frac{3.1416}{P}$	$\frac{N+1.6}{P}$	$\frac{0.8}{P}$	$\frac{1}{P}$	$\frac{1.8}{P}$	$\frac{0.2}{P}$	$\frac{1.5708}{P}$
Fellows 20-degree stub	See Note[a]	$\frac{N}{P_N}$	$\frac{3.1416}{P_N}$	$\frac{N}{P_N} + \frac{2}{P_D}$	$\frac{1}{P_D}$	$\frac{1.25}{P_D}$	$\frac{2.25}{P_D}$	$\frac{0.25}{P_D}$	$\frac{1.5708}{P_N}$

[a] In the Fellows stub-tooth system, P_N = diametral pitch in numerator of stub-tooth designation and is used to determine circular pitch and number of teeth, and P_D = diametral pitch in the denominator of stub-tooth designation and is used to determine tooth depth.

N = number of teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Formulas for Calculating Dimensions of Milled Bevel Gears — 90 degree Shafts[a]

Tooth Form and Pressure Angle	Tangent of Pitch Cone Angle of Gear, tan A	Tangent of Pitch Cone Angle of Pinion, tan a	Diametral Pitch[b] of Both Gear and Pinion, P	Outside Diameter of Gear, O, or Pinion, o	Pitch-Cone Radius[b] or Cone Distance, E	Tangent of Addendum Angle[b]	Tangent of Dedendum Angle[b]	Cosine of Pitch-Cone Angle[c] of Gear, cos A
American Standard $14\frac{1}{2}°$ and 20-degree full depth	$\frac{N_G}{N_P}$	$\frac{N_P}{N_G}$	$\frac{N_G + 2\cos A}{O}$ or $\frac{N_P + 2\cos a}{o}$	$\frac{N_G + 2\cos A}{P}$ or $\frac{N_P + 2\cos a}{P}$	$\frac{D}{2\sin A}$ or $\frac{d}{2\sin a}$	$\frac{2\sin A}{N_a}$ or $\frac{2\sin a}{N_P}$	$\frac{2.314\sin A}{N_G}$ or $\frac{2.314\sin a}{N_P}$	$\frac{(P \times O) - N_G}{2}$
American Standard 20-degree stub	$\frac{N_G}{N_P}$	$\frac{N_P}{N_G}$	$\frac{N_G + 1.6\cos A}{O}$ or $\frac{N_P + 1.6\cos a}{o}$	$\frac{N_G + 1.6\cos A}{P}$ or $\frac{N_P + 1.6\cos a}{P}$	$\frac{D}{2\sin A}$ or $\frac{d}{2\sin a}$	$\frac{1.6\sin A}{N_G}$ or $\frac{1.6\sin a}{N_P}$	$\frac{2\sin A}{N_G}$ or $\frac{2\sin a}{N_P}$	$\frac{(P \times O) - N_G}{1.6}$
Fellows 20-degree stub	$\frac{N_G}{N_P}$	$\frac{N_P}{N_G}$	…	$\frac{N_G}{P_N} + \frac{2\cos A}{P_D}$ or $\frac{N_P}{P_N} + \frac{2\cos a}{P_D}$	$\frac{D}{2\sin A}$ or $\frac{d}{2\sin a}$	$\frac{2P_N\sin A}{N_G \times P_D}$ or $\frac{2P_N\sin a}{N_P \times P_D}$	$\frac{2.5P_N\sin A}{N_G \times P_D}$ or $\frac{2.5P_N\sin a}{N_P \times P_D}$	$\frac{P_D[(O \times P_N) - N_G]}{2P_N}$

[a] These formulas do not apply to Gleason System Gearing.

[b] These values are the same for both gear and pinion.

[c] The same formulas apply to the pinion, substituting N_P for N_G and o for O.

N_G = number of teeth in gear; N_P = number of teeth in pinion; O = outside diameter of gear; o = outside diameter of pinion; D = pitch diameter of gear = $N_G \div P$; d = pitch diameter of pinion = $N_P \div P$; P_c = circular pitch; J = addendum; K = dedendum; W = whole depth.

See footnote in Table 1a for meaning of P_N and P_D. The tooth thickness on the pitch circle is found by means of the formulas in the last column under spur gears.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1c. Formulas for Caluclating Dimensions of Helical Gears

Tooth Form and Pressure Angle	Normal Diametral Pitch P_N	Diametral Pitch P	Outside Diameter of Blank O	Pitch Diameter D	Cosine of Helix Angle A	Addendum	Dedendum	Whole Depth
American Standard $14\frac{1}{2}°$ and 20-degree full depth	$\frac{N + 2\cos A}{O \times \cos A}$ or $\frac{P}{\cos A}$	$P_N \cos A$ or $\frac{N + 2\cos A}{O}$	$\frac{N + 2\cos A}{P_N \cos A}$ or $\frac{N + 2\cos A}{P}$	$\frac{N}{P_N \cos A}$ or $\frac{N}{P}$	$\frac{P}{P_N}$ or $\frac{N}{O \times P_N - 2}$	$\frac{1}{P_N}$ or $\frac{\cos A}{P}$	$\frac{1.157}{P_N}$ or $\frac{1.157\cos A}{P}$	$\frac{2.157}{P_N}$ or $\frac{2.157\cos A}{P}$
American Standard 20-degree stub	$\frac{N + 1.6\cos A}{O \times \cos A}$ or $\frac{P}{\cos A}$	$P_n \cos A$ or $\frac{N + 1.6\cos A}{O}$	$\frac{N + 1.6\cos A}{P_N \cos A}$ or $\frac{N + 1.6\cos A}{P}$	$\frac{N}{P_N \cos A}$ or $\frac{N}{P}$	$\frac{P}{P_N}$ or $\frac{N}{O \times P_N - 1.6}$	$\frac{0.8}{P_N}$ or $\frac{0.8\cos A}{P}$	$\frac{1}{P_N}$ or $\frac{\cos A}{P}$	$\frac{1.8}{P_N}$ or $\frac{1.8\cos A}{P}$
Fellows 20-degree stub	…	…	$\frac{N}{(P_N)_N \cos A} + \frac{2}{(P_N)_D}$	$\frac{N}{(P_N)_N \cos A}$	$\frac{N}{(P_N)_N\left(O - \frac{2}{(P_N)_D}\right)}$	$\frac{1}{(P_N)_D}$	$\frac{1.25}{(P_N)_D}$	$\frac{2.25}{(P_N)_D}$

P_N = normal diametral pitch = normal diametral pitch of cutter or hob used to cut teeth

P = diametral pitch

O = outside diameter of blank

D = pitch diameter

A = helix angle

N = number of teeth

$(P_N)_N$ = normal diametral pitch in numerator of stub-tooth designation, which determines thickness of tooth and number of teeth

$(P_N)_D$ = normal diametral pitch in denominator of stub-tooth designation, which determines the addendum, dedendum, and whole depth

Copyright 2004, Industrial Press, Inc., New York, NY

SPLINES AND SERRATIONS

A splined shaft is one having a series of parallel keys formed integrally with the shaft and mating with corresponding grooves cut in a hub or fitting; this arrangement is in contrast to a shaft having a series of keys or feathers fitted into slots cut into the shaft. The latter construction weakens the shaft to a considerable degree because of the slots cut into it and consequently, reduces its torque-transmitting capacity.

Splined shafts are most generally used in three types of applications: 1) for coupling shafts when relatively heavy torques are to be transmitted without slippage; 2) for transmitting power to slidably-mounted or permanently-fixed gears, pulleys, and other rotating members; and 3) for attaching parts that may require removal for indexing or change in angular position.

Splines having straight-sided teeth have been used in many applications (see SAE Parallel Side Splines for Soft Broached Holes in Fittings); however, the use of splines with teeth of involute profile has steadily increased since 1) involute spline couplings have greater torque-transmitting capacity than any other type; 2) they can be produced by the same techniques and equipment as is used to cut gears; and 3) they have a self-centering action under load even when there is backlash between mating members.

Involute Splines

American National Standard Involute Splines*.— These splines or multiple keys are similar in form to internal and external involute gears. The general practice is to form the external splines either by hobbing, rolling, or on a gear shaper, and internal splines either by broaching or on a gear shaper. The internal spline is held to basic dimensions and the external spline is varied to control the fit. Involute splines have maximum strength at the base, can be accurately spaced and are self-centering, thus equalizing the bearing and stresses, and they can be measured and fitted accurately.

In American National Standard ANSI B92.1-1970 (R 1993), many features of the 1960 standard are retained; plus the addition of three tolerance classes, for a total of four. The term "involute serration," formerly applied to involute splines with 45-degree pressure angle, has been deleted and the standard now includes involute splines with 30-, 37.5-, and 45-degree pressure angles. Tables for these splines have been rearranged accordingly. The term "serration" will no longer apply to splines covered by this Standard.

The Standard has only one fit class for all side fit splines; the former Class 2 fit. Class 1 fit has been deleted because of its infrequent use. The major diameter of the flat root side fit spline has been changed and a tolerance applied to include the range of the 1950 and the 1960 standards. The interchangeability limitations with splines made to previous standards are given later in the section entitled "Interchangeability."

There have been no tolerance nor fit changes to the major diameter fit section.

The Standard recognizes the fact that proper assembly between mating splines is dependent only on the spline being within effective specifications from the tip of the tooth to the form diameter. Therefore, on side fit splines, the internal spline major diameter now is shown as a maximum dimension and the external spline minor diameter is shown as a minimum dimension. The minimum internal major diameter and the maximum external minor diameter must clear the specified form diameter and thus do not need any additional control.

The spline specification tables now include a greater number of tolerance level selections. These tolerance classes were added for greater selection to suit end product needs. The selections differ only in the tolerance as applied to space widthand tooth thickness.

* See American National Standard ANSI B92.2M-1980 (R1989), Metric Module Involute Splines; also see page 2176.

Copyright 2004, Industrial Press, Inc., New York, NY

The tolerance class used in ASA B5.15-1960 is the basis and is now designated as tolerance Class 5. The new tolerance classes are based on the following formulas:

$$\text{Tolerance Class 4} = \text{Tolerance Class 5} \times 0.71$$
$$\text{Tolerance Class 6} = \text{Tolerance Class 5} \times 1.40$$
$$\text{Tolerance Class 7} = \text{Tolerance Class 5} \times 2.00$$

All dimensions listed in this standard are for the finished part. Therefore, any compensation that must be made for operations that take place during processing, such as heat treatment, must be taken into account when selecting the tolerance level for manufacturing.

The standard has the same internal minimum effective space width and external maximum effective tooth thickness for all tolerance classes and has two types of fit. For tooth side fits, the minimum effective space width and the maximum effective tooth thickness are of equal value. This basic concept makes it possible to have interchangeable assembly between mating splines where they are made to this standard regardless of the tolerance class of the individual members. A tolerance class "mix" of mating members is thus allowed, which often is an advantage where one member is considerably less difficult to produce than its mate, and the "average" tolerance applied to the two units is such that it satisfies the design need. For instance, assigning a Class 5 tolerance to one member and Class 7 to its mate will provide an assembly tolerance in the Class 6 range. The maximum effective tooth thickness is less than the minimum effective space width for major diameter fits to allow for eccentricity variations.

In the event the fit as provided in this standard does not satisfy a particular design need and a specific amount of effective clearance or press fit is desired, the change should be made only to the external spline by a reduction or an increase in effective tooth thickness and a like change in actual tooth thickness. The minimum effective space width, in this standard, is always basic. The basic minimum effective space width should always be retained when special designs are derived from the concept of this standard.

Terms Applied to Involute Splines.— The following definitions of involute spline terms, here listed in alphabetical order, are given in the American National Standard. Some of these terms are illustrated in the diagram in Table 6.

Active Spline Length (L_a) is the length of spline that contacts the mating spline. On sliding splines, it exceeds the length of engagement.

Actual Space Width (s) is the circular width on the pitch circle of any single space considering an infinitely thin increment of axial spline length.

Actual Tooth Thickness (t) is the circular thickness on the pitch circle of any single tooth considering an infinitely thin increment of axial spline length.

Alignment Variation is the variation of the effective spline axis with respect to the reference axis (see Fig. 1c).

Base Circle is the circle from which involute spline tooth profiles are constructed.

Base Diameter (D_b) is the diameter of the base circle.

Basic Space Width is the basic space width for 30-degree pressure angle splines; half the circular pitch. The basic space width for 37.5- and 45-degree pressure angle splines, however, is greater than half the circular pitch. The teeth are proportioned so that the external tooth, at its base, has about the same thickness as the internal tooth at the form diameter. This proportioning results in greater minor diameters than those of comparable involute splines of 30-degree pressure angle.

Circular Pitch (p) is the distance along the pitch circle between corresponding points of adjacent spline teeth.

Depth of Engagement is the radial distance from the minor circle of the internal spline to the major circle of the external spline, minus corner clearance and/or chamfer depth.

Copyright 2004, Industrial Press, Inc., New York, NY

Diametral Pitch (P) is the number of spline teeth per inch of pitch diameter. The diametral pitch determines the circular pitch and the basic space width or tooth thickness. In conjunction with the number of teeth, it also determines the pitch diameter. (See also Pitch.)

Effective Clearance (c_v) is the effective space width of the internal spline minus the effective tooth thickness of the mating external spline.

Effective Space Width (S_v) of an internal spline is equal to the circular tooth thickness on the pitch circle of an imaginary perfect external spline that would fit the internal spline without looseness or interference considering engagement of the entire axial length of the spline. The minimum effective space width of the internal spline is always basic, as shown in Table 3. Fit variations may be obtained by adjusting the tooth thickness of the external spline.

Three types of involute spline variations



Fig. 1a. Lead Variation



Fig. 1b. Parallelism Variation



Fig. 1c. Alignment Variation

Effective Tooth Thickness (t_v) of an external spline is equal to the circular space width on the pitch circle of an imaginary perfect internal spline that would fit the external spline without looseness or interference, considering engagement of the entire axial length of the spline.

Effective Variation is the accumulated effect of the spline variations on the fit with the mating part.

External Spline is a spline formed on the outer surface of a cylinder.

Fillet is the concave portion of the tooth profile that joins the sides to the bottom of the space.

Fillet Root Splines are those in which a single fillet in the general form of an arc joins the sides of adjacent teeth.

Flat Root Splines are those in which fillets join the arcs of major or minor circles to the tooth sides.

Copyright 2004, Industrial Press, Inc., New York, NY

Form Circle is the circle which defines the deepest points of involute form control of the tooth profile. This circle along with the tooth tip circle (or start of chamfer circle) determines the limits of tooth profile requiring control. It is located near the major circle on the internal spline and near the minor circle on the external spline.

Form Clearance (c_F) is the radial depth of involute profile beyond the depth of engagement with the mating part. It allows for looseness between mating splines and for eccentricities between the minor circle (internal), the major circle (external), and their respective pitch circles.

Form Diameter (D_{Fe}, D_{Fi}) the diameter of the form circle.

Internal Spline is a spline formed on the inner surface of a cylinder.

Involute Spline is one having teeth with involute profiles.

Lead Variation is the variation of the direction of the spline tooth from its intended direction parallel to the reference axis, also including parallelism and alignment variations (see Fig. 1a). *Note:* Straight (nonhelical) splines have an infinite lead.

Length of Engagement (L_q) is the axial length of contact between mating splines.

Machining Tolerance (m) is the permissible variation in actual space width or actual tooth thickness.

Major Circle is the circle formed by the outermost surface of the spline. It is the outside circle (tooth tip circle) of the external spline or the root circle of the internal spline.

Major Diameter (D_o, D_{ri}) is the diameter of the major circle.

Minor Circle is the circle formed by the innermost surface of the spline. It is the root circle of the external spline or the inside circle (tooth tip circle) of the internal spline.

Minor Diameter (D_{re}, D_i) is the diameter of the minor circle.

Nominal Clearance is the actual space width of an internal spline minus the actual tooth thickness of the mating external spline. It does not define the fit between mating members, because of the effect of variations.

Out of Roundness is the variation of the spline from a true circular configuration.

Parallelism Variation is the variation of parallelism of a single spline tooth with respect to any other single spline tooth (see Fig. 1b).

Pitch (P/P_s) is a combination number of a one-to-two ratio indicating the spline proportions; the upper or first number is the diametral pitch, the lower or second number is the stub pitch and denotes, as that fractional part of an inch, the basic radial length of engagement, both above and below the pitch circle.

Pitch Circle is the reference circle from which all transverse spline tooth dimensions are constructed.

Pitch Diameter (D) is the diameter of the pitch circle.

Pitch Point is the intersection of the spline tooth profile with the pitch circle.

Pressure Angle (ϕ) is the angle between a line tangent to an involute and a radial line through the point of tangency. Unless otherwise specified, it is the standard pressure angle.

Profile Variation is any variation from the specified tooth profile normal to the flank.

Spline is a machine element consisting of integral keys (spline teeth) or keyways (spaces) equally spaced around a circle or portion thereof.

Standard (Main) Pressure Angle (ϕ_D) is the pressure angle at the specified pitch diameter.

Stub Pitch (P_s) is a number used to denote the radial distance from the pitch circle to the major circle of the external spline and from the pitch circle to the minor circleof the internal spline. The stub pitch for splines in this standard is twice the diametral pitch.

Total Index Variation is the greatest difference in any two teeth (adjacent or otherwise) between the actual and the perfect spacing of the tooth profiles.

Total Tolerance ($m + \lambda$) is the machining tolerance plus the variation allowance.

Variation Allowance (λ) is the permissible effective variation.

Copyright 2004, Industrial Press, Inc., New York, NY

Tooth Proportions.— There are 17 pitches: 2.5/5, 3/6, 4/8,5/10, 6/12, 8/16, 10/20, 12/24, 16/32, 20/40, 24/48, 32/64, 40/80, 48/96, 64/128, 80/160, and 128/256. The numerator in this fractional designation is known as the diametral pitch and controls the pitch diameter; the denominator, which is always double the numerator, is known as the stub pitch and controls the tooth depth. For convenience in calculation, only the numerator is used in the formulas given and is designated as P. Diametral pitch, as in gears, means the number of teeth per inch of pitch diameter.

Table 1 shows the symbols and Table 2 the formulas for basic tooth dimensions of involute spline teeth of various pitches. Basic dimensions are given in Table 3.

Table 1. American National Standard Involute Spline Symbols
ANSI B92.1-1970, R1993

c_v	effective clearance	M_i	measurement between pins, internal spline
c_F	form clearance	N	number of teeth
D	pitch diameter	P	diametral pitch
D_b	base diameter	P_s	stub pitch
D_{ci}	pin contact diameter, internal spline	p	circular pitch
D_{ce}	pin contact diameter, external spline	r_f	fillet radius
D_{Fe}	form diameter, external spline	s	actual space width, circular
D_{Fi}	form diameter, internal spline	s_v	effective space width, circular
D_i	minor diameter, internal spline	s_c	allowable compressive stress, psi
D_o	major diameter, external spline	s_s	allowable shear stress, psi
D_{re}	minor diameter, external spline (root)	t	actual tooth thickness, circular
D_{ri}	major diameter, internal spline (root)	t_v	effective tooth thickness, circular
d_e	diameter of measuring pin for external spline	λ	variation allowance
d_i	diameter of measuring pin for internal spline	$\in$	involute roll angle
K_e	change factor for external spline	ϕ	pressure angle
K_i	change factor for internal spline	ϕ_D	standard pressure angle
L	spline length	ϕ_{ci}	pressure angle at pin contact diameter, internal spline
L_a	active spline length	ϕ_{ce}	pressure angle at pin contact diameter, external spline
L_g	length of engagement	ϕ_i	pressure angle at pin center, internal spline
m	machining tolerance	ϕ_e	pressure angle at pin center, external spline
M_e	measurement over pins, external spline	ϕ_F	pressure angle at form diameter

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Formulas for Involute Spline Basic Dimensions *ANSI B92.1-1970, R1993*

Term	Symbol	30 deg ϕ_D			37.5 deg ϕ_D	45 deg ϕ_D
		Flat Root Side Fit	Flat Root Major Dia Fit	Fillet Root Side Fit	Fillet Root Side Fit	Fillet Root Side Fit
		2.5/5 – 32/64 Pitch	3/6 – 16/32 Pitch	2.5/5 – 48/96 Pitch	2.5/5 – 48/96 Pitch	10/20 – 128/256 Pitch
Stub Pitch	P_s	$2P$	$2P$	$2P$	$2P$	$2P$
Pitch Diameter	D	N/P	N/P	N/P	N/P	N/P
Base Diameter	D_b	$D\cos\phi_D$	$D\cos\phi_D$	$D\cos\phi_D$	$D\cos\phi_D$	$D\cos\phi_D$
Circular Pitch	p	π/P	π/P	π/P	π/P	π/P
Minimum Effective Space Width	s_v	$\pi/(2P)$	$\pi/(2P)$	$\pi/(2P)$	$(0.5\pi + 0.1)/P$	$(0.5\pi + 0.2)/P$
Major Diameter, Internal	D_{ri}	$(N + 1.35)/P$	$(N + 1)/P$	$(N + 1.8)/P$	$(N + 1.6)/P$	$(N + 1.4)/P$
Major Diameter, External	D_o	$(N + 1)/P$	$(N + 1)/P$	$(N + 1)/P$	$(N + 1)/P$	$(N + 1)/P$
Minor Diameter, Internal	D_i	$(N - 1)/P$	$(N - 1)/P$	$(N - 1)/P$	$(N - 0.8)/P$	$(N - 0.6)/P$
Minor Dia. Ext. 2.5/5 thru 12/24 pitch	D_{re}	$(N - 1.35)/P$		$(N - 1.8)/P$	$(N - 1.3)/P$	…
Minor Dia. Ext. 16/32 pitch and finer	D_{re}			$(N - 2)/P$		
Minor Dia. Ext. 10/20 pitch and finer	D_{re}			…		$(N - 1)/P$
Form Diameter, Internal	D_{Fi}	$(N + 1)/P + 2cF$	$(N + 0.8)/P - 0.004 + 2cF$	$(N + 1)/P + 2cF$	$(N + 1)/P + 2cF$	$(N + 1)/P + 2cF$
Form Diameter, External	D_{Fe}	$(N - 1)/P - 2cF$	$(N - 1)/P - 2cF$	$(N - 1)/P - 2cF$	$(N - 0.8)/P - 2cF$	$(N - 0.6)/P - 2cF$
Form Clearance (Radial)	c_F	0.001 D, with max of 0.010, min of 0.002				

$\pi = 3.1415927$

Note: All spline specification table dimensions in the standard are derived from these basic formulas by application of tolerances.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Basic Dimensions for Involute Splines *ANSI B92.1-1970, R1993*

Pitch, P/P_s	Circular Pitch, p	Min Effective Space Width (BASIC), S_v min			Pitch, P/P_s	Circular Pitch, p	Min Effective Space Width (BASIC), S_v min		
		30 deg ϕ	37.5 deg ϕ	45 deg ϕ			30 deg ϕ	37.5 deg ϕ	45 deg ϕ
2.5/5	1.2566	0.6283	0.6683	…	20/40	0.1571	0.0785	0.0835	0.0885
3/6	1.0472	0.5236	0.5569	…	24/48	0.1309	0.0654	0.0696	0.0738
4/8	0.7854	0.3927	0.4177	…	32/64	0.0982	0.0491	0.0522	0.0553
5/10	0.6283	0.3142	0.3342	…	40/80	0.0785	0.0393	0.0418	0.0443
6/12	0.5236	0.2618	0.2785	…	48/96	0.0654	0.0327	0.0348	0.0369
8/16	0.3927	0.1963	0.2088	…	64/128	0.0491	…	…	0.0277
10/20	0.3142	0.1571	0.1671	0.1771	80/160	0.0393	…	…	0.0221
12/24	0.2618	0.1309	0.1392	0.1476	128/256	0.0246	…	…	0.0138
16/32	0.1963	0.0982	0.1044	0.1107	…	…	…	…	…

Tooth Numbers.— The American National Standard covers involute splines having tooth numbers ranging from 6 to 60 with a 30- or 37.5-degree pressure angle and from 6 to 100 with a 45-degree pressure angle. In selecting the number of teeth for a given spline application, it is well to keep in mind that there are no advantages to be gained by using odd numbers of teeth and that the diameters of splines with odd tooth numbers, particularly internal splines, are troublesome to measure with pins since no two tooth spaces are diametrically opposite each other.

Types and Classes of Involute Spline Fits.— Two types of fits are covered by the American National Standard for involute splines, the side fit, and the major diameter fit. Dimensional data for flat root side fit, flat root major diameter fit, and fillet root side fit splines are tabulated in this standard for 30-degree pressure angle splines; but for only the fillet root side fit for 37.5- and 45-degree pressure angle splines.

Side Fit: In the side fit, the mating members contact only on the sides of the teeth; major and minor diameters are clearance dimensions. The tooth sides act as drivers and centralize the mating splines.

Major Diameter Fit: Mating parts for this fit contact at the major diameter for centralizing. The sides of the teeth act as drivers. The minor diameters are clearance dimensions.

The major diameter fit provides a minimum effective clearance that will allow for contact and location at the major diameter with a minimum amount of location or centralizing effect by the sides of the teeth. The major diameter fit has only one space width and tooth thickness tolerance which is the same as side fit Class 5.

A fillet root may be specified for an external spline, even though it is otherwise designed to the flat root side fit or major diameter fit standard. An internal spline with a fillet root can be used only for the side fit.

Classes of Tolerances.— This standard includes four classes of tolerances on space width and tooth thickness. This has been done to provide a range of tolerances for selection to suit a design need. The classes are variations of the former single tolerance which is now Class 5 and are based on the formulas shown in the footnote of Table 4. All tolerance classes have the same minimum effective space width and maximum effective tooth thickness limits so that a mix of classes between mating parts is possible.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Maximum Tolerances for Space Width and Tooth Thickness of Tolerance Class 5 Splines *ANSI B92.1-1970, R1993*
(Values shown in ten thousandths; 20 = 0.0020)

No. of Teeth	Pitch, P/P_s							
	2.5/5 and 3/6	4/8 and 5/10	6/12 and 8/16	10/20 and 12/24	16/32 and 20/40	24/48 thru 48/96	64/128 and 80/160	128/256
N	Machining Tolerance, *m*							
10	15.8	14.5	12.5	12.0	11.7	11.7	9.6	9.5
20	17.6	16.0	14.0	13.0	12.4	12.4	10.2	10.0
30	18.4	17.5	15.5	14.0	13.1	13.1	10.8	10.5
40	21.8	19.0	17.0	15.0	13.8	13.8	11.4	—
50	23.0	20.5	18.5	16.0	14.5	14.5	—	—
60	24.8	22.0	20.0	17.0	15.2	15.2	—	—
70	—	—	—	18.0	15.9	15.9	—	—
80	—	—	—	19.0	16.6	16.6	—	—
90	—	—	—	20.0	17.3	17.3	—	—
100	—	—	—	21.0	18.0	18.0	—	—
N	Variation Allowance, λ							
10	23.5	20.3	17.0	15.7	14.2	12.2	11.0	9.8
20	27.0	22.6	19.0	17.4	15.4	13.4	12.0	10.6
30	30.5	24.9	21.0	19.1	16.6	14.6	13.0	11.4
40	34.0	27.2	23.0	21.6	17.8	15.8	14.0	—
50	37.5	29.5	25.0	22.5	19.0	17.0	—	—
60	41.0	31.8	27.0	24.2	20.2	18.2	—	—
70	—	—	—	25.9	21.4	19.4	—	—
80	—	—	—	27.6	22.6	20.6	—	—
90	—	—	—	29.3	23.8	21.8	—	—
100	—	—	—	31.0	25.0	23.0	—	—
N	Total Index Variation							
10	20	17	15	15	14	12	11	10
20	24	20	18	17	15	13	12	11
30	28	22	20	19	16	15	14	13
40	32	25	22	20	18	16	15	—
50	36	27	25	22	19	17	—	—
60	40	30	27	24	20	18	—	—
70	—	—	—	26	21	20	—	—
80	—	—	—	28	22	21	—	—
90	—	—	—	29	24	23	—	—
100	—	—	—	31	25	24	—	—
N	Profile Variation							
All	+7 −10	+6 −8	+5 −7	+4 −6	+3 −5	+2 −4	+2 −4	+2 −4

Lead Variation												
L_g, in.	0.3	0.5	1	2	3	4	5	6	7	8	9	10
Variation	2	3	4	5	6	7	8	9	10	11	12	13

For other tolerance classes: Class 4 = 0.71 × Tabulated value
Class 5 = As tabulated in table
Class 6 = 1.40 × Tabulated value
Class 7 = 2.00 × Tabulated value

Copyright 2004, Industrial Press, Inc., New York, NY

Fillets and Chamfers.— Spline teeth may have either a flat root or a rounded fillet root.

Flat Root Splines: are suitable for most applications. The fillet that joins the sides to the bottom of the tooth space, if generated, has a varying radius of curvature. Specification of this fillet is usually not required. It is controlled by the form diameter, which is the diameter at the deepest point of the desired true involute form (sometimes designated as TIF).

When flat root splines are used for heavily loaded couplings that are not suitable for fillet root spline application, it may be desirable to minimize the stress concentration in the flat root type by specifying an approximate radius for the fillet.

Because internal splines are stronger than external splines due to their broad bases and high pressure angles at the major diameter, broaches for flat root internal splines are normally made with the involute profile extending to the major diameter.

Fillet Root Splines: are recommended for heavy loads because the larger fillets provided reduce the stress concentrations. The curvature along any generated fillet varies and cannot be specified by a radius of any given value.

External splines may be produced by generating with a pinion-type shaper cutter or with a hob, or by cutting with no generating motion using a tool formed to the contour of a tooth space. External splines are also made by cold forming and are usually of the fillet root design. Internal splines are usually produced by broaching, by form cutting, or by generating with a shaper cutter. Even when full-tip radius tools are used, each of these cutting methods produces a fillet contour with individual characteristics. Generated spline fillets are curves related to the prolate epicycloid for external splines and the prolate hypocycloid for internal splines. These fillets have a minimum radius of curvature at the point where the fillet is tangent to the external spline minor diameter circle or the internal spline major diameter circle and a rapidly increasing radius of curvature up to the point where the fillet comes tangent to the involute profile.

Chamfers and Corner Clearance: In major diameter fits, it is always necessary to provide corner clearance at the major diameter of the spline coupling. This clearance is usually effected by providing a chamfer on the top corners of the external member. This method may not be possible or feasible because of the following:

a) If the external member is roll formed by plastic deformation, a chamfer cannot be provided by the process.

b) A semitopping cutter may not be available.

c) When cutting external splines with small numbers of teeth, a semitopping cutter may reduce the width of the top land to a prohibitive point.

In such conditions, the corner clearance can be provided on the internal spline, as shown in Fig. 2.

When this option is used, the form diameter may fall in the protuberance area.



Fig. 2. Internal corner clearance.

Copyright 2004, Industrial Press, Inc., New York, NY

Spline Variations.— The maximum allowable variations for involute splines are listed in Table 4.

Profile Variation: The reference profile, from which variations occur, passes through the point used to determine the actual space width or tooth thickness. This is either the pitch point or the contact point of the standard measuring pins.

Profile variation is positive in the direction of the space and negative in the direction of the tooth. Profile variations may occur at any point on the profile for establishing effective fits and are shown in Table 4.

Lead Variations: The lead tolerance for the total spline length applies also to any portion thereof unless otherwise specified.

Out of Roundness: This condition may appear merely as a result of index and profile variations given in Table 4 and requires no further allowance. However, heat treatment and deflection of thin sections may cause out of roundness, which increases index and profile variations. Tolerances for such conditions depend on many variables and are therefore not tabulated. Additional tooth and/or space width tolerance must allow for such conditions.

Eccentricity: Eccentricity of major and minor diameters in relation to the effective diameter of side fit splines should not cause contact beyond the form diameters of the mating splines, even under conditions of maximum effective clearance. This standard does not establish specific tolerances.

Eccentricity of major diameters in relation to the effective diameters of major diameter fit splines should be absorbed within the maximum material limits established by the tolerances on major diameter and effective space width or effective tooth thickness.

If the alignment of mating splines is affected by eccentricity of locating surfaces relative to each other and/or the splines, it may be necessary to decrease the effective and actual tooth thickness of the external splines in order to maintain the desired fit condition. This standard does not include allowances for eccentric location.

Effect of Spline Variations.— Spline variations can be classified as index variations, profile variations, or lead variations.

Index Variations: These variations cause the clearance to vary from one set of mating tooth sides to another. Because the fit depends on the areas with minimum clearance, index variations reduce the effective clearance.

Profile Variations: Positive profile variations affect the fit by reducing effective clearance. Negative profile variations do not affect the fit but reduce the contact area.

Lead Variations: These variations will cause clearance variations and therefore reduce the effective clearance.

Variation Allowance: The effect of individual spline variations on the fit (effective variation) is less than their total, because areas of more than minimum clearance can be altered without changing the fit. The variation allowance is 60 percent of the sum of twice the positive profile variation, the total index variation and the lead variation for the length of engagement. The variation allowances in Table 4 are based on a lead variation for an assumed length of engagement equal to one-half the pitch diameter. Adjustment may be required for a greater length of engagement.

Effective and Actual Dimensions.— Although each space of an internal spline may have the same width as each tooth of a perfect mating external spline, the two may not fit because of variations of index and profile in the internal spline. To allow the perfect external spline to fit in any position, all spaces of the internal spline must then be widened by the amount of interference. The resulting width of these tooth spaces is the *actual* space width of the internal spline. The *effective* space width is the tooth thickness of the perfect mating external spline. The same reasoning applied to an external spline that has variations of index and profile when mated with a perfect internal spline leads to the concept of effective

Copyright 2004, Industrial Press, Inc., New York, NY

tooth thickness, which exceeds the actual tooth thickness by the amount of the effective variation.

The effective space width of the internal spline minus the effective tooth thickness of the external spline is the effective clearance and defines the fit of the mating parts. (This statement is strictly true only if high points of mating parts come into contact.) Positive effective clearance represents looseness or backlash. Negative effective clearance represents tightness or interference.

Space Width and Tooth Thickness Limits.— The variation of actual space width and actual tooth thickness within the machining tolerance causes corresponding variations of effective dimensions, so that there are four limit dimensions for each component part.

These variations are shown diagrammatically in Table 5.

Table 5. Specification Guide for Space Width and Tooth Thickness
ANSI B92.1-1970, R1993



The minimum effective space width is always basic. The maximum effective tooth thickness is the same as the minimum effective space width except for the major diameter fit. The major diameter fit maximum effective tooth thickness is less than the minimum effective space width by an amount that allows for eccentricity between the effective spline and the major diameter. The permissible variation of the effective clearance is divided between the internal and external splines to arrive at the maximum effective space width and the minimum effective tooth thickness. Limits for the actual space width and actual tooth thickness are constructed from suitable variation allowances.

Use of Effective and Actual Dimensions.— Each of the four dimensions for space width and tooth thickness shown in Table 5 has a definite function.

Minimum Effective Space Width and Maximum Effective Tooth Thickness: These dimensions control the minimum effective clearance, and must always be specified.

Minimum Actual Space Width and Maximum Actual Tooth Thickness: These dimensions cannot be used for acceptance or rejection of parts. If the actual space width is less than the minimum without causing the effective space width to be undersized, or if the actual tooth thickness is more than the maximum without causing the effective tooth thickness to be oversized, the effective variation is less than anticipated; such parts are desirable and not defective. The specification of these dimensions as processing reference dimensions is optional. They are also used to analyze undersize effective space width or oversize effective tooth thickness conditions to determine whether or not these conditions are caused by excessive effective variation.

Copyright 2004, Industrial Press, Inc., New York, NY

Maximum Actual Space Width and Minimum Actual Tooth Thickness: These dimensions control machining tolerance and limit the effective variation. The spread between these dimensions, reduced by the effective variation of the internal and external spline, is the maximum effective clearance. Where the effective variation obtained in machining is appreciably less than the variation allowance, these dimensions must be adjusted in order to maintain the desired fit.

Maximum Effective Space Width and Minimum Effective Tooth Thickness: These dimensions define the maximum effective clearance but they do not limit the effective variation. They may be used, in addition to the maximum actual space width and minimum actual tooth thickness, to prevent the increase of maximum effective clearance due to reduction of effective variations. The notation "inspection optional" may be added where maximum effective clearance is an assembly requirement, but does not need absolute control. It will indicate, without necessarily adding inspection time and equipment, that the actual space width of the internal spline must be held below the maximum, or the actual tooth thickness of the external spline above the minimum, if machining methods result in less than the allowable variations. Where effective variation needs no control or is controlled by laboratory inspection, these limits may be substituted for maximum actual space width and minimum actual tooth thickness.

Combinations of Involute Spline Types.— Flat root side fit internal splines may be used with fillet root external splines where the larger radius is desired on the external spline for control of stress concentrations. This combination of fits may also be permitted as a design option by specifying for the minimum root diameter of the external, the value of the minimum root diameter of the fillet root external spline and noting this as "optional root."

A design option may also be permitted to provide either flat root internal or fillet root internal by specifying for the maximum major diameter, the value of the maximum major diameter of the fillet root internal spline and noting this as "optional root."

Interchangeability.— Splines made to this standard may interchange with splines made to older standards. Exceptions are listed below.

External Splines: These external splines will mate with older internal splines as follows:

Year	Major Dia. Fit	Flat Root Side Fit	Fillet Root Side Fit
1946	Yes	No (A)[a]	No (A)
1950[b]	Yes (B)	Yes (B)	Yes (C)
1950[c]	Yes (B)	No (A)	Yes (C)
1957 SAE	Yes	No (A)	Yes (C)
1960	Yes	No (A)	Yes (C)

[a] For exceptions A, B, C, see the paragraph on *Exceptions* that follows.
[b] Full dedendum.
[c] Short dedendum.

Internal Splines: These will mate with older external splines as follows:

Year	Major Dia. Fit	Flat Root Side Fit	Fillet Root Side Fit
1946	No (D)[a]	No (E)	No (D)
1950	Yes (F)	Yes	Yes (C)
1957 SAE	Yes (G)	Yes	Yes
1960	Yes (G)	Yes	Yes

[a] For exceptions C, D, E, F, G, see the paragraph on *Exceptions* that follows.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Spline Terms, Symbols, and Drawing Data, 30-Degree Pressure Angle, Flat Root Side Fit *ANSI B92.1-1970, R1993*



The fit shown is used in restricted areas (as with tubular parts with wall thickness too small to permit use of fillet roots, and to allow hobbing closer to shoulders, etc.) and for economy (when hobbing, shaping, etc., and using shorter broaches for the internal member).

Press fits are not tabulated because their design depends on the degree of tightness desired and must allow for such factors as the shape of the blank, wall thickness, materila, hardness, thermal expansion, etc. Close tolerances or selective size grouping may be required to limit fit variations.

Drawing Data

Internal Involute Spline Data		External Involute Spline Data	
Flat Root Side Fit		Flat Root Side Fit	
Number of Teeth	xx	Number of Teeth	xx
Pitch	xx/xx	Pitch	xx/xx
Pressure Angle	30°	Pressure Angle	30°
Base Diameter	x.xxxxxx Ref	Base Diameter	x.xxxxxx Ref
Pitch Diameter	x.xxxxxx Ref	Pitch Diameter	x.xxxxxx Ref
Major Diameter	x.xxx max	Major Diameter	x.xxx/x.xxx
Form Diameter	x.xxx	Form Diameter	x.xxx
Minor Diameter	x.xxx/x.xxx	Minor Diameter	x.xxx min
Circular Space Width		Circular Tooth Thickness	
Max Actual	x.xxxx	Max Effective	x.xxxx
Min Effective	x.xxxx	Min Actual	x.xxxx
The following information may be added as required:		The following information may be added as required:	
Max Measurement Between Pins	x.xxx Ref	Min Measurement Over Pins	x.xxxx Ref
Pin Diameter	x.xxxx	Pin Diameter	x.xxxx

The above drawing data are required for the spline specifications. The standard system is shown; for alternate systems, see Table 5. Number of x's indicates number of decimal places normally used.

Copyright 2004, Industrial Press, Inc., New York, NY

Exceptions:

a) The external major diameter, unless chamfered or reduced, may interfere with the internal form diameter on flat root side fit splines. Internal splines made to the 1957 and 1960 standards had the same dimensions as shown for the major diameter fit splines in this standard.

b) For 15 teeth or less, the minor diameter of the internal spline, unless chamfered, will interfere with the form diameter of the external spline.

c) For 9 teeth or less, the minor diameter of the internal spline, unless chamfered, will interfere with form diameter of the external spline.

d) The internal minor diameter, unless chamfered, will interfere with the external form diameter.

e) The internal minor diameter, unless chamfered, will interfere with the external form diameter.

f) For 10 teeth or less, the minimum chamfer on the major diameter of the external spline may not clear the internal form diameter.

g) Depending upon the pitch of the spline, the minimum chamfer on the major diameter may not clear the internal form diameter.

Drawing Data.— It is important that uniform specifications be used to show complete information on detail drawings of splines. Much misunderstanding will be avoided by following the suggested arrangement of dimensions and data as given in Table 6. The number of x's indicates the number of decimal places normally used. With this tabulated type of spline specifications, it is usually not necessary to show a graphic illustration of the spline teeth.

Spline Data and Reference Dimensions.— Spline data are used for engineering and manufacturing purposes. Pitch and pressure angle are not subject to individual inspection.

As used in this standard, *reference* is an added notation or modifier to a dimension, specification, or note when that dimension, specification, or note is:

1) Repeated for drawing clarification.

2) Needed to define a nonfeature datum or basis from which a form or feature is generated.

3) Needed to define a nonfeature dimension from which other specifications or dimensions are developed.

4) Needed to define a nonfeature dimension at which toleranced sizes of a feature are specified.

5) Needed to define a nonfeature dimension from which control tolerances or sizes are developed or added as useful information.

Any dimension, specification, or note that is noted "REF" should not be used as a criterion for part acceptance or rejection.

Estimating Key and Spline Sizes and Lengths.— Fig. 3 may be used to estimate the size of American Standard involute splines required to transmit a given torque. It also may be used to find the outside diameter of shafts used with single keys. After the size of the shaft is found, the proportions of the key can be determined from Table 1 on page 2363.

Curve A is for flexible splines with teeth hardened to Rockwell C 55–65. For these splines, lengths are generally made equal to or somewhat greater than the pitch diameter for diameters below 1¼ inches; on larger diameters, the length is generally one-third to two-thirds the pitch diameter. Curve A also applies for a single key used as a fixed coupling, the length of the key being one to one and one-quarter times the shaft diameter. The stress in the shaft, neglecting stress concentration at the keyway, is about 7500 pounds per square inch. See also *Effect of Keyways on Shaft Strength* starting on page 305.

Curve B represents high-capacity single keys used as fixed couplings for stresses of 9500 pounds per square inch, neglecting stress concentration. Key-length is one to one and one-quarter times shaft diameter and both shaft and key are of moderately hard heat-treated

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Chart for Estimating Involute Spline Size Based on Diameter-Torque Relationships

steel. This type of connection is commonly used to key commercial flexible couplings to motor or generator shafts.

Curve C is for multiple-key fixed splines with lengths of three-quarters to one and one-quarter times pitch diameter and shaft hardness of 200–300 BHN.

Curve D is for high-capacity splines with lengths one-half to one times the pitch diameter. Hardnesses up to Rockwell C 58 are common and in aircraft applications the shaft is generally hollow to reduce weight.

Curve E represents a solid shaft with 65,000 pounds per square inch shear stress. For hollow shafts with inside diameter equal to three-quarters of the outside diameter the shear stress would be 95,000 pounds per square inch.

Length of Splines: Fixed splines with lengths of one-third the pitch diameter will have the same shear strength as the shaft, assuming uniform loading of the teeth; however, errors in spacing of teeth result in only half the teeth being fully loaded. Therefore, for balanced strength of teeth and shaft the length should be two-thirds the pitch diameter. If weight is not important, however, this may be increased to equal the pitch diameter. In the case of flexible splines, long lengths do not contribute to load carrying capacity when there is misalignment to be accommodated. Maximum effective length for flexible splines may be approximated from Fig. 4.

Formulas for Torque Capacity of Involute Splines.— The formulas for torque capacity of 30-degree involute splines given in the following paragraphs are derived largely from an article "When Splines Need Stress Control" by D. W. Dudley, *Product Engineering*, Dec. 23, 1957.

In the formulas that follow the symbols used are as defined on page 2160 with the following additions: D_h = inside diameter of hollow shaft, inches; K_a = application factor from Table 7; K_m = load distribution factor from Table 8; K_f = fatigue life factor from Table 9; K_w

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Maximum Effective Length for Fixed and Flexible Splines

= wear life factor from Table 10; L_e = maximum effective length from Fig. 4, to be used in stress formulas even though the actual length may be greater; T = transmitted torque, pound-inches. For fixed splines without helix modification, the effective length L_e should never exceed $5000\ D^{3.5} \div T$.

Table 7. Spline Application Factors, K_a

Power Source	Type of Load			
	Uniform (Generator, Fan)	Light Shock (Oscillating Pumps, etc.)	Intermittent Shock (Actuating Pumps, etc.)	Heavy Shock (Punches, Shears, etc.)
	Application Factor, K_a			
Uniform (Turbine, Motor)	1.0	1.2	1.5	1.8
Light Shock (Hydraulic Motor)	1.2	1.3	1.8	2.1
Medium Shock (Internal Combustion, Engine)	2.0	2.2	2.4	2.8

Table 8. Load Distribution Factors, K_m, for Misalignment of Flexible Splines

Misalignment, inches per inch	Load Distribution Factor, K_m[a]			
	½-in. Face Width	1-in. Face Width	2-in. Face Width	4-in. Face Width
0.001	1	1	1	1 ½
0.002	1	1	1 ½	2
0.004	1	1 ½	2	2 ½
0.008	1 ½	2	2 ½	3

[a] For fixed splines, K_m=1.

For fixed splines, $K_m = 1$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Fatigue-Life Factors, K_f, for Splines

No. of Torque Cycles[a]	Fatigue-Life Factor, K_f	
	Unidirectional	Fully-reversed
1,000	1.8	1.8
10,000	1.0	1.0
100,000	0.5	0.4
1,000,000	0.4	0.3
10,000,000	0.3	0.2

[a] A torque cycle consists of one start and one stop, not the number of revolutions.

Table 10. Wear Life Factors, K_w, for Flexible Splines

Number of Revolutions of Spline	Life Factor, K_w	Number of Revolutions of Spline	Life Factor, K_w
10,000	4.0	100,000,000	1.0
100,000	2.8	1,000,000,000	0.7
1,000,000	2.0	10,000,000,000	0.5
10,000,000	1.4	…	…

Wear life factors, unlike fatigue life factors given in Table 9, are based on the total number of revolutions of the spline, since each revolution of a flexible spline results in a complete cycle of rocking motion which contributes to spline wear.

Definitions: A *fixed* spline is one which is either shrink fitted or loosely fitted but piloted with rings at each end to prevent rocking of the spline which results in small axial movements that cause wear. A *flexible* spline permits some rocking motion such as occurs when the shafts are not perfectly aligned. This flexing or rocking motion causes axial movement and consequently wear of the teeth. Straight-toothed flexible splines can accommodate only small angular misalignments (less than 1 deg.) before wear becomes a serious problem. For greater amounts of misalignment (up to about 5 deg.), crowned splines are preferable to reduce wear and end-loading of the teeth.

Shear Stress Under Roots of External Teeth: For a transmitted torque T, the torsional shear stress induced in the shaft under the root diameter of an external spline is:

$$S_s = \frac{16TK_a}{\pi D_{re}^3 K_f} \quad \text{for a solid shaft} \tag{1}$$

$$S_s = \frac{16TD_{re}K_a}{\pi(D_{re}^4 - D_h^4)K_f} \quad \text{for a hollow shaft} \tag{2}$$

The computed stress should not exceed the values in Table 11.

Table 11. Allowable Shear, Compressive, and Tensile Stresses for Splines

Material	Hardness		Max. Allowable Stress			
			Shear Stress,	Compressive Stress, psi		Tensile Stress,
	Brinell	Rockwell C	psi	Straight	Crowned	psi
Steel	160–200	—	20,000	1,500	6,000	22,000
	230–260	—	30,000	2,000	8,000	32,000
	302–351	33–38	40,000	3,000	12,000	45,000
Surface-hardened Steel	—	48–53	40,000	4,000	16,000	45,000
Case-hardened Steel	—	58–63	50,000	5,000	20,000	55,000
Through-hardened Steel (Aircraft Quality)	—	42–46	45,000	—	—	50,000

Copyright 2004, Industrial Press, Inc., New York, NY

Shear Stress at the Pitch Diameter of Teeth: The shear stress at the pitch line of the teeth for a transmitted torque T is:

$$S_s = \frac{4TK_aK_m}{DNL_etK_f} \tag{3}$$

The factor of 4 in (3) assumes that only half the teeth will carry the load because of spacing errors. For poor manufacturing accuracies, change the factor to 6.

The computed stress should not exceed the values in Table 11.

Compressive Stresses on Sides of Spline Teeth: Allowable compressive stresses on splines are very much lower than for gear teeth since non-uniform load distribution and misalignment result in unequal load sharing and end loading of the teeth.

$$\text{For flexible splines, } S_c = \frac{2TK_mK_a}{DNL_ehK_w} \tag{4}$$

$$\text{For fixed splines, } S_c = \frac{2TK_mK_a}{9DNL_ehK_f} \tag{5}$$

In these formulas, h is the depth of engagement of the teeth, which for flat root splines is $0.9/P$ and for fillet root splines is $1/P$, approximately.

The stresses computed from Formulas (4) and (5) should not exceed the values in Table 11.

Bursting Stresses on Splines: Internal splines may burst due to three kinds of tensile stress: 1) tensile stress due to the radial component of the transmitted load; 2) centrifugal tensile stress; and 3) tensile stress due to the tangential force at the pitch line causing bending of the teeth.

$$\text{Radial load tensile stress, } S_1 = \frac{T\tan\phi}{\pi Dt_wL} \tag{6}$$

where t_w = wall thickness of internal spline = outside diameter of spline sleeve minus spline major diameter, all divided by 2. L = full length of spline.

$$\text{Centrifugal tensile stress, } S_2 = \frac{1.656 \times (\text{rpm})^2(D_{oi}^2 + 0.212D_{ri}^2)}{1,000,000} \tag{7}$$

where D_{oi} = outside diameter of spline sleeve.

$$\text{Beam loading tensile stress, } S_3 = \frac{4T}{D^2L_eY} \tag{8}$$

In Equation (8), Y is the Lewis form factor obtained from a tooth layout. For internal splines of 30-deg. pressure angle a value of $Y = 1.5$ is a satisfactory estimate. The factor 4 in (8) assumes that only half the teeth are carrying the load.

The total tensile stress tending to burst the rim of the external member is: $S_t = [K_aK_m(S_1 + S_3) + S_2]/K_f$; and should be less than those in Table 11.

Crowned Splines for Large Misalignments.— As mentioned on page 2172, crowned splines can accommodate misalignments of up to about 5 degrees. Crowned splineshave considerably less capacity than straight splines of the same size if both are operating with precise alignment. However, when large misalignments exist, the crowned spline has greater capacity.

American Standard tooth forms may be used for crowned external members so that they may be mated with straight internal members of Standard form.

Copyright 2004, Industrial Press, Inc., New York, NY



The accompanying diagram of a crowned spline shows the radius of the crown r_1; the radius of curvature of the crowned tooth, r_2; the pitch diameter of the spline, D; the face width, F; and the relief or crown height A at the ends of the teeth. The crown height A should always be made somewhat greater than one-half the face width multiplied by the tangent of the misalignment angle. For a crown height A, the approximate radius of curvature r_2 is $F^2 \div 8A$, and $r_1 = r_2 \tan \phi$, where ϕ is the pressure angle of the spline.

For a torque T, the compressive stress on the teeth is:

$$S_c = 2290\sqrt{2T \div DNhr_2};$$

and should be less than the value in Table 11.

Fretting Damage to Splines and Other Machine Elements.— Fretting is wear that occurs when cyclic loading, such as vibration, causes two surfaces in intimate contact to undergo small oscillatory motions with respect to each other. During fretting, high points or asperities of the mating surfaces adhere to each other and small particles are pulled out, leaving minute, shallow pits and a powdery debris. In steel parts exposed to air, the metallic debris oxidizes rapidly and forms a red, rustlike powder or sludge; hence, the coined designation "fretting corrosion."

Fretting is mechanical in origin and has been observed in most materials, including those that do not oxidize, such as gold, platinum, and nonmetallics; hence, the corrosion accompanying fretting of steel parts is a secondary factor.

Fretting can occur in the operation of machinery subject to motion or vibration or both. It can destroy close fits; the debris may clog moving parts; and fatigue failure may be accelerated because stress levels to initiate fatigue in fretted parts are much lower than for undamaged material. Sites for fretting damage include interference fits; splined, bolted, keyed, pinned, and riveted joints; between wires in wire rope; flexible shafts and tubes; between leaves in leaf springs; friction clamps; small amplitude-of-oscillation bearings; and electrical contacts.

Vibration or cyclic loadings are the main causes of fretting. If these factors cannot be eliminated, greater clamping force may reduce movement but, if not effective, may actually worsen the damage. Lubrication may delay the onset of damage; hard plating or surface hardening methods may be effective, not by reducing fretting, but by increasing the fatigue strength of the material. Plating soft materials having inherent lubricity onto contacting surfaces is effective until the plating wears through.

Involute Spline Inspection Methods.— Spline gages are used for routine inspection of production parts.

Analytical inspection, which is the measurement of individual dimensions and variations, may be required:

a) To supplement inspection by gages, for example, where NOT GO composite gages are used in place of NOT GO sector gages and variations must be controlled.

b) To evaluate parts rejected by gages.

c) For prototype parts or short runs where spline gages are not used.

Copyright 2004, Industrial Press, Inc., New York, NY

d) To supplement inspection by gages where each individual variation must be restrained from assuming too great a portion of the tolerance between the minimum material actual and the maximum material effective dimensions.

Inspection with Gages.— A variety of gages is used in the inspection of involute splines.

Types of Gages: A composite spline gage has a full complement of teeth. A sector spline gage has two diametrically opposite groups of teeth. A sector plug gage with only two teeth per sector is also known as a "paddle gage." A sector ring gage with only two teeth per sector is also known as a "snap ring gage." A progressive gage is a gage consisting of two or more adjacent sections with different inspection functions. Progressive GO gages are physical combinations of GO gage members that check consecutively first one feature or one group of features, then their relationship to other features. GO and NOT GO gages may also be combined physically to form a progressive gage.



Fig. 5. Space width and tooth-thickness inspection.

GO and NOT GO Gages: GO gages are used to inspect maximum material conditions (maximum external, minimum internal dimensions). They may be used to inspect an individual dimension or the relationship between two or more functional dimensions. They control the minimum looseness or maximum interference.

NOT GO gages are used to inspect minimum material conditions (minimum external, maximum internal dimensions), thereby controlling the maximum looseness or minimum interference. Unless otherwise agreed upon, a product is acceptable only if the NOT GO gage does not enter or go on the part. A NOT GO gage can be used to inspect only one dimension. An attempt at simultaneous NOT GO inspection of more than one dimension could result in failure of such a gage to enter or go on (acceptance of part), even though all but one of the dimensions were outside product limits. In the event all dimensions are outside the limits, their relationship could be such as to allow acceptance.

Effective and Actual Dimensions: The effective space width and tooth thickness are inspected by means of an accurate mating member in the form of a composite spline gage.

The actual space width and tooth thickness are inspected with sector plug and ring gages, or by measurements with pins.

Measurements with Pins.— The actual space width of internal splines, and the actual tooth thickness of external splines, may be measured with pins. These measurements do not determine the fit between mating parts, but may be used as part of the analytic inspection of splines to evaluate the effective space width or effective tooth thickness by approximation.

Formulas for 2-Pin Measurement Between Pins: For measurement *between* pins of internal splines using the symbols given on page 2160:

1) Find involute of pressure angle at pin center:

$$\text{inv}\,\phi_i = \frac{s}{D} + \text{inv}\,\phi_d - \frac{d_i}{D_b}$$

Copyright 2004, Industrial Press, Inc., New York, NY

2) Find the value of ϕ_i in degrees, in the involute function tables beginning on page 104. Find sec ϕ_i = 1/cosine ϕ_i in the trig tables, pages 100 through 102, using interpolation to obtain higher accuracy.

3) Compute measurement, M_i, between pins:

For even numbers of teeth: $M_i = D_b \sec \phi_i - d_i$

For odd numbers of teeth: $M_i = (D_b \cos 90°/N) \sec \phi_i - d_i$

where: $d_i = 1.7280/P$ for 30° and 37.5° standard pressure angle (ϕ_D) splines

$d_i = 1.9200/P$ for 45° pressure angle splines

Example: Find the measurement between pins for *maximum* actual space width of an internal spline of 30° pressure angle, tolerance class 4, $\frac{3}{6}$ diametral pitch, and 20 teeth.

The maximum actual space width to be substituted for s in Step 1 above is obtained as follows: In Table 5, page 2166, the maximum actual space width is the sum of the minimum effective space width (second column) and $\lambda + m$ (third column). The minimum effective space width s_v from Table 2, page 2161, is $\pi/2P = \pi/(2 \times 3)$. The values of λ and m from Table 4, page 2163, are, for a class 4 fit, 3⁄6 diametral pitch, 20-tooth spline: $\lambda = 0.0027 \times 0.71 = 0.00192$; and $m = 0.00176 \times 0.71 = 0.00125$, so that $s = 0.52360 + 0.00192 + 0.00125 = 0.52677$.

Other values required for Step 1 are:

$D = N \div P = 20 \div 3 = 6.66666$

$inv\,\phi_D$ = inv 30° = 0.053751 from a calculator

$d_i = 1.7280/3 = 0.57600$

$D_b = D \cos \phi_D = 6.66666 \times 0.86603 = 5.77353$

The computation is made as follows:

1) inv $\phi_i = 0.52677/6.66666 + 0.053751 - 0.57600/5.77353 = 0.03300$

2) From a calculator, $\phi_i = 25°46.18'$ and sec $\phi_i = 1.11044$

3) $M_i = 5.77353 \times 1.11044 - 0.57600 = 5.8352$ inches

Formulas for 2-Pin Measurement Over Pins: For measurement *over* pins of external splines:

1) Find involute of pressure angle at pin center:

$$\text{inv}\,\phi_e = \frac{t}{D} + \text{inv}\,\phi_D + \frac{d_e}{D_b} - \frac{\pi}{N}$$

2) Find the value of ϕ_e and sec ϕ_e from the involute function tables beginning on page 104.

3) Compute measurement, M_e, over pins:

For even numbers of teeth: $M_e = D_b \sec \phi_e + d_e$

For odd numbers of teeth: $M_e = (D_b \cos 90°/N) \sec \phi_e + d_e$

where $d_e = 1.9200/P$ for all external splines

American National Standard Metric Module Splines.— ANSI B92.2M-1980 (R1989) is the American National Standards Institute version of the International Standards Organization involute spline standard. It is not a "soft metric" conversion of any previous, inch-based, standard,* and splines made to this hard metric version are not intended for use with components made to the B92.1 or other, previous standards. The ISO 4156 Standard from

* A "soft" conversion is one in which dimensions in inches, when multiplied by 25.4 will, after being appropriately rounded off, provide equivalent dimensions in millimeters. In a "hard" system the tools of production, such as hobs, do not bear a usable relation to the tools in another system; i.e., a 10 diametral pitch hob calculates to be equal to a 2.54 module hob in the metric module system, a hob that does not exist in the metric standard.

Copyright 2004, Industrial Press, Inc., New York, NY

which this one is derived is the result of a cooperative effort between the ANSI B92 committee and other members of the ISO/TC 14-2 involute spline committee.

Many of the features of the previous standard, ANSI B92.1-1970 (R1993), have been retained such as: 30-, 37.5-, and 45-degree pressure angles; flat root and fillet root side fits; the four tolerance classes 4, 5, 6, and 7; tables for a single class of fit; and the effective fit concept.

Among the major differences are: use of modules of from 0.25 through 10 mm in place of diametral pitch; dimensions in millimeters instead of inches; the "basic rack"; removal of the major diameter fit; and use of ISO symbols in place of those used previously. Also, provision is made for calculating three defined clearance fits.

The Standard recognizes that proper assembly between mating splines is dependent only on the spline being within effective specifications from the tip of the tooth to the form diameter. Therefore, the internal spline major diameter is shown as a maximum dimension and the external spline minor diameter is shown as a minimum dimension. The minimum internal major diameter and the maximum external minor diameter must clear the specified form diameter and thus require no additional control. All dimensions are for the finished part; any compensation that must be made for operations that take place during processing, such as heat treatment, must be considered when selecting the tolerance level for manufacturing.

The Standard provides the same internal minimum effective space width and external maximum effective tooth thickness for all tolerance classes. This basic concept makes possible interchangeable assembly between mating splines regardless of the tolerance class of the individual members, and permits a tolerance class "mix" of mating members. This arrangement is often an advantage when one member is considerably less difficult to produce than its mate, and the "average" tolerance applied to the two units is such that it satisfies the design need. For example, by specifying Class 5 tolerance for one member and Class 7 for its mate, an assembly tolerance in the Class 6 range is provided.

If a fit given in this Standard does not satisfy a particular design need, and a specific clearance or press fit is desired, the change shall be made only to the external spline by a reduction of, or an increase in, the effective tooth thickness and a like change in the actual tooth thickness. The minimum effective space width is always basic and this basic width should always be retained when special designs are derived from the concept of this Standard.

Spline Terms and Definitions: The spline terms and definitions given for American National Standard ANSI B92.1-1970 (R1993) described in the preceding section, may be used in regard to ANSI B92.2M-1980 (R1989). The 1980 Standard utilizes ISO symbols in place of those used in the 1970 Standard; these differences are shown in Table 12.

Dimensions and Tolerances: Dimensions and tolerances of splines made to the 1980 Standard may be calculated using the formulas given in Table 13. These formulas are for metric module splines in the range of from 0.25 to 10 mm metric module of side-fit design and having pressure angles of 30-, 37.5-, and 45-degrees. The standard modules in the system are: 0.25; 0.5; 0.75; 1; 1.25; 1.5; 1.75; 2; 2.5; 3; 4; 5; 6; 8; and 10. The range of from 0.5 to 10 module applies to all splines except 45-degree fillet root splines; for these, the range of from 0.25 to 2.5 module applies.

Fit Classes: Four classes of side fit splines are provided: spline fit class H/h having a minimum effective clearance, $c_v = es = 0$; classes H/f, H/e, and H/d having tooth thickness modifications, *es*, of f, e, and d, respectively, to provide progressively greater effective clearance c_v, The tooth thickness modifications h, f, e, and d in Table 14 are fundamental deviations selected from ISO R286, "ISO System of Limits and Fits." They are applied to the external spline by shifting the tooth thickness total tolerance below the basic tooth thickness by the amount of the tooth thickness modification to provide a prescribed minimum effective clearance c_v.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Comparison of Symbols Used in *ANSI B92.2M-1980 (R1989)* and Those in *ANSI B92.1-1970, R1993*

Symbol			Symbol		
B92.2M	B92.1	Meaning of Symbol	B92.2M	B92.1	Meaning of Symbol
c	…	theoretical clearance	m	…	module
c_v	c_v	effective clearance	…	P	diametral pitch
c_F	c_F	form clearance	…	P_s	stub pitch = $2P$
D	D	pitch diameter	P_b	…	base pitch
DB	D_b	base diameter	p	p	circular pitch
d_{ce}	D_{ce}	pin contact diameter, external spline	π	π	3.141592654
d_{ci}	D_{ci}	pin contact diameter, internal spline	rfe	r_f	fillet rad., ext. spline
DEE	D_o	major diam., ext. spline	rfi	r_f	fillet rad., int. spline
DEI	D_{ri}	major diam., int. spline	E_{bsc}	s_v min	basic circular space width
DFE	D_{Fe}	form diam., ext. spline	E_{max}	s	max. actual circular space width
DFI	D_{Fi}	form diam., int. spline	E_{min}	s	min. actual circular space width
DIE	D_{re}	minor diam., ext. spline	EV	s_v	effective circular space width
DII	D_i	minor diam., int. spline	S_{bsc}	t_v max	basic circular tooth thickness
DRE	d_e	pin diam., ext. spline	S_{max}	t	max. actual circular tooth thick.
DRI	d_i	pin diam., int. spline	S_{min}	t	min. actual circular tooth thick.
h_s	…	see Figs. 6a, 6b, 6c, and 6d	SV	t_v	effective circular tooth thick.
λ	λ	effective variation	α	ϕ	pressure angle
INV α	…	involute α=tan α − arc α	α_D	ϕ_D	standard pressure angle
KE	K_e	change factor, ext. spline	α_{ci}	ϕ_{ci}	press. angle at pin contact diameter, internal spline
KI	K_i	change factor, int. spline	α_{ce}	ϕ_{ce}	press. angle at pin contact diameter, external spline
g	L	spline length	α_i	ϕ_i	press. angle at pin center, internal spline
g_w	…	active spline length	α_e	ϕ_e	press. angle at pin center, external spline
$g\gamma$	…	length of engagement	α_{Fe}	ϕ_F	press. angle at form diameter, external spline
T	m	machining tolerance	α_{Fi}	ϕ_F	press. angle at form diameter, internal spline
MRE	M_e	meas. over 2 pins, ext. spline	es	…	ext. spline cir. tooth thick.modification for required fit class=c_v min (Table 14)
MRI	M_i	meas. bet. 2 pins, int. spline	h, f, e, or d	…	tooth thick, size modifiers (called fundamental deviation in ISO R286), Table 14
Z	N	number of teeth	H	…	space width size modifier (called fundamental deviation in ISO R286), Table 14

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. Formulas for Dimensions and Tolerances for All Fit Classes—Metric Module Involute Splines

Term	Symbol	Formula: 30-Degree Flat Root, 0.5 to 10 module	30-Degree Fillet Root, 0.5 to 10 module	37.5-Degree Fillet Root, 0.5 to 10 module	45-Degree Fillet Root, 0.25 to 2.5 module
Pitch Diameter	D	mZ			
Base Diameter	DB	$mZ\cos\alpha_D$			
Circular Pitch	p	πm			
Base Pitch	p_b	$\pi m\cos\alpha_D$			
Tooth Thick Mod	es	According to selected fit class, H/h, H/f, H/e, or H/d (see Table 14)			
Min Maj. Diam. Int	DEI min	$m(Z+1.5)$	$m(Z+1.8)$	$m(Z+1.4)$	$m(Z+1.2)$
Max Maj Diam. Int.	DEI max	DEI min $+(T+\lambda)/\tan\alpha_D$ (see Footnote [a])			
Form Diam, Int.	DFI	$m(Z+1)+2c_F$	$m(Z+1)+2c_F$	$m(Z+0.9)+2c_F$	$m(Z+0.8)+2c_F$
Min Minor Diam, Int	DII min	$DFE+2c_F$ (see Footnote [b])			
Max Minor Diam, Int	DII max	DII min $+(0.2m^{0.667}-0.01m^{-0.5})$ (see Footnote [c])			
Cir Space Width,					
Basic	E_{bsc}	$0.5\pi m$			
Min Effective	EV min	$0.5\pi m$			
Max Actual	E max	EV min $+(T+\lambda)$ for classes 4, 5, 6, and 7 (see Table 15 for $T+\lambda$)			
Min Actual	E min	EV min $+\lambda$ (see text on page 2180 for λ)			
Max Effective	EV max	E max $-\lambda$ (see text on page 2180 for λ)			
Max Major Diam, Ext[d]	DEE max	$m(Z+1)-es/\tan\alpha_D$	$m(Z+1)-es/\tan\alpha_D$	$m(Z+0.9)-es/\tan\alpha_D$	$m(Z+0.8)-es/\tan\alpha_D$
Min Major Diam. Ext	DEE min	DEE max $-(0.2m^{0.667}-0.01m^{-0.5})$[c]			
Form Diam, External	DFE	$2\times\sqrt{(0.5DB)^2+\left[0.5D\sin\alpha_D-\frac{h_s+((0.5es)/\tan\alpha_D)}{\sin\alpha_D}\right]^2}$			
Max Minor Diam, Ext[d]	DIE max	$m(Z-1.5)-es/\tan\alpha_D$	$m(Z-1.8)-es/\tan\alpha_D$	$m(Z-1.4)-es/\tan\alpha_D$	$m(Z-1.2)-es/\tan\alpha_D$
Min Minor Diam, Ext	DIE min	DIE max $-(T+\lambda)/\tan\alpha_D$ (see Footnote [a])			
Cir Tooth Thick,					
Basic	S_{bsc}	$0.5\pi m$			
Max Effective	SV max	$S_{bsc}-es$			
Min Actual	S min	SV max $-(T+\lambda)$ for classes 4, 5, 6, and 7 (see Table 15 for $T+\lambda$)			
Max Actual	S max	SV max $-\lambda$ (see text on page 2180 for λ)			
Min Effective	SV min	S min $+\lambda$ (see text on page 2180 for λ)			
Total Tolerance on Circular Space Width or Tooth Thickness	$(T+\lambda)$	See formulas in Table 15			
Machining Tolerance on Circular Space Width or Tooth Thickness	T	$T=(T+\lambda)$ from Table 15 $-\lambda$ from text on page 2180.			
Effective Variation Allowed on Circular Space Width or Tooth Thickness	λ	See text on page 2180.			
Form Clearance	c_F	$0.1m$			
Rack Dimension	h_s	$0.6m$ (see Fig. 6a)	$0.6m$ (see Fig. 6b)	$0.55m$ (see Fig. 6c)	$0.5m$ (see Fig. 6d)

[a] Use $(T+\lambda)$ for class 7 from Table 15

[b] For all types of fit, always use the DFE value corresponding to the H/h fit.

Copyright 2004, Industrial Press, Inc., New York, NY

[c] Values of $(0.2m^{0.667} - 0.01m^{-0.5})$ are as follows: for 10 module, 0.93; for 8 module, 0.80; for 6 module, 0.66; for 5 module, 0.58; for 4 module, 0.50; for 3 module, 0.41; for 2.5 module, 0.36; for 2 module, 0.31; for 1.75 module, 0.28; for 1.5 module, 0.25; for 1.25 module, 0.22; for 1 module, 0.19; for 0.75 module, 0.15; for 0.5 module, 0.11; and for 0.25 module, 0.06.

[d] See Table 17 for values of $es/\tan\alpha_D$.

Table 14. Tooth Thickness Modification, *es*, for Selected Spline Fit Classes

Pitch Diameter in mm, *D*	External Splines[a] Selected Fit Class d	e	f	h	Pitch Diameter in mm, *D*	External Splines[a] Selected Fit Class d	e	f	h
	Tooth Thickness Modification (Reduction) Relative to Basic Tooth Thickness at Pitch Diameter, *es*, in mm					Tooth Thickness Modification (Reduction) Relative to Basic Tooth Thickness at Pitch Diameter, *es*, in mm			
≤ 3	0.020	0.014	0.006	0	> 120 to 180	0.145	0.085	0.043	0
> 3 to 6	0.030	0.020	0.010	0	> 180 to 250	0.170	0.100	0.050	0
> 6 to 10	**0.040**	0.025	0.013	0	> 250 to 315	0.190	0.110	0.056	0
> 10 to 18	0.050	0.032	0.016	0	> 315 to 400	0.210	**0.125**	**0.062**	0
> 18 to 30	0.065	0.040	0.020	0	> 400 to 500	0.230	0.135	**0.068**	0
> 30 to 50	0.080	0.050	0.025	0	> 500 to 630	0.260	0.145	**0.076**	0
> 50 to 80	0.100	0.060	0.030	0	> 630 to 800	0.290	0.160	**0.080**	0
> 80 to 120	0.120	**0.072**	0.036	0	> 800 to 1000	0.320	**0.170**	**0.086**	0

[a] Internal splines are fit class H and have space width modification from basic space width equal to zero; thus, an H/h fit class has effective clearance $c_v = 0$.

Note: The values listed in this table are taken from ISO R286 and have been computed on the basis of the geometrical mean of the size ranges shown. Values in **boldface** type do not comply with any documented rule for rounding but are those used by ISO R286; they are used in this table to comply with established international practice.

Basic Rack Profiles: The basic rack profile for the standard pressure angle splines are shown in Figs. 6a, 6b, 6c, and 6d. The dimensions shown are for maximum material condition and for fit class H/h.

Spline Machining Tolerances and Variations.— The total tolerance $(T + \lambda)$, Table 15, is the sum of Effective Variation, λ, and a Machining Tolerance, T.

Table 15. Space Width and Tooth Thickness Total Tolerance, $(T + \lambda)$, in Millimeters

Spline Tolerance Class	Formula for Total Tolerance, $(T + \lambda)$	Spline Tolerance Class	Formula for Total Tolerance, $(T + \lambda)$	In these formulas, i* and i** are tolerance units based upon pitch diameter and tooth thickness, respectively:
				$i^* = 0.001(0.45\sqrt[3]{D} + 0.001D)$ for D ≤ 500 mm
4	$10i^* + 40i^{**}$	6	$25i^* + 100i^{**}$	$= 0.001(0.004D + 2.1)$ for D > 500 mm
5	$16i^* + 64i^{**}$	7	$40i^* + 160i^{**}$	$i^{**} = 0.001(0.45\sqrt[3]{S_{bsc}} + 0.001S_{bsc})$

Effective Variation: The effective variation, λ, is the combined effect that total index variation, positive profile variation, and tooth alignment variation has on the effective fit of mating involute splines. The effect of the individual variations is less than the sum of the allowable variations because areas of more than minimum clearance can have profile, tooth alignment, or index variations without changing the fit. It is also unlikely that these variations would occur in their maximum amounts simultaneously on the same spline. For this reason, total index variation, total profile variation, and tooth alignment variation are used to calculate the combined effect by the following formula:

$$\lambda = 0.6\sqrt{(F_p)^2 + (f_f)^2 + (F_\beta)^2} \text{ millimeters}$$

The above variation is based upon a length of engagement equal to one-half the pitch diameter of the spline; adjustment of λ may be required for a greater length of engagement. Formulas for values of F_p, f_f, and F_β used in the above formula are given in Table 16.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. Formulas for F_p, f_f, and F_β used to calculate λ

Spline Tolerance Class	Total Index Variation, in mm, F_p	Total Profile Variation, in mm, f_f	Total Lead Variation, in mm, F_β
4	$0.001(2.5\sqrt{mZ\pi/2} + 6.3)$	$0.001\,[1.6m(1 + 0.0125Z) + 10]$	$0.001(0.8\sqrt{g} + 4)$
5	$0.001(3.55\sqrt{mZ\pi/2} + 9)$	$0.001\,[2.5m(1 + 0.0125Z) + 16]$	$0.001(1.0\sqrt{g} + 5)$
6	$0.001(5\sqrt{mZ\pi/2} + 12.5)$	$0.001\,[4m(1 + 0.0125Z) + 25]$	$0.001(1.25\sqrt{g} + 6.3)$
7	$0.001(7.1\sqrt{mZ\pi/2} + 18)$	$0.001\,[6.3m(1 + 0.0125Z) + 40]$	$0.001(2\sqrt{g} + 10)$

g = length of spline in millimeters.

Table 17. Reduction, es/tan α_D, of External Spline Major and Minor Diameters Required for Selected Fit Classes

Pitch Diameter D in mm	Standard Pressure Angle, in Degrees									
	30	37.5	45	30	37.5	45	30	37.5	45	All
	Classes of Fit									
	d			e			f			h
	es/tan α_D in millimeters									
≤3	0.035	0.026	0.020	0.024	0.018	0.014	0.010	0.008	0.006	0
>3 to 6	0.052	0.039	0.030	0.035	0.026	0.020	0.017	0.013	0.010	0
> 6 to 10	0.069	0.052	0.040	0.043	0.033	0.025	0.023	0.017	0.013	0
> 10 to 18	0.087	0.065	0.050	0.055	0.042	0.032	0.028	0.021	0.016	0
> 18 to 30	0.113	0.085	0.065	0.069	0.052	0.040	0.035	0.026	0.020	0
> 30 to 50	0.139	0.104	0.080	0.087	0.065	0.050	0.043	0.033	0.025	0
> 50 to 80	0.173	0.130	0.100	0.104	0.078	0.060	0.052	0.039	0.030	0
> 80 to 120	0.208	0.156	0.120	0.125	0.094	0.072	0.062	0.047	0.036	0
> 120 to 180	0.251	0.189	0.145	0.147	0.111	0.085	0.074	0.056	0.043	0
> 180 to 250	0.294	0.222	0.170	0.173	0.130	0.100	0.087	0.065	0.050	0
> 250 to 315	0.329	0.248	0.190	0.191	0.143	0.110	0.097	0.073	0.056	0
> 315 to 400	0.364	0.274	0.210	0.217	0.163	0.125	0.107	0.081	0.062	0
> 400 to 500	0.398	0.300	0.230	0.234	0.176	0.135	0.118	0.089	0.068	0
> 500 to 630	0.450	0.339	0.260	0.251	0.189	0.145	0.132	0.099	0.076	0
> 630 to 800	0.502	0.378	0.290	0.277	0.209	0.160	0.139	0.104	0.080	0
> 800 to 1000	0.554	0.417	0.320	0.294	0.222	0.170	0.149	0.112	0.086	0

These values are used with the applicable formulas in Table 13.

Machining Tolerance: A value for machining tolerance may be obtained by subtracting the effective variation, λ, from the total tolerance ($T + \lambda$). Design requirements or specific processes used in spline manufacture may require a different amount of machining tolerance in relation to the total tolerance.



Fig. 6a. Profile of Basic Rack for 30° Flat Root Spline

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6b. Profile of Basic Rack for 30° Fillet Root Spline



Fig. 6c. Profile of Basic Rack for 37.5° Fillet Root Spline



Fig. 6d. Profile of Basic Rack for 45° Fillet Root Spline

British Standard Striaght Splines.— British Standard BS 2059:1953, "Straight-sided Splines and Serrations", was introduced because of the widespread development and use of splines and because of the increasing use of involute splines it was necessary to provide a separate standard for straight-sided splines. BS 2059 was prepared on the hole basis, the hole being the constant member, and provide for different fits to be obtained by varying the size of the splined or serrated shaft. Part 1 of the standard deals with 6 splines only, irrespective of the shaft diameter, with two depths termed shallow and deep. The splines are bottom fitting with top clearance.

The standard contains three different grades of fit, based on the principle of variations in the diameter of the shaft at the root of the splines, in conjunction with variations in the widths of the splines themselves. Fit 1 represents the condition of closest fit and is designed for minimum backlash. Fit 2 has a positive allowance and is designed for ease of assembly, and Fit 3 has a larger positive allowance for applications that can accept such clearances.

Copyright 2004, Industrial Press, Inc., New York, NY

all these splines allow for clearance on the sides of the splines (the widths), but in Fit 1, the minor diameters of the hole and the shaft may be of identical size.

Assembly of a splined shaft and hole requires consideration of the designed profile of each member, and this consideration should concentrate on the maximum diameter of the shafts and the widths of external splines, in association with the minimum diameter of the hole and the widths of the internal splineways. In other words, both internal and external splines are in the maximum metal condition. The accuracy of spacing of the splines will affect the quality of the resultant fit. If angular positioning is inaccurate, or the splines are not parallel with the axis, there will be interference between the hole and the shaft.

Part 2 of the Standard deals with straight-sided 90° serrations having nominal diameters from 0.25 to 6.0 inches. Provision is again made for three grades of fits, the basic constant being the serrated hole size. Variations in the fits of these serrations is obtained by varying the sizes of the serrations on the shaft, and the fits are related to flank bearing, the depth of engagement being constant for each size and allowing positive clearance at crest and root.

Fit 1 is an interference fit intended for permanent or semi-permanent ass emblies. Heating to expand the internally-serrated member is needed for assembly. Fit 2 is a transition fit intended for assemblies that require accurate location of the serrated members, but must allow disassembly. In maximum metal conditions, heating of the outside member may be needed for assembly. Fit. 3 is a clearance or sliding fit, intended for general applications.

Maximum and minimum dimensions for the various features are shown in the Standard for each class of fit. Maximum metal conditions presupposes that there are no errors of form such as spacing, alignment, or roundness of hole or shaft. Any compensation needed for such errors may require reduction of a shaft diameter or enlargement of a serrated bore, but the measured effective size must fall within the specified limits.

British Standard BS 3550:1963, "Involute Splines", is complementary to BS 2059, and the basic dimensions of all the sizes of splines are the same as those in the ANSI/ASME B5.15-1960, for major diameter fit and side fit. The British Standard uses the same terms and symbols and provides data and guidance for design of straight involute splines of 30° pressure angle, with tables of limiting dimensions. The standard also deals with manufacturing errors and their effect on the fit between mating spline elements. The range of splines covered is:

Side fit, flat root, 2.5/5.0 to 32/64 pitch, 6 to 60 splines.

Major diameter, flat root, 3.0/6.0 to 16/32 pitch, 6 to 60 splines.

Side fit, fillet root, 2.5/5.0 to 48/96 pitch, 6 to 60 splines.

British Standard BS 6186, Part 1:1981, "Involute Splines, Metric Module, Side Fit" is identical with sections 1 and 2 of ISO 4156 and with ANSI B92.2M-1980 (R1989) "Straight Cylindrical Involute Splines, Metric Module, Side Fit – Generalities, Dimensions and Inspection".

S.A.E. Standard Spline Fittings.— The S.A.E. spline fittings (Tables 18 through 21 inclusive) have become an established standard for many applications in the agricultural, automotive, machine tool, and other industries. The dimensions given, in inches, apply only to soft broached holes. Dimensions are illustrated in Figs. 7a, 7b, and 7c. The tolerances given may be readily maintained by usual broaching methods. The tolerances selected for the large and small diameters may depend upon whether the fit between the mating part, as finally made, is on the large or the small diameter. The other diameter, which is designed for clearance, may have a larger manufactured tolerance. If the final fit between the parts is on the sides of the spline only, larger tolerances are permissible for both the large and small diameters. The spline should not be more than 0.006 inch per foot out of parallel with respect to the shaft axis. No allowance is made for corner radii to obtain clearance. Radii at the corners of the spline should not exceed 0.015 inch.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7a. 4-Spline Fitting



Fig. 7b. 6-Spline Fitting



Fig. 7c. 10-Spline Fitting

Table 18. S.A.E. Standard 4–Spline Fittings

Nom. Diam	For All Fits				4A—Permanent Fit					4B—To Slide—No Load				
	D		*W*		*d*		*h*			*d*		*h*		
	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	*T*[a]	Min.	Max.	Min.	Max.	*T*[a]
¾	0.749	0.750	0.179	0.181	0.636	0.637	0.055	0.056	78	0.561	0.562	0.093	0.094	123
⅞	0.874	0.875	0.209	0.211	0.743	0.744	0.065	0.066	107	0.655	0.656	0.108	0.109	167
1	0.999	1.000	0.239	0.241	0.849	0.850	0.074	0.075	139	0.749	0.750	0.124	0.125	219
1⅛	1.124	1.125	0.269	0.271	0.955	0.956	0.083	0.084	175	0.843	0.844	0.140	0.141	277
1¼	1.249	1.250	0.299	0.301	1.061	1.062	0.093	0.094	217	0.936	0.937	0.155	0.156	341
1⅜	1.374	1.375	0.329	0.331	1.168	1.169	0.102	0.103	262	1.030	1.031	0.171	0.172	414
1½	1.499	1.500	0.359	0.361	1.274	1.275	0.111	0.112	311	1.124	1.125	0.186	0.187	491
1⅝	1.624	1.625	0.389	0.391	1.380	1.381	0.121	0.122	367	1.218	1.219	0.202	0.203	577
1¾	1.749	1.750	0.420	0.422	1.486	1.487	0.130	0.131	424	1.311	1.312	0.218	0.219	670
2	1.998	2.000	0.479	0.482	1.698	1.700	0.148	0.150	555	1.498	1.500	0.248	0.250	875
2¼	2.248	2.250	0.539	0.542	1.910	1.912	0.167	0.169	703	1.685	1.687	0.279	0.281	1106
2½	2.498	2.500	0.599	0.602	2.123	2.125	0.185	0.187	865	1.873	1.875	0.310	0.312	1365
3	2.998	3.000	0.720	0.723	2.548	2.550	0.223	0.225	1249	2.248	2.250	0.373	0.375	1969

[a] See note at end of Table 21.

Table 19. S.A.E. Standard 6–Spline Fittings

Nom. Diam.	For All Fits				6A—Permanent Fit			6B—To Slide—No Load			6C—To Slide Under Load		
	D		*W*		*d*			*d*			*d*		
	Min.	Max.	Min.	Max.	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]
¾	0.749	0.750	0.186	0.188	0.674	0.675	80	0.637	0.638	117	0.599	0.600	152
⅞	0.874	0.875	0.217	0.219	0.787	0.788	109	0.743	0.744	159	0.699	0.700	207
1	0.999	1.000	0.248	0.250	0.899	0.900	143	0.849	0.850	208	0.799	0.800	270
1⅛	1.124	1.125	0.279	0.281	1.012	1.013	180	0.955	0.956	263	0.899	0.900	342
1¼	1.249	1.250	0.311	0.313	1.124	1.125	223	1.062	1.063	325	0.999	1.000	421
1⅜	1.374	1.375	0.342	0.344	1.237	1.238	269	1.168	1.169	393	1.099	1.100	510
1½	1.499	1.500	0.373	0.375	1.349	1.350	321	1.274	1.275	468	1.199	1.200	608
1⅝	1.624	1.625	0.404	0.406	1.462	1.463	376	1.380	1.381	550	1.299	1.300	713
1¾	1.749	1.750	0.436	0.438	1.574	1.575	436	1.487	1.488	637	1.399	1.400	827
2	1.998	2.000	0.497	0.500	1.798	1.800	570	1.698	1.700	833	1.598	1.600	1080
2¼	2.248	2.250	0.560	0.563	2.023	2.025	721	1.911	1.913	1052	1.798	1.800	1367
2½	2.498	2.500	0.622	0.625	2.248	2.250	891	2.123	2.125	1300	1.998	2.000	1688
3	2.998	3.000	0.747	0.750	2.698	2.700	1283	2.548	2.550	1873	2.398	2.400	2430

[a] See note at end of Table 21.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 20. S.A.E. Standard 10–Spline Fittings

Nom. Diam.	For All Fits				10A—Permanent Fit			10B—To Slide, No Load			10C—To Slide Under Load		
	D		*W*		*d*			*d*			*d*		
	Min.	Max.	Min.	Max.	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]
¾	0.749	0.750	0.115	0.117	0.682	0.683	120	0.644	0.645	183	0.607	0.608	241
⅞	0.874	0.875	0.135	0.137	0.795	0.796	165	0.752	0.753	248	0.708	0.709	329
1	0.999	1.000	0.154	0.156	0.909	0.910	215	0.859	0.860	326	0.809	0.810	430
1⅛	1.124	1.125	0.174	0.176	1.023	1.024	271	0.967	0.968	412	0.910	0.911	545
1¼	1.249	1.250	0.193	0.195	1.137	1.138	336	1.074	1.075	508	1.012	1.013	672
1⅜	1.374	1.375	0.213	0.215	1.250	1.251	406	1.182	1.183	614	1.113	1.114	813
1½	1.499	1.500	0.232	0.234	1.364	1.365	483	1.289	1.290	732	1.214	1.215	967
1⅝	1.624	1.625	0.252	0.254	1.478	1.479	566	1.397	1.398	860	1.315	1.316	1135
1¾	1.749	1.750	0.271	0.273	1.592	1.593	658	1.504	1.505	997	1.417	1.418	1316
2	1.998	2.000	0.309	0.312	1.818	1.820	860	1.718	1.720	1302	1.618	1.620	1720
2¼	2.248	2.250	0.348	0.351	2.046	2.048	1088	1.933	1.935	1647	1.821	1.823	2176
2½	2.498	2.500	0.387	0.390	2.273	2.275	1343	2.148	2.150	2034	2.023	2.025	2688
3	2.998	3.000	0.465	0.468	2.728	2.730	1934	2.578	2.580	2929	2.428	2.430	3869
3½	3.497	3.500	0.543	0.546	3.182	3.185	2632	3.007	3.010	3987	2.832	2.835	5266
4	3.997	4.000	0.621	0.624	3.637	3.640	3438	3.437	3.440	5208	3.237	3.240	6878
4½	4.497	4.500	0.699	0.702	4.092	4.095	4351	3.867	3.870	6591	3.642	3.645	8705
5	4.997	5.000	0.777	0.780	4.547	4.550	5371	4.297	4.300	8137	4.047	4.050	10746
5½	5.497	5.500	0.855	0.858	5.002	5.005	6500	4.727	4.730	9846	4.452	4.455	13003
6	5.997	6.000	0.933	0.936	5.457	5.460	7735	5.157	5.160	11718	4.857	4.860	15475

[a] See note at end of Table 21.

Table 21. S.A.E. Standard 16–Spline Fittings

Nom. Diam.	For All Fits				16A—Permanent Fit			16B—To Slide—No Load			16C—To Slide Under Load		
	D		*W*		*d*			*d*			*d*		
	Min.	Max.	Min.	Max.	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]	Min.	Max.	*T*[a]
2	1.997	2.000	0.193	0.196	1.817	1.820	1375	1.717	1.720	2083	1.617	1.620	2751
2½	2.497	2.500	0.242	0.245	2.273	2.275	2149	2.147	2.150	3255	2.022	2.025	4299
3	2.997	3.000	0.291	0.294	2.727	2.730	3094	2.577	2.580	4687	2.427	2.430	6190
3½	3.497	3.500	0.340	0.343	3.182	3.185	4212	3.007	3.010	6378	2.832	2.835	8426
4	3.997	4.000	0.389	0.392	3.637	3.640	5501	3.437	3.440	8333	3.237	3.240	11005
4½	4.497	4.500	0.438	0.441	4.092	4.095	6962	3.867	3.870	10546	3.642	3.645	13928
5	4.997	5.000	0.487	0.490	4.547	4.550	8595	4.297	4.300	13020	4.047	4.050	17195
5½	5.497	5.500	0.536	0.539	5.002	5.005	10395	4.727	4.730	15754	4.452	4.455	20806
6	5.997	6.000	0.585	0.588	5.457	5.460	12377	5.157	5.160	18749	4.857	4.860	24760

[a] *Torque Capacity of Spline Fittings:* The torque capacities of the different spline fittings are given in the columns headed "*T*." The torque capacity, per inch of bearing length at 1000 pounds pressure per square inch on the sides of the spline, may be determined by the following formula, in which T = torque capacity in inch-pounds per inch of length, N = number of splines, R = mean radius or radial distance from center of hole to center of spline, h = depth of spline: $T = 1000NRh$

Table 22. Formulas for Determining Dimensions of S.A.E. Standard Splines

No. of Splines	*W* For All Fits	*A* Permanent Fit		*B* To Slide Without Load		*C* To Slide Under Load	
		h	*d*	*h*	*d*	*h*	*d*
Four	0.241*D*[a]	0.075*D*	0.850*D*	0.125*D*	0.750*D*	…	…
Six	0.250*D*	0.050*D*	0.900*D*	0.075*D*	0.850*D*	0.100*D*	0.800*D*
Ten	0.156*D*	0.045*D*	0.910*D*	0.070*D*	0.860*D*	0.095*D*	0.810*D*
Sixteen	0.098*D*	0.045*D*	0.910*D*	0.070*D*	0.860*D*	0.095*D*	0.810*D*

Copyright 2004, Industrial Press, Inc., New York, NY

[a] Four splines for fits *A* and *B* only.

The formulas in the table above give the maximum dimensions for *W*, *h*, and *d*, as listed in Tables 18 through 21 inclusive.

Polygon-Type Shaft Connections.— Involute-form and straight-sided splines are used for both fixed and sliding connections between machine members such as shafts and gears. Polygon-type connections, so called because they resemble regular polygons but with curved sides, may be used similarly. German DIN Standards 32711 and 32712 include data for three- and four-sided metric polygon connections. Data for 11 of the sizes shown in those Standards, but converted to inch dimensions by Stoffel Polygon Systems, are given in the accompanying table.

Dimensions of Three- and Four-Sided Polygon-type Shaft Connections

DRAWING FOR 3-SIDED DESIGNS



DRAWING FOR 4-SIDED DESIGNS



Three-Sided Designs					Four-Sided Designs				
Nominal Sizes			Design Data		Nominal Sizes			Design Data	
D_A (in.)	D_1 (in.)	e (in.)	Area (in.^{2})	Z_P (in.^{3})	D_A (in.)	D_1 (in.)	e (in.)	Area (in.^{2})	Z_P (in.^{3})
0.530	0.470	0.015	0.194	0.020	0.500	0.415	0.075	0.155	0.014
0.665	0.585	0.020	0.302	0.039	0.625	0.525	0.075	0.250	0.028
0.800	0.700	0.025	0.434	0.067	0.750	0.625	0.125	0.350	0.048
0.930	0.820	0.027	0.594	0.108	0.875	0.725	0.150	0.470	0.075
1.080	0.920	0.040	0.765	0.153	1.000	0.850	0.150	0.650	0.12
1.205	1.045	0.040	0.977	0.224	1.125	0.950	0.200	0.810	0.17
1.330	1.170	0.040	1.208	0.314	1.250	1.040	0.200	0.980	0.22
1.485	1.265	0.055	1.450	0.397	1.375	1.135	0.225	1.17	0.29
1.610	1.390	0.055	1.732	0.527	1.500	1.260	0.225	1.43	0.39
1.870	1.630	0.060	2.378	0.850	1.750	1.480	0.250	1.94	0.64
2.140	1.860	0.070	3.090	1.260	2.000	1.700	0.250	2.60	0.92

Dimensions Q and R shown on the diagrams are approximate and used only for drafting purposes: $Q \approx 7.5e$; $R \approx D_1/2 + 16e$.

Dimension $D_M = D_1 + 2e$. Pressure angle B_{max} is approximately $344e/D_M$ degrees for three sides, and $299e/D_M$ degrees for four sides.

Tolerances: ISO H7 tolerances apply to bore dimensions. For shafts, g6 tolerances apply for sliding fits; k7 tolerances for tight fits.

Choosing Between Three- and Four-Sided Designs: Three-sided designs are best for applications in which no relative movement between mating components is allowed while torque is transmitted. If a hub is to slide on a shaft while under torque, four-sided designs, which have larger pressure angles B_{max} than those of three-sided designs, are better suited to sliding even though the axial force needed to move the sliding member is approximately 50 percent greater than for comparable involute spline connections.

Copyright 2004, Industrial Press, Inc., New York, NY

Strength of Polygon Connections: In the formulas that follow,

H_w = hub width, inches H_t = hub wall thickness, inches

M_b = bending moment, lb-inch

M_t = torque, lb-inch

Z = section modulus, bending, in.^{3}

$=0.098D_M{}^4/D_A$ for three sides $=0.15D_I{}^3$ for four sides

Z_P = polar section modulus, torsion, in.^{3}

$=0.196D_M{}^4/D_A$ for three sides $=0.196D_I{}^3$ for four sides

D_A and D_M. See table footnotes.

S_b = bending stress, allowable, lb/in.^{2}

S_s = shearing stress, allowable, lb/in.^{2}

S_t = tensile stress, allowable, lb/in.^{2}

For shafts, $M_t\,(\text{maximum}) = S_s Z_p$;

$M_b\,(\text{maximum}) = S_b Z$

For bores,

$$H_t(\text{minimum}) = K\sqrt{\frac{M_t}{S_t H_w}}$$

in which $K = 1.44$ for three sides except that if D_M is greater than 1.375 inches, then $K = 1.2$; $K = 0.7$ for four sides.

Failure may occur in the hub of a polygon connection if the hoop stresses in the hub exceed the allowable tensile stress for the material used. The radial force tending to expand the rim and cause tensile stresses is calculated from

$$\text{Radial Force, lb} = \frac{2M_t}{D_I n \tan(B_{max} + 11.3)}$$

This radial force acting at n points may be used to calculate the tensile stress in the hub wall using formulas from strength of materials.

Manufacturing: Polygon shaft profiles may be produced using conventional machining processes such as hobbing, shaping, contour milling, copy turning, and numerically controlled milling and grinding. Bores are produced using broaches, spark erosion, gear shapers with generating cutters of appropriate form, and, in some instances, internal grinders of special design. Regardless of the production methods used, points on both of the mating profiles may be calculated from the following equations:

$$X = (D_I/2 + e)\cos\alpha - e\cos\, n\alpha\, \cos\,\alpha - ne\, \sin\, n\alpha\, \sin\,\alpha$$

$$Y = (D_I/2 + e)\sin\alpha - e\cos\, n\alpha\, \sin\,\alpha + ne\, \sin\, n\alpha\, \cos\,\alpha$$

In these equations, α is the angle of rotation of the workpiece from any selected reference position; n is the number of polygon sides, either 3 or 4; D_I is the diameter of the inscribed circle shown on the diagram in the table; and e is the dimension shown on the diagram in the table and which may be used as a setting on special polygon grinding machines. The value of e determines the shape of the profile. A value of 0, for example, results in a circular shaft having a diameter of D_I. The values of e in the table were selected arbitrarily to provide suitable proportions for the sizes shown.

Copyright 2004, Industrial Press, Inc., New York, NY

CAMS AND CAM DESIGN

Classes of Cams.— Cams may, in general, be divided into two classes: uniform motion cams and accelerated motion cams. The uniform motion cam moves the follower at the same rate of speed from the beginning to the end of the stroke; but as the movement is started from zero to the full speed of the uniform motion and stops in the same abrupt way, there is a distinct shock at the beginning and end of the stroke, if the movement is at all rapid. In machinery working at a high rate of speed, therefore, it is important that cams are so constructed that sudden shocks are avoided when starting the motion or when reversing the direction of motion of the follower.

The uniformly accelerated motion cam is suitable for moderate speeds, but it has the disadvantage of sudden changes in acceleration at the beginning, middle and end of the stroke. A cycloidal motion curve cam produces no abrupt changes in acceleration and is often used in high-speed machinery because it results in low noise, vibration and wear. The cycloidal motion displacement curve is so called because it can be generated from a cycloid which is the locus of a point of a circle rolling on a straight line.*

Cam Follower Systems.— The three most used cam and follower systems are radial and offset translating roller follower, Figs. 1a and 1b; and the swinging roller follower, Fig. 1c. When the cam rotates, it imparts a translating motion to the roller followers in Figs. 1a and 1b and a swinging motion to the roller follower in Fig. 1c. The motionof the follower is, of course, dependent on the shape of the cam; and the following section on displacement diagrams explains how a favorable motion is obtained so that the cam can rotate at high speed without shock.



Fig. 1a. Radial Translating Roller Follower



Fig. 1b. Offset Translating Roller Follower



Fig. 1c. Swinging Roller Follower



Fig. 2a. Closed-Track Cam



Fig. 2b. Closed-Track Cam With Two Rollers

The arrangements in Figs. 1a, 1b, and 1c show open-track cams. In Figs. 2a and 2b the roller is forced to move in a closed track. Open-track cams build smaller than closed-track

* Jensen, P. W., *Cam Design and Manufacture,* Industrial Press Inc.

Copyright 2004, Industrial Press, Inc., New York, NY

cams but, in general, springs are necessary to keep the roller in contact with the cam at all times. Closed-track cams do not require a spring and have the advantage of positive drive throughout the rise and return cycle. The positive drive is sometimes required as in the case where a broken spring would cause serious damage to a machine.

Displacement Diagrams.— Design of a cam begins with the displacement diagram. A simple displacement diagram is shown in Fig. 3. One cycle means one whole revolution of the cam; i.e., one cycle represents 360°. The horizontal distances T_1, T_2, T_3, T_4 are expressed in units of time (seconds); or radians or degrees. The vertical distance, h, represents the maximum "rise" or stroke of the follower.



Fig. 3. A Simple Displacement Diagram

The displacement diagram of Fig. 3 is not a very favorable one because the motion from rest (the horizontal lines) to constant velocity takes place instantaneously and this means that accelerations become infinitely large at these transition points.

Types of Cam Displacement Curves: A variety of cam curves are available for moving the follower. In the following sections only the rise portions of the total time-displacement diagram are studied. The return portions can be analyzed in a similar manner. Complex cams are frequently employed which may involve a number of rise-dwell-return intervals in which the rise and return aspects are quite different. To analyze the action of a cam it is necessary to study its time-displacement and associated velocity and acceleration curves. The latter are based on the first and second time-derivatives of the equation describing the time-displacement curve:

$$y = \text{displacement} = f(t) \quad \text{or} \quad y = f(\phi)$$

$$v = \frac{dy}{dt} = \text{velocity} = \omega\frac{dy}{d\phi}$$

$$a = \frac{d^2y}{dt^2} = \text{acceleration} = \omega^2\frac{d^2y}{d\phi^2}$$

Meaning of Symbols and Equivalent Relations: y = displacement of follower, inch
h = maximum displacement of follower, inch
t = time for cam to rotate through angle ϕ, sec, = ϕ/ω, sec
T = time for cam to rotate through angle β, sec, = β/ω, or $\beta/6N$, sec
ϕ = cam angle rotation for follower displacement y, degrees
β = cam angle rotation for total rise h, degrees
v = velocity of follower, in./sec
a = follower acceleration, in./sec^2
$t/T = \phi/\beta$
N = cam speed, rpm
ω = angular velocity of cam, degrees/sec = $\beta/T = \phi/t = d\phi/dt = 6N$
ω_R = angular velocity of cam, radians/sec = $\pi\omega/180$
W = effective weight, lbs

Copyright 2004, Industrial Press, Inc., New York, NY

g = gravitational constant = 386 in./sec^2
$f(t)$ = means a function of t
$f(\phi)$ = means a function of ϕ
R_{min} = minimum radius to the cam pitch curve, inch
R_{max} = maximum radius to the cam pitch curve, inch
r_f = radius of cam follower roller, inch
ρ = radius of curvature of cam pitch curve (path of center of roller follower), inch
R_c = radius of curvature of actual cam surface, in., = $\rho - r_f$ for convex surface;
= $\rho + r_f$ for concave surface.



Fig. 4. Cam Displacement, Velocity, and Acceleration Curves for Constant Velocity Motion

Four displacement curves are of the greatest utility in cam design.

1. Constant-Velocity Motion: (Fig. 4)

$$y = h\frac{t}{T} \quad \text{or} \quad y = \frac{h\phi}{\beta} \qquad (1a)$$

$$v = \frac{dy}{dt} = \frac{h}{T} \quad \text{or} \quad v = \frac{h\omega}{\beta} \qquad (1b)$$

$$a = \frac{d^2y}{dt^2} = 0^* \qquad (1c)$$

} $0 < t < T$

* Except at $t = 0$ and $t = T$ where the acceleration is theoretically infinite.

This motion and its disadvantages were mentioned previously. While in the unaltered form shown it is rarely used except in very crude devices, nevertheless, the advantage of uniform velocity is an important one and by modifying the start and finish of the follower stroke this form of cam motion can be utilized. Such modification is explained in the section Displacement Diagram Synthesis.

2. Parabolic Motion: (Fig. 5)

For $0 \le t \le T/2$ and $0 \le \phi \le \beta/2$

$$y = 2h(t/T)^2 = 2h(\phi/\beta)^2 \qquad (2a)$$
$$v = 4ht/T^2 = 4h\omega\phi/\beta^2 \qquad (2b)$$
$$a = 4h/T^2 = 4h(\omega/\beta)^2 \qquad (2c)$$

For $T/2 \le t \le T$ and $\beta/2 \le \phi \le \beta$

$$y = h[1 - 2(1 - t/T)^2] = h[1 - 2(1 - \phi/\beta)^2] \qquad (2d)$$
$$v = 4h/T(1 - t/T) = (4h\omega/\beta)(1 - \phi/\beta) \qquad (2e)$$
$$a = -4h/T^2 = -4h(\omega/\beta)^2 \qquad (2f)$$

Examination of the above formulas shows that the velocity is zero when $t = 0$ and $y = 0$; and when $t = T$ and $y = h$.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Cam Displacement, Velocity, and Acceleration Curves for Parabolic Motion

The most important advantage of this curve is that for a given angle of rotation and rise it produces the smallest possible acceleration. However, because of the sudden changes in acceleration at the beginning, middle, and end of the stroke, shocks are produced. If the follower system were perfectly rigid with no backlash or flexibility, this would be of little significance. But such systems are mechanically impossible to build and a certain amount of impact is caused at each of these changeover points.



Fig. 6. Cam Displacement, Velocity, and Acceleration Curves for Simple Harmonic Motion

3. Simple Harmonic Motion: (Fig. 6)

$$y = \frac{h}{2}\left[1 - \cos\left(\frac{180°t}{T}\right)\right] \quad \text{or} \quad y = \frac{h}{2}\left[1 - \cos\left(\frac{180°\phi}{\beta}\right)\right] \tag{3a}$$

$$v = \frac{h}{2} \cdot \frac{\pi}{T} \sin\left(\frac{180°t}{T}\right) \quad \text{or} \quad v = \frac{h}{2} \cdot \frac{\pi\omega}{\beta} \sin\left(\frac{180°\phi}{\beta}\right) \tag{3b}$$

$$a = \frac{h}{2} \cdot \frac{\pi^2}{T^2} \cos\left(\frac{180°t}{T}\right) \quad \text{or} \quad a = \frac{h}{2} \cdot \left(\frac{\pi\omega}{\beta}\right)^2 \cos\left(\frac{180°\phi}{\beta}\right) \tag{3c}$$

} $0 \le t \le T$

Smoothness in velocity and acceleration during the stroke is the advantage inherent in this curve. However, the instantaneous changes in acceleration at the beginning and end of the stroke tend to cause vibration, noise, and wear. As can be seen from Fig. 6, the maximum acceleration values occur at the ends of the stroke. Thus, if inertia loads are to be overcome by the follower, the resulting forces cause stresses in the members. These forces are in many cases much larger than the externally applied loads.

Copyright 2004, Industrial Press, Inc., New York, NY

4. Cycloidal Motion: (Fig. 7)

$$y = h\left[\frac{t}{T} - \frac{1}{2\pi}\sin\left(\frac{360°t}{T}\right)\right] \quad \text{or} \quad y = h\left[\frac{\phi}{\beta} - \frac{1}{2\pi}\sin\left(\frac{360°\phi}{\beta}\right)\right] \tag{4a}$$

$$v = \frac{h}{T}\left[1 - \cos\left(\frac{360°t}{T}\right)\right] \quad \text{or} \quad v = \frac{h\omega}{\beta}\left[1 - \cos\left(\frac{360°\phi}{\beta}\right)\right] \tag{4b}$$

$$a = \frac{2\pi h}{T^2}\sin\left(\frac{360°t}{T}\right) \quad \text{or} \quad a = \frac{2\pi h\omega^2}{\beta^2}\sin\left(\frac{360°\phi}{\beta}\right) \tag{4c}$$

} $0 \le i \le T$



Fig. 7. Cam Displacement, Velocity, and Acceleration Curves for Cycloidal Motion

This time-displacement curve has excellent acceleration characteristics; there are no abrupt changes in its associated acceleration curve. The maximum value of the acceleration of the follower for a given rise and time is somewhat higher than that of the simple harmonic motion curve. In spite of this, the cycloidal curve is used often as a basis for designing cams for high-speed machinery because it results in low levels of noise, vibration, and wear.

Displacement Diagram Synthesis.— The straight-line graph shown in Fig. 3 has the important advantage of uniform velocity. This is so desirable that many cams based on this graph are used. To avoid impact at the beginning and end of the stroke, a modification is introduced at these points. There are many different types of modifications possible, ranging from a simple circular arc to much more complicated curves. One of the better curves used for this purpose is the parabolic curve given by Equation (2a). As seen from the derived time graphs, this curve causes the follower to begin a stroke with zero velocity but having a finite and constant acceleration. We must accept the necessity of acceleration, but effort should be made to hold it to a minimum.

Matching of Constant Velocity and Parabolic Motion Curves: By matching a parabolic cam curve to the beginning and end of a straight-line cam displacement diagram it is possible to reduce the acceleration from infinity to a finite constant value to avoid impact loads. As illustrated in Fig. 8, it can be shown that for any parabola the vertex of which is at O, the tangent to the curve at the point P intersects the line OQ at its midpoint. This means that the tangent at P represents the velocity of the follower at time X_0 as shown in Fig. 8. Since the tangent also represents the velocity of the follower over the constant velocity portion of the stroke, the transition from rest to the maximum velocity is accomplished with smoothness.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. The Tangent at *P* Bisects *OQ*, When Curve is a Parabola

Example: A cam follower is to rise ¼ in. with constant acceleration; 1¼ in. with constant velocity, over an angle of 50 degrees; and then ½ in. with constant deceleration.

In Fig. 9 the three rise distances are laid out, $y_1 = \frac{1}{4}$ in., $y_2 = 1\frac{1}{4}$ in., $y_3 = \frac{1}{2}$ in., and horizontals drawn. Next, an arbitrary horizontal distance ϕ_2 proportional to 50 degrees is measured off and points *A* and *B* are located. The line *AB* is extended to M_1 and M_2. By remembering that a tangent to a parabola, Fig. 8, will cut the abscissa axis at point $(X_0/2,0)$ where X_0 is the abscissa of the point of tangency, the two values $\phi_1 = 20°$ and $\phi_3 = 40°$ will be found. Analytically,

$$\frac{M_1E}{\phi_2} = \frac{y_1}{y_2} \qquad \frac{\frac{1}{2}\phi_1}{50°} = \frac{0.25}{1.25} \qquad \therefore \phi_1 = 20°$$

$$\frac{FM_2}{\phi_2} = \frac{y_3}{y_2} \qquad \frac{\frac{1}{2}\phi_3}{50°} = \frac{0.50}{1.25} \qquad \therefore \phi_3 = 40°$$

In Fig. 9, the portions of the parabola have been drawn in; the details of this operation are as follows:

Assume that accuracy to the nearest thousandth of one inch is desired, and it is decided to plot values for every 5 degrees of cam rotation.

The formula for the acceleration portion of the parabolic curve is:

$$y = \frac{2h}{T^2}t^2 = 2h\left(\frac{\phi}{\beta}\right)^2 \tag{5}$$

Two different parabolas are involved in this example; one for accelerating the follower during a cam rotation of 20 degrees, the other for decelerating it in 40 degrees, these two being tangent, to opposite ends of the same line *AB*.

In Fig. 9 only the first half of a complete acceleration-deceleration parabolic curve is used to blend with the left end of the straight line *AB*. Therefore, in using the Formula (5) substitute $2y_1$ for *h* and $2\phi_1$ for β so that

Copyright 2004, Industrial Press, Inc., New York, NY

$$y = \frac{2h\phi^2}{\beta^2} = \frac{(2)(2y_1)}{(2\phi_1)^2}\phi^2$$

For the right end of the straight line *AB*, the calculations are similar but, in using Formula (5), calculated *y* values are *subtracted* from the *total* rise of the cam ($y_1 + y_2 + y_3$) to obtain the follower displacement.



Fig. 9. Matching a Parabola at Each End of Straight Line Displacement Curve *AB* to Provide More Acceptable Acceleration and Deceleration

Table 1 shows the computations and resulting values for the cam displacement diagram described. The calculations are shown in detail so that if equations are programmed for a digital computer, the results can be verified easily. Obviously, the intermediate points are not needed to draw the straight line, but when the cam profile is later to be drawn or cut, these values will be needed since they are to be measured on radial lines.

The matching procedure when using cycloidal motion is exactly the same as for parabolic motion, because parabolic and cycloidal motion have the same maximum velocity for equal rise (or return) and lift angle (or return angle).

Cam Profile Determination.— In the cam constructions that follow an artificial device called an *inversion* is used. This represents a mental concept which is very helpful in performing the graphical work. The construction of a cam profile requires the drawing of many positions of the cam with the follower in each case in its related location. However, instead of revolving the cam, it is assumed that the follower rotates around the *fixed* cam. It requires the drawing of many follower positions, but since this is done more or less diagrammatically, it is relatively simple.

As part of the inversion process, the direction of rotation is important. In order to preserve the correct sequence of events, the artificial rotation of the follower must be the reverse of the cam's prescribed rotation. Thus, in Fig. 10 the cam rotation is counterclockwise, whereas the artificial rotation of the follower is clockwise.

Radial Translating Roller Follower: The time-displacement diagram for a camwith a radial translating roller follower is shown in Fig. 10(a). This diagram is read from left to right as follows: For 100 degrees of cam shaft rotation the follower rises *h* inches (*AB*), dwells in its upper position for 20 degrees (*BC*), returns over 180 degrees (*CD*), and finally dwells in its lowest position for 60 degrees (*DE*). Then the entire cycle is repeated.

Fig. 10(b) shows the cam construction layout with the cam pitch curve as a dot and dash line. To locate a point on this curve, take a point on the displacement curve, as 6′ at the 60-degree position, and project this horizontally to point 6″ on the 0-degree position of the cam construction diagram. Using the center of cam rotation, an arc is struck from point 6″ to intercept the 60-degree position radial line which gives point 6‴ on the cam pitch curve. It will be seen that the smaller circle in the cam construction layout has a radius R_{min} equal

Copyright 2004, Industrial Press, Inc., New York, NY

to the smallest distance from the center of cam rotation to the pitch curve and, similarly, the larger circle has a radius R_{max} equal to the largest distance to the pitch curve. Thus, the difference in radii of these two circles is equal to the maximum rise h of the follower.

The cam pitch curve is also the actual profile or working surface when a knife-edged follower is used. To get the profile or working surface for a cam with a roller follower, a series of arcs with centers on the pitch curve and radii equal to the radius of the roller are drawn and the inner envelope drawn tangent to these arcs is the cam working surface or profile shown as a solid line in Fig. 10(b).

Table 1. Development of Modified Constant Velocity Cam with Parabolic Matching

Rise Angle	φ Degrees	Computation	Follower Displacement y	Explanation
	0	0	0	
	5	0.000625×5^2	0.016	$\beta = 40°\ h = 0.500$
$\phi_1 = 20°$	10	0.00625×10^2	0.063	$y = \frac{(2)(0.500)}{(40)^2}\phi^2$
	15	0.000625×15^2	0.141	$= 0.000625\phi^2$
	20	0.000625×20^2	0.250	
	25		0.375	
	30		0.500	
	35		0.625	
	40		0.750	
$\phi_2 = 50°$	45		0.875	1.250 in. divided into
	50		1.000	10 uniform divisions
	55		1.125	
	60		1.250	
	65		1.375	
	70		1.500	
	75	$2.000 - (0.0003125 \times 35^2)$	1.617	
	80	$2.000 - (0.0003125 \times 30^2)$	1.617	$\beta = 80°\ h = 1.000$
	85	$2.000 - (0.0003125 \times 25^2)$	1.805	$y = 2 - \frac{(2)(1.000)}{(80°)^2}(110° - \phi)^2$
$\phi_3 = 40°$	90	$2.000 - (0.0003125 \times 20^2)$	1.875	$= 2 - 0.0003125(110° - \phi)^2$
	95	$2.000 - (0.0003125 \times 15^2)$	1.930	See footnote [a]
	100	$2.000 - (0.0003125 \times 10^2)$	1.969	
	105	$2.000 - (0.0003125 \times 5^2)$	1.992	
	110	$2.000 - (0.0003125 \times 0^2)$	2.000	

[a] Since the deceleration portion of a parabolic cam is the same shape as the acceleration portion, but inverted, Formula (5) may be used to calculate the y values by substituting $2y_3$ for h and for β and the result subtracted from the total rise $(y_1 + y_2 + y_3)$ to obtain the follower displacement.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 10. (a) Time-Displacement Diagram for Cam to be Laid Out; (b) Construction of Contour of Cam With Radial Translating Roller Follower

Offset Translating Roller Follower: Given the time-displacement diagram Fig. 11(a) and an offset follower. The construction of the cam in this case is very similar to the foregoing case and is shown in Fig. 11(b). In this construction it will be noted that the angular position lines are not drawn radially from the cam shaft center but tangent to a circle having a radius equal to the amount of offset of the center line of the cam follower from the center of the cam shaft. For counterclockwise rotation of the cam, points 6′, 6″, and 6‴ are located in succession as indicated.



Fig. 11. (a) Time-Displacement Diagram for Cam to be Laid Out; (b) Construction of Contour of Cam With Offset Translating Roller Follower

Swinging Roller Follower: Given the time-displacement diagram Fig. 12(a) and the length of the swinging follower arm L_f, it is required that the displacement of the follower center along the circular arc that it describes be equal to the corresponding displacements in the time-displacement diagram. If ϕ_0 is known, the displacement h of Fig. 12(a) would be found from the formula $h = \pi\phi_0 L_f/180°$: otherwise the maximum rise h of the follower is stepped off on the arc drawn with M as a center and starting at a point on the R_{min} circle. Point M is the actual position of the pivot center of the swinging follower with respect to the cam shaft center. It is again required that the rotation of the cam be counterclockwise and therefore M is considered to have been rotated clockwise around the cam shaft center, whereby the points 2, 4, 6, etc., are obtained as shown in Fig. 12(b). Around each of the pivot points, 2, 4, 6, etc., circular arcs whose radii equal L_f are drawn between the R_{min} and

Copyright 2004, Industrial Press, Inc., New York, NY

R_{max} circles giving the points $2', 4', 6'$, etc. The R_{min} circle with center at the cam shaft center is drawn through the lowest position of the center of the roller follower and the R_{max} circle through the highest position as shown. The different points on the pitch curve are now located. Point $6'''$, for instance, is found by stepping off the y_6 ordinate of the displacement diagram on arc $6'$ starting at the R_{min} circle.



Fig. 12. (a) Time-Displacement Diagram for Cam to be Laid Out; (b) Construction of Contour of Cam With Swinging Roller Follower

Pressure Angle and Radius of Curvature.— The pressure angle at any point on the profile of a cam may be defined as the angle between the direction where the follower wants to go at that point and where the cam wants to push it. It is the angle between the tangent to the path of follower motion and the line perpendicular to the tangent of the cam profile at the point of cam-roller contact.

The size of the pressure angle is important because:

1) Increasing the pressure angle increases the side thrust and this increases the forces exerted on cam and follower.

2) Reducing the pressure angle increases the cam size and often this is not desirable because:

a) The size of the cam determines, to a certain extent, the size of the machine.

b) Larger cams require more precise cutting points in manufacturing and, therefore, an increase in cost.

c) Larger cams have higher circumferential speed and small deviations from the theoretical path of the follower cause additional acceleration, the size of which increases with the square of the cam size.

d) Larger cams mean more revolving weight and in high-speed machines this leads to increased vibrations in the machine.

e) The inertia of a large cam may interfere with quick starting and stopping.

The maximum pressure angle α_m should, in general, be kept at or below 30 degrees for translating-type followers and at or below 45 degrees for swinging-type followers.These values are on the conservative side and in many cases may be increased considerably, but beyond these limits trouble could develop and an analysis is necessary.

In the following, graphical methods are described by which a cam mechanism can be designed with translating or swinging roller followers having specified maximum pressure angles for rise and return. These methods are applicable to any kind of time-displacement diagram.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 13. Displacement Diagram

Determination of Cam Size for a Radial or an Offset Translating Follower.— Fig. 13 shows a time-displacement diagram. The maximum displacement is preferably made to scale, but the length of the abscissa, L, can be chosen arbitrarily. The distance L from 0 to 360 degrees is measured and is set equal to $2\pi k$ from which

$$k = \frac{L}{2\pi}$$

k is calculated and laid out as length E to M in Fig. 14.

In Fig. 13 the two points P_1 and P_2 having the maximum angles of slope, τ_1, and τ_2, are located by inspection. In this example y_1 and y_2 are of equal length.

Angles τ_1 and τ_2 are laid out as shown in Fig. 14, and the points of intersection with a perpendicular to EM at M determine Q_1 and Q_2. The measured distances

$$MQ_1 = k\tan\tau_1 \quad \text{and} \quad MQ_2 = k\tan\tau_2$$

are laid out in Fig. 15, which is constructed as follows:

Draw a vertical line R_uR_o of length h equal to the stroke of the roller follower, R_u being the lowest position and R_o the highest position of the center of the roller follower. From R_u lay out $R_uR_{y1} = y_1$ and $R_uR_{y2} = y_2$; these are equal lengths in this example. Next, if the rotation of the cam is counterclockwise, lay out $k\tan\tau_1$, to the left, $k\tan\tau_2$ to the right from points R_{y1} and R_{y2}, respectively, R_{y1} and R_{y2} being the same point in this case.



Fig. 14. Construction to Find $k\tan\tau_1$ and $k\tan\tau_2$

The specified maximum pressure angle α_1 is laid out at E_1 as shown, and a ray (line) E_1F_1 is determined. Any point on this ray chosen as the cam shaft center will proportion the cam so that the pressure angle at a point on the cam profile corresponding to point P_1, of the displacement diagram will be exactly α_1.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 15. Finding Proportions of Cam; Offset Translating Follower

The angle α_2 is laid out at E_2 as shown, and another ray E_2F_2 is determined. Similarly, any point on this ray chosen as the cam shaft center will proportion the cam so that the pressure angle at a point on the cam profile corresponding to point P_2 of the displacement diagram will be exactly α_2.

Any point chosen within the cross-hatched area A as the cam center will yield a cam whose pressure angles at points corresponding to P_1 and P_2 will not exceed the specified values α_1 and α_2 respectively. If O_1 is chosen as the cam shaft center, the pressure angles on the cam profile corresponding to points P_1 and P_2 are exactly α_1 and α_2, respectively. Selection of point O_1 also yields the smallest possible cam for the given requirements and requires an offset follower in which e is the offset distance.

If O_2 is chosen as the cam shaft center, a radial translating follower is obtained (zero offset). In that case, the pressure angle α_1 for the rise is unchanged, whereas the pressure angle for the return is changed from α_2 to α'_2. That is, the pressure angle on the return stroke is reduced at the point P_2. If point O_3 had been selected, then α_2 would remain unchanged but α_1 would be decreased and the offset, e, increased.



Fig. 16. Construction of Cam Contour; Offset Translating Follower

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. 16 shows the shape of the cam when O_1 from Fig. 15 is chosen as the cam shaft center, and it is seen that the pressure angle at a point on the cam profile corresponding to point P_1 is α_1 and at a point corresponding to point P_2 is α_2.

In the foregoing, a cam mechanism has been so proportioned that the pressure angles α_1 and α_2 at points on the cam corresponding to points P_1 and P_2 were obtained. Even though P_1 and P_2 are the points of greatest slope on the displacement diagram, the pressure angles produced at some other points on the actual cam may be slightly greater.

However, if the pressure angles α_1 and α_2 are not to be exceeded at any point — i.e., they are to be maximum pressure angles — then P_1 and P_2 must be selected to be at the locations where these maximum pressure angles occur. If these locations are not known, then the graphical procedure described must be repeated, letting P_1 take various positions on the curve for rise (*AB*) and P_2 various positions on the return curve (*CD*) and then setting R_{min} equal to the largest of the values determined from the various positions.



Fig. 17. Displacement Diagram

Determination of Cam Size for Swinging Roller Follower.— The proportioning of a cam with swinging roller follower having specific pressure angles at selected points follows the same procedure as that for a translating follower.

Example: Given the diagram for the roller displacement along its circular arc, Fig. 17 with $h = 1.95$ in., the periods of rise and fall, respectively, $\beta_1 = 160°$ and $\beta_2 = 120°$, the length of the swinging follower arm $L_f = 3.52$ in., rotation of the cam away from pivot point *M*, and pressure angles $\alpha_1 = \alpha_2 = 45°$ (corresponding to the points P_1 and P_2 in the displacement diagram). Find the cam proportions.

Solution: Distances $k \tan \tau_1$ and $k \tan \tau_2$ are determined as in the previous example, Fig. 14. In Fig. 18, R_{y1} is determined by making the distance $R_u R_{y1} = y_1$ along the arc $R_u R_o$ and R_{y2} by making $R_u R_{y2} = y_2$. The arc $R_u R_o = h$ and R_u indicates the lowest position of the center of the swinging roller follower and R_o the highest position.

Because the cam (i.e., the surface of the cam as it passes under the follower roller) rotates away from pivot point *M*, $k \tan \tau_1$ is laid out away from *M*, that is, from R_{y1} to E_1 and $k \tan \tau_2$ is laid out toward *M* from R_{y2} to E_2. Angle α_1 at E_1 determines one ray and α_2 at E_2 another ray, which together subtend an area *A* having the property that if the cam shaft center is chosen inside this area, the pressure angles at the points of the cam corresponding to P_1 and P_2 in the displacement diagram will not exceed the given values α_1 and α_2, respectively. If the cam shaft center is chosen on the ray drawn from E_1 at an angle $\alpha_1 = 45°$, the pressure angle α_1 on the cam profile corresponding to point P_1 will be exactly 45°, and if chosen on the ray from E_2, the pressure angle α_2 corresponding to P_2 will be exactly 45°. If another point, O_2 for example, is chosen as the cam shaft center, the pressure angle corresponding to P_1 will be α'_1 and that corresponding to P_2 will be α_2.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 18. Finding Proportions of Cam; Swinging Roller Follower (CCW Rotation)



Fig. 19. Finding Proportions of Cam; Swinging Roller Follower (CW Rotation)

Fig. 19 shows the construction for rotation toward pivot point *M* (clockwise rotation of the cam in this case). The layout of the cam curve is made in a manner similar to that shown previously in Fig. 12.

In this example, the cam mechanism was so proportioned that the pressure angles at certain points (corresponding to P_1 and P_2) do not exceed certain specified values (namely α_1 and α_2).

To make sure that the pressure angle at *no point* along the cam profile exceeds the specified value, the previous procedure should be repeated for a series of points along the profile.

Formulas for Calculating Pressure Angles.— The graphical methods described previously are useful because they permit layout and measurement of pressure angles and radii of curvature of *any* cam profile. For cams of complicated profiles, and especially if the pro-

Copyright 2004, Industrial Press, Inc., New York, NY

file cannot be represented by a simple formula, the graphical method may be the only practical solution. However, for some of the standard cam profiles utilizing *radial* translating roller followers, the following formulas may be used to determine key cam dimensions before laying out the cam. These formulas enable the designer to specify the maximum pressure angle (usually 30° or less) and, using the specified value, to calculate the minimum cam size that will satisfy the requirement.

The following symbols are in addition to those starting on page 2189.

α_{max} = specified maximum pressure angle, degrees
$R_{\alpha max}$ = radius from cam center to point on pitch curve where α_{max} is located, inches
ϕ_p = rise angle, in degrees, corresponding to α_{max} and $R_{\alpha\,max}$
α = pressure angle at any selected point, degrees
R_α = radius from cam center to pitch curve at α, inches
ϕ = rise angle, in degrees, corresponding to α and R_α

For Uniform Velocity Motion: $\alpha = \arctan\left[\frac{180°h}{\pi\beta R_\alpha}\right]$ at radius R_α to the pitch curve (6a)

$$\alpha_{max} = \arctan\left[\frac{180°h}{\pi\beta R_{min}}\right] \text{ at radius } R_{min} \text{ of the pitch curve } (\phi=0°). \quad (6b)$$

If α_{max} is specified, then the minimum radius to the lowest point on the pitch curve, R_{min}, is:

$$R_{min} = \frac{180°h}{\pi\beta\tan\alpha_{max}} \text{ which corresponds to } \phi=0°. \quad (6c)$$

For Parabolic Motion: $\alpha = \arctan\left[\frac{720°h\phi}{\pi\beta^2 R_\alpha}\right]$ at radius R_α to the pitch curve at angle ϕ, where $0\le\phi\le\beta/2$ (7a)

$\alpha = \arctan\left[\frac{720°h(1-\phi/\beta)}{\pi\beta R_\alpha}\right]$ at radius R_α to the pitch curve at angle ϕ, where $\beta/2\le\phi\le\beta$.

$$\alpha = \arctan\left[\frac{360°h}{\pi\beta R_\alpha}\right] \text{ which occurs at } \phi=\beta/2 \text{ and } R_\alpha=R_{min}+h/2 \quad (7b)$$

If α_{max} is specified, then the minimum radius to the lowest point of the pitch curve is:

$$R_{min} = \left[\frac{360°h}{\pi\beta\tan\alpha_{max}} - \frac{h}{2}\right] \text{ which corresponds to } \phi=0°. \quad (7c)$$

For Simple Harmonic Motion: $\alpha = \arctan\left[\frac{90°h}{\beta R_\alpha}\sin\left(\frac{180°\phi}{\beta}\right)\right]$ at radius R_α to the pitch curve at angle ϕ (8a)

$\phi_p = \left(\frac{\beta}{180°}\right)\left[\text{arccot}\left(\frac{\beta}{180°}\tan\alpha_{max}\right)\right]$ = value of ϕ where specified pressure angle α_{max} occurs (8b)

$$R_{\alpha max} = \frac{h[\sin(180°\phi_p/\beta)]^2}{2\cos(180°\phi_p/\beta)} \text{ at point where } \alpha=\alpha_{max} \text{ and } \phi=\phi_{max} \quad (8c)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$R_{min} = R_{\alpha\ max} - \frac{h}{2}\left[1 - \cos\left(\frac{180°\phi_p}{\beta}\right)\right] \quad (8d)$$

For Cycloidal Motion: $\alpha = \arctan\left[\frac{180°}{\pi\beta R_\alpha}\left[1 - \cos\left(\frac{360°\phi}{\beta}\right)\right]\right]$ at radius R_α to the pitch curve at angle ϕ (9a)

$$\phi_p = \frac{\beta}{180°}\left[\text{arccot}\left(\frac{\beta \tan\alpha_{max}}{360°}\right)\right]$$ ϕ_p=value of ϕ where specified pressure angle α_{max} occurs

$$R_{\alpha max} = \frac{h}{2\pi}\frac{[1 - \cos(360°\phi_p/\beta)]^2}{\sin(360°\phi_p/\beta)}$$ at point where $\alpha=\alpha_{max}$ and $\phi=\phi_p$ (9b)

(9c)

$$R_{min} = R_{\alpha\ max} - h\left[\frac{\phi_p}{\beta} - \frac{1}{2\pi}\sin\left(\frac{360°\phi_p}{\beta}\right)\right] \quad (9d)$$

Radius of Curvature.— The minimum radius of curvature of a cam should be kept as large as possible (1) to prevent undercutting of the convex portion of the cam and (2) to prevent too high surface stresses. Figs. 20(a), (b) and (c) illustrate how undercutting occurs.



Fig. 20. (a) No Undercutting. (b) Sharp Corner on Cam. (c) Undercutting

In Fig. 20(a) the radius of curvature of the path of the follower is ρ_{min} and the cam will at that point have a radius of curvature $R_c = \rho_{min} - r_f$.

In Fig. 20(b) $\rho_{min} = r_f$ and $R_c = 0$. Therefore, the actual cam will have a sharp corner which in most cases will result in too high surface stresses.

In Fig. 20(c) is shown the case where $\rho_{min} < r_f$. This case is not possible because undercutting will occur and the actual motion of the roller follower will deviate from the desired one as shown.

Undercutting cannot occur at the *concave* portion of the cam profile (working surface), but caution should be exerted in not making the radius of curvature equal to the radius of the roller follower. This condition would occur if there is a cusp on the displacement diagram which, of course, should always be avoided. To enable milling or grinding of *concave* portions of a cam profile, the radius of curvature of concave portions of the cam, $R_c = \rho_{min} + r_f$, must be larger than the radius of the cutter to be used.

The radius of curvature is used in calculating surface stresses (see following section), and may be determined by measurement on the cam layout or, in the case of radial translating followers, may be calculated using the formulas that follow. Although these formulas are exact for radial followers, they may be used for offset and swinging followers to obtain an approximation.

Copyright 2004, Industrial Press, Inc., New York, NY

Based upon polar coordinates, the radius of curvature is:

$$\rho = \frac{\left[r^2 + \left(\frac{dr}{d\phi}\right)^2\right]^{3/2}}{r^2 + 2\left(\frac{dr}{d\phi}\right)^2 - r\left(\frac{d^2r}{d\phi^2}\right)} \quad (10)$$

*Positive values (+) indicate convex curve; negative values (−), concave.

In Equation (10), $r = (R_{min} + y)$, where R_{min} is the smallest radius to the pitch curve (see Fig. 12) and y is the displacement of the follower from its lowest position given in terms of ϕ, the angle of cam rotation. The following formulas for r, $dr/d\phi$, and $d^2r/d\phi^2$ may be substituted into Equation (10) to calculate the radius of curvature at any point of the cam pitch curve; however, to determine the possibility of undercutting of the convex portion of the cam, it is the minimum radius of curvature on the convex portion, ρ_{min}, that is needed. The minimum radius of curvature occurs, generally, at the point of maximum *negative* acceleration.

Parabolic motion:

$$r = R_{min} + h - 2h\left(1 - \frac{\phi}{\beta}\right)^2 \quad (11a)$$

$$\frac{dr}{d\phi} = \frac{720°h}{\pi\beta}\left(1 - \frac{\phi}{\beta}\right) \quad (11b)$$

$$\frac{d^2r}{d\phi^2} = \frac{-4(180°)^2h}{\pi^2\beta^2} \quad (11c)$$

} $\frac{\beta}{2} \le \phi \le \beta$

These equations are for the deceleration portion of the curve as explained in the footnote to Table 1.

The minimum radius of curvature can occur at either $\phi = \beta/2$ or at $\phi = \beta$, depending on the magnitudes of h, R_{min}, and β. Therefore, to determine which is the case, make two calculations using Formula (10), one for $\phi = \beta/2$, and the other for $\phi = \beta$.

Simple harmonic motion:

$$r = R_{min} + \frac{h}{2}\left[1 - \cos\left(\frac{180°\phi}{\beta}\right)\right] \quad (12a)$$

$$\frac{dr}{d\phi} = \frac{180°h}{2\beta}\sin\left(\frac{180°\phi}{\beta}\right) \quad (12b)$$

$$\frac{d^2r}{d\phi^2} = \frac{(180°)^2h}{2\beta^2}\cos\left(\frac{180°\phi}{\beta}\right) \quad (12c)$$

} $0 \le \phi \le \beta$

The minimum radius of curvature can occur at either $\phi = \beta/2$ or at $\phi = \beta$, depending on the magnitudes of h, R_{min}, and β. Therefore, to determine which is the case, make two calculations using Formula (10), one for $\phi = \beta/2$, and the other for $\phi = \beta$.

Cycloidal motion:

$$r = R_{min} + h\left[\frac{\phi}{\beta} - \frac{1}{2\pi}\sin\left(\frac{360°\phi}{\beta}\right)\right] \quad (13a)$$

$$\frac{dr}{d\phi} = \frac{180°h}{\pi\beta}\left[1 - \cos\left(\frac{360°\phi}{\beta}\right)\right] \quad (13b)$$

} $0 \le \phi \le \beta$

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{d^2r}{d\phi^2} = \frac{2(180°)^2h}{\pi\beta^2}\sin\left(\frac{360°\phi}{\beta}\right) \quad (13c)$$

$$\rho_{min} = \frac{[(R_{min} + 0.91h)^2 + (180°h/\pi\beta)^2]^{3/2}}{(R_{min} + 0.91h)^2 + 2(180°h/\pi\beta)^2 + (R_{min} + 0.91h)[2(180°)^2h/\pi\beta^2]} \quad (13d)$$

(ρ_{min} occurs near $\phi = 0.75\beta$.)

Example: Given $h = 1$ in., $R_{min} = 2.9$ in., and $\beta = 60°$. Find ρ_{min} for parabolic motion, simple harmonic motion, and cycloidal motion.

Solution: $\rho_{min} = 2.02$ in. for parabolic motion, from Equation (10)
$\rho_{min} = 1.8$ in. for simple harmonic motion, from Equation (10)
$\rho_{min} = 1.6$ in. for cycloidal motion, from Equation (13d)

The value of ρ_{min} on *any* cam may also be obtained by measurement on the layout of the cam using a compass.

Cam Forces, Contact Stresses, and Materials.— After a cam and follower configuration has been determined, the forces acting on the cam may be calculated or otherwise determined. Next, the stresses at the cam surface are calculated and suitable materials to withstand the stress are selected. If the calculated maximum stress is too great, it will be necessary to change the cam design.

Such changes may include: 1) increasing the cam size to decrease pressure angle and increase the radius of curvature; 2) changing to an offset or swinging follower to reduce the pressure angle; 3) reducing the cam rotation speed to reduce inertia forces; 4) increasing the cam rise angle, β, during which the rise, h, occurs; 5) increasing the thickness of the cam, provided that deflections of the follower are small enough to maintain uniform loading across the width of the cam; and 6) using a more suitable cam curve or modifying the cam curve at critical points.

Although parabolic motion seems to be the best with respect to minimizing the calculated maximum acceleration and, therefore, also the maximum acceleration forces, nevertheless, in the case of high speed cams, cycloidal motion yields the lower maximum acceleration forces. Thus, it can be shown that owing to the sudden change in acceleration (called *jerk* or *pulse*) in the case of parabolic motion, the actual forces acting on the cam are doubled and sometimes even tripled at high speed, whereas with cycloidal motion, owing to the gradually changing acceleration, the actual dynamic forces are only slightly higher than the theoretical. Therefore, the calculated force due to acceleration should be multiplied by at least a factor of 2 for parabolic and 1.05 for cycloidal motion to provide an allowance for the load-increasing effects of elasticity and backlash.

The main factors influencing cam forces are: 1) displacement and cam speed (forces due to acceleration); 2) dynamic forces due to backlash and flexibility; 3) linkage dimensions which affect weight and weight distribution; 4) pressure angle and friction forces; and 5) spring forces.

The main factors influencing stresses in cams are: 1) radius of curvature for cam and roller; and 2) materials.

Acceleration Forces: The formula for the force acting on a translating body given an acceleration a is:

$$R = \frac{Wa}{g} = \frac{Wa}{386} \quad (14)$$

In this formula, $g = 386$ inches/second squared, a = acceleration of W in inches/second squared; R = resultant of all the external forces (except friction) acting on the weight W. For cam analysis purposes, W, in pounds, consists of the weight of the follower, a portion of the

Copyright 2004, Industrial Press, Inc., New York, NY

weight of the return spring (⅓), and the weight of the members of the external mechanism against which the follower pushes, for example, the weight of a piston:

$$W = W_f + \tfrac{1}{3}W_s + W_e \tag{15}$$

where W = equivalent single weight; W_f = follower weight; W_s = spring weight; and W_e = external weight, all in pounds.

Spring Forces: The return spring, K_s, shown in Fig. 21a must be strong enough to hold the follower against the cam at all times. At high cam speeds the main force attempting to separate the follower from the cam surface is the acceleration force R at the point of maximum *negative* acceleration. Thus, at that point the spring must exert a force F_s,

$$F_s = R - W_f - F_e - F_f \tag{16}$$

where F_e = external force resisting motion of follower, and F_f = friction force from follower guide bushings and other sources.

When the follower is at its lowest position (R_{min} in Fig. 21a), it is usual practice to have the spring provide some estimated preload to account for "set" that takes place in a spring after repeated use and to prevent roller sliding at the start of movement.

The required spring constant, K_s, in pounds per inch of spring deflection is:

$$K_s = \frac{F_s - \text{preload}}{y_a} \tag{17}$$

where y_a = rise of cam from R_{min} to height at which maximum negative acceleration takes place.

The force, F_y, that the spring exerts at any height y above R_{min} is:

$$F_y = yK_s + \text{preload} \tag{18}$$



Fig. 21. (a) Radial Translating Follower and Cam System (b) Force Acting on a Translating Follower

Pressure Angle and Friction Forces: As shown in Fig. 21b, the pressure angle of the cam causes a sideways component $F_n \sin \alpha$ which produces friction forces μF_1 and μF_2 in the guide bushing. If the follower rod is too flexible, bending of the follower will increase

Copyright 2004, Industrial Press, Inc., New York, NY

these friction forces. The effect of the friction forces and the pressure angle are taken into account in the formula,

$$F_n = \frac{P}{\cos\alpha - \frac{\mu \sin\alpha}{l_2}(2l_1 + l_2 - \mu d)} \quad (19a)$$

where μ = coefficient of friction in bushing; l_1, l_2, and d are as shown in Fig. 21; and P = the sum of all the forces acting down against the upward motion of the follower (acceleration force + spring force + follower weight + external force)

$$P = \frac{W \times a}{386} + (yK_s + \text{preload}) + W_f + F_e \quad (19b)$$

Cam Torque: The follower pressing against the cam causes resisting torques during the rise period and assisting torques during the return period. The maximum value of the resisting torque determines the cam drive requirements. Instantaneous torque values may be calculated from

$$T_o = \frac{30vF_n\cos\alpha}{\pi N} = (R_{\min} + y)F_n \sin\alpha \quad (20)$$

in which T_o = instantaneous torque in pound-inches.

Exampleof Force Analysis: A radial translating follower system is shown in Fig. 21a. The follower is moved with cycloidal motion over a distance of 1 in. and an angle of lift $\beta = 100°$. Cam speed $N = 900$ rpm. The weight of the follower mass, W_f, is 2 pounds. Both the spring weight W_s and the external weight W_e are negligible. The follower stem diameter is 0.75 in., $l_1 = 1.5$ in., $l_2 = 4$ in., coefficient of friction $\mu = 0.05$, external force $F_e = 10$ lbs, and the pressure angle is not to exceed 30°.

(a) What is the smallest radius $R_{\min}$ to the pitch curve?

From Formula (9b) the rise angle ϕ_p to where the maximum pressure angle α_{max} exists is:

$$\phi_p = \frac{\beta}{180°}\left[\text{arccot}\left(\frac{\beta \tan\alpha_{\max}}{360°}\right)\right] = \frac{100°}{180°}\left[\text{arccot}\left(\frac{100° \times \tan 30°}{360°}\right)\right]$$
$$= 44.94° = 45°$$

From Formula (9c) the radius, $R_{\alpha\,max}$, at which the angle of rise is ϕ_p is:

$$R_{\alpha\max} = \frac{h}{2\pi}\frac{[1 - \cos(360°\phi_p/\beta)]^2}{\sin(360°\phi_p/\beta)} = \frac{1}{2\pi}\frac{[1 - \cos[(360° \times 45°)/100°]]^2}{\sin[(360° \times 45°)/100°]} = 1.96 \text{ in.}$$

From Formula (9d), $R_{\min}$ is given by

$$R_{\min} = R_{\alpha\max} - h\left[\frac{\phi_p}{\beta} - \frac{1}{2\pi}\sin\left(\frac{360°\phi_p}{\beta}\right)\right]$$
$$= 1.96 - 1 \times \left[\frac{45°}{100°} - \frac{1}{2\pi}\sin\left(\frac{360° \times 45°}{100°}\right)\right] = 1.560 \text{ in.}$$

The same results could have been obtained graphically. If this $R_{\min}$ is too small, i.e., if the cam bore and hub require a larger cam, then $R_{\min}$ can be increased, in which case the maximum pressure angle will be less than 30°.

(b) If the return spring K_s is specified to provide a preload of 36 lbs when the follower is at $R_{\min}$, what is the spring constant required to hold the follower on the cam throughout the cycle?

Copyright 2004, Industrial Press, Inc., New York, NY

The follower tends to leave the cam at the point of maximum *negative* acceleration. Fig. 7 shows this to be at $\phi = \frac{3}{4}\beta = 75°$.

From Formula (4c),

$$a = \frac{2\pi h\omega^2}{\beta^2}\sin\left(\frac{360°\phi}{\beta}\right) = \frac{2\pi \times 1 \times (6 \times 900)^2}{(100°)^2}\sin\left(\frac{360° \times 75°}{100°}\right) = -18{,}300 \text{ in./sec}^2$$

From Formulas (14) and (15),

$$R = \frac{Wa}{386} = \frac{(W_f + \frac{1}{3}W_s + W_e)a}{386} = \frac{(2 + 0 + 0)(-18{,}300)}{386} = 95 \text{ lbs (upward)}$$

Using Formula (16) to determine the spring force F_s to hold the follower on the cam,

$$F_s = R - W_f - F_e - F_f$$

as stated on page 2205, the value of R in the above formula should be multiplied by 1.05 for cycloidal motion to provide a factor of safety for dynamic pulses. Thus,

$$F_s = 1.05R - W_f - F_e - F_f = 1.05 \times 95 - 2 - 10 - 0 = 88 \text{ lbs (downward)}$$

The spring constant from Formula (17) is:

$$K_s = \frac{F_s - \text{preload}}{y_a} = \frac{88 - 36}{y_a}$$

and, from Formula (4a) y_a is:

$$y_a = h\left[\frac{\phi}{\beta} - \frac{1}{2\pi}\sin\left(\frac{360°\phi}{\beta}\right)\right] = 1 \times \left[\frac{75°}{100°} - \frac{1}{2\pi}\sin\left(\frac{360° \times 75°}{100°}\right)\right] = 0.909 \text{ in.}$$

so that $K_s = (88 - 36)/0.909 = 57$ lb/in.

(c) At the point where the pressure angle α_{max} is 30° ($\phi = 45°$) the rise of the follower is 1.96 – 1.56 = 0.40 in. What is the normal force, F_n, on the cam? From Formulas (19a) and (19b)

$$F_n = \frac{Wa/386 + yK_s + \text{preload} + W_f + F_e}{\cos\alpha - \frac{\mu\sin\alpha}{l_2}(2l_1 + l_2 - \mu d)}$$

using $\phi = 45°$, $h = 1$ in., $\beta = 100°$, and $\omega = 6 \times 900$ in Formula (4c) gives $a = 5660$ in./sec^2. So that, with $W = 2$ lbs, $y = 0.4$, $K_s = 57$, preload = 36 lbs, $W_f = 2$ lbs, $F_e = 10$ lbs, $\alpha = 30°$, $\mu = 0.05$, $l_1 = 1.5$, $l_2 = 4$, and $d = 0.75$,

$$F_n = \frac{(2 \times 5660)/386 + 0.4 \times 57 + 36 + 2}{\cos 30° - \frac{0.05 \times \sin 30°}{4}(2 \times 1.5 + 4 - 0.05 \times 0.75)} = 110 \text{ lbs}$$

Note: If the coefficient of friction had been assumed to be 0, then $F_n = 104$; on the other hand, if the follower is too flexible, so that sidewise bending occurs causing jamming in the bushing, the coefficient of friction may increase to, say, 0.5, in which case the calculated $F_n = 200$ lbs.

(d) Assuming that in the manufacture of this cam that an error or "bump" resulting from a chattermark or as a result of poor blending occurred, and that this "bump" rose to a height of 0.001 in. in a 1° rise of the cam in the vicinity of $\phi = 45°$. What effect would this bump have on the acceleration force R?

One formula that may be used to calculate the change in acceleration caused by such a cam error is:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\Delta a = \pm 2e\left(\frac{6N}{\Delta\phi}\right)^2 \quad (21)$$

where Δa = change in acceleration,

e = error in inches,

$\Delta\phi$ = width of error in degrees. The plus (+) sign is used for a "bump" and the minus (−) sign for a dent or hollow in the surface

For $e = 0.001$, $\Delta\phi = 1°$, and $N = 900$ rpm,

$$\Delta a = +2 \times 0.001\left(\frac{6 \times 900}{1°}\right)^2 = 58{,}320 \text{ in./sec}^2$$

which is 10 times the acceleration calculated for a perfect cam and would cause sufficient force F_n to damage the cam surface. On high speed cams, therefore, accuracy is of considerable importance.

(e) What is the cam torque at $\phi = 45°$?

From Formula (20),

$$T_o = (R_{\min} + y)F_n \sin\alpha$$
$$= (1.56 + 0.4) \times 110 \times \sin 30° = 108 \text{ in.-lbs}$$

(f) What is the radius of curvature at $\phi = 45°$?

From Formula (10),

$$\rho = \frac{\left[r^2 + \left(\frac{dr}{d\phi}\right)^2\right]^{3/2}}{r^2 + 2\left(\frac{dr}{d\phi}\right)^2 - r\left(\frac{d^2r}{d\phi^2}\right)}$$

$$r = R_{\min} + y = 1.56 + 0.4 = 1.96$$

From Formula (13b),

$$\frac{dr}{d\phi} = \frac{180°h}{\pi\beta}\left[1 - \cos\left(\frac{360°\phi}{\beta}\right)\right] = \frac{180° \times 1}{\pi \times 100°}\left[1 - \cos\left(\frac{360° \times 45°}{100°}\right)\right]$$
$$= 1.12$$

From Formula (13c),

$$\frac{d^2r}{d\phi^2} = \frac{2(180°)^2h}{\pi\beta^2}\sin\left(\frac{360°\phi}{\beta}\right) = \frac{2 \times (180°)^2 \times 1}{\pi \times (100°)^2}\sin\left(\frac{360° \times 45°}{100°}\right)$$
$$= 0.64$$

$$\rho = \frac{[(1.96)^2 + (1.12)^2]^{3/2}}{(1.96)^2 + 2(1.12)^2 - 1.96 \times 0.64} = 2.26 \text{ in.}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Calculation of Contact Stresses.— When a roller follower is loaded against a cam, the compressive stress developed at the surface of contact may be calculated from

$$S_c = 2290\sqrt{\frac{F_n}{b}\left(\frac{1}{r_f} \pm \frac{1}{R_c}\right)} \qquad (22)$$

for a steel roller against a steel cam. For a steel roller on a cast iron cam, use 1850 instead of 2290 in Equation (22).

S_c = maximum calculated compressive stress, psi
F_n = normal load, lb
b = width of cam, inch
R_c = radius of curvature of cam surface, inch
r_f = radius of roller follower, inch

The plus sign in (21) is used in calculating the maximum compressive stress when the roller is in contact with the convex portion of the cam profile and the minus sign is used when the roller is in contact with the concave portion. When the roller is in contact with the straight (flat) portion of the cam profile, $R_c = \infty$ and $1/R_c = 0$. In practice, the greatest compressive stress is most apt to occur when the roller is in contact with that part of the cam profile which is convex and has the smallest radius of curvature.

Example: Given the previous cam example, the radius of the roller $r_f = 0.25$ in., the convex radius of the cam $R_c = (2.26–0.25)$ in., the width of contact $b = 0.3$ in., and the normal load $F_n = 110$ lbs. Find the maximum surface compressive stress. From (21),

$$S_c = 2290\sqrt{\frac{110}{0.3}\left(\frac{1}{0.25} + \frac{1}{2.01}\right)} = 93{,}000 \text{ psi}$$

This calculated stress should be less than the allowable stress for the material selected from Table 2.

Cam Materials: In considering materials for cams it is difficult to select any single material as being the best for every application. Often the choice is based on custom or the machinability of the material rather than its strength. However, the failure of a cam or roller is commonly due to fatigue, so that an important factor to be considered is the limiting wear load, which depends on the surface endurance limits of the materials used and the relative hardnesses of the mating surfaces.

Table 2. Cam Materials

Cam Materials for Use with Roller of Hardened Steel	Maximum Allowable Compressive Stress, psi
Gray-iron casting, ASTM A 48-48, Class 20, 160–190 Bhn, phosphate-coated	58,000
Gray-iron casting, ASTM A 339-51T, Grade 20, 140–160 Bhn	51,000
Nodular-iron casting, ASTM A 339-51T, Grade 80-60-03, 207–241Bhn	72,000
Gray-iron casting, ASTM A 48–48, Class 30, 200–220 Bhn	65,000
Gray-iron casting, ASTM A 48–48, Class 35, 225–225 Bhn	78,000
Gray-iron casting, ASTM A 48-48, Class 30, heat treated (Austempered), 225–300 Bhn	90,000
SAE 1020 steel, 130–150 Bhn	82,000
SAE 4150 steel, heat treated to 270–300 Bhn, phosphate coated	20,000
SAE 4150 steel, heat treated to 270–300 Bhn	188,000
SAE 1020 steel, carburized to 0.045 in. depth of case, 50–58 Rc	226,000
SAE 1340 steel, induction hardened to 45–55 Rc	198,000
SAE 4340 steel, induction hardened to 50–55 Rc	226,000

Based on United Shoe Machinery Corp. data by Guy J. Talbourdet.

Copyright 2004, Industrial Press, Inc., New York, NY

In Table 2 are given maximum permissible compressive stresses (surface endurance limits) for various cam materials when in contact with a roller of hardened steel. The stress values shown are based on 100,000,000 cycles or repetitions of stress for pure rolling. Where the repetitions of stress are considerably greater than 100,000,000, where there is appreciable misalignment, or where there is sliding, more conservative stress figures must be used.

Layout of Cylinder Cams.— In Fig. 22 is shown the development of a uniformly accelerated motion cam curve laid out on the surface of a cylindrical cam. This development is necessary for finding the projection on the cylindrical surface, as shown at *KL*. To construct the developed curve, first divide the base circle of the cylinder into, say, twelve equal parts. Set off these parts along line *ag*. Only one-half of the layout has been shown, as the other half is constructed in the same manner, except that the curve is here falling instead of rising. Divide line *aH* into the same number of divisions as the half circle, the divisions being in the proportion 1 : 3 : 5 : 5 : 3 : 1. Draw horizontal lines from these division points and vertical lines from *a*, *b*, *c*, etc. The intersections between the two sets of lines are points on the developed cam curve. These points are transferred to the cylindrical surface at the left by projection in the usual manner.



Fig. 22. Development of Cylindrical Cam

Shape of Rolls for Cylinder Cams.— The rolls for cylindrical cams working in a groove in the cam should be conical rather than cylindrical in shape, in order that they may rotate freely and without excessive friction. Fig. 23(a) shows a straight roll and groove, the action of which is faulty because of the varying surface speed at the top and bottom of the groove. Fig. 23(b) shows a roll with curved surface. For heavy work, however, the small bearing area is quickly worn down and the roll presses a groove into the side of the cam as well, thus destroying the accuracy of the movement and creating backlash. Fig. 23(c) shows the conical shape which permits a true rolling action in the groove. The amount of taper depends on the angle of spiral of the cam groove. As this angle, as a rule, is not constant for the whole movement, the roll and groove should be designed to meet the requirements on that section of the cam where the heaviest duty is performed. Frequently the cam groove is of a nearly even spiral angle for a considerable length. The method for determining the angle of the roll and groove to work correctly during the important part of the cycle is as follows:

In Fig. 23(d), *b* is the circumferential distance on the surface of the cam that includes the section of the groove for which correct rolling action is required. The throw of the cam for this circumferential movement is *a*. Line *OU* is the development of the movement of the

Copyright 2004, Industrial Press, Inc., New York, NY

cam roll during the given part of the cycle, and *c* is the movement corresponding to *b*, but on a circle the diameter of which is equal to that of the cam at the bottom of the groove. With the same throw *a* as before, the line *OV* will be the development of the cam at the bottom of the groove. *OU* then is the length of the helix traveled by the top of the roll, while *OV* is the travel at the bottom of the groove. If, then, the top width and bottom width of the groove be made proportional to *OU* and *OV*, the groove will be properly proportioned.



Fig. 23. Shape of Rolls for Cylinder Cams

Cam Milling.— Plate cams having a constant rise, such as are used on automatic screw machines, can be cut in a universal milling machine, with the spiral head set at an angle α, as shown by the illustration.



Fig. 24.

When the spiral head is set vertical, the "lead" of the cam (or its rise for one complete revolution) is the same as the lead for which the machine is geared; but when the spiral head and cutter are inclined, any lead or rise of the cam can be obtained, provided it is less than the lead for which the machine is geared, that is, less than the forward feed of the table for one turn of the spiral-head spindle. The cam lead, then, can be varied within certain limits by simply changing the inclination α of the spiral head and cutter. The following formula is for determining this angle of inclination, for a given rise of cam and with the machine geared for a lead, *L*, selected from the tables beginning on page 1967,

$$\sin\alpha = \frac{360^\circ \times r}{\phi \times L}$$

where α = angle to which index head and milling attachment are set from horizontal as shown in the accompanying diagram
r = rise of cam in given part of circumference
L = spiral lead for which milling machine is geared
ϕ = angle in which rise is required, expressed in degrees

For example, suppose a cam is to be milled having a rise of 0.125 inch in 300 degrees and that the machine is geared for the smallest possible lead, or 0.670 inch; then:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\sin\alpha = \frac{360° \times 0.125}{300° \times 0.670} = 0.2239$$

which is the sine of 12° 56′. Therefore, to secure a rise of 0.125 inch with the machine geared for 0.670 inch lead, the spiral head is elevated to an angle of 12° 56′ and the vertical milling attachment is also swiveled around to locate the cutter in line with the spiral-head spindle, so that the edge of the finished cam will be parallel to its axis of rotation. In the example given, the lead used was 0.670. A larger lead, say 0.930, could have been selected from the table on page 1967. In that case, $\alpha = 9° 17′$.

When there are several lobes on a cam, having different leads, the machine can be geared for a lead somewhat in excess of the greatest lead on the cam, and then all the lobes can be milled without changing the spiral head gearing, by simply varying the angle of the spiral head and cutter to suit the different cam leads. Whenever possible, it is advisable to mill on the under side of the cam, as there is less interference from chips; moreover, it is easier to see any lines that may be laid out on the cam face. To set the cam for a new cut, it is first turned back by operating the handle of the table feed screw, after which the index crank is disengaged from the plate and turned the required amount.

Simple Method for Cutting Uniform Motion Cams.— Some cams are laid out with dividers, machined and filed to the line; but for a cam that must advance a certain number of thousandths per revolution of spindle this method is not accurate. Cams are easily and accurately cut in the following manner.



Let it be required to make the heart cam shown in the illustration. The throw of this cam is 1.1 inch. Now, by setting the index on the milling machine to cut 200 teeth and also dividing 1.1 inch by 100, we find that we have 0.011 inch to recede from or advance towards the cam center for each cut across the cam. Placing the cam securely on an arbor, and the latter between the centers of the milling machine, and using a convex cutter set the proper distance from the center of the arbor, make the first cut across the cam. Then, by lowering the milling machine knee 0.011 inch and turning the index pin the proper number of holes on the index plate, take the next cut and so on.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINE ELEMENTS

PLAIN BEARINGS

2218 Introduction
2218 Classes of Plain Bearings
2218 Types of Journal Bearings
2221 Hydrostatic Bearings
2221 Guide Bearings
2221 Modes of Bearing Operation
2223 Methods of Retaining Bearings
2223 Methods of Sealing
2225 Hardness and Surface Finish
2226 Machining Bores
2226 Methods of Lubrication
2227 Lubricant Selection
2229 Greases and Solid Lubricants
2230 Journal or Sleeve Bearings
2230 Grooving and Oil Feeding
2231 Heat Radiating Capacity
2232 Journal Bearing Design Notation
2233 Journal Bearing Lubrication
2234 Sleeve Bearing Pressure
2239 Use of Lubrication Analysis
2242 Thrust Bearings
2243 Design Notation
2244 Flat Plate Design
2249 Step Design
2251 Tapered Land Design
2256 Tilting Pad Thrust Bearing Design
2260 Plain Bearing Materials
2260 Properties of Bearing Materials
2261 Bearing and Bushing Alloys
2262 Babbitt or White Metal Alloys
2263 Copper-Lead
2264 Leaded Bronze and Tin-Bronze
2264 Aluminum
2264 Silver
2264 Cast Iron
2265 Sintered Metal and Nonmetallic Bearings
2265 Plastics Bearings
2266 Wood
2266 Carbon-Graphite
2267 Copper- and Iron-Base Sintered Bearings

BALL, ROLLER, AND NEEDLE BEARINGS

2269 Rolling Contact Bearings
2269 Types of Anti-friction Bearings
2270 Types of Ball Bearings
2272 Types of Roller Bearings
2273 Types of Ball and Roller Thrust Bearings
2274 Types of Needle Bearings
2276 Plastics Bearings
2277 Flanged Housing Bearings
2277 Conventional Bearing Materials
2277 Cage Materials
2277 Method of Bearing Designation
2278 Bearing Tolerances
2279 Ball aand Roller Bearings
2283 Thrust Bearings
2285 Needle Roller Bearings
2286 Shaft and Housing Fits
2291 Design and Installation
2291 Needle Roller Bearing Fitting
2294 Bearing Mounting Practice
2295 Alignment Tolerances
2295 Squareness and Alignment
2296 Soft Metal and Resilient Housings
2297 Quiet or Vibration-free Mountings
2297 General Mounting Precautions
2297 Seating Fits for Bearings
2297 Clamping and Retaining Methods
2302 Bearing Closures
2302 Bearing Fits
2302 Design Considerations
2302 Friction Losses
2303 Selection of Ball and Roller Bearings
2304 Method of Lubrication
2305 Type of Mounting
2305 Radial and Axial Clearance
2306 Bearing Handling Precautions
2307 Bearing Failures and Deficiencies
2307 Load Ratings and Fatigue Life
2307 Ball and Roller Bearing Life
2308 Ball Bearing Types Covered
2308 Limitations for Ball Bearings
2309 Ball Bearing Rating Life
2313 Roller Bearing Types Covered
2314 Roller Bearing Rating Life
2318 Life Adjustment Factors
2319 Ball Bearing Static Load Rating
2322 Equivalent Load

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINE ELEMENTS

STANDARD METAL BALLS

2324 Standard Metal Balls
2324 Definitions and Symbols
2325 Preferred Ball Gages
2328 Preferred Ball Sizes
2330 Number of Metal Balls per Pound
2331 Number of Metal Balls per Kg

LUBRICANTS AND LUBRICATION

2332 Lubricating Oils
2333 Types of Oils
2333 Viscosity
2334 Specific Gravity of Oils
2334 Application of Lubricating Oils
2335 Lubrication Systems
2336 Oil Mist Systems
2337 Lubricating Greases
2337 Grease Classifications
2337 Types of Grease
2338 Temperature Effects on Grease Life
2338 Relubricating with Grease
2339 Solid Film Lubricants
2339 Anti-friction Bearing Lubrication
2342 Aerodynamic Lubrication
2342 Elastohydrodynamic Lubrication
2345 Viscosity-pressure relationship

COUPLINGS AND CLUTCHES

2346 Connecting Shafts
2346 Safety Flange Coupling
2347 Interference Fits
2347 Double-cone Clamping Couplings
2348 Flexible Couplings
2348 The Universal Joint
2349 Knuckle Joints
2349 Friction Clutches
2350 Proportions of Knuckle Joints
2351 Cast-iron Friction Clutches
2351 Formulas for Cone Clutches
2353 Magnetic Clutches
2353 Slipping Clutch/Couplings
2353 Wrapped-spring Clutches
2354 Positive Clutches
2355 Cutting Clutch Teeth

FRICTION BRAKES

2358 Formulas for Band Brakes
2360 Coefficient of Friction in Brakes
2361 Formulas for Block Brakes

KEYS AND KEYSEATS

2363 Keys and Keyseats
2363 Key Size Versus Shaft Diameter
2366 Plain and Gib Head Keys
2367 Fits for Parallel and Taper Keys
2368 Key Chamfer
2368 Keyseat Tolerances for Electric Motor
2368 Set Screws for Use Over Keys
2368 Woodruff Keys and Keyseats
2369 Woodruff Keys
2371 Keyseat Dimensions
2374 Depths for Milling Keyseats
2374 Depth of Keyseat
2374 Cotters
2374 British Keys and Keyways
2374 Metric Keys and Keyways
2380 Preferred Lengths of Metric Keys
2381 Parallel Keys, Keyways, and Keybars
2383 Taper Keys and Keyways
2385 Dimensions and Tolerances
2385 Woodruff Keys and Keyways
2387 Preferred Lengths of Plain and Gib-head Keys

FLEXIBLE BELTS AND SHEAVES

2388 Calculations for Belts and Pulleys
2388 Diameters and Drive Ratios
2388 Wrap Angles and Center Distances
2388 Center Distances and Belt Length
2389 Pulley Diameters and Speeds
2390 Pulley Speed in Compound Drive
2390 Belt Length in Three Pulleys
2391 Power Transmitted By Belts
2391 Measuring the Effective Length
2391 Flat Belting
2393 Narrow V-Belts
2394 Standard Effective Lengths
2395 Sheave and Groove Dimensions
2397 Sheave Outside Diameters
2398 Cross Section Correction Factors
2399 Length Correction Factors

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINE ELEMENTS

FLEXIBLE BELTS AND SHEAVES

(Continued)

2399 Classical V-Belts
2400 Standard Datum Length
2401 Sheave and Groove Dimensions
2405 Length Correction Factors
2406 Double V-Belts
2407 Sheave and Groove Dimensions
2410 Terms for Calculations
2411 Allowable Tight Side Tension
2414 Tension Ratio/Arc of Contact Factors
2414 Light Duty V-Belts
2414 Belt Cross Sections
2414 Belt Size Designation
2415 V-Belt Standard Dimensions
2416 Sheave and Groove Dimensions
2417 Combined Correction Factors
2417 V-Ribbed Belts
2417 Nominal Dimensions
2418 Sheave and Groove Dimensions
2420 Standard Effective Lengths
2421 Length Correction Factors
2421 Arc of Contact Correction Factors
2422 Speed Ratio Correction Factors
2422 Variable Speed Belts
2422 Normal Dimensions
2423 Standard Belt Lengths
2424 Sheave and Groove Dimensions
2427 Speed Ratio Correction Factors
2428 Length Correction Factors
2429 Arc of Contact Correction Factors
2429 60 Degree V-Belts
2429 SAE Standard V-Belts
2429 SAE Belt and Pulley Dimensions
2429 Belt Storage and Handling
2431 Service Factors for V-belts
2432 Synchronous Belts
2433 Synchronous Belt Service Factors
2434 Nominal Tooth and Section Dimensions
2434 Pulley and Flange Dimensions
2435 Pitch Lengths and Tolerances
2436 Widths and Tolerances
2437 Pulley Diameters
2438 Pulley Tolerances
2439 Teeth in Mesh Factor
2440 Torque Rating
2440 Belt Width Factor

TRANSMISSION CHAINS

2441 Types of Chains
2441 Types of Roller Chains
2442 Roller Chain Parts
2443 Transmission Roller Chain
2443 Dimensions and Loads
2443 ANSI Dimensions
2444 Roller Chain Numbers
2444 Types of Sprockets
2445 Attachments
2445 Straight and Bent Link Plate
2446 Sprocket Classes
2446 Keys, Keyways, and Set Screws
2446 Sprocket Diameters
2448 Tolerances on the Caliper Diameter
2449 Profile Dimension
2450 Proportions of Sprockets
2450 Proportions of Single-Strand
2450 Bar-steel Sprockets
2451 Chain and Sprockets
2451 Selection of Chain and Sprockets
2451 Power Ratings for Roller Chain
2456 Maximum Bore and Hub Diameter
2456 Center Distance between Sprockets
2457 Center Distance of Chain Length
2457 Idler Sprockets
2457 Length of Driving Chain
2458 Tooth Form for Roller Chain
2459 Standard Hob Design
2460 Cutting Sprocket Tooth Form
2460 Standard Space Cutters
2461 Space Cutter Sizes
2461 Sprocket Materials
2462 Roller Chain Drive Ratings
2462 Service Factors
2463 Lubrication
2463 Installation and Alignment
2464 Design Procedure

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MACHINE ELEMENTS

STANDARDS FOR ELECTRIC MOTORS

2465 Classes of NEMA Standards
2465 Mounting Dimensions
2465 Integral-horsepower Motors
2466 Locked-rotor Torque
2467 Torque and Current Definitions
2467 Direction of Motor Rotation
2468 Pull-up Torque
2468 Types of Motors
2469 Shunt-wound Motor Drive
2470 Compound-wound Motors
2470 Types of Polyphase AC Motors
2470 Squirrel-cage Induction Motor
2471 Multiple-Speed Induction Motors
2471 Wound-Rotor Induction Motors
2471 High-Frequency Induction Motors
2471 Synchronous Motors
2472 Alternating-Current Motors
2473 Speed Reducers
2473 Factors Governing Motor Selection
2473 Speed, Horsepower, Torque and Inertia Requirements
2474 Space Limitations in Motor Selection
2476 Applications of DC Motors
2477 Polyphase AC Motors
2478 Electric Motor Maintenance

ADHESIVES AND SEALANTS

2480 Bonding Adhesives
2481 Two-Component Mix Adhesives
2483 Retaining Compounds
2484 Threadlocking
2484 Sealants
2485 Tapered Pipe-thread Sealing
2486 Anaerobic Pipe Sealants

MOTION CONTROL

2487 Control Systems
2488 Control Motor Types
2490 Controllers
2490 Control Function
2491 Electromechanical Control Systems
2491 Mechanical Stiffness
2492 Torsional Vibration
2492 Electric Motors
2493 Stepper Motors
2493 Gearing

MOTION CONTROL

(Continued)

2494 Feedback Transducers
2495 Analog Transducers
2495 Synchros and Resolvers
2495 Hydraulic and Pneumatic Systems
2496 Hydraulic Pumps
2496 Hydraulic Fluids
2499 Proportional Control Systems
2500 Electronic Controls
2500 Pneumatic Systems

O-RINGS

2503 Gland Depth
2505 Clearances and Groove Sizes
2506 Typical O-Ring Compounds
2507 Ring Materials

ROLLED STEEL SECTIONS, WIRE, AND SHEET-METAL GAGES

2508 Rolled Steel Sections
2508 Angles Bent to Circular Shape
2508 Hot-Rolled Structural Steel
2509 Steel Wide-Flange
2513 Steel S Sections
2514 Steel Channels
2515 Steel Angles with Equal Legs
2516 Angles with Unequal Legs
2518 Aluminum Structural Shapes
2519 Wire and Sheet-Metal Gages
2519 Wire Gages
2519 Wall Thicknesses of Tubing
2521 Properties of Perforated Materials
2522 Sheet-Metal Gages
2523 Flat Metal Products
2524 Preferred Metric Thicknesses
2525 Letter and Number Drills

PIPE AND PIPE FITTINGS

2526 Wrought Steel Pipe
2527 Weights and Dimensions
2529 Properties of Schedule Pipe
2531 Volume of Flow
2532 Plastics Pipe
2532 Dimensions and Weights
2533 Properties and Uses
2534 Temperature-Correction Factors
2535 Pipe and Tube Bending
2535 Definitions of Pipe Fittings

Copyright 2004, Industrial Press, Inc., New York, NY

PLAIN BEARINGS

Introduction

On the following pages are given data and procedures for designing full-film or hydrodynamically lubricated bearings of the journal and thrust types. However, before proceeding to these design methods, it is thought useful to first review those bearing aspects concerning the types of bearings available; lubricants and lubrication methods; hardness and surface finish; machining methods; seals; retainers; and typical length-to-diameter ratios for various applications.

The following paragraphs preceding the design sections provide guidance in these matters and suggest modifications in allowable loads when other than full-film operating conditions exist in a bearing.

Classes of Plain Bearings.— Bearings that provide sliding contact between mating surfaces fall into three general classes: *radial bearings* that support rotating shafts or journals; *thrust bearings* that support axial loads on rotating members; and *guide* or *slipper bearings* that guide moving parts in a straight line. Radial sliding bearings, more commonly called sleeve bearings, may be of several types, the most usual being the plain full journal bearing, which has 360-degree contact with its mating journal, and the partial journal bearing, which has less than 180-degree contact. This latter type is used when the load direction is constant and has the advantages of simplicity, ease of lubrication, and reduced frictional loss.

The relative motions between the parts of plain bearings may take place:1) as pure sliding without the benefit of a liquid or gaseous lubricating medium between the moving surfaces such as with the dry operation of nylon or Teflon; 2) with hydrodynamic lubrication in which a wedge or film buildup of lubricating medium is produced, with either whole or partial separation of the bearing surfaces; 3) with hydrostatic lubrication in which a lubricating medium is introduced under pressure between the mating surfaces causing a force opposite to the applied load and a lifting or separation of these surfaces; and 4) with a hybrid form or combination of hydrodynamic and hydrostatic lubrication.

Listed below are some of the advantages and disadvantages of sliding contact (plain) bearings as compared with rolling contact (antifriction) bearings.

Advantages: 1) require less space; 2) are quieter in operation; 3) are lower in cost, particularly in high-volume production; 4) have greater rigidity; and 5) their life is generally not limited by fatigue.

Disadvantages: 1) have higher frictional properties resulting in higher power consumption; 2) are more susceptible to damage from foreign material in lubrication system; 3) have more stringent lubrication requirements; and 4) are more susceptible to damage from interrupted lubrication supply.

Types of Journal Bearings.— Many types of journal bearing configurations have been developed; some of these are shown in Fig. 1.

Circumferential-groove bearings, Fig. 1(a), have an oil groove extending circumferentially around the bearing. The oil is maintained under pressure in the groove. The groove divides the bearing into two shorter bearings that tend to run at a slightly greater eccentricity. However, the advantage in terms of stability is slight, and this design is most commonly used in reciprocating-load main and connecting-rod bearings because of the uniformity of oil distribution.

Short cylindrical bearings are a better solution than the circumferential-groove bearing for high-speed, low-load service. Often the bearing can be shortened enough to increase the unit loading to a substantial value, causing the shaft to ride at a position of substantial eccentricity in the bearing. Experience has shown that instability rarely results when the shaft eccentricity is greater than 0.6. Very short bearings are not often used for this type of

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Typical shapes of several types of pressure-fed bearings.

application, because they do not provide a high temporary rotating-load capacity in the event some unbalance should be created in the rotor during service.

Copyright 2004, Industrial Press, Inc., New York, NY

Cylindrical-overshot bearings, Fig. 1(b), are used where surface speeds of 10,000 fpm or more exist, and where additional oil flow is desired to maintain a reasonable bearing temperature. This bearing has a wide circumferential groove extending from one axial oil groove to the other over the upper half of the bearing. Oil is usually admitted to the trailing-edge oil groove. An inlet orifice is used to control the oil flow. Cooler operation results from the elimination of shearing action over a large section of the upper half of the bearing and, to a great extent, from the additional flow of cool oil over the top half of the bearing.

Pressure bearings, Fig. 1(c), employ a groove over the top half of the bearing. The groove terminates at a sharp dam about 45 degrees beyond the vertical in the direction of shaft rotation. Oil is pumped into this groove by shear action from the rotation of the shaft and is then stopped by the dam. In high-speed operation, this situation creates a high oil pressure over the upper half of the bearing. The pressure created in the oil groove and surrounding upper half of the bearing increases the load on the lower half of the bearing. This self-generated load increases the shaft eccentricity. If the eccentricity is increased to 0.6 or greater, stable operation under high-speed, low-load conditions can result. The central oil groove can be extended around the lower half of the bearing, further increasing the effective loading. This design has one primary disadvantage: Dirt in the oil will tend to abrade the sharp edge of the dam and impair ability to create high pressures.

Multiple-groove bearings, Fig. 1(d), are sometimes used to provide increased oil flow. The interruptions in the oil film also appear to give this bearing some merit as a stable design.

Elliptical bearings, Fig. 1(e), are not truly elliptical, but are formed from two sections of a cylinder. This two-piece bearing has a large clearance in the direction of the split and a smaller clearance in the load direction at right angles to the split. At light loads, the shaft runs eccentric to both halves of the bearing, and hence, the elliptical bearing has a higher oil flow than the corresponding cylindrical bearing. Thus, the elliptical bearing will run cooler and will be more stable than a cylindrical bearing.

Elliptical-overshot bearings (not shown) are elliptical bearings in which the upper half is relieved by a wide oil groove connecting the axial oil grooves. They are analogous to cylindrical-overshot bearings.

Displaced elliptical bearings, Fig. 1(f), shift the centers of the two bearing arcs in both a horizontal and a vertical direction. This design has greater stiffness than a cylindrical bearing, in both horizontal and vertical directions, with substantially higher oil flow. It has not been extensively used, but offers the prospect of high stability and cool operation.

Three-lobe bearings, Fig. 1(g), are made up in cross section of three circular arcs. They are most effective as antioil whip bearings when the centers of curvature of each of the three lobes lie well outside the clearance circle that the shaft center can describe within the bearing. Three axial oil-feed grooves are used. It is a more difficult design to manufacture, because it is almost necessary to make it in three parts instead of two. The bore is machined with shims between each of the three parts. The shims are removed after machining is completed.

Pivoted-shoe bearings, Fig. 1(h), are one of the most stable bearings. The bearing surface is divided into three or more segments, each of which is pivoted at the center. In operation, each shoe tilts to form a wedge-shaped oil film, thus creating a force tending to push the shaft toward the center of the bearing. For single-direction rotation, the shoes are sometimes pivoted near one end and forced toward the shaft by springs.

Nutcracker bearings, Fig. 1(i), consist of two cylindrical half-bearings. The upper half-bearing is free to move in a vertical direction and is forced toward the shaft by a hydraulic cylinder. External oil pressure may be used to create load on the upper half of the bearing through the hydraulic cylinder. Or the high-pressure oil may be obtained from the lower half of the bearing by tapping a hole into the high-pressure oil film, thus creating a self-loading bearing. Either type can increase bearing eccentricity to the point where stable operation can be achieved.

Copyright 2004, Industrial Press, Inc., New York, NY

Hydrostatic Bearings.— Hydrostatic bearings are used when operating conditions require full film lubrication that cannot be developed hydrodynamically. The hydrostatically lubricated bearing, either thrust or radial, is supplied with lubricant under pressure from an external source. Some advantages of the hydrostatic bearing over bearings of other types are: low friction; high load capacity; high reliability; high stiffness; and long life.

Hydrostatic bearings are used successfully in many applications including machine tools, rolling mills, and other heavily loaded slow-moving machinery. However, specialized techniques, including a thorough understanding of hydraulic components external to the bearing package is required. The designer is cautioned against use of this type of bearing without a full knowledge of all aspects of the problem. Determination of the operating performance of hydrostatic bearings is a specialized area of the lubrication field and is described in specialized reference books.

Guide Bearings.— This type of bearing is generally used as a positioning device or as a guide to linear motion such as in machine tools. Fig. 2 shows several examples of guideway bearing designs. It is normal for this type of bearing to operate in the boundary lubrication region with either dry, dry film such as molybdenum disulfide (MoS_2) or tetrafluorethylene (TFE), grease, oil, or gaseous lubrication. Hydrostatic lubrication is often used to improve performance, reduce wear, and increase stability. This type of design uses pumps to supply air or gas under pressure to pockets designed to produce a bearing film and maintain complete separation of the sliding surfaces.



Fig. 2. Types of Guide Bearings

Design.— The design of a sliding bearing is generally accomplished in one of two ways: 1) a bearing operating under similar conditions is used as a model or basis from which the new bearing is designed; and 2) in the absence of any previous experience with similar bearings in similar environments, certain assumptions concerning operating conditions and requirements are made and a tentative design prepared based on general design parameters or rules of thumb. Detailed lubrication analysis is then performed to establish design and operating details and requirements.

Modes of Bearing Operation.— The load-carrying ability of a sliding bearing depends upon the kind of fluid film that is formed between its moving surfaces. The formation of this film is dependent, in part, on the design of the bearing and, in part, on the speed of rotation. The bearing has three modes or regions of operation designated as *full-film, mixed-film,* and *boundary* lubrication with effects on bearing friction, as shown in Fig. 3.

In terms of physical bearing operation these three modes may be further described as follows:

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Three modes of bearing operation.

1) Full-film, or hydrodynamic, lubrication produces a complete physical separation of the sliding surfaces resulting in low friction and long wear-free service life.

To promote full-film lubrication in hydrodynamic operation, the following parameters should be satisfied: a) Lubricant selected has the correct viscosity for the proposed operation; b) proper lubricant flow rates are maintained; c) proper design methods and considerations have been utilized; and d) surface velocity in excess of 25 feet per minute is maintained.

When full-film lubrication is achieved, a coefficient of friction between 0.001 and 0.005 can be expected.

2) Mixed-film lubrication is a mode of operation between the full-film and boundary modes. With this mode, there is a partial separation of the sliding surfaces by the lubricant film; however, as in boundary lubrication, limitations on surface speed and wear will result. With this type of lubrication, a surface velocity in excess of 10 feet per minute is required with resulting coefficients of friction of 0.02 to 0.08.

3) Boundary lubrication takes place when the sliding surfaces are rubbing together with only an extremely thin film of lubricant present. This type of operation is acceptable only in applications with oscillating or slow rotary motion. In complete boundary lubrication, the oscillatory or rotary motion is usually less than 10 feet per minute with resulting coefficients of friction of 0.08 to 0.14. These bearings are usually grease lubricated or periodically oil lubricated.

In starting up and accelerating to its operating point, a journal bearing passes through all three modes of operation. At rest, the journal and bearing are in contact, and thus when starting, the operation is in the boundary lubrication region. As the shaft begins to rotate

Copyright 2004, Industrial Press, Inc., New York, NY

more rapidly and the hydrodynamic film starts to build up, bearing operation enters the region of mixed-film lubrication. When design speeds and loads are reached, the hydrodynamic action in a properly designed bearing will promote full-film lubrication.

Methods of Retaining Bearings.— Several methods are available to ensure that a bearing remains in place within a housing. Which method to use depends upon the particular application but requires first that the unit lends itself to convenient assembly and disassembly; additionally, the bearing wall should be of uniform thickness to avoid introduction of weak points in the construction that may lead to elastic or thermal distortion.

Press or Shrink Fit: One common and satisfactory technique for retaining the bearing is to press or shrink the bearing in the housing with an interference fit. This method permits the use of bearings having uniform wall thickness over the entire bearing length.

Standard bushings with finished inside and outside diameters are available in sizes up to approximately 5 inches inside diameter. Stock bushings are commonly provided 0.002 to 0.003 inch over nominal on outside diameter sizes of 3 inches or less. For diameters greater than 3 inches, outside diameters are 0.003 to 0.005 inch over nominal. Because these tolerances are built into standard bushings, the amount of press fit is controlled by the housing-bore size.

As a result of a press or shrink fit, the bore of the bearing material "closes in" by some amount. In general, this diameter decrease is approximately 70 to 100 per cent of the amount of the interference fit. Any attempt to accurately predict the amount of reduction, in an effort to avoid final clearance machining, should be avoided.

Shrink fits may be accomplished by chilling the bearing in a mixture of dry ice and alcohol, or in liquid air. These methods are easier than heating the housing and are preferred. Dry ice in alcohol has a temperature of −110 degrees F and liquid air boils at −310 degrees F.

When a bearing is pressed into the housing, the driving force should be uniformly applied to the end of the bearing to avoid upsetting or peening of the bearing. Of equal importance, the mating surfaces must be clean, smoothly finished, and free of machining imperfections.

Keying Methods: A variety of methods can be used to fix the position of the bearing with respect to its housing by "keying" the two together. Possible keying methods are shown in Figs. 4a through 4f including: a) set screws; b) Woodruff keys; c) bolted bearing flanges; d) threaded bearings; e) dowel pins; and f) housing caps.

Factors to be considered when selecting one of these methods are as follows:

1) Maintaining uniform wall thickness of the bearing material, if possible, especially in the load-carrying region of the bearing.

2) Providing as much contact area as possible between bearing and housing. Mating surfaces should be clean, smooth, and free from imperfections to facilitate heat transfer.

3) Preventing any local deformation of the bearing that might result from the keying method. Machining after keying is recommended.

4) Considering the possibility of bearing distortion resulting from the effect of temperature changes on the particular keying method.

Methods of Sealing.— In applications where lubricants or process fluids are utilized in operation, provision must be made normally to prevent leakage to other areas. This provision is made by the use of static and dynamic type sealing devices. In general, three terms are used to describe the devices used for sealing:

Seal: A means of preventing migration of fluids, gases, or particles across a joint or opening in a container.

Packing: A dynamic seal, used where some form of relative motion occurs between rigid members of an assembly.

Gaskets: A static seal, used where there is no relative motion between joined parts.

Copyright 2004, Industrial Press, Inc., New York, NY

Methods of Bearing Retention



Fig. 4a. Set Screws



Fig. 4b. Woodruff Key



Fig. 4c. Bolts through Flange



Fig. 4d. Bearing Screwed into Housing



Fig. 4e. Dowel Pin



Fig. 4f. Housing Cap

Two major functions must be achieved by all sealing applications: prevent escape of fluid; and prevent migration of foreign matter from the outside.

The first determination in selecting the proper seal is whether the application is static or dynamic. To meet the requirements of a static application there must be no relative motion between the joining parts or between the seal and the mating part. If there is any relative motion, the application must be considered dynamic, and the seal selected accordingly.

Dynamic sealing requires control of fluids leaking between parts with relative motion. Two primary methods are used to this end: positive contact or rubbing seals; and controlled clearance noncontact seals.

Positive Contact or Rubbing Seals: These seals are used where positive containment of liquids or gases is required, or where the seal area is continuously flooded. If properly selected and applied, contact seals can provide zero leakage for most fluids. However, because they are sensitive to temperature, pressure, and speed, improper application can result in early failure. These seals are applicable to rotating and reciprocating shafts. In many assemblies, positive-contact seals are available as off-the-shelf items. In other instances, they are custom-designed to the special demands of a particular application. Custom design is offered by many seal manufacturers and, for extreme cases, probably offers the best solution to the sealing problem.

Controlled Clearance Noncontact Seals: Representative of the controlled-clearance seals, which includes all seals in which there is no rubbing contact between the rotating and

Copyright 2004, Industrial Press, Inc., New York, NY

stationary members, are throttling bushings and labyrinths. Both types operate by fluid-throttling action in narrow annular or radial passages.

Clearance seals are frictionless and very insensitive to temperature and speed. They are chiefly effective as devices for limiting leakage rather than stopping it completely. Although they are employed as primary seals in many applications, the clearance seal also finds use as auxiliary protection in contact-seal applications. These seals are usually designed into the equipment by the designer himself, and they can take on many different forms.

Advantages of this seal are that friction is kept to an absolute minimum and there is no wear or distortion during the life of the equipment. However, there are two significant disadvantages: The seal has limited use when leakage rates are critical; and it becomes quite costly as the configuration becomes elaborate.

Static Seals: Static seals such as gaskets, "O" rings, and molded packings cover very broad ranges of both design and materials.

Some of the typical types are as follows: 1) Molded packings: a) lip type, and b) squeeze-molded; 2) simple compression packings; 3) diaphragm seals; 4) nonmetallic gaskets; 5) "O" rings; and 6) metallic gaskets and "O" rings.

Data on "O" rings are found starting on page 2502.

Detailed design information for specific products should be obtained directly from manufacturers.

Hardness and Surface Finish.— Even in well-lubricated full-film sleeve bearings, momentary contact between journal and bearing may occur under such conditions as starting, stopping, or overloading. In mixed-film and boundary-film lubricated sleeve bearings, continuous metal-to-metal contact occurs. Hence, to allow for any necessary wearing-in, the journal is usually made harder than the bearing material. This arrangement allows the effects of scoring or wearing to take place on the bearing, which is more easily replaced, rather than on the more expensive shaft. As a general rule, recommended Brinell (Bhn) hardness of the journal is at least 100 points harder than the bearing material.

The softer cast bronzes used for bearings are those with high lead content and very little tin. Such bronzes give adequate service in boundary-and mixed-film applications where full advantage is taken of their excellent "bearing" characteristics.

High-tin, low-lead content cast bronzes are the harder bronzes and these have high ultimate load-carrying capacity: higher journal hardnesses are required with these bearing bronzes. Aluminum bronze, for example, requires a journal hardness in the range of 550 to 600 Bhn.

In general, harder bearing materials require better alignment and more reliable lubrication to minimize local heat generation if and when the journal touches the shaft. Also, abrasives that find their way into the bearing are a problem for the harder bearing materials and greater care should be taken to exclude them.

Surface Finish: Whether bearing operation is complete boundary, mixed film, or fluid film, surface finishes of the journal and bearing must receive careful attention. In applications where operation is hydrodynamic or full-film, peak surface variations should be less than the expected minimum film thickness; otherwise, peaks on the journal surface will contact peaks on the bearing surface, with resulting high friction and temperature rise. Ranges of surface roughness obtained by various finishing methods are: boring, broaching, and reaming, 32 to 64 microinches, rms; grinding, 16 to 64 microinches, rms; and fine grinding, 4 to 16 microinches, rms.

In general, the better surface finishes are required for full-film bearings operating at high eccentricity ratios because full-film lubrication must be maintained with small clearances, and metal-to-metal contact must be avoided. Also, the harder the material, the better the surface finish required. For boundary- and mixed-film applications, surface finish requirements may be somewhat relaxed because bearing wear-in will in time smooth the surfaces.

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. 5 is a general guide to the ranges required for bearing and journal surface finishes. Selecting a particular surface finish in each range can be simplified by observing the general rule that smoother finishes are required for the harder materials, for high loads, and for high speeds.



Fig. 5. Recommended ranges of surface finish for the three types of sleeve bearing operations.

Machining Bores.— The methods most commonly used in finishing journal bearing bores are boring, broaching, reaming, and burnishing.

Broaching is a rapid finishing method providing good size and alignment control when adequate piloting is possible. Soft babbitt materials are particularly compatible with the broaching method. A third finishing method, reaming, facilitates good size and alignment control when piloting is utilized. Reaming can be accomplished both manually or by machine, the machine method being preferred. Burnishing is a fast sizing operation that gives good alignment control, but does not give as good size control as the cutting methods. It is not recommended for soft materials such as babbitt. Burnishing has an ironing effect that gives added seating of the bushing outside diameter in the housing bore; consequently, it is often used for this purpose, especially on a $\frac{1}{32}$-inch wall bushing, even if a further sizing operation is to be used subsequently.

Boring of journal bearings provides the best concentricity, alignment, and size control and is the finishing method of choice when close tolerances and clearances are desirable.

Methods of Lubrication.— There are numerous ways to supply lubricant to bearings. The more common of these are described in the following.

Pressure lubrication, in which an abundance of oil is fed to the bearing from a central groove, single or multiple holes, or axial grooves, is effective and efficient. The moving oil assists in flushing dirt from the bearing and helps keep the bearing cool. In fact, it removes heat faster than other lubricating methods and, therefore, permits thinner oil films and unimpaired load capacities. The oil-supply pressure needed for bushings carrying the basic load is directly proportional to the shaft speed, but for most installations, 50 psi will be adequate.

Splash fed applies to a variety of intermittently lubricated bushings. It includes everything from bearings spattered with oil from the action of other moving parts to bearings regularly dipped in oil. Like oil bath lubrication, splash feeding is practical when the housing can be made oiltight and when the moving parts do not churn the oil. The fluctuating

Copyright 2004, Industrial Press, Inc., New York, NY

nature of the load and the intermittent oil supply in splash fed applications requires the designer to use experience and judgment when determining the probable load capacity of bearings lubricated in this way.

Oil bath lubrication, in which the bushing is submerged in oil, is the most reliable of all methods except pressure lubrication. It is practical if the housing can be made oil tight, and if the shaft speed is not so great as to cause excessive churning of the oil.

Oil ring lubrication, in which oil is supplied to the bearing by a ring in contact with the shaft, will, within reasonable limits, bring enough oil to the bearing to maintain hydrodynamic lubrication. If the shaft speed is too low, little oil will follow the ring to the bearing; and, if the speed is too high, the ring speed will not keep pace with the shaft. Also, a ring revolving at high speed will lose oil by centrifugal force. For best results, the peripheral speed of the shaft should be between 200 and 2000 feet per minute. Safe load to achieve hydrodynamic lubrication should be one-half of that for pressure fed bearings. Unless the load is light, hydrodynamic lubrication is doubtful. The safe load, then, to achieve hydrodynamic lubrication, should be one-quarter of that of pressure fed bearings.

Wick or waste pack lubrication delivers oil to a bushing by the capillary action of a wick or waste pack; the amount delivered is proportional to the size of the wick or pack.

Lubricants: The value of an oil as a lubricant depends mainly on its film-forming capacity, that is, its capability to maintain a film of oil between the bearing surfaces. The film-forming capacity depends to a large extent on the viscosity of the oil, but this should not be understood to mean that oil of the highest viscosity is always the most suitable lubricant. For practical reasons, an oil of the lowest viscosity that will retain an unbroken oil film between the bearing surfaces is the most suitable for purposes of lubrication. A higher viscosity than that necessary to maintain the oil film results in a waste of power due to the expenditure of energy necessary to overcome the internal friction of the oil itself.

Fig. 6 provides representative values of viscosity in centipoises for SAE mineral oils. Table 55a on page 2586 is provided as a means of converting viscosities of other units to centipoises.

Grease packed in a cavity surrounding the bushing is less adequate than an oil system, but it has the advantage of being more or less permanent. Although hydrodynamic lubrication is possible under certain very favorable circumstances, boundary lubrication is the usual state.

Lubricant Selection.— In selecting lubricants for journal bearing operation, several factors must be considered: 1) type of operation (full, mixed, or boundary film) anticipated; 2) surface speed; and 3) bearing loading.

Fig. 7 combines these factors and facilitates general selection of the proper lubricant viscosity range.

As an example of using these curves, consider a lightly loaded bearing operating at 2000 rpm. At the bottom of the figure, locate 2000 rpm and move vertically to intersect the light-load full-film lubrication curve, which indicates an SAE 5 oil.

As a general rule-of-thumb, heavier oils are recommended for high loads and lighter oils for high speeds.

In addition, other than using conventional lubrication oils, journal bearings may be lubricated with greases or solid lubricants. Some of the reasons for use of these lubricants are to:

1) Lengthen the period between relubrication:

2) Avoid contaminating surrounding equipment or material with “leaking” lubricating oil;

3) Provide effective lubrication under extreme temperature ranges;

4) Provide effective lubrication in the presence of contaminating atmospheres; and

5) Prevent intimate metal-to-metal contact under conditions of high unit pressure which might destroy boundary lubricating films.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6. Viscosity vs. Temperature—SAE oils.

Greases: Where full-film lubrication is not possible or is impractical for slow-speed fairly high-load applications, greases are widely used as bearing lubricants. Although full-film lubrication with grease is possible, it is not normally considered since an elaborate pumping system is required to continuously supply a prescribed amount of grease to the bearing. Bearings supplied with grease are usually lubricated periodically. Grease lubrication, therefore, implies that the bearing will operate under conditions of complete boundary lubrication and should be designed accordingly.

Lubricating greases are essentially a combination of a mineral lubricating oil and a thickening agent, which is usually a metallic soap. When suitably mixed, they make excellent bearing lubricants. There are many different types of greases which, in general, may be classified according to the soap base used. Information on commonly used greases is shown in Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Lubricant Selection Guide

Table 3. Commonly Used Greases and Solid Lubricants

Type	Operating Temperature, Degrees F	Load	Comments
Greases			
Calcium or lime soap	160	Moderate	…
Sodium soap	300	Wide	For wide speed range
Aluminum soap	180	Moderate	…
Lithium soap	300	Moderate	Good low temperature
Barium soap	350	Wide	…
Solid Lubricants			
Graphite	1000	Wide	…
Molybdenum disulfide	−100 to 750	Wide	…

Synthetic greases are composed of normal types of soaps but use synthetic hydrocarbons instead of normal mineral oils. They are available in a range of consistencies in both water-soluble and insoluble types. Synthetic greases can accommodate a wide range of variation in operating temperature; however, recommendations on special-purpose greases should be obtained from the lubricant manufacturer.

Application of grease is accomplished by one of several techniques depending upon grease consistency. These classifications are shown in Table 4 along with typical methods of application. Grooves for grease are generally greater in width, up to 1.5 times, than for oil.

Coefficients of friction for grease-lubricated bearings range from 0.08 to 0.16, depending upon consistency of the grease, frequency of lubrication, and type of grease. An average value of 0.12 may be used for design purposes.

Solid Lubricants: The need for effective high-temperature lubricants led to the development of several solid lubricants. Essentially, solid lubricants may be described as low-shear-strength solid materials. Their function within a bronze bearing is to act as an inter-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. NLGI Consistency Numbers

NLGI[a] Consistency No.	Consistency of Grease	Typical Method of Application
0	Semifluid	Brush or gun
1	Very soft	Pin-type cup or gun
2	Soft	Pressure gun or centralized pressure system
3	Light cup grease	Pressure gun or centralized pressure system
4	Medium cup grease	Pressure gun or centralized pressure system
5	Heavy cup grease	Pressure gun or hand
6	Block grease	Hand, cut to fit

[a] NLGI is National Lubricating Grease Institute

mediary material between sliding surfaces. Since these solids have very low shear strength, they shear more readily than the bearing material and thereby allow relative motion. So long as solid lubricant remains between the moving surfaces, effective lubrication is provided and friction and wear are reduced to acceptable levels.

Solid lubricants provide the most effective boundary films in terms of reduced friction, wear, and transfer of metal from one sliding component to the other. However, there is a significant deterioration in these desirable properties as the operating temperature of the boundary film approaches the melting point of the solid film. At this temperature the friction may increase by a factor of 5 to 10 and the rate of metal transfer may increase by as much as 1000. What occurs is that the molecules of the lubricant lose their orientation to the surface that exists when the lubricant is solid. As the temperature further increases, additional deterioration sets in with the friction increasing by some additional small amount but the transfer of metal accelerates by an additional factor of 20 or more. The final effect of too high temperature is the same as metal-to-metal contact without benefit of lubricant. These changes, which are due to the physical state of the lubricant, are reversed when cooling takes place.

The effects just described also partially explain why fatty acid lubricants are superior to paraffin base lubricants. The fatty acid lubricants react chemically with the metallic surfaces to form a metallic soap that has a higher melting point than the lubricant itself, the result being that the breakdown temperature of the film, now in the form of a metallic soap is raised so that it acts more like a solid film lubricant than a fluid film lubricant.

Journal or Sleeve Bearings

Although this type of bearing may take many shapes and forms, there are always three basic components: journal or shaft, bushing or bearing, and lubricant. Fig. 1 shows these components with the nomenclature generally used to describe a journal bearing: W = applied load, N = revolution, e = eccentricity of journal center to bearing center, θ = attitude angle, which is the angle between the applied load and the point of minimum film thickness, d = diameter of the shaft, c_d = bearing clearance, $d + c_d$ = diameter of the bearing and h_o = minimum film thickness.

Grooving and Oil Feeding.— Grooving in a journal bearing has two purposes:

1) to establish and maintain an efficient film of lubricant between the bearing moving surfaces and

2) to provide adequate bearing cooling

The obvious and only practical location for introducing lubricant to the bearing is in a region of low pressure. A typical pressure profile of a bearing is shown by Fig. 2. The arrow W shows the applied load. Typical grooving configurations used for journal bearings are shown in Figs. 3a through 3e.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Basic components of a journal bearing.



Fig. 2. Typical pressure profile of journal bearing.

Types of Journal Bearing Oil Grooving



Fig. 3a. Single inlet hole



Fig. 3b. Circular groove



Fig. 3c. Straight axial groove



Fig. 3d. Straight axial groove with feeder groove



Fig. 3e. Straight axial groove in shaft

Heat Radiating Capacity.— In a self-contained lubrication system for a journal bearing, the heat generated by bearing friction must be removed to prevent continued temperature rise to an unsatisfactory level. The heat-radiating capacity H_R of the bearing in foot-pounds per minute may be calculated from the formula $H_R = Ld\,Ct_R$ in which C is a constant determined by O. Lasche, and t_R is temperature rise in degrees Fahrenheit.

Values for the product Ct_R may be found from the curves in Fig. 4 for various values of bearing temperature rise t_R and for three operating conditions. In this equation, L = total length of the bearing in inches and d = bearing diameter in inches.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Heat-radiating capacity factor, Ct_R, vs. bearing temperature rise, t_R—journal bearings.

Journal Bearing Design Notation.— The symbols used in the following step-by-step procedure for lubrication analysis and design of a plain sleeve or journal bearing are as follows:

c = specific heat of lubricant, Btu/lb/degree F
c_d = diametral clearance, inches
C_n = bearing capacity number
d = journal diameter, inches
e = eccentricity, inches
h_o = minimum film thickness, inch
K = constants
l = bearing length as defined in Fig. 5, inches
L = actual length of bearing, inches
m = clearance modulus
N = rpm
p_b = unit load, psi
p_s = oil supply pressure, psi
P_f = friction horsepower
P' = bearing pressure parameter
q = flow factor
Q_1 = hydrodynamic flow, gpm
Q_2 = pressure flow, gpm
Q = total flow, gpm
Q_{new} = new total flow, gpm
Q_R = total flow required, gpm

Copyright 2004, Industrial Press, Inc., New York, NY

r = journal radius, inches
Δt = actual temperature rise of oil in bearing, °F
Δt_a = assumed temperature rise of oil in bearing, °F
Δt_{new} = new assumed temperature rise of oil in bearing, °F
t_b = bearing operating temperature, °F
t_{in} = oil inlet temperature, °F
T_f = friction torque, inch-pounds/inch
T' = torque parameter
W = load, pounds
X = factor
Z = viscosity, centipoises
ϵ = eccentricity ratio — ratio of eccentricity to radial clearance
α = oil density, lbs/inch^3



Fig. 5. Length, l, of bearing for circular groove type (left) and single inlet hole type (right).

Journal Bearing Lubrication Analysis.— The following procedure leads to a complete lubrication analysis which forms the basis for the bearing design.

1) *Diameter of bearing d*: This is usually determined by considering strength and/or deflection requirements for the shaft using principles of strength of materials.

2) *Length of bearing L*: This is determined by an assumed *l*/*d* ratio in which *l* may or may not be equal to the overall length, *L* (See Step 6). Bearing pressure and the possibility of edge loading due to shaft deflection and misalignment are factors to be considered. In general, shaft misalignment resulting from location tolerances and/or shaft deflections should be maintained below 0.0003 inch per inch of length.

3) *Bearing pressure* p_b: The unit load in pound per square inch is calculated from the formula:

$$p_b = \frac{W}{Kld}$$

where $K = 1$ for single oil hole

$K = 2$ for central groove

W = load, pounds

l = bearing length as defined in Fig. 5, inches

d = journal diameter, inches

Typical unit loads in service are shown in Table 5. These pressures can be used as a safe guide in selection. However, if space limitations impose a higher limit of loading, the complete lubrication analysis and evaluation of material properties will determine acceptability.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Allowable Sleeve Bearing Pressures for Various Classes of Bearings

Types of Bearing or Kind of Service	Pressure[a] psi	Types of Bearing or Kind of Service	Pressure[a] psi
Electric Motor & Generator Bearings (General)	100–200	Diesel Engine Rod	1000–2000
Turbine & Reduction Gears	100–250	Wrist Pins	1800–2000
Heavy Line Shafting	100–150	Automotive, Main Bearings	500–700
Locomotive Axles	300–350	Automotive, Rod Bearings	1500–2500
Light Line Shafting	15–35	Centrifugal Pumps	80–100
Diesel Engine, Main	800–1500	Aircraft Rod Bearings	700–3000

[a] These pressures in pounds per square inch of area equal to length times diameter are intended as a general guide only. The allowable unit pressure depends upon operating conditions, especially in regard to lubrication, design of bearings, workmanship, velocity, and nature of load.

4) *Diametral clearance c_d:* This is selected on a trial basis from Fig. 6 which shows suggested diametral clearance ranges for various shaft sizes and for two speed ranges. These are *hot* or *operating* clearances so that thermal expansion of journal and bearing to these temperatures must be taken into consideration in establishing machining dimensions. The optimum operating clearance should be determined on the basis of a complete lubrication analysis (See paragraph following Step (23).

5) *Clearance modulus m:* This is calculated from the formula: $m = \frac{c_d}{d}$

6) *Length to diameter ratio l/d:* This is usually between 1 and 2; however, with the modern trend toward higher speeds and more compact units, lower ratios down to 0.3 are used. In shorter bearings there is a consequent reduction in load carrying capacity due to excessive end or side leakage of lubricant. In longer bearings there may be a tendency towards edge loading. Length l for a single oil feed hole is taken as the total length of the bearing as shown in Fig. 5. For a central oil groove length, l is taken as one-half the total length.

Typical *l/d* ratio's use for various types of applications are given in Table 6.

7) *Assumed operating temperature t_b:* A temperature rise of the lubricant as it passes through the bearing is assumed and the consequent operating temperature in degrees F is calculated from the formula:

$$t_b = t_{in} + \Delta t_a$$

where t_{in} = inlet temperature of oil in °F

Δt_a = assumed temperature rise of oil in bearing in °F. An initial assumption of 20°F is usually made.

8) *Viscosity of lubricant Z:* The viscosity in centipoises at the assumed bearing operating temperature is found from the curve in Fig. 6 which shows the viscosity of SAE grade oils versus temperature.

9) *Bearing pressure parameter P′:* This value is required to find the eccentricity ratio and is calculated from the formula:

$$P' = \frac{6.9(1000m)^2 p_b}{ZN}$$

where N = rpm

Copyright 2004, Industrial Press, Inc., New York, NY



Type of Service	*l*/*d*	Type of Service	*l*/*d*
Gasoline and diesel engine		Light shafting	2.5 to 3.5
main bearings and crankpins	0.3 to 1.0	Heavy shafting	2.0 to 3.0
Generators and motors	1.2 to 2.5	Steam engine	
Turbogenerators	0.8 to 1.5	Main bearings	1.5 to 2.5
Machine tools	2.0 to 3.0	Crank and wrist pins	1.0 to 1.3

10) *Eccentricity ratio* ϵ*:* Using P' and *l*/*d*, the value of $1/(1-\epsilon)$ is determined from Fig. 7 and from this, ϵ can be determined.

11) *Torque parameter T′:* This value is obtained from Fig. 8 or Fig. 9 using $1/(1-\epsilon)$ and *l*/*d*.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Bearing parameter. P', vs. eccentricity ratio. $1/(1-\epsilon)$ — journal bearings.

12) *Friction torque T:* This value is calculated from the formula:

$$T = \frac{T' r^2 ZN}{6900(1000m)}$$

where r = journal radius, inches

13) *Friction horsepower P_f:* This value is calculated from the formula:

$$P_f = \frac{KTNl}{63{,}000}$$

where $K = 1$ for single oil hole, 2 for central groove.

14) *Factor X:* This factor is used in the calculation of the lubricant flow and can either be obtained from Table 7 or calculated from the formula:

$$X = 0.1837/\alpha c$$

where α = oil density in pounds per cubic inch
c = specific heat of lubricant in Btu/lb/°F

15) *Total flow of lubricant required Q_R:* This is calculated from the formula:

$$Q_R = \frac{X(P_f)}{\Delta t_a}$$

16) *Bearing capacity number C_n:* This value is needed to obtain the flow factor and is calculated from the formula:

$$C_n = \left(\frac{l}{d}\right)^2 / 60P'$$

17) *Flow factor q:* This value is obtained from the curve in Fig. 10.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. Torque parameter, T', vs. eccentricity ratio, $1(1-\epsilon)$ — journal bearings.



Fig. 9. Torque parameter, T', vs eccentricity ratio, $1/(1-\epsilon)$ — journal bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. *X* Factor vs. Temperature of Mineral Oils

Temperature	*X* Factor
100	12.9
150	12.4
200	12.1
250	11.8
300	11.5



Fig. 10. Flow factor, q, vs. bearing capacity number, C_n—journal bearings.

18) *Hydrodynamic flow of lubricant Q_1:* This flow in gallons per minute is calculated from the formula:

$$Q_1 = \frac{Nlc_d qd}{294}$$

19) *Pressure flow of lubricant Q_2:* This flow in gallons per minute is calculated from the formula:

$$Q_2 = \frac{Kp_s c_d^3 d(1 + 1.5\epsilon^2)}{Zl}$$

where $K = 1.64 \times 10^5$ for single oil hole
$K = 2.35 \times 10^5$ for central groove
p_s = oil supply pressure

20) *Total flow of lubricant Q:* This value is obtained by adding the hydrodynamic flow and the pressure flow.

$$Q = Q_1 + Q_2$$

Copyright 2004, Industrial Press, Inc., New York, NY

21) *Bearing temperature rise* Δt*:* This temperature rise in degrees F is obtained from the formula:

$$\Delta t = \frac{X(P_f)}{Q}$$

22) *Comparison of actual and assumed temperature rises:* At this point if Δt_a and Δt differ by more than 5 degrees F, Steps 7 through 22 are repeated using a Δt_{new} halfway between the former Δt_a and Δt.

23) *Minimum film thickness* h_o*:* When Step 22 has been satisfied, the minimum film thickness in inches is calculated from the formula: $h_o = \frac{1}{2}C_d(1 - \epsilon)$.

A new diametral clearance c_d is now assumed and Steps 5 through 23 are repeated. When this repetition has been done for a sufficient number of values for c_d, the full lubrication study is plotted as shown in Fig. 11. From this chart a working range of diametral clearance can be determined that optimizes film thickness, differential temperature, friction horsepower and oil flow.



Fig. 11. Example of lubrication analysis curves for journal bearing.

Use of Lubrication Analysis.— Once the lubrication analysis has been completed and plotted as shown in Fig. 11, the following steps lead to the optimum bearing design, taking into consideration both basic operating requirements and requirements peculiar to the application.

1) Examine the curve (Fig. 11) for minimum film thickness and determine the acceptable range of diametral clearance, c_d, based on

a) a minimum of 200×10^{-6} inches for small bearings under 1 inch diameter
b) a minimum of 500×10^{-6} inches for bearings from 1 to 4 inches diameter
c) a minimum of 750×10^{-6} inches for larger bearings.
More conservative designs would increase these requirements

2) Determine the minimum acceptable c_d based on a maximum Δt of 40°F from the oil temperature rise curve (Fig. 11).

Copyright 2004, Industrial Press, Inc., New York, NY

3) If there are no requirements for maintaining low friction horsepower and oil flow, the possible limits of diametral clearance are now defined.
4) The required manufacturing tolerances can now be placed within this band to optimize h_o as shown by Fig. 11.
5) If oil flow and power loss are a consideration, the manufacturing tolerances may then be shifted, within the range permitted by the requirements for h_o and Δt.



Fig. 12. Full journal bearing example design.

Example: A full journal bearing, Fig. 12, 2.3 inches in diameter and 1.9 inches long is to carry a load of 6000 pounds at 4800 rpm, using SAE 30 oil supplied at 200°F through a single oil hole at 30 psi. Determine the operating characteristics of this bearing as a function of diametral clearance.
1) *Diameter of bearing,* given as 2.3 inches.
2) *Length of bearing,* given as 1.9 inches.
3) *Bearing pressure:*

$$p_b = \frac{6000}{1 \times 1.9 \times 2.3} = 1372 \text{ lbs. per sq. in.}$$

4) *Diametral clearance:* Assume c_d is equal to 0.003 inch from Fig. 6 on page 2235 for first calculation.

5) *Clearance modulus:* $m = \frac{0.003}{2.3} = 0.0013$ inch

6) *Length-to-diameter ratio:*

$$\frac{l}{d} = \frac{1.9}{2.3} = 0.83$$

7) *Assumed operating temperature:* If the temperature rise Δt_a is assumed to be 20°F,

$$t_b = 200 + 20 = 220°\text{F}$$

8) *Viscosity of lubricant:* From Fig. 6 on page 2228, Z = 7.7 centipoises
9) *Bearing-pressure parameter:*

$$P' = \frac{6.9 \times 1.3^2 \times 1372}{7.7 \times 4800} = 0.43$$

10) *Eccentricity ratio:* From Fig. 7, $\frac{1}{1-\epsilon} = 6.8$ and $\epsilon = 0.85$
11) *Torque parameter:* From Fig. 8, $T' = 1.46$
12) *Friction torque:*

$$T_f = \frac{1.46 \times 1.15^2 \times 7.7 \times 4800}{6900 \times 1.3} = 7.96 \text{ inch-pounds per inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

13) *Friction horsepower:*

$$P_f = \frac{1 \times 7.96 \times 4800 \times 1.9}{63{,}000} = 1.15 \text{ horsepower}$$

14) *Factor X:* From Table 7, $X = 12$, approximately

15) *Total flow of lubricant required:*

$$Q_R = \frac{12 \times 1.15}{20} = 0.69 \text{ gallon per minute}$$

16) *Bearing-capacity number:*

$$C_n = \frac{0.83^2}{60 \times 0.43} = 0.027$$

17) *Flow factor:* From Fig. 10, $q = 1.43$

18) *Actual hydrodynamic flow of lubricant:*

$$Q_1 = \frac{4800 \times 1.9 \times 0.003 \times 1.43 \times 2.3}{294} = 0.306 \text{ gallon per minute}$$

19) *Actual pressure flow of lubricant:*

$$Q_2 = \frac{1.64 \times 10^5 \times 30 \times 0.003^3 \times 2.3 \times (1 + 1.5 \times 0.85^2)}{7.7 \times 1.9} = 0.044 \text{ gallon per min}$$

20) *Actual total flow of lubricant:*

$$Q = 0.306 + 0.044 = 0.350 \text{ gallon per minute}$$

21) *Actual bearing-temperature rise:*

$$\Delta t = \frac{12 \times 1.15}{0.350} = 39.4°\text{F}$$

22) *Comparison of actual and assumed temperature rises:* Because Δt_a and Δt differ by more than 5°F, a new Δt_a, midway between these two, of 30°F is assumed and Steps 7 through 22 are repeated.

7a) *Assumed operating temperature:*

$$t_b = 200 + 30 = 230°\text{F}$$

8a) *Viscosity of lubricant:* From Fig. 6, $Z = 6.8$ centipoises

9a) *Bearing-pressure parameter:*

$$P' = \frac{6.9 \times 1.3^2 \times 1372}{6.8 \times 4800} = 0.49$$

10a) *Eccentricity ratio:* From Fig. 7,

$$\frac{1}{1 - \epsilon} = 7.4$$

and $\epsilon = 0.86$

11a) *Torque parameter:* From Fig. 8, $T' = 1.53$

12a) *Friction torque:*

$$T_f = \frac{1.53 \times 1.15^2 \times 6.8 \times 4800}{6900 \times 1.3} = 7.36 \text{ inch-pounds per inch}$$

13a) *Friction horsepower:*

$$P_f = \frac{1 \times 7.36 \times 4800 \times 1.9}{63{,}000} = 1.07 \text{ horsepower}$$

14a) *Factor X*: From Table 7, $X = 11.9$ approximately

15a) *Total flow of lubricant required:*

$$Q_R = \frac{11.9 \times 1.07}{30} = 0.42 \text{ gallon per minute}$$

Copyright 2004, Industrial Press, Inc., New York, NY

16a) *Bearing-capacity number:*

$$C_n = \frac{0.83^2}{60 \times 0.49} = 0.023$$

17a) *Flow factor:* From Fig. 10, $q = 1.48$

18a) *Actual hydrodynamic flow of lubricant:*

$$Q_1 = \frac{4800 \times 1.9 \times 0.003 \times 1.48 \times 2.3}{294} = 0.317 \text{ gallon per minute}$$

19a) *Pressure flow:*

$$Q_2 = \frac{1.64 \times 10^5 \times 30 \times 0.003^3 \times 2.3 \times (1 + 1.5 \times 0.86^2)}{6.8 \times 1.9} = 0.050 \text{ gallon per minute}$$

20a) *Actual flow of lubricant:*

$$Q_{\text{new}} = 0.317 + 0.050 = 0.367 \text{ gallon per minute}$$

21a) *Actual bearing-temperature rise:*

$$\Delta t = \frac{11.9 \times 1.06}{0.367} = 34.4°\text{F}$$

22a) *Comparison of actual and assumed temperature rises:* Now Δt and Δt_a are within 5 degrees F.

23) *Minimum film thickness:*

$$h_o = \frac{0.003}{2}(1 - 0.86) = 0.00021 \text{ inch}$$

This analysis may now be repeated for other values of c_d determined from Fig. 6 and a complete lubrication analysis performed and plotted as shown in Fig. 11. An operating range for c_d can then be determined to optimize minimum clearance, friction horsepower loss, lubricant flow, and temperature rise.

Thrust Bearings

As the name implies, thrust bearings are used either to absorb axial shaft loads or to position shafts axially. Brief descriptions of the normal designs for these bearings follow with approximate design methods for each. The generally accepted load ranges for these types of bearings are given in Table 1 and the schematic configurations are shown in Fig. 1.

The parallel or flat plate thrust bearing is probably the most frequently used type. It is the simplest and lowest in cost of those considered; however, it is also the least capable of absorbing load, as can be seen from Table 1. It is most generally used as a positioning device where loads are either light or occasional.

The step bearing, like the parallel plate, is also a relatively simple design. This type of bearing will accept the normal range of thrust loads and lends itself to low-cost, high-volume production. However, this type of bearing becomes sensitive to alignment as its size increases.

The tapered land thrust bearing, as shown in Table 1, is capable of high load capacity. Where the step bearing is generally used for small sizes, the tapered land type can be used in larger sizes. However, it is more costly to manufacture and does require good alignment as size is increased.

The tilting pad or Kingsbury thrust bearing (as it is commonly referred to) is also capable of high thrust capacity. Because of its construction it is more costly, but it has the inherent advantage of being able to absorb significant amounts of misalignment.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Types of thrust bearings.

Table 1. Thrust Bearing Loads*

Type	Normal Unit Loads, Lb per Sq. In.	Maximum Unit Loads, Lb per Sq. In.
Parallel surface	<75	<150
Step	200	500
Tapered land	200	500
Tilting pad	200	500

Thrust Bearing Design Notation.— The symbols used in the design procedures that follow for flat plate, step, tapered land, and tilting pad thrust bearings are as follows:

a = radial width of pad, inches
b = circumferential length of pad at pitch line, inches
b_2 = pad step length
B = circumference of pitch circle, inches
c = specific heat of oil, Btu/gal/°F
D = diameter, inches
e = depth of step, inch
f = coefficient of friction
g = depth of 45° chamfer, inches
h = film thickness, inch
i = number of pads
J = power loss coefficient
K = film thickness factor
K_g = fraction of circumference occupied by the pads; usually, 0.8
l = length of chamfer, inches
M = horsepower per square inch
N = revolutions per minute
O = operating number
p = bearing unit load, psi
p_s = oil-supply pressure, psi
P_f = friction horsepower
Q = total flow, gpm

* Reproduced with permission from Wilcock and Booser, *Bearing Design and Applications,* McGraw-Hill Book Co., Copyright © 1957.

Copyright 2004, Industrial Press, Inc., New York, NY

Q_c = required flow per chamfer, gpm
Q^o_c = uncorrected required flow per chamfer, gpm
Q_F = film flow, gpm
s = oil-groove width
Δt = temperature rise, °F
U = velocity, feet per minute
V = effective width-to-length ratio for one pad
W = applied load, pounds
Y_G = oil-flow factor
Y_L = leakage factor
Y_S = shape factor
Z = viscosity, centipoises
α = dimensionless film-thickness factor
δ = taper
ξ = kinetic energy correction factor

Note: In the following, subscript 1 denotes inside diameter and subscript 2 denotes outside diameter. Subscript *i* denotes inlet and subscript *o* denotes outlet.

Flat Plate Thrust Bearing Design.— The following steps define the performance of a flat plate thrust bearing, one section of which is shown in Fig. 2. Although each bearing section is wedge shaped, as shown below right, for the purposes of design calculation, it is considered to be a rectangle with a length *b* equal to the circumferential length along the pitch line of the section being considered, and a width *a* equal to the difference in the external and internal radii.

General Parameters: a) From Table 1, the maximum unit load is between 75 and 100 pounds per square inch; and b) The outside diameter is usually between 1.5 and 2.5 times the inside diameter.



Fig. 2. Basic elements of flat plate thrust bearing.*



Basic elements of flat plate thrust bearing.*

1) *Inside diameter, D_1.* Determined by shaft size and clearance.
2) *Outside diameter, D_2.* Calculated by the formula

$$D_2 = \left(\frac{4W}{\pi K_g p} + D_1^2\right)^{1/2}$$

where W = applied load, pounds
K_g = fraction of circumference occupied by pads; usually, 0.8
p = bearing unit load, psi

3) *Radial pad width, a.* Equal to one-half the difference between the inside and outside diameters.

Copyright 2004, Industrial Press, Inc., New York, NY

$$a = \frac{D_2 - D_1}{2}$$

4) *Pitch line circumference, B*. Found from the pitch diameter.

$$B = \pi(D_2 - a)$$

5) *Number of pads, i*. Assume an oil groove width, *s*. If the length of pad is assumed to be optimum, i.e., equal to its width,

$$i_{\text{app}} = \frac{B}{a + s}$$

Take *i* as nearest even number.

6) *Length of pad, b*. If number of pads and oil groove width are known,

$$b = \frac{B - (i \times s)}{i}$$

7) *Actual unit load, p*. Calculated in pounds per square inch based on pad dimensions.

$$p = \frac{W}{iab}$$

8) *Pitch line velocity, U*. Found in feet per minute from

$$U = \frac{BN}{12}$$

where N = rpm

9) *Friction power loss, P_f*. Friction power loss is difficult to calculate for this type of bearing because there is no theoretical method of determining the operating film thickness. However, a good approximation can be made using Fig. 3. From this curve, the value of *M*, horsepower loss per square inch of bearing surface, can be obtained. The total power loss, P_f, is then calculated from

$$P_f = iabM$$

10) *Oil flow required, Q*. May be estimated in gallons per minute for a given temperature rise from

$$Q = \frac{42.4P_f}{c\Delta t}$$

where c = specific heat of oil in Btu/gal/°F
Δt = temperature rise of the oil in °F

Note: A Δt of 50°F is an acceptable maximum.

Because there is no theoretical method of predicting the minimum film thickness in this type of bearing, only an approximation, based on experience, of the film flow can be made. For this reason and based on practical experience, it is desirable to have a minimum of one-half of the desired oil flow pass through the chamfer.

11) *Film flow, Q_F*. Calculated in gallons per minute from

$$Q_F = \frac{(1.5)(10^5)iVh^3p_s}{Z_2}$$

where V = effective width-to-length ratio for one pad, *a*/*b*
Z_2 = oil viscosity at outlet temperature
h = film thickness

Note: Because *h* cannot be calculated, use $h = 0.002$ inch.

12) *Required flow per chamfer, Q_c*. Readily found from the formula

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Friction power loss, M, vs. peripheral speed, U — thrust bearings.[a]

[a] See footnote on page 2243.

$$Q_c = \frac{Q}{i}$$

13) *Kinetic energy correction factor*, ξ. Found by assuming a chamfer length l and entering Fig. 4 with a value $Z_2 l$ and Q_c.

14) *Uncorrected required flow per chamfer*, $Q^0{}_c$. Found from the formula

$$Q_c^0 = \frac{Q_c}{\xi}$$

15) *Depth of chamfer*, g. Found from the formula

$$g = \sqrt[4]{\frac{Q_c^0 l Z_2}{4.74\times10^4 p_s}}$$

Example: Design a flat plate thrust bearing to carry 900 pounds load at 4000 rpm using an SAE 10 oil with a specific heat of 3.5 Btu/gal/°F at 120°F and 30-psi inlet conditions. The

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Kinetic energy correction factor, ξ—thrust bearings.[a]

[a] See footnote on page 2243.

shaft is 2¾ inches in diameter and the temperature rise is not to exceed 40°F. Fig. 5 shows the final design of this bearing.

1) *Inside diameter*. Assumed to be 3 inches to clear shaft.

2) *Outside diameter*. Assuming a unit bearing load of 75 pounds per square inch from Table 1,

$$D_2 = \sqrt{\frac{4 \times 900}{\pi \times 0.8 \times 75} + 3^2} = 5.30 \text{ inches}$$

Use 5½ inches.

3) *Radial pad width*.

$$a = \frac{5.5 - 3}{2} = 1.25 \text{ inches}$$

4) *Pitch-line circumference*.

$$B = \pi \times 4.25 = 13.35 \text{ inches}$$

5) *Number of pads*. Assume an oil groove width of 3/16 inch. If length of pad is assumed to be equal to width of pad, then

$$i_{app} = \frac{13.3}{1.25 + 0.1875} = 9+$$

If the number of pads, i, is taken as 10, then

Copyright 2004, Industrial Press, Inc., New York, NY

6) *Length of pad*. $b = \dfrac{13.35 - (10 \times 0.1875)}{10} = 1.14$ inches

7) *Actual unit load*.

$$p = \frac{900}{10 \times 1.25 \times 1.14} = 63 \text{ psi}$$

8) *Pitch-line velocity*.

$$U = \frac{13.35 \times 4000}{12} = 4,430 \text{ ft per min.}$$

9) *Friction power loss*. From Fig. 3, $M = 0.19$

$$P_f = 10 \times 1.25 \times 1.14 \times 0.19 = 2.7 \text{ horsepower}$$

10) *Oil flow required*.

$$Q = \frac{42.4 \times 2.7}{3.5 \times 40} = 0.82 \text{ gallon per minute}$$

(Assuming a temperature rise of 40°F—the maximum allowable according to the given condition—then the assumed operating temperature will be 120°F + 40°F = 160°F and the oil viscosity Z_2 is found from Fig. 6 to be 9.6 centipoises.)

11) *Film flow*.

$$Q_F = \frac{1.5 \times 10^5 \times 10 \times 1 \times 0.002^3 \times 30}{9.6} = 0.038 \text{ gpm}$$

Because 0.038 gpm is a very small part of the required flow of 0.82 gpm, the bulk of the flow must be carried through the chamfers.

12) *Required flow per chamfer*. Assume that all the oil flow is to be carried through the chamfers.

$$Q_c = \frac{0.82}{10} = 0.082 \text{ gpm}$$

13) *Kinetic energy correction factor*. If l, the length of chamfer is made ⅛ inch, then $Z_2 l = 9.6 \times \frac{1}{8} = 1.2$. Entering Fig. 4 with this value and $Q_c = 0.082$,

$$\xi = 0.44$$

14) *Uncorrected required oil flow per chamfer*.

$$Q_c^0 = \frac{0.082}{0.44} = 0.186 \text{ gpm}$$

15) *Depth of chamfer*.

$$g = \sqrt[4]{\frac{0.186 \times 0.125 \times 9.6}{4.74 \times 10^4 \times 30}}$$

$$g = 0.02 \text{ inch}$$

A schematic drawing of this bearing is shown in Fig. 5.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Flat plate thrust bearing example design.*

Step Thrust Bearing Design.— The following steps define the performance of a step thrust bearing, one section of which is shown in Fig. 6.



Fig. 6. Basic elements of step thrust bearing.*

Although each bearing section is wedge shaped, as shown at the right in Fig. 6, for the purposes of design calculation it is considered to be a rectangle with a length b equal to the circumferential length along the pitch line of the section being considered, and a width a equal to the difference in the external and internal radii.

General Parameters: For optimum proportions, $a = b, b_2 = 1.2b_1$, and $e = 0.7h$.

1) *Internal diameter, D_1.* An internal diameter is assumed that is sufficient to clear the shaft.

2) *External diameter, D_2.* A unit bearing pressure is assumed from Table 1 and the external diameter is then found from the formula

$$D_2 = \sqrt{\frac{4W}{\pi K_g p} + D_1^2}$$

3) *Radial pad width, a.* Equal to the difference between the external and internal radii.

$$a = \frac{D_2 - D_1}{2}$$

* See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

4) *Pitch-line circumference, B*. Found from the formula

$$B = \frac{\pi(D_1 + D_2)}{2}$$

5) *Number of pads,i*. Assume an oil groove width, *s* (0.062 inch may be taken as a minimum), and find the approximate number of pads, assuming the pad length is equal to *a*. Note that if a chamfer is found necessary to increase the oil flow (see Step 13), the oil groove width should be greater than the chamfer width.

$$i_{\text{app}} = \frac{B}{a + s}$$

Then *i* is taken as the nearest even number.

6) *Length of pad, b*. Readily determined from the number of pads and groove width.

$$b = \frac{B}{i} - s$$

7) *Pitch-line velocity, U*. Found in feet per minute from the formula $U = \frac{BN}{12}$

8) *Film thickness, h*. Found in inches from the formula

$$h = \sqrt{\frac{2.09\times10^{-9} i a^3 U Z}{W}}$$

9) *Depth of step, e*. According to the general parameter

$$e = 0.7h$$

10) *Friction power loss, P_f*. Found from the formula

$$P_f = \frac{7.35\times10^{-13} i a^2 U^2 Z}{h}$$

11) *Pad step length, b_2*. This distance, on the pitch line, from the leading edge of the pad to the step in inches is determined by the general parameters

$$b_2 = \frac{1.2b}{2.2}$$

12) *Hydrodynamic oil flow, Q*. Found in gallons per minute from the formula

$$Q = 6.65\times10^{-4} i a h U$$

13) *Temperature rise, Δt*. Found in degrees F from the formula

$$\Delta t = \frac{42.4 P_f}{cQ}$$

If the flow is insufficient, as indicated by too high a temperature rise, chamfers can be added to provide adequate flow as in Steps 12–15 of the flat plate thrust bearing design.

Example: Design a step thrust bearing for positioning a ⅞-inch diameter shaft operating with a 25-pound thrust load and a speed of 5,000 rpm. The lubricating oil has a viscosity of 25 centipoises at the operating temperature of 160 deg. F and has a specific heat of 3.4 Btu per gal. per deg. F.

1) *Internal diameter*. Assumed to be 1 inch to clear the shaft.

2) *External diameter*. Because the example is a positioning bearing with low total load, unit load will be negligible and the external diameter is not established by using the formula given in Step 2 of the procedure, but a convenient size is taken to give the desired overall bearing proportions.

$$D_2 = 3 \text{ inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

3) *Radial pad width*.

$$a = \frac{3-1}{2} = 1 \text{ inch}$$

4) *Pitch-line circumference*.

$$B = \frac{\pi(3+1)}{2} = 6.28 \text{ inches}$$

5) *Number of pads*. Assuming a minimum groove width of 0.062 inch,

$$i_{app} = \frac{6.28}{1+0.062} = 5.9$$

Take $i = 6$.

6) *Length of pad*.

$$b = \frac{6.28}{6} - 0.062 = 0.985$$

7) *Pitch-line velocity*.

$$U = \frac{6.28 \times 5{,}000}{12} = 2{,}620 \text{ fpm}$$

8) *Film thickness*.

$$h = \sqrt{\frac{2.09\times10^{-9} \times 6 \times 1^3 \times 2{,}620 \times 25}{25}} = 0.0057 \text{ inch}$$

9) *Depth of step*.

$$e = 0.7 \times 0.0057 = 0.004 \text{ inch}$$

10) *Power loss*.

$$P_f = \frac{7.35\times10^{-13} \times 6 \times 1^2 \times 2{,}620^{\,2} \times 25}{0.0057} = 0.133 \text{ hp}$$

11) *Pad step length*.

$$b_2 = \frac{1.2 \times 0.985}{2.2} = 0.537 \text{ inch}$$

12) *Total hydrodynamic oil flow*.

$$Q = 6.65\times10^{-4} \times 6 \times 1 \times 0.0057 \times 2{,}620 = 0.060 \text{ gpm}$$

13) *Temperature rise*.

$$\Delta t = \frac{42.4 \times 0.133}{3.4 \times 0.060} = 28° \text{ F}$$

Tapered Land Thrust Bearing Design.— The following steps define the performance of a tapered land thrust bearing, one section of which is shown in Fig. 7. Although each bearing section is wedge shaped, as shown in Fig. 7, right, for the purposes of design calculation, it is considered to be a rectangle with a length b equal to the circumferential length along the pitch line of the section being considered and a width a equal to the difference in the external and internal radii.

General Parameters: Usually, the taper extends to only 80 per cent of the pad length with the remainder being flat, thus: $b_2 = 0.8b$ and $b_1 = 0.2b$.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Basic elements of tapered land thrust bearing.*

1) *Inside diameter, D_1.* Determined by shaft size and clearance.

2) *Outside diameter, D_2.* Calculated by the formula

$$D_2 = \left(\frac{4W}{\pi K_g P_a} + D_1^2\right)^{1/2}$$

where K_g = 0.8 or 0.9 and W = applied load, pounds
P_a = assumed unit load from Table 1, page 2243

3) *Radial pad width, a.* Equal to one-half the difference between the inside and outside diameters.

$$a = \frac{D_2 - D_1}{2}$$

4) *Pitch-line circumference, B.* Found from the mean diameter:

$$B = \frac{\pi(D_1 + D_2)}{2}$$

5) *Number of pads, i.* Assume an oil groove width, s, and find the approximate number of pads, assuming the pad length is equal to a.

$$i_{app} = \frac{B}{a + s}$$

Then i is taken as the nearest even number.

6) *Length of pad, b.* Readily determined because the number of pads and groove width are known.

$$b = \frac{B - is}{i}$$

7) *Taper values, δ_1 and δ_2.* Can be taken from Table 2.

8) *Actual bearing unit load, p.* Calculated in pounds per square inch from the formula

$$p = \frac{W}{iab}$$

9) *Pitch-line velocity, U.* Found in feet per minute at the pitch circle from the formula

$$U = \frac{BN}{12}$$

where N = rpm

10) *Oil leakage factor, Y_L.* Found either from Fig. 8 which shows curves for Y_L as functions of the pad width a and length of land b or from the formula

$$Y_L = \frac{b}{1 + (\pi^2 b^2 / 12a^2)}$$

11) *Film thickness factor, K.* Calculated using the formula

$$K = \frac{5.75 \times 10^6 p}{U Y_L Z}$$

*See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

12) *Minimum film thickness, h*. Using the value of K just determined and the selected taper values δ_1 and δ_2, h is found from Fig. 9. In general, h should be 0.001 inch for small bearings and 0.002 inch for larger and high-speed bearings.

13) *Friction power loss, P_f*. Using the film thickness h, the coefficient J can be obtained from Fig. 10. The friction loss in horsepower is then calculated from the formula

$$P_f = 8.79\times10^{-13} iabJU^2Z$$

14) *Required oil flow, Q*. May be estimated in gallons per minute for a given temperature rise Δ_t from the formula

$$Q = \frac{42.4P_f}{c\Delta t}$$

where c = specific heat of the oil in Btu/gal/°F

Note: A Δt of 50°F is an acceptable maximum.

15) *Shape factor, Y_s*. Needed to compute the actual oil flow and calculated from

$$Y_S = \frac{8ab}{D^2{}_2 - D_1^2}$$

16) *Oil flow factor, Y_G*. Found from Fig. 11 using Y_s and D_1/D_2.

17) *Actual oil film flow, Q_F*. The amount of oil in gallons per minute that the bearing film will pass is calculated from the formula

$$Q_F = \frac{8.9\times10^{-4} i\delta_2 D_2^3 N Y_G Y_S^2}{D_2 - D_1}$$

18) If the flow is insufficient, the tapers can be increased or chamfers calculated to provide adequate flow, as in Steps 12–15 of the flat plate thrust bearing design procedure.

Example: Design a tapered land thrust bearing for 70,000 pounds at 3600 rpm. The shaft diameter is 6.5 inches. The oil inlet temperature is 110°F at 20 psi.



Fig. 8. Leakage factor, Y_L, vs. pad dimensions a and b—tapered land thrust bearings.*

*See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 9. Thickness, h, vs. factor K—tapered land thrust bearings.*



Fig. 10. Power-loss coefficient, J, vs. film thickness, h—tapered land thrust bearings.*

A maximum temperature rise of 50°F is acceptable and results in a viscosity of 18 centipoises. Use values of $K_g = 0.9$ and $c = 3.5$ Btu/gal/°F.

*See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

1) *Internal diameter*. Assume $D_1 = 7$ inches to clear shaft.

2) *External diameter*. Assume a unit bearing load p_a of 400 pounds per square inch from Table 1, then

$$D_2 = \sqrt{\frac{4 \times 70{,}000}{3.14 \times 0.9 \times 400} + 7^2} = 17.2 \text{ inches}$$

Round off to 17 inches.

3) *Radial pad width*.

$$a = \frac{17 - 7}{2} = 5 \text{ inches}$$

4) *Pitch-line circumference*.

$$B = \frac{3.14(17 + 7)}{2} = 37.7 \text{ inches}$$

5) *Number of pads*. Assume groove width of 0.5 inch, then

$$i_{app} = \frac{37.7}{5 + 0.5} = 6.85$$

Take $i = 6$.

6) *Length of pad*.

$$b = \frac{37.7 - 6 \times 0.5}{6} = 5.78 \text{ inches}$$



Fig. 11. Oil-flow factor, Y_G, vs. diameter ratio D_1/D_2—tapered land bearings.*

7) *Taper values*. Interpolate in Table 2 to obtain

$$\delta_1 = 0.008 \text{ inch} \quad \text{and} \quad \delta_2 = 0.005 \text{ inch}$$

8) *Actual bearing unit load*.

$$p = \frac{70{,}000}{6 \times 5 \times 5.78} = 404 \text{ psi}$$

* See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

9) *Pitch-line velocity*.

$$U = \frac{37.7 \times 3600}{12} = 11{,}300 \text{ ft per min}$$

10) *Oil leakage factor*.

From Fig. 8, $Y_L = 2.75$

11) *Film-thickness factor*.

$$K = \frac{5.75 \times 10^6 \times 404}{11{,}300 \times 2.75 \times 18} = 4150$$

12) *Minimum film thickness*.

From Fig. 9, $h = 2.2$ mils

13) *Friction power loss*. From Fig. 10, $J = 260$, then

$$P_f = 8.79 \times 10^{-13} \times 6 \times 5 \times 5.78 \times 260 \times 11{,}300^2 \times 18 = 91 \text{ hp}$$

14) *Required oil flow*.

$$Q = \frac{42.4 \times 91}{3.5 \times 50} = 22.0 \text{ gpm}$$

See footnote on page 2243.

15) *Shape factor*.

$$Y_S = \frac{8 \times 5 \times 5.78}{17^2 - 7^2} = 0.963$$

16) *Oil-flow factor*.

From Fig. 11, $Y_G = 0.61$

where $D_i/D_2 = 0.41$

17) *Actual oil film flow*.

$$Q_F = \frac{8.9 \times 10^{-4} \times 6 \times 0.005 \times 17^3 \times 3600 \times 0.61 \times 0.963^2}{17 - 7} = 26.7 \text{ gpm}$$

Because calculated film flow exceeds required oil flow, chamfers are not necessary. However, if film flow were less than required, suitable chamfers would be needed.

Table 2. Taper Values for Tapered Land Thrust Bearings

Pad Dimensions, Inches	Taper, Inch	
$a \times b$	$\delta_1 = h_2 - h_1$ (at ID)	$\delta_2 = h_2 - h_1$ (at OD)
½ × ½	0.0025	0.0015
1 × 1	0.005	0.003
3 × 3	0.007	0.004
7 × 7	0.009	0.006

Tilting Pad Thrust Bearing Design.— The following steps define the performance of a tilting pad thrust bearing, one section of which is shown in Fig. 12. Although each bearing section is wedge shaped, as shown at the right below, for the purposes of design calculation, it is considered to be a rectangle with a length b equal to the circumferential length along the pitch line of the section being considered and a width a equal to the difference in the external and internal radii, as shown at left in Fig. 12. The location of the pivot shown in Fig. 12 is optimum. If shaft rotation in both directions is required, however, the pivot must be at the midpoint, which results in little or no detrimental effect on the performance.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 12. Basic elements of tilting pad thrust bearing.*

1) *Inside diameter, D_1.* Determined by shaft size and clearance.

2) *Outside diameter, D_2.* Calculated from the formula

$$D_2 = \left(\frac{4W}{\pi K_g p} + D_1^2\right)^{1/2}$$

where W = applied load, pounds
$K_g = 0.8$
p = unit load from Table 1

3) *Radial pad width, a.* Equal to one-half the difference between the inside and outside diameters:

$$a = \frac{D_2 - D_1}{2}$$

4) *Pitch-line circumference, B.* Found from the mean diameter:

$$B = \pi\left(\frac{D_1 + D_2}{2}\right)$$

5) *Number of pads, i.* The number of pads may be estimated from the formula

$$i = \frac{BK_g}{a}$$

Select the nearest even number.

6) *Length of pad, b.* Found from the formula

$$b \cong \frac{BK_g}{i}$$

7) *Pitch-line velocity, U.* Calculated in feet per minute from the formula

$$U = \frac{BN}{12}$$

8) *Bearing unit load, p.* Calculated from the formula

$$p = \frac{W}{iab}$$

9) *Operating number, O.* Calculated from the formula

$$O = \frac{1.45 \times 10^{-7} Z_2 U}{5pb}$$

10) where Z_2 = viscosity of oil at outlet temperature (inlet temperature plus assumed temperature rise through the bearing).

* See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

11) *Minimum film thickness,* h_{min}. By using the operating number, the value of α = dimensionless film thickness is found from Fig. 13. Then the actual minimum film thickness is calculated from the formula:

$$h_{min} = \alpha b$$

In general, this value should be 0.001 inch for small bearings and 0.002 inch for larger and high-speed bearings.

12) *Coefficient of friction, f*. Found from Fig. 14.

13) *Friction power loss,* P_f. This horsepower loss now is calculated by the formula

$$P_f = \frac{fWU}{33,000}$$

14) *Actual oil flow,* Q. This flow over the pad in gallons per minute is calculated from the formula

$$Q = 0.0591 \alpha i a b U$$

15) *Temperature rise,* Δt. Found from the formula

$$\Delta t = 0.0217 \frac{fp}{\alpha c}$$

where c = specific heat of oil in Btu/gal/°F

If the flow is insufficient, as indicated by too high a temperature rise, chamfers can be added to provide adequate flow, as in Steps 12–15 of the flat plate thrust bearing design.

Example: Design a tilting pad thrust bearing for 70,000 pounds thrust at 3600 rpm. The shaft diameter is 6.5 inches and a maximum OD of 15 inches is available. The oil inlet temperature is 110°F and the supply pressure is 20 pounds per square inch. A maximum temperature rise of 50°F is acceptable and results in a viscosity of 18 centipoises. Use a value of 3.5 Btu/gal/°F for c.

1) *Inside diameter*. Assume $D_1 = 7$ inches to clear shaft.

2) *Outside diameter*. Given maximum $D_2 = 15$ inches.

3) *Radial pad width*.

$$a = \frac{15 - 7}{2} = 4 \text{ inches}$$

4) *Pitch-line circumference*.

$$B = \pi\left(\frac{7 + 15}{2}\right) = 34.6 \text{ inches}$$

5) *Number of pads*.

$$i = \frac{34.6 \times 0.8}{4} = 6.9$$

Select 6 pads: $i = 6$.

6) *Length of pad*.

$$b = \frac{34.6 \times 0.8}{6} = 4.61 \text{ inches}$$

Make $b = 4.75$ inches.

7) *Pitch-line velocity*.

$$U = \frac{34.6 \times 3600}{12} = 10,400 \text{ ft/min}$$

8) *Bearing unit load*.

$$p = \frac{70,000}{6 \times 4 \times 4.75} = 614 \text{ psi}$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 13. Dimensionless minimum film thickness, α, vs. operating number, *O*—tilting pad thrust bearings.*



Fig. 14. Coefficient of friction *f* vs. dimensionless film thickness α for tilting pad thrust bearings with optimum pivot location.*

* See footnote on page 2243.

Copyright 2004, Industrial Press, Inc., New York, NY

9) *Operating number*.

$$O = \frac{1.45\times10^{-7} \times 18 \times 10,400}{5 \times 614 \times 4.75} = 1.86\times10^{-6}$$

10) *Minimum film thickness*. From Fig. 13, $\alpha = 0.30 \times 10^{-3}$.

$$h_{min} = 0.00030 \times 4.75 = 0.0014 \text{ inch}$$

11) *Coefficient of friction*. From Fig. 14, $f = 0.0036$.

12) *Friction power loss*.

$$P_f = \frac{0.0036 \times 70,000 \times 10,400}{33,000} = 79.4 \text{ hp}$$

13) *Oil flow*.

$$Q = 0.0591 \times 6 \times 0.30 \times 10^{-3} \times 4 \times 4.75 \times 10,400 = 21.02 \text{ gpm}$$

14) *Temperature rise*.

$$\Delta t = \frac{0.0217 \times 0.0036 \times 614}{0.30 \times 10^{-3} \times 3.5} = 45.7^{\circ}\text{F}$$

Because this temperature is less than the 50°F, which is considered as the acceptable maximum, the design is satisfactory.

Plain Bearing Materials

Materials used for sliding bearings cover a wide range of metals and nonmetals. To make the optimum selection requires a complete analysis of the specific application. The important general categories are: Babbitts, alkali-hardened lead, cadmium alloys, copper lead, aluminum bronze, silver, sintered metals, plastics, wood, rubber, and carbon graphite.

Properties of Bearing Materials.— For a material to be used as a plain bearing, it must possess certain physical and chemical properties that permit it to operate properly. If a material does not possess all of these characteristics to some degree, it will not function long as a bearing. It should be noted, however, that few, if any, materials are outstanding in all these characteristics. Therefore, the selection of the optimum bearing material for a given application is at best a compromise to secure the most desirable combination of properties required for that particular usage.

The seven properties generally acknowledged to be the most significant are: 1) Fatigue resistance; 2) Embeddability; 3) Compatibility; 4) Conformability; 5) Thermal conductivity; 6) Corrosion resistance; and 7) Load capacity.

These properties are described as follows:

1) *Fatigue resistance* is the ability of the bearing lining material to withstand repeated applications of stress and strain without cracking, flaking, or being destroyed by some other means.

2) *Embeddability* is the ability of the bearing lining material to absorb or embed within itself any of the larger of the small dirt particles present in a lubrication system. Poor embeddability permits particles circulating around the bearing to score both the bearing surface and the journal or shaft. Good embeddability will permit these particles to be trapped and forced into the bearing surface and out of the way where they can do no harm.

3) *Compatibility or antiscoring tendencies* permit the shaft and bearing to "get along" with each other. It is the ability to resist galling or seizing under conditions of metal-to-metal contact such as at startup. This characteristic is most truly a bearing property, because contact between the bearing and shaft in good designs occurs only at startup.

4) *Conformability* is defined as malleability or as the ability of the bearing material to creep or flow slightly under load, as in the initial stages of running, to permit the shaft and bearing contours to conform with each other or to compensate for nonuniform loading caused by misalignment.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Bearing and Bushing Alloys—Composition, Forms, Characteristics, and Applications *SAE General Information*

SAE No. and Alloy Grouping		Nominal Composition, Per cent	Form of Use (1), Characteristics (2), and Applications (3)
Sn-Base Alloys	11	Sn, 87.5; Sb, 6.75; Cu, 5.75	(1) Cast on steel, bronze, or brass backs, or directly in the bearing housing. (2) Soft, corrosion-resistant with moderate fatigue resistance. (3) Main and connecting-rod bearings; motor bushings. Operates with either hard or soft journal.
	12	Sn, 89; Sb,7.5; Cu, 3.5	
Pb-Base Alloys	13	Pb, 84; Sb, 10; Sn, 6	(1) SAE 13 and 14 are cast on steel, bronze, or brass, or in the bearing housing; SAE 15 is cast on steel; and SAE 16 is cast into and on a porous sintered matrix, usually copper-nickel bonded to steel. (2) Soft, moderately fatigue-resistant, corrosion-resistant. (3) Main and connecting-rod bearings. Operates with hard or soft journal with good finish.
	14	Pb, 75; Sb, 15; Sn, 10	
	15	Pb, 83; Sb,15; Sn,14; As,1	
	16	Pb, 92; Sb, 3.5;Sn, 4.5	
Pb-Sn Overlays	19	Pb, 90; Sn, 10	(1) Electrodeposited as a thin layer on copper-lead or silver bearings faces. (2) Soft, corrosion-resistant. Bearings so coated run satisfactorily against soft shafts throughout the life of the coating. (3) Heavy-duty, high-speed main and connecting-rod bearings.
	190	Pb, 93; Sn, 7	
Cu-Pb Alloys	49	Cu, 76; Pb, 24	(1) Cast or sintered on steel back with the exception of SAE 481, which is cast on steel back only. (2) Moderately hard. Somewhat subject to oil corrosion. Some oils minimize this; protection with overlay may be desirable. Fatigue resistance good to fairly good. Listed in order of decreasing hardness and fatigue resistance. (3) Main and connecting-rod bearings. The higher lead alloys can be used unplated against a soft shaft, although an overlay is helpful. The lower lead alloys may be used against a hard shaft, or with an overlay against a soft one.
	48	Cu, 70; Pb, 30	
	480	Cu, 65; Pb, 35	
	481	Cu, 60; Pb, 40	
Cu-Pb-Sn-Alloys	482	Cu, 67; Pb, 28; Sn, 5	(1) Steel-backed and lined with a structure combining sintered copper alloy matrix with corrosion-resistant lead alloy. (2) Moderately hard. Corrosion resistance improved over copper-leads of equal lead content without tin. Fatigue resistance fairly good. Listed in order of decreasing hardness and fatigue resistance. (3) Main and connecting-rod bearings. Generally used without overlay. SAE 484 and 485 may be used with hard or soft shaft, and a hardened or cast shaft is recommended for SAE 482.
	484	Cu, 55; Pb, 42; Sn, 3	
	485	Cu, 46; Pb, 51; Sn, 3	
Al-Base Alloys	770	Al, 91.75; Sn, 6.25; Cu, 1; Ni, 1	(1) SAE 770 cast in permanent molds; work-hardened to improve physical properties. SAE 780 and 782 usually bonded to steel back but is procurable in strip form without steel backing. SAE 781 usually bonded to steel back but can be produced as castings or wrought strip without steel back. (2) Hard, extremely fatigue-resistant, resistant to oil corrosion. (3) Main and connecting-rod bearings. Generally used with suitable overlay. SAE 781 and 782 also used for bushings and thrust bearings with or without overlay.
	780	Al, 91; Sn, 6; Si, 1.5; Cu, 1; Ni, 0.5	
	781	Al, 95; Si, 4; Cd, 1	
	782	Al, 95; Cu, 1;Ni, 1; Cd, 3	
Other Cu-Base Alloys	795	Cu, 90; Zn, 9.5; Sn, 0.5	(1) Wrought solid bronze, (2) Hard, strong, good fatigue resistance, (3) Intermediate-load oscillating motion such as tie-rods and brake shafts.
	791	Cu, 88; Zn,4;Sn,4; Pb, 4	(1) SAE 791, wrought solid bronze; SAE 793, cast on steel back; SAE 798, sintered on steel back. (2) General-purpose bearing material, good shock and load capacity. Resistant to high temperatures. Hard shaft desirable. Less score-resistant than higher lead alloys. (3) Medium to high loads. Transmission bushings and thrust washers. SAE 791 also used for piston pin and 793 and 798 for chassis bushings.
	793	Cu, 84; Pb, 8; Sn, 4; Zn, 4	
	798	Cu, 84; Pb, 8; Sn,4; Zn, 4	
Other Cu-Base Alloys	792	Cu, 80; Sn, 10; Pb, 10	(1) SAE 792, cast on steel back, SAE 797, sintered on steel back. (2) Has maximum shock and load-carrying capacity of conventional cast bearing alloys; hard, both fatigue- and corrosion-resistant. Hard shaft desirable. (3) Heavy loads with oscillating or rotating motion. Used for piston pins, steering knuckles, differential axles, thrust washers, and wear plates.
	797	Cu, 80; Sn, 10; Pb, 10	
	794	Cu, 73.5; Pb, 23; Sn, 3.5	(1) SAE 794, cast on steel back; SAE 799, sintered on steel back. (2) Higher lead content gives improved surface action for higher speeds but results in somewhat less corrosion resistance. (3) Intermediate load application for both oscillating and rotating shafts, that is, rocker-arm bushings, transmissions, and farm implements.
	799	Cu, 73.5,; Pb, 23; Sn, 3.5	

Copyright 2004, Industrial Press, Inc., New York, NY

5) *High thermal conductivity* is required to absorb and carry away the heat generated in the bearing. This conductivity is most important, not in removing frictional heat generated in the oil film, but in preventing seizures due to hot spots caused by local asperity breakthroughs or foreign particles.

6) *Corrosion resistance* is required to resist attack by organic acids that are sometimes formed in oils at operating conditions.

7) *Load capacity or strength* is the ability of the material to withstand the hydrodynamic pressures exerted upon it during operation.

Babbitt or White Metal Alloys.— Many different bearing metal compositions are referred to as babbitt metals. The exact composition of the original babbitt metal is not known; however, the ingredients were probably tin, copper, and antimony in approximately the following percentages: 89.3, 3.6, and 7.1. Tin and lead-base babbitts are probably the best known of all bearing materials. With their excellent embeddability and compatibility characteristics under boundary lubrication, babbitt bearings are used in a wide range of applications including household appliances, automobile and diesel engines, railroad cars, electric motors, generators, steam and gas turbines, and industrial and marine gear units.

Table 4. White Metal Bearing Alloys—Composition and Properties
ASTM B23-83, reapproved 1988

ASTM Alloy[a] Number	Nominal Composition, Per Cent				Compressive Yield Point,[b] psi		Ultimate Compressive Strength,[c] psi		Brinell Hardness[d]		Melting Point °F	Proper Pouring Temperature, °F
	Sn	Sb	Pb	Cu	68 °F	212 °F	68 °F	212 °F	68 °F	212 °F		
1	91.0	4.5	…	4.5	4400	2650	12,850	6950	17.0	8.0	433	825
2	89.0	7.5	…	3.5	6100	3000	14,900	8700	24.5	12.0	466	795
3	83.33	8.33	…	8.33	6600	3150	17,600	9900	27.0	14.5	464	915
4	75.0	12.0	10.0	3.0	5550	2150	16,150	6900	24.5	12.0	363	710
5	65.0	15.0	18.0	2.0	5050	2150	15,050	6750	22.5	10.0	358	690
6	20.0	15.0	63.5	1.5	3800	2050	14,550	8050	21.0	10.5	358	655
7[e]	10.0	15.0	bal.	…	3550	1600	15,650	6150	22.5	10.5	464	640
8[e]	5.0	15.0	bal.	…	3400	1750	15,600	6150	20.0	9.5	459	645
10	2.0	15.0	83.0	…	3350	1850	15,450	5750	17.5	9.0	468	630
11	…	15.0	85.0	…	3050	1400	12,800	5100	15.0	7.0	471	630
12	…	10.0	90.0	…	2800	1250	12,900	5100	14.5	6.5	473	625
15[f]	1.0	16.0	bal.	0.5	…	…	…	…	21.0	13.0	479	662
16	10.0	12.5	77.0	0.5	…	…	…	…	27.5	13.6	471	620
19	5.0	9.0	86.0	…	…	…	15,600	6100	17.7	8.0	462	620

[a] Data for ASTM alloys 1, 2, 3, 7, 8, and 15 appear in the Appendix of ASTM B23-83; the data for alloys 4, 5, 6, 10, 11, 12, 16, and 19 are given in ASTM B23-49. All values are for reference purposes only.

[b] The values for yield point were taken from stress-strain curves at the deformation of 0.125 per cent reduction of gage.

[c] The ultimate strength values were taken as the unit load necessary to produce a deformation of 25 per cent of the length of the specimen.

[d] These values are the average Brinell number of three impressions on each alloy using a 10-mm ball and a 500-kg load applied for 30 seconds.

[e] Also nominal arsenic, 0.45 per cent.

[f] Also nominal arsenic, 1 per cent.

The compression test specimens were cylinders 1.5 inches in length and 0.5 inch in diameter, machined from chill castings 2 inches in length and 0.75 inch in diameter. The Brinell tests were made on the bottom face of parallel machined specimens cast in a 2-inch diameter by 0.625-inch deep steel mold at room temperature.

Copyright 2004, Industrial Press, Inc., New York, NY

Both the Society of Automotive Engineers and American Society for Testing and Materials have classified white metal bearing alloys. Tables 3 and 4 give compositions and properties or characteristics for the two classifications.

In small bushings for fractional-horsepower motors and in automotive engine bearings, the babbitt is generally used as a thin coating over a flat steel strip. After forming oil distribution grooves and drilling required holes, the strip is cut to size, then rolled and shaped into the finished bearing. These bearings are available for shaft diameters from 0.5 to 5 inches. Strip bearings are turned out by the millions yearly in highly automated factories and offer an excellent combination of low cost with good bearing properties.

For larger bearings in heavy-duty equipment, a thicker babbitt is cast on a rigid backing of steel or cast iron. Chemical and electrolytic cleaning of the bearing shell, thorough rinsing, tinning, and then centrifugal casting of the babbitt are desirable for sound bonding of the babbitt to the bearing shell. After machining, the babbitt layer is usually ½ to ¼ inch thick.

Compared to other bearing materials, babbitts generally have lower load-carrying capacity and fatigue strength, are a little higher in cost, and require a more complicated design. Also, their strength decreases rapidly with increasing temperature. These shortcomings can be avoided by using an intermediate layer of high-strength, fatigue-resistant material that is placed between a steel backing and a thin babbitt surface layer. Such composite bearings frequently eliminate any need for using alternate materials having poorer bearing characteristics.

Tin babbitt is composed of 80 to 90 per cent tin to which is added about 3 to 8 per cent copper and 4 to 14 per cent antimony. An increase in copper or antimony produces increased hardness and tensile strength and decreased ductility. However, if the percentages of these alloys are increased above those shown in Table 4, the resulting alloy will have decreased fatigue resistance. These alloys have very little tendency to cause wear to their journals because of their ability to embed dirt. They resist the corrosive effects of acids, are not prone to oil-film failure, and are easily bonded and cast. Two drawbacks are encountered from use of these alloys because they have low fatigue resistance and their hardness and strength drop appreciably at low temperatures.

Lead babbitt compositions generally range from 10 to 15 per cent antimony and up to 10 per cent tin in combination with the lead. Like tin-base babbitts, these alloys have little tendency to cause wear to their journals, embed dirt well, resist the corrosive effects of acids, are not prone to oil-film failure and are easily bonded and cast. Their chief disadvantages when compared with tin-base alloys are a rather lower strength and a susceptibility to corrosion.

Cadmium Base.— Cadmium alloy bearings have a greater resistance to fatigue than babbitt bearings, but their use is very limited due to their poor corrosion resistance. These alloys contain 1 to 15 per cent nickel, or 0.4 to 0.75 per cent copper, and 0.5 to 2.0 per cent silver. Their prime attribute is their high-temperature capability. The load-carrying capacity and relative basic bearing properties are shown in Table 5.

Copper-Lead.— Copper-lead bearings are a binary mixture of copper and lead containing from 20 to 40 per cent lead. Lead is practically insoluble in copper, so a cast microstructure consists of lead pockets in a copper matrix. A steel backing is commonly used with this material and high volume is achieved either by continuous casting or by powder metallurgy techniques. This material is very often used with an overplate such as lead-tin and lead-tin-copper to increase basic bearing properties. Table 5 provides comparisons of material properties.

The combination of good fatigue strength, high-load capacity, and high-temperature performance has resulted in extensive use of this material for heavy-duty main and connecting-rod bearings as well as moderate-load and speed applications in turbines and electric motors.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Properties of Bearing Alloys and Bearing Characteristics Ratings

Material	Recommended Shaft Hardness, Brinell	Load-Carrying Capacity, psi	Maximum Operating Temp., °F	Compatibility [a]	Conformability and Embeddability [a]	Corrosion Resistance [a]	Fatigue Strength [a]
Tin-Base Babbitt	150 or less	800 – 1500	300	1	1	1	5
Lead-Base Babbitt	150 or less	800 – 1200	300	1	1	3	5
Cadmium Base	200 – 250	1200 – 2000	500	1	2	5	4
Copper-Lead	300	1500 – 2500	350	2	2	5	3
Tin-Bronze	300 – 400	4000+	500+	3	5	2	1
Lead-Bronze	300	3000 – 4500	450 – 500	3	4	4	2
Aluminum	300	4000+	225 – 300	5	3	1	2
Silver-Overplate	300	4000+	500	2	3	1	1
Trimetal-Overplate	230 or less	2000 – 4000+	225 – 300	1	2	2	3

[a] *Note:* 1 is best; 5 is worst.

Leaded Bronze and Tin-Bronze.— Leaded and tin-bronzes contain up to 25 per cent lead or approximately 10 per cent tin, respectively. Cast leaded bronze bearings offer good compatibility, excellent casting, and easy machining characteristics, low cost, good structural properties and high-load capacity, usefulness as a single material that requires neither a separate overlay nor a steel backing. Bronzes are available in standard bar stock, sand or permanent molds, investment, centrifugal or continuous casting. Leaded bronzes have better compatibility than tin-bronzes because the spheroids of lead smear over the bearing surface under conditions of inadequate lubrication. These alloys are generally a first choice at intermediate loads and speeds. Table 5 provides comparisons of basic bearing properties of these materials.

Aluminum.— Aluminum bearings are either cast solid aluminum, aluminum with a steel backing, or aluminum with a suitable overlay. The aluminum is usually alloyed with small amounts of tin, silicon, cadmium, nickel, or copper, as shown in Table 3. An aluminum bearing alloy with 20 to 30 per cent tin alloy and up to 3 per cent copper has shown promise as a substitute for bronzes in some industrial applications.

These bearings are best suited for operation with hard journals. Owing to the high thermal expansion of the metal (resulting in diametral contraction when it is confined as a bearing in a rigid housing), large clearances are required, which tend to make the bearing noisy, especially on starting. Overlays of lead-tin, lead, or lead-tin-copper may be applied to aluminum bearings to facilitate their use with soft shafts.

Aluminum alloys are available with properties specifically designed for bearing applications, such as high load-carrying capacity, fatigue strength, and thermal conductivity, in addition to excellent corrosion resistance and low cost.

Silver.— Silver bearings were developed for and have an excellent record in heavy-duty applications such as aircraft master rod and diesel engine main bearings. Silver has a higher fatigue rating than any of the other bearing materials; the steel backing used with this material may show evidence of fatigue before the silver. The advent of overlays, or more commonly called overplates, made it possible for silver to be used as a bearing material. Silver by itself does not possess any of the desirable bearing qualities except high fatigue resistance and high thermal conductivity. The overlays such as lead, lead-tin, or lead-indium improve the embeddability and antiscoring properties of silver. The relative basic properties of this material, when used as an overplate, are shown in Table 5.

Cast Iron.— Cast iron is an inexpensive bearing material capable of operation at light loads and low speeds, i.e., up to 130 ft/min and 150 lb/in.^{2} These bearings must be well

Copyright 2004, Industrial Press, Inc., New York, NY

lubricated and have a rather large clearance so as to avoid scoring from particles torn from the cast iron that ride between bearing and journal. A journal hardness of between 150 and 250 Brinell has been found to be best when using cast-iron bearings.

Porous Metals.— Porous metal self-lubricating bearings are usually made by sintering metals such as plain or leaded bronze, iron, and stainless steel. The sintering produces a spongelike structure capable of absorbing fairly large quantities of oil, usually 10–35 per cent of the total volume. These bearings are used where lubrication supply is difficult, inadequate, or infrequent. This type of bearing should be flooded from time to time to resaturate the material. Another use of these porous materials is to meter a small quantity of oil to the bearings such as in drip feed systems. The general design operating characteristics of this class of materials are shown in Table 6.

Table 6. Application Limits — Sintered Metal and Nonmetallic Bearings

Bearing Material	Load Capacity (psi)	Maximum Temperature (°F)	Surface Speed, V_{max} (max. fpm)	PV Limit P = psi load V = surface ft/min
Acetal	1000	180	1000	3000
Graphite (dry)	600	750	2500	15,000
Graphite (lubricated)	600	750	2500	150,000
Nylon, Polycarbonate	1000	200	1000	3000
Nylon composite	…	400	…	16,000
Phenolics	6000	200	2500	15,000
Porous bronze	4500	160	1500	50,000
Porous iron	8000	160	800	50,000
Porous metals	4000–8000	150	1500	50,000
Virgin Teflon (TFE)	500	500	50	1000
Reinforced Teflon	2500	500	1000	10,000–15,000
TFE fabric	60,000	500	150	25,000
Rubber	50	150	4000	15,000
Maple & Lignum Vitae	2000	150	2000	15,000

Tables 7, 8, and 9 give the chemical compositions, permissible loads, interference fits, and running clearances of bronze-base and iron-base metal-powder sintered bearings that are specified in the ASTM specifications for oil-impregnated metal-powder sintered bearings (B438-83a and B439-83).

Plastics Bearings.— Plastics are finding increased use as bearing materials because of their resistance to corrosion, quiet operation, ability to be molded into many configurations, and their excellent compatibility, which minimizes or eliminates the need for lubrication. Many plastics are capable of operating as bearings, especially phenolic, tetrafluoroethylene (TFE), and polyamide (nylon) resins. The general application limits for these materials are shown in Table 6.

Laminated Phenolics: These composite materials consist of cotton fabric, asbestos, or other fillers bonded with phenolic resin. They have excellent compatibility with various fluids as well as strength and shock resistance. However, precautions must be taken to maintain adequate bearing cooling because the thermal conductivity of these materials is low.

Nylon: This material has the widest use for small, lightly loaded applications. It has low frictional properties and requires no lubrication.

Teflon: This material, with its exceptional low coefficient of friction, self-lubricating characteristics, resistance to attack by almost any chemicals, and its wide temperature

Copyright 2004, Industrial Press, Inc., New York, NY

range, is one of the most interesting of the plastics for bearing use. High cost combined with low load capacity cause Teflon to be selected mostly in modified form, where other less expensive materials have proved inadequate for design requirements.

Bearings made of laminated phenolics, nylon, or Teflon are all unaffected by acids and alkalies except if highly concentrated and therefore can be used with lubricants containing dilute acids or alkalies. Water is used to lubricate most phenolic laminate bearings but oil, grease, and emulsions of grease and water are also used. Water and oil are used as lubricants for nylon and Teflon bearings. Almost all types of plastic bearings absorb water and oil to some extent. In some the dimensional change caused by the absorption may be as much as three per cent in one direction. This means that bearings have to be treated before use so that proper clearances will be kept. This may be done by boiling in water, for water lubricated bearings. Boiling in water makes bearings swell the maximum amount. Clearances for phenolic bearings are kept at about 0.001 inch per inch of diameter on treated bearings. Partially lubricated or dry nylon bearings are given a clearance of 0.004 to 0.006 inches for a one-inch diameter bearing.

Rubber: Rubber bearings give excellent performance on propeller shafts and rudders of ships, hydraulic turbines, pumps, sand and gravel washers, dredges and other industrial equipment that handle water or slurries. The resilience of rubber helps to isolate vibration and provide quiet operation, allows running with relatively large clearances and helps to compensate for misalignment. In these bearings a fluted rubber structure is supported by a metal shell. The flutes or scallops in the rubber form a series of grooves through which lubricant or, as generally used, water and foreign material such as sand may pass through the beating.

Wood.— Bearings made from such woods as lignum vitae, rock maple, or oak offer self-lubricating properties, low cost, and clean operation. However, they have frequently been displaced in recent years by various plastics, rubber and sintered-metal bearings. General applications are shown in Table 6.

Carbon-Graphite.— Bearings of molded and machined carbon-graphite are used where regular maintenance and lubrication cannot be given. They are dimensionally stable over a wide range of temperatures, may be lubricated if desired, and are not affected by chemicals. These bearings may be used up to temperatures of 700 to 750 degrees F. in air or 1200 degrees F. in a non-oxidizing atmosphere, and generally are operated at a maximum load of 20 pounds per square inch. In some instances a metal or metal alloy is added to the carbon-graphite composition to improve such properties as compressive strength and density. The temperature limitation depends upon the melting point of the metal or alloy and the maximum load is generally 350 pounds per square inch when used with no lubrication or 600 pounds per square inch when used with lubrication.

Normal running clearances for both types of carbon-graphite bearings used with steel shafts and operating at a temperature of less than 200 degrees F. are as follows: 0.001 inch for bearings of 0.187 to 0.500-inch inside diameter, 0.002 inch for bearings of 0.501 to 1.000-inch inside diameter, 0.003 inch for bearings of 1.001 to 1.250-inch inside diameter, 0.004 inch for bearings of 1.251 to 1.500-inch diameter, and 0.005 inch for bearings of 1.501 to 2.000-inch inside diameter. Speeds depend upon too many variables to list specifically so it can only be stated here that high loads require a low number of rpm and low loads permit a high number of rpm. Smooth journals are necessary in these bearings as rough ones tend to abrade the bearings quickly. Cast iron and hard chromium-plate steel shafts of 400 Brinell and over, and phosphor-bronze shafts over 135 Brinell are recommended.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Copper- and Iron-Base Sintered Bearings (Oil Impregnated) — *ASTM B438-83a (R1989) , B439-83 (R1989), and Appendices*

Chemical Requirements								
	Percentage Composition							
	Copper-Base Bearings				Iron-Base Bearings			
Alloying	Grade 1		Grade 2		Grades			
Elements[a]	Class A	Class B	Class A	Class B	1	2	3	4
Cu	87.5–99.5	87.5–90.5	87.5–90.5	87.5–90.5	…	…	7.0–11.0	18.0–22.0
Sn	9.5–10.5	9.5–10.5	9.5–10.5	9.5–10.5	…	…	…	…
Graphite	0.1 max.	1.75 max.	0.1 max.	1.75 max.	…	…	…	…
Pb	…	…	2.0–4.0	2.0–4.0	…	…	…	…
Fe	1.0 max.	1.0 max.	1.0 max.	1.0 max.	96.25 min.	95.9 min.	Balance[b]	Balance[b]
Comb. C[c]	…	…	…	…	0.25 max.	0.25–0.60	…	…
Si, max.	…	…	…	…	0.3	0.3	…	…
Al, max.	…	…	…	…	0.2	0.2	…	…
Others	0.5 max.	0.5 max.	1.0 max.	1.0 max.	3.0 max.	3.0 max.	3.0 max.	3.0 max.

[a] Abbreviations used for the alloying elements are as follows: Cu, copper; Fe, iron; Sn, tin; Pb, lead; Zn, zinc; Ni, nickel; Sb, antimony; Si, silicon; Al, aluminum; and C, carbon.

[b] Total of iron plus copper shall be 97 per cent, minimum.

[c] Combined carbon (on basis of iron only) may be a metallographic estimate of the carbon in the iron.

Permissible Loads						
Copper-Base Bearings				Iron-Base Bearings		
	Grades 1 & 2				Grades 1 & 2	Grades 3 & 4
	Type 1	Type 2	Types 3 & 4			
Shaft Velocity, fpm	Max. Load, psi			Shaft Velocity, fpm	Max. Load, psi	
Slow and intermittent	3200	4000	4000	Slow and intermittent	3600	8000
25	2000	2000	2000	25	1800	3000
50 to 100	500	500	550	50 to 100	450	700
Over 100 to 150	365	325	365	Over 100 to 150	300	400
Over 150 to 200	280	250	280	Over 150 to 200	225	300
Over 200		[a]	[a]	[a]	Over 200	[a]

[a] For shaft velocities over 200 fpm, the permissible loads may be calculated as follows: $P = 50{,}000/V$; where P = safe load, psi of projected area; and V = shaft velocity, fpm. With a shaft velocity of less than 50 fpm and a permissible load greater than 1,000 psi, an extreme pressure lubricant should be used; with heat dissipation and removal techniques, higher PV ratings can be obtained.

Clearances						
Press-Fit Clearances			Running Clearances[a]			
Copper- and Iron-Base			Copper-Base		Iron-Base	
Bearing OD	Min.	Max.	Shaft Size	Min. Clearance	Shaft Size	Min. Clearance
Up to 0.760	0.001	0.003	Up to 0.250	0.0003	Up to 0.760	0.0005
0.761–1.510	0.0015	0.004	0.250–0.760	0.0005	0.761–1.510	0.001
1.511–2.510	0.002	0.005	0.760–1.510	0.0010	1.511–2.510	0.0015
2.511–3.010	0.002	0.006	1.510–2.510	0.0015	Over 2.510	0.002
Over 3.010	0.002	0.007	Over 2.510	0.0020		

[a] Only minimum recommended clearances are listed. It is assumed that ground steel shafting will be used and that all bearings will be oil-impregnated.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Copper- and Iron-Base Sintered Bearings (Oil Impregnated) — *ASTM B438-83a (R1989) , B439-83 (R1989), and Appendices*

Commercial Dimensional Tolerances [a,b]							
Diameter Tolerance		Length Tolerance		Diameter Tolerance		Length Tolerance	
Copper Base				Iron Base			
Inside or Outside Diameter	Total Diameter Tolerances	Length	Total Length Tolerances	Inside or Outside Diameter	Total Diameter Tolerances	Length	Total Length Tolerances
Up to 1	0.001	Up to 1.5	0.01	Up to 0.760	–0.001	Up to 1.495	0.01
1 to 1.5	0.0015	1.5 to 3	0.01	0.761–1.510	–0.0015	1.496–1.990	0.02
1.5 to 2	0.002	3 to 4.5	0.02	1.511–2.510	–0.002	1.991–2.990	0.02
2 to 2.5	0.0025	…	…	2.511–3.010	–0.003	2.991–4.985	0.03
2.5 to 3	0.003	…	…	3.011–4.010	–0.005	…	…
…	…	…	…	4.011–5.010	–0.005	…	…
…	…	…	…	5.011–6.010	–0.006	…	…

Concentricity Tolerance [a,b,c]					
Iron Base			Copper Base		
Outside Diameter	Max. Wall Thickness	Concentricity Tolerance	Outside Diameter	Length	Concentricity Tolerance
Up to 1.510	Up to 0.355	0.003	Up to 1	0 to 1	0.00.
				1 to 2	0.004
				2 to 3	0.005
1.511 to 2.010	Up to 0.505	0.004	1 to 2	0 to 1	0.004
				1 to 2	0.005
				2 to 3	0.006
2.011 to 4.010	Up to 1.010	0.005	2 to 3	0 to 1	0.005
				1 to 2	0.006
				2 to 3	0.007
4.011 to 5.010	Up to 1.510	0.006			
5.011 to 6.010	Up to 2.010	0.007			

[a] For copper-base bearings with 4-to-1 maximum-length-diameter ratio and a 24-to-1 maximum-length-to-wall-thickness ratio; bearings with greater ratios are not covered here.

[b] For iron-base bearings with a 3-to-1 maximum-length-to-inside diameter ration and a 20-to-1 maximum-length-to-wall-thickness ratio; bearings with greater ratios are not covered here.

[c] Total indicator reading.

Table 9. Copper- and Iron-Base Sintered Bearings (Oil Impregnated) — *ASTM B438-83a (R1989) , B439-83 (R1989), and Appendices*

Diameter Range	Flange and Thrust Bearings, Diameter, and Thickness Tolerances[a]				Parallelism[a] on Faces, max.			
	Flange Diameter Tolerance		Flange Thickness Tolerance		Copper Base		Iron Base	
	Standard	Special	Standard	Special	Standard	Special	Standard	Special
0 to 1½	±0.005	±0.0025	±0.005	±0.0025	0.003	0.002	0.005	0.003
Over 1½ to 3	±0.010	±0.005	±0.010	±0.007	0.004	0.003	0.007	0.005
Over 3 to 6	±0.025	±0.010	±0.015	±0.010	0.005	0.004	0.010	0.007

[a] Standard and special tolerances are specified for diameters, thicknesses, and parallelism. Special tolerances should not be specified unless required because they require additional or secondary operations and, therefore, are costlier. Thrust bearings (¼ inch thickness, max.) have a standard thickness tolerance of ±0.005 inch and a special thickness tolerance of ±0.0025 inch for all diameters.

All dimensions in inches except where otherwise noted.

Copyright 2004, Industrial Press, Inc., New York, NY

BALL, ROLLER, AND NEEDLE BEARINGS

Rolling Contact Bearings

Rolling contact bearings substitute a rolling element, ball or roller, for a hydrodynamic or hydrostatic fluid film to carry an impressed load without wear and with reduced friction. Because of their greatly reduced starting friction, when compared to the conventional journal bearing, they have acquired the common designation of "anti-friction" bearings. Although normally made with hardened rolling elements and races, and usually utilizing a separator to space the rolling elements and reduce friction, many variations are in use throughout the mechanical and electrical industries. The most common anti-friction bearing application is that of the deep-groove ball bearing with ribbon-type separator and sealed-grease lubrication used to support a shaft with radial and thrust loads in rotating equipment. This shielded or sealed bearing has become a standard and commonplace item ordered from a supplier's catalogue in much the same manner as nuts and bolts. Because of the simple design approach and the elimination of a separate lubrication system or device, this bearing is found in as many installations as the wick-fed or impregnated porous plain bushing.

Currently, a number of manufacturers produce a complete range of ball and roller bearings in a fully interchangeable series with standard dimensions, tolerances and fits as specified in Anti-Friction Bearing Manufacturers Association (AFBMA) Standards. Except for deep-groove ball bearings, performance standards are not so well defined and sizing and selection must be done in close conformance with the specific manufacturer's catalogue requirements. In general, desired functional features should be carefully gone over with the vendor's representatives.

Rolling contact bearings are made to high standards of accuracy and with close metallurgical control. Balls and rollers are normally held to diametral tolerances of .0001 inch or less within one bearing and are often used as "gage" blocks in routine toolroom operations. This accuracy is essential to the performance and durability of rolling-contact bearings and in limiting runout, providing proper radial and axial clearances, and ensuring smoothness of operation.

Because of their low friction, both starting and running, rolling-contact bearings are utilized to reduce the complexity of many systems that normally function with journal bearings. Aside from this advantage and that of precise radial and axial location of rotating elements, however, they also are desirable because of their reduced lubrication requirements and their ability to function during brief interruptions in normal lubrication.

In applying rolling-contact bearings it is well to appreciate that their life is limited by the fatigue life of the material from which they are made and is modified by the lubricant used. In rolling-contact fatigue, precise relationships among life, load, and design characteristics are not predictable, but a statistical function described as the "probability of survival" is used to relate them according to equations recommended by the AFBMA. Deviations from these formulas result when certain extremes in applications such as speed, deflection, temperature, lubrication, and internal geometry must be dealt with.

Types of Anti-friction Bearings.— The general types are usually determined by the shape of the rolling element, but many variations have been developed that apply conventional elements in unique ways. Thus it is well to know that special bearings can be procured with races adapted to specific applications, although this is not practical for other than high volume configurations or where the requirements cannot be met in a more economical manner. "Special" races are appreciably more expensive. Quite often, in such situations, races are made to incorporate other functions of the mechanism, or are "submerged" in the surrounding structure, with the rolling elements supported by a shaft or housing that has been hardened and finished in a suitable manner. Typical anti-friction bearing types are shown in Tables 1a through 1g.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. Types of Rolling Element Bearings and Their Symbols

BALL BEARINGS, SINGLE ROW, RADIAL CONTACT			
Symbol	Description	Symbol	Description
BC	Non-filling slot assembly	BH	Non-separable counter-bore assembly
BL	Filling slot assembly	BM	Separable assembly
BALL BEARINGS, SINGLE ROW, ANGULAR CONTACT[a]			
Symbol	Description	Symbol	Description
BN	Non-separable Nominal contact angle: from above 10° to and including 22°	BAS	Separable inner ring Nominal contact angle: from above 22° to and including 32°
BNS	Separable outer ring Nominal contact angle: from above 10° to and including 22°	BT	Non-separable Nominal contact angle: from above 32° to and including 45°
BNT	Separable inner ring Nominal contact angle: from above 10° to and including 22°	BY	Two-piece outer ring
BA	Non-separable Nominal contact angle: from above 22° to and including 32°	BZ	Two-piece inner ring
BALL BEARINGS, SINGLE ROW, RADIAL CONTACT, SPHERICAL OUTSIDE SURFACE			
Symbol	Description	Symbol	Description
BCA	Non-filling slot assembly	BLA	Filling slot assembly

[a] A line through the ball contact points forms an acute angle with a perpendicular to the bearing axis.

Types of Ball Bearings.— Most types of ball bearings originate from three basic designs: the single-row radial, the single-row angular contact, and the double-row angular contact.

Single-row Radial, Non-filling Slot: This is probably the most widely used ball bearing and is employed in many modified forms. It is also known as the "Conrad" type or "Deep-groove" type. It is a symmetrical unit capable of taking combined radial and thrust loads in which the thrust component is relatively high, but is not intended for pure thrust loads, however. Because this type is not self-aligning, accurate alignment between shaft and housing bore is required.

Single-row Radial, Filling Slot: This type is designed primarily to carry radial loads. Bearings of this type are assembled with as many balls as can be introduced by eccentric displacement of the rings, as in the non-filling slot type, and then several more balls are inserted through the loading slot, aided by a slight spreading of the rings and heat expansion of the outer ring, if necessary. This type of bearing will take a certain degree of thrust when in combination with a radial load but is not recommended where thrust loads exceed 60 per cent of the radial load.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1b. Types of Rolling Element Bearings and Their Symbols

BALL BEARINGS, DOUBLE ROW, RADIAL CONTACT					
Symbol	Description		Symbol	Description	
BF	Filling slot assembly		BHA	Non-separable two-piece outer ring	
BK	Non-filling slot assembly				
BALL BEARINGS, DOUBLE ROW, ANGULAR CONTACT [a]					
Symbol	Description		Symbol	Description	
BD	Filling slot assembly Vertex of contact angles inside bearing		BG	Non-filling slot assembly Vertex of contact angles outside bearing	
BE	Filling slot assembly Vertex of contact angles outside bearing		BAA	Non-separable Vertex of contact angles inside bearing Two-piece outer ring	
BJ	Non-filling slot assembly Vertex of contact angles inside bearing		BVV	Separable Vertex of contact angles outside bearing Two-piece inner ring	
BALL BEARINGS, DOUBLE ROW, SELF-ALIGNING [a]					
Symbol	Description				
BS	Raceway of outer ring spherical				

[a] A line through the ball contact points forms an acute angle with a perpendicular to the bearing axis.

Single-row Angular-contact: This type is designed for combined radial and thrust loads where the thrust component may be large and axial deflection must be confined within very close limits. A high shoulder on one side of the outer ring is provided to take the thrust, while the shoulder on the other side is only high enough to make the bearing non-separable. Except where used for a pure thrust load in one direction, this type is applied either in pairs (duplex) or one at each end of the shaft, opposed.

Double-row Bearings: These are, in effect, two single-row angular-contact bearings built as a unit with the internal fit between balls and raceway fixed at the time of bearing assembly. This fit is therefore not dependent upon mounting methods for internal rigidity. These bearings usually have a known amount of internal preload built in for maximum resistance to deflection under combined loads with thrust from either direction. Thus, with balls and races under compression before an external load is applied, due to this internal preload, the bearings are very effective for radial loads where bearing deflection must be minimized.

Other Types: Modifications of these basic types provide arrangements for self-sealing, location by snap ring, shielding, etc., but the fundamentals of mounting are not changed. A special type is the *self-aligning* ball bearing which can be used to compensate for an appreciable degree of misalignment between shaft and housing due to shaft deflections, mount-

Copyright 2004, Industrial Press, Inc., New York, NY

ing inaccuracies, or other causes commonly encountered. With a single row of balls, alignment is provided by a spherical outer surface on the outer ring; with a double row of balls, alignment is provided by a spherical raceway on the outer ring. Bearings in the wide series have a considerable amount of thrust capacity.

Table 1c. Types of Rolling Element Bearings and Their Symbols

CYLINDRICAL ROLLER BEARING, SINGLE ROW, NON-LOCATING TYPE			
Symbol	Description	Symbol	Description
RU	Inner ring without ribs Double-ribbed outer ring Inner ring separable	RNS	Double-ribbed inner ring Outer ring without ribs Outer ring separable Spherical outside surface
RUP	Inner ring without ribs Double-ribbed outer ring with one loose rib Both rings separable	RAB	Inner ring without ribs Single-ribbed outer ring Both rings separable
RUA	Inner ring without ribs Double-ribbed outer ring Inner ring separable Spherical outside surface	RM	Inner ring without ribs Rollers located by cage, end-rings or internal snap rings recesses in outer ring Inner ring separable
RN	Double-ribbed inner ring Outer ring without ribs Outer ring separable	RNU	Inner ring without ribs Outer ring without ribs Both rings separable
CYLINDRICAL ROLLER BEARINGS, SINGLE ROW, ONE-DIRECTION-LOCATING TYPE			
Symbol	Description	Symbol	Description
RR	Single-ribbed inner-ring Outer ring with two internal snap rings Inner ring separable	RF	Double-ribbed inner ring Single-ribbed outer ring Outer ring separable
RJ	Single-ribbedinner ring Double-ribbed outer ring Inner ring separable	RS	Single-ribbed inner ring Outer ring with one rib and one internal snap ring Inner ring separable
RJP	Single-ribbed inner ring Double-ribbed outer ring with one loose rib Both rings separable	RAA	Single-ribbed inner ring Single-ribbed outer ring Both rings separable

Types of Roller Bearings.— Types of roller bearings are distinguished by the design of rollers and raceways to handle axial, combined axial and thrust, or thrust loads.

Cylindrical Roller: These bearings have solid or helically wound hollow cylindrical rollers. The free ring may have a restraining flange to provide some restraint to endwise movement in one direction or may be without a flange so that the bearing rings may be displaced axially with respect to each other. Either rolls or roller path on the races may be slightly crowned to prevent edge loading under slight shaft misalignment. Low friction makes this type suitable for relatively high speeds.

Barrel Roller: These bearings have rollers that are barrel-shaped and symmetrical. They are furnished in both single- and double-row mountings. As with cylindrical roller bearings, the single-row mounting type has a low thrust capacity, but angular mounting of rolls in the double-row type permits its use for combined axial and thrust loads.

Spherical Roller: These bearings are usually furnished in a double-row, self-aligning mounting. Both rows of rollers have a common spherical outer raceway. The rollers are

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1d. Types of Rolling Element Bearings and Their Symbols

CYLINDRICAL ROLLER BEARINGS, SINGLE ROW, TWO-DIRECTION-LOCATING TYPE			
Symbol	Description	Symbol	Description
RK	Double-ribbed inner ring Outer ring with two internal snap rings Non-separable	RY	Double-ribbed inner ring Outer ring with one rib and one internal snap ring Non-separable
RC	Doble-ribbed inner ring Double-ribbed outer ring Non-separable	RCS	Double-ribbed inner ring Double-ribbed outer ring Non-separable Spherical outside surface
RG	Inner ring, with one rib and one snap ring Double-ribbed outer ring Non-separable		
RP	Double-ribbed inner ring Double-ribbed outer ring with one loose rib Outer ring separable	RT	Double-ribbed inner ring with one loose rib Double-ribbed outer ring Inner ring separable
CYLINDRICAL ROLLER BEARINGS			
Double Row Non-Locating Type		Double Row Two-Direction-Locating Type	
Symbol	Description	Symbol	Description
RA	Inner ring without ribs Three integral ribs on outer ring Inner ring separable	RB	Three integral ribs on inner ring Outer ring without ribs, with two internal snap rings Non-separable
RD	Three integral ribs on inner ring Outer ring without ribs Outer ring separable	Multi-Row Non-Locating Type	
		Symbol	Description
RE	Inner ring without ribs Outer rings without ribs, with two internal snap rings Inner ring separable	RV	Inner ring without ribs Double-ribbed outer ring (loose ribs) Both rings separable

barrel-shaped with one end smaller than the other to provide a small thrust to keep the rollers in contact with the center guide flange. This type of roller bearing has a high radial and thrust load carrying capacity with the ability to maintain this capacity under some degree of misalignment of shaft and bearing housing.

Tapered Roller: In this type, straight tapered rollers are held in accurate alignment by means of a guide flange on the inner ring. The basic characteristic of these bearings is that the apexes of the tapered working surfaces of both rollers and races, if extended, would coincide on the bearing axis. These bearings are separable. They have a high radial and thrust carrying capacity.

Types of Ball and Roller Thrust Bearings.— Are designed to take thrust loads alone or in combination with radial loads.

One-direction Ball Thrust: These bearings consist of a shaft ring and a flat or spherical housing ring with a single row of balls between. They are capable of carrying pure thrust loads in one direction only. They cannot carry any radial load.

Two-direction Ball Thrust: These bearings consist of a shaft ring with a ball groove in either side, two sets of balls, and two housing rings so arranged that thrust loads in either direction can be supported. No radial loads can be carried.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1e. Types of Rolling Element Bearings and Their Symbols

SELF-ALIGNING ROLLER BEARINGS, DOUBLE ROW			
Symbol	Description	Symbol	Description
SD	Three integral ribs on inner ring Raceway of outer ring spherical	SL	Raceway of outer ring spherical Rollers guided by the cage Two integral ribs on inner ring
SE	Raceway of outer ring spherical Rollers guided by separate center guide ring in outer ring	SELF-ALIGNING ROLLER BEARINGS SINGLE ROW	
		Symbol	Description
SW	Raceway of inner ring spherical	SR	Inner ring with ribs Raceway of outer ring spherical Radial contact
SC	Raceway of outer ring spherical Rollers guided by separate axially floating guide ring on inner ring	SA	Raceway of outer ring spherical Angular contact
		SB	Raceway of inner ring spherical Angular contact
THRUST BALL BEARINGS			
Symbol	Description	Symbol	Description
TA TB[a]	Single direction, grooved raceways, flat seats	TDA	Double direction, washers with grooved raceways, flat seats
TBF[a]	Single direction, flat washers, flat seats		
THRUST ROLLER BEARINGS			
Symbol	Description	Symbol	Description
TS	Single direction, aligning flat seats, spherical rollers	TPC[a]	Single direction, flat seats, flat races, outside band, cylindrical rollers
TP	Single direction, flat seats, cylindrical rollers	TR[a]	Single direction, flat races, aligning seat with aligning washer, cylindrical rollers

[a] Inch dimensioned only.

Spherical Roller Thrust: This type is similar in design to the radial spherical roller bearing except that it has a much larger contact angle. The rollers are barrel shaped with one end smaller than the other. This type of bearing has a very high thrust load carrying capacity and can also carry radial loads.

Tapered Roller Thrust: In this type the rollers are tapered and several different arrangements of housing and shaft are used.

Roller Thrust: In this type the rollers are straight and several different arrangements of housing and shaft are used.

Types of Needle Bearings.— Needle bearings are characterized by their relatively small size rollers, usually not above ¼ inch in diameter, and a relatively high ratio of length to diameter, usually ranging from about 3 to 1 and 10 to 1. Another feature that is characteris-

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1f. Types of Rolling Element Bearings and Their Symbols

TAPERED ROLLER BEARINGS — INCH			
Symbol	Description	Symbol	Description
TS	Single row	TDI	Two row, double-cone single cups 
TDO	Two row, double-cup single-cone adjustable	TNA	Two row, double-cup single cone nonadjustable
TQD, TQI	Four row, cup adjusted 		
TAPERED ROLLER BEARINGS — METRIC			
Symbol	Description	Symbol	Description
TS	Single row, straight bore	TSF	Single row, straight bore, flanged cup
TDO	Double row, straight bore, two single cones, one double cup with lubrication hole and groove	2TS	Double row, straight bore, two single cones, two single cups
THRUST TAPERED ROLLER BARINGS			
Symbol	Description		
TT	Thrust bearings 		

tic of several types of needle bearings is the absence of a cage or separator for retaining the individual rollers. Needle bearings may be divided into three classes: loose-roller, outer race and retained roller, and non-separable units.

Loose-roller: This type of bearing has no integral races or retaining members, the needles being located directly between the shaft and the outer bearing bore. Usually both shaft and outer bore bearing surfaces are hardened and retaining members that have smooth unbroken surfaces are provided to prevent endwise movement. Compactness and high radial load capacity are features of this type.

Outer Race and Retained Roller: There are two types of outer race and retained roller bearings. In the *Drawn Shell* type, the needle rollers are enclosed by a hardened shell that acts as a retaining member and as a hardened outer race. The needles roll directly on the shaft, the bearing surface of which should be hardened. The capacity for given roller length and shaft diameter is about two-thirds that of the loose roller type. It is mounted in the housing with a press fit.

In the *Machined Race* type, the outer race consists of a heavy machined member. Various modifications of this type provide heavy ends or faces for end location of the needle rollers, or open end construction with end washers for roller retention, or a cage that maintains alignment of the rollers and is itself held in place by retaining rings. An auxiliary outer member with spherical seat that holds the outer race may be provided for self-alignment.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1g. Types of Rolling Element Bearings and Their Symbols

NEEDLE ROLLER BEARINGS, DRAWN CUP			
Symbol[a]	Description	Symbol[a]	Description
NIB NB	Needle roller bearing, full complement, drawn cup, without inner ring	NIYM NYM	Needle roller bearing, full complement, rollers retained by lubricant, drawn cup, closed end,without inner ring
NIBM NBM	Needle roller bearing, full complement,drawn cup, closed end, without inner ring	NIH NH	Needle roller bearing, with cage, drawn cup, without inner ring
NIY NY	Needle roller bearing, full complement, rollers retained by lubricant, drawn cup, without inner ring	NIHM NHM	Needle roller bearing, with cage, drawn cup, closed end, without inner ring
NEEDLE ROLLER BEARINGS		NEEDLE ROLLER AND CAGE ASSEMBLIES	
Symbol[a]	Description	Symbol[a]	Description
NIA NA	Needle roller bearing, with cage, machined ring lubrication hole and groove in OD, without inner ring	NIM NM	Needle roller and cage assembly
NEEDLE ROLLER BEARING INNER RINGS		Machined Ring Needle Roller Bearings Type NIA may be used with inch dimensioned inner rings, Type NIR, and Type NA may be used with metric dimensional inner rings, Type NR.	
Symbol[a]	Description		
NIR NR	Needle roller bearing inner ring, lubrication hole and groove in bore		

[a] Symbols with I, as NIB, are inch-dimensioned, and those without the I, as NB, are metric dimensioned.

This type is applicable where split housings occur or where a press fit of the bearing into the housing is not possible.

Non-separable: This type consists of a non-separable unit of outer race, rollers and inner race. These bearings are used where high static or oscillating motion loads are expected as in certain aircraft components and where both outer and inner races are necessary.

Special or Unconventional Types.— Rolling contact bearings have been developed for many highly specialized applications. They may be constructed of non-corrosive materials, non-magnetic materials, plastics, ceramics, and even wood. Although the materials are chosen to adapt more conventional configurations to difficult applications or environments, even greater ingenuity has been applied in utilizing rolling contact for solving particular problems. Thus, linear or recirculating bearings are available to provide low friction, accurate location, and simplified lubrication features to such applications as machine ways, axial motion devices, jack-screws, steering linkages, collets, and chucks. This type of bearing utilizes the "full-complement" style of loading the rolling elements between "races" or ways without a cage and with each element advancing by the action of "races" in the loaded areas and by contact with the adjacent element in the unloaded areas. The "races" may not be cylindrical or bodies of revolution but plane surfaces, with suitable interruptions to free the rolling elements so that they can follow a return trough or slot back to the entry-point at the start of the "race" contact area. Combinations of radial and thrust bearings are available for the user with special requirements.

Plastics Bearings.— A more recent development has been the use of Acetal resin rollers and balls in applications where abrasive, corrosive and difficult-to-lubricate conditions exist. Although these bearings do not have the load carrying capacity nor the low friction factor of their hard steel counterparts, they do offer freedom from indentation, wear, and corrosion, while at the same time providing significant weight savings.

Copyright 2004, Industrial Press, Inc., New York, NY

Of additional value are: 1) their resistance to indentation from shock loads or oscillation; and 2) their self-lubricating properties.

Usually these bearings are not available from stock, but must be designed and produced in accordance with the data made available by the plastics processor.

Pillow Block and Flanged Housing Bearings.— Of great interest to the shop man and particularly adaptable to "line-shafting" applications are a series of ball and roller bearings supplied with their own housings, adapters, and seals. Often called pre-mounted bearings, they come with a wide variety of flange mountings permitting location on faces parallel to or perpendicular to the shaft axis.

Inner races can be mounted directly on ground shafts, or can be adapter-mounted to "drill-rod" or to commercial shafting. For installations sensitive to imbalance and vibration, the use of accurately ground shaft seats is recommended.

Most pillow block designs incorporate self-aligning types of bearings so they do not require the precision mountings utilized with more normal bearing installations.

Conventional Bearing Materials.— Most rolling contact bearings are made with all load carrying members of full hard steel, either through- or case-hardened. For greater reliability this material is controlled and selected for cleanliness and alloying practices in conformity with rigid specifications in order to reduce anomalies and inclusions that could limit the useful fatigue life. Magnaflux inspection is employed to ensure that elements are free from both material defects and cracks. Likewise, a light etch is employed between rough and finish grinding to allow detection of burns due to heavy stock removal and associated decarburization in finished pieces.

Cage Materials.— Standard bearings are normally made with cages of free-machining brass or low carbon sulfurized steel. In high-speed applications or where lubrication may be intermittent or marginal, special materials may be employed. Iron-silicon-bronze, laminated phenolics, silver-plating, over-lays, solid-film baked-on coatings, carbon-graphite inserts, and, in extreme cases, sintered or even impregnated materials are used in separators.

Commercial bearings usually rely on stamped steel with or without a phosphate treatment; some low cost varieties are found with snap-in plastic or metallic cages.

So long as lubrication is adequate and speeds are both reasonable and steady, the materials and design of the cage are of secondary importance when compared with those of the rolling elements and their contacts with the races. In spite of this tolerance, a good portion of all rolling bearing failures encountered can be traced to cage failures resulting from inadequate lubrication. It can never be overemphasized that *no bearing can be designed to run continuously without lubrication!*

Standard Method of Bearing Designation.— The Anti-Friction Bearing Manufacturers Association has adopted a standard identification code that provides a specific designation for each different ball, roller, and needle bearing. Thus, for any given bearing, a uniform designation is provided for manufacturer and user alike, so that the confusion of different company designations can be avoided.

In this identification code there is a "basic number" for each bearing that consists of three elements: a one- to four-digit number to indicate the size of the bore in numbers of millimeters (metric series); a two- or three-letter symbol to indicate the type of bearing; and a two-digit number to identify the dimension series to which the bearing belongs.

In addition to this "basic number" other numbers and letters are added to designate type of tolerance, cage, lubrication, fit up, ring modification, addition of shields, seals, mounting accessories, etc. Thus, a complete designating symbol might be *50BC02JPXE0A10,* for example. The basic number is *50BC02* and the remainder is the supplementary number. For a radial bearing, this latter consists of up to four letters to indicate modification of design, one or two digits to indicate internal fit and tolerances, a letter to indicate lubricants and preservatives, and up to three digits to indicate special requirements.

Copyright 2004, Industrial Press, Inc., New York, NY

For a thrust bearing the supplementary number would consist of two letters to indicate modifications of design, one digit to indicate tolerances, one letter to indicate lubricants and preservatives, and up to three digits to indicate special requirements.

For a needle bearing the supplementary number would consist of up to three letters indicating cage material or integral seal information or whether the outer ring has a crowned outside surface and one letter to indicate lubricants or preservatives.

Dimension Series: Annular ball, cylindrical roller, and self-aligning roller bearings are made in a series of different outside diameters for every given bore diameter and in a series of different widths for every given outside diameter. Thus, each of these bearings belongs to a dimension series that is designated by a two-digit number such as or, 23, 93, etc. The first digit (8, 0, 1, 2, 3, 4, 5, 6 and 9) indicates the *width series* and the second digit (7, 8, 9, 0, 1, 2, 3, and 4) the *diameter series* to which the bearing belongs. Similar types of identification codes are used for ball and roller thrust bearings and needle roller bearings.

Bearing Tolerances

Ball and Roller Bearings.— In order to provide standards of precision for proper application of ball or roller bearings in all types of equipment, five classes of tolerances have been established by the Anti-Friction Bearing Manufacturers Association for ball bearings, three for cylindrical roller bearings and one for spherical roller bearings. These tolerances are given in Tables 2, 3, 4, 5, and 6. They are designated as ABEC-1, ABEC-3, ABEC-5, ABEC-7 and ABEC-9 for ball bearings, the ABEC-9 being the most precise, RBEC-1, RBEC-3, and RBEC-5 for roller bearings. In general, bearings to specifications closer than ABEC-1 or RBEC-1 are required because of the need for very precise fits on shaft or housing, to reduce eccentricity or runout of shaft or supported part, or to permit operation at very high speeds. All five classes include tolerances for bore, outside diameter, ring width, and radial runouts of inner and outer rings. ABEC-5, ABEC-7 and ABEC-9 provide added tolerances for parallelism of sides, side runout and groove parallelism with sides.

Thrust Bearings.— Anti-Friction Bearing Manufacturers Association and American National Standard tolerance limits for metric single direction thrust ball and roller bearings are given in Table 8. Tolerance limits for single direction thrust ball bearings, inch dimensioned are given in Table 7, and for cylindrical thrust roller bearings, inch dimensioned in Table 9.

Only one class of tolerance limits is established for metric thrust bearings.

Radial Needle Roller Bearings.— Tolerance limits for needle roller bearings, drawn cup, without inner ring, inch types NIB, NIBM, NIY, NIYM, NIH, and NIHM are given in Table 10 and for metric types NB, NBM, NY, NYM, NH and NHM in Table 11. Standard tolerance limits for needle roller bearings, with cage, machined ring, without inner ring, inch type NIA are given in Table 12 and for needle roller bearings inner rings, inch type NIR in Table 13.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ABEC-1 and RBEC-1 Tolerance Limits for Metric Ball and Roller Bearings *ANSI/ABMA 20-1987*

Basic Inner Ring Bore Diameter, d		V_{dp},[a] max			Δ_{dmp}[b]		K_{ia}[c]
mm		Diameter Series					
Over	Incl.	7,8,9	0,1	2,3,4	High	Low	max
2.5	10	10	8	6	0	−8	10
10	18	10	8	6	0	−8	10
18	30	13	10	8	0	−10	13
30	50	15	12	9	0	−12	15
50	80	19	19	11	0	−15	20
80	120	25	25	15	0	−20	25
120	180	31	31	19	0	−25	30
180	250	38	38	23	0	−30	40
250	315	44	44	26	0	−35	50
315	400	50	50	30	0	−40	60

[a] Bore diameter variation in a single radial plane.

[b] Single plane mean bore diameter deviation from basic. (For a basically tapered bore, Δ_{dmp} refers only to the theoretical small end of the bore.)

[c] Radial runout of assembled bearing inner ring.

Basic Outer Ring Outside Outerside Diameter, D		V_{Dp},[a] max				Δ_{Dmp}[b]		K_{ea}[c]
		Open Bearings			Capped Bearings[d]			
mm		Diameter Series						
Over	Incl.	7,8,9	0,1	2,3,4	2,3,4	High	Low	max
6	18	10	8	6	10	0	−8	15
18	30	12	9	7	12	0	−9	15
30	50	14	11	8	16	0	−11	20
50	80	16	13	10	20	0	−13	25
80	120	19	19	11	26	0	−15	35
120	150	23	23	14	30	0	−18	40
150	180	31	31	19	38	0	−25	45
180	250	38	38	23	…	0	−30	50
250	315	44	44	26	…	0	−35	60
315	400	50	50	50	…	0	−40	70

[a] Outside diameter variation in a single radial plane. Applies before mounting and after removal of internal or external snap ring.

[b] Single plane mean outside diameter deviation from basic.

[c] Radial runout of assembled bearing outer ring.

[d] No values have been established for diameters series 7, 8, 9, 0, and 1.

Width Tolerances									
d		Δ_{Bs}[a]			d		Δ_{Bs}[a]		
mm		All	Normal	Modified[b]	mm		All	Normal	Modified[b]
Over	Incl.	High	Low		Over	Incl.	High	Low	
2.5	10	0	−120	−250	80	120	0	−200	−380
10	18	0	−120	−250	120	180	0	−250	−500
18	30	0	−120	−250	180	250	0	−300	−500
30	50	0	−120	−250	250	315	0	−350	−500
50	80	0	−150	−380	315	400	0	−400	−630

[a] Single inner ring width deviation from basic. Δ_{Cs} (single outer ring width deviation from basic) is identical to Δ_{Bs} of inner ring of same bearing.

[b] Refers to the rings of single bearings made for paired or stack mounting.

All units are micrometers, unless otherwise indicated.For sizes beyond range of this table, see Standard.This table does not cover tapered roller bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ABEC-3 AND RBEC-3 Tolerance Limits for Metric Ball and Roller Bearings *ANSI/ABMA 20-1987*

Basic Inner Ring Bore Diameter, d		V_{dp},[a] max			Δ_{dmp}[b]		K_{ia}[c]
mm		Diameter Series					
Over	Incl.	7, 8, 9	0, 1	2, 3, 4	High	Low	max
2.5	10	9	7	5	0	−7	6
10	18	9	7	5	0	−7	7
18	30	10	8	6	0	−8	8
30	50	13	10	8	0	−10	10
50	80	15	15	9	0	−12	10
80	120	19	19	11	0	−15	13
120	180	23	23	14	0	−18	18
180	250	28	28	17	0	−22	20
250	315	31	31	19	0	−25	25
315	400	38	38	23	0	−30	30

[a] Bore diameter variation in a single radial plane.

[b] Single plane mean bore diameter deviation from basic. (For a basically tapered bore, Δ_{dmp} refers only to the theoretical small end of the bore.)

[c] Radial runout of assembled bearing inner ring.

Basic Outer Ring Outside Outerside Diameter, D		V_{Dp},[a] max				Δ_{Dmp}[b]		K_{ea}[c]
		Open Bearings			Capped Bearings[d]			
mm		Diameter Series						
Over	Incl.	7,8,9	0,1	2,3,4	2,3,4	High	Low	max
6	18	9	7	5	9	0	−7	8
18	30	10	8	6	10	0	−8	9
30	50	11	9	7	13	0	−9	10
50	80	14	11	8	16	0	−11	13
80	120	16	16	10	20	0	−13	18
120	150	19	19	11	25	0	−15	20
150	180	23	23	14	30	0	−18	23
180	250	25	25	15	…	0	−20	25
250	315	31	31	19	…	0	−25	30
315	400	35	35	21	…	0	−28	35

[a] Outside diameter variation in a single radial plane. Applies before mounting and after removal of internal or external snap ring.

[b] Single plane mean outside diameter deviation from basic.

[c] Radial runout of assembled bearing outer ring.

[d] No values have been established for diameter series 7, 8, 9, 0, and 1.

Width Tolerances									
d		Δ_{Bs}[a]			d		Δ_{Bs}[a]		
mm		All	Normal	Modified[b]	mm		All	Normal	Modified[b]
Over	Incl.	High	Low		Over	Incl.	High	Low	
2.5	10	0	−120	−250	80	120	0	−200	−380
10	18	0	−120	−250	120	180	0	−250	−500
18	30	0	−120	−250	180	250	0	−300	−500
30	50	0	−120	−250	250	315	0	−350	−500
50	80	0	−150	−380	315	400	0	−400	−630

[a] Single inner ring width deviation from basic. Δ_{Cs} (single outer ring width deviation from basic) is identical to Δ_{Bs} of inner ring of same bearing.

[b] Refers to the rings of single bearings made for paired or stack mounting.

All units are micrometers, unless otherwise indicated.For sizes beyond range of this table, see Standard.This table does not cover tapered roller bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ABEC-5 and RBEC-5 Tolerance Limits for Metric Ball and Roller Bearings *ANSI/ABMA 20-1987*

INNER RING												
Inner Ring Bore Basic Dia., d mm		V_{dp},[a] max Diameter Series		Δ_{dmp}[b]		Radial Runout K_{ia}	Ref. Face Runout with Bore S_d	Axial Runout S_{ia}[c]	Width			
									Δ_{Bs}[d]			V_{Bs}[e]
Over	Incl.	7, 8, 9	0, 1, 2, 3, 4	High	Low	max	max	max	All	Normal	Modified[f]	max
2.5	10	5	4	0	–5	4	7	7	0	–40	–250	5
10	18	5	4	0	–5	4	7	7	0	–80	–250	5
18	30	6	5	0	–6	4	8	8	0	–120	–250	5
30	50	8	6	0	–8	5	8	8	0	–120	–250	5
50	80	9	7	0	–9	5	8	8	0	–150	–250	6
80	120	10	8	0	–10	6	9	9	0	–200	–380	7
120	180	13	10	0	–13	8	10	10	0	–250	–380	8
180	250	15	12	0	–15	10	11	13	0	–300	–500	10

[a] Bore (V_{dp}) and outside diameter (V_{Dp}) variation in a single radial plane.

[b] Single plane mean bore (Δ_{dmp}) and outside diameter (Δ_{Dmp}) deviation from basic. (For a basically tapered bore, Δ_{dmp} refers only to the theoretical small end of the bore.)

[c] Axial runout of assembled bearing with inner ring S_{ia}. Applies to groove-type ball bearings only.

[d] Single bore (Δ_{Bs}) and outer ring (Δ_{Cs}) width variation.

[e] Inner (V_{Bs}) and outer (V_{Cs}) ring width deviation from basic.

[f] Applies to the rings of single bearings made for paired or stack mounting.

OUTER RING											
Basic Outer Ring Outside Dia., D mm		V_{Dp},[aa] max Diameter Series		Δ_{Dmp}[b]		Radial Runout K_{ea}	Outside Cylindrical Surface Runout S_D[b]	Axial Runout S_{ea}[c]	Width		
									Δ_{Cs}[d]		V_{Cs}[e]
Over	Incl.	7, 8, 9	0, 1, 2, 3, 4	High	Low	max	max	max	High	Low	max
6	18	5	4	0	–5	5	8	8			5
18	30	6	5	0	–6	6	8	8			5
30	50	7	5	0	–7	7	8	8	Identical		5
50	80	9	7	0	–9	8	8	10	to Δ_{Bs}		6
80	120	10	8	0	–10	10	9	11	of inner ring		8
120	150	11	8	0	–11	11	10	13	of same bearing		8
150	180	13	10	0	–13	13	10	14			8
180	250	15	11	0	–15	15	11	15			10

[a] No values have been established for capped bearings.

[b] Outside cylindrical surface runout with outer ring reference face S_D

[c] Axial runout of assembled bearing with outer ring S_{ea}.

All units are micrometers, unless otherwise indicated. For sizes beyond range of this table, see Standard.This table does not cover instrument bearings and tapered roller bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. ABEC-7 Tolerance Limits for Metric Ball and Roller Bearings *ANSI/ABMA 20-1987*

INNER RING														
Inner Ring Bore Basic Diameter, d mm		V_{dp},[a] max Diameter Series		Δ_{dmp}[b]		Δ_{ds}[c]		Radial Runout K_{ia}	Ref. Face Runout with Bore S_d	Axial Runout S_{ia}[d]	Width			
											Δ_{Bs}[e]			V_{Bs}[f]
Over	Incl.	7, 8, 9	0, 1, 2, 3, 4	High	Low	High	Low	max	max	max	All	Normal	Modified[g]	max
2.5	10	4	3	0	−4	0	−4	2.5	3	3	0	−40	−250	2.5
10	18	4	3	0	−4	0	−4	2.5	3	3	0	−80	−250	2.5
18	30	5	4	0	−5	0	−5	3	4	4	0	−120	−250	2.5
30	50	6	5	0	−6	0	−6	4	4	4	0	−120	−250	3
50	80	7	5	0	−7	0	−7	4	5	5	0	−150	−250	4
80	120	8	6	0	−8	0	−8	5	5	5	0	−200	−380	4
120	180	10	8	0	−10	0	−10	6	6	7	0	−250	−380	5
180	250	12	9	0	−12	0	−12	8	7	8	0	−300	−500	6

[a] Bore (V_{dp}) and outside diameter (V_{Dp}) variation in a single radial plane.

[b] Single plane mean bore (Δ_{dmp}) and outside diameter (Δ_{Dmp}) deviation from basic. (For a basically tapered bore, Δ_{dmp} refers only to the theoretical small end of the bore.)

[c] Single bore (Δ_{ds}) and outside diameter (Δ_{Ds}) deviations from basic. These deviations apply to diameter series 0, 1, 2, 3, and 4 only.

[d] Axial run out of assembled bearing with inner ring S_{ia}. Applies to groove-type ball bearings only.

[e] Single bore (Δ_{Bs}) and outer ring (Δ_{Cs}) width deviation from basic.

[f] Inner (V_{Bs}) and outer (V_{Cs}) ring width variation.

[g] Applies to the rings of single bearings made for paired or stack mounting.

OUTER RING													
Basic Outer Ring Outside Dia., D mm		V_{Dp},[a] max Diameter Series		Δ_{Dmp}[b]		Δ_{Ds}[c]		Radial Runout K_{ea}	Surface Runout S_D[d]	Axial Runout S_{ea}[e]	Width		
											Δ_{Cs}[f]		V_{Cs}[g]
Over	Incl.	7, 8, 9	0, 1, 2, 3, 4	High	Low	High	Low	max	max	max	High	Low	max
6	18	4	3	0	−4	0	−4	3	4	5			2.5
18	30	5	4	0	−5	0	−5	4	4	5			2.5
30	50	6	5	0	−6	0	−6	5	4	5	Identical to Δ_{Bs} of inner ring of same bearing		2.5
50	80	7	5	0	−7	0	−7	5	4	5			3
80	120	8	6	0	−8	0	−8	6	5	6			4
120	150	9	7	0	−9	0	−9	7	5	7			5
150	180	10	8	0	−10	0	−10	8	5	8			5
180	250	11	8	0	−11	0	−11	19	7	10			7

[a] No values have been established for capped bearings.

[b] Single plane mean bore (Δ_{dmp}) and outside diameter (Δ_{Dmp}) deviation from basic. (For a basically tapered bore, Δ_{dmp} refers only to the theoretical small end of the bore.)

[c] Single bore (Δ_{ds}) and outside diameter (Δ_{Ds}) deviations from basic. These deviations apply to diameter series 0, 1, 2, 3, and 4 only.

[d] Outside cylindrical surface runout outer ring reference face S_D

[e] Axial run out of assembled bearing with outer ring S_{ia}. Applies to groove-type ball bearings only.

[f] Single bore (Δ_{Bs}) and outer ring (Δ_{Cs}) width deviation from basic.

[g] Inner (V_{Bs}) and outer (V_{Cs}) ring width variation.

All units are micrometers, unless otherwise indicated. For sizes beyond range of this table, see Standard. This table does not cover instrument bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ABEC-9 Tolerance Limits for Metric Ball and Roller Bearing *ANSI/ABMA 20-1987*

INNER RING												
Inner Ring Bore Basic Dia., d mm		V_{dp}[a] max	Δ_{dmp}[b]		Δ_{ds}[c]		Radial Runout K_{ia}	Ref. Face Runout with Bore S_d	Axial Runout of Assembled Bearing with Inner Ring S_{ia}[d]	Width		
										Δ_{Bs}[e]		V_{Bs}[f]
Over	Incl.	max	High	Low	High	Low	max	max	max	High	Low	max
2.5	10	2.5	0	−2.5	0	−2.5	1.5	1.5	1.5	0	−40	1.5
10	18	2.5	0	−2.5	0	−2.5	1.5	1.5	1.5	0	−80	1.5
18	30	2.5	0	−2.5	0	−2.5	2.5	1.5	2.5	0	−120	1.5
30	50	2.5	0	−2.5	0	−2.5	2.5	1.5	2.5	0	−120	1.5
50	80	4	0	−4	0	−4	2.5	1.5	2.5	0	−150	1.5
50	80	4	0	−4	0	−4	2.5	1.5	2.5	0	−150	1.5
80	120	5	0	−5	0	−5	2.5	2.5	2.5	0	−200	2.5
120	150	7	0	−7	0	−7	2.5	2.5	2.5	0	−250	2.5
150	180	7	0	−7	0	−7	5	4	5	0	−300	4
180	250	8	0	−8	0	−8	5	5	5	0	−350	5

[a] Bore (V_{dp}) and outside diameter (V_{Dp}) variation in a single radial plane.

[b] Single plane mean bore (Δ_{dmp}) and outside diameter (Δ_{Dmp}) deviation from basic. (For a basically tapered bore, Δ_{dmp} refers to the theoretical small end of the bore.)

[c] Single bore diameter (Δ_{ds}) and outside diameter (Δ_{Ds}) deviation from basic.

[d] Applies to groove-type ball bearings only.

[e] Single bore (Δ_{Bs}) and outer ring (Δ_{Cs}) width variation from basic.

[f] Inner (V_{Bs}) and outer (V_{Cs}) ring width variation.

OUTER RING												
Basic Outside Diameter, D mm		V_{Dp}[a]	Δ_{Dmp}[b]		Δ_{Ds}[c]		Radial Runout K_{ea}	Outside Cylindrical Surface Runout with Outer Ring S_D	Axial Runout of Assembled Bearing with Outer Ring S_{ea}	Width		
										Δ_{Cs}[e]		V_{Cs}[f]
Over	Incl.	max	High	Low	High	Low	max	max	max	High	Low	max
6	18	2.5	0	−2.5	0	−2.5	1.5	1.5	1.5	Identical to Δ_{Bs} of inner ring of same bearing		1.5
18	30	4	0	−4	0	−4	2.5	1.5	2.5			1.5
30	50	4	0	−4	0	−4	2.5	1.5	2.5			1.5
50	80	4	0	−4	0	−4	4	1.5	4			1.5
80	120	5	0	−5	0	−5	5	2.5	5			1.5
120	150	5	0	−5	0	−5	5	2.5	5			1.5
150	180	7	0	−7	0	−7	5	2.5	5			2.5
180	250	8	0	−8	0	−8	7	4	7			4
250	315	8	0	−8	0	−8	7	5	7			5

[a] No values have been established for capped bearings.

All units are micrometers, unless otherwise indicated.For sizes beyond range of this table, see Standard.This table does not cover instrument bearings.

Table 7. Tolerance Limits for Single Direction Ball Thrust Bearings—Inch Design *ANSI/ABMA 24.2-1998*

Bore Diameter [a] d, Inches		Single Plane Mean Bore Dia. Variation, d, Inch		Outside Diameter D, Inches		Single Plane Mean O.D. Variation, D, Inch	
Over	Incl.	High	Low	Over	Incl.	High	Low
0	6.7500	+0.005	0	0	5.3125	+0	−0.002
6.7500	20.0000	+0.010	0	5.3125	17.3750	+0	−0.003
…	…	…	…	17.3750	39.3701	+0	−0.004

[a] Bore tolerance limits: For bore diameters 0 to 1.8125 inches, inclusive, +0.005, –0.005; over 1.8125 to 12.000 inches, inclusive, +0.010, –0.010; over 12.000 to 20.000, inclusive, +0.0150, –0.0150.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. AFBMA and American National Standard Tolerance Limits for Metric Single Direction Thrust Ball (Type TA) and Roller Type (Type TS) Bearings *ANSI/ABMA 24.1-1989*

Bore Dia.of Shaft Washer, d		Δd_{mp}[a]		S_i, S_e[b]	$\Delta T_{s\,Mm}$[c]			Outside Dia. of Housing Washer, D		ΔD_{mp}[a]	
mm								mm			
Over	Incl.	High	Low	Max	Max	Type TA	Type TS	Over	Incl.	High	Low
18	30	0	−10	10	20	−250	…	10	18	0	−11
30	**50**	**0**	**−12**	10	**20**	−250	−300	18	30	0	−13
50	**80**	**0**	**−15**	10	**20**	−300	−400	30	50	0	−16
80	**120**	**0**	**−20**	15	**25**	−300	−400	**50**	**80**	**0**	**−19**
120	**180**	**0**	**−25**	15	**25**	−400	−500	**80**	**120**	**0**	**−22**
180	**250**	**0**	**−30**	20	**30**	−400	−500	**120**	**180**	**0**	**−25**
250	**315**	**0**	**−35**	25	**40**	−400	−700	**180**	**250**	**0**	**−30**
315	**400**	**0**	**−40**	30	**40**	−500	−700	**250**	**315**	**0**	**−35**
400	**500**	**0**	**−45**	30	**50**	−500	−900	**315**	**400**	**0**	**−40**
500	**630**	**0**	**−50**	35	**60**	−600	−1200	**400**	**500**	**0**	**−45**

[a] Single plane mean bore diameter deviation of central shaft washer (Δd_{mp}) and outside diameter (ΔD_{mp}) variation.

[b] Raceway parallelism with the face, housing-mounted (S_e) and boremounted (S_i) race or washer.

[c] Deviation of the actual bearing height.

All dimensions in micrometers, unless otherwise indicated. Tolerances are for normal tolerance class only. For sizes beyond the range of this table and for other tolerance class values, see Standard. All entries apply to type TA bearings; boldface entries also apply to type TS bearings.

Table 9. Tolerance Limits for Cylindrical Roller Thrust Bearings—Inch Design *ANSI/ABMA 24.2-1998*

Basic Bore Dia., d		Δd_{mp}[a]		ΔT_s[b]		Basic Outside dia., D		ΔD_{mp}[c]	
Over	Incl.	Low	High	High	Low	Over	Incl.	High	Low
EXTRA LIGHT SERIES—TYPE TP									
0	0.9375	+.0040	+.0060	+.0050	−.0050	0	4.7188	+0	−.0030
0.9375	1.9375	+.0050	+.0070	+.0050	−.0050	4.7188	5.2188	+0	−.0030
1.9375	3.0000	+.0060	+.0080	+.0050	−.0050	…	…	…	…
3.0000	3.5000	+.0080	+.0100	−.0100	−.0100	…	…	…	…

[a] Single plane mean bore diameter deviation.

[b] Deviation of the actual bearing height, single direction bearing.

[c] Single plane mean outside diameter deviation.

Basic Bore Diameter, d		Δd_{mp}[a]		Basic Outside Diameter, D		Outside Dia., D Tolerance Limits		Basic Bore Diameter, d		ΔT_s	
Over	Inc.	High	Low	Over	Incl.	High	Low	Over	Incl.	High	Low
LIGHT SERIES—TYPE TP											
0	1.1870	+0	−.0005	0	2.8750	+.0005	−0	0	2.0000	+0	−.006
1.1870	1.3750	+0	−.0006	2.8750	3.3750	+.0007	−0	2.0000	3.0000	+0	−.008
1.3750	1.5620	+0	−.0007	3.3750	3.7500	+.0009	−0	3.0000	6.0000	+0	−.010
1.5620	1.7500	+0	−.0008	3.7500	4.1250	+.0011	−0	6.0000	10.0000	+0	−.015
1.7500	1.9370	+0	−.0009	4.1250	4.7180	+.0013	−0	10.0000	18.0000	+0	−.020
1.9370	2.1250	+0	−.0010	4.7180	5.2180	+.0015	−0	18.0000	30.0000	+0	−.025
2.1250	2.5000	+0	−.0011	…	…	…	…	…	…	…	…
2.2500	3.0000	+0	−.0012	…	…	…	…	…	…	…	…
3.0000	3.5000	+0	−.0013	…	…	…	…	…	…	…	…
HEAVY SERIES—TYPE TP											
2.0000	3.0000	+0	−.0010	5.0000	10.0000	+.0015	−0	0	2.000	+0	−.006
3.0000	3.5000	+0	−.0012	10.0000	18.0000	+.0020	−0	2.000	3.000	+0	−.008
3.5000	9.0000	+0	−.0015	18.0000	26.0000	+.0025	−0	3.000	6.000	+0	−.010
9.0000	12.0000	+0	−.0018	26.0000	34.0000	+.0030	−0	6.000	10.000	+0	−.015
12.0000	18.0000	+0	−.0020	34.0000	44.0000	+.0040	−0	10.000	18.000	+0	−.020
18.0000	22.0000	+0	−.0025	…	…	…	…	18.000	30.000	+0	−.025
22.0000	30.0000	+0	−.003	…	…	…	…	…	…	…	…
TYPE TPC											
0	2.0156	+.010	−0	2.5000	4.0000	+.005	−.005	0	2.0156	+0	−.008
2.0156	3.0156	+.010	−.020	4.0000	6.0000	+.006	−.006	2.0156	3.0156	+0	−.010
3.0156	6.0156	+.015	−.020	6.0000	10.0000	+.010	−.010	3.0156	6.0156	+0	−.015
6.0156	10.1560	+.015	−.050	10.0000	18.0000	+.012	−.012	6.0156	10.1560	+0	−.020

All dimensions are in inches. For Type TR bearings, see Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. AFBMA and American National Standard Tolerance Limits for Needle Roller Bearings, Drawn Cup, Without Inner Ring — Inch Types NIB, NIBM, NIY, NIYM, NIH, and NIHM *ANSI/ABMA 18.2-1982 (R1993)*

Ring Gage Bore Diameter[a]			Basic Bore Diameter under Needle Rollers, F_w		Allowable Deviation from F_w[a]		Allowable Deviation from Width, B	
Basic Outside Diameter, D Inch		Deviation from D	Inch		Inch		Inch	
Over	Incl.	Inch	Over	Incl.	Low	High	High	Low
0.1875	0.9375	+0.0005						
0.9375	4.0000	−0.0005	0.1875	0.6875	+0.0015	+0.0024	+0	−0.0100
For fitting and mounting practice see Table 19.			0.6875	1.2500	+0.0005	+0.0014	+0	−0.0100
			1.2500	1.3750	+0.0005	+0.0015	+0	−0.0100
			1.3750	1.6250	+0.0005	+0.0016	+0	−0.0100
			1.6250	1.8750	+0.0005	+0.0017	+0	−0.0100
			1.8750	2.0000	+0.0006	+0.0018	+0	−0.0100
			2.0000	2.5000	+0.0006	+0.0020	+0	−0.0100
			2.5000	3.5000	+0.0010	+0.0024	+0	−0.0100

[a] The bore diameter under needle rollers can be measured only when bearing is pressed into a ring gage, which rounds and sizes the bearing.

Table 11. AFBMA and American National Standard Tolerance Limits for Needle Roller Bearings, Drawn Cup, Without Inner Ring — Metric Types NB, NBM, NY, NYM, NH, and NHM *ANSI/ABMA 18.1-1982 (R1994)*

Ring Gage Bore Diameter[a]			Basic Bore Diameter underNeedle Rollers, F_w		Allowable Deviation from F_w[a]		Allowable Deviation from Width, B	
Basic Outside Diameter, D		Deviation from D	mm		Micrometers		Micrometers	
mm								
Over	Incl.	Micrometers	Over	Incl.	Low	High	High	Low
6	10	−16	3	6	+10	+28	+0	−250
10	18	−20	6	10	+13	+31	+0	−250
30	50	−28	18	30	+20	+41	+0	−250
50	80	−33	30	50	+25	+50	+0	−250
…	…	…	50	70	+30	+60	+0	−250

[a] The bore diameter under needle rollers can be measured only when bearing is pressed into a ring gage, which rounds and sizes the bearing.

For fitting and mounting practice, see Table 19.

Table 12. AFBMA and American National Standard Tolerance Limits for Needle Roller Bearings, With Cage, Machined Ring, Without Inner Ring— Inch Type NIA *ANSI/ABMA 18.2-1982 (R1993)*

Basic Outside Diameter, D		Allowable Deviation From D of Single Mean Diameter, D_{mp}		Basic Bore Diameter under Needle Rollers, F_w		Allowable Deviation from F_w		Allowable Deviation from Width, B	
Inch		Inch		Inch		Inch		Inch	
Over	Incl.	High	Low	Over	Incl.	Low	High	High	Low
0.7500	2.0000	+0	−0.0005	0.3150	0.7087	+0.0008	+0.0017	+0	−0.0050
2.0000	3.2500	+0	−0.0006	0.7087	1.1811	+0.0009	+0.0018	+0	−0.0050
3.2500	4.7500	+0	−0.0008	1.1811	1.6535	+0.0010	+0.0019	+0	−0.0050
4.7500	7.2500	+0	−0.0010	1.6535	1.9685	+0.0010	+0.0020	+0	−0.0050
				1.9685	2.7559	+0.0011	+0.0021	+0	−0.0050
7.2500	10.2500	+0	−0.0012	2.7559	3.1496	+0.0011	+0.0023	+0	−0.0050
10.2500	11.1250	+0	−0.0014	3.1496	4.0157	+0.0012	+0.0024	+0	−0.0050
…	…	…	…	4.0157	4.7244	+0.0012	+0.0026	+0	−0.0050
…	…	…	…	4.7244	6.2992	+0.0013	+0.0027	+0	−0.0050
…	…	…	…	6.2992	7.0866	+0.0013	+0.0029	+0	−0.0050
…	…	…	…	7.0866	7.8740	+0.0014	+0.0030	+0	−0.0050
…	…	…	…	7.8740	9.2520	+0.0014	+0.0032	+0	−0.0050

For fitting and mounting practice, see Table 20.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. AFBMA and American National Standard Tolerance Limits for Needle Roller Bearing Inner Rings—Inch Type NIR *ANSI/ABMA 18.2-1982 (R1993)*

Basic Outside Diameter, F		Allowable Deviation From F of Single Mean Diameter, F_{mp}		Basic Bore Diameter d		Allowable Deviation from d of Single Mean Diameter, d_{mp}		Allowable Deviation from Width, B	
Inch		Inch		Inch		Inch		Inch	
Over	Incl.	High	Low	Over	Incl.	High	Low	High	Low
0.3937	0.7087	–0.0005	–0.0009	0.3125	0.7500	+0	–0.0004	+0.0100	+0.0050
0.7087	1.0236	–0.0007	–0.0012	0.7500	2.0000	+0	–0.0005	+0.0100	+0.0050
1.0236	1.1811	–0.0009	–0.0014	2.0000	3.2500	+0	–0.0006	+0.0100	+0.0050
1.1811	1.3780	–0.0009	–0.0015	3.2500	4.2500	+0	–0.0008	+0.0100	+0.0050
1.3780	1.9685	–0.0010	–0.0016	4.2500	4.7500	+0	–0.0008	+0.0150	+0.0100
1.9685	3.1496	–0.0011	–0.0018	4.7500	7.0000	+0	–0.0010	+0.0150	+0.0100
3.1496	3.9370	–0.0013	–0.0022	7.0000	8.0000	+0	–0.0012	+0.0150	+0.0100
3.9370	4.7244	–0.0015	–0.0024	…	…	…	…	…	…
4.7244	5.5118	–0.0015	–0.0025	…	…	…	…	…	…
5.5118	7.0866	–0.0017	–0.0027	…	…	…	…	…	…
7.0866	8.2677	–0.0019	–0.0031	…	…	…	…	…	…
8.2677	9.2520	–0.0020	–0.0032	…	…	…	…	…	…

For fitting and mounting practice, see Table 21.

Metric Radial Ball and Roller Bearing Shaft and Housing Fits.— To select the proper fits, it is necessary to consider the type and extent of the load, bearing type, and certain other design and performance requirements.

The required shaft and housing fits are indicated in Tables 14 and 15. The terms "Light," "Normal," and "Heavy" loads refer to radial loads that are generally within the following limits, with some overlap (C being the Basic Load Rating computed in accordance with AFBMA-ANSI Standards):

Bearing Type	Radial Load		
	Light	Normal	Heavy
Ball	Up to 0.075C	From 0.075C to 0.15C	Over 0.15C
Cylindrical Roller	Up to 0.075C	From 0.075C to 0.2C	Over 0.15C
Spherical Roller	Up to 0.075C	From 0.070C to 0.25C	Over 0.15C

Shaft Fits: Table 14 indicates the initial approach to shaft fit selection. Note that for most normal applications where the shaft rotates and the radial load direction is constant, an interference fit should be used. Also, the heavier the load, the greater is the required interference. For stationary shaft conditions and constant radial load direction, the inner ring may be moderately loose on the shaft.

For pure thrust (axial) loading, heavy interference fits are not necessary; only a moderately loose to tight fit is needed.

The upper part of Table 16 shows how the shaft diameters for various ANSI shaft limit classifications deviate from the basic bore diameters.

Table 17 gives metric values for the shaft diameter and housing bore tolerance limits given in Table 16.

The lower parts of Tables 16 and 17 show how housing bores for various ANSI hole limit classifications deviate from the basic shaft outside diameters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Selection of Shaft Tolerance Classifications for Metric Radial Ball and Roller Bearings of ABEC-1 and RBEC-1 Tolerance Classes *ANSI/ABMA 7-1995*

Operating Conditions			Ball Bearings		Cylindrical Roller Bearings		Spherical Roller Bearings		Tolerance Symbol[a]
			mm	Inch	mm	Inch	mm	Inch	
Inner ring stationary in relation to the direction of the load.	All loads	Inner ring has to be easily displaceable	All diameters	All diameters	All diameters	All diameters	All diameters	All diameters	g6
		Inner ring does not have to be easily displaceable	All diameters	All diameters	All diameters	All diameters	All diameters	All diameters	h6
Direction of load indeterminate or the inner ring rotating in relation to the direction of the load.	Radial load:		Nominal Shaft Diameter						
	LIGHT		≤18	≤0.71					h5
			>18	>0.71	≤40	≤1.57	≤40	≤1.57	j6[b]
					(40)-140	(1.57)–5.51	(40)–100	(1.57)–3.94	k6[b]
					(140)–320	(5.51)–12.6	(100)–320	(3.94)–12.6	m6[b]
					(320)–500	(126)–19.7	(320)–500	(126)–19.7	n6
					>500	>19.7	>500	>19.7	p6
	NORMAL		≤18	≤0.71					j5
			>18	>0.71	≤40	≤1.57	≤40	≤1.57	k5
					(40)–100	(1.57)–3.94	(40)–65	(1.57)–2.56	m5
					(100)–140	(3.94)–5.51	(65)–100	(2.56)–3.94	m6
					(140)–320	(5.51)–12.6	(100)–140	(3.94)–5.51	n6
					(320)–500	(12.6)–19.7	(140)–280	(5.51)–11.0	p6
					>500	>19.7	(280)–500	(11.0)–19.7	r6
							>500	>19.7	r7
	HEAVY		(18)–100	(0.71)–3.94					k5
			>100	>3.94	≤40	≤1.57	≤40	≤1.57	m5
					(40)-65	(1.57)–2.56	(40)–65	(1.57)–2.56	m6[b]
					(65)–140	(2.56)–5.51	(65)–100	(2.56)–3.94	n6[b]
					(140)–200	(5.51)–7.87	(100)–140	(3.94)–5.51	p6[b]
					(200)–500	(7.87)–19.7	(140)–200	(5.51)–7.87	r6[b]
					>500	>19.7	>200	>7.87	r7[b]
Pure Thrust Load			All diams.	All diams.	Consult Bearing Manufacturer				j6

[a] For solid steel shafts. For hollow or nonferrous shafts, tighter fits may be needed.

[b] When greater accuracy is required, use j5, k5, and m5 instead of j6, k6, and m6, respectively.

Numerical values are given in Tables 16 and 17.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. Selection of Housing Tolerance Classifications for Metric Radial Ball and Roller Bearings of ABEC-1 and RBEC-1 Tolerance Classes

Design and Operating Conditions				Tolerance Classification[a]
Rotational Conditions	Loading	Outer Ring Axial Displacement Limitations	Other Conditions	
Outer ring stationary in relation to load direction	Light Normal and Heavy	Outer ring must be easily axially displaceable	Heat input through shaft	G7
			Housing split axially	H7[b]
			Housing not split axially	H6[b]
	Shock with temporary complete unloading	Transitional Range[c]		J6[b]
Load direction is indeterminate	Light and normal			
	Normal and Heavy			
	Heavy Shock		split housing not recommended	K6[b]
Outer ring rotating in relation to load direction	Light			M6[b]
	Normal and Heavy	Outer ring need not be axially displaceable		N6[b]
	Heavy		Thin wall housing not split	P6[b]

[a] For cast iron or steel housings. For housings of nonferrous alloys tighter fits may be needed.

[b] Where wider tolerances are permissible, use tolerance classifications P7, N7, M7, K7, J7, and H7, in place of P6, N6, M6, K6, J6, and H6, respectively.

[c] The tolerance zones are such that the outer ring may be either tight or loose in the housing.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. AFBMA and American National Standard Shaft Diameter and Housing Bore Tolerance Limits *ANSI/ABMA 7-1995*

Allowable Deviations of Shaft Diameter from Basic Bore Diameter, Inch															
Inches		mm													
Over	Incl.	Over	Incl.												
Base Bore Diameter				g6	h6	h5	j5	j6	k5	k6	m5	m6	n6	p6	r6	r7
0.2362	0.3937	6	10	−.0002 −.0006	0 −.0004	0 −.0002	+.0002 −.0001	+.0003 −.0001	+.0003 0		+.0005 +.0002					
0.3937	0.7087	10	18	−.0002 −.0007	0 −.0004	0 −.0003	+.0002 −.0001	+.0003 −.0001	+.0004 0		+.0006 +.0003					
0.7087	1.1811	18	30	−.0003 −.0008	0 −.0005		+.0002 −.0002	+.0004 −.0002	+.0004 +.0001		+.0007 +.0003					
1.1811	1.9685	30	50	−.0004 −.0010	0 −.0006		+.0002 −.0002	+.0004 −.0002	+.0005 +.0001	+.0007 +.0001	+.0008 +.0004	+.0010 +.0004				
1.9685	3.1496	50	80	−.0004 −.0011	0 −.0007		+.0002 −.0003	+.0005 −.0003	+.0006 +.0001	+.0008 +.0001	+.0009 +.0004	+.0012 +.0004	+.0018 +.0009			
3.1496	4.7244	80	120	−.0005 −.0013	0 −.0009		+.0002 −.0004	+.0005 −.0004	+.0007 +.0001	+.0010 +.0001	+.0011 +.0005	+.0014 +.0005	+.0019 +.0010	+.0023 +.0015		
Allowable Deviations of Housing Bore from Basic Outside Diameter of Shaft, Inch																
Basic Outside Diameter				G7	H7	H6	J7	J6	K6	K7	M6	M7	N6	N7	P6	P7
0.7087	1.1811	18	30	+.0003 +.0011	0 +.0008	0 +.0005	−.0004 +.0005	−.0002 +.0003	−.0004 +.0001	−.0006 +.0002	−.0007 +.0002	−.0008 0	−.0009 −.0004	−.0011 −.0003	−.0012 −.0007	−.0014 −.0006
1.1811	1.9685	30	50	+.0004 +.0013	0 +.0010	0 +.0006	−.0004 +.0006	−.0002 +.0004	−.0005 +.0001	−.0007 +.0003	−.0008 −.0002	−.0010 0	−.0011 −.0005	−.0013 −.0003	−.0015 −.0008	−.0017 −.0007
1.9685	3.1496	50	80	+.0004 +.0016	0 +.0012	0 +.0007	−.0005 +.0007	−.0002 +.0005	−.0006 +.0002	−.0008 +.0004	−.0009 −.0002	−.0012 0	−.0013 −.0006	−.0015 −.0004	−.0018 −.0010	−.0020 −.0008
3.1496	4.7244	80	120	+.0005 +.0019	0 +.0014	0 +.0009	−.0005 +.0009	−.0002 +.0006	−.0007 +.0002	−.0010 +.0004	−.0011 −.0002	−.0014 0	−.0015 −.0006	−.0018 −.0004	−.0020 −.0012	−.0023 −.0009
4.7244	7.0866	120	180	+.0006 +.0021	0 +.0016	0 +.0010	−.0006 +.0010	−.0003 +.0007	−.0008 +.0002	−.0011 +.0005	−.0013 −.0003	−.0016 0	−.0018 −.0008	−.0020 −.0005	−.0024 −.0014	−.0027 −.0011
7.0866	9.8425	180	250	+.0006 +.0024	0 +.0018	0 +.0011	−.0006 +.0012	−.0003 +.0009	−.0009 +.0002	−.0013 +.0005	−.0015 −.0003	−.0018 0	−.0020 −.0009	−.0024 −.0006	−.0028 −.0016	−.0031 −.0013

Based on ANSI B4.1-1967 (R1994) Preferred Limits and Fits for Cylindrical Parts. Symbols g6, h6, etc., are shaft and G7, H7, etc., hole limits designations. For larger diameters and metric values see AFBMA Standard 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. AFBMA and American National Standard Shaft Diameter and Housing Bore Tolerance Limits *ANSI/ABMA 7-1995*

Allowable Deviations of Shaft Diameter from Basic Bore Diameter, mm															
Inches		mm													
Over	Incl.	Over	Incl.												
Base Bore Diameter				g6	h6	h5	j5	j6	k5	k6	m5	m6	n6	p6	r6	r7
0.2362	0.3937	6	10	−.005 −.014	0 −.009	0 −.006	+.004 −.002	+.007 −.002	+.007 −.001		+.012 +.006					
0.3937	0.7087	10	18	−.006 −.017	0 −.011	0 −.008	+.005 −.003	+.008 −.003	+.009 +.001		+.015 +.007					
0.7087	1.1811	18	30	−.007 −.020	0 −.013		+.005 −.004	+.009 −.004	+.011 +.002		+.017 +.008					
1.1811	1.9685	30	50	−.009 −.025	0 −.016		+.006 −.005	+.011 −.005	+.013 +.002	+.018 +.002	+.020 +.009	+.025 +.009				
1.9685	3.1496	50	80	−.010 −.029	0 −.019		+.006 −.007	+.012 −.007	+.015 +.002	+.021 +.002	+.024 +.011	+.030 +.011	+.039 +.020			
3.1496	4.7244	80	120	−.012 −.034	0 −.022		+.006 −.009	+.013 −.009	+.018 +.003	+.025 +.003	+.028 +.013	+.035 +.013	+.045 +.023	+.059 +.037		
Allowable Deviations of Housing Bore from Basic Outside Diameter of Shaft, mm															
Basic Outside Diameter				G7	H7	H6	J7	J6	K6	K7	M6	M7	N6	N7	P6	P7
.7086	1.1811	18	30	+.007 +.028	0 +.021	0 +.013	−.009 +.012	−.005 +.008	−.011 +.002	−.015 +.006	−.017 −.004	−.021 0	−.024 −.011	−.028 −.007	−.031 −.018	−.035 −.014
1.1811	1.9685	30	50	+.009 +.034	0 +.025	0 +.016	−.011 +.014	−.006 +.010	−.013 +.003	−.018 +.007	−.020 −.004	−.025 0	−.028 −.012	−.033 −.008	−.037 −.021	−.042 −.017
1.9685	3.1496	50	80	+.010 +.040	0 +.030	0 +.019	−.012 +.018	−.006 +.013	−.015 +.004	−.021 +.009	−.024 −.005	−.030 0	−.033 −.014	−.039 −.009	−.045 −.026	−.051 −.021
3.1496	4.7244	80	120	+.012 +.047	0 +.035	0 +.022	−.013 +.022	−.006 +.016	−.018 +.004	−.025 +.010	−.028 −.006	−.035 0	−.038 −.016	−.045 −.010	−.052 −.030	−.059 −.024
4.7244	7.0866	120	180	+.014 +.054	0 +.040	0 +.025	−.014 +.026	−.007 +.018	−.021 +.004	−.028 +.012	−.033 −.008	−.040 0	−.045 −.020	−.052 −.012	−.061 −.036	−.068 −.028
7.0866	9.8425	180	250	+.015 +.061	0 +.046	0 +.029	−.016 +.030	−.007 +.022	−.024 +.005	−.033 +.013	−.037 −.008	−.046 0	−.051 −.022	−.060 −.014	−.070 −.041	−.079 −.033

Based on ANSI B4.1-1967 (R1994) Preferred Limits and Fits for Cylindrical Parts. Symbols g6, h6, etc., are shaft and G7, H7, etc., hole limits designations. For larger diameters and metric values see AFBMA Standard 7.

Copyright 2004, Industrial Press, Inc., New York, NY

Design and Installation Considerations.— Interference fitting will reduce bearing radial internal clearance, so it is recommended that prospective users consult bearing manufacturers to make certain that the required bearings are correctly specified to satisfy all mounting, environmental and other operating conditions and requirements. This check is particularly necessary where heat sources in associated parts may further diminish bearing clearances in operation.

Standard values of radial internal clearances of radial bearings are listed in AFBMA-ANSI Standard 20.

Allowance for Axial Displacement.— Consideration should be given to axial displacement of bearing components owing to thermal expansion or contraction of associated parts. Displacement may be accommodated either by the internal construction of the bearing or by allowing one of the bearing rings to be axially displace-able. For unusual applications consult bearing manufacturers.

Needle Roller Bearing Fitting and Mounting Practice.— The tolerance limits required for shaft and housing seat diameters for needle roller beatings with inner and outer rings as well as limits for raceway diameters where inner or outer rings or both are omitted and rollers operate directly upon these surfaces are given in Tables 18 through 21, inclusive. Unusual design and operating conditions may require a departure from these practices. In such cases, bearing manufacturers should be consulted.

Needle Roller Bearings, Drawn Cup: These beatings without inner ring, Types NIB, NB, NIBM, NBM, NIY, NY, NIYM, NYM, NIH, NH, NIHM, NHM, and Inner Rings, Type NIR depend on the housings into which they are pressed for their size and shape. Therefore, the housings must not only have the proper bore dimensions but also must have sufficient strength. Tables 18 and 19, show the bore tolerance limits for rigid housings such as those made from cast iron or steel of heavy radial section equal to or greater than the ring gage section given in AFBMA Standard 4, 1984. The bearing manufacturers should be consulted for recommendations if the housings must be of lower strength materials such as aluminum or even of steel of thin radial section. The shape of the housing bores should be such that when the mean bore diameter of a housing is measured in each of several radial planes, the maximum difference between these mean diameters should not exceed 0.0005 inch (0.013 mm) or one-half the housing bore tolerance limit, if smaller. Also, the radial deviation from circular form should not exceed 0.00025 inch (0.006 mm). The housing bore surface finish should not exceed 125 micro-inches (3.2 micrometers) arithmetical average.

Table 18. AFBMA and American National Standard Tolerance Limits for Shaft Raceway and Housing Bore Diameters—Needle Roller Bearings, Drawn Cup, Without Inner Ring, Inch Types NIB, NIBM, NIY, NIYM, NIH, and NIHM *ANSI/ABMA 18.2-1982 (R1993)*

Basic Bore Diameter under Needle Rollers, F_w		Shaft Raceway Diameter[a] Allowable Deviation from F_w		Basic Outside Diameter, D		Housing Bore Diameter[a] Allowable Deviation from D	
Inch		Inch		Inch		Inch	
Over	Incl.	High	Low	Over	Incl.	Low	High
OUTER RING STATIONARY RELATIVE TO LOAD							
0.1875	1.8750	+0	–0.0005	0.3750	4.0000	–0.0005	+0.0005
1.8750	3.5000	+0	–0.0006	…	…	…	…
OUTER RING ROTATING RELATIVE TO LOAD							
0.1875	1.8750	–0.0005	–0.0010	0.3750	4.0000	–0.0010	+0
1.8750	3.5000	–0.0005	–0.0011	…	…	…	…

[a] See text for additional requirements.

For bearing tolerances, see Table 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. AFBMA and American National Standard Tolerance Limits for Shaft Raceway and Housing Bore Diameters—Needle Roller Bearings, Drawn Cup, Without Inner Ring, Metric Types NB, NBM, NY, NYM, NH, and NHM
ANSI/ABMA 18.1-1982 (R1994)

Basic Bore Diameter Under Needle Rollers, F_w				Shaft Raceway Diameter[a] Allowable Deviation from F_w		Basic Outside Diameter, D				Housing Bore Diameter-[a]Allowable Deviation from D	
OUTER RING STATIONARY RELATIVE TO LOAD											
mm		Inch		ANSI h6, Inch		mm		Inch		ANSI N7, Inch	
Over	Incl.	Over	Incl.	High	Low	Over	Incl.	Over	Incl.	Low	High
3	6	0.1181	0.2362	+0	–0.0003	6	10	0.2362	0.3937	–0.0007	–0.0002
6	10	0.2362	0.3937	+0	–0.0004	10	18	0.3937	0.7087	–0.0009	–0.0002
10	18	0.3937	0.7087	+0	–0.0004	18	30	0.7087	1.1811	–0.0011	–0.0003
18	30	0.7087	1.1811	+0	–0.0005	30	50	1.1811	1.9685	–0.0013	–0.0003
30	50	1.1811	1.9685	+0	–0.0006	50	80	1.9685	3.1496	–0.0015	–0.0004
50	80	1.9685	3.1496	+0	–0.0007	…	…	…	…	…	…
OUTER RING ROTATING RELATIVE TO LOAD											
mm		Inch		ANSI f6, Inch		mm		Inch		ANSI R7, Inch	
Over	Incl.	Over	Incl.	High	Low	Over	Incl.	Over	Incl.	Low	High
3	6	0.1181	0.2362	–0.0004	–0.0007	6	10	0.2362	0.3937	–0.0011	–0.0005
6	10	0.2362	0.3937	–0.0005	–0.0009	10	18	0.3937	0.7087	–0.0013	–0.0006
10	18	0.3937	0.7087	–0.0006	–0.0011	18	30	0.7087	1.1811	–0.0016	–0.0008
18	30	0.7087	1.1811	–0.0008	–0.0013	30	50	1.1811	1.9685	–0.0020	–0.0010
30	50	1.1811	1.9685	–0.0010	–0.0016	50	65	1.9685	2.5591	–0.0024	–0.0012
50	80	1.9685	3.1496	–0.0012	–0.0019	65	80	2.5591	3.1496	–0.0024	–0.0013

For bearing tolerances, see Table 11.

Table 20. AFBMA and American National Standard Tolerance Limits for Shaft Raceway and Housing Bore Diameters—Needle Roller Bearings, With Cage, Machined Ring, Without Inner Ring, Inch Type NIA
ANSI/ABMA 18.2-1982 (R1993)

Basic Bore Diameter under Needle Rollers, F_w		Shaft Raceway Diameter[a] Allowable Deviation from F_w		Basic Outside Diameter, D		Housing Bore Diameter[a] Allowable Deviation from D	
OUTER RING STATIONARY RELATIVE TO LOAD							
Inch		ANSI h6, Inch		Inch		ANSI H7, Inch	
Over	Incl.	High	Low	Over	Incl.	Low	High
0.2362	0.3937	+0	–0.0004	0.3937	0.7087	+0	+0.0007
0.3937	0.7087	+0	–0.0004	0.7087	1.1811	+0	+0.0008
0.7087	1.1811	+0	–0.0005	1.1811	1.9685	+0	+0.0010
1.1811	1.9685	+0	–0.0006	1.9685	3.1496	+0	+0.0012
1.9685	3.1496	+0	–0.0007	3.1496	4.7244	+0	+0.0014
3.1496	4.7244	+0	–0.0009	4.7244	7.0866	+0	+0.0016
4.7244	7.0866	+0	–0.0010	7.0866	9.8425	+0	+0.0018
7.0866	9.8425	+0	–0.0011	9.8425	12.4016	+0	+0.0020
OUTER RING ROTATING RELATIVE TO LOAD							
Inch		ANSI f6, Inch		Inch		ANSI N7, Inch	
Over	Incl.	High	Low	Over	Incl.	Low	High
0.2362	0.3937	–0.0005	–0.0009	0.3937	0.7087	–0.0009	–0.0002
0.3937	0.7087	–0.0006	–0.0011	0.7087	1.1811	–0.0011	–0.0003
0.7087	1.1811	–0.0008	–0.0013	1.1811	1.9685	–0.0013	–0.0003
1.1811	1.9685	–0.0010	–0.0016	1.9685	3.1496	–0.0015	–0.0004
1.9685	3.1496	–0.0012	–0.0019	3.1496	4.7244	–0.0018	–0.0004
3.1496	4.7244	–0.0014	–0.0023	4.7244	7.0866	–0.0020	–0.0005
4.7244	7.0866	–0.0016	–0.0027	7.0866	9.8425	–0.0024	–0.0006
7.0866	9.8425	–0.0020	–0.0031	9.8425	11.2205	–0.0026	–0.0006

[a] See text for additional requirements.

For bearing tolerances, see Table 12.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. AFBMA and American National Standard Tolerance Limits for Shaft Diameters—Needle Roller Bearing Inner Rings, Inch Type NIR (Used with Bearing Type NIA) *ANSI/ABMA 18.2-1982 (R1993)*

Basic Bore, *d*		Shaft Diameter[a]			
		Shaft Rotating Relative to Load, Outer Ring Stationary Relative to Load Allowable Deviation from *d*		Shaft Stationary Relative to Load, Outer Ring Rotating Relative to Load Allowable Deviation from *d*	
Inch		ANSI m5, Inch		ANSI g6, Inch	
Over	Incl.	High	Low	High	Low
0.2362	0.3937	+0.0005	+0.0002	–0.0002	–0.0006
0.3937	0.7087	+0.0006	+0.0003	–0.0002	–0.0007
0.7087	1.1811	+0.0007	+0.0003	–0.0003	–0.0008
1.1811	1.9685	+0.0008	+0.0004	–0.0004	–0.0010
1.9685	3.1496	+0.0009	+0.0004	–0.0004	–0.0011
3.1496	4.7244	+0.0011	+0.0005	–0.0005	–0.0013
4.7244	7.0866	+0.0013	+0.0006	–0.0006	–0.0015
7.0866	9.8425	+0.0015	+0.0007	–0.0006	–0.0017

[a] See text for additional requirements.

For inner ring tolerance limits, see Table 13.

Most needle roller bearings do not use inner rings, but operate directly on the surfaces of shafts. When shafts are used as inner raceways, they should be made of bearing quality steel hardened to Rockwell C 58 minimum. Tables 15 and 19 show the shaft raceway tolerance limits and Table 21 shows the shaft seat tolerance limits when inner rings are used. However, whether the shaft surfaces are used as inner raceways or as seats for inner rings, the mean outside diameter of the shaft surface in each of several radial planes should be determined. The difference between these mean diameters should not exceed 0.0003 inch (0.008 mm) or one-half the diameter tolerance limit, if smaller. The radial deviation from circular form should not exceed 0.0001 inch (0.0025 mm), for diameters up to and including 1 in. (25.4 mm). Above one inch the allowable deviation is 0.0001 times the shaft diameter. The surface finish should not exceed 16 micro-inches (0.4 micrometer) arithmetical average. The housing bore and shaft diameter tolerance limits depend upon whether the load rotates relative to the shaft or the housing.

Needle Roller Bearing With Cage, Machined Ring, Without Inner Ring: The following covers needle roller bearings Type NIA and inner rings Type NIR. The shape of the housing bores should be such that when the mean bore diameter of a housing is measured in each of several radial planes, the maximum difference between these mean diameters does not exceed 0.0005 inch (0.013 mm) or one-half the housing bore tolerance limit, if smaller. Also, the radial deviation from circular form should not exceed 0.00025 inch (0.006 mm). The housing bore surface finish should not exceed 125 micro-inches (3.2 micrometers) arithmetical average. Table 21 shows the housing bore tolerance limits.

When shafts are used as inner raceways their requirements are the same as those given above for Needle Roller Bearings, Drawn Cup. Table 20 shows the shaft raceway tolerance limits and Table 21 shows the shaft seat tolerance limits when inner rings are used.

Needle Roller and Cage Assemblies, Types NIM and NM: For information concerning boundary dimensions, tolerance limits, and fitting and mounting practice, reference should be made to ANSI/ABMA 18.1-1982 (R1994) and ANSI/ABMA 18.2-1982 (R1993).

Copyright 2004, Industrial Press, Inc., New York, NY

Bearing Mounting Practice

Because of their inherent design and material rigidity, rolling contact bearings must be mounted with careful control of their alignment and runout. Medium-speed or slower (400,000 *DN* values or less where *D* is the bearing bore in millimeters and *N* is the beating speed in revolutions per minute), and medium to light load (*C*/*P* values of 7 or greater where *C* is the beating specific dynamic capacity in pounds and *P* is the average beating load in pounds) applications can endure misalignments equivalent to those acceptable for high-capacity, precision journal beatings utilizing hard bearing materials such as silver, copper-lead, or aluminum. In no case, however, should the maximum shaft deflection exceed .001 inch per inch for well-crowned roller bearings, and .003 inch per inch for deep-groove ball-beatings. Except for self-aligning ball-bearings and spherical or barrel roller bearings, all other types require shaft alignments with deflections no greater than .0002 inch per inch. With preloaded ball bearings, this same limit is recommended as a maximum. Close-clearance tapered bearings or thrust beatings of most types require the same shaft alignment also.

Of major importance for all bearings requiring good reliability, is the location of the races on the shaft and in the housing.

Assembly methods must insure: 1) that the faces are square, before the cavity is closed; 2) that the cover face is square to the shoulder and pulled in evenly; and 3) that it will be located by a face parallel to it when finally seated against the housing.

These requirements are shown in the accompanying Table 22. In applications not controlled by automatic tooling with closely controlled fixtures and bolt torquing mechanisms, races should be checked for squareness by sweeping with a dial indicator mounted as shown below. For commercial applications with moderate life and reliability requirements, outer race runouts should be held to .0005 inch per inch of radius and inner race runout to .0004 inch per inch of radius. In preloaded and precision applications, these tolerances must be cut in half. In regard to the question of alignment, it must be recognized that rolling-contact bearings, being made of fully-hardened steel, do not wear in as may certain journal bearings when carefully applied and initially operated. Likewise, rolling contact bearings absorb relatively little deflection when loaded to *C*/*P* values of 6 or less. At such stress levels the rolling element-race deformation is generally not over .0002 inch. Consequently, proper mounting and control of shaft deflections are imperative for reliable bearing performance. Aside from inadequate lubrication, these factors are the most frequent causes of premature bearing failures.

Mountings for Precision and Quiet-running Applications.— In applications of rolling-element bearings where vibration or smoothness of operation is critical, special precautions must be taken to eliminate those conditions which can serve to initiate radial and axial motions. These exciting forces can result in shaft excursions which are in resonance with shaft or housing components over a range of frequencies from well below shaft speed to as much as 100 times above it. The more sensitive the configuration, the greater is the need for precision bearings and mountings to be used.

Precision bearings are normally made to much closer tolerances than standard and therefore benefit from better finishing techniques. Special inspection operations are required, however, to provide races and rolling elements with smoothness and runouts compatible with the needs of the application. Similarly, shafts and housings must be carefully controlled.

Among the important elements to be controlled are shaft, race, and housing roundness; squareness of faces, diameters, shoulders, and rolling paths. Though not readily appreciated, grinding chatter, lobular and compensating out-of-roundness, waviness, and flats of less than .0005 inch deviation from the average or mean diameter can cause significant roughness. To detect these and insure the selection of good pieces, three-point electronic indicator inspection must be made. For ultra-precise or quiet applications, pieces are often

Copyright 2004, Industrial Press, Inc., New York, NY

checked on a "Talyrond" or a similar continuous recording instrument capable of measuring to within a few millionths of an inch. Though this may seem extreme, it has been found that shaft deformities will be reflected through inner races shrunk onto them. Similarly, tight-fit outer races pick up significant deviations in housings. In many instrument and in missile guidance applications, such deviations and deformities may have to be limited to less than .00002 inch.

In most of these precision applications, bearings are used with rolling elements controlled to less than 5 millionths of an inch deviation from roundness and within the same range for diameter.

Special attention is required both in housing design and in assembly of the bearing to shaft and housing. Housing response to axial excursions forced by bearing wobble (which in itself is a result of out-of-square mounting) has been found to be a major source of small electric and other rotating equipment noise and howl. Stiffer, more massive housings and careful alignment of bearing races can make significant improvements in applications where noise or vibration has been found to be objectionable.

Table 22. Commercial Application Alignment Tolerances

Feature	Location	Tolerance
Housing Face Runout	1	Square to shaft center within .0004 inch/inch of radius full indicatoreading.
Outer Race Face Runout	2	Square to shaft center within .0004 inch/inch of radius full indicator reading and complementary to the housing runout (not opposed).
Inner Race Face Runout	3	Square to shaft center within .0003 inch/inch of radius full indicator reading.
Cover and Closure Mounting Face Parallelism	4 and 5	Parallel within .001.
Housing Mounting Face Parallelism	6	Parallel within .001



Squareness and Alignment.— In addition to the limits for roundness and wall variation of the races and their supports, squareness of end faces and shoulders must be closely controlled. Tolerances of .0001 inch full indicator reading per inch of diameter are normally required for end faces and shoulders, with appropriately selected limits for fillet eccentricities. The latter must also fall within specified limits for radii tolerances to prevent interference and the resulting cocking of the race. Reference should be made to the bearing dimension tables which list corner radii for typical bearings. Shoulders must also be of a sufficient height to insure proper support for the races, since they are of hardened steel and are less capable of absorbing shock loads and abuse. The general subject of squareness and alignment is of primary importance to the life of rolling element bearings.

Copyright 2004, Industrial Press, Inc., New York, NY

The following recommendations for shaft and housing design are given by the New Departure Division of General Motors Corporation:*

"As a rule, there is little trouble experienced with inaccuracies in shafts. Bearings seats and locating shoulders are turned and ground to size with the shaft held on centers and, with ordinary care, there is small chance for serious out-of-roundness or taper. Shaft shoulders should present sufficient surface in contact with the bearing face to assure positive and accurate location.

"Where an undercut must be made for wheel runout in grinding a bearing seat, care should be exercised that no sharp corners are left, for it is at such points that fatigue is most likely to result in shaft breakage. It is best to undercut as little as possible and to have the undercut end in a fillet instead of a sharp corner.

"Where clamping nuts are to be used, it is important to cut the threads as true and square as possible in order to insure even pressure at all points on the bearing inner ring faces when the nuts are set up tight. It is also important not to cut threads so far into the bearing seat as to leave part of the inner ring unsupported or carried on the threads. Excessive deflection is usually the result of improperly designed or undersized machine parts. With a weak shaft, it is possible to seriously affect bearing operation through misalignment due to shaft deflection. Where shafts are comparatively long, the diameter between bearings must be great enough to properly resist bending. In general, the use of more than two bearings on a single shaft should be avoided, owing to the difficulty of securing accurate alignment. With bearings mounted close to each other, this can result in extremely heavy bearing loads.

"Design is as important as careful machining in construction of accurate bearing housings. There should be plenty of metal in the wall sections and large, thin areas should be avoided as much as possible, since they are likely to permit deflection of the boring tool when the housing is being finish-machined.

"Wherever possible, it is best to design a housing so that the radial load placed on the bearing is transmitted as directly as possible to the wall or rib supporting the housing. Diaphragm walls connecting an offset housing to the main wall or side of a machine are apt to deflect unless made thick and well braced.

"When two bearings are to be mounted opposed, but in separate housings, the housings should be so reinforced with fins or webs as to prevent deflection due to the axial load under which the bearings are opposed.

"Where housings are deep and considerable overhang of the boring tool is required, there is a tendency to produce out-of-roundness and taper, unless the tool is very rigid and light finishing cuts are taken. In a too roughly bored housing there is a possibility for the ridges of metal to peen down under load, thus eventually resulting in too loose a fit for the bearing outer ring."

Soft Metal and Resilient Housings.— In applications relying on bearing housings made of soft materials (aluminum, magnesium, light sheet metal, etc.) or those which lose their fit because of differential thermal expansion, outer race mounting must be approached in a cautious manner. Of first importance is the determination of the possible consequences of race loosening and turning. In conjunction with this, the type of loading must be considered for it may serve to magnify the effect of race loosening. It must be remembered that generally, balancing processes do not insure zero unbalance at operating speeds, but rather an "acceptable" maximum. This force exerted by the rotating element on the outer race can initiate a precession which will aggravate the race loosening problem by causing further attrition through wear, pounding, and abrasion. Since this force is generally of an order greater than the friction forces in effect between the outer race, housing, and closures (retaining nuts also), no foolproof method can be recommended for securing outer races in housings which deform significantly under load or after appreciable service wear. Though

* New Departure Handbook. Vol. II — 1951.

Copyright 2004, Industrial Press, Inc., New York, NY

many such "fixes" are offered, the only sure solution is to press the race into a housing of sufficient stiffness with the heaviest fit consistent with the installed and operating clearances. In many cases, inserts, or liners of cast iron or steel are provided to maintain the desired fit and increase useful life of both bearing and housing.

Quiet or Vibration-free Mountings.— In seeming contradiction is the approach to bearing mountings in which all shaft or rotating element excursions must be isolated from the frame, housing, or supporting structure. Here bearing outer races are often supported on elastomeric or metallic springs. Fundamentally, this is an isolation problem and must be approached with caution to insure solution of the primary bearing objective — location and restraint of the rotating body, as well as the reduction or elimination of the dynamic problem. Again, the danger of skidding rolling elements must be considered and reference to the resident engineers or sales engineers of the numerous bearing companies is recommended, as this problem generally develops requirements for special, or non-catalog-type bearings.

General Mounting Precautions.— Since the last operations involving the bearing application — mounting and closing — have such important effects on bearing performance, durability, and reliability, it must be cautioned that more bearings are abused or "killed" in this early stage of their life than wear out or "die" under conditions for which they were designed. Hammer and chisel "mechanics" invariably handle bearings as though no blow could be too hard, no dirt too abrasive, and no misalignment of any consequence. Proper tools, fixtures, and techniques are a must for rolling bearing application, and it is the responsibility of the design engineer to provide for this in his design, advisory notes, mounting instructions, and service manuals. Nicks, dents, scores, scratches, corrosion staining, and dirt must be avoided if reliability, long life, and smooth running are to be expected of rolling bearings. All manufacturers have pertinent service instructions available for the bearing user. These should be followed for best performance. In a later section, methods for inspecting bearings and descriptions of most common bearing deficiencies will be given.

Seating Fits for Bearings.— Anti-Friction Bearing Manufacturers Association (AFBMA) standard shaft and housing bearing seat tolerances are given in Tables 13 through 18, inclusive.

Clamping and Retaining Methods.— Various methods of clamping bearings to prevent axial movement on the shaft are employed, one of the most common being a nut screwed on the end of the shaft and held in place by a tongued lock washer (see Table 23). The shaft thread for the clamping nut (see Table 24) should be cut in accurate relation to bearing seats and shoulders if bearing stresses are to be avoided. The threads used are of American National Form, Class 3; special diameters and data for these are given in Tables 25 and 26. Where somewhat closer than average accuracy is required, the washers and locknut faces may be obtained ground for closer alignment with the threads. For a high degree of accuracy the shaft threads are ground and a more precise clamping means is employed. Where a bearing inner ring is to be clamped, it is important to provide a sufficiently high shoulder on the shaft to locate the bearing positively and accurately. If the difference between bearing bore and maximum shaft diameter gives a low shoulder which would enter the corner of the radius of the bearing, a shoulder ring that extends above the shoulder and well into the shaft corner is employed. A shoulder ring with snap wire fitting into a groove in the shaft is sometimes used where no locating shaft shoulder is present. A snap ring fitting into a groove is frequently employed to prevent endwise movement of the bearing away from the locating shoulder where tight clamping is not required. Such a retaining ring should not be used where a slot in the shaft surface might lead to fatigue failure. Snap rings are also used to locate the outer bearing ring in the housing. Dimensions of snap rings used for this latter purpose are given in AFBMA and ANSI standards.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 23. AFBMA Standard Lockwashers (Series W-00) for Ball Bearings and Cylindrical and Spherical Roller Bearings and (Series TW-100) for Tapered Roller Bearings. Inch Design.



Type W No.	Q	Type TW No.	Q	Tangs		Key						Bore R		Diameter		Dia. Over Tangs. Max.	
					Width[a]	Project.[a]	Width S		X		X′						
				No.	T	V	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	E	Tol.	B	B′
W-00	.032	TW-100	.032	9	.120	.031	.110	.120	.334	.359	.334	.359	.406	0.421	0.625	+.015	0.875	0.891
W-01	.032	TW-101	.032	9	.120	.031	.110	.120	.412	.437	.412	.437	.484	.499	0.719	+.015	1.016	1.031
W-02	.032	TW-102	.048	11	.120	.031	.110	.120	.529	.554	.513	.538	.601	.616	0.813	+.015	1.156	1.156
W-03	.032	TW-103	.048	11	.120	.031	.110	.120	.607	.632	.591	.616	.679	.694	0.938	+.015	1.328	1.344
W-04	.032	TW-104	.048	11	.166	.031	.156	.176	.729	.754	.713	.738	.801	.816	1.125	+.015	1.531	1.563
W-05	.040	TW-105	.052	13	.166	.047	.156	.176	.909	.939	.897	.927	.989	1.009	1.281	+.015	1.719	1.703
W-06	.040	TW-106	.052	13	.166	.047	.156	.176	1.093	1.128	1.081	1.116	1.193	1.213	1.500	+.015	1.922	1.953
		TW-065	.052	15	.166	…	.156	.176	…	…	1.221	1.256	1.333	1.353	1.813	+.015	…	2.234
W-07	.040	TW-107	.052	15	.166	.047	.156	.176	1.296	1.331	1.284	1.319	1.396	1.416	1.813	+.015	2.250	2.250
W-08	.048	TW-108	.062	15	.234	.047	.250	.290	1.475	1.510	1.461	1.496	1.583	1.603	2.000	+.030	2.469	2.484
W-09	.048	TW-109	.062	17	.234	.062	.250	.290	1.684	1.724	1.670	1.710	1.792	1.817	2.281	+.030	2.734	2.719
W-10	.048	TW-110	.062	17	.234	.062	.250	.290	1.884	1.924	1.870	1.910	1.992	2.017	2.438	+.030	2.922	2.922
W-11	.053	TW-111	.062	17	.234	.062	.250	.290	2.069	2.109	2.060	2.100	2.182	2.207	2.656	±.030	3.109	3.094
W-12	.053	TW-112	.072	17	.234	.062	.250	.290	2.267	2.307	2.248	2.288	2.400	2.425	2.844	+.030	3.344	3.328
W-13	.053	TW-113	.072	19	.234	.062	.250	.290	2.455	2.495	2.436	2.476	2.588	2.613	3.063	+.030	3.578	3.563
W-14	.053	TW-114	.072	19	.234	.094	.250	.290	2.658	2.698	2.639	2.679	2.791	2.816	3.313	+.030	3.828	3.813
W-15	.062	TW-115	.085	19	.328	.094	.250	.290	2.831	2.876	2.808	2.853	2.973	3.003	3.563	+.030	4.109	4.047
W-16	.062	TW-116	.085	19	.328	.094	.313	.353	3.035	3.080	3.012	3.057	3.177	3.207	3.844	+.030	4.375	4.391

[a] *Tolerances:* On width, *T*, –.010 inch for Types W-00 to W-03 and TW-100 to TW-103; –.020 inch for W-04 to W-07 and TW-104 to TW-107; –.030 inch for all others shown. On Projection *V*, +.031 inch for all sizes up through W-13 and TW-113; +.062 inch for all others shown.

All dimensions in inches. For dimensions in millimeters, multiply inch values by 25.4 and round result to two decimal places.

Data for sizes larger than shown are given in ANSI/AFBMA Standard 8.2-1991.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 24. AFBMA Standard Locknuts (Series N-00) for Ball Bearings and Cylindrical and Spherical Roller Bearings and (Series TN-00) for Tapered Roller Bearings. Inch Design.

Runout and parallelism of faces measured on a tight fitting threaded arbor.

N-00 to N-06 = .002 Max.
N-07 to AN-15 = .004 Max.

TN-065 to TAN-15 = .002 Max.

Surface Finish Note

TN-065 to TN-11, 100μ in., max.
TN-12 to TAN-15, 120μ in., max.



N-00 through AN-15
TN-065 through TAN-15



BB & RB Nut No.	TRB Nut No.	Thds. per Inch	Thread Minor Deam.		Thread Pitch Dia.		Thd. Major Dia. *d*	Outside Dia. *C*	Face Dia. *E*		Slot dimension			Thickness *D*	
											Width *G*		Height *H*		
			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Min.	Max.
N-00	—	32	0.3572	0.3606	0.3707	0.3733	0.391	0.755	.605	.625	.120	.130	.073	.209	.229
N-01	—	32	0.4352	0.4386	0.4487	0.4513	0.469	0.880	.699	.719	.120	.130	.073	.303	.323
N-02	—	32	0.5522	0.5556	0.5657	0.5687	0.586	1.005	.793	.813	.120	.130	.104	.303	.323
N-03	—	32	0.6302	0.6336	0.6437	0.6467	0.664	1.130	.918	.938	.120	.130	.104	.334	.354
N-04	—	32	0.7472	0.7506	0.7607	0.7641	0.781	1.380	1.105	1.125	.178	.198	.104	.365	.385
N-05	—	32	0.9352	0.9386	0.9487	0.9521	0.969	1.568	1.261	1.281	.178	.198	.104	.396	.416
N-06	—	18	1.1129	1.1189	1.1369	1.1409	1.173	1.755	1.480	1.500	.178	.198	.104	.396	.416
	TN-065	18	1.2524	1.2584	1.2764	1.2804	1.312	2.068	1.793	1.813	.178	.198	.104	.428	.448
N-07	TN-07	18	1.3159	1.3219	1.3399	1.3439	1.376	2.068	1.793	1.813	.178	.198	.104	.428	.448
N-08	TN-08	18	1.5029	1.5089	1.5269	1.5314	1.563	2.255	1.980	2.000	.240	.260	.104	.428	.448
N-09	TN-09	18	1.7069	1.7129	1.7309	1.7354	1.767	2.536	2.261	2.281	.240	.260	.104	.428	.448
N-10	TN-10	18	1.9069	1.9129	1.9309	1.9354	1.967	2.693	2.418	2.438	.240	.260	.104	.490	.510
N-11	TN-11	18	2.0969	2.1029	2.1209	2.1260	2.157	2.974	2.636	2.656	.240	.260	.135	.490	.510
N-12	TN-12	18	2.2999	2.3059	2.3239	2.3290	2.360	3.161	2.824	2.844	.240	.260	.135	.521	.541
N-13	TN-13	18	2.4879	2.4949	2.5119	2.5170	2.548	3.380	3.043	3.063	.240	.260	.135	.553	.573
N-14	TN-14	18	2.6909	2.6969	2.7149	2.7200	2.751	3.630	3.283	3.313	.240	.260	.135	.553	.573
AN-15	TAN-15	12	2.8428	2.8518	2.8789	2.8843	2.933	3.880	3.533	3.563	.360	.385	.135	.584	.604

All dimensions in inches. For dimensions in millimeters, multiply inch values, except thread diameters, by 25.4 and round result to two decimal places.

Threads are American National form, Class 3.

Typical steels for locknuts are: AISI, C1015, C1018, C1020, C1025, C1035, C1117, C1118, C1212, C1213, and C1215. Minimum hardness, tensile strength, yield strength and elongation are given in ANSI/ABMA 8.2-1991 which also lists larger sizes of locknuts.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 25. AFBMA Standard for Shafts for Locknuts (series N-00) for Ball Bearings and Cylindrical and Spherical Roller Bearings. Inch Design.



Locknut Number	Bearing Bore	V_2	Threads[a]					Relief		Keyway		
			No. per inch	Major Dia.	Pitch Dia.	Minor Dia.	Length *L*	Dia. *A*	Width *W*	Depth *H*	Width *S*	*M*
		Max.		Max.	Max.	Max.	Max.	Max.	Max.	Min.	Min.	Min.
N-00	0.3937	0.312	32	0.391	0.3707	0.3527	0.297	0.3421	0.078	0.062	0.125	0.094
N-01	0.4724	0.406	32	0.469	0.4487	0.4307	0.391	0.4201	0.078	0.062	0.125	0.094
N-02	0.5906	0.500	32	0.586	0.5657	0.5477	0.391	0.5371	0.078	0.078	0.125	0.094
N-03	0.6693	0.562	32	0.664	0.6437	0.6257	0.422	0.6151	0.078	0.078	0.125	0.094
N-04	0.7874	0.719	32	0.781	0.7607	0.7427	0.453	0.7321	0.078	0.078	0.188	0.094
N-05	0.9843	0.875	32	0.969	0.9487	0.9307	0.484	0.9201	0.078	0.094	0.188	0.125
N-06	1.1811	1.062	18	1.173	1.1369	1.1048	0.484	1.0942	0.109	0.094	0.188	0.125
N-07	1.3780	1.250	18	1.376	1.3399	1.3078	0.516	1.2972	0.109	0.094	0.188	0.125
N-08	1.5748	1.469	18	1.563	1.5269	1.4948	0.547	1.4842	0.109	0.094	0.312	0.125
N-09	1.7717	1.688	18	1.767	1.7309	1.6988	0.547	1.6882	0.141	0.094	0.312	0.156
N-10	1.9685	1.875	18	1.967	1.9309	1.8988	0.609	1.8882	0.141	0.094	0.312	0.156
N-11	2.1654	2.062	18	2.157	2.1209	2.0888	0.609	2.0782	0.141	0.125	0.312	0.156
N-12	2.3622	2.250	18	2.360	2.3239	2.2918	0.641	2.2812	0.141	0.125	0.312	0.156
N-13	2.5591	2.438	18	2.548	2.5119	2.4798	0.672	2.4692	0.141	0.125	0.312	0.156
N-14	2.7559	2.625	18	2.751	2.7149	2.6828	0.672	2.6722	0.141	0.125	0.312	0.250
AN-15	2.9528	2.781	12	2.933	2.8789	2.8308	0.703	2.8095	0.172	0.125	0.312	0.250
AN-16	3.1496	3.000	12	3.137	3.0829	3.0348	0.703	3.0135	0.172	0.125	0.375	0.250

[a] Threads are American National form Class 3.

All dimensions in inches. For dimensions in millimeters, multiply inch values, except thread diameters, by 25.4 and round result to two decimal places. See footnote to Table 26 for material other than sttel.For sizes larger than shown, see ANSI/ABMA 8.2-1991.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 26. AFBMA Standard for Shafts for Tapered Roller Bearing Locknuts. Inch Design.



Locknut Number	Bearing Bore	V_2	Threads[a]						Relief		Keyway			
			No. per inch	Major Dia.	Pitch Dia.	Minor Dia.	Length L_1	Length L_2	Dia. A	Width W	Depth H	Width S	M	U
		Max.		Max.	Max.	Max.	Max.	Max.	Max.	Max.	Max.	Min.	Min.	Min.
N-00	0.3937	0.312	32	0.391	0.3707	0.3527	0.609	0.391	0.3421	0.078	0.094	0.125	0.094	0.469
N-01	0.4724	0.406	32	0.469	0.4487	0.4307	0.797	0.484	0.4201	0.078	0.094	0.125	0.094	0.562
N-02	0.5906	0.500	32	0.586	0.5657	0.5477	0.828	0.516	0.5371	0.078	0.094	0.125	0.094	0.594
N-03	0.6693	0.562	32	0.664	0.6437	0.6257	0.891	0.547	0.6151	0.078	0.078	0.125	0.094	0.625
N-04	0.7874	0.703	32	0.781	0.7607	0.7427	0.922	0.547	0.7321	0.078	0.094	0.188	0.094	0.625
N-05	0.9843	0.875	32	0.969	0.9487	0.9307	1.016	0.609	0.9201	0.078	0.125	0.188	0.125	0.719
N-06	1.1811	1.062	18	1.173	1.1369	1.1048	1.016	0.609	1.0942	0.109	0.125	0.188	0.125	0.719
TN-065	1.3750	1.188	18	1.312	1.2764	1.2443	1.078	0.641	1.2337	0.109	0.125	0.188	0.125	0.750
TN-07	1.3780	1.250	18	1.376	1.3399	1.3078	1.078	0.641	1.2972	0.109	0.125	0.188	0.125	0.750
TN-08	1.5748	1.438	18	1.563	1.5269	1.4948	1.078	0.641	1.4842	0.109	0.125	0.312	0.125	0.750
TN-09	1.7717	1.656	18	1.767	1.7309	1.6988	1.078	0.641	1.6882	0.141	0.125	0.312	0.156	0.781
TN-10	1.9685	1.859	18	1.967	1.9309	1.8988	1.203	0.703	1.882	0.141	0.125	0.312	0.156	0.844
TN-11	2.1654	2.047	18	2.157	2.1209	2.0888	1.203	0.703	2.0782	0.141	0.125	0.312	0.156	0.844
TN-12	2.3622	2.250	18	2.360	2.3239	2.2918	1.297	0.766	2.2812	0.141	0.156	0.312	0.156	0.906
TN-13	2.5591	2.422	18	2.548	2.5119	2.4798	1.359	0.797	2.4692	0.141	0.156	0.312	0.156	0.938
TN-14	2.7559	2.625	18	2.751	2.7149	2.6828	1.359	0.797	2.6722	0.141	0.156	0.312	0.250	1.000
TAN-15	2.9528	2.781	12	2.933	2.8789	2.8308	1.422	0.828	2.8095	0.172	0.188	0.312	0.250	1.031
TAN-16	3.1496	3.000	12	3.137	3.0829	3.0348	1.422	0.828	3.0135	0.172	0.188	0.375	0.250	1.031

[a] Threads are American National form Class 3.

All dimensions in inches. For dimensions in millimeters, multiply inch values, except thread diameters, by 25.4 and round results to two decimal places.These data apply to steel. When either the nut or the shaft is made of stainless steel, aluminum, or other material having a tendency to seize, it is recommended that the maximum thread diameter of the shaft, both major and pitch, be reduced by 20 per cent of the pitch diameter tolerance listed in the Standard.For sizes larger than shown, see ANSI/ABMA 8.2-1991.

Copyright 2004, Industrial Press, Inc., New York, NY

Bearing Closures.— Shields, seals, labyrinths, and slingers are employed to retain the lubricant in the bearing and to prevent the entry of dirt, moisture, or other harmful substances. The type selected for a given application depends upon the lubricant, shaft, speed, and the atmospheric conditions in which the unit is to operate. The shields or seals may be located in the bearing itself. Shields differ from seals in that they are attached to one bearing race but there is a definite clearance between the shield and the other, usually the inner, race. When a shielded bearing is placed in a housing in which the grease space has been filled, the bearing in running will tend to expel excess grease past the shields or to accept grease from the housing when the amount in the bearing itself is low.

Seals of leather, rubber, cork, felt, or plastic composition may be used. Since they must bear against the rotating member, excessive pressure should be avoided and some lubricant must be allowed to flow into the area of contact in order to prevent seizing and burning of the seal and scoring of the rotating member. Some seals are made up in the form of cartridges which can be pressed into the end of the bearing housing.

Leather seals may be used over a wide range of speeds. Although lubricant is best retained with a leather cupped inward toward the bearing, this arrangement is not suitable at high speeds due to danger of burning the leather. At high speeds where abrasive dust is present, the seal should be arranged with the leather cupped outward to lead some lubricant into the contact area. Only light pressure of leather against the shaft should be maintained.

Bearing Fits.— The slipping or creeping of a bearing ring on a rotating shaft or in a rotating housing occurs when the fit of the ring on the shaft or in the housing is loose. Such slipping or creeping action may cause rapid wear of both shaft and bearing ring when the surfaces are dry and highly loaded. To prevent this action the bearing is customarily mounted with the rotating ring a press fit and the stationary ring a push fit, the tightness or looseness depending upon the service intended. Thus, where shock or vibratory loads are to be encountered, fits should be made somewhat tighter than for ordinary service. The stationary ring, if correctly fitted, is allowed to creep very slowly so that prolonged stressing of one part of the raceway is avoided.

To facilitate the assembly of a bearing on a shaft it may become necessary to expand the inner ring by heating. This should be done in clean oil or in a temperature-controlled furnace at a temperature of between 200 and 250°F. The utmost care must be used to make sure that the temperature does not exceed 250°F. as overheating will tend to reduce the hardness of the rings. Prelubricated bearings should not be mounted by this method.

Design Considerations

Friction Losses in Rolling Element Bearings.— The static and kinematic torques of rolling element bearings are generally small and in many applications are not significant. Bearing torque is a measure of the frictional resistance of the bearing to rotation and is the sum of three components: the torque due to the applied load; the torque due to viscous forces in lubricated rolling element bearings; and the torque due to roller end motions, for example, thrust loads against flanges. The friction or torque data may be used to calculate power absorption or heat generation within the bearing and can be utilized in efficiency or system-cooling studies.

Empirical equations have been developed for each of the torque components. These equations are influenced by such factors as bearing load, lubrication environment, and bearing design parameters. These design parameters include sliding friction from contact between the rolling elements and separator surfaces or between adjacent rolling elements; rolling friction from material deformations during the passage of the rolling elements over the race path; skidding or sliding of the Hertzian contact; and windage friction as a function of speed.

Starting or breakaway torques are also of interest in some situations. Breakaway torques tend to be between 1.5 and 1.8 times the running or kinetic torques.

Copyright 2004, Industrial Press, Inc., New York, NY

When evaluating the torque requirements of a system under design, it should be noted that other components of the bearing package, such as seals and closures, can increase the overall system torque significantly. Seal torques have been shown to vary from a fraction of the bearing torque to several times that torque. In addition, the torque values given can vary significantly when load, speed of rotation, temperature, or lubrication are outside normal ranges.

For small instrument bearings friction torque has implications more critical than for larger types of bearings. These bearings have three operating friction torques to consider: starting torque, normal running torque, and peak running torque. These torque levels may vary between manufacturers and among lots from a given manufacturer.

Instrument bearings are even more critically dependent on design features — radial play, retainer type, and race conformity — than larger bearings. Typical starting torque values for small bearings are given in the accompanying table, extracted from the New Departure General Catalog.

Finally, if accurate control of friction torque is critical to a particular application, tests of the selected bearings should be conducted to evaluate performance.

Starting Torque — ABEC7

Bearing Bore (in.)	Max. Starting Torque (g cm)	Thrust Load (g)	Minimum Radial Play Range (inches)	
			High Carbon Chrome Steel and All Miniatures	Stainless Steel Except Miniatures
0.125	0.10	75	0.0003–0.0005	—
	0.14	75	0.0002–0.0004	0.0004–0.0006
	0.18	75	0.0001–0.0003	0.0003–0.0005
	0.22	75	0.0001–0.0003	0.0001–0.0003
0.1875–0.312	0.40	400	0.0005–0.0008	—
	0.45	400	0.0004–0.0006	0.0005–0.0008
	0.50	400	0.0003–0.0005	0.0003–0.0005
	0.63	400	0.0001–0.0003	0.0002–0.0004
0.375	0.50	400	0.0005–0.0008	0.0008–0.0011
	0.63	400	0.0004–0.0006	0.0005–0.0008
	0.75	400	0.0003–0.0005	0.0004–0.0006
	0.95	400	0.0002–0.0004	0.0003–0.0005

Selection of Ball and Roller Bearings.— As compared with sleeve bearings, ball and roller bearings offer the following advantages: 1) Starting friction is low; 2) Less axial space is required; 3) Relatively accurate shaft alignment can be maintained; 4) Both radial and axial loads can be carried by certain types; 5) Angle of load application is not restricted; 6) Replacement is relatively easy; 7) Comparatively heavy overloads can be carried momentarily; 8) Lubrication is simple; and 9) Design and application can be made with the assistance of bearing supplier engineers.

In selecting a ball or roller bearing for a specific application five choices must be made: 1) the bearing series; 2) the type of bearing; 3) the size of bearing; 4) the method of lubrication; and 5) the type of mounting.

Naturally these considerations are modified or affected by the anticipated operating conditions, expected life, cost, and overhaul philosophy.

It is well to review the possible history of the bearing and its function in the machine it will be applied to, thus: 1) Will it be expected to endure removal and reapplication?; 2) Must it be free from maintenance attention during its useful life?; 3) Can wear of the housing or shaft be tolerated during the overhaul period?; 4) Must it be adjustable to take up wear, or to change shaft location?; 5) How accurately can the load spectrum be estimated? and; and 6) Will it be relatively free from abuse in operation?.

Copyright 2004, Industrial Press, Inc., New York, NY

Though many cautions could be pointed out, it should always be remembered that inadequate design approaches limit the utilization of rolling element bearings, reduce customer satisfaction, and reduce reliability. Time spent in this stage of design is the most rewarding effort of the bearing engineer, and here again he can depend on the bearing manufacturers' field organization for assistance.

Type: Where loads are low, ball bearings are usually less expensive than roller bearings in terms of unit-carrying capacity. Where loads are high, the reverse is usually true.

For a purely radial load, almost any type of radial bearing can be used, the actual choice being determined by other factors. To support a combination of thrust and radial loads, several types of bearings may be considered. If the thrust load component is large, it may be most economical to provide a separate thrust bearing. When a separate thrust bearing cannot be used due to high speed, lack of space, or other factors, the following types may be considered: angular contact ball bearing, deep groove ball bearing without filling slot, tapered roller bearing with steep contact angle, and self-aligning bearing of the wide type. If movement or deflection in an axial direction must be held to a minimum, then a separate thrust bearing or a preloaded bearing capable of taking considerable thrust load is required. To minimize deflection due to a moment in an axial plane, a rigid bearing such as a double row angular contact type with outwardly converging load lines is required. In such cases, the resulting stresses must be taken into consideration in determining the proper size of the bearing.

For shock loads or heavy loads of short duration, roller bearings are usually preferred.

Special bearing designs may be required where accelerations are usually high as in planetary or crank motions.

Where the problem of excessive shaft deflection or misalignment between shaft and housing is present, a self-aligning type of bearing may be a satisfactory solution.

It should be kept in mind that a great deal of difficulty can be avoided if standard types of bearings are used in preference to special designs, wherever possible.

Size: The size of bearing required for a given application is determined by the loads that are to be carried and, in some cases, by the amount of rigidity that is necessary to limit deflection to some specified amount.

The forces to which a bearing will be subjected can be calculated by the laws of engineering mechanics from the known loads, power, operating pressure, etc. Where loads are irregular, varying, or of unknown magnitude, it may be difficult to determine the actual forces. In such cases, empirical determination of such forces, based on extensive experience in bearing design, may be needed to attack the problem successfully. Where such experience is lacking, the bearing manufacturer should be consulted or the services of a bearing expert obtained.

If a ball or roller bearing is to be subjected to a combination of radial and thrust loads, an *equivalent radial load* is computed in the case of radial or angular type bearings and an *equivalent thrust load* is computed in the case of thrust bearings.

Method of Lubrication.— If speeds are high, relubrication difficult, the shaft angle other than horizontal, the application environment incompatible with normal lubrication, leakage cannot be tolerated; if other elements of the mechanism establish the lubrication requirements, bearing selection must be made with these criteria as controlling influences. Modern bearing types cover a wide selection of lubrication means. Though the most popular type is the "cartridge" type of sealed grease ball bearing, many applications have requirements which dictate against them. Often, operating environments may subject bearings to temperatures too high for seals utilized in the more popular designs. If minute leakage or the accumulation of traces of dirt at seal lips cannot be tolerated by the application (as in baking industry machinery), then the selections of bearings must be made with other sealing and lubrication systems in mind.

Copyright 2004, Industrial Press, Inc., New York, NY

High shaft speeds generally dictate bearing selection based on the need for cooling, the suppression of churning or aeration of conventional lubricants, and most important of all, the inherent speed limitations of certain bearing types. An example of the latter is the effect of cage design and of the roller-end thrust-flange contact on the lubrication requirements in commercial taper roller bearings, which limit the speed they can endure and the thrust load they can carry. Reference to the manufacturers' catalog and application-design manuals is recommended before making bearing selections.

See *Anti-friction Bearing Lubrication* on page 2339 for more information on this topic.

Type of Mounting.— Many bearing installations are complicated because the best adapted type was not selected. Similarly, performance, reliability, and maintenance operations are restricted because the mounting was not thoroughly considered. There is no universally adaptable bearing for all needs. Careful reviews of the machine requirements should be made before designs are implemented. In many cases complicated machining, redundant shaft and housings, and use of an oversize bearing can be eliminated if the proper bearing in a well-thought-out mounting is chosen.

Advantage should be taken of the many race variations available in "standard" series of bearings. Puller grooves, tapered sleeves, ranged outer races, split races, fully demountable rolling-element and cage assemblies, flexible mountings, hydraulic removal features, relubrication holes and grooves, and many other innovations are available beyond the obvious advantages which are inherent in the basic bearing types.

Radial and Axial Clearance.— In designing the bearing mounting, a major consideration is to provide running clearances consistent with the requirements of the application. Race fits must be expected to absorb some of the original bearing clearance so that allowance should be made for approximately 80 per cent of the actual interference showing up in the diameter of the race. This will increase for heavy, stiff housings or for extra light series races shrunk onto solid shafts, while light metal housings (aluminum, magnesium, or sheet metal) and tubular shafts with wall sections less than the race wall thickness will cause a lesser change in the race diameter.

Where the application will impose heat losses through housing or shaft, or where a temperature differential may be expected, allowances must be made in the proper direction to insure proper operating clearance. Some compromises are required in applications where the indicated modification cannot be fully accommodated without endangering the bearing performance at lower speeds, during starting, or under lower temperature conditions than anticipated. Some leeway can be relied on with ball bearings since they can run with moderate preloads (.0005 inch, max.) without affecting bearing life or temperature rise. Roller bearings, however, have a lesser tolerance for preloading, and must be carefully controlled to avoid overheating and resulting self-destruction.

In all critical applications axial and radial clearances should be checked with feeler gages or dial indicators to insure mounted clearances within tolerances established by the design engineer. Since chips, scores, race misalignment, shaft or housing denting, housing distortion, end cover (closure) off-squareness, and mismatch of rotor and housing axial dimensions can rob the bearing of clearance, careful checks of running clearance is recommended.

For precision applications, taper-sleeve mountings, opposed ball or tapered-roller bearings with adjustable or shimmed closures are employed to provide careful control of radial and/or axial clearances. This practice requires skill and experience as well as the initial assistance of the bearing manufacturer's field engineer.

Tapered bore bearings are often used in applications such as these, again requiring careful and well worked-out assembly procedures. They can be assembled on either tapered shafts or on adapter sleeves. Advancement of the inner race over the tapered shaft can be done either by controlled heating (to expand the race as required) or by the use of a hydraulic jack. The adapter sleeve is supplied with a lock-nut which is used to advance the race on

Copyright 2004, Industrial Press, Inc., New York, NY

the tapered sleeve. With the heavier fits normally required to effect the clearance changes compatible with such mountings, hydraulic removal devices are normally recommended.

For the conventional application, with standard fits, clearances provided in the standard bearing are suitable for normal operation. To insure that the design conditions are "normal," a careful review of the application requirements, environments, operating speed range, anticipated abuses, and design parameters must be made.

General Bearing Handling Precautions.— To insure that rolling element bearings are capable of achieving their design life and that they perform without objectionable noise, temperature rise, or shaft excursions, the following precautions are recommended:

1) Use the best bearing available for the application, consistent with the value of the application. Remember, the cost of the best bearing is generally small compared to the replacement costs of the rotating components that can be destroyed if a bearing fails or malfunctions.

2) If questions arise in designing the bearing application, seek out the assistance of the bearing manufacturer's representative.

3) Handle bearings with care, keeping them in the sealed, original container until ready to use.

4) Follow the manufacturer's instructions in handling and assembling the bearings.

5) Work with clean tools, clean dry hands, and in clean surroundings.

6) Do not wash or wipe bearings prior to installation unless special instructions or requirements have been established to do so.

7) Place unwrapped bearings on clean paper and keep them similarly covered until applied, if they cannot be kept in the original container.

8) Don't use wooden mallets, brittle or chipped tools, or dirty fixtures and tools in mounting bearings.

9) Don't spin uncleaned bearings, nor spin *any* bearing with an air blast.

10) Use care not to scratch or nick bearings.

11) Don't strike or press on race flanges.

12) Use adapters for mounting which provide uniform steady pressure rather than hammering on a drift or sleeve.

13) Insure that races are started onto shafts and into housings evenly so as to prevent cocking.

14) Inspect shafts and housings before mounting beating to insure that proper fits will be maintained.

15) When removing beatings, clean housings, covers, and shafts before exposing the bearings. All dirt can be considered an abrasive, dangerous to the reuse of any rolling bearing.

16) Treat used beatings, which may be reused, as new ones.

17) Protect dismantled bearings from dirt and moisture.

18) Use clean, lint-free rags if bearings are wiped.

19) Wrap beatings in clean, oil-proof paper when not in use.

20) Use clean filtered, water-free Stoddard's solvent or flushing oil to clean bearings.

21) In heating beatings for mounting onto shafts, follow manufacturer's instructions.

22) In assembling bearings onto shafts *never* strike the outer race, or press on it to force the inner race. Apply the pressure on the inner race only. In dismantling follow the same precautions.

23) Do not press, strike, or otherwise force the seal or shield on factory-sealed beatings.

Copyright 2004, Industrial Press, Inc., New York, NY

Bearing Failures, Deficiencies, and Their Origins.— The general classifications of failures and deficiencies requiting bearing removal are:

1) Overheating due to a) Inadequate or insufficient lubrication; b) Excessive lubrication; c) Grease liquefaction or aeration; d) Oil foaming; e) Abrasive or corrosive action due to contaminants in beating; f) Distortion of housing due to warping, or out-of-round; g) Seal rubbing or failure; h) Inadequate or blocked scavenge oil passages; i) Inadequate beating-clearance or bearing-preload; j) Race turning; k) Cage wear; and l) Shaft expansion–loss of bearing or seal clearance.

2) Vibration due to a) Dirt or chips in bearing; b) Fatigued race or rolling elements; c) Race turning; d) Rotor unbalance; e) Out-of-round shaft; f) Race misalignment; g) Housing resonance; h) Cage wear; i) Flats on races or rolling elements; j) Excessive clearance; k) Corrosion; l) False-brinelling or indentation of races; m) Electrical discharge (similar to corrosion effects); n) Mixed rolling element diameters; and o) Out-of-square rolling paths in races.

3) Turning on shaft due to a) Growth of race due to overheating; b) Fretting wear; c) Improper initial fit; d) Excessive shaft deflection; e) Initially coarse shaft finish; and f) Seal rub on inner race.

4) Binding of the shaft due to a) Lubricant breakdown; b) Contamination by abrasive or corrosive matter; c) Housing distortion or out-of-round pinching bearing; d) Uneven shimming of housing with loss of clearance; e) Tight rubbing seals; f) Preloaded beatings; g) Cocked races; h) Loss of clearance due to excessive tightening of adapter; i) Thermal expansion of shaft or housing; and j) Cage failure.

5) Noisy bearing due to a) Lubrication breakdown, inadequate lubrication, stiff grease; b) Contamination; c) Pinched beating; d) Seal rubbing; e) Loss of clearance and preloading; f) Bearing slipping on shaft or in housing; g) Flatted roller or ball; h) Brinelling due to assembly abuse, handling, or shock loads; i) Variation in size of rolling elements; j) Out-of-round or lobular shaft; k) Housing bore waviness; and l) Chips or scores under beating race seat.

6) Displaced shaft due to a) Bearing wear; b) Improper housing or closure assembly; c) Overheated and shifted bearing; d) Inadequate shaft or housing shoulder; e) Lubrication and cage failure permitting rolling elements to bunch; f) Loosened retainer nut or adapter; g) Excessive heat application in assembling inner race, causing growth and shifting on shaft; and h) Housing pounding out.

7) Lubricant leakage due to a) Overfilling of lubricant; b) Grease churning due to use of too soft a consistency; c) Grease deterioration due to excessive operating temperature; d) Operating life longer than grease life (grease breakdown, aeration, and purging); e) Seal wear; f) Wrong shaft attitude (bearing seals designed for horizontal mounting only); g) Seal failure; h) Clogged breather; i) Oil foaming due to churning or air flow through housing; j) Gasket (O-ring) failure or misapplication; k) Porous housing or closure; and l) Lubricator set at wrong flow rate.

Load Ratings and Fatigue Life

Ball and Roller Bearing Life.— The performance of ball and roller bearings is a function of many variables. These include the bearing design, the characteristics of the material from which the bearings are made, the way in which they are manufactured, as well as many variables associated with their application. The only sure way to establish the satisfactory operation of a bearing selected for a specific application is by actual performance in the application. As this is often impractical, another basis is required to estimate the suitability of a particular bearing for a given application. Two factors are taken into consideration: the beating fatigue life, and its ability to withstand static loading.

Life Criterion: Even if a ball or roller bearing is properly mounted, adequately lubricated, protected from foreign matter and not subjected to extreme operating conditions, it

Copyright 2004, Industrial Press, Inc., New York, NY

can ultimately fatigue. Under ideal conditions, the repeated stresses developed in the contact areas between the balls or rollers and the raceways eventually can result in the fatigue of the material which manifests itself with the spalling of the load-carrying surfaces. In most applications the fatigue life is the maximum useful life of a bearing.

Static Load Criterion: A static load is a load acting on a non-rotating bearing. Permanent deformations appear in balls or rollers and raceways under a static load of moderate magnitude and increase gradually with increasing load. The permissible static load is, therefore, dependent upon the permissible magnitude of permanent deformation. It has been found that for ball and roller bearings suitably manufactured from hardened alloy steel, deformations occurring under maximum contact stress of 4,000 megapascals (580,000 pounds per square inch) acting at the center of contact (in the case of roller beatings, of a uniformly loaded roller) do not greatly impair smoothness or friction. Depending on requirements for smoothness of operation, friction, or sound level, higher or lower static load limits may be tolerated.

Ball Bearing Types Covered.— AFBMA and American National Standard ANSI/ABMA 9-1990 sets forth the method of determining ball bearing Rating Life and Static Load Rating and covers the following types:

1) *Radial, deep groove and angular contact ball bearings* whose inner ring race-ways have a cross-sectional radius not larger than 52 percent of the ball diameter and whose outer ring raceways have a cross-sectional radius not larger than 53 percent of the ball diameter.

2) *Radial, self-aligning ball bearings* whose inner ring raceways have cross-sectional radii not larger than 53 percent of the ball diameter.

3) *Thrust ball bearings* whose washer raceways have cross-sectional radii not larger than 54 percent of the ball diameter.

4) *Double row, radial and angular contact ball bearings* and double direction thrust ball bearings are presumed to be symmetrical.

Limitations for Ball Bearings.— The following limitations apply:

1) *Truncated contact area*. This standard* may not be safely applied to ball bearings subjected to loading which causes the contact area of the ball with the raceway to be truncated by the raceway shoulder. This limitation depends strongly on details of bearing design which are not standardized.

2) *Material*. This standard applies only to ball bearings fabricated from hardened good quality steel.

3) *Types*. The f_c factors specified in the basic load rating formulas are valid only for those ball bearing types specified above.

4) *Lubrication*. The Rating Life calculated according to this standard is based on the assumption that the bearing is adequately lubricated. The determination of adequate lubrication depends upon the bearing application.

5) *Ring support and alignment*. The Rating Life calculated according to this standard assumes that the bearing inner and outer rings are rigidly supported and the inner and outer ring axes are properly aligned.

6) *Internal clearance*. The radial ball bearing Rating Life calculated according to this standard is based on the assumption that only a nominal interior clearance occurs in the mounted bearing at operating speed, load and temperature.

7) *High speed effects*. The Rating Life calculated according to this standard does not account for high speed effects such as ball centrifugal forces and gyroscopic moments. These effects tend to diminish fatigue life. Analytical evaluation of these effects frequently requires the use of high speed digital computation devices and hence is not covered in the standard.

* All references to "standard" are to AFBMA and American National Standard "Load Ratings and Fatigue Life for Ball Bearings"ANSI/ABMA 9-1990.

Copyright 2004, Industrial Press, Inc., New York, NY

8) *Groove radii*. If groove radii are smaller than those specified in the bearing types covered, the ability of a bearing to resist fatigue is not improved: however, it is diminished by the use of larger radii.

Ball Bearing Rating Life.— According to the Anti-Friction Bearing Manufacturers Association standards the Rating Life L_{10} of a group of apparently identical ball bearings is the life in millions of revolutions that 90 percent of the group will complete or exceed. For a single bearing, L_{10} also refers to the life associated with 90 percent reliability.

Radial and Angular Contact Ball Bearings: The magnitude of the Rating Life L_{10} in millions of revolutions, for a radial or angular contact ball bearing application is given by the formula:

$$L_{10} = \left(\frac{C}{P}\right)^3 \quad (1)$$

where C = basic load rating, newtons (pounds). See Formulas (2), (3a) and (3b)

P = equivalent radial load, newtons (pounds). See Formula (4)

Table 27. Values of f_c for Radial and Angular Contact Ball Bearings

$\frac{D\cos\alpha}{d_m}$	Single Row Radial Contact; Single and Double Row Angular Contact, Groove Type[a]		Double Row Radial Contact Groove Type		Self-Aligning	
	Values of f_c					
	Metric[b]	Inch[c]	Metric[b]	Inch[c]	Metric[b]	Inch[c]
0.05	46.7	3550	44.2	3360	17.3	1310
0.06	49.1	3730	46.5	3530	18.6	1420
0.07	51.1	3880	48.4	3680	19.9	1510
0.08	52.8	4020	50.0	3810	21.1	1600
0.09	54.3	4130	51.4	3900	22.3	1690
0.10	55.5	4220	52.6	4000	23.4	1770
0.12	57.5	4370	54.5	4140	25.6	1940
0.14	58.8	4470	55.7	4230	27.7	2100
0.16	59.6	4530	56.5	4290	29.7	2260
0.18	59.9	4550	56.8	4310	31.7	2410
0.20	59.9	4550	56.8	4310	33.5	2550
0.22	59.6	4530	56.5	4290	35.2	2680
0.24	59.0	4480	55.9	4250	36.8	2790
0.26	58.2	4420	55.1	4190	38.2	2910
0.28	57.1	4340	54.1	4110	39.4	3000
0.30	56.0	4250	53.0	4030	40.3	3060
0.32	54.6	4160	51.8	3950	40.9	3110
0.34	53.2	4050	50.4	3840	41.2	3130
0.36	51.7	3930	48.9	3730	41.3	3140
0.38	50.0	3800	47.4	3610	41.0	3110
0.40	48.4	3670	45.8	3480	40.4	3070

[a] A. When calculating the basic load rating for a unit consisting of two similar, single row, radial contact ball bearings, in a duplex mounting, the pair is considered as one, double row, radial contact ball bearing.
B. When calculating the basic load rating for a unit consisting of two, similar, single row, angular contact ball bearings in a duplex mounting, "face-to-face" or "back-to-back," the pair is considered as one, double row, angular contact ball bearing.
C. When calculating the basic load rating for a unit consisting of two or more similar, single angular contact ball bearings mounted "in tandem," properly manufactured and mounted for equal load distribution, the rating of the combination is the number of bearings to the 0.7 power times the rating of a single row ball bearing. If the unit may be treated as a number of individually interchangeable single row bearings, this footnote "C" does not apply.

[b] **Use to obtain C in newtons when D is given in mm.**

[c] Use to obtain C in pounds when D is given in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 28. Values of *X* and *Y* for Computing Equivalent Radial Load *P* of Radial and Angular Contact Ball Bearings

Contact Angle, α	Table Entering Factors[a]			Single Row Bearings[b]			Double Row Bearings			
				$\frac{F_a}{F_r} > e$		$\frac{F_a}{F_r} \le e$		$\frac{F_a}{F_r} > e$		
RADIAL CONTACT GROOVE BEARINGS										
		F_a/iZD^2								
	F_a/C_o	Metric Units	Inch Units	e	X	Y	X	Y	X	Y
	0.014	0.172	25	0.19		2.30				2.30
	0.028	0.345	50	0.22		1.99				1.99
	0.056	0.689	100	0.26		1.71				1.71
	0.084	1.03	150	0.28		1.56				1.55
0°	0.11	1.38	200	0.30	0.56	1.45	1	0	0.56	1.45
	0.17	2.07	300	0.34		1.31				1.31
	0.28	3.45	500	0.38		1.15				1.15
	0.42	5.17	750	0.42		1.04				1.04
	0.56	6.89	1000	0.44		1.00				1.00
ANGULAR CONTACT GROOVE BEARINGS										
		F_a/ZD^2								
	iF_a/C_o	Metric Units	Inch Units	e	X	Y	X	Y	X	Y
	0.014	0.172	25	0.23	For this type use the X, Y, and e values applicable to single row radial contact bearings			2.78	0.78	3.74
	0.028	0.345	50	0.26				2.40		3.23
	0.056	0.689	100	0.30				2.07		2.78
	0.085	1.03	150	0.34				1.87		2.52
5°	0.11	1.38	200	0.36			1	1.75		2.36
	0.17	2.07	300	0.40				1.58		2.13
	0.28	3.45	500	0.45				1.39		1.87
	0.42	5.17	750	0.50				1.26		1.69
	0.56	6.89	1000	0.52				1.21		1.63
	0.014	0.172	25	0.29		1.88		2.18		3.06
	0.029	0.345	50	0.32		1.71		1.98		2.78
	0.057	0.689	100	0.36		1.52		1.76		2.47
	0.086	1.03	150	0.38		1.41		1.63		2.20
10°	0.11	1.38	200	0.40	0.46	1.34	1	1.55	0.75	2.18
	0.17	2.07	300	0.44		1.23		1.42		2.00
	0.29	3.45	500	0.49		1.10		1.27		1.79
	0.43	5.17	750	0.54		1.01		1.17		1.64
	0.57	6.89	1000	0.54		1.00		1.16		1.63
	0.015	0.172	25	0.38		1.47		1.65		2.39
	0.029	0.345	50	0.40		1.40		1.57		2.28
	0.058	0.689	100	0.43		1.30		1.46		2.11
	0.087	1.03	150	0.46		1.23		1.38		2.00
15°	0.12	1.38	200	0.47	0.44	1.19	1	1.34	0.72	1.93
	0.17	2.07	300	0.50		1.12		1.26		1.82
	0.29	3.45	500	0.55		1.02		1.14		1.66
	0.44	5.17	750	0.56		1.00		1.12		1.63
	0.58	6.89	1000	0.56		1.00		1.12		1.63
20°	…	…	…	0.57	0.43	1.00	1	1.09	0.70	1.63
25°	…	…	…	0.68	0.41	0.87	1	0.92	0.67	1.41
30°	…	…	…	0.80	0.39	0.76	1	0.78	0.63	1.24
35°	…	…	…	0.95	0.37	0.66	1	0.66	0.60	1.07
40°	…	…	…	1.14	0.35	0.57	1	0.55	0.57	0.98
Self-aligning Ball Bearings				1.5 tan α	0.40	0.4 cot α	1	0.42 cot α	0.65	0.65 cot α

[a] Symbol definitions are given on the following page.

[b] For single row bearings when $F_a/F_r \le e$, use $X = 1$, $Y = 0$. Two similar, single row, angular contact ball bearings mounted face-to-face or back-to-back are considered as one double row, angular contact bearing.

Values of *X*, *Y*, and *e* for a load or contact angle other than shown are obtained by linear interpolation. Values of *X*, *Y*, and *e* do not apply to filling slot bearings for applications in which ball-raceway

Copyright 2004, Industrial Press, Inc., New York, NY

contact areas project substantially into the filling slot under load.Symbol Definitions: F_a is the applied axial load in newtons (pounds); C_o is the static load rating in newtons (pounds) of the bearing under consideration and is found by Formula (20); i is the number of rows of balls in the bearing; Z is the number of balls per row in a radial or angular contact bearing or the number of balls in a single row, single direction thrust bearing; D is the ball diameter in millimeters (inches); and F_r is the applied radial load in newtons (pounds).

For radial and angular contact ball bearings with balls not larger than 25.4 mm (1 inch) in diameter, C is found by the formula:

$$C = f_c(i\cos\alpha)^{0.7}Z^{2/3}D^{1.8} \tag{2}$$

and with balls larger than 25.4 mm (1 inch) in diameter C is found by the formula:

$$C = 3.647f_c(i\cos\alpha)^{0.7}Z^{2/3}D^{1.4} \quad \text{(metric)} \tag{3a}$$

$$C = f_c(i\cos\alpha)^{0.7}Z^{2/3}D^{1.4} \text{ (inch)} \tag{3b}$$

where f_c = a factor which depends on the geometry of the bearing components, the accuracy to which the various bearing parts are made and the material. Values of f_c, are given in Table 27
i = number of rows of balls in the bearing
α = nominal contact angle, degrees
Z = number of balls per row in a radial or angular contact bearing
D = ball diameter, mm (inches)

The magnitude of the equivalent radial load, P, in newtons (pounds) for radial and angular contact ball bearings, under combined constant radial and constant thrust loads is given by the formula:

$$P = XF_r + YF_a \tag{4}$$

where F_r = the applied radial load in newtons (pounds)
F_a = the applied axial load in newtons (pounds)
X = radial load factor as given in Table 30
Y = axial load factor as given in Table 30

Thrust Ball Bearings: The magnitude of the Rating Life L_{10} in millions of revolutions for a thrust ball bearing application is given by the formula:

$$L_{10} = \left(\frac{C_a}{P_a}\right)^3 \tag{5}$$

where C_a = the basic load rating, newtons (pounds). See Formulas (6) to (10)
P_a = equivalent thrust load, newtons (pounds). See Formula (11)

For single row, single and double direction, thrust ball bearing with balls not larger than 25.4 mm (1 inch) in diameter, C_a is found by the formulas:

$$\text{for } \alpha = 90 \text{ degrees}, \quad C_a = f_cZ^{2/3}D^{1.8} \tag{6}$$

$$\text{for } \alpha \neq 90 \text{ degrees}, \quad C_a = f_c(\cos\alpha)^{0.7}Z^{2/3}D^{1.8}\tan\alpha \tag{7}$$

and with balls larger than 25.4 mm (1 inch) in diameter, C_a is found by the formulas:

$$\text{for } \alpha = 90 \text{ degrees}, \quad C_a = 3.647f_cZ^{2/3}D^{1.4} \quad \text{(metric)} \tag{8a}$$

$$C_a = f_cZ^{2/3}D^{1.4} \quad \text{(inch)} \tag{8b}$$

$$\text{for } \alpha \neq 90 \text{ degrees}, \quad C_a = 3.647f_c(\cos\alpha)^{0.7}Z^{2/3}D^{1.4}\tan\alpha \quad \text{(metric)} \tag{9a}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$C_a = f_c(\cos\alpha)^{0.7} Z^{2/3} D^{1.4} \tan\alpha \quad \text{(inch)} \tag{9b}$$

where f_c = a factor which depends on the geometry of the bearing components, the accuracy to which the various bearing parts are made, and the material. Values of f_c are given in Table 29

Z = number of balls per row in a single row, single direction thrust ball bearing

D = ball diameter, mm (inches)

α = nominal contact angle, degrees

Table 29. Values of f_c for Thrust Ball Bearings

$\frac{D}{d_m}$	α = 90°		$D\cos\alpha$	α = 45°		α = 60°		α = 75°	
	Metric[a]	Inch[b]		Metric[a]	Inch[b]	Metric[a]	Inch[b]	Metric[a]	Inch[b]
0.01	36.7	2790	0.01	42.1	3200	39.2	2970	37.3	2840
0.02	45.2	3430	0.02	51.7	3930	48.1	3650	45.9	3490
0.03	51.1	3880	0.03	58.2	4430	54.2	4120	51.7	3930
0.04	55.7	4230	0.04	63.3	4810	58.9	4470	56.1	4260
0.05	59.5	4520	0.05	67.3	5110	62.6	4760	59.7	4540
0.06	62.9	4780	0.06	70.7	5360	65.8	4990	62.7	4760
0.07	65.8	5000	0.07	73.5	5580	68.4	5190	65.2	4950
0.08	68.5	5210	0.08	75.9	5770	70.7	5360	67.3	5120
0.09	71.0	5390	0.09	78.0	5920	72.6	5510	69.2	5250
0.10	73.3	5570	0.10	79.7	6050	74.2	5630	70.7	5370
0.12	77.4	5880	0.12	82.3	6260	76.6	5830	…	…
0.14	81.1	6160	0.14	84.1	6390	78.3	5950	…	…
0.16	84.4	6410	0.16	85.1	6470	79.2	6020	…	…
0.18	87.4	6640	0.18	85.5	6500	79.6	6050	…	…
0.20	90.2	6854	0.20	85.4	6490	79.5	6040	…	…
0.22	92.8	7060	0.22	84.9	6450	…	…	…	…
0.24	95.3	7240	0.24	84.0	6380	…	…	…	…
0.26	97.6	7410	0.26	82.8	6290	…	…	…	…
0.28	99.8	7600	0.28	81.3	6180	…	…	…	…
0.30	101.9	7750	0.30	79.6	6040	…	…	…	…
0.32	103.9	7900	…	…	…	…	…	…	…
0.34	105.8	8050	…	…	…	…	…	…	…

[a] **Use to obtain C_a in newtons when D is given in mm.**

[b] Use to obtain C_a in pounds when D is given in inches.

For thrust ball bearings with two or more rows of similar balls carrying loads in the same direction, the basic load rating, C_a, in newtons (pounds) is found by the formula:

$$C_a = (Z_1 + Z_2 + \ldots Z_n)\left[\left(\frac{Z_1}{C_{a1}}\right)^{10/3} + \left(\frac{Z_2}{C_{a2}}\right)^{10/3} + \ldots\left(\frac{Z_n}{C_{an}}\right)^{10/3}\right]^{-0.3} \tag{10}$$

where $Z_1, Z_2 \ldots Z_n$ = number of balls in respective rows of a single-direction multi-row thrust ball bearing

$C_{a1}, C_{a2} \ldots C_{an}$ = basic load rating per row of a single-direction, multi-row thrust ball bearing, each calculated as a single-row bearing with $Z_1, Z_2 \ldots Z_n$ balls, respectively

The magnitude of the equivalent thrust load, P_a, in newtons (pounds) for thrust ball bearings with $\alpha \neq 90$ degrees under combined constant thrust and constant radial loads is found by the formula:

$$P_a = XF_r + YF_a \tag{11}$$

where F_r = the applied radial load in newtons (pounds)

F_a = the applied axial load in newtons (pounds)

X = radial load factor as given in Table 30

Y = axial load factor as given in Table 30

Copyright 2004, Industrial Press, Inc., New York, NY

Table 30. Values of *X* and *Y* for Computing Equivalent Thrust Load P_a for Thrust Ball Bearings

Contact Angle α	e	Single Direction Bearings		Double Direction Bearings			
		$\frac{F_a}{F_r} > e$		$\frac{F_a}{F_r} \le e$		$\frac{F_a}{F_r} > e$	
		X	Y	X	Y	X	Y
45°	1.25	0.66	1	1.18	0.59	0.66	1
60°	2.17	0.92	1	1.90	0.54	0.92	1
75°	4.67	1.66	1	3.89	0.52	1.66	1

For $\alpha = 90°$, $F_r = 0$ and $Y = 1$.

Roller Bearing Types Covered.— This standard* applies to *cylindrical, tapered and self-aligning radial and thrust roller bearings* and to *needle roller bearings*. These bearings are presumed to be within the size ranges shown in the AFBMA dimensional standards, of good quality and produced in accordance with good manufacturing practice.

Roller bearings vary considerably in design and execution. Since small differences in relative shape of contacting surfaces may account for distinct differences in load carrying ability, this standard does not attempt to cover all design variations, rather it applies to basic roller bearing designs.

The following limitations apply:

1) *Truncated contact area*. This standard may not be safely applied to roller bearings subjected to application conditions which cause the contact area of the roller with the raceway to be severely truncated by the edge of the raceway or roller.

2) *Stress concentrations*. A cylindrical, tapered or self-aligning roller bearing must be expected to have a basic load rating less than that obtained using a value of f_c taken from Table 31 or 32 if, under load, a stress concentration is present in some part of the roller-raceway contact. Such stress concentrations occur in the center of nominal point contacts, at the contact extremities for line contacts and at inadequately blended junctions of a rolling surface profile. Stress concentrations can also occur if the rollers are not accurately guided such as in bearings without cages and bearings not having rigid integral flanges. Values of f_c given in Tables 31 and 32 are based upon bearings manufactured to achieve optimized contact. For no bearing type or execution will the factor f_c be greater than that obtained in Tables 31 and 32.

3) *Material*. This standard applies only to roller bearings fabricated from hardened, good quality steel.

4) *Lubrication*. Rating Life calculated according to this standard is based on the assumption that the bearing is adequately lubricated. Determination of adequate lubrication depends upon the bearing application.

5) *Ring support and alignment*. Rating Life calculated according to this standard assumes that the bearing inner and outer rings are rigidly supported, and that the inner and outer ring axes are properly aligned.

6) *Internal clearance*. Radial roller bearing Rating Life calculated according to this standard is based on the assumption that only a nominal internal clearance occurs in the mounted bearing at operating speed, load, and temperature.

7) *High speed effects*. The Rating Life calculated according to this standard does not account for high speed effects such as roller centrifugal forces and gyroscopic moments: These effects tend to diminish fatigue life. Analytical evaluation of these effects frequently requires the use of high speed digital computation devices and hence, cannot be included.

* All references to "standard" are to AFBMA and American National Standard "Load Ratings and Fatigue Life for Roller Bearings" ANSI/AFBMA Std 11–1990.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 31. Values of f_c for Radial Roller Bearings

$\frac{D\cos\alpha}{d_m}$	f_c		$\frac{D\cos\alpha}{d_m}$	f_c		$\frac{D\cos\alpha}{d_m}$	f_c	
	Metric[a]	Inch[b]		Metric[a]	Inch[b]		Metric[a]	Inch[b]
0.01	52.1	4680	0.18	88.8	7980	0.35	79.5	7140
0.02	60.8	5460	0.19	88.8	7980	0.36	78.6	7060
0.03	66.5	5970	0.20	88.7	7970	0.37	77.6	6970
0.04	70.7	6350	0.21	88.5	7950	0.38	76.7	6890
0.05	74.1	6660	0.22	88.2	7920	0.39	75.7	6800
0.06	76.9	6910	0.23	87.9	7890	0.40	74.6	6700
0.07	79.2	7120	0.24	87.5	7850	0.41	73.6	6610
0.08	81.2	7290	0.25	87.0	7810	0.42	72.5	6510
0.09	82.8	7440	0.26	86.4	7760	0.43	71.4	6420
0.10	84.2	7570	0.27	85.8	7710	0.44	70.3	6320
0.11	85.4	7670	0.28	85.2	7650	0.45	69.2	6220
0.12	86.4	7760	0.29	84.5	7590	0.46	68.1	6120
0.13	87.1	7830	0.30	83.8	7520	0.47	67.0	6010
0.14	87.7	7880	0.31	83.0	7450	0.48	65.8	5910
0.15	88.2	7920	0.32	82.2	7380	0.49	64.6	5810
0.16	88.5	7950	0.33	81.3	7300	0.50	63.5	5700
0.17	88.7	7970	0.34	80.4	7230	…	…	…

[a] For $\alpha = 0°, F_a = 0$ and $X = 1$.

[b] Use to obtain C in pounds when l_{eff} and D are given in inches.

Table 32. Values of f_c for Thrust Roller Bearings

$\frac{D\cos\alpha}{d_m}$	45° < α < 60°		60° < α < 75°		75° ≤ α < 90°		$\frac{D}{d_m}$	α = 90°	
	f_c							f_c	
	Metric[a]	Inch[b]	Metric[a]	Inch[b]	Metric[a]	Inch[b]		Metric[a]	Inch[b]
0.01	109.7	9840	107.1	9610	105.6	9470	0.01	105.4	9500
0.02	127.8	11460	124.7	11180	123.0	11030	0.02	122.9	11000
0.03	139.5	12510	136.2	12220	134.3	12050	0.03	134.5	12100
0.04	148.3	13300	144.7	12980	142.8	12810	0.04	143.4	12800
0.05	155.2	13920	151.5	13590	149.4	13400	0.05	150.7	13200
0.06	160.9	14430	157.0	14080	154.9	13890	0.06	156.9	14100
0.07	165.6	14850	161.6	14490	159.4	14300	0.07	162.4	14500
0.08	169.5	15200	165.5	14840	163.2	14640	0.08	167.2	15100
0.09	172.8	15500	168.7	15130	166.4	14930	0.09	171.7	15400
0.10	175.5	15740	171.4	15370	169.0	15160	0.10	175.7	15900
0.12	179.7	16120	175.4	15730	173.0	15520	0.12	183.0	16300
0.14	182.3	16350	177.9	15960	175.5	15740	0.14	189.4	17000
0.16	183.7	16480	179.3	16080	…	…	0.16	195.1	17500
0.18	184.1	16510	179.7	16120	…	…	0.18	200.3	18000
0.20	183.7	16480	179.3	16080	…	…	0.20	205.0	18500
0.22	182.6	16380	…	…	…	…	0.22	209.4	18800
0.24	180.9	16230	…	…	…	…	0.24	213.5	19100
0.26	178.7	16030	…	…	…	…	0.26	217.3	19600
0.28	…	…	…	…	…	…	0.28	220.9	19900
0.30	…	…	…	…	…	…	0.30	224.3	20100

[a] Use to obtain C_a in newtons when l_{eff} and D are given in mm.

[b] Use to obtain C_a in pounds when l_{eff} and D are given in inches.

Roller Bearing Rating Life.— The Rating Life L_{10} of a group of apparently identical roller bearings is the life in millions of revolutions that 90 percent of the group will complete or exceed. For a single bearing, L_{10} also refers to the life associated with 90 percent reliability.

Copyright 2004, Industrial Press, Inc., New York, NY

Radial Roller Bearings: The magnitude of the Rating Life, L_{10}, in millions of revolutions, for a radial roller bearing application is given by the formula:

$$L_{10} = \left(\frac{C}{P}\right)^{10/3} \tag{12}$$

where C = the basic load rating in newtons (pounds), see Formula (13); and, P = equivalent radial load in newtons (pounds), see Formula (14).

For radial roller bearings, C is found by the formula:

$$C = f_c(il_{eff}\cos\alpha)^{7/9}Z^{3/4}D^{29/27} \tag{13}$$

where f_c = a factor which depends on the geometry of the bearing components, the accuracy to which the various bearing parts are made, and the material. Maximum values of f_c are given in Table 31

i = number of rows of rollers in the bearing

l_{eff} = effective length, mm (inches) α = nominal contact angle, degrees

Z = number of rollers per row in a radial roller bearing

D = roller diameter, mm (inches) (mean diameter for a tapered roller, major diameter for a spherical roller)

When rollers are longer than $2.5D$, a reduction in the f_c value must be anticipated. In this case, the bearing manufacturer may be expected to establish load ratings accordingly.

In applications where rollers operate directly on a shaft surface or a housing surface, such a surface must be equivalent in all respects to the raceway it replaces to achieve the basic load rating of the bearing.

When calculating the basic load rating for a unit consisting of two or more similar single-row bearings mounted "in tandem," properly manufactured and mounted for equal load distribution, the rating of the combination is the number of bearings to the 7/9 power times the rating of a single-row bearing. If, for some technical reason, the unit may be treated as a number of individually interchangeable single-row bearings, this consideration does not apply.

The magnitude of the equivalent radial load, P, in newtons (pounds), for radial roller bearings, under combined constant radial and constant thrust loads is given by the formula:

$$P = XF_r + YF_a \tag{14}$$

where F_r = the applied radial load in newtons (pounds)

F_a = the applied axial load in newtons (pounds)

X = radial load factor as given in Table 33

Y = axial load factor as given in Table 33

Table 33. Values of *X* and *Y* for Computing Equivalent Radial Load *P* for Radial Roller Bearing

Bearing Type	$\frac{F_a}{F_r} \le e$		$\frac{F_a}{F_r} > e$	
	X	*Y*	*X*	*Y*
Self-Aligning and Tapered Roller Bearings[a] $\alpha \neq 0°$	Single Row Bearings			
	1	0	0.4	0.4 cot α
	Double Row Bearings[a]			
	1	0.45 cot α	0.67	0.67 cot α

[a] For $\alpha = 0°$, $F_a = 0$ and $X = 1$.

$e = 1.5 \tan\alpha$

Copyright 2004, Industrial Press, Inc., New York, NY

Typical Bearing Life for Various Design Applications

Uses	Design life in hours	Uses	Design life in hours
Agricultural equipment	3000 – 6000	Gearing units	
Aircraft equipment	500 – 2000	Automotive	600 – 5000
Automotive		Multipurpose	8000 – 15000
Race car	500 – 800	Machine tools	20000
Light motor cycle	600 – 1200	Rail Vehicles	15000 – 25000
Heavy motor cycle	1000 – 2000	Heavy rolling mill	> 50000
Light cars	1000 – 2000	Machines	
Heavy cars	1500 – 2500	Beater mills	20000 – 30000
Light trucks	1500 – 2500	Briquette presses	20000 – 30000
Heavy trucks	2000 – 2500	Grinding spindles	1000 – 2000
Buses	2000 – 5000	Machine tools	10000 – 30000
Electrical		Mining machinery	4000 – 15000
Household appliances	1000 – 2000	Paper machines	50000 – 80000
Motors ≤ ½ hp	1000 – 2000	Rolling mills	
Motors ≤ 3 hp	8000 – 10000	Small cold mills	5000 – 6000
Motors, medium	10000 – 15000	Large multipurpose mills	8000 – 10000
Motors, large	20000 – 30000	Rail vehicle axle	
Elevator cables sheaves	40000 – 60000	Mining cars	5000
Mine ventillation fans	40000 – 50000	Motor rail cars	16000 – 20000
Propeller thrust bearings	15000 – 25000	Open–pit mining cars	20000 – 25000
Propeller shaft bearings	> 80000	Streetcars	20000 – 25000
Gear drives		Passenger cars	26000
Boat gearing units	3000 – 5000	Freight cars	35000
Gear drives	> 50000	Locomotive outer bearings	20000 – 25000
Ship gear drives	20000 – 30000	Locomotive inner bearings	30000 – 40000
Machinery for 8 hour service which are not always fully utilized	14000 – 20000	Machinery for short or intermittent opearation where service interruption is of minor importance	4000 – 8000
Machinery for 8 hour service which are fully utilized	20000 – 30000	Machinery for intermittent service where reliable opearation is of great importance	8000 – 14000
Machinery for continuous 24 hour service	50000 – 60000	Instruments and apparatus in frequent use	0 – 500

Roller bearings are generally designed to achieve optimized contact; however, they usually support loads other than the loading at which optimized contact is maintained. The 10/3 exponent in Rating Life Formulas (12) and (15) was selected to yield satisfactory Rating Life estimates for a broad spectrum from light to heavy loading. When loading exceeds that which develops optimized contact, e.g., loading greater than $C/4$ to $C/2$ or $C_a/4$ to $C_a/2$, the user should consult the bearing manufacturer to establish the adequacy of the Rating Life formulas for the particular application.

Thrust Roller Bearings: The magnitude of the Rating Life, L_{10}, in millions of revolutions for a thrust roller bearing application is given by the formula:

$$L_{10} = \left(\frac{C_a}{P_a}\right)^{10/3} \tag{15}$$

where C_a = basic load rating, newtons (pounds). See Formulas (16) to (18)

P_a = equivalent thrust load, newtons (pounds). See Formula (19)

For single row, single and double direction, thrust roller bearings, the magnitude of the basic load rating, C_a, in newtons (pounds), is found by the formulas:

$$\text{for } \alpha = 90^\circ,\ C_a = f_c l_{eff}^{7/9} Z^{3/4} D^{29/27} \tag{16}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{for } \alpha \neq 90^\circ,\ C_a = f_c(l_{eff}\cos\alpha)^{7/9}Z^{3/4}D^{29/27}\tan\alpha \tag{17}$$

where f_c = a factor which depends on the geometry of the bearing components, the accuracy to which the various parts are made, and the material. Values of f_c are given in Table 32

l_{eff} = effective length, mm (inches)

Z = number of rollers in a single row, single direction, thrust roller bearing

D = roller diameter, mm (inches) (mean diameter for a tapered roller, major diameter for a spherical roller)

α = nominal contact angle, degrees

For thrust roller bearings with two or more rows of rollers carrying loads in the same direction the magnitude of C_a is found by the formula:

$$C_a = (Z_1 l_{eff1} + Z_2 l_{eff2} \ldots Z_n l_{effn})\left\{\left[\frac{Z_1 l_{eff1}}{C_{a1}}\right]^{9/2} + \left[\frac{Z_2 l_{eff2}}{C_{a2}}\right]^{9/2} + \ldots \left[\frac{Z_n l_{effn}}{C_{an}}\right]^{9/2}\right\}^{-2/9} \tag{18}$$

Where $Z_1, Z_2 \ldots . Z_n$ = the number of rollers in respective rows of a single direction, multi-row bearing

$C_{a1}, C_{a2} \ldots . C_{an}$ = the basic load rating per row of a single direction, multi-row, thrust roller bearing, each calculated as a single row bearing with $Z_1, Z_2 \ldots Z_n$ rollers respectively

$l_{eff1} l_{eff2} \ldots l_{effn}$ = effective length, mm (inches), or rollers in the respective rows

In applications where rollers operate directly on a surface supplied by the user, such a surface must be equivalent in all respects to the washer raceway it replaces to achieve the basic load rating of the bearing.

In case the bearing is so designed that several rollers are located on a common axis, these rollers are considered as one roller of a length equal to the total effective length of contact of the several rollers. Rollers as defined above, or portions thereof which contact the same washer-raceway area, belong to one row.

When the ratio of the individual roller effective length to the pitch diameter (at which this roller operates) is too large, a reduction of the f_c value must be anticipated due to excessive slip in the roller-raceway contact.

When calculating the basic load rating for a unit consisting of two or more similar single row bearings mounted "in tandem," properly manufactured and mounted for equal load distribution, the rating of the combination is defined by Formula (18). If, for some technical reason, the unit may be treated as a number of individually interchangeable single-row bearings, this consideration does not apply.

The magnitude of the equivalent thrust load, P_a, in pounds, for thrust roller bearings with α not equal to 90 degrees under combined constant thrust and constant radial loads is given by the formula:

$$P_a = XF_r + YF_a \tag{19}$$

where F_r = applied radial load, newtons (pounds)

F_a = applied axial load, newtons (pounds)

X = radial load factor as given in Table 34

Y = axial load factor as given in Table 34

Copyright 2004, Industrial Press, Inc., New York, NY

Table 34. Values of *X* and *Y* for Computing Equivalent Thrust Load P_a for Thrust Roller Bearings

Bearing Type	Single Direction Bearings		Double Direction Bearings			
	$\frac{F_a}{F_r} > e$		$\frac{F_a}{F_r} \le e$		$\frac{F_a}{F_r} > e$	
	X	Y	X	Y	X	Y
Self-Aligning Tapered Thrust Roller Bearings[a] $\alpha \neq 0$	$\tan\alpha$	1	$1.5\tan\alpha$	0.67	$\tan\alpha$	1

[a] For $\alpha = 90°$, $F_r = 0$ and $Y = 1$.

$e = 1.5\tan\alpha$

Life Adjustment Factors.— In certain applications of ball or roller bearings it is desirable to specify life for a reliability other than 90 per cent. In other cases the bearings may be fabricated from special bearing steels such as vacuum-degassed and vacuum-melted steels, and improved processing techniques. Finally, application conditions may indicate other than normal lubrication, load distribution, or temperature. For such conditions a series of life adjustment factors may be applied to the fatigue life formula. This is fully explained in AFBMA and American National Standard "Load Ratings and Fatigue Life for Ball Bearings"ANSI/AFBMA Std 9–1990 and AFBMA and American National Standard "Load Ratings and Fatigue Life for Roller Bearings"ANSI/AFBMA Std 11–1990. In addition to consulting these standards it may be advantageous to also obtain information from the bearing manufacturer.

Life Adjustment Factor for Reliability: For certain applications, it is desirable to specify life for a reliability greater than 90 per cent which is the basis of the Rating Life.

To determine the bearing life of ball or roller bearings for reliability greater than 90 per cent, the Rating Life must be adjusted by a factor a_1 such that $L_n = a_1 L_{10}$. For a reliability of 95 per cent, designated as L_5, the life adjustment factor a_1 is 0.62; for 96 per cent, L_4, a_1 is 0.53; for 97 per cent, L_3, a_1 is 0.44; for 98 per cent, L_2, a_1 is 0.33; and for 99 per cent, L_1, a_1 is 0.21.

Life Adjustment Factor for Material: For certain types of ball or roller bearings which incorporate improved materials and processing, the Rating Life can be adjusted by a factor a_2 such that $L_{10}' = a_2 L_{10}$. Factor a_2 depends upon steel analysis, metallurgical processes, forming methods, heat treatment, and manufacturing methods in general. Ball and roller bearings fabricated from consumable vacuum remelted steels and certain other special analysis steels, have demonstrated extraordinarily long endurance. These steels are of exceptionally high quality, and bearings fabricated from these are usually considered special manufacture. Generally, a_2 values for such steels can be obtained from the bearing manufacturer. However, all of the specified limitations and qualifications for the application of the Rating Life formulas still apply.

Life Adjustment Factor for Application Condition: Application conditions which affect ball or roller bearing life include: 1) lubrication; 2) load distribution (including effects of clearance, misalignment, housing and shaft stiffness, type of loading, and thermal gradients); and 3) temperature.

Items 2 and 3 require special analytical and experimental techniques, therefore the user should consult the bearing manufacturer for evaluations and recommendations.

Operating conditions where the factor a_3 might be less than 1 include: a) exceptionally low values of Nd_m (rpm times pitch diameter, in mm); e.g., $Nd_m < 10{,}000$; b) lubricant viscosity at less than 70 SSU for ball bearings and 100 SSU for roller bearings at operating temperature; and c) excessively high operating temperatures.

Copyright 2004, Industrial Press, Inc., New York, NY

When a_3 is less than 1 it may not be assumed that the deficiency in lubrication can be overcome by using an improved steel. When this factor is applied, $L_{10}' = a_3 L_{10}$.

In most ball and roller bearing applications, lubrication is required to separate the rolling surfaces, i.e., rollers and raceways, to reduce the retainer-roller and retainer-land friction and sometimes to act as a coolant to remove heat generated by the bearing.

Factor Combinations: A fatigue life formula embodying the foregoing life adjustment factors is $L_{10}' = a_1 a_2 a_3 L_{10}$. Indiscriminate application of the life adjustment factors in this formula may lead to serious overestimation of bearing endurance, since fatigue life is only one criterion for bearing selection. Care must be exercised to select bearings which are of sufficient size for the application.

Ball Bearing Static Load Rating.— For ball bearings suitably manufactured from hardened alloy steels, the static radial load rating is that uniformly distributed static radial bearing load which produces a maximum contact stress of 4,000 megapascals (580,000 pounds per square inch). In the case of a single row, angular contact ball bearing, the static radial load rating refers to the radial component of that load which causes a purely radial displacement of the bearing rings in relation to each other. The static axial load rating is that uniformly distributed static centric axial load which produces a maximum contact stress of 4,000 megapascals (580,000 pounds per square inch).

Radial and Angular Contact Groove Ball Bearings: The magnitude of the static load rating C_o in newtons (pounds) for radial ball bearings is found by the formula:

$$C_o = f_o i Z D^2 \cos\alpha \tag{20}$$

where f_o = a factor for different kinds of ball bearings given in Table 35
i = number of rows of balls in bearing
Z = number of balls per row
D = ball diameter, mm (inches)
α = nominal contact angle, degrees

This formula applies to bearings with a cross sectional raceway groove radius not larger than 0.52 D in radial and angular contact groove ball bearing inner rings and 0.53 D in radial and angular contact groove ball bearing outer rings and self-aligning ball bearing inner rings.

The load carrying ability of a ball bearing is not necessarily increased by the use of a smaller groove radius but is reduced by the use of a larger radius than those indicated above.

Radial or Angular Contact Ball Bearing Combinations: The basic static load rating for two similar single row radial or angular contact ball bearings mounted side by side on the same shaft such that they operate as a unit (duplex mounting) in "back-to-back" or "face-to-face" arrangement is two times the rating of one single row bearing.

The basic static radial load rating for two or more single row radial or angular contact ball bearings mounted side by side on the same shaft such that they operate as a unit (duplex or stack mounting) in "tandem" arrangement, properly manufactured and mounted for equal load distribution, is the number of bearings times the rating of one single row bearing.

Thrust Ball Bearings: The magnitude of the static load rating C_{oa} for thrust ball bearings is found by the formula:

$$C_{oa} = f_o Z D^2 \cos\alpha \tag{21}$$

where f_o = a factor given in Table 35
Z = number of balls carrying the load in one direction
D = ball diameter, mm (inches)
α = nominal contact angle, degrees

Copyright 2004, Industrial Press, Inc., New York, NY

This formula applies to thrust ball bearings with a cross sectional raceway radius not larger than 0.54 D. The load carrying ability of a bearing is not necessarily increased by use of a smaller radius, but is reduced by use of a larger radius.

Roller Bearing Static Load Rating: For roller bearings suitably manufactured from hardened alloy steels, the static radial load rating is that uniformly distributed static radial bearing load which produces a maximum contact stress of 4,000 megapascals (580,000 pounds per square inch) acting at the center of contact of the most heavily loaded rolling element. The static axial load rating is that uniformly distributed static centric axial load which produces a maximum contact stress of 4,000 megapascals (580,000 pounds per square inch) acting at the center of contact of each rolling element.

Table 35. f_o for Calculating Static Load Rating for Ball Bearings

$\frac{D\cos\alpha}{d_m}$	Radial and Angular Contact Groove Type		Radial Self-Aligning		Thrust	
	Metric[a]	Inch[b]	Metric[a]	Inch[b]	Metric[a]	Inch[b]
0.00	12.7	1850	1.3	187	51.9	7730
0.01	13.0	1880	1.3	191	52.6	7620
0.02	13.2	1920	1.3	195	51.7	7500
0.03	13.5	1960	1.4	198	50.9	7380
0.04	13.7	1990	1.4	202	50.2	7280
0.05	14.0	2030	1.4	206	49.6	7190
0.06	14.3	2070	1.5	210	48.9	7090
0.07	14.5	2100	1.5	214	48.3	7000
0.08	14.7	2140	1.5	218	47.6	6900
0.09	14.5	2110	1.5	222	46.9	6800
0.10	14.3	2080	1.6	226	46.4	6730
0.11	14.1	2050	1.6	231	45.9	6660
0.12	13.9	2020	1.6	235	45.5	6590
0.13	13.6	1980	1.7	239	44.7	6480
0.14	13.4	1950	1.7	243	44.0	6380
0.15	13.2	1920	1.7	247	43.3	6280
0.16	13.0	1890	1.7	252	42.6	6180
0.17	12.7	1850	1.8	256	41.9	6070
0.18	12.5	1820	1.8	261	41.2	5970
0.19	12.3	1790	1.8	265	40.4	5860
0.20	12.1	1760	1.9	269	39.7	5760
0.21	11.9	1730	1.9	274	39.0	5650
0.22	11.6	1690	1.9	278	38.3	5550
0.23	11.4	1660	2.0	283	37.5	5440
0.24	11.2	1630	2.0	288	37.0	5360
0.25	11.0	1600	2.0	293	36.4	5280
0.26	10.8	1570	2.1	297	35.8	5190
0.27	10.6	1540	2.1	302	35.0	5080
0.28	10.4	1510	2.1	307	34.4	4980
0.29	10.3	1490	2.1	311	33.7	4890
0.30	10.1	1460	2.2	316	33.2	4810
0.31	9.9	1440	2.2	321	32.7	4740
0.32	9.7	1410	2.3	326	32.0	4640
0.33	9.5	1380	2.3	331	31.2	4530
0.34	9.3	1350	2.3	336	30.5	4420
0.35	9.1	1320	2.4	341	30.0	4350
0.36	8.9	1290	2.4	346	29.5	4270
0.37	8.7	1260	2.4	351	28.8	4170
0.38	8.5	1240	2.5	356	28.0	4060
0.39	8.3	1210	2.5	361	27.2	3950
0.40	8.1	1180	2.5	367	26.8	3880
0.41	8.0	1160	2.6	372	26.2	3800
0.42	7.8	1130	2.6	377	25.7	3720
0.43	7.6	1100	2.6	383	25.1	3640
0.44	7.4	1080	2.7	388	24.6	3560
0.45	7.2	1050	2.7	393	24.0	3480

Copyright 2004, Industrial Press, Inc., New York, NY

Table 35. ***(Continued)*** f_o **for Calculating Static Load Rating for Ball Bearings**

$\frac{D\cos\alpha}{d_m}$	Radial and Angular Contact Groove Type		Radial Self-Aligning		Thrust	
	Metric[a]	Inch[b]	Metric[a]	Inch[b]	Metric[a]	Inch[b]
0.46	7.1	1030	2.8	399	23.5	3400
0.47	6.9	1000	2.8	404	22.9	3320
0.48	6.7	977	2.8	410	22.4	3240
0.49	6.6	952	2.9	415	21.8	3160
0.50	6.4	927	2.9	421	21.2	3080

[a] **Use to obtain C_o or C_{oa} in newtons when D is given in mm.**

[b] Use to obtain C_o or C_{oa} in pounds when D is given in inches.

Note: Based on modulus of elasticity = 2.07×10^5 megapascals (30×10^6 pounds per square inch) and Poisson's ratio = 0.3.

Radial Roller Bearings: The magnitude of the static load rating C_o in newtons (pounds) for radial roller bearings is found by the formulas:

$$C_o = 44\left(1 - \frac{D\cos\alpha}{d_m}\right) iZl_{eff}D\cos\alpha \qquad \text{(metric)} \tag{22a}$$

$$C_o = 6430\left(1 - \frac{D\cos\alpha}{d_m}\right) iZl_{eff}D\cos\alpha \qquad \text{(inch)} \tag{22b}$$

where D = roller diameter, mm (inches); mean diameter for a tapered roller and major diameter for a spherical roller

d_m = mean pitch diameter of the roller complement, mm (inches)

i = number of rows of rollers in bearing

Z = number of rollers per row

l_{eff} = effective length, mm (inches); overall roller length minus roller chamfers or minus grinding undercuts at the ring where contact is shortest

α = nominal contact angle, degrees

Radial Roller Bearing Combinations: The static load rating for two similar single row roller bearings mounted side by side on the same shaft such that they operate as a unit is two times the rating of one single row bearing.

The static radial load rating for two or more similar single row roller bearings mounted side by side on the same shaft such that they operate as a unit (duplex or stack mounting) in "tandem" arrangement, properly manufactured and mounted for equal load distribution, is the number of bearings times the rating of one single row bearing.

Thrust Roller Bearings: The magnitude of the static load rating C_{oa} in newtons (pounds) for thrust roller bearings is found by the formulas:

$$C_{oa} = 220\left(1 - \frac{D\cos\alpha}{d_m}\right) Zl_{eff}D\sin\alpha \qquad \text{(metric)} \tag{23a}$$

$$C_{oa} = 32150\left(1 - \frac{D\cos\alpha}{d_m}\right) Zl_{eff}D\sin\alpha \qquad \text{(inch)} \tag{23b}$$

where the symbol definitions are the same as for Formulas (22a) and (22b).

Thrust Roller Bearing Combination: The static axial load rating for two or more similar single direction thrust roller bearings mounted side by side on the same shaft such that they operate as a unit (duplex or stack mounting) in "tandem" arrangement, properly manufactured and mounted for equal load distribution, is the number of bearings times the rating of one single direction bearing. The accuracy of this formula decreases in the case of single direction bearings when $F_r > 0.44\, F_a \cot\alpha$ where F_r is the applied radial load in newtons (pounds) and F_a is the applied axial load in newtons (pounds).

Copyright 2004, Industrial Press, Inc., New York, NY

Ball Bearing Static Equivalent Load.— For ball bearings the static equivalent radial load is that calculated static radial load which produces a maximum contact stress equal in magnitude to the maximum contact stress in the actual condition of loading. The static equivalent axial load is that calculated static centric axial load which produces a maximum contact stress equal in magnitude to the maximum contact stress in the actual condition of loading.

Radial and Angular Contact Ball Bearings: The magnitude of the static equivalent radial load P_o in newtons (pounds) for radial and angular contact ball bearings under combined thrust and radial loads is the greater of:

$$P_o = X_o F_r + Y_o F_a \tag{24}$$

$$P_o = F_r \tag{25}$$

where X_o = radial load factor given in Table 36
Y_o = axial load factor given in Table 36
F_r = applied radial load, newtons (pounds)
F_a = applied axial load, newtons (pounds)

Table 36. Values of X_o and Y_o for Computing Static Equivalent Radial Load P_o of Ball Bearings

Contact Angle	Single Row Bearings[a]		Double Row Bearings	
	X_o	Y_o[b]	X_o	Y_o[b]
RADIAL CONTACT GROOVE BEARINGS[c,a]				
$\alpha = 0°$	0.6	0.5	0.6	0.5
ANGULAR CONTACT GROOVE BEARINGS				
$\alpha = 15°$	0.5	0.47	1	0.94
$\alpha = 20°$	0.5	0.42	1	0.84
$\alpha = 25°$	0.5	0.38	1	0.76
$\alpha = 30°$	0.5	0.33	1	0.66
$\alpha = 35°$	0.5	0.29	1	0.58
$\alpha = 40°$	0.5	0.26	1	0.52
SELF-ALIGNING BEARINGS				
…	0.5	0.22 cot α	1	0.44 cot α

[a] P_o is always $\geq F_r$.

[b] Values of Y_o for intermediate contact angles are obtained by linear interpolation.

[c] Permissible maximum value of F_a/C_o (where F_a is applied axial load and C_o is static radial load rating) depends on the bearing design (groove depth and internal clearance).

Thrust Ball Bearings: The magnitude of the static equivalent axial load P_{oa} in newtons (pounds) for thrust ball bearings with contact angle $\alpha \neq 90°$ under combined radial and thrust loads is found by the formula:

$$P_{oa} = F_a + 2.3 F_r \tan\alpha \tag{26}$$

where the symbol definitions are the same as for Formulas (24) and (25). This formula is valid for all load directions in the case of double direction ball bearings. For single direction ball bearings, it is valid where $F_r/F_a \leq 0.44 \cot\alpha$ and gives a satisfactory but less conservative value of P_{oa} for F_r/F_a up to $0.67 \cot\alpha$.

Thrust ball bearings with $\alpha = 90°$ can support axial loads only. The static equivalent load for this type of bearing is $P_{oa} = F_a$.

Roller Bearing Static Equivalent Load.— The static equivalent radial load for roller bearings is that calculated, static radial load which produces a maximum contact stress acting at the center of contact of a uniformly loaded rolling element equal in magnitude to the maximum contact stress in the actual condition of loading. The static equivalent axial load is that calculated, static centric axial load which produces a maximum contact stress acting

Copyright 2004, Industrial Press, Inc., New York, NY

at the center of contact of a uniformly loaded rolling element equal in magnitude to the maximum contact stress in the actual condition of loading.

Radial Roller Bearings: The magnitude of the static equivalent radial load P_o in newtons (pounds) for radial roller bearings under combined radial and thrust loads is the greater of:

$$P_o = X_o F_r + Y_o F_a \quad (27)$$

$$P_o = F_r \quad (28)$$

where X_o = radial factor given in Table 37
Y_o = axial factor given in Table 37
F_r = applied radial load, newtons (pounds)
F_a = applied axial load, newtons (pounds)

Table 37. Values of X_o and Y_o for Computing Static Equivalent Radial Load P_o for Self-Aligning and Tapered Roller Bearings

Bearing Type	Single Row[a]		Double Row	
	X_o	Y_o	X_o	Y_o
Self-Aligningand Tapered $\alpha \neq 0$	0.5	0.22 cot α	1	0.44 cot α

[a] P_o is always $\geq F_r$.

The static equivalent radial load for radial roller bearings with $\alpha = 0°$ and subjected to radial load only is $P_{or} = F_r$.

Note: The ability of radial roller bearings with $\alpha = 0°$ to support axial loads varies considerably with bearing design and execution. The bearing user should therefore consult the bearing manufacturer for recommendations regarding the evaluation of equivalent load in cases where bearings with $\alpha = 0°$ are subjected to axial load.

Radial Roller Bearing Combinations: When calculating the static equivalent radial load for two similar single row angular contact roller bearings mounted side by side on the same shaft such that they operate as a unit (duplex mounting) in "back-to-back" or "face-to-face" arrangement, use the X_o and Y_o values for a double row bearing and the F_r and F_a values for the total loads on the arrangement.

When calculating the static equivalent radial load for two or more similar single row angular contact roller bearings mounted side by side on the same shaft such that they operate as a unit (duplex or stack mounting) in "tandem" arrangement, use the X_o and Y_o values for a single row bearing and the F_r and F_a values for the total loads on the arrangement.

Thrust Roller Bearings: The magnitude of the static equivalent axial load P_{oa} in newtons (pounds) for thrust roller bearings with contact angle $\alpha \neq 90°$, under combined radial and thrust loads is found by the formula:

$$P_{oa} = F_a + 2.3 F_r \tan\alpha \quad (29)$$

where F_a = applied axial load, newtons (pounds)
F_r = applied radial load, newtons (pounds)
α = nominal contact angle, degrees

The accuracy of this formula decreases for single direction thrust roller bearings when $F_r > 0.44 F_a \cot\alpha$.

Thrust Roller Bearing Combinations: When calculating the static equivalent axial load for two or more thrust roller bearings mounted side by side on the same shaft such that they operate as a unit (duplex or stack mounting) in "tandem" arrangement, use the F_r and F_a values for the total loads acting on the arrangement.

Copyright 2004, Industrial Press, Inc., New York, NY

STANDARD METAL BALLS

Standard Metal Balls.— American National Standard ANSI/AFBMA Std 10-1989 provides information for the user of metal balls permitting them to be described readily and accurately. It also covers certain measurable characteristics affecting ball quality.

On the following pages, tables taken from this Standard cover standard balls for bearings and other purposes by type of material, grade, and size range; preferred ball sizes; ball hardness corrections for curvature; various tolerances, marking increments, and maximum surface roughnesses by grades; total hardness ranges for various materials; and minimum case depths for carbon steel balls. The numbers of balls per pound and per kilogram for ferrous and nonferrous metals are also shown.

Definitions and Symbols.— The following definitions and symbols apply to American National Standard metal balls.

Nominal Ball Diameter, D_w: The diameter value that is used for the general identification of a ball size, e.g., $\frac{1}{4}$ inch, 6 mm, etc.

Single Diameter of a Ball, D_{ws}: The distance between two parallel planes tangent to the surface of a ball.

Mean Diameter of a Ball, D_{wm}: The arithmetical mean of the largest and smallest single diameters of a ball.

Ball Diameter Variation, V_{Dws}: The difference between the largest and smallest single diameters of one ball.

Deviation from Spherical Form, ΔR_w: The greatest radial distance in any radial plane between a sphere circumscribed around the ball surface and any point on the ball surface.

Lot: A definite quantity of balls manufactured under conditions that are presumed uniform, considered and identified as an entirety.

Lot Mean Diameter, D_{wmL}: The arithmetical mean of the mean diameter of the largest ball and that of the smallest ball in the lot.

Lot Diameter Variation, V_{DwL}: The difference between the mean diameter of the largest ball and that of the smallest ball in the lot.

Nominal Ball Diameter Tolerance: The maximum allowable deviation of any ball lot mean diameter from the Nominal Ball Diameter.

Container Marking Increment: The Standard unit steps in millionths of an inch or in micrometers used to express the Specific Diameter.

Specific Diameter: The amount by which the lot mean diameter (D_{wmL}) differs from the nominal diameter (D_w), accurate to the container marking increment for that grade; the specific diameter should be marked on the unit container.

Ball Gage Deviation, ΔS: The difference between the lot mean diameter and the sum of the nominal mean diameter and the ball gage.

Surface Roughness, R_a: Surface roughness consists of all those irregularities that form surface relief and are conventionally defined within the area where deviations of form and waviness are eliminated. (See Handbook Surface Texture Section.)

Ordering Specifications.— Unless otherwise agreed between producer and user, orders for metal balls should provide the following information: quantity, material, nominal ball diameter, grade, and ball gage. A *ball grade* embodies a specific combination of dimensional form, and surface roughness tolerances. A *ball gage(s)* is the prescribed small amount, expressed with the proper algebraic sign, by which the lot mean diameter (arithmetic mean of the mean diameters of the largest and smallest balls in the lot) should differ from the nominal diameter, this amount being one of an established series of amounts as shown in the table below. The 0 ball gage is commonly referred to as "OK".

Copyright 2004, Industrial Press, Inc., New York, NY

Preferred Ball Gages for Grades 3 to 200

	Ball Gages (in 0.0001-in. units)			Ball Gages (in 1μm units)		
Grade	Minus	OK	Plus	Minus	OK	Plus
3, 5	− 3 − 2 − 1	0	+ 1 + 2 + 3	− 8 − 7 − 6 − 5 − 4 − 3 − 2 − 1	0	+ 1 + 2 + 3 + 4 + 5 + 6 + 7 + 8
10, 16	− 4 − 3 − 2 − 1	0	+ 1 + 2 + 3 + 4	− 10 − 8 − 6 − 4 − 2	0	+ 2 + 4 + 6 + 8 + 10
24	− 5 − 4 − 3 − 2 − 1	0	+ 1 + 2 + 3 + 4 + 5	− 12 − 10 − 8 − 6 − 4 − 2	0	+ 2 + 4 + 6 + 8 + 10 + 12
48	− 6 − 4 − 2	0	+ 2 + 4 + 6	− 16 − 12 − 8 − 4	0	+ 4 + 8 + 12 + 16
100		0			0	
200		0			0	

Table 1. AFBMA Standard Balls — Tolerances for Individual Balls and for Lots of Balls

	Allowable Ball Diameter Variation	Allowable Deviation from Spherical Form	Maximum Surface Roughness R_a	Allowable Lot Diameter Variation	Nominal Ball Diameter Tolerance (±)	Container Marking Increments
	For Individual Balls			For Lots of Balls		
Grade	Millionths of an Inch					
3	3	3	0.5	5	[a]	10
5	5	5	0.8	10	[a]	10
10	10	10	1	20	[a]	10
16	16	16	1	32	[a]	10
24	24	24	2	48	[a]	10
48	48	48	3	96	[a]	50
100	100	100	5	200	500	[a]
200	200	200	8	400	1000	[a]
500	500	500	[a]	1000	2000	[a]
1000	1000	1000	[a]	2000	5000	[a]
	Micrometers					
3	0.08	0.08	0.012	0.13	[a]	0.25
5	0.13	0.13	0.02	0.25	[a]	0.25
10	0.25	0.25	0.025	0.5	[a]	0.25
16	0.4	0.4	0.025	0.8	[a]	0.25
24	0.6	0.6	0.05	1.2	[a]	0.25
48	1.2	1.2	0.08	2.4	[a]	1.25
100	2.5	2.5	0.125	5	12.5	[a]
200	5	5	0.2	10	25	[a]
500	13	13	[a]	25	50	[a]
1000	25	25	[a]	50	125	[a]

[a] Not applicable.

Allowable ball gage (see text) deviation is for Grade 3: + 0.000030, – 0.000030 inch (+0.75, – 0.75 μm); for Grades 5, 10, and 16: + 0.000050, – 0.000040 inch (+ 1.25, – 1 μm); and for Grade 24: + 0.000100, – 0.000100 inch (+ 2.5, – 2.5 μm). Other grades not given.

Examples: A typical order, in inch units, might read as follows: 80,000 pieces, chrome alloy steel, ¼-inch Nominal Diameter, Grade 16, and Ball Gage to be –0.0002 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

A typical order, in metric units, might read as follows: 80,000 pieces, chrome alloy steel, 6 mm Nominal Diameter, Grade 16, and Ball Gage to be –4 μm.

Package Marking: The ball manufacturer or supplier will identify packages containing each lot with information provided on the orders, as given above. In addition, the specific diameter of the contents shall be stated. Container marking increments are listed in Table 1.

Examples: Balls supplied to the order of the first of the previous examples would, if perfect size, be $D_{wmL} = 0.249800$ inch. In Grade 16 these balls would be acceptable with D_{wmL} from 0.249760 to 0.249850 inch. If they actually measured 0.249823 (which would be rounded off to 0.249820), each package would be marked: 5,000 Balls, Chrome Alloy Steel, ¼″ Nominal Diameter, Grade 16, –0.0002 inch Ball Gage, and –0.000180 inch Specific Diameter.

Balls supplied to the order of the second of the two previous examples would, if perfect size, be $D_{wmL} = 5.99600$ mm. In Grade 16 these balls would be acceptable with a D_{wmL} from 5.99500 to 5.99725 mm. If they actually measured 5.99627 mm (which would be rounded off to 5.99625 mm), each package would be marked: 5,000 Balls, Chrome Alloy Steel, 6 mm Nominal Diameter, Grade 16, –4 μm Ball Gage, and –3.75 μm Specific Diameter.

For complete details as to material requirements, quality specifications, quality assurance provisions, and methods of hardness testing, reference should be made to the Standard.

Table 2. AFBMA Standard Balls — Typical Nominal Size Ranges by Material and Grade

Steel Balls[a]				Non-Ferrous Balls[a]			
		Size Range[b]				Size Range[b]	
Material	Grade	Inch	mm	Material Grade	Grade	Inch	mm
Chrome Alloy	3	1/32–1	0.8–25	Aluminum	200	1/16–1	1.5–25
	5,10, 16,24	1/64–1 1/2	0.3–38	Aluminum Bronze	200	13/16–4	20–100
	48, 100, 200, 500	1/32–2 7/8	0.8–75	Brass	100,200, 500, 1000	1/16–3/4	1.5–19
	1000	3/8–4 1/2	10–115	Bronze	200,500, 1000	1/16–3/4	1.5–19
AISI M-50	3 5,10,16	1/32–1 1/2	0.8–12	Monel Metal 400	100,200, 500	1/16–3/4	1.5–19
	24,48	1/32–1 5/8	0.8–40	K-Monel Metal 500	100	1/16–3/4	1.5–19
Corrosion Resisting Hardened	3,5,10,16	1/64–3/4	0.3–19		200	1/16–1 11/16	1.5–45
	24	1/32–1	0.8–25	Tungsten Carbide	5	3/64–1/2	1.2–12
	48	1/32–2	0.8–50		10	3/64–3/4	1.2–19
	100,200	1/32–4 1/2	0.8–115		16	3/64–1	1.2–25
Corrosion-Resisting Unhardened	100,200, 500	1/16–3/4	1.5–19		24	3/64–1 1/4	1.2–32
Carbon Steel[c]	100,200, 500, 1000	1/16–1 1/2	1.5–38				
Silicon Molybdenum	200	1/4–1 1/8	6.5–28				

[a] For hardness rages see Table 3.
[b] For tolerances see Table 1.
[c] For minimum case depths refer to the Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. AFBMA Standard Balls—Typical Hardness Ranges

Material	Common Standard	SAE Unified Number	Rockwell Value[a,b]
Steel—			
Alloy tool	AISI/SAE M50	T11350	60–65 "C"[c,d]
Carbon[e]	AISI/SAE 1008	G10080	60 Minimum "C"[b]
	AISI/SAE 1013	G10130	60 Minimum "C"[b]
	AISI/SAE 1018	G10180	60 Minimum "C"[b]
	AISI/SAE 1022	G10220	60 Minimum "C"[b]
Chrome alloy	AISI/SAE E52100	G52986	60–67 "C"[c,d]
	AISI/SAE E51100	G51986	60-67 "C"[c,d]
Corrosion-resisting hardened			
	AISI/SAE 440C	S44004	58–65 "C"[f,d]
	AISI/SAE 440B	S44003	55–62 "C"[f,d]
	AISI/SAE 420	S42000	52 Minimum "C"[f,d]
	AISI/SAE 410	S41000	97 "B"; 41 "C"[f,d]
	AISI/SAE 329	S32900	45 Minimum "C"[f,d]
Corrosion-resisting unhardened			
	AISI/SAE 3025	S30200	25–39 "C"[d,g]
	AISI/SAE 304	S30400	25–39 "C"[d,g]
	AISI/SAE 305	S30500	25–39 "C"[d,g]
	AISI/SAE 316	S31600	25–39 "C"[d,g]
	AISI/SAE 430	S43000	48–63 "A"[d]
Silicon molybdenum	AISI/SAE S2	T41902	52–60 "C"[c]
Aluminum	AA-2017	A92017	54–72 "B"
Aluminium bronze	CDA-624	C62400	94–98 "B"
	CDA-630	C63000	94–98 "B"
Brass	CDA-260	C26000	75–87 "B"
Bronze	CDA-464	C46400	75–98 "B"
Monel 400	AMS-4730	N04400	85–95 "B"
Monel K-500	QA-N-286	N05500	24 Minimum "C"
Tungsten carbide	JIC Carbide Classification	…	84-91.5 "A"

[a] Rockwell Hardness Tests shall be conducted on parallel flats in accordance with ASTM Standard E18 unless otherwise specified.

[b] Hardness readings taken on spherical surfaces are subject to the corrections shown in Table 5. Hardness readings for carbon steel balls smaller than 5 mm (¼ inch) shall be taken by the microhardness method (detailed in ANSI/AFBMA Std 10-1989) or as agreed between manufacturer and purchaser.

[c] Hardness of balls in any one lot shall be within 3 points on Rockwell C scale.

[d] When microhardness method (see ANSI/AFBMA Std 10-1989 is used, the Rockwell hardness values given are converted to DPH in accordance with ASTM Standard E 140, "Standard Hardness Conversion Tables for Metals."

[e] Choice of carbon steels shown to be at ball manufacturer's option.

[f] Hardness of balls in any one lot shall be within 4 points on Rockwell C scale.

[g] Annealed hardness of 75-90 "B" is available when specified.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Preferred Ball Sizes

Nominal Ball Sizes Metric	Diameter mm	Diameter Inches	Nominal Ball Sizes Inch	Nominal Ball Sizes Metric	Diameter mmb	Diameter Inches	Nominal Ball Sizes Inch
0.3	0.300 00	0.011 810			0.793 75	0.031 250	1/32
	0.396 88	0.015 625	1/64	0.8	0.800 00	0.031 496	
0.4	0.400 00	0.015 750		1	1.000 00	0.039 370	
0.5	0.500 00	0.019 680			1.190 63	0.046 875	3/64
	0.508 00	0.020 000	0.020	1.2	1.200 00	0.047 240	
0.6	0.600 00	0.023 620		1.5	1.500 00	0.059 060	
	0.635 00	0.025 000	0.025		1.587 50	0.062 500	1/16
0.7	0.700 00	0.027 560			1.984 38	0.078 125	5/64
2	2.000 00	0.078 740		21	21.000 000	0.826 770	
	2.381 25	0.093 750	3/32		21.431 25	0.843 750	27/32
2.5	2.500 00	0.098 420		22	22.000 00	0.866 140	
	2.778 00	0.109 375	7/64		22.225 00	0.875 000	7/8
3	3.000 00	0.118 110		23	23.000 00	0.905 510	
	3.175 00	0.125 000	1/8		23.018 75	0.906 250	29/32
3.5	3.500 00	0.137 800			23.812 50	0.937 500	15/16
	3.571 87	0.140 625	9/64	24	24.000 00	0.944 880	
	3.968 75	0.156 250	5/32		24.606 25	0.968 750	31/32
4	4.000 00	0.157 480		25	25.000 00	0.984 250	
	4.365 63	0.171 875	11/64		25.400 00	1.000 000	1
4.5	4.500 00	0.177 160		26	26.000 00	1.023 620	
	4.762 50	0.187 500	3/16		26.987 50	1.062 500	1 1/16
5	5.000 00	0.196 850		28	28.000 00	1.102 360	
5.5	5.500 00	0.216 540			28.575 00	1.125 000	1 1/8
	5.556 25	0.218 750	7/32	30	30.000 00	1.181 100	
	5.953 12	0.234 375	15/64		30.162 50	1.187 500	1 3/16
6	6.000 00	0.236 220			31.750 00	1.250 000	1 1/4
	6.350 00	0.250 000	1/4	32	32.000 00	1.259 840	
6.5	6.500 00	0.255 900			33.337 50	1.312 500	1 5/16
	6.746 88	0.265 625	17/64	34	34.000 00	1.338 580	
7	7.000 00	0.275 590			34.925 00	1.375 000	1 3/8
	7.143 75	0.281 250	9/32	35	35.000 00	1.377 950	
7.5	7.500 00	0.295 280		36	36.000 00	1.417 320	
	7.540 63	0.296 875	19/64		36.512 50	1.437 500	1 7/16
	7.937 50	0.312 500	5/16	38	38.000 00	1.496 060	
8	8.000 00	0.314 960			38.100 00	1.500 000	1 1/2
8.5	8.500 00	0.334 640			39.687 50	1.562 500	1 9/16
	8.731 25	0.343 750	11/32	40	40.000 00	1.574 800	
9	9.000 00	0.354 330			41.275 00	1.625 000	1 5/8
	9.128 12	0.359 375	23/64		42.862 50	1.687 500	1 11/16
	9.525 00	0.375 000	3/8		44.450 00	1.750 000	1 3/4
	9.921 87	0.390 625	25/64	45	45.000 00	1.771 650	
10	10.000 00	0.393 700			46.037 50	1.812 500	1 13/16
	10.318 75	0.406 250	13/32		47.625 00	1.875 000	1 7/8
11	11.000 00	0.433 070			49.212 50	1.937 500	1 15/16
	11.112 50	0.437 500	7/16	50	50.000 00	1.968 500	
11.5	11.500 00	0.452 756			50.800 00	2.000 000	2
	11.509 38	0.453 125	29/64		53.975 00	2.125 000	2 1/8

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. *(Continued)* Preferred Ball Sizes

Nominal Ball Sizes Metric	Diameter mm	Diameter Inches	Nominal Ball Sizes Inch	Nominal Ball Sizes Metric	Diameter mmb	Diameter Inches	Nominal Ball Sizes Inch
	11.906 25	0.468 750	15/32	55	55.000 00	2.165 354	
12	12.000 00	0.472 440			57.150 00	2.250 000	2¼
	12.303 12	0.484 375	31/64	60	60.000 00	2.362 205	
	12.700 00	0.500 000	½		60.325 00	2.375 00	2⅜
13	13.000 00	0.511 810			63.500 00	2.500 000	2½
	13.493 75	0.531 250	17/32	65	65.000 00	2.559 055	
14	14.000 00	0.551 180			66.675 00	2.625 000	2⅝
	14.287 50	0.562 500	9/16		69.850 00	2.750 000	2¾
15	15.000 00	0.590 550			73.025 00	2.875 000	2⅞
	15.081 25	0.593 750	19/32		76.200 00	3.000 000	3
	15.875 00	0.625 000	⅝		79.375 00	3.125 000	3 ⅛
16	16.000 00	0.629 920			82.550 00	3.250 000	3¼
	16.668 75	0.656 250	21/32		85.725 00	3.375 00	3⅜
17	17.000 00	0.669 290			88.900 00	3.500 000	3½
	17.462 50	0.687 500	11/16		92.075 00	3.625 000	3⅝
18	18.000 00	0.708 660			95.250 00	3.750 000	3¾
	18.256 25	0.718 750	23/32		98.425 00	3.875 000	3⅞
19	19.000 00	0.748 030			101.600 00	4.000 000	4
	19.050 00	0.750 000	¾		104.775 00	4.125 000	4⅛
	19.843 75	0.781 250	25/32		107.950 00	4.250 000	4¼
20	20.000 00	0.787 400			111.125 00	4.375 000	4⅜
	20.637 50	0.812 500	13/16		114.300 00	4.500 000	4½

Table 5. Ball Hardness Corrections for Curvatures

Hardness Reading, Rockwell C	Ball Diameters, Inch						
	¼	5/16	⅜	½	⅝	¾	1
	Correction—Rockwell C						
20	12.1	9.3	7.7	6.1	4.9	4.1	3.1
25	11.0	8.4	7.0	5.5	4.4	3.7	2.7
30	9.8	7.5	6.2	4.9	3.9	3.2	2.4
35	8.6	6.6	5.5	4.3	3.4	2.8	2.1
40	7.5	5.7	4.7	3.6	2.9	2.4	1.7
45	6.3	4.9	4.0	3.0	2.4	1.9	1.4
50	5.2	4.0	3.2	2.4	1.9	1.5	1.1
55	4.1	3.1	2.5	1.8	1.4	1.1	0.8
60	2.9	2.2	1.8	1.2	0.9	0.7	0.4
65	1.8	1.3	1.0	0.5	0.3	0.2	0.1
20	12.8	9.3	7.6	6.6	5.2	4.0	3.2
25	11.7	8.4	6.9	5.9	4.6	3.5	2.8
30	10.5	7.5	6.1	5.2	4.1	3.1	2.4
35	9.4	6.6	5.4	4.6	3.6	2.7	2.1
40	8.0	5.7	4.5	3.8	3.0	2.2	1.8
45	6.7	4.9	3.8	3.2	2.5	1.8	1.4
50	5.5	4.0	3.0	2.6	2.0	1.4	1.1
55	4.3	3.1	2.3	1.9	1.5	1.0	0.8
60	3.0	2.2	1.7	1.2	1.0	0.6	0.4
65	1.9	1.3	0.9	0.6	0.4	0.2	0.1

Corrections to be added to Rockwell C readings obtained on spherical surfaces of chrome alloy steel, corrosion resisting hardened and unhardened steel, and carbon steel balls. For other ball sizes and hardness readings, interpolate between correction values shown.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Number of Metal Balls per Pound

Nom. Dia.,[a] Inches	Material Density, Pounds per Cubic Inch												
	.101	.274	.277	.279	.283	.284	.286	.288	.301	.304	.306	.319	.540
1/32	620 000	228 000	226 000	224 000	221 000	220 000	219 000	217 000	208 000	206 000	205 000	196 000	116 000
1/16	77 500	28 600	28 200	28 000	27 600	27 500	27 400	27 200	26 000	25 700	25 600	24 500	14 500
3/32	22 900	8 460	8 370	8 310	8 190	8 160	8 100	8 050	7 700	7 620	7 570	7 270	4 290
1/8	9 680	3 570	3 530	3 500	3 460	3 440	3 420	3 400	3 250	3 220	3 200	3 070	1 810
5/32	4 960	1 830	1 810	1 790	1 770	1 760	1 750	1 740	1 660	1 650	1 640	1 570	927
3/16	2 870	1 060	1 050	1 040	1 020	1 020	1 010	1 010	963	953	947	908	537
7/32	1 810	666	659	654	645	642	638	634	606	600	596	572	338
1/4	1 210	446	441	438	432	430	427	424	406	402	399	383	226
9/32	850	313	310	308	303	302	300	298	285	282	281	269	159
5/16	620	228	226	224	221	220	219	217	208	206	205	196	116
11/32	466	172.	170.	169.	166.	166.	164.	163.	156.	155.	154.	147.	87.1
3/8	359	132.	131.	130.	128.	128.	127.	126.	120.	119.	118.	114.	67.1
13/32	282	104.	103.	102.	101.	100.	99.6	98.9	94.6	93.7	93.1	89.3	52.8
7/16	226	83.2	82.3	81.7	80.6	80.3	79.7	79.2	75.8	75.0	74.5	71.5	42.2
15/32	184	67.7	66.9	66.5	65.5	65.3	64.8	64.4	61.6	61.0	60.6	58.1	34.3
1/2	151.	55.8	55.2	54.8	54.0	53.8	53.4	53.1	50.8	50.3	49.9	47.9	28.3
17/32	126.	46.5	46.0	45.7	45.0	44.9	44.5	44.2	42.3	41.9	41.6	39.9	23.6
9/16	106.	39.2	38.7	38.5	37.9	37.8	37.5	37.3	35.7	35.3	35.1	33.6	19.9
19/32	90.3	33.3	32.9	32.7	32.2	32.1	31.9	31.7	30.3	30.0	29.8	28.6	16.9
5/8	77.5	28.6	28.2	28.0	27.6	27.5	27.4	27.2	26.0	25.7	25.6	24.5	14.5
21/32	66.9	24.7	24.4	24.2	23.9	23.8	23.6	23.5	22.5	22.2	22.1	21.2	12.5
11/16	58.2	21.5	21.2	21.1	20.8	20.7	20.6	20.4	19.5	19.3	19.2	18.4	10.9
23/32	50.9	18.8	18.6	18.4	18.2	18.1	18.0	17.9	17.1	16.9	16.8	16.1	9.53
3/4	44.8	16.5	16.3	16.2	16.0	15.9	15.8	15.7	15.0	14.9	14.8	14.2	8.38
25/32	39.7	14.6	14.5	14.4	14.2	14.1	14.0	13.9	13.3	13.2	13.1	12.6	7.42
13/16	35.3	13.0	12.9	12.8	12.6	12.5	12.5	12.4	11.8	11.7	11.6	11.2	6.59
27/32	31.5	11.6	11.5	11.4	11.2	11.2	11.1	11.0	10.6	10.5	10.4	9.97	5.89
7/8	28.2	10.4	10.3	10.2	10.1	10.0	9.97	9.90	9.47	9.38	9.32	8.94	5.28
29/32	25.4	9.37	9.26	9.20	9.07	9.04	8.97	8.91	8.53	8.44	8.39	8.04	4.75
15/16	22.9	8.46	8.37	8.31	8.19	8.16	8.10	8.05	7.70	7.62	7.57	7.27	4.29
31/32	20.8	7.67	7.58	7.53	7.42	7.40	7.35	7.29	6.98	6.91	6.87	6.59	3.89
1	18.9	6.97	6.89	6.85	6.75	6.72	6.68	6.63	6.35	6.28	6.24	5.99	3.54

[a] For sizes above 1 in. diameter, use the following formula: No. balls per pound = 1.91 ÷ [(nom. dia., in.)^3 × (material density, lbs. per cubic in.)].

Ball material densities in pounds per cubic inch: aluminum .101; aluminum bronze .274; corrosion resisting hardened steel .277; AISI M-50 and silicon molybdenum steels .279; chrome alloy steel .283; carbon steel .284; AISI 302 corrosion resisting unhardened steel .286; AISI 316 corrosion resisting unhardened steel .288; bronze .304; brass and K-Monel metal .306; Monel metal .319; and tungsten carbide .540.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Number of Metal Balls per Kilogram

Nom.Dia.,[a] mm	Material Density, Grams per Cubic Centimeter												
	2.796	7.584	7.667	7.723	7.833	7.861	7.916	7.972	8.332	8.415	8.470	8.830	14.947
0.3	25 300 000	9 330 000	9 230 000	9 160 000	9 030 000	9 000 000	8 940 000	8 870 000	8 490 000	8 410 000	8 350 000	8 010 000	4 730 000
0.4	10 670 000	3 930 000	3 890 000	3 860 000	3 810 000	3 800 000	3 770 000	3 740 000	3 580 000	3 550 000	3 520 000	3 380 000	2 000 000
0.5	5 470 000	2 010 000	1 990 000	1 980 000	1 950 000	1 940 000	1 930 000	1 920 000	1 830 000	1 820 000	1 800 000	1 730 000	1 020 000
0.7	1 990 000	734 000	726 000	721 000	711 000	708 000	703 000	698 000	668 000	662 000	657 000	631 000	373 000
0.8	1 330 000	492 000	487 000	483 000	476 000	475 000	471 000	468 000	448 000	443 000	440 000	422 000	250 000
1.0	683 000	252 000	249 000	247 000	244 000	243 000	241 000	240 000	229 000	227 000	225 000	216 000	128 000
1.2	395 000	146 000	144 000	143 000	141 000	141 000	140 000	139 000	133 000	131 000	130 000	125 000	73 900
1.5	202 000	74 600	73 800	73 300	72 200	72 000	71 500	71 000	67 900	67 200	66 800	64 100	37 900
2.0	85 400	31 500	31 100	30 900	30 500	30 400	30 200	29 900	28 700	28 400	28 200	27 000	16 000
2.5	43 700	16 100	15 900	15 800	15 600	15 500	15 400	15 300	14 700	14 500	14 400	13 800	8 180
3.0	25 300	9 330	9 230	9 160	9 030	9 000	8 940	8 870	8 490	8 410	8 350	8 010	4 730
3.5	15 900	5 870	5 810	5 770	5 690	5 670	5 630	5 590	5 350	5 290	5 260	5 040	2 980
4.0	10 700	3 930	3 890	3 860	3 810	3 800	3 770	3 740	3 580	3 550	3 520	3 380	2 000
4.5	7 500	2 760	2 730	2 710	2 680	2 670	2 650	2 630	2 520	2 490	2 470	2 370	1 400
5.0	5 470	5 010	1 990	1 980	1 950	1 940	1 930	1 920	1 830	1 820	1 800	1 730	1 020
5.5	4 110	1 510	1 500	1 490	1 470	1 460	1 450	1 440	1 380	1 360	1 360	1 300	768
6.0	3 160	1 170	1 150	1 140	1 130	1 120	1 120	1 110	1 060	1 050	1 040	1 000	592
6.5	2 490	917	907	901	888	885	878	872	835	826	821	788	465
7.0	1 990	734	726	721	711	708	703	698	668	662	657	631	373
7.5	1 620	597	590	586	578	576	572	568	543	538	534	513	303
8.0	1 330	492	487	483	476	475	471	468	448	443	440	422	250
8.5	1 110	410	406	403	397	396	393	390	373	370	367	352	208
9.0	937	345	342	339	334	333	331	329	314	311	309	297	175
10.0	683	252	249	247	244	243	241	240	229	227	225	216	128
11.0	513.0	189.0	187.0	186.0	183.0	183.0	181.0	180.0	172.0	171.0	169.0	163.0	96.0
11.5	449.0	166.0	164.0	163.0	160.0	160.0	159.0	158.0	151.0	149.0	148.0	142.0	84.0
12.0	395.0	146.0	144.0	143.0	141.0	141.0	140.0	139.0	133.0	131.0	130.0	125.0	73.9
13.0	311.0	115.0	113.0	113.0	111.0	111.0	110.0	109.0	104.0	103.0	103.0	98.5	58.2
14.0	249.0	91.8	90.8	90.1	88.9	88.5	87.9	87.3	83.5	82.7	82.2	78.8	46.6
15.0	202.0	74.6	73.8	73.3	72.2	72.0	71.5	71.0	67.9	67.2	66.8	64.1	37.9
16.0	167.0	61.5	60.8	60.4	59.5	59.3	58.9	58.5	56.0	55.4	55.1	52.8	31.2
17.0	139.0	51.3	50.7	50.3	49.6	49.5	49.1	48.8	46.7	46.2	45.9	44.0	26.0

[a] For sizes above 17 mm diameter, use the following formula: No. balls per kilogram = 1,910,000 ÷ [(nom. dia., mm)^3 × (material density, grams per cu. cm)].

Ball material densities in grams per cubic centimeter: aluminum, 2.796; aluminum bronze, 7.584; corrosion-resisting hardened steel, 7.677; AISI M-50 and silicon molybdenum steel, 7.723; chrome alloy steel, 7.833; carbon steel, 7.861; AISI 302 corrosion-resisting unhardened steel, 7.916; AISI 316 corrosion-resisting unhardened steel, 7.972; bronze, 8.415; brass and K-Monel metal, 8.470; Monel metal, 8.830; tungsten carbide, 14.947.

Copyright 2004, Industrial Press, Inc., New York, NY

LUBRICANTS AND LUBRICATION

A lubricant is used for one or more of the following purposes: to reduce friction; to prevent wear; to prevent adhesion; to aid in distributing the load; to cool the moving elements; and to prevent corrosion.

The range of materials used as lubricants has been greatly broadened over the years, so that in addition to oils and greases, many plastics and solids and even gases are now being applied in this role. The only limitations on many of these materials are their ability to replenish themselves, to dissipate frictional heat, their reaction to high environmental temperatures, and their stability in combined environments. Because of the wide selection of lubricating materials available, great care is advisable in choosing the material and the method of application. The following types of lubricants are available: petroleum fluids, synthetic fluids, greases, solid films, working fluids, gases, plastics, animal fat, metallic and mineral films, and vegetable oils.

Lubricating Oils.— The most versatile and best-known lubricant is mineral oil. When applied in well-designed applications that provide for the limitations of both mechanical and hydraulic elements, oil is recognized as the most reliable lubricant. Concurrently, it is offered in a wide selection of stocks, carefully developed to meet the requirements of the specific application.

Lubricating oils are seldom marketed without additives blended for a narrow range of applications. These "additive packages" are developed for particular applications, so it is advisable to consult the sales-engineering representatives of a reputable petroleum company on the proper selection for the conditions under consideration. The following are the most common types of additives: wear preventive, oxidation inhibitor, rust inhibitor, detergent-dispersant, viscosity index improver, defoaming agent, and pour-point depressant.

A more recent development in the field of additives is a series of organic compounds that leave no ash when heated to a temperature high enough to evaporate or burn off the base oil. Initially produced for internal-combustion-engine applications these additives have found ready acceptance in those other applications where metallic or mineral trace elements would promote catalytic, corrosive, deposition, or degradation effects on mechanism materials.

Additives usually are not stable over the entire temperature and shear-rate ranges considered acceptable for the base stock oil application. Because of this problem, additive type oils must be carefully monitored to ensure that they are not continued in service after their principal capabilities have been diminished or depleted. Of primary importance in this regard is the action of the detergent-dispersant additives that function so well to reduce and control degradation products that would otherwise deposit on the operating parts and oil cavity walls. Because the materials cause the oil to carry a higher than normal amount of the breakdown products in a fine suspension, they may cause an accelerated deposition rate or foaming when they have been depleted or degenerated by thermal or contamination action. Ingestion of water by condensation or leaking can cause markedly harmful effects.

Viscosity index improvers serve to modify oils so that their change in viscosity is reduced over the operating temperature range. These materials may be used to improve both a heavy or a light oil; however, the original stock will tend to revert to its natural state when the additive has been depleted or degraded due to exposure to high temperatures or to the high shear rates normally encountered in the load-carrying zones of bearings and gears. In heavy-duty installations, it is generally advisable to select a heavier or a more highly refined oil (and one that is generally more costly) rather than to rely on a less stable viscosity-index-improvement product. Viscosity-index-improved oils are generally used in applications where the shear rate is well below 1,000,000 reciprocal seconds, as determined by the following formula:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Shear rate}(s^{-1}) = \frac{DN}{60t}$$

where D is the journal diameter in inches, N is the journal speed in rpm, and t is the film thickness in inches.

Types of Oils.— Aside from being aware of the many additives available to satisfy particular application requirements and improve the performance of fluids, the designer must also be acquainted with the wide variety of oils, natural and synthetic, which are also available. Each oil has its own special features that make it suitable for specific applications and limit its utility in others. Though a complete description of each oil and its application feasibility cannot be given here, reference to major petroleum and chemical company sales engineers will provide full descriptions and sound recommendations. In some applications, however, it must be accepted that the interrelation of many variables, including shear rate, load, and temperature variations, prohibit precise recommendations or predictions of fluid durability and performance. Thus, prototype and rig testing are often required to ensure the final selection of the most satisfactory fluid.

The following table lists the major classifications and properties of available commercial petroleum oils.

Properties of Commercial Petroleum Oils and Their Applications

Automotive. With increased additives, diesel and marine reciprocating engines.				Gear trains and transmissions. With E. P. additives, hypoid gears.			
Type	Viscosity,Centistokes		Density, g/cc at 60°F	Type	Viscosity,Centistokes		Density, g/cc at 60°F
	100°F	210°F			100°F	210°F	
SAE 10 W	41	6.0	0.870		22	3.9	0.880
SAE 20 W	71	8.5	0.885		44	6.0	0.898
SAE 30	114	11.2	0.890	General Purpose	66	7.0	0.915
SAE 40	173	14.5	0.890		110	9.9	0.915
SAE 50	270	19.5	0.900		200	15.5	0.890
Machine tools and other industrial applications.				Marine propulsion and stationary power turbines.			
SAE 75	47	7.0					
SAE 80	69	8.0		Turbine Light	32	5.5	0.871
SAE 90	285	20.5	0.930, approx.	Medium	65	8.1	0.876
SAE 140	725	34.0		Heavy	99	10.7	0.885
SAE 250	1,220	47.0					
Turbojet engines.				Reciprocating engines.			
	5	1.5	0.858		76	9.3	0.875
Aviation	10	2.5	0.864	Aviation	268	20.0	0.891
					369	25.0	0.892

Viscosity.— As noted before, fluids used as lubricants are generally categorized by their viscosity at 100 and 210 deg. F. Absolute viscosity is defined as a fluid's resistance to shear or motion—its internal friction in other words. This property is described in several ways, but basically it is the force required to move a plane surface of unit area with unit speed parallel to a second plane and at unit distance from it. In the metric system, the unit of viscosity is called the "poise" and in the English system is called the "reyn." One reyn is equal to 68,950 poises. One poise is the viscosity of a fluid, such that one dyne force is required to move a surface of one square centimeter with a speed of one centimeter per second, the distance between surfaces being one centimeter. The range of kinematic viscosity for a series of typical fluids is shown in the table on page 2333. Kinematic viscosity is related directly to the flow time of a fluid through the viscosimeter capillary. By multiplying the kinematic viscosity by the density of the fluid at the test temperature, one can determine the absolute viscosity. Because, in the metric system, the mass density is equal to the specific gravity, the conversion from kinematic to absolute viscosity is generally made in this sys-

Copyright 2004, Industrial Press, Inc., New York, NY

tem and then converted to English units where required. The densities of typical lubricating fluids with comparable viscosities at 100 deg. F and 210 deg. F are shown in this same table.

The following conversion table may be found helpful.

Viscosity Conversion Factors

Multiply	By	To Get
Centipoises, Z, $\frac{\text{dyne-s}}{100\ \text{cm}^2}$	1.45×10^{-7}	Reyns, μ, $\frac{\text{lb force-s}}{\text{in.}^2}$
Centistokes, ν, $\frac{\text{cm}^2}{100\ \text{s}}$	Density in g/cc	Centipoises, Z, $\frac{\text{dyne-s}}{100\ \text{cm}^2}$
Saybolt Universal Seconds, t_s	$0.22t_s - \frac{180}{t_s}$	Centistokes, ν, $\frac{\text{cm}^2}{100\ \text{s}}$

Also see page 2586 for additinal conversion factors.

Finding Specific Gravity of Oils at Different Temperatures.— The standard practice in the oil industry is to obtain a measure of specific gravity at 60 deg. F on an arbitrary scale, in degrees API, as specified by the American Petroleum Institute. As an example, API gravity, ρ_{API}, may be expressed as 27.5 degrees at 60 deg. F.

The relation between gravity in API degrees and specific gravity (grams of mass per cubic centimeter) at 60 deg. F, ρ_{60}, is

$$\rho_{60} = \frac{141.5}{131.5 + \rho_{API}}$$

The specific gravity, ρ_T, at some other temperature, T, is found from the equation

$$\rho_T = \rho_{60} - 0.00035(T - 60)$$

Normal values of specific gravity for sleeve-bearing lubricants range from 0.75 to 0.95 at 60 deg. F. If the API rating is not known, an assumed value of 0.85 may be used.

Application of Lubricating Oils.— In the selection and application of lubricating oils, careful attention must be given to the temperature in the critical operating area and its effect on oil properties. Analysis of each application should be made with detailed attention given to cooling, friction losses, shear rates, and contaminants.

Many oil selections are found to result in excessive operating temperatures because of a viscosity that is initially too high, which raises the friction losses. As a general rule, the lightest-weight oil that can carry the maximum load should be used. Where it is felt that the load carrying capacity is borderline, lubricity improvers may be employed rather than an arbitrarily higher viscosity fluid. It is well to remember that in many mechanisms the thicker fluid may increase friction losses sufficiently to lower the operating viscosity into the range provided by an initially lighter fluid. In such situations also, improved cooling, such as may be accomplished by increasing the oil flow, can improve the fluid properties in the load zone.

Similar improvements can be accomplished in many gear trains and other mechanisms by reducing churning and aeration through improved scavenging, direction of oil jets, and elimination of obstacles to the flow of the fluid. Many devices, such as journal bearings, are extremely sensitive to the effects of cooling flow and can be improved by greater flow rates with a lighter fluid. In other cases it is well to remember that the load carrying capacity of a petroleum oil is affected by pressure, shear rate, and bearing surface finish as well as initial viscosity and therefore these must be considered in the selection of the fluid. Detailed explanation of these factors is not within the scope of this text; however the technical representatives of the petroleum companies can supply practical guides for most applications.

Copyright 2004, Industrial Press, Inc., New York, NY

Other factors to consider in the selection of an oil include the following:1) Compatibility with system materials; 2) Water absorption properties; 3) Break-in requirements; 4) Detergent requirements; 5) Corrosion protection; 6) Low temperature properties; 7) Foaming tendencies; 8) Boundary lubrication properties; 9) Oxidation resistance (high temperature properties); and 10) Viscosity/temperature stability (Viscosity Temperature Index)..

Generally, the factors listed above are those which are usually modified by additives as described earlier. Since additives are used in limited amounts in most petroleum products, blended oils are not as durable as the base stock and must therefore be used in carefully worked-out systems. Maintenance procedures must be established to monitor the oil so that it may be replaced when the effect of the additive is noted or expected to degrade. In large systems supervised by a lubricating engineer, sampling and associated laboratory analysis can be relied on, while in customer-maintained systems as in automobiles and reciprocating engines, the design engineer must specify a safe replacement period which takes into account any variation in type of service or utilization.

Some large systems, such as turbine-power units, have complete oil systems which are designed to filter, cool, monitor, meter, and replenish the oil automatically. In such facilities, much larger oil quantities are used and they are maintained by regularly assigned lubricating personnel. Here reliance is placed on conservatively chosen fluids with the expectation that they will endure many months or even years of service.

Centralized Lubrication Systems.— Various forms of centralized lubrication systems are used to simplify and render more efficient the task of lubricating machines. In general, a central reservoir provides the supply of oil, which is conveyed to each bearing either through individual lines of tubing or through a single line of tubing that has branches extending to each of the different bearings. Oil is pumped into the lines either manually by a single movement of a lever or handle, or automatically by mechanical drive from some revolving shaft or other part of the machine. In either case, all bearings in the central system are lubricated simultaneously. Centralized force-feed lubrication is adaptable to various classes of machine tools such as lathes, planers, and milling machines and to many other types of machines. It permits the use of a lighter grade of oil, especially where complete coverage of the moving parts is assured.

Gravity Lubrication Systems.— Gravity systems of lubrication usually consist of a small number of distributing centers or manifolds from which oil is taken by piping as directly as possible to the various surfaces to be lubricated, each bearing point having its own independent pipe and set of connections. The aim of the gravity system, as of all lubrication systems, is to provide a reliable means of supplying the bearing surfaces with the proper amount of lubricating oil. The means employed to maintain this steady supply of oil include drip feeds, wick feeds, and the wiping type of oiler. Most manifolds are adapted to use either or both drip and wick feeds.

Drip-feed Lubricators: A drip feed consists of a simple cup or manifold mounted in a convenient position for filling and connected by a pipe or duct to each bearing to be oiled. The rate of feed in each pipe is regulated by a needle or conical valve. A loose-fitting cover is usually fitted to the manifold in order to prevent cinders or other foreign matter from becoming mixed with the oil. When a cylinder or other chamber operating under pressure is to be lubricated, the oil-cup takes the form of a lubricator having a tight-fitting screw cover and a valve in the oil line. To fill a lubricator of this kind, it is only necessary to close the valve and unscrew the cover.

Operation of Wick Feeds: For a wick feed, the siphoning effect of strands of worsted yarn is employed. The worsted wicks give a regular and reliable supply of oil and at the same time act as filters and strainers. A wick composed of the proper number of strands is fitted into each oil-tube. In order to insure using the proper sizes of wicks, a study should be made of the oil requirements of each installation, and the number of strands necessary to

Copyright 2004, Industrial Press, Inc., New York, NY

meet the demands of bearings at different rates of speed should be determined. When the necessary data have been obtained, a table should be prepared showing the size of wick or the number of strands to be used for each bearing of the machine.

Oil-conducting Capacity of Wicks: With the oil level maintained at a point $\frac{3}{8}$ to $\frac{3}{4}$ inch below the top of an oil-tube, each strand of a clean worsted yarn will carry slightly more than one drop of oil a minute. A twenty-four-strand wick will feed approximately thirty drops a minute, which is ordinarily sufficient for operating a large bearing at high speed. The wicks should be removed from the oil-tubes when the machinery is idle. If left in place, they will continue to deliver oil to the bearings until the supply in the cup is exhausted, thus wasting a considerable quantity of oil, as well as flooding the bearing. When bearings require an extra supply of oil temporarily, it may be supplied by dipping the wicks or by pouring oil down the tubes from an oil-can or, in the case of drip feeds, by opening the needle valves. When equipment that has remained idle for some time is to be started up, the wicks should be dipped and the moving parts oiled by hand to insure an ample initial supply of oil. The oil should be kept at about the same level in the cup, as otherwise the rate of flow will be affected. Wicks should be lifted periodically to prevent dirt accumulations at the ends from obstructing the flow of oil.

How Lubricating Wicks are Made: Wicks for lubricating purposes are made by cutting worsted yarn into lengths about twice the height of the top of the oil-tube above the bottom of the oil-cup, plus 4 inches. Half the required number of strands are then assembled and doubled over a piece of soft copper wire, laid across the middle of the strands. The free ends are then caught together by a small piece of folded sheet lead, and the copper wire twisted together throughout its length. The lead serves to hold the lower end of the wick in place, and the wire assists in forcing the other end of the wick several inches into the tube. When the wicks are removed, the free end of the copper wire may be hooked over the tube end to indicate which tube the wick belongs to. Dirt from the oil causes the wick to become gummy and to lose its filtering effect. Wicks that have thus become clogged with dirt should be cleaned or replaced by new ones. The cleaning is done by boiling the wicks in soda water and then rinsing them thoroughly to remove all traces of the soda. Oil-pipes are sometimes fitted with openings through which the flow of oil can be observed. In some installations, a short glass tube is substituted for such an opening.

Wiper-type Lubricating Systems: Wiper-type lubricators are used for out-of-the-way oscillating parts. A wiper consists of an oil-cup with a central blade or plate extending above the cup, and is attached to a moving part. A strip of fibrous material fed with oil from a source of supply is placed on a stationary part in such a position that the cup in its motion scrapes along the fibrous material and wipes off the oil, which then passes to the bearing surfaces.

Oil manifolds, cups, and pipes should be cleaned occasionally with steam conducted through a hose or with boiling soda water. When soda water is used, the pipes should be disconnected, so that no soda water can reach the bearings.

Oil Mist Systems.— A very effective system for both lubricating and cooling many elements which require a limited quantity of fluid is found in a device which generates a mist of oil, separates out the denser and larger (wet) oil particles, and then distributes the mist through a piping or conduit system. The mist is delivered into the bearing, gear, or lubricated element cavity through a condensing or spray nozzle, which also serves to meter the flow. In applications which do not encounter low temperatures or which permit the use of visual devices to monitor the accumulation of solid oil, oil mist devices offer advantages in providing cooling, clean lubricant, pressurized cavities which prevent entrance of contaminants, efficient application of limited lubricant quantities, and near-automatic performance. These devices are supplied with fluid reservoirs holding from a few ounces up to several gallons of oil and with accommodations for either accepting shop air or working

Copyright 2004, Industrial Press, Inc., New York, NY

from a self-contained compressor powered by electricity. With proper control of the fluid temperature, these units can atomize and dispense most motor and many gear oils.

Lubricating Greases.— In many applications, fluid lubricants cannot be used because of the difficulty of retention, relubrication, or the danger of churning. To satisfy these and other requirements such as simplification, greases are applied. These formulations are usually petroleum oils thickened by dispersions of soap, but may consist of synthetic oils with soap or inorganic thickeners, or oil with silaceous dispersions. In all cases, the thickener, which must be carefully prepared and mixed with the fluid, is used to immobilize the oil, serving as a storehouse from which the oil bleeds at a slow rate. Though the thickener very often has lubricating properties itself, the oil bleeding from the bulk of the grease is the determining lubricating function. Thus, it has been shown that when the oil has been depleted to the level of 50 per cent of the total weight of the grease, the lubricating ability of the material is no longer reliable. In some applications requiring an initially softer and wetter material, however, this level may be as high as 60 per cent.

Grease Consistency Classifications.— To classify greases as to mobility and oil content, they are divided into Grades by the NLGI (National Lubricating Grease Institute). These grades, ranging from 0, the softest, up through 6, the stiffest, are determined by testing in a penetrometer, with the depth of penetration of a specific cone and weight being the controlling criterion. To insure proper averaging of specimen resistance to the cone, most specifications include a requirement that the specimen be worked in a sieve-like device before being packed into the penetrometer cup for the penetration test. Since many greases exhibit thixotropic properties (they soften with working, as they often do in an application with agitation of the bulk of the grease by the working elements or accelerations), this penetration of the worked specimen should be used as a guide to compare the material to the original manufactured condition of it and other greases, rather than to the exact condition in which it will be found in the application. Conversely, many greases are found to stiffen when exposed to high shear rates at moderate loads as in automatic grease dispensing equipment. The application of a grease, therefore must be determined by a carefully planned cut-and-try procedure. Most often this is done by the original equipment manufacturer with the aid of the petroleum company representatives, but in many cases it is advisable to include the bearing engineer as well. In this general area it is well to remember that shock loads, axial or thrust movement within or on the grease cavity can cause the grease to contact the moving parts and initiate softening due to the shearing or working thus induced. To limit this action, grease-lubricated bearing assemblies often utilize dams or dividers to keep the bulk of the grease contained and unchanged by this working. Successful application of a grease depends however, on a relatively small amount of mobile lubricant (the oil bled out of the bulk) to replenish that small amount of lubricant in the element to be lubricated. If the space between the bulk of the mobile grease and the bearing is too large, then a critical delay period (which will be regulated by the grease bleed rate and the temperature at which it is held) will ensue before lubricant in the element can be resupplied. Since most lubricants undergo some attrition due to thermal degradation, evaporation, shearing, or decomposition in the bearing area to which applied, this delay can be fatal.

To prevent this from leading to failure, grease is normally applied so that the material in the cavity contacts the bearing in the lower quadrants, insuring that the excess originally packed into it impinges on the material in the reservoir. With the proper selection of a grease which does not slump excessively, and a reservoir construction to prevent churning, the initial action of the bearing when started into operation will be to purge itself of excess grease, and to establish a flow path for bleed oil to enter the bearing. For this purpose, most greases selected will be of a grade 2 or 3 consistency, falling into the "channelling" variety or designation.

Types of Grease.— Greases are made with a variety of soaps and are chosen for many particular characteristics. Most popular today, however, are the lithium, or soda-soap grease

Copyright 2004, Industrial Press, Inc., New York, NY

and the modified-clay thickened materials. For high temperature applications (250 deg. F. and above) certain finely divided dyes and other synthetic thickeners are applied. For all-around use the lithium soap greases are best for moderate temperature applications (up to 225 deg. F.) while a number of soda-soap greases have been found to work well up to 285 deg. F. Since the major suppliers offer a number of different formulations for these temperature ranges it is recommended that the user contact the engineering representatives of a reputable petroleum company before choosing a grease. Greases also vary in volatility and viscosity according to the oil used. Since the former will affect the useful life of the bulk applied to the bearing and the latter will affect the load carrying capacity of the grease, they must both be considered in selecting a grease.

For application to certain gears and slow-speed journal bearings, a variety of greases are thickened with carbon, graphite, molybdenum disulfide, lead, or zinc oxide. Some of these materials are likewise used to inhibit fretting corrosion or wear in sliding or oscillating mechanisms and in screw or thread applications. One material used as a "gear grease" is a residual asphaltic compound which is known as a "Crater Compound." Being extremely stiff and having an extreme temperature-viscosity relationship, its application must also be made with careful consideration of its limitations and only after careful evaluation in the actual application. Its oxidation resistance is limited and its low mobility in winter temperature ranges make it a material to be used with care. However, it is used extensively in the railroad industry and in other applications where containment and application of lubricants is difficult. In such conditions its ability to adhere to gear and chain contact surfaces far outweighs its limitations and in some extremes it is "painted" onto the elements at regular intervals.

Temperature Effects on Grease Life.— Since most grease applications are made where long life is important and relubrication is not too practical, operating temperatures must be carefully considered and controlled. Being a hydro-carbon, and normally susceptible to oxidation, grease is subject to the general rule that: Above a critical threshold temperature, each 15- to 18-deg. F. rise in temperature reduces the oxidation life of the lubricant by half. For this reason, it is vital that all elements affecting the operating temperature of the application be considered, correlated, and controlled. With sealed-for-life bearings, in particular, grease life must be determined for representative bearings and limits must be established for all subsequent applications.

Most satisfactory control can be established by measuring bearing temperature rise during a controlled test, at a consistent measuring point or location. Once a base line and limiting range are determined, all deviating bearings should be dismantled, inspected, and reassembled with fresh lubricant for retest. In this manner mavericks or faulty assemblies will be ferreted out and the reliability of the application established. Generally, a well lubricated grease packed bearing will have a temperature rise above ambient, as measured at the outer race, of from 10 to 50 deg. F. In applications where heat is introduced into the bearing through the shaft or housing, a temperature rise must be added to that of the frame or shaft temperature.

In bearing applications care must be taken not to fill the cavity too full. The bearing should have a practical quantity of grease worked into it with the rolling elements thoroughly coated and the cage covered, but the housing (cap and cover) should be no more than 75 per cent filled; with softer greases, this should be no more than 50 per cent. Excessive packing is evidenced by overheating, churning, aerating, and eventual purging with final failure due to insufficient lubrication. In grease lubrication, *never* add a bit more for good luck — hold to the prescribed amount and determine this with care on a number of representative assemblies.

Relubricating with Grease.— In some applications, sealed-grease methods are not applicable and addition of grease at regular intervals is required. Where this is recommended by the manufacturer of the equipment, or where the method has been worked out as part of a development program, the procedure must be carefully followed. *First,* use the proper

Copyright 2004, Industrial Press, Inc., New York, NY

lubricant — the same as recommended by the manufacturer or as originally applied (grease performance can be drastically impaired if contaminated with another lubricant). *Second,* clean the lubrication fitting thoroughly with materials which will not affect the mechanism or penetrate into the grease cavity. *Third,* remove the cap (and if applicable, the drain or purge plug). *Fourth*, clean and inspect the drain or scavenge cavity. *Fifth,* weigh the grease gun or calibrate it to determine delivery rate. *Sixth,* apply the directed quantity or fill until grease is detected coming out the drain or purge hole. *Seventh*, operate the mechanism with the drain open so that excess grease is purged. *Last,* continue to operate the mechanism while determining the temperature rise and insure that it is within limits. Where there is access to a laboratory, samples of the purged material may be analyzed to determine the deterioration of the lubricant and to search for foreign material which may be evidence of contamination or of bearing failure.

Normally, with modern types of grease and bearings, lubrication need only be considered at overhaul periods or over intervals of three to ten years.

Solid Film Lubricants.— Solids such as graphite, molybdenum disulfide, polytetrafluoroethylene, lead, babbit, silver, or metallic oxides are used to provide dry film lubrication in high-load, slow-speed or oscillating load conditions. Though most are employed in conjunction with fluid or grease lubricants, they are often applied as the primary or sole lubricant where their inherent limitations are acceptable. Of foremost importance is their inability to carry away heat. Second, they cannot replenish themselves, though they generally do lay down an oriented film on the contacting interface. Third, they are relatively immobile and must be bonded to the substrate by a carrier, by plating, fusing, or by chemical or thermal deposition.

Though these materials do not provide the low coefficient of friction associated with fluid lubrication, they do provide coefficients in the range of 0.4 down to 0.02, depending on the method of application and the material against which they rub. Polytetrafluoroethylene, in normal atmospheres and after establishing a film on both surfaces has been found to exhibit a coefficient of friction down to 0.02. However, this material is subject to cold flow and must be supported by a filler or on a matrix to continue its function. Since it can now be cemented in thin sheets and is often supplied with a fine glass fiber filler, it is practical in a number of installations where the speed and load do not combine to melt the bond or cause the material to sublime.

Bonded films of molybdenum disulfide, using various resins and ceramic combinations as binders, are deposited over phosphate treated steel, aluminum, or other metals with good success. Since its action produces a gradual wear of the lubricant, its life is limited by the thickness which can be applied (not over a thousandth or two in the conventional application). In most applications this is adequate if the material is used to promote break-in, prevent galling or pick-up, and to reduce fretting or abrasion in contacts otherwise impossible to separate.

In all applications of solid film lubricants, the performance of the film is limited by the care and preparation of the surface to which they are applied. If they can't adhere properly, they cannot perform, coming off in flakes and often jamming under flexible components. The best advice is to seek the assistance of the supplier's field engineer and set up a close control of the surface preparation and solid film application procedure. It should be noted that the functions of a good solid film lubricant cannot overcome the need for better surface finishing. Contacting surfaces should be smooth and flat to insure long life and minimum friction forces. Generally, surfaces should be finished to no more than 24 micro-inches AA with wariness no greater than 0.00002 inch.

Anti-friction Bearing Lubrication.— The limiting factors in bearing lubrication are the load and the linear velocity of the centers of the balls or rollers. Since these are difficult to evaluate, a speed factor which consists of the inner race bore diameter × RPM is used as a

Copyright 2004, Industrial Press, Inc., New York, NY

criterion. This factor will be referred to as S_i where the bore diameter is in inches and S_m where it is in millimeters.

For use in anti-friction bearings, grease must have the following properties:

1) Freedom from chemically or mechanically active ingredients such as uncombined metals or oxides, and similar mineral or solid contaminants.

2) The slightest possible tendency of change in consistency, such as thickening, separation of oil, evaporation or hardening.

3) A melting point considerably higher than the operating temperatures.

The choice of lubricating oils is easier. They are more uniform in their characteristics and if resistant to oxidation, gumming and evaporation, can be selected primarily with regard to a suitable viscosity.

Grease Lubrication: Anti-friction bearings are normally grease lubricated, both because grease is much easier than oil to retain in the housing over a long period and because it acts to some extent as a seal against the entry of dirt and other contaminants into the bearings. For almost all applications, a No. 2 soda-base grease or a mixed-base grease with up to 5 per cent calcium soap to give a smoother consistency, blended with an oil of around 250 to 300 SSU (Saybolt Universal Seconds) at 100 degrees F. is suitable. In cases where speeds are high, say S_i is 5000 or over, a grease made with an oil of about 150 SSU at 100 degrees F. may be more suitable especially if temperatures are also high. In many cases where bearings are exposed to large quantities of water, it has been found that a standard soda-base ball-bearing grease, although classed as water soluble gives better results than water-insoluble types. Greases are available that will give satisfactory lubrication over a temperature range of –40 degrees to +250 degrees F.

Conservative grease renewal periods will be found in the accompanying chart. Grease should not be allowed to remain in a bearing for longer than 48 months or if the service is very light and temperatures low, 60 months, irrespective of the number of hours' operation during that period as separation of the oil from the soap and oxidation continue whether the bearing is in operation or not.

Before renewing the grease in a hand-packed bearing, the bearing assembly should be removed and washed in clean kerosene, degreasing fluid or other solvent. As soon as the bearing is quite clean it should be washed at once in clean light mineral oil, preferably rust-inhibited. The bearing should *not be spun* before or while it is being oiled. Caustic solutions may be used if the old grease is hard and difficult to remove, but the best method is to soak the bearing for a few hours in light mineral oil, preferably warmed to about 130 degrees F., and then wash in cleaning fluid as described above. The use of chlorinated solvents is best avoided.

When replacing the grease, it should be forced with the fingers between the balls or rollers, dismantling the bearing, if convenient. The available space inside the bearing should be filled completely and the bearing then spun by hand. Any grease thrown out should be wiped off. The space on each side of the bearing in the housing should be not more than half-filled. Too much grease will result in considerable churning, high bearing temperatures and the possibility of early failure. Unlike any other kind of bearing, anti-friction bearings more often give trouble due to over-rather than to under-lubrication.

Grease is usually not very suitable for speed factors over 12,000 for S_i or 300,000 for S_m (although successful applications have been made up to an S_i of 50,000) or for temperatures much over 210 degrees F., 300 degrees F. being the extreme practical upper limit, even if synthetics are used. For temperatures above 210 degrees F., the grease renewal periods are very short.

Oil Lubrication: Oil lubrication is usually adopted when speeds and temperatures are high or when it is desired to adopt a central oil supply for the machine as a whole. Oil for anti-friction bearing lubrication should be well refined with high film strength and good resistance to oxidation and good corrosion protection. Anti-oxidation additives do no harm

Copyright 2004, Industrial Press, Inc., New York, NY

but are not really necessary at temperatures below about 200 degrees F. Anti-corrosion additives are always desirable. The accompanying table gives recommended viscosities of oil for ball bearing lubrication other than by an air-distributed oil mist. Within a given temperature and speed range, an oil towards the lighter end of the grade should be used, if convenient, as speeds increase. Roller bearings usually require an oil one grade heavier than do ball bearings for a given speed and temperature range. Cooled oil is sometimes circulated through an anti-friction bearing to carry off excess heat resulting from high speeds and heavy loads.



Oil Viscosities and Temperature Ranges for Ball Bearing Lubrication

Maximum Temperature Range Degrees F.	Optimum Temperature Range, Degrees F.	Speed Factor, S_i[a]	
		Under 1000	Over 1000
		Viscosity	
– 40 to + 100	– 40 to – 10	80 to 90 SSU[b]	70 to 80 SSU[b]
– 10 to + 100	– 10 to + 30	100 to 115 SSU[b]	80 to 100 SSU[b]
+ 30 to + 150	+ 30 to + 150	SAE 20	SAE 10
+ 30 to + 200	+ 150 to + 200	SAE 40	SAE 30
+ 50 to + 300	+ 200 to + 300	SAE 70	SAE 60

[a] Inner race bore diameter (inches) × RPM.
[b] At 100 deg. F.

Not applicable to air-distributed oil mist lubrication.

Copyright 2004, Industrial Press, Inc., New York, NY

Aerodynamic Lubrication

A natural extension of hydrodynamic lubrication consists in using air or some other gas as the lubricant. The viscosity of air is 1,000 times smaller than that of a very thin mineral oil. Consequently, the viscous resistance to motion is very much less. However, the distance of nearest approach, i.e. the closest distance between the shaft and the bearing is also correspondingly smaller, so that special precautions must be taken.

To obtain full benefit from such aerodynamic lubrication, the surfaces must have a very fine finish, the alignment must be very good, the speeds must be high and the loading relatively low. If all these conditions are fulfilled extremely successful bearing system can be made to run at very low coefficients of friction. They may also operate at very high temperatures since chemical degradation of the lubricant need not occur. Furthermore, if air is used as the lubricant, it costs nothing. This type of lubrication mechanism is very important for oil-free compressors and gas turbines. Another area of growing application for aerodynamic bearings is in data recording heads for computers. Air is used as the lubricant for the recording heads which are designed to be separated from the magnetic recording disc by a thin air film. The need for high recording densities in magnetic discs necessitates the smallest possible air film thickness between the head and disc. A typical thickness is around 1μm.

The analysis of aerodynamic bearings is very similar to liquid hydrodynamic bearings. The main difference, however, is that the gas compressibility is now a distinctive feature and has to be incorporated into the analysis.

Elastohydrodynamic Lubrication.— In the arrangement of the shaft and bearing it is usually assumed that the surfaces are perfectly rigid and retain their geometric shape during operation. However, a question might be posed: what is the situation if the geometry or mechanical properties of the materials are such that appreciable elastic deformation of the surfaces occurs? Suppose a steel shaft rests on a rubber block. It deforms the block elastically and provides an approximation to a half-bearing (see Figure 1 a).



Fig. 1a.



Fig. 1b.

If a lubricant is applied to the system it will be dragged into the interface and, if the conditions are right, it will form a hydrodynamic film. However, the pressures developed in the oil film will now have to match up with the elastic stresses in the rubber. In fact the shape of the rubber will be changed as indicated in Figure 1 b.

This type of lubrication is known as elastohydrodynamic lubrication. It occurs between rubber seals and shafts. It also occurs, rather surprisingly, in the contact between a windshield wiper blade and a windshield in the presence of rain. The geometry of the deformable member, its elastic properties, the load, the speed and the viscosity of the liquid and its dependence on the contact pressure are all important factors in the operation of elastohydrodynamic lubrication.

With conventional journals and bearings the average pressure over the bearing is of the order of 7×10^{-6} N/rn^2. With elastohydrodynamic bearings using a material such as rubber the pressures are perhaps 10 to 20 times smaller. At the other end of pressure spectrum, for instance in gear teeth, contact pressures of the order of $700\text{x}10^6$ N/in^2 may easily be

Copyright 2004, Industrial Press, Inc., New York, NY

reached. Because the metals used for gears are very hard this may still be within the range of elastic deformation. With careful alignment of the engaging gear teeth and appropriate surface finish, gears can in fact run successfully under these conditions using an ordinary mineral oil as the lubricant. If the thickness of the elastohydrodynamic film formed at such pressures is calculated it will be found that it is less than an atomic diameter. Sincc even the smoothest metal surfaces are far rougher than this (a millionth of an inch is about 100 atomic diameters) it seems hard to understand why lubrication is effective in these circumstances.

The explanation was first provided by A.N. Grubin in 1949 and a little later (1958) by A.W. Crook. With most mineral oils the application of a high pressure can lead to an enormous increase in viscosity. For example, at a pressure of 700×10^6 N/m^2 the viscosity may be increased 10,000-fold. The oil entering the gap between the gear teeth is trapped between the surfaces and at the high pressures existing in the contact region behaves virtually like a solid separating layer. This process explains why many mechanisms in engineering practice operate under much severer conditions than the classical theory would allow.

This type of elastohydrodynamic lubrication becomes apparent only when the film thickness is less than about 0.25 to 1 μm. To be exploited successfully it implies that the surfaces must be very smooth and very carefully aligned. If these conditions are met systems such as gears or cams and tappets can operate effectively at very high contact pressures without any metallic contact occurring. The coefficient of friction depends on the load, contact geometry, speed, etc., but generally it lies between about $\mu = 0.01$ at the lightest pressures and $\mu = 0.1$ at the highest pressures. The great success of elastohydrodynamic theory in explaining effective lubrication at very high contact pressures also raises a problem that has not yet been satisfactorily resolved: why do lubricants ever fail, since the harder they are squeezed the harder it is to extrude them? It is possible that high temperature flashes are responsible; alternatively the high rates of shear can actually fracture the lubricant film since when it is trapped between the surfaces it is, instantaneously, more like a wax than an oil.

It is clear that in this type of lubrication the effect of pressure on viscosity is a factor of major importance. It turns out that mineral oils have reasonably good pressure-viscosity characteristics. It appears that synthetic oils do not have satisfactory pressure-viscosity characteristics.

In engineering, two most frequently encountered types of contact are line contact and point contact.

The film thickness for line contact (gears, cam-tappet) can be estimated from:

$$h_o = 2.65 \frac{\alpha^{0.54} (\eta_o U)^{0.7} R_e^{0.43}}{w^{0.13} E_e^{0.03}}$$

In the case of point contact (ball bearings), the film thickness is given by:

$$h_o = 0.84 \alpha \eta_o U^{0.74} 0.41 R_e \left(\frac{E_e}{W}\right)^{0.074}$$

In the above equations the symbols used are defined as:

α = the pressure-viscosity coefficient. A typical value for mineral oil is 1.8×10^{-8} m^2/N

ν = the viscosity of the lubricant at atmospheric pressure Ns/m^2

U = the entraining surface velocity, $U = (U_A + U_B)/2$ m/s, where the subscripts A and B refer to the velocities of bodies 'A' and 'B' respectively.

W = the load on the contact, N

w = the load per unit width of line contact, N/m

Copyright 2004, Industrial Press, Inc., New York, NY

E_O = the reduced Young's modulus $\frac{1}{E_e} = \frac{1}{2}\left(\frac{1-\upsilon_A^2}{E_A} + \frac{1-\upsilon_B^2}{E_B}\right)$ N/m^2 where 'ν_A and ν_B are the Poisson's ratios of the contacting bodies 'A' and 'B' respectively; E_A and E_B are the Young's moduli of the contacting bodies 'A' and 'B' respectively.

R_e = - is the reduced radius of curvature (meters) and is given by different equations for different contact configurations.

In ball bearings (see Figure 2) the reduced radius is given by:

- contact between the ball and inner race: $R_e = \frac{rR_1}{R_1 + r}$
- contact between the ball and outer race: $R_e = \frac{r(R_1 + 2r)}{R_1 + r}$



Fig. 2.

For involute gears it can readily be shown that the contact at a distance s from the pitch point can be represented by two cylinders of radii $R_{1,2}\sin\psi + s$ rotating with the angular velocity of the wheels (see Fig. 3b). In the expression below R_1 or R_2 represent pitch radii of the wheels and ψ is the pressure angle. Thus,

$$R_e = \frac{(R_1 \sin\psi + s)(R_2 \sin\psi + s)}{(R_1 + R_2)\sin\psi}$$

The thickness of the film developed in the contact zone between smooth surfaces must be related to the topography of the actual surfaces. The most commonly used parameter for this purpose is the specific film thickness defined as the ratio of the minimum film thickness for smooth surfaces (given by the above equations) to the roughness parameter of the contacting surfaces.

$$\lambda = \frac{h_o}{\sqrt{R_{m1}^2 + R_{m2}^2}}$$

where $R_m = 1.11R_a$ is the root-mean-square height of surface asperities, and R_a is the centre-line-average height of surface asperities.

Copyright 2004, Industrial Press, Inc., New York, NY

If λ is greater than 3 then it is usually assumed that there is full separation of contacting bodies by an elastohydrodynamic film.



Fig. 3a.



Fig. 3b.

Viscosity-pressure relationship.— Lubricant viscosity increases with pressure. For most lubricants this effect is considerably larger than the effect of temperature or shear when the pressure is appreciably above atmospheric. This is of fundamental importance in the lubrication of highly loaded concentrated contacts such as in rolling contact bearings, gears and cam-tappet systems.

The best known equation to calculate the viscosity of a lubricant at moderate pressures is the Barus equation.

$$\eta_p = \eta_o e^{\alpha p}$$

where η is the viscosity at pressure p (Ns/m^2), η_0 is the viscosity at atmospheric pressure (Ns/in^2), α is the pressure-viscosity coefficient (m^2/N) which can be obtained by plotting the natural logarithm of dynamic viscosity η measured at pressure p. The slope of the graph is α and p is the pressure of concern (N/m^2).

Values of dynamic viscosity η and pressure-viscosity coefficient α for most commonly used lubricants are given in Table 1.

Table 1. Dynamic Viscosity η and Pressure-viscosity Coefficient α for Lubricants

Lubricant	Dynamic viscosity η measured at atmospheric pressure and room temperature η × 10^{-3} Ns/m^2	Pressure-viscosity coefficient α measured at room temperature α × 10^{-3} m^2/N
Light machine oil	45	28
Heavy machine oil	153	23.7
Cylinder oil	810	34
Spindle oil	18.6	20
Medicinal whale oil	107	29.5
Castor oil	360	15.9
Glycerol (glycerine)	535	5.9

Copyright 2004, Industrial Press, Inc., New York, NY

COUPLINGS AND CLUTCHES

Connecting Shafts.— For couplings to transmit up to about 150 horsepower, simple flange-type couplings of appropriate size, as shown in the table, are commonly used. The design shown is known as a safety flange coupling because the bolt heads and nuts are shrouded by the flange, but such couplings today are normally shielded by a sheet metal or other cover.

Safety Flange Couplings



										Bolts	
A	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*J*	*K*	No.	Dia.
1	1 3/4	2 1/4	4	11/16	5/16	1 1/2	1/4	9/32	1/4	5	3/8
1 1/4	2 3/16	2 3/4	5	13/16	3/8	1 7/8	1/4	9/32	1/4	5	7/16
1 1/2	2 5/8	3 3/8	6	15/16	7/16	2 1/4	1/4	9/32	1/4	5	1/2
1 3/4	3 1/16	4	7	1 1/16	1/2	2 5/8	1/4	9/32	1/4	5	9/16
2	3 1/2	4 1/2	8	1 3/16	9/16	3	1/4	9/32	5/16	5	5/8
2 1/4	3 15/16	5 1/8	9	1 5/16	5/8	3 3/8	1/4	9/32	5/16	5	11/16
2 1/2	4 3/8	5 5/8	10	1 7/16	11/16	3 3/4	1/4	9/32	5/16	5	3/4
2 3/4	4 13/16	6 1/4	11	1 9/16	3/4	4 1/8	1/4	9/32	5/16	5	13/16
3	5 1/4	6 3/4	12	1 11/16	13/16	4 1/2	1/4	9/32	3/8	5	7/8
3 1/4	5 11/16	7 3/8	13	1 13/16	7/8	4 7/8	1/4	9/32	3/8	5	15/16
3 1/2	6 1/8	8	14	1 15/16	15/16	5 1/4	1/4	9/32	3/8	5	1
3 3/4	6 9/16	8 1/2	15	2 1/16	1	5 5/8	1/4	9/32	3/8	5	1 1/16
4	7	9	16	2 1/4	1 1/8	6	1/4	9/32	7/16	5	1 1/8
4 1/2	7 7/8	10 1/4	18	2 1/2	1 1/4	6 3/4	1/4	9/32	7/16	5	1 1/4
5	8 3/4	11 1/4	20	2 3/4	1 3/8	7 1/2	1/4	9/32	7/16	5	1 3/8
5 1/2	8 3/4	11 1/4	20	2 3/4	1 3/8	7 1/2	1/4	9/32	7/16	5	1 3/8
6	10 1/2	12 3/8	22	2 15/16	1 1/2	8 1/4	5/16	11/32	1/2	5	1 7/16
6 1/2	11 3/8	13 1/2	24	3 1/8	1 5/8	9	5/16	11/32	1/2	5	1 1/2
7	12 1/4	14 5/8	26	3 1/4	1 3/4	9 3/4	5/16	11/32	9/16	6	1 1/2
7 1/2	13 1/8	15 3/4	28	3 7/16	1 7/8	10 1/2	5/16	11/32	9/16	6	1 9/16
8	14	16 7/8	28	3 1/2	2	10 7/8	5/16	11/32	5/8	7	1 1/2
8 1/2	14 7/8	18	30	3 11/16	2 1/8	11 1/4	5/16	11/32	5/8	7	1 9/16
9	15 3/4	19 1/8	31	3 3/4	2 1/4	11 5/8	5/16	11/32	11/16	8	1 1/2
9 1/2	16 5/8	20 1/4	32	3 15/16	2 3/8	12	5/16	11/32	11/16	8	1 9/16
10	17 1/2	21 3/8	34	4 1/8	2 1/2	12 3/4	5/16	11/32	3/4	8	1 5/8
10 1/2	18 3/8	22 1/2	35	4 1/4	2 5/8	13 1/8	5/16	11/32	3/4	10	1 5/8
11	19 1/4	23 5/8	36	4 7/16	2 3/4	13 1/2	5/16	11/32	7/8	10	1 11/16
11 1/2	20 1/8	24 3/4	37	4 5/8	2 7/8	13 7/8	5/16	11/32	7/8	10	1 3/4
12	21	25 7/8	38	4 13/16	3	14 1/4	5/16	11/32	1	10	1 13/16

Copyright 2004, Industrial Press, Inc., New York, NY

For small sizes and low power applications, a setscrew may provide the connection between the hub and the shaft, but higher power usually requires a key and perhaps two setscrews, one of them above the key. A flat on the shaft and some means of locking the setscrew(s) in position are advisable. In the AGMA Class I and II fits the shaft tolerances are –0.0005 inch from ½ to 1 ½ inches diameter and -0.001 inch on larger diameters up to 7 inches.

Class I coupling bore tolerances are + 0.001 inch up to 1 ½ inches diameter, then + 0.0015 inch to 7 inches diameter. Class II coupling bore tolerances are + 0.002 inch on sizes up to 3 inches diameter, + 0.003 inch on sizes from 3 ¼ through 3¾ inches diameter, and + 0.004 inch on larger diameters up to 7 inches.

Interference Fits.— Components of couplings transmitting over 150 horsepower often are made an interference fit on the shafts, which may reduce fretting corrosion. These couplings may or may not use keys, depending on the degree of interference. Keys may range in size from ⅛ inch wide by 1/16 inch high for ½-inch diameter shafts to 1 ¾ inches wide by ⅞ inch high for 7-inch diameter shafts. Couplings transmitting high torque or operating at high speeds or both may use two keys. Keys must be a good fit in their keyways to ensure good transmission of torque and prevent failure. AGMA standards provide recommendations for square parallel, rectangular section, and plain tapered keys, for shafts of 5/16 through 7 inches diameter, in three classes designated commercial, precision, and fitted. These standards also cover keyway offset, lead, parallelism, finish and radii, and face keys and splines. (See also ANSI and other Standards in Keys and Keyways section of this Handbook.)

Double-cone Clamping Couplings.— As shown in the table, double-cone clamping couplings are made in a range of sizes for shafts from 1 7/16 to 6 inches in diameter, and are easily assembled to shafts. These couplings provide an interference fit, but they usually cost more and have larger overall dimensions than regular flanged couplings.

Double-cone Clamping Couplings



A	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*J*	*K*	*L*	*M*	No. of Bolts	No. of Keys
1 7/16	5¼	2¾	2⅛	1⅝	⅝	2⅛	4¾	1⅛	1	5	½	3	1
1 15/16	7	3½	2⅞	2⅛	⅝	2¾	6¼	1⅛	1⅜	6¼	½	3	1
2 7/16	8¾	4 5/16	3⅝	3	¾	3½	7 13/16	1⅞	1¾	7⅞	⅝	3	1
3	10½	5½	4 3/32	3½	¾	4 3/16	9	2¼	2	9½	⅝	3	1
3½	12¼	7	5⅜	4⅜	⅞	5 1/16	11¼	2⅝	2⅛	11¼	¾	4	1
4	14	7	5½	4¾	⅞	5½	12	3¾	2½	12	¾	4	1
4½	15½	8	6⅞	5¼	⅞	6¾	13½	3¾	2¾	14½	¾	4	1
5	17	9	7¼	5¾	⅞	7	15	3¾	3	15¼	¾	4	1
5½	17½	9½	7¾	6¼	1	7	15½	3¾	3	15¼	⅞	4	1
6	18	10	8¼	6¾	1	7	16	3¾	3	15¼	⅞	4	2

Copyright 2004, Industrial Press, Inc., New York, NY

Flexible Couplings.— Shafts that are out of alignment laterally or angularly can be connected by any of several designs of flexible couplings. Such couplings also permit some degree of axial movement in one or both shafts. Some couplings use disks or diaphragms to transmit the torque. Another simple form of flexible coupling consists of two flanges connected by links or endless belts made of leather or other strong, pliable material. Alternatively, the flanges may have projections that engage spacers of molded rubber or other flexible materials that accommodate uneven motion between the shafts. More highly developed flexible couplings use toothed flanges engaged by correspondingly toothed elements, permitting relative movement. These couplings require lubrication unless one or more of the elements is made of a self-lubricating material. Other couplings use diaphragms or bellows that can flex to accommodate relative movement between the shafts.

The Universal Joint.— This form of coupling, originally known as a Cardan or Hooke's coupling, is used for connecting two shafts the axes of which are not in line with each other, but which merely intersect at a point. There are many different designs of universal joints or couplings, which are based on the principle embodied in the original design. One well-known type is shown by the accompanying diagram.

As a rule, a universal joint does not work well if the angle α (see illustration) is more than 45 degrees, and the angle should preferably be limited to about 20 degrees or 25 degrees, excepting when the speed of rotation is slow and little power is transmitted.

Variation in Angular Velocity of Driven Shaft: Owing to the angularity between two shafts connected by a universal joint, there is a variation in the angular velocity of one shaft during a single revolution, and because of this, the use of universal couplings is sometimes prohibited. Thus, the angular velocity of the driven shaft will not be the same at all points of the revolution as the angular velocity of the driving shaft. In other words, if the driving shaft moves with a uniform motion, then the driven shaft will have a variable motion and, therefore, the universal joint should not be used when absolute uniformity of motion is essential for the driven shaft.

Determining Maximum and Minimum Velocities: If shaft *A* (see diagram) runs at a constant speed, shaft *B* revolves at maximum speed when shaft A occupies the position shown in the illustration, and the minimum speed of shaft *B* occurs when the fork of the driving shaft *A* has turned 90 degrees from the position illustrated. The maximum speed of the driven shaft may be obtained by multiplying the speed of the driving shaft by the secant of angle α. The minimum speed of the driven shaft equals the speed of the driver multiplied by cosine α. Thus, if the driver rotates at a constant speed of 100 revolutions per minute and the shaft angle is 25 degrees, the maximum speed of the driven shaft is at a rate equal to $1.1034 \times 100 = 110.34$ rpm. The minimum speed rate equals $0.9063 \times 100 = 90.63$; hence, the extreme variation equals $110.34 - 90.63 = 19.71$ rpm.



Copyright 2004, Industrial Press, Inc., New York, NY

Use of Intermediate Shaft between Two Universal Joints.— The lack of uniformity in the speed of the driven shaft resulting from the use of a universal coupling, as previously explained, is objectionable for some forms of mechanisms. This variation may be avoided if the two shafts are connected with an intermediate shaft and two universal joints, provided the latter are properly arranged or located. Two conditions are necessary to obtain a constant speed ratio between the driving and driven shafts. First, the shafts must make the same angle with the intermediate shaft; second, the universal joint forks (assuming that the fork design is employed) on the intermediate shaft must be placed relatively so that when the plane of the fork at the left end coincides with the center lines of the intermediate shaft and the shaft attached to the left-hand coupling, the plane of the right-hand fork must also coincide with the center lines of the intermediate shaft and the shaft attached to the right-hand coupling; therefore the driving and the driven shafts may be placed in a variety of positions. One of the most common arrangements is with the driving and driven shafts parallel. The forks on the intermediate shafts should then be placed in the same plane.

This intermediate connecting shaft is frequently made telescoping, and then the driving and driven shafts can be moved independently of each other within certain limits in longitudinal and lateral directions. The telescoping intermediate shaft consists of a rod which enters a sleeve and is provided with a suitable spline, to prevent rotation between the rod and sleeve and permit a sliding movement. This arrangement is applied to various machine tools.

Knuckle Joints.— Movement at the joint between two rods may be provided by knuckle joints, for which typical proportions are seen in the table *Proportions of Knuckle Joints* that follows.

Friction Clutches.— Clutches which transmit motion from the driving to the driven member by the friction between the engaging surfaces are built in many different designs, although practically all of them can be classified under four general types, namely, conical clutches; radially expanding clutches; contracting-band clutches; and friction disk clutches in single and multiple types. There are many modifications of these general classes, some of which combine the features of different types. The proportions of various sizes of cone clutches are given in the table "Cast-iron Friction Clutches." The multicone friction clutch is a further development of the cone clutch. Instead of having a single cone-shaped surface, there is a series of concentric conical rings which engage annular grooves formed by corresponding rings on the opposite clutch member. The internal-expanding type is provided with shoes which are forced outward against an enclosing drum by the action of levers connecting with a collar free to slide along the shaft. The engaging shoes are commonly lined with wood or other material to increase the coefficient of friction. Disk clutches are based on the principle of multiple-plane friction, and use alternating plates or disks so arranged that one set engages with an outside cylindrical case and the other set with the shaft. When these plates are pressed together by spring pressure, or by other means, motion is transmitted from the driving to the driven members connected to the clutch. Some disk clutches have a few rather heavy or thick plates and others a relatively large number of thinner plates. Clutches of the latter type are common in automobile transmissions. One set of disks may be of soft steel and the other set of phosphor-bronze, or some other combination may be employed. For instance, disks are sometimes provided with cork inserts, or one set or series of disks may be faced with a special friction material such as asbestos-wire fabric, as in "dry plate" clutches, the disks of which are not lubricated like the disks of a clutch having, for example, the steel and phosphor-bronze combination. It is common practice to hold the driving and driven members of friction clutches in engagement by means of spring pressure, although pneumatic or hydraulic pressure may be employed.

Copyright 2004, Industrial Press, Inc., New York, NY

Proportions of Knuckle Joints



For sizes not given below:

$a = 1.2\,D$	$h = 2\,D$
$b = 1.1\,D$	$i = 0.5\,D$
$c = 1.2\,D$	$j = 0.25\,D$
$e = 0.75\,D$	$k = 0.5\,D$
$f = 0.6\,D$	$l = 1.5\,D$
$g = 1.5\,D$	

D	*a*	*b*	*c*	*e*	*f*	*g*	*h*	*i*	*j*	*k*	*l*
1/2	5/8	9/16	5/8	3/8	5/16	3/4	1	1/4	1/8	1/4	3/4
3/4	7/8	3/4	7/8	9/16	7/16	1 1/8	1 1/2	3/8	3/16	3/8	1 1/8
1	1 1/4	1 1/8	1 1/4	3/4	5/8	1 1/2	2	1/2	1/4	1/2	1 1/2
1 1/4	1 1/2	1 3/8	1 1/2	15/16	3/4	1 7/8	2 1/2	5/8	5/16	5/8	1 7/8
1 1/2	1 3/4	1 5/8	1 3/4	1 1/8	7/8	2 1/4	3	3/4	3/8	3/4	2 1/4
1 3/4	2 1/8	2	2 1/8	1 5/16	1 1/16	2 5/8	3 1/2	7/8	7/16	7/8	2 5/8
2	2 3/8	2 1/4	2 3/8	1 1/2	1 3/16	3	4	1	1/2	1	3
2 1/4	2 3/4	2 1/2	2 3/4	1 11/16	1 3/8	3 3/8	4 1/2	1 1/8	9/16	1 1/8	3 3/8
2 1/2	3	2 3/4	3	1 7/8	1 1/2	3 3/4	5	1 1/4	5/8	1 1/4	3 3/4
2 3/4	3 1/4	3	3 1/4	2 1/16	1 5/8	4 1/8	5 1/2	1 3/8	11/16	1 3/8	4 1/8
3	3 5/8	3 1/4	3 5/8	2 1/4	1 13/16	4 1/2	6	1 1/2	3/4	1 1/2	4 1/2
3 1/4	4	3 5/8	4	2 7/16	2	4 7/8	6 1/2	1 5/8	13/16	1 5/8	4 7/8
3 1/2	4 1/4	3 7/8	4 1/4	2 5/8	2 1/8	5 1/4	7	1 3/4	7/8	1 3/4	5 1/4
3 3/4	4 1/2	4 1/8	4 1/2	2 13/16	2 1/4	5 5/8	7 1/2	1 7/8	15/16	1 7/8	5 5/8
4	4 3/4	4 3/8	4 3/4	3	2 3/8	6	8	2	1	2	6
4 1/4	5 1/8	4 3/4	5 1/8	3 3/16	2 9/16	6 3/8	8 1/2	2 1/8	1 1/16	2 1/8	6 3/8
4 1/2	5 1/2	5	5 1/2	3 3/8	2 3/4	6 3/4	9	2 1/4	1 1/8	2 1/4	6 3/4
4 3/4	5 3/4	5 1/4	5 3/4	3 9/16	2 7/8	7 1/8	9 1/2	2 3/8	1 3/16	2 3/8	7 1/8
5	6	5 1/2	6	3 3/4	3	7 1/2	10	2 1/2	1 1/4	2 1/2	7 1/2

Power Transmitting Capacity of Friction Clutches.— When selecting a clutch for a given class of service, it is advisable to consider any overloads that may be encountered and base the power transmitting capacity of the clutch upon such overloads. When the load varies or is subject to frequent release or engagement, the clutch capacity should be greater than the actual amount of power transmitted. If the power is derived from a gas or gasoline engine, the horsepower rating of the clutch should be 75 or 100 per cent greater than that of the engine.

Power Transmitted by Disk Clutches.— The approximate amount of power that a disk clutch will transmit may be determined from the following formula, in which H = horsepower transmitted by the clutch; μ = coefficient of friction; r = mean radius of engaging surfaces; F = axial force in pounds (spring pressure) holding disks in contact; N = number of frictional surfaces; S = speed of shaft in revolutions per minute:

$$H = \frac{\mu r F N S}{63{,}000}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Cast-iron Friction Clutches



For sizes not given below:

$a = 2\,D$
$b = 4$ to $8\,D$
$c = 2\frac{1}{4}\,D$
$t = 1\frac{1}{2}\,D$
$e = \frac{3}{8}\,D$
$h = \frac{1}{2}\,D$
$s = \frac{5}{16}\,D$, nearly
$k = \frac{1}{4}\,D$

Note: The angle ϕ of the cone may be from 4 to 10 degrees

D	*a*	*b*	*c*	*t*	*e*	*h*	*s*	*k*
1	2	4 – 8	2¼	1½	⅜	½	5/16	¼
1¼	2½	5–10	2⅞	1⅞	½	⅝	⅜	5/16
1½	3	6–12	3⅜	2¼	⅝	¾	½	⅜
1¾	3½	7–14	4	2⅝	⅝	⅞	⅝	7/16
2	4	8–16	4½	3	¾	1	⅝	½
2¼	4½	9–18	5	3⅜	⅞	1⅛	⅝	9/16
2½	5	10–20	5⅝	3¾	1	1¼	¾	⅝
2¾	5½	11–22	6¼	4⅛	1	1⅜	⅞	11/16
3	6	12–24	6¾	4½	1⅛	1½	⅞	¾
3¼	6½	13–26	7⅜	4⅞	1¼	1⅝	1	13/16
3½	7	14–28	7⅞	5¼	1⅜	1¾	1	⅞
3¾	7½	15–30	8½	5⅝	1⅜	1⅞	1¼	15/16
4	8	16–32	9	6	1½	2	1¼	1
4¼	8½	17–34	9½	6⅜	1⅝	2⅛	1⅜	1 1/16
4½	9	18–36	10¼	6¾	1¾	2¼	1⅜	1⅛
4¾	9½	19–38	10¾	7⅛	1¾	2⅜	1½	1 3/16
5	10	20–40	11¼	7½	1⅞	2½	1½	1¼
5¼	10½	21–42	11¾	7⅞	2	2⅝	1⅝	1 5/16
5½	11	22–44	12⅜	8¼	2	2¾	1¾	1⅜
5¾	11½	23–46	13	8⅝	2¼	2⅞	1¾	1 7/16
6	12	24–48	13½	9	2¼	3	1⅞	1½

Frictional Coefficients for Clutch Calculations.— While the frictional coefficients used by designers of clutches differ somewhat and depend upon variable factors, the following values may be used in clutch calculations: For greasy leather on cast iron about 0.20 or 0.25, leather on metal that is quite oily 0.15; metal and cork on oily metal 0.32; the same on dry metal 0.35; metal on dry metal 0.15; disk clutches having lubricated surfaces 0.10.

Formulas for Cone Clutches.— In cone clutch design, different formulas have been developed for determining the horsepower transmitted. These formulas, at first sight, do not seem to agree, there being a variation due to the fact that in some of the formulas the friction clutch surfaces are assumed to engage without slip, whereas, in others, some allowance is made for slip. The following formulas include both of these conditions:

H.P. = horsepower transmitted

Copyright 2004, Industrial Press, Inc., New York, NY

N = revolutions per minute
r = mean radius of friction cone, in inches
r_1 = large radius of friction cone, in inches
r_2 = small radius of friction cone, in inches
R_1 = outside radius of leather band, in inches
R_2 = inside radius of leather band, in inches
V = velocity of a point at distance r from the center, in feet per minute
F = tangential force acting at radius r, in pounds
P_n = total normal force between cone surfaces, in pounds
P_s = spring force, in pounds
α = angle of clutch surface with axis of shaft = 7 to 13 degrees
β = included angle of clutch leather, when developed, in degrees
f = coefficient of friction = 0.20 to 0.25 for greasy leather on iron
p = allowable pressure per square inch of leather band = 7 to 8 pounds
W = width of clutch leather, in inches

DEVELOPMENT OF CLUTCH LEATHER



$$R_1 = \frac{r_1}{\sin\alpha} \qquad R_2 = \frac{r_2}{\sin\alpha}$$

$$\beta = \sin\alpha \times 360 \qquad r = \frac{r_1 + r_2}{2}$$

$$V = \frac{2\pi rN}{12}$$

$$F = \frac{\text{HP} \times 33{,}000}{V} \qquad W = \frac{P_n}{2\pi rp} \qquad \text{HP} = \frac{P_n frN}{63{,}025}$$

For engagement with some slip:

$$P_n = \frac{P_s}{\sin\alpha} \qquad P_s = \frac{\text{HP} \times 63{,}025 \sin\alpha}{frN}$$

For engagement without slip:

$$P_n = \frac{P_s}{\sin\alpha + f\cos\alpha} \qquad P_s = \frac{\text{HP} \times 63{,}025(\sin\alpha + f\cos\alpha)}{frN}$$

Angle of Cone.— If the angle of the conical surface of the cone type of clutch is too small, it may be difficult to release the clutch on account of the wedging effect, whereas, if the angle is too large, excessive spring force will be required to prevent slipping. The minimum angle for a leather-faced cone is about 8 or 9 degrees and the maximum angle about 13 degrees. An angle of 12 ½ degrees appears to be the most common and is generally con-

Copyright 2004, Industrial Press, Inc., New York, NY

sidered good practice. These angles are given with relation to the clutch axis and are one-half the included angle.

Magnetic Clutches.— Many disk and other clutches are operated electromagnetically with the magnetic force used only to move the friction disk(s) and the clutch disk(s) into or out of engagement against spring or other pressure. On the other hand, in a magnetic particle clutch, transmission of power is accomplished by magnetizing a quantity of metal particles enclosed between the driving and the driven components. forming a bond between them. Such clutches can be controlled to provide either a rigid coupling or uniform slip, useful in wire drawing and manufacture of cables.

Another type of magnetic clutch uses eddy currents induced in the input member which interact with the field in the output rotor. Torque transmitted is proportional to the coil current, so precise control of torque is provided. A third type of magnetic clutch relies on the hysteresis loss between magnetic fields generated by a coil in an input drum and a close-fitting cup on the output shaft, to transmit torque. Torque transmitted with this type of clutch also is proportional to coil current, so close control is possible.

Permanent-magnet types of clutches also are available, in which the engagement force is exerted by permanent magnets when the electrical supply to the disengagement coils is cut off. These types of clutches have capacities up to five times the torque-to-weight ratio of spring-operated clutches. In addition, if the controls are so arranged as to permit the coil polarity to be reversed instead of being cut off, the combined permanent magnet and electromagnetic forces can transmit even greater torque.

Centrifugal and Free-wheeling Clutches.— Centrifugal clutches have driving members that expand outward to engage a surrounding drum when speed is sufficient to generate centrifugal force. Free-wheeling clutches are made in many different designs and use balls, cams or sprags, ratchets, and fluids to transmit motion from one member to the other. These types of clutches are designed to transmit torque in only one direction and to take up the drive with various degrees of gradualness up to instantaneously.

Slipping Clutch/Couplings.— Where high shock loads are likely to be experienced, a slipping clutch or coupling or both should be used. The most common design uses a clutch plate that is clamped between the driving and driven plates by spring pressure that can be adjusted. When excessive load causes the driven member to slow, the clutch plate surfaces slip, allowing reduction of the torque transmitted. When the overload is removed, the drive is taken up automatically. Switches can be provided to cut off current supply to the driving motor when the driven shaft slows to a preset limit or to signal a warning or both. The slip or overload torque is calculated by taking 150 per cent of the normal running torque.

Wrapped-spring Clutches.— For certain applications, a simple steel spring sized so that its internal diameter is a snug fit on both driving and driven shafts will transmit adequate torque in one direction. The tightness of grip of the spring on the shafts increases as the torque transmitted increases. Disengagement can be effected by slight rotation of the spring, through a projecting tang, using electrical or mechanical means, to wind up the spring to a larger internal diameter, allowing one of the shafts to run free within the spring.

Normal running torque T_r in lb-ft = (required horsepower × 5250) ÷ rpm. For heavy shock load applications, multiply by a 200 per cent or greater overload factor. (See Motors, factors governing selection.)

The clutch starting torque T_c, in lb-ft, required to accelerate a given inertia in a specific time is calculated from the formula:

$$T_c = \frac{WR^2 \times \Delta N}{308t}$$

where WR^2 = total inertia encountered by clutch in lb-ft^2 (W = weight and R = radius of gyration of rotating part)

ΔN = final rpm – initial rpm

Copyright 2004, Industrial Press, Inc., New York, NY

$308 =$ = constant (see *Factors Governing Motor Selection* on page 2473)

t = time to required speed in seconds

Example: If the inertia is 80 lb-ft^2, and the speed of the driven shaft is to be increased from 0 to 1500 rpm in 3 seconds, find the clutch starting torque in lb-ft.

$$T_c = \frac{80 \times 1500}{308 \times 3} = 130 \text{ lb-ft}$$

The heat E, in BTU, generated in one engagement of a clutch can be calculated from the formula:

$$E = \frac{T_c \times WR^2 \times (N_1^2 - N_2^2)}{(T_c - T_1) \times 4.7 \times 10^6}$$

where: WR^2 = total inertia encountered by clutch in lb-ft.^{2}

N_1 = final rpm N_2 = initial rpm

Tc = clutch torque in lb-ft T_1 = torque load in lb-ft

Example: Calculate the heat generated for each engagement under the conditions cited for the first example.

$$E = \frac{130 \times 80 \times (1500)^2}{(130 - 10) \times 4.7 \times 10^6} = 41.5 \text{ BTU}$$

The preferred location for a clutch is on the high- rather than on the low-speed shaft because a smaller-capacity unit, of lower cost and with more rapid dissipation of heat, can be used. However, the heat generated may also be more because of the greater slippage at higher speeds, and the clutch may have a shorter life. For light-duty applications, such as to a machine tool, where cutting occurs after the spindle has reached operating speed, the calculated torque should be multiplied by a safety factor of 1.5 to arrive at the capacity of the clutch to be used. Heavy-duty applications such as frequent starting of a heavily loaded vibratory-finishing barrel require a safety factor of 3 or more.

Positive Clutches.— When the driving and driven members of a clutch are connected by the engagement of interlocking teeth or projecting lugs, the clutch is said to be "positive" to distinguish it from the type in which the power is transmitted by frictional contact. The positive clutch is employed when a sudden starting action is not objectionable and when the inertia of the driven parts is relatively small. The various forms of positive clutches differ merely in the angle or shape of the engaging surfaces. The least positive form is one having planes of engagement which incline backward, with respect to the direction of motion. The tendency of such a clutch is to disengage under load, in which case it must be held in position by axial pressure.



Fig. 1. Types of Clutch Teeth

This pressure may be regulated to perform normal duty, permitting the clutch to slip and disengage when over-loaded. Positive clutches, with the engaging planes parallel to the axis of rotation, are held together to obviate the tendency to jar out of engagement, but they provide no safety feature against over-load. So-called "under-cut" clutches engage more tightly the heavier the load, and are designed to be disengaged only when free from load. The teeth of positive clutches are made in a variety of forms, a few of the more common

Copyright 2004, Industrial Press, Inc., New York, NY

styles being shown in Fig. 1. Clutch *A* is a straight-toothed type, and *B* has angular or saw-shaped teeth. The driving member of the former can be rotated in either direction: the latter is adapted to the transmission of motion in one direction only, but is more readily engaged. The angle θ of the cutter for a saw-tooth clutch *B* is ordinarily 60 degrees. Clutch *C* is similar to *A*, except that the sides of the teeth are inclined to facilitate engagement and disengagement. Teeth of this shape are sometimes used when a clutch is required to run in either direction without backlash. Angle θ is varied to suit requirements and should not exceed 16 or 18 degrees. The straight-tooth clutch A is also modified to make the teeth engage more readily, by rounding the corners of the teeth at the top and bottom. Clutch *D* (commonly called a "spiral-jaw" clutch) differs from *B* in that the surfaces *e* are helicoidal. The driving member of this clutch can transmit motion in only one direction.



Fig. 2. Diagrammatic View Showing Method of Cutting Clutch Teeth



Fig. 3.

Clutches of this type are known as right- and left-hand, the former driving when turning to the right, as indicated by the arrow in the illustration. Clutch *E* is the form used on the backshaft of the Brown & Sharpe automatic screw machines. The faces of the teeth are radial and incline at an angle of 8 degrees with the axis, so that the clutch can readily be disengaged. This type of clutch is easily operated, with little jar or noise. The 2-inch diameter size has 10 teeth. Height of working face, ⅛ inch.

Cutting Clutch Teeth.— A common method of cutting a straight-tooth clutch is indicated by the diagrams *A*, *B* and *C*, Fig. 2, which show the first, second and third cuts required for forming the three teeth. The work is held in the chuck of a dividing-head, the latter being set at right angles to the table. A plain milling cutter may be used (unless the corners of the teeth are rounded), the side of the cutter being set to exactly coincide with the center-line. When the number of teeth in the clutch is odd, the cut can be taken clear across the blank as shown, thus finishing the sides of two teeth with one passage of the cutter. When the number of teeth is even, as at *D*, it is necessary to mill all the teeth on one side and then set the cutter for finishing the opposite side. Therefore, clutches of this type commonly have an odd number of teeth. The maximum width of the cutter depends upon the width of the space at the narrow ends of the teeth. If the cutter must be quite narrow in order to pass the narrow ends, some stock may be left in the tooth spaces, which must be removed by a separate cut. If the tooth is of the modified form shown at *C*, Fig. 1, the cutter should be set as

Copyright 2004, Industrial Press, Inc., New York, NY

indicated in Fig. 3; that is, so that a point a on the cutter at a radial distance *d* equal to one-half the depth of the clutch teeth lies in a radial plane. When it is important to eliminate all backlash, point *a* is sometimes located at a radial distance *d* equal to six-tenths of the depth of the tooth, in order to leave clearance spaces at the bottoms of the teeth; the two clutch members will then fit together tightly. Clutches of this type must be held in mesh.



Fig. 4.

Angle of Dividing-head for Milling V-shaped Teeth with Single-angle Cutter



$$\cos\alpha = \frac{\tan(360°/N) \times \cot\theta}{2}$$

α is the angle shown in Fig. 4 and is the angle shown by the graduations on the dividing head. θ is the included angle of a single cutter, see Fig. 1.

No. of Teeth, *N*	Angle of Single-angle Cutter, θ						No. of Teeth, *N*	Angle of Single-angle Cutter, θ					
	60°		70°		80°			60°		70°		80°	
	Dividing Head Angle, α							Dividing Head Angle, α					
5	27°	19.2′	55°	56.3′	74°	15.4′	18	83°	58.1′	86°	12.1′	88°	9.67′
6	60		71	37.6	81	13	19	84	18.8	86	25.1	88	15.9
7	68	46.7	76	48.5	83	39.2	20	84	37.1	86	36.6	88	21.5
8	73	13.3	79	30.9	84	56.5	21	84	53.5	86	46.9	88	26.5
9	75	58.9	81	13	85	45.4	22	85	8.26	86	56.2	88	31
10	77	53.6	82	24.1	86	19.6	23	85	21.6	87	4.63	88	35.1
11	79	18.5	83	17	86	45.1	24	85	33.8	87	12.3	88	38.8
12	80	24.4	83	58.1	87	4.94	25	85	45	87	19.3	88	42.2
13	81	17.1	84	31.1	87	20.9	26	85	55.2	87	25.7	88	45.3
14	82	.536	84	58.3	87	34	27	86	4.61	87	31.7	88	48.2
15	82	36.9	85	21.2	87	45	28	86	13.3	87	37.2	88	50.8
16	83	7.95	85	40.6	87	54.4	29	86	21.4	87	42.3	88	53.3
17	83	34.7	85	57.4	88	2.56	30	86	28.9	87	47	88	55.6

Cutting Saw-tooth Clutches: When milling clutches having angular teeth as shown at *B*, Fig. 1, the axis of the clutch blank should be inclined a certain angle α as shown at *A* in Fig. 4. If the teeth were milled with the blank vertical, the tops of the teeth would incline towards the center as at *D*, whereas, if the blank were set to such an angle that the tops of the teeth were square with the axis, the bottoms would incline upwards as at *E*. In either case,

Copyright 2004, Industrial Press, Inc., New York, NY

the two clutch members would not mesh completely: the engagement of the teeth cut as shown at D and E would be as indicated at D_1 and E_1 respectively. As will be seen, when the outer points of the teeth at D_1 are at the bottom of the grooves in the opposite member, the inner ends are not together, the contact area being represented by the dotted lines. At E_1 the inner ends of the teeth strike first and spaces are left between the teeth around the outside of the clutch. To overcome this objectionable feature, the clutch teeth should be cut as indicated at B, or so that the bottoms and tops of the teeth have the same inclination, converging at a central point x. The teeth of both members will then engage across the entire width as shown at C. The angle α required for cutting a clutch as at B can be determined by the following formula in which α equals the required angle, N = number of teeth, θ = cutter angle, and $360°/N$ = angle between teeth:

$$\cos\alpha = \frac{\tan(360°/N) \times \cot\theta}{2}$$

The angles α for various numbers of teeth and for 60-, 70- or 80-degree single-angle cutters are given in the table on page 2356. The following table is for double-angle cutters used to cut V-shaped teeth.

Angle of Dividing-head for Milling V-shaped Teeth with Double-angle Cutter



$$\cos\alpha = \frac{\tan(180°/N) \times \cot(\theta/2)}{2}$$

This is the angle (α, Fig. 4) shown by graduations on the dividing-head. θ is the included angle of a double-angle cutter, see Fig. 1.

No. of Teeth, N	Included Angle of Cutter, θ				No. of Teeth, N	Included Angle of Cutter, θ			
	60°		90°			60°		90°	
	Dividing Head Angle, α					Dividing Head Angle, α			
10	73°	39.4′	80°	39′	31	84°	56.9′	87°	5.13′
11	75	16.1	81	33.5	32	85	6.42	87	10.6
12	76	34.9	82	18	33	85	15.4	87	15.8
13	77	40.5	82	55.3	34	85	23.8	87	20.7
14	78	36	83	26.8	35	85	31.8	87	25.2
15	79	23.6	83	54	36	85	39.3	87	29.6
16	80	4.83	84	17.5	37	85	46.4	87	33.7
17	80	41	84	38.2	38	85	53.1	87	37.5
18	81	13	84	56.5	39	85	59.5	87	41.2
19	81	41.5	85	12.8	40	86	5.51	87	44.7
20	82	6.97	85	27.5	41	86	11.3	87	48
21	82	30	85	40.7	42	86	16.7	87	51.2
22	82	50.8	85	52.6	43	86	22	87	54.2
23	83	9.82	86	3.56	44	86	26.9	87	57
24	83	27.2	86	13.5	45	86	31.7	87	59.8
25	83	43.1	86	22.7	46	86	36.2	88	2.4
26	83	57.8	26	31.2	47	86	40.6	88	4.91
27	84	11.4	86	39	48	86	44.8	88	7.32
28	84	24	86	46.2	49	86	48.8	88	9.63
29	84	35.7	86	53	50	86	52.6	88	11.8
30	84	46.7	86	59.3	51	86	56.3	88	14

The angles given in the table above are applicable to the milling of V-shaped grooves in brackets, etc., which must have toothed surfaces to prevent the two members from turning relative to each other, except when unclamped for angular adjustment

Copyright 2004, Industrial Press, Inc., New York, NY

FRICTION BRAKES

Formulas for Band Brakes.— In any band brake, such as shown in Fig. 1, in the tabulation of formulas, where the brake wheel rotates in a clockwise direction, the tension in that part of the band marked x equals $P\frac{1}{e^{\mu\theta}-1}$

The tension in that part marked y equals $P\frac{e^{\mu\theta}}{e^{\mu\theta}-1}$.

P = tangential force in pounds at rim of brake wheel

e = base of natural logarithms = 2.71828

μ = coefficient of friction between the brake band and the brake wheel

θ = angle of contact of the brake band with the brake wheel expressed in radians (one radian $= \frac{180 \text{ deg.}}{\pi \text{ radians}} = 57.296\frac{\text{deg.}}{\text{radian}}$).

For simplicity in the formulas presented, the tensions at x and y (Fig. 1) are denoted by T_1 and T_2 respectively, for clockwise rotation. When the direction of the rotation is reversed, the tension in x equals T_2, and the tension in y equals T_1, which is the reverse of the tension in the clockwise direction.

The value of the expression $e^{\mu\theta}$ in these formulas may be most easily found by using a hand-held calculator of the scientific type; that is, one capable of raising 2.71828 to the power $\mu\theta$. The following example outlines the steps in the calculations.

Table of Values of $e^{\mu\theta}$

Proportion of Contact to Whole Circumference, $\frac{\theta}{2\pi}$	Steel Band on Cast Iron, $\mu = 0.18$	Leather Belt on Wood	Leather Belt on Cast Iron		
		Slightly Greasy; $\mu = 0.47$	Very Greasy; $\mu = 0.12$	Slightly Greasy; $\mu = 0.28$	Damp; $\mu = 0.38$
0.1	1.12	1.34	1.08	1.19	1.27
0.2	1.25	1.81	1.16	1.42	1.61
0.3	1.40	2.43	1.25	1.69	2.05
0.4	1.57	3.26	1.35	2.02	2.60
0.425	1.62	3.51	1.38	2.11	2.76
0.45	1.66	3.78	1.40	2.21	2.93
0.475	1.71	4.07	1.43	2.31	3.11
0.5	1.76	4.38	1.46	2.41	3.30
0.525	1.81	4.71	1.49	2.52	3.50
0.55	1.86	5.07	1.51	2.63	3.72
0.6	1.97	5.88	1.57	2.81	4.19
0.7	2.21	7.90	1.66	3.43	5.32
0.8	2.47	10.60	1.83	4.09	6.75
0.9	2.77	14.30	1.97	4.87	8.57
1.0	3.10	19.20	2.12	5.81	10.90

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for Simple and Differential Band Brakes

F = force in pounds at end of brake handle; P = tangential force in pounds at rim of brake wheel; e = base of natural logarithms = 2.71828; μ = coefficient of friction between the brake band and the brake wheel; θ = angle of contact of the brake band with the brake wheel, expressed in radians (one radian = 57.296 degrees).

$$T_1 = P\frac{1}{e^{\mu\theta}-1} \qquad T_2 = P\frac{e^{\mu\theta}}{e^{\mu\theta}-1}$$

Simple Band Brake



Fig. 1.

For clockwise rotation:

$$F = \frac{bT_2}{a} = \frac{Pb}{a}\left(\frac{e^{\mu\theta}}{e^{\mu\theta}-1}\right)$$

For counter clockwise rotation:

$$F = \frac{bT_1}{a} = \frac{Pb}{a}\left(\frac{1}{e^{\mu\theta}-1}\right)$$



Fig. 2.

For clockwise rotation:

$$F = \frac{bT_1}{a} = \frac{Pb}{a}\left(\frac{1}{e^{\mu\theta}-1}\right)$$

For counter clockwise rotation:

$$F = \frac{bT_2}{a} = \frac{Pb}{a}\left(\frac{e^{\mu\theta}}{e^{\mu\theta}-1}\right)$$

Differential Band Brake



Fig. 3.

For clockwise rotation:

$$F = \frac{b_2T_2 - b_1T_1}{a} = \frac{P}{a}\left(\frac{b_2e^{\mu\theta} - b_1}{e^{\mu\theta}-1}\right)$$

For counter clockwise rotation:

$$F = \frac{b_2T_1 - b_1T_2}{a} = \frac{P}{a}\left(\frac{b_2 - b_1e^{\mu\theta}}{e^{\mu\theta}-1}\right)$$

In this case, if b_2 is equal to, or less than, $b_1e^{\mu\theta}$, the force F will be 0 or negative and the band brake works automatically.



Fig. 4.

For clockwise rotation:

$$F = \frac{b_2T_2 + b_1T_1}{a} = \frac{P}{a}\left(\frac{b_2e^{\mu\theta} + b_1}{e^{\mu\theta}-1}\right)$$

For counter clockwise rotation:

$$F = \frac{b_1T_2 + b_2T_1}{a} = \frac{P}{a}\left(\frac{b_1e^{\mu\theta} + b_2}{e^{\mu\theta}-1}\right)$$

If $b_2 = b_1$, both of the above formulas reduce to $F = \frac{Pb_1}{a}\left(\frac{e^{\mu\theta}+1}{e^{\mu\theta}-1}\right)$.

In this case, the same force F is required for rotation in either direction.

Example: In a band brake of the type in Fig. 1, dimension $a = 24$ inches, and $b = 4$ inches; force $P = 100$ pounds; coefficient $\mu = 0.2$, and angle of contact = 240 degrees, or

$$\theta = \frac{240}{180} \times \pi = 4.18$$

Copyright 2004, Industrial Press, Inc., New York, NY

The rotation is clockwise. Find force F required.

$$F = \frac{Pb}{a}\left(\frac{e^{\mu\theta}}{e^{\mu\theta}-1}\right)$$

$$= \frac{100\times 4}{24}\left(\frac{2.71828^{0.2\times 4.18}}{2.71828^{0.2\times 4.18}-1}\right)$$

$$= \frac{400}{24}\times\frac{2.71828^{0.836}}{2.71828^{0.836}-1} = 16.66\times\frac{2.31}{2.31-1} = 29.4$$

If a hand-held calculator is not used, determining the value of $e^{\mu\theta}$ is rather tedious, and the table on page 2358 will save calculations.

Coefficient of Friction in Brakes.— The coefficients of friction that may be assumed for friction brake calculations are as follows: Iron on iron, 0.25 to 0.3 leather on iron, 0.3; cork on iron, 0.35. Values somewhat lower than these should be assumed when the velocities exceed 400 feet per minute at the beginning of the braking operation.

For brakes where wooden brake blocks are used on iron drums, poplar has proved the best brake-block material. The best material for the brake drum is wrought iron. Poplar gives a high coefficient of friction, and is little affected by oil. The average coefficient of friction for poplar brake blocks and wrought-iron drums is 0.6; for poplar on cast iron, 0.35 for oak on wrought iron, 0.5; for oak on cast iron, 0.3; for beech on wrought iron, 0.5; for beech on cast iron, 0.3; for elm on wrought iron, 0.6; and for elm on cast iron, 0.35. The objection to elm is that the friction decreases rapidly if the friction surfaces are oily. The coefficient of friction for elm and wrought iron, if oily, is less than 0.4.

Calculating Horsepower from Dynamometer Tests.— When a dynamometer is arranged for measuring the horsepower transmitted by a shaft, as indicated by the diagrammatic view in Fig. 5, the horsepower may be obtained by the formula:

$$\text{HP} = \frac{2\pi LPN}{33000}$$

in which H.P. = horsepower transmitted; N = number of revolutions per minute; L = distance (as shown in illustration) from center of pulley to point of action of weight P, in feet; P = weight hung on brake arm or read on scale.



Fig. 5.

By adopting a length of brake arm equal to 5 feet 3 inches, the formula may be reduced to the simple form:

$$\text{HP} = \frac{NP}{1000}$$

If a length of brake arm equal to 2 feet 7½ inches is adopted as a standard, the formula takes the form:

$$\text{HP} = \frac{NP}{2000}$$

The *transmission* type of dynamometer measures the power by transmitting it through the mechanism of the dynamometer from the apparatus in which it is generated, or to the

Copyright 2004, Industrial Press, Inc., New York, NY

apparatus in which it is to be utilized. Dynamometers known as *indicators* operate by simultaneously measuring the pressure and volume of a confined fluid. This type may be used for the measurement of the power generated by steam or gas engines or absorbed by refrigerating machinery, air compressors, or pumps. An electrical dynamometer is for measuring the power of an electric current, based on the mutual action of currents flowing in two coils. It consists principally of one fixed and one movable coil, which, in the normal position, are at right angles to each other. Both coils are connected in series, and, when a current traverses the coils, the fields produced are at right angles; hence, the coils tend to take up a parallel position. The movable coil with an attached pointer will be deflected, the deflection measuring directly the electric current.

Formulas for Block Brakes

F = force in pounds at end of brake handle;
P = tangential force in pounds at rim of brake wheel;
μ = coefficient of friction between the brake block and brake wheel.



Fig. 1.

Block brake.
For rotation in either direction:

$$F = P\frac{b}{a+b} \times \frac{1}{\mu} = \frac{Pb}{a+b}\left(\frac{1}{\mu}\right)$$



Fig. 2.

Block brake.
For clockwise rotation:

$$F = \frac{\frac{Pb}{\mu} - Pc}{a+b} = \frac{Pb}{a+b}\left(\frac{1}{\mu} - \frac{c}{b}\right)$$

For counter clockwise rotation:

$$F = \frac{\frac{Pb}{\mu} + Pc}{a+b} = \frac{Pb}{a+b}\left(\frac{1}{\mu} + \frac{c}{b}\right)$$



Fig. 3.

Block brake.
For clockwise rotation:

$$F = \frac{\frac{Pb}{\mu} + Pc}{a+b} = \frac{Pb}{a+b}\left(\frac{1}{\mu} + \frac{c}{b}\right)$$

For counter clockwise rotation:

$$F = \frac{\frac{Pb}{\mu} - Pc}{a+b} = \frac{Pb}{a+b}\left(\frac{1}{\mu} - \frac{c}{b}\right)$$


Fig. 4.

The brake wheel and friction block of the block brake are often grooved as shown in Fig. 4. In this case, substitute for μ in the above equations the value $\frac{\mu}{\sin\alpha + \mu\cos\alpha}$ where α is one-half the angle included by the facts of the grooves.

Friction Wheels for Power Transmission

When a rotating member is driven intermittently and the rate of driving does not need to be positive, friction wheels are frequently used, especially when the amount of power to be transmitted is comparatively small. The driven wheels in a pair of friction disks should always be made of a harder material than the driving wheels, so that if the driven wheel

Copyright 2004, Industrial Press, Inc., New York, NY

should be held stationary by the load, while the driving wheel revolves under its own pressure, a flat spot may not be rapidly worn on the driven wheel. The driven wheels, therefore, are usually made of iron, while the driving wheels are made of or covered with, rubber, paper, leather, wood or fiber. The safe working force per inch of face width of contact for various materials are as follows: Straw fiber, 150; leather fiber, 240; tarred fiber, 240; leather, 150; wood, 100 to 150; paper, 150. Coefficients of friction for different combinations of materials are given in the following table. Smaller values should be used for exceptionally high speeds, or when the transmission must be started while under load.

Horsepower of Friction Wheels.— Let D = diameter of friction wheel in inches; N = Number of revolutions per minute; W = width of face in inches; f = coefficient of friction; P = force in pounds, per inch width of face. Then:

$$\text{H.P.} = \frac{3.1416 \times D \times N \times P \times W \times f}{33{,}000 \times 12}$$

Assume

$$\frac{3.1416 \times P \times f}{33{,}000 \times 12} = C$$

then,

for $P = 100$ and $f = 0.20$, $C = 0.00016$

for $P = 150$ and $f = 0.20$, $C = 0.00024$

for $P = 200$ and $f = 0.20$, $C = 0.00032$

Working Values of Coefficient of Friction

Materials	Coefficient of Friction	Materials	Coefficient of Friction
Straw fiber and cast iron	0.26	Tarred fiber and aluminum	0.18
Straw fiber and aluminum	0.27	Leather and cast iron	0.14
Leather fiber and cast iron	0.31	Leather and aluminum	0.22
Leather fiber and aluminum	0.30	Leather and typemetal	0.25
Tarred fiber and cast iron	0.15	Wood and metal	0.25
Paper and cast iron	0.20		

The horsepower transmitted is then:

$$\text{HP} = D \times N \times W \times C$$

Example: Find the horsepower transmitted by a pair of friction wheels; the diameter of the driving wheel is 10 inches, and it revolves at 200 revolutions per minute. The width of the wheel is 2 inches. The force per inch width of face is 150 pounds, and the coefficient of friction 0.20.

$$\text{HP} = 10 \times 200 \times 2 \times 0.00024 = 0.96 \text{ horsepower}$$

Horsepower Which May be Transmitted by Means of a Clean Paper Friction Wheel of One-inch Face when Run Under a Force of 150 Pounds (Rockwood Mfg. Co.)

Dia. of FrictionWheel	Revolutions per Minute										
	25	50	75	100	150	200	300	400	600	800	1000
4	0.023	0.047	0.071	0.095	0.142	0.190	0.285	0.380	0.571	0.76	0.95
6	0.035	0.071	0.107	0.142	0.214	0.285	0.428	0.571	0.856	1.14	1.42
8	0.047	0.095	0.142	0.190	0.285	0.380	0.571	0.761	1.142	1.52	1.90
10	0.059	0.119	0.178	0.238	0.357	0.476	0.714	0.952	1.428	1.90	2.38
14	0.083	0.166	0.249	0.333	0.499	0.666	0.999	1.332	1.999	2.66	3.33
16	0.095	0.190	0.285	0.380	0.571	0.761	1.142	1.523	2.284	3.04	3.80
18	0.107	0.214	0.321	0.428	0.642	0.856	1.285	1.713	2.570	3.42	4.28
24	0.142	0.285	0.428	0.571	0.856	1.142	1.713	2.284	3.427	4.56	5.71
30	0.178	0.357	0.535	0.714	1.071	1.428	2.142	2.856	4.284	5.71	7.14
36	0.214	0.428	0.642	0.856	1.285	1.713	2.570	3.427	5.140	6.85	8.56
42	0.249	0.499	0.749	0.999	1.499	1.999	2.998	3.998	5.997	7.99	9.99
48	0.285	0.571	0.856	1.142	1.713	2.284	3.427	4.569	6.854	9.13	11.42
50	0.297	0.595	0.892	1.190	1.785	2.380	3.570	4.760	7.140	9.52	11.90

Copyright 2004, Industrial Press, Inc., New York, NY

KEYS AND KEYSEATS

ANSI Standard Keys and Keyseats.— American National Standard, B17.1 Keys and Keyseats, based on current industry practice, was approved in 1967, and reaffirmed in 1989. This standard establishes a uniform relationship between shaft sizes and key sizes for parallel and taper keys as shown in Table 1. Other data in this standard are given in Tables 2 and 3 through 7. The sizes and tolerances shown are for single key applications only.

The following definitions are given in the standard:

Key: A demountable machinery part which, when assembled into keyseats, provides a positive means for transmitting torque between the shaft and hub.

Keyseat: An axially located rectangular groove in a shaft or hub.

This standard recognizes that there are two classes of stock for parallel keys used by industry. One is a close, plus toleranced key stock and the other is a broad, negative toleranced bar stock. Based on the use of two types of stock, two classes of fit are shown:

Class 1: A clearance or metal-to-metal side fit obtained by using bar stock keys and keyseat tolerances as given in Table 4. This is a relatively free fit and applies only to parallel keys.

Class 2: A side fit, with possible interference or clearance, obtained by using key stock and keyseat tolerances as given in Table 4. This is a relatively tight fit.

Class 3: This is an interference side fit and is not tabulated in Table 4 since the degree of interference has not been standardized. However, it is suggested that the top and bottom fit range given under Class 2 in Table 4, for parallel keys be used.

Table 1. Key Size Versus Shaft Diameter *ANSI B17.1-1967 (R1998)*

Nominal Shaft Diameter		Nominal Key Size			Normal Keyseat Depth	
			Height, *H*		*H*/2	
Over	To (Incl.)	Width, *W*	Square	Rectangular	Square	Rectangular
5/16	7/16	3/32	3/32	...	3/64	...
7/16	9/16	1/8	1/8	3/32	1/16	3/64
9/16	7/8	3/16	3/16	1/8	3/32	1/16
7/8	1 1/4	1/4	1/4	3/16	1/8	3/32
1 1/4	1 3/8	5/16	5/16	1/4	5/32	1/8
1 3/8	1 3/4	3/8	3/8	1/4	3/16	1/8
1 3/4	2 1/4	1/2	1/2	3/8	1/4	3/16
2 1/4	2 3/4	5/8	5/8	7/16	5/16	7/32
2 3/4	3 1/4	3/4	3/4	1/2	3/8	1/4
3 1/4	3 3/4	7/8	7/8	5/8	7/16	5/16
3 3/4	4 1/2	1	1	3/4	1/2	3/8
4 1/2	5 1/2	1 1/4	1 1/4	7/8	5/8	7/16
5 1/2	6 1/2	1 1/2	1 1/2	1	3/4	1/2
Square Keys preferred for shaft diameters above this line; rectangular keys, below						
6 1/2	7 1/2	1 3/4	1 3/4	1 1/2[a]	7/8	3/4
7 1/2	9	2	2	1 1/2	1	3/4
9	11	2 1/2	2 1/2	1 3/4	1 1/4	7/8

[a] Some key standards show 1 1/4 inches; preferred height is 1 1/2 inches.

All dimensions are given in inches. For larger shaft sizes, see *ANSI Standard Woodruff Keys and Keyseats*.

Key Size vs. Shaft Diameter: Shaft diameters are listed in Table 1 for identification of various key sizes and are not intended to establish shaft dimensions, tolerances or selections. For a stepped shaft, the size of a key is determined by the diameter of the shaft at the

Copyright 2004, Industrial Press, Inc., New York, NY

point of location of the key. Up through 6½-inch diameter shafts square keys are preferred; rectangular keys are preferred for larger shafts.

If special considerations dictate the use of a keyseat in the hub shallower than the preferred nominal depth shown, it is recommended that the tabulated preferred nominal standard keyseat always be used in the shaft.

Keyseat Alignment Tolerances: A tolerance of 0.010 inch, max is provided for offset (due to parallel displacement of keyseat centerline from centerline of shaft or bore) of keyseats in shaft and bore. The following tolerances for maximum lead (due to angular displacement of keyseat centerline from centerline of shaft or bore and measured at right angles to the shaft or bore centerline) of keyseats in shaft and bore are specified: 0.002 inch for keyseat length up to and including 4 inches; 0.0005 inch per inch of length for keyseat lengths above 4 inches to and including 10 inches; and 0.005 inch for keyseat lengths above 10 inches. For the effect of keyways on shaft strength, see *Effect of Keyways on Shaft Strength* on page 305.



Table 2. Depth Control Values *S* and *T* for Shafts and Hub
ANSI B17.1-1967 (R1998)

Nominal Shaft Diameter	Shafts, Parallel and Taper		Hubs, Parallel		Hubs, Taper	
	Square	Rectangular	Square	Rectangular	Square	Rectangular
	S	*S*	*T*	*T*	*T*	*T*
1/2	0.430	0.445	0.560	0.544	0.535	0.519
9/16	0.493	0.509	0.623	0.607	0.598	0.582
5/8	0.517	0.548	0.709	0.678	0.684	0.653
11/16	0.581	0.612	0.773	0.742	0.748	0.717
3/4	0.644	0.676	0.837	0.806	0.812	0.781
13/16	0.708	0.739	0.900	0.869	0.875	0.844
7/8	0.771	0.802	0.964	0.932	0.939	0.907
15/16	0.796	0.827	1.051	1.019	1.026	0.994
1	0.859	0.890	1.114	1.083	1.089	1.058
1 1/16	0.923	0.954	1.178	1.146	1.153	1.121
1 1/8	0.986	1.017	1.241	1.210	1.216	1.185
1 3/16	1.049	1.080	1.304	1.273	1.279	1.248
1 1/4	1.112	1.144	1.367	1.336	1.342	1.311
1 5/16	1.137	1.169	1.455	1.424	1.430	1.399
1 3/8	1.201	1.232	1.518	1.487	1.493	1.462
1 7/16	1.225	1.288	1.605	1.543	1.580	1.518
1 1/2	1.289	1.351	1.669	1.606	1.644	1.581
1 9/16	1.352	1.415	1.732	1.670	1.707	1.645
1 5/8	1.416	1.478	1.796	1.733	1.771	1.708
1 11/16	1.479	1.541	1.859	1.796	1.834	1.771
1 3/4	1.542	1.605	1.922	1.860	1.897	1.835
1 13/16	1.527	1.590	2.032	1.970	2.007	1.945
1 7/8	1.591	1.654	2.096	2.034	2.071	2.009
1 15/16	1.655	1.717	2.160	2.097	2.135	2.072
2	1.718	1.781	2.223	2.161	2.198	2.136
2 1/16	1.782	1.844	2.287	2.224	2.262	2.199
2 1/8	1.845	1.908	2.350	2.288	2.325	2.263
2 3/16	1.909	1.971	2.414	2.351	2.389	2.326
2 1/4	1.972	2.034	2.477	2.414	2.452	2.389
2 5/16	1.957	2.051	2.587	2.493	2.562	2.468
2 3/8	2.021	2.114	2.651	2.557	2.626	2.532

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ***(Continued)*** **Depth Control Values *S* and *T* for Shaft and Hub**
ANSI B17.1-1967 (R1998)

Nominal Shaft Diameter	Shafts, Parallel and Taper		Hubs, Parallel		Hubs, Taper	
	Square	Rectangular	Square	Rectangular	Square	Rectangular
	S	*S*	*T*	*T*	*T*	*T*
2 7/16	2.084	2.178	2.714	2.621	2.689	2.596
2 1/2	2.148	2.242	2.778	2.684	2.753	2.659
2 9/16	2.211	2.305	2.841	2.748	2.816	2.723
2 5/8	2.275	2.369	2.905	2.811	2.880	2.786
2 11/16	2.338	2.432	2.968	2.874	2.943	2.849
2 3/4	2.402	2.495	3.032	2.938	3.007	2.913
2 13/16	2.387	2.512	3.142	3.017	3.117	2.992
2 7/8	2.450	2.575	3.205	3.080	3.180	3.055
2 15/16	2.514	2.639	3.269	3.144	3.244	3.119
3	2.577	2.702	3.332	3.207	3.307	3.182
3 1/16	2.641	2.766	3.396	3.271	3.371	3.246
3 1/8	2.704	2.829	3.459	3.334	3.434	3.309
3 3/16	2.768	2.893	3.523	3.398	3.498	3.373
3 1/4	2.831	2.956	3.586	3.461	3.561	3.436
3 5/16	2.816	2.941	3.696	3.571	3.671	3.546
3 3/8	2.880	3.005	3.760	3.635	3.735	3.610
3 7/16	2.943	3.068	3.823	3.698	3.798	3.673
3 1/2	3.007	3.132	3.887	3.762	3.862	3.737
3 9/16	3.070	3.195	3.950	3.825	3.925	3.800
3 5/8	3.134	3.259	4.014	3.889	3.989	3.864
3 11/16	3.197	3.322	4.077	3.952	4.052	3.927
3 3/4	3.261	3.386	4.141	4.016	4.116	3.991
3 13/16	3.246	3.371	4.251	4.126	4.226	4.101
3 7/8	3.309	3.434	4.314	4.189	4.289	4.164
3 15/16	3.373	3.498	4.378	4.253	4.353	4.228
4	3.436	3.561	4.441	4.316	4.416	4.291
4 3/16	3.627	3.752	4.632	4.507	4.607	4.482
4 1/4	3.690	3.815	4.695	4.570	4.670	4.545
4 3/8	3.817	3.942	4.822	4.697	4.797	4.672
4 7/16	3.880	4.005	4.885	4.760	4.860	4.735
4 1/2	3.944	4.069	4.949	4.824	4.924	4.799
4 3/4	4.041	4.229	5.296	5.109	5.271	5.084
4 7/8	4.169	4.356	5.424	5.236	5.399	5.211
4 15/16	4.232	4.422	5.487	5.300	5.462	5.275
5	4.296	4.483	5.551	5.363	5.526	5.338
5 3/16	4.486	4.674	5.741	5.554	5.716	5.529
5 1/4	4.550	4.737	5.805	5.617	5.780	5.592
5 7/16	4.740	4.927	5.995	5.807	5.970	5.782
5 1/2	4.803	4.991	6.058	5.871	6.033	5.846
5 3/4	4.900	5.150	6.405	6.155	6.380	6.130
5 15/16	5.091	5.341	6.596	6.346	6.571	6.321
6	5.155	5.405	6.660	6.410	6.635	6.385
6 1/4	5.409	5.659	6.914	6.664	6.889	6.639
6 1/2	5.662	5.912	7.167	6.917	7.142	6.892
6 3/4	5.760	[a]5.885	7.515	[a]7.390	7.490	[a]7.365
7	6.014	[a]6.139	7.769	[a]7.644	7.744	[a]7.619
7 1/4	6.268	[a]6.393	8.023	[a]7.898	7.998	[a]7.873
7 1/2	6.521	[a]6.646	8.276	[a]8.151	8.251	[a]8.126
7 3/4	6.619	6.869	8.624	8.374	8.599	8.349
8	6.873	7.123	8.878	8.628	8.853	8.603
9	7.887	8.137	9.892	9.642	9.867	9.617
10	8.591	8.966	11.096	10.721	11.071	10.696
11	9.606	9.981	12.111	11.736	12.086	11.711
12	10.309	10.809	13.314	12.814	13.289	12.789
13	11.325	11.825	14.330	13.830	14.305	13.805
14	12.028	12.528	15.533	15.033	15.508	15.008
15	13.043	13.543	16.548	16.048	16.523	16.023

[a] 1¾ × 1½ inch key.
All dimensions are given in inches. See Table 4 for tolerances.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. ANSI Standard Plain and Gib Head Keys *ANSI B17.1-1967 (R1998)*



Key			Nominal Key Size Width *W* Over	Nominal Key Size Width *W* To (Incl.)	Tolerance Width, *W*		Tolerance Height, *H*	
Parallel	Square	Keystock	…	1¼	+0.001	−0.000	+0.001	−0.000
			1¼	3	+0.002	−0.000	+0.002	−0.000
			3	3½	+0.003	−0.000	+0.003	−0.000
		Bar Stock	…	¾	+0.000	−0.002	+0.000	−0.002
			¾	1½	+0.000	−0.003	+0.000	−0.003
			1½	2½	+0.000	−0.004	+0.000	−0.004
			2½	3½	+0.000	−0.006	+0.000	−0.006
	Rectangular	Keystock	…	1¼	+0.001	−0.000	+0.005	−0.005
			1¼	3	+0.002	−0.000	+0.005	−0.005
			3	7	+0.003	−0.000	+0.005	−0.005
		Bar Stock	…	¾	+0.000	−0.003	+0.000	−0.003
			¾	1½	+0.000	−0.004	+0.000	−0.004
			1½	3	+0.000	−0.005	+0.000	−0.005
			3	4	+0.000	−0.006	+0.000	−0.006
			4	6	+0.000	−0.008	+0.000	−0.008
			6	7	+0.000	−0.013	+0.000	−0.013
Taper	Plain or Gib Head Square or Rectangular		…	1¼	+0.001	−0.000	+0.005	−0.000
			1¼	3	+0.002	−0.000	+0.005	−0.000
			3	7	+0.003	−0.000	+0.005	−0.000

Gib Head Nominal Dimensions

Nominal Key Size Width, *W*	Square *H*	Square *A*	Square *B*	Rectangular *H*	Rectangular *A*	Rectangular *B*	Nominal Key Size Width, *W*	Square *H*	Square *A*	Square *B*	Rectangular *H*	Rectangular *A*	Rectangular *B*
⅛	⅛	¼	¼	3/32	3/16	⅛	1	1	1⅝	1⅛	¾	1¼	⅞
3/16	3/16	5/16	5/16	⅛	¼	¼	1¼	1¼	2	1 7/16	⅞	1⅜	1
¼	¼	7/16	⅜	3/16	5/16	5/16	1½	1½	2⅜	1¾	1	1⅝	1⅛
5/16	5/16	½	7/16	¼	7/16	⅜	1¾	1¾	2¾	2	1½	2⅜	1¾
⅜	⅜	⅝	½	¼	7/16	⅜	2	2	3½	2¼	1½	2⅜	1¾
½	½	⅞	⅝	⅜	⅝	½	2½	2½	4	3	1¾	2¾	2
⅝	⅝	1	¾	7/16	¾	9/16	3	3	5	3½	2	3½	2¼
¾	¾	1¼	⅞	½	⅞	⅝	3½	3½	6	4	2½	4	3
⅞	⅞	1⅜	1	⅝	1	¾	…	…	…	…	…	…	…

All dimensions are given in inches.

*For locating position of dimension *H*. Tolerance does not apply.

For larger sizes the following relationships are suggested as guides for establishing *A* and *B*: A = 1.8*H* and *B* = 1.2*H*.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ANSI Standard Fits for Parallel and Taper Keys *ANSI B17.1-1967 (R1998)*

Type of Key	Key Width		Side Fit			Top and Bottom Fit			
			Width Tolerance		Fit Range[a]	Depth Tolerance			Fit Range[a]
	Over	To (Incl.)	Key	Key-Seat		Key	Shaft Key-Seat	Hub Key-Seat	
Class 1 Fit for Parallel Keys									
Square	…	1/2	+0.000	+0.002	0.004 CL	+0.000	+0.000	+0.010	0.032 CL
			–0.002	–0.000	0.000	–0.002	–0.015	–0.000	0.005 CL
	1/2	3/4	+0.000	+0.003	0.005 CL	+0.000	+0.000	+0.010	0.032 CL
			–0.002	–0.000	0.000	–0.002	–0.015	–0.000	0.005 CL
	3/4	1	+0.000	+0.003	0.006 CL	+0.000	+0.000	+0.010	0.033 CL
			–0.003	–0.000	0.000	–0.003	–0.015	–0.000	0.005 CL
	1	1 1/2	+0.000	+0.004	0.007 CL	+0.000	+0.000	+0.010	0.033 CL
			–0.003	–0.000	0.000	–0.003	–0.015	–0.000	0.005 CL
	1 1/2	2 1/2	+0.000	+0.004	0.008 CL	+0.000	+0.000	+0.010	0.034 CL
			–0.004	–0.000	0.000	–0.004	–0.015	–0.000	0.005 CL
	2 1/2	3 1/2	+0.000	+0.004	0.010 CL	+0.000	+0.000	+0.010	0.036 CL
			–0.006	–0.000	0.000	–0.006	–0.015	–0.000	0.005 CL
Rectangular	…	1/2	+0.000	+0.002	0.005 CL	+0.000	+0.000	+0.010	0.033 CL
			–0.003	–0.000	0.000	–0.003	–0.015	–0.000	0.005 CL
	1/2	3/4	+0.000	+0.003	0.006 CL	+0.000	+0.000	+0.010	0.033 CL
			–0.003	–0.000	0.000	–0.003	–0.015	–0.000	0.005 CL
	3/4	1	+0.000	+0.003	0.007 CL	+0.000	+0.000	+0.010	0.034 CL
			–0.004	–0.000	0.000	–0.004	–0.015	–0.000	0.005 CL
	1	1 1/2	+0.000	+0.004	0.008 CL	+0.000	+0.000	+0.010	0.034 CL
			–0.004	–0.000	0.000	–0.004	–0.015	–0.000	0.005 CL
	1 1/2	3	+0.000	+0.004	0.009 CL	+0.000	+0.000	+0.010	0.035 CL
			–0.005	–0.000	0.000	–0.005	–0.015	–0.000	0.005 CL
	3	4	+0.000	+0.004	0.010 CL	+0.000	+0.000	+0.010	0.036 CL
			–0.006	–0.000	0.000	–0.006	–0.015	–0.000	0.005 CL
	4	6	+0.000	+0.004	0.012 CL	+0.000	+0.000	+0.010	0.038 CL
			–0.008	–0.000	0.000	–0.008	–0.015	–0.000	0.005 CL
	6	7	+0.000	+0.004	0.017 CL	+0.000	+0.000	+0.010	0.043 CL
			–0.013	–0.000	0.000	–0.013	–0.015	–0.000	0.005 CL
Class 2 Fit for Parallel and Taper Keys									
Parallel Square	…	1 1/4	+0.001	+0.002	0.002 CL	+0.001	+0.000	+0.010	0.030 CL
			–0.000	–0.000	0.001 INT	–0.000	–0.015	–0.000	0.004 CL
	1 1/4	3	+0.002	+0.002	0.002 CL	+0.002	+0.000	+0.010	0.030 CL
			–0.000	–0.000	0.002 INT	–0.000	–0.015	–0.000	0.003 CL
	3	3 1/2	+0.003	+0.002	0.002 CL	+0.003	+0.000	+0.010	0.030 CL
			–0.000	–0.000	0.003 INT	–0.000	–0.015	–0.000	0.002 CL
Parallel Rectangular	…	1 1/4	+0.001	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.035 CL
			–0.000	–0.000	0.001 INT	–0.005	–0.015	–0.000	0.000 CL
	1 1/4	3	+0.002	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.035 CL
			–0.000	–0.000	0.002 INT	–0.005	–0.015	–0.000	0.000 CL
	3	7	+0.003	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.035 CL
			–0.000	–0.000	0.003 INT	–0.005	–0.015	–0.000	0.000 CL
Taper	…	1 1/4	+0.001	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.005 CL
			–0.000	–0.000	0.001 INT	–0.000	–0.015	–0.000	0.025 INT
	1 1/4	3	+0.002	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.005 CL
			–0.000	–0.000	0.002 INT	–0.000	–0.015	–0.000	0.025 INT
	3	[b]	+0.003	+0.002	0.002 CL	+0.005	+0.000	+0.010	0.005 CL
			–0.000	–0.000	0.003 INT	–0.000	–0.015	–0.000	0.025 INT

[a] Limits of variation. CL = Clearance; INT = Interference.
[b] To (Incl.) 3 1/2-inch Square and 7-inch Rectangular key widths.

All dimensions are given in inches. See also text on page 2363.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Suggested Keyseat Fillet Radius and Key Chamfer
ANSI B17.1-1967 (R1998)

Keyseat Depth, *H*/2		Fillet Radius	45 deg. Chamfer	Keyseat Depth, *H*/2		Fillet Radius	45 deg. Chamfer
Over	To (Incl.)			Over	To (Incl.)		
1/8	1/4	1/32	3/64	7/8	1 1/4	3/16	7/32
1/4	1/2	1/16	5/64	1 1/4	1 3/4	1/4	9/32
1/2	7/8	1/8	5/32	1 3/4	2 1/2	3/8	13/32

All dimensions are given in inches.

Table 6. ANSI Standard Keyseat Tolerances for Electric Motor and Generator Shaft Extensions *ANSI B17.1-1967 (R1998)*

Keyseat Width			
Over	To (Incl.)	Width Tolerance	Depth Tolerance
…	1/4	+0.001	+0.000
		–0.001	–0.015
1/4	3/4	+0.000	+0.000
		–0.002	–0.015
3/4	1 1/4	+0.000	+0.000
		–0.003	–0.015

All dimensions are given in inches.

Table 7. Set Screws for Use Over Keys *ANSI B17.1-1967 (R1998)*

Nom. Shaft Dia.		Nom. Key Width	Set Screw Dia.	Nom. Shaft Dia.		Nom. Key Width	Set Screw Dia.
Over	To (Incl.)			Over	To (Incl.)		
5/16	7/16	3/32	No. 10	2 1/4	2 3/4	5/8	1/2
7/16	9/16	1/8	No. 10	2 3/4	3 1/4	3/4	5/8
9/16	7/8	3/16	1/4	3 1/4	3 3/4	7/8	3/4
7/8	1 1/4	1/4	5/16	3 3/4	4 1/2	1	3/4
1 1/4	1 3/8	5/16	3/8	4 1/2	5 1/2	1 1/4	7/8
1 3/8	1 3/4	3/8	3/8	5 1/2	6 1/2	1 1/2	1
1 3/4	2 1/4	1/2	1/2	…	…	…	…

All dimensions are given in inches.

These set screw diameter selections are offered as a guide but their use should be dependent upon design considerations.

ANSI Standard Woodruff Keys and Keyseats.— American National Standard B17.2 was approved in 1967, and reaffirmed in 1990. Data from this standard are shown in Tables 8, 9, and 10.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. ANSI Standard Woodruff Keys *ANSI B17.2-1967 (R1998)*



Key No.	Nominal Key Size W X B	Actual Length F +0.000 −0.010	Height of Key C Max.	Height of Key C Min.	Height of Key D Max.	Height of Key D Min.	Distance Below Center E
202	1/16 × 1/4	0.248	0.109	0.104	0.109	0.104	1/64
202.5	1/16 × 5/16	0.311	0.140	0.135	0.140	0.135	1/64
302.5	3/32 × 5/16	0.311	0.140	0.135	0.140	0.135	1/64
203	1/16 × 3/8	0.374	0.172	0.167	0.172	0.167	1/64
303	3/32 × 3/8	0.374	0.172	0.167	0.172	0.167	1/64
403	1/8 × 3/8	0.374	0.172	0.167	0.172	0.167	1/64
204	1/16 × 1/2	0.491	0.203	0.198	0.194	0.188	3/64
304	3/32 × 1/2	0.491	0.203	0.198	0.194	0.188	3/64
404	1/8 × 1/2	0.491	0.203	0.198	0.194	0.188	3/64
305	3/32 × 5/8	0.612	0.250	0.245	0.240	0.234	1/16
405	1/8 × 5/8	0.612	0.250	0.245	0.240	0.234	1/16
505	5/32 × 5/8	0.612	0.250	0.245	0.240	0.234	1/16
605	3/16 × 5/8	0.612	0.250	0.245	0.240	0.234	1/16
406	1/8 × 3/4	0.740	0.313	0.308	0.303	0.297	1/16
506	5/32 × 3/4	0.740	0.313	0.308	0.303	0.297	1/16
606	3/16 × 3/4	0.740	0.313	0.308	0.303	0.297	1/16
806	1/4 × 3/4	0.740	0.313	0.308	0.303	0.297	1/16
507	5/32 × 7/8	0.866	0.375	0.370	0.365	0.359	1/16
607	3/16 × 7/8	0.866	0.375	0.370	0.365	0.359	1/16
707	7/32 × 7/8	0.866	0.375	0.370	0.365	0.359	1/16
807	1/4 × 7/8	0.866	0.375	0.370	0.365	0.359	1/16
608	3/16 × 1	0.992	0.438	0.433	0.428	0.422	1/16
708	7/32 × 1	0.992	0.438	0.433	0.428	0.422	1/16
808	1/4 × 1	0.992	0.438	0.433	0.428	0.422	1/16
1008	5/16 × 1	0.992	0.438	0.433	0.428	0.422	1/16
1208	3/8 × 1	0.992	0.438	0.433	0.428	0.422	1/16
609	3/16 × 1 1/8	1.114	0.484	0.479	0.475	0.469	5/64
709	7/32 × 1 1/8	1.114	0.484	0.479	0.475	0.469	5/64
809	1/4 × 1 1/8	1.114	0.484	0.479	0.475	0.469	5/64
1009	5/16 × 1 1/8	1.114	0.484	0.479	0.475	0.469	5/64
610	3/16 × 1 1/4	1.240	0.547	0.542	0.537	0.531	5/64
710	7/32 × 1 1/4	1.240	0.547	0.542	0.537	0.531	5/64
810	1/4 × 1 1/4	1.240	0.547	0.542	0.537	0.531	5/64
1010	5/16 × 1 1/4	1.240	0.547	0.542	0.537	0.531	5/64
1210	3/8 × 1 1/4	1.240	0.547	0.542	0.537	0.531	5/64
811	1/4 × 1 3/8	1.362	0.594	0.589	0.584	0.578	3/32
1011	5/16 × 1 3/8	1.362	0.594	0.589	0.584	0.578	3/32
1211	3/8 × 1 3/8	1.362	0.594	0.589	0.584	0.578	3/32
812	1/4 × 1 1/2	1.484	0.641	0.636	0.631	0.625	7/64
1012	5/16 × 1 1/2	1.484	0.641	0.636	0.631	0.625	7/64
1212	3/8 × 1 1/2	1.484	0.641	0.636	0.631	0.625	7/64

All dimensions are given in inches.

The Key numbers indicate normal key dimensions. The last two digits give the nominal diameter *B* in eighths of an inch and the digits preceding the last two give the nominal width *W* in thirty-seconds of an inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ANSI Standard Woodruff Keys *ANSI B17.2-1967 (R1998)*



Key No.	Nominal Key Size $W \times B$	Actual Length F +0.000 −0.010	Height of Key				Distance Below Center E
			C		D		
			Max.	Min.	Max.	Min.	
617-1	3/16 × 2 1/8	1.380	0.406	0.401	0.396	0.390	21/32
817-1	1/4 × 2 1/8	1.380	0.406	0.401	0.396	0.390	21/32
1017-1	5/16 × 2 1/8	1.380	0.406	0.401	0.396	0.390	21/32
1217-1	3/8 × 2 1/8	1.380	0.406	0.401	0.396	0.390	21/32
617	3/16 × 2 1/8	1.723	0.531	0.526	0.521	0.515	17/32
817	1/4 × 2 1/8	1.723	0.531	0.526	0.521	0.515	17/32
1017	5/16 × 2 1/8	1.723	0.531	0.526	0.521	0.515	17/32
1217	3/8 × 2 1/8	1.723	0.531	0.526	0.521	0.515	17/32
822-1	1/4 × 2 3/4	2.000	0.594	0.589	0.584	0.578	25/32
1022-1	5/16 × 2 3/4	2.000	0.594	0.589	0.584	0.578	25/32
1222-1	3/8 × 2 3/4	2.000	0.594	0.589	0.584	0.578	25/32
1422-1	7/16 × 2 3/4	2.000	0.594	0.589	0.584	0.578	25/32
1622-1	1/2 × 2 3/4	2.000	0.594	0.589	0.584	0.578	25/32
822	1/4 × 2 3/4	2.317	0.750	0.745	0.740	0.734	5/8
1022	5/16 × 2 3/4	2.317	0.750	0.745	0.740	0.734	5/8
1222	3/8 × 2 3/4	2.317	0.750	0.745	0.740	0.734	5/8
1422	7/16 × 2 3/4	2.317	0.750	0.745	0.740	0.734	5/8
1622	1/2 × 2 3/4	2.317	0.750	0.745	0.740	0.734	5/8
1228	3/8 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
1428	7/16 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
1628	1/2 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
1828	9/16 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
2028	5/8 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
2228	11/16 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16
2428	3/4 × 3 1/2	2.880	0.938	0.933	0.928	0.922	13/16

All dimensions are given in inches.

The key numbers indicate nominal key dimensions. The last two digits give the nominal diameter B in eighths of an inch and the digits preceding the last two give the nominal width W in thirty-seconds of an inch.

The key numbers with the −1 designation, while representing the nominal key size have a shorter length F and due to a greater distance below center E are less in height than the keys of the same number without the −1 designation.

Copyright 2004, Industrial Press, Inc., New York, NY



Table 10. ANSI Keyseat Dimensions for Woodruff Keys

ANSI B17.2-1967 (R1998)

Key No.	Nominal Size Key	Keyseat—Shaft					Key Above Shaft	Keyseat—Hub	
		Width *A*[a]		Depth *B*	Diameter *F*		Height *C*	Width *D*	Depth *E*
		Min.	Max.	+0.005 −0.000	Min.	Max.	+0.005 −0.005	+0.002 −0.000	+0.005 −0.000
202	1/16 × 1/4	0.0615	0.0630	0.0728	0.250	0.268	0.0312	0.0635	0.0372
202.5	1/16 × 5/16	0.0615	0.0630	0.1038	0.312	0.330	0.0312	0.0635	0.0372
302.5	3/32 × 5/16	0.0928	0.0943	0.0882	0.312	0.330	0.0469	0.0948	0.0529
203	1/16 × 3/8	0.0615	0.0630	0.1358	0.375	0.393	0.0312	0.0635	0.0372
303	3/32 × 3/8	0.0928	0.0943	0.1202	0.375	0.393	0.0469	0.0948	0.0529
403	1/8 × 3/8	0.1240	0.1255	0.1045	0.375	0.393	0.0625	0.1260	0.0685
204	1/16 × 1/2	0.0615	0.0630	0.1668	0.500	0.518	0.0312	0.0635	0.0372
304	3/32 × 1/2	0.0928	0.0943	0.1511	0.500	0.518	0.0469	0.0948	0.0529
404	1/8 × 1/2	0.1240	0.1255	0.1355	0.500	0.518	0.0625	0.1260	0.0685
305	3/32 × 5/8	0.0928	0.0943	0.1981	0.625	0.643	0.0469	0.0948	0.0529
405	1/8 × 5/8	0.1240	0.1255	0.1825	0.625	0.643	0.0625	0.1260	0.0685
505	5/32 × 5/8	0.1553	0.1568	0.1669	0.625	0.643	0.0781	0.1573	0.0841
605	3/16 × 5/8	0.1863	0.1880	0.1513	0.625	0.643	0.0937	0.1885	0.0997
406	1/8 × 3/4	0.1240	0.1255	0.2455	0.750	0.768	0.0625	0.1260	0.0685
506	5/32 × 3/4	0.1553	0.1568	0.2299	0.750	0.768	0.0781	0.1573	0.0841
606	3/16 × 3/4	0.1863	0.1880	0.2143	0.750	0.768	0.0937	0.1885	0.0997
806	1/4 × 3/4	0.2487	0.2505	0.1830	0.750	0.768	0.1250	0.2510	0.1310
507	5/32 × 7/8	0.1553	0.1568	0.2919	0.875	0.895	0.0781	0.1573	0.0841
607	3/16 × 7/8	0.1863	0.1880	0.2763	0.875	0.895	0.0937	0.1885	0.0997
707	7/32 × 7/8	0.2175	0.2193	0.2607	0.875	0.895	0.1093	0.2198	0.1153
807	1/4 × 7/8	0.2487	0.2505	0.2450	0.875	0.895	0.1250	0.2510	0.1310
608	3/16 × 1	0.1863	0.1880	0.3393	1.000	1.020	0.0937	0.1885	0.0997
708	7/32 × 1	0.2175	0.2193	0.3237	1.000	1.020	0.1093	0.2198	0.1153
808	1/4 × 1	0.2487	0.2505	0.3080	1.000	1.020	0.1250	0.2510	0.1310
1008	5/16 × 1	0.3111	0.3130	0.2768	1.000	1.020	0.1562	0.3135	0.1622
1208	3/8 × 1	0.3735	0.3755	0.2455	1.000	1.020	0.1875	0.3760	0.1935
609	3/16 × 1 1/8	0.1863	0.1880	0.3853	1.125	1.145	0.0937	0.1885	0.0997
709	7/32 × 1 1/8	0.2175	0.2193	0.3697	1.125	1.145	0.1093	0.2198	0.1153
809	1/4 × 1 1/8	0.2487	0.2505	0.3540	1.125	1.145	0.1250	0.2510	0.1310
1009	5/16 × 1 1/8	0.3111	0.3130	0.3228	1.125	1.145	0.1562	0.3135	0.1622
610	3/16 × 1 1/4	0.1863	0.1880	0.4483	1.250	1.273	0.0937	0.1885	0.0997
710	7/32 × 1 1/4	0.2175	0.2193	0.4327	1.250	1.273	0.1093	0.2198	0.1153
810	1/4 × 1 1/4	0.2487	0.2505	0.4170	1.250	1.273	0.1250	0.2510	0.1310
1010	5/16 × 1 1/4	0.3111	0.3130	0.3858	1.250	1.273	0.1562	0.3135	0.1622
1210	3/8 × 1 1/4	0.3735	0.3755	0.3545	1.250	1.273	0.1875	0.3760	0.1935
811	1/4 × 1 3/8	0.2487	0.2505	0.4640	1.375	1.398	0.1250	0.2510	0.1310
1011	5/16 × 1 3/8	0.3111	0.3130	0.4328	1.375	1.398	0.1562	0.3135	0.1622

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **ANSI Keyseat Dimensions for Woodruff Keys**
ANSI B17.2-1967 (R1998)

Key No.	Nominal Size Key	Keyseat—Shaft					Key Above Shaft	Keyseat—Hub	
		Width *A*[a]		Depth *B*	Diameter *F*		Height *C*	Width *D*	Depth *E*
		Min.	Max.	+0.005 −0.000	Min.	Max.	+0.005 −0.005	+0.002 −0.000	+0.005 −0.000
1211	3/32 × 1 3/8	0.3735	0.3755	0.4015	1.375	1.398	0.1875	0.3760	0.1935
812	1/4 × 1 1/2	0.2487	0.2505	0.5110	1.500	1.523	0.1250	0.2510	0.1310
1012	5/16 × 1 1/2	0.3111	0.3130	0.4798	1.500	1.523	0.1562	0.3135	0.1622
1212	3/8 × 1 1/2	0.3735	0.3755	0.4485	1.500	1.523	0.1875	0.3760	0.1935
617-1	3/16 × 2 1/8	0.1863	0.1880	0.3073	2.125	2.160	0.0937	0.1885	0.0997
817-1	1/4 × 2 1/8	0.2487	0.2505	0.2760	2.125	2.160	0.1250	0.2510	0.1310
1017-1	5/16 × 2 1/8	0.3111	0.3130	0.2448	2.125	2.160	0.1562	0.3135	0.1622
1217-1	3/8 × 2 1/8	0.3735	0.3755	0.2135	2.125	2.160	0.1875	0.3760	0.1935
617	3/16 × 2 1/8	0.1863	0.1880	0.4323	2.125	2.160	0.0937	0.1885	0.0997
817	1/4 × 2 1/8	0.2487	0.2505	0.4010	2.125	2.160	0.1250	0.2510	0.1310
1017	5/16 × 2 1/8	0.3111	0.3130	0.3698	2.125	2.160	0.1562	0.3135	0.1622
1217	3/8 × 2 1/8	0.3735	0.3755	0.3385	2.125	2.160	0.1875	0.3760	0.1935
822-1	1/4 × 2 3/4	0.2487	0.2505	0.4640	2.750	2.785	0.1250	0.2510	0.1310
1022-1	5/16 × 2 3/4	0.3111	0.3130	0.4328	2.750	2.785	0.1562	0.3135	0.1622
1222-1	3/8 × 2 3/4	0.3735	0.3755	0.4015	2.750	2.785	0.1875	0.3760	0.1935
1422-1	7/16 × 2 3/4	0.4360	0.4380	0.3703	2.750	2.785	0.2187	0.4385	0.2247
1622-1	1/2 × 2 3/4	0.4985	0.5005	0.3390	2.750	2.785	0.2500	0.5010	0.2560
822	1/4 × 2 3/4	0.2487	0.2505	0.6200	2.750	2.785	0.1250	0.2510	0.1310
1022	5/16 × 2 3/4	0.3111	0.3130	0.5888	2.750	2.785	0.1562	0.3135	0.1622
1222	3/8 × 2 3/4	0.3735	0.3755	0.5575	2.750	2.785	0.1875	0.3760	0.1935
1422	7/16 × 2 3/4	0.4360	0.4380	0.5263	2.750	2.785	0.2187	0.4385	0.2247
1622	1/2 × 2 3/4	0.4985	0.5005	0.4950	2.750	2.785	0.2500	0.5010	0.2560
1228	3/8 × 3 1/2	0.3735	0.3755	0.7455	3.500	3.535	0.1875	0.3760	0.1935
1428	7/16 × 3 1/2	0.4360	0.4380	0.7143	3.500	3.535	0.2187	0.4385	0.2247
1628	1/2 × 3 1/2	0.4985	0.5005	0.6830	3.500	3.535	0.2500	0.5010	0.2560
1828	9/16 × 3 1/2	0.5610	0.5630	0.6518	3.500	3.535	0.2812	0.5635	0.2872
2028	5/8 × 3 1/2	0.6235	0.6255	0.6205	3.500	3.535	0.3125	0.6260	0.3185
2228	11/16 × 3 1/2	0.6860	0.6880	0.5893	3.500	3.535	0.3437	0.6885	0.3497
2428	3/4 × 3 1/2	0.7485	0.7505	0.5580	3.500	3.535	0.3750	0.7510	0.3810

[a] These Width *A* values were set with the maximum keyseat (shaft) width as that figure which will receive a key with the greatest amount of looseness consistent with assuring the key's sticking in the keyseat (shaft). Minimum keyseat width is that figure permitting the largest shaft distortion acceptable when assembling maximum key in minimum keyseat. Dimensions *A*, *B*, *C*, *D* are taken at side intersection.

All dimensions are given in inches.

The following definitions are given in this standard:

Woodruff Key: A demountable machinery part which, when assembled into key-seats, provides a positive means for transmitting torque between the shaft and hub.

Woodruff Key Number: An identification number by which the size of key may be readily determined.

Woodruff Keyseat—Shaft: The circular pocket in which the key is retained.

Woodruff Keyseat—Hub: An axially located rectangular groove in a hub. (This has been referred to as a keyway.)

Woodruff Keyseat Milling Cutter: An arbor type or shank type milling cutter normally used for milling Woodruff keyseats in shafts (see page 820).

Copyright 2004, Industrial Press, Inc., New York, NY

Taper Shaft Ends with Slotted Nuts *SAE Standard*



TAPER PER FOOT = $1.500^{\pm 0.002}$ IN.
H IS MEASURED PERPENDICULAR TO KEY.
C, COTTER-PIN HOLE HAS CENTERLINE
DISPLACED 90° FROM KEYWAY CENTER

Nom. Dia.	Dia. of Shaft, D_s		Dia. of Hole, D_h		L_c	L_s	L_h	L_t	T_s	T_p	Nut Width, Flats
	Max.	Min.	Max.	Min.							
1/4	0.250	0.249	0.248	0.247	9/16	5/16	3/8	5/16	7/32	9/64	5/16
3/8	0.375	0.374	0.373	0.372	47/64	7/16	1/2	23/64	17/64	3/16	1/2
1/2	0.500	0.499	0.498	0.497	63/64	11/16	3/4	23/64	17/64	3/16	1/2
5/8	0.625	0.624	0.623	0.622	1 3/32	11/16	3/4	17/32	7/16	1/4	3/4
3/4	0.750	0.749	0.748	0.747	1 11/32	15/16	1	17/32	7/16	1/4	3/4
7/8	0.875	0.874	0.873	0.872	1 11/16	1 1/8	1 1/4	11/16	1/2	5/16	15/16
1	1.001	0.999	0.997	0.995	1 15/16	1 3/8	1 1/2	11/16	1/2	5/16	1 1/16
1 1/8	1.126	1.124	1.122	1.120	1 15/16	1 3/8	1 1/2	11/16	1/2	5/16	1 1/4
1 1/4	1.251	1.249	1.247	1.245	1 15/16	1 3/8	1 1/2	11/16	1/2	5/16	1 7/16
1 3/8	1.376	1.374	1.372	1.370	2 7/16	1 7/8	2	11/16	1/2	5/16	1 7/16
1 1/2	1.501	1.499	1.497	1.495	2 7/16	1 7/8	2	11/16	1/2	5/16	1 7/16
1 5/8	1.626	1.624	1.622	1.620	2 13/16	2 1/8	2 1/4	13/16	5/8	7/16	2 3/16
1 3/4	1.751	1.749	1.747	1.745	2 13/16	2 1/8	2 1/4	13/16	5/8	7/16	2 3/16
1 7/8	1.876	1.874	1.872	1.870	3 1/16	2 3/8	2 1/2	13/16	5/8	7/16	2 3/16
2	2.001	1.999	1.997	1.995	3 9/16	2 7/8	3	13/16	5/8	7/16	2 3/16
2 1/4	2.252	2.248	2.245	2.242	3 9/16	2 7/8	3	13/16	5/8	7/16	2 3/8
2 1/2	2.502	2.498	2.495	2.492	4 9/32	3 3/8	3 1/2	1 1/4	1	5/8	3 1/8
2 3/4	2.752	2.748	2.745	2.742	4 9/32	3 3/8	3 1/2	1 1/4	1	5/8	3 1/8
3	3.002	2.998	2.995	2.992	2 25/32	3 7/8	4	1 1/4	1	5/8	3 1/8
3 1/4	3.252	3.248	3.245	3.242	5 1/32	4 1/8	4 1/4	1 1/4	1	5/8	3 1/8
3 1/2	3.502	3.498	3.495	3.492	5 7/16	4 3/8	4 1/2	1 3/8	1 1/8	3/4	3 7/8
4	4.002	3.998	3.995	3.992	6 7/16	5 3/8	5 1/2	1 3/8	1 1/8	3/4	3 7/8

Nom. Dia.	D_t	Thds. per Inch	Keyway				Square Key		A	B	C
			W		H						
			Max.	Min.	Max.	Min.	Max.	Min.			
1/4	#10	40	0.0625	.0615	.037	.033	0.0635	0.0625	1/2	3/16	5/64
3/8	5/16	32	0.0937	.0927	.053	.049	0.0947	0.0937	11/16	1/4	5/64
1/2	5/16	32	0.1250	.1240	.069	.065	0.1260	0.1250	7/8	3/8	5/64
5/8	1/2	28	0.1562	.1552	.084	.080	0.1572	0.1562	1 1/16	3/8	1/8
3/4	1/2	28	0.1875	.1865	.100	.096	0.1885	0.1875	1 1/4	5/8	1/8
7/8	5/8	24	0.2500	.2490	.131	.127	0.2510	0.2500	1 1/2	3/4	5/32
1	3/4	20	0.2500	.2490	.131	.127	0.2510	0.2500	1 3/4	7/8	5/32
1 1/8	7/8	20	0.3125	.3115	.162	.158	0.3135	0.3125	2	7/8	5/32
1 1/4	1	20	0.3125	.3115	.162	.158	0.3135	0.3125	2 1/8	7/8	5/32
1 3/8	1	20	0.3750	.3740	.194	.190	0.3760	0.3750	2 1/4	1	5/32
1 1/2	1	20	0.3750	.3740	.194	.190	0.3760	0.3750	2 1/2	1	5/32
1 5/8	1 1/4	18	0.4375	.4365	.225	.221	0.4385	0.4375	2 3/4	1 1/4	5/32
1 3/4	1 1/4	18	0.4375	.4365	.225	.221	0.4385	0.4375	3	1 1/4	5/32
1 7/8	1 1/4	18	0.4375	.4365	.225	.221	0.4385	0.4375	3 1/8	1 1/4	5/32
2	1 1/4	18	0.5000	.4990	.256	.252	0.5010	0.5000	3 1/4	1 1/2	5/32
2 1/4	1 1/2	18	0.5625	.5610	.287	.283	0.5640	0.5625	3 1/2	1 1/2	5/32
2 1/2	2	16	0.6250	.6235	.319	.315	0.6265	0.6250	4	1 3/4	7/32
2 3/4	2	16	0.6875	.6860	.350	.346	0.6890	0.6875	4 3/8	1 3/4	7/32
3	2	16	0.7500	.7485	.381	.377	0.7515	0.7500	4 3/4	2	7/32
3 1/4	2	16	0.7500	.7485	.381	.377	0.7515	0.7500	5	2 1/8	7/32
3 1/2	2 1/2	16	0.8750	.8735	.444	.440	0.8765	0.8750	5 1/2	2 1/4	9/32
4	2 1/2	16	1.0000	.9985	.506	.502	1.0015	1.0000	6 1/4	2 3/4	9/32

All dimensions in inches except where otherwise noted. © 1990, SAE.

Copyright 2004, Industrial Press, Inc., New York, NY

Chamfered Keys and Filleted Keyseats.— In general practice, chamfered keys and filleted keyseats are not used. However, it is recognized that fillets in keyseats decrease stress concentration at corners. When used, fillet radii should be as large as possible without causing excessive bearing stresses due to reduced contact area between the key and its mating parts. Keys must be chamfered or rounded to clear fillet radii. Values in Table 5 assume general conditions and should be used only as a guide when critical stresses are encountered.

Depths for Milling Keyseats.— Table 11 on page 2375 has been compiled to facilitate the accurate milling of keyseats. This table gives the distance M (see illustration accompanying table) between the top of the shaft and a line passing through the upper corners or edges of the keyseat. Dimension M is calculated by the formula: $M = \frac{1}{2}(S - \sqrt{S^2 - E^2})$ where S is diameter of shaft, and E is width of keyseat. A simple approximate formula that gives M to within 0.001 inch is $M = E^2 \div 4S$.

Cotters.— A cotter is a form of key that is used to connect rods, etc., that are subjected either to tension or compression or both, the cotter being subjected to shearing stresses at two transverse cross-sections. When taper cotters are used for drawing and holding parts together, if the cotter is held in place by the friction between the bearing surfaces, the taper should not be too great. Ordinarily a taper varying from $\frac{1}{4}$ to $\frac{1}{2}$ inch per foot is used for plain cotters. When a set-screw or other device is used to prevent the cotter from backing out of its slot, the taper may vary from 1 $\frac{1}{2}$ to 2 inches per foot.

British Keys and Keyways

British Standard Metric Keys and Keyways.— This British Standard, BS 4235:Part 1:1972 (1986), covers square and rectangular parallel keys and keyways, and square and rectangular taper keys and keyways. Plain and gib-head taper keys are specified. There are three classes of fit for the square and rectangular parallel keys and keyways, designated free, normal, and close. A *free fit* is applied when the application requires the hub of an assembly to slide over the key; a *normal fit* is employed when the key is to be inserted in the keyway with the minimum amount of fitting, as may be required in mass-production assembly work; and a *close fit* is applied when accurate fitting of the key is required under maximum material conditions, which may involve selection of components.

The Standard does not provide for misalignment or offset greater than can be accommodated within the dimensional tolerances. If an assembly is to be heavily stressed, a check should be made to ensure that the cumulative effect of misalignment or offset, or both, does not prevent satisfactory bearing on the key. Radii and chamfers are not normally provided on keybar and keys as supplied, but they can be produced during manufacture by agreement between the user and supplier.

Unless otherwise specified, keys in compliance with this Standard are manufactured from steel made to BS 970 having a tensile strength of not less than 550 MN/m^2 in the finished condition. BS 970, Part 1, lists the following steels and maximum section sizes, respectively, that meet this tensile strength requirement: 070M20, 25 × 14 mm; 070M26, 36 × 20 mm; 080M30, 90 × 45 mm; and 080M40, 100 × 50 mm.

At the time of publication of this Standard, the demand for metric keys was not sufficient to enable standard ranges of lengths to be established. The lengths given in the accompanying table are those shown as standard in ISO Recommendations R773: 1969, "Rectangular or Square Parallel Keys and their Corresponding Keyways (Dimensions in Millimeters)," and R 774: 1969, "Taper Keys and their Corresponding Keyways—with or without Gib Head (Dimensions in Millimeters)."

Tables 12 through 15 on the following pages cover the dimensions and tolerances of square and rectangular keys and keyways, and square and rectangular taper keys and keyways.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Finding Depth of Keyseat and Distance from Top of Key to Bottom of Shaft



For milling keyseats, the total depth to feed cutter in from outside of shaft to bottom of keyseat is $M + D$, where D is depth of keyseat.

For checking an assembled key and shaft, caliper measurement J between top of key and bottom of shaft is used.

$$J = S - (M + D) + C$$

where C is depth of key. For Woodruff keys, dimensions C and D can be found in Tables 8 through 10. Assuming shaft diameter S is normal size, the tolerance on dimension J for Woodruff keys in keyslots are + 0.000, –0.010 inch.

Dia. of Shaft S. Inches	Width of Keyseat, E														
	1/16	3/32	1/8	5/32	3/16	7/32	1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4
	Dimension M, Inch														
0.3125	.0032	…	…	…	…	…	…	…	…	…	…	…	…	…	…
0.3437	.0029	.0065	…	…	…	…	…	…	…	…	…	…	…	…	…
0.3750	.0026	.0060	.0107	…	…	…	…	…	…	…	…	…	…	…	…
0.4060	.0024	.0055	.0099	…	…	…	…	…	…	…	…	…	…	…	…
0.4375	.0022	.0051	.0091	…	…	…	…	…	…	…	…	…	…	…	…
0.4687	.0021	.0047	.0085	.0134	…	…	…	…	…	…	…	…	…	…	…
0.5000	.0020	.0044	.0079	.0125	…	…	…	…	…	…	…	…	…	…	…
0.5625	…	.0039	.0070	.0111	.0161	…	…	…	…	…	…	…	…	…	…
0.6250	…	.0035	.0063	.0099	.0144	.0198	…	…	…	…	…	…	…	…	…
0.6875	…	.0032	.0057	.0090	.0130	.0179	.0235	…	…	…	…	…	…	…	…
0.7500	…	.0029	.0052	.0082	.0119	.0163	.0214	.0341	…	…	…	…	…	…	…
0.8125	…	.0027	.0048	.0076	.0110	.0150	.0197	.0312	…	…	…	…	…	…	…
0.8750	…	.0025	.0045	.0070	.0102	.0139	.0182	.0288	…	…	…	…	…	…	…
0.9375	…	…	.0042	.0066	.0095	.0129	.0170	.0263	.0391	…	…	…	…	…	…
1.0000	…	…	.0039	.0061	.0089	.0121	.0159	.0250	.0365	…	…	…	…	…	…
1.0625	…	…	.0037	.0058	.0083	.0114	.0149	.0235	.0342	…	…	…	…	…	…
1.1250	…	…	.0035	.0055	.0079	.0107	.0141	.0221	.0322	.0443	…	…	…	…	…
1.1875	…	…	.0033	.0052	.0074	.0102	.0133	.0209	.0304	.0418	…	…	…	…	…
1.2500	…	…	.0031	.0049	.0071	.0097	.0126	.0198	.0288	.0395	…	…	…	…	…
1.3750	…	…	…	.0045	.0064	.0088	.0115	.0180	.0261	.0357	.0471	…	…	…	…
1.5000	…	…	…	.0041	.0059	.0080	.0105	.0165	.0238	.0326	.0429	…	…	…	…
1.6250	…	…	…	.0038	.0054	.0074	.0097	.0152	.0219	.0300	.0394	.0502	…	…	…
1.7500	…	…	…	…	.0050	.0069	.0090	.0141	.0203	.0278	.0365	.0464	…	…	…
1.8750	…	…	…	…	.0047	.0064	.0084	.0131	.0189	.0259	.0340	.0432	.0536	…	…
2.0000	…	…	…	…	.0044	.0060	.0078	.0123	.0177	.0242	.0318	.0404	.0501	…	…
2.1250	…	…	…	…	…	.0056	.0074	.0116	.0167	.0228	.0298	.0379	.0470	.0572	.0684
2.2500	…	…	…	…	…	…	.0070	.0109	.0157	.0215	.0281	.0357	.0443	.0538	.0643
2.3750	…	…	…	…	…	…	…	.0103	.0149	.0203	.0266	.0338	.0419	.0509	.0608
2.5000	…	…	…	…	…	…	…	…	.0141	.0193	.0253	.0321	.0397	.0482	.0576
2.6250	…	…	…	…	…	…	…	…	.0135	.0184	.0240	.0305	.0377	.0457	.0547
2.7500	…	…	…	…	…	…	…	…	…	.0175	.0229	.0291	.0360	.0437	.0521
2.8750	…	…	…	…	…	…	…	…	…	.0168	.0219	.0278	.0344	.0417	.0498
3.0000	…	…	…	…	…	…	…	…	…	…	.0210	.0266	.0329	.0399	.0476

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. British Standard Metric Keyways for Square and Rectangular Parallel Keys *BS 4235:Part 1:1972 (1986)*





Section x-x



Enlarged Detail of Key and Keyways

Shaft		Key	Keyway											
Nominal Diameter *d*			Width *b*						Depth				Radius *r*	
				Free Fit		Normal Fit		Close Fit	Shaft t_1		Hub t_2			
Over	Up to and Incl	Size, *b* × *h*	Nominal	Shaft (H9)	Hub (D10)	Shaft (N9)	Hub (J_S9)[a]	Shaft and Hub (P9)	Nominal	Tolerance	Nominal	Tolerance	Max.	Min.
				Tolerances										
Keyways for Square Parallel Keys														
6	8	2 × 2	2	+0.025	+0.060	−0.004	+0.012	−0.006	1.2		1		0.16	0.08
8	10	3 × 3	3	0	+0.020	−0.029	−0.012	−0.031	1.8		1.4		0.16	0.08
10	12	4 × 4	4						2.5	+0.1 0	1.8	+0.1 0	0.16	0.08
12	17	5 × 5	5	+0.030 0	+0.078 +0.030	0 −0.030	+0.015 −0.015	−0.012 −0.042	3		2.3		0.25	0.16
17	22	6 × 6	6						3.5		2.8		0.25	0.16
Keyways for Rectangular Parallel Keys														
22	30	8 × 7	8	+0.036	+0.098	0	+0.018	−0.015	4		3.3		0.25	0.16
30	38	10 × 8	10	0	+0.040	−0.036	−0.018	−0.051	5		3.3		0.40	0.25
38	44	12 × 8	12						5		3.3		0.40	0.25
44	50	14 × 9	14	+0.043	+0.120	0	+0.021	−0.018	5.5		3.8		0.40	0.25
50	58	16 × 10	16		+0.050	−0.043	−0.021	−0.061	6		4.3		0.40	0.25
58	65	18 × 11	18						7	+0.2 0	4.4	+0.2 0	0.40	0.25
65	75	20 × 12	20						7.5		4.9		0.60	0.40
75	85	22 × 14	22	+0.052	+0.149	0	+0.026	−0.022	9		5.4		0.60	0.40
85	95	25 × 14	25		+0.065	−0.052	−0.026	−0.074	9		5.4		0.60	0.40
95	110	28 × 16	28						10		6.4		0.60	0.40
110	130	32 × 18	32						11		7.4		0.60	0.40
130	150	36 × 20	36						12		8.4		1.00	0.70
150	170	40 × 22	40	+0.062	+0.180 −0.080	0 −0.062	+0.031 −0.031	−0.026 −0.088	13		9.4		1.00	0.70
170	200	45 × 25	45						15		10.4		1.00	0.70
200	230	50 × 28	50						17		11.4		1.00	0.70
230	260	56 × 32	56						20	+0.3 0	12.4	+0.3 0	1.60	1.20
260	290	63 × 32	63	+0.074	+0.220 +0.100	0 −0.074	+0.037 −0.037	−0.032 −0.106	20		12.4		1.60	1.20
290	330	70 × 36	70						22		14.4		1.60	1.20
330	380	80 × 40	80						25		15.4		2.50	2.00
380	440	90 × 45	90	+0.087	+0.260	0	+0.043	−0.037	28		17.4		2.50	2.00
440	500	100 × 50	100	0	+0.120	−0.087	−0.043	−0.124	31		19.5		2.50	2.00

[a] Tolerance limits J_S9 are quoted from BS 4500, "ISO Limits and Fits," to three significant figures.

All dimensions in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13. British Standard Metric Keyways for Square and Rectangular Taper Keys *BS 4235:Part 1:1972 (1986)*



Shaft		Key	Keyway							
Nominal Diameter *d*		Size, *b* × *h*	Width *b*, Shaft and Hub		Depth				Corner Radius of Keyway	
					Shaft t_1		Hub t_2			
Over	Up to and Incl.		Nom.	Tol. (D10)	Nom.	Tol.	Nom.	Tol.	Max.	Min.
Keyways for Square Taper Keys										
6	8	2 × 2	2	+0.060 +0.020	1.2		0.5		0.16	0.08
8	10	3 × 3	3		1.8	±0.10	0.9	±0.10	0.16	0.08
10	12	4 × 4	4	+0.078 +0.030	2.5		1.2		0.16	0.08
12	17	5 × 5	5		3		1.7		0.25	0.16
17	22	6 × 6	6		3.5	+0.20	2.2	+0.20	0.25	0.16
Keyways for Rectangular Taper Keys										
22	30	8 × 7	8	+0.098 +0.040	4		2.4		0.25	0.16
30	38	10 × 8	10		5		2.4		0.40	0.25
38	44	12 × 8	12	+0.120 +0.050	5		2.4		0.40	0.25
44	50	14 × 9	14		5.5		2.9		0.40	0.25
50	58	16 × 10	16		6		3.4		0.40	0.25
58	65	18 × 11	18		7	±0.20	3.4	±0.20	0.40	0.25
65	75	20 × 12	20	+0.149 +0.065	7.5		3.9		0.60	0.40
75	85	22 × 14	22		9		4.4		0.60	0.40
85	95	25 × 14	25		9		4.4		0.60	0.40
95	110	28 × 16	28		10		5.4		0.60	0.40
110	130	32 × 18	32	+0.180 +0.080	11		6.4		0.60	0.40
130	150	36 × 20	36		12		7.1		1.00	0.70
150	170	40 × 22	40		13		8.1		1.00	0.70
170	200	45 × 25	45		15		9.1		1.00	0.70
200	230	50 × 28	50		17		10.1		1.00	0.70
230	260	56 × 32	56	+0.220 +0.120	20		11.1		1.60	1.20
260	290	63 × 32	63		20	±0.30	11.1	±0.30	1.60	1.20
290	330	70 × 36	70		22		13.1		1.60	1.20
330	380	80 × 40	80		25		14.1		2.50	2.00
380	440	90 × 45	90	+0.260 +0.120	28		16.1		2.50	2.00
440	500	100 × 50	100		31		18.1		2.50	2.00

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. British Standard Metric Square and Rectangular Parallel Keys *BS 4235:Part 1:1972 (1986)*



Width b		Thickness, h		Chamfer, s		Length Range, l	
Nom.	Tol.[a]	Nom.	Tol.[a]	Min.	Max.	From	To
Square Parallel Keys							
2	0 −0.025	2	0 −0.025	0.16	0.25	6	20
3		3		0.16	0.25	6	36
4	0 −0.030	4	0 −0.030	0.16	0.25	8	45
5		5		0.25	0.40	10	56
6		6		0.25	0.40	14	70
Rectangular Parallel Keys							
8	0 −0.036	7	0 −0.090	0.25	0.40	18	90
10		8		0.40	0.60	22	110
12	0 −0.043	8		0.40	0.60	28	140
14		9		0.40	0.60	36	160
16		10		0.40	0.60	45	180
18		11	0 −0.110	0.40	0.60	50	200
20	0 −0.052	12		0.60	0.80	56	220
22		14		0.60	0.80	63	250
25		14		0.60	0.80	70	280
28		16		0.60	0.80	80	320
32	0 −0.062	18		0.60	0.80	90	360
36		20	0 −0.130	1.00	1.20	100	400
40		22		1.00	1.20	…	…
45		25		1.00	1.20	…	…
50		28		1.00	1.20	…	…
56	0 −0.074	32	0 −0.160	1.60	2.00	…	…
63		32		1.60	2.00	…	…
70		36		1.60	2.00	…	…
80		40		2.50	3.00	…	…
90	0 −0.087	45		2.50	3.00	…	…
100		50		2.50	3.00	…	…

[a] The tolerance on the width and thickness of square taper keys is h9, and on the width and thickness of rectangular keys, h9 and h11, respectively, in accordance with ISO metric limits and fits. All dimensions in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 15. British Standard Metric Square and Rectangular Taper Keys *BS 4235:Part 1:1972 (1986)*



Width b		Thickness h		Chamfer s		Length Range l		Gib head h_1	Radius r
Nom.	Tol.[a]	Nom.	Tol.[a]	Min.	Max.	From	To	Nom.	Nom.
Square Taper Keys									
2	0 −0.025	2	0 −0.025	0.16	0.25	6	20	…	…
3		3		0.16	0.25	6	36	…	…
4	0 −0.030	4	0 −0.030	0.16	0.25	8	45	7	0.25
5		5		0.25	0.40	10	56	8	0.25
6		6		0.25	0.40	14	70	10	0.25
Rectangular Taper Keys									
8	0 −0.036	7	0 −0.090	0.25	0.40	18	90	11	1.5
10		8		0.40	0.60	22	110	12	1.5
12	0 −0.043	8		0.40	0.60	28	140	12	1.5
14		9		0.40	0.60	36	160	14	1.5
16		10		0.40	0.60	45	180	16	3.2
18	0 −0.052	11	0 −0.110	0.40	0.60	50	200	18	3.2
20		12		0.60	0.80	56	220	20	3.2
22		14		0.60	0.80	63	250	22	3.2
25		14		0.60	0.80	70	280	22	3.2
28		16		0.60	0.80	80	320	25	3.2
32	0 −0.062	18	0 −0.130	0.60	0.80	90	360	28	6.4
36		20		1.00	1.20	100	400	32	6.4
40		22		1.00	1.20	…	…	36	6.4
45		25		1.00	1.20	…	…	40	6.4
50		28		1.00	1.20	…	…	45	6.4
56	0 −0.074	32	0 −0.160	1.60	2.00	…	…	50	9.5
63		32		1.60	2.00	…	…	50	9.5
70		36		1.60	2.00	…	…	56	9.5
80		40		2.50	3.00	…	…	63	9.5
90	0 −0.087	45		2.50	3.00	…	…	70	9.5
100		50		2.50	3.00	…	…	80	9.5

[a] The tolerance on the width and thickness of square taper keys is h9, and on the width and thickness of rectangular taper keys, h9 and h11 respectively, in accordance with ISO metric limits and fits. Does not apply to gib head dimensions.

British Standard Keys and Keyways: Tables 16 through 21 from BS 46:Part 1:1958 (1985) (obsolescent) provide data for rectangular parallel keys and keyways, square parallel keys and keyways, plain and gib head rectangular taper keys and key-ways, plain and gib head square taper keys and keyways, and Woodruff keys and keyways.

Parallel Keys: These keys are used for transmitting unidirectional torques in transmissions not subject to heavy starting loads and where periodic withdrawal or sliding of the hub member may be required. In many instances, particularly couplings, a gib-head cannot be accommodated, and there is insufficient room to drift out the key from behind. It is then necessary to withdraw the component over the key and a parallel key is essential. Parallel square and rectangular keys are normally side fitting with top clearance and are usually retained in the shaft rather more securely than in the hub. The rectangular key is the general-purpose key for shafts greater than 1 inch in diameter; the square key is intended for

Copyright 2004, Industrial Press, Inc., New York, NY

use with shafts up to and including 1-inch diameter or for shafts up to 6-inch diameter where it is desirable to have a greater key depth than is provided by rectangular keys. In stepped shafts, the larger diameters are usually required by considerations other than torque, e.g., resistance to bending. Where components such as fans, gears, impellers, etc., are attached to the larger shaft diameter, the use of a key smaller than standard for that diameter may be permissible. As this results in unequal disposition of the key in the shaft and its related hub, the dimensions H and h must be recalculated to maintain the $T/2$ relationship.

British Standard Preferred Lengths of Metric Keys *BS 4235:Part 1:1972 (1986)*

	Type of key					Type of key			
Length	Sq.	Rect.	Sq. Taper	Rect. Taper	Length	Sq.	Rect.	Sq. Taper	Rect. Taper
6	●		●		63	●	●	●	●
8	●		●		70	●	●	●	●
10	●		●		80		●		●
12	●		●		90		●		●
14	●		●		100		●		●
16	●		●		110		●		●
18	●	●	●	●	125		●		●
20	●	●	●	●	140		●		●
22	●	●	●	●	160		●		●
25	●	●	●	●	180		●		●
28	●	●	●	●	200		●		●
32	●	●	●	●	220		●		●
36	●	●	●	●	250		●		●
40	●	●	●	●	280		●		●
45	●	●	●	●	320		●		●
50	●	●	●	●	360		●		●
56	●	●	●	●	400		●		●

Taper Keys: These keys are used for transmitting heavy unidirectional, reversing, or vibrating torques and in applications where periodic withdrawal of the key may be necessary. Taper keys are usually top fitting, but may be top and side fitting where required, and the keyway in the hub should then have the same width value as the keyway in the shaft. Taper keys of rectangular section are used for general purposes and are of less depth than square keys; square sections are for use with shafts up to and including 1-inch diameter or for shafts up to 6-inch diameter where it is desirable to have greater key depth.

Woodruff Keys: These keys are used for light applications or the angular location of associated parts on tapered shaft ends. They are not recommended for other applications, but if so used, corner radii in the shaft and hub keyways are advisable to reduce stress concentration.

Dimensions and Tolerances for British Parallel and Taper Keys and Keyways: Dimensions and tolerances for key and keyway widths given in Tables 16, 17, 18, and 19 are based on the width of key W and provide a fitting allowance. The fitting allowance is designed to permit an interference between the key and the shaft keyway and a slightly easier condition between the key and the hub keyway. In shrink and heavy force fits, it may be found necessary to depart from the width and depth tolerances specified. Any variation in the width of the keyway should be such that the greatest width is at the end from which the key enters and any variation in the depth of the keyway should be such that the greatest depth is at the end from which the key enters.

Keys and keybar normally are not chamfered or radiused as supplied, but this may be done at the time of fitting. Radii and chamfers are given in Tables 16, 17, 18, and 19. Corner radii are recommended for keyways to alleviate stress concentration.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 16. British Standard Rectangular Parallel Keys, Keyways, and Keybars *B.S. 46: Part I: 1958*



Diameter of Shaft		Key					Keyway in Shaft				Keyway in Hub				Nominal Keyway Radius, r[a]	Keybar			
Over	Up to and Including	Size W × T	Width, W		Thickness, T		Width W_s		Depth H		Width W_h		Depth h			Width W		Thickness T	
			Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.		Max.	Min.	Max.	Min.
1	1¼	5/16 × 1/4	0.314	0.312	0.253	0.250	0.311	0.312	0.146	0.152	0.312	0.313	0.112	0.118	0.010	0.314	0.312	0.253	0.250
1¼	1½	3/8 × 1/4	0.377	0.375	0.253	0.250	0.374	0.375	0.150	0.156	0.375	0.376	0.108	0.114	0.010	0.377	0.375	0.253	0.250
1½	1¾	7/16 × 5/16	0.440	0.438	0.315	0.312	0.437	0.438	0.186	0.192	0.438	0.439	0.135	0.141	0.020	0.440	0.438	0.315	0.312
1¾	2	1/2 × 5/16	0.502	0.500	0.315	0.312	0.499	0.500	0.190	0.196	0.500	0.501	0.131	0.137	0.020	0.502	0.500	0.315	0.312
2	2½	5/8 × 7/16	0.627	0.625	0.441	0.438	0.624	0.625	0.260	0.266	0.625	0.626	0.185	0.191	0.020	0.627	0.625	0.441	0.438
2½	3	3/4 × 1/2	0.752	0.750	0.503	0.500	0.749	0.750	0.299	0.305	0.750	0.751	0.209	0.215	0.020	0.752	0.750	0.503	0.500
3	3½	7/8 × 5/8	0.877	0.875	0.629	0.625	0.874	0.875	0.370	0.376	0.875	0.876	0.264	0.270	0.062	0.877	0.875	0.629	0.625
3½	4	1 × 3/4	1.003	1.000	0.754	0.750	0.999	1.000	0.441	0.447	1.000	1.001	0.318	0.324	0.062	1.003	1.000	0.754	0.750
4	5	1¼ × 7/8	1.253	1.250	0.879	0.875	1.248	1.250	0.518	0.524	1.250	1.252	0.366	0.372	0.062	1.253	1.250	0.879	0.875
5	6	1½ × 1	1.504	1.500	1.006	1.000	1.498	1.500	0.599	0.605	1.500	1.502	0.412	0.418	0.062	1.504	1.500	1.006	1.000
6	7	1½ × 1¼	1.754	1.750	1.256	1.250	1.748	1.750	1.740	0.746	1.750	1.752	0.526	0.532	0.125				
7	8	2 × 1⅜	2.005	2.000	1.381	1.375	1.998	2.000	0.818	0.824	2.000	2.002	0.573	0.579	0.125				
8	9	2¼ × 1½	2.255	2.250	1.506	1.500	2.248	2.250	0.897	0.905	2.250	2.252	0.619	0.627	0.125	Bright keybar is not normally available in sections larger than the above.			
9	10	2½ × 1⅝	2.505	2.500	1.631	1.625	2.498	2.500	0.975	0.983	2.500	2.502	0.666	0.674	0.187				
10	11	2¾ × 1⅞	2.755	2.750	1.881	1.875	2.748	2.750	1.114	1.122	2.750	2.752	0.777	0.785	0.187				
11	12	3 × 2	3.006	3.000	2.008	2.000	2.998	3.000	1.195	1.203	3.000	3.002	0.823	0.831	0.187				
12	13	3¼ × 2⅛	3.256	3.250	2.133	2.125	3.248	3.250	1.273	1.281	3.250	3.252	0.870	0.878	0.187				
13	14	3½ × 2⅜	3.506	3.500	2.383	2.375	3.498	3.500	1.413	1.421	3.500	3.502	0.980	0.988	0.250				
14	15	3¾ × 2½	3.756	3.750	2.508	2.500	3.748	3.750	1.492	1.502	3.750	3.752	1.026	1.036	0.250	All dimensions in inches.			
15	16	4 × 2⅝	4.008	4.000	2.633	2.625	3.998	4.000	1.571	1.581	4.000	4.002	1.072	1.082	0.250				
16	17	4¼ × 2⅞	4.258	4.250	2.883	2.875	4.248	4.250	1.711	1.721	4.250	4.252	1.182	1.192	0.312				
17	18	4½ × 3	4.508	4.500	3.010	3.000	4.498	4.500	1.791	1.801	4.500	4.502	1.229	1.239	0.312				
18	19	4¼ × 3⅛	4.758	4.750	3.135	3.125	4.748	4.750	1.868	1.878	4.750	4.752	1.277	1.287	0.312				
19	20	5 × 3⅜	5.008	5.000	3.385	3.375	4.998	5.000	2.010	2.020	5.000	5.002	1.385	1.395	0.312				

[a] The key chamfer shall be the minimum to clear the keyway radius. Nominal values are given.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. British Standard Square Parallel Keys, Keyways, and Keybars *B.S. 46: Part 1: 1958*



Diameter of Shaft		Key			Keyway in Shaft				Keyway in Hub				Nominal Keyway Radius, r[a]	Bright Keybar	
Over	Up to and Including	Size, W × T	Width, W and Thickness, T		Width, W_s		Depth, H		Width, W_h		Depth, h			Width, W and Thickness, T	
			Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.		Max.	Min.
1/4	1/2	1/8 × 1/8	0.127	0.125	0.124	0.125	0.072	0.078	0.125	0.126	0.060	0.066	0.010	0.127	0.125
1/2	3/4	3/16 × 3/16	0.190	0.188	0.187	0.188	0.107	0.113	0.188	0.189	0.088	0.094	0.010	0.190	0.188
3/4	1	1/4 × 1/4	0.252	0.250	0.249	0.250	0.142	0.148	0.250	0.251	0.115	0.121	0.010	0.252	0.250
1	1 1/4	5/16 × 5/16	0.314	0.312	0.311	0.312	0.177	0.183	0.312	0.313	0.142	0.148	0.010	0.314	0.312
1 1/4	1 1/2	3/8 × 3/8	0.377	0.375	0.374	0.375	0.213	0.219	0.375	0.376	0.169	0.175	0.010	0.377	0.375
1 1/2	1 3/4	7/16 × 7/16	0.440	0.438	0.437	0.438	0.248	0.254	0.438	0.439	0.197	0.203	0.020	0.440	0.438
1 3/4	2	1/2 × 1/2	0.502	0.500	0.499	0.500	0.283	0.289	0.500	0.501	0.224	0.230	0.020	0.502	0.500
2	2 1/2	5/8 × 5/8	0.627	0.625	0.624	0.625	0.354	0.360	0.625	0.626	0.278	0.284	0.020	0.627	0.625
2 1/2	3	3/4 × 3/4	0.752	0.750	0.749	0.750	0.424	0.430	0.750	0.751	0.333	0.339	0.020	0.752	0.750
3	3 1/2	7/8 × 7/8	0.877	0.875	0.874	0.875	0.495	0.501	0.875	0.876	0.387	0.393	0.062	0.877	0.875
3 1/2	4	1 × 1	1.003	1.000	0.999	1.000	0.566	0.572	1.000	1.001	0.442	0.448	0.062	1.003	1.000
4	5	1 1/4 × 1 1/4	1.253	1.250	1.248	1.250	0.707	0.713	1.250	1.252	0.551	0.557	0.062	1.253	1.250
5	6	1 1/2 × 1 1/2	1.504	1.500	1.498	1.500	0.848	0.854	1.500	1.502	0.661	0.667	0.062	1.504	1.500

[a] The key chamfer shall be the minimum to clear the keyway radius. Nominal values are given. All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 18. British Standard Rectangular Taper Keys and Keyways, Gib-head and Plain *B.S. 46: Part 1: 1958*



Section at Deep End of Keyway in Hub



Plain Taper Key



Gib-Head Key

Diameter of Shaft		Key					Keyway in Shaft and Hub								Nominal Keyway Radius, r[a]	Gib-head[b]				Radius, R
Over	Up to and Including	Size, $W \times T$	Width, W		Thickness, T		Keyway in Shaft Width, W_s		Keyway in Hub Width, W_h		Depth in Shaft, H		Depth in Hub at Deep End of Keyway, h			A	B	C	D	
			Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.						
1	1¼	5/16 × 1/4	0.314	0.312	0.254	0.249	0.311	0.312	0.312	0.313	0.146	0.152	0.090	0.096	0.010	3/8	7/16	1/4	0.3	1/16
1¼	1½	3/8 × 1/4	0.377	0.375	0.254	0.249	0.374	0.375	0.375	0.376	0.150	0.156	0.086	0.092	0.010	7/16	7/16	9/32	0.3	1/16
1½	1¾	7/16 × 5/16	0.440	0.438	0.316	0.311	0.437	0.438	0.438	0.439	0.186	0.192	0.112	0.118	0.020	1/2	9/16	5/16	0.4	1/16
1¾	2	1/2 × 5/16	0.502	0.500	0.316	0.311	0.499	0.500	0.500	0.0.501	0.190	0.196	0.108	0.114	0.020	9/16	5/8	3/8	0.4	1/16
2	2½	5/8 × 7/16	0.627	0.625	0.442	0.437	0.624	0.625	0.625	0.626	0.260	0.266	0.162	0.168	0.020	11/16	3/4	7/16	0.5	1/8
2½	3	3/4 × 1/2	0.752	0.750	0.504	0.499	0.749	0.750	0.750	0.751	0.299	0.305	0.185	0.191	0.020	13/16	7/8	17/32	0.5	1/8
3	3½	7/8 × 5/8	0.877	0.875	0.630	0.624	0.874	0.875	0.875	0.876	0.370	0.376	0.239	0.245	0.062	15/16	1	21/32	0.6	1/8
3½	4	1 × 3/4	1.003	1.000	0.755	0.749	0.999	1.000	1.000	1.001	0.441	0.447	0.293	0.299	0.062	1 1/16	1 1/4	25/32	0.6	1/8
4	5	1 1/4 × 7/8	1.253	1.250	0.880	0.874	1.248	1.250	1.250	1252	0.518	0.524	0.340	0.346	0.062	1 5/16	1 1/2	27/32	0.7	1/4
5	6	1 1/2 × 1	1.504	1.500	1.007	0.999	1.498	1.500	1.500	1.502	0.599	0.605	0.384	0.390	0.062	1 9/16	1 5/8	1 1/32	0.7	1/4
6	7	1 3/4 × 1 1/4	1.754	1.750	1.257	1.249	1.748	1.750	1.750	1.752	0.740	0.746	0.493	0.499	0.125	1 13/16	2	1 7/32	0.8	1/4
7	8	2 × 1 3/8	2.005	2.000	1.382	1.374	1.998	2.000	2.000	2.002	0.818	0.824	0.539	0.545	0.125	2 1/16	2 1/4	1 13/32	0.8	1/4
8	9	2 1/4 × 1 1/2	2.255	2.250	1.509	1.499	2.248	2.250	2.250	2.252	0.897	0.905	0.581	0.589	0.125	2 5/16	2 1/2	1 9/16	0.9	3/8
9	10	2 1/2 × 1 5/8	2.505	2.500	1.634	1.624	2.498	2.500	2.500	2.502	0.975	0.983	0.628	0.636	0.187	2 9/16	2 3/4	1 11/16	0.9	3/8
10	11	2 3/4 × 1 7/8	2.755	2.750	1.884	1.874	2.748	2.750	2.750	2.752	1.114	1.122	0.738	0.746	0.187	2 13/16	3	1 15/16	1.0	3/8
11	12	3 × 2	3.006	3.000	2.014	1.999	2.998	3.000	3.000	3.002	1.195	1.203	0.782	0.790	0.187	3 1/16	3 1/4	2 1/16	1.0	3/8

[a] The key chamfer shall be the minimum to clear the keyway radius. Nominal values shall be given.
[b] Dimensions A, B, C, D, and R pertain to gib-head keys only.
All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. British Standard Square Taper Keys and Keyways, Gib-head or Plain *B.S. 46: Part I: 1958*



Diameter of Shaft		Key					Keyway in Shaft and Hub								Nominal Keyway Radius, r[a]	Gib-head[b]				
							Keyway in Shaft		Keyway in Hub				Depth in Hub at Deep End of Keyway, h							
Over	Up to and Including	Size $W \times T$	Width, W		Thickness, T		Width W_s		Width W_h		Depth in Shaft, H					A	B	C	D	Radius, R
			Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.						
1/4	1/2	1/8 × 1/8	0.127	0.125	0.129	0.124	0.124	0.125	0.125	0.126	0.072	0.078	0.039	0.045	0.010	3/16	1/4	5/32	0.1	1/32
1/2	3/4	3/16 × 3/16	0.190	0.188	0.192	0.187	0.187	0.188	0.188	0.189	0.107	0.113	0.067	0.073	0.010	1/4	3/8	7/32	0.2	1/32
3/4	1	1/4 × 1/4	0.252	0.250	0.254	0.249	0.249	0.250	0.250	0.251	0.142	0.148	0.094	0.100	0.010	5/16	7/16	9/32	0.2	1/16
1	1 1/4	5/16 × 5/16	0.314	0.312	0.316	0.311	0.311	0.312	0.312	0.313	0.177	0.183	0.121	0.127	0.010	3/8	9/16	11/32	0.3	1/16
1 1/4	1 1/2	3/8 × 3/8	0.377	0.375	0.379	0.374	0.374	0.375	0.375	0.376	0.213	0.219	0.148	0.154	0.010	7/16	5/8	13/32	0.3	1/16
1 1/2	1 3/4	7/16 × 7/16	0.440	0.438	0.442	0.437	0.437	0.438	0.438	0.439	0.248	0.254	0.175	0.181	0.020	1/2	3/4	15/32	0.4	1/16
1 3/4	2	1/2 × 1/2	0.502	0.500	0.504	0.499	0.499	0.500	0.500	0.501	0.283	0.289	0.202	0.208	0.020	9/16	7/8	17/32	0.4	1/16
2	2 1/2	5/8 × 5/8	0.627	0.625	0.630	0.624	0.624	0.625	0.625	0.626	0.354	0.360	0.256	0.262	0.020	11/16	1	21/32	0.5	1/8
2 1/2	3	3/4 × 3/4	0.752	0.750	0.755	0.749	0.749	0.750	0.750	0.751	0.424	0.430	0.310	0.316	0.020	13/16	1 1/4	25/32	0.5	1/8
3	3 1/2	7/8 × 7/8	0.877	0.875	0.880	0.874	0.874	0.875	0.875	0.876	0.495	0.501	0.364	0.370	0.062	15/16	1 3/8	29/32	0.6	1/8
3 1/2	4	1 × 1	1.003	1.000	1.007	0.999	0.999	1.000	1.000	1.001	0.566	0.572	0.418	0.424	0.062	1 1/16	1 5/8	1 1/32	0.6	1/8
4	5	1 1/4 × 1 1/4	1.253	1.250	1.257	1.249	1.248	1.250	1.250	1.252	0.707	0.713	0.526	0.532	0.062	1 5/16	2	1 5/32	0.7	1/4
5	6	1 1/2 × 1 1/2	1.504	1.500	1.509	1.499	1.498	1.500	1.500	1.502	0.848	0.854	0.635	0.641	0.062	1 9/16	2 1/2	1 17/32	0.7	1/4

[a] The key chamfer shall be the minimum to clear the keyway radius. Nominal values shall be given.

[b] Dimensions A, B, C, D, and R pertain to gib-head keys only.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions and Tolerances of British Woodruff Keys and Keyways.— Dimensions and tolerances are shown in Table 20. An optional alternative design of the Woodruff key that differs from the normal form in its depth is given in the illustration accompanying the table. The method of designating British Woodruff Keys is the same as the American method explained in the footnote on page 2369.



Table 20. British Standard Woodruff Keys and Keyways *BS 46: Part 1: 1958*

Key and Cutter No.	Key								Keyway								Optional Design		
	Nominal Fractional Size		Diameter *A*		Depth *B*		Thickness *C*		Width in Shaft, *D*		Width in Hub, *E*		Depth in Shaft, *F*		Depth in Hub at Center Line, *G*		Depth of Key, *H*		Dimension, *J*
	Width.	Dia.	Max.	Min.	Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Min.	Nom.
203	1/16	3/8	0.375	0.370	0.171	0.166	0.063	0.062	0.061	0.063	0.063	0.065	0.135	0.140	0.042	0.047	0.162	0.156	1/64
303	3/32	3/8	0.375	0.370	0.171	0.166	0.095	0.094	0.093	0.095	0.095	0.097	0.119	0.124	0.057	0.062	0.162	0.156	1/64
403	1/8	3/8	0.375	0.370	0.171	0.166	0.126	0.125	0.124	0.126	0.126	0.128	0.104	0.109	0.073	0.078	0.162	0.156	1/64
204	1/16	1/2	0.500	0.490	0.203	0.198	0.063	0.062	0.061	0.063	0.063	0.065	0.167	0.172	0.042	0.047	0.194	0.188	3/64
304	3/32	1/2	0.500	0.490	0.203	0.198	0.095	0.094	0.093	0.095	0.095	0.097	0.151	0.156	0.057	0.062	0.194	0.188	3/64
404	1/8	1/2	0.500	0.490	0.203	0.198	0.126	0.125	0.124	0.126	0.126	0.128	0.136	0.141	0.073	0.078	0.194	0.188	3/64
305	3/32	5/8	0.625	0.615	0.250	0.245	0.095	0.094	0.093	0.095	0.095	0.097	0.198	0.203	0.057	0.062	0.240	0.234	1/16
405	1/8	5/8	0.625	0.615	0.250	0.245	0.126	0.125	0.124	0.126	0.126	0.128	0.182	0.187	0.073	0.078	0.240	0.234	1/16
505	5/32	5/8	0.625	0.615	0.250	0.245	0.157	0.156	0.155	0.157	0.157	0.159	0.167	0.172	0.089	0.094	0.240	0.234	1/16
406	1/8	3/4	0.750	0.740	0.313	0.308	0.126	0.125	0.124	0.126	0.126	0.128	0.246	0.251	0.073	0.078	0.303	0.297	1/16

Copyright 2004, Industrial Press, Inc., New York, NY

Table 20. ***(Continued)*** **British Standard Woodruff Keys and Keyways** *BS 46: Part 1: 1958*

Key and Cutter No.	Key								Keyway								Optional Design		
	Nominal Fractional Size		Diameter *A*		Depth *B*		Thickness *C*		Width in Shaft, *D*		Width in Hub, *E*		Depth in Shaft, *F*		Depth in Hub at Center Line, *G*		Depth of Key, *H*		Dimension, *J*
	Width.	Dia.	Max.	Min.	Max.	Min.	Max.	Min.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Max.	Min.	Nom.
506	5/32	3/4	0.750	0.740	0.313	0.308	0.157	0.156	0.155	0.157	0.157	0.159	0.230	0.235	0.089	0.094	0.303	0.297	1/16
606	3/16	3/4	0.750	0.740	0.313	0.308	0.189	0.188	0.187	0.189	0.189	0.191	0.214	0.219	0.104	0.109	0.303	0.297	1/16
507	5/32	7/8	0.875	0.865	0.375	0.370	0.157	0.156	0.155	0.157	0.157	0.159	0.292	0.297	0.089	0.094	0.365	0.359	1/16
607	3/16	7/8	0.875	0.865	0.375	0.370	0.189	0.188	0.187	0.189	0.189	0.191	0.276	0.281	0.104	0.109	0.365	0.359	1/16
807	1/4	7/8	0.875	0.865	0.375	0.370	0.251	0.250	0.249	0.251	0.251	0.253	0.245	0.250	0.136	0.141	0.365	0.359	1/16
608	3/16	1	1.000	0.990	0.438	0.433	0.189	0.188	0.187	0.189	0.189	0.191	0.339	0.344	0.104	0.109	0.428	0.422	1/16
808	1/4	1	1.000	0.990	0.438	0.433	0.251	0.250	0.249	0.251	0.251	0.253	0.308	0.313	0.136	0.141	0.428	0.422	1/16
1008	5/16	1	1.000	0.990	0.438	0.433	0.313	0.312	0.311	0.313	0.313	0.315	0.277	0.282	0.167	0.172	0.428	0.422	1/16
609	3/16	1 1/8	1.125	1.115	0.484	0.479	0.189	0.188	0.187	0.189	0.189	0.191	0.385	0.390	0.104	0.109	0.475	0.469	5/64
809	1/4	1 1/8	1.125	1.115	0.484	0.479	0.251	0.250	0.249	0.251	0.251	0.253	0.354	0.359	0.136	0.141	0.475	0.469	5/64
1009	5/16	1 1/8	1.125	1.115	0.484	0.479	0.313	0.312	0.311	0.313	0.313	0.315	0.323	0.328	0.167	0.172	0.475	0.469	5/64
810	1/4	1 1/4	1.250	1.240	0.547	0.542	0.251	0.250	0.249	0.251	0.251	0.253	0.417	0.422	0.136	0.141	0.537	0.531	5/64
1010	5/16	1 1/4	1.250	1.240	0.547	0.542	0.313	0.312	0.311	0.313	0.313	0.315	0.386	0.391	0.167	0.172	0.537	0.531	5/64
1210	3/8	1 1/4	1.250	1.240	0.547	0.542	0.376	0.375	0.374	0.376	0.376	0.378	0.354	0.359	0.198	0.203	0.537	0.531	5/64
1011	5/16	1 3/8	1.375	1.365	0.594	0.589	0.313	0.312	0.311	0.313	0.313	0.315	0.433	0.438	0.167	0.172	0.584	0.578	3/32
1211	3/8	1 3/8	1.375	1.365	0.594	0.589	0.376	0.375	0.374	0.376	0.376	0.378	0.402	0.407	0.198	0.203	0.584	0.578	3/32
812	1/4	1 1/2	1.500	1.490	0.641	0.636	0.251	0.250	0.249	0.251	0.251	0.253	0.511	0.516	0.136	0.141	0.631	0.625	7/64
1012	5/16	1 1/2	1.500	1.490	0.641	0.636	0.313	0.312	0.311	0.313	0.313	0.315	0.480	0.485	0.167	0.172	0.631	0.625	7/64
1212	3/8	1 1/2	1.500	1.490	0.641	0.636	0.376	0.375	0.374	0.376	0.376	0.378	0.448	0.453	0.198	0.203	0.631	0.625	7/64

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. British Preferred Lengths of Plain (Parallel or Taper) and Gib-head Keys, Rectangular and Square Section *BS 46:Part 1:1958 (1985) Appendix*



Plain Key Size $W \times T$	Overall Length, L													
	¾	1	1¼	1½	1¾	2	2¼	2½	2¾	3	3½	4	4½	5	6
⅛ × ⅛	●	●													
3⁄16 × 3⁄16	●	●	●	●	●	●									
¼ × ¼	●	●	●	●	●	●	●	●	●	●					
5⁄16 × ¼	●	●	●	●	●	●	●	●	●	●					
5⁄16 × 5⁄16	●	●	●	●	●	●	●	●	●	●					
⅜ × ¼		●	●	●	●	●	●	●	●	●	●	●			
⅜ × ⅜		●	●	●	●	●	●	●	●	●	●	●			
7⁄16 × 5⁄16				●	●	●	●	●	●	●	●	●			
7⁄16 × 7⁄16					●	●	●	●	●	●	●	●	●	●	
½ × 5⁄16						●	●	●	●	●	●	●	●	●	
½ × ½						●	●	●	●	●	●	●	●	●	
5⁄8 × 7⁄16								●	●	●	●	●	●	●	
5⁄8 × 5⁄8															●
¾ × ½															●
¾ × ¾															●
⅞ × ⅝															●
⅞ × ⅞															●



Gib-head Key Size, $W \times T$	Overall Length, L															
	1½	1¾	2	2¼	2½	2¾	3	3½	4	4½	5	5½	6	6½	7	7½	8
3⁄16 × 3⁄16	●	●	●	●	●		●										
¼ × ¼	●	●	●	●	●	●	●	●	●								
5⁄16 × ¼			●	●	●	●	●	●	●								
5⁄16 × 5⁄16			●	●	●	●	●	●	●	●							
⅜ × ¼			●	●	●	●	●	●	●	●	●						
⅜ × ⅜			●	●	●	●	●	●	●	●	●	●	●				
7⁄16 × 5⁄16					●		●	●	●	●	●	●	●				
7⁄16 × 7⁄16					●		●	●	●	●	●	●	●				
½ × 5⁄16					●		●	●	●	●	●	●	●	●			
½ × ½					●		●	●	●	●	●	●	●	●			
5⁄8 × 7⁄16							●		●	●	●	●	●	●	●		
5⁄8 × 5⁄8									●	●	●	●	●	●	●		●
¾ × ½									●	●		●	●	●	●	●	●
¾ × ¾									●		●		●		●		●
⅞ × ⅝											●		●	●	●	●	●
⅞ × ⅞													●		●		●
1 × ¾													●		●	●	●
1 × 1													●		●		●

All dimension are in inches

Copyright 2004, Industrial Press, Inc., New York, NY

FLEXIBLE BELTS AND SHEAVES

Flexible belt drives are used in industrial power transmission applications, especially when the speeds of the driver and driven shafts must be different or when shafts must be widely separated. The trend toward higher speed prime movers and the need to achieve a slower, useful driven speed are additional factors favoring the use of belts. Belts have numerous advantages over other means of power transmission; these advantages include overall economy, cleanliness, no need for lubrication, lower maintenance costs, easy installation, dampening of shock loads, and the abilities to be used for clutching and variable speed power transmission between widely spaced shafts.

Calculations for Belts and Pulleys

Belt speed plays an important role in the amount of load a friction drive system can transmit. Higher speeds will require higher preloads (increased belt tension) to compensate for the higher centrifugal force. In positive drive (toothed belt) systems, higher speeds generate dynamic forces caused by unavoidable tolerance errors that may result in increased tooth or pin stresses and shorter belt life.

Pulley Diameters and Drive Ratios.— Minimum pulley diameters determined by belt manufacturers are based on the minimum radius that a belt can wrap around a pulley without stressing the load-carrying members. For positive drive systems, minimum pulley diameters are also determined by the minimum number of teeth that must be engaged with the sprocket to guarantee the operating load.

Diameters of driving and driven pulleys determine the velocity ratio of the input relative to the output shaft and are derived from the following formulas: for all belt systems, velocity ratio $V = D_{pi}/D_{po}$, and for positive (toothed) drive systems, velocity ratio $V = N_i/N_o$, where D_{pi} is the pitch diameter of the driving pulley, D_{po} is the pitch diameter of the driven pulley, N_i is the number of teeth on the driving pulley, and N_o is the number of teeth on the driven pulley. For most drive systems, a velocity ratio of 8:1 is the largest that should be attempted with a single reduction drive, and 6:1 is a reasonable maximum.

Wrap Angles and Center-to-Center Distances.— The radial distance for which the belt is in contact with the pulley surface, or the number of teeth in engagement for positive drive belts, is called the wrap angle. Belt and sprocket combinations should be chosen to ensure a wrap angle of about 120° around the smaller pulley. The wrap angle should not be less than 90°, especially with positive drive belts, because if too few teeth are in engagement, the belt may jump a tooth or pin and timing or synchronization may be lost.

For flat belts, the minimum allowable center-to-center distance (CD) for any belt-and-sprocket combination should be chosen to ensure a minimum wrap angle around the smaller pulley. For high-velocity systems, a good rule of thumb is a minimum CD equal to the sum of the pitch diameter of the larger sprocket and one-half the pitch diameter of the smaller sprocket. This formula ensures a minimum wrap angle of approxximately 120°, which is generally sufficient for friction drives and will ensure that positive drive belts do not jump teeth.

Pulley Center Distances and Belt Lengths.— Maximum center distances of pulleys should be about 15 to 20 times the pitch diameter of the smaller pulley. Greater spacing requires tight control of the belt tension because a small amount of stretch will cause a large drop in tension. Constant belt tension can be obtained by application of an adjustable tensioning pulley applied to the slack side of the belt. Friction drive systems using flat belts require much more tension than positive drive belt systems.

Belt length can be calculated from: $L = 2C + \pi(D_2 + D_1)/2 + (D_2 - D_1)^2/4C$ for friction drives, and length $L = 2C + \pi(D_2 + D_1)/2 + (D_2 + D_1)^2/4C$ for crossed belt friction belt drives, where C is the center distance, D_1 is the pitch diameter of the small pulley, and D_2 is

Copyright 2004, Industrial Press, Inc., New York, NY

the pitch diameter of the large pulley. For serrated belt drives, the length determined by use of these equations should be divided by the serration pitch. The belt length must then be adjusted to provide a whole number of serrations.

Pulley Diameters and Speeds.— If D = diameter of driving pulley, d = diameter of driven pulley, S = speed of driving pulley, and s = speed of driven pulley:

$$D = \frac{d \times s}{S}, \qquad d = \frac{D \times S}{s}, \qquad S = \frac{d \times s}{D}, \qquad \text{and} \qquad s = \frac{D \times S}{d}$$

Example 1: If the diameter of the driving pulley D is 24 inches, its speed is 100 rpm, and the driven pulley is to run at 600 rpm, the diameter of the driven pulley, $d = 24 \times 100/600 =$ 4 inches.

Example 2: If the diameter of the driven pulley d is 36 inches, its required speed is to be 150 rpm, and the speed of the driving pulley is to be 600 rpm, the diameter of the driving pulley $D = 36 \times 150/600 = 9$ inches.

Example 3: If the diameter of the driven pulley d is 4 inches, its required speed is 800 rpm, and the diameter of the driving pulley D is 26 inches, the speed of the driving pulley = $4 \times 800/26 = 123$ rpm.

Example 4: If the diameter of the driving pulley D is 15 inches and its speed is 180 rpm, and the diameter of the driven pulley d is 9 inches, then the speed of the driven pulley = $15 \times 180/9 = 300$ rpm.

Pulley Diameters in Compound Drive.— If speeds of driving and driven pulleys, A, B, C, and D (see illustration) are known, the first step in finding their diameters is to form a fraction with the driving pulley speed as the numerator and the driven pulley speed as the, denominator, and then reduce this fraction to its lowest terms. Resolve the numerator and the denominator into two pairs of factors (a pair being one factor in the numerator and one in the denominator) and, if necessary, multiply each pair by a trial number that will give pulleys of suitable diameters.

Example 5: If the speed of pulley A is 260 rpm and the required speed of pulley D is 720 rpm, find the diameters of the four pulleys. Reduced to its lowest terms, the fraction $260/720 = 13/36$, which represents the required speed ratio. Resolve this ratio $13/36$ into two factors:

$$\frac{13}{36} = \frac{1 \times 13}{2 \times 18}$$

Multiply by trial numbers 12 and 1 to get:

$$\frac{(1 \times 12) \times (13 \times 1)}{(2 \times 12) \times (18 \times 1)} = \frac{12 \times 13}{24 \times 18}$$



Compound Drive with Four Pulleys.

Copyright 2004, Industrial Press, Inc., New York, NY

The values 12 and 13 in the numerator represent the diameters of the *driven* pulleys, *B* and *D*, and the values 24 and 18 in the denominator represent the diameters of the *driving* pulleys, *A* and *C*, as shown in the illustration.

Speed of Driven Pulley in Compound Drive.— If diameters of pulleys *A*, *B*, *C*, and *D* (see illustration above), and speed of pulley *A* are known, the speed of the driven pulley *D* is found from:

$$\frac{\text{driving pulley diameter}}{\text{driven pulley diameter}} \times \frac{\text{driving pulley diameter}}{\text{driven pulley diameter}} \times \text{speed of first driving pulley}$$

Example 6: If the diameters of driving pulleys *A* and *C* are 18 and 24 inches, diameters of driven pulleys *B* and *D* are 12 and 13 inches, and the speed of driving pulley *A* is 260 rpm, speed of driven pulley

$$D = \frac{18 \times 24}{12 \times 13} \times 260 = 720 \text{ rpm}$$

Length of Belt Traversing Three Pulleys.— The length *L* of a belt traversing three pulleys, as shown in the diagram below, and touching them on one side only, can be found by the following formula.



Flat Belt Traversing Three Pulleys.

Referring to the diagram, R_1, R_2, and R_3 are the radii of the three pulleys; C_{12}, C_{13}, and C_{23} are the center distances; and α_1, α_2, and α_3 are the angles, in radians, of the triangle formed by the center distances. Then:

$$L = C_{12} + C_{13} + C_{23} + \frac{1}{2}\left[\frac{(R_2 - R_1)^2}{C_{12}} + \frac{(R_3 - R_1)^2}{C_{13}} + \frac{(R_3 - R_2)^2}{C_{23}}\right]$$
$$+\pi(R_1 + R_2 + R_3) - (\alpha_1 R_1 + \alpha_2 R_2 + \alpha_3 R_3)$$

Example 7: Assume $R_1 = 1, R_2 = 2, R_3 = 4, C_{12} = 10, C_{13} = 6, C_{23} = 8, \alpha_1 = 53.13$ degrees or 0.9273 radian, $\alpha_2 = 36.87$ degrees or 0.6435 radian, and $\alpha_3 = 90$ degrees or 1.5708 radians. Then:

$$L = 10 + 6 + 8 + \frac{1}{2}\left[\frac{(2-1)^2}{10} + \frac{(4-1)^2}{6} + \frac{(4-2)^2}{8}\right]$$
$$+\pi(1 + 2 + 4) + (0.9273 \times 1 + 0.6435 \times 2 + 1.5708 \times 4)$$
$$= 24 + 1.05 + 21.9911 - 8.4975 = 38.5436$$

Copyright 2004, Industrial Press, Inc., New York, NY

Power Transmitted By Belts.— With belt drives, the force that produces work acts on the rim of a pulley or sheave and causes it to rotate. Since a belt on a drive must be tight enough to prevent slip, there is a belt pull on both sides of a driven wheel. When a drive is stationary or operating with no power transmitted, the pulls on both sides of the driven wheel are equal. When the drive is transmitting power, however, the pulls are not the same. There is a tight side tension T_T and a slack side tension, T_S. The difference between these two pulls ($T_T - T_S$) is called *effective pull* or *net pull*. This effective pull is applied at the rim of the pulley and is the force that produces work.

Net pull equals horsepower (HP) × 33,000 ÷ belt speed (fpm). Belt speed in fpm can be set by changing the pulley, sprocket, or sheave diameter. The shaft speeds remain the same. Belt speed is directly related to pulley diameter. Double the diameter and the total belt pull is cut in half, reducing the load on the shafts and bearings.

A belt experiences three types of tension as it rotates around a pulley: working tension (tight side – slack side), bending tension, and centrifugal tension.

The *tension ratio* (R) equals tight side divided by slack side tension (measured in pounds). The larger R is, the closer a V-belt is to slipping—the belt is too loose. (Synchronous belts do not slip, because they depend on the tooth grip principle.)

In addition to working tension (tight side – slack side), two other tensions are developed in a belt when it is operating on a drive. *Bending tension* T_B occurs when the belt bends around the pulley. One part of the belt is in tension and the other is in compression, so compressive stresses also occur. The amount of tension depends on the belt's construction and the pulley diameter. *Centrifugal tension* (T_C) occurs as the belt rotates around the drive and is calculated by $T_C = MV^2$, where T_C is centrifugal tension in pounds, M is a constant dependent on the belt's weight, and V is the belt velocity in feet per minute. Neither the bending nor centrifugal tensions are imposed on the pulley, shaft, or bearing—only on the belt.

Combining these three types of tension results in *peak tension* which is important in determining the degree of performance or belt life: $T_{peak} = T_T + T_B + T_C$.

Measuring the Effective Length.— The effective length of a V-belt is determined by placing the belt on a measuring device having two equal diameter sheaves with standard groove dimensions. The shaft of one of the sheaves is fixed. A specified measuring tension is applied to the housing for the shaft of the other sheave, moving it along a graduated scale. The belt is rotated around the sheaves at least two revolutions of the belt to seat it properly in the sheave grooves and to divide the total tension equally between the two strands of the belt.

The effective length of the belt is obtained by adding the effective (outside) circumference of one of the measuring sheaves to twice the center distance. Synchronous belts are measured in a similar manner.

The following sections cover common belts used in industrial applications for power transmission and specified in Rubber Manufacturers Association (RMA), Mechanical Power Transmission Association (MPTA), and The Rubber Association of Canada (RAC) standards. The information presented does not apply to automotive or agricultural drives, for which other standards exist. The belts covered in this section are Narrow, Classical, Double, and Light-Duty V-Belts, V-Ribbed Belts, Variable-Speed Belts, 60 deg V-Belts, and Synchronous (Timing) Belts.

Flat Belting

Flat belting was originally made from leather because it was the most durable material available and could easily be cut and joined to make a driving belt suitable for use with cylindrical or domed pulleys. This type of belting was popular because it could be used to

Copyright 2004, Industrial Press, Inc., New York, NY

transmit high torques over long distances and it was employed in factories to drive many small machines from a large common power source such as a steam engine. As electric motors became smaller, more efficient, and more powerful, and new types of belts and chains were made possible by modern materials and manufacturing processes, flat belts fell out of favor. Flat belts are still used for some drive purposes, but leather has been replaced by other natural and synthetic materials such as urethanes, which can be reinforced by high-strength polyamide or steel fabrics to provide properties such as resistance to stretching. The high modulus of elasticity in these flat belts eliminates the need for periodic retensioning that is usually necessary with V-belts.

Driving belts can be given a coating of an elastomer with a high coefficient of friction, to enable belts to grip pulleys without the degree of tension common with earlier materials. Urethanes are commonly used for driving belts where high resistance to abrasion is required, and also resist attack by chemical solvents of most kinds. Flat belts having good resistance to high temperatures are also available. Typical properties of polyurethane belts include tensile strength up to 40,000 psi, depending on reinforcement type and Shore hardness of 85 to 95. Most polyurethane belts are installed under tension. The amount of tension varies with the belt cross-section, being greater for belts of small section. Belt tension can be measured by marking lines 10 inches apart on an installed belt, then applying tension until the separation increases by the desired percentage. For 2 per cent tension, lines on the tensioned belt would be 10.2 inches apart. Mechanical failure may result when belt tensioning is excessive, and 2 to 2.5 per cent elongation should be regarded as the limit.

Flat belts offer high load capacities and are capable of transmitting power over long distances, maintaining relative rotational direction, can operate without lubricants, and are generally inexpensive to maintain or replace when worn. Flat belt systems will operate with little maintenance and only periodic adjustment. Because they transmit motion by friction, flat belts have the ability to slip under excessive loads, providing a fail-safe action to guard against malfunctions. This advantage is offset by the problem that friction drives can both slip and creep so that they do not offer exact, consistent velocity ratios nor precision timing between input and output shafts. Flat belts can be made to any desired length, being joined by reliable chemical bonding processes.

Increasing centrifugal force has less effect on the load-carrying capacity of flat belts at high speeds than it has on V-belts, for instance. The low thickness of a flat belt, compared with a V-belt, places its center of gravity near the pulley surface. Flat belts therefore may be run at surface speeds of up to 16,000 or even 20,000 ft/min (81.28 and 101.6 m/s), although ideal speeds are in the range of 3,000 to 10,000 ft/min (15.25 to 50.8 m/s). Elastomeric drive surfaces on flat belts have eliminated the need for belt dressings that were often needed to keep leather belts in place. These surface coatings can also contain antistatic materials. Belt pulley wear and noise are low with flat belts shock and vibration are damped, and efficiency is generally greater than 98 per cent compared with 96 per cent for V-belts.

Driving belt load capacities can be calculated from torque $T = F(d/2)$ and horsepower $HP = T \times rpm/396{,}000$, where T is the torque in in-lb, F is the force transmitted in lb, and d is the pulley diameter in inches. Pulley width is usually about 10 per cent larger than the belt, and for good tracking, pulleys are often crowned by 0.012 to 0.10 inch for diameters in the range of 1.5 to 80 inches.

Before a belt specification is written, the system should be checked for exessive startup and shut-down loads, which sometimes are more than 10 per cent above operating conditions. In overcoming such loads, the belt will transmit considerably more force than during normal operation. Large starting and stopping forces will also shorten belt life unless they are taken into account during the design stage.

Flat Belt Pulleys.— Flat belt pulleys are usually made of cast iron, fabricated steel, paper, fiber, or various kinds of wood. They may be solid or split and in either case the hub may be split for clamping to the shaft.

Copyright 2004, Industrial Press, Inc., New York, NY

Pulley face widths are nominally the same as the widths of the belts they are to carry. The pulley face should be approximately one inch more than the belt width for belts under 12 inches wide, 2 inches more for belts from 12 to 24 inches wide, and 3 inches more for belts over 24 inches in width.

Belts may be made to center themselves by the use of crowned pulleys. The usual amount of crowning is $\frac{1}{8}$ inch per foot of pulley width. Thus, the difference in maximum and minimum radii of a crowned 6-inch wide pulley would be $\frac{1}{16}$ inch. Crowned pulleys have a rim section either with a convex curve or a flat V form. Flanges on the sides of flat belt pulleys are in general undesirable as the belt tends to crawl against them. Too much crown is undesirable because of the tendency to "break the belt's back." This is particularly true for riding idlers close to driving pulleys where the curvature of the belt changes rapidly from one pulley to the other. Here, the idler should under no circumstances be crowned and the adjacent pulley should have very little crown. Pulleys carrying shifting belts are not crowned.

Open belt drives connecting pulleys on short centers with one pulley considerably larger than the other may be unsatisfactory due to the small angle of wrap on the smaller pulley. This angle may be increased by the use of idler pulleys on one or both sides of the belt.

V-Belts

Narrow V-Belts ANSI/RMA IP-22.— Narrow V-belts serve the same applications as multiple, classical V-belts, but allow for a lighter, more compact drive. Three basic cross sections—3V and 3VX, 5V and 5VX, and 8V—are provided, as shown in Fig. 1. The 3VX and 5VX are molded, notched V-belts that have greater power capacity than conventional belts. Narrow V-belts are specified by cross section and effective length and have top widths ranging from $\frac{3}{8}$ to 1 inch.

Narrow V-belts usually provide substantial weight and space savings over classical belts. Some narrow belts can transmit up to three times the horsepower of conventional belts in the same drive space, or the same horsepower in one-third to one-half the space. These belts are designed to operate in multiples and are also available in the joined configuration.

Belt Cross Sections: Nominal dimensions of the three cross sections are given in Fig. 1.

Belt Size Designation: Narrow V-belt sizes are identified by a standard belt number. The first figure of this number followed by the letter V denotes the belt cross section. An X following the V indicates a notched cross section. The remaining figures show the effective belt length in tenths of an inch. For example, the number 5VX1400 designates a notched V-belt with a 5V cross section and an effective length of 140.0 in. Standard effective lengths of narrow V-belts are shown in Table 1.



Fig. 1. Nominal Narrow V-Belt Dimensions

Sheave Dimensions: Groove angles and dimensions for sheaves and face widths of sheaves for multiple belt drives are given in Tables 2a and 2b, along with various tolerance values. Standard sheave outside diameters are given in Table 3.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Narrow V-Belt Standard Effective Lengths *ANSI/RMA IP-22 (1983)*

Standard Length Designation[a]	Standard Effective Outside Length — Cross Section			Permissible Deviation from Standard Length	Matching Limits for One Set	Standard Length Designation[a]	Standard Effective Outside Length — Cross Section			Permissible Deviation from Standard Length	Matching Limits for One Set
	3V	5V	8V				3V	5V	8V		
250	25.0	…	…	±0.3	0.15	1060	106.0	106.0	106.0	±0.6	0.30
265	26.5	…	…	±0.3	0.15	1120	112.0	112.0	112.0	±0.6	0.30
280	28.0	…	…	±0.3	0.15	1180	118.0	118.0	118.0	±0.6	0.30
300	30.0	…	…	±0.3	0.15	1250	125.0	125.0	125.0	±0.6	0.30
315	31.5	…	…	±0.3	0.15	1320	132.0	132.0	132.0	±0.6	0.30
335	33.5	…	…	±0.3	0.15	1400	140.0	140.0	140.0	±0.6	0.30
355	35.5	…	…	±0.3	0.15	1500	…	150.0	150.0	±0.8	0.30
375	37.5	…	…	±0.3	0.15	1600	…	160.0	160.0	±0.8	0.45
400	40.0	…	…	±0.3	0.15	1700	…	170.0	170.0	±0.8	0.45
425	42.5	…	…	±0.3	0.15	1800	…	180.0	180.0	±0.8	0.45
450	45.0	…	…	±0.3	0.15	1900	…	190.0	190.0	±0.8	0.45
475	47.5	…	…	±0.3	0.15	2000	…	200.0	200.0	±0.8	0.45
500	50.0	50.0	…	±0.3	0.15	2120	…	212.0	212.0	±0.8	0.45
530	53.0	53.0	…	±0.4	0.15	2240	…	224.0	224.0	±0.8	0.45
560	56.0	56.0	…	±0.4	0.15	2360	…	236.0	236.0	±0.8	0.45
600	60.0	60.0	…	±0.4	0.15	2500	…	250.0	250.0	±0.8	0.45
630	63.0	63.0	…	±0.4	0.15	2650	…	265.0	265.0	±0.8	0.60
670	67.0	67.0	…	±0.4	0.30	2800	…	280.0	280.0	±0.8	0.60
710	71.0	71.0	…	±0.4	0.30	3000	…	300.0	300.0	±0.8	0.60
750	75.0	75.0	…	±0.4	0.30	3150	…	315.0	315.0	±1.0	0.60
800	80.0	80.0	…	±0.4	0.30	3350	…	335.0	335.0	±1.0	0.60
850	85.0	85.0	…	±0.5	0.30	3550	…	355.0	355.0	±1.0	0.60
900	90.0	90.0	…	±0.5	0.30	3750	…	…	375.0	±1.0	0.60
950	95.0	95.0	…	±0.5	0.30	4000	…	…	400.0	±1.0	0.75
1000	100.0	100.0	100.0	±0.5	0.30	4250	…	…	425.0	±1.2	0.75

[a] To specify belt size, use the Standard Length Designation prefixed by the cross section, for example, 5 V850.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2a. Narrow V-Belt Standard Sheave and Groove Dimensions *ANSI/RMA IP-22 (1983)*



Face Width of Standard and Deep Groove Sheaves = $s_g\,(N_g - 1) + 2S_e$, where N_g = number of grooves

Cross Section	Standard Groove Outside Diameter	Standard Groove Dimensions								Design Factors	
		Groove Angle, α, ±0.25 deg	b_g ±0.005	b_e (Ref)	h_g (Min)	R_B (Min)	d_B ±0.0005	S_g[a] ±0.015	S_e	Min Recommended OD	2a
3V	Up through 3.49	36	0.350	0.350	0.340	0.181	0.3438	0.406	0.344 (+0.099, −0.031)	2.65	0.050
	Over 3.49 up to and including 6.00	38				0.183					
	Over 6.00 up to and including 12.00	40				0.186					
	Over 12.00	42				0.188					
5V	Up through 9.99	38	0.600	0.600	0.590	0.329	0.5938	0.688	0.500 +0.125, −0.047)	7.10	0.100
	Over 9.99 up to and including 16.00	40				0.332					
	Over 16.00	42				0.336					
8V	Up through 15.99	38	1.000	1.000	0.990	0.575	1.0000	1.125	0.750 (+0.250, −0.062)	12.50	0.200
	Over 15.99 up to and including 22.40	40				0.580					
	Over 22.40	42				0.585					

[a] See footnote [b] following Table 2b.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Narrow V-Belt Standard Sheave and Groove Dimensions *ANSI/RMA IP-22 (1983)*

Cross Section	Deep Groove Outside Diameter	Deep Groove Dimensions[a]								Design Factors		
		Groove Angle, α, ±0.25 deg	b_g ±0.005	b_e (Ref)	h_s (Min)	R_B (Min)	d_B ±0.0005	S_g[b] ±0.015	S_e	Min Recommended OD	$2a$	$2h_e$
3V	Up through 3.71	36	0.421	0.350	0.449	0.070	0.3438	0.500	0.375 (+0.094, –0.031)	2.87	0.050	0.218
	Over 3.71 up to and including 6.22	38	0.425			0.073						
	Over 6.22 up to and including 12.22	40	0.429			0.076						
	Over 12.22	42	0.434			0.078						
5V	Up through 10.31	38	0.710	0.600	0.750	0.168	0.5938	0.812	0.562 (+0.125, – 0.047)	7.42	0.100	0.320
	Over 10.31 up to and including 16.32	40	0.716			0.172						
	Over 16.32	42	0.723			0.175						
8V	Up through 16.51	38	1.180	1.000	1.252	0.312	1.0000	1.312	0.844 (+0.250, –0.062)	13.02	0.200	0.524
	Over 16.51 up to and including 22.92	40	1.191			0.316						
	Over 22.92	42	1.201			0.321						

[a] Deep groove sheaves are intended for drives with belt offset such as quarter-turn or vertical shaft drives. They may also be necessary where oscillations in the center distance may occur. Joined belts will not operate in deep groove sheaves.

[b] Summation of the deviations from S_g for all grooves in any one sheave should not exceed ±0.031 in. The variations in pitch diameter between the grooves in any one sheave must be within the following limits: Up through 19.9 in. outside diameter and up through 6 grooves—0.010 in. (add 0.0005 in. for each additional groove). 20.0 in. and over on outside diameter and up through 10 grooves—0.015 in. (add 0.0005 in. for each additional groove). This variation can be obtained by measuring the distance across two measuring balls or rods placed in the grooves diametrically opposite each other. Comparing this "diameter over balls or rods" measurement between grooves will give the variation in pitch diameter.

Other Sheave Tolerances		
Outside Diameter	Radial Runout[a]	Axial Runout[a]
Up through 8.0 in. outside diameter ±0.020 in.	Up through 10.0 in. outside diameter 0.010 in.	Up through 5.0 in. outside diameter 0.005 in.
For each additional inch of outside diameter add ±0.0025 in.	For each additional inch of outside diameter add 0.0005 in.	For each additional inch of outside diameter add 0.001 in.

[a] Total indicator reading.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Standard Sheave Outside Diameters *ANSI/RMA IP-22, 1983*

3V			5V			8V		
Nom	Min	Max	Nom	Min	Max	Nom	Min	Max
2.65	2.638	2.680	7.10	7.087	7.200	12.50	12.402	12.600
2.80	2.795	2.840	7.50	7.480	7.600	13.20	13.189	13.400
3.00	2.953	3.000	8.00	7.874	8.000	14.00	13.976	14.200
3.15	3.150	3.200	8.50	8.346	8.480	15.00	14.764	15.000
3.35	3.346	3.400	9.00	8.819	8.960	16.00	15.748	16.000
3.55	3.543	3.600	9.25	9.291	9.440	17.00	16.732	17.000
3.65	3.642	3.700	9.75	9.567	9.720	18.00	17.717	18.000
4.00	3.937	4.000	10.00	9.843	10.000	19.00	18.701	19.000
4.12	4.055	4.120	10.30	10.157	10.320	20.00	19.685	20.000
4.50	4.409	4.480	10.60	10.433	10.600	21.20	20.866	21.200
4.75	4.646	4.720	10.90	10.709	10.880	22.40	22.047	22.400
5.00	4.921	5.000	11.20	11.024	11.200	23.60	23.622	24.000
5.30	5.197	5.280	11.80	11.811	12.000	24.80	24.803	25.200
5.60	5.512	5.600	12.50	12.402	12.600	30.00	29.528	30.000
6.00	5.906	6.000	13.20	13.189	13.400	31.50	31.496	32.000
6.30	6.299	6.400	14.00	13.976	14.200	35.50	35.433	36.000
6.50	6.496	6.600	15.00	14.764	15.000	40.00	39.370	40.000
6.90	6.890	7.000	16.00	15.748	16.000	44.50	44.094	44.800
8.00	7.874	8.000	18.70	18.701	19.000	50.00	49.213	50.000
10.00	9.843	10.000	20.00	19.685	20.000	52.00	51.969	52.800
10.60	10.433	10.600	21.20	20.866	21.200	63.00	62.992	64.000
12.50	12.402	12.600	23.60	23.622	24.000	71.00	70.866	72.000
14.00	13.976	14.200	25.00	24.803	25.200	79.00	78.740	80.000
16.00	15.748	16.000	28.00	27.953	28.400	99.00	98.425	100.000
19.00	18.701	19.000	31.50	31.496	32.000	…	…	…
20.00	19.685	20.000	37.50	37.402	38.000	…	…	…
25.00	24.803	25.200	40.00	39.370	40.000	…	…	…
31.50	31.496	32.000	44.50	44.094	44.800	…	…	…
33.50	33.465	34.000	50.00	49.213	50.000	…	…	…
…	…	…	63.00	62.992	64.000	…	…	…
…	…	…	71.00	70.866	72.000	…	…	…

All dimensions in inches. The nominal diameters were selected from R40 and R80 preferred numbers (see page 689).

Minimum Sheave Size: The recommended minimum sheave size depends on the rpm of the faster shaft. Minimum sheave diameters for each belt cross-section are listed in Table 3.

Cross Section Selection: The chart (Fig. 2, on page 2398) is a guide to the V-belt cross section to use for any combination of design horsepower and speed of the faster shaft. When the intersection of the design horsepower and speed of the faster shaft falls near a line between two areas on the chart, it is advisable to investigate the possibilities in both areas. Special circumstances (such as space limitations) may lead to a choice of belt cross section different from that indicated in the chart.

Horsepower Ratings: The horsepower ratings of narrow V-belts can be calculated using the following formula:

$$\text{HP} = d_p r[K_1 - K_2/d_p - K_3(d_p r)^2 - K_4 \log(d_p r)] + K_{SR} r$$

where d_p = the pitch diameter of the small sheave, in.; r = rpm of the faster shaft divided by 1000; K_{SR}, speed ratio correction factor (Table 4), and K_1, K_2, K_3, and K_4, cross section parameters, are listed in the accompanying Table 5. This formula gives the basic horsepower rating, corrected for the speed ratio. To obtain the horsepower per belt for an arc of contact other than 180° and for belts shorter or longer than average length, multiply the horsepower obtained from this formula by the length correction factor (Table 7) and the arc of contact correction factor (Table 6).

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Selection of Narrow V-Belt Cross Section

Table 4. Speed Ratio Correction Factors

	K_{SR}			K_{SR}	
	Cross Section			Cross Section	
Speed Ratio[a] Range	3VX	5VX	Speed Ratio[a] Range	5V	8V
1.00–1.01	0.0000	0.0000	1.00–1.01	0.0000	0.0000
1.02–1.03	0.0157	0.0801	1.02–1.05	0.0963	0.4690
1.04–1.06	0.0315	0.1600	1.06–1.11	0.2623	1.2780
1.07–1.09	0.0471	0.2398	1.12–1.18	0.4572	2.2276
1.10–1.13	0.0629	0.3201	1.19–1.26	0.6223	3.0321
1.14–1.18	0.0786	0.4001	1.27–1.38	0.7542	3.6747
1.19–1.25	0.0944	0.4804	1.39–1.57	0.8833	4.3038
1.26–1.35	0.1101	0.5603	1.58–1.94	0.9941	4.8438
1.36–1.57	0.1259	0.6405	1.95–3.38	1.0830	5.2767
Over 1.57	0.1416	0.7202	Over 3.38	1.1471	5.5892

[a] D_p/d_p, where D_p (d_p) is the pitch diameter of the large (small) sheave.

Table 5. Cross Section Correction Factors

Cross Section	K_1	K_2	K_3	K_4
3VX	1.1691	1.5295	1.5229×10^{-4}	0.15960
5VX	3.3038	7.7810	3.6432×10^{-4}	0.43343
5V	3.3140	10.123	5.8758×10^{-4}	0.46527
8V	8.6628	49.323	1.5804×10^{-3}	1.1669

Arc of Contact: Arc of contact on the small sheave may be determined by the formulas.

Exact formula: $$\text{Arc of Contact (deg)} = 2\cos^{-1}\left(\frac{D_e - d_e}{2C}\right)$$

Approximate formula: $$\text{Arc of Contact (deg)} = 180 - \frac{(D_e - d_e)60}{C}$$

where: D_e = Effective diameter of large sheave, inch
d_e = Effective diameter of small sheave, inch
C = Center distance, inch

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Arc of Contact Correction Factors

$\frac{D_e - d_e}{C}$	Arc of Contact, θ, on Small Sheave (deg)	Correction Factor	$\frac{D_e - d_e}{C}$	Arc of Contact, θ, on Small Sheave (deg)	Correction Factor
0.00	180	1.00	0.80	133	0.87
0.10	174	0.99	0.90	127	0.85
0.20	169	0.97	1.00	120	0.82
0.30	163	0.96	1.10	113	0.80
0.40	157	0.94	1.20	106	0.77
0.50	151	0.93	1.30	99	0.73
0.60	145	0.91	1.40	91	0.70
0.70	139	0.89	1.50	83	0.65

Table 7. Length Correction Factors

Standard Length Designation	Cross Section			Standard Length Designation	Cross Section		
	3V	5V	8V		3V	5V	8V
250	0.83			1180	1.12	0.99	0.89
265	0.84			1250	1.13	1.00	0.90
280	0.85			1320	1.14	1.01	0.91
300	0.86			1400	1.15	1.02	0.92
315	0.87			1500		1.03	0.93
335	0.88			1600		1.04	0.94
355	0.89			1700		1.05	0.94
375	0.90			1800		1.06	0.95
400	0.92			1900		1.07	0.96
425	0.93			2000		1.08	0.97
450	0.94			2120		1.09	0.98
475	0.95			2240		1.09	0.98
500	0.96	0.85		2360		1.10	0.99
530	0.97	0.86		2500		1.11	1.00
560	0.98	0.87		2650		1.12	1.01
600	0.99	0.88		2800		1.13	1.02
630	1.00	0.89		3000		1.14	1.03
670	1.01	0.90		3150		1.15	1.03
710	1.02	0.91		3350		1.16	1.04
750	1.03	0.92		3550		1.17	1.05
800	1.04	0.93		3750			1.06
850	1.06	0.94		4000			1.07
900	1.07	0.95		4250			1.08
950	1.08	0.96		4500			1.09
1000	1.09	0.96	0.87	4750			1.09
1060	1.10	0.97	0.88	5000			1.10
1120	1.11	0.98	0.88	…			…

Number of Belts: The number of belts required for an application is obtained by dividing the design horsepower by the corrected horsepower rating for one belt.

Classical V-Belts ANSI/RMA IP-20.— Classical V-belts are most commonly used in heavy-duty applications and include these standard cross sections: A, AX, B, BX, C, CX, D, and DX (Fig. 3, page 2403). Top widths range from ½ to 1¼ in. and are specified by cross section and nominal length. Classical belts can be teamed in multiples of two or more. These multiple drives can transmit up to several hundred horsepower continuously and absorb reasonable shock loads.

Belt Cross Sections: Nominal dimensions of the four cross sections are given in Fig. 3.

Belt Size Designation: Classical V-belt sizes are identified by a standard belt number consisting of a letter-numeral combination. The letter identifies the cross section; the numeral identifies the length as shown in Table 8. For example, A60 indicates an A cross section and a standard length designation of 60. An X following the section letter designation indicates a molded notch cross section, for example, AX60.

Copyright 2004, Industrial Press, Inc., New York, NY

Sheave Dimensions: Groove angles and dimensions for sheaves and the face widths of sheaves for multiple belt drives are given in Table 9, along with various tolerance values.

Table 8. Classical V-Belt Standard Datum Length *ANSI/RMA IP-20, 1988*

Standard Length Designation[a]	Standard Datum lengths				Permissible Deviations from Std. Datum Length	Matching Limits for One Set
	Cross Section					
	A, AX	B, BX	C, CX	D		
26	27.3	…	…	…	+0.6, –0.6	0.15
31	32.3	…	…	…	+0.6, –0.6	0.15
35	36.3	36.8	…	…	+0.6, –0.6	0.15
38	39.3	39.8	…	…	+0.7, –0.7	0.15
42	43.3	43.8	…	…	+0.7, –0.7	0.15
46	47.3	47.8	…	…	+0.7, –0.7	0.15
51	52.3	52.8	53.9	…	+0.7, –0.7	0.15
55	56.3	56.8	…	…	+0.7, –0.7	0.15
60	61.3	61.8	62.9	…	+0.7, –0.7	0.15
68	69.3	69.8	70.9	…	+0.7, –0.7	0.30
75	75.3	76.8	77.9	…	+0.7, –0.7	0.30
80	81.3	…	…	…	+0.7, –0.7	0.30
81	…	82.8	83.9	…	+0.7, –0.7	0.30
85	86.3	86.8	87.9	…	+0.7, –0.7	0.30
90	91.3	91.8	92.9	…	+0.8, –0.8	0.30
96	97.3	…	98.9	…	+0.8, –0.8	0.30
97	…	98.8	…	…	+0.8, –0.8	0.30
105	106.3	106.8	107.9	…	+0.8, –0.8	0.30
112	113.3	113.8	114.9	…	+0.8, –0.8	0.30
120	121.3	121.8	122.9	123.3	+0.8, –0.8	0.30
128	129.3	129.8	130.9	131.3	+0.8, –0.8	0.30
144	…	145.8	146.9	147.3	+0.8, –0.8	0.30
158	…	159.8	160.9	161.3	+1.0, –1.0	0.45
173	…	174.8	175.9	176.3	+1.0, –1.0	0.45
180	…	181.8	182.9	183.3	+1.0, –1.0	0.45
195	…	196.8	197.9	198.3	+1.1, –1.1	0.45
210	…	211.8	212.9	213.3	+1.1, –1.1	0.45
240	…	240.3	240.9	240.8	+1.3, –1.3	0.45
270	…	270.3	270.9	270.8	+1.6, –1.6	0.60
300	…	300.3	300.0	300.8	+1.6, –1.6	0.60
330	…	…	330.9	330.8	+2.0, –2.0	0.60
360	…	…	380.9	360.8	+2.0, –2.0	0.60
540	…	…	…	540.8	+3.3, –3.3	0.90
390	…	…	390.9	390.8	+2.0, –2.0	0.75
420	…	…	420.9	420.8	+3.3, –3.3	0.75
480	…	…	…	480.8	+3.3, –3.3	0.75
600	…	…	…	600.8	+3.3, –3.3	0.90
660	…	…	…	660.8	+3.3, –3.3	0.90

[a] To specify belt size use the Standard Length Designation prefixed by the letter indicating the cross section, e.g., B90.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Classical V-Belt Sheave and Groove Dimensions *ANSI/RMA IP-20, 1988*



Face Width of Standard and Deep Groove Sheaves = $S_g\,(N_g - 1) + 2S_e$, where N_g = number of grooves

Standard Groove Dimensions													Design Factors	
Cross Section		Datum[a] Diameter Range	α Groove Angle ±0.33°	b_d Ref	b_g		h_g Min	$2h_d$	R_B Min	d_B ±0.0005	S_g[b] ±0.025	S_e		Min Recom. Datum Diameter	$2a_p$
A, AX		Through 5.4	34	0.418	0.494	±0.005	0.460	0.250	0.148	0.4375	0.625	0.375	+0.090	A 3.0	0
		Over 5.4	38		0.504				0.149	(7/16)			−0.062	AX 2.2	
B, BX		Through 7.0	34	0.530	0.637	±0.006	0.550	0.350	0.189	0.5625	0.750	0.500	+0.120	B 5.4	0
		Over 7.0	38		0.650				0.190	(9/16)			−0.065	BX 4.0	
Combination	A, AX Belt	Through 7.4[c]	34	0.508[d]	0.612	±0.006	0.612	0.634[e]	0.230	0.5625 (9/16)	0.750	0.500	+0.120 −0.065	A 3.6[c]	0.37
		Over 7.4	38		0.625			0.602[e]	0.226					AX 2.8	
	B, BX Belt	Through 7.4[c]	34		0.612	±0.006		0.333[e]	0.230					B 5.7[c]	−0.01
		Over 7.4	38		0.625			0.334[e]	0.226					BX 4.3	
C, CX		Through 7.99	34	0.757	0.879	±0.007	0.750	0.400	0.274	0.7812 (25/32)	1.000	0.688	+0.160 −0.070	C 9.0 CX 6.8	0
		Over 7.99 to and incl. 12.0	36		0.887				0.276						
		Over 12.0	38		0.895				0.277						
D		Through 12.99	34	1.076	1.259	±0.008	1.020	0.600	0.410	1.1250 (1 1/8)	1.438	0.875	+0.220 −0.080	13.0	0
		Over 12.99 to and incl. 17.0	36		1.271				0.410						
		Over 17.0	38		1.283				0.411						

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. *(Continued)* Classical V-Belt Sheave and Groove Dimensions *ANSI/RMA IP-20, 1988*

Deep Groove Dimensions[f]												Design Factors	
Cross Section	Datum[a] Dia. Range	α Groove Angle ± 0.33°	b_g Ref	b_g	h_g Min	$2h_d$ Ref	R_B Min	d_B ± 0.0005	S_g[b] ± 0.025	S_e		Min Rec. Datum Diameter	$2a_p$
B, BX	Through 7.0	34	0.530	0.747 ± 0.006	0.730	0.710	0.007	0.5625	0.875	0.562	+ 0.120 − 0.065	B 5.4	0.36
	Over 7.0	38		0.774			0.008	(9/16)				BX 4.0	
C, CX	Through 7.99	34	0.757	1.066	1.055	1.010	− 0.035	0.7812 (25/32)	1.250	0.812	+ 0.160 − 0.070	C 9.0 CX 6.8	0.61
	Over 7.99 to and incl. 12.0	36		1.085 ± 0.007			− 0.032						
	Over 12.0	38		1.105			−0.031						
D	Through 12.99	34	1.076	1.513 ±0.008	1.435	1.430	−0.010	1.1250 (1 1/8)	1.750	1.062	+0.220 −0.080	13.0	0.83
	Over 12.99 to and incl. 17.0	36		1.514			−0.009						
	Over 17.0	38		1.569			−0.008						

[a] The A/AX, B/BX combination groove should be used when deep grooves are required for A or AX belts.

[b] Summation of the deviations from S_g for all grooves in any one sheave should not exceed ±0.050 in. The variation in datum diameter between the grooves in any one sheave must be within the following limits: Through 19.9 in. outside diameter and through 6 grooves: 0.010 in. (add 0.0005 in. for each additional groove). 20.0 in. and over on outside diameter and through 10 grooves: 0.015 in. (add 0.0005 in. for each additional groove). This variation can be obtained by measuring the distance across two measuring balls or rods placed diametrically opposite each other in a groove. Comparing this "diameter over balls or rods" measurement between grooves will give the variation in datum diameter.

[c] Diameters shown for combination grooves are outside diameters. A specific datum diameter does not exist for either A or B belts in combination grooves.

[d] The b_d value shown for combination grooves is the "constant width" point, but does not represent a datum width for either A or B belts ($2h_d = 0.340$ ref).

[e] $2h_d$ values for combination grooves are calculated based on b_d for A and B grooves.

[f] Deep groove sheaves are intended for drives with belt offset such as quarter-turn or vertical shaft drives. Joined belts will not operate in deep groove sheaves. Also, A and AX joined belts will not operate in A/AX and B/BX combination grooves.

Other Sheave Tolerances		
Outside Diameter	Radial Runout[a]	Axial Runout[a]
Through 8.0 in. outside diameter ±0.020 in. For each additional inch of outside diameter add ±0.005 in.	Through 10.0 in. outside diameter 0.010 in. For each additional inch of outside diameter add 0.0005 in.	Through 5.0 in. outside diameter 0.005 in. For each additional inch of outside diameter add 0.001 in.

[a] Total indicator readings.

A, AX & B, BX Combin. All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Minimum Sheave Size: The recommended minimum sheave size depends on the rpm of the faster shaft. Minimum sheave diameters for each cross-section belt are listed in Table 9.

Cross Section Selection: Use the chart (Fig. 4) as a guide to the Classical V-belt cross section for any combination of design horsepower and speed of the faster shaft. When the intersection of the design horsepower and speed of the faster shaft falls near a line between two areas on the chart, the possibilities in both areas should be investigated. Special circumstances (such as space limitations) may lead to a choice of belt cross section different from that indicated in the chart.



Fig. 3. Classical V-Belt Cross Sections

Horsepower Ratings: The horsepower rating formulas for classical V-belts are:

$$\textbf{A:}\,\mathrm{HP} = d_p r\left[1.004 - \frac{1.652}{d_p} - 1.547\times10^{-4}(d_p r)^2 - 0.2126\log(d_p r)\right] + 1.652r\left(1 - \frac{1}{K_{SR}}\right)$$

$$\textbf{AX:}\,\mathrm{HP} = d_p r\left[1.462 - \frac{2.239}{d_p} - 2.198\times10^{-4}(d_p r)^2 - 0.4238\log(d_p r)\right] + 2.239r\left(1 - \frac{1}{K_{SR}}\right)$$

$$\textbf{B:}\,\mathrm{HP} = d_p r\left[1.769 - \frac{4.372}{d_p} - 3.081\times10^{-4}(d_p r)^2 - 0.3658\log(d_p r)\right] + 4.372r\left(1 - \frac{1}{K_{SR}}\right)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$\textbf{BX:}\,\text{HP} = d_p r\left[2.051 - \frac{3.532}{d_p} - 3.097\times10^{-4}(d_p r)^2 - 0.5735\log(d_p r)\right] + 3.532r\left(1 - \frac{1}{K_{SR}}\right)$$

$$\textbf{C:}\,\text{HP} = d_p r\left[3.325 - \frac{12.07}{d_p} - 5.828\times10^{-4}(d_p r)^2 - 0.6886\log(d_p r)\right] + 12.07r\left(1 - \frac{1}{K_{SR}}\right)$$

$$\textbf{CX:}\,\text{HP} = d_p r\left[3.272 - \frac{6.655}{d_p} - 5.298\times10^{-4}(d_p r)^2 - 0.8637\log(d_p r)\right] + 6.655r\left(1 - \frac{1}{K_{SR}}\right)$$

$$\textbf{D:}\,\text{HP} = d_p r\left[7.160 - \frac{43.21}{d_p} - 1.384\times10^{-3}(d_p r)^2 - 1.454\log(d_p r)\right] + 43.21r\left(1 - \frac{1}{K_{SR}}\right)$$



Fig. 4. Selection of Classic V-Belt Cross Sections

In these equations, d_p = pitch diameter of small sheave, in.; r = rpm of the faster shaft divided by 1000; K_{SR} = speed ratio factor given in the accompanying Table 10. These formulas give the basic horsepower rating, corrected for the speed ratio. To obtain the horsepower per belt for an arc of contact other than 180 degrees and for belts shorter or longer than average length, multiply the horsepower obtained from these formulas by the length correction factor (Table 11) and the arc of contact correction factor (Table 12).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Speed Ratio Correction Factors

Speed Ratio[a] Range	K_{SR}	Speed Ratio[a] Range	K_{SR}
1.00–1.01	1.0000	1.15–1.20	1.0586
1.02–1.04	1.0112	1.21–1.27	1.0711
1.05–1.07	1.0226	1.28–1.39	1.0840
1.08–1.10	1.0344	1.40–1.64	1.0972
1.11–1.14	1.0463	Over 1.64	1.1106

[a] D_p/d_p, where D_p (d_p) is the pitch diameter of the large (small) sheave.

Table 11. Length Correction Factors

Std. Length Designation	Cross Section			
	A, AX	B, BX	C, CX	D
26	0.78	…	…	…
31	0.82	…	…	…
35	0.85	0.80	…	…
38	0.87	0.82	…	…
42	0.89	0.84	…	…
46	0.91	0.86	…	…
51	0.93	0.88	0.80	…
55	0.95	0.89	…	…
60	0.97	0.91	0.83	…
68	1.00	0.94	0.85	…
75	1.02	0.96	0.87	…
80	1.04	…	…	…
81	…	0.98	0.89	…
85	1.05	0.99	0.90	…
90	1.07	1.00	0.91	…
96	1.08	…	0.92	…
97	…	1.02	…	…
105	1.10	1.03	0.94	…
112	1.12	1.05	0.95	…
120	1.13	1.06	0.96	0.88
128	1.15	1.08	0.98	0.89
144	…	1.10	1.00	0.91
158	…	1.12	1.02	0.93
173	…	1.14	1.04	0.94
180	…	1.15	1.05	0.95
195	…	1.17	1.08	0.96
210	…	1.18	1.07	0.98
240	…	1.22	1.10	1.00
270	…	1.24	1.13	1.02
300	…	1.27	1.15	1.04
330	…	…	1.17	1.06
360	…	…	1.18	1.07
390	…	…	1.20	1.09
420	…	…	1.21	1.10
480	…	…	…	1.13
540	…	…	…	1.15
600	…	…	…	1.17
660	…	…	…	1.18

Number of Belts: The number of belts required for an application is obtained by dividing the design horsepower by the corrected horsepower rating for one belt.

Arc of Contact: Arc of contact on the small sheave may be determined by the formulas.

Exact formula: Arc of Contact (deg) $= 2\cos^{-1}\left(\frac{D_d - d_d}{2C}\right)$

Approximate formula: Arc of Contact (deg) $= 180 - \left(\frac{(D_d - d_d)60}{C}\right)$

where D_d = Datum diameter of large sheave or flat pulley, inch; d_d = Datum diameter of small sheave, inch; and, C = Center distance, inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Arc of Contact Correction Factors

$\frac{D_d - d_d}{C}$	Arc of Contact, θ, Small Sheave (deg)	Correction Factor		$\frac{D_d - d_d}{C}$	Arc of Contact, θ Small Sheave (deg)	Correction Factor	
		V-V	V-Flat[a]			V-V	V-Flat[a]
0.00	180	1.00	0.75	0.80	133	0.87	0.85
0.10	174	0.99	0.76	0.90	127	0.85	0.85
0.20	169	0.97	0.78	1.00	120	0.82	0.82
0.30	163	0.96	0.79	1.10	113	0.80	0.80
0.40	157	0.94	0.80	1.20	106	0.77	0.77
0.50	151	0.93	0.81	1.30	99	0.73	0.73
0.60	145	0.91	0.83	1.40	91	0.70	0.70
0.70	139	0.89	0.84	1.50	83	0.65	0.65

[a] A V-flat drive is one using a small sheave and a large diameter flat pulley.

Double V-Belts ANSI/RMA IP-21.— Double V-belts or hexagonal belts are used when power input or takeoff is required on both sides of the belt. Designed for use on "serpentine" drives, which consist of sheaves rotating in opposite directions, the belts are available in AA, BB, CC, and DD cross sections and operate in standard classical sheaves. They are specified by cross section and nominal length.

Belt Cross Sections: Nominal dimensions of the four cross sections are given in Fig. 5.

Belt Size Designation: Double V-belt sizes are identified by a standard belt number, consisting of a letter-numeral combination. The letters identify the cross section; the numbers identify length as shown in Column 1 of Table 13. For example, AA51 indicates an AA cross section and a standard length designation of 51.

Table 13. Double V-Belt Standard Effective Lengths *ANSI/RMA IP-21, 1984*

Standard Length Designation[a]	Standard Effetive Length Cross Section				Permissible Deviation from Standard Effective Length	Matching Limits for One Set
	AA	BB	CC	DD		
51	53.1	53.9	…	…	±0.7	0.15
55	…	57.9	…	…	±0.7	0.15
60	62.1	62.9	…	…	±0.7	0.15
68	70.1	70.9	…	…	±0.7	0.30
75	77.1	77.9	…	…	±0.7	0.30
80	82.1	…	…	…	±0.7	0.30
81	…	83.9	85.2	…	±0.7	0.30
85	87.1	87.9	89.2	…	±0.7	0.30
90	92.1	92.9	94.2	…	±0.8	0.30
96	98.1	…	100.2	…	±0.8	0.30
97	…	99.9	…	…	±0.8	0.30
105	107.1	107.9	109.2	…	±0.8	0.30
112	114.1	114.9	116.2	…	±0.8	0.30
120	122.1	122.9	124.2	125.2	±0.8	0.30
128	130.1	130.9	132.2	133.2	±0.8	0.30
144	…	146.9	148.2	149.2	±0.8	0.30
158	…	160.9	162.2	163.2	±1.0	0.45
173	…	175.9	177.2	178.2	±1.0	0.45
180	…	182.9	184.2	185.2	±1.0	0.45
195	…	197.9	199.2	200.2	±1.1	0.45
210	…	212.9	214.2	215.2	±1.1	0.45
240	…	241.4	242.2	242.7	±1.3	0.45
270	…	271.4	272.2	272.7	±1.6	0.60
300	…	301.4	302.2	302.7	±1.6	0.60
330	…	…	332.2	332.7	±2.0	0.60
360	…	…	362.2	362.7	±2.0	0.60

[a] To specify belt size use the Standard Length Designation prefixed by the letters indicating cross section; for example, BB90.

All dimensions in inches.

Sheave Dimensions: Groove angles and dimensions for sheaves and face widths of sheaves for multiple belt drives are given in Table 14, along with various tolerance values.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. Double V-Belt Sheave and Groove Dimensions *ANSI/RMA IP-21, 1984*



Face Width of Standard and Deep Groove Sheaves = $S_g (N_g - 1) + 2S_e$, where N_g = number of grooves

Standard Groove Dimensions											Drive Design Factors	
Cross Section	Outside Diameter Range	Groove Angle, α ±0.33°	b_g	h_g (Min.)	$2h_d$	R_B (Min.)	d_B ±0.0005	S_g[a] ±0.025	S_e		Min. Recomm. Outside Dia.	$2a_p$[b]
AA	Up through 5.65	34	0.494 ±0.005	0.460	0.250	0.148	0.4375	0.625	0.375	+0.090 −0.062	3.25	0.0
	Over 5.65	38	0.504			0.149	(7/16)					
BB	Up through 7.35	34	0.637 ±0.006	0.550	0.350	0.189	0.5625	0.750	0.500	+0.120 −0.065	5.75	0.0
	Over 7.35	38	0.650			0.190	(9/16)					
AA-BB	Up through 7.35	34	0.612 ±0.006	0.612	A = 0.750	0.230	0.5625	0.750	0.500	+0.120 −0.065	A = 3.620	A = 0.370
	Over 7.35	38	0.625		B = 0.350	0.226	(9/16)				B = 5.680	B = −0.070
CC	Up through 8.39	34	0.879	0.750	0.400	0.274	0.7812	1.000	0.688	+0.160 −0.070	9.4	0.0
	Over 8.39 up to and including 12.40	36	0.887 ±0.007			0.276	(25/32)					
	Over 12.40	38	0.895			0.277						
DD	Up through 13.59	34	1.259 ±0.008	1.020	0.600	0.410	1.1250	1.438	0.875	+0.220 −0.080	13.6	0.0
	Over 13.59 up to and including 17.60	36	1.271			0.410	(1 1/8)					
	Over 17.60	38	1.283			0.411						

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14. ***(Continued)*** **Double V-Belt Sheave and Groove Dimensions** *ANSI/RMA IP-21, 1984*

Deep Groove Dimensions[c]											Drive Design Factors	
Cross Section	Outside Diameter Range	Groove Angle, α ±0.33°	b_g	h_g (Min.)	$2h_d$	R_B (Min.)	d_B ±0.0005	S_g[a] ±0.025	S_e		Minimum Recommended Outside Diameter	$2a_p$
AA	Up through 5.96	34	0.589 ±0.005	0.615	0.560	−0.009 −0.008	0.4375 (7/16)	0.750	0.438	+0.090 −0.062	3.56	0.310
	Over 5.96	38	0.611									
BB	Up through 7.71	34	0.747 ±0.006	0.730	0.710	+0.007 +0.008	0.5625 (9/16)	0.875	0.562	+0.120 −0.065	6.11	0.360
	Over 7.71	38	0.774									
CC	Up through 9.00	34	1.066 1.085 1.105 } ±0.007	1.055	1.010	−0.035 −0.032 −0.031	0.7812 (25/32)	1.250	0.812	+0.160 −0.070	10.01	0.610
	Over 9.00 up to and including 13.01	36										
	Over 13.01	38										
DD	Up through 14.42	34	1.513 1.541 1.569 } ±0.008	1.435	1.430	−0.010 −0.009 −0.008	1.1250 (1 1/8)	1.750	1.062	+0.220 −0.080	14.43	0.830
	Over 14.42 up to and including 18.43	36										
	Over 18.43	38										

[a] Summation of the deviations from S_g for all grooves in any one sheave shall not exceed ±0.050 in. The variation in pitch diameter between the grooves in any one sheave must be within the following limits: Up through 19.9 in. outside diameter and up through 6 grooves: 0.010 in. (add 0.005 in. for each additional groove). 20.0 in. and over on outside diameter and up through 10 grooves: 0.015 in. (add 0.0005 in. for each additional groove). This variation can be obtained easily by measuring the distance across two measuring balls or rods placed diametrically opposite each other in a groove. Comparing this "diameter over balls or rods" measurement between grooves will give the variation in pitch diameter.

[b] The a_p values shown for the A/B combination sheaves are the geometrically derived values. These values may be different from those shown in manufacturer's catalogs.

[c] Deep groove sheaves are intended for drives with belt offset such as quarter-turn or vertical shaft drives.

Other Sheave Tolerances		
Outside Diameter	Radial Runout[a]	Axial Runout[a]
Up through 4.0 in. outside diameter ±0.020 in. For each additional inch of outside diameter add ±0.005 in.	Up through 10.0 in. outside diameter ±0.010 in. For each additional inch of outside diameter add 0.0005 in.	Up through 5.0 in. outside diameter 0.005 in. For each additional inch of outside diameter add 0.001 in.

[a] Total indicator reading.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Cross Section Selection: Use the chart (Fig. 6) as a guide to the double V-belt cross section for any combination of design horsepower and speed of the faster shaft. When the intersection of the design horsepower and speed of the faster shaft falls near a line between two areas on the chart, it is best to investigate the possibilities in both areas. Special circumstances (such as space limitations) may lead to a choice of belt cross section different from that indicated in the chart.



Fig. 5. Double-V Belt Cross Section



Fig. 6. Selection of Double V-Belt Cross Section

Effective Diameter Determination: Fig. 6 shows the relationship of effective diameter, outside diameter, and nomenclature diameter. Nomenclature diameter is used when ordering sheaves for double V-belt drives. The effective diameter is determined as follows:

$$\text{Effective diameter} = \text{Nomenclature diameter} + 2h_d - 2a_p$$

The values of $2h_d$ and $2a_p$ are given in Table 14.

Double V-belt Length Determination: The effective belt length of a specific drive may be determined by making a scaled layout of the drive. Draw the sheaves in terms of their effective diameters and in the position when a new belt is applied and first brought to driv-

Copyright 2004, Industrial Press, Inc., New York, NY

ing tension. Next, measure the tangents and calculate the effective arc length (AL_e) of each sheave (see Table 15 for a glossary of terms):

$$AL_e = \frac{d_e \theta}{115}$$

The effective length of the belt will then be the sum of the tangents and the connecting arc lengths. Manufacturers may be consulted for mathematical calculation of effective belt length for specific drive applications.

Table 15. Glossary of Terms for Double V-belt Calculations

AL_e	= Length, arc, effective, in.	R	= Ratio, tight side to slack side tension
$2a_p$	= Diameter, differential, pitch to outside, in.	$R/(R-1)$	= Factor, tension ratio
d	= Diameter, pitch, in. (same as effective diameter)	r	= Angular velocity, faster shaft, rpm/1000
d_e	= Diameter, effective, in.	S	= Speed, belt, fpm/1000
$2h_d$	= Diameter differential, nomenclature to outside, in.	T_e	= Tension, effective pull, lbf
K_f	= Factor, length – flex correction	T_r	= Tension, allowable tight side, lbf
L_e	= Length, effective, in.	T_S	= Tension, slack side, lbf
n	= Sheaves, number on drive	T_T	= Tension, tight side, lbf
P_d	= Power, design, horsepower (transmitted horsepower × service factor)	θ	= Angle, arc of belt contact, deg



Fig. 7. Effective, Outside, and Nomenclature Sheave Diameters

Number of Belts Determination: The number of belts required may be determined on the basis of allowable tight side tension rating (T_r) at the most severe sheave. The allowable tight side tensions per belt are given in Tables 16 through 19, and must be multiplied by the length-flex correction factors (K_f) listed in Table 20. To select the allowable tight side tension from the tables for a given sheave, the belt speed and effective diameter of the sheave in question are required.

Double V-Belt Drive Design Method: The fourteen drive design steps are as follows:

1) Number the sheaves starting from the driver in the opposite direction to belt rotation; include the idlers.

2) Select the proper service factor for each loaded driven unit.

3) Multiply the horsepower requirement for each loaded driven sheave by the corresponding service factor. This is the design horsepower at each sheave.

4) Calculate driver design horsepower. This hp is equal to the sum of all the driven design horsepowers.

5) Calculate belt speed (S) in thousands of feet per minute: $S = rd/3.820$.

6) Calculate effective tension (T_e) for each loaded sheave: $T_e = 33P_d/S$.

7) Determine minimum $R/(R-1)$ for each loaded sheave from Table 21 using the arc of contact determined from the drive layout.

Copyright 2004, Industrial Press, Inc., New York, NY

8) In most drives, slippage will occur first at the driver sheave. Assume this to be true and calculate T_T and T_S for the driver: $T_T = T_e\,[R/(R-1)]$ and $T_s = T_T - T_e$. Use $R/(R-1)$ from Step 7 and T_e from Step 6 for the driver sheave.

9) Starting with the first driven sheave, determine T_T and T_S for each segment of the drive. The T_T for the driver becomes T_S for that sheave and is equal to $T_T - T_e$. Proceed around the drive in like manner.

10) Calculate actual $R/(R-1)$ for each sheave using: $R/(R-1) = T_T/T_e = T_T/(T_T - T_S)$. The T_T and T_S values are for those determined in Step 9. If these values are equal to or greater than those determined in Step 7, the assumption that slippage will first occur at the driver is correct and the next two steps are not necessary. If the value is less, the assumption was not correct, so proceed with Step 11.

11) Take the sheave where the actual value $R/(R-1)$ (Step 10) is less than the minimum, as determined in Step 7, and calculate a new T_T and T_S for this sheave using the minimum $R/(R-1)$ as determined in Step 7: $T_T = T_e\,[R/(R-1)]$ and $T_S = T_T - T_e$.

12) Start with this sheave and recalculate the tension in each segment of the drive as in Step 9.

13) The length-flex factor (K_f) is taken from Table 20. Before using this table, calculate the value of L_e/n. Be sure to use the appropriate belt cross-section column when selecting the correction factor.

14) Beginning with the driver sheave, determine the number of belts (N_b) needed to satisfy the conditions at each loaded sheave using: $N_b = T_T/T_r K_f$. Note: T_T is tight side tension as determined in Step 9 or 11 and 12. T_r is allowable tight side tension as shown in Tables 18-21. K_f is the length-flex correction factor from Table 20. The sheave that requires the largest number of belts is the number of belts required for the drive. Any fraction of a belt should be treated as a whole belt.

Table 16. Allowable Tight Side Tension for an AA Section

Belt Speed (fpm)	Sheave Effective Diameter (in.)							
	3.0	3.5	4.0	4.5	5.0	5.5	6.0	6.5
200	30	46	57	66	73	79	83	88
400	23	38	49	58	65	71	76	80
600	18	33	44	53	60	66	71	75
800	14	30	41	50	57	63	67	72
1000	12	27	38	47	54	60	65	69
1200	9	24	36	45	52	57	62	66
1400	7	22	34	42	49	55	60	64
1600	5	20	32	40	47	53	58	62
1800	3	18	30	38	46	51	56	60
2000	1	16	28	37	44	50	54	58
2200	…	15	26	35	42	48	53	57
2400	…	13	24	33	40	46	51	55
2600	…	11	23	31	39	44	49	53
2800	…	9	21	30	37	43	47	51
3000	…	8	19	28	35	41	46	50
3200	…	6	17	26	33	39	44	48
3400	…	4	16	24	31	37	42	46
3600	…	2	14	23	30	35	40	44
3800	…	1	12	21	28	34	38	43
4000	…	…	10	19	26	32	37	41
4200	…	…	8	17	24	30	35	39
4400	…	…	6	15	22	28	33	37
4600	…	…	4	13	20	26	31	35
4800	…	…	2	11	18	24	29	33
5000	…	…	…	9	16	22	27	31
5200	…	…	…	7	14	20	24	28
5400	…	…	…	4	12	17	22	26
5600	…	…	…	2	9	15	20	24
5800	…	…	…	…	7	13	18	22

The allowable tight side tension must be evaluated for each sheave in the system (see Step 14). Values must be corrected by K_f from Table 20.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17. Allowable Tight Side Tension for a BB Section

Belt Speed (fpm)	Sheave Effective Diameter (in.)								
	5.0	5.5	6.0	6.5	7.0	7.5	8.0	8.5	9.0
200	81	93	103	111	119	125	130	135	140
400	69	81	91	99	107	113	118	123	128
600	61	74	84	92	99	106	111	116	121
800	56	68	78	87	94	101	106	111	115
1000	52	64	74	83	90	96	102	107	111
1200	48	60	71	79	86	93	98	103	107
1400	45	57	67	76	83	89	95	100	104
1600	42	54	64	73	80	86	92	97	101
1800	39	51	61	70	77	84	89	94	98
2000	36	49	59	67	74	81	86	91	96
2200	34	46	56	64	72	78	84	89	93
2400	31	43	53	62	69	75	81	86	90
2600	29	41	51	59	67	73	78	83	88
2800	26	38	48	57	64	70	76	81	85
3000	23	35	45	54	61	68	73	78	82
3200	21	33	43	51	59	65	70	75	80
3400	18	30	40	49	56	62	68	73	77
3600	15	27	37	46	53	59	65	70	74
3800	12	24	35	43	50	57	62	67	71
4000	9	22	32	40	47	54	59	64	69
4200	7	19	29	37	45	51	56	61	66
4400	4	16	26	34	42	48	53	58	63
4600	1	13	23	31	39	45	50	55	60
4800	…	10	20	28	35	42	47	52	57
5000	…	6	16	25	32	39	44	49	53
5200	…	3	13	22	29	35	41	46	50
5400	…	…	10	18	26	32	38	42	47
5600	…	…	6	15	22	29	34	39	43
5800	…	…	3	11	19	25	31	36	40

The allowable tight side tension must be evaluated for each sheave in the system (see Step 14). Values must be corrected by K_f from Table 20.

Table 18. Allowable Tight Side Tension for a CC Section

Belt Speed (fpm)	Sheave Effective Diameter (in.)								
	7.0	8.0	9.0	10.0	11.0	12.0	13.0	14.0	15.0
200	121	158	186	207	228	244	257	268	278
400	99	135	164	187	206	221	234	246	256
600	85	122	151	173	192	208	221	232	242
800	75	112	141	164	182	198	211	222	232
1000	67	104	133	155	174	190	203	214	224
1200	60	97	126	149	167	183	196	207	217
1400	54	91	120	142	161	177	190	201	211
1600	48	85	114	137	155	171	184	196	205
1800	43	80	108	131	150	166	179	190	200
2000	38	75	103	126	145	160	174	185	195
2200	33	70	98	121	140	155	169	180	190
2400	28	65	93	116	135	150	164	175	185
2600	23	60	88	111	130	145	159	170	180
2800	18	55	83	106	125	140	154	165	175
3000	13	50	78	101	120	135	149	160	170
3200	8	45	73	96	115	130	144	155	165
3400	3	39	68	91	110	125	138	150	160
3600	…	34	63	86	104	120	133	145	154
3800	…	29	58	80	99	115	128	139	149
4000	…	24	52	75	94	109	123	134	144
4200	…	18	47	70	88	104	117	128	138
4400	…	12	41	64	83	98	112	123	133
4600	…	7	35	58	77	93	106	117	127
4800	…	1	29	52	71	87	100	111	121
5000	…	…	23	46	65	81	94	105	115
5200	…	…	17	40	59	75	88	99	109
5400	…	…	11	34	53	68	81	93	103
5600	…	…	5	27	46	62	75	86	96
5800	…	…	…	21	40	55	68	80	90

The allowable tight side tension must be evaluated for each sheave in the system (see Step 14). Values must be corrected by K_f from Table 20.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19. Allowable Tight Side Tension for a DD Section

Belt Speed (fpm)	Sheave Effective Diameter (in.)								
	12.0	13.0	14.0	15.0	16.0	17.0	18.0	19.0	20.0
200	243	293	336	373	405	434	459	482	503
400	195	245	288	325	358	386	412	434	455
600	167	217	259	297	329	358	383	406	426
800	146	196	239	276	308	337	362	385	405
1000	129	179	222	259	291	320	345	368	389
1200	114	164	207	244	277	305	331	353	374
1400	101	151	194	231	263	292	318	340	361
1600	89	139	182	219	251	280	305	328	349
1800	78	128	170	207	240	269	294	317	337
2000	67	117	159	196	229	258	283	306	326
2200	56	106	149	186	218	247	272	295	316
2400	45	95	138	175	208	236	262	284	305
2600	35	85	128	165	197	226	251	274	294
2800	24	74	117	154	187	215	241	263	284
3000	14	64	106	144	176	205	230	253	273
3200	3	53	96	133	165	194	219	242	263
3400	…	42	85	122	155	183	209	231	252
3600	…	31	74	111	144	172	198	220	241
3800	…	20	63	100	132	161	186	209	230
4000	…	9	51	89	121	150	175	198	218
4200	…	…	40	77	109	138	163	186	207
4400	…	…	28	65	97	126	152	174	195
4600	…	…	16	53	85	114	139	162	183
4800	…	…	3	40	73	102	127	150	170
5000	…	…	…	28	60	89	114	137	158
5200	…	…	…	15	47	76	101	124	145
5400	…	…	…	1	34	62	88	111	131
5600	…	…	…	…	20	49	74	97	118
5800	…	…	…	…	6	35	60	83	104

The allowable tight side tension must be evaluated for each sheave in the system (see Step 14). Values must be corrected by K_f from Table 20.

Table 20. Length-Flex Correction Factors K_f

$\frac{L_e}{n}$	Belt Cross Section				$\frac{L_e}{n}$	Belt Cross Section			
	AA	BB	CC	DD		AA	BB	CC	DD
10	0.64	0.58	…	…	70	…	1.03	0.95	0.91
15	0.74	0.68	…	…	80	…	1.06	0.98	0.94
20	0.82	0.74	0.68	…	90	…	1.09	1.00	0.96
25	0.87	0.79	0.73	0.70	100	…	1.11	1.03	0.99
30	0.92	0.84	0.77	0.74	110	…	…	1.05	1.00
35	0.96	0.87	0.80	0.77	120	…	…	1.06	1.02
40	0.99	0.90	0.83	0.80	130	…	…	1.08	1.04
45	1.02	0.93	0.86	0.82	140	…	…	1.10	1.05
50	1.05	0.95	0.88	0.84	150	…	…	1.11	1.07
60	…	0.99	0.92	0.88	…	…	…	…	…

Tension Ratings: The tension rating formulas are:

$$\text{AA} \quad T_r = 118.5 - \frac{318.2}{d} - 0.8380S^2 - 25.76\log S$$

$$\text{BB} \quad T_r = 186.3 - \frac{665.1}{d} - 1.269S^2 - 39.02\log S$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{CC} \quad T_r = 363.9 - \frac{2060}{d} - 2.400S^2 - 73.77\log S$$

$$\text{DD} \quad T_r = 783.1 - \frac{7790}{d} - 5.078S^2 - 156.1\log S$$

where T_r = The allowable tight side tension for a double-V belt drive, lbf (not corrected for tension ratio or length-flex correction factor)

d = Pitch diameter of small sheave, inch

S = Belt speed, fpm/1000

Table 21. Tension Ratio/Arc of Contact Factors

Arc of Contact, θ (deg.)	Design $\frac{R}{R-1}$	Arc of Contact, θ(deg.)	Design $\frac{R}{R-1}$
300	1.07	170	1.28
290	1.08	160	1.31
280	1.09	150	1.35
270	1.10	140	1.40
260	1.11	130	1.46
250	1.12	120	1.52
240	1.13	110	1.60
230	1.15	100	1.69
220	1.16	90	1.81
210	1.18	80	1.96
200	1.20	70	2.15
190	1.22	60	2.41
180	1.25	50	2.77

Minimum Sheave Size: The recommended minimum sheave size depends on the rpm of the faster shaft. Minimum groove diameters for each belt cross section are listed in Table 14.

Light Duty V-Belts ANSI/RMA IP-23.— Light duty V-belts are typically used with fractional horsepower motors or small engines, and are designed primarily for fractional horsepower service. These belts are intended and specifically designed for use with small diameter sheaves and drives of loads and service requirements that are within the capacity of a single belt.



Fig. 8. Light Duty V-Belt Cross Sections

The four belt cross sections and sheave groove sizes are 2L, 3L, 4L, and 5L. The 2L is generally used only by OEMs and is not covered in the RMA standards.

Belt Cross Sections.— Nominal dimensions of the four cross sections are given in Fig. 8.

Belt Size Designation.— V-belt sizes are identified by a standard belt number, consisting of a letter-numeral combination. The first number and letter identify the cross section; the remaining numbers identify length as shown in Table 22. For example, a 3L520 belt has a 3L cross section and a length of 52.0 in.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 22. Light Duty V-Belt Standard Dimensions *ANSI/RMA IP-23, 1968*

Standard Effective Outside Length (in.) Cross Section				Permissible Deviation From Standard Effective Length (in.)	Standard Effective Outside Length (in.) Cross Section				Permissible Deviation From Standard Effective Length (in.)
2L	3L	4L	5L		2L	3L	4L	5L	
8	…	…	…	+0.12, –0.38	…	…	53	53	+0.25, –0.62
9	…	…	…	+0.12, –0.38	…	54	54	54	+0.25, –0.62
10	…	…	…	+0.12, –0.38	…	…	55	55	+0.25, –0.62
11	…	…	…	+0.12, –0.38	…	56	56	56	+0.25, –0.62
12	…	…	…	+0.12, –0.38	…	…	57	57	+0.25, –0.62
13	…	…	…	+0.12, –0.38	…	58	58	58	+0.25, –0.62
14	14	…	…	+0.12, –0.38	…	…	59	59	+0.25, –0.62
15	15	…	…	+0.12, –0.38	…	60	60	60	+0.25, –0.62
16	16	…	…	+0.12, –0.38	…	…	61	61	+0.31, –0.69
17	17	…	…	+0.12, –0.38	…	…	62	62	+0.31, –0.69
18	18	18	…	+0.12, –0.38	…	…	63	63	+0.31, –0.69
19	19	19	…	+0.12, –0.38	…	…	64	64	+0.31, –0.69
20	20	20	…	+0.12, –0.38	…	…	65	65	+0.31, –0.69
…	21	21	…	+0.25, –0.62	…	…	66	66	+0.31, –0.69
…	22	22	…	+0.25, –0.62	…	…	67	67	+0.31, –0.69
…	23	23	…	+0.25, –0.62	…	…	68	68	+0.31, –0.69
…	24	24	…	+0.25, –0.62	…	…	69	69	+0.31, –0.69
…	25	25	25	+0.25, –0.62	…	…	70	70	+0.31, –0.69
…	26	26	26	+0.25, –0.62	…	…	71	71	+0.31, –0.69
…	27	27	27	+0.25, –0.62	…	…	72	72	+0.31, –0.69
…	28	28	28	+0.25, –0.62	…	…	73	73	+0.31, –0.69
…	29	29	29	+0.25, –0.62	…	…	74	74	+0.31, –0.69
…	30	30	30	+0.25, –0.62	…	…	75	75	+0.31, –0.69
…	31	31	31	+0.25, –0.62	…	…	76	76	+0.31, –0.69
…	32	32	32	+0.25, –0.62	…	…	77	77	+0.31, –0.69
…	33	33	33	+0.25, –0.62	…	…	78	78	+0.31, –0.69
…	34	34	34	+0.25, –0.62	…	…	79	79	+0.31, –0.69
…	35	35	35	+0.25, –0.62	…	…	80	80	+0.62, –0.88
…	36	36	36	+0.25, –0.62	…	…	82	82	+0.62, –0.88
…	37	37	37	+0.25, –0.62	…	…	84	84	+0.62, –0.88
…	38	38	38	+0.25, –0.62	…	…	86	86	+0.62, –0.88
…	39	39	39	+0.25, –0.62	…	…	88	88	+0.62, –0.88
…	40	40	40	+0.25, –0.62	…	…	90	90	+0.62, –0.88
…	41	41	41	+0.25, –0.62	…	…	92	92	+0.62, –0.88
…	42	42	42	+0.25, –0.62	…	…	94	94	+0.62, –0.88
…	43	43	43	+0.25, –0.62	…	…	96	96	+0.62, –0.88
…	44	44	44	+0.25, –0.62	…	…	98	98	+0.62, –0.88
…	45	45	45	+0.25, –0.62	…	…	100	100	+0.62, –0.88
…	46	46	46	+0.25, –0.62	…	…	…	…	…
…	47	47	47	+0.25, –0.62	…	…	…	…	…
…	48	48	48	+0.25, –0.62					
…	49	49	49	+0.25, –0.62	…	…	…	…	…
…	50	50	50	+0.25, –0.62	…	…	…	…	…
…	…	51	51	+0.25, –0.62	…	…	…	…	…
…	52	52	52	+0.25, –0.62	…	…	…	…	…

All dimensions in inches.

Sheave Dimensions: Groove angles and dimensions for sheaves and various sheave tolerances are given in Table 23.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 23. Light Duty V-Belt Sheave and Groove Dimensions
ANSI/RMA IP-23, 1968



Belt Section	Effective Outside Diameter		α Groove Angle ±0°20′ (deg)	d_B Ball Diameter ±0.0005	$2K$	b_g (Ref)	h_g (min)	$2a$[a]
	Min. Recomm.	Range						
2L	0.8	Less Than 1.50	32	0.2188	0.176	0.240	0.250	0.04
		1.50 to 1.99	34		0.182			
		2.00 to 2.50	36		0.188			
		Over 2.50	38		0.194			
3L	1.5	Less Than 2.20	32	0.3125	0.177	0.364	0.406	0.06
		2.20 to 3.19	34		0.191			
		3.20 to 4.20	36		0.203			
		Over 4.20	38		0.215			
4L	2.5	Less Than 2.65	30	0.4375	0.299	0.490	0.490	0.10
		2.65 to 3.24	32		0.316			
		3.25 to 5.65	34		0.331			
		Over 5.65	38		0.358			
5L	3.5	Less Than 3.95	30	0.5625	0.385	0.630	0.580	0.16
		3.95 to 4.94	32		0.406			
		4.95 to 7.35	34		0.426			
		Over 7.35	38		0.461			

[a] The diameter used in calculating speed ratio and belt speed is obtained by subtracting the $2a$ value from the Effective Outside Diameter of the sheave.

Other Sheave Tolerances		
Outside Diameters	Outside Diameter Eccentricity[a]	Groove Side Wobble & Runout[a]
For outside diameters under 6.0 in. ±0.015 in.	For outside diameters 10.0 in. and under 0.010 in.	For outside diameters 20.0 in. and under 0.0015 in. per inch of outside diameter.
For outside diameters 6.0 to 12.0 in. ±0.020 in.	For each additional inch of outside diameter, add 0.0005 in.	For each additional inch of outside diameter, add 0.0005 in.
For outside diameters over 12.0 in. ±0.040 in.		

[a] Total indicator reading.

All dimensions in inches.

Horsepower Ratings: The horsepower ratings for light duty V-belts can be calculated from the following formulas:

Copyright 2004, Industrial Press, Inc., New York, NY

$$3L \quad HP = r\left(\frac{0.2164d^{0.91}}{r^{0.09}} - 0.2324 - 0.0001396r^2d^3\right)$$

$$4L \quad HP = r\left(\frac{0.4666d^{0.91}}{r^{0.09}} - 0.7231 - 0.0002286r^2d^3\right)$$

$$5L \quad HP = r\left(\frac{0.7748d^{0.91}}{r^{0.09}} - 1.727 - 0.0003641r^2d^3\right)$$

where $d = d_0 - 2a$; d_0 = effective outside diameter of small sheave, in.; r = rpm of the faster shaft divided by 1000. The corrected horsepower rating is obtained by dividing the horsepower rating by the combined correction factor (Table 24), which accounts for drive geometry and service factor requirements.

Table 24. Combined Correction Factors

Type of Driven Unit	Speed Ratio	
	Less than 1.5	1.5 and Over
Fans and blowers	1.0	0.9
Domestic laundry machines	1.1	1.0
Centrifugal pumps	1.1	1.0
Generators	1.2	1.1
Rotary compressors	1.2	1.1
Machine tools	1.3	1.2
Reciprocating pumps	1.4	1.3
Reciprocating compressors	1.4	1.3
Wood working machines	1.4	1.3

V-Ribbed Belts ANSI/RMA IP-26.— V-ribbed belts are a cross between flat belts and V-belts. The belt is basically flat with V-shaped ribs projecting from the bottom, which guide the belt and provide greater stability than that found in a flat belt. The ribs operate in grooved sheaves.

V-ribbed belts do not have the wedging action of a V-belt and thus operate at higher tensions. This design provides excellent performance in high-speed and serpentine applications, and in drives that utilize small diameter sheaves. The V-ribbed belt comes in five cross sections: H, J, K, L, and M, specified by effective length, cross section and number of ribs.

Belt Cross Sections: Nominal dimensions of the five cross sections are given in Table 25.

Table 25. Nominal Dimensions of V-Ribbed Belt Cross Sections
ANSI/RMA IP-26, 1977



$b_b = N_r \times S_g$, where N_r = number of ribs and S_g is sheave groove spacing

Cross Section	h_b	S_g	Standard Number of Ribs
H	0.12	0.063	…
J	0.16	0.092	4, 6, 10, 16, 20
K	0.24	0.140	…
L	0.38	0.185	6, 8, 10, 12, 14, 16, 18, 20
M	0.66	0.370	6, 8, 10, 12, 14, 16, 18, 20

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 26. V-Ribbed Belt Sheave and Groove Dimensions *ANSI/RMA IP-26, 1977*



Face width = $S_e\,(N_g - 1) + 2S_e$, where N_g is number of grooves

Cross Section	Minimum Recommended Outside Diameter	α Groove Angle ±0.25 (deg)	S_g[a]	r_t +0.005, −0.000	$2a$	r_b	h_g (min)	d_B ±0.0005	S_e
H	0.50	40	0.063 ±0.001	0.005	0.020	0.013 +0.000 −0.005	0.041	0.0469	0.080 +0.020 −0.010
J	0.80	40	0.092 ±0.001	0.008	0.030	0.015 +0.000 −0.005	0.071	0.0625	0.125 +0.030 −0.015
K	1.50	40	0.140 ±0.002	0.010	0.038	0.020 +0.000 −0.005	0.122	0.1093	0.125 +0.050 −0.000
L	3.00	40	0.185 ±0.002	0.015	0.058	0.015 +0.000 −0.005	0.183	0.1406	0.375 +0.075 −0.030
M	7.00	40	0.370 ±0.003	0.030	0.116	0.030 +0.000 −0.010	0.377	0.2812	0.500 +0.100 −0.040

[a] Summation of the deviations from S_g for all grooves in any one sheave shall not exceed ±0.010 in.

Other Sheave Tolerances[a]		
Outside Diameter	Radial Runout[b]	Axial Runout[b]
Up through 2.9 in. outside diameter ±0.010 in.	Up through 2.9 in. outside diameter 0.005 in.	0.001 in. per inch of outside diameter
Over 2.9 in. to and including 8.0 in. outside diameter ±0.020 in.	Over 2.9 in. to and including 10.0 in. outside diameter 0.010 in.	
For each additional inch of outside diameter over 8.0 in., add ±0.0025 in.	For each additional inch of outside diameter over 10.0 in., add 0.0005 in.	

[a] Variations in pitch diameter between the grooves in any one sheave must be within the following limits: Up through 2.9 in. outside diameter and up through 6 grooves, 0.002 in. (add 0.001 in. for each additional groove); over 2.9 in. to and including 19.9 in. and up through 10 grooves, 0.005 in. (add 0.0002 in. for each additional groove); over 19.9 in. and up through 10 grooves, 0.010 in. (add 0.0005 in. for each additional groove). This variation can be obtained by measuring the distance across two measuring balls or rods placed in the grooves diametrically opposite each other. Comparing this "diameter-over-balls or -rods" measurement between grooves will give the variation in pitch diameter.

[b] Total indicator reading.

All dimensions in inches

Copyright 2004, Industrial Press, Inc., New York, NY

Belt Size Designation: Belt sizes are identified by a standard belt number, which consists of belt effective length to the nearest tenth of an inch, a letter designating cross section, and the number of ribs. For example, 540L6 signifies a 54.0 in. effective length, L belt, six ribs wide.

Sheave Dimensions.: Groove angles and dimensions for sheaves and face widths of sheaves for multiple belt drives are given in Table 26, along with various tolerance values.

Cross Section Selection.: Use the chart (Fig. 9) as a guide to the V-ribbed belt cross section for any combination of design horsepower and speed of the faster shaft. When the intersection of the design horsepower and speed of the faster shaft falls near a line between two areas on the chart, the possibilities in both areas should be explored. Special circumstances (such as space limitations) may lead to a choice of belt cross section different from that indicated in the chart. H and K cross sections are not included because of their specialized use. Belt manufacturers should be contacted for specific data.



Fig. 9. Selection of V-Ribbed Belt Cross Section

Horsepower Ratings.: The horsepower rating formulas are:

$$\textbf{J:}\ \mathrm{HP} = d_p r\left[\frac{0.1240}{(d_p r)^{0.09}} - \frac{0.08663}{d_p} - 0.2318\times10^{-4}(d_p r)^2\right] + 0.08663r\left[1 - \frac{1}{K_{SR}}\right]$$

$$\textbf{L:}\ \mathrm{HP} = d_p r\left[\frac{0.5761}{(d_p r)^{0.09}} - \frac{0.8987}{d_p} - 1.018\times10^{-4}(d_p r)^2\right] + 0.8987r\left[1 - \frac{1}{K_{SR}}\right]$$

$$\textbf{M:}\ \mathrm{HP} = d_p r\left[\frac{1.975}{(d_p r)^{0.09}} - \frac{6.597}{d_p} - 3.922\times10^{-4}(d_p r)^2\right] + 6.597r\left[1 - \frac{1}{K_{SR}}\right]$$

In these equations, d_p = pitch diameter of the small sheave, in.; r = rpm of the faster shaft divided by 1000; K_{SR} = speed ratio factor given in the accompanying Table 30. These formulas give the maximum horsepower per rib recommended, corrected for the speed ratio. To obtain the horsepower per rib for an arc of contact other than 180 degrees, and for belts longer or shorter than the average length, multiply the horsepower obtained from these formulas by the length correction factor (Table 28) and the arc of contact correction factor (Table 29).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 27. V-Ribbed Belt Standard Effective Lengths *ANSI/RMA IP-26, 1977*

J Cross Section			L Cross Section			M Cross Section		
Standard Length Designation[a]	Standard Effective Length	Permissible Deviation From Standard Length	Standard Length Designation[a]	Standard Effective Length	Permissible Deviation From Standard Length	Standard Length Designation[a]	Standard Effective Length	Permissible Deviation From Standard Length
180	18.0	+0.2, –0.2	500	50.0	+0.2, –0.4	900	90.0	+0.4, –0.7
190	19.0	+0.2, –0.2	540	54.0	+0.2, –0.4	940	94.0	+0.4, –0.8
200	20.0	+0.2, –0.2	560	56.0	+0.2, –0.4	990	99.0	+0.4, –0.8
220	22.0	+0.2, –0.2	615	61.5	+0.2, –0.5	1060	106.0	+0.4, –0.8
240	24.0	+0.2, –0.2	635	63.5	+0.2, –0.5	1115	111.5	+0.4, –0.9
260	26.0	+0.2, –0.2	655	65.5	+0.2, –0.5	1150	115.0	+0.4, –0.9
280	28.0	+0.2, –0.2	675	67.5	+0.3, –0.6	1185	118.5	+0.4, –0.9
300	30.0	+0.2, –0.3	695	69.5	+0.3, –0.6	1230	123.0	+0.4, –1.0
320	32.0	+0.2, –0.3	725	72.5	+0.3, –0.6	1310	131.0	+0.5, –1.1
340	34.0	+0.2, –0.3	765	76.5	+0.3, –0.6	1390	139.0	+0.5, –1.1
360	36.0	+0.2, –0.3	780	78.0	+0.3, –0.6	1470	147.0	+0.6, –1.2
380	38.0	+0.2, –0.3	795	79.5	+0.3, –0.6	1610	161.0	+0.6, –1.2
400	40.0	+0.2, –0.4	815	81.5	+0.3, –0.7	1650	165.0	+0.6, –1.3
430	43.0	+0.2, –0.4	840	84.0	+0.3, –0.7	1760	176.0	+0.7, –1.4
460	46.0	+0.2, –0.4	865	86.5	+0.3, –0.7	1830	183.0	+0.7, –1.4
490	49.0	+0.2, –0.4	915	91.5	+0.4, –0.7	1980	198.0	+0.8, –1.6
520	52.0	+0.2, –0.4	975	97.5	+0.4, –0.8	2130	213.0	+0.8, –1.6
550	55.0	+0.2, –0.4	990	99.0	+0.4, –0.8	2410	241.0	+0.9, –1.6
580	58.0	+0.2, –0.5	1065	106.5	+0.4, –0.8	2560	256.0	+1.0, –1.8
610	61.0	+0.2, –0.5	1120	112.0	+0.4, –0.9	2710	271.0	+1.1, –2.2
650	65.0	+0.2, –0.5	1150	115.0	+0.4, –0.9	3010	301.0	+1.2, –2.4

[a] To specify belt size, use the standard length designation, followed by the letter indicating belt cross section and the number of ribs desired. For example: 865L10.

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 28. Length Correction Factors

Std. Length Designation	Cross Section			Std. Length Designation	Cross Section		
	J	L	M		J	L	M
180	0.83	…	…	1230	…	1.08	0.94
200	0.85	…	…	1310	…	1.10	0.96
240	0.89	…	…	1470	…	1.12	0.098
280	0.92	…	…	1610	…	1.14	1.00
320	0.95	…	…	1830	…	1.17	1.03
360	0.98	…	…	1980	…	1.19	1.05
400	1.00	…	…	2130	…	1.21	1.06
440	1.02	…	…	2410	…	1.24	1.09
500	1.05	0.89	…	2710	…	…	1.12
550	1.07	0.91	…	3010	…	…	1.14
610	1.09	0.93	…	3310	…	…	1.16
690	1.12	0.96	…	3610	…	…	1.18
780	1.16	0.98	…	3910	…	…	1.20
910	1.18	1.02	0.88	4210	…	…	1.22
940	1.19	1.02	0.89	4810	…	…	1.25
990	1.20	1.04	0.90	5410	…	…	1.28
1060	…	1.05	0.91	6000	…	…	1.30
1150	…	1.07	0.93	…	…	…	…

Table 29. Arc of Contact Correction Factors

$\frac{D_o - d_o}{C}$	Arc of Contact, θ, on Small Sheave, (deg)	Correction Factor
0.00	180	1.00
0.10	174	0.98
0.20	169	0.97
0.30	163	0.95
0.40	157	0.94
0.50	151	0.92
0.60	145	0.90
0.70	139	0.88
0.80	133	0.85
0.90	127	0.83
1.00	120	0.80
1.10	113	0.77
1.20	106	0.74
1.30	99	0.71
1.40	91	0.67
1.50	83	0.63

Number of Ribs: The number of ribs required for an application is obtained by dividing the design horsepower by the corrected horsepower rating for one rib.

Arc of contact on the small sheave may be determined by the following formulas:

Exact Formula: Arc of Contact (deg) $= 2\cos^{-1}\left(\frac{D_o - d_o}{2C}\right)$

Approximate Formula: Arc of Contact (deg) $= 180 - \frac{(D_o - d_o)60}{C}$ where

Copyright 2004, Industrial Press, Inc., New York, NY

D_o = Effective outside diameter of large sheave, in; d_o = Effective outside diameter of small sheave, in; and, C = Center distance, inch.

Table 30. Speed Ratio Correction Factors

Speed Ratio[a]	K_{SR}
1.00 to and incl. 1.10	1.0000
Over 1.01 to and incl. 1.04	1.0136
Over 1.04 to and incl. 1.08	1.0276
Over 1.08 to and incl. 1.12	1.0419
Over 1.12 to and incl. 1.18	1.0567
Over 1.18 to and incl. 1.24	1.0719
Over 1.24 to and incl. 1.34	1.0875
Over 1.34 to and incl. 1.51	1.1036
Over 1.51 to and incl. 1.99	1.1202
Over 1.99	1.1373

[a] D_p/d_p, where D_p (d_p) is the pitch diameter of the large (small) sheave.

Variable Speed Belts ANSI/ RMA IP-25.— For drives that require more speed variation than can be obtained with conventional industrial V-belts, standard-line variable-speed drives are available. These drives use special wide, thin belts. Package units of standard-line variable-speed belts and sheaves, combined with the motor and output gearbox are available in ranges from approximately ½ through 100 horsepower.

The speed ranges of variable-speed drives can be much greater than those drives using classical V-belts. Speed ranges up to 10:1 can be obtained on lower horsepower units.

This section covers 12 variable speed belt cross sections and sheave groove sizes designed 1422V, 1922V, 2322V 1926V, 2926V, 3226V, 2530V, 3230V, 4430V, 4036V, 4436V, and 4836V. The industry supplies many other sizes that are not listed in this section.

Belt Cross Sections and Lengths: Nominal dimensions of the 12 cross sections are given in Table 31, and lengths in Table 32.

Table 31. Normal Variable-Speed Belt Dimensions *ANSI/RMA IP-25, 1982*



Cross Section	b_b	h_b	h_b/b_b	Cross Section	b_b	h_b	h_b/b_b
1422V	0.88	0.31	0.35	2530V	1.56	0.59	0.38
1922V	1.19	0.38	0.32	3230V	2.00	0.62	0.31
2322V	1.44	0.44	0.31	4430V	2.75	0.69	0.25
1926V	1.19	0.44	0.37	4036V	2.50	0.69	0.28
2926V	1.81	0.50	0.28	4436V	2.75	0.72	0.26
3226V	2.0	0.53	0.27	4836V	3.00	0.75	0.25

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 32. Variable-Speed V-Belt Standard Belt Lengths *ANSI/RMA IP-25, 1982*

Standard Pitch Length Designation	Standard Effective Lengths — Cross Section												Permissible Deviations From Standard Length
	1422V	1922V	2322V	1926V	2926V	3226V	2530V	3230V	4430V	4036V	4436V	4836V	
315	32.1	…	…	…	…	…	…	…	…	…	…	…	±0.7
335	34.1	…	…	…	…	…	…	…	…	…	…	…	±0.7
355	36.1	36.2	…	36.3	…	…	…	…	…	…	…	…	±0.7
375	38.1	38.2	…	38.3	…	…	…	…	…	…	…	…	±0.7
400	40.6	40.7	40.8	40.8	…	…	…	…	…	…	…	…	±0.7
425	43.1	43.2	43.3	43.3	…	…	…	…	…	…	…	…	±0.8
450	45.6	45.7	45.8	45.8	…	…	…	…	…	…	…	…	±0.8
475	48.1	48.2	48.3	48.3	…	…	…	…	…	…	…	…	±0.8
500	50.6	50.7	50.8	50.8	…	…	50.9	…	…	…	…	…	±0.8
530	53.6	53.7	53.8	53.8	53.9	…	53.9	…	…	…	…	…	±0.8
560	56.6	56.7	56.8	56.8	56.9	56.9	56.9	57.1	57.3	57.3	57.3	57.4	±0.9
600	60.6	60.7	60.8	60.8	60.9	60.9	60.9	61.1	61.3	61.3	61.3	61.4	±0.9
630	63.6	63.7	63.8	63.8	63.9	63.9	63.9	64.1	64.3	64.3	64.3	64.4	±0.9
670	67.6	67.7	67.8	67.8	67.9	67.9	67.9	68.1	68.3	68.3	68.3	68.4	±0.9
710	71.6	71.7	71.8	71.8	71.9	71.9	71.9	72.1	72.3	72.3	72.3	72.4	±0.9
750	75.6	75.7	75.8	75.8	75.9	75.9	75.9	76.1	76.3	76.3	76.3	76.4	±1.0
800	…	80.7	80.8	80.8	80.9	80.9	80.9	81.1	81.3	81.3	81.3	81.4	±1.0
850	…	85.7	85.8	85.8	85.9	85.9	85.9	86.1	86.3	86.3	86.3	86.4	±1.1
900	…	90.7	90.8	90.8	90.9	90.9	90.9	91.1	91.3	91.3	91.3	91.4	±1.1
950	…	95.7	95.8	95.8	95.9	95.9	95.9	96.1	96.3	96.3	96.3	96.4	±1.1
1000	…	100.7	100.8	100.8	100.9	100.9	100.9	101.1	101.3	101.3	101.3	101.4	±1.2
1060	…	106.7	106.8	106.8	106.9	106.9	106.9	107.1	107.3	107.3	107.3	107.4	±1.2
1120	…	112.7	112.8	112.8	112.9	112.9	112.9	113.1	113.3	113.3	113.3	113.4	±1.2
1180	…	118.7	118.8	118.8	118.9	118.9	118.9	119.1	119.3	119.3	119.3	119.4	±1.3
1250	…	…	…	…	125.9	125.9	125.9	126.1	126.3	126.3	126.3	126.4	±1.3
1320	…	…	…	…	…	132.9	…	133.1	133.3	133.3	133.3	133.4	±1.3

All dimensions in inches.

The lengths given in this table are not necessarily available from all manufacturers. Availability should be investigated prior to design commitment.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 33. Variable-Speed Sheave and Groove Dimensions

Cross Section	Standard Groove Dimensions: Variable: α Groove Angle ±0.67 (deg)	Variable: b_g[a] Closed +0.000 −0.030	Variable: b_{go} Open Max	Variable: h_{gv} Min	Variable: S_g ±0.03	Companion: α Groove Angle ±0.33 (deg)	Companion: b_g ±0.010	Companion: h_g Min	Companion: S_g ±0.03	Drive Design Factors: Min. Recomm. Pitch Diameter	Drive Design Factors: 2a	Drive Design Factors: 2av Max	Drive Design Factors: CL Min
1422V	22	0.875	1.63	2.33	1.82	22	0.875	0.500	1.82	2.0	0.20	3.88	0.08
1922V	22	1.188	2.23	3.14	2.42	22	1.188	0.562	2.42	3.0	0.22	5.36	0.08
2322V	22	1.438	2.71	3.78	2.89	22	1.438	0.625	2.89	3.5	0.25	6.52	0.08
1926V	26	1.188	2.17	2.65	2.36	26	1.188	0.625	2.36	3.0	0.25	4.26	0.08
2926V	26	1.812	3.39	4.00	3.58	26	1.812	0.750	3.58	3.5	0.30	6.84	0.08
3226V	26	2.000	3.75	4.41	3.96	26	2.000	0.781	3.96	4.0	0.30	7.60	0.08
2530V	30	1.562	2.81	3.01	2.98	30	1.562	0.844	2.98	4.0	0.30	4.64	0.10
3230V	30	2.000	3.67	3.83	3.85	30	2.000	0.875	3.85	4.5	0.35	6.22	0.10
4430V	30	2.750	5.13	5.23	5.38	30	2.750	0.938	5.38	5.0	0.40	8.88	0.10
4036V	36	2.500	4.55	3.95	4.80	36	2.500	0.938	4.80	4.5	0.40	6.32	0.10
4436V	36	2.750	5.03	4.33	5.30	36	2.750	0.969	5.30	5.0	0.40	7.02	0.10
4836V	36	3.000	5.51	4.72	5.76	36	3.000	1.000	5.76	6.0	0.45	7.74	0.10

[a] The effective width (b_e), a reference dimension, is the same as the ideal top width of closed variable-speed sheave (b_g) and the ideal top width of the companion sheave (b_g).

Other Sheave Tolerances					
Outside Diameter		Radial Runout[a]		Axial Runout[a]	
Up through 4.0 in. outside diameter	±0.020 in.	Up through 10.0 in. outside diameter	0.010 in.	Up through 5.0 in. outside diameter	0.005 in.
For each additional inch of outside diameter add ±0.005 in.		For each additional inch of outside diameter add 0.0005 in.		For each additional inch of outside diameter add 0.001 in.	

[a] Total indicator reading.

Surface Finish			
Machined Surface Area	Max Surface Roughness Height, R_a (AA) (μ in.)	Machined Surface Area	Max Surface Roughness Height, R_a (AA) (μ in.)
V-Sheave groove sidewalls	125	Straight bores with 0.002 in. or less total tolerance	125
Rim edges and ID, Hub ends and OD	500	Taper and straight bores with total tolerance over 0.002 in.	250

All dimensions in inches, except where noted.

Copyright 2004, Industrial Press, Inc., New York, NY

Belt Size Designation: Variable-speed belt sizes are identified by a standard belt number. The first two digits denote the belt top width in sixteenths of an inch; the third and fourth digits indicate the angle of the groove in which the belt is designed to operate. Letter V (for variable) follows the first four digits. The digits after the V indicate pitch length to the nearest 0.1 in. For example, 1422V450 is a belt of $\frac{7}{8}$ in. ($\frac{14}{16}$ in.) nominal top width designed to operate in a sheave of 22 degree groove angle and having a pitch length of 45.0 in.

Sheave Groove Data: A variable speed sheave is an assembly of movable parts, designed to permit one or both flanges of the sheave to be moved axially causing a radial movement of the variable speed belt in the sheave groove. This radial movement permits stepless speed variation within the physical limits of the sheave and the belt. A companion sheave may be a solid sheave having a constant diameter and groove profile or another variable sheave. Variable speed sheave designs should conform to the dimensions in Table 33 and Fig. 10. The included angle of the sheaves, top width, and clearance are boundary dimensions. Groove angles and dimensions of companion sheaves should conform to Table 33 and Fig. 11. Various tolerance values are also given in Table 33.



Fig. 10. Variable Sheaves

Variable-Speed Drive Design: Variable-speed belts are designed to operate in sheaves that are an assembly of movable parts. The sheave design permits one or both flanges of the sheave to be moved axially, causing a radial movement of the variable-speed belt in the sheave groove. The result is a stepless speed variation within the physical limits of the sheave and the variable-speed belt. Therefore, besides transmitting power, variable-speed belt drives provide speed variation.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 11. Companion Sheaves

The factors that determine the amount of pitch diameter change on variable-speed sheaves are belt top width, belt thickness, and sheave angle. This pitch diameter change, combined with the selected operating pitch diameters for a sheave, determines the possible speed variation.

The range of output speeds from a variable-speed sheave drive is established by the companion sheave and is a function of the ratio of the pitch diameter of the companion sheave to the maximum and minimum pitch diameters of the variable sheave. Speed variation is usually obtained by varying the center distance between the two sheaves. This type of drive seldom exceeds a speed variation of 3:1.

For a single variable-speed sheave drive, the speed variation

$$\text{Speed variation} = \frac{\text{PD Max}}{\text{PD Min}} \text{ (of variable sheave)}$$

For a dual variable-speed sheave drive, which is frequently referred to as a compound drive because both sheaves are variable, the speed variation is

$$\text{Speed variation} = \frac{DR(DN)}{dr(dn)}$$

where DR = Max driver PD
DN = Max driven PD
dr = Min driver PD
dn = Min driven PD

With this design, the center distance is generally fixed and speed variation is usually accomplished by mechanically altering the pitch diameter of one sheave. In this type of drive, the other sheave is spring loaded to make an opposite change in the pitch diameter and to provide the correct belt tension. Speed variations of up to 10: 1 are common on this type of drive.

Speed Ratio Adjustment: All speed ratio changes must be made while the drives are running. Attempting to make adjustments while the unit is stopped creates unnecessary and possibly destructive forces on both the belt and sheaves. In stationary control drives, the belt tension should be released to allow the flanges to adjust without belt force interference.

Cross Section Selection: Selection of a variable speed belt cross section is based on the drive design horsepower and speed variation. Table 33 shows the maximum pitch diameter variation ($2av$) that each cross section can attain.

Horsepower Ratings: The general horsepower formulas for variable-speed belts are:

$$1422\text{V HP} = d_p r\left[0.4907(d_p r)^{-0.09} - \frac{0.8378}{d_p} - 0.000337(d_p r)^2\right] + 0.8378 r\left(1 - \frac{1}{K_{SR}}\right)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$1922\,\text{VHP} = d_p r\left[0.8502(d_p r)^{-0.09} - \frac{1.453}{d_p} - 0.000538(d_p r)^2\right] + 1.453r\left(1 - \frac{1}{K_{SR}}\right)$$

$$2322\,\text{VHP} = d_p r\left[1.189(d_p r)^{-0.09} - \frac{2.356}{d_p} - 0.000777(d_p r)^2\right] + 2.356r\left(1 - \frac{1}{K_{SR}}\right)$$

$$1926\,\text{VHP} = d_p r\left[1.046(d_p r)^{-0.09} - \frac{1.833}{d_p} - 0.000589(d_p r)^2\right] + 1.833r\left(1 - \frac{1}{K_{SR}}\right)$$

$$2926\,\text{VHP} = d_p r\left[1.769(d_p r)^{-0.09} - \frac{4.189}{d_p} - 0.001059(d_p r)^2\right] + 4.189r\left(1 - \frac{1}{K_{SR}}\right)$$

$$3226\,\text{VHP} = d_p r\left[2.073(d_p r)^{-0.09} - \frac{5.236}{d_p} - 0.001217(d_p r)^2\right] + 5.236r\left(1 - \frac{1}{K_{SR}}\right)$$

$$2530\,\text{VHP} = d_p r\left[2.395(d_p r)^{-0.09} - \frac{6.912}{d_p} - 0.001148(d_p r)^2\right] + 6.912r\left(1 - \frac{1}{K_{SR}}\right)$$

$$3230\,\text{VHP} = d_p r\left[2.806(d_p r)^{-0.09} - \frac{7.854}{d_p} - 0.001520(d_p r)^2\right] + 7.854r\left(1 - \frac{1}{K_{SR}}\right)$$

$$4430\,\text{VHP} = d_p r\left[3.454(d_p r)^{-0.09} - \frac{7.854}{d_p} - 0.002196(d_p r)^2\right] + 9.818r\left(1 - \frac{1}{K_{SR}}\right)$$

$$4036\,\text{VHP} = d_p r\left[3.566(d_p r)^{-0.09} - \frac{9.687}{d_p} - 0.002060(d_p r)^2\right] + 9.687r\left(1 - \frac{1}{K_{SR}}\right)$$

$$4436\,\text{VHP} = d_p r\left[4.041(d_p r)^{-0.09} - \frac{11.519}{d_p} - 0.002297(d_p r)^2\right] + 11.519r\left(1 - \frac{1}{K_{SR}}\right)$$

$$4836\,\text{VHP} = d_p r\left[4.564(d_p r)^{-0.09} - \frac{13.614}{d_p} - 0.002634(d_p r)^2\right] + 13.614r\left(1 - \frac{1}{K_{SR}}\right)$$

In these equations, d_p = pitch diameter of small sheave, in.; r = rpm of faster shaft divided by 1000; K_{SR} = speed ratio factor given in the accompanying Table 34. These formulas give the basic horsepower rating, corrected for the speed ratio. To obtain the horsepower for arcs of contact other than 180 degrees and for belts longer or shorter than average length, multiply the horsepower obtained from these formulas by the arc of contact correction factor (Table 36) and the length correction factor (Table 35).

Table 34. Speed Ratio Correction Factors

Speed Ratio[a]	K_{SR}	Speed Ratio[a]	K_{SR}
1.00–1.01	1.0000	1.19–1.24	1.0719
1.02–1.04	1.0136	1.25–1.34	1.0875
1.05–1.08	1.0276	1.35–1.51	1.1036
1.09–1.12	1.0419	1.52–1.99	1.1202
1.13–1.18	1.0567	2.0 and over	1.1373

[a] D_p/d_p, where D_p (d_p) is the pitch diameter of the large (small) sheave.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 35. Length Correction Factors

Standard Pitch Length Designation	Cross Section											
	1422V	1922V	2322V	1926V	2926V	3226V	2530V	3230V	4430V	4036V	4436V	4836V
315	0.93	…	…	…	…	…	…	…	…	…	…	…
335	0.94	…	…	…	…	…	…	…	…	…	…	…
355	0.95	0.90	…	0.90	…	…	…	…	…	…	…	…
375	0.96	0.91	…	0.91	…	…	…	…	…	…	…	…
400	0.97	0.92	0.90	0.92	…	…	…	…	…	…	…	…
425	0.98	0.93	0.91	0.93	…	…	…	…	…	…	…	…
450	0.99	0.94	0.92	0.94	…	…	…	…	…	…	…	…
475	1.00	0.95	0.93	0.95	…	…	…	…	…	…	…	…
500	1.01	0.95	0.94	0.95	…	…	0.90	…	…	…	…	…
530	1.02	0.96	0.95	0.96	0.92	…	0.92	…	…	…	…	…
560	1.03	0.97	0.96	0.97	0.93	0.92	0.93	0.91	0.90	0.91	0.91	0.92
600	1.04	0.98	0.97	0.98	0.94	0.93	0.94	0.93	0.92	0.93	0.92	0.93
630	1.05	0.99	0.98	0.99	0.95	0.94	0.95	0.94	0.93	0.94	0.93	0.94
670	1.06	1.00	0.99	1.00	0.97	0.95	0.96	0.95	0.94	0.95	0.95	0.95
710	1.07	1.01	1.00	1.01	0.98	0.96	0.98	0.96	0.96	0.96	0.96	0.96
750	1.08	1.02	1.01	1.02	0.99	0.98	0.99	0.97	0.97	0.97	0.97	0.98
800	…	1.03	1.02	1.03	1.00	0.99	1.00	0.99	0.99	0.99	0.99	0.99
850	…	1.04	1.03	1.04	1.01	1.00	1.01	1.00	1.00	1.00	1.00	1.00
900	…	1.05	1.04	1.05	1.02	1.01	1.02	1.01	1.01	1.01	1.01	1.01
950	…	1.06	1.05	1.06	1.03	1.02	1.04	1.02	1.03	1.02	1.02	1.02
1000	…	1.07	1.06	1.07	1.04	1.03	1.05	1.03	1.04	1.03	1.04	1.03
1060	…	1.08	1.07	1.07	1.06	1.04	1.06	1.05	1.06	1.05	1.05	1.04
1120	…	1.09	1.08	1.08	1.07	1.06	1.07	1.06	1.07	1.06	1.06	1.06
1180	…	1.09	1.09	1.09	1.08	1.07	1.08	1.07	1.08	1.07	1.07	1.07
1250	…	…	…	…	1.09	1.08	1.10	1.08	1.10	1.08	1.09	1.08
1320	…	…	…	…	…	1.09	…	1.09	1.11	1.09	1.10	1.09

Copyright 2004, Industrial Press, Inc., New York, NY

Rim Speed: The material and design selected for sheaves must be capable of withstanding the high rim speeds that may occur in variable-speed drives. The rim speed is calculated as follows: Rim speed (fpm) = (π/12) (D_o) (rpm).

Arc of Contact: Arc of contact on the small sheave may be determined by the formulas:

Exact Formula: Arc of Contact (deg) $= 2\cos^{-1}\left(\frac{D-d}{2C}\right)$

Approximate Formula: Arc of Contact (deg) $= 180 - \frac{(D-d)60}{C}$

where D = Pitch diameter of large sheave or flat pulley, inch
d = Pitch diameter of small sheave, inch
C = Center distance, inch

Table 36. Arc of Contact Correction Factors

$\frac{D-d}{C}$	Arc of Contact, θ, on Small Sheave, (deg)	Correction Factor	$\frac{D-d}{C}$	Arc of Contact, θ, on Small Sheave, (deg)	Correction Factor
0.00	180	1.00	0.80	0.80	0.87
0.10	174	0.99	0.90	0.90	0.85
0.20	169	0.97	1.00	1.00	0.82
0.30	163	0.96	1.10	1.10	0.80
0.40	157	0.94	1.20	1.20	0.77
0.50	151	0.93	1.30	1.30	0.73
0.60	145	0.91	1.40	1.40	0.70
0.70	139	0.89	1.50	1.50	0.65

60 Degree V-Belts.— 60 degree V-belts are ideal for compact drives. Their 60 degree angle and ribbed top are specifically designed for long life on small diameter sheaves. These belts offer extremely smooth operation at high speeds (in excess of 10,000 rpm) and can be used on drives with high speed ratios. They are available in 3M, 5M, 7M, and 11M (3, 5, 7, 11 mm) cross sections (top widths) and are commonly found in the joined configuration, which provides extra stability and improved performance. They are specified by cross section and nominal length; for example, a 5M315 designation indicates a belt having a 5 mm cross section and an effective length of 315 mm.

Industry standards have not yet been published for 60 degree V-belts. Therefore, belt manufacturers should be contacted for specific applications, specifications, and additional information.

SAE Standard V-Belts.— The data for V-belts and pulleys shown in Table 37 cover nine sizes, three of which — 0.250, 0.315, and 0.440 — were added in 1977 to conform to existing practice. This standard was reaffirmed in 1987.

V-belts are produced in a variety of constructions in a basic trapezoidal shape and are to be dimensioned in such a way that they are functional in pulleys dimensioned as described in the standard. Standard belt lengths are in increments of ½ inch up to and including 80 inches. Standard lengths above 80 inches up to and including 100 inches are in increments of 1 inch, without fractions. Standard belt length tolerances are based on the center distance and are as follows: For belt lengths of 50 inches or less, ± 0.12 inch; over 50 to 60 inches, inclusive, ± 0.16 inch; over 60 to 80 inches, inclusive, ± 0.19; and over 80 to 100 inches, inclusive, ± 0.22.

Belt Storage and Handling.— To achieve maximum belt performance, proper belt storage procedures should always be practiced. If belts are not stored properly, their performance can be adversely affected. Four key rules are:

1) Do not store belts on floors unless they are protected by appropriate packaging.

2) Do not store belts near windows where the belts may be exposed to direct sunlight or moisture.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 37. SAE V-Belt and Pulley Dimensions



SAE Size	Recommended Min. Eff Dia[a]	*A* Groove Angle (deg) ±0.5	*W* Eff. Groove Width	*D* Groove Depth Min	*d* Ball or Rod Dia (±0.0005)	2*K* 2 × Ball Extension	2*X*[b]	*S* Groove[c] Spacing (±0.015)
0.250	2.25	36	0.248	0.276	0.2188	0.164	0.04	0.315
0.315	2.25	36	0.315	0.354	0.2812	0.222	0.05	0.413
0.380	2.40	36	0.380	0.433	0.3125	0.154	0.06	0.541
0.440	2.75	36	0.441	0.512	0.3750	0.231	0.07	0.591
0.500	3.00	36	0.500	0.551	0.4375	0.314	0.08	0.661
11/16	3.00	34	0.597	0.551	0.500	0.258	0.00	0.778
	Over 4.00	36				0.280		
	Over 6.00	38				0.302		
3/4	3.00	34	0.660	0.630	0.5625	0.328	0.02	0.841
	Over 4.00	36				0.352		
	Over 6.00	38				0.374		
7/8	3.50	34	0.785	0.709	0.6875	0.472	0.04	0.966
	Over 4.50	36				0.496		
	Over 6.00	38				0.520		
1	4.00	34	0.910	0.827	0.8125	0.616	0.06	1.091
	Over 6.00	36				0.642		
	Over 8.00	38				0.666		

All dimensions in inches.

[a] Pulley effective diameters below those recommended should be used with caution, because power transmission and belt life may be reduced.

[b] The *X* dimension is radial; 2*X* is to be subtracted from the effective diameter to obtain "pitch diameter" for speed ratio calculations.

[c] These values are intended for adjacent grooves of the same effective width (*W*). Choice of pulley manufacture or belt design parameter may justify variance from these values. The *S* dimension should be the same on all multiple groove pulleys in a drive using matched belts. © 1990, SAE, Inc.

3) Do not store belts near electrical devices that may generate ozone (transformers, electric motors, etc.).

4) Do not store belts in areas where solvents or chemicals are present in the atmosphere.

Belts should be stored in a cool, dry environment. When stacked on shelves, the stacks should be short enough to avoid excess weight on the bottom belts, which may cause distortion. When stored in containers, the container size and contents should be sufficiently limited to avoid distortion.

V-Belts: A common method is to hang the belts on pegs or pin racks. Very long belts stored this way should use sufficiently large pins or crescent shaped "saddles" to prevent their weight from causing distortion.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 38. Service Factors for V-Belts

Driving Unit	*AC Motors:* Normal Torque, Squirrel Cage, Synchronous and Split Phase. *DC Motors:* Shunt Wound. *Engines:* Multiple Cylinder Internal Combustion.		
Types of Driven Machines	Intermittent Service (3–5 hours daily or seasonal)	Normal Service (8–10 hours daily)	Continuous Service (16–24 hours daily)
Agitators for liquids; Blowers and exhausters; Centrifugal pumps & compressors; Fans up to 10 horsepower; Light duty conveyors	1.1	1.2	1.3
Belt conveyors for sand, grain, etc.; Dough mixers; Fans over 10 horsepower; Generators; Line shafts; Laundry machinery; Machine tools; Punches, presses, shears; Printing machinery; Positive displacement rotary pumps; Revolving and vibrating screens	1.2	1.3	1.4
Brick machinery; Bucket elevators; Exciters; Piston compressors; Conveyors (drag, pan, screw); Hammer mills; Paper mill beaters; Piston pumps; Positive displacement blowers; Pulverizers; Saw mill and woodworking machinery; Textile machinery	1.4	1.5	1.6
Crushers (gyratory, jaw, roll); Mills (ball, rod, tube); Hoists; Rubber calendars, extruders, mills	1.5	1.6	1.8
Driving Unit	*AC Motors:* High Torque, High Slip, Repulsion-Induction, Single Phase, Series Wound, Slip Ring. *DC Motors:* Series Wound, Compound Wound. *Engines:* Single Cylinder Internal Combustion. *Line Shafts*, *Clutches*		
Types of Driven Machines	Intermittent Service (3–5 hours daily or seasonal)	Normal Service (8–10 hours daily)	Continuous Service (16–24 hours daily)
Agitators for liquids; Blowers and exhausters; Centrifugal pumps & compressors; Fans up to 10 horsepower; Light duty conveyors	1.1	1.2	1.3
Belt conveyors for sand, grain, etc.; Dough mixers; Fans over 10 horsepower; Generators; Line shafts; Laundry machinery; Machine tools; Punches, presses, shears; Printing machinery; Positive displacement rotary pumps; Revolving and vibrating screens	1.2	1.3	1.4
Brick machinery; Bucket elevators; Exciters; Piston compressors; Conveyors (drag, pan, screw); Hammer mills; Paper mill beaters; Piston pumps; Positive displacement blowers; Pulverizers; Saw mill and woodworking machinery; Textile machinery	1.4	1.5	1.6
Crushers (gyratory, jaw, roll); Mills (ball, rod, tube); Hoists; Rubber calendars, extruders, mills	1.5	1.6	1.8

The machines listed above are representative samples only. Select the group listed above whose load characteristics most closely approximate those of the machine being considered.

Joined V-belts, Synchronous Belts, V-Ribbed Belts: Like V-belts, these belts may be stored on pins or saddles with precautions taken to avoid distortion. However, belts of this type up to approximately 120 in. are normally shipped in a "nested" configuration and should be stored in the same manner. Nests are formed by laying a belt on its side on a flat surface and placing as many belts inside the first belt as possible without undue force. When the nests are tight and are stacked with each rotated 180° from the one below, they may be stacked without damage.

Belts of this type over 120 in. may be "rolled up" and tied for shipment. These rolls may be stacked for easy storage. Care should be taken to avoid small bend radii which could damage the belts.

Variable Speed Belts: Variable speed belts are more sensitive to distortion than most other belts, and should not be hung from pins or racks but stored on shelves in the sleeves in which they are shipped.

Service Factors: Service factors for V-belts are listed in Table 38.

Copyright 2004, Industrial Press, Inc., New York, NY

Synchronous Belts

Synchronous Belts ANSI/RMA IP-24.— Synchronous belts are also known as timing or positive-drive belts. These belts have evenly spaced teeth on their surfaces, which mesh with teeth on pulleys or sprockets to produce a positive, no-slip transmission of power. Such designs should not be confused with molded notched V-belts, which transmit power by means of the wedging action of the V-shape. Synchronous belts are used where driven shaft speeds must be synchronized to the rotation of the driver shaft and to eliminate the noise and maintenance problems of chain drives.

Standard Timing Belts: Conventional trapezoidal, or rectangular tooth, timing belts come in six cross sections, which relate to the pitch of the belt. Pitch is the distance from center to center of the teeth. The six basic cross sections or pitches are MXL (mini extra light), XL (extra light), L (light), H (heavy), XH (extra heavy), and XXH (double extra heavy) (Fig. 12). Belts are specified by pitch length, cross section (pitch), and width.

Double-sided timing belts have identical teeth on both sides of the belt and are used where synchronization is required from each belt face. They are available in XL, L, and H cross sections.

Size Designations: Synchronous belt sizes are identified by a standard number. The first digits specify the belt length to 0.1 in. followed by the belt section (pitch) designation. The digits following the belt section designation represent the nominal belt width times 100. For example, an L section belt 30.000 in. pitch length and 0.75 in. in width would be specified as a 300L075 synchronous belt.



Fig. 12. Standard Synchronous Belt Sections

The RMA nomenclature for double-sided belts is the same as for single-sided belts with the addition of the prefix “D” in front of the belt section. However, some manufacturers use their own designation system for double-sided belts.

Standard Sections: Belt sections are specified in terms of pitch. Table 40 gives the Standard Belt Sections and their corresponding pitches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 39. Service Factors for Synchronous Belt Drives

Driving Units	*AC Motors:* Normal Torque, Squirrel Cage, Synchronous and Split Phase. *DC Motors:* Shunt Wound. *Engines:* Multiple Cylinder Internal Combustion.		
Types of Driven Machines	Intermittent Service (3–5 hours daily or seasonal)	Normal Service (8–10 hours daily)	Continuous Service (16–24 hours daily)
Display, Dispensing, Projection, Medical equipment; Instrumentation; Measuring devices	1.0	1.2	1.4
Appliances, sweepers, sewing machines; Office equipment; Wood lathes, band saws	1.2	1.4	1.6
Conveyors: belt, light package, oven, screens, drums, conical	1.3	1.5	1.7
Agitators for liquids; Dough mixers; Drill presses, lathes; Screw machines, jointers; Circular saws, planes; Laundry, Paper, Printing machinery	1.4	1.6	1.8
Agitators for semiliquids; Brick machinery (except pug mills); Conveyor belt: ore, coal, sand; Line shafts; Machine tools: grinder, shaper, boring mill, milling machines; Pumps: centrifugal, gear, rotary	1.5	1.7	1.9
Conveyor: apron, pan, bucket, elevator; Extractors, washers; Fans, blowers; centifugal, induced draft exhausters; Generators & exciters; Hoists, elevators; Rubber calenders, mills, extruders; Saw mill, Textile machinery inc. looms, spinning frames, twisters	1.6	1.8	2.0
Centrifuges; Conveyors: flight, screw; Hammer mills; Paper pulpers	1.7	1.9	2.1
Brick & clay pug mills; Fans, blowers, propeller mine fans, positive blowers	1.8	2.0	2.2
Driving Units	*AC Motors:* High Torque, High Slip, Repulsion-Induction, Single Phase Series Wound and Slip Ring. *DC Motors:* Series Wound and Compound Wound. *Engines:* Single Cylinder Internal Combustion. *Line Shafts. Clutches.*		
Types of Driven Machines	Intermittent Service (3–5 hours daily or seasonal)	Normal Service (8–10 hours daily)	Continuous Service (16–24 hours daily)
Display, Dispensing, Projection, Medical equipment; Instrumentation; Measuring devices	1.2	1.4	1.6
Appliances, sweepers, sewing machines; Office equipment; Wood lathes, band saws	1.4	1.6	1.8
Conveyors: belt, light package, oven, screens, drums, conical	1.5	1.7	1.9
Agitators for liquids; Dough mixers; Drill presses, lathes; Screw machines, jointers; Circular saws, planes; Laundry, Paper, Printing machinery	1.6	1.8	2.0
Agitators for semiliquids; Brick machinery (except pug mills); Conveyor belt: ore, coal, sand; Line shafts; Machine tools:grinder, shaper, boring mill, milling machines; Pumps: centrifugal, gear, rotary	1.7	1.9	2.1
Conveyor: apron, pan, bucket, elevator; Extractors, washers; Fans, blowers; centifugal, induced draft exhausters; Generators & exciters; Hoists, elevators; Rubber calenders, mills, extruders; Saw mill, Textile machinery inc. looms, spinning frames, twisters	1.8	2.0	2.2
Centrifuges; Conveyors: flight, screw; Hammer mills; Paper pulpers	1.9	2.1	2.3
Brick & clay pug mills; Fans, blowers, propeller mine fans, positive blowers	2.0	2.2	2.4

Synchronous belts will not slip, and therefore must be belted for the highest loadings anticipated in the system. A minimum service factor of 2.0 is recommended for equipment subject to chocking.

Pitch Lengths: Standard belt pitch lengths, belt length designations, and numbers of teeth are shown in Table 42. Belt length tolerances are also given in this table; these tolerances apply to all belt sections and represent the total manufacturing tolerance on belt length.

Nominal Tooth Dimensions: Table 40 shows the nominal tooth dimensions for each of the standard belt sections. Tooth dimensions for single- and double-sided belts are identical.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 40. Synchronous Belt Nominal Tooth and Section Dimensions
ANSI/RMA IP-24, 1983



Single-Sided Belts



Double-Sided Belts

Belt Section (Pitch)	Tooth Angle	h_t	b_t	r_a	r_r	h_s	h_d
MXL (0.080)	40	0.020	0.045	0.005	0.005	0.045	…
XL (0.200)	50	0.050	0.101	0.015	0.015	0.090	…
L (0.375)	40	0.075	0.183	0.020	0.020	0.14	…
H (0.500)	40	0.090	0.241	0.040	0.040	0.16	…
XH (0.875)	40	0.250	0.495	0.047	0.062	0.44	…

Belt Section (Pitch)	Tooth Angle	h_t	b_t	r_a	r_r	h_s	h_d
XXH (1.250)	40	0.375	0.750	0.060	0.090	0.62	…
DXL (0.200)	50	0.050	0.101	0.015	0.015	…	0.120
DL (0.375)	40	0.075	0.183	0.020	0.020	…	0.180
DH (0.500)	40	0.090	0.241	0.040	0.040	…	0.234

All dimensions in inches.

Table 41. Synchronous Belt Standard Pulley and Flange Dimensions
ANSI/RMA IP-24, 1983



Flanged Pulley **Unflanged Pulley** **Flange Dimensions**

Belt Section	Standard Nominal Pulley Width	Standard Pulley Width Designation	Minimum Pulley Width		Flange	
			Flanged b_f	Unflanged b'_f	Thickness (min)	Height[a] (min)
MXL	0.25	025	0.28	0.35	0.023	0.020
XL	0.38	037	0.41	0.48	0.029	0.040
L	0.50	050	0.55	0.67	0.050	0.065
	0.75	075	0.80	0.92		
	1.00	100	1.05	1.17		
H	1.00	100	1.05	1.23	0.050	0.080
	1.50	150	1.55	1.73		
	2.00	200	2.08	2.26		
	3.00	300	3.11	3.29		
XH	2.00	200	2.23	2.46	0.098	0.190
	3.00	300	3.30	3.50		
	4.00	400	4.36	4.59		
XXH	2.00	200	2.23	2.52	0.127	0.245
	3.00	300	3.30	3.59		
	4.00	400	4.36	4.65		
	5.00	500	5.42	5.72		

Copyright 2004, Industrial Press, Inc., New York, NY

Table 42. Synchronous Belt Standard Pitch Lengths and Tolerances *ANSI/RMA IP-24, 1983*

Belt Length Designation	Pitch Length	Permissible Deviation From Standard Length	Number of Teeth for Standard Lengths						Belt Length Designation	Pitch Length	Permissible Deviation From Standard Length	Number of Teeth for Standard Lengths					
			MXL (0.080)	XL (0.200)	L (0.375)	H (0.500)	XH (0.875)	XXH (1.250)				MXL (0.080)	XL (0.200)	L (0.375)	H (0.500)	XH (0.875)	XXH (1.250)
36	3.600	±0.016	45						230	23.000	±0.024	…	115	…	…		
40	4.000	±0.016	50						240	24.000	±0.024	…	120	64	48		
44	4.400	±0.016	55						250	25.000	±0.024	…	125	…	…		
48	4.800	±0.016	60						255	25.500	±0.024	…	…	68	…		
56	5.600	±0.016	70						260	26.000	±0.024	…	130	…	…		
60	6.000	±0.016	75	30					270	27.000	±0.024	…	…	72	54		
64	6.400	±0.016	80	…					285	28.500	±0.024	…	…	76	…		
70	7.000	±0.016	…	35					300	30.000	±0.024	…	…	80	60		
72	7.200	±0.016	90	…					322	32.250	±0.026	…	…	86	…		
80	8.000	±0.016	100	40					330	33.000	±0.026	…	…	…	66		
88	8.800	±0.016	110	…					345	34.500	±0.026			92	…		
90	9.000	±0.016	…	45					360	36.000	±0.026			…	72		
100	10.000	±0.016	125	50					367	36.750	±0.026			98	…		
110	11.000	±0.018	…	55					390	39.000	±0.026			104	78		
112	11.200	±0.018	140	…					420	42.000	±0.030			112	84		
120	12.000	±0.018	…	60	…				450	45.000	±0.030			120	90	…	
124	12.375	±0.018	…	…	33				480	48.000	±0.030			128	96	…	
124	12.400	±0.018	155	…	…				507	50.750	±0.032			…	…	58	
130	13.000	±0.018	…	65	…				510	51.000	±0.032			136	102	…	
140	14.000	±0.018	175	70	…				540	54.000	±0.032			144	108	…	
150	15.000	±0.018	…	75	40				560	56.000	±0.032			…	…	64	
160	16.000	±0.020	200	80	…				570	57.000	±0.032			…	114	…	
170	17.000	±0.020	…	85	…				600	60.000	±0.032			160	120	…	
180	18.000	±0.020	225	90	…				630	63.000	±0.034			…	126	72	
187	18.750	±0.020	…	…	50				660	66.000	±0.034			…	132	…	
190	19.000	±0.020	…	95	…				700	70.000	±0.034				140	80	56
200	20.000	±0.020	250	100	…				750	75.000	±0.036				150	…	…
210	21.000	±0.024	…	105	56				770	77.000	±0.036				…	88	…
220	22.000	±0.024	…	110	…				800	80.000	±0.036				160	…	64
225	22.500	±0.024	…	…	60				840	84.000	±0.038				…	96	…

All dimensions in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 43. Synchronous Belt Standard Widths and Tolerances
ANSI/RMA IP-24, 1983

Belt Section	Standard Belt Widths		Tolerances on Width for Belt Pitch Lengths		
	Designation	Dimensions	Up to and including 33 in.	Over 33 in. up to and including 66 in.	Over 66 in.
MXL (0.080)	012 019 025	0.12 0.19 0.25	+0.02 −0.03	…	…
XL (0.200)	025 037	0.25 0.38	+0.02 −0.03	…	…
L (0.375)	050 075 100	0.50 0.75 1.00	+0.03 −0.03	+0.03 −0.05	…
H (0.500)	075 100 150	0.75 1.00 1.50	+0.03 −0.03	+0.03 −0.05	+0.03 −0.05
	200	2.00	+0.03 −0.05	+0.05 −0.05	+0.05 −0.06
	300	3.00	+0.05 −0.06	+0.06 −0.06	+0.06 −0.08
XH (0.875)	200 300 400	2.00 3.00 4.00	…	+0.19 −0.19	+0.19 −0.19
XXH (1.250)	200 300 400 500	2.00 3.00 4.00 5.00	…	…	+0.19 −0.19

Widths.: Standard belt widths, width designations, and width tolerances are shown in Table 43.

Length Determination.: The pitch length of a synchronous belt is determined by placing the belt on a measuring fixture having two pulleys of equal diameter, a method of applying force, and a means of measuring the center distance between the two pulleys. The position of one of the two pulleys is fixed and the other is movable along a graduated scale.

Synchronous Belt Pulley Diameters: Table 44 lists the standard pulley diameters by belt section (pitch). Fig. 13 defines the pitch, pitch diameter, outside diameter and pitch line differential.



Fig. 13. Synchronous Belt Pulley Dimensions

Copyright 2004, Industrial Press, Inc., New York, NY

Table 44. Synchronous Belt Standard Pulley Diameters *ANSI/RMA IP-24, 1983*

Number of Grooves	Belt Section											
	MXL (0.080)		XL (0.200)		L (0.375)		H (0.500)		XH (0.875)		XXH (1.250)	
	Diameters		Diameters		Diameters		Diameters		Diameters		Diameters	
	Pitch	Outside	Pitch	Outside	Pitch	Outside	Pitch	Outside	Pitch	Outside	Pitch	Outside
10	0.255	0.235	0.637	0.617	1.194[a]	1.164	…	…	…	…	…	…
12	0.306	0.286	0.764	0.744	1.432[a]	1.402	…	…	…	…	…	…
14	0.357	0.337	0.891	0.871	1.671	1.641	2.228[a]	2.174	…	…	…	…
16	0.407	0.387	1.019	0.999	1.910	1.880	2.546	2.492	…	…	…	…
18	0.458	0.438	1.146	1.126	2.149	2.119	2.865	2.811	5.013	4.903	7.162	7.042
20	0.509	0.489	1.273	1.253	2.387	2.357	3.183	3.129	5.570	5.460	7.958	7.838
22	0.560	0.540	1.401	1.381	2.626	2.596	3.501	3.447	6.127	6.017	8.754	8.634
24	0.611	0.591	1.528	1.508	2.865	2.835	3.820	3.766	6.685	6.575	9.549	9.429
26	0.662	0.642	…	…	3.104	3.074	4.138	4.084	7.242	7.132	10.345	10.225
28	0.713	0.693	1.783	1.763	3.342	3.312	4.456	4.402	7.799	7.689	…	…
30	0.764	0.744	1.910	1.890	3.581	3.551	4.775	4.721	8.356	8.246	11.937	11.817
32	0.815	0.795	2.037	2.017	3.820	3.790	5.093	5.039	8.913	8.803	…	…
34	0.866	0.846	…	…	…	…	…	…	…	…	13.528	13.408
36	0.917	0.897	2.292	2.272	4.297	4.267	5.730	5.676	…	…	…	…
40	1.019	0.999	2.546	2.526	4.775	4.745	6.366	6.312	11.141	11.031	15.915	15.795
42	1.070	1.050	2.674	2.654	…	…	…	…	…	…	…	…
44	1.120	1.100	2.801	2.781	5.252	5.222	7.003	6.949	…	…	…	…
48	1.222	1.202	3.056	3.036	5.730	5.700	7.639	7.585	13.369	13.259	19.099	18.979
60	1.528	1.508	3.820	3.800	7.162	7.132	9.549	9.495	16.711	16.601	23.873	23.753
72	1.833	1.813	4.584	4.564	8.594	8.564	11.459	11.405	20.054	19.944	28.648	28.528
84	…	…	…	…	10.027	9.997	13.369	13.315	23.396	23.286	…	…
90	…	…	…	…	…	…	…	…	…	…	35.810	35.690
96	…	…	…	…	…	…	15.279	15.225	26.738	26.628	…	…
120	…	…	…	…	…	…	19.099	19.045	33.423	33.313	…	…

All dimensions in inches.

* Usually not available in all widths — consult supplier.

Copyright 2004, Industrial Press, Inc., New York, NY

Widths: Standard pulley widths for each belt section are shown in Table 41. The nominal pulley width is specified in terms of the maximum standard belt width the pulley will accommodate. The minimum pulley width, whether flanged or unflanged, is also shown in Table 41, along with flange dimensions and various pulley tolerances.

Pulley Size Designation: Synchronous belt pulleys are designated by the number of grooves, the belt section, and a number representing 100 times the nominal width. For example, a 30 groove L section pulley with a nominal width of 0.75 in. would be designated by 30L075. Pulley tolerances are shown in Table 45.

Table 45. Pulley Tolerances (All Sections)

Outside Diameter Range	Outside Diameter Tolerance	Pitch to Pitch Tolerance	
		Adjacent Grooves	Accumulative Over 90 Degrees
Up thru 1.000	+0.002 −0.000	±0.001	±0.003
Over 1.000 to and including 2.000	+0.003 −0.000	±0.001	±0.004
Over 2.000 to and including 4.000	+0.004 −0.000	±0.001	±0.005
Over 4.000 to and including 7.000	+0.005 −0.000	±0.001	±0.005
Over 7.000 to and including 12.000	+0.006 −0.000	±0.001	±0.006
Over 12.000 to and including 20.000	+0.007 −0.000	±0.001	±0.007
Over 20.000	+0.008 −0.000	±0.001	±0.008

Radial Runout[a]	Axial Runout[b]
For outside diameters 8.0 in. and under 0.005 in.	For outside diameters 1.0 in. and under 0.001 in.
For each additional inch of outside diameter add 0.0005 in.	For each additional inch of outside diameter up through 10.0 in., add 0.001 in.
	For each additional inch of outside diameter over 10.0 in., add 0.0005 in.

[a] Flange outside diameter equals pulley outside diameter plus twice flange height.

[b] Total indicator reading.

All dimensions in inches.

Cross Section Selection: The chart (Fig. 14) may be used as a guide to the selection of a synchronous belt for any combination of design horsepower and speed of the faster shaft. When the intersection of the design horsepower and speed of the faster shaft falls near a line between two areas on the chart, the possibilities in both areas should be explored. Special circumstances (such as space limitations) may result in selection of a belt cross section different from that indicated in the chart. Belt manufacturers should be contacted for specific data.

Torque Ratings: It is customary to use torque load requirements rather than horsepower load when designing drives using the small pitch MXL section belts. These belts operate on small diameters resulting in relatively low belt speeds, so torque is essentially constant for all rpm. The torque rating formulas for MXL sections are:

$$Q_r = d[1.13 - 1.38\times10^{-3}d^2] \text{ for belt width} = 0.12 \text{ in.}$$

$$Q_r = d[1.88 - 2.30\times10^{-3}d^2] \text{ for belt width} = 0.19 \text{ in.}$$

$$Q_r = d[2.63 - 3.21\times10^{-3}d^2] \text{ for belt width} = 0.25 \text{ in.}$$

where Q_r = the maximum torque rating (lbf-in.) for a belt of specified width having six or more teeth in mesh and a pulley surface speed of 6500 fpm or less. Torque ratings for drives with less than six teeth in mesh must be corrected as shown in Table 46. d = pitch diameter of smaller pulley, inch.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 14. Selection of Synchronous Belt Cross Section

Table 46. Teeth in Mesh Factor

Teeth in Mesh	Factor K_z	Teeth in Mesh	Factor K_z
6 or more	1.00	3	0.40
5	0.80	2	0.20
4	0.60		

Horsepower Rating Formulas: The horsepower rating formulas for synchronous belts, other than the MLX section, are determined from the following formulas, where the number in parentheses is the belt width in inches.

$$\text{XL}(0.38)\text{HP} = dr[0.0916 - 7.07\times10^{-5}(dr)^2]$$

$$\text{L}(1.00)\text{HP} = dr[0.436 - 3.01\times10^{-4}(dr)^2]$$

$$\text{H}(3.00)\text{HP} = dr[3.73 - 1.41\times10^{-3}(dr)^2]$$

$$\text{XH}(4.00)\text{HP} = dr[7.21 - 4.68\times10^{-3}(dr)^2]$$

$$\text{XXH}(5.00)\text{HP} = dr[11.4 - 7.81\times10^{-3}(dr)^2]$$

where HP = the maximum horsepower rating recommended for the specified standard belt width having six or more teeth in mesh and a pulley surface speed of 6500 fpm or less. Horsepower ratings for drives with less than six teeth in mesh must be corrected as shown in Table 46. d = pitch diameter of smaller pulley, in. r = rpm of faster shaft divided by 1000. Total horsepower ratings are the same for double-sided as for single-sided belts. Contact manufacturers for percentage of horsepower available for each side of the belt.

Finding the Required Belt Width: The belt width should not exceed the small pulley diameter or excessive side thrust will result.

Torque Rating Method (MXL Section): Divide the design torque by the teeth in mesh factor to obtain the corrected design torque. Compare the corrected design torque with the torque rating given in Table 47 for the pulley diameter being considered. Select the narrowest belt width that has a torque rating equal to or greater than the corrected design torque.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 47. Torque Rating for MXL Section (0.080 in. Pitch)

Belt Width, (in.)	Rated Torque (lbf-in.) for Small Pulley (Number of Grooves and Pitch Diameter, in.)									
	10MXL 0.255	12MXL 0.306	14MXL 0.357	16MXL 0.407	18MXL 0.458	20MXL 0.509	22MXL 0.560	24MXL 0.611	28MXL 0.713	30MXL 0.764
0.12	0.29	0.35	0.40	0.46	0.52	0.57	0.63	0.69	0.81	0.86
0.19	0.48	0.58	0.67	0.77	0.86	0.96	1.05	1.15	1.34	1.44
0.25	0.67	0.80	0.94	1.07	1.20	1.34	1.47	1.61	1.87	2.01

Horsepower Rating Method (XL, L, H, XH, and XXH Sections): Multiply the horsepower rating for the widest standard belt of the selected section by the teeth in mesh factor to obtain the corrected horsepower rating. Divide the design horsepower by the corrected horsepower rating to obtain the required belt width factor. Compare the required belt width factor with those shown in Table 48. Select the narrowest belt width that has a width factor equal to or greater than the required belt width factor.

Table 48. Belt Width Factor

Belt Section	Belt Width (in.)											
	0.12	0.19	0.25	0.38	0.50	0.75	1.00	1.50	2.00	3.00	4.00	5.00
MXL (0.080)	0.43	0.73	1.00	…	…	…	…	…	…	…	…	…
XL (0.200)	…	…	0.62	1.00	…	…	…	…	…	…	…	…
L (0.375)	…	…	…	…	0.45	0.72	1.00	…	…	…	…	…
H (0.500)	…	…	…	…	…	0.21	0.29	0.45	0.63	1.00	…	…
XH (0.875)	…	…	…	…	…	…	…	…	0.45	0.72	1.00	…
XXH (1.250)	…	…	…	…	…	…	…	…	0.35	0.56	0.78	1.00

Drive Selection: Information on design and selection of synchronous belt drives is available in engineering manuals published by belt manufacturers. Manufacturers should be consulted on such matters as preferred stock sizes, desirable speeds, center distances, etc.

Minimum Pulley Size: The recommended minimum pulley size depends on the rpm of the faster shaft. Minimum sheave diameters for each cross-section belt are listed in Table 44.

Selection of Flanged Pulleys: To determine when to use flanged pulleys, consider the following conditions:

1) On all two-pulley drives, the minimum flanging requirements are two flanges on one pulley, or one flange on each pulley on opposite sides.

2) On drives where the center distance is more than eight times the diameter of the small pulley, both pulleys should be flanged on both sides.

3) On vertical shaft drives, one pulley should be flanged on both sides and other pulleys in the system should be flanged on the bottom side only.

4) On drives with more than two pulleys, the minimum flanging requirements are two flanges on every other pulley, or one flange on every pulley, alternating sides around the system.

Service Factors: Service factors for synchronous belts in Table 39.

Copyright 2004, Industrial Press, Inc., New York, NY

TRANSMISSION CHAINS

Types of Chains

In addition to the standard roller and inverted tooth types, a wide variety of drive chains of different construction is available. Such chains are manufactured to various degrees of precision ranging from unfinished castings or forgings to chains having certain machined parts. Practically all of these chains as well as standard roller chains can be equipped with attachments to fit them for conveyor use. A few such types are briefly described in the following paragraphs. Detailed information about them can be obtained from the manufacturers.

Types of Chains.— *Detachable Chains:* The links of this type of chain, which are identical, are easily detachable. Each has a hook-shaped end in which the bar of the adjacent link articulates. These chains are available in malleable iron or pressed steel. The chief advantage is the ease with which any link can be removed.

Cast Roller Chains: Cast roller chains are constructed, wholly or partly, of cast metal parts and are available in various styles. In general the rollers and side bars are accurately made castings without machine finish. The links are usually connected by means of forged pins secured by nuts or cotters. Such chains are used for slow speeds and moderate loads, or where the precision of standard roller chains is not required.

Pintle Chains: Unlike the roller chain, the pintle chain is composed of hollow-cored cylinders cast or forged integrally with two offset side bars and each link identical. The links are joined by pins inserted in holes in the ends of the side bars and through the cored holes in the adjacent links. Lugs prevent turning of the pins in the side bars ensuring articulation of the chain between the pin and the cored cylinder.

Standard Roller Transmission Chains

A roller chain is made up of two kinds of links: roller links and pin links alternately spaced throughout the length of the chain as shown in Table 1.

Roller chains are manufactured in several types, each designed for the particular service required. All roller chains are so constructed that the rollers are evenly spaced throughout the chain. The outstanding advantage of this type of chain is the ability of the rollers to rotate when contacting the teeth of the sprocket. Two arrangements of roller chains are in common use: the single-strand type and the multiple-strand type. In the latter type, two or more chains are joined side by side by means of common pins which maintain the alignment of the rollers in the different strands.

Types of Roller Chains.— *Standard roller chains* are manufactured to the specifications in the American National Standard for precision power transmission roller chains, attachments, and sprockets ANSI/ASME B29.1M-1993 and, where indicated, the data in the subsequent tables have been taken from this standard. These roller chains and sprockets are commonly used for the transmission of power in industrial machinery, machine tools, motor trucks, motorcycles, tractors, and similar applications. In tabulating the dimensional information in ANSI/ASME B29.1M, customary inch-pound units were used. Metric (SI) units are given in separate tabulations in the Standard.

Nonstandard roller chains, developed individually by various manufacturers prior to the adoption of the ANSI standard, are similar in form and construction to standard roller chains but do not conform dimensionally to standard chains. Some sizes are still available from the originating manufacturers for replacement on existing equipment. They are not recommended for new installations, since their manufacture is being discontinued as rapidly as possible.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ANSI Nomenclature for Roller Chain Parts *ANSI/ASME B29.1M-1993*



Roller Link D. — An inside link consisting of two inside plates, two bushings, and two rollers.

Pin Link G and E. — An outside link consisting of two pin-link plates assembled with two pins.

Inside Plate A. — One of the plates forming the tension members of a roller link.

Pin Link Plate E. — One of the plates forming the tension members of a pin link.

Pin F. — A stud articulating within a bushing of an inside link and secured at its ends by the pin-link plates.

Bushing B. — A cylindrical bearing in which the pin turns.

Roller C. — A ring or thimble which turns over a bushing.

Assembled Pins G. — Two pins assembled with one pin-link plate.

Connecting-Link G and I. — A pin link having one side plate detachable.

Connecting-Link Plate I. — The detachable pin-link plate belonging to a connecting link. It is retained by cotter pins or by a one-piece spring clip (not shown).

Connecting Link Assembly M. — A unit designed to connect two roller links.

Offset Link L. — A link consisting of two offset plates assembled with a bushing and roller at one end and an offset link pin at the other.

Offset Plate J. — One of the plates forming the tension members of the offset link.

Offset Link Pin K. — A pin used in offset links.

Standard double-pitch roller chains are like standard roller chains, except that their link plates have twice the pitch of the corresponding standard-pitch chain. Their design conforms to specifications in the ANSI Standard for double-pitch power transmission roller chains and sprockets ANSI/ASME B29.3M-1994. They are especially useful for low speeds, moderate loads, or long center distances.

Copyright 2004, Industrial Press, Inc., New York, NY

Transmission Roller Chain

Standard Roller Chain Nomenclature, Dimensions and Loads.— Standard nomenclature for roller chain parts are given in Table 1. Dimensions for Standard Series roller chain are given in Table 2.

Table 2. ANSI Roller Chain Dimensions *ASME/ANSI B29.1M-1986*



Pitch *P*	Max. Roller Diameter D_r	Standard Series					Heavy Series
		Standard Chain No.	Width *W*	Pin Diameter D_p	Thickness of Link Plates *LPT*	Measuring Load,† Lb.	Thickness of Link Plates *LPT*
0.250	[a]0.130	25	0.125	0.0905	0.030	18	…
0.375	[a]0.200	35	0.188	0.141	0.050	18	…
0.500	0.306	41	0.250	0.141	0.050	18	…
0.500	0.312	40	0.312	0.156	0.060	31	…
0.625	0.400	50	0.375	0.200	0.080	49	…
0.750	0.469	60	0.500	0.234	0.094	70	0.125
1.000	0.625	80	0.625	0.312	0.125	125	0.156
1.250	0.750	100	0.750	0.375	0.156	195	0.187
1.500	0.875	120	1.000	0.437	0.187	281	0.219
1.750	1.000	140	1.000	0.500	0.219	383	0.250
2.000	1.125	160	1.250	0.562	0.250	500	0.281
2.250	1.406	180	1.406	0.687	0.281	633	0.312
2.500	1.562	200	1.500	0.781	0.312	781	0.375
3.000	1.875	240	1.875	0.937	0.375	1000	0.500

[a] Bushing diameter. This size chain has no rollers.

All dimensions are in inches.

Roller Diameters D_r are approximately $\frac{5}{8}P$.

The *width W* is defined as the distance between the link plates. It is approximately $\frac{5}{8}$ of the chain pitch.

Pin Diameters D_p are approximately $\frac{5}{16}P$ or $\frac{1}{2}$ of the roller diameter.

Thickness LPT of Inside and Outside Link Plates for the standard series is approximately $\frac{1}{8}P$.

Thickness of Link Plates for the heavy series of any pitch is approximately that of the next larger pitch Standard Series chain.

Maximum Height of Roller Link Plates = 0.95 *P*.

Maximum Height of Pin Link Plates = 0.82 *P*.

Maximum Pin Diameter = nominal pin diameter + 0.0005 inch.

Minimum Hole in Bushing = nominal pin diameter + 0.0015 inch.

Maximum Width of Roller Link = nominal width of chain + (2.12 × nominal link plate thickness.)

Minimum Distance between Pin Link Plates = maximum width of roller link + 0.002 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Chain Pitch: Distance in inches between centers of adjacent joint members. Other dimensions are proportional to the pitch.

Tolerances for Chain Length: New chains, under standard measuring load, must not be underlength. Overlength tolerance is $0.001/(\text{pitch in inches})^2 + 0.015$ inch per foot. Length measurements are to be taken over a length of at least 12 inches.

Measuring Load: The load in pounds under which a chain should be measured for length. It is equal to one per cent of the ultimate tensile strength, with a minimum of 18 pounds and a maximum of 1000 pounds for both single and multiple-strand chain.

Minimum Ultimate Tensile Strength: For single-strand chain, equal to or greater than $12{,}500 \times (\text{pitch in inches})^2$ pounds. The minimum tensile strength or breaking strength of a multiple-strand chain is equal to that of a single-strand chain multiplied by the number of strands. Minimum ultimate tensile strength is indicative only of the tensile strength quality of the chain, not the maximum load that can be applied.

Standard Roller Chain Numbers.— The right-hand figure in the chain number is zero for roller chains of the usual proportions, 1 for a lightweight chain, and 5 for a rollerless bushing chain. The numbers to the left of the right-hand figure denote the number of $\frac{1}{8}$ inches in the pitch. The letter *H* following the chain number denotes the heavy series; thus the number 80 *H* denotes a 1-inch pitch heavy chain. The hyphenated number 2 suffixed to the chain number denotes a double strand, 3 a triple strand, 4 a quadruple strand chain and so on.

Heavy Series: These chains, made in $\frac{3}{4}$-inch and larger pitches, have thicker link plates than those of the regular standard. Their value is only in the acceptance of higher loads at lower speeds.

Light-weight Machinery Chain: This chain is designated as No. 41. It is $\frac{1}{2}$ inch pitch; $\frac{1}{4}$ inch wide; has 0.306-inch diameter rollers and a 0.141-inch pin diameter. The minimum ultimate tensile strength is 1500 pounds.

Multiple-strand Chain: This is essentially an assembly of two or more single-strand chains placed side by side with pins that extend through the entire width to maintain alignment of the different strands.

Types of Sprockets.— Four different designs or types of roller-chain sprockets are shown by the sectional views, Fig. 1. Type *A* is a plain plate; type *B* has a hub on one side only; type *C*, a hub on both sides; and type *D*, a detachable hub. Also used are shear pin and slip clutch sprockets designed to prevent damage to the drive or to other equipment caused by overloads or stalling.



Fig. 1. Types of Sprockets

Copyright 2004, Industrial Press, Inc., New York, NY

Attachments.— Modifications to standard chain components to adapt the chain for use in conveying, elevating, and timing operations are known as "attachments." The components commonly modified are: 1) the link plates, which are provided with extended lugs which may be straight or bent ; and 2) the chain pins, which are extended in length so as to project substantially beyond the outer surface of the pin link plates.

Hole diameters, thicknesses, hole locations and offset dimensions for straight link and bent link plate extensions and lengths and diameters of extended pins are given in Table 3.

Table 3. Straight and Bent Link Plate Extensions and Extended Pin Dimensions
ANSI/ASME B29.1M-1993



Chain No.	Straight Link Plate Extension			Bent Link Plate Extension				Extended Pin	
	B min.	*D*	*F*	*B* min.	*C*	*D*	*F*	D_p Nominal	*L*
35	0.102	0.375	0.050	0.102	0.250	0.375	0.050	0.141	0.375
40	0.131	0.500	0.060	0.131	0.312	0.500	0.060	0.156	0.375
50	0.200	0.625	0.080	0.200	0.406	0.625	0.080	0.200	0.469
60	0.200	0.719	0.094	0.200	0.469	0.750	0.094	0.234	0.562
80	0.261	0.969	0.125	0.261	0.625	1.000	0.125	0.312	0.750
100	0.323	1.250	0.156	0.323	0.781	1.250	0.156	0.375	0.938
120	0.386	1.438	0.188	0.386	0.906	1.500	0.188	0.437	1.125
140	0.448	1.750	0.219	0.448	1.125	1.750	0.219	0.500	1.312
160	0.516	2.000	0.250	0.516	1.250	2.000	0.250	0.562	1.500
200	0.641	2.500	0.312	0.641	1.688	2.500	0.312	0.781	1.875

All dimensions are in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Sprocket Classes.— The American National Standard ANSI/ASME B29.1M-1993 provides for two classes of sprockets designated as Commercial and Precision. The selection of either is a matter of drive application judgment. The usual moderate to slow speed commercial drive is adequately served by Commercial sprockets. Where extreme high speed in combination with high load is involved, or where the drive involves fixed centers, critical timing, or register problems, or close clearance with outside interference, then the use of Precision sprockets may be more appropriate.

As a general guide, drives requiring Type A or Type B lubrication (see page 2463) would be served by Commercial sprockets. Drives requiring Type C lubrication may require Precision sprockets; the manufacturer should be consulted.

Keys, Keyways, and Set Screws.— To secure sprockets to the shaft, both keys and set screws should be used. The key is used to prevent rotation of the sprocket on the shaft. Keys should be fitted carefully in the shaft and sprocket keyways to eliminate all backlash, especially on the fluctuating loads. A set screw should be located over a flat key to secure it against longitudinal displacement.

Where a set screw is to be used with a parallel key, the following sizes are recommended by the American Chain Association. For a sprocket bore and shaft diameter in the range of

$\frac{1}{2}$ through $\frac{7}{8}$ inch, a $\frac{1}{4}$-inch set screw

$\frac{15}{16}$ through $1\frac{3}{4}$ inches, a $\frac{3}{8}$-inch set screw

$1\frac{13}{16}$ through $2\frac{1}{4}$ inches, a $\frac{1}{2}$-inch set screw

$2\frac{5}{16}$ through $3\frac{1}{4}$ inches, a $\frac{5}{8}$-inch set screw

$3\frac{3}{8}$ through $4\frac{1}{2}$ inches, a $\frac{3}{4}$-inch set screw

$4\frac{3}{4}$ through $5\frac{1}{2}$ inches, a $\frac{7}{8}$-inch set screw

$5\frac{3}{4}$ through $7\frac{3}{8}$ inches, a 1-inch set screw

$7\frac{1}{2}$ through $12\frac{1}{2}$ inches, a $1\frac{1}{4}$-inch set screw

Sprocket Diameters.— The various diameters of roller chain sprockets are shown in Fig. 2. These are defined as follows.

Pitch Diameter: The pitch diameter is the diameter of the pitch circle that passes through the centers of the link pins as the chain is wrapped on the sprocket.



Fig. 2. Sprocket Diameters

Because the chain pitch is measured on a straight line between the centers of adjacent pins, the chain pitch lines form a series of chords of the sprocket pitch circle. Sprocket pitch diameters for one-inch pitch and for 9 to 108 teeth are given in Table 4. For lower (5 to 8) or higher (109 to 200) numbers of teeth use the following formula in which P = pitch, N = number of teeth: Pitch Diameter = $P \div \sin(180° \div N)$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ANSI Roller Chain Sprocket Diameters *ANSI/ASME B29.1M-1993*

These diameters and caliper factors apply only to chain of 1-inch pitch. For any other pitch, multiply the values given below by the pitch.
Caliper Dia. (even teeth) = Pitch Diameter – Roller Dia.
Caliper Dia. (odd teeth) = Caliper factor × Pitch – Roller Dia.
See Table 5 for tolerances on Caliper Diameters.

No. Teeth[a]	Pitch Diameter	Outside Diameter		Caliper Factor	No. Teeth[a]	Pitch Diameter	Outside Diameter		Caliper Factor
		Turned	Topping Hob Cut				Turned	Topping Hob Cut	
9	2.9238	3.348	3.364	2.8794	59	18.7892	19.363	19.361	18.7825
10	3.2361	3.678	3.676		60	19.1073	19.681	19.680	
11	3.5495	4.006	3.990	3.5133	61	19.4255	20.000	19.998	19.4190
12	3.8637	4.332	4.352		62	19.7437	20.318	20.316	
13	4.1786	4.657	4.666	4.1481	63	20.0618	20.637	20.634	20.0556
14	4.4940	4.981	4.982		64	20.3800	20.956	20.952	
15	4.8097	5.304	5.298	4.7834	65	20.6982	21.274	21.270	20.6921
16	5.1258	5.627	5.614		66	21.0164	21.593	21.588	
17	5.4422	5.949	5.930	5.4190	67	21.3346	21.911	21.907	21.3287
18	5.7588	6.271	6.292		68	21.6528	22.230	22.225	
19	6.0755	6.593	6.609	6.0548	69	21.9710	22.548	22.543	21.9653
20	6.3924	6.914	6.926		70	22.2892	22.867	22.861	
21	6.7095	7.235	7.243	6.6907	71	22.6074	23.185	23.179	22.6018
22	7.0267	7.555	7.560		72	22.9256	23.504	23.498	
23	7.3439	7.876	7.877	7.3268	73	23.2438	23.822	23.816	23.2384
24	7.6613	8.196	8.195		74	23.5620	24.141	24.134	
25	7.9787	8.516	8.512	7.9630	75	23.8802	24.459	24.452	23.8750
26	8.2962	8.836	8.829		76	24.1984	24.778	24.770	
27	8.6138	9.156	9.147	8.5992	77	24.5166	25.096	25.089	24.5116
28	8.9314	9.475	9.465		78	24.8349	25.415	25.407	
29	9.2491	9.795	9.782	9.2355	79	25.1531	25.733	25.725	25.1481
30	9.5668	10.114	10.100		80	25.4713	26.052	26.043	
31	9.8845	10.434	10.418	9.8718	81	25.7896	26.370	26.362	25.7847
32	10.2023	10.753	10.736		82	26.1078	26.689	26.680	
33	10.5201	11.073	11.053	10.5082	83	26.4260	27.007	26.998	26.4213
34	10.8379	11.392	11.371		84	26.7443	27.326	27.316	
35	11.1558	11.711	11.728	11.1446	85	27.0625	27.644	27.635	27.0579
36	11.4737	12.030	12.046		86	27.3807	27.962	27.953	
37	11.7916	12.349	12.364	11.7810	87	27.6990	28.281	28.271	27.6945
38	12.1095	12.668	12.682		88	28.0172	28.599	28.589	
39	12.4275	12.987	13.000	12.4174	89	28.3354	28.918	28.907	28.3310
40	12.7455	13.306	13.318		90	28.6537	29.236	29.226	
41	13.0635	13.625	13.636	13.0539	91	28.9719	29.555	29.544	28.9676
42	13.3815	13.944	13.954		92	29.2902	29.873	29.862	
43	13.6995	14.263	14.272	13.6904	93	29.6084	30.192	30.180	29.6042
44	14.0175	14.582	14.590		94	29.9267	30.510	30.499	
45	14.3355	14.901	14.908	14.3269	95	30.2449	30.828	30.817	30.2408
46	14.6535	15.219	15.226		96	30.5632	31.147	31.135	
47	14.9717	15.538	15.544	14.9634	97	30.8815	31.465	31.454	30.8774
48	15.2898	15.857	15.862		98	31.1997	31.784	31.772	
49	15.6079	16.176	16.180	15.5999	99	31.5180	32.102	32.090	31.5140
50	15.9260	16.495	16.498		100	31.8362	32.421	32.408	
51	16.2441	16.813	16.816	16.2364	101	32.1545	32.739	32.727	32.1506
52	16.5622	17.132	17.134		102	32.4727	33.057	33.045	
53	16.8803	17.451	17.452	16.8729	103	32.7910	33.376	33.363	32.7872
54	17.1984	17.769	17.770		104	33.1093	33.694	33.681	
55	17.5165	18.088	18.089	17.5094	105	33.4275	34.013	34.000	33.4238
56	17.8347	18.407	18.407		106	33.7458	34.331	34.318	
57	18.1528	18.725	18.725	18.1459	107	34.0641	34.649	34.636	34.0604
58	18.4710	19.044	19.043		108	34.3823	34.968	34.954	

[a] For 5 – 8 and 109–200 teeth see text, pages 2446, 2448.

Copyright 2004, Industrial Press, Inc., New York, NY

Bottom Diameter: The bottom diameter is the diameter of a circle tangent to the curve (called the seating curve) at the bottom of the tooth gap. It equals the pitch diameter minus the diameter of the roller.

Caliper Diameter: The caliper diameter is the same as the bottom diameter for a sprocket with an even number of teeth. For a sprocket with an odd number of teeth, it is defined as the distance from the bottom of one tooth gap to that of the nearest opposite tooth gap. The caliper diameter for an even tooth sprocket is equal to pitch diameter–roller diameter. The caliper diameter for an odd tooth sprocket is equal to caliper factor–roller diameter. Here, the caliper factor = $PD[\cos(90° \div N)]$, where PD = pitch diameter and N = number of teeth. Caliper factors for 1-in. pitch and sprockets having 9–108 teeth are given in Table 4. For other tooth numbers use above formula. Caliper diameter tolerances are minus only and are equal to $0.002P\sqrt{N} + 0.006$ inch for the Commercial sprockets and $0.001P\sqrt{N} + 0.003$ inch for Precision sprockets. Tolerances are given in Table 5.

Table 5. Minus Tolerances on the Caliper Diameters of Precision Sprockets
ANSI/ASME B29.1M-1993

	Number of Teeth				
Pitch	Up to 15	16–24	25–35	36–48	49–63
0.250	0.004	0.004	0.004	0.005	0.005
0.375	0.004	0.004	0.004	0.005	0.005
0.500	0.004	0.005	0.0055	0.006	0.0065
0.625	0.005	0.0055	0.006	0.007	0.008
0.750	0.005	0.006	0.007	0.008	0.009
1.000	0.006	0.007	0.008	0.009	0.010
1.250	0.007	0.008	0.009	0.010	0.012
1.500	0.007	0.009	0.0105	0.012	0.013
1.750	0.008	0.010	0.012	0.013	0.015
2.000	0.009	0.011	0.013	0.015	0.017
2.250	0.010	0.012	0.014	0.016	0.018
2.500	0.010	0.013	0.015	0.018	0.020
3.000	0.012	0.015	0.018	0.021	0.024
	Number of Teeth				
Pitch	64–80	81–99	100–120	121–143	144 up
0.250	0.005	0.005	0.006	0.006	0.006
0.375	0.006	0.006	0.006	0.007	0.007
0.500	0.007	0.0075	0.008	0.0085	0.009
0.625	0.009	0.009	0.009	0.010	0.011
0.750	0.010	0.010	0.011	0.012	0.013
1.000	0.011	0.012	0.013	0.014	0.015
1.250	0.013	0.014	0.016	0.017	0.018
1.500	0.015	0.016	0.018	0.019	0.021
1.750	0.017	0.019	0.020	0.022	0.024
2.000	0.019	0.021	0.023	0.025	0.027
2.250	0.021	0.023	0.025	0.028	0.030
2.500	0.023	0.025	0.028	0.030	0.033
3.000	0.027	0.030	0.033	0.036	0.039

Minus tolerances for Commercial sprockets are twice those shown in this table.

Outside Diameter: OD is the diameter over the tips of teeth. Sprocket ODs for 1-in. pitch and 9–108 teeth are given in Table 4. For other tooth numbers the OD may be determined by the following formulas in which O = approximate OD; P = pitch of chain; N = number of sprocket teeth: $O = P\,[0.6 + \cot(180° \div N)]$, for turned sprocket; O = pitch diameter – roller diameter + 2 × whole depth of topping hob cut, for topping hob cut sprocket.*

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. American National Standard Roller Chain Sprocket Flange Thickness and Tooth Section Profile Dimension *ANSI/ASME B29.1M-1993*



Sprocket Flange Thickness

Std. Chain No.	Width of Chain, *W*	Maximum Sprocket Flange Thickness, *t*			Minus Tolerance on *t*		Tolerance on *M*		Max. Variation of *t* on Each Flange	
		Single	Double & Triple	Quad. & Over	Commercial	Precision	Commercial Plus or Minus	Precision Minus Only	Commercial	Precision
25	0.125	0.110	0.106	0.096	0.021	0.007	0.007	0.007	0.021	0.004
35	0.188	0.169	0.163	0.150	0.027	0.008	0.008	0.008	0.027	0.004
41	0.250	0.226	…	…	0.032	0.009	…	…	0.032	0.004
40	0.312	0.284	0.275	0.256	0.035	0.009	0.009	0.009	0.035	0.004
50	0.375	0.343	0.332	0.310	0.036	0.010	0.010	0.010	0.036	0.005
60	0.500	0.459	0.444	0.418	0.036	0.011	0.011	0.011	0.036	0.006
80	0.625	0.575	0.556	0.526	0.040	0.012	0.012	0.012	0.040	0.006
100	0.750	0.0692	0.669	0.633	0.046	0.014	0.014	0.014	0.046	0.007
120	1.000	0.924	0.894	0.848	0.057	0.016	0.016	0.016	0.057	0.008
140	1.000	0.924	0.894	0.848	0.057	0.016	0.016	0.016	0.057	0.008
160	1.250	1.156	1.119	1.063	0.062	0.018	0.018	0.018	0.062	0.009
180	1.406	1.302	1.259	1.198	0.068	0.020	0.020	0.020	0.068	0.010
200	1.500	1.389	1.344	1.278	0.072	0.021	0.021	0.021	0.072	0.010
240	1.875	1.738	1.682	1.602	0.087	0.025	0.025	0.025	0.087	0.012

Sprocket Tooth Section Profile Dimensions

Std. Chain No.	Chain Pitch *P*	Depth of Chamfer *h*	Width of Chamfer *g*	Minimum Radius R_c	Transverse Pitch *K*	
					Standard Series	Heavy Series
25	0.250	0.125	0.031	0.265	0.252	…
35	0.375	0.188	0.047	0.398	0.399	…
41	0.500	0.250	0.062	0.531	…	…
40	0.500	0.250	0.062	0.531	0.566	…
50	0.625	0.312	0.078	0.664	0.713	…
60	0.750	0.375	0.094	0.796	0.897	1.028
80	1.000	0.500	0.125	1.062	1.153	1.283
100	1.250	0.625	0.156	1.327	1.408	1.539
120	1.500	0.750	0.188	1.593	1.789	1.924
140	1.750	0.875	0.219	1.858	1.924	2.055
160	2.000	1.000	0.250	2.124	2.305	2.437
180	2.250	1.125	0.281	2.392	2.592	2.723
200	2.500	1.250	0.312	2.654	2.817	3.083
240	3.000	1.500	0.375	3.187	3.458	3.985

All dimensions are in inches. r_f max = 0.04 *P* for max. hub diameter.

* This dimension was added in 1984 as a desirable goal for the future. It should in no way obsolete existing tools or sprockets. The whole depth *WD* is found from the formula: $WD = \frac{1}{2}D_r + P[0.3 - \frac{1}{2}\tan(90 \text{ deg} \div N_a)]$, where N_a is the intermediate number of teeth for the topping hob. For teeth range 5, $N_a = 5$; 6, 6; 7–8, 7.47; 9–11, 9.9; 12–17, 14.07; 18–34, 23.54; 35 and over, 56.

Copyright 2004, Industrial Press, Inc., New York, NY

Proportions of Sprockets.— Typical proportions of single-strand and multiple-strand cast roller chain sprockets, as provided by the American Chain Association, are shown in Table 7. Typical proportions of roller chain bar-steel sprockets, also provided by this association, are shown in Table 8.

Table 7. Typical Proportions of Single-Strand and Multiple-Strand Cast Roller Chain Sprockets



Single-Strand



Multiple-Strand

Sprocket Web Thickness, *T*, for Various Pitches *P*

Single-Strand								Multiple-Strand							
P	*T*	*P*	*T*	*P*	*T*	*P*	*T*	*P*	*T*	*P*	*T*	*P*	*T*	*P*	*T*
3/8	.312	3/4	.437	1 1/2	.625	2 1/4	1.000	3/8	.375	3/4	.500	1 1/2	.750	2 1/4	1.125
1/2	.375	1	.500	1 3/4	.750	2 1/2	1.125	1/2	.406	1	.562	1 3/4	.875	2 1/2	1.250
5/8	.406	1 1/4	.562	2	.875	3	1.250	5/8	.437	1 1/4	.625	2	1.000	3	1.500

Formulas for Dimensions of Single and Multiple Sprockets

$H = 0.375 + \frac{D}{6} + 0.01\,PD$

$L = 4H$ for semi-steel castings

$C = 0.5P$

$C' = 0.9P$

$E = 0.625P + 0.93W$

$F = 0.150 + 0.25P$

$G = 2T$

$R = 0.4P$ for single-strand sprockets

$R = 0.5T$ for multiple-strand sprockets

All dimensions in inches. Where: P = chain pitch and W = nominal chain width.

Table 8. Typical Proportions of Roller Chain Bar-steel Sprockets



$H = Z + D/6 + 0.01\,PD$

For PD up to 2 inches, $Z = 0.125$ inch; for 2–4 inches, $Z = 0.187$ inch; for 4–6 inches, 0.25 inch; and for over 6 inches, 0.375 inch.

Hub length $L = 3.3\,H$, normally, with a minimum of $2.6H$.

Hub diameter $HD = D + 2H$, but not more than the maximum hub diameter MHD given by the formula:

$$MHD = P\left(\cot\frac{180°}{N} - 1\right) - 0.030$$

where: P = Chain pitch, in inches

N = Number of sprocket teeth

When sprocket wheels are designed with spokes, the usual assumptions made in order to determine suitable proportions are as follows: 1) That the maximum torque load acting on a sprocket is the chain tensile strength times the sprocket pitch radius; 2) That the torque load is equally divided between the arms by the rim; and 3) That each arm acts as a cantilever beam.

The arms are generally elliptical in cross section, the major axis twice the minor axis.

Copyright 2004, Industrial Press, Inc., New York, NY

Selection of Chain and Sprockets.— The smallest applicable pitch of roller chain is desirable for quiet operation and high speed. The horsepower capacity varies with the chain pitch as shown in Table 9. However, short pitch with high working load can often be obtained by the use of multiple-strand chain.

The small sprocket selected must be large enough to accommodate the shaft. Table 10 gives maximum bore and hub diameters consistent with commercial practice for sprockets with up to 25 teeth.

After selecting the small sprocket, the number of teeth in the larger sprocket is determined by the desired ratio of the shaft speed. Overemphasis on the exactness in the speed ratio may result in a cumbersome and expensive installation. In most cases, satisfactory operation can be obtained with a minor change in speed of one or both shafts.

Table 9. Horsepower Ratings for Roller Chain–1986

To properly use this table the following factors must be taken into consideration:
1) Service factors
2) Multiple Strand Factors
3) Lubrication

Service Factors: See Table 15.

Multiple Strand Factors: For two strands, the multiple strand factor is 1.7; for three strands, it is 2.5; and for four strands, it is 3.3.

Lubrication:

Required type of lubrication is indicated at the bottom of each roller chain size section of the table. For a description of each type of lubrication, see page 2463.

Type A — Manual or Drip Lubrication
Type B — Bath or Disc Lubrication
Type C — Oil Stream Lubrication

To find the required horsepower table rating, use the following formula:

$$\text{Required hp Table Rating} = \frac{\text{hp to be Transmitted} \times \text{Service Factor}}{\text{Multiple-Strand Factor}}$$

¼-inch Pitch Standard Single-Strand Roller Chain — No. 25

No. of Teeth Small Spkt.	Revolutions per Minute — Small Sprocket[a]												
	50	100	300	500	700	900	1200	1500	1800	2100	2500	3000	3500
	Horsepower Rating												
11	0.03	0.05	0.14	0.23	0.31	0.39	0.50	0.62	0.73	0.83	0.98	1.15	1.32
12	0.03	0.06	0.16	0.25	0.34	0.43	0.55	0.68	0.80	0.92	1.07	1.26	1.45
13	0.04	0.06	0.17	0.27	0.37	0.47	0.60	0.74	0.87	1.00	1.17	1.38	1.58
14	0.04	0.07	0.19	0.30	0.40	0.50	0.65	0.80	0.94	1.08	1.27	1.49	1.71
15	0.04	0.08	0.20	0.32	0.43	0.54	0.70	0.86	1.01	1.17	1.36	1.61	1.85
16	0.04	0.08	0.22	0.34	0.47	0.58	0.76	0.92	1.09	1.25	1.46	1.72	1.98
17	0.05	0.09	0.23	0.37	0.50	0.62	0.81	0.99	1.16	1.33	1.56	1.84	2.11
18	0.05	0.09	0.25	0.39	0.53	0.66	0.86	1.05	1.24	1.42	1.66	1.96	2.25
19	0.05	0.10	0.26	0.41	0.56	0.70	0.91	1.11	1.31	1.50	1.76	2.07	2.38
20	0.06	0.10	0.28	0.44	0.59	0.74	0.96	1.17	1.38	1.59	1.86	2.19	2.52
21	0.06	0.11	0.29	0.46	0.62	0.78	1.01	1.24	1.46	1.68	1.96	2.31	2.66
22	0.06	0.11	0.31	0.48	0.66	0.82	1.07	1.30	1.53	1.76	2.06	2.43	2.79
23	0.06	0.12	0.32	0.51	0.69	0.86	1.12	1.37	1.61	1.85	2.16	2.55	2.93
24	0.07	0.13	0.34	0.53	0.72	0.90	1.17	1.43	1.69	1.94	2.27	2.67	3.07
25	0.07	0.13	0.35	0.56	0.75	0.94	1.22	1.50	1.76	2.02	2.37	2.79	3.21
26	0.07	0.14	0.37	0.58	0.79	0.98	1.28	1.56	1.84	2.11	2.47	2.91	3.34
28	0.08	0.15	0.40	0.63	0.85	1.07	1.38	1.69	1.99	2.29	2.68	3.15	3.62
30	0.08	0.16	0.43	0.68	0.92	1.15	1.49	1.82	2.15	2.46	2.88	3.40	3.90
32	0.09	0.17	0.46	0.73	0.98	1.23	1.60	1.95	2.30	2.64	3.09	3.64	4.18
35	0.10	0.19	0.51	0.80	1.08	1.36	1.76	2.15	2.53	2.91	3.41	4.01	4.61
40	0.12	0.22	0.58	0.92	1.25	1.57	2.03	2.48	2.93	3.36	3.93	4.64	5.32
45	0.13	0.25	0.66	1.05	1.42	1.78	2.31	2.82	3.32	3.82	4.47	5.26	6.05
	Type A				Type B								

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ***(Continued)*** **Horsepower Ratings for Roller Chain–1986**

⅜-inch Pitch Standard Single-Strand Roller Chain — No. 35	No. of Teeth Small Sprkt.	Revolutions per Minute — Small Sprocket[a]												
		50	100	300	500	700	900	1200	1500	1800	2100	2500	3000	3500
		Horsepower Rating												
	11	0.10	0.18	0.49	0.77	1.05	1.31	1.70	2.08	2.45	2.82	3.30	2.94	2.33
	12	0.11	0.20	0.54	0.85	1.15	1.44	1.87	2.29	2.70	3.10	3.62	3.35	2.66
	13	0.12	0.22	0.59	0.93	1.26	1.57	2.04	2.49	2.94	3.38	3.95	3.77	3.00
	14	0.13	0.24	0.63	1.01	1.36	1.71	2.21	2.70	3.18	3.66	4.28	4.22	3.35
	15	0.14	0.25	0.68	1.08	1.47	1.84	2.38	2.91	3.43	3.94	4.61	4.68	3.71
	16	0.15	0.27	0.73	1.16	1.57	1.97	2.55	3.12	3.68	4.22	4.94	5.15	4.09
	17	0.16	0.29	0.78	1.24	1.68	2.10	2.73	3.33	3.93	4.51	5.28	5.64	4.48
	18	0.17	0.31	0.83	1.32	1.78	2.24	2.90	3.54	4.18	4.80	5.61	6.15	4.88
	19	0.18	0.33	0.88	1.40	1.89	2.37	3.07	3.76	4.43	5.09	5.95	6.67	5.29
	20	0.19	0.35	0.93	1.48	2.00	2.51	3.25	3.97	4.68	5.38	6.29	7.20	5.72
	21	0.20	0.37	0.98	1.56	2.11	2.64	3.42	4.19	4.93	5.67	6.63	7.75	6.15
	22	0.21	0.38	1.03	1.64	2.22	2.78	3.60	4.40	5.19	5.96	6.97	8.21	6.59
	23	0.22	0.40	1.08	1.72	2.33	2.92	3.78	4.62	5.44	6.25	7.31	8.62	7.05
	24	0.23	0.42	1.14	1.80	2.44	3.05	3.96	4.84	5.70	6.55	7.66	9.02	7.51
	25	0.24	0.44	1.19	1.88	2.55	3.19	4.13	5.05	5.95	6.84	8.00	9.43	7.99
	26	0.25	0.46	1.24	1.96	2.66	3.33	4.31	5.27	6.21	7.14	8.35	9.84	8.47
	28	0.27	0.50	1.34	2.12	2.88	3.61	4.67	5.71	6.73	7.73	9.05	10.7	9.47
	30	0.29	0.54	1.45	2.29	3.10	3.89	5.03	6.15	7.25	8.33	9.74	11.5	10.5
	32	0.31	0.58	1.55	2.45	3.32	4.17	5.40	6.60	7.77	8.93	10.4	12.3	11.6
	35	0.34	0.64	1.71	2.70	3.66	4.59	5.95	7.27	8.56	9.84	11.5	13.6	13.2
	40	0.39	0.73	1.97	3.12	4.23	5.30	6.87	8.40	9.89	11.4	13.3	15.7	16.2
	45	0.45	0.83	2.24	3.55	4.80	6.02	7.80	9.53	11.2	12.9	15.1	17.8	19.3
		Type A		Type B							Type C			

½-inch Pitch Standard Single-Strand Roller Chain — No. 40	No. of Teeth Small Sprkt.	Revolutions per Minute — Small Sprocket[a]												
		50	100	200	300	400	500	700	900	1000	1200	1400	1600	1800
		Horsepower Rating												
	11	0.23	0.43	0.80	1.16	1.50	1.83	2.48	3.11	3.42	4.03	4.63	5.22	4.66
	12	0.25	0.47	0.88	1.27	1.65	2.01	2.73	3.42	3.76	4.43	5.09	5.74	5.31
	13	0.28	0.52	0.96	1.39	1.80	2.20	2.97	3.73	4.10	4.83	5.55	6.26	5.99
	14	0.30	0.56	1.04	1.50	1.95	2.38	3.22	4.04	4.44	5.23	6.01	6.78	6.70
	15	0.32	0.60	1.12	1.62	2.10	2.56	3.47	4.35	4.78	5.64	6.47	7.30	7.43
	16	0.35	0.65	1.20	1.74	2.25	2.75	3.72	4.66	5.13	6.04	6.94	7.83	8.18
	17	0.37	0.69	1.29	1.85	2.40	2.93	3.97	4.98	5.48	6.45	7.41	8.36	8.96
	18	0.39	0.73	1.37	1.97	2.55	3.12	4.22	5.30	5.82	6.86	7.88	8.89	9.76
	19	0.42	0.78	1.45	2.09	2.71	3.31	4.48	5.62	6.17	7.27	8.36	9.42	10.5
	20	0.44	0.82	1.53	2.21	2.86	3.50	4.73	5.94	6.53	7.69	8.83	9.96	11.1
	21	0.46	0.87	1.62	2.33	3.02	3.69	4.99	6.26	6.88	8.11	9.31	10.5	11.7
	22	0.49	0.91	1.70	2.45	3.17	3.88	5.25	6.58	7.23	8.52	9.79	11.0	12.3
	23	0.51	0.96	1.78	2.57	3.33	4.07	5.51	6.90	7.59	8.94	10.3	11.6	12.9
	24	0.54	1.00	1.87	2.69	3.48	4.26	5.76	7.23	7.95	9.36	10.8	12.1	13.5
	25	0.56	1.05	1.95	2.81	3.64	4.45	6.02	7.55	8.30	9.78	11.2	12.7	14.1
	26	0.58	1.09	2.04	2.93	3.80	4.64	6.28	7.88	8.66	10.2	11.7	13.2	14.7
	28	0.63	1.18	2.20	3.18	4.11	5.03	6.81	8.54	9.39	11.1	12.7	14.3	15.9
	30	0.68	1.27	2.38	3.42	4.43	5.42	7.33	9.20	10.1	11.9	13.7	15.4	17.2
	32	0.73	1.36	2.55	3.67	4.75	5.81	7.86	9.86	10.8	12.8	14.7	16.5	18.4
	35	0.81	1.50	2.81	4.04	5.24	6.40	8.66	10.9	11.9	14.1	16.2	18.2	20.3
	40	0.93	1.74	3.24	4.67	6.05	7.39	10.0	12.5	13.8	16.3	18.7	21.1	23.4
	45	1.06	1.97	3.68	5.30	6.87	8.40	11.4	14.2	15.7	18.5	21.2	23.9	26.6
		Type A		Type B							Type C			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ***(Continued)*** **Horsepower Ratings for Roller Chain–1986**

	No. of Teeth Small Sprkt.	Revolutions per Minute — Small Sprocket[a]												
		10	25	50	100	200	300	400	500	700	900	1000	1200	1400
		Horsepower Rating												
½-inch Pitch Light Weight Machinery Roller Chain — No. 41	11	0.03	0.07	0.13	0.24	0.44	0.64	0.82	1.01	1.37	1.71	1.88	1.71	1.36
	12	0.03	0.07	0.14	0.26	0.49	0.70	0.91	1.11	1.50	1.88	2.07	1.95	1.55
	13	0.04	0.08	0.15	0.28	0.53	0.76	0.99	1.21	1.63	2.05	2.25	2.20	1.75
	14	0.04	0.09	0.16	0.31	0.57	0.83	1.07	1.31	1.77	2.22	2.44	2.46	1.95
	15	0.04	0.09	0.18	0.33	0.62	0.89	1.15	1.41	1.91	2.39	2.63	2.73	2.17
	16	0.04	0.10	0.19	0.36	0.66	0.95	1.24	1.51	2.05	2.57	2.82	3.01	2.39
	17	0.05	0.11	0.20	0.38	0.71	1.02	1.32	1.61	2.18	2.74	3.01	3.29	2.61
	18	0.05	0.12	0.22	0.40	0.75	1.08	1.40	1.72	2.32	2.91	3.20	3.59	2.85
	19	0.05	0.12	0.23	0.43	0.80	1.15	1.49	1.82	2.46	3.09	3.40	3.89	3.09
	20	0.06	0.13	0.24	0.45	0.84	1.21	1.57	1.92	2.60	3.26	3.59	4.20	3.33
	21	0.06	0.14	0.26	0.48	0.89	1.28	1.66	2.03	2.74	3.44	3.78	4.46	3.59
	22	0.06	0.14	0.27	0.50	0.93	1.35	1.74	2.13	2.89	3.62	3.98	4.69	3.85
	23	0.06	0.15	0.28	0.53	0.98	1.41	1.83	2.24	3.03	3.80	4.17	4.92	4.11
	24	0.07	0.16	0.29	0.55	1.03	1.48	1.92	2.34	3.17	3.97	4.37	5.15	4.38
	25	0.07	0.17	0.31	0.57	1.07	1.55	2.00	2.45	3.31	4.15	4.57	5.38	4.66
	26	0.07	0.17	0.32	0.60	1.12	1.61	2.09	2.55	3.46	4.33	4.76	5.61	4.94
	28	0.08	0.19	0.35	0.65	1.21	1.75	2.26	2.77	3.74	4.69	5.16	6.08	5.52
	30	0.08	0.20	0.38	0.70	1.31	1.88	2.44	2.98	4.03	5.06	5.56	6.55	6.13
	32	0.09	0.22	0.40	0.75	1.40	2.02	2.61	3.20	4.33	5.42	5.96	7.03	6.75
	35	0.10	0.24	0.44	0.83	1.54	2.22	2.88	3.52	4.76	5.97	6.57	7.74	7.72
	40	0.12	0.27	0.51	0.96	1.78	2.57	3.33	4.07	5.50	6.90	7.59	8.94	9.43
	45	0.14	0.31	0.58	1.08	2.02	2.92	3.78	4.62	6.25	7.84	8.62	10.2	11.3
		Type A				Type B							Type C	

	No. of Teeth Small Sprkt.	Revolutions per Minute — Small Sprocket[a]												
		25	50	100	200	300	400	500	700	900	1000	1200	1400	1600
		Horsepower Rating												
⅝-inch Pitch Standard Single-Strand Roller Chain — No. 50	11	0.24	0.45	0.84	1.56	2.25	2.92	3.57	4.83	6.06	6.66	7.85	8.13	6.65
	12	0.26	0.49	0.92	1.72	2.47	3.21	3.92	5.31	6.65	7.31	8.62	9.26	7.58
	13	0.29	0.54	1.00	1.87	2.70	3.50	4.27	5.78	7.25	7.97	9.40	10.4	8.55
	14	0.31	0.58	1.09	2.03	2.92	3.79	4.63	6.27	7.86	8.64	10.2	11.7	9.55
	15	0.34	0.63	1.17	2.19	3.15	4.08	4.99	6.75	8.47	9.31	11.0	12.6	10.6
	16	0.36	0.67	1.26	2.34	3.38	4.37	5.35	7.24	9.08	9.98	11.8	13.5	11.7
	17	0.39	0.72	1.34	2.50	3.61	4.67	5.71	7.73	9.69	10.7	12.6	14.4	12.8
	18	0.41	0.76	1.43	2.66	3.83	4.97	6.07	8.22	10.3	11.3	13.4	15.3	13.9
	19	0.43	0.81	1.51	2.82	4.07	5.27	6.44	8.72	10.9	12.0	14.2	16.3	15.1
	20	0.46	0.86	1.60	2.98	4.30	5.57	6.80	9.21	11.5	12.7	15.0	17.2	16.3
	21	0.48	0.90	1.69	3.14	4.53	5.87	7.17	9.71	12.2	13.4	15.8	18.1	17.6
	22	0.51	0.95	1.77	3.31	4.76	6.17	7.54	10.2	12.8	14.1	16.6	19.1	18.8
	23	0.53	1.00	1.86	3.47	5.00	6.47	7.91	10.7	13.4	14.8	17.4	20.0	20.1
	24	0.56	1.04	1.95	3.63	5.23	6.78	8.29	11.2	14.1	15.5	18.2	20.9	21.4
	25	0.58	1.09	2.03	3.80	5.47	7.08	8.66	11.7	14.7	16.2	19.0	21.9	22.8
	26	0.61	1.14	2.12	3.96	5.70	7.39	9.03	12.2	15.3	16.9	19.9	22.8	24.2
	28	0.66	1.23	2.30	4.29	6.18	8.01	9.79	13.2	16.6	18.3	21.5	24.7	27.0
	30	0.71	1.33	2.48	4.62	6.66	8.63	10.5	14.3	17.9	19.7	23.2	26.6	30.0
	32	0.76	1.42	2.66	4.96	7.14	9.25	11.3	15.3	19.2	21.1	24.9	28.6	32.2
	35	0.84	1.57	2.93	5.46	7.86	10.2	12.5	16.9	21.1	23.2	27.4	31.5	35.5
	40	0.97	1.81	3.38	6.31	9.08	11.8	14.4	19.5	24.4	26.8	31.6	36.3	41.0
	45	1.10	2.06	3.84	7.16	10.3	13.4	16.3	22.1	27.7	30.5	35.9	41.3	46.5
		Type A			Type B					Type C				

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ***(Continued)*** **Horsepower Ratings for Roller Chain–1986**

¾-inch Pitch Standard Single-Strand Roller Chain — No. 60														
	No. of Teeth Small Spkt.	Revolutions per Minute — Small Sprocket[a]												
		25	50	100	150	200	300	400	500	600	700	800	900	1000
		Horsepower Rating												
	11	0.41	0.77	1.44	2.07	2.69	3.87	5.02	6.13	7.23	8.30	9.36	10.4	11.4
	12	0.45	0.85	1.58	2.28	2.95	4.25	5.51	6.74	7.94	9.12	10.3	11.4	12.6
	13	0.50	0.92	1.73	2.49	3.22	4.64	6.01	7.34	8.65	9.94	11.2	12.5	13.7
	14	0.54	1.00	1.87	2.69	3.49	5.02	6.51	7.96	9.37	10.8	12.1	13.5	14.8
	15	0.58	1.08	2.01	2.90	3.76	5.41	7.01	8.57	10.1	11.6	13.1	14.5	16.0
	16	0.62	1.16	2.16	3.11	4.03	5.80	7.52	9.19	10.8	12.4	14.0	15.6	17.1
	17	0.66	1.24	2.31	3.32	4.30	6.20	8.03	9.81	11.6	13.3	15.0	16.7	18.3
	18	0.70	1.31	2.45	3.53	4.58	6.59	8.54	10.4	12.3	14.1	15.9	17.7	19.5
	19	0.75	1.39	2.60	3.74	4.85	6.99	9.05	11.1	13.0	15.0	16.9	18.8	20.6
	20	0.79	1.47	2.75	3.96	5.13	7.38	9.57	11.7	13.8	15.8	17.9	19.8	21.8
	21	0.83	1.55	2.90	4.17	5.40	7.78	10.1	12.3	14.5	16.7	18.8	20.9	23.0
	22	0.87	1.63	3.05	4.39	5.68	8.19	10.6	13.0	15.3	17.5	19.8	22.0	24.2
	23	0.92	1.71	3.19	4.60	5.96	8.59	11.1	13.6	16.0	18.4	20.8	23.1	25.4
	24	0.96	1.79	3.35	4.82	6.24	8.99	11.6	14.2	16.8	19.3	21.7	24.2	26.6
	25	1.00	1.87	3.50	5.04	6.52	9.40	12.2	14.9	17.5	20.1	22.7	25.3	27.8
	26	1.05	1.95	3.65	5.25	6.81	9.80	12.7	15.5	18.3	21.0	23.7	26.4	29.0
	28	1.13	2.12	3.95	5.69	7.37	10.6	13.8	16.8	19.8	22.8	25.7	28.5	31.4
	30	1.22	2.28	4.26	6.13	7.94	11.4	14.8	18.1	21.4	24.5	27.7	30.8	33.8
	32	1.31	2.45	4.56	6.57	8.52	12.3	15.9	19.4	22.9	26.3	29.7	33.0	36.3
	35	1.44	2.69	5.03	7.24	9.38	13.5	17.5	21.4	25.2	29.0	32.7	36.3	39.9
	40	1.67	3.11	5.81	8.37	10.8	15.6	20.2	24.7	29.1	33.5	37.7	42.0	46.1
	45	1.89	3.53	6.60	9.50	12.3	17.7	23.0	28.1	33.1	38.0	42.9	47.7	52.4
		Type A		Type B							Type C			

1-inch Pitch Standard Single-Strand Roller Chain — No. 80														
	No. of Teeth Small Spkt.	Revolutions per Minute — Small Sprocket[a]												
		25	50	100	150	200	300	400	500	600	700	800	900	1000
		Horsepower Ratings												
	11	0.97	1.80	3.36	4.84	6.28	9.04	11.7	14.3	16.9	19.4	21.9	23.0	19.6
	12	1.06	1.98	3.69	5.32	6.89	9.93	12.9	15.7	18.5	21.3	24.0	26.2	22.3
	13	1.16	2.16	4.03	5.80	7.52	10.8	14.0	17.1	20.2	23.2	26.2	29.1	25.2
	14	1.25	2.34	4.36	6.29	8.14	11.7	15.2	18.6	21.9	25.1	28.4	31.5	28.2
	15	1.35	2.52	4.70	6.77	8.77	12.6	16.4	20.0	23.6	27.1	30.6	34.0	31.2
	16	1.45	2.70	5.04	7.26	9.41	13.5	17.6	21.5	25.3	29.0	32.8	36.4	34.4
	17	1.55	2.88	5.38	7.75	10.0	14.5	18.7	22.9	27.0	31.0	35.0	38.9	37.7
	18	1.64	3.07	5.72	8.25	10.7	15.4	19.9	24.4	28.7	33.0	37.2	41.4	41.1
	19	1.74	3.25	6.07	8.74	11.3	16.3	21.1	25.8	30.4	35.0	39.4	43.8	44.5
	20	1.84	3.44	6.41	9.24	12.0	17.2	22.3	27.3	32.2	37.0	41.7	46.3	48.1
	21	1.94	3.62	6.76	9.74	12.6	18.2	23.5	28.8	33.9	39.0	43.9	48.9	51.7
	22	2.04	3.81	7.11	10.2	13.3	19.1	24.8	30.3	35.7	41.0	46.2	51.4	55.5
	23	2.14	4.00	7.46	10.7	13.9	20.1	26.0	31.8	37.4	43.0	48.5	53.9	59.3
	24	2.24	4.19	7.81	11.3	14.6	21.0	27.2	33.2	39.2	45.0	50.8	56.4	62.0
	25	2.34	4.37	8.16	11.8	15.2	21.9	28.4	34.7	40.9	47.0	53.0	59.0	64.8
	26	2.45	4.56	8.52	12.3	15.9	22.9	29.7	36.2	42.7	49.1	55.3	61.5	67.6
	28	2.65	4.94	9.23	13.3	17.2	24.8	32.1	39.3	46.3	53.2	59.9	66.7	73.3
	30	2.85	5.33	9.94	14.3	18.5	26.7	34.6	42.3	49.9	57.3	64.6	71.8	78.9
	32	3.06	5.71	10.7	15.3	19.9	28.6	37.1	45.4	53.5	61.4	69.2	77.0	84.6
	35	3.37	6.29	11.7	16.9	21.9	31.6	40.9	50.0	58.9	67.6	76.3	84.8	93.3
	40	3.89	7.27	13.6	19.5	25.3	36.4	47.2	57.7	68.0	78.1	88.1	99.0	108
	45	4.42	8.25	15.4	22.2	28.7	41.4	53.6	65.6	77.2	88.7	100	111	122
		Type A		Type B					Type C					

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. ***(Continued)*** **Horsepower Ratings for Roller Chain–1986**

1¼-inch Pitch Standard Single-Strand Roller Chain — No. 100

No. of Teeth Small Spkt.	Revolutions per Minute — Small Sprocket[a]												
	10	25	50	100	150	200	300	400	500	600	700	800	900
	Horsepower Rating												
11	0.81	1.85	3.45	6.44	9.28	12.0	17.3	22.4	27.4	32.3	37.1	32.8	27.5
12	0.89	2.03	3.79	7.08	10.2	13.2	19.0	24.6	30.1	35.5	40.8	37.3	31.3
13	0.97	2.22	4.13	7.72	11.1	14.4	20.7	26.9	32.8	38.7	44.5	42.1	35.3
14	1.05	2.40	4.48	8.36	12.0	15.6	22.5	29.1	35.6	41.9	48.2	47.0	39.4
15	1.13	2.59	4.83	9.01	13.0	16.8	24.2	31.4	38.3	45.2	51.9	52.2	43.7
16	1.22	2.77	5.17	9.66	13.9	18.0	26.0	33.6	41.1	48.4	55.6	57.5	48.2
17	1.30	2.96	5.52	10.3	14.8	19.2	27.7	35.9	43.9	51.7	59.4	63.0	52.8
18	1.38	3.15	5.88	11.0	15.8	20.5	29.5	38.2	46.7	55.0	63.2	68.6	57.5
19	1.46	3.34	6.23	11.6	16.7	21.7	31.2	40.5	49.5	58.3	67.0	74.4	62.3
20	1.55	3.53	6.58	12.3	17.7	22.9	33.0	42.8	52.3	61.6	70.8	79.8	67.3
21	1.63	3.72	6.94	13.0	18.7	24.2	34.8	45.1	55.1	65.0	74.6	84.2	72.4
22	1.71	3.91	7.30	13.6	19.6	25.4	36.6	47.4	58.0	68.3	78.5	88.5	77.7
23	1.80	4.10	7.66	14.3	20.6	26.7	38.4	49.8	60.8	71.7	82.3	92.8	83.0
24	1.88	4.30	8.02	15.0	21.5	27.9	40.2	52.1	63.7	75.0	86.2	97.2	88.5
25	1.97	4.49	8.38	15.6	22.5	29.2	42.0	54.4	66.6	78.4	90.1	102	94.1
26	2.05	4.68	8.74	16.3	23.5	30.4	43.8	56.8	69.4	81.8	94.0	106	99.8
28	2.22	5.07	9.47	17.7	25.5	33.0	47.5	61.5	75.2	88.6	102	115	112
30	2.40	5.47	10.2	19.0	27.4	35.5	51.2	66.3	81.0	95.5	110	124	124
32	2.57	5.86	10.9	20.4	29.4	38.1	54.9	71.1	86.9	102	118	133	136
35	2.83	6.46	12.0	22.5	32.4	42.0	60.4	78.3	95.7	113	130	146	156
40	3.27	7.46	13.9	26.0	37.4	48.5	69.8	90.4	111	130	150	169	188
45	3.71	8.47	15.8	29.5	42.5	55.0	79.3	103	126	148	170	192	213
	Type A			Type B				Type C					

1½-inch Pitch Standard Single-Strand Roller Chain — No. 120

No. of Teeth Small Spkt.	Revolutions per Minute — Small Sprocket[a]												
	10	25	50	100	150	200	300	400	500	600	700	800	900
	Horsepower Rating												
11	1.37	3.12	5.83	10.9	15.7	20.3	29.2	37.9	46.3	54.6	46.3	37.9	31.8
12	1.50	3.43	6.40	11.9	17.2	22.3	32.1	41.6	50.9	59.9	52.8	43.2	36.2
13	1.64	3.74	6.98	13.0	18.8	24.3	35.0	45.4	55.5	65.3	59.5	48.7	40.8
14	1.78	4.05	7.56	14.1	20.3	26.3	37.9	49.1	60.1	70.8	66.5	54.4	45.6
15	1.91	4.37	8.15	15.2	21.9	28.4	40.9	53.0	64.7	76.3	73.8	60.4	50.6
16	2.05	4.68	8.74	16.3	23.5	30.4	43.8	56.8	69.4	81.8	81.3	66.5	55.7
17	2.19	5.00	9.33	17.4	25.1	32.5	46.8	60.6	74.1	87.3	89.0	72.8	61.0
18	2.33	5.32	9.92	18.5	26.7	34.6	49.8	64.5	78.8	92.9	97.0	79.4	66.5
19	2.47	5.64	10.5	19.6	28.3	36.6	52.8	68.4	83.6	98.5	105	86.1	72.1
20	2.61	5.96	11.1	20.7	29.9	38.7	55.8	72.2	88.3	104	114	92.9	77.9
21	2.75	6.28	11.7	21.9	31.5	40.8	58.8	76.2	93.1	110	122	100	83.8
22	2.90	6.60	12.3	23.0	33.1	42.9	61.8	80.1	97.9	115	131	107	89.9
23	3.04	6.93	12.9	24.1	34.8	45.0	64.9	84.0	103	121	139	115	96.1
24	3.18	7.25	13.5	25.3	36.4	47.1	67.9	88.0	108	127	146	122	102
25	3.32	7.58	14.1	26.4	38.0	49.3	71.0	91.9	112	132	152	130	109
26	3.47	7.91	14.8	27.5	39.7	51.4	74.0	95.9	117	138	159	138	115
28	3.76	8.57	16.0	29.8	43.0	55.7	80.2	104	127	150	172	154	129
30	4.05	9.23	17.2	32.1	46.3	60.0	86.4	112	137	161	185	171	143
32	4.34	9.90	18.5	34.5	49.6	64.3	92.6	120	147	173	199	188	158
35	4.78	10.9	20.3	38.0	54.7	70.9	102	132	162	190	219	215	180
40	5.52	12.6	23.5	43.9	63.2	81.8	118	153	187	220	253	…	…
45	6.27	14.3	26.7	49.8	71.7	92.9	134	173	212	250	287	…	…
	Type A			Type B				Type C					

[a] For lower or higher rpm, larger chain sizes, and rpm above 3500, see B29.1M-1993.

For use of table see page 2451.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Recommended Roller Chain Sprocket Maximum Bore and Hub Diameters

No. of Teeth	Roller Chain Pitch 3/8 Max. Bore	3/8 Max. Hub Dia.	1/2 Max. Bore	1/2 Max. Hub Dia.	5/8 Max. Bore	5/8 Max. Hub Dia.	3/4 Max. Bore	3/4 Max. Hub Dia.	1 Max. Bore	1 Max. Hub Dia.
11	19/32	55/64	25/32	1 11/64	31/32	1 15/32	1 1/4	1 49/64	1 5/8	2 3/8
12	5/8	63/64	7/8	1 21/64	1 5/32	1 43/64	1 9/32	2 1/64	1 25/32	2 45/64
13	3/4	1 7/64	1	1 1/2	1 9/32	1 7/8	1 1/2	2 1/4	2	3 1/64
14	27/32	1 15/64	1 5/32	1 21/32	1 5/16	2 5/64	1 3/4	2 1/2	2 9/32	3 11/32
15	7/8	1 23/64	1 1/4	1 13/16	1 17/32	2 9/32	1 25/32	2 3/4	2 13/32	3 43/64
16	31/32	1 15/32	1 9/32	1 63/64	1 11/16	2 31/64	1 31/32	2 63/64	2 23/32	3 63/64
17	1 3/32	1 19/32	1 3/8	2 9/64	1 25/32	2 11/16	2 7/32	3 7/32	2 13/16	4 5/16
18	1 7/32	1 23/32	1 17/32	2 19/64	1 7/8	2 57/64	2 9/32	3 15/32	3 1/8	4 41/64
19	1 1/4	1 27/32	1 11/16	2 29/64	2 1/16	3 5/64	2 7/16	3 45/64	3 5/16	4 61/64
20	1 9/32	1 61/64	1 25/32	2 5/8	2 1/4	3 9/32	2 11/16	3 61/64	3 1/2	5 5/32
21	1 5/16	2 5/64	1 25/32	2 25/32	2 9/32	3 31/64	2 13/16	4 3/16	3 3/4	5 19/32
22	1 7/16	2 13/16	1 15/16	2 15/16	2 7/16	3 11/16	2 15/16	4 7/16	3 7/8	5 39/64
23	1 9/16	2 5/16	2 3/32	3 3/32	2 5/8	3 57/64	3 1/8	4 43/64	4 3/16	6 15/64
24	1 11/16	2 7/16	2 1/4	3 17/64	2 13/16	4 5/64	3 1/4	4 29/32	4 9/16	6 9/16
25	1 3/4	2 9/16	2 9/32	3 27/64	2 27/32	4 9/32	3 3/8	5 5/32	4 11/16	6 7/8

No. of Teeth	Roller Chain Pitch 1 1/4 Max. Bore	1 1/4 Max. Hub Dia.	1 1/2 Max. Bore	1 1/2 Max. Hub Dia.	1 3/4 Max. Bore	1 3/4 Max. Hub Dia.	2 Max. Bore	2 Max. Hub Dia.	2 1/2 Max. Bore	2 1/2 Max. Hub Dia.
11	1 31/32	2 31/32	2 5/16	3 37/64	2 13/16	4 11/64	3 9/32	4 25/32	3 15/16	5 63/64
12	2 9/32	3 3/8	2 3/4	4 1/16	3 1/4	4 3/4	3 5/8	5 27/64	4 23/32	6 51/64
13	2 17/32	3 25/32	3 1/16	4 35/64	3 9/16	5 5/16	4 1/16	6 5/64	5 3/32	7 39/64
14	2 11/16	4 3/16	3 5/16	5 1/32	3 7/8	5 7/8	4 11/16	6 23/32	5 23/32	8 27/64
15	3 3/32	4 19/32	3 3/4	5 33/64	4 7/16	6 29/64	4 7/8	7 3/8	6 1/4	9 7/32
16	3 9/32	5	4	6	4 11/16	7 1/64	5 1/2	8 1/64	7	10 1/32
17	3 21/32	5 13/32	4 15/32	6 31/64	5 1/16	7 37/64	5 11/16	8 21/32	7 7/16	10 27/32
18	3 25/32	5 51/64	4 21/32	6 31/32	5 5/8	8 9/64	6 1/4	9 5/16	8 1/8	11 41/64
19	4 3/16	6 13/64	4 15/16	7 29/64	5 11/16	8 45/64	6 7/8	9 61/64	9	12 7/16
20	4 19/32	6 39/64	5 7/16	7 15/16	6 1/4	9 17/64	7	10 19/32	9 3/4	13 1/4
21	4 11/16	7	5 11/16	8 27/64	6 13/16	9 53/64	7 3/4	11 15/64	10	14 3/64
22	4 7/8	7 13/32	5 7/8	8 57/64	7 1/4	10 25/64	8 3/8	11 7/8	10 7/8	14 27/32
23	5 5/16	7 13/16	6 3/8	9 3/8	7 7/16	10 15/16	9	12 33/64	11 5/8	15 21/32
24	5 11/16	8 13/64	6 13/16	9 55/64	8	11 1/2	9 5/8	13 5/32	13	16 29/64
25	5 23/32	8 39/64	7 1/4	10 11/32	8 9/16	12 1/16	10 1/4	13 51/64	13 1/2	17 1/4

All dimensions in inches.

For standard key dimensions see pages 2363 through 2364.

Source: American Chain Association.

Center Distance between Sprockets.— The center-to-center distance between sprockets, as a general rule, should not be less than 1½ times the diameter of the larger sprocket and not less than thirty times the pitch nor more than about 50 times the pitch, although much depends upon the speed and other conditions. A center distance equivalent to 80 pitches may be considered an approved maximum. Very long center distances result in catenary tension in the chain. If roller-chain drives are designed correctly, the center-to-center distance for some transmissions may be so short that the sprocket teeth nearly touch each other, assuming that the load is not too great and the number of teeth is not too small. To

Copyright 2004, Industrial Press, Inc., New York, NY

avoid interference of the sprocket teeth, the center distance must, of course, be somewhat greater than one-half the sum of the outside diameters of the sprockets. The chain should extend around at least 120 degrees of the pinion circumference, and this minimum amount of contact is obtained for all center distances provided the ratio is less than 3½ to 1. Other things being equal, a fairly long chain is recommended in preference to the shortest one allowed by the sprocket diameters, because the rate of chain elongation due to natural wear is inversely proportional to the length, and also because the greater elasticity of the longer strand tends to absorb irregularities of motion and to decrease the effect of shocks.

If possible, the center distance should be adjustable in order to take care of slack due to elongation from wear and this range of adjustment should be at least one and one-half pitches. A little slack is desirable as it allows the chain links to take the best position on the sprocket teeth and reduces the wear on the bearings. Too much sag or an excessive distance between the sprockets may cause the chain to whip up and down — a condition detrimental to smooth running and very destructive to the chain. The sprockets should run in a vertical plane, the sprocket axes being approximately horizontal, unless an idler is used on the slack side to keep the chain in position. The most satisfactory results are obtained when the slack side of the chain is on the bottom.

Center Distance for a Given Chain Length.— When the distance between the driving and driven sprockets can be varied to suit the length of the chain, this center distance for a tight chain may be determined by the following formula, in which c = center-to-center distance in inches; L = chain length in pitches; P = pitch of chain; N = number of teeth in large sprocket; n = number of teeth in small sprocket.

$$c = \frac{P}{8}(2L - N - n + \sqrt{(2L - N - n)^2 - 0.810(N - n)^2})$$

This formula is approximate, but the error is less than the variation in the length of the best chains. The length L in pitches should be an even number for a roller chain, so that the use of an offset connecting link will not be necessary.

Idler Sprockets.— When sprockets have a fixed center distance or are non-adjustable, it may be advisable to use an idler sprocket for taking up the slack. The idler should preferably be placed against the slack side between the two strands of the chain. When a sprocket is applied to the tight side of the chain to reduce vibration, it should be on the lower side and so located that the chain will run in a straight line between the two main sprockets. A sprocket will wear excessively if the number of teeth is too small and the speed too high, because there is impact between the teeth and rollers even though the idler carries practically no load.

Length of Driving Chain.— The total length of a block chain should be given in multiples of the pitch, whereas for a roller chain, the length should be in multiples of twice the pitch, because the ends must be connected with an outside and inside link. The length of a chain can be calculated accurately enough for ordinary practice by the use of the following formula, in which L = chain length in pitches; C = center distance in pitches; N = number of teeth in large sprocket; n = number of teeth in small sprocket:

$$L = 2C + \frac{N}{2} + \frac{n}{2} + \left(\frac{N - n}{2\pi}\right)^2 \times \frac{1}{C}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ANSI Sprocket Tooth Form for Roller Chain *ANSI/ASME B29.1M-1993*



Seating Curve Data—Inches

P	D_r	Min. *R*	Min. D_s	D_s Tol.[a]	*P*	D_r	Min. *R*	Min. D_s	D_s Tol.[a]
0.250	0.130	0.0670	0.134	0.0055	1.250	0.750	0.3785	0.757	0.0070
0.375	0.200	0.1020	0.204	0.0055	1.500	0.875	0.4410	0.882	0.0075
0.500	0.306	0.1585	0.317	0.0060	1.750	1.000	0.5040	1.008	0.0080
0.500	0.312	0.1585	0.317	0.0060	2.000	1.125	0.5670	1.134	0.0085
0.625	0.400	0.2025	0.405	0.0060	2.250	1.406	0.7080	1.416	0.0090
0.750	0.469	0.2370	0.474	0.0065	2.500	1.562	0.7870	1.573	0.0095
1.000	0.625	0.3155	0.631	0.0070	3.000	1.875	0.9435	1.887	0.0105

[a] Plus tolerance only.

P = pitch (*ae*)

N = number of teeth D_r = nominal roller diameter

D_s = seating curve diameter = $1.005\,D_r + 0.003$ (in inches)

$R = \frac{1}{2} D_s$ (D_s has only plus tolerance)

$A = 35° + (60° \div N)$ $B = 18° - (56° \div N)$ $ac = 0.8\,D_r$

$M = 0.8\,D_r \cos(35° + (60° \div N))$

$T = 0.8\,D_r \sin(35° + (60° \div N))$

$E = 1.3025\,D_r + 0.0015$ (in inches)

Chord $xy = (2.605\,D_r + 0.003) \sin 9° - (28° \div N))$ (in inches)

$yz = D_r\,[1.4 \sin(17° - (64° \div N)) - 0.8 \sin(18° - (56° \div N))]$

Length of a line between *a* and *b* = $1.4\,D_r$

$W = 1.4\,D_r \cos(180° \div N)$; $V = 1.4\,D_r \sin(180° \div N)$

$F = D_r\,[0.8 \cos(18° - (56° \div N)) + 1.4 \cos(17° - (64° \div N)) - 1.3025] - 0.0015$ inch

$H = \sqrt{F^2 - (1.4D_r - 0.5P)^2}$

$S = 0.5\,P \cos(180° \div N) + H \sin(180° \div N)$

Approximate O.D. of sprocket when J is $0.3\,P = P\,[0.6 + \cot(180° \div N)]$

O.D. of sprocket when tooth is pointed $+ P \cot(180° \div N) + \cos(180° \div N)\,(D_s - D_r) + 2H$

Pressure angle for new chain = $xab = 35° - (120° \div N)$

Minimum pressure angle = $xab - B = 17° - (64° \div N)$;
Average pressure angle = $26° - (92° \div N)$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Standard Hob Design for Roller Chain Sprockets



Section Normal to Hob Teeth

Data for Laying Out Hob Outlines — Inches

P	P_n	*H*	*E*	O.D.	*W*	Bore	Keyway	No. Gashes
¼	0.2527	0.0675	0.0075	2⅝	2½	1.250	¼ × ⅛	13
⅜	0.379	0.101	0.012	3⅛	2½	1.250	¼ × ⅛	13
½	0.506	0.135	0.015	3⅜	2½	1.250	¼ × ⅛	12
⅝	0.632	0.170	0.018	3⅝	2½	1.250	11/4 × ⅛	12
¾	0.759	0.202	0.023	3¾	2⅞	1.250	¼ × ⅛	11
1	1.011	0.270	0.030	4⅜	3⅜	1.250	¼ × ⅛	11
1¼	1.264	0.337	0.038	4¾	4½	1.250	¼ × ⅛	10
1½	1.517	0.405	0.045	5⅜	5¼	1.250	¼ × ⅛	10
1¾	1.770	0.472	0.053	6⅜	6	1.500	⅜ × 3/16	9
2	2.022	0.540	0.060	6⅞	6¾	1.500	⅜ × 3/16	9
2¼	2.275	0.607	0.068	8	8½	1.750	⅜ × 3/16	8
2½	2.528	0.675	0.075	8⅝	9⅜	1.750	⅜ × 3/16	8
3	3.033	0.810	0.090	9¾	11¼	2.000	½ × 3/6	8

Hobs designed for a given roller diameter (D_r) and chain pitch (P) will cut any number of teeth.

P = Pitch of Chain

P_n = Normal Pitch of Hob = 1.011 P inches

D_s = Minimum Diameter of Seating Curve = 1.005 D_r + 0.003 inches

F = Radius Center for Arc GK; $TO = OU = P_n \div 2$

H = 0.27 P; E = 0.03 P = Radius of Fillet Circle

Q is located on line passing through F and J. Point J is intersection of line XY with circle of diameter D_s. R is found by trial and the arc of this radius is tangent to arc KG at K and to fillet radius.

OD = Outside Diameter = 1.7 (Bore + D_r + 0.7 P) approx.

D_h = Pitch Diameter = $OD - D_s$; M = Helix Angle; $\sin M = P_n \div \pi D_h$

L = Lead = $P_n \div \cos M$; W = Width = Not less than 2 × Bore, or 6 D_r, or 3.2 P

To the length obtained by this formula, add enough to make a whole number (and for a roller chain, an even number) of pitches. If a roller chain has an odd number of pitches, it will be necessary to use an offset connecting link.

Another formula for obtaining chain length in which D = distance between centers of shafts; R = pitch radius of large sprocket; r = pitch radius of small sprocket: N = number of teeth in large sprocket; n = number of teeth in small sprocket; P = pitch of chain and sprockets; and l = required chain length in inches, is:

$$l = \frac{180° + 2\alpha}{360°}NP + \frac{180° - 2\alpha}{360°}nP + 2D\cos\alpha \qquad \text{where } \sin\alpha = \frac{R - r}{D}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Cutting Standard Sprocket Tooth Form.— The proportions and seating curve data for the standard sprocket tooth form for roller chain are given in Table 11. Either formed or generating types of sprocket cutters may be employed.

Hobs: Only one hob will be required to cut any number of teeth for a given pitch and roller diameter. All hobs should be marked with pitch and roller diameter to be cut. Formulas and data for standard hob design are given in Table 12.

Space Cutters: Five cutters of this type will be required to cut from 7 teeth up for any given roller diameter. The ranges are, respectively, 7–8, 9–11, 12–17, 18–34, and 35 teeth and over. If less than 7 teeth is necessary, special cutters conforming to the required number of teeth should be used.

The regular cutters are based upon an intermediate number of teeth N_a, equal to $2N_1N_2 \div (N_1 + N_2)$ in which N_1 = minimum number of teeth and N_2 = maximum number of teeth for which cutter is intended; but the topping curve radius F (see diagram in Table 13) is designed to produce adequate tooth height on a sprocket of N_2 teeth. The values of N_a for the several cutters are, respectively, 7.47, 9.9, 14.07, 23.54, and 56. Formulas and construction data for space cutter layout are given in Table 13 and recommended cutter sizes are given in Table 14.

Table 13. Standard Space Cutters for Roller-Chain Sprockets



Data for Laying Out Space Cutter				
Range of Teeth	*M*	*T*	*W*	*V*
7–8	0.5848 D_r	0.5459 D_r	1.2790 D_r	0.5694 D_r
9–11	0.6032 D_r	0.5255 D_r	1.3302 D_r	0.4365 D_r
12–17	0.6194 D_r	0.5063 D_r	1.3694 D_r	0.2911 D_r
18–34	0.6343 D_r	0.4875 D_r	1.3947 D_r	0.1220 D_r
35 up	0.6466 D_r	0.4710 D_r	1.4000 D_r	0
Range of Teeth	*F*	Chord *xy*	*yz*	Angle *Yab*
7–8	0.8686 D_r – 0.0015	0.2384 D_r + 0.0003	0.0618 D_r	24°
9–11	0.8554 D_r – 0.0015	0.2800 D_r + 0.0003	0.0853 D_r	18° 10′
12–17	0.8364 D_r – 0.0015	0.3181 D_r + 0.0004	0.1269 D_r	12°
18–34	0.8073 D_r – 0.0015	0.3540 D_r + 0.0004	0.1922 D_r	5°
35 up	0.7857 D_r – 0.0015	0.3850 D_r + 0.0004	0.2235 D_r	0°

E (same for all ranges) = 1.3025 D_r + 0.0015; G (same for all ranges) = 1.4 D_r

See Table 14 for recommended cutter sizes.

Angle *Yab* is equal to 180° ÷ N when the cutter is made for a specific number of teeth. For the design of cutters covering a range of teeth, angle *Yab* was determined by layout to ensure chain roller clearance and to avoid pointed teeth on the larger sprockets of each range. It has values as given below for cutters covering the range of teeth shown. The following formulas are for cutters covering the standard ranges of teeth where N_a equals intermediate values given on page 2460.

Copyright 2004, Industrial Press, Inc., New York, NY

$$W = 1.4D_r \cos Yab \qquad V = 1.4D_r \sin Yab$$

$$yz = D_r\left[1.4\sin\left(17° + \frac{116°}{N_a} - Yab\right) - 0.8\sin\left(18° - \frac{56°}{N_a}\right)\right]$$

$$F = D_r\left[0.8\cos\left(18° - \frac{56°}{N_a}\right) + 1.4\cos\left(17° + \frac{116°}{N_a} - Yab\right) - 1.3025\right] - 0.0015 \text{ in.}$$

For other points, use the value of N_a for N in the standard formulas in Table 11.

Table 14. Recommended Space Cutter Sizes for Roller-Chain Sprockets

		Number of Teeth					
		6	7–8	9–11	12–17	18–34	35 up
Pitch	Roller Dia.	Cutter Diameter (Minimum)					
0.250	0.130	2.75	2.75	2.75	2.75	2.75	2.75
0.375	0.200	2.75	2.75	2.75	2.75	2.75	2.75
0.500	0.312	3.00	3.00	3.12	3.12	3.12	3.12
0.625	0.400	3.12	3.12	3.25	3.25	3.25	3.25
0.725	0.469	3.25	3.25	3.38	3.38	3.38	3.38
1.000	0.625	3.88	4.00	4.12	4.12	4.25	4.25
1.250	0.750	4.25	4.38	4.50	4.50	4.62	4.62
1.500	0.875	4.38	4.50	4.62	4.62	4.75	4.75
1.750	1.000	5.00	5.12	5.25	5.38	5.50	5.50
2.000	1.125	5.38	5.50	5.62	5.75	5.88	5.88
2.250	1.406	5.88	6.00	6.25	6.38	6.50	6.50
2.500	1.563	6.38	6.62	6.75	6.88	7.00	7.12
3.000	1.875	7.50	7.75	7.88	8.00	8.00	8.25
Pitch	Roller Dia.	Cutter Width (Minimum)					
0.250	0.130	0.31	0.31	0.31	0.31	0.28	0.28
0.375	0.200	0.47	0.47	0.47	0.44	0.44	0.41
0.500	0.312	0.75	0.75	0.75	0.75	0.72	0.69
0.625	0.400	0.75	0.75	0.75	0.75	0.72	0.69
0.750	0.469	0.91	0.91	0.91	0.88	0.84	0.81
1.000	0.625	1.50	1.50	1.47	1.47	1.41	1.34
1.250	0.750	1.81	1.81	1.78	1.75	1.69	1.62
1.500	0.875	1.81	1.81	1.78	1.75	1.69	1.62
1.750	1.000	2.09	2.09	2.06	2.03	1.97	1.88
2.000	1.125	2.41	2.41	2.38	2.31	2.25	2.16
2.250	1.406	2.69	2.69	2.66	2.59	2.47	2.41
2.500	1.563	3.00	3.00	2.94	2.91	2.75	2.69
3.000	1.875	3.59	3.59	3.53	3.47	3.34	3.22

Where the same roller diameter is commonly used with chains of two different pitches it is recommended that stock cutters be made wide enough to cut sprockets for both chains.

Marking of Cutters.— All cutters are to be marked, giving pitch, roller diameter and range of teeth to be cut.

Bores for Sprocket Cutters (recommended practice) are approximately as calculated from the formula:

$$\text{Bore} = 0.7\sqrt{(\text{Width of Cutter} + \text{Roller Diameter} + 0.7\ \text{Pitch})}$$

and are equal to 1 inch for ¼- through ¾-inch pitches; 1¼ inches for 1- through 1½-inch for 1¾- through 2¼-inch pitches; 1¾ inches for 2½-inch pitch; and 2 inches for 3-inch pitch.

Minimum Outside Diameters of Space Cutters for 35 teeth and over (recommended practice) are approximately as calculated from the formula:

$$\text{Outside Diameter} = 1.2(\text{Bore} + \text{Roller Diameter} + 0.7\ \text{Pitch}) + 1 \text{ in.}$$

Shaper Cutters: Only one will be required to cut any number of teeth for a given pitch and roller diameter. The manufacturer should be referred to for information concerning the cutter form design to be used.

Sprocket Manufacture.— Cast sprockets have cut teeth, and the rim, hub face, and bore are machined. The smaller sprockets are generally cut from steel bar stock, and are finished all over. Sprockets are often made from forgings or forged bars. The extent of finishing depends on the particular specifications that are applicable. Many sprockets are made by welding a steel hub to a steel plate. This process produces a one-piece sprocket of desired proportions and one that can be heat-treated.

Sprocket Materials.— For large sprockets, cast iron is commonly used, especially in drives with large speed ratios, since the teeth of the larger sprocket are subjected to fewer chain engagements in a given time. For severe service, cast steel or steel plate is preferred.

Copyright 2004, Industrial Press, Inc., New York, NY

The smaller sprockets of a drive are usually made of steel. With this material the body of the sprocket can be heat-treated to produce toughness for shock resistance, and the tooth surfaces can be hardened to resist wear.

Stainless steel or bronze may be used for corrosion resistance, and Formica, nylon or other suitable plastic materials for special applications.

Roller Chain Drive Ratings.— In 1961, under auspices of The American Sprocket Chain Manufacturers Association (now called American Chain Association), a joint research program was begun to study pin-bushing interaction at high speeds and to gain further data on the phenomenon of chain joint galling among other research areas. These studies have shown that a separating film of lubricant is formed in chain joints in a manner similar to that found in journal bearings. These developments appear in ANSI/ASME B29.1M-1993, and are contained in Table 9. The ratings shown in Table 9 are below the galling range.

The horsepower ratings in Table 9 apply to lubricated, single-pitch, single-strand roller chains, both ANSI Standard and Heavy series. To obtain ratings of multiple-strand chains, a multiple-strand factor is applied.

The ratings in Table 9 are based upon: 1) A service factor of 1.; 2) A chain length of approximately 100 pitches.; 3) Use of recommended lubrication methods.; and 4) A drive arrangement where two aligned sprockets are mounted on parallel shafts in a horizontal plane.

Under these conditions, approximately 15,000 hours of service life at full load operation may be expected.

Table 15. Roller Chain Drive Service Factors

Type of Driven Load	Type of Input Power		
	Internal Combustion Engine with Hydraulic Drive	Electric Motor or Turbine	Internal Combustion Engine with Mechanical Drive
Smooth	1.0	1.0	1.2
Moderate Shock	1.2	1.3	1.4
Heavy Shock	1.4	1.5	1.7

Substantial increases in rated speed loads can be utilized, as when a service life of less than 15,000 hours is satisfactory, or when full load operation is encountered only during a portion of the required service life. Chain manufacturers should be consulted for assistance with any special application requirements.

The horsepower ratings shown in Table 9 relate to the speed of the smaller sprocket and drive selections are made on this basis, whether the drive is speed reducing or speed increasing. Drives with more than two sprockets, idlers, composite duty cycles, or other unusual conditions often require special consideration. Where quietness or extra smooth operation are of special importance, small-pitch chain operating over large diameter sprockets will minimize noise and vibration.

When making drive selection, consideration is given to the loads imposed on the chain by the type of input power and the type of equipment to be driven. Service factors are used to compensate for these loads and the *required* horsepower rating of the chain is determined by the following formula:

$$\text{Required hp Table Rating} = \frac{\text{hp to be Transmitted} \times \text{Service Factor}}{\text{Multiple-Strand Factor}}$$

Service Factors: The service factors in Table 15 are for normal chain loading. For unusual or extremely severe operating conditions not shown in this table, it is desirable to use larger service factors.

Multiple-Strand Factors: The horsepower ratings for multiple-strand chains equal single-strand ratings multiplied by these factors: for two strands, a factor of 1.7; for three strands, 2.5; and and for four strands, 3.3.

Copyright 2004, Industrial Press, Inc., New York, NY

Lubrication.— It has been shown that a separating wedge of fluid lubricant is formed in operating chain joints much like that formed in journal bearings. Therefore, fluid lubricant must be applied to ensure an oil supply to the joints and minimize metal-to-metal contact. If supplied in sufficient volume, lubrication also provides effective cooling and impact damping at higher speeds. For this reason, it is important that lubrication recommendations be followed. *The ratings in* Table 9 *apply only to drives lubricated in the manner specified in this table.*

Chain drives should be protected against dirt and moisture and the oil supply kept free of contamination. Periodic oil change is desirable. A good grade of non-detergent petroleum base oil is recommended. Heavy oils and greases are generally too stiff to enter and fill the chain joints. The following lubricant viscosities are recommended: For temperatures of 20° to 40°F, use SAE 20 lubricant; for 40° to 100°, use SAE 30; for 100° to 120°, use SAE 40; and for 120° to 140°, use SAE 50.

There are three basic types of lubrication for roller chain drives. The recommended type shown in Table 9 as Type A, Type B, or Type C is influenced by the chain speed and the amount of power transmitted. These are *minimum* lubrication requirements and the use of a better type (for example, Type C instead of Type B) is acceptable and may be beneficial. Chain life can vary appreciably depending upon the way the drive is lubricated. The better the chain lubrication, the longer the chain life. For this reason, it is important that the lubrication recommendations be followed when using the ratings given in Table 9. The types of lubrication are as follows:

Type A — Manual or Drip Lubrication: In manual lubrication, oil is applied copiously with a brush or spout can at least once every eight hours of operation. Volume and frequency should be sufficient to prevent overheating of the chain or discoloration of the chain joints. In drip lubrication, oil drops from a drip lubricator are directed between the link plate edges. The volume and frequency should be sufficient to prevent discoloration of the lubricant in the chain joints. Precautions must be taken against misdirection of the drops by windage.

Type B — Bath or Disc Lubrication: In bath lubrication, the lower strand of the chain runs through a sump of oil in the drive housing. The oil level should reach the pitch line of the chain at its lowest point while operating. In disc lubrication, the chain operates above the oil level. The disc picks up oil from the sump and deposits it onto the chain, usually by means of a trough. The diameter of the disc should be such as to produce rim speeds of between 600 and 8000 feet per minute.

Type C — Oil Stream Lubrication: The lubricant is usually supplied by a circulating pump capable of supplying each chain drive with a continuous stream of oil. The oil should be applied inside the chain loop evenly across the chain width, and directed at the slack strand.

The chain manufacturer should be consulted when it appears desirable to use a type of lubricant other than that recommended.

Installation and Alignment.— Sprockets should have the tooth form, thickness, profile, and diameters conforming to ASME/ANSI B29.1M. For maximum service life small sprockets operating at moderate to high speeds, or near the rated horsepower, should have hardened teeth. Normally, large sprockets should not exceed 120 teeth.

In general a center distance of 30 to 50 chain pitches is most desirable. The distance between sprocket centers should provide at least a 120 degree chain wrap on the smaller sprocket. Drives may be installed with either adjustable or fixed center distances. Adjustable centers simplify the control of chain slack. Sufficient housing clearance must always be provided for the chain slack to obtain full chain life.

Accurate alignment of shafts and sprocket tooth faces provides uniform distribution of the load across the entire chain width and contributes substantially to optimum drive life.

Copyright 2004, Industrial Press, Inc., New York, NY

Shafting, bearings, and foundations should be suitable to maintain the initial alignment. Periodic maintenance should include an inspection of alignment.

Example of Roller Chain Drive Design Procedure.— The selection of a roller chain and sprockets for a specific design requirement is best accomplished by a systematic step-by-step procedure such as is used in the following example.

Example: Select a roller chain drive to transmit 10 horsepower from a countershaft to the main shaft of a wire drawing machine. The countershaft is $1\frac{15}{16}$-inches diameter and operates at 1000 rpm. The main shaft is also $1\frac{15}{16}$-inches diameter and must operate between 378 and 382 rpm. Shaft centers, once established, are fixed and by initial calculations must be approximately $22\frac{1}{2}$ inches. The load on the main shaft is uneven and presents "peaks," which place it in the heavy shock load category. The input power is supplied by an electric motor. The driving head is fully enclosed and all parts are lubricated from a central system.

Step 1. Service Factor: From Table 15 the service factor for heavy shock load and an electric motor drive is 1.5.

Step 2. Design Horsepower: The horsepower upon which the chain selection is based (design horsepower) is equal to the specified horsepower multiplied by the service factor, $10 \times 1.5 = 15$ hp.

Step 3. Chain Pitch and Small Sprocket Size for Single-Strand Drive: In Table 9 under 1000 rpm, a $\frac{5}{8}$-inch pitch chain with a 24-tooth sprocket or a $\frac{3}{4}$-inch pitch chain with a 15-tooth sprocket are possible choices.

Step 4. Check of Chain Pitch and Sprocket Selection: From Table 10 it is seen that only the 24-tooth sprocket in Step 3 can be bored to fit the $1\frac{15}{16}$-inch diameter main shaft. In Table 9 a $\frac{5}{8}$-pitch chain at a small sprocket speed of 1000 rpm is rated at 15.5 hp for a 24-tooth sprocket.

Step 5. Selection of Large Sprocket: Since the driver is to operate at 1000 rpm and the driven at a minimum of 378 rpm, the speed ratio 1000⁄378 = 2.646. Therefore the large sprocket should have $24 \times 2.646 = 63.5$ (use 63) teeth.

This combination of 24 and 63 teeth will produce a main drive shaft speed of 381 rpm which is within the limitation of 378 to 382 rpm established in the original specification.

Step 6. Computation of Chain Length: Since the 24- and 63-tooth sprockets are to be placed on $22\frac{1}{2}$-inch centers, the chain length is determined from the formula:

$$L = 2C + \frac{N}{2} + \frac{n}{2} + \left(\frac{N-n}{2\pi}\right)^2 \times \frac{1}{C}$$

where L = chain length in pitches; C = shaft center distance in pitches; N = number of teeth in large sprocket; and n = number of teeth in small sprocket.

$$L = 2 \times 36 + \frac{63+24}{2} + \left(\frac{63-24}{6.28}\right)^2 \times \frac{1}{36} = 116.57 \text{ pitches}$$

Step 7. Correction of Center Distance: Since the chain is to couple at a whole number of pitches, 116 pitches will be used and the center distance recomputed based on this figure using the formula on page 2457 where c is the center distance in inches and P is the pitch.

$$c = \frac{P}{8}(2L - N - n + \sqrt{(2L-N-n)^2 - 0.810(N-n)^2})$$

$$c = \frac{5}{64}(2 \times 116 - 63 - 24 + \sqrt{(2 \times 116 - 63 - 24)^2 - 0.810(63-24)^2})$$

$$c = \frac{5}{64}(145 + 140.69) = 22.32 \text{ inches, say } 22\frac{3}{8} \text{ inches}$$

Copyright 2004, Industrial Press, Inc., New York, NY

STANDARDS FOR ELECTRIC MOTORS

Classes of NEMA Standards.— National Electrical Manufacturers Association Standards, available from the Association at 2101 L Street, NW, Washington, DC 20037, are of two classes: 1) *NEMA Standard,* which relates to a product commercially standardized and subject to repetitive manufacture, which standard has been approved by at least 90 per cent of the members of the Subdivision eligible to vote thereon; and 2) *Suggested Standard for Future Design,* which may not have been regularly applied to a commercial product, but which suggests a sound engineering approach to future development and has been approved by at least two-thirds of the members of the Subdivision eligible to vote thereon.

Authorized Engineering Information consists of explanatory data and other engineering information of an informative character not falling within the classification of NEMA Standard or Suggested Standard for Future Design.

Mounting Dimensions and Frame Sizes for Electric Motors.— Dimensions for foot-mounted electric motors as standardized in the United States by the National Electrical Manufacturers Association (NEMA) include the spacing of bolt holes in the feet of the motor, the distance from the bottom of the feet to the center-line of the motor shaft, the size of the conduit, the length and diameter of shaft, and other dimensions likely to be required by designers or manufacturers of motor-driven equipment. The Standard provides dimensions for face-mounted and flange-mounted motors by means of standard motor frame numbers.

Standard dimensions also are given where the motor is to be mounted upon a belt-tightening base or upon rails.

The NEMA standards also prescribe lettering for dimension drawings, mounting and terminal housing locations and dimensions, symbols and terminal connections, and provision for grounding of field wiring. In addition, the standards give recommended knock-out and clearance hole dimensions; tolerances on shaft extension diameters and keyseats; methods of measuring shaft run-out and eccentricity, also face runout of mounting surfaces; and tolerances of face-mounted and flanged-mounted motors.

Design Letters of Polyphase Integral-horsepower Motors.— Designs A, B, C, and D motors are squirrel-cage motors designed to withstand full voltage starting and developing locked-rotor torque and breakdown torque, drawing locked-rotor current, and having a slip as specified below:

Design A: Locked-rotor torque as shown in Table 2, breakdown torque as shown in Table 3, locked-rotor current higher than the values shown in Table 1, and a slip at rated load of less than 5 per cent. Motors with 10 or more poles may have a slightly greater slip.

Table 1. NEMA Standard Locked-rotor Current of 3-phase 60-hertz Integral-horsepower Squirrel-cage Induction Motors Rated at 230 Volts

Horse-power	Locked-rotor Current, Amps.	Design Letters	Horse-power	Locked-rotor Current, Amps.	Design Letters	Horse-power	Locked-rotor Current, Amps.	Design Letters
½	20	B, D	7½	127	B, C, D	50	725	B, C, D
¾	25	B, D	10	162	B, C, D	60	870	B, C, D
1	30	B, D	15	232	B, C, D	75	1085	B, C, D
1½	40	B, D	20	290	B, C, D	100	1450	B, C, D
2	50	B, D	25	365	B, C, D	125	1815	B, C, D
3	64	B, C, D	30	435	B, C, D	150	2170	B, C, D
5	92	B, C, D	40	580	B, C, D	200	2900	B, C

Note: The locked-rotor current of a motor is the steady-state current taken from the line with the rotor locked and with rated voltage and frequency applied to the motor.

For motors designed for voltages other than 230 volts, the locked-rotor current is inversely proportional to the voltages. For motors larger than 200 hp, see NEMA Standard MG 1-12.34.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. NEMA Standard Locked-rotor Torque of Single-speed Polyphase 60- and 50-hertz Squirrel-cage Integral-horsepower Motors with Continuous Ratings

Hp	Designs A and B							Design C		
	Synchronous Speed, rpm									
	60 hertz	3600	1800	1200	900	720	600	514	1800	1200	900
	50 hertz	3000	1500	1000	750	…	…	…	1500	1000	750
	Percent of Full-load Torque[a]										
½		…	…	…	140	140	115	110	…	…	…
¾		…	…	175	135	135	115	110	…	…	…
1		…	275	170	135	135	115	110	…	…	…
1½		175	250	165	130	130	115	110	…	…	…
2		170	235	160	130	125	115	110	…	…	…
3		160	215	155	130	125	115	110	…	250	225
5		150	185	150	130	125	115	110	250	250	225
7½		140	175	150	125	120	115	110	250	225	200
10		135	165	150	125	120	115	110	250	225	200
15		130	160	140	125	120	115	110	225	200	200
20		130	150	135	125	120	115	110	200 for all sizes above 15 hp.		
25		130	150	135	125	120	115	110			
30		130	150	135	125	120	115	110			
40		125	140	135	125	120	115	110			
50		120	140	135	125	120	115	110			
60		120	140	135	125	120	115	110			
75		105	140	135	125	120	115	110	For Design D motors, see footnote.		
100		105	125	125	125	120	115	110			
125		100	110	125	120	115	115	110			
150		100	110	120	120	115	115	…			
200		100	100	120	120	115	…	…			

[a] These values represent the upper limit of application for these motors.

Note: The locked-rotor torque of a motor is the minimum torque which it will develop at rest for all angular positions of the rotor, with rated voltage applied at rated frequency.

The locked-rotor torque of Design D, 60- and 50-hertz 4-, 6-, and 8-pole single-speed, polyphase squirrel-cage motors rated 150 hp and smaller, with rated voltage and frequency applied is 275 per cent of full-load torque, which represents the upper limit of application for these motors.

For motors larger than 200 hp, see NEMA Standard MG 1-12.37.

Table 3. NEMA Standard Breakdown Torque of Single-speed Polyphase Squirrel-cage, Integral-horsepower Motors with Continuous Ratings

Horsepower	Synchronous Speed, rpm							
	60 hertz	3600	1800	1200	900	720	600	514
	50 hertz	3000	1500	1000	750	…	…	…
	Per Cent of Full Load Torque							
	Designs A and B[a]							
½		…	…	…	225	200	200	200
¾		…	…	275	220	200	200	200
1		…	300	265	215	200	200	200
1½		250	280	250	210	200	200	200
2		240	270	240	210	200	200	200
3		230	250	230	205	200	200	200
5		215	225	215	205	200	200	200
7½		200	215	205	200	200	200	200
10–125, incl.		200	200	200	200	200	200	200
150		200	200	200	200	200	200	…
200		200	200	200	200	200	…	…
	Design C							
3		…	…	225	200	…	…	…
5		…	200	200	200	…	…	…
7½–200, incl.		…	190	190	190	…	…	…

[a] Design A values are in excess of those shown.

These values represent the upper limit of the range of application for these motors. For above 200 hp, see NEMA Standard MG1-12.38.

Copyright 2004, Industrial Press, Inc., New York, NY

Design B: Locked-rotor torque as shown in Table 2, breakdown torque as shown in Table 3, locked-rotor current not exceeding that in Table 1, and a slip at rated load of less than 5 per cent. Motors with 10 or more poles may have a slightly greater slip.

Design C: Locked-rotor torque for special high-torque applications up to values shown in Table 2, breakdown torque up to values shown in Table 3, locked-rotor current not exceeding values shown in Table 1 and a slip at rated load of less than 5 per cent.

Design D: Locked-rotor torque as indicated in Table 2, locked-rotor current not greater than that shown in Table 1 and a slip at rated load of 5 per cent or more.

Torque and Current Definitions.— The definitions which follow have been adopted as standard by the National Electrical Manufacturers Association.

Locked-Rotor or Static Torque: The locked-rotor torque of a motor is the minimum torque which it will develop at rest for all angular positions of the rotor, with rated voltage applied at rated frequency.

Breakdown Torque: The breakdown torque of a motor is the maximum torque which the motor will develop, with rated voltage applied at rated frequency, without an abrupt drop in speed (see Table 4).

Full-Load Torque: The full-load torque of a motor is the torque necessary to produce its rated horsepower at full load speed. In pounds at 1-foot radius, it is equal to the horsepower times 5252 divided by the full-load speed.

Pull-Out Torque: The pull-out torque of a synchronous motor is the maximum sustained torque which the motor will develop at synchronous speed with rated voltage applied at rated frequency and with normal excitation.

Pull-In Torque: The pull-in torque of a synchronous motor is the maximum constant torque under which the motor will pull its connected inertia load into synchronism at rated voltage and frequency, when its field excitation is applied.

Pull-Up Torque: The pull-up torque of an alternating current motor is the minimum torque developed by the motor during the period of acceleration from rest to the speed at which breakdown torque occurs. For motors which do not have a definite breakdown torque, the pull-up torque is the minimum torque developed up to rated speed.

Locked Rotor Current: The locked rotor current of a motor is the steady-state current taken from the line with the rotor locked and with rated voltage (and rated frequency in the case of alternating-current motors) applied to the motor.

Table 4. NEMA Standard Breakdown Torque of Polyphase Wound-rotor Motors with Continuous Ratings — 60- and 50-hertz

Horsepower	Speed, rpm			Horsepower	Speed, rpm		
	1800	1200	900		1800	1200	900
	Per cent of Full-load Torque				Per cent of Full-load Torque		
1	…	…	250	7½	275	250	225
1½	…	…	250	10	275	250	225
2	275	275	250	15	250	225	225
3	275	275	250	20–200, incl.	225	225	225
5	275	275	250	…	…	…	…
These values represent the upper limit of the range of application for these motors.							

Standard Direction of Motor Rotation.— The standard direction of rotation for all non-reversing direct-current motors, all alternating-current single-phase motors, all synchronous motors, and all universal motors, is *counterclockwise* when facing that end of the motor opposite the drive.

This rule does not apply to two- and three-phase induction motors, as in most applications the phase sequence of the power lines is rarely known.

Copyright 2004, Industrial Press, Inc., New York, NY

Motor Types According to Variability of Speed.— Five types of motors classified according to variability of speed are:

Constant-speed Motors: In this type of motor the normal operating speed is constant or practically constant; for example, a synchronous motor, an induction motor with small slip, or a direct-current shunt-wound motor.

Varying-speed Motor: In this type of motor, the speed varies with the load, ordinarily decreasing when the load increases; such as a series-wound or repulsion motor.

Adjustable-speed Motor: In this type of motor, the speed can be varied gradually over a considerable range, but when once adjusted remains practically unaffected by the load; such as a direct-current shunt-wound motor with field resistance control designed for a considerable range of speed adjustment.

The base speed of an adjustable-speed motor is the lowest rated speed obtained at rated load and rated voltage at the temperature rise specified in the rating.

Adjustable Varying-speed Motor: This type of motor is one in which the speed can be adjusted gradually, but when once adjusted for a given load will vary in considerable degree with the change in load; such as a direct-current compound-wound motor adjusted by field control or a wound-rotor induction motor with rheostatic speed control.

Multispeed Motor: This type of motor is one which can be operated at any one of two or more definite speeds, each being practically independent of the load; such as a direct-current motor with two armature windings or an induction motor with windings capable of various pole groupings. In the case of multispeed permanent-split capacitor and shaded pole motors, the speeds are dependent upon the load.

Pull-up Torque.— NEMA Standard pull up torques for single-speed, polyphase, squirrel-cage integral-horsepower motors, Designs A and B, with continuous ratings and with rated voltage and frequency applied are as follows: When the locked-rotor torque given in Table 2 is 110 per cent or less, the pull-up torque is 90 per cent of the locked-rotor torque; when the locked-rotor torque is greater than 110 per cent but less than 145 per cent, the pull-up torque is 100 per cent of full-load torque; and when the locked-rotor torque is 145 per cent or more, the pull-up torque is 70 per cent of the locked-rotor torque.

For Design C motors, with rated voltage and frequency applied, the pull-up torque is not less than 70 per cent of the locked-rotor torque as given in Table 2.

Types and Characteristics of Electric Motors

Types of Direct-Current Motors.— Direct-current motors may be grouped into three general classes: series-wound; shunt-wound; and compound-wound.

In the *series-wound motor* the field windings, which are fixed in the stator frame, and the armature windings, which are placed around the rotor, are connected in series so that all current passing through the armature also passes through the field. In the *shunt-wound motor,* both armature and field are connected across the main power supply so that the armature and field currents are separate. In the *compound-wound motor,* both series and shunt field windings are provided and these may be connected so that the currents in both are flowing in the same direction, called *cumulative compounding,* or so that the currents in each are flowing in opposite directions, called *differential compounding*.

Characteristics of Series-wound Direct-Current Motors.— In the series-wound motor, any increase in load results in more current passing through the armature and the field windings. As the field is strengthened by this increased current, the motor speed decreases. Conversely, as the load is decreased the field is weakened and the speed increases and at very light loads may become excessive. For this reason, series-wound direct-current motors are usually directly connected or geared to the load to prevent "run-away." (A series-wound motor, designated as series-shunt wound, is sometimes provided with a light shunt field winding to prevent dangerously high speeds at light loads.) The increase in armature current with increasing load produces increased torque, so that the

Copyright 2004, Industrial Press, Inc., New York, NY

series-wound motor is particularly suited to heavy starting duty and where severe overloads may be expected. Its speed may be adjusted by means of a variable resistance placed in series with the motor, but due to variation with load, the speed cannot be held at any constant value. This variation of speed with load becomes greater as the speed is reduced. Series-wound motors are used where the load is practically constant and can easily be controlled by hand. They are usually limited to traction and lifting service.

Shunt-wound Direct-Current Motors.— In the shunt-wound motor, the strength of the field is not affected appreciably by change in the load, so that a fairly constant speed (about 10 to 12 per cent drop from no load to full load speed) is obtainable. This type of motor may be used for the operation of machines requiring an approximately constant speed and imposing low starting torque and light overload on the motor.

The shunt-wound motor becomes an adjustable-speed motor by means of field control or by armature control. If a variable resistance is placed in the field circuit, the amount of current in the field windings and hence the speed of rotation can be controlled. As the speed increases, the torque decreases proportionately, resulting in nearly constant horsepower. A speed range of 6 to 1 is possible using field control, but 4 to 1 is more common. Speed regulation is somewhat greater than in the constant-speed shunt-wound motors, ranging from about 15 to 22 per cent. If a variable resistance is placed in the armature circuit, the voltage applied to the armature can be reduced and hence the speed of rotation can be reduced over a range of about 2 to 1. With armature control, speed regulation becomes poorer as speed is decreased, and is about 100 per cent for a 2 to 1 speed range. Since the current through the field remains unchanged, the torque remains constant.

Machine Tool Applications: The adjustable-speed shunt-wound motors are useful on larger machines of the boring mill, lathe, and planer type and are particularly adapted to spindle drives because constant horsepower characteristics permit heavy cuts at low speed and light or finishing cuts at high speed. They have long been used for planer drives because they can provide an adjustable low speed for the cutting stroke and a high speed for the return stroke. Their application has been limited, however, to plants in which direct-current power is available.

Adjustable-voltage Shunt-wound Motor Drive.— More extensive use of the shunt-wound motor has been made possible by a combination drive that includes a means of converting alternating current to direct current. This conversion may be effected by a self-contained unit consisting of a separately excited direct-current generator driven by a constant speed alternating-current motor connected to the regular alternating-current line, or by an electronic rectifier with suitable controls connected to the regular alternating-current supply lines. The latter has the advantage of causing no vibration when mounted directly on the machine tool, an important factor in certain types of grinders.

In this type of adjustable-speed, shunt-wound motor drive, speed control is effected by varying the voltage applied to the armature while supplying constant voltage to the field. In addition to providing for the adjustment of the voltage supplied by the conversion unit to the armature of the shunt-wound motor, the amount of current passing through the motor field may also be controlled. In fact, a single control may be provided to vary the motor speed from minimum to base speed (speed of the motor at full load with rated voltage on armature and field) by varying the voltage applied to the armature and from base speed to maximum speed by varying the current flowing through the field. When so controlled, the motor operates at constant torque up to base speed and at constant horsepower above base speed.

Speed Range: Speed ranges of at least 20 to 1 below base speed and 4 or 5 to 1 above base speed (a total range of 100 to 1, or more) are obtainable as compared with about 2 to 1 below normal speed and 3 or 4 to 1 above normal speed for the conventional type of control. Speed regulation may be as great as 25 per cent at high speeds. Special electronic controls, when used with this type shunt motor drive, make possible maintenance of motor

Copyright 2004, Industrial Press, Inc., New York, NY

speeds with as little variation as ½ to 1 per cent of full load speed from full load to no load over a line voltage variation of ± 10 per cent and over any normal variation in motor temperature and ambient temperature.

Applications: These direct-current, adjustable-voltage drives, as they are sometimes called, have been applied successfully to such machine tools as planers, milling machines, boring mills and lathes, as well as to other industrial machines where wide, stepless speed control, uniform speed under all operating conditions, constant torque acceleration and adaptability to automatic operation are required.

Compound-wound Motors.— In the compound-wound motor, the speed variation due to load changes is much less than in the series-wound motor, but greater than in the shunt-wound motor (ranging up to 25 per cent from full load to no load). It has a greater starting torque than the shunt-wound motor, is able to withstand heavier overloads, but has a narrower adjustable speed range. Standard motors of this type have a cumulative-compound winding, the differential-compound winding being limited to special applications. They are used where the starting load is very heavy or where the load changes suddenly and violently as with reciprocating pumps, printing presses and punch presses.

Types of Polyphase Alternating-Current Motors.— The most widely used polyphase motors are of the induction type. The *"squirrel cage" induction motor* consists of a wound stator which is connected to an external source of alternating-current power and a laminated steel core rotor with a number of heavy aluminum or copper conductors set into the core around its periphery and parallel to its axis. These conductors are connected together at each end of the rotor by a heavy ring, which provides closed paths for the currents induced in the rotor to circulate. The rotor bars form, in effect, a "squirrel cage" from which the motor takes its name.

Wound-rotor type of *Induction motor:* This type has in addition to a squirrel cage, a series of coils set into the rotor which are connected through slip-rings to external variable resistors. By varying the resistance of the wound-rotor circuits, the amount of current flowing in these circuits and hence the speed of the motor can be controlled. Since the rotor of an induction motor is not connected to the power supply, the motor is said to operate by transfer action and is analogous to a transformer with a short-circuited secondary that is free to rotate. Induction motors are built with a wide range of speed and torque characteristics which are discussed under "Operating Characteristics of Squirrel-cage Induction Motors."

Synchronous Motor: The other type of polyphase alternating-current motor used industrially is the *synchronous motor*. In contrast to the induction motor, the rotor of the synchronous motor is connected to a direct-current supply which provides a field that rotates in step with the alternating-current field in the stator. After having been brought up to synchronous speed, which is governed by the frequency of the power supply and the number of poles in the rotor, the synchronous motor operates at this constant speed throughout its entire load range.

Operating Characteristics of Squirrel-cage Induction Motors.— In general, squirrel-cage induction motors are simple in design and construction and offer rugged service. They are essentially constant-speed motors, their speed changing very little with load and not being subject to adjustment. They are used for a wide range of industrial applications calling for integral horsepower ratings. According to the NEMA (National Electrical Manufacturers Association) Standards, there are four classes of squirrel-cage induction motors designated respectively as *A*, *B*, *C*, and *D*.

Design A motors are not commonly used since Design *B* has similar characteristics with the advantage of lower starting current.

Design B: motors may be designated as a general purpose type suitable for the majority of polyphase alternating-current applications such as blowers, compressors, drill presses, grinders, hammer mills, lathes, planers, polishers, saws, screw machines, shakers, stokers,

Copyright 2004, Industrial Press, Inc., New York, NY

etc. The starting torque at 1800 R.P.M. is 250 to 275 per cent of full load torque for 3 H.P. and below; for 5 H.P. to 75 H. P. ratings the starting torque ranges from 185 to 150 per cent of full load torque. They have low starting current requirements, usually no more than 5 to 6 times full load current and can be started at full voltage. Their slip (difference between synchronous speed and actual speed at rated load) is relatively low.

Design C: motors have high starting torque (up to 250 per cent of full load torque) but low starting current. They can be started at full voltage. Slip at rated load is relatively low. They are used for compressors requiring a loaded start, heavy conveyors, reciprocating pumps and other applications requiring high starting torque.

Design D: motors have high slip at rated load, that is, the motor speed drops off appreciably as the load increases, permitting use of the stored energy of a flywheel. They provide heavy starting torque, up to 275 per cent of full load torque, are quiet in operation and have relatively low starting current. Applications are for impact, shock and other high peak loads or flywheel drives such as trains, elevators, hoists, punch and drawing presses, shears, etc.

Design F: motors are no longer standard. They had low starting torque, about 125 per cent of full-load torque, and low starting current. They were used to drive machines which required infrequent starting at no load or at very light load.

Multiple-Speed Induction Motors.— This type has a number of windings in the stator so arranged and connected that the number of effective poles and hence the speed can be changed. These motors are for the same types of starting conditions as the conventional squirrel-cage induction motors and are available in designs that provide constant horsepower at all rated speeds and in designs that provide constant torque at all rated speeds.

Typical speed combinations obtainable in these motors are 600, 900, 1200 and 1800 R.P.M.; 450, 600, 900 and 1200 R.P.M.; and 600, 720, 900 and 1200 R.P.M.

Where a gradual change in speed is called for, a wound rotor may be provided in addition to the multiple stator windings.

Wound-Rotor Induction Motors.— These motors are designed for applications where extremely low starting current with high starting torque are called for, such as in blowers, conveyors, compressors, fans and pumps. They may be employed for adjustable-varying speed service where the speed range does not extend below 50 per cent of synchronous speed, as for steel plate-forming rolls, printing presses, cranes, blowers, stokers, lathes and milling machines of certain types. The speed regulation of a wound rotor induction motor ranges from 5 to 10 per cent at maximum speed and from 18 to 30 per cent at low speed. They are also employed for reversing service as in cranes, gates, hoists and elevators.

High-Frequency Induction Motors.— This type is used in conjunction with frequency changers when very high speeds are desired, as on grinders, drills, routers, portable tools or woodworking machinery. These motors have an advantage over the series-wound or universal type of high speed motor in that they operate at a relatively constant speed over the entire load range. A motor-generator set, a two-unit frequency converter or a single unit inductor frequency converter may be used to supply three-phase power at the frequency required. The single unit frequency converter may be obtained for delivering any one of a number of frequencies ranging from 360 to 2160 cycles and it is self-driven and self-excited from the general polyphase power supply.

Synchronous Motors.— These are widely used in electric timing devices; to drive machines that must operate in synchronism; and also to operate compressors, rolling mills, crushers which are started without load, paper mill screens, shredders, vacuum pumps and motor-generator sets. Synchronous motors have an inherently high power factor and are often employed to make corrections for the low power factor of other types of motors on the same system.

Copyright 2004, Industrial Press, Inc., New York, NY

Types of Single-Phase Alternating-Current Motors.— Most of the single-phase alternating-current motors are basically induction motors distinguished by different arrangements for starting. (A single-phase induction motor with only a squirrel-cage rotor has no starting torque.) In the *capacitor-start* single-phase motor, an auxiliary winding in the stator is connected in series with a capacitor and a centrifugal switch. During the starting and accelerating period the motor operates as a two-phase induction motor. At about two-thirds full-load speed, the auxiliary circuit is disconnected by the switch and the motor then runs as a single-phase induction motor. In the *capacitor-start, capacitor-run* motor, the auxiliary circuit is arranged to provide high effective capacity for high starting torque and to remain connected to the line but with reduced capacity during the running period. In the *single-value capacitor* or *capacitor split-phase* motor, a relatively small continuously-rated capacitor is permanently connected in one of the two stator windings and the motor both starts and runs like a two-phase motor.

In the *repulsion-start* single-phase motor, a drum-wound rotor circuit is connected to a commutator with a pair of short-circuited brushes set so that the magnetic axis of the rotor winding is inclined to the magnetic axis of the stator winding. The current flowing in this rotor circuit reacts with the field to produce starting and accelerating torques. At about two-thirds full load speed the brushes are lifted, the commutator is short circuited and the motor runs as a single-phase squirrel-cage motor. The *repulsion* motor employs a repulsion winding on the rotor for both starting and running. The *repulsion-induction* motor has an outer winding on the rotor acting as a repulsion winding and an inner squirrel-cage winding. As the motor comes up to speed, the induced rotor current partially shifts from the repulsion winding to the squirrel-cage winding and the motor runs partly as an induction motor.

In the *split-phase* motor, an auxiliary winding in the stator is used for starting with either a resistance connected in series with the auxiliary winding (*resistance-start*) or a reactor in series with the main winding (*reactor-start*).

The *series-wound* single-phase motor has a rotor winding in series with the stator winding as in the series-wound direct-current motor. Since this motor may also be operated on direct current, it is called a *universal* motor.

Characteristics of Single-Phase Alternating-Current Motors.— Single-phase motors are used in sizes up to about 7½ horsepower for heavy starting duty chiefly in home and commercial appliances for which polyphase power is not available. The *capacitor-start* motor is available in normal starting torque designs for such applications as centrifugal pumps, fans, and blowers and in high-starting torque designs for reciprocating compressors, pumps, loaded conveyors, or belts. The *capacitor-start, capacitor-run* motor is exceptionally quiet in operation when loaded to at least 50 per cent of capacity. It is available in low-torque designs for fans and centrifugal pumps and in high-torque designs for applications similar to those of the capacitor-start motor.

The *capacitor split-phase* motor requires the least maintenance of all single-phase motors, but has very low starting torque. Its high maximum torque makes it potentially useful in floor sanders or in grinders where momentary overloads due to excessive cutting pressure are experienced. It is also used for slow-speed direct connected fans.

The *repulsion-start, induction-run* motor has higher starting torque than the capacitor motors, although for the same current, the capacitor motors have equivalent pull-up and maximum torque. Electrical and mechanical noise and the extra maintenance sometimes required are disadvantages. These motors are used for compressors, conveyors and stokers starting under full load. The *repulsion-induction* motor has relatively high starting torque and low starting current. It also has a smooth speed-torque curve with no break and a greater ability to withstand long accelerating periods than capacitor type motors. It is particularly suitable for severe starting and accelerating duty and for high inertia loads such as laundry extractors. Brush noise is, however, continuous.

Copyright 2004, Industrial Press, Inc., New York, NY

The *repulsion* motor has no limiting synchronous speed and the speed changes with the load. At certain loads, slight changes in load cause wide changes in speed. A brush shifting arrangement may be provided to adjust the speed which may have a range of 4 to 1 if full rated constant torque is applied but a decreasing range as the torque falls below this value. This type of motor may be reversed by shifting the brushes beyond the neutral point. These motors are suitable for machines requiring constant-torque and adjustable speed.

The *split-phase* and *universal* motors are limited to about ⅓ H.P. ratings and are used chiefly for small appliance and office machine applications.

Motors with Built-in Speed Reducers.— Electric motors having built-in speed-changing units are compact and the design of these motorized speed reducers tends to improve the appearance of the machines which they drive. There are several types of these speed reducers; they may be classified according to whether they are equipped with worm gearing, a regular gear train with parallel shafts, or planetary gearing.

The claims made for the worm gearing type of reduction unit are that the drive is quiet in operation and well adapted for use where the slow-speed shaft must be at right angles to the motor shaft and where a high speed ratio is essential.

For very low speeds, the double reduction worm gearing units are suitable. In these units two sets of worm gearing form the gear train, and both the slow-speed shaft and the armature shaft are parallel. The intermediate worm gear shaft can be built to extend from the housing, if required, so as to make two countershaft speeds available on the same unit.

In the parallel-shaft type of speed reducer, the slow-speed shaft is parallel with the armature shaft. The slow-speed shaft is rotated by a pinion on the armature shaft, this pinion meshing with a larger gear on the slow-speed shaft.

Geared motors having built-in speed-changing units are available with constant-mesh change gears for varying the speed ratio.

Planetary gearing permits a large speed reduction with few parts; hence, it is well adapted for geared-head motor units where economy and compactness are essential. The slow-speed shaft is in line with the armature shaft.

Factors Governing Motor Selection

Speed, Horsepower, Torque and Inertia Requirements.— Where more than one speed or a range of speeds are called for, one of the following types of motors may be selected, depending upon other requirements: For direct-current, the standard shunt-wound motor with field control has a 2 to 1 range in some designs; the adjustable speed motor may have a range of from 3 to 1 up to 6 to 1; the shunt motor with adjustable voltage supply has a range up to 20 to 1 or more below base speed and 4 or 5 to 1 above base speed, making a total range of up to 100 to 1 or more. For polyphase alternating current, multi-speed squirrel-cage induction motors have 2, 3 or 4 fixed speeds; the wound-rotor motor has a 2 to 1 range. The two-speed wound-rotor motor has a 4 to 1 range. The brush-shifting shunt motor has a 4 to 1 range. The brush-shifting series motor has a 3 to 1 range; and the squirrel-cage motor with a variable-frequency supply has a very wide range. For single-phase alternating current, the brush-shifting repulsion motor has a 2½ to 1 range; the capacitor motor with tapped winding has a 2 to 1 range and the multi-speed capacitor motor has 2 or 3 fixed speeds. Speed regulation (variation in speed from no load to full load) is greatest with motors having series field windings and entirely absent with synchronous motors.

Horsepower: Where the load to be carried by the motor is not constant but follows a definite cycle, a horsepower-time curve enables the peak horsepower to be determined as well as the root-mean-square-average horsepower, which indicates the proper motor rating from a heating standpoint. Where the load is maintained at a constant value for a period of from 15 minutes to 2 hours depending on the size, the horsepower rating required will usually not be less than this constant value. When selecting the size of an induction motor, it should be kept in mind that this type of motor operates at maximum efficiency when it is

Copyright 2004, Industrial Press, Inc., New York, NY

loaded to full capacity. Where operation is to be at several speeds, the horsepower requirement for each speed should be considered.

Torque: Starting torque requirements may vary from 10 per cent of full load to 250 per cent of full load torque depending upon the type of machine being driven. Starting torque may vary for a given machine because of frequency of start, temperature, type and amount of lubricant, etc., and such variables should be taken into account. The motor torque supplied to the machine must be well above that required by the driven machine at all points up to full speed. The greater the excess torque, the more rapid the acceleration. The approximate time required for acceleration from rest to full speed is given by the formula:

$$\text{Time} = \frac{N \times WR^2}{T_a \times 308} \text{ seconds}$$

where N = Full load speed in R.P.M.

T_a = Torque = average foot-pounds available for acceleration.

WR^2 = Inertia of rotating part in pounds feet squared (W = weight and R = radius of gyration of rotating part).

308 = Combined constant converting minutes into seconds, weight into mass and radius into circumference.

If the time required for acceleration is greater than 20 seconds, special motors or starters may be required to avoid overheating.

The running torque T_r is found by the formula:

$$T_r = \frac{5250 \times \text{HP}}{N} \text{ foot pounds}$$

where *H.P.* = Horsepower being supplied to the driven machine

N = Running speed in R.P.M.

5250 = Combined constant converting horsepower to foot-pounds per minute and work per revolution into torque.

The peak horsepower determines the maximum torque required by the driven machine and the motor must have a maximum running torque in excess of this value.

Inertia: The inertia or flywheel effect of the rotating parts of a driven machine will, if large, appreciably affect the accelerating time and, hence, the amount of heating in the motor. If synchronous motors are used, the inertia (WR^2) of both the motor rotor and the rotating parts of the machine must be known since the pull-in torque (torque required to bring the driven machine up to synchronous speed) varies approximately as the square root of the total inertia of motor and load.

Space Limitations in Motor Selection.— If the motor is to become an integral part of the machine which it drives and space is at a premium, a partial motor may be called for. A complete motor is one made up of a stator, a rotor, a shaft, and two end shields with bearings. A *partial motor* is without one or more of these elements. One common type is furnished without drive-end end shield and bearing and is directly connected to the end or side of the machine which it drives, such as the headstock of a lathe. A so-called *shaftless type of motor* is supplied without shaft, end shields or bearings and is intended for built-in application in such units as multiple drilling machines, precision grinders, deep well pumps, compressors and hoists where the rotor is actually made a part of the driven machine. Where a partial motor is used, however, proper ventilation, mounting, alignment and bearings must be arranged for by the designer of the machine to which it is applied.

Sometimes it is possible to use a motor having a smaller frame size and wound with Class *B* insulation, permitting it to be subjected to a higher temperature rise than the larger-frame Class *A* insulated motor having the same horsepower rating.

Copyright 2004, Industrial Press, Inc., New York, NY

Temperatures.— The applicability of a given motor is limited not only by its load starting and carrying ability, but also by the temperature which it reaches under load. Motors are given temperature ratings which are based upon the type of insulation (Class A or Class B are the most common) used in their construction and their type of frame (open, semienclosed, or enclosed).

Insulating Materials: Class A materials are: cotton, silk, paper, and similar organic materials when either impregnated or immersed in a liquid dielectric; molded and laminated materials with cellulose filler, phenolic resins, and other resins of similar properties; films and sheets of cellulose acetate and other cellulose derivatives of similar properties; and varnishes (enamel) as applied to conductors.

Class B insulating materials are: materials or combinations of materials such as mica, glass fiber, asbestos, etc., with suitable bonding substances. Other materials shown capable of operation at Class B temperatures may be included.

Ambient Temperature and Allowable Temperature Rise: Normal ambient temperature is taken to be 40°C (104°F). For open general-purpose motors with Class A insulation, the normal temperature rise on which the performance guarantees are based is 40°C (104°F).

Motors with Class A insulation having protected, semiprotected, drip-proof, or splash-proof, or drip-proof protected enclosures have a 50°C (122°F) rise rating.

Motors with Class A insulation and having totally enclosed, fan-cooled, explosion-proof, waterproof, dust-tight, submersible, or dust-explosion-proof enclosures have a 55°C (131°F) rise rating.

Motors with Class B insulation are permissible for total temperatures up to 110 degrees C (230°F) for open motors and 115°C (239°F) for enclosed motors.

Motors Exposed to Injurious Conditions.— Where motors are to be used in locations imposing unusual operating conditions, the manufacturer should be consulted, especially where any of the following conditions apply: exposure to chemical fumes; operation in damp places; operation at speeds in excess of specified overspeed; exposure to combustible or explosive dust; exposure to gritty or conducting dust; exposure to lint; exposure to steam; operation in poorly ventilated rooms; operation in pits, or where entirely enclosed in boxes; exposure to inflammable or explosive gases; exposure to temperatures below 10°C (50°F); exposure to oil vapor; exposure to salt air; exposure to abnormal shock or vibration from external sources; where the departure from rated voltage is excessive; and or where the alternating-current supply voltage is unbalanced.

Improved insulating materials and processes and greater mechanical protection against falling materials and liquids make it possible to use general-purpose motors in many locations where special-purpose motors were previously considered necessary. *Splash-proof motors* having well-protected ventilated openings and specially treated windings are used where they are to be subjected to falling and splashing water or are to be washed down as with a hose. Where climatic conditions are not severe, this type of motor is also successfully used in unprotected outdoor installations.

If the surrounding atmosphere carries abnormal quantities of metallic, abrasive, or non-explosive dust or acid or alkali fumes, a *totally enclosed fan-cooled motor* may be called for. In this type, the motor proper is completely enclosed but air is blown through an outer shell that completely or partially surrounds the inner case. If the dust in the atmosphere tends to pack or solidify and close the air passages of open splash-proof or totally enclosed fan-cooled motors, *totally enclosed (nonventilated) motors* are used. This type, which is limited to low horsepower ratings, is also used for outdoor service in mild or severe climates.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Characteristics and Applications of D.C. Motors, 1–300 hp

Type	Starting Duty	Maximum Momentary Running Torque	Speed Regulation	Speed Control[a]	Applications
Shunt-wound, constant-speed	Medium starting torque. Varies with voltage supplied to armature, and is limited by starting resistor to 125 to 200% full-load torque	125 to 200%. Limited by commutation	8 to 12%	Basic speed to 200% basic speed by field control	Drives where starting requirements are not severe. Use constant-speed or adjustable-speed, depending on speed required. Centrifugal pumps, fans, blowers, conveyors, elevators, wood- and metalworking machines
Shunt-wound, adjustable speed			10 to 20%, increases with weak fields	Basic speed to 60% basic speed (lower for some ratings) by field control	
Shunt-wound, adjustable voltage control			Up to 25%. Less than 5% obtainable with special rotating regulator	Basic speed to 2% basic speed and basic speed to 200% basic speed	Drives where wide, stepless speed control, uniform speed, constant-torque acceleration and adaptability to automatic operation are required. Planers, milling machines, boring machines, lathes, etc.
Compound wound, constant-speed	Heavy starting torque, Limited by starting resistor to 130 to 260% of full-load torque	130 to 260%. Limited by commutation	Standard compounding 25%. Depends on amount of series winding	Basic speed to 125% basic speed by field control	Drives requiring high starting torque and fairly constant speed. Pulsating loads. Shears, bending rolls, pumps, conveyors, crushers, etc.
Series-wound, varying-speed	Very heavy starting torque. Limited to 300 to 350% full-load torque	300 to 350%. Limited by commutation	Very high. Infinite no-load speed	From zero to maximum speed, depending on control and load	Drives where very high starting torque is required and speed can be regulated. Cranes, hoists, gates, bridges, car dumpers, etc.

[a] Minimum speed below basic speed by armature control limited by heating.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Characteristics and Applications of Polyphase AC Motors

Polyphase Type	Ratings hp	Speed Regulation	Speed Control	Starting Torque	Breakdown Torque	Applications
General-purpose squirrel cage, normal stg current, normal stg torque. Design B	0.5 to 200	Less than 5%	None, except multi-speed types, designed for two to four fixed speeds	100 to 250% of full-load	200 to 300% of full-load	Constant-speed service where starting torque is not excessive. Fans, blowers, rotary compressors, centrifugal pumps, woodworking machines, machine tools, line shafts
Full-voltage starting, high stg torque, normal stg current, squirrel-cage, Design C	3 to 150	Less than 5%	None except multi-speed types, designed for two to four fixed speeds	200 to 250% of full-load	190 to 225% of full-load	Constant-speed service where fairly high starting torque is required at infrequent intervals with starting current of about 500% full-load. Reciprocating pumps and compressors, conveyors, crushers, pulverizers, agitators, etc.
Full-voltage starting, high stg-torque, high-slip squirrel cage, Design D	0.5 to 150	Drops about 7 to 12% from no load to full load	None, except multi-speed types, designed for two to four fixed speeds	275% of full-load depending on speed and rotor resistance	275% of full-load Will usually not stall until loaded to its maximum torque, which occurs at standstill	Constant-speed service and high-starting torque if starting not too frequent, and for taking high-peak loads with or without flywheels. Punch presses, die stamping, shears, bulldozers, bailers, hoists, cranes, elevators, etc.
Wound-rotor, external-resistance starting	0.5 to several thousand	With rotor rings short-circuited drops about 3% for large to 5% for small sizes	Speed can be reduced to 50% of normal by rotor resistance. Speed varies inversely as the load	Up to 300% depending on external resistance in rotor circuit and how distributed	200% when rotor slip rings are short circulated	Where high-starting torque with low-starting current or where limited speed control is required. Fans, centrifugal and plunger pumps, compressors, conveyors, hoists, cranes, ball mills, gate hoists, etc.
Synchronous	25 to several thousand	Constant	None, except special motors designed for two fixed speeds	40% for slow speed to 160% for medium speed 80% p-f designs. Special high-torque designs	Pull-out torque of unity-p-f motors 170%; 80%-p-f motors 225%. Special designs up to 300%	For constant-speed service, direct connection to slow-speed machines and where power-factor correction is required.

Copyright 2004, Industrial Press, Inc., New York, NY

In addition to these special-purpose motors, there are two types of *explosion-proof motors* designed for hazardous locations. One type is for operation in hazardous dust locations (Class II, Group *G* of the National Electrical Code) and the other is for atmospheres containing explosive vapors and fumes classified as Class I, Group *D* (gasoline, naphtha, alcohols, acetone, lacquer-solvent vapors, natural gas).

Electric Motor Maintenance

Electric Motor Inspection Schedule.— Frequency and thoroughness of inspection depend upon such factors as 1) importance of the motor in the production scheme; 2) percentage of days the motor operates; 3) nature of service; and 4) winding conditions.

The following schedules, recommended by the General Electric Company, and covering both AC and DC motors are based on average conditions in so far as duty and dirt are concerned.

Weekly Inspection.— 1) *Surroundings*. Check to see if the windings are exposed to any dripping water, acid or alcoholic fumes; also, check for any unusual amount of dust, chips, or lint on or about the motor. See if any boards, covers, canvas, etc., have been misplaced that might interfere with the motor ventilation or jam moving parts.

2) *Lubrication of sleeve-bearing motors*. In sleeve-bearing motors check oil level, if a gage is used, and fill to the specified line. If the journal diameter is less than 2 inches, the motor should be stopped before checking the oil level. For special lubricating systems, such as wool-packed, forced lubrication, flood and disk lubrication, follow instruction book. Oil should be added to bearing housing only when motor is at rest. A check should be made to see if oil is creeping along the shaft toward windings where it may harm the insulation.

3) *Mechanical condition*. Note any unusual noise that may be caused by metal-to-metal contact or any odor as from scorching insulation varnish.

4) *Ball or roller bearings*. Feel ball- or roller-bearing housings for evidence of vibration, and listen for any unusual noise. Inspect for creepage of grease on inside of motor.

5) *Commutators and brushes*. Check brushes and commutator for sparking. If the motor is on cyclic duty it should be observed through several cycles. Note color and surface condition of the commutator. A stable copper oxide-carbon film (as distinguished from a pure copper surface) on the commutator is an essential requirement for good commutation. Such a film may vary in color all the way from copper to straw, chocolate to black. It should be clean and smooth and have a high polish. All brushes should be checked for wear and pigtail connections for looseness. The commutator surface may be cleaned by using a piece of dry canvas or other hard, nonlinting material that is wound around and securely fastened to a wooden stick, and held against the rotating commutator.

6) *Rotors and armatures*. The air gap on sleeve-bearing motors should be checked, especially if they have been recently overhauled. After installing new bearings, make sure that the average reading is within 10 per cent, provided reading should be less than 0.020 inch. Check air passages through punchings and make sure they are free of foreign matter.

7) *Windings*. If necessary clean windings by suction or mild blowing. After making sure that the motor is dead, wipe off windings with dry cloth, note evidence of moisture, and see if any water has accumulated in the bottom of frame. Check if any oil or grease has worked its way up to the rotor or armature windings. Clean with carbon tetrachloride in a well-ventilated room.

8) *General*. This is a good time to check the belt, gears, flexible couplings, chain, and sprockets for excessive wear or improper location. The motor starting should be checked to make sure that it comes up to proper speed each time power is applied.

Monthly or Bimonthly Inspection.— 1) *Windings*. Check shunt, series, and commutating field windings for tightness. Try to move field spools on the poles, as drying out may have caused some play. If this condition exists, a service shop should be consulted. Check motor cable connections for tightness.

Copyright 2004, Industrial Press, Inc., New York, NY

2) *Brushes*. Check brushes in holders for fit and free play. Check the brush-spring pressure. Tighten brush studs in holders to take up slack from drying out of washers, making sure that studs are not displaced, particularly on DC motors. Replace brushes that are worn down almost to the brush rivet, examine brush faces for chipped toes or heels, and for heat cracks. Damaged brushes should be replaced immediately.

3) *Commutators*. Examine commutator surface for high bars and high mica, or evidence of scratches or roughness. See that the risers are clean and have not been damaged.

4) *Ball or roller bearings*. On hard-driven, 24-hour service ball- or roller-bearing motors, purge out old grease through drain hole and apply new grease. Check to make sure grease or oil is not leaking out of the bearing housing. If any leakage is present, correct the condition before continuing to operate.

5) *Sleeve bearings*. Check sleeve bearings for wear, including end-play bearing surfaces. Clean out oil wells if there is evidence of dirt or sludge. Flush with lighter oil before refilling.

6) *Enclosed gears*. For motors with enclosed gears, open drain plug and check oil flow for presence of metal scale, sand, or water. If condition of oil is bad, drain, flush, and refill as directed. Rock rotor to see if slack or backlash is increasing.

7) *Loads*. Check loads for changed conditions, bad adjustment, poor handling, or control.

8) *Couplings and other drive details*. Note if belt-tightening adjustment is all used up. Shorten belt if this condition exists. See if belt runs steadily and close to inside (motor edge) of pulley. Chain should be checked for evidence of wear and stretch. Clean inside of chain housing. Check chain-lubricating system. Note inclination of slanting base to make sure it does not cause oil rings to rub on housing.

Annual or Biannual Inspection.— 1) *Windings*. Check insulation resistance by using either a megohmmeter or a voltmeter having a resistance of about 100 ohms per volt. Check insulation surfaces for dry cracks and other evidence of need for coatings of insulating material. Clean surfaces and ventilating passages thoroughly if inspection shows accumulation of dust. Check for mold or water standing in frame to determine if windings need to be dried out, varnished, and baked.

2) *Air gap and bearings*. Check air gap to make sure that average reading is within 10 per cent, provided reading should be less than 0.020 inch. All bearings, ball, roller, and sleeve should be thoroughly checked and defective ones replaced. Waste-packed and wick-oiled bearings should have waste or wicks renewed, if they have become glazed or filled with metal or dirt, making sure that new waste bears well against shaft.

3) *Rotors (squirrel-cage)*. Check squirrel-cage rotors for broken or loose bars and evidence of local heating. If fan blades are not cast in place, check for loose blades. Look for marks on rotor surface indicating foreign matter in air gap or a worn bearing.

4) *Rotors (wound)*. Clean wound rotors thoroughly around collector rings, washers, and connections. Tighten connections if necessary. If rings are rough, spotted, or eccentric, refer to service shop for refinishing. See that all top sticks or wedges are tight. If any are loose, refer to service shop.

5) *Armatures*. Clean all armature air passages thoroughly if any are obstructed. Look for oil or grease creeping along shaft, checking back to bearing. Check commutator for surface condition, high bars, high mica, or eccentricity. If necessary, remachine the commutator to secure a smooth fresh surface.

6) *Loads*. Read load on motor with instruments at no load, full load, or through an entire cycle, as a check on the mechanical condition of the driven machine.

Copyright 2004, Industrial Press, Inc., New York, NY

ADHESIVES AND SEALANTS

By strict definition, an adhesive is any substance that fastens or bonds materials to be joined (adherends) by means of surface attachment. The bond durability depends on the strength of the adhesive to the substrate (adhesion) and the strength within the adhesive (cohesion). Besides bonding a joint, an adhesive may serve as a seal against foreign matter. When an adhesive performs both bonding and sealing functions, it is usually referred to as an adhesive sealant. Joining materials with adhesives offers significant benefits compared with mechanical methods of uniting two materials.

Among these benefits are that an adhesive distributes a load over an area rather than concentrating it at a point, resulting in a more even distribution of stresses. The adhesive bonded joint is therefore more resistant to flexural and vibrational stresses than, for example, a bolted, riveted, or welded joint. Another benefit is that an adhesive forms a seal as well as a bond. This seal prevents the corrosion that may occur with dissimilar metals, such as aluminum and magnesium, or mechanically fastened joints, by providing a dielectric insulation between the substrates. An adhesive also joins irregularly shaped surfaces more easily than does a mechanical fastener. Other benefits include negligible weight addition and virtually no change to part dimensions or geometry.

Most adhesives are available in liquids, gels, pastes, and tape forms. The growing variety of adhesives available can make the selection of the proper adhesive or sealant a challenging experience. In addition to the technical requirements of the adhesive, time and costs are also important considerations. Proper choice of an adhesive is based on knowledge of the suitability of the adhesive or sealant for the particular substrates. Appropriate surface preparation, curing parameters, and matching the strength and durability characteristics of the adhesive to its intended use are essential. The performance of an adhesive-bonded joint depends on a wide range of these factors, many of them quite complex. Adhesive suppliers can usually offer essential expertise in the area of appropriate selection.

Adhesives can be classified as structural or nonstructural. In general, an adhesive can be considered structural when it is capable of supporting heavy loads; nonstructural when it cannot support such loads. Many adhesives and sealants, under various brand names, may be available for a particular bonding application. It is always advisable to check the adhesive manufacturers' information before making an adhesive sealant selection. Also, testing under end-use conditions is always suggested to help ensure bonded or sealed joints meet or exceed expected performance requirements.

Though not meant to be all-inclusive, the following information correlates the features of some successful adhesive compositions available in the marketplace.

Bonding Adhesives

Reactive-type bonding adhesives are applied as liquids and react (cure) to solids under appropriate conditions. The cured adhesive is either a thermosetting or thermoplastic polymer. These adhesives are supplied as two-component no-mix, two-component mix, and one-component no-mix types, which are discussed in the following paragraphs.

Two-Component No-Mix Adhesives

Types of Adhesives.— *Anaerobic (Urethane Methacrylate Ester) Structural Adhesives:* Anaerobic structural adhesives are mixtures of acrylic esters that remain liquid when exposed to air but harden when confined between metal substrates. These adhesives can be used for large numbers of industrial purposes where high reliability of bond joints is required. Benefits include: no mixing is required (no pot-life or waste problems), flexible/durable bonds are made that withstand thermal cycling, have excellent resistance to solvents and severe environments, and rapid cure at room temperatures (eliminating

Copyright 2004, Industrial Press, Inc., New York, NY

expensive ovens). The adhesives are easily dispensed with automatic equipment. An activator is usually required to be present on one surface to initiate the cure for these adhesives. Applications for these adhesives include bonding of metals, magnets (ferrites), glass, thermosetting plastics, ceramics, and stone.

Acrylic Adhesives: Acrylic adhesives are composed of a polyurethane polymer backbone with acrylate end groups. They can be formulated to cure through heat or the use of an activator applied to the substrate surface, but many industrial acrylic adhesives are cured by light. Light-cured adhesives are used in applications where the bond geometry allows light to reach the adhesive and the production rate is high enough to justify the capital expense of a light source. Benefits include: no mixing is required (no pot-life or waste problems); formulations cure (solidify) with activator, heat, or light; the adhesive will bond to a variety of substrates, including metal and most thermoplastics; and tough and durable bonds are produced with a typical resistance to the effects of temperatures up to 180°C. Typical applications include automobile body parts (steel stiffeners), assemblies subjected to paint-baking cycles, speaker magnets to pole plates, and bonding of motor magnets, sheet steel, and many other structural applications. Other applications include bonding glass, sheet metal, magnets (ferrite), thermosetting and thermoplastic plastics, wood, ceramics, and stone.

Two-Component Mix Adhesives

Types of Adhesives.— *Epoxy Adhesives:* Two-component epoxy adhesives are well-established adhesives that offer many benefits in manufacturing. The reactive components of these adhesives are separated prior to use, so they usually have a good shelf life without refrigeration. Polymerization begins upon mixing, and a thermoset polymer is formed. Epoxy adhesives cure to form thermosetting polymers made up of a base side with the polymer resin and a second part containing the catalyst. The main benefit of these systems is that the depth of cure is unlimited. As a result, large volume can be filled for work such as potting, without the cure being limited by the need for access to an external influence such as moisture or light to activate the curing process.

For consistent adhesive performance, it is important that the mix ratio remain constant to eliminate variations in adhesive performance. Epoxies can be handled automatically, but the equipment involves initial and maintenance costs. Alternatively, adhesive components can be mixed by hand. However, this approach involves labor costs and the potential for human error. The major disadvantage of epoxies is that they tend to be very rigid and consequently have low peel strength. This lack of peel strength is less of a problem when bonding metal to metal than it is when bonding flexible substrates such as plastics.

Applications of epoxy adhesives include bonding, potting, and coating of metals, bonding of glass, rigid plastics, ceramics, wood, and stone.

Polyurethane Adhesives: Like epoxies, polyurethane adhesives are available as two-part systems or as one-component frozen premixes. They are also available as one-part moisture-cured systems. Polyurethane adhesives can provide a wide variety of physical properties. Their flexibility is greater than that of most epoxies. Coupled with the high cohesive strength, this flexibility provides a tough polymer able to achieve better peel strength and lower flexural modulus than most epoxy systems. This superior peel resistance allows use of polyurethanes in applications that require high flexibility. Polyurethanes bond very well to a variety of substrates, though a primer may be needed to prepare the substrate surface. These primers are moisture-reactive and require several hours to react sufficiently for the parts to be used. Such a time requirement may cause a production bottleneck if the bond-strength requirements are such that a primer is needed.

Applications for polyurethane adhesives include bonding of metals, glass, rubber, thermosetting and thermoplastic plastics, and wood.

Copyright 2004, Industrial Press, Inc., New York, NY

One-Component No-Mix Adhesives

Types of Adhesives.— *Light-Curable Adhesives:* Light-curing systems use a unique curing mechanism. The adhesives contain photoinitiators that absorb light energy and dissociate to form radicals. These radicals then initiate the polymerization of the polymers, oligomers, and monomers in the adhesive. The photoinitiator acts as a chemical solar cell, converting the light energy into chemical energy for the curing process. Typically, these systems are formulated for use with ultraviolet light sources. However, newer products have been formulated for use with visible light sources.

One of the biggest benefits that light-curing adhesives offer to the manufacturer is the elimination of the work time to work-in-progress trade-off, which is embodied in most adhesive systems. With light-curing systems, the user can take as much time as needed to position the part without fear of the adhesive curing. Upon exposure to the appropriate light source, the adhesive then can be fully cured in less than 1 minute, minimizing the costs associated with work in progress. Adhesives that utilize light as the curing mechanism are often one-part systems with good shelf life, which makes them even more attractive for manufacturing use.

Applications for light-curable adhesives include bonding of glass, and glass to metal, tacking of wires, surface coating, thin-film encapsulation, clear substrate bonding, and potting of components,

Cyanoacrylate Adhesives (Instant Adhesives): Cyanoacrylates or instant adhesives are often called Superglue™. Cyanoacrylates are one-part adhesives that cure rapidly, as a result of the presence of surface moisture, to form high-strength bonds, when confined between two substrates. Cyanoacrylates have excellent adhesion to many substrates, including most plastics and they achieve fixture strength in seconds and full strength within 24 hours. These qualities make cyanoacrylates suitable for use in automated production environments. They are available in viscosities ranging from water-thin liquids to thixotropic gels.

Because cyanoacrylates are a relatively mature adhesive family, a wide variety of specialty formulations is now available to help the user address difficult assembly problems. One of the best examples is the availability of polyolefin primers, which allow users to obtain high bond strengths on difficult-to-bond plastics such as polyethylene and polypropylene. One common drawback of cyanoacrylates is that they form a very rigid polymer matrix, resulting in very low peel strengths. To address this problem, formulations have been developed that are rubber-toughened. Although the rubber toughening improves the peel strength of the system to some extent, peel strength remains a weak point for this system, and, therefore, cyanoacrylates are poor candidates for joint designs that require high peel resistance. In manufacturing environments with low relative humidity, the cure of the cyanoacrylate can be significantly retarded.

This problem can be addressed in one of two ways. One approach is to use accelerators that deposit active species on the surface to initiate the cure of the product. The other approach is to use specialty cyanoacrylate formulations that have been engineered to be surface-insensitive. These formulations can cure rapidly even on dry or slightly acidic surfaces.

Applications for cyanoacrylate adhesives include bonding of thermoplastic and thermosetting plastics, rubber, metals, wood, and leather, also strain relief of wires.

Hot-Melt Adhesives: Hot-melt adhesives are widely used in assembly applications. In general, hot-melt adhesives permit fixturing speeds that are much faster than can be achieved with water- or solvent-based adhesives. Usually supplied in solid form, hot-melt adhesives liquify when exposed to elevated temperatures. After application, they cool quickly, solidifying and forming a bond between two mating substrates. Hot-melt adhesives have been used successfully for a wide variety of adherends and can greatly reduce both the need for clamping and the length of time for curing. Some drawbacks with hot-

Copyright 2004, Industrial Press, Inc., New York, NY

melt adhesives are their tendency to string during dispensing and relatively low-temperature resistance.

Applications for hot-melt adhesives are bonding of fabrics, wood, paper, plastics, and cardboard.

Rubber-Based Solvent Cements: Rubber-based solvent cements are adhesives made by combining one or more rubbers or elastomers in a solvent. These solutions are further modified with additives to improve the tack or stickiness, the degree of peel strength, flexibility, and the viscosity or body. Rubber-based adhesives are used in a wide variety of applications such as contact adhesive for plastics laminates like counter tops, cabinets, desks, and tables. Solvent-based rubber cements have also been the mainstay of the shoe and leather industry for many years.

Applications for rubber-based solvent cements include bonding of plastics laminates, wood, paper, carpeting, fabrics, and leather.

Moisture-Cured Polyurethane Adhesives: Like heat-curing systems, moisture-cured polyurethanes have the advantage of a very simple curing process. These adhesives start to cure when moisture from the atmosphere diffuses into the adhesive and initiates the polymerization process. In general, these systems will cure when the relative humidity is above 25 per cent, and the rate of cure will increase as the relative humidity increases.

The dependence of these systems on the permeation of moisture through the polymer is the source of their most significant process limitations. As a result of this dependence, depth of cure is limited to between 0.25 and 0.5 in. (6.35 and 12.7 mm). Typical cure times are in the range of 12 to 72 hours. The biggest use for these systems is for windshield bonding in automobile bodies.

Applications for moisture-cured polyurethane adhesives include bonding of metals, glass, rubber, thermosetting and thermoplastic plastics, and wood.

Retaining Compounds

The term *retaining compounds* is used to describe adhesives used in circumferential assemblies joined by inserting one part into the other. In general, retaining compounds are anaerobic adhesives composed of mixtures of acrylic esters that remain liquid when exposed to air but harden when confined between cylindrical machine components. A typical example is a bearing held in an electric motor housing with a retaining compound. The first retaining compounds were launched in 1963, and the reaction among users of bearings was very strong because these retaining compounds enabled buyers of new bearings to salvage worn housings and minimize their scrap rate.

The use of retaining compounds has many benefits, including elimination of bulk needed for high friction forces, ability to produce more accurate assemblies and to augment or replace press fits, increased strength in heavy press fits, and reduction of machining costs. Use of these compounds also helps in dissipating heat through assembly, and eliminating distortion when installing drill bushings, fretting corrosion and backlash in keys and splines, and bearing seizure during operation.

The major advantages of retaining compounds for structural assemblies are that they require less severe machining tolerances and no securing of parts. Components are assembled quickly and cleanly, and they transmit high forces and torques, including dynamic forces. Retaining compounds also seal, insulate, and prevent micromovements so that neither fretting corrosion nor stress corrosion occurs. The adhesive joint can be taken apart easily after heating above 450°F (230°C) for a specified time.

Applications for retaining compounds include mounting of bearings in housings or on shafts, avoiding distortion of precision tooling and machines, mounting of rotors on shafts, inserting drill jig bushings, retaining cylinder linings, holding oil filter tubes in castings, retaining engine-core plugs, restoring accuracy to worn machine tools, and eliminating keys and set screws.

Copyright 2004, Industrial Press, Inc., New York, NY

Threadlocking

The term *threadlocker* is used to describe adhesives used in threaded assemblies for locking the threaded fasteners by filling the spaces between the nut and bolt threads with a hard, dense material that prevents loosening. In general, thread-lockers are anaerobic adhesives comprising mixtures of acrylic esters that remain liquid when exposed to air but harden when confined between threaded components. A typical example is a mounting bolt on a motor or a pump. Threadlocker strengths range from very low strength (removable) to high strength (permanent).

It is important that the total length of the thread is coated and that there is no restriction to the curing of the threadlocker material. (Certain oils or cleaning systems can impede or even completely prevent the adhesive from curing by anaerobic reaction.) The liquid threadlocker may be applied by hand or with special dispensing devices. Proper coating (wetting) of a thread is dependent on the size of the thread, the viscosity of the adhesive, and the geometry of the parts. With blind-hole threads, it is essential that the adhesive be applied all the way to the bottom of the threaded hole. The quantity must be such that after assembly, the displaced adhesive fills the whole length of the thread.

Some threadlocking products cured by anaerobic reaction have a positive influence on the coefficient of friction in the thread. The values are comparable with those of oiled bolts. Prestress and installation torque therefore can be defined exactly. This property allows threadlocking products cured by anaerobic reaction to be integrated into automated production lines using existing assembly equipment. The use of thread-lockers has many benefits including ability to lock and seal all popular bolt and nut sizes with all industrial finishes, and to replace mechanical locking devices. The adhesive can seal against most industrial fluids and will lubricate threads so that the proper clamp load is obtained. The materials also provide vibration-resistant joints that require handtool dismantling for servicing, prevent rusting of threads, and cure (solidify) without cracking or shrinking.

The range of applications includes such uses as locking and sealing nuts on hydraulic pistons, screws on vacuum cleaner bell housings, track bolts on bulldozers, hydraulic-line fittings, screws on typewriters, oil-pressure switch assembly, screws on carburetors, rocker nuts, machinery driving keys, and on construction equipment.

Sealants

The primary role of a sealant composition is the prevention of leakage from or access by dust, fluids, and other materials to assembly structures. Acceptable leak rates can range from a slight drip to bubbletight to molecular diffusion through the base materials. Equipment users in the industrial market want trouble-free operation, but it is not always practical to specify zero leak rates. Factors influencing acceptable leak rates are toxicity, product or environmental contamination, combustibility, economics, and personnel considerations. All types of fluid seals perform the same basic function: they seal the process fluid (gas, liquid, or vapor) and keep it where it belongs. A general term for these assembly approaches is gasketing. Many products are being manufactured that are capable of sealing a variety of substrates.

Types of Sealants.— *Anaerobic Formed-in-Place Gasketing Materials:* Mechanical assemblies that require the joining of metal-to-metal flange surfaces have long been designed with prefabricated, precut materials required to seal the imperfect surfaces of the assembly. Numerous gasket materials that have been used to seal these assemblies include paper, cork, asbestos, wood, metals, dressings, and even plastics. Fluid seals are divided into static and dynamic systems, depending on whether or not the parts move in relationship to each other. Flanges are classed as static systems, although they may be moved relative to each other by vibration, temperature, and/or pressure changes, shocks, and impacts.

The term *anaerobic formed-in-place gasketing* is used to describe sealants that are used in flanged assemblies to compensate for surface imperfections of metal-to-metal compo-

Copyright 2004, Industrial Press, Inc., New York, NY

nents by filling the space between the substrates with a flexible, nonrunning material. In general, anaerobic formed-in-place gaskets are sealants made up of mixtures of acrylic esters that remain liquid when exposed to air but harden when confined between components. A typical example is sealing two halves of a split crankcase.

The use of anaerobic formed-in-place gaskets has many benefits, including the ability to seal all surface imperfections, allow true metal-to-metal contact, eliminate compression set and fastener loosening, and add structural strength to assemblies. These gaskets also help improve torque transmission between bolted flange joints, eliminate bolt retorquing needed with conventional gaskets, permit use of smaller fasteners and lighter flanges, and provide for easy disassembly and cleaning.

Applications in which formed-in-place gasketing can be used to produce leakproof joints include pipe flanges, split crankcases, pumps, compressors, power takeoff covers, and axle covers. These types of gaskets may also be used for repairing damaged conventional gaskets and for coating soft gaskets.

Silicone Rubber Formed-in-Place Gasketing: Another type of formed-in-place gasket uses room-temperature vulcanizing (RTV) silicone rubbers. These materials are one-component sealants that cure on exposure to atmospheric moisture. They have excellent properties for vehicle use such as flexibility, low volatility, good adhesion, and high resistance to most automotive fluids. The materials will also withstand temperatures up to 600°F (320°C) for intermittent operation.

RTV silicones are best suited for fairly thick section (gap) gasketing applications where flange flexing is greatest. In the form of a very thin film, for a rigid metal-to-metal seal, the cured elastomer may abrade and eventually fail under continual flange movement. The RTV silicone rubber does not unitize the assembly, and it requires relatively clean, oil-free surfaces for sufficient adhesion and leakproof seals.

Because of the silicone's basic polymeric structure, RTV silicone elastomers have several inherent characteristics that make them useful in a wide variety of applications. These properties include outstanding thermal stability at temperatures from 400 to 600°F (204 to 320°C), and good low-temperature flexibility at −85 to −165°F (−65 to −115°C). The material forms an instant seal, as is required of all liquid gaskets, and will fill large gaps up to 0.250 in. (6.35 mm) for stamped metal parts and flanges. The rubber also has good stability in ultraviolet light and excellent weathering resistance.

Applications for formed-in-place RTV silicones in the automotive field are valve, camshaft and rocker covers, manual transmission (gearbox) flanges, oil pans, sealing panels, rear axle housings, timing chain covers, and window plates. The materials are also used on oven doors and flues.

Tapered Pipe-thread Sealing

Thread sealants are used to prevent leakage of gases and liquids from pipe joints. All joints of this type are considered to be dynamic because of vibration, changing pressures, or changing temperatures.

Several types of sealants are used on pipe threads including noncuring pipe dopes, which are one of the oldest methods of sealing the spiral leak paths of threaded joints. In general, pipe dopes are pastes made from oils and various fillers. They lubricate joints and jam threads but provide no locking advantage. They also squeeze out under pressure, and have poor solvent resistance. Noncuring pipe dopes are not suitable for use on straight threads.

Another alternative is solvent-drying pipe dopes, which are an older method of sealing tapered threaded joints. These types of sealant offer the advantages of providing lubrication and orifice jamming and they also extrude less easily than noncuring pipe dopes. One disadvantage is that they shrink during cure as the solvents evaporate and fittings must be retorqued to minimize voids. These materials generally lock the threaded joint together by friction. A third type of sealer is the trapped elastomer supplied in the form of a thin tape

Copyright 2004, Industrial Press, Inc., New York, NY

incorporating polytetrafluorethylene (PTFE). This tape gives a good initial seal and resists chemical attack, and is one of the only materials used for sealing systems that will seal against oxygen gas.

Some other advantages of PTFE are that it acts as a lubricant, allows for high torquing, and has a good resistance to various solvents. Some disadvantages are that it may not provide a true seal between the two threaded surfaces, and it lubricates in the off direction, so it may allow fittings to loosen. In dynamic joints, tape may allow creep, resulting in leakage over time. The lubrication effect may allow overtightening, which can add stress or lead to breakage. Tape also may be banned in some hydraulic systems due to shredding, which may cause clogging of key orifices.

Anaerobic Pipe Sealants.— *Anaerobic Pipe Sealants:* The term *anaerobic pipe sealants* is used to describe anaerobic sealants used in tapered threaded assemblies for sealing and locking threaded joints. Sealing and locking are accomplished by filling the space between the threads with the sealant. In general, these pipe sealants are anaerobic adhesives consisting of mixtures of acrylic esters that remain liquid when exposed to air but harden when confined between threaded components to form an insoluble tough plastics. The strength of anaerobic pipe sealants is between that of elastomers and yielding metal.

Clamp loads need be only tight enough to prevent separation in use. Because they develop strength by curing after they are in place, these sealants are generally forgiving of tolerances, tool marks, and slight misalignment. These sealants are formulated for use on metal substrates. If the materials are used on plastics, an activator or primer should be used to prepare the surfaces.

Among the advantages of these anaerobic sealers are that they lubricate during assembly, they seal regardless of assembly torque, and they make seals that correspond with the burst rating of the pipe. They also provide controlled disassembly torque, do not cure outside the joint, and are easily dispensed on the production line. These sealants also have the lowest cost per sealed fitting. Among the disadvantages are that the materials are not suitable for oxygen service, for use with strong oxidizing agents, or for use at temperatures above 200°C. The sealants also are typically not suitable for diameters over M80 (approximately 3 inches).

The many influences faced by pipe joints during service should be known and understood at the design stage, when sealants are selected. Sealants must be chosen for reliability and long-term quality. Tapered pipe threads must remain leak-free under the severest vibration and chemical attack, also under heat and pressure surges.

Applications of aerobic sealants are found in industrial plant fluid power systems, the textile industry, chemical processing, utilities and power generation facilities, petroleum refining, and in marine, automotive, and industrial equipment. The materials are also used in the pulp and paper industries, in gas compression and distribution, and in waste-treatment facilities.

Copyright 2004, Industrial Press, Inc., New York, NY

MOTION CONTROL

The most important factor in the manufacture of accurately machined components is the control of motion, whatever power source is used. For all practical purposes, motion control is accomplished by electrical or electronic circuits, energizing or deenergizing actuators such as electric motors or solenoid valves connected to hydraulic or pneumatic cylinders or motors. The accuracy with which a machine tool slide, for example, may be brought to a required position, time after time, controls the dimensions of the part being machined. This accuracy is governed by the design of the motion control system in use.

There is a large variety of control systems, with power outputs from milliwatts to megawatts, and they are used for many purposes besides motion control. Such a system may control a mechanical positioning unit, which may be linear or rotary, its velocity, acceleration, or combinations of these motion parameters. A control system may also be used to set voltage, tension, and other manufacturing process variables and to actuate various types of solenoid-operated valves. The main factors governing design of control systems are whether they are to be open- or closed-loop; what kinds and amounts of power are available; and the function requirements.

Factors governing selection of control systems are listed in Table 1.

Table 1. Control System Application Factors

Type of System	Nature of required control motion, i.e., position, velocity, acceleration
Accuracy	Controlled output versus input
Mechanical Load	Viscous friction, coulomb friction, starting friction, load inertia
Impact Loads	Hitting mechanical stops and load disturbances
Ratings	Torque or force, and speed
Torque	Peak instantaneous torque
Duty Cycle	Load response, torque level, and duration and effect on thermal response
Ambient Temperature	Relation to duty cycle and internal temperature rise, and to the effect of temperature on the sensor
Speed of Response	Time to reach commanded condition. Usually defined by a response to a stepped command
Frequency Response	Output to input ratio versus frequency, for varying frequency and specified constant input amplitude. Usually expressed in decibels
No-Load Speed	Frequently applies to maximum kinetic energy and to impact on stops; avoiding overspeeding
Backdriving	With power off, can the load drive the motor? Is a fail-safe brake required? Can the load backdrive with power on without damage to the control electronics? (Electric motor acting as a generator)
Power Source	Range of voltage and frequency within which the system must work. Effect of line transients
Environmental Conditions	Range of nonoperating and operating conditions, reliability and serviceability, scheduled maintenance

Open-Loop Systems.— The term open-loop typically describes use of a rheostat or variable resistance to vary the input voltage and thereby adjust the speed of an electric motor, a low-accuracy control method because there is no output sensor to measure the performance. However, use of stepper motors (see Table 2, and page 2493) in open-loop systems can make them very accurate. Shafts of stepper motors are turned through a fixed angle for every electrical pulse transmitted to them. The maximum pulse rate can be high, and the shaft can be coupled with step-down gear drives to form inexpensive, precise drive units

Copyright 2004, Industrial Press, Inc., New York, NY

with wide speed ranges. Although average speed with stepper motors is exact, speed modulation can occur at low pulse rates and drives can incur serious resonance problems.

Table 2. Control Motor Types

AC Motors	Induction motors, simplest, lowest cost, most rugged, can work directly off the ac line or through an inexpensive, efficient, and compact thyristor controller. Useful in fan and other drives where power increases rapidly with speed as well as in simple speed regulation. Ac motors are larger than comparable permanent-magnet motors
Two-Phase Induction Motors	Often used as control motors in small electromechanical control systems. Power outputs range from a few milliwatts to tens of watts
Split-Field Series Motors	Work on both ac and dc. Feature high starting torque, low cost, uniform power output over a wide speed range, and are easily reversed with a single-pole three-position switch. Very easy to use with electric limit switches for controlling angle of travel
Permanent-Magnet Motors	Operate on dc, with high power output and high efficiency. The most powerful units use rare-earth magnets and are more expensive than conventional types. Lower-cost ferrite magnets are much less expensive and require higher gear-reduction ratios, but at their higher rated speeds are very efficient
Brushless DC Motors	Use electrical commutation and may be applied as simple drive motors or as four-quadrant control motors. The absence of brushes for commutation ensures high reliability and low electromagnetic interference
Stepper Motors	Index through a fixed angle for each input pulse so that speed is in exact proportion to pulse rate and the travel angle increases uniformly with the number of pulses. Proper application in systems with backlash and load inertia requires special care
Wound-Field DC Motors	For subfractional to integral horsepower applications where size is not significant. Cost is moderate because permanent magnets are not required. Depending on the windings, output characteristics can be adjusted for specific applications

Open-loop systems are only as accurate as the input versus output requirement can be calibrated, including the effects of changes in line voltage, temperature, and other operating conditions.

Closed-Loop Systems.— Table 3 shows some parameters and characteristics of closed-loop systems, and a simple example of such a system is shown below. A command may be input by a human operator, it may be derived from another piece of system equipment, or it may be generated by a computer. Generally, the command is in the form of an electrical signal. The system response is converted by the output sensor to a compatible, scaled electrical signal that may be compared with the input command, the difference constituting an error signal. It is usually required that the error be small, so it is amplified and applied to an appropriate driving unit. The driver may take many forms, but for motion control it is usually a motor.

The amplified error voltage drives the motor to correct the error. If the input command is constant, the system is a closed-loop regulator.

Closed-loop systems use feedback sensors that measure system output and give instructions to the power drive components, based on the measured values. A typical closed-loop speed control, for instance, uses a tachometer as a feedback sensor and will correct automatically for differences between the tachometer output and the commanded speed. All motion control systems require careful design to achieve good practical performance. Closed-loop systems generally cost more than open-loop systems because of the extra cost

Copyright 2004, Industrial Press, Inc., New York, NY

of the tachometer or transducer used for output measurement. Faster response components also increase cost.

Table 3. Closed-Loop System Parameters and Characteristics

Step Response	The response of the system to a step change in the input command. The response to a large step, which can saturate the system amplifier, is different from the response to a small nonsaturating step. Initial overshoots may not be permissible in some types of equipment
Frequency Response	System response to a specified small-amplitude sinusoidal command where frequency is varied over the range of interest. The response is in decibels (dB), where dB = 20 $\log_{10}$(output/input). This characteristic determines whether the system is responsive enough to meet requirements
Bandwidth	The effective range of input frequencies within which the control system responds well. The bandwidth is often described by the point where the frequency response is down by three decibels. Bandwidth is usually defined in Hz (cycles/sec) or $\omega = 2\pi \times$ Hz (radians/sec)
Loading	The torque required to drive the load and the load inertia. The amplifier must supply enough power to meet acceleration as well as output power requirements. If the load is nonlinear, its effect on error must be within specifications. Behavior may vary considerably, depending on whether the load aids or opposes motor torque, as in a hoist
Output Stiffness	A measure of the system's response to load disturbances. Dynamic stiffness measures the system's response to a rapidly varying load
Resonant Peaks	Can show up in frequency-response testing as sharp (undamped) resonances. These resonances cannot be tolerated in the normal frequency range of the control system because they can lead to oscillation and vibration
No load, or maximum speed and maximum torque	Can be controlled by voltage or current limiting in the electronic amplifier. A slip clutch can also be used for torque limiting, particularly to avoid impact damage



Fig. 1. General Arrangement of a Closed-Loop Control System

Accuracy of closed-loop systems is directly related to the accuracy of the sensor, so that choosing between open-loop and closed-loop controls may mean choosing between low price and consistent, accurate repeatability. In the closed-loop arrangement in Fig. 1, the sensor output is compared with the input command and the difference is amplified and applied to the motor to produce a correction. When the amplifier gain is high (the difference is greatly enlarged), even a small error will generate a correction. However, a high gain can lead to an unstable system due to inherent delays between the electrical inputs and outputs, especially with the motor.

Response accuracy depends not only on the precision of the feedback sensor and the gain of the amplifier, but also on the rate at which the command signal changes. The ability of the control system to follow rapidly changing inputs is naturally limited by the maximum motor speed and acceleration.

Copyright 2004, Industrial Press, Inc., New York, NY

Amplified corrections cannot be applied to the motor instantaneously, and the motor does not respond immediately. Overshoots and oscillations can occur and the system must be adjusted or tuned to obtain acceptable performance. This adjustment is called damping the system response. Table 4 lists a variety of methods of damping, some of which require specialized knowledge.

Table 4. Means of Damping System Response

Network Damping	Included in the electrical portion of the closed loop. The networks adjust amplitude and phase to minimize control system feedback oscillations. Notch networks are used to reduce gain at specific frequencies to avoid mechanical resonance oscillations
Tachometer Damping	Feedback proportional to output velocity is added to the error signal for system stabilization
Magnetic Damping	Viscous or inertial dampers on the motor rear shaft extension for closed-loop stabilization. Similar dampers use silicone fluid instead of magnetic means to provide damping
Nonlinear Damping	Used for special characteristics. Inverse error damping provides low damping for large errors, permitting fast slewing toward zero and very stable operation at zero. Other nonlinearities meet specific needs, for example, coulomb friction damping works well in canceling backlash oscillations
Damping Algorithms	With information on output position or velocity, or both, sampled data may be used with appropriate algorithms to set motor voltage for an optimum system response

The best damping methods permit high error amplification and accuracy, combined with the desired degree of stability. Whatever form the output takes, it is converted by the output sensor to an electrical signal of compatible form that can be compared with the input command. The error signal thus generated is amplified before being applied to the driving unit.

Drive Power.— Power for the control system often depends on what is available and may vary from single- and three-phase ac 60 or 400 Hz, through dc and other types. Portable or mobile equipment is usually battery-powered dc or an engine-driven electrical generator. Hydraulic and pneumatic power may also be available. Cost is often the deciding factor in the choice.

Table 5. Special Features of Controllers

Linear or Pulse-Width Modulated	Linear is simpler, PWM is more complex and can generate electromagnetic interference, but is more efficient
Current Limiting	Sets limits to maximum line or motor current. Limits the torque output of permanent magnet motors. Can reduce starting transients and current surges
Voltage Limiting	Sets limits to maximum motor speed. Permits more uniform motor performance over a wide range of line voltages
Energy Absorption	Ability of the controller to absorb energy from a dc motor drive, back-driven by the load
EMI Filtering	Especially important when high electrical gain is required, as in thermocouple circuits, for example
Isolation	Of input and output, sometimes using optoisolators, or transformers, when input and output circuits require a high degree of isolation

Control Function.— The function of the control is usually set by the designer of the equipment and needs careful definition because it is the basis for the overall design. For instance, in positioning a machine tool table, such aspects as speed of movement and permissible variations in speed, accuracy of positioning, repeatability, and overshoot are among dozens of factors that must be considered. Some special features of controllers are

Copyright 2004, Industrial Press, Inc., New York, NY

listed in Table 5. Complex electromechanical systems require more knowledge of design and debugging than are needed for strictly mechanical systems.

Electromechanical Control Systems.— Wiring is the simplest way to connect components, so electromechanical controls are more versatile than pure hydraulic or pneumatic controls. The key to this versatility is often in the controller, the fundamental characteristic of which is its power output. The power output must be compatible with motor and load requirements. Changes to computer chips or software can usually change system performance to suit the application.

When driving a dc motor, for instance, the controller must supply sufficient power to match load requirements as well as motor operating losses, at minimum line voltage and maximum ambient temperature. The system's wiring must not be greatly sensitive to transient or steady-state electrical interference, and power lines must be separated from control signal lines, or appropriately shielded and isolated to avoid cross-coupling. Main lines to the controller must often include electrical interference filters so that the control system does not affect the power source, which may influence other equipment connected to the same source. For instance, an abruptly applied step command can be smoothed out so that heavy motor inrush currents are avoided. The penalty is a corresponding delay in response.

Use of current limiting units in a controller will not only set limits to line currents, but will also limit motor torque. Electronic torque limiting can frequently avoid the need for mechanical torque limiting. An example of the latter is using a slip clutch to avoid damage due to overtravel, the impact of which usually includes the kinetic energy of the moving machine elements. In many geared systems, most of the kinetic energy is in the motor. Voltage limiting is less useful than current limiting but may be needed to isolate the motor from voltage transients on the power line, to prevent overspeeding, as well as to protect electronic components.

Mechanical Stiffness.— When output motion must respond to a rapidly changing input command, the control system must have a wide bandwidth. Where the load mass (in linear motion systems) or the polar moment of inertia (in rotary systems) is high, there is a possibility of resonant oscillations. For the most stable and reliable systems, with a defined load, a high system mechanical stiffness is preferred. To attain this stiffness requires strengthening shafts, preloading bearings, and minimizing free play or backlash. In the best-performing systems, motor and load are coupled without intervening compliant members. Even tightly bolted couplings can introduce compliant oscillations resulting from extremely minute slippages caused by the load motions.

Backlash is a factor in the effective compliance of any coupling but has little effect on the resonant frequency because little energy is exchanged as the load is moved through the backlash region. However, even in the absence of significant torsional resonance, a high-gain control system can “buzz” in the backlash region. Friction is often sufficient to eliminate this small-amplitude, high-frequency component.

The difficulty with direct-drive control systems lies in matching motor to load. Most electric motors deliver rated power at higher speeds than are required by the driven load, so that load power must be delivered by the direct-drive motor operating at a slow and relatively inefficient speed. Shaft power at low speed involves a correspondingly high torque, which requires a large motor and a high-power controller. Motor copper loss (heating) is high in delivering the high motor torque. However, direct-drive motors provide maximum load velocity and acceleration, and can position massive loads within seconds of arc (rotational) or tenths of thousandths of an inch (linear) under dynamic conditions.

Where performance requirements are moderate, the required load torque can be traded off against speed by using a speed-changing transmission, typically, a gear train. The transmission effectively matches the best operating region of the motor to the required operating region of the load, and both motor and controller can be much smaller than would be needed for a comparable direct drive.

Copyright 2004, Industrial Press, Inc., New York, NY

Torsional Vibration.— Control system instabilities can result from insufficient stiffness between the motor and the inertia of the driven load. The behavior of such a system is similar to that of a torsional pendulum, easily excited by commanded motions of the control system. If frictional losses are moderate to low, sustained oscillations will occur. In spite of the complex dynamics of the closed-loop system, the resonant frequency, as for a torsional pendulum, is given to a high degree of accuracy by the formula:

$$f_n = \frac{1}{2\pi} \times \sqrt{\frac{K}{J_L}}$$

where f_n is in hertz, K is torsional stiffness in in.-lb/rad, and J_L is load inertia in in.-lb-sec^2/rad. If this resonant frequency falls within the bandwidth of the control system, self-sustained oscillations are likely to occur. These oscillations are often overlooked by control systems analysts because they do not appear in simple control systems, and they are very difficult to correct.

Friction inherently reduces the oscillation by dissipating the energy in the system inertia. If there is backlash between motor and load, coulomb friction (opposing motion but independent of speed) is especially effective in damping out the oscillation. However, the required friction for satisfactory damping can be excessive, introducing positioning error and adding to motor (and controller) power requirements. Friction also varies with operating conditions and time.

The most common method of eliminating torsional oscillation is to introduce a filter in the error channel of the control system to shape the gain characteristic as a function of frequency. If the torsional resonance is within the required system bandwidth, little can be done except stiffening the mechanical system and increasing the resonant frequency. If the filter reduces the gain within the required bandwidth, it will reduce performance. This method will work only if the natural resonance is above the minimum required performance bandwidth.

The simplest shaping network is the notch network (Table 4, network damping), which, in effect, is a band-rejection filter that sharply reduces gain at the notch frequency. By locating the notch frequency so as to balance out the torsional resonance peak, the oscillation can be eliminated. Where there are several modes of oscillation, several filter networks can be connected in series.

Electric Motors.— Electric motors for control systems must suit the application. Motors used in open-loop systems (excluding stepper motors) need not respond quickly to input command changes. Where the command is set by a human, response times of hundreds of milliseconds to several seconds may be acceptable. Slow response does not lead to the instabilities that time delays can introduce into closed-loop systems.

Closed-loop systems need motors with fast response, of which the best are permanent-magnet dc units, used where wide bandwidth, efficient operation, and high power output are required. Table 2 lists some types of control motors and their characteristics. An important feature of high-performance, permanent-magnet motors using high-energy, rare-earth magnets is that their maximum torque output capacity can be 10 to 20 or more times higher than their rated torque. In intermittent or low-duty-cycle applications, very high torque loads can be driven by a given motor. However, when rare-earth magnets (samarium cobalt or neodymium) are not used, peak torque capability may be limited by the possibility of demagnetization. Rare-earth magnets are relatively expensive, so it is important to verify peak torque capabilities for lower-cost motors that may use weaker Alnico or ferrite magnets.

Duty-cycle calculations are an aspect of thermal analysis that are well understood and are not covered here. Motor manufacturers usually supply information on thermal characteristics including thermal time constants and temperature rise per watt of internal power dissipation.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Idealized Control Motor Characteristics for a Consistent Set of Units

Characteristics of permanent-magnet motors are defined with fair accuracy by relatively few parameters. The most important characteristics are: D_M motor damping in lb-in.-sec/rad; J_M motor inertia in lb-in.-sec$_2$/rad; and R winding resistance in ohms. Fig. 1 shows other control motor characteristics, T_{STo} stall torque with no current limiting; T_L maximum torque with current limiting; ω_{NL} no-load speed; ω_R rated speed. Other derived motor parameters include V rated voltage in volts; $I_{STo} = V/R$ current in amperes at stall with no current limiting; I_L ampere limit, adjusted in amplifier; I_R rated current; $K_T = T_{STo}/I_{STo}$ torque constant in in.-lb/ampere; $K_E = V/\omega_{NL}$ voltage constant in volt/rad/sec; $K_M = K_T/\sqrt{R}$, torque per square root of winding resistance; $D_M = T_{STo}/\omega_{NL}$ motor damping in in.-lb/rad/sec; and $T_M = J_M/D_M$ motor mechanical time constant in seconds.

Stepper Motors.— In a stepper motor, power is applied to a wound stator, causing the brushless rotor to change position to correspond with the internal magnetic field. The rotor maintains its position relative to the internal magnetic field at all times. In its most common mode of operation, the stepper motor is energized by an electronic controller whose current output to the motor windings defines the position of the internally generated magnetic field. Applying a command pulse to the controller will change the motor currents to reposition the rotor. A series of pulses, accompanied by a direction command, will cause rotation in uniformly spaced steps in the specified direction.

If the pulses are applied at a sufficiently high frequency, the rotor will be carried along with the system's inertia and will rotate relatively uniformly but with a modulated velocity. At the other extreme, the response to a single pulse will be a step followed by an overshoot and a decaying oscillation. Where the application cannot permit the oscillation, damping can be included in the controller.

Stepper motors are often preferred because positions of the rotor are known from the number of pulses and the step size. An initial index point is required as an output position reference, and care is required in the electronic circuits to avoid introducing random pulses that will cause false positions. As a minimum, the output index point on an appropriate shaft can verify the step count during operation.

Gearing.— In a closed-loop system, gearing may be used to couple a high-speed, low-torque motor to a lower-speed, higher-torque load. The gearing must meet requirements for accuracy, strength, and reliability to suit the application. In addition, the closed loop requires minimum backlash at the point where the feedback sensor is coupled. In a velocity-controlled system, the feedback sensor is a tachometer that is usually coupled directly to the rotor shaft. Backlash between motor and tachometer, as well as torsional compliance, must be minimized for stable operation of a high-performance system. Units combining motor and tachometer on a single shaft can usually be purchased as an assembly.

By contrast, a positioning system may use a position feedback sensor that is closely coupled to the shaft being positioned. As with the velocity system, backlash between the motor and feedback sensor must be minimized for closed-loop stability. Antibacklash gearing is frequently used between the gearing and the position feedback sensor. When the position

Copyright 2004, Industrial Press, Inc., New York, NY

feedback sensor is a limited rotation device, it may be coupled to a gear that turns faster than the output gear to allow use of its full range. Although this step-up gearing enhances it, accuracy is ultimately limited by the errors in the intermediate gearing between the position sensor and the output.

When an appreciable load inertia is being driven, it is important that the mechanical stiffness between the position sensor coupling point and the load be high enough to avoid natural torsional resonances in the passband.

Feedback Transducers.— Controlled variables are measured by feedback transducers and are the key to accuracy in operation of closed-loop systems. When the accuracy of a carefully designed control system approaches the accuracy of the feedback transducer, the need for precision in the other system components is reduced.

Transducers may measure the quantity being controlled in digital or analog form, and are available for many different parameters such as pressure and temperature, as well as distance traveled or degrees of rotation. Machine designers generally need to measure and control linear or rotary motion, velocity, position, and sometimes acceleration. Although some transducers are nonlinear, a linear relationship between the measured variable and the (usually electrical) output is most common.

Output characteristics of an analog linear-position transducer are shown in Fig. 2. By dividing errors into components, accuracy can be increased by external adjustments, and slope error and zero offsets are easily trimmed in. Nonlinearity is controlled by the manufacturer. In Fig. 2 are seen the discrete error components that can be distinguished because of the ease with which they can be canceled out individually by external adjustments. The most common compensation is for zero-position alignment, so that when the machine has been set to the start position for a sequence, the transducer can be positioned to read zero output. Alternatively, with all components in fixed positions, a small voltage can be inserted in series with the transducer output for a very accurate alignment of mechanical and electrical zeros. This method helps in canceling long-term drift, particularly in the mechanical elements.

The second most common adjustment of a position transducer is of its output gradient, that is, transducer output volts per degree. Depending on the type of analog transducer, it is usually possible to add a small adjustment to the electrical input, to introduce a proportional change in output gradient. As with the zero-position adjustment, the gradient may be set very accurately initially and during periodic maintenance. The remaining errors shown in Fig. 2, such as intrinsic nonlinearity or nonconformity, result from limitations in design and manufacture of the transducer.



Fig. 3. Output Characteristics of a General Linear Position Transducer

Greater accuracy can be achieved in computer-controlled systems by using the computer to cancel out transducer errors. The system's mechanical values and corresponding transducer values are stored in a lookup table in the computer and referred to as necessary.

Copyright 2004, Industrial Press, Inc., New York, NY

Accuracies approaching the inherent repeatability and stability of the system can thus be secured. If necessary, recalibration can be performed at frequent intervals.

Analog Transducers.— The simplest analog position transducer is the resistance potentiometer, the resistance element in which is usually a deposited-film rather than a wirewound type. Very stable resistance elements based on conductive plastics, with resolution to a few microinches and operating lives in the 100 million rotations, are available, capable of working in severe environments with high vibrations and shock and at temperatures of 150 to 200°C. Accuracies of a few hundredths, and stability of thousandths, of a per cent, can be obtained from these units by trimming the plastics resistance element as a function of angle.

Performance of resistance potentiometers deteriorates when they operate at high speeds, and prolonged operation at speeds above 10 rpm causes excessive wear and increasing output noise. An alternative to the resistance potentiometer is the variable differential transformer, which uses electrical coupling between ac magnetic elements to measure angular or linear motion without sliding contacts. These units have unlimited resolution with accuracy comparable to the best resistance potentiometers but are more expensive and require compatible electronic circuits.

A variable differential transformer needs ac energization, so an ac source is required. A precision demodulator is frequently used to change the ac output to dc. Sometimes the ac output is balanced against an ac command signal whose input is derived from the same ac source. In dealing with ac signals, phase-angle matching and an accurate amplitude-scale factor are required for proper operation. Temperature compensation also may be required, primarily due to changes in resistance of the copper windings. Transducer manufacturers will supply full sets of compatible electronic controls.

Synchros and Resolvers.— Synchros and resolvers are transducers that are widely used for sensing of angles at accuracies down to 10 to 20 arc-seconds. More typically, and at much lower cost, their accuracies are 1 to 2 arc-minutes. Cost is further reduced when accuracies of 0.1 degree or higher are acceptable.

Synchros used as angle-position transducers are made as brush types with slip rings and in brushless types. These units can rotate continuously at high speeds, the operating life of brushless designs being limited only by the bearing life. Synchros have symmetrical three-wire stator windings that facilitate transmission of angle data over long distances (thousands of feet). Such a system is also highly immune to noise and coupled signals. Practically the only trimming required for very long line systems is matching the line-to-line capacitances.

Because synchros can rotate continuously, they can be used in multispeed arrangements, where, for example, full-scale system travel may be represented by 36 or 64 full rotations. When reduced by gearing to a single, full-scale turn, a synchro's electrical inaccuracy is the typical 0.1° error divided by 36 or 64 or whatever gear ratio is used. This error is insignificant compared with the error of the gearing coupling the high-speed synchro and the single speed (1 rotation for full scale) output shaft. The accuracy is dependable and stable, using standard synchros and gearing.

Hydraulic and Pneumatic Systems

In Fig. 1 is shown a schematic of a hydraulic cylinder and the relationships between force and area that govern all hydraulic systems. Hydraulic actuators that drive the load may be cylinders or motors, depending on whether linear or rotary motion is required. The load must be defined by its torque–speed characteristics and inertia, and a suitable hydraulic actuator selected before the remaining system components can be chosen. Fluid under pressure and suitable valves are needed to control motion. Both single- and double-acting hydraulic cylinders are available, and the latter type is seen in Fig. 1.

Copyright 2004, Industrial Press, Inc., New York, NY

Pressure can be traded off against velocity, if desired, by placing a different effective area at each side of the piston. The same pressure on a smaller area will move the piston at a higher speed but lower force for a given rate of fluid delivery. The cylinder shown in Fig. 1 can drive loads in either direction. The simple formulas of plane geometry relate cylinder areas, force, fluid flow, and rate of movement. Other configurations can develop equal forces and speeds in both directions.

The rotary equivalent of the cylinder is the hydraulic motor, which is defined by the fluid displacement required to turn the output shaft through one revolution, by the output torque, and by the load requirements of torque and speed. Output torque is proportional to fluid pressure, which can be as high as safety permits. Output speed is defined by the number of gallons per minute supplied to the motor. As an example, if 231 cu. in. = 1 gallon, an input of 6 gallons/min (gpm) with a 5-cu. in. displacement gives a mean speed of $6 \times 231/5 = 277$ rpm. The motor torque must be defined by lb-in. per 100 $lb_f/in.^2$ (typically) from which the required pressure can be determined. Various motor types are available.

Hydraulic Pumps.— The most-used hydraulic pump is the positive-displacement type, which delivers a fixed amount of fluid for every cycle. These pumps are also called hydrostatic because they deliver energy by static pressure rather than by the kinetic energy of a moving fluid. Positive-displacement pumps are rated by the gpm delivered at a stated speed and by the maximum pressure, which are the key parameters defining the power capacity of the hydraulic actuator. Delivered gpm are reduced under load due to leakage, and the reduction is described by the volumetric efficiency, which is the ratio of actual to theoretical output.

Hydraulic Fluids.— The hydraulic fluid is the basic means of transmitting power, and it also provides lubrication and cooling when passed through a heat exchanger. The fluid must be minimally compressible to avoid springiness and delay in response. The total system inertia reacts with fluid compliance to generate a resonant frequency, much as inertia and mechanical compliance react in an electromechanical system. Compliance must be low enough that resonances do not occur in the active bandwidth of the servomechanism, and that unacceptable transients do not occur under shock loads. Seal friction and fluid viscosity tend to damp out resonant vibrations. Shock-absorbing limit stops or cushions are usually located at the travel limits to minimize transient impact forces.

F = force (lb) = pressure × area

P_1 and P_2 = line pressure on either side of piston in $lb_f/in.^2$

d_1 and d_2 = diameters of piston rod and piston in in.

$$F_1 = \frac{\pi}{4}(d_2^2 - d_1^2) \times P_1 = 0.7854P_1(d_2^2 - d_1^2)$$

$$F_2 = \frac{\pi}{4} d_2^2 P_2 = 0.7854P_2 d_2^2$$



Fig. 1. Elementary Hydraulic Force/Area Formulas

Hydraulic fluids with special additives for lubrication minimize wear between moving parts. An auxiliary function is prevention of corrosion and pitting. Hydraulic fluids must also be compatible with gaskets, seals, and other nonmetallic materials.

Viscosity is another critical parameter of hydraulic fluids as high viscosity means high resistance to fluid flow with a corresponding power loss and heating of the fluid, pressure drop in the hydraulic lines, difficulty in removing bubbles, and sometimes overdamped operation. Unfortunately, viscosity falls very rapidly with increasing temperature, which can lead to reduction of the lubrication properties and excessive wear as well as increasing leakage. For hydraulic actuators operating at very low temperatures, the fluid pour point is important. Below this temperature, the hydraulic fluid will not flow. Design guidelines similar to those used with linear or rotating bearings are applicable in these conditions.

Copyright 2004, Industrial Press, Inc., New York, NY

Fire-resistant fluids are available for use in certain conditions such as in die casting, where furnaces containing molten metal are often located near hydraulic systems.

A problem with hydraulic systems that is absent in electromechanical systems is that of dirt, air bubbles, and contaminants in the fluid. Enclosed systems are designed to keep out contaminants, but the main problem is with the reservoir or fluid storage unit. A suitable sealer must be used in the reservoir to prevent corrosion and a filter should be used during filling. Atmospheric pressure is required on the fluid surface in the reservoir except where a pressurized reservoir is used. Additional components include coarse and fine filters to remove contaminants and these filters may be rated to remove micron sized particles (1 micron = 0.00004 in.).

Very fine filters are sometimes used in high-pressure lines, where dirt might interfere with the operation of sensitive valves. Where a high-performance pump is used, a fine filter is a requirement. Usually, only coarse filters are used on fluid inlet lines because fine filters might introduce excessive pressure drop.

Aside from the reservoir used for hydraulic fluid storage, line connections, fittings, and couplings are needed. Expansion of these components under pressure increases the mechanical compliance of the system, reducing the frequencies of any resonances and possibly interfering with the response of wide-band systems.

Formulas relating fluid flow and mechanical power follow. These formulas supplement the general force, torque, speed, and power formulas of mechanical systems.

$$F = P \times A$$

$$A = 0.7854 \times d^2$$

$$hp = 0.000583q \times \text{pressure in lb}_f/\text{in.}^2$$

1 gallon of fluid flow/min at 1 $\text{lb}_f/\text{in.}^2$ pressure = 0.000582 hp.

For rotary outputs,

$$hp = \text{torque} \times \text{rpm}/63{,}025$$

where torque is in lb-in. (Theoretical hp output must be multiplied by the efficiency of the hydraulic circuits to determine actual output.)

In the preceding equations,

P = pressure in $\text{lb}_f/\text{in.}^2$

A = piston area in in.^2

F = force in lb

q = fluid flow in gallons/min

d = piston diameter in inches

Hydraulic and Pneumatic Control Systems.— Control systems for hydraulic and pneumatic circuits are more mature than those for electromechanical systems because they have been developed over many more years. Hydraulic components are available at moderate prices from many sources. Although their design is complex, application and servicing of these systems are usually more straightforward than with electromechanical systems.

Electromechanical and hydraulic/pneumatic systems may be analyzed by similar means. The mathematical requirements for accuracy and stability are analogous, as are most performance features, although nonlinearities are caused by different physical attributes. Nonlinear friction, backlash, and voltage and current limiting are common to both types of system, but hydraulic/pneumatic systems also have the behavior characteristics of fluid-driven systems such as thermal effects and fluid flow dynamics including turbulence, leakage caused by imperfect seals, and contamination.

Both control types require overhead equipment that does not affect performance but adds to overall cost and complexity. For instance, electromechanical systems require electrical power sources and power control components, voltage regulators, fuses and circuit breakers, relays and switches, connectors, wiring and related devices. Hydraulic/pneumatic sys-

Copyright 2004, Industrial Press, Inc., New York, NY

tems require fluid stored under pressure, motor-driven pumps or compressors, valves, pressure regulators/limiters, piping and fasteners, as well as hydraulic/pneumatic motors and cylinders. Frequently, the optimum system is selected on the basis of overhead equipment already available.

Electromechanical systems are generally slower and heavier than hydraulic systems and less suited to controlling heavy loads. The bandwidths of hydraulic control systems can respond to input signals of well over 100 Hz as easily as an electromechanical system can respond to, say, 10 to 20 Hz. Hydraulic systems can drive very high torque loads without intermediate transmissions such as the gear trains often used with electromechanical systems. Also, hydraulic/pneumatic systems using servo valves and piston/cylinder arrangements are inherently suited to linear motion operation, whereas electromechanical controls based on conventional electrical machines are more naturally suited to driving rotational loads.

Until recently, electromechanical systems were limited to system bandwidths of about 10 Hz, with power outputs of a few hundred watts. However, their capabilities have now been sharply extended through the use of rare-earth motor magnets having much higher energies than earlier designs. Similarly, semiconductor power components deliver much higher output power at lower prices than earlier equipment. Electromechanical control systems are now suited to applications of more than 100 hp with bandwidths up to 40 Hz and sometimes up to 100 Hz.

Although much depends on the specific design, the edge in reliability, even for high-power, fast-response needs, is shifting toward electromechanical systems. Basically, there are more things that can go wrong in hydraulic/pneumatic systems, as indicated by the shift to more electrical systems in aircraft.

Hydraulic Control Systems.— Using essentially incompressible fluid, hydraulic systems are suited to a wide range of applications, whereas pneumatic power is generally limited to simpler uses. In Fig. 2 are shown the essential features of a simple linear hydraulic control system and a comparable system for driving a rotating load.



Fig. 2. (left) A Simple Linear Hydraulic Control System in Which the Load Force Returns the Piston and (right) a Comparable System for Driving a Rotating Load

Hydraulic controls of the type shown have fast response and very high load capacities. In a linear actuator, for example, each $lb_f/in.^2$ of system pressure acts against the area of the piston to generate the force applied. Hydraulic pressures of up to 3000 $lb_f/in.^2$ are readily obtained from hydraulic pumps, so that cylinders can exert forces of hundreds of tons without the need for speed-reducing transmission systems to increase the force. The hydraulic fluid distributes heat, so it helps cool the system.

Systems similar to those in Fig. 2 can be operated in open- or closed-loop modes. Open-loop operation can be controlled by programming units that initiate each step by operating relays, limit switches, solenoid valves, and other components to generate the forces over

Copyright 2004, Industrial Press, Inc., New York, NY

the required travel ranges. Auxiliary components are used to ensure safe operation and make such systems flexible and reliable, as shown in Fig. 3.



Fig. 3. Some of the Auxiliary Components Used in a Practical Hydraulic System

In the simplest mode, whether open- or closed-loop, hydraulic system operation may be discontinuous or proportional. Discontinuous operation, sometimes called bang-bang, or on–off, works well, is widely used in low- to medium-accuracy systems, and is easy to maintain. In this closed-loop mode, accuracy is limited; if the response to error is set too high, the system will oscillate between on–off modes, with average output at about the desired value. This oscillation, however, can be noisy, introduces system transients, and may cause rapid wear of system components.

Another factor to be considered in on–off systems is the shock caused by sudden opening and closing of high-pressure valves, which introduce transient pulses in the fluid flow and can cause high stresses in components. These problems can be addressed by the use of pressure-limiting relief valves and other units.

Proportional Control Systems.— Where the highest accuracy is required, perhaps in two directions, and with aiding or opposing forces or torques, a more sophisticated proportional control, closed-loop system is preferred. As shown in Fig. 4, the amplifier and electric servomotor used in electromechanical closed-loop systems is replaced in the closed-loop hydraulic system by an electronically controlled servo-valve. In its simplest form, the valve uses a linear motor to position the spool that determines the flow path for the hydraulic fluid. In some designs, the linear motor may be driven by a solenoid against a bias spring on the value spool. In other arrangements, the motor may be a bidirectional unit that permits a fluid flow depending on the polarity and amplitude of the voltage supplied to the motor.



Fig. 4.

Such designs can be used in proportional control systems to achieve smooth operation and minimum nonlinearities, and will give the maximum accuracy required by the best machine tool applications. Where very high power must be controlled, use is often made of a two-stage valve in which the output from the first stage is used to drive the second-stage valve, as shown in Fig. 5.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Two-Stage Valve for Large-Power Control from a Low-Power Input

Electronic Controls.— An error-sensing electronic amplifier drives the solenoid motor of Fig. 5, which provides automatic output correction in a closed-loop system. The input is an ideal place to introduce electrical control features, adding greatly to the versatility of the control system. The electronic amplifier can provide the necessary driving power using pulse-width modulation as required, for minimum heating. The output can respond to signals in the low-microvolt range.

A major decision is whether to use analog or digital control. Although analog units are simple, they are much less versatile than their digital counterparts. Digital systems can be readjusted for total travel, speed, and acceleration by simple reprogramming. Use of appropriate feedback sensors can match accuracy to any production requirement, and a single digital system can be easily adapted to a great variety of similar applications. This adaptability is an important cost-saving feature for moderate-sized production runs. Modern microprocessors can integrate the operation of sets of systems.

Because nonlinearities and small incremental motions are easy to implement, digital systems are capable of very smooth acceleration, which avoids damaging shocks and induced leaks, and enhances reliability so that seals and hose connections last longer. The accuracy of digital control systems depends on transducer availability, and a full range of such devices has been developed and is now available.

Other features of digital controls are their capacity for self-calibration, easy digital readout, and periodic self-compensation. For example, it is easy to incorporate backlash compensation. Inaccuracies can be corrected by using lookup tables that may themselves be updated as necessary. Digital outputs can be used as part of an inspection plan, to indicate need for tool changing, adjustment or sharpening, or for automatic record keeping. Despite continuing improvements in analog systems, digital control of hydraulic systems is favored in large plants.

Pneumatic Systems.— Hydraulic systems transmit power by means of the flow of an essentially incompressible fluid. Pneumatic systems use a highly compressible gas. For this reason, a pneumatic system is slower in responding to loads, especially sudden output loads, than a hydraulic system. Similarly, torque or force requires time and output motion to build up. Response to sudden output loads shows initial overshoot. Much more complex networks or other damping means are required to develop stable response in closed-loop systems. On the other hand, there are no harmful shock waves analogous to the transients that can occur in hydraulic systems, and pneumatic system components last comparatively longer.

Notwithstanding their performance deficiencies, pneumatic systems have numerous desirable features. Pneumatic systems avoid some fire hazards compared with the most preferred hydraulic fluids. Air can be vented to the atmosphere so a flow line only is needed, reducing the complexity, cost, and weight of the overall system. Pneumatic lines,

Copyright 2004, Industrial Press, Inc., New York, NY

couplings, and fittings are lighter than their hydraulic counterparts, often a significant advantage. The gaseous medium also is lighter than hydraulic fluid, and pneumatic systems are usually easier to clean, assemble, and generally maintain. Fluid viscosity and its temperature variations are virtually negligible with pneumatic systems.

Among drawbacks with pneumatics are that lubrication must be carefully designed in, and more power is needed to achieve a desired pressure when the fluid medium is a compressible gas. Gas under high pressure can cause an explosion if its storage tank is damaged, so storage must have substantial safety margins. Gas compressibility makes pneumatic systems 1 or 2 orders of magnitude slower than hydraulic systems.

The low stiffness of pneumatic systems is another indicator of the long response time. Resonances occur between the compressible gas and equivalent system inertias at lower frequencies. Even the relatively low speed of sound in connecting lines contributes to response delay, adding to the difficulty of closed-loop stabilization. Fortunately, it is possible to construct pneumatic analogs to electrical networks to simplify stabilization at the exact point of the delays. Such pneumatic stabilizing means are commercially available and are important elements of closed-loop pneumatic control systems.

In contrast with hydraulic systems, where speed may be controlled by varying pump output, pneumatic system control is almost exclusively by valves, which control the flow from a pneumatic accumulator or pressure source. The pressure is maintained between limits by an intermittently operated pump. Low-pressure outlet ports must be large enough to accommodate the high volume of the expanded gas. In Fig. 6 is shown a simplified system for closed-loop position control applied to an air cylinder, in which static accuracy is controlled by the position sensor. Proper design requires a good theoretical analysis and attention to practical design if good, stable, closed-loop response is to be achieved.



Fig. 6. A Pneumatic Closed-Loop Linear Control System

Copyright 2004, Industrial Press, Inc., New York, NY

O-RINGS

An O-ring is a one-piece molded elastomeric seal with a circular cross-section that seals by distortion of its resilient elastic compound. Dimensions of O-rings are given in ANSI/SAE AS568A, Aerospace Size Standard for O-rings. The standard ring sizes have been assigned identifying dash numbers that, in conjunction with the compound (ring material), completely specifies the ring. Although the ring sizes are standardized, ANSI/SAE AS568A does not cover the compounds used in making the rings; thus, different manufacturers will use different designations to identify various ring compounds. For example, 230-8307 represents a standard O-ring of size 230 (2.484 in. ID by 0.139 in. width) made with compound 8307, a general-purpose nitrile compound. O-ring material properties are discussed at the end of this section.

When properly installed in a groove, an O-ring is normally slightly deformed so that the naturally round cross-section is squeezed diametrically out of round prior to the application of pressure. This compression ensures that under static conditions, the ring is in contact with the inner and outer walls enclosing it, with the resiliency of the rubber providing a zero-pressure seal. When pressure is applied, it tends to force the O-ring across the groove, causing the ring to further deform and flow up to the fluid passage and seal it against leakage, as in Fig. 1(a). As additional pressure is applied, the O-ring deforms into a D shape, as in Fig. 1(b). If the clearance gap between the sealing surface and the groove corners is too large or if the pressure exceeds the deformation limits of the O-ring material (compound), the O-ring will extrude into the clearance gap, reducing the effective life of the seal. For very low-pressure static applications, the effectiveness of the seal can be improved by using a softer durometer compound or by increasing the initial squeeze on the ring, but at higher pressures, the additional squeeze may reduce the ring's dynamic sealing ability, increase friction, and shorten ring life.



Fig. 1.

The initial diametral squeeze of the ring is very important in the success of an O-ring application. The squeeze is the difference between the ring width *W* and the gland depth *F* (Fig. 2) and has a great effect on the sealing ability and life of an O-ring application.



Fig. 2. Groove and Ring Details

Copyright 2004, Industrial Press, Inc., New York, NY

The ideal squeeze varies according to the ring cross-section, with the average being about 20 per cent, i.e., the ring's cross-section *W* is about 20 per cent greater than the gland depth *F* (groove depth plus clearance gap). The groove width is normally about 1.5 times larger than the ring width *W*. When installed, an O-ring compresses slightly and distorts into the free space within the groove. Additional expansion or swelling may also occur due to contact of the ring with fluid or heat. The groove must be large enough to accommodate the maximum expansion of the ring or the ring may extrude into the clearance gap or rupture the assembly. In a dynamic application, the extruded ring material will quickly wear and fray, severely limiting seal life.

To prevent O-ring extrusion or to correct an O-ring application, reduce the clearance gap by modifying the dimensions of the system, reduce the system operating pressure, install antiextrusion backup rings in the groove with the O-ring, as in Fig. 3, or use a harder O-ring compound. A harder compound may result in higher friction and a greater tendency of the seal to leak at low pressures. Backup rings, frequently made of leather, Teflon, metal, phenolic, hard rubber, and other hard materials, prevent extrusion and nibbling where large clearance gaps and high pressure are necessary.



Fig. 3. Preferred Use of Backup Washers

The most effective and reliable sealing is generally provided by using the diametrical clearances given in manufacturers' literature. However, the information in Table 1 may be used to estimate the gland depth (groove depth plus radial clearance) required in O-ring applications. The radial clearance used (radial clearance equals one-half the diametral clearance) also depends on the system pressure, the ring compound and hardness, and specific details of the application.

Table 1. Gland Depth for O-Ring Applications

Standard O-Ring Cross-Sectional Diameter (in.)	Gland Depth (in.)	
	Reciprocating Seals	Static Seals
0.070	0.055 to 0.057	0.050 to 0.052
0.103	0.088 to 0.090	0.081 to 0.083
0.139	0.121 to 0.123	0.111 to 0.113
0.210	0.185 to 0.188	0.170 to 0.173
0.275	0.237 to 0.240	0.226 to 0.229

Source: Auburn Manufacturing Co. When possible, use manufacturer recommendations for clearance gaps and groove depth.

Fig. 4 indicates conditions where O-ring seals may be used, depending on the fluid pressure and the O-ring hardness. If the conditions of use fall to the right of the curve, extrusion of the O-ring into the surrounding clearance gap will occur, greatly reducing the life of the ring. If conditions fall to the left of the curve, no extrusion of the ring will occur, and the ring may be used under these conditions. For example, in an O-ring application with a 0.004-in. diametral clearance and 2500-psi pressure, extrusion will occur with a 70 durometer O-ring but not with an 80 durometer O-ring. As the graph indicates, high-pressure applications require lower clearances and harder O-rings for effective sealing.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Extrusion Potential of O-Rings as a Function of Hardness and Clearance

Recommended groove width, clearance dimensions, and bottom-of-groove radius for O-ring numbers up to 475 (25.940-in. ID by 0.275-in. width) can be found using Table 2 in conjunction with Fig. 5. In general, except for ring cross-sections smaller than $\frac{1}{16}$ in., the groove width is approximately $1.5W$, where W is the ring cross-sectional diameter. Straight-sided grooves are best for preventing extrusion of the ring or nibbling; however, for low-pressure applications (less than 1500 psi) sloped sides with an angle up to 5° can be used to simplify machining of the groove. The groove surfaces should be free of burrs, nicks, or scratches. For static seals (i.e., no contact between the O-ring and any moving parts), the groove surfaces should have a maximum roughness of 32 to 63 µin. rms for liquid-sealing applications and 16 to 32 µin. rms for gaseous-sealing applications. In dynamic seals, relative motion exists between the O-ring and one or more parts and the maximum groove surface roughness should be 8 to 16 µin. rms for sliding contact applications (reciprocating seals, for example) and 16 to 32 µin. rms for rotary contact applications (rotating and oscillating seals).

In dynamic seal applications, the roughness of surfaces in contact with O-rings (bores, pistons, and shafts, for example) should be 8 to 16 µin. rms, without longitudinal or circumferential scratches. Surface finishes of less than 5 µin. rms are too smooth to give a good seal life because they wipe too clean, causing the ring to wear against the housing in the absence of a lubricating film. The best-quality surfaces are honed, burnished, or hard chromium plated. Soft and stringy metals such as aluminum, brass, bronze, Monel, or free machining stainless steel should not be used in contact with moving seals. In static applica-

Copyright 2004, Industrial Press, Inc., New York, NY

tions, O-ring contacting surfaces should have a maximum surface roughness of 64 to 125 µin. rms.

Table 2. Diametral Clearance and Groove Sizes for O-Ring Applications

ANSI/SAE AS568 Number	Tolerances		Diametral Clearance, *D*		Groove Width, *G*			Bottom of Groove Radius, *R*
					Backup Rigs			
	A	*B*	Reciprocating & Static Seals	Rotary Seals	None	One	Two	
001	+0.001 −0.000	+0.000 −0.001	0.002 to 0.004	0.012 to 0.016	0.063			0.005 to 0.015
002					0.073			
003					0.083			
004 to 012					0.094	0.149	0.207	
013 to 050	+0.002 −0.000	+0.000 −0.002	0.002 to 0.005					
102 to 129					0.141	0.183	0.245	
130 to 178			0.002 to 0.006	0.016 to 0.020	0.188	0.235	0.304	0.010 to 0.025
201 to 284								
309 to 395			0.003 to 0.007		0.281	0.334	0.424	
425 to 475	+0.003 −0.000	+0.000 −0.003	0.004 to 0.010		0.375	0.475	0.579	0.020 to 0.035

Source: Auburn Manufacturing Co. All dimensions are in inches. Clearances listed are minimum and maximum values; standard groove widths may be reduced by about 10 per cent for use with ring compounds that free swell less than 15 per cent. Dimension *A* is the ID of any surface contacted by the outside circumference of the ring; *B* is the OD of any surface contacted by the inside circumference of the ring.



Fig. 5. Installation data for use with Table 2. Max and Min are maximum and minimum piston and bore diameters for O.D. and I.D., respectively.

The preferred bore materials are steel and cast iron, and pistons should be softer than the bore to avoid scratching them. The bore sections should be thick enough to resist expansion and contraction under pressure so that the radial clearance gap remains constant, reducing the chance of damage to the O-ring by extrusion and nibbling. Some compatibility problems may occur when O-rings are used with plastics parts because certain compounding ingredients may attack the plastics, causing crazing of the plastics surface.

O-rings are frequently used as driving belts in round bottom or V-grooves with light tension for low-power drive elements. Special compounds are available with high resistance to stress relaxation and fatigue for these applications. Best service is obtained in drive belt applications when the initial belt tension is between 80 and 200 psi and the initial installed stretch is between 8 and 25 per cent of the circumferential length. Most of the compounds used for drive belts operate best between 10 and 15 per cent stretch, although polyurethane has good service life when stretched as much as 20 to 25 per cent.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Typical O-Ring Compounds

Nitrile	General-purpose compound for use with most petroleum oils, greases, gasoline, alcohols and glycols, LP gases, propane and butane fuels. Also for food service to resist vegetable and animal fats. Effective temperature range is about –40° to 250°F. Excellent compression set, tear and abrasion resistance, but poor resistance to ozone, sunlight and weather. Higher-temperature nitrile compounds with similar properties are also available.
Hydrogenated Nitrile	Similar to general-purpose nitrile compounds with improved high-temperature performance, resistance to aging, and petroleum product compatibility.
Polychloroprene (Neoprene)	General-purpose compound with low compression set and good resistance to elevated temperatures. Good resistance to sunlight, ozone, and weathering, and fair oil resistance. Frequently used for refrigerator gases such as Freon. Effective temperature range is about –40° to 250°F.
Ethylene Propylene	General-purpose compound with excellent resistance to polar fluids such as water, steam, ketones, and phosphate esters, and brake fluids, but not resistant to petroleum oils and solvents. Excellent resistance to ozone and flexing. Recommended for belt-drive applications. Continuous duty service in temperatures up to 250°F.
Silicon	Widest temperature range (–150° to 500°F) and best low-temperature flexibility of all elastomeric compounds. Not recommended for dynamic applications, due to low strength, or for use with most petroleum oils. Shrinkage characteristics similar to organic rubber, allowing existing molds to be used.
Polyurethane	Toughest of the elastomers used for O-rings, characterized by high tensile strength, excellent abrasion resistance, and tear strength. Compression set and heat resistance are inferior to nitrile. Suitable for hydraulic applications that anticipate abrasive contaminants and shock loads. Temperature service range of –65° to 212°F.
Fluorosilicone	Wide temperature range (–80° to 450°F) for continuous duty and excellent resistance to petroleum oils and fuels. Recommended for static applications only, due to limited strength and low abrasion resistance.
Polyacrylate	Heat resistance better than nitrile compounds, but inferior low temperature, compression set, and water resistance. Often used in power steering and transmission applications due to excellent resistance to oil, automatic transmission fluids, oxidation, and flex cracking. Temperature service range of –20° to 300°F.
Fluorocarbon (Viton)	General-purpose compound suitable for applications requiring resistance to aromatic or halogenated solvents or to high temperatures (–20° to 500°F with limited service to 600°F). Outstanding resistance to blended aromatic fuels, straight aromatics, and halogenated hydrocarbons and other petroleum products. Good resistance to strong acids (temperature range in acids (–20° to 250°F), but not effective for use with very hot water, steam, and brake fluids.

Copyright 2004, Industrial Press, Inc., New York, NY

Ring Materials.— Thousands of O-ring compounds have been formulated for specific applications. Some of the most common types of compounds and their typical applications are given in Table 3. The Shore A durometer is the standard instrument used for measuring the hardness of elastomeric compounds. The softest O-rings are 50 and 60 Shore A and stretch more easily, exhibit lower breakout friction, seal better on rough surfaces, and need less clamping pressure than harder rings. For a given squeeze, the higher the durometer hardness of a ring, the greater the associated friction because a greater compressive force is exerted by hard rings than soft rings.

The most widely used rings are medium-hard O-rings with 70 Shore A hardness, which have the best wear resistance and frictional properties for running seals. Applications that involve oscillating or rotary motion frequently use 80 Shore A materials. Rings with a hardness above 85 Shore A often leak more because of less effective wiping action. These harder rings have a greater resistance to extrusion, but for small sizes may break easily during installation. O-ring hardness varies inversely with temperature, but when used for continuous service at high temperatures, the hardness may eventually increase after an initial softening of the compound.

O-ring compounds have thermal coefficients of expansion in the range of 7 to 20 times that of metal components, so shrinkage or expansion with temperature change can pose problems of leakage past the seal at low temperatures and excessive pressures at high temperatures when a ring is installed in a tight-fitting groove. Likewise, when an O-ring is immersed in a fluid, the compound usually absorbs some of the fluid and consequently increases in volume. Manufacturer's data give volumetric increase data for compounds completely immersed in various fluids. For confined rings (those with only a portion of the ring exposed to fluid), the size increase may be considerably lower than for rings completely immersed in fluid. Certain fluids can also cause ring shrinkage during “idle” periods, i.e., when the seal has a chance to dry out. If this shrinkage is more than 3 to 4 per cent, the seal may leak.

Excessive swelling due to fluid contact and high temperatures softens all compounds approximately 20 to 30 Shore A points from room temperature values and designs should anticipate the expected operating conditions. At low temperatures, swelling may be beneficial because fluid absorption may make the seal more flexible. However, the combination of low temperature and low pressure makes a seal particularly difficult to maintain. A soft compound should be used to provide a resilient seal at low temperatures. Below –65°F, only compounds formulated with silicone are useful; other compounds are simply too stiff, especially for use with air and other gases.

Compression set is another material property and a very important sealing factor. It is a measure of the shape memory of the material, that is, the ability to regain shape after being deformed. Compression set is a ratio, expressed as a percentage, of the unrecovered to original thickness of an O-ring compressed for a specified period of time between two heated plates and then released. O-rings with excessive compressive set will fail to maintain a good seal because, over time, the ring will be unable to exert the necessary compressive force (squeeze) on the enclosing walls. Swelling of the ring due to fluid contact tends to increase the squeeze and may partially compensate for the loss due to compression set. Generally, compression set varies by compound and ring cross-sectional diameter, and increases with the operating temperature.

Copyright 2004, Industrial Press, Inc., New York, NY

ROLLED STEEL SECTIONS, WIRE, AND SHEET-METAL GAGES

Rolled Steel Sections

Lengths of Angles Bent to Circular Shape.— To calculate the length of an angle-iron used either inside or outside of a tank or smokestack, the following table of constants may be used: Assume, for example, that a stand-pipe, 20 feet inside diameter, is provided with a 3 by 3 by $\frac{3}{8}$ inch angle-iron on the inside at the top. The circumference of a circle 20 feet in diameter is 754 inches. From the table of constants, find the constant for a 3 by 3 by $\frac{3}{8}$ inch angle-iron, which is 4.319. The length of the angle then is 754 − 4.319 = 749.681 inches. Should the angle be on the outside, add the constant instead of subtracting it; thus, 754 + 4.319 = 758.319 inches.

Size of Angle	Const.	Size of Angle	Const.	Size of Angle	Const.
$\frac{1}{4} \times 2 \times 2$	2.879	$\frac{5}{16} \times 3 \times 3$	4.123	$\frac{1}{2} \times 5 \times 5$	6.804
$\frac{5}{16} \times 2 \times 2$	3.076	$\frac{3}{8} \times 3 \times 3$	4.319	$\frac{3}{8} \times 6 \times 6$	7.461
$\frac{3}{8} \times 2 \times 2$	3.272	$\frac{1}{2} \times 3 \times 3$	4.711	$\frac{1}{2} \times 6 \times 6$	7.854
$\frac{1}{4} \times 2\frac{1}{2} \times 2\frac{1}{2}$	3.403	$\frac{3}{8} \times 3\frac{1}{2} \times 3\frac{1}{2}$	4.843	$\frac{3}{4} \times 6 \times 6$	8.639
$\frac{5}{16} \times 2\frac{1}{2} \times 2\frac{1}{2}$	3.600	$\frac{1}{2} \times 3\frac{1}{2} \times 3\frac{1}{2}$	5.235	$\frac{1}{2} \times 8 \times 8$	9.949
$\frac{3}{8} \times 2\frac{1}{2} \times 2\frac{1}{2}$	3.796	$\frac{3}{8} \times 4 \times 4$	5.366	$\frac{3}{4} \times 8 \times 8$	10.734
$\frac{1}{2} \times 2\frac{1}{2} \times 2\frac{1}{2}$	4.188	$\frac{1}{2} \times 4 \times 4$	5.758	$1 \times 8 \times 8$	11.520
$\frac{1}{4} \times 3 \times 3$	3.926	$\frac{3}{8} \times 5 \times 5$	6.414	…	…

Standard Designations of Rolled Steel Shapes.— Through a joint effort, the American Iron and Steel Institute (AISI) and the American Institute of Steel Construction (AISC) have changed most of the designations for their hot-rolled structural steel shapes. The present designations, standard for steel producing and fabricating industries, should be used when designing, detailing, and ordering steel. The accompanying Table 1 compares the present designations with the previous descriptions.

Table 1. Hot-Rolled Structural Steel Shape Designations (AISI and AISC)

Present Designation	Type of Shape	Previous Designation
W 24 × 76	W shape	24 WF 76
W 14 × 26	W shape	14 B 26
S 24 × 100	S shape	24 I 100
M 8 × 18.5	M shape	8 M 18.5
M 10 × 9	M shape	10 JR 9.0
M 8 × 34.3	M shape	8 × 8 M 34.3
C 12 × 20.7	American Standard Channel	12 [20.7
MC 12 × 45	Miscellaneous Channel	12 × 4 [45.0
MC 12 × 10.6	Miscellaneous Channel	12 JR [10.6
HP 14 × 73	HP shape	14 BP 73
L 6 × 6 × $\frac{3}{4}$	Equal Leg Angle	∠ 6 × 6 × $\frac{3}{4}$
L 6 × 4 × $\frac{5}{8}$	Unequal Leg Angle	∠ 6 × 4 × $\frac{5}{8}$
WT 12 × 38	Structural Tee cut from W shape	ST 12 WF 38
WT 7 × 13	Structural Tee cut from W shape	ST 7 B 13
St 12 × 50	Structural Tee cut from S shape	ST 12 I 50
MT 4 × 9.25	Structural Tee cut from M shape	ST 4 M 9.25
MT 5 × 4.5	Structural Tee cut from M shape	ST 5 JR 4.5
MT 4 × 17.15	Structural Tee cut from M shape	ST 4 M 17.15
PL ½ × 18	Plate	PL 18 × ½
Bar 1	Square Bar	Bar 1
Bar 1 ¼ ∅	Round Bar	Bar 1¼∅
Bar 2½ × ½	Flat Bar	Bar 2½ × ½
Pipe 4 Std.	Pipe	Pipe 4 Std.
Pipe 4 X-Strong	Pipe	Pipe 4 X-Strong
Pipe 4 XX-Strong	Pipe	Pipe 4 XX-Strong
TS 4 × 4 × .375	Structural Tubing: Square	Tube 4 × 4 × .375
TS 5 × 3 × .375	Structural Tubing: Rectangular	Tube 5 × 3 × .375
TS 3 OD × .250	Structural Tubing: Circular	Tube 3 OD × .250

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2a. Steel Wide-Flange Sections

Wide-flange sections are designated, in order, by a section letter, nominal depth of the member in inches, and the nominal weight in pounds per foot; thus:

W 18 × 64

indicates a wide-flange section having a nominal depth of 18 inches, and a nominal weight per foot of 64 pounds. Actual geometry for each section can be obtained from the values below.



Designation	Area, A inch^2	Depth, d inch	Flange		Web	Axis X–X			Axis Y–Y		
			Width, b_f inch	Thickness, t_f inch	Thickness, t_w inch	I inch^4	S inch^3	r inch	I inch^4	S inch^3	r inch
[a]W 27 × 178	52.3	27.81	14.085	1.190	0.725	6990	502	11.6	555	78.8	3.26
× 161	47.4	27.59	14.020	1.080	0.660	6280	455	11.5	497	70.9	3.24
× 146	42.9	27.38	13.965	0.975	0.605	5630	411	11.4	443	63.5	3.21
× 114	33.5	27.29	10.070	0.930	0.570	4090	299	11.0	159	31.5	2.18
× 102	30.0	27.09	10.015	0.830	0.515	3620	267	11.0	139	27.8	2.15
× 94	27.7	26.92	9.990	0.745	0.490	3270	243	10.9	124	24.8	2.12
× 84	24.8	26.71	9.960	0.640	0.460	2850	213	10.7	106	21.2	2.07
W 24 × 162	47.7	25.00	12.955	1.220	0.705	5170	414	10.4	443	68.4	3.05
× 146	43.0	24.74	12.900	1.090	0.650	4580	371	10.3	391	60.5	3.01
× 131	38.5	24.48	12.855	0.960	0.605	4020	329	10.2	340	53.0	2.97
× 117	34.4	24.26	12.800	0.850	0.550	3540	291	10.1	297	46.5	2.94
× 104	30.6	24.06	12.750	0.750	0.500	3100	258	10.1	259	40.7	2.91
× 94	27.7	24.31	9.065	0.875	0.515	2700	222	9.87	109	24.0	1.98
× 84	24.7	24.10	9.020	0.770	0.470	2370	196	9.79	94.4	20.9	1.95
× 76	22.4	23.92	8.990	0.680	0.440	2100	176	9.69	82.5	18.4	1.92
× 68	20.1	23.73	8.965	0.585	0.415	1830	154	9.55	70.4	15.7	1.87
× 62	18.2	23.74	7.040	0.590	0.430	1550	131	9.23	34.5	9.80	1.38
× 55	16.2	23.57	7.005	0.505	0.395	1350	114	9.11	29.1	8.30	1.34
W 21 × 147	43.2	22.06	12.510	1.150	0.720	3630	329	9.17	376	60.1	2.95
× 132	38.8	21.83	12.440	1.035	0.650	3220	295	9.12	333	53.5	2.93
× 122	35.9	21.68	12.390	0.960	0.600	2960	273	9.09	305	49.2	2.92
× 111	32.7	21.51	12.340	0.875	0.550	2670	249	9.05	274	44.5	2.90
× 101	29.8	21.36	12.290	0.800	0.500	2420	227	9.02	248	40.3	2.89
× 93	27.3	21.62	8.420	0.930	0.580	2070	192	8.70	92.9	22.1	1.84
× 83	24.3	21.43	8.355	0.835	0.515	1830	171	8.67	81.4	19.5	1.83
× 73	21.5	21.24	8.295	0.740	0.455	1600	151	8.64	70.6	17.0	1.81
× 68	20.0	21.13	8.270	0.685	0.430	1480	140	8.60	64.7	15.7	1.80
× 62	18.3	20.99	8.240	0.615	0.400	1330	127	8.54	57.5	13.9	1.77
× 57	16.7	21.06	6.555	0.650	0.405	1170	111	8.36	30.6	9.35	1.35
× 50	14.7	20.83	6.530	0.535	0.380	984	94.5	8.18	24.9	7.64	1.30
× 44	13.0	20.66	6.500	0.450	0.350	843	81.6	8.06	20.7	6.36	1.26
W 18 × 119	35.1	18.97	11.265	1.060	0.655	2190	231	7.90	253	44.9	2.69
× 106	31.1	18.73	11.200	0.940	0.590	1910	204	7.84	220	39.4	2.66
× 97	28.5	18.59	11.145	0.870	0.535	1750	188	7.82	201	36.1	2.65
× 86	25.3	18.39	11.090	0.770	0.480	1530	166	7.77	175	31.6	2.63
× 76	22.3	18.21	11.035	0.680	0.425	1330	146	7.73	152	27.6	2.61
× 71	20.8	18.47	7.635	0.810	0.495	1170	127	7.50	60.3	15.8	1.70
× 65	19.1	18.35	7.590	0.750	0.450	1070	117	7.49	54.8	14.4	1.69
× 60	17.6	18.24	7.555	0.695	0.415	984	108	7.47	50.1	13.3	1.69
× 55	16.2	18.11	7.530	0.630	0.390	890	98.3	7.41	44.9	11.9	1.67
× 50	14.7	17.99	7.495	0.570	0.355	800	88.9	7.38	40.1	10.7	1.65
× 46	13.5	18.06	6.060	0.605	0.360	712	78.8	7.25	22.5	7.43	1.29
× 40	11.8	17.90	6.015	0.525	0.315	612	68.4	7.21	19.1	6.35	1.27
× 35	10.3	17.70	6.000	0.425	0.300	510	57.6	7.04	15.3	5.12	1.22

[a] Consult the AISC Manual, noted above, for W steel shapes having nominal depths greater than 27 inches.

Symbols: I = moment of inertia; S = section modulus; r = radius of gyration.

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Steel Wide-Flange Sections

Wide-flange sections are designated, in order, by a section letter, nominal depth of the member in inches, and the nominal weight in pounds per foot. Thus:

W 16 × 78

indicates a wide-flange section having a nominal depth of 16 inches, and a nominal weight per foot of 78 pounds. Actual geometry for each section can be obtained from the values below.



Designation	Area, A inch^2	Depth, d inch	Flange		Web Thick-ness, t_w inch	Axis X–X			Axis Y–Y		
			Width, b_f inch	Thick-ness, t_f inch		I inch^4	S inch^3	r inch	I inch^4	S inch^3	r inch
W 16 × 100	29.4	16.97	10.425	0.985	0.585	1490	175	7.10	186	35.7	2.51
× 89	26.2	16.75	10.365	0.875	0.525	1300	155	7.05	163	31.4	2.49
× 77	22.6	16.52	10.295	0.760	0.455	1110	134	7.00	138	26.9	2.47
× 67	19.7	16.33	10.235	0.665	0.395	954	117	6.96	119	23.2	2.46
× 57	16.8	16.43	7.120	0.715	0.430	758	92.2	6.72	43.1	12.1	1.60
× 50	14.7	16.26	7.070	0.630	0.380	659	81.0	6.68	37.2	10.5	1.59
× 45	13.3	16.13	7.035	0.565	0.345	586	72.7	6.65	32.8	9.34	1.57
× 40	11.8	16.01	6.995	0.505	0.305	518	64.7	6.63	28.9	8.25	1.57
× 36	10.6	15.86	6.985	0.430	0.295	448	56.5	6.51	24.5	7.00	1.52
× 31	9.12	15.88	5.525	0.440	0.275	375	47.2	6.41	12.4	4.49	1.17
× 26	7.68	15.69	5.500	0.345	0.250	301	38.4	6.26	9.59	3.49	1.12
W 14 × 730	215.0	22.42	17.890	4.910	3.070	14300	1280	8.17	4720	527	4.69
× 665	196.0	21.64	17.650	4.520	2.830	12400	1150	7.98	4170	472	4.62
× 605	178.0	20.92	17.415	4.160	2.595	10800	1040	7.80	3680	423	4.55
× 550	162.0	20.24	17.200	3.820	2.380	9430	931	7.63	3250	378	4.49
× 500	147.0	19.60	17.010	3.500	2.190	8210	838	7.48	2880	339	4.43
× 455	134.0	19.02	16.835	3.210	2.015	7190	756	7.33	2560	304	4.38
× 426	125.0	18.67	16.695	3.035	1.875	6600	707	7.26	2360	283	4.34
× 398	117.0	18.29	16.590	2.845	1.770	6000	656	7.16	2170	262	4.31
× 370	109.0	17.92	16.475	2.660	1.655	5440	607	7.07	1990	241	4.27
× 342	101.0	17.54	16.360	2.470	1.540	4900	559	6.98	1810	221	4.24
× 311	91.4	17.12	16.230	2.260	1.410	4330	506	6.88	1610	199	4.20
× 283	83.3	16.74	16.110	2.070	1.290	3840	459	6.79	1440	179	4.17
× 257	75.6	16.38	15.995	1.890	1.175	3400	415	6.71	1290	161	4.13
× 233	68.5	16.04	15.890	1.720	1.070	3010	375	6.63	1150	145	4.10
× 211	62.0	15.72	15.800	1.560	0.980	2660	338	6.55	1030	130	4.07
× 193	56.8	15.48	15.710	1.440	0.890	2400	310	6.50	931	119	4.05
× 176	51.8	15.22	15.650	1.310	0.830	2140	281	6.43	838	107	4.02
× 159	46.7	14.98	15.565	1.190	0.745	1900	254	6.38	748	96.2	4.00
× 145	42.7	14.78	15.500	1.090	0.680	1710	232	6.33	677	87.3	3.98

Symbols: I = moment of inertia; S = section modulus; r = radius of gyration.

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2c. Steel Wide-Flange Sections

Wide-flange sections are designated, in order, by a section letter, nominal depth of the member in inches, and the nominal weight in pounds per foot. Thus:

W 14 × 38

indicates a wide-flange section having a nominal depth of 14 inches, and a nominal weight per foot of 38 pounds. Actual geometry for each section can be obtained from the values below.



Designation	Area, A inch^2	Depth, d inch	Flange Width, b_f inch	Flange Thickness, t_f inch	Web Thickness, t_w inch	Axis X–X I inch^4	Axis X–X S inch^3	Axis X–X r inch	Axis Y–Y I inch^4	Axis Y–Y S inch^3	Axis Y–Y r inch
W 14 × 132	38.8	14.66	14.725	1.030	0.645	1530	209	6.28	548	74.5	3.76
× 120	35.3	14.48	14.670	0.940	0.590	1380	190	6.24	495	67.5	3.74
× 109	32.0	14.32	14.605	0.860	0.525	1240	173	6.22	447	61.2	3.73
× 99	29.1	14.16	14.565	0.780	0.485	1110	157	6.17	402	55.2	3.71
× 90	26.5	14.02	14.520	0.710	0.440	999	143	6.14	362	49.9	3.70
× 82	24.1	14.31	10.130	0.855	0.510	882	123	6.05	148	29.3	2.48
× 74	21.8	14.17	10.070	0.785	0.450	796	112	6.04	134	26.6	2.48
× 68	20.0	14.04	10.035	0.720	0.415	723	103	6.01	121	24.2	2.46
× 61	17.9	13.89	9.995	0.645	0.375	640	92.2	5.98	107	21.5	2.45
× 53	15.6	13.92	8.060	0.660	0.370	541	77.8	5.89	57.7	14.3	1.92
× 48	14.1	13.79	8.030	0.595	0.340	485	70.3	5.85	51.4	12.8	1.91
× 43	12.6	13.66	7.995	0.530	0.305	428	62.7	5.82	45.2	11.3	1.89
× 38	11.2	14.10	6.770	0.515	0.310	385	54.6	5.87	26.7	7.88	1.55
× 34	10.0	13.98	6.745	0.455	0.285	340	48.6	5.83	23.3	6.91	1.53
× 30	8.85	13.84	6.730	0.385	0.270	291	42.0	5.73	19.6	5.82	1.49
× 26	7.69	13.91	5.025	0.420	0.255	245	35.3	5.65	8.91	3.54	1.08
× 22	6.49	13.74	5.000	0.335	0.230	199	29.0	5.54	7.00	2.80	1.04
W 12 × 336	98.8	16.82	13.385	2.955	1.775	4060	483	6.41	1190	177	3.47
× 305	89.6	16.32	13.235	2.705	1.625	3550	435	6.29	1050	159	3.42
× 279	81.9	15.85	13.140	2.470	1.530	3110	393	6.16	937	143	3.38
× 252	74.1	15.41	13.005	2.250	1.395	2720	353	6.06	828	127	3.34
× 230	67.7	15.05	12.895	2.070	1.285	2420	321	5.97	742	115	3.31
× 210	61.8	14.71	12.790	1.900	1.180	2140	292	5.89	664	104	3.28
× 190	55.8	14.38	12.670	1.735	1.060	1890	263	5.82	589	93.0	3.25
× 170	50.0	14.03	12.570	1.560	0.960	1650	235	5.74	517	82.3	3.22
× 152	44.7	13.71	12.480	1.400	0.870	1430	209	5.66	454	72.8	3.19
× 136	39.9	13.41	12.400	1.250	0.790	1240	186	5.58	398	64.2	3.16
× 120	35.3	13.12	12.320	1.105	0.710	1070	163	5.51	345	56.0	3.13
× 106	31.2	12.89	12.220	0.990	0.610	933	145	5.47	301	49.3	3.11
× 96	28.2	12.71	12.160	0.900	0.550	833	131	5.44	270	44.4	3.09
× 87	25.6	12.53	12.125	0.810	0.515	740	118	5.38	241	39.7	3.07
× 79	23.2	12.38	12.080	0.735	0.470	662	107	5.34	216	35.8	3.05
× 72	21.1	12.25	12.040	0.670	0.430	597	97.4	5.31	195	32.4	3.04
× 65	19.1	12.12	12.000	0.605	0.390	533	87.9	5.28	174	29.1	3.02
× 58	17.0	12.19	10.010	0.640	0.360	475	78.0	5.28	107	21.4	2.51
× 53	15.6	12.06	9.995	0.575	0.345	425	70.6	5.23	95.8	19.2	2.48
× 50	14.7	12.19	8.080	0.640	0.370	394	64.7	5.18	56.3	13.9	1.96
× 45	13.2	12.06	8.045	0.575	0.335	350	58.1	5.15	50.0	12.4	1.94
× 40	11.8	11.94	8.005	0.515	0.295	310	51.9	5.13	44.1	11.0	1.93
× 35	10.3	12.50	6.560	0.520	0.300	285	45.6	5.25	24.5	7.47	1.54
× 30	8.79	12.34	6.520	0.440	0.260	238	38.6	5.21	20.3	6.24	1.52
× 26	7.65	12.22	6.490	0.380	0.230	204	33.4	5.17	17.3	5.34	1.51
× 22	6.48	12.31	4.030	0.425	0.260	156	25.4	4.91	4.66	2.31	0.847
× 19	5.57	12.16	4.005	0.350	0.235	130	21.3	4.82	3.76	1.88	0.822
× 16	4.71	11.99	3.990	0.265	0.220	103	17.1	4.67	2.82	1.41	0.773
× 14	4.16	11.91	3.970	0.225	0.200	88.6	14.9	4.62	2.36	1.19	0.753

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2d. Steel Wide-Flange Sections

Wide-flange sections are designated, in order, by a section letter, nominal depth of the member in inches, and the nominal weight in pounds per foot; thus:

W 8 × 67

indicates a wide-flange section having a nominal depth of 8 inches, and a nominal weight per foot of 67 pounds. Actual geometry for each section can be obtained from the values below.



Designation	Area, A inch^2	Depth, d inch	Flange: Width, b_f inch	Flange: Thickness, t_f inch	Web Thickness, t_w inch	Axis X–X: I inch^4	Axis X–X: S inch^3	Axis X–X: r inch	Axis Y–Y: I inch^4	Axis Y–Y: S inch^3	Axis Y–Y: r inch
W 10 × 112	32.9	11.36	10.415	1.250	0.755	716	126	4.66	236	45.3	2.68
× 100	29.4	11.10	10.340	1.120	0.680	623	112	4.60	207	40.0	2.65
× 88	25.9	10.84	10.265	0.990	0.605	534	98.5	4.54	179	34.8	2.63
× 77	22.6	10.60	10.190	0.870	0.530	455	85.9	4.49	154	30.1	2.60
× 68	20.0	10.40	10.130	0.770	0.470	394	75.7	4.44	134	26.4	2.59
× 60	17.6	10.22	10.080	0.680	0.420	341	66.7	4.39	116	23.0	2.57
× 54	15.8	10.09	10.030	0.615	0.370	303	60.0	4.37	103	20.6	2.56
× 49	14.4	9.98	10.000	0.560	0.340	272	54.6	4.35	93.4	18.7	2.54
× 45	13.3	10.10	8.020	0.620	0.350	248	49.1	4.32	53.4	13.3	2.01
× 39	11.5	9.92	7.985	0.530	0.315	209	42.1	4.27	45.0	11.3	1.98
× 33	9.71	9.73	7.960	0.435	0.290	170	35.0	4.19	36.6	9.20	1.94
× 30	8.84	10.47	5.810	0.510	0.300	170	32.4	4.38	16.7	5.75	1.37
× 26	7.61	10.33	5.770	0.440	0.260	144	27.9	4.35	14.1	4.89	1.36
× 22	6.49	10.17	5.750	0.360	0.240	118	23.2	4.27	11.4	3.97	1.33
× 19	5.62	10.24	4.020	0.395	0.250	96.3	18.8	4.14	4.29	2.14	0.874
× 17	4.99	10.11	4.010	0.330	0.240	81.9	16.2	4.05	3.56	1.78	0.844
× 15	4.41	9.99	4.000	0.270	0.230	68.9	13.8	3.95	2.89	1.45	0.810
× 12	3.54	9.87	3.960	0.210	0.190	53.8	10.9	3.90	2.18	1.10	0.785
W 8 × 67	19.7	9.00	8.280	0.935	0.570	272	60.4	3.72	88.6	21.4	2.12
× 58	17.1	8.75	8.220	0.810	0.510	228	52.0	3.65	75.1	18.3	2.10
× 48	14.1	8.50	8.110	0.685	0.400	184	43.3	3.61	60.9	15.0	2.08
× 40	11.7	8.25	8.070	0.560	0.360	146	35.5	3.53	49.1	12.2	2.04
× 35	10.3	8.12	8.020	0.495	0.310	127	31.2	3.51	42.6	10.6	2.03
× 31	9.13	8.00	7.995	0.435	0.285	110	27.5	3.47	37.1	9.27	2.02
× 28	8.25	8.06	6.535	0.465	0.285	98.0	24.3	3.45	21.7	6.63	1.62
× 24	7.08	7.93	6.495	0.400	0.245	82.8	20.9	3.42	18.3	5.63	1.61
× 21	6.16	8.28	5.270	0.400	0.250	75.3	18.2	3.49	9.77	3.71	1.26
× 18	5.26	8.14	5.250	0.330	0.230	61.9	15.2	3.43	7.97	3.04	1.23
× 15	4.44	8.11	4.015	0.315	0.245	48.0	11.8	3.29	3.41	1.70	0.876
× 13	3.84	7.99	4.000	0.255	0.230	39.6	9.91	3.21	2.73	1.37	0.843
× 10	2.96	7.89	3.940	0.205	0.170	30.8	7.81	3.22	2.09	1.06	0.841
W 6 × 25	7.34	6.38	6.080	0.455	0.320	53.4	16.7	2.70	17.1	5.61	1.52
× 20	5.87	6.20	6.020	0.365	0.260	41.4	13.4	2.66	13.3	4.41	1.50
× 16	4.74	6.28	4.030	0.405	0.260	32.1	10.2	2.60	4.43	2.20	0.966
× 15	4.43	5.99	5.990	0.260	0.230	29.1	9.72	2.56	9.32	3.11	1.46
× 12	3.55	6.03	4.000	0.280	0.230	22.1	7.31	2.49	2.99	1.50	0.918
× 9	2.68	5.90	3.940	0.215	0.170	16.4	5.56	2.47	2.19	1.11	0.905
W 5 × 19	5.54	5.15	5.030	0.430	0.270	26.2	10.2	2.17	9.13	3.63	1.28
× 16	4.68	5.01	5.000	0.360	0.240	21.3	8.51	2.13	7.51	3.00	1.27
W 4 × 13	3.83	4.16	4.060	0.345	0.280	11.3	5.46	1.72	3.86	1.90	1.00

Symbols: I = moment of inertia; S = section modulus; r = radius of gyration.

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Steel S Sections

"S" is the section symbol for "I" Beams. S shapes are designated, in order, by their section letter, actual depth in inches, and nominal weight in pounds per foot. Thus:

S 5 × 14.75

indicates an S shape (or I beam) having a depth of 5 inches and a nominal weight of 14.75 pounds per foot.



Designation	Area A inch^2	Depth, d inch	Flange: Width, b_f inch	Flange: Thickness, t_f inch	Web Thickness, t_w inch	Axis-X–X: I inch^4	Axis-X–X: S inch^3	Axis-X–X: r inch	Axis Y–Y: I inch^4	Axis Y–Y: S inch^3	Axis Y–Y: r inch
S 24 × 121	35.6	24.50	8.050	1.090	0.800	3160	258	9.43	83.3	20.7	1.53
× 106	31.2	24.50	7.870	1.090	0.620	2940	240	9.71	77.1	19.6	1.57
×100	29.3	24.00	7.245	0.870	0.745	2390	199	9.02	47.7	13.2	1.27
× 90	26.5	24.00	7.125	0.870	0.625	2250	187	9.21	44.9	12.6	1.30
× 80	23.5	24.00	7.000	0.870	0.500	2100	175	9.47	42.2	12.1	1.34
S 20 × 96	28.2	20.30	7.200	0.920	0.800	1670	165	7.71	50.2	13.9	1.33
× 86	25.3	20.30	7.060	0.920	0.660	1580	155	7.89	46.8	13.3	1.36
× 75	22.0	20.00	6.385	0.795	0.635	1280	128	7.62	29.8	9.32	1.16
× 66	19.4	20.00	6.255	0.795	0.505	1190	119	7.83	27.7	8.85	1.19
S 18 × 70	20.6	18.00	6.251	0.691	0.711	926	103	6.71	24.1	7.72	1.08
× 54.7	16.1	18.00	6.001	0.691	0.461	804	89.4	7.07	20.8	6.94	1.14
S 15 × 50	14.7	15.00	5.640	0.622	0.550	486	64.8	5.75	15.7	5.57	1.03
× 42.9	12.6	15.00	5.501	0.622	0.411	447	59.6	5.95	14.4	5.23	1.07
S 12 × 50	14.7	12.00	5.477	0.659	0.687	305	50.8	4.55	15.7	5.74	1.03
× 40.8	12.0	12.00	5.252	0.659	0.462	272	45.4	4.77	13.6	5.16	1.06
× 35	10.3	12.00	5.078	0.544	0.428	229	38.2	4.72	9.87	3.89	0.980
× 31.8	9.35	12.00	5.000	0.544	0.350	218	36.4	4.83	9.36	3.74	1.00
S 10 × 35	10.3	10.00	4.944	0.491	0.594	147	29.4	3.78	8.36	3.38	0.901
× 25.4	7.46	10.00	4.661	0.491	0.311	124	24.7	4.07	6.79	2.91	0.954
S 8 × 23	6.77	8.00	4.171	0.426	0.441	64.9	16.2	3.10	4.31	2.07	0.798
× 18.4	5.41	8.00	4.001	0.426	0.271	57.6	14.4	3.26	3.73	1.86	0.831
S 7 × 20	5.88	7.00	3.860	0.392	0.450	42.4	12.1	2.69	3.17	1.64	0.734
× 15.3	4.50	7.00	3.662	0.392	0.252	36.7	10.5	2.86	2.64	1.44	0.766
S 6 × 17.25	5.07	6.00	3.565	0.359	0.465	26.3	8.77	2.28	2.31	1.30	0.675
× 12.5	3.67	6.00	3.332	0.359	0.232	22.1	7.37	2.45	1.82	1.09	0.705
S 5 × 14.75	4.34	5.00	3.284	0.326	0.494	15.2	6.09	1.87	1.67	1.01	0.620
× 10	2.94	5.00	3.004	0.326	0.214	12.3	4.92	2.05	1.22	0.809	0.643
S 4 × 9.5	2.79	4.00	2.796	0.293	0.326	6.79	3.39	1.56	0.903	0.646	0.569
× 7.7	2.26	4.00	2.663	0.293	0.193	6.08	3.04	1.64	0.764	0.574	0.581
S 3 × 7.5	2.21	3.00	2.509	0.260	0.349	2.93	1.95	1.15	0.586	0.468	0.516
× 5.7	1.67	3.00	2.330	0.260	0.170	2.52	1.68	1.23	0.455	0.390	0.522

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. American Standard Steel Channels

American Standard Channels are designated, in order, by a section letter, actual depth in inches, and nominal weight per foot in pounds. Thus:

C 7 × 14.75

indicates an American Standard Channel with a depth of 7 inches and a nominal weight of 14.75 pounds per foot.



Designation	Area, A inch^2	Depth, d inch	Flange		Web	Axis X-X			Axis Y-Y			x inch
			Width, b_f inch	Thickness, t_f inch	Thickness, t_w inch	I inch^4	S inch^3	r inch	I inch^4	S inch^3	r inch	
C 15 × 50	14.7	15.00	3.716	0.650	0.716	404	53.8	5.24	11.0	3.78	0.867	0.798
× 40	11.8	15.00	3.520	0.650	0.520	349	46.5	5.44	9.23	3.37	0.886	0.777
× 33.9	9.96	15.00	3.400	0.650	0.400	315	42.0	5.62	8.13	3.11	0904	0.787
C 12 × 30	8.82	12.00	3.170	0.501	0.510	162	27.0	4.29	5.14	2.06	0.763	0.674
× 25	7.35	12.00	3.047	0.501	0.387	144	24.1	4.43	4.47	1.88	0.780	0.674
× 20.7	6.09	12.00	2.942	0.501	0.282	129	21.5	4.61	3.88	1.73	0.799	0.698
C 10 × 30	8.82	10.00	3.033	0.436	0.673	103	20.7	3.42	3.94	1.65	0.669	0.649
× 25	7.35	10.00	2.886	0.436	0.526	91.2	18.2	3.52	3.36	1.48	0.676	0.617
× 20	5.88	10.00	2.739	0.436	0.379	78.9	15.8	3.66	2.81	1.32	0.692	0.606
× 15.3	4.49	10.00	2.600	0.436	0.240	67.4	13.5	3.87	2.28	1.16	0.713	0.634
C 9 × 20	5.88	9.00	2.648	0.413	0.448	60.9	13.5	3.22	2.42	1.17	0.642	0.583
× 15	4.41	9.00	2.485	0.413	0.285	51.0	11.3	3.40	1.93	1.01	0.661	0.586
× 13.4	3.94	9.00	2.433	0.413	0.233	47.9	10.6	3.48	1.76	0.962	0.669	0.601
C 8 × 18.75	5.51	8.00	2.527	0.390	0.487	44.0	11.0	2.82	1.98	1.01	0.599	0.565
× 13.75	4.04	8.00	2.343	0.390	0.303	36.1	9.03	2.99	1.53	0.854	0.615	0.553
× 11.5	3.38	8.00	2.260	0.390	0.220	32.6	8.14	3.11	1.32	0.781	0.625	0.571
C 7 × 14.75	4.33	7.00	2.299	0.366	0.419	27.2	7.78	2.51	1.38	0.779	0.564	0.532
× 12.25	3.60	7.00	2.194	0.366	0.314	24.2	6.93	2.60	1.17	0.703	0.571	0.525
× 9.8	2.87	7.00	2.090	0.366	0.210	21.3	6.08	2.72	0.968	0.625	0.581	0.540
C 6 × 13	3.83	6.00	2.157	0.343	0.437	17.4	5.80	2.13	1.05	0.642	0.525	0.514
× 10.5	3.09	6.00	2.034	0.343	0.314	15.2	5.06	2.22	0.866	0.564	0.529	0.499
× 8.2	2.40	6.00	1.920	0.343	0.200	13.1	4.38	2.34	0.693	0.492	0.537	0.511
C 5 × 9	2.64	5.00	1.885	0.320	0.325	8.90	3.56	1.83	0.632	0.450	0.489	0.478
× 6.7	1.97	5.00	1.750	0.320	0.190	7.49	3.00	1.95	0.479	0.378	0.493	0.484
C 4 × 7.25	2.13	4.00	1.721	0.296	0.321	4.59	2.29	1.47	0.433	0.343	0.450	0.459
× 5.4	1.59	4.00	1.584	0.296	0.184	3.85	1.93	1.56	0.319	0.283	0.449	0.457
C 3 × 6	1.76	3.00	1.596	0.273	0.356	2.07	1.38	1.08	0.305	0.268	0.416	0.455
× 5	1.47	3.00	1.498	0.273	0.258	1.85	1.24	1.12	0.247	0.233	0.410	0.438
× 4.1	1.21	3.00	1.410	0.273	0.170	1.66	1.10	1.17	0.197	0.202	0.404	0.436

Symbols: I = moment of inertia; *S* = section modulus; *r* = radius of gyration; *x* = distance from center of gravity of section to outer face of structural shape.

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Steel Angles with Equal Legs

These angles are commonly designated by section symbol, width of each leg, and thickness, thus:

L 3 × 3 × ¼

indicates a 3 × 3-inch angle of ¼-inch thickness.



Size inch	Thickness inch	Weight per Foot lb.	Area inch²	Axis X–X & Y–Y			Z–Z
				I inch⁴	*r* inch	*x* or *y* inch	*r* inch
8 × 8	1⅛	56.9	16.7	98.0	2.42	2.41	1.56
	1	51.0	15.0	89.0	2.44	2.37	1.56
	⅞	45.0	13.2	79.6	2.45	2.32	1.57
	¾	38.9	11.4	69.7	2.47	2.28	1.58
	⅝	32.7	9.61	59.4	2.49	2.23	1.58
	9/16	29.6	8.68	54.1	2.50	2.21	1.59
	½	26.4	7.75	48.6	2.50	2.19	1.59
6 × 6	1	37.4	11.00	35.5	1.80	1.86	1.17
	⅞	33.1	9.73	31.9	1.81	1.82	1.17
	¾	28.7	8.44	28.2	1.83	1.78	1.17
	⅝	24.2	7.11	24.2	1.84	1.73	1.18
	9/16	21.9	6.43	22.1	1.85	1.71	1.18
	½	19.6	5.75	19.9	1.86	1.68	1.18
	7/16	17.2	5.06	17.7	1.87	1.66	1.19
	⅜	14.9	4.36	15.4	1.88	1.64	1.19
	5/16	12.4	3.65	13.0	1.89	1.62	1.20
5 × 5	⅞	27.2	7.98	17.8	1.49	1.57	.973
	¾	23.6	6.94	15.7	1.51	1.52	.975
	⅝	20.0	5.86	13.6	1.52	1.48	.978
	½	16.2	4.75	11.3	1.54	1.43	.983
	7/16	14.3	4.18	10.0	1.55	1.41	.986
	⅜	12.3	3.61	8.74	1.56	1.39	.990
	5/16	10.3	3.03	7.42	1.57	1.37	.994
4 × 4	¾	18.5	5.44	7.67	1.19	1.27	.778
	⅝	15.7	4.61	6.66	1.20	1.23	.779
	½	12.8	3.75	5.56	1.22	1.18	.782
	7/16	11.3	3.31	4.97	1.23	1.16	.785
	⅜	9.8	2.86	4.36	1.23	1.14	.788
	5/16	8.2	2.40	3.71	1.24	1.12	.791
	¼	6.6	1.94	3.04	1.25	1.09	.795
3½ × 3½	½	11.1	3.25	3.64	1.06	1.06	.683
	7/16	9.8	2.87	3.26	1.07	1.04	.684
	⅜	8.5	2.48	2.87	1.07	1.01	.687
	5/16	7.2	2.09	2.45	1.08	.990	.690
	¼	5.8	1.69	2.01	1.09	.968	.694
3 × 3	½	9.4	2.75	2.22	.898	.932	.584
	7/16	8.3	2.43	1.99	.905	.910	.585
	⅜	7.2	2.11	1.76	.913	.888	.587
	5/16	6.1	1.78	1.51	.922	.865	.589
	¼	4.9	1.44	1.24	.930	.842	.592
	3/16	3.71	1.09	.962	.939	.820	.596
2½ × 2½	½	7.7	2.25	1.23	.739	.806	.487
	⅜	5.9	1.73	.984	.753	.762	.487
	5/16	5.0	1.46	.849	.761	.740	.489
	¼	4.1	1.19	.703	.769	.717	.491
	3/16	3.07	.902	.547	.778	.694	.495
2 × 2	⅜	4.7	1.36	.479	.594	.636	.389
	5/16	3.92	1.15	.416	.601	.614	.390
	¼	3.19	.938	.348	.609	.592	.391
	3/16	2.44	.715	.272	.617	.569	.394
	⅛	1.65	.484	.190	.626	.546	.398

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Steel Angles with Unequal Legs

These angles are commonly designated by section symbol, width of each leg, and thickness, thus:

L 7 × 4 × ½

indicates a 7 × 4-inch angle of ½-inch thickness.



Size inch	Thickness inch	Weight per Ft. lb.	Area inch^2	Axis X–X				Axis Y–Y			Axis Z–Z		
				I inch^4	*S* inch^3	*r* inch	*y* inch	*I* inch^4	*S* inch^3	*r* inch	*x* inch	*r* inch	Tan *A*
9 × 4	5/8	26.3	7.73	64.9	11.5	2.90	3.36	8.32	2.65	1.04	.858	.847	.216
	9/16	23.8	7.00	59.1	10.4	2.91	3.33	7.63	2.41	1.04	.834	.850	.218
	1/2	21.3	6.25	53.2	9.34	2.92	3.31	6.92	2.17	1.05	.810	.854	.220
8 × 6	1	44.2	13.0	80.8	15.1	2.49	2.65	38.8	8.92	1.73	1.65	1.28	.543
	7/8	39.1	11.5	72.3	13.4	2.51	2.61	34.9	7.94	1.74	1.61	1.28	.547
	3/4	33.8	9.94	63.4	11.7	2.53	2.56	30.7	6.92	1.76	1.56	1.29	.551
	5/8	28.5	8.36	54.1	9.87	2.54	2.52	26.3	5.88	1.77	1.52	1.29	.554
	9/16	7	7.56	49.3	8.95	2.55	2.50	24.0	5.34	1.78	1.50	1.30	.556
	1/2	23.0	6.75	44.3	8.02	2.56	2.47	21.7	4.79	1.79	1.47	1.30	.558
	7/16	20.2	5.93	39.2	7.07	2.57	2.45	19.3	4.23	1.80	1.45	1.31	.560
8 × 4	1	37.4	11.0	69.6	14.1	2.52	3.05	11.6	3.94	1.03	1.05	.846	.247
	3/4	28.7	8.44	54.9	10.9	2.55	2.95	9.36	3.07	1.05	.953	.852	.258
	9/16	21.9	6.43	42.8	8.35	2.58	2.88	7.43	2.38	1.07	.882	.861	.265
	1/2	19.6	5.75	38.5	7.49	2.59	2.86	6.74	2.15	1.08	.859	.865	.267
7 × 4	3/4	26.2	7.69	37.8	8.42	2.22	2.51	9.05	3.03	1.09	1.01	.860	.324
	5/8	22.1	6.48	32.4	7.14	2.24	2.46	7.84	2.58	1.10	.963	.865	.329
	1/2	17.9	5.25	26.7	5.81	2.25	2.42	6.53	2.12	1.11	.917	.872	.335
	3/8	13.6	3.98	20.6	4.44	2.27	2.37	5.10	1.63	1.13	.870	.880	.340
6 × 4	7/8	27.2	7.98	27.7	7.15	1.86	2.12	9.75	3.39	1.11	1.12	.857	.421
	3/4	23.6	6.94	24.5	6.25	1.88	2.08	8.68	2.97	1.12	1.08	.860	.428
	5/8	20.0	5.86	21.1	5.31	1.90	2.03	7.52	2.54	1.13	1.03	.864	.435
	9/16	18.1	5.31	19.3	4.83	1.90	2.01	6.91	2.31	1.14	1.01	.866	.438
	1/2	16.2	4.75	17.4	4.33	1.91	1.99	6.27	2.08	1.15	.987	.870	.440
	7/16	14.3	4.18	15.5	3.83	1.92	1.96	5.60	1.85	1.16	.964	.873	.443
	3/8	12.3	3.61	13.5	3.32	1.93	1.94	4.90	1.60	1.17	.941	.877	.446
	5/16	10.3	3.03	11.4	2.79	1.94	1.92	4.18	1.35	1.17	.918	.882	.448
6 × 3½	1/2	15.3	4.50	16.6	4.24	1.92	2.08	4.25	1.59	.972	.833	.759	.344
	3/8	11.7	3.42	12.9	3.24	1.94	2.04	3.34	1.23	.988	.787	.676	.350
	5/16	9.8	2.87	10.9	2.73	1.95	2.01	2.85	1.04	.996	.763	.772	.352
5 × 3½	3/4	19.8	5.81	13.9	4.28	1.55	1.75	5.55	2.22	.977	.996	.748	.464
	5/8	16.8	4.92	12.0	3.65	1.56	1.70	4.83	1.90	.991	.951	.751	.472
	1/2	13.6	4.00	9.99	2.99	1.58	1.66	4.05	1.56	1.01	.906	.755	.479
	7/16	12.0	3.53	8.90	2.64	1.59	1.63	3.63	1.39	1.01	.883	.758	.482
	3/8	10.4	3.05	7.78	2.29	1.60	1.61	3.18	1.21	1.02	.861	.762	.486
	5/16	8.7	2.56	6.60	1.94	1.61	1.59	2.72	1.02	1.03	.838	.766	.489
	1/4	7.0	2.06	5.39	1.57	1.62	1.56	2.23	.830	1.04	.814	.770	.492
5 × 3	5/8	15.7	4.61	11.4	3.55	1.57	1.80	3.06	1.39	.815	.796	.644	.349
	1/2	12.8	3.75	9.45	2.91	1.59	1.75	2.58	1.15	.829	.750	.648	.357

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. *(Continued)* Steel Angles with Unequal Legs

Size inch	Thick-ness inch	Weight per Ft. lb.	Area inch^2	Axis X–X				Axis Y–Y			Axis Z–Z		
				I inch^4	*S* inch^3	*r* inch	*y* inch	*I* inch^4	*S* inch^3	*r* inch	*x* inch	*r* inch	Tan *A*
5 × 3	7/16	11.3	3.31	8.43	2.58	1.60	1.73	2.32	1.02	.837	.727	.651	.361
	3/8	9.8	2.86	7.37	2.24	1.61	1.70	2.04	.888	.845	.704	.654	.364
	5/16	8.2	2.40	6.26	1.89	1.61	1.68	1.75	.753	.853	.681	.658	.368
	1/4	6.6	1.94	5.11	1.53	1.62	1.66	1.44	.614	.861	.657	.663	.371
4 × 3½	5/8	14.7	4.30	6.37	2.35	1.22	1.29	4.52	1.84	1.03	1.04	.719	.745
	1/2	11.9	3.50	5.32	1.94	1.23	1.25	3.79	1.52	1.04	1.00	.722	.750
	7/16	10.6	3.09	4.76	1.72	1.24	1.23	3.40	1.35	1.05	.978	.724	.753
	3/8	9.1	2.67	4.18	1.49	1.25	1.21	2.95	1.17	1.06	.955	.727	.755
	5/16	7.7	2.25	3.56	1.26	1.26	1.18	2.55	.994	1.07	.932	.730	.757
	1/4	6.2	1.81	2.91	1.03	1.27	1.16	2.09	.808	1.07	.909	.734	.759
4 × 3	5/8	13.6	3.98	6.03	2.30	1.23	1.37	2.87	1.35	.849	.871	.637	.534
	1/2	11.1	3.25	5.05	1.89	1.25	1.33	2.42	1.12	.864	.827	.639	.543
	7/16	9.8	2.87	4.52	1.68	1.25	1.30	2.18	.992	.871	.804	.641	.547
	3/8	8.5	2.48	3.96	1.46	1.26	1.28	1.92	.866	.879	.782	.644	.551
	5/16	7.2	2.09	3.38	1.23	1.27	1.26	1.65	.734	.887	.759	.647	.554
	1/4	5.8	1.69	2.77	1.00	1.28	1.24	1.36	.599	.896	.736	.651	.558
3½ × 3	1/2	10.2	3.00	3.45	1.45	1.07	1.13	2.33	1.10	.881	.875	.621	.714
	7/16	9.1	2.65	3.10	1.29	1.08	1.10	2.09	.975	.889	.853	.622	.718
	3/8	7.9	2.30	2.72	1.13	1.09	1.08	1.85	.851	.897	.830	.625	.721
	5/16	6.6	1.93	2.33	.954	1.10	1.06	1.58	.722	.905	.808	.627	.724
	1/4	5.4	1.56	1.91	.776	1.11	1.04	1.30	.589	.914	.785	.631	.727
3½ × 2½	1/2	9.4	2.75	3.24	1.41	1.09	1.20	1.36	.760	.704	.705	.534	.486
	7/16	8.3	2.43	2.91	1.26	1.09	1.18	1.23	.677	.711	.682	.535	.491
	3/8	7.2	2.11	2.56	1.09	1.10	1.16	1.09	.592	.719	.660	.537	.496
	5/16	6.1	1.78	2.19	.927	1.11	1.14	.939	.504	.727	.637	.540	.501
	1/4	4.9	1.44	1.80	.755	1.12	1.11	.777	.412	.735	.614	.544	.506
3 × 2½	1/2	8.5	2.50	2.08	1.04	.913	1.00	1.30	.744	.722	.750	.520	.667
	7/16	7.6	2.21	1.88	.928	.920	.978	1.18	.664	.729	.728	.521	.672
	3/8	6.6	1.92	1.66	.810	.928	.956	1.04	.581	.736	.706	.522	.676
	5/16	5.6	1.62	1.42	.688	.937	.933	.898	.494	.744	.683	.525	.680
	1/4	4.5	1.31	1.17	.561	.945	.911	.743	.404	.753	.661	.528	.684
	3/16	3.39	.996	.907	.430	.954	.888	.577	.310	.761	.638	.533	.688
3 × 2	1/2	7.7	2.25	1.92	1.00	.924	1.08	.672	.474	.546	.583	.428	.414
	7/16	6.8	2.00	1.73	.894	.932	1.06	.609	.424	.553	.561	.429	.421
	3/8	5.9	1.73	1.53	.781	.940	1.04	.543	.371	.559	.539	.430	.428
	5/16	5.0	1.46	1.32	.664	.948	1.02	.740	.317	.567	.516	.432	.435
	1/4	4.1	1.19	1.09	.542	.957	.993	.392	.260	.574	.493	.435	.440
	3/16	3.07	.902	.842	.415	.966	.970	.307	.200	.583	.470	.439	.446
2½ × 2	3/8	5.3	1.55	.912	.547	.768	.831	.514	.363	.577	.581	.420	.614
	5/16	4.5	1.31	.788	.466	.776	.809	.446	.310	.584	.559	.422	.620
	1/4	3.62	1.06	.654	.381	.784	.787	.372	.254	.592	.537	.424	.626
	3/16	2.75	.809	.509	.293	.793	.764	.291	.196	.600	.514	.427	.631

Symbols: I = moment of inertia; *S* = section modulus; *r* = radius of gyration; *x* = distance from center of gravity of section to outer face of structural shape.

Data taken from the "Manual of Steel Construction," 8th Edition, 1980, with permission of the American Institute of Steel Construction.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Aluminum Association Standard Structural Shapes



Depth	Width	Weight per Foot	Area	Flange Thickness	Web Thickness	Fillet Radius	Axis *X–X*			Axis *Y–Y*			
							I	*S*	*r*	*I*	*S*	*r*	*x*
inch	inch	lb.	inch^2	inch	inch	inch	inch^4	inch^3	inch	inch^4	inch^3	inch	inch
I-BEAMS													
3.00	2.50	1.637	1.392	0.20	0.13	0.25	2.24	1.49	1.27	0.52	0.42	0.61	…
3.00	2.50	2.030	1.726	0.26	0.15	0.25	2.71	1.81	1.25	0.68	0.54	0.63	…
4.00	3.00	2.311	1.965	0.23	0.15	0.25	5.62	2.81	1.69	1.04	0.69	0.73	…
4.00	3.00	2.793	2.375	0.29	0.17	0.25	6.71	3.36	1.68	1.31	0.87	0.74	…
5.00	3.50	3.700	3.146	0.32	0.19	0.30	13.94	5.58	2.11	2.29	1.31	0.85	…
6.00	4.00	4.030	3.427	0.29	0.19	0.30	21.99	7.33	2.53	3.10	1.55	0.95	…
6.00	4.00	4.692	3.990	0.35	0.21	0.30	25.50	8.50	2.53	3.74	1.87	0.97	…
7.00	4.50	5.800	4.932	0.38	0.23	0.30	42.89	12.25	2.95	5.78	2.57	1.08	…
8.00	5.00	6.181	5.256	0.35	0.23	0.30	59.69	14.92	3.37	7.30	2.92	1.18	…
8.00	5.00	7.023	5.972	0.41	0.25	0.30	67.78	16.94	3.37	8.55	3.42	1.20	…
9.00	5.50	8.361	7.110	0.44	0.27	0.30	102.02	22.67	3.79	12.22	4.44	1.31	…
10.00	6.00	8.646	7.352	0.41	0.25	0.40	132.09	26.42	4.24	14.78	4.93	1.42	…
10.00	6.00	10.286	8.747	0.50	0.29	0.40	155.79	31.16	4.22	18.03	6.01	1.44	…
12.00	7.00	11.672	9.925	0.47	0.29	0.40	255.57	42.60	5.07	26.90	7.69	1.65	…
12.00	7.00	14.292	12.153	0.62	0.31	0.40	317.33	52.89	5.11	35.48	10.14	1.71	…
CHANNELS													
2.00	1.00	0.577	0.491	0.13	0.13	0.10	0.288	0.288	0.766	0.045	0.064	0.303	0.298
2.00	1.25	1.071	0.911	0.26	0.17	0.15	0.546	0.546	0.774	0.139	0.178	0.391	0.471
3.00	1.50	1.135	0.965	0.20	0.13	0.25	1.41	0.94	1.21	0.22	0.22	0.47	0.49
3.00	1.75	1.597	1.358	0.26	0.17	0.25	1.97	1.31	1.20	0.42	0.37	0.55	0.62
4.00	2.00	1.738	1.478	0.23	0.15	0.25	3.91	1.95	1.63	0.60	0.45	0.64	0.65
4.00	2.25	2.331	1.982	0.29	0.19	0.25	5.21	2.60	1.62	1.02	0.69	0.72	0.78
5.00	2.25	2.212	1.881	0.26	0.15	0.30	7.88	3.15	2.05	0.98	0.64	0.72	0.73
5.00	2.75	3.089	2.627	0.32	0.19	0.30	11.14	4.45	2.06	2.05	1.14	0.88	0.95
6.00	2.50	2.834	2.410	0.29	0.17	0.30	14.35	4.78	2.44	1.53	0.90	0.80	0.79
6.00	3.25	4.030	3.427	0.35	0.21	0.30	21.04	7.01	2.48	3.76	1.76	1.05	1.12
7.00	2.75	3.205	2.725	0.29	0.17	0.30	22.09	6.31	2.85	2.10	1.10	0.88	0.84
7.00	3.50	4.715	4.009	0.38	0.21	0.30	33.79	9.65	2.90	5.13	2.23	1.13	1.20
8.00	3.00	4.147	3.526	0.35	0.19	0.30	37.40	9.35	3.26	3.25	1.57	0.96	0.93
8.00	3.75	5.789	4.923	0.471	0.25	0.35	52.69	13.17	3.27	7.13	2.82	1.20	1.22
9.00	3.25	4.983	4.237	0.35	0.23	0.35	54.41	12.09	3.58	4.40	1.89	1.02	0.93
9.00	4.00	6.970	5.927	0.44	0.29	0.35	78.31	17.40	3.63	9.61	3.49	1.27	1.25
10.00	3.50	6.136	5.218	0.41	0.25	0.35	83.22	16.64	3.99	6.33	2.56	1.10	1.02
10.00	4.25	8.360	7.109	0.50	0.31	0.40	116.15	23.23	4.04	13.02	4.47	1.35	1.34
12.00	4.00	8.274	7.036	0.47	0.29	0.40	159.76	26.63	4.77	11.03	3.86	1.25	1.14
12.00	5.00	11.822	10.053	0.62	0.35	0.45	239.69	39.95	4.88	25.74	7.60	1.60	1.61

Structural sections are available in 6061-T6 aluminum alloy. Data supplied by The Aluminum Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Wire and Sheet-Metal Gages

The thicknesses of sheet metals and the diameters of wires conform to various gaging systems. These gage sizes are indicated by numbers, and the following tables give the decimal equivalents of the different gage numbers. Much confusion has resulted from the use of gage numbers, and in ordering materials it is preferable to give the exact dimensions in decimal fractions of an inch. While the dimensions thus specified should conform to the gage ordinarily used for a given class of material, any error in the specification due, for example, to the use of a table having "rounded off" or approximate equivalents, will be apparent to the manufacturer at the time the order is placed. Furthermore, the decimal method of indicating wire diameters and sheet metal thicknesses has the advantage of being self-explanatory, whereas arbitrary gage numbers are not. The decimal system of indicating gage sizes is now being used quite generally, and gage numbers are gradually being discarded. Unfortunately, there is considerable variation in the use of different gages. For example, a gage ordinarily used for copper, brass and other non-ferrous materials, may at times be used for steel, and vice versa. The gages specified in the following are the ones ordinarily employed for the materials mentioned, but there are some minor exceptions and variations in the different industries.

Wire Gages.— The wire gage system used by practically all of the steel producers in the United States is known by the name Steel Wire Gage or to distinguish it from the Standard Wire Gage (S.W.G.) used in Great Britain it is called the United States Steel Wire Gage. It is the same as the Washburn and Moen, American Steel and Wire Company, and Roebling Wire Gages. The name has the official sanction of the Bureau of Standards at Washington but is not legally effective. The only wire gage which has been recognized in Acts of Congress is the Birmingham Gage (also known as Stub's Iron Wire). The Birmingham Gage is, however, nearly obsolete in both the United States and Great Britain, where it originated. Copper and aluminum wires are specified in decimal fractions. They were formerly universally specified in the United States by the American or Brown & Sharpe Wire Gage. Music spring steel wire, one of the highest quality wires of several types used for mechanical springs, is specified by the piano or music wire gage.

In Great Britain one wire gage has been legalized. This is called the Standard Wire Gage (S.W.G.), formerly called Imperial Wire Gage.

Gages for Rods.— Steel wire rod sizes are designated by fractional or decimal parts of an inch and by the gage numbers of the United States Steel Wire Gage. Copper and aluminum rods are specified by decimal fractions and fractions. Drill rod may be specified in decimal fractions but in the carbon and alloy tool steel grades may also be specified in the Stub's Steel Wire Gage and in the high-speed steel drill rod grade may be specified by the Morse Twist Drill Gage (Manufacturers' Standard Gage for Twist Drills). For gage numbers with corresponding decimal equivalents see the tables of American Standard Straight Shank Twist Drills, for example, page 856, and Table 5a on page 2525.

Gages for Wall Thicknesses of Tubing.— At one time the Birmingham or Stub's Iron Wire Gage was used to specify the wall thickness of the following classes of tubing: seamless brass, seamless copper, seamless steel, and aluminum. The Brown & Sharpe Wire Gage was used for brazed brass and brazed copper tubing. Wall thicknesses are now specified by decimal parts of an inch but the wall thickness of steel pressure tubes and steel mechanical tubing may be specified by the Birmingham or Stub's Iron Wire Gage. In Great Britain the Standard Wire Gage (S.W.G.) is used to specify the wall thickness of some kinds of steel tubes.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Wire Gages in Approximate Decimals of an Inch

No. of Wire Gage	American Wire or Brown & Sharpe Gage	Steel Wire Gage (U.S.)[a]	British Standard Wire Gage (Imperial Wire Gage)	Music or Piano Wire Gage	Birmingham or Stub's Iron Wire Gage	Stub's Steel Wire Gage	No. of Wire Gage	Stub's Steel Wire Gage
7/0	…	0.4900	0.5000	…	…	…	51	0.066
6/0	0.5800	0.4615	0.4640	0.004	…	…	52	0.063
5/0	0.5165	0.4305	0.4320	0.005	0.5000	…	53	0.058
4/0	0.4600	0.3938	0.4000	0.006	0.4540	…	54	0.055
3/0	0.4096	0.3625	0.3720	0.007	0.4250	…	55	0.050
2/0	0.3648	0.3310	0.3480	0.008	0.3800	…	56	0.045
1/0	0.3249	0.3065	0.3240	0.009	0.3400	…	57	0.042
1	0.2893	0.2830	0.3000	0.010	0.3000	0.227	58	0.041
2	0.2576	0.2625	0.2760	0.011	0.2840	0.219	59	0.040
3	0.2294	0.2437	0.2520	0.012	0.2590	0.212	60	0.039
4	0.2043	0.2253	0.2320	0.013	0.2380	0.207	61	0.038
5	0.1819	0.2070	0.2120	0.014	0.2200	0.204	62	0.037
6	0.1620	0.1920	0.1920	0.016	0.2030	0.201	63	0.036
7	0.1443	0.1770	0.1760	0.018	0.1800	0.199	64	0.035
8	0.1285	0.1620	0.1600	0.020	0.1650	0.197	65	0.033
9	0.1144	0.1483	0.1440	0.022	0.1480	0.194	66	0.032
10	0.1019	0.1350	0.1280	0.024	0.1340	0.191	67	0.031
11	0.0907	0.1205	0.1160	0.026	0.1200	0.188	68	0.030
12	0.0808	0.1055	0.1040	0.029	0.1090	0.185	69	0.029
13	0.0720	0.0915	0.0920	0.031	0.0950	0.182	70	0.027
14	0.0641	0.0800	0.0800	0.033	0.0830	0.180	71	0.026
15	0.0571	0.0720	0.0720	0.035	0.0720	0.178	72	0.024
16	0.0508	0.0625	0.0640	0.037	0.0650	0.175	73	0.023
17	0.0453	0.0540	0.0560	0.039	0.0580	0.172	74	0.022
18	0.0403	0.0475	0.0480	0.041	0.0490	0.168	75	0.020
19	0.0359	0.0410	0.0400	0.043	0.0420	0.164	76	0.018
20	0.0320	0.0348	0.0360	0.045	0.0350	0.161	77	0.016
21	0.0285	0.0318	0.0320	0.047	0.0320	0.157	78	0.015
22	0.0253	0.0286	0.0280	0.049	0.0280	0.155	79	0.014
23	0.0226	0.0258	0.0240	0.051	0.0250	0.153	80	0.013
24	0.0201	0.0230	0.0220	0.055	0.0220	0.151	…	…
25	0.0179	0.0204	0.0200	0.059	0.0200	0.148	…	…
26	0.0159	0.0181	0.0180	0.063	0.0180	0.146	…	…
27	0.0142	0.0173	0.0164	0.067	0.0160	0.143	…	…
28	0.0126	0.0162	0.0149	0.071	0.0140	0.139	…	…
29	0.0113	0.0150	0.0136	0.075	0.0130	0.134	…	…
30	0.0100	0.0140	0.0124	0.080	0.0120	0.127	…	…
31	0.00893	0.0132	0.0116	0.085	0.0100	0.120	…	…
32	0.00795	0.0128	0.0108	0.090	0.0090	0.115	…	…
33	0.00708	0.0118	0.0100	0.095	0.0080	0.112	…	…
34	0.00630	0.0104	0.0092	0.100	0.0070	0.110	…	…
35	0.00561	0.0095	0.0084	0.106	0.0050	0.108	…	…
36	0.00500	0.0090	0.0076	0.112	0.0040	0.106	…	…
37	0.00445	0.0085	0.0068	0.118	…	0.103	…	…
38	0.00396	0.0080	0.0060	0.124	…	0.101	…	…
39	0.00353	0.0075	0.0052	0.130	…	0.099	…	…
40	0.00314	0.0070	0.0048	0.138	…	0.097	…	…
41	0.00280	0.0066	0.0044	0.146	…	0.095	…	…
42	0.00249	0.0062	0.0040	0.154	…	0.092	…	…
43	0.00222	0.0060	0.0036	0.162	…	0.088	…	…
44	0.00198	0.0058	0.0032	0.170	…	0.085	…	…
45	0.00176	0.0055	0.0028	0.180	…	0.081	…	…
46	0.00157	0.0052	0.0024	…	…	0.079	…	…
47	0.00140	0.0050	0.0020	…	…	0.077	…	…
48	0.00124	0.0048	0.0016	…	…	0.075	…	…
49	0.00111	0.0046	0.0012	…	…	0.072	…	…
50	0.00099	0.0044	0.0010	…	…	0.069	…	…

[a] Also known as Washburn and Moen, American Steel and Wire Co. and Roebling Wire Gages. A greater selection of sizes is available and is specified by what are known as split gage numbers. They can be recognized by ½ fractions which follow the gage number; i.e., 4½. The decimal equivalents of split gage numbers are in the Steel Products Manual entitled: *Wire and Rods, Carbon Steel* published by the American Iron and Steel Institute, Washington, DC.

Copyright 2004, Industrial Press, Inc., New York, NY

Strength and Stiffness of Perforated Metals.— It is common practice to use perforated metals in equipment enclosures to provide cooling by the flow of air or fluids. If the perforated material is to serve also as a structural member, then calculations of stiffness and strength must be made that take into account the effect of the perforations on the strength of the panels.

The accompanying table provides equivalent or effective values of the yield strength S^*; modulus of elasticity E^*; and Poisson's ratio ν^* of perforated metals in terms of the values for solid material. The S^*/S and E^*/E ratios, given in the accompanying table for the standard round hole staggered pattern, can be used to determine the safety margins or deflections for perforated metal use as compared to the unperforated metal for any geometry or loading condition.

Perforated material has different strengths depending on the direction of loading; therefore, values of S^*/S in the table are given for the width (strongest) and length (weakest) directions. Also, the effective elastic constants are for plane stress conditions and apply to the in-plane loading of thin perforated sheets; the bending stiffness is greater. However, since most loading conditions involve a combination of bending and stretching, it is more convenient to use the same effective elastic constants for these combined loading conditions. The plane stress effective elastic constants given in the table can be conservatively used for all loading conditions.

Mechanical Properties of Materials Perforated with Round Holes in IPA Standard Staggered Hole Pattern



IPA No.	Perforation Diam. (in.)	Center Distance (in.)	Open Area (%)	S^*/S Width (in.)	S^*/S Length (in.)	E^*/E	ν^*
100	0.020	(625)	20	0.530	0.465	0.565	0.32
106	1/16	1/8	23	0.500	0.435	0.529	0.33
107	5/64	7/64	46	0.286	0.225	0.246	0.38
108	5/64	1/8	36	0.375	0.310	0.362	0.35
109	3/32	5/32	32	0.400	0.334	0.395	0.34
110	3/32	3/16	23	0.500	0.435	0.529	0.33
112	1/10	5/32	36	0.360	0.296	0.342	0.35
113	1/8	3/16	40	0.333	0.270	0.310	0.36
114	1/8	7/32	29	0.428	0.363	0.436	0.33
115	1/8	1/4	23	0.500	0.435	0.529	0.33
116	5/32	7/32	46	0.288	0.225	0.249	0.38
117	5/32	1/4	36	0.375	0.310	0.362	0.35
118	3/16	1/4	51	0.250	0.192	0.205	0.42
119	3/16	5/16	33	0.400	0.334	0.395	0.34
120	1/4	5/16	58	0.200	0.147	0.146	0.47
121	1/4	3/8	40	0.333	0.270	0.310	0.36
122	1/4	7/16	30	0.428	0.363	0.436	0.33
123	1/4	1/2	23	0.500	0.435	0.529	0.33
124	3/8	1/2	51	0.250	0.192	0.205	0.42
125	3/8	9/16	40	0.333	0.270	0.310	0.36
126	3/8	5/8	33	0.400	0.334	0.395	0.34
127	7/16	5/8	45	0.300	0.239	0.265	0.38
128	1/2	11/16	47	0.273	0.214	0.230	0.39
129	9/16	3/4	51	0.250	0.192	0.205	0.42

Value in parentheses specifies holes per square inch instead of center distance. S^*/S = ratio of yield strength of perforated to unperforated material; E^*/E = ratio of modulus of elasticity of perforated to unperforated material; ν^* = Poisson's ratio for given percentage of open area.

IPA is Industrial Perforators Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Sheet-Metal Gages.— Thicknesses of steel sheets given in Table 2 are based upon a weight of 41.82 pounds per square foot per inch of thickness, which is known as the Manufacturers' Standard Gage for Sheet Steel. This gage differs from the older United States Standard Gage for iron and steel sheets and plates, established by Congress in 1893, based upon a weight of 40 pounds per square foot per inch of thickness which is the weight of wrought-iron plate.

Table 2. Sheet-Metal Gages in Approximate Decimals of an Inch

Gage No.	Steel Gage[a]	B.G.[b]	Galvanized Sheet	Zinc Gage	Gage No.	Steel Gage[a]	B.G.[b]	Galvanized Sheet	Zinc Gage
15/0	…	1.000	…	…	20	0.0359	0.0392	0.0396	0.070
14/0	…	0.9583	…	…	21	0.0329	0.0349	0.0366	0.080
13/0	…	0.9167	…	…	22	0.0299	0.03125	0.0336	0.090
12/0	…	0.8750	…	…	23	0.0269	0.02782	0.0306	0.100
11/0	…	0.8333	…	…	24	0.0239	0.02476	0.0276	0.125
10/0	…	0.7917	…	…	25	0.0209	0.02204	0.0247	…
9/0	…	0.7500	…	…	26	0.0179	0.01961	0.0217	…
8/0	…	0.7083	…	…	27	0.0164	0.01745	0.0202	…
7/0	…	0.6666	…	…	28	0.0149	0.01562	0.0187	…
6/0	…	0.6250	…	…	29	0.0135	0.01390	0.0172	…
5/0	…	0.5883	…	…	30	0.0120	0.01230	0.0157	…
4/0	…	0.5416	…	…	31	0.0105	0.01100	0.0142	…
3/0	…	0.5000	…	…	32	0.0097	0.00980	0.0134	…
2/0	…	0.4452	…	…	33	0.0090	0.00870	…	…
1/0	…	0.3964	…	…	34	0.0082	0.00770	…	…
1	…	0.3532	…	…	35	0.0075	0.00690	…	…
2	…	0.3147	…	…	36	0.0067	0.00610	…	…
3	0.2391	0.2804	…	0.006	37	0.0064	0.00540	…	…
4	0.2242	0.2500	…	0.008	38	0.0060	0.00480	…	…
5	0.2092	0.2225	…	0.010	39	…	0.00430	…	…
6	0.1943	0.1981	…	0.012	40	…	0.00386	…	…
7	0.1793	0.1764	…	0.014	41	…	0.00343	…	…
8	0.1644	0.1570	0.1681	0.016	42	…	0.00306	…	…
9	0.1495	0.1398	0.1532	0.018	43	…	0.00272	…	…
10	0.1345	0.1250	0.1382	0.020	44	…	0.00242	…	…
11	0.1196	0.1113	0.1233	0.024	45	…	0.00215	…	…
12	0.1046	0.0991	0.1084	0.028	46	…	0.00192	…	…
13	.0897	0.0882	0.0934	0.032	47	…	0.00170	…	…
14	0.0747	0.0785	0.0785	0.036	48	…	0.00152	…	…
15	0.0673	0.0699	0.0710	0.040	49	…	0.00135	…	…
16	0.0598	0.0625	0.0635	0.045	50	…	0.00120	…	…
17	0.0538	0.0556	0.0575	0.050	51	…	0.00107	…	…
18	.0478	0.0495	0.0516	0.055	52	…	0.00095	…	…
19	0.0418	0.0440	0.0456	0.060	…	…	…	…	…

[a] Manufacturers' Standard Gage for Sheet Steel

[b] B.G. is the Birmingham Gage for sheets and hoops.

The United States Standard Gage (not shown above) for iron and steel sheets and plates was established by Congress in 1893 and was primarily a *weight* gage rather than a thickness gage. The equivalent thicknesses were derived from the weight of wrought iron. The weight per cubic foot was taken at 480 pounds, thus making the weight of a plate 12 inches square and 1 inch thick, 40 pounds. In converting weight to equivalent thickness, gage tables formerly published contained thicknesses equivalent to the basic weights just mentioned. For example, a No. 3 U.S. gage represents a wrought-iron plate having a weight of 10 pounds per square foot; hence, if the weight per square foot per inch thick is 40 pounds, the plate thickness for a No. 3 gage = 10 ÷ 40 = 0.25 inch, which was the original thickness equivalent for this gage number. Because this and the other thickness equivalents were derived from the weight of wrought iron, they are not correct for steel.

Copyright 2004, Industrial Press, Inc., New York, NY

Zinc sheets are usually ordered by specifying decimal thickness although a zinc gage exists and is shown in Table 2.

Most sheet-metal products in Great Britain are specified by the British Standard Wire Gage (Imperial Wire Gage). Black iron and steel sheet and hooping, and galvanized flat and corrugated steel sheet, however, are specified by the Birmingham Gage (B.G.), which was legalized in 1914, and are also shown in Table 2. This Birmingham Gage should not be confused with the Birmingham or Stub's Iron Wire Gage mentioned previously.

Thicknesses of aluminum, copper, and copper-base alloys were formerly designated by the American or Brown & Sharpe Wire Gage but now are specified in decimals or fractions of an inch. American National Standard B32.1-1952 (R1988) entitled Preferred Thicknesses for Uncoated Thin Flat Metals (see accompanying Table 3) gives thicknesses that are based on the 20- and 40-series of preferred numbers in American National Standard Preferred Numbers — ANSI Z17.1 (see Handbook page 689) and are applicable to uncoated, thin, flat metals and alloys. Each number of the 20-series is approximately 12 percent greater than the next smaller one and each number of the 40-series is approximately 6 percent greater than the next smaller one.

Table 3. Preferred Thicknesses for Uncoated Metals and Alloys— Under 0.250 Inch in Thickness *ANSI B32.1-1952 (R1994)*

Preferred Thickness, Inches							
Based on 20-Series	Based on 40-Series	Based on 20-Series	Based on 40-Series	Based on 20-Series	Based on 40-Series	Based on 20-Series	Based on 40-Series
…	0.236	0.100	0.100	…	0.042	0.018	0.018
0.224	0.224	…	0.095	0.040	0.040	…	0.017
…	0.212	0.090	0.090	…	0.038	0.016	0.016
0.200	0.200	…	0.085	0.036	0.036	…	0.015
…	0.190	0.080	0.080	…	0.034	0.014	0.014
0.180	0.180	…	0.075	0.032	0.032	…	0.013
…	0.170	0.071	0.071	…	0.030	0.012	0.012
0.160	0.160	…	0.067	0.028	0.028	0.011	0.011
…	0.150	0.063	0.063	…	0.026	0.010	0.010
0.140	0.140	…	0.060	0.025	0.025	0.009	0.009
…	0.132	0.056	0.056	…	0.024	0.008	0.008
0.125	0.125	…	0.053	0.022	0.022	0.007	0.007
…	0.118	0.050	0.050	…	0.021	0.006	0.006
0.112	0.112	…	0.048	0.020	0.020	0.005	0.005
…	0.106	0.045	0.045	…	0.019	0.004	0.004

The American National Standard ANSI B32.1-1952 (R1994) lists preferred thicknesses that are based on the 20- and 40-series of preferred numbers and states that those based on the 40-series should provide adequate coverage. However, where intermediate thicknesses are required, the Standard recommends that thicknesses be based on the 80-series of preferred numbers (see Handbook page 689).

Thicknesses for copper and copper-base alloy flat products below $\frac{1}{4}$ inch thick are specified by the 20-series of American National Standard Preferred Numbers given in ANSI B32.1. Although the table in ANSI B32.1 gives only the 20- and 40-series of numbers, it states that when intermediate thicknesses are required they should be selected from thicknesses based on the 80-series of numbers (see Handbook page 689).

Metric Sizes for Flat Metal Products.— American National Standard B32.3M-1984, (R1994) establishes a preferred series of metric thicknesses, widths, and lengths for flat metal products of rectangular cross section; the thickness and width values are also applicable to base metals that may be coated in later operations. Table 4a lists the preferred thicknesses; Table 4b lists the preferred widths. Whenever possible, the Preferred Thick-

Copyright 2004, Industrial Press, Inc., New York, NY

ness and Preferred Widths values should be used, with the Second or Third Preference chosen only if no suitable Preferred size is available. Since not all metals and grades are produced in each of the sizes given in Tables 4a and 4b, producers or distributors should be consulted to determine a particular product and size combination's availability.

Table 4a. Preferred Metric Thicknesses for All Flat Metal Products
ANSI/ASME B32.3M-1984 (R1994)

Preferred Thickness	Second Preference	Third Preference	Preferred Thickness	Second Preference	Third Preference	Preferred Thickness	Second Preference	Third Preference
0.050	…	…	…	…	1.5	12	…	…
0.060	…	…	1.6	…	…	…	14	…
0.080	…	…	…	…	1.7	16	…	…
0.10	…	…	…	1.8	…	…	18	…
0.12	…	…	…	…	1.9	20	…	…
…	0.14	…	2.0	…	…	…	22	…
0.16	…	…	…	…	2.1	25	…	…
…	0.18	…	…	2.2	…	…	28	…
0.20	…	…	…	…	2.4	30	…	…
…	0.22	…	2.5	…	…	…	32	…
0.25	…	…	…	…	2.6	35	…	…
…	0.28	…	…	2.8	…	…	38	…
0.30	…	…	3.0	…	…	40	…	…
…	0.35	…	…	3.2	…	…	45	…
0.40	…	…	…	…	3.4	50	…	…
…	0.45	…	3.5	…	…	…	55	…
0.50	…	…	…	…	3.6	60	…	…
…	0.55	…	…	3.8	…	…	70	…
0.60	…	…	4.0	…	…	80	…	…
…	0.65	…	…	4.2	…	…	90	…
…	0.70	…	…	4.5	…	100	…	…
…	…	0.75	…	4.8	…	…	110	…
0.80	…	…	5.0	…	…	120	…	…
…	…	0.85	…	5.5	…	…	130	…
…	0.90	…	6.0	…	…	140	…	…
…	…	0.95	…	…	6.5	…	150	…
1.0	…	…	…	7.0	…	160	…	…
…	…	1.05	…	…	7.5	180	…	…
…	1.1	…	8.0	…	…	200	…	…
1.2	…	…	…	9.0	…	250	…	…
…	…	1.3	10	…	…	300	…	…
…	1.4	…	…	11	…			

Table 4b. Preferred Metric Widths[a] for All Flat Metal Products

Preferred Widths	Second Preference	Preferred Widths	Second Preference	Preferred Widths	Second Preference	Preferred Widths	Second Preference
10	…	60	…	180	…	…	900
12	…	…	70	200	…	1000	…
16	…	80	…	…	225	1200	…
20	…	…	90	250	…	1500	…
25	…	100	…	…	280	2000	…
30	…	…	110	300	…	2500	…
35	…	120	…	400	…	3000	…
40	…	…	130	500	…	3500	…
…	45	140	…	600	…	4000	…
50	…	…	150	…	700	5000	…
…	55	160	…	800	…	…	…

[a] These widths are applicable to bar, foil, flat wire, plate,ribbon, sheet, strip, etc. only where the width falls within the 100 to 500 mm range.

All dimensions are in millimeters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5a. Decimal Equivalent of Numbered Drill Sizes

Drill Number	Decimal		Drill Number	Decimal		Drill Number	Decimal		Drill Number	Decimal	
	Inch	mm		Inch	mm		Inch	mm		Inch	mm
1	0.2280	5.791	26	0.1470	3.734	51	0.0670	1.702	76	0.0200	0.508
2	0.2210	5.613	27	0.1440	3.658	52	0.0635	1.613	77	0.0180	0.457
3	0.2130	5.410	28	0.1405	3.569	53	0.0595	1.511	78	0.0160	0.406
4	0.2090	5.309	29	0.1360	3.454	54	0.0550	1.397	79	0.0145	0.368
5	0.2055	5.220	30	0.1285	3.264	55	0.0520	1.321	80	0.0135	0.343
6	0.2040	5.182	31	0.1200	3.048	56	0.0465	1.181	81	0.0130	0.330
7	0.2010	5.105	32	0.1160	2.946	57	0.0430	1.092	82	0.0125	0.318
8	0.1990	5.054	33	0.1130	2.870	58	0.0420	1.067	83	0.0120	0.305
9	0.1960	4.978	34	0.1110	2.819	59	0.0410	1.041	84	0.0115	0.292
10	0.1935	4.915	35	0.1100	2.794	60	0.0400	1.016	85	0.0110	0.280
11	0.1910	4.851	36	0.1065	2.705	61	0.0390	0.991	86	0.0105	0.267
12	0.1890	4.800	37	0.1040	2.642	62	0.0380	0.965	87	0.0100	0.254
13	0.1850	4.700	38	0.1015	2.578	63	0.0370	0.940	88	0.0095	0.241
14	0.1820	4.623	39	0.0995	2.527	64	0.0360	0.914	89	0.0091	0.231
15	0.1800	4.572	40	0.0980	2.489	65	0.0350	0.889	90	0.0087	0.221
16	0.1770	4.496	41	0.0960	2.438	66	0.0330	0.838	91	0.0083	0.211
17	0.1730	4.394	42	0.0935	2.375	67	0.0320	0.813	92	0.0079	0.200
18	0.1695	4.305	43	0.0890	2.261	68	0.0310	0.787	93	0.0075	0.190
19	0.1660	4.216	44	0.0860	2.184	69	0.0292	0.742	94	0.0071	0.180
20	0.1610	4.089	45	0.0820	2.083	70	0.0280	0.711	95	0.0067	0.170
21	0.1590	4.039	46	0.0810	2.057	71	0.0260	0.660	96	0.0063	0.160
22	0.1570	3.988	47	0.0785	1.994	72	0.0250	0.635	97	0.0059	0.150
23	0.1540	3.912	48	0.0760	1.930	73	0.0240	0.610	…	…	…
24	0.1520	3.861	49	0.0730	1.854	74	0.0225	0.572	…	…	…
25	0.1495	3.797	50	0.0700	1.778	75	0.0210	0.533	…	…	…

Table 5b. Decimal Equivalent of Letter Drill Sizes

Drill Size	Decimal		Drill Size	Decimal		Drill Size	Decimal		Drill Size	Decimal		Drill Size	Decimal	
	Inch	mm		Inch	mm		Inch	mm		Inch	mm		Inch	mm
A	0.234	5.944	G	0.261	6.629	M	0.295	7.493	S	0.348	8.839	Y	0.404	10.262
B	0.238	6.045	H	0.266	6.756	N	0.302	7.671	T	0.358	9.093	Z	0.413	10.490
C	0.242	6.147	I	0.272	6.909	O	0.316	8.026	U	0.368	9.347	…	…	…
D	0.246	6.248	J	0.277	7.036	P	0.323	8.204	V	0.377	9.576	…	…	…
E	0.250	6.350	K	0.281	7.137	Q	0.332	8.433	W	0.386	9.804	…	…	…
F	0.257	6.528	L	0.290	7.366	R	0.339	8.611	X	0.397	10.084	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

PIPE AND PIPE FITTINGS

Wrought Steel Pipe.— ANSI/ASME B36.10M-1995 covers dimensions of welded and seamless wrought steel pipe, for high or low temperatures or pressures.

The word *pipe* as distinguished from *tube* is used to apply to tubular products of dimensions commonly used for pipelines and piping systems. Pipe dimensions of sizes 12 inches and smaller have outside diameters numerically larger than the corresponding nominal sizes whereas outside diameters of tubes are identical to nominal sizes.

Size: The size of all pipe is identified by the nominal pipe size. The manufacture of pipe in the nominal sizes of ⅛ inch to 12 inches, inclusive, is based on a standardized outside diameter (OD). This OD was originally selected so that pipe with a standard OD and having a wall thickness which was typical of the period would have an inside diameter (ID) approximately equal to the nominal size. Although there is now no such relation between the existing standard thicknesses, ODs and nominal sizes, these nominal sizes and standard ODs continue in use as "standard."

The manufacture of pipe in nominal sizes of 14-inch OD and larger proceeds on the basis of an OD corresponding to the nominal size.

Weight: The nominal weights of steel pipe are calculated values and are tabulated in Table 1. They are based on the following formula:

$$W_{pe} = 10.68(D - t)t$$

where W_{pe} = nominal plain end weight to the nearest 0.01 lb/ft.

D = outside diameter to the nearest 0.001 inch

t = specified wall thickness rounded to the nearest 0.001 inch

Wall thickness: The nominal wall thicknesses are given in Table 1 which also indicates the wall thicknesses in API Standard 5L.

The wall thickness designations "Standard," "Extra-Strong," and "Double Extra-Strong" have been commercially used designations for many years. The Schedule Numbers were subsequently added as a convenient designation for use in ordering pipe. "Standard" and Schedule 40 are identical for nominal pipe sizes up to 10 inches, inclusive. All larger sizes of "Standard" have ⅜-inch wall thickness. "Extra-Strong" and Schedule 80 are identical for nominal pipe sizes up to 8 inch, inclusive. All larger sizes of "Extra-Strong" have ½-inch-wall thickness.

Wall Thickness Selection: When the selection of wall thickness depends primarily on capacity to resist internal pressure under given conditions, the designer shall compute the exact value of wall thickness suitable for conditions for which the pipe is required as prescribed in the "ASME Boiler and Pressure Vessel Code," "ANSI B31 Code for Pressure Piping," or other similar codes, whichever governs the construction. A thickness can then be selected from Table 1 to suit the value computed to fulfill the conditions for which the pipe is desired.

Metric Weights and Mass: Standard SI metric dimensions in millimeters for outside diameters and wall thicknesses may be found by multiplying the inch dimensions by 25.4. Outside diameters converted from those shown in Table 1 should be rounded to the nearest 0.1 mm and wall thicknesses to the nearest 0.01 mm.

The following formula may be used to calculate the SI metric plain end mass in kg/m using the converted metric diameters and thicknesses:

$$W_{pe} = 0.02466(D - t)t$$

where W_{pe} = nominal plain end mass rounded to the nearest 0.01 kg/m.

D = outside diameter to the nearest 0.1 mm for sizes shown in Table 1.

t = specified wall thickness rounded to the nearest 0.01 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. American National Standard Weights and Dimensions of Welded and Seamless Wrought Steel Pipe *ANSI/ASME B36.10M-1995*

Nom. Size and (O.D.), inch	Wall Thick., inch	Plain End Wgt., lb/ft	Identification		
			Sch. No.	Other	
⅛ (0.405)	0.057	0.21	30	…	…
	0.068	0.24	40	5L	STD
	0.095	0.31	80	5L	XS
¼ (0.540)	0.073	0.36	30	…	…
	0.088	0.42	40	5L	STD
	0.119	0.54	80	5L	XS
⅜ (0.675)	0.073	0.47	30	…	…
	0.091	0.57	40	5L	STD
	0.126	0.74	80	5L	XS
½ (0.840)	0.095	0.76	30	…	…
	0.109	0.85	40	5L	STD
	0.147	1.09	80	5L	XS
	0.188	1.31	160	…	…
	0.294	1.71	…	5L	XXS
¾ (1.050)	0.095	0.97	30	…	…
	0.113	1.13	40	5L	STD
	0.154	1.47	80	5L	XS
	0.219	1.94	160	…	…
	0.308	2.44	…	5L	XXS
1 (1.315)	0.114	1.46	30	…	…
	0.133	1.68	40	5L	STD
	0.179	2.17	80	5L	XS
	0.250	2.84	160	…	…
	0.358	3.66	…	5L	XXS
1¼ (1.660)	0.117	1.93	30	…	…
	0.140	2.27	40	5L	STD
	0.191	3.00	80	5L	XS
	0.250	3.76	160	…	…
	0.382	5.21	…	5L	XXS
1½ (1.900)	0.125	2.37	30	…	…
	0.145	2.72	40	5L	STD
	0.200	3.63	80	5L	XS
	0.281	4.86	160	…	…
	0.400	6.41	…	5L	XXS
2 (2.375)	0.083	2.03	…	5L	…
	0.109	2.64	…	5L	…
	0.125	3.00	…	5L	…
	0.141	3.36	…	5L	…
	0.154	3.65	40	5L	STD
	0.172	4.05	…	5L	…
	0.188	4.39	…	5L	…
	0.218	5.02	80	5L	XS
	0.250	5.67	…	5L	…
	0.281	6.28	…	…	…
	0.344	7.46	160	…	…
	0.436	9.03	…	…	XXS
2½ (2.875)	0.083	2.47	…	5L	…
	0.109	3.22	…	5L	…
	0.125	3.67	…	5L	…
	0.141	4.12	…	5L	…
	0.156	4.53	…	5L	…
	0.172	4.97	…	5L	…
	0.188	5.40	…	5L	…
	0.203	5.79	40	5L	STD
	0.216	6.13	…	5L	…
	0.250	7.01	…	5L	…
	0.276	7.66	80	5L	XS
	0.375	10.01	160	…	…
	0.552	13.69	…	5L	XXS
3 (3.500)	0.083	3.03	…	5L	…
	0.109	3.95	…	5L	…
	0.125	4.51	…	5L	…
3 (3.500)	0.141	5.06	…	5L	…
	0.156	5.57	…	5L	…
	0.172	6.11	…	5L	…
	0.188	6.65	…	5L	…
	0.216	7.58	40	5L	STD
	0.250	8.68	…	5L	…
	0.281	9.66	…	5L	…
	0.300	10.25	80	5L	XS
	0.438	14.32	160	…	…
	0.600	18.58	…	5L	XXS
3½ (4.000)	0.083	3.47	…	5L	…
	0.109	4.53	…	5L	…
	0.125	5.17	…	5L	…
	0.141	5.81	…	5L	…
	0.156	6.40	…	5L	…
	0.172	7.03	…	5L	…
	0.188	7.65	…	5L	…
	0.226	9.11	40	5L	STD
	0.250	10.01	…	5L	…
	0.281	11.16	…	5L	…
	0.318	12.50	80	5L	XS
4 (4.500)	0.083	3.92	…	5L	…
	0.109	5.11	…	5L	…
	0.125	5.84	…	5L	…
	0.141	6.56	…	5L	…
	0.156	7.24	…	5L	…
	0.172	7.95	…	5L	…
	0.188	8.66	…	5L	…
	0.203	9.32	…	5L	…
	0.219	10.01	…	5L	…
	0.237	10.79	40	5L	STD
	0.250	11.35	…	5L	…
	0.281	12.66	…	5L	…
	0.312	13.96	…	5L	…
	0.337	14.98	80	5L	XS
	0.438	19.00	120	5L	…
	0.531	22.51	160	5L	…
	0.674	27.54	…	5L	XXS
5 (5.563)	0.083	4.86	…	5L	…
	0.125	7.26	…	5L	…
	0.156	9.01	…	5L	…
	0.188	10.79	…	5L	…
	0.219	12.50	…	5L	…
	0.258	14.62	40	5L	STD
	0.281	15.85	…	5L	…
	0.312	17.50	…	5L	…
	0.344	19.17	…	5L	…
	0.375	20.78	80	5L	XS
	0.500	27.04	120	5L	…
	0.625	32.96	160	5L	…
	0.750	38.55	…	5L	XXS
6 (6.625)	0.083	5.80	…	5L	…
	0.109	7.59	…	5L	…
	0.125	8.68	…	5L	…
	0.141	9.76	…	5L	…
	0.156	10.78	…	5L	…
	0.172	11.85	…	5L	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **American National Standard Weights and Dimensions of Welded and Seamless Wrought Steel Pipe** *ANSI/ASME B36.10M-1995*

Nom. Size and (O.D.), inch	Wall Thick., inch	Plain End Wgt., lb/ft	Identification			Nom. Size and (O.D.), inch	Wall Thick., inch	Plain End Wgt., lb/ft	Identification		
			Sch. No.	Other					Sch. No.	Other	
	0.188	12.92	…	5L	…	10 (10.750)	1.125	115.64	160	…	…
	0.203	13.92	…	5L	…		1.250	126.83	…	5L	…
	0.219	14.98	…	5L	…						
	0.250	17.02	…	5L	…		0.172	23.11	…	5L	…
	0.280	18.97	40	5L	STD		0.188	25.22	…	5L	…
	0.312	21.04	…	5L	…		0.203	27.20	…	…	…
	0.344	23.08	…	5L	…		0.219	29.31	…	5L	…
6 (6.625)	0.375	25.03	…	5L	…		0.250	33.38	20	5L	…
	0.432	28.57	80	5L	XS		0.281	37.42	…	5L	…
	0.500	32.71	…	5L	…		0.312	41.45	…	5L	…
	0.562	36.39	120	5L	…		0.330	43.77	30	5L	…
	0.625	40.05	…	5L	…		0.344	45.58	…	5L	…
	0.719	45.35	160	5L	…		0.375	49.56	…	5L	STD
	0.750	47.06	…	5L	…		0.406	53.52	40	5L	…
	0.864	53.16	…	5L	XXS		0.438	57.59	…	5L	…
	0.875	53.73	…	5L	…	12 (12.750)	0.500	65.42	…	5L	XS
							0.562	73.15	60	5L	…
	0.125	11.35	…	5L	…		0.625	80.93	…	5L	…
	0.156	14.11	…	5L	…		0.688	88.63	80	5L	…
	0.188	16.94	…	5L	…		0.750	96.12	…	5L	…
	0.203	18.26	…	5L	…		0.812	103.53	…	5L	…
	0.219	19.66	…	5L	…		0.844	107.32	100	…	…
	0.250	22.36	20	5L	…		0.875	110.97	…	5L	…
	0.277	24.70	30	5L	…		0.938	118.33	…	5L	…
	0.312	27.70	…	5L	…		1.000	125.49	120	5L	XXS
	0.322	28.55	40	5L	STD		1.062	132.57	…	5L	…
	0.344	30.42	…	5L	…		1.125	139.67	140	5L	…
	0.375	33.04	…	5L	…		1.250	153.53	…	5L	…
8 (8.625)	0.406	35.64	60	…	…		1.312	160.27	160	5L	…
	0.438	38.30	…	5L	…						
	0.500	43.39	80	5L	XS		0.188	27.73	…	5L	…
	0.562	48.40	…	5L	…		0.203	29.91	…	5L	…
	0.594	50.95	100	…	…		0.210	30.93	…	5L	…
	0.625	53.40	…	5L	…		0.219	32.23	…	5L	…
	0.719	60.71	120	5L	…		0.250	36.71	10	5L	…
	0.750	63.08	…	5L	…		0.281	41.17	…	5L	…
	0.812	67.76	140	5L	…		0.312	45.61	20	5L	…
	0.875	72.42	…	5L	XXS		0.344	50.17	…	5L	…
	0.906	74.69	160	…	…		0.375	54.57	30	5L	STD
	1.000	81.44	…	5L	…		0.406	58.94	…	5L	…
							0.438	63.44	40	5L	…
	0.156	17.65	…	5L	…		0.469	67.78	…	5L	…
	0.188	21.21	…	5L	…		0.500	72.09	…	5L	XS
	0.203	22.87	…	5L	…		0.562	80.66	…	5L	…
	0.219	24.63	…	5L	…	14 (14.000)	0.594	85.05	60	…	…
	0.250	28.04	20	5L	…		0.625	89.28	…	5L	…
	0.279	31.20	…	5L	…		0.688	97.81	…	5L	…
	0.307	34.24	30	5L	…		0.750	106.13	80	5L	…
	0.344	38.23	…	5L	…		0.812	114.37	…	5L	…
	0.365	40.48	40	5L	STD		0.875	122.65	…	5L	…
10 (10.750)	0.438	48.24	…	5L	…		0.938	130.85	100	5L	…
	0.500	54.74	60	5L	XS		1.000	138.84	…	5L	…
	0.562	61.15	…	5L	…		1.062	146.74	…	5L	…
	0.594	64.43	80	…	…		1.094	150.79	120	…	…
	0.625	67.58	…	5L	…		1.125	154.69	…	5L	…
	0.719	77.03	100	5L	…		1.250	170.21	140	5L	…
	0.812	86.18	…	5L	…		1.406	189.11	160	…	…
	0.844	89.29	120	…	…		2.000	256.32	…	…	…
	0.875	92.28	…	5L	…		2.125	269.50	…	…	…
	0.938	98.30	…	5L	…		2.200	277.25	…	…	…
	1.000	104.13	140	5L	XXS		2.500	307.05	…	…	…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Properties of American National Standard Schedule 40 Welded and Seamless Wrought Steel Pipe

Diameter, Inches			Wall Thickness, Inches	Cross-Sectional Area of Metal	Weight per Foot, Pounds		Capacity per Foot of Length		Length of Pipe in Feet to Contain		Properties of Sections		
Nominal	Actual Inside	Actual Outside			Of Pipe	Of Water in Pipe	In Cubic Inches	In Gallons	One Cubic Foot	One Gallon	Moment of Inertia	Radius of Gyration	Section Modulus
1/8	0.269	0.405	0.068	0.072	0.24	0.025	0.682	0.003	2532.	338.7	0.00106	0.122	0.00525
1/4	0.364	0.540	0.088	0.125	0.42	0.045	1.249	0.005	1384.	185.0	0.00331	0.163	0.01227
3/8	0.493	0.675	0.091	0.167	0.57	0.083	2.291	0.010	754.4	100.8	0.00729	0.209	0.02160
1/2	0.622	0.840	0.109	0.250	0.85	0.132	3.646	0.016	473.9	63.35	0.01709	0.261	0.4070
3/4	0.824	1.050	0.113	0.333	1.13	0.231	6.399	0.028	270.0	36.10	0.03704	0.334	0.07055
1	1.049	1.315	0.133	0.494	1.68	0.374	10.37	0.045	166.6	22.27	0.08734	0.421	0.1328
1 1/4	1.380	1.660	0.140	0.669	2.27	0.648	17.95	0.078	96.28	12.87	0.1947	0.539	0.2346
1 1/2	1.610	1.900	0.145	0.799	2.72	0.882	24.43	0.106	70.73	9.456	0.3099	0.623	0.3262
2	2.067	2.375	0.154	1.075	3.65	1.454	40.27	0.174	42.91	5.737	0.6658	0.787	0.5607
2 1/2	2.469	2.875	0.203	1.704	5.79	2.074	57.45	0.249	30.08	4.021	1.530	0.947	1.064
3	3.068	3.500	0.216	2.228	7.58	3.202	88.71	0.384	19.48	2.604	3.017	1.163	1.724
3 1/2	3.548	4.000	0.226	2.680	9.11	4.283	118.6	0.514	14.56	1.947	4.788	1.337	2.394
4	4.026	4.500	0.237	3.174	10.79	5.515	152.8	0.661	11.31	1.512	7.233	1.510	3.215
5	5.047	5.563	0.258	4.300	14.62	8.666	240.1	1.04	7.198	0.9622	15.16	1.878	5.451
6	6.065	6.625	0.280	5.581	18.97	12.52	346.7	1.50	4.984	0.6663	28.14	2.245	8.496
8	7.981	8.625	0.322	8.399	28.55	21.67	600.3	2.60	2.878	0.3848	72.49	2.938	16.81
10	10.020	10.750	0.365	11.91	40.48	34.16	946.3	4.10	1.826	0.2441	160.7	3.674	29.91
12	11.938	12.750	0.406	15.74	53.52	48.49	1343.	5.81	1.286	0.1720	300.2	4.364	47.09
16	15.000	16.000	0.500	24.35	82.77	76.55	2121.	9.18	0.8149	0.1089	732.0	5.484	91.50
18	16.876	18.000	0.562	30.79	104.7	96.90	2684.	11.62	0.6438	0.0861	1172.	6.168	130.2
20	18.812	20.000	0.594	36.21	123.1	120.4	3335.	14.44	0.5181	0.0693	1706.	6.864	170.6
24	22.624	24.000	0.688	50.39	171.3	174.1	4824.	20.88	0.3582	0.0479	3426.	8.246	285.5
32	30.624	32.000	0.688	67.68	230.1	319.1	8839.	38.26	0.1955	0.0261	8299.	11.07	518.7

Note: Torsional section modulus equals twice section modulus.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Properties of American National Standard Schedule 80 Welded and Seamless Wrought Steel Pipe

Diameter, Inches			Wall Thickness, Inches	Cross-Sectional Area of Metal	Weight per Foot, Pounds		Capacity per Foot of Length		Length of Pipe in Feet to Contain		Properties of Sections		
Nominal	Actual Inside	Actual Outside			Of Pipe	Of Water in Pipe	In Cubic Inches	In Gallons	One Cubic Foot	One Gallon	Moment of Inertia	Radius of Gyration	Section Modulus
⅛	0.215	0.405	0.095	0.093	0.315	0.016	0.436	0.0019	3966.	530.2	0.00122	0.115	0.00600
¼	0.302	0.540	0.119	0.157	0.537	0.031	0.860	0.0037	2010.	268.7	0.00377	0.155	0.01395
⅜	0.423	0.675	0.126	0.217	0.739	0.061	1.686	0.0073	1025.	137.0	0.00862	0.199	0.02554
½	0.546	0.840	0.147	0.320	1.088	0.101	2.810	0.0122	615.0	82.22	0.02008	0.250	0.04780
¾	0.742	1.050	0.154	0.433	1.474	0.187	5.189	0.0225	333.0	44.52	0.04479	0.321	0.08531
1	0.957	1.315	0.179	0.639	2.172	0.312	8.632	0.0374	200.2	26.76	0.1056	0.407	0.1606
1¼	1.278	1.660	0.191	0.881	2.997	0.556	15.39	0.0667	112.3	15.01	0.2418	0.524	0.2913
1½	1.500	1.900	0.200	1.068	3.631	0.766	21.21	0.0918	81.49	10.89	0.3912	0.605	0.4118
2	1.939	2.375	0.218	1.477	5.022	1.279	35.43	0.1534	48.77	6.519	0.8680	0.766	0.7309
2½	2.323	2.875	0.276	2.254	7.661	1.836	50.86	0.2202	33.98	4.542	1.924	0.924	1.339
3	2.900	3.500	0.300	3.016	10.25	2.861	79.26	0.3431	21.80	2.914	3.895	1.136	2.225
3½	3.364	4.000	0.318	3.678	12.50	3.850	106.7	0.4617	16.20	2.166	6.280	1.307	3.140
4	3.826	4.500	0.337	4.407	14.98	4.980	138.0	0.5972	12.53	1.674	9.611	1.477	4.272
5	4.813	5.563	0.375	6.112	20.78	7.882	218.3	0.9451	7.915	1.058	20.67	1.839	7.432
6	5.761	6.625	0.432	8.405	28.57	11.29	312.8	1.354	5.524	0.738	40.49	2.195	12.22
8	7.625	8.625	0.500	12.76	43.39	19.78	548.0	2.372	3.153	0.422	105.7	2.878	24.52
10	9.562	10.750	0.594	18.95	64.42	31.11	861.7	3.730	2.005	0.268	245.2	3.597	45.62
12	11.374	12.750	0.688	26.07	88.63	44.02	1219.	5.278	1.417	0.189	475.7	4.271	74.62
14	12.500	14.000	0.750	31.22	106.1	53.16	1473.	6.375	1.173	0.157	687.4	4.692	98.19
16	14.312	16.000	0.844	40.19	136.6	69.69	1931.	8.357	0.895	0.120	1158.	5.366	144.7
18	16.124	18.000	0.938	50.28	170.9	88.46	2450.	10.61	0.705	0.094	1835.	6.041	203.9
20	17.938	20.000	1.031	61.44	208.9	109.5	3033.	13.13	0.570	0.076	2772.	6.716	277.2
22	19.750	22.000	1.125	73.78	250.8	132.7	3676.	15.91	0.470	0.063	4031.	7.391	366.4

Note: Torsional section modulus equals twice section modulus.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Volume of Flow at 1 Foot Per-Minute Velocity in Pipe and Tube

Nominal Dia., Inches	Schedule 40 Pipe			Schedule 80 Pipe			Type K Copper Tube			Type L Copper Tube		
	Cu. Ft. per Minute	Gallons per Minute	Pounds 60 F Water per Min.	Cu. Ft. per Minute	Gallons per Minute	Pounds 60 F Water per Min.	Cu. Ft. per Minute	Gallons per Minute	Pounds 60 F Water per Min.	Cu. Ft. per Minute	Gallons per Minute	Pounds 60 F Water per Min.
⅛	0.0004	0.003	0.025	0.0003	0.002	0.016	0.0002	0.0014	0.012	0.0002	0.002	0.014
¼	0.0007	0.005	0.044	0.0005	0.004	0.031	0.0005	0.0039	0.033	0.0005	0.004	0.034
⅜	0.0013	0.010	0.081	0.0010	0.007	0.061	0.0009	0.0066	0.055	0.0010	0.008	0.063
½	0.0021	0.016	0.132	0.0016	0.012	0.102	0.0015	0.0113	0.094	0.0016	0.012	0.101
¾	0.0037	0.028	0.232	0.0030	0.025	0.213	0.0030	0.0267	0.189	0.0034	0.025	0.210
1	0.0062	0.046	0.387	0.0050	0.037	0.312	0.0054	0.0404	0.338	0.0057	0.043	0.358
1¼	0.0104	0.078	0.649	0.0088	0.067	0.555	0.0085	0.0632	0.53	0.0087	0.065	0.545
1½	0.0141	0.106	0.882	0.0123	0.092	0.765	0.0196	0.1465	1.22	0.0124	0.093	0.770
2	0.0233	0.174	1.454	0.0206	0.154	1.280	0.0209	0.1565	1.31	0.0215	0.161	1.34
2½	0.0332	0.248	2.073	0.0294	0.220	1.830	0.0323	0.2418	2.02	0.0331	0.248	2.07
3	0.0514	0.383	3.201	0.0460	0.344	2.870	0.0461	0.3446	2.88	0.0473	0.354	2.96
3½	0.0682	0.513	4.287	0.0617	0.458	3.720	0.0625	0.4675	3.91	0.0640	0.479	4.00
4	0.0884	0.660	5.516	0.0800	0.597	4.970	0.0811	0.6068	5.07	0.0841	0.622	5.20
5	0.1390	1.040	8.674	0.1260	0.947	7.940	0.1259	0.9415	7.87	0.1296	0.969	8.10
6	0.2010	1.500	12.52	0.1820	1.355	11.300	0.1797	1.3440	11.2	0.1862	1.393	11.6
8	0.3480	2.600	21.68	0.3180	2.380	19.800	0.3135	2.3446	19.6	0.3253	2.434	20.3
10	0.5476	4.10	34.18	0.5560	4.165	31.130	0.4867	3.4405	30.4	0.5050	3.777	21.6
12	0.7773	5.81	48.52	0.7060	5.280	44.040	0.6978	5.2194	43.6	0.7291	5.454	45.6
14	0.9396	7.03	58.65	0.8520	6.380	53.180	…	…	…	…	…	…
16	1.227	9.18	76.60	1.1170	8.360	69.730	…	…	…	…	…	…
18	1.553	11.62	96.95	1.4180	10.610	88.500	…	…	…	…	…	…
20	1.931	14.44	120.5	1.7550	13.130	109.510	…	…	…	…	…	…

To obtain volume of flow at any other velocity, multiply values in table by velocity in feet per minute.

Copyright 2004, Industrial Press, Inc., New York, NY

Plastics Pipe.— Shortly after World War II, plastics pipe became an acceptable substitute, under certain service conditions, for other piping materials. Now, however, plastics pipe is specified on the basis of its own special capabilities and limitations. The largest volume of application has been for water piping systems.

Besides being light in weight, plastics pipe performs well in resisting deterioration from corrosive or caustic fluids. Even if the fluid borne is harmless, the chemical resistance of plastics pipe offers protection against a harmful exterior environment, such as when buried in a corrosive soil.

Generally, plastics pipe is limited by its temperature and pressure capacities. The higher the operating pressure of the pipe system, the less will be its temperature capability. The reverse is true, also. Since it is formed from organic resins, plastics pipe will burn. For various piping compositions, ignition temperatures vary from 700° to 800°F (370° to 430°C).

The following are accepted methods for joining plastics pipe:

Solvent Welding is usually accomplished by brushing a solvent cement on the end of the length of pipe and into the socket end of a fitting or the flange of the next pipe section. A chemical weld then joins and seals the pipe after connection.

Threading is a procedure not recommended for thin-walled plastics pipe or for specific grades of plastics. During connection of thicker-walled pipe, strap wrenches are used to avoid damaging and weakening the plastics.

Heat Fusion involves the use of heated air and plastics filler rods to weld plastics pipe assemblies. A properly welded joint can have a tensile strength equal to 90 percent that of the pipe material.

Elastomeric Sealing is used with bell-end piping. It is a recommended procedure for large diameter piping and for underground installations. The joints are set quickly and have good pressure capabilities.

Table 5. Dimensions and Weights of Thermoplastics Pipe

Nominal Pipe Size		Outside Diameter		Schedule 40				Schedule 80			
				Nom. Wall Thickness		Nominal Weight		Nom. Wall Thickness		Nominal Weight	
in.	cm	in.	cm	in.	cm	lb/100′	kg/m	in.	cm	lb/100′	kg/m
⅛	0.3	0.405	1.03	0.072	0.18	3.27	0.05	0.101	0.256	4.18	0.06
¼	0.6	0.540	1.37	0.093	0.24	5.66	0.08	0.126	0.320	7.10	0.11
⅜	1.0	0.675	1.71	0.096	0.24	7.57	0.11	0.134	0.340	9.87	0.15
½	1.3	0.840	2.13	0.116	0.295	11.4	0.17	0.156	0.396	14.5	0.22
¾	2.0	1.050	2.67	0.120	0.305	15.2	0.23	0.163	0.414	19.7	0.29
1	2.5	1.315	3.34	0.141	0.358	22.5	0.33	0.190	0.483	29.1	0.43
1¼	3.2	1.660	4.22	0.148	0.376	30.5	0.45	0.202	0.513	40.1	0.60
1½	3.8	1.900	4.83	0.154	0.391	36.6	0.54	0.212	0.538	48.7	0.72
2	5.1	2.375	6.03	0.163	0.414	49.1	0.73	0.231	0.587	67.4	1.00
2½	6.4	2.875	7.30	0.215	0.546	77.9	1.16	0.293	0.744	103	1.5
3	7.6	3.500	8.89	0.229	0.582	102	1.5	0.318	0.808	138	2.1
3½	8.9	4.000	10.16	0.240	0.610	123	1.8	0.337	0.856	168	2.5
4	10.2	4.500	11.43	0.251	0.638	145	2.2	0.357	0.907	201	3.0
5	12.7	5.563	14.13	0.273	0.693	197	2.9	0.398	1.011	280	4.2
6	15.2	6.625	16.83	0.297	0.754	256	3.8	0.458	1.163	385	5.7
8	20.3	8.625	21.91	0.341	0.866	385	5.7	0.530	1.346	584	8.7
10	25.4	10.75	27.31	0.387	0.983	546	8.1	0.629	1.598	867	12.9
12	30.5	12.75	32.39	0.430	1.09	722	10.7	0.728	1.849	1192	17.7

The nominal weights of plastics pipe given in this table are based on an empirically chosen material density of 1.00 g/cm^3. The nominal unit weight for a specific plastics pipe formulation can be

Copyright 2004, Industrial Press, Inc., New York, NY

obtained by multiplying the weight values from the table by the density in g/cm^3 or by the specific gravity of the particular platics composition.

The following are ranges of density factors for various plastics pipe materials: PE, 0.93 to 0.96; PVC, 1.35 to 1.40; CPVC, 1.55; ABS, 1.04 to 1.08; SR, 1.05; PB, 0.91 to 0.92; and PP, 0.91. For meanings of abbreviations see Table 6.

Information supplied by the Plastics Pipe Institute.

Insert Fitting is particularly useful for PE and PB pipe. For joining pipe sections, insert fittings are pushed into the pipe and secured by stainless steel clamps.

Transition Fitting involves specially designed connectors to join plastic pipe with other materials, such as cast iron, steel, copper, clay, and concrete.

Plastic pipe can be specified by means of Schedules 40, 80, and 120, which conform dimensionally to metal pipe, or through a Standard Dimension Ratio (SDR). The SDR is a rounded value obtained by dividing the average outside diameter of the pipe by the wall thickness. Within an individual SDR series of pipe, pressure ratings are uniform, regardless of pipe diameter.

Table 5 provides the weights and dimensions for Schedule 40 and 80 thermoplastic pipe, Table 6 gives properties of plastics pipe, Table 7 gives maximum non-shock operating pressures for several varieties of Schedule 40 and 80 plastics pipe at 73°F, and Table 8 gives correction factors to pressure ratings for elevated temperatures.

Table 6. General Properties and Uses of Plastic Pipe

Plastic Pipe Material	Properties	Common Uses	Operating Temperature[a]		Joining Methods
			With Pressure	Without Pressure	
ABS (Acrylonitrileb-utadiene sty-rene)	Rigid; excellent impact strength at low tempera-tures; maintains rigidity at higher temperatures.	Water, Drain, Waste, Vent, Sewage.	100°F (38°C)	180°F (82°C)	Solvent cement, Thread-ing, Transition fitting.
PE (Polyethylene)	Flexible; excellent impact strength; good perfor-mance at low temperatures.	Water, Gas, Chemical, Irrigation.	100°F (38°C)	180°F (82°C)	Heat fusion, Insert and Transition fitting.
PVC (Polyvinylchlo-ride)	Rigid; fire self-extinguish-ing; high impact and ten-sile strength.	Water, Gas, Sewage, Industrial process, Irri-gation.	100°F (38°C)	180°F (82°C)	Solvent cement, Elasto-meric seal, Mechanical coupling, Transition fit-ting.
CPVC (Chlorinated polyvinyl chlo-ride)	Rigid; fire self-extinguish-ing; high impact and ten-sile strength.	Hot and cold water, Chem-ical.	180°F (82°C) at 100 psig (690kPa) for SDR-11		Solvent cement, Thread-ing, Mechanical coupling, Transition fitting.
PB (Polybutylene)	Flexible; good performance at elevated temperatures.	Water, Gas, Irrigation.	180°F (82°C)	200°F (93°C)	Insert fitting, Heat fusion, Transition fitting.
PP (Polypropylene)	Rigid; very light; high chemical resistance, partic-ularly to sulfur-bearing compounds.	Chemical waste and processing.	100°F (38°C)	180°F (82°C)	Mechanical coupling, Heat fusion, Threading.
SR (Styrene rubber plastic)	Rigid; moderate chemical resistance; fair impact strength.	Drainage, Septic fields.	150°F (66°C)	…	Solvent cement, Transition fitting, Elastomeric seal.

[a] The operating temperatures shows are general guide points. For specific operating temperature and pressure data for various grades of the types of plastic pipe given, please consult the pipe manufacturer or the Plastics Pipe Institute.

From information supplied by the Plastics Pipe Institute.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Maximum Nonshock Operating Pressure (psi) for Thermoplastic Piping at 73°F

Nominal Pipe Size (inch)	Schedule 40		Schedule 80						
	PVC & CPVC (Socket End)	ABS	PVC & CPVC		Polypropylene		PVDF		ABS
			Socket End	Threaded End	Thermo-seal Joint	Threaded End[a]	Thermoseal Joint	Threaded End	
½	600	476	850	420	410	20	580	290	678
¾	480	385	690	340	330	20	470	230	550
1	450	360	630	320	310	20	430	210	504
1¼	370	294	520	260	260	20	…	…	416
1½	330	264	470	240	230	20	326	160	376
2	280	222	400	200	200	…	270	140	323
2½	300	243	420	210	…	20	…	…	340
3	260	211	370	190	160	20	250	NR	297
4	220	177	320	160	140	NR	220	NR	259
6	180	141	280	NR	…	…	190	NR	222
8	160	…	250[b]	NR	…	…	…	…	…
10	140	…	230	NR	…	…	…	…	…
12	130	…	230	NR	…	…	…	…	…

[a] Recommended for intermittent drainage pressure not exceeding 20 psi.

[b] 8-inch CPVC Tee, 90° Ell, and 45° Ell are rated at half the pressure shown.

ABS pressures refer to unthreaded pipe only.

For service at higher temperature, multiply the pressure obtained from this table by the correction factor from Table 6.

NR is not recommended.

Table 8. Temperature-Correction Factors for Thermoplastic Piping Operating Pressures

Operating Temperature,°F	Pipe Material			
	PVC	CPVC	Polypropylene	PVDF
70	1	1	1	1
80	0.90	0.96	0.97	0.95
90	0.75	0.92	0.91	0.87
100	0.62	0.85	0.85	0.80
110	0.50	0.77	0.80	0.75
115	0.45	0.74	0.77	0.71
120	0.40	0.70	0.75	0.68
125	0.35	0.66	0.71	0.66
130	0.30	0.62	0.68	0.62
140	0.22	0.55	0.65	0.58
150	NR	0.47	0.57	0.52
160	NR	0.40	0.50	0.49
170	NR	0.32	0.26	0.45
180	NR	0.25	[a]	0.42
200	NR	0.18	NR	0.36
210	NR	0.15	NR	0.33
240	NR	NR	NR	0.25
280	NR	NR	NR	0.18

[a] Recommended for intermittent drainage pressure not exceeding 20 psi.

NR = not recommended.

For more detailed information concerning the properties of a particular plastic pipe formulation, consult the pipe manufacturer or Plastics Pipe Institute, 1825 Connecticut Ave. NW, Washington, D.C. 2009.

Copyright 2004, Industrial Press, Inc., New York, NY

Pipe and Tube Bending.— In bending a pipe or tube, the outer part of the bend is stretched and the inner section compressed, and as the result of opposite and unequal stresses, the pipe or tube tends to flatten or collapse. To prevent such distortion, the common practice is to support the wall of the pipe or tube in some manner during the bending operation. This support may be in the form of a filling material, or, when a bending machine or fixture is used, an internal mandrel or ball-shaped member may support the inner wall when required.

If a filling material is used, it is melted and poured into the pipe or tube. Many filler materials made up from combinations of bismuth, lead, tin, and cadmium, with melting points around 160 degrees F are commercially available. With this material, tubes having very thin walls have been bent to small radii. The metal filler conforms to the inside of the tube so closely that the tube can be bent just as though it were a solid rod. The filler is removed readily by melting.

This method has been applied to the bending of copper, brass, duralumin, plain steel, and stainless steel tubes with uniform success. Tubes plated with chromium or nickel can often be bent without danger of the plate flaking off. Other filling materials such as resin, tar, lead, and dry sand have also been used.

Pipes are often bent to avoid the use of fittings, thus eliminating joints, providing a smooth unobstructed passage for fluids, and resulting in certain other advantages.

Minimum Radius: The safe minimum radius for a given diameter, material, and method of bending depends upon the thickness of the pipe wall, it being possible, for example, to bend extra heavy pipe to a smaller radius than pipe of standard weight. As a general rule, wrought iron or steel pipe of standard weight may readily be bent to a radius equal to five or six times the nominal pipe diameter. The minimum radius for standard weight pipe should, as a rule, be three and one-half to four times the diameter. It will be understood, however, that the minimum radius may vary considerably, depending upon the method of bending. Extra heavy pipe may be bent to radii varying from two and one-half times the diameter for smaller sizes to three and one-half to four times the diameter for larger sizes.

Rules for Finding Lengths of Bends: In determining the required length of a pipe or tube before bending, the lengths of the straight sections are, of course, added to the lengths required for the curved sections in order to make the proper allowance for bends. The following rules are for finding the lengths of the curved sections.

Length of 90-Degree Bend: To find the length of a 90-degree or right-angle bend, multiply the radius of the bend by 1.57. The radius is measured to the center of the pipe, or to a point midway between the inner and outer walls.

Length of 180-Degree Bend: Multiply the radius of the bend by 3.14.

Length of other than 90- or 180-Degree Bend: Multiply the radius of the bend by the included angle, and then multiply the product by the constant 0.01745. The result is the length of the curved section.

Definitions of Pipe Fittings.— The following definitions for various pipe fittings are given by the National Tube Co.:

Armstrong Joint: A two-bolt, flanged or lugged connection for high pressures. The ends of the pipes are peculiarly formed to properly hold a gutta-percha ring. It was originally made for cast-iron pipe. The two-bolt feature has much to corn-mend it. There are various substitutes for this joint, many of which employ rubber in place of gutta-percha; others use more bolts in order to reduce the cost.

Bell and Spigot Joint: a) The usual term for the joint in cast-iron pipe. Each piece is made with an enlarged diameter or bell at one end into which the plain or spigot end of another piece is inserted when laying. The joint is then made tight by cement, oakum, lead, rubber or other suitable substance, which is driven in or calked into the bell and around the spigot. When a similar joint is made in wrought pipe by means of a cast bell (or hub), it is at times

Copyright 2004, Industrial Press, Inc., New York, NY

called hub and spigot joint (poor usage). Matheson joint is the name applied to a similar joint in wrought pipe which has the bell formed from the pipe.

b) Applied to fittings or valves, means that one end of the run is a "bell," and the other end is a "spigot," similar to those used on regular cast-iron pipe.

Bonnet: a) A cover used to guide and enclose the tail end of a valve spindle.

b) A cap over the end of a pipe (poor usage).

Branch: The outlet or inlet of a fitting not in line with the run, but which may make any angle.

Branch Ell: a) Used to designate an elbow having a back outlet in line with one of the outlets of the "run." It is also called a heel outlet elbow.

b) Incorrectly used to designate side outlet or back outlet elbow.

Branch Pipe: A very general term used to signify a pipe either cast or wrought, that is equipped with one or more branches. Such pipes are used so frequently that they have acquired common names such as tees, crosses, side or back outlet elbows, manifolds, double-branch elbows, etc. The term branch pipe is generally restricted to such as do not conform to usual dimensions.

Branch Tee or Header: A tee having many side branches. (See *Manifold*.)

Bull Head Tee: A tee the branch of which is larger than the run.

Bushing: A pipe fitting for the purpose of connecting a pipe with a fitting of larger size, being a hollow plug with internal and external threads to suit the different diameters.

Card Weight Pipe: A term used to designate standard or full weight pipe, which is the Briggs' standard thickness of pipe.

Close Nipple: One the length of which is about twice the length of a standard pipe thread and is without any shoulder.

Coupling: A threaded sleeve used to connect two pipes. Commercial couplings are threaded inside to suit the exterior thread of the pipe. The term coupling is occasionally used to mean any jointing device and may be applied to either straight or reducing sizes.

Cross: A pipe fitting with four branches arranged in pairs, each pair on one axis, and the axes at right angles. When the outlets are otherwise arranged the fittings are branch pipes or specials.

Cross-over: A small fitting with a double offset, or shaped like the letter U with the ends turned out. It is only made in small sizes and used to pass the flow of one pipe past another when the pipes are in the same plane.

Cross-over Tee: A fitting made along lines similar to the cross-over, but having at one end two openings in a tee-head the plane of which is at right angles to the plane of the cross-over bend.

Cross Valve: a) A valve fitted on a transverse pipe so as to open communication at will between two parallel lines of piping. Much used in connection with oil and water pumping arrangements, especially on ship board.

b) Usually considered as an angle valve with a back outlet in the same plane as the other two openings.

Crotch: A fitting that has the general shape of the letter Y. Caution should be exercised not to confuse the crotch and wye.

Double-branch Elbow: A fitting that, in a manner, looks like a tee, or as if two elbows had been shaved and then placed together, forming a shape something like the letter Y or a crotch.

Double Sweep Tee: A tee made with easy curves between body and branch, i.e., the center of the curve between run and branch lies outside the body.

Drop Elbow: A small sized ell that is frequently used where gas is put into a building. These fittings have wings cast on each side. The wings have small countersunk holes so that they may be fastened by wood screws to a ceiling or wall or framing timbers.

Drop Tee: One having the same peculiar wings as the drop elbow.

Dry Joint: One made without gasket or packing or smear of any kind, as a ground joint.

Copyright 2004, Industrial Press, Inc., New York, NY

Elbow (ELL): A fitting that makes an angle between adjacent pipes. The angle is always 90 degrees, unless another angle is stated. (See *Branch Ell*, *Service Ell*, and *Union Ell*.)

Extra Heavy: When applied to pipe, means pipe thicker than standard pipe; when applied to valves and fittings, indicates goods suitable for a working pressure of 250 pounds per square inch.

Header: A large pipe into which one set of boilers is connected by suitable nozzles or tees, or similar large pipes from which a number of smaller ones lead to consuming points. Headers are often used for other purposes-for heaters or in refrigeration work. Headers are essentially branch pipes with many outlets, which are usually parallel. Largely used for tubes of water-tube boilers.

Hydrostatic Joint: Used in large water mains, in which sheet lead is forced tightly into the bell of a pipe by means of the hydrostatic pressure of a liquid.

Kewanee Union: A patented pipe union having one pipe end of brass and the other of malleable iron, with a ring or nut of malleable iron, in which the arrangement and finish of the several parts is such as to provide a non-corrosive ball-and-socket joint at the junction of the pipe ends, and a non-corrosive connection between the ring and brass pipe end.

Lead Joint: a) Generally used to signify the connection between pipes which is made by pouring molten lead into the annular space between a bell and spigot, and then making the lead tight by calking.

b) Rarely used to mean the joint made by pressing the lead between adjacent pieces, as when a lead gasket is used between flanges.

Lead Wool: A material used in place of molten lead for making pipe joints. It is lead fiber, about as coarse as fine excelsior, and when made in a strand, it can be calked into the joints, making them very solid.

Line Pipe: Special brand of pipe that employs recessed and taper thread couplings, and usually greater length of thread than Briggs' standard. The pipe is also subjected to higher test.

Lip Union: a) A special form of union characterized by the lip that prevents the gasket from being squeezed into the pipe so as to obstruct the flow.

b) A ring union, unless flange is specified.

Manifold: a) A fitting with numerous branches used to convey fluids between a large pipe and several smaller pipes. (See *Branch Tee or Header*.)

b) A header for a coil.

Matheson Joint: A wrought pipe joint made by enlarging. one end of the pipe to form a suitable lead recess, similar to the bell end of a cast-iron pipe, and which receives the male or spigot end of the next length. Practically the same style of a joint as used for cast-iron pipe.

Medium Pressure: When applied to valves and fittings, means suitable for a working pressure of from 125 to 175 pounds per square inch.

Needle Valve: A valve provided with a long tapering point in place of the ordinary valve disk. The tapering point permits fine graduation of the opening. At times called a needle point valve.

Nipple: A tubular pipe fitting usually threaded on both ends and under 12 inches in length. Pipe over 12 inches long is regarded as cut pipe. (See *Close Nipple*, *Short Nipple*, *Shoulder Nipple*, and *Space Nipple*.)

Reducer: a) A fitting having a larger size at one end than at the other. Some have tried to establish the term "increaser" — thinking of direction of flow —but this has been due to a misunderstanding of the trade custom of always giving the largest size of run of a fitting first; hence, all fittings having more than one size are reducers. They are always threaded inside, unless specified flanged or for some special joint.

b) Threaded type, made with abrupt reduction.

c) Flanged pattern with taper body.

d) Flanged eccentric pattern with taper body, but flanges at 90 degrees to one side of body.

Copyright 2004, Industrial Press, Inc., New York, NY

e) Misapplied at times, to a reducing coupling.

Run: a) A length of pipe that is made of more than one piece of pipe.

b) The portion of any fitting having its ends "in line" or nearly so, in contradistinction to the branch or side opening, as of a tee. The two main openings of an ell also indicate its run, and when there is a third opening on an eli, the fitting is a "side outlet" or "back outlet" elbow, except that when all three openings are in one plane and the back outlet is in line with one of the run openings, the fitting is a "heel outlet elbow" or a "single sweep tee" or sometimes a "branch tee."

Rust Joint: Employed to secure rigid connection. The joint is made by packing an intervening space tightly with a stiff paste which oxidizes the iron, the whole rusting together and hardening into a solid mass. It generally cannot be separated except by destroying some of the pieces. One recipe is 80 pounds cast-iron borings or filings, 1 pound sal-ammoniac, 2 pounds flowers of sulphur, mixed to a paste with water.

Service Ell: An elbow having an outside thread on one end. Also known as street ell.

Service Pipe: A pipe connecting mains with a dwelling.

Service Tee: A tee having inside thread on one end and on branch, but outside thread on other end of run. Also known as street tee.

Short Nipple: One whose length is a little greater than that of two threaded lengths or somewhat longer than a close nipple. It always has some unthreaded portion between the two threads.

Shoulder Nipple: A nipple of any length, which has a portion of pipe between two pipe threads. As generally used, however, it is a nipple about halfway between the length of a close nipple and a short nipple.

Space Nipple: A nipple with a portion of pipe or shoulder between the two threads. It may be of any length long enough to allow a shoulder.

Standard Pressure: A term applied to valves and fittings suitable for a working steam pressure of 125 pounds per square inch.

Tee: A fitting, either cast or wrought, that has one side outlet at right angles to the run. A single outlet branch pipe. (See *Branch Tee or Header*, *Bull Head Tee*, *Cross-over Tee*, *Double Sweep Tee*, *Drop Tee*, *Service Tee*, and *Union Tee*.)

Union: The usual trade term for a device used to connect pipes. It commonly consists of three pieces which are, first, the thread end fitted with exterior and interior threads; second, the bottom end fitted with interior threads and a small exterior shoulder; and third, the ring which has an inside flange at one end while the other end has an inside thread like that on the exterior of the thread end. A gasket is placed between the thread and bottom ends, which are drawn together by the ring. Unions are very extensively used, because they permit of connections with little disturbance of the pipe positions.

Union Ell: An ell with a male or female union at one end.

Union Joint: A pipe coupling, usually threaded, which permits disconnection without disturbing other sections.

Union Tee: A tee with male or female union at connection on one end of run.

Wiped Joint: A lead joint in which the molten solder is poured upon the desired place, after scraping and fitting the parts together, and the joint is wiped up by hand with a moleskin or cloth pad while the metal is in a plastic condition.

Wye (Y): A fitting either cast or wrought that has one side outlet at any angle other than 90 degrees. The angle is usually 45 degrees, unless another angle is specified. The fitting is usually indicated by the letter Y.

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

MEASURING UNITS

SYMBOLS AND ABBREVIATIONS

2540 Greek Alphabet
2540 Scientific and Engineering
2542 Mathematical Signs and
2543 Letter Symbols for Mechanics

MEASURING UNITS

2544 Metric Systems Of Measurement
2544 SI Unit System
2546 Prefixes for SI Units
2546 Binary Multiples
2546 SI Base Units
2548 Standard of Length
2548 U.S. Customary Unit System
2548 Fundamental Constants

U.S. SYSTEM AND METRIC SYSTEM CONVERSIONS

2549 Units of Length
2549 Linear Conversion Factors
2550 Angular Conversion Factors
2550 Feet and Inches to Inches
2550 Inch to Feet and Yards
2551 Inch Fractions to Decimal Feet
2552 Feet to Inches
2552 Inch ↔ Millimeter
2553 Feet to Millimeter
2554 Fractional Inch to Millimeters
2556 Decimal Inch to Millimeters
2558 Millimeters to Inches
2560 Microinches to Micrometers
2561 Micrometers to Microinches
2562 Feet ↔ Meters
2562 Miles ↔ Kilometers
2563 Units of Area
2563 Conversion Factors
2564 Square Inch ↔ Square Centimeter
2564 Square Feet ↔ Square Meter
2565 Square Yard ↔ Square Meter
2565 Acre ↔ Hectare
2566 Units of Volume
2566 Conversion Factors
2567 Cubic Inch ↔ Cubic Centimeter
2568 Cubic Feet ↔ Cubic Meters
2568 Cubic Feet ↔ Liters
2569 U.K. Gallons ↔ Liters
2569 U.S. Gallons ↔ Liters
2570 U.S. Fluid Ounce ↔ Milliliters

U.S. SYSTEM AND METRIC SYSTEM CONVERSIONS

(Continued)

2570 Units of Volumetric Flow Rate
2570 Pitot Tube
2571 Units of Mass and Weight
2571 Conversion Factors
2571 Pound ↔ Kilogram
2572 Ounce ↔ Gram
2572 Density Conversion Factors
2573 Pound/Cu Inch ↔ Gram/Cu Cm
2573 Pound/Cu Inch ↔ Kg/Cu Meter
2574 Units of Pressure and Stress
2574 Conversion Factors
2574 Pound/Sq Inch ↔ Kg/Sq Cm
2575 Pound/Sq Foot ↔ Km/Sq Meter
2575 Pound/Sq Inch ↔ Kilopscal
2576 Conversion Factors Table
2576 Units of Force
2576 Conversion Factors
2577 Pound ↔ Newton
2577 Units of Moment and Torque
2577 Conversion Factors
2577 Pound-Inch ↔ Newton-Meter
2578 Poundal
2578 Units of Energy, Power, and Heat
2578 Conversion Factor Tables
2579 Btu ↔ Foot-pound
2579 Btu ↔ Kilojoule
2580 Horsepower ↔ Kilowatt
2580 Foot-pound ↔ Joule
2581 Power Conversion Factors
2581 Energy and Work Conversion
2582 Thermal Conductance Conversion
2582 Conduction
2582 Fuel Oil, Coal and Gas Equivalents
2583 Units of Temperature
2583 Thermometer Scales
2583 Conversion Formulas
2583 Absolute Temperature and Absolute Zero
2583 Thermal Energy Units
2584 Temperature Conversion Table
2586 Units of Velocity and Acceleration
2586 Velocity Conversion Factors
2586 Acceleration Conversion Factors
2586 Units of Viscosity
2587 Units of Inertia and Momentum
2587 Miscellaneous Measuring Units
2587 Ohm's Law

Copyright 2004, Industrial Press, Inc., New York, NY

SYMBOLS AND ABBREVIATIONS

Greek Letters and Standard Abbreviations

The Greek letters are frequently used in mathematical expressions and formulas. The Greek alphabet is given below.

A	α	Alpha	H	η	Eta	N	ν	Nu	T	τ	Tau
B	β	Beta	Θ	ϑ θ	Theta	Ξ	ξ	Xi	Υ	υ	Upsilon
Γ	γ	Gamma	I	ι	Iota	O	o	Omicron	Φ	ϕ	Phi
Δ	δ	Delta	K	κ	Kappa	Π	π	Pi	X	χ	Chi
E	ε	Epsilon	Λ	λ	Lambda	R	ρ	Rho	Ψ	ψ	Psi
Z	ζ	Zeta	M	μ	Mu	Σ	σ ς	Sigma	Ω	ω	Omega

ANSI Abbreviations for Scientific and Engineering Terms

ANSI Y1.1-1972, (R 1984)

Absolute	abs	Decibel	dB
Alternating current	ac	Degree	deg or°
Ampere	amp	Degree Centigrade	°C
Ampere-hour	amp hr	Degree Fahrenheit	°F
Angstrom unit	A	Degree Kelvin	K
Antilogarithm	antilog	Diameter	dia
Arithmetical average	aa	Direct current	dc
Atmosphere	atm	Dozen	doz
Atomic weight	at wt	Dram	dr
Avoirdupois	avdp	Efficiency	eff
Barometer	baro	Electric	elec
Board feet (feet board measure)	fbm	Electromotive force	emf
Boiler pressure	bopress	Elevation	el
Boiling point	bp	Engine	eng
Brinell hardness number	Bhn	Engineer	engr
British thermal unit	Btu or B	Engineering	engrg
Bushel	bu	Equation	eq
Calorie	cal	External	ext
Candle	cd	Fluid	fl
Center to center	c to c	Foot	ft
Centimeter	cm	Foot-candle	fc
Centimeter-gram-second (system)	cgs	Foot-Lambert	fL or fl
Chemical	chem	Foot per minute	fpm
Chemically pure	cp	Foot per second	fps
Circular	circ	Foot-pound	ft lb
Circular mil	cmil	Foot-pound-second (system)	fps
Coefficient	coef	Free on board	fob
Cologarithm	colog	Freezing point	fp
Concentrate	conc	Frequency	freq
Conductivity	cndct	Fusion point	fnpt
Constant	const	Gallon	gal
Cord	cd	Gallon per minute	gpm
Cosecant	csc	Gallon per second	gps
Cosine	cos	Grain	gr
Cost, insurance, and freight	cif	Gram	g
Cotangent	ctn	Greatest common divisor	gcd
Counter electromotive force	cemf	High pressure	hp
Cubic	cu	Horsepower	hp
Cubic centimeter	cm^3 or cc	Horsepower-hour	hp hr
Cubic foot	ft^3 or cu ft	Hour	h or hr
Cubic feet per second	ft^3 or cfs	Hyperbolic cosine	cosh
Cubic inch	in^3 or cu in	Hyperbolic sine	sinh
Cubic meter	m^3 or cu m	Hyperbolic tangent	tanh
Cubic millimeter	mm^3 or cumm	Inch	in
Cubic yard	yd^3 or cu yd	Inch per second	in/s or ips
Current density	cd	Inch-pound	in lb
Cylinder	cyl		

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Abbreviations for Scientific and Engineering Terms *(Continued)*
ANSI Y1.1-1972, (R 1984)

Indicated horsepower-hour	iph	Pound-force foot	$lb_f \cdot ft$ or lb ft
Intermediate pressure	ip	Pound-force inch	$lb_f \cdot in$ or lb in
Internal	intl	pound-force per square foot	lb_f/ft^2 or psf
Kilovolt-ampere/hour	KVA-h or kVah	pound-force per square inch	lb_f/in^2 or psi
Kilowatt-hour meter	kwhm	pound per horsepower	lb/hp or php
Latitude	lat	Power factor	pf
Least common multiple	lcm	Quart	qt
Liquid	liq	Reactive volt-ampere meter	rva
Logarithm (common)	log	Revolution per minute	r/min or rpm
Logarithm (natural)	ln	Revolution per second	r/s or rps
Low pressure	lp	Root mean square	rms
Lumen per watt	lm/W or lpw	Round	rnd
Magnetomotive force	mmf	Secant	sec
Mathematics (ical)	math	Second	s or sec
Maximum	max	Sine	sin
Mean effective pressure	mep	Specific gravity	sp gr
Melting point	mp	Specific heat	sp ht
Meter	m	Square	sq
Meter-kilogram-second	mks	Square centimeter	cm^2 or sq cm
Microfarad	µF	Square foot	ft^2 or sq ft
Mile	mi	Square inch	in^2 or sq in
Mile per hour	mi/h or mph	Square kilometer	km^2 or sq km
Milliampere	m/A	Square root of mean square	rms
Minimum	min	Standard	std
Molecular weight	mol wt	Tangent	tan
Molecule	mo	Temperature	temp
National Electrical Code	NEC	Tensile strength	ts
Ounce	oz	Versed sine	vers
Ounce-inch	oz in	Volt	V
Pennyweight	dwt	Watt	W
Pint	pt	Watthour	Wh
Potential	pot	Week	wk
Potential difference	pd	Weight	wt
Pound	lb	Yard	yd

Alternative abbreviations conforming to the practice of the International Electrotechnical Commission.

Ampere	A	Kilovolt-ampere	kVA	Microfarad	µF	Milliampere	mA
Ampere-hour	Ah	Kilowatt	kW	Microwatt	µW	Volt	V
Coulomb	C			Milliampere	mA	Volt-ampere	VA
Farad	F	Kilowatthour	kWh	Millifarad	mF	Volt-coulomb	VC
Henry	H	Megawatt	MW	Millihenry	mH	Watt	W
Joule	J	Megohm	Mω	Millivolt	mV	Watthour	Wh
Kilovolt	kV	Microampere	µA	Ohm	ω	Volt	VA

Only the most commonly used terms have been included. These forms are recommended for those whose familiarity with the terms used makes possible a maximum of abbreviations. For others, less contracted combinations made up from this list may be used. For example, the list gives the abbreviation of the term "feet per second" as "fps." To some, however, ft per sec will be more easily understood.

Abbreviations should be used sparingly and only where their meaning will be clear. If there is any doubt, then spell out the term or unit of measurement.

The following points are good practice when preparing engineering documentation. Terms denoting units of measurement should be abbreviated in text only when preceded by the amounts indicated in numerals: "several inches," "one inch," "12 in." A sentence should not begin with a numeral followed by an abbreviation. The use of conventional signs for abbreviations in text should be avoided: use "lb," not "#" or "in," not ″.

Symbols for the chemical elements are listed in the table on page 398.

Copyright 2004, Industrial Press, Inc., New York, NY

Mathematical Signs and Commonly Used Abbreviations

+	Plus (sign of addition)	π	Pi (3.1416)
+	Positive	Σ	Sigma (sign of summation)
−	Minus (sign of subtraction)	ω	Omega (angles measured in radians)
−	Negative	g	Acceleration due to gravity (32.16 ft/s^2 or 9.81 m/s^2)
± (∓)	Plus or minus (minus or plus)	i (or j)	Imaginary quantity $(\sqrt{-1})$
×	Multiplied by (multiplication sign)	sin	Sine
·	Multiplied by (multiplication sign)	cos	Cosine
÷	Divided by (division sign)	tan	Tangent
/	Divided by (division sign)	cot	Cotangent
:	Is to (in proportion)	sec	Secant
=	Equals	csc	Cosecant
≠	Is not equal to	vers	Versed sine
≡	Is identical to	covers	Coversed sine
≅ or ≈	Approximately equals	$\sin^{-1} a$ arcsin a or asin a	Arc the sine of which is a
>	Greater than	$(\sin a)^{-1}$	Reciprocal of sin a ($1 \div \sin a$)
<	Less than	$\sin^n x$	nth power of sin x
≥	Greater than or equal to	sinh x	Hyperbolic sine of x
≤	Less than or equal to	cosh x	Hyperbolic cosine of x
→	Approaches as a limit	Δ	Delta (increment of)
∝	Varies directly as	δ	Delta (variation of)
∴	Therefore	d	Differential (in calculus)
::	Equals (in proportion)	∂	Partial differentiation (in calculus)
$\sqrt{\ }$	Square root	∫	Integral (in calculus)
$\sqrt[3]{\ }$	Cube root	$\int_b^a$	Integral between the limits a and b
$\sqrt[4]{\ }$	4th root	!	5! = 1 × 2 × 3 × 4 × 5 (Factorial)
$\sqrt[n]{\ }$	nth root	∠	Angle
a^2	a squared (2nd power of a)	∟	Right angle
a^3	a cubed (3rd power of a)	⊥	Perpendicular to
a^4	4th power of a	△	Triangle
a^n	nth power of a	○	Circle
a^{-n}	$1 \div a^n$	▱	Parallelogram
$\frac{1}{n}$	Reciprocal value of n	°	Degree (circular arc or temperature)
log	Logarithm	′	Minutes or feet
$\log_e$	Natural or Napierian logarithm	″	Seconds or inches
ln	Natural or Napierian logarithm	a'	a prime
e	Base of natural logarithms (2.71828)	a''	a double prime
lim	Limit value (of an expression)	a_1	a sub one
∞	Infinity	a_2	a sub two
α	Alpha	a_n	a sub n
β	Beta — commonly used to denote angles	( )	Parentheses
γ	Gamma	[ ]	Brackets
θ	Theta	{ }	Braces
ϕ	Phi	$\lvert K \rvert$	Absolute value of K, size of K irrespective of sign
μ	Mu (coefficient of friction)		

Copyright 2004, Industrial Press, Inc., New York, NY

Letter Symbols for Mechanics and Time-Related Phenomena
ANSI/ASME Y10.3M-1984

Acceleration, angular	α (alpha)	Height	*h*
Acceleration, due to gravity	*g*	Inertia, moment of	*I* or *J*
Acceleration, linear	*a*	Inertia, polar (area) moment of[a]	*J*
Amplitude[a]	*A*	Inertia, product (area) moment of[a]	I_{xy}
		Length	*L* or *l*
Angle	α (alpha) β (beta) γ (gamma) θ (theta) ϕ (phi) ψ (psi)	Load per unit distance[a]	*q* or *w*
		Load, total[a]	*P* or W
		Mass	*m*
		Moment of force, including bending moment	*M*
		Neutral axis, distance to extreme fiber from[a]	*c*
Angle, solid	Ω (omega)	Period	*T*
Angular frequency	ω (omega)	Poisson's ratio	μ (mu) or ν (nu)
Angular momentum	*L*	Power	*P*
Angular velocity	ω (omega)	Pressure, normal force per unit area	*p*
Arc length	*s*	Radius	*r*
Area	*A*	Revolutions per unit of time	*n*
Axes, through any point[a]	*X-X*, *Y-Y*, or *Z-Z*	Second moment of area (second axial moment of area)	I_a
Bulk modulus	*K*	Second polar moment of area	I_P or *J*
Breadth (width)	*b*	Section modulus	*Z*
Coefficient of expansion, linear[a]	α (alpha)	Shear force in beam section[a]	*V*
Coefficient of friction	μ (mu)	Spring constant (load per unit deflection)[a]	*k*
Concentrated load (same as force)	*F*	Statical moment of any area about a given axis[a]	*Q*
Deflection of beam, max[a]	δ (delta)	Strain, normal	ε (epsilon)
Density	ρ (rho)	Strain, shear	γ (gamma)
Depth	*d*, δ (delta), or *t*	Stress, concentration factor[a]	*K*
Diameter	*D* or *d*	Stress, normal	σ (sigma)
Displacement[a]	*u*, *v*, *w*	Stress, shear	τ (tau)
Distance, linear[a]	*s*	Temperature, absolute[b]	*T*, or θ (theta)
Eccentricity of application of load[a]	*e*	Temperature[b]	*t*, or θ (theta)
Efficiency[a]	η (eta)	Thickness	*d*, δ (delta), or *t*
Elasticity, modulus of	*E*	Time	*t*
Elasticity, modulus of, in shear	*G*	Torque	*T*
Elongation, total[a]	δ (delta)	Velocity, linear	*v*
Energy, kinetic	E_k, *K*, *T*	Volume	*V*
Energy, potential	E_P, *V*, or Φ (phi)	Wavelength	λ (lambda)
Factor of safety[a]	*N*, or *n*	Weight	*W*
Force or load, concentrated	*F*	Weight per unit volume	γ (gamma)
Frequency	*f*	Work	*W*
Gyration, radius of[a]	*k*		

[a] Not specified in Standard
[b] Specified in ANSI Y10.4-1982 (R1988)

Copyright 2004, Industrial Press, Inc., New York, NY

MEASURING UNITS

Metric Systems Of Measurement

A metric system of measurement was first established in France in the years following the French Revolution, and various systems of metric units have been developed since that time. All metric unit systems are based, at least in part, on the International Metric Standards, which are the meter and kilogram, or decimal multiples or submultiples of these standards.

In 1795, a metric system called the centimeter-gram-second (cgs) system was proposed, and was adopted in France in 1799. In 1873, the British Association for the Advancement of Science recommended the use of the cgs system, and since then it has been widely used in all branches of science throughout the world. From the base units in the cgs system are derived the following:

Unit of velocity = 1 centimeter per second

Acceleration due to gravity (at Paris) = 981 centimeters per second per second

Unit of force = 1 dyne = $^1/_{981}$ gram

Unit of work = 1 erg = 1 dyne-centimeter

Unit of power = 1 watt = 10,000,000 ergs per second

Another metric system called the MKS (meter-kilogram-second) system of units was proposed by Professor G. Giorgi in 1902. In 1935, the International Electro-technical Commission (IEC) accepted his recommendation that this system of units of mechanics should be linked with the electromagnetic units by the adoption of a fourth base unit. In 1950, the IEC adopted the ampere, the unit of electric current, as the fourth unit, and the MKSA system thus came into being.

A gravitational system of metric units, known as the technical system, is based on the meter, the kilogram as a force, and the second. It has been widely used in engineering. Because the standard of force is defined as the weight of the mass of the standard kilogram, the fundamental unit of force varies due to the difference in gravitational pull at different locations around the earth. By international agreement, a standard value for acceleration due to gravity was chosen (9.81 meters per second squared) that for all practical measurements is approximately the same as the local value at the point of measurement.

The International System of Units (SI).— The Conference Generale des Poids et Mesures (CGPM), which is the body responsible for all international matters concerning the metric system, adopted in 1954, a rationalized and coherent system of units, based on the four MKSA units (see above), and including the *kelvin* as the unit of temperature and the *candela* as the unit of luminous intensity. In 1960, the CGPM formally named this system the Système International d'Unites, for which the abbreviation is SI in all languages. In 1971, the 14th CGPM adopted a seventh base unit, the *mole,* which is the unit of quantity ("amount of substance").

In the period since the first metric system was established in France toward the end of the 18th century, most of the countries of the world have adopted a metric system. At the present time, most of the industrially advanced metric-using countries are changing from their traditional metric system to SI. Those countries that are currently changing or considering change from the English system of measurement to metric have the advantage that they can convert directly to the modernized system. The United Kingdom, which can be said to have led the now worldwide move to change from the English system, went straight to SI.

The use of SI units instead of the traditional metric units has little effect on everyday life or trade. The units of linear measurement, mass, volume, and time remain the same, viz. meter, kilogram, liter, and second.

Copyright 2004, Industrial Press, Inc., New York, NY

The SI, like the traditional metric system, is based on decimal arithmetic. For each physical quantity, units of different sizes are formed by multiplying or dividing a single base value by powers of 10. Thus, changes can be made very simply by adding zeros or shifting decimal points. For example, the meter is the basic unit of length; the kilometer is a multiple (1000 meters); and the millimeter is a sub-multiple (one-thousandth of a meter).

In the older metric systems, the simplicity of a series of units linked by powers of ten is an advantage for plain quantities such as length, but this simplicity is lost as soon as more complex units are encountered. For example, in different branches of science and engineering, energy may appear as the erg, the calorie, the kilogram-meter, the liter-atmosphere, or the horsepower-hour. In contrast, the SI provides only one basic unit for each physical quantity, and universality is thus achieved.

As mentioned before, there are seven base units, which are for the basic quantities of length, mass, time, electric current, thermodynamic temperature, amount of substance, and luminous intensity, expressed as the meter (m), the kilogram (kg), the second (s), the ampere (A), the kelvin (K), the mole (mol), and the candela (cd). The units are defined in the accompanying Table 1.

The SI is a coherent system. A system is said to be coherent if the product or quotient of any two unit quantities in the system is the unit of the resultant quantity. For example, in a coherent system in which the foot is the unit of length, the square foot is the unit of area, whereas the acre is not.

Other physical quantities are derived from the base units. For example, the unit of velocity is the meter per second (m/s), which is a combination of the base units of length and time. The unit of acceleration is the meter per second squared (m/s^2). By applying Newton's second law of motion—force is proportional to mass multiplied by acceleration—the unit of force is obtained that is the kilogram-meter per second squared ($kg\text{-}m/s^2$). This unit is known as the newton, or N. Work, or force times distance is the kilogram-meter squared per second squared ($kg\text{-}m^2/s^2$), which is the joule (1 joule = 1 newton-meter), and energy is also expressed in these terms. The abbreviation for joule is J. Power or work per unit time is the kilogram-meter squared per second cubed ($kg\text{-}m^2/s^3$), which is the watt (1 watt = 1 joule per second = 1 newton-meter per second). The abbreviation for watt is W. The term horsepower is not used in the SI and is replaced by the watt, which together with multiples and submultiples—kilowatt and milliwatt, for example—is the same unit as that used in electrical work.

The use of the newton as the unit of force is of particular interest to engineers. In practical work using the English or traditional metric systems of measurements, it is a common practice to apply weight units as force units. Thus, the unit of force in those systems is that force that when applied to unit mass produces an acceleration g rather than unit acceleration. The value of gravitational acceleration g varies around the earth, and thus the weight of a given mass also varies. In an effort to account for this minor error, the kilogram-force and pound-force were introduced, which are defined as the forces due to "standard gravity" acting on bodies of one kilogram or one pound mass, respectively. The standard gravitational acceleration is taken as 9.80665 meters per second squared or 32.174 feet per second squared. The newton is defined as "that force, which when applied to a body having a mass of one kilogram, gives it an acceleration of one meter per second squared." It is independent of g. As a result, the factor g disappears from a wide range of formulas in dynamics. However, in some formulas in statics, where the weight of a body is important rather than its mass, g does appear where it was formerly absent (the weight of a mass of W kilograms is equal to a force of Wg newtons, where g = approximately 9.81 meters per second squared). Details concerning the use of SI units in mechanics calculations are given on page 142 and throughout the Mechanics section in this Handbook. The use of SI units in strength of materials calculations is covered in the section on that subject.

Copyright 2004, Industrial Press, Inc., New York, NY

Decimal multiples and sub-multiples of the SI units are formed by means of the prefixes given in the following table, which represent the numerical factors shown.

Factors and Prefixes for Forming Decimal Multiples of SI Units

Factor by which the unit is multiplied	Prefix	Symbol	Factor by which the unit is multiplied	Prefix	Symbol
10^{12}	tera	T	10^{-2}	centi	c
10^{9}	giga	G	10^{-3}	milli	m
10^{6}	mega	M	10^{-6}	micro	μ
10^{3}	kilo	k	10^{-9}	nano	n
10^{2}	hecto	h	10^{-12}	pico	p
10	deka	da	10^{-15}	femto	f
10^{-1}	deci	d	10^{-18}	atto	a

For more information on SI practice, the reader is referred to the following publications:

Metric Practice Guide, published by the American Society for Testing and Materials, 1916 Race St., Philadelphia, PA 19103.

ISO International Standard 1000. This publication covers the rules for use of SI units, their multiples and sub-multiples. It can be obtained from the American National Standards Institute 11 West 42nd Street, New York, NY 10036.

The International System of Units, Special Publication 330 of the National Bureau of Standards—available from the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.

Binary Multiples.— The International Electrotechnical Commission has assigned the following prefixes to represent exponential binary multiples. This avoids confusion with standard SI decimal prefixes when representing powers of 2, as in bits and bytes.

Symbol	Name	Binary Power	Symbol	Name	Binary Power	Symbol	Name	Binary Power
Ki	kibi	2^{10}	Gi	gibi	2^{30}	Pi	pebi	2^{50}
Mi	mebi	2^{20}	Ti	tebi	2^{40}	Ei	exbi	2^{60}

Example 1: 2 Ki = $2 \times 2^{10} = 2 \times 1{,}024 = 2{,}048$. This does *not* equal 2 K = $2 \times 10^{3} = 2{,}000$.

Example 2: 1 mebibyte = $1 \times 2^{20} = 1{,}048{,}576$ bytes. Again this does *not* equal 1 megabyte = $1 \times 10^{6} = 1{,}000{,}000$ bytes, a value that is often confused with 1,048,576 bytes.

Table 1. International System (SI) Units

Physical Quantity	Name of Unit	Unit Symbol	Definition
Basic SI Units			
Length	meter	m	Distance traveled by light in vacuo during 1/299,792,458 of a second.
Mass	kilogram	kg	Mass of the international prototype which is in the custody of the Bureau International des Poids et Mesures (BIPM) at Sèvres, near Paris.
Time	second	s	The duration of 9,192,631,770 periods of the radiation corresponding to the transition between the two hyperfine levels of the ground state of the cesium-133 atom.
Electric Current	ampere	A	The constant current which, if maintained in two parallel rectilinear conductors of infinite length, of negligible circular cross section, and placed at a distance of one meter apart in a vacuum, would produce between these conductors a force equal to 2×10^{-7} N/m length.
Thermodynamic Temperature	degree kelvin	K	The fraction 1/273.16 of the thermodynamic temperature of the triple point of water.
Amount of Substance	mole	mol	The amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12.
Luminous Intensity	candela	cd	Luminous intensity, in the perpendicular direction, of a surface of 1/600,000 square meter of a black body at the temperature of freezing platinum under a pressure of 101,325 newtons per square meter.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. *(Continued)* International System (SI) Units

Physical Quantity	Name of Unit	Unit Symbol	Definition
SI Units Having Special Names			
Force	newton	N = kg·m/s^2	That force which, when applied to a body having a mass of one kilogram, gives it an acceleration of one meter per second squared.
Work, Energy, Quantity of Heat	joule	J = N·m	The work done when the point of application of a force of one newton is displaced through a distance of one meter in the direction of the force.
Electric Charge	coulomb	C = A·s	The quantity of electricity transported in one second by a current of one ampere.
Electric Potential	volt	V = W/A	The difference of potential between two points of a conducting wire carrying a constant current of one ampere, when the power dissipated between these points is equal to one watt.
Electric Capacitance	farad	F = C/V	The capacitance of a capacitor between the plates of which there appears a difference of potential of one volt when it is charged by a quantity of electricity equal to one coulomb.
Electric Resistance	ohm	Ω = V/A	The resistance between two points of a conductor when a constant difference of potential of one volt, applied between these two points, produces in this conductor a current of one ampere, this conductor not being the source of any electromotive force.
Magnetic Flux	weber	Wb = V·s	The flux which, linking a circuit of one turn produces in it an electromotive force of one volt as it is reduced to zero at a uniform rate in one second.
Inductance	henry	H = V·s/A	The inductance of a closed circuit in which an electromotive force of one volt is produced when the electric current in the circuit varies uniformly at the rate of one ampere per second.
Luminous Flux	lumen	1m = cd·sr	The flux emitted within a unit solid angle of one steradian by a point source having a uniform intensity of one candela.
Illumination	lux	lx = lm/m^2	An illumination of one lumen per square meter.

Table 2. International System (SI) Units with Complex Names

Physical Quantity	SI Unit	Unit Symbol
SI Units Having Complex Names		
Area	square meter	m^2
Volume	cubic meter	m^3
Frequency	hertz[a]	Hz
Density (Mass Density)	kilogram per cubic meter	kg/m^3
Velocity	meter per second	m/s
Angular Velocity	radian per second	rad/s
Acceleration	meter per second squared	m/s^2
Angular Acceleration	radian per second squared	rad/s^2
Pressure	pascal[b]	Pa
Surface Tension	newton per meter	N/m
Dynamic Viscosity	newton second per meter squared	N s/m^2
Kinematic Viscosity Diffusion Coefficient }	meter squared per second	m^2/s
Thermal Conductivity	watt per meter degree Kelvin	W/(m °K)
Electric Field Strength	volt per meter	V/m
Magnetic Flux Density	tesla[c]	T
Magnetic Field Strength	ampere per meter	A/m
Luminance	candela per square meter	cd/m^2

[a] Hz = cycle/second
[b] Pa = newton/meter^2
[c] T = weber/meter^2

Copyright 2004, Industrial Press, Inc., New York, NY

Standard of Length.— In 1866 the United States, by act of Congress, passed a law making legal the meter, the only measure of length that has been legalized by the United States Government. The United States yard is defined by the relation: 1 yard = $^{3600}/_{3937}$ meter. The legal equivalent of the meter for commercial purposes was fixed as 39.37 inches, by law, in July, 1866, and experience having shown that this value was exact within the error of observation, the United States Office of Standard Weights and Measures was, in 1893, authorized to derive the yard from the meter by the use of this relation. The United States prototype meters Nos. 27 and 21 were received from the International Bureau of Weights and Measures in 1889. Meter No. 27, sealed in its metal case, is preserved in a fireproof vault at the Bureau of Standards.

Comparisons made prior to 1893 indicated that the relation of the yard to the meter, fixed by the Act of 1866, was by chance the exact relation between the international meter and the British imperial yard, within the error of observation. A subsequent comparison made between the standards just mentioned indicates that the legal relation adopted by Congress is in error 0.0001 inch; but, in view of the fact that certain comparisons made by the English Standards Office between the imperial yard and its authentic copies show variations as great if not greater than this, it cannot be said with certainty that there is a difference between the imperial yard of Great Britain and the United States yard derived from the meter. The bronze yard No. 11, which was an exact copy of the British imperial yard both in form and material, had shown changes when compared with the imperial yard in 1876 and 1888, which could not reasonably be said to be entirely due to changes in Bronze No. 11. On the other hand, the new meters represented the most advanced ideas of standards, and it therefore seemed that greater stability as well as higher accuracy would be secured by accepting the international meter as a fundamental standard of length.

U.S. Customary Unit System

The USCS is originated from the foot-pound-second unit system or English unit system. The USCS system and English unit system are same for the measures of length and mass, but it varies for the measure of capacity. The U.S. gallon is defined as 231 cubic inches and bushel as 2,150.42 cubic inches where as the corresponding English units are 277.42 cubic inches and 2,219.36 cubic inches.

Fundamental Constants

Name	Symbol	USCS units	SI units
Avogadro's number	N_A		6.022×10^{23} mol^{-1}
Boltzman constant	k	5.65×10^{-24} ft·lb$_f$/°R	1.38065×10^{-23} J/°K
Faraday Constant	F		96487 C/mol
Gravitational constant	g	32.174 lb$_m$-ft/lb$_f$-sec^2	9.80667 m/sec^2
Gravitational constant	G	5.65×10^{-24} ft·lb$_f$/°R	6.672×10^{-11} N.m^2/kg^2
Specific gas constant	R	53.3 ft·lb$_f$/lb$_m$·°R	287 J/kg°K
Universal gas constant	R	1545 ft·lb$_f$/lbmol·°R	8314 J/kmol.°K
Volume (molal ideal gas)	V	359 ft^3/lbmol	22.41 m^3/kmol
Pressure, atmospheric	P	14.696 lb$_f$/in^2	101330 Pa (n/m^2)
Temperature, standard	T	32°F	0°C
Density			
Air at 32°F (0°C)		0.0805 lb$_m$/ft^3	1.29 kg/m^3
Air at 70°F (20°C), 1 atm		0.0749 lb$_m$/ft^3	1.20 kg/m^3
Sea water		64 lb$_m$/ft^3	1025 kg/m^3
Fresh water		62.4 lb$_m$/ft^3	1000 kg/m^3
Mercury		849 lb$_m$/ft^3	13600 kg/m^3
Earth		345 lb$_m$/ft^3	5520 kg/m^3

Copyright 2004, Industrial Press, Inc., New York, NY

U.S. SYSTEM AND METRIC SYSTEM CONVERSIONS

Units of Length

Table 1. Linear Measure Conversion Factors

Metric

1 kilometer (km) =
1000 meters
100,000 centimeters
1,000,000 millimeters
0.539956 nautical mile
0.621371 mile
1093.61 yards
3280.83 feet
39,370.08 inches

1 meter (m) =
10 decimeters
100 centimeters
1000 millimeters
1.09361 yards
3.28084 feet
39.37008 inches

1 decimeter (dm) = **10** centimeters

1 centimeter (cm) =
0.01 meter
10 millimeters
0.0328 foot
0.3937 inch

1 millimeter (mm) =
0.001 meter
0.1 centimeter
1000 micron
0.03937 inch

1 micrometer or *micron (μm) =*
0.000001 meter = one millionth meter
0.0001 centimeter
0.001 millimeter
0.00003937 inch
39.37 micro-inches

US Customary

1 mile (mi) =
0.868976 nautical mile
1760 yards
5280 feet
63,360 inches
1.609344 kilometers
1609.344 meters
160,934.4 centimeters
1,609,344 millimeters

1 yard (yd) =
3 feet
36 inches
0.9144 meter
91.44 centimeter
914.4 millimeter

1 foot (international) (ft) =
12 inches = $\frac{1}{3}$ yard
0.3048 meter
30.48 centimeter
304.8 millimeters

1 survey foot =
1.000002 international feet
$\frac{12}{39.37}$ = 0.3048006096012 meter

1 inch (in) =
1000 mils
1,000,000 micro-inch
2.54 centimeters
25.4 millimeters
25,400 microns

1 mil =
0.001 inch
1000 micro-inches
0.0254 millimeters

1 micro-inch (μin) =
0.000001 inch = one millionth inch
0.0254 micrometer (micron)

Note: Figures in **Bold** indicate exact conversion values

Surveyors Measure

1 mile = **8** furlongs = **80** chains
1 furlong = **10** chains = **220** yards
1 chain =
4 rods = **22** yards = **66** feet = **100** links
1 rod =
5.5 yards = **16.5** feet = **25** links
5.0292 meter
1 link = 7.92 inches
1 span = 9 inches
1 hand = 4 inches

Nautical Measure

1 league = 3 nautical miles
1 nautical mile =
1.1508 statute miles
6076.11549 feet
1.8516 kilometers
1 fathom = **2** yards = **6** feet
1 knot = nautical unit of speed =
1 nautical mile per hour
1.1508 statute miles per hour
1.8516 kilometers per hour

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. *(Continued)* Linear Measure Conversion Factors

One degree at the equator = 60 nautical miles 69.047 statute miles 111.098 kilometers	*360 degrees at the equator =* circumference at equator 21,600 nautical miles 24,856.8 statute miles 39,995.4 kilometers
One minute at the equator = 1 nautical mile 1.1508 statute miles 1.8516 kilometers	

Table 2. Circular and Angular Measure Conversion Factors

circumference of circle = 360 degrees = 2π radian = 6.283185 radian	*1 degree (°) =* 60 minutes = 3600 seconds = π/180 radian = 0.017453 radian
1 quadrant = 90 degrees = π/2 radian = 1.570796 radian	*1 minute (′) =* 60 seconds = 0.016667 degrees = 0.000291 radian
1 radian = 57.2957795 degrees	π = 3.141592654

Table 3. Feet and Inches to Inches Conversion

Inches →	0	1	2	3	4	5	6	7	8	9	10	11
Feet ↓	Inches											
0	0	1	2	3	4	5	6	7	8	9	10	11
1	12	13	14	15	16	17	18	19	20	21	22	23
2	24	25	26	27	28	29	30	31	32	33	34	35
3	36	37	38	39	40	41	42	43	44	45	46	47
4	48	49	50	51	52	53	54	55	56	57	58	59
5	60	61	62	63	64	65	66	67	68	69	70	71
6	72	73	74	75	76	77	78	79	80	81	82	83
7	84	85	86	87	88	89	90	91	92	93	94	95
8	96	97	98	99	100	101	102	103	104	105	106	107
9	108	109	110	111	112	113	114	115	116	117	118	119
10	120	121	122	123	124	125	126	127	128	129	130	131
20	240	241	242	243	244	245	246	247	248	249	250	251
30	360	361	362	363	364	365	366	367	368	369	370	371
40	480	481	482	483	484	485	486	487	488	489	490	491
50	600	601	602	603	604	605	606	607	608	609	610	611
60	720	721	722	723	724	725	726	727	728	729	730	731
70	840	841	842	843	844	845	846	847	848	849	850	851
80	960	961	962	963	964	965	966	967	968	969	970	971
90	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091
100	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211

Example: A tape measure reads 17 feet 8 inches. How many inches is this? *Solution:* Read down the first column of Table 3 to find 10 ft 0 inch = 120 inches. Next, find the intersection of the 7 ft row and the 8 inch column to get 92 inches. Add both results to get 120 inches + 92 inches = 212 inches.

Table 4. Inches to Feet and Yards Conversion

inch	feet	yard	inch	feet	yard	inch	feet	yard	inch	feet	yard	inch	feet	yard
100	8.3333	2.7778	10	0.8333	0.2778	1	0.0833	0.0278	0.1	0.0083	0.0028	0.01	0.0008	0.0003
200	16.6667	5.5556	20	1.6667	0.5556	2	0.1667	0.0556	0.2	0.0167	0.0056	0.02	0.0017	0.0006
300	25	8.3333	30	2.5	0.8333	3	0.25	0.0833	0.3	0.025	0.0083	0.03	0.0025	0.0008
400	33.3333	11.1111	40	3.3333	1.1111	4	0.3333	0.1111	0.4	0.0333	0.0111	0.04	0.0033	0.0011
500	41.6667	13.8889	50	4.1667	1.3889	5	0.4167	0.1389	0.5	0.0417	0.0139	0.05	0.0042	0.0014
600	50	16.6667	60	5	1.6667	6	0.5	0.1667	0.6	0.05	0.0167	0.06	0.005	0.0017
700	58.3333	19.4444	70	5.8333	1.9444	7	0.5833	0.1944	0.7	0.0583	0.0194	0.07	0.0058	0.0019
800	66.6667	22.2222	80	6.6667	2.2222	8	0.6667	0.2222	0.8	0.0667	0.0222	0.08	0.0067	0.0022
900	75	25.0000	90	7.5	2.5000	9	0.75	0.2500	0.9	0.075	0.0250	0.09	0.0075	0.0025
1000	83.3333	27.7778	100	8.3333	2.7778	10	0.8333	0.2778	1	0.0833	0.0278	0.1	0.0083	0.0028

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Fractional Inches to Decimal Feet for 0 to 1 Foot

→ Inches ↓	0	1	2	3	4	5	6	7	8	9	10	11
	Feet											
0	0.0000	0.0833	0.1667	0.2500	0.3333	0.4167	0.5000	0.5833	0.6667	0.7500	0.8333	0.9167
1/64	0.0013	0.0846	0.1680	0.2513	0.3346	0.4180	0.5013	0.5846	0.6680	0.7513	0.8346	0.9180
1/32	0.0026	0.0859	0.1693	0.2526	0.3359	0.4193	0.5026	0.5859	0.6693	0.7526	0.8359	0.9193
3/64	0.0039	0.0872	0.1706	0.2539	0.3372	0.4206	0.5039	0.5872	0.6706	0.7539	0.8372	0.9206
1/16	0.0052	0.0885	0.1719	0.2552	0.3385	0.4219	0.5052	0.5885	0.6719	0.7552	0.8385	0.9219
5/64	0.0065	0.0898	0.1732	0.2565	0.3398	0.4232	0.5065	0.5898	0.6732	0.7565	0.8398	0.9232
3/32	0.0078	0.0911	0.1745	0.2578	0.3411	0.4245	0.5078	0.5911	0.6745	0.7578	0.8411	0.9245
7/64	0.0091	0.0924	0.1758	0.2591	0.3424	0.4258	0.5091	0.5924	0.6758	0.7591	0.8424	0.9258
1/8	0.0104	0.0938	0.1771	0.2604	0.3438	0.4271	0.5104	0.5938	0.6771	0.7604	0.8438	0.9271
9/64	0.0117	0.0951	0.1784	0.2617	0.3451	0.4284	0.5117	0.5951	0.6784	0.7617	0.8451	0.9284
5/32	0.0130	0.0964	0.1797	0.2630	0.3464	0.4297	0.5130	0.5964	0.6797	0.7630	0.8464	0.9297
11/64	0.0143	0.0977	0.1810	0.2643	0.3477	0.4310	0.5143	0.5977	0.6810	0.7643	0.8477	0.9310
3/16	0.0156	0.0990	0.1823	0.2656	0.3490	0.4323	0.5156	0.5990	0.6823	0.7656	0.8490	0.9323
13/64	0.0169	0.1003	0.1836	0.2669	0.3503	0.4336	0.5169	0.6003	0.6836	0.7669	0.8503	0.9336
7/32	0.0182	0.1016	0.1849	0.2682	0.3516	0.4349	0.5182	0.6016	0.6849	0.7682	0.8516	0.9349
15/64	0.0195	0.1029	0.1862	0.2695	0.3529	0.4362	0.5195	0.6029	0.6862	0.7695	0.8529	0.9362
1/4	0.0208	0.1042	0.1875	0.2708	0.3542	0.4375	0.5208	0.6042	0.6875	0.7708	0.8542	0.9375
17/64	0.0221	0.1055	0.1888	0.2721	0.3555	0.4388	0.5221	0.6055	0.6888	0.7721	0.8555	0.9388
9/32	0.0234	0.1068	0.1901	0.2734	0.3568	0.4401	0.5234	0.6068	0.6901	0.7734	0.8568	0.9401
19/64	0.0247	0.1081	0.1914	0.2747	0.3581	0.4414	0.5247	0.6081	0.6914	0.7747	0.8581	0.9414
5/16	0.0260	0.1094	0.1927	0.2760	0.3594	0.4427	0.5260	0.6094	0.6927	0.7760	0.8594	0.9427
21/64	0.0273	0.1107	0.1940	0.2773	0.3607	0.4440	0.5273	0.6107	0.6940	0.7773	0.8607	0.9440
11/32	0.0286	0.1120	0.1953	0.2786	0.3620	0.4453	0.5286	0.6120	0.6953	0.7786	0.8620	0.9453
23/64	0.0299	0.1133	0.1966	0.2799	0.3633	0.4466	0.5299	0.6133	0.6966	0.7799	0.8633	0.9466
3/8	0.0313	0.1146	0.1979	0.2813	0.3646	0.4479	0.5313	0.6146	0.6979	0.7813	0.8646	0.9479
25/64	0.0326	0.1159	0.1992	0.2826	0.3659	0.4492	0.5326	0.6159	0.6992	0.7826	0.8659	0.9492
13/32	0.0339	0.1172	0.2005	0.2839	0.3672	0.4505	0.5339	0.6172	0.7005	0.7839	0.8672	0.9505
27/64	0.0352	0.1185	0.2018	0.2852	0.3685	0.4518	0.5352	0.6185	0.7018	0.7852	0.8685	0.9518
7/16	0.0365	0.1198	0.2031	0.2865	0.3698	0.4531	0.5365	0.6198	0.7031	0.7865	0.8698	0.9531
29/64	0.0378	0.1211	0.2044	0.2878	0.3711	0.4544	0.5378	0.6211	0.7044	0.7878	0.8711	0.9544
15/32	0.0391	0.1224	0.2057	0.2891	0.3724	0.4557	0.5391	0.6224	0.7057	0.7891	0.8724	0.9557
31/64	0.0404	0.1237	0.2070	0.2904	0.3737	0.4570	0.5404	0.6237	0.7070	0.7904	0.8737	0.9570
1/2	0.0417	0.1250	0.2083	0.2917	0.3750	0.4583	0.5417	0.6250	0.7083	0.7917	0.8750	0.9583
33/64	0.0430	0.1263	0.2096	0.2930	0.3763	0.4596	0.5430	0.6263	0.7096	0.7930	0.8763	0.9596
17/32	0.0443	0.1276	0.2109	0.2943	0.3776	0.4609	0.5443	0.6276	0.7109	0.7943	0.8776	0.9609
35/64	0.0456	0.1289	0.2122	0.2956	0.3789	0.4622	0.5456	0.6289	0.7122	0.7956	0.8789	0.9622
9/16	0.0469	0.1302	0.2135	0.2969	0.3802	0.4635	0.5469	0.6302	0.7135	0.7969	0.8802	0.9635
37/64	0.0482	0.1315	0.2148	0.2982	0.3815	0.4648	0.5482	0.6315	0.7148	0.7982	0.8815	0.9648
19/32	0.0495	0.1328	0.2161	0.2995	0.3828	0.4661	0.5495	0.6328	0.7161	0.7995	0.8828	0.9661
39/64	0.0508	0.1341	0.2174	0.3008	0.3841	0.4674	0.5508	0.6341	0.7174	0.8008	0.8841	0.9674
5/8	0.0521	0.1354	0.2188	0.3021	0.3854	0.4688	0.5521	0.6354	0.7188	0.8021	0.8854	0.9688
41/64	0.0534	0.1367	0.2201	0.3034	0.3867	0.4701	0.5534	0.6367	0.7201	0.8034	0.8867	0.9701
21/32	0.0547	0.1380	0.2214	0.3047	0.3880	0.4714	0.5547	0.6380	0.7214	0.8047	0.8880	0.9714
43/64	0.0560	0.1393	0.2227	0.3060	0.3893	0.4727	0.5560	0.6393	0.7227	0.8060	0.8893	0.9727
11/16	0.0573	0.1406	0.2240	0.3073	0.3906	0.4740	0.5573	0.6406	0.7240	0.8073	0.8906	0.9740
45/64	0.0586	0.1419	0.2253	0.3086	0.3919	0.4753	0.5586	0.6419	0.7253	0.8086	0.8919	0.9753
23/32	0.0599	0.1432	0.2266	0.3099	0.3932	0.4766	0.5599	0.6432	0.7266	0.8099	0.8932	0.9766
47/64	0.0612	0.1445	0.2279	0.3112	0.3945	0.4779	0.5612	0.6445	0.7279	0.8112	0.8945	0.9779
3/4	0.0625	0.1458	0.2292	0.3125	0.3958	0.4792	0.5625	0.6458	0.7292	0.8125	0.8958	0.9792
49/64	0.0638	0.1471	0.2305	0.3138	0.3971	0.4805	0.5638	0.6471	0.7305	0.8138	0.8971	0.9805
25/32	0.0651	0.1484	0.2318	0.3151	0.3984	0.4818	0.5651	0.6484	0.7318	0.8151	0.8984	0.9818
51/64	0.0664	0.1497	0.2331	0.3164	0.3997	0.4831	0.5664	0.6497	0.7331	0.8164	0.8997	0.9831
13/16	0.0677	0.1510	0.2344	0.3177	0.4010	0.4844	0.5677	0.6510	0.7344	0.8177	0.9010	0.9844
53/64	0.0690	0.1523	0.2357	0.3190	0.4023	0.4857	0.5690	0.6523	0.7357	0.8190	0.9023	0.9857
27/32	0.0703	0.1536	0.2370	0.3203	0.4036	0.4870	0.5703	0.6536	0.7370	0.8203	0.9036	0.9870
55/64	0.0716	0.1549	0.2383	0.3216	0.4049	0.4883	0.5716	0.6549	0.7383	0.8216	0.9049	0.9883
7/8	0.0729	0.1563	0.2396	0.3229	0.4063	0.4896	0.5729	0.6563	0.7396	0.8229	0.9063	0.9896
57/64	0.0742	0.1576	0.2409	0.3242	0.4076	0.4909	0.5742	0.6576	0.7409	0.8242	0.9076	0.9909
29/32	0.0755	0.1589	0.2422	0.3255	0.4089	0.4922	0.5755	0.6589	0.7422	0.8255	0.9089	0.9922
59/64	0.0768	0.1602	0.2435	0.3268	0.4102	0.4935	0.5768	0.6602	0.7435	0.8268	0.9102	0.9935
15/16	0.0781	0.1615	0.2448	0.3281	0.4115	0.4948	0.5781	0.6615	0.7448	0.8281	0.9115	0.9948
61/64	0.0794	0.1628	0.2461	0.3294	0.4128	0.4961	0.5794	0.6628	0.7461	0.8294	0.9128	0.9961
31/32	0.0807	0.1641	0.2474	0.3307	0.4141	0.4974	0.5807	0.6641	0.7474	0.8307	0.9141	0.9974
63/64	0.0820	0.1654	0.2487	0.3320	0.4154	0.4987	0.5820	0.6654	0.7487	0.8320	0.9154	0.9987
1	0.0833	0.1667	0.2500	0.3333	0.4167	0.5000	0.5833	0.6667	0.7500	0.8333	0.9167	1.0000

Example: Convert 78¾ inches to feet. *Solution:* From Table 4, find 70 inches = 5.8333 feet and add to that 8¾ inches = 0.7292 feet found in Table 8a at the intersection of the ¾ inch row and the 8 inch column. Thus, 78¾ inches = 5.8333 + 0.7292 = 6.5625 feet.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Feet to Inches Conversion

feet	inch	feet	inch	feet	inch	feet	inch	feet	inch	feet	inch	feet	inch
100	1200	10	120	1	12	0.1	1.2	0.01	0.12	0.001	0.012	0.0001	0.0012
200	2400	20	240	2	24	0.2	2.4	0.02	0.24	0.002	0.024	0.0002	0.0024
300	3600	30	360	3	36	0.3	3.6	0.03	0.36	0.003	0.036	0.0003	0.0036
400	4800	40	480	4	48	0.4	4.8	0.04	0.48	0.004	0.048	0.0004	0.0048
500	6000	50	600	5	60	0.5	6	0.05	0.6	0.005	0.06	0.0005	0.006
600	7200	60	720	6	72	0.6	7.2	0.06	0.72	0.006	0.072	0.0006	0.0072
700	8400	70	840	7	84	0.7	8.4	0.07	0.84	0.007	0.084	0.0007	0.0084
800	9600	80	960	8	96	0.8	9.6	0.08	0.96	0.008	0.096	0.0008	0.0096
900	10800	90	1080	9	108	0.9	10.8	0.09	1.08	0.009	0.108	0.0009	0.0108
1000	12000	100	1200	10	120	1	12	0.1	1.2	0.01	0.12	0.001	0.012

Table 7. Fractional Inch to Decimal Inch and Millimeter

Fractional Inch	Decimal Inch	Millimeters	Fractional Inch	Decimal Inch	Millimeters
1/64	0.015625	0.396875		0.511811024	13
1/32	0.03125	0.79375	33/64	0.515625	13.096875
	0.039370079	1	17/32	0.53125	13.49375
3/64	0.046875	1.190625	35/64	0.546875	13.890625
1/16	0.0625	1.5875		0.551181102	14
5/64	0.078125	1.984375	9/16	0.5625	14.2875
	0.078740157	2	37/64	0.578125	14.684375
3/32	0.09375	2.38125		0.590551181	15
7/64	0.109375	2.778125	19/32	0.59375	15.08125
	0.118110236	3	39/64	0.609375	15.478125
1/8	0.125	3.175	5/8	0.625	15.875
9/64	0.140625	3.571875		0.62992126	16
5/32	0.15625	3.96875	41/64	0.640625	16.271875
	0.157480315	4	21/32	0.65625	16.66875
11/64	0.171875	4.365625		0.669291339	17
3/16	0.1875	4.7625	43/64	0.671875	17.065625
	0.196850394	5	11/16	0.6875	17.4625
13/64	0.203125	5.159375	45/64	0.703125	17.859375
7/32	0.21875	5.55625		0.708661417	18
15/64	0.234375	5.953125	23/32	0.71875	18.25625
	0.236220472	6	47/64	0.734375	18.653125
1/4	0.25	6.35		0.748031496	19
17/64	0.265625	6.746875	3/4	0.75	19.05
	0.275590551	7	49/64	0.765625	19.446875
9/32	0.28125	7.14375	25/32	0.78125	19.84375
19/64	0.296875	7.540625		0.787401575	20
5/16	0.3125	7.9375	51/64	0.796875	20.240625
	0.31496063	8	13/16	0.8125	20.6375
21/64	0.328125	8.334375		0.826771654	21
11/32	0.34375	8.73125	53/64	0.828125	21.034375
	0.354330709	9	27/32	0.84375	21.43125
23/64	0.359375	9.128125	55/64	0.859375	21.828125
3/8	0.375	9.525		0.866141732	22
25/64	0.390625	9.921875	7/8	0.875	22.225
	0.393700787	10	57/64	0.890625	22.621875
13/32	0.40625	10.31875		0.905511811	23
27/64	0.421875	10.715625	29/32	0.90625	23.01875
	0.433070866	11	59/64	0.921875	23.415625
7/16	0.4375	11.1125	15/16	0.9375	23.8125
29/64	0.453125	11.509375		0.94488189	24
15/32	0.46875	11.90625	61/64	0.953125	24.209375
	0.472440945	12	31/32	0.96875	24.60625
31/64	0.484375	12.303125		0.984251969	25
1/2	0.5	12.7	63/64	0.984375	25.003125

Copyright 2004, Industrial Press, Inc., New York, NY

Table 8a. Inch to Millimeters Conversion

inch	mm	inch	mm	inch	mm	inch	mm	inch	mm	inch	mm
10	254.00000	1	25.40000	0.1	2.54000	.01	0.25400	0.001	0.02540	0.0001	0.00254
20	508.00000	2	50.80000	0.2	5.08000	.02	0.50800	0.002	0.05080	0.0002	0.00508
30	762.00000	3	76.20000	0.3	7.62000	.03	0.76200	0.003	0.07620	0.0003	0.00762
40	1,016.00000	4	101.60000	0.4	10.16000	.04	1.01600	0.004	0.10160	0.0004	0.01016
50	1,270.00000	5	127.00000	0.5	12.70000	.05	1.27000	0.005	0.12700	0.0005	0.01270
60	1,524.00000	6	152.40000	0.6	15.24000	.06	1.52400	0.006	0.15240	0.0006	0.01524
70	1,778.00000	7	177.80000	0.7	17.78000	.07	1.77800	0.007	0.17780	0.0007	0.01778
80	2,032.00000	8	203.20000	0.8	20.32000	.08	2.03200	0.008	0.20320	0.0008	0.02032
90	2,286.00000	9	228.60000	0.9	22.86000	.09	2.2860	0.009	0.22860	0.0009	0.02286
100	2,540.00000	10	254.00000	1.0	25.40000	.10	2.54000	0.010	0.25400	0.0010	0.02540

All values in this table are exact. For inches to centimeters, shift decimal point in mm column one place to left and read centimeters, thus, for example, 40 in. = 1016 mm = 101.6 cm.

Table 8b. Millimeters to Inch Conversion

mm	inch	mm	inch	mm	inch	mm	inch	mm	inch	mm	inch
100	3.93701	10	0.39370	1	0.03937	0.1	0.00394	0.01	.000039	0.001	0.00004
200	7.87402	20	0.78740	2	0.07874	0.2	0.00787	0.02	.00079	0.002	0.00008
300	11.81102	30	1.18110	3	0.11811	0.3	0.01181	0.03	.00118	0.003	0.00012
400	15.74803	40	1.57480	4	0.15748	0.4	0.01575	0.04	.00157	0.004	0.00016
500	19.68504	50	1.96850	5	0.19685	0.5	0.01969	0.05	.00197	0.005	0.00020
600	23.62205	60	2.36220	6	0.23622	0.6	0.02362	0.06	.00236	0.006	0.00024
700	27.55906	70	2.75591	7	0.27559	0.7	0.02756	0.07	.00276	0.007	0.00028
800	31.49606	80	3.14961	8	0.31496	0.8	0.03150	0.08	.00315	0.008	0.00031
900	35.43307	90	3.54331	9	0.35433	0.9	0.03543	0.09	.00354	0.009	0.00035
1,000	39.37008	100	3.93701	10	0.39370	1.0	0.03937	0.10	.00394	0.010	0.00039

Based on 1 inch = 25.4 millimeters, exactly. For centimeters to inches, shift decimal point of centimeter value one place to right and enter mm column, thus, for example, 70 cm = 700 mm = 27.55906 inches.

Table 9. Feet to Millimeters Conversion

feet	mm	feet	mm	feet	mm	feet	mm	feet	mm
100	30,480	10	3,048	1	304.8	0.1	30.48	0.01	3.048
200	60,960	20	6,096	2	609.6	0.2	60.96	0.02	6.096
300	91,440	30	9,144	3	914.4	0.3	91.44	0.03	9.144
400	121,920	40	12,192	4	1,219.2	0.4	121.92	0.04	12.192
500	152,400	50	15,240	5	1,524.0	0.5	152.40	0.05	15.240
600	182,880	60	18,288	6	1,828.8	0.6	182.88	0.06	18.288
700	213,360	70	21,336	7	2,133.6	0.7	213.36	0.07	21.336
800	243,840	80	24,384	8	2,438.4	0.8	243.84	0.08	24.384
900	274,320	90	27,432	9	2,743.2	0.9	274.32	0.09	27.432
1,000	304,800	100	30,480	10	3,048.0	1.0	304.80	0.10	30.480

Based on 1 inch = 25.4 millimeters, exactly. All values in this table are exact.

Example 1: Convert 293 feet, $5\frac{47}{64}$ inches to mm.

200 ft		=	60,960.0	mm
90 ft		=	27,432.0	mm
3 ft		=	914.4	mm
5	inch	=	127.0	mm
$\frac{47}{64}$	inch	=	18.653	mm
293 ft $5\frac{47}{64}$	inch	=	89,452.053	mm

Example 2: Convert 71.86 feet to mm.

70.0	feet	=	21,336.0	mm
1.0	feet	=	304.8	mm
0.80	feet	=	243.84	mm
0.06	feet	=	18.288	mm
71.86	feet	=	21,902.928	mm

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Mixed Fractional Inches to Millimeters Conversion for 0 to 41 Inches in 1/64-Inch Increments

→ Inches↓	0	1	2	3	4	5	6	7	8	9	10	20	30	40
	Millimeters													
0	0	25.4	50.8	76.2	101.6	127.0	152.4	177.8	203.2	228.6	254.0	508.0	762.0	1016.0
1/64	0.396875	25.796875	51.196875	76.596875	101.996875	127.396875	152.796875	178.196875	203.596875	228.996875	254.396875	508.396875	762.396875	1016.396875
1/32	0.79375	26.19375	51.59375	76.99375	102.39375	127.79375	153.19375	178.59375	203.99375	229.39375	254.79375	508.79375	762.79375	1016.79375
3/64	1.190625	26.590625	51.990625	77.390625	102.790625	128.190625	153.590625	178.990625	204.390625	229.790625	255.190625	509.190625	763.190625	1017.190625
1/16	1.5875	26.9875	52.3875	77.7875	103.1875	128.5875	153.9875	179.3875	204.7875	230.1875	255.5875	509.5875	763.5875	1017.5875
5/64	1.984375	27.384375	52.784375	78.184375	103.584375	128.984375	154.384375	179.784375	205.184375	230.584375	255.984375	509.984375	763.984375	1017.984375
3/32	2.38125	27.78125	53.18125	78.58125	103.98125	129.38125	154.78125	180.18125	205.58125	230.98125	256.38125	510.38125	764.38125	1018.38125
7/64	2.778125	28.178125	53.578125	78.978125	104.378125	129.778125	155.178125	180.578125	205.978125	231.378125	256.778125	510.778125	764.778125	1018.778125
1/8	3.175	28.575	53.975	79.375	104.775	130.175	155.575	180.975	206.375	231.775	257.175	511.175	765.175	1019.175
9/64	3.571875	28.971875	54.371875	79.771875	105.171875	130.571875	155.971875	181.371875	206.771875	232.171875	257.571875	511.571875	765.571875	1019.571875
5/32	3.96875	29.36875	54.76875	80.16875	105.56875	130.96875	156.36875	181.76875	207.16875	232.56875	257.96875	511.96875	765.96875	1019.96875
11/64	4.365625	29.765625	55.165625	80.565625	105.965625	131.365625	156.765625	182.165625	207.565625	232.965625	258.365625	512.365625	766.365625	1020.365625
3/16	4.7625	30.1625	55.5625	80.9625	106.3625	131.7625	157.1625	182.5625	207.9625	233.3625	258.7625	512.7625	766.7625	1020.7625
13/64	5.159375	30.559375	55.959375	81.359375	106.759375	132.159375	157.559375	182.959375	208.359375	233.759375	259.159375	513.159375	767.159375	1021.159375
7/32	5.55625	30.95625	56.35625	81.75625	107.15625	132.55625	157.95625	183.35625	208.75625	234.15625	259.55625	513.55625	767.55625	1021.55625
15/64	5.953125	31.353125	56.753125	82.153125	107.553125	132.953125	158.353125	183.753125	209.153125	234.553125	259.953125	513.953125	767.953125	1021.953125
1/4	6.35	31.75	57.15	82.55	107.95	133.35	158.75	184.15	209.55	234.95	260.35	514.35	768.35	1022.35
17/64	6.746875	32.146875	57.546875	82.946875	108.346875	133.746875	159.146875	184.546875	209.946875	235.346875	260.746875	514.746875	768.746875	1022.746875
9/32	7.14375	32.54375	57.94375	83.34375	108.74375	134.14375	159.54375	184.94375	210.34375	235.74375	261.14375	515.14375	769.14375	1023.14375
19/64	7.540625	32.940625	58.340625	83.740625	109.140625	134.540625	159.940625	185.340625	210.740625	236.140625	261.540625	515.540625	769.540625	1023.540625
5/16	7.9375	33.3375	58.7375	84.1375	109.5375	134.9375	160.3375	185.7375	211.1375	236.5375	261.9375	515.9375	769.9375	1023.9375
21/64	8.334375	33.734375	59.134375	84.534375	109.934375	135.334375	160.734375	186.134375	211.534375	236.934375	262.334375	516.334375	770.334375	1024.334375
11/32	8.73125	34.13125	59.53125	84.93125	110.33125	135.73125	161.13125	186.53125	211.93125	237.33125	262.73125	516.73125	770.73125	1024.73125
23/64	9.128125	34.528125	59.928125	85.328125	110.728125	136.128125	161.528125	186.928125	212.328125	237.728125	263.128125	517.128125	771.128125	1025.128125
3/8	9.525	34.925	60.325	85.725	111.125	136.525	161.925	187.325	212.725	238.125	263.525	517.525	771.525	1025.525
25/64	9.921875	35.321875	60.721875	86.121875	111.521875	136.921875	162.321875	187.721875	213.121875	238.521875	263.921875	517.921875	771.921875	1025.921875
13/32	10.31875	35.71875	61.11875	86.51875	111.91875	137.31875	162.71875	188.11875	213.51875	238.91875	264.31875	518.31875	772.31875	1026.31875
27/64	10.715625	36.115625	61.515625	86.915625	112.315625	137.715625	163.115625	188.515625	213.915625	239.315625	264.715625	518.715625	772.715625	1026.715625
7/16	11.1125	36.5125	61.9125	87.3125	112.7125	138.1125	163.5125	188.9125	214.3125	239.7125	265.1125	519.1125	773.1125	1027.1125
29/64	11.509375	36.909375	62.309375	87.709375	113.109375	138.509375	163.909375	189.309375	214.709375	240.109375	265.509375	519.509375	773.509375	1027.509375
15/32	11.90625	37.30625	62.70625	88.10625	113.50625	138.90625	164.30625	189.70625	215.10625	240.50625	265.90625	519.90625	773.90625	1027.90625
31/64	12.303125	37.703125	63.103125	88.503125	113.903125	139.303125	164.703125	190.103125	215.503125	240.903125	266.303125	520.303125	774.303125	1028.303125
1/2	12.7	38.1	63.5	88.9	114.3	139.7	165.1	190.5	215.9	241.3	266.7	520.7	774.7	1028.7

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. ***(Continued)*** **Mixed Fractional Inches to Millimeters Conversion for 0 to 41 Inches in $\frac{1}{64}$-Inch Increments**

→ Inches↓	0	1	2	3	4	5	6	7	8	9	10	20	30	40
	Millimeters													
33/64	13.096875	38.496875	63.896875	89.296875	114.696875	140.096875	165.496875	190.896875	216.296875	241.696875	267.096875	521.096875	775.096875	1029.096875
17/32	13.49375	38.89375	64.29375	89.69375	115.09375	140.49375	165.89375	191.29375	216.69375	242.09375	267.49375	521.49375	775.49375	1029.49375
35/64	13.890625	39.290625	64.690625	90.090625	115.490625	140.890625	166.290625	191.690625	217.090625	242.490625	267.890625	521.890625	775.890625	1029.890625
9/16	14.2875	39.6875	65.0875	90.4875	115.8875	141.2875	166.6875	192.0875	217.4875	242.8875	268.2875	522.2875	776.2875	1030.2875
37/64	14.684375	40.084375	65.484375	90.884375	116.284375	141.684375	167.084375	192.484375	217.884375	243.284375	268.684375	522.684375	776.684375	1030.684375
19/32	15.08125	40.48125	65.88125	91.28125	116.68125	142.08125	167.48125	192.88125	218.28125	243.68125	269.08125	523.08125	777.08125	1031.08125
39/64	15.478125	40.878125	66.278125	91.678125	117.078125	142.478125	167.878125	193.278125	218.678125	244.078125	269.478125	523.478125	777.478125	1031.478125
5/8	15.875	41.275	66.675	92.075	117.475	142.875	168.275	193.675	219.075	244.475	269.875	523.875	777.875	1031.875
41/64	16.271875	41.671875	67.071875	92.471875	117.871875	143.271875	168.671875	194.071875	219.471875	244.871875	270.271875	524.271875	778.271875	1032.271875
21/32	16.66875	42.06875	67.46875	92.86875	118.26875	143.66875	169.06875	194.46875	219.86875	245.26875	270.66875	524.66875	778.66875	1032.66875
43/64	17.065625	42.465625	67.865625	93.265625	118.665625	144.065625	169.465625	194.865625	220.265625	245.665625	271.065625	525.065625	779.065625	1033.065625
11/16	17.4625	42.8625	68.2625	93.6625	119.0625	144.4625	169.8625	195.2625	220.6625	246.0625	271.4625	525.4625	779.4625	1033.4625
45/64	17.859375	43.259375	68.659375	94.059375	119.459375	144.859375	170.259375	195.659375	221.059375	246.459375	271.859375	525.859375	779.859375	1033.859375
23/32	18.25625	43.65625	69.05625	94.45625	119.85625	145.25625	170.65625	196.05625	221.45625	246.85625	272.25625	526.25625	780.25625	1034.25625
47/64	18.653125	44.053125	69.453125	94.853125	120.253125	145.653125	171.053125	196.453125	221.853125	247.253125	272.653125	526.653125	780.653125	1034.653125
3/4	19.05	44.45	69.85	95.25	120.65	146.05	171.45	196.85	222.25	247.65	273.05	527.05	781.05	1035.05
49/64	19.446875	44.846875	70.246875	95.646875	121.046875	146.446875	171.846875	197.246875	222.646875	248.046875	273.446875	527.446875	781.446875	1035.446875
25/32	19.84375	45.24375	70.64375	96.04375	121.44375	146.84375	172.24375	197.64375	223.04375	248.44375	273.84375	527.84375	781.84375	1035.84375
51/64	20.240625	45.640625	71.040625	96.440625	121.840625	147.240625	172.640625	198.040625	223.440625	248.840625	274.240625	528.240625	782.240625	1036.240625
13/16	20.6375	46.0375	71.4375	96.8375	122.2375	147.6375	173.0375	198.4375	223.8375	249.2375	274.6375	528.6375	782.6375	1036.6375
53/64	21.034375	46.434375	71.834375	97.234375	122.634375	148.034375	173.434375	198.834375	224.234375	249.634375	275.034375	529.034375	783.034375	1037.034375
27/32	21.43125	46.83125	72.23125	97.63125	123.03125	148.43125	173.83125	199.23125	224.63125	250.03125	275.43125	529.43125	783.43125	1037.43125
55/64	21.828125	47.228125	72.628125	98.028125	123.428125	148.828125	174.228125	199.628125	225.028125	250.428125	275.828125	529.828125	783.828125	1037.828125
7/8	22.225	47.625	73.025	98.425	123.825	149.225	174.625	200.025	225.425	250.825	276.225	530.225	784.225	1038.225
57/64	22.621875	48.021875	73.421875	98.821875	124.221875	149.621875	175.021875	200.421875	225.821875	251.221875	276.621875	530.621875	784.621875	1038.621875
29/32	23.01875	48.41875	73.81875	99.21875	124.61875	150.01875	175.41875	200.81875	226.21875	251.61875	277.01875	531.01875	785.01875	1039.01875
59/64	23.415625	48.815625	74.215625	99.615625	125.015625	150.415625	175.815625	201.215625	226.615625	252.015625	277.415625	531.415625	785.415625	1039.415625
15/16	23.8125	49.2125	74.6125	100.0125	125.4125	150.8125	176.2125	201.6125	227.0125	252.4125	277.8125	531.8125	785.8125	1039.8125
61/64	24.209375	49.609375	75.009375	100.409375	125.809375	151.209375	176.609375	202.009375	227.409375	252.809375	278.209375	532.209375	786.209375	1040.209375
31/32	24.60625	50.00625	75.40625	100.80625	126.20625	151.60625	177.00625	202.40625	227.80625	253.20625	278.60625	532.60625	786.60625	1040.60625
63/64	25.003125	50.403125	75.803125	101.203125	126.603125	152.003125	177.403125	202.803125	228.203125	253.603125	279.003125	533.003125	787.003125	1041.003125
1	25.4	50.8	76.2	101.6	127	152.4	177.8	203.2	228.6	254	279.4	533.4	787.4	1041.4

Based on 1 inch = 25.4 millimeters, exactly. All values in this table are exact. *Example:* Convert $21\frac{23}{64}$ inches to millimeters. *Solution:* From the first page of this table, find 20 inches = 508.0 millimeters and add to that $1\frac{23}{64}$ inches = 34.528125 millimeters found at the intersection of the 1- inch column and the row containing $\frac{23}{64}$ inch . Thus, $21\frac{23}{64}$ inches = 508.0 + 34.528125 = 542.528125 mm, exactly.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. Decimals of an Inch to Millimeters Conversion

→ Inches ↓	0.000	0.001	0.002	0.003	0.004	0.005	0.006	0.007	0.008	0.009
	Millimeters									
0.000	…	0.0254	0.0508	0.0762	0.1016	0.1270	0.1524	0.1778	0.2032	0.2286
0.010	0.2540	0.2794	0.3048	0.3302	0.3556	0.3810	0.4064	0.4318	0.4572	0.4826
0.020	0.5080	0.5334	0.5588	0.5842	0.6096	0.6350	0.6604	0.6858	0.7112	0.7366
0.030	0.7620	0.7874	0.8128	0.8382	0.8636	0.8890	0.9144	0.9398	0.9652	0.9906
0.040	1.0160	1.0414	1.0668	1.0922	1.1176	1.1430	1.1684	1.1938	1.2192	1.2446
0.050	1.2700	1.2954	1.3208	1.3462	1.3716	1.3970	1.4224	1.4478	1.4732	1.4986
0.060	1.5240	1.5494	1.5748	1.6002	1.6256	1.6510	1.6764	1.7018	1.7272	1.7526
0.070	1.7780	1.8034	1.8288	1.8542	1.8796	1.9050	1.9304	1.9558	1.9812	2.0066
0.080	2.0320	2.0574	2.0828	2.1082	2.1336	2.1590	2.1844	2.2098	2.2352	2.2606
0.090	2.2860	2.3114	2.3368	2.3622	2.3876	2.4130	2.4384	2.4638	2.4892	2.5146
0.100	2.5400	2.5654	2.5908	2.6162	2.6416	2.6670	2.6924	2.7178	2.7432	2.7686
0.110	2.7940	2.8194	2.8448	2.8702	2.8956	2.9210	2.9464	2.9718	2.9972	3.0226
0.120	3.0480	3.0734	3.0988	3.1242	3.1496	3.1750	3.2004	3.2258	3.2512	3.2766
0.130	3.3020	3.3274	3.3528	3.3782	3.4036	3.4290	3.4544	3.4798	3.5052	3.5306
0.140	3.5560	3.5814	3.6068	3.6322	3.6576	3.6830	3.7084	3.7338	3.7592	3.7846
0.150	3.8100	3.8354	3.8608	3.8862	3.9116	3.9370	3.9624	3.9878	4.0132	4.0386
0.160	4.0640	4.0894	4.1148	4.1402	4.1656	4.1910	4.2164	4.2418	4.2672	4.2926
0.170	4.3180	4.3434	4.3688	4.3942	4.4196	4.4450	4.4704	4.4958	4.5212	4.5466
0.180	4.5720	4.5974	4.6228	4.6482	4.6736	4.6990	4.7244	4.7498	4.7752	4.8006
0.190	4.8260	4.8514	4.8768	4.9022	4.9276	4.9530	4.9784	5.0038	5.0292	5.0546
0.200	5.0800	5.1054	5.1308	5.1562	5.1816	5.2070	5.2324	5.2578	5.2832	5.3086
0.210	5.3340	5.3594	5.3848	5.4102	5.4356	5.4610	5.4864	5.5118	5.5372	5.5626
0.220	5.5880	5.6134	5.6388	5.6642	5.6896	5.7150	5.7404	5.7658	5.7912	5.8166
0.230	5.8420	5.8674	5.8928	5.9182	5.9436	5.9690	5.9944	6.0198	6.0452	6.0706
0.240	6.0960	6.1214	6.1468	6.1722	6.1976	6.2230	6.2484	6.2738	6.2992	6.3246
0.250	6.3500	6.3754	6.4008	6.4262	6.4516	6.4770	6.5024	6.5278	6.5532	6.5786
0.260	6.6040	6.6294	6.6548	6.6802	6.7056	6.7310	6.7564	6.7818	6.8072	6.8326
0.270	6.8580	6.8834	6.9088	6.9342	6.9596	6.9850	7.0104	7.0358	7.0612	7.0866
0.280	7.1120	7.1374	7.1628	7.1882	7.2136	7.2390	7.2644	7.2898	7.3152	7.3406
0.290	7.3660	7.3914	7.4168	7.4422	7.4676	7.4930	7.5184	7.5438	7.5692	7.5946
0.300	7.6200	7.6454	7.6708	7.6962	7.7216	7.7470	7.7724	7.7978	7.8232	7.8486
0.310	7.8740	7.8994	7.9248	7.9502	7.9756	8.0010	8.0264	8.0518	8.0772	8.1026
0.320	8.1280	8.1534	8.1788	8.2042	8.2296	8.2550	8.2804	8.3058	8.3312	8.3566
0.330	8.3820	8.4074	8.4328	8.4582	8.4836	8.5090	8.5344	8.5598	8.5852	8.6106
0.340	8.6360	8.6614	8.6868	8.7122	8.7376	8.7630	8.7884	8.8138	8.8392	8.8646
0.350	8.8900	8.9154	8.9408	8.9662	8.9916	9.0170	9.0424	9.0678	9.0932	9.1186
0.360	9.1440	9.1694	9.1948	9.2202	9.2456	9.2710	9.2964	9.3218	9.3472	9.3726
0.370	9.3980	9.4234	9.4488	9.4742	9.4996	9.5250	9.5504	9.5758	9.6012	9.6266
0.380	9.6520	9.6774	9.7028	9.7282	9.7536	9.7790	9.8044	9.8298	9.8552	9.8806
0.390	9.9060	9.9314	9.9568	9.9822	10.0076	10.0330	10.0584	10.0838	10.1092	10.1346
0.400	10.1600	10.1854	10.2108	10.2362	10.2616	10.2870	10.3124	10.3378	10.3632	10.3886
0.410	10.4140	10.4394	10.4648	10.4902	10.5156	10.5410	10.5664	10.5918	10.6172	10.6426
0.420	10.6680	10.6934	10.7188	10.7442	10.7696	10.7950	10.8204	10.8458	10.8712	10.8966
0.430	10.9220	10.9474	10.9728	10.9982	11.0236	11.0490	11.0744	11.0998	11.1252	11.1506
0.440	11.1760	11.2014	11.2268	11.2522	11.2776	11.3030	11.3284	11.3538	11.3792	11.4046
0.450	11.4300	11.4554	11.4808	11.5062	11.5316	11.5570	11.5824	11.6078	11.6332	11.6586
0.460	11.6840	11.7094	11.7348	11.7602	11.7856	11.8110	11.8364	11.8618	11.8872	11.9126
0.470	11.9380	11.9634	11.9888	12.0142	12.0396	12.0650	12.0904	12.1158	12.1412	12.1666
0.480	12.1920	12.2174	12.2428	12.2682	12.2936	12.3190	12.3444	12.3698	12.3952	12.4206
0.490	12.4460	12.4714	12.4968	12.5222	12.5476	12.5730	12.5984	12.6238	12.6492	12.6746
0.500	12.7000	12.7254	12.7508	12.7762	12.8016	12.8270	12.8524	12.8778	12.9032	12.9286

Copyright 2004, Industrial Press, Inc., New York, NY

Table 11. ***(Continued)*** **Decimals of an Inch to Millimeters Conversion**

→ Inches ↓	0.000	0.001	0.002	0.003	0.004	0.005	0.006	0.007	0.008	0.009
	Millimeters									
0.510	12.9540	12.9794	13.0048	13.0302	13.0556	13.0810	13.1064	13.1318	13.1572	13.1826
0.520	13.2080	13.2334	13.2588	13.2842	13.3096	13.3350	13.3604	13.3858	13.4112	13.4366
0.530	13.4620	13.4874	13.5128	13.5382	13.5636	13.5890	13.6144	13.6398	13.6652	13.6906
0.540	13.7160	13.7414	13.7668	13.7922	13.8176	13.8430	13.8684	13.8938	13.9192	13.9446
0.550	13.9700	13.9954	14.0208	14.0462	14.0716	14.0970	14.1224	14.1478	14.1732	14.1986
0.560	14.2240	14.2494	14.2748	14.3002	14.3256	14.3510	14.3764	14.4018	14.4272	14.4526
0.570	14.4780	14.5034	14.5288	14.5542	14.5796	14.6050	14.6304	14.6558	14.6812	14.7066
0.580	14.7320	14.7574	14.7828	14.8082	14.8336	14.8590	14.8844	14.9098	14.9352	14.9606
0.590	14.9860	15.0114	15.0368	15.0622	15.0876	15.1130	15.1384	15.1638	15.1892	15.2146
0.600	15.2400	15.2654	15.2908	15.3162	15.3416	15.3670	15.3924	15.4178	15.4432	15.4686
0.610	15.4940	15.5194	15.5448	15.5702	15.5956	15.6210	15.6464	15.6718	15.6972	15.7226
0.620	15.7480	15.7734	15.7988	15.8242	15.8496	15.8750	15.9004	15.9258	15.9512	15.9766
0.630	16.0020	16.0274	16.0528	16.0782	16.1036	16.1290	16.1544	16.1798	16.2052	16.2306
0.640	16.2560	16.2814	16.3068	16.3322	16.3576	16.3830	16.4084	16.4338	16.4592	16.4846
0.650	16.5100	16.5354	16.5608	16.5862	16.6116	16.6370	16.6624	16.6878	16.7132	16.7386
0.660	16.7640	16.7894	16.8148	16.8402	16.8656	16.8910	16.9164	16.9418	16.9672	16.9926
0.670	17.0180	17.0434	17.0688	17.0942	17.1196	17.1450	17.1704	17.1958	17.2212	17.2466
0.680	17.2720	17.2974	17.3228	17.3482	17.3736	17.3990	17.4244	17.4498	17.4752	17.5006
0.690	17.5260	17.5514	17.5768	17.6022	17.6276	17.6530	17.6784	17.7038	17.7292	17.7546
0.700	17.7800	17.8054	17.8308	17.8562	17.8816	17.9070	17.9324	17.9578	17.9832	18.0086
0.710	18.0340	18.0594	18.0848	18.1102	18.1356	18.1610	18.1864	18.2118	18.2372	18.2626
0.720	18.2880	18.3134	18.3388	18.3642	18.3896	18.4150	18.4404	18.4658	18.4912	18.5166
0.730	18.5420	18.5674	18.5928	18.6182	18.6436	18.6690	18.6944	18.7198	18.7452	18.7706
0.740	18.7960	18.8214	18.8468	18.8722	18.8976	18.9230	18.9484	18.9738	18.9992	19.0246
0.750	19.0500	19.0754	19.1008	19.1262	19.1516	19.1770	19.2024	19.2278	19.2532	19.2786
0.760	19.3040	19.3294	19.3548	19.3802	19.4056	19.4310	19.4564	19.4818	19.5072	19.5326
0.770	19.5580	19.5834	19.6088	19.6342	19.6596	19.6850	19.7104	19.7358	19.7612	19.7866
0.780	19.8120	19.8374	19.8628	19.8882	19.9136	19.9390	19.9644	19.9898	20.0152	20.0406
0.790	20.0660	20.0914	20.1168	20.1422	20.1676	20.1930	20.2184	20.2438	20.2692	20.2946
0.800	20.3200	20.3454	20.3708	20.3962	20.4216	20.4470	20.4724	20.4978	20.5232	20.5486
0.810	20.5740	20.5994	20.6248	20.6502	20.6756	20.7010	20.7264	20.7518	20.7772	20.8026
0.820	20.8280	20.8534	20.8788	20.9042	20.9296	20.9550	20.9804	21.0058	21.0312	21.0566
0.830	21.0820	21.1074	21.1328	21.1582	21.1836	21.2090	21.2344	21.2598	21.2852	21.3106
0.840	21.3360	21.3614	21.3868	21.4122	21.4376	21.4630	21.4884	21.5138	21.5392	21.5646
0.850	21.5900	21.6154	21.6408	21.6662	21.6916	21.7170	21.7424	21.7678	21.7932	21.8186
0.860	21.8440	21.8694	21.8948	21.9202	21.9456	21.9710	21.9964	22.0218	22.0472	22.0726
0.870	22.0980	22.1234	22.1488	22.1742	22.1996	22.2250	22.2504	22.2758	22.3012	22.3266
0.880	22.3520	22.3774	22.4028	22.4282	22.4536	22.4790	22.5044	22.5298	22.5552	22.5806
0.890	22.6060	22.6314	22.6568	22.6822	22.7076	22.7330	22.7584	22.7838	22.8092	22.8346
0.900	22.8600	22.8854	22.9108	22.9362	22.9616	22.9870	23.0124	23.0378	23.0632	23.0886
0.910	23.1140	23.1394	23.1648	23.1902	23.2156	23.2410	23.2664	23.2918	23.3172	23.3426
0.920	23.3680	23.3934	23.4188	23.4442	23.4696	23.4950	23.5204	23.5458	23.5712	23.5966
0.930	23.6220	23.6474	23.6728	23.6982	23.7236	23.7490	23.7744	23.7998	23.8252	23.8506
0.940	23.8760	23.9014	23.9268	23.9522	23.9776	24.0030	24.0284	24.0538	24.0792	24.1046
0.950	24.1300	24.1554	24.1808	24.2062	24.2316	24.2570	24.2824	24.3078	24.3332	24.3586
0.960	24.3840	24.4094	24.4348	24.4602	24.4856	24.5110	24.5364	24.5618	24.5872	24.6126
0.970	24.6380	24.6634	24.6888	24.7142	24.7396	24.7650	24.7904	24.8158	24.8412	24.8666
0.980	24.8920	24.9174	24.9428	24.9682	24.9936	25.0190	25.0444	25.0698	25.0952	25.1206
0.990	25.1460	25.1714	25.1968	25.2222	25.2476	25.2730	25.2984	25.3238	25.3492	25.3746
1.000	25.4000	…	…	…	…	…	…	…	…	…

Based on 1 inch = 25.4 millimeters, exactly. All values in this table are exact. Use Table 8a to obtain whole inch and other decimal equivalents to add to decimal equivalents above. *Example:* Convert 10.9983 in. to mm. *Solution:* 10.9983 in. = 254.0 + 25.3492 + 0.00762 = 279.35682 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. Millimeters to Inches Conversion

→ Millimeters ↓	0	1	2	3	4	5	6	7	8	9
	Inches									
0	…	0.03937	0.07874	0.11811	0.15748	0.19685	0.23622	0.27559	0.31496	0.35433
10	0.39370	0.43307	0.47244	0.51181	0.55118	0.59055	0.62992	0.66929	0.70866	0.74803
20	0.78740	0.82677	0.86614	0.90551	0.94488	0.98425	1.02362	1.06299	1.10236	1.14173
30	1.18110	1.22047	1.25984	1.29921	1.33858	1.37795	1.41732	1.45669	1.49606	1.53543
40	1.57480	1.61417	1.65354	1.69291	1.73228	1.77165	1.81102	1.85039	1.88976	1.92913
50	1.96850	2.00787	2.04724	2.08661	2.12598	2.16535	2.20472	2.24409	2.28346	2.32283
60	2.36220	2.40157	2.44094	2.48031	2.51969	2.55906	2.59843	2.63780	2.67717	2.71654
70	2.75591	2.79528	2.83465	2.87402	2.91339	2.95276	2.99213	3.03150	3.07087	3.11024
80	3.14961	3.18898	3.22835	3.26772	3.30709	3.34646	3.38583	3.42520	3.46457	3.50394
90	3.54331	3.58268	3.62205	3.66142	3.70079	3.74016	3.77953	3.81890	3.85827	3.89764
100	3.93701	3.97638	4.01575	4.05512	4.09449	4.13386	4.17323	4.21260	4.25197	4.29134
110	4.33071	4.37008	4.40945	4.44882	4.48819	4.52756	4.56693	4.60630	4.64567	4.68504
120	4.72441	4.76378	4.80315	4.84252	4.88189	4.92126	4.96063	5.00000	5.03937	5.07874
130	5.11811	5.15748	5.19685	5.23622	5.27559	5.31496	5.35433	5.39370	5.43307	5.47244
140	5.51181	5.55118	5.59055	5.62992	5.66929	5.70866	5.74803	5.78740	5.82677	5.86614
150	5.90551	5.94488	5.98425	6.02362	6.06299	6.10236	6.14173	6.18110	6.22047	6.25984
160	6.29921	6.33858	6.37795	6.41732	6.45669	6.49606	6.53543	6.57480	6.61417	6.65354
170	6.69291	6.73228	6.77165	6.81102	6.85039	6.88976	6.92913	6.96850	7.00787	7.04724
180	7.08661	7.12598	7.16535	7.20472	7.24409	7.28346	7.32283	7.36220	7.40157	7.44094
190	7.48031	7.51969	7.55906	7.59843	7.63780	7.67717	7.71654	7.75591	7.79528	7.83465
200	7.87402	7.91339	7.95276	7.99213	8.03150	8.07087	8.11024	8.14961	8.18898	8.22835
210	8.26772	8.30709	8.34646	8.38583	8.42520	8.46457	8.50394	8.54331	8.58268	8.62205
220	8.66142	8.70079	8.74016	8.77953	8.81890	8.85827	8.89764	8.93701	8.97638	9.01575
230	9.05512	9.09449	9.13386	9.17323	9.21260	9.25197	9.29134	9.33071	9.37008	9.40945
240	9.44882	9.48819	9.52756	9.56693	9.60630	9.64567	9.68504	9.72441	9.76378	9.80315
250	9.84252	9.88189	9.92126	9.96063	10.0000	10.0394	10.0787	10.1181	10.1575	10.1969
260	10.2362	10.2756	10.3150	10.3543	10.3937	10.4331	10.4724	10.5118	10.5512	10.5906
270	10.6299	10.6693	10.7087	10.7480	10.7874	10.8268	10.8661	10.9055	10.9449	10.9843
280	11.0236	11.0630	11.1024	11.1417	11.1811	11.2205	11.2598	11.2992	11.3386	11.3780
290	11.4173	11.4567	11.4961	11.5354	11.5748	11.6142	11.6535	11.6929	11.7323	11.7717
300	11.8110	11.8504	11.8898	11.9291	11.9685	12.0079	12.0472	12.0866	12.1260	12.1654
310	12.2047	12.2441	12.2835	12.3228	12.3622	12.4016	12.4409	12.4803	12.5197	12.5591
320	12.5984	12.6378	12.6772	12.7165	12.7559	12.7953	12.8346	12.8740	12.9134	12.9528
330	12.9921	13.0315	13.0709	13.1102	13.1496	13.1890	13.2283	13.2677	13.3071	13.3465
340	13.3858	13.4252	13.4646	13.5039	13.5433	13.5827	13.6220	13.6614	13.7008	13.7402
350	13.7795	13.8189	13.8583	13.8976	13.9370	13.9764	14.0157	14.0551	14.0945	14.1339
360	14.1732	14.2126	14.2520	14.2913	14.3307	14.3701	14.4094	14.4488	14.4882	14.5276
370	14.5669	14.6063	14.6457	14.6850	14.7244	14.7638	14.8031	14.8425	14.8819	14.9213
380	14.9606	15.0000	15.0394	15.0787	15.1181	15.1575	15.1969	15.2362	15.2756	15.3150
390	15.3543	15.3937	15.4331	15.4724	15.5118	15.5512	15.5906	15.6299	15.6693	15.7087
400	15.7480	15.7874	15.8268	15.8661	15.9055	15.9449	15.9843	16.0236	16.0630	16.1024
410	16.1417	16.1811	16.2205	16.2598	16.2992	16.3386	16.3780	16.4173	16.4567	16.4961
420	16.5354	16.5748	16.6142	16.6535	16.6929	16.7323	16.7717	16.8110	16.8504	16.8898
430	16.9291	16.9685	17.0079	17.0472	17.0866	17.1260	17.1654	17.2047	17.2441	17.2835
440	17.3228	17.3622	17.4016	17.4409	17.4803	17.5197	17.5591	17.5984	17.6378	17.6772
450	17.7165	17.7559	17.7953	17.8346	17.8740	17.9134	17.9528	17.9921	18.0315	18.0709
460	18.1102	18.1496	18.1890	18.2283	18.2677	18.3071	18.3465	18.3858	18.4252	18.4646
470	18.5039	18.5433	18.5827	18.6220	18.6614	18.7008	18.7402	18.7795	18.8189	18.8583
480	18.8976	18.9370	18.9764	19.0157	19.0551	19.0945	19.1339	19.1732	19.2126	19.2520
490	19.2913	19.3307	19.3701	19.4094	19.4488	19.4882	19.5276	19.5669	19.6063	19.6457

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12. ***(Continued)*** **Millimeters to Inches Conversion**

→ Millimeters ↓	0	1	2	3	4	5	6	7	8	9
	Inches									
500	19.6850	19.7244	19.7638	19.8031	19.8425	19.8819	19.9213	19.9606	20.0000	20.0394
510	20.0787	20.1181	20.1575	20.1969	20.2362	20.2756	20.3150	20.3543	20.3937	20.4331
520	20.4724	20.5118	20.5512	20.5906	20.6299	20.6693	20.7087	20.7480	20.7874	20.8268
530	20.8661	20.9055	20.9449	20.9843	21.0236	21.0630	21.1024	21.1417	21.1811	21.2205
540	21.2598	21.2992	21.3386	21.3780	21.4173	21.4567	21.4961	21.5354	21.5748	21.6142
550	21.6535	21.6929	21.7323	21.7717	21.8110	21.8504	21.8898	21.9291	21.9685	22.0079
560	22.0472	22.0866	22.1260	22.1654	22.2047	22.2441	22.2835	22.3228	22.3622	22.4016
570	22.4409	22.4803	22.5197	22.5591	22.5984	22.6378	22.6772	22.7165	22.7559	22.7953
580	22.8346	22.8740	22.9134	22.9528	22.9921	23.0315	23.0709	23.1102	23.1496	23.1890
590	23.2283	23.2677	23.3071	23.3465	23.3858	23.4252	23.4646	23.5039	23.5433	23.5827
600	23.6220	23.6614	23.7008	23.7402	23.7795	23.8189	23.8583	23.8976	23.9370	23.9764
610	24.0157	24.0551	24.0945	24.1339	24.1732	24.2126	24.2520	24.2913	24.3307	24.3701
620	24.4094	24.4488	24.4882	24.5276	24.5669	24.6063	24.6457	24.6850	24.7244	24.7638
630	24.8031	24.8425	24.8819	24.9213	24.9606	25.0000	25.0394	25.0787	25.1181	25.1575
640	25.1969	25.2362	25.2756	25.3150	25.3543	25.3937	25.4331	25.4724	25.5118	25.5512
650	25.5906	25.6299	25.6693	25.7087	25.7480	25.7874	25.8268	25.8661	25.9055	25.9449
660	25.9843	26.0236	26.0630	26.1024	26.1417	26.1811	26.2205	26.2598	26.2992	26.3386
670	26.3780	26.4173	26.4567	26.4961	26.5354	26.5748	26.6142	26.6535	26.6929	26.7323
680	26.7717	26.8110	26.8504	26.8898	26.9291	26.9685	27.0079	27.0472	27.0866	27.1260
690	27.1654	27.2047	27.2441	27.2835	27.3228	27.3622	27.4016	27.4409	27.4803	27.5197
700	27.5591	27.5984	27.6378	27.6772	27.7165	27.7559	27.7953	27.8346	27.8740	27.9134
710	27.9528	27.9921	28.0315	28.0709	28.1102	28.1496	28.1890	28.2283	28.2677	28.3071
720	28.3465	28.3858	28.4252	28.4646	28.5039	28.5433	28.5827	28.6220	28.6614	28.7008
730	28.7402	28.7795	28.8189	28.8583	28.8976	28.9370	28.9764	29.0157	29.0551	29.0945
740	29.1339	29.1732	29.2126	29.2520	29.2913	29.3307	29.3701	29.4094	29.4488	29.4882
750	29.5276	29.5669	29.6063	29.6457	29.6850	29.7244	29.7638	29.8031	29.8425	29.8819
760	29.9213	29.9606	30.0000	30.0394	30.0787	30.1181	30.1575	30.1969	30.2362	30.2756
770	30.3150	30.3543	30.3937	30.4331	30.4724	30.5118	30.5512	30.5906	30.6299	30.6693
780	30.7087	30.7480	30.7874	30.8268	30.8661	30.9055	30.949	30.9843	31.0236	31.0630
790	31.1024	31.1417	31.1811	31.2205	31.2598	31.2992	31.3386	31.3780	31.4173	31.4567
800	31.4961	31.5354	31.5748	31.6142	31.6535	31.6929	31.7323	31.7717	31.8110	31.8504
810	31.8898	31.9291	31.9685	32.0079	32.0472	32.0866	32.1260	32.1654	32.2047	32.2441
820	32.2835	32.3228	32.3622	32.4016	32.4409	32.4803	32.5197	32.5591	32.5984	32.6378
830	32.6772	32.7165	32.7559	32.7953	32.8346	32.8740	32.9134	32.9528	32.9921	33.0315
840	33.0709	33.1102	33.1496	33.1890	33.2283	33.2677	33.3071	33.3465	33.3858	33.4252
850	33.4646	33.5039	33.5433	33.5827	33.6220	33.6614	33.7008	33.7402	33.7795	33.8189
860	33.8583	33.8976	33.9370	33.9764	34.0157	34.0551	34.0945	34.1339	34.1732	34.2126
870	34.2520	34.2913	34.3307	34.3701	34.4094	34.4488	34.4882	34.5276	34.5669	34.6063
880	34.6457	34.6850	34.7244	34.7638	34.8031	34.8425	34.8819	34.9213	34.9606	35.0000
890	35.0394	35.0787	35.1181	35.1575	35.1969	35.2362	35.2756	35.3150	35.3543	35.3937
900	35.4331	35.4724	35.5118	35.5512	35.5906	35.6299	35.6693	35.7087	35.7480	35.7874
910	35.8268	35.8661	35.9055	35.9449	35.9843	36.0236	36.0630	36.1024	36.1417	36.1811
920	36.2205	36.2598	36.2992	36.3386	36.3780	36.4173	36.4567	36.4961	36.5354	36.5748
930	36.6142	36.6535	36.6929	36.7323	36.7717	36.8110	36.8504	36.8898	36.9291	36.9685
940	37.0079	37.0472	37.0866	37.1260	37.1654	37.2047	37.2441	37.2835	37.3228	37.3622
950	37.4016	37.409	37.4803	37.5197	37.5591	37.5984	37.6378	37.6772	37.7165	37.7559
960	37.7953	37.8346	37.8740	37.9134	37.9528	37.9921	38.0315	38.0709	38.1102	38.1496
970	38.1800	38.2283	38.2677	38.3071	38.3465	38.3858	38.4252	38.4646	38.5039	38.5433
980	38.5827	38.6220	38.6614	38.7008	38.7402	38.7795	38.8189	38.8583	38.8976	38.9370
990	38.9764	39.0157	39.0551	39.0945	39.1339	39.1732	39.2126	39.2520	39.2913	39.3307
1000	39.3701	…	…	…	…	…	…	…	…	…

Based on 1 inch = 25.4 millimeters, exactly.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13a. Microinches to Micrometers (microns) Conversion

→ Microinches ↓	0	1	2	3	4	5	6	7	8	9
	Micrometers (microns)									
0	0	0.0254	0.0508	0.0762	0.1016	0.127	0.1524	0.1778	0.2032	0.2286
10	0.254	0.2794	0.3048	0.3302	0.3556	0.381	0.4064	0.4318	0.4572	0.4826
20	0.508	0.5334	0.5588	0.5842	0.6096	0.635	0.6604	0.6858	0.7112	0.7366
30	0.762	0.7874	0.8128	0.8382	0.8636	0.889	0.9144	0.9398	0.9652	0.9906
40	1.016	1.0414	1.0668	1.0922	1.1176	1.143	1.1684	1.1938	1.2192	1.2446
50	1.27	1.2954	1.3208	1.3462	1.3716	1.397	1.4224	1.4478	1.4732	1.4986
60	1.524	1.5494	1.5748	1.6002	1.6256	1.651	1.6764	1.7018	1.7272	1.7526
70	1.778	1.8034	1.8288	1.8542	1.8796	1.905	1.9304	1.9558	1.9812	2.0066
80	2.032	2.0574	2.0828	2.1082	2.1336	2.159	2.1844	2.2098	2.2352	2.2606
90	2.286	2.3114	2.3368	2.3622	2.3876	2.413	2.4384	2.4638	2.4892	2.5146
100	2.54	2.5654	2.5908	2.6162	2.6416	2.667	2.6924	2.7178	2.7432	2.7686
110	2.794	2.8194	2.8448	2.8702	2.8956	2.921	2.9464	2.9718	2.9972	3.0226
120	3.048	3.0734	3.0988	3.1242	3.1496	3.175	3.2004	3.2258	3.2512	3.2766
130	3.302	3.3274	3.3528	3.3782	3.4036	3.429	3.4544	3.4798	3.5052	3.5306
140	3.556	3.5814	3.6068	3.6322	3.6576	3.683	3.7084	3.7338	3.7592	3.7846
150	3.81	3.8354	3.8608	3.8862	3.9116	3.937	3.9624	3.9878	4.0132	4.0386
160	4.064	4.0894	4.1148	4.1402	4.1656	4.191	4.2164	4.2418	4.2672	4.2926
170	4.318	4.3434	4.3688	4.3942	4.4196	4.445	4.4704	4.4958	4.5212	4.5466
180	4.572	4.5974	4.6228	4.6482	4.6736	4.699	4.7244	4.7498	4.7752	4.8006
190	4.826	4.8514	4.8768	4.9022	4.9276	4.953	4.9784	5.0038	5.0292	5.0546
200	5.08	5.1054	5.1308	5.1562	5.1816	5.207	5.2324	5.2578	5.2832	5.3086
210	5.334	5.3594	5.3848	5.4102	5.4356	5.461	5.4864	5.5118	5.5372	5.5626
220	5.588	5.6134	5.6388	5.6642	5.6896	5.715	5.7404	5.7658	5.7912	5.8166
230	5.842	5.8674	5.8928	5.9182	5.9436	5.969	5.9944	6.0198	6.0452	6.0706
240	6.096	6.1214	6.1468	6.1722	6.1976	6.223	6.2484	6.2738	6.2992	6.3246
250	6.35	6.3754	6.4008	6.4262	6.4516	6.477	6.5024	6.5278	6.5532	6.5786
260	6.604	6.6294	6.6548	6.6802	6.7056	6.731	6.7564	6.7818	6.8072	6.8326
270	6.858	6.8834	6.9088	6.9342	6.9596	6.985	7.0104	7.0358	7.0612	7.0866
280	7.112	7.1374	7.1628	7.1882	7.2136	7.239	7.2644	7.2898	7.3152	7.3406
290	7.366	7.3914	7.4168	7.4422	7.4676	7.493	7.5184	7.5438	7.5692	7.5946
300	7.62	7.6454	7.6708	7.6962	7.7216	7.747	7.7724	7.7978	7.8232	7.8486
310	7.874	7.8994	7.9248	7.9502	7.9756	8.001	8.0264	8.0518	8.0772	8.1026
320	8.128	8.1534	8.1788	8.2042	8.2296	8.255	8.2804	8.3058	8.3312	8.3566
330	8.382	8.4074	8.4328	8.4582	8.4836	8.509	8.5344	8.5598	8.5852	8.6106
340	8.636	8.6614	8.6868	8.7122	8.7376	8.763	8.7884	8.8138	8.8392	8.8646
350	8.89	8.9154	8.9408	8.9662	8.9916	9.017	9.0424	9.0678	9.0932	9.1186
360	9.144	9.1694	9.1948	9.2202	9.2456	9.271	9.2964	9.3218	9.3472	9.3726
370	9.398	9.4234	9.4488	9.4742	9.4996	9.525	9.5504	9.5758	9.6012	9.6266
380	9.652	9.6774	9.7028	9.7282	9.7536	9.779	9.8044	9.8298	9.8552	9.8806
390	9.906	9.9314	9.9568	9.9822	10.0076	10.033	10.0584	10.0838	10.1092	10.1346
400	10.16	10.1854	10.2108	10.2362	10.2616	10.287	10.3124	10.3378	10.3632	10.3886
410	10.414	10.4394	10.4648	10.4902	10.5156	10.541	10.5664	10.5918	10.6172	10.6426
420	10.668	10.6934	10.7188	10.7442	10.7696	10.795	10.8204	10.8458	10.8712	10.8966
430	10.922	10.9474	10.9728	10.9982	11.0236	11.049	11.0744	11.0998	11.1252	11.1506
440	11.176	11.2014	11.2268	11.2522	11.2776	11.303	11.3284	11.3538	11.3792	11.4046
450	11.43	11.4554	11.4808	11.5062	11.5316	11.557	11.5824	11.6078	11.6332	11.6586
460	11.684	11.7094	11.7348	11.7602	11.7856	11.811	11.8364	11.8618	11.8872	11.9126
470	11.938	11.9634	11.9888	12.0142	12.0396	12.065	12.0904	12.1158	12.1412	12.1666
480	12.192	12.2174	12.2428	12.2682	12.2936	12.319	12.3444	12.3698	12.3952	12.4206
490	12.446	12.4714	12.4968	12.5222	12.5476	12.573	12.5984	12.6238	12.6492	12.6746
500	12.7	12.7254	12.7508	12.7762	12.8016	12.827	12.8524	12.8778	12.9032	12.9286

Use the small table below to convert microinches to micrometers for ranges higher than given in the main table above. Appropriate quantities chosen from both tables are simply added to obtain the higher converted value:

µin.	µm	µin.	µm	µin.	µm	µin.	µm	µin.	µm	µin.	µm
600	15.24	800	20.32	1000	25.4	1500	38.1	2100	53.34	2700	68.58
700	17.78	900	22.86	1200	30.48	1800	45.72	2400	60.96	3000	76.2

Both tables based on 1 microinch = 0.0254 micrometers, exactly. All values in both parts of this table are exact; figures to the right of the last place figures are all zeros.

Example: Convert 1375 µin. to µm:

From lower portion of Table 13a:	1200 µin.	=	30.48 µm
From upper portion of Table 13a:	175 µin.	=	4.445 µm
	1375 µin.	=	34.925 µm

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13b. Micrometers (microns) to Microinches Conversion

→ Microns ↓	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09
	Microinches									
0.00	0.0000	0.3937	0.7874	1.1811	1.5748	1.9685	2.3622	2.7559	3.1496	3.5433
0.10	3.9370	4.3307	4.7244	5.1181	5.5118	5.9055	6.2992	6.6929	7.0866	7.4803
0.20	7.8740	8.2677	8.6614	9.0551	9.4488	9.8425	10.2362	10.6299	11.0236	11.4173
0.30	11.8110	12.2047	12.5984	12.9921	13.3858	13.7795	14.1732	14.5669	14.9606	15.3543
0.40	15.7480	16.1417	16.5354	16.9291	17.3228	17.7165	18.1102	18.5039	18.8976	19.2913
0.50	19.6850	20.0787	20.4724	20.8661	21.2598	21.6535	22.0472	22.4409	22.8346	23.2283
0.60	23.6220	24.0157	24.4094	24.8031	25.1969	25.5906	25.9843	26.3780	26.7717	27.1654
0.70	27.5591	27.9528	28.3465	28.7402	29.1339	29.5276	29.9213	30.3150	30.7087	31.1024
0.80	31.4961	31.8898	32.2835	32.6772	33.0709	33.4646	33.8583	34.2520	34.6457	35.0394
0.90	35.4331	35.8268	36.2205	36.6142	37.0079	37.4016	37.7953	38.1890	38.5827	38.9764
1.00	39.3701	39.7638	40.1575	40.5512	40.9449	41.3386	41.7323	42.1260	42.5197	42.9134
1.10	43.3071	43.7008	44.0945	44.4882	44.8819	45.2756	45.6693	46.0630	46.4567	46.8504
1.20	47.2441	47.6378	48.0315	48.4252	48.8189	49.2126	49.6063	50.0000	50.3937	50.7874
1.30	51.1811	51.5748	51.9685	52.3622	52.7559	53.1496	53.5433	53.9370	54.3307	54.7244
1.40	55.1181	55.5118	55.9055	56.2992	56.6929	57.0866	57.4803	57.8740	58.2677	58.6614
1.50	59.0551	59.4488	59.8425	60.2362	60.6299	61.0236	61.4173	61.8110	62.2047	62.5984
1.60	62.9921	63.3858	63.7795	64.1732	64.5669	64.9606	65.3543	65.7480	66.1417	66.5354
1.70	66.9291	67.3228	67.7165	68.1102	68.5039	68.8976	69.2913	69.6850	70.0787	70.4724
1.80	70.8661	71.2598	71.6535	72.0472	72.4409	72.8346	73.2283	73.6220	74.0157	74.4094
1.90	74.8031	75.1969	75.5906	75.9843	76.3780	76.7717	77.1654	77.5591	77.9528	78.3465
2.00	78.7402	79.1339	79.5276	79.9213	80.3150	80.7087	81.1024	81.4961	81.8898	82.2835
2.10	82.6772	83.0709	83.4646	83.8583	84.2520	84.6457	85.0394	85.4331	85.8268	86.2205
2.20	86.6142	87.0079	87.4016	87.7953	88.1890	88.5827	88.9764	89.3701	89.7638	90.1575
2.30	90.5512	90.9449	91.3386	91.7323	92.1260	92.5197	92.9134	93.3071	93.7008	94.0945
2.40	94.4882	94.8819	95.2756	95.6693	96.0630	96.4567	96.8504	97.2441	97.6378	98.0315
2.50	98.4252	98.8189	99.2126	99.6063	100.0000	100.3937	100.7874	101.1811	101.5748	101.9685
2.60	102.3622	102.7559	103.1496	103.5433	103.9370	104.3307	104.7244	105.1181	105.5118	105.9055
2.70	106.2992	106.6929	107.0866	107.4803	107.8740	108.2677	108.6614	109.0551	109.4488	109.8425
2.80	110.2362	110.6299	111.0236	111.4173	111.8110	112.2047	112.5984	112.9921	113.3858	113.7795
2.90	114.1732	114.5669	114.9606	115.3543	115.7480	116.1417	116.5354	116.9291	117.3228	117.7165
3.00	118.1102	118.5039	118.8976	119.2913	119.6850	120.0787	120.4724	120.8661	121.2598	121.6535
3.10	122.0472	122.4409	122.8346	123.2283	123.6220	124.0157	124.4094	124.8031	125.1969	125.5906
3.20	125.9843	126.3780	126.7717	127.1654	127.5591	127.9528	128.3465	128.7402	129.1339	129.5276
3.30	129.9213	130.3150	130.7087	131.1024	131.4961	131.8898	132.2835	132.6772	133.0709	133.4646
3.40	133.8583	134.2520	134.6457	135.0394	135.4331	135.8268	136.2205	136.6142	137.0079	137.4016
3.50	137.7953	138.1890	138.5827	138.9764	139.3701	139.7638	140.1575	140.5512	140.9449	141.3386
3.60	141.7323	142.1260	142.5197	142.9134	143.3071	143.7008	144.0945	144.4882	144.8819	145.2756
3.70	145.6693	146.0630	146.4567	146.8504	147.2441	147.6378	148.0315	148.4252	148.8189	149.2126
3.80	149.6063	150.0000	150.3937	150.7874	151.1811	151.5748	151.9685	152.3622	152.7559	153.1496
3.90	153.5433	153.9370	154.3307	154.7244	155.1181	155.5118	155.9055	156.2992	156.6929	157.0866
4.00	157.4803	157.8740	158.2677	158.6614	159.0551	159.4488	159.8425	160.2362	160.6299	161.0236
4.10	161.4173	161.8110	162.2047	162.5984	162.9921	163.3858	163.7795	164.1732	164.5669	164.9606
4.20	165.3543	165.7480	166.1417	166.5354	166.9291	167.3228	167.7165	168.1102	168.5039	168.8976
4.30	169.2913	169.6850	170.0787	170.4724	170.8661	171.2598	171.6535	172.0472	172.4409	172.8346
4.40	173.2283	173.6220	174.0157	174.4094	174.8031	175.1969	175.5906	175.9843	176.3780	176.7717
4.50	177.1654	177.5591	177.9528	178.3465	178.7402	179.1339	179.5276	179.9213	180.3150	180.7087
4.60	181.1024	181.4961	181.8898	182.2835	182.6772	183.0709	183.4646	183.8583	184.2520	184.6457
4.70	185.0394	185.4331	185.8268	186.2205	186.6142	187.0079	187.4016	187.7953	188.1890	188.5827
4.80	188.9764	189.3701	189.7638	190.1575	190.5512	190.9449	191.3386	191.7323	192.1260	192.5197
4.90	192.9134	193.3071	193.7008	194.0945	194.4882	194.8819	195.2756	195.6693	196.0630	196.4567
5.00	196.8504	197.2441	197.6378	198.0315	198.4252	198.8189	199.2126	199.6063	200.0000	200.3937

The table given below can be used with the preceding main table to obtain higher converted values, simply by adding appropriate quantities chosen from each table:

μm	μin.	μm	μin.	μm	μin.	μm	μin.	μm	μin.
10	393.7008	20	787.4016	30	1,181.1024	40	1,574.8032	50	1,968.5039
15	590.5512	25	984.2520	35	1,378.9528	45	1,771.6535	55	2,165.3543

Both portions of Table 13b are based on 1 microinch = 0.0254 micrometers, exactly.

Example: Convert 23.55 μm to μin.:

From above table:	20.00 μm	=	787.4016 μin
From main table:	3.55 μm	=	139.7638 μin
	23.55 μm	=	927.1654 μin

Copyright 2004, Industrial Press, Inc., New York, NY

Table 14a. Feet to Meters Conversion

feet	meters	feet	meters	feet	meters	feet	meters	feet	meters
100	30.48	10	3.048	1	0.3048	0.1	0.03048	0.01	0.003048
200	60.96	20	6.096	2	0.6096	0.2	0.06096	0.02	0.006096
300	91.44	30	9.144	3	0.9144	0.3	0.09144	0.03	0.009144
400	121.92	40	12.192	4	1.2192	0.4	0.12192	0.04	0.012192
500	152.4	50	15.24	5	1.524	0.5	0.1524	0.05	0.01524
600	182.88	60	18.288	6	1.8288	0.6	0.18288	0.06	0.018288
700	213.36	70	21.336	7	2.1336	0.7	0.21336	0.07	0.021336
800	243.84	80	24.384	8	2.4384	0.8	0.24384	0.08	0.024384
900	274.32	90	27.432	9	2.7432	0.9	0.27432	0.09	0.027432
1,000	304.8	100	30.48	10	3.048	1.0	0.3048	0.10	0.03048

1 ft = 0.3048 m, exactly

Table 14b. Meters to Feet Conversion

meters	feet	meters	feet	meters	feet	meters	feet	meters	feet
100	328.084	10	32.808	1	3.281	0.1	0.328	0.01	0.033
200	656.168	20	65.617	2	6.562	0.2	0.656	0.02	0.066
300	984.252	30	98.425	3	9.843	0.3	0.984	0.03	0.098
400	1,312.336	40	131.234	4	13.123	0.4	1.312	0.04	0.131
500	1,640.420	50	164.042	5	16.404	0.5	1.640	0.05	0.164
600	1,968.504	60	196.850	6	19.685	0.6	1.969	0.06	0.197
700	2,296.588	70	229.659	7	22.966	0.7	2.297	0.07	0.230
800	2,624.672	80	262.467	8	26.247	0.8	2.625	0.08	0.262
900	2,952.756	90	295.276	9	29.528	0.9	2.953	0.09	0.295
1,000	3,280.840	100	328.084	10	32.808	1.0	3.281	0.10	0.328

1 m = 3.280840 ft

Table 15a. Miles to Kilometers Conversion

miles	km	miles	km	miles	km	miles	km	miles	km
1,000	1,609.34	100	160.93	10	16.09	1	1.61	0.1	0.16
2,000	3,218.69	200	321.87	20	32.19	2	3.22	0.2	0.32
3,000	4,828.03	300	482.80	30	48.28	3	4.83	0.3	0.48
4,000	6,437.38	400	643.74	40	64.37	4	6.44	0.4	0.64
5,000	8,046.72	500	804.67	50	80.47	5	8.05	0.5	0.80
6,000	9,656.06	600	965.61	60	96.56	6	9.66	0.6	0.97
7,000	11,265.41	700	1,126.54	70	112.65	7	11.27	0.7	1.13
8,000	12,874.75	800	1,287.48	80	128.75	8	12.87	0.8	1.29
9,000	14,484.10	900	1,448.41	90	144.84	9	14.48	0.9	1.45
10,000	16,093.44	1,000	1,609.34	100	160.93	10	16.09	1.0	1.61

1 mile = 1.609344 km, exactly

Table 15b. Kilometers to Miles Conversion

km	miles	km	miles	km	miles	km	miles	km	miles
1,000	621.37	100	62.14	10	6.21	1	0.62	0.1	0.06
2,000	1,242.74	200	124.27	20	12.43	2	1.24	0.2	0.12
3,000	1,864.11	300	186.41	30	18.64	3	1.86	0.3	0.19
4,000	2,485.48	400	248.55	40	24.85	4	2.49	0.4	0.25
5,000	3,106.86	500	310.69	50	31.07	5	3.11	0.5	0.31
6,000	3,728.23	600	372.82	60	37.28	6	3.73	0.6	0.37
7,000	4,349.60	700	434.96	70	43.50	7	4.35	0.7	0.43
8,000	4,970.97	800	497.10	80	49.71	8	4.97	0.8	0.50
9,000	5,592.34	900	559.23	90	55.92	9	5.59	0.9	0.56
10,000	6,213.71	1,000	621.37	100	62.14	10	6.21	1.0	0.62

1 km = 0.6213712 mile

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Area

Table 16. Square Measure and Conversion Factors

Metric System

1 square kilometer (km^2) =
100 hectares
1,000,000 square meters
0.3861 square mile
247.1 acres

1 hectare (ha) =
0.01 square kilometer
100 ares
10,000 square meters
2.471 acres
107,639 square feet

1 are (a) =
0.0001 square kilometer
100 square meters
0.0247 acre
1076.4 square feet

1 square meter (m^2) =
0.000001 square kilometer
100 square decimeters
10000 square centimeters
1,000,000 square millimeters
10.764 square feet
1.196 square yards

1 square decimeter (dm^2) =
100 square centimeters

1 square centimeter (cm^2) =
0.0001 square meters
100 square millimeters
0.001076 square foot
0.155 square inch

1 square millimeter (mm^2) =
0.01 square centimeters
1,000,000 square microns
0.00155 square inch

1 square micrometer (micron) (μm^2) =
$\mathbf{1 \times 10^{-12}}$ square meter
0.000001 square millimeters
1×10^{-9} square inch
1549.997 square micro-inch

U.S. System

1 square mile (mi^2) =
640 acres
6400 square chains
2.5899 square kilometers

1 acre =
10 square chains
4840 square yards
43,560 square feet
a square, 208.71 feet on a side
0.4046856 hectare
40.47 ares
4046.856 square meters

1 square chain =
16 square rods
484 square yards
4356 square feet

1 square rod =
30.25 square yards
272.25 square feet
625 square links

1 square yard (yd^2) =
9 square feet
1296 square inches
0.83612736 square meter
8361.2736 square centimeter
836,127.36 square millimeter

1 square foot (ft^2) =
0.111111 square yard
144 square inches
0.09290304 square meter
929.0304 square centimeters
92,903.04 square millimeters

1 square inch (in^2) =
0.0007716 square yard
0.006944 square foot
0.00064516 square meter
6.4516 square centimeters
645.16 square millimeters

1 square mil (mil^2) =
0.000001 square inch
0.00064516 square millimeter

1 square micro-inch (μin^2) =
$\mathbf{1 \times 10^{-12}}$ square inch
0.00064516 square micrometer (micron)

Note: Figures in **Bold** indicate exact conversion values

Measure Used for Diameters and Areas of Electric Wires

1 circular inch =
area of 1-inch diameter circle
$\pi/4$ square inch
0.7854 square inch
5.067 square centimeter
1,000,000 circular mils

1 circular mil =
area of 0.001-inch diameter circle
$\pi/4$ square mill

1 square inch =
1.2732 circular inch
1,273,239 circular mils

Copyright 2004, Industrial Press, Inc., New York, NY

Table 17a. Square Inches to Square Centimeters Conversion

$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$	cm^2
100	645.16	10	64.516	1	6.4516	0.1	0.64516	0.01	0.064516
200	1,290.32	20	129.032	2	12.9032	0.2	1.29032	0.02	0.129032
300	1,935.48	30	193.548	3	19.3548	0.3	1.93548	0.03	0.135489
400	2,580.64	40	258.064	4	25.8064	0.4	2.58064	0.04	0.258064
500	3,225.80	50	322.58	5	32.258	0.5	3.2258	0.05	0.32258
600	30,870.96	60	387.096	6	38.7096	0.6	3.87096	0.06	0.387096
700	4,516.12	70	451.612	7	45.1612	0.7	4.51612	0.07	0.451612
800	5,161.28	80	516.128	8	51.6128	0.8	5.16128	0.08	0.516128
900	5,806.44	90	580.644	9	58.0644	0.9	5.80644	0.09	0.580644
1,000	6,451.60	100	645.16	10	64.516	1.0	6.4516	0.10	0.64516

Based on 1 inch = 2.54 centimeters, exactly, 1 $inch^2 = 6.4516\ cm^2$, exactly.

Table 17b. Square Centimeters to Square Inches Conversion

cm^2	$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$	cm^2	$inch^2$
100	15.500	10	1.550	1	0.155	0.1	0.016	0.01	0.002
200	31.000	20	3.100	2	0.310	0.2	0.031	0.02	0.003
300	46.500	30	4.650	3	0.465	0.3	0.047	0.03	0.005
400	62.000	40	6.200	4	0.620	0.4	0.062	0.04	0.006
500	77.500	50	7.750	5	0.75	0.5	0.078	0.05	0.008
600	93.000	60	9.300	6	0.930	0.6	0.093	0.06	0.009
700	108.500	70	10.850	7	1.085	0.7	0.109	0.07	0.011
800	124.000	80	12.400	8	1.240	0.8	0.124	0.08	0.012
900	139.500	90	13.950	9	1.395	0.9	0.140	0.09	0.014
1,000	155.000	100	15.500	10	1.550	1.0	0.155	0.10	0.016

Based on 1 inch = 2.54 centimeters, exactly, 1 $cm^2 = 0.1550003\ inch^2$.

Table 18a. Square Feet to Square Meters Conversion

ft^2	m^2	ft^2	m^2	ft^2	m^2	ft^2	m^2	ft^2	m^2
1,000	92.903	100	9.290	10	0.929	1	0.093	0.1	0.009
2,000	185.806	200	18.581	20	1.858	2	0.186	0.2	0.019
3,000	278.709	300	27.871	30	2.787	3	0.279	0.3	0.028
4,000	371.612	400	37.161	40	3.716	4	0.372	0.4	0.037
5,000	464.515	500	46.452	50	4.645	5	0.465	0.5	0.046
6,000	557.418	600	55.742	60	5.574	6	0.557	0.6	0.056
7,000	650.321	700	65.032	70	6.503	7	0.650	0.7	0.065
8,000	743.224	800	74.322	80	7.432	8	0.743	0.8	0.074
9,000	836.127	900	83.613	90	8.361	9	0.836	0.9	0.084
10,000	929.030	1,000	92.903	100	9.290	10	0.929	1.0	0.093

Based on 1 inch = 2.54 centimeters, exactly, 1 $ft^2 = 0.09290304\ m^2$, exactly.

Table 18b. Square Meters to Square Feet Conversion

m^2	ft^2	m^2	ft^2	m^2	ft^2	m^2	ft^2	m^2	ft^2
100	1,076.39	10	107.64	1	10.76	0.1	1.08	0.01	0.11
200	2,152.78	20	215.28	2	21.53	0.2	2.15	0.02	0.22
300	3,229.17	30	322.92	3	32.29	0.3	3.23	0.03	0.32
400	4,305.56	40	430.56	4	43.06	0.4	4.31	0.04	0.43
500	5,381.96	50	538.20	5	53.82	0.5	5.38	0.05	0.54
600	6,458.35	60	645.83	6	64.58	0.6	6.46	0.06	0.65
700	7,534.74	70	753.47	7	75.35	0.7	7.53	0.07	0.75
800	8,611.13	80	861.11	8	86.11	0.8	8.61	0.08	0.86
900	9,687.52	90	968.75	9	96.88	0.9	9.69	0.09	0.97
1,000	10,763.91	100	1,076.39	10	107.64	1.0	10.76	0.10	1.08

Based on 1 inch = 2.54 centimeters, exactly, 1 $m^2 = 10.76391\ ft^2$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 19a. Square Yard to Square Meter Conversion

yd^2	m^2	yd^2	m^2	yd^2	m^2	yd^2	m^2	yd^2	m^2
1000	836.12736	100	83.612736	10	8.3612736	1	0.83612736	0.1	0.083612736
2000	1672.25472	200	167.225472	20	16.7225472	2	1.67225472	0.2	0.167225472
3000	2508.38208	300	250.838208	30	25.0838208	3	2.50838208	0.3	0.250838208
4000	3344.50944	400	334.450944	40	33.4450944	4	3.34450944	0.4	0.334450944
5000	4180.6368	500	418.06368	50	41.806368	5	4.1806368	0.5	0.41806368
6000	5016.76416	600	501.676416	60	50.1676416	6	5.01676416	0.6	0.501676416
7000	5852.89152	700	585.289152	70	58.5289152	7	5.85289152	0.7	0.585289152
8000	6689.01888	800	668.901888	80	66.8901888	8	6.68901888	0.8	0.668901888
9000	7525.14624	900	752.514624	90	75.2514624	9	7.52514624	0.9	0.752514624
10000	8361.2736	1000	836.12736	100	83.612736	10	8.3612736	1	0.83612736

Based on 1 inch = 2.54 centimeters, exactly, 1 $yd^2 = 0.83612736\ m^2$, exactly

Table 19b. Square Meter to Square Yard Conversion

m^2	yd^2	m^2	yd^2	m^2	yd^2	m^2	yd^2	m^2	yd^2
1000	1195.990046	100	119.5990046	10	11.95990046	1	1.195990046	0.1	0.119599005
2000	2391.980093	200	239.1980093	20	23.91980093	2	2.391980093	0.2	0.239198009
3000	3587.970139	300	358.7970139	30	35.87970139	3	3.587970139	0.3	0.358797014
4000	4783.960185	400	478.3960185	40	47.83960185	4	4.783960185	0.4	0.478396019
5000	5979.950232	500	597.9950232	50	59.79950232	5	5.979950232	0.5	0.597995023
6000	7175.940278	600	717.5940278	60	71.75940278	6	7.175940278	0.6	0.717594028
7000	8371.930324	700	837.1930324	70	83.71930324	7	8.371930324	0.7	0.837193032
8000	9567.92037	800	956.792037	80	95.6792037	8	9.56792037	0.8	0.956792037
9000	10763.91042	900	1076.391042	90	107.6391042	9	10.76391042	0.9	1.076391042
10000	11959.90046	1000	1195.990046	100	119.5990046	10	11.95990046	1	1.195990046

Based on 1 inch = 2.54 centimeters, exactly, 1 $m^2 = 1.195990046\ yd^2$.

Table 20a. Acres to Hectares Conversion

→ acres ↓	0	10	20	30	40	50	60	70	80	90
	hectares									
0	…	4.047	8.094	12.141	16.187	20.234	24.281	28.328	32.375	36.422
100	40.469	44.515	48.562	52.609	56.656	60.703	64.750	68.797	72.843	76.890
200	80.937	84.984	89.031	93.078	97.125	101.171	105.218	109.265	113.312	117.359
300	121.406	125.453	129.499	133.546	137.593	141.640	145.687	149.734	153.781	157.827
400	161.874	165.921	169.968	174.015	178.062	182.109	186.155	190.202	194.249	198.296
500	202.343	206.390	240.437	214.483	218.530	222.577	226.624	230.671	234.718	238.765
600	242.811	246.858	250.905	254.952	258.999	263.046	267.092	271.139	275.186	279.233
700	283.280	287.327	291.374	295.420	299.467	303.514	307.561	311.608	315.655	319.702
800	323.748	327.795	331.842	335.889	339.936	343.983	348.030	352.076	356.123	360.170
900	364.217	368.264	372.311	376.358	380.404	384.451	388.498	392.545	396.592	400.639
1000	404.686	…	…	…	…	…	…	…	…	…

1 acre = 0.4046856 hectare

Table 20b. Hectares to Acres Conversion

→ hectares ↓	0	10	20	30	40	50	60	70	80	90
	acres									
0	…	24.71	49.42	74.13	98.84	123.55	148.26	172.97	197.68	222.39
100	247.11	271.82	296.53	321.24	345.95	370.66	395.37	420.08	444.79	469.50
200	494.21	518.92	543.63	568.34	593.05	617.76	642.47	667.18	691.90	716.61
300	741.32	766.03	790.74	815.45	840.16	864.87	889.58	914.29	939.00	963.71
400	988.42	1013.13	1037.84	1062.55	1087.26	1111.97	1136.68	1161.40	1186.11	1210.82
500	1235.53	1260.24	1284.95	1309.66	1334.37	1359.08	1383.79	1408.50	1433.21	1457.92
600	1482.63	1507.34	1532.05	1556.76	1581.47	1606.19	1630.90	1655.61	1680.32	1705.03
700	1729.74	1754.45	1779.16	1803.87	1828.58	1853.29	1878.00	1902.71	1927.42	1952.13
800	1976.84	2001.55	2026.26	2050.97	2075.69	2100.40	2125.11	2149.82	2174.53	2199.24
900	2223.95	2248.66	2273.37	2298.08	2322.79	2347.50	2372.21	2396.92	2421.63	2446.34
1000	2471.05	…	…	…	…	…	…	…	…	…

1 hectare = 2.471054 acres

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Volume

Table 21. Cubic Measure and Conversion Factors

Metric System

1 cubic meter (m^3) =
1000 cubic decimeters (liters)
1,000,000 cubic centimeters
1.30795 cubic yards
35.314667 cubic feet
61,023.74 cubic inches
264.17205 U.S. gallons
219.96925 British Imperial gallons

1 liter (l) or 1 cubic decimeter (dm^3) =
1 liter = volume of 1 kg water at 39.2°F
0.001 cubic meter
1000 cubic centimeters
10 deciliters
0.03531466 cubic foot
61.023744 cubic inches
0.2642 U.S. gallon
0.21997 British Imperial gallon
1.0566882 U.S. quarts
33.814 U.S. fluid ounces

1 cubic centimeter (cm^3) =
0.001 liter
1000 cubic millimeters
0.061024 cubic inch

1 cubic milliliter = **0.001** cubic centimeters

1 hectoliter (hl) = **100** liters

1 deciliter (dl) = **10** centiliters

1 centiliter (cl) = **10** milliliters

U.S. System

1 cubic yard (yd^3) =
27 cubic feet
201.97403 U.S. gallons
46,656 cubic inch
0.7646 cubic meter

1 cubic foot (ft^3) =
1728 cubic inches
7.4805 U.S. gallons
6.23 British Imperial gallons
0.02831685 cubic meter
28.31685 liters

1 cubic inch (in^3) =
0.55411256 U.S. fluid ounces
16.387064 cubic centimeters

Shipping Measure

For measuring internal capacity of a vessel:

1 register ton = 100 cubic feet

For measurement of cargo:

1 shipping ton =
Approximately 40 cubic feet of merchandise is considered a shipping ton, unless that bulk would weigh more than 2000 pounds, in which case the freight charge may be based upon weight

40 cubic feet =
32.143 U.S. bushels
31.16 Imperial bushels

British (Imperial) Liquid and Dry Measure

1 British Imperial gallon =
0.1605 cubic foot
277.42 cubic inches
1.2009 U.S. gallon
160 Imperial fluid ounces
4 Imperial quarts
8 Imperial pints
4.54609 liters

1 quart =
2 Imperial pints
8 Imperial gills
40 Imperial fluid ounces
69.354 cubic inches
1.1365225 liters

1 pint =
4 Imperial gills
20 Imperial fluid ounces
34.678 cubic inches
568.26125 milliliters

1 gill =
5 Imperial fluid ounces
8.669 cubic inches
142.07 milliliters

U.S. Liquid Measure

1 U.S. gallon =
0.13368 cubic foot
231 cubic inches
128 U.S. fluid ounces
4 U.S. quarts
8 U.S. pints
0.8327 British Imperial gallon
3.785411784 liters

1 quart =
2 U.S. pints
8 U.S. gills
32 U.S. fluid ounces
57.75 cubic inches
0.9463529 liters

1 pint =
4 U.S. gills
16 U.S fluid ounces
28.875 cubic inches
473.176 milliliters

1 gill =
1/2 cup = **4** U.S. fluid ounces
7.21875 cubic inches
118.29 milliliters

Note: Figures in **Bold** indicate exact conversion values

Copyright 2004, Industrial Press, Inc., New York, NY

Table 21. *(Continued)* Cubic Measure and Conversion Factors

British (Imperial) Liquid and Dry Measure

1 British Imperial fluid ounce =
1.733871 cubic inch
$\frac{1}{160}$ British Imperial gallon
28.41306 milliliters

1 British Imperial bushel =
8 Imperial gallons = 1.284 cubic feet
2219.36 cubic inches

U.S. Dry Measure

1 bushel (U.S. or Winchester struck bushel) =
1.2445 cubic feet
2150.42 cubic inches
a cylinder 18.5 inches dia., 8 inches deep
a cylinder 47.0 cm dia., 20.3 cm deep

1 bushel = **4** pecks = **32** quarts = **64** pints

1 peck = **8** quarts = **16** pints

1 dry quart = **2** pints =
67.200625 cubic inches
1.101221 liters

1 heaped bushel = 1¼ struck bushel

1 cubic foot = 0.8036 struck bushel

Apothecaries' Fluid Measure

1 U.S. fluid ounce =
1.8046875 cubic inch
$\frac{1}{128}$ U.S. gallon
8 drachms
0.02957353 liter
29.57353 milliliters

1 fluid drachm = **60** minims

Old Liquid Measure

1 barrel (bbl) = 31½ gallons

1 hogshead = 2 barrels = 63 gallons

1 pipe or *butt* = 2 hogsheads = 4 barrels = 126 gallons

1 tierce = 42 gallons

1 puncheon = 2 tierces = 84 gallons

1 tun = 2 pipes = 3 puncheons

Other Cubic Measure

The following are used for wood and masonry:

1 cord of wood = 4 × 4 × 8 feet = 128 cubic feet

1 perch of masonry =
16½ × 1½ × 1 foot = 24¾ cubic feet

Barrel Measure

1 drum =
55 U.S. gallon
7.3524 cubic feet
208.19765 liters

1 petroleum barrel (bo) =
42 U.S. gallons
5.614583 cubic feet
158.98729 liters

Note: Figures in **Bold** indicate exact conversion values

Table 22a. Cubic Inches to Cubic Centimeters Conversion

inch³	cm³	inch³	cm³	inch³	cm³	inch³	cm³	inch³	cm³
100	1,638.71	10	163.87	1	16.39	0.1	1.64	0.01	0.16
200	3,277.41	20	327.74	2	32.77	0.2	3.28	0.02	0.33
300	4,916.12	30	491.61	3	49.16	0.3	4.92	0.03	0.49
400	6,554.82	40	655.48	4	65.55	0.4	6.55	0.04	0.66
500	8,193.53	50	819.35	5	81.94	0.5	8.19	0.05	0.82
600	9,832.24	60	983.22	6	98.32	0.6	9.83	0.06	0.98
700	11,470.94	70	1,147.09	7	114.71	0.7	11.47	0.07	1.15
800	13,109.65	80	1,310.96	8	131.10	0.8	13.11	0.08	1.31
900	14,748.35	90	1,474.84	9	147.48	0.9	14.75	0.09	1.47
1,000	16,387.06	100	1,638.71	10	163.87	1.0	16.39	0.10	1.64

Based on 1 inch = 2.54 centimeters, exactly. 1 inch³ = 16.387064 cm³, exactly

Table 22b. Cubic Centimeres to Cubic Inches Conversion

cm³	inch³	cm³	in³	cm³	inch³	cm³	in³	cm³	in³
1,000	61.024	100	6.102	10	0.610	1	0.061	0.1	0.006
2,000	122.048	200	12.205	20	1.220	2	0.122	0.2	0.012
3,000	183.071	300	18.307	30	1,831	3	0.183	0.3	0.018
4,000	244.095	400	24.410	40	2.441	4	0.244	0.4	0.024
5,000	305.119	500	30.512	50	3.051	5	0.305	0.5	0.031
6,000	366.143	600	36.614	60	3.661	6	0.366	0.6	0.037
7,000	427.166	700	42.717	70	4.272	7	0.427	0.7	0.043
8,000	488.190	800	48.819	80	4.882	8	0.488	0.8	0.049
9,000	549.214	900	54.921	90	5.492	9	0.549	0.9	0.055
10,000	610.238	1,000	61.024	100	6.102	10	0.610	1.0	0.061

Based on 1 inch = 2.54 centimeters, exactly. 1 cm³ = 0.06102376 inch³

Copyright 2004, Industrial Press, Inc., New York, NY

Table 23a. Cubic Feet to Cubic Meters Conversion

ft^3	m^3	ft^3	m^3	ft^3	m^3	ft^3	m^3	ft^3	m^3
1,000	28.317	100	2.832	10	0.283	1	0.028	0.1	0.003
2,000	56.634	200	5.663	20	0.566	2	0.057	0.2	0.006
3,000	84.951	300	8.495	30	0.850	3	0.085	0.3	0.008
4,000	113.267	400	11.327	40	1.133	4	0.113	0.4	0.011
5,000	141.584	500	14.158	50	1.416	5	0.142	0.5	0.014
6,000	169.901	600	16.990	60	1.699	6	0.170	0.6	0.017
7,000	198.218	700	19.822	70	1.982	7	0.198	0.7	0.020
8,000	226.535	800	22.653	80	2.265	8	0.227	0.8	0.023
9,000	254.852	900	25.485	90	2.549	9	0.255	0.9	0.025
10,000	283.168	1,000	28.317	100	2.832	10	0.283	1.0	0.028

Based on 1 inch = 2.54 centimeters, exactly. $1\ ft^3 = 0.02831685\ m^3$

Table 23b. Cubic Meters to Cubic Feet Conversion

m^3	ft^3	m^3	ft^3	m^3	ft^3	m^3	ft^3	m^3	ft^3
100	3,531.47	10	353.15	1	35.31	0.1	3.53	0.01	0.35
200	7,062.93	20	706.29	2	70.63	0.2	7.06	0.02	0.71
300	10,594.40	30	1,059.44	3	105.94	0.3	10.59	0.03	1.06
400	14,125.86	40	4,412.59	4	141.26	0.4	14.13	0.04	1.41
500	17,657.33	50	1,756.73	5	176.57	0.5	17.66	0.05	1.77
600	21,188.80	60	2,118.88	6	211.89	0.6	21.19	0.06	2.12
700	24,720.26	70	2,472.03	7	247.20	0.7	24.72	0.07	2.47
800	28,251.73	80	2,825.17	8	282.52	0.8	28.25	0.08	2.83
900	31,783.19	90	3,178.32	9	317.83	0.9	31.78	0.09	3.18
1,000	35,314.66	100	3,531.47	10	353.15	1.0	35.311	0.10	3.53

Based on 1 inch = 2.54 centimeters, exactly. $1\ m^3 = 35.31466\ ft^3$

Table 24a. Cubic Feet to Liters Conversion

ft^3	liters	ft^3	liters	ft^3	liters	ft^3	liters	ft^3	liters
100	2,831.68	10	283.17	1	28.32	0.1	2.83	0.01	0.28
200	5,663.37	20	566.34	2	56.63	0.2	5.66	0.02	0.57
300	8,495.06	30	849.51	3	84.95	0.3	8.50	0.03	0.85
400	11,326.74	40	1,132.67	4	113.27	0.4	11.33	0.04	1.13
500	14,158.42	50	1,415.84	5	141.58	0.5	14.16	0.05	1.42
600	16,990.11	60	1,699.01	6	169.90	0.6	16.99	0.06	1.70
700	19,821.80	70	1,982.18	7	198.22	0.7	19.82	0.07	1.98
800	22,653.48	80	2,263.35	8	226.53	0.8	22.65	0.08	2.27
900	25,485.16	90	2,548.52	9	254.85	0.9	25.49	0.09	2.55
1,000	28,316.85	100	2,831.68	10	283.17	1.0	28.32	0.10	2.83

$1\ ft^3 = 28.31685$ liters

Table 24b. Liters to Cubic Feet Conversion

liters	ft^3	liters	ft^3	liters	ft^3	liters	ft^3	liters	ft^3
1,000	35.315	100	3.531	10	0.353	1	0.035	0.1	0.004
2,000	70.629	200	7.063	20	0.706	2	0.071	0.2	0.007
3,000	105.944	300	10.594	30	1.059	3	0.106	0.3	0.011
4,000	141.259	400	14.126	40	1.413	4	0.141	0.4	0.014
5,000	176.573	500	17.657	50	1.766	5	0.177	0.5	0.018
6,000	211.888	600	21.189	60	2.119	6	0.212	0.6	0.021
7,000	247.203	700	24.720	70	2.472	7	0.247	0.7	0.025
8,000	282.517	800	28.252	80	2.825	8	0.283	0.8	0.028
9,000	317.832	900	31.783	90	3.178	9	0.318	0.9	0.032
10,000	353.147	1,000	35.315	100	3.531	10	0.353	1.0	0.035

1 liter = 0.03531466 ft^3

Copyright 2004, Industrial Press, Inc., New York, NY

Table 25a. U.K. (Imperial) Gallons to Liters Conversion

Imp. gals	0	1	2	3	4	5	6	7	8	9
	liters									
0	…	4.546	9.092	13.638	18.184	22.730	27.277	31.823	36.369	40.915
10	45.461	50.007	54.553	59.099	63.645	68.191	72.737	77.284	81.830	86.376
20	90.922	95.468	100.014	104.560	109.106	113.652	118.198	122.744	127.291	131.837
30	136.383	140.929	145.475	150.021	154.567	159.113	163.659	168.205	172.751	177.298
40	181.844	186.390	190.936	195.482	200.028	204.574	209.120	213.666	218.212	222.759
50	227.305	231.851	236.397	240.943	245.489	250.035	254.581	259.127	263.673	268.219
60	272.766	277.312	281.858	286.404	290.950	295.496	300.042	304.588	309.134	313.680
70	318.226	322.773	327.319	331.865	336.411	340.957	345.503	350.049	354.595	359.141
80	363.687	368.233	372.780	377.326	381.872	386.418	390.964	395.510	400.056	404.602
90	409.148	413.694	418.240	422.787	427.333	431.879	436.425	440.971	445.517	450.063
100	454.609	459.155	463.701	468.247	472.794	477.340	481.886	486.432	490.978	495.524

1 U.K. gallon = 4.546092 liters

Table 25b. Liters to U.K. (Imperial) Gallons Conversion

liters	0	1	2	3	4	5	6	7	8	9
	Imperial gallons									
0	…	0.220	0.440	0.660	0.880	1.100	1.320	1.540	1.760	1.980
10	2.200	2.420	2.640	2.860	3.080	3.300	3.520	3.739	3.959	4.179
20	4.399	4.619	4.839	5.059	5.279	5.499	5.719	5.939	6.159	6.379
30	6.599	6.819	7.039	7.259	7.479	7.699	7.919	8.139	8.359	8.579
40	8.799	9.019	9.239	9.459	9.679	9.899	10.119	10.339	10.559	10.778
50	10.998	11.218	11.438	11.658	11.878	12.098	12.318	12.538	12.758	12.978
60	13.198	13.418	13.638	13.858	14.078	14.298	14.518	14.738	14.958	15.178
70	15.398	15.618	15.838	16.058	16.278	16.498	16.718	16.938	17.158	17.378
80	17.598	17.818	18.037	18.257	18.477	18.697	18.917	19.137	19.357	19.577
90	19.797	20.017	20.237	20.457	20.677	20.897	21.117	21.337	21.557	21.777
100	21.997	22.217	22.437	22.657	22.877	23.097	23.317	23.537	23.757	23.977

1 liter = 0.2199692 U.K. gallons

Table 26a. U.S. Gallons to Liters Conversion

gals	liters	gals	liters	gals	liters	gals	liters	gals	liters
1,000	3,785.41	100	378.54	10	37.85	1	3.79	0.1	0.38
2,000	7,570.82	200	757.08	20	75.71	2	7.57	0.2	0.76
3,000	11,356.24	300	1,135.62	30	113.56	3	11.36	0.3	1.14
4,000	15,141.65	400	1,514.16	40	151.42	4	15.14	0.4	1.51
5,000	18,927.06	500	1,892.71	50	189.27	5	18.93	0.5	1.89
6,000	22,712.47	600	2,271.25	60	227.12	6	22.71	0.6	2.27
7,000	26,497.88	700	2,649.79	70	264.98	7	26.50	0.7	2.65
8,000	30,283.30	800	3,028.33	80	302.83	8	30.28	0.8	3.03
9,000	34,068.71	900	3,406.87	90	340.69	9	34.07	0.9	3.41
10,000	37,854.12	1,000	3,785.41	100	378.54	10	37.85	1.0	3.79

1 U.S. gallon = 3.785412 liters

Table 26b. Liters to U.S. Gallons Conversion

liters	gals	liters	gals	liters	gals	liters	gals	liters	gals
1,000	264.17	100	26.42	10	2.64	1	0.26	0.1	0.03
2,000	528.34	200	52.83	20	5.28	2	0.53	0.2	0.05
3,000	792.52	300	79.25	30	7.93	3	0.79	0.3	0.08
4,000	1,056.69	400	105.67	40	10.57	4	1.06	0.4	0.11
5,000	1,320.86	500	132.09	50	13.21	5	1.32	0.5	0.13
6,000	1,585.03	600	158.50	60	15.85	6	1.59	0.6	0.16
7,000	1,849.20	700	184.92	70	18.49	7	1.85	0.7	0.18
8,000	2,113.38	800	211.34	80	21.13	8	2.11	0.8	0.21
9,000	2,377.55	900	237.75	90	23.78	9	2.38	0.9	0.24
10,000	2,641.72	1,000	264.17	100	26.42	10	2.64	1.0	0.26

1 liter = 0.2641720 U.S. gallon

Copyright 2004, Industrial Press, Inc., New York, NY

Table 27a. U.S. Fluid Ounces to Milliliters Conversion

oz	mL	oz	mL	oz	mL	oz	mL	oz	mL
100	2957.353	10	295.7353	1	29.57353	0.1	2.957353	0.01	0.2957353
200	5914.706	20	591.4706	2	59.14706	0.2	5.914706	0.02	0.5914706
300	8872.059	30	887.2059	3	88.72059	0.3	8.872059	0.03	0.8872059
400	11829.412	40	1182.9412	4	118.29412	0.4	11.829412	0.04	1.1829412
500	14786.765	50	1478.6765	5	147.86765	0.5	14.786765	0.05	1.4786765
600	17744.118	60	1774.4118	6	177.44118	0.6	17.744118	0.06	1.7744118
700	20701.471	70	2070.1471	7	207.01471	0.7	20.701471	0.07	2.0701471
800	23658.824	80	2365.8824	8	236.58824	0.8	23.658824	0.08	2.3658824
900	26616.177	90	2661.6177	9	266.16177	0.9	26.616177	0.09	2.6616177
1000	29573.53	100	2957.353	10	295.7353	1	29.57353	0.1	2.957353

1 U.S. fluid ounce = 29.57353 milliliters

Table 27b. Milliliters to U.S. Fluid Ounces Conversion

mL	oz	mL	oz	mL	oz	mL	oz	mL	oz
100	3.3814	10	0.33814	1	0.033814	0.1	0.0033814	0.01	0.00033814
200	6.7628	20	0.67628	2	0.067628	0.2	0.0067628	0.02	0.00067628
300	10.1442	30	1.01442	3	0.101442	0.3	0.0101442	0.03	0.00101442
400	13.5256	40	1.35256	4	0.135256	0.4	0.0135256	0.04	0.00135256
500	16.907	50	1.6907	5	0.16907	0.5	0.016907	0.05	0.0016907
600	20.2884	60	2.02884	6	0.202884	0.6	0.0202884	0.06	0.00202884
700	23.6698	70	2.36698	7	0.236698	0.7	0.0236698	0.07	0.00236698
800	27.0512	80	2.70512	8	0.270512	0.8	0.0270512	0.08	0.00270512
900	30.4326	90	3.04326	9	0.304326	0.9	0.0304326	0.09	0.00304326
1000	33.814	100	3.3814	10	0.33814	1	0.033814	0.1	0.0033814

1 milliliter = 0.003814 U.S. fluid ounce

Units of Volumetric Flow Rate

Table 28a. Volume Flow per Second Conversion

To Convert ↓	Multiply By Factor To Obtain →	Cm^3/sec	$Meter^3/sec$	$Foot^3/sec$	Liter/sec	Gallon/sec (US)	Gallon/sec (UK)
Cm^3/sec		1	**1×10^{-6}**	3.531×10^{-5}	**0.001**	2.642×10^{-4}	2.19969×10^{-4}
$Meter^3/sec$		**1×10^{6}**	1	35.31466	**1,000**	264.172	219.9692
$Foot^3/sec$		28,316.846	0.028316	1	28.3168	7.480519	6.22883
Liter/sec		**1000**	**0.001**	0.0353146	1	0.264172	0.21996
Gallon/sec (US)		3,785.412	3.7854×10^{-3}	0.133368	3.785412	1	0.8326739
Gallon/sec (UK)		4,546.092	4.546×10^{-3}	0.1605432	4.546092	1.2009504	1

Table 28b. Volume Flow per Minute Conversion

To Convert ↓	Multiply By Factor To Obtain →	$Foot^3/min$	Liter/min	Gallon/min (US)	Gallon/min (UK)
$Foot^3/min$		1	28.316846	7.480519	6.2288327
Liter/min		0.035314	1	0.264172	0.2199692
Gallon/min (US)		0.133680	3.785412	1	0.832673
Gallon/min (UK)		0.1605437	4.546092	1.20095	1

Pitot Tube.— A pitot tube is a small, transparent, open tube bent at right angle. It is a hollow tube that is placed longitudinally in the direction of fluid flow, allowing the flow to enter one end at the fluids velocity of approach. When the fluids enter the pitot tube, it comes to a stop, all of the velocity head is converted to pressure head. The difference between the total and static energies is the kinetic energy of the fluid. The velocity of the fluid can be calculated by using the Bernoulli equation.

$$\frac{p_1}{\rho} + \frac{v_1^2}{2} = \frac{p_2}{\rho} \qquad v_1 = \sqrt{\frac{2(p_2 - p_1)}{\rho}} \text{ (SI)} \qquad v_1 = \sqrt{\frac{2(p_2 - p_1)g_c}{\rho}} \text{ (US)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Mass and Weight

Table 29. Mass and Weight Conversion Factors

Metric System

1 metric ton (t) =
1000 kilograms
2204.6223 pounds
0.9842 gross or long ton (of 2240 pounds)
0.9072 net or short ton (of 2000 pounds)

1 kilogram (kg) =
1000 grams = **10** hectograms
2.2046 pounds
35.274 ounces avoirdupois

1 hectogram (hg) = **10** dekagrams

1 dekagram (dag) = **10** grams

1 gram (g) =
10 decigrams
0.0022046 pound
0.03215 ounce Troy
0.03527 ounce avoirdupois
15.432 grains

1 decigram (dg) = **10** centigrams

1 centigram (cg) = **10** milligrams

Avoirdupois or Commercial Weight

1 gross or long ton =
2240 pounds
1.016 metric ton
1016 kilograms

1 net or short ton = **2000** pounds

1 pound = **16** ounces
7000 grains
0.45359237 kilogram
453.6 grams

1 ounce =
$\frac{1}{16}$ pound
16 drachms
437.5 grains
28.3495 grams
0.2780139 newton

1 grain Avoirdupois =
1 grain apothecaries' weight =
1 grain Troy weight
0.064799 gram

Troy Weight

Used for Weighing Gold and Silver

1 pound Troy =
12 ounces Troy = 5760 grains
$\frac{144}{175}$ Avoirdupois pound

1 ounce Troy =
20 pennyweights = 480 grains
31.103 grams

1 pennyweight = 24 grains

1 grain Troy =
1 grain avoirdupois
1 grain apothecaries' weight
0.0648 gram

1 carat (used in weighing diamonds) =
3.086 grains
200 milligrams = $\frac{1}{5}$ gram

1 gold karat = $\frac{1}{24}$ proportion pure gold

Apothecaries' Weight

1 pound = 12 ounces = 5760 grains

1 ounce =
8 drachms = 480 grains
31.103 grams

1 drachm = 3 scruples = 60 grains

1 scruple = 20 grains

Old Weight Measures

Measures for weight seldom used in the United States:

1 gross or long ton = 20 hundred-weights

1 hundred-weight = 4 quarters = 112 pounds

1 quarter = 28 pounds

1 stone = 14 pounds

1 quintal = 100 pounds

Note: Figures in **Bold** indicate exact conversion values

Table 30a. Pounds to Kilograms Conversion

lb	kg	lb	kg	lb	kg	lb	kg	lb	kg
1,000	453.59	100	45.36	10	4.54	1	0.45	0.1	0.05
2,000	907.18	200	90.72	20	9.07	2	0.91	0.2	0.09
3,000	1,360.78	300	136.08	30	13.61	3	1.36	0.3	0.14
4,000	1,814.37	400	181.44	40	18.14	4	1.81	0.4	0.18
5,000	2,267.96	500	226.80	50	22.68	5	2.27	0.5	0.23
6,000	2,721.55	600	272.16	60	27.22	6	2.72	0.6	0.27
7,000	3,175.15	700	317.51	70	31.75	7	3.18	0.7	0.32
8,000	3,628.74	800	362.87	80	36.29	8	3.63	0.8	0.36
9,000	4,082.33	900	408.23	90	40.82	9	4.08	0.9	0.41
10,000	4,535.92	1,000	453.59	100	45.36	10	4.54	1.0	0.45

1 pound = 0.4535924 kilogram

Copyright 2004, Industrial Press, Inc., New York, NY

Table 30b. Kilograms to Pounds Conversion

kg	lb	kg	lb	kg	lb	kg	lb	kg	lb
1,000	2,204.62	100	220.46	10	22.05	1	2.20	0.1	0.22
2,000	4,409.24	200	440.92	20	44.09	2	4.41	0.2	0.44
3,000	6,613.87	300	661.39	30	66.14	3	6.61	0.3	0.66
4,000	8,818.49	400	881.85	40	88.18	4	8.82	0.4	0.88
5,000	11,023.11	500	1,102.31	50	110.23	5	11.02	0.5	1.10
6,000	13,227.73	600	1,322.77	60	132.28	6	13.23	0.6	1.32
7,000	15,432.35	700	1,543.24	70	154.32	7	15.43	0.7	1.54
8,000	17,636.98	800	1,763.70	80	176.37	8	17.64	0.8	1.76
9,000	19,841.60	900	1,984.16	90	198.42	9	19.84	0.9	1.98
10,000	22,046.22	1,000	2,204.62	100	220.46	10	22.05	1.0	2.20

1 kilogram = 2.204622 pounds

Table 31a. Ounces to Grams Conversion

oz	g	oz	g	oz	g	oz	g	oz	g
10	283.50	1	28.35	0.1	2.83	0.01	0.28	0.001	0.03
20	566.99	2	56.70	0.2	5.67	0.02	0.57	0.002	0.06
30	850.49	3	85.05	0.3	8.50	0.03	0.85	0.003	0.09
40	1,133.98	4	113.40	0.4	11.34	0.04	1.13	0.004	0.11
50	1,417.48	5	141.75	0.5	14.17	0.05	1.42	0.005	0.14
60	1,700.97	6	170.10	0.6	17.01	0.06	1.70	0.006	0.17
70	1,984.47	7	198.45	0.7	19.84	0.07	1.98	0.007	0.20
80	2,267.96	8	226.80	0.8	22.68	0.08	2.27	0.008	0.23
90	2,551.46	9	255.15	0.9	25.51	0.09	2.55	0.009	0.26
100	2,834.95	10	283.50	1.0	28.35	0.10	2.83	0.010	0.28

1 ounce = 28.34952 grams

Table 31b. Grams to Ounces Conversion

g	oz	g	oz	g	oz	g	oz	g	oz
100	3.527	10	0.353	1	0.035	0.1	0.004	0.01	0.000
200	7.055	20	0.705	2	0.071	0.2	0.007	0.02	0.001
300	10.582	30	1.058	3	0.106	0.3	0.011	0.03	0.001
400	14.110	40	1.411	4	0.141	0.4	0.014	0.04	0.001
500	17.637	50	1.764	5	0.176	0.5	0.018	0.05	0.002
600	21.164	60	2.116	6	0.212	0.6	0.021	0.06	0.002
700	24.692	70	2.469	7	0.247	0.7	0.025	0.07	0.002
800	28.219	80	2.822	8	0.282	0.8	0.028	0.08	0.003
900	31.747	90	3.175	9	0.317	0.9	0.032	0.09	0.003
1,000	35.274	100	3.527	10	0.353	1.0	0.035	0.10	0.004

1 gram = 0.03527397 ounce

Table 32. Density Conversion Factors

To Convert ↓	→	Gram/mL	Gram/cm^3	Kg/m^3	Lb/inch^3	Lb/feet^3	Lb/gallon (US)	Ton/yard^3
Grams/mL	Multiply By This Factor, To Obtain	1	1	**1000**	0.036128	62.43	8.345	0.8428
Grams/cm^3		1	1	**1000**	0.036128	62.43	8.345	0.8428
Kilogram/m^3		**0.001**	**0.001**	1	3.6128×10^{-5}	0.06243	0.008345	8.428×10^{-4}
Lb/inch^3		27.67788	27.67788	27677.83	1	1728.0	230.9718	23.32687
Lb/feet^3		0.01602	0.01602	16.02	5.787×10^{-4}	1	0.1337	0.01349
Lb/gallon (US)		0.11983	0.11983	119.83	0.004329	7.481126	1	0.10099
Ton/yard^3		1.18652	1.18652	1186.52	0.042869	74.07451	9.9015	1

Copyright 2004, Industrial Press, Inc., New York, NY

Table 33a. Pounds per Cubic Inch to Grams per Cubic Centimeter Conversion

lb/in³	g/cm³	lb/in³	g/cm³	lb/in³	g/cm³	lb/in³	g/cm³	lb/in³	g/cm³
100	2,767.99	10	276.80	1	27.68	0.1	2.77	0.01	0.28
200	5,535.98	20	553.60	2	55.36	0.2	5.54	0.02	0.55
300	8,303.97	30	830.40	3	83.04	0.3	8.30	0.03	0.83
400	11,071.96	40	1,107.20	4	110.72	0.4	11.07	0.04	1.11
500	13,839.95	50	1,384.00	5	138.40	0.5	13.84	0.05	1.38
600	16,607.94	60	1,660.79	6	166.08	0.6	16.61	0.06	1.66
700	19,375.93	70	1,937.59	7	193.76	0.7	19.38	0.07	1.94
800	22,143.92	80	2,214.39	8	221.44	0.8	22.14	0.08	2.21
900	24,911.91	90	2,491.19	9	249.12	0.9	24.91	0.09	2.49
1,000	27,679.90	100	2,767.99	10	276.80	1.0	27.68	0.10	2.77

1 lb/in³ = 27.67990 g/cm³

Table 33b. Grams per Cubic Centimeter to Pounds per Cubic Inch Conversion

g/cm³	lb/in³	g/cm³	lb/in³	g/cm³	lb/in³	g/cm³	lb/in³	g/cm³	lb/in³
1,000	36.127	100	3.613	10	0.361	1	0.036	0.1	0.004
2,000	72.255	200	7.225	20	0.723	2	0.072	0.2	0.007
3,000	108.382	300	10.838	30	1.084	3	0.108	0.3	0.011
4,000	144.509	400	14.451	40	1.445	4	0.145	0.4	0.014
5,000	180.636	500	18.064	50	1.806	5	0.181	0.5	0.018
6,000	216.764	600	21.676	60	2.168	6	0.217	0.6	0.022
7,000	252.891	700	25.289	70	2.529	7	0.253	0.7	0.025
8,000	289.018	800	28.902	80	2.890	8	0.289	0.8	0.029
9,000	325.146	900	32.515	90	3.251	9	0.325	0.9	0.033
10,000	361.273	1,000	36.127	100	3.613	10	0.361	1.0	0.036

1 g/cm³ = 0.03612730 lb/in³

Table 34a. Pounds per Cubic Foot to Kilograms per Cubic Meter Conversion

lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³
100	1,601.85	10	160.18	1	16.02	0.1	1.60	0.01	0.16
200	3,203.69	20	320.37	2	32.04	0.2	3.20	0.02	0.32
300	4,805.54	30	480.55	3	48.06	0.3	4.81	0.03	0.48
400	6,407.38	40	640.74	4	64.07	0.4	6.41	0.04	0.64
500	8,009.23	50	800.92	5	80.09	0.5	8.01	0.05	0.80
600	9,611.08	60	961.11	6	96.11	0.6	9.61	0.06	0.96
700	11,212.92	70	1,121.29	7	112.13	0.7	11.21	0.07	1.12
800	12,814.77	80	1,281.48	8	128.15	0.8	12.81	0.08	1.28
900	14,416.61	90	1,441.66	9	144.17	0.9	14.42	0.09	1.44
1,000	16,018.46	100	1,601.85	10	160.18	1.0	16.02	0.10	1.60

1 lb/ft³ = 16.01846 kg/m³

Table 34b. Kilograms per Cubic Meter to Pounds per Cubic Foot Conversion

kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³	kg/m³	lb/ft³
1,000	62.428	100	6.243	10	0.624	1	0.062	0.1	0.006
2,000	124.856	200	12.486	20	1.249	2	0.125	0.2	0.012
3,000	187.284	300	18.728	30	1.873	3	0.187	0.3	0.019
4,000	249.712	400	24.971	40	2.497	4	0.250	0.4	0.025
5,000	312.140	500	31.214	50	3.121	5	0.312	0.5	0.031
6,000	374.568	600	37.457	60	3.746	6	0.375	0.6	0.037
7,000	436.996	700	43.700	70	4.370	7	0.437	0.7	0.044
8,000	499.424	800	49.942	80	4.994	8	0.499	0.8	0.050
9,000	561.852	900	56.185	90	5.619	9	0.562	0.9	0.056
10,000	624.280	1,000	62.428	100	6.243	10	0.624	1.0	0.062

1 kg/m³ =0.06242797 lb/ft³

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Pressure and Stress

Table 35. Pressure and Stress Conversion Factors

1 kilogram per sq. millimeter (kg_f/mm^2) =
1422.32 pounds per square inch

1 kilogram per sq. centimeter (kg_f/cm^2) =
14.223 pounds per square inch

1 bar =
1,000,000 dynes per square centimeter
1000 millibars
100 kilopascals
750.06168 torr
1.0197162 kilogram force per sq. centimeter
14.50377 pounds per square inch
29.529983 inches of mercury at 0°C
10,197.162 mm water at 4°C
33.455256 feet of water at 4°C

1 millibar =
100,000 dynes per square centimeter
100 pascal

1 torr =
760 millimeters mercury
$^1/_{760}$ atmosphere
133.224 pascal
1.333224 millibar

1 pound per square inch =
144 pounds per square foot
0.068 atmosphere
2.042 inches of mercury at 62°F
27.7 inches of water at 62°F
2.31 feet of water at 62°F
0.0703 kilogram per square centimeter
6.894757 kilopascals
6894.757 pascal

1 atmosphere =
30 inches of mercury at 62°F
14.7 pounds per square inch
2116.3 pounds per square foot
33.95 feet of water at 62°F

1 foot of water at 62°F =
62.355 pounds per square foot
0.433 pound per square inch

1 inch of mercury at 62°F =
1.132 foot of water
13.58 inches of water
0.491 pound per square inch

1 inch of water =
0.0735559 inch mercury at 0°C
1.8683205 torr
0.5780367 ounce force per square inch
0.0024583 atmosphere

Table 36a. Pounds per Square Inch to Kilograms per Square Centimeter Conversion

lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2
1,000	70.307	100	7.031	10	0.703	1	0.070	0.1	0.007
2,000	140.614	200	14.061	20	1.406	2	0.141	0.2	0.014
3,000	210.921	300	21.092	30	2.109	3	0.211	0.3	0.021
4,000	281.228	400	28.123	40	2.812	4	0.281	0.4	0.028
5,000	351.535	500	35.153	50	3.515	5	0.352	0.5	0.035
6,000	421.842	600	42.184	60	4.218	6	0.422	0.6	0.042
7,000	492.149	700	49.215	70	4.921	7	0.492	0.7	0.049
8,000	562.456	800	56.246	80	5.625	8	0.562	0.8	0.056
9,000	632.763	900	63.276	90	6.328	9	0.633	0.9	0.063
10,000	703.070	1,000	70.307	100	7.031	10	0.703	1.0	0.070

1 lb/in^2 = 0.07030697 kg/cm^2

Table 36b. Kilogram per Square Centimeter to Pounds per Square Inch Conversion

kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2	kg/cm^2	lb/in^2
100	1,422.33	10	142.23	1	14.22	0.1	1.42	0.01	0.14
200	2,844.67	20	284.47	2	28.45	0.2	2.84	0.02	0.28
300	4,267.00	30	426.70	3	42.67	0.3	4.27	0.03	0.43
400	5,689.34	40	568.93	4	56.89	0.4	5.69	0.04	0.57
500	7,111.67	50	711.17	5	71.12	0.5	7.11	0.05	0.71
600	8,534.00	60	853.40	6	85.34	0.6	8.53	0.06	0.85
700	9,956.34	70	995.63	7	99.56	0.7	9.96	0.07	1.00
800	11,378.67	80	1,137.87	8	113.79	0.8	11.38	0.08	1.14
900	12,801.01	90	1,280.10	9	128.01	0.9	12.80	0.09	1.28
1,000	14,223.34	100	1,422.33	10	142.23	1.0	14.22	0.10	1.42

1 kg/cm^2 = 14.22334 lb/in^2

Copyright 2004, Industrial Press, Inc., New York, NY

Table 37a. Pounds per Square Foot to Kilograms per Square Meter Conversion

lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2
1,000	4,882.43	100	488.24	10	48.82	1	4.88	0.1	0.49
2,000	9,764.86	200	976.49	20	97.65	2	9.76	0.2	0.98
3,000	14,647.29	300	1,464.73	30	146.47	3	14.65	0.3	1.46
4,000	19,529.72	400	1,952.97	40	195.30	4	19.53	0.4	1.95
5,000	24,412.14	500	2,441.21	50	244.12	5	24.41	0.5	2.44
6,000	29,294.57	600	2,929.46	60	292.95	6	29.29	0.6	2.93
7,000	34,177.00	700	3,417.70	70	341.77	7	34.18	0.7	3.42
8,000	39,059.43	800	3,905.94	80	390.59	8	39.06	0.8	3.91
9,000	43,941.86	900	4,394.19	90	439.42	9	43.94	0.9	4.39
10,000	48,824.28	1,000	4,882.43	100	488.24	10	48.82	1.0	4.88

1 lb/ft^2 = 4.882429 kg/m^2

Table 37b. Kilograms per Square Meter to Pounds per Square Foot Conversion

kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2	kg/m^2	lb/ft^2
1,000	204.82	100	20.48	10	2.05	1	0.20	0.1	0.02
2,000	409.63	200	40.96	20	4.10	2	0.41	0.2	0.04
3,000	614.45	300	61.44	30	6.14	3	0.61	0.3	0.06
4,000	819.26	400	81.93	40	8.19	4	0.82	0.4	0.08
5,000	1,024.08	500	102.41	50	10.24	5	1.02	0.5	0.10
6,000	1,228.90	600	122.89	60	12.29	6	1.23	0.6	0.12
7,000	1,433.71	700	143.37	70	14.34	7	1.43	0.7	0.14
8,000	1,638.53	800	163.85	80	16.39	8	1.64	0.8	0.16
9,000	1,843.34	900	184.33	90	18.43	9	1.84	0.9	0.18
10,000	2,048.16	1,000	204.82	100	20.48	10	2.05	1.0	0.20

1 kg/m^2 = 0.2048161 lb/ft^2

Table 38a. Pounds Per Square Inch to Kilopascals Conversion

→ / lb/in^2 ↓	0	1	2	3	4	5	6	7	8	9
	kilopascals									
0	…	6.895	13.790	20.684	27.579	34.474	41.369	48.263	55.158	62.053
10	68.948	75.842	82.737	89.632	96.527	103.421	110.316	117.211	124.106	131.000
20	137.895	144.790	151.685	158.579	165.474	172.369	179.264	186.158	193.053	199.948
30	206.843	213.737	220.632	227.527	234.422	241.316	248.211	255.106	262.001	268.896
40	275.790	282.685	289.580	296.475	303.369	310.264	317.159	324.054	330.948	337.843
50	344.738	351.633	358.527	365.422	372.317	379.212	386.106	393.001	399.896	406.791
60	413.685	420.580	427.475	434.370	441.264	448.159	455.054	461.949	468.843	475.738
70	482.633	489.528	496.423	503.317	510.212	517.107	524.002	530.896	537.791	544.686
80	551.581	558.475	565.370	572.265	579.160	586.054	592.949	599.844	606.739	613.633
90	620.528	627.423	634.318	641.212	648.107	655.002	661.897	668.791	675.686	682.581
100	689.476	696.370	703.265	710.160	717.055	723.949	730.844	737.739	744.634	751.529

1 lb/in^2 = 6.894757 kPa. *Note:* 1 kilopascal = 1 kilonewton/$meter^2$.

Table 38b. Kilopascals to Pounds Per Square Inch Conversion

→ / kPa ↓	0	1	2	3	4	5	6	7	8	9
	lb/in^2									
0	…	0.145	0.290	0.435	0.580	0.725	0.870	1.015	1.160	1.305
10	1.450	1.595	1.740	1.885	2.031	2.176	2.321	2.466	2.611	2.756
20	2.901	3.046	3.191	3.336	3.481	3.626	3.771	3.916	4.061	4.206
30	4.351	4.496	4.641	4.786	4.931	5.076	5.221	5.366	5.511	5.656
40	5.802	5.947	6.092	6.237	6.382	6.527	6.672	6.817	6.962	7.107
50	7.252	7.397	7.542	7.687	7.832	7.977	8.122	8.267	8.412	8.557
60	8.702	8.847	8.992	9.137	9.282	9.427	9.572	9.718	9.863	10.008
70	10.153	10.298	10.443	10.588	10.733	10.878	11.023	11.168	11.313	11.458
80	11.603	11.748	11.893	12.038	12.183	12.328	12.473	12.618	12.763	12.908
90	13.053	13.198	13.343	13.489	13.634	13.779	13.924	14.069	14.214	14.359
100	14.504	14.649	14.794	14.939	15.084	15.229	15.374	15.519	15.664	15.809

1 kPa = 0.1450377 lb/in^2. *Note:* 1 kilopascal = 1 kilonewton/$meter^2$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 39. Pressure and Stress Conversion Factors

To Convert ↓ / Multiply By This Factor, To Obtain →	Atmosphere	Pascal (n/m^2)	Dyne/cm^2	Bar	Kg/cm^2	Kg/m^2	Psia (Lb/$inch^2$)	Pound/ft^2	Inch of Water	Inch of Mercury	Millimeter of Mercury	Ton/ft^2
Atmosphere	1	101325	1.0133×10^6	1.01325	1.03319076	10,331.9076	14.6959488	2,116.216	407.1893	29.9212	760	0.9597354
Pascal (n/m^2)	9.8692×10^{-6}	1	**10**	$\mathbf{1 \times 10^{-5}}$	1.01968×10^{-5}	0.101968	0.00014504	0.02088	0.004019	0.0002953	0.0075	9.472×10^{-6}
Dyne/cm^2	9.8692×10^{-7}	**0.1**	1	$\mathbf{1 \times 10^{-6}}$	1.01968×10^{-6}	0.0101968	1.4504×10^{-5}	0.002088	0.000402	2.95×10^{-5}	0.00075	9.472×10^{-7}
Bar	0.98692327	$\mathbf{1 \times 10^5}$	$\mathbf{1 \times 10^6}$	1	1.01968	10194.8	14.5037256	2088.5434	401.8646	29.5299	750.06168	0.9471852
Kilogram/$centimeter^2$	0.96784111	98,069.982	980,699.83	0.9807	1	**10000**	14.2232691	2048.6123	394.0945	28.9653	735.58536	0.9289043
Kilogram/$meter^2$	9.6787×10^{-5}	9.80699	98.06998	9.807×10^{-5}	**0.0001**	1	0.001422	0.204823	0.039409	0.002896	0.0735585	9.289×10^{-5}
Psi (Lb/$inch^2$)	0.06804596	6,894.7572	68,947.573	0.068947	0.07029148	703.0446	1	**144**	27.70768	2.03602	51.71493	0.0653061
Pound/ft^2	4.7254×10^{-4}	47.88025	478.80258	0.000478	0.00048813	4.88225	0.006944	1	0.19241	0.014139	0.3591314	0.0004535
Inch of Water	0.00245586	248.8400	2488.4003	0.002488	0.00253690	25.3737	0.036091	5.19713	1	0.073482	1.866453	0.002356
Inch of Mercury	0.03342112	3386.3949	33,863.949	0.033863	0.03452401	345.3039	0.491153	70.72632	13.6087	1	**25.4**	0.0320754
Millimeter of Mercury	0.00131579	133.32236	1333.22368	0.001333	0.00135921	13.594615	0.019336	2.784495	0.53577	0.03937	1	0.0012628
Ton/ft^2 (US)	1.04195382	105575.970	1055759.70	1.055759	1.076537	10765.3706	15.3125	2205	424.2724	31.1765	791.8849	1

Units of Force

Table 40. Force Conversion Factors

To Convert ↓ / Multiply By This Factor, To Obtain →	Dyne	Gram-force	Joule/cm	Newton	Kg_f	Lb_f	Kip	Poundal	Ounce-force
Dyne	1	0.00101968	**0.001**	**0.00001**	1.01968×10^{-6}	2.24809×10^{-6}	2.2481×10^{-9}	7.233013×10^{-5}	3.59694×10^{-5}
Gram-force	980.7	1	0.9807	0.009807	**0.001**	0.0022047	2.2047×10^{-6}	0.0709341	0.03527521
Joule/cm	**1000**	1.0196798	1	**0.01**	0.00101968	0.002248	2.2481×10^{-6}	0.0723301	0.03596942
Newton	$\mathbf{1 \times 10^5}$	101.96798	**100**	1	0.101967982	0.2248089	2.2481×10^{-4}	7.23301	3.596942
Kg-force	9.807×10^5	**1000**	980.7	9.807	1	2.2047	0.0022047	70.934129	35.2752102
Lb_f	4.4482×10^5	453.57627	444.822	4.44822	0.45357626	1	**0.001**	32.174038	16
Kip	4.4482×10^8	4.5357×10^5	4.4482×10^5	4448.2224	453.5762688	**1000**	1	32174.038	16000
Poundal	13825.50	14.097586	13.8255	0.1382555	0.014097586	0.0310809	3.1081×10^{-5}	1	0.497296
Ounce-force	27801.39	28.348519	27.8013	0.278013	0.02834852	0.06250	6.25×10^{-5}	2.010877	1

Figures in **bold face** indicate the conversion is exact

Copyright 2004, Industrial Press, Inc., New York, NY

Table 41a. Pounds-Force to Newtons Conversion

$lb_f \rightarrow$ ↓	0	1	2	3	4	5	6	7	8	9
	newtons									
0	…	4.448	8.896	13.345	17.793	22.241	26.689	31.138	35.586	40.034
10	44.482	48.930	53.379	57.827	62.275	66.723	71.172	75.620	80.068	84.516
20	88.964	93.413	97.861	102.309	106.757	111.206	115.654	120.102	124.550	128.998
30	133.447	137.895	142.343	146.791	151.240	155.688	160.136	164.584	169.032	173.481
40	177.929	182.377	186.825	191.274	195.722	200.170	204.618	209.066	213.515	217.963
50	222.411	226.859	231.308	235.756	240.204	244.652	249.100	253.549	257.997	262.445
60	266.893	271.342	275.790	280.238	284.686	289.134	293.583	298.031	302.479	306.927
70	311.376	315.824	320.272	324.720	329.168	333.617	338.065	342.513	346.961	351.410
80	355.858	360.306	364.754	369.202	373.651	378.099	382.547	386.995	391.444	395.892
90	400.340	404.788	409.236	413.685	418.133	422.581	427.029	431.478	435.926	440.374
100	444.822	449.270	453.719	458.167	462.615	467.063	471.512	475.960	480.408	484.856

1 pound-force = 4.448222 newtons

Table 41b. Newtons to Pounds-Force Conversion

N→ ↓	0	1	2	3	4	5	6	7	8	9
	pounds-force									
0	…	0.22481	0.44962	0.67443	0.89924	1.12404	1.34885	1.57366	1.79847	2.02328
10	2.24809	2.47290	2.69771	2.92252	3.14732	3.37213	3.59694	3.82175	4.04656	4.27137
20	4.49618	4.72099	4.94580	5.17060	5.39541	5.62022	5.84503	6.06984	6.29465	6.51946
30	6.74427	6.96908	7.19388	7.41869	7.64350	7.86831	8.09312	8.31793	8.54274	8.76755
40	8.99236	9.21716	9.44197	9.66678	9.89159	10.1164	10.3412	10.5660	10.7908	11.0156
50	11.2404	11.4653	11.6901	11.9149	12.1397	12.3645	12.5893	12.8141	13.0389	13.2637
60	13.4885	13.7133	13.9382	14.1630	14.3878	14.6126	14.8374	15.0622	15.2870	15.5118
70	15.7366	15.9614	16.1862	16.4110	16.6359	16.8607	17.0855	17.3103	17.5351	17.7599
80	17.9847	18.2095	18.4343	18.6591	18.8839	19.1088	19.3336	19.5584	19.7832	20.0080
90	20.2328	20.4576	20.6824	20.9072	21.1320	21.3568	21.5817	21.8065	22.0313	22.2561
100	22.4809	22.7057	22.9305	23.1553	23.3801	23.6049	23.8297	24.0546	24.2794	24.5042

1 newton = 0.2248089 pound-force

Units of Moment and Torque

Table 42. Bending Moment or Torque Conversion Factors

To Convert → ↓	Multiply By Factor, →	Dyne-centimeter	Kilogram-meter	Newton-millimeter	Newton-meter	Ounce-inch	Pound-foot
Dyne-centimeter		1	**1×10^{-7}**	**0.0001**	**1×10^{-7}**	1.416×10^{-5}	7.375×10^{-8}
Kilogram-meter		9.80665×10^{7}	1	9806.65	9.80665	1388.78818707	7.233271722
Newton-millimeter		**10,000**	0.000101968	1	**0.001**	0.14161193	0.000737562
Newton-meter		**1×10^{7}**	0.101967982	**1000**	1	141.61192894	0.737562121
Ounce-inch		70615.52	0.000720052	7.061552	0.007061552	1	0.005208333
Pound-feet		13,558,180	0.138250025	1355.818	1.355818	192	1

Figures in **bold face** indicate the conversion is exact

Table 43a. Pound-Inches to Newton-Meters Conversion

lb_f-in	N·m	lb_f-in	N·m	lb_f-in	N·m	lb_f-in	N·m	lb_f-in	N·m
100	11.298	10	1.130	1	0.113	0.1	0.011	0.01	0.001
200	22.597	20	2.260	2	0.226	0.2	0.023	0.02	0.002
300	33.895	30	3.390	3	0.339	0.3	0.034	0.03	0.003
400	45.194	40	4.519	4	0.452	0.4	0.045	0.04	0.005
500	56.492	50	5.649	5	0.565	0.5	0.056	0.05	0.006
600	67.791	60	6.779	6	0.678	0.6	0.068	0.06	0.007
700	79.089	70	7.909	7	0.791	0.7	0.079	0.07	0.008
800	90.388	80	9.039	8	0.904	0.8	0.090	0.08	0.009
900	101.686	90	10.169	9	1.017	0.9	0.102	0.09	0.010
1000	112.985	100	11.298	10	1.130	1.0	0.113	0.10	0.011

1 pound-inch = 0.1129848 newton-meter

Copyright 2004, Industrial Press, Inc., New York, NY

Table 43b. Newton-Meters to Pound-Inches Conversion

N·m	lb_f-in	N·m	lb_f-in	N·m	lb_f-in	N·m	lb_f-in	N·m	lb_f-in
100	885.07	10	88.51	1	8.85	0.1	0.89	0.01	0.09
200	1770.15	20	177.01	2	17.70	0.2	1.77	0.02	0.18
300	2655.22	30	265.52	3	26.55	0.3	2.66	0.03	0.27
400	3540.30	40	354.03	4	35.40	0.4	3.54	0.04	0.35
500	4425.37	50	442.54	5	44.25	0.5	4.43	0.05	0.44
600	5310.45	60	531.04	6	53.10	0.6	5.31	0.06	0.53
700	6195.52	40	619.55	7	61.96	0.7	6.20	0.07	0.62
800	7080.60	80	708.06	8	70.81	0.8	7.08	0.08	0.71
900	7965.67	90	796.57	9	79.66	0.9	7.97	0.09	0.80
1000	8850.75	100	885.07	10	88.51	1.0	8.85	0.10	0.89

1 newton meter = 8.850748 pound-inches

Poundal.— The expression "poundal" is sometimes used in connection with calculations in mechanics. Many mechanical handbooks, however, do not define it, because of its limited use. A poundal is a unit of force, and is defined as that force which, acting on a mass of one pound for one second, produces a velocity of one foot per second. A foot-poundal is a unit of energy equal to the energy resulting when a force of one poundal acts through a distance of one foot. In order to reduce foot-poundals to foot-pounds, multiply the number of foot-poundals by 0.03108. Dividing the number of foot-poundals by 32.16 (acceleration due to gravity) will also give foot-pounds.

Units of Energy, Power, and Heat

1 horsepower-hour =
0.746 kilowatt-hour
1,980,000 foot-pounds
2545 Btu (British thermal units)
2.64 pounds of water evaporated at 212°F
17 pounds of water raised from 62° to 212°F

1 kilowatt-hour =
100 watt-hours
1.34 horsepower-hour
2,655,200 foot-pounds
3,600,000 joules
3415 Btu
3.54 pounds of water evaporated at 212°F
22.8 pounds of water raised from 62° to 212°F

Table 43c. Power Conversion Factors

1 horsepower =
746 watts
0.746 kilowatt
33,000 foot-pounds/minute
550 foot-pounds/second
2545 Btu/hour
42.4 Btu/minute
0.71 Btu/second
2.64 pounds of water evaporated per hour at 212°F

1 kilowatt =
1000 watts
1.34 horsepower
2,654,200 foot-pounds/hour
44,200 foot-pounds/minute
737 foot-pounds/second
3415 Btu/hour
57 Btu/minute
0.95 Btu/second
3.54 pounds of water evaporated per hour at 212°F

1 watt =
1 joule/second
0.00134 horsepower
0.001 kilowatt
3.42 Btu/hour
44.22 foot-pounds/minute
0.74 foot-pounds/second
0.0035 pound of water evaporated per hour at 212°F

Table 43d. Heat Conversion Factors

1 Btu (British thermal unit) =
1052 watt-seconds
778 foot-pounds
0.252 kilogram-calorie
0.000292 kilowatt-hour
0.000393, horsepower-hour
0.00104 pound of water evaporated at 212°F

1 kilogram calorie = 3.968 Btu

1 foot-pound =
1.36 joules
0.000000377 kilowatt-hour
0.00129 Btu
0.0000005 horsepower-hour

1 kilogram-meter =
7.233 foot-pounds

1 joule =
1 watt-second
0.00000078 kilowatt-hour
0.00095 Btu
0.74 foot-pound

Copyright 2004, Industrial Press, Inc., New York, NY

Table 44a. British Thermal Units to Foot-Pounds

Btu	Ft·lb	Btu	Ft·lb	Btu	Ft·lb	Btu	Ft·lb	Btu	Ft·lb
100	77,826	10	7,783	1	778	0.1	78	0.01	8
200	155,652	20	15,565	2	1,557	0.2	156	0.02	16
300	233,478	30	23,348	3	2,335	0.3	233	0.03	23
400	311,304	40	31,130	4	3,113	0.4	311	0.04	31
500	389,130	50	38,913	5	3,891	0.5	389	0.05	39
600	466,956	60	46,696	6	4,670	0.6	467	0.06	47
700	544,782	70	54,478	7	5,448	0.7	545	0.07	54
800	622,608	80	62,261	8	6,226	0.8	623	0.08	62
900	700,434	90	70,043	9	7,004	0.9	700	0.09	70
1,000	778,260	100	77,826	10	7,783	1.0	778	0.10	78

1 Btu = 778.26 ft·lb, conversion factor defined by International Steam Table Conference, 1929.

Table 44b. Foot-Pounds to British Thermal Units

Ft·lb	Btu	Ft·lb	Btu	Ft·lb	Btu	Ft·lb	Btu	Ft·lb	Btu
10,000	12.849	1,000	1.285	100	0.128	10	0.013	1	0.001
20,000	25.698	2,000	2.570	200	0.257	20	0.026	2	0.003
30,000	38.548	3,000	3.855	300	0.385	30	0.039	3	0.004
40,000	51.397	4,000	5.140	400	0.514	40	0.051	4	0.005
50,000	64.246	5,000	6.425	500	0.642	50	0.064	5	0.006
60,000	77.095	6,000	7.710	600	0.771	60	0.077	6	0.008
70,000	89.944	7,000	8.994	700	0.899	70	0.090	7	0.009
80,000	102.794	8,000	10.279	800	1.028	80	0.103	8	0.010
90,000	115.643	9,000	11.564	900	1.156	90	0.116	9	0.012
100,000	128.492	10,000	12.849	1,000	1.285	100	0.128	10	0.013

1 ft·lb = 0.00128492 Btu, conversion factor defined by International Steam Table Conference, 1929.

Table 45a. British Thermal Units to Kilojoules

Btu→ ↓	0	100	200	300	400	500	600	700	800	900
	kilojoules									
0	…	105.51	211.01	316.52	422.02	527.53	633.03	738.54	844.04	949.55
1000	1055.06	1160.56	1266.07	1371.57	1477.08	1582.58	1688.09	1793.60	1899.10	2004.61
2000	2110.11	2215.62	2321.12	2426.63	2532.13	2637.64	2743.15	2848.65	2954.16	3059.66
3000	3165.17	3270.67	3376.18	3481.68	3587.19	3692.70	3798.20	3903.71	4009.21	4114.72
4000	4220.22	4325.73	4431.24	4536.74	4642.25	4747.75	4853.26	4958.76	5064.27	5169.77
5000	5275.28	5380.79	5486.29	5591.80	5697.30	5802.81	5908.31	6013.82	6119.32	6224.83
6000	6330.34	6435.84	6541.35	6646.85	6752.36	6857.86	6963.37	7068.88	7174.38	7279.89
7000	7385.39	7490.90	7596.40	7701.91	7807.41	7912.92	8018.43	8123.93	8229.44	8334.94
8000	8440.45	8545.95	8651.46	8756.96	8862.47	8967.98	9073.48	9178.99	9284.49	9390.00
9000	9495.50	9601.01	9706.52	9812.02	9917.53	10023.0	10128.5	10234.0	10339.5	10445.1
10000	10550.6	…	…	…	…	…	…	…	…	…

1 Btu = 1055.056 joules

Table 45b. Kilojoules to British Thermal Units

kJ→ ↓	0	100	200	300	400	500	600	700	800	900
	British Thermal Units									
0	…	94.78	189.56	284.35	379.13	473.91	568.69	663.47	758.25	853.04
1000	947.82	1042.60	1137.38	1232.16	1326.94	1421.73	1516.51	1611.29	1706.07	1800.85
2000	1895.63	1990.42	2085.20	2179.98	2274.76	2369.54	2464.32	2559.11	2653.89	2748.67
3000	2843.45	2938.23	3033.01	3127.80	3222.58	3317.36	3412.14	3506.92	3601.70	3696.49
4000	3791.27	3886.05	3980.83	4075.61	4170.39	4265.18	4359.96	4454.74	4549.52	4644.30
5000	4739.08	4833.87	4928.65	5023.43	5118.21	5212.99	5307.78	5402.56	5497.34	5592.12
6000	5686.90	5781.68	5876.47	5971.25	6066.03	6160.81	6255.59	6350.37	6445.16	6539.94
7000	6634.72	6729.50	6824.28	6919.06	7013.85	7108.63	7203.41	7298.19	7392.97	7487.75
8000	7582.54	7677.32	7772.10	7866.88	7961.66	8056.44	8151.23	8246.01	8340.79	8435.57
9000	8530.35	8625.13	8719.92	8814.70	8909.48	9004.26	9099.04	9193.82	9288.61	9383.39
10000	9478.17	…	…	…	…	…	…	…	…	…

1 joule = 0.0009478170 Btu

Copyright 2004, Industrial Press, Inc., New York, NY

Table 46a. Horsepower to Kilowatts Conversion

hp	kW	hp	kW	hp	kW	hp	kW	hp	kW
1,000	745.7	100	74.6	10	7.5	1	0.7	0.1	0.07
2,000	1,491.4	200	149.1	20	14.9	2	1.5	0.2	0.15
3,000	2,237.1	300	223.7	30	22.4	3	2.2	0.3	0.22
4,000	2,982.8	400	298.3	40	29.8	4	3.0	0.4	0.30
5,000	3,728.5	500	372.8	50	37.3	5	3.7	0.5	0.37
6,000	4,474.2	600	447.4	60	44.7	6	4.5	0.6	0.45
7,000	5,219.9	700	522.0	70	52.2	7	5.2	0.7	0.52
8,000	5,965.6	800	596.6	80	59.7	8	6.0	0.8	0.60
9,000	6,711.3	900	671.1	90	67.1	9	6.7	0.9	0.67
10,000	7,457.0	1,000	745.7	100	74.6	10	7.5	1.0	0.75

1 hp = 0.7456999 kW, based on 1 horsepower = 550 foot-pounds per second.

Table 46b. Kilowatts to Horsepower Conversion

kW	hp	kW	hp	kW	hp	kW	hp	kW	hp
1,000	1,341.0	100	134.1	10	13.4	1	1.3	0.1	0.13
2,000	2,682.0	200	268.2	20	26.8	2	2.7	0.2	0.27
3,000	4,023.1	300	402.3	30	40.2	3	4.0	0.3	0.40
4,000	5,364.1	400	536.4	40	53.6	4	5.4	0.4	0.54
5,000	6,705.1	500	670.5	50	67.1	5	6.7	0.5	0.67
7,000	9,387.2	700	938.7	70	93.9	7	9.4	0.7	0.94
8,000	10,728.2	800	1,072.8	80	107.3	8	10.7	0.8	1.07
9,000	12,069.2	900	1,206.9	90	120.7	9	12.1	0.9	1.21
10,000	13,410.2	1,000	1,341.0	100	134.1	10	13.4	1.0	1.34

1 kW = 1.341022 hp, based on 1 horsepower = 550 foot-pounds per second.

Table 47a. Foot-Pounds to Joules Conversion

ft·lb→ ↓	0	1	2	3	4	5	6	7	8	9
	joules									
0	…	1.356	2.712	4.067	5.423	6.779	8.135	9.491	10.847	12.202
10	13.558	14.914	16.270	17.626	18.981	20.337	21.693	23.049	24.405	25.761
20	27.116	28.472	29.828	31.184	32.540	33.895	35.251	36.607	37.963	39.319
30	40.675	42.030	43.386	44.742	46.098	47.454	48.809	50.165	51.521	52.877
40	54.233	55.589	56.944	58.300	59.656	61.012	62.368	63.723	65.079	66.435
50	67.791	69.147	70.503	71.858	73.214	74.570	75.926	77.282	78.637	79.993
60	81.349	82.705	84.061	85.417	86.772	88.128	89.484	90.840	92.196	93.551
70	94.907	96.263	97.619	98.975	100.331	101.686	103.042	104.398	105.754	107.110
80	108.465	109.821	111.177	112.533	113.889	115.245	116.600	117.956	119.312	120.668
90	122.024	123.379	124.735	126.091	127.447	128.803	130.159	131.514	132.870	134.226
100	135.582	136.938	138.293	139.649	141.005	142.361	143.717	145.073	146.428	147.784

1 foot-pound = 1.355818 joules

Table 47b. Joules to Foot-Pounds Conversion

J→ ↓	0	1	2	3	4	5	6	7	8	9
	foot-pounds									
0	…	0.7376	1.4751	2.2127	2.9502	3.6878	4.4254	5.1629	5.9005	6.6381
10	7.3756	8.1132	8.8507	9.5883	10.3259	11.0634	11.8010	12.5386	13.2761	14.0137
20	14.7512	15.4888	16.2264	16.9639	17.7015	18.4391	19.1766	19.4142	20.6517	21.3893
30	22.1269	22.8644	23.6020	24.3395	25.0771	25.8147	26.5522	27.2898	28.0274	28.7649
40	29.5025	30.2400	30.9776	31.7152	32.4527	33.1903	33.9279	34.6654	35.4030	36.1405
50	36.8781	37.6157	38.3532	39.0908	39.8284	40.5659	41.3035	42.0410	42.7786	43.5162
60	44.2537	44.9913	45.7289	46.4664	47.2040	47.9415	48.6791	49.4167	50.1542	50.8918
70	51.6293	52.3669	53.1045	53.8420	54.5796	55.3172	56.0547	56.7923	57.5298	58.2674
80	59.0050	59.7425	60.4801	61.2177	61.9552	62.6928	63.4303	64.1679	64.9055	65.6430
90	66.3806	67.1182	67.8557	68.5933	69.3308	70.0684	70.8060	71.5435	72.2811	73.0186
100	73.7562	74.4938	75.2313	75.9689	76.7065	77.4440	78.1816	78.9191	79.6567	80.3943

1 joule = 0.7375621 foot-pound

Copyright 2004, Industrial Press, Inc., New York, NY

Table 48. Power Conversion Factors

To Convert ↓ / Multiply By This Factor, To Obtain →	Horsepower	Watts	Kilowatts	HP (metric)	Kg_f·m/s	Ft·Lb_f/s	Ft·Lb_f/min	Calories/sec	Btu/sec	Btu/hr
Horsepower	1	745.699	0.745699	1.0138681	76.04	**550**	**33000**	178.1	0.7068	2544.48
Watts	0.00134024	1	**0.001**	0.0013596	0.1019714	0.7375630	44.253727	0.2388363	0.0009478	3.4122
Kilowatts	1.34102365	**1000**	1	1.3596196	101.9713158	737.563011	44253.727270	238.836025	0.9478344	3412.20
HP (metric)	0.9863215	735.499	0.735499	1	**75**	542.476857	32548.61114	175.663869	0.6971321	2509.6754
Kg_f-m/s	0.01315097	9.8066	0.0098067	0.0133334	1	7.2330352	433.982114	2.3421883	0.0092951	33.4623
Ft·lb_f/s	0.00181818	1.35581	0.0013558	0.0018434	0.1382545	1	**60**	0.3238181	0.0012851	4.6263
Ft·lb_f/min	3.0303×10^{-5}	0.02259	2.2596×10^{-5}	3.07233×10^{-5}	0.0023042	0.0166667	1	0.0053969	2.1418×10^{-5}	0.077105
Calories/sec	0.00561482	4.18696	0.0041869	0.0056927	0.4269512	3.0881527	185.288916	1	0.0039686	14.2868
Btu/sec	1.41482739	1055.035	1.0550353	1.4344484	107.5834748	778.155065	46689.3039	**252**	1	**3600**
Btu/hr	0.0003930	0.29306	0.0002931	0.0003985	0.0298843	0.2161542	12.969251	0.069994	0.0002778	1

Figures in **bold face** indicate the conversion is exact

Table 49. Energy and Work Conversion Factors

To Convert ↓ / Multiply By This Factor, To Obtain →	Joules	Ft·lb_f	Ft-Poundal	Btu	Kg-m	Calories	Watt-hour	Erg	Therm	HP-hours	HP-hours (m)
Joules	1	0.73756	23.7303	0.0009478	0.101972	0.2388458	0.00027778	$\mathbf{1 \times 10^{7}}$	9.478×10^{-9}	3.725×10^{-7}	3.7764×10^{-7}
Ft·lb_f	1.355818	1	32.1740	0.00128506	0.138255	0.3238316	0.00037661	1.356×10^{7}	1.285×10^{-8}	5.0505×10^{-7}	5.1201×10^{-7}
Ft-Poundal	0.04214	0.03108	1	3.994×10^{-5}	0.0042971	0.010065	1.1705×10^{-5}	4.214×10^{5}	3.994×10^{-10}	1.5697×10^{-8}	1.5914×10^{-8}
Btu	1055.055	778.1692	25036.8174	1	107.5875	252	0.29307071	1.055×10^{10}	1×10^{-5}	0.0003930	0.0003984
Kg-m	9.80665	7.233013	232.714987	0.00929524	1	2.342278	0.00272416	9.807×10^{7}	9.294×10^{-8}	3.653×10^{-6}	3.703×10^{-6}
Calories	4.1868	3.088025	99.35427	0.00396832	0.42691934	1	0.001163	4.187×10^{7}	3.968×10^{-8}	1.5596×10^{-6}	1.5811×10^{-6}
Watt-Hour	**3600**	2655.2237	85429.168	3.4121416	367.09783	859.845227	1	3.6×10^{10}	3.412×10^{-5}	0.001341	0.0013595
Erg	$\mathbf{1 \times 10^{-7}}$	7.375×10^{-8}	2.373×10^{-6}	9.478×10^{-11}	1.0197×10^{-8}	2.3884×10^{-8}	2.778×10^{-11}	1	9.478×10^{-16}	3.725×10^{-14}	3.776×10^{-14}
Therm	1.055×10^{8}	7.781×10^{7}	2.503×10^{7}	$\mathbf{1 \times 10^{5}}$	1.0758×10^{7}	2.5196×10^{7}	29307.222	1.055×10^{15}	1	39.3020	39.843655
HP-hours	2.6845×10^{6}	1.9799×10^{6}	6.3704×10^{7}	2544.4150	2.7374×10^{5}	6.4118×10^{5}	745.6944	2.685×10^{13}	0.025444	1	1.0137839
HP-hours (m)	2.648×10^{6}	1.953×10^{6}	6.2837×10^{7}	2509.8197	2.70×10^{5}	6.3246×10^{5}	735.555	2.648×10^{13}	0.025098	0.9864034	1

Figures in **bold face** indicate the conversion is exact

Copyright 2004, Industrial Press, Inc., New York, NY

Table 50. Thermal Conductance Conversion Factors

To Convert ↓	Multiply By This Factor, To Obtain →	Btu·ft/(h·ft²·°F)	Btu·in/(h·ft²·°F)	Btu·in/(sec·ft²·°F)	Cal/(cm·s·°C)	Kcal/(cm·s·°C)	Kcal/(m·h·°C)	Erg/(cm·s·°C)	Joules/(m·h·°C)	Watt/(ft·°C)	Watt/(m·°K)
Btu·ft/(h·ft²·°F)		1	**12**	0.00333333	0.00413385	4.13386×10^{-6}	1.488188976	173076.378	6230.0055	0.5274738	1.73056
Btu·in/(h·ft²·°F)		0.083333	1	0.000277778	0.00034448	3.44448×10^{-7}	0.124015748	14423.0315	519.25573	0.04395615	0.14421
Btu·in/(sec·ft²·°F)		**300**	**3600**	1	1.24001574	0.001240157	446.4566929	5.1925×10^{7}	1.8693×10^{6}	158.24214	519.167
Cal/(cm·s·°C)		241.9047	2902.8571	0.806349	1	**0.001**	**360**	4.1868×10^{7}	1.507×10^{6}	127.598424	418.63
Kcal/(cm·s·°C)		2.419×10^{5}	2.902×10^{6}	806.3492	**1000**	1	**360000**	4.1868×10^{10}	1.507×10^{9}	1.276×10^{5}	4.1863×10^{5}
Kcal/(m·h·°C)		0.671957	8.063349	0.00223985	0.00277778	2.77778×10^{-6}	1	116300	4186.8	0.35444	1.16286
Erg/(cm· s·°C)		5.7778×10^{-6}	6.933×10^{-5}	1.92593×10^{-8}	2.3884×10^{-8}	2.3884×10^{-11}	8.5984×10^{-6}	1	0.036	3.0476×10^{-6}	1×10^{-5}
Joules/(m·h·°C)		1.6051×10^{-4}	0.00192616	5.35045×10^{-7}	6.6354×10^{-7}	6.6354×10^{-10}	0.000238874	27.781095	1	8.4666×10^{-5}	2.7777×10^{-4}
Watt/(ft·°C)		1.895828	22.75	0.006319429	0.00783708	7.83709×10^{-6}	2.821351461	328123.1749	11811.024	1	3.28
Watt/(m·°K)		0.5778486	6.934183	0.001926162	0.002388744	2.38874×10^{-6}	0.859947925	$\mathbf{1 \times 10^{5}}$	**3600**	0.304878	1

Figures in **bold face** indicate the conversion is exact

Conduction.— Whenever the molecules of a working substance, whether liquid, solid, or vapor, are restrained so that no appreciable relative translatory motion occurs among them, the kinetic energies of the various molecules will be largely due to vibration. If a temperature difference exists in the working substance, some adjacent molecules will necessarily be at different temperatures hence will possess different degrees of vibratory motion. In this case the molecule which is vibrating most rapidly will transfer some of its motion to the slower-moving molecule next to it, the one then undergoing a decrease in temperature and the other an increase. In this way, thermal energy will be transferred by the mechanism of conduction from the region of higher to the region of lower temperature. The process will continue spontaneously until the entire system has reached a uniform equilibrium temperature.

In contrast to radiation, conduction only occurs when a working substance is present and when the molecules of that working substance retain practically fixed positions with respect to one another. Thus, conductive heat flow would always occur through solids, but would take place in liquids and vapors only if special conditions prevented or greatly reduced the normal translatory motion of the molecules within these materials.

Fuel Oil, Coal and Gas Equivalents.— One gallon of fuel oil equals 13.1 pounds of coal, equals 160 cubic feet of natural gas. One barrel of fuel oil equals 0.278 ton of coal, equals 680.6 cubic feet of natural gas. One pound of fuel oil equals 1.75 pounds of coal, equals 21.3 cubic feet of natural gas. One pound of coal equals 0.763 gallon of oil, equals 12.2 cubic feet of natural gas. One ton of coal equals 3.6 barrels of oil, equals 24,500 cubic feet of natural gas. The heating value of the average mid-continent fuel oil having a Baume gravity of 26.9 is 19,376 British thermal units per pound of oil, and 143,950 British thermal units per gallon of oil. The specific gravity and the heat value may be expressed approximately by means of a simple formula, as follows: BTU per pound = 18,650 + 40 × (Degrees Baume – 10).

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Temperature

Thermometer Scales.— There are two thermometer scales in general use: the Fahrenheit (F), which is used in the United States and in other countries still using the English system of units, and the Celsius (C) or Centigrade used throughout the rest of the world.

In the Fahrenheit thermometer, the freezing point of water is marked at 32 degrees on the scale and the boiling point, at atmospheric pressure, at 212 degrees. The distance between these two points is divided into 180 degrees. On the Celsius scale, the freezing point of water is at 0 degrees and the boiling point at 100 degrees. The following formulas may be used for converting temperatures given on any one of the scales to the other scale:

$$\text{Degrees Fahrenheit} = \frac{9 \times \text{degrees C}}{5} + 32$$

$$\text{Degrees Celsius} = \frac{5 \times (\text{degrees F} - 32)}{9}$$

Tables on the pages that follow can be used to convert degrees Celsius into degrees Fahrenheit or vice versa. In the event that the conversions are not covered in the tables, use those applicable portions of the formulas given above for converting.

Table 51. Temperature Conversion Fomulas

To Convert	To	Use Formula	To Convert	To	Use Formula
Celsius, t_C	°K, t_K	$t_K = t_C + 273.15$	Kelvin, t_K	°C, t_C	$t_C = t_K - 273.15$
	°F, t_F	$t_F = 1.8\ t_C + 32$		°F, t_F	$t_F = 1.8\ t_K - 459.67$
	°R, t_R	$t_R = 9(t_C + 273.15)/5$		°R, t_R	$t_R = 9/5 \times t_K$
Fahrenheit, t_F	°K, t_K	$t_K = (t_F + 459.67)/1.8$	Rankine, t_R	°K, t_K	$t_K = 5/9 \times t_R$
	°C, t_C	$t_C = (t_F - 32)/1.8$		°C, t_C	$t_C = 5/9 \times t_R - 273.15$
	°R, t_R	$t_K = t_F - 459.67$		°F, t_F	$t_F = t_R - 459.67$

Absolute Temperature and Absolute Zero.— A point has been determined on the thermometer scale, by theoretical considerations, that is called the absolute zero and beyond which a further decrease in temperature is inconceivable. This point is located at –273.15 degrees Celsius or –459.67 degrees F. A temperature reckoned from this point, instead of from the zero on the ordinary thermometers, is called absolute temperature. Absolute temperature in degrees C is known as "degrees Kelvin" or the "Kelvin scale" (K) and absolute temperature in degrees F is known as "degrees Rankine" or the "Rankine scale" (R).

$$\text{Degrees Kelvin} = \text{degrees C} + 273.15$$

$$\text{Degrees Rankine} = \text{degrees F} + 459.67$$

Measures of the Quantity of Thermal Energy.— The unit of quantity of thermal energy used in the United States is the British thermal unit, which is the quantity of heat or thermal energy required to raise the temperature of one pound of pure water one degree F. (American National Standard abbreviation, Btu; conventional British symbol, B.Th.U.) The French thermal unit, or *kilogram calorie*, is the quantity of heat or thermal energy required to raise the temperature of one kilogram of pure water one degree C. One kilogram calorie = 3.968 British thermal units = 1000 gram calories. The number of foot-pounds of mechanical energy equivalent to one British thermal unit is called the *mechanical equivalent of heat*, and equals 778 foot-pounds.

In the modern metric or SI system of units, the unit for thermal energy is the *joule* (J); a commonly used multiple being the kilojoule (kJ), or 1000 joules. See page 2544 for an explanation of the SI System. One kilojoule = 0.9478 Btu. Also in the SI System, the *watt* (W), equal to joule per second (J/s), is used for power, where one watt = 3.412 Btu per hour.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 52. °C → °F and °R Temperature Conversion °F → °C and °K

°K	°C		°F	°R	°K	°C		°F	°R	°K	°C		°F	°R
0.0	−273.2	**−459.7**	…	…	261.5	−11.7	**11**	51.8	511.5	293.7	20.6	**69**	156.2	615.9
5.4	−267.8	**−450**	…	…	262.0	−11.1	**12**	53.6	513.3	294.3	21.1	**70**	158.0	617.7
10.9	−262.2	**−440**	…	…	262.6	−10.6	**13**	55.4	515.1	294.8	21.7	**71**	159.8	619.5
16.5	−256.7	**−430**	…	…	263.2	−10.0	**14**	57.2	516.9	295.4	22.2	**72**	161.6	621.3
22.0	−251.1	**−420**	…	…	263.7	−9.4	**15**	59.0	518.7	295.9	22.8	**73**	163.4	623.1
27.6	−245.6	**−410**	…	…	264.3	−8.9	**16**	60.8	520.5	296.5	23.3	**74**	165.2	624.9
33.2	−240.0	**−400**	…	…	264.8	−8.3	**17**	62.6	522.3	297.0	23.9	**75**	167.0	626.7
38.7	−234.4	**−390**	…	…	265.4	−7.8	**18**	64.4	524.1	297.6	24.4	**76**	168.8	628.5
44.3	−228.9	**−380**	…	…	265.9	−7.2	**19**	66.2	525.9	298.2	25.0	**77**	170.6	630.3
49.8	−223.3	**−370**	…	…	266.5	−6.7	**20**	68.0	527.7	298.7	25.6	**78**	172.4	632.1
55.4	−217.8	**−360**	…	…	267.0	−6.1	**21**	69.8	529.5	299.3	26.1	**79**	174.2	633.9
60.9	−212.2	**−350**	…	…	267.6	−5.6	**22**	71.6	531.3	299.8	26.7	**80**	176.0	635.7
66.5	−206.7	**−340**	…	…	268.2	−5.0	**23**	73.4	533.1	300.4	27.2	**81**	177.8	637.5
72.0	−201.1	**−330**	…	…	268.7	−4.4	**24**	75.2	534.9	300.9	27.8	**82**	179.6	639.3
77.6	−195.6	**−320**	…	…	269.3	−3.9	**25**	77.0	536.7	301.5	28.3	**83**	181.4	641.1
83.2	−190.0	**−310**	…	…	269.8	−3.3	**26**	78.8	538.5	302.0	28.9	**84**	183.2	642.9
88.7	−184.4	**−300**	…	…	270.4	−2.8	**27**	80.6	540.3	302.6	29.4	**85**	185.0	644.7
94.3	−178.9	**−290**	…	…	270.9	−2.2	**28**	82.4	542.1	303.2	30.0	**86**	186.8	646.5
99.8	−173.3	**−280**	…	…	271.5	−1.7	**29**	84.2	543.9	303.7	30.6	**87**	188.6	648.3
103.6	−169.5	**−273.2**	−459.7	0.0	272.0	−1.1	**30**	86.0	545.7	304.3	31.1	**88**	190.4	650.1
105.4	−167.8	**−270**	−454.0	5.7	272.6	−0.6	**31**	87.8	547.5	304.8	31.7	**89**	192.2	651.9
110.9	−162.2	**−260**	−436.0	23.7	273.2	0.0	**32**	89.6	549.3	305.4	32.2	**90**	194.0	653.7
116.5	−156.7	**−250**	−418.0	41.7	273.7	0.6	**33**	91.4	551.1	305.9	32.8	**91**	195.8	655.5
122.0	−151.1	**−240**	−400.0	59.7	274.3	1.1	**34**	93.2	552.9	306.5	33.3	**92**	197.6	657.3
127.6	−145.6	**−230**	−382.0	77.7	274.8	1.7	**35**	95.0	554.7	307.0	33.9	**93**	199.4	659.1
133.2	−140.0	**−220**	−364.0	95.7	275.4	2.2	**36**	96.8	556.5	307.6	34.4	**94**	201.2	660.9
138.7	−134.4	**−210**	−346.0	113.7	275.9	2.8	**37**	98.6	558.3	308.2	35.0	**95**	203.0	662.7
144.3	−128.9	**−200**	−328.0	131.7	276.5	3.3	**38**	100.4	560.1	308.7	35.6	**96**	204.8	664.5
149.8	−123.3	**−190**	−310.0	149.7	277.0	3.9	**39**	102.2	561.9	309.3	36.1	**97**	206.6	666.3
155.4	−117.8	**−180**	−292.0	167.7	277.6	4.4	**40**	104.0	563.7	309.8	36.7	**98**	208.4	668.1
160.9	−112.2	**−170**	−274.0	185.7	278.2	5.0	**41**	105.8	565.5	310.4	37.2	**99**	210.2	669.9
166.5	−106.7	**−160**	−256.0	203.7	278.7	5.6	**42**	107.6	567.3	310.9	37.8	**100**	212.0	671.7
172.0	−101.1	**−150**	−238.0	221.7	279.3	6.1	**43**	109.4	569.1	311.5	38.3	**101**	213.8	673.5
177.6	−95.6	**−140**	−220.0	239.7	279.8	6.7	**44**	111.2	570.9	312.0	38.9	**102**	215.6	675.3
183.2	−90.0	**−130**	−202.0	257.7	280.4	7.2	**45**	113.0	572.7	312.6	39.4	**103**	217.4	677.1
188.7	−84.4	**−120**	−184.0	275.7	280.9	7.8	**46**	114.8	574.5	313.2	40.0	**104**	219.2	678.9
194.3	−78.9	**−110**	−166.0	293.7	281.5	8.3	**47**	116.6	576.3	313.7	40.6	**105**	221.0	680.7
199.8	−73.3	**−100**	−148.0	311.7	282.0	8.9	**48**	118.4	578.1	314.3	41.1	**106**	222.8	682.5
205.4	−67.8	**−90**	−130.0	329.7	282.6	9.4	**49**	120.2	579.9	314.8	41.7	**107**	224.6	684.3
210.9	−62.2	**−80**	−112.0	347.7	283.2	10.0	**50**	122.0	581.7	315.4	42.2	**108**	226.4	686.1
216.5	−56.7	**−70**	−94.0	365.7	283.7	10.6	**51**	123.8	583.5	315.9	42.8	**109**	228.2	687.9
222.0	−51.1	**−60**	−76.0	383.7	284.3	11.1	**52**	125.6	585.3	316.5	43.3	**110**	230.0	689.7
227.6	−45.6	**−50**	−58.0	401.7	284.8	11.7	**53**	127.4	587.1	317.0	43.9	**111**	231.8	691.5
233.2	−40.0	**−40**	−40.0	419.7	285.4	12.2	**54**	129.2	588.9	317.6	44.4	**112**	233.6	693.3
238.7	−34.4	**−30**	−22.0	437.7	285.9	12.8	**55**	131.0	590.7	318.2	45.0	**113**	235.4	695.1
244.3	−28.9	**−20**	−4.0	455.7	286.5	13.3	**56**	132.8	592.5	318.7	45.6	**114**	237.2	696.9
249.8	−23.3	**−10**	14.0	473.7	287.0	13.9	**57**	134.6	594.3	319.3	46.1	**115**	239.0	698.7
255.4	−17.8	**0**	32.0	491.7	287.6	14.4	**58**	136.4	596.1	319.8	46.7	**116**	240.8	700.5
255.9	−17.2	**1**	33.8	493.5	288.2	15.0	**59**	138.2	597.9	320.4	47.2	**117**	242.6	702.3
256.5	−16.7	**2**	35.6	495.3	288.7	15.6	**60**	140.0	599.7	320.9	47.8	**118**	244.4	704.1
257.0	−16.1	**3**	37.4	497.1	289.3	16.1	**61**	141.8	601.5	321.5	48.3	**119**	246.2	705.9
257.6	−15.6	**4**	39.2	498.9	289.8	16.7	**62**	143.6	603.3	322.0	48.9	**120**	248.0	707.7
258.2	−15.0	**5**	41.0	500.7	290.4	17.2	**63**	145.4	605.1	322.6	49.4	**121**	249.8	709.5
258.7	−14.4	**6**	42.8	502.5	290.9	17.8	**64**	147.2	606.9	323.2	50.0	**122**	251.6	711.3
259.3	−13.9	**7**	44.6	504.3	291.5	18.3	**65**	149.0	608.7	323.7	50.6	**123**	253.4	713.1
259.8	−13.3	**8**	46.4	506.1	292.0	18.9	**66**	150.8	610.5	324.3	51.1	**124**	255.2	714.9
260.4	−12.8	**9**	48.2	507.9	292.6	19.4	**67**	152.6	612.3	324.8	51.7	**125**	257.0	716.7
260.9	−12.2	**10**	50.0	509.7	293.2	20.0	**68**	154.4	614.1	325.4	52.2	**126**	258.8	718.5

Copyright 2004, Industrial Press, Inc., New York, NY

Table 52. ***(Continued)*** **°C → °F and °R Temperature Conversion °F → °C and °K**

°K	°C		°F	°R	°K	°C		°F	°R	°K	°C		°F	°R
325.9	52.8	**127**	260.6	720.3	357.6	84.4	**184**	363.2	822.9	741.5	468.3	**875**	1607.0	2066.7
326.5	53.3	**128**	262.4	722.1	358.2	85.0	**185**	365.0	824.7	755.4	482.2	**900**	1652.0	2111.7
327.0	53.9	**129**	264.2	723.9	358.7	85.6	**186**	366.8	826.5	769.3	496.1	**925**	1697.0	2156.7
327.6	54.4	**130**	266.0	725.7	359.3	86.1	**187**	368.6	828.3	783.2	510.0	**950**	1742.0	2201.7
328.2	55.0	**131**	267.8	727.5	359.8	86.7	**188**	370.4	830.1	797.0	523.9	**975**	1787.0	2246.7
328.7	55.6	**132**	269.6	729.3	360.4	87.2	**189**	372.2	831.9	810.9	537.8	**1000**	1832.0	2291.7
329.3	56.1	**133**	271.4	731.1	360.9	87.8	**190**	374.0	833.7	838.7	565.6	**1050**	1922.0	2381.7
329.8	56.7	**134**	273.2	732.9	361.5	88.3	**191**	375.8	835.5	866.5	593.3	**1100**	2012.0	2471.7
330.4	57.2	**135**	275.0	734.7	362.0	88.9	**192**	377.6	837.3	894.3	621.1	**1150**	2102.0	2561.7
330.9	57.8	**136**	276.8	736.5	362.6	89.4	**193**	379.4	839.1	922.0	648.9	**1200**	2192.0	2651.7
331.5	58.3	**137**	278.6	738.3	363.2	90.0	**194**	381.2	840.9	949.8	676.7	**1250**	2282.0	2741.7
332.0	58.9	**138**	280.4	740.1	363.7	90.6	**195**	383.0	842.7	977.6	704.4	**1300**	2372.0	2831.7
332.6	59.4	**139**	282.2	741.9	364.3	91.1	**196**	384.8	844.5	1005.4	732.2	**1350**	2462.0	2921.7
333.2	60.0	**140**	284.0	743.7	364.8	91.7	**197**	386.6	846.3	1033.2	760.0	**1400**	2552.0	3011.7
333.7	60.6	**141**	285.8	745.5	365.4	92.2	**198**	388.4	848.1	1060.9	787.8	**1450**	2642.0	3101.7
334.3	61.1	**142**	287.6	747.3	365.9	92.8	**199**	390.2	849.9	1088.7	815.6	**1500**	2732.0	3191.7
334.8	61.7	**143**	289.4	749.1	366.5	93.3	**200**	392.0	851.7	1116.5	843.3	**1550**	2822.0	3281.7
335.4	62.2	**144**	291.2	750.9	367.0	93.9	**201**	393.8	853.5	1144.3	871.1	**1600**	2912.0	3371.7
335.9	62.8	**145**	293.0	752.7	367.6	94.4	**202**	395.6	855.3	1172.0	898.9	**1650**	3002.0	3461.7
336.5	63.3	**146**	294.8	754.5	368.2	95.0	**203**	397.4	857.1	1199.8	926.7	**1700**	3092.0	3551.7
337.0	63.9	**147**	296.6	756.3	368.7	95.6	**204**	399.2	858.9	1227.6	954.4	**1750**	3182.0	3641.7
337.6	64.4	**148**	298.4	758.1	369.3	96.1	**205**	401.0	860.7	1255.4	982.2	**1800**	3272.0	3731.7
338.2	65.0	**149**	300.2	759.9	369.8	96.7	**206**	402.8	862.5	1283.2	1010.0	**1850**	3362.0	3821.7
338.7	65.6	**150**	302.0	761.7	370.4	97.2	**207**	404.6	864.3	1310.9	1037.8	**1900**	3452.0	3911.7
339.3	66.1	**151**	303.8	763.5	370.9	97.8	**208**	406.4	866.1	1338.7	1065.6	**1950**	3542.0	4001.7
339.8	66.7	**152**	305.6	765.3	371.5	98.3	**209**	408.2	867.9	1366.5	1093.3	**2000**	3632.0	4091.7
340.4	67.2	**153**	307.4	767.1	372.0	98.9	**210**	410.0	869.7	1394.3	1121.1	**2050**	3722.0	4181.7
340.9	67.8	**154**	309.2	768.9	372.6	99.4	**211**	411.8	871.5	1422.0	1148.9	**2100**	3812.0	4271.7
341.5	68.3	**155**	311.0	770.7	373.2	100.0	**212**	413.6	873.3	1449.8	1176.7	**2150**	3902.0	4361.7
342.0	68.9	**156**	312.8	772.5	377.6	104.4	**220**	428.0	887.7	1477.6	1204.4	**2200**	3992.0	4451.7
342.6	69.4	**157**	314.6	774.3	383.2	110.0	**230**	446.0	905.7	1505.4	1232.2	**2250**	4082.0	4541.7
343.2	70.0	**158**	316.4	776.1	388.7	115.6	**240**	464.0	923.7	1533.2	1260.0	**2300**	4172.0	4631.7
343.7	70.6	**159**	318.2	777.9	394.3	121.1	**250**	482.0	941.7	1560.9	1287.8	**2350**	4262.0	4721.7
344.3	71.1	**160**	320.0	779.7	408.2	135.0	**275**	527.0	986.7	1588.7	1315.6	**2400**	4352.0	4811.7
344.8	71.7	**161**	321.8	781.5	422.0	148.9	**300**	572.0	1031.7	1616.5	1343.3	**2450**	4442.0	4901.7
345.4	72.2	**162**	323.6	783.3	435.9	162.8	**325**	617.0	1076.7	1644.3	1371.1	**2500**	4532.0	4991.7
345.9	72.8	**163**	325.4	785.1	449.8	176.7	**350**	662.0	1121.7	1672.0	1398.9	**2550**	4622.0	5081.7
346.5	73.3	**164**	327.2	786.9	463.7	190.6	**375**	707.0	1166.7	1699.8	1426.7	**2600**	4712.0	5171.7
347.0	73.9	**165**	329.0	788.7	477.6	204.4	**400**	752.0	1211.7	1727.6	1454.4	**2650**	4802.0	5261.7
347.6	74.4	**166**	330.8	790.5	491.5	218.3	**425**	797.0	1256.7	1755.4	1482.2	**2700**	4892.0	5351.7
348.2	75.0	**167**	332.6	792.3	505.4	232.2	**450**	842.0	1301.7	1783.2	1510.0	**2750**	4982.0	5441.7
348.7	75.6	**168**	334.4	794.1	519.3	246.1	**475**	887.0	1346.7	1810.9	1537.8	**2800**	5072.0	5531.7
349.3	76.1	**169**	336.2	795.9	533.2	260.0	**500**	932.0	1391.7	1838.7	1565.6	**2850**	5162.0	5621.7
349.8	76.7	**170**	338.0	797.7	547.0	273.9	**525**	977.0	1436.7	1866.5	1593.3	**2900**	5252.0	5711.7
350.4	77.2	**171**	339.8	799.5	560.9	287.8	**550**	1022.0	1481.7	1894.3	1621.1	**2950**	5342.0	5801.7
350.9	77.8	**172**	341.6	801.3	574.8	301.7	**575**	1067.0	1526.7	1922.0	1648.9	**3000**	5432.0	5891.7
351.5	78.3	**173**	343.4	803.1	588.7	315.6	**600**	1112.0	1571.7	2033.2	1760.0	**3200**	5792.0	6251.7
352.0	78.9	**174**	345.2	804.9	602.6	329.4	**625**	1157.0	1616.7	2144.3	1871.1	**3400**	6152.0	6611.7
352.6	79.4	**175**	347.0	806.7	616.5	343.3	**650**	1202.0	1661.7	2255.4	1982.2	**3600**	6512.0	6971.7
353.2	80.0	**176**	348.8	808.5	630.4	357.2	**675**	1247.0	1706.7	2366.5	2093.3	**3800**	6872.0	7331.7
353.7	80.6	**177**	350.6	810.3	644.3	371.1	**700**	1292.0	1751.7	2477.6	2204.4	**4000**	7232.0	7691.7
354.3	81.1	**178**	352.4	812.1	658.2	385.0	**725**	1337.0	1796.7	2588.7	2315.6	**4200**	7592.0	8051.7
354.8	81.7	**179**	354.2	813.9	672.0	398.9	**750**	1382.0	1841.7	2699.8	2426.7	**4400**	7952.0	8411.7
355.4	82.2	**180**	356.0	815.7	685.9	412.8	**775**	1427.0	1886.7	2810.9	2537.8	**4600**	8312.0	8771.7
355.9	82.8	**181**	357.8	817.5	699.8	426.7	**800**	1472.0	1931.7	2922.0	2648.9	**4800**	8672.0	9131.7
356.5	83.3	**182**	359.6	819.3	713.7	440.6	**825**	1517.0	1976.7	3033.2	2760.0	**5000**	9032.0	9491.7
357.0	83.9	**183**	361.4	821.1	727.6	454.4	**850**	1562.0	2021.7	…	…	…	…	…

Table converts °C → °F and °R, or °F → °C and °K. Find "convert from" temperature in **bold** column and read result from °F and °R or °C and °K columns. *Example 1:* 183 °C = 361.4 °F and 821.1 °R. *Example 2:* 183 °F = 83.9 °C and 357.0 °K.

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Velocity and Acceleration

Table 53. Velocity Conversion Factors

To Convert ↓ / Multiply By Factor, To Obtain →	cm/sec	m/sec	km/hr	ft/sec	ft/min	ft/hr	knot[a]	mile/hr
cm/sec	1	**0.01**	**0.036**	0.032808	1.9685	118.110236	0.01944	0.02237
m/sec	**100**	1	**3.6**	3.2808	196.8504	11811.0236	1.94384	2.236936
km/hr	27.77778	0.27778	1	0.911344	54.6806	3280.8399	0.53995	0.621371
ft/sec	30.48	0.3048	1.09728	1	**60**	**3600**	0.59248	0.681818
ft/min	0.5080	0.00508	0.018288	0.016667	1	**60**	9.8×10^{-3}	0.011364
ft/hr	0.008467	8.47×10^{-5}	3.05×10^{-4}	2.78×10^{-4}	0.01666	1	1.6×10^{-4}	1.89×10^{-4}
knot	51.444	0.51444	1.852	1.687808	101.2686	6076.11549	1	1.15167
mile/hr	44.704	0.447040	1.609344	1.466667	**88**	**5280**	0.8689	1

[a] Knot means nautical miles per hour

Figures in **bold face** indicate the conversion is exact

Table 54. Acceleration Conversion Factors

To Convert ↓ / Multiply By Factor, To Obtain →	cm/sec^2	m/sec^2	km/hr^2	feet/sec^2	ft/hr^2	Knot/sec	miles/hr^2
cm/sec^2	1	**0.01**	129.6	0.0328	4.252×10^5	0.0194384	80.529
m/sec^2	**100**	1	12960	3.280	4.252×10^7	1.943844	8052.970
km/hr^2	0.007716	7.72×10^{-5}	1	2.532×10^{-4}	3280.84	0.0001499	0.6213
ft/sec^2	30.48	0.3048	3950.20	1	1.296×10^7	0.592483	2454.545
ft/hr^2	2.35×10^{-6}	2.35×10^{-5}	3.048×10^{-4}	7.716×10^{-8}	1	4.571×10^{-8}	1.893×10^{-4}
Knot/sec	51.44444	0.514444	6667.2	1.687809	2.187×10^7	1	4142.8060
mile/hr^2	0.0124	0.000124	1.609	4.074×10^{-4}	**5280**	0.00024138	1

Figures in **bold face** indicate the conversion is exact.

Units of Viscosity

Table 55a. Oil Viscosity Conversion Factors

To Convert ↓ / Multiply By This Factor, To Obtain →	Poise (*P*)	Centi-poise (*Z*)	Reyn (μ)	Stoke (*S*)	Centistoke (*v*)
Poise (*P*) $\frac{\text{dyne-s}}{\text{cm}^2} = \frac{\text{gram mass}}{\text{cm-s}}$	1	100	1.45×10^{-5}	$\frac{1}{\rho}$	$\frac{100}{\rho}$
Centipoise (*Z*) $\frac{\text{dyne-s}}{100\ \text{cm}^2} = \frac{\text{gram mass}}{100\ \text{cm-s}}$	0.01	1	1.45×10^{-7}	$\frac{0.01}{\rho}$	$\frac{1}{\rho}$
Reyn (μ) $\frac{\text{lb force-s}}{\text{in}^2}$	6.9×10^4	6.9×10^6	1	$\frac{6.9 \times 10^4}{\rho}$	$\frac{6.9 \times 10^6}{\rho}$
Stoke (*S*) $\frac{\text{cm}^2}{\text{s}}$	ρ	$100\ \rho$	$1.45 \times 10^{-5}\ \rho$	1	100
Centistoke (*v*) $\frac{\text{cm}^2}{100\ \text{s}}$	$0.01\ \rho$	ρ	$1.45 \times 10^{-7}\ \rho$	0.01	1

Table 55b. Additional Viscosity Conversion Factors

Multiply	By	To Obtain	Multiply	By	To Obtain
centipoise	**0.001**	pascal-second (Pa · s)	pascal-second	**1000**	centipoise
centistoke	**0.000001**	meter^2/second (m^2/s)	pascal-second	**10**	poise
stoke	**0.0001**	meter^2/second (m^2/s)	poise	**0.1**	pascal-second (Pa·s)

ρ = Specific gravity of the oil.

Figures in **bold face** indicate the conversion is exact

Copyright 2004, Industrial Press, Inc., New York, NY

Units of Moment of Inertia and Momentum

Table 56. Moment of Inertia Conversion Factors

Multiply	By	To Obtain
Moment of Inertia and Section Modulus		
moment of inertia [kg · m^2]	23.73036	pound-foot^2
moment of inertia [kg · m^2]	3417.171	pound-inch^2
moment of inertia [lb · ft^2]	0.04214011	kilogram-meter^2 (kg · m^2)
moment of inertia [lb · inch^2]	0.0002926397	kilogram-meter^2 (kg · m^2)
moment of section [foot^4]	0.008630975	meter^4 (m^4)
moment of section [inch^4]	41.62314	centimeter^4
moment of section [meter^4]	115.8618	foot^4
moment of section [centimeter^4]	0.02402510	inch^4
section modulus [foot^3]	0.02831685	meter^3 (m^3)
section modulus [inch^3]	0.00001638706	meter^3 (m^3)
section modulus [meter^3]	35.31466	foot^3
section modulus [meter^3]	61,023.76	inch^3

Table 57. Momentum Conversion Factors

Multiply	By	To Obtain
Momentum		
kilogram-meter/second	7.233011	pound-foot/second
kilogram-meter/second	86.79614	pound-inch/second
pound-foot/second	0.1382550	kilogram-meter/second (kg · m/s)
pound-inch/second	0.01152125	kilogram-meter/second (kg · m/s)

Miscellaneous Measuring Units

1 great gross = 12 gross = 144 dozen
1 gross = 12 dozen = 144 units
1 dozen = 12 units

1 quire = 24 sheets
1 ream = 20 quires = 480 sheets
1 ream printing paper = 500 sheets
1 score = 20 units

Ohm's Law.— The following figure represents basic electrical relationships. This chart has been formatted in such a way that each variable has been related to the other three variables. This figure is simply for reference.



Circular Model of Electrical Relations

Key to variables:
V = Voltage (Volts)
R = Resistance (Ohms)
I = Current (Amps)
W = Power (Watts)

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX

Additional Indexes	**Page**
•Index of Standards	**2677**
•Index of Interactive Equations	**2689**
•Index of Materials	**2694**

A

Abbreviations
accuracy 1250
mathematical signs and 2542
scientific and engineering terms 2540–2543
symbols for mechanics 2543
welding 1435
Abrasive
belt
applications 1230
cutting off difficulties 1233
grinding 1230–1231
rotative speeds 1234
selection 1230–1231
contact wheel selecting 1232
cubic boron nitride (CBN) 782, 1178, 1195, 1204
cutting 1230–1233
diamond 1177
grains and materials 1177
grinding 1177
honing 1233–1235
lapping 1235–1238
polishing 1460
stones for honing 1235
ABS plastics 2533
Absolute
programming, NC 1269
system of measurement 142
temperature 2583
zero 2583
Acceleration 142, 167–170
angular 169
constant 167
linear, of point on rotating body 169
of gravity, g 142
Accuracy
effect of, on part tolerances 1249
of NC machine tools 1247–1248
positioning 1245
repeatability, and resolution, NC 1245
significance of 1247–1248
Acme threads
abbreviations 1826–1827
angle of thread 1825
ANSI Standard 1825–1846
centralizing 1832–1843
checking 1908
Acme threads *(continued)*
diameter allowances 1825
diameter tolerances 1825
drill sizes for 919
form 1825
general purpose 1825–1832
length of engagement 1825
multiple start 1826–1827
stub 1843–1846
alternative 1846
60-degree 1846
taps for 918–919
thread profile form 1825–1834
tolerances application 1837
types of 1825, 1834, 1837
wire sizes for checking 1908
Active face width 2029
Acute-angle triangles solution 64, 94–95
Adaptive control, NC 1262
Addendum 2029
chordal 2048–2049
modification 2077
involute spur and helical gears 2077
Addition
decimal fractions 10
fractions and mixed numbers 9
matrix 119
Addresses, letter, NC 1272
Adhesives
acrylic 2481
bonding 2480
moisture cured polyurethane 2483
one-component 2482
retaining compounds 2483
rubber cements 2483
sealants 2484
threadlocking 2484
two-component 2480
types 2480–2481
Adiabatic expansion and compression 430
Adjoint of a matrix 121
Adjusting gear blanks for milling 2093
Aerodynamic lubrication 2342
Aerospace screws, bolts and nuts 1805
Aero-thread 1890
Aging of metal 503
Air
absolute pressure 433–435
adiabatic expansion and compression 431
compression and flow 428
density 429
expansion and compression
adiabatic 430

Copyright 2004, Industrial Press, Inc., New York, NY

Air *(continued)*
expansion and compression
compression 430
expansion 430
horsepower to compress 432–435
isothermal 431
work to compress 431
flow in pipes 436
gage pressure 433–435
power or work to compress 431, 435
pressure, temperature, and volume relationships 430
properties of 428–429
velocity of escaping 437
volume and weight at different temperatures 428
volume transmitted through pipes 436
work to compress 431
Airdry wood, weight per cubic foot 413
AISI–SAE
alloy steels 446–447
carbon steels 444–445
Algebra and equations 29
Algebraic
expressions and formulas 30
rearrangement and transposition of terms 29
Allowances and tolerances
allowance defined 645, 651
allowance for forced fits 647
application 646
bending sheet metal 1332–1335
cylindrical fits, ANSI Standard for 651
fits 645–651
metric ISO, British Standard for 679–688
preferred series 652
tolerance defined 645, 651
unilateral and bilateral tolerances 645
Alloy cast iron 1360
Alloy steels 439
AISI-SAE designations 442–443
basic numbering system 440, 442
carburizing grades 455
casting 1363
compositions 446–447, 1364, 2146
directly hardenable grades 456–457
drilling and reaming 1061–1064
effects of alloying elements 2147
electrodes (welding)
current to use with 1413
elongation 1364
forged and rolled 2145
gears 2145
hardness of heat-treated 466–471
heat treatments 533
mechanical properties 466–471, 1364
milling 1045–1048
numbering system 440, 442
strength of heat-treated 466–471
Alloy steels *(continued)*
tensile strength 1364
turning 1027–1030
Alloys
aluminum 571–579
antimony 585
bearing 1373, 2261–2263
binary 441
brazing 1382–1388
cast steels 1362
copper 555–570
copper-beryllium 569–570
copper-silicon 569
die casting 1371
magnesium 586, 588
nickel 589–590
nonferrous 554
numbering systems for 440
quaternary 441
soldering 1380
ternary 441
titanium 589, 591
Alternating current motors 2469–2472
Alternating stress 206
Aluminum
alloys 571–579
anodizing 1463
characteristics 584
chemical composition 575, 578–579
electrical conductivity 584
elongation 575–583
high corrosion resistance 584
mechanical properties 584
temper 575–583
ultimate tensile strength 575–583
workability 584
yield strength 575–583
Association 572, 575
bearing material 2264
cast composition 575
characteristics of 571
clad alloys 583–584
coefficient of expansion 403
density 403
designations 575
die casting 1372
elongation 417
heat treatability of wrought 583
machining 1153
melting point 403
soldering 1380
specific heat 403
structural shapes 2518
temper designation 572–575
tensile strength 417
thermal conductivity 403
welding 1416
wrought 583
yield strength 417
American
Boiler Makers Association 292

Copyright 2004, Industrial Press, Inc., New York, NY

American *(continued)*
Brass Company 569
Bureau of Shipping 390
Foundrymen's Association 503
Gear Manufacturers Association (AGMA) 2032, 2035, 2068
Institute of Steel Construction 291
column formulas 289
Iron and Steel Institute (AISI) 380, 440, 442
National Standards Institute VI, 2079 *(see also* ANSI Standard*)*
Society for Metals (ASM) 471
Society for Testing and Materials (ASTM) 503, 550, 586–588, 1360
copper alloys 554
Society of Mechanical Engineers (ASME) VI, 2079 *(see* Index of Standards*)*
Standard Code for Information Interchange (ASCII) 1323
Standards Association VI
wire gage 2520
AMO thread 1886–1889
design dimensions 1888
design requirements 1887
formulas 1888
gage testing 1887
lengths of engagement 1887
limit of size 1889
swiss screw thread 1889
symbols 1888
tolerances and allowances 1887, 1889
Analysis, break-even 134–137
Analytical geometry 39–48
Angle
between lines tangent to two circles 715
between two lines 42
compound 108–110
cutting tool 750
degrees into radians 96, 98
functions of 88–107
helix 1965
indexing 1990
involute functions of 103–107
lead 1965
length of arc of given radius 66, 70–72
length of chord 66, 70–72
measuring by disc method 713
minutes, seconds into decimal degrees 97
minutes, seconds into radian 96
radian into degrees 96–98
sine bar for measuring 695–705
structural 2515–2517
bent to circular shape, lengths of 2508
moment of inertia 2515–2517
radius of gyration 2515–2517
section modulus 2515–2517
weight per foot 2515–2517
taper per foot corresponding to 714
Angle *(continued)*
thread, tolerances on gages 1917
to find, given taper per foot 713–715
tolerance, single point tool 767
trigonometric functions of 99–102
useful relationships among 99
Angular
acceleration 169
torque, relation to 172
backlash in gears 2073
indexing 1990–2009
velocity 167–169
of rotating bodies 168
Annealing 450, 503
constant temperature, transformation 525
temperatures
carbon steel 525
stainless 536–537
tungsten 541
Annuities (calculation of) 127–128
Anode 1349
Anodizing 1464
hard 1468
ANSI Standard
abbreviations 2540, 2543
Acme threads 1825–1843
bolts, nuts, screws, washers
inch 1512–1539
metric 1540–1544
boring tools 887, 891
carbide 887–888
buttress inch screw thread 1850
cap screws
inch
hex 1516
slotted head 1618–1619
socket head 1620
metric 1540–1543
socket head 1552
chain, transmission 2441–2446
clearance fits 669–671, 674–675
core drills 876
cutting tools 756–772
cylindrical fits 645
diamond wheels 1201–1206
dowel pins, hardened and ground 1670–1671
drawing and drafting practices 630
symbols
accuracy 1250–1253
between 633
comparison to ISO 633
concentricity 1252
controlled radius 633
datum referencing 638
diameter 633
parallelism 633
part tolerance 633, 667
perpendicularity 633
position 633, 1250
roundness 633

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Standard *(continued)*
drawing and drafting practices
runout 633
section lining 632
statical tolerance 633
total runout 633, 1253
welding 1432
drill drivers 875, 878
collet type 875
drive screws 1654
drive studs 1678
electric socket and lamp base threads 1884
engineering drawings 630–631
fine-pitch
helical gears 2108–2111
standard gear tooth parts 2040
worm gearing 2095–2098
fire hose connection threads 1874
fits 652
hole basis 670–673
shaft basis 674–677
flat metal products
inch sizes 2522–2523
metric sizes 2523
gagemakers tolerances 678
gages 1910–1918
for self-holding tapers 934
for Unified screw threads 1911–1918
usage, recommended 678
gear tooth forms 2035
geometric characteristic symbols 633
geometric dimensioning and tolerancing 630
grinding wheel safety 1207–1211
grinding wheels 1179–1187, 1195, 1204
grooved pins 1677
hexagon socket head shoulder screws 1624
hexagon spline socket set screws 1627
hose coupling screw threads 1873–1876
interference fits 669, 672–673, 1877–1882
involute splines 2156, 2160
metric module 2176–2181
jig bushings 975–985
key drive 931–932
keys and keyseats 2363
keys and keyways 819
knurls and knurling 1240–1244
letter symbols for mechanics 2543
limits and fits 651–677
lock washers 1535–1539
M profile thread
design profile 1787
designations 1803
limits of size 1797
tolerances of internal threads 1794
machine screws 1587–1596
binding head 1595

ANSI Standard *(continued)*
machine screws
fillister head 1593
flat, countersunk head 1588–1590
hexagon washer head 1590
metric 1597–1604
oval head 1593–1595
pan head 1592
round head 1596
slotted hexagon 1591
truss head 1591
manufacturers' standard gage for sheet steel 2522
metric
cap screws 1540–1543
clearance fits 670–671, 674–675
hex flange nuts 1564
hex flange screws 1547
interference fits 672–677
nut thread series 1563
nut tops 1561
nuts 1560, 1567
retaining rings 1684–1692
screw 1551
screw threads, M profile 1783–1803
screw threads, MJ profile 1804–1807
screws, bolts, nuts, and washers 1540–1544
slotted hex nuts 1563
square neck bolts 1547–1548
transition fits 672–673, 676–677
microscope threads 1884
milling cutters 797–825
miniature threads 1777–1781
numerical control 1255
nuts 1512–1516
pins 1667–1683
pipe and pipe fittings 2526–2530
pipe thread 1860–1869
plain washers 1532–1535, 1569
preferred
basic sizes 690
fits 669
metric limits and fits 656
metric sizes 665, 690
thicknesses, thin, flat metals 2522
reamers 839–853
retaining rings 1684–1692
rivets 1483–1485
roundness symbols 1251
runout symbols 1253
screw thread symbols 1825–1834, 1837, 1846, 1878
metric 1785
screw threads 1725, 1732–1776, 1783–1843, 1850, 1881
metric MJ profile 1804–1807
screws and bolts
hex structural bolts 1549
hexagon socket 1560
metric 1540, 1544–1546

Copyright 2004, Industrial Press, Inc., New York, NY

ANSI Standard *(continued)*
screws and bolts
metric hex bolts 1550
metric neck bolts 1547
square neck bolts 1548
section lining symbols 630, 632
self-tapping thread inserts 1654
self-threading screws
inch 1639–1649
metric
head types 1656
serrations, involute 2156
set-screws
heads and points 1625–1628
socket type 1626, 1631
shoulder screws 1624
slotted headless set screws 1625
spindles and drives for portable tools 948–951
spline socket set screws 1626, 1631
splines, involute
metric module 2176–2181
spring pin 1682
spur gear tooth forms 2035
square head set screws 1628
straight pins 1673
surface texture 724
symbols 678
accuracy symbols 1253
concentricity 633
datum referencing 638
diameter 1251
for section lining 632
tang drives 929–930
tapers 926–938
taps and threading dies 892–918
thread dimension 1879
threads for electric sockets 1884
thumb screws 1712–1720
T-nuts, T-bolts, T-slots 1664–1666
tolerances 652
allowances for cylindrical fits 645
gagemakers 678
symbols 633, 638
tooth proportions 2039
transition fits 669, 672–673
twist drills 854–877
Unified threads 1725, 1732–1782
washers
inch 1532–1539
metric 1566, 1568
welded and seamless wrought steel pipe 2527
wing nuts and screws 1712–1720
wood screws 1477
woodruff keys 2369–2372
worm gearing, fine pitch 2095–2098
wrench openings 1530
Antifriction bearings 2269–2323
Apothecaries measure
fluid 2567
weight 2571
Applications nickel alloys 589–590
APT (automatically programmed tool) 1292–1309
axis nomenclature 1264
circles 1294–1299, 1301
computational statements 1294
for turning 1307–1309
geometry statements 1294
geometry, 3-D 1303
motion statements 1299–1304
planes 1302
points 1295
postprocessor statements 1304–1309
program 1306
programming 1292–1309
tabulated cylinder 1303
Arbors
circular saw 948
diameters for spring-winding 353
dimensions of centers 839
keys and keyways for 819
milling cutters 815
shell reamer 850
standard milling machine 940–944
Arc
checking radius of 718
cutting 1418
electric, cutting of metals 1418–1419
length of given angle and radius 66, 70–72
plasma precision cutting 1418
plasma welding 1414
welding 1389–1414
Area
circle 66
circular
ring 67
ring sector 67
sector 66
segments 66, 71–72
cycloid 66
ellipse 68
enclosed by cycloidal curve 61
fillet 67
finding by Simpson's rule 60
geometrical figures 63–74
hexagon 65
hyperbola 68
irregular outline 60
octagon 65
parabola 67–68
segment of 68
parallelogram 63
plane figures 63–74
plane surface of irregular outline 60
polygon 65
rectangle 63
spandrel 67

Copyright 2004, Industrial Press, Inc., New York, NY

Area *(continued)*
square 63
surface of revolution 59–60
trapezium 65
trapezoid 64
triangle 64
units 2563
units and conversion of 2563–2565
various sections 238–247
volume 59–80
Argon, welding gas 1393, 1401, 1414
Arithmetical
operations, sequence of 5
progressions 36–37
ASA Code for transmission shafting 303
ASCII, American Standard Code for Information Interchange 1323
Atmospheric pressure 428, 2574
Austempering 503, 520
Austenite 507, 511
Autocollimation 1248–1249
Automatic screw machines 1131–1136
knurling on 1131
Avoirdupois or commercial weight 2571
Azimuth reading displacements 1248

B

B & S automatic screw machines 1131
Babbitt metals 2261–2263
properties of 2263
SAE general information 2261
Backlash 2030
allowance in checking gears by the pin method 2139
bevel gears 2069
calculation 2067
control of allowances in production 2070
control of in assemblies 2072
determining proper amount of 2067
excess depth of cut 2070
fine-pitch gears 2071
gearing 2067–2073
hypoid gears 2069
recommended for gears 2069
Balance wheels 183
Balancing
calculations 197–202
counterbalancing masses
located in single plane 198–200
located in two or more planes 200–201
dynamic 197
lathe fixtures 201–202
machines 197
rotating parts 197–202
running or dynamic 197
static 197
Ball bearing *(see* Bearings: ball*)*
Balls, standard 2323–2331
Balls, standard *(continued)*
grades 2326
hardness corrections for curvatures 2329
hardness ranges 2327
materials 2326
number per kilogram 2331
number per pound 2330
ordering specifications 2324
package markings 2315
preferred gages 2324
preferred sizes 2325, 2328–2329
tolerances 2326
Band brakes 2358
coefficient of friction 2360
simple and differential 2359
Band saw
blade selection 1138–1139
blade types 1139
break-in 1142–1143
speed and feed 1140
speed for cutting materials 1141–1142
speeds and feeds, metal cutting 1140–1142
tooth forms 1139
Barometer reading and equivalent pressure 430
Barrel
effect 1350
liquid capacity 2567
volume 80
Base
circle 2030, 2157
diameter 2157
helix angle 2030
oils for metal cutting 1146
pitch 2030
spur gear, diameter 2035
tooth thickness 2030
Basic
dimensions 636
of shaft or hole 645
endurance limit 2077
gear dimensions 2041
rack profiles 2180
space width 2157
Baumé's hydrometer 408
conversion 407
Beams 260–276, 2508–2514
channel 2514, 2518
combined stresses in 215–218
curved 279
deflections 260–271, 277–281
designing for 277–281
fixed at one end 272–276
I-beams 2508–2513, 2518
rectangular solid 272–276
stresses in 213, 260–271
stresses produced by shocks 283
supported at both ends 260–276
Bearings 2218–2323
ball bearing 2269–2288, 2294

Copyright 2004, Industrial Press, Inc., New York, NY

Bearings *(continued)*
ball bearing
ABEC tolerances 2279–2284
alignment and squareness 2295
allowance for axial displacement in 2286
angular contact 2271
cage materials 2277
clamping and retaining methods 2297–2302
clearances, running 2304
closures 2297, 2302
deficiencies 2307
design and installation 2286
designation 2277, 2289
double row bearing 2271
equivalent thrust load 2313
failures 2307
fatigue life 2307
fits 2297, 2302
flanged housing 2277
friction losses 2302
handling precautions 2306
housing bore tolerances 2289–2290
housings, soft metal 2296
life 2307
adjustment factor application 2318
adjustment factor for material 2318
adjustment factors 2318
criterion 2307
limitations 2308
load ratings 2307
locknuts and shafts for 2299–2300
lockwashers for 2298
lubrication method 2304
materials for 2277
mounting 2294
precautions 2297
types 2305
pillow block 2277
plastics 2276
quiet or vibration-free mountings 2297
radial and angular contact 2309–2310
radial and axial clearance 2305
radial, deep groove and angular contact 2308
rating life 2309, 2316
reliability 2318
seating fits 2297
selection 2303
shaft
and housing fits for metric radial 2288
bore limits 2289–2290
housing fits 2286–2288
tolerance
classifications, metric 2287–2288
limits, metric 2288–2289
single row radial, filling slot 2270
single row radial, non filling slot 2270

Bearings *(continued)*
ball bearing
soft metal and resilient housings 2296
special or unconventional types of 2276
squareness and alignment 2295
starting torque 2303
static
equivalent load 2321–2322
load criterion 2308
load ratings 2319
symbols 2269, 2271
thrust 2274, 2312
thrust load 2313
tolerances 2278, 2284
types 2270, 2308
guide 2221, 2260
hydrostatic 2221
journal 2229
allowable pressure 2234
bearing pressure 2233
capacity number 2236
classes 2234
clearance modulus 2234
diameter of bearing 2233
diametral clearance 2234
eccentricity ratio 2235
factor 2236
film thickness 2239
flow factor 2236
flow of lubricant 2236
friction horsepower 2236
friction torque 2236
hydrodynamic flow of lubricant 2238
length of bearing 2233
length to diameter ratio 2234
lubrication analysis 2239
operating temperature 2234
pressure 2234
pressure flow of lubricant 2238
temperature of mineral oils 2236
temperature rise 2239
torque parameter 2235
total flow of lubricant 2238
viscosity of lubricant 2234
keying 2223
laminated phenolic 2265
life adjustment factors 2318
lubricants and lubrication
grease 2227
journal bearings 2230, 2233, 2239
plain bearings 2226–2230
materials, plain 2260–2268
aluminum 2261, 2264
babbitt metals 2261
bronze 2264
cadmium alloys 2263
carbon-graphite 2264
cast iron 2264
compatibility 2260
conformability 2260
copper-lead 2261, 2263

Copyright 2004, Industrial Press, Inc., New York, NY

Bearings *(continued)*
materials, plain
corrosion resistance 2262
embeddability 2260
fatigue resistance 2260
graphitic 2266
laminated phenolics 2265
load capacity 2262
nylon 2265
plastics laminates 2265
porous 2265
properties 2260
rubber 2266
SAE compositions 2261
silver 2264
strength 2262
teflon (TFE) 2265
thermal conductivity 2262
tin-bronze 2261
white metal 2261–2262
wood 2266
needle 2274
loose roller 2275
symbols 2274
types of 2274
needle roller
designations of 2289
fitting and mounting practice 2291
roller and cage assemblies 2291
shaft and housing tolerances 2292–2293
tolerances 2284–2286
pillow block 2277
plain 2218–2268
allowable pressures 2233
boundary lubrication 2222
circumferential-groove 2218
classes of 2218
clearances 2233
controlled clearence noncontact seals 2224
cylindrical-overshot 2220
cylindrical-undershot 2220
design 2221–2258
design notation 2232
die casting in place 1373
displaced elliptical 2220
elliptical-overshot 2220
full film lubrication 2222
full film operational mode 2222
greases 2229
grooving feeding 2230
hardness and surface finish 2225
heat radiating capacity 2229
hydrostatic 2221
journal 2230
journal bearing oil grooving 2230
journal bearing types 2231
journal or sleeve 2218
keying methods 2223

Bearings *(continued)*
plain
length-to-diameter ratio 2233
lubricants 2227
lubrication analysis 2233
lubrication methods 2226
machining 2225–2226
materials 2260
mixed-film lubrication mode 2222
modes of operation 2221, 2223
multiple-groove 2220
nutcracker 2220
oil bath lubrication 2227
oil feeding 2230
oil grooves 2229, 2233
oil ring lubrication 2227
operating temperatures 2234
pivot-shoe 2220
positive contact 2224
press or shrink fit 2223
pressure 2220
pressure lubrication 2226
pressure profile 2231
retaining methods 2223
rubbing seals 2224
sealing methods 2223–2225
sleeve 2230
solid lubricants 2229
splash lubrication 2226
static seals 2225
surface finish and hardness 2225
three-lobe 2220
types 2218–2221
viscosity conversion table 2334
viscosity temperature chart 2228
waste pack lubrication 2227
porous 2265
retension
dowel pin 2224
housing cap 2224
set screws 2223
woodruff key 2224
roller 2269–2323
ABEC and RBEC tolerances 2289
alignment and squareness 2295
allowance for axial displacement 2286
barrel roller 2272
barrel type 2276
bearing closures 2302
cage materials 2277
clamping and retaining methods 2297
closures 2302
cylindrical type 2272, 2276
deficiencies 2307
design and installation considerations 2286
designation of 2277, 2289
failures 2307
fatigue life 2307
fits 2297, 2302
flanged housing 2277

Copyright 2004, Industrial Press, Inc., New York, NY

Bearings *(continued)*
roller
friction losses in 2302
handling precautions 2306
high speed effects 2313
housing bore tolerances 2289–2290
housings, soft metal and resilient 2296
internal clearance 2313
life 2307
adjustment factors 2318
for application 2318
for material 2318
criterion 2307
life adjustment factors 2318
load ratings 2307
location and seating 2294–2302
locknuts and shafts 2299–2301
lockwashers 2298
lubrication 2304, 2313
materials for 2277, 2313
method of designation 2288–2289
mounting 2294
precautions 2297
type 2305
needle type 2291–2293
pillow block 2277
plastics 2276
quiet or vibration-free mountings 2297
radial 2315, 2323
radial and axial clearance 2305
radial load 2315
rating life 2314, 2316
reliability 2318
seating fits for 2297
selection 2303–2304
self-aligning 2274
shaft and housing fits for 2297, 2302
metric radial 2286–2288
soft metal and resilient housings 2296
special or unconventional types of 2276
spherical roller 2272
spherical type 2276
squareness and alignment 2295
static equivalent loads 2322–2323
static load criterion 2308
stress concentrations 2313
symbols 2269
tapered 2273
tapered roller thrust type 2273
thrust 2273–2274, 2284, 2316
tolerances for 2278–2286
torque, starting 2303
types of 2272, 2313
roller thrust
spherical roller 2274
sleeve 2229
spacing and shaft stiffness 2084
tapered
land thrust bearing 2242, 2251, 2256
roller bearings 2273

Bearings *(continued)*
tapered
roller thrust bearings 2273
thrust bearing 2242, 2274
ball 2274
symbols 2272
design notation 2243
flat plate design 2242, 2244–2249
depth of chamber 2246
film flow 2245
flow per chamber 2245–2246
friction power loss 2245
kinetic energy correction 2246
length of pad 2245
number of pad 2245
pitch line velocity 2245
radial pad width 2244
required oil flow 2245
flat plate type 2248
friction power loss 2246
leakage factor 2253
load 2243
parallel flat plate 2242
plain 2242
rated life 2312–2318
roller 2273–2274, 2316
symbols 2273–2274
static equivalent load 2322–2323
step design 2242, 2248–2251
depth of step 2250
film thickness 2250
friction power loss 2250
hydrodynamic oil flow 2250
length of pad 2250
number of pads 2250
pad step length 2250
pitch line circumference 2250
pitch line velocity 2250
radial pad width 2249
temperature rise 2250
tapered land design 2242, 2251, 2256
film thickness 2252
friction power loss 2253
length of pad 2252
number of pads 2252
oil film flow 2253
oil flow factor 2253
oil leakage factor 2252
pitch line circumference 2252
pitch line velocity 2252
radial pad width 2252
shape factor 2253
taper values 2252
tilting pad design 2242, 2256
bearing unit load 2257
dimensionless film thickness 2259
film thickness 2258
friction coefficient 2258
length of pad 2257
number of pads 2257
operating number 2257, 2259

Copyright 2004, Industrial Press, Inc., New York, NY

Bearings *(continued)*
thrust bearing
pitch line velocity 2257
radial pad width 2257
temperature rise 2258
tolerances 2284
tolerances 2278
metric ball and roller 2279–2286
needle roller 2278
thrust 2278
Belleville disc springs or washers 348, 354
(see also Springs: disc*)*
Belts and pulleys 2388–2440
flat belts 2391
length formula 2388
rules for diameters and speeds of pulleys 2388
speed limitations 2391
speed in compound drive 2390
synchronus belts 2432, 2436–2440
cross section 2438
designation 2432, 2438
horsepower rating 2439–2440
length determination 2436
pitch lengths 2435
pulley
and flange dimension 2434
diameter 2436–2437
size 2437, 2440
tolerances 2438
section dimension 2434
service factors 2432
storage and handling 2429
timing 2432
tolerances 2435
tooth dimensions 2433–2434
torque ratings 2438–2439
width factor 2440
width, finding 2439
widths and tolerances 2436
variable speed belts 2422–2427
arc of contact 2429
cross section selection 2426
degree 2427, 2429
designation 2425
dimension 2422
drive design 2425
groove dimension 2424
horsepower rating 2426–2427
length correction 2428
lengths 2423
sheave dimension 2424
sheave groove data 2425
speed ratio 2426
V-belts 2393–2431
belt lengths and center distances 2398
classical V-belts 2399–2406
arc of contact correction 2406
cross section correction factors 2398
datum length 2400
Belts and pulleys *(continued)*
V-belts
groove dimension 2401
horsepower ratings 2403
length correction 2405
sheave dimensions 2400–2402
speed ratio correction 2405
double V-belts 2406–2414
arc of contact 2414
design method 2410
effective diameter 2409
effective length 2406
groove dimension 2407
length determination 2409
length-flex correction 2413
number of belts 2410
sheave dimension 2406–2407
tension 2414
tension ratings 2413–2414
tight side tension 2411
effective length 2391
horsepower ratings 2388
light duty V-belts 2414–2417
arc of contact 2414
designation 2414
dimensions 2415
groove dimension 2416
horsepower rating 2416
sheave dimension 2416
narrow V-belts 2393, 2398
arc of contact correction 2399
cross section selection 2397
groove dimension 2395–2396
horsepower ratings 2397
length correction factors 2399
number of belts 2399
sheave
dimensions 2393, 2395–2396
outside diameter 2397
size 2397
speed ratio correction factors 2398
ratio 2388
SAE belts and belting 2429
belt dimensions 2430
pulley dimensions 2430
service factors 2431
sheaves 2388
sixty (60)-degree 2429
storage and handling 2430–2431
V-ribbed belts 2417–2422
arc of contact correction 2421
cross-sections 2417
designation 2419
dimensions 2417
effective length 2420
grooved dimension 2418
horsepower rating 2419
length correction 2421
sheave dimension 2418–2419
speed ratio correction 2422
60 degree 2429

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX

Belts and pulleys *(continued)*
V-belts
speed ratio correction 2427
Bending
allowances, sheet metal 1332–1335
formulas
for beams 260–276
for shafts 299–301
stress in beams 260–281
structural angles 2515–2517
Bending load, wood 411
Bending moments units conversion 2577
Beryllium and copper alloys 570
Bevel gearing 2081–2095
ANSI/AGMA Standard 2085
applications of 2083
bearing spacing 2084
blanks 2083
bronze and brass gears 2147
chordal addendum 2095
chordal thickness 2093, 2095
circular pitch 2088
circular thickness 2095
cutting angle 2088
cutting teeth 2084
design 2083
dimensions 2087
face angle 2088
factors for offset of cutter 2092
formed cutters for 2089–2091
German standard tooth form 2121
hypoid gears 2082
materials for 2094
milled 2085, 2093
milling cutters for 817
milling setup 2092–2093
mountings 2084
nomenclature 2085
offset of cutter 2092
pitch cone 2087
pitch diameter 2087
planetary 2115
replacement gear dimensions 2154
selecting formed cutters for 2091
shaft stiffness 2084
spiral 2082
straight 2029, 2081, 2083
thickness of tooth 2088
types of 2081
typical steels used for 2094
Zerol 2029, 2082–2083
Bilateral and unilateral tolerances 645
Binary multiples 2546
Birmingham wire gage 2520
Birnie's equation 295
Blank diameters, drawing dies 1331, 1333
Blanks, sintered carbide 764
Blast cleaning of castings 1368
Block
brakes 2361
Block *(continued)*
NC 1270, 1272, 1274
or multiple indexing 2021–2022
Blow, force of 175
Boilers, strength of flat stayed surfaces 292
Boiling temperature,various substances 399
Bolt hole circles
chordal distance 69
coordinates for 989–1004
Bolts and nuts
angularity and eccentricity 1579
ANSI Standard 1514
ANSI, inch dimensions
cap or acorn nuts 1523
countersunk bolts 1528–1529
flat jam nuts 1520
hex
flat nuts 1520
nuts 1519
slotted nuts 1520, 1522
thick slotted nuts 1521–1522
jam nuts 1519
ribbed neck bolts 1527
round head bolts 1525–1527
round head fin neck bolts 1526
slotted countersunk bolts 1529
square
neck bolts 1525, 1528
nuts 1512–1513, 1522
step bolts 1528
T-bolts 1665
T-nuts 1666
Unified 1512, 1519, 1522
wing nuts 1712–1716
ANSI, metric dimensions
diameters 1543
heavy hex bolts 1549
heavy hex flange screws 1546
heavy hex nuts 1567
hex jam nuts 1567
hex nuts 1562
prevailing torque hex
flange nuts 1566
nuts 1565
reduced diameter bolts 1544
slotted hex nuts 1563
thread series 1563
bolt designation 1513, 1550–1551, 1566, 1570, 1579–1580, 1588, 1601, 1618, 1629, 1632, 1640, 1656, 1715, 1718
British Standard 1614
fine thread 1638, 1859–1885
hexagon bolts, screws, and nuts 1578
hexagon slotted and castle nuts 1573
metric hexagon 1574
precision hexagon nuts 1572
slotted and castle nuts 1572
Unified 1616
Whitworth 1571–1573, 1610, 1617, 1638
chamfering 1579

Copyright 2004, Industrial Press, Inc., New York, NY

Bolts and nuts *(continued)*
combination 1580
counterbore sizes 887, 1557
countersinking 1579
deflection 1495
designation 1580
diameter-length combinations 1552
drill sizes 1557
elongation and tightening tension 1504
elongation measurements 1500
eye bolts and nuts 394–395
finish 1578
friction coefficient 1504
friction coefficients 1498
grade markings for steel 1508
head markings
inch 1508–1509
metric 1550, 1561, 1566
heavy hex structural 1514
heavy hex structural bolts 1549
hex structural 1513
hexagon bolts, screws, and nuts 1578
hexagon sockets 1560
identification symbols 1551
length of thread 1579
load allowable on bolts 1509
loaded joints 1496
marking 1580
materials properties 1550
metric hex bolts 1550
metric hex cap screws 1553
metric hex flange nuts 1564
metric hex lag screws 1552
metric round head bolts 1551
metric screw 1551
nominal lengths 1578
preload 1495
adjustments 1498
application methods 1500
applications 1497
loaded joints 1496
shear 1496
proof strength 1495
relaxation of preloads 1499
round head neck bolts 1526
socket head cap screws 1552, 1560
spacing for wrench clearances 1530–1531
spline sockets 1560
square 1513
steel nuts 1580
strength grade designations 1508–1509, 1550–1551, 1561, 1566, 1579–1580
tightening 1495
torque 1495
torque prevailing types 1564
torque required to tighten 1495
Unified square 1514–1515
Unified Standard 1514–1515
washer facing 1579
Bolts and nuts *(continued)*
working strength of bolts 1509
wrench and socket clearances 1530–1531
wrench clearances for nuts 1530
wrench openings 1530
yield strength 1495
Bonding, adhesives 2480
Boring
carbide tools for 887–888
cutting time for 1082
insert holder 762–764
wood 414
Boring machine, origin 891
Boring tools
carbide carbide tipped round 889
carbide sizes 887
carbide style 887
sintered carbide 887
solid carbide 891
Boring-bar, cutters, carbide 887–888
Boron nitride
cubic (CBN) abrasive 1013, 1178, 1195, 1204
cutting tool materials 1013
speeds and feeds for 1033, 1039
Box wrench clearances 1530
Brakes
band 2358
block type 2361
coefficient of friction 2359
Brass and bronze
alloys 555
cast 556–559
speeds and feeds
drilling and reaming 1072
wrought 560–568
speeds and feeds
turning 1037
strength data 554
Brass files 965
Brazing 1382–1388
blowpipe 1387
dip 1387
filler metals for 1382
fluxes for 1386
furnace 1387
heating for 1387
induction 1387
methods 1387
resistance 1387
supplying heat
blowpipe 1387
torch 1387
symbols 1387–1388
vacuum furnace 1387
work 1387
Break-even analysis 134–137
Breaking load, bolts 1511
Breaking load, screws 1511
Bricks strength 420

Copyright 2004, Industrial Press, Inc., New York, NY

Briggs (now ANSI) standard pipe thread 1861–1862, 1890, 1892
drills for 1941
Brinell hardness 547
aluminum alloys 575–583
heat-treated steels 466–471
Rockwell conversion tables 550–551
test 547
British Association
basic dimensions 1886
instrument makers threads 1886
standard screw threads 1885
tolerance formulas 1886
tolerances and allowances 1886
British Standard
button head screws 1632
buttress threads 1849
cap screws 1633
cheese head screw 1615
clearance holes for metric bolts and screws 1938
combined drills and countersinks 874
core drills 880–881
countersunk head screws 1610, 1614, 1617
deviations for holes 687
deviations for shafts 685
dowel pins, metric 1668–1669
drills and countersinks 878
drills, metric 878, 880–884
fasteners, mechanical properties 1578, 1632
fine threads (BSF)
basic dimensions 1859
tolerance formulas 1857
fits 683
hexagon and thin nuts 1576
hexagon bolts 1570
hexagon bolts and screws 1575
hexagon head screws 1614–1615
hexagon nuts 1573
hexagon slotted and castle nuts 1572, 1577
hexagon socket countersunk 1632
hexagon socket screws, metric 1632, 1634, 1637
button head 1636
cap 1633
set 1635, 1637
imperial wire gauge 2520
interference fits 1581
ISO metric
grade markings 1578
limits and fits 679–688
tapping drill sizes for 1937
taps 922–925
threads 1805, 1823
ISO metric nuts 1576
ISO profile dimensions 1814
keys and keyways 2374, 2387
British Standard *(continued)*
limits and fits 684
limits of tolerance for shafts 682
machine screw nuts 1605, 1610
machine screws 1605–1617
countersunk head 1608
material 1605
metric series 1607
slotted countersunk head 1607
machine screws and nuts 1614
machine screws, cheese head 1612
machine screws, metric series 1613
metric
and inch pipe threads 1870–1871
basic sizes, preferred 690
bolts, clearance holes 1938
bright metal washers 1585
comparison of British, French, German and Swiss 1824
dowel pins 1668–1669
drills 878–884
gauge and letter sizes 879
hexagon socket screws 1632, 1637
keys and keyways 2374, 2387
limits and fits 679–688
machine screws and nuts 1605
metal washers 1584
series 1605
series plain washers 1584–1586
series spring washers 1582–1584
spring washers 1583–1584
taps, ISO 922–925
threads 1824
morse taper 881
mushroom head screw 1615
nuts 1571–1574, 1576–1577, 1605–1614
pan head screw 1615
pipe threads
jointing threads 1870
longscrew threads 1870
non pressure tight joints 1869
pressure tight joints 1870
precison metric nuts 1577
preferred metric basic sizes 690
preferred numbers 690
preferred sizes 691
recessed head screws 1614
rivets 1485–1491, 1494
RMS thread 1886
round head screw 1614
screws 1570, 1605, 1617, 1632–1638
thread dimensions 1871, 1886
thread profiles 1782, 1857
slotted head screws 1614
socket head 1633
spark plug threads 1883
spur and helical gears 2076
straight splines 2182
studs 1570, 1581
taps, ISO, metric 922–925
tolerance for holes and shafts 680, 682

Copyright 2004, Industrial Press, Inc., New York, NY

British Standard *(continued)*
twist drills 880–883
Unified
machine screws and nuts 1616
screws and nuts 1616
thread system
UNJ profile threads 1782
washers, plain, metric 1584–1586
Whitworth and fine machine screws 1605
Whitworth threads (BSW) 1857–1859
basic dimensions 1858–1859
formulas 1858–1859
instrument threads 1886
machine screws 1617
measuring 1896–1897, 1899, 1902
pipe threads 1869–1870
set-screws 1617, 1638
thread form 1857
tolerance formulas 1857
British thermal units, (BTU) 2583
converted into foot-pounds 2579
power and heat equivalents 2578
Broaches
chip breakers 959–960
clearance angles for teeth 959
depth of cut per tooth 958
depth of teeth 959
face angle or rake 959
land width 959
pitch of teeth 956–959
radius of tooth fillet 959
shear angle 959–960
surface 957
total length of 959
types 955–956
Broaching 955–961
cutting oils for 1146
cutting speeds for 1074
difficulties 961
pressure 957
types of machines 959–960
Broken tap, removal of 1941
Bronze bearing material 2264
Brown & Sharpe
automatic screw machines 1131–1136
forming tool formula 787
indexing plates 1983, 2011–2012
milling machine indexing 1983, 1985, 2011–2012
taper 926, 935–936
taper reamers for sockets 852
wire gage 2520
Brush finishing, power 1456–1459
Buckling, columns 286
Buffing and polishing 1457
Buffing wheels 1460
Bulk modulus of various material 420
Buoyancy 424
Burs and files, rotary 965
Bushings
gear 2149
jig, materials for 975
standard, for jigs 975
Butt joint, riveted 1478–1482
Button head screw 1632
Buttress threads 1849–1856
allowances and tolerances 1855
ANSI Standard inch type 1850
basic dimensions 1849–1850
British Standard 1849
designations 1856
diameter equivalents 1852
diameter-pitch combinations 1849–1850
dimensions 1855
formula 1856
height of thread engagement 1850
lead and flank angles 1852
pitch-diameter tolerances 1851
symbols and formulas 1850
thread form 1850
tolerances 1851, 1854–1855
wire method of measuring 1910–1911
Byte 2546
Byte, PLC 1258

C

Cables, wire, breaking strength 372–377
CAD/CAM 1315–1325
drawing exchange standards 1322–1324
projections 1317
rapid prototyping 1324
standard lettering sizes 1322
tips 1318
Cadmium
bearing alloys 2263
plating 1465
vacuum coating 1471
Cage materials, anti-friction bearings 2277
Caliper
gear tooth 2051
measurement of gear teeth 2051
vernier 692
Calorie, kilogram 2578, 2583
Cams and cam design 1135–1136, 2188–2213
accelerating forces 2205
acceleration, velocity, and displacement formulas 2190
classes of cams 2188
constant velocity with parabolic matching 2195
contact stresses 2210
cylinder cams shape 2211
displacement
constant velocity 2190
curves 2189
cycloidal 2192
diagrams 2189

Copyright 2004, Industrial Press, Inc., New York, NY

Cams and cam design *(continued)*
displacement
harmonic 2191
parabolic 2190
synthesis of 2192
follower systems 2188
forces 2205–2206
friction forces 2206
harmonic motion 2204
layout of a cylinder cams 2211
materials 2205, 2210
compressive stress 2210
milling 2212
offset translating follower 2198
pressure angle 2197, 2206
formula 2201
harmonic motion 2202
parabolic motion 2202
uniform velocity motion 2202
profile determination 2194, 2196–2197
radius of curvature 2203
cycloidal motion 2204
parabolic motion 2204
rise for threading 1134
size determination 2197–2201
stresses, contact 2205, 2209–2210
swinging roller follower 2196, 2200
symbols 2189
torque 2207
translating roller follower 2196
Cams and tool design 1135
Canned (fixed) cycles, NC 1287–1291
Cap screws 1516, 1618–1623
button head 1623
drill and counterbore sizes for 1621
finished, hexagonal 1516
flat head 1622
hexagon socket head 1632
hexagon socket type 1620–1623
hexagonal 1516
metric 1541
round head 1619
slotted fillister head 1619
slotted flat head 1618–1619
slotted head 1618
designation 1618
length of thread 1618
spline socket type 1620–1623
Capitalized cost 132
Carat 2571
Carbide blank
designations 764–765
sizes 764–765
Carbide tools 771, 773
application of cutting fluids to 1148
boring 887–888, 1075
coated 1011–1012
cutting 764
grinding 971–974
insert holders 752–764, 1310–1312
Carbide tools *(continued)*
insert type 752, 756–764
materials for 773–780, 1010–1012
nose angle 769–770
nose radius 767, 770
rectangular shank 767
sharpening 971
side cutting edge angle 768
single point 764
sintered 764
square shank 767
standard blanks for 764
style A 767
style B 768
style C 769
style E 770
style EL 770
style ER 770
tips for boring tools 887–888
Carbides and carbonitrides 773–778
Carbon steel 438
AISI-SAE designations 442–443
chemical compositions 444, 2145
classification 452
cold drawn 464–465
electrodes 1413
forged and rolled 2145
free cutting 454
gears 2145
heat treatments 532
mechanical properties 466–471
milling 1045–1048
numbering system 440, 442
structure of 507
tool steel as a cutting tool material 1010
turning 1027–1030
unified numbering system 440, 442
Carbonaceous mixtures 526
Carbon-graphite bearings 2266
Carbonitrides and carbides 773–778
Carbonitriding 510
Carburizing 503, 509, 526
gas 528
liquid 528
solid materials 526
steels for 455
temperatures
alloy steel 533
carbon steel 532
vacuum 528
Cartesian coordinates 42
Case hardening 503, 526
steel 526
Cash flow conversion 127–130
annuity to future value 129
annuity to gradient value 129
annuity to present value 129
diagrams 128
future value to annuity 129
future value to gradient 129
future value to present value 129

Copyright 2004, Industrial Press, Inc., New York, NY

Cash flow conversion *(continued)*
present value to annuity 129
present value to future value 129
present value to gradient 129
Casing thread 1890
Cast copper alloys 555–559
Cast iron
bearings 2264
chilled 1360
coefficient of expansion 404
cutting, flame 1419
density 404
ductile 1361
malleable 1361
melting points 404
nodular 1361
specific heat 404
speeds and feeds for
drilling, reaming, and threading 1068–1069
milling 1052–1053
turning 1033–1034
strength 474
thermal conductivity 404
Cast metals, power constant 1084
Cast roller chains 2441
Cast steel 1362
austenitic manganese 1364
chemical composition 1364, 2146
corrosion resistant alloy 1364
elongation 1364
mechanical properties 1363
strength 474, 1363
tensile strength 1364
yield point 1364
Casting processes
accuracy 1376
aluminum alloys 1372
ductile iron 1361
extrusion 1377
gravity die casting 1367
gray iron 1366
green-sand molding 1366
investment casting 1374, 1376
investment removal 1376
low pressure casting 1367
permanent mold 1366–1367
shell-molding 1366
squeeze casting 1367
V-process 1366
weights and sizes 1376
Castings
alloy steel 1362
blast cleaning 1368
brass and bronze 554
bronze and brass for gears 2147
centrifugal 180
cleaning 1368
cleaning methods 1368
die design 1371
Castings *(continued)*
dimensions 1375
ductile (nodular) iron 1361
finishing operations 1367
heat treatment 1367–1368
investment 1374
malleable iron 474, 1361
metal 1365
milling cutters 1377
nodular cast iron 1361
removal of gates and risers 1367
shrinkage of 1369
steel, for gears 2094, 2146
surface texture of 735
tolerances 1375
weight 1368, 1370
Castle and slotted nuts 1513, 1571, 1573
Cathode 1350
Cell, flexible manufacturing, NC 1264
Cement, strength of 420
Cementation 503
Cemented carbide tools 773–778
coated 778
drilling with 1061–1064
grinding 971–974
materials for 1010–1012
milling with 1044–1053
turning with 1027–1040
Cementite 507
Cements, pipe joints 2484
Center
distance, gear set 2041, 2043, 2111
drills reamers and machine countersinks 839
of oscillation 235
of percussion 235
Center distance, gearing 2030
Center of gravity 225–231, 235
any four-sided figure 226
circle sector 227
circular arc 226
cone 229
cone, frustum 229
cylinder 228
cylinder, portion of 228
ellipse segment 227
ellipsoid, segment of 230
fillet 227
of two bodies 229
parabola, area of 228
paraboloid 230
part of circle ring 227
perimeter or area of parallelogram 225
pyramid 229
pyramid, frustum 229
spandrel 227
sphere, hollow 230
spherical
sector 230
segment 230
surface 227

Copyright 2004, Industrial Press, Inc., New York, NY

Center of gravity *(continued)*
spheroid, segment of 230
trapezoid 226
triangle 225
wedge 230
Centering tools, length of point 877
Centerless grinding 1220–1222
troubles 1221–1222
Centers, for arbors and reamers 839
Centimeter-gram-second system of measurement 2544
Centimeter-inch conversion tables 2553
Centipoises 2334, 2586
Centistokes 2334, 2586
Centralized lubrication systems 2335
Centralizing Acme threads 1832, 1843
alternative series 1843, 1846
basic dimensions 1834
designation 1843
diameter allowance 1836
diameter tolerance 1837
formulas for determining diameters 1836
limiting dimensions 1836
major and minor diameter allowances and tolerances 1837
pitch diameter allowances 1836
pitch diameter tolerance 1837
single start screw thread 1836
thread data 1836
thread form 1834
Centrifugal
casting 180
clutches 2353
force 179–182
calculation 180
stresses in flywheels 188
Ceramic
coefficient of expansion 415, 780
compressive properties 415
compressive strength 415, 780
cutting tool materials 778–781, 1012
density 415, 780
dielectric strength 415
fracture toughness 780
hardness 415, 780
mechanical properties 415
modulus of elasticity 780
modulus of rigidity 780
poission's ratio 780
properties 780
tensile strength 415
thermal conductivity 415, 780
whisker reinforced 781
Cermets 773
Cgs system of measurement 2544
Chain
cast roller 2441
close-link 390
crane and hoisting 386–391
detachable 2441
Chain *(continued)*
pintle 2441
saw files 965
Chamfering insert holder 762–764
Chamfers and corner clearance, gearing 2164
Change gears
compound 1946, 2009
finding accurate ratios 1950
finding ratios 1950
helical gear hobbing 2112
helical milling 1965
idler gears 2009
lathe 1946
leads and angles for helical milling 1980–1981
odd inch pitch threads 1949
output, quick change 1948
relieving helical-fluted hobs 1950–1951
thread cutting, lathe 1946
fractional ratios 1947
fractional threads 1946
metric pitches 1946–1947
modifying the gearbox output 1947
threads per inch with given combination 1946–1947
trains, for fractional ratios 1947
Channels
aluminum 2518
moment of inertia 2514, 2518
radius of gyration 2514, 2518
section modulus 2514, 2518
steel 2514
structural 2514, 2518
weight per foot 2514, 2518
Checking
Acme threads by three-wire method 1906
assembly 643
castings 643
dimensions 643
drawings 642–644
enlarged spur pinion 2143
for strength 642
gear size 2125–2143
gears 2134
machined parts 644
measurements over pins or wires 2143
radius of arc 718
rake angles
indicator drop method 829–830
indicator drops on milling cutter face 830
relief angles
indicator drop method 829
indicator drops on end teeth 829
indicator drops on side teeth 829
screw thread dimensions 1901
shaft conditions 719
spur gear by wires 2126–2133
spur gear size 2126–2133
Whitworth threads 1901

Copyright 2004, Industrial Press, Inc., New York, NY

Cheese head screws 1610, 1615
Chemical compositions
alloy steels 446–447, 1364
aluminum alloys 578–579
carbon steels 444, 1364
cast steels 2146
copper 569
copper alloys 556–568
forged and rolled alloy steels 2146
forged and rolled carbon steels 2145
HSLA steels 463
magnesium alloys 587
molybdenum 541
nickel alloys 589–590
shock-resisting tool steels 497
stainless steels 448–449
tool steels 481
treatment of metals 1461
vapor deposition (CVD) 776
Chemical elements 398
atomic number 398
atomic weight 398
melting temperature 398
symbol 398
Chemical surface treatment of metals 1462–1464
Chilled cast iron 1360
Chip flow angle 1100
Chip thickness 1093, 1158
Chipbreakers 755
angular shoulder type 755
grinding 973–974
groove type 755
light cuts 756
parallel shoulder type 755
Chord
length for given angle and radius 66, 70–72
length for given number of divisions 989–992
Chordal addendum 2030, 2049
milled bevel gear teeth 2095
milled, full-depth gear teeth 2047–2048
Chordal distance of bolt circle 69
Chordal thickness 2030
gear teeth 2046, 2048, 2093
milled bevel gear teeth 2095
milled, full-depth gear teeth 2047–2048
Chrome 1465
Chromium
gearing material 2146
plating 1423–1424
tool steels 491
Chucking reamers 833
expansion 842
rose 834
Chucks
drill, tapers and threads for 939
hexagonal, for portable tools 951
spindle, for portable tool grinders 948
Cincinnati milling machines, indexing movements 2017–2020
Circles 45
center 45
chords for dividing circumference of 989–992
dividing, on jig boring machine 993–1004
enclosed within a circle 81–84
enclosed within a rectangle 86
general equation 45
geometry of 53
lengths of chords for dividing 989–992
moment of inertia 241
packing
in circles 81–84
in circles and rectangles 81–86
in rectangles 86
programming in APT (NC) 1296–1299
radius 45
radius of gyration 241
section modulus 241
segments 66, 70–72
squares of equivalent areas 73
Circular
arc center of gravity 226
disk, radius of gyration 233
gear teeth 2039
interpolation, NC 1283–1284
measure 2550
mil gage for wires 2563
pitch 2030, 2157
given center distance and ratio 2045
pitch gears, diameters of 2052
pitch in gears 2052
ring
moment of inertia 242
radius of gyration 242
section modulus 242
sector area 67
saws, arbors for 948
sector segment 989–992
sector, area 66
segment
area 66, 70
formulas 70
table of dimensions 71–72
thickness 2030
milled bevel gear teeth 2095
outside diameter
has been enlarged 2046
has been reduced 2046
is standard 2045
tools 794
Circumference
chords for dividing 989–992
of a circle, spacing 991–992
CL data, NC 1271
Clad aluminum alloys 584
Cladding with lasers 1454

Copyright 2004, Industrial Press, Inc., New York, NY

Classical belts and pulleys
V-belts 2399–2406
datum length 2400
groove dimension 2401
horsepower rating 2403
length correction 2405
sheave dimension 2400–2401
Classification of carbon steels 452
Clavarino's equation 295
Clearance 2030
angles
boring tools 887–888
for dies 1329
milling cutters 825
punch and die 1329
reamers, tooth rest position 835
drill sizes, machine screw 1934
effects on working pressure 1329
for wrench 1530–1531
holes 640, 645, 652, 655, 670
hex-head bolt and nut 887
inch machine screws 1934
metric
bolts and screws 1938
machine screws 1604
screws and bolts 1556
socket head cap screws 1557
square neck bolts 1558
tapping screws 1659
punch and die 1329
Cleveland forming tool formula 787
Clevis pins 1668
Closed-loop system 1262, 2488
Clutches 2350–2357
angle of cone 2352
angle of dividing head for milling 2356–2357
centrifugal and free-wheeling 2353
cone 2351–2352
cutting teeth 2355–2356
cutting with angular cutters 2355, 2357
disk 2350
double angle cutter 2357
friction 2349, 2351
friction coefficients 2351
magnetic 2352–2353
positive 2354–2355
power capacity of 2350
saw tooth 2356
single angle cutter 2356
slipping 2353
wrapped spring 2353
CNC 1254–1255
programming 1269–1309
Cobalt alloys 1012
Cobaltchrom steel 538
elongation 418
hardness 418
tensile strength 418
yield strength 418
Coefficient of
expansion
aluminum 403
cast iron 404
ceramics 415
common materials 402
copper alloys 403
ductile iron 404
plastics 416
thermoplastics 402
titanium alloys 404
various substances 402
friction 157–158, 2362
rolling resistance 159
steel on various materials 158
various materials on metal 2351
heat radiation 402
heat transmission 402
Cofactors of a matrix 121
Cold-form tapping 1939–1941
Cold-work
tool steels
air hardening 495
chemical composition 495
heat treatment 495
oil hardening 494
Collets 945–947
Colloidal suspension 1350
Coloring metals 1462–1464
Columns 285–291
American Institute of Steel Construction 289, 291
American Railway Engineering Association formulas 285
eccentrically loaded 286
Euler formula 286–289
J. B. Johnson formula 288–289
Rankine or Gordon formulas 285, 287
steel pipe, allowable concentric loads 290–291
Combination 18
drill and tap 1943
involute spline types 2167
shank, helix single end mills 807
Combined drills and countersinks 873
Combined stress 215–218
normal stresses at right angles 215
Common fractions 8
Compensation, insert radius, NC 1310–1312
Complex conjugate 17
Complex or imaginary numbers 17
Composite, checking of gears 2073
Compound
angles 108–110
indexing 1984–1990
thread cutting, NC 1292
Compression
in columns 285–291
springs 308–328
Compressive properties
ceramics 415

Copyright 2004, Industrial Press, Inc., New York, NY

Compressive properties *(continued)*
definitions 205
of air 430, 437
strength
ceramics 415
common non-metals 420
iron and steel 474
magnesium alloys 588
wood 412
strength, wood 412
Computer numerical control, CNC 1254–1255
programming 1269–1309
Computer-aided (or-assisted)
design (CAD) 1315–1325
manufacturing (CAM) 1315
Concave arbor-type milling cutters 815
Concrete strength 420
Conditional expressions, NC 1287
Conductance, thermal 401, 2582
Conductivity
electrical, of metals 1354
electrical, of plastics 605
Cone
center of gravity 229
clutches 2351–2352
frustum
center of gravity 229
of volume 77
polar moments of inertia 252
radius of gyration 234
polar moments of inertia 252
radius of gyration 234
volume 77
Coned springs 354
Conical pendulum 165
Conjugate fractions 12, 14
Constants, fundamental 2548
Constructional steels 1188–1189
Contact
diameter 2030, 2059
diameter, gearing 2059
ratio 2030, 2060
face 2030
gearing 2060
total 2030
stress 2030
stresses, cams 2210
Contents of tanks 61–62
Continued fractions 11–12
use of as conjugates 13–14
Continuity equation 432
Control, adaptive, NC 1262
Convergents 11–14
Conversational part programming, NC 1269–1270
Conversion
acceleration 2586
acres to hectares 2563
bending moments 2577

Conversion *(continued)*
celsius to fahrenheit temperatures 2583
centimeter to inch 2553
coordinate systems 42–44
cutting speed formulas 1016
density units 2572
energy units 2581
fahrenheit and celsius temperatures 2583
flow units 2570
force units 2576
fractional inch to millimeter 3
millimeter to fractional inch 3
moment and torque units 2577
moment of inertia units 2587
newton-meters into pound-inches 2577
numbers to powers-of-ten notation 15
oil viscosity unit 2334
pound-inches into newton-meters 2577
power units 2581
pressure units 2576
section modulus units 2587
specific gravity 408
tables
angular measure 96, 98
cutting speed and diameter to rpm 1017, 1211
cutting speed formulas 1943
decimal multiples of SI units 2546
foot-pounds into Btu 2579
fractional inch to millimeter 2552
hardness 550–551
horsepower into kilowatts 2579
millimeter to fractional inch 2552
pounds-force into newtons 2577
power and heat 2578
radians into degrees 96, 98
thermal conductance 2582
torque units 2577
U.S.gallons into liters 2566
UK gallons into liters 2566
velocity units 2586
viscosity 2586
work units 2581
Convex arbor-type milling cutters 815
Coolants for
lapping 1238
machining
aluminum 1153
magnesium 1154–1155
tool sharpening 973–974
zinc alloys 1155
tapping 1943
Coordinate system 42–44
converting to another 43
Coordinates, for jig boring 986–1004
Copolymer 594
Copper
coloring 1462
lead bearings 2261–2264
passivation 1462
plating 1466

Copyright 2004, Industrial Press, Inc., New York, NY

Copper and copper-base alloys
classification 555
coefficient of expansion 403
composition 556–568
copper-silicon alloys 569
copper-zinc-tin alloys 569
strength 420
density 403
die casting 1372
elongation 417, 556–568
hardness 417
machinability 556–568
melting points 403
passivation 1462, 1464
powdered metal alloys 419
specific heat 403
speeds, for drilling and reaming 1072
for turning and milling 1037
tensile strength 417, 556–568
thermal conductivity 403
UNS number 555–568
yield strength 417, 556–568
Copper- and iron-base sintered bearings 2267–2268
Copper-base powdered alloys
density 419
elongation 419
hardness 419
rupture strength 419
ultimate strength 419
yield strength 419
Cordeaux thread 1891
Core drills 876
Corner-rounding milling cutters 800, 815
Corrosion-resisting alloys 457, 460, 554, 570
Cosecant 88
Cosine law of 89
Cost
cutting grinding 1115
feeds and speeds 1118
function 1108
minimum 1107, 1109, 1161
optimum 1109
regrinding 1116
tools with inserts 1116
Cotangent 88
Cotter pins, standard sizes 1667, 1678, 1681
Cotters 2374
Coulomb shear theory (plastics) 609
Counterbores
cutters and guides 886
pilot 886
solid 886
three piece 886
Counterboring 885
Countersinks 839, 891
combined with drills 872
machine 839
Countersunk head
cap screws 1618
Countersunk head *(continued)*
rivets 1483, 1485, 1491
British Standard 1491
screw, British Standard 1614
screws 1588–1590, 1593–1594, 1610–1622
British Standard 1610–1617
Couples of forces 148
Couplings
connecting shafts 2346
double-cone 2347
fire-hose 1874–1876
flexible 2348
hose 1873–1874
interference fits 2347
knuckle joint 2350
safety flange 2346
shaft 306
single keys used as fixed 2169–2170
slipping 2353
universal 2348
CPVC plastics 2533
Crane
chain
hoisting 386–391
safe loads 387–388, 390
slings 387–388
strength 386–387
hooks, eyes, shackles 386–395
capacity of 393
dimensions 393–395
Crane motors 2476–2477
Crater-resistant carbide tools 1011
Creep 205, 208, 313, 602
modulus 602
rupture 205, 602
Critical
slenderness ratio 286
speeds 195–196
formulas for 195–196
of rotating bodies and shafts 195–196
speeds of rotating shafts 306
temperatures, heat treatment 503, 512
determining 515
Critical points of
decalescance 514–516
recalescance 514–515
Croning shell mold process 1366
Crosby Group 392–395
Cross recesses
for machine screws 1596
for self-tapping screws 1642
Cross section lining, ANSI Standard for drawings 630, 632
Crossed helical gears 2029
Crowned involute splines 2173
Crushing strength, wood 411
Cryogenic treatment, steel 547
Cube, volume 75
Cubes of wire diameters 351

Copyright 2004, Industrial Press, Inc., New York, NY

Cubic
boron nitride (CBN) 1013, 1033, 1035, 1039, 1177–1178, 1195, 1204
grinding wheels 1195, 1204
conversions 2566
equations 33
measure 2566
Cumulative fatigue damage 207
Cupola malleable iron 1361
Curve, normal distribution 1245–1248
Curved beams 279
stress correction factor 279
Curved tooth files 964
Cutoff or roughness sampling length 734
Cut-off tools, circular dimensions 795
Cutter
bevel gear, formed types 2089–2090
box-tool 1132
compensation, NC 1280–1282, 1310–1312
helical gear, formed type 2108
internal gear 2074
location data (CL data) 1271
Cutting
abrasive 952–954
bevel gear teeth 2084
blades 783
clutch teeth 2355
costs grinding 1115
electric arc 1418–1419
fluids 1143–1148
application of to carbides 1148
aqueous solutions 1144
broaching 1146
carbides 1148
chlorinated oils 1144–1146
magnesium 1146, 1148
mineral oil 1146
selection 1144–1146
soluble oils and compounds 1144
sulfurized oils 1144, 1146–1147
various alloys 1144–1146
gas torch cutting 1418, 1420
metals oxidizing flame 1418
roller chain sprocket teeth 2460
time for turning, boring and facing 1082
time per piece 1114
wire rope 380–381
Cutting fluids
for different materials 1145
for different operations 1145
for steel 1145
Cutting forces 1100
Cutting plane irons 783
Cutting speed
economic 1110
files and burs 966
lives 1122
optimum 1112
Cutting speeds and feeds 1009–1074
automatic screw machine 1132–1133
bandsaw 1140–1142
broaching 1074
chip thickness 1023–1025
cutting speed calculations 1036
cutting tool materials 475–501
CVD diamond tools 1013
diamond tools 1012
drilling and turning titanium and titanium alloys 1038
drilling, reaming, and threading
copper alloys 1072
ferrous cast metals 1068–1069
glass 1065
light metals 1070
plain carbon and alloy steels 1061–1064
stainless steels 1067
tool steels 1066
equivalent
chip thickness (ECT) 1023–1025
rpm for given cutting speed 1017–1021
rpm for given drill sizes and speed 1017
formulas for 1016, 1036
honing 1233–1235
metal cutting saws 1082
milling 1040–1053
feeds for high-speed steel cutters 1054
ferrous cast metals 1052–1053
plain carbon and alloy steels 1045–1048
stainless steels 1050–1051
titanium and titanium alloys 1038
planing 1082
reamers 1071
rpm for different speeds and diameters 1018–1021
shaping 1082
tapping 1072–1074, 1993–2007
thread chasing 1072–1074
tool
inserts 1310–1312
life 1013–1014
adjusting 1035–1036, 1040, 1043, 1059
steels 1031, 1049–1050, 1066
turning
copper alloys 1037
ferrous cast metals 1033–1034
light metals 1038
stainless steels 1032
superalloys 1039
titanium and titanium alloys 1038
tool steels 1031
unusual materials 1082
twist drills 1071
work materials 1009
Cutting tool grade 1059
Cutting tools 749–764, 833–834
angles 749–764, 1310–1312

Copyright 2004, Industrial Press, Inc., New York, NY

Cutting tools *(continued)*
angular
milling 802, 808, 821, 824, 834
application codes, ISO 779
boring-bar 887–888
carbide grade selection 773–783, 1011–1012
carbon tool steels 1010
carbonitrides (cermets) 773–778, 1012
cast nonferrous alloy 1012
cemented carbides 773–778, 1010–1012
ceramics 778–780, 1012
checking relief and rake angles 826, 830
chipbreaker 752
chucking reamers 834
clearance angles 826, 831
coated carbides 1011
coatings 776, 1011
crater-resistant carbides 1011
cubic boron nitride (CBN) 1013, 1178, 1195, 1204
CVD diamond 1013
diamond 781, 1012
polycrystalline 781, 1012
grades 1011–1012
grinding 823–831
checking rake angle 829
checking relief angle 829
high-speed steel 1010
indexable insert holder 751
indexable inserts 751, 1310–1312
machining data 782
materials 771, 773, 1009–1013
carbide ceramics 781
metals
compositions and properties 774
hardness 774
rupture strength 774
structures 774
tungsten carbide 774
oxide ceramics 780
silicon nitride base 781
superhard 781
milling 796–831
hand of flute helix 799
side 799
staggered tooth 799
point configuration 758
radial relief, eccentric type 826
rake angles 826
rose chucking reamers 834
sharpening 968–969
single-point 749–764
specifications, ISO 778
spline 824
titanium carbides 778, 1011
tool bit 751
tooth rest positions 831
trouble-shooting checklist 1014
T-slot cutters 800

Cutting tools *(continued)*
tungsten carbide 771, 773, 1011
combined with other elements 776
wheels for sharpening milling cutters 823–825
Woodruff keyseat cutters 820
Cyanide hardening (cyaniding) 504, 510, 527
Cycloid 2030
area 66
curves, area enclosed by 61
Cylinder
center of gravity 228
collapsing pressure 297–298
hollow
polar moment of inertia 250
radius of gyration 234
volume 77
plates and shells 292–298
polar moment of inertia 250
portion of volume 76–77
portion of, center of gravity 228
radius of gyration 233
strength to resist internal pressure 294–298
volume 76
working pressure vs. radius ratio 295–296
Cylindrical
coordinates 44
tank, contents 61–62
to rectangular coordinates 44
Cylindrical grinding 1212–1220
automation in 1215–1216
basic process data 1215
high speed 1215–1216
machines 1212
operating data 1214
selection of grinding wheels 1180, 1194–1195, 1204, 1213–1214
traverse and plunge grinding 1212
troubles 1216–1219
workholding 1213
Cylindrical roller bearings, symbols 2272

D

Damascus steel 441
Dardelet thread 1891
Data input, manual, NC 1269
Datum
feature 634
identifier 634
plan 635
reference frame 635
referencing 634, 638
simulator 635
target 635, 639
target lines 640
target points 640

Copyright 2004, Industrial Press, Inc., New York, NY

Decalescence point in steel hardening 514–516
Decimal
fractions 10
inch into fraction inch 3, 2552
multiples and submultiples of SI units 2546
point programming, NC 1274
Dedendum 2030
Definitions
gear terms 2029–2032, 2077–2079
geometric dimensioning and tolerancing 634
spline terms 2157–2159, 2172
surface texture 726
surfaces of solid materials 724
Deflection
beams 260–271, 277–281
calculation 214
flat plates 292–294
shaft, linear 302
shaft, torsional 301–302
springs
compression and extension 325–328
torsion 343–346
Degrees, expressed in radians 96, 98
Density
air 429
aluminum 403
cast iron 404
ceramics 415
copper alloys 403
copper-base powdered alloys 419
ideal 2548
iron-base powdered alloys 419
nickel alloys 404
of air at different temperature 428
plastics 416
plastics materials 416
powdered metals 419
stainless steels 404
titanium alloys 404
tungsten-base powdered alloys 419
units conversion 2572
water 423
wood 413
Department of Commerce 297
Deposition rates (welding) 1395
Depreciation 130–131
double declining balance method 130
property class and factors 131
statutory depreciation system 130
straight line method 130
sum of the years digit method 130
Depth of cut 1013–1014
Depth of engagement 2157
Derivatives of functions 34
Detachable chains 2441
Diameter factor 1163
Diameter of circle enclosing smaller circles 81–84
Diameters for finished shafting 303
Diametra pitch
knurls, (ANSI) Standard 1241
Diametral pitch
definition 2030
equivalent
circular pitch and tooth proportions 2038–2039
metric modules and circular pitch 2124
knurls, (ANSI) Standard 1240–1244
system 2034
Diamond
built up edge 783
concentration 971–972
cratering 783
dust for lapping 1237
grinding wheels 1190–1207
laps and lapping 1237
tool materials 781, 1012–1013
truing 1196–1200
wheels 971–973, 1201–1207
composition 1204
designation symbols 1201–1204
diamond concentration 971–973
feeds and speeds 1207
grades, grit sizes 971–972
modifications 1204
operating guidelines for 1207
operations and handling 1207
selection of 1206
shapes of standard 1201–1204
speeds and feeds 1207
terminology 1201
thread grinding 1957
work speeds 1207
Die casting
alloys 1371–1374
bearing metals 1373
design 1370–1371
dies machines 1373
files 965
injection molding 1374
machining zinc alloy 1155
porosity 1370–1371
skin effect 1371
Dielectric strength
ceramics 415
plastics 416
Diemaker's reamers 822
Dies and taps
combination drill and tap 1943
maximum pitches 1964
square thread 903, 907–910
tap drill size 919, 1933
Acme threads 919
formula 1934
metric 1937
pipe 1942
Unified 1925–1932
Dies, sheet metal
bending allowances 1332–1335

Copyright 2004, Industrial Press, Inc., New York, NY

Dies, sheet metal *(continued)*
blank diameters for drawing 1331
clearance between punch and die 1329
diameter reductions in drawing 1333
lubricants 1330
rectangular drawing 1330–1331
Dies, steel rule 1346–1348
Dies, threading, maximum pitches 1964
Differential
indexing 2008
pulley 163
Dimension
basic 636, 645
origin 636
reference 636
Dimensioning and tolerancing, geometric 630
Dip brazing 1387
Direct (or distributed) NC 1324
Disc spring 354–368
contact surfaces 355, 358
forces and stresses 358
group classes 354
materials 355
nomenclature 354
stacking 356
Disk
circular, radius of gyration 233
clutches 2350
method of measuring tapers 713
springs 348
Displacement in ball and roller bearings, allowance for axial 2286
Distance across bolt circle 717
Distance between two points 39
Distributed numerical control (DNC) 1324
Distribution curve, normal 1245
Dividing
circles 993–1004
fractions and mixed numbers 9
head, angular position 821–824
numbers written in powers-of-ten notation 16
Dolly bars for riveting 1483
Double angle milling cutters 802
Double V-belts
(see Belts and pulleys: double V-belts*)*
Double-cone clamping couplings 2347
Dovetail slides, measuring 713
Dowel pins 1667–1673
designation 1671–1672
ductility 1671
hardened ground machine 1670–1671
hardened ground production 1671–1672
lengths and sizes 1671
metric 1667–1669
shear strength 1671–1672
unhardened ground 1672–1673
Drafting practices, ANSI Standard 630
Draw-in bolt ends 943
Drawing
ANSI Standard
line conventions 630–631
surface texture symbols 732–733
welding 1442
applying surface texture symbols 733
bisect angle 55
checking 642
inspecting a new design 642
materials specified 642
method of making drawing 643
circle around square 57
circle around triangle 56
circular arc 56
data for gear blanks 2064
data for gears 2067
data for involute splines 2167
data for spur and helical gear 2067
data, splines 2169
divide line into equal parts 54
drafting practices 630
ellipse 47, 57
equilateral triangle 55
helix 58
hexagon around circle 57
hyperbola 58
involute 58
metric dimensions on 735
parabola 58
parallel lines 55
perpendicular lines 54
scales of metric drawings 736
sheet sizes 630
specifying spur and helical gear data on 2065
square around circle 57
symbols
ANSI Standard 630
section lining 632
geometric 633
ISO 633
lines 630–631
materials 632
tangent to circle 56
tempering, steel 521
triangle around circle 56
45-degree angle 55
60-degree angle 55
Drawing dies
annealing drawn shells 1330
blank diameters 1331
brass 1330
depth drawn in one operation 1334
diameter reduction in one operation 1334
rectangular 1330–1331
Dressing grinding wheels 1196–1200
Drilling
accuracy of drilled holes 884
automatic screw machine feeds and speeds 1132
cutting speeds for 1131

Copyright 2004, Industrial Press, Inc., New York, NY

Drilling *(continued)*
cutting speeds for
ferrous cast metals 1068–1069
light metals 1070
superalloys 1039
titanium and titanium alloys 1038
tool steels 1066
difficulties 1065
estimating thrust, torque, and power 1090–1092
feed factors 1091
holes in glass 1065
holes, accuracy of 884
horsepower and thrust for 1090–1092
machine, shaftless motor type 2474
spade 1075–1079
Drills
accuracy of drilled holes 884
and countersink plain types 873
and countersinks, bell types 873
angle of cutting point 968–970
ANSI Standards 854
chucks, tapers 939
cobalt high-speed steel 885
combined drills and countersinks 872–874
core, taper shank 874
counterbores 854
cutting speeds and equivalent rpm 1017
definitions of terms 854
diameter factors, thurst 1091
diameter factors, torque 1091
diameters of tap 1925–1932
driver, collet type 878
driver, split sleeve 878
drivers 878
for taper pin reamers 1674, 1677
grinding 968–971
jobbers length 856–862
length of point 877
letter sizes and gauge 879
metric, British Standard 874–884
nomenclature 854
screw machine drills 856–867
sharpening 969–971
sizes for tapping 1933
for Acme threads 919
sizes for tapping Acme threads 919
spade 1075–1079
specifications 1675
steels for 884–885
straight shank 854
straight-shank drill sizes
core drills 876
letter 860–861
metric 856–866
number 856–860
straight-shank, taper-length, drill sizes
fractional 857–866
letter 860–861
Drills *(continued)*
straight-shank, taper-length, drill sizes
metric 857–866
number 857–860
screw machine length 867
tangs for 866
tap and clearance hole sizes 1934
taper shank 854
taper-shank core drills 873–876
taper-shank drill sizes
fractional inch 868–873
metric 868–873
terms 854–855
twist 854–877
twisted
jobber series 882
parallel series 883
types 854–855
Drives
nose key 931–932
screws 1639, 1654
square, for portable tools 949
studs 1681
taper 930–931
Drums, chain and wire rope 378–379, 391
Drunken thread 1891
Dry measure 2567
Dryseal pipe threads 1866–1869
assembly limitations 1869
designations 1868–1869
diameter pitch combinations 1869
fine taper 1869
limitation of assembly 1866
limits on crest and root 1866
pressure tight joints 1866
taps for 901
types 1866
Ductile
cast iron 1361
iron 474, 1361
Duranickel, machining 1155
Durometer tests 551
Dynamic
balance 197
stresses 283
viscosity coefficient 2345
Dynamic factor 2078
Dynamometers 2359
Dyne 2544

E

Eccentricity 2165
Echols thread 1891
Economic tool-life 1110
ECT (equivalent chip thickness) 1023–1025
EDG (electrical discharge grinding) 1350
EDM 1349
capacitor 1350
craters 1350

Copyright 2004, Industrial Press, Inc., New York, NY

EDM *(continued)*
dielectric
filter 1350
fluid 1350
strength 1350
discharge channel 1350
dither 1350
duty cycle 1350, 1353
electrical controls 1354
electrode
growth 1350
wear 1350
electrode materials 1355
electrode uses 1356
electro-forming 1350
electronic controls 1352
Farad 1350
flushing 1352
gap current 1350
gap voltage 1350
heat-affected zone 1353
ion 1350
ionization 1350
low-wear 1350
machine settings 1353
materials 1355
characteristics 1355
elctrode 1355
metal removal rates 1354
negative electrode 1350
no-wear 1350
overcut 1351
plasma 1351
plunge (sinker) method
electrode materials 1354
machine settings 1352
making electrodes 1357
metal removal rates 1354
positive electrode 1351
power parameters 1351
process 1351
quench 1351
recast layer 1351, 1354
secondary discharge 1351
spark frequency 1353
spark in and out 1351
square wave 1351
stroke 1351
UV axis 1351
white layer 1351
wire 1359
drilling holes 1359
EDM 1351
guide 1351
speed 1351
wire electrode 1359
wire method 1349
workpiece materials 1354
Effective
dimensions, splines 2157, 2165
length of bolt 1499
Efficiency 2031
influence of friction on 157
machine tool 1086–1090
riveted joints 1479–1483
Elastic
limit 204
limit, plastics 598
modulus 204
in shear (torsion) 204
spring materials 348–350
various materials 204
properties of material 420
region 204, 1503–1504
tightening fasteners in 1497–1502
Elastohydrodynamic lubrication 2342
Electric
arc, cutting metals 1418–1419
fixture threads 1885
motor keys and keyseats 2368
socket and lamp base threads 1884
Electrical fixture threads 1884
lamp base 1884
socket shell threads 1884
Electrical network 124
Electrical relationships 2587
Electrode
diameter, sheet metal 1407
making 1357
machining graphite 1357
material 1355
brass 1356
copper 1356
copper-tungsten 1356
graphite 1356
steel 1356
zinc 1356
material selection 1357
uses on various materials 1356
wear 1357
Electrodes (welding)
characteristics of standard types 1409
AWS E60XX 1406
current to use with 1394, 1413
deposition rates 1391, 1395–1397
diameter to use 1390, 1399, 1408
selecting GTAW tungsten type 1411–1414
wire, feed rates 1394
Electropolishing 1468
Elements, table of chemical 398
Elevation reading displacements 1248
Ellipse 46–47
area 68
drawing 47, 57
eccentricity 46
foci 46
general equation 46
major axis 46
methods of drawing 57
minor axis 46
moment of inertia 242

Copyright 2004, Industrial Press, Inc., New York, NY

Ellipse *(continued)*
radius of gyration 242
section modulus 242
segment, center of gravity 227
Ellipsoid
polar moment of inertia 251
radius of gyration 235
volume 78
Elliptic gears
Gears and gearing
elliptic 2114
Elongation
alloy steel 1364
aluminum 417
aluminum alloys 575–583
carbon and alloy steels 466–471
carbon steel 1364
carbon steel rounds, squares, and hexagons 464–465
cobalt alloys 418
copper alloys 417, 556–568
copper-base powdered alloys 419
copper-beryllium alloys 570
copper-silicon alloys 569
high-strength, low-alloy steels 463
iron-base powdered alloys 419
magnesium alloys 588
measurement of bolts 1500
nickel alloys 418, 589–590
plastics 416
powdered metals 419
stainless steel 418, 472–473
steels 417, 1363
titanium alloys 591
tungsten-base powdered alloys 419
Emery
grades 1461
grain numbers for polishing 1461
End mills
angles for milling teeth in 821
ANSI Standard 804–814
combination shanks for 806
high speed steel 807
plain and ball end 810
terminology of 803
with combination shank 807
with straight shanks 808–809
with taper shanks 809
with weldon shanks 804, 806–807, 810
Endurance limit 205, 2077–2078
for spring materials 318
Energy 173–174, 1350
and momentum 171
kinetic 173–175
of flywheels 184–185
potential 174
units conversion 2581
Engagement, length of thread 1510
Engine lathe, change gears 1946
Engineering economics 125–137
Enlarged pinions
center-distance system for 2058
in helical gearing 2108–2111
in spur gearing 2050, 2058
Epicyclic gearing 2115–2118
bevel gear type 2116–2118
ratios 2116–2118
Epicycloidal curves, areas 61
Equations
cubic 33
line 40
quadratic 31
simultaneous 122
solution of
first degree with one unknown 31
first degree with two unknowns 31
numerical with one unknown 33
quadratic with one unknown 31
using Newton-Raphson method 33
Equilateral triangle 88
Equivalent chip thickness (ECT) 1023–1025
Equivalent pitch ratio 2031
Equivalent uniform annual cost 133–134
Erg 2544
Etching and etching fluids 1461–1462
Euler's formulas for columns 286–287
Evaluating alternatives 131–134
benefit cost ratio 134
capitalized cost 132
equivalent uniform annual cost 133
net present value 131
payback period 134
rate of return 134
Evaluation length 727
Evaporation, latent heat of 399
Everdur copper-silicon alloy 569
Exbi 2546
Expansion
air 430
chucking reamers 842
fits 648
hand reamers 844
pipe 427
Exponent 14
External spline 2158, 2167
External spur gear 2029
Extrusion
applications 1378
for tubes 1378
of metals 1377
process 1377
cold 1377
hot 1377
Eye bolts and nuts 394–395
Eye splice 393

F

Fabric, bonding 2482
Facing cutting time for 1082

Copyright 2004, Industrial Press, Inc., New York, NY

Facing insert holder 762–764
Factorial 18, 103
Factors
of numbers 19–28
prime number 19–28
Factors of safety 208
machine columns 288
shafts 300, 305
tubes subject to external pressure 298
wire rope 375–376
Failure
fatigue, modes of 207
fatigue, springs 318
of riveted joints 1479
of springs 352
Fasteners detecting counterfeit 1509
Fatigue
combined with creep 208
contact 208
corrosion 208
cumulative damage 207
failure, modes of 207
influence of stress on 206–208
life factor involute splines 2172
low/high cycle 207
properties 205
S-N diagrams 205, 207
springs 318
surface 208
tests on plastics 603
thermal 207
FCAW (flux-cored arc welding) 1398
Federal specification
gage blocks, inch and metric sizes 743
Feed
function, NC 1278–1279
rate override, NC 1280
rates
centering tools 1132
for drilling 1132
for milling 1040
for turning 1027–1040
hollow mills 1132
number of teeth 1128
Feeds and speeds 1009–1074, 1079, 1131–1132, 1140–1143
grinding 1158
total costs 1118
Feet
and inches into inches 2550
into meters 2562
Feet per minute into rpm 1016–1021, 1943
Fellows stub tooth gears 2041
Ferrite 507
Ferrous
cast metals, speeds
for drilling, reaming, and threading 1068–1069
for milling 1052–1053
for turning 1033–1034
Fiber, vulcanized, strength of 420
Files 1456
chain saw 965
characteristics 963
classes 963
American pattern 963
curved tooth 963
machinist's 963
mill or saw 963
rasp 963
Swiss pattern 963
coarseness of cut
bastard 963
coarse 963
second 963
smooth 963
cross section 963
curved tooth class 964–965
cut
double cut 963
double cut finishing 963
rasp 963
single cut 963
cutting speeds 966
definitions of terms 962
flat 964
machinist's class 964
flat 964
general purpose 964
half round 964
hand 964
knife 964
pillar 964
round 964
square 964
three square 964
warding 964
wood 964
mill or saw class 963
blunt hand saw 964
blunt mill 964
blunt triangular 964
cantsaw 963
crosscut 963
double ender 963
mill 963
taper saw 964
triangular saw 964
web saw 964
pillar 964
rasps 965
rifflers 965
rotary 965
round 964
shear tooth 965
special purpose 965
aluminum rasp 965
brass file 965
chain saw 965
die casting 965
foundry 965
lead float 965

Copyright 2004, Industrial Press, Inc., New York, NY

Files *(continued)*
special purpose
long angle lathe 965
shear tooth 965
square 964
Swiss pattern class 965
blunt machine 965
die sinker 965
die sinker rifflers 965
needle 965
silversmiths rifflers 965
teeth, cut of 963
warding 964
wood 964
Filler metals for brazing 1382
Fillet
area 67
center of gravity 227
radius 2031
Fillister head machine screws 1593
Fine blanking 1344
tool dimensions 1345
Finishing, power brush 1456–1459
Fire hose connection
screw threads 1874–1876
Fire hose connection screw threads
ANSI Standard 1874
thread designation 1874
thread form 1874
Fits 652
actual 652
and limits
graphical representation 655–657
tolerances designation 666
basic shaft fits 656
bilateral hole fits 656
British Standard
limits and fits 684
minimum and maxmum clearances 683
tolerance limits
holes 682
shafts 682
clearance fits 670–671, 674–675
cylindrical
allowances and tolerances for 645
ANSI Standard 651–677
British Standard 679
definitions 645
expansion 648
forced 646, 663
metric ISO, British 679–688
metric radial, ball and roller bearing shaft and housing 2286
preferred series 652
shrinkage 648, 663
transition 657, 662
drive 656
expansion 648
force 655–656, 663
allowance 647
Fits *(continued)*
force
pressure in assembling 647
hole basis
British Standard 680
figure 668
hole system 652
interference 652, 669
locational 655
clearance 655, 660
interferance 665
interference 655
transition 655, 662
metric clearance fits 670–671, 674–675
metric interference fits 672–673
metric transition fits 672–673
running 655, 658
shaft basis
British Standard 680
figure 668
shaft system 652
shrinkage 648, 655–656, 663
allowance 648–650
sliding 655, 658
transition 652, 669
Fittings
pipe 2526–2538
pipe,friction loss in 427
Fixed (canned) cycles, NC 1287–1291
Fixtures and jigs 975–985
Flame
cutting of metals 1418–1420
cutting torch 1419
hardening 529
spraying process 1472
Flanged housing bearings 2277
Flank of tooth 2031
Flat
belts rivets 1485
head cap screws 1618, 1622
head machine screws 1588–1590, 1614
metal products, preferred thicknesses 2523
plate
circular 294
square and rectangular 292–293
strengths 292–294
thin radius of gyration 232
stayed surfaces in boiler work, strength 292
Flexible
belts 2388
couplings 2348
manufacturing
cell 1264
module 1264
systems, (FMS) 1263
Flexural modulus, plastics 416
Floor and bench stand grinding 1229
Flow of air in pipes 436

Copyright 2004, Industrial Press, Inc., New York, NY

Flow of water through nozzles 425
in pipes 423, 2531
Flow, units conversion 2570
Fluid maintenance 1151
biocide treatment 1151
personal protective clothing 1151
system service 1151
Fluidized bed furnace 503, 512
Fluting cutters, reamers 833–834
fluting, for reamers 833–834
Fluxes
brazing 1386
soldering 1380
Flywheels 183–194
bursting speed tests 192–193
calculations 184–194
centrifugal stresses in 188
classification 183
design, general procedure 184
energy of 184–185
for presses, punches, shears 185–188
dimensions of 186
rim velocity 186
simplified calculations 187–188
weight of rim 187
pulley 183
spokes or arms of 194
stream engine 193–194
stresses 193
centrifugal in rim 188
combined bending and centrifugal 189
in rotating disks 193
types of 183
Foot-pound
equivalents 2578
into British thermal units 2579
Force 141, 203
acceleration resulting from 171–172
addition and subtraction of 145
algebraic composition and resolution of 148–156
algebraic solution
forces in same plane 149–151
forces not in same plane 153–156
and couples, work performed by 174
centrifugal 179–182
calculating 180
colinear 148
components of 145, 148
composition 145, 148
concurrent 148
components of single force 149
coplanar 148
couples of 147–148
differential pulley 163
disc springs 358
for moving body on horizontal plane 161
friction 171
graphical representation 145–149
moment of 141, 147
Force *(continued)*
noncoplanar 148
normal component 171
of blow 175
of gravity 171
on inclined plane 160
parallel 146
parallelogram of 145
polygon of 146
pound 142–143
relationship to time 203
resolution of 145, 148
into rectangular components 153
resultant 145, 148
any number of concurrent forces 153
locating when components are known 156
non-intersecting forces 151–152
non-parallel, non-intersecting forces 155
parallel forces 150
parallel forces not in same plane 154
single force and couple 150
three or more concurrent forces 149
two concurrent forces 149
screw 163
systems 145
toggle joint 164
units conversion 2576
work performed by 174
Format
classification 1272–1274
detail, NC 1272–1274
word address, NC 1272–1274
Formed cutters for internal gears 2074
Formica, machining 1156
Forming tools 784–795
arrangement of 789
circular 787
constant for determining 789
corrected diameter 789
diameters of 789–795
with top rake 789
diameter 788
dimensions 785
feeds per revolution 789, 795, 1131
formula 787
Acme machine 787
Brown and Sharpe machine 787
Cleveland machine 787
screw machine dimensions 794
speeds for 789, 795
straight 784
with rake 784
Formulas
algebraic 30
area 63–68
column
American Railway Engineering Association 285
Euler 286–289

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas *(continued)*
column
Johnson 286
Rankine or Gordon 285
straight-line 285
contour milling 2025
critical speeds 195–196
cutting speed 1016
derivative 34
dimensions of milled bevel gears 2085, 2087
dimensions of SAE standard splines 2185
dimensions of standard spur gears 2035
distance across bolt circle 717
for helical gears 2099, 2101–2105, 2107, 2110
for module system gears 2121, 2123
integral 34
internal gears 2075
linear motion, constant acceleration 167
pendulum 165
proportions of ANSI fine-pitch worms and wormgears 2096
rearrangement of 29
rotary motion, constant acceleration 169
tooth parts, coarse pitch spur gear 2035
torque capacity of involute splines 2170
transposition 29
triangle
oblique 64, 94–95
right 64, 91, 93
trigonometric 89–90
volume 75–80
work and power 178
Fractional inch to millimeter conversion 3, 2552
Fractional threads 1946
Fractions 10
conjugate 12
continued 11–12
use of 13–14
mixed numbers 9
Free
body diagram 171
cutting steels 454
wheeling clutches 2353
Freezing mixtures 403
French
metric screw threads 1824
thermal unit 2583
thread 1891
Fretting damage 2174
Friction 157–159, 171
brakes 2358–2361
clutches 2349, 2351
coefficient in gears 2078
coefficients 158, 1505, 2351, 2359–2362
bolts 1498
hexagon head bolt and nut 1504–1505
nuts 1498

Friction *(continued)*
coefficients
rolling resistance 159
static steel on various materials 158
torque 1504–1505
effect on efficiency 157
in brakes 2360
laws of 157
rolling 159
wheels horsepower 2362
wheels, power transmission 2360–2361
Friction loss
elbow
45 degree 427
90 degree 427
in bearings 2302
standard tee
flow thru branch 427
flow thru run 427
Fuels, equivalent 2582
Functions
derivatives 34
integration 34
involute 103–107
of angles graphic illustration 98
sevolute 103
trigonometric 88–90, 99
tables of 99–102
versed cosine 103
versed sine 103
Fundamental constants 2548
Furnace brazing 1387
Furnaces, steel heat-treating 503, 511–512, 543
Fusion, latent heat of 399

G

Gage block sets
inch sizes 744
metric sizes 745
Gage blocks, precision 743–745
federal specifications for 743
inch sizes 744
metric sizes 745
Gage tolerances 1916–1917
Gagemakers tolerances 678
Gages
ANSI Unified thread
classification 1911
constants for computing dimensions 1916
form 1913, 1916
formulas for limits 1918
tolerances for plain gages 1916
rods 2519
sheet metal 2522–2523
sheet zinc 2522–2523
thickness and diameter sizes, galvanized sheet 2522–2523

Copyright 2004, Industrial Press, Inc., New York, NY

Gages *(continued)*
thread form 1914
tolerances 1914
tubing 2519
usage, ANSI Standard recommended 678
wire 351, 2519
zinc 2522–2523
Gaging methods and measuring instruments 692
Gallons
cylindrical tanks 61–62
in tank at given level 61–62
into cubic inches 2566
U.S. into liters 2566, 2569
Galvanized, (welding) 1390
Gas
carburizing 528
illuminating, specific gravity 407
metal arc welding (GMAW) 1390
specific gravity 407
specific heat 400
tungsten arc welding (GTAW) 1409–1414
G-code programming, NC 1272–1292
Gear cutters, formed
involute 2048, 2074, 2109
milling cutters for
chain sprockets 817–818
14.5 deg pressure angles 816–817
number for bevel gears 2089–2090
Gear cutting
block or multiple indexing 2021–2022
excess depth to obtain backlash 2070
formed cutter selection 2052, 2089–2090, 2108
internal gears 2074
Gearing materials
effect of alloying meatals 2146
chrome-molybdenum 2147
chrome-nickel 2147
chrome-vanadium 2147
chromium 2146
manganese 2147
molybdenum 2147
nickel 2146
nickel-modybdenum 2147
vanadium 2147
forged and rolled
alloy steels 2145
carbon steels 2145
non metallic 2149
applications 2150
bore sizes 2151
diametral pitch for given power 2151
diametral pitch for given torque 2152
keyway stresses 2151
mating gear 2150
power transmitting capacity 2150
preferred pitch 2151
safe working stress 2150
Gearing materials *(continued)*
non metallic
tooth form 2150
sintered materials 2147
steel castings 2146
Gears and gearing 2099–2143
active face width 2029
active spline length 2157
actual safety factor 2078
actual space width 2157
actual tooth thickness 2157
AGMA Standards 2068, 2072
angular backlash 2067–2073
arc
of action 2029
of approach 2029
of recession 2029
thickness of internal gear tooth 2074
thickness of pinion tooth 2074
axial
pitch 2029
plane 2029
thickness 2030
backlash 2067–2073, 2139
angular 2073
recommended 2069
bearing spacing and shaft stiffness 2084
bevel gears 2081–2095
blanks
design of 2065
for fine pitch gears 2064
bottom land 2030
bronze and brass castings for 2147
bulk temperature thermal flash factor 2079
bushings for gears 2149
calculated safety factors 2078
calculating
dimensions of milled bevel gears 2087
replacement gear dimensions 2153
spur gear proportions 2035
case hardening steels for 2144
change gears, for lathe 1946
checking
gear sizes 2125–2143
pressures 2073
spur gear sizes 2135–2138
chordal measurement of teeth 2140–2142
circular pitch system 2034
coefficient of
friction 2078
contact ratio factor 2060, 2077–2078
crossed helical 2029
deburring tooth profile 1456
design of bevel gear blanks 2083
diametral pitch
definition 2030
preferred 2040
system 2034
differential indexing ratio 2008

Copyright 2004, Industrial Press, Inc., New York, NY

Gears and gearing *(continued)*
drawing
data for spur and helical gears 2067
information to be given on 2076
efficiency 2031
elasticity factor 2077–2078
endurance limit 2078
enlarged pinion
fine-pitch 2054
meshing without backlash 2058
reduced dimensions to avoid interference 2050
epicyclic 2115–2118
equivalent pitch radius 2031
external spur gears 2029
dimensions for checking over wires 2126–2129
face advance 2031
Fellows stub tooth 2041
fillet radius 2031
fillet stress 2031
finishing gear milling cutters 2054
flank of tooth 2031
forged and rolled
alloy steels for gears 2145
carbon steels for gears 2145
formed cutters for bevel gears 2091
formulas
for helical gears 2099, 2101–2105, 2107, 2110
for module system gears 2121, 2123
for spur gears 2035–2036, 2039, 2041–2042
given center distance and ratio 2041, 2043
to mesh with enlarged pinion 2058
gear ratio, definition 2031
geometrical factor 2078–2079
given center distance and ratio 2043
harder pinion 2145
heat treatment to permit machining 2144
helical 2029, 2099–2114
herringbone 2114
highest point of single tooth contact (HPSTC) 2061
hypoid bevel gears 2029, 2082
increasing pinion diameter to avoid undercut or interference 2052
inspection of gears 2073
integral temperature criterion 2079
interference 2031
internal diameter 2031
internal gears 2031, 2074
spur 2029, 2074–2075
dimensions between wires 2130–2133
invention 2152
involute curve 2033
land 2031
lead 2031

Gears and gearing *(continued)*
length of action 2031
life factor 2077–2078
line of action 2031
load distribution 2078
lowest point of single tooth contact (LPSTC) 2031, 2060
lubricant influence 2078
roughness, and speed 2077
lubrication film factor 2078
material quality 2077
materials for 2144–2150
bevel gears 2094
maximum hob tip radius 2061
measuring
gear size over wires 2125–2143
teeth 2051
methods of cutting internal gears 2074
metric module gear cutters 2052
module system 2121–2124
module, definition 2031
motion control 2493
mountings for bevel gears 2084
nomenclature of gear teeth 2033
non-metallic 625, 2149
normal plane 2031
number of teeth 2031
to avoid undercutting 2058
outside diameter 2031
pin method of checking size 2125–2143
pinions flanges composition 2149
pitch diameter 2034
obtained with diametral pitch system 2034
pitch point 2031
plane of rotation 2031
planetary 2115
plastics gearing 625
pressure angle 2032, 2039
profile checker settings 2062
rack 2032
ratchet gearing 2119–2120
ratio, defined 2031
relative sizes of internal gear and pinion 2074
replacement gear dimensions 2153
roll angle 2032
root diameter 2032
selection of involute gear milling cutter 2052
shapers, root diameters of gears cut on 2042
size factor 2077
size, checking 2125–2143
specifications 2067
spur gear 2033–2067
external 2029
internal 2029, 2074–2075
standard normal diametral pitches 2076
steels for 2144, 2146
straight bevel 2029

Copyright 2004, Industrial Press, Inc., New York, NY

Gears and gearing *(continued)*
surface condition factor 2078
tangent plane 2032
tangential force 2077
teeth invention 2152
terms used in gear specifications 2065
through hardening steels for 2144
tip relief 2032
tooth caliper, vernier 2051
tooth face 2032
tooth profile
deburring 1456
producing a radius 1456
tooth proportions
comparative sizes and shape of 2033
fine-pitch involute spur and helical gears 2039
for enlarging fine-pitch pinions 2056–2057
tooth stiffness constants 2078
tooth surface 2032
tooth thickness allowance for shaving 2045
tooth-to-tooth composite error 2073
total composite error 2073
total face width 2032
transverse load distribution factor 2078
transverse plane 2032
trochoid curve 2032
true involute form diameter 2032, 2061
undercut 2032
limit for hobbed involute gears 2061
Van Keuren wire diameter 2133
wear equalizing 2145
welding factor 2079
whole depth 2032
wire diameter 2133
work hardening factor 2077–2078
working depth 2032
worm gears 2029, 2095–2098
zerol bevel 2029
zone factor 2077–2078
Gears, metric thread on inch lead screw 1948
General purpose Acme threads 1825–1832
data 1827
designation 1826–1827
form 1825, 1827, 1834
formulas for diameters 1827
limiting dimensions 1826–1830, 1834
pitch diameter allowances 1827
thread form 1827, 1834
Generator shaft keys and keyseats 2368
Geneva wheel 163
Geometric dimensioning and tolerancing 630, 634
datum
feature 634
identifier 634
plane 635
reference frame 635
Geometric dimensioning and tolerancing *(continued)*
datum
simulator 635
target 635
target areas 640
target lines 640
definitions 634
degrees of freedom 635
dimension
basic 636
origin 636
reference 636
feature 636
feature control frame 636
free state 642
least material condition (LMC) 636
material removal required or prohibited 732
maximum material condition (MMC) 637
mean line 726
modifiers 640
position 637
positional tolerance 640
projected tolerance zone 640
regardless of feature size (RFS) 637
relation of surface roughness to tolerances 729
size, actual 637
size, feature of 637
tangent plane 642
Geometrical
constructions 54–58
dimensioning and tolerancing 630
progression 36–38
propositions 49–53
symbols for drawings 633
symbols, comparison of ANSI and ISO 633
German standard
gear tooth 2121
screw threads, metric 1824
Gib-head keys 2366
Gibi 2546
Gleason system, Zerol bevel gears 2082
Glue, pattern 1368
GMAW
(gas metal arc welding) 1390
welding carbon steels 1393
welding stainless steel 1393
GO and NOT GO gages 2175
Gold, plating 1468
Goodman diagram 206–207
Gordon formula for columns 285, 287
Grade markings on bolts and nuts
ASTM and SAE 1508
inch 1508
metric 1578
Grams
into ounces, avoirdupois 2571–2572

Copyright 2004, Industrial Press, Inc., New York, NY

Grams *(continued)*
per cubic centimeter into pounds per cubic inch 2573
Granite, strength 420
Graphical solution of force systems 145–149
Graphitic materials for bearings 2266
Gravitational system of measurement 142
Gravity 142
acceleration due to 142
center of, in various geometrical figures 225–231
die casting process 1367
force of 171
lubrication systems 2335
specific 407
gases 407
liquids 407–408
various substances 408
Gray cast iron 1360
Grease lubricants 2337
Grease lubrication 2340
Greek symbols and alphabet 2540
Green sand molding 1366
Green wood, weight per cubic feet 413
Grindability data 1166–1168, 1189–1190
Grindability of tool steels 1189–1193
Grinders spindles for portable 950
Grinding 1177
abrasive belt grinding 1230
abrasives 1177–1179
basic rules 1158
carbide materials, diamond wheel 1173
carbide tools 971–974
cast iron 1170
centerless 1220–1222
centerless grinding troubles 1221–1222
ceramic materials, diamond wheel 1173
chip breakers 973–974
cost 1176
cutting forces 1164
cutting time formula 1114
cutting torque 1164
cylindrical 1212–1220
cylindrical grinding troubles 1216–1219
data selection including wheel life 1165
data, wheel life selection 1165
diamond wheel 971–973, 1173–1174, 1201–1207
ECT grinding 1159
equivalent diameter factor 1163
feeds 1158
finishing 1166
floor and bench stand 1229
fluids 1144
grindability groups 1166
grinding rules and data selection 1158
heat resistant alloys 1172
inconel 1172
internal centerless 1220
milling cutters 823

Grinding *(continued)*
minimum cost conditions 1161
mounted wheels and points 952
offhand grinding 1229
optimization planning 1176
optimum grinding data for roughing 1161
planing tools 756
plunge 1212
portable grinding 1229
power 1164
procedure to determine data 1168
ratio 1158
relative grindability 1167
rene 1172
rpm, various speeds and diameters 1211
screw threads 1957–1960
side feed, roughing and finishing 1166
silicon carbide wheels 971–973
spark-out time 1163
specific metal removal rates 1163
speeds 1163
spindles for portable tools 948
stainless steels 1169
surface 1222–1228
surface finish, Ra 1162
surface grinding troubles 1227
swing-frame 1229
terms and definitions 1167
tool steels 1170–1172
tools
carbide 971–973
twist drills 968–971
traverse 1212
unhardened steels 1169
user calibration of recommendations 1174
vertical and angle spindles 948
wheel life
cost 1176
grinding data relationship 1160
grinding ratio 1158
life vs. cost 1176
relationships and optimum grinding data 1160
wheel safety 1207–1211
handling 1207
inspection 1207
machine conditions 1207
mounting 1207
portable grinders 1210
safe operating speeds 1209–1211
speed conversion table 1211
speeds, maximum 1210
storage 1207
wheel safety grades 1178
wheels 1177–1200, 1207–1211
abrasive materials for 1177–1178
angles for eccentric type radial relief angles on milling cutters 828-829
bond properties 1178, 1227
CBN 1178, 1195, 1204

Copyright 2004, Industrial Press, Inc., New York, NY

Grinding *(continued)*
wheels
cubic boron nitride 1177, 1195
cutting fluids 1165
diamond 781
truing of 1196–1200
dressing and truing of 1196–1200
eccentric type 828
faces, shapes of 1188
finishing 1166
grades 1178
handling 1208
inspection 1208
markings, standard 1179–1180
mounted wheels and points
metric 954
mounting and safety 1207–1208
radial relief angle 828
roughing 1166
safe operating speeds 1165
selection of 1165, 1180–1200
sequence of markings 1179
shapes and sizes, standard 1180–1188
metric 1186–1187
side feed 1166
silicate bonding process 1227
single point truing diamonds 1200
storage 1208
structure 1178–1179
truing
diamond feeds 1199
diamond sizes 1199
dressing of 1196–1200
vitrified 1227
wheel markings 1179
work speed
and depth of cut selection 1159
in rough and finish grinding 1163
Grooved drive studs
dimensions 1681
hole sizes 1681
Grooved pins 1677
designation 1678
hole sizes 1678
lengths and sizes 1677
materials 1678, 1680
properties 1680
requirements 1678
standard sizes 1680
type 1679
Grooving and oil feeding of bearings 2229
Grooving insert holder 762–764
Ground thread tap, designations 918
GTAW (gas tungsten arc welding) 1409–1414
Guide bearings 2221, 2260
Guldinus or Pappus rules 59
Gutta percha, turning 1083
G-word, NC 1274–1278
Gyration, radius of 232
bar, small diameter 232
circular disk, thin 233
circular ring, thin flat 233
cone, frustum 234
cylinder, hollow 234
ellipsoid 235
flat plate, thin 232
hollow cylinder, thin 234
hollow sphere 235
paraboloid 235
parallelepiped 233
parallelogram 232
prism, rectangular 234
ring 232
sphere, hollow 235
spherical shell, thin 235
thin flat plate 232

H

H- and L-limits 916–917
Half circle
moment of inertia 241
radius of gyration 241
section modulus 241
Hand
expansion reamers 844
of flute helix 799
of milling cutter 797
reamers 832
taps 892
Hard facing 1420
austenitic high chromium irons 1421
austenitic manganese steels 1421
cobalt base alloys 1421
copper base alloys 1422
high speed steels 1420
materials 1420
nickel-chromium-boron alloys 1423
Hard rubber, machining 1156
Hardening 513–515
alloy steels 456
steel 503, 512, 515
flame 529
induction 529
temperatures
stainless steel 536–537
tool steels 515
test methods 508
tool steels 477
Hardmetals 773–783
carbonitride based 776
coated 778
ISO classifications 779
titanium carbide 776
tooling for wood and nonmetals 783
tungsten carbide 774–776
Hardness 507
aluminum alloys 575–583

Copyright 2004, Industrial Press, Inc., New York, NY

Hardness *(continued)*
bearings 2225
ceramics 415
cobalt alloys 418
copper alloys 417
copper-base powdered alloys 419
heat-treated steels 464–465
iron-base powdered alloys 419
magnesium alloys 588
nickel alloys 418
number
Brinell 552
Rockwell 552
steel 1363
O-ring 2502, 2504
plastics 416
powdered metal alloys 419
relation to tensile strength 551
scales
comparison 549–551
Rockwell 548
unhardness scales 552
stainless steel 418
steel 417
carbon and alloy 466–471
tool steels 488, 490–491, 497, 500
testing 547
Brinell 547
conversion errors, causes 551
conversion tables 550
correction for curvature 2325
durometer 551, 2505
Hultgren ball 547, 551
Keep's test 549
Mohs hardness scale 551
monotron 549
Rockwell 548, 550
scleroscope 548, 551
Turner's sclerometer 551
Vickers 548, 551
tungsten-base powdered alloys 419
Harmonic 166
Harvey grip thread 1891
Heat
absolute temperature and zero 2583
coefficients of radiation 402
coefficients of transmission 402
fahrenheit-celsius conversion 2583
freezing mixtures 403
ignition temperatures 403
latent 399
loss from uncovered steam pipes 400
mechanical equivalent 2583
power equivalents 2578
quantity measurement 2583
radiating capacity of bearings 2229, 2231
radiation coefficient 402
scales 2583
specific 399–400
temperature scales 2583
thermal energy 2583
Heat treating furnace
fluidized bed furnace 513
oven or box 512
pit type 512
pot type 512
retort 512
vacuum furnace 512
Heat treatment 503–547
alloy steel 533
carburizing temperatures 533
normalizing temperatures 533
tempering temperatures 533
carbon steels 532
molybdenum high speed steels 542
stainless steel 536–537
quenching medium 536–537
tempering temperatures 536–537
stainless steel temperatures 536–537
steel 449, 503–512, 515, 1363
annealing 450, 503, 507, 524
annealing temperatures 525
baths quenching 519
carburizing temperatures 526, 532
case hardening 526
cleaning work after case hardening 528
colors for tempering 522
cooling period 546
cooling subzero, to improve properties 546
cyanide hardening 527
decalescence point 503, 512
defects in hardening 517
flame hardening 529
furnaces 503, 511–512
hardening baths 517
hardening temperatures 503, 512, 515, 533
hardening, defects in 517
induction hardening 529–531
interrupted quenching 519
lead bath temperatures 516
liquid baths 516
nitriding 543
normalizing 450, 524, 526
temperatures 532
oil quenching 517
pack-hardening 527
pressure-spraying quenching 518
protective coatings for molybdenum steels 542
quenching 540
temperatures 533
quenching baths 517
recalescence point 503, 512
scale formation 517
spheroidizing 524, 526
stabilizing dimensions 545–546
strength and hardness of AISI steels 466–471
stress relieving 450
subzero treatments 546

Copyright 2004, Industrial Press, Inc., New York, NY

Heat treatment *(continued)*
steel
surface hardening 531
tanks for quenching baths 519
tempering 506, 521
temperatures 532
tempering period 546
time aging 545
water quenching 518
Hectares into acres 2563
Helical
end mills 809
gear, helix angle 1966
interpolation, NC 1284
milling, change gears 1965
wire screw thread inserts 1654
Helical gearing 2029, 2099–2114
addendum 2099
modifications 2077
backlash 2068
British Standard 2076
calculations 2099
center distance 2099
exact 2102
for enlarged 2111
change gears 2112
checking gear size 2134, 2139
cutter for milling 2108
data on drawings 2067
direction of thrust 2099
enlarged fine-pitch pinions 2108, 2110–2111
feed rate change 2113
fine pitch teeth 2110
formulas 2099, 2101–2105, 2107, 2110
helical overlap 2031
helix angles 2100, 2105
herringbone type 2114
hobbing 2112, 2114
involute form milling cutter 2109
lead accuracy 2113
lead of tooth 2099
machine
with differential 2113
without differential 2112
measurements using wires or balls 2139
milling the helical teeth 2109
minimum center distance 2105, 2107
normal tooth thickness 2039
pitch diameter 2099
pitch of cutter 2100
replacement gear dimensions 2155
shafts
at right angles 2103–2104
parallel 2101–2102
shafts at right angle 2106
specifications 2065
spur gear replacement by helical gears 2153, 2155
thrust 2099
Helical gearing *(continued)*
tooth proportions 2039
tooth thickness measurement 2139
troubleshooting 2114
wire diameter 2134
Helical milling
development of helix 1965
helix angle 1966
lead of ahelix 1965
Helical overlap 2031
Helix 1965
angle 1966, 2031
angle factor 2078
angles, screw threads 1763–1772
constructing 58
end mills with welden shanks 805
lead and diameter 1981–1982
lead and pitch radius 1982
lead angle 1966
lead for given angle 1977–1979
measurement of angle 1965
number of tooth 1982
Herringbone gearing 2114
failures 2114
Hertz stress 2031
Hexagon
area 65
distance across corners 74
moment of inertia 240
radius of gyration 240
section modulus 240
Highest point of single tooth contact (HPSTC) 2031, 2061
High-speed steels 488–490, 1010
annealing rehardening 540
as cutting tool materials 1010
cobalt 884–885
cobaltcrom 538
cooling period 546
cutters 826
drawing 540
hardening molybdenum 541
heat treatment 538
annealing 541
cutting efficiency 539
equipment 543
hardening temperatures 539
preheating tungsten 538
quenching
molybdenum 542
tungsten 539–540
subzero treatment 547
tempering molybdenum 542
time for through hardening 539
molybdenum 488, 493, 541–543
hardening 541
quenching straightening 540
tempering 540
tool 490
tungsten 490, 493, 538, 541
tungsten annealing 541

Copyright 2004, Industrial Press, Inc., New York, NY

High-strength, low-alloy (HSLA) steels *(see* HSLA steels*)*
Hob tip radius, maximum 2061
Hobs
change gears for relieving 1950
roller chain sprocket 2459–2460
tip radius, maximum 2061
worm gear 2095
Hoisting chain and wire rope 369, 386–391
Holders for NC, insert 758–764, 1310–1312
Hold-on or dolly bars for riveting 1483
Hole sizes, tapping 1935–1936
Holes
accuracy of drilled 884
coordinate dimension factors for jig boring 993–1004
difficulties in reaming 840
for riveted joints 1478
for tapping 1925–1932
in glass, drilling 1065
sizes for self-tapping screws 1647
spacing of, on a jig borer 993–1004
Hollow
circle, moment of inertia 241
circle, radius of gyration 241
circle, section modulus 241
cylinder, radius of gyration 234
mills, feeds and speeds 1132
sphere, radius of gyration 235
Honing process 1233–1235
adjustments 1234–1235
carbide tools 973–974
rotative speeds in 1233–1235
stock removal, rate of 1233
tolerances 1235
Hooks, dimensions of crane 393
Horsepower 141
air compression 435
calculating by dynamometer 2360
chain transmission 2451–2455
converted into kilowatts 2578–2579
disk clutches 2350
drilling different materials 1090
dynamometer test 2359–2361
electric motor 2473
ratings 2466
equivalents 2578–2579
formulas 178
friction wheels 2360–2362
gearing 2149–2150
hour equivalents 2578
machining 1084–1090
nonmetallic gears 2149–2150
planing and shaping 1084–1088
roller chains 2451–2455
set-screw transmitting capacity 1637
shafting 299–301
spade drilling 1080, 1090–1091
to compress air 432–435
torque equivalent 299–301
Horsepower *(continued)*
V-belt drives 2391
water at a given head 423
Hose connection screw threads 1872–1876
ANSI Standards 1872
basic dimension 1875
tolerances 1875
Hot-working, tool steels for 491
HSLA steels 442–443
application 462
chemical compositions 463
composition 462
elongation 463
formability 463
properties 462
tensile strength 463
toughness 463
weldability 463
yield strength 463
Hunting tooth ratio 2098
Hydrant screw thread 1874–1876
Hydrometer, Baumé's, and specific gravity 408
Hyperbola
area 68
area construction 58
eccentricity 47
foci 47
general equation 47
major and minor axis 47
Hypocycloidal curves, areas 61
Hypoid gears 2029, 2080, 2082–2083
applications of 2083
Hypotenuse 88
Hysteresis 313

I

I-beam
aluminum 2518
standard structural steel 2513
structural
moment of inertia 2509–2513
section modulus 2509–2513
steel 2509
weight per foot 2509–2513
Idler gears 2009
IGES (initial graphics exchange specification) 1322–1324
Ignition temperature 403
Impact force of 175
Impact strength, Izod
carbon and alloy steels 466–467
plastics 416
Impulse 176–178
angular momentum 177
Inch
decimals of, into millimeters 2556–2557
into centimeter and millimeter 2553

Copyright 2004, Industrial Press, Inc., New York, NY

Inch *(continued)*
millimeters into decimals of 3, 2552, 2558–2559
Inclined plane 161, 171
force for moving body on 161
forces on 160
motion on 171
Inconel metals 589–590
Incremental programming, NC 1277
Index plates, one hole moves of angular values 1991
Indexable
carbide inserts 756
insert holder
boring 762–764
chamfering 762–764
end cutting edge angle 761
facing 762–764
grooving 762–764
identification system 757, 759
insert shape 761
lead angle 761
NC 758–764, 1310–1312
planing 762–764
plunge angle 762
rake angle 761
selection 761
shank sizes 759
shape 762
tracing 762–764
turning and backfacing 762–764
turning and facing 762–764
Indexing
angular 1990–2007
block or multiple 2021–2022
Brown and Sharpe milling machine 2011–2016
compound 1984–1989
compound gearing ratio 2009
differential 2008
ratio of gearing 2008
gear ratio
finding 2009
head angular position for
milling end mills and angular cutters 821–824
head worm wheel with 64 teeth 2023
hole circles 1983
milling machine 1983–1989
movements 1985–2007, 2009–2020, 2023–2024
number of holes 1983
ratio of gearing 2009
reamer teeth for irregular spacing 833
simple 1983–1989, 2011–2016
simple and differential 2011–2016
smaller angles 2007
tables 2021
Indicator drop method 829
Induction
annealing 530
brazing 1387
hardening 510, 529–531
equipment 529
gear teeth 531
normalizing 530
Inertia 141
electric motor 2474
moment of 237–259
polar 248–249
Initial graphics exchange specification (IGES), NC 1322–1324
Injection molding, metal 1374
Insert radius compensation 1310
Inserts
hardmetal materials 773–783
holders for NC 758–764, 1310–1312
indexable 756–764, 1310–1312
radius compensation, NC 1310–1312
screw thread 1654
self-tapping screw 1654
throw away carbide 773
Inspection methods 692
Instrument maker's thread system 1884
Integration of functions 34
Interest 125–128
compound 125
finding unknown rate 127
nominal vs. effective 126
simple 125
Interference 2031
Interference fit threads 1877–1882
allowances 1881
British Standard 1581
change in diameter 1882
coarse threads 1881
design and application data 1878
designation symbols 1878
dimensions 1879
driving speed 1880
driving torque and length of engagement relation 1881
engagement lengths 1880
interferences 1878, 1880
lead and angle variations 1882
lubrication 1880
materials for 1880
profile 1877
spur gearing 2050, 2052
surface roughness 1881
thread dimensions 1879
tolerances for pitch diameter 1881
torques 1880
variation in axial lead 1882
Interferometer 1248
Internal diameter 2031
Internal gears 2031
spur 2029, 2074
International System (SI) units 2544

Copyright 2004, Industrial Press, Inc., New York, NY

Interpolation 110, 112
circular, NC 1283–1284
helical and parabolic, NC 1284
linear, NC 1282
Interrupted quenching 518–519
Inverse
and direct proportions combined 7
of a matrix 122
ratio or reciprocal 5
Investment
casting 1374
design 1376
making procedure 1375
milling cutters 1377
materials 1375
Investment casting alloy
elongation 417–418
hardness 417–418
tensile strength 417–418
yield strength 417–418
Involute 2031
constructing 58
curve properties 2035
curve, properties 2033
functions 103–107
gear cutters, formed type 2052, 2074
serrations 2156
true form diameter in gears 2032
Involute splines 2031, 2156, 2159–2177
American National Standard 2156
application factor 2171
basic dimension 2162
basic rack profile 2181
bursting stress 2173
chamfers and fillets 2164, 2181
circular pitch 2157, 2162
classes of tolerances 2162
combinations 2167
combinations of types 2167
compressive stress at side teeth 2173
compressive stresses allowable 2172
crowning for misalignment 2173
diametral pitch 2158
dimensions, effective and actual 2177, 2179
drawing data 2167, 2169
effect of spline variations 2165
effective
and actual dimensions 2165–2166, 2175
clearance 2158
space width 2158
tooth thickness 2158
variation 2158, 2180
fatigue life factor 2172
fillet 2158
chamfers 2164, 2181
root splines 2158, 2164
fit classes 2162, 2177, 2181
flat root splines 2158, 2164

Involute splines *(continued)*
form circle 2159
form clearance 2159
form diameter 2159
formulas 2181
basic dimension 2161, 2177, 2179
2-pin measurement 2175
fretting damage 2174
inspection
methods 2174
types of gages 2175
with gages 2175
interchangeability 2167
internal splines 2159, 2167
lead variations 2159, 2165
length of engagement 2159
length of splines 2170
load distribution factors 2171
machining tolerance 2159, 2181
major circle 2159
major diameter fit 2159, 2162
manufacturing 2187
maximum
actual space width 2167
actual tooth thickness 2166
effective space width 2167
effective tooth thickness 2166
metric module 2176–2181
milling cutter 824
minimum
actual space width 2166
actual tooth thickness 2167
effective space width 2166
effective tooth thickness 2167
minor circle 2159
minor diameter 2159
misalignment 2171
parallelism variation 2159
pin measurement of 2175
pitch 2159
circle 2159
diameter 2159
point 2159
pressure angle 2159
rack profiles 2180
reference dimensions 2167, 2169, 2181
shear stress
allowable 2172
at pitch diameter 2173
at the pitch diameter of teeth 2173
under roots of external teeth 2172
side fit 2162
sizes and lengths, estimating 2169–2170
space width and tooth thickness limits 2166, 2177
stub pitch 2159
symbols 2159–2160, 2167, 2177
tensile stresses allowable 2172
terms and definition 2157, 2177
tolerances 2162, 2177, 2180
tolerances and variations 2180

Copyright 2004, Industrial Press, Inc., New York, NY

Involute splines *(continued)*
tooth
numbers 2159, 2162
proportions 2159–2181
thickness limits 2166, 2180
thickness modification 2180
torque capacity formulas 2170
total index variation 2159
total tolerance 2159
types and classes of fits 2162
variations 2165, 2180
allowance 2159, 2165
eccentricity 2165
effect of 2180
effect of profile 2165
lead 2165
types of 2157, 2180
wear life factors, flexible splines 2172
width and tooth thickness 2180
Iron
and copper-base sintered bearings 2268
castings 1360
coloring 1463
copper-base sintered bearings 2267
Iron-base powdered alloys 419
density 419
elongation 419
hardness 419
rupture strength 419
ultimate strength 419
yield strength 419
I-section
moment of inertia 242
radius of gyration 242
section modulus 242
ISO Standard
drawing symbols, compared with ANSI 633
geometric dimensioning and tolerancing 630
metric
British Standard taps 922–925
grade markings on bolts 1578
hexagon bolts, screws and nuts 1574
limits and fits, British Standard 679
thread 1805, 1823
thread system, miniature screw threads 1814
surface finish 738
surface parameter symbols 739
surface texture symbology 741
washers, compared with ANSI 1568
ISO surface finish 738
Isosceles triangle 88
Isothermal
expansion, compression of air 431
quenching 521
Izod impact strength
carbon and alloy steels 466–467
plastics 416

J

Jacobs tapers 939
Jam nuts, standard 1513, 1519–1520
metric 1567
Jarno taper 926, 937
Jig
boring 986–988
hole coordinate dimension factors for 993–1004
lengths of chords 990
transfer of tolerances 987
bushings 975–985
definitions 975
designation system for 985
fixed type wearing bushings 981
head type liner bushings 979, 983
headless type liner bushings 979, 982
headless type press fit 977
locking mechanisms for 984
materials 975
plate thickness 985
press fit wearing bushings 976, 979
slip type 980
fixture 975–985
fixture definition 985
Jobbers reamers 845
drills 856–862
Johnson, J. B., column formula 288–289
Joints
plastics pipe 2532–2534
riveted 1478
toggle 164
universal 2348
Journal bearing *(see* Bearings: journal*)*

K

Karat 2571
Keep's hardness test 549
Kelvin, degrees 2583
Key and spline sizes and lengths 2169
Keying bearings 2223
Keys and bits, hexagon and spline 1630
Keys and keyseats 2363
alignment tolerances 2364
ANSI Standard 2363
British Standards 2374, 2387
keyways and keybars 2381–2384
rectangular parallel keys 2381–2384
woodruff keys and keyways 2385–2386
chamfered keys 2368, 2374
cotters 2372, 2374
depth control values 2364
depth of keyseat 2374
depths for milling keyseats 2374
dimensions and tolerances 2380

Copyright 2004, Industrial Press, Inc., New York, NY

Keys and keyseats *(continued)*
effect on shaft strength 305
estimating key sizes 2169
filleted keyseats 2368, 2374
fitting 2367
gib-head keys 2366, 2379, 2383–2384, 2387
keyseat milling cutters, Woodruff 820
keyseats, depth of 2364, 2374
metric 2374
metric keys length 2376, 2380
milling cutters and arbors 819
parallel and taper 2364, 2367, 2380
parallel keys 2376
plain 2366, 2383–2384, 2387
preferred length 2380
rectangular parallel keys 2376, 2378
rectangular taper keys 2377, 2379–2380
set screws for keys 2368
shaft diameter 2363
size vs. shaft diameter 2363, 2374
square parallel keys 2376, 2378
square taper keys 2377, 2379
strength considerations for shafts 305
taper key tolerances 2380
taper keys 2379–2380
tolerances 2366, 2368–2370
transmission chain 2446
woodruff keys and keyseats 2368, 2380, 2385
Kibi 2546
Kilogram calorie 2583
Kilograms
into pounds 2571–2572
per cubic meter into pounds per cubic foot 2573
per square centimeter into pounds per square inch 2575
per square meter into pounds per square foot 2575
per square meter into pounds per square inch 2575
Kilometers into miles 2562
Kilopascals into pounds per square inch 2575
Kilowatt
hour equivalents 2578
into horsepower 2579
power required for machining 1084
Kinematics and kinetics 141
Kinetic energy 173–175
Kingsbury thrust bearing 2242
Kirchoff
current law 124
voltage law 124
K-Monel, machining 1155
Knee tools, speeds and feeds 1132
Knoop hardness numbers 549
Knuckle joints 2349
proportions 2350
Knurls and knurling 1240–1244
automatic screw machines 1131–1136
concave 1244
diagonal teeth 1240
diametral pitch knurls 1240–1244
dies marking 1244
flat tools 1242
formulas 1242
lathe knurls 1240
revolutions required for top knurling 1131
sizes, preferred 1240
speeds and feeds 1132
straight teeth 1240
tools 1241
tracking correction 1240
work diameter tolerances 1243–1244

L

Lag screws and threads 1517–1518
metric 1545
Lame's formula for internal pressure 295
Land gear tooth drill 854
Laps and lapping 1235–1239
abrasives 1238
carbide tools 973–974
charging laps 1237
cutting properties 1238
cutting qualities 1238
flat surfaces 1236
grading abrasives for 1236
grading diamond dust for 1237
lubricants 1238
materials for 1235–1236
pressures 1239
rotary diamond 1237
tests 1239
wear 1238
wet and dry 1239
Lasers 1443–1455
beam focusing 1443–1444
beams 1443
cladding 1454
cutting metal with 1447
cut edge roughness 1448
cutting speeds 1451
heat-affected zone 1449–1450
kerf widths 1448
narrow kerf 1448
cutting nonmetals 1449–1450
direct drilling 1453
drilling 1453
drilling rates 1454
drilling theory 1453
hardening rates 1454
heat affected zones 1449

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX

Lasers *(continued)*
heat treatment 1454
industrial applications 1445
industrial systems 1445
light 1443
marking 1455
mask marking 1455
materials 1446, 1454
nonmetals cutting rates 1451
safety 1446
scanned beam marking 1455
thermal properties 1447
trepanning 1454
types of industrial 1445
welding
conduction 1451
deep penetration keyhole 1451
joint design 1451–1452
processing gas 1452
helium 1453
rates 1451–1452
theory 1451
Latent heat 399
Lathe
change gears 1946
fixtures, balancing 201–202
screw constant 1946
Law of
cosines 89
sines 89
Lay symbols 735
Lead
angle of cutting tools 749
inserts 1310
angle of screw thread 1965
tables for 1763–1772, 1827, 1836, 1846, 1908
of helix
change gears and angles for milling 1980–1981
find change gears for milling 1967–1976
for given angles 1977–1979, 1982
of milling machine 1964
of screw thread 1893, 1965
side cutting edge 754
Lead and lead alloys
element 398
lead bath 516
tempering in 523
melting temperatures 398, 523
solder 1380
Lead-base alloys, die casting 1373
Leaded-bronze bearings 2261–2264
Least material condition (LMC) 636
Length
differences due to temperature 405
engagement of screw thread 1510
of action 2031
of engagement 1935
Length *(continued)*
of rivets for forming heads 1483
units and conversion of 2549–2562
Letter
addresses, NC 1272
symbols for mechanics 2543
Levers 159
Light
duty Belts and pulleys
V-belts 2410–2417
laser 1443
metals
drilling, reaming, and threading 1070
milling 1044
turning 1038
wave interference bands, measuring surface variations with 723
Limestone
cutting speed for 1083
strength 420
Limit
elastic 204
endurance 205
proportional 203–204
Limits and fits
actual size 651
allowance 651
ANSI Standard preferred metric 656
basic size 651–652, 665, 680
British Standard for holes and shafts 680–688
cylindrical fits, ANSI Standard 651–677
definitions 656
design size 651
deviations for holes 687
deviations for shafts 685
dimension 651
gagemakers tolerance 678
gages, plain 646, 678
gages, thread 1914
graphical representation 656–657
indicating on drawings 645
maximum material condition 652
metric screw threads 1787
minimum material condition 652
screw thread gages 1914
size, nominal 651
symbols 667
tolerance 651, 666
bilateral 652
unilateral 652
tolerance limit 652
tolerances 652, 680
woodruff keys 2369–2370
Limits, upper and lower (UL and LL) 637
Line
angle between two 42
conventions for drawings 630
distance between point 39, 42
distance to external point 40
equation of 40

Copyright 2004, Industrial Press, Inc., New York, NY

Line *(continued)*
geometry of 51
intermediate points on 39
of action 2031
parallel 41
perpendicular 41
slope of 40
Linear
coefficient of expansion 402, 405–406
metals 402–404
pipe material
copper 427
FRP 427
PP & PVDF 427
PVC 427
steel 427
plastics 402
deflection of shafting 302
interpolation, NC 1282
Lines, points, circles (APT) NC 1294–1299
Liquid
baths, heating steel in 516
depth to volume conversion 61–62
specific gravity 407
Liters
into cubic feet 2568
into U.S. gallons 2566
Lloyd and lloyd thread 1892
Load
rating, static, bearings 2319
ratings and fatigue life, bearings 2307–2323
Lobing 721
Lock nut pipe thread 1892
Lock nuts, ball and roller bearing 2299
Lock wire proceedure 1511
Locknuts, ball and roller bearing 2299
shafts for 2300–2301
Lockwashers
ANSI Standard 1536–1539
ball and roller bearing 2298
British Standard, metric
plain 1584–1586
spring 1582–1584
spring type 1536–1537
tooth lock 1538
tooth type 1536, 1538–1539
Logarithms 111–118
common 111, 115–116
extracting roots by 114
mantissa 111
natural 111, 113, 117–118
obtaining powers by 113
tables 115–118
common 115–116
natural 117–118
using calculator to find 113
Long angle lathe file 965
Low pressure casting 1367
Löwenherz thread 1849
L-section
moment of inertia 246
radius of gyration 246
section modulus 246
Lubricants 2332
application of oils 2333
bearings 2227–2229, 2339
cutting 1143–1148
density 2332
dynamic viscosity coefficient 2345
electric motors 2478
grease 2227, 2337
oil mist 2336
oil types 2333
operating temperature 2229
pressure-viscosity coefficient 2345
presswork 1330
solid films 2339
specific gravity 2334
temperature vs. viscosity 2228, 2334
viscosity 2332, 2340
Lubrication 2226–2229
aerodynamic 2342
analysis 2239
analysis, journal bearings 2233
anti-friction bearing 2339
centralized systems 2335
chain 2463
density 2332
drip -feed 2335
elastohydrodynamic 2342
film thickness 2239
films 2339
gravity systems 2335
grease consistancy classifications 2337
greases 2228, 2337, 2340
hydrodynamic flow 2238
method 2304
motors 2478
oil bath 2227
oil, application 2334
oils 2336, 2340
plain bearings 2226
pressure flow 2238
relubricating with grease 2338
roller chain 2463
selection for bearings 2227
solid films 2339
specific gravity 2334
system, wiper type 2336
temperature effects on grease 2338
total flow 2238
viscosity 2228, 2332, 2341
pressure relationship 2345
waste pack 2227
wick-feed operation 2335
wicks and wick feeds 2335
Lumber, sizes of sawn 414

Copyright 2004, Industrial Press, Inc., New York, NY

M

Machinability
copper alloys 556–568
of wood 413
Machine
accuracy, effect of on part tolerances 1249
countersinks 839
cutting time formula 1114
elements, subjected to compressive loads 286
nuts coating 1605
screw coating 1605
screw nuts 1614
screw taps 892, 903–913
settings costs 1113
settings economy 1113
tool
accuracy 1245
efficiency 1088
repeatability 1245
resolution 1245
Machine screws
ANSI Standard 1587–1604
binding head 1595
body diameter 1588
British Metric 1605, 1617
British Standard 1613–1614
British Unified 1614–1616
BSW and BSF 1605, 1610, 1617
cheese head 1612
chesse head screw 1612, 1615
clearance holes, metric 1604
countersunk head 1589, 1598–1599, 1609
countersunk head screw 1614
cross recesses 1596
designation 1588, 1601
diameter of body 1601
diameter of unthreaded shank 1606
end of screws 1609
fillister head 1593
flange head metric 1602
flat head 1588–1590, 1598
header points for metric 1593–1594, 1601
header points for threading 1594–1595
hex and hex flange 1602
hexagon head screw 1591, 1615
hexagon nuts 1587
hexagon washer head 1590
length of thread 1606
lengths of thread 1601, 1606
metric countersunk 1597, 1599
metric recessed countersunk head 1597
metric thread lengths 1597
metric, ANSI standard 1596–1604
Machine screws *(continued)*
mushroom head screw 1615
nuts for 1587
oval head 1593–1595, 1599
pan head screw 1592, 1600, 1611, 1615
radius under the head 1606
recessed flat head 1598
recessed pan head 1600
round head screw 1596, 1614
slotted and crosses 1598, 1600
slotted countersunk head 1589, 1608
slotted pan head 1611
slotted, recessed 1599
square nuts 1587
tap and clearance drills 1925–1932, 1934, 1938
taps for 892, 903–913
thread 1597, 1606
truss head 1591
washerhead 1590
washers for 1532–1537, 1584–1586
Machine tool
lathe, change gears for fractional ratios 1947
motor types 2476–2477
Machining
aluminum 1153
bearings 2225
copper alloys 1156
economy
chip thickness 1123, 1125
depth of cut 1123, 1125
high speed 1122
high speed milling 1129
formica 1156
hard rubber 1156
magnesium 1154–1155
micarta 1157
monel and nickel alloys 1155–1156
noise 1325
nonferrous metals 1153–1156
power constants 1084–1085
power factors
chisel-edge 1091
drill diameters 1091
feeds 1085, 1092
machine tool efficiency 1088
metal removal rates 1088
tool wear 1085
work materials 1090
power, estimating 1084–1091
unit horsepower for 1080, 1084–1085, 1089
processes, ANSI Standard tolerance grade relationships 652, 654, 679
speeds and feeds *(see* Speeds and feeds*)*
tolerances and variations 2180
ultrasonic 1157
zinc alloy die castings 1155
Macro, NC 1286–1287

Copyright 2004, Industrial Press, Inc., New York, NY

Magnesium alloys 586–588, 1372
applications 586
bearing strength 588
coloring 1464
compositions 587
compressive strength 588
cutting fluids for 1148, 1154–1155
designations 586
die casting 1372
elongation 588
extruded bars 587
machining 1154–1155
mechanical properties 588
plate 587
pressure die casting 587
properties 588
sand and permanent mold 587
shear strength 588
sheet 587
soldering of 1382
tensile strength 588
yield strength 588
Magnesium, coating 1466
Magnetic clutches 2352–2353
Malleable
cast iron 1361
iron castings 1361
Iron Research Institute 1369
strength 1361
Manganese
bronze castings 558
gearing material 2147
steel 446–447
Manganese-bronze castings 558
Manila rope, strength 387, 391
Mantissa, logarithm 111
Manual data input, NC 1269
Manufacturers' standard gage for sheet steel 2522
Manufacturing cell, flexible, NC 1264
module 1264
system 1264
Marble turning 1083
Martempering 521
Martensite 511
Mass 141–143
units and conversion of 2571–2573
Materials
disc spring 355
mechanical properties of 203–204
spring, disc 355
Mathematical
constants, frequently used 16
signs and abbreviations 2542
Matrix 119–122
addition 119
adjoint 121
cofactors 121
column 119
determination 120
Matrix *(continued)*
diagonal 119
identity 119
inverse 122
minors 121
multiplication 119
rank 122
row 119
simultaneous equations 122
singular 122
square 119–120
subtraction 119
zero 119
Maximum
bending load, wood 412
material condition (MMC) 637
temperature, plastics 416
MBEC bearing tolerances 2263
M-codes (M-words), NC 1278
Mean positional deviation 1245–1248
Measurement of backlash 2071
Measuring
angles with sine-bar 695–705
buttress thread 1910
compound angles 108–110
dovetail slides 713
gear size 2125–2143
instruments and gaging methods 692
over pins
bolt circle 717
gear size 2125–2143
splines 2175
over pins, bolt circle 717
pitch diameter
thread ring gages 1911
three wire method 1900
radius or arc, over rolls 717–718
tapers 698
center distance 716
diameter 716
threads
American standard 1899–1901
buttress 1910–1911
taper screw 1909
tapered 1909
using micrometer 1893
using screw thread gage 1910
using three-wire method 1893, 1910
Whitworth 1901
V-shaped groove, over pins 717
with light-wave interference bands 723
with micrometer 694–695, 1893
with vernier 692–693
Measuring screw threads
Acme thread 1899
Acme thread thickness 1905
ball point micrometer 1894
buckingham involute helicoid formula 1903
buttress thread 1899, 1910
contact pressure, measurement 1897

Copyright 2004, Industrial Press, Inc., New York, NY

Measuring screw threads *(continued)*
formula for checking pitch diameter 1899
formula to taper pipe threads 1909
formula, three wire method 1898
helical gear formula 1903
lowenherz 1899
pipe thread 1899
pitch diameter equivalent 1909
profiles 1895
three wire method 1897
Acme threads 1905, 1907
buttress thread 1910
checking thickness of Acme thread 1905
stub Acme threads 1905, 1907
testing angle of thread 1906
wire diameters and constants 1907
wire sizes 1906
V thread 1899
Whitworth 1899, 1901
wire accuracy 1897
wire diameter 1910
wire sizes for checking pitch diameters 1896
worm thread 1899
Mebi 2546
Mechanical equivalent of heat 2583
Mechanical properties
aluminum alloys 583
bolts, inch sizes 1508–1509
bolts, metric sizes 1540
ceramics 415
copper 569
magnesium 586–588
nickel 589–590
plastics 416, 596
powdered metal alloys 419
spring wire 421
stainless steels 472–473
steel 474
titanium 589, 591
tool steels 475
various materials 203–204
wood 411–412
Mechanics of materials 141
acceleration 169, 171
due to gravity, g 142
algebraic solution of force systems 145, 148–156
angular
impulse 177
momentum 177
velocity 167, 169
center
and radius of oscillation 235
of gravity 225–231, 235
of percussion 235
centrifugal force 179–182
calculating 180
couples 147–148
Mechanics of materials *(continued)*
differential pulley 163
dynamics 141
energy 173–174
flywheels 183, 194
force 145, 148–149
force of a blow 175
graphical solution of force systems 145–149
impulse and momentum 176–178
angular 177
inclined plane 161, 171
kinetic energy 173–175
levers 159
linear velocity 167
metric SI units 141–145
moment of inertia 236–252
momentum 176–178
Newton's laws 171
pendulums 165–166
potential energy 173–174
pound force 142
power 178–179
pulleys 162
radius of gyration 232–235
radius of oscillation 235
scalar and vector quantities 145
screw 163
SI metric units 141–145
statics 141
toggle joints 164
torque 172
units 142
vectors 145
velocity, angular 167–170
velocity, linear 167–168
wedge 161
wheels 162
work 174, 178–179
and energy relation 174
and power formulas 178–179
performed by forces and couples 174
Melting points
alloys of copper and zinc 1382–1383
alloys of lead and tin 1380
aluminum 403
brazing alloys 1382–1385
cast iron 404
chemical elements 398
copper alloys 403–404
solder 1380
stainless steels 404
titanium alloys 404
Metal
alumimium alloys 403
balls, standard 2323–2331
bonded grinding wheels 971–972, 1178
casting 1365
coatings
conversion coatings 1462–1464
surface coatings 1464–1471

Copyright 2004, Industrial Press, Inc., New York, NY

Metal *(continued)*
coloring 1462–1464
etching 1461–1464
foundry patterns 1369
identification 441, 551
injection molding 1374
numbering systems for 440–449
patterns 1369
plasma welding 1414–1416
removal rate 1088, 1163
slitting saws 801
spraying process 1472
temperature effect on strength 421
working
fluids occupational exposure 1149–1152
working application 1150
working fluids 1149–1150
Metal balls
ordering specification 2324
preferred gages 2325
tolerances 2325
Metal washers
bright 1584
metric series 1584–1585
Metallography 534
Metallurgy, powder 1379
Meters into feet 2562
Metric
basic sizes, British Standard preferred 690
bolts and screws, British Standard clearance holes for 1938
conversion factors 2553
dimensions on drawings 735
dowel pins, British Standard 1668–1669
drawings, scales 736
fasteners
ANSI hex nuts 1563
ANSI nut thread series 1563
bolts and screws
bolt clearance holes 1556
bolt designation 1551
bolt thread lengths 1551
bolt thread series 1556
cap screws 1553, 1557–1559
clearance holes 1558
countersink 1557
diameter-length combinations 1552, 1554
drill and counterbore sizes 1557
drilled head dimensions 1558
hex flange screws 1553
hex screws 1553
hex structural bolts 1554
identification symbols 1551
neck bolts 1554, 1558
socket head cap screws 1555
socket head neck screws 1558
thread length 1551–1552

Metric *(continued)*
fasteners
hex structural bolts 1549
nuts 1564
ANSI Standard 1562
bearing surfaces 1561
materials 1561
mechanical properties 1561
heavy hex structural bolts 1549
hex bolts 1550
inch vernier, dual 693–694
International System of Units (SI) 2544–2546
ISO limits and fits, British Standard 679
keys and keyways, British Standard 2374–2380
micrometer, reading 694–695
module, gear cutter 2052
gear teeth 2121–2124
round head square neck bolts 1547–1548
screw threads
aerospace screws, bolts and nuts 1805
basic profile 1727, 1788
crest diameter tolerance 1819
design profiles 1817
designation 1817–1818
diameter pitch combinations 1804–1805, 1823
dimensional effect of coating 1793
fits 1788
fundamental deviation 1790, 1818
length of thread engagement 1791, 1817
lengths of engagement 1819–1822
limiting dimensions formula 1793
limits and fits 1787
limits and tolerance 1819–1822
M crest 1784
M profile 1784
external thread 1784
internal thread 1784
M profile designations 1790
minor diameter tolerances 1790
MJ profile
designations 1807
symbols 1807
root form 1784
tolerance system 1790
tolerances of external threads 1795, 1797–1798
tolerances of pitch -diameter 1795
series British ISO
hexagon bolts, nuts, and screws 1574
machine screws and nuts 1605–1613
metal washers 1584–1586
spring washers 1582–1584
taps 922–925
SI units, factors and prefixes 2546
sizes, preferred for flat metal products 2523
systems of measurement 2544

Copyright 2004, Industrial Press, Inc., New York, NY

Metric *(continued)*
threads, British (ISO) 1805, 1814, 1823
threads, SI 1857
twist drills, ANSI 854–873
vernier, reading 693
washers, plain, ANSI 1566, 1568
Metric system (SI) 141–142
base units 143
in mechanics calculations 141–145
in strength of materials calculations 203, 213–215, 218, 221–224, 232, 236–237, 260, 273, 277–278, 280–281, 283–284, 286, 293–297, 300–302, 304–306
Micarta, machining 1157
Microinch 2549
into micrometers (microns) 2560–2561
Micrometer
into microinches 2560–2561
reading 694–695
screw thread 1893
Microprocessor 1258–1259
Microscope screw thread 1885–1889
Mil 2549
Miles into kilometers 2562
Military plating specifications 1464–1471
Mill or saw files 963
Millimeters
hundreds of, into inches 2553
into inches 3, 2552–2553, 2558–2559
thousandths of an inch, into 2556–2557
Milling
angular 802, 808
cam 2212
change gears for helical or spiral 1964–1982
chip geometry 1123
cost 1122
cutters, hollow 1132
depth of cut 1056–1058
economy 1129
feeds for
cemented carbide cutters 1044–1053
high-speed steel cutters 1054
in inches per tooth for cemented carbide cutters 1044–1053
helical, change gears for different leads 1964–1982
horsepower for 1082–1090
lead angle 1056, 1058
machine tool shanks 1313
short lead 1965
speed adjustment factors 1056–1058
speeds and feeds
aluminum alloys 1044
automatic screw machine 1132
copper alloys 1037, 1055
ferrous cast metals 1052–1053
light metals 1044
metal slitting (saws) 801, 1043

Milling *(continued)*
speeds and feeds
plain carbon and alloy steels 1045–1048
stainless steels 1050–1051
titanium and titanium alloys 1038
tool steels 1049–1050
thread 1962–1963
Milling cutters 796–831
ANSI Standard 797–820
arbor keys and keyways 819
arbor type 815
bevel gear 817, 2089–2090
casting 1377
clearance angles 796, 825
concave and convex 815
corner rounding 800, 815
double angle 802
eccentric type radial relief 826
end mills 804–814
medium helix 813
stub length 813
terminology 803
with weldon shanks 813
gear 816–817
grinding or sharpening 823–831
hand of
cut 797–798
cutter 797
flute helix 799
rotation 798
helical gear 2109
high speed steel 807
indicator drop methods of checking relief and rake angles 826
keys and keyways 819
keyseat 820
metal slitting (saws) 801
mounting method 797
multiple flute 809
number of teeth 796
peripheral teeth 827
pitch diameter 2109
plain and ball end 810
radial relief angle 827
rake angles 796, 826
relief on cutting edges 797
relieved corner rounding cutters 800
roller chain sprocket 817–818
selection of 796
setting angles for milling teeth in 821–824
sharpening wheels 824
shell mills 803
single angle 802, 808–809
sintered carbide 826
speeds and feeds for sharpening 825
spline shaft 824
spur gear 816, 2052
taper and weldon shanks 800
teeth, clearance angles 825

Copyright 2004, Industrial Press, Inc., New York, NY

Milling cutters *(continued)*
terminology 801
tool material 826
T-slot 800
weldon shanks 800, 812, 814
with taper shanks 809
Woodruff keyseats 820
Milling machine
Brown & Sharpe 2011
centering plugs 943
Cincinnati 2017–2020
cutters for 14.5-deg. pressure angle gears 816–817
draw-in bolt ends 943
indexing 1983–2024
lead of 1964
spindle noses 940–941, 944
tapers for 940
tool shanks 942
V-flange, NC 1313
Miner's law of linear damage 207
Miniature end mills 808–809
Miniature screw threads 1777–1781
basic thread form 1777
design thread form 1777–1778
formulas 1777
hole sizes 1936
root flats 1781
tapping 1936
tolerances and size 1780
Minors of a matrix 121
Minutes into decimals of a degree 96, 98
Miscelaneous threads aero-thread 1890
Miscellaneous functions, NC 1278
Mixed numbers 9
Module 2031
flexible manufacturing, NC 1264
splines, metric 2176–2181
system gearing 2121–2124
diametral pitch 2123
formulas 2121, 2123
rules 2123
Modulus of
creep or apparent 602
elasticity, E (Young's modulus) 204
for various materials 204
iron and steel 474
nickel-based alloy 312–313
nonferrous metals 554
of various materials 420
perforated metal 2521
plastics 416, 596–598, 601
spring materials 349–350
polar section 213, 248–249
rupture
powdered metal alloys 419
wood 411–412
secant 598
shear, G (rigidity) 204, 600
for various materials 204, 609
Modulus of *(continued)*
shear, G (rigidity)
in angular deflection formula 214
nonferrous metals 554
spring materials 350
Mol 410
Mold dispensable patterns 1375
Molding
green sand 1366
shell 1366
Molds, steels for permanent 497
Molecular weight 410
Molybdenum
gearing material 2147
high-speed steels
chemical composition 541
tool steels 488, 490–491, 493
steels, SAE 442
Moment and torque
in combined stresses 215
in simple stresses 213
unit conversion 2577–2578
Moment of a force 141, 147
Moments of inertia 236–252
angles, steel 2515–2517
built-up sections 237
channels, aluminum 2518
channels, steel 2514
circle 241
circular ring 242
cross-sections 238–247
ellipse 242
formulas for various sections 238–247
half circle 241
hollow circle 241
I or S shapes, steel 2513
I-beams, aluminum 2518
I-beams, steel 2509–2513
I-section 242
L-section 246
octagon 241
of complex areas 252
pipe 2360–2361
plane areas 236
polar 236, 248–252
cone, frustum 252
cylinder, hollow 250
ellipsoid 251
paraboloid 251
prism 250
pyramid 250
solid ring 251
sphere 250
spherical sector and segment 251
torus 251
rectangles 239, 253
round shafts, table for 254–259
structural channels 2514, 2518
trapezoid 240
triangle 240
T-section 245

Copyright 2004, Industrial Press, Inc., New York, NY

Moments of inertia *(continued)*
units conversion 2587
wide flange, steel 2509–2512
Z-section 247
Momentum 176–178
Monel metals, machining 1155
properties 589–590
Monotron for hardness testing 549
Morse
reamers for sockets 851
stub taper shanks 927–928
taper shank twist drill 881
tapers 926–937
Mortising wood 414
Motion
accelerated 169, 171–172
constant acceleration 167
constant velocity 167
force and work 171, 174
general formulas 167, 169
constant acceleration 167, 169
Newton
first law 171
second law 171
third law 171
on inclined plane 161, 171
rotary, formulas 169
uniformly accelerated 167
Motion control 2487
analog transducers 2495
closed loop system 2488–2489
control function 2490
features of controllers 2490
damping system response 2490
driving power 2490
electric motors 2492
electromechanical system 2491
electronic control 2500
feedback transducers 2494
gearing 2493
hydraulic fluids 2496
hydraulic pumps 2496
hydraulic systems 2497–2498
control systems 2496
electronic controls 2500
proportional control 2499
pumps and fluids 2495–2496
mechanical stiffness and vibration 2491
motor types 2488
open loop systems 2487
pneumatic systems 2496–2497, 2500
proportional system 2499
synchros and resolvers 2495
system application factors 2487
torsional vibration 2492
Motors, electric 2465, 2492
adjustable speed motors 2468
adjustable-voltage, shunt-wound 2469
alternating current 2469–2472
armature rotors 2479
Motors, electric *(continued)*
ball or roller bearings 2478
brushes 2478
characteristics 2468–2477
classes of standards 2465
commutators 2478
compound-wound 2469–2470
constant speed motors 2468
control 2488, 2492
current definitions 2465
DC motors 2476–2477
design letters 2465
direction of rotation 2467
frame sizes, standard 2465
high frequency induction 2471
horsepower requirements 2473
hydraulic, NC 2495–2496
induction motor 2470
injurious operating conditions 2475
inspection schedule 2478–2479
insulating materials 2475
locked rotor current and torque ratings 2466–2467
lubrication, proper 2478
maintaining and repairing 2478–2479
maintenance 2478
mechanical condition 2478
monthly inspection 2478
mounting dimensions, standard 2465
multiple speed induction 2471
multispeed motor 2468
NEMA 2465–2467
standards for 2465–2466
polyphase AC motor 2470
polyphase wound-rotor 2466
pull up torque 2466, 2468
rotation, standard direction 2467
rotors and armatures 2478
selection 2473–2474
shunt-wound 2469
single-phase motors characteristics 2472
space limitations 2474
speed reducer type 2473
speed requirements 2473
squirrel cage induction 2469–2470
squirrel cage rotors 2479
stepper, NC 2493
synchronous motor 2470
temperature effects 2475
torque and inertia requirements 2473
torque definitions 2467
type, dc and ac 2468, 2492
types and characteristics for different applications 2476–2477, 2492
variable speed 2467–2468
weekly inspection 2478
windings 2478
wound rotor induction 2471
wound rotor type 2470
Mounted wheels and points 952–954
Mounting bearings 2294

Copyright 2004, Industrial Press, Inc., New York, NY

Multiple or block indexing 2021–2022
Multiplication of matrix 119
Multiplying 15
  decimal fractions 10
  fraction and mixed numbers 9
  numbers written in powers-of-ten notation 15
Music wire 309
Music wire, gages 2519
M-words, NC 1278

N

Nails and spikes, standard 1476
National Tube Co. 298
Nautical measure 2549
NC programming 1269–1312
Negative and positive numbers 4
Negative functions of angles 99
NEMA standards for electric motors 2465–2467
Net present value 131
Newton's laws of motion 171
Newton's laws of motion 143
Newton-Raphson method 33
Newtons into pounds force 2577
Nickel alloys 589–590
  applications 589–590
  chemical composition 589–590
  chromium steels, SAE strength 474
  coefficient of expansion 404
  density 404
  elongation 418, 589–590
  gearing material 2146–2147
  hardness 418
  machining 1155–1156
  melting points 404
  plating 1467, 1469
  specific heat 404
  tensile strength 418, 589–590
  thermal conductivity 404
  yield strength 418
Nitinol, machining 1155
Nitralloy steels 527
Nitriding 509, 527
  high-speed steel tools 543
  ion nitriding 527
Nitrogen, liquid temperature 648
Nodular cast iron 1361
Noise, machinery 1325
Nomenclature
  bevel gears 2085
  gear teeth 2033
  spur gears 2034
Nominal clearance 2159
Nominal vs effective interest rates 126
Nondestructive testing symbols 1441–1442
Nonferrous metals 554
  machining 1153–1156
Nonferrous metals *(continued)*
  modulus of elasticity 554
  modulus of shear 554
  shear strength 554
  strength 420, 554
  tensile strength 554
  yield strength 554
Normal
  distribution curve 1245–1248
  positional deviation 1245–1248
Normalizing 450
  temperatures, alloy steel 532–533
Norton Company 1180, 1188–1194
Nose radius 754
  carbide tools 767
  single point tool 767
Nozzles, flow of water through 425
Number of nails and spikes in a pound 1476
Number of teeth 2031
Numbering systems
  for aluminum alloys 575
  for aluminum alloys, wrought 578
  for metals and alloys 440, 442
  for steel 440–443
Numbers
  associative law 4
  commutative law 4
  distributive law 4
  identity law 4
  inverse law 4
  positive and negative 4
  powers-of-ten notation 14, 16
  preferred series 656, 690
  prime 19–28
  progressions 36–37
Numerical control 1254–1325
  absolute programming 1277
  accuracy, repeatability, and resolution 1245–1248
  adaptive control 1262
  addresses, letter 1272
  APT programming 1292–1309
    circles 1298–1299, 1301
    computational statements 1294
    example program 1306
    for turning 1307–1309
    geometry statements 1294
    lines 1296
    motion statements 1299–1304
    planes 1302
    points 1295
    postprocessor statements 1304–1309
    tabulated cylinder 1303
  automatically programmed tool (APT) 1292–1309
  axis nomenclature 1264–1268
  bit 1258
  block 1272–1274
  byte 1258
  CAD/CAM 1324–1325
  central processing unit 1258

Copyright 2004, Industrial Press, Inc., New York, NY

Numerical control *(continued)*
circular interpolation 1283–1284
closed-loop system 1262
computer-aided part programming 1270
control, adaptive 1262
cutter compensation 1280–1282, 1310–1312
cutter location data 1271
decimal point programming 1272
direct (or distributed) NC 1324
feed rate override 1280
fixed (canned) cycles 1287–1291
flexible manufacturing
cell 1264
module 1264
system 1263
format detail 1272
F-word 1279
G-code addresses 1274–1278
helical interpolation 1284
incremental programming 1277
initial graphics exchange specification (IGES) 1322–1324
insert holders for NC 1310–1312
insert radius compensation 1310–1312
interpolation
circular 1283–1284
helical and parabolic 1284
linear 1282
letter addresses 1272–1274
macro 1286–1287
manual data input 1269
microprocessor 1258–1259
miscellaneous functions 1278
parabolic interpolation 1284
parametric
expressions and macros 1286–1287
programming, NC 1286–1287
subroutine 1286–1287
part programming 1269–1272
part tolerance symbols
ANSI 1250–1253
compared to ISO 633
points, lines, circles (APT) 1295–1299
postprocessor 1272, 1294
preload registers (G92) 1278
preparatory word 1274–1278
programmable controllers 1258–1262
programming
absolute 1277
incremental 1277
NC 1269–1312
repeatability, accuracy, and resolution 1245–1248
sequence number 1274
standards 1255–1256
steeper motors 2493
subroutine 1285–1287
S-word 1280
tapping 1942
Numerical control *(continued)*
thread cutting 1291
tool
compensation 1310–1312
data table 1280
length offset 1282
nose radius compensation 1282, 1310–1312
offset 1281
total indicator reading 1267
turning cycles 1291
T-word 1280–1282
V-flange tool shanks 1313
word address format 1272–1274
zero suppression 1274
Nuts
acorn 1523
ANSI, inch dimensions
flat jam 1520
hex 1513
hex flat 1520
hex slotted 1520, 1522
hex thick slotted 1521–1522
jam 1519
machine screw 1587
square 1513, 1522
T-type 1666
Unified 1519, 1522
ANSI, metric dimensions
heavy hex 1567
hex jam 1567
hex, styles 2 and 3 1562
metric hex flange nuts 1564
prevailing torque, hex 1565–1566
slotted hex 1563
British Standard 1614
ISO metric 1574–1577
metric 1605, 1608, 1610, 1615
Unified 1616
Whitworth 1571, 1573, 1617, 1638
crown, low and high (SAE) 1523
eye nuts 395
friction coefficients 1498
high, SAE 1524
slotted, high hex (SAE) 1524
tap 892, 904, 910–911
wing nuts 1712–1715
wrench clearances 1530–1531
wrench openings 1530
Nylon
bearings 2265
properties 416
rope, strength of 389

O

Obtuse-angle triangles solution 64, 94–95
Octagon
area 65
moment of inertia 241

Copyright 2004, Industrial Press, Inc., New York, NY

Octagon *(continued)*
radius of gyration 241
section modulus 241
Offhand grinding 1229
Offset method of determining yield strength 204
Ohm's law 2587
Oil feeding and grooving of bearings 2229
Oil lubrication 2340
Oilless bearings 2267–2268
Oils
and compounds, machining 1143–1156
emulsifying or soluble 1144
mineral 1146–1147
sulfurized and chlorinated 1146–1147
coating 1468
lubricating 2332, 2340
viscosity unit conversion 2334
tempering 521
Open-end wrench clearances 1531
Open-loop system 1262, 2487
Operations on complex numbers 17
Orbit 1351
Order of performing arithmetic 5
O-ring 2502–2507
applications 2503, 2505
compounds 2506
diametral clearance 2505
flurocarbon 2506
gland depth 2503
groove dimensions and clearances 2502, 2505
hardness 2504
nitrile 2506
reciprocating seals 2503
ring materials 2507
silicon 2506
squeeze 2502
static seals 2503
surface finish in contact with 2504
tolerances 2505
washers, backup 2503
Oscillation, center and radius of 235
Ounces, avoirdupois, into grams 2571–2572
Out of roundness 721
Oval head machine screws 1593–1595
Overhead
machine-hour distribution 137
man-hour distribution 137
man-rate distribution 137
Oxygen gas in welding 1394, 1419

P

Pack hardening 527
Packing
in circles 81–84
in circles and rectangles 81–86
in rectangles 86
Palladium, plating 1469
Pan head machine screws 1592
Paper, bonding 2482
Pappus or Guldinus rules 59
Parabola 45
area 67–68
center of gravity 228
constructing 58
directrix 45
focus 45
general equation 45
latus rectum 45
segment of area 68
vertex 45
Parabolic interpolation, NC 1284
Paraboloid
center of gravity 230
polar moment of inertia 251
radius of gyration 235
segment volume 80
volume 79
Parallel lines 41
Parallelogram
area 63
center of gravity 225
geometry of 51
of forces 145
radius of gyration 232
Parametric subroutine, NC 1286–1287
Passivation of copper 1462
Patterns for castings 1368
dispansable 1375
master mold 1375
materials 1368
metal 1369
shrinkage allowances 1369, 1375
varnish 1369
weight of casting from 1370
wood selection 1368–1369
Payback period 134
Pearlite 507, 511
Pearlitic malleable iron 1361
Pebi 2546
Pendulum 165–166
calculations 165
conical 165
formulas for 165
physical 165
simple and compound 165
torsional 165
types of 165
Percentage 7
Percussion, center of 235
Perforated metals, strength and stiffness of 2521
Permanent mold, casting process 1367
Permanickel, machining 1155
Permutation 18
Perpendicular lines 41
Petroleum oils, application 2333, 2582
Phenolic plastics 2265
Philadelphia carriage bolt thread 1892

Copyright 2004, Industrial Press, Inc., New York, NY

Phosphor-bronze, worm gearing 2149
Physical vapor deposition (PVD) 776
Piano wire, working stresses 318
  at elevated temperatures 319–320
Piles, weight of 409
Pillow block bearings 2277
Pin method for checking
  gear sizes 2125
    allowance for backlash 2139
    for involute splines 2175
    wire diameters 2125, 2134
  spur gear sizes 2135–2138
  V-shaped grooves 717
Pinion, spur gear
  enlarged to avoid undercut 2050
Pins
  clevis 1668
  cotter 1667, 1678, 1681
  dowel 1667–1673
  grooved 1677, 1681
  metric dowel 1667, 1669
  spring 1682–1683
  straight 1672–1674
  strength of taper 224
  taper 1674–1677
Pintle chains 2441
Pipe and pipe fittings 2526–2538
  ANSI Standard wrought steel 2529–2530
  bending pipe and tubes 2535
  British threads 1870–1871
  columns 290–291
  cross-sectional area of metal 2529–2530
  cubic contents for given length 427, 2529–2530
  definitions 2526, 2532–2533
  definitions of pipe fittings 2535–2538
  dryseal 1866–1869
    measuring by wire method 1909
    taper 1860
    threads 1866–1869
  flow in 2531
  gallons per foot 427, 2529–2530
  grades of 2527–2530
  heat loss from uncovered steam 400
  internal thread in pipe couplings 1864
  length per cubic foot 2529–2530
  loads, table of 290–291
  metric weights and mass 2526
  moment of inertia 2529–2530
  plastics 2532–2538
    joining 2532–2533
    pressure ratings 2534
    properties and use of 2533
    temperature correction factors 2534
    threads 610
    weights and dimensions 2532
  radius of gyration 2529–2530
  reamers, taper 852
  schedule numbers 2527
  sealing joints 1479
Pipe and pipe fittings *(continued)*
  section modulus 2529–2530
  steel, welded and seamless 2527
  taps, dimensions 899–902, 914
    Briggs and Whitworth 1941
    internal dryseal 1868
    power for driving 1941
    straight 892, 899–916
    taper 892, 900–901
  threads
    American National Standard 1860–1868
    British Standard 1869–1871
    designation and notation 1860
  wall thickness 2526
  weight per foot 2527–2530
  welding 1425
    fill passes 1427
    flux cored electrode 1428
    fusion 1428
    position 1426
      flat 1426
      horizontal 1426–1427
      overhead 1426
      vertical up and down 1427
    procedure 1429
      carbon steel 1429–1431
      MIG 1429–1431
      root 1429–1431
      thick walled 1429–1431
    root passes 1426
    thin wall 1428
  wrought steel 2526–2527
Pitch 2031
  broach teeth 955–958
  circle 2031
  circular, of gears 2033
  diameters, gears
    circular pitch 2052
    helical 2099
    pin method of checking 2125
    spur 2035, 2052
    worms 2096
  diameters, roller chain sprockets 2447–2448
  diameters, thread
    checking 1893
    for tensile stress area 1502
    metric, M profile 1795–1797
    unified 1732–1772
    wire sizes for measuring 1895
  diameters, thread unified 1736
  gear 2035
  plane 2031
  rivets 1478, 1482–1483
  screw threads, measuring 1893
  worm gearing 2095
  worms 2095
Pitot tube 2570
Plain bearing *(see* Bearings: plain*)*
Plain milling cutters 798

Copyright 2004, Industrial Press, Inc., New York, NY

Plain washers
inch 1532–1535
metric 1568
types 1568
Plane figures, areas and dimensions 63–74
Plane of rotation 2031
Planetary gearing 2115–2118
bevel gears 2115
compound drive 2115
direction of rotations 2115
Planetary thread milling 1963
Planing
estimating cutting speeds 1082
power required 1084–1088
speeds and feeds 1082
time 1082
tool grinding 756
wood 414
Planing insert holder 762–764
Plastics 592–628
aging at elevated temperature 604
assembly with fasteners 620
bearings 2276
anti-friction 2276
laminated, plain bearings 2265
sleeve 2265
bending strength 601
bending stress 627
bonding 616
brittleness 595
characteristics 592
chemical resistance of 607
coefficient of expansion 416
compressive strength 601
creep 603
deflection 601, 604
density 416
design
analysis 607
for assembly 615
for injection molding 611
stress 609
developing prototypes 623–624
draft angles and depth of draw 614
drilling speeds and feeds 623
ductility 595
effects of temperature 603, 605
elasticity 595, 598
electrical properties 605
comparative tracking index 606
conductivity 605
dielectric constant 606
dielectric strength 606
permittivity 606
surface resistivity 605
volume resistivity 605
elongation 416
environmental effects 606
fatigue 603
fillets 615
Plastics *(continued)*
flammability ratings 604
flexural modulus 416, 601
gearing 625
accuracy 628
backlash 628
service factors 627
tooth form factors 626
glass transition point 604
hardness 416
heat dissipation factor 606
hoop stress 609
impact loading and testing 603
impact resistance 612
injection moldings 611
izod impact 416
linear thermal expansion 604
lubricity 595
machining 621
cutting off 622
drilling 622
molded 623
sawing thermoset cast 623
tapping 623
threading 623
turning 622
material 592–593
elastomers 593
thermoplastic 593
thermoset 593
maximum temperature 416
mechanical fasteners 616
mechanical properties 596
effect of temperature on 603–604
related to time 602
milling 624
mixtures 593
coploymers 594
reinforcing fibers 593
molulus of elasticity 597
normal strain 597
notch sensitivity 595
opacity 594
physical properties 596
density 594
shrinkage 594
specific gravity 594
water absorption 594
pipe and fittings 2532–2533
pipe threads 610
plasticity 595
press fits 609
pressure vessels 609
propotional limit 598
region 204
relaxation 603
sawing, speeds and numbers of teeth 623–624
secant modulus 598
shear modulus, G 600
shear stress 599

Copyright 2004, Industrial Press, Inc., New York, NY

Plastics *(continued)*
snap-fit 616
specific gravity 416
stress 596
normal 597
stress relaxation 602
structural analysis 607
safety factors 607
structures 593
temperature effect 604
temperature index 604
tensile impact 603
tensile modulus 416
thermal conductivity 604
thermal properties 603
thermal stresses 610
thermal welding 616
thermoplastic 592
thermosetting 592
toughness 595
ultimate strength 598
undercuts 615
vicat softening point 604
wall thickness 612–613
yield point 598
Plates
flat, strength and deflection of 292–294
shells and cylinders, strength of 292–298
Plating 1464–1471
chromium 1423
magnesium anodic treatment 1466
magnesium, coating 1466
phosphate coating 1469–1470
surface coatings 1464
zinc 1471
PLC (programmable logic control) 1258–1262
Plow steel haulage rope, strength of 372–377, 387
Plunge angle 762
Points, lines, circles, (APT) NC 1294–1299
Poise 2334, 2586
Poisson's ratio 204
flat plates 292
for various materials 204, 294, 420
perforated metal 2521
plastics 599
Polar coordinates 42
Polar moment of inertia 236, 248–252, 254–259
cone 252
frustum 252
cylinder, hollow 250
ellipsoid 251
formulas 250–252
masses 236
paraboloid 251
plane areas 236
prism 250
pyramid 250
Polar moment of inertia *(continued)*
solid ring 251
spherical sector 251
spherical segment 251
torus 251
Polar section modulus 248–249, 254–259
Polishers, spindles for portable 950
Polishing and buffing 1457
abrasives 1457, 1460
operations 1460
speeds 1460
wheels, material 1457
Polygon
area 65, 69
forces 146
formulas and table 69
length of side 69
radius of circumscribed circle 69
radius of inscribed circle 65, 69
Polygon shafts 2186
connections 2186
dimensions of 2186
manufacturing 2187
strength of connections 2187
three- and four-sided designs 2186
Polyphase motors 2467, 2470
Polypropylene plastics 2533
Polyurethane plastics 2506
Porosity, pressure die castings 1370
Porous bearings 2265
Portable grinding 1229
safety 1210
Portable tools
hexagonal chucks for 951
spindles and drives for 948–951
Positional deviation, mean 1245–1248
Positioning accuracy 1245–1248
Positive and negative numbers 4
Positive clutches 2354
Positive functions of angles 99
Postprocessor, NC 1272, 1294
Potential energy 173–174
Poundal 2578
Pounds
force 142–143
force into newtons 2577
mass 143
per cubic foot into kilograms per cubic meter 2573
per cubic inch into grams per cubic centimeter 2573
per square foot into kilograms per square meter 2575
per square inch into kilograms per square centimeter 2575
per square inch into kilopascals 2575
Powder metallurgy 1379
briquetting tools 1379
design 1379
limiting factors 1379
metal process 1379

Copyright 2004, Industrial Press, Inc., New York, NY

Powdered metal alloys
copper base 419
density 419
elongation 419
hardness 419
iron base 419
tungsten base 419
Powdered metal bearings 2265
Power
calculating by dynamometer 2360
consumption spade drilling 1080
cutting tool 1086
feed factors 1085
for driving pipe taps 1942
general formulas 178
heat equivalents 2578
in mechanics 141
motor 1086
required for machining 1084–1092
roots of numbers 14
transmission
belting 2391–2440
by friction wheels 2361
capacity 2150, 2350
chain 2451–2455
disc clutch 2350
friction wheels 2360–2362
units conversion 2581
Power brush
brush finishing 1456–1459
brush uses 1456
deburring 1456
tooth profile of gears 1456
Power constant
alloy steels 1086
high temperature alloys 1085
nonferrous metals 1085
plain carbon steels 1086
stainless steel 1085
tool steels 1085
wrought steels 1086
Power of ten notation 14, 16
expressing numbers in 15
Power transmission
roller chain 2441–2464
Precipitation
hardening 504
heat-treatment 583
Precision
bolts and screws, British 1571–1572, 1578
gage blocks 743–745
investment casting 1374
Preferred
basic sizes, ANSI Standard 690
hole basis metric fits, ANSI Standard 669, 673
metric sizes
ANSI Standard 665, 690
British Standard 690
Preferred *(continued)*
numbers, ANSI Standard 689
numbers, British Standard 690
roughness average values (Ra) 734
roughness values and roughness grades 740
series for tolerances and allowances 652
series maximum waviness height values 735
shaft basis metric fits, ANSI Standard 668, 674–677
thicknesses for
flat metal products, metric 2523
uncoated metals and alloys 2522
Preload measurements 1499
Preload registers, (G-114 word) NC 1278
Preload relaxation 1499
Preparatory word, (G-word) NC 1274–1278
Present value and discount 127
Pressure
and flow of water 422
angle 2032
angle, cams 2197
composite checking of fine-pitch gears 2073
cylinders and tubes, collapsing pressure 297–298
definition and units for 144–145
effect on wood property 412
head in foot to psia relation 422
Lame's formula for internal 295
psia to head in feet relation 422
radial on sheave or drum 379
spherical shells, strength to resist internal 295
tight joints 1864
tube, collapsing pressure 298
unit conversion 430, 2574–2575
viscosity coefficient for lubricants 2345
Prime numbers and factors 19–28
Principle reference planes 2032
Prism
polar moment of inertia 250
volume 75
volume formula 59
Prismoidal formula for volume 59
Production rate 1108
Profile checking, gearing 2062
Programmable logic controller, NC 1258–1262
Programming
absolute, NC 1277
APT 1292–1309
G-code 1272–1292
incremental, NC 1277
numerical control 1269–1309
Progression
arithmetical 36–37
geometrical 36–38
Prony brake dynamometer 2360–2361

Copyright 2004, Industrial Press, Inc., New York, NY

Properties
commercial petroleum oils 2333
mechanical 203–204, 420
compressive 205
definitions 203
fatigue 205
modulus of elasticity values 204
perforated metal 2521
Poisson's ratio values 204
shear 205
strength 420–421, 464–465
thermal 399–400, 421
yield point values 204
of materials
air 428
aluminum alloys 571
copper alloys 554
copper-zinc-tin alloys 420
magnesium alloys 586–588
metals 420
nickel alloys 589–590
nonferrous alloys 554
plastics 416
powdered metal alloys 419
specific gravity 408
spring wire 421
standard steels 438, 460, 464–465
titanium alloys 589, 591
tool steels 490, 501
water 422
wood 413
strength effect of heat or temperature 603
Proportion 5–7
compound 5
inverse 6–7
simple 6
Proportional limit 203
plastics 598
Protractor, reading vernier scale on 692
Providing backlash 2070
PTFE plastics 2265, 2485
Pulley
speeds, rpm into feet per minute 1016–1021
taps 904, 910–911
Pulleys and belts
and belt drives 162–163
and wheels in mechanics 162–163
arc of contact correction factors 2399
center distances, V-belt 2391
center to center distance 2388
cross section correction factors 2398
diameter and speeds 2389
diameter in compound drives 2389
differential 163
flat belt 2388, 2391
flywheel pulley 183
length correction factors 2399
length of belt traversing three pulleys 2390
Pulleys and belts *(continued)*
lengths of open and crossed belts 2388
lengths of V-belt 2394
rules for calculating diameters and speeds 2388
sheave size 2397
speed in compound drive 2390
speed ratio correction factors 2398
speeds, rpm into feet per minute 1943
V-belt 2388
wrap angles 2388
Pull-up torque 2466
Pump
head and horsepower relation 423
horsepower at different head 423
Punch presses speeds and pressures 1330–1331
Punches and dies
pressures required 1331
PVC plastics 2533
Pyramid
center of gravity 229
frustum center of gravity 229
polar moment of inertia 250
volume 75
volume of frustum 76

Q

Quadrant 99
Quadratic equations 31
Quenching 449
baths 519
tanks for 518
high speed steel 540
interrupted 518–519
media 508
tungsten 540
air cooling 540
salt bath 540

R

Rack 2032
gear 2036
milling, indexing 2024
spline, metric 2181
Radian per second conversion from rpm 169
Radians equivalent to degrees 96, 98
Radius
of arc, checking 717–718
of curvature 2203
of gyration 232, 235
angles, steel 2515–2517
bar of small diameter 232
bar, small diameter 232
channels, aluminum 2518
channels, steel 2514
circle 241

Copyright 2004, Industrial Press, Inc., New York, NY

Radius *(continued)*
of gyration
circular disk, thin 233
circular ring 242
circular ring, thin flat 233
cone 234
cone, frustum 234
cylinder 233
cylinder, hollow 234
ellipse 242
ellipsoid 235
flat plate, thin 232
half circle 241
hexagon 240
hollow circle 241
hollow cylinder, thin 234
hollow sphere 235
I-beams 2509–2512
I-beams, aluminum 2518
I-section 242
L-section 246
octagon 241
paraboloid 235
parallelepiped 233
parallelogram 232
pipe 2529–2530
prism, rectangular 234
rectangle 239
ring 232
S- or W-shape, steel 2513
sphere 235
sphere, hollow 235
spherical shell, thin 235
structural angles 2515–2517
thin flat plate 232
thin spherical shell 235
trapezoid 240
triangle 240
T-section 245
various cross-sections 238–247
wide flange, steel 2509–2512
Z-section 247
of oscillation 235
Rails
size to carry given load 281
strength of 281
Rake angles 753
checking milling cutter 826
single-point cutting tools
lead angles 753
turning tool 750
Rank of a matrix 122
Rankine's formulas for columns 285, 287
Rankine, temperature 2583
Rasps 965
aluminum 965
Ratchet gearing 2119–2120
frictional 2120
multiple pawl 2120
pitch of wheel teeth 2120
Ratchet gearing *(continued)*
reversing 2120
shape of wheel teeth 2120
types 2119
Rate of return (interest) 126–127, 134
Ratio 5–7
and proportion 5–7
compound 5
contact, in gearing 2055–2060
epicyclic gearing 2115–2118
fractional, change gears for 1947
gear for differential indexing 2008
geometrical 36–38
inverse or reciprocal 5
mean proportional 6
of volumes 80
Poisson's 204
slenderness, columns 285
Ream, paper 2587
Reamer
bull center 851
center 851
Reamers 832–853
ANSI Standard 832–853
arbors for shell 850
Brown & Sharpe taper socket 852
center and countersink 839
centers for 839
chucking 834, 837, 841, 846–847
straight flutes 846–847
definition 835
die-maker's 853
drills for taper pin 1675–1677
driving slots and lugs 845
expansion chucking 842
expansion hand 844
finishing 851
fluting cutters 833–834
dimension 834
fluting to obtain negative rake 832
formed 834
hand 833, 843–844
squared shank 844
straight and helical flutes 843–844
helical flutes 850
jobbers 845
letter sizes 847
machine countersinks 840
morse taper socket 851
negative front rake 832
pipe 852
rose chucking 834, 848
straight and helical flutes 848
shell 845, 849
straight and helical flutes 841, 849
straight flutes 845–846
straight shank 840
stub screw machine 847, 850
taper pin 853
taper pin reamers, drills for 1674, 1677
taper pipe 852

Copyright 2004, Industrial Press, Inc., New York, NY

Reamers *(continued)*
taper shank 841
taper, milling teeth 821
terms applying to 835
threaded end 833
dimension 833
tooth-rest position for grinding clearance 835
wire gage sizes 846
Reaming
automatic screw machines 1132
cutting speeds for
copper alloys 1072
ferrous cast metals 1068–1069
light metals 1070
stainless steels 1067
tool steels 1066
difficulties 840
bellmouth holes 840
oversize holes 840
poor finish 841
taper pin 1676
Rearrangement of terms in formulas 29
Recalescence point in steel hardening 503, 512
Recessing tools, speeds 1132
Reciprocals of numbers 5, 8
Rectangle
area 63
moment of inertia 239
radius of gyration 239
section modulus 239
table of section moduli 254
Rectangular
coordinates 42
cylindrical coordinates 44
spherical coordinates, relationship 43
Refrigeration of steel 546
Relative density 407
Relief and rake angles
for single-point cutting tools 752, 1944
indicator drop method of checking 826
Relief angles
for single-point cutting tools 752
turning tool 750
Repeatability, accuracy, and resolution 1245
Replacement-gear dimensions 2153
Resinoid bonded wheels 971–972, 1178
thread grinding 1957
Resistance brazing 1387
Retaining rings 1684
ANSI Standard 1684–1692
centrifugal capacity 1708
compressed in bore 1690
diameter tolerances 1702–1703
dimensions in inches 1701, 1704
expanded over shaft 1688
external dimensions 1705, 1708
external series 1684–1685
external spiral 1695, 1699
Retaining rings *(continued)*
failure of 1702, 1709
groove bottom radii 1685
groove design and machining 1706–1707, 1710
groove diameter 1685
groove diameter tolerances 1703
groove failure 1709
groove width 1685
groove width tolerances 1703
industrial 1707
internal 1708
internal spiral 1693, 1697
load capacity 1700
material 1700
metric performance data 1688
ring free diameter 1685
rotation between parts 1709
seated in groove 1688, 1690, 1692–1693
selection 1684
self locking dimensions 1707
self locking external and internal 1708
self locking inch series 1708
self locking types 1707
spiral 1695
standards 1708–1711
tapered 1684–1685
thickness 1696, 1700
thickness tolerances 1696, 1700, 1702–1703
thrust load capacities 1706
thrust load safety factors 1705
width capacity 1702
Retarded motion 167
Retention knobs, V-flange tool shanks 1313
Reyn 2334, 2586
Rhodium plating 1470
Right-angle triangles solution 64, 91–93
Rigidity
modulus of (shear) 204
spring materials 348–350
Ring
area and volume 59
radius of gyration 232
solid
polar moment of inertia 251
stresses in loaded 223–224
Rivet
allowable stresses 1480
ANSI Standard 1483–1485
belt 1485
British Standard 1491, 1494
cold forged 1491
hot forged 1491
lengths 1491
snap head 1491
universal head 1491
button head 1483, 1485
cone head 1483
cooper's 1485
countersunk 1483, 1491

Copyright 2004, Industrial Press, Inc., New York, NY

Rivet *(continued)*
diameters for given plate thicknesses 1478
dimension countersunk head 1494
dimension snap head 1494
excess length to form head 1483
flat head 1485, 1491
hold-on or dolly bar sets 1483
large rivets, standard 1483
material 1479
mushroom head 1491
pan head 1483, 1485
pitch 1478, 1482–1483
sets, dimensions of impressions in 1483
shearing strength 1482–1483
small rivets, standard 1483–1485
spacing 1478
steel 1479
strength 1479
tinner's 1485
truss 1485
types 1478
Riveted joints 1478–1483
allowable stresses 1479
double and triple 1482
efficiency 1479–1480
failure 1479
holes for 1478
joint failure 1479
joint strength 1479–1480
rivet length for forming heads 1483
rivet materials 1479
strength 1480
types of riveted joints 1478
working strength 1479
Rockwell hardness
conversion to Brinell hardness 550–551
number 552
scales 548
test 547–548
Rod gages 2519
Roebling wire gage 2519
Rolled threads, electric socket and lamp base 1884
Roller bearing *(see* Bearings: roller*)*
Roller chain, double pitch 2442
Rolling
contact bearings 2269–2323
friction resistance 159
Rolling screw threads 1952–1956
cylindrical die machines 1952
diameter of blank 1953
diameter of threading roll 1954
flat die machines 1952
in automatic screw machines 1953
shapes and kind of thread 1954
speeds, and feeds 1955
steels for 1953
Root diameter gearing 2032
Roots
and powers of numbers 14
finding square and cube 14
Rope
manila, safe loads and strength 387, 391
nylon, safe loads and strength 389
safe loads for 387
slings, strength 387, 389
weight per 100 feet 391
wire 369
definitions of terms 369–370
strength and properties 372–377
winding drum, grooves for 378–379
Rose chucking reamers 834
fractional sizes 848
Rotary file or burs 965
Rotary motion formulas 169
Rotating parts, balancing 197–202
Roughness
control of 724
cutoff 734
height values 726–727
parameters
rules for determining 739
rules for measurement of 740
symbols indicating degree of 724–727
Round head machine screws 1596
Royal Microscopical Society thread 1886–1887, 1889
Rpm
conversion to radian per second 169
for various cutting speeds and diameters, inch units 1018–1021
metric units 1020–1021
for various grinding speeds and diameters 1211
Rubber
bearings 2266
bonded grinding wheels 1178
bonding 2481
turning 1082
Running balance 197
Rupture strength
copper-base powdered alloys 419
iron-base powdered alloys 419
tungsten-base powdered alloys 419

S

SAE Standards
babbitt metals 2263
bearing metals 2263
crown or acorn nuts 1523
die casting alloys 1371
high nuts 1524
taper shaft ends 2373
V-belts 2429
Woodruff keyseat cutters 820
SAE steels
basic numbering system 440

Copyright 2004, Industrial Press, Inc., New York, NY

SAE steels *(continued)*
compositions 440, 442, 446–447
heat treatments for 532
Safe loads for wire rope 372–377
Safe speeds grinding wheels 1209–1211
Safety
factors of 208, 2078
flange couplings 2346
for wire rope 375–376
Salt baths for heat treating 516
Sand blast cleaning 1368
Sanders, spindles for portable 950
Sanding wood 414
Sandstone and limestone, strength 420
Saw tooth clutches 2356
Sawn lumber size 414
Saws
band 1138–1143
circular, arbors for 948
metal-cutting, speeds 1082
metal-slitting 801
sharpening files 963
slitting 801
Scalar and vector quantities 145
Scleroscope 548
Screw machines
automatic 1131–1136
automatic box-tools 1132
drilling speeds and feeds 1132
drills 860, 867
forming tools with rake 784–789
knurling 1131–1132
reaming speeds and feeds 1132
speeds and feeds 1132–1133
stock required for given production 1136
threading cams 1131
Screws
and bolts 1512
angularity and eccentricity 1579
ANSI head recesses 1642
breaking load 1511
British Standard
BSF 1617
inch 1570–1573, 1605, 1632–1638
metric 1578, 1605–1613, 1632–1637
Unified 1614, 1616
Whitworth 1570, 1573, 1617, 1638
cap 1516, 1618–1623
cap, metric 1541
drive 1639, 1654
force for turning 163
form 1579
grade markings for steel 1508–1509
head recesses 1642
heavy hex 1516
hex cap 1513
inserts 1654
jig and fixture
button head 1636
heavy hex 1516
Screws *(continued)*
jig and fixture
hex 1513
lag screw 1517–1518
metric 1545
length of engagement 1510
length of thread 1579
mechanical principle of 163
metric
British Standard 1613
cap 1541
diameters 1543
flange 1546–1547
formed 1542
heavy hex 1543
ISO 1575
reduced body diameter 1544
socket 1632
self-threading 1639–1663
set 1625–1638
shoulder 1624
sockets for 1627
sockets metric series 1634
strength of 1509
stress areas 1502, 1510
tap drills 1933–1941
tap marking symbols 916–917
thumb 1716, 1719–1720
Unified Standard 1512, 1616
wing 1716
wood 1477
worm threads 2095–2098
Sealants 2484
anaerobic pipe 2486
gasket materials 2485
pipe joining 2484
silicone rubber gasketing 2485
tapered pipe threading 2485
types 2484
Sealing bearings 2223–2225
Seasoning steel, sub zero 547
Secant 88
Secant modulus (plastics) 598
Section lining, standard for drawings 630, 632
Section modulus
angles 2515–2517
circle 241
circular ring 242
ellipse 242
for torsion 283
formulas for various sections 238–247
half circle 241
hexagon 240
hollow circle 241
I-beams 2509–2513
I-section 242
L-section 246
octagon 241
pipe 2529–2530
polar 248–249, 254–259

Copyright 2004, Industrial Press, Inc., New York, NY

Section modulus *(continued)*
rectangle 239
rectangles, table for 253–254
round shafts, table for 254–259
structural shapes
angles, steel 2517
channels, aluminum 2518
I-beams or S-shapes
aluminum 2518
steel 2513
wide flange, steel 2509–2512
steel 2514
trapezoid 240
triangle 240
T-section 245
units conversion 2587
Z-section 247
Segment, circular 66, 70–72
area 66, 71–72
height for given angle and radius 66, 70–72
Seizing and cutting wire rope 380–381
Self alignment roller bearings
symbols 2272
Self-threading screws 1639–1663
countersink heads 1639
cross recesses 1642
designations 1640
drill size 1650
drilled hole sizes 1648
drive type 1639–1640
extruded hole sizes 1648
fillister head 1640
head cross recesses 1642
hex head 1640
hex washer head 1640
hole sizes 1647, 1650
inch, metric 1654
metallic drive 1640
metals
brass sheet metal 1650
monel steel 1650
stainless steel 1650
steel 1650
metric 1654–1663
clearance holes 1659
cutting tapping 1656
designations 1655–1656
drilled hole sizes 1660, 1662
extruded hole sizes 1659
head types 1654–1655
heat treatment 1658
hole sizes for steel 1659–1663
hole sizes for tapping 1659
material 1658
punched hole size for steel 1660, 1662
recommended lengths 1657
tapping 1659
thread and point types 1655
thread cutting types 1654–1658
Self-threading screws *(continued)*
metric
tapping 1656
thread forming 1656
tapping 1660–1661
types 1654–1657
thread tapping
in asbestos 1661
in cast metals 1662–1663
in plastics 1661, 1663
in plywoods 1661
in sheet metal 1662
pan head 1640
round head 1639
self-tapping inserts 1654
sheet metal hole sizes 1650
slotted pan head 1640
steel thread cutting 1651
thread and point
dimensions 1643–1646
types 1641–1642
thread cutting 1646
sheet metals 1650
tapping 1642
types 1639, 1642, 1644
thread forming 1643–1644, 1647–1648
types 1641–1642
torsional strength requirements 1654
truss head 1640
types of 1639
Sellers screw thread 1892
Sensivity factor 2078
Sequence number, NC 1274
Series, infinite 34, 103
Set-screws
British Standard
metric 1632–1638
Whitworth 1638
cone point 1625–1637
cup point 1625–1637
dog point 1625–1637
flat point 1625–1637
headless 1625
hexagon and spline 1626
hexagon socket 1632, 1635, 1637
hexagon socket type 1637
holding power 1637
oval point 1625
spline socket type 1631
square head type 1628–1629, 1638
Sevolute functions 103
Shackle and end-link chain 392
Shaft conditions
checking 719
out of roundness 723
no. of lobes 723
V-block angles 723
out-of-roundness, lobing 721
Shafts 299–307
allowances and tolerances for fits 645
British Standard for fits 679–688

Copyright 2004, Industrial Press, Inc., New York, NY

Shafts *(continued)*
brittle materials, formulas for 305
checking for various conditions of 719–723
critical speeds of 306
deflection, linear 302
deflection, torsional 301–302
effect of keyways on strength 305
factor of safety 300, 305
hollow 307
horsepower transmitted by 299–302
linear deflection 302
maximum allowable working stress 305
moment of inertia, polar 248–249, 254–259
polygon type connections 2186
round, section moduli 254–259
steel, diameters of 303
strength 299–301
taper ends, SAE Standard 2373
torsional
deflection 301–302
strength 299–301
hollow vs. solid 307
transmission, design of 303–305
Shanks taper 926–937
Shapes
of grinding wheels 1180–1188
of mounted wheels and points 952–954
Shaping wood 414
Shaping, speeds and feeds 1082
Sharp V-thread 1725
Sharpening
carbide tools 971–973
circular saws 963
diamond wheels for 972
drills 969–971
milling cutters 821, 824–825
Shear
formulas for 213
modulus 204
of G spring materials 348–350
of various materials 204, 420
properties 205
spring design 350
stress 203, 214
combined with tension or compression 215
in beams 215–218
Shear strength
cast iron 474
magnesium alloys 588
nonferrous metals 554
rivets 1482–1483
steels 474
wood 412
wrought iron 474
Shear tooth files 965
Sheaves
for V-belt drives 2393
for wire rope 353, 370
Sheet metal
allowances 1335
and wire gages 2522–2523
bending allowances 1332–1335
formula 1339
edging process 1339
joining process 1339
angle frame 1343
button punch snap lock 1341
clinch bar slip and angle 1343
clinch type flanged connections 1344
corner standing seam 1341
double flanges and cleats 1344
double seam 1341
flange 1342
flange and flange corner 1341
flanged duct connections 1343
flanged end and angle 1343
flat drive slip 1342
flat S slip 1342
flush lap 1340
formed flanges 1343
groove seam 1341
hem 1342
hemmed S slip 1343
pittsburg 1342
plain lap 1340
raw and flange corner 1340
slide corner 1341
standing drive slip 1342
standing seam 1341
joints 1340
screws 1639
stock allowances 1335–1338
Sheet sizes for drawings 630
Shell
blanks, diameters 1331
mills 803
molding 1366
plates and cylinders, strength 292–298
reamers 849
Shielded metal arc welding (SMAW) 1405–1409
Shielding gases 1393
Shipping measure 2566
Shock-resisting
tool steels 495
chemical composition 497
heat treatment 497
Shocks, stresses in springs 283
stresses produced by 283
Shore's scleroscope 548, 550–551
Shoulder screws 1624
Shrinkage allowance, patterns 1369
Shrinkage fits 648, 655–656, 663
allowances 648–650
Shut height, power press 1331

Copyright 2004, Industrial Press, Inc., New York, NY

SI system units
in strength of materials calculations 203, 213–215, 218, 221–224, 232, 236–237, 260, 273, 277–278, 280–281, 283–284, 286, 293–297, 300–302, 304–306
metric 143
use of in mechanics 141–145
SI, binary prefixes 2546
Side cutting edge 754
Side milling cutters 799
Sigma (standard deviation) 1246–1247
Significance of accuracy 1245–1248
Signs and abbreviations
mathematical 2542
scientific and engineering 2540–2543
Signs of trigonometric functions 89
Silicon carbide grinding wheels 971–972
Silver
bearing material 2264
brazing filler alloys 1382
plating 1470
Simple
indexing 2011–2016
proportion 6
stresses 213–214
Simpson's rule 60
Simultaneous equations 122
Sine bar
checking angle 696
checking taper per foot 697
checking templets 697
constants 699–705
measuring angle of templet 696
settling to a given angle 696
settling10- inch to an angle 697
types of 695
use of 695–705
Sine, law of 89
Single tooth contact 2031
Single-angle milling cutters 802, 808–809
Single-point cutting tools 749–772, 887–888
angle tolerances 772
carbide tips and inserts for 764–772
chipbreakers 755–756
definitions and terms 749–752
end cutting edge angles 754
indexable inserts 756–758
insert toolholders 756–764, 1310–1312
lead angles 754
nose radius 754, 771
numerical control tool compensation 1310–1312
planing tools 756
rake angles 753
relief angles 752
relief angles for thread cutting 1944
side cutting edge angle 754
tip overhang 765–766
tool contour 749
tool holders, indexable inserts 756–764
Singularity of a matrix 122
Sinking funds 128
Sintered
carbide tools
ANSI Standard 764–772
tool materials 1010–1012
gear materials 2147
metal bearings 2265
Sixty (60)-degree stub threads 1846
Size factor cover 2078
Sizes of sawn lumber 414
Slate cutting speed for 1082
Sleeve bearings 2229
Sleeves, Morse taper 935
Slenderness ratio, columns 285–286
Slides, measuring 713, 717
Slings
and fittings for wire rope 381–386
strength of rope and chain 387–390
Slipping clutches, couplings 2353
Slitting saws, metal 801
Slope of a line 40
Slots for T-bolts, ANSI Standard 1664
Slug 142
S-N diagrams 205, 207
Socket
ANSI hexagon and spline 1627
head, screw type
British Standard metric 1632
cap 1620–1623, 1633
drill and counterbore sizes for 1621
keys and bits for 1630
set 1637
shoulder 1624
reamers, Morse taper 851
taper shank 926–937
threads for electric 1884
wrench clearances 1531
Solders and soldering 1380, 1382
alloys for 1380
aluminum 1380
fluxes 1380
forms 1380
magnesium 1382
methods 1380–1382
stainless steel 1382
ultrasonic fluxless 1382
Solid film lubricants 2339
Solidification temperature 648
Solids, volumes and dimensions 75–80
Soluble oils for machining operations 1144
Solution heat treatment 504
Sorbite 521
Sound level specifications 1325
Space cutters, roller chain sprockets 2460–2461
Spacing holes on jig borer 989–1004
Spade drills and drilling
blades 1076–1077
drilling 1077, 1079
feed rates for 1078–1079
geometry of 1075–1079

Copyright 2004, Industrial Press, Inc., New York, NY

Spade drills and drilling *(continued)*
power consumption and thrust 1080–1081
Spandrel
area 67
center of gravity 227
Spark out time 1163
Spark plug
threads 1883
dimensions 1883
hole in cylinder head 1883
taps 911
Spatter, (welding) 1414
Specific gravity 407
conversion 408
gases 407
liquids 407–408
of various metals 407
oils 2334
plastics 416
Specific heat 399–400
aluminum 403
copper alloys 403
gasses 400
Speed reducers, motors, built-in 2473
Speeds
calculating cutting speeds 1016–1021
critical, of rotating shafts 306
pulleys, rules for calculating 2388
rpm for different diameters and cutting speeds 1016–1021
Speeds and feeds, machining 1009–1074
abrasive belt grinding 1230
bandsawing 1140–1143
CBN grinding wheels 1195
cutting 624, 1014, 1016, 1071, 1078, 1131–1143
drilling 1132
diameters and rpm 1017
feeds for spade drills 1078–1079
end milling 1040
face milling 1040
form-turning 1132, 1148
general 1071, 1131–1132
grinding wheels
maximum peripheral speeds 1210
truing and dressing 1198–1199
wheel and work speeds 1959
grinding with diamond wheels 1207
honing 1230–1235
milling 1022
nonferrous metals 1153–1156
reaming 1071, 1132
reaming and threading 1022
rotary files and burs 966
sawing
band 1140–1143
circular 1082
shaping 1082
slit and slot milling 1040, 1043–1058
Speeds and feeds, machining *(continued)*
superalloys 1039
surface grinding 1226–1228
tables, how to use 1022–1025
tapping and thread cutting 1061–1070, 1072–1074, 1132, 1920–1921
thread rolling 1955–1956
titanium and alloys 1038
tool life 1013–1025
adjusting 1035–1036, 1040, 1043, 1059
tool steels
drilling reaming, and threading 1066
milling 1049–1050
turning 1031
turning 1022, 1026–1040
carbon and alloy steels 1027–1030
copper alloys 1037
ferrous cast metals 1033–1034
hard-to-machine materials 1039
light metals 1038
speeds and feeds 1026–1040, 1132
stainless steels 1032
superalloys 1039
titanium 1038
tool steels 1031
Sphere
hollow
center of gravity 230
radius of gyration 235
polar moment of inertia 250
radius of gyration 235
surface area 78
volume 78
Spherical
and rectangular coordinates, relationship 43
coordinates 43
sector
center of gravity 230
polar moment of inertia 251
volume 78
segment
center of gravity 230
polar moment of inertia 251
volume 78
shell, thin 235
shells, strength to resist internal pressure 295–297
surface center of gravity 227
wedge volume 79
zone volume 79
Spheroidal graphite iron 474, 1361
Spheroidize, annealizing 450
Spheroidizing 450, 526
Spikes and nails, standard 1476
Spindle
for portable tools 948–951
function, NC 1280
noses 940–944, 1280, 1313
Spiral bevel gears 2029, 2082–2083
tooth contact 2082

Copyright 2004, Industrial Press, Inc., New York, NY

Spline keys and bits 1630
Splines 2159
application factors 2171
comparison of symbols 2177
data and reference dimensions 2169
dimensions, formula 2185
fatigue-life factors for 2172
fittings 2183–2185
fittings, torque capacity 2185
for large misalignments 2173
formulas for SAE standard 2185
involute 2156–2181
(see also Involute splines*)*
involute, socket keys and bits 1630
machining tolerances and variations 2180
milling cutter 824
SAE standard splined fittings 2184–2185
terms, symbols, and drawing data 2167
variations 2165
Spray transfer (welding) 1392
Spraying process, flame (metal) 1472
Spring 308–353
arbor diameters for 353
Belleville 348, 354–368
clock 348
compression, formulas for 321–322
coned 354–368
conical compression 348
constant force 348
copper-base spring alloys 311–312
deflections for
compression 325–328
extension 325–328
torsion 343–346
design data 319–353
disc 354–368
contact surfaces 355, 358
forces and stresses 358
group classes 354
materials 355
nomenclature 354
stacking 356
stress 358
elevated temperature stresses 318–319
endurance limit for spring materials 318–319
extension 324–333
extension spring design 331–333
failure in 352
force, disc 358
heat treatment of 348–350
helical compression spring design 320–324
helical, shock stresses produced in 283
high-carbon spring steels 309
index 319
materials 309–313
miscellaneous 348
moduli of elasticity 348
motor 348
Spring *(continued)*
music wire arbor diameters 353
nickel-base spring alloys 311–313
pins 1682–1683
shock stresses produced in helical 283
spiral 348
stainless spring steels 310–311
steels for 309–311
stresses 319–320
produced by shocks 283
tolerances
compression and extension 332–335
for torsion 341–348
torsion
bars 347
design 335–341
modulus 348–350
volute 347–348
wire
diameters for 309
maximum working temperature 312
tensile strength 421
Spring pins
coiled type 1683
designation 1682
lengths and sizes 1682
materials 1682
slotted type 1682
Spring washers
double coil rectangular section 1583
single coil square section 1584
Sprockets
chain transmission 2441
idler 2457
Spur gearing 2033
addendum modifications 2077
AGMA tolerances for fine pitch gears 2072
American National Standard tooth forms 2035, 2039
angular backlash 2073
backash range 2068
backlash 2067–2073, 2139
basic dimensions 2041
blanks for fine pitch gears 2064
British Standard 2076
bronze and brass gears 2147
caliper measurement of tooth 2051
center distance 2059
variable 2041, 2043, 2045
center distance for enlarged pinion 2058
checking gear size 2125
chordal
addendum 2048–2049, 2051
measurement 2142
thickness 2046, 2048–2049, 2051
circular
pitch system 2034, 2052
thickness 2046
given outside diameter 2045
composite error inspection 2073

Copyright 2004, Industrial Press, Inc., New York, NY

Spur gearing *(continued)*
contact
diameter 2059
lowest point of single tooth 2060–2063
ratio 2060
data on drawings 2067
diameters for hobbing, preshaving, and shaping 2042
diametral pitch shown full size 2033
diametral pitch system 2033–2034
dimensions and formulas 2035
drawing data 2067
enlarged pinions 2050, 2108–2111
external 2029
Fellows stub tooth systems 2041
fine-pitch 2039, 2064
finishing gear milling cutters 2054
formulas for basic dimensions 2161
full-depth, teeth 2035, 2046
gear milling cutters, series of
metric module 2052
gear tooth parts 2036–2041
checking 2125
German standard tooth form 2121
hob tip radius, maximum 2061
interference, avoiding 2050, 2052
internal 2029, 2074
internal arc thickness 2074
internal gear and pinion sizes 2074
internal gears rule 2075
involute curve properties 2034
lowest point of single tooth contact 2060
measurement of tooth with caliper 2051
measurement over pins 2125
measurement over wires 2135–2138
mesh with enlarged pinion 2058
milling cutters 2052
metric module 2052
minimum number of teeth 2058
module system 2121–2124
nonmetallic 625, 2149
outside and root diameters 2042, 2052
pinion arc thickness 2074
pitch diameters, tabulated 2052
profile checker settings 2062
reduced gear 2050
replacement gear dimensions 2153
root and outside diameters 2042, 2052
specifications 2065
to avoid undercutting by hob 2058
tooth
contact of highest point 2061
dimensions 2036–2041
forms 2035
measurements over wires 2135–2138
proportions 2039
thickness measurement 2045
true involute form (TIF) diameter 2061
undercut, limit for hobbed gears 2061
Square
area 63
circles of area equal to 73
distances across corners 74
of wire diameters 351
prism volume 75
recesses, for machine screws
for self-tapping screws 1642
roots of numbers 14
Square thread 1848
Squeeze casting 1366
Squirrel cage induction motors 2466
S-shapes, structural steel 2513
moment of inertia 2513
radius of gyration 2513
section modulus 2513
weight per foot 2513
Stabilizing gages 545
Stacking disc springs 356
Stainless steels 439, 457, 460
application 460–461
characteristics and applications 457
chemical compositions 448–449
coefficient of expansion 404
compositions 448–449, 460–461
cutting, flame 1418–1419
density 404
electrodes (welding) current to use with 1413
elongation 418, 472–473
hardness 418
heat treatments 536–537
mechanical properties 472–473
melting points 404
properties 460–461
soldering 1382
ultrasonic 1382
specific heat 404
speeds
for drilling, reaming, and threading 1067
for milling 1050–1051
for turning 1032
strength 474
tensile strength 418, 472–473
thermal conductivity 404
yield strength 418, 472–473
Stamping
blank diameters 1331
die clearances 1329
fine blanking 1344
lubricants for 1330
pressures required 1331
steel rule dies 1346–1348
Standard
deviation 1245–1247
NC 1255
nomenclature 2079
organizations 2079
wire gage (SWG) 2520

Copyright 2004, Industrial Press, Inc., New York, NY

Static 141
balancing 197
equivalent load, bearings 2319
load rating, bearings 2319
Statistical tolerance 641
Statistics
normal distributions 1245
standard deviation 1246
Stayed surfaces, flat 292
Steel
alloy
compositions of SAE 446–447
general properties 466–471
Bessemer 452, 454
carbon steel structure 507
carburizing 453, 455, 526
case hardening 526
cast for gears 2146
castings 1362
brinell hardness number 1363
elongation 1363
mechanical properties 1363
tensile strength 1363
yield point 1363
chromium
compositions 460
nickel austenitic 457, 460
classification 438, 443
cobalt high-speed 884–885
cobaltcrom 538
color of heated 522
coloring 1463
columns, pipe 290–291
corrosion-resisting 457–460
Damascus 441
deep-drawing 452
elongation 417
free-cutting 454, 456
stainless 457
gearing, hardness 2147
gearing, industrial 2147
hardening 503, 512
hardness 417
and tensile strength relationships 551
of heat-treated 466–471
heat treatment 449–450, 503–512, 538–547
of high speed steel 538
high-speed 480
hypereutectoid 510
hypoeutectoid 510
induction hardening 529
killed 452
molybdenum
compositions 457, 460
high-speed 488
nickel chromium, SAE compositions 457, 460
nickel, SAE compositions 457
SAE compositions 446–447
Steel *(continued)*
nitriding 527
numbering systems for 440–442
pipe
ANSI standard 2527
columns, allowable concentric loads 290–291
rimmed 452
rivets 1479
rolled sections, shape designations 2508
rule dies 1346–1348
cutting edges 1347
dimensions 1347
heat treatment 1348
makes 1347
SAE specification numbers 440, 442–443
sheet, standard gage 2522–2523
silicon-manganese, SAE compositions 446–447
stainless 448–449, 457, 460
strength 474
and hardness data 466–471, 474
of heat-treated 474
structural shapes 2508–2517
subzero treatment 544–547
taps 1920
tensile strength 417
tool 475–501
tungsten
compositions 490
high-speed 490
twist drill 884–885
wrought 2526
yield strength 417
Steel wool 966
Steel-threading screws
cast metals 1651, 1653
depth of panetration 1653
drill sizes 1653
hole sizes 1653
plastics 1651, 1653
Stellite alloy 1012
Step bearings 2242, 2248–2251
Stepper motors 2493
Stock, amount required for screw machine production 1136
Stoke 2586
Straight
bevel gears 2029
line 39
line column formula 285
pins 1672–1674
designation 1674
materails 1674
Straight pipe threads
free fitting mechanical joints 1864
hose couplings 1864
locknuts 1864
mechanical joints 1864–1865
Straight splines, British Standard 2182

Copyright 2004, Industrial Press, Inc., New York, NY

Strain
lateral 204
longitudinal 204
ratio of 204
Strength
hollow vs. solid shafts 307
of polygon connections 2187
of screws and bolts 1509
riveted joints 1479
struts or columns 285–291
tensile 204
ultimate 204
wire rope 370–377
yield perforated metal 2521
Strength of materials 203
angles, lengths of bent 2508
beams 272–276
shock stresses in 283
channels, elements of 2514, 2518
columns 285–291
AISC formula 289
AREA formula 285
Euler formula for 286–289
Gordon formula 285, 287
Johnson formula for 286
combined stresses 215–218
compression 205
critical speeds of shafts 306
curved beams 279
cylinders 294–298
definitions 203–204
deflection of beams 260–271, 277
Euler formula 286–289
factors of safety 208
ferrous metals 474
flat plates 292–294
heat-treated steels 466–471
hoop stress
thick-walled tube 609
thin-walled tube 609
influence of temperature 420
Izod impact 416, 466–471
J. B. Johnson column formula 286–289
keyways in shafts 305
linear deflection in shafts 302
mechanical properties 203–204
metals, properties of 420
modulus of elasticity 204
modulus of shear 204
moment of inertia 238–247
built-up sections 237
perforated metals 2521
pipe columns 290–291
plates, shells, and cylinders 292–298
polar
moment of inertia 248–249, 254–259
section modulus 248–249, 254–259
rails 281
Rankine, column formula 285, 287
rings, stresses and deflections 223–224
Strength of materials *(continued)*
section moduli tables 238–259
shafts 299–307
American Standard design code 305
brittle material formula for 305
critical speeds of 306
effect of keyways on strength of 305
horsepower transmitted by 299–302
torsional strength of 299–301
shear 203, 205
shells, spherical 295–297
shocks, stresses produced by 283
simple stresses 213–214
springs, shock stresses in 283
steels 474
straight-line column formula 285
stress 144, 203
areas of screw threads 1510
concentration factors
grooved shaft in torsion 212
shaft with transverse hole in bending 212
relieving 450
working 208
struts or columns 285–291
taper pins, strength of 224
temperature effects 421
tensile stress 203
torsional strength of shafting 299–301
tubes 297–298
wood 412
working stresses 208
Young's modulus 204
Stress 144
alternating 206–207
area of thread 1502, 1834
bending in flywheels 189
centrifugal in flywheels 188
combined 215–218
concentration factors 209–212
grooved shaft in torsion 212
shaft with transverse hole in bending 212
contact, in cams 2209–2210
cyclic 205
disc springs 358
hoop in flywheels 188–189
in beams 213–218, 260–283
in bolts when tightening 1497, 1505–1507
in flywheels 193
in involute splines 2172
in loaded ring 223–224
in rotating disks 193
in shafting 303–305
in splines
allowable contact stress 2078
allowable shear 2172
in springs 283, 319–320
produced by shocks 283
relieving 450

Copyright 2004, Industrial Press, Inc., New York, NY

Stress *(continued)*
shear 214
in beams 215–218
simple 213–214
spline teeth compressive 2173
strain curves 203–204
superposition of 215
three-dimensional, or triaxial 219–221
units and conversion of 2574–2576
working, of various materials 208
Structural shapes
aluminum 2518
steel 2508–2517
angles, properties of 2515–2517
channels, properties of 2514
I- or S-shapes, properties of 2513
standard designations 2508
strength 474
wide flange, properties of 2509–2512
Structure of carbon steel 510
Stub Acme screw threads 1825, 1837–1843
alternative 1843, 1846
ANSI Standard 1837–1846
basic dimensions 1826
designations 1843
formula for determining diameters 1843
limiting dimensions 1827
shear area 1827
stress area 1827
thread data 1846
thread form 1825, 1843
wire sizes for checking 1908
29- and 60-degree 1963, 1968
Stub screw machine reamers 847
Stub tooth gearing 2036, 2041
Fellows 2041
former American Standard 2036, 2041
outside and root diameters 2035, 2042
Stub's iron and steel wire gage 2520
Studs
British 1570, 1581
drive 1678
Studs and pins
designation 1678
hole sizes 1678
material 1678
standard sizes 1678
Subprogram, NC 1285
Subroutine, NC 1285–1287
Subtracting
decimal fractions 10
fractions 9
matrices 119
Subzero treatment of steel 544–547
carburized parts 546
Superhard tool materials (CBN) 1013, 1039, 1178, 1195, 1204
Surface
coatings for metals 1464–1471
finish and hardness of bearings 2225

Surface *(continued)*
grinding 1222–1228
advantages 1222
common faults and possible causes 1228
common faults and possible causes in 1227–1228
principal systems 1223–1225
process data for 1226
selection of grinding wheels for 1177–1188, 1222, 1225–1226
wheel recommendations 1225–1226
of revolution, area 60
roughness
measurements 731
produced by common production methods 729–730
produced by laser cutting 1449
relationship to tolerances 729, 731
speeds, diameters and rpm
grinding wheels 1209, 1211
pulleys and sheaves 1016, 1018–1021, 1943
speeds, diameters and rpm cutting speeds formula 1016–1021, 1943
Surface texture 725
applying symbols 732
castings 735
comparing measured values to specified limits 738
control and production 724
cutoff for roughness measurements 731
definition of terms 724, 726
drawing practices for symbols 731–733
error of form 724
finish 1162
differences between ISO and ANSI symbology 738
flaws 724
graphical centerline. 726
instruments of measurements 730
lay 724, 735
symbols 735–736
measurement 729
area avearaging methods 731
instruments 730
non-contact 730
probe microscope 730
skidded instruments 731
skidless instruments 730
max rule 738
profile 726
measured 726
modified 726
nominal 726
real 726
total 726
variation 2159, 2165
root mean square 729
roughness 724
average (Ra) 728, 734

Copyright 2004, Industrial Press, Inc., New York, NY

Surface texture *(continued)*
roughness
evaluation length 728
parameters 728
production method 730
profile 726
sampling length 727
spacing 726
topography 727
roughness average (Ra) 728
roughness sampling length 734
sampling length 727
spatial resolution 727
standard roughness sampling lengths 734
symbols 630, 731–733, 735
lay 735–736
material removal 732
proportions of 732
system height resolution 727
topography 727
measured 727
modified 727
traversing length 727
use of symbols 732
valley 727
waviness 725, 727
evaluation length 727, 729
height 729, 735
long-wavelength cutoff 727
parameters 729
profile 727
sampling length 727
short-wavelength cutoff 727
spacing 727
topography 727
Surveyor's measure 2549
Swing frame grinding 1229
Swiss pattern files 965
S-word, NC 1280
Sychronous belts
(see Belts and pulleys: sychronous belts*)*
Symbols
abbreviations 2540, 2542–2543
ANSI Y14.5M 630, 632–633
applying surface texture 732
arc and gas welding 1432–1440
arrow 1432
basic weld 1432
bearing
ball bearings 2269, 2271
cylindrical roller bearings 2272
needle bearings 2274
roller bearings 2269
self alignment roller bearings 2272
tapered roller bearings 2273
thrust ball bearings 2272
thrust tapered roller bearings 2273
between, ANSI 633
brazing 1387–1388
buttress threads 1850
Symbols *(continued)*
cams and cam design 2189
chemical elements 398
concentricity, ANSI 633, 1252
contour and finish 1433
controlled radius, ANSI 633
diameter, ANSI 633, 1251
diamond wheel marking 1201–1204
dimensions 1433
drawing practices for surface texture 731–733
gagemakers tolerance 678
geometric characteristic 633
geometric controls
forms 634
locations 634
orientation 634
profiles 634
runout 634
straightness 634
Greek 2540
grinding wheel markings 1179–1180
hole basis 669
involute splines 2159–2160, 2167
lines for drawings 630–631
mechanics 2543
metric module involute splines 2177
nondestructive testing 1441–1442
parallelism, ANSI 633, 1252
perpendicularity, ANSI 633, 1253
reference line 1432
roundness, ANSI 633, 1251
runout, ANSI 633, 1253
screw thread, for tap marking 916–917
section lining
aluminum 632
bronze 632
cast and malleable iron 632
earth 632
insulation 632
magnesium 632
materials 632
rock 632
sand 632
steel 632
white metal 632
shaft basis 669
standard geometric characteristic engineering drawing
section lining 630
statical tolerance, ANSI 633
surface profile, ANSI 633, 1251
surface texture 732–733, 735
tolerances 667
total runout, ANSI 633, 1253
welding 1432, 1442
System of measurement
absolute 142
gravitational 142
Système International d'Unites (SI)
in mechanics calculations 141–145

Copyright 2004, Industrial Press, Inc., New York, NY

T

Tangent 88
Tangential force 2078
Tanks
  contents at given level 61–62
  cylindrical, capacity in gallons 61–62
  quenching bath 518–519
Tantung alloy 1012
Tap drill diameters, Acme 919
Tap drill selection
  (see Taps and tapping: tap drills*)*
Taper
  American (ANSI) Standard 926–938
  applications of standard 937
  British Standard 927–928
  Brown & Sharpe 644, 926, 935–936
  collets 945–947
  for given angle 715
  gages for self-holding 934
  Jacobs 939
  Jarno 926, 937
  keys 2379
  machine tool spindle 644, 937
  measurement methods 698
  measuring with
    V-block and sine bar 698
  method of dimensioning 698
  milling machine spindles, arbors and spindle noses 940–944
  Morse 926–937
    stub taper shanks 927–928
  per foot and corresponding angles 714
  pin reamers 853, 1676
  pins 1674, 1677
    designation 1675
    diameter 1675
    drilling spefications 1675
    drills for 1674, 1677
    hole sizes 1674
    materials 1674
    small ends 1675
    strength 224
  pipe taps 900–901, 914
  reamers
    Brown & Sharpe 852
    Morse 851
  rules for figuring 715
  self-holding and self-releasing 926–934
  shaft ends, SAE Standard 2373
  steep machine 933, 938
Taper pipe threads 1860–1862
  angle of thread 1863
  basic dimensions 1861
  external 1863
  form 1860
  internal 1863
  lead 1863
Taper pipe threads *(continued)*
  pitch diameter formula 1860
  railing joint 1864
  taper 1860
  thread length 1860
  tolerances on taper 1863
Taps and tapping 1919–1944
  automatic screw machine 1132
  clearance holes
    ISO metric bolts and screws 1938
  CNC machine 1942
  cold form tapping 1939–1941
  coolant 1943
  cutting oils 1147
  cutting speeds 1061–1070, 1072–1074, 1132, 1921
  hole size before tapping 1935–1936
    Unified miniature thread 1925–1936
  length of engagement and tolerances 1935
  lubrication 1147
  methods of tapping 1919
  nitriding of 1920
  numerically controlled 1942
  pipe
    power for driving 1942
    tap drills for 1941
  pipe threads
    drill sizes 1941
    power required 1942
  pitch increased to compensate for shrinkage 1963
  rake angles for various materials 1921
  removing a broken tap 1941
  serial taps and close tolerances 1920
  speeds 1920–1921
  spiral
    fluted 1920
    pointed 1919
  square threads 919–921, 925
  steel 1920
  surface treatment of 1920
  tap drills
    Acme threads 919
    American National threads 1933
      machine screws 1934
    diameter of tap drill 1924
    ISO metric threads 1937
      coarse pitch 1937
      cold form 1941
    pipe
      Briggs (NPT) 1941
      Whitworth 1941
    Unified thread system
      cold form 1940
      miniature 1936
  tapping specific materials 1921
    alloy steel 1922
    aluminium 1923
    carbon steel 1921
    copper alloys 1924

Copyright 2004, Industrial Press, Inc., New York, NY

Taps and tapping *(continued)*
tapping specific materials
free cutting steel 1923
gray cast iron 1923
high temperature alloys 1923
high tensile strength steels 1922
malleable cast iron 1923
nodular cast iron 1923
stainless steel 1922
titanium and titanium alloys 1923
taps 892–895
Acme 919–921
drill hole size 921–922
adjustable 920–921
ANSI Standard 892–918
British Standard
ISO metric series 922–925
collapsing 919
definitions 892–895
fits, classes obtained 915
for Class 2B and 2C threads 915
fractional inch sizes 896–897, 911
hand, dimensions of standard 895, 903, 908–912
hand, types of 892
limits
cut thread 896–902, 911
machine screw 900
pipe 902
ground thread 897–903, 912
H- and L- numbers 916–918
pipe 901–902
H- and L- limits 897–898, 916–918
machine screw 903–913
markings
multiple-start threads 918
over or under-size pitch diameter 918
metric D or DU limit 918
standard 916
symbols for identifying 899, 916–918
metric sizes 896, 903–913
multiple-thread taps, marking 918
nut 892, 904, 910–911
pipe 892, 899–902, 914
straight 899–902, 914
limits 901–902
taper 899–902, 914
tolerances 900
pulley 892, 904, 910
spark plug 911
spiral
fluted 903, 906, 912
pointed 905–913
square thread 918–919, 921
straight fluted 895, 903, 908–909, 912
terms 892
thread series designations 916–917
tolerances 896–917
types of 892
Taps and tapping *(continued)*
tolerances on minor diameter 1934–1935
Unified thread form 1725
Taps and tapping tap drills
Acme threads 919
Taylor tool life equation 1023
T-bolts and T-slots, ANSI Standard 1664–1665
Tebi 2546
Teflon (TFE) bearings 2265
Temper designations, aluminum alloy 572–583
Temperature
absolute 2583
boiling points, various substances 399
changes in length due to 405
critical, heat treating of steel 504, 507, 511
effect on working stresses, of springs 318–319
fahrenheit and celsius 2583
ignition 403
influence on strength of metals 421
judging by color, steel 522
of carbon dioxide, solid 649
of freezing mixtures 403
of ignition, various materials 403
of lead bath alloys 523
of nitrogen, solid 649
required to develop tightening stress in bolt 1500, 1502
Temperature effects on grease 2338
Tempering 449–509, 521–523
double 524
in oil 522
in sand 524
insalt baths 522
lead bath temperatures 523
steel 450, 523
temperature 522
carbon steel tools 522
Tensile
modulus *(see* Modulus of: elasticity*)*
strength 204, 206–207
aluminum alloys 417, 575–583
ceramics 415
cobalt alloys 418
copper alloys 417, 556–568
copper-beryllium alloys 570
copper-silicon alloys 569
copper-zinc-tin alloys 569
Everdur 569
magnesium alloys 588
nickel alloys 418, 589–590
nonferrous metals 554
spring wire 421
stainless steel 418, 472–473
steel 417, 464–473
heat-treated 466–471
high-strength, low-alloy 463
relation to hardness 551

Copyright 2004, Industrial Press, Inc., New York, NY

Tensile *(continued)*
strength
titanium alloys 591
wood 412
strength, alloy steel 1364
strength, carbon steel 1364
strength, steel 1363
stress 203, 206
test 207
Thermal
conductance 401
conductance units conversion 2582
conductivity 401
aluminum 403
cast iron 404
ceramics 415
copper alloys 403
nickel alloys 404
stainless steels 404
titanium alloys 404
cracking of cutting tools 1148
energy 2583
expansion coefficients 402, 405
stresses 405
plastics 610
Thermometer scales 2583
Thicknesses, preferred
metal products 2523
uncoated metals and alloys 2522
Thin flat plate 232
Thin spherical shell
radius of gyration 235
Thread locking 2484
Threading cam, screw machine 1131, 1135
cutting speeds, threading dies 1131
Threads and threading 1725, 1776, 1783, 1787, 1794, 1797, 1803–1846
Acme thread 1825–1848
pitch diameter allowance 1827, 1832
aerospace screws, bolts and nuts 1805
Aero-thread 1890
allowance and tolerance 1855
American microscope objective (AMO) 1886–1889
American National form 1725
angle, wire method of testing 1906
ANSI Standard
Acme thread 1825–1843
buttress thread 1850–1856
form or profile 1725
M profile thread 1783–1803
allowances 1790–1791
basic profile 1727, 1788
coarse pitch 1787–1788
coated threads 1791, 1793
crest and root form 1784–1789
data 1786
design profile, M series 1784, 1787–1788
designations 1803

Threads and threading *(continued)*
ANSI Standard
external thread design 1789
external thread root 1789
fine pitch 1789
lengths of engagement 1791–1795
limiting dimensions 1798–1802, 1824
limits and fits 1787
limits of size 1793
major diameter tolerances 1795
minor diameter tolerances 1794, 1803
pitch diameter tolerances 1795
profile data 1786
profile series 1787
symbols 1785
thread series 1785, 1789
tolerance grades 1790–1793
MJ profile thread 1803–1806
Unified thread system 1732–1782
allowances 1736–1762
basic dimensions 1763, 1772
coarse thread series 1735–1763
coated 1776
definitions 1727–1731
design profile 1733
designations 1775–1776
dimensions 1736–1762
external and internal thread forms 1725, 1779
fine and extra fine series 1735–1768
hole sizes for tapping 1776
internal and external profile 1733
limits 1736–1762, 1773
miniature screw thread 1777–1781
miniature, design dimensions 1779
pitch diameter tolerances 1775
standard series, tables of 1736–1762
thread classes 1764–1768
thread form, data and formulas 1725, 1732–1735
thread series 1733
uniform 4-, 6-, 8-, 12-, 16-, 20-, 28-, and 32-pitch series 1735–1772
Briggs pipe thread 1890
British Standard
buttress threads 1849
ISO metric 1805, 1823
ISO profile 1814
pipe 1869–1871
RMS thread 1886
UNJ profile 1782
Whitworth 1857–1859
casing thread 1890
change gears for lathe 1946
for fractional output 1947
modifying the quick change gearbox output 1947
changing pitch slightly 1964
chasing, cutting speeds for 1061–1074

Copyright 2004, Industrial Press, Inc., New York, NY

Threads and threading *(continued)*
checking by three-wire method, tables 1901, 1906
classes of tolerance 1764–1832, 1850
Cordeaux thread 1891
crest diameter tolerance 1819
cutting 1944
numerically controlled 1291–1292
square 918–921
cutting, change gears 1946
fractional ratios 1947
Dardelet thread 1891
definitions 1727–1731
design and application data 1878
design dimensions and tolerances 1779
designation of Unified threads 1736–1776
designation symbols for 916–917
on taps, marks and symbols for identifying 916–917
deviation formulas 1818
diameter pitch combinations 1735, 1805, 1823
diameters of wires for measuring 1895
dies, maximum pitches 1964
dimensional effect of coating 1793
drunken thread 1891
dryseal pipe 1866
Echols thread 1891
electric socket and lamp base 1884
electrical fixture threads 1884
external thread tolerances 1798
formulas for three-wire measurement 1894–1895
French thread 1891
fundamental deviation 1790
gages for screw threads 1911
classification 1911
for unified screw threads 1911
standard tolerances 1917
grinding 1957–1960
centerless method 1961
Harvey grip thread 1891
helix angle 1729, 1763–1772
hole size for tapping 1776
hose coupling 1875–1876
instrument makers' 1884
interference fit 1729, 1877–1882
internal threads in pipe couplings 1864
International Metric thread system 1726
ISO metric 1727, 1805, 1823
design profile 1817
designation 1817–1818
fundamental deviation formulas 1818
lengths of thread engagements 1817
lead angle 1966
length of thread engagement 1729, 1817, 1819–1822
limiting dimensions formula 1793

Threads and threading *(continued)*
limits
Class 1A and 1B 1737–1762
Class 2A and 2B 1736–1762
Class 3A and 3B 1736–1762
limits and tolerance 1819–1822
Lloyd and Lloyd thread 1892
lock nut pipe thread 1892
Löwenherz 1849
M profile limits of size 1797
maximum material condition 1729
measuring screw threads 1893–1918
three wire method 1894–1911
contact pressure 1897
formulas 1898–1899, 1901, 1903, 1909–1910
accuracy 1904
Whitworth
best wire sizes 1896–1897
formulas 1899
metric screw threads
ANSI Standard
M profile 1783–1803
allowance 1783
comparison with inch threads 1783
MJ profile 1803–1806
designations 1807
diameter-pitch combinations 1804
symbols 1807
British Standard ISO metric 1814–1823
ISO metric 1727
British Standard 1814–1823
miniature 1814
trapezoidal 1807–1813
micrometers for measuring pitch diameters 1893
microscope objective thread 1885
milling 1962–1963
changing pitch of thread slightly 1963
classes of work 1963
multiple cutter method 1962
on numerically controlled machines 1291–1292
planetary method 1963
single cutter method 1962–1963
miniature
ISO metric 1814
Unified 1777–1781
minor diameter tolerances 1776
modified square thread, 10-degree 1848
multiple, designation 1776
National standard form or profile 1725
Philadelphia carriage bolt thread 1892
pipe
ANSI Standard 1860–1869
dryseal 1866–1869
taper 1860–1862
pitch 1730
pitch diameter 1730
pitch, changing slightly 1964

Copyright 2004, Industrial Press, Inc., New York, NY

Threads and threading *(continued)*
pitch, maximum when die cut 1963
pressure tight joints 1864
rolled lamp base threads 1884
SAE standard screw thread 1892
saw-tooth 1849
screw thread, definition 1731
self-forming screws 1639–1642, 1647
self-tapping screws 1642
Sellers screw thread 1892
sharp V-type thread 1725
spark plug threads 1883
square thread 1848
ten-degree modified 1848
stress area 1502, 1510, 1731, 1834
Acme thread 1827, 1831
Unified fine thread 1763
stub Acme screw threads 1825, 1837–1843
stub thread, 60-degree 1846
tap drill sizes 1925–1933
taper, measurement by wire method 1910
thread forms 1725
thread grinding
accuracy obtainable 1957
from the solid 1959
multi-ribbed wheels 1958
number of wheel passes 1958–1959
ribbed wheel for fine pitches 1959
roughing and finishing wheels 1958
single edge wheel 1957
wheels 1957
and work rotation 1959
grain size 1961
hardness of grade 1960
speeds 1960
truing 1960
types for 1957
work speeds 1960
thread rolling 1952–1956
advantages of process 1955
automatic screw machines 1953
blank diameter 1953
dies, cylindrical 1952
dies, flat 1952
in automatic screw machines 1953
machines used 1953
precision thread rolling 1953
production rates 1952
speeds and feeds 1955
steels 1953
thread selection 1775
tolerance system 1790, 1815
tolerances
grade dimensions 1797
of external threads 1795
of pitch diameter 1795
tools
relief angles, single-point 1944–1945

Threads and threading *(continued)*
tools for square threads 918–921
trapezoidal metric thread 1807, 1809, 1813
formulas 1808
US Standard 1725
watch 1777–1781
Whitworth 1887
truncated 1887, 1889
wire sizes for checking pitch diameters 1895–1896
Three-dimensional stress 219–221
Three-wire measurement
gears 2125–2143
screw threads 1894–1911
Thrust bearing *(see* Bearings: thrust)
Thumb screws
dimensions 1719
flat-head type 1716, 1719–1720
lengths 1719
materials 1716
points 1720
cone point 1720
cup point 1720
dog point 1720
flat point 1720
oval point 1720
threads 1720
types 1716
Tin lead, plating 1466
Tin plating 1471
Tin-base alloys, die casting 1373
Tin-lead alloys for soldering 1380
Titanium and titanium alloys
coefficient of expansion 404
density 404
melting points 404
properties 589, 591
specific heat 404
speeds and feeds 1038, 1074, 1142
thermal conductivity 404
Titanium Metals Corp. 591
Titanium carbides as cutting tool materials 1011
T-nuts, ANSI Standard 1666
Toggle joint 164
Tolerances 1312, 1815
ANSI Standard 652
application of tolerances 646
bilateral and unilateral 645
symbols 633, 667
ANSI symbols 1250–1253
ball and roller bearing 2278–2288
bilateral 637
British Standard 680
British Standard ISO threads 1815
buttress threads 1850–1851, 1854
clearence fit 666
compression spring 332–335
core drill, metric 881
cylindrical fits 645

Copyright 2004, Industrial Press, Inc., New York, NY

Tolerances *(continued)*
defined 645
designation of limits and fits 666
dimensions on drawings 645
drilled holes 884
extension spring 332–335
fundamental deviations 680
gagemakers 678
gages, direction of tolerances on 646
gear, composite tooth to tooth 2073
gear, composite total 2073
geometric 637
grades
relative to machining processes 652, 654, 679
hole basis 666
honing 1235
interference fit 666
involute splines, inch 2156
involute splines, metric 2177, 2180
ISO metric threads 1815
crest diameter tolerance 1819
finished uncoated threads 1819, 1822
tolerance classes 1816
tolerance grades 1816
tolerance positions 1816–1817
tolerances classes 1816
keys and keyways 2366
knurling 1244
limits and fits 680
nut threads 1815
obtainable by various operations 652, 654, 679
positional 640
free state 642
modifiers 640
projected zone 640
target plane 642
preferred series of 652
relationship to surface roughness 729, 731
shaft basis 666
statistical 641
symbols 633, 1250–1253
tapped holes 1934
taps 892–915
hand taps 896–900, 911
machine screw taps 898–900, 915
pipe taps 899–902, 914
thread gage 1914
torsion springs 341–348
transition fits 666
twist drill, metric 881
Unified thread gages 1917
unilateral 637
unilateral and bilateral 645
zone symmetry 637
Tolerancing and geometric dimensioning 630
Ton
long and short 2571
metric 2571
Tool
change schedule 1114–1115
compensation, NC 1310–1312
contour, cutting tools 749
cost per batch 1115
cost per edge 1116
cost, cutting 1115
data table 1280
forming 784–795
function, NC 1280–1282
grade, cutting 1059
grinding, angles 749–755
holders 758–764
letter symbols 760
indexable inserts 756–764, 779, 1310–1312
knurling 1240–1244
length offset, NC 1282
life 1013–1014, 1094, 1102, 1114
adjusting 1035–1036, 1040, 1043, 1059
adjusting factors
drilling 1059
end milling 1059
face milling 1059
reaming 1059
colding relation 1097
cutting speed 1107
drilling 1106
economic 1110
economy 1110
feed speed 1107
global optimization 1111
grinding 1106
milling 1106
optimization models 1110
optimum 1112
surface finish 1104
taylor's equation 1095–1097
turning 1106
life envelope 1099
life factors for turning
carbides 1035
CBN 1035
ceramics 1035
cermets 1035
polycrystalline diamond 1035
materials 773–783, 1009–1013
nose radius compensation, NC 1282, 1310–1312
offset, NC 1281
shanks, ANSI Standard for milling machines 942
sharpening
carbide tools 971
grinding wheels for 971–974
twist drills 968–971
single-point 749, 887–888
steels 475–501

Copyright 2004, Industrial Press, Inc., New York, NY

Tool *(continued)*
steels
air hardening 495
alloying elements effects 479–480
applications 487
chemical compositions 481
chromium types 491
classification of 480
cold work 494–495
cutting speed for 1031, 1049–1050, 1066
decarburization limits 501
dimensional tolerances 501
faults and failures, common 478–482
grindability of 478, 1189–1193
hardening 477
hardness 478
high-carbon, high-chromium 494
high-speed 488
hot work 491, 493
machinability 477
machining allowances 501
mechanical properties 475
mill production forms 500–501
mold 495, 497
molybdenum types 488, 493
numbering system 440, 442
oil hardening 495
properties of 475–478
shock resisting 495, 497
special purpose 495–499
speeds drilling, reaming, and threading 1066
speeds, milling 1049–1050
speeds, turning 1031
tolerances on dimensions 501
toughness 478, 481
tungsten types 490
water hardening 499–500
wear resistance 478
trouble-shooting checklist 1014
wear 967–969, 1093
Tooling cost equivalent 1115
Tooling cost time 1115
Tooth rest position
milling cutter grinding 831
reamer grinding 835
Torches, metal cutting 1419
Torque 141
calculating, for tightening bolts 163
capacity
formulas involute spline 2170
spline fittings 2185
clamping force 1503
coefficient 1504–1505
electric motor 2467, 2474
pull-up 2466
relationship to angular acceleration 172
starting, small bearings 2303
tension relation 1506
Torque *(continued)*
tightening, for bolts 1495–1507
torsion springs 335, 337
unit conversion 2577
Torsion
and bending of shafts, combined formulas 213, 219, 303–305
deflection of shafts, formula 301–302
formulas for shafts 299–301
modulus 213, 348–350
springs, design 341
strength of shafts 299–301
Torus
polar moment of inertia 251
volume 80
Total indicator reading, NC 1267
Toughness
HSLA steels 463
tool steels 481
Transmission chains 2441
cast roller chains 2441
detachable chains 2441
nonstandard 2441
pintle chains 2441
roller chain sprockets 2444
caliper diameter 2448
classes 2446
diameters 2446–2447
flange thickness 2449
manufacture 2461
materials 2461
proportions 2450
roller chains 2441, 2443
attachments 2445
bar steel sprockets 2450
bent link plate 2445
bore and hub diameters 2456
bottom diameter 2448
center distances and chain links 2456
cutters for sprockets 2461
cutting sprocket tooth forms 2460
design procedure 2464
dimensions 2443
drive ratings 2462
hob design 2459
horsepower ratings 2451–2464
idler sprockets 2457
installation and alignment 2463
keys, keyways and set-screws 2446
length of driving chain 2457
lubrication 2463
multiple strand cast sprockets 2450
nomenclature 2442
nonstandard 2441
numbering system 2444
parts 2442
pin dimensions 2445
pitch 2444
selection 2451
single strand cast sprockets 2450
straight link plate 2445

Copyright 2004, Industrial Press, Inc., New York, NY

Transmission chains *(continued)*
roller chains
tolerances 2444, 2448
tooth form 2458
tooth section profile dimension 2449
types 2441
ultimate tensile strength 2444
types 2441
Transmission shafting design 303–305
Transpose of a matrix 120
Trap rock, strength 420
Trapezium area 65
Trapezoid
area 64
center of gravity 226
moment of inertia 240
radius of gyration 240
section modulus 240
Trapezoidal screw threads 1807–1813
data 1809–1813
formulas 1808
Trepanning 1081, 1454
Tresca shear theory (plastics) 609
Triangle
acute 64, 88, 94–95
area 64
center of gravity 225
equilateral 88
geometry of 49
isosceles 88
moment of inertia 240
obtuse 64, 88, 94–95
radius of gyration 240
right-angle 64, 88, 91–93
section modulus 240
solution 88–95
oblique angle 94–95
right angle 91–93
Triaxial stress 219–221
Trigonometric
formulas 89–90
functions
of angles 88–107
signs of 89
using calculator to find 103
identities 89–90
tables 99–102
Trochoid curve 2032
Troostite 521
Trouble-shooting
broaching 961
drilling 1065
machining difficulties 1015–1016
reaming 840
tools 479–482
Troy weight for gold and silver 2571
Truing and dressing grinding wheels 1196–1200
T-section
moment of inertia 245
T-section *(continued)*
radius of gyration 245
section modulus 245
T-slots and T-bolts, ANSI Standard 1664–1665
T-slot cutters, standard 800
Tube 2526
collapsing pressure 297–298
gages 2519
maximum allowable pressures 298
strength of 297–298
subjected to external pressure
factor of safety 298
thickness and working pressure 297–298
wall thickness gages 2508, 2519
Tungsten
carbide tools grinding 971–973
carbide tools materials 1011
electrodes, welding 1409–1414
powdered alloys
density 419
elongation 419
hardness 419
rupture strength 419
ultimate strength 419
yield strength 419
steels 490
compositions 484, 490
high-speed, heat-treatment of 538
tool steels 490
Turner's sclerometer 551
Turning
and facing, insert holder 762–764
cutting speeds for
copper alloys 1037
ferrous cast metals 1033–1034
hard-to-machine materials 1039
light metals 1038
plain carbon and alloy steels 1027–1030
stainless steels 1032
superalloys 1039
titanium and titanium alloys 1038
tool steels 1031
unusual materials 1082
cutting time for 1082
cycles, NC 1291
insert holder 762–764
speed adjustment factors
depth of cut 1035
feed 1035
lead angle 1035
speeds and feeds 1026–1040, 1132
wood 414
Twist drill 854, 858–884
equivalent of gage or letter size 856–860
grinding (sharpening) 968–970
length of point on 877
parallel shank jobber 882
parallel shank long series 883
tolerances, metric 881

Copyright 2004, Industrial Press, Inc., New York, NY

Twist drill *(continued)*
types 854
T-word, NC 1280–1282
Type metal 585

U

U.S.
Board of Supervising Inspectors 292
Dept. of Commerce, formula for pressure in tubes 297
gallons into liters 2569
standard screw threads 1725
standard sheet metal gage 2522
UK gallons to liters 2566, 2569
Ultimate strength
common materials 420
compressive 205
copper-base powdered alloys 419
iron and steel 474
iron-base powdered alloys 419
nonferrous metals 554
plastics 598
shear 205
tungsten-base powdered alloys 419
Ultrasonic fluxless soldering 1382
Uncoated metals and alloys, preferred thicknesses, metric 2522
Undercut, in spur gearing 2050
Unified numbering system for metals *(see* UNS number)
Unified thread system
cold form tap drill sizes 1940
screw thread form 1725–1727, 1731–1782
British UNJ 1782
diameter-pitch combinations 1735
hole sizes for tapping 1776, 1925–1932
miniature screw thread 1777–1781
standard series 1733, 1736–1762
coarse thread 1763
constant pitch 1765–1772
extra-fine thread 1764–1765
fine thread 1763–1764
thread classes 1773–1775
thread designation 1775–1776
thread formulas 1734
threaded fasteners
bolts, screws, and nuts 1512–1539, 1570, 1587, 1605, 1614–1616, 1618–1620, 1622–1625, 1628, 1631, 1639, 1654, 1715, 1720
tensile stress area 1502–1503, 1510
tensile stress due to tightening 1498
Uniform motion 167
Unit systems
cgs 142, 2544
MKS 142, 2544
MKSA (m-kg-s-A) 2544
Unit systems *(continued)*
SI metric 2544, 2546–2547
US customary 2548
Units of measure and conversion factors
angular and circular 2550
Apothecaries' fluid 2567
area 2563
barrel 2567
dry 2567
electric wires 2563
energy 2581
flow 2570
fluid 2566–2567
force 2576
heat 2578
inertia and momentum 2587
length 2549
mass and weight 2571
Apothecaries' weight 2571
Avoirdupois or commercial 2571
Troy weight 2571
miscellaneous 2587
nautical 2549
power 2578, 2581
pressure and stress 2574
shipping 2566
surveyors 2549
temperature 2583
thermal conductance 2582
velocity and acceleration 2586
viscosity 2586
volume 2566–2567
work 2581
Universal joints 2348
angular velocity of driven shaft 2348
indermediate shaft 2349
maximum and minimum velocities 2348
UNS number 440
copper alloys 556–568
copper and copper alloys 555
number 444–445
plain carbon, alloy and tool steel 440, 442, 446–447
series of different metal 440
stainless steel 440, 448
Upsetting, steel for cold 452

V

Vacuum furnace brazing 1387
Van Keuren gear measuring tables 2125–2138
Vanadium, gearing material 2147
Variable speed belts *(see* Belts and pulleys: variable speed belts*)*
Varnish, pattern 1369
V-belts *(see* Belts and pulleys: V-belts*)*
Vector and scalar quantities 145
Velocity 141, 167–170
angular 167, 169

Copyright 2004, Industrial Press, Inc., New York, NY

Velocity *(continued)*
angular
rpm to radian per second conversion 169
converting to rpm 1016–1021
linear 167
of points on rotating bodies 169
unit conversion 2586
Vernier scale
dual metric-inch 693–694
reading 692
reading a metric 693
reading on a protractor 692
Versed sine and versed cosine 103
V-flange tool shanks and retention knobs 1313–1314
Vickers hardness 548
Viscosity 2332–2333
conversion table for lubricating oils 2586
dynamic 2345
oil 2341
pressure relationship 2345
temperature chart for SAE oils 2228
temperature effect 2341
unit conversion 2586
Vitrified bonded wheels 971–972, 1178
coolants for 1146
thread grinding 1957
Volume
air at different temperatures 428
barrel 80
cone 77
cube 75
cylinder 76
hollow 77
portion of 76–77
ellipsoid 78
frustum of cone 77
geometrical figures 75–80
measures 2566
nozzles 425
of flow in pipes and tubes 423, 427, 2531
of solids 75–80
paraboloid 79
paraboloidal segment 80
prism 75
prismoidal formula 59
pyramid 75
frustum of 76
solid of revolution 59
specific gravity 407–408
sphere 78
hollow 79
spherical
sector 78
segment 78
wedge 79
zone 79
square prism 75
torus 80
Volume *(continued)*
units and conversion of 2566, 2570
water at different temperature 422
wedge 76
V-process, casting 1366
V-projections, fine-blanking tools 1345
V-shaped groove, checking by pins 717
V-thread 1725
Vulcanized fiber, strength 420

W

Wahl spring curvature correction factor 318
Washburn & Moen wire gage 2520
Washers
ANSI, lock 1535
ANSI, plain 1532–1537, 1566, 1568
Belleville or disc spring 348, 354
British Standard metric 1584–1586
metric spring 1582–1584
designations 1585
metric 1566, 1568
designations 1568
materials 1568
preferred sizes 1532–1535
spring lock type 1536–1539
tooth lock type 1536–1539
Watch screw threads 1777–1781
Water
boiling point 422
density 423
flow in pipes 423–426, 2531
flow through nozzles 425
pressure 422
pressure, head or depth known 422
velocity due to head 426
volume of flow in pipes and tubes 427, 2531
Watt equivalent 2578
Waviness 724
height values 729
Wear life factor involute spline 2172
Wear resistance cutting tool 967–968
Wedge 161
center of gravity 230
mechanical principle of 161
spherical, volume 79
volume 76
Weight 143
air 428
angles, structural steel 2515–2517
avoirdupois or commercial 2571
castings, from pattern weight 1370
channels, structural 2514, 2518
earth or soil 410
hollow shafts 307
I-beams 2509–2513
metric measures 2571
mol 410
molecular 410

Copyright 2004, Industrial Press, Inc., New York, NY

Weight *(continued)*
nails and spikes 1476
of natural piles 409
per feet of wood 412
pipe, per foot 2527–2530
solid fuels 409
specific gravity 407–408
steel S-sections 2513
troy, for gold and silver 2571
water 422
wide flange, steel 2509–2512
wood 412–413
Weldability, HSLA steels 463
Welding 1389–1442, 1451
aluminum 1416
ANSI welding symbols 1432–1442
application of 1436–1440
nondestructive testing 1441–1442
arc cutting of metals 1419
basic symbols 1432–1433
codes, rules, regulations, specifications 1434
complete fusion 1428
controls 1393
current ranges diameter, sheet metal 1408
current selection 1412
cutting
metals
with electric arc 1419
with oxidizing flame 1418
with lasers 1447
definitions and symbols 1432–1440
designations 1435
dies 1441
dimensions 1433
electrode 1389–1390, 1394, 1412–1414
AWS E60XX 1406
AWS E70XX 1408
carbon steels 1390
characteristics 1407
composition 1412
current ranges 1413
diameters 1407
sizes 1390
stainless steels 1390
thoriated 1413
zirconiated 1413
electron beam welding 1424
FCAW (flux-cored arc) 1398–1405
all position electrodes 1401–1403
alloy steeels 1398
carbon steels 1398, 1400
contact tip recess 1401
deposition rates 1403–1405
electrodes 1398–1399, 1404
diameter 1403
gas shielded 1398, 1400
material condition 1399
pipe welding 1430
porosity and worm tracks 1401
Welding *(continued)*
FCAW (flux-cored arc)
selection 1399
settings 1399
shielding gases 1404–1405
stainless steeels 1398
weld requirements 1399
fill passes 1427, 1430–1431
filler metals 1414
fluxes 1389
gas shielded, all position 1398
GMAW (gas metal arc)
electrode diameters 1390
metal thickness 1395–1396
optimum settings 1397
shielding gases 1391, 1393
alloy steels 1391
aluminum 1393
carbon steels 1391
stainless steels 1392
spray transfer 1395–1397
welding sheet steel 1391
GTAW (gas tungsten arc) 1409–1414
aluminum 1413
current 1409
EWP electrode 1413
filler metals 1414
selecting tungsten electrode 1412–1414
shielding gases 1414
hard-facing 1420
horizontal pipe welding 1427
laser
cutting 1447–1451
welding 1451
letter designations for processes 1435
materials used in welding 1432
nondestructive testing 1441–1442
PAW (plasma arc) 1414
applications 1416
cutting 1417–1418
equipment 1415
fusion 1416
gases for 1414
of aluminum 1416
surface coating 1417–1418
surfacing 1417
pipe welding 1425
fill and cover pass procedures 1430–1431
positioning of joint components 1426
root welding procedure 1430–1431
tack welding procedures 1430
thick-wall 1429–1430
thin-wall 1428, 1431
plasma arc welding
gases 1414
shielding gases 1415
argon 1415
helium 1415
hydrogen 1415
process letter designation 1435

Copyright 2004, Industrial Press, Inc., New York, NY

Welding *(continued)*
process names 1389
root passes 1426
shielding gas 1414
SMAW (shielded metal arc) 1405–1409
characteristic of electrodes 1406
specifications 1434
supplementary symbols 1433–1434
symbol 1433
arrow side 1438
bead type back 1437
bevel groove 1436
built up surface 1437
electron beam 1436, 1440
fillet 1436–1437
intermittent fillet 1438
letter designations 1434
melt thru weld 1440
plug groove 1436
process 1434
resistance-seam 1436
single pass back 1437
square groove 1436
U- groove 1439
V-groove 1438
tungsten electrode compositions 1412
use of flux-cored electrodes 1428
vertical-up, vertical-down 1427
wire extension 1429–1430
Weldon shanks
dimensions of 804–814
end mills 804–805, 807
Wheel life in grinding
(see Grinding: wheel life*)*
Wheels
abrasive cutting 952–954
and pulleys in mechanics 162–163
buffing 1460
diamond 971–973, 1201–1207
dressing 1196–1199
flywheel
balance wheels 183
flywheel pulley 183
Geneva 163
grinding 1177–1200
diamond 1201–1207
mechanical principles of 162
polishing 1457, 1460
silicon carbide 971–972
White cast iron 1360
White metal bearing alloys 2261–2262
Whitworth
bolts, screws, nuts, washers, and studs 1570–1573, 1605, 1617, 1638
screw thread form 1725, 1857–1859, 1869–1870, 1885–1889, 1891–1892
drills for pipe taps 1941
measuring 1896–1897, 1899–1900, 1902
truncated thread 1887
wire size for measuring threads 1896
Wide-flange shapes, steel 2509–2512
moment of inertia 2509–2512
radius of gyration 2509–2512
section modulus 2509–2512
weight per foot 2509–2512
Winding drums, wire rope and chain 378–379, 391
Windlass 162–163
Wing nuts and screws
nuts
dimensions 1712–1715
finish 1716
materials 1716
standard 1712–1715
types 1712
screws 1712–1720
dimensions 1716
lengths 1719
materials 1716
points 1720
cone point 1720
cup point 1720
dog point 1720
flat point 1720
oval point 1720
threads 1720
types 1716
Wire
checking screw threads 1894
Acme threads 1899, 1908
buttress threads 1910
contact pressure 1897
formulas for large lead angles 1897–1908
taper screws 1909
circular mill measurement 2563
diameters, raised to powers 351
EDM 1349, 1358
music 351, 2519
nails and spikes 1476
preferred thicknesses 2523
rod gages 2519
rope 369–386
sheet metal gages 2522–2523
size for checking gears 2125
for external spur gears 2125
for helical gears 2139
for internal gears 2134
for spur and helical gears 2134
spring, tensile strength 421
tubing, wall thickness gages 2519
wire gages 2519
Wire rope
bending stresses 380–381
breaking strengths 370
classes 371–374
construction 369
cutting and seizing 380–381
definitions of terms 369–370
drum or reel capacity 378–379
drum score for winding 391

Copyright 2004, Industrial Press, Inc., New York, NY

Wire rope *(continued)*
factors of safety 375–376
installation 376–382
life 381
lubrication 381
maintenance 381
plow steel, strength of 372–377
properties 370–371
rated capacities of 382
replacement 381
rope loads due to bending 380–381
safe loads for 375–376
sheave and drum dimensions 378
simplified practice recommendations 374
sizes 372–377
slings and fittings 381
specification 370
strength 372–377
weight 372–377
Wood
bearings 2266
bonding 2480
boring 414
compression strength 412
crushing strength 411–412
density 413
dimensions of sawn lumber 413
hardmetal tooling for 783
ignition temperatures 403
machinability 413
maximum bending load 412
maximum crushing strength 411
mechanical properties of 412
effect of pressure treatment 412
mechanical property 411
modulus of rupture 411–412
mortising 414
patterns 1368
planing 414
sanding 414
screws 1477
shaping 414
shear strength 412
tensile strength 412
tooling for wood and nonmetals 783
Woodruff keys and keyseats
ANSI 2368
cutters 820
key 2372
dimensions 2369–2370
number 2372
keyseat
dimensions 2371–2372
hub 2372
milling cutter 2372
shaft 2372
British Standard 2385–2386
Woodworking cutters 783
Word address format, NC 1272–1274
Word, NC 1272–1274
Work 141, 174
formulas 174
formulas for work and power 178
maximum load in bending
wood 411
relation to energy 174
units conversion 2581
Working stress 204, 208, 216
at elevated temperature 319
factors of saftey 208
flywheels 189
of bolts 1509
shafts 305
springs 305, 319–320
Worm gearing 2095–2098
addendum 2096
ANSI Standard, fine-pitch 2095–2097
effect on profile and pressure angle
of cutting diameter 2097
of production method 2097
fine-pitch 2095–2098
formulas for dimensions 2096
hobs for 2095
lead angles 2095–2096
material 2098, 2149
number of threads or “starts” 2098
multi-thread worms 2098
single-thread worms 2098
outside diameter 2096
pitch diameters, range 2097
pitches, standard 2095
pressure angles 2095, 2097
proportions 2096
ratio of teeth to thread starts 2098
tooth form of worm and wormgear 2097
Worm wheel, indexing movements 2023
Wrapped spring clutches 2353
Wrench
clearances
for box wrenches 1530
for open end wrenches 1531
for socket wrenches 1531
for spacing of bolts 1530–1531
openings, ANSI Standard 1530
torque
cap screws 1496
steel bolts 1496
studs 1496
Wrought
copper alloys 560–568
copper-beryllium 570
iron
strength 474
temperature effect on 420
thickness gage for sheet 2522–2523
steel pipe 2526–2527

Copyright 2004, Industrial Press, Inc., New York, NY

Y

Yield point 204
for various materials 204
heat-treated steels 466–471
iron and steel 474
plastics 598
steel 1363
Yield strength 204
aluminum alloys 417, 575–583
carbon steel 1364
cobalt alloys 418
compressive 205
copper alloys 417, 556–568
Cu-base powdered alloys 419
Cu-beryllium alloys 570
Cu-silicon alloys 569
Everdur 569
iron-base powdered alloys 419
magnesium alloys 588
nickel alloys 418, 589–590
nonferrous metals 554
perforated metal 2521
plastics 598
shear 205
spring wire 421
stainless steel 418, 472–473
steel 417, 464–473
high-strength, low-alloy 463
titanium alloys 591
tungsten-base powdered alloys 419
Young's modulus *(see* Modulus of: elasticity*)*

Z

Zero suppression, NC 1274
Zero, absolute 2583
Zerol bevel gears 2029, 2082
Zinc plating 1471
Zinc-base alloys, die casting 1372
Z-section
moment of inertia 247
radius of gyration 247
section modulus 247

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX OF STANDARDS

Additional Indexes	Page
•Primary Index	2588
•Index of Interactive Equations	2689
•Index of Materials	2694

A

Aerospace Industries Association Standard
NAS 911 1257
NAS 912 1257
NAS 913 1257
NAS 914 1257
NAS 960 1257
NAS 963 1257
NAS 970 1257
NAS 971 1257
NAS 978 1257
NAS 990 1257
NAS 993 1257
NAS 994 1257
NAS 995 1257
Aerospace Standard
AS3215 1711
AS3216 1711
AS3217 1711
AS3218 1711
AS3219 1711
AGMA Standard
330.01 2085
370.01 2097
390.03 2069
112.05 2032
115.01 2032
116.01 2032
202.03 2085
208.03 2085
209.04 2085
390.03a 628
Alloys
babbitt, ASTM B23 2262
bearing and bushing
SAE J459c 2261
SAE J460e 2261
sintered bronze
ASTM B438-83a 2267–2268
sintered iron
ASTM B439-83 2267–2268
white metal, ASTM B23 2262
Aluminum
alloys for electroplating
ASTM B253 1467
anodic coatings for
MIL-A-8625F 1464, 1468
American National Standard
AFBMA/AFBMA Standard
American National Standard *(continued)*
AFBMA/AFBMA Standard
Std 7 2287, 2289–2290
Std 9 2308, 2318
Std 10 2324, 2327
Std 11 2313, 2318
Std 20 2279–2283
Std 8.2 2298–2301
Std 18.1 2285, 2292–2293
Std 18.2 2285–2286, 2291–2293
Std 24.1 2284
Std 24.2 2283–2284
ANSI Standard
ANSI B32.1 2523
B1.1 948, 1526, 1528, 1732
B1.3 1913
B1.5 1825, 1843
B1.7 1887
B1.9 1850–1851, 1854–1855, 1911
B1.11 1886–1889
B1.12 1877
B4.1 651, 653–654, 657–663, 665, 2289–2290
B4.2 665, 667, 670–677, 679, 690
B5.18 940, 942–944, 1313
B6.9 2095–2096
B7.1 948, 1208, 1210–1211, 1220, 1232
B47.1 1917
B74.2 952–954, 1180–1181, 1186, 1188
B74.3 1201–1203, 1205
B74.13 1179, 1204
B92.1 2160–2163, 2166, 2168, 2177–2178
B94.2 840–847, 849–853
B94.33 976–977, 979–984
B94.35 875, 878
B17.1 2363–2364, 2366–2368
B17.2 2369–2371
B18.3 1560
B18.17 1712–1720
B27.6 1711
B27.7 1684–1687, 1689, 1691–1692
B1.20.3 900, 1866, 1868
B1.20.4 1868
B1.20.5 1868
B18.1.2 1483, 1485–1487
B18.2.1 1512
B18.2.2 1512, 1530
B18.6.1 1477
B18.6.3 1587–1596
B18.6.4 1639, 1641–1644, 1646, 1654

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX OF STANDARDS

American National Standard *(continued)*
ANSI Standard
B18.8.1 1668
B18.22.1 1532–1533, 1535
B18.2.3.1M 1540–1541
B18.2.3.2M 1540, 1542, 1544
B18.2.3.3M 1540, 1543
B18.2.3.4M 1544
B18.2.3.5M 1540, 1544, 1550
B18.2.3.6M 1540, 1544, 1549
B18.2.3.7M 1540, 1548–1549
B18.2.3.8M 1540, 1545, 1552
B18.2.3.9M 1544
B18.2.4.1M 1540, 1561–1562
B18.2.4.2M 1540, 1561–1562
B18.2.4.3M 1540, 1561
B18.2.4.4M 1540, 1561, 1563–1564
B18.2.4.5M 1561, 1567
B18.2.4.6M 1540, 1561, 1567
B1.20.6M 1868
B18.3.1M 1542
B18.6.7M 1587
B18.16.1M 1561, 1566
B18.16.3M 1540, 1561, 1566
B1.3M 1803
B1.13M 1790
B1.13M 1556, 1563
B1.18M 1783
B4.4M 678
B32.4M 690
B92.2M 2156, 2176–2178, 2183
B94.55M 1014
B94.11M 854
B18.22M 1540, 1568–1569
B27.7M 1711
B27.8M 1711
B107.4 948
B212.1 756, 764–765, 767–772, 887–891
B212.3 1310
B212.4 757
B212.5 759–760
B212.12 757
X3.37 1293
Y10.4 2543
Y14.1 630
Y14.2M 632, 1322
Y14.5M 1250, 1314
Y14.36M 630, 731
Z17.1 689
Z136.1 1446
ANSI/AGMA 2005 2085
ANSI/CAM-I 101 1256
ANSI/EIA Standard
408 1256
431 1256
441 1256
449 1256
484 1256
494 1256

American National Standard *(continued)*
ANSI/EIA Standard
423-A 1256
491-A 1256
227-A 1256
358-B 1256
267-B 1256
232-D 1256
RS 274-D 1256, 1269–1270, 1272, 1274, 1277–1278, 1293
ANSI/RMA Standard
IP-20 2399–2401
IP-21 2406–2407
IP-22 2393–2395, 2397
IP-23 2414–2416
IP-24 2432, 2434–2437
IP-25 2422–2423
IP-26 2417–2418, 2420
ASME and ANSI/ASME Standard
ANSI/ASME B32.3M 2523–2524
B1.1 1732, 1762, 1775–1776
B1.2 1873, 1898, 1911, 1914, 1916, 1918
B1.5 921, 1825–1826, 1828–1829, 1831–1833, 1835, 1837–1842
B1.8 1826, 1832–1833, 1843–1845, 1847
B1.12 1877, 1879–1882
B1.15 1804
B5.50 1256, 1313–1314
B5.54 1256
B5.10 875, 929–934, 938
B5.15 2183
B46.1 724, 728
B94.6 1240, 1242–1243
B94.9 892, 896–915, 917–918
B94.19 797–817, 819–820
B18.3 1560, 1620–1624, 1626–1627, 1630–1631
B18.5 1525–1529, 1548
B1.20.1 1861–1865
B1.20.7 1872, 1874
B46.3.1 724
B18.1.1 1483, 1488–1490
B18.2.1 1512–1518, 1570
B18.2.2 1512–1513, 1519–1522, 1530, 1570
B18.6.2 1618–1619, 1625, 1628–1629
B18.8.2 1670–1674, 1677–1683
B18.21.1 1535–1539
B18.2.3.4M 1547
B18.2.3.5M 1550
B18.2.3.9M 1546
B18.5.2.2M 1547, 1551
B89.1.12M 1256
B18.1.3M 1485
B18.3.1M 1552, 1559–1560
B18.6.5M 1642, 1654–1659
B18.6.7M 1596–1604
B18.16.3M 1565
B18.21.2M 1535

Copyright 2004, Industrial Press, Inc., New York, NY

American National Standard *(continued)*
ASME and ANSI/ASME Standard
B1.3M 1732, 1775, 1882
B1.7M 1726–1727, 1732
B1.30M 1804
B1.13M 1783, 1785–1787, 1791–1792, 1794–1797, 1803–1804, 1807
B1.21M 1783, 1804–1806
B5.1M 1664–1666
B36.10M 2526–2527
B92.2M 2183
B94.11M 856, 864, 866–868, 873–874, 876
B29.1M 2441–2443, 2445–2449, 2455, 2458, 2462–2463
B29.3M 2442
Y14.2M 631
Y14.5M 630, 633–634, 637, 642, 732–733
Y14.36M 738
Y10.3M-1984 2543
AWS Standard
ANSI/AWS 2.4 1387, 1435, 1441
SAE Standard
ANSI/SAE
AS568A 2502
MA4030 1711
MA4035 1711
MA4036 1711
MA4016 1711
MA4017 1711
MA4020 1711
MA4021 1711
MA4029 1711
American Standards Association
ASA B1.1 1732
ASA B1.6 1887
ASA B1.10 1777, 1936
ASA B1.12 1578
ASA B5.38 949–951
ASA B17.1 303
ASA B18.2 1512, 1530
ASA B18.2.1 1512
ASA B17c 303
ANSI 2543
ANSI Technical Report
ANSI B11 TR2 1150, 1152
ASTM Standard
A31 1483
A307 1508, 1515
A325 1508, 1550
A354 1508, 1516
A449 1508, 1516
A490 1508, 1550
A502 1483
A131 1483
A152 1483
A255 508
A563M 1561, 1563, 1566
A574M 1550–1551

ASTM Standard *(continued)*
ASTM A743 1365
ASTM A220 1361
ASTM A297 1364
ASTM B32 1381
ASTM B633 1471
ASTM B253 1467
B438 2267–2268
B439 2267–2268
B23-83 2262
E18 2327
E140 551, 2327
E1497 1150
E1687 1150
F568 1550
F594 1514
F467M 1563
F837M 1551

B

Belts
synchronous
ANSI/RMA IP-24 2432, 2434–2437
V
drives using double-V
ANSI/RMA IP-21 2406–2407
drives using multiple
ANSI/RMA IP-20 2399–2401
drives using narrow multiple
ANSI/RMA IP-22 2393–2395, 2397
drives using variable-speed 2422–2423
light duty
ANSI/RMA IP-23 2414–2416
ribbed
ANSI/RMA IP-26 2417–2418
Bolts
British Association BS 57 1605
finished hexagon
ASA B18.2.1 1512
heavy hex
ANSI B18.2.3.6M 1540, 1544, 1549
heavy hex, structural
ANSI B18.2.3.7M 1540, 1548–1549
heavy hexagon, Unified, UNC and UNF thread, black
BS 1769 1512, 1570
hex
ANSI B18.2.3.5M 1540, 1544, 1550
ANSI/ASME B18.2.3.5M 1550
hexagon, ISO, black
BS 4190 1570, 1938
machine
BSW and BSF thread
BS 450 1605, 1614, 1617
precision hexagon
BSW and BSF thread
BS 1083 1570, 1572–1573
ISO **BS 3692** 1570, 1574–1578
Unified, UNC and UNF thread

Copyright 2004, Industrial Press, Inc., New York, NY

Bolts *(continued)*
precision hexagon
BS 1768 1512, 1570
round head (inch)
ANSI/ASME B18.5 1525–1529
ANSI/ASME B18.5.2.2M 1547–1548, 1551
square and hex (inch)
ANSI B18.2.1 1512
ANSI/ASME B18.2.1 1512–1518, 1570
ASA B18.2 1512, 1530
Unified, UNC and UNF thread, black
BS 2708 1570
British Standard
BS 45 1883
BS 46 2379, 2381–2385, 2387
BS 57 1605
BS 84 1570, 1859
BS 93 1570, 1886
BS 21 1869–1871
BS 308 2076
BS 3027 2076
BS 328 878–884
BS 3382 1578, 1605
BS 3550 2183
BS 3643 922, 924, 1579, 1606, 1814, 1819, 1822–1823
BS 3692 1570, 1574–1578, 1938–1939
BS 3696 2076
BS 4084 1782
BS 4168 1632–1637, 1938–1939
BS 4183 1605, 1607–1608, 1611–1613, 1938–1939
BS 4186 1938
BS 4190 1570, 1938
BS 4235 2374, 2376–2380
BS 436 2076–2078
BS 4320 1584–1586
BS 4464 1582–1584
BS 450 1605, 1614, 1617
BS 4620 1491–1492
BS 545 2076
BS 6186 2183
BS 641 1493
BS 721 2076
BS 821 2076
BS 949 922–923
BS 970 2374
BS 978 2076
BS 1083 1570, 1572–1573
BS 1157 1859, 1937–1938
BS 1387 1870
BS 1449 1584
BS 1580 1570
BS 1657 1849
BS 1768 1512, 1570
BS 1769 1512, 1570
BS 1981 1614, 1616
BS 1916 1669
British Standard *(continued)*
BS 2059 2182–2183
BS 235 2076
BS 2519 2076
BS 2693 1570, 1578, 1581
BS 275 1491, 1494
BS 2779 1869–1870
BS 2870 1584
BS 2827 1605
BS 4500 679–688, 2376
BS 6104 1632
BS 6105 1632
BS 1807 2076
BS 2708 1570
PD 3376 2076
PD 6457 2077
PD 6481 690–691

C

Castings
corrosion resistant, ASTM A743 1365
Copper
rolled and alloys, sheet, strip, and foil
BS 2870 1584

D

Deutsches Institut fur Normung
DIN 471 1711
DIN 472 1711
DIN 5417 1711
DIN 6799 1711
DIN 7993 1711
DIN 867 2121
DIN 984 1711
DIN 103 1807–1808, 1813
LN 471 1711
LN 472 1711
LN 6799 1711
Diamond and CBN
specification for shapes and sizes
ANSI B74.3 1201–1203, 1205
Dimensioning and tolerancing
ANSI Y14.5M 1250, 1314
ANSI/ASME Y14.5M 630, 633–634, 637, 642, 732–733
Drawing
engineering practice BS 308 2076
fundamental tolerancing principle
ISO 8015 630
line conventions and lettering
ANSI Y14.2M 631–632, 1322
method of indicating surface texture
ISO 1302 738, 740
sheet size and format
ANSI Y14.1 630
surface texture symbols
ANSI Y14.36M 630, 731

Copyright 2004, Industrial Press, Inc., New York, NY

Drawing *(continued)*
surface texture symbols
ANSI/ASME Y14.36M 738
symbols
welding, brazing, and nondestructive testing
ANSI/AWS A2.4 1387, 1435, 1441

E

Electronic Industries Association Standard
EIA AB3-D 1256
EIA Bulletin 12 1256

F

Fasteners
clearance holes for bolts and screws
ISO 273 1938
corrosion-resistant stainless steel
BS 6105 1632
externally threaded
mechanical and material requirements
SAE J429 1508–1509, 1516
SAE J995 1509
SAE J1199 1550
grade designation
SAE J429 1508–1509
SAE J995 1509
SAE J1199 1550
hexagon, width across flats
ISO R272 1578
mechanical properties
BS 6104 1632
ISO 898 1803
O-rings, ANSI/SAE AS568A 2502
o-rings, ANSI/SAE AS568A 2502
threaded
general rules for tightening
JIS B 1083 1502
Federal Specification
GGG-G-15A 743
GGG-G-15B 743
GGG-G-15C 743–745
RR-R-571a 378, 381
Flat metal products
preferred sizes
ANSI/A 2523–2524

G

Gage blanks, ANSI B47.1 1917
Gage blocks
GGG-G-15A 743
GGG-G-15B 743
inch and metric
GGG-G-15C 743–745
Gears
basic rack, ISO 53 2076
bevel, machine cut, BS 545 2076
classifIcation and inspection
AGMA 390.03 2069
cylindrical, ISO 54 2076
design
bevel
AGMA 330.01 2085
AGMA 208.03 2085
AGMA 209.04 2085
ANSI/AGMA 2005 2085
face gears, AGMA 202.03 2085
fine pitch, AGMA 370.01 2097
worm gear, fine pitch
ANSI B6.9 2095–2096
double circular arc type
PD 3376 2076
fine pitch, BS 978 2076
for traction, BS 235 2076
for turbines and similar drives
BS 1807 2076
geometry
AGMA 115.01
Basic Gear Geometry 2032
glossary of terms, BS 2519 2076
iron castings for BS 821 2076
master, BS 3696 2076
nomenclature, terms definitions, symbols and abbreviations
AGMA 112.05 2032
AGMA 116.01 2032
spur and helical
BS 436 2076–2078
guide to addendum modifications
PD 6457 2077
tooth proportions
coarse-pitch involute spur
USAS B6.1 2035–2037, 2039–2042, 2050, 2053
fine-pitch involute spur and helical
USAS B6.7 2039, 2042, 2054–2057, 2110
involute, **DIN 867** 2121
worm BS 721 2076
worm dimensions, BS 3027 2076
Grinding wheels
abrasive wheels, use, care, and protection
ANSI B7.1 948, 1208, 1210–1211, 1220, 1232
markings for identifying
ANSI B74.13 1179
shapes, sizes and identification
ANSI B74.2 1180

H

Hardness, metallic
conversion tables for ASTM E140 2327
test methods, ASTM E18 2327

Copyright 2004, Industrial Press, Inc., New York, NY

Hexagon wrench keys
BS 4168 1632–1637, 1938–1939

I

Iron
pearlitic malleable, ASTM A220 1361
ISO metric screw threads
BS 3643 1606
ISO Standard
ISO 53 2076
ISO 54 2076
ISO 68 1727, 1783–1784, 1788
ISO 3592 1257
ISO 4032 1561
ISO 4033 1561
ISO 4035 1561
ISO 4156 2176
ISO 4161 1561
ISO 4336 1257
ISO 4343 1257
ISO 4762 1542
ISO 8015 630
ISO 841 1257
ISO 8785 738
ISO 887 1568
ISO 898 1803
ISO 965 1790–1792, 1794–1796, 1807
ISO 230 1257
ISO 261 1804
ISO 273 1938
ISO 2972 1257
ISO 6983/1 1277
ISO 6983/2 1277
ISO 6983/3 1277
ISO 8038-1 1887
ISO 1302 738, 740
ISO 230-2 1248
ISO 26921 630
ISO 2806 1257
ISO 2904 1807–1809
ISO DR 911 1578
ISO DR 947 1578
ISO DR 950 1578
ISO DR 952 1578
ISO DR 987 1578
ISO R773 2374
ISO R774 2374
ISO R861 1542
ISO R272 1578
ISO R288 1578
ISO TC/600 2078
ISO TR 6132 1257
ISO/TC2/WG6/N47 1568

J

Japanese Industrial Standard
Japanese Industrial Standard *(continued)*
JIS B 6336 1248
JIS B 6338 1248
JIS B 1083 1502
JIS B 6201 1248

K

Keys and keyseats
ANSI B17.1 2363–2364, 2366–2368
ASA B17.1 303
metric, **BS 4235** 2374, 2376–2380
USAS B17.1 303
Woodruff
ANSI B17.2 2369–2371
BS 46 2379, 2381–2385, 2387

L

Lasers, safe use of, ANSI Z136.1 1446
Letter symbols
heat and thermodynamics
ANSI Y10.4 2543
mechanics and time-related
ANSI/ASME Y10.3M-1984 2543
Limits and fits
for engineering, BS 1916 1669
ISO
BS 4500 679–688
metric **BS 3643** 1579, 1606
metric **BS 4500** 2376
preferred
cylindrical ANSI B4.1 651, 653–654, 657–663, 665, 2289–2290
metric
ANSI B4.2 665, 667, 670–677, 679, 690

M

Metalworking fluids
mist control consideration
ANSI B11 TR2 1150, 1152
respiratory protection
NIOSH 1987a 1152
NIOSH 1987b 1152
virgin base oils
carcinogenic potential
ASTM E1687 1150
water miscible
standard practive for safe use
ASTM E1497 1150
Military Standard or Specification
DOD-P-16232-F 1470
MIL-A-8625F 1464, 1468
MIL-C-14550B 1466
MIL-C-13924C 1465
MIL-C-14538C 1464

Copyright 2004, Industrial Press, Inc., New York, NY

Military Standard or Specification *(continued)*
MIL-C-8837B 1471
MIL-C-5541E 1465
MIL-F-495E 1465
MIL-G-45204C 1468
MIL-L-46010D 1468
MIL-M-45202C 1466
MIL-M-3171C 1466
MIL-P-81728AT 1466
MIL-P-45209B 1469
MIL-R-21248 1710
MIL-R-27426 1693, 1695, 1697, 1699, 1711
MIL-R-46085B 1470
MIL-R-21248B 1711
MIL-T-10727C 1471
MS 3215 1706
MS 16624 1701
MS 16632 1704
MS 16633 1705
QQ-C-320B 1465
QQ-N-290A 1469
QQ-P-416F 1465
QQ-P-35C 1469
QQ-S-365D 1470
TT-C-490D 1469

N

National Electrical Manufacturers Association Standard
NEMA 1A1 1257
National Fire Protection Association
NFPA 1963 1875–1876
NFPA No. 194 1874
National Institute of Safety and Health
NIOSH 1987a 1152
NIOSH 1987b 1152
National Machine Tool Builders Association Standard, NMTBA 1257
Numerical control
ASCII 1256
axis and motion nomenclature 1256
binary input format
ANSI/EIA 494 1256
computerized (CNC), specification for
NAS 995 1257
coordinate measuring machines
methods for performance evaluation
ANSI/ASME B89.1.12M 1256
coordinate system and motion nomenclature, ISO 841 1257
data interface
asynchronous, ANSI/EIA 491-A 1256
parallel, ANSI/EIA 408 1256
serial
ANSI/EIA 449 1256
ANSI/EIA 232-D 1256
dimensional measuring interface standard
Numerical control *(continued)*
dimensional measuring interface standard
ANSI/CAM-I 101 1256
direct numerical control system
NAS 993 1257
electrical and mechanical interface for DNC and NC, ANSI/EIA 484 1256
electrical interface between machine tool and control, ANSI/EIA 431 1256
industrial automation systems
output file structure and language format, ISO 3592 1257
post processor commands
ISO 4343 1257
vocabulary, ISO 2806 1257
industrial cell controller, classification and selection
NEMA 1A1 1257
interface signals between NC unit and electrical equipment
ISO 4336 1257
machine tools
test code, ISO 230 1257
tool holders, NAS 970 1257
machines
composite filament tape laying
NAS 990 1257
drilling, NAS 960 1257
glossary of terms
EIA AB3-D 1256
horizontal boring, drilling, and milling
NAS 914 1257
milling
adaptive control system, NAS 994 1257
profiling and contouring, NAS 913 1257
spar, NAS 912 1257
precision measuring/inspection
NAS 971 1257
vertical and horizontal jig boring
NAS 963 1257
machining centers
methods for performance evaluation
ANSI/ASME B5.54 1256
NAS 978 1257
milling machines
skin/profile, NAS 911 1257
one-inch perforated tape
ANSI/EIA 227-A 1256
operator interface function
ANSI/EIA 441 1256
programming
program format and definition of address words
ISO TR 6132 1257
programming language
ANSI/EIA RS 274-D 1256
symbols ISO 2972 1257
Numerical control machines
program format and address words

Copyright 2004, Industrial Press, Inc., New York, NY

Numerical control machines *(continued)*
program format and address words
ISO 6983/1 1277
ISO 6983/2 1277
ISO 6983/3 1277
programming language
ANSI/EIA RS 274-D 1269–1270, 1272, 1274, 1277–1278, 1293
APT, ANSI X3.37 1293
Nuts
British Association BS 57 1605
crown (blind, acorn)
SAE J483a 1523
heavy hex
ANSI B18.2.4.6M 1540, 1561, 1567
heavy hexagon
Unified, UNC and UNF thread, black
BS 1769 1512, 1570
hex
flange
ANSI B18.2.4.4M 1540, 1561, 1563–1564
jam
ANSI B18.2.4.5M 1561, 1567
slotted
ANSI B18.2.4.3M 1540, 1561
style 1
ANSI B18.2.4.1M 1540, 1561–1562
style 2
ANSI B18.2.4.2M 1540, 1561–1562
hexagon high SAE J482a 1524
hexagon with flange
ISO 4161 1561
hexagon, ISO, black
BS 4190 1570, 1938
hexagon, thin, **ISO 4035** 1561
machine
BS 4183 1605, 1607–1608, 1611–1613, 1938–1939
BS 1981 1614, 1616
BSW and BSF thread
BS 450 1605, 1614, 1617
machine screw
ANSI B18.6.3 1587–1596
nonferrous specification for
ASTM F467M 1563
precision hexagon
BSW and BSF thread
BS 1083 1570, 1572–1573
ISO **BS 3692** 1570, 1574–1578
Unified, UNC and UNF thread
BS 1768 1512, 1570
prevailing-torque, hex and hex flange
ANSI B18.16.1M 1561, 1566
ANSI B18.16.3M 1540, 1561, 1566
ANSI/ASME B18.16.3M 1565
slotted and castle **ISO R288** 1578
square and hex (inch)
ANSI B18.2.2 1512, 1530
Nuts *(continued)*
square and hex (inch)
ANSI/ASME B18.2.2 1512–1513, 1519–1522, 1530, 1570
ASA B18.2 1512, 1530
Unified, UNC and UNF thread, black
BS 2708 1570
style 1 **ISO 4032** 1561
style 2 **ISO 4033** 1561
wing ANSI B18.17 1712–1720

P

Pins
clevis and cotter
ANSI B18.8.1 1668
taper, BS 46 2379, 2381–2385, 2387
taper, dowel, straight, grooved and spring (inch)
ANSI/ASME B18.8.2 1670–1674, 1677–1683
Pipe
wrought steel, welded and seamless
ANSI/ASME B36.10M 2526–2527
Plating standard
black chrome, MIL-C-14538C 1464
black oxide, MIL-C-13924C 1465
cadmium, QQ-P-416F 1465
chemical films, MIL-C-5541E 1465
chemical finish, black
MIL-F-495E 1465
chrome, QQ-C-320B 1465
copper, MIL-C-14550B 1466
gold, MIL-G-45204C 1468
lubricant, solid film
MIL-L-46010D 1468
magnesium anodic
MIL-M-45202C 1466
magnesium process
MIL-M-3171C 1466
nickel, QQ-N-290A 1469
palladium, MIL-P-45209B 1469
passivate, QQ-P-35C 1469
phosphate, heavy
DOD-P-16232-F 1470
phosphate, light, TT-C-490D 1469
rhodium, MIL-R-46085B 1470
silver, QQ-S-365D 1470
tin lead, MIL-P-81728AT 1466
tin, MIL-T-10727C 1471
vacuum deposited cadmium
MIL-C-8837B 1471
Power transmission
roller chains and sprockets, double-pitch
ANSI/ASME B29.3M 2442
roller chains, attachments, and sprockets
ANSI/ASME B29.1M 2441–2443, 2445–2449, 2455, 2458, 2462–2463
Preferred
limits and fits

Copyright 2004, Industrial Press, Inc., New York, NY

Preferred *(continued)*
limits and fits
cylindrical, ANSI B4.1 651, 653–654, 657–663, 665, 2289–2290
metric
ANSI B4.2 665, 667, 670–677, 679, 690
numbers
ANSI Z17.1 689
PD 6481 690–691
sizes
flat metal products
ANSI/ASME B32.3M 2523–2524
PD 6481 690–691
round, square, rectangle, and hexagon metal products
ANSI B32.4M 690
thickness
uncoated thin flat metals
ANSI B32.1 2523
Public Law 101-592 1512

R

Retaining rings
aerospace
internal, LN 472 1711
shafts LN 471 1711
ANSI B27.7 1684–1687, 1689, 1691–1692
for bearings with ring groove
DIN 5417 1711
internal DIN 472 1711
internal spring type DIN 984 1711
reinforced external **MA4030** 1711
round wire, snap type
DIN 7993 1711
shafts DIN 471 1711
spiral
dimensional limits
AS3219 1711
external
AS3216 1711
AS3218 1711
MA4016 1711
internal
AS3215 1711
AS3217 1711
MA4017 1711
MIL-R-27426 1693, 1695, 1697, 1699, 1711
uniform section
ANSI B27.6 1711
MA4035 1711
tapered
external **MA4020** 1711
internal **MA4021** 1711
internal, beveled
MA4029 1711
Retaining rings *(continued)*
tapered and reduced cross section
ANSI B27.7M 1711
ANSI B27.8M 1711
tapered and reduced section type
MIL-R-21248 1710–1711
tapered width, uniform thickness
MA4035 1711
Retaining washers
aerospace lock, for shafts
LN 6799 1711
Rivets
dimensions
BS 275 1491, 1494
general engineering
BS 4620 1491–1492
large
ANSI B18.1.2 1483, 1485–1487
small dimensions BS 641 1493
small solid
ANSI/ASME B18.1.1 1483, 1488–1490
ANSI/ASME B18.1.3M 1485
steel, ASTM A31 1483

S

SAE Standard
SAE J406 508
SAE J429 1508–1509, 1516
SAE J501 2373
SAE J995 1509, 1514
SAE J1199 1550
SAE J482a 1524
SAE J483a 1523
SAE J459c 2261
SAE J460e 2261
Screws
British Association BS 57 1605
heavy hex
ANSI B18.2.3.3M 1540, 1543
heavy hex, flange
ANSI B18.2.3.9M 1544
ANSI/ASME B18.2.3.4M 1547
ANSI/ASME B18.2.3.9M 1546
heavy, Unified, UNC and UNF thread, black
BS 1769 1512, 1570
hex
cap
ANSI B18.2.3.1M 1540–1541
flange
ANSI B18.2.3.4M 1544
ANSI/ASME B18.2.3.4M 1547
formed
ANSI B18.2.3.2M 1540, 1542, 1544
lag
ANSI B18.2.3.8M 1540, 1545, 1552
hex lag
ANSI/ASME B18.2.1 1518

Copyright 2004, Industrial Press, Inc., New York, NY

Screws *(continued)*
hexagon head cap
ASA B18.2.1 1512
ISO, black, **BS 4190** 1570, 1938
machine
ANSI B18.6.3 1587–1596
ANSI B18.6.7M 1587
ANSI/ASME B18.6.7M 1596–1604
BS 4183 1605, 1607–1608, 1611–1613, 1938–1939
BS 1981 1614, 1616
BSW and BSF thread
BS 450 1605, 1614, 1617
pressed, British Association and Whitworth thread
BS 2827 1605
metallic drive
ANSI B18.6.4 1639, 1641–1644, 1646, 1654
metric
hex cap
ANSI B18.2.3.1M 1540–1541
precision, BSW and BSF thread
BS 1083 1570, 1572–1573
precision, ISO
BS 3692 1570, 1574–1578
precision, Unified, UNC and UNF thread
BS 1768 1512, 1570
set
ANSI B18.3 1560
ANSI B18.3.1M 1542
ANSI/ASME B18.3 1620–1624, 1626–1627, 1630–1631
ANSI/ASME B18.3.1M 1552, 1559–1560
slotted headless 1618–1619, 1625, 1628–1629
square head
ANSI/ASME B18.6.2 1618–1619, 1625, 1628–1629
shoulder
ANSI B18.3 1560
ANSI B18.3.1M 1542
ANSI/ASME B18.3 1560, 1620–1624, 1626–1627, 1630–1631
ANSI/ASME B18.3.1M 1552, 1559–1560
slotted head cap
ANSI/ASME B18.6.2 1618–1619, 1625, 1628–1629
socket **BS 4168** 1632–1637, 1938–1939
socket head cap
ANSI B18.3 1560
ANSI B18.3.1M 1542
ANSI/ASME B18.3 1560, 1620–1624, 1626–1627, 1630–1631
ANSI/ASME B18.3.1M 1552, 1559–1560
socket head cap, hex
ISO 4762 1542

Screws *(continued)*
square and hex (inch)
ANSI B18.2.1 1512
ANSI/ASME B18.2.1 1512–1517, 1570
tapping
ANSI B18.6.4 1639, 1641–1644, 1646, 1654
tapping, thread forming and thread tapping
ANSI/ASME B18.6.5M 1642, 1654–1659
thread forming and cutting
ANSI B18.6.4 1639, 1641–1644, 1646, 1654
thumb and wing
ANSI B18.17 1712–1719
Unified, UNC and UNF thread, black
BS 2708 1570
wing
ANSI B18.17 1712–1720
wood, ANSI B18.6.1 1477
Shaft ends, SAE J501 2373
Solder, ASTM B32 1381
Spark plugs, BS 45 1883
Splines
involute
ANSI B92.1 2160–2163, 2166, 2168, 2177–2178
BS 3550 2183
metric module
ANSI B92.2M 2156, 2176–2178, 2183
BS 6186 2183
ISO 4156 2176
straight sided and serrations
BS 2059 2182–2183
Stainless steel
corrosion-resistant for fasteners
BS 6105 1632
for nuts ASTM F594 1514
for socket head cap screws
ASTM F837M 1551
Steel
alloy
for nuts
ASTM A563M 1561, 1563, 1566
for socket-head cap screws
ASTM A574M 1550–1551
quenched and tempered
for bolts, studs and external threaded fasteners
ASTM A354 1508, 1516
carbon
for bolts and studs
ASTM A307 1508, 1515
for nuts
ASTM A563M 1561, 1563, 1566
castings
heat resistant, ASTM A297 1364
for rivets and pressure vessels

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
for rivets and pressure vessels
ASTM A31 1483
hardenability
method for determining
ASTM A255 508
SAE J406 508
heat treated
for structural bolts
ASTM A325 1508
ASTM A490 1508
ASTM A325M 1550
ASTM A490M 1550
plate, sheet, and strip
British Standard
BS 1449B 1584
quenched and tempered
for bolts and studs
ASTM A449 1508, 1516
structural, for ships
ASTM A131 1483
tube, BS 1387 1870
wrought, BS 970 2374
Studs, screwed
BS 2693 1570, 1578, 1581
Surface texture
roughness, waviness and lay
ANSI/ASME B46.1 724, 728
terms, definitions and parameters
ISO 8785 738

T

Threads
Acme
ANSI B1.5 1825, 1843
ANSI/ASME B1.5 921, 1825–1826, 1828–1829, 1831–1833, 1835, 1837–1842
Acme, stub
ANSI/ASME B1.8 1826, 1832–1833, 1843–1845, 1847
British Association, BS 93 1570, 1886
buttress
ANSI B1.9 1850–1851, 1854–1855, 1911
BS 1657 1849
calculating and rounding dimensions
ANSI/ASME B1.30M 1804
class 5 interference-fit
ASA B1.12 1578
electroplated coating for
BS 3382 1578, 1605
gaging and gaging systems
ANSI B1.3 1913
ANSI B1.3M 1803
ANSI/ASME B1.3M 1732, 1775, 1882
general purpose, basic profile
ISO 68 1727, 1783–1784, 1788
Threads *(continued)*
Interference fit
ANSI B1.12 1877
ANSI/ASME B1.12 1877, 1880–1881
ISO metric
BS 3643 922, 924, 1579, 1606, 1814, 1819, 1822–1823
metric
ANSI B1.13M 1556, 1563
general purpose tolerances
ISO 965 1790–1792, 1794–1796, 1807
general purpose, **ISO 261** 1804
M profile
ANSI B1.13M 1790
ANSI B1.18M 1783
ANSI/ASME B1.13M 1783, 1785–1787, 1791–1792, 1794–1797, 1803–1804, 1807
ANSI/ASME B1.21M 1783, 1804–1806
M profile B1.18M 1783
trapezoidal
DIN 103 1807–1808, 1813
ISO 2904 1807–1809
microscope objective
ANSI B1.11 1886–1889
ISO 8038-1 1887
nomenclature ANSI B1.7 1887
nomenclature, definitions, and letter symbols for
ANSI/ASME B1.7M 1726–1727, 1732
pipe
dryseal
ANSI B1.20.3 900, 1866, 1868
ANSI B1.20.4 1868
gaging
ANSI B1.20.5 1868
ANSI B1.20.6M 1868
general purpose
ANSI/ASME B1.20.1 1861–1865
not pressure tight
BS 2779 1869–1870
pressure tight
BS 21 1869–1871
UN and UNR
ANSI B1.1 948, 1526, 1528
Unified
ANSI B1.1 948, 1526, 1528, 1732
ANSI/ASME B1.1 1732, 1762, 1775–1776
ANSI/ASME B1.12 1879, 1882
ASA B1.1 1732
BS 1580 1570
gaging
ANSI/ASME B1.2 1898, 1911, 1914, 1916, 1918
ANSI/ASME B1.20.1 1861–1865
ANSI/ASME B1.20.7 1873–1874
miniature, ASA B1.10 1777, 1936
UNJ

Copyright 2004, Industrial Press, Inc., New York, NY

Threads *(continued)*
Unified
ANSI/ASME B1.15 1804
BS 4084 1782
Whitworth
BS 84 1570, 1859
truncated, ASA B1.6 1887
Thumb screws
ANSI B18.17 1712–1720
Tolerances
gagemaker **ANSI B4.4M** 678
Tools and tooling
cutting
indexable inserts
ANSI B212.4 757
drill sizes for tapping
BS 1157 1859, 1937–1938
drills
BS 328 878–884
driver, split-sleve, collet type
ANSI B94.35 875, 878
twist
ANSI/ASME B94.11M 854, 856, 864, 866–868, 873–874, 876
driving and spindle ends
portable hand, air and air electric tools
ANSI B107.4 948
holders
indexable insert
ANSI B212.3 1310
ANSI B212.5 759–760
jig bushings
ANSI B94.33 976–977, 979–984
knurling
ANSI/ASME B94.6 1240, 1242–1243
machine tapers
ANSI/ASME B5.10 875, 929–934, 938
machine tools
accuracy, work and position
VDI/DGQ 3441 1247
determination of accuracy and repeatability
ISO 230-2 1248
running and rigidity tests
JIS B 6201 1248
machining center
test conditions, JIS B 6336 1248
V flange tool shanks
ANSI/ASME B5.50 1256, 1313–1314
milling
cutters
ANSI/ASME B94.19 797–817, 819–820
end mills
ANSI/ASME B94.19 797–817, 819–820
machine spindle noses
ANSI B5.18 940, 942–944, 1313
reamers
Tools and tooling *(continued)*
reamers
ANSI B94.2 840–847, 849–853
BS 328 878–884
single-point
carbide blanks, brazed and solid
ANSI B212.1 764–765, 767–772, 887–891
ANSI B212.12 756
spindles
portable tool, tapered and threaded
ASA B5.38 949–951
taps, ISO metric **BS 949** 922–923
tool life testing, ANSI B94.55M 1014
turning tools ANSI B212.12 757
Transmission shafting design ASA B17c 303
T-slots, bolts, nuts and tongues
ANSI/ASME B5.1M 1664–1666

U

USA Standard
USAS B6.1 2035–2037, 2039–2042, 2050, 2053
USAS B6.7 2039, 2042, 2054–2057, 2110
USAS B17.1 303

V

Verein Deutscher Ingenieure
VDI/DGQ 3441 1247

W

Washers
general purpose **BS 4320** 1584–1586
lock
ANSI/ASME B18.21.1 1535–1539
ANSI/ASME B18.21.2M 1535
plain
ANSI B18.22.1 1532–1533, 1535
ANSI B18.22M 1540, 1568–1569
ISO 887 1568
ISO/TC2/WG6/N47 1568
spring **BS 4464** 1582–1584
Wing nuts and screws
ANSI B18.17 1712–1720

Z

Zinc
electrodeposited coatings on iron and steel
ASTM B633 1471

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX OF INTERACTIVE EQUATIONS

Additional Indexes	Page
•Primary Index	2588
•Index of Standards	2677
•Index of Materials	2694

A

Air
- **C**ompressed, Velocity of Escaping 437
- Density of 428
- Expansion and Compression
  - Adiabatic 431
  - Isothermal 431
- Horsepower Required to Compress 432
- Volume given Pressure and Temperature 430
- Volume Transmitted through Pipes 436
- Work Required to Compress 431–432

Angle
- Conversion
  - Decimal to Degree-Minute-Second 97
  - Degree-Minute-Second to Decimal 97
  - Degree-Minute-Second to Radian 96
  - Radian to Degree-Minute-Second 96

Area
- Acute-angle Triangle 64
- Circle 66
- Circular Ring 67
- Circular Ring Sector 67
- Ellipse 68
- Enclosed by Cycloid 66
- Hyperbola 68
- Obtuse-angle Triangle 64
- Parabola 67
- Parallelogram 63
- Rectangle 63
- Regular Polygon 65
- Right-angle Triangle 64
- Spandrel or Fillet 67
- Square 63
- Trapezium 65
- Trapezoid 64

B

Beam
- Both Ends Overhanging Supports
  - Load at any Point Between 263
  - Single Overhanging Load 264

Beam *(continued)*
- Both Ends Overhanging Supports
  - Symmetrical Overhanging Load 264
  - Symmetrical, Uniform Load 262
  - Unsymmetrical, Uniform Load 263
- Combined Stresses
  - Direct Compression and Bending
    - Cantilever, Circular 216
    - Cantilever, Rectangular 216
    - Circular or Shaft 217
  - Direct Compression and Torsion
    - Circular or Shaft 217
  - Direct Compression, Offset Link 218
  - Direct Tension and Bending
    - Cantilever, Circular 216
    - Cantilever, Rectangular 217
    - Circular or Shaft 217
    - Rectangular 217
  - Direct Tension and Torsion
    - Circular Shaft 218
  - Direct Tension, Offset Link 218
- Continuous, Two Equal Spans
  - Equal Loads at Center of Each 270
  - Uniform Loads 270
- Continuous, Two Unequal Spans
  - Unequal Loads at any Point 271
  - Unequal Uniform Loads 269
- Design Example 221–223
- Fixed at Both Ends
  - Load at any Point 268
  - Load at Center 268
  - Uniform Load 269
- Fixed at One End
  - Free but Guided at the Other
    - Load at Free End 267
    - Uniform Load 267
  - Intermediate Load 265
  - Load at Other End 265, 272–273
  - Supported at the Other
    - Load at any Point 266
    - Load at Center 266
    - Uniform Load 267
  - Uniform Load 265, 272–273
- Supported at Both Ends
  - Load at Any Point 261
  - Load at Center 261
  - Single Load in Middle 272–273
  - Single Unsymmetrical Load 272–273
  - Two Symmetrical Loads 262, 272–273

Copyright 2004, Industrial Press, Inc., New York, NY

Beam *(continued)*
Supported at Both Ends
Uniform Load 261, 273
Uniform Load Part of Length
Deflection 272
Three Dimensional Stresses 220
Bearings
Journal Bearing 2240
Thrust
Flat Plate Type 2246
Step Type 2250
Tapered Land Type 2253
Tilting Pad Type 2258

C

Center of Gravity
Circle Sector 227
Circular Arc 226
Circular Segment 226
Cone 229
Cylinder 228
Frustum of Cone 229
Frustum of Pyramid 229
Half of a Hollow Sphere 230
Parabola 228
Paraboloid 230
Part of Circle Ring 227
Pyramid 229
Spandrel or Fillet 227
Spherical Sector 230
Spherical Segment 230
Trapezoid 226
Triangle 225
Two Bodies 229
Wedge 230
Circles and Squares with Equal Area 73
Circular Segment Formulas 66
Column
Eccentrically Loaded 287–288
Euler's Formulas 287
Rankine's Formulas 287
Combined Stresses
Direct Compression and Bending
Cantilever Beam
Circular 216
Rectangular 216
Circular Beam or Shaft 217
Direct Compression and Torsion
Circular Beam or Shaft 217
Direct Compression, Offset Link 218
Direct Tension and Bending
Cantilever Beam
Circular 216
Rectangular 217
Circular Beam or Shaft 217
Combined Stresses *(continued)*
Direct Tension and Bending
Rectangular Beam 217
Direct Tension and Torsion
Circular Shaft 218
Direct Tension, Offset Link 218
Complex Numbers
Addition 17
Division 18
Multiplication 18
Contents of Cylinderical Tank 62
Conversion
Complex Number to Polar Form 17
Coordinates
Cylindrical to Rectangular 44
Polar to Rectangular 17, 43
Rectangular to Polar 43
Rectangular to Spherical 44
Spherical to Rectangular 44
Cutting Speed to RPM 1016
Letter Drill Sizes 1017
Numbered Drill Sizes 1017
RPM to Cutting Speed 1016
Specific Gravity to Density 407
Temperature 2583
Critical Speed Formulas 196
Cutting Speed
Convert from RPM 1016
Convert to RPM 1016
Letter Drill Sizes 1017
Numbered Drill Sizes 1017

D

Density of Wood 413
Diameter of Circle Enclosing N Circles 84
Distance Across Squares and Hexagons 74
Drilling
Thrust, Torque, and Power Required
Inch 1091
Metric 1091
Spade Drills 1080

E

Economic Analysis
Annuity to Gradient 129
Depreciation 130
Future Value to Annuity 129
Future Value to Gradient 129
Net Present Value 131
Present Value to Annuity 129
Present Value to Future Value 129
Present Value to Gradient 129

Copyright 2004, Industrial Press, Inc., New York, NY

F

Factorial of a Number 18
Find Equation of Circle Given Point 45
Finding Depth of Keyseat 2374
Flat Belts and Pulleys
  Belt Lengths 2388
  Length of Belt Traversing Three Pulleys 2390
  Pulley Diameters and Speeds 2389
  Pulley Diameters in Compound Drive 2389
  Speed of Pulley in Compound Drive 2390
Force System Solution
  Components of Single Force 149, 153
  Resultant of
    Non-intersecting Forces 151
    Parallel Forces Not in Same Plane 154–155
    Three or More Forces 149
    Two Concurrent Forces 149

G

Gears
  Calculating Dimensions of
    Bevel
      Circular Thickness, Circular Addendum 2095
      Examples 2091
      Formulas for Milled Gears 2087
      14.5 and 20 Degree Full Depth 2154
    Helical
      Fellows 20 Degree Stub 2155
      Fine Pitch Tooth Proportions 2039
      14.5 and 20 Degree Full Depth 2155
      20 Degree Stub 2155
    Spur
      Fellows 20 Degree Stub 2153
      Fine Pitch Tooth Proportions 2039
      Outside and Root Diameters 2042
      Standard Dimensions 2035
      14.5 and 20 Degree Full Depth 2153
      14.5 Degree Involute Full Depth Tooth Parts 2041
      20 Degree Involute Full Depth Tooth Parts 2041
      20 Degree Stub 2153
  Helical Gearing 2099
    Shafts at Right Angles
      Center Distance Approximate 2103
      Center Distance Exact 2104
    Shafts Parallel
      Center Distance Approximate 2101
Gears *(continued)*
  Helical Gearing
    Center Distance Exact 2102
  Replacement Gear Dimensions
    Milled Bevel Gear 2154
    Spur Gear 2153
  Spur Gear Design 2062
    Center Distance 2045
    Center Distance for No Backlash 2059
    Chordal Addendum 2049
    Chordal Thickness 2049
    Example 2044
  Worm Gearing 2096

H

Hardness
  Brinell, Calculate from Indentation 547
  Tensile Strength Equivalent to Brinell 551

M

Machining
  Cutting Speed to Utilize Max Power
    Milling 1089
    Turning 1089
  Power Required
    Turning 1088
Matrix
  Addition 119
  Determinant 120
  Inverse 122
  Multiplication 120
  Solution of Simultaneous Equations 123–124
  Transpose 120
Measurement Over Pins
  Checking Radius of Arc
    Concave 719
    Convex 719
  Checking V-groove 717
  Distance across Bolt Circle 717
  Dovetail Slides 713
Measuring Screw Threads
  Acme Thread 1903, 1906
  American National Standard Unified Thread 1899
  British Association Screw Thread 1899
  British Standard and Whitworth Screw Thread 1899
  Buckingham Exact Involute Helicoid 1903–1904
  Constants for Measuring American Standard and Whitworth Screw Threads 1900

Copyright 2004, Industrial Press, Inc., New York, NY

Measuring Screw Threads *(continued)*
International Standard Screw Thread 1899
Lowenherz Screw Thread 1899
Pitch and Number of Threads per Inch 1896
Sharp V-Thread Screw Thread 1899
Whitworth Thread 1902
Wire Diameters 1900–1901
Moment of Inertia
Circle 241
Circular Ring 241
C-Section 244
Elliptical Section 242
Half Circular Section 241
Hexagon 240–241
Hollow Circular Section 242
Hollow Elliptical Section 242
Hollow Rectangle 239
Hollow Square 238
I-Section 242–245
L-Section 246–247
Polar Area
Circle 249
Circular Section with Hexagon Hole 249
Circular Section with Square Hole 249
Hexagon 249
Hollow Circular Section 249
Inverted Triangle 249
Rectangle 249
Square 249
Polar Mass
Cone 252
Cylinder 250
Ellipsoid 251
Frustum of Cone 252
Hollow Cylinder 250
Paraboloid 251
Prism 250
Pyramid 250
Sphere 250
Spherical Sector 251
Spherical Segment 251
Torus 251
Rectangle 239
Square 238
Trapezium 240
Triangle 240
T-Section 245–246
X-Section 247
Z-Section 247

P

Packing of Circles in Circles 82
Packing of Circles in Rectangles 86
Prismoidal Formula for Volume 59

R

Radius of Gyration
Bar of Small Diameter 232
Bar of Small Diameter Bent Circular 232
Cone 234
Cylinder 233
Ellipsoid and Paraboloid 235
Frustum of Cone 234
Hollow Cylinder 234
Hollow Sphere 235
Parallelepiped 233
Parallelogram 232
Rectangular Prism 234
Sphere 235
Thin Circular Section 233
Thin Hollow Cylinder 234
Thin Spherical Shell 235
Thin, Flat Circular Ring 233
Ratio of Volumes 80
Rearrangement of Formulas 29

S

Screw Threads
External Metric Thread - M Profile Limiting Dimensions 1800
Internal Metric Thread - M Profile Limiting Dimensions 1798
Pitch and Threads per Inch 1893
Unified Miniature Screw Threads 1780
Unified Screw Threads Dimension 1736
Shaft
Design of a Transmission Shaft 304
Design of Transmission Shafting 303
Diameter of Soild Circular Shaft (FPS unit) 299
Diameter of Solid Circular Shaft (MKS unit) 300
Torsional Deflection of Circular Shafts 301
Sheet Metal
Allowance for Bends 1335
Simple Mechanism
Inclined Plane Wedge 161

Copyright 2004, Industrial Press, Inc., New York, NY

Solution
Cubic Equation 33
First Degree Equation, Two Unknowns 31
Quadratic Equation 31
Factor 32
Specific Gravity
Conversion to Density 407
Spline
Basic Dimensions 2161
Dimensions and Tolerances 2179
Spring
Closed and Ground End 322
Open or Plain End
Ends Ground 322
Ends not Ground 322
Round Wire Spring Formula 322
Square Wire Spring Formula 322
Squared or Closed End, Ends not Ground 322

T

Taper
Angle given Diameter and Length 715
Angle given Taper 715
Center Distance given Diameter and Angle 716
Center Distance given Diameter and Taper 716
Center Distance given Taper Measured from One Side 716
Diameter of Disk in Contact with Another Disk 716
Measuring with V-block 698
Taper at Right Angle to One Side 716
Taper given Angle 715
Taper given Diameter and Length 715
Temperature
Adjusting Lengths for Changes of 405
Length Change Due to 406
Radius of Ring Change Due to 405
Temperature Conversion 2583
Triangle
Obtuse
One Side and Two Angles Known 94
Three Sides Known 95
Two Sides and Angle Opposite One Side Known 95
Two Sides, Angle Between Known 94
Right
Hypotenuse and Angle Known 91–92
Side and Angle Known 91–92
Side and Hypotenuse Known 91–92
Two Sides Known 91–92
Trigonometric Functions
Involute and Sevolute Functions 103
Table Values 99
Versed Sine and Versed Cosine 103

V

Volume
Barrel 80
Cone 77
Cube 75
Cylinder 76
Ellipsoid 78
Frustrum of Cone 77
Frustrum of Pyramid 76
Hollow Cylinder 77
Hollow Sphere 79
Paraboloid 79
Paraboloidal Segment 80
Portion of Cylinder 76
Prism 75
Pyramid 75
Sphere 78
Spherical Sector 78
Spherical Segment 78
Spherical Wedge 79
Spherical Zone 79
Square Prism 75
Torus 80
Wedge 76

W

Water
Velocity of, in Pipes 424

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX OF MATERIALS

Additional Indexes **Page**
•Primary Index **2588**
•Index of Standards **2677**
•Index of Interactive Equations **2689**

A

ABS
chemical resistance to various materials 608
coefficient of expansion 402
density 416
for plastics gearing 625
mechanical properties 416
safe bending stress 627
specific gravity 407, 416
speeds and feeds for drilling 623
Absolute zero 428
Acetal 402, 416, 592–593, 606, 608, 612–613, 619, 623, 625, 627
chemical resistance to various materials 608
coefficient of expansion 402
density 416
mechanical properties 416
paintability 625
safe bending stress 627
specific gravity 416
speeds and feeds for drilling 623
Acetic acid
specific gravity 408
specific heat 400
Acetyl
density 416
mechanical properties 416
specific gravity 416
Acetylene
specific gravity 408
Acrylic 402, 407, 416, 592–593, 606, 613, 622–623, 625
coefficient of expansion 402
density 416
mechanical properties 416
polishing 625
specific gravity 407, 416
speeds and feeds for drilling 623
Acrylic (polymethyl methacrylate)
drilling
point angle 622
Acrylite
polishing 625
Acrylonitrile butadiene styrene
for plastics gearing 625
Actinium
element properties 398
Air
atmospheric pressure 428
composition 428
density 428
at various pressures and temperatures 429
density-temperature relationship 428
expansion and compression 430
pressure-temperature-volume relationship 430
specific gravity 408
specific heat 400
weight of 428
Alcohol
boiling point 399
latent heat of evaporation 399
specific gravity 408
specific heat 400
wood
boiling point 399
Alcohol vapor
specific gravity 408
Alder
machinability of 414
weight of 413
Alloy steels
chemical composition 457
Alloys
aluminum
casting, AA number
A356.0 576–577
A357.0 575, 577
A444.0 575, 577
B443.0 575–577
C355.0 575–577
201.0 575–576
204.0 575–577
208.0 575–577
222.0 575–577
242.0 575–577
295.0 575–576
296.0 577
308.0 575, 577
319.0 575–577
328.0 575–576
332.0 575, 577
333.0 575, 577
336.0 575, 577
354.0 576–577
355.0 575–577
356.0 575–577
357.0 575, 577
359.0 577

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
aluminum
443.0 575–577
512.0 575–576
513.0 575, 577
514.0 575–576
520.0 575–576
535.0 576–577
705.0 575–577
707.0 575–577
710.0 575–576
711.0 575, 577
712.0 575–576
713.0 576–577
771.0 576
850.0 575–577
851.0 575–577
852.0 576–577
elastic properties 420
investment casting alloys
A354 417
A356 417
A357 417
C355 417
D712 (40E) 417
KO-1 417
Precedent 71 417
RR-350 417
355 417
356 417
wrought, AA number
Alclad 2014 580
Alclad 3003 581
Alclad 3004 581
Alclad 6061 582
Alclad 7075 583
1050 578
1060 578, 580
1100 578, 580
1145 578
1175 578
1200 578
1230 578
1235 578
1345 578
1350 578, 580, 583
2011 403, 578, 580
2014 580
2017 403, 578, 580
2018 578, 580
2024 403, 420, 578, 580
2025 578, 580
2036 578, 580
2117 578, 580
2124 578
2218 578, 580
2219 578, 580
2319 578
2618 578
3003 403, 579–581

Alloys *(continued)*
aluminum
3004 579, 581
3005 579
3105 581
4032 579, 581
4043 579
4045 579
4047 579
4145 579
5005 579, 581
5050 579, 581
5052 403, 579, 581
5056 579, 581
5083 579, 581
5086 403, 579, 582
5154 582
5183 579
5252 579, 582
5254 579, 582
5356 579
5454 582
5456 579, 582
5457 579, 582
5554 579
5556 579
5652 579, 582
5654 579
5657 582
6003 579
6005 579
6053 579
6061 403, 420, 579, 582
6063 582
6066 579, 583
6070 579, 583
6101 579, 583
6105 579
6151 579
6201 579
6253 579
6262 579, 583
6351 579, 583
6463 579, 583
7005 579
7008 579
7049 579, 583
7050 579, 583
7072 579
7075 403, 579, 583
7108 579
7178 579, 583
8017 579
8030 579
8176 583
8177 579
2011 403
2017 403
2024 403
2024-T4
elastic properties 420

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
aluminum
3003 403
5052 403
5086 403
6061 403
6061-T6
elastic properties 420
7075 403
bearing strength
magnesium alloys 588
chemical composition
alloy steels 457
carbon steels 457
copper alloys 556
everdur 569
titanium alloys 591
cobalt-base
investment casting alloys
cobalt 21 418
cobalt 25 418
cobalt 31 418
cobalt 36 418
F75 418
N-155 418
compressive strength
magnesium alloys 588
copper
alloy name (UNS number)
aluminum brass, arsenical (C68700) 567, 1037, 1072
aluminum bronze, D (C61400) 566, 1037, 1072
architectural bronze (C38500) 564, 1037, 1072
beryllium Cu
(C17000) 562, 1037, 1072
(C17200) 403, 562, 1037, 1072
(C17300) 403, 562
(C17500) 562, 1037, 1072
(C17510) 562
brass
catridge 70% (C26000) 403
extra-high-leaded (C35600) 403
free machining (C36000) 403
high-leaded (C35300) 403
naval (C46400) 403
red, 85% (C23000) 403
yellow (C27000) 403
bronze
aluminum 11% A (C62400) 403
aluminum 9% A (C62300) 403
commercial, 90% (C22000) 403
nickel aluminum (C63000) 403
phosphor 5% A (C51000) 403
phosphor, free cutting (C54400) 403
cadmium Cu
(C16200) 562
(C16210) 562
deoxidized (C14300) 561

Alloys *(continued)*
copper
deoxidized (C14310) 561
cartridge brass
70% (C26000) 403, 563, 1037, 1072
70% (C26100) 563
70% (C26130) 563
70% (C26200) 563
chromium Cu
(C18200) 403, 562
(C18400) 562
(C18500) 562
commercial bronze, 90% (C22000) 403, 563, 1037, 1072
Cu nickel
10% (C70600) 568, 1037, 1072
20% (C71000) 568
30% (C71500) 568, 1037, 1072
5% (C70400) 567
Cu– nickel– phosphorus– tellurium (C19100) 562
Cu–nickel–phosphorus (C19000) 562
forging brass (C37700) 564, 1037, 1072
free machining Cu (C14500) 403
free-cutting brass (C36000) 403, 564, 1037, 1072
gilding, 95% (C21000) 563, 1037, 1072
inhibited admiralty
(C44300) 565, 1037, 1072
(C44400) 565
(C44500) 565, 1037, 1072
jewelry bronze, 87.5% (C22600) 563, 1037, 1072
leaded brass
(C33500) 564, 1037, 1072
(C34000) 564, 1037, 1072
(C34200) 564, 1037, 1072
(C35000) 564
(C35300) 403, 564, 1037, 1072
(C35600) 403, 564, 1037, 1072
tube (C33000) 403, 563
tube (C33200) 564, 1037, 1072
leaded commercial bronze
(C31400) 563, 1037, 1072
nickel-bearing (C31600) 563
leaded Cu
(C18700) 403, 562
leaded naval brass (C48500) 1037, 1072
low brass, 80% 563, 1037, 1072
manganese brass (C66700) 567
manganese bronze, A (C67500) 567, 1037, 1072
Muntz metal
free-cutting (C37000) 564, 1037, 1072
leaded (C36500) 403, 564, 1037, 1072
leaded (C36800) 564, 1037, 1072
60% (C28000) 403, 563, 1037, 1072
naval brass

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
copper
(C46400) 403, 565
(C46700) 565
leaded (C48500) 565
medium-leaded (C48200) 565
nickel silver
55–18 (C77000) 568, 1037, 1072
65–10 (C74500) 568, 1037, 1072
65–12 (C75700) 568, 1037, 1072
65–15 (C75400) 568, 1037, 1072
65–18 (C75200) 568, 1037, 1072
oxygen-free
(C10200) 560, 1037, 1072
electronic (C10100) 560–562
extra-low phosphorus (C10300) 560
low phosphorus (C10800) 560
silver-bearing
(C10400) 560
(C10500) 560
(C10700) 560
phosphor bronze
1.25% E (C50500) 565
10% D (C52400) 566, 1037, 1072
5% A (C51000) 403, 565–566, 1037, 1072
8% C (C52100) 566, 1037, 1072
phosphorus deoxidized Cu
arsenical (C14200) 561
high residual phosphorus
(C12200) 561, 1037, 1072
low residual phosphorus
(C12000) 561
(C12100) 561
red brass, 85% (C23000) 403, 563, 1037, 1072
silicon bronze
high, A (C65500) 567, 1037, 1072
low, B (C65100) 567, 1037, 1072
silicon red brass (C69400) 567
sulfur bearing
(C14700) 561
(C14710) 561
(C14720) 561
tellurium bearing
(C14500) 403, 561
(C14510) 561
(C14520) 561
tough pitch
electrolytic (C11000) 403, 560–561, 1037, 1072
fire refined, with silver
(C12500) 561
(C12700) 561
(C12800) 561
(C12900) 561
(C13000) 561
silver-bearing
(C11300) 560
(C11400) 560
(C11500) 560
(C11600) 560
yellow brass
(C26800) 563, 1037, 1072
(C27000) 403, 563
zirconium Cu (C15000) 561
beryllium copper
elastic properties 420
brass
elastic properties
cast 420
70-30 420
low-leaded, tube (C33000) 403
bronze
elastic properties 420
manganese 403
elastic properties 420
investment casting alloys
beryllium Cu
10C (820) 417
165C (824) 417
20C (825) 417
275C (828) 417
brass
red 417
silicon 417
yellow leaded (854) 417
bronze
aluminum, C (954) 417
aluminum, D (955) 417
manganese, A 417
manganese, C 417
silicon 417
tin 417
chrome copper 417
copper (pure) 417
manganese bronze 403
nickel silver
elastic properties 420
nickel-silver 403
phosphor bronze
elastic properties 420
tensile strength 421
powder metal alloys
CNZ-1818 419
copper (pure) 419
CTG-1001 419
CTG-1004 419
CZP-3002 419
UNS number (alloy name)
C10100 (oxygen-free electronic) 560–562
C10200 (oxygen-free Cu) 560, 1037, 1072
C10300 (oxygen-free, extra-low phosphorus) 560
C10400 (oxygen-free, silver-bearing) 560
C10500 (oxygen-free, silver-bearing) 560

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
copper
C10700 (oxygen-free, silver-bearing) 560
C10800 (oxygen-free, low phosphorus) 560
C11000 (electrolytic tough pitch Cu) 403, 560–561, 1037, 1072
C11000 (electrolytic tough pitch) 403
C11300 (silver-bearing tough pitch Cu) 560
C11400 (silver-bearing tough pitch Cu) 560
C11500 (silver-bearing tough pitch Cu) 560
C11600 (silver-bearing tough pitch Cu) 560
C12000 (phosphorus deoxidized Cu, low residual phosphorus) 561
C12100 (phosphorus deoxidized Cu, low residual phosphorus) 561
C12200 (phosphorus deoxidized Cu, high residual phosphorus) 561, 1037, 1072
C12500 (fire-refined tough pitch with silver) 561
C12700 (fire-refined tough pitch with silver) 561
C12800 (fire-refined tough pitch with silver) 561
C12900 (fire-refined tough pitch with silver) 561
C13000 (fire-refined tough pitch with silver) 561
C14200 (phosphorus deoxidized Cu, arsenical) 561
C14300 (cadmium Cu, deoxidized) 561
C14310 (cadmium Cu, deoxidized) 561
C14500 (free machining Cu) 403
C14500 (tellurium bearing) 403, 561
C14510 (tellurium bearing) 561
C14520 (tellurium bearing) 561
C14700 (sulfur bearing) 561
C14710 (sulfur bearing) 561
C14720 (sulfur bearing) 561
C15000 (zirconium Cu) 561
C15500 561
C15715 561
C15720 561
C15760 562
C16200 (cadmium Cu) 562
C16210 (cadmium Cu) 562
C16500 562
C17000 (beryllium Cu) 562, 1037, 1072
C17200 (beryllium Cu) 403, 562, 1037, 1072

Alloys *(continued)*
copper
C17300 (beryllium Cu) 403, 562
C17500 (beryllium Cu) 562, 1037, 1072
C17510 (beryllium Cu) 562
C18200 (chromium Cu) 403, 562
C18400 (chromium Cu) 562
C18500 (chromium Cu) 562
C18700 (leaded copper) 403, 562
C18700 (leaded Cu) 403
C19000 (Cu–nickel–phosphorus) 562
C19100 (Cu– nickel– phosphorus–tellurium) 562
C19200 562
C19400 563
C19500 563
C21000 (gilding, 95%) 563, 1037, 1072
C22000 (commercial bronze, 90%) 403, 563, 1037, 1072
C22600 (jewelry bronze, 87.5%) 563, 1037, 1072
C23000 (red brass, 85%) 403, 563, 1037, 1072
C24000 (low brass, 80%) 563, 1037, 1072
C26000 (cartridge brass, 70%) 403, 563, 1037, 1072
C26100 (cartridge brass, 70%) 563
C26130 (cartridge brass, 70%) 563
C26200 (cartridge brass, 70%) 563
C26800 (yellow brass) 563, 1037, 1072
C27000 (yellow brass) 403, 563
C28000 (Muntz metal, 60%) 403, 563, 1037, 1072
C31400 (leaded commercial bronze) 563, 1037, 1072
C31600 (leaded commercial bronze, nickel-bearing) 563
C33000 (low-leaded brass tube) 403, 563
C33200 (high-leaded brass tube) 564, 1037, 1072
C33500 (low-leaded brass) 564, 1037, 1072
C34000 (medium-leaded brass) 564, 1037, 1072
C34200 (high-leaded brass) 564, 1037, 1072
C35000 (medium-leaded brass) 564
C35300 (high-leaded brass) 403, 564, 1037, 1072
C35600 (extra-high-leaded brass) 403, 564, 1037, 1072
C36000 (free machining brass) 403
C36000 (free-cutting brass) 403, 564, 1037, 1072
C36500 (leaded Muntz metal) 403, 564, 1037, 1072

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
copper
C36800 (leaded Muntz metal) 564, 1037, 1072
C37000 (free-cutting Muntz metal) 564, 1037, 1072
C37700 (forging brass) 564, 1037, 1072
C38500 (architectural bronze) 564, 1037, 1072
C40500 564
C40800 564
C41100 564
C41300 564
C41500 565
C42200 565
C42500 565
C43000 565
C43400 565
C43500 565
C44300 (inhibited admiralty) 565, 1037, 1072
C44400 (inhibited admiralty) 565
C44500 (inhibited admiralty) 565, 1037, 1072
C46400 (naval brass) 403, 565
C46700 (naval brass) 565
C48200 (naval brass, medium-leaded) 565
C48500 (leaded naval brass) 1037, 1072
C48500 (naval brass, leaded) 565
C50500 (phosphor bronze, 1.25% E) 565
C51000 (phosphor bronze, 5% A) 403, 565–566, 1037, 1072
C51100 565
C52100 (phosphor bronze, 8% C) 566, 1037, 1072
C52400 (phosphor bronze, 10% D) 566, 1037, 1072
C54400 403, 566, 1037, 1072
C54400 (free cutting phos. bronze) 403
C60800 566
C61000 566
C61300 566
C61400 (aluminum bronze, D) 566, 1037, 1072
C61500 566
C61800 566
C61900 566
C62300 403, 566
C62300 (aluminum bronze, 9%) 403
C62400 403, 566
C62400 (aluminum bronze, 11%) 403
C62500 566
C63000 403, 566
C63000 (Ni-Al bronze) 403
C63200 566

Alloys *(continued)*
copper
C63600 567
C63800 567
C64200 555, 567
C65100 (low-silicon bronze, B) 567, 1037, 1072
C65500 (high-silicon bronze, A) 567, 1037, 1072
C66700 (manganese brass) 567
C67400 567
C67500 (manganese bronze, A) 567, 1037, 1072
C68700 (aluminum brass, arsenical) 567, 1037, 1072
C68800 567
C69000 567
C69400 (silicon red brass) 567
C70400 (Cu nickel, 5%) 567
C70600 (Cu nickel, 10%) 568, 1037, 1072
C71000 (Cu nickel, 20%) 568
C71500 (Cu nickel, 30%) 568, 1037, 1072
C72200 568
C72500 568
C73500 568
C74500 (nickel silver, 65–10) 568, 1037, 1072
C75200 (nickel silver, 65–18) 568, 1037, 1072
C75400 (nickel silver, 65–15) 568, 1037, 1072
C75700 (nickel silver, 65–12) 568, 1037, 1072
C76390 568
C77000 (nickel silver, 55–18) 568, 1037, 1072
C78200 568
C80100 556
C80300 556
C80500 556
C80700 556
C80900 556
C81100 556
C81300 556
C81400 556
C81500 556
C81700 556
C81800 556
C82000 556
C82100 556
C82200 556
C82400 556
C82500 556
C82600 556
C82700 556
C82800 556
C83300 557
C83400 557
C83600 557

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
copper
C83800 557
C84200 557
C84400 557
C84500 557
C84800 557
C85200 557
C85400 557
C85500 557
C85700 557
C85800 557
C86100 557
C86200 557
C86300 557
C86400 557
C86500 557
C86700 557
C86800 557
C87200 557
C87400 557
C87500 558
C87600 558
C87800 558
C87900 558
C90200 558
C90300 558
C90500 558
C90700 558
C90900 558
C91000 558
C91100 558
C91300 558
C91600 558
C91700 558
C92200 558
C92300 558
C92500 558
C92600 558
C92700 558
C92800 558
C92900 558
C93200 558
C93400 558
C93500 558
C93700 558
C93800 558
C93900 558
C94300 558
C94400 558
C94500 558
C94700 559
C94800 559
C95200 559
C95300 559
C95400 559
C95500 559
C95600 559
C95700 559
C95800 559

Alloys *(continued)*
copper
C96200 559
C96300 559
C96400 559
C96600 559
C97300 559
C97400 559
C97600 559
C97800 559
C99300 559
C99400 559
C99500 559
C99700 559
C99750 559
copper-beryllium
10 570
165 570
25 570
35 570
50 570
copper-silicon (Everdur)
637 569
651 569
655 569
6552 569
661 569
elongation
aluminum alloys 580
everdur 569
magnesium alloys 588
titanium alloys 591
endurance limit
aluminum alloys 580
hardness
magnesium alloys 588
iron base
elastic properties
cast 420
ductile 420
grey cast 420
malleable 420
powder metal alloys
FC-0208 419
FC-0508 419
FC-0800 419
FC-2008 419
FC-2015 419
FL-4605 419
FL-4608 419
FN-0005 419
FN-0200 419
FN-0205 419
FN-0208 419
FN-0405 419
FN-0408 419
FX-2008 419
F-0000 419
F-0008 419
magnesium
casting, pressure die cast

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
magnesium
AM60A 587–588
AM60B 587–588
AS41A 587–588
AZ91A 587–588
AZ91B 587–588
AZ91D 587–588
casting, sand and permanent mold
AM100A 587–588
AZ63A 587–588
AZ81A 587–588
AZ91C 587–588
AZ91E 587–588
AZ92A 587–588
EZ33A 587–588
HK31A 587–588
HZ32A 587–588
K1A 587–588
QE22A 587–588
QH21A 587–588
WE54A 587–588
ZE41A 587–588
ZE63A 587–588
ZH62A 587–588
ZK51A 587–588
ZK61A 587–588
elastic properties 420
extrusion
AZ10A 587–588
AZ31B 587–588
AZ31C 587–588
AZ61A 587–588
AZ80A 587–588
HM31A 587–588
M1A 587–588
ZK40A 587–588
ZK60A 587–588
sheet and plate
AZ31B 587–588
AZ31C 587–588
HK31A 587–588
HM21A 587–588
nickel
Inconel
elastic properties 420
Monel metal
elastic properties 420
nickel-base
alloy name (UNS number)
commercially pure Ni (N02200) 590
hastelloy
hastelloy B (N10001) 590
hastelloy C-22 404
hastelloy C-276 (N10276) 404, 590
hastelloy W (N10004) 590
hastelloy X (N06002) 590
IN 100 (N13100) 590
incoloy
incoloy 800 (N08800) 590

Alloys *(continued)*
nickel-base
incoloy 825 (N08825) 590
incoloy 901 (N09901) 590
inconel
inconel X-750 (N07750) 590
inconel 600 (N06600) 590
inconel 625 (N06625) 590
inconel 718 404
Monel 404
Monel K500 (N05500) 404, 590
Monel R405 404
Monel 400 (N04400) 404, 590
nichrome (N06003) 590
nickel 200 (N02200) 404, 590
nickel 201 (N02201) 404
nickel 205 (N02205) 404
RA 333 (N06333) 590
udimet (N07500) 590
waspalloy (N07001) 590
investment casting alloys
Alloy B 418
Alloy C 418
Alloy X 418
Inconel
In 600 418
In 625 418
Invar (Fe-Ni alloy) 418
Monel
E 418
M-35 418
RH 418
S 418
410 418
specific heat 404
shearing strength
aluminum alloys 580
magnesium alloys 588
stainless steel
AFC-77 1032, 1051
AF-71 1032, 1051
AISI (SAE) Number
... (51430F) 536
201 (30201) 1032, 1050, 1067
202 (30202) 1032, 1050, 1067
203EZ () 1032, 1050, 1067
301 (30301) 1032, 1050, 1067
302 (30302) 474, 1032, 1050, 1067
303 (30303) 1032, 1050, 1067
303MA () 1032, 1050, 1067
303Pb (30303) 1032, 1050, 1067
304 (30304) 1032, 1050, 1067
305 (30305) 1032, 1050, 1067
310 (30310) 1032, 1050, 1067
316 (30316) 1032, 1050, 1067
317 (30317) 1032, 1050
321 (30321) 474, 1032, 1050, 1067
347 (30347) 474, 1032, 1050, 1067
410 (51410) 536, 1032, 1050, 1067
414 (51414) 536, 1032, 1051, 1067
416 (51416) 536, 1032, 1050, 1067

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
stainless steel
420 (51420) 474, 1032, 1050, 1067
430 (51430) 474, 536, 1032, 1050, 1067
431 (51431) 536, 1032, 1051, 1067
440A (51440A) 1032, 1051, 1067
440B (51440B) 1032, 1051, 1067
440C (51440C) 1032, 1051, 1067
442 (51442) 536, 1032, 1050
446 (51446) 474, 536, 1032, 1050
455 (51455) 1032, 1051, 1067
501 (51501) 474, 536, 1032, 1050, 1067
AISI (SAE) number
... (51409) 461, 537
... (51416F) 461
... (51420F) 461, 537
... (51430F) 461, 537
... (51434) 537
... (51436) 537
... (51440F) 461, 537
201 (30201) 448, 457, 460, 472, 536
202 (30202) 448, 458, 460, 472, 536
301 (30301) 448, 457–458, 460, 472, 535–536
302 (30302) 448, 458, 460, 472, 536
303 (30303) 448, 458, 472, 536
303 (30330) 536
304 (30304) 448, 458, 460, 472, 536
305 (30305) 448, 458–460, 472, 536
310 (30310) 448, 458, 460, 472, 536
316 (30316) 448, 458–459, 461, 472, 536
317 (30317) 448, 459, 461, 472, 536
321 (30321) 448, 459, 461, 472, 536
325 (30325) 461, 536
347 (30347) 448, 459, 461, 472, 535–536
410 (51410) 449, 459, 461, 472, 537
414 (51414) 449, 459, 461, 473, 537
416 (51416) 449, 459, 472, 537
420 (51420) 449, 459–461, 473, 537
430 (51430) 448, 459–461, 473, 537
431 (51431) 449, 459, 461, 537
440A (51440A) 449, 460–461, 473, 537
440B (51440B) 449, 460–461, 473, 537
440C (51440C) 449, 460–461, 473, 537
442 (51442) 448, 460–461, 537
446 (51446) 448, 460–461, 473, 537
501 (51501) 449, 460–461, 473, 537
AISI (UNS) Number
201 (S20100) 1032, 1050, 1067
202 (S20200) 1032, 1050, 1067
203EZ (S20300) 1032, 1050, 1067
301 (S30100) 1032, 1050, 1067
302 (S30200) 1032, 1050, 1067

Alloys *(continued)*
stainless steel
302B (S30215) 1032, 1050, 1067
303 (S30300) 1032, 1050, 1067
303MA () 1032, 1050, 1067
303Pb (S30300) 1032, 1050, 1067
303Se (S30323) 1032, 1050, 1067
304 (S30400) 1032, 1050, 1067
304L (S30403) 1032, 1050, 1067
305 (S30500) 1032, 1050, 1067
308 (S30800) 1032, 1050, 1067
309 (S30309) 1032, 1050, 1067
309 (S30900) 1032, 1050, 1067
309S (S30908) 1032, 1050, 1067
310 (S31000) 1032, 1050, 1067
310S (S31008) 1032, 1050, 1067
314 (S31400) 1032, 1050, 1067
316 (S31600) 1032, 1050, 1067
316L (S31603) 1032, 1050
317 (S31700) 1032, 1050
321 (S32100) 1032, 1050, 1067
330 (N08330) 1032, 1050
347 (S34700) 1032, 1050, 1067
348 (S34800) 1032, 1050, 1067
403 (S40300) 1032, 1050, 1067
405 (S40500) 1032, 1050, 1067
409 (S40900) 1032, 1050, 1067
410 (S41000) 1032, 1050, 1067
414 (S41400) 1032, 1051, 1067
416 (S41600) 1032, 1050, 1067
416Se (S41623) 1032, 1050, 1067
420 (S42000) 1032, 1050, 1067
420F (S42020) 1032, 1050, 1067
420FSe () 1032, 1050, 1067
429 (S42900) 1032, 1050, 1067
430 (S43000) 1032, 1050, 1067
430F (S43020) 1032, 1050, 1067
430FSe (S43023) 1032, 1050, 1067
431 (S43100) 1032, 1051, 1067
434 (S43400) 1032, 1050, 1067
436 (S43600) 1032, 1050
440A (S44002) 1032, 1051, 1067
440B (S44003) 1032, 1051, 1067
440C (S44004) 1032, 1051, 1067
440F (S44020) 1032, 1050, 1067
442 (S44200) 1032, 1050
446 (S44600) 1032, 1050
455 (S45500) 1032, 1051, 1067
501 (S50100) 1032, 1050, 1067
502 (S50200) 1032, 1050
AISI (UNS) number
201 (S20100) 448, 457, 472, 536
201 (S20200) 448, 458
201 (S20500) 448, 458
202 (S20200) 448, 458, 472, 536
205 (S20500) 448, 458
301 (S30100) 404, 448, 457–458, 472, 536
302 (S30200) 404, 448, 458, 472, 536
302B (S30215) 404, 448, 458, 472
303 (S30300) 404, 448, 458, 472, 536

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
stainless steel
303Se (S30323) 404, 448, 458, 472
304 (S30400) 404, 448, 458, 472, 536
304Cu (S30430) 404, 448, 458
304L (S30403) 448, 458, 472
304N (S30451) 448, 458
305 (S30500) 404, 448, 458–459, 472, 536
308 (S30800) 404, 448, 458, 472
309 (S30309) 448, 458, 460, 472, 536
309 (S30900) 404, 448, 458, 472, 536
309S (S30908) 404, 448, 458, 472
310 (S31000) 404, 448, 458, 472, 536
310S (S31008) 404, 448, 458, 472
314 (S31400) 448, 458, 472
316 (S31600) 404, 448, 458–459, 472, 536
316F (S31620) 448, 458
316L (S31603) 448, 458, 472
316N (S31651) 448, 458
317 (S31700) 404, 448, 459, 472, 536
317L (S31703) 404, 448, 459
321 (S32100) 404, 448, 459, 472, 536
329 (S32900) 448, 459
330 (N08330) 448, 459
347 (S34700) 404, 448, 459, 472, 536
347 (S34800) 404
348 (S34800) 448, 459, 472
384 (S38400) 404, 448, 459
403 (S40300) 404, 449, 459, 472
405 (S40500) 404, 448, 459, 473
409 (S40900) 448, 459
410 (S41000) 404, 449, 459, 472, 537
414 (S41400) 404, 449, 459, 473, 537
416 (S41600) 404, 449, 459, 472, 537
416Se (S41623) 404, 449, 459, 472
420 (S42000) 404, 449, 459–460, 473, 537
420F (S42020) 404, 449, 459, 473
422 (S42200) 404, 449, 459
429 (S42900) 404, 448, 459
430 (S43000) 404, 448, 459–460, 473, 537
430F (S43020) 404, 448, 459, 473
430FSe (S43023) 404, 448, 459, 473
431 (S43100) 449, 459, 537
434 (S43400) 448, 459–460
436 (S43600) 404, 448, 460
440A (S44002) 404, 449, 460, 473, 537
440B (S44003) 404, 449, 460, 473, 537
440C (S44004) 404, 449, 460, 473, 537
440F (S44020) 473
442 (S44200) 448, 460, 537
446 (S44600) 404, 448, 460, 473, 537
501 (S50100) 404, 449, 460, 473, 537
502 (S50200) 404, 449, 460, 473

Alloys *(continued)*
stainless steel
alloy, AISI-SAE (UNS) number
30615 () 451–452
30705 () 452
30805 () 451
30905 () 451–452
51210 () 452
51710 () 452
AM-350 1032, 1051
AM-355 1032, 1051
AM-362 1032, 1051
elastic properties
18-8 420
HNM 1032, 1051, 1067
investment casting alloys
austenitic
CF-16F 418
CF-20 418
CF-3 418
CF-3M 418
CF-8 418
CF-8C 418
CF-8M 418
CH-20 418
CK-20 418
CN-7M 418
IC 316F 418
IC 321 418
hardenable
Am-355 418
CA-15 418
CA-40 418
CD-4M Cu 418
IC 15-5 418
IC 17-4 418
IC 416 418
IC 431 418
powder metal alloys
SS-303N1 419
SS-304N1 419
SS-316L 419
SS-410 419
Stainless W 1032, 1051, 1067
15-5PH 1032, 1051
17-14CuMo 1032, 1051
17-7PH 1032, 1051
18-8
tensile strength 421
steel
alloy, AISI-SAE (UNS) number
E4340 (G43406) 442, 446
E50100 (501) 457
E51100 (G51986) 442, 447
E51100 (G52986) 457
E52100 (G52986) 442, 447, 451–452, 457, 474, 535, 1029, 1047, 1063, 1086
10B46 (G10461) 445
1045 (G10450) 444, 453–454, 465, 474, 1028, 1046, 1061

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
10956 () 452
1320 (G13200) 451–452, 456, 533
1330 (G13300) 442, 446, 456–457, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
1335 (G13350) 442, 446, 457, 535, 1029, 1047, 1063, 1086
1340 (G13400) 442, 446, 457, 467, 469, 535, 1029, 1047, 1054, 1063, 1086
1345 (G13450) 442, 446, 1029, 1047, 1063
2317 (G23170) 451, 456, 533
2330 (G23300) 451–452, 457, 535
2340 (G23400) 451–452, 457, 535
2345 (G23450) 451–452, 457, 535
2512 (G25120) 533
2515 (G25150) 451, 456
2517 (G25170) 533
30905 () 451–452
3115 (G31150) 451–452, 456, 533
3120 (G31200) 451–452, 456, 533
3130 (G31300) 451–452, 457, 535
3135 (G31350) 451–452, 456–457, 535
3140 (G31400) 451–452, 457, 467, 474
3145 (G31450) 451, 457, 535
3150 (G31500) 451, 457, 535
3240 (G32400) 451
3310 (G33100) 451, 456, 474, 533
3316 (G33160) 533
4012 (G40120) 1029, 1047, 1054, 1062
4023 (G40230) 442, 446, 451–452, 456, 474, 1029, 1047, 1054, 1062, 1086
4024 (G40240) 442, 446, 456–457, 1029, 1047, 1062, 1086
4027 (G40270) 442, 446, 451, 456, 1054, 1086
4028 (G40280) 442, 446, 456–457, 1029, 1047, 1062, 1086
4032 (G40320) 451, 456, 533, 1029, 1047, 1054, 1063, 1086
4037 (G40370) 442, 446, 457, 469, 535, 1029, 1047, 1054, 1063, 1086
4042 (G40420) 451–452, 457, 469, 535, 1029, 1047, 1063, 1086
4047 (G40470) 442, 446, 457, 535, 1029, 1047, 1063, 1086
4053 (G40530) 535
4063 (G40630) 451–452, 456–457, 535
4068 (G40680) 535
41L30 (G41403) 1029, 1047, 1062
41L40 (G41404) 447, 1029, 1047, 1062

Alloys *(continued)*
steel
41L47() 1029, 1047, 1062
41L50 (G41405) 1029, 1047, 1062
4118 (G41180) 442, 446, 1029, 1047, 1054, 1062
4119 (G41190) 451–452, 456, 534
4125 (G41250) 451, 534
4130 (G41300) 442, 446, 457, 467, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
4135 (G41350) 1029, 1047, 1063
4137 (G41370) 442, 446, 456–457, 535, 1029, 1047, 1063, 1086
4140 (G41400) 442, 446, 451–452, 456–457, 467, 469, 535, 1028–1029, 1046–1047, 1054, 1062–1063, 1086
4142 (G41420) 442, 446, 1029, 1047, 1063, 1086
4145 (G41450) 442, 446, 456–457, 535, 1029, 1047, 1063, 1086
4147 (G13300) 442
4147 (G41470) 446, 1029, 1047, 1063, 1086
4150 (G41500) 442, 446, 457, 467, 469, 535, 1028–1029, 1046–1047, 1054, 1062–1063, 1086
4161 (G41610) 442, 446, 1029, 1047, 1063
43L47 () 1029, 1047, 1062
4317 (G43170) 534
4320 (G43200) 442, 446, 451, 456, 467, 534, 1029, 1047, 1054, 1062, 1086
4337 (G43370) 1029, 1047, 1063
4340 (G43400) 442, 446, 451–452, 457, 467, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
4419 (G44190) 1029, 1047, 1062
4422 (G44220) 1029, 1047, 1054, 1062
4427 (G44270) 1029, 1047, 1054, 1062
4608 (G46080) 534
4615 (G46150) 442, 446, 451–452, 456, 1029, 1047, 1054, 1062, 1086
4620 (G46200) 442, 446, 451–452, 456, 467, 1029, 1047, 1054, 1062, 1086
4621 (G46210) 534, 1029, 1047, 1062
4626 (G46260) 442, 446, 1029, 1047, 1054, 1062, 1086
4640 (G46400) 451–452, 457, 474, 535, 1086
4718 (G47180) 1029, 1047, 1054, 1062
4720 (G47200) 442, 446, 1029, 1047, 1062
4812 (G48120) 534

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
4815 (G48150) 442, 446, 451–452, 456, 1029, 1047, 1062, 1086
4817 (G48170) 442, 446, 456, 1029, 1047, 1062, 1086
4820 (G48200) 442, 446, 451–452, 456, 467, 474, 534, 1029, 1047, 1054, 1062, 1086
50B44 (G50441) 442, 447, 1029, 1047, 1063
50B46 (G50461) 442, 447, 470, 1029, 1047, 1063
50B50 (G50501) 442, 447, 1029, 1047, 1063
50B60 (G50601) 442, 447, 470, 1029, 1047, 1054, 1063
50100 () 535
5045 (G50450) 535
5046 (G50460) 470, 535
5050 (G51500) 446, 451–452, 456–457, 467, 470, 474, 1029, 1047, 1063, 1086
51B60 (G51601) 442, 447, 470, 1029, 1047, 1054, 1063
51L32 () 1029, 1047, 1062
51100 (G51986) 535
5115 (G51150) 534
5117 (G51170) 442, 446, 1029, 1047, 1062
5120 (G51200) 442, 446, 456, 534, 1029, 1047, 1054, 1062, 1086
5130 (G51300) 442, 446, 457, 470, 535, 1029, 1047, 1054, 1063, 1086
5132 (G51320) 442, 446, 457, 535, 1029, 1047, 1063, 1086
51335 () 451
5135 (G51350) 442, 446, 457, 535, 1086
5140 (G51400) 442, 446, 451–452, 457, 467, 470, 1029, 1047, 1063, 1086
5145 (G51450) 535, 1029, 1047, 1063, 1086
5147 (G51470) 535, 1029, 1047, 1063
5150 (G51500) 442
5152 (G51520) 535
5155 (G51550) 442, 446
5160 (G51600) 442, 446, 467, 470, 1029, 1047, 1063
51710 () 451
6118 (G51986) 447, 1029, 1047, 1054, 1062, 1086
6118 (G61180) 442
6150 (G52986) 447, 451–452, 457, 467, 470, 474, 535, 1029, 1047, 1054, 1063, 1086
6150 (G61500) 442
6421 () 1030, 1048, 1063

Alloys *(continued)*
steel
6422 () 1030, 1048, 1063
6424 () 1030, 1048, 1063
6427 () 1030, 1048, 1063
6428 () 1030, 1048, 1063
6430 () 1030, 1048, 1063
6432 () 1030, 1048, 1063
6434 () 1030, 1048, 1063
6436 () 1030, 1048, 1063
6442 () 1030, 1048, 1063
81B45 (G81451) 442, 447, 470, 1029, 1047, 1054, 1063
8115 (G81150) 1029, 1047, 1054, 1062
86B45 (G86451) 471
86L20 () 1029, 1047, 1062
86L40 () 1029, 1047, 1062
8615 (G86150) 442, 447, 456, 534, 1029, 1047, 1062, 1086
8617 (G86170) 442, 447, 456, 1029, 1047, 1062, 1086
8620 (G86200) 442, 447, 456, 467, 1029, 1047, 1054, 1062, 1086
8622 (G86220) 442, 447, 456, 1029, 1047, 1062, 1086
8625 (G86250) 442, 447, 534, 1029, 1047, 1062, 1086
8627 (G86270) 442, 447, 535, 1029, 1047, 1054, 1062
8630 (G86300) 442, 447, 457, 467, 471, 1029, 1047, 1054, 1063, 1086
8632 (G86320) 535
8635 (G86350) 535, 1029, 1047, 1063
8637 (G86370) 442, 447, 457, 1029, 1047, 1063, 1086
8640 (G86400) 442, 447, 457, 471, 1029, 1047, 1054, 1063, 1086
8641 (G86410) 535
8642 (G86420) 442, 447, 457, 535, 1029, 1047, 1063, 1086
8645 (G86450) 442, 447, 457, 1029, 1047, 1063, 1086
8650 (G86500) 467, 471
8653 (G86530) 535
8655 (G86550) 442, 447, 457, 535, 1029, 1047, 1063
8660 (G86600) 471, 535, 1029, 1047, 1054, 1063
8720 (G87200) 442, 447, 456, 534, 1029, 1047, 1054, 1062, 1086
8735 (G87350) 535
8740 (G87400) 442, 447, 457, 467, 471, 474, 535, 1029, 1047, 1054, 1063, 1086
8745 (G87450) 535
8750 (G87500) 535
8822 (G88220) 442, 447, 1029, 1047, 1054, 1062

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
9254 (G92540) 535, 1029, 1047, 1063
9255 (G92550) 467, 471, 1029, 1047, 1063
9260 (G92600) 442, 447, 451–452, 457, 471, 1029, 1047, 1063
9262 (G92620) 535, 1029, 1047, 1063
9310 (G93100) 467, 534
9317 (G93170) 534
94B17 (G94171) 442, 447, 1029, 1047, 1062
94B30 (G94301) 442, 447, 471, 1054
9437 (G94370) 535
9440 (G94400) 535
9442 (G94420) 535
9747 (G97470) 535
9840 (G98400) 535
9845 (G98450) 535
9850 (G98500) 457, 535
elastic properties 420
cast 420
cold-rolled 420
elongation 466
hardness bhn 466
high speed
cobalt
18–4–14 546
cobalt–molybdenum–tungsten, 6–6–2–8 484
cobalt–tungsten
14–4–2–5 484
18–4–1–5 484
18–4–2–12 484
18–4–2–8 484
molybdenum, 8–2–1 484
molybdenum–tungsten
6–6–2 484
6–6–3 484
6–6–4 484
tungsten
18-4-1 546
18–4–1 484, 490, 538, 541–542
18–4–2 484
18–4–3 484
high-strength, low alloy, SAE number
942X 462–463
945A 462–463
945C 462–463
945X 462–463
950A 462–463
950B 462–463
950C 462–463
950D 462–463
950X 462–463
955X 462–463
960X 462–463
965X 462–463

Alloys *(continued)*
steel
970X 462–463
980X 462–463
impact strength 466
investment casting alloys
IC 1010 417
IC 1020 417
IC 1030 417
IC 1035 417
IC 1045 417
IC 1050 417
IC 1060 417
IC 1090 417
IC 1722AS 418
IC 2345 417
IC 4130 417
IC 4140 417
IC 4150 417
IC 4330 417
IC 4340 417
IC 4620 417
IC 52100 418
IC 6150 417
IC 8620 417
IC 8630 417
IC 8640 417
IC 8665 418
IC 8730 418
IC 8740 417
plain carbon, AISI-SAE (UNS) number
10L45 (G10454) 445
1005 444
1005 (G10050) 442
1006 444, 452, 1027, 1045, 1054, 1061
1006 (G10060) 442
1008 444, 451–452, 1027, 1045, 1061
1008 (G10080) 442
1009(G) 1027, 1045, 1061
1010 444, 451–452, 1027, 1045, 1061
1010 (G10100) 442, 532
1012 1027, 1045, 1061
1012 (G10120) 442
1015 444, 451–452, 466, 1027, 1045, 1061
1015 (G10150) 442
1016 444, 453, 1027, 1045, 1061
1016 (G10160) 442
1017 (G10170) 442, 444, 453, 1027, 1045, 1061
1018 (G10180) 442, 444, 453, 464, 1027, 1045, 1061
1019 (G10190) 442, 444, 453, 1027, 1045, 1061
1020 (G10200) 442, 444, 451–453, 466, 1027, 1045, 1061
1021 (G10210) 442, 444, 453, 1027, 1045, 1061
1022 (G10220) 442, 444, 451, 453, 466, 532, 1027, 1045, 1061

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
1023 (G10230) 442, 444, 453, 1027, 1045, 1061
1024 (G10240) 451, 453, 532, 1027, 1045, 1061
1025 (G10250) 442, 444, 453, 464, 474, 533, 1027, 1045, 1061
1026 (G10260) 442, 444, 453, 1027, 1045, 1061
1027 (G10270) 1028, 1046, 1061
1029 (G10290) 442, 444
1030 (G10300) 442, 444, 451–454, 466, 468, 532–533, 1028, 1046, 1054, 1061
1033 (G10330) 453, 533, 1028, 1046, 1054, 1061
1034 (G10340) 453
1035 (G10350) 442, 444, 451–454, 464, 533, 1028, 1046, 1061
1036 (G10360) 451, 453–454, 533, 1028, 1046, 1061
1037 (G10370) 442, 444, 1028, 1046, 1061
1038 (G10380) 442, 444, 453–454, 533, 1028, 1046, 1061
1039 (G10390) 442, 444, 453, 1028, 1046, 1061
1040 (G10400) 442, 444, 451–454, 464, 466, 468, 533, 1028, 1046, 1061
1041 (G10410) 453, 533, 1028, 1046, 1061
1042 (G10420) 442, 453, 533, 1028, 1046, 1061
1043 (G10430) 442, 444, 453, 1028, 1046, 1061
1044 (G10440) 442, 444
1045 (G10450) 442, 474, 1028, 1046, 1061
1046 (G10460) 442, 444, 453–454, 1028, 1046, 1061
1048 (G10480) 1028, 1046, 1061
1049 (G10490) 442, 1028, 1046, 1061
1050 (G10500) 442, 444, 453, 465–466, 468, 533, 1028, 1046, 1061
1052 (G10520) 453–454, 533, 1028, 1046, 1061
1053 (G10530) 442, 444
1055 (G10550) 442, 444, 452, 454, 533, 1028, 1046, 1062
1059 (G10590) 442, 444
1060 (G10600) 442, 444, 451–452, 454, 466, 468, 533, 1028, 1046, 1062
1064 (G10640) 1028, 1046, 1062
1065 (G10640) 1028, 1046, 1062
1066 (G10660) 452, 454

Alloys *(continued)*
steel
1070 (G10700) 442, 444, 451–452, 454, 1028, 1046, 1062
1074 (G10740) 533, 1028, 1046, 1062
1078 (G10780) 442, 444, 454, 533, 1028, 1046, 1062
1080 (G10800) 442, 444, 451–452, 454, 466, 468, 533, 1028, 1046, 1062
1084 (G10840) 442, 444, 1028, 1046, 1062
1085 (G10850) 451–452, 454
1086 (G10860) 442, 444, 454, 1028, 1046, 1062
1090 (G10900) 442, 444, 452, 454, 533, 1028, 1046, 1062
1095 (G10950) 442, 444, 451–452, 454, 466, 468, 474, 533, 1028, 1046, 1054, 1062
11L17 () 1009, 1027, 1045, 1061
11L18 () 1027, 1045, 1061
1108 (G11080) 1027, 1045, 1061, 1086
1109 (G11090) 455, 532, 1027, 1045, 1061, 1086
1110 (G11100) 442, 445, 1086
1111 (G11110) 451–452, 454, 532
1112 (G11120) 452, 454, 474, 532
1113 (G11130) 451–452, 454, 532
1114 (G11140) 455
1115 (G11150) 452, 455, 1027, 1045, 1061, 1086
1116 (G11160) 455, 1086
1117 (G11170) 442, 455, 1027, 1045, 1061, 1086
1118 (G11180) 442, 445, 451, 455, 464, 466, 1009, 1027, 1045, 1061, 1086
1119 (G11190) 455, 1086
1120 (G11200) 455, 532, 1027, 1045, 1061, 1086
1126 (G11260) 455, 532, 1027, 1045, 1061, 1086
1132 (G11320) 451–452, 455, 533, 1027, 1045, 1061, 1086
1137 (G11370) 442, 445, 451, 455, 465–466, 468–469, 533, 1027, 1045, 1061, 1086
1138 (G11380) 533
1139 (G11390) 442, 445, 1027, 1045, 1061, 1086
1140 (G11400) 442, 445, 455, 464, 533, 1027, 1045, 1061, 1086
1141 (G11410) 442, 445, 455, 465–466, 469, 533, 1086
1144 (G11440) 442, 445, 455, 465–466, 469, 533, 1027, 1045, 1061, 1086

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
1145 (G11450) 451–452, 455, 465, 533, 1086
1146 (G11460) 442, 445, 455, 465, 1027, 1045, 1061, 1086
1151 (G11510) 442, 445, 455, 465, 533, 1027, 1045, 1061, 1086
12L13 () 1027, 1045, 1061
12L14 (G12144) 442, 445, 1027, 1045, 1061
12L15 (G12154) 445
1211 (G12110) 442, 445, 1027, 1045, 1061
1212 (G12120) 442, 445, 474, 1027, 1045, 1061
1213 (G12130) 442, 445, 1027, 1045, 1061
1215 (G12150) 442, 445, 1027, 1045, 1061
1513 (G15130) 442, 445, 1027, 1045, 1054, 1061
1522 (G15220) 442, 445, 1054
1524 (G15240) 442, 445, 1028, 1046, 1054, 1061
1526 (G15260) 442, 445, 1028, 1046, 1061
1527 (G15270) 442, 445, 1028, 1046, 1061
1541 (G15410) 442, 445, 1028, 1046, 1061
1548 (G15480) 442, 445, 1028, 1046, 1062
1551 (G15510) 442, 445, 1028, 1046, 1062
1552 (G15520) 442, 445, 1028, 1046, 1062
1561 (G15610) 442, 445, 1028, 1046, 1062
1566 (G15660) 442, 445, 1028, 1046, 1054, 1062
tensile strength 464, 466
tool, AISI (UNS) number
A10 (T30110) 442, 496, 1031, 1049, 1066
A2 (T30102) 442, 486–487, 495–496, 1031, 1049, 1066
A3 (T30103) 442, 496, 1031, 1049, 1066
A4 (T30104) 442, 496, 1031, 1049, 1066
A5 (T30105) 442
A6 (T30106) 442, 486, 495–496, 1031, 1049, 1066
A7 (T30107) 442, 496, 1031, 1049, 1066
A8 (T30108) 442, 496, 1031, 1049, 1066
A9 (T30109) 442, 496, 1031, 1049, 1066

Alloys *(continued)*
steel
CA2 (T90102) 442
CD2 (T90402) 442
CD5 (T90405) 442
CH12 (T90812) 442
CH13 (T90813) 442
CO1 (T91501) 442
CS5 (T91905) 442
D2 (T30402) 442, 478, 485–487, 494, 496, 1031, 1049, 1066
D3 (T30403) 442, 478, 494, 496, 1031, 1049, 1066
D4 (T30404) 442, 496, 1031, 1049, 1066
D5 (T30405) 442, 478, 496, 1031, 1049, 1066
D7 (T30407) 442, 478, 487, 496, 1031, 1049, 1066
F1 (T60601) 442, 498
F2 (T60602) 442, 498–499
H10 (T20810) 442, 485, 492, 1031, 1049, 1066
H11 (T20811) 442, 486, 491–493, 1031, 1049, 1066
H12 (T20812) 442, 492–493, 1031, 1049, 1066
H13 (T20813) 442, 486, 492–493, 1031, 1049, 1066
H14 (T20814) 442, 492, 1031, 1049, 1066
H19 (T20819) 442, 485, 492–493, 1031, 1049, 1066
H20 (T20820) 485, 493
H21 (T20821) 442, 486, 492–493, 1031, 1049, 1066
H22 (T20822) 442, 485, 492, 1031, 1049, 1066
H23 (T20823) 442, 492, 1031, 1049, 1066
H24 (T20824) 442, 492–493, 1031, 1049, 1066
H25 (T20825) 442, 492, 1031, 1049, 1066
H26 (T20826) 442, 485, 492, 1031, 1049, 1066
H41 (T20841) 442, 478, 492, 1031, 1049, 1066
H42 (T20842) 442, 478, 492, 1031, 1049, 1066
H43 (T20843) 442, 478, 485, 492, 494, 1031, 1049, 1066
L2 (T61202) 442, 498, 1031, 1049, 1066
L3 (T61203) 442, 498, 1031, 1049, 1066
L6 (T61206) 442, 486, 498–499, 1031, 1049, 1066
M1 (T11301) 442, 478, 486, 488–489, 1031, 1049, 1066

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
steel
M10 (T11310) 442, 478, 488–489, 1031, 1049, 1066
M15 (T11315) 478
M2 (T11302) 442, 478, 485–489, 1031, 1049, 1066
M21 (T11321) 486
M25 (T11325) 486
M3 (...) 478, 485–487, 1031, 1049, 1066
M30 (T11330) 442, 489, 1031, 1049, 1066
M3-1 (T11313) 442, 489, 1031, 1049, 1066
M3-2 (T11323) 442, 489, 1031, 1049, 1066
M33 (T11333) 442, 489, 1031, 1049, 1066
M34 (T11334) 442, 489, 1031, 1049, 1066
M36 (T11336) 442, 478, 489, 1031, 1049, 1066
M4 (T11304) 442, 478, 485, 489, 1031, 1049, 1066
M41 (T11341) 442, 489, 1031, 1049, 1066
M42 (T11342) 442, 485, 488–490, 1031, 1049, 1066
M43 (T11343) 442, 478, 489, 1031, 1049, 1066
M44 (T11344) 442, 485, 489, 1031, 1049, 1066
M46 (T11346) 442, 489, 1031, 1049, 1066
M47 (T11347) 442, 489, 1031, 1049, 1066
M6 (T11306) 442, 489, 1031, 1049, 1066
M7 (T11307) 442, 478, 488–489, 1031, 1049, 1066
M8 (T11308) 478
O1 (T31501) 442, 486, 495–496, 1031, 1049, 1066
O2 (T31502) 442, 495–496, 1031, 1049, 1066
O6 (T31506) 442, 495–496, 1031, 1049, 1066
O7 (T31507) 442, 496, 1031, 1049, 1066
P2 (T51602) 442, 486, 498, 1031, 1049, 1066
P20 (T51620) 442, 486, 498–499, 1049, 1066
P21 (T51621) 442, 498, 1031, 1049, 1066
P3 (T51603) 442, 497–498, 1031, 1049, 1066

Alloys *(continued)*
steel
P4 (T51604) 442, 486, 497–499, 1031, 1049, 1066
P5 (T51605) 442, 498, 1031, 1049, 1066
P6 (T51606) 442, 498–499, 1031, 1049, 1066
S1 (T41901) 442, 485–486, 497–498, 1031, 1049, 1066
S2 (T41902) 442, 497–498, 1031, 1049, 1066
S4 (T41904) 442
S5 (T41905) 442, 497–498, 1031, 1049, 1066
S6 (T41906) 442, 1031, 1049, 1066
S7 (T41907) 442, 486, 498, 1031, 1049, 1066
T1 (T12001) 442, 478, 485–488, 490, 493, 1031, 1049, 1066
T15 (T12015) 442, 478, 487, 490–491, 1010, 1031, 1049, 1066
T2 (T12002) 442, 478, 490–491, 1031, 1049, 1066
T3 (T12003) 478
T4 (T12004) 442, 490
T5 (T12005) 442, 478, 485, 490–491, 1031, 1049, 1066
T6 (T12006) 442, 478, 490, 1031, 1049, 1066
T8 (T12008) 442, 490, 1031, 1049, 1066
W1 (T72301) 442, 486, 500, 1031, 1049, 1066
W2 (T72302) 442, 486, 500, 1031, 1049, 1066
W5 (T72305) 442, 500, 1031, 1049, 1066
yield strength 464, 466
tensile strength
aluminum alloys 576, 580
everdur 569
magnesium alloys 588
titanium alloys 591
titanium
alpha alloys
5 Al, 2.5 Sn 404, 591
alpha-beta alloys
10 V, 2 Fe, 3 Al 591
3 Al, 2.5 V 591
6 Al, 2 Sn, 4 Zr, 6 Mo 591
6 Al, 4 V 591
6 Al, 4 V (low O2) 591
6 Al, 6 V, 2 Sn 591
7 Al, 4 Mo 591
8 Mn 404, 591
beta alloys
111.5 Mo, 6 Zr, 4.5 Sn 591
13 V, 11 Cr, 3 Al 591
8 Mo, 8 V, 2 Fe, 3 Al 591
commercially pure 404

Copyright 2004, Industrial Press, Inc., New York, NY

Alloys *(continued)*
titanium
98.9 Ti 591
99.0 Ti 420, 591
99.1 Ti 591
99.2 Ti 591
99.5 Ti 591
elastic properties
Ti-8Al-1Mo-1V 420
99.0 Ti 420
near alpha alloys
11 Sn, 1 Mo, 2.25 Al, 5.0 Zr, 1 Mo, 0.2 Si 591
5 Al, 5 Sn, 2 Zr, 2 Mo, 0.25 Si 591
6 Al, 2 Nb, 1 Ta, 1 Mo 591
6 Al, 2 Sn, 1.5 Zr, 1 Mo, 0.35 Bi, 0.1 Si 591
6 Al, 2 Sn, 4 Zr, 2 Mo 591
8 Al, 1 Mo, 1 V 420, 591
tungsten
powder metal alloys
90W, 6Ni, 4Cu 419
90W, 7Ni, 3Cu 419
92.5W, Bal. Ni, Fe, and Mo 419
92.5W, 5.25Ni, 2.25Cu 419
93W, Bal. Ni, Fe, and Mo 419
95W, 3.5Ni, 1.5Cu 419
95W, 3.5Ni, 1.5Fe 419
97W, 2.1Ni, 0.9Fe 419
UNS numbering system
aluminum alloys 440
cast iron 440
cast steel 440
copper alloys 440
low-melting metals 440
miscellaneous nonferrous metals 440
miscellaneous steels and ferrous 440
nickel-base alloys 440
precious metals 440
rare- earth and earth-like metals, alloys 440
reactive and refractory metals, alloys 440
specified mechanical property steels 440
stainless steel alloys 440
tool steels, wrought and cast 440
welding filler metals 440
zinc-base alloys 440
yield strength
everdur 569
magnesium alloys 588
zinc
elastic properties
cast 420
wrought 420
Alumina silicate
density 415
mechanical properties 415
Aluminum
Aluminum *(continued)*
cast
specific gravity 407
chemical resistance to various materials 608
coefficient of expansion 402
coefficient of heat transmission 402
density 403
element properties 398
melting point 403
specific heat 400, 403
vapor deposition on plastics 625
wrought
specific gravity 407
Aluminum alloys
casting, AA number
A356.0 576–577
A357.0 575, 577
A444.0 575, 577
B443.0 575–577
C355.0 575–577
201.0 575–576
204.0 575–577
208.0 575–577
222.0 575–577
242.0 575–577
295.0 575–576
296.0 577
308.0 575, 577
319.0 575–577
328.0 575–576
332.0 575, 577
333.0 575, 577
336.0 575, 577
354.0 576–577
355.0 575–577
356.0 575–577
357.0 575, 577
359.0 577
443.0 575–577
512.0 575–576
513.0 575, 577
514.0 575–576
520.0 575–576
535.0 576–577
705.0 575–577
707.0 575–577
710.0 575–576
711.0 575, 577
712.0 575–576
713.0 576–577
771.0 576
850.0 575–577
851.0 575–577
852.0 576–577
coefficient of expansion 403
density 403
elastic properties 420
elongation 576, 580
endurance limit 580
investment casting alloys

Copyright 2004, Industrial Press, Inc., New York, NY

Aluminum alloys *(continued)*
investment casting alloys
A354 417
A356 417
A357 417
C355 417
D712 (40E) 417
KO-1 417
Precedent 71 417
RR-350 417
355 417
356 417
melting point 403
shearing strength 580
tensile strength 575–576, 580
thermal conductivity and conductance 403
ultimate strength 576, 580
UNS numbering system 440
wrought, AA number
Alclad 2014 580
Alclad 3003 581
Alclad 3004 581
Alclad 6061 582
Alclad 7075 583
1050 578
1060 578, 580
1100 578, 580
1145 578
1175 578
1200 578
1230 578
1235 578
1345 578
1350 578, 580, 583
2011 403, 578, 580
2014 578, 580
2017 403, 578, 580
2018 578, 580
2024 403, 420, 578, 580
2025 578, 580
2036 578, 580
2117 578, 580
2124 578
2218 578, 580
2219 578, 580
2319 578
2618 578
3003 403, 579–581
3004 579, 581
3005 579
3105 581
4032 579, 581
4043 579
4045 579
4047 579
4145 579
5005 579, 581
5050 579, 581
5052 403, 579, 581

Aluminum alloys *(continued)*
wrought, AA number
5056 579, 581
5083 579, 581
5086 403, 579, 582
5154 582
5183 579
5252 579, 582
5254 579, 582
5356 579
5454 582
5456 579, 582
5457 579, 582
5554 579
5556 579
5652 579, 582
5654 579
5657 582
6003 579
6005 579
6053 579
6061 403, 420, 579, 582
6063 582
6066 579, 583
6070 579, 583
6101 579, 583
6105 579
6151 579
6201 579
6253 579
6262 579, 583
6351 579, 583
6463 579, 583
7005 579
7008 579
7049 579, 583
7050 579, 583
7072 579
7075 403, 579, 583
7108 579
7178 579, 583
8017 579
8030 579
8176 583
8177 579
yield strength 576, 580
2011 403
2017 403
2024 403
3003 403
5052 403
5086 403
6061 403
6061-T6
elastic properties 420
7075 403
Aluminum bronze
specific gravity 407
Aluminum oxide
for polishing plastics 625

Copyright 2004, Industrial Press, Inc., New York, NY

Aluminum silicate
density 415
mechanical properties 415
Al2O3 (Alumina)
density 415
mechanical properties 415
Americium
element properties 398
Ammonia
boiling point 399
latent heat of evaporation 399
specific gravity 408
specific heat 400
Ammonium nitrate (NH_4NO_3)
in freezing mixtures 403
Amosite
thermal conductivity and conductance 401
AMS 2404C 1467
AMS 2405B 1467
AMS 2433B 1467
Aniline
boiling point 399
Antimony
coefficient of heat transmission 402
element properties 398
specific heat 400
Argon
element properties 398
Arsenic
element properties 398
Asbestos
specific gravity 407
Asbestos cement
thermal conductivity and conductance 401
Asbestos paper
thermal conductivity and conductance 401
Ash
machinability of 414
weight of 413
Aspen
machinability of 414
weight of 413
Asphalt roll
thermal conductivity and conductance 401
Asphaltum
specific gravity 407
Astatine
element properties 398
Atomic number and weight 398
Atomic symbol, elements 398
Azdel
density 416
mechanical properties 416
specific gravity 416

B

Barium
element properties 398
Basswood
machinability of 414
mechanical properties 412
weight of 413
Beech
machinability of 414
weight of 413
weight per cord 412
Beeswax
latent heat of fusion 399
Bending modulus 601
Bending strength 601
Bending stress
safe
various plastics 627
Benzine
boiling point 399
specific gravity 408
specific heat 400
Berkelium
element properties 398
Beryllium
element properties 398
Birch
machinability of 414
weight of 413
Bismuth
element properties 398
latent heat of fusion 399
Bisulfide of carbon
ignition temperature 403
Block
thermal conductivity and conductance
cinder 401
concrete 401
Board foot
weight of wood per 412
Boiling points
various substances 399
Borax 543
specific gravity 407
Boric acid 543
Boron
element properties 398
Brass
coefficient of expansion 402
red
coefficient of heat transmission 402
specific heat 400
yellow
coefficient of heat transmission 402
Brick
coefficient of expansion 402
specific gravity 407
thermal conductivity and conductance

Copyright 2004, Industrial Press, Inc., New York, NY

Brick *(continued)*
thermal conductivity and conductance
common 401
face 401
ultimate strength 420
Brickwork
specific gravity 407
specific heat 400
ultimate strength 420
Brine 499–500, 518–519, 526
quenching 519, 533
Bromine
boiling point 399
element properties 398
specific gravity 408
Bronze
coefficient of expansion 402
commercial, 90% 403
strength, effect of temperature on 421
Bulk modulus 420

C

Cadmium
element properties 398
specific heat 400
Calcium
element properties 398
Calcium chloride ($CaCl_2$)
in freezing mixtures 403
Californium
element properties 398
Carbide 624
Carbolic acid
specific gravity 408
Carbon
element properties 398
Carbon bisulfide
boiling point 399
ignition temperature 403
latent heat of evaporation 399
Carbon dioxide
specific gravity 408
Carbon disulfide
specific gravity 408
Carbon monoxide
specific gravity 408
Carbon steels
chemical composition 457
Carbonic acid
specific heat 400
Carbonic oxide
specific heat 400
Cast iron
ASTM A48 474
coefficient of expansion 404
cutting tools materials for 501
density 404
hardness 549, 552
Cast iron *(continued)*
induction hardening 530
influence of temperature on strength 421
latent heat of fusion 399
malleablizing 505
melting point 404
specific gravity 407
strength data for 474
strength, effect of temperature on 421
thermal conductivity and conductance 404
UNS numbering system 440
Cast steel
coefficient of expansion 404
density 404
melting point 404
thermal conductivity and conductance 404
Cast steels
UNS numbering system 440
Cedar
mechanical properties 412
weight of 413
weight per board foot 412
Cellulose
thermal conductivity and conductance 401
Cement
Portland
coefficient of expansion 402
ultimate strength 420
specific gravity 407
thermal conductivity and conductance 401
Ceramics
coefficient of expansion 415
compressive strength 415
density 415
dielectric strength 415
flexural strength 415
Mohs's hardness 415
tensile strength 415
thermal conductivity 415
Cerium
element properties 398
Cesium
element properties 398
Chalk
specific gravity 407
specific heat 400
Charcoal 407
ignition temperature 403
specific heat 400
Chemical composition
copper alloys 560
nickel 590
Chemical compositions
aluminum alloys 575
magnesium alloys 587
Cherry
machinability of 414

Copyright 2004, Industrial Press, Inc., New York, NY

Cherry *(continued)*
weight of 413
Chestnut
machinability of 414
weight of 413
weight per board foot 412
weight per cord 412
Chlorinated PVC (CPVC) 407, 416, 592
Chlorine
element properties 398
specific gravity 408
specific heat 400
Chloroform
boiling point 399
specific heat 400
Chromium
element properties 398
plating 625
Coal
specific gravity 407
specific heat 400
Cobalt
element properties 398
Cobalt-base alloys
investment casting alloys
cobalt 21 418
cobalt 25 418
cobalt 31 418
cobalt 36 418
F75 418
N-155 418
Coefficient of expansion 402, 415–416, 592, 604, 610–611, 622, 625
ABS 402
acetal 402
acrylic 402
aluminum 402
aluminum alloys 403
brass 402
brick 402
bronze 402
cast iron 404
cast steel 404
cement
Portland 402
ceramics 415
concrete 402
copper 402
copper alloys 403
ductile iron 404
ebonite 402
epoxy 402
glass 402
hard 402
thermometer 402
granite 402
magnesium 402
malleable iron 404
marble 402
masonry 402
Coefficient of expansion *(continued)*
nickel-base alloys 404
nylon 402
pipe 427
plaster 402
plastics 416, 622
polycarbonate 402
polyethylene 402
polypropylene 402
porcelain 402
quartz 402
sandstone 402
slate 402
stainless steel alloys 404
steel 402
thermoplastic polyester 402
titanium alloys 404
wood
pine 402
zinc 402
Coefficient of friction 592, 610
Coefficient of heat transmission
aluminum 402
antimony 402
brass
red 402
yellow 402
copper 402
german silver 402
iron 402
lead 402
mercury 402
silver 402
steel
hard 402
soft 402
tin 402
zinc 402
Coefficient of radiation
copper 402
glass 402
iron 402
cast 402
tinned and polished 402
oil 402
sand
fine 402
sawdust 402
silver
polished 402
tin 402
water 402
Coke
specific heat 400
Compression modulus 601
Concrete
coefficient of expansion 402
Portland
ultimate strength 420
poured

Copyright 2004, Industrial Press, Inc., New York, NY

Concrete *(continued)*
poured
thermal conductivity and conductance 401
specific gravity 407
Copper
coefficient of expansion 402
coefficient of heat transmission 402
density 403
element properties 398
melting point 403
polished
coefficient of radiation 402
specific heat 400, 403
strength, effect of temperature on 421
vapor deposition on plastics 625
Copper alloys
alloy name (UNS number)
aluminum brass, arsenical (C68700) 567, 1037, 1072
aluminum bronze, D (C61400) 566, 1037, 1072
architectural bronze (C38500) 564, 1037, 1072
beryllium Cu
(C17000) 562, 1037, 1072
(C17200) 403, 562, 1037, 1072
(C17300) 403, 562
(C17500) 562, 1037, 1072
(C17510) 562
C17200 403
C17300 403
brass
catridge 70% (C26000) 403
extra-high-leaded (C35600) 403
free machining (C36000) 403
high-leaded (C35300) 403
low-leaded, tube (C33000) 403
naval (C46400) 403
red, 85% (C23000) 403
yellow (C27000) 403
bronze
aluminum 11% A (C62400) 403
aluminum 9% A (C62300) 403
commercial, 90% (C22000) 403
nickel aluminum (C63000) 403
phosphor 5% A (C51000) 403
phosphor, free cutting (C54400) 403
cadmium Cu
(C16200) 562
(C16210) 562
deoxidized (C14300) 561
deoxidized (C14310) 561
cartridge brass
70% (C26000) 403, 563, 1037, 1072
70% (C26100) 563
70% (C26130) 563
70% (C26200) 563
chromium Cu
(C18200) 403, 562

Copper alloys *(continued)*
alloy name (UNS number)
(C18400) 562
(C18500) 562
commercial bronze, 90% (C22000) 403, 563, 1037, 1072
Cu nickel
10% (C70600) 568, 1037, 1072
20% (C71000) 568
30% (C71500) 568, 1037, 1072
5% (C70400) 567
Cu– nickel– phosphorus– tellurium (C19100) 562
Cu–nickel–phosphorus (C19000) 562
forging brass (C37700) 564, 1037, 1072
free machining Cu (C14500) 403
free-cutting brass (C36000) 403, 564, 1037, 1072
gilding, 95% (C21000) 563, 1037, 1072
inhibited admiralty
(C44300) 565, 1037, 1072
(C44400) 565
(C44500) 565, 1037, 1072
jewelry bronze, 87.5% (C22600) 563, 1037, 1072
leaded brass
(C33500) 564, 1037, 1072
(C34000) 564, 1037, 1072
(C34200) 564, 1037, 1072
(C35000) 564
(C35300) 403, 564, 1037, 1072
(C35600) 403, 564, 1037, 1072
tube (C33000) 403, 563
tube (C33200) 564, 1037, 1072
leaded commercial bronze
(C31400) 563, 1037, 1072
nickel-bearing (C31600) 563
leaded Cu
(C18700) 403, 562
low brass, 80% 563, 1037, 1072
manganese brass (C66700) 567
manganese bronze, A (C67500) 567, 1037, 1072
Muntz metal
free-cutting (C37000) 564, 1037, 1072
leaded (C36500) 403, 564, 1037, 1072
leaded (C36800) 564, 1037, 1072
60% (C28000) 403, 563, 1037, 1072
naval brass
(C46400) 403, 565
(C46700) 565
leaded (C48500) 565, 1037, 1072
medium-leaded (C48200) 565
nickel silver
55–18 (C77000) 568, 1037, 1072
65–10 (C74500) 568, 1037, 1072
65–12 (C75700) 568, 1037, 1072
65–15 (C75400) 568, 1037, 1072

Copyright 2004, Industrial Press, Inc., New York, NY

Copper alloys *(continued)*
alloy name (UNS number)
65–18 (C75200) 568, 1037, 1072
oxygen-free
(C10200) 560, 1037, 1072
electronic (C10100) 560–562
extra-low phosphorus (C10300) 560
low phosphorus (C10800) 560
silver-bearing
(C10400) 560
(C10500) 560
(C10700) 560
phosphor bronze
1.25% E (C50500) 565
10% D (C52400) 566, 1037, 1072
5% A (C51000) 403, 565–566, 1037, 1072
8% C (C52100) 566, 1037, 1072
phosphorus deoxidized Cu
arsenical (C14200) 561
high residual phosphorus
(C12200) 561, 1037, 1072
low residual phosphorus
(C12000) 561
(C12100) 561
red brass, 85% (C23000) 403, 563, 1037, 1072
silicon bronze
high, A (C65500) 567, 1037, 1072
low, B (C65100) 567, 1037, 1072
silicon red brass (C69400) 567
sulfur bearing
(C14700) 561
(C14710) 561
(C14720) 561
tellurium bearing
(C14500) 403, 561
(C14510) 561
(C14520) 561
tough pitch
electrolytic (C11000) 403, 560–561, 1037, 1072
fire refined, with silver
(C12500) 561
(C12700) 561
(C12800) 561
(C12900) 561
(C13000) 561
silver-bearing
(C11300) 560
(C11400) 560
(C11500) 560
(C11600) 560
yellow brass
(C26800) 563, 1037, 1072
(C27000) 403, 563
zirconium Cu (C15000) 561
beryllium copper
elastic properties 420
brass

Copper alloys *(continued)*
brass
elastic properties
cast 420
70-30 420
bronze
elastic properties 420
manganese 403
chemical compositions 560
coefficient of expansion 403
density 403
elastic properties 420
elongation 556, 560
investment casting alloys
beryllium Cu
10C (820) 417
165C (824) 417
20C (825) 417
275C (828) 417
brass
red 417
silicon 417
yellow leaded (854) 417
bronze
aluminum, C (954) 417
aluminum, D (955) 417
manganese, A 417
manganese, C 417
silicon 417
tin 417
chrome copper 417
copper (pure) 417
machinability 556, 560
manganese bronze 403
melting point 403
nickel silver
elastic properties 420
nickel-silver 403
phosphor bronze
elastic properties 420
wire
tensile strength 421
powder metal alloys
CNZ-1818 419
copper (pure) 419
CTG-1001 419
CTG-1004 419
CZP-3002 419
tensile strength 556, 560
thermal conductivity and conductance 403
UNS number (alloy name)
C10100 (oxygen-free electronic) 560–562
C10200 (oxygen-free Cu) 560, 1037, 1072
C10300 (oxygen-free, extra-low phosphorus) 560
C10400 (oxygen-free, silver-bearing) 560

Copyright 2004, Industrial Press, Inc., New York, NY

Copper alloys *(continued)*
UNS number (alloy name)
C10500 (oxygen-free, silver-bearing) 560
C10700 (oxygen-free, silver-bearing) 560
C10800 (oxygen-free, low phosphorus) 560
C11000 (electrolytic tough pitch) 403, 560–561, 1037, 1072
C11300 (silver-bearing tough pitch) 560
C11400 (silver-bearing tough pitch) 560
C11500 (silver-bearing tough pitch) 560
C11600 (silver-bearing tough pitch) 560
C12000 (phosphorus deoxidized Cu, low residual phosphorus) 561
C12100 (phosphorus deoxidized Cu, low residual phosphorus) 561
C12200 (phosphorus deoxidized Cu, high residual phosphorus) 561, 1037, 1072
C12500 (fire-refined tough pitch with silver) 561
C12700 (fire-refined tough pitch with silver) 561
C12800 (fire-refined tough pitch with silver) 561
C12900 (fire-refined tough pitch with silver) 561
C13000 (fire-refined tough pitch with silver) 561
C14200 (phosphorus deoxidized Cu, arsenical) 561
C14300 (cadmium Cu, deoxidized) 561
C14310 (cadmium Cu, deoxidized) 561
C14500 (free machining Cu) 403
C14500 (tellurium bearing) 403, 561
C14510 (tellurium bearing) 561
C14520 (tellurium bearing) 561
C14700 (sulfur bearing) 561
C14710 (sulfur bearing) 561
C14720 (sulfur bearing) 561
C15000 (zirconium Cu) 561
C15500 561
C15715 561
C15720 561
C15760 562
C16200 (cadmium Cu) 562
C16210 (cadmium Cu) 562
C16500 562
C17000 (beryllium Cu) 562, 1037, 1072
C17200 (beryllium Cu) 403, 562, 1037, 1072
C17300 (beryllium Cu) 403, 562

Copper alloys *(continued)*
UNS number (alloy name)
C17500 (beryllium Cu) 562, 1037, 1072
C17510 (beryllium Cu) 562
C18200 (chromium Cu) 403, 562
C18400 (chromium Cu) 562
C18500 (chromium Cu) 562
C18700 (leaded copper) 403, 562
C18700 (leaded Cu) 403
C19000 (Cu–nickel–phosphorus) 562
C19100 (Cu– nickel– phosphorus–tellurium alloy) 562
C19200 562
C19400 563
C19500 563
C21000 (gilding, 95%) 563, 1037, 1072
C22000 (commercial bronze, 90%) 403, 563, 1037, 1072
C22600 (jewelry bronze, 87.5%) 563, 1037, 1072
C23000 (red brass, 85%) 403, 563, 1037, 1072
C24000 (low brass, 80%) 563, 1037, 1072
C26000 (cartridge brass, 70%) 403, 563, 1037, 1072
C26100 (cartridge brass, 70%) 563
C26130 (cartridge brass, 70%) 563
C26200 (cartridge brass, 70%) 563
C26800 (yellow brass) 563, 1037, 1072
C27000 (yellow brass) 403, 563
C28000 (Muntz metal, 60%) 403, 563, 1037, 1072
C31400 (leaded commercial bronze) 563, 1037, 1072
C31600 (leaded commercial bronze, nickel-bearing) 563
C33000 (low-leaded brass tube) 403, 563
C33200 (high-leaded brass tube) 564, 1037, 1072
C33500 (low-leaded brass) 564, 1037, 1072
C34000 (medium-leaded brass) 564, 1037, 1072
C34200 (high-leaded brass) 564, 1037, 1072
C35000 (medium-leaded brass) 564
C35300 (high-leaded brass) 403, 564, 1037, 1072
C35600 (extra-high-leaded brass) 403, 564, 1037, 1072
C36000 (free machining brass) 403
C36000 (free-cutting brass) 403, 564, 1037, 1072
C36500 (leaded Muntz metal) 403, 564, 1037, 1072
C36800 (leaded Muntz metal) 564, 1037, 1072

Copyright 2004, Industrial Press, Inc., New York, NY

Copper alloys *(continued)*
UNS number (alloy name)
C37000 (free-cutting Muntz metal) 564, 1037, 1072
C37700 (forging brass) 564, 1037, 1072
C38500 (architectural bronze) 564, 1037, 1072
C40500 564
C40800 564
C41100 564
C41300 564
C41500 565
C42200 565
C42500 565
C43000 565
C43400 565
C43500 565
C44300 (inhibited admiralty) 565, 1037, 1072
C44400 (inhibited admiralty) 565
C44500 (inhibited admiralty) 565, 1037, 1072
C46400 (naval brass) 403, 565
C46700 (naval brass) 565
C48200 (naval brass, medium-leaded) 565
C48500 (leaded naval brass) 565, 1037, 1072
C50500 (phosphor bronze, 1.25% E) 565
C51000 (phosphor bronze, 5% A) 403, 565–566, 1037, 1072
C51100 565
C52100 (phosphor bronze, 8% C) 566, 1037, 1072
C52400 (phosphor bronze, 10% D) 566, 1037, 1072
C54400 403, 566, 1037, 1072
C54400 (free cutting phos. bronze) 403
C60800 566
C61000 566
C61300 566
C61400 (aluminum bronze, D) 566, 1037, 1072
C61500 566
C61800 566
C61900 566
C62300 403, 566
C62300 (aluminum bronze, 9%) 403
C62400 403, 566
C62400 (aluminum bronze, 11%) 403
C62500 566
C63000 403, 566
C63000 (Ni-Al bronze) 403
C63200 566
C63600 567
C63800 567
C64200 555, 567

Copper alloys *(continued)*
UNS number (alloy name)
C65100 (low-silicon bronze, B) 567, 1037, 1072
C65500 (high-silicon bronze, A) 567, 1037, 1072
C66700 (manganese brass) 567
C67400 567
C67500 (manganese bronze, A) 567, 1037, 1072
C68700 (aluminum brass, arsenical) 567, 1037, 1072
C68800 567
C69000 567
C69400 (silicon red brass) 567
C70400 (Cu nickel, 5%) 567
C70600 (Cu nickel, 10%) 568, 1037, 1072
C71000 (Cu nickel, 20%) 568
C71500 (Cu nickel, 30%) 568, 1037, 1072
C72200 568
C72500 568
C73500 568
C74500 (nickel silver, 65–10) 568, 1037, 1072
C75200 (nickel silver, 65–18) 568, 1037, 1072
C75400 (nickel silver, 65–15) 568, 1037, 1072
C75700 (nickel silver, 65–12) 568, 1037, 1072
C76390 568
C77000 (nickel silver, 55–18) 568, 1037, 1072
C78200 568
C80100 556
C80300 556
C80500 556
C80700 556
C80900 556
C81100 556
C81300 556
C81400 556
C81500 556
C81700 556
C81800 556
C82000 556
C82100 556
C82200 556
C82400 556
C82500 556
C82600 556
C82700 556
C82800 556
C83300 557
C83400 557
C83600 557
C83800 557
C84200 557
C84400 557

Copyright 2004, Industrial Press, Inc., New York, NY

Copper alloys *(continued)*
UNS number (alloy name)
C84500 557
C84800 557
C85200 557
C85400 557
C85500 557
C85700 557
C85800 557
C86100 557
C86200 557
C86300 557
C86400 557
C86500 557
C86700 557
C86800 557
C87200 557
C87400 557
C87500 558
C87600 558
C87800 558
C87900 558
C90200 558
C90300 558
C90500 558
C90700 558
C90900 558
C91000 558
C91100 558
C91300 558
C91600 558
C91700 558
C92200 558
C92300 558
C92500 558
C92600 558
C92700 558
C92800 558
C92900 558
C93200 558
C93400 558
C93500 558
C93700 558
C93800 558
C93900 558
C94300 558
C94400 558
C94500 558
C94700 559
C94800 559
C95200 559
C95300 559
C95400 559
C95500 559
C95600 559
C95700 559
C95800 559
C96200 559
C96300 559
C96400 559

Copper alloys *(continued)*
UNS number (alloy name)
C96600 559
C97300 559
C97400 559
C97600 559
C97800 559
C99300 559
C99400 559
C99500 559
C99700 559
C99750 559
UNS numbering system 440
yield strength 556, 560
Copper-beryllium alloys
tensile strength 570
yield strength 570
10 570
165 570
25 570
35 570
50 570
Copper-silicon alloys (Everdur)
637 569
651 569
655 569
6552 569
661 569
Copper-zinc-tin alloys
tensile strength 569
Cord
weight per wood in 412
Cordierite (2MgO·2Al2O3·5SiO2)
density 415
mechanical properties 415
Corrosion resistance
salt water
stainless steel 461
Corundum
specific heat 400
Cotton-seed oil
specific gravity 408
Cottonwood
machinability of 414
weight of 413
CPVC
density 416
mechanical properties 416
specific gravity 407, 416
CPVC (chlorinated PVC) 407, 416, 592
Curium
element properties 398
Cypress
weight of 413
weight per board foot 412
C18900 562

D

Copyright 2004, Industrial Press, Inc., New York, NY

Density
air 428
at various pressures and temperatures 429
aluminum alloys 403
cast iron 404
cast steel 404
ceramics 415
copper alloys 403
ductile iron 404
iron
cast 404
ductile 404
malleable 404
malleable iron 404
nickel-base alloys 404
plastics 416
stainless steel alloys 404
Steel
cast 404
titanium alloys 404
various metals 403
water 422–423
Dielectric constant
nylon 6/6 606
Dielectric strength
ceramics 415
plastics 416
Douglas Fir
mechanical properties 412
Douglas fir
weight of 413
Ductile iron
A536 404
coefficient of expansion 404
density 404
investment casting alloys
ferritic 418
pearlitic 418
Melting point 404
thermal conductivity and conductance 404
Dysprosium
element properties 398

E

Earth
specific gravity 407
Ebonite
coefficient of expansion 402
Einsteinium
element properties 398
Element
atomic number and weight 398
melting point 398
symbol 398
Elm
machinability of 414
Elm *(continued)*
weight of 413
weight per cord 412
Elongation
investment casting alloys 417
Emery
specific gravity 407
Epoxy
coefficient of expansion 402
Erbium
element properties 398
Ether
boiling point 399
latent heat of evaporation 399
specific heat 400
vapor
specific gravity 408
Ether, sulfuric
specific gravity 408
Ethylene
specific gravity 408
specific heat 400
Europium
element properties 398
Everdur
chemical composition 569
elongation 569
tensile strength 569
yield strength 569
Everdur (copper-silicon) alloys
637 569
651 569
655 569
6552 569
661 569

F

Felt
thermal conductivity and conductance 401
Fermium
element properties 398
Fiber glass sheet
density 416
mechanical properties 416
specific gravity 416
Fiberglass 592
Fir
mechanical properties 412
weight of 413
weight per board foot 412
Flexural modulus 601, 604, 607, 613
plastics 416
Flexural strength
ceramics 415
Fluoric acid
specific gravity 408
Fluorine
element properties 398

Copyright 2004, Industrial Press, Inc., New York, NY

Fluoroplastics
effect of heat in machining 622
Forsterite (2MgO·SiO2)
density 415
mechanical properties 415
Francium
element properties 398
Freezing mixtures
ammonium nitrate (NH_4NO_3) 403
calcium chloride ($CaCl_2$) 403
potassium hydrate (KOH) 403
sal ammoniac (NH_4Cl) 403
salt, common 403
Friction, coefficient of 592, 610
Fusel oil
specific heat 400

G

Gadolinium
element properties 398
Gallium
element properties 398
Gas
specific heat 400
Gasoline
specific gravity 408
German silver
coefficient of heat transmission 402
Germanium
element properties 398
Glass
coefficient of expansion 402
coefficient of radiation 402
elastic properties 420
hard
coefficient of expansion 402
specific gravity 407
specific heat 400
thermal conductivity and
conductance 401
thermometer
coefficient of expansion 402
Glass ceramic (machinable)
elastic properties 420
Glass ceramic, machinable
density 415
mechanical properties 415
Glass fiber
for plastics gearing 625
Glass mica
density 415
mechanical properties 415
Gold
element properties 398
specific gravity 407
specific heat 400
vapor deposition on plastics 625
Granite
Granite *(continued)*
coefficient of expansion 402
specific gravity 407
ultimate strength 420
Graphite
specific heat 400
Gravel
specific gravity 407
Gum
weight of 413
Gun cotton
ignition temperature 403
Gypsum
specific gravity 407

H

Hackberry
machinability of 414
Hafnium
element properties 398
Hardness
plastics 416
Helium
element properties 398
Hemlock
mechanical properties 412
weight of 413
weight per board foot 412
Hickory
machinability of 414
weight of 413
Holmium
element properties 398
Honeylocust
weight of 413
Hydrochloric acid
specific gravity 408
Hydrofluoric acid
specific gravity 408
Hydrogen
element properties 398
specific gravity 408
specific heat 400

I

Ice
latent heat of fusion 399
specific gravity 407
specific heat 400
Ignition temperature
bisulfide of carbon 403
charcoal 403
dry wood
oak 403
pine 403
gun cotton 403
nitro-glycerine 403

Copyright 2004, Industrial Press, Inc., New York, NY

Ignition temperature *(continued)*
phosphorus
amorphous 403
transparent 403
rifle powder 403
Illuminating gas
specific gravity 408
Indium
element properties 398
Iodine
element properties 398
Iridium
element properties 398
Iron
cast
coefficient of radiation 402
density 404
latent heat of fusion 399
melting point 404
specific gravity 407
specific heat 400, 404
strength, effect of temperature on 421
UNS numbering system 440
coefficient of heat transmission 402
coefficient of radiation 402
ductile
density 404
investment casting alloys
ferritic 418
pearlitic 418
melting point 404
specific heat 404
elastic properties
cast 420
ductile 420
grey cast 420
malleable 420
element properties 398
investment casting alloys
1.2% Si 418
malleable
density 404
melting point 404
specific heat 404
powder metal alloys
FC-0208 419
FC-0508 419
FC-0800 419
FC-2008 419
FC-2015 419
FL-4605 419
FL-4608 419
FN-0005 419
FN-0200 419
FN-0205 419
FN-0208 419
FN-0405 419
FN-0408 419
FX-2008 419
F-0000 419
Iron *(continued)*
powder metal alloys
F-0008 419
sheet, polished
coefficient of radiation 402
specific gravity 407
specific heat 400
wrought
specific heat 400
strength, effect of temperature on 421
Iron slag
specific gravity 407
Izod impact
plastics 416

K

Kerosene
specific gravity 408
specific heat 400
Krypton
element properties 398

L

Lanthanum
element properties 398
Larch
weight of 413
Latent heat
of evaporation 399
of fusion 399
Lava
density 415
mechanical properties 415
Lawrencium
element properties 398
Lead
coefficient of heat transmission 402
elastic properties 420
element properties 398
latent heat of fusion 399
specific gravity 407
specific heat 400
Lime
thermal conductivity and conductance 401
Limestone
specific gravity 407
specific heat 400
ultimate strength 420
Linseed oil
boiling point 399
specific gravity 408
Liquid crystal polymer
chemical resistance to various materials 608
Lithium
element properties 398

Copyright 2004, Industrial Press, Inc., New York, NY

Locust
weight of 413
Lubricants
molybdenum disulfide 625
silicone 625
tetrafluoroethylene (TFE) 625
TFE (tetrafluoroethylene) 625
Lutetium
element properties 398

M

Magnesia
specific heat 400
thermal conductivity and conductance 401
Magnesium
coefficient of expansion 402
elastic properties 420
element properties 398
Magnesium alloys
bearing strength 588
casting, pressure die cast
AM60A 587–588
AM60B 587–588
AS41A 587–588
AZ91A 587–588
AZ91B 587–588
AZ91D 587–588
casting, sand and permanent mold
AM100A 587–588
AZ63A 587–588
AZ81A 587–588
AZ91C 587–588
AZ91E 587–588
AZ92A 587–588
EZ33A 587–588
HK31A 587–588
HZ32A 587–588
K1A 587–588
QE22A 587–588
QH21A 587–588
WE54A 587–588
ZE41A 587–588
ZE63A 587–588
ZH62A 587–588
ZK51A 587–588
ZK61A 587–588
compressive strength 588
elastic properties 420
elongation 588
extrusion
AZ10A 587–588
AZ31B 587–588
AZ31C 587–588
AZ61A 587–588
AZ80A 587–588
HM31A 587–588
M1A 587–588
Magnesium alloys *(continued)*
extrusion
ZK40A 587–588
ZK60A 587–588
hardness 588
shear strength 588
sheet and plate
AZ31B 587–588
AZ31C 587–588
HK31A 587–588
HM21A 587–588
tensile strength 588
yield strength 588
Magnolia
machinability of 414
Malleable iron
A220 404
coefficient of expansion 404
density 404
melting point 404
thermal conductivity and conductance 404
Manganese
element properties 398
Maple
machinability of 414
weight of 413
weight per cord 412
Marble
coefficient of expansion 402
specific gravity 407
specific heat 400
Marsh gas
specific gravity 408
Masonry
brick
coefficient of expansion 402
specific heat 400
specific gravity 407
Maximum operating temperature
plastics 416
MB
wire
tensile strength
hard-drawn 421
oil tempered 421
Mechanical properties
elongation
alloy steel 466
aluminum alloys 576
copper alloys 556, 560
investment casting alloys 417
nickel 590
hardness no.
alloy steel 466
impact strength
alloy steel 466
machinability
copper alloys 556
machinablity

Copyright 2004, Industrial Press, Inc., New York, NY

Mechanical properties *(continued)*
machinablity
copper alloys 560
tensile strength
alloy steel 466
cold drawn steel 464
copper alloys 556, 560
investment casting alloys 417
nickel 590
ultimate strength
aluminum alloys 576, 580
Wood
compressive strength 412
shearing strength 412
tensile strength 412
wood
compressive strength 411
density 413
machinability 413
maximum crushing strength 411–412
maximum load in bending 411
modulus of rupture 411–412
shearing strength 412
tensile strength 412
work to max load 412
yield strength
alloy steel 466
aluminum alloys 576, 580
cold drawn steel 464
copper alloys 556, 560
copper-beryllium alloys 570
investment casting alloys 417
nickel 590
Melting point
aluminum alloys 403
cast iron 404
cast steel 404
copper alloys 403
ductile iron 404
elements 398
iron
cast 404
ductile 404
malleable 404
malleable iron 404
nickel-base alloys 404
stainless steel alloys 404
steel
cast 404
titanium alloys 404
Mendelevium
element properties 398
Merchanical properties
tensile strength
copper-beryllium alloys 570
Mercury
boiling point 399
coefficient of heat transmission 402
element properties 398
specific gravity 407
specific heat 400
Mercury vapor
specific gravity 408
MgO·SiO2 (Steatite)
density 415
mechanical properties 415
Mica
specific gravity 407
Mineral fiber
thermal conductivity and conductance 401
Mineral fiber cement
thermal conductivity and conductance 401
Mineral oil
quenching baths 517–518
specific gravity 408
tempering in 522
Modulus of elasticity 420–421, 474, 554, 593, 596–598, 600–602, 610–611, 622
Modulus of rigidity, G 474
Modulus of rupture
wood 411
Moh's hardness
ceramics 415
Molybdenum
elastic properties 420
element properties 398
Molybdenum disulfide
lubricant for plastics gearing 625
Mortar
specific gravity 407
thermal conductivity and conductance 401
Muriatic acid
specific gravity 408
Music wire
tensile strength 421

N

Naphtha
specific gravity 408
specific heat 400
Napthaline
boiling point 399
Neodymium
element properties 398
Neon
element properties 398
Neptunium
element properties 398
Nickel
element properties 398
specific gravity 407
specific heat 400
Nickel alloys
chemical composition 590
elongation 590
Inconel
elastic properties 420

Copyright 2004, Industrial Press, Inc., New York, NY

Nickel alloys *(continued)*
Monel metal
elastic properties 420
tensile strength 590
yield strength 590
Nickel steel
elastic properties 420
Nickel-base alloys
alloy name (UNS number)
hastelloy
hastelloy C-22 404
hastelloy C-276 404
inconel
inconel 718 404
Monel 404
Monel K500 (N05500) 404
Monel R405 404
Monel 400 (N05500) 404
nickel 200 (N02200) 404
nickel 201 (N02201) 404
nickel 205 (N02205) 404
coefficient of expansion 404
density 404
investment casting alloys
Alloy B 418
Alloy C 418
Alloy X 418
Inconel
In 600 418
In 625 418
Invar (Fe-Ni alloy) 418
Monel
E 418
M-35 418
RH 418
S 418
410 418
melting point 404
nickel alloys 404
specific heat 404
thermal conductivity and conductance 404
UNS numbering system 440
Niobium
element properties 398
Nitric acid
boiling point 399
specific gravity 408
Nitric oxide
specific gravity 408
Nitrogen
element properties 398
specific gravity 408
specific heat 400
Nitro-glycerine
ignition temperature 403
Nitrous oxide
specific gravity 408
Nobelium
element properties 398
Nylon 402, 407, 416, 592–593, 606, 608, 612–613, 619, 622–624, 627
coefficient of expansion 402
density 416
effect of heat in machining 622
family characteristics 592
for plastics gearing 625
glass reinforced
coefficient of expansion 402
milling 624
joint designs using 619
mechanical properties 416
nylon 6/6
chemical resistance to various materials 608
dielectric constant 606
flow characteristics 612
speeds and feeds for drilling 623
safe bending stress 627
specific gravity 407, 416
structure 593
thermoplastic characteristics 593
wall thickness for molding 613
welding
effect of moisture in 619

O

Oak
machinability of 414
weight of 413
weight per board foot 412
weight per cord 412
Oil
coefficient of radiation 402
linseed
boiling point 399
specific gravity 408
machine
specific heat 400
mineral
quenching baths 517–518
specific gravity 408
tempering in 522
olive
specific gravity 408
specific heat 400
petroleum
specific gravity 408
quenching 518–519, 526–527, 531, 535, 543
quenching baths
mineral 517
rape
specific gravity 408
saponifiable 522
tempering 522
turpentine
boiling point 399
specific gravity 408

Copyright 2004, Industrial Press, Inc., New York, NY

Oil *(continued)*
whale
specific gravity 408
Olive oil
specific gravity 408
Osmium
element properties 398
Oxygen
element properties 398
specific gravity 408
specific heat 400

P

Palladium
element properties 398
Palm oil
specific gravity 408
Paraffine
latent heat of fusion 399
PBT
chemical resistance to various materials 608
Pecan
machinability of 414
PEEK(polyetherether-ketone) 592
Percent elongation
plastics 416
Perlite
thermal conductivity and conductance 401
PET
chemical resistance to various materials 608
density 416
mechanical properties 416
specific gravity 416
PET (polyethylene-terephthalate) 416, 592, 608
Petroleum oil
specific gravity 408
Phenolic 592–593, 624
Phenolics
density 416
mechanical properties 416
specific gravity 416
Phenylene oxides
for plastics gearing 625
Phosphoric acid
specific gravity 408
Phosphorus
element properties 398
ignition temperature
amorphous 403
transparent 403
latent heat of fusion 399
specific gravity 407
specific heat 400
Pine
Pine *(continued)*
mechanical properties 412
weight of 413
weight per board foot 412
weight per cord 412
Pipe
gallons of water per foot 427
thermal expansion of 427
Plaster
coefficient of expansion 402
thermal conductivity and conductance 401
Plaster of Paris
specific gravity 407
Plastics
coefficient of expansion 416
density 416
dielectric strength 416
finishing properties 625
flexural modulus 416
hardness 416
Izod impact 416
maximum operating temperature 416
modulus of elastity 622
percent elongation 416
sawing, speeds and numbers of teeth 624
specific gravity 416
speeds and feeds for drilling 623
tensile modulus 416
thermal conductivity 622
Platinum
element properties 398
specific gravity 407
specific heat 400
Plexiglass
polishing 625
Plutonium
element properties 398
Plywood
thermal conductivity and conductance 401
Poisson's ratio 420, 596, 599
Polonium
element properties 398
Polyarylate
chemical resistance to various materials 608
Polycarbonate 402, 407, 416, 592–593, 606, 608, 613, 623, 627
chemical resistance to various materials 608
coefficient of expansion 402
density 416
for plastics gearing 625
mechanical properties 416
safe bending stress 627
specific gravity 407, 416
speeds and feeds for drilling 623
Polyester
for plastics gearing 625
safe bending stress 627

Copyright 2004, Industrial Press, Inc., New York, NY

Polyester *(continued)*
speeds and feeds for drilling 623
Polyester elastomer
chemical resistance to various materials 608
Polyetherimide
density 416
mechanical properties 416
specific gravity 416
Polyethylene
coefficient of expansion 402
density 416
mechanical properties 416
paintability 625
specific gravity 407, 416
speeds and feeds for drilling 623
thermoplastic characteristics 593
Polyethylene-terephthalate (PET) 416, 592, 608
Polyimide
milling 624
Polymer
liquid, for prototypes 624
Polymethyl methacrylate (Acrylic)
drilling
point angle 622
Polymethylpentene
density 416
mechanical properties 416
specific gravity 416
Polymid
density 416
mechanical properties 416
specific gravity 416
Polyphenylene oxide
chemical resistance to various materials 608
Polyphenylene sulfide
chemical resistance to various materials 608
density 416
effect of heat in machining 622
mechanical properties 416
specific gravity 416
Polypropylene 402, 407, 416, 592–593, 606, 608, 613, 623, 625
chemical resistance to various materials 608
coefficient of expansion 402
density 416
mechanical properties 416
paintability 625
specific gravity 407, 416
speeds and feeds for drilling 623
Polystyrene
effect of heat in machining 622
speeds and feeds for drilling 623
thermal conductivity and conductance
beaded 401
rigid 401
thermoplastic characteristics 593
Polysulfone 416, 592, 606, 608, 613
chemical resistance to various materials 608
density 416
for plastics gearing 625
mechanical properties 416
specific gravity 416
Polytetrafluoroethylene
speeds and feeds for drilling 623
Polytetrafluoro-ethylene (PTFE) 407, 416, 592
Polyurethane 407, 416, 592–593, 613, 619, 625, 627
density 416
for plastics gearing 625
mechanical properties 416
safe bending stress 627
specific gravity 407, 416
Polyvinyl chloride
drilling
point angle 622
effect of heat in machining 622
speeds and feeds for drilling 623
Polyvinyl chloride (PVC) 416, 427, 592–593, 613, 619, 622–623
Polyvinylidene-fluoride (PVDF) 416, 427, 592
Poplar
machinability of 414
weight of 413
weight per cord 412
Porcelain
coefficient of expansion 402
Potassium
element properties 398
Potassium hydrate (KOH)
in freezing mixtures 403
Praseodymium
element properties 398
Pressure
barometric 428
Promethium
element properties 398
Protactinium
element properties 398
PTFE
density 416
mechanical properties 416
specific gravity 407, 416
PTFE (polytetrafluoro-ethylene) 407, 416, 592
PVC
density 416
mechanical properties 416
specific gravity 416
PVC (polyvinyl chloride) 416, 427, 592–593, 613, 619, 622–623
PVDF
density 416
mechanical properties 416
specific gravity 416

Copyright 2004, Industrial Press, Inc., New York, NY

PVDF (polyvinylidene-fluoride) 416, 427, 592

Q

Quartz
coefficient of expansion 402
specific gravity 407
specific heat 400
Quenching
brine 499–500, 518–519, 526, 533
caustic solution 535
oil 518–519, 526–527, 531, 535, 543
salt 518, 520
tanks for 519
water 450, 453, 455–457, 471, 479, 481–484, 497–500, 508, 510, 518–519, 526–527, 531, 533, 535, 584
water-polymer 508

R

Radium
element properties 398
Radon
element properties 398
Rape oil
specific gravity 408
Redwood
mechanical properties 412
weight of 413
Rhenium
element properties 398
Rhodium
element properties 398
Rifle powder
ignition temperature 403
Roofing
thermal conductivity and conductance 401
Rouge
for polishing plastics 625
Rubber, rigid foam
thermal conductivity and conductance 401
Rubidium
element properties 398
Ruthenium
element properties 398

S

Sal ammoniac (NH_4Cl)
in freezing mixtures 403
Salt
freezing mixtures 403
quenching 518, 520
specific gravity 407
Samarium
element properties 398
Sand
fine
coefficient of radiation 402
specific gravity 407
specific heat 400
thermal conductivity and conductance 401
Sandstone
coefficient of expansion 402
specific gravity 407
ultimate strength 420
Saturated brine
boiling point 399
Sawdust
coefficient of radiation 402
Scandium
element properties 398
Selenium
element properties 398
Shear modulus 420, 474, 600
Shingle
asbestos cement
thermal conductivity and conductance 401
asphalt
thermal conductivity and conductance 401
wood
thermal conductivity and conductance 401
Siding
metal
thermal conductivity and conductance 401
Silica
for polishing plastics 625
specific heat 400
Silica aerogel
thermal conductivity and conductance 401
Silica foam
density 415
mechanical properties 415
Silicon
element properties 398
Silicon carbide
for polishing plastics 625
Silicone
lubricant for plastics gearing 625
milling 624
Silver
coefficient of heat transmission 402
element properties 398
latent heat of fusion 399
polished
coefficient of radiation 402
specific gravity 407
specific heat 400
vapor deposition on plastics 625

Copyright 2004, Industrial Press, Inc., New York, NY

Slate
coefficient of expansion 402
specific gravity 407
ultimate strength 420
Soapstone
specific gravity 407
Soda
specific heat 400
Sodium
element properties 398
Specific gravity 407, 594
Baumé's hydrometer conversion 408
gasses 408
plastics 416
various liquids 408
various substances 407
water 407
Specific heat 399
cast steel 404
copper alloys 403
iron
cast 404
ductile 404
malleable 404
of gasses 400
stainless steel alloys 404
titanium alloys 404
various metals 403
various substances 400
various woods 400
Speeds and feeds
plastics
drilling 622–623
milling 624
sawing 624
tapping and threading 623
turning and cutting off 622
Spruce
mechanical properties 412
weight of 413
weight per board foot 412
Stainless steel
alloy, AISI-SAE (UNS) number
30615 () 451–452
30705 () 452
30805 () 451
30905 () 451–452
51210 () 452
51710 () 452
UNS numbering system 440
316
chemical resistance to various materials 608
Stainless steel alloys
AISI (SAE) Number
... (51430F) 536
201 (30201) 1032, 1050, 1067
202 (30202) 1032, 1050, 1067
203EZ () 1032, 1050, 1067
Stainless steel alloys *(continued)*
AISI (SAE) Number
301 (30301) 1032, 1050, 1067
302 (30302) 474, 1032, 1050, 1067
303 (30303) 1032, 1050, 1067
303MA () 1032, 1050, 1067
303Pb () 1032, 1050, 1067
304 (30304) 1032, 1050, 1067
305 (30305) 1032, 1050, 1067
310 (30310) 1032, 1050, 1067
316 (30316) 1032, 1050, 1067
317 (30317) 1032, 1050
321 (30321) 474, 1032, 1050, 1067
347 (30347) 474, 1032, 1050, 1067
410 (51410) 536, 1032, 1050, 1067
414 (51414) 536, 1032, 1051, 1067
416 (51416) 536, 1032, 1050, 1067
420 (51420) 474, 1032, 1050, 1067
430 (51430) 474, 536, 1032, 1050, 1067
431 (51431) 536, 1032, 1051, 1067
440A (51440A) 1032, 1051, 1067
440B (51440B) 1032, 1051, 1067
440C (51440C) 1032, 1051, 1067
442 (51442) 536, 1032, 1050
446 (51446) 474, 536, 1032, 1050
455 () 1032, 1051, 1067
501 (51501) 474, 536, 1032, 1050, 1067
AISI (SAE) number
... (51409) 461, 537
... (51416F) 461
... (51420F) 461, 537
... (51430F) 461, 537
... (51434) 537
... (51436) 537
... (51440F) 461, 537
201 (30201) 448, 457, 460, 472, 536
202 (30202) 448, 458, 460, 472, 536
301 (30301) 448, 457–458, 460, 472, 535–536
302 (30302) 448, 458, 460, 472, 536
303 (30303) 448, 458, 472, 536
303(30330) 536
304 (30304) 448, 458, 460, 472, 536
305 (30305) 448, 458–460, 472, 536
310 (30310) 448, 458, 460, 472, 536
316 (30316) 448, 458–459, 461, 472, 536
317 (30317) 448, 459, 461, 472, 536
321 (30321) 448, 459, 461, 472, 536
325 (30325) 461, 536
347 (30347) 448, 459, 461, 472, 535–536
410 (51410) 449, 459, 461, 472, 537
414 (51414) 449, 459, 461, 473, 537
416 (51416) 449, 459, 472, 537
420 (51420) 449, 459–461, 473, 537
430 (51430) 448, 459–461, 473, 537
431 (51431) 449, 459, 461, 537

Copyright 2004, Industrial Press, Inc., New York, NY

Stainless steel alloys *(continued)*
AISI (SAE) number
440A (51440A) 449, 460–461, 473, 537
440B (51440B) 449, 460–461, 473, 537
440C (51440C) 449, 460–461, 473, 537
442 (51442) 448, 460–461, 537
446 (51446) 448, 460–461, 473, 537
501 (51501) 449, 460–461, 473, 537
AISI (UNS) Number
201 (S20100) 1032, 1050, 1067
202 (S20200) 1032, 1050, 1067
203EZ () 1032, 1050, 1067
301 (S30100) 1032, 1050, 1067
302 (S30200) 1032, 1050, 1067
302B (S30215) 1032, 1050, 1067
303 (S30300) 1032, 1050, 1067
303MA () 1032, 1050, 1067
303Pb () 1032, 1050, 1067
303Se (S30323) 1032, 1050, 1067
304 (S30400) 1032, 1050, 1067
304L (S30403) 1032, 1050, 1067
305 (S30500) 1032, 1050, 1067
308 (S30800) 1032, 1050, 1067
309 (S30309) 1032, 1050, 1067
309 (S30900) 1032, 1050, 1067
309S (S30908) 1032, 1050, 1067
310 (S31000) 1032, 1050, 1067
310S (S31008) 1032, 1050, 1067
314 (S31400) 1032, 1050, 1067
316 (S31600) 1032, 1050, 1067
316L (S31603) 1032, 1050
317 (S31700) 1032, 1050
321 (S32100) 1032, 1050, 1067
330 (N08330) 1032, 1050
347 (S34700) 1032, 1050, 1067
348 (S34800) 1032, 1050, 1067
403 (S40300) 1032, 1050, 1067
405 (S40500) 1032, 1050, 1067
409 (S40900) 1032, 1050, 1067
410 (S41000) 1032, 1050, 1067
414 (S41400) 1032, 1051, 1067
416 (S41600) 1032, 1050, 1067
416Se (S41623) 1032, 1050, 1067
420 (S42000) 1032, 1050, 1067
420F (S42020) 1032, 1050, 1067
420FSe () 1032, 1050, 1067
429 (S42900) 1032, 1050, 1067
430 (S43000) 1032, 1050, 1067
430F (S43020) 1032, 1050
430FSe (S43023) 1032, 1050, 1067
431 (S43100) 1032, 1051, 1067
434 (S43400) 1032, 1050, 1067
436 (S43600) 1032, 1050
440A (S44002) 1032, 1051, 1067
440B (S44003) 1032, 1051, 1067
440C (S44004) 1032, 1051, 1067
440FSe () 1032, 1050, 1067
442 (S44200) 1032, 1050
446 (S44600) 1032, 1050

Stainless steel alloys *(continued)*
AISI (UNS) Number
455 (S45500) 1032, 1051, 1067
501 (S50100) 1032, 1050, 1067
502 (S50200) 1032, 1050
AISI (UNS) number
201 (S20100) 448, 457, 472, 536
201 (S20200) 448, 458
201 (S20500) 448, 458
202 (S20200) 448, 458, 472, 536
205 (S20500) 448, 458
301 (S30100) 404, 448, 457–458, 472, 536
302 (S30200) 404, 448, 458, 472, 536
302B (S30215) 404, 448, 458, 472
303 (S30300) 404, 448, 458, 472, 536
303Se (S30323) 404, 448, 458, 472
304 (S30400) 404, 448, 458, 472, 536
304Cu (S30430) 404, 448, 458
304L (S30403) 448, 458, 472
304N (S30451) 448, 458
305 (S30500) 404, 448, 458–459, 472, 536
308 (S30800) 404, 448, 458, 472
309 (S30309) 448, 458, 460, 472, 536
309 (S30900) 404, 448, 458, 472, 536
309S (S30908) 404, 448, 458, 472
310 (S31000) 404, 448, 458, 472, 536
310S (S31008) 404, 448, 458, 472
314 (S31400) 448, 458, 472
316 (S31600) 404, 448, 458–459, 472, 536
316F (S31620) 448, 458
316L (S31603) 448, 458, 472
316N (S31651) 448, 458
317 (S31700) 404, 448, 459, 472, 536
317 (S31703) 404
317L (S31703) 448, 459
321 (S32100) 404, 448, 459, 472, 536
329 (S32900) 448, 459
330 (N08330) 448, 459
347 (S34700) 404, 448, 459, 472, 536
348 (S34800) 404, 448, 459, 472
384 (S38400) 404, 448, 459
403 (S40300) 404, 449, 459, 472
405 (S40500) 404, 448, 459, 473
409 (S40900) 448, 459
410 (S41000) 404, 449, 459, 472, 537
414 (S41400) 404, 449, 459, 473, 537
416 (S41600) 404, 449, 459, 472, 537
416Se (S41623) 404, 449, 459, 472
420 (S42000) 404, 449, 459–460, 473, 537
420F (S42020) 404, 449, 459, 473
422 (S42200) 404, 449, 459
429 (S42900) 404, 448, 459
430 (S43000) 404, 448, 459–460, 473, 537
430F (S43020) 404, 448, 459, 473
430FSe (S43023) 448, 459, 473
430Se (S43023) 404

Copyright 2004, Industrial Press, Inc., New York, NY

Stainless steel alloys *(continued)*
AISI (UNS) number
431 (S43100) 449, 459, 537
434 (S43400) 448, 459–460
436 (S43600) 404, 448, 460
440A (S44002) 404, 449, 460, 473, 537
440B (S44003) 404, 449, 460, 473, 537
440C (S44004) 404, 449, 460, 473, 537
440F (S44020) 473
442 (S44200) 448, 460, 537
446 (S44600) 404, 448, 460, 473, 537
501 (S50100) 404, 449, 460, 473, 537
502 (S50200) 404, 449, 460, 473
coefficient of expansion 404
density 404
elastic properties
18-8 420
investment casting alloys
austenitic
CF-16F 418
CF-20 418
CF-3 418
CF-3M 418
CF-8 418
CF-8C 418
CF-8M 418
CH-20 418
CK-20 418
CN-7M 418
IC 316F 418
IC 321 418
hardenable
Am-355 418
CA-15 418
CA-40 418
CD-4M Cu 418
IC 15-5 418
IC 17-4 418
IC 416 418
IC 431 418
melting point 404
powder metal alloys
SS-303N1 419
SS-304N1 419
SS-316L 419
SS-410 419
specific heat 404
thermal conductivity and conductance 404
15-5PH 1032, 1051
17-4PH 1032, 1051
17-7PH 1032, 1051
18-8
wire
tensile strength 421
Steam
specific heat 400
Steel
alloy, AISI-SAE (UNS) number
E4340 (G43406) 442, 446
Steel *(continued)*
alloy, AISI-SAE (UNS) number
E50100 (501) 457
E51100 (G51986) 442, 447
E51100 (G52986) 457
E52100 (G52986) 442, 447, 451–452, 457, 474, 535, 1029, 1047, 1063, 1086
10B46 (G10461) 445
1045 (G10450) 444, 453–454, 465, 474, 1028, 1046, 1061
10956 () 452
1108 (G11080) 1027, 1045, 1061, 1086
1320 (G13200) 451–452, 456, 533
1330 (G13300) 442, 446, 456–457, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
1335 (G13350) 442, 446, 457, 535, 1029, 1047, 1063, 1086
1340 (G13400) 442, 446, 457, 467, 469, 535, 1029, 1047, 1054, 1063, 1086
1345 (G13450) 442, 446, 1029, 1047, 1063
2317 (G23170) 451, 456, 533
2330 (G23300) 451–452, 457, 535
2340 (G23400) 451–452, 457, 535
2512 (G25120) 533
2515 (G25150) 451, 456
2517 (G25170) 533
30905 () 451–452
3115 (G31150) 451–452, 456, 533
3120 (G31200) 451–452, 456, 533
3130 (G31300) 451–452, 457, 535
3135 (G31350) 451–452, 456–457, 535
3140 (G31400) 451–452, 457, 467, 474
3141 (G31410) 451–452, 457, 535
3145 (G31450) 451, 457, 535
3150 (G31500) 451, 457, 535
3240 (G32400) 451
3310 (G33100) 451, 456, 474, 533
3316 (G33160) 533
4012 (G40120) 1029, 1047, 1054, 1062
4017 (G40170) 533
4023 (G40230) 442, 446, 451–452, 456, 474, 1029, 1047, 1054, 1062, 1086
4024 (G40240) 442, 446, 456–457, 1029, 1047, 1062, 1086
4027 (G40270) 442, 446, 451, 456, 1054, 1086
4028 (G40280) 442, 446, 456–457, 1029, 1047, 1062, 1086
4032 (G40320) 451, 456, 533, 1029, 1047, 1054, 1063, 1086
4037 (G40370) 442, 446, 457, 469, 535, 1029, 1047, 1054, 1063, 1086
4042 (G40420) 451–452, 457, 469, 535, 1029, 1047, 1063, 1086
4047 (G40470) 442, 446, 457, 535, 1029, 1047, 1063, 1086

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
alloy, AISI-SAE (UNS) number
4053 (G40530) 535
4063 (G40630) 451–452, 456–457, 535
4068 (G40680) 535
41L30 (G41403) 1029, 1047, 1062
41L40 (G41404) 447, 1029, 1047, 1062
41L47 () 1029, 1047, 1062
41L50 (G41405) 1029, 1047, 1062
4118 (G41180) 442, 446, 1029, 1047, 1054, 1062
4119 (G41190) 451–452, 456, 534
4125 (G41250) 451, 534
4130 (G41300) 442, 446, 457, 467, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
4135 (G41350) 1029, 1047, 1063
4137 (G41370) 442, 446, 456–457, 535, 1029, 1047, 1063, 1086
4140 (G41400) 442, 446, 451–452, 456–457, 467, 469, 535, 1028–1029, 1046–1047, 1054, 1062–1063, 1086
4142 (G41420) 442, 446, 1029, 1047, 1063, 1086
4145 (G41450) 442, 446, 456–457, 535, 1029, 1047, 1063, 1086
4147 (G13300) 442
4147 (G41470) 446, 1029, 1047, 1063, 1086
4150 (G41500) 442, 446, 457, 467, 469, 535, 1028–1029, 1046–1047, 1054, 1062–1063, 1086
4161 (G41610) 442, 446, 1029, 1047, 1063
43L47 () 1029, 1047, 1062
4317 (G43170) 534
4320 (G43200) 442, 446, 451, 456, 467, 534, 1029, 1047, 1054, 1062, 1086
4337 (G43370) 1029, 1047, 1063
4340 (G43400) 442, 446, 451–452, 457, 467, 469, 474, 535, 1029, 1047, 1054, 1063, 1086
4419 (G44190) 1029, 1047, 1062
4422 (G44220) 1029, 1047, 1054, 1062
4427 (G44270) 1029, 1047, 1054, 1062
4608 (G46080) 534
4615 (G46150) 442, 446, 451–452, 456, 1029, 1047, 1054, 1062, 1086
4620 (G46200) 442, 446, 451–452, 456, 467, 1029, 1047, 1054, 1062, 1086
4621 (G46210) 534, 1029, 1047, 1062
4626 (G46260) 442, 446, 1029, 1047, 1054, 1062, 1086
4640 (G46400) 451–452, 457, 474, 535, 1086
4718 (G47180) 1029, 1047, 1062
4720 (G47200) 442, 446, 1029, 1047, 1054, 1062

Steel *(continued)*
alloy, AISI-SAE (UNS) number
4812 (G48120) 534
4815 (G48150) 442, 446, 451–452, 456, 1029, 1047, 1062, 1086
4817 (G48170) 442, 446, 456, 1029, 1047, 1062, 1086
4820 (G48200) 442, 446, 451–452, 456, 467, 474, 534, 1029, 1047, 1054, 1062, 1086
50B44 (G50441) 442, 447, 1029, 1047, 1063
50B46 (G50461) 442, 447, 470, 1029, 1047, 1063
50B50 (G50501) 442, 447, 1029, 1047, 1063
50B60 (G50601) 442, 447, 470, 1029, 1047, 1054, 1063
50100 () 535
5045 (G50450) 535
5046 (G50460) 470, 535
5050 (G51500) 446, 451–452, 456–457, 467, 470, 474, 1029, 1047, 1063, 1086
51B60 (G51601) 442, 447, 470, 1029, 1047, 1054, 1063
51100 (G51986) 535
5115 (G51150) 534
5117 (G51170) 442, 446, 1029, 1047, 1062
5120 (G51200) 442, 446, 456, 534, 1029, 1047, 1054, 1062, 1086
5130 (G51300) 442, 446, 457, 470, 535, 1029, 1047, 1054, 1063, 1086
5132 (G51320) 442, 446, 457, 535, 1029, 1047, 1063, 1086
51335 () 451
5135 (G51350) 442, 446, 457, 535, 1086
5140 (G51400) 442, 446, 451–452, 457, 467, 470, 1029, 1047, 1063, 1086
5145 (G51450) 535, 1029, 1047, 1063, 1086
5147 (G51470) 535, 1029, 1047, 1063
5150 (G51500) 442
5152 (G51520) 535
5155 (G51550) 442, 446
5160 (G51600) 442, 446, 467, 470, 1029, 1047, 1063
51710 () 451
6118 (G51986) 447, 1029, 1047, 1054, 1062, 1086
6118 (G61180) 442
6150 (G52986) 447, 451–452, 457, 467, 470, 474, 535, 1029, 1047, 1054, 1063, 1086
6150 (G61500) 442
6421 () 1030, 1048, 1063
6422 () 1030, 1048, 1063
6424 () 1030, 1048, 1063

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
alloy, AISI-SAE (UNS) number
6427 () 1030, 1048, 1063
6428 () 1030, 1048, 1063
6430 () 1030, 1048, 1063
6432 () 1030, 1048, 1063
6434 () 1030, 1048, 1063
6436 () 1030, 1048, 1063
6442 () 1030, 1048, 1063
81B45 (G81451) 442, 447, 470, 1029, 1047, 1054, 1063
8115 (G81150) 1029, 1047, 1054, 1062
86B45 (G86451) 471
86L20 () 1029, 1047, 1062
86L40 () 1029, 1047, 1062
8615 (G86150) 442, 447, 456, 534, 1029, 1047, 1062, 1086
8617 (G86170) 442, 447, 456, 1029, 1047, 1062, 1086
8620 (G86200) 442, 447, 456, 467, 1029, 1047, 1054, 1062, 1086
8622 (G86220) 442, 447, 456, 1029, 1047, 1062, 1086
8625 (G86250) 442, 447, 534, 1029, 1047, 1062, 1086
8627 (G86270) 442, 447, 535, 1029, 1047, 1054, 1062
8630 (G86300) 442, 447, 457, 467, 471, 1029, 1047, 1054, 1063, 1086
8632 (G86320) 535
8635 (G86350) 535, 1029, 1047, 1063
8637 (G86370) 442, 447, 457, 1029, 1047, 1063, 1086
8640 (G86400) 442, 447, 457, 471, 1029, 1047, 1054, 1063, 1086
8641 (G86410) 457, 535
8642 (G86420) 442, 447, 457, 535, 1029, 1047, 1063, 1086
8645 (G86450) 442, 447, 457, 1029, 1047, 1063, 1086
8650 (G86500) 467, 471
8653 (G86530) 535
8655 (G86550) 442, 447, 457, 535, 1029, 1047, 1063
8660 (G86600) 471, 535, 1029, 1047, 1054, 1063
8720 (G87200) 442, 447, 456, 534, 1029, 1047, 1054, 1062, 1086
8735 (G87350) 535
8740 (G87400) 442, 447, 457, 467, 471, 474, 535, 1029, 1047, 1054, 1063, 1086
8745 (G87450) 535
8750 (G87500) 535
8822 (G88220) 442, 447, 1029, 1047, 1054, 1062
9254 (G92540) 535, 1029, 1047, 1063
9255 (G92550) 467, 471, 1029, 1047, 1063

Steel *(continued)*
alloy, AISI-SAE (UNS) number
9260 (G92600) 442, 447, 451–452, 457, 471, 1029, 1047, 1063
9262 (G92620) 535, 1029, 1047, 1063
9310 (G93100) 467, 534
9317 (G93170) 534
94B17 (G94171) 442, 447, 1029, 1047, 1062
94B30 (G94301) 442, 447, 471, 1054
9437 (G94370) 535
9440 (G94400) 535
9442 (G94420) 535
9747 (G97470) 535
9840 (G98400) 535
9845 (G98450) 535
9850 (G98500) 457, 535
carbon
chemical resistance to various materials 608
cast
density 404
melting point 404
specific heat 404
UNS numbering system 440
castings
strength, effect of temperature on 421
coefficient of expansion 402
hard
coefficient of heat transmission 402
high speed
cobalt
18–4–14 546
cobalt–molybdenum–tungsten, 6–6–2–8 484
cobalt–tungsten
14–4–2–5 484
18–4–1–5 484
18–4–2–12 484
18–4–2–8 484
molybdenum, 8–2–1 484
molybdenum–tungsten
6–6–2 484
6–6–3 484
6–6–4 484
tungsten
18–4–1 484, 490, 538, 541–542, 546
18–4–2 484
18–4–3 484
high-strength, low alloy, SAE number
942X 462–463
945A 462–463
945C 462–463
945X 462–463
950A 462–463
950B 462–463
950C 462–463
950D 462–463
950X 462–463
955X 462–463
960X 462–463

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
high-strength, low alloy, SAE number
965X 462–463
970X 462–463
980X 462–463
investment casting alloys
IC 1010 417
IC 1020 417
IC 1030 417
IC 1035 417
IC 1045 417
IC 1050 417
IC 1060 417
IC 1090 417
IC 1722AS 418
IC 2345 417
IC 4130 417
IC 4140 417
IC 4150 417
IC 4330 417
IC 4340 417
IC 4620 417
IC 52100 418
IC 6150 417
IC 8620 417
IC 8630 417
IC 8640 417
IC 8665 418
IC 8730 418
IC 8740 417
plain carbon, AISI-SAE (UNS) number
10L45 (G10454) 445
1005 (G10050) 442, 444
1006 (G) 444, 452, 1027, 1045, 1054, 1061
1006 (G10060) 442
1008 (G) 444, 451–452, 1027, 1045, 1061
1008 (G10080) 442
1009 (G) 1027, 1045, 1061
1010 (G) 444, 451–452, 1027, 1045, 1061
1010 (G10100) 442, 532
1012 (G) 1027, 1045, 1061
1012 (G10120) 442
1015 (G) 444, 451–452, 466, 1027, 1045, 1061
1015 (G10150) 442
1016 (G) 444, 453, 1027, 1045, 1061
1016 (G10160) 442
1017 (G10170) 442, 444, 453, 1027, 1045, 1061
1018 (G10180) 442, 444, 453, 464, 1027, 1045, 1061
1019 (G10190) 442, 444, 453, 1027, 1045, 1061
1020 (G10200) 442, 444, 451–453, 466, 1027, 1045, 1061

Steel *(continued)*
plain carbon, AISI-SAE (UNS) number
1021 (G10210) 442, 444, 453, 1027, 1045, 1061
1022 (G10220) 442, 444, 451, 453, 466, 532, 1027, 1045, 1061
1023 (G10230) 442, 444, 453, 1027, 1045, 1061
1024 (G10240) 451, 453, 532, 1027, 1045, 1061
1025 (G10250) 442, 444, 453, 464, 474, 533, 1027, 1045, 1061
1026 (G10260) 442, 444, 453, 1027, 1045, 1061
1027(G10270) 1028, 1046, 1061
1029 (G10290) 442, 444
1030 (G10300) 442, 444, 451–454, 466, 468, 532–533, 1028, 1046, 1054, 1061
1033 (G10330) 453, 533, 1028, 1046, 1054, 1061
1034 (G10340) 453
1035 (G10350) 442, 444, 451–454, 464, 533, 1028, 1046, 1061
1036 (G10360) 451, 453–454, 533, 1028, 1046, 1061
1037 (G10370) 442, 444, 1028, 1046, 1061
1038 (G10380) 442, 444, 453–454, 533, 1028, 1046, 1061
1039 (G10390) 442, 444, 453, 1028, 1046, 1061
1040 (G10400) 442, 444, 451–454, 464, 466, 468, 533, 1028, 1046, 1061
1041 (G10410) 453, 533, 1028, 1046, 1061
1042 (G10420) 442, 533, 1028, 1046, 1061
1043 (G10430) 442, 444, 453, 1028, 1046, 1061
1044 (G10440) 442, 444
1045 (G10450) 442, 474, 1028, 1046, 1061
1046 (G10460) 442, 444, 453–454, 1028, 1046, 1061
1048 (G10480) 1028, 1046, 1061
1049 (G10490) 442, 1028, 1046, 1061
1050 (G10500) 442, 444, 453, 465–466, 468, 533, 1028, 1046, 1061
1052 (G10520) 453–454, 533, 1028, 1046, 1061
1053 (G10530) 442, 444
1055 (G10550) 442, 444, 452, 454, 533, 1028, 1046, 1062
1059 (G10590) 442, 444
1060 (G10600) 442, 444, 451–452, 454, 466, 468, 533, 1028, 1046, 1062
1064 (G10640) 1028, 1046, 1062
1065 (G10640) 1028, 1046, 1062
1066 (G10660) 452, 454

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
plain carbon, AISI-SAE (UNS) number
1070 (G10700) 442, 444, 451–452, 454, 1028, 1046, 1062
1074 (G10740) 533, 1028, 1046, 1062
1078 (G10780) 442, 444, 454, 533, 1028, 1046, 1062
1080 (G10800) 442, 444, 451–452, 454, 466, 468, 533, 1028, 1046, 1062
1084 (G10840) 442, 444, 1028, 1046, 1062
1085 (G10850) 451–452, 454
1086 (G10860) 442, 444, 454, 1028, 1046, 1062
1090 (G10900) 442, 444, 452, 454, 533, 1028, 1046, 1062
1095 (G10950) 442, 444, 451–452, 454, 466, 468, 474, 533, 1028, 1046, 1054, 1062
11L17 () 1009, 1027, 1045, 1061
11L18 () 1027, 1045, 1061
1109 (G11090) 455, 1027, 1045, 1061, 1086
1110 (G11100) 442, 445, 1086
1111 (G11110) 451–452, 454, 532
1112 (G11120) 452, 454, 474, 532
1113 (G11130) 451–452, 454, 532
1114 (G11140) 455
1115 (G11150) 452, 455, 1027, 1045, 1061, 1086
1116 (G11160) 455, 1086
1117 (G11170) 442, 455, 1027, 1045, 1061, 1086
1118 (G11180) 442, 445, 451, 455, 464, 466, 1009, 1027, 1045, 1061, 1086
1119 (G11190) 455, 1086
1120 (G11200) 455, 532, 1027, 1045, 1061, 1086
1126 (G11260) 455, 532, 1027, 1045, 1061, 1086
1132 (G11320) 451–452, 455, 533, 1027, 1045, 1061, 1086
1137 (G11370) 442, 445, 451, 455, 465–466, 468–469, 533, 1027, 1045, 1061, 1086
1138 (G11380) 533
1139 (G11390) 442, 445, 1027, 1045, 1061, 1086
1140 (G11400) 442, 445, 455, 464, 533, 1027, 1045, 1061, 1086
1141 (G11410) 442, 445, 455, 465–466, 469, 533, 1086
1144 (G11440) 442, 445, 455, 465–466, 469, 533, 1027, 1045, 1061, 1086
1145 (G11450) 451–452, 455, 465, 533, 1086

Steel *(continued)*
plain carbon, AISI-SAE (UNS) number
1146 (G11460) 442, 445, 455, 465, 1027, 1045, 1061, 1086
1151 (G11510) 442, 445, 455, 465, 533, 1027, 1045, 1061, 1086
12L13 () 1027, 1045, 1061
12L14 (G12144) 442, 445, 1027, 1045, 1061
12L15 (G12154) 445
1211 (G12110) 442, 445, 1027, 1045, 1061
1212 (G12120) 442, 445, 474, 1027, 1045, 1061
1213 (G12130) 442, 445, 1027, 1045, 1061
1215 (G12150) 442, 445, 1027, 1045, 1061
1513 (G15130) 442, 445
1514 (G15140) 1027, 1045, 1061
1522 (G15220) 442, 445, 1054
1524 (G15240) 442, 445, 1028, 1046, 1054, 1061
1526 (G15260) 442, 445, 1028, 1046, 1061
1527 (G15270) 442, 445, 1028, 1046, 1061
1541 (G15410) 442, 445, 1028, 1046, 1061
1548 (G15480) 442, 445, 1028, 1046, 1062
1551 (G15510) 442, 445, 1028, 1046, 1062
1552 (G15520) 442, 445, 1028, 1046, 1062
1561 (G15610) 442, 445, 1028, 1046, 1062
1566 (G15660) 442, 445, 1028, 1046, 1054, 1062
soft
coefficient of heat transmission 402
specific gravity 407
specific heat
high carbon 400
mild 400
structural
strength, effect of temperature on 421
tool, AISI (UNS) number
A10 (T30110) 442, 496, 1031, 1049, 1066
A2 (T30102) 442, 486–487, 495–496, 1031, 1049, 1066
A3 (T30103) 442, 496, 1031, 1049, 1066
A4 (T30104) 442, 496, 1031, 1049, 1066
A5 (T30105) 442
A6 (T30106) 442, 486, 495–496, 1031, 1049, 1066
A7 (T30107) 442, 474, 496, 1031, 1049, 1066

Copyright 2004, Industrial Press, Inc., New York, NY

Steel (continued)
tool, AISI (UNS) number
A8 (T30108) 442, 496, 1031, 1049, 1066
A9 (T30109) 442, 496, 1031, 1049, 1066
CA2 (T90102) 442
CD2 (T90402) 442
CD5 (T90405) 442
CH12 (T90812) 442
CH13 (T90813) 442
CO1 (T91501) 442
CS5 (T91905) 442
D2 (T30402) 442, 478, 485–487, 494, 496, 1031, 1049, 1066
D3 (T30403) 442, 478, 494, 496, 1031, 1049, 1066
D4 (T30404) 442, 496, 1031, 1049, 1066
D5 (T30405) 442, 478, 496, 1031, 1049, 1066
D7 (T30407) 442, 478, 487, 496, 1031, 1049, 1066
F1 (T60601) 442, 498
F2 (T60602) 442, 498–499
H10 (T20810) 442, 485, 492, 1031, 1049, 1066
H11 (T20811) 442, 486, 491–493, 1031, 1049, 1066
H12 (T20812) 442, 492–493, 1031, 1049, 1066
H13 (T20813) 442, 486, 492–493, 1031, 1049, 1066
H14 (T20814) 442, 492, 1031, 1049, 1066
H19 (T20819) 442, 485, 492–493, 1031, 1049, 1066
H20 (T20820) 485, 493
H21 (T20821) 442, 486, 492–493, 1031, 1049, 1066
H22 (T20822) 442, 485, 492, 1031, 1049, 1066
H23 (T20823) 442, 492, 1031, 1049, 1066
H24 (T20824) 442, 492–493, 1031, 1049, 1066
H25 (T20825) 442, 492, 1031, 1049, 1066
H26 (T20826) 442, 485, 492, 1031, 1049, 1066
H41 (T20841) 442, 478, 492, 1031, 1049, 1066
H42 (T20842) 442, 478, 492, 1031, 1049, 1066
H43 (T20843) 442, 478, 485, 492, 494, 1031, 1049, 1066
L2 (T61202) 442, 498, 1031, 1049, 1066

Steel (continued)
tool, AISI (UNS) number
L3 (T61203) 442, 498, 1031, 1049, 1066
L6 (T61206) 442, 486, 498–499, 1031, 1049, 1066
M1 (T11301) 442, 478, 486, 488–489, 1031, 1049, 1066
M10 (T11310) 442, 478, 488–489, 1031, 1049, 1066
M15 (T11315) 478
M2 (T11302) 442, 478, 485–489, 1031, 1049, 1066
M21 (T11321) 486
M25 (T11325) 486
M3 (...) 478, 485–487, 1031, 1049, 1066
M30 (T11330) 442, 489, 1031, 1049, 1066
M3-1 (T11313) 442, 489, 1031, 1049, 1066
M3-2 (T11323) 442, 489, 1031, 1049, 1066
M33 (T11333) 442, 489, 1031, 1049, 1066
M34 (T11334) 442, 489, 1031, 1049, 1066
M36 (T11336) 442, 478, 489, 1031, 1049, 1066
M4 (T11304) 442, 478, 485, 489, 1031, 1049, 1066
M41 (T11341) 442, 489, 1031, 1049, 1066
M42 (T11342) 442, 485, 488–490, 1031, 1049, 1066
M43 (T11343) 442, 478, 489, 1031, 1049, 1066
M44 (T11344) 442, 485, 489, 1031, 1049, 1066
M46 (T11346) 442, 489, 1031, 1049, 1066
M47 (T11347) 442, 489, 1031, 1049, 1066
M6 (T11306) 442, 489, 1031, 1049, 1066
M7 (T11307) 442, 478, 488–489, 1031, 1049, 1066
M8 (T11308) 478
O1 (T31501) 442, 486, 495–496, 1031, 1049, 1066
O2 (T31502) 442, 495–496, 1031, 1049, 1066
O6 (T31506) 442, 495–496, 1031, 1049, 1066
O7 (T31507) 442, 496, 1031, 1049, 1066
P2 (T51602) 442, 486, 498, 1031, 1049, 1066
P20 (T51620) 442, 486, 498–499, 1049, 1066

Copyright 2004, Industrial Press, Inc., New York, NY

Steel *(continued)*
tool, AISI (UNS) number
P21 (T51621) 442, 498, 1031, 1049, 1066
P3 (T51603) 442, 497–498, 1031, 1049, 1066
P4 (T51604) 442, 486, 497–499, 1031, 1049, 1066
P5 (T51605) 442, 498, 1031, 1049, 1066
P6 (T51606) 442, 498–499, 1031, 1049, 1066
S1 (T41901) 442, 485–486, 497–498, 1031, 1049, 1066
S2 (T41902) 442, 497–498, 1031, 1049, 1066
S4 (T41904) 442
S5 (T41905) 442, 497–498, 1031, 1049, 1066
S6 (T41906) 442, 1031, 1049, 1066
S7 (T41907) 442, 486, 498, 1031, 1049, 1066
T1 (T12001) 442, 478, 485–488, 490, 493, 1031, 1049, 1066
T15 (T12015) 442, 478, 487, 490–491, 1010, 1031, 1049, 1066
T2 (T12002) 442, 478, 490–491, 1031, 1049, 1066
T3 (T12003) 478
T4 (T12004) 442, 490
T5 (T12005) 442, 478, 485, 490–491, 1031, 1049, 1066
T6 (T12006) 442, 478, 490, 1031, 1049, 1066
T8 (T12008) 442, 490, 1031, 1049, 1066
W1 (T72301) 442, 486, 500, 1031, 1049, 1066
W2 (T72302) 442, 486, 500, 1031, 1049, 1066
W5 (T72305) 442, 500, 1031, 1049, 1066
Steel alloys
elastic properties 420
cast 420
cold-rolled 420
Steel castings
strength, effect of temperature on 421
Stone
specific heat 400
Strontium
element properties 398
Structural steel
strength, effect of temperature on 421
Stucco
thermal conductivity and conductance 401
Sulfur
boiling point 399
element properties 398
Sulfur *(continued)*
latent heat of fusion 399
specific gravity 407
specific heat 400
Sulfur dioxide
latent heat of evaporation 399
specific gravity 408
Sulfuric acid
boiling point 399
specific gravity 408
specific heat 400
Sweetgum
machinability of 414
Sycamore
machinability of 414
weight of 413

T

Tamarack
weight of 413
Tanoak
machinability of 414
Tantalum
element properties 398
Tar
specific gravity 407–408
Technetium
element properties 398
Tellurium
element properties 398
Temperature
absolute 428
Rankine 428
Tempering oil 522
specific gravity 522
Tensile modulus 420–421, 474, 554, 593, 596–598, 600–602, 610–611, 622
plastics 416
Tensile strength
ceramics 415
copper-zinc-tin alloys 569
investment casting alloys 417
wire 421
Terbium
element properties 398
Tetrafluoroethylene (TFE)
lubricant for plastics gearing 625
Textile
thermal conductivity and conductance 401
TFE (tetrafluoroethylene)
lubricant for plastics gearing 625
Thallium
element properties 398
Thermal conductivity
ceramics 415
plastics 622
various metals 403

Copyright 2004, Industrial Press, Inc., New York, NY

Thermal conductivity and conductance
aluminum alloys 403
amosite 401
asbestos cement 401
asbestos paper 401
asphalt roll 401
block
cinder 401
concrete 401
brick
common 401
face 401
cast iron 404
cast steel 404
cellulose 401
cement 401
concrete (poured) 401
copper alloys 403
ductile iron 404
felt 401
glass 401
lime or sand 401
magnesia 401
malleable iron 404
mineral fiber 401
mineral fiber cement 401
mortar 401
nickel-base alloys 404
perlite 401
plaster 401
plywood 401
polystyrene
beaded 401
rigid 401
roofing 401
rubber, rigid foam 401
shingle
asbestos cement 401
asphalt 401
wood 401
siding
metal 401
wood, medium density 401
silica aerogel 401
stainless steel alloys 404
stucco 401
textile 401
tile 401
titanium alloys 404
vermiculite 401
wall tile 401
wood felt 401
wood subfloor 401
Thermal expansion, coefficient of 402, 415–416, 592, 604, 610–611, 622, 625
Thermoplastic polyester
coefficient of expansion 402
Thermoplastic Polyester (PBT)
chemical resistance to various materials 608
Thermoplastic polyester (PET)
chemical resistance to various materials 608
Thorium
element properties 398
Thulium
element properties 398
Tile
specific gravity 407
thermal conductivity and conductance 401
Tin
coefficient of heat transmission 402
element properties 398
latent heat of fusion 399
polished
coefficient of radiation 402
specific heat 400
TiO2 (Titania)
density 415
mechanical properties 415
Titanium
element properties 398
Titanium alloys
alpha alloys
5 Al, 2.5 Sn 404, 591
alpha-beta alloys
10 V, 2 Fe, 3 Al 591
3 Al, 2.5 V 591
6 Al, 2 Sn, 2 Zr, 2 Mo, 2 Cr, 0.25 Si 591
6 Al, 2 Sn, 4 Zr, 6 Mo 591
6 Al, 4 V 591
6 Al, 4 V (low O2) 591
6 Al, 6 V, 2 Sn 591
7 Al, 4 Mo 591
8 Mn 404, 591
beta alloys
11.5 Mo, 6 Zr, 4.5 Sn 591
13 V, 11 Cr, 3 Al 591
3 Al, 8 V, 6 Cr, 4 Mo,4 Zr 591
8 Mo, 8 V, 2 Fe, 3 Al 591
chemical composition 591
coefficient of expansion 404
commercially pure 404
98.9 Ti 591
99.0 Ti 420, 591
99.1 Ti 591
99.2 Ti 591
99.5 Ti 591
density 404
elastic properties
Ti-8Al-1Mo-1V 420
99.0 Ti 420
elongation 591
melting point 404
near alpha alloys
11 Sn, 1 Mo, 2.25 Al, 5.0 Zr, 1 Mo, 0.2 Si 591
5 Al, 5 Sn, 2 Zr, 2 Mo, 0.25 Si 591
6 Al, 2 Nb, 1 Ta, 1 Mo 591

Copyright 2004, Industrial Press, Inc., New York, NY

Titanium alloys *(continued)*
near alpha alloys
6 Al, 2 Sn, 1.5 Zr, 1 Mo, 0.35 Bi, 0.1 Si 591
6 Al, 2 Sn, 4 Zr, 2 Mo 591
8 Al, 1 Mo, 1 V 420, 591
specific heat 404
thermal conductivity and conductance 404
titanium alloys 404
Titanium alloys tensile strength 591
Tool steels
C2
for milling plastics 624
for milling plastics 624
molybdenum high-speed steel
for tapping and threading plastics 623
M1
for tapping and threading plastics 623
M10
for tapping and threading plastics 623
M2
for milling plastics 624
M3
for milling plastics 624
M33
for drilling plastics 622
M41
for drilling plastics 622
M47
for drilling plastics 622
M7
for milling plastics 624
for tapping and threading plastics 623
T15
for drilling plastics 622
for milling plastics 624
UNS numbering system
wrought and cast 440
water hardening 479
Trap rock
specific gravity 407
ultimate strength 420
Tripoli
for polishing plastics 625
Tungsten
element properties 398
Tungsten alloys
powder metal alloys
90W, 6Ni, 4Cu 419
90W, 7Ni, 3Cu 419
92.5W, Bal. Ni, Fe, and Mo 419
92.5W, 5.25Ni, 2.25Cu 419
93W, Bal. Ni, Fe, and Mo 419
95W, 3.5Ni, 1.5Cu 419
95W, 3.5Ni, 1.5Fe 419
97W, 2.1Ni, 0.9Fe 419
Tupelo
machinability of 414
Turpentine
Turpentine *(continued)*
latent heat of evaporation 399
oil of
boiling point 399
specific gravity 408
specific heat 400

U

Ultimate strength
brick 420
brickwork 420
cement
Portland 420
concrete
Portland 420
granite 420
limestone 420
sandstone 420
slate 420
trap rock 420
vulcanized fiber 420
Unnilhexium
element properties 398
Unnilnonium
element properties 398
Unniloctium
element properties 398
Unnilpentium
element properties 398
Unnilquadium
element properties 398
Unnilseptium
element properties 398
Uranium
element properties 398

V

Vanadium
element properties 398
Vermiculite
thermal conductivity and conductance 401
Vinegar
specific gravity 408
Vinyl
thermoplastic characteristics 593
Vulcanized fiber
ultimate strength 420

W

Wall tile
thermal conductivity and conductance 401
Walnut
machinability of 414

Copyright 2004, Industrial Press, Inc., New York, NY

Walnut *(continued)*
weight of 413
Water
boiling point 399, 422–423
coefficient of radiation 402
compressibility 422–423
density 422–423
latent heat of evaporation 399
pressure-head relationship 422–423
quenching 450, 453, 455–457, 471, 479, 481–484, 497–500, 508, 510, 518–519, 526–527, 531, 533, 535, 584
salt 461
specific gravity 407–408
specific heat 400
vapor
specific gravity 408
volume at various temperatures 422
Water, sea
boiling point 399
specific gravity 408
Whale oil
specific gravity 408
White metal
specific gravity 407
Willow
machinability of 414
Wire
tensile strength
chrome silicon 421
Cr-V alloy 421
MB
hard-drawn 421
oil tempered 421
music wire 421
phosphor bronze 421
stainless steel
18-8 421
Wood
compression perpendicular to grain 411
fir
specific heat 400
machinability of 414
mechanical properties 412
medium density
thermal conductivity and conductance 401
oak
ignition temperature 403
specific heat 400
pine
coefficient of expansion 402
ignition temperature 403
specific heat 400
shear strength parallel to grain 412
subfloor
thermal conductivity and conductance 401
tensile strength 412
Wood *(continued)*
thermal conductivity and conductance
plywood 401
weight of 412–413
weight per board foot 412
weight per cord 412
Wood felt
thermal conductivity and conductance 401
Wrought iron
strength, effect of temperature on 421

X

Xenon
element properties 398

Y

Yield 590
Yield strength
investment casting alloys 417
Young's modulus 420–421, 474, 554, 593, 596–598, 600–602, 610–611, 622
Ytterbium
element properties 398
Yttrium
element properties 398

Z

Zinc
coefficient of expansion 402
coefficient of heat transmission 402
element properties 398
latent heat of fusion 399
specific gravity 407
specific heat 400
Zinc alloys
elastic properties
cast 420
wrought 420
Zinc-base alloys
UNS numbering system 440
Zirconium
element properties 398
Zirconium phosphate
density 415
mechanical properties 415
Z-nickel
elastic properties 420
ZrO2
density 415
mechanical properties 415
ZrO2·SiO2 (Zircon)
density 415
mechanical properties 415

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

ADDITIONAL ONLY ON THE CD

MATHEMATICS

2746 Trig and Involute Functions
2746 0 Degrees
2751 5 Degrees
2756 10 Degrees
2761 15 Degrees
2766 20 Degrees
2771 25 Degrees
2776 30 Degrees
2781 35 Degrees
2786 40 Degrees
2790 45 Degrees
2791 Constants for Sine-Bars
2791 2.5-inch Sine-Bar
2798 3-inch Sine-Bar
2805 5-inch Sine-Bar
2812 10-inch Sine-Bar
2819 75-mm Sine-Bar
2826 125-mm Sine-Bar
2833 Squares of Numbers
2833 Numbers from 1 to 999
2835 Mixed Numbers from 1/64 to 12
2837 Squares and Cubes of Fractions
2843 Fractions of Pi (π)
2844 Powers, Roots, and Reciprocals
2844 From 1 to 200
2848 From 201 to 400
2852 From 401 to 600
2856 From 601 to 800
2860 From 801 to 1000
2864 From 1001 to 1500
2874 From 1501 to 2000
2884 Multiplication Tables for Fractions
2884 Fractions and Whole Numbers
2885 Common Fractions
2887 Area and Volume of Spheres
2890 Circumference and Area of Circles
2902 Decimal Equivalents, Squares, Cubes, Roots, & Logarithms of Fractions

CEMENT, CONCRETE, LUTES, ADHESIVES, AND SEALANTS

2903 Cement
2903 Portland Cement
2903 Natural Cement
2904 Pozzuolanic or Slag Cement
2904 Concrete
2904 Concrete

CEMENT, CONCRETE, LUTES, ADHESIVES, AND SEALANTS

(Continued)

2904 Concrete Mixtures
2904 Sand, Gravel, and Stone for Concrete
2904 Amount of Water for Mixing Concrete
2904 Reinforced Concrete
2905 Strength of Concrete
2905 Durability of Concrete in Sea Water
2905 Waterproofing Concrete
2905 Resistance to Acids and Oils
2905 Lutes and Cements
2906 Water-proof Compositions
2906 Oil-proof Cements
2906 Acid-proof Cements
2906 Gasket Compositions
2907 Machinists Cements
2907 Leather Cements
2907 Iron and Stone Cements
2907 Cement Proof to Hydrocarbon Gases
2907 Cements Proof to Chlorine
2907 Elastic Cements
2908 General Purposes
2908 Marine Glue
2908 Acid-proof Lining
2908 Cements for Pipe Joints
2908 Adhesives
2908 Adhesives Bonding
2912 Sealants
2912 Sealants

SURFACE TREATMENTS FOR METALS

2914 Coloring Metals
2914 General Requirements in the Coloring of Metal Surfaces
2914 Cleaning Metals for Coloring
2914 Pickling Solutions or Dips for Coloring
2914 Coloring Brass
2914 To Produce a Rich Gold Color
2915 White Colors or Coatings
2915 Silvering
2915 To Give Brass a Green Tint
2915 Blackening Brass
2915 Preservation of Color

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

ADDITIONAL ONLY ON THE CD

SURFACE TREATMENTS FOR METALS

(Continued)

2915 Niter Process of Bluing Steel
2916 Bluing Steel by Heat-treatment
2916 Blue-black Finish
2916 Black Finish
2916 Gun Metal Finish
2917 Browning Iron and Steel
2917 To Produce a Bronze Color
2917 To Produce a Gray Color
2917 Mottled Coloring
2917 Coppering Solution
2917 White Coatings for Laying Out Lines
2917 To Produce Gray Colors
2918 Blue and Violet Shades
2918 To Give Brass a Green Tint
2918 Etching And Etching Fluids
2918 Etching Fluids for Different Metals
2919 Etching Brass Nameplates
2919 Producing a Black Background
2919 Etching Ornamental Designs in Metal

MANUFACTURING

2921 Welding with Thermit
2921 Thermit Process
2921 Preparation of Part to be Welded
2921 Mold for Thermit Welding
2922 Thermit Required for Welding
2922 Thermit Additions
2922 Pre-heating — Making a Weld
2923 Filling Shrinkage Holes and Surface Flaws
2923 Composition of Thermit Steel
2923 High- and Low-pressure Torches

SYMBOLS FOR DRAFTING

2924 Symbols For Drafting
2924 Air Conditioning Symbols
2925 Heating and Ventilation Symbols
2926 Valve Symbols
2927 Piping Symbols
2928 Pipe Fittings Symbols

FORGE SHOP EQUIPMENT

2930 Hammer and Anvil
2930 Blacksmiths' Anvils
2930 Setting the Anvil
2930 Steam Hammer Rating
2930 Capacity of Steam Hammers
2930 Power for Operating Steam Hammers
2931 Board Drop-hammers
2932 Forging Presses
2933 Air Pressures and Pipe Sizes for Forges
2933 The Cold Swaging Process
2934 Forging Machines
2934 Dies for Bolt and Rivet Forging Machines
2934 Dies and Tools Used in Hot-pressed Center-feed Nut Machines
2934 Bulldozer Dies
2934 Helve Hammers
2934 Vertical Power Hammers
2934 Efficiency of Forging Hammers
2936 Machinery and Hammer Foundations
2936 Concrete Foundations
2937 Drop Hammer Foundations
2937 Foundation for Steam Hammer
2937 Machine and Forge Shop Floor Materials
2938 Concrete and Wooden Floors
2938 To Prevent Dust on Concrete Floors
2938 Floors for Forge Shops
2939 Drop-Forging Dies
2939 Steel for Drop-forging Dies
2939 Allowance for Shrinkage
2939 Draft Allowance
2939 Locating Impression in the Die
2939 Obtaining Weight of Forging from Lead Proof
2940 Amount of Flash for Drop-forging Dies
2940 The Break-down of Drop-forging Dies
2940 Hardening Drop-forging Dies
2940 Heating the Die
2940 Cooling the Heated Die
2941 Tempering Dies

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

ADDITIONAL ONLY ON THE CD

FORGE SHOP EQUIPMENT

(Continued)

2941 Dies for Bronze and Copper Forgings
2941 Trimming Dies for Drop-forgings
2941 Standard Tolerances for Forgings
2944 Welding Methods
2944 Classes of Welds
2944 Welding Heat
2944 Fire for Welding
2944 Fluxes for Welding
2945 Fuels for Forge
2945 Machine Welding
2946 Hydraulic Press
2946 Rules and Formulas for Hydraulic Press Calculations

SILENT OR INVERTED TOOTH CHAIN

2948 Characteristics of Silent Chain Drives
2948 Standard Silent Chain Designation
2949 Silent Chain Links
2949 Silent Chain Sprocket Diameters
2949 Silent Chain Sprocket Profiles and Chain Widths
2959 Sprocket Hub Dimensions
2963 Sprocket Design and Tooth Form
2963 Cutting Silent Chain Sprocket Teeth
2965 Design of Silent Chain Drives
2965 Pitch of Silent Chain
2965 Maximum Ratios for Silent Chain Drives
2966 Center Distance for Silent Chain Drives
2966 Silent Tooth Chain Horsepower Capacity
2966 Installation of Silent Chain Drives
2967 Double-Flexure Silent Chain
2967 Horsepower Ratings Per Inch of Chain Width for Silent Chain Drives — 1982

GEARS AND GEARING

2971 Geometry Factors For Gear Teeth
2971 Contact and Bending Stresses
2971 Geometry Factors for Pitting Resistance and Bending Strength

GEARS AND GEARING

(Continued)

2971 Exceptions to the Information Sheet Data and Procedures
2971 Basic Gear Geometry of Spur and Helical Gears
2973 Contact Ratios
2974 Minimum Lengths of Lines of Contact
2974 Load Sharing Ratio, mN
2974 Calculating the Pitting Resistance Geometry Factor, I
2975 Bending Strength Geometry Factor, J
2976 Pressure Angle at Load Application Point
2977 Generating-Rack Shift Coefficient
2978 Tables of Geometry Factors, I and J
2978 Using the Tables
2987 Power–Transmitting Capacity of Spur Gears
2987 Modes of Failure
2987 Strength Calculations for Spur and Helical Gears
2988 Rating Formulas
2988 Exceptions
2988 Additional Considerations
2989 Criteria for Gear Tooth Capacity
2989 Relationship of Pitting Resistance and Bending Strength Ratings
2990 Fundamental Rating Formulas
2990 Pitting Resistance
2991 Symbols Used in Gear Rating Equations
2993 Pitting Resistance Power Rating
2993 Contact Load Factor, K
2994 Bending Strength
2994 Allowable Bending Stress Number
2994 Bending Strength Power Rating
2995 Values for Factors Applied in Fundamental Equations
2995 Rim Thickness Factor KB
2995 Geometry Factors I and J
2995 Transmitted Tangential Load, Wt
2996 Dynamic Factors, Cv and Kd
2998 Application Factors, Ca and Ka
2998 Service Factors, CSF and KSF
2999 Elastic Coefficient,Cp
2999 Surface Condition Factor, Cf

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

ADDITIONAL ONLY ON THE CD

GEARS AND GEARING

(Continued)
2999 Size Factors, Cs and Ks
2999 Load Distribution Factors, Cm and Km
3001 Allowable Stress Numbers, Sac and Sat
3002 Case Depth of Surface–Hardened Gears
3003 Momentary Overloads
3003 Yield Strength
3003 Hardness Ratio Factor CH
3004 Life Factors CL and KL
3005 Localized Yielding
3005 Reliability Factors, CR and KR
3005 Temperature Factors CT and KT
3007 Worm Gearing
3007 Standard Design for Fine-pitch
3008 Formulas for Proportions of Wormgears
3009 Proportions of Fine-pitch Worms and Wormgears
3017 Materials for Worm Gearing
3017 Single-thread Worms
3017 Multi-thread Worms
3019 Ratio for Obtaining “Hunting Tooth” Action
3020 Pitch Diameter of Worm
3020 Addendum and Dedendum
3021 Outside Diameter of Wormgear
3021 Pressure Angles
3021 Designing Worm Gearing Relative to Center Distance and Ratio
3022 Efficiency of Worm Gearing
3026 Self-locking or Irreversible Worm Gearing
3027 Worm Gearing Operating Temperatures
3027 Thermal Rating
3027 Water and Forced-Air Cooling
3027 Double-enveloping Worm Gearing
3029 Worm Thread Cutting
3029 Wormgear Hobs
3030 Helical Fluted Hobs
3032 Gear Shaving

MISCELLANEOUS TOPICS

3033 Mathematics
3033 Catenary Curve
3033 Mechanics
3033 Running Balance
3033 Properties of Materials
3033 Copper-Clad Steel
3033 Truflex
3033 Firebrick Properties
3033 Inconel
3034 Inconel “X”
3034 Lodestone
3034 Metallography
3035 Micarta
3035 Monel
3036 “R” Monel
3036 “K” Monel
3036 “KR” Monel
3036 “S” Monel
3036 “H” Monel
3036 Nichrome
3037 Nickel Alloy for Resisting Acids
3037 Duronze
3038 Aluminum Alloys, Wrought, Sheet
3038 Plow-steel Wire Rope
3038 Type Metal
3038 Vanadium Steel
3038 Wood’s Metal
3039 Lumber
3039 Lumber, Manufactured
3039 Lumber Water Content
3040 Dimensioning, Gaging, amd Measuring
3040 Transfer Calipers
3040 Wheatstone Bridge
3041 Tools and Tooling
3041 Rotary Files and Burs
3041 Tooth-rest for Cutter Grinding
3042 Machining Operations
3042 Feed Rate on Machine Tools
3042 Billet
3042 Milling Machines, Lincoln Type
3042 Saddle
3043 Cold Extrusion
3043 Transfer Machines

Copyright 2004, Industrial Press, Inc., New York, NY

TABLE OF CONTENTS

ADDITIONAL ONLY ON THE CD

MISCELLANEOUS TOPICS
(Continued)

3044 Fasteners
3044 Stove Bolt
3044 Flattening Test
3044 Rivets, Cold Formed
3045 Expansion Bolt
3045 Washers
3045 Threads and Threading
3045 History of Briggs Pipe Thread (NPT)
3047 Lock-Nut Pipe Thread
3047 Thread Grinding
3048 Hand Chaser
3048 Thread-Cutting Methods
3049 Taps

MISCELLANEOUS TOPICS
(Continued)

3050 Machine Elements
3050 Nordberg Key
3050 Woodruff Keys
3050 Saddle Key
3050 Locomotive Development
3050 Percentages of Radial and Thrust Loads
3051 Roller Bearing
3051 Ball Bearing Lubrication
3052 Engine Governors
3053 Loaded or Weighted Fly-ball Governors
3053 Sensitiveness and Stability of Governors
3054 Shaft Governors
3054 Rope Splicing

Copyright 2004, Industrial Press, Inc., New York, NY

MATHEMATICS

↓ 0° or 180° Trigonometric and Involute Functions 179° or 359° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 0°–1°	Read Up	Minutes
0	0.000000	1.000000	0.000000	Infinite	1.000000	Infinite	0.0000000	Infinite	60
1	0.000291	1.000000	0.000291	3437.75	1.000000	3437.75	0.0000000	3436.176	59
2	0.000582	1.000000	0.000582	1718.87	1.000000	1718.87	0.0000000	1717.303	58
3	0.000873	1.000000	0.000873	1145.92	1.000000	1145.92	0.0000000	1144.345	57
4	0.001164	0.999999	0.001164	859.436	1.000001	859.437	0.0000000	857.8667	56
5	0.001454	0.999999	0.001454	687.549	1.000001	687.550	0.0000000	685.9795	55
6	0.001745	0.999998	0.001745	572.957	1.000002	572.958	0.0000000	571.3882	54
7	0.002036	0.999998	0.002036	491.106	1.000002	491.107	0.0000000	489.5372	53
8	0.002327	0.999997	0.002327	429.718	1.000003	429.719	0.0000000	428.1491	52
9	0.002618	0.999997	0.002618	381.971	1.000003	381.972	0.0000000	380.4028	51
10	0.002909	0.999996	0.002909	343.774	1.000004	343.775	0.0000000	342.2058	50
11	0.003200	0.999995	0.003200	312.521	1.000005	312.523	0.0000000	310.9538	49
12	0.003491	0.999994	0.003491	286.478	1.000006	286.479	0.0000000	284.9104	48
13	0.003782	0.999993	0.003782	264.441	1.000007	264.443	0.0000000	262.8738	47
14	0.004072	0.999992	0.004072	245.552	1.000008	245.554	0.0000000	243.9853	46
15	0.004363	0.999990	0.004363	229.182	1.000010	229.184	0.0000000	227.6152	45
16	0.004654	0.999989	0.004654	214.858	1.000011	214.860	0.0000000	213.2915	44
17	0.004945	0.999988	0.004945	202.219	1.000012	202.221	0.0000000	200.6529	43
18	0.005236	0.999986	0.005236	190.984	1.000014	190.987	0.0000000	189.4186	42
19	0.005527	0.999985	0.005527	180.932	1.000015	180.935	0.0000001	179.3669	41
20	0.005818	0.999983	0.005818	171.885	1.000017	171.888	0.0000001	170.3204	40
21	0.006109	0.999981	0.006109	163.700	1.000019	163.703	0.0000001	162.1355	39
22	0.006399	0.999980	0.006400	156.259	1.000020	156.262	0.0000001	154.6947	38
23	0.006690	0.999978	0.006691	149.465	1.000022	149.468	0.0000001	147.9009	37
24	0.006981	0.999976	0.006981	143.237	1.000024	143.241	0.0000001	141.6733	36
25	0.007272	0.999974	0.007272	137.507	1.000026	137.511	0.0000001	135.9439	35
26	0.007563	0.999971	0.007563	132.219	1.000029	132.222	0.0000001	130.6553	34
27	0.007854	0.999969	0.007854	127.321	1.000031	127.325	0.0000002	125.7584	33
28	0.008145	0.999967	0.008145	122.774	1.000033	122.778	0.0000002	121.2113	32
29	0.008436	0.999964	0.008436	118.540	1.000036	118.544	0.0000002	116.9778	31
30	0.008727	0.999962	0.008727	114.589	1.000038	114.593	0.0000002	113.0266	30
31	0.009017	0.999959	0.009018	110.892	1.000041	110.897	0.0000002	109.3303	29
32	0.009308	0.999957	0.009309	107.426	1.000043	107.431	0.0000003	105.8650	28
33	0.009599	0.999954	0.009600	104.171	1.000046	104.176	0.0000003	102.6097	27
34	0.009890	0.999951	0.009891	101.107	1.000049	101.112	0.0000003	99.54600	26
35	0.010181	0.999948	0.010181	98.2179	1.000052	98.2230	0.0000004	96.65733	25
36	0.010472	0.999945	0.010472	95.4895	1.000055	95.4947	0.0000004	93.92915	24
37	0.010763	0.999942	0.010763	92.9085	1.000058	92.9139	0.0000004	91.34845	23
38	0.011054	0.999939	0.011054	90.4633	1.000061	90.4689	0.0000005	88.90359	22
39	0.011344	0.999936	0.011345	88.1436	1.000064	88.1492	0.0000005	86.58412	21
40	0.011635	0.999932	0.011636	85.9398	1.000068	85.9456	0.0000005	84.38063	20
41	0.011926	0.999929	0.011927	83.8435	1.000071	83.8495	0.0000006	82.28464	19
42	0.012217	0.999925	0.012218	81.8470	1.000075	81.8531	0.0000006	80.28846	18
43	0.012508	0.999922	0.012509	79.9434	1.000078	79.9497	0.0000007	78.38514	17
44	0.012799	0.999918	0.012800	78.1263	1.000082	78.1327	0.0000007	76.56834	16
45	0.013090	0.999914	0.013091	76.3900	1.000086	76.3966	0.0000007	74.83230	15
46	0.013380	0.999910	0.013382	74.7292	1.000090	74.7359	0.0000008	73.17175	14
47	0.013671	0.999907	0.013673	73.1390	1.000093	73.1458	0.0000009	71.58187	13
48	0.013962	0.999903	0.013964	71.6151	1.000097	71.6221	0.0000009	70.05824	12
49	0.014253	0.999898	0.014254	70.1533	1.000102	70.1605	0.0000010	68.59680	11
50	0.014544	0.999894	0.014545	68.7501	1.000106	68.7574	0.0000010	67.19384	10
51	0.014835	0.999890	0.014836	67.4019	1.000110	67.4093	0.0000011	65.84589	9
52	0.015126	0.999886	0.015127	66.1055	1.000114	66.1130	0.0000012	64.54980	8
53	0.015416	0.999881	0.015418	64.8580	1.000119	64.8657	0.0000012	63.30263	7
54	0.015707	0.999877	0.015709	63.6567	1.000123	63.6646	0.0000013	62.10165	6
55	0.015998	0.999872	0.016000	62.4992	1.000128	62.5072	0.0000014	60.94436	5
56	0.016289	0.999867	0.016291	61.3829	1.000133	61.3911	0.0000014	59.82840	4
57	0.016580	0.999863	0.016582	60.3058	1.000137	60.3141	0.0000015	58.75160	3
58	0.016871	0.999858	0.016873	59.2659	1.000142	59.2743	0.0000016	57.71195	2
59	0.017162	0.999853	0.017164	58.2612	1.000147	58.2698	0.0000017	56.70754	1
60	0.017452	0.999848	0.017455	57.2900	1.000152	57.2987	0.0000018	55.73662	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	89°–90° Involute	Minutes

↑ 90° or 270° 89° or 269° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 1° or 181° Trigonometric and Involute Functions 178° or 358° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 1°–2°	Read Up	Minutes
0	0.017452	0.999848	0.017455	57.2900	1.000152	57.2987	0.0000018	55.73662	60
1	0.017743	0.999843	0.017746	56.3506	1.000157	56.3595	0.0000019	54.79754	59
2	0.018034	0.999837	0.018037	55.4415	1.000163	55.4505	0.0000020	53.88876	58
3	0.018325	0.999832	0.018328	54.5613	1.000168	54.5705	0.0000021	53.00883	57
4	0.018616	0.999827	0.018619	53.7086	1.000173	53.7179	0.0000022	52.15641	56
5	0.018907	0.999821	0.018910	52.8821	1.000179	52.8916	0.0000023	51.33022	55
6	0.019197	0.999816	0.019201	52.0807	1.000184	52.0903	0.0000024	50.52907	54
7	0.019488	0.999810	0.019492	51.3032	1.000190	51.3129	0.0000025	49.75185	53
8	0.019779	0.999804	0.019783	50.5485	1.000196	50.5584	0.0000026	48.99749	52
9	0.020070	0.999799	0.020074	49.8157	1.000201	49.8258	0.0000027	48.26500	51
10	0.020361	0.999793	0.020365	49.1039	1.000207	49.1141	0.0000028	47.55345	50
11	0.020652	0.999787	0.020656	48.4121	1.000213	48.4224	0.0000029	46.86194	49
12	0.020942	0.999781	0.020947	47.7395	1.000219	47.7500	0.0000031	46.18965	48
13	0.021233	0.999775	0.021238	47.0853	1.000226	47.0960	0.0000032	45.53578	47
14	0.021524	0.999768	0.021529	46.4489	1.000232	46.4596	0.0000033	44.89959	46
15	0.021815	0.999762	0.021820	45.8294	1.000238	45.8403	0.0000035	44.28037	45
16	0.022106	0.999756	0.022111	45.2261	1.000244	45.2372	0.0000036	43.67745	44
17	0.022397	0.999749	0.022402	44.6386	1.000251	44.6498	0.0000037	43.09020	43
18	0.022687	0.999743	0.022693	44.0661	1.000257	44.0775	0.0000039	42.51801	42
19	0.022978	0.999736	0.022984	43.5081	1.000264	43.5196	0.0000040	41.96031	41
20	0.023269	0.999729	0.023275	42.9641	1.000271	42.9757	0.0000042	41.41655	40
21	0.023560	0.999722	0.023566	42.4335	1.000278	42.4452	0.0000044	40.88623	39
22	0.023851	0.999716	0.023857	41.9158	1.000285	41.9277	0.0000045	40.36885	38
23	0.024141	0.999709	0.024148	41.4106	1.000292	41.4227	0.0000047	39.86393	37
24	0.024432	0.999701	0.024439	40.9174	1.000299	40.9296	0.0000049	39.37105	36
25	0.024723	0.999694	0.024731	40.4358	1.000306	40.4482	0.0000050	38.88977	35
26	0.025014	0.999687	0.025022	39.9655	1.000313	39.9780	0.0000052	38.41968	34
27	0.025305	0.999680	0.025313	39.5059	1.000320	39.5185	0.0000054	37.96041	33
28	0.025595	0.999672	0.025604	39.0568	1.000328	39.0696	0.0000056	37.51157	32
29	0.025886	0.999665	0.025895	38.6177	1.000335	38.6307	0.0000058	37.07283	31
30	0.026177	0.999657	0.026186	38.1885	1.000343	38.2016	0.0000060	36.64384	30
31	0.026468	0.999650	0.026477	37.7686	1.000350	37.7818	0.0000062	36.22429	29
32	0.026759	0.999642	0.026768	37.3579	1.000358	37.3713	0.0000064	35.81386	28
33	0.027049	0.999634	0.027059	36.9560	1.000366	36.9695	0.0000066	35.41226	27
34	0.027340	0.999626	0.027350	36.5627	1.000374	36.5763	0.0000068	35.01921	26
35	0.027631	0.999618	0.027641	36.1776	1.000382	36.1914	0.0000070	34.63443	25
36	0.027922	0.999610	0.027933	35.8006	1.000390	35.8145	0.0000073	34.25768	24
37	0.028212	0.999602	0.028224	35.4313	1.000398	35.4454	0.0000075	33.88870	23
38	0.028503	0.999594	0.028515	35.0695	1.000406	35.0838	0.0000077	33.52726	22
39	0.028794	0.999585	0.028806	34.7151	1.000415	34.7295	0.0000080	33.17312	21
40	0.029085	0.999577	0.029097	34.3678	1.000423	34.3823	0.0000082	32.82606	20
41	0.029375	0.999568	0.029388	34.0273	1.000432	34.0420	0.0000085	32.48589	19
42	0.029666	0.999560	0.029679	33.6935	1.000440	33.7083	0.0000087	32.15238	18
43	0.029957	0.999551	0.029970	33.3662	1.000449	33.3812	0.0000090	31.82536	17
44	0.030248	0.999542	0.030262	33.0452	1.000458	33.0603	0.0000092	31.50463	16
45	0.030539	0.999534	0.030553	32.7303	1.000467	32.7455	0.0000095	31.19001	15
46	0.030829	0.999525	0.030844	32.4213	1.000476	32.4367	0.0000098	30.88133	14
47	0.031120	0.999516	0.031135	32.1181	1.000485	32.1337	0.0000101	30.57843	13
48	0.031411	0.999507	0.031426	31.8205	1.000494	31.8362	0.0000103	30.28114	12
49	0.031702	0.999497	0.031717	31.5284	1.000503	31.5442	0.0000106	29.98930	11
50	0.031992	0.999488	0.032009	31.2416	1.000512	31.2576	0.0000109	29.70278	10
51	0.032283	0.999479	0.032300	30.9599	1.000522	30.9761	0.0000112	29.42142	9
52	0.032574	0.999469	0.032591	30.6833	1.000531	30.6996	0.0000115	29.14509	8
53	0.032864	0.999460	0.032882	30.4116	1.000540	30.4280	0.0000118	28.87365	7
54	0.033155	0.999450	0.033173	30.1446	1.000550	30.1612	0.0000122	28.60698	6
55	0.033446	0.999441	0.033465	29.8823	1.000560	29.8990	0.0000125	28.34495	5
56	0.033737	0.999431	0.033756	29.6245	1.000570	29.6414	0.0000128	28.08745	4
57	0.034027	0.999421	0.034047	29.3711	1.000579	29.3881	0.0000131	27.83434	3
58	0.034318	0.999411	0.034338	29.1220	1.000589	29.1392	0.0000135	27.58553	2
59	0.034609	0.999401	0.034630	28.8771	1.000599	28.8944	0.0000138	27.34091	1
60	0.034899	0.999391	0.034921	28.6363	1.000610	28.6537	0.0000142	27.10036	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	88°–89° Involute	Minutes

↑ 91° or 271° 88° or 268° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 2° or 182° Trigonometric and Involute Functions 177° or 357° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 2°–3°	Read Up	Minutes
0	0.034899	0.999391	0.034921	28.6363	1.000610	28.6537	0.0000142	27.10036	60
1	0.035190	0.999381	0.035212	28.3994	1.000620	28.4170	0.0000145	26.86380	59
2	0.035481	0.999370	0.035503	28.1664	1.000630	28.1842	0.0000149	26.63111	58
3	0.035772	0.999360	0.035795	27.9372	1.000640	27.9551	0.0000153	26.40222	57
4	0.036062	0.999350	0.036086	27.7117	1.000651	27.7298	0.0000157	26.17701	56
5	0.036353	0.999339	0.036377	27.4899	1.000661	27.5080	0.0000160	25.95542	55
6	0.036644	0.999328	0.036668	27.2715	1.000672	27.2898	0.0000164	25.73734	54
7	0.036934	0.999318	0.036960	27.0566	1.000683	27.0750	0.0000168	25.52270	53
8	0.037225	0.999307	0.037251	26.8450	1.000694	26.8636	0.0000172	25.31142	52
9	0.037516	0.999296	0.037542	26.6367	1.000704	26.6555	0.0000176	25.10342	51
10	0.037806	0.999285	0.037834	26.4316	1.000715	26.4505	0.0000180	24.89862	50
11	0.038097	0.999274	0.038125	26.2296	1.000726	26.2487	0.0000185	24.69695	49
12	0.038388	0.999263	0.038416	26.0307	1.000738	26.0499	0.0000189	24.49834	48
13	0.038678	0.999252	0.038707	25.8348	1.000749	25.8542	0.0000193	24.30271	47
14	0.038969	0.999240	0.038999	25.6418	1.000760	25.6613	0.0000198	24.11002	46
15	0.039260	0.999229	0.039290	25.4517	1.000772	25.4713	0.0000202	23.92017	45
16	0.039550	0.999218	0.039581	25.2644	1.000783	25.2841	0.0000207	23.73313	44
17	0.039841	0.999206	0.039873	25.0798	1.000795	25.0997	0.0000211	23.54881	43
18	0.040132	0.999194	0.040164	24.8978	1.000806	24.9179	0.0000216	23.36717	42
19	0.040422	0.999183	0.040456	24.7185	1.000818	24.7387	0.0000220	23.18815	41
20	0.040713	0.999171	0.040747	24.5418	1.000830	24.5621	0.0000225	23.01169	40
21	0.041004	0.999159	0.041038	24.3675	1.000842	24.3880	0.0000230	22.83773	39
22	0.041294	0.999147	0.041330	24.1957	1.000854	24.2164	0.0000235	22.66622	38
23	0.041585	0.999135	0.041621	24.0263	1.000866	24.0471	0.0000240	22.49712	37
24	0.041876	0.999123	0.041912	23.8593	1.000878	23.8802	0.0000245	22.33037	36
25	0.042166	0.999111	0.042204	23.6945	1.000890	23.7156	0.0000250	22.16592	35
26	0.042457	0.999098	0.042495	23.5321	1.000903	23.5533	0.0000256	22.00373	34
27	0.042748	0.999086	0.042787	23.3718	1.000915	23.3932	0.0000261	21.84374	33
28	0.043038	0.999073	0.043078	23.2137	1.000927	23.2352	0.0000266	21.68592	32
29	0.043329	0.999061	0.043370	23.0577	1.000940	23.0794	0.0000272	21.53022	31
30	0.043619	0.999048	0.043661	22.9038	1.000953	22.9256	0.0000277	21.37660	30
31	0.043910	0.999035	0.043952	22.7519	1.000965	22.7739	0.0000283	21.22502	29
32	0.044201	0.999023	0.044244	22.6020	1.000978	22.6241	0.0000288	21.07543	28
33	0.044491	0.999010	0.044535	22.4541	1.000991	22.4764	0.0000294	20.92781	27
34	0.044782	0.998997	0.044827	22.3081	1.001004	22.3305	0.0000300	20.78210	26
35	0.045072	0.998984	0.045118	22.1640	1.001017	22.1865	0.0000306	20.63827	25
36	0.045363	0.998971	0.045410	22.0217	1.001030	22.0444	0.0000312	20.49629	24
37	0.045654	0.998957	0.045701	21.8813	1.001044	21.9041	0.0000318	20.35612	23
38	0.045944	0.998944	0.045993	21.7426	1.001057	21.7656	0.0000324	20.21773	22
39	0.046235	0.998931	0.046284	21.6056	1.001071	21.6288	0.0000330	20.08108	21
40	0.046525	0.998917	0.046576	21.4704	1.001084	21.4937	0.0000336	19.94615	20
41	0.046816	0.998904	0.046867	21.3369	1.001098	21.3603	0.0000343	19.81289	19
42	0.047106	0.998890	0.047159	21.2049	1.001111	21.2285	0.0000349	19.68128	18
43	0.047397	0.998876	0.047450	21.0747	1.001125	21.0984	0.0000356	19.55128	17
44	0.047688	0.998862	0.047742	20.9460	1.001139	20.9698	0.0000362	19.42288	16
45	0.047978	0.998848	0.048033	20.8188	1.001153	20.8428	0.0000369	19.29603	15
46	0.048269	0.998834	0.048325	20.6932	1.001167	20.7174	0.0000376	19.17071	14
47	0.048559	0.998820	0.048617	20.5691	1.001181	20.5934	0.0000382	19.04690	13
48	0.048850	0.998806	0.048908	20.4465	1.001195	20.4709	0.0000389	18.92456	12
49	0.049140	0.998792	0.049200	20.3253	1.001210	20.3499	0.0000396	18.80367	11
50	0.049431	0.998778	0.049491	20.2056	1.001224	20.2303	0.0000403	18.68421	10
51	0.049721	0.998763	0.049783	20.0872	1.001238	20.1121	0.0000411	18.56614	9
52	0.050012	0.998749	0.050075	19.9702	1.001253	19.9952	0.0000418	18.44946	8
53	0.050302	0.998734	0.050366	19.8546	1.001268	19.8798	0.0000425	18.33412	7
54	0.050593	0.998719	0.050658	19.7403	1.001282	19.7656	0.0000433	18.22011	6
55	0.050883	0.998705	0.050949	19.6273	1.001297	19.6528	0.0000440	18.10740	5
56	0.051174	0.998690	0.051241	19.5156	1.001312	19.5412	0.0000448	17.99598	4
57	0.051464	0.998675	0.051533	19.4051	1.001327	19.4309	0.0000455	17.88582	3
58	0.051755	0.998660	0.051824	19.2959	1.001342	19.3218	0.0000463	17.77690	2
59	0.052045	0.998645	0.052116	19.1879	1.001357	19.2140	0.0000471	17.66920	1
60	0.052336	0.998630	0.052408	19.0811	1.001372	19.1073	0.0000479	17.56270	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	87°–88° Involute	Minutes

↑ 92° or 272° 87° or 267° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 3° or 183° Trigonometric and Involute Functions 176° or 356° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 3°–4°	Read Up	Minutes
0	0.052336	0.998630	0.052408	19.0811	1.001372	19.1073	0.0000479	17.56270	60
1	0.052626	0.998614	0.052699	18.9755	1.001388	19.0019	0.0000487	17.45738	59
2	0.052917	0.998599	0.052991	18.8711	1.001403	18.8975	0.0000495	17.35321	58
3	0.053207	0.998583	0.053283	18.7678	1.001419	18.7944	0.0000503	17.25019	57
4	0.053498	0.998568	0.053575	18.6656	1.001434	18.6923	0.0000512	17.14829	56
5	0.053788	0.998552	0.053866	18.5645	1.001450	18.5914	0.0000520	17.04749	55
6	0.054079	0.998537	0.054158	18.4645	1.001465	18.4915	0.0000529	16.94778	54
7	0.054369	0.998521	0.054450	18.3655	1.001481	18.3927	0.0000537	16.84914	53
8	0.054660	0.998505	0.054742	18.2677	1.001497	18.2950	0.0000546	16.75155	52
9	0.054950	0.998489	0.055033	18.1708	1.001513	18.1983	0.0000555	16.65499	51
10	0.055241	0.998473	0.055325	18.0750	1.001529	18.1026	0.0000563	16.55945	50
11	0.055531	0.998457	0.055617	17.9802	1.001545	18.0079	0.0000572	16.46491	49
12	0.055822	0.998441	0.055909	17.8863	1.001562	17.9142	0.0000581	16.37136	48
13	0.056112	0.998424	0.056200	17.7934	1.001578	17.8215	0.0000591	16.27879	47
14	0.056402	0.998408	0.056492	17.7015	1.001594	17.7298	0.0000600	16.18717	46
15	0.056693	0.998392	0.056784	17.6106	1.001611	17.6389	0.0000609	16.09649	45
16	0.056983	0.998375	0.057076	17.5205	1.001628	17.5490	0.0000619	16.00673	44
17	0.057274	0.998359	0.057368	17.4314	1.001644	17.4600	0.0000628	15.91789	43
18	0.057564	0.998342	0.057660	17.3432	1.001661	17.3720	0.0000638	15.82995	42
19	0.057854	0.998325	0.057951	17.2558	1.001678	17.2848	0.0000647	15.74290	41
20	0.058145	0.998308	0.058243	17.1693	1.001695	17.1984	0.0000657	15.65672	40
21	0.058435	0.998291	0.058535	17.0837	1.001712	17.1130	0.0000667	15.57140	39
22	0.058726	0.998274	0.058827	16.9990	1.001729	17.0283	0.0000677	15.48692	38
23	0.059016	0.998257	0.059119	16.9150	1.001746	16.9446	0.0000687	15.40328	37
24	0.059306	0.998240	0.059411	16.8319	1.001763	16.8616	0.0000698	15.32046	36
25	0.059597	0.998223	0.059703	16.7496	1.001781	16.7794	0.0000708	15.23845	35
26	0.059887	0.998205	0.059995	16.6681	1.001798	16.6981	0.0000718	15.15724	34
27	0.060177	0.998188	0.060287	16.5874	1.001816	16.6175	0.0000729	15.07681	33
28	0.060468	0.998170	0.060579	16.5075	1.001833	16.5377	0.0000739	14.99716	32
29	0.060758	0.998153	0.060871	16.4283	1.001851	16.4587	0.0000750	14.91828	31
30	0.061049	0.998135	0.061163	16.3499	1.001869	16.3804	0.0000761	14.84015	30
31	0.061339	0.998117	0.061455	16.2722	1.001887	16.3029	0.0000772	14.76276	29
32	0.061629	0.998099	0.061747	16.1952	1.001905	16.2261	0.0000783	14.68610	28
33	0.061920	0.998081	0.062039	16.1190	1.001923	16.1500	0.0000794	14.61016	27
34	0.062210	0.998063	0.062331	16.0435	1.001941	16.0746	0.0000805	14.53494	26
35	0.062500	0.998045	0.062623	15.9687	1.001959	15.9999	0.0000817	14.46041	25
36	0.062791	0.998027	0.062915	15.8945	1.001977	15.9260	0.0000828	14.38658	24
37	0.063081	0.998008	0.063207	15.8211	1.001996	15.8527	0.0000840	14.31343	23
38	0.063371	0.997990	0.063499	15.7483	1.002014	15.7801	0.0000851	14.24095	22
39	0.063661	0.997972	0.063791	15.6762	1.002033	15.7081	0.0000863	14.16914	21
40	0.063952	0.997953	0.064083	15.6048	1.002051	15.6368	0.0000875	14.09798	20
41	0.064242	0.997934	0.064375	15.5340	1.002070	15.5661	0.0000887	14.02747	19
42	0.064532	0.997916	0.064667	15.4638	1.002089	15.4961	0.0000899	13.95759	18
43	0.064823	0.997897	0.064959	15.3943	1.002108	15.4267	0.0000911	13.88835	17
44	0.065113	0.997878	0.065251	15.3254	1.002127	15.3579	0.0000924	13.81972	16
45	0.065403	0.997859	0.065543	15.2571	1.002146	15.2898	0.0000936	13.75171	15
46	0.065693	0.997840	0.065836	15.1893	1.002165	15.2222	0.0000949	13.68429	14
47	0.065984	0.997821	0.066128	15.1222	1.002184	15.1553	0.0000961	13.61748	13
48	0.066274	0.997801	0.066420	15.0557	1.002203	15.0889	0.0000974	13.55125	12
49	0.066564	0.997782	0.066712	14.9898	1.002223	15.0231	0.0000987	13.48560	11
50	0.066854	0.997763	0.067004	14.9244	1.002242	14.9579	0.0001000	13.42052	10
51	0.067145	0.997743	0.067296	14.8596	1.002262	14.8932	0.0001013	13.35601	9
52	0.067435	0.997724	0.067589	14.7954	1.002282	14.8291	0.0001026	13.29206	8
53	0.067725	0.997704	0.067881	14.7317	1.002301	14.7656	0.0001040	13.22866	7
54	0.068015	0.997684	0.068173	14.6685	1.002321	14.7026	0.0001053	13.16580	6
55	0.068306	0.997664	0.068465	14.6059	1.002341	14.6401	0.0001067	13.10348	5
56	0.068596	0.997645	0.068758	14.5438	1.002361	14.5782	0.0001080	13.04169	4
57	0.068886	0.997625	0.069050	14.4823	1.002381	14.5168	0.0001094	12.98042	3
58	0.069176	0.997604	0.069342	14.4212	1.002401	14.4559	0.0001108	12.91966	2
59	0.069466	0.997584	0.069635	14.3607	1.002422	14.3955	0.0001122	12.85942	1
60	0.069756	0.997564	0.069927	14.3007	1.002442	14.3356	0.0001136	12.79968	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	86°–87° Involute	Minutes

↑ 93° or 273° 86° or 266° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 4° or 184° Trigonometric and Involute Functions 175° or 355° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 4°–5°	Read Up	Minutes
0	0.069756	0.997564	0.069927	14.3007	1.002442	14.3356	0.0001136	12.79968	60
1	0.070047	0.997544	0.070219	14.2411	1.002462	14.2762	0.0001151	12.74044	59
2	0.070337	0.997523	0.070511	14.1821	1.002483	14.2173	0.0001165	12.68169	58
3	0.070627	0.997503	0.070804	14.1235	1.002503	14.1589	0.0001180	12.62343	57
4	0.070917	0.997482	0.071096	14.0655	1.002524	14.1010	0.0001194	12.56564	56
5	0.071207	0.997462	0.071389	14.0079	1.002545	14.0435	0.0001209	12.50833	55
6	0.071497	0.997441	0.071681	13.9507	1.002566	13.9865	0.0001224	12.45148	54
7	0.071788	0.997420	0.071973	13.8940	1.002587	13.9300	0.0001239	12.39510	53
8	0.072078	0.997399	0.072266	13.8378	1.002608	13.8739	0.0001254	12.33917	52
9	0.072368	0.997378	0.072558	13.7821	1.002629	13.8183	0.0001269	12.28369	51
10	0.072658	0.997357	0.072851	13.7267	1.002650	13.7631	0.0001285	12.22866	50
11	0.072948	0.997336	0.073143	13.6719	1.002671	13.7084	0.0001300	12.17407	49
12	0.073238	0.997314	0.073435	13.6174	1.002693	13.6541	0.0001316	12.11992	48
13	0.073528	0.997293	0.073728	13.5634	1.002714	13.6002	0.0001332	12.06619	47
14	0.073818	0.997272	0.074020	13.5098	1.002736	13.5468	0.0001347	12.01289	46
15	0.074108	0.997250	0.074313	13.4566	1.002757	13.4937	0.0001363	11.96001	45
16	0.074399	0.997229	0.074605	13.4039	1.002779	13.4411	0.0001380	11.90754	44
17	0.074689	0.997207	0.074898	13.3515	1.002801	13.3889	0.0001396	11.85548	43
18	0.074979	0.997185	0.075190	13.2996	1.002823	13.3371	0.0001412	11.80383	42
19	0.075269	0.997163	0.075483	13.2480	1.002845	13.2857	0.0001429	11.75257	41
20	0.075559	0.997141	0.075775	13.1969	1.002867	13.2347	0.0001445	11.70172	40
21	0.075849	0.997119	0.076068	13.1461	1.002889	13.1841	0.0001462	11.65125	39
22	0.076139	0.997097	0.076361	13.0958	1.002911	13.1339	0.0001479	11.60117	38
23	0.076429	0.997075	0.076653	13.0458	1.002934	13.0840	0.0001496	11.55148	37
24	0.076719	0.997053	0.076946	12.9962	1.002956	13.0346	0.0001513	11.50216	36
25	0.077009	0.997030	0.077238	12.9469	1.002978	12.9855	0.0001530	11.45321	35
26	0.077299	0.997008	0.077531	12.8981	1.003001	12.9368	0.0001548	11.40464	34
27	0.077589	0.996985	0.077824	12.8496	1.003024	12.8884	0.0001565	11.35643	33
28	0.077879	0.996963	0.078116	12.8014	1.003046	12.8404	0.0001583	11.30858	32
29	0.078169	0.996940	0.078409	12.7536	1.003069	12.7928	0.0001601	11.26109	31
30	0.078459	0.996917	0.078702	12.7062	1.003092	12.7455	0.0001619	11.21395	30
31	0.078749	0.996894	0.078994	12.6591	1.003115	12.6986	0.0001637	11.16716	29
32	0.079039	0.996872	0.079287	12.6124	1.003138	12.6520	0.0001655	11.12072	28
33	0.079329	0.996848	0.079580	12.5660	1.003161	12.6057	0.0001674	11.07461	27
34	0.079619	0.996825	0.079873	12.5199	1.003185	12.5598	0.0001692	11.02885	26
35	0.079909	0.996802	0.080165	12.4742	1.003208	12.5142	0.0001711	10.98342	25
36	0.080199	0.996779	0.080458	12.4288	1.003232	12.4690	0.0001729	10.93832	24
37	0.080489	0.996756	0.080751	12.3838	1.003255	12.4241	0.0001748	10.89355	23
38	0.080779	0.996732	0.081044	12.3390	1.003279	12.3795	0.0001767	10.84910	22
39	0.081069	0.996709	0.081336	12.2946	1.003302	12.3352	0.0001787	10.80497	21
40	0.081359	0.996685	0.081629	12.2505	1.003326	12.2913	0.0001806	10.76116	20
41	0.081649	0.996661	0.081922	12.2067	1.003350	12.2476	0.0001825	10.71766	19
42	0.081939	0.996637	0.082215	12.1632	1.003374	12.2043	0.0001845	10.67447	18
43	0.082228	0.996614	0.082508	12.1201	1.003398	12.1612	0.0001865	10.63159	17
44	0.082518	0.996590	0.082801	12.0772	1.003422	12.1185	0.0001885	10.58901	16
45	0.082808	0.996566	0.083094	12.0346	1.003446	12.0761	0.0001905	10.54673	15
46	0.083098	0.996541	0.083386	11.9923	1.003471	12.0340	0.0001925	10.50475	14
47	0.083388	0.996517	0.083679	11.9504	1.003495	11.9921	0.0001945	10.46306	13
48	0.083678	0.996493	0.083972	11.9087	1.003519	11.9506	0.0001965	10.42166	12
49	0.083968	0.996468	0.084265	11.8673	1.003544	11.9093	0.0001986	10.38055	11
50	0.084258	0.996444	0.084558	11.8262	1.003569	11.8684	0.0002007	10.33973	10
51	0.084547	0.996419	0.084851	11.7853	1.003593	11.8277	0.0002028	10.29919	9
52	0.084837	0.996395	0.085144	11.7448	1.003618	11.7873	0.0002049	10.25892	8
53	0.085127	0.996370	0.085437	11.7045	1.003643	11.7471	0.0002070	10.21893	7
54	0.085417	0.996345	0.085730	11.6645	1.003668	11.7073	0.0002091	10.17922	6
55	0.085707	0.996320	0.086023	11.6248	1.003693	11.6677	0.0002113	10.13978	5
56	0.085997	0.996295	0.086316	11.5853	1.003718	11.6284	0.0002134	10.10060	4
57	0.086286	0.996270	0.086609	11.5461	1.003744	11.5893	0.0002156	10.06169	3
58	0.086576	0.996245	0.086902	11.5072	1.003769	11.5505	0.0002178	10.02304	2
59	0.086866	0.996220	0.087196	11.4685	1.003794	11.5120	0.0002200	9.9846536	1
60	0.087156	0.996195	0.087489	11.4301	1.003820	11.4737	0.0002222	9.9465224	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	85°–86° Involute	Minutes

↑ 94° or 274° 85° or 265° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 5° or 185° Trigonometric and Involute Functions 174° or 354° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 5°–6°	Read Up	Minutes
0	0.087156	0.996195	0.087489	11.4301	1.003820	11.4737	0.0002222	9.9465224	60
1	0.087446	0.996169	0.087782	11.3919	1.003845	11.4357	0.0002244	9.9086459	59
2	0.087735	0.996144	0.088075	11.3540	1.003871	11.3979	0.0002267	9.8710215	58
3	0.088025	0.996118	0.088368	11.3163	1.003897	11.3604	0.0002289	9.8336468	57
4	0.088315	0.996093	0.088661	11.2789	1.003923	11.3231	0.0002312	9.7965192	56
5	0.088605	0.996067	0.088954	11.2417	1.003949	11.2861	0.0002335	9.7596363	55
6	0.088894	0.996041	0.089248	11.2048	1.003975	11.2493	0.0002358	9.7229958	54
7	0.089184	0.996015	0.089541	11.1681	1.004001	11.2128	0.0002382	9.6865952	53
8	0.089474	0.995989	0.089834	11.1316	1.004027	11.1765	0.0002405	9.6504322	52
9	0.089763	0.995963	0.090127	11.0954	1.004053	11.1404	0.0002429	9.6145046	51
10	0.090053	0.995937	0.090421	11.0594	1.004080	11.1045	0.0002452	9.5788100	50
11	0.090343	0.995911	0.090714	11.0237	1.004106	11.0689	0.0002476	9.5433462	49
12	0.090633	0.995884	0.091007	10.9882	1.004133	11.0336	0.0002500	9.5081109	48
13	0.090922	0.995858	0.091300	10.9529	1.004159	10.9984	0.0002524	9.4731021	47
14	0.091212	0.995832	0.091594	10.9178	1.004186	10.9635	0.0002549	9.4383174	46
15	0.091502	0.995805	0.091887	10.8829	1.004213	10.9288	0.0002573	9.4037549	45
16	0.091791	0.995778	0.092180	10.8483	1.004240	10.8943	0.0002598	9.3694123	44
17	0.092081	0.995752	0.092474	10.8139	1.004267	10.8600	0.0002622	9.3352876	43
18	0.092371	0.995725	0.092767	10.7797	1.004294	10.8260	0.0002647	9.3013788	42
19	0.092660	0.995698	0.093061	10.7457	1.004321	10.7921	0.0002673	9.2676838	41
20	0.092950	0.995671	0.093354	10.7119	1.004348	10.7585	0.0002698	9.2342005	40
21	0.093239	0.995644	0.093647	10.6783	1.004375	10.7251	0.0002723	9.2009271	39
22	0.093529	0.995617	0.093941	10.6450	1.004403	10.6919	0.0002749	9.1678616	38
23	0.093819	0.995589	0.094234	10.6118	1.004430	10.6589	0.0002775	9.1350020	37
24	0.094108	0.995562	0.094528	10.5789	1.004458	10.6261	0.0002801	9.1023464	36
25	0.094398	0.995535	0.094821	10.5462	1.004485	10.5935	0.0002827	9.0698930	35
26	0.094687	0.995507	0.095115	10.5136	1.004513	10.5611	0.0002853	9.0376399	34
27	0.094977	0.995479	0.095408	10.4813	1.004541	10.5289	0.0002879	9.0055852	33
28	0.095267	0.995452	0.095702	10.4491	1.004569	10.4969	0.0002906	8.9737272	32
29	0.095556	0.995424	0.095995	10.4172	1.004597	10.4650	0.0002933	8.9420640	31
30	0.095846	0.995396	0.096289	10.3854	1.004625	10.4334	0.0002959	8.9105939	30
31	0.096135	0.995368	0.096583	10.3538	1.004653	10.4020	0.0002986	8.8793151	29
32	0.096425	0.995340	0.096876	10.3224	1.004682	10.3708	0.0003014	8.8482258	28
33	0.096714	0.995312	0.097170	10.2913	1.004710	10.3397	0.0003041	8.8173245	27
34	0.097004	0.995284	0.097464	10.2602	1.004738	10.3089	0.0003069	8.7866094	26
35	0.097293	0.995256	0.097757	10.2294	1.004767	10.2782	0.0003096	8.7560788	25
36	0.097583	0.995227	0.098051	10.1988	1.004795	10.2477	0.0003124	8.7257311	24
37	0.097872	0.995199	0.098345	10.1683	1.004824	10.2174	0.0003152	8.6955646	23
38	0.098162	0.995170	0.098638	10.1381	1.004853	10.1873	0.0003180	8.6655778	22
39	0.098451	0.995142	0.098932	10.1080	1.004882	10.1573	0.0003209	8.6357690	21
40	0.098741	0.995113	0.099226	10.0780	1.004911	10.1275	0.0003237	8.6061367	20
41	0.099030	0.995084	0.099519	10.0483	1.004940	10.0979	0.0003266	8.5766794	19
42	0.099320	0.995056	0.099813	10.0187	1.004969	10.0685	0.0003295	8.5473954	18
43	0.099609	0.995027	0.100107	9.989305	1.004998	10.0392	0.0003324	8.5182834	17
44	0.099899	0.994998	0.100401	9.960072	1.005028	10.0101	0.0003353	8.4893417	16
45	0.100188	0.994969	0.100695	9.931009	1.005057	9.981229	0.0003383	8.4605689	15
46	0.100477	0.994939	0.100989	9.902113	1.005086	9.952479	0.0003412	8.4319635	14
47	0.100767	0.994910	0.101282	9.873382	1.005116	9.923894	0.0003442	8.4035241	13
48	0.101056	0.994881	0.101576	9.844817	1.005146	9.895474	0.0003472	8.3752493	12
49	0.101346	0.994851	0.101870	9.816414	1.005175	9.867218	0.0003502	8.3471377	11
50	0.101635	0.994822	0.102164	9.788173	1.005205	9.839123	0.0003532	8.3191877	10
51	0.101924	0.994792	0.102458	9.760093	1.005235	9.811188	0.0003563	8.2913982	9
52	0.102214	0.994762	0.102752	9.732171	1.005265	9.783412	0.0003593	8.2637676	8
53	0.102503	0.994733	0.103046	9.704407	1.005295	9.755794	0.0003624	8.2362947	7
54	0.102793	0.994703	0.103340	9.676800	1.005325	9.728333	0.0003655	8.2089781	6
55	0.103082	0.994673	0.103634	9.649347	1.005356	9.701026	0.0003686	8.1818164	5
56	0.103371	0.994643	0.103928	9.622049	1.005386	9.673873	0.0003718	8.1548085	4
57	0.103661	0.994613	0.104222	9.594902	1.005416	9.646872	0.0003749	8.1279529	3
58	0.103950	0.994583	0.104516	9.567907	1.005447	9.620023	0.0003781	8.1012485	2
59	0.104239	0.994552	0.104810	9.541061	1.005478	9.593323	0.0003813	8.0746939	1
60	0.104528	0.994522	0.105104	9.514364	1.005508	9.566772	0.0003845	8.0482879	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	84°–85° Involute	Minutes

↑ 95° or 275° 84° or 264° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 6° or 186° Trigonometric and Involute Functions 173° or 353° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 6°–7°	Read Up	Minutes
0	0.104528	0.994522	0.105104	9.514364	1.005508	9.566772	0.0003845	8.0482879	60
1	0.104818	0.994491	0.105398	9.487815	1.005539	9.540369	0.0003877	8.0220292	59
2	0.105107	0.994461	0.105692	9.461412	1.005570	9.514111	0.0003909	7.9959168	58
3	0.105396	0.994430	0.105987	9.435153	1.005601	9.487998	0.0003942	7.9699492	57
4	0.105686	0.994400	0.106281	9.409038	1.005632	9.462030	0.0003975	7.9441254	56
5	0.105975	0.994369	0.106575	9.383066	1.005663	9.436203	0.0004008	7.9184441	55
6	0.106264	0.994338	0.106869	9.357236	1.005694	9.410518	0.0004041	7.8929043	54
7	0.106553	0.994307	0.107163	9.331545	1.005726	9.384974	0.0004074	7.8675047	53
8	0.106843	0.994276	0.107458	9.305994	1.005757	9.359568	0.0004108	7.8422441	52
9	0.107132	0.994245	0.107752	9.280580	1.005788	9.334301	0.0004141	7.8171216	51
10	0.107421	0.994214	0.108046	9.255304	1.005820	9.309170	0.0004175	7.7921359	50
11	0.107710	0.994182	0.108340	9.230163	1.005852	9.284175	0.0004209	7.7672859	49
12	0.107999	0.994151	0.108635	9.205156	1.005883	9.259314	0.0004244	7.7425705	48
13	0.108289	0.994120	0.108929	9.180284	1.005915	9.234588	0.0004278	7.7179887	47
14	0.108578	0.994088	0.109223	9.155544	1.005947	9.209993	0.0004313	7.6935394	46
15	0.108867	0.994056	0.109518	9.130935	1.005979	9.185531	0.0004347	7.6692216	45
16	0.109156	0.994025	0.109812	9.106456	1.006011	9.161198	0.0004382	7.6450341	44
17	0.109445	0.993993	0.110107	9.082107	1.006043	9.136995	0.0004417	7.6209759	43
18	0.109734	0.993961	0.110401	9.057887	1.006076	9.112920	0.0004453	7.5970461	42
19	0.110023	0.993929	0.110695	9.033793	1.006108	9.088972	0.0004488	7.5732436	41
20	0.110313	0.993897	0.110990	9.009826	1.006141	9.065151	0.0004524	7.5495673	40
21	0.110602	0.993865	0.111284	8.985984	1.006173	9.041455	0.0004560	7.5260164	39
22	0.110891	0.993833	0.111579	8.962267	1.006206	9.017884	0.0004596	7.5025898	38
23	0.111180	0.993800	0.111873	8.938673	1.006238	8.994435	0.0004632	7.4792865	37
24	0.111469	0.993768	0.112168	8.915201	1.006271	8.971110	0.0004669	7.4561056	36
25	0.111758	0.993735	0.112463	8.891850	1.006304	8.947905	0.0004706	7.4330461	35
26	0.112047	0.993703	0.112757	8.868621	1.006337	8.924821	0.0004743	7.4101071	34
27	0.112336	0.993670	0.113052	8.845510	1.006370	8.901857	0.0004780	7.3872877	33
28	0.112625	0.993638	0.113346	8.822519	1.006403	8.879011	0.0004817	7.3645869	32
29	0.112914	0.993605	0.113641	8.799645	1.006436	8.856283	0.0004854	7.3420037	31
30	0.113203	0.993572	0.113936	8.776887	1.006470	8.833671	0.0004892	7.3195374	30
31	0.113492	0.993539	0.114230	8.754246	1.006503	8.811176	0.0004930	7.2971870	29
32	0.113781	0.993506	0.114525	8.731720	1.006537	8.788796	0.0004968	7.2749516	28
33	0.114070	0.993473	0.114820	8.709308	1.006570	8.766530	0.0005006	7.2528304	27
34	0.114359	0.993439	0.115114	8.687009	1.006604	8.744377	0.0005045	7.2308224	26
35	0.114648	0.993406	0.115409	8.664822	1.006638	8.722336	0.0005083	7.2089269	25
36	0.114937	0.993373	0.115704	8.642747	1.006671	8.700407	0.0005122	7.1871429	24
37	0.115226	0.993339	0.115999	8.620783	1.006705	8.678589	0.0005161	7.1654696	23
38	0.115515	0.993306	0.116294	8.598929	1.006739	8.656881	0.0005200	7.1439062	22
39	0.115804	0.993272	0.116588	8.577184	1.006773	8.635281	0.0005240	7.1224518	21
40	0.116093	0.993238	0.116883	8.555547	1.006808	8.613790	0.0005280	7.1011057	20
41	0.116382	0.993205	0.117178	8.534017	1.006842	8.592407	0.0005319	7.0798671	19
42	0.116671	0.993171	0.117473	8.512594	1.006876	8.571130	0.0005359	7.0587350	18
43	0.116960	0.993137	0.117768	8.491277	1.006911	8.549958	0.0005400	7.0377088	17
44	0.117249	0.993103	0.118063	8.470065	1.006945	8.528892	0.0005440	7.0167876	16
45	0.117537	0.993068	0.118358	8.448957	1.006980	8.507930	0.0005481	6.9959707	15
46	0.117826	0.993034	0.118653	8.427953	1.007015	8.487072	0.0005522	6.9752573	14
47	0.118115	0.993000	0.118948	8.407052	1.007049	8.466316	0.0005563	6.9546467	13
48	0.118404	0.992966	0.119243	8.386252	1.007084	8.445663	0.0005604	6.9341380	12
49	0.118693	0.992931	0.119538	8.365554	1.007119	8.425111	0.0005645	6.9137305	11
50	0.118982	0.992896	0.119833	8.344956	1.007154	8.404659	0.0005687	6.8934236	10
51	0.119270	0.992862	0.120128	8.324458	1.007190	8.384306	0.0005729	6.8732164	9
52	0.119559	0.992827	0.120423	8.304059	1.007225	8.364053	0.0005771	6.8531082	8
53	0.119848	0.992792	0.120718	8.283758	1.007260	8.343899	0.0005813	6.8330984	7
54	0.120137	0.992757	0.121013	8.263555	1.007295	8.323841	0.0005856	6.8131861	6
55	0.120426	0.992722	0.121308	8.243448	1.007331	8.303881	0.0005898	6.7933708	5
56	0.120714	0.992687	0.121604	8.223438	1.007367	8.284017	0.0005941	6.7736516	4
57	0.121003	0.992652	0.121899	8.203524	1.007402	8.264249	0.0005985	6.7540279	3
58	0.121292	0.992617	0.122194	8.183704	1.007438	8.244575	0.0006028	6.7344991	2
59	0.121581	0.992582	0.122489	8.163979	1.007474	8.224995	0.0006071	6.7150644	1
60	0.121869	0.992546	0.122785	8.144346	1.007510	8.205509	0.0006115	6.6957231	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	83°–84° Involute	Minutes

↑ 96° or 276° 83° or 263° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 7° or 187° Trigonometric and Involute Functions 172° or 352° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 7°–8°	Read Up	Minutes
0	0.121869	0.992546	0.122785	8.144346	1.007510	8.205509	0.0006115	6.6957231	60
1	0.122158	0.992511	0.123080	8.124807	1.007546	8.186116	0.0006159	6.6764747	59
2	0.122447	0.992475	0.123375	8.105360	1.007582	8.166815	0.0006203	6.6573184	58
3	0.122735	0.992439	0.123670	8.086004	1.007618	8.147605	0.0006248	6.6382536	57
4	0.123024	0.992404	0.123966	8.066739	1.007654	8.128486	0.0006292	6.6192796	56
5	0.123313	0.992368	0.124261	8.047565	1.007691	8.109457	0.0006337	6.6003959	55
6	0.123601	0.992332	0.124557	8.028480	1.007727	8.090518	0.0006382	6.5816017	54
7	0.123890	0.992296	0.124852	8.009483	1.007764	8.071668	0.0006427	6.5628964	53
8	0.124179	0.992260	0.125147	7.990576	1.007801	8.052906	0.0006473	6.5442795	52
9	0.124467	0.992224	0.125443	7.971755	1.007837	8.034232	0.0006518	6.5257502	51
10	0.124756	0.992187	0.125738	7.953022	1.007874	8.015645	0.0006564	6.5073080	50
11	0.125045	0.992151	0.126034	7.934376	1.007911	7.997144	0.0006610	6.4889523	49
12	0.125333	0.992115	0.126329	7.915815	1.007948	7.978730	0.0006657	6.4706825	48
13	0.125622	0.992078	0.126625	7.897340	1.007985	7.960400	0.0006703	6.4524979	47
14	0.125910	0.992042	0.126920	7.878949	1.008022	7.942156	0.0006750	6.4343981	46
15	0.126199	0.992005	0.127216	7.860642	1.008059	7.923995	0.0006797	6.4163823	45
16	0.126488	0.991968	0.127512	7.842419	1.008097	7.905918	0.0006844	6.3984501	44
17	0.126776	0.991931	0.127807	7.824279	1.008134	7.887924	0.0006892	6.3806008	43
18	0.127065	0.991894	0.128103	7.806221	1.008172	7.870012	0.0006939	6.3628339	42
19	0.127353	0.991857	0.128399	7.788245	1.008209	7.852182	0.0006987	6.3451489	41
20	0.127642	0.991820	0.128694	7.770351	1.008247	7.834433	0.0007035	6.3275451	40
21	0.127930	0.991783	0.128990	7.752537	1.008285	7.816766	0.0007083	6.3100220	39
22	0.128219	0.991746	0.129286	7.734803	1.008323	7.799178	0.0007132	6.2925791	38
23	0.128507	0.991709	0.129582	7.717149	1.008361	7.781670	0.0007181	6.2752158	37
24	0.128796	0.991671	0.129877	7.699574	1.008399	7.764241	0.0007230	6.2579315	36
25	0.129084	0.991634	0.130173	7.682077	1.008437	7.746890	0.0007279	6.2407259	35
26	0.129373	0.991596	0.130469	7.664658	1.008475	7.729618	0.0007328	6.2235982	34
27	0.129661	0.991558	0.130765	7.647317	1.008513	7.712423	0.0007378	6.2065481	33
28	0.129949	0.991521	0.131061	7.630053	1.008552	7.695305	0.0007428	6.1895749	32
29	0.130238	0.991483	0.131357	7.612866	1.008590	7.678263	0.0007478	6.1726782	31
30	0.130526	0.991445	0.131652	7.595754	1.008629	7.661298	0.0007528	6.1558575	30
31	0.130815	0.991407	0.131948	7.578718	1.008668	7.644407	0.0007579	6.1391122	29
32	0.131103	0.991369	0.132244	7.561757	1.008706	7.627592	0.0007629	6.1224418	28
33	0.131391	0.991331	0.132540	7.544870	1.008745	7.610852	0.0007680	6.1058460	27
34	0.131680	0.991292	0.132836	7.528057	1.008784	7.594185	0.0007732	6.0893240	26
35	0.131968	0.991254	0.133132	7.511318	1.008823	7.577592	0.0007783	6.0728756	25
36	0.132256	0.991216	0.133428	7.494651	1.008862	7.561071	0.0007835	6.0565001	24
37	0.132545	0.991177	0.133725	7.478058	1.008902	7.544624	0.0007887	6.0401971	23
38	0.132833	0.991138	0.134021	7.461536	1.008941	7.528248	0.0007939	6.0239662	22
39	0.133121	0.991100	0.134317	7.445086	1.008980	7.511944	0.0007991	6.0078069	21
40	0.133410	0.991061	0.134613	7.428706	1.009020	7.495711	0.0008044	5.9917186	20
41	0.133698	0.991022	0.134909	7.412398	1.009059	7.479548	0.0008096	5.9757010	19
42	0.133986	0.990983	0.135205	7.396160	1.009099	7.463456	0.0008150	5.9597535	18
43	0.134274	0.990944	0.135502	7.379991	1.009139	7.447433	0.0008203	5.9438758	17
44	0.134563	0.990905	0.135798	7.363892	1.009178	7.431480	0.0008256	5.9280674	16
45	0.134851	0.990866	0.136094	7.347861	1.009218	7.415596	0.0008310	5.9123277	15
46	0.135139	0.990827	0.136390	7.331899	1.009258	7.399780	0.0008364	5.8966565	14
47	0.135427	0.990787	0.136687	7.316005	1.009298	7.384032	0.0008418	5.8810532	13
48	0.135716	0.990748	0.136983	7.300178	1.009339	7.368351	0.0008473	5.8655174	12
49	0.136004	0.990708	0.137279	7.284418	1.009379	7.352738	0.0008527	5.8500487	11
50	0.136292	0.990669	0.137576	7.268725	1.009419	7.337191	0.0008582	5.8346466	10
51	0.136580	0.990629	0.137872	7.253099	1.009460	7.321710	0.0008638	5.8193107	9
52	0.136868	0.990589	0.138169	7.237538	1.009500	7.306295	0.0008693	5.8040407	8
53	0.137156	0.990549	0.138465	7.222042	1.009541	7.290946	0.0008749	5.7888360	7
54	0.137445	0.990509	0.138761	7.206612	1.009581	7.275662	0.0008805	5.7736963	6
55	0.137733	0.990469	0.139058	7.191246	1.009622	7.260442	0.0008861	5.7586212	5
56	0.138021	0.990429	0.139354	7.175944	1.009663	7.245286	0.0008917	5.7436102	4
57	0.138309	0.990389	0.139651	7.160706	1.009704	7.230194	0.0008974	5.7286629	3
58	0.138597	0.990349	0.139948	7.145531	1.009745	7.215165	0.0009031	5.7137791	2
59	0.138885	0.990309	0.140244	7.130419	1.009786	7.200200	0.0009088	5.6989581	1
60	0.139173	0.990268	0.140541	7.115370	1.009828	7.185297	0.0009145	5.6841997	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	82°–83° Involute	Minutes

↑ 97° or 277° 82° or 262° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 8° or 188° Trigonometric and Involute Functions 171° or 351° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 8°–9°	Read Up	Minutes
0	0.139173	0.990268	0.140541	7.115370	1.009828	7.185297	0.0009145	5.6841997	60
1	0.139461	0.990228	0.140837	7.100383	1.009869	7.170456	0.0009203	5.6695035	59
2	0.139749	0.990187	0.141134	7.085457	1.009910	7.155676	0.0009260	5.6548691	58
3	0.140037	0.990146	0.141431	7.070593	1.009952	7.140959	0.0009318	5.6402961	57
4	0.140325	0.990105	0.141728	7.055790	1.009993	7.126302	0.0009377	5.6257841	56
5	0.140613	0.990065	0.142024	7.041048	1.010035	7.111706	0.0009435	5.6113327	55
6	0.140901	0.990024	0.142321	7.026366	1.010077	7.097170	0.0009494	5.5969416	54
7	0.141189	0.989983	0.142618	7.011744	1.010119	7.082694	0.0009553	5.5826104	53
8	0.141477	0.989942	0.142915	6.997182	1.010161	7.068278	0.0009612	5.5683387	52
9	0.141765	0.989900	0.143212	6.982678	1.010203	7.053920	0.0009672	5.5541261	51
10	0.142053	0.989859	0.143508	6.968234	1.010245	7.039622	0.0009732	5.5399724	50
11	0.142341	0.989818	0.143805	6.953847	1.010287	7.025382	0.0009792	5.5258771	49
12	0.142629	0.989776	0.144102	6.939519	1.010329	7.011200	0.0009852	5.5118399	48
13	0.142917	0.989735	0.144399	6.925249	1.010372	6.997076	0.0009913	5.4978604	47
14	0.143205	0.989693	0.144696	6.911036	1.010414	6.983009	0.0009973	5.4839383	46
15	0.143493	0.989651	0.144993	6.896880	1.010457	6.968999	0.0010034	5.4700733	45
16	0.143780	0.989610	0.145290	6.882781	1.010499	6.955046	0.0010096	5.4562649	44
17	0.144068	0.989568	0.145587	6.868738	1.010542	6.941150	0.0010157	5.4425129	43
18	0.144356	0.989526	0.145884	6.854751	1.010585	6.927309	0.0010219	5.4288168	42
19	0.144644	0.989484	0.146181	6.840820	1.010628	6.913524	0.0010281	5.4151765	41
20	0.144932	0.989442	0.146478	6.826944	1.010671	6.899794	0.0010343	5.4015914	40
21	0.145220	0.989399	0.146776	6.813123	1.010714	6.886119	0.0010406	5.3880614	39
22	0.145507	0.989357	0.147073	6.799357	1.010757	6.872499	0.0010469	5.3745861	38
23	0.145795	0.989315	0.147370	6.785645	1.010801	6.858934	0.0010532	5.3611651	37
24	0.146083	0.989272	0.147667	6.771987	1.010844	6.845422	0.0010595	5.3477981	36
25	0.146371	0.989230	0.147964	6.758383	1.010887	6.831964	0.0010659	5.3344848	35
26	0.146659	0.989187	0.148262	6.744832	1.010931	6.818560	0.0010722	5.3212249	34
27	0.146946	0.989144	0.148559	6.731334	1.010975	6.805208	0.0010786	5.3080181	33
28	0.147234	0.989102	0.148856	6.717889	1.011018	6.791909	0.0010851	5.2948640	32
29	0.147522	0.989059	0.149154	6.704497	1.011062	6.778663	0.0010915	5.2817624	31
30	0.147809	0.989016	0.149451	6.691156	1.011106	6.765469	0.0010980	5.2687129	30
31	0.148097	0.988973	0.149748	6.677868	1.011150	6.752327	0.0011045	5.2557152	29
32	0.148385	0.988930	0.150046	6.664631	1.011194	6.739236	0.0011111	5.2427691	28
33	0.148672	0.988886	0.150343	6.651445	1.011238	6.726196	0.0011176	5.2298742	27
34	0.148960	0.988843	0.150641	6.638310	1.011283	6.713208	0.0011242	5.2170302	26
35	0.149248	0.988800	0.150938	6.625226	1.011327	6.700270	0.0011308	5.2042369	25
36	0.149535	0.988756	0.151236	6.612192	1.011371	6.687382	0.0011375	5.1914939	24
37	0.149823	0.988713	0.151533	6.599208	1.011416	6.674545	0.0011441	5.1788009	23
38	0.150111	0.988669	0.151831	6.586274	1.011461	6.661757	0.0011508	5.1661577	22
39	0.150398	0.988626	0.152129	6.573389	1.011505	6.649018	0.0011575	5.1535639	21
40	0.150686	0.988582	0.152426	6.560554	1.011550	6.636329	0.0011643	5.1410193	20
41	0.150973	0.988538	0.152724	6.547767	1.011595	6.623689	0.0011711	5.1285236	19
42	0.151261	0.988494	0.153022	6.535029	1.011640	6.611097	0.0011779	5.1160766	18
43	0.151548	0.988450	0.153319	6.522340	1.011685	6.598554	0.0011847	5.1036779	17
44	0.151836	0.988406	0.153617	6.509698	1.011730	6.586059	0.0011915	5.0913272	16
45	0.152123	0.988362	0.153915	6.497104	1.011776	6.573611	0.0011984	5.0790243	15
46	0.152411	0.988317	0.154213	6.484558	1.011821	6.561211	0.0012053	5.0667689	14
47	0.152698	0.988273	0.154510	6.472059	1.011866	6.548859	0.0012122	5.0545608	13
48	0.152986	0.988228	0.154808	6.459607	1.011912	6.536553	0.0012192	5.0423997	12
49	0.153273	0.988184	0.155106	6.447202	1.011957	6.524294	0.0012262	5.0302852	11
50	0.153561	0.988139	0.155404	6.434843	1.012003	6.512081	0.0012332	5.0182172	10
51	0.153848	0.988094	0.155702	6.422530	1.012049	6.499915	0.0012402	5.0061954	9
52	0.154136	0.988050	0.156000	6.410263	1.012095	6.487794	0.0012473	4.9942195	8
53	0.154423	0.988005	0.156298	6.398042	1.012141	6.475720	0.0012544	4.9822893	7
54	0.154710	0.987960	0.156596	6.385866	1.012187	6.463690	0.0012615	4.9704044	6
55	0.154998	0.987915	0.156894	6.373736	1.012233	6.451706	0.0012687	4.9585647	5
56	0.155285	0.987870	0.157192	6.361650	1.012279	6.439767	0.0012758	4.9467700	4
57	0.155572	0.987824	0.157490	6.349609	1.012326	6.427872	0.0012830	4.9350198	3
58	0.155860	0.987779	0.157788	6.337613	1.012372	6.416022	0.0012903	4.9233141	2
59	0.156147	0.987734	0.158086	6.325660	1.012419	6.404215	0.0012975	4.9116525	1
60	0.156434	0.987688	0.158384	6.313752	1.012465	6.392453	0.0013048	4.9000348	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	81°–82° Involute	Minutes

↑ 98° or 278° 81° or 261° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 9° or 189° Trigonometric and Involute Functions 170° or 350° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 9°–10°	Read Up	Minutes
0	0.156434	0.987688	0.158384	6.313752	1.012465	6.392453	0.0013048	4.9000348	60
1	0.156722	0.987643	0.158683	6.301887	1.012512	6.380735	0.0013121	4.8884608	59
2	0.157009	0.987597	0.158981	6.290065	1.012559	6.369060	0.0013195	4.8769302	58
3	0.157296	0.987551	0.159279	6.278287	1.012605	6.357428	0.0013268	4.8654428	57
4	0.157584	0.987506	0.159577	6.266551	1.012652	6.345839	0.0013342	4.8539983	56
5	0.157871	0.987460	0.159876	6.254859	1.012699	6.334292	0.0013416	4.8425965	55
6	0.158158	0.987414	0.160174	6.243209	1.012747	6.322788	0.0013491	4.8312372	54
7	0.158445	0.987368	0.160472	6.231601	1.012794	6.311327	0.0013566	4.8199202	53
8	0.158732	0.987322	0.160771	6.220035	1.012841	6.299907	0.0013641	4.8086451	52
9	0.159020	0.987275	0.161069	6.208511	1.012889	6.288530	0.0013716	4.7974119	51
10	0.159307	0.987229	0.161368	6.197028	1.012936	6.277193	0.0013792	4.7862201	50
11	0.159594	0.987183	0.161666	6.185587	1.012984	6.265898	0.0013868	4.7750697	49
12	0.159881	0.987136	0.161965	6.174186	1.013031	6.254645	0.0013944	4.7639604	48
13	0.160168	0.987090	0.162263	6.162827	1.013079	6.243432	0.0014020	4.7528920	47
14	0.160455	0.987043	0.162562	6.151508	1.013127	6.232259	0.0014097	4.7418642	46
15	0.160743	0.986996	0.162860	6.140230	1.013175	6.221128	0.0014174	4.7308769	45
16	0.161030	0.986950	0.163159	6.128992	1.013223	6.210036	0.0014251	4.7199298	44
17	0.161317	0.986903	0.163458	6.117794	1.013271	6.198984	0.0014329	4.7090227	43
18	0.161604	0.986856	0.163756	6.106636	1.013319	6.187972	0.0014407	4.6981553	42
19	0.161891	0.986809	0.164055	6.095517	1.013368	6.177000	0.0014485	4.6873276	41
20	0.162178	0.986762	0.164354	6.084438	1.013416	6.166067	0.0014563	4.6765392	40
21	0.162465	0.986714	0.164652	6.073398	1.013465	6.155174	0.0014642	4.6657899	39
22	0.162752	0.986667	0.164951	6.062397	1.013513	6.144319	0.0014721	4.6550796	38
23	0.163039	0.986620	0.165250	6.051434	1.013562	6.133503	0.0014800	4.6444080	37
24	0.163326	0.986572	0.165549	6.040510	1.013611	6.122725	0.0014880	4.6337750	36
25	0.163613	0.986525	0.165848	6.029625	1.013659	6.111986	0.0014960	4.6231802	35
26	0.163900	0.986477	0.166147	6.018777	1.013708	6.101285	0.0015040	4.6126236	34
27	0.164187	0.986429	0.166446	6.007968	1.013757	6.090622	0.0015120	4.6021049	33
28	0.164474	0.986381	0.166745	5.997196	1.013807	6.079996	0.0015201	4.5916239	32
29	0.164761	0.986334	0.167044	5.986461	1.013856	6.069409	0.0015282	4.5811805	31
30	0.165048	0.986286	0.167343	5.975764	1.013905	6.058858	0.0015363	4.5707743	30
31	0.165334	0.986238	0.167642	5.965104	1.013954	6.048345	0.0015445	4.5604053	29
32	0.165621	0.986189	0.167941	5.954481	1.014004	6.037868	0.0015527	4.5500732	28
33	0.165908	0.986141	0.168240	5.943895	1.014054	6.027428	0.0015609	4.5397779	27
34	0.166195	0.986093	0.168539	5.933346	1.014103	6.017025	0.0015691	4.5295190	26
35	0.166482	0.986045	0.168838	5.922832	1.014153	6.006658	0.0015774	4.5192966	25
36	0.166769	0.985996	0.169137	5.912355	1.014203	5.996327	0.0015857	4.5091103	24
37	0.167056	0.985947	0.169437	5.901914	1.014253	5.986033	0.0015941	4.4989600	23
38	0.167342	0.985899	0.169736	5.891508	1.014303	5.975774	0.0016024	4.4888455	22
39	0.167629	0.985850	0.170035	5.881139	1.014353	5.965550	0.0016108	4.4787665	21
40	0.167916	0.985801	0.170334	5.870804	1.014403	5.955362	0.0016193	4.4687230	20
41	0.168203	0.985752	0.170634	5.860505	1.014453	5.945210	0.0016277	4.4587148	19
42	0.168489	0.985703	0.170933	5.850241	1.014504	5.935092	0.0016362	4.4487416	18
43	0.168776	0.985654	0.171233	5.840012	1.014554	5.925009	0.0016447	4.4388032	17
44	0.169063	0.985605	0.171532	5.829817	1.014605	5.914961	0.0016533	4.4288996	16
45	0.169350	0.985556	0.171831	5.819657	1.014656	5.904948	0.0016618	4.4190305	15
46	0.169636	0.985507	0.172131	5.809532	1.014706	5.894969	0.0016704	4.4091957	14
47	0.169923	0.985457	0.172430	5.799440	1.014757	5.885024	0.0016791	4.3993951	13
48	0.170209	0.985408	0.172730	5.789383	1.014808	5.875113	0.0016877	4.3896285	12
49	0.170496	0.985358	0.173030	5.779359	1.014859	5.865236	0.0016964	4.3798957	11
50	0.170783	0.985309	0.173329	5.769369	1.014910	5.855392	0.0017051	4.3701965	10
51	0.171069	0.985259	0.173629	5.759412	1.014962	5.845582	0.0017139	4.3605308	9
52	0.171356	0.985209	0.173929	5.749489	1.015013	5.835805	0.0017227	4.3508984	8
53	0.171643	0.985159	0.174228	5.739599	1.015064	5.826062	0.0017315	4.3412992	7
54	0.171929	0.985109	0.174528	5.729742	1.015116	5.816351	0.0017403	4.3317329	6
55	0.172216	0.985059	0.174828	5.719917	1.015167	5.806673	0.0017492	4.3221994	5
56	0.172502	0.985009	0.175127	5.710126	1.015219	5.797028	0.0017581	4.3126986	4
57	0.172789	0.984959	0.175427	5.700366	1.015271	5.787415	0.0017671	4.3032303	3
58	0.173075	0.984909	0.175727	5.690639	1.015323	5.777835	0.0017760	4.2937942	2
59	0.173362	0.984858	0.176027	5.680945	1.015375	5.768287	0.0017850	4.2843903	1
60	0.173648	0.984808	0.176327	5.671282	1.015427	5.758770	0.0017941	4.2750184	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	80°–81° Involute	Minutes

↑ 99° or 279° 80° or 260° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 10° or 190° Trigonometric and Involute Functions 169° or 349° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 10°–11°	Read Up	Minutes
0	0.173648	0.984808	0.176327	5.671282	1.015427	5.758770	0.0017941	4.2750184	60
1	0.173935	0.984757	0.176627	5.661651	1.015479	5.749286	0.0018031	4.2656783	59
2	0.174221	0.984707	0.176927	5.652052	1.015531	5.739833	0.0018122	4.2563699	58
3	0.174508	0.984656	0.177227	5.642484	1.015583	5.730412	0.0018213	4.2470930	57
4	0.174794	0.984605	0.177527	5.632947	1.015636	5.721022	0.0018305	4.2378475	56
5	0.175080	0.984554	0.177827	5.623442	1.015688	5.711664	0.0018397	4.2286332	55
6	0.175367	0.984503	0.178127	5.613968	1.015741	5.702336	0.0018489	4.2194499	54
7	0.175653	0.984452	0.178427	5.604525	1.015793	5.693039	0.0018581	4.2102975	53
8	0.175939	0.984401	0.178727	5.595112	1.015846	5.683773	0.0018674	4.2011758	52
9	0.176226	0.984350	0.179028	5.585730	1.015899	5.674538	0.0018767	4.1920848	51
10	0.176512	0.984298	0.179328	5.576379	1.015952	5.665333	0.0018860	4.1830241	50
11	0.176798	0.984247	0.179628	5.567057	1.016005	5.656158	0.0018954	4.1739938	49
12	0.177085	0.984196	0.179928	5.557766	1.016058	5.647014	0.0019048	4.1649936	48
13	0.177371	0.984144	0.180229	5.548505	1.016111	5.637899	0.0019142	4.1560234	47
14	0.177657	0.984092	0.180529	5.539274	1.016165	5.628815	0.0019237	4.1470830	46
15	0.177944	0.984041	0.180829	5.530072	1.016218	5.619760	0.0019332	4.1381724	45
16	0.178230	0.983989	0.181130	5.520900	1.016272	5.610735	0.0019427	4.1292913	44
17	0.178516	0.983937	0.181430	5.511758	1.016325	5.601739	0.0019523	4.1204396	43
18	0.178802	0.983885	0.181731	5.502645	1.016379	5.592772	0.0019619	4.1116172	42
19	0.179088	0.983833	0.182031	5.493560	1.016433	5.583834	0.0019715	4.1028239	41
20	0.179375	0.983781	0.182332	5.484505	1.016487	5.574926	0.0019812	4.0940596	40
21	0.179661	0.983729	0.182632	5.475479	1.016541	5.566046	0.0019909	4.0853241	39
22	0.179947	0.983676	0.182933	5.466481	1.016595	5.557195	0.0020006	4.0766173	38
23	0.180233	0.983624	0.183234	5.457512	1.016649	5.548373	0.0020103	4.0679392	37
24	0.180519	0.983571	0.183534	5.448572	1.016703	5.539579	0.0020201	4.0592894	36
25	0.180805	0.983519	0.183835	5.439659	1.016757	5.530813	0.0020299	4.0506680	35
26	0.181091	0.983466	0.184136	5.430775	1.016812	5.522075	0.0020398	4.0420747	34
27	0.181377	0.983414	0.184437	5.421919	1.016866	5.513366	0.0020496	4.0335094	33
28	0.181663	0.983361	0.184737	5.413091	1.016921	5.504684	0.0020596	4.0249720	32
29	0.181950	0.983308	0.185038	5.404290	1.016975	5.496030	0.0020695	4.0164624	31
30	0.182236	0.983255	0.185339	5.395517	1.017030	5.487404	0.0020795	4.0079804	30
31	0.182522	0.983202	0.185640	5.386772	1.017085	5.478806	0.0020895	3.9995259	29
32	0.182808	0.983149	0.185941	5.378054	1.017140	5.470234	0.0020995	3.9910988	28
33	0.183094	0.983096	0.186242	5.369363	1.017195	5.461690	0.0021096	3.9826989	27
34	0.183379	0.983042	0.186543	5.360699	1.017250	5.453173	0.0021197	3.9743261	26
35	0.183665	0.982989	0.186844	5.352063	1.017306	5.444683	0.0021298	3.9659803	25
36	0.183951	0.982935	0.187145	5.343453	1.017361	5.436220	0.0021400	3.9576613	24
37	0.184237	0.982882	0.187446	5.334870	1.017416	5.427784	0.0021502	3.9493691	23
38	0.184523	0.982828	0.187747	5.326313	1.017472	5.419374	0.0021605	3.9411034	22
39	0.184809	0.982774	0.188048	5.317783	1.017527	5.410990	0.0021707	3.9328643	21
40	0.185095	0.982721	0.188349	5.309279	1.017583	5.402633	0.0021810	3.9246514	20
41	0.185381	0.982667	0.188651	5.300802	1.017639	5.394303	0.0021914	3.9164648	19
42	0.185667	0.982613	0.188952	5.292350	1.017695	5.385998	0.0022017	3.9083044	18
43	0.185952	0.982559	0.189253	5.283925	1.017751	5.377719	0.0022121	3.9001698	17
44	0.186238	0.982505	0.189555	5.275526	1.017807	5.369466	0.0022226	3.8920612	16
45	0.186524	0.982450	0.189856	5.267152	1.017863	5.361239	0.0022330	3.8839783	15
46	0.186810	0.982396	0.190157	5.258804	1.017919	5.353038	0.0022435	3.8759210	14
47	0.187096	0.982342	0.190459	5.250481	1.017976	5.344862	0.0022541	3.8678892	13
48	0.187381	0.982287	0.190760	5.242184	1.018032	5.336711	0.0022646	3.8598828	12
49	0.187667	0.982233	0.191062	5.233912	1.018089	5.328586	0.0022752	3.8519017	11
50	0.187953	0.982178	0.191363	5.225665	1.018145	5.320486	0.0022859	3.8439457	10
51	0.188238	0.982123	0.191665	5.217443	1.018202	5.312411	0.0022965	3.8360147	9
52	0.188524	0.982069	0.191966	5.209246	1.018259	5.304361	0.0023073	3.8281087	8
53	0.188810	0.982014	0.192268	5.201074	1.018316	5.296335	0.0023180	3.8202275	7
54	0.189095	0.981959	0.192570	5.192926	1.018373	5.288335	0.0023288	3.8123709	6
55	0.189381	0.981904	0.192871	5.184804	1.018430	5.280359	0.0023396	3.8045390	5
56	0.189667	0.981849	0.193173	5.176705	1.018487	5.272407	0.0023504	3.7967315	4
57	0.189952	0.981793	0.193475	5.168631	1.018544	5.264480	0.0023613	3.7889483	3
58	0.190238	0.981738	0.193777	5.160581	1.018602	5.256577	0.0023722	3.7811894	2
59	0.190523	0.981683	0.194078	5.152556	1.018659	5.248698	0.0023831	3.7734547	1
60	0.190809	0.981627	0.194380	5.144554	1.018717	5.240843	0.0023941	3.7657439	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	79°–80° Involute	Minutes

↑ 100° or 280° 79° or 259° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 11° or 191° Trigonometric and Involute Functions 168° or 348° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 11°–12°	Read Up	Minutes
0	0.190809	0.981627	0.194380	5.144554	1.018717	5.240843	0.0023941	3.7657439	60
1	0.191095	0.981572	0.194682	5.136576	1.018774	5.233012	0.0024051	3.7580571	59
2	0.191380	0.981516	0.194984	5.128622	1.018832	5.225205	0.0024161	3.7503940	58
3	0.191666	0.981460	0.195286	5.120692	1.018890	5.217422	0.0024272	3.7427547	57
4	0.191951	0.981405	0.195588	5.112786	1.018948	5.209662	0.0024383	3.7351390	56
5	0.192237	0.981349	0.195890	5.104902	1.019006	5.201925	0.0024495	3.7275467	55
6	0.192522	0.981293	0.196192	5.097043	1.019064	5.194212	0.0024607	3.7199778	54
7	0.192807	0.981237	0.196494	5.089206	1.019122	5.186523	0.0024719	3.7124322	53
8	0.193093	0.981180	0.196796	5.081393	1.019180	5.178856	0.0024831	3.7049098	52
9	0.193378	0.981124	0.197099	5.073602	1.019239	5.171213	0.0024944	3.6974104	51
10	0.193664	0.981068	0.197401	5.065835	1.019297	5.163592	0.0025057	3.6899340	50
11	0.193949	0.981012	0.197703	5.058091	1.019356	5.155995	0.0025171	3.6824804	49
12	0.194234	0.980955	0.198005	5.050369	1.019415	5.148420	0.0025285	3.6750496	48
13	0.194520	0.980899	0.198308	5.042670	1.019473	5.140868	0.0025399	3.6676414	47
14	0.194805	0.980842	0.198610	5.034994	1.019532	5.133338	0.0025513	3.6602558	46
15	0.195090	0.980785	0.198912	5.027339	1.019591	5.125831	0.0025628	3.6528927	45
16	0.195376	0.980728	0.199215	5.019708	1.019650	5.118346	0.0025744	3.6455519	44
17	0.195661	0.980672	0.199517	5.012098	1.019709	5.110884	0.0025859	3.6382334	43
18	0.195946	0.980615	0.199820	5.004511	1.019769	5.103443	0.0025975	3.6309370	42
19	0.196231	0.980558	0.200122	4.996946	1.019828	5.096025	0.0026091	3.6236627	41
20	0.196517	0.980500	0.200425	4.989403	1.019887	5.088628	0.0026208	3.6164103	40
21	0.196802	0.980443	0.200727	4.981881	1.019947	5.081254	0.0026325	3.6091798	39
22	0.197087	0.980386	0.201030	4.974382	1.020006	5.073901	0.0026443	3.6019711	38
23	0.197372	0.980329	0.201333	4.966904	1.020066	5.066570	0.0026560	3.5947840	37
24	0.197657	0.980271	0.201635	4.959447	1.020126	5.059261	0.0026678	3.5876186	36
25	0.197942	0.980214	0.201938	4.952012	1.020186	5.051973	0.0026797	3.5804746	35
26	0.198228	0.980156	0.202241	4.944599	1.020246	5.044706	0.0026916	3.5733520	34
27	0.198513	0.980098	0.202544	4.937207	1.020306	5.037461	0.0027035	3.5662507	33
28	0.198798	0.980041	0.202847	4.929836	1.020366	5.030237	0.0027154	3.5591705	32
29	0.199083	0.979983	0.203149	4.922486	1.020426	5.023034	0.0027274	3.5521115	31
30	0.199368	0.979925	0.203452	4.915157	1.020487	5.015852	0.0027394	3.5450736	30
31	0.199653	0.979867	0.203755	4.907849	1.020547	5.008691	0.0027515	3.5380565	29
32	0.199938	0.979809	0.204058	4.900562	1.020608	5.001551	0.0027636	3.5310603	28
33	0.200223	0.979750	0.204361	4.893296	1.020668	4.994431	0.0027757	3.5240848	27
34	0.200508	0.979692	0.204664	4.886050	1.020729	4.987332	0.0027879	3.5171300	26
35	0.200793	0.979634	0.204967	4.878825	1.020790	4.980254	0.0028001	3.5101958	25
36	0.201078	0.979575	0.205271	4.871620	1.020851	4.973196	0.0028123	3.5032820	24
37	0.201363	0.979517	0.205574	4.864436	1.020912	4.966159	0.0028246	3.4963886	23
38	0.201648	0.979458	0.205877	4.857272	1.020973	4.959142	0.0028369	3.4895156	22
39	0.201933	0.979399	0.206180	4.850128	1.021034	4.952145	0.0028493	3.4826627	21
40	0.202218	0.979341	0.206483	4.843005	1.021095	4.945169	0.0028616	3.4758300	20
41	0.202502	0.979282	0.206787	4.835901	1.021157	4.938212	0.0028741	3.4690173	19
42	0.202787	0.979223	0.207090	4.828817	1.021218	4.931275	0.0028865	3.4622245	18
43	0.203072	0.979164	0.207393	4.821754	1.021280	4.924359	0.0028990	3.4554517	17
44	0.203357	0.979105	0.207697	4.814710	1.021341	4.917462	0.0029115	3.4486986	16
45	0.203642	0.979045	0.208000	4.807685	1.021403	4.910584	0.0029241	3.4419653	15
46	0.203927	0.978986	0.208304	4.800681	1.021465	4.903727	0.0029367	3.4352515	14
47	0.204211	0.978927	0.208607	4.793696	1.021527	4.896889	0.0029494	3.4285573	13
48	0.204496	0.978867	0.208911	4.786730	1.021589	4.890070	0.0029620	3.4218825	12
49	0.204781	0.978808	0.209214	4.779784	1.021651	4.883271	0.0029747	3.4152272	11
50	0.205065	0.978748	0.209518	4.772857	1.021713	4.876491	0.0029875	3.4085911	10
51	0.205350	0.978689	0.209822	4.765949	1.021776	4.869730	0.0030003	3.4019742	9
52	0.205635	0.978629	0.210126	4.759060	1.021838	4.862988	0.0030131	3.3953764	8
53	0.205920	0.978569	0.210429	4.752191	1.021900	4.856266	0.0030260	3.3887977	7
54	0.206204	0.978509	0.210733	4.745340	1.021963	4.849562	0.0030389	3.3822379	6
55	0.206489	0.978449	0.211037	4.738508	1.022026	4.842877	0.0030518	3.3756971	5
56	0.206773	0.978389	0.211341	4.731695	1.022089	4.836211	0.0030648	3.3691750	4
57	0.207058	0.978329	0.211645	4.724901	1.022151	4.829564	0.0030778	3.3626717	3
58	0.207343	0.978268	0.211949	4.718126	1.022214	4.822936	0.0030908	3.3561870	2
59	0.207627	0.978208	0.212253	4.711369	1.022277	4.816326	0.0031039	3.3497209	1
60	0.207912	0.978148	0.212557	4.704630	1.022341	4.809734	0.0031171	3.3432733	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	78°–79° Involute	Minutes

↑ 101° or 281° 78° or 258° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 12° or 192° Trigonometric and Involute Functions 167° or 347° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 12°–13°	Read Up	Minutes
0	0.207912	0.978148	0.212557	4.704630	1.022341	4.809734	0.0031171	3.3432733	60
1	0.208196	0.978087	0.212861	4.697910	1.022404	4.803161	0.0031302	3.3368441	59
2	0.208481	0.978026	0.213165	4.691208	1.022467	4.796607	0.0031434	3.3304333	58
3	0.208765	0.977966	0.213469	4.684525	1.022531	4.790070	0.0031566	3.3240407	57
4	0.209050	0.977905	0.213773	4.677860	1.022594	4.783552	0.0031699	3.3176663	56
5	0.209334	0.977844	0.214077	4.671212	1.022658	4.777052	0.0031832	3.3113100	55
6	0.209619	0.977783	0.214381	4.664583	1.022722	4.770570	0.0031966	3.3049718	54
7	0.209903	0.977722	0.214686	4.657972	1.022785	4.764106	0.0032100	3.2986515	53
8	0.210187	0.977661	0.214990	4.651379	1.022849	4.757660	0.0032234	3.2923491	52
9	0.210472	0.977600	0.215294	4.644803	1.022913	4.751231	0.0032369	3.2860645	51
10	0.210756	0.977539	0.215599	4.638246	1.022977	4.744821	0.0032504	3.2797977	50
11	0.211040	0.977477	0.215903	4.631706	1.023042	4.738428	0.0032639	3.2735486	49
12	0.211325	0.977416	0.216208	4.625183	1.023106	4.732052	0.0032775	3.2673170	48
13	0.211609	0.977354	0.216512	4.618678	1.023170	4.725695	0.0032911	3.2611030	47
14	0.211893	0.977293	0.216817	4.612191	1.023235	4.719354	0.0033048	3.2549064	46
15	0.212178	0.977231	0.217121	4.605721	1.023299	4.713031	0.0033185	3.2487273	45
16	0.212462	0.977169	0.217426	4.599268	1.023364	4.706726	0.0033322	3.2425654	44
17	0.212746	0.977108	0.217731	4.592832	1.023429	4.700437	0.0033460	3.2364208	43
18	0.213030	0.977046	0.218035	4.586414	1.023494	4.694166	0.0033598	3.2302933	42
19	0.213315	0.976984	0.218340	4.580013	1.023559	4.687912	0.0033736	3.2241830	41
20	0.213599	0.976921	0.218645	4.573629	1.023624	4.681675	0.0033875	3.2180896	40
21	0.213883	0.976859	0.218950	4.567261	1.023689	4.675455	0.0034014	3.2120133	39
22	0.214167	0.976797	0.219254	4.560911	1.023754	4.669252	0.0034154	3.2059538	38
23	0.214451	0.976735	0.219559	4.554578	1.023819	4.663065	0.0034294	3.1999112	37
24	0.214735	0.976672	0.219864	4.548261	1.023885	4.656896	0.0034434	3.1938853	36
25	0.215019	0.976610	0.220169	4.541961	1.023950	4.650743	0.0034575	3.1878762	35
26	0.215303	0.976547	0.220474	4.535677	1.024016	4.644606	0.0034716	3.1818836	34
27	0.215588	0.976485	0.220779	4.529410	1.024082	4.638487	0.0034858	3.1759076	33
28	0.215872	0.976422	0.221084	4.523160	1.024148	4.632384	0.0035000	3.1699481	32
29	0.216156	0.976359	0.221389	4.516926	1.024214	4.626297	0.0035142	3.1640050	31
30	0.216440	0.976296	0.221695	4.510709	1.024280	4.620226	0.0035285	3.1580783	30
31	0.216724	0.976233	0.222000	4.504507	1.024346	4.614172	0.0035428	3.1521679	29
32	0.217008	0.976170	0.222305	4.498322	1.024412	4.608134	0.0035572	3.1462737	28
33	0.217292	0.976107	0.222610	4.492153	1.024478	4.602113	0.0035716	3.1403957	27
34	0.217575	0.976044	0.222916	4.486000	1.024544	4.596107	0.0035860	3.1345338	26
35	0.217859	0.975980	0.223221	4.479864	1.024611	4.590117	0.0036005	3.1286879	25
36	0.218143	0.975917	0.223526	4.473743	1.024678	4.584144	0.0036150	3.1228580	24
37	0.218427	0.975853	0.223832	4.467638	1.024744	4.578186	0.0036296	3.1170440	23
38	0.218711	0.975790	0.224137	4.461549	1.024811	4.572244	0.0036441	3.1112458	22
39	0.218995	0.975726	0.224443	4.455476	1.024878	4.566318	0.0036588	3.1054635	21
40	0.219279	0.975662	0.224748	4.449418	1.024945	4.560408	0.0036735	3.0996968	20
41	0.219562	0.975598	0.225054	4.443376	1.025012	4.554513	0.0036882	3.0939458	19
42	0.219846	0.975535	0.225360	4.437350	1.025079	4.548634	0.0037029	3.0882104	18
43	0.220130	0.975471	0.225665	4.431339	1.025146	4.542771	0.0037177	3.0824906	17
44	0.220414	0.975406	0.225971	4.425344	1.025214	4.536923	0.0037325	3.0767862	16
45	0.220697	0.975342	0.226277	4.419364	1.025281	4.531090	0.0037474	3.0710972	15
46	0.220981	0.975278	0.226583	4.413400	1.025349	4.525273	0.0037623	3.0654236	14
47	0.221265	0.975214	0.226889	4.407450	1.025416	4.519471	0.0037773	3.0597653	13
48	0.221548	0.975149	0.227194	4.401516	1.025484	4.513684	0.0037923	3.0541223	12
49	0.221832	0.975085	0.227500	4.395598	1.025552	4.507913	0.0038073	3.0484944	11
50	0.222116	0.975020	0.227806	4.389694	1.025620	4.502157	0.0038224	3.0428816	10
51	0.222399	0.974956	0.228112	4.383805	1.025688	4.496415	0.0038375	3.0372838	9
52	0.222683	0.974891	0.228418	4.377932	1.025756	4.490689	0.0038527	3.0317011	8
53	0.222967	0.974826	0.228724	4.372073	1.025824	4.484977	0.0038679	3.0261333	7
54	0.223250	0.974761	0.229031	4.366229	1.025892	4.479281	0.0038831	3.0205804	6
55	0.223534	0.974696	0.229337	4.360400	1.025961	4.473599	0.0038984	3.0150424	5
56	0.223817	0.974631	0.229643	4.354586	1.026029	4.467932	0.0039137	3.0095190	4
57	0.224101	0.974566	0.229949	4.348787	1.026098	4.462280	0.0039291	3.0040104	3
58	0.224384	0.974501	0.230255	4.343002	1.026166	4.456643	0.0039445	2.9985165	2
59	0.224668	0.974435	0.230562	4.337232	1.026235	4.451020	0.0039599	2.9930372	1
60	0.224951	0.974370	0.230868	4.331476	1.026304	4.445411	0.0039754	2.9875724	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	77°–78° Involute	Minutes

↑ 102° or 282° 77° or 257° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 13° or 193° Trigonometric and Involute Functions 166° or 346° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 13°–14°	Read Up	Minutes
0	0.224951	0.974370	0.230868	4.331476	1.026304	4.445411	0.0039754	2.9875724	60
1	0.225234	0.974305	0.231175	4.325735	1.026373	4.439818	0.0039909	2.9821220	59
2	0.225518	0.974239	0.231481	4.320008	1.026442	4.434238	0.0040065	2.9766861	58
3	0.225801	0.974173	0.231788	4.314295	1.026511	4.428673	0.0040221	2.9712646	57
4	0.226085	0.974108	0.232094	4.308597	1.026581	4.423122	0.0040377	2.9658574	56
5	0.226368	0.974042	0.232401	4.302914	1.026650	4.417586	0.0040534	2.9604645	55
6	0.226651	0.973976	0.232707	4.297244	1.026719	4.412064	0.0040692	2.9550858	54
7	0.226935	0.973910	0.233014	4.291589	1.026789	4.406556	0.0040849	2.9497212	53
8	0.227218	0.973844	0.233321	4.285947	1.026859	4.401062	0.0041007	2.9443708	52
9	0.227501	0.973778	0.233627	4.280320	1.026928	4.395582	0.0041166	2.9390344	51
10	0.227784	0.973712	0.233934	4.274707	1.026998	4.390116	0.0041325	2.9337119	50
11	0.228068	0.973645	0.234241	4.269107	1.027068	4.384664	0.0041484	2.9284035	49
12	0.228351	0.973579	0.234548	4.263522	1.027138	4.379226	0.0041644	2.9231089	48
13	0.228634	0.973512	0.234855	4.257950	1.027208	4.373801	0.0041804	2.9178281	47
14	0.228917	0.973446	0.235162	4.252392	1.027278	4.368391	0.0041965	2.9125612	46
15	0.229200	0.973379	0.235469	4.246848	1.027349	4.362994	0.0042126	2.9073080	45
16	0.229484	0.973313	0.235776	4.241318	1.027419	4.357611	0.0042288	2.9020684	44
17	0.229767	0.973246	0.236083	4.235801	1.027490	4.352242	0.0042450	2.8968425	43
18	0.230050	0.973179	0.236390	4.230298	1.027560	4.346886	0.0042612	2.8916302	42
19	0.230333	0.973112	0.236697	4.224808	1.027631	4.341544	0.0042775	2.8864313	41
20	0.230616	0.973045	0.237004	4.219332	1.027702	4.336215	0.0042938	2.8812460	40
21	0.230899	0.972978	0.237312	4.213869	1.027773	4.330900	0.0043101	2.8760741	39
22	0.231182	0.972911	0.237619	4.208420	1.027844	4.325598	0.0043266	2.8709156	38
23	0.231465	0.972843	0.237926	4.202983	1.027915	4.320309	0.0043430	2.8657704	37
24	0.231748	0.972776	0.238234	4.197561	1.027986	4.315034	0.0043595	2.8606384	36
25	0.232031	0.972708	0.238541	4.192151	1.028057	4.309772	0.0043760	2.8555197	35
26	0.232314	0.972641	0.238848	4.186755	1.028129	4.304523	0.0043926	2.8504142	34
27	0.232597	0.972573	0.239156	4.181371	1.028200	4.299287	0.0044092	2.8453218	33
28	0.232880	0.972506	0.239464	4.176001	1.028272	4.294064	0.0044259	2.8402425	32
29	0.233163	0.972438	0.239771	4.170644	1.028343	4.288854	0.0044426	2.8351762	31
30	0.233445	0.972370	0.240079	4.165300	1.028415	4.283658	0.0044593	2.8301229	30
31	0.233728	0.972302	0.240386	4.159969	1.028487	4.278474	0.0044761	2.8250825	29
32	0.234011	0.972234	0.240694	4.154650	1.028559	4.273303	0.0044929	2.8200550	28
33	0.234294	0.972166	0.241002	4.149345	1.028631	4.268145	0.0045098	2.8150404	27
34	0.234577	0.972098	0.241310	4.144052	1.028703	4.263000	0.0045267	2.8100385	26
35	0.234859	0.972029	0.241618	4.138772	1.028776	4.257867	0.0045437	2.8050494	25
36	0.235142	0.971961	0.241925	4.133505	1.028848	4.252747	0.0045607	2.8000730	24
37	0.235425	0.971893	0.242233	4.128250	1.028920	4.247640	0.0045777	2.7951093	23
38	0.235708	0.971824	0.242541	4.123008	1.028993	4.242546	0.0045948	2.7901581	22
39	0.235990	0.971755	0.242849	4.117778	1.029066	4.237464	0.0046120	2.7852195	21
40	0.236273	0.971687	0.243157	4.112561	1.029138	4.232394	0.0046291	2.7802934	20
41	0.236556	0.971618	0.243466	4.107357	1.029211	4.227337	0.0046464	2.7753798	19
42	0.236838	0.971549	0.243774	4.102165	1.029284	4.222293	0.0046636	2.7704786	18
43	0.237121	0.971480	0.244082	4.096985	1.029357	4.217261	0.0046809	2.7655898	17
44	0.237403	0.971411	0.244390	4.091818	1.029430	4.212241	0.0046983	2.7607133	16
45	0.237686	0.971342	0.244698	4.086663	1.029503	4.207233	0.0047157	2.7558491	15
46	0.237968	0.971273	0.245007	4.081520	1.029577	4.202238	0.0047331	2.7509972	14
47	0.238251	0.971204	0.245315	4.076389	1.029650	4.197255	0.0047506	2.7461574	13
48	0.238533	0.971134	0.245624	4.071271	1.029724	4.192284	0.0047681	2.7413298	12
49	0.238816	0.971065	0.245932	4.066164	1.029797	4.187325	0.0047857	2.7365143	11
50	0.239098	0.970995	0.246241	4.061070	1.029871	4.182378	0.0048033	2.7317109	10
51	0.239381	0.970926	0.246549	4.055988	1.029945	4.177444	0.0048210	2.7269195	9
52	0.239663	0.970856	0.246858	4.050917	1.030019	4.172521	0.0048387	2.7221401	8
53	0.239946	0.970786	0.247166	4.045859	1.030093	4.167610	0.0048564	2.7173726	7
54	0.240228	0.970716	0.247475	4.040813	1.030167	4.162711	0.0048742	2.7126170	6
55	0.240510	0.970647	0.247784	4.035778	1.030241	4.157824	0.0048921	2.7078732	5
56	0.240793	0.970577	0.248092	4.030755	1.030315	4.152949	0.0049099	2.7031413	4
57	0.241075	0.970506	0.248401	4.025744	1.030390	4.148086	0.0049279	2.6984211	3
58	0.241357	0.970436	0.248710	4.020745	1.030464	4.143234	0.0049458	2.6937126	2
59	0.241640	0.970366	0.249019	4.015757	1.030539	4.138394	0.0049638	2.6890158	1
60	0.241922	0.970296	0.249328	4.010781	1.030614	4.133565	0.0049819	2.6843307	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	76°–77° Involute	Minutes

↑ 103° or 283° 76° or 256° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 14° or 194° Trigonometric and Involute Functions 165° or 345° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 14°–15°	Read Up	Minutes
0	0.241922	0.970296	0.249328	4.010781	1.030614	4.133565	0.0049819	2.6843307	60
1	0.242204	0.970225	0.249637	4.005817	1.030688	4.128749	0.0050000	2.6796572	59
2	0.242486	0.970155	0.249946	4.000864	1.030763	4.123943	0.0050182	2.6749952	58
3	0.242769	0.970084	0.250255	3.995922	1.030838	4.119150	0.0050364	2.6703447	57
4	0.243051	0.970014	0.250564	3.990992	1.030913	4.114368	0.0050546	2.6657057	56
5	0.243333	0.969943	0.250873	3.986074	1.030989	4.109597	0.0050729	2.6610781	55
6	0.243615	0.969872	0.251183	3.981167	1.031064	4.104837	0.0050912	2.6564620	54
7	0.243897	0.969801	0.251492	3.976271	1.031139	4.100089	0.0051096	2.6518572	53
8	0.244179	0.969730	0.251801	3.971387	1.031215	4.095353	0.0051280	2.6472636	52
9	0.244461	0.969659	0.252111	3.966514	1.031290	4.090627	0.0051465	2.6426814	51
10	0.244743	0.969588	0.252420	3.961652	1.031366	4.085913	0.0051650	2.6381104	50
11	0.245025	0.969517	0.252729	3.956801	1.031442	4.081210	0.0051835	2.6335506	49
12	0.245307	0.969445	0.253039	3.951962	1.031518	4.076518	0.0052021	2.6290019	48
13	0.245589	0.969374	0.253348	3.947133	1.031594	4.071837	0.0052208	2.6244644	47
14	0.245871	0.969302	0.253658	3.942316	1.031670	4.067168	0.0052395	2.6199379	46
15	0.246153	0.969231	0.253968	3.937509	1.031746	4.062509	0.0052582	2.6154225	45
16	0.246435	0.969159	0.254277	3.932714	1.031822	4.057862	0.0052770	2.6109181	44
17	0.246717	0.969088	0.254587	3.927930	1.031899	4.053225	0.0052958	2.6064246	43
18	0.246999	0.969016	0.254897	3.923156	1.031975	4.048599	0.0053147	2.6019421	42
19	0.247281	0.968944	0.255207	3.918394	1.032052	4.043984	0.0053336	2.5974704	41
20	0.247563	0.968872	0.255516	3.913642	1.032128	4.039380	0.0053526	2.5930096	40
21	0.247845	0.968800	0.255826	3.908901	1.032205	4.034787	0.0053716	2.5885595	39
22	0.248126	0.968728	0.256136	3.904171	1.032282	4.030205	0.0053907	2.5841203	38
23	0.248408	0.968655	0.256446	3.899452	1.032359	4.025633	0.0054098	2.5796918	37
24	0.248690	0.968583	0.256756	3.894743	1.032436	4.021072	0.0054289	2.5752739	36
25	0.248972	0.968511	0.257066	3.890045	1.032513	4.016522	0.0054481	2.5708668	35
26	0.249253	0.968438	0.257377	3.885357	1.032590	4.011982	0.0054674	2.5664702	34
27	0.249535	0.968366	0.257687	3.880681	1.032668	4.007453	0.0054867	2.5620843	33
28	0.249817	0.968293	0.257997	3.876014	1.032745	4.002935	0.0055060	2.5577088	32
29	0.250098	0.968220	0.258307	3.871358	1.032823	3.998427	0.0055254	2.5533439	31
30	0.250380	0.968148	0.258618	3.866713	1.032900	3.993929	0.0055448	2.5489895	30
31	0.250662	0.968075	0.258928	3.862078	1.032978	3.989442	0.0055643	2.5446455	29
32	0.250943	0.968002	0.259238	3.857454	1.033056	3.984965	0.0055838	2.5403119	28
33	0.251225	0.967929	0.259549	3.852840	1.033134	3.980499	0.0056034	2.5359887	27
34	0.251506	0.967856	0.259859	3.848236	1.033212	3.976043	0.0056230	2.5316758	26
35	0.251788	0.967782	0.260170	3.843642	1.033290	3.971597	0.0056427	2.5273732	25
36	0.252069	0.967709	0.260480	3.839059	1.033368	3.967162	0.0056624	2.5230809	24
37	0.252351	0.967636	0.260791	3.834486	1.033447	3.962737	0.0056822	2.5187988	23
38	0.252632	0.967562	0.261102	3.829923	1.033525	3.958322	0.0057020	2.5145268	22
39	0.252914	0.967489	0.261413	3.825371	1.033604	3.953917	0.0057218	2.5102651	21
40	0.253195	0.967415	0.261723	3.820828	1.033682	3.949522	0.0057417	2.5060134	20
41	0.253477	0.967342	0.262034	3.816296	1.033761	3.945138	0.0057617	2.5017719	19
42	0.253758	0.967268	0.262345	3.811773	1.033840	3.940763	0.0057817	2.4975404	18
43	0.254039	0.967194	0.262656	3.807261	1.033919	3.936399	0.0058017	2.4933189	17
44	0.254321	0.967120	0.262967	3.802759	1.033998	3.932044	0.0058218	2.4891074	16
45	0.254602	0.967046	0.263278	3.798266	1.034077	3.927700	0.0058420	2.4849058	15
46	0.254883	0.966972	0.263589	3.793784	1.034156	3.923365	0.0058622	2.4807142	14
47	0.255165	0.966898	0.263900	3.789311	1.034236	3.919040	0.0058824	2.4765324	13
48	0.255446	0.966823	0.264211	3.784848	1.034315	3.914725	0.0059027	2.4723605	12
49	0.255727	0.966749	0.264523	3.780395	1.034395	3.910420	0.0059230	2.4681984	11
50	0.256008	0.966675	0.264834	3.775952	1.034474	3.906125	0.0059434	2.4640461	10
51	0.256289	0.966600	0.265145	3.771518	1.034554	3.901840	0.0059638	2.4599035	9
52	0.256571	0.966526	0.265457	3.767095	1.034634	3.897564	0.0059843	2.4557707	8
53	0.256852	0.966451	0.265768	3.762681	1.034714	3.893298	0.0060048	2.4516475	7
54	0.257133	0.966376	0.266079	3.758276	1.034794	3.889041	0.0060254	2.4475340	6
55	0.257414	0.966301	0.266391	3.753882	1.034874	3.884794	0.0060460	2.4434301	5
56	0.257695	0.966226	0.266702	3.749496	1.034954	3.880557	0.0060667	2.4393358	4
57	0.257976	0.966151	0.267014	3.745121	1.035035	3.876329	0.0060874	2.4352511	3
58	0.258257	0.966076	0.267326	3.740755	1.035115	3.872111	0.0061081	2.4311759	2
59	0.258538	0.966001	0.267637	3.736398	1.035196	3.867903	0.0061289	2.4271101	1
60	0.258819	0.965926	0.267949	3.732051	1.035276	3.863703	0.0061498	2.4230539	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	75°–76° Involute	Minutes

↑ 104° or 284° 75° or 255° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 15° or 195° Trigonometric and Involute Functions 164° or 344° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 15°–16°	Read Up	Minutes
0	0.258819	0.965926	0.267949	3.732051	1.035276	3.863703	0.0061498	2.4230539	60
1	0.259100	0.965850	0.268261	3.727713	1.035357	3.859514	0.0061707	2.4190070	59
2	0.259381	0.965775	0.268573	3.723385	1.035438	3.855333	0.0061917	2.4149696	58
3	0.259662	0.965700	0.268885	3.719066	1.035519	3.851162	0.0062127	2.4109415	57
4	0.259943	0.965624	0.269197	3.714756	1.035600	3.847001	0.0062337	2.4069228	56
5	0.260224	0.965548	0.269509	3.710456	1.035681	3.842848	0.0062548	2.4029133	55
6	0.260505	0.965473	0.269821	3.706165	1.035762	3.838705	0.0062760	2.3989132	54
7	0.260785	0.965397	0.270133	3.701883	1.035843	3.834571	0.0062972	2.3949222	53
8	0.261066	0.965321	0.270445	3.697610	1.035925	3.830447	0.0063184	2.3909405	52
9	0.261347	0.965245	0.270757	3.693347	1.036006	3.826331	0.0063397	2.3869680	51
10	0.261628	0.965169	0.271069	3.689093	1.036088	3.822225	0.0063611	2.3830046	50
11	0.261908	0.965093	0.271382	3.684848	1.036170	3.818128	0.0063825	2.3790503	49
12	0.262189	0.965016	0.271694	3.680611	1.036252	3.814040	0.0064039	2.3751052	48
13	0.262470	0.964940	0.272006	3.676384	1.036334	3.809961	0.0064254	2.3711691	47
14	0.262751	0.964864	0.272319	3.672166	1.036416	3.805891	0.0064470	2.3672420	46
15	0.263031	0.964787	0.272631	3.667958	1.036498	3.801830	0.0064686	2.3633239	45
16	0.263312	0.964711	0.272944	3.663758	1.036580	3.797778	0.0064902	2.3594148	44
17	0.263592	0.964634	0.273256	3.659566	1.036662	3.793735	0.0065119	2.3555147	43
18	0.263873	0.964557	0.273569	3.655384	1.036745	3.789701	0.0065337	2.3516234	42
19	0.264154	0.964481	0.273882	3.651211	1.036827	3.785676	0.0065555	2.3477410	41
20	0.264434	0.964404	0.274194	3.647047	1.036910	3.781660	0.0065773	2.3438675	40
21	0.264715	0.964327	0.274507	3.642891	1.036993	3.777652	0.0065992	2.3400029	39
22	0.264995	0.964250	0.274820	3.638744	1.037076	3.773653	0.0066211	2.3361470	38
23	0.265276	0.964173	0.275133	3.634606	1.037159	3.769664	0.0066431	2.3322999	37
24	0.265556	0.964095	0.275446	3.630477	1.037242	3.765682	0.0066652	2.3284615	36
25	0.265837	0.964018	0.275759	3.626357	1.037325	3.761710	0.0066873	2.3246318	35
26	0.266117	0.963941	0.276072	3.622245	1.037408	3.757746	0.0067094	2.3208108	34
27	0.266397	0.963863	0.276385	3.618141	1.037492	3.753791	0.0067316	2.3169985	33
28	0.266678	0.963786	0.276698	3.614047	1.037575	3.749845	0.0067539	2.3131948	32
29	0.266958	0.963708	0.277011	3.609961	1.037659	3.745907	0.0067762	2.3093997	31
30	0.267238	0.963630	0.277325	3.605884	1.037742	3.741978	0.0067985	2.3056132	30
31	0.267519	0.963553	0.277638	3.601815	1.037826	3.738057	0.0068209	2.3018352	29
32	0.267799	0.963475	0.277951	3.597754	1.037910	3.734145	0.0068434	2.2980658	28
33	0.268079	0.963397	0.278265	3.593702	1.037994	3.730241	0.0068659	2.2943048	27
34	0.268359	0.963319	0.278578	3.589659	1.038078	3.726346	0.0068884	2.2905523	26
35	0.268640	0.963241	0.278891	3.585624	1.038162	3.722459	0.0069110	2.2868082	25
36	0.268920	0.963163	0.279205	3.581598	1.038246	3.718580	0.0069337	2.2830726	24
37	0.269200	0.963084	0.279519	3.577579	1.038331	3.714711	0.0069564	2.2793453	23
38	0.269480	0.963006	0.279832	3.573570	1.038415	3.710849	0.0069791	2.2756264	22
39	0.269760	0.962928	0.280146	3.569568	1.038500	3.706996	0.0070019	2.2719158	21
40	0.270040	0.962849	0.280460	3.565575	1.038584	3.703151	0.0070248	2.2682135	20
41	0.270320	0.962770	0.280773	3.561590	1.038669	3.699314	0.0070477	2.2645194	19
42	0.270600	0.962692	0.281087	3.557613	1.038754	3.695485	0.0070706	2.2608337	18
43	0.270880	0.962613	0.281401	3.553645	1.038839	3.691665	0.0070936	2.2571561	17
44	0.271160	0.962534	0.281715	3.549685	1.038924	3.687853	0.0071167	2.2534868	16
45	0.271440	0.962455	0.282029	3.545733	1.039009	3.684049	0.0071398	2.2498256	15
46	0.271720	0.962376	0.282343	3.541789	1.039095	3.680254	0.0071630	2.2461725	14
47	0.272000	0.962297	0.282657	3.537853	1.039180	3.676466	0.0071862	2.2425276	13
48	0.272280	0.962218	0.282971	3.533925	1.039266	3.672687	0.0072095	2.2388908	12
49	0.272560	0.962139	0.283286	3.530005	1.039351	3.668915	0.0072328	2.2352620	11
50	0.272840	0.962059	0.283600	3.526094	1.039437	3.665152	0.0072561	2.2316413	10
51	0.273120	0.961980	0.283914	3.522190	1.039523	3.661396	0.0072796	2.2280286	9
52	0.273400	0.961901	0.284229	3.518295	1.039609	3.657649	0.0073030	2.2244239	8
53	0.273679	0.961821	0.284543	3.514407	1.039695	3.653910	0.0073266	2.2208271	7
54	0.273959	0.961741	0.284857	3.510527	1.039781	3.650178	0.0073501	2.2172383	6
55	0.274239	0.961662	0.285172	3.506655	1.039867	3.646455	0.0073738	2.2136574	5
56	0.274519	0.961582	0.285487	3.502792	1.039953	3.642739	0.0073975	2.2100844	4
57	0.274798	0.961502	0.285801	3.498936	1.040040	3.639031	0.0074212	2.2065193	3
58	0.275078	0.961422	0.286116	3.495087	1.040126	3.635332	0.0074450	2.2029620	2
59	0.275358	0.961342	0.286431	3.491247	1.040213	3.631640	0.0074688	2.1994125	1
60	0.275637	0.961262	0.286745	3.487414	1.040299	3.627955	0.0074927	2.1958708	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	74°–75° Involute	Minutes

↑ 105° or 285° 74° or 254° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 16° or 196° Trigonometric and Involute Functions 163° or 343° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 16°–17°	Read Up	Minutes
0	0.275637	0.961262	0.286745	3.487414	1.040299	3.627955	0.0074927	2.1958708	60
1	0.275917	0.961181	0.287060	3.483590	1.040386	3.624279	0.0075166	2.1923369	59
2	0.276197	0.961101	0.287375	3.479773	1.040473	3.620610	0.0075406	2.1888107	58
3	0.276476	0.961021	0.287690	3.475963	1.040560	3.616949	0.0075647	2.1852922	57
4	0.276756	0.960940	0.288005	3.472162	1.040647	3.613296	0.0075888	2.1817815	56
5	0.277035	0.960860	0.288320	3.468368	1.040735	3.609650	0.0076130	2.1782784	55
6	0.277315	0.960779	0.288635	3.464581	1.040822	3.606012	0.0076372	2.1747830	54
7	0.277594	0.960698	0.288950	3.460803	1.040909	3.602382	0.0076614	2.1712951	53
8	0.277874	0.960618	0.289266	3.457031	1.040997	3.598759	0.0076857	2.1678149	52
9	0.278153	0.960537	0.289581	3.453268	1.041085	3.595144	0.0077101	2.1643423	51
10	0.278432	0.960456	0.289896	3.449512	1.041172	3.591536	0.0077345	2.1608772	50
11	0.278712	0.960375	0.290211	3.445764	1.041260	3.587936	0.0077590	2.1574196	49
12	0.278991	0.960294	0.290527	3.442023	1.041348	3.584344	0.0077835	2.1539696	48
13	0.279270	0.960212	0.290842	3.438289	1.041436	3.580759	0.0078081	2.1505270	47
14	0.279550	0.960131	0.291158	3.434563	1.041524	3.577181	0.0078327	2.1470919	46
15	0.279829	0.960050	0.291473	3.430845	1.041613	3.573611	0.0078574	2.1436643	45
16	0.280108	0.959968	0.291789	3.427133	1.041701	3.570048	0.0078822	2.1402440	44
17	0.280388	0.959887	0.292105	3.423430	1.041789	3.566493	0.0079069	2.1368311	43
18	0.280667	0.959805	0.292420	3.419733	1.041878	3.562945	0.0079318	2.1334256	42
19	0.280946	0.959724	0.292736	3.416044	1.041967	3.559404	0.0079567	2.1300275	41
20	0.281225	0.959642	0.293052	3.412363	1.042055	3.555871	0.0079817	2.1266367	40
21	0.281504	0.959560	0.293368	3.408688	1.042144	3.552345	0.0080067	2.1232532	39
22	0.281783	0.959478	0.293684	3.405021	1.042233	3.548826	0.0080317	2.1198769	38
23	0.282062	0.959396	0.294000	3.401361	1.042322	3.545315	0.0080568	2.1165079	37
24	0.282341	0.959314	0.294316	3.397709	1.042412	3.541811	0.0080820	2.1131462	36
25	0.282620	0.959232	0.294632	3.394063	1.042501	3.538314	0.0081072	2.1097917	35
26	0.282900	0.959150	0.294948	3.390425	1.042590	3.534824	0.0081325	2.1064443	34
27	0.283179	0.959067	0.295265	3.386794	1.042680	3.531341	0.0081578	2.1031041	33
28	0.283457	0.958985	0.295581	3.383170	1.042769	3.527866	0.0081832	2.0997711	32
29	0.283736	0.958902	0.295897	3.379553	1.042859	3.524398	0.0082087	2.0964452	31
30	0.284015	0.958820	0.296213	3.375943	1.042949	3.520937	0.0082342	2.0931264	30
31	0.284294	0.958737	0.296530	3.372341	1.043039	3.517482	0.0082597	2.0898147	29
32	0.284573	0.958654	0.296846	3.368745	1.043129	3.514035	0.0082853	2.0865101	28
33	0.284852	0.958572	0.297163	3.365157	1.043219	3.510595	0.0083110	2.0832124	27
34	0.285131	0.958489	0.297480	3.361575	1.043309	3.507162	0.0083367	2.0799219	26
35	0.285410	0.958406	0.297796	3.358001	1.043400	3.503737	0.0083625	2.0766383	25
36	0.285688	0.958323	0.298113	3.354433	1.043490	3.500318	0.0083883	2.0733616	24
37	0.285967	0.958239	0.298430	3.350873	1.043581	3.496906	0.0084142	2.0700920	23
38	0.286246	0.958156	0.298747	3.347319	1.043671	3.493500	0.0084401	2.0668292	22
39	0.286525	0.958073	0.299063	3.343772	1.043762	3.490102	0.0084661	2.0635734	21
40	0.286803	0.957990	0.299380	3.340233	1.043853	3.486711	0.0084921	2.0603245	20
41	0.287082	0.957906	0.299697	3.336700	1.043944	3.483327	0.0085182	2.0570824	19
42	0.287361	0.957822	0.300014	3.333174	1.044035	3.479949	0.0085444	2.0538472	18
43	0.287639	0.957739	0.300331	3.329654	1.044126	3.476578	0.0085706	2.0506189	17
44	0.287918	0.957655	0.300649	3.326142	1.044217	3.473215	0.0085969	2.0473973	16
45	0.288196	0.957571	0.300966	3.322636	1.044309	3.469858	0.0086232	2.0441825	15
46	0.288475	0.957487	0.301283	3.319137	1.044400	3.466507	0.0086496	2.0409746	14
47	0.288753	0.957404	0.301600	3.315645	1.044492	3.463164	0.0086760	2.0377733	13
48	0.289032	0.957319	0.301918	3.312160	1.044583	3.459827	0.0087025	2.0345788	12
49	0.289310	0.957235	0.302235	3.308681	1.044675	3.456497	0.0087290	2.0313910	11
50	0.289589	0.957151	0.302553	3.305209	1.044767	3.453173	0.0087556	2.0282099	10
51	0.289867	0.957067	0.302870	3.301744	1.044859	3.449857	0.0087823	2.0250354	9
52	0.290145	0.956983	0.303188	3.298285	1.044951	3.446547	0.0088090	2.0218676	8
53	0.290424	0.956898	0.303506	3.294833	1.045043	3.443243	0.0088358	2.0187064	7
54	0.290702	0.956814	0.303823	3.291388	1.045136	3.439947	0.0088626	2.0155519	6
55	0.290981	0.956729	0.304141	3.287949	1.045228	3.436656	0.0088895	2.0124039	5
56	0.291259	0.956644	0.304459	3.284516	1.045321	3.433373	0.0089164	2.0092625	4
57	0.291537	0.956560	0.304777	3.281091	1.045413	3.430096	0.0089434	2.0061277	3
58	0.291815	0.956475	0.305095	3.277671	1.045506	3.426825	0.0089704	2.0029994	2
59	0.292094	0.956390	0.305413	3.274259	1.045599	3.423561	0.0089975	1.9998776	1
60	0.292372	0.956305	0.305731	3.270853	1.045692	3.420304	0.0090247	1.9967623	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	73°–74° Involute	Minutes

↑ 106° or 286° 73° or 253° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 17° or 197° Trigonometric and Involute Functions 162° or 342° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 17°–18°	Read Up	Minutes
0	0.292372	0.956305	0.305731	3.270853	1.045692	3.420304	0.0090247	1.9967623	60
1	0.292650	0.956220	0.306049	3.267453	1.045785	3.417053	0.0090519	1.9936534	59
2	0.292928	0.956134	0.306367	3.264060	1.045878	3.413808	0.0090792	1.9905511	58
3	0.293206	0.956049	0.306685	3.260673	1.045971	3.410570	0.0091065	1.9874551	57
4	0.293484	0.955964	0.307003	3.257292	1.046065	3.407338	0.0091339	1.9843656	56
5	0.293762	0.955879	0.307322	3.253918	1.046158	3.404113	0.0091614	1.9812825	55
6	0.294040	0.955793	0.307640	3.250551	1.046252	3.400894	0.0091889	1.9782058	54
7	0.294318	0.955707	0.307959	3.247190	1.046345	3.397682	0.0092164	1.9751354	53
8	0.294596	0.955622	0.308277	3.243835	1.046439	3.394475	0.0092440	1.9720714	52
9	0.294874	0.955536	0.308596	3.240486	1.046533	3.391276	0.0092717	1.9690137	51
10	0.295152	0.955450	0.308914	3.237144	1.046627	3.388082	0.0092994	1.9659623	50
11	0.295430	0.955364	0.309233	3.233808	1.046721	3.384895	0.0093272	1.9629172	49
12	0.295708	0.955278	0.309552	3.230478	1.046815	3.381714	0.0093551	1.9598783	48
13	0.295986	0.955192	0.309870	3.227155	1.046910	3.378539	0.0093830	1.9568458	47
14	0.296264	0.955106	0.310189	3.223837	1.047004	3.375371	0.0094109	1.9538194	46
15	0.296542	0.955020	0.310508	3.220526	1.047099	3.372208	0.0094390	1.9507993	45
16	0.296819	0.954934	0.310827	3.217221	1.047193	3.369052	0.0094670	1.9477853	44
17	0.297097	0.954847	0.311146	3.213923	1.047288	3.365903	0.0094952	1.9447776	43
18	0.297375	0.954761	0.311465	3.210630	1.047383	3.362759	0.0095234	1.9417760	42
19	0.297653	0.954674	0.311784	3.207344	1.047478	3.359621	0.0095516	1.9387805	41
20	0.297930	0.954588	0.312104	3.204064	1.047573	3.356490	0.0095799	1.9357912	40
21	0.298208	0.954501	0.312423	3.200790	1.047668	3.353365	0.0096083	1.9328080	39
22	0.298486	0.954414	0.312742	3.197522	1.047763	3.350246	0.0096367	1.9298309	38
23	0.298763	0.954327	0.313062	3.194260	1.047859	3.347132	0.0096652	1.9268598	37
24	0.299041	0.954240	0.313381	3.191004	1.047954	3.344025	0.0096937	1.9238948	36
25	0.299318	0.954153	0.313700	3.187754	1.048050	3.340924	0.0097223	1.9209359	35
26	0.299596	0.954066	0.314020	3.184510	1.048145	3.337829	0.0097510	1.9179830	34
27	0.299873	0.953979	0.314340	3.181272	1.048241	3.334740	0.0097797	1.9150360	33
28	0.300151	0.953892	0.314659	3.178041	1.048337	3.331658	0.0098085	1.9120951	32
29	0.300428	0.953804	0.314979	3.174815	1.048433	3.328581	0.0098373	1.9091601	31
30	0.300706	0.953717	0.315299	3.171595	1.048529	3.325510	0.0098662	1.9062311	30
31	0.300983	0.953629	0.315619	3.168381	1.048625	3.322444	0.0098951	1.9033080	29
32	0.301261	0.953542	0.315939	3.165173	1.048722	3.319385	0.0099241	1.9003908	28
33	0.301538	0.953454	0.316258	3.161971	1.048818	3.316332	0.0099532	1.8974796	27
34	0.301815	0.953366	0.316578	3.158774	1.048915	3.313285	0.0099823	1.8945742	26
35	0.302093	0.953279	0.316899	3.155584	1.049011	3.310243	0.0100115	1.8916747	25
36	0.302370	0.953191	0.317219	3.152399	1.049108	3.307208	0.0100407	1.8887810	24
37	0.302647	0.953103	0.317539	3.149221	1.049205	3.304178	0.0100700	1.8858932	23
38	0.302924	0.953015	0.317859	3.146048	1.049302	3.301154	0.0100994	1.8830112	22
39	0.303202	0.952926	0.318179	3.142881	1.049399	3.298136	0.0101288	1.8801350	21
40	0.303479	0.952838	0.318500	3.139719	1.049496	3.295123	0.0101583	1.8772646	20
41	0.303756	0.952750	0.318820	3.136564	1.049593	3.292117	0.0101878	1.8743999	19
42	0.304033	0.952661	0.319141	3.133414	1.049691	3.289116	0.0102174	1.8715411	18
43	0.304310	0.952573	0.319461	3.130270	1.049788	3.286121	0.0102471	1.8686879	17
44	0.304587	0.952484	0.319782	3.127132	1.049886	3.283132	0.0102768	1.8658405	16
45	0.304864	0.952396	0.320103	3.123999	1.049984	3.280148	0.0103066	1.8629987	15
46	0.305141	0.952307	0.320423	3.120872	1.050081	3.277170	0.0103364	1.8601627	14
47	0.305418	0.952218	0.320744	3.117751	1.050179	3.274198	0.0103663	1.8573323	13
48	0.305695	0.952129	0.321065	3.114635	1.050277	3.271231	0.0103963	1.8545076	12
49	0.305972	0.952040	0.321386	3.111525	1.050376	3.268270	0.0104263	1.8516885	11
50	0.306249	0.951951	0.321707	3.108421	1.050474	3.265315	0.0104564	1.8488751	10
51	0.306526	0.951862	0.322028	3.105322	1.050572	3.262365	0.0104865	1.8460672	9
52	0.306803	0.951773	0.322349	3.102229	1.050671	3.259421	0.0105167	1.8432650	8
53	0.307080	0.951684	0.322670	3.099142	1.050769	3.256483	0.0105469	1.8404683	7
54	0.307357	0.951594	0.322991	3.096060	1.050868	3.253550	0.0105773	1.8376772	6
55	0.307633	0.951505	0.323312	3.092983	1.050967	3.250622	0.0106076	1.8348916	5
56	0.307910	0.951415	0.323634	3.089912	1.051066	3.247700	0.0106381	1.8321116	4
57	0.308187	0.951326	0.323955	3.086847	1.051165	3.244784	0.0106686	1.8293371	3
58	0.308464	0.951236	0.324277	3.083787	1.051264	3.241873	0.0106991	1.8265681	2
59	0.308740	0.951146	0.324598	3.080732	1.051363	3.238968	0.0107298	1.8238045	1
60	0.309017	0.951057	0.324920	3.077684	1.051462	3.236068	0.0107604	1.8210465	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	72°–73° Involute	Minutes

↑ 107° or 287° 72° or 252° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 18° or 198° Trigonometric and Involute Functions 161° or 341° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 18°–19°	Read Up	Minutes
0	0.309017	0.951057	0.324920	3.077684	1.051462	3.236068	0.0107604	1.8210465	60
1	0.309294	0.950967	0.325241	3.074640	1.051562	3.233174	0.0107912	1.8182939	59
2	0.309570	0.950877	0.325563	3.071602	1.051661	3.230285	0.0108220	1.8155467	58
3	0.309847	0.950786	0.325885	3.068569	1.051761	3.227401	0.0108528	1.8128050	57
4	0.310123	0.950696	0.326207	3.065542	1.051861	3.224523	0.0108838	1.8100686	56
5	0.310400	0.950606	0.326528	3.062520	1.051960	3.221650	0.0109147	1.8073377	55
6	0.310676	0.950516	0.326850	3.059504	1.052060	3.218783	0.0109458	1.8046121	54
7	0.310953	0.950425	0.327172	3.056493	1.052161	3.215921	0.0109769	1.8018919	53
8	0.311229	0.950335	0.327494	3.053487	1.052261	3.213064	0.0110081	1.7991771	52
9	0.311506	0.950244	0.327817	3.050487	1.052361	3.210213	0.0110393	1.7964676	51
10	0.311782	0.950154	0.328139	3.047492	1.052461	3.207367	0.0110706	1.7937634	50
11	0.312059	0.950063	0.328461	3.044502	1.052562	3.204527	0.0111019	1.7910645	49
12	0.312335	0.949972	0.328783	3.041517	1.052663	3.201691	0.0111333	1.7883709	48
13	0.312611	0.949881	0.329106	3.038538	1.052763	3.198861	0.0111648	1.7856826	47
14	0.312888	0.949790	0.329428	3.035564	1.052864	3.196037	0.0111964	1.7829995	46
15	0.313164	0.949699	0.329751	3.032595	1.052965	3.193217	0.0112280	1.7803217	45
16	0.313440	0.949608	0.330073	3.029632	1.053066	3.190403	0.0112596	1.7776491	44
17	0.313716	0.949517	0.330396	3.026674	1.053167	3.187594	0.0112913	1.7749817	43
18	0.313992	0.949425	0.330718	3.023721	1.053269	3.184790	0.0113231	1.7723196	42
19	0.314269	0.949334	0.331041	3.020773	1.053370	3.181991	0.0113550	1.7696626	41
20	0.314545	0.949243	0.331364	3.017830	1.053471	3.179198	0.0113869	1.7670108	40
21	0.314821	0.949151	0.331687	3.014893	1.053573	3.176410	0.0114189	1.7643642	39
22	0.315097	0.949059	0.332010	3.011960	1.053675	3.173626	0.0114509	1.7617227	38
23	0.315373	0.948968	0.332333	3.009033	1.053777	3.170848	0.0114830	1.7590864	37
24	0.315649	0.948876	0.332656	3.006111	1.053878	3.168076	0.0115151	1.7564552	36
25	0.315925	0.948784	0.332979	3.003194	1.053981	3.165308	0.0115474	1.7538290	35
26	0.316201	0.948692	0.333302	3.000282	1.054083	3.162545	0.0115796	1.7512080	34
27	0.316477	0.948600	0.333625	2.997375	1.054185	3.159788	0.0116120	1.7485921	33
28	0.316753	0.948508	0.333949	2.994473	1.054287	3.157035	0.0116444	1.7459812	32
29	0.317029	0.948416	0.334272	2.991577	1.054390	3.154288	0.0116769	1.7433753	31
30	0.317305	0.948324	0.334595	2.988685	1.054492	3.151545	0.0117094	1.7407745	30
31	0.317580	0.948231	0.334919	2.985798	1.054595	3.148808	0.0117420	1.7381788	29
32	0.317856	0.948139	0.335242	2.982917	1.054698	3.146076	0.0117747	1.7355880	28
33	0.318132	0.948046	0.335566	2.980040	1.054801	3.143348	0.0118074	1.7330022	27
34	0.318408	0.947954	0.335890	2.977168	1.054904	3.140626	0.0118402	1.7304215	26
35	0.318684	0.947861	0.336213	2.974302	1.055007	3.137909	0.0118730	1.7278456	25
36	0.318959	0.947768	0.336537	2.971440	1.055110	3.135196	0.0119059	1.7252748	24
37	0.319235	0.947676	0.336861	2.968583	1.055213	3.132489	0.0119389	1.7227089	23
38	0.319511	0.947583	0.337185	2.965731	1.055317	3.129786	0.0119720	1.7201479	22
39	0.319786	0.947490	0.337509	2.962884	1.055420	3.127089	0.0120051	1.7175918	21
40	0.320062	0.947397	0.337833	2.960042	1.055524	3.124396	0.0120382	1.7150407	20
41	0.320337	0.947304	0.338157	2.957205	1.055628	3.121708	0.0120715	1.7124944	19
42	0.320613	0.947210	0.338481	2.954373	1.055732	3.119025	0.0121048	1.7099530	18
43	0.320889	0.947117	0.338806	2.951545	1.055836	3.116347	0.0121381	1.7074164	17
44	0.321164	0.947024	0.339130	2.948723	1.055940	3.113674	0.0121715	1.7048848	16
45	0.321439	0.946930	0.339454	2.945905	1.056044	3.111006	0.0122050	1.7023579	15
46	0.321715	0.946837	0.339779	2.943092	1.056148	3.108342	0.0122386	1.6998359	14
47	0.321990	0.946743	0.340103	2.940284	1.056253	3.105683	0.0122722	1.6973187	13
48	0.322266	0.946649	0.340428	2.937481	1.056357	3.103030	0.0123059	1.6948063	12
49	0.322541	0.946555	0.340752	2.934682	1.056462	3.100381	0.0123396	1.6922986	11
50	0.322816	0.946462	0.341077	2.931888	1.056567	3.097736	0.0123734	1.6897958	10
51	0.323092	0.946368	0.341402	2.929099	1.056672	3.095097	0.0124073	1.6872977	9
52	0.323367	0.946274	0.341727	2.926315	1.056777	3.092462	0.0124412	1.6848044	8
53	0.323642	0.946180	0.342052	2.923536	1.056882	3.089832	0.0124752	1.6823158	7
54	0.323917	0.946085	0.342377	2.920761	1.056987	3.087207	0.0125093	1.6798319	6
55	0.324193	0.945991	0.342702	2.917991	1.057092	3.084586	0.0125434	1.6773527	5
56	0.324468	0.945897	0.343027	2.915226	1.057198	3.081970	0.0125776	1.6748783	4
57	0.324743	0.945802	0.343352	2.912465	1.057303	3.079359	0.0126119	1.6724085	3
58	0.325018	0.945708	0.343677	2.909709	1.057409	3.076752	0.0126462	1.6699434	2
59	0.325293	0.945613	0.344002	2.906958	1.057515	3.074151	0.0126806	1.6674829	1
60	0.325568	0.945519	0.344328	2.904211	1.057621	3.071553	0.0127151	1.6650271	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	71°–72° Involute	Minutes

↑ 108° or 288° 71° or 251° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 19° or 199° Trigonometric and Involute Functions 160° or 340° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 19°–20°	Read Up	Minutes
0	0.325568	0.945519	0.344328	2.904211	1.057621	3.071553	0.0127151	1.6650271	60
1	0.325843	0.945424	0.344653	2.901469	1.057727	3.068961	0.0127496	1.6625759	59
2	0.326118	0.945329	0.344978	2.898731	1.057833	3.066373	0.0127842	1.6601294	58
3	0.326393	0.945234	0.345304	2.895999	1.057939	3.063790	0.0128188	1.6576875	57
4	0.326668	0.945139	0.345630	2.893270	1.058045	3.061211	0.0128535	1.6552502	56
5	0.326943	0.945044	0.345955	2.890547	1.058152	3.058637	0.0128883	1.6528174	55
6	0.327218	0.944949	0.346281	2.887828	1.058258	3.056068	0.0129232	1.6503893	54
7	0.327493	0.944854	0.346607	2.885113	1.058365	3.053503	0.0129581	1.6479657	53
8	0.327768	0.944758	0.346933	2.882403	1.058472	3.050942	0.0129931	1.6455466	52
9	0.328042	0.944663	0.347259	2.879698	1.058579	3.048386	0.0130281	1.6431321	51
10	0.328317	0.944568	0.347585	2.876997	1.058686	3.045835	0.0130632	1.6407221	50
11	0.328592	0.944472	0.347911	2.874301	1.058793	3.043288	0.0130984	1.6383167	49
12	0.328867	0.944376	0.348237	2.871609	1.058900	3.040746	0.0131336	1.6359157	48
13	0.329141	0.944281	0.348563	2.868921	1.059007	3.038208	0.0131689	1.6335193	47
14	0.329416	0.944185	0.348889	2.866239	1.059115	3.035675	0.0132043	1.6311273	46
15	0.329691	0.944089	0.349216	2.863560	1.059222	3.033146	0.0132398	1.6287398	45
16	0.329965	0.943993	0.349542	2.860886	1.059330	3.030622	0.0132753	1.6263567	44
17	0.330240	0.943897	0.349868	2.858217	1.059438	3.028102	0.0133108	1.6239781	43
18	0.330514	0.943801	0.350195	2.855552	1.059545	3.025587	0.0133465	1.6216040	42
19	0.330789	0.943705	0.350522	2.852891	1.059653	3.023076	0.0133822	1.6192342	41
20	0.331063	0.943609	0.350848	2.850235	1.059762	3.020569	0.0134180	1.6168689	40
21	0.331338	0.943512	0.351175	2.847583	1.059870	3.018067	0.0134538	1.6145080	39
22	0.331612	0.943416	0.351502	2.844936	1.059978	3.015569	0.0134897	1.6121514	38
23	0.331887	0.943319	0.351829	2.842293	1.060087	3.013076	0.0135257	1.6097993	37
24	0.332161	0.943223	0.352156	2.839654	1.060195	3.010587	0.0135617	1.6074515	36
25	0.332435	0.943126	0.352483	2.837020	1.060304	3.008102	0.0135978	1.6051080	35
26	0.332710	0.943029	0.352810	2.834390	1.060412	3.005622	0.0136340	1.6027689	34
27	0.332984	0.942932	0.353137	2.831764	1.060521	3.003146	0.0136702	1.6004342	33
28	0.333258	0.942836	0.353464	2.829143	1.060630	3.000675	0.0137065	1.5981037	32
29	0.333533	0.942739	0.353791	2.826526	1.060739	2.998207	0.0137429	1.5957776	31
30	0.333807	0.942641	0.354119	2.823913	1.060849	2.995744	0.0137794	1.5934558	30
31	0.334081	0.942544	0.354446	2.821304	1.060958	2.993286	0.0138159	1.5911382	29
32	0.334355	0.942447	0.354773	2.818700	1.061067	2.990831	0.0138525	1.5888250	28
33	0.334629	0.942350	0.355101	2.816100	1.061177	2.988381	0.0138891	1.5865160	27
34	0.334903	0.942252	0.355429	2.813505	1.061287	2.985935	0.0139258	1.5842112	26
35	0.335178	0.942155	0.355756	2.810913	1.061396	2.983494	0.0139626	1.5819107	25
36	0.335452	0.942057	0.356084	2.808326	1.061506	2.981056	0.0139994	1.5796145	24
37	0.335726	0.941960	0.356412	2.805743	1.061616	2.978623	0.0140364	1.5773224	23
38	0.336000	0.941862	0.356740	2.803165	1.061727	2.976194	0.0140734	1.5750346	22
39	0.336274	0.941764	0.357068	2.800590	1.061837	2.973769	0.0141104	1.5727510	21
40	0.336547	0.941666	0.357396	2.798020	1.061947	2.971349	0.0141475	1.5704716	20
41	0.336821	0.941569	0.357724	2.795454	1.062058	2.968933	0.0141847	1.5681963	19
42	0.337095	0.941471	0.358052	2.792892	1.062168	2.966521	0.0142220	1.5659252	18
43	0.337369	0.941372	0.358380	2.790334	1.062279	2.964113	0.0142593	1.5636583	17
44	0.337643	0.941274	0.358708	2.787780	1.062390	2.961709	0.0142967	1.5613955	16
45	0.337917	0.941176	0.359037	2.785231	1.062501	2.959309	0.0143342	1.5591369	15
46	0.338190	0.941078	0.359365	2.782685	1.062612	2.956914	0.0143717	1.5568824	14
47	0.338464	0.940979	0.359694	2.780144	1.062723	2.954522	0.0144093	1.5546320	13
48	0.338738	0.940881	0.360022	2.777607	1.062834	2.952135	0.0144470	1.5523857	12
49	0.339012	0.940782	0.360351	2.775074	1.062945	2.949752	0.0144847	1.5501435	11
50	0.339285	0.940684	0.360679	2.772545	1.063057	2.947372	0.0145225	1.5479054	10
51	0.339559	0.940585	0.361008	2.770020	1.063168	2.944997	0.0145604	1.5456714	9
52	0.339832	0.940486	0.361337	2.767499	1.063280	2.942627	0.0145983	1.5434415	8
53	0.340106	0.940387	0.361666	2.764982	1.063392	2.940260	0.0146363	1.5412156	7
54	0.340380	0.940288	0.361995	2.762470	1.063504	2.937897	0.0146744	1.5389937	6
55	0.340653	0.940189	0.362324	2.759961	1.063616	2.935538	0.0147126	1.5367759	5
56	0.340927	0.940090	0.362653	2.757456	1.063728	2.933183	0.0147508	1.5345621	4
57	0.341200	0.939991	0.362982	2.754955	1.063840	2.930833	0.0147891	1.5323523	3
58	0.341473	0.939891	0.363312	2.752459	1.063953	2.928486	0.0148275	1.5301465	2
59	0.341747	0.939792	0.363641	2.749966	1.064065	2.926143	0.0148659	1.5279447	1
60	0.342020	0.939693	0.363970	2.747477	1.064178	2.923804	0.0149044	1.5257469	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	70°–71° Involute	Minutes

↑ 109° or 289° 70° or 250° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 20° or 200° Trigonometric and Involute Functions 159° or 339° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 20°–21°	Read Up	Minutes
0	0.342020	0.939693	0.363970	2.747477	1.064178	2.923804	0.0149044	1.5257469	60
1	0.342293	0.939593	0.364300	2.744993	1.064290	2.921470	0.0149430	1.5235531	59
2	0.342567	0.939493	0.364629	2.742512	1.064403	2.919139	0.0149816	1.5213633	58
3	0.342840	0.939394	0.364959	2.740035	1.064516	2.916812	0.0150203	1.5191774	57
4	0.343113	0.939294	0.365288	2.737562	1.064629	2.914489	0.0150591	1.5169954	56
5	0.343387	0.939194	0.365618	2.735093	1.064743	2.912170	0.0150979	1.5148174	55
6	0.343660	0.939094	0.365948	2.732628	1.064856	2.909855	0.0151369	1.5126433	54
7	0.343933	0.938994	0.366278	2.730167	1.064969	2.907544	0.0151758	1.5104731	53
8	0.344206	0.938894	0.366608	2.727710	1.065083	2.905237	0.0152149	1.5083068	52
9	0.344479	0.938794	0.366938	2.725257	1.065196	2.902934	0.0152540	1.5061444	51
10	0.344752	0.938694	0.367268	2.722808	1.065310	2.900635	0.0152932	1.5039860	50
11	0.345025	0.938593	0.367598	2.720362	1.065424	2.898339	0.0153325	1.5018313	49
12	0.345298	0.938493	0.367928	2.717920	1.065538	2.896048	0.0153719	1.4996806	48
13	0.345571	0.938393	0.368259	2.715483	1.065652	2.893760	0.0154113	1.4975337	47
14	0.345844	0.938292	0.368589	2.713049	1.065766	2.891476	0.0154507	1.4953907	46
15	0.346117	0.938191	0.368919	2.710619	1.065881	2.889196	0.0154903	1.4932515	45
16	0.346390	0.938091	0.369250	2.708192	1.065995	2.886920	0.0155299	1.4911161	44
17	0.346663	0.937990	0.369581	2.705770	1.066110	2.884647	0.0155696	1.4889845	43
18	0.346936	0.937889	0.369911	2.703351	1.066224	2.882379	0.0156094	1.4868568	42
19	0.347208	0.937788	0.370242	2.700936	1.066339	2.880114	0.0156492	1.4847328	41
20	0.347481	0.937687	0.370573	2.698525	1.066454	2.877853	0.0156891	1.4826127	40
21	0.347754	0.937586	0.370904	2.696118	1.066569	2.875596	0.0157291	1.4804963	39
22	0.348027	0.937485	0.371235	2.693715	1.066684	2.873343	0.0157692	1.4783837	38
23	0.348299	0.937383	0.371566	2.691315	1.066799	2.871093	0.0158093	1.4762749	37
24	0.348572	0.937282	0.371897	2.688919	1.066915	2.868847	0.0158495	1.4741698	36
25	0.348845	0.937181	0.372228	2.686527	1.067030	2.866605	0.0158898	1.4720685	35
26	0.349117	0.937079	0.372559	2.684138	1.067146	2.864367	0.0159301	1.4699709	34
27	0.349390	0.936977	0.372890	2.681754	1.067262	2.862132	0.0159705	1.4678770	33
28	0.349662	0.936876	0.373222	2.679372	1.067377	2.859902	0.0160110	1.4657869	32
29	0.349935	0.936774	0.373553	2.676995	1.067493	2.857674	0.0160516	1.4637004	31
30	0.350207	0.936672	0.373885	2.674621	1.067609	2.855451	0.0160922	1.4616177	30
31	0.350480	0.936570	0.374216	2.672252	1.067726	2.853231	0.0161329	1.4595386	29
32	0.350752	0.936468	0.374548	2.669885	1.067842	2.851015	0.0161737	1.4574632	28
33	0.351025	0.936366	0.374880	2.667523	1.067958	2.848803	0.0162145	1.4553915	27
34	0.351297	0.936264	0.375211	2.665164	1.068075	2.846594	0.0162554	1.4533235	26
35	0.351569	0.936162	0.375543	2.662809	1.068191	2.844389	0.0162964	1.4512591	25
36	0.351842	0.936060	0.375875	2.660457	1.068308	2.842188	0.0163375	1.4491984	24
37	0.352114	0.935957	0.376207	2.658109	1.068425	2.839990	0.0163786	1.4471413	23
38	0.352386	0.935855	0.376539	2.655765	1.068542	2.837796	0.0164198	1.4450878	22
39	0.352658	0.935752	0.376872	2.653424	1.068659	2.835605	0.0164611	1.4430380	21
40	0.352931	0.935650	0.377204	2.651087	1.068776	2.833419	0.0165024	1.4409917	20
41	0.353203	0.935547	0.377536	2.648753	1.068894	2.831235	0.0165439	1.4389491	19
42	0.353475	0.935444	0.377869	2.646423	1.069011	2.829056	0.0165854	1.4369100	18
43	0.353747	0.935341	0.378201	2.644097	1.069129	2.826880	0.0166269	1.4348746	17
44	0.354019	0.935238	0.378534	2.641774	1.069246	2.824707	0.0166686	1.4328427	16
45	0.354291	0.935135	0.378866	2.639455	1.069364	2.822538	0.0167103	1.4308144	15
46	0.354563	0.935032	0.379199	2.637139	1.069482	2.820373	0.0167521	1.4287896	14
47	0.354835	0.934929	0.379532	2.634827	1.069600	2.818211	0.0167939	1.4267684	13
48	0.355107	0.934826	0.379864	2.632519	1.069718	2.816053	0.0168359	1.4247507	12
49	0.355379	0.934722	0.380197	2.630214	1.069836	2.813898	0.0168779	1.4227366	11
50	0.355651	0.934619	0.380530	2.627912	1.069955	2.811747	0.0169200	1.4207260	10
51	0.355923	0.934515	0.380863	2.625614	1.070073	2.809599	0.0169621	1.4187189	9
52	0.356194	0.934412	0.381196	2.623320	1.070192	2.807455	0.0170044	1.4167153	8
53	0.356466	0.934308	0.381530	2.621029	1.070311	2.805315	0.0170467	1.4147152	7
54	0.356738	0.934204	0.381863	2.618741	1.070429	2.803178	0.0170891	1.4127186	6
55	0.357010	0.934101	0.382196	2.616457	1.070548	2.801044	0.0171315	1.4107255	5
56	0.357281	0.933997	0.382530	2.614177	1.070668	2.798914	0.0171740	1.4087359	4
57	0.357553	0.933893	0.382863	2.611900	1.070787	2.796787	0.0172166	1.4067497	3
58	0.357825	0.933789	0.383197	2.609626	1.070906	2.794664	0.0172593	1.4047670	2
59	0.358096	0.933685	0.383530	2.607356	1.071025	2.792544	0.0173021	1.4027877	1
60	0.358368	0.933580	0.383864	2.605089	1.071145	2.790428	0.0173449	1.4008119	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	69°–70° Involute	Minutes

↑ 110° or 290° 69° or 249° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 21° or 201° Trigonometric and Involute Functions 158° or 338° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 21°–22°	Read Up	Minutes
0	0.358368	0.933580	0.383864	2.605089	1.071145	2.790428	0.0173449	1.4008119	60
1	0.358640	0.933476	0.384198	2.602826	1.071265	2.788315	0.0173878	1.3988395	59
2	0.358911	0.933372	0.384532	2.600566	1.071384	2.786206	0.0174308	1.3968705	58
3	0.359183	0.933267	0.384866	2.598309	1.071504	2.784100	0.0174738	1.3949050	57
4	0.359454	0.933163	0.385200	2.596056	1.071624	2.781997	0.0175169	1.3929428	56
5	0.359725	0.933058	0.385534	2.593807	1.071744	2.779898	0.0175601	1.3909841	55
6	0.359997	0.932954	0.385868	2.591561	1.071865	2.777802	0.0176034	1.3890287	54
7	0.360268	0.932849	0.386202	2.589318	1.071985	2.775710	0.0176468	1.3870768	53
8	0.360540	0.932744	0.386536	2.587078	1.072106	2.773621	0.0176902	1.3851282	52
9	0.360811	0.932639	0.386871	2.584842	1.072226	2.771535	0.0177337	1.3831829	51
10	0.361082	0.932534	0.387205	2.582609	1.072347	2.769453	0.0177773	1.3812411	50
11	0.361353	0.932429	0.387540	2.580380	1.072468	2.767374	0.0178209	1.3793026	49
12	0.361625	0.932324	0.387874	2.578154	1.072589	2.765299	0.0178646	1.3773674	48
13	0.361896	0.932219	0.388209	2.575931	1.072710	2.763227	0.0179084	1.3754356	47
14	0.362167	0.932113	0.388544	2.573712	1.072831	2.761158	0.0179523	1.3735071	46
15	0.362438	0.932008	0.388879	2.571496	1.072952	2.759092	0.0179963	1.3715819	45
16	0.362709	0.931902	0.389214	2.569283	1.073074	2.757030	0.0180403	1.3696600	44
17	0.362980	0.931797	0.389549	2.567074	1.073195	2.754971	0.0180844	1.3677414	43
18	0.363251	0.931691	0.389884	2.564867	1.073317	2.752916	0.0181286	1.3658262	42
19	0.363522	0.931586	0.390219	2.562665	1.073439	2.750863	0.0181728	1.3639142	41
20	0.363793	0.931480	0.390554	2.560465	1.073561	2.748814	0.0182172	1.3620055	40
21	0.364064	0.931374	0.390889	2.558269	1.073683	2.746769	0.0182616	1.3601001	39
22	0.364335	0.931268	0.391225	2.556076	1.073805	2.744726	0.0183061	1.3581979	38
23	0.364606	0.931162	0.391560	2.553886	1.073927	2.742687	0.0183506	1.3562990	37
24	0.364877	0.931056	0.391896	2.551699	1.074049	2.740651	0.0183953	1.3544034	36
25	0.365148	0.930950	0.392231	2.549516	1.074172	2.738619	0.0184400	1.3525110	35
26	0.365418	0.930843	0.392567	2.547336	1.074295	2.736589	0.0184848	1.3506218	34
27	0.365689	0.930737	0.392903	2.545159	1.074417	2.734563	0.0185296	1.3487359	33
28	0.365960	0.930631	0.393239	2.542985	1.074540	2.732540	0.0185746	1.3468532	32
29	0.366231	0.930524	0.393574	2.540815	1.074663	2.730520	0.0186196	1.3449737	31
30	0.366501	0.930418	0.393910	2.538648	1.074786	2.728504	0.0186647	1.3430974	30
31	0.366772	0.930311	0.394247	2.536484	1.074909	2.726491	0.0187099	1.3412243	29
32	0.367042	0.930204	0.394583	2.534323	1.075033	2.724480	0.0187551	1.3393544	28
33	0.367313	0.930097	0.394919	2.532165	1.075156	2.722474	0.0188004	1.3374876	27
34	0.367584	0.929990	0.395255	2.530011	1.075280	2.720470	0.0188458	1.3356241	26
35	0.367854	0.929884	0.395592	2.527860	1.075403	2.718469	0.0188913	1.3337637	25
36	0.368125	0.929776	0.395928	2.525712	1.075527	2.716472	0.0189369	1.3319065	24
37	0.368395	0.929669	0.396265	2.523567	1.075651	2.714478	0.0189825	1.3300524	23
38	0.368665	0.929562	0.396601	2.521425	1.075775	2.712487	0.0190282	1.3282015	22
39	0.368936	0.929455	0.396938	2.519286	1.075899	2.710499	0.0190740	1.3263537	21
40	0.369206	0.929348	0.397275	2.517151	1.076024	2.708514	0.0191199	1.3245091	20
41	0.369476	0.929240	0.397611	2.515018	1.076148	2.706532	0.0191659	1.3226676	19
42	0.369747	0.929133	0.397948	2.512889	1.076273	2.704554	0.0192119	1.3208292	18
43	0.370017	0.929025	0.398285	2.510763	1.076397	2.702578	0.0192580	1.3189939	17
44	0.370287	0.928917	0.398622	2.508640	1.076522	2.700606	0.0193042	1.3171617	16
45	0.370557	0.928810	0.398960	2.506520	1.076647	2.698637	0.0193504	1.3153326	15
46	0.370828	0.928702	0.399297	2.504403	1.076772	2.696671	0.0193968	1.3135066	14
47	0.371098	0.928594	0.399634	2.502289	1.076897	2.694708	0.0194432	1.3116837	13
48	0.371368	0.928486	0.399971	2.500178	1.077022	2.692748	0.0194897	1.3098638	12
49	0.371638	0.928378	0.400309	2.498071	1.077148	2.690791	0.0195363	1.3080470	11
50	0.371908	0.928270	0.400646	2.495966	1.077273	2.688837	0.0195829	1.3062333	10
51	0.372178	0.928161	0.400984	2.493865	1.077399	2.686887	0.0196296	1.3044227	9
52	0.372448	0.928053	0.401322	2.491766	1.077525	2.684939	0.0196765	1.3026150	8
53	0.372718	0.927945	0.401660	2.489671	1.077650	2.682995	0.0197233	1.3008105	7
54	0.372988	0.927836	0.401997	2.487578	1.077776	2.681053	0.0197703	1.2990089	6
55	0.373258	0.927728	0.402335	2.485489	1.077902	2.679114	0.0198174	1.2972104	5
56	0.373528	0.927619	0.402673	2.483402	1.078029	2.677179	0.0198645	1.2954149	4
57	0.373797	0.927510	0.403011	2.481319	1.078155	2.675247	0.0199117	1.2936224	3
58	0.374067	0.927402	0.403350	2.479239	1.078281	2.673317	0.0199590	1.2918329	2
59	0.374337	0.927293	0.403688	2.477161	1.078408	2.671391	0.0200063	1.2900465	1
60	0.374607	0.927184	0.404026	2.475087	1.078535	2.669467	0.0200538	1.2882630	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	68°–69° Involute	Minutes

↑ 111° or 291° 68° or 248° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 22° or 202° Trigonometric and Involute Functions 157° or 337° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 22°–23°	Read Up	Minutes
0	0.374607	0.927184	0.404026	2.475087	1.078535	2.669467	0.0200538	1.2882630	60
1	0.374876	0.927075	0.404365	2.473015	1.078662	2.667547	0.0201013	1.2864825	59
2	0.375146	0.926966	0.404703	2.470947	1.078788	2.665629	0.0201489	1.2847049	58
3	0.375416	0.926857	0.405042	2.468882	1.078916	2.663715	0.0201966	1.2829304	57
4	0.375685	0.926747	0.405380	2.466819	1.079043	2.661803	0.0202444	1.2811588	56
5	0.375955	0.926638	0.405719	2.464760	1.079170	2.659895	0.0202922	1.2793901	55
6	0.376224	0.926529	0.406058	2.462703	1.079297	2.657989	0.0203401	1.2776245	54
7	0.376494	0.926419	0.406397	2.460649	1.079425	2.656086	0.0203881	1.2758617	53
8	0.376763	0.926310	0.406736	2.458599	1.079553	2.654187	0.0204362	1.2741019	52
9	0.377033	0.926200	0.407075	2.456551	1.079680	2.652290	0.0204844	1.2723451	51
10	0.377302	0.926090	0.407414	2.454506	1.079808	2.650396	0.0205326	1.2705911	50
11	0.377571	0.925980	0.407753	2.452464	1.079936	2.648505	0.0205809	1.2688401	49
12	0.377841	0.925871	0.408092	2.450425	1.080065	2.646617	0.0206293	1.2670920	48
13	0.378110	0.925761	0.408432	2.448389	1.080193	2.644732	0.0206778	1.2653468	47
14	0.378379	0.925651	0.408771	2.446356	1.080321	2.642850	0.0207264	1.2636044	46
15	0.378649	0.925541	0.409111	2.444326	1.080450	2.640971	0.0207750	1.2618650	45
16	0.378918	0.925430	0.409450	2.442298	1.080578	2.639095	0.0208238	1.2601285	44
17	0.379187	0.925320	0.409790	2.440274	1.080707	2.637221	0.0208726	1.2583948	43
18	0.379456	0.925210	0.410130	2.438252	1.080836	2.635351	0.0209215	1.2566640	42
19	0.379725	0.925099	0.410470	2.436233	1.080965	2.633483	0.0209704	1.2549361	41
20	0.379994	0.924989	0.410810	2.434217	1.081094	2.631618	0.0210195	1.2532111	40
21	0.380263	0.924878	0.411150	2.432204	1.081223	2.629756	0.0210686	1.2514889	39
22	0.380532	0.924768	0.411490	2.430194	1.081353	2.627897	0.0211178	1.2497695	38
23	0.380801	0.924657	0.411830	2.428186	1.081482	2.626041	0.0211671	1.2480530	37
24	0.381070	0.924546	0.412170	2.426182	1.081612	2.624187	0.0212165	1.2463393	36
25	0.381339	0.924435	0.412511	2.424180	1.081742	2.622337	0.0212660	1.2446284	35
26	0.381608	0.924324	0.412851	2.422181	1.081872	2.620489	0.0213155	1.2429204	34
27	0.381877	0.924213	0.413192	2.420185	1.082002	2.618644	0.0213651	1.2412152	33
28	0.382146	0.924102	0.413532	2.418192	1.082132	2.616802	0.0214148	1.2395127	32
29	0.382415	0.923991	0.413873	2.416201	1.082262	2.614962	0.0214646	1.2378131	31
30	0.382683	0.923880	0.414214	2.414214	1.082392	2.613126	0.0215145	1.2361163	30
31	0.382952	0.923768	0.414554	2.412229	1.082523	2.611292	0.0215644	1.2344223	29
32	0.383221	0.923657	0.414895	2.410247	1.082653	2.609461	0.0216145	1.2327310	28
33	0.383490	0.923545	0.415236	2.408267	1.082784	2.607633	0.0216646	1.2310426	27
34	0.383758	0.923434	0.415577	2.406291	1.082915	2.605808	0.0217148	1.2293569	26
35	0.384027	0.923322	0.415919	2.404317	1.083046	2.603985	0.0217651	1.2276740	25
36	0.384295	0.923210	0.416260	2.402346	1.083177	2.602165	0.0218154	1.2259938	24
37	0.384564	0.923098	0.416601	2.400377	1.083308	2.600348	0.0218659	1.2243164	23
38	0.384832	0.922986	0.416943	2.398412	1.083439	2.598534	0.0219164	1.2226417	22
39	0.385101	0.922875	0.417284	2.396449	1.083571	2.596723	0.0219670	1.2209698	21
40	0.385369	0.922762	0.417626	2.394489	1.083703	2.594914	0.0220177	1.2193006	20
41	0.385638	0.922650	0.417967	2.392532	1.083834	2.593108	0.0220685	1.2176341	19
42	0.385906	0.922538	0.418309	2.390577	1.083966	2.591304	0.0221193	1.2159704	18
43	0.386174	0.922426	0.418651	2.388625	1.084098	2.589504	0.0221703	1.2143093	17
44	0.386443	0.922313	0.418993	2.386676	1.084230	2.587706	0.0222213	1.2126510	16
45	0.386711	0.922201	0.419335	2.384729	1.084362	2.585911	0.0222724	1.2109954	15
46	0.386979	0.922088	0.419677	2.382786	1.084495	2.584118	0.0223236	1.2093425	14
47	0.387247	0.921976	0.420019	2.380844	1.084627	2.582328	0.0223749	1.2076923	13
48	0.387516	0.921863	0.420361	2.378906	1.084760	2.580541	0.0224262	1.2060447	12
49	0.387784	0.921750	0.420704	2.376970	1.084892	2.578757	0.0224777	1.2043999	11
50	0.388052	0.921638	0.421046	2.375037	1.085025	2.576975	0.0225292	1.2027577	10
51	0.388320	0.921525	0.421389	2.373107	1.085158	2.575196	0.0225808	1.2011182	9
52	0.388588	0.921412	0.421731	2.371179	1.085291	2.573420	0.0226325	1.1994814	8
53	0.388856	0.921299	0.422074	2.369254	1.085424	2.571646	0.0226843	1.1978472	7
54	0.389124	0.921185	0.422417	2.367332	1.085558	2.569875	0.0227361	1.1962156	6
55	0.389392	0.921072	0.422759	2.365412	1.085691	2.568107	0.0227881	1.1945867	5
56	0.389660	0.920959	0.423102	2.363495	1.085825	2.566341	0.0228401	1.1929605	4
57	0.389928	0.920845	0.423445	2.361580	1.085959	2.564578	0.0228922	1.1913369	3
58	0.390196	0.920732	0.423788	2.359668	1.086092	2.562818	0.0229444	1.1897159	2
59	0.390463	0.920618	0.424132	2.357759	1.086226	2.561060	0.0229967	1.1880975	1
60	0.390731	0.920505	0.424475	2.355852	1.086360	2.559305	0.0230491	1.1864818	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	67°–68° Involute	Minutes

↑ 112° or 292° 67° or 247° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 23° or 203° Trigonometric and Involute Functions 156° or 336° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 23°–24°	Read Up	Minutes
0	0.390731	0.920505	0.424475	2.355852	1.086360	2.559305	0.0230491	1.1864818	60
1	0.390999	0.920391	0.424818	2.353948	1.086495	2.557552	0.0231015	1.1848686	59
2	0.391267	0.920277	0.425162	2.352047	1.086629	2.555802	0.0231541	1.1832581	58
3	0.391534	0.920164	0.425505	2.350148	1.086763	2.554055	0.0232067	1.1816502	57
4	0.391802	0.920050	0.425849	2.348252	1.086898	2.552310	0.0232594	1.1800448	56
5	0.392070	0.919936	0.426192	2.346358	1.087033	2.550568	0.0233122	1.1784421	55
6	0.392337	0.919821	0.426536	2.344467	1.087167	2.548828	0.0233651	1.1768419	54
7	0.392605	0.919707	0.426880	2.342579	1.087302	2.547091	0.0234181	1.1752443	53
8	0.392872	0.919593	0.427224	2.340693	1.087437	2.545357	0.0234711	1.1736493	52
9	0.393140	0.919479	0.427568	2.338809	1.087573	2.543625	0.0235242	1.1720569	51
10	0.393407	0.919364	0.427912	2.336929	1.087708	2.541896	0.0235775	1.1704670	50
11	0.393675	0.919250	0.428256	2.335050	1.087843	2.540169	0.0236308	1.1688797	49
12	0.393942	0.919135	0.428601	2.333175	1.087979	2.538445	0.0236842	1.1672949	48
13	0.394209	0.919021	0.428945	2.331302	1.088115	2.536724	0.0237376	1.1657126	47
14	0.394477	0.918906	0.429289	2.329431	1.088251	2.535005	0.0237912	1.1641329	46
15	0.394744	0.918791	0.429634	2.327563	1.088387	2.533288	0.0238449	1.1625558	45
16	0.395011	0.918676	0.429979	2.325698	1.088523	2.531574	0.0238986	1.1609811	44
17	0.395278	0.918561	0.430323	2.323835	1.088659	2.529863	0.0239524	1.1594090	43
18	0.395546	0.918446	0.430668	2.321974	1.088795	2.528154	0.0240063	1.1578394	42
19	0.395813	0.918331	0.431013	2.320116	1.088932	2.526448	0.0240603	1.1562723	41
20	0.396080	0.918216	0.431358	2.318261	1.089068	2.524744	0.0241144	1.1547077	40
21	0.396347	0.918101	0.431703	2.316408	1.089205	2.523043	0.0241686	1.1531457	39
22	0.396614	0.917986	0.432048	2.314557	1.089342	2.521344	0.0242228	1.1515861	38
23	0.396881	0.917870	0.432393	2.312709	1.089479	2.519648	0.0242772	1.1500290	37
24	0.397148	0.917755	0.432739	2.310864	1.089616	2.517954	0.0243316	1.1484744	36
25	0.397415	0.917639	0.433084	2.309021	1.089753	2.516262	0.0243861	1.1469222	35
26	0.397682	0.917523	0.433430	2.307180	1.089890	2.514574	0.0244407	1.1453726	34
27	0.397949	0.917408	0.433775	2.305342	1.090028	2.512887	0.0244954	1.1438254	33
28	0.398215	0.917292	0.434121	2.303506	1.090166	2.511203	0.0245502	1.1422807	32
29	0.398482	0.917176	0.434467	2.301673	1.090303	2.509522	0.0246050	1.1407384	31
30	0.398749	0.917060	0.434812	2.299843	1.090441	2.507843	0.0246600	1.1391986	30
31	0.399016	0.916944	0.435158	2.298014	1.090579	2.506166	0.0247150	1.1376612	29
32	0.399283	0.916828	0.435504	2.296188	1.090717	2.504492	0.0247702	1.1361263	28
33	0.399549	0.916712	0.435850	2.294365	1.090855	2.502821	0.0248254	1.1345938	27
34	0.399816	0.916595	0.436197	2.292544	1.090994	2.501151	0.0248807	1.1330638	26
35	0.400082	0.916479	0.436543	2.290726	1.091132	2.499485	0.0249361	1.1315361	25
36	0.400349	0.916363	0.436889	2.288910	1.091271	2.497820	0.0249916	1.1300109	24
37	0.400616	0.916246	0.437236	2.287096	1.091410	2.496159	0.0250471	1.1284882	23
38	0.400882	0.916130	0.437582	2.285285	1.091549	2.494499	0.0251028	1.1269678	22
39	0.401149	0.916013	0.437929	2.283476	1.091688	2.492842	0.0251585	1.1254498	21
40	0.401415	0.915896	0.438276	2.281669	1.091827	2.491187	0.0252143	1.1239342	20
41	0.401681	0.915779	0.438622	2.279865	1.091966	2.489535	0.0252703	1.1224211	19
42	0.401948	0.915663	0.438969	2.278064	1.092105	2.487885	0.0253263	1.1209103	18
43	0.402214	0.915546	0.439316	2.276264	1.092245	2.486238	0.0253824	1.1194019	17
44	0.402480	0.915429	0.439663	2.274467	1.092384	2.484593	0.0254386	1.1178959	16
45	0.402747	0.915311	0.440011	2.272673	1.092524	2.482950	0.0254948	1.1163922	15
46	0.403013	0.915194	0.440358	2.270881	1.092664	2.481310	0.0255512	1.1148910	14
47	0.403279	0.915077	0.440705	2.269091	1.092804	2.479672	0.0256076	1.1133921	13
48	0.403545	0.914960	0.441053	2.267304	1.092944	2.478037	0.0256642	1.1118955	12
49	0.403811	0.914842	0.441400	2.265518	1.093085	2.476403	0.0257208	1.1104014	11
50	0.404078	0.914725	0.441748	2.263736	1.093225	2.474773	0.0257775	1.1089095	10
51	0.404344	0.914607	0.442095	2.261955	1.093366	2.473144	0.0258343	1.1074201	9
52	0.404610	0.914490	0.442443	2.260177	1.093506	2.471518	0.0258912	1.1059329	8
53	0.404876	0.914372	0.442791	2.258402	1.093647	2.469894	0.0259482	1.1044481	7
54	0.405142	0.914254	0.443139	2.256628	1.093788	2.468273	0.0260053	1.1029656	6
55	0.405408	0.914136	0.443487	2.254857	1.093929	2.466654	0.0260625	1.1014855	5
56	0.405673	0.914018	0.443835	2.253089	1.094070	2.465037	0.0261197	1.1000077	4
57	0.405939	0.913900	0.444183	2.251322	1.094212	2.463423	0.0261771	1.0985321	3
58	0.406205	0.913782	0.444532	2.249558	1.094353	2.461811	0.0262345	1.0970589	2
59	0.406471	0.913664	0.444880	2.247796	1.094495	2.460201	0.0262920	1.0955881	1
60	0.406737	0.913545	0.445229	2.246037	1.094636	2.458593	0.0263497	1.0941195	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	66°–67° Involute	Minutes

↑ 113° or 293° 66° or 246° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 24° or 204° Trigonometric and Involute Functions 155° or 335° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 24°–25°	Read Up	Minutes
0	0.406737	0.913545	0.445229	2.246037	1.094636	2.458593	0.0263497	1.0941195	60
1	0.407002	0.913427	0.445577	2.244280	1.094778	2.456988	0.0264074	1.0926532	59
2	0.407268	0.913309	0.445926	2.242525	1.094920	2.455385	0.0264652	1.0911892	58
3	0.407534	0.913190	0.446275	2.240772	1.095062	2.453785	0.0265231	1.0897275	57
4	0.407799	0.913072	0.446624	2.239022	1.095204	2.452186	0.0265810	1.0882680	56
5	0.408065	0.912953	0.446973	2.237274	1.095347	2.450591	0.0266391	1.0868109	55
6	0.408330	0.912834	0.447322	2.235528	1.095489	2.448997	0.0266973	1.0853560	54
7	0.408596	0.912715	0.447671	2.233785	1.095632	2.447405	0.0267555	1.0839034	53
8	0.408861	0.912596	0.448020	2.232043	1.095775	2.445816	0.0268139	1.0824531	52
9	0.409127	0.912477	0.448369	2.230304	1.095917	2.444229	0.0268723	1.0810050	51
10	0.409392	0.912358	0.448719	2.228568	1.096060	2.442645	0.0269308	1.0795592	50
11	0.409658	0.912239	0.449068	2.226833	1.096204	2.441062	0.0269894	1.0781156	49
12	0.409923	0.912120	0.449418	2.225101	1.096347	2.439482	0.0270481	1.0766743	48
13	0.410188	0.912001	0.449768	2.223371	1.096490	2.437904	0.0271069	1.0752352	47
14	0.410454	0.911881	0.450117	2.221643	1.096634	2.436329	0.0271658	1.0737983	46
15	0.410719	0.911762	0.450467	2.219918	1.096777	2.434756	0.0272248	1.0723637	45
16	0.410984	0.911643	0.450817	2.218194	1.096921	2.433184	0.0272839	1.0709313	44
17	0.411249	0.911523	0.451167	2.216473	1.097065	2.431616	0.0273430	1.0695011	43
18	0.411514	0.911403	0.451517	2.214754	1.097209	2.430049	0.0274023	1.0680732	42
19	0.411779	0.911284	0.451868	2.213038	1.097353	2.428484	0.0274617	1.0666474	41
20	0.412045	0.911164	0.452218	2.211323	1.097498	2.426922	0.0275211	1.0652239	40
21	0.412310	0.911044	0.452568	2.209611	1.097642	2.425362	0.0275806	1.0638026	39
22	0.412575	0.910924	0.452919	2.207901	1.097787	2.423804	0.0276403	1.0623835	38
23	0.412840	0.910804	0.453269	2.206193	1.097931	2.422249	0.0277000	1.0609665	37
24	0.413104	0.910684	0.453620	2.204488	1.098076	2.420695	0.0277598	1.0595518	36
25	0.413369	0.910563	0.453971	2.202784	1.098221	2.419144	0.0278197	1.0581392	35
26	0.413634	0.910443	0.454322	2.201083	1.098366	2.417595	0.0278797	1.0567288	34
27	0.413899	0.910323	0.454673	2.199384	1.098511	2.416048	0.0279398	1.0553206	33
28	0.414164	0.910202	0.455024	2.197687	1.098657	2.414504	0.0279999	1.0539146	32
29	0.414429	0.910082	0.455375	2.195992	1.098802	2.412961	0.0280602	1.0525108	31
30	0.414693	0.909961	0.455726	2.194300	1.098948	2.411421	0.0281206	1.0511091	30
31	0.414958	0.909841	0.456078	2.192609	1.099094	2.409883	0.0281810	1.0497095	29
32	0.415223	0.909720	0.456429	2.190921	1.099239	2.408347	0.0282416	1.0483122	28
33	0.415487	0.909599	0.456781	2.189235	1.099386	2.406813	0.0283022	1.0469169	27
34	0.415752	0.909478	0.457132	2.187551	1.099532	2.405282	0.0283630	1.0455238	26
35	0.416016	0.909357	0.457484	2.185869	1.099678	2.403752	0.0284238	1.0441329	25
36	0.416281	0.909236	0.457836	2.184189	1.099824	2.402225	0.0284847	1.0427441	24
37	0.416545	0.909115	0.458188	2.182512	1.099971	2.400700	0.0285458	1.0413574	23
38	0.416810	0.908994	0.458540	2.180836	1.100118	2.399176	0.0286069	1.0399729	22
39	0.417074	0.908872	0.458892	2.179163	1.100264	2.397656	0.0286681	1.0385905	21
40	0.417338	0.908751	0.459244	2.177492	1.100411	2.396137	0.0287294	1.0372102	20
41	0.417603	0.908630	0.459596	2.175823	1.100558	2.394620	0.0287908	1.0358320	19
42	0.417867	0.908508	0.459949	2.174156	1.100706	2.393106	0.0288523	1.0344559	18
43	0.418131	0.908387	0.460301	2.172491	1.100853	2.391593	0.0289139	1.0330820	17
44	0.418396	0.908265	0.460654	2.170828	1.101000	2.390083	0.0289756	1.0317101	16
45	0.418660	0.908143	0.461006	2.169168	1.101148	2.388575	0.0290373	1.0303403	15
46	0.418924	0.908021	0.461359	2.167509	1.101296	2.387068	0.0290992	1.0289727	14
47	0.419188	0.907899	0.461712	2.165853	1.101444	2.385564	0.0291612	1.0276071	13
48	0.419452	0.907777	0.462065	2.164198	1.101592	2.384063	0.0292232	1.0262436	12
49	0.419716	0.907655	0.462418	2.162546	1.101740	2.382563	0.0292854	1.0248822	11
50	0.419980	0.907533	0.462771	2.160896	1.101888	2.381065	0.0293476	1.0235229	10
51	0.420244	0.907411	0.463124	2.159248	1.102036	2.379569	0.0294100	1.0221656	9
52	0.420508	0.907289	0.463478	2.157602	1.102185	2.378076	0.0294724	1.0208104	8
53	0.420772	0.907166	0.463831	2.155958	1.102334	2.376584	0.0295349	1.0194573	7
54	0.421036	0.907044	0.464185	2.154316	1.102482	2.375095	0.0295976	1.0181062	6
55	0.421300	0.906922	0.464538	2.152676	1.102631	2.373608	0.0296603	1.0167572	5
56	0.421563	0.906799	0.464892	2.151038	1.102780	2.372122	0.0297231	1.0154103	4
57	0.421827	0.906676	0.465246	2.149402	1.102930	2.370639	0.0297860	1.0140654	3
58	0.422091	0.906554	0.465600	2.147768	1.103079	2.369158	0.0298490	1.0127225	2
59	0.422355	0.906431	0.465954	2.146137	1.103228	2.367679	0.0299121	1.0113817	1
60	0.422618	0.906308	0.466308	2.144507	1.103378	2.366202	0.0299753	1.0100429	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	65°–66° Involute	Minutes

↑ 114° or 294° 65° or 245° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 25° or 205° Trigonometric and Involute Functions 154° or 334° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 25°–26°	Read Up	Minutes
0	0.422618	0.906308	0.466308	2.144507	1.103378	2.366202	0.0299753	1.0100429	60
1	0.422882	0.906185	0.466662	2.142879	1.103528	2.364727	0.0300386	1.0087062	59
2	0.423145	0.906062	0.467016	2.141254	1.103678	2.363254	0.0301020	1.0073714	58
3	0.423409	0.905939	0.467371	2.139630	1.103828	2.361783	0.0301655	1.0060387	57
4	0.423673	0.905815	0.467725	2.138009	1.103978	2.360314	0.0302291	1.0047080	56
5	0.423936	0.905692	0.468080	2.136389	1.104128	2.358847	0.0302928	1.0033794	55
6	0.424199	0.905569	0.468434	2.134771	1.104278	2.357382	0.0303566	1.0020527	54
7	0.424463	0.905445	0.468789	2.133156	1.104429	2.355919	0.0304205	1.0007281	53
8	0.424726	0.905322	0.469144	2.131542	1.104580	2.354458	0.0304844	0.9994054	52
9	0.424990	0.905198	0.469499	2.129931	1.104730	2.352999	0.0305485	0.9980848	51
10	0.425253	0.905075	0.469854	2.128321	1.104881	2.351542	0.0306127	0.9967661	50
11	0.425516	0.904951	0.470209	2.126714	1.105032	2.350088	0.0306769	0.9954495	49
12	0.425779	0.904827	0.470564	2.125108	1.105184	2.348635	0.0307413	0.9941348	48
13	0.426042	0.904703	0.470920	2.123505	1.105335	2.347184	0.0308058	0.9928221	47
14	0.426306	0.904579	0.471275	2.121903	1.105486	2.345735	0.0308703	0.9915114	46
15	0.426569	0.904455	0.471631	2.120303	1.105638	2.344288	0.0309350	0.9902027	45
16	0.426832	0.904331	0.471986	2.118706	1.105790	2.342843	0.0309997	0.9888959	44
17	0.427095	0.904207	0.472342	2.117110	1.105942	2.341400	0.0310646	0.9875912	43
18	0.427358	0.904083	0.472698	2.115516	1.106094	2.339959	0.0311295	0.9862883	42
19	0.427621	0.903958	0.473054	2.113925	1.106246	2.338520	0.0311946	0.9849875	41
20	0.427884	0.903834	0.473410	2.112335	1.106398	2.337083	0.0312597	0.9836886	40
21	0.428147	0.903709	0.473766	2.110747	1.106551	2.335648	0.0313250	0.9823916	39
22	0.428410	0.903585	0.474122	2.109161	1.106703	2.334215	0.0313903	0.9810966	38
23	0.428672	0.903460	0.474478	2.107577	1.106856	2.332784	0.0314557	0.9798035	37
24	0.428935	0.903335	0.474835	2.105995	1.107009	2.331355	0.0315213	0.9785124	36
25	0.429198	0.903210	0.475191	2.104415	1.107162	2.329928	0.0315869	0.9772232	35
26	0.429461	0.903086	0.475548	2.102837	1.107315	2.328502	0.0316527	0.9759360	34
27	0.429723	0.902961	0.475905	2.101261	1.107468	2.327079	0.0317185	0.9746507	33
28	0.429986	0.902836	0.476262	2.099686	1.107621	2.325658	0.0317844	0.9733673	32
29	0.430249	0.902710	0.476619	2.098114	1.107775	2.324238	0.0318504	0.9720858	31
30	0.430511	0.902585	0.476976	2.096544	1.107929	2.322820	0.0319166	0.9708062	30
31	0.430774	0.902460	0.477333	2.094975	1.108082	2.321405	0.0319828	0.9695286	29
32	0.431036	0.902335	0.477690	2.093408	1.108236	2.319991	0.0320491	0.9682529	28
33	0.431299	0.902209	0.478047	2.091844	1.108390	2.318579	0.0321156	0.9669790	27
34	0.431561	0.902084	0.478405	2.090281	1.108545	2.317169	0.0321821	0.9657071	26
35	0.431823	0.901958	0.478762	2.088720	1.108699	2.315761	0.0322487	0.9644371	25
36	0.432086	0.901833	0.479120	2.087161	1.108853	2.314355	0.0323154	0.9631690	24
37	0.432348	0.901707	0.479477	2.085604	1.109008	2.312951	0.0323823	0.9619027	23
38	0.432610	0.901581	0.479835	2.084049	1.109163	2.311549	0.0324492	0.9606384	22
39	0.432873	0.901455	0.480193	2.082495	1.109318	2.310149	0.0325162	0.9593759	21
40	0.433135	0.901329	0.480551	2.080944	1.109473	2.308750	0.0325833	0.9581153	20
41	0.433397	0.901203	0.480909	2.079394	1.109628	2.307354	0.0326506	0.9568566	19
42	0.433659	0.901077	0.481267	2.077847	1.109783	2.305959	0.0327179	0.9555998	18
43	0.433921	0.900951	0.481626	2.076301	1.109938	2.304566	0.0327853	0.9543449	17
44	0.434183	0.900825	0.481984	2.074757	1.110094	2.303175	0.0328528	0.9530918	16
45	0.434445	0.900698	0.482343	2.073215	1.110250	2.301786	0.0329205	0.9518405	15
46	0.434707	0.900572	0.482701	2.071674	1.110406	2.300399	0.0329882	0.9505912	14
47	0.434969	0.900445	0.483060	2.070136	1.110562	2.299013	0.0330560	0.9493436	13
48	0.435231	0.900319	0.483419	2.068599	1.110718	2.297630	0.0331239	0.9480980	12
49	0.435493	0.900192	0.483778	2.067065	1.110874	2.296248	0.0331920	0.9468542	11
50	0.435755	0.900065	0.484137	2.065532	1.111030	2.294869	0.0332601	0.9456122	10
51	0.436017	0.899939	0.484496	2.064001	1.111187	2.293491	0.0333283	0.9443721	9
52	0.436278	0.899812	0.484855	2.062472	1.111344	2.292115	0.0333967	0.9431338	8
53	0.436540	0.899685	0.485214	2.060944	1.111500	2.290740	0.0334651	0.9418973	7
54	0.436802	0.899558	0.485574	2.059419	1.111657	2.289368	0.0335336	0.9406627	6
55	0.437063	0.899431	0.485933	2.057895	1.111814	2.287997	0.0336023	0.9394299	5
56	0.437325	0.899304	0.486293	2.056373	1.111972	2.286629	0.0336710	0.9381989	4
57	0.437587	0.899176	0.486653	2.054853	1.112129	2.285262	0.0337399	0.9369697	3
58	0.437848	0.899049	0.487013	2.053335	1.112287	2.283897	0.0338088	0.9357424	2
59	0.438110	0.898922	0.487373	2.051818	1.112444	2.282533	0.0338778	0.9345168	1
60	0.438371	0.898794	0.487733	2.050304	1.112602	2.281172	0.0339470	0.9332931	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	64°–65° Involute	Minutes

↑ 115° or 295° 64° or 244° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 26° or 206° Trigonometric and Involute Functions 153° or 333° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 26°–27°	Read Up	Minutes
0	0.438371	0.898794	0.487733	2.050304	1.112602	2.281172	0.0339470	0.9332931	60
1	0.438633	0.898666	0.488093	2.048791	1.112760	2.279812	0.0340162	0.9320712	59
2	0.438894	0.898539	0.488453	2.047280	1.112918	2.278455	0.0340856	0.9308511	58
3	0.439155	0.898411	0.488813	2.045771	1.113076	2.277099	0.0341550	0.9296328	57
4	0.439417	0.898283	0.489174	2.044263	1.113234	2.275744	0.0342246	0.9284162	56
5	0.439678	0.898156	0.489534	2.042758	1.113393	2.274392	0.0342942	0.9272015	55
6	0.439939	0.898028	0.489895	2.041254	1.113552	2.273042	0.0343640	0.9259886	54
7	0.440200	0.897900	0.490256	2.039752	1.113710	2.271693	0.0344339	0.9247774	53
8	0.440462	0.897771	0.490617	2.038252	1.113869	2.270346	0.0345038	0.9235680	52
9	0.440723	0.897643	0.490978	2.036753	1.114028	2.269001	0.0345739	0.9223604	51
10	0.440984	0.897515	0.491339	2.035256	1.114187	2.267657	0.0346441	0.9211546	50
11	0.441245	0.897387	0.491700	2.033762	1.114347	2.266315	0.0347144	0.9199506	49
12	0.441506	0.897258	0.492061	2.032268	1.114506	2.264976	0.0347847	0.9187483	48
13	0.441767	0.897130	0.492422	2.030777	1.114666	2.263638	0.0348552	0.9175478	47
14	0.442028	0.897001	0.492784	2.029287	1.114826	2.262301	0.0349258	0.9163490	46
15	0.442289	0.896873	0.493145	2.027799	1.114985	2.260967	0.0349965	0.9151520	45
16	0.442550	0.896744	0.493507	2.026313	1.115145	2.259634	0.0350673	0.9139568	44
17	0.442810	0.896615	0.493869	2.024829	1.115306	2.258303	0.0351382	0.9127633	43
18	0.443071	0.896486	0.494231	2.023346	1.115466	2.256974	0.0352092	0.9115715	42
19	0.443332	0.896358	0.494593	2.021865	1.115626	2.255646	0.0352803	0.9103815	41
20	0.443593	0.896229	0.494955	2.020386	1.115787	2.254320	0.0353515	0.9091932	40
21	0.443853	0.896099	0.495317	2.018909	1.115948	2.252996	0.0354228	0.9080067	39
22	0.444114	0.895970	0.495679	2.017433	1.116108	2.251674	0.0354942	0.9068219	38
23	0.444375	0.895841	0.496042	2.015959	1.116269	2.250354	0.0355658	0.9056389	37
24	0.444635	0.895712	0.496404	2.014487	1.116431	2.249035	0.0356374	0.9044575	36
25	0.444896	0.895582	0.496767	2.013016	1.116592	2.247718	0.0357091	0.9032779	35
26	0.445156	0.895453	0.497130	2.011548	1.116753	2.246402	0.0357810	0.9021000	34
27	0.445417	0.895323	0.497492	2.010081	1.116915	2.245089	0.0358529	0.9009239	33
28	0.445677	0.895194	0.497855	2.008615	1.117077	2.243777	0.0359249	0.8997494	32
29	0.445937	0.895064	0.498218	2.007152	1.117238	2.242467	0.0359971	0.8985767	31
30	0.446198	0.894934	0.498582	2.005690	1.117400	2.241158	0.0360694	0.8974056	30
31	0.446458	0.894805	0.498945	2.004229	1.117563	2.239852	0.0361417	0.8962363	29
32	0.446718	0.894675	0.499308	2.002771	1.117725	2.238547	0.0362142	0.8950687	28
33	0.446979	0.894545	0.499672	2.001314	1.117887	2.237243	0.0362868	0.8939027	27
34	0.447239	0.894415	0.500035	1.999859	1.118050	2.235942	0.0363594	0.8927385	26
35	0.447499	0.894284	0.500399	1.998406	1.118212	2.234642	0.0364322	0.8915760	25
36	0.447759	0.894154	0.500763	1.996954	1.118375	2.233344	0.0365051	0.8904151	24
37	0.448019	0.894024	0.501127	1.995504	1.118538	2.232047	0.0365781	0.8892559	23
38	0.448279	0.893894	0.501491	1.994055	1.118701	2.230753	0.0366512	0.8880985	22
39	0.448539	0.893763	0.501855	1.992609	1.118865	2.229459	0.0367244	0.8869426	21
40	0.448799	0.893633	0.502219	1.991164	1.119028	2.228168	0.0367977	0.8857885	20
41	0.449059	0.893502	0.502583	1.989720	1.119192	2.226878	0.0368712	0.8846361	19
42	0.449319	0.893371	0.502948	1.988279	1.119355	2.225590	0.0369447	0.8834853	18
43	0.449579	0.893241	0.503312	1.986839	1.119519	2.224304	0.0370183	0.8823361	17
44	0.449839	0.893110	0.503677	1.985400	1.119683	2.223019	0.0370921	0.8811887	16
45	0.450098	0.892979	0.504041	1.983964	1.119847	2.221736	0.0371659	0.8800429	15
46	0.450358	0.892848	0.504406	1.982529	1.120011	2.220455	0.0372399	0.8788988	14
47	0.450618	0.892717	0.504771	1.981095	1.120176	2.219175	0.0373139	0.8777563	13
48	0.450878	0.892586	0.505136	1.979664	1.120340	2.217897	0.0373881	0.8766154	12
49	0.451137	0.892455	0.505502	1.978233	1.120505	2.216621	0.0374624	0.8754762	11
50	0.451397	0.892323	0.505867	1.976805	1.120670	2.215346	0.0375368	0.8743387	10
51	0.451656	0.892192	0.506232	1.975378	1.120835	2.214073	0.0376113	0.8732028	9
52	0.451916	0.892061	0.506598	1.973953	1.121000	2.212802	0.0376859	0.8720685	8
53	0.452175	0.891929	0.506963	1.972530	1.121165	2.211532	0.0377606	0.8709359	7
54	0.452435	0.891798	0.507329	1.971108	1.121331	2.210264	0.0378354	0.8698049	6
55	0.452694	0.891666	0.507695	1.969687	1.121496	2.208997	0.0379103	0.8686756	5
56	0.452953	0.891534	0.508061	1.968269	1.121662	2.207732	0.0379853	0.8675478	4
57	0.453213	0.891402	0.508427	1.966852	1.121828	2.206469	0.0380605	0.8664217	3
58	0.453472	0.891270	0.508793	1.965436	1.121994	2.205208	0.0381357	0.8652972	2
59	0.453731	0.891139	0.509159	1.964023	1.122160	2.203948	0.0382111	0.8641743	1
60	0.453990	0.891007	0.509525	1.962611	1.122326	2.202689	0.0382866	0.8630531	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	63°–64° Involute	Minutes

↑ 116° or 296° 63° or 243° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 27° or 207° Trigonometric and Involute Functions 152° or 332° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 27°–28°	Read Up	Minutes
0	0.453990	0.891007	0.509525	1.962611	1.122326	2.202689	0.0382866	0.8630531	60
1	0.454250	0.890874	0.509892	1.961200	1.122493	2.201433	0.0383621	0.8619334	59
2	0.454509	0.890742	0.510258	1.959791	1.122659	2.200177	0.0384378	0.8608154	58
3	0.454768	0.890610	0.510625	1.958384	1.122826	2.198924	0.0385136	0.8596990	57
4	0.455027	0.890478	0.510992	1.956978	1.122993	2.197672	0.0385895	0.8585841	56
5	0.455286	0.890345	0.511359	1.955574	1.123160	2.196422	0.0386655	0.8574709	55
6	0.455545	0.890213	0.511726	1.954171	1.123327	2.195173	0.0387416	0.8563592	54
7	0.455804	0.890080	0.512093	1.952770	1.123494	2.193926	0.0388179	0.8552492	53
8	0.456063	0.889948	0.512460	1.951371	1.123662	2.192681	0.0388942	0.8541408	52
9	0.456322	0.889815	0.512828	1.949973	1.123829	2.191437	0.0389706	0.8530339	51
10	0.456580	0.889682	0.513195	1.948577	1.123997	2.190195	0.0390472	0.8519286	50
11	0.456839	0.889549	0.513563	1.947183	1.124165	2.188954	0.0391239	0.8508249	49
12	0.457098	0.889416	0.513930	1.945790	1.124333	2.187715	0.0392006	0.8497228	48
13	0.457357	0.889283	0.514298	1.944398	1.124501	2.186478	0.0392775	0.8486222	47
14	0.457615	0.889150	0.514666	1.943008	1.124669	2.185242	0.0393545	0.8475233	46
15	0.457874	0.889017	0.515034	1.941620	1.124838	2.184007	0.0394316	0.8464259	45
16	0.458133	0.888884	0.515402	1.940233	1.125006	2.182775	0.0395088	0.8453300	44
17	0.458391	0.888751	0.515770	1.938848	1.125175	2.181543	0.0395862	0.8442358	43
18	0.458650	0.888617	0.516138	1.937465	1.125344	2.180314	0.0396636	0.8431431	42
19	0.458908	0.888484	0.516507	1.936082	1.125513	2.179086	0.0397411	0.8420519	41
20	0.459166	0.888350	0.516875	1.934702	1.125682	2.177859	0.0398188	0.8409623	40
21	0.459425	0.888217	0.517244	1.933323	1.125851	2.176635	0.0398966	0.8398743	39
22	0.459683	0.888083	0.517613	1.931946	1.126021	2.175411	0.0399745	0.8387878	38
23	0.459942	0.887949	0.517982	1.930570	1.126191	2.174189	0.0400524	0.8377029	37
24	0.460200	0.887815	0.518351	1.929196	1.126360	2.172969	0.0401306	0.8366195	36
25	0.460458	0.887681	0.518720	1.927823	1.126530	2.171751	0.0402088	0.8355376	35
26	0.460716	0.887548	0.519089	1.926452	1.126700	2.170534	0.0402871	0.8344573	34
27	0.460974	0.887413	0.519458	1.925082	1.126870	2.169318	0.0403655	0.8333785	33
28	0.461232	0.887279	0.519828	1.923714	1.127041	2.168104	0.0404441	0.8323013	32
29	0.461491	0.887145	0.520197	1.922347	1.127211	2.166892	0.0405227	0.8312255	31
30	0.461749	0.887011	0.520567	1.920982	1.127382	2.165681	0.0406015	0.8301513	30
31	0.462007	0.886876	0.520937	1.919619	1.127553	2.164471	0.0406804	0.8290787	29
32	0.462265	0.886742	0.521307	1.918257	1.127724	2.163263	0.0407594	0.8280075	28
33	0.462523	0.886608	0.521677	1.916896	1.127895	2.162057	0.0408385	0.8269379	27
34	0.462780	0.886473	0.522047	1.915537	1.128066	2.160852	0.0409177	0.8258698	26
35	0.463038	0.886338	0.522417	1.914180	1.128237	2.159649	0.0409970	0.8248032	25
36	0.463296	0.886204	0.522787	1.912824	1.128409	2.158447	0.0410765	0.8237381	24
37	0.463554	0.886069	0.523158	1.911469	1.128581	2.157247	0.0411561	0.8226745	23
38	0.463812	0.885934	0.523528	1.910116	1.128752	2.156048	0.0412357	0.8216125	22
39	0.464069	0.885799	0.523899	1.908765	1.128924	2.154851	0.0413155	0.8205519	21
40	0.464327	0.885664	0.524270	1.907415	1.129096	2.153655	0.0413954	0.8194928	20
41	0.464584	0.885529	0.524641	1.906066	1.129269	2.152461	0.0414754	0.8184353	19
42	0.464842	0.885394	0.525012	1.904719	1.129441	2.151268	0.0415555	0.8173792	18
43	0.465100	0.885258	0.525383	1.903374	1.129614	2.150077	0.0416358	0.8163246	17
44	0.465357	0.885123	0.525754	1.902030	1.129786	2.148888	0.0417161	0.8152715	16
45	0.465615	0.884988	0.526125	1.900687	1.129959	2.147699	0.0417966	0.8142199	15
46	0.465872	0.884852	0.526497	1.899346	1.130132	2.146513	0.0418772	0.8131698	14
47	0.466129	0.884717	0.526868	1.898007	1.130305	2.145327	0.0419579	0.8121211	13
48	0.466387	0.884581	0.527240	1.896669	1.130479	2.144144	0.0420387	0.8110740	12
49	0.466644	0.884445	0.527612	1.895332	1.130652	2.142962	0.0421196	0.8100283	11
50	0.466901	0.884309	0.527984	1.893997	1.130826	2.141781	0.0422006	0.8089841	10
51	0.467158	0.884174	0.528356	1.892663	1.131000	2.140602	0.0422818	0.8079413	9
52	0.467416	0.884038	0.528728	1.891331	1.131173	2.139424	0.0423630	0.8069000	8
53	0.467673	0.883902	0.529100	1.890001	1.131348	2.138247	0.0424444	0.8058602	7
54	0.467930	0.883766	0.529473	1.888671	1.131522	2.137073	0.0425259	0.8048219	6
55	0.468187	0.883629	0.529845	1.887344	1.131696	2.135899	0.0426075	0.8037850	5
56	0.468444	0.883493	0.530218	1.886017	1.131871	2.134727	0.0426892	0.8027495	4
57	0.468701	0.883357	0.530591	1.884692	1.132045	2.133557	0.0427710	0.8017156	3
58	0.468958	0.883221	0.530963	1.883369	1.132220	2.132388	0.0428530	0.8006830	2
59	0.469215	0.883084	0.531336	1.882047	1.132395	2.131221	0.0429351	0.7996520	1
60	0.469472	0.882948	0.531709	1.880726	1.132570	2.130054	0.0430172	0.7986223	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	62°–63° Involute	Minutes

↑ 117° or 297° 62° or 242° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 28° or 208° Trigonometric and Involute Functions 151° or 331° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 28°–29°	Read Up	Minutes
0	0.469472	0.882948	0.531709	1.880726	1.132570	2.130054	0.0430172	0.7986223	60
1	0.469728	0.882811	0.532083	1.879407	1.132745	2.128890	0.0430995	0.7975941	59
2	0.469985	0.882674	0.532456	1.878090	1.132921	2.127727	0.0431819	0.7965674	58
3	0.470242	0.882538	0.532829	1.876774	1.133096	2.126565	0.0432645	0.7955421	57
4	0.470499	0.882401	0.533203	1.875459	1.133272	2.125405	0.0433471	0.7945182	56
5	0.470755	0.882264	0.533577	1.874145	1.133448	2.124246	0.0434299	0.7934958	55
6	0.471012	0.882127	0.533950	1.872834	1.133624	2.123089	0.0435128	0.7924748	54
7	0.471268	0.881990	0.534324	1.871523	1.133800	2.121933	0.0435957	0.7914552	53
8	0.471525	0.881853	0.534698	1.870214	1.133976	2.120778	0.0436789	0.7904370	52
9	0.471782	0.881715	0.535072	1.868906	1.134153	2.119625	0.0437621	0.7894203	51
10	0.472038	0.881578	0.535446	1.867600	1.134329	2.118474	0.0438454	0.7884050	50
11	0.472294	0.881441	0.535821	1.866295	1.134506	2.117324	0.0439289	0.7873911	49
12	0.472551	0.881303	0.536195	1.864992	1.134683	2.116175	0.0440124	0.7863786	48
13	0.472807	0.881166	0.536570	1.863690	1.134860	2.115027	0.0440961	0.7853676	47
14	0.473063	0.881028	0.536945	1.862390	1.135037	2.113882	0.0441799	0.7843579	46
15	0.473320	0.880891	0.537319	1.861091	1.135215	2.112737	0.0442639	0.7833497	45
16	0.473576	0.880753	0.537694	1.859793	1.135392	2.111594	0.0443479	0.7823429	44
17	0.473832	0.880615	0.538069	1.858496	1.135570	2.110452	0.0444321	0.7813374	43
18	0.474088	0.880477	0.538445	1.857202	1.135748	2.109312	0.0445163	0.7803334	42
19	0.474344	0.880339	0.538820	1.855908	1.135926	2.108173	0.0446007	0.7793308	41
20	0.474600	0.880201	0.539195	1.854616	1.136104	2.107036	0.0446853	0.7783295	40
21	0.474856	0.880063	0.539571	1.853325	1.136282	2.105900	0.0447699	0.7773297	39
22	0.475112	0.879925	0.539946	1.852036	1.136460	2.104765	0.0448546	0.7763312	38
23	0.475368	0.879787	0.540322	1.850748	1.136639	2.103632	0.0449395	0.7753342	37
24	0.475624	0.879649	0.540698	1.849461	1.136818	2.102500	0.0450245	0.7743385	36
25	0.475880	0.879510	0.541074	1.848176	1.136997	2.101370	0.0451096	0.7733442	35
26	0.476136	0.879372	0.541450	1.846892	1.137176	2.100241	0.0451948	0.7723513	34
27	0.476392	0.879233	0.541826	1.845610	1.137355	2.099113	0.0452801	0.7713598	33
28	0.476647	0.879095	0.542203	1.844329	1.137534	2.097987	0.0453656	0.7703696	32
29	0.476903	0.878956	0.542579	1.843049	1.137714	2.096862	0.0454512	0.7693808	31
30	0.477159	0.878817	0.542956	1.841771	1.137893	2.095739	0.0455369	0.7683934	30
31	0.477414	0.878678	0.543332	1.840494	1.138073	2.094616	0.0456227	0.7674074	29
32	0.477670	0.878539	0.543709	1.839218	1.138253	2.093496	0.0457086	0.7664227	28
33	0.477925	0.878400	0.544086	1.837944	1.138433	2.092376	0.0457947	0.7654394	27
34	0.478181	0.878261	0.544463	1.836671	1.138613	2.091258	0.0458808	0.7644574	26
35	0.478436	0.878122	0.544840	1.835400	1.138794	2.090142	0.0459671	0.7634768	25
36	0.478692	0.877983	0.545218	1.834130	1.138974	2.089027	0.0460535	0.7624976	24
37	0.478947	0.877844	0.545595	1.832861	1.139155	2.087913	0.0461401	0.7615197	23
38	0.479203	0.877704	0.545973	1.831594	1.139336	2.086800	0.0462267	0.7605432	22
39	0.479458	0.877565	0.546350	1.830327	1.139517	2.085689	0.0463135	0.7595680	21
40	0.479713	0.877425	0.546728	1.829063	1.139698	2.084579	0.0464004	0.7585942	20
41	0.479968	0.877286	0.547106	1.827799	1.139879	2.083471	0.0464874	0.7576217	19
42	0.480223	0.877146	0.547484	1.826537	1.140061	2.082364	0.0465745	0.7566505	18
43	0.480479	0.877006	0.547862	1.825277	1.140242	2.081258	0.0466618	0.7556807	17
44	0.480734	0.876867	0.548240	1.824017	1.140424	2.080154	0.0467491	0.7547123	16
45	0.480989	0.876727	0.548619	1.822759	1.140606	2.079051	0.0468366	0.7537451	15
46	0.481244	0.876587	0.548997	1.821503	1.140788	2.077949	0.0469242	0.7527793	14
47	0.481499	0.876447	0.549376	1.820247	1.140971	2.076849	0.0470120	0.7518149	13
48	0.481754	0.876307	0.549755	1.818993	1.141153	2.075750	0.0470998	0.7508517	12
49	0.482009	0.876167	0.550134	1.817741	1.141336	2.074652	0.0471878	0.7498899	11
50	0.482263	0.876026	0.550513	1.816489	1.141518	2.073556	0.0472759	0.7489294	10
51	0.482518	0.875886	0.550892	1.815239	1.141701	2.072461	0.0473641	0.7479703	9
52	0.482773	0.875746	0.551271	1.813990	1.141884	2.071367	0.0474525	0.7470124	8
53	0.483028	0.875605	0.551650	1.812743	1.142067	2.070275	0.0475409	0.7460559	7
54	0.483282	0.875465	0.552030	1.811497	1.142251	2.069184	0.0476295	0.7451007	6
55	0.483537	0.875324	0.552409	1.810252	1.142434	2.068094	0.0477182	0.7441468	5
56	0.483792	0.875183	0.552789	1.809009	1.142618	2.067006	0.0478070	0.7431942	4
57	0.484046	0.875042	0.553169	1.807766	1.142802	2.065919	0.0478960	0.7422429	3
58	0.484301	0.874902	0.553549	1.806526	1.142986	2.064833	0.0479851	0.7412930	2
59	0.484555	0.874761	0.553929	1.805286	1.143170	2.063748	0.0480743	0.7403443	1
60	0.484810	0.874620	0.554309	1.804048	1.143354	2.062665	0.0481636	0.7393969	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	61°–62° Involute	Minutes

↑ 118° or 298° 61° or 241° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 29° or 209° Trigonometric and Involute Functions 150° or 330° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 29°–30°	Read Up	Minutes
0	0.484810	0.874620	0.554309	1.804048	1.143354	2.062665	0.0481636	0.7393969	60
1	0.485064	0.874479	0.554689	1.802811	1.143539	2.061584	0.0482530	0.7384508	59
2	0.485318	0.874338	0.555070	1.801575	1.143723	2.060503	0.0483426	0.7375061	58
3	0.485573	0.874196	0.555450	1.800341	1.143908	2.059424	0.0484323	0.7365626	57
4	0.485827	0.874055	0.555831	1.799108	1.144093	2.058346	0.0485221	0.7356204	56
5	0.486081	0.873914	0.556212	1.797876	1.144278	2.057269	0.0486120	0.7346795	55
6	0.486335	0.873772	0.556593	1.796645	1.144463	2.056194	0.0487020	0.7337399	54
7	0.486590	0.873631	0.556974	1.795416	1.144648	2.055120	0.0487922	0.7328016	53
8	0.486844	0.873489	0.557355	1.794188	1.144834	2.054048	0.0488825	0.7318645	52
9	0.487098	0.873347	0.557736	1.792962	1.145020	2.052976	0.0489730	0.7309288	51
10	0.487352	0.873206	0.558118	1.791736	1.145205	2.051906	0.0490635	0.7299943	50
11	0.487606	0.873064	0.558499	1.790512	1.145391	2.050837	0.0491542	0.7290611	49
12	0.487860	0.872922	0.558881	1.789289	1.145578	2.049770	0.0492450	0.7281291	48
13	0.488114	0.872780	0.559263	1.788068	1.145764	2.048704	0.0493359	0.7271985	47
14	0.488367	0.872638	0.559645	1.786847	1.145950	2.047639	0.0494269	0.7262691	46
15	0.488621	0.872496	0.560027	1.785628	1.146137	2.046575	0.0495181	0.7253410	45
16	0.488875	0.872354	0.560409	1.784411	1.146324	2.045513	0.0496094	0.7244141	44
17	0.489129	0.872212	0.560791	1.783194	1.146511	2.044451	0.0497008	0.7234885	43
18	0.489382	0.872069	0.561174	1.781979	1.146698	2.043392	0.0497924	0.7225642	42
19	0.489636	0.871927	0.561556	1.780765	1.146885	2.042333	0.0498840	0.7216411	41
20	0.489890	0.871784	0.561939	1.779552	1.147073	2.041276	0.0499758	0.7207193	40
21	0.490143	0.871642	0.562322	1.778341	1.147260	2.040220	0.0500677	0.7197987	39
22	0.490397	0.871499	0.562705	1.777131	1.147448	2.039165	0.0501598	0.7188794	38
23	0.490650	0.871357	0.563088	1.775922	1.147636	2.038111	0.0502519	0.7179614	37
24	0.490904	0.871214	0.563471	1.774714	1.147824	2.037059	0.0503442	0.7170446	36
25	0.491157	0.871071	0.563854	1.773508	1.148012	2.036008	0.0504367	0.7161290	35
26	0.491411	0.870928	0.564238	1.772302	1.148200	2.034958	0.0505292	0.7152147	34
27	0.491664	0.870785	0.564621	1.771098	1.148389	2.033910	0.0506219	0.7143016	33
28	0.491917	0.870642	0.565005	1.769896	1.148578	2.032863	0.0507147	0.7133898	32
29	0.492170	0.870499	0.565389	1.768694	1.148767	2.031817	0.0508076	0.7124792	31
30	0.492424	0.870356	0.565773	1.767494	1.148956	2.030772	0.0509006	0.7115698	30
31	0.492677	0.870212	0.566157	1.766295	1.149145	2.029729	0.0509938	0.7106617	29
32	0.492930	0.870069	0.566541	1.765097	1.149334	2.028686	0.0510871	0.7097548	28
33	0.493183	0.869926	0.566925	1.763901	1.149524	2.027645	0.0511806	0.7088491	27
34	0.493436	0.869782	0.567310	1.762705	1.149713	2.026606	0.0512741	0.7079447	26
35	0.493689	0.869639	0.567694	1.761511	1.149903	2.025567	0.0513678	0.7070415	25
36	0.493942	0.869495	0.568079	1.760318	1.150093	2.024530	0.0514616	0.7061395	24
37	0.494195	0.869351	0.568464	1.759127	1.150283	2.023494	0.0515555	0.7052387	23
38	0.494448	0.869207	0.568849	1.757936	1.150473	2.022459	0.0516496	0.7043392	22
39	0.494700	0.869064	0.569234	1.756747	1.150664	2.021425	0.0517438	0.7034408	21
40	0.494953	0.868920	0.569619	1.755559	1.150854	2.020393	0.0518381	0.7025437	20
41	0.495206	0.868776	0.570004	1.754372	1.151045	2.019362	0.0519326	0.7016478	19
42	0.495459	0.868632	0.570390	1.753187	1.151236	2.018332	0.0520271	0.7007531	18
43	0.495711	0.868487	0.570776	1.752002	1.151427	2.017303	0.0521218	0.6998596	17
44	0.495964	0.868343	0.571161	1.750819	1.151618	2.016276	0.0522167	0.6989673	16
45	0.496217	0.868199	0.571547	1.749637	1.151810	2.015249	0.0523116	0.6980762	15
46	0.496469	0.868054	0.571933	1.748456	1.152001	2.014224	0.0524067	0.6971864	14
47	0.496722	0.867910	0.572319	1.747277	1.152193	2.013200	0.0525019	0.6962977	13
48	0.496974	0.867765	0.572705	1.746098	1.152385	2.012178	0.0525973	0.6954102	12
49	0.497226	0.867621	0.573092	1.744921	1.152577	2.011156	0.0526928	0.6945239	11
50	0.497479	0.867476	0.573478	1.743745	1.152769	2.010136	0.0527884	0.6936389	10
51	0.497731	0.867331	0.573865	1.742571	1.152962	2.009117	0.0528841	0.6927550	9
52	0.497983	0.867187	0.574252	1.741397	1.153154	2.008099	0.0529799	0.6918723	8
53	0.498236	0.867042	0.574638	1.740225	1.153347	2.007083	0.0530759	0.6909907	7
54	0.498488	0.866897	0.575026	1.739053	1.153540	2.006067	0.0531721	0.6901104	6
55	0.498740	0.866752	0.575413	1.737883	1.153733	2.005053	0.0532683	0.6892313	5
56	0.498992	0.866607	0.575800	1.736714	1.153926	2.004040	0.0533647	0.6883533	4
57	0.499244	0.866461	0.576187	1.735547	1.154119	2.003028	0.0534612	0.6874765	3
58	0.499496	0.866316	0.576575	1.734380	1.154313	2.002018	0.0535578	0.6866009	2
59	0.499748	0.866171	0.576962	1.733215	1.154507	2.001008	0.0536546	0.6857265	1
60	0.500000	0.866025	0.577350	1.732051	1.154701	2.000000	0.0537515	0.6848533	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	60°–61° Involute	Minutes

↑ 119° or 299° 60° or 240° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 30° or 210° Trigonometric and Involute Functions 149° or 329° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 30°–31°	Read Up	Minutes
0	0.500000	0.866025	0.577350	1.732051	1.154701	2.000000	0.0537515	0.6848533	60
1	0.500252	0.865880	0.577738	1.730888	1.154895	1.998993	0.0538485	0.6839812	59
2	0.500504	0.865734	0.578126	1.729726	1.155089	1.997987	0.0539457	0.6831103	58
3	0.500756	0.865589	0.578514	1.728565	1.155283	1.996982	0.0540430	0.6822405	57
4	0.501007	0.865443	0.578903	1.727406	1.155478	1.995979	0.0541404	0.6813720	56
5	0.501259	0.865297	0.579291	1.726248	1.155672	1.994976	0.0542379	0.6805045	55
6	0.501511	0.865151	0.579680	1.725091	1.155867	1.993975	0.0543356	0.6796383	54
7	0.501762	0.865006	0.580068	1.723935	1.156062	1.992975	0.0544334	0.6787732	53
8	0.502014	0.864860	0.580457	1.722780	1.156257	1.991976	0.0545314	0.6779093	52
9	0.502266	0.864713	0.580846	1.721626	1.156452	1.990979	0.0546295	0.6770465	51
10	0.502517	0.864567	0.581235	1.720474	1.156648	1.989982	0.0547277	0.6761849	50
11	0.502769	0.864421	0.581625	1.719322	1.156844	1.988987	0.0548260	0.6753244	49
12	0.503020	0.864275	0.582014	1.718172	1.157039	1.987993	0.0549245	0.6744651	48
13	0.503271	0.864128	0.582403	1.717023	1.157235	1.987000	0.0550231	0.6736070	47
14	0.503523	0.863982	0.582793	1.715875	1.157432	1.986008	0.0551218	0.6727500	46
15	0.503774	0.863836	0.583183	1.714728	1.157628	1.985017	0.0552207	0.6718941	45
16	0.504025	0.863689	0.583573	1.713583	1.157824	1.984028	0.0553197	0.6710394	44
17	0.504276	0.863542	0.583963	1.712438	1.158021	1.983039	0.0554188	0.6701858	43
18	0.504528	0.863396	0.584353	1.711295	1.158218	1.982052	0.0555181	0.6693333	42
19	0.504779	0.863249	0.584743	1.710153	1.158415	1.981066	0.0556175	0.6684820	41
20	0.505030	0.863102	0.585134	1.709012	1.158612	1.980081	0.0557170	0.6676319	40
21	0.505281	0.862955	0.585524	1.707872	1.158809	1.979097	0.0558166	0.6667828	39
22	0.505532	0.862808	0.585915	1.706733	1.159007	1.978115	0.0559164	0.6659349	38
23	0.505783	0.862661	0.586306	1.705595	1.159204	1.977133	0.0560164	0.6650881	37
24	0.506034	0.862514	0.586697	1.704459	1.159402	1.976153	0.0561164	0.6642425	36
25	0.506285	0.862366	0.587088	1.703323	1.159600	1.975174	0.0562166	0.6633980	35
26	0.506535	0.862219	0.587479	1.702189	1.159798	1.974195	0.0563169	0.6625546	34
27	0.506786	0.862072	0.587870	1.701056	1.159996	1.973218	0.0564174	0.6617123	33
28	0.507037	0.861924	0.588262	1.699924	1.160195	1.972243	0.0565180	0.6608712	32
29	0.507288	0.861777	0.588653	1.698793	1.160393	1.971268	0.0566187	0.6600311	31
30	0.507538	0.861629	0.589045	1.697663	1.160592	1.970294	0.0567196	0.6591922	30
31	0.507789	0.861481	0.589437	1.696534	1.160791	1.969322	0.0568206	0.6583544	29
32	0.508040	0.861334	0.589829	1.695407	1.160990	1.968351	0.0569217	0.6575177	28
33	0.508290	0.861186	0.590221	1.694280	1.161189	1.967381	0.0570230	0.6566822	27
34	0.508541	0.861038	0.590613	1.693155	1.161389	1.966411	0.0571244	0.6558477	26
35	0.508791	0.860890	0.591006	1.692031	1.161589	1.965444	0.0572259	0.6550143	25
36	0.509041	0.860742	0.591398	1.690908	1.161788	1.964477	0.0573276	0.6541821	24
37	0.509292	0.860594	0.591791	1.689786	1.161988	1.963511	0.0574294	0.6533509	23
38	0.509542	0.860446	0.592184	1.688665	1.162188	1.962546	0.0575313	0.6525209	22
39	0.509792	0.860297	0.592577	1.687545	1.162389	1.961583	0.0576334	0.6516919	21
40	0.510043	0.860149	0.592970	1.686426	1.162589	1.960621	0.0577356	0.6508641	20
41	0.510293	0.860001	0.593363	1.685308	1.162790	1.959659	0.0578380	0.6500374	19
42	0.510543	0.859852	0.593757	1.684192	1.162990	1.958699	0.0579405	0.6492117	18
43	0.510793	0.859704	0.594150	1.683077	1.163191	1.957740	0.0580431	0.6483871	17
44	0.511043	0.859555	0.594544	1.681962	1.163393	1.956782	0.0581458	0.6475637	16
45	0.511293	0.859406	0.594937	1.680849	1.163594	1.955825	0.0582487	0.6467413	15
46	0.511543	0.859258	0.595331	1.679737	1.163795	1.954870	0.0583518	0.6459200	14
47	0.511793	0.859109	0.595725	1.678626	1.163997	1.953915	0.0584549	0.6450998	13
48	0.512043	0.858960	0.596120	1.677516	1.164199	1.952961	0.0585582	0.6442807	12
49	0.512293	0.858811	0.596514	1.676407	1.164401	1.952009	0.0586617	0.6434627	11
50	0.512543	0.858662	0.596908	1.675299	1.164603	1.951058	0.0587652	0.6426457	10
51	0.512792	0.858513	0.597303	1.674192	1.164805	1.950107	0.0588690	0.6418298	9
52	0.513042	0.858364	0.597698	1.673086	1.165008	1.949158	0.0589728	0.6410150	8
53	0.513292	0.858214	0.598093	1.671982	1.165210	1.948210	0.0590768	0.6402013	7
54	0.513541	0.858065	0.598488	1.670878	1.165413	1.947263	0.0591809	0.6393887	6
55	0.513791	0.857915	0.598883	1.669776	1.165616	1.946317	0.0592852	0.6385771	5
56	0.514040	0.857766	0.599278	1.668674	1.165819	1.945373	0.0593896	0.6377666	4
57	0.514290	0.857616	0.599674	1.667574	1.166022	1.944429	0.0594941	0.6369571	3
58	0.514539	0.857467	0.600069	1.666475	1.166226	1.943486	0.0595988	0.6361488	2
59	0.514789	0.857317	0.600465	1.665377	1.166430	1.942545	0.0597036	0.6353415	1
60	0.515038	0.857167	0.600861	1.664279	1.166633	1.941604	0.0598086	0.6345352	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	59°–60° Involute	Minutes

↑ 120° or 300° 59° or 239° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 31° or 211° Trigonometric and Involute Functions 148° or 328° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 31°–32°	Read Up	Minutes
0	0.515038	0.857167	0.600861	1.664279	1.166633	1.941604	0.0598086	0.6345352	60
1	0.515287	0.857017	0.601257	1.663183	1.166837	1.940665	0.0599136	0.6337300	59
2	0.515537	0.856868	0.601653	1.662088	1.167042	1.939726	0.0600189	0.6329259	58
3	0.515786	0.856718	0.602049	1.660994	1.167246	1.938789	0.0601242	0.6321229	57
4	0.516035	0.856567	0.602445	1.659902	1.167450	1.937853	0.0602297	0.6313209	56
5	0.516284	0.856417	0.602842	1.658810	1.167655	1.936918	0.0603354	0.6305199	55
6	0.516533	0.856267	0.603239	1.657719	1.167860	1.935983	0.0604412	0.6297200	54
7	0.516782	0.856117	0.603635	1.656629	1.168065	1.935050	0.0605471	0.6289212	53
8	0.517031	0.855966	0.604032	1.655541	1.168270	1.934119	0.0606532	0.6281234	52
9	0.517280	0.855816	0.604429	1.654453	1.168475	1.933188	0.0607594	0.6273266	51
10	0.517529	0.855665	0.604827	1.653366	1.168681	1.932258	0.0608657	0.6265309	50
11	0.517778	0.855515	0.605224	1.652281	1.168887	1.931329	0.0609722	0.6257363	49
12	0.518027	0.855364	0.605622	1.651196	1.169093	1.930401	0.0610788	0.6249427	48
13	0.518276	0.855214	0.606019	1.650113	1.169299	1.929475	0.0611856	0.6241501	47
14	0.518525	0.855063	0.606417	1.649030	1.169505	1.928549	0.0612925	0.6233586	46
15	0.518773	0.854912	0.606815	1.647949	1.169711	1.927624	0.0613995	0.6225681	45
16	0.519022	0.854761	0.607213	1.646869	1.169918	1.926701	0.0615067	0.6217786	44
17	0.519271	0.854610	0.607611	1.645789	1.170124	1.925778	0.0616140	0.6209902	43
18	0.519519	0.854459	0.608010	1.644711	1.170331	1.924857	0.0617215	0.6202028	42
19	0.519768	0.854308	0.608408	1.643634	1.170538	1.923937	0.0618291	0.6194164	41
20	0.520016	0.854156	0.608807	1.642558	1.170746	1.923017	0.0619368	0.6186311	40
21	0.520265	0.854005	0.609205	1.641482	1.170953	1.922099	0.0620447	0.6178468	39
22	0.520513	0.853854	0.609604	1.640408	1.171161	1.921182	0.0621527	0.6170635	38
23	0.520761	0.853702	0.610003	1.639335	1.171368	1.920265	0.0622609	0.6162813	37
24	0.521010	0.853551	0.610403	1.638263	1.171576	1.919350	0.0623692	0.6155000	36
25	0.521258	0.853399	0.610802	1.637192	1.171785	1.918436	0.0624777	0.6147198	35
26	0.521506	0.853248	0.611201	1.636122	1.171993	1.917523	0.0625863	0.6139407	34
27	0.521754	0.853096	0.611601	1.635053	1.172201	1.916611	0.0626950	0.6131625	33
28	0.522002	0.852944	0.612001	1.633985	1.172410	1.915700	0.0628039	0.6123853	32
29	0.522251	0.852792	0.612401	1.632918	1.172619	1.914790	0.0629129	0.6116092	31
30	0.522499	0.852640	0.612801	1.631852	1.172828	1.913881	0.0630221	0.6108341	30
31	0.522747	0.852488	0.613201	1.630787	1.173037	1.912973	0.0631314	0.6100600	29
32	0.522995	0.852336	0.613601	1.629723	1.173246	1.912066	0.0632408	0.6092869	28
33	0.523242	0.852184	0.614002	1.628660	1.173456	1.911160	0.0633504	0.6085148	27
34	0.523490	0.852032	0.614402	1.627598	1.173665	1.910255	0.0634602	0.6077437	26
35	0.523738	0.851879	0.614803	1.626537	1.173875	1.909351	0.0635700	0.6069736	25
36	0.523986	0.851727	0.615204	1.625477	1.174085	1.908448	0.0636801	0.6062045	24
37	0.524234	0.851574	0.615605	1.624418	1.174295	1.907546	0.0637902	0.6054364	23
38	0.524481	0.851422	0.616006	1.623360	1.174506	1.906646	0.0639005	0.6046694	22
39	0.524729	0.851269	0.616408	1.622303	1.174716	1.905746	0.0640110	0.6039033	21
40	0.524977	0.851117	0.616809	1.621247	1.174927	1.904847	0.0641216	0.6031382	20
41	0.525224	0.850964	0.617211	1.620192	1.175138	1.903949	0.0642323	0.6023741	19
42	0.525472	0.850811	0.617613	1.619138	1.175349	1.903052	0.0643432	0.6016110	18
43	0.525719	0.850658	0.618015	1.618085	1.175560	1.902156	0.0644542	0.6008489	17
44	0.525967	0.850505	0.618417	1.617033	1.175772	1.901262	0.0645654	0.6000878	16
45	0.526214	0.850352	0.618819	1.615982	1.175983	1.900368	0.0646767	0.5993277	15
46	0.526461	0.850199	0.619221	1.614932	1.176195	1.899475	0.0647882	0.5985686	14
47	0.526709	0.850046	0.619624	1.613883	1.176407	1.898583	0.0648998	0.5978104	13
48	0.526956	0.849893	0.620026	1.612835	1.176619	1.897692	0.0650116	0.5970533	12
49	0.527203	0.849739	0.620429	1.611788	1.176831	1.896803	0.0651235	0.5962971	11
50	0.527450	0.849586	0.620832	1.610742	1.177044	1.895914	0.0652355	0.5955419	10
51	0.527697	0.849433	0.621235	1.609697	1.177257	1.895026	0.0653477	0.5947877	9
52	0.527944	0.849279	0.621638	1.608653	1.177469	1.894139	0.0654600	0.5940344	8
53	0.528191	0.849125	0.622042	1.607609	1.177682	1.893253	0.0655725	0.5932822	7
54	0.528438	0.848972	0.622445	1.606567	1.177896	1.892368	0.0656851	0.5925309	6
55	0.528685	0.848818	0.622849	1.605526	1.178109	1.891485	0.0657979	0.5917806	5
56	0.528932	0.848664	0.623253	1.604486	1.178322	1.890602	0.0659108	0.5910312	4
57	0.529179	0.848510	0.623657	1.603446	1.178536	1.889720	0.0660239	0.5902829	3
58	0.529426	0.848356	0.624061	1.602408	1.178750	1.888839	0.0661371	0.5895355	2
59	0.529673	0.848202	0.624465	1.601371	1.178964	1.887959	0.0662505	0.5887890	1
60	0.529919	0.848048	0.624869	1.600335	1.179178	1.887080	0.0663640	0.5880436	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	58°–59° Involute	Minutes

↑ 121° or 301° 58° or 238° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 32° or 212° Trigonometric and Involute Functions 147° or 327° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 32°–33°	Read Up	Minutes
0	0.529919	0.848048	0.624869	1.600335	1.179178	1.887080	0.0663640	0.5880436	60
1	0.530166	0.847894	0.625274	1.599299	1.179393	1.886202	0.0664776	0.5872991	59
2	0.530413	0.847740	0.625679	1.598265	1.179607	1.885325	0.0665914	0.5865555	58
3	0.530659	0.847585	0.626083	1.597231	1.179822	1.884449	0.0667054	0.5858129	57
4	0.530906	0.847431	0.626488	1.596199	1.180037	1.883574	0.0668195	0.5850713	56
5	0.531152	0.847276	0.626894	1.595167	1.180252	1.882700	0.0669337	0.5843307	55
6	0.531399	0.847122	0.627299	1.594137	1.180468	1.881827	0.0670481	0.5835910	54
7	0.531645	0.846967	0.627704	1.593107	1.180683	1.880954	0.0671627	0.5828522	53
8	0.531891	0.846813	0.628110	1.592078	1.180899	1.880083	0.0672774	0.5821144	52
9	0.532138	0.846658	0.628516	1.591051	1.181115	1.879213	0.0673922	0.5813776	51
10	0.532384	0.846503	0.628921	1.590024	1.181331	1.878344	0.0675072	0.5806417	50
11	0.532630	0.846348	0.629327	1.588998	1.181547	1.877476	0.0676223	0.5799067	49
12	0.532876	0.846193	0.629734	1.587973	1.181763	1.876608	0.0677376	0.5791727	48
13	0.533122	0.846038	0.630140	1.586949	1.181980	1.875742	0.0678530	0.5784397	47
14	0.533368	0.845883	0.630546	1.585926	1.182197	1.874876	0.0679686	0.5777076	46
15	0.533615	0.845728	0.630953	1.584904	1.182414	1.874012	0.0680843	0.5769764	45
16	0.533861	0.845573	0.631360	1.583883	1.182631	1.873148	0.0682002	0.5762462	44
17	0.534106	0.845417	0.631767	1.582863	1.182848	1.872286	0.0683162	0.5755169	43
18	0.534352	0.845262	0.632174	1.581844	1.183065	1.871424	0.0684324	0.5747886	42
19	0.534598	0.845106	0.632581	1.580825	1.183283	1.870564	0.0685487	0.5740612	41
20	0.534844	0.844951	0.632988	1.579808	1.183501	1.869704	0.0686652	0.5733347	40
21	0.535090	0.844795	0.633396	1.578792	1.183719	1.868845	0.0687818	0.5726092	39
22	0.535335	0.844640	0.633804	1.577776	1.183937	1.867987	0.0688986	0.5718846	38
23	0.535581	0.844484	0.634211	1.576761	1.184155	1.867131	0.0690155	0.5711609	37
24	0.535827	0.844328	0.634619	1.575748	1.184374	1.866275	0.0691326	0.5704382	36
25	0.536072	0.844172	0.635027	1.574735	1.184593	1.865420	0.0692498	0.5697164	35
26	0.536318	0.844016	0.635436	1.573723	1.184812	1.864566	0.0693672	0.5689955	34
27	0.536563	0.843860	0.635844	1.572713	1.185031	1.863713	0.0694848	0.5682756	33
28	0.536809	0.843704	0.636253	1.571703	1.185250	1.862860	0.0696024	0.5675565	32
29	0.537054	0.843548	0.636661	1.570694	1.185469	1.862009	0.0697203	0.5668384	31
30	0.537300	0.843391	0.637070	1.569686	1.185689	1.861159	0.0698383	0.5661213	30
31	0.537545	0.843235	0.637479	1.568678	1.185909	1.860310	0.0699564	0.5654050	29
32	0.537790	0.843079	0.637888	1.567672	1.186129	1.859461	0.0700747	0.5646896	28
33	0.538035	0.842922	0.638298	1.566667	1.186349	1.858614	0.0701931	0.5639752	27
34	0.538281	0.842766	0.638707	1.565662	1.186569	1.857767	0.0703117	0.5632617	26
35	0.538526	0.842609	0.639117	1.564659	1.186790	1.856922	0.0704304	0.5625491	25
36	0.538771	0.842452	0.639527	1.563656	1.187011	1.856077	0.0705493	0.5618374	24
37	0.539016	0.842296	0.639937	1.562655	1.187232	1.855233	0.0706684	0.5611267	23
38	0.539261	0.842139	0.640347	1.561654	1.187453	1.854390	0.0707876	0.5604168	22
39	0.539506	0.841982	0.640757	1.560654	1.187674	1.853548	0.0709069	0.5597078	21
40	0.539751	0.841825	0.641167	1.559655	1.187895	1.852707	0.0710265	0.5589998	20
41	0.539996	0.841668	0.641578	1.558657	1.188117	1.851867	0.0711461	0.5582927	19
42	0.540240	0.841511	0.641989	1.557660	1.188339	1.851028	0.0712659	0.5575864	18
43	0.540485	0.841354	0.642399	1.556664	1.188561	1.850190	0.0713859	0.5568811	17
44	0.540730	0.841196	0.642810	1.555669	1.188783	1.849352	0.0715060	0.5561767	16
45	0.540974	0.841039	0.643222	1.554674	1.189005	1.848516	0.0716263	0.5554731	15
46	0.541219	0.840882	0.643633	1.553681	1.189228	1.847681	0.0717467	0.5547705	14
47	0.541464	0.840724	0.644044	1.552688	1.189451	1.846846	0.0718673	0.5540688	13
48	0.541708	0.840567	0.644456	1.551696	1.189674	1.846012	0.0719880	0.5533679	12
49	0.541953	0.840409	0.644868	1.550705	1.189897	1.845179	0.0721089	0.5526680	11
50	0.542197	0.840251	0.645280	1.549715	1.190120	1.844348	0.0722300	0.5519689	10
51	0.542442	0.840094	0.645692	1.548726	1.190344	1.843517	0.0723512	0.5512708	9
52	0.542686	0.839936	0.646104	1.547738	1.190567	1.842687	0.0724725	0.5505735	8
53	0.542930	0.839778	0.646516	1.546751	1.190791	1.841857	0.0725940	0.5498771	7
54	0.543174	0.839620	0.646929	1.545765	1.191015	1.841029	0.0727157	0.5491816	6
55	0.543419	0.839462	0.647342	1.544779	1.191239	1.840202	0.0728375	0.5484870	5
56	0.543663	0.839304	0.647755	1.543795	1.191464	1.839375	0.0729595	0.5477933	4
57	0.543907	0.839146	0.648168	1.542811	1.191688	1.838550	0.0730816	0.5471005	3
58	0.544151	0.838987	0.648581	1.541828	1.191913	1.837725	0.0732039	0.5464085	2
59	0.544395	0.838829	0.648994	1.540846	1.192138	1.836901	0.0733263	0.5457175	1
60	0.544639	0.838671	0.649408	1.539865	1.192363	1.836078	0.0734489	0.5450273	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	57°–58° Involute	Minutes

↑ 122° or 302° 57° or 237° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 33° or 213° Trigonometric and Involute Functions 146° or 326° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 33°–34°	Read Up	Minutes
0	0.544639	0.838671	0.649408	1.539865	1.192363	1.836078	0.0734489	0.5450273	60
1	0.544883	0.838512	0.649821	1.538885	1.192589	1.835256	0.0735717	0.5443380	59
2	0.545127	0.838354	0.650235	1.537905	1.192814	1.834435	0.0736946	0.5436495	58
3	0.545371	0.838195	0.650649	1.536927	1.193040	1.833615	0.0738177	0.5429620	57
4	0.545615	0.838036	0.651063	1.535949	1.193266	1.832796	0.0739409	0.5422753	56
5	0.545858	0.837878	0.651477	1.534973	1.193492	1.831977	0.0740643	0.5415895	55
6	0.546102	0.837719	0.651892	1.533997	1.193718	1.831160	0.0741878	0.5409046	54
7	0.546346	0.837560	0.652306	1.533022	1.193945	1.830343	0.0743115	0.5402205	53
8	0.546589	0.837401	0.652721	1.532048	1.194171	1.829527	0.0744354	0.5395373	52
9	0.546833	0.837242	0.653136	1.531075	1.194398	1.828713	0.0745594	0.5388550	51
10	0.547076	0.837083	0.653551	1.530102	1.194625	1.827899	0.0746835	0.5381735	50
11	0.547320	0.836924	0.653966	1.529131	1.194852	1.827085	0.0748079	0.5374929	49
12	0.547563	0.836764	0.654382	1.528160	1.195080	1.826273	0.0749324	0.5368132	48
13	0.547807	0.836605	0.654797	1.527190	1.195307	1.825462	0.0750570	0.5361343	47
14	0.548050	0.836446	0.655213	1.526222	1.195535	1.824651	0.0751818	0.5354563	46
15	0.548293	0.836286	0.655629	1.525253	1.195763	1.823842	0.0753068	0.5347791	45
16	0.548536	0.836127	0.656045	1.524286	1.195991	1.823033	0.0754319	0.5341028	44
17	0.548780	0.835967	0.656461	1.523320	1.196219	1.822225	0.0755571	0.5334274	43
18	0.549023	0.835807	0.656877	1.522355	1.196448	1.821418	0.0756826	0.5327528	42
19	0.549266	0.835648	0.657294	1.521390	1.196677	1.820612	0.0758082	0.5320791	41
20	0.549509	0.835488	0.657710	1.520426	1.196906	1.819806	0.0759339	0.5314062	40
21	0.549752	0.835328	0.658127	1.519463	1.197135	1.819002	0.0760598	0.5307342	39
22	0.549995	0.835168	0.658544	1.518501	1.197364	1.818199	0.0761859	0.5300630	38
23	0.550238	0.835008	0.658961	1.517540	1.197593	1.817396	0.0763121	0.5293927	37
24	0.550481	0.834848	0.659379	1.516580	1.197823	1.816594	0.0764385	0.5287232	36
25	0.550724	0.834688	0.659796	1.515620	1.198053	1.815793	0.0765651	0.5280546	35
26	0.550966	0.834527	0.660214	1.514661	1.198283	1.814993	0.0766918	0.5273868	34
27	0.551209	0.834367	0.660631	1.513704	1.198513	1.814194	0.0768187	0.5267199	33
28	0.551452	0.834207	0.661049	1.512747	1.198744	1.813395	0.0769457	0.5260538	32
29	0.551694	0.834046	0.661467	1.511790	1.198974	1.812598	0.0770729	0.5253886	31
30	0.551937	0.833886	0.661886	1.510835	1.199205	1.811801	0.0772003	0.5247242	30
31	0.552180	0.833725	0.662304	1.509881	1.199436	1.811005	0.0773278	0.5240606	29
32	0.552422	0.833565	0.662723	1.508927	1.199667	1.810210	0.0774555	0.5233979	28
33	0.552664	0.833404	0.663141	1.507974	1.199898	1.809416	0.0775833	0.5227360	27
34	0.552907	0.833243	0.663560	1.507022	1.200130	1.808623	0.0777113	0.5220749	26
35	0.553149	0.833082	0.663979	1.506071	1.200362	1.807830	0.0778395	0.5214147	25
36	0.553392	0.832921	0.664398	1.505121	1.200594	1.807039	0.0779678	0.5207553	24
37	0.553634	0.832760	0.664818	1.504172	1.200826	1.806248	0.0780963	0.5200967	23
38	0.553876	0.832599	0.665237	1.503223	1.201058	1.805458	0.0782249	0.5194390	22
39	0.554118	0.832438	0.665657	1.502275	1.201291	1.804669	0.0783537	0.5187821	21
40	0.554360	0.832277	0.666077	1.501328	1.201523	1.803881	0.0784827	0.5181260	20
41	0.554602	0.832115	0.666497	1.500382	1.201756	1.803094	0.0786118	0.5174708	19
42	0.554844	0.831954	0.666917	1.499437	1.201989	1.802307	0.0787411	0.5168164	18
43	0.555086	0.831793	0.667337	1.498492	1.202223	1.801521	0.0788706	0.5161628	17
44	0.555328	0.831631	0.667758	1.497549	1.202456	1.800736	0.0790002	0.5155100	16
45	0.555570	0.831470	0.668179	1.496606	1.202690	1.799952	0.0791300	0.5148581	15
46	0.555812	0.831308	0.668599	1.495664	1.202924	1.799169	0.0792600	0.5142069	14
47	0.556054	0.831146	0.669020	1.494723	1.203158	1.798387	0.0793901	0.5135566	13
48	0.556296	0.830984	0.669442	1.493782	1.203392	1.797605	0.0795204	0.5129071	12
49	0.556537	0.830823	0.669863	1.492843	1.203626	1.796825	0.0796508	0.5122585	11
50	0.556779	0.830661	0.670284	1.491904	1.203861	1.796045	0.0797814	0.5116106	10
51	0.557021	0.830499	0.670706	1.490966	1.204096	1.795266	0.0799122	0.5109635	9
52	0.557262	0.830337	0.671128	1.490029	1.204331	1.794488	0.0800431	0.5103173	8
53	0.557504	0.830174	0.671550	1.489092	1.204566	1.793710	0.0801742	0.5096719	7
54	0.557745	0.830012	0.671972	1.488157	1.204801	1.792934	0.0803055	0.5090273	6
55	0.557987	0.829850	0.672394	1.487222	1.205037	1.792158	0.0804369	0.5083835	5
56	0.558228	0.829688	0.672817	1.486288	1.205273	1.791383	0.0805685	0.5077405	4
57	0.558469	0.829525	0.673240	1.485355	1.205509	1.790609	0.0807003	0.5070983	3
58	0.558710	0.829363	0.673662	1.484423	1.205745	1.789836	0.0808322	0.5064569	2
59	0.558952	0.829200	0.674085	1.483492	1.205981	1.789063	0.0809643	0.5058164	1
60	0.559193	0.829038	0.674509	1.482561	1.206218	1.788292	0.0810966	0.5051766	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	56°–57° Involute	Minutes

↑ 123° or 303° 56° or 236° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 34° or 214° Trigonometric and Involute Functions 145° or 325° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 34°–35°	Read Up	Minutes
0	0.559193	0.829038	0.674509	1.482561	1.206218	1.788292	0.0810966	0.5051766	60
1	0.559434	0.828875	0.674932	1.481631	1.206455	1.787521	0.0812290	0.5045376	59
2	0.559675	0.828712	0.675355	1.480702	1.206692	1.786751	0.0813616	0.5038995	58
3	0.559916	0.828549	0.675779	1.479774	1.206929	1.785982	0.0814943	0.5032621	57
4	0.560157	0.828386	0.676203	1.478846	1.207166	1.785213	0.0816273	0.5026255	56
5	0.560398	0.828223	0.676627	1.477920	1.207404	1.784446	0.0817604	0.5019897	55
6	0.560639	0.828060	0.677051	1.476994	1.207641	1.783679	0.0818936	0.5013548	54
7	0.560880	0.827897	0.677475	1.476069	1.207879	1.782913	0.0820271	0.5007206	53
8	0.561121	0.827734	0.677900	1.475144	1.208118	1.782148	0.0821606	0.5000872	52
9	0.561361	0.827571	0.678324	1.474221	1.208356	1.781384	0.0822944	0.4994546	51
10	0.561602	0.827407	0.678749	1.473298	1.208594	1.780620	0.0824283	0.4988228	50
11	0.561843	0.827244	0.679174	1.472376	1.208833	1.779857	0.0825624	0.4981918	49
12	0.562083	0.827081	0.679599	1.471455	1.209072	1.779095	0.0826967	0.4975616	48
13	0.562324	0.826917	0.680025	1.470535	1.209311	1.778334	0.0828311	0.4969322	47
14	0.562564	0.826753	0.680450	1.469615	1.209550	1.777574	0.0829657	0.4963035	46
15	0.562805	0.826590	0.680876	1.468697	1.209790	1.776815	0.0831005	0.4956757	45
16	0.563045	0.826426	0.681302	1.467779	1.210030	1.776056	0.0832354	0.4950486	44
17	0.563286	0.826262	0.681728	1.466862	1.210270	1.775298	0.0833705	0.4944223	43
18	0.563526	0.826098	0.682154	1.465945	1.210510	1.774541	0.0835058	0.4937968	42
19	0.563766	0.825934	0.682580	1.465030	1.210750	1.773785	0.0836413	0.4931721	41
20	0.564007	0.825770	0.683007	1.464115	1.210991	1.773029	0.0837769	0.4925481	40
21	0.564247	0.825606	0.683433	1.463201	1.211231	1.772274	0.0839127	0.4919249	39
22	0.564487	0.825442	0.683860	1.462287	1.211472	1.771520	0.0840486	0.4913026	38
23	0.564727	0.825278	0.684287	1.461375	1.211713	1.770767	0.0841847	0.4906809	37
24	0.564967	0.825113	0.684714	1.460463	1.211954	1.770015	0.0843210	0.4900601	36
25	0.565207	0.824949	0.685142	1.459552	1.212196	1.769263	0.0844575	0.4894400	35
26	0.565447	0.824785	0.685569	1.458642	1.212438	1.768513	0.0845941	0.4888207	34
27	0.565687	0.824620	0.685997	1.457733	1.212680	1.767763	0.0847309	0.4882022	33
28	0.565927	0.824456	0.686425	1.456824	1.212922	1.767013	0.0848679	0.4875845	32
29	0.566166	0.824291	0.686853	1.455916	1.213164	1.766265	0.0850050	0.4869675	31
30	0.566406	0.824126	0.687281	1.455009	1.213406	1.765517	0.0851424	0.4863513	30
31	0.566646	0.823961	0.687709	1.454103	1.213649	1.764770	0.0852799	0.4857359	29
32	0.566886	0.823797	0.688138	1.453197	1.213892	1.764024	0.0854175	0.4851212	28
33	0.567125	0.823632	0.688567	1.452292	1.214135	1.763279	0.0855553	0.4845073	27
34	0.567365	0.823467	0.688995	1.451388	1.214378	1.762535	0.0856933	0.4838941	26
35	0.567604	0.823302	0.689425	1.450485	1.214622	1.761791	0.0858315	0.4832817	25
36	0.567844	0.823136	0.689854	1.449583	1.214866	1.761048	0.0859699	0.4826701	24
37	0.568083	0.822971	0.690283	1.448681	1.215109	1.760306	0.0861084	0.4820593	23
38	0.568323	0.822806	0.690713	1.447780	1.215354	1.759564	0.0862471	0.4814492	22
39	0.568562	0.822641	0.691143	1.446880	1.215598	1.758824	0.0863859	0.4808398	21
40	0.568801	0.822475	0.691572	1.445980	1.215842	1.758084	0.0865250	0.4802312	20
41	0.569040	0.822310	0.692003	1.445081	1.216087	1.757345	0.0866642	0.4796234	19
42	0.569280	0.822144	0.692433	1.444183	1.216332	1.756606	0.0868036	0.4790163	18
43	0.569519	0.821978	0.692863	1.443286	1.216577	1.755869	0.0869431	0.4784100	17
44	0.569758	0.821813	0.693294	1.442390	1.216822	1.755132	0.0870829	0.4778044	16
45	0.569997	0.821647	0.693725	1.441494	1.217068	1.754396	0.0872228	0.4771996	15
46	0.570236	0.821481	0.694156	1.440599	1.217313	1.753661	0.0873628	0.4765956	14
47	0.570475	0.821315	0.694587	1.439705	1.217559	1.752926	0.0875031	0.4759923	13
48	0.570714	0.821149	0.695018	1.438811	1.217805	1.752192	0.0876435	0.4753897	12
49	0.570952	0.820983	0.695450	1.437919	1.218052	1.751459	0.0877841	0.4747879	11
50	0.571191	0.820817	0.695881	1.437027	1.218298	1.750727	0.0879249	0.4741868	10
51	0.571430	0.820651	0.696313	1.436136	1.218545	1.749996	0.0880659	0.4735865	9
52	0.571669	0.820485	0.696745	1.435245	1.218792	1.749265	0.0882070	0.4729869	8
53	0.571907	0.820318	0.697177	1.434355	1.219039	1.748535	0.0883483	0.4723881	7
54	0.572146	0.820152	0.697610	1.433466	1.219286	1.747806	0.0884898	0.4717900	6
55	0.572384	0.819985	0.698042	1.432578	1.219534	1.747078	0.0886314	0.4711926	5
56	0.572623	0.819819	0.698475	1.431691	1.219782	1.746350	0.0887732	0.4705960	4
57	0.572861	0.819652	0.698908	1.430804	1.220030	1.745623	0.0889152	0.4700001	3
58	0.573100	0.819486	0.699341	1.429918	1.220278	1.744897	0.0890574	0.4694050	2
59	0.573338	0.819319	0.699774	1.429033	1.220526	1.744171	0.0891998	0.4688106	1
60	0.573576	0.819152	0.700208	1.428148	1.220775	1.743447	0.0893423	0.4682169	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	55°–56° Involute	Minutes

↑ 124° or 304° 55° or 235° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 35° or 215° Trigonometric and Involute Functions 144° or 324° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 35°–36°	Read Up	Minutes
0	0.573576	0.819152	0.700208	1.428148	1.220775	1.743447	0.0893423	0.4682169	60
1	0.573815	0.818985	0.700641	1.427264	1.221023	1.742723	0.0894850	0.4676240	59
2	0.574053	0.818818	0.701075	1.426381	1.221272	1.742000	0.0896279	0.4670318	58
3	0.574291	0.818651	0.701509	1.425499	1.221521	1.741277	0.0897710	0.4664403	57
4	0.574529	0.818484	0.701943	1.424617	1.221771	1.740556	0.0899142	0.4658496	56
5	0.574767	0.818317	0.702377	1.423736	1.222020	1.739835	0.0900576	0.4652596	55
6	0.575005	0.818150	0.702812	1.422856	1.222270	1.739115	0.0902012	0.4646703	54
7	0.575243	0.817982	0.703246	1.421977	1.222520	1.738395	0.0903450	0.4640818	53
8	0.575481	0.817815	0.703681	1.421098	1.222770	1.737676	0.0904889	0.4634940	52
9	0.575719	0.817648	0.704116	1.420220	1.223021	1.736958	0.0906331	0.4629069	51
10	0.575957	0.817480	0.704551	1.419343	1.223271	1.736241	0.0907774	0.4623205	50
11	0.576195	0.817313	0.704987	1.418466	1.223522	1.735525	0.0909218	0.4617349	49
12	0.576432	0.817145	0.705422	1.417590	1.223773	1.734809	0.0910665	0.4611499	48
13	0.576670	0.816977	0.705858	1.416715	1.224024	1.734094	0.0912113	0.4605657	47
14	0.576908	0.816809	0.706294	1.415841	1.224276	1.733380	0.0913564	0.4599823	46
15	0.577145	0.816642	0.706730	1.414967	1.224527	1.732666	0.0915016	0.4593995	45
16	0.577383	0.816474	0.707166	1.414094	1.224779	1.731953	0.0916469	0.4588175	44
17	0.577620	0.816306	0.707603	1.413222	1.225031	1.731241	0.0917925	0.4582361	43
18	0.577858	0.816138	0.708039	1.412351	1.225284	1.730530	0.0919382	0.4576555	42
19	0.578095	0.815969	0.708476	1.411480	1.225536	1.729819	0.0920842	0.4570757	41
20	0.578332	0.815801	0.708913	1.410610	1.225789	1.729110	0.0922303	0.4564965	40
21	0.578570	0.815633	0.709350	1.409740	1.226042	1.728400	0.0923765	0.4559180	39
22	0.578807	0.815465	0.709788	1.408872	1.226295	1.727692	0.0925230	0.4553403	38
23	0.579044	0.815296	0.710225	1.408004	1.226548	1.726984	0.0926696	0.4547632	37
24	0.579281	0.815128	0.710663	1.407137	1.226801	1.726277	0.0928165	0.4541869	36
25	0.579518	0.814959	0.711101	1.406270	1.227055	1.725571	0.0929635	0.4536113	35
26	0.579755	0.814791	0.711539	1.405404	1.227309	1.724866	0.0931106	0.4530364	34
27	0.579992	0.814622	0.711977	1.404539	1.227563	1.724161	0.0932580	0.4524622	33
28	0.580229	0.814453	0.712416	1.403675	1.227818	1.723457	0.0934055	0.4518887	32
29	0.580466	0.814284	0.712854	1.402811	1.228072	1.722753	0.0935533	0.4513159	31
30	0.580703	0.814116	0.713293	1.401948	1.228327	1.722051	0.0937012	0.4507439	30
31	0.580940	0.813947	0.713732	1.401086	1.228582	1.721349	0.0938493	0.4501725	29
32	0.581176	0.813778	0.714171	1.400224	1.228837	1.720648	0.0939975	0.4496018	28
33	0.581413	0.813608	0.714611	1.399364	1.229092	1.719947	0.0941460	0.4490318	27
34	0.581650	0.813439	0.715050	1.398503	1.229348	1.719247	0.0942946	0.4484626	26
35	0.581886	0.813270	0.715490	1.397644	1.229604	1.718548	0.0944435	0.4478940	25
36	0.582123	0.813101	0.715930	1.396785	1.229860	1.717850	0.0945925	0.4473261	24
37	0.582359	0.812931	0.716370	1.395927	1.230116	1.717152	0.0947417	0.4467589	23
38	0.582596	0.812762	0.716810	1.395070	1.230373	1.716456	0.0948910	0.4461924	22
39	0.582832	0.812592	0.717250	1.394213	1.230629	1.715759	0.0950406	0.4456267	21
40	0.583069	0.812423	0.717691	1.393357	1.230886	1.715064	0.0951903	0.4450616	20
41	0.583305	0.812253	0.718132	1.392502	1.231143	1.714369	0.0953402	0.4444972	19
42	0.583541	0.812084	0.718573	1.391647	1.231400	1.713675	0.0954904	0.4439335	18
43	0.583777	0.811914	0.719014	1.390793	1.231658	1.712982	0.0956406	0.4433705	17
44	0.584014	0.811744	0.719455	1.389940	1.231916	1.712289	0.0957911	0.4428081	16
45	0.584250	0.811574	0.719897	1.389088	1.232174	1.711597	0.0959418	0.4422465	15
46	0.584486	0.811404	0.720339	1.388236	1.232432	1.710906	0.0960926	0.4416856	14
47	0.584722	0.811234	0.720781	1.387385	1.232690	1.710215	0.0962437	0.4411253	13
48	0.584958	0.811064	0.721223	1.386534	1.232949	1.709525	0.0963949	0.4405657	12
49	0.585194	0.810894	0.721665	1.385684	1.233207	1.708836	0.0965463	0.4400069	11
50	0.585429	0.810723	0.722108	1.384835	1.233466	1.708148	0.0966979	0.4394487	10
51	0.585665	0.810553	0.722550	1.383987	1.233726	1.707460	0.0968496	0.4388911	9
52	0.585901	0.810383	0.722993	1.383139	1.233985	1.706773	0.0970016	0.4383343	8
53	0.586137	0.810212	0.723436	1.382292	1.234245	1.706087	0.0971537	0.4377782	7
54	0.586372	0.810042	0.723879	1.381446	1.234504	1.705401	0.0973061	0.4372227	6
55	0.586608	0.809871	0.724323	1.380600	1.234764	1.704716	0.0974586	0.4366679	5
56	0.586844	0.809700	0.724766	1.379755	1.235025	1.704032	0.0976113	0.4361138	4
57	0.587079	0.809530	0.725210	1.378911	1.235285	1.703348	0.0977642	0.4355604	3
58	0.587314	0.809359	0.725654	1.378067	1.235546	1.702665	0.0979173	0.4350076	2
59	0.587550	0.809188	0.726098	1.377224	1.235807	1.701983	0.0980705	0.4344555	1
60	0.587785	0.809017	0.726543	1.376382	1.236068	1.701302	0.0982240	0.4339041	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	54°–55° Involute	Minutes

↑ 125° or 305° 54° or 234° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 36° or 216° Trigonometric and Involute Functions 143° or 323° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 36°–37°	Read Up	Minutes
0	0.587785	0.809017	0.726543	1.376382	1.236068	1.701302	0.0982240	0.4339041	60
1	0.588021	0.808846	0.726987	1.375540	1.236329	1.700621	0.0983776	0.4333534	59
2	0.588256	0.808675	0.727432	1.374699	1.236591	1.699941	0.0985315	0.4328033	58
3	0.588491	0.808504	0.727877	1.373859	1.236853	1.699261	0.0986855	0.4322540	57
4	0.588726	0.808333	0.728322	1.373019	1.237115	1.698582	0.0988397	0.4317052	56
5	0.588961	0.808161	0.728767	1.372181	1.237377	1.697904	0.0989941	0.4311572	55
6	0.589196	0.807990	0.729213	1.371342	1.237639	1.697227	0.0991487	0.4306098	54
7	0.589431	0.807818	0.729658	1.370505	1.237902	1.696550	0.0993035	0.4300631	53
8	0.589666	0.807647	0.730104	1.369668	1.238165	1.695874	0.0994584	0.4295171	52
9	0.589901	0.807475	0.730550	1.368832	1.238428	1.695199	0.0996136	0.4289717	51
10	0.590136	0.807304	0.730996	1.367996	1.238691	1.694524	0.0997689	0.4284270	50
11	0.590371	0.807132	0.731443	1.367161	1.238955	1.693850	0.0999244	0.4278830	49
12	0.590606	0.806960	0.731889	1.366327	1.239218	1.693177	0.1000802	0.4273396	48
13	0.590840	0.806788	0.732336	1.365493	1.239482	1.692505	0.1002361	0.4267969	47
14	0.591075	0.806617	0.732783	1.364660	1.239746	1.691833	0.1003922	0.4262548	46
15	0.591310	0.806445	0.733230	1.363828	1.240011	1.691161	0.1005485	0.4257134	45
16	0.591544	0.806273	0.733678	1.362996	1.240275	1.690491	0.1007050	0.4251727	44
17	0.591779	0.806100	0.734125	1.362165	1.240540	1.689821	0.1008616	0.4246326	43
18	0.592013	0.805928	0.734573	1.361335	1.240805	1.689152	0.1010185	0.4240932	42
19	0.592248	0.805756	0.735021	1.360505	1.241070	1.688483	0.1011756	0.4235545	41
20	0.592482	0.805584	0.735469	1.359676	1.241336	1.687815	0.1013328	0.4230164	40
21	0.592716	0.805411	0.735917	1.358848	1.241602	1.687148	0.1014903	0.4224789	39
22	0.592951	0.805239	0.736366	1.358020	1.241867	1.686481	0.1016479	0.4219421	38
23	0.593185	0.805066	0.736815	1.357193	1.242134	1.685815	0.1018057	0.4214060	37
24	0.593419	0.804894	0.737264	1.356367	1.242400	1.685150	0.1019637	0.4208705	36
25	0.593653	0.804721	0.737713	1.355541	1.242666	1.684486	0.1021219	0.4203357	35
26	0.593887	0.804548	0.738162	1.354716	1.242933	1.683822	0.1022804	0.4198015	34
27	0.594121	0.804376	0.738611	1.353892	1.243200	1.683159	0.1024389	0.4192680	33
28	0.594355	0.804203	0.739061	1.353068	1.243467	1.682496	0.1025977	0.4187351	32
29	0.594589	0.804030	0.739511	1.352245	1.243735	1.681834	0.1027567	0.4182029	31
30	0.594823	0.803857	0.739961	1.351422	1.244003	1.681173	0.1029159	0.4176713	30
31	0.595057	0.803684	0.740411	1.350601	1.244270	1.680512	0.1030753	0.4171403	29
32	0.595290	0.803511	0.740862	1.349779	1.244539	1.679853	0.1032348	0.4166101	28
33	0.595524	0.803337	0.741312	1.348959	1.244807	1.679193	0.1033946	0.4160804	27
34	0.595758	0.803164	0.741763	1.348139	1.245075	1.678535	0.1035545	0.4155514	26
35	0.595991	0.802991	0.742214	1.347320	1.245344	1.677877	0.1037147	0.4150230	25
36	0.596225	0.802817	0.742666	1.346501	1.245613	1.677220	0.1038750	0.4144953	24
37	0.596458	0.802644	0.743117	1.345683	1.245882	1.676563	0.1040356	0.4139682	23
38	0.596692	0.802470	0.743569	1.344866	1.246152	1.675907	0.1041963	0.4134418	22
39	0.596925	0.802297	0.744020	1.344049	1.246421	1.675252	0.1043572	0.4129160	21
40	0.597159	0.802123	0.744472	1.343233	1.246691	1.674597	0.1045184	0.4123908	20
41	0.597392	0.801949	0.744925	1.342418	1.246961	1.673943	0.1046797	0.4118663	19
42	0.597625	0.801776	0.745377	1.341603	1.247232	1.673290	0.1048412	0.4113424	18
43	0.597858	0.801602	0.745830	1.340789	1.247502	1.672637	0.1050029	0.4108192	17
44	0.598091	0.801428	0.746282	1.339975	1.247773	1.671985	0.1051648	0.4102966	16
45	0.598325	0.801254	0.746735	1.339162	1.248044	1.671334	0.1053269	0.4097746	15
46	0.598558	0.801080	0.747189	1.338350	1.248315	1.670683	0.1054892	0.4092532	14
47	0.598791	0.800906	0.747642	1.337539	1.248587	1.670033	0.1056517	0.4087325	13
48	0.599024	0.800731	0.748096	1.336728	1.248858	1.669383	0.1058144	0.4082124	12
49	0.599256	0.800557	0.748549	1.335917	1.249130	1.668735	0.1059773	0.4076930	11
50	0.599489	0.800383	0.749003	1.335108	1.249402	1.668086	0.1061404	0.4071741	10
51	0.599722	0.800208	0.749458	1.334298	1.249675	1.667439	0.1063037	0.4066559	9
52	0.599955	0.800034	0.749912	1.333490	1.249947	1.666792	0.1064672	0.4061384	8
53	0.600188	0.799859	0.750366	1.332682	1.250220	1.666146	0.1066309	0.4056214	7
54	0.600420	0.799685	0.750821	1.331875	1.250493	1.665500	0.1067947	0.4051051	6
55	0.600653	0.799510	0.751276	1.331068	1.250766	1.664855	0.1069588	0.4045894	5
56	0.600885	0.799335	0.751731	1.330262	1.251040	1.664211	0.1071231	0.4040744	4
57	0.601118	0.799160	0.752187	1.329457	1.251313	1.663567	0.1072876	0.4035599	3
58	0.601350	0.798985	0.752642	1.328652	1.251587	1.662924	0.1074523	0.4030461	2
59	0.601583	0.798811	0.753098	1.327848	1.251861	1.662282	0.1076171	0.4025329	1
60	0.601815	0.798636	0.753554	1.327045	1.252136	1.661640	0.1077822	0.4020203	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	53°–54° Involute	Minutes

↑ 126° or 306° 53° or 233° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 37° or 217° Trigonometric and Involute Functions 142° or 322° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 37°–38°	Read Up	Minutes
0	0.601815	0.798636	0.753554	1.327045	1.252136	1.661640	0.1077822	0.4020203	60
1	0.602047	0.798460	0.754010	1.326242	1.252410	1.660999	0.1079475	0.4015084	59
2	0.602280	0.798285	0.754467	1.325440	1.252685	1.660359	0.1081130	0.4009970	58
3	0.602512	0.798110	0.754923	1.324638	1.252960	1.659719	0.1082787	0.4004863	57
4	0.602744	0.797935	0.755380	1.323837	1.253235	1.659080	0.1084445	0.3999762	56
5	0.602976	0.797759	0.755837	1.323037	1.253511	1.658441	0.1086106	0.3994667	55
6	0.603208	0.797584	0.756294	1.322237	1.253787	1.657803	0.1087769	0.3989578	54
7	0.603440	0.797408	0.756751	1.321438	1.254062	1.657166	0.1089434	0.3984496	53
8	0.603672	0.797233	0.757209	1.320639	1.254339	1.656529	0.1091101	0.3979419	52
9	0.603904	0.797057	0.757667	1.319841	1.254615	1.655893	0.1092770	0.3974349	51
10	0.604136	0.796882	0.758125	1.319044	1.254892	1.655258	0.1094440	0.3969285	50
11	0.604367	0.796706	0.758583	1.318247	1.255169	1.654623	0.1096113	0.3964227	49
12	0.604599	0.796530	0.759041	1.317451	1.255446	1.653989	0.1097788	0.3959175	48
13	0.604831	0.796354	0.759500	1.316656	1.255723	1.653355	0.1099465	0.3954129	47
14	0.605062	0.796178	0.759959	1.315861	1.256000	1.652722	0.1101144	0.3949089	46
15	0.605294	0.796002	0.760418	1.315067	1.256278	1.652090	0.1102825	0.3944056	45
16	0.605526	0.795826	0.760877	1.314273	1.256556	1.651458	0.1104508	0.3939028	44
17	0.605757	0.795650	0.761336	1.313480	1.256834	1.650827	0.1106193	0.3934007	43
18	0.605988	0.795473	0.761796	1.312688	1.257113	1.650197	0.1107880	0.3928991	42
19	0.606220	0.795297	0.762256	1.311896	1.257392	1.649567	0.1109570	0.3923982	41
20	0.606451	0.795121	0.762716	1.311105	1.257671	1.648938	0.1111261	0.3918978	40
21	0.606682	0.794944	0.763176	1.310314	1.257950	1.648309	0.1112954	0.3913981	39
22	0.606914	0.794768	0.763636	1.309524	1.258229	1.647681	0.1114649	0.3908990	38
23	0.607145	0.794591	0.764097	1.308735	1.258509	1.647054	0.1116347	0.3904004	37
24	0.607376	0.794415	0.764558	1.307946	1.258789	1.646427	0.1118046	0.3899025	36
25	0.607607	0.794238	0.765019	1.307157	1.259069	1.645801	0.1119747	0.3894052	35
26	0.607838	0.794061	0.765480	1.306370	1.259349	1.645175	0.1121451	0.3889085	34
27	0.608069	0.793884	0.765941	1.305583	1.259629	1.644551	0.1123156	0.3884123	33
28	0.608300	0.793707	0.766403	1.304796	1.259910	1.643926	0.1124864	0.3879168	32
29	0.608531	0.793530	0.766865	1.304011	1.260191	1.643303	0.1126573	0.3874219	31
30	0.608761	0.793353	0.767327	1.303225	1.260472	1.642680	0.1128285	0.3869275	30
31	0.608992	0.793176	0.767789	1.302441	1.260754	1.642057	0.1129999	0.3864338	29
32	0.609223	0.792999	0.768252	1.301657	1.261036	1.641435	0.1131715	0.3859406	28
33	0.609454	0.792822	0.768714	1.300873	1.261317	1.640814	0.1133433	0.3854481	27
34	0.609684	0.792644	0.769177	1.300090	1.261600	1.640194	0.1135153	0.3849561	26
35	0.609915	0.792467	0.769640	1.299308	1.261882	1.639574	0.1136875	0.3844647	25
36	0.610145	0.792290	0.770104	1.298526	1.262165	1.638954	0.1138599	0.3839739	24
37	0.610376	0.792112	0.770567	1.297745	1.262448	1.638335	0.1140325	0.3834837	23
38	0.610606	0.791935	0.771031	1.296965	1.262731	1.637717	0.1142053	0.3829941	22
39	0.610836	0.791757	0.771495	1.296185	1.263014	1.637100	0.1143784	0.3825051	21
40	0.611067	0.791579	0.771959	1.295406	1.263298	1.636483	0.1145516	0.3820167	20
41	0.611297	0.791401	0.772423	1.294627	1.263581	1.635866	0.1147250	0.3815289	19
42	0.611527	0.791224	0.772888	1.293849	1.263865	1.635251	0.1148987	0.3810416	18
43	0.611757	0.791046	0.773353	1.293071	1.264150	1.634636	0.1150726	0.3805549	17
44	0.611987	0.790868	0.773818	1.292294	1.264434	1.634021	0.1152466	0.3800689	16
45	0.612217	0.790690	0.774283	1.291518	1.264719	1.633407	0.1154209	0.3795834	15
46	0.612447	0.790511	0.774748	1.290742	1.265004	1.632794	0.1155954	0.3790984	14
47	0.612677	0.790333	0.775214	1.289967	1.265289	1.632181	0.1157701	0.3786141	13
48	0.612907	0.790155	0.775680	1.289192	1.265574	1.631569	0.1159451	0.3781304	12
49	0.613137	0.789977	0.776146	1.288418	1.265860	1.630957	0.1161202	0.3776472	11
50	0.613367	0.789798	0.776612	1.287645	1.266146	1.630346	0.1162955	0.3771646	10
51	0.613596	0.789620	0.777078	1.286872	1.266432	1.629736	0.1164711	0.3766826	9
52	0.613826	0.789441	0.777545	1.286099	1.266719	1.629126	0.1166468	0.3762012	8
53	0.614056	0.789263	0.778012	1.285328	1.267005	1.628517	0.1168228	0.3757203	7
54	0.614285	0.789084	0.778479	1.284557	1.267292	1.627908	0.1169990	0.3752400	6
55	0.614515	0.788905	0.778946	1.283786	1.267579	1.627300	0.1171754	0.3747603	5
56	0.614744	0.788727	0.779414	1.283016	1.267866	1.626693	0.1173520	0.3742812	4
57	0.614974	0.788548	0.779881	1.282247	1.268154	1.626086	0.1175288	0.3738026	3
58	0.615203	0.788369	0.780349	1.281478	1.268442	1.625480	0.1177058	0.3733247	2
59	0.615432	0.788190	0.780817	1.280709	1.268730	1.624874	0.1178831	0.3728473	1
60	0.615661	0.788011	0.781286	1.279942	1.269018	1.624269	0.1180605	0.3723704	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	52°–53° Involute	Minutes

↑ 127° or 307° 52° or 232° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 38° or 218° Trigonometric and Involute Functions 141° or 321° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 38°–39°	Read Up	Minutes
0	0.615661	0.788011	0.781286	1.279942	1.269018	1.624269	0.1180605	0.3723704	60
1	0.615891	0.787832	0.781754	1.279174	1.269307	1.623665	0.1182382	0.3718942	59
2	0.616120	0.787652	0.782223	1.278408	1.269596	1.623061	0.1184161	0.3714185	58
3	0.616349	0.787473	0.782692	1.277642	1.269885	1.622458	0.1185942	0.3709433	57
4	0.616578	0.787294	0.783161	1.276876	1.270174	1.621855	0.1187725	0.3704688	56
5	0.616807	0.787114	0.783631	1.276112	1.270463	1.621253	0.1189510	0.3699948	55
6	0.617036	0.786935	0.784100	1.275347	1.270753	1.620651	0.1191297	0.3695214	54
7	0.617265	0.786756	0.784570	1.274584	1.271043	1.620050	0.1193087	0.3690485	53
8	0.617494	0.786576	0.785040	1.273820	1.271333	1.619450	0.1194878	0.3685763	52
9	0.617722	0.786396	0.785510	1.273058	1.271624	1.618850	0.1196672	0.3681045	51
10	0.617951	0.786217	0.785981	1.272296	1.271914	1.618251	0.1198468	0.3676334	50
11	0.618180	0.786037	0.786451	1.271534	1.272205	1.617652	0.1200266	0.3671628	49
12	0.618408	0.785857	0.786922	1.270773	1.272496	1.617054	0.1202066	0.3666928	48
13	0.618637	0.785677	0.787394	1.270013	1.272788	1.616457	0.1203869	0.3662233	47
14	0.618865	0.785497	0.787865	1.269253	1.273079	1.615860	0.1205673	0.3657544	46
15	0.619094	0.785317	0.788336	1.268494	1.273371	1.615264	0.1207480	0.3652861	45
16	0.619322	0.785137	0.788808	1.267735	1.273663	1.614668	0.1209289	0.3648183	44
17	0.619551	0.784957	0.789280	1.266977	1.273956	1.614073	0.1211100	0.3643511	43
18	0.619779	0.784776	0.789752	1.266220	1.274248	1.613478	0.1212913	0.3638844	42
19	0.620007	0.784596	0.790225	1.265463	1.274541	1.612884	0.1214728	0.3634183	41
20	0.620235	0.784416	0.790697	1.264706	1.274834	1.612291	0.1216546	0.3629527	40
21	0.620464	0.784235	0.791170	1.263950	1.275128	1.611698	0.1218366	0.3624878	39
22	0.620692	0.784055	0.791643	1.263195	1.275421	1.611106	0.1220188	0.3620233	38
23	0.620920	0.783874	0.792117	1.262440	1.275715	1.610514	0.1222012	0.3615594	37
24	0.621148	0.783693	0.792590	1.261686	1.276009	1.609923	0.1223838	0.3610961	36
25	0.621376	0.783513	0.793064	1.260932	1.276303	1.609332	0.1225666	0.3606333	35
26	0.621604	0.783332	0.793538	1.260179	1.276598	1.608742	0.1227497	0.3601711	34
27	0.621831	0.783151	0.794012	1.259427	1.276893	1.608153	0.1229330	0.3597094	33
28	0.622059	0.782970	0.794486	1.258675	1.277188	1.607564	0.1231165	0.3592483	32
29	0.622287	0.782789	0.794961	1.257923	1.277483	1.606976	0.1233002	0.3587878	31
30	0.622515	0.782608	0.795436	1.257172	1.277779	1.606388	0.1234842	0.3583277	30
31	0.622742	0.782427	0.795911	1.256422	1.278074	1.605801	0.1236683	0.3578683	29
32	0.622970	0.782246	0.796386	1.255672	1.278370	1.605214	0.1238527	0.3574093	28
33	0.623197	0.782065	0.796862	1.254923	1.278667	1.604628	0.1240373	0.3569510	27
34	0.623425	0.781883	0.797337	1.254174	1.278963	1.604043	0.1242221	0.3564931	26
35	0.623652	0.781702	0.797813	1.253426	1.279260	1.603458	0.1244072	0.3560359	25
36	0.623880	0.781520	0.798290	1.252678	1.279557	1.602873	0.1245924	0.3555791	24
37	0.624107	0.781339	0.798766	1.251931	1.279854	1.602290	0.1247779	0.3551229	23
38	0.624334	0.781157	0.799242	1.251185	1.280152	1.601706	0.1249636	0.3546673	22
39	0.624561	0.780976	0.799719	1.250439	1.280450	1.601124	0.1251495	0.3542122	21
40	0.624789	0.780794	0.800196	1.249693	1.280748	1.600542	0.1253357	0.3537576	20
41	0.625016	0.780612	0.800674	1.248948	1.281046	1.599960	0.1255221	0.3533036	19
42	0.625243	0.780430	0.801151	1.248204	1.281344	1.599379	0.1257087	0.3528501	18
43	0.625470	0.780248	0.801629	1.247460	1.281643	1.598799	0.1258955	0.3523972	17
44	0.625697	0.780067	0.802107	1.246717	1.281942	1.598219	0.1260825	0.3519448	16
45	0.625923	0.779884	0.802585	1.245974	1.282241	1.597639	0.1262698	0.3514929	15
46	0.626150	0.779702	0.803063	1.245232	1.282541	1.597061	0.1264573	0.3510416	14
47	0.626377	0.779520	0.803542	1.244490	1.282840	1.596482	0.1266450	0.3505908	13
48	0.626604	0.779338	0.804021	1.243749	1.283140	1.595905	0.1268329	0.3501406	12
49	0.626830	0.779156	0.804500	1.243009	1.283441	1.595328	0.1270210	0.3496909	11
50	0.627057	0.778973	0.804979	1.242268	1.283741	1.594751	0.1272094	0.3492417	10
51	0.627284	0.778791	0.805458	1.241529	1.284042	1.594175	0.1273980	0.3487931	9
52	0.627510	0.778608	0.805938	1.240790	1.284343	1.593600	0.1275869	0.3483450	8
53	0.627737	0.778426	0.806418	1.240052	1.284644	1.593025	0.1277759	0.3478974	7
54	0.627963	0.778243	0.806898	1.239314	1.284945	1.592450	0.1279652	0.3474503	6
55	0.628189	0.778060	0.807379	1.238576	1.285247	1.591877	0.1281547	0.3470038	5
56	0.628416	0.777878	0.807859	1.237839	1.285549	1.591303	0.1283444	0.3465579	4
57	0.628642	0.777695	0.808340	1.237103	1.285851	1.590731	0.1285344	0.3461124	3
58	0.628868	0.777512	0.808821	1.236367	1.286154	1.590158	0.1287246	0.3456675	2
59	0.629094	0.777329	0.809303	1.235632	1.286457	1.589587	0.1289150	0.3452231	1
60	0.629320	0.777146	0.809784	1.234897	1.286760	1.589016	0.1291056	0.3447792	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	51°–52° Involute	Minutes

↑ 128° or 308° 51° or 231° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 39° or 219° Trigonometric and Involute Functions 140° or 320° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 39°–40°	Read Up	Minutes
0	0.629320	0.777146	0.809784	1.234897	1.286760	1.589016	0.1291056	0.3447792	60
1	0.629546	0.776963	0.810266	1.234163	1.287063	1.588445	0.1292965	0.3443359	59
2	0.629772	0.776780	0.810748	1.233429	1.287366	1.587875	0.1294876	0.3438931	58
3	0.629998	0.776596	0.811230	1.232696	1.287670	1.587306	0.1296789	0.3434508	57
4	0.630224	0.776413	0.811712	1.231963	1.287974	1.586737	0.1298704	0.3430091	56
5	0.630450	0.776230	0.812195	1.231231	1.288278	1.586169	0.1300622	0.3425678	55
6	0.630676	0.776046	0.812678	1.230500	1.288583	1.585601	0.1302542	0.3421271	54
7	0.630902	0.775863	0.813161	1.229769	1.288887	1.585033	0.1304464	0.3416870	53
8	0.631127	0.775679	0.813644	1.229038	1.289192	1.584467	0.1306389	0.3412473	52
9	0.631353	0.775496	0.814128	1.228308	1.289498	1.583900	0.1308316	0.3408082	51
10	0.631578	0.775312	0.814612	1.227579	1.289803	1.583335	0.1310245	0.3403695	50
11	0.631804	0.775128	0.815096	1.226850	1.290109	1.582770	0.1312177	0.3399315	49
12	0.632029	0.774944	0.815580	1.226121	1.290415	1.582205	0.1314110	0.3394939	48
13	0.632255	0.774761	0.816065	1.225393	1.290721	1.581641	0.1316046	0.3390568	47
14	0.632480	0.774577	0.816549	1.224666	1.291028	1.581078	0.1317985	0.3386203	46
15	0.632705	0.774393	0.817034	1.223939	1.291335	1.580515	0.1319925	0.3381843	45
16	0.632931	0.774209	0.817519	1.223212	1.291642	1.579952	0.1321868	0.3377488	44
17	0.633156	0.774024	0.818005	1.222487	1.291949	1.579390	0.1323814	0.3373138	43
18	0.633381	0.773840	0.818491	1.221761	1.292256	1.578829	0.1325761	0.3368793	42
19	0.633606	0.773656	0.818976	1.221036	1.292564	1.578268	0.1327711	0.3364454	41
20	0.633831	0.773472	0.819463	1.220312	1.292872	1.577708	0.1329663	0.3360119	40
21	0.634056	0.773287	0.819949	1.219588	1.293181	1.577148	0.1331618	0.3355790	39
22	0.634281	0.773103	0.820435	1.218865	1.293489	1.576589	0.1333575	0.3351466	38
23	0.634506	0.772918	0.820922	1.218142	1.293798	1.576030	0.1335534	0.3347147	37
24	0.634731	0.772734	0.821409	1.217420	1.294107	1.575472	0.1337495	0.3342833	36
25	0.634955	0.772549	0.821897	1.216698	1.294416	1.574914	0.1339459	0.3338524	35
26	0.635180	0.772364	0.822384	1.215977	1.294726	1.574357	0.1341425	0.3334221	34
27	0.635405	0.772179	0.822872	1.215256	1.295036	1.573800	0.1343394	0.3329922	33
28	0.635629	0.771995	0.823360	1.214536	1.295346	1.573244	0.1345365	0.3325629	32
29	0.635854	0.771810	0.823848	1.213816	1.295656	1.572689	0.1347338	0.3321341	31
30	0.636078	0.771625	0.824336	1.213097	1.295967	1.572134	0.1349313	0.3317057	30
31	0.636303	0.771440	0.824825	1.212378	1.296278	1.571579	0.1351291	0.3312779	29
32	0.636527	0.771254	0.825314	1.211660	1.296589	1.571025	0.1353271	0.3308506	28
33	0.636751	0.771069	0.825803	1.210942	1.296900	1.570472	0.1355254	0.3304238	27
34	0.636976	0.770884	0.826292	1.210225	1.297212	1.569919	0.1357239	0.3299975	26
35	0.637200	0.770699	0.826782	1.209509	1.297524	1.569366	0.1359226	0.3295717	25
36	0.637424	0.770513	0.827272	1.208792	1.297836	1.568815	0.1361216	0.3291464	24
37	0.637648	0.770328	0.827762	1.208077	1.298149	1.568263	0.1363208	0.3287216	23
38	0.637872	0.770142	0.828252	1.207362	1.298461	1.567712	0.1365202	0.3282973	22
39	0.638096	0.769957	0.828743	1.206647	1.298774	1.567162	0.1367199	0.3278736	21
40	0.638320	0.769771	0.829234	1.205933	1.299088	1.566612	0.1369198	0.3274503	20
41	0.638544	0.769585	0.829725	1.205219	1.299401	1.566063	0.1371199	0.3270275	19
42	0.638768	0.769400	0.830216	1.204506	1.299715	1.565514	0.1373203	0.3266052	18
43	0.638992	0.769214	0.830707	1.203793	1.300029	1.564966	0.1375209	0.3261834	17
44	0.639215	0.769028	0.831199	1.203081	1.300343	1.564418	0.1377218	0.3257621	16
45	0.639439	0.768842	0.831691	1.202369	1.300658	1.563871	0.1379228	0.3253414	15
46	0.639663	0.768656	0.832183	1.201658	1.300972	1.563324	0.1381242	0.3249211	14
47	0.639886	0.768470	0.832676	1.200947	1.301287	1.562778	0.1383257	0.3245013	13
48	0.640110	0.768284	0.833169	1.200237	1.301603	1.562232	0.1385275	0.3240820	12
49	0.640333	0.768097	0.833662	1.199528	1.301918	1.561687	0.1387296	0.3236632	11
50	0.640557	0.767911	0.834155	1.198818	1.302234	1.561142	0.1389319	0.3232449	10
51	0.640780	0.767725	0.834648	1.198110	1.302550	1.560598	0.1391344	0.3228271	9
52	0.641003	0.767538	0.835142	1.197402	1.302867	1.560055	0.1393372	0.3224098	8
53	0.641226	0.767352	0.835636	1.196694	1.303183	1.559511	0.1395402	0.3219930	7
54	0.641450	0.767165	0.836130	1.195987	1.303500	1.558969	0.1397434	0.3215766	6
55	0.641673	0.766979	0.836624	1.195280	1.303817	1.558427	0.1399469	0.3211608	5
56	0.641896	0.766792	0.837119	1.194574	1.304135	1.557885	0.1401506	0.3207454	4
57	0.642119	0.766605	0.837614	1.193868	1.304453	1.557344	0.1403546	0.3203306	3
58	0.642342	0.766418	0.838109	1.193163	1.304771	1.556803	0.1405588	0.3199162	2
59	0.642565	0.766231	0.838604	1.192458	1.305089	1.556263	0.1407632	0.3195024	1
60	0.642788	0.766044	0.839100	1.191754	1.305407	1.555724	0.1409679	0.3190890	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	50°–51° Involute	Minutes

↑ 129° or 309° 50° or 230° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 40° or 220° Trigonometric and Involute Functions 139° or 319° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 40°–41°	Read Up	Minutes
0	0.642788	0.766044	0.839100	1.191754	1.305407	1.555724	0.1409679	0.3190890	60
1	0.643010	0.765857	0.839595	1.191050	1.305726	1.555185	0.1411729	0.3186761	59
2	0.643233	0.765670	0.840092	1.190347	1.306045	1.554646	0.1413780	0.3182637	58
3	0.643456	0.765483	0.840588	1.189644	1.306364	1.554108	0.1415835	0.3178517	57
4	0.643679	0.765296	0.841084	1.188941	1.306684	1.553571	0.1417891	0.3174403	56
5	0.643901	0.765109	0.841581	1.188240	1.307004	1.553034	0.1419950	0.3170293	55
6	0.644124	0.764921	0.842078	1.187538	1.307324	1.552497	0.1422012	0.3166189	54
7	0.644346	0.764734	0.842575	1.186837	1.307644	1.551961	0.1424076	0.3162089	53
8	0.644569	0.764547	0.843073	1.186137	1.307965	1.551425	0.1426142	0.3157994	52
9	0.644791	0.764359	0.843571	1.185437	1.308286	1.550890	0.1428211	0.3153904	51
10	0.645013	0.764171	0.844069	1.184738	1.308607	1.550356	0.1430282	0.3149819	50
11	0.645235	0.763984	0.844567	1.184039	1.308928	1.549822	0.1432355	0.3145738	49
12	0.645458	0.763796	0.845066	1.183340	1.309250	1.549288	0.1434432	0.3141662	48
13	0.645680	0.763608	0.845564	1.182642	1.309572	1.548755	0.1436510	0.3137591	47
14	0.645902	0.763420	0.846063	1.181945	1.309894	1.548223	0.1438591	0.3133525	46
15	0.646124	0.763232	0.846562	1.181248	1.310217	1.547691	0.1440675	0.3129464	45
16	0.646346	0.763044	0.847062	1.180551	1.310540	1.547159	0.1442761	0.3125408	44
17	0.646568	0.762856	0.847562	1.179855	1.310863	1.546628	0.1444849	0.3121356	43
18	0.646790	0.762668	0.848062	1.179160	1.311186	1.546097	0.1446940	0.3117309	42
19	0.647012	0.762480	0.848562	1.178464	1.311510	1.545567	0.1449033	0.3113267	41
20	0.647233	0.762292	0.849062	1.177770	1.311833	1.545038	0.1451129	0.3109229	40
21	0.647455	0.762104	0.849563	1.177076	1.312158	1.544509	0.1453227	0.3105197	39
22	0.647677	0.761915	0.850064	1.176382	1.312482	1.543980	0.1455328	0.3101169	38
23	0.647898	0.761727	0.850565	1.175689	1.312807	1.543452	0.1457431	0.3097146	37
24	0.648120	0.761538	0.851067	1.174996	1.313132	1.542924	0.1459537	0.3093127	36
25	0.648341	0.761350	0.851568	1.174304	1.313457	1.542397	0.1461645	0.3089113	35
26	0.648563	0.761161	0.852070	1.173612	1.313782	1.541871	0.1463756	0.3085105	34
27	0.648784	0.760972	0.852573	1.172921	1.314108	1.541345	0.1465869	0.3081100	33
28	0.649006	0.760784	0.853075	1.172230	1.314434	1.540819	0.1467985	0.3077101	32
29	0.649227	0.760595	0.853578	1.171539	1.314760	1.540294	0.1470103	0.3073106	31
30	0.649448	0.760406	0.854081	1.170850	1.315087	1.539769	0.1472223	0.3069116	30
31	0.649669	0.760217	0.854584	1.170160	1.315414	1.539245	0.1474347	0.3065130	29
32	0.649890	0.760028	0.855087	1.169471	1.315741	1.538721	0.1476472	0.3061150	28
33	0.650111	0.759839	0.855591	1.168783	1.316068	1.538198	0.1478600	0.3057174	27
34	0.650332	0.759650	0.856095	1.168095	1.316396	1.537675	0.1480731	0.3053202	26
35	0.650553	0.759461	0.856599	1.167407	1.316724	1.537153	0.1482864	0.3049236	25
36	0.650774	0.759271	0.857104	1.166720	1.317052	1.536631	0.1485000	0.3045274	24
37	0.650995	0.759082	0.857608	1.166033	1.317381	1.536110	0.1487138	0.3041316	23
38	0.651216	0.758893	0.858113	1.165347	1.317710	1.535589	0.1489279	0.3037364	22
39	0.651437	0.758703	0.858619	1.164662	1.318039	1.535069	0.1491422	0.3033416	21
40	0.651657	0.758514	0.859124	1.163976	1.318368	1.534549	0.1493568	0.3029472	20
41	0.651878	0.758324	0.859630	1.163292	1.318698	1.534030	0.1495716	0.3025533	19
42	0.652098	0.758134	0.860136	1.162607	1.319027	1.533511	0.1497867	0.3021599	18
43	0.652319	0.757945	0.860642	1.161923	1.319358	1.532993	0.1500020	0.3017670	17
44	0.652539	0.757755	0.861148	1.161240	1.319688	1.532475	0.1502176	0.3013745	16
45	0.652760	0.757565	0.861655	1.160557	1.320019	1.531957	0.1504335	0.3009825	15
46	0.652980	0.757375	0.862162	1.159875	1.320350	1.531440	0.1506496	0.3005909	14
47	0.653200	0.757185	0.862669	1.159193	1.320681	1.530924	0.1508659	0.3001998	13
48	0.653421	0.756995	0.863177	1.158511	1.321013	1.530408	0.1510825	0.2998092	12
49	0.653641	0.756805	0.863685	1.157830	1.321344	1.529892	0.1512994	0.2994190	11
50	0.653861	0.756615	0.864193	1.157149	1.321677	1.529377	0.1515165	0.2990292	10
51	0.654081	0.756425	0.864701	1.156469	1.322009	1.528863	0.1517339	0.2986400	9
52	0.654301	0.756234	0.865209	1.155790	1.322342	1.528349	0.1519515	0.2982512	8
53	0.654521	0.756044	0.865718	1.155110	1.322675	1.527835	0.1521694	0.2978628	7
54	0.654741	0.755853	0.866227	1.154432	1.323008	1.527322	0.1523875	0.2974749	6
55	0.654961	0.755663	0.866736	1.153753	1.323341	1.526809	0.1526059	0.2970875	5
56	0.655180	0.755472	0.867246	1.153075	1.323675	1.526297	0.1528246	0.2967005	4
57	0.655400	0.755282	0.867756	1.152398	1.324009	1.525785	0.1530435	0.2963140	3
58	0.655620	0.755091	0.868266	1.151721	1.324343	1.525274	0.1532626	0.2959279	2
59	0.655839	0.754900	0.868776	1.151044	1.324678	1.524763	0.1534821	0.2955422	1
60	0.656059	0.754710	0.869287	1.150368	1.325013	1.524253	0.1537017	0.2951571	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	49°–50° Involute	Minutes

↑ 130° or 310° 49° or 229° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 41° or 221° Trigonometric and Involute Functions 138° or 318° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 41°–42°	Read Up	Minutes
0	0.656059	0.754710	0.869287	1.150368	1.325013	1.524253	0.1537017	0.2951571	60
1	0.656279	0.754519	0.869798	1.149693	1.325348	1.523743	0.1539217	0.2947724	59
2	0.656498	0.754328	0.870309	1.149018	1.325684	1.523234	0.1541419	0.2943881	58
3	0.656717	0.754137	0.870820	1.148343	1.326019	1.522725	0.1543623	0.2940043	57
4	0.656937	0.753946	0.871332	1.147669	1.326355	1.522217	0.1545831	0.2936209	56
5	0.657156	0.753755	0.871843	1.146995	1.326692	1.521709	0.1548040	0.2932380	55
6	0.657375	0.753563	0.872356	1.146322	1.327028	1.521201	0.1550253	0.2928555	54
7	0.657594	0.753372	0.872868	1.145649	1.327365	1.520694	0.1552468	0.2924735	53
8	0.657814	0.753181	0.873381	1.144976	1.327702	1.520188	0.1554685	0.2920919	52
9	0.658033	0.752989	0.873894	1.144304	1.328040	1.519682	0.1556906	0.2917108	51
10	0.658252	0.752798	0.874407	1.143633	1.328378	1.519176	0.1559128	0.2913301	50
11	0.658471	0.752606	0.874920	1.142961	1.328716	1.518671	0.1561354	0.2909499	49
12	0.658689	0.752415	0.875434	1.142291	1.329054	1.518166	0.1563582	0.2905701	48
13	0.658908	0.752223	0.875948	1.141621	1.329393	1.517662	0.1565812	0.2901908	47
14	0.659127	0.752032	0.876462	1.140951	1.329731	1.517158	0.1568046	0.2898119	46
15	0.659346	0.751840	0.876976	1.140281	1.330071	1.516655	0.1570281	0.2894334	45
16	0.659564	0.751648	0.877491	1.139613	1.330410	1.516152	0.1572520	0.2890554	44
17	0.659783	0.751456	0.878006	1.138944	1.330750	1.515650	0.1574761	0.2886779	43
18	0.660002	0.751264	0.878521	1.138276	1.331090	1.515148	0.1577005	0.2883008	42
19	0.660220	0.751072	0.879037	1.137609	1.331430	1.514646	0.1579251	0.2879241	41
20	0.660439	0.750880	0.879553	1.136941	1.331771	1.514145	0.1581500	0.2875479	40
21	0.660657	0.750688	0.880069	1.136275	1.332112	1.513645	0.1583752	0.2871721	39
22	0.660875	0.750496	0.880585	1.135609	1.332453	1.513145	0.1586006	0.2867967	38
23	0.661094	0.750303	0.881102	1.134943	1.332794	1.512645	0.1588263	0.2864218	37
24	0.661312	0.750111	0.881619	1.134277	1.333136	1.512146	0.1590523	0.2860473	36
25	0.661530	0.749919	0.882136	1.133612	1.333478	1.511647	0.1592785	0.2856733	35
26	0.661748	0.749726	0.882653	1.132948	1.333820	1.511149	0.1595050	0.2852997	34
27	0.661966	0.749534	0.883171	1.132284	1.334163	1.510651	0.1597318	0.2849265	33
28	0.662184	0.749341	0.883689	1.131620	1.334506	1.510154	0.1599588	0.2845538	32
29	0.662402	0.749148	0.884207	1.130957	1.334849	1.509657	0.1601861	0.2841815	31
30	0.662620	0.748956	0.884725	1.130294	1.335192	1.509160	0.1604136	0.2838097	30
31	0.662838	0.748763	0.885244	1.129632	1.335536	1.508665	0.1606414	0.2834383	29
32	0.663056	0.748570	0.885763	1.128970	1.335880	1.508169	0.1608695	0.2830673	28
33	0.663273	0.748377	0.886282	1.128309	1.336225	1.507674	0.1610979	0.2826968	27
34	0.663491	0.748184	0.886802	1.127648	1.336569	1.507179	0.1613265	0.2823267	26
35	0.663709	0.747991	0.887321	1.126987	1.336914	1.506685	0.1615554	0.2819570	25
36	0.663926	0.747798	0.887842	1.126327	1.337259	1.506191	0.1617846	0.2815877	24
37	0.664144	0.747605	0.888362	1.125667	1.337605	1.505698	0.1620140	0.2812189	23
38	0.664361	0.747412	0.888882	1.125008	1.337951	1.505205	0.1622437	0.2808506	22
39	0.664579	0.747218	0.889403	1.124349	1.338297	1.504713	0.1624737	0.2804826	21
40	0.664796	0.747025	0.889924	1.123691	1.338643	1.504221	0.1627039	0.2801151	20
41	0.665013	0.746832	0.890446	1.123033	1.338990	1.503730	0.1629344	0.2797480	19
42	0.665230	0.746638	0.890967	1.122375	1.339337	1.503239	0.1631652	0.2793814	18
43	0.665448	0.746445	0.891489	1.121718	1.339684	1.502748	0.1633963	0.2790151	17
44	0.665665	0.746251	0.892012	1.121062	1.340032	1.502258	0.1636276	0.2786493	16
45	0.665882	0.746057	0.892534	1.120405	1.340379	1.501768	0.1638592	0.2782840	15
46	0.666099	0.745864	0.893057	1.119750	1.340728	1.501279	0.1640910	0.2779190	14
47	0.666316	0.745670	0.893580	1.119094	1.341076	1.500790	0.1643232	0.2775545	13
48	0.666532	0.745476	0.894103	1.118439	1.341425	1.500302	0.1645556	0.2771904	12
49	0.666749	0.745282	0.894627	1.117785	1.341774	1.499814	0.1647882	0.2768268	11
50	0.666966	0.745088	0.895151	1.117130	1.342123	1.499327	0.1650212	0.2764635	10
51	0.667183	0.744894	0.895675	1.116477	1.342473	1.498840	0.1652544	0.2761007	9
52	0.667399	0.744700	0.896199	1.115823	1.342823	1.498353	0.1654879	0.2757383	8
53	0.667616	0.744506	0.896724	1.115171	1.343173	1.497867	0.1657217	0.2753764	7
54	0.667833	0.744312	0.897249	1.114518	1.343523	1.497381	0.1659557	0.2750148	6
55	0.668049	0.744117	0.897774	1.113866	1.343874	1.496896	0.1661900	0.2746537	5
56	0.668265	0.743923	0.898299	1.113215	1.344225	1.496411	0.1664246	0.2742930	4
57	0.668482	0.743728	0.898825	1.112563	1.344577	1.495927	0.1666595	0.2739328	3
58	0.668698	0.743534	0.899351	1.111913	1.344928	1.495443	0.1668946	0.2735729	2
59	0.668914	0.743339	0.899877	1.111262	1.345280	1.494960	0.1671301	0.2732135	1
60	0.669131	0.743145	0.900404	1.110613	1.345633	1.494477	0.1673658	0.2728545	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	48°–49° Involute	Minutes

↑ 131° or 311° 48° or 228° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 42° or 222° Trigonometric and Involute Functions 137° or 317° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 42°–43°	Read Up	Minutes
0	0.669131	0.743145	0.900404	1.110613	1.345633	1.494477	0.1673658	0.2728545	60
1	0.669347	0.742950	0.900931	1.109963	1.345985	1.493994	0.1676017	0.2724959	59
2	0.669563	0.742755	0.901458	1.109314	1.346338	1.493512	0.1678380	0.2721377	58
3	0.669779	0.742561	0.901985	1.108665	1.346691	1.493030	0.1680745	0.2717800	57
4	0.669995	0.742366	0.902513	1.108017	1.347045	1.492549	0.1683113	0.2714226	56
5	0.670211	0.742171	0.903041	1.107369	1.347399	1.492068	0.1685484	0.2710657	55
6	0.670427	0.741976	0.903569	1.106722	1.347753	1.491588	0.1687857	0.2707092	54
7	0.670642	0.741781	0.904098	1.106075	1.348107	1.491108	0.1690234	0.2703531	53
8	0.670858	0.741586	0.904627	1.105428	1.348462	1.490628	0.1692613	0.2699975	52
9	0.671074	0.741391	0.905156	1.104782	1.348817	1.490149	0.1694994	0.2696422	51
10	0.671289	0.741195	0.905685	1.104137	1.349172	1.489670	0.1697379	0.2692874	50
11	0.671505	0.741000	0.906215	1.103491	1.349528	1.489192	0.1699767	0.2689330	49
12	0.671721	0.740805	0.906745	1.102846	1.349884	1.488714	0.1702157	0.2685790	48
13	0.671936	0.740609	0.907275	1.102202	1.350240	1.488237	0.1704550	0.2682254	47
14	0.672151	0.740414	0.907805	1.101558	1.350596	1.487760	0.1706946	0.2678722	46
15	0.672367	0.740218	0.908336	1.100914	1.350953	1.487283	0.1709344	0.2675194	45
16	0.672582	0.740023	0.908867	1.100271	1.351310	1.486807	0.1711746	0.2671671	44
17	0.672797	0.739827	0.909398	1.099628	1.351668	1.486332	0.1714150	0.2668151	43
18	0.673013	0.739631	0.909930	1.098986	1.352025	1.485856	0.1716557	0.2664636	42
19	0.673228	0.739435	0.910462	1.098344	1.352383	1.485382	0.1718967	0.2661125	41
20	0.673443	0.739239	0.910994	1.097702	1.352742	1.484907	0.1721380	0.2657618	40
21	0.673658	0.739043	0.911526	1.097061	1.353100	1.484433	0.1723795	0.2654115	39
22	0.673873	0.738848	0.912059	1.096420	1.353459	1.483960	0.1726214	0.2650616	38
23	0.674088	0.738651	0.912592	1.095780	1.353818	1.483487	0.1728635	0.2647121	37
24	0.674302	0.738455	0.913125	1.095140	1.354178	1.483014	0.1731059	0.2643630	36
25	0.674517	0.738259	0.913659	1.094500	1.354538	1.482542	0.1733486	0.2640143	35
26	0.674732	0.738063	0.914193	1.093861	1.354898	1.482070	0.1735915	0.2636661	34
27	0.674947	0.737867	0.914727	1.093222	1.355258	1.481599	0.1738348	0.2633182	33
28	0.675161	0.737670	0.915261	1.092584	1.355619	1.481128	0.1740783	0.2629708	32
29	0.675376	0.737474	0.915796	1.091946	1.355980	1.480657	0.1743221	0.2626237	31
30	0.675590	0.737277	0.916331	1.091309	1.356342	1.480187	0.1745662	0.2622771	30
31	0.675805	0.737081	0.916866	1.090671	1.356703	1.479718	0.1748106	0.2619309	29
32	0.676019	0.736884	0.917402	1.090035	1.357065	1.479248	0.1750553	0.2615850	28
33	0.676233	0.736687	0.917938	1.089398	1.357428	1.478779	0.1753003	0.2612396	27
34	0.676448	0.736491	0.918474	1.088762	1.357790	1.478311	0.1755455	0.2608946	26
35	0.676662	0.736294	0.919010	1.088127	1.358153	1.477843	0.1757911	0.2605500	25
36	0.676876	0.736097	0.919547	1.087492	1.358516	1.477376	0.1760369	0.2602058	24
37	0.677090	0.735900	0.920084	1.086857	1.358880	1.476908	0.1762830	0.2598619	23
38	0.677304	0.735703	0.920621	1.086223	1.359244	1.476442	0.1765294	0.2595185	22
39	0.677518	0.735506	0.921159	1.085589	1.359608	1.475975	0.1767761	0.2591755	21
40	0.677732	0.735309	0.921697	1.084955	1.359972	1.475509	0.1770230	0.2588329	20
41	0.677946	0.735112	0.922235	1.084322	1.360337	1.475044	0.1772703	0.2584907	19
42	0.678160	0.734915	0.922773	1.083690	1.360702	1.474579	0.1775179	0.2581489	18
43	0.678373	0.734717	0.923312	1.083057	1.361068	1.474114	0.1777657	0.2578075	17
44	0.678587	0.734520	0.923851	1.082425	1.361433	1.473650	0.1780138	0.2574665	16
45	0.678801	0.734323	0.924390	1.081794	1.361799	1.473186	0.1782622	0.2571258	15
46	0.679014	0.734125	0.924930	1.081163	1.362166	1.472723	0.1785109	0.2567856	14
47	0.679228	0.733927	0.925470	1.080532	1.362532	1.472260	0.1787599	0.2564458	13
48	0.679441	0.733730	0.926010	1.079902	1.362899	1.471797	0.1790092	0.2561064	12
49	0.679655	0.733532	0.926551	1.079272	1.363267	1.471335	0.1792588	0.2557673	11
50	0.679868	0.733334	0.927091	1.078642	1.363634	1.470874	0.1795087	0.2554287	10
51	0.680081	0.733137	0.927632	1.078013	1.364002	1.470412	0.1797589	0.2550904	9
52	0.680295	0.732939	0.928174	1.077384	1.364370	1.469951	0.1800093	0.2547526	8
53	0.680508	0.732741	0.928715	1.076756	1.364739	1.469491	0.1802601	0.2544151	7
54	0.680721	0.732543	0.929257	1.076128	1.365108	1.469031	0.1805111	0.2540781	6
55	0.680934	0.732345	0.929800	1.075501	1.365477	1.468571	0.1807624	0.2537414	5
56	0.681147	0.732147	0.930342	1.074873	1.365846	1.468112	0.1810141	0.2534051	4
57	0.681360	0.731949	0.930885	1.074247	1.366216	1.467653	0.1812660	0.2530693	3
58	0.681573	0.731750	0.931428	1.073620	1.366586	1.467195	0.1815182	0.2527338	2
59	0.681786	0.731552	0.931971	1.072994	1.366957	1.466737	0.1817707	0.2523987	1
60	0.681998	0.731354	0.932515	1.072369	1.367327	1.466279	0.1820235	0.2520640	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	47°–48° Involute	Minutes

↑ 132° or 312° 47° or 227° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 43° or 223° Trigonometric and Involute Functions 136° or 316° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 43°–44°	Read Up	Minutes
0	0.681998	0.731354	0.932515	1.072369	1.367327	1.466279	0.1820235	0.2520640	60
1	0.682211	0.731155	0.933059	1.071744	1.367699	1.465822	0.1822766	0.2517296	59
2	0.682424	0.730957	0.933603	1.071119	1.368070	1.465365	0.1825300	0.2513957	58
3	0.682636	0.730758	0.934148	1.070494	1.368442	1.464909	0.1827837	0.2510622	57
4	0.682849	0.730560	0.934693	1.069870	1.368814	1.464453	0.1830377	0.2507290	56
5	0.683061	0.730361	0.935238	1.069247	1.369186	1.463997	0.1832920	0.2503963	55
6	0.683274	0.730162	0.935783	1.068623	1.369559	1.463542	0.1835465	0.2500639	54
7	0.683486	0.729963	0.936329	1.068000	1.369932	1.463087	0.1838014	0.2497319	53
8	0.683698	0.729765	0.936875	1.067378	1.370305	1.462633	0.1840566	0.2494003	52
9	0.683911	0.729566	0.937422	1.066756	1.370678	1.462179	0.1843121	0.2490691	51
10	0.684123	0.729367	0.937968	1.066134	1.371052	1.461726	0.1845678	0.2487383	50
11	0.684335	0.729168	0.938515	1.065513	1.371427	1.461273	0.1848239	0.2484078	49
12	0.684547	0.728969	0.939063	1.064892	1.371801	1.460820	0.1850803	0.2480778	48
13	0.684759	0.728769	0.939610	1.064271	1.372176	1.460368	0.1853369	0.2477481	47
14	0.684971	0.728570	0.940158	1.063651	1.372551	1.459916	0.1855939	0.2474188	46
15	0.685183	0.728371	0.940706	1.063031	1.372927	1.459464	0.1858512	0.2470899	45
16	0.685395	0.728172	0.941255	1.062412	1.373303	1.459013	0.1861087	0.2467614	44
17	0.685607	0.727972	0.941803	1.061793	1.373679	1.458562	0.1863666	0.2464332	43
18	0.685818	0.727773	0.942352	1.061174	1.374055	1.458112	0.1866248	0.2461055	42
19	0.686030	0.727573	0.942902	1.060556	1.374432	1.457662	0.1868832	0.2457781	41
20	0.686242	0.727374	0.943451	1.059938	1.374809	1.457213	0.1871420	0.2454511	40
21	0.686453	0.727174	0.944001	1.059321	1.375187	1.456764	0.1874011	0.2451245	39
22	0.686665	0.726974	0.944552	1.058703	1.375564	1.456315	0.1876604	0.2447982	38
23	0.686876	0.726775	0.945102	1.058087	1.375943	1.455867	0.1879201	0.2444724	37
24	0.687088	0.726575	0.945653	1.057470	1.376321	1.455419	0.1881801	0.2441469	36
25	0.687299	0.726375	0.946204	1.056854	1.376700	1.454971	0.1884404	0.2438218	35
26	0.687510	0.726175	0.946756	1.056239	1.377079	1.454524	0.1887010	0.2434971	34
27	0.687721	0.725975	0.947307	1.055624	1.377458	1.454077	0.1889619	0.2431728	33
28	0.687932	0.725775	0.947859	1.055009	1.377838	1.453631	0.1892230	0.2428488	32
29	0.688144	0.725575	0.948412	1.054394	1.378218	1.453185	0.1894845	0.2425252	31
30	0.688355	0.725374	0.948965	1.053780	1.378598	1.452740	0.1897463	0.2422020	30
31	0.688566	0.725174	0.949518	1.053166	1.378979	1.452295	0.1900084	0.2418792	29
32	0.688776	0.724974	0.950071	1.052553	1.379360	1.451850	0.1902709	0.2415567	28
33	0.688987	0.724773	0.950624	1.051940	1.379742	1.451406	0.1905336	0.2412347	27
34	0.689198	0.724573	0.951178	1.051328	1.380123	1.450962	0.1907966	0.2409130	26
35	0.689409	0.724372	0.951733	1.050715	1.380505	1.450518	0.1910599	0.2405916	25
36	0.689620	0.724172	0.952287	1.050103	1.380888	1.450075	0.1913236	0.2402707	24
37	0.689830	0.723971	0.952842	1.049492	1.381270	1.449632	0.1915875	0.2399501	23
38	0.690041	0.723771	0.953397	1.048881	1.381653	1.449190	0.1918518	0.2396299	22
39	0.690251	0.723570	0.953953	1.048270	1.382037	1.448748	0.1921163	0.2393101	21
40	0.690462	0.723369	0.954508	1.047660	1.382420	1.448306	0.1923812	0.2389906	20
41	0.690672	0.723168	0.955064	1.047050	1.382804	1.447865	0.1926464	0.2386715	19
42	0.690882	0.722967	0.955621	1.046440	1.383189	1.447424	0.1929119	0.2383528	18
43	0.691093	0.722766	0.956177	1.045831	1.383573	1.446984	0.1931777	0.2380344	17
44	0.691303	0.722565	0.956734	1.045222	1.383958	1.446544	0.1934438	0.2377165	16
45	0.691513	0.722364	0.957292	1.044614	1.384344	1.446104	0.1937102	0.2373988	15
46	0.691723	0.722163	0.957849	1.044006	1.384729	1.445665	0.1939769	0.2370816	14
47	0.691933	0.721962	0.958407	1.043398	1.385115	1.445226	0.1942440	0.2367647	13
48	0.692143	0.721760	0.958966	1.042790	1.385502	1.444788	0.1945113	0.2364482	12
49	0.692353	0.721559	0.959524	1.042183	1.385888	1.444350	0.1947790	0.2361321	11
50	0.692563	0.721357	0.960083	1.041577	1.386275	1.443912	0.1950469	0.2358163	10
51	0.692773	0.721156	0.960642	1.040970	1.386663	1.443475	0.1953152	0.2355010	9
52	0.692983	0.720954	0.961202	1.040364	1.387050	1.443038	0.1955838	0.2351859	8
53	0.693192	0.720753	0.961761	1.039759	1.387438	1.442601	0.1958527	0.2348713	7
54	0.693402	0.720551	0.962322	1.039154	1.387827	1.442165	0.1961220	0.2345570	6
55	0.693611	0.720349	0.962882	1.038549	1.388215	1.441729	0.1963915	0.2342430	5
56	0.693821	0.720148	0.963443	1.037944	1.388604	1.441294	0.1966613	0.2339295	4
57	0.694030	0.719946	0.964004	1.037340	1.388994	1.440859	0.1969315	0.2336163	3
58	0.694240	0.719744	0.964565	1.036737	1.389383	1.440425	0.1972020	0.2333034	2
59	0.694449	0.719542	0.965127	1.036133	1.389773	1.439990	0.1974728	0.2329910	1
60	0.694658	0.719340	0.965689	1.035530	1.390164	1.439557	0.1977439	0.2326789	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	46°–47° Involute	Minutes

↑ 133° or 313° 46° or 226° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

↓ 44° or 224° Trigonometric and Involute Functions 135° or 315° ↓

Minutes	Sine	Cosine	Tangent	Cotangent	Secant	Cosecant	Involute 44°–45°	Read Up	Minutes
0	0.694658	0.719340	0.965689	1.035530	1.390164	1.439557	0.1977439	0.2326789	60
1	0.694868	0.719138	0.966251	1.034928	1.390554	1.439123	0.1980153	0.2323671	59
2	0.695077	0.718936	0.966814	1.034325	1.390945	1.438690	0.1982871	0.2320557	58
3	0.695286	0.718733	0.967377	1.033724	1.391337	1.438257	0.1985591	0.2317447	57
4	0.695495	0.718531	0.967940	1.033122	1.391728	1.437825	0.1988315	0.2314341	56
5	0.695704	0.718329	0.968504	1.032521	1.392120	1.437393	0.1991042	0.2311238	55
6	0.695913	0.718126	0.969067	1.031920	1.392513	1.436962	0.1993772	0.2308138	54
7	0.696122	0.717924	0.969632	1.031319	1.392905	1.436531	0.1996505	0.2305042	53
8	0.696330	0.717721	0.970196	1.030719	1.393298	1.436100	0.1999242	0.2301950	52
9	0.696539	0.717519	0.970761	1.030120	1.393692	1.435669	0.2001982	0.2298862	51
10	0.696748	0.717316	0.971326	1.029520	1.394086	1.435239	0.2004724	0.2295777	50
11	0.696957	0.717113	0.971892	1.028921	1.394480	1.434810	0.2007471	0.2292695	49
12	0.697165	0.716911	0.972458	1.028323	1.394874	1.434380	0.2010220	0.2289618	48
13	0.697374	0.716708	0.973024	1.027724	1.395269	1.433952	0.2012972	0.2286543	47
14	0.697582	0.716505	0.973590	1.027126	1.395664	1.433523	0.2015728	0.2283473	46
15	0.697790	0.716302	0.974157	1.026529	1.396059	1.433095	0.2018487	0.2280406	45
16	0.697999	0.716099	0.974724	1.025931	1.396455	1.432667	0.2021249	0.2277342	44
17	0.698207	0.715896	0.975291	1.025335	1.396851	1.432240	0.2024014	0.2274282	43
18	0.698415	0.715693	0.975859	1.024738	1.397248	1.431813	0.2026783	0.2271226	42
19	0.698623	0.715490	0.976427	1.024142	1.397644	1.431386	0.2029554	0.2268173	41
20	0.698832	0.715286	0.976996	1.023546	1.398042	1.430960	0.2032329	0.2265124	40
21	0.699040	0.715083	0.977564	1.022951	1.398439	1.430534	0.2035108	0.2262078	39
22	0.699248	0.714880	0.978133	1.022356	1.398837	1.430109	0.2037889	0.2259036	38
23	0.699455	0.714676	0.978703	1.021761	1.399235	1.429684	0.2040674	0.2255997	37
24	0.699663	0.714473	0.979272	1.021166	1.399634	1.429259	0.2043462	0.2252962	36
25	0.699871	0.714269	0.979842	1.020572	1.400033	1.428834	0.2046253	0.2249931	35
26	0.700079	0.714066	0.980413	1.019979	1.400432	1.428410	0.2049047	0.2246903	34
27	0.700287	0.713862	0.980983	1.019385	1.400831	1.427987	0.2051845	0.2243878	33
28	0.700494	0.713658	0.981554	1.018792	1.401231	1.427564	0.2054646	0.2240857	32
29	0.700702	0.713454	0.982126	1.018200	1.401631	1.427141	0.2057450	0.2237840	31
30	0.700909	0.713250	0.982697	1.017607	1.402032	1.426718	0.2060257	0.2234826	30
31	0.701117	0.713047	0.983269	1.017015	1.402433	1.426296	0.2063068	0.2231815	29
32	0.701324	0.712843	0.983842	1.016424	1.402834	1.425874	0.2065882	0.2228808	28
33	0.701531	0.712639	0.984414	1.015833	1.403236	1.425453	0.2068699	0.2225805	27
34	0.701739	0.712434	0.984987	1.015242	1.403638	1.425032	0.2071520	0.2222805	26
35	0.701946	0.712230	0.985560	1.014651	1.404040	1.424611	0.2074344	0.2219808	25
36	0.702153	0.712026	0.986134	1.014061	1.404443	1.424191	0.2077171	0.2216815	24
37	0.702360	0.711822	0.986708	1.013471	1.404846	1.423771	0.2080001	0.2213826	23
38	0.702567	0.711617	0.987282	1.012882	1.405249	1.423351	0.2082835	0.2210840	22
39	0.702774	0.711413	0.987857	1.012293	1.405653	1.422932	0.2085672	0.2207857	21
40	0.702981	0.711209	0.988432	1.011704	1.406057	1.422513	0.2088512	0.2204878	20
41	0.703188	0.711004	0.989007	1.011115	1.406462	1.422095	0.2091356	0.2201903	19
42	0.703395	0.710799	0.989582	1.010527	1.406867	1.421677	0.2094203	0.2198930	18
43	0.703601	0.710595	0.990158	1.009939	1.407272	1.421259	0.2097053	0.2195962	17
44	0.703808	0.710390	0.990735	1.009352	1.407677	1.420842	0.2099907	0.2192996	16
45	0.704015	0.710185	0.991311	1.008765	1.408083	1.420425	0.2102764	0.2190035	15
46	0.704221	0.709981	0.991888	1.008178	1.408489	1.420008	0.2105624	0.2187076	14
47	0.704428	0.709776	0.992465	1.007592	1.408896	1.419592	0.2108487	0.2184121	13
48	0.704634	0.709571	0.993043	1.007006	1.409303	1.419176	0.2111354	0.2181170	12
49	0.704841	0.709366	0.993621	1.006420	1.409710	1.418761	0.2114225	0.2178222	11
50	0.705047	0.709161	0.994199	1.005835	1.410118	1.418345	0.2117098	0.2175277	10
51	0.705253	0.708956	0.994778	1.005250	1.410526	1.417931	0.2119975	0.2172336	9
52	0.705459	0.708750	0.995357	1.004665	1.410934	1.417516	0.2122855	0.2169398	8
53	0.705665	0.708545	0.995936	1.004081	1.411343	1.417102	0.2125739	0.2166464	7
54	0.705872	0.708340	0.996515	1.003497	1.411752	1.416688	0.2128626	0.2163533	6
55	0.706078	0.708134	0.997095	1.002913	1.412161	1.416275	0.2131516	0.2160605	5
56	0.706284	0.707929	0.997676	1.002330	1.412571	1.415862	0.2134410	0.2157681	4
57	0.706489	0.707724	0.998256	1.001747	1.412981	1.415449	0.2137307	0.2154760	3
58	0.706695	0.707518	0.998837	1.001164	1.413392	1.415037	0.2140207	0.2151843	2
59	0.706901	0.707312	0.999418	1.000582	1.413802	1.414625	0.2143111	0.2148929	1
60	0.707107	0.707107	1.000000	1.000000	1.414214	1.414214	0.2146018	0.2146018	0
Minutes	Cosine	Sine	Cotangent	Tangent	Cosecant	Secant	Read Down	45°–46° Involute	Minutes

↑ 134° or 314° 45° or 225° ↑

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 2.5-inch Sine-Bar

Constants for Setting a 2.5-inch Sine-Bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	0.043631	0.087249	0.130840	0.174391	0.217889	0.261321	0.304673
1	0.000727	0.044358	0.087976	0.131566	0.175117	0.218614	0.262044	0.305395
2	0.001454	0.045085	0.088702	0.132292	0.175842	0.219338	0.262768	0.306117
3	0.002182	0.045812	0.089429	0.133019	0.176567	0.220063	0.263491	0.306839
4	0.002909	0.046539	0.090156	0.133745	0.177293	0.220787	0.264214	0.307560
5	0.003636	0.047267	0.090883	0.134471	0.178018	0.221511	0.264937	0.308282
6	0.004363	0.047994	0.091609	0.135197	0.178744	0.222236	0.265660	0.309004
7	0.005091	0.048721	0.092336	0.135923	0.179469	0.222960	0.266383	0.309725
8	0.005818	0.049448	0.093063	0.136649	0.180194	0.223684	0.267106	0.310447
9	0.006545	0.050175	0.093789	0.137375	0.180920	0.224409	0.267829	0.311169
10	0.007272	0.050902	0.094516	0.138102	0.181645	0.225133	0.268552	0.311890
11	0.007999	0.051629	0.095243	0.138828	0.182370	0.225857	0.269275	0.312612
12	0.008727	0.052356	0.095970	0.139554	0.183095	0.226581	0.269998	0.313333
13	0.009454	0.053083	0.096696	0.140280	0.183821	0.227306	0.270721	0.314055
14	0.010181	0.053810	0.097423	0.141006	0.184546	0.228030	0.271444	0.314776
15	0.010908	0.054537	0.098150	0.141732	0.185271	0.228754	0.272167	0.315497
16	0.011635	0.055264	0.098876	0.142458	0.185996	0.229478	0.272890	0.316219
17	0.012363	0.055991	0.099603	0.143184	0.186722	0.230202	0.273613	0.316940
18	0.013090	0.056718	0.100329	0.143910	0.187447	0.230926	0.274336	0.317662
19	0.013817	0.057445	0.101056	0.144636	0.188172	0.231651	0.275059	0.318383
20	0.014544	0.058172	0.101783	0.145362	0.188897	0.232375	0.275781	0.319104
21	0.015272	0.058899	0.102509	0.146088	0.189622	0.233099	0.276504	0.319825
22	0.015999	0.059626	0.103236	0.146814	0.190347	0.233823	0.277227	0.320547
23	0.016726	0.060353	0.103963	0.147540	0.191072	0.234547	0.277950	0.321268
24	0.017453	0.061080	0.104689	0.148266	0.191798	0.235271	0.278672	0.321989
25	0.018180	0.061807	0.105416	0.148992	0.192523	0.235995	0.279395	0.322710
26	0.018908	0.062534	0.106142	0.149718	0.193248	0.236719	0.280118	0.323431
27	0.019635	0.063261	0.106869	0.150444	0.193973	0.237443	0.280840	0.324152
28	0.020362	0.063988	0.107595	0.151170	0.194698	0.238167	0.281563	0.324873
29	0.021089	0.064715	0.108322	0.151895	0.195423	0.238890	0.282285	0.325594
30	0.021816	0.065442	0.109048	0.152621	0.196148	0.239614	0.283008	0.326315
31	0.022544	0.066169	0.109775	0.153347	0.196873	0.240338	0.283731	0.327036
32	0.023271	0.066896	0.110502	0.154073	0.197598	0.241062	0.284453	0.327757
33	0.023998	0.067623	0.111228	0.154799	0.198323	0.241786	0.285176	0.328478
34	0.024725	0.068350	0.111955	0.155525	0.199048	0.242510	0.285898	0.329199
35	0.025452	0.069077	0.112681	0.156251	0.199772	0.243234	0.286620	0.329920
36	0.026179	0.069804	0.113407	0.156976	0.200497	0.243957	0.287343	0.330641
37	0.026907	0.070531	0.114134	0.157702	0.201222	0.244681	0.288065	0.331362
38	0.027634	0.071258	0.114860	0.158428	0.201947	0.245405	0.288788	0.332083
39	0.028361	0.071985	0.115587	0.159154	0.202672	0.246128	0.289510	0.332803
40	0.029088	0.072712	0.116313	0.159879	0.203397	0.246852	0.290232	0.333524
41	0.029815	0.073439	0.117040	0.160605	0.204122	0.247576	0.290955	0.334245
42	0.030543	0.074166	0.117766	0.161331	0.204846	0.248299	0.291677	0.334965
43	0.031270	0.074893	0.118493	0.162056	0.205571	0.249023	0.292399	0.335686
44	0.031997	0.075619	0.119219	0.162782	0.206296	0.249747	0.293121	0.336407
45	0.032724	0.076346	0.119945	0.163508	0.207021	0.250470	0.293844	0.337127
46	0.033451	0.077073	0.120672	0.164233	0.207745	0.251194	0.294566	0.337848
47	0.034178	0.077800	0.121398	0.164959	0.208470	0.251917	0.295288	0.338568
48	0.034905	0.078527	0.122124	0.165685	0.209195	0.252641	0.296010	0.339289
49	0.035633	0.079254	0.122851	0.166410	0.209919	0.253364	0.296732	0.340009
50	0.036360	0.079981	0.123577	0.167136	0.210644	0.254088	0.297454	0.340730
51	0.037087	0.080707	0.124303	0.167862	0.211369	0.254811	0.298176	0.341450
52	0.037814	0.081434	0.125030	0.168587	0.212093	0.255535	0.298898	0.342171
53	0.038541	0.082161	0.125756	0.169313	0.212818	0.256258	0.299620	0.342891
54	0.039268	0.082888	0.126482	0.170038	0.213542	0.256981	0.300342	0.343611
55	0.039995	0.083615	0.127209	0.170764	0.214267	0.257705	0.301064	0.344332
56	0.040723	0.084342	0.127935	0.171489	0.214991	0.258428	0.301786	0.345052
57	0.041450	0.085068	0.128661	0.172215	0.215716	0.259151	0.302508	0.345772
58	0.042177	0.085795	0.129387	0.172940	0.216440	0.259875	0.303230	0.346492
59	0.042904	0.086522	0.130114	0.173666	0.217165	0.260598	0.303952	0.347213
60	0.043631	0.087249	0.130840	0.174391	0.217889	0.261321	0.304673	0.347933

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	0.347933	0.391086	0.434120	0.477022	0.519779	0.562378	0.604805	0.647048
1	0.348653	0.391804	0.434837	0.477736	0.520491	0.563086	0.605510	0.647750
2	0.349373	0.392523	0.435553	0.478450	0.521202	0.563795	0.606216	0.648452
3	0.350093	0.393241	0.436269	0.479164	0.521913	0.564503	0.606921	0.649155
4	0.350813	0.393959	0.436985	0.479878	0.522624	0.565212	0.607627	0.649857
5	0.351533	0.394677	0.437701	0.480591	0.523335	0.565920	0.608332	0.650559
6	0.352253	0.395395	0.438417	0.481305	0.524046	0.566628	0.609038	0.651261
7	0.352973	0.396113	0.439133	0.482019	0.524757	0.567337	0.609743	0.651963
8	0.353693	0.396831	0.439849	0.482732	0.525468	0.568045	0.610448	0.652665
9	0.354413	0.397549	0.440564	0.483446	0.526179	0.568753	0.611153	0.653367
10	0.355133	0.398267	0.441280	0.484159	0.526890	0.569461	0.611858	0.654069
11	0.355853	0.398985	0.441996	0.484872	0.527601	0.570169	0.612563	0.654771
12	0.356572	0.399703	0.442712	0.485586	0.528312	0.570877	0.613268	0.655473
13	0.357292	0.400421	0.443428	0.486299	0.529023	0.571585	0.613973	0.656175
14	0.358012	0.401139	0.444143	0.487013	0.529734	0.572293	0.614678	0.656876
15	0.358732	0.401856	0.444859	0.487726	0.530444	0.573001	0.615383	0.657578
16	0.359451	0.402574	0.445574	0.488439	0.531155	0.573709	0.616088	0.658280
17	0.360171	0.403292	0.446290	0.489152	0.531865	0.574417	0.616793	0.658981
18	0.360891	0.404010	0.447006	0.489865	0.532576	0.575124	0.617498	0.659683
19	0.361610	0.404727	0.447721	0.490578	0.533287	0.575832	0.618202	0.660384
20	0.362330	0.405445	0.448436	0.491292	0.533997	0.576540	0.618907	0.661085
21	0.363049	0.406162	0.449152	0.492005	0.534707	0.577247	0.619611	0.661787
22	0.363769	0.406880	0.449867	0.492718	0.535418	0.577955	0.620316	0.662488
23	0.364488	0.407597	0.450583	0.493430	0.536128	0.578662	0.621020	0.663189
24	0.365208	0.408315	0.451298	0.494143	0.536838	0.579370	0.621725	0.663890
25	0.365927	0.409032	0.452013	0.494856	0.537549	0.580077	0.622429	0.664591
26	0.366646	0.409750	0.452728	0.495569	0.538259	0.580784	0.623133	0.665292
27	0.367366	0.410467	0.453444	0.496282	0.538969	0.581492	0.623838	0.665993
28	0.368085	0.411184	0.454159	0.496994	0.539679	0.582199	0.624542	0.666694
29	0.368804	0.411902	0.454874	0.497707	0.540389	0.582906	0.625246	0.667395
30	0.369524	0.412619	0.455589	0.498420	0.541099	0.583613	0.625950	0.668096
31	0.370243	0.413336	0.456304	0.499132	0.541809	0.584321	0.626654	0.668797
32	0.370962	0.414053	0.457019	0.499845	0.542519	0.585028	0.627358	0.669497
33	0.371681	0.414771	0.457734	0.500558	0.543229	0.585735	0.628062	0.670198
34	0.372400	0.415488	0.458449	0.501270	0.543939	0.586442	0.628766	0.670899
35	0.373119	0.416205	0.459164	0.501982	0.544648	0.587148	0.629470	0.671599
36	0.373838	0.416922	0.459878	0.502695	0.545358	0.587855	0.630173	0.672300
37	0.374557	0.417639	0.460593	0.503407	0.546068	0.588562	0.630877	0.673000
38	0.375276	0.418356	0.461308	0.504119	0.546777	0.589269	0.631581	0.673700
39	0.375995	0.419073	0.462023	0.504832	0.547487	0.589976	0.632284	0.674401
40	0.376714	0.419790	0.462737	0.505544	0.548197	0.590682	0.632988	0.675101
41	0.377433	0.420507	0.463452	0.506256	0.548906	0.591389	0.633691	0.675801
42	0.378152	0.421223	0.464167	0.506968	0.549616	0.592095	0.634395	0.676501
43	0.378871	0.421940	0.464881	0.507680	0.550325	0.592802	0.635098	0.677201
44	0.379590	0.422657	0.465596	0.508392	0.551034	0.593508	0.635802	0.677901
45	0.380308	0.423374	0.466310	0.509104	0.551744	0.594215	0.636505	0.678601
46	0.381027	0.424090	0.467025	0.509816	0.552453	0.594921	0.637208	0.679301
47	0.381746	0.424807	0.467739	0.510528	0.553162	0.595627	0.637911	0.680001
48	0.382465	0.425524	0.468453	0.511240	0.553871	0.596334	0.638614	0.680701
49	0.383183	0.426240	0.469168	0.511952	0.554580	0.597040	0.639317	0.681400
50	0.383902	0.426957	0.469882	0.512664	0.555289	0.597746	0.640020	0.682100
51	0.384620	0.427673	0.470596	0.513376	0.555999	0.598452	0.640723	0.682800
52	0.385339	0.428390	0.471310	0.514087	0.556708	0.599158	0.641426	0.683499
53	0.386057	0.429106	0.472025	0.514799	0.557416	0.599864	0.642129	0.684199
54	0.386776	0.429823	0.472739	0.515510	0.558125	0.600570	0.642832	0.684898
55	0.387494	0.430539	0.473453	0.516222	0.558834	0.601276	0.643535	0.685597
56	0.388213	0.431255	0.474167	0.516934	0.559543	0.601982	0.644237	0.686297
57	0.388931	0.431972	0.474881	0.517645	0.560252	0.602688	0.644940	0.686996
58	0.389650	0.432688	0.475595	0.518357	0.560960	0.603393	0.645643	0.687695
59	0.390368	0.433404	0.476309	0.519068	0.561669	0.604099	0.646345	0.688394
60	0.391086	0.434120	0.477022	0.519779	0.562378	0.604805	0.647048	0.689093

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	0.689093	0.730929	0.772543	0.813920	0.855050	0.895920	0.936517	0.976828
1	0.689792	0.731625	0.773234	0.814608	0.855734	0.896599	0.937191	0.977497
2	0.690491	0.732320	0.773926	0.815295	0.856417	0.897278	0.937865	0.978166
3	0.691190	0.733015	0.774617	0.815983	0.857100	0.897956	0.938539	0.978836
4	0.691889	0.733711	0.775309	0.816670	0.857783	0.898635	0.939213	0.979505
5	0.692588	0.734406	0.776000	0.817358	0.858466	0.899314	0.939887	0.980174
6	0.693287	0.735101	0.776691	0.818045	0.859149	0.899992	0.940561	0.980843
7	0.693985	0.735796	0.777382	0.818732	0.859832	0.900670	0.941234	0.981512
8	0.694684	0.736491	0.778073	0.819419	0.860515	0.901349	0.941908	0.982180
9	0.695382	0.737186	0.778764	0.820106	0.861198	0.902027	0.942582	0.982849
10	0.696081	0.737881	0.779455	0.820793	0.861880	0.902705	0.943255	0.983518
11	0.696779	0.738575	0.780146	0.821480	0.862563	0.903383	0.943929	0.984186
12	0.697478	0.739270	0.780837	0.822167	0.863246	0.904061	0.944602	0.984855
13	0.698176	0.739965	0.781528	0.822853	0.863928	0.904739	0.945275	0.985523
14	0.698874	0.740659	0.782219	0.823540	0.864610	0.905417	0.945948	0.986191
15	0.699573	0.741354	0.782910	0.824227	0.865293	0.906095	0.946622	0.986860
16	0.700271	0.742048	0.783600	0.824913	0.865975	0.906773	0.947295	0.987528
17	0.700969	0.742743	0.784291	0.825600	0.866657	0.907450	0.947968	0.988196
18	0.701667	0.743437	0.784981	0.826286	0.867339	0.908128	0.948640	0.988864
19	0.702365	0.744132	0.785672	0.826972	0.868021	0.908806	0.949313	0.989532
20	0.703063	0.744826	0.786362	0.827659	0.868703	0.909483	0.949986	0.990199
21	0.703761	0.745520	0.787052	0.828345	0.869385	0.910160	0.950659	0.990867
22	0.704458	0.746214	0.787742	0.829031	0.870067	0.910838	0.951331	0.991535
23	0.705156	0.746908	0.788433	0.829717	0.870748	0.911515	0.952004	0.992202
24	0.705854	0.747602	0.789123	0.830403	0.871430	0.912192	0.952676	0.992870
25	0.706551	0.748296	0.789813	0.831089	0.872112	0.912869	0.953348	0.993537
26	0.707249	0.748990	0.790503	0.831775	0.872793	0.913546	0.954020	0.994204
27	0.707946	0.749684	0.791192	0.832460	0.873475	0.914223	0.954693	0.994872
28	0.708644	0.750377	0.791882	0.833146	0.874156	0.914900	0.955365	0.995539
29	0.709341	0.751071	0.792572	0.833832	0.874837	0.915576	0.956037	0.996206
30	0.710038	0.751765	0.793262	0.834517	0.875519	0.916253	0.956709	0.996873
31	0.710736	0.752458	0.793951	0.835203	0.876200	0.916930	0.957380	0.997540
32	0.711433	0.753151	0.794641	0.835888	0.876881	0.917606	0.958052	0.998206
33	0.712130	0.753845	0.795330	0.836573	0.877562	0.918283	0.958724	0.998873
34	0.712827	0.754538	0.796020	0.837259	0.878243	0.918959	0.959395	0.999540
35	0.713524	0.755232	0.796709	0.837944	0.878923	0.919635	0.960067	1.000206
36	0.714221	0.755925	0.797398	0.838629	0.879604	0.920311	0.960738	1.000873
37	0.714918	0.756618	0.798087	0.839314	0.880285	0.920988	0.961410	1.001539
38	0.715615	0.757311	0.798777	0.839999	0.880965	0.921664	0.962081	1.002205
39	0.716311	0.758004	0.799466	0.840684	0.881646	0.922339	0.962752	1.002871
40	0.717008	0.758697	0.800155	0.841369	0.882326	0.923015	0.963423	1.003538
41	0.717705	0.759390	0.800844	0.842053	0.883007	0.923691	0.964094	1.004204
42	0.718401	0.760083	0.801533	0.842738	0.883687	0.924367	0.964765	1.004869
43	0.719098	0.760775	0.802221	0.843423	0.884367	0.925043	0.965436	1.005535
44	0.719794	0.761468	0.802910	0.844107	0.885048	0.925718	0.966107	1.006201
45	0.720491	0.762161	0.803599	0.844792	0.885728	0.926394	0.966777	1.006867
46	0.721187	0.762853	0.804287	0.845476	0.886408	0.927069	0.967448	1.007532
47	0.721883	0.763546	0.804976	0.846161	0.887088	0.927744	0.968119	1.008198
48	0.722579	0.764238	0.805664	0.846845	0.887767	0.928420	0.968789	1.008863
49	0.723276	0.764931	0.806353	0.847529	0.888447	0.929095	0.969459	1.009529
50	0.723972	0.765623	0.807041	0.848213	0.889127	0.929770	0.970130	1.010194
51	0.724668	0.766315	0.807729	0.848897	0.889807	0.930445	0.970800	1.010859
52	0.725364	0.767007	0.808417	0.849581	0.890486	0.931120	0.971470	1.011524
53	0.726060	0.767699	0.809106	0.850265	0.891166	0.931795	0.972140	1.012189
54	0.726755	0.768392	0.809794	0.850949	0.891845	0.932469	0.972810	1.012854
55	0.727451	0.769083	0.810482	0.851633	0.892524	0.933144	0.973480	1.013519
56	0.728147	0.769775	0.811169	0.852316	0.893204	0.933819	0.974150	1.014184
57	0.728843	0.770467	0.811857	0.853000	0.893883	0.934493	0.974819	1.014848
58	0.729538	0.771159	0.812545	0.853684	0.894562	0.935168	0.975489	1.015513
59	0.730234	0.771851	0.813233	0.854367	0.895241	0.935842	0.976158	1.016177
60	0.730929	0.772543	0.813920	0.855050	0.895920	0.936517	0.976828	1.016842

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	1.016842	1.056546	1.095928	1.134976	1.173679	1.212024	1.250000	1.287595
1	1.017506	1.057205	1.096581	1.135624	1.174321	1.212660	1.250630	1.288218
2	1.018170	1.057864	1.097235	1.136272	1.174963	1.213296	1.251259	1.288842
3	1.018834	1.058522	1.097888	1.136920	1.175605	1.213932	1.251889	1.289465
4	1.019498	1.059181	1.098542	1.137567	1.176247	1.214567	1.252518	1.290088
5	1.020162	1.059840	1.099195	1.138215	1.176888	1.215203	1.253148	1.290711
6	1.020826	1.060499	1.099848	1.138862	1.177530	1.215839	1.253777	1.291333
7	1.021490	1.061157	1.100501	1.139510	1.178171	1.216474	1.254406	1.291956
8	1.022154	1.061816	1.101154	1.140157	1.178813	1.217109	1.255035	1.292579
9	1.022817	1.062474	1.101807	1.140804	1.179454	1.217744	1.255664	1.293201
10	1.023481	1.063132	1.102459	1.141451	1.180095	1.218379	1.256293	1.293823
11	1.024144	1.063790	1.103112	1.142098	1.180736	1.219014	1.256921	1.294445
12	1.024808	1.064448	1.103765	1.142745	1.181377	1.219649	1.257550	1.295068
13	1.025471	1.065106	1.104417	1.143392	1.182018	1.220284	1.258178	1.295690
14	1.026134	1.065764	1.105070	1.144038	1.182659	1.220919	1.258807	1.296311
15	1.026797	1.066422	1.105722	1.144685	1.183299	1.221553	1.259435	1.296933
16	1.027460	1.067080	1.106374	1.145331	1.183940	1.222188	1.260063	1.297555
17	1.028123	1.067737	1.107026	1.145978	1.184580	1.222822	1.260691	1.298176
18	1.028786	1.068395	1.107678	1.146624	1.185220	1.223456	1.261319	1.298798
19	1.029449	1.069052	1.108330	1.147270	1.185861	1.224090	1.261947	1.299419
20	1.030111	1.069709	1.108982	1.147916	1.186501	1.224724	1.262575	1.300040
21	1.030774	1.070367	1.109633	1.148562	1.187141	1.225358	1.263202	1.300661
22	1.031436	1.071024	1.110285	1.149208	1.187781	1.225992	1.263830	1.301282
23	1.032099	1.071681	1.110937	1.149854	1.188421	1.226626	1.264457	1.301903
24	1.032761	1.072338	1.111588	1.150499	1.189061	1.227259	1.265084	1.302524
25	1.033423	1.072995	1.112239	1.151145	1.189700	1.227893	1.265712	1.303145
26	1.034085	1.073652	1.112890	1.151790	1.190340	1.228526	1.266339	1.303765
27	1.034748	1.074308	1.113542	1.152436	1.190979	1.229160	1.266966	1.304386
28	1.035409	1.074965	1.114193	1.153081	1.191619	1.229793	1.267593	1.305006
29	1.036071	1.075621	1.114844	1.153726	1.192258	1.230426	1.268219	1.305626
30	1.036733	1.076278	1.115495	1.154372	1.192897	1.231059	1.268846	1.306246
31	1.037395	1.076934	1.116145	1.155017	1.193536	1.231692	1.269472	1.306866
32	1.038056	1.077590	1.116796	1.155661	1.194175	1.232325	1.270099	1.307486
33	1.038718	1.078246	1.117447	1.156306	1.194814	1.232957	1.270725	1.308106
34	1.039379	1.078903	1.118097	1.156951	1.195453	1.233590	1.271351	1.308726
35	1.040041	1.079558	1.118747	1.157596	1.196091	1.234222	1.271978	1.309345
36	1.040702	1.080214	1.119398	1.158240	1.196730	1.234855	1.272604	1.309965
37	1.041363	1.080870	1.120048	1.158885	1.197368	1.235487	1.273229	1.310584
38	1.042024	1.081526	1.120698	1.159529	1.198006	1.236119	1.273855	1.311203
39	1.042685	1.082181	1.121348	1.160173	1.198645	1.236751	1.274481	1.311822
40	1.043346	1.082837	1.121998	1.160817	1.199283	1.237383	1.275106	1.312441
41	1.044007	1.083492	1.122648	1.161461	1.199921	1.238015	1.275732	1.313060
42	1.044668	1.084148	1.123298	1.162105	1.200559	1.238647	1.276357	1.313679
43	1.045328	1.084803	1.123947	1.162749	1.201197	1.239278	1.276983	1.314298
44	1.045989	1.085458	1.124597	1.163393	1.201834	1.239910	1.277608	1.314916
45	1.046649	1.086113	1.125246	1.164036	1.202472	1.240541	1.278233	1.315535
46	1.047310	1.086768	1.125896	1.164680	1.203110	1.241173	1.278858	1.316153
47	1.047970	1.087423	1.126545	1.165323	1.203747	1.241804	1.279482	1.316771
48	1.048630	1.088078	1.127194	1.165967	1.204384	1.242435	1.280107	1.317389
49	1.049290	1.088732	1.127843	1.166610	1.205022	1.243066	1.280732	1.318008
50	1.049950	1.089387	1.128492	1.167253	1.205659	1.243697	1.281356	1.318625
51	1.050610	1.090042	1.129141	1.167896	1.206296	1.244328	1.281981	1.319243
52	1.051270	1.090696	1.129790	1.168539	1.206932	1.244958	1.282605	1.319861
53	1.051930	1.091350	1.130438	1.169182	1.207569	1.245589	1.283229	1.320478
54	1.052590	1.092005	1.131087	1.169825	1.208206	1.246219	1.283853	1.321096
55	1.053249	1.092659	1.131735	1.170467	1.208843	1.246850	1.284477	1.321713
56	1.053909	1.093313	1.132384	1.171110	1.209479	1.247480	1.285101	1.322330
57	1.054568	1.093967	1.133032	1.171752	1.210116	1.248110	1.285725	1.322948
58	1.055227	1.094620	1.133680	1.172395	1.210752	1.248740	1.286348	1.323565
59	1.055887	1.095274	1.134328	1.173037	1.211388	1.249370	1.286972	1.324181
60	1.056546	1.095928	1.134976	1.173679	1.212024	1.250000	1.287595	1.324798

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	1.324798	1.361598	1.397982	1.433941	1.469463	1.504538	1.539154	1.573301
1	1.325415	1.362207	1.398585	1.434537	1.470051	1.505118	1.539727	1.573866
2	1.326031	1.362817	1.399188	1.435132	1.470640	1.505699	1.540300	1.574431
3	1.326648	1.363427	1.399790	1.435728	1.471228	1.506279	1.540872	1.574996
4	1.327264	1.364036	1.400393	1.436323	1.471815	1.506860	1.541445	1.575561
5	1.327880	1.364646	1.400995	1.436918	1.472403	1.507440	1.542017	1.576125
6	1.328496	1.365255	1.401597	1.437513	1.472991	1.508020	1.542590	1.576689
7	1.329112	1.365864	1.402200	1.438108	1.473578	1.508600	1.543162	1.577254
8	1.329728	1.366473	1.402802	1.438703	1.474166	1.509180	1.543734	1.577818
9	1.330344	1.367082	1.403404	1.439298	1.474753	1.509760	1.544306	1.578382
10	1.330960	1.367691	1.404005	1.439892	1.475340	1.510339	1.544878	1.578946
11	1.331575	1.368300	1.404607	1.440487	1.475927	1.510918	1.545449	1.579510
12	1.332191	1.368908	1.405208	1.441081	1.476514	1.511498	1.546021	1.580073
13	1.332806	1.369517	1.405810	1.441675	1.477101	1.512077	1.546592	1.580637
14	1.333421	1.370125	1.406411	1.442269	1.477688	1.512656	1.547164	1.581200
15	1.334036	1.370733	1.407012	1.442863	1.478274	1.513235	1.547735	1.581763
16	1.334651	1.371341	1.407613	1.443457	1.478860	1.513814	1.548306	1.582326
17	1.335266	1.371949	1.408214	1.444051	1.479447	1.514392	1.548877	1.582889
18	1.335881	1.372557	1.408815	1.444644	1.480033	1.514971	1.549448	1.583452
19	1.336496	1.373165	1.409416	1.445238	1.480619	1.515549	1.550018	1.584015
20	1.337110	1.373772	1.410016	1.445831	1.481205	1.516128	1.550589	1.584577
21	1.337724	1.374380	1.410617	1.446424	1.481791	1.516706	1.551159	1.585140
22	1.338339	1.374987	1.411217	1.447017	1.482376	1.517284	1.551729	1.585702
23	1.338953	1.375595	1.411818	1.447610	1.482962	1.517862	1.552300	1.586264
24	1.339567	1.376202	1.412418	1.448203	1.483547	1.518440	1.552870	1.586826
25	1.340181	1.376809	1.413018	1.448796	1.484133	1.519017	1.553439	1.587388
26	1.340795	1.377416	1.413617	1.449388	1.484718	1.519595	1.554009	1.587950
27	1.341409	1.378023	1.414217	1.449981	1.485303	1.520172	1.554579	1.588512
28	1.342022	1.378629	1.414817	1.450573	1.485888	1.520749	1.555148	1.589073
29	1.342636	1.379236	1.415416	1.451165	1.486472	1.521327	1.555717	1.589634
30	1.343249	1.379843	1.416016	1.451757	1.487057	1.521904	1.556287	1.590196
31	1.343862	1.380449	1.416615	1.452349	1.487641	1.522480	1.556856	1.590757
32	1.344476	1.381055	1.417214	1.452941	1.488226	1.523057	1.557425	1.591318
33	1.345088	1.381661	1.417813	1.453533	1.488810	1.523634	1.557993	1.591878
34	1.345701	1.382267	1.418412	1.454125	1.489394	1.524210	1.558562	1.592439
35	1.346314	1.382873	1.419011	1.454716	1.489978	1.524787	1.559131	1.593000
36	1.346927	1.383479	1.419609	1.455307	1.490562	1.525363	1.559699	1.593560
37	1.347540	1.384084	1.420208	1.455899	1.491146	1.525939	1.560267	1.594120
38	1.348152	1.384690	1.420806	1.456490	1.491730	1.526515	1.560835	1.594680
39	1.348765	1.385296	1.421405	1.457081	1.492313	1.527091	1.561404	1.595240
40	1.349377	1.385901	1.422003	1.457672	1.492897	1.527667	1.561971	1.595800
41	1.349989	1.386506	1.422601	1.458262	1.493480	1.528242	1.562539	1.596360
42	1.350601	1.387111	1.423199	1.458853	1.494063	1.528818	1.563107	1.596920
43	1.351213	1.387716	1.423797	1.459444	1.494646	1.529393	1.563674	1.597479
44	1.351825	1.388321	1.424394	1.460034	1.495229	1.529968	1.564242	1.598038
45	1.352436	1.388926	1.424992	1.460624	1.495812	1.530543	1.564809	1.598598
46	1.353048	1.389530	1.425589	1.461214	1.496394	1.531118	1.565376	1.599157
47	1.353659	1.390135	1.426187	1.461804	1.496977	1.531693	1.565943	1.599715
48	1.354271	1.390739	1.426784	1.462394	1.497559	1.532268	1.566509	1.600274
49	1.354882	1.391343	1.427381	1.462984	1.498141	1.532842	1.567076	1.600833
50	1.355493	1.391947	1.427978	1.463574	1.498723	1.533417	1.567643	1.601391
51	1.356104	1.392551	1.428575	1.464163	1.499305	1.533991	1.568209	1.601950
52	1.356715	1.393155	1.429172	1.464752	1.499887	1.534565	1.568775	1.602508
53	1.357326	1.393759	1.429768	1.465342	1.500469	1.535139	1.569342	1.603066
54	1.357936	1.394363	1.430365	1.465931	1.501051	1.535713	1.569908	1.603624
55	1.358547	1.394966	1.430961	1.466520	1.501632	1.536287	1.570474	1.604182
56	1.359157	1.395570	1.431557	1.467109	1.502213	1.536860	1.571039	1.604740
57	1.359767	1.396173	1.432153	1.467698	1.502795	1.537434	1.571605	1.605297
58	1.360378	1.396776	1.432750	1.468286	1.503376	1.538007	1.572170	1.605855
59	1.360988	1.397379	1.433345	1.468875	1.503957	1.538581	1.572736	1.606412
60	1.361598	1.397982	1.433941	1.469463	1.504538	1.539154	1.573301	1.606969

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	1.606969	1.640148	1.672827	1.704996	1.736646	1.767767	1.798349	1.828384
1	1.607526	1.640696	1.673367	1.705528	1.737169	1.768281	1.798855	1.828880
2	1.608083	1.641245	1.673907	1.706059	1.737692	1.768795	1.799360	1.829376
3	1.608640	1.641793	1.674447	1.706591	1.738215	1.769309	1.799864	1.829871
4	1.609196	1.642342	1.674987	1.707122	1.738737	1.769823	1.800369	1.830367
5	1.609753	1.642890	1.675527	1.707653	1.739260	1.770336	1.800873	1.830862
6	1.610309	1.643438	1.676067	1.708184	1.739782	1.770850	1.801378	1.831357
7	1.610865	1.643986	1.676606	1.708715	1.740304	1.771363	1.801882	1.831852
8	1.611421	1.644534	1.677145	1.709246	1.740826	1.771876	1.802386	1.832347
9	1.611977	1.645082	1.677685	1.709777	1.741348	1.772389	1.802890	1.832842
10	1.612533	1.645629	1.678224	1.710307	1.741870	1.772902	1.803394	1.833336
11	1.613089	1.646176	1.678763	1.710838	1.742391	1.773414	1.803897	1.833831
12	1.613644	1.646724	1.679302	1.711368	1.742913	1.773927	1.804401	1.834325
13	1.614200	1.647271	1.679840	1.711898	1.743434	1.774439	1.804904	1.834819
14	1.614755	1.647818	1.680379	1.712428	1.743955	1.774951	1.805407	1.835313
15	1.615310	1.648365	1.680917	1.712958	1.744476	1.775463	1.805910	1.835806
16	1.615865	1.648911	1.681455	1.713487	1.744997	1.775975	1.806413	1.836300
17	1.616420	1.649458	1.681993	1.714017	1.745518	1.776487	1.806915	1.836793
18	1.616974	1.650004	1.682531	1.714546	1.746038	1.776999	1.807418	1.837286
19	1.617529	1.650550	1.683069	1.715075	1.746559	1.777510	1.807920	1.837780
20	1.618083	1.651097	1.683607	1.715604	1.747079	1.778021	1.808422	1.838273
21	1.618638	1.651643	1.684144	1.716133	1.747599	1.778533	1.808924	1.838765
22	1.619192	1.652188	1.684682	1.716662	1.748119	1.779044	1.809426	1.839258
23	1.619746	1.652734	1.685219	1.717190	1.748639	1.779554	1.809928	1.839751
24	1.620300	1.653280	1.685756	1.717719	1.749158	1.780065	1.810430	1.840243
25	1.620854	1.653825	1.686293	1.718247	1.749678	1.780576	1.810931	1.840735
26	1.621407	1.654370	1.686830	1.718775	1.750197	1.781086	1.811432	1.841227
27	1.621961	1.654916	1.687366	1.719303	1.750716	1.781596	1.811934	1.841719
28	1.622514	1.655461	1.687903	1.719831	1.751235	1.782106	1.812435	1.842211
29	1.623067	1.656005	1.688439	1.720359	1.751754	1.782616	1.812935	1.842702
30	1.623620	1.656550	1.688976	1.720886	1.752273	1.783126	1.813436	1.843193
31	1.624173	1.657095	1.689512	1.721414	1.752792	1.783636	1.813936	1.843685
32	1.624726	1.657639	1.690048	1.721941	1.753310	1.784145	1.814437	1.844176
33	1.625278	1.658183	1.690583	1.722468	1.753829	1.784655	1.814937	1.844667
34	1.625831	1.658728	1.691119	1.722995	1.754347	1.785164	1.815437	1.845157
35	1.626383	1.659272	1.691655	1.723522	1.754865	1.785673	1.815937	1.845648
36	1.626935	1.659816	1.692190	1.724049	1.755383	1.786182	1.816437	1.846138
37	1.627488	1.660359	1.692725	1.724575	1.755900	1.786690	1.816936	1.846629
38	1.628040	1.660903	1.693260	1.725102	1.756418	1.787199	1.817436	1.847119
39	1.628592	1.661446	1.693795	1.725628	1.756935	1.787708	1.817935	1.847609
40	1.629143	1.661990	1.694330	1.726154	1.757453	1.788216	1.818434	1.848099
41	1.629695	1.662533	1.694865	1.726680	1.757970	1.788724	1.818933	1.848588
42	1.630246	1.663076	1.695399	1.727206	1.758487	1.789232	1.819432	1.849078
43	1.630797	1.663619	1.695934	1.727732	1.759004	1.789740	1.819931	1.849567
44	1.631348	1.664162	1.696468	1.728257	1.759520	1.790247	1.820429	1.850056
45	1.631899	1.664704	1.697002	1.728783	1.760037	1.790755	1.820928	1.850545
46	1.632450	1.665247	1.697536	1.729308	1.760553	1.791262	1.821426	1.851034
47	1.633001	1.665789	1.698070	1.729833	1.761069	1.791770	1.821924	1.851523
48	1.633551	1.666331	1.698603	1.730358	1.761586	1.792277	1.822422	1.852012
49	1.634102	1.666873	1.699137	1.730883	1.762102	1.792783	1.822919	1.852500
50	1.634652	1.667415	1.699670	1.731407	1.762617	1.793290	1.823417	1.852988
51	1.635202	1.667957	1.700203	1.731932	1.763133	1.793797	1.823914	1.853476
52	1.635752	1.668499	1.700736	1.732456	1.763648	1.794303	1.824412	1.853964
53	1.636302	1.669040	1.701270	1.732981	1.764164	1.794810	1.824909	1.854452
54	1.636852	1.669582	1.701802	1.733505	1.764679	1.795316	1.825406	1.854940
55	1.637402	1.670123	1.702335	1.734029	1.765194	1.795822	1.825903	1.855427
56	1.637951	1.670664	1.702867	1.734552	1.765709	1.796328	1.826399	1.855914
57	1.638500	1.671205	1.703400	1.735076	1.766224	1.796833	1.826896	1.856402
58	1.639050	1.671745	1.703932	1.735599	1.766738	1.797339	1.827392	1.856889
59	1.639599	1.672286	1.704464	1.736123	1.767253	1.797844	1.827888	1.857375
60	1.640148	1.672827	1.704996	1.736646	1.767767	1.798349	1.828384	1.857862

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 2.5-inch Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	1.857862	1.886774	1.915111	1.942865	1.970027	1.996589	2.022542	2.047880
1	1.858349	1.887251	1.915578	1.943323	1.970475	1.997026	2.022970	2.048297
2	1.858835	1.887728	1.916046	1.943780	1.970922	1.997464	2.023397	2.048714
3	1.859321	1.888205	1.916513	1.944237	1.971369	1.997901	2.023824	2.049131
4	1.859807	1.888681	1.916980	1.944694	1.971816	1.998338	2.024251	2.049547
5	1.860293	1.889157	1.917446	1.945151	1.972263	1.998775	2.024678	2.049963
6	1.860779	1.889634	1.917913	1.945608	1.972710	1.999212	2.025104	2.050380
7	1.861264	1.890110	1.918379	1.946064	1.973157	1.999648	2.025530	2.050796
8	1.861750	1.890586	1.918846	1.946521	1.973603	2.000085	2.025957	2.051212
9	1.862235	1.891061	1.919312	1.946977	1.974050	2.000521	2.026383	2.051627
10	1.862720	1.891537	1.919778	1.947433	1.974496	2.000957	2.026809	2.052043
11	1.863205	1.892012	1.920243	1.947889	1.974942	2.001393	2.027234	2.052458
12	1.863690	1.892488	1.920709	1.948345	1.975388	2.001828	2.027660	2.052873
13	1.864175	1.892963	1.921174	1.948801	1.975833	2.002264	2.028085	2.053288
14	1.864659	1.893438	1.921640	1.949256	1.976279	2.002699	2.028510	2.053703
15	1.865143	1.893913	1.922105	1.949711	1.976724	2.003134	2.028935	2.054117
16	1.865628	1.894387	1.922570	1.950166	1.977169	2.003570	2.029360	2.054532
17	1.866112	1.894862	1.923034	1.950621	1.977614	2.004004	2.029784	2.054946
18	1.866596	1.895336	1.923499	1.951076	1.978059	2.004439	2.030209	2.055360
19	1.867079	1.895810	1.923963	1.951531	1.978503	2.004874	2.030633	2.055774
20	1.867563	1.896284	1.924428	1.951985	1.978948	2.005308	2.031057	2.056188
21	1.868046	1.896758	1.924892	1.952439	1.979392	2.005742	2.031481	2.056601
22	1.868529	1.897231	1.925356	1.952893	1.979836	2.006176	2.031905	2.057015
23	1.869012	1.897705	1.925820	1.953347	1.980280	2.006610	2.032329	2.057428
24	1.869495	1.898178	1.926283	1.953801	1.980724	2.007044	2.032752	2.057841
25	1.869978	1.898651	1.926747	1.954255	1.981168	2.007477	2.033175	2.058254
26	1.870461	1.899125	1.927210	1.954708	1.981611	2.007910	2.033598	2.058666
27	1.870943	1.899597	1.927673	1.955162	1.982055	2.008344	2.034021	2.059079
28	1.871425	1.900070	1.928136	1.955615	1.982498	2.008777	2.034444	2.059491
29	1.871907	1.900543	1.928599	1.956068	1.982941	2.009210	2.034867	2.059904
30	1.872389	1.901015	1.929062	1.956520	1.983383	2.009642	2.035289	2.060316
31	1.872871	1.901487	1.929524	1.956973	1.983826	2.010075	2.035711	2.060727
32	1.873353	1.901959	1.929986	1.957425	1.984268	2.010507	2.036133	2.061139
33	1.873834	1.902431	1.930448	1.957878	1.984711	2.010939	2.036555	2.061550
34	1.874316	1.902903	1.930910	1.958330	1.985153	2.011371	2.036977	2.061962
35	1.874797	1.903374	1.931372	1.958782	1.985595	2.011803	2.037398	2.062373
36	1.875278	1.903846	1.931834	1.959234	1.986037	2.012234	2.037819	2.062784
37	1.875759	1.904317	1.932295	1.959685	1.986478	2.012666	2.038241	2.063195
38	1.876239	1.904788	1.932757	1.960137	1.986920	2.013097	2.038662	2.063605
39	1.876720	1.905259	1.933218	1.960588	1.987361	2.013528	2.039083	2.064016
40	1.877200	1.905730	1.933679	1.961039	1.987802	2.013959	2.039503	2.064426
41	1.877680	1.906200	1.934140	1.961490	1.988243	2.014390	2.039924	2.064836
42	1.878160	1.906671	1.934601	1.961941	1.988684	2.014821	2.040344	2.065246
43	1.878640	1.907141	1.935061	1.962392	1.989124	2.015251	2.040764	2.065655
44	1.879120	1.907611	1.935521	1.962842	1.989565	2.015682	2.041184	2.066065
45	1.879600	1.908081	1.935982	1.963292	1.990005	2.016112	2.041604	2.066474
46	1.880079	1.908551	1.936442	1.963742	1.990445	2.016541	2.042024	2.066884
47	1.880558	1.909021	1.936902	1.964193	1.990885	2.016971	2.042443	2.067293
48	1.881037	1.909490	1.937361	1.964642	1.991325	2.017401	2.042862	2.067701
49	1.881516	1.909959	1.937821	1.965092	1.991764	2.017830	2.043281	2.068110
50	1.881995	1.910429	1.938280	1.965541	1.992204	2.018260	2.043700	2.068519
51	1.882474	1.910897	1.938739	1.965991	1.992643	2.018688	2.044119	2.068927
52	1.882952	1.911366	1.939198	1.966440	1.993082	2.019117	2.044538	2.069335
53	1.883430	1.911835	1.939657	1.966889	1.993521	2.019546	2.044956	2.069743
54	1.883909	1.912304	1.940116	1.967338	1.993960	2.019975	2.045374	2.070151
55	1.884387	1.912772	1.940575	1.967786	1.994398	2.020403	2.045792	2.070559
56	1.884864	1.913240	1.941033	1.968235	1.994837	2.020831	2.046210	2.070966
57	1.885342	1.913708	1.941491	1.968683	1.995275	2.021259	2.046628	2.071373
58	1.885819	1.914176	1.941949	1.969131	1.995713	2.021687	2.047045	2.071780
59	1.886297	1.914644	1.942407	1.969579	1.996151	2.022115	2.047463	2.072187
60	1.886774	1.915111	1.942865	1.970027	1.996589	2.022542	2.047880	2.072594

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 3-inch Sine-Bar

Constants for Setting a 3-inch Sine-Bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	0.052357	0.104698	0.157008	0.209269	0.261467	0.313585	0.365608
1	0.000873	0.053230	0.105571	0.157879	0.210140	0.262337	0.314453	0.366474
2	0.001745	0.054102	0.106443	0.158751	0.211010	0.263206	0.315321	0.367340
3	0.002618	0.054975	0.107315	0.159622	0.211881	0.264075	0.316189	0.368206
4	0.003491	0.055847	0.108187	0.160494	0.212751	0.264944	0.317057	0.369072
5	0.004363	0.056720	0.109059	0.161365	0.213622	0.265814	0.317924	0.369938
6	0.005236	0.057592	0.109931	0.162236	0.214492	0.266683	0.318792	0.370804
7	0.006109	0.058465	0.110803	0.163108	0.215363	0.267552	0.319660	0.371670
8	0.006981	0.059337	0.111675	0.163979	0.216233	0.268421	0.320528	0.372536
9	0.007854	0.060210	0.112547	0.164851	0.217104	0.269290	0.321395	0.373402
10	0.008727	0.061082	0.113419	0.165722	0.217974	0.270160	0.322263	0.374268
11	0.009599	0.061955	0.114291	0.166593	0.218844	0.271029	0.323131	0.375134
12	0.010472	0.062827	0.115163	0.167465	0.219715	0.271898	0.323998	0.376000
13	0.011345	0.063700	0.116035	0.168336	0.220585	0.272767	0.324866	0.376865
14	0.012217	0.064572	0.116907	0.169207	0.221455	0.273636	0.325733	0.377731
15	0.013090	0.065445	0.117779	0.170078	0.222325	0.274505	0.326601	0.378597
16	0.013963	0.066317	0.118651	0.170950	0.223196	0.275374	0.327468	0.379463
17	0.014835	0.067190	0.119523	0.171821	0.224066	0.276243	0.328336	0.380328
18	0.015708	0.068062	0.120395	0.172692	0.224936	0.277112	0.329203	0.381194
19	0.016581	0.068934	0.121267	0.173563	0.225806	0.277981	0.330070	0.382059
20	0.017453	0.069807	0.122139	0.174434	0.226677	0.278850	0.330938	0.382925
21	0.018326	0.070679	0.123011	0.175306	0.227547	0.279718	0.331805	0.383790
22	0.019198	0.071552	0.123883	0.176177	0.228417	0.280587	0.332672	0.384656
23	0.020071	0.072424	0.124755	0.177048	0.229287	0.281456	0.333540	0.385521
24	0.020944	0.073297	0.125627	0.177919	0.230157	0.282325	0.334407	0.386387
25	0.021816	0.074169	0.126499	0.178790	0.231027	0.283194	0.335274	0.387252
26	0.022689	0.075041	0.127371	0.179661	0.231897	0.284062	0.336141	0.388118
27	0.023562	0.075914	0.128243	0.180532	0.232767	0.284931	0.337008	0.388983
28	0.024434	0.076786	0.129114	0.181404	0.233637	0.285800	0.337875	0.389848
29	0.025307	0.077658	0.129986	0.182275	0.234507	0.286669	0.338743	0.390713
30	0.026180	0.078531	0.130858	0.183146	0.235377	0.287537	0.339610	0.391579
31	0.027052	0.079403	0.131730	0.184017	0.236247	0.288406	0.340477	0.392444
32	0.027925	0.080276	0.132602	0.184888	0.237117	0.289275	0.341344	0.393309
33	0.028797	0.081148	0.133474	0.185759	0.237987	0.290143	0.342211	0.394174
34	0.029670	0.082020	0.134345	0.186630	0.238857	0.291012	0.343078	0.395039
35	0.030543	0.082893	0.135217	0.187501	0.239727	0.291880	0.343945	0.395904
36	0.031415	0.083765	0.136089	0.188372	0.240597	0.292749	0.344811	0.396769
37	0.032288	0.084637	0.136961	0.189242	0.241467	0.293617	0.345678	0.397634
38	0.033161	0.085510	0.137832	0.190113	0.242336	0.294486	0.346545	0.398499
39	0.034033	0.086382	0.138704	0.190984	0.243206	0.295354	0.347412	0.399364
40	0.034906	0.087254	0.139576	0.191855	0.244076	0.296223	0.348279	0.400229
41	0.035778	0.088126	0.140448	0.192726	0.244946	0.297091	0.349146	0.401094
42	0.036651	0.088999	0.141319	0.193597	0.245816	0.297959	0.350012	0.401959
43	0.037524	0.089871	0.142191	0.194468	0.246685	0.298828	0.350879	0.402823
44	0.038396	0.090743	0.143063	0.195339	0.247555	0.299696	0.351746	0.403688
45	0.039269	0.091616	0.143934	0.196209	0.248425	0.300564	0.352612	0.404553
46	0.040141	0.092488	0.144806	0.197080	0.249294	0.301432	0.353479	0.405418
47	0.041014	0.093360	0.145678	0.197951	0.250164	0.302301	0.354345	0.406282
48	0.041887	0.094232	0.146549	0.198822	0.251034	0.303169	0.355212	0.407147
49	0.042759	0.095105	0.147421	0.199692	0.251903	0.304037	0.356078	0.408011
50	0.043632	0.095977	0.148293	0.200563	0.252773	0.304905	0.356945	0.408876
51	0.044504	0.096849	0.149164	0.201434	0.253642	0.305773	0.357811	0.409740
52	0.045377	0.097721	0.150036	0.202305	0.254512	0.306641	0.358678	0.410605
53	0.046249	0.098593	0.150907	0.203175	0.255381	0.307510	0.359544	0.411469
54	0.047122	0.099466	0.151779	0.204046	0.256251	0.308378	0.360411	0.412334
55	0.047995	0.100338	0.152650	0.204917	0.257120	0.309246	0.361277	0.413198
56	0.048867	0.101210	0.153522	0.205787	0.257990	0.310114	0.362143	0.414062
57	0.049740	0.102082	0.154393	0.206658	0.258859	0.310982	0.363009	0.414927
58	0.050612	0.102954	0.155265	0.207528	0.259728	0.311850	0.363876	0.415791
59	0.051485	0.103826	0.156136	0.208399	0.260598	0.312717	0.364742	0.416655
60	0.052357	0.104698	0.157008	0.209269	0.261467	0.313585	0.365608	0.417519

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	0.417519	0.469303	0.520945	0.572427	0.623735	0.674853	0.725766	0.776457
1	0.418383	0.470165	0.521804	0.573284	0.624589	0.675703	0.726612	0.777300
2	0.419248	0.471027	0.522663	0.574140	0.625442	0.676554	0.727459	0.778143
3	0.420112	0.471889	0.523523	0.574997	0.626296	0.677404	0.728306	0.778986
4	0.420976	0.472751	0.524382	0.575853	0.627149	0.678254	0.729152	0.779828
5	0.421840	0.473612	0.525241	0.576710	0.628002	0.679104	0.729999	0.780671
6	0.422704	0.474474	0.526100	0.577566	0.628856	0.679954	0.730845	0.781514
7	0.423568	0.475336	0.526959	0.578422	0.629709	0.680804	0.731691	0.782356
8	0.424432	0.476197	0.527818	0.579278	0.630562	0.681654	0.732538	0.783198
9	0.425295	0.477059	0.528677	0.580135	0.631415	0.682504	0.733384	0.784041
10	0.426159	0.477921	0.529536	0.580991	0.632268	0.683353	0.734230	0.784883
11	0.427023	0.478782	0.530395	0.581847	0.633121	0.684203	0.735076	0.785725
12	0.427887	0.479644	0.531254	0.582703	0.633974	0.685053	0.735922	0.786568
13	0.428751	0.480505	0.532113	0.583559	0.634827	0.685902	0.736768	0.787410
14	0.429614	0.481366	0.532972	0.584415	0.635680	0.686752	0.737614	0.788252
15	0.430478	0.482228	0.533831	0.585271	0.636533	0.687601	0.738460	0.789094
16	0.431341	0.483089	0.534689	0.586127	0.637386	0.688451	0.739306	0.789936
17	0.432205	0.483950	0.535548	0.586983	0.638239	0.689300	0.740151	0.790777
18	0.433069	0.484811	0.536407	0.587838	0.639091	0.690149	0.740997	0.791619
19	0.433932	0.485673	0.537265	0.588694	0.639944	0.690998	0.741843	0.792461
20	0.434796	0.486534	0.538124	0.589550	0.640796	0.691848	0.742688	0.793302
21	0.435659	0.487395	0.538982	0.590405	0.641649	0.692697	0.743534	0.794144
22	0.436522	0.488256	0.539841	0.591261	0.642501	0.693546	0.744379	0.794986
23	0.437386	0.489117	0.540699	0.592117	0.643354	0.694395	0.745224	0.795827
24	0.438249	0.489978	0.541557	0.592972	0.644206	0.695244	0.746070	0.796668
25	0.439112	0.490839	0.542416	0.593827	0.645058	0.696093	0.746915	0.797510
26	0.439976	0.491700	0.543274	0.594683	0.645911	0.696941	0.747760	0.798351
27	0.440839	0.492561	0.544132	0.595538	0.646763	0.697790	0.748605	0.799192
28	0.441702	0.493421	0.544990	0.596393	0.647615	0.698639	0.749450	0.800033
29	0.442565	0.494282	0.545849	0.597249	0.648467	0.699488	0.750295	0.800874
30	0.443428	0.495143	0.546707	0.598104	0.649319	0.700336	0.751140	0.801715
31	0.444291	0.496004	0.547565	0.598959	0.650171	0.701185	0.751985	0.802556
32	0.445154	0.496864	0.548423	0.599814	0.651023	0.702033	0.752830	0.803397
33	0.446017	0.497725	0.549281	0.600669	0.651875	0.702882	0.753674	0.804238
34	0.446880	0.498585	0.550138	0.601524	0.652726	0.703730	0.754519	0.805078
35	0.447743	0.499446	0.550996	0.602379	0.653578	0.704578	0.755364	0.805919
36	0.448606	0.500306	0.551854	0.603234	0.654430	0.705426	0.756208	0.806759
37	0.449469	0.501167	0.552712	0.604089	0.655281	0.706275	0.757053	0.807600
38	0.450332	0.502027	0.553569	0.604943	0.656133	0.707123	0.757897	0.808440
39	0.451194	0.502887	0.554427	0.605798	0.656984	0.707971	0.758741	0.809281
40	0.452057	0.503748	0.555285	0.606653	0.657836	0.708819	0.759586	0.810121
41	0.452920	0.504608	0.556142	0.607507	0.658687	0.709667	0.760430	0.810961
42	0.453782	0.505468	0.557000	0.608362	0.659539	0.710514	0.761274	0.811801
43	0.454645	0.506328	0.557857	0.609216	0.660390	0.711362	0.762118	0.812641
44	0.455508	0.507188	0.558715	0.610071	0.661241	0.712210	0.762962	0.813481
45	0.456370	0.508049	0.559572	0.610925	0.662092	0.713058	0.763806	0.814321
46	0.457233	0.508909	0.560429	0.611780	0.662943	0.713905	0.764650	0.815161
47	0.458095	0.509769	0.561287	0.612634	0.663795	0.714753	0.765494	0.816001
48	0.458958	0.510629	0.562144	0.613488	0.664645	0.715600	0.766337	0.816841
49	0.459820	0.511488	0.563001	0.614342	0.665496	0.716448	0.767181	0.817680
50	0.460682	0.512348	0.563858	0.615197	0.666347	0.717295	0.768025	0.818520
51	0.461545	0.513208	0.564715	0.616051	0.667198	0.718143	0.768868	0.819360
52	0.462407	0.514068	0.565572	0.616905	0.668049	0.718990	0.769712	0.820199
53	0.463269	0.514928	0.566429	0.617759	0.668900	0.719837	0.770555	0.821038
54	0.464131	0.515787	0.567286	0.618613	0.669750	0.720684	0.771398	0.821878
55	0.464993	0.516647	0.568143	0.619466	0.670601	0.721531	0.772242	0.822717
56	0.465855	0.517507	0.569000	0.620320	0.671452	0.722378	0.773085	0.823556
57	0.466717	0.518366	0.569857	0.621174	0.672302	0.723225	0.773928	0.824395
58	0.467579	0.519226	0.570714	0.622028	0.673152	0.724072	0.774771	0.825234
59	0.468441	0.520085	0.571570	0.622881	0.674003	0.724919	0.775614	0.826073
60	0.469303	0.520945	0.572427	0.623735	0.674853	0.725766	0.776457	0.826912

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	0.826912	0.877115	0.927051	0.976704	1.026060	1.075104	1.123820	1.172193
1	0.827751	0.877950	0.927881	0.977530	1.026880	1.075919	1.124629	1.172997
2	0.828590	0.878784	0.928711	0.978355	1.027700	1.076733	1.125438	1.173800
3	0.829428	0.879618	0.929540	0.979179	1.028520	1.077548	1.126247	1.174603
4	0.830267	0.880453	0.930370	0.980004	1.029340	1.078362	1.127056	1.175406
5	0.831106	0.881287	0.931200	0.980829	1.030160	1.079176	1.127864	1.176209
6	0.831944	0.882121	0.932029	0.981654	1.030979	1.079991	1.128673	1.177011
7	0.832782	0.882955	0.932859	0.982478	1.031799	1.080805	1.129481	1.177814
8	0.833621	0.883789	0.933688	0.983303	1.032618	1.081619	1.130290	1.178617
9	0.834459	0.884623	0.934517	0.984127	1.033437	1.082433	1.131098	1.179419
10	0.835297	0.885457	0.935347	0.984951	1.034256	1.083246	1.131906	1.180221
11	0.836135	0.886290	0.936176	0.985776	1.035076	1.084060	1.132714	1.181024
12	0.836973	0.887124	0.937005	0.986600	1.035895	1.084874	1.133522	1.181826
13	0.837811	0.887958	0.937834	0.987424	1.036714	1.085687	1.134330	1.182628
14	0.838649	0.888791	0.938663	0.988248	1.037532	1.086501	1.135138	1.183430
15	0.839487	0.889625	0.939491	0.989072	1.038351	1.087314	1.135946	1.184232
16	0.840325	0.890458	0.940320	0.989896	1.039170	1.088127	1.136754	1.185033
17	0.841163	0.891291	0.941149	0.990719	1.039988	1.088941	1.137561	1.185835
18	0.842000	0.892125	0.941977	0.991543	1.040807	1.089754	1.138368	1.186636
19	0.842838	0.892958	0.942806	0.992367	1.041625	1.090567	1.139176	1.187438
20	0.843675	0.893791	0.943634	0.993190	1.042444	1.091380	1.139983	1.188239
21	0.844513	0.894624	0.944463	0.994014	1.043262	1.092193	1.140790	1.189041
22	0.845350	0.895457	0.945291	0.994837	1.044080	1.093005	1.141597	1.189842
23	0.846187	0.896290	0.946119	0.995660	1.044898	1.093818	1.142404	1.190643
24	0.847024	0.897122	0.946947	0.996483	1.045716	1.094630	1.143211	1.191444
25	0.847861	0.897955	0.947775	0.997306	1.046534	1.095443	1.144018	1.192245
26	0.848698	0.898788	0.948603	0.998129	1.047352	1.096255	1.144825	1.193045
27	0.849536	0.899620	0.949431	0.998952	1.048170	1.097067	1.145631	1.193846
28	0.850372	0.900453	0.950259	0.999775	1.048987	1.097880	1.146438	1.194646
29	0.851209	0.901285	0.951086	1.000598	1.049805	1.098692	1.147244	1.195447
30	0.852046	0.902117	0.951914	1.001421	1.050622	1.099504	1.148050	1.196247
31	0.852883	0.902950	0.952742	1.002243	1.051440	1.100316	1.148857	1.197047
32	0.853719	0.903782	0.953569	1.003066	1.052257	1.101127	1.149663	1.197848
33	0.854556	0.904614	0.954396	1.003888	1.053074	1.101939	1.150469	1.198648
34	0.855392	0.905446	0.955224	1.004710	1.053891	1.102751	1.151275	1.199448
35	0.856229	0.906278	0.956051	1.005533	1.054708	1.103562	1.152080	1.200247
36	0.857065	0.907110	0.956878	1.006355	1.055525	1.104374	1.152886	1.201047
37	0.857901	0.907941	0.957705	1.007177	1.056342	1.105185	1.153692	1.201847
38	0.858738	0.908773	0.958532	1.007999	1.057158	1.105996	1.154497	1.202646
39	0.859574	0.909605	0.959359	1.008821	1.057975	1.106807	1.155303	1.203446
40	0.860410	0.910436	0.960186	1.009642	1.058792	1.107618	1.156108	1.204245
41	0.861246	0.911268	0.961012	1.010464	1.059608	1.108429	1.156913	1.205044
42	0.862082	0.912099	0.961839	1.011286	1.060425	1.109240	1.157718	1.205843
43	0.862917	0.912931	0.962666	1.012107	1.061241	1.110051	1.158523	1.206642
44	0.863753	0.913762	0.963492	1.012929	1.062057	1.110862	1.159328	1.207441
45	0.864589	0.914593	0.964318	1.013750	1.062873	1.111672	1.160133	1.208240
46	0.865424	0.915424	0.965145	1.014571	1.063689	1.112483	1.160938	1.209039
47	0.866260	0.916255	0.965971	1.015393	1.064505	1.113293	1.161742	1.209837
48	0.867095	0.917086	0.966797	1.016214	1.065321	1.114104	1.162547	1.210636
49	0.867931	0.917917	0.967623	1.017035	1.066137	1.114914	1.163351	1.211434
50	0.868766	0.918748	0.968449	1.017856	1.066952	1.115724	1.164156	1.212233
51	0.869601	0.919578	0.969275	1.018677	1.067768	1.116534	1.164960	1.213031
52	0.870436	0.920409	0.970101	1.019497	1.068583	1.117344	1.165764	1.213829
53	0.871272	0.921239	0.970927	1.020318	1.069399	1.118154	1.166568	1.214627
54	0.872107	0.922070	0.971752	1.021139	1.070214	1.118963	1.167372	1.215425
55	0.872941	0.922900	0.972578	1.021959	1.071029	1.119773	1.168176	1.216223
56	0.873776	0.923731	0.973403	1.022780	1.071844	1.120583	1.168979	1.217020
57	0.874611	0.924561	0.974229	1.023600	1.072659	1.121392	1.169783	1.217818
58	0.875446	0.925391	0.975054	1.024420	1.073474	1.122201	1.170587	1.218615
59	0.876281	0.926221	0.975879	1.025240	1.074289	1.123011	1.171390	1.219413
60	0.877115	0.927051	0.976704	1.026060	1.075104	1.123820	1.172193	1.220210

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	1.220210	1.267855	1.315113	1.361971	1.408415	1.454429	1.500000	1.545114
1	1.221007	1.268646	1.315898	1.362749	1.409185	1.455192	1.500756	1.545862
2	1.221804	1.269436	1.316682	1.363526	1.409956	1.455955	1.501511	1.546610
3	1.222601	1.270227	1.317466	1.364304	1.410726	1.456718	1.502267	1.547358
4	1.223398	1.271018	1.318250	1.365081	1.411496	1.457481	1.503022	1.548105
5	1.224195	1.271808	1.319034	1.365858	1.412266	1.458244	1.503777	1.548853
6	1.224991	1.272598	1.319818	1.366635	1.413036	1.459006	1.504532	1.549600
7	1.225788	1.273389	1.320601	1.367412	1.413805	1.459769	1.505287	1.550347
8	1.226584	1.274179	1.321385	1.368188	1.414575	1.460531	1.506042	1.551094
9	1.227381	1.274969	1.322168	1.368965	1.415344	1.461293	1.506797	1.551841
10	1.228177	1.275758	1.322951	1.369741	1.416114	1.462055	1.507551	1.552588
11	1.228973	1.276548	1.323735	1.370518	1.416883	1.462817	1.508306	1.553334
12	1.229769	1.277338	1.324518	1.371294	1.417652	1.463579	1.509060	1.554081
13	1.230565	1.278127	1.325301	1.372070	1.418421	1.464341	1.509814	1.554827
14	1.231361	1.278917	1.326083	1.372846	1.419190	1.465102	1.510568	1.555574
15	1.232157	1.279706	1.326866	1.373622	1.419959	1.465864	1.511322	1.556320
16	1.232952	1.280496	1.327649	1.374398	1.420728	1.466625	1.512076	1.557066
17	1.233748	1.281285	1.328431	1.375173	1.421496	1.467386	1.512829	1.557812
18	1.234543	1.282074	1.329214	1.375949	1.422265	1.468147	1.513583	1.558557
19	1.235338	1.282863	1.329996	1.376724	1.423033	1.468908	1.514336	1.559303
20	1.236134	1.283651	1.330778	1.377499	1.423801	1.469669	1.515090	1.560048
21	1.236929	1.284440	1.331560	1.378275	1.424569	1.470430	1.515843	1.560794
22	1.237724	1.285229	1.332342	1.379050	1.425337	1.471190	1.516596	1.561539
23	1.238519	1.286017	1.333124	1.379825	1.426105	1.471951	1.517349	1.562284
24	1.239313	1.286805	1.333906	1.380599	1.426873	1.472711	1.518101	1.563029
25	1.240108	1.287594	1.334687	1.381374	1.427640	1.473472	1.518854	1.563774
26	1.240903	1.288382	1.335469	1.382149	1.428408	1.474232	1.519606	1.564518
27	1.241697	1.289170	1.336250	1.382923	1.429175	1.474992	1.520359	1.565263
28	1.242491	1.289958	1.337031	1.383698	1.429942	1.475751	1.521111	1.566007
29	1.243286	1.290746	1.337812	1.384472	1.430709	1.476511	1.521863	1.566752
30	1.244080	1.291533	1.338593	1.385246	1.431476	1.477271	1.522615	1.567496
31	1.244874	1.292321	1.339374	1.386020	1.432243	1.478030	1.523367	1.568240
32	1.245668	1.293108	1.340155	1.386794	1.433010	1.478789	1.524119	1.568984
33	1.246462	1.293896	1.340936	1.387568	1.433776	1.479549	1.524870	1.569727
34	1.247255	1.294683	1.341717	1.388341	1.434543	1.480308	1.525622	1.570471
35	1.248049	1.295470	1.342497	1.389115	1.435309	1.481067	1.526373	1.571214
36	1.248842	1.296257	1.343277	1.389888	1.436076	1.481826	1.527124	1.571958
37	1.249636	1.297044	1.344058	1.390661	1.436842	1.482584	1.527875	1.572701
38	1.250429	1.297831	1.344838	1.391435	1.437608	1.483343	1.528626	1.573444
39	1.251222	1.298618	1.345618	1.392208	1.438374	1.484101	1.529377	1.574187
40	1.252015	1.299404	1.346398	1.392981	1.439139	1.484860	1.530128	1.574930
41	1.252808	1.300191	1.347177	1.393753	1.439905	1.485618	1.530878	1.575672
42	1.253601	1.300977	1.347957	1.394526	1.440671	1.486376	1.531629	1.576415
43	1.254394	1.301764	1.348737	1.395299	1.441436	1.487134	1.532379	1.577157
44	1.255187	1.302550	1.349516	1.396071	1.442201	1.487892	1.533129	1.577900
45	1.255979	1.303336	1.350295	1.396844	1.442966	1.488650	1.533879	1.578642
46	1.256772	1.304122	1.351075	1.397616	1.443731	1.489407	1.534629	1.579384
47	1.257564	1.304908	1.351854	1.398388	1.444496	1.490165	1.535379	1.580126
48	1.258356	1.305693	1.352633	1.399160	1.445261	1.490922	1.536129	1.580867
49	1.259148	1.306479	1.353412	1.399932	1.446026	1.491679	1.536878	1.581609
50	1.259941	1.307264	1.354190	1.400704	1.446790	1.492436	1.537628	1.582350
51	1.260732	1.308050	1.354969	1.401475	1.447555	1.493193	1.538377	1.583092
52	1.261524	1.308835	1.355747	1.402247	1.448319	1.493950	1.539126	1.583833
53	1.262316	1.309620	1.356526	1.403018	1.449083	1.494707	1.539875	1.584574
54	1.263107	1.310405	1.357304	1.403790	1.449847	1.495463	1.540624	1.585315
55	1.263899	1.311190	1.358082	1.404561	1.450611	1.496220	1.541373	1.586056
56	1.264690	1.311975	1.358860	1.405332	1.451375	1.496976	1.542121	1.586797
57	1.265482	1.312760	1.359638	1.406103	1.452139	1.497732	1.542870	1.587537
58	1.266273	1.313545	1.360416	1.406873	1.452902	1.498488	1.543618	1.588277
59	1.267064	1.314329	1.361194	1.407644	1.453666	1.499244	1.544366	1.589018
60	1.267855	1.315113	1.361971	1.408415	1.454429	1.500000	1.545114	1.589758

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	1.589758	1.633917	1.677579	1.720729	1.763356	1.805445	1.846985	1.887961
1	1.590498	1.634649	1.678302	1.721444	1.764062	1.806142	1.847672	1.888639
2	1.591238	1.635381	1.679025	1.722159	1.764768	1.806839	1.848359	1.889317
3	1.591977	1.636112	1.679749	1.722873	1.765473	1.807535	1.849047	1.889995
4	1.592717	1.636844	1.680471	1.723588	1.766179	1.808232	1.849734	1.890673
5	1.593456	1.637575	1.681194	1.724302	1.766884	1.808928	1.850421	1.891350
6	1.594196	1.638306	1.681917	1.725016	1.767589	1.809624	1.851108	1.892027
7	1.594935	1.639037	1.682639	1.725730	1.768294	1.810320	1.851794	1.892704
8	1.595674	1.639768	1.683362	1.726444	1.768999	1.811016	1.852481	1.893382
9	1.596413	1.640499	1.684084	1.727157	1.769704	1.811711	1.853167	1.894058
10	1.597152	1.641229	1.684806	1.727871	1.770408	1.812407	1.853853	1.894735
11	1.597890	1.641959	1.685528	1.728584	1.771113	1.813102	1.854539	1.895412
12	1.598629	1.642690	1.686250	1.729297	1.771817	1.813797	1.855225	1.896088
13	1.599367	1.643420	1.686972	1.730010	1.772521	1.814492	1.855911	1.896764
14	1.600106	1.644150	1.687693	1.730723	1.773225	1.815187	1.856596	1.897440
15	1.600844	1.644880	1.688415	1.731436	1.773929	1.815882	1.857282	1.898116
16	1.601582	1.645609	1.689136	1.732148	1.774633	1.816577	1.857967	1.898792
17	1.602319	1.646339	1.689857	1.732861	1.775336	1.817271	1.858652	1.899467
18	1.603057	1.647069	1.690578	1.733573	1.776040	1.817965	1.859337	1.900143
19	1.603795	1.647798	1.691299	1.734285	1.776743	1.818659	1.860022	1.900818
20	1.604532	1.648527	1.692020	1.734997	1.777446	1.819353	1.860706	1.901493
21	1.605269	1.649256	1.692740	1.735709	1.778149	1.820047	1.861391	1.902168
22	1.606007	1.649985	1.693461	1.736421	1.778852	1.820741	1.862075	1.902843
23	1.606744	1.650714	1.694181	1.737132	1.779554	1.821434	1.862759	1.903517
24	1.607481	1.651442	1.694901	1.737844	1.780257	1.822128	1.863443	1.904192
25	1.608217	1.652171	1.695621	1.738555	1.780959	1.822821	1.864127	1.904866
26	1.608954	1.652899	1.696341	1.739266	1.781661	1.823514	1.864811	1.905540
27	1.609690	1.653627	1.697061	1.739977	1.782363	1.824207	1.865494	1.906214
28	1.610427	1.654355	1.697780	1.740688	1.783065	1.824899	1.866178	1.906888
29	1.611163	1.655083	1.698500	1.741398	1.783767	1.825592	1.866861	1.907561
30	1.611899	1.655811	1.699219	1.742109	1.784468	1.826284	1.867544	1.908235
31	1.612635	1.656539	1.699938	1.742819	1.785170	1.826977	1.868227	1.908908
32	1.613371	1.657266	1.700657	1.743529	1.785871	1.827669	1.868909	1.909581
33	1.614106	1.657993	1.701376	1.744240	1.786572	1.828361	1.869592	1.910254
34	1.614842	1.658721	1.702094	1.744949	1.787273	1.829052	1.870274	1.910927
35	1.615577	1.659448	1.702813	1.745659	1.787974	1.829744	1.870957	1.911600
36	1.616312	1.660175	1.703531	1.746369	1.788675	1.830436	1.871639	1.912272
37	1.617047	1.660901	1.704250	1.747078	1.789375	1.831127	1.872321	1.912944
38	1.617783	1.661628	1.704968	1.747788	1.790076	1.831818	1.873003	1.913617
39	1.618517	1.662355	1.705686	1.748497	1.790776	1.832509	1.873684	1.914289
40	1.619252	1.663081	1.706403	1.749206	1.791476	1.833200	1.874366	1.914960
41	1.619987	1.663807	1.707121	1.749915	1.792176	1.833891	1.875047	1.915632
42	1.620721	1.664533	1.707839	1.750624	1.792876	1.834581	1.875728	1.916304
43	1.621455	1.665259	1.708556	1.751332	1.793575	1.835272	1.876409	1.916975
44	1.622189	1.665985	1.709273	1.752041	1.794275	1.835962	1.877090	1.917646
45	1.622923	1.666711	1.709990	1.752749	1.794974	1.836652	1.877770	1.918317
46	1.623657	1.667436	1.710707	1.753457	1.795673	1.837342	1.878451	1.918988
47	1.624391	1.668162	1.711424	1.754165	1.796372	1.838032	1.879131	1.919659
48	1.625125	1.668887	1.712141	1.754873	1.797071	1.838721	1.879811	1.920329
49	1.625858	1.669612	1.712857	1.755581	1.797770	1.839411	1.880491	1.921000
50	1.626591	1.670337	1.713574	1.756288	1.798468	1.840100	1.881171	1.921670
51	1.627325	1.671062	1.714290	1.756996	1.799166	1.840789	1.881851	1.922340
52	1.628058	1.671786	1.715006	1.757703	1.799865	1.841478	1.882531	1.923010
53	1.628791	1.672511	1.715722	1.758410	1.800563	1.842167	1.883210	1.923679
54	1.629524	1.673235	1.716438	1.759117	1.801261	1.842856	1.883889	1.924349
55	1.630256	1.673960	1.717153	1.759824	1.801959	1.843544	1.884568	1.925018
56	1.630989	1.674684	1.717869	1.760531	1.802656	1.844233	1.885247	1.925688
57	1.631721	1.675408	1.718584	1.761237	1.803354	1.844921	1.885926	1.926357
58	1.632453	1.676131	1.719299	1.761944	1.804051	1.845609	1.886605	1.927026
59	1.633185	1.676855	1.720014	1.762650	1.804748	1.846297	1.887283	1.927694
60	1.633917	1.677579	1.720729	1.763356	1.805445	1.846985	1.887961	1.928363

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	1.928363	1.968177	2.007392	2.045995	2.083975	2.121320	2.158020	2.194061
1	1.929031	1.968836	2.008040	2.046633	2.084603	2.121937	2.158626	2.194656
2	1.929700	1.969494	2.008688	2.047271	2.085230	2.122554	2.159231	2.195251
3	1.930368	1.970152	2.009337	2.047909	2.085858	2.123171	2.159837	2.195846
4	1.931036	1.970810	2.009984	2.048547	2.086485	2.123787	2.160443	2.196440
5	1.931703	1.971468	2.010632	2.049184	2.087112	2.124403	2.161048	2.197035
6	1.932371	1.972126	2.011280	2.049821	2.087738	2.125020	2.161653	2.197629
7	1.933038	1.972783	2.011927	2.050458	2.088365	2.125635	2.162258	2.198223
8	1.933706	1.973441	2.012575	2.051095	2.088991	2.126251	2.162863	2.198817
9	1.934373	1.974098	2.013222	2.051732	2.089618	2.126867	2.163468	2.199410
10	1.935040	1.974755	2.013869	2.052369	2.090244	2.127482	2.164072	2.200003
11	1.935706	1.975412	2.014515	2.053005	2.090870	2.128097	2.164677	2.200597
12	1.936373	1.976068	2.015162	2.053641	2.091495	2.128712	2.165281	2.201190
13	1.937040	1.976725	2.015808	2.054277	2.092121	2.129327	2.165885	2.201782
14	1.937706	1.977381	2.016454	2.054913	2.092746	2.129942	2.166488	2.202375
15	1.938372	1.978037	2.017101	2.055549	2.093371	2.130556	2.167092	2.202968
16	1.939038	1.978693	2.017746	2.056185	2.093997	2.131171	2.167695	2.203560
17	1.939704	1.979349	2.018392	2.056820	2.094621	2.131784	2.168298	2.204152
18	1.940369	1.980005	2.019037	2.057455	2.095246	2.132398	2.168901	2.204744
19	1.941035	1.980661	2.019683	2.058090	2.095870	2.133012	2.169504	2.205336
20	1.941700	1.981316	2.020328	2.058725	2.096495	2.133626	2.170107	2.205927
21	1.942365	1.981971	2.020973	2.059360	2.097119	2.134239	2.170709	2.206518
22	1.943030	1.982626	2.021618	2.059994	2.097743	2.134852	2.171312	2.207109
23	1.943695	1.983281	2.022263	2.060628	2.098366	2.135465	2.171914	2.207700
24	1.944360	1.983936	2.022907	2.061263	2.098990	2.136078	2.172516	2.208291
25	1.945024	1.984590	2.023552	2.061897	2.099613	2.136691	2.173117	2.208882
26	1.945689	1.985245	2.024196	2.062530	2.100237	2.137303	2.173719	2.209472
27	1.946353	1.985899	2.024840	2.063164	2.100860	2.137916	2.174320	2.210063
28	1.947017	1.986553	2.025484	2.063797	2.101483	2.138528	2.174922	2.210653
29	1.947681	1.987207	2.026127	2.064431	2.102105	2.139140	2.175522	2.211242
30	1.948344	1.987860	2.026771	2.065064	2.102728	2.139751	2.176123	2.211832
31	1.949008	1.988514	2.027414	2.065697	2.103350	2.140363	2.176724	2.212421
32	1.949671	1.989167	2.028057	2.066329	2.103972	2.140974	2.177324	2.213011
33	1.950334	1.989820	2.028700	2.066962	2.104594	2.141586	2.177924	2.213600
34	1.950997	1.990473	2.029343	2.067594	2.105216	2.142197	2.178524	2.214189
35	1.951660	1.991126	2.029985	2.068227	2.105838	2.142807	2.179124	2.214777
36	1.952323	1.991779	2.030628	2.068859	2.106459	2.143418	2.179724	2.215366
37	1.952985	1.992431	2.031270	2.069490	2.107080	2.144028	2.180324	2.215954
38	1.953648	1.993084	2.031912	2.070122	2.107702	2.144639	2.180923	2.216543
39	1.954310	1.993736	2.032554	2.070754	2.108323	2.145249	2.181522	2.217131
40	1.954972	1.994388	2.033196	2.071385	2.108943	2.145859	2.182121	2.217718
41	1.955634	1.995039	2.033838	2.072016	2.109564	2.146469	2.182720	2.218306
42	1.956295	1.995691	2.034479	2.072647	2.110184	2.147078	2.183318	2.218893
43	1.956957	1.996343	2.035120	2.073278	2.110804	2.147688	2.183917	2.219481
44	1.957618	1.996994	2.035761	2.073909	2.111424	2.148297	2.184515	2.220068
45	1.958279	1.997645	2.036402	2.074539	2.112044	2.148906	2.185113	2.220654
46	1.958940	1.998296	2.037043	2.075170	2.112664	2.149515	2.185711	2.221241
47	1.959601	1.998947	2.037683	2.075800	2.113283	2.150123	2.186308	2.221828
48	1.960262	1.999597	2.038324	2.076430	2.113903	2.150732	2.186906	2.222414
49	1.960922	2.000248	2.038964	2.077059	2.114522	2.151340	2.187503	2.223000
50	1.961583	2.000898	2.039604	2.077689	2.115141	2.151948	2.188100	2.223586
51	1.962243	2.001548	2.040244	2.078318	2.115759	2.152556	2.188697	2.224171
52	1.962903	2.002198	2.040884	2.078948	2.116378	2.153164	2.189294	2.224757
53	1.963563	2.002848	2.041523	2.079577	2.116997	2.153772	2.189891	2.225343
54	1.964223	2.003498	2.042163	2.080206	2.117615	2.154379	2.190487	2.225928
55	1.964882	2.004147	2.042802	2.080834	2.118233	2.154986	2.191083	2.226513
56	1.965541	2.004797	2.043441	2.081463	2.118851	2.155593	2.191679	2.227097
57	1.966201	2.005445	2.044080	2.082091	2.119468	2.156200	2.192275	2.227682
58	1.966860	2.006094	2.044718	2.082719	2.120086	2.156807	2.192870	2.228266
59	1.967518	2.006743	2.045357	2.083347	2.120703	2.157413	2.193466	2.228851
60	1.968177	2.007392	2.045995	2.083975	2.121320	2.158020	2.194061	2.229434

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 3-inch Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	2.229434	2.264129	2.298133	2.331438	2.364032	2.395907	2.427051	2.457456
1	2.230018	2.264701	2.298694	2.331987	2.364569	2.396432	2.427564	2.457957
2	2.230602	2.265273	2.299255	2.332536	2.365106	2.396956	2.428077	2.458457
3	2.231185	2.265846	2.299815	2.333085	2.365643	2.397481	2.428589	2.458957
4	2.231769	2.266417	2.300375	2.333633	2.366180	2.398006	2.429101	2.459457
5	2.232352	2.266989	2.300936	2.334181	2.366716	2.398530	2.429613	2.459956
6	2.232935	2.267560	2.301496	2.334729	2.367252	2.399054	2.430125	2.460456
7	2.233517	2.268132	2.302055	2.335277	2.367788	2.399578	2.430636	2.460955
8	2.234100	2.268703	2.302615	2.335825	2.368324	2.400102	2.431148	2.461454
9	2.234682	2.269274	2.303174	2.336373	2.368860	2.400625	2.431659	2.461953
10	2.235264	2.269845	2.303733	2.336920	2.369395	2.401148	2.432170	2.462451
11	2.235846	2.270415	2.304292	2.337467	2.369930	2.401671	2.432681	2.462950
12	2.236428	2.270985	2.304851	2.338014	2.370465	2.402194	2.433192	2.463448
13	2.237010	2.271555	2.305409	2.338561	2.371000	2.402717	2.433702	2.463946
14	2.237591	2.272125	2.305967	2.339107	2.371534	2.403239	2.434212	2.464443
15	2.238172	2.272695	2.306525	2.339653	2.372069	2.403761	2.434722	2.464941
16	2.238753	2.273265	2.307083	2.340200	2.372603	2.404284	2.435232	2.465438
17	2.239334	2.273834	2.307641	2.340745	2.373137	2.404805	2.435741	2.465935
18	2.239915	2.274403	2.308199	2.341291	2.373671	2.405327	2.436251	2.466432
19	2.240495	2.274972	2.308756	2.341837	2.374204	2.405848	2.436760	2.466929
20	2.241075	2.275541	2.309313	2.342382	2.374738	2.406370	2.437269	2.467425
21	2.241655	2.276109	2.309870	2.342927	2.375271	2.406891	2.437777	2.467921
22	2.242235	2.276678	2.310427	2.343472	2.375804	2.407411	2.438286	2.468418
23	2.242815	2.277246	2.310983	2.344017	2.376337	2.407932	2.438794	2.468914
24	2.243394	2.277814	2.311540	2.344562	2.376869	2.408453	2.439302	2.469409
25	2.243974	2.278382	2.312096	2.345106	2.377401	2.408973	2.439810	2.469905
26	2.244553	2.278949	2.312652	2.345650	2.377934	2.409493	2.440318	2.470400
27	2.245132	2.279517	2.313208	2.346194	2.378465	2.410012	2.440825	2.470895
28	2.245710	2.280084	2.313763	2.346738	2.378997	2.410532	2.441333	2.471390
29	2.246289	2.280651	2.314319	2.347281	2.379529	2.411052	2.441840	2.471884
30	2.246867	2.281218	2.314874	2.347825	2.380060	2.411571	2.442347	2.472379
31	2.247445	2.281785	2.315429	2.348368	2.380591	2.412090	2.442853	2.472873
32	2.248023	2.282351	2.315984	2.348911	2.381122	2.412608	2.443360	2.473367
33	2.248601	2.282917	2.316538	2.349453	2.381653	2.413127	2.443866	2.473861
34	2.249179	2.283483	2.317092	2.349996	2.382183	2.413645	2.444372	2.474354
35	2.249756	2.284049	2.317647	2.350538	2.382714	2.414163	2.444878	2.474847
36	2.250333	2.284615	2.318201	2.351080	2.383244	2.414681	2.445383	2.475341
37	2.250910	2.285180	2.318754	2.351622	2.383774	2.415199	2.445889	2.475833
38	2.251487	2.285746	2.319308	2.352164	2.384304	2.415717	2.446394	2.476326
39	2.252064	2.286311	2.319862	2.352706	2.384833	2.416234	2.446899	2.476819
40	2.252640	2.286876	2.320415	2.353247	2.385362	2.416751	2.447404	2.477311
41	2.253217	2.287441	2.320968	2.353788	2.385892	2.417268	2.447908	2.477803
42	2.253793	2.288005	2.321521	2.354329	2.386420	2.417785	2.448413	2.478295
43	2.254368	2.288569	2.322073	2.354870	2.386949	2.418301	2.448917	2.478787
44	2.254944	2.289134	2.322626	2.355411	2.387478	2.418818	2.449421	2.479278
45	2.255519	2.289697	2.323178	2.355951	2.388006	2.419334	2.449925	2.479769
46	2.256095	2.290261	2.323730	2.356491	2.388534	2.419850	2.450428	2.480260
47	2.256670	2.290825	2.324282	2.357031	2.389062	2.420366	2.450932	2.480751
48	2.257245	2.291388	2.324833	2.357571	2.389590	2.420881	2.451435	2.481242
49	2.257819	2.291951	2.325385	2.358110	2.390117	2.421396	2.451938	2.481732
50	2.258394	2.292514	2.325936	2.358650	2.390645	2.421911	2.452440	2.482222
51	2.258968	2.293077	2.326487	2.359189	2.391172	2.422426	2.452943	2.482712
52	2.259542	2.293640	2.327038	2.359728	2.391699	2.422941	2.453445	2.483202
53	2.260117	2.294202	2.327589	2.360267	2.392226	2.423455	2.453947	2.483692
54	2.260690	2.294764	2.328139	2.360805	2.392752	2.423970	2.454449	2.484181
55	2.261264	2.295326	2.328690	2.361344	2.393278	2.424484	2.454951	2.484670
56	2.261837	2.295888	2.329240	2.361882	2.393804	2.424998	2.455452	2.485159
57	2.262410	2.296450	2.329789	2.362420	2.394330	2.425511	2.455954	2.485648
58	2.262983	2.297011	2.330339	2.362957	2.394856	2.426025	2.456455	2.486136
59	2.263556	2.297572	2.330889	2.363495	2.395381	2.426538	2.456955	2.486625
60	2.264129	2.298133	2.331438	2.364032	2.395907	2.427051	2.457456	2.487113

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 5-inch Sine-Bar

Constants for Setting a 5-inch Sine-Bar for 1° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.00000	0.08726	0.17450	0.26168	0.34878	0.43578	0.52264	0.60935
1	0.00145	0.08872	0.17595	0.26313	0.35023	0.43723	0.52409	0.61079
2	0.00291	0.09017	0.17740	0.26458	0.35168	0.43868	0.52554	0.61223
3	0.00436	0.09162	0.17886	0.26604	0.35313	0.44013	0.52698	0.61368
4	0.00582	0.09308	0.18031	0.26749	0.35459	0.44157	0.52843	0.61512
5	0.00727	0.09453	0.18177	0.26894	0.35604	0.44302	0.52987	0.61656
6	0.00873	0.09599	0.18322	0.27039	0.35749	0.44447	0.53132	0.61801
7	0.01018	0.09744	0.18467	0.27185	0.35894	0.44592	0.53277	0.61945
8	0.01164	0.09890	0.18613	0.27330	0.36039	0.44737	0.53421	0.62089
9	0.01309	0.10035	0.18758	0.27475	0.36184	0.44882	0.53566	0.62234
10	0.01454	0.10180	0.18903	0.27620	0.36329	0.45027	0.53710	0.62378
11	0.01600	0.10326	0.19049	0.27766	0.36474	0.45171	0.53855	0.62522
12	0.01745	0.10471	0.19194	0.27911	0.36619	0.45316	0.54000	0.62667
13	0.01891	0.10617	0.19339	0.28056	0.36764	0.45461	0.54144	0.62811
14	0.02036	0.10762	0.19485	0.28201	0.36909	0.45606	0.54289	0.62955
15	0.02182	0.10907	0.19630	0.28346	0.37054	0.45751	0.54433	0.63099
16	0.02327	0.11053	0.19775	0.28492	0.37199	0.45896	0.54578	0.63244
17	0.02473	0.11198	0.19921	0.28637	0.37344	0.46040	0.54723	0.63388
18	0.02618	0.11344	0.20066	0.28782	0.37489	0.46185	0.54867	0.63532
19	0.02763	0.11489	0.20211	0.28927	0.37634	0.46330	0.55012	0.63677
20	0.02909	0.11634	0.20357	0.29072	0.37779	0.46475	0.55156	0.63821
21	0.03054	0.11780	0.20502	0.29218	0.37924	0.46620	0.55301	0.63965
22	0.03200	0.11925	0.20647	0.29363	0.38069	0.46765	0.55445	0.64109
23	0.03345	0.12071	0.20793	0.29508	0.38214	0.46909	0.55590	0.64254
24	0.03491	0.12216	0.20938	0.29653	0.38360	0.47054	0.55734	0.64398
25	0.03636	0.12361	0.21083	0.29798	0.38505	0.47199	0.55879	0.64542
26	0.03782	0.12507	0.21228	0.29944	0.38650	0.47344	0.56024	0.64686
27	0.03927	0.12652	0.21374	0.30089	0.38795	0.47489	0.56168	0.64830
28	0.04072	0.12798	0.21519	0.30234	0.38940	0.47633	0.56313	0.64975
29	0.04218	0.12943	0.21664	0.30379	0.39085	0.47778	0.56457	0.65119
30	0.04363	0.13088	0.21810	0.30524	0.39230	0.47923	0.56602	0.65263
31	0.04509	0.13234	0.21955	0.30669	0.39375	0.48068	0.56746	0.65407
32	0.04654	0.13379	0.22100	0.30815	0.39520	0.48212	0.56891	0.65551
33	0.04800	0.13525	0.22246	0.30960	0.39665	0.48357	0.57035	0.65696
34	0.04945	0.13670	0.22391	0.31105	0.39810	0.48502	0.57180	0.65840
35	0.05090	0.13815	0.22536	0.31250	0.39954	0.48647	0.57324	0.65984
36	0.05236	0.13961	0.22681	0.31395	0.40099	0.48791	0.57469	0.66128
37	0.05381	0.14106	0.22827	0.31540	0.40244	0.48936	0.57613	0.66272
38	0.05527	0.14252	0.22972	0.31686	0.40389	0.49081	0.57758	0.66417
39	0.05672	0.14397	0.23117	0.31831	0.40534	0.49226	0.57902	0.66561
40	0.05818	0.14542	0.23263	0.31976	0.40679	0.49370	0.58046	0.66705
41	0.05963	0.14688	0.23408	0.32121	0.40824	0.49515	0.58191	0.66849
42	0.06109	0.14833	0.23553	0.32266	0.40969	0.49660	0.58335	0.66993
43	0.06254	0.14979	0.23699	0.32411	0.41114	0.49805	0.58480	0.67137
44	0.06399	0.15124	0.23844	0.32556	0.41259	0.49949	0.58624	0.67281
45	0.06545	0.15269	0.23989	0.32702	0.41404	0.50094	0.58769	0.67425
46	0.06690	0.15415	0.24134	0.32847	0.41549	0.50239	0.58913	0.67570
47	0.06836	0.15560	0.24280	0.32992	0.41694	0.50383	0.59058	0.67714
48	0.06981	0.15705	0.24425	0.33137	0.41839	0.50528	0.59202	0.67858
49	0.07127	0.15851	0.24570	0.33282	0.41984	0.50673	0.59346	0.68002
50	0.07272	0.15996	0.24715	0.33427	0.42129	0.50818	0.59491	0.68146
51	0.07417	0.16141	0.24861	0.33572	0.42274	0.50962	0.59635	0.68290
52	0.07563	0.16287	0.25006	0.33717	0.42419	0.51107	0.59780	0.68434
53	0.07708	0.16432	0.25151	0.33863	0.42564	0.51252	0.59924	0.68578
54	0.07854	0.16578	0.25296	0.34008	0.42708	0.51396	0.60068	0.68722
55	0.07999	0.16723	0.25442	0.34153	0.42853	0.51541	0.60213	0.68866
56	0.08145	0.16868	0.25587	0.34298	0.42998	0.51686	0.60357	0.69010
57	0.08290	0.17014	0.25732	0.34443	0.43143	0.51830	0.60502	0.69154
58	0.08435	0.17159	0.25877	0.34588	0.43288	0.51975	0.60646	0.69298
59	0.08581	0.17304	0.26023	0.34733	0.43433	0.52120	0.60790	0.69443
60	0.08726	0.17450	0.26168	0.34878	0.43578	0.52264	0.60935	0.69587

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	0.69587	0.78217	0.86824	0.95404	1.03956	1.12476	1.20961	1.29410
1	0.69731	0.78361	0.86967	0.95547	1.04098	1.12617	1.21102	1.29550
2	0.69875	0.78505	0.87111	0.95690	1.04240	1.12759	1.21243	1.29690
3	0.70019	0.78648	0.87254	0.95833	1.04383	1.12901	1.21384	1.29831
4	0.70163	0.78792	0.87397	0.95976	1.04525	1.13042	1.21525	1.29971
5	0.70307	0.78935	0.87540	0.96118	1.04667	1.13184	1.21666	1.30112
6	0.70451	0.79079	0.87683	0.96261	1.04809	1.13326	1.21808	1.30252
7	0.70595	0.79223	0.87827	0.96404	1.04951	1.13467	1.21949	1.30393
8	0.70739	0.79366	0.87970	0.96546	1.05094	1.13609	1.22090	1.30533
9	0.70883	0.79510	0.88113	0.96689	1.05236	1.13751	1.22231	1.30673
10	0.71027	0.79653	0.88256	0.96832	1.05378	1.13892	1.22372	1.30814
11	0.71171	0.79797	0.88399	0.96974	1.05520	1.14034	1.22513	1.30954
12	0.71314	0.79941	0.88542	0.97117	1.05662	1.14175	1.22654	1.31095
13	0.71458	0.80084	0.88686	0.97260	1.05805	1.14317	1.22795	1.31235
14	0.71602	0.80228	0.88829	0.97403	1.05947	1.14459	1.22936	1.31375
15	0.71746	0.80371	0.88972	0.97545	1.06089	1.14600	1.23077	1.31516
16	0.71890	0.80515	0.89115	0.97688	1.06231	1.14742	1.23218	1.31656
17	0.72034	0.80658	0.89258	0.97830	1.06373	1.14883	1.23359	1.31796
18	0.72178	0.80802	0.89401	0.97973	1.06515	1.15025	1.23500	1.31937
19	0.72322	0.80945	0.89544	0.98116	1.06657	1.15166	1.23640	1.32077
20	0.72466	0.81089	0.89687	0.98258	1.06799	1.15308	1.23781	1.32217
21	0.72610	0.81232	0.89830	0.98401	1.06941	1.15449	1.23922	1.32357
22	0.72754	0.81376	0.89973	0.98544	1.07084	1.15591	1.24063	1.32498
23	0.72898	0.81519	0.90117	0.98686	1.07226	1.15732	1.24204	1.32638
24	0.73042	0.81663	0.90260	0.98829	1.07368	1.15874	1.24345	1.32778
25	0.73185	0.81806	0.90403	0.98971	1.07510	1.16015	1.24486	1.32918
26	0.73329	0.81950	0.90546	0.99114	1.07652	1.16157	1.24627	1.33058
27	0.73473	0.82093	0.90689	0.99256	1.07794	1.16298	1.24768	1.33199
28	0.73617	0.82237	0.90832	0.99399	1.07936	1.16440	1.24908	1.33339
29	0.73761	0.82380	0.90975	0.99541	1.08078	1.16581	1.25049	1.33479
30	0.73905	0.82524	0.91118	0.99684	1.08220	1.16723	1.25190	1.33619
31	0.74049	0.82667	0.91261	0.99826	1.08362	1.16864	1.25331	1.33759
32	0.74192	0.82811	0.91404	0.99969	1.08504	1.17006	1.25472	1.33899
33	0.74336	0.82954	0.91547	1.00112	1.08646	1.17147	1.25612	1.34040
34	0.74480	0.83098	0.91690	1.00254	1.08788	1.17288	1.25753	1.34180
35	0.74624	0.83241	0.91833	1.00396	1.08930	1.17430	1.25894	1.34320
36	0.74768	0.83384	0.91976	1.00539	1.09072	1.17571	1.26035	1.34460
37	0.74911	0.83528	0.92119	1.00681	1.09214	1.17712	1.26175	1.34600
38	0.75055	0.83671	0.92262	1.00824	1.09355	1.17854	1.26316	1.34740
39	0.75199	0.83815	0.92405	1.00966	1.09497	1.17995	1.26457	1.34880
40	0.75343	0.83958	0.92547	1.01109	1.09639	1.18136	1.26598	1.35020
41	0.75487	0.84101	0.92690	1.01251	1.09781	1.18278	1.26738	1.35160
42	0.75630	0.84245	0.92833	1.01394	1.09923	1.18419	1.26879	1.35300
43	0.75774	0.84388	0.92976	1.01536	1.10065	1.18560	1.27020	1.35440
44	0.75918	0.84531	0.93119	1.01678	1.10207	1.18702	1.27160	1.35580
45	0.76062	0.84675	0.93262	1.01821	1.10349	1.18843	1.27301	1.35720
46	0.76205	0.84818	0.93405	1.01963	1.10491	1.18984	1.27442	1.35860
47	0.76349	0.84961	0.93548	1.02106	1.10632	1.19125	1.27582	1.36000
48	0.76493	0.85105	0.93691	1.02248	1.10774	1.19267	1.27723	1.36140
49	0.76637	0.85248	0.93834	1.02390	1.10916	1.19408	1.27863	1.36280
50	0.76780	0.85391	0.93976	1.02533	1.11058	1.19549	1.28004	1.36420
51	0.76924	0.85535	0.94119	1.02675	1.11200	1.19690	1.28145	1.36560
52	0.77068	0.85678	0.94262	1.02817	1.11342	1.19832	1.28285	1.36700
53	0.77211	0.85821	0.94405	1.02960	1.11483	1.19973	1.28426	1.36840
54	0.77355	0.85965	0.94548	1.03102	1.11625	1.20114	1.28566	1.36980
55	0.77499	0.86108	0.94691	1.03244	1.11767	1.20255	1.28707	1.37119
56	0.77643	0.86251	0.94833	1.03387	1.11909	1.20396	1.28847	1.37259
57	0.77786	0.86394	0.94976	1.03529	1.12050	1.20538	1.28988	1.37399
58	0.77930	0.86538	0.95119	1.03671	1.12192	1.20679	1.29129	1.37539
59	0.78074	0.86681	0.95262	1.03814	1.12334	1.20820	1.29269	1.37679
60	0.78217	0.86824	0.95404	1.03956	1.12476	1.20961	1.29410	1.37819

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	1.37819	1.46186	1.54509	1.62784	1.71010	1.79184	1.87303	1.95366
1	1.37958	1.46325	1.54647	1.62922	1.71147	1.79320	1.87438	1.95499
2	1.38098	1.46464	1.54785	1.63059	1.71283	1.79456	1.87573	1.95633
3	1.38238	1.46603	1.54923	1.63197	1.71420	1.79591	1.87708	1.95767
4	1.38378	1.46742	1.55062	1.63334	1.71557	1.79727	1.87843	1.95901
5	1.38518	1.46881	1.55200	1.63472	1.71693	1.79863	1.87977	1.96035
6	1.38657	1.47020	1.55338	1.63609	1.71830	1.79998	1.88112	1.96169
7	1.38797	1.47159	1.55476	1.63746	1.71966	1.80134	1.88247	1.96302
8	1.38937	1.47298	1.55615	1.63884	1.72103	1.80270	1.88382	1.96436
9	1.39076	1.47437	1.55753	1.64021	1.72240	1.80405	1.88516	1.96570
10	1.39216	1.47576	1.55891	1.64159	1.72376	1.80541	1.88651	1.96704
11	1.39356	1.47715	1.56029	1.64296	1.72513	1.80677	1.88786	1.96837
12	1.39496	1.47854	1.56167	1.64433	1.72649	1.80812	1.88920	1.96971
13	1.39635	1.47993	1.56306	1.64571	1.72786	1.80948	1.89055	1.97105
14	1.39775	1.48132	1.56444	1.64708	1.72922	1.81083	1.89190	1.97238
15	1.39915	1.48271	1.56582	1.64845	1.73059	1.81219	1.89324	1.97372
16	1.40054	1.48410	1.56720	1.64983	1.73195	1.81355	1.89459	1.97506
17	1.40194	1.48549	1.56858	1.65120	1.73331	1.81490	1.89594	1.97639
18	1.40333	1.48687	1.56996	1.65257	1.73468	1.81626	1.89728	1.97773
19	1.40473	1.48826	1.57134	1.65394	1.73604	1.81761	1.89863	1.97906
20	1.40613	1.48965	1.57272	1.65532	1.73741	1.81897	1.89997	1.98040
21	1.40752	1.49104	1.57410	1.65669	1.73877	1.82032	1.90132	1.98173
22	1.40892	1.49243	1.57548	1.65806	1.74013	1.82168	1.90266	1.98307
23	1.41031	1.49382	1.57687	1.65943	1.74150	1.82303	1.90401	1.98440
24	1.41171	1.49520	1.57825	1.66081	1.74286	1.82438	1.90535	1.98574
25	1.41310	1.49659	1.57963	1.66218	1.74422	1.82574	1.90670	1.98707
26	1.41450	1.49798	1.58101	1.66355	1.74559	1.82709	1.90804	1.98841
27	1.41589	1.49937	1.58238	1.66492	1.74695	1.82845	1.90939	1.98974
28	1.41729	1.50075	1.58376	1.66629	1.74831	1.82980	1.91073	1.99108
29	1.41868	1.50214	1.58514	1.66766	1.74967	1.83115	1.91207	1.99241
30	1.42008	1.50353	1.58652	1.66903	1.75104	1.83251	1.91342	1.99375
31	1.42147	1.50492	1.58790	1.67041	1.75240	1.83386	1.91476	1.99508
32	1.42287	1.50630	1.58928	1.67178	1.75376	1.83521	1.91610	1.99641
33	1.42426	1.50769	1.59066	1.67315	1.75512	1.83657	1.91745	1.99775
34	1.42565	1.50908	1.59204	1.67452	1.75649	1.83792	1.91879	1.99908
35	1.42705	1.51046	1.59342	1.67589	1.75785	1.83927	1.92013	2.00041
36	1.42844	1.51185	1.59480	1.67726	1.75921	1.84062	1.92148	2.00175
37	1.42984	1.51324	1.59617	1.67863	1.76057	1.84198	1.92282	2.00308
38	1.43123	1.51462	1.59755	1.68000	1.76193	1.84333	1.92416	2.00441
39	1.43262	1.51601	1.59893	1.68137	1.76329	1.84468	1.92550	2.00574
40	1.43402	1.51739	1.60031	1.68274	1.76465	1.84603	1.92685	2.00708
41	1.43541	1.51878	1.60169	1.68411	1.76601	1.84738	1.92819	2.00841
42	1.43680	1.52017	1.60307	1.68548	1.76737	1.84873	1.92953	2.00974
43	1.43820	1.52155	1.60444	1.68685	1.76873	1.85009	1.93087	2.01107
44	1.43959	1.52294	1.60582	1.68821	1.77010	1.85144	1.93221	2.01240
45	1.44098	1.52432	1.60720	1.68958	1.77146	1.85279	1.93355	2.01373
46	1.44237	1.52571	1.60857	1.69095	1.77282	1.85414	1.93490	2.01506
47	1.44377	1.52709	1.60995	1.69232	1.77418	1.85549	1.93624	2.01640
48	1.44516	1.52848	1.61133	1.69369	1.77553	1.85684	1.93758	2.01773
49	1.44655	1.52986	1.61271	1.69506	1.77689	1.85819	1.93892	2.01906
50	1.44794	1.53125	1.61408	1.69643	1.77825	1.85954	1.94026	2.02039
51	1.44934	1.53263	1.61546	1.69779	1.77961	1.86089	1.94160	2.02172
52	1.45073	1.53401	1.61683	1.69916	1.78097	1.86224	1.94294	2.02305
53	1.45212	1.53540	1.61821	1.70053	1.78233	1.86359	1.94428	2.02438
54	1.45351	1.53678	1.61959	1.70190	1.78369	1.86494	1.94562	2.02571
55	1.45490	1.53817	1.62096	1.70327	1.78505	1.86629	1.94696	2.02704
56	1.45629	1.53955	1.62234	1.70463	1.78641	1.86764	1.94830	2.02837
57	1.45769	1.54093	1.62371	1.70600	1.78777	1.86899	1.94964	2.02970
58	1.45908	1.54232	1.62509	1.70737	1.78912	1.87034	1.95098	2.03103
59	1.46047	1.54370	1.62647	1.70873	1.79048	1.87168	1.95232	2.03235
60	1.46186	1.54509	1.62784	1.71010	1.79184	1.87303	1.95366	2.03368

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	2.03368	2.11309	2.19186	2.26995	2.34736	2.42405	2.50000	2.57519
1	2.03501	2.11441	2.19316	2.27125	2.34864	2.42532	2.50126	2.57644
2	2.03634	2.11573	2.19447	2.27254	2.34993	2.42659	2.50252	2.57768
3	2.03767	2.11704	2.19578	2.27384	2.35121	2.42786	2.50378	2.57893
4	2.03900	2.11836	2.19708	2.27513	2.35249	2.42913	2.50504	2.58018
5	2.04032	2.11968	2.19839	2.27643	2.35378	2.43041	2.50630	2.58142
6	2.04165	2.12100	2.19970	2.27772	2.35506	2.43168	2.50755	2.58267
7	2.04298	2.12231	2.20100	2.27902	2.35634	2.43295	2.50881	2.58391
8	2.04431	2.12363	2.20231	2.28031	2.35763	2.43422	2.51007	2.58516
9	2.04563	2.12495	2.20361	2.28161	2.35891	2.43549	2.51133	2.58640
10	2.04696	2.12626	2.20492	2.28290	2.36019	2.43676	2.51259	2.58765
11	2.04829	2.12758	2.20622	2.28420	2.36147	2.43803	2.51384	2.58889
12	2.04962	2.12890	2.20753	2.28549	2.36275	2.43930	2.51510	2.59014
13	2.05094	2.13021	2.20883	2.28678	2.36404	2.44057	2.51636	2.59138
14	2.05227	2.13153	2.21014	2.28808	2.36532	2.44184	2.51761	2.59262
15	2.05359	2.13284	2.21144	2.28937	2.36660	2.44311	2.51887	2.59387
16	2.05492	2.13416	2.21275	2.29066	2.36788	2.44438	2.52013	2.59511
17	2.05625	2.13547	2.21405	2.29196	2.36916	2.44564	2.52138	2.59635
18	2.05757	2.13679	2.21536	2.29325	2.37044	2.44691	2.52264	2.59760
19	2.05890	2.13810	2.21666	2.29454	2.37172	2.44818	2.52389	2.59884
20	2.06022	2.13942	2.21796	2.29583	2.37300	2.44945	2.52515	2.60008
21	2.06155	2.14073	2.21927	2.29712	2.37428	2.45072	2.52640	2.60132
22	2.06287	2.14205	2.22057	2.29842	2.37556	2.45198	2.52766	2.60256
23	2.06420	2.14336	2.22187	2.29971	2.37684	2.45325	2.52891	2.60381
24	2.06552	2.14468	2.22318	2.30100	2.37812	2.45452	2.53017	2.60505
25	2.06685	2.14599	2.22448	2.30229	2.37940	2.45579	2.53142	2.60629
26	2.06817	2.14730	2.22578	2.30358	2.38068	2.45705	2.53268	2.60753
27	2.06950	2.14862	2.22708	2.30487	2.38196	2.45832	2.53393	2.60877
28	2.07082	2.14993	2.22839	2.30616	2.38324	2.45959	2.53519	2.61001
29	2.07214	2.15124	2.22969	2.30745	2.38452	2.46085	2.53644	2.61125
30	2.07347	2.15256	2.23099	2.30874	2.38579	2.46212	2.53769	2.61249
31	2.07479	2.15387	2.23229	2.31003	2.38707	2.46338	2.53894	2.61373
32	2.07611	2.15518	2.23359	2.31132	2.38835	2.46465	2.54020	2.61497
33	2.07744	2.15649	2.23489	2.31261	2.38963	2.46591	2.54145	2.61621
34	2.07876	2.15781	2.23619	2.31390	2.39091	2.46718	2.54270	2.61745
35	2.08008	2.15912	2.23749	2.31519	2.39218	2.46844	2.54396	2.61869
36	2.08140	2.16043	2.23880	2.31648	2.39346	2.46971	2.54521	2.61993
37	2.08273	2.16174	2.24010	2.31777	2.39474	2.47097	2.54646	2.62117
38	2.08405	2.16305	2.24140	2.31906	2.39601	2.47224	2.54771	2.62241
39	2.08537	2.16436	2.24270	2.32035	2.39729	2.47350	2.54896	2.62364
40	2.08669	2.16567	2.24400	2.32163	2.39857	2.47477	2.55021	2.62488
41	2.08801	2.16698	2.24530	2.32292	2.39984	2.47603	2.55146	2.62612
42	2.08934	2.16830	2.24660	2.32421	2.40112	2.47729	2.55271	2.62736
43	2.09066	2.16961	2.24789	2.32550	2.40239	2.47856	2.55397	2.62860
44	2.09198	2.17092	2.24919	2.32679	2.40367	2.47982	2.55522	2.62983
45	2.09330	2.17223	2.25049	2.32807	2.40494	2.48108	2.55647	2.63107
46	2.09462	2.17354	2.25179	2.32936	2.40622	2.48235	2.55772	2.63231
47	2.09594	2.17485	2.25309	2.33065	2.40749	2.48361	2.55896	2.63354
48	2.09726	2.17616	2.25439	2.33193	2.40877	2.48487	2.56021	2.63478
49	2.09858	2.17746	2.25569	2.33322	2.41004	2.48613	2.56146	2.63602
50	2.09990	2.17877	2.25698	2.33451	2.41132	2.48739	2.56271	2.63725
51	2.10122	2.18008	2.25828	2.33579	2.41259	2.48866	2.56396	2.63849
52	2.10254	2.18139	2.25958	2.33708	2.41386	2.48992	2.56521	2.63972
53	2.10386	2.18270	2.26088	2.33836	2.41514	2.49118	2.56646	2.64096
54	2.10518	2.18401	2.26217	2.33965	2.41641	2.49244	2.56771	2.64219
55	2.10650	2.18532	2.26347	2.34093	2.41769	2.49370	2.56895	2.64343
56	2.10782	2.18663	2.26477	2.34222	2.41896	2.49496	2.57020	2.64466
57	2.10914	2.18793	2.26606	2.34350	2.42023	2.49622	2.57145	2.64590
58	2.11045	2.18924	2.26736	2.34479	2.42150	2.49748	2.57270	2.64713
59	2.11177	2.19055	2.26866	2.34607	2.42278	2.49874	2.57394	2.64836
60	2.11309	2.19186	2.26995	2.34736	2.42405	2.50000	2.57519	2.64960

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	2.64960	2.72320	2.79596	2.86788	2.93893	3.00908	3.07831	3.14660
1	2.65083	2.72441	2.79717	2.86907	2.94010	3.01024	3.07945	3.14773
2	2.65206	2.72563	2.79838	2.87026	2.94128	3.01140	3.08060	3.14886
3	2.65330	2.72685	2.79958	2.87146	2.94246	3.01256	3.08174	3.14999
4	2.65453	2.72807	2.80079	2.87265	2.94363	3.01372	3.08289	3.15112
5	2.65576	2.72929	2.80199	2.87384	2.94481	3.01488	3.08403	3.15225
6	2.65699	2.73051	2.80319	2.87503	2.94598	3.01604	3.08518	3.15338
7	2.65822	2.73173	2.80440	2.87622	2.94716	3.01720	3.08632	3.15451
8	2.65946	2.73295	2.80560	2.87741	2.94833	3.01836	3.08747	3.15564
9	2.66069	2.73416	2.80681	2.87860	2.94951	3.01952	3.08861	3.15676
10	2.66192	2.73538	2.80801	2.87978	2.95068	3.02068	3.08976	3.15789
11	2.66315	2.73660	2.80921	2.88097	2.95185	3.02184	3.09090	3.15902
12	2.66438	2.73782	2.81042	2.88216	2.95303	3.02300	3.09204	3.16015
13	2.66561	2.73903	2.81162	2.88335	2.95420	3.02415	3.09318	3.16127
14	2.66684	2.74025	2.81282	2.88454	2.95538	3.02531	3.09433	3.16240
15	2.66807	2.74147	2.81402	2.88573	2.95655	3.02647	3.09547	3.16353
16	2.66930	2.74268	2.81523	2.88691	2.95772	3.02763	3.09661	3.16465
17	2.67053	2.74390	2.81643	2.88810	2.95889	3.02878	3.09775	3.16578
18	2.67176	2.74511	2.81763	2.88929	2.96007	3.02994	3.09890	3.16690
19	2.67299	2.74633	2.81883	2.89048	2.96124	3.03110	3.10004	3.16803
20	2.67422	2.74754	2.82003	2.89166	2.96241	3.03226	3.10118	3.16915
21	2.67545	2.74876	2.82123	2.89285	2.96358	3.03341	3.10232	3.17028
22	2.67668	2.74997	2.82243	2.89403	2.96475	3.03457	3.10346	3.17140
23	2.67791	2.75119	2.82364	2.89522	2.96592	3.03572	3.10460	3.17253
24	2.67913	2.75240	2.82484	2.89641	2.96709	3.03688	3.10574	3.17365
25	2.68036	2.75362	2.82604	2.89759	2.96827	3.03803	3.10688	3.17478
26	2.68159	2.75483	2.82723	2.89878	2.96944	3.03919	3.10802	3.17590
27	2.68282	2.75605	2.82843	2.89996	2.97061	3.04034	3.10916	3.17702
28	2.68404	2.75726	2.82963	2.90115	2.97178	3.04150	3.11030	3.17815
29	2.68527	2.75847	2.83083	2.90233	2.97294	3.04265	3.11143	3.17927
30	2.68650	2.75969	2.83203	2.90351	2.97411	3.04381	3.11257	3.18039
31	2.68772	2.76090	2.83323	2.90470	2.97528	3.04496	3.11371	3.18151
32	2.68895	2.76211	2.83443	2.90588	2.97645	3.04611	3.11485	3.18264
33	2.69018	2.76332	2.83563	2.90707	2.97762	3.04727	3.11599	3.18376
34	2.69140	2.76453	2.83682	2.90825	2.97879	3.04842	3.11712	3.18488
35	2.69263	2.76575	2.83802	2.90943	2.97996	3.04957	3.11826	3.18600
36	2.69385	2.76696	2.83922	2.91061	2.98112	3.05073	3.11940	3.18712
37	2.69508	2.76817	2.84042	2.91180	2.98229	3.05188	3.12053	3.18824
38	2.69630	2.76938	2.84161	2.91298	2.98346	3.05303	3.12167	3.18936
39	2.69753	2.77059	2.84281	2.91416	2.98463	3.05418	3.12281	3.19048
40	2.69875	2.77180	2.84401	2.91534	2.98579	3.05533	3.12394	3.19160
41	2.69998	2.77301	2.84520	2.91652	2.98696	3.05648	3.12508	3.19272
42	2.70120	2.77422	2.84640	2.91771	2.98813	3.05764	3.12621	3.19384
43	2.70243	2.77543	2.84759	2.91889	2.98929	3.05879	3.12735	3.19496
44	2.70365	2.77664	2.84879	2.92007	2.99046	3.05994	3.12848	3.19608
45	2.70487	2.77785	2.84998	2.92125	2.99162	3.06109	3.12962	3.19720
46	2.70610	2.77906	2.85118	2.92243	2.99279	3.06224	3.13075	3.19831
47	2.70732	2.78027	2.85237	2.92361	2.99395	3.06339	3.13189	3.19943
48	2.70854	2.78148	2.85357	2.92479	2.99512	3.06454	3.13302	3.20055
49	2.70976	2.78269	2.85476	2.92597	2.99628	3.06568	3.13415	3.20167
50	2.71099	2.78389	2.85596	2.92715	2.99745	3.06683	3.13529	3.20278
51	2.71221	2.78510	2.85715	2.92833	2.99861	3.06798	3.13642	3.20390
52	2.71343	2.78631	2.85834	2.92950	2.99977	3.06913	3.13755	3.20502
53	2.71465	2.78752	2.85954	2.93068	3.00094	3.07028	3.13868	3.20613
54	2.71587	2.78873	2.86073	2.93186	3.00210	3.07143	3.13982	3.20725
55	2.71709	2.78993	2.86192	2.93304	3.00326	3.07257	3.14095	3.20836
56	2.71831	2.79114	2.86311	2.93422	3.00443	3.07372	3.14208	3.20948
57	2.71953	2.79235	2.86431	2.93540	3.00559	3.07487	3.14321	3.21059
58	2.72076	2.79355	2.86550	2.93657	3.00675	3.07601	3.14434	3.21171
59	2.72198	2.79476	2.86669	2.93775	3.00791	3.07716	3.14547	3.21282
60	2.72320	2.79596	2.86788	2.93893	3.00908	3.07831	3.14660	3.21394

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	3.21394	3.28030	3.34565	3.40999	3.47329	3.53553	3.59670	3.65677
1	3.21505	3.28139	3.34673	3.41106	3.47434	3.53656	3.59771	3.65776
2	3.21617	3.28249	3.34781	3.41212	3.47538	3.53759	3.59872	3.65875
3	3.21728	3.28359	3.34889	3.41318	3.47643	3.53862	3.59973	3.65974
4	3.21839	3.28468	3.34997	3.41424	3.47747	3.53965	3.60074	3.66073
5	3.21951	3.28578	3.35105	3.41531	3.47852	3.54067	3.60175	3.66172
6	3.22062	3.28688	3.35213	3.41637	3.47956	3.54170	3.60276	3.66271
7	3.22173	3.28797	3.35321	3.41743	3.48061	3.54273	3.60376	3.66370
8	3.22284	3.28907	3.35429	3.41849	3.48165	3.54375	3.60477	3.66469
9	3.22395	3.29016	3.35537	3.41955	3.48270	3.54478	3.60578	3.66568
10	3.22507	3.29126	3.35645	3.42061	3.48374	3.54580	3.60679	3.66667
11	3.22618	3.29235	3.35753	3.42168	3.48478	3.54683	3.60779	3.66766
12	3.22729	3.29345	3.35860	3.42274	3.48583	3.54785	3.60880	3.66865
13	3.22840	3.29454	3.35968	3.42380	3.48687	3.54888	3.60981	3.66964
14	3.22951	3.29564	3.36076	3.42486	3.48791	3.54990	3.61081	3.67063
15	3.23062	3.29673	3.36183	3.42592	3.48895	3.55093	3.61182	3.67161
16	3.23173	3.29782	3.36291	3.42697	3.48999	3.55195	3.61283	3.67260
17	3.23284	3.29892	3.36399	3.42803	3.49104	3.55297	3.61383	3.67359
18	3.23395	3.30001	3.36506	3.42909	3.49208	3.55400	3.61484	3.67457
19	3.23506	3.30110	3.36614	3.43015	3.49312	3.55502	3.61584	3.67556
20	3.23617	3.30219	3.36721	3.43121	3.49416	3.55604	3.61684	3.67655
21	3.23728	3.30329	3.36829	3.43227	3.49520	3.55707	3.61785	3.67753
22	3.23838	3.30438	3.36936	3.43332	3.49624	3.55809	3.61885	3.67852
23	3.23949	3.30547	3.37044	3.43438	3.49728	3.55911	3.61986	3.67950
24	3.24060	3.30656	3.37151	3.43544	3.49832	3.56013	3.62086	3.68049
25	3.24171	3.30765	3.37259	3.43649	3.49936	3.56115	3.62186	3.68147
26	3.24281	3.30874	3.37366	3.43755	3.50039	3.56217	3.62286	3.68245
27	3.24392	3.30983	3.37473	3.43861	3.50143	3.56319	3.62387	3.68344
28	3.24503	3.31092	3.37581	3.43966	3.50247	3.56421	3.62487	3.68442
29	3.24613	3.31201	3.37688	3.44072	3.50351	3.56523	3.62587	3.68540
30	3.24724	3.31310	3.37795	3.44177	3.50455	3.56625	3.62687	3.68639
31	3.24835	3.31419	3.37902	3.44283	3.50558	3.56727	3.62787	3.68737
32	3.24945	3.31528	3.38010	3.44388	3.50662	3.56829	3.62887	3.68835
33	3.25056	3.31637	3.38117	3.44494	3.50766	3.56931	3.62987	3.68933
34	3.25166	3.31746	3.38224	3.44599	3.50869	3.57033	3.63087	3.69031
35	3.25277	3.31854	3.38331	3.44704	3.50973	3.57135	3.63187	3.69130
36	3.25387	3.31963	3.38438	3.44810	3.51077	3.57236	3.63287	3.69228
37	3.25498	3.32072	3.38545	3.44915	3.51180	3.57338	3.63387	3.69326
38	3.25608	3.32181	3.38652	3.45020	3.51284	3.57440	3.63487	3.69424
39	3.25718	3.32289	3.38759	3.45126	3.51387	3.57542	3.63587	3.69522
40	3.25829	3.32398	3.38866	3.45231	3.51491	3.57643	3.63687	3.69620
41	3.25939	3.32507	3.38973	3.45336	3.51594	3.57745	3.63787	3.69718
42	3.26049	3.32615	3.39080	3.45441	3.51697	3.57846	3.63886	3.69816
43	3.26159	3.32724	3.39187	3.45546	3.51801	3.57948	3.63986	3.69913
44	3.26270	3.32832	3.39294	3.45651	3.51904	3.58049	3.64086	3.70011
45	3.26380	3.32941	3.39400	3.45757	3.52007	3.58151	3.64186	3.70109
46	3.26490	3.33049	3.39507	3.45862	3.52111	3.58252	3.64285	3.70207
47	3.26600	3.33158	3.39614	3.45967	3.52214	3.58354	3.64385	3.70305
48	3.26710	3.33266	3.39721	3.46072	3.52317	3.58455	3.64484	3.70402
49	3.26820	3.33375	3.39827	3.46177	3.52420	3.58557	3.64584	3.70500
50	3.26930	3.33483	3.39934	3.46281	3.52523	3.58658	3.64683	3.70598
51	3.27040	3.33591	3.40041	3.46386	3.52627	3.58759	3.64783	3.70695
52	3.27150	3.33700	3.40147	3.46491	3.52730	3.58861	3.64882	3.70793
53	3.27260	3.33808	3.40254	3.46596	3.52833	3.58962	3.64982	3.70890
54	3.27370	3.33916	3.40360	3.46701	3.52936	3.59063	3.65081	3.70988
55	3.27480	3.34025	3.40467	3.46806	3.53039	3.59164	3.65181	3.71085
56	3.27590	3.34133	3.40573	3.46910	3.53142	3.59266	3.65280	3.71183
57	3.27700	3.34241	3.40680	3.47015	3.53245	3.59367	3.65379	3.71280
58	3.27810	3.34349	3.40786	3.47120	3.53348	3.59468	3.65478	3.71378
59	3.27920	3.34457	3.40893	3.47225	3.53451	3.59569	3.65578	3.71475
60	3.28030	3.34565	3.40999	3.47329	3.53553	3.59670	3.65677	3.71572

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 5-inch Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	3.71572	3.77355	3.83022	3.88573	3.94005	3.99318	4.04508	4.09576
1	3.71670	3.77450	3.83116	3.88665	3.94095	3.99405	4.04594	4.09659
2	3.71767	3.77546	3.83209	3.88756	3.94184	3.99493	4.04679	4.09743
3	3.71864	3.77641	3.83303	3.88847	3.94274	3.99580	4.04765	4.09826
4	3.71961	3.77736	3.83396	3.88939	3.94363	3.99668	4.04850	4.09909
5	3.72059	3.77831	3.83489	3.89030	3.94453	3.99755	4.04936	4.09993
6	3.72156	3.77927	3.83583	3.89122	3.94542	3.99842	4.05021	4.10076
7	3.72253	3.78022	3.83676	3.89213	3.94631	3.99930	4.05106	4.10159
8	3.72350	3.78117	3.83769	3.89304	3.94721	4.00017	4.05191	4.10242
9	3.72447	3.78212	3.83862	3.89395	3.94810	4.00104	4.05277	4.10325
10	3.72544	3.78307	3.83956	3.89487	3.94899	4.00191	4.05362	4.10409
11	3.72641	3.78402	3.84049	3.89578	3.94988	4.00279	4.05447	4.10492
12	3.72738	3.78498	3.84142	3.89669	3.95078	4.00366	4.05532	4.10575
13	3.72835	3.78593	3.84235	3.89760	3.95167	4.00453	4.05617	4.10658
14	3.72932	3.78688	3.84328	3.89851	3.95256	4.00540	4.05702	4.10741
15	3.73029	3.78783	3.84421	3.89942	3.95345	4.00627	4.05787	4.10823
16	3.73126	3.78877	3.84514	3.90033	3.95434	4.00714	4.05872	4.10906
17	3.73222	3.78972	3.84607	3.90124	3.95523	4.00801	4.05957	4.10989
18	3.73319	3.79067	3.84700	3.90215	3.95612	4.00888	4.06042	4.11072
19	3.73416	3.79162	3.84793	3.90306	3.95701	4.00975	4.06127	4.11155
20	3.73513	3.79257	3.84886	3.90397	3.95790	4.01062	4.06211	4.11238
21	3.73609	3.79352	3.84978	3.90488	3.95878	4.01148	4.06296	4.11320
22	3.73706	3.79446	3.85071	3.90579	3.95967	4.01235	4.06381	4.11403
23	3.73802	3.79541	3.85164	3.90669	3.96056	4.01322	4.06466	4.11486
24	3.73899	3.79636	3.85257	3.90760	3.96145	4.01409	4.06550	4.11568
25	3.73996	3.79730	3.85349	3.90851	3.96234	4.01495	4.06635	4.11651
26	3.74092	3.79825	3.85442	3.90942	3.96322	4.01582	4.06720	4.11733
27	3.74189	3.79919	3.85535	3.91032	3.96411	4.01669	4.06804	4.11816
28	3.74285	3.80014	3.85627	3.91123	3.96500	4.01755	4.06889	4.11898
29	3.74381	3.80109	3.85720	3.91214	3.96588	4.01842	4.06973	4.11981
30	3.74478	3.80203	3.85812	3.91304	3.96677	4.01928	4.07058	4.12063
31	3.74574	3.80297	3.85905	3.91395	3.96765	4.02015	4.07142	4.12145
32	3.74671	3.80392	3.85997	3.91485	3.96854	4.02101	4.07227	4.12228
33	3.74767	3.80486	3.86090	3.91576	3.96942	4.02188	4.07311	4.12310
34	3.74863	3.80581	3.86182	3.91666	3.97031	4.02274	4.07395	4.12392
35	3.74959	3.80675	3.86274	3.91756	3.97119	4.02361	4.07480	4.12475
36	3.75056	3.80769	3.86367	3.91847	3.97207	4.02447	4.07564	4.12557
37	3.75152	3.80863	3.86459	3.91937	3.97296	4.02533	4.07648	4.12639
38	3.75248	3.80958	3.86551	3.92027	3.97384	4.02619	4.07732	4.12721
39	3.75344	3.81052	3.86644	3.92118	3.97472	4.02706	4.07817	4.12803
40	3.75440	3.81146	3.86736	3.92208	3.97560	4.02792	4.07901	4.12885
41	3.75536	3.81240	3.86828	3.92298	3.97649	4.02878	4.07985	4.12967
42	3.75632	3.81334	3.86920	3.92388	3.97737	4.02964	4.08069	4.13049
43	3.75728	3.81428	3.87012	3.92478	3.97825	4.03050	4.08153	4.13131
44	3.75824	3.81522	3.87104	3.92568	3.97913	4.03136	4.08237	4.13213
45	3.75920	3.81616	3.87196	3.92658	3.98001	4.03222	4.08321	4.13295
46	3.76016	3.81710	3.87288	3.92748	3.98089	4.03308	4.08405	4.13377
47	3.76112	3.81804	3.87380	3.92839	3.98177	4.03394	4.08489	4.13459
48	3.76207	3.81898	3.87472	3.92928	3.98265	4.03480	4.08572	4.13540
49	3.76303	3.81992	3.87564	3.93018	3.98353	4.03566	4.08656	4.13622
50	3.76399	3.82086	3.87656	3.93108	3.98441	4.03652	4.08740	4.13704
51	3.76495	3.82179	3.87748	3.93198	3.98529	4.03738	4.08824	4.13785
52	3.76590	3.82273	3.87840	3.93288	3.98616	4.03823	4.08908	4.13867
53	3.76686	3.82367	3.87931	3.93378	3.98704	4.03909	4.08991	4.13949
54	3.76782	3.82461	3.88023	3.93468	3.98792	4.03995	4.09075	4.14030
55	3.76877	3.82554	3.88115	3.93557	3.98880	4.04081	4.09158	4.14112
56	3.76973	3.82648	3.88207	3.93647	3.98967	4.04166	4.09242	4.14193
57	3.77068	3.82742	3.88298	3.93737	3.99055	4.04252	4.09326	4.14275
58	3.77164	3.82835	3.88390	3.93826	3.99143	4.04337	4.09409	4.14356
59	3.77259	3.82929	3.88481	3.93916	3.99230	4.04423	4.09493	4.14437
60	3.77355	3.83022	3.88573	3.94005	3.99318	4.04508	4.09576	4.14519

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 10-inch Sine-Bar

Constants for Setting a 10-inch Sine-Bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	0.17452	0.34899	0.52336	0.69756	0.87156	1.04528	1.218693
1	0.002909	0.17743	0.35190	0.52626	0.70047	0.87446	1.04818	1.221581
2	0.005818	0.18034	0.35481	0.52917	0.70337	0.87735	1.05107	1.224468
3	0.008727	0.18325	0.35772	0.53207	0.70627	0.88025	1.05396	1.227355
4	0.011636	0.18616	0.36062	0.53498	0.70917	0.88315	1.05686	1.230241
5	0.014544	0.18907	0.36353	0.53788	0.71207	0.88605	1.05975	1.233128
6	0.017453	0.19197	0.36644	0.54079	0.71497	0.88894	1.06264	1.236015
7	0.020362	0.19488	0.36934	0.54369	0.71788	0.89184	1.06553	1.238901
8	0.023271	0.19779	0.37225	0.54660	0.72078	0.89474	1.06843	1.241788
9	0.026180	0.20070	0.37516	0.54950	0.72368	0.89763	1.07132	1.244674
10	0.029089	0.20361	0.37806	0.55241	0.72658	0.90053	1.07421	1.247560
11	0.031998	0.20652	0.38097	0.55531	0.72948	0.90343	1.07710	1.250446
12	0.034907	0.20942	0.38388	0.55822	0.73238	0.90633	1.07999	1.253332
13	0.037815	0.21233	0.38678	0.56112	0.73528	0.90922	1.08289	1.256218
14	0.040724	0.21524	0.38969	0.56402	0.73818	0.91212	1.08578	1.259104
15	0.043633	0.21815	0.39260	0.56693	0.74108	0.91502	1.08867	1.261990
16	0.046542	0.22106	0.39550	0.56983	0.74399	0.91791	1.09156	1.264875
17	0.049451	0.22397	0.39841	0.57274	0.74689	0.92081	1.09445	1.267761
18	0.052360	0.22687	0.40132	0.57564	0.74979	0.92371	1.09734	1.270646
19	0.055268	0.22978	0.40422	0.57854	0.75269	0.92660	1.10023	1.273531
20	0.058177	0.23269	0.40713	0.58145	0.75559	0.92950	1.10313	1.276417
21	0.061086	0.23560	0.41004	0.58435	0.75849	0.93239	1.10602	1.279302
22	0.063995	0.23851	0.41294	0.58726	0.76139	0.93529	1.10891	1.282187
23	0.066904	0.24141	0.41585	0.59016	0.76429	0.93819	1.11180	1.285071
24	0.069813	0.24432	0.41876	0.59306	0.76719	0.94108	1.11469	1.287956
25	0.072721	0.24723	0.42166	0.59597	0.77009	0.94398	1.11758	1.290841
26	0.075630	0.25014	0.42457	0.59887	0.77299	0.94687	1.12047	1.293725
27	0.078539	0.25305	0.42748	0.60177	0.77589	0.94977	1.12336	1.296609
28	0.081448	0.25595	0.43038	0.60468	0.77879	0.95267	1.12625	1.299494
29	0.084357	0.25886	0.43329	0.60758	0.78169	0.95556	1.12914	1.302378
30	0.087265	0.26177	0.43619	0.61049	0.78459	0.95846	1.13203	1.305262
31	0.090174	0.26468	0.43910	0.61339	0.78749	0.96135	1.13492	1.308146
32	0.093083	0.26759	0.44201	0.61629	0.79039	0.96425	1.13781	1.311030
33	0.095992	0.27049	0.44491	0.61920	0.79329	0.96714	1.14070	1.313913
34	0.098900	0.27340	0.44782	0.62210	0.79619	0.97004	1.14359	1.316797
35	0.101809	0.27631	0.45072	0.62500	0.79909	0.97293	1.14648	1.319681
36	0.104718	0.27922	0.45363	0.62791	0.80199	0.97583	1.14937	1.322564
37	0.107627	0.28212	0.45654	0.63081	0.80489	0.97872	1.15226	1.325447
38	0.110535	0.28503	0.45944	0.63371	0.80779	0.98162	1.15515	1.328330
39	0.113444	0.28794	0.46235	0.63661	0.81069	0.98451	1.15804	1.331213
40	0.116353	0.29085	0.46525	0.63952	0.81359	0.98741	1.16093	1.334096
41	0.119261	0.29375	0.46816	0.64242	0.81649	0.99030	1.16382	1.336979
42	0.122170	0.29666	0.47106	0.64532	0.81939	0.99320	1.16671	1.339862
43	0.125079	0.29957	0.47397	0.64823	0.82228	0.99609	1.16960	1.342744
44	0.127987	0.30248	0.47688	0.65113	0.82518	0.99899	1.17249	1.345627
45	0.130896	0.30539	0.47978	0.65403	0.82808	1.00188	1.17537	1.348509
46	0.133805	0.30829	0.48269	0.65693	0.83098	1.00477	1.17826	1.351392
47	0.136713	0.31120	0.48559	0.65984	0.83388	1.00767	1.18115	1.354274
48	0.139622	0.31411	0.48850	0.66274	0.83678	1.01056	1.18404	1.357156
49	0.142530	0.31702	0.49140	0.66564	0.83968	1.01346	1.18693	1.360038
50	0.145439	0.31992	0.49431	0.66854	0.84258	1.01635	1.18982	1.362919
51	0.148348	0.32283	0.49721	0.67145	0.84547	1.01924	1.19270	1.365801
52	0.151256	0.32574	0.50012	0.67435	0.84837	1.02214	1.19559	1.368683
53	0.154165	0.32864	0.50302	0.67725	0.85127	1.02503	1.19848	1.371564
54	0.157073	0.33155	0.50593	0.68015	0.85417	1.02793	1.20137	1.374446
55	0.159982	0.33446	0.50883	0.68306	0.85707	1.03082	1.20426	1.377327
56	0.162890	0.33737	0.51174	0.68596	0.85997	1.03371	1.20714	1.380208
57	0.165799	0.34027	0.51464	0.68886	0.86286	1.03661	1.21003	1.383089
58	0.168707	0.34318	0.51755	0.69176	0.86576	1.03950	1.21292	1.385970
59	0.171616	0.34609	0.52045	0.69466	0.86866	1.04239	1.21581	1.388850
60	0.174524	0.34899	0.52336	0.69756	0.87156	1.04528	1.21869	1.391731

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	1.391731	1.56434	1.73648	1.90809	2.07912	2.24951	2.41922	2.588191
1	1.394611	1.56722	1.73935	1.91095	2.08196	2.25234	2.42204	2.591000
2	1.397492	1.57009	1.74221	1.91380	2.08481	2.25518	2.42486	2.593810
3	1.400372	1.57296	1.74508	1.91666	2.08765	2.25801	2.42769	2.596619
4	1.403252	1.57584	1.74794	1.91951	2.09050	2.26085	2.43051	2.599428
5	1.406132	1.57871	1.75080	1.92237	2.09334	2.26368	2.43333	2.602237
6	1.409012	1.58158	1.75367	1.92522	2.09619	2.26651	2.43615	2.605045
7	1.411892	1.58445	1.75653	1.92807	2.09903	2.26935	2.43897	2.607853
8	1.414772	1.58732	1.75939	1.93093	2.10187	2.27218	2.44179	2.610662
9	1.417651	1.59020	1.76226	1.93378	2.10472	2.27501	2.44461	2.613469
10	1.420531	1.59307	1.76512	1.93664	2.10756	2.27784	2.44743	2.616277
11	1.423410	1.59594	1.76798	1.93949	2.11040	2.28068	2.45025	2.619085
12	1.426289	1.59881	1.77085	1.94234	2.11325	2.28351	2.45307	2.621892
13	1.429168	1.60168	1.77371	1.94520	2.11609	2.28634	2.45589	2.624699
14	1.432047	1.60455	1.77657	1.94805	2.11893	2.28917	2.45871	2.627506
15	1.434926	1.60743	1.77944	1.95090	2.12178	2.29200	2.46153	2.630312
16	1.437805	1.61030	1.78230	1.95376	2.12462	2.29484	2.46435	2.633119
17	1.440684	1.61317	1.78516	1.95661	2.12746	2.29767	2.46717	2.635925
18	1.443562	1.61604	1.78802	1.95946	2.13030	2.30050	2.46999	2.638731
19	1.446440	1.61891	1.79088	1.96231	2.13315	2.30333	2.47281	2.641536
20	1.449319	1.62178	1.79375	1.96517	2.13599	2.30616	2.47563	2.644342
21	1.452197	1.62465	1.79661	1.96802	2.13883	2.30899	2.47845	2.647147
22	1.455075	1.62752	1.79947	1.97087	2.14167	2.31182	2.48126	2.649952
23	1.457953	1.63039	1.80233	1.97372	2.14451	2.31465	2.48408	2.652757
24	1.460830	1.63326	1.80519	1.97657	2.14735	2.31748	2.48690	2.655561
25	1.463708	1.63613	1.80805	1.97942	2.15019	2.32031	2.48972	2.658366
26	1.466585	1.63900	1.81091	1.98228	2.15303	2.32314	2.49253	2.661170
27	1.469463	1.64187	1.81377	1.98513	2.15588	2.32597	2.49535	2.663974
28	1.472340	1.64474	1.81663	1.98798	2.15872	2.32880	2.49817	2.666777
29	1.475217	1.64761	1.81950	1.99083	2.16156	2.33163	2.50098	2.669581
30	1.478094	1.65048	1.82236	1.99368	2.16440	2.33445	2.50380	2.672384
31	1.480971	1.65334	1.82522	1.99653	2.16724	2.33728	2.50662	2.675187
32	1.483848	1.65621	1.82808	1.99938	2.17008	2.34011	2.50943	2.677990
33	1.486724	1.65908	1.83094	2.00223	2.17292	2.34294	2.51225	2.680792
34	1.489601	1.66195	1.83379	2.00508	2.17575	2.34577	2.51506	2.683594
35	1.492477	1.66482	1.83665	2.00793	2.17859	2.34859	2.51788	2.686396
36	1.495354	1.66769	1.83951	2.01078	2.18143	2.35142	2.52069	2.689198
37	1.498230	1.67056	1.84237	2.01363	2.18427	2.35425	2.52351	2.692000
38	1.501106	1.67342	1.84523	2.01648	2.18711	2.35708	2.52632	2.694801
39	1.503981	1.67629	1.84809	2.01933	2.18995	2.35990	2.52914	2.697602
40	1.506857	1.67916	1.85095	2.02218	2.19279	2.36273	2.53195	2.700403
41	1.509733	1.68203	1.85381	2.02502	2.19562	2.36556	2.53477	2.703204
42	1.512608	1.68489	1.85667	2.02787	2.19846	2.36838	2.53758	2.706005
43	1.515483	1.68776	1.85952	2.03072	2.20130	2.37121	2.54039	2.708805
44	1.518359	1.69063	1.86238	2.03357	2.20414	2.37403	2.54321	2.711605
45	1.521234	1.69350	1.86524	2.03642	2.20697	2.37686	2.54602	2.714405
46	1.524109	1.69636	1.86810	2.03927	2.20981	2.37968	2.54883	2.717204
47	1.526984	1.69923	1.87096	2.04211	2.21265	2.38251	2.55165	2.720004
48	1.529858	1.70210	1.87381	2.04496	2.21549	2.38533	2.55446	2.722803
49	1.532733	1.70496	1.87667	2.04781	2.21832	2.38816	2.55727	2.725601
50	1.535607	1.70783	1.87953	2.05065	2.22116	2.39098	2.56008	2.728400
51	1.538482	1.71069	1.88238	2.05350	2.22399	2.39381	2.56289	2.731199
52	1.541356	1.71356	1.88524	2.05635	2.22683	2.39663	2.56571	2.733997
53	1.544230	1.71643	1.88810	2.05920	2.22967	2.39946	2.56852	2.736794
54	1.547104	1.71929	1.89095	2.06204	2.23250	2.40228	2.57133	2.739592
55	1.549978	1.72216	1.89381	2.06489	2.23534	2.40510	2.57414	2.742390
56	1.552851	1.72502	1.89667	2.06773	2.23817	2.40793	2.57695	2.745187
57	1.555725	1.72789	1.89952	2.07058	2.24101	2.41075	2.57976	2.747984
58	1.558598	1.73075	1.90238	2.07343	2.24384	2.41357	2.58257	2.750781
59	1.561472	1.73362	1.90523	2.07627	2.24668	2.41640	2.58538	2.753577
60	1.564345	1.73648	1.90809	2.07912	2.24951	2.41922	2.58819	2.756374

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	2.756374	2.92372	3.09017	3.25568	3.42020	3.58368	3.74607	3.907311
1	2.759170	2.92650	3.09294	3.25843	3.42293	3.58640	3.74876	3.909989
2	2.761966	2.92928	3.09570	3.26118	3.42567	3.58911	3.75146	3.912666
3	2.764761	2.93206	3.09847	3.26393	3.42840	3.59183	3.75416	3.915343
4	2.767557	2.93484	3.10123	3.26668	3.43113	3.59454	3.75685	3.918020
5	2.770352	2.93762	3.10400	3.26943	3.43387	3.59725	3.75955	3.920696
6	2.773147	2.94040	3.10676	3.27218	3.43660	3.59997	3.76224	3.923371
7	2.775941	2.94318	3.10953	3.27493	3.43933	3.60268	3.76494	3.926047
8	2.778736	2.94596	3.11229	3.27768	3.44206	3.60540	3.76763	3.928722
9	2.781530	2.94874	3.11506	3.28042	3.44479	3.60811	3.77033	3.931397
10	2.784324	2.95152	3.11782	3.28317	3.44752	3.61082	3.77302	3.934071
11	2.787117	2.95430	3.12059	3.28592	3.45025	3.61353	3.77571	3.936745
12	2.789911	2.95708	3.12335	3.28867	3.45298	3.61625	3.77841	3.939419
13	2.792705	2.95986	3.12611	3.29141	3.45571	3.61896	3.78110	3.942093
14	2.795497	2.96264	3.12888	3.29416	3.45844	3.62167	3.78379	3.944766
15	2.798290	2.96542	3.13164	3.29691	3.46117	3.62438	3.78649	3.947439
16	2.801083	2.96819	3.13440	3.29965	3.46390	3.62709	3.78918	3.950111
17	2.803875	2.97097	3.13716	3.30240	3.46663	3.62980	3.79187	3.952783
18	2.806667	2.97375	3.13992	3.30514	3.46936	3.63251	3.79456	3.955455
19	2.809459	2.97653	3.14269	3.30789	3.47208	3.63522	3.79725	3.958127
20	2.812251	2.97930	3.14545	3.31063	3.47481	3.63793	3.79994	3.960798
21	2.815042	2.98208	3.14821	3.31338	3.47754	3.64064	3.80263	3.963469
22	2.817833	2.98486	3.15097	3.31612	3.48027	3.64335	3.80532	3.966139
23	2.820624	2.98763	3.15373	3.31887	3.48299	3.64606	3.80801	3.968809
24	2.823415	2.99041	3.15649	3.32161	3.48572	3.64877	3.81070	3.971479
25	2.826205	2.99318	3.15925	3.32435	3.48845	3.65148	3.81339	3.974148
26	2.828995	2.99596	3.16201	3.32710	3.49117	3.65418	3.81608	3.976817
27	2.831785	2.99873	3.16477	3.32984	3.49390	3.65689	3.81877	3.979486
28	2.834575	3.00151	3.16753	3.33258	3.49662	3.65960	3.82146	3.982155
29	2.837364	3.00428	3.17029	3.33533	3.49935	3.66231	3.82415	3.984823
30	2.840153	3.00706	3.17305	3.33807	3.50207	3.66501	3.82683	3.987491
31	2.842942	3.00983	3.17581	3.34081	3.50480	3.66772	3.82952	3.990158
32	2.845731	3.01261	3.17856	3.34355	3.50752	3.67042	3.83221	3.992825
33	2.848520	3.01538	3.18132	3.34629	3.51025	3.67313	3.83490	3.995492
34	2.851308	3.01815	3.18408	3.34903	3.51297	3.67584	3.83758	3.998159
35	2.854096	3.02093	3.18684	3.35178	3.51569	3.67854	3.84027	4.000825
36	2.856884	3.02370	3.18959	3.35452	3.51842	3.68125	3.84295	4.003490
37	2.859671	3.02647	3.19235	3.35726	3.52114	3.68395	3.84564	4.006156
38	2.862458	3.02924	3.19511	3.36000	3.52386	3.68665	3.84832	4.008821
39	2.865246	3.03202	3.19786	3.36274	3.52658	3.68936	3.85101	4.011486
40	2.868032	3.03479	3.20062	3.36547	3.52931	3.69206	3.85369	4.014150
41	2.870819	3.03756	3.20337	3.36821	3.53203	3.69476	3.85638	4.016814
42	2.873605	3.04033	3.20613	3.37095	3.53475	3.69747	3.85906	4.019478
43	2.876391	3.04310	3.20889	3.37369	3.53747	3.70017	3.86174	4.022141
44	2.879177	3.04587	3.21164	3.37643	3.54019	3.70287	3.86443	4.024804
45	2.881963	3.04864	3.21439	3.37917	3.54291	3.70557	3.86711	4.027467
46	2.884748	3.05141	3.21715	3.38190	3.54563	3.70828	3.86979	4.030129
47	2.887533	3.05418	3.21990	3.38464	3.54835	3.71098	3.87247	4.032791
48	2.890318	3.05695	3.22266	3.38738	3.55107	3.71368	3.87516	4.035453
49	2.893103	3.05972	3.22541	3.39012	3.55379	3.71638	3.87784	4.038115
50	2.895887	3.06249	3.22816	3.39285	3.55651	3.71908	3.88052	4.040775
51	2.898671	3.06526	3.23092	3.39559	3.55923	3.72178	3.88320	4.043436
52	2.901455	3.06803	3.23367	3.39832	3.56194	3.72448	3.88588	4.046096
53	2.904239	3.07080	3.23642	3.40106	3.56466	3.72718	3.88856	4.048756
54	2.907022	3.07357	3.23917	3.40380	3.56738	3.72988	3.89124	4.051416
55	2.909805	3.07633	3.24193	3.40653	3.57010	3.73258	3.89392	4.054075
56	2.912588	3.07910	3.24468	3.40927	3.57281	3.73528	3.89660	4.056734
57	2.915371	3.08187	3.24743	3.41200	3.57553	3.73797	3.89928	4.059393
58	2.918153	3.08464	3.25018	3.41473	3.57825	3.74067	3.90196	4.062051
59	2.920935	3.08740	3.25293	3.41747	3.58096	3.74337	3.90463	4.064709
60	2.923717	3.09017	3.25568	3.42020	3.58368	3.74607	3.90731	4.067367

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	4.067367	4.22618	4.38371	4.53991	4.69472	4.84810	5.00000	5.150381
1	4.070024	4.22882	4.38633	4.54250	4.69728	4.85064	5.00252	5.152874
2	4.072680	4.23145	4.38894	4.54509	4.69985	4.85318	5.00504	5.155367
3	4.075337	4.23409	4.39155	4.54768	4.70242	4.85573	5.00756	5.157859
4	4.077993	4.23673	4.39417	4.55027	4.70499	4.85827	5.01007	5.160351
5	4.080649	4.23936	4.39678	4.55286	4.70755	4.86081	5.01259	5.162843
6	4.083305	4.24199	4.39939	4.55545	4.71012	4.86335	5.01511	5.165333
7	4.085960	4.24463	4.40200	4.55804	4.71268	4.86590	5.01762	5.167824
8	4.088614	4.24726	4.40462	4.56063	4.71525	4.86844	5.02014	5.170314
9	4.091269	4.24990	4.40723	4.56322	4.71781	4.87098	5.02266	5.172804
10	4.093923	4.25253	4.40984	4.56580	4.72038	4.87352	5.02517	5.175293
11	4.096577	4.25516	4.41245	4.56839	4.72294	4.87606	5.02769	5.177782
12	4.099231	4.25779	4.41506	4.57098	4.72551	4.87860	5.03020	5.180270
13	4.101883	4.26043	4.41767	4.57357	4.72807	4.88114	5.03271	5.182758
14	4.104536	4.26306	4.42028	4.57615	4.73063	4.88367	5.03523	5.185246
15	4.107189	4.26569	4.42289	4.57874	4.73320	4.88621	5.03774	5.187733
16	4.109840	4.26832	4.42550	4.58133	4.73576	4.88875	5.04025	5.190219
17	4.112492	4.27095	4.42810	4.58391	4.73832	4.89129	5.04276	5.192706
18	4.115144	4.27358	4.43071	4.58650	4.74088	4.89382	5.04528	5.195191
19	4.117795	4.27621	4.43332	4.58908	4.74344	4.89636	5.04779	5.197677
20	4.120445	4.27884	4.43593	4.59166	4.74600	4.89890	5.05030	5.200161
21	4.123096	4.28147	4.43853	4.59425	4.74856	4.90143	5.05281	5.202646
22	4.125746	4.28410	4.44114	4.59683	4.75112	4.90397	5.05532	5.205130
23	4.128395	4.28672	4.44375	4.59942	4.75368	4.90650	5.05783	5.207613
24	4.131044	4.28935	4.44635	4.60200	4.75624	4.90904	5.06034	5.210096
25	4.133693	4.29198	4.44896	4.60458	4.75880	4.91157	5.06285	5.212579
26	4.136342	4.29461	4.45156	4.60716	4.76136	4.91411	5.06535	5.215061
27	4.138990	4.29723	4.45417	4.60974	4.76392	4.91664	5.06786	5.217543
28	4.141638	4.29986	4.45677	4.61233	4.76647	4.91917	5.07037	5.220025
29	4.144285	4.30249	4.45937	4.61491	4.76903	4.92170	5.07288	5.222506
30	4.146933	4.30511	4.46198	4.61749	4.77159	4.92424	5.07538	5.224986
31	4.149580	4.30774	4.46458	4.62007	4.77414	4.92677	5.07789	5.227466
32	4.152225	4.31036	4.46718	4.62265	4.77670	4.92930	5.08040	5.229945
33	4.154872	4.31299	4.46979	4.62523	4.77925	4.93183	5.08290	5.232424
34	4.157518	4.31561	4.47239	4.62780	4.78181	4.93436	5.08541	5.234903
35	4.160163	4.31823	4.47499	4.63038	4.78436	4.93689	5.08791	5.237381
36	4.162808	4.32086	4.47759	4.63296	4.78692	4.93942	5.09041	5.239859
37	4.165453	4.32348	4.48019	4.63554	4.78947	4.94195	5.09292	5.242337
38	4.168097	4.32610	4.48279	4.63812	4.79203	4.94448	5.09542	5.244813
39	4.170741	4.32873	4.48539	4.64069	4.79458	4.94700	5.09792	5.247290
40	4.173385	4.33135	4.48799	4.64327	4.79713	4.94953	5.10043	5.249766
41	4.176028	4.33397	4.49059	4.64584	4.79968	4.95206	5.10293	5.252242
42	4.178671	4.33659	4.49319	4.64842	4.80224	4.95459	5.10543	5.254717
43	4.181314	4.33921	4.49579	4.65100	4.80479	4.95711	5.10793	5.257191
44	4.183956	4.34183	4.49839	4.65357	4.80734	4.95964	5.11043	5.259665
45	4.186597	4.34445	4.50098	4.65615	4.80989	4.96217	5.11293	5.262139
46	4.189239	4.34707	4.50358	4.65872	4.81244	4.96469	5.11543	5.264613
47	4.191880	4.34969	4.50618	4.66129	4.81499	4.96722	5.11793	5.267086
48	4.194521	4.35231	4.50878	4.66387	4.81754	4.96974	5.12043	5.269558
49	4.197162	4.35493	4.51137	4.66644	4.82009	4.97226	5.12293	5.272030
50	4.199801	4.35755	4.51397	4.66901	4.82263	4.97479	5.12543	5.274502
51	4.202441	4.36017	4.51656	4.67158	4.82518	4.97731	5.12792	5.276973
52	4.205081	4.36278	4.51916	4.67416	4.82773	4.97983	5.13042	5.279443
53	4.207719	4.36540	4.52175	4.67673	4.83028	4.98236	5.13292	5.281914
54	4.210358	4.36802	4.52435	4.67930	4.83282	4.98488	5.13541	5.284383
55	4.212996	4.37063	4.52694	4.68187	4.83537	4.98740	5.13791	5.286853
56	4.215634	4.37325	4.52953	4.68444	4.83792	4.98992	5.14040	5.289321
57	4.218272	4.37587	4.53213	4.68701	4.84046	4.99244	5.14290	5.291790
58	4.220910	4.37848	4.53472	4.68958	4.84301	4.99496	5.14539	5.294258
59	4.223546	4.38110	4.53731	4.69215	4.84555	4.99748	5.14789	5.296726
60	4.226183	4.38371	4.53991	4.69472	4.84810	5.00000	5.15038	5.299193

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	5.299193	5.44639	5.59193	5.73576	5.87785	6.01815	6.15661	6.293204
1	5.301660	5.44883	5.59434	5.73815	5.88021	6.02047	6.15891	6.295465
2	5.304125	5.45127	5.59675	5.74053	5.88256	6.02280	6.16120	6.297724
3	5.306591	5.45371	5.59916	5.74291	5.88491	6.02512	6.16349	6.299984
4	5.309057	5.45614	5.60157	5.74529	5.88726	6.02744	6.16578	6.302242
5	5.311522	5.45858	5.60398	5.74767	5.88961	6.02976	6.16807	6.304501
6	5.313986	5.46102	5.60639	5.75005	5.89196	6.03208	6.17036	6.306758
7	5.316450	5.46346	5.60880	5.75243	5.89431	6.03440	6.17265	6.309015
8	5.318913	5.46589	5.61121	5.75481	5.89666	6.03672	6.17494	6.311272
9	5.321377	5.46833	5.61361	5.75719	5.89901	6.03904	6.17722	6.313529
10	5.323839	5.47076	5.61602	5.75957	5.90136	6.04136	6.17951	6.315784
11	5.326302	5.47320	5.61843	5.76195	5.90371	6.04367	6.18180	6.318039
12	5.328763	5.47563	5.62083	5.76432	5.90606	6.04599	6.18408	6.320293
13	5.331224	5.47807	5.62324	5.76670	5.90840	6.04831	6.18637	6.322547
14	5.333685	5.48050	5.62564	5.76908	5.91075	6.05062	6.18865	6.324800
15	5.336145	5.48293	5.62805	5.77145	5.91310	6.05294	6.19094	6.327054
16	5.338605	5.48536	5.63045	5.77383	5.91544	6.05526	6.19322	6.329306
17	5.341064	5.48780	5.63286	5.77620	5.91779	6.05757	6.19551	6.331558
18	5.343524	5.49023	5.63526	5.77858	5.92013	6.05988	6.19779	6.333809
19	5.345982	5.49266	5.63766	5.78095	5.92248	6.06220	6.20007	6.336060
20	5.348440	5.49509	5.64007	5.78332	5.92482	6.06451	6.20235	6.338310
21	5.350898	5.49752	5.64247	5.78570	5.92716	6.06682	6.20464	6.340559
22	5.353355	5.49995	5.64487	5.78807	5.92950	6.06914	6.20692	6.342808
23	5.355812	5.50238	5.64727	5.79044	5.93185	6.07145	6.20920	6.345057
24	5.358268	5.50481	5.64967	5.79281	5.93419	6.07376	6.21148	6.347305
25	5.360724	5.50724	5.65207	5.79518	5.93653	6.07607	6.21376	6.349553
26	5.363179	5.50966	5.65447	5.79755	5.93887	6.07838	6.21604	6.351800
27	5.365634	5.51209	5.65687	5.79992	5.94121	6.08069	6.21831	6.354046
28	5.368089	5.51452	5.65927	5.80229	5.94355	6.08300	6.22059	6.356292
29	5.370543	5.51694	5.66166	5.80466	5.94589	6.08531	6.22287	6.358538
30	5.372996	5.51937	5.66406	5.80703	5.94823	6.08761	6.22515	6.360782
31	5.375449	5.52180	5.66646	5.80940	5.95057	6.08992	6.22742	6.363027
32	5.377902	5.52422	5.66886	5.81177	5.95290	6.09223	6.22970	6.365270
33	5.380354	5.52664	5.67125	5.81413	5.95524	6.09454	6.23197	6.367514
34	5.382806	5.52907	5.67365	5.81650	5.95758	6.09684	6.23425	6.369756
35	5.385257	5.53149	5.67604	5.81886	5.95991	6.09915	6.23652	6.371998
36	5.387708	5.53392	5.67844	5.82123	5.96225	6.10145	6.23880	6.374240
37	5.390158	5.53634	5.68083	5.82359	5.96458	6.10376	6.24107	6.376481
38	5.392609	5.53876	5.68323	5.82596	5.96692	6.10606	6.24334	6.378722
39	5.395058	5.54118	5.68562	5.82832	5.96925	6.10836	6.24561	6.380962
40	5.397507	5.54360	5.68801	5.83069	5.97159	6.11067	6.24789	6.383201
41	5.399955	5.54602	5.69040	5.83305	5.97392	6.11297	6.25016	6.385440
42	5.402403	5.54844	5.69280	5.83541	5.97625	6.11527	6.25243	6.387679
43	5.404851	5.55086	5.69519	5.83777	5.97858	6.11757	6.25470	6.389916
44	5.407298	5.55328	5.69758	5.84014	5.98092	6.11987	6.25697	6.392153
45	5.409745	5.55570	5.69997	5.84250	5.98325	6.12217	6.25923	6.394390
46	5.412191	5.55812	5.70236	5.84486	5.98558	6.12447	6.26150	6.396626
47	5.414637	5.56054	5.70475	5.84722	5.98791	6.12677	6.26377	6.398862
48	5.417082	5.56296	5.70714	5.84958	5.99024	6.12907	6.26604	6.401097
49	5.419527	5.56537	5.70952	5.85194	5.99257	6.13137	6.26830	6.403332
50	5.421971	5.56779	5.71191	5.85429	5.99489	6.13367	6.27057	6.405566
51	5.424415	5.57021	5.71430	5.85665	5.99722	6.13596	6.27284	6.407799
52	5.426859	5.57262	5.71669	5.85901	5.99955	6.13826	6.27510	6.410032
53	5.429302	5.57504	5.71907	5.86137	6.00188	6.14056	6.27737	6.412265
54	5.431745	5.57745	5.72146	5.86372	6.00420	6.14285	6.27963	6.414497
55	5.434187	5.57987	5.72384	5.86608	6.00653	6.14515	6.28189	6.416728
56	5.436628	5.58228	5.72623	5.86844	6.00885	6.14744	6.28416	6.418959
57	5.439070	5.58469	5.72861	5.87079	6.01118	6.14974	6.28642	6.421189
58	5.441511	5.58711	5.73100	5.87315	6.01350	6.15203	6.28868	6.423419
59	5.443951	5.58952	5.73338	5.87550	6.01583	6.15432	6.29094	6.425648
60	5.446391	5.59193	5.73576	5.87785	6.01815	6.15661	6.29320	6.427876

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	6.427876	6.56059	6.69131	6.81998	6.94658	7.07107	7.19340	7.313537
1	6.430104	6.56279	6.69347	6.82211	6.94868	7.07312	7.19542	7.315521
2	6.432332	6.56498	6.69563	6.82424	6.95077	7.07518	7.19744	7.317503
3	6.434559	6.56717	6.69779	6.82636	6.95286	7.07724	7.19946	7.319486
4	6.436785	6.56937	6.69995	6.82849	6.95495	7.07929	7.20148	7.321467
5	6.439011	6.57156	6.70211	6.83061	6.95704	7.08134	7.20349	7.323449
6	6.441236	6.57375	6.70427	6.83274	6.95913	7.08340	7.20551	7.325429
7	6.443461	6.57594	6.70642	6.83486	6.96122	7.08545	7.20753	7.327409
8	6.445686	6.57814	6.70858	6.83698	6.96330	7.08750	7.20954	7.329389
9	6.447909	6.58033	6.71074	6.83911	6.96539	7.08956	7.21156	7.331367
10	6.450132	6.58252	6.71290	6.84123	6.96748	7.09161	7.21357	7.333345
11	6.452355	6.58471	6.71505	6.84335	6.96957	7.09366	7.21559	7.335322
12	6.454577	6.58689	6.71721	6.84547	6.97165	7.09571	7.21760	7.337299
13	6.456799	6.58908	6.71936	6.84759	6.97374	7.09776	7.21962	7.339275
14	6.459020	6.59127	6.72151	6.84971	6.97582	7.09981	7.22163	7.341250
15	6.461240	6.59346	6.72367	6.85183	6.97790	7.10185	7.22364	7.343225
16	6.463460	6.59564	6.72582	6.85395	6.97999	7.10390	7.22565	7.345200
17	6.465679	6.59783	6.72797	6.85607	6.98207	7.10595	7.22766	7.347173
18	6.467898	6.60002	6.73012	6.85818	6.98415	7.10800	7.22967	7.349146
19	6.470116	6.60220	6.73228	6.86030	6.98623	7.11004	7.23168	7.351119
20	6.472334	6.60439	6.73443	6.86242	6.98832	7.11209	7.23369	7.353090
21	6.474551	6.60657	6.73658	6.86453	6.99040	7.11413	7.23570	7.355061
22	6.476768	6.60875	6.73873	6.86665	6.99248	7.11617	7.23771	7.357032
23	6.478984	6.61094	6.74088	6.86876	6.99455	7.11822	7.23971	7.359002
24	6.481199	6.61312	6.74302	6.87088	6.99663	7.12026	7.24172	7.360971
25	6.483414	6.61530	6.74517	6.87299	6.99871	7.12230	7.24372	7.362940
26	6.485629	6.61748	6.74732	6.87510	7.00079	7.12434	7.24573	7.364908
27	6.487843	6.61966	6.74947	6.87721	7.00287	7.12639	7.24773	7.366875
28	6.490056	6.62184	6.75161	6.87932	7.00494	7.12843	7.24974	7.368842
29	6.492269	6.62402	6.75376	6.88144	7.00702	7.13047	7.25174	7.370808
30	6.494481	6.62620	6.75590	6.88355	7.00909	7.13250	7.25374	7.372774
31	6.496692	6.62838	6.75805	6.88566	7.01117	7.13454	7.25575	7.374738
32	6.498903	6.63056	6.76019	6.88776	7.01324	7.13658	7.25775	7.376703
33	6.501114	6.63273	6.76233	6.88987	7.01531	7.13862	7.25975	7.378666
34	6.503324	6.63491	6.76448	6.89198	7.01739	7.14066	7.26175	7.380629
35	6.505533	6.63709	6.76662	6.89409	7.01946	7.14269	7.26375	7.382592
36	6.507742	6.63926	6.76876	6.89620	7.02153	7.14473	7.26575	7.384553
37	6.509951	6.64144	6.77090	6.89830	7.02360	7.14676	7.26775	7.386515
38	6.512159	6.64361	6.77304	6.90041	7.02567	7.14880	7.26974	7.388475
39	6.514366	6.64579	6.77518	6.90251	7.02774	7.15083	7.27174	7.390435
40	6.516572	6.64796	6.77732	6.90462	7.02981	7.15286	7.27374	7.392395
41	6.518779	6.65013	6.77946	6.90672	7.03188	7.15490	7.27573	7.394353
42	6.520984	6.65230	6.78160	6.90882	7.03395	7.15693	7.27773	7.396311
43	6.523189	6.65448	6.78373	6.91093	7.03601	7.15896	7.27972	7.398269
44	6.525394	6.65665	6.78587	6.91303	7.03808	7.16099	7.28172	7.400225
45	6.527598	6.65882	6.78801	6.91513	7.04015	7.16302	7.28371	7.402182
46	6.529801	6.66099	6.79014	6.91723	7.04221	7.16505	7.28570	7.404137
47	6.532004	6.66316	6.79228	6.91933	7.04428	7.16708	7.28769	7.406092
48	6.534206	6.66532	6.79441	6.92143	7.04634	7.16911	7.28969	7.408046
49	6.536408	6.66749	6.79655	6.92353	7.04841	7.17113	7.29168	7.410000
50	6.538609	6.66966	6.79868	6.92563	7.05047	7.17316	7.29367	7.411952
51	6.540810	6.67183	6.80081	6.92773	7.05253	7.17519	7.29566	7.413905
52	6.543010	6.67399	6.80295	6.92982	7.05459	7.17721	7.29765	7.415857
53	6.545209	6.67616	6.80508	6.93192	7.05666	7.17924	7.29964	7.417808
54	6.547409	6.67833	6.80721	6.93402	7.05872	7.18126	7.30162	7.419759
55	6.549607	6.68049	6.80934	6.93611	7.06078	7.18329	7.30361	7.421709
56	6.551805	6.68265	6.81147	6.93821	7.06284	7.18531	7.30560	7.423658
57	6.554002	6.68482	6.81360	6.94030	7.06489	7.18733	7.30758	7.425606
58	6.556199	6.68698	6.81573	6.94240	7.06695	7.18936	7.30957	7.427554
59	6.558395	6.68914	6.81786	6.94449	7.06901	7.19138	7.31155	7.429502
60	6.560590	6.69131	6.81998	6.94658	7.07107	7.19340	7.31354	7.431448

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 10-inch Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	7.431448	7.54710	7.66044	7.77146	7.88011	7.98636	8.09017	8.191521
1	7.433394	7.54900	7.66231	7.77329	7.88190	7.98811	8.09188	8.193189
2	7.435340	7.55091	7.66418	7.77512	7.88369	7.98986	8.09359	8.194856
3	7.437285	7.55282	7.66605	7.77695	7.88548	7.99160	8.09530	8.196523
4	7.439229	7.55472	7.66792	7.77878	7.88727	7.99335	8.09700	8.198189
5	7.441173	7.55663	7.66979	7.78060	7.88905	7.99510	8.09871	8.199854
6	7.443115	7.55853	7.67165	7.78243	7.89084	7.99685	8.10042	8.201519
7	7.445058	7.56044	7.67352	7.78426	7.89263	7.99859	8.10212	8.203182
8	7.447000	7.56234	7.67538	7.78608	7.89441	8.00034	8.10383	8.204846
9	7.448941	7.56425	7.67725	7.78791	7.89620	8.00208	8.10553	8.206509
10	7.450881	7.56615	7.67911	7.78973	7.89798	8.00383	8.10723	8.208171
11	7.452821	7.56805	7.68097	7.79156	7.89977	8.00557	8.10894	8.209832
12	7.454760	7.56995	7.68284	7.79338	7.90155	8.00731	8.11064	8.211493
13	7.456699	7.57185	7.68470	7.79520	7.90333	8.00906	8.11234	8.213152
14	7.458637	7.57375	7.68656	7.79702	7.90511	8.01080	8.11404	8.214811
15	7.460574	7.57565	7.68842	7.79884	7.90690	8.01254	8.11574	8.216470
16	7.462511	7.57755	7.69028	7.80067	7.90868	8.01428	8.11744	8.218127
17	7.464447	7.57945	7.69214	7.80248	7.91046	8.01602	8.11914	8.219784
18	7.466382	7.58134	7.69400	7.80430	7.91224	8.01776	8.12084	8.221440
19	7.468317	7.58324	7.69585	7.80612	7.91401	8.01950	8.12253	8.223096
20	7.470251	7.58514	7.69771	7.80794	7.91579	8.02123	8.12423	8.224751
21	7.472184	7.58703	7.69957	7.80976	7.91757	8.02297	8.12592	8.226405
22	7.474117	7.58893	7.70142	7.81157	7.91935	8.02470	8.12762	8.228059
23	7.476050	7.59082	7.70328	7.81339	7.92112	8.02644	8.12931	8.229712
24	7.477981	7.59271	7.70513	7.81521	7.92290	8.02818	8.13101	8.231364
25	7.479912	7.59461	7.70699	7.81702	7.92467	8.02991	8.13270	8.233015
26	7.481843	7.59650	7.70884	7.81883	7.92645	8.03164	8.13439	8.234666
27	7.483772	7.59839	7.71069	7.82065	7.92822	8.03337	8.13608	8.236316
28	7.485701	7.60028	7.71254	7.82246	7.92999	8.03511	8.13778	8.237966
29	7.487629	7.60217	7.71440	7.82427	7.93176	8.03684	8.13947	8.239614
30	7.489557	7.60406	7.71625	7.82608	7.93353	8.03857	8.14116	8.241262
31	7.491485	7.60595	7.71810	7.82789	7.93530	8.04030	8.14284	8.242909
32	7.493411	7.60784	7.71994	7.82970	7.93707	8.04203	8.14453	8.244555
33	7.495337	7.60972	7.72179	7.83151	7.93884	8.04376	8.14622	8.246202
34	7.497262	7.61161	7.72364	7.83332	7.94061	8.04548	8.14791	8.247847
35	7.499187	7.61350	7.72549	7.83513	7.94238	8.04721	8.14959	8.249492
36	7.501111	7.61538	7.72734	7.83693	7.94415	8.04894	8.15128	8.251135
37	7.503034	7.61727	7.72918	7.83874	7.94591	8.05066	8.15296	8.252778
38	7.504957	7.61915	7.73103	7.84055	7.94768	8.05239	8.15465	8.254421
39	7.506879	7.62104	7.73287	7.84235	7.94944	8.05411	8.15633	8.256063
40	7.508801	7.62292	7.73472	7.84416	7.95121	8.05584	8.15801	8.257704
41	7.510721	7.62480	7.73656	7.84596	7.95297	8.05756	8.15969	8.259343
42	7.512641	7.62668	7.73840	7.84776	7.95474	8.05928	8.16138	8.260983
43	7.514561	7.62856	7.74024	7.84957	7.95650	8.06100	8.16306	8.262622
44	7.516480	7.63045	7.74209	7.85137	7.95826	8.06273	8.16474	8.264260
45	7.518398	7.63232	7.74393	7.85317	7.96002	8.06445	8.16642	8.265898
46	7.520316	7.63420	7.74577	7.85497	7.96178	8.06617	8.16809	8.267534
47	7.522233	7.63608	7.74761	7.85677	7.96354	8.06788	8.16977	8.269171
48	7.524149	7.63796	7.74944	7.85857	7.96530	8.06960	8.17145	8.270805
49	7.526065	7.63984	7.75128	7.86037	7.96706	8.07132	8.17313	8.272441
50	7.527980	7.64171	7.75312	7.86217	7.96882	8.07304	8.17480	8.274075
51	7.529894	7.64359	7.75496	7.86396	7.97057	8.07475	8.17648	8.275707
52	7.531808	7.64547	7.75679	7.86576	7.97233	8.07647	8.17815	8.277340
53	7.533722	7.64734	7.75863	7.86756	7.97408	8.07819	8.17982	8.278973
54	7.535634	7.64921	7.76046	7.86935	7.97584	8.07990	8.18150	8.280603
55	7.537546	7.65109	7.76230	7.87115	7.97759	8.08161	8.18317	8.282234
56	7.539457	7.65296	7.76413	7.87294	7.97935	8.08333	8.18484	8.283864
57	7.541368	7.65483	7.76596	7.87473	7.98110	8.08504	8.18651	8.285493
58	7.543278	7.65670	7.76780	7.87652	7.98285	8.08675	8.18818	8.287121
59	7.545187	7.65857	7.76963	7.87832	7.98460	8.08846	8.18985	8.288749
60	7.547096	7.66044	7.77146	7.88011	7.98636	8.09017	8.19152	8.290376

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 75-mm Sine-Bar

Constants for Setting a 75-mm Sine-Bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	1.308931	2.617462	3.925197	5.231736	6.536681	7.839635	9.140201
1	0.021817	1.330744	2.639266	3.946983	5.253499	6.558414	7.861332	9.161855
2	0.043633	1.352557	2.661068	3.968770	5.275262	6.580147	7.883028	9.183507
3	0.065450	1.374370	2.682871	3.990556	5.297024	6.601880	7.904724	9.205160
4	0.087266	1.396183	2.704674	4.012341	5.318786	6.623611	7.926418	9.226810
5	0.109083	1.417996	2.726476	4.034126	5.340548	6.645342	7.948112	9.248462
6	0.130900	1.439808	2.748278	4.055911	5.362309	6.667072	7.969805	9.270111
7	0.152716	1.461621	2.770080	4.077695	5.384069	6.688803	7.991498	9.291760
8	0.174533	1.483433	2.791882	4.099480	5.405829	6.710532	8.013190	9.313408
9	0.196349	1.505245	2.813683	4.121264	5.427589	6.732261	8.034882	9.335055
10	0.218166	1.527058	2.835484	4.143047	5.449348	6.753989	8.056572	9.356702
11	0.239982	1.548870	2.857285	4.164830	5.471107	6.775717	8.078262	9.378348
12	0.261799	1.570682	2.879086	4.186613	5.492865	6.797443	8.099952	9.399993
13	0.283615	1.592493	2.900886	4.208395	5.514623	6.819170	8.121640	9.421637
14	0.305432	1.614305	2.922686	4.230177	5.536380	6.840896	8.143329	9.443280
15	0.327248	1.636116	2.944486	4.251959	5.558137	6.862622	8.165016	9.464923
16	0.349065	1.657928	2.966286	4.273740	5.579894	6.884346	8.186703	9.486565
17	0.370881	1.679739	2.988085	4.295521	5.601649	6.906071	8.208388	9.508205
18	0.392697	1.701550	3.009884	4.317302	5.623405	6.927794	8.230074	9.529846
19	0.414514	1.723361	3.031683	4.339082	5.645160	6.949517	8.251758	9.551485
20	0.436330	1.745172	3.053482	4.360862	5.666914	6.971240	8.273442	9.573124
21	0.458146	1.766982	3.075280	4.382642	5.688668	6.992961	8.295125	9.594762
22	0.479962	1.788793	3.097079	4.404421	5.710422	7.014683	8.316808	9.616399
23	0.501778	1.810603	3.118877	4.426200	5.732174	7.036404	8.338489	9.638035
24	0.523595	1.832413	3.140674	4.447978	5.753927	7.058124	8.360170	9.659670
25	0.545411	1.854223	3.162472	4.469756	5.775679	7.079843	8.381850	9.681304
26	0.567227	1.876033	3.184269	4.491534	5.797431	7.101562	8.403530	9.702938
27	0.589043	1.897843	3.206065	4.513311	5.819182	7.123280	8.425209	9.724571
28	0.610859	1.919653	3.227862	4.535088	5.840933	7.144998	8.446887	9.746203
29	0.632674	1.941462	3.249658	4.556864	5.862682	7.166715	8.468564	9.767834
30	0.654490	1.963271	3.271454	4.578640	5.884432	7.188432	8.490241	9.789465
31	0.676306	1.985080	3.293250	4.600416	5.906182	7.210148	8.511917	9.811094
32	0.698122	2.006889	3.315045	4.622191	5.927930	7.231863	8.533592	9.832723
33	0.719937	2.028698	3.336840	4.643967	5.949678	7.253578	8.555267	9.854351
34	0.741753	2.050506	3.358635	4.665741	5.971426	7.275291	8.576941	9.875978
35	0.763568	2.072315	3.380430	4.687515	5.993173	7.297005	8.598615	9.897604
36	0.785384	2.094123	3.402224	4.709289	6.014919	7.318717	8.620286	9.919230
37	0.807199	2.115931	3.424018	4.731062	6.036666	7.340430	8.641958	9.940854
38	0.829015	2.137739	3.445812	4.752836	6.058411	7.362141	8.663629	9.962478
39	0.850830	2.159546	3.467606	4.774608	6.080156	7.383852	8.685300	9.984100
40	0.872645	2.181354	3.489399	4.796380	6.101901	7.405562	8.706968	10.005722
41	0.894460	2.203161	3.511191	4.818152	6.123645	7.427272	8.728638	10.027344
42	0.916275	2.224968	3.532984	4.839923	6.145388	7.448981	8.750305	10.048964
43	0.938090	2.246775	3.554776	4.861694	6.167131	7.470690	8.771973	10.070583
44	0.959905	2.268582	3.576568	4.883465	6.188873	7.492397	8.793639	10.092202
45	0.981720	2.290389	3.598360	4.905235	6.210616	7.514105	8.815305	10.113820
46	1.003534	2.312195	3.620151	4.927004	6.232358	7.535811	8.836970	10.135437
47	1.025349	2.334001	3.641942	4.948774	6.254098	7.557517	8.858634	10.157053
48	1.047164	2.355807	3.663733	4.970542	6.275839	7.579223	8.880298	10.178668
49	1.068978	2.377613	3.685523	4.992311	6.297578	7.600927	8.901960	10.200282
50	1.090792	2.399418	3.707313	5.014079	6.319318	7.622631	8.923623	10.221896
51	1.112607	2.421224	3.729103	5.035847	6.341056	7.644334	8.945284	10.243508
52	1.134421	2.443029	3.750892	5.057614	6.362795	7.666037	8.966945	10.265121
53	1.156235	2.464834	3.772682	5.079381	6.384532	7.687739	8.988604	10.286731
54	1.178049	2.486638	3.794471	5.101147	6.406270	7.709441	9.010263	10.308341
55	1.199863	2.508443	3.816259	5.122913	6.428006	7.731141	9.031921	10.329950
56	1.221676	2.530247	3.838048	5.144678	6.449742	7.752841	9.053579	10.351559
57	1.243490	2.552051	3.859835	5.166443	6.471478	7.774540	9.075235	10.373166
58	1.265304	2.573855	3.881623	5.188208	6.493213	7.796239	9.096891	10.394773
59	1.287117	2.595659	3.903410	5.209972	6.514947	7.817937	9.118546	10.416378
60	1.308931	2.617462	3.925197	5.231736	6.536681	7.839635	9.140201	10.437983

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	10.437983	11.732585	13.023614	14.310675	15.593377	16.871330	18.144142	19.411428
1	10.459586	11.754132	13.045098	14.332089	15.614717	16.892586	18.165310	19.432501
2	10.481191	11.775680	13.066583	14.353505	15.636055	16.913841	18.186478	19.453573
3	10.502792	11.797225	13.088064	14.374917	15.657392	16.935095	18.207642	19.474642
4	10.524393	11.818769	13.109546	14.396328	15.678726	16.956348	18.228804	19.495708
5	10.545993	11.840312	13.131025	14.417738	15.700060	16.977598	18.249966	19.516773
6	10.567594	11.861856	13.152505	14.439148	15.721394	16.998850	18.271128	19.537840
7	10.589191	11.883397	13.173983	14.460556	15.742724	17.020098	18.292286	19.558901
8	10.610788	11.904937	13.195459	14.481962	15.764053	17.041344	18.313442	19.579962
9	10.632385	11.926476	13.216935	14.503367	15.785382	17.062588	18.334597	19.601021
10	10.653982	11.948016	13.238410	14.524773	15.806710	17.083834	18.355751	19.622080
11	10.675576	11.969553	13.259884	14.546175	15.828035	17.105076	18.376904	19.643135
12	10.697170	11.991089	13.281356	14.567576	15.849360	17.126316	18.398054	19.664188
13	10.718762	12.012625	13.302827	14.588977	15.870683	17.147554	18.419203	19.685242
14	10.740356	12.034160	13.324298	14.610377	15.892006	17.168793	18.440351	19.706293
15	10.761947	12.055693	13.345766	14.631775	15.913326	17.190029	18.461498	19.727341
16	10.783537	12.077225	13.367234	14.653171	15.934645	17.211264	18.482641	19.748388
17	10.805127	12.098757	13.388701	14.674567	15.955963	17.232500	18.503786	19.769436
18	10.826715	12.120287	13.410167	14.695961	15.977280	17.253731	18.524927	19.790480
19	10.848303	12.141816	13.431631	14.717354	15.998594	17.274961	18.546066	19.811522
20	10.869889	12.163344	13.453094	14.738746	16.019909	17.296190	18.567204	19.832561
21	10.891476	12.184873	13.474557	14.760138	16.041222	17.317419	18.588343	19.853601
22	10.913060	12.206398	13.496017	14.781527	16.062532	17.338646	18.609476	19.874640
23	10.934645	12.227923	13.517477	14.802914	16.083841	17.359869	18.630610	19.895676
24	10.956227	12.249447	13.538936	14.824301	16.105150	17.381092	18.651741	19.916708
25	10.977810	12.270971	13.560394	14.845687	16.126457	17.402315	18.672873	19.937742
26	10.999391	12.292493	13.581850	14.867071	16.147762	17.423536	18.694002	19.958773
27	11.020970	12.314013	13.603306	14.888453	16.169067	17.444754	18.715128	19.979801
28	11.042550	12.335533	13.624760	14.909835	16.190369	17.465971	18.736254	20.000828
29	11.064129	12.357053	13.646214	14.931216	16.211672	17.487188	18.757380	20.021854
30	11.085706	12.378571	13.667665	14.952596	16.232971	17.508402	18.778502	20.042879
31	11.107283	12.400087	13.689116	14.973973	16.254271	17.529615	18.799622	20.063900
32	11.128859	12.421604	13.710566	14.995351	16.275568	17.550829	18.820742	20.084923
33	11.150434	12.443118	13.732014	15.016726	16.296864	17.572039	18.841860	20.105940
34	11.172007	12.464632	13.753461	15.038100	16.318159	17.593246	18.862974	20.126957
35	11.193579	12.486144	13.774906	15.059472	16.339451	17.614452	18.884089	20.147972
36	11.215152	12.507657	13.796352	15.080845	16.360744	17.635660	18.905203	20.168987
37	11.236722	12.529167	13.817796	15.102215	16.382034	17.656864	18.926313	20.189999
38	11.258291	12.550676	13.839238	15.123584	16.403322	17.678066	18.947424	20.211010
39	11.279860	12.572185	13.860679	15.144951	16.424610	17.699266	18.968531	20.232018
40	11.301429	12.593693	13.882120	15.166319	16.445898	17.720467	18.989639	20.253025
41	11.322996	12.615199	13.903559	15.187684	16.467182	17.741665	19.010742	20.274031
42	11.344562	12.636703	13.924996	15.209047	16.488466	17.762861	19.031847	20.295034
43	11.366126	12.658208	13.946433	15.230410	16.509747	17.784056	19.052948	20.316034
44	11.387691	12.679711	13.967869	15.251772	16.531029	17.805250	19.074049	20.337036
45	11.409254	12.701213	13.989303	15.273131	16.552307	17.826443	19.095146	20.358034
46	11.430816	12.722713	14.010736	15.294490	16.573586	17.847633	19.116243	20.379030
47	11.452378	12.744215	14.032168	15.315848	16.594864	17.868822	19.137339	20.400026
48	11.473938	12.765713	14.053599	15.337205	16.616138	17.890011	19.158432	20.421019
49	11.495498	12.787210	14.075028	15.358560	16.637411	17.911196	19.179523	20.442011
50	11.517056	12.808706	14.096457	15.379912	16.658684	17.932381	19.200615	20.462999
51	11.538613	12.830203	14.117885	15.401266	16.679955	17.953564	19.221704	20.483990
52	11.560169	12.851697	14.139310	15.422616	16.701225	17.974745	19.242790	20.504974
53	11.581725	12.873191	14.160735	15.443966	16.722492	17.995926	19.263876	20.525959
54	11.603279	12.894682	14.182158	15.465314	16.743759	18.017103	19.284960	20.546942
55	11.624833	12.916175	14.203582	15.486662	16.765024	18.038280	19.306042	20.567923
56	11.646385	12.937664	14.225002	15.508007	16.786289	18.059456	19.327124	20.588902
57	11.667936	12.959153	14.246422	15.529351	16.807550	18.080629	19.348202	20.609880
58	11.689487	12.980640	14.267840	15.550694	16.828812	18.101803	19.369278	20.630856
59	11.711037	13.002129	14.289259	15.572037	16.850071	18.122974	19.390356	20.651831
60	11.732585	13.023614	14.310675	15.593377	16.871330	18.144142	19.411428	20.672802

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	20.672802	21.927879	23.176275	24.417612	25.651512	26.877598	28.095495	29.304836
1	20.693773	21.948740	23.197023	24.438238	25.672010	26.897963	28.115723	29.324917
2	20.714741	21.969601	23.217768	24.458864	25.692509	26.918327	28.135946	29.344994
3	20.735708	21.990459	23.238512	24.479486	25.713003	26.938688	28.156168	29.365070
4	20.756676	22.011318	23.259256	24.500109	25.733500	26.959049	28.176390	29.385145
5	20.777639	22.032173	23.279995	24.520727	25.753990	26.979406	28.196606	29.405216
6	20.798599	22.053026	23.300734	24.541344	25.774479	26.999762	28.216822	29.425285
7	20.819559	22.073877	23.321468	24.561958	25.794964	27.020115	28.237034	29.445351
8	20.840517	22.094725	23.342203	24.582569	25.815449	27.040464	28.257242	29.465414
9	20.861473	22.115572	23.362934	24.603180	25.835932	27.060812	28.277451	29.485476
10	20.882429	22.136417	23.383665	24.623789	25.856411	27.081158	28.297655	29.505533
11	20.903381	22.157261	23.404392	24.644394	25.876888	27.101501	28.317858	29.525589
12	20.924334	22.178104	23.425121	24.665001	25.897367	27.121845	28.338060	29.545645
13	20.945284	22.198944	23.445845	24.685602	25.917839	27.142183	28.358259	29.565697
14	20.966230	22.219782	23.466566	24.706202	25.938311	27.162519	28.378454	29.585745
15	20.987177	22.240620	23.487286	24.726799	25.958780	27.182854	28.398647	29.605789
16	21.008120	22.261454	23.508003	24.747395	25.979246	27.203186	28.418839	29.625834
17	21.029062	22.282286	23.528721	24.767988	25.999712	27.223515	28.439026	29.645874
18	21.050003	22.303116	23.549435	24.788580	26.020174	27.243841	28.459211	29.665913
19	21.070944	22.323946	23.570148	24.809170	26.040636	27.264170	28.479397	29.685951
20	21.091881	22.344772	23.590858	24.829758	26.061094	27.284492	28.499578	29.705984
21	21.112816	22.365597	23.611567	24.850344	26.081551	27.304811	28.519756	29.726015
22	21.133749	22.386419	23.632273	24.870926	26.102003	27.325130	28.539934	29.746042
23	21.154680	22.407240	23.652975	24.891506	26.122456	27.345446	28.560106	29.766069
24	21.175610	22.428059	23.673677	24.912085	26.142904	27.365759	28.580278	29.786093
25	21.196537	22.448877	23.694378	24.932661	26.163351	27.386070	28.600447	29.806112
26	21.217463	22.469692	23.715076	24.953236	26.183796	27.406380	28.620613	29.826132
27	21.238390	22.490507	23.735775	24.973810	26.204241	27.426687	28.640779	29.846149
28	21.259312	22.511318	23.756468	24.994381	26.224680	27.446991	28.660942	29.866161
29	21.280233	22.532127	23.777161	25.014950	26.245119	27.467293	28.681101	29.886173
30	21.301151	22.552935	23.797850	25.035515	26.265554	27.487593	28.701258	29.906181
31	21.322069	22.573742	23.818539	25.056080	26.285988	27.507891	28.721413	29.926186
32	21.342983	22.594545	23.839224	25.076641	26.306419	27.528185	28.741564	29.946190
33	21.363897	22.615347	23.859907	25.097200	26.326849	27.548477	28.761715	29.966190
34	21.384811	22.636148	23.880592	25.117760	26.347279	27.568769	28.781864	29.986191
35	21.405720	22.656946	23.901272	25.138315	26.367702	27.589058	28.802008	30.006186
36	21.426628	22.677742	23.921949	25.158869	26.388124	27.609343	28.822151	30.026178
37	21.447535	22.698538	23.942625	25.179420	26.408545	27.629625	28.842291	30.046169
38	21.468439	22.719330	23.963299	25.199968	26.428963	27.649906	28.862427	30.066156
39	21.489342	22.740120	23.983971	25.220516	26.449379	27.670185	28.882563	30.086142
40	21.510242	22.760908	24.004641	25.241060	26.469791	27.690460	28.902695	30.106125
41	21.531141	22.781694	24.025309	25.261602	26.490204	27.710735	28.922825	30.126104
42	21.552040	22.802481	24.045977	25.282146	26.510614	27.731009	28.942955	30.146086
43	21.572935	22.823263	24.066639	25.302685	26.531021	27.751278	28.963079	30.166059
44	21.593828	22.844044	24.087301	25.323221	26.551426	27.771544	28.983202	30.186033
45	21.614721	22.864822	24.107960	25.343754	26.571829	27.791809	29.003323	30.206003
46	21.635611	22.885599	24.128618	25.364286	26.592228	27.812071	29.023441	30.225969
47	21.656498	22.906374	24.149273	25.384815	26.612627	27.832331	29.043556	30.245935
48	21.677385	22.927147	24.169928	25.405344	26.633022	27.852587	29.063669	30.265898
49	21.698271	22.947922	24.190580	25.425871	26.653418	27.872845	29.083782	30.285860
50	21.719154	22.968689	24.211229	25.446394	26.673809	27.893097	29.103889	30.305817
51	21.740034	22.989456	24.231876	25.466915	26.694197	27.913347	29.123995	30.325771
52	21.760912	23.010221	24.252522	25.487434	26.714584	27.933596	29.144098	30.345722
53	21.781790	23.030985	24.273165	25.507952	26.734968	27.953840	29.164198	30.365673
54	21.802664	23.051746	24.293806	25.528467	26.755350	27.974085	29.184296	30.385620
55	21.823538	23.072506	24.314445	25.548979	26.775730	27.994326	29.204391	30.405563
56	21.844410	23.093264	24.335083	25.569489	26.796108	28.014563	29.224485	30.425505
57	21.865280	23.114021	24.355721	25.590000	26.816484	28.034801	29.244577	30.445446
58	21.886148	23.134775	24.376352	25.610506	26.836859	28.055035	29.264666	30.465384
59	21.907015	23.155525	24.396984	25.631010	26.857229	28.075266	29.284752	30.485317
60	21.927879	23.176275	24.417612	25.651512	26.877598	28.095495	29.304836	30.505249

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	30.505249	31.696371	32.877838	34.049290	35.210369	36.360722	37.500000	38.627857
1	30.525177	31.716141	32.897446	34.068726	35.229630	36.379803	37.518894	38.646557
2	30.545105	31.735910	32.917049	34.088158	35.248886	36.398880	37.537781	38.665249
3	30.565027	31.755674	32.936649	34.107590	35.268143	36.417950	37.556667	38.683941
4	30.584951	31.775440	32.956249	34.127022	35.287395	36.437023	37.575550	38.702633
5	30.604870	31.795200	32.975845	34.146446	35.306644	36.456089	37.594429	38.721317
6	30.624786	31.814959	32.995438	34.165871	35.325893	36.475155	37.613308	38.740002
7	30.644699	31.834713	33.015030	34.185287	35.345135	36.494217	37.632179	38.758678
8	30.664610	31.854465	33.034618	34.204704	35.364376	36.513275	37.651051	38.777355
9	30.684519	31.874214	33.054203	34.224121	35.383614	36.532330	37.669914	38.796028
10	30.704424	31.893961	33.073784	34.243530	35.402847	36.551380	37.688778	38.814697
11	30.724327	31.913706	33.093361	34.262939	35.422077	36.570427	37.707638	38.833363
12	30.744228	31.933449	33.112942	34.282345	35.441311	36.589478	37.726498	38.852028
13	30.764128	31.953188	33.132515	34.301750	35.460533	36.608521	37.745350	38.870686
14	30.784021	31.972923	33.152084	34.321148	35.479755	36.627560	37.764202	38.889343
15	30.803915	31.992657	33.171654	34.340546	35.498978	36.646595	37.783051	38.907997
16	30.823805	32.012386	33.191219	34.359940	35.518192	36.665627	37.801895	38.926643
17	30.843693	32.032116	33.210781	34.379330	35.537407	36.684658	37.820736	38.945290
18	30.863577	32.051838	33.230339	34.398716	35.556614	36.703686	37.839573	38.963932
19	30.883461	32.071564	33.249897	34.418102	35.575825	36.722710	37.858410	38.982574
20	30.903341	32.091286	33.269451	34.437485	35.595028	36.741730	37.877239	39.001213
21	30.923218	32.111000	33.289001	34.456863	35.614231	36.760750	37.896069	39.019844
22	30.943092	32.130714	33.308552	34.476242	35.633430	36.779762	37.914894	39.038475
23	30.962963	32.150425	33.328094	34.495613	35.652622	36.798775	37.933716	39.057098
24	30.982832	32.170135	33.347637	34.514984	35.671818	36.817783	37.952534	39.075722
25	31.002699	32.189842	33.367180	34.534351	35.691006	36.836788	37.971348	39.094341
26	31.022562	32.209545	33.386715	34.553715	35.710190	36.855789	37.990162	39.112961
27	31.042427	32.229248	33.406250	34.573078	35.729378	36.874790	38.008972	39.131573
28	31.062284	32.248947	33.425781	34.592438	35.748558	36.893787	38.027775	39.150185
29	31.082140	32.268642	33.445313	34.611794	35.767735	36.912777	38.046577	39.168789
30	31.101994	32.288334	33.464836	34.631145	35.786907	36.931767	38.065376	39.187393
31	31.121845	32.308022	33.484360	34.650497	35.806080	36.950756	38.084175	39.205994
32	31.141693	32.327709	33.503880	34.669842	35.825249	36.969738	38.102966	39.224590
33	31.161537	32.347393	33.523396	34.689186	35.844414	36.988716	38.121758	39.243183
34	31.181383	32.367077	33.542912	34.708530	35.863575	37.007698	38.140545	39.261776
35	31.201223	32.386757	33.562424	34.727867	35.882736	37.026672	38.159328	39.280361
36	31.221060	32.406433	33.581932	34.747204	35.901890	37.045643	38.178108	39.298943
37	31.240896	32.426105	33.601440	34.766537	35.921043	37.064610	38.196884	39.317524
38	31.260727	32.445778	33.620941	34.785866	35.940193	37.083572	38.215656	39.336102
39	31.280558	32.465443	33.640442	34.805191	35.959339	37.102535	38.234428	39.354675
40	31.300385	32.485107	33.659939	34.824516	35.978485	37.121494	38.253193	39.373245
41	31.320208	32.504772	33.679432	34.843834	35.997623	37.140450	38.271957	39.391811
42	31.340033	32.524433	33.698925	34.863155	36.016766	37.159401	38.290722	39.410378
43	31.359852	32.544090	33.718414	34.882469	36.035900	37.178352	38.309479	39.428936
44	31.379667	32.563744	33.737900	34.901783	36.055031	37.197296	38.328232	39.447491
45	31.399481	32.583397	33.757385	34.921089	36.074158	37.216240	38.346981	39.466045
46	31.419292	32.603043	33.776863	34.940395	36.093285	37.235180	38.365730	39.484596
47	31.439100	32.622688	33.796341	34.959698	36.112408	37.254116	38.384476	39.503143
48	31.458906	32.642334	33.815815	34.978996	36.131527	37.273048	38.403214	39.521687
49	31.478712	32.661976	33.835289	34.998299	36.150642	37.291981	38.421955	39.540226
50	31.498512	32.681614	33.854759	35.017590	36.169758	37.310905	38.440689	39.558762
51	31.518309	32.701248	33.874222	35.036880	36.188866	37.329830	38.459419	39.577297
52	31.538105	32.720879	33.893688	35.056171	36.207973	37.348751	38.478149	39.595825
53	31.557898	32.740509	33.913147	35.075455	36.227077	37.367668	38.496872	39.614353
54	31.577686	32.760136	33.932602	35.094738	36.246178	37.386581	38.515594	39.632877
55	31.597473	32.779758	33.952057	35.114014	36.265278	37.405491	38.534313	39.651394
56	31.617258	32.799377	33.971508	35.133293	36.284370	37.424400	38.553028	39.669910
57	31.637041	32.819000	33.990959	35.152565	36.303467	37.443306	38.571743	39.688427
58	31.656820	32.838615	34.010406	35.171837	36.322556	37.462208	38.590450	39.706936
59	31.676598	32.858227	34.029850	35.191105	36.341640	37.481106	38.609154	39.725441
60	31.696371	32.877838	34.049290	35.210369	36.360722	37.500000	38.627857	39.743946

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	39.743946	40.847927	41.939468	43.018234	44.083897	45.136127	46.174610	47.199032
1	39.762444	40.866222	41.957554	43.036102	44.101543	45.153549	46.191803	47.215984
2	39.780941	40.884514	41.975636	43.053967	44.119186	45.170967	46.208988	47.232933
3	39.799435	40.902802	41.993713	43.071831	44.136826	45.188381	46.226170	47.249874
4	39.817924	40.921089	42.011787	43.089687	44.154465	45.205791	46.243347	47.266815
5	39.836411	40.939369	42.029858	43.107544	44.172096	45.223198	46.260521	47.283752
6	39.854893	40.957645	42.047924	43.125393	44.189728	45.240597	46.277691	47.300686
7	39.873371	40.975922	42.065987	43.143242	44.207352	45.257996	46.294857	47.317612
8	39.891853	40.994194	42.084053	43.161087	44.224976	45.275394	46.312023	47.334541
9	39.910324	41.012463	42.102108	43.178928	44.242596	45.292786	46.329182	47.351463
10	39.928795	41.030727	42.120159	43.196766	44.260208	45.310173	46.346336	47.368378
11	39.947262	41.048988	42.138210	43.214596	44.277821	45.327557	46.363483	47.385292
12	39.965721	41.067245	42.156254	43.232426	44.295425	45.344936	46.380630	47.402199
13	39.984180	41.085499	42.174297	43.250252	44.313030	45.362312	46.397774	47.419106
14	40.002636	41.103748	42.192337	43.268074	44.330627	45.379681	46.414913	47.436005
15	40.021091	41.121994	42.210369	43.285889	44.348225	45.397049	46.432049	47.452900
16	40.039539	41.140236	42.228401	43.303703	44.365818	45.414413	46.449177	47.469791
17	40.057983	41.158474	42.246429	43.321514	44.383404	45.431774	46.466305	47.486683
18	40.076427	41.176712	42.264454	43.339321	44.400990	45.449131	46.483429	47.503567
19	40.094864	41.194942	42.282475	43.357124	44.418568	45.466484	46.500546	47.520447
20	40.113300	41.213173	42.300491	43.374924	44.436146	45.483829	46.517662	47.537323
21	40.131733	41.231400	42.318504	43.392719	44.453720	45.501175	46.534771	47.554195
22	40.150162	41.249622	42.336514	43.410515	44.471287	45.518517	46.551880	47.571064
23	40.168591	41.267841	42.354527	43.428307	44.488857	45.535858	46.568989	47.587933
24	40.187012	41.286057	42.372528	43.446091	44.506420	45.553192	46.586086	47.604790
25	40.205429	41.304268	42.390526	43.463871	44.523975	45.570518	46.603180	47.621647
26	40.223846	41.322479	42.408524	43.481647	44.541531	45.587845	46.620274	47.638500
27	40.242256	41.340683	42.426514	43.499424	44.559082	45.605167	46.637360	47.655346
28	40.260666	41.358883	42.444504	43.517193	44.576630	45.622486	46.654446	47.672192
29	40.279072	41.377079	42.462486	43.534962	44.594170	45.639797	46.671524	47.689034
30	40.297470	41.395275	42.480469	43.552723	44.611710	45.657108	46.688599	47.705868
31	40.315868	41.413464	42.498447	43.570480	44.629246	45.674416	46.705669	47.722698
32	40.334263	41.431652	42.516418	43.588238	44.646778	45.691715	46.722736	47.739529
33	40.352654	41.449837	42.534389	43.605988	44.664303	45.709015	46.739803	47.756351
34	40.371044	41.468018	42.552357	43.623737	44.681828	45.726311	46.756863	47.773170
35	40.389427	41.486191	42.570320	43.641483	44.699348	45.743599	46.773918	47.789986
36	40.407806	41.504364	42.588280	43.659222	44.716866	45.760887	46.790970	47.806797
37	40.426186	41.522533	42.606236	43.676960	44.734379	45.778172	46.808018	47.823608
38	40.444565	41.540707	42.624191	43.694698	44.751892	45.795452	46.825066	47.840412
39	40.462936	41.558868	42.642143	43.712425	44.769394	45.812729	46.842106	47.857212
40	40.481300	41.577026	42.660088	43.730152	44.786896	45.829998	46.859142	47.874008
41	40.499664	41.595181	42.678028	43.747875	44.804394	45.847267	46.876175	47.890800
42	40.518024	41.613335	42.695965	43.765594	44.821888	45.864529	46.893200	47.907589
43	40.536385	41.631481	42.713902	43.783306	44.839378	45.881790	46.910225	47.924370
44	40.554737	41.649628	42.731831	43.801018	44.856865	45.899044	46.927246	47.941151
45	40.573086	41.667770	42.749760	43.818726	44.874348	45.916298	46.944260	47.957928
46	40.591434	41.685905	42.767681	43.836430	44.891823	45.933544	46.961273	47.974697
47	40.609776	41.704041	42.785603	43.854130	44.909298	45.950790	46.978283	47.991467
48	40.628117	41.722172	42.803516	43.871826	44.926769	45.968029	46.995285	48.008228
49	40.646454	41.740299	42.821430	43.889519	44.944237	45.985264	47.012287	48.024986
50	40.664783	41.758423	42.839340	43.907207	44.961700	46.002499	47.029282	48.041740
51	40.683113	41.776543	42.857246	43.924892	44.979160	46.019726	47.046276	48.058495
52	40.701439	41.794659	42.875145	43.942574	44.996616	46.036953	47.063263	48.075241
53	40.719769	41.812775	42.893047	43.960255	45.014072	46.054176	47.080250	48.091988
54	40.738087	41.830887	42.910942	43.977928	45.031521	46.071392	47.097233	48.108727
55	40.756401	41.848991	42.928833	43.995598	45.048965	46.088604	47.114208	48.125462
56	40.774715	41.867096	42.946720	44.013268	45.066402	46.105816	47.131180	48.142189
57	40.793022	41.885193	42.964603	44.030930	45.083839	46.123020	47.148148	48.158916
58	40.811329	41.903290	42.982483	44.048588	45.101273	46.140221	47.165115	48.175640
59	40.829632	41.921379	43.000362	44.066242	45.118702	46.157417	47.182076	48.192356
60	40.847927	41.939468	43.018234	44.083897	45.136127	46.174610	47.199032	48.209072

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	48.209072	49.204430	50.184795	51.149879	52.099380	53.033009	53.950485	54.851528
1	48.225780	49.220890	50.201008	51.165833	52.115070	53.048435	53.965637	54.866405
2	48.242489	49.237350	50.217213	51.181782	52.130756	53.063854	53.980785	54.881275
3	48.259190	49.253803	50.233414	51.197723	52.146439	53.079269	53.995930	54.896145
4	48.275887	49.270256	50.249615	51.213665	52.162117	53.094681	54.011070	54.911007
5	48.292583	49.286701	50.265808	51.229603	52.177792	53.110085	54.026203	54.925865
6	48.309273	49.303143	50.281998	51.245533	52.193459	53.125488	54.041332	54.940716
7	48.325958	49.319580	50.298180	51.261459	52.209126	53.140884	54.056458	54.955566
8	48.342644	49.336018	50.314365	51.277386	52.224789	53.156281	54.071583	54.970413
9	48.359322	49.352448	50.330544	51.293304	52.240444	53.171669	54.086697	54.985252
10	48.375996	49.368874	50.346714	51.309219	52.256096	53.187054	54.101810	55.000088
11	48.392662	49.385296	50.362881	51.325130	52.271744	53.202431	54.116917	55.014915
12	48.409328	49.401711	50.379047	51.341034	52.287384	53.217808	54.132019	55.029743
13	48.425991	49.418125	50.395206	51.356937	52.303024	53.233177	54.147118	55.044563
14	48.442646	49.434532	50.411362	51.372833	52.318657	53.248543	54.162209	55.059380
15	48.459301	49.450935	50.427513	51.388725	52.334286	53.263905	54.177299	55.074188
16	48.475948	49.467339	50.443657	51.404613	52.349911	53.279263	54.192383	55.088997
17	48.492592	49.483734	50.459801	51.420498	52.365532	53.294613	54.207462	55.103798
18	48.509235	49.500126	50.475941	51.436378	52.381145	53.309959	54.222538	55.118595
19	48.525871	49.516514	50.492073	51.452251	52.396759	53.325306	54.237606	55.133389
20	48.542503	49.532898	50.508202	51.468124	52.412365	53.340641	54.252674	55.148174
21	48.559132	49.549274	50.524326	51.483990	52.427967	53.355976	54.267735	55.162960
22	48.575756	49.565651	50.540447	51.499851	52.443565	53.371307	54.282791	55.177738
23	48.592381	49.582027	50.556568	51.515713	52.459164	53.386635	54.297844	55.192516
24	48.608994	49.598392	50.572681	51.531567	52.474754	53.401955	54.312893	55.207283
25	48.625607	49.614754	50.588791	51.547417	52.490337	53.417271	54.327934	55.222050
26	48.642216	49.631115	50.604893	51.563259	52.505920	53.432583	54.342972	55.236809
27	48.658817	49.647469	50.620995	51.579102	52.521496	53.447891	54.358006	55.251564
28	48.675419	49.663818	50.637089	51.594936	52.537067	53.463192	54.373035	55.266315
29	48.692013	49.680164	50.653179	51.610767	52.552631	53.478493	54.388058	55.281059
30	48.708603	49.696507	50.669266	51.626595	52.568195	53.493786	54.403080	55.295803
31	48.725193	49.712841	50.685349	51.642418	52.583755	53.509075	54.418095	55.310539
32	48.741776	49.729176	50.701427	51.658234	52.599308	53.524357	54.433105	55.325272
33	48.758354	49.745502	50.717503	51.674049	52.614857	53.539639	54.448109	55.339996
34	48.774929	49.761829	50.733570	51.689857	52.630402	53.554913	54.463112	55.354721
35	48.791500	49.778149	50.749638	51.705666	52.645943	53.570183	54.478107	55.369438
36	48.808067	49.794464	50.765697	51.721466	52.661480	53.585449	54.493099	55.384151
37	48.824627	49.810776	50.781754	51.737263	52.677010	53.600712	54.508087	55.398857
38	48.841190	49.827087	50.797810	51.753059	52.692539	53.615974	54.523075	55.413567
39	48.857746	49.843391	50.813858	51.768845	52.708065	53.631226	54.538052	55.428265
40	48.874294	49.859692	50.829903	51.784630	52.723583	53.646473	54.553024	55.442959
41	48.890839	49.875988	50.845943	51.800407	52.739094	53.661716	54.567993	55.457649
42	48.907383	49.892277	50.861977	51.816181	52.754604	53.676956	54.582958	55.472336
43	48.923920	49.908566	50.878010	51.831951	52.770111	53.692192	54.597919	55.487015
44	48.940453	49.924847	50.894035	51.847717	52.785610	53.707420	54.612873	55.501690
45	48.956982	49.941128	50.910057	51.863480	52.801105	53.722649	54.627823	55.516361
46	48.973507	49.957401	50.926075	51.879238	52.816597	53.737869	54.642769	55.531029
47	48.990028	49.973671	50.942089	51.894989	52.832085	53.753086	54.657711	55.545689
48	49.006546	49.989937	50.958099	51.910740	52.847565	53.768295	54.672649	55.560345
49	49.023060	50.006199	50.974102	51.926483	52.863045	53.783504	54.687580	55.574997
50	49.039566	50.022453	50.990105	51.942223	52.878517	53.798706	54.702507	55.589645
51	49.056072	50.038708	51.006100	51.957958	52.893986	53.813904	54.717430	55.604286
52	49.072571	50.054955	51.022091	51.973686	52.909451	53.829098	54.732349	55.618927
53	49.089073	50.071205	51.038086	51.989418	52.924915	53.844292	54.747265	55.633560
54	49.105564	50.087444	51.054070	52.005138	52.940369	53.859474	54.762173	55.648190
55	49.122051	50.103680	51.070045	52.020859	52.955822	53.874657	54.777077	55.662815
56	49.138535	50.119911	51.086021	52.036572	52.971268	53.889832	54.791977	55.677433
57	49.155014	50.136139	51.101994	52.052280	52.986710	53.905003	54.806873	55.692047
58	49.171490	50.152363	51.117958	52.067982	53.002148	53.920166	54.821762	55.706657
59	49.187962	50.168583	51.133919	52.083683	53.017582	53.935329	54.836647	55.721264
60	49.204430	50.184795	51.149879	52.099380	53.033009	53.950485	54.851528	55.735863

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 75-mm Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	55.735863	56.603218	57.453335	58.285950	59.100807	59.897663	60.676277	61.436405
1	55.750458	56.617531	57.467354	58.299675	59.114235	59.910789	60.689098	61.448914
2	55.765049	56.631836	57.481373	58.313396	59.127659	59.923912	60.701912	61.461422
3	55.779636	56.646137	57.495380	58.327114	59.141079	59.937031	60.714722	61.473923
4	55.794216	56.660431	57.509388	58.340828	59.154495	59.950142	60.727528	61.486416
5	55.808792	56.674725	57.523388	58.354534	59.167904	59.963249	60.740330	61.498905
6	55.823364	56.689011	57.537388	58.368237	59.181305	59.976349	60.753124	61.511391
7	55.837933	56.703293	57.551376	58.381935	59.194706	59.989445	60.765911	61.523869
8	55.852497	56.717571	57.565369	58.395630	59.208103	60.002541	60.778702	61.536346
9	55.867058	56.731842	57.579350	58.409317	59.221493	60.015625	60.791481	61.548817
10	55.881611	56.746113	57.593327	58.423000	59.234875	60.028706	60.804256	61.561279
11	55.896156	56.760372	57.607300	58.436676	59.248253	60.041782	60.817024	61.573738
12	55.910702	56.774632	57.621265	58.450348	59.261627	60.054855	60.829788	61.586193
13	55.925240	56.788883	57.635227	58.464016	59.274998	60.067921	60.842548	61.598640
14	55.939774	56.803131	57.649185	58.477680	59.288361	60.080982	60.855301	61.611084
15	55.954304	56.817375	57.663139	58.491337	59.301720	60.094036	60.868050	61.623520
16	55.968830	56.831612	57.677086	58.504990	59.315071	60.107086	60.880795	61.635956
17	55.983349	56.845848	57.691029	58.518639	59.328423	60.120132	60.893532	61.648380
18	55.997864	56.860077	57.704967	58.532280	59.341766	60.133175	60.906265	61.660805
19	56.012375	56.874298	57.718899	58.545918	59.355103	60.146210	60.918995	61.673222
20	56.026882	56.888519	57.732830	58.559551	59.368439	60.159241	60.931717	61.685631
21	56.041382	56.902733	57.746754	58.573181	59.381767	60.172264	60.944435	61.698040
22	56.055878	56.916943	57.760670	58.586803	59.395092	60.185284	60.957146	61.710442
23	56.070374	56.931152	57.774586	58.600426	59.408413	60.198303	60.969856	61.722839
24	56.084858	56.945351	57.788494	58.614037	59.421726	60.211311	60.982559	61.735229
25	56.099342	56.959545	57.802399	58.627647	59.435036	60.224319	60.995258	61.747616
26	56.113819	56.973736	57.816299	58.641251	59.448338	60.237316	61.007950	61.759995
27	56.128292	56.987923	57.830193	58.654846	59.461636	60.250313	61.020634	61.772369
28	56.142757	57.002102	57.844082	58.668442	59.474930	60.263302	61.033318	61.784740
29	56.157223	57.016277	57.857967	58.682030	59.488216	60.276287	61.045994	61.797108
30	56.171680	57.030449	57.871845	58.695614	59.501503	60.289265	61.058666	61.809464
31	56.186134	57.044613	57.885719	58.709190	59.514782	60.302238	61.071331	61.821819
32	56.200584	57.058777	57.899590	58.722763	59.528053	60.315208	61.083992	61.834167
33	56.215027	57.072933	57.913452	58.736332	59.541321	60.328175	61.096649	61.846512
34	56.229465	57.087086	57.927315	58.749897	59.554585	60.341133	61.109299	61.858852
35	56.243900	57.101231	57.941170	58.763454	59.567844	60.354088	61.121944	61.871185
36	56.258331	57.115372	57.955017	58.777008	59.581097	60.367035	61.134586	61.883511
37	56.272755	57.129509	57.968864	58.790558	59.594345	60.379978	61.147221	61.895836
38	56.287178	57.143646	57.982708	58.804104	59.607590	60.392921	61.159851	61.908157
39	56.301594	57.157772	57.996540	58.817642	59.620831	60.405853	61.172478	61.920467
40	56.316006	57.171894	58.010372	58.831177	59.634064	60.418781	61.185097	61.932774
41	56.330410	57.186012	58.024197	58.844707	59.647289	60.431705	61.197712	61.945076
42	56.344810	57.200127	58.038017	58.858231	59.660511	60.444622	61.210320	61.957375
43	56.359207	57.214233	58.051834	58.871750	59.673729	60.457535	61.222923	61.969666
44	56.373600	57.228336	58.065643	58.885262	59.686943	60.470444	61.235523	61.981953
45	56.387985	57.242435	58.079449	58.898769	59.700150	60.483345	61.248119	61.994232
46	56.402370	57.256531	58.093250	58.912273	59.713352	60.496243	61.260708	62.006508
47	56.416744	57.270618	58.107048	58.925774	59.726551	60.509136	61.273289	62.018780
48	56.431118	57.284702	58.120838	58.939266	59.739746	60.522022	61.285870	62.031044
49	56.445488	57.298782	58.134624	58.952755	59.752934	60.534904	61.298443	62.043304
50	56.459850	57.312855	58.148403	58.966240	59.766113	60.547783	61.311008	62.055557
51	56.474209	57.326927	58.162182	58.979721	59.779293	60.560654	61.323570	62.067806
52	56.488560	57.340988	58.175953	58.993195	59.792465	60.573521	61.336128	62.080051
53	56.502914	57.355053	58.189720	59.006664	59.805634	60.586388	61.348682	62.092293
54	56.517258	57.369106	58.203484	59.020130	59.818798	60.599243	61.361233	62.104527
55	56.531597	57.383156	58.217239	59.033588	59.831955	60.612095	61.373772	62.116756
56	56.545929	57.397202	58.230991	59.047043	59.845108	60.624943	61.386311	62.128979
57	56.560261	57.411243	58.244740	59.060490	59.858253	60.637783	61.398842	62.141197
58	56.574585	57.425278	58.258480	59.073936	59.871395	60.650620	61.411369	62.153408
59	56.588905	57.439308	58.272217	59.087376	59.884533	60.663448	61.423889	62.165615
60	56.603218	57.453335	58.285950	59.100807	59.897663	60.676277	61.436405	62.177818

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for 125-mm Sine-Bar

Constants for Setting a 125-mm Sine-Bar for 0° to 7°

Min.	0°	1°	2°	3°	4°	5°	6°	7°
0	0.000000	2.181551	4.362437	6.541995	8.719560	10.894468	13.066058	15.233668
1	0.036361	2.217906	4.398776	6.578306	8.755832	10.930691	13.102220	15.269758
2	0.072722	2.254261	4.435114	6.614616	8.792103	10.966911	13.138380	15.305845
3	0.109083	2.290616	4.471452	6.650926	8.828374	11.003133	13.174540	15.341933
4	0.145444	2.326972	4.507790	6.687235	8.864643	11.039351	13.210696	15.378017
5	0.181805	2.363326	4.544127	6.723544	8.900913	11.075570	13.246854	15.414103
6	0.218166	2.399680	4.580463	6.759851	8.937181	11.111787	13.283010	15.450185
7	0.254527	2.436035	4.616800	6.796159	8.973449	11.148005	13.319164	15.486267
8	0.290888	2.472389	4.653136	6.832467	9.009715	11.184219	13.355317	15.522346
9	0.327249	2.508742	4.689472	6.868773	9.045981	11.220434	13.391470	15.558426
10	0.363610	2.545096	4.725807	6.905079	9.082246	11.256648	13.427621	15.594503
11	0.399971	2.581449	4.762142	6.941384	9.118511	11.292861	13.463771	15.630580
12	0.436331	2.617803	4.798476	6.977688	9.154775	11.329072	13.499920	15.666655
13	0.472692	2.654155	4.834810	7.013992	9.191038	11.365284	13.536068	15.702728
14	0.509053	2.690508	4.871144	7.050296	9.227300	11.401493	13.572214	15.738800
15	0.545414	2.726861	4.907477	7.086599	9.263561	11.437702	13.608359	15.774872
16	0.581774	2.763213	4.943810	7.122901	9.299823	11.473911	13.644505	15.810942
17	0.618135	2.799565	4.980142	7.159203	9.336082	11.510118	13.680647	15.847010
18	0.654496	2.835917	5.016474	7.195503	9.372341	11.546324	13.716789	15.883077
19	0.690856	2.872268	5.052805	7.231804	9.408599	11.582529	13.752930	15.919142
20	0.727216	2.908620	5.089137	7.268104	9.444858	11.618733	13.789070	15.955207
21	0.763577	2.944971	5.125467	7.304403	9.481113	11.654936	13.825208	15.991269
22	0.799937	2.981322	5.161798	7.340702	9.517369	11.691138	13.861346	16.027330
23	0.836297	3.017672	5.198128	7.377000	9.553624	11.727339	13.897482	16.063391
24	0.872658	3.054022	5.234457	7.413297	9.589879	11.763539	13.933618	16.099451
25	0.909018	3.090372	5.270786	7.449594	9.626132	11.799738	13.969750	16.135508
26	0.945378	3.126722	5.307115	7.485890	9.662385	11.835937	14.005883	16.171564
27	0.981738	3.163072	5.343442	7.522185	9.698636	11.872133	14.042014	16.207619
28	1.018098	3.199421	5.379770	7.558480	9.734888	11.908330	14.078145	16.243671
29	1.054457	3.235770	5.416097	7.594774	9.771137	11.944525	14.114274	16.279724
30	1.090817	3.272119	5.452424	7.631068	9.807387	11.980720	14.150402	16.315775
31	1.127177	3.308467	5.488750	7.667360	9.843637	12.016913	14.186529	16.351824
32	1.163536	3.344815	5.525075	7.703653	9.879884	12.053104	14.222654	16.387871
33	1.199896	3.381163	5.561400	7.739944	9.916131	12.089296	14.258779	16.423918
34	1.236255	3.417511	5.597725	7.776235	9.952376	12.125485	14.294902	16.459963
35	1.272614	3.453858	5.634050	7.812525	9.988622	12.161675	14.331024	16.496008
36	1.308973	3.490205	5.670373	7.848815	10.024865	12.197863	14.367144	16.532049
37	1.345332	3.526552	5.706697	7.885104	10.061110	12.234050	14.403264	16.568090
38	1.381691	3.562898	5.743020	7.921392	10.097352	12.270235	14.439382	16.604130
39	1.418050	3.599244	5.779343	7.957680	10.133594	12.306421	14.475499	16.640167
40	1.454408	3.635590	5.815664	7.993967	10.169834	12.342604	14.511615	16.676205
41	1.490767	3.671935	5.851986	8.030253	10.206075	12.378787	14.547729	16.712240
42	1.527125	3.708281	5.888307	8.066539	10.242313	12.414968	14.583842	16.748274
43	1.563483	3.744626	5.924627	8.102823	10.278552	12.451150	14.619955	16.784306
44	1.599842	3.780970	5.960947	8.139108	10.314789	12.487329	14.656065	16.820337
45	1.636199	3.817314	5.997266	8.175391	10.351027	12.523508	14.692175	16.856367
46	1.672557	3.853658	6.033585	8.211674	10.387262	12.559686	14.728284	16.892395
47	1.708915	3.890002	6.069903	8.247956	10.423496	12.595862	14.764391	16.928421
48	1.745273	3.926345	6.106221	8.284238	10.459731	12.632038	14.800497	16.964447
49	1.781630	3.962688	6.142539	8.320518	10.495964	12.668212	14.836601	17.000471
50	1.817987	3.999031	6.178855	8.356798	10.532196	12.704386	14.872705	17.036493
51	1.854344	4.035373	6.215172	8.393078	10.568427	12.740557	14.908807	17.072514
52	1.890701	4.071715	6.251487	8.429357	10.604658	12.776729	14.944907	17.108534
53	1.927058	4.108056	6.287803	8.465634	10.640887	12.812899	14.981007	17.144552
54	1.963415	4.144397	6.324118	8.501912	10.677115	12.849068	15.017105	17.180569
55	1.999771	4.180738	6.360432	8.538188	10.713343	12.885235	15.053202	17.216583
56	2.036128	4.217079	6.396746	8.574464	10.749570	12.921402	15.089298	17.252598
57	2.072484	4.253419	6.433059	8.610739	10.785795	12.957567	15.125392	17.288610
58	2.108840	4.289759	6.469371	8.647013	10.822021	12.993732	15.161486	17.324621
59	2.145195	4.326098	6.505683	8.683287	10.858245	13.029896	15.197577	17.360630
60	2.181551	4.362437	6.541995	8.719560	10.894468	13.066058	15.233668	17.396639

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 8° to 15°

Min.	8°	9°	10°	11°	12°	13°	14°	15°
0	17.396639	19.554308	21.706022	23.851126	25.988962	28.118883	30.240238	32.352383
1	17.432644	19.590221	21.741831	23.886816	26.024527	28.154310	30.275517	32.387501
2	17.468651	19.626133	21.777637	23.922508	26.060091	28.189737	30.310795	32.422623
3	17.504654	19.662043	21.813440	23.958195	26.095652	28.225159	30.346069	32.457737
4	17.540655	19.697948	21.849243	23.993881	26.131210	28.260580	30.381340	32.492847
5	17.576654	19.733854	21.885042	24.029564	26.166765	28.295998	30.416611	32.527958
6	17.612656	19.769760	21.920843	24.065247	26.202322	28.331415	30.451878	32.563065
7	17.648653	19.805662	21.956638	24.100927	26.237873	28.366829	30.487143	32.598167
8	17.684649	19.841562	21.992432	24.136604	26.273422	28.402239	30.522404	32.633270
9	17.720642	19.877460	22.028225	24.172279	26.308969	28.437647	30.557661	32.668369
10	17.756636	19.913361	22.064018	24.207954	26.344517	28.473055	30.592920	32.703465
11	17.792627	19.949255	22.099806	24.243626	26.380060	28.508459	30.628174	32.738560
12	17.828617	19.985149	22.135593	24.279295	26.415600	28.543859	30.663424	32.773647
13	17.864605	20.021040	22.171377	24.314960	26.451138	28.579258	30.698671	32.808735
14	17.900593	20.056932	22.207163	24.350628	26.486675	28.614656	30.733919	32.843822
15	17.936579	20.092821	22.242945	24.386292	26.522209	28.650049	30.769163	32.878902
16	17.972561	20.128708	22.278723	24.421951	26.557741	28.685440	30.804403	32.913982
17	18.008545	20.164595	22.314503	24.457613	26.593273	28.720833	30.839643	32.949059
18	18.044525	20.200480	22.350279	24.493269	26.628799	28.756218	30.874878	32.984131
19	18.080505	20.236361	22.386051	24.528923	26.664324	28.791603	30.910110	33.019203
20	18.116482	20.272240	22.421824	24.564577	26.699846	28.826984	30.945341	33.054272
21	18.152460	20.308121	22.457596	24.600229	26.735369	28.862366	30.980570	33.089336
22	18.188435	20.343998	22.493362	24.635878	26.770887	28.897741	31.015795	33.124401
23	18.224407	20.379871	22.529129	24.671524	26.806402	28.933117	31.051016	33.159458
24	18.260378	20.415745	22.564894	24.707167	26.841915	28.968489	31.086235	33.194515
25	18.296350	20.451618	22.600657	24.742811	26.877428	29.003859	31.121454	33.229568
26	18.332317	20.487488	22.636417	24.778452	26.912937	29.039227	31.156670	33.264622
27	18.368284	20.523355	22.672176	24.814089	26.948444	29.074591	31.191881	33.299667
28	18.404249	20.559221	22.707932	24.849726	26.983950	29.109953	31.227089	33.334713
29	18.440214	20.595089	22.743689	24.885361	27.019453	29.145313	31.262299	33.369759
30	18.476177	20.630951	22.779442	24.920992	27.054953	29.180672	31.297501	33.404797
31	18.512136	20.666813	22.815191	24.956621	27.090450	29.216026	31.332703	33.439835
32	18.548098	20.702673	22.850943	24.992250	27.125948	29.251381	31.367903	33.474869
33	18.584055	20.738531	22.886690	25.027876	27.161440	29.286730	31.403099	33.509903
34	18.620010	20.774387	22.922434	25.063499	27.196930	29.322077	31.438292	33.544930
35	18.655964	20.810240	22.958178	25.099121	27.232418	29.357422	31.473482	33.579956
36	18.691919	20.846094	22.993919	25.134741	27.267906	29.392765	31.508671	33.614979
37	18.727871	20.881945	23.029659	25.170359	27.303391	29.428106	31.543856	33.649998
38	18.763819	20.917793	23.065397	25.205973	27.338871	29.463442	31.579039	33.685017
39	18.799767	20.953640	23.101131	25.241585	27.374352	29.498777	31.614218	33.720028
40	18.835714	20.989489	23.136868	25.277199	27.409830	29.534111	31.649397	33.755043
41	18.871660	21.025331	23.172598	25.312807	27.445303	29.569441	31.684572	33.790051
42	18.907602	21.061172	23.208326	25.348412	27.480776	29.604769	31.719744	33.825058
43	18.943544	21.097012	23.244055	25.384016	27.516245	29.640093	31.754913	33.860058
44	18.979486	21.132853	23.279781	25.419621	27.551716	29.675417	31.790081	33.895061
45	19.015425	21.168688	23.315506	25.455219	27.587179	29.710737	31.825245	33.930058
46	19.051361	21.204523	23.351227	25.490816	27.622643	29.746054	31.860405	33.965050
47	19.087297	21.240358	23.386948	25.526415	27.658106	29.781372	31.895565	34.000046
48	19.123230	21.276188	23.422665	25.562008	27.693563	29.816683	31.930721	34.035030
49	19.159163	21.312017	23.458382	25.597599	27.729019	29.851994	31.965874	34.070019
50	19.195091	21.347845	23.494095	25.633188	27.764473	29.887300	32.001022	34.105000
51	19.231022	21.383673	23.529808	25.668776	27.799925	29.922607	32.036175	34.139980
52	19.266949	21.419497	23.565517	25.704361	27.835375	29.957909	32.071320	34.174957
53	19.302874	21.455317	23.601225	25.739943	27.870821	29.993208	32.106461	34.209930
54	19.338799	21.491137	23.636930	25.775522	27.906265	30.028505	32.141598	34.244904
55	19.374722	21.526957	23.672636	25.811104	27.941708	30.063803	32.176739	34.279873
56	19.410643	21.562775	23.708338	25.846680	27.977148	30.099094	32.211872	34.314838
57	19.446560	21.598589	23.744038	25.882252	28.012585	30.134382	32.247002	34.349800
58	19.482477	21.634401	23.779734	25.917824	28.048019	30.169670	32.282131	34.384758
59	19.518394	21.670214	23.815432	25.953396	28.083452	30.204956	32.317257	34.419716
60	19.554308	21.706022	23.851126	25.988962	28.118883	30.240238	32.352383	34.454670

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 16° to 23°

Min.	16°	17°	18°	19°	20°	21°	22°	23°
0	34.454670	36.546463	38.627125	40.696022	42.752518	44.795994	46.825825	48.841393
1	34.489620	36.581234	38.661705	40.730396	42.786686	44.829937	46.859535	48.874859
2	34.524567	36.616001	38.696281	40.764774	42.820847	44.863876	46.893242	48.908325
3	34.559513	36.650764	38.730854	40.799145	42.855007	44.897816	46.926945	48.941784
4	34.594460	36.685532	38.765427	40.833515	42.889164	44.931751	46.960648	48.975243
5	34.629398	36.720287	38.799992	40.867878	42.923317	44.965679	46.994343	49.008694
6	34.664333	36.755043	38.834557	40.902241	42.957462	44.999603	47.028034	49.042141
7	34.699265	36.789795	38.869114	40.936596	42.991608	45.033524	47.061722	49.075584
8	34.734196	36.824543	38.903671	40.970951	43.025749	45.067440	47.095406	49.109024
9	34.769123	36.859287	38.938225	41.005299	43.059887	45.101353	47.129086	49.142460
10	34.804047	36.894032	38.972775	41.039646	43.094017	45.135262	47.162758	49.175888
11	34.838970	36.928768	39.007320	41.073990	43.128147	45.169170	47.196430	49.209316
12	34.873890	36.963509	39.041866	41.108334	43.162277	45.203075	47.230103	49.242741
13	34.908806	36.998241	39.076408	41.142670	43.196400	45.236973	47.263763	49.276161
14	34.943718	37.032970	39.110943	41.177002	43.230518	45.270866	47.297424	49.309574
15	34.978626	37.067699	39.145477	41.211330	43.264633	45.304756	47.331078	49.342983
16	35.013535	37.102421	39.180008	41.245659	43.298744	45.338642	47.364731	49.376389
17	35.048439	37.137142	39.214535	41.279980	43.332851	45.372524	47.398376	49.409790
18	35.083340	37.171860	39.249058	41.314297	43.366955	45.406403	47.432018	49.443188
19	35.118240	37.206577	39.283581	41.348618	43.401062	45.440281	47.465664	49.476585
20	35.153133	37.241287	39.318096	41.382931	43.435158	45.474152	47.499298	49.509972
21	35.188026	37.275993	39.352612	41.417236	43.469250	45.508018	47.532928	49.543358
22	35.222916	37.310699	39.387119	41.451542	43.503338	45.541885	47.566555	49.576740
23	35.257801	37.345402	39.421627	41.485844	43.537426	45.575745	47.600178	49.610115
24	35.292683	37.380100	39.456131	41.520142	43.571507	45.609600	47.633797	49.643486
25	35.327560	37.414795	39.490631	41.554436	43.605583	45.643452	47.667412	49.676853
26	35.362438	37.449486	39.525127	41.588726	43.639660	45.677299	47.701023	49.710220
27	35.397316	37.484180	39.559624	41.623016	43.673733	45.711147	47.734634	49.743580
28	35.432186	37.518864	39.594112	41.657303	43.707802	45.744987	47.768238	49.776936
29	35.467056	37.553547	39.628601	41.691582	43.741863	45.778824	47.801834	49.810287
30	35.501919	37.588226	39.663082	41.725857	43.775925	45.812656	47.835430	49.843636
31	35.536781	37.622902	39.697563	41.760132	43.809978	45.846481	47.869022	49.876976
32	35.571640	37.657574	39.732040	41.794403	43.844032	45.880306	47.902607	49.910316
33	35.606495	37.692245	39.766514	41.828667	43.878082	45.914127	47.936192	49.943649
34	35.641350	37.726913	39.800987	41.862934	43.912128	45.947948	47.969772	49.976982
35	35.676201	37.761578	39.835453	41.897194	43.946171	45.981762	48.003345	50.010311
36	35.711048	37.796238	39.869915	41.931450	43.980209	46.015572	48.036919	50.043633
37	35.745892	37.830894	39.904377	41.965698	44.014240	46.049377	48.070484	50.076950
38	35.780731	37.865547	39.938831	41.999947	44.048271	46.083176	48.104046	50.110260
39	35.815571	37.900200	39.973286	42.034195	44.082298	46.116974	48.137604	50.143570
40	35.850403	37.934845	40.007732	42.068436	44.116322	46.150768	48.171158	50.176876
41	35.885235	37.969490	40.042179	42.102673	44.150341	46.184559	48.204708	50.210175
42	35.920067	38.004135	40.076626	42.136909	44.184357	46.218346	48.238258	50.243473
43	35.954891	38.038773	40.111065	42.171139	44.218369	46.252129	48.271801	50.276768
44	35.989716	38.073406	40.145500	42.205368	44.252377	46.285908	48.305336	50.310055
45	36.024536	38.108040	40.179935	42.239590	44.286381	46.319679	48.338871	50.343338
46	36.059349	38.142666	40.214363	42.273811	44.320381	46.353451	48.372402	50.376617
47	36.094162	38.177292	40.248791	42.308025	44.354378	46.387218	48.405926	50.409893
48	36.128975	38.211914	40.283211	42.342239	44.388371	46.420979	48.439449	50.443161
49	36.163784	38.246536	40.317635	42.376453	44.422363	46.454742	48.472969	50.476433
50	36.198589	38.281151	40.352051	42.410660	44.456348	46.488495	48.506481	50.509693
51	36.233391	38.315762	40.386463	42.444859	44.490330	46.522247	48.539993	50.542950
52	36.268188	38.350368	40.420872	42.479057	44.524307	46.555992	48.573498	50.576206
53	36.302982	38.384975	40.455276	42.513252	44.558281	46.589733	48.606998	50.609455
54	36.337776	38.419579	40.489677	42.547443	44.592251	46.623474	48.640495	50.642700
55	36.372562	38.454178	40.524075	42.581631	44.626217	46.657207	48.673988	50.675938
56	36.407349	38.488773	40.558472	42.615814	44.660179	46.690937	48.707474	50.709175
57	36.442135	38.523369	40.592865	42.650002	44.694141	46.724670	48.740963	50.742413
58	36.476913	38.557957	40.627254	42.684177	44.728096	46.758392	48.774445	50.775639
59	36.511692	38.592545	40.661640	42.718349	44.762047	46.792110	48.807919	50.808861
60	36.546463	38.627125	40.696022	42.752518	44.795994	46.825825	48.841393	50.842083

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 24° to 31°

Min.	24°	25°	26°	27°	28°	29°	30°	31°
0	50.842083	52.827286	54.796394	56.748814	58.683949	60.601204	62.500000	64.379761
1	50.875298	52.860237	54.829075	56.781208	58.716049	60.633003	62.531487	64.410927
2	50.908508	52.893181	54.861748	56.813599	58.748146	60.664799	62.562969	64.442085
3	50.941711	52.926125	54.894417	56.845985	58.780239	60.696587	62.594444	64.473236
4	50.974918	52.959068	54.927082	56.878368	58.812328	60.728374	62.625919	64.504387
5	51.008118	52.992001	54.959743	56.910744	58.844410	60.760151	62.657383	64.535530
6	51.041309	53.024929	54.992397	56.943115	58.876488	60.791924	62.688843	64.566666
7	51.074497	53.057854	55.025047	56.975483	58.908558	60.823692	62.720299	64.597801
8	51.107681	53.090775	55.057693	57.007843	58.940628	60.855457	62.751747	64.628929
9	51.140865	53.123692	55.090336	57.040199	58.972687	60.887215	62.783192	64.660049
10	51.174038	53.156601	55.122971	57.072552	59.004745	60.918968	62.814632	64.691162
11	51.207211	53.189507	55.155605	57.104897	59.036797	60.950714	62.846066	64.722275
12	51.240383	53.222416	55.188236	57.137245	59.068848	60.982460	62.877495	64.753380
13	51.273544	53.255314	55.220856	57.169582	59.100891	61.014198	62.908920	64.784477
14	51.306705	53.288204	55.253475	57.201912	59.132927	61.045929	62.940338	64.815575
15	51.339859	53.321095	55.286087	57.234241	59.164959	61.077656	62.971748	64.846657
16	51.373009	53.353977	55.318695	57.266563	59.196987	61.109379	63.003155	64.877739
17	51.406155	53.386856	55.351299	57.298882	59.229008	61.141094	63.034557	64.908821
18	51.439293	53.419731	55.383900	57.331196	59.261024	61.172806	63.065952	64.939888
19	51.472435	53.452606	55.416496	57.363506	59.293041	61.204517	63.097347	64.970955
20	51.505569	53.485474	55.449085	57.395809	59.325050	61.236217	63.128735	65.002022
21	51.538696	53.518333	55.481670	57.428108	59.357052	61.267914	63.160114	65.033073
22	51.571819	53.551193	55.514252	57.460400	59.389050	61.299603	63.191486	65.064125
23	51.604939	53.584045	55.546825	57.492691	59.421040	61.331291	63.222858	65.095169
24	51.638054	53.616894	55.579399	57.524975	59.453026	61.362968	63.254223	65.126205
25	51.671165	53.649734	55.611965	57.557251	59.485008	61.394646	63.285580	65.157234
26	51.704273	53.682575	55.644527	57.589527	59.516987	61.426315	63.316933	65.188263
27	51.737377	53.715412	55.677086	57.621799	59.548962	61.457985	63.348286	65.219292
28	51.770473	53.748241	55.709637	57.654064	59.580929	61.489643	63.379627	65.250305
29	51.803566	53.781067	55.742184	57.686325	59.612888	61.521297	63.410965	65.281319
30	51.836658	53.813889	55.774727	57.718578	59.644848	61.552948	63.442295	65.312325
31	51.869740	53.846706	55.807266	57.750828	59.676800	61.584591	63.473625	65.343323
32	51.902821	53.879517	55.839798	57.783073	59.708744	61.616230	63.504944	65.374313
33	51.935898	53.912323	55.872326	57.815311	59.740688	61.647861	63.536259	65.405304
34	51.968971	53.945129	55.904854	57.847549	59.772625	61.679493	63.567574	65.436295
35	52.002037	53.977928	55.937374	57.879780	59.804558	61.711117	63.598881	65.467270
36	52.035103	54.010719	55.969887	57.912006	59.836483	61.742737	63.630180	65.498238
37	52.068161	54.043510	56.002399	57.944225	59.868404	61.774349	63.661472	65.529205
38	52.101212	54.076294	56.034901	57.976444	59.900322	61.805954	63.692764	65.560165
39	52.134262	54.109074	56.067402	58.008652	59.932232	61.837559	63.724045	65.591125
40	52.167309	54.141850	56.099899	58.040859	59.964138	61.869156	63.755325	65.622070
41	52.200348	54.174618	56.132389	58.073059	59.996040	61.900745	63.786598	65.653015
42	52.233387	54.207390	56.164879	58.105259	60.027939	61.932335	63.817867	65.683960
43	52.266418	54.240150	56.197357	58.137451	60.059830	61.963917	63.849129	65.714890
44	52.299446	54.272907	56.229836	58.169636	60.091717	61.995495	63.880386	65.745819
45	52.332470	54.305660	56.262306	58.201817	60.123596	62.027065	63.911636	65.776741
46	52.365486	54.338406	56.294773	58.233994	60.155472	62.058632	63.942883	65.807655
47	52.398502	54.371147	56.327236	58.266163	60.187344	62.090191	63.974125	65.838570
48	52.431511	54.403889	56.359692	58.298328	60.219208	62.121746	64.005356	65.869476
49	52.464520	54.436626	56.392147	58.330494	60.251072	62.153297	64.036591	65.900375
50	52.497520	54.469353	56.424595	58.362652	60.282928	62.184845	64.067818	65.931274
51	52.530514	54.502079	56.457039	58.394802	60.314777	62.216381	64.099037	65.962158
52	52.563507	54.534798	56.489479	58.426949	60.346622	62.247917	64.130249	65.993042
53	52.596493	54.567513	56.521912	58.459091	60.378464	62.279446	64.161453	66.023918
54	52.629478	54.600224	56.554340	58.491226	60.410297	62.310966	64.192657	66.054794
55	52.662457	54.632931	56.586761	58.523357	60.442127	62.342487	64.223854	66.085655
56	52.695431	54.665630	56.619183	58.555485	60.473953	62.374001	64.255043	66.116516
57	52.728401	54.698334	56.651600	58.587612	60.505775	62.405510	64.286232	66.147377
58	52.761368	54.731026	56.684010	58.619728	60.537590	62.437012	64.317413	66.178230
59	52.794327	54.763710	56.716415	58.651840	60.569401	62.468510	64.348595	66.209068
60	52.827286	54.796394	56.748814	58.683949	60.601204	62.500000	64.379761	66.239906

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 32° to 39°

Min.	32°	33°	34°	35°	36°	37°	38°	39°
0	66.239906	68.079880	69.899117	71.697060	73.473160	75.226883	76.957687	78.665054
1	66.270744	68.110374	69.929253	71.726837	73.502571	75.255913	76.986336	78.693306
2	66.301567	68.140862	69.959389	71.756615	73.531975	75.284943	77.014977	78.721550
3	66.332390	68.171341	69.989517	71.786385	73.561378	75.313965	77.043617	78.749794
4	66.363205	68.201813	70.019646	71.816147	73.590775	75.342987	77.072243	78.778030
5	66.394020	68.232285	70.049759	71.845901	73.620163	75.371994	77.100868	78.806252
6	66.424820	68.262741	70.079872	71.875656	73.649544	75.401001	77.129486	78.834473
7	66.455620	68.293198	70.109978	71.905403	73.678917	75.429993	77.158096	78.862686
8	66.486420	68.323662	70.140083	71.935150	73.708298	75.458992	77.186707	78.890900
9	66.517212	68.354103	70.170181	71.964882	73.737656	75.487976	77.215302	78.919106
10	66.547989	68.384544	70.200264	71.994606	73.767014	75.516953	77.243889	78.947296
11	66.578766	68.414978	70.230347	72.024330	73.796364	75.545929	77.272476	78.975487
12	66.609535	68.445404	70.260422	72.054039	73.825714	75.574890	77.301056	79.003670
13	66.640305	68.475830	70.290497	72.083748	73.855049	75.603851	77.329620	79.031837
14	66.671059	68.506248	70.320557	72.113457	73.884384	75.632805	77.358185	79.060005
15	66.701813	68.536652	70.350616	72.143150	73.913712	75.661751	77.386749	79.088165
16	66.732567	68.567062	70.380669	72.172844	73.943024	75.690689	77.415298	79.116325
17	66.763306	68.597458	70.410713	72.202522	73.972343	75.719620	77.443840	79.144470
18	66.794044	68.627853	70.440758	72.232201	74.001648	75.748550	77.472382	79.172607
19	66.824776	68.658241	70.470787	72.261879	74.030945	75.777473	77.500908	79.200745
20	66.855499	68.688622	70.500816	72.291542	74.060242	75.806389	77.529434	79.228874
21	66.886223	68.718994	70.530838	72.321205	74.089531	75.835297	77.557953	79.256989
22	66.916939	68.749367	70.560860	72.350853	74.118813	75.864197	77.586464	79.285103
23	66.947647	68.779739	70.590874	72.380508	74.148094	75.893097	77.614975	79.313217
24	66.978355	68.810097	70.620880	72.410149	74.177368	75.921982	77.643478	79.341316
25	67.009048	68.840446	70.650879	72.439789	74.206627	75.950867	77.671967	79.369415
26	67.039742	68.870796	70.680870	72.469414	74.235886	75.979744	77.700455	79.397499
27	67.070427	68.901138	70.710861	72.499039	74.265137	76.008614	77.728935	79.425583
28	67.101112	68.931473	70.740837	72.528656	74.294380	76.037476	77.757408	79.453651
29	67.131783	68.961800	70.770813	72.558266	74.323616	76.066330	77.785873	79.481720
30	67.162453	68.992126	70.800781	72.587868	74.352852	76.095177	77.814331	79.509781
31	67.193115	69.022446	70.830742	72.617470	74.382072	76.124023	77.842781	79.537834
32	67.223770	69.052757	70.860703	72.647064	74.411293	76.152863	77.871231	79.565880
33	67.254425	69.083061	70.890648	72.676651	74.440506	76.181694	77.899673	79.593918
34	67.285072	69.113358	70.920593	72.706230	74.469711	76.210518	77.928101	79.621956
35	67.315712	69.143654	70.950531	72.735802	74.498917	76.239334	77.956528	79.649979
36	67.346344	69.173943	70.980469	72.765373	74.528107	76.268143	77.984947	79.678001
37	67.376976	69.204224	71.010391	72.794930	74.557297	76.296951	78.013359	79.706009
38	67.407608	69.234512	71.040321	72.824493	74.586487	76.325752	78.041779	79.734024
39	67.438225	69.264778	71.070236	72.854042	74.615662	76.354546	78.070175	79.762024
40	67.468834	69.295044	71.100143	72.883583	74.644829	76.383331	78.098572	79.790016
41	67.499443	69.325302	71.130051	72.913124	74.673988	76.412109	78.126953	79.818001
42	67.530045	69.355560	71.159943	72.942657	74.703148	76.440880	78.155334	79.845978
43	67.560638	69.385803	71.189835	72.972176	74.732300	76.469650	78.183708	79.873955
44	67.591225	69.416046	71.219719	73.001701	74.761436	76.498405	78.212074	79.901917
45	67.621811	69.446281	71.249596	73.031212	74.790573	76.527161	78.240433	79.929878
46	67.652390	69.476509	71.279472	73.060715	74.819710	76.555908	78.268791	79.957832
47	67.682961	69.506737	71.309334	73.090218	74.848831	76.584648	78.297134	79.985771
48	67.713524	69.536949	71.339195	73.119713	74.877953	76.613380	78.325478	80.013710
49	67.744087	69.567162	71.369049	73.149200	74.907059	76.642113	78.353813	80.041641
50	67.774643	69.597374	71.398895	73.178680	74.936165	76.670830	78.382141	80.069572
51	67.805191	69.627571	71.428741	73.208153	74.965263	76.699547	78.410461	80.097488
52	67.835732	69.657768	71.458580	73.237625	74.994362	76.728249	78.438774	80.125397
53	67.866280	69.687958	71.488411	73.267090	75.023453	76.756958	78.467087	80.153313
54	67.896812	69.718140	71.518242	73.296547	75.052536	76.785652	78.495384	80.181206
55	67.927338	69.748322	71.548058	73.325996	75.081604	76.814346	78.523682	80.209099
56	67.957855	69.778488	71.577866	73.355446	75.110672	76.843025	78.551971	80.236984
57	67.988373	69.808655	71.607674	73.384880	75.139732	76.871696	78.580246	80.264862
58	68.018883	69.838814	71.637474	73.414314	75.168793	76.900368	78.608521	80.292732
59	68.049385	69.868965	71.667267	73.443741	75.197838	76.929031	78.636787	80.320595
60	68.079880	69.899117	71.697060	73.473160	75.226883	76.957687	78.665054	80.348450

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 40° to 47°

Min.	40°	41°	42°	43°	44°	45°	46°	47°
0	80.348450	82.007378	83.641327	85.249794	86.832298	88.388351	89.917480	91.419212
1	80.376305	82.034821	83.668343	85.276382	86.858452	88.414055	89.942734	91.444008
2	80.404144	82.062248	83.695358	85.302971	86.884598	88.439758	89.967979	91.468796
3	80.431984	82.089676	83.722359	85.329544	86.910728	88.465446	89.993217	91.493576
4	80.459816	82.117088	83.749359	85.356110	86.936859	88.491135	90.018448	91.518341
5	80.487640	82.144501	83.776344	85.382668	86.962982	88.516808	90.043671	91.543106
6	80.515450	82.171906	83.803329	85.409218	86.989098	88.542480	90.068886	91.567863
7	80.543266	82.199303	83.830299	85.435768	87.015205	88.568138	90.094101	91.592613
8	80.571068	82.226700	83.857277	85.462311	87.041313	88.593803	90.119301	91.617355
9	80.598869	82.254082	83.884239	85.488838	87.067406	88.619446	90.144501	91.642090
10	80.626656	82.281456	83.911194	85.515366	87.093491	88.645088	90.169685	91.666809
11	80.654442	82.308823	83.938141	85.541885	87.119568	88.670723	90.194862	91.691528
12	80.682213	82.336189	83.965080	85.568390	87.145638	88.696342	90.220032	91.716240
13	80.709984	82.363541	83.992012	85.594894	87.171707	88.721962	90.245193	91.740936
14	80.737747	82.390884	84.018936	85.621391	87.197762	88.747574	90.270348	91.765633
15	80.765503	82.418228	84.045853	85.647873	87.223808	88.773170	90.295494	91.790314
16	80.793251	82.445564	84.072762	85.674355	87.249847	88.798767	90.320641	91.814995
17	80.820992	82.472893	84.099670	85.700829	87.275887	88.824356	90.345772	91.839661
18	80.848724	82.500206	84.126564	85.727295	87.301910	88.849937	90.370895	91.864326
19	80.876450	82.527519	84.153458	85.753754	87.327934	88.875504	90.396011	91.888977
20	80.904175	82.554825	84.180336	85.780205	87.353943	88.901070	90.421120	91.913628
21	80.931885	82.582130	84.207214	85.806648	87.379944	88.926628	90.446220	91.938263
22	80.959595	82.609421	84.234077	85.833084	87.405945	88.952179	90.471313	91.962898
23	80.987297	82.636711	84.260948	85.859520	87.431938	88.977722	90.496407	91.987526
24	81.014992	82.663986	84.287804	85.885941	87.457924	89.003258	90.521484	92.012138
25	81.042679	82.691261	84.314651	85.912361	87.483894	89.028786	90.546555	92.036751
26	81.070358	82.718521	84.341492	85.938766	87.509865	89.054306	90.571625	92.061348
27	81.098030	82.745781	84.368324	85.965164	87.535828	89.079819	90.596680	92.085938
28	81.125694	82.773026	84.395149	85.991562	87.561775	89.105324	90.621727	92.110527
29	81.153358	82.800270	84.421967	86.017944	87.587723	89.130821	90.646767	92.135101
30	81.181007	82.827507	84.448776	86.044327	87.613663	89.156311	90.671799	92.159668
31	81.208656	82.854736	84.475578	86.070694	87.639587	89.181793	90.696823	92.184227
32	81.236290	82.881958	84.502380	86.097061	87.665512	89.207260	90.721840	92.208786
33	81.263924	82.909172	84.529167	86.123413	87.691429	89.232727	90.746849	92.233330
34	81.291550	82.936378	84.555954	86.149765	87.717339	89.258186	90.771851	92.257866
35	81.319168	82.963585	84.582726	86.176109	87.743240	89.283638	90.796844	92.282394
36	81.346779	82.990776	84.609497	86.202446	87.769135	89.309082	90.821831	92.306915
37	81.374382	83.017960	84.636253	86.228767	87.795013	89.334518	90.846809	92.331429
38	81.401985	83.045151	84.663017	86.255096	87.820900	89.359955	90.871788	92.355942
39	81.429573	83.072319	84.689766	86.281410	87.846771	89.385376	90.896751	92.380440
40	81.457161	83.099487	84.716507	86.307716	87.872635	89.410789	90.921707	92.404930
41	81.484734	83.126648	84.743233	86.334015	87.898491	89.436195	90.946655	92.429413
42	81.512306	83.153801	84.769958	86.360306	87.924339	89.461594	90.971596	92.453888
43	81.539864	83.180939	84.796677	86.386589	87.950180	89.486984	90.996529	92.478355
44	81.567421	83.208076	84.823395	86.412865	87.976013	89.512367	91.021454	92.502815
45	81.594971	83.235207	84.850098	86.439133	88.001839	89.537743	91.046371	92.527267
46	81.622513	83.262337	84.876793	86.465393	88.027664	89.563110	91.071281	92.551712
47	81.650047	83.289452	84.903481	86.491653	88.053474	89.588470	91.096184	92.576149
48	81.677574	83.316559	84.930161	86.517899	88.079277	89.613823	91.121078	92.600578
49	81.705101	83.343658	84.956841	86.544136	88.105072	89.639175	91.145966	92.624992
50	81.732613	83.370758	84.983505	86.570374	88.130859	89.664513	91.170845	92.649406
51	81.760117	83.397842	85.010170	86.596596	88.156647	89.689842	91.195717	92.673813
52	81.787621	83.424927	85.036819	86.622810	88.182419	89.715164	91.220581	92.698212
53	81.815117	83.452003	85.063477	86.649033	88.208191	89.740486	91.245438	92.722603
54	81.842606	83.479073	85.090111	86.675232	88.233948	89.765793	91.270287	92.746986
55	81.870087	83.506134	85.116745	86.701431	88.259705	89.791092	91.295128	92.771355
56	81.897560	83.533188	85.143372	86.727615	88.285446	89.816383	91.319962	92.795723
57	81.925026	83.560234	85.169991	86.753799	88.311180	89.841667	91.344788	92.820084
58	81.952484	83.587273	85.196594	86.779976	88.336914	89.866943	91.369606	92.844429
59	81.979935	83.614304	85.223198	86.806137	88.362633	89.892212	91.394417	92.868774
60	82.007378	83.641327	85.249794	86.832298	88.388351	89.917480	91.419212	92.893105

Copyright 2004, Industrial Press, Inc., New York, NY

Constants for Setting a 125-mm Sine-Bar for 48° to 55°

Min.	48°	49°	50°	51°	52°	53°	54°	55°
0	92.893105	94.338699	95.755554	97.143250	98.501343	99.829437	101.127129	102.394005
1	92.917435	94.362549	95.778923	97.166122	98.523727	99.851318	101.148491	102.414856
2	92.941750	94.386391	95.802284	97.188995	98.546104	99.873192	101.169853	102.435699
3	92.966057	94.410225	95.825638	97.211861	98.568466	99.895050	101.191208	102.456535
4	92.990364	94.434052	95.848984	97.234711	98.590820	99.916901	101.212547	102.477364
5	93.014656	94.457870	95.872314	97.257553	98.613174	99.938744	101.233879	102.498177
6	93.038940	94.481682	95.895645	97.280396	98.635513	99.960579	101.255203	102.518982
7	93.063225	94.505486	95.918961	97.303223	98.657845	99.982407	101.276520	102.539787
8	93.087502	94.529289	95.942276	97.326050	98.680168	100.004234	101.297836	102.560577
9	93.111763	94.553070	95.965584	97.348862	98.702484	100.026047	101.319130	102.581360
10	93.136017	94.576851	95.988876	97.371666	98.724792	100.047844	101.340424	102.602135
11	93.160263	94.600624	96.012161	97.394463	98.747093	100.069641	101.361710	102.622902
12	93.184502	94.624382	96.035446	97.417252	98.769379	100.091423	101.382980	102.643654
13	93.208733	94.648140	96.058716	97.440025	98.791664	100.113197	101.404243	102.664398
14	93.232956	94.671883	96.081978	97.462799	98.813934	100.134972	101.425499	102.685143
15	93.257172	94.695625	96.105232	97.485565	98.836197	100.156731	101.446747	102.705872
16	93.281380	94.719353	96.128479	97.508316	98.858452	100.178482	101.467987	102.726593
17	93.305580	94.743080	96.151718	97.531067	98.880699	100.200226	101.489220	102.747299
18	93.329773	94.766792	96.174942	97.553802	98.902939	100.221954	101.510445	102.768005
19	93.353958	94.790497	96.198166	97.576530	98.925171	100.243683	101.531654	102.788704
20	93.378136	94.814201	96.221382	97.599251	98.947395	100.265396	101.552864	102.809387
21	93.402306	94.837891	96.244583	97.621964	98.969612	100.287109	101.574059	102.830063
22	93.426460	94.861572	96.267784	97.644669	98.991814	100.308807	101.595245	102.850731
23	93.450623	94.885254	96.290977	97.667374	99.014023	100.330505	101.616432	102.871399
24	93.474762	94.908920	96.314163	97.690063	99.036209	100.352188	101.637596	102.892052
25	93.498901	94.932579	96.337334	97.712746	99.058388	100.373863	101.658760	102.912689
26	93.523033	94.956230	96.360497	97.735413	99.080566	100.395531	101.679916	102.933327
27	93.547150	94.979866	96.383652	97.758080	99.102730	100.417191	101.701057	102.953949
28	93.571266	95.003502	96.406799	97.780739	99.124886	100.438835	101.722198	102.974571
29	93.595367	95.027130	96.429939	97.803383	99.147034	100.460480	101.743324	102.995178
30	93.619469	95.050751	96.453072	97.826019	99.169167	100.482109	101.764442	103.015778
31	93.643555	95.074356	96.476196	97.848656	99.191299	100.503731	101.785553	103.036369
32	93.667641	95.097961	96.499313	97.871277	99.213425	100.525345	101.806656	103.056946
33	93.691711	95.121552	96.522423	97.893890	99.235535	100.546959	101.827744	103.077522
34	93.715775	95.145142	96.545525	97.916496	99.257645	100.568550	101.848831	103.098083
35	93.739838	95.168716	96.568611	97.939095	99.279739	100.590141	101.869904	103.118637
36	93.763885	95.192291	96.591698	97.961685	99.301826	100.611725	101.890976	103.139191
37	93.787926	95.215851	96.614769	97.984261	99.323906	100.633301	101.912033	103.159729
38	93.811966	95.239410	96.637840	98.006844	99.345985	100.654869	101.933090	103.180260
39	93.835991	95.262955	96.660904	98.029404	99.368050	100.676422	101.954132	103.200783
40	93.860008	95.286491	96.683952	98.051964	99.390106	100.697968	101.975159	103.221291
41	93.884018	95.310020	96.706993	98.074509	99.412148	100.719505	101.996185	103.241798
42	93.908020	95.333542	96.730026	98.097046	99.434189	100.741035	102.017204	103.262291
43	93.932014	95.357056	96.753052	98.119583	99.456215	100.762558	102.038208	103.282776
44	93.956001	95.380562	96.776070	98.142105	99.478241	100.784073	102.059204	103.303253
45	93.979980	95.404060	96.799080	98.164619	99.500252	100.805580	102.080193	103.323723
46	94.003944	95.427551	96.822083	98.187126	99.522255	100.827072	102.101181	103.344177
47	94.027908	95.451035	96.845078	98.209625	99.544250	100.848564	102.122147	103.364632
48	94.051865	95.474503	96.868065	98.232109	99.566238	100.870041	102.143112	103.385071
49	94.075813	95.497971	96.891037	98.254593	99.588219	100.891510	102.164070	103.405502
50	94.099747	95.521423	96.914009	98.277069	99.610191	100.912971	102.185013	103.425934
51	94.123680	95.544876	96.936966	98.299530	99.632156	100.934425	102.205956	103.446342
52	94.147598	95.568314	96.959923	98.321991	99.654106	100.955872	102.226883	103.466751
53	94.171524	95.591751	96.982872	98.344444	99.676056	100.977310	102.247810	103.487160
54	94.195427	95.615181	97.005806	98.366882	99.697998	100.998741	102.268715	103.507545
55	94.219330	95.638596	97.028732	98.389313	99.719925	101.020157	102.289619	103.527924
56	94.243217	95.662003	97.051651	98.411736	99.741844	101.041573	102.310516	103.548302
57	94.267097	95.685402	97.074562	98.434151	99.763756	101.062973	102.331406	103.568665
58	94.290977	95.708794	97.097466	98.456558	99.785660	101.084366	102.352280	103.589012
59	94.314842	95.732178	97.120361	98.478958	99.807556	101.105751	102.373146	103.609360
60	94.338699	95.755554	97.143250	98.501343	99.829437	101.127129	102.394005	103.629700

Copyright 2004, Industrial Press, Inc., New York, NY

Squares of Numbers

Squares of Numbers from 1 to 999

	0	1	2	3	4	5	6	7	8	9
0	0	1	4	9	16	25	36	49	64	81
1	100	121	144	169	196	225	256	289	324	361
2	400	441	484	529	576	625	676	729	784	841
3	900	961	1024	1089	1156	1225	1296	1369	1444	1521
4	1600	1681	1764	1849	1936	2025	2116	2209	2304	2401
5	2500	2601	2704	2809	2916	3025	3136	3249	3364	3481
6	3600	3721	3844	3969	4096	4225	4356	4489	4624	4761
7	4900	5041	5184	5329	5476	5625	5776	5929	6084	6241
8	6400	6561	6724	6889	7056	7225	7396	7569	7744	7921
9	8100	8281	8464	8649	8836	9025	9216	9409	9604	9801
10	10000	10201	10404	10609	10816	11025	11236	11449	11664	11881
11	12100	12321	12544	12769	12996	13225	13456	13689	13924	14161
12	14400	14641	14884	15129	15376	15625	15876	16129	16384	16641
13	16900	17161	17424	17689	17956	18225	18496	18769	19044	19321
14	19600	19881	20164	20449	20736	21025	21316	21609	21904	22201
15	22500	22801	23104	23409	23716	24025	24336	24649	24964	25281
16	25600	25921	26244	26569	26896	27225	27556	27889	28224	28561
17	28900	29241	29584	29929	30276	30625	30976	31329	31684	32041
18	32400	32761	33124	33489	33856	34225	34596	34969	35344	35721
19	36100	36481	36864	37249	37636	38025	38416	38809	39204	39601
20	40000	40401	40804	41209	41616	42025	42436	42849	43264	43681
21	44100	44521	44944	45369	45796	46225	46656	47089	47524	47961
22	48400	48841	49284	49729	50176	50625	51076	51529	51984	52441
23	52900	53361	53824	54289	54756	55225	55696	56169	56644	57121
24	57600	58081	58564	59049	59536	60025	60516	61009	61504	62001
25	62500	63001	63504	64009	64516	65025	65536	66049	66564	67081
26	67600	68121	68644	69169	69696	70225	70756	71289	71824	72361
27	72900	73441	73984	74529	75076	75625	76176	76729	77284	77841
28	78400	78961	79524	80089	80656	81225	81796	82369	82944	83521
29	84100	84681	85264	85849	86436	87025	87616	88209	88804	89401
30	90000	90601	91204	91809	92416	93025	93636	94249	94864	95481
31	96100	96721	97344	97969	98596	99225	99856	100489	101124	101761
32	102400	103041	103684	104329	104976	105625	106276	106929	107584	108241
33	108900	109561	110224	110889	111556	112225	112896	113569	114244	114921
34	115600	116281	116964	117649	118336	119025	119716	120409	121104	121801
35	122500	123201	123904	124609	125316	126025	126736	127449	128164	128881
36	129600	130321	131044	131769	132496	133225	133956	134689	135424	136161
37	136900	137641	138384	139129	139876	140625	141376	142129	142884	143641
38	144400	145161	145924	146689	147456	148225	148996	149769	150544	151321
39	152100	152881	153664	154449	155236	156025	156816	157609	158404	159201
40	160000	160801	161604	162409	163216	164025	164836	165649	166464	167281
41	168100	168921	169744	170569	171396	172225	173056	173889	174724	175561
42	176400	177241	178084	178929	179776	180625	181476	182329	183184	184041
43	184900	185761	186624	187489	188356	189225	190096	190969	191844	192721
44	193600	194481	195364	196249	197136	198025	198916	199809	200704	201601
45	202500	203401	204304	205209	206116	207025	207936	208849	209764	210681
46	211600	212521	213444	214369	215296	216225	217156	218089	219024	219961
47	220900	221841	222784	223729	224676	225625	226576	227529	228484	229441
48	230400	231361	232324	233289	234256	235225	236196	237169	238144	239121
49	240100	241081	242064	243049	244036	245025	246016	247009	248004	249001
50	250000	251001	252004	253009	254016	255025	256036	257049	258064	259081

Copyright 2004, Industrial Press, Inc., New York, NY

Squares of Numbers from 1 to 999

	0	1	2	3	4	5	6	7	8	9
51	260100	261121	262144	263169	264196	265225	266256	267289	268324	269361
52	270400	271441	272484	273529	274576	275625	276676	277729	278784	279841
53	280900	281961	283024	284089	285156	286225	287296	288369	289444	290521
54	291600	292681	293764	294849	295936	297025	298116	299209	300304	301401
55	302500	303601	304704	305809	306916	308025	309136	310249	311364	312481
56	313600	314721	315844	316969	318096	319225	320356	321489	322624	323761
57	324900	326041	327184	328329	329476	330625	331776	332929	334084	335241
58	336400	337561	338724	339889	341056	342225	343396	344569	345744	346921
59	348100	349281	350464	351649	352836	354025	355216	356409	357604	358801
60	360000	361201	362404	363609	364816	366025	367236	368449	369664	370881
61	372100	373321	374544	375769	376996	378225	379456	380689	381924	383161
62	384400	385641	386884	388129	389376	390625	391876	393129	394384	395641
63	396900	398161	399424	400689	401956	403225	404496	405769	407044	408321
64	409600	410881	412164	413449	414736	416025	417316	418609	419904	421201
65	422500	423801	425104	426409	427716	429025	430336	431649	432964	434281
66	435600	436921	438244	439569	440896	442225	443556	444889	446224	447561
67	448900	450241	451584	452929	454276	455625	456976	458329	459684	461041
68	462400	463761	465124	466489	467856	469225	470596	471969	473344	474721
69	476100	477481	478864	480249	481636	483025	484416	485809	487204	488601
70	490000	491401	492804	494209	495616	497025	498436	499849	501264	502681
71	504100	505521	506944	508369	509796	511225	512656	514089	515524	516961
72	518400	519841	521284	522729	524176	525625	527076	528529	529984	531441
73	532900	534361	535824	537289	538756	540225	541696	543169	544644	546121
74	547600	549081	550564	552049	553536	555025	556516	558009	559504	561001
75	562500	564001	565504	567009	568516	570025	571536	573049	574564	576081
76	577600	579121	580644	582169	583696	585225	586756	588289	589824	591361
77	592900	594441	595984	597529	599076	600625	602176	603729	605284	606841
78	608400	609961	611524	613089	614656	616225	617796	619369	620944	622521
79	624100	625681	627264	628849	630436	632025	633616	635209	636804	638401
80	640000	641601	643204	644809	646416	648025	649636	651249	652864	654481
81	656100	657721	659344	660969	662596	664225	665856	667489	669124	670761
82	672400	674041	675684	677329	678976	680625	682276	683929	685584	687241
83	688900	690561	692224	693889	695556	697225	698896	700569	702244	703921
84	705600	707281	708964	710649	712336	714025	715716	717409	719104	720801
85	722500	724201	725904	727609	729316	731025	732736	734449	736164	737881
86	739600	741321	743044	744769	746496	748225	749956	751689	753424	755161
87	756900	758641	760384	762129	763876	765625	767376	769129	770884	772641
88	774400	776161	777924	779689	781456	783225	784996	786769	788544	790321
89	792100	793881	795664	797449	799236	801025	802816	804609	806404	808201
90	810000	811801	813604	815409	817216	819025	820836	822649	824464	826281
91	828100	829921	831744	833569	835396	837225	839056	840889	842724	844561
92	846400	848241	850084	851929	853776	855625	857476	859329	861184	863041
93	864900	866761	868624	870489	872356	874225	876096	877969	879844	881721
94	883600	885481	887364	889249	891136	893025	894916	896809	898704	900601
95	902500	904401	906304	908209	910116	912025	913936	915849	917764	919681
96	921600	923521	925444	927369	929296	931225	933156	935089	937024	938961
97	940900	942841	944784	946729	948676	950625	952576	954529	956484	958441
98	960400	962361	964324	966289	968256	970225	972196	974169	976144	978121
99	980100	982081	984064	986049	988036	990025	992016	994009	996004	998001

To find the square of a given whole number, divide the number by 10 and find the row in the first column that contains the whole number portion of the result. The selected row contains the square of given number under the column corresponding to the last digit in the number.

Example: The square of 673, found in row labeled 67, under column labeled 3, is given as 452,929.

Copyright 2004, Industrial Press, Inc., New York, NY

Squares of Mixed Numbers from 1/64 to 6, by 64ths

No.	0	1	2	3	4	5
1/64	0.00024	1.03149	4.06274	9.09399	16.12524	25.15649
1/32	0.00098	1.06348	4.12598	9.18848	16.25098	25.31348
3/64	0.00220	1.09595	4.18970	9.28345	16.37720	25.47095
1/16	0.00391	1.12891	4.25391	9.37891	16.50391	25.62891
5/64	0.00610	1.16235	4.31860	9.47485	16.63110	25.78735
3/32	0.00879	1.19629	4.38379	9.57129	16.75879	25.94629
7/64	0.01196	1.23071	4.44946	9.66821	16.88696	26.10571
1/8	0.01563	1.26563	4.51563	9.76563	17.01563	26.26563
9/64	0.01978	1.30103	4.58228	9.86353	17.14478	26.42603
5/32	0.02441	1.33691	4.64941	9.96191	17.27441	26.58691
11/64	0.02954	1.37329	4.71704	10.06079	17.40454	26.74829
3/16	0.03516	1.41016	4.78516	10.16016	17.53516	26.91016
13/64	0.04126	1.44751	4.85376	10.26001	17.66626	27.07251
7/32	0.04785	1.48535	4.92285	10.36035	17.79785	27.23535
15/64	0.05493	1.52368	4.99243	10.46118	17.92993	27.39868
1/4	0.06250	1.56250	5.06250	10.56250	18.06250	27.56250
17/64	0.07056	1.60181	5.13306	10.66431	18.19556	27.72681
9/32	0.07910	1.64160	5.20410	10.76660	18.32910	27.89160
19/64	0.08813	1.68188	5.27563	10.86938	18.46313	28.05688
5/16	0.09766	1.72266	5.34766	10.97266	18.59766	28.22266
21/64	0.10767	1.76392	5.42017	11.07642	18.73267	28.38892
11/32	0.11816	1.80566	5.49316	11.18066	18.86816	28.55566
23/64	0.12915	1.84790	5.56665	11.28540	19.00415	28.72290
3/8	0.14063	1.89063	5.64063	11.39063	19.14063	28.89063
25/64	0.15259	1.93384	5.71509	11.49634	19.27759	29.05884
13/32	0.16504	1.97754	5.79004	11.60254	19.41504	29.22754
27/64	0.17798	2.02173	5.86548	11.70923	19.55298	29.39673
7/16	0.19141	2.06641	5.94141	11.81641	19.69141	29.56641
29/64	0.20532	2.11157	6.01782	11.92407	19.83032	29.73657
15/32	0.21973	2.15723	6.09473	12.03223	19.96973	29.90723
31/64	0.23462	2.20337	6.17212	12.14087	20.10962	30.07837
1/2	0.25000	2.25000	6.25000	12.25000	20.25000	30.25000
33/64	0.26587	2.29712	6.32837	12.35962	20.39087	30.42212
17/32	0.28223	2.34473	6.40723	12.46973	20.53223	30.59473
35/64	0.29907	2.39282	6.48657	12.58032	20.67407	30.76782
9/16	0.31641	2.44141	6.56641	12.69141	20.81641	30.94141
37/64	0.33423	2.49048	6.64673	12.80298	20.95923	31.11548
19/32	0.35254	2.54004	6.72754	12.91504	21.10254	31.29004
39/64	0.37134	2.59009	6.80884	13.02759	21.24634	31.46509
5/8	0.39063	2.64063	6.89063	13.14063	21.39063	31.64063
41/64	0.41040	2.69165	6.97290	13.25415	21.53540	31.81665
21/32	0.43066	2.74316	7.05566	13.36816	21.68066	31.99316
43/64	0.45142	2.79517	7.13892	13.48267	21.82642	32.17017
11/16	0.47266	2.84766	7.22266	13.59766	21.97266	32.34766
45/64	0.49438	2.90063	7.30688	13.71313	22.11938	32.52563
23/32	0.51660	2.95410	7.39160	13.82910	22.26660	32.70410
47/64	0.53931	3.00806	7.47681	13.94556	22.41431	32.88306
3/4	0.56250	3.06250	7.56250	14.06250	22.56250	33.06250
49/64	0.58618	3.11743	7.64868	14.17993	22.71118	33.24243
25/32	0.61035	3.17285	7.73535	14.29785	22.86035	33.42285
51/64	0.63501	3.22876	7.82251	14.41626	23.01001	33.60376
13/16	0.66016	3.28516	7.91016	14.53516	23.16016	33.78516
53/64	0.68579	3.34204	7.99829	14.65454	23.31079	33.96704
27/32	0.71191	3.39941	8.08691	14.77441	23.46191	34.14941
55/64	0.73853	3.45728	8.17603	14.89478	23.61353	34.33228
7/8	0.76563	3.51563	8.26563	15.01563	23.76563	34.51563
57/64	0.79321	3.57446	8.35571	15.13696	23.91821	34.69946
29/32	0.82129	3.63379	8.44629	15.25879	24.07129	34.88379
59/64	0.84985	3.69360	8.53735	15.38110	24.22485	35.06860
15/16	0.87891	3.75391	8.62891	15.50391	24.37891	35.25391
61/64	0.90845	3.81470	8.72095	15.62720	24.53345	35.43970
31/32	0.93848	3.87598	8.81348	15.75098	24.68848	35.62598
63/64	0.96899	3.93774	8.90649	15.87524	24.84399	35.81274
1	1.00000	4.00000	9.00000	16.00000	25.00000	36.00000

Copyright 2004, Industrial Press, Inc., New York, NY

Squares of Mixed Numbers from 6 1/64 to 12, by 64ths

No.	6	7	8	9	10	11
1/64	36.18774	49.21899	64.25024	81.28149	100.31274	121.34399
1/32	36.37598	49.43848	64.50098	81.56348	100.62598	121.68848
3/64	36.56470	49.65845	64.75220	81.84595	100.93970	122.03345
1/16	36.75391	49.87891	65.00391	82.12891	101.25391	122.37891
5/64	36.94360	50.09985	65.25610	82.41235	101.56860	122.72485
3/32	37.13379	50.32129	65.50879	82.69629	101.88379	123.07129
7/64	37.32446	50.54321	65.76196	82.98071	102.19946	123.41821
1/8	37.51563	50.76563	66.01563	83.26563	102.51563	123.76563
9/64	37.70728	50.98853	66.26978	83.55103	102.83228	124.11353
5/32	37.89941	51.21191	66.52441	83.83691	103.14941	124.46191
11/64	38.09204	51.43579	66.77954	84.12329	103.46704	124.81079
3/16	38.28516	51.66016	67.03516	84.41016	103.78516	125.16016
13/64	38.47876	51.88501	67.29126	84.69751	104.10376	125.51001
7/32	38.67285	52.11035	67.54785	84.98535	104.42285	125.86035
15/64	38.86743	52.33618	67.80493	85.27368	104.74243	126.21118
1/4	39.06250	52.56250	68.06250	85.56250	105.06250	126.56250
17/64	39.25806	52.78931	68.32056	85.85181	105.38306	126.91431
9/32	39.45410	53.01660	68.57910	86.14160	105.70410	127.26660
19/64	39.65063	53.24438	68.83813	86.43188	106.02563	127.61938
5/16	39.84766	53.47266	69.09766	86.72266	106.34766	127.97266
21/64	40.04517	53.70142	69.35767	87.01392	106.67017	128.32642
11/32	40.24316	53.93066	69.61816	87.30566	106.99316	128.68066
23/64	40.44165	54.16040	69.87915	87.59790	107.31665	129.03540
3/8	40.64063	54.39063	70.14063	87.89063	107.64063	129.39063
25/64	40.84009	54.62134	70.40259	88.18384	107.96509	129.74634
13/32	41.04004	54.85254	70.66504	88.47754	108.29004	130.10254
27/64	41.24048	55.08423	70.92798	88.77173	108.61548	130.45923
7/16	41.44141	55.31641	71.19141	89.06641	108.94141	130.81641
29/64	41.64282	55.54907	71.45532	89.36157	109.26782	131.17407
15/32	41.84473	55.78223	71.71973	89.65723	109.59473	131.53223
31/64	42.04712	56.01587	71.98462	89.95337	109.92212	131.89087
1/2	42.25000	56.25000	72.25000	90.25000	110.25000	132.25000
33/64	42.45337	56.48462	72.51587	90.54712	110.57837	132.60962
17/32	42.65723	56.71973	72.78223	90.84473	110.90723	132.96973
35/64	42.86157	56.95532	73.04907	91.14282	111.23657	133.33032
9/16	43.06641	57.19141	73.31641	91.44141	111.56641	133.69141
37/64	43.27173	57.42798	73.58423	91.74048	111.89673	134.05298
19/32	43.47754	57.66504	73.85254	92.04004	112.22754	134.41504
39/64	43.68384	57.90259	74.12134	92.34009	112.55884	134.77759
5/8	43.89063	58.14063	74.39063	92.64063	112.89063	135.14063
41/64	44.09790	58.37915	74.66040	92.94165	113.22290	135.50415
21/32	44.30566	58.61816	74.93066	93.24316	113.55566	135.86816
43/64	44.51392	58.85767	75.20142	93.54517	113.88892	136.23267
11/16	44.72266	59.09766	75.47266	93.84766	114.22266	136.59766
45/64	44.93188	59.33813	75.74438	94.15063	114.55688	136.96313
23/32	45.14160	59.57910	76.01660	94.45410	114.89160	137.32910
47/64	45.35181	59.82056	76.28931	94.75806	115.22681	137.69556
3/4	45.56250	60.06250	76.56250	95.06250	115.56250	138.06250
49/64	45.77368	60.30493	76.83618	95.36743	115.89868	138.42993
25/32	45.98535	60.54785	77.11035	95.67285	116.23535	138.79785
51/64	46.19751	60.79126	77.38501	95.97876	116.57251	139.16626
13/16	46.41016	61.03516	77.66016	96.28516	116.91016	139.53516
53/64	46.62329	61.27954	77.93579	96.59204	117.24829	139.90454
27/32	46.83691	61.52441	78.21191	96.89941	117.58691	140.27441
55/64	47.05103	61.76978	78.48853	97.20728	117.92603	140.64478
7/8	47.26563	62.01563	78.76563	97.51563	118.26563	141.01563
57/64	47.48071	62.26196	79.04321	97.82446	118.60571	141.38696
29/32	47.69629	62.50879	79.32129	98.13379	118.94629	141.75879
59/64	47.91235	62.75610	79.59985	98.44360	119.28735	142.13110
15/16	48.12891	63.00391	79.87891	98.75391	119.62891	142.50391
61/64	48.34595	63.25220	80.15845	99.06470	119.97095	142.87720
31/32	48.56348	63.50098	80.43848	99.37598	120.31348	143.25098
63/64	48.78149	63.75024	80.71899	99.68774	120.65649	143.62524
1	49.00000	64.00000	81.00000	100.00000	121.00000	144.00000

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Fractions

Squares and Cubes of Numbers from 1/32 to 6 15/16

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
1/32	0.00098	0.00003	1 17/32	2.34473	3.59036	4	16.00000	64.00000
1/16	0.00391	0.00024	1 9/16	2.44141	3.81470	4 1/16	16.50391	67.04712
3/32	0.00879	0.00082	1 19/32	2.54004	4.04819	4 1/8	17.01563	70.18945
1/8	0.01563	0.00195	1 5/8	2.64063	4.29102	4 3/16	17.53516	73.42847
5/32	0.02441	0.00381	1 21/32	2.74316	4.54337	4 1/4	18.06250	76.76563
3/16	0.03516	0.00659	1 11/16	2.84766	4.80542	4 5/16	18.59766	80.20239
7/32	0.04785	0.01047	1 23/32	2.95410	5.07736	4 3/8	19.14063	83.74023
1/4	0.06250	0.01563	1 3/4	3.06250	5.35938	4 7/16	19.69141	87.38062
9/32	0.07910	0.02225	1 25/32	3.17285	5.65164	4 1/2	20.25000	91.12500
5/16	0.09766	0.03052	1 13/16	3.28516	5.95435	4 9/16	20.81641	94.97485
11/32	0.11816	0.04062	1 27/32	3.39941	6.26767	4 5/8	21.39063	98.93164
3/8	0.14063	0.05273	1 7/8	3.51563	6.59180	4 11/16	21.97266	102.99683
13/32	0.16504	0.06705	1 29/32	3.63379	6.92691	4 3/4	22.56250	107.17188
7/16	0.19141	0.08374	1 15/16	3.75391	7.27319	4 13/16	23.16016	111.45825
15/32	0.21973	0.10300	1 31/32	3.87598	7.63083	4 7/8	23.76563	115.85742
1/2	0.25000	0.12500	2	4.00000	8.00000	4 15/16	24.37891	120.37085
17/32	0.28223	0.14993	2 1/32	4.12598	8.38089	5	25.00000	125.00000
9/16	0.31641	0.17798	2 1/16	4.25391	8.77368	5 1/16	25.62891	129.74634
19/32	0.35254	0.20932	2 1/8	4.51563	9.59570	5 1/8	26.26563	134.61133
5/8	0.39063	0.24414	2 3/16	4.78516	10.46753	5 3/16	26.91016	139.59644
21/32	0.43066	0.28262	2 1/4	5.06250	11.39063	5 1/4	27.56250	144.70313
11/16	0.47266	0.32495	2 5/16	5.34766	12.36646	5 5/16	28.22266	149.93286
23/32	0.51660	0.37131	2 3/8	5.64063	13.39648	5 3/8	28.89063	155.28711
3/4	0.56250	0.42188	2 7/16	5.94141	14.48218	5 7/16	29.56641	160.76733
25/32	0.61035	0.47684	2 1/2	6.25000	15.62500	5 1/2	30.25000	166.37500
13/16	0.66016	0.53638	2 9/16	6.56641	16.82642	5 9/16	30.94141	172.11157
27/32	0.71191	0.60068	2 5/8	6.89063	18.08789	5 5/8	31.64063	177.97852
7/8	0.76563	0.66992	2 11/16	7.22266	19.41089	5 11/16	32.34766	183.97729
29/32	0.82129	0.74429	2 3/4	7.56250	20.79688	5 3/4	33.06250	190.10938
15/16	0.87891	0.82397	2 13/16	7.91016	22.24731	5 13/16	33.78516	196.37622
31/32	0.93848	0.90915	2 7/8	8.26563	23.76367	5 7/8	34.51563	202.77930
1	1.00000	1.00000	2 15/16	8.62891	25.34741	5 15/16	35.25391	209.32007
1 1/32	1.06348	1.09671	3	9.00000	27.00000	6	36.00000	216.00000
1 1/16	1.12891	1.19946	3 1/16	9.37891	28.72290	6 1/16	36.75391	222.82056
1 3/32	1.19629	1.30844	3 1/8	9.76563	30.51758	6 1/8	37.51563	229.78320
1 1/8	1.26563	1.42383	3 3/16	10.16016	32.38550	6 3/16	38.28516	236.88940
1 5/32	1.33691	1.54581	3 1/4	10.56250	34.32813	6 1/4	39.06250	244.14063
1 3/16	1.41016	1.67456	3 5/16	10.97266	36.34692	6 5/16	39.84766	251.53833
1 7/32	1.48535	1.81027	3 3/8	11.39063	38.44336	6 3/8	40.64063	259.08398
1 1/4	1.56250	1.95313	3 7/16	11.81641	40.61890	6 7/16	41.44141	266.77905
1 9/32	1.64160	2.10330	3 1/2	12.25000	42.87500	6 1/2	42.25000	274.62500
1 5/16	1.72266	2.26099	3 9/16	12.69141	45.21313	6 9/16	43.06641	282.62329
1 11/32	1.80566	2.42636	3 5/8	13.14063	47.63477	6 5/8	43.89063	290.77539
1 3/8	1.89063	2.59961	3 11/16	13.59766	50.14136	6 11/16	44.72266	299.08276
1 13/32	1.97754	2.78091	3 3/4	14.06250	52.73438	6 3/4	45.56250	307.54688
1 7/16	2.06641	2.97046	3 13/16	14.53516	55.41528	6 13/16	46.41016	316.16919
1 15/32	2.15723	3.16843	3 7/8	15.01563	58.18555	6 7/8	47.26563	324.95117
1 1/2	2.25000	3.37500	3 15/16	15.50391	61.04663	6 15/16	48.12891	333.89429

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 7 to 21 7/8

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
7	49.00000	343.00000	10	100.00000	1000.00000	16	256.00000	4096.00000
1/16	49.87891	352.26978	1/8	102.51563	1037.97070	1/8	260.01563	4192.75195
1/8	50.76563	361.70508	1/4	105.06250	1076.89063	1/4	264.06250	4291.01563
3/16	51.66016	371.30737	3/8	107.64063	1116.77148	3/8	268.14063	4390.80273
1/4	52.56250	381.07813	1/2	110.25000	1157.62500	1/2	272.25000	4492.12500
5/16	53.47266	391.01880	5/8	112.89063	1199.46289	5/8	276.39063	4594.99414
3/8	54.39063	401.13086	3/4	115.56250	1242.29688	3/4	280.56250	4699.42188
7/16	55.31641	411.41577	7/8	118.26563	1286.13867	7/8	284.76563	4805.41992
1/2	56.25000	421.87500	11	121.00000	1331.00000	17	289.00000	4913.00000
9/16	57.19141	432.51001	1/8	123.76563	1376.89258	1/8	293.26563	5022.17383
5/8	58.14063	443.32227	1/4	126.56250	1423.82813	1/4	297.56250	5132.95313
11/16	59.09766	454.31323	3/8	129.39063	1471.81836	3/8	301.89063	5245.34961
3/4	60.06250	465.48438	1/2	132.25000	1520.87500	1/2	306.25000	5359.37500
13/16	61.03516	476.83716	5/8	135.14063	1571.00977	5/8	310.64063	5475.04102
7/8	62.01563	488.37305	3/4	138.06250	1622.23438	3/4	315.06250	5592.35938
15/16	63.00391	500.09351	7/8	141.01563	1674.56055	7/8	319.51563	5711.34180
8	64.00000	512.00000	12	144.00000	1728.00000	18	324.00000	5832.00000
1/16	65.00391	524.09399	1/8	147.01563	1782.56445	1/8	328.51563	5954.34570
1/8	66.01563	536.37695	1/4	150.06250	1838.26563	1/4	333.06250	6078.39063
3/16	67.03516	548.85034	3/8	153.14063	1895.11523	3/8	337.64063	6204.14648
1/4	68.06250	561.51563	1/2	156.25000	1953.12500	1/2	342.25000	6331.62500
5/16	69.09766	574.37427	5/8	159.39063	2012.30664	5/8	346.89063	6460.83789
3/8	70.14063	587.42773	3/4	162.56250	2072.67188	3/4	351.56250	6591.79688
7/16	71.19141	600.67749	7/8	165.76563	2134.23242	7/8	356.26563	6724.51367
1/2	72.25000	614.12500	13	169.00000	2197.00000	19	361.00000	6859.00000
9/16	73.31641	627.77173	1/8	172.26563	2260.98633	1/8	365.76563	6995.26758
5/8	74.39063	641.61914	1/4	175.56250	2326.20313	1/4	370.56250	7133.32813
11/16	75.47266	655.66870	3/8	178.89063	2392.66211	3/8	375.39063	7273.19336
3/4	76.56250	669.92188	1/2	182.25000	2460.37500	1/2	380.25000	7414.87500
13/16	77.66016	684.38013	5/8	185.64063	2529.35352	5/8	385.14063	7558.38477
7/8	78.76563	699.04492	3/4	189.06250	2599.60938	3/4	390.06250	7703.73438
15/16	79.87891	713.91772	7/8	192.51563	2671.15430	7/8	395.01563	7850.93555
9	81.00000	729.00000	14	196.00000	2744.00000	20	400.00000	8000.00000
1/16	82.12891	744.29321	1/8	199.51563	2818.15820	1/8	405.01563	8150.93945
1/8	83.26563	759.79883	1/4	203.06250	2893.64063	1/4	410.06250	8303.76563
3/16	84.41016	775.51831	3/8	206.64063	2970.45898	3/8	415.14063	8458.49023
1/4	85.56250	791.45313	1/2	210.25000	3048.62500	1/2	420.25000	8615.12500
5/16	86.72266	807.60474	5/8	213.89063	3128.15039	5/8	425.39063	8773.68164
3/8	87.89063	823.97461	3/4	217.56250	3209.04688	3/4	430.56250	8934.17188
7/16	89.06641	840.56421	7/8	221.26563	3291.32617	7/8	435.76563	9096.60742
1/2	90.25000	857.37500	15	225.00000	3375.00000	21	441.00000	9261.00000
9/16	91.44141	874.40845	1/8	228.76563	3460.08008	1/8	446.26563	9427.36133
5/8	92.64063	891.66602	1/4	232.56250	3546.57813	1/4	451.56250	9595.70313
11/16	93.84766	909.14917	3/8	236.39063	3634.50586	3/8	456.89063	9766.03711
3/4	95.06250	926.85938	1/2	240.25000	3723.87500	1/2	462.25000	9938.37500
13/16	96.28516	944.79810	5/8	244.14063	3814.69727	5/8	467.64063	10112.72852
7/8	97.51563	962.96680	3/4	248.06250	3906.98438	3/4	473.06250	10289.10938
15/16	98.75391	981.36694	7/8	252.01563	4000.74805	7/8	478.51563	10467.52930

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 22 to 39 7/8

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
22	484.00000	10648.00000	28	784.00000	21952.00000	34	1156.00000	39304.00000
1/8	489.51563	10830.53320	1/8	791.01563	22247.31445	1/8	1164.51563	39739.09570
1/4	495.06250	11015.14063	1/4	798.06250	22545.26563	1/4	1173.06250	40177.39063
3/8	500.64063	11201.83398	3/8	805.14063	22845.86523	3/8	1181.64063	40618.89648
1/2	506.25000	11390.62500	1/2	812.25000	23149.12500	1/2	1190.25000	41063.62500
5/8	511.89063	11581.52539	5/8	819.39063	23455.05664	5/8	1198.89063	41511.58789
3/4	517.56250	11774.54688	3/4	826.56250	23763.67188	3/4	1207.56250	41962.79688
7/8	523.26563	11969.70117	7/8	833.76563	24074.98242	7/8	1216.26563	42417.26367
23	529.00000	12167.00000	29	841.00000	24389.00000	35	1225.00000	42875.00000
1/8	534.76563	12366.45508	1/8	848.26563	24705.73633	1/8	1233.76563	43336.01758
1/4	540.56250	12568.07813	1/4	855.56250	25025.20313	1/4	1242.56250	43800.32813
3/8	546.39063	12771.88086	3/8	862.89063	25347.41211	3/8	1251.39063	44267.94336
1/2	552.25000	12977.87500	1/2	870.25000	25672.37500	1/2	1260.25000	44738.87500
5/8	558.14063	13186.07227	5/8	877.64063	26000.10352	5/8	1269.14063	45213.13477
3/4	564.06250	13396.48438	3/4	885.06250	26330.60938	3/4	1278.06250	45690.73438
7/8	570.01563	13609.12305	7/8	892.51563	26663.90430	7/8	1287.01563	46171.68555
24	576.00000	13824.00000	30	900.00000	27000.00000	36	1296.00000	46656.00000
1/8	582.01563	14041.12695	1/8	907.51563	27338.90820	1/8	1305.01563	47143.68945
1/4	588.06250	14260.51563	1/4	915.06250	27680.64063	1/4	1314.06250	47634.76563
3/8	594.14063	14482.17773	3/8	922.64063	28025.20898	3/8	1323.14063	48129.24023
1/2	600.25000	14706.12500	1/2	930.25000	28372.62500	1/2	1332.25000	48627.12500
5/8	606.39063	14932.36914	5/8	937.89063	28722.90039	5/8	1341.39063	49128.43164
3/4	612.56250	15160.92188	3/4	945.56250	29076.04688	3/4	1350.56250	49633.17188
7/8	618.76563	15391.79492	7/8	953.26563	29432.07617	7/8	1359.76563	50141.35742
25	625.00000	15625.00000	31	961.00000	29791.00000	37	1369.00000	50653.00000
1/8	631.26563	15860.54883	1/8	968.76563	30152.83008	1/8	1378.26563	51168.11133
1/4	637.56250	16098.45313	1/4	976.56250	30517.57813	1/4	1387.56250	51686.70313
3/8	643.89063	16338.72461	3/8	984.39063	30885.25586	3/8	1396.89063	52208.78711
1/2	650.25000	16581.37500	1/2	992.25000	31255.87500	1/2	1406.25000	52734.37500
5/8	656.64063	16826.41602	5/8	1000.14063	31629.44727	5/8	1415.64063	53263.47852
3/4	663.06250	17073.85938	3/4	1008.06250	32005.98438	3/4	1425.06250	53796.10938
7/8	669.51563	17323.71680	7/8	1016.01563	32385.49805	7/8	1434.51563	54332.27930
26	676.00000	17576.00000	32	1024.00000	32768.00000	38	1444.00000	54872.00000
1/8	682.51563	17830.72070	1/8	1032.01563	33153.50195	1/8	1453.51563	55415.28320
1/4	689.06250	18087.89063	1/4	1040.06250	33542.01563	1/4	1463.06250	55962.14063
3/8	695.64063	18347.52148	3/8	1048.14063	33933.55273	3/8	1472.64063	56512.58398
1/2	702.25000	18609.62500	1/2	1056.25000	34328.12500	1/2	1482.25000	57066.62500
5/8	708.89063	18874.21289	5/8	1064.39063	34725.74414	5/8	1491.89063	57624.27539
3/4	715.56250	19141.29688	3/4	1072.56250	35126.42188	3/4	1501.56250	58185.54688
7/8	722.26563	19410.88867	7/8	1080.76563	35530.16992	7/8	1511.26563	58750.45117
27	729.00000	19683.00000	33	1089.00000	35937.00000	39	1521.00000	59319.00000
1/8	735.76563	19957.64258	1/8	1097.26563	36346.92383	1/8	1530.76563	59891.20508
1/4	742.56250	20234.82813	1/4	1105.56250	36759.95313	1/4	1540.56250	60467.07813
3/8	749.39063	20514.56836	3/8	1113.89063	37176.09961	3/8	1550.39063	61046.63086
1/2	756.25000	20796.87500	1/2	1122.25000	37595.37500	1/2	1560.25000	61629.87500
5/8	763.14063	21081.75977	5/8	1130.64063	38017.79102	5/8	1570.14063	62216.82227
3/4	770.06250	21369.23438	3/4	1139.06250	38443.35938	3/4	1580.06250	62807.48438
7/8	777.01563	21659.31055	7/8	1147.51563	38872.09180	7/8	1590.01563	63401.87305

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 40 to 57 7/8

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
40	1600.00000	64000.00000	46	2116.00000	97336.00000	52	2704.00000	140608.00000
1/8	1610.01563	64601.87695	1/8	2127.51563	98131.65820	1/8	2717.01563	141624.43945
1/4	1620.06250	65207.51563	1/4	2139.06250	98931.64063	1/4	2730.06250	142645.76563
3/8	1630.14063	65816.92773	3/8	2150.64063	99735.95898	3/8	2743.14063	143671.99023
1/2	1640.25000	66430.12500	1/2	2162.25000	100544.62500	1/2	2756.25000	144703.12500
5/8	1650.39063	67047.11914	5/8	2173.89063	101357.65039	5/8	2769.39063	145739.18164
3/4	1660.56250	67667.92188	3/4	2185.56250	102175.04688	3/4	2782.56250	146780.17188
7/8	1670.76563	68292.54492	7/8	2197.26563	102996.82617	7/8	2795.76563	147826.10742
41	1681.00000	68921.00000	47	2209.00000	103823.00000	53	2809.00000	148877.00000
1/8	1691.26563	69553.29883	1/8	2220.76563	104653.58008	1/8	2822.26563	149932.86133
1/4	1701.56250	70189.45313	1/4	2232.56250	105488.57813	1/4	2835.56250	150993.70313
3/8	1711.89063	70829.47461	3/8	2244.39063	106328.00586	3/8	2848.89063	152059.53711
1/2	1722.25000	71473.37500	1/2	2256.25000	107171.87500	1/2	2862.25000	153130.37500
5/8	1732.64063	72121.16602	5/8	2268.14063	108020.19727	5/8	2875.64063	154206.22852
3/4	1743.06250	72772.85938	3/4	2280.06250	108872.98438	3/4	2889.06250	155287.10938
7/8	1753.51563	73428.46680	7/8	2292.01563	109730.24805	7/8	2902.51563	156373.02930
42	1764.00000	74088.00000	48	2304.00000	110592.00000	54	2916.00000	157464.00000
1/8	1774.51563	74751.47070	1/8	2316.01563	111458.25195	1/8	2929.51563	158560.03320
1/4	1785.06250	75418.89063	1/4	2328.06250	112329.01563	1/4	2943.06250	159661.14063
3/8	1795.64063	76090.27148	3/8	2340.14063	113204.30273	3/8	2956.64063	160767.33398
1/2	1806.25000	76765.62500	1/2	2352.25000	114084.12500	1/2	2970.25000	161878.62500
5/8	1816.89063	77444.96289	5/8	2364.39063	114968.49414	5/8	2983.89063	162995.02539
3/4	1827.56250	78128.29688	3/4	2376.56250	115857.42188	3/4	2997.56250	164116.54688
7/8	1838.26563	78815.63867	7/8	2388.76563	116750.91992	7/8	3011.26563	165243.20117
43	1849.00000	79507.00000	49	2401.00000	117649.00000	55	3025.00000	166375.00000
1/8	1859.76563	80202.39258	1/8	2413.26563	118551.67383	1/8	3038.76563	167511.95508
1/4	1870.56250	80901.82813	1/4	2425.56250	119458.95313	1/4	3052.56250	168654.07813
3/8	1881.39063	81605.31836	3/8	2437.89063	120370.84961	3/8	3066.39063	169801.38086
1/2	1892.25000	82312.87500	1/2	2450.25000	121287.37500	1/2	3080.25000	170953.87500
5/8	1903.14063	83024.50977	5/8	2462.64063	122208.54102	5/8	3094.14063	172111.57227
3/4	1914.06250	83740.23438	3/4	2475.06250	123134.35938	3/4	3108.06250	173274.48438
7/8	1925.01563	84460.06055	7/8	2487.51563	124064.84180	7/8	3122.01563	174442.62305
44	1936.00000	85184.00000	50	2500.00000	125000.00000	56	3136.00000	175616.00000
1/8	1947.01563	85912.06445	1/8	2512.51563	125939.84570	1/8	3150.01563	176794.62695
1/4	1958.06250	86644.26563	1/4	2525.06250	126884.39063	1/4	3164.06250	177978.51563
3/8	1969.14063	87380.61523	3/8	2537.64063	127833.64648	3/8	3178.14063	179167.67773
1/2	1980.25000	88121.12500	1/2	2550.25000	128787.62500	1/2	3192.25000	180362.12500
5/8	1991.39063	88865.80664	5/8	2562.89063	129746.33789	5/8	3206.39063	181561.86914
3/4	2002.56250	89614.67188	3/4	2575.56250	130709.79688	3/4	3220.56250	182766.92188
7/8	2013.76563	90367.73242	7/8	2588.26563	131678.01367	7/8	3234.76563	183977.29492
45	2025.00000	91125.00000	51	2601.00000	132651.00000	57	3249.00000	185193.00000
1/8	2036.26563	91886.48633	1/8	2613.76563	133628.76758	1/8	3263.26563	186414.04883
1/4	2047.56250	92652.20313	1/4	2626.56250	134611.32813	1/4	3277.56250	187640.45313
3/8	2058.89063	93422.16211	3/8	2639.39063	135598.69336	3/8	3291.89063	188872.22461
1/2	2070.25000	94196.37500	1/2	2652.25000	136590.87500	1/2	3306.25000	190109.37500
5/8	2081.64063	94974.85352	5/8	2665.14063	137587.88477	5/8	3320.64063	191351.91602
3/4	2093.06250	95757.60938	3/4	2678.06250	138589.73438	3/4	3335.06250	192599.85938
7/8	2104.51563	96544.65430	7/8	2691.01563	139596.43555	7/8	3349.51563	193853.21680

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 58 to 75⅞

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
58	3364.00000	195112.00000	64	4096.00000	262144.00000	70	4900.00000	343000.00000
⅛	3378.51563	196376.22070	⅛	4112.01563	263683.00195	⅛	4917.51563	344840.78320
¼	3393.06250	197645.89063	¼	4128.06250	265228.01563	¼	4935.06250	346688.14063
⅜	3407.64063	198921.02148	⅜	4144.14063	266779.05273	⅜	4952.64063	348542.08398
½	3422.25000	200201.62500	½	4160.25000	268336.12500	½	4970.25000	350402.62500
⅝	3436.89063	201487.71289	⅝	4176.39063	269899.24414	⅝	4987.89063	352269.77539
¾	3451.56250	202779.29688	¾	4192.56250	271468.42188	¾	5005.56250	354143.54688
⅞	3466.26563	204076.38867	⅞	4208.76563	273043.66992	⅞	5023.26563	356023.95117
59	3481.00000	205379.00000	65	4225.00000	274625.00000	71	5041.00000	357911.00000
⅛	3495.76563	206687.14258	⅛	4241.26563	276212.42383	⅛	5058.76563	359804.70508
¼	3510.56250	208000.82813	¼	4257.56250	277805.95313	¼	5076.56250	361705.07813
⅜	3525.39063	209320.06836	⅜	4273.89063	279405.59961	⅜	5094.39063	363612.13086
½	3540.25000	210644.87500	½	4290.25000	281011.37500	½	5112.25000	365525.87500
⅝	3555.14063	211975.25977	⅝	4306.64063	282623.29102	⅝	5130.14063	367446.32227
¾	3570.06250	213311.23438	¾	4323.06250	284241.35938	¾	5148.06250	369373.48438
⅞	3585.01563	214652.81055	⅞	4339.51563	285865.59180	⅞	5166.01563	371307.37305
60	3600.00000	216000.00000	66	4356.00000	287496.00000	72	5184.00000	373248.00000
⅛	3615.01563	217352.81445	⅛	4372.51563	289132.59570	⅛	5202.01563	375195.37695
¼	3630.06250	218711.26563	¼	4389.06250	290775.39063	¼	5220.06250	377149.51563
⅜	3645.14063	220075.36523	⅜	4405.64063	292424.39648	⅜	5238.14063	379110.42773
½	3660.25000	221445.12500	½	4422.25000	294079.62500	½	5256.25000	381078.12500
⅝	3675.39063	222820.55664	⅝	4438.89063	295741.08789	⅝	5274.39063	383052.61914
¾	3690.56250	224201.67188	¾	4455.56250	297408.79688	¾	5292.56250	385033.92188
⅞	3705.76563	225588.48242	⅞	4472.26563	299082.76367	⅞	5310.76563	387022.04492
61	3721.00000	226981.00000	67	4489.00000	300763.00000	73	5329.00000	389017.00000
⅛	3736.26563	228379.23633	⅛	4505.76563	302449.51758	⅛	5347.26563	391018.79883
¼	3751.56250	229783.20313	¼	4522.56250	304142.32813	¼	5365.56250	393027.45313
⅜	3766.89063	231192.91211	⅜	4539.39063	305841.44336	⅜	5383.89063	395042.97461
½	3782.25000	232608.37500	½	4556.25000	307546.87500	½	5402.25000	397065.37500
⅝	3797.64063	234029.60352	⅝	4573.14063	309258.63477	⅝	5420.64063	399094.66602
¾	3813.06250	235456.60938	¾	4590.06250	310976.73438	¾	5439.06250	401130.85938
⅞	3828.51563	236889.40430	⅞	4607.01563	312701.18555	⅞	5457.51563	403173.96680
62	3844.00000	238328.00000	68	4624.00000	314432.00000	74	5476.00000	405224.00000
⅛	3859.51563	239772.40820	⅛	4641.01563	316169.18945	⅛	5494.51563	407280.97070
¼	3875.06250	241222.64063	¼	4658.06250	317912.76563	¼	5513.06250	409344.89063
⅜	3890.64063	242678.70898	⅜	4675.14063	319662.74023	⅜	5531.64063	411415.77148
½	3906.25000	244140.62500	½	4692.25000	321419.12500	½	5550.25000	413493.62500
⅝	3921.89063	245608.40039	⅝	4709.39063	323181.93164	⅝	5568.89063	415578.46289
¾	3937.56250	247082.04688	¾	4726.56250	324951.17188	¾	5587.56250	417670.29688
⅞	3953.26563	248561.57617	⅞	4743.76563	326726.85742	⅞	5606.26563	419769.13867
63	3969.00000	250047.00000	69	4761.00000	328509.00000	75	5625.00000	421875.00000
⅛	3984.76563	251538.33008	⅛	4778.26563	330297.61133	⅛	5643.76563	423987.89258
¼	4000.56250	253035.57813	¼	4795.56250	332092.70313	¼	5662.56250	426107.82813
⅜	4016.39063	254538.75586	⅜	4812.89063	333894.28711	⅜	5681.39063	428234.81836
½	4032.25000	256047.87500	½	4830.25000	335702.37500	½	5700.25000	430368.87500
⅝	4048.14063	257562.94727	⅝	4847.64063	337516.97852	⅝	5719.14063	432510.00977
¾	4064.06250	259083.98438	¾	4865.06250	339338.10938	¾	5738.06250	434658.23438
⅞	4080.01563	260610.99805	⅞	4882.51563	341165.77930	⅞	5757.01563	436813.56055

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 76 to 93⅞

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
76	5776.00000	438976.00000	82	6724.00000	551368.00000	88	7744.00000	681472.00000
1/8	5795.01563	441145.56445	1/8	6744.51563	553893.34570	1/8	7766.01563	684380.12695
1/4	5814.06250	443322.26563	1/4	6765.06250	556426.39063	1/4	7788.06250	687296.51563
3/8	5833.14063	445506.11523	3/8	6785.64063	558967.14648	3/8	7810.14063	690221.17773
1/2	5852.25000	447697.12500	1/2	6806.25000	561515.62500	1/2	7832.25000	693154.12500
5/8	5871.39063	449895.30664	5/8	6826.89063	564071.83789	5/8	7854.39063	696095.36914
3/4	5890.56250	452100.67188	3/4	6847.56250	566635.79688	3/4	7876.56250	699044.92188
7/8	5909.76563	454313.23242	7/8	6868.26563	569207.51367	7/8	7898.76563	702002.79492
77	5929.00000	456533.00000	83	6889.00000	571787.00000	89	7921.00000	704969.00000
1/8	5948.26563	458759.98633	1/8	6909.76563	574374.26758	1/8	7943.26563	707943.54883
1/4	5967.56250	460994.20313	1/4	6930.56250	576969.32813	1/4	7965.56250	710926.45313
3/8	5986.89063	463235.66211	3/8	6951.39063	579572.19336	3/8	7987.89063	713917.72461
1/2	6006.25000	465484.37500	1/2	6972.25000	582182.87500	1/2	8010.25000	716917.37500
5/8	6025.64063	467740.35352	5/8	6993.14063	584801.38477	5/8	8032.64063	719925.41602
3/4	6045.06250	470003.60938	3/4	7014.06250	587427.73438	3/4	8055.06250	722941.85938
7/8	6064.51563	472274.15430	7/8	7035.01563	590061.93555	7/8	8077.51563	725966.71680
78	6084.00000	474552.00000	84	7056.00000	592704.00000	90	8100.00000	729000.00000
1/8	6103.51563	476837.15820	1/8	7077.01563	595353.93945	1/8	8122.51563	732041.72070
1/4	6123.06250	479129.64063	1/4	7098.06250	598011.76563	1/4	8145.06250	735091.89063
3/8	6142.64063	481429.45898	3/8	7119.14063	600677.49023	3/8	8167.64063	738150.52148
1/2	6162.25000	483736.62500	1/2	7140.25000	603351.12500	1/2	8190.25000	741217.62500
5/8	6181.89063	486051.15039	5/8	7161.39063	606032.68164	5/8	8212.89063	744293.21289
3/4	6201.56250	488373.04688	3/4	7182.56250	608722.17188	3/4	8235.56250	747377.29688
7/8	6221.26563	490702.32617	7/8	7203.76563	611419.60742	7/8	8258.26563	750469.88867
79	6241.00000	493039.00000	85	7225.00000	614125.00000	91	8281.00000	753571.00000
1/8	6260.76563	495383.08008	1/8	7246.26563	616838.36133	1/8	8303.76563	756680.64258
1/4	6280.56250	497734.57813	1/4	7267.56250	619559.70313	1/4	8326.56250	759798.82813
3/8	6300.39063	500093.50586	3/8	7288.89063	622289.03711	3/8	8349.39063	762925.56836
1/2	6320.25000	502459.87500	1/2	7310.25000	625026.37500	1/2	8372.25000	766060.87500
5/8	6340.14063	504833.69727	5/8	7331.64063	627771.72852	5/8	8395.14063	769204.75977
3/4	6360.06250	507214.98438	3/4	7353.06250	630525.10938	3/4	8418.06250	772357.23438
7/8	6380.01563	509603.74805	7/8	7374.51563	633286.52930	7/8	8441.01563	775518.31055
80	6400.00000	512000.00000	86	7396.00000	636056.00000	92	8464.00000	778688.00000
1/8	6420.01563	514403.75195	1/8	7417.51563	638833.53320	1/8	8487.01563	781866.31445
1/4	6440.06250	516815.01563	1/4	7439.06250	641619.14063	1/4	8510.06250	785053.26563
3/8	6460.14063	519233.80273	3/8	7460.64063	644412.83398	3/8	8533.14063	788248.86523
1/2	6480.25000	521660.12500	1/2	7482.25000	647214.62500	1/2	8556.25000	791453.12500
5/8	6500.39063	524093.99414	5/8	7503.89063	650024.52539	5/8	8579.39063	794666.05664
3/4	6520.56250	526535.42188	3/4	7525.56250	652842.54688	3/4	8602.56250	797887.67188
7/8	6540.76563	528984.41992	7/8	7547.26563	655668.70117	7/8	8625.76563	801117.98242
81	6561.00000	531441.00000	87	7569.00000	658503.00000	93	8649.00000	804357.00000
1/8	6581.26563	533905.17383	1/8	7590.76563	661345.45508	1/8	8672.26563	807604.73633
1/4	6601.56250	536376.95313	1/4	7612.56250	664196.07813	1/4	8695.56250	810861.20313
3/8	6621.89063	538856.34961	3/8	7634.39063	667054.88086	3/8	8718.89063	814126.41211
1/2	6642.25000	541343.37500	1/2	7656.25000	669921.87500	1/2	8742.25000	817400.37500
5/8	6662.64063	543838.04102	5/8	7678.14063	672797.07227	5/8	8765.64063	820683.10352
3/4	6683.06250	546340.35938	3/4	7700.06250	675680.48438	3/4	8789.06250	823974.60938
7/8	6703.51563	548850.34180	7/8	7722.01563	678572.12305	7/8	8812.51563	827274.90430

Copyright 2004, Industrial Press, Inc., New York, NY

Squares and Cubes of Numbers from 94 to 100

No.	Square	Cube	No.	Square	Cube	No.	Square	Cube
94	8836.00000	830584.00000	96	9216.00000	884736.00000	98	9604.00000	941192.00000
1/8	8859.51563	833901.90820	1/8	9240.01563	888196.50195	1/8	9628.51563	944798.09570
1/4	8883.06250	837228.64063	1/4	9264.06250	891666.01563	1/4	9653.06250	948413.39063
3/8	8906.64063	840564.20898	3/8	9288.14063	895144.55273	3/8	9677.64063	952037.89648
1/2	8930.25000	843908.62500	1/2	9312.25000	898632.12500	1/2	9702.25000	955671.62500
5/8	8953.89063	847261.90039	5/8	9336.39063	902128.74414	5/8	9726.89063	959314.58789
3/4	8977.56250	850624.04688	3/4	9360.56250	905634.42188	3/4	9751.56250	962966.79688
7/8	9001.26563	853995.07617	7/8	9384.76563	909149.16992	7/8	9776.26563	966628.26367
95	9025.00000	857375.00000	97	9409.00000	912673.00000	99	9801.00000	970299.00000
1/8	9048.76563	860763.83008	1/8	9433.26563	916205.92383	1/8	9825.76563	973979.01758
1/4	9072.56250	864161.57813	1/4	9457.56250	919747.95313	1/4	9850.56250	977668.32813
3/8	9096.39063	867568.25586	3/8	9481.89063	923299.09961	3/8	9875.39063	981366.94336
1/2	9120.25000	870983.87500	1/2	9506.25000	926859.37500	1/2	9900.25000	985074.87500
5/8	9144.14063	874408.44727	5/8	9530.64063	930428.79102	5/8	9925.14063	988792.13477
3/4	9168.06250	877841.98438	3/4	9555.06250	934007.35938	3/4	9950.06250	992518.73438
7/8	9192.01563	881284.49805	7/8	9579.51563	937595.09180	7/8	9975.01563	996254.68555
						100	10,000.00	1,000,000

Fractions of Pi (π)

Table of Fractions of $\pi = 3.14159265$

a	π/a	a	π/a	a	π/a	a	π/a	a	π/a
1	3.14159	21	0.14960	41	0.07662	61	0.05150	81	0.03879
2	1.57080	22	0.14280	42	0.07480	62	0.05067	82	0.03831
3	1.04720	23	0.13659	43	0.07306	63	0.04987	83	0.03785
4	0.78540	24	0.13090	44	0.07140	64	0.04909	84	0.03740
5	0.62832	25	0.12566	45	0.06981	65	0.04833	85	0.03696
6	0.52360	26	0.12083	46	0.06830	66	0.04760	86	0.03653
7	0.44880	27	0.11636	47	0.06684	67	0.04689	87	0.03611
8	0.39270	28	0.11220	48	0.06545	68	0.04620	88	0.03570
9	0.34907	29	0.10833	49	0.06411	69	0.04553	89	0.03530
10	0.31416	30	0.10472	50	0.06283	70	0.04488	90	0.03491
11	0.28560	31	0.10134	51	0.06160	71	0.04425	91	0.03452
12	0.26180	32	0.09817	52	0.06042	72	0.04363	92	0.03415
13	0.24166	33	0.09520	53	0.05928	73	0.04304	93	0.03378
14	0.22440	34	0.09240	54	0.05818	74	0.04245	94	0.03342
15	0.20944	35	0.08976	55	0.05712	75	0.04189	95	0.03307
16	0.19635	36	0.08727	56	0.05610	76	0.04134	96	0.03272
17	0.18480	37	0.08491	57	0.05512	77	0.04080	97	0.03239
18	0.17453	38	0.08267	58	0.05417	78	0.04028	98	0.03206
19	0.16535	39	0.08055	59	0.05325	79	0.03977	99	0.03173
20	0.15708	40	0.07854	60	0.05236	80	0.03927	100	0.03142

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals

Powers, Roots, and Reciprocals From 1 to 50

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1	1	1	1.00000	1.00000	1.0000000	1
2	4	8	1.41421	1.25992	0.5000000	2
3	9	27	1.73205	1.44225	0.3333333	3
4	16	64	2.00000	1.58740	0.2500000	4
5	25	125	2.23607	1.70998	0.2000000	5
6	36	216	2.44949	1.81712	0.1666667	6
7	49	343	2.64575	1.91293	0.1428571	7
8	64	512	2.82843	2.00000	0.1250000	8
9	81	729	3.00000	2.08008	0.1111111	9
10	100	1000	3.16228	2.15443	0.1000000	10
11	121	1331	3.31662	2.22398	0.0909091	11
12	144	1728	3.46410	2.28943	0.0833333	12
13	169	2197	3.60555	2.35133	0.0769231	13
14	196	2744	3.74166	2.41014	0.0714286	14
15	225	3375	3.87298	2.46621	0.0666667	15
16	256	4096	4.00000	2.51984	0.0625000	16
17	289	4913	4.12311	2.57128	0.0588235	17
18	324	5832	4.24264	2.62074	0.0555556	18
19	361	6859	4.35890	2.66840	0.0526316	19
20	400	8000	4.47214	2.71442	0.0500000	20
21	441	9261	4.58258	2.75892	0.0476190	21
22	484	10648	4.69042	2.80204	0.0454545	22
23	529	12167	4.79583	2.84387	0.0434783	23
24	576	13824	4.89898	2.88450	0.0416667	24
25	625	15625	5.00000	2.92402	0.0400000	25
26	676	17576	5.09902	2.96250	0.0384615	26
27	729	19683	5.19615	3.00000	0.0370370	27
28	784	21952	5.29150	3.03659	0.0357143	28
29	841	24389	5.38516	3.07232	0.0344828	29
30	900	27000	5.47723	3.10723	0.0333333	30
31	961	29791	5.56776	3.14138	0.0322581	31
32	1024	32768	5.65685	3.17480	0.0312500	32
33	1089	35937	5.74456	3.20753	0.0303030	33
34	1156	39304	5.83095	3.23961	0.0294118	34
35	1225	42875	5.91608	3.27107	0.0285714	35
36	1296	46656	6.00000	3.30193	0.0277778	36
37	1369	50653	6.08276	3.33222	0.0270270	37
38	1444	54872	6.16441	3.36198	0.0263158	38
39	1521	59319	6.24500	3.39121	0.0256410	39
40	1600	64000	6.32456	3.41995	0.0250000	40
41	1681	68921	6.40312	3.44822	0.0243902	41
42	1764	74088	6.48074	3.47603	0.0238095	42
43	1849	79507	6.55744	3.50340	0.0232558	43
44	1936	85184	6.63325	3.53035	0.0227273	44
45	2025	91125	6.70820	3.55689	0.0222222	45
46	2116	97336	6.78233	3.58305	0.0217391	46
47	2209	103823	6.85565	3.60883	0.0212766	47
48	2304	110592	6.92820	3.63424	0.0208333	48
49	2401	117649	7.00000	3.65931	0.0204082	49
50	2500	125000	7.07107	3.68403	0.0200000	50

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 51 to 100

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
51	2601	132651	7.14143	3.70843	0.0196078	51
52	2704	140608	7.21110	3.73251	0.0192308	52
53	2809	148877	7.28011	3.75629	0.0188679	53
54	2916	157464	7.34847	3.77976	0.0185185	54
55	3025	166375	7.41620	3.80295	0.0181818	55
56	3136	175616	7.48331	3.82586	0.0178571	56
57	3249	185193	7.54983	3.84850	0.0175439	57
58	3364	195112	7.61577	3.87088	0.0172414	58
59	3481	205379	7.68115	3.89300	0.0169492	59
60	3600	216000	7.74597	3.91487	0.0166667	60
61	3721	226981	7.81025	3.93650	0.0163934	61
62	3844	238328	7.87401	3.95789	0.0161290	62
63	3969	250047	7.93725	3.97906	0.0158730	63
64	4096	262144	8.00000	4.00000	0.0156250	64
65	4225	274625	8.06226	4.02073	0.0153846	65
66	4356	287496	8.12404	4.04124	0.0151515	66
67	4489	300763	8.18535	4.06155	0.0149254	67
68	4624	314432	8.24621	4.08166	0.0147059	68
69	4761	328509	8.30662	4.10157	0.0144928	69
70	4900	343000	8.36660	4.12129	0.0142857	70
71	5041	357911	8.42615	4.14082	0.0140845	71
72	5184	373248	8.48528	4.16017	0.0138889	72
73	5329	389017	8.54400	4.17934	0.0136986	73
74	5476	405224	8.60233	4.19834	0.0135135	74
75	5625	421875	8.66025	4.21716	0.0133333	75
76	5776	438976	8.71780	4.23582	0.0131579	76
77	5929	456533	8.77496	4.25432	0.0129870	77
78	6084	474552	8.83176	4.27266	0.0128205	78
79	6241	493039	8.88819	4.29084	0.0126582	79
80	6400	512000	8.94427	4.30887	0.0125000	80
81	6561	531441	9.00000	4.32675	0.0123457	81
82	6724	551368	9.05539	4.34448	0.0121951	82
83	6889	571787	9.11043	4.36207	0.0120482	83
84	7056	592704	9.16515	4.37952	0.0119048	84
85	7225	614125	9.21954	4.39683	0.0117647	85
86	7396	636056	9.27362	4.41400	0.0116279	86
87	7569	658503	9.32738	4.43105	0.0114943	87
88	7744	681472	9.38083	4.44796	0.0113636	88
89	7921	704969	9.43398	4.46475	0.0112360	89
90	8100	729000	9.48683	4.48140	0.0111111	90
91	8281	753571	9.53939	4.49794	0.0109890	91
92	8464	778688	9.59166	4.51436	0.0108696	92
93	8649	804357	9.64365	4.53065	0.0107527	93
94	8836	830584	9.69536	4.54684	0.0106383	94
95	9025	857375	9.74679	4.56290	0.0105263	95
96	9216	884736	9.79796	4.57886	0.0104167	96
97	9409	912673	9.84886	4.59470	0.0103093	97
98	9604	941192	9.89949	4.61044	0.0102041	98
99	9801	970299	9.94987	4.62607	0.0101010	99
100	10000	1000000	10.00000	4.64159	0.0100000	100

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 101 to 150

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
101	10201	1030301	10.04988	4.65701	0.0099010	101
102	10404	1061208	10.09950	4.67233	0.0098039	102
103	10609	1092727	10.14889	4.68755	0.0097087	103
104	10816	1124864	10.19804	4.70267	0.0096154	104
105	11025	1157625	10.24695	4.71769	0.0095238	105
106	11236	1191016	10.29563	4.73262	0.0094340	106
107	11449	1225043	10.34408	4.74746	0.0093458	107
108	11664	1259712	10.39230	4.76220	0.0092593	108
109	11881	1295029	10.44031	4.77686	0.0091743	109
110	12100	1331000	10.48809	4.79142	0.0090909	110
111	12321	1367631	10.53565	4.80590	0.0090090	111
112	12544	1404928	10.58301	4.82028	0.0089286	112
113	12769	1442897	10.63015	4.83459	0.0088496	113
114	12996	1481544	10.67708	4.84881	0.0087719	114
115	13225	1520875	10.72381	4.86294	0.0086957	115
116	13456	1560896	10.77033	4.87700	0.0086207	116
117	13689	1601613	10.81665	4.89097	0.0085470	117
118	13924	1643032	10.86278	4.90487	0.0084746	118
119	14161	1685159	10.90871	4.91868	0.0084034	119
120	14400	1728000	10.95445	4.93242	0.0083333	120
121	14641	1771561	11.00000	4.94609	0.0082645	121
122	14884	1815848	11.04536	4.95968	0.0081967	122
123	15129	1860867	11.09054	4.97319	0.0081301	123
124	15376	1906624	11.13553	4.98663	0.0080645	124
125	15625	1953125	11.18034	5.00000	0.0080000	125
126	15876	2000376	11.22497	5.01330	0.0079365	126
127	16129	2048383	11.26943	5.02653	0.0078740	127
128	16384	2097152	11.31371	5.03968	0.0078125	128
129	16641	2146689	11.35782	5.05277	0.0077519	129
130	16900	2197000	11.40175	5.06580	0.0076923	130
131	17161	2248091	11.44552	5.07875	0.0076336	131
132	17424	2299968	11.48913	5.09164	0.0075758	132
133	17689	2352637	11.53256	5.10447	0.0075188	133
134	17956	2406104	11.57584	5.11723	0.0074627	134
135	18225	2460375	11.61895	5.12993	0.0074074	135
136	18496	2515456	11.66190	5.14256	0.0073529	136
137	18769	2571353	11.70470	5.15514	0.0072993	137
138	19044	2628072	11.74734	5.16765	0.0072464	138
139	19321	2685619	11.78983	5.18010	0.0071942	139
140	19600	2744000	11.83216	5.19249	0.0071429	140
141	19881	2803221	11.87434	5.20483	0.0070922	141
142	20164	2863288	11.91638	5.21710	0.0070423	142
143	20449	2924207	11.95826	5.22932	0.0069930	143
144	20736	2985984	12.00000	5.24148	0.0069444	144
145	21025	3048625	12.04159	5.25359	0.0068966	145
146	21316	3112136	12.08305	5.26564	0.0068493	146
147	21609	3176523	12.12436	5.27763	0.0068027	147
148	21904	3241792	12.16553	5.28957	0.0067568	148
149	22201	3307949	12.20656	5.30146	0.0067114	149
150	22500	3375000	12.24745	5.31329	0.0066667	150

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 151 to 200

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
151	22801	3442951	12.28821	5.32507	0.0066225	151
152	23104	3511808	12.32883	5.33680	0.0065789	152
153	23409	3581577	12.36932	5.34848	0.0065359	153
154	23716	3652264	12.40967	5.36011	0.0064935	154
155	24025	3723875	12.44990	5.37169	0.0064516	155
156	24336	3796416	12.49000	5.38321	0.0064103	156
157	24649	3869893	12.52996	5.39469	0.0063694	157
158	24964	3944312	12.56981	5.40612	0.0063291	158
159	25281	4019679	12.60952	5.41750	0.0062893	159
160	25600	4096000	12.64911	5.42884	0.0062500	160
161	25921	4173281	12.68858	5.44012	0.0062112	161
162	26244	4251528	12.72792	5.45136	0.0061728	162
163	26569	4330747	12.76715	5.46256	0.0061350	163
164	26896	4410944	12.80625	5.47370	0.0060976	164
165	27225	4492125	12.84523	5.48481	0.0060606	165
166	27556	4574296	12.88410	5.49586	0.0060241	166
167	27889	4657463	12.92285	5.50688	0.0059880	167
168	28224	4741632	12.96148	5.51785	0.0059524	168
169	28561	4826809	13.00000	5.52877	0.0059172	169
170	28900	4913000	13.03840	5.53966	0.0058824	170
171	29241	5000211	13.07670	5.55050	0.0058480	171
172	29584	5088448	13.11488	5.56130	0.0058140	172
173	29929	5177717	13.15295	5.57205	0.0057803	173
174	30276	5268024	13.19091	5.58277	0.0057471	174
175	30625	5359375	13.22876	5.59344	0.0057143	175
176	30976	5451776	13.26650	5.60408	0.0056818	176
177	31329	5545233	13.30413	5.61467	0.0056497	177
178	31684	5639752	13.34166	5.62523	0.0056180	178
179	32041	5735339	13.37909	5.63574	0.0055866	179
180	32400	5832000	13.41641	5.64622	0.0055556	180
181	32761	5929741	13.45362	5.65665	0.0055249	181
182	33124	6028568	13.49074	5.66705	0.0054945	182
183	33489	6128487	13.52775	5.67741	0.0054645	183
184	33856	6229504	13.56466	5.68773	0.0054348	184
185	34225	6331625	13.60147	5.69802	0.0054054	185
186	34596	6434856	13.63818	5.70827	0.0053763	186
187	34969	6539203	13.67479	5.71848	0.0053476	187
188	35344	6644672	13.71131	5.72865	0.0053191	188
189	35721	6751269	13.74773	5.73879	0.0052910	189
190	36100	6859000	13.78405	5.74890	0.0052632	190
191	36481	6967871	13.82027	5.75897	0.0052356	191
192	36864	7077888	13.85641	5.76900	0.0052083	192
193	37249	7189057	13.89244	5.77900	0.0051813	193
194	37636	7301384	13.92839	5.78896	0.0051546	194
195	38025	7414875	13.96424	5.79889	0.0051282	195
196	38416	7529536	14.00000	5.80879	0.0051020	196
197	38809	7645373	14.03567	5.81865	0.0050761	197
198	39204	7762392	14.07125	5.82848	0.0050505	198
199	39601	7880599	14.10674	5.83827	0.0050251	199
200	40000	8000000	14.14214	5.84804	0.0050000	200

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 201 to 250

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
201	40401	8120601	14.17745	5.85777	0.0049751	201
202	40804	8242408	14.21267	5.86746	0.0049505	202
203	41209	8365427	14.24781	5.87713	0.0049261	203
204	41616	8489664	14.28286	5.88677	0.0049020	204
205	42025	8615125	14.31782	5.89637	0.0048780	205
206	42436	8741816	14.35270	5.90594	0.0048544	206
207	42849	8869743	14.38749	5.91548	0.0048309	207
208	43264	8998912	14.42221	5.92499	0.0048077	208
209	43681	9129329	14.45683	5.93447	0.0047847	209
210	44100	9261000	14.49138	5.94392	0.0047619	210
211	44521	9393931	14.52584	5.95334	0.0047393	211
212	44944	9528128	14.56022	5.96273	0.0047170	212
213	45369	9663597	14.59452	5.97209	0.0046948	213
214	45796	9800344	14.62874	5.98142	0.0046729	214
215	46225	9938375	14.66288	5.99073	0.0046512	215
216	46656	10077696	14.69694	6.00000	0.0046296	216
217	47089	10218313	14.73092	6.00925	0.0046083	217
218	47524	10360232	14.76482	6.01846	0.0045872	218
219	47961	10503459	14.79865	6.02765	0.0045662	219
220	48400	10648000	14.83240	6.03681	0.0045455	220
221	48841	10793861	14.86607	6.04594	0.0045249	221
222	49284	10941048	14.89966	6.05505	0.0045045	222
223	49729	11089567	14.93318	6.06413	0.0044843	223
224	50176	11239424	14.96663	6.07318	0.0044643	224
225	50625	11390625	15.00000	6.08220	0.0044444	225
226	51076	11543176	15.03330	6.09120	0.0044248	226
227	51529	11697083	15.06652	6.10017	0.0044053	227
228	51984	11852352	15.09967	6.10911	0.0043860	228
229	52441	12008989	15.13275	6.11803	0.0043668	229
230	52900	12167000	15.16575	6.12693	0.0043478	230
231	53361	12326391	15.19868	6.13579	0.0043290	231
232	53824	12487168	15.23155	6.14463	0.0043103	232
233	54289	12649337	15.26434	6.15345	0.0042918	233
234	54756	12812904	15.29706	6.16224	0.0042735	234
235	55225	12977875	15.32971	6.17101	0.0042553	235
236	55696	13144256	15.36229	6.17975	0.0042373	236
237	56169	13312053	15.39480	6.18846	0.0042194	237
238	56644	13481272	15.42725	6.19715	0.0042017	238
239	57121	13651919	15.45962	6.20582	0.0041841	239
240	57600	13824000	15.49193	6.21447	0.0041667	240
241	58081	13997521	15.52417	6.22308	0.0041494	241
242	58564	14172488	15.55635	6.23168	0.0041322	242
243	59049	14348907	15.58846	6.24025	0.0041152	243
244	59536	14526784	15.62050	6.24880	0.0040984	244
245	60025	14706125	15.65248	6.25732	0.0040816	245
246	60516	14886936	15.68439	6.26583	0.0040650	246
247	61009	15069223	15.71623	6.27431	0.0040486	247
248	61504	15252992	15.74802	6.28276	0.0040323	248
249	62001	15438249	15.77973	6.29119	0.0040161	249
250	62500	15625000	15.81139	6.29961	0.0040000	250

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 251 to 300

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
251	63001	15813251	15.84298	6.30799	0.0039841	251
252	63504	16003008	15.87451	6.31636	0.0039683	252
253	64009	16194277	15.90597	6.32470	0.0039526	253
254	64516	16387064	15.93738	6.33303	0.0039370	254
255	65025	16581375	15.96872	6.34133	0.0039216	255
256	65536	16777216	16.00000	6.34960	0.0039063	256
257	66049	16974593	16.03122	6.35786	0.0038911	257
258	66564	17173512	16.06238	6.36610	0.0038760	258
259	67081	17373979	16.09348	6.37431	0.0038610	259
260	67600	17576000	16.12452	6.38250	0.0038462	260
261	68121	17779581	16.15549	6.39068	0.0038314	261
262	68644	17984728	16.18641	6.39883	0.0038168	262
263	69169	18191447	16.21727	6.40696	0.0038023	263
264	69696	18399744	16.24808	6.41507	0.0037879	264
265	70225	18609625	16.27882	6.42316	0.0037736	265
266	70756	18821096	16.30951	6.43123	0.0037594	266
267	71289	19034163	16.34013	6.43928	0.0037453	267
268	71824	19248832	16.37071	6.44731	0.0037313	268
269	72361	19465109	16.40122	6.45531	0.0037175	269
270	72900	19683000	16.43168	6.46330	0.0037037	270
271	73441	19902511	16.46208	6.47127	0.0036900	271
272	73984	20123648	16.49242	6.47922	0.0036765	272
273	74529	20346417	16.52271	6.48715	0.0036630	273
274	75076	20570824	16.55295	6.49507	0.0036496	274
275	75625	20796875	16.58312	6.50296	0.0036364	275
276	76176	21024576	16.61325	6.51083	0.0036232	276
277	76729	21253933	16.64332	6.51868	0.0036101	277
278	77284	21484952	16.67333	6.52652	0.0035971	278
279	77841	21717639	16.70329	6.53434	0.0035842	279
280	78400	21952000	16.73320	6.54213	0.0035714	280
281	78961	22188041	16.76305	6.54991	0.0035587	281
282	79524	22425768	16.79286	6.55767	0.0035461	282
283	80089	22665187	16.82260	6.56541	0.0035336	283
284	80656	22906304	16.85230	6.57314	0.0035211	284
285	81225	23149125	16.88194	6.58084	0.0035088	285
286	81796	23393656	16.91153	6.58853	0.0034965	286
287	82369	23639903	16.94107	6.59620	0.0034843	287
288	82944	23887872	16.97056	6.60385	0.0034722	288
289	83521	24137569	17.00000	6.61149	0.0034602	289
290	84100	24389000	17.02939	6.61911	0.0034483	290
291	84681	24642171	17.05872	6.62671	0.0034364	291
292	85264	24897088	17.08801	6.63429	0.0034247	292
293	85849	25153757	17.11724	6.64185	0.0034130	293
294	86436	25412184	17.14643	6.64940	0.0034014	294
295	87025	25672375	17.17556	6.65693	0.0033898	295
296	87616	25934336	17.20465	6.66444	0.0033784	296
297	88209	26198073	17.23369	6.67194	0.0033670	297
298	88804	26463592	17.26268	6.67942	0.0033557	298
299	89401	26730899	17.29162	6.68688	0.0033445	299
300	90000	27000000	17.32051	6.69433	0.0033333	300

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 301 to 350

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
301	90601	27270901	17.34935	6.70176	0.0033223	301
302	91204	27543608	17.37815	6.70917	0.0033113	302
303	91809	27818127	17.40690	6.71657	0.0033003	303
304	92416	28094464	17.43560	6.72395	0.0032895	304
305	93025	28372625	17.46425	6.73132	0.0032787	305
306	93636	28652616	17.49286	6.73866	0.0032680	306
307	94249	28934443	17.52142	6.74600	0.0032573	307
308	94864	29218112	17.54993	6.75331	0.0032468	308
309	95481	29503629	17.57840	6.76061	0.0032362	309
310	96100	29791000	17.60682	6.76790	0.0032258	310
311	96721	30080231	17.63519	6.77517	0.0032154	311
312	97344	30371328	17.66352	6.78242	0.0032051	312
313	97969	30664297	17.69181	6.78966	0.0031949	313
314	98596	30959144	17.72005	6.79688	0.0031847	314
315	99225	31255875	17.74824	6.80409	0.0031746	315
316	99856	31554496	17.77639	6.81128	0.0031646	316
317	100489	31855013	17.80449	6.81846	0.0031546	317
318	101124	32157432	17.83255	6.82562	0.0031447	318
319	101761	32461759	17.86057	6.83277	0.0031348	319
320	102400	32768000	17.88854	6.83990	0.0031250	320
321	103041	33076161	17.91647	6.84702	0.0031153	321
322	103684	33386248	17.94436	6.85412	0.0031056	322
323	104329	33698267	17.97220	6.86121	0.0030960	323
324	104976	34012224	18.00000	6.86829	0.0030864	324
325	105625	34328125	18.02776	6.87534	0.0030769	325
326	106276	34645976	18.05547	6.88239	0.0030675	326
327	106929	34965783	18.08314	6.88942	0.0030581	327
328	107584	35287552	18.11077	6.89643	0.0030488	328
329	108241	35611289	18.13836	6.90344	0.0030395	329
330	108900	35937000	18.16590	6.91042	0.0030303	330
331	109561	36264691	18.19341	6.91740	0.0030211	331
332	110224	36594368	18.22087	6.92436	0.0030120	332
333	110889	36926037	18.24829	6.93130	0.0030030	333
334	111556	37259704	18.27567	6.93823	0.0029940	334
335	112225	37595375	18.30301	6.94515	0.0029851	335
336	112896	37933056	18.33030	6.95205	0.0029762	336
337	113569	38272753	18.35756	6.95894	0.0029674	337
338	114244	38614472	18.38478	6.96582	0.0029586	338
339	114921	38958219	18.41195	6.97268	0.0029499	339
340	115600	39304000	18.43909	6.97953	0.0029412	340
341	116281	39651821	18.46619	6.98637	0.0029326	341
342	116964	40001688	18.49324	6.99319	0.0029240	342
343	117649	40353607	18.52026	7.00000	0.0029155	343
344	118336	40707584	18.54724	7.00680	0.0029070	344
345	119025	41063625	18.57418	7.01358	0.0028986	345
346	119716	41421736	18.60108	7.02035	0.0028902	346
347	120409	41781923	18.62794	7.02711	0.0028818	347
348	121104	42144192	18.65476	7.03385	0.0028736	348
349	121801	42508549	18.68154	7.04058	0.0028653	349
350	122500	42875000	18.70829	7.04730	0.0028571	350

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 351 to 400

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
351	123201	43243551	18.73499	7.05400	0.0028490	351
352	123904	43614208	18.76166	7.06070	0.0028409	352
353	124609	43986977	18.78829	7.06738	0.0028329	353
354	125316	44361864	18.81489	7.07404	0.0028249	354
355	126025	44738875	18.84144	7.08070	0.0028169	355
356	126736	45118016	18.86796	7.08734	0.0028090	356
357	127449	45499293	18.89444	7.09397	0.0028011	357
358	128164	45882712	18.92089	7.10059	0.0027933	358
359	128881	46268279	18.94730	7.10719	0.0027855	359
360	129600	46656000	18.97367	7.11379	0.0027778	360
361	130321	47045881	19.00000	7.12037	0.0027701	361
362	131044	47437928	19.02630	7.12694	0.0027624	362
363	131769	47832147	19.05256	7.13349	0.0027548	363
364	132496	48228544	19.07878	7.14004	0.0027473	364
365	133225	48627125	19.10497	7.14657	0.0027397	365
366	133956	49027896	19.13113	7.15309	0.0027322	366
367	134689	49430863	19.15724	7.15960	0.0027248	367
368	135424	49836032	19.18333	7.16610	0.0027174	368
369	136161	50243409	19.20937	7.17258	0.0027100	369
370	136900	50653000	19.23538	7.17905	0.0027027	370
371	137641	51064811	19.26136	7.18552	0.0026954	371
372	138384	51478848	19.28730	7.19197	0.0026882	372
373	139129	51895117	19.31321	7.19840	0.0026810	373
374	139876	52313624	19.33908	7.20483	0.0026738	374
375	140625	52734375	19.36492	7.21125	0.0026667	375
376	141376	53157376	19.39072	7.21765	0.0026596	376
377	142129	53582633	19.41649	7.22405	0.0026525	377
378	142884	54010152	19.44222	7.23043	0.0026455	378
379	143641	54439939	19.46792	7.23680	0.0026385	379
380	144400	54872000	19.49359	7.24316	0.0026316	380
381	145161	55306341	19.51922	7.24950	0.0026247	381
382	145924	55742968	19.54482	7.25584	0.0026178	382
383	146689	56181887	19.57039	7.26217	0.0026110	383
384	147456	56623104	19.59592	7.26848	0.0026042	384
385	148225	57066625	19.62142	7.27479	0.0025974	385
386	148996	57512456	19.64688	7.28108	0.0025907	386
387	149769	57960603	19.67232	7.28736	0.0025840	387
388	150544	58411072	19.69772	7.29363	0.0025773	388
389	151321	58863869	19.72308	7.29989	0.0025707	389
390	152100	59319000	19.74842	7.30614	0.0025641	390
391	152881	59776471	19.77372	7.31238	0.0025575	391
392	153664	60236288	19.79899	7.31861	0.0025510	392
393	154449	60698457	19.82423	7.32483	0.0025445	393
394	155236	61162984	19.84943	7.33104	0.0025381	394
395	156025	61629875	19.87461	7.33723	0.0025316	395
396	156816	62099136	19.89975	7.34342	0.0025253	396
397	157609	62570773	19.92486	7.34960	0.0025189	397
398	158404	63044792	19.94994	7.35576	0.0025126	398
399	159201	63521199	19.97498	7.36192	0.0025063	399
400	160000	64000000	20.00000	7.36806	0.0025000	400

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 401 to 450

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
401	160801	64481201	20.02498	7.37420	0.0024938	401
402	161604	64964808	20.04994	7.38032	0.0024876	402
403	162409	65450827	20.07486	7.38644	0.0024814	403
404	163216	65939264	20.09975	7.39254	0.0024752	404
405	164025	66430125	20.12461	7.39864	0.0024691	405
406	164836	66923416	20.14944	7.40472	0.0024631	406
407	165649	67419143	20.17424	7.41080	0.0024570	407
408	166464	67917312	20.19901	7.41686	0.0024510	408
409	167281	68417929	20.22375	7.42291	0.0024450	409
410	168100	68921000	20.24846	7.42896	0.0024390	410
411	168921	69426531	20.27313	7.43499	0.0024331	411
412	169744	69934528	20.29778	7.44102	0.0024272	412
413	170569	70444997	20.32240	7.44703	0.0024213	413
414	171396	70957944	20.34699	7.45304	0.0024155	414
415	172225	71473375	20.37155	7.45904	0.0024096	415
416	173056	71991296	20.39608	7.46502	0.0024038	416
417	173889	72511713	20.42058	7.47100	0.0023981	417
418	174724	73034632	20.44505	7.47697	0.0023923	418
419	175561	73560059	20.46949	7.48292	0.0023866	419
420	176400	74088000	20.49390	7.48887	0.0023810	420
421	177241	74618461	20.51828	7.49481	0.0023753	421
422	178084	75151448	20.54264	7.50074	0.0023697	422
423	178929	75686967	20.56696	7.50666	0.0023641	423
424	179776	76225024	20.59126	7.51257	0.0023585	424
425	180625	76765625	20.61553	7.51847	0.0023529	425
426	181476	77308776	20.63977	7.52437	0.0023474	426
427	182329	77854483	20.66398	7.53025	0.0023419	427
428	183184	78402752	20.68816	7.53612	0.0023364	428
429	184041	78953589	20.71232	7.54199	0.0023310	429
430	184900	79507000	20.73644	7.54784	0.0023256	430
431	185761	80062991	20.76054	7.55369	0.0023202	431
432	186624	80621568	20.78461	7.55953	0.0023148	432
433	187489	81182737	20.80865	7.56535	0.0023095	433
434	188356	81746504	20.83267	7.57117	0.0023041	434
435	189225	82312875	20.85665	7.57698	0.0022989	435
436	190096	82881856	20.88061	7.58279	0.0022936	436
437	190969	83453453	20.90454	7.58858	0.0022883	437
438	191844	84027672	20.92845	7.59436	0.0022831	438
439	192721	84604519	20.95233	7.60014	0.0022779	439
440	193600	85184000	20.97618	7.60590	0.0022727	440
441	194481	85766121	21.00000	7.61166	0.0022676	441
442	195364	86350888	21.02380	7.61741	0.0022624	442
443	196249	86938307	21.04757	7.62315	0.0022573	443
444	197136	87528384	21.07131	7.62888	0.0022523	444
445	198025	88121125	21.09502	7.63461	0.0022472	445
446	198916	88716536	21.11871	7.64032	0.0022422	446
447	199809	89314623	21.14237	7.64603	0.0022371	447
448	200704	89915392	21.16601	7.65172	0.0022321	448
449	201601	90518849	21.18962	7.65741	0.0022272	449
450	202500	91125000	21.21320	7.66309	0.0022222	450

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 451 to 500

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
451	203401	91733851	21.23676	7.66877	0.0022173	451
452	204304	92345408	21.26029	7.67443	0.0022124	452
453	205209	92959677	21.28380	7.68009	0.0022075	453
454	206116	93576664	21.30728	7.68573	0.0022026	454
455	207025	94196375	21.33073	7.69137	0.0021978	455
456	207936	94818816	21.35416	7.69700	0.0021930	456
457	208849	95443993	21.37756	7.70262	0.0021882	457
458	209764	96071912	21.40093	7.70824	0.0021834	458
459	210681	96702579	21.42429	7.71384	0.0021786	459
460	211600	97336000	21.44761	7.71944	0.0021739	460
461	212521	97972181	21.47091	7.72503	0.0021692	461
462	213444	98611128	21.49419	7.73061	0.0021645	462
463	214369	99252847	21.51743	7.73619	0.0021598	463
464	215296	99897344	21.54066	7.74175	0.0021552	464
465	216225	100544625	21.56386	7.74731	0.0021505	465
466	217156	101194696	21.58703	7.75286	0.0021459	466
467	218089	101847563	21.61018	7.75840	0.0021413	467
468	219024	102503232	21.63331	7.76394	0.0021368	468
469	219961	103161709	21.65641	7.76946	0.0021322	469
470	220900	103823000	21.67948	7.77498	0.0021277	470
471	221841	104487111	21.70253	7.78049	0.0021231	471
472	222784	105154048	21.72556	7.78599	0.0021186	472
473	223729	105823817	21.74856	7.79149	0.0021142	473
474	224676	106496424	21.77154	7.79697	0.0021097	474
475	225625	107171875	21.79449	7.80245	0.0021053	475
476	226576	107850176	21.81742	7.80793	0.0021008	476
477	227529	108531333	21.84033	7.81339	0.0020964	477
478	228484	109215352	21.86321	7.81885	0.0020921	478
479	229441	109902239	21.88607	7.82429	0.0020877	479
480	230400	110592000	21.90890	7.82974	0.0020833	480
481	231361	111284641	21.93171	7.83517	0.0020790	481
482	232324	111980168	21.95450	7.84059	0.0020747	482
483	233289	112678587	21.97726	7.84601	0.0020704	483
484	234256	113379904	22.00000	7.85142	0.0020661	484
485	235225	114084125	22.02272	7.85683	0.0020619	485
486	236196	114791256	22.04541	7.86222	0.0020576	486
487	237169	115501303	22.06808	7.86761	0.0020534	487
488	238144	116214272	22.09072	7.87299	0.0020492	488
489	239121	116930169	22.11334	7.87837	0.0020450	489
490	240100	117649000	22.13594	7.88374	0.0020408	490
491	241081	118370771	22.15852	7.88909	0.0020367	491
492	242064	119095488	22.18107	7.89445	0.0020325	492
493	243049	119823157	22.20360	7.89979	0.0020284	493
494	244036	120553784	22.22611	7.90513	0.0020243	494
495	245025	121287375	22.24860	7.91046	0.0020202	495
496	246016	122023936	22.27106	7.91578	0.0020161	496
497	247009	122763473	22.29350	7.92110	0.0020121	497
498	248004	123505992	22.31591	7.92641	0.0020080	498
499	249001	124251499	22.33831	7.93171	0.0020040	499
500	250000	125000000	22.36068	7.93701	0.0020000	500

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 501 to 550

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
501	251001	125751501	22.38303	7.94229	0.0019960	501
502	252004	126506008	22.40536	7.94757	0.0019920	502
503	253009	127263527	22.42766	7.95285	0.0019881	503
504	254016	128024064	22.44994	7.95811	0.0019841	504
505	255025	128787625	22.47221	7.96337	0.0019802	505
506	256036	129554216	22.49444	7.96863	0.0019763	506
507	257049	130323843	22.51666	7.97387	0.0019724	507
508	258064	131096512	22.53886	7.97911	0.0019685	508
509	259081	131872229	22.56103	7.98434	0.0019646	509
510	260100	132651000	22.58318	7.98957	0.0019608	510
511	261121	133432831	22.60531	7.99479	0.0019569	511
512	262144	134217728	22.62742	8.00000	0.0019531	512
513	263169	135005697	22.64950	8.00520	0.0019493	513
514	264196	135796744	22.67157	8.01040	0.0019455	514
515	265225	136590875	22.69361	8.01559	0.0019417	515
516	266256	137388096	22.71563	8.02078	0.0019380	516
517	267289	138188413	22.73763	8.02596	0.0019342	517
518	268324	138991832	22.75961	8.03113	0.0019305	518
519	269361	139798359	22.78157	8.03629	0.0019268	519
520	270400	140608000	22.80351	8.04145	0.0019231	520
521	271441	141420761	22.82542	8.04660	0.0019194	521
522	272484	142236648	22.84732	8.05175	0.0019157	522
523	273529	143055667	22.86919	8.05689	0.0019120	523
524	274576	143877824	22.89105	8.06202	0.0019084	524
525	275625	144703125	22.91288	8.06714	0.0019048	525
526	276676	145531576	22.93469	8.07226	0.0019011	526
527	277729	146363183	22.95648	8.07737	0.0018975	527
528	278784	147197952	22.97825	8.08248	0.0018939	528
529	279841	148035889	23.00000	8.08758	0.0018904	529
530	280900	148877000	23.02173	8.09267	0.0018868	530
531	281961	149721291	23.04344	8.09776	0.0018832	531
532	283024	150568768	23.06513	8.10284	0.0018797	532
533	284089	151419437	23.08679	8.10791	0.0018762	533
534	285156	152273304	23.10844	8.11298	0.0018727	534
535	286225	153130375	23.13007	8.11804	0.0018692	535
536	287296	153990656	23.15167	8.12310	0.0018657	536
537	288369	154854153	23.17326	8.12814	0.0018622	537
538	289444	155720872	23.19483	8.13319	0.0018587	538
539	290521	156590819	23.21637	8.13822	0.0018553	539
540	291600	157464000	23.23790	8.14325	0.0018519	540
541	292681	158340421	23.25941	8.14828	0.0018484	541
542	293764	159220088	23.28089	8.15329	0.0018450	542
543	294849	160103007	23.30236	8.15831	0.0018416	543
544	295936	160989184	23.32381	8.16331	0.0018382	544
545	297025	161878625	23.34524	8.16831	0.0018349	545
546	298116	162771336	23.36664	8.17330	0.0018315	546
547	299209	163667323	23.38803	8.17829	0.0018282	547
548	300304	164566592	23.40940	8.18327	0.0018248	548
549	301401	165469149	23.43075	8.18824	0.0018215	549
550	302500	166375000	23.45208	8.19321	0.0018182	550

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 551 to 600

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
551	303601	167284151	23.47339	8.19818	0.0018149	551
552	304704	168196608	23.49468	8.20313	0.0018116	552
553	305809	169112377	23.51595	8.20808	0.0018083	553
554	306916	170031464	23.53720	8.21303	0.0018051	554
555	308025	170953875	23.55844	8.21797	0.0018018	555
556	309136	171879616	23.57965	8.22290	0.0017986	556
557	310249	172808693	23.60085	8.22783	0.0017953	557
558	311364	173741112	23.62202	8.23275	0.0017921	558
559	312481	174676879	23.64318	8.23766	0.0017889	559
560	313600	175616000	23.66432	8.24257	0.0017857	560
561	314721	176558481	23.68544	8.24747	0.0017825	561
562	315844	177504328	23.70654	8.25237	0.0017794	562
563	316969	178453547	23.72762	8.25726	0.0017762	563
564	318096	179406144	23.74868	8.26215	0.0017730	564
565	319225	180362125	23.76973	8.26703	0.0017699	565
566	320356	181321496	23.79075	8.27190	0.0017668	566
567	321489	182284263	23.81176	8.27677	0.0017637	567
568	322624	183250432	23.83275	8.28164	0.0017606	568
569	323761	184220009	23.85372	8.28649	0.0017575	569
570	324900	185193000	23.87467	8.29134	0.0017544	570
571	326041	186169411	23.89561	8.29619	0.0017513	571
572	327184	187149248	23.91652	8.30103	0.0017483	572
573	328329	188132517	23.93742	8.30587	0.0017452	573
574	329476	189119224	23.95830	8.31069	0.0017422	574
575	330625	190109375	23.97916	8.31552	0.0017391	575
576	331776	191102976	24.00000	8.32034	0.0017361	576
577	332929	192100033	24.02082	8.32515	0.0017331	577
578	334084	193100552	24.04163	8.32995	0.0017301	578
579	335241	194104539	24.06242	8.33476	0.0017271	579
580	336400	195112000	24.08319	8.33955	0.0017241	580
581	337561	196122941	24.10394	8.34434	0.0017212	581
582	338724	197137368	24.12468	8.34913	0.0017182	582
583	339889	198155287	24.14539	8.35390	0.0017153	583
584	341056	199176704	24.16609	8.35868	0.0017123	584
585	342225	200201625	24.18677	8.36345	0.0017094	585
586	343396	201230056	24.20744	8.36821	0.0017065	586
587	344569	202262003	24.22808	8.37297	0.0017036	587
588	345744	203297472	24.24871	8.37772	0.0017007	588
589	346921	204336469	24.26932	8.38247	0.0016978	589
590	348100	205379000	24.28992	8.38721	0.0016949	590
591	349281	206425071	24.31049	8.39194	0.0016920	591
592	350464	207474688	24.33105	8.39667	0.0016892	592
593	351649	208527857	24.35159	8.40140	0.0016863	593
594	352836	209584584	24.37212	8.40612	0.0016835	594
595	354025	210644875	24.39262	8.41083	0.0016807	595
596	355216	211708736	24.41311	8.41554	0.0016779	596
597	356409	212776173	24.43358	8.42025	0.0016750	597
598	357604	213847192	24.45404	8.42494	0.0016722	598
599	358801	214921799	24.47448	8.42964	0.0016694	599
600	360000	216000000	24.49490	8.43433	0.0016667	600

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 601 to 650

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
601	361201	217081801	24.51530	8.43901	0.0016639	601
602	362404	218167208	24.53569	8.44369	0.0016611	602
603	363609	219256227	24.55606	8.44836	0.0016584	603
604	364816	220348864	24.57641	8.45303	0.0016556	604
605	366025	221445125	24.59675	8.45769	0.0016529	605
606	367236	222545016	24.61707	8.46235	0.0016502	606
607	368449	223648543	24.63737	8.46700	0.0016474	607
608	369664	224755712	24.65766	8.47165	0.0016447	608
609	370881	225866529	24.67793	8.47629	0.0016420	609
610	372100	226981000	24.69818	8.48093	0.0016393	610
611	373321	228099131	24.71841	8.48556	0.0016367	611
612	374544	229220928	24.73863	8.49018	0.0016340	612
613	375769	230346397	24.75884	8.49481	0.0016313	613
614	376996	231475544	24.77902	8.49942	0.0016287	614
615	378225	232608375	24.79919	8.50403	0.0016260	615
616	379456	233744896	24.81935	8.50864	0.0016234	616
617	380689	234885113	24.83948	8.51324	0.0016207	617
618	381924	236029032	24.85961	8.51784	0.0016181	618
619	383161	237176659	24.87971	8.52243	0.0016155	619
620	384400	238328000	24.89980	8.52702	0.0016129	620
621	385641	239483061	24.91987	8.53160	0.0016103	621
622	386884	240641848	24.93993	8.53618	0.0016077	622
623	388129	241804367	24.95997	8.54075	0.0016051	623
624	389376	242970624	24.97999	8.54532	0.0016026	624
625	390625	244140625	25.00000	8.54988	0.0016000	625
626	391876	245314376	25.01999	8.55444	0.0015974	626
627	393129	246491883	25.03997	8.55899	0.0015949	627
628	394384	247673152	25.05993	8.56354	0.0015924	628
629	395641	248858189	25.07987	8.56808	0.0015898	629
630	396900	250047000	25.09980	8.57262	0.0015873	630
631	398161	251239591	25.11971	8.57715	0.0015848	631
632	399424	252435968	25.13961	8.58168	0.0015823	632
633	400689	253636137	25.15949	8.58620	0.0015798	633
634	401956	254840104	25.17936	8.59072	0.0015773	634
635	403225	256047875	25.19921	8.59524	0.0015748	635
636	404496	257259456	25.21904	8.59975	0.0015723	636
637	405769	258474853	25.23886	8.60425	0.0015699	637
638	407044	259694072	25.25866	8.60875	0.0015674	638
639	408321	260917119	25.27845	8.61325	0.0015649	639
640	409600	262144000	25.29822	8.61774	0.0015625	640
641	410881	263374721	25.31798	8.62222	0.0015601	641
642	412164	264609288	25.33772	8.62671	0.0015576	642
643	413449	265847707	25.35744	8.63118	0.0015552	643
644	414736	267089984	25.37716	8.63566	0.0015528	644
645	416025	268336125	25.39685	8.64012	0.0015504	645
646	417316	269586136	25.41653	8.64459	0.0015480	646
647	418609	270840023	25.43619	8.64904	0.0015456	647
648	419904	272097792	25.45584	8.65350	0.0015432	648
649	421201	273359449	25.47548	8.65795	0.0015408	649
650	422500	274625000	25.49510	8.66239	0.0015385	650

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 651 to 700

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
651	423801	275894451	25.51470	8.66683	0.0015361	651
652	425104	277167808	25.53429	8.67127	0.0015337	652
653	426409	278445077	25.55386	8.67570	0.0015314	653
654	427716	279726264	25.57342	8.68012	0.0015291	654
655	429025	281011375	25.59297	8.68455	0.0015267	655
656	430336	282300416	25.61250	8.68896	0.0015244	656
657	431649	283593393	25.63201	8.69338	0.0015221	657
658	432964	284890312	25.65151	8.69778	0.0015198	658
659	434281	286191179	25.67100	8.70219	0.0015175	659
660	435600	287496000	25.69047	8.70659	0.0015152	660
661	436921	288804781	25.70992	8.71098	0.0015129	661
662	438244	290117528	25.72936	8.71537	0.0015106	662
663	439569	291434247	25.74879	8.71976	0.0015083	663
664	440896	292754944	25.76820	8.72414	0.0015060	664
665	442225	294079625	25.78759	8.72852	0.0015038	665
666	443556	295408296	25.80698	8.73289	0.0015015	666
667	444889	296740963	25.82634	8.73726	0.0014993	667
668	446224	298077632	25.84570	8.74162	0.0014970	668
669	447561	299418309	25.86503	8.74598	0.0014948	669
670	448900	300763000	25.88436	8.75034	0.0014925	670
671	450241	302111711	25.90367	8.75469	0.0014903	671
672	451584	303464448	25.92296	8.75904	0.0014881	672
673	452929	304821217	25.94224	8.76338	0.0014859	673
674	454276	306182024	25.96151	8.76772	0.0014837	674
675	455625	307546875	25.98076	8.77205	0.0014815	675
676	456976	308915776	26.00000	8.77638	0.0014793	676
677	458329	310288733	26.01922	8.78071	0.0014771	677
678	459684	311665752	26.03843	8.78503	0.0014749	678
679	461041	313046839	26.05763	8.78935	0.0014728	679
680	462400	314432000	26.07681	8.79366	0.0014706	680
681	463761	315821241	26.09598	8.79797	0.0014684	681
682	465124	317214568	26.11513	8.80227	0.0014663	682
683	466489	318611987	26.13427	8.80657	0.0014641	683
684	467856	320013504	26.15339	8.81087	0.0014620	684
685	469225	321419125	26.17250	8.81516	0.0014599	685
686	470596	322828856	26.19160	8.81945	0.0014577	686
687	471969	324242703	26.21068	8.82373	0.0014556	687
688	473344	325660672	26.22975	8.82801	0.0014535	688
689	474721	327082769	26.24881	8.83228	0.0014514	689
690	476100	328509000	26.26785	8.83656	0.0014493	690
691	477481	329939371	26.28688	8.84082	0.0014472	691
692	478864	331373888	26.30589	8.84509	0.0014451	692
693	480249	332812557	26.32489	8.84934	0.0014430	693
694	481636	334255384	26.34388	8.85360	0.0014409	694
695	483025	335702375	26.36285	8.85785	0.0014388	695
696	484416	337153536	26.38181	8.86210	0.0014368	696
697	485809	338608873	26.40076	8.86634	0.0014347	697
698	487204	340068392	26.41969	8.87058	0.0014327	698
699	488601	341532099	26.43861	8.87481	0.0014306	699
700	490000	343000000	26.45751	8.87904	0.0014286	700

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 701 to 750

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
701	491401	344472101	26.47640	8.88327	0.0014265	701
702	492804	345948408	26.49528	8.88749	0.0014245	702
703	494209	347428927	26.51415	8.89171	0.0014225	703
704	495616	348913664	26.53300	8.89592	0.0014205	704
705	497025	350402625	26.55184	8.90013	0.0014184	705
706	498436	351895816	26.57066	8.90434	0.0014164	706
707	499849	353393243	26.58947	8.90854	0.0014144	707
708	501264	354894912	26.60827	8.91274	0.0014124	708
709	502681	356400829	26.62705	8.91693	0.0014104	709
710	504100	357911000	26.64583	8.92112	0.0014085	710
711	505521	359425431	26.66458	8.92531	0.0014065	711
712	506944	360944128	26.68333	8.92949	0.0014045	712
713	508369	362467097	26.70206	8.93367	0.0014025	713
714	509796	363994344	26.72078	8.93784	0.0014006	714
715	511225	365525875	26.73948	8.94201	0.0013986	715
716	512656	367061696	26.75818	8.94618	0.0013966	716
717	514089	368601813	26.77686	8.95034	0.0013947	717
718	515524	370146232	26.79552	8.95450	0.0013928	718
719	516961	371694959	26.81418	8.95866	0.0013908	719
720	518400	373248000	26.83282	8.96281	0.0013889	720
721	519841	374805361	26.85144	8.96696	0.0013870	721
722	521284	376367048	26.87006	8.97110	0.0013850	722
723	522729	377933067	26.88866	8.97524	0.0013831	723
724	524176	379503424	26.90725	8.97938	0.0013812	724
725	525625	381078125	26.92582	8.98351	0.0013793	725
726	527076	382657176	26.94439	8.98764	0.0013774	726
727	528529	384240583	26.96294	8.99176	0.0013755	727
728	529984	385828352	26.98148	8.99588	0.0013736	728
729	531441	387420489	27.00000	9.00000	0.0013717	729
730	532900	389017000	27.01851	9.00411	0.0013699	730
731	534361	390617891	27.03701	9.00822	0.0013680	731
732	535824	392223168	27.05550	9.01233	0.0013661	732
733	537289	393832837	27.07397	9.01643	0.0013643	733
734	538756	395446904	27.09243	9.02053	0.0013624	734
735	540225	397065375	27.11088	9.02462	0.0013605	735
736	541696	398688256	27.12932	9.02871	0.0013587	736
737	543169	400315553	27.14774	9.03280	0.0013569	737
738	544644	401947272	27.16616	9.03689	0.0013550	738
739	546121	403583419	27.18455	9.04097	0.0013532	739
740	547600	405224000	27.20294	9.04504	0.0013514	740
741	549081	406869021	27.22132	9.04911	0.0013495	741
742	550564	408518488	27.23968	9.05318	0.0013477	742
743	552049	410172407	27.25803	9.05725	0.0013459	743
744	553536	411830784	27.27636	9.06131	0.0013441	744
745	555025	413493625	27.29469	9.06537	0.0013423	745
746	556516	415160936	27.31300	9.06942	0.0013405	746
747	558009	416832723	27.33130	9.07347	0.0013387	747
748	559504	418508992	27.34959	9.07752	0.0013369	748
749	561001	420189749	27.36786	9.08156	0.0013351	749
750	562500	421875000	27.38613	9.08560	0.0013333	750

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 751 to 800

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
751	564001	423564751	27.40438	9.08964	0.0013316	751
752	565504	425259008	27.42262	9.09367	0.0013298	752
753	567009	426957777	27.44085	9.09770	0.0013280	753
754	568516	428661064	27.45906	9.10173	0.0013263	754
755	570025	430368875	27.47726	9.10575	0.0013245	755
756	571536	432081216	27.49545	9.10977	0.0013228	756
757	573049	433798093	27.51363	9.11378	0.0013210	757
758	574564	435519512	27.53180	9.11779	0.0013193	758
759	576081	437245479	27.54995	9.12180	0.0013175	759
760	577600	438976000	27.56810	9.12581	0.0013158	760
761	579121	440711081	27.58623	9.12981	0.0013141	761
762	580644	442450728	27.60435	9.13380	0.0013123	762
763	582169	444194947	27.62245	9.13780	0.0013106	763
764	583696	445943744	27.64055	9.14179	0.0013089	764
765	585225	447697125	27.65863	9.14577	0.0013072	765
766	586756	449455096	27.67671	9.14976	0.0013055	766
767	588289	451217663	27.69476	9.15374	0.0013038	767
768	589824	452984832	27.71281	9.15771	0.0013021	768
769	591361	454756609	27.73085	9.16169	0.0013004	769
770	592900	456533000	27.74887	9.16566	0.0012987	770
771	594441	458314011	27.76689	9.16962	0.0012970	771
772	595984	460099648	27.78489	9.17359	0.0012953	772
773	597529	461889917	27.80288	9.17754	0.0012937	773
774	599076	463684824	27.82086	9.18150	0.0012920	774
775	600625	465484375	27.83882	9.18545	0.0012903	775
776	602176	467288576	27.85678	9.18940	0.0012887	776
777	603729	469097433	27.87472	9.19335	0.0012870	777
778	605284	470910952	27.89265	9.19729	0.0012853	778
779	606841	472729139	27.91057	9.20123	0.0012837	779
780	608400	474552000	27.92848	9.20516	0.0012821	780
781	609961	476379541	27.94638	9.20910	0.0012804	781
782	611524	478211768	27.96426	9.21303	0.0012788	782
783	613089	480048687	27.98214	9.21695	0.0012771	783
784	614656	481890304	28.00000	9.22087	0.0012755	784
785	616225	483736625	28.01785	9.22479	0.0012739	785
786	617796	485587656	28.03569	9.22871	0.0012723	786
787	619369	487443403	28.05352	9.23262	0.0012706	787
788	620944	489303872	28.07134	9.23653	0.0012690	788
789	622521	491169069	28.08914	9.24043	0.0012674	789
790	624100	493039000	28.10694	9.24434	0.0012658	790
791	625681	494913671	28.12472	9.24823	0.0012642	791
792	627264	496793088	28.14249	9.25213	0.0012626	792
793	628849	498677257	28.16026	9.25602	0.0012610	793
794	630436	500566184	28.17801	9.25991	0.0012594	794
795	632025	502459875	28.19574	9.26380	0.0012579	795
796	633616	504358336	28.21347	9.26768	0.0012563	796
797	635209	506261573	28.23119	9.27156	0.0012547	797
798	636804	508169592	28.24889	9.27544	0.0012531	798
799	638401	510082399	28.26659	9.27931	0.0012516	799
800	640000	512000000	28.28427	9.28318	0.0012500	800

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 801 to 850

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
801	641601	513922401	28.30194	9.28704	0.0012484	801
802	643204	515849608	28.31960	9.29091	0.0012469	802
803	644809	517781627	28.33725	9.29477	0.0012453	803
804	646416	519718464	28.35489	9.29862	0.0012438	804
805	648025	521660125	28.37252	9.30248	0.0012422	805
806	649636	523606616	28.39014	9.30633	0.0012407	806
807	651249	525557943	28.40775	9.31018	0.0012392	807
808	652864	527514112	28.42534	9.31402	0.0012376	808
809	654481	529475129	28.44293	9.31786	0.0012361	809
810	656100	531441000	28.46050	9.32170	0.0012346	810
811	657721	533411731	28.47806	9.32553	0.0012330	811
812	659344	535387328	28.49561	9.32936	0.0012315	812
813	660969	537367797	28.51315	9.33319	0.0012300	813
814	662596	539353144	28.53069	9.33702	0.0012285	814
815	664225	541343375	28.54820	9.34084	0.0012270	815
816	665856	543338496	28.56571	9.34466	0.0012255	816
817	667489	545338513	28.58321	9.34847	0.0012240	817
818	669124	547343432	28.60070	9.35229	0.0012225	818
819	670761	549353259	28.61818	9.35610	0.0012210	819
820	672400	551368000	28.63564	9.35990	0.0012195	820
821	674041	553387661	28.65310	9.36370	0.0012180	821
822	675684	555412248	28.67054	9.36751	0.0012165	822
823	677329	557441767	28.68798	9.37130	0.0012151	823
824	678976	559476224	28.70540	9.37510	0.0012136	824
825	680625	561515625	28.72281	9.37889	0.0012121	825
826	682276	563559976	28.74022	9.38268	0.0012107	826
827	683929	565609283	28.75761	9.38646	0.0012092	827
828	685584	567663552	28.77499	9.39024	0.0012077	828
829	687241	569722789	28.79236	9.39402	0.0012063	829
830	688900	571787000	28.80972	9.39780	0.0012048	830
831	690561	573856191	28.82707	9.40157	0.0012034	831
832	692224	575930368	28.84441	9.40534	0.0012019	832
833	693889	578009537	28.86174	9.40911	0.0012005	833
834	695556	580093704	28.87906	9.41287	0.0011990	834
835	697225	582182875	28.89637	9.41663	0.0011976	835
836	698896	584277056	28.91366	9.42039	0.0011962	836
837	700569	586376253	28.93095	9.42414	0.0011947	837
838	702244	588480472	28.94823	9.42789	0.0011933	838
839	703921	590589719	28.96550	9.43164	0.0011919	839
840	705600	592704000	28.98275	9.43539	0.0011905	840
841	707281	594823321	29.00000	9.43913	0.0011891	841
842	708964	596947688	29.01724	9.44287	0.0011876	842
843	710649	599077107	29.03446	9.44661	0.0011862	843
844	712336	601211584	29.05168	9.45034	0.0011848	844
845	714025	603351125	29.06888	9.45407	0.0011834	845
846	715716	605495736	29.08608	9.45780	0.0011820	846
847	717409	607645423	29.10326	9.46152	0.0011806	847
848	719104	609800192	29.12044	9.46525	0.0011792	848
849	720801	611960049	29.13760	9.46897	0.0011779	849
850	722500	614125000	29.15476	9.47268	0.0011765	850

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 851 to 900

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
851	724201	616295051	29.17190	9.47640	0.0011751	851
852	725904	618470208	29.18904	9.48011	0.0011737	852
853	727609	620650477	29.20616	9.48381	0.0011723	853
854	729316	622835864	29.22328	9.48752	0.0011710	854
855	731025	625026375	29.24038	9.49122	0.0011696	855
856	732736	627222016	29.25748	9.49492	0.0011682	856
857	734449	629422793	29.27456	9.49861	0.0011669	857
858	736164	631628712	29.29164	9.50231	0.0011655	858
859	737881	633839779	29.30870	9.50600	0.0011641	859
860	739600	636056000	29.32576	9.50969	0.0011628	860
861	741321	638277381	29.34280	9.51337	0.0011614	861
862	743044	640503928	29.35984	9.51705	0.0011601	862
863	744769	642735647	29.37686	9.52073	0.0011587	863
864	746496	644972544	29.39388	9.52441	0.0011574	864
865	748225	647214625	29.41088	9.52808	0.0011561	865
866	749956	649461896	29.42788	9.53175	0.0011547	866
867	751689	651714363	29.44486	9.53542	0.0011534	867
868	753424	653972032	29.46184	9.53908	0.0011521	868
869	755161	656234909	29.47881	9.54274	0.0011507	869
870	756900	658503000	29.49576	9.54640	0.0011494	870
871	758641	660776311	29.51271	9.55006	0.0011481	871
872	760384	663054848	29.52965	9.55371	0.0011468	872
873	762129	665338617	29.54657	9.55736	0.0011455	873
874	763876	667627624	29.56349	9.56101	0.0011442	874
875	765625	669921875	29.58040	9.56466	0.0011429	875
876	767376	672221376	29.59730	9.56830	0.0011416	876
877	769129	674526133	29.61419	9.57194	0.0011403	877
878	770884	676836152	29.63106	9.57557	0.0011390	878
879	772641	679151439	29.64793	9.57921	0.0011377	879
880	774400	681472000	29.66479	9.58284	0.0011364	880
881	776161	683797841	29.68164	9.58647	0.0011351	881
882	777924	686128968	29.69848	9.59009	0.0011338	882
883	779689	688465387	29.71532	9.59372	0.0011325	883
884	781456	690807104	29.73214	9.59734	0.0011312	884
885	783225	693154125	29.74895	9.60095	0.0011299	885
886	784996	695506456	29.76575	9.60457	0.0011287	886
887	786769	697864103	29.78255	9.60818	0.0011274	887
888	788544	700227072	29.79933	9.61179	0.0011261	888
889	790321	702595369	29.81610	9.61540	0.0011249	889
890	792100	704969000	29.83287	9.61900	0.0011236	890
891	793881	707347971	29.84962	9.62260	0.0011223	891
892	795664	709732288	29.86637	9.62620	0.0011211	892
893	797449	712121957	29.88311	9.62980	0.0011198	893
894	799236	714516984	29.89983	9.63339	0.0011186	894
895	801025	716917375	29.91655	9.63698	0.0011173	895
896	802816	719323136	29.93326	9.64057	0.0011161	896
897	804609	721734273	29.94996	9.64415	0.0011148	897
898	806404	724150792	29.96665	9.64774	0.0011136	898
899	808201	726572699	29.98333	9.65132	0.0011123	899
900	810000	729000000	30.00000	9.65489	0.0011111	900

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 901 to 950

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
901	811801	731432701	30.01666	9.65847	0.0011099	901
902	813604	733870808	30.03331	9.66204	0.0011086	902
903	815409	736314327	30.04996	9.66561	0.0011074	903
904	817216	738763264	30.06659	9.66918	0.0011062	904
905	819025	741217625	30.08322	9.67274	0.0011050	905
906	820836	743677416	30.09983	9.67630	0.0011038	906
907	822649	746142643	30.11644	9.67986	0.0011025	907
908	824464	748613312	30.13304	9.68342	0.0011013	908
909	826281	751089429	30.14963	9.68697	0.0011001	909
910	828100	753571000	30.16621	9.69052	0.0010989	910
911	829921	756058031	30.18278	9.69407	0.0010977	911
912	831744	758550528	30.19934	9.69762	0.0010965	912
913	833569	761048497	30.21589	9.70116	0.0010953	913
914	835396	763551944	30.23243	9.70470	0.0010941	914
915	837225	766060875	30.24897	9.70824	0.0010929	915
916	839056	768575296	30.26549	9.71177	0.0010917	916
917	840889	771095213	30.28201	9.71531	0.0010905	917
918	842724	773620632	30.29851	9.71884	0.0010893	918
919	844561	776151559	30.31501	9.72236	0.0010881	919
920	846400	778688000	30.33150	9.72589	0.0010870	920
921	848241	781229961	30.34798	9.72941	0.0010858	921
922	850084	783777448	30.36445	9.73293	0.0010846	922
923	851929	786330467	30.38092	9.73645	0.0010834	923
924	853776	788889024	30.39737	9.73996	0.0010823	924
925	855625	791453125	30.41381	9.74348	0.0010811	925
926	857476	794022776	30.43025	9.74699	0.0010799	926
927	859329	796597983	30.44667	9.75049	0.0010787	927
928	861184	799178752	30.46309	9.75400	0.0010776	928
929	863041	801765089	30.47950	9.75750	0.0010764	929
930	864900	804357000	30.49590	9.76100	0.0010753	930
931	866761	806954491	30.51229	9.76450	0.0010741	931
932	868624	809557568	30.52868	9.76799	0.0010730	932
933	870489	812166237	30.54505	9.77148	0.0010718	933
934	872356	814780504	30.56141	9.77497	0.0010707	934
935	874225	817400375	30.57777	9.77846	0.0010695	935
936	876096	820025856	30.59412	9.78195	0.0010684	936
937	877969	822656953	30.61046	9.78543	0.0010672	937
938	879844	825293672	30.62679	9.78891	0.0010661	938
939	881721	827936019	30.64311	9.79239	0.0010650	939
940	883600	830584000	30.65942	9.79586	0.0010638	940
941	885481	833237621	30.67572	9.79933	0.0010627	941
942	887364	835896888	30.69202	9.80280	0.0010616	942
943	889249	838561807	30.70831	9.80627	0.0010604	943
944	891136	841232384	30.72458	9.80974	0.0010593	944
945	893025	843908625	30.74085	9.81320	0.0010582	945
946	894916	846590536	30.75711	9.81666	0.0010571	946
947	896809	849278123	30.77337	9.82012	0.0010560	947
948	898704	851971392	30.78961	9.82357	0.0010549	948
949	900601	854670349	30.80584	9.82703	0.0010537	949
950	902500	857375000	30.82207	9.83048	0.0010526	950

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 951 to 1000

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
951	904401	860085351	30.83829	9.83392	0.0010515	951
952	906304	862801408	30.85450	9.83737	0.0010504	952
953	908209	865523177	30.87070	9.84081	0.0010493	953
954	910116	868250664	30.88689	9.84425	0.0010482	954
955	912025	870983875	30.90307	9.84769	0.0010471	955
956	913936	873722816	30.91925	9.85113	0.0010460	956
957	915849	876467493	30.93542	9.85456	0.0010449	957
958	917764	879217912	30.95158	9.85799	0.0010438	958
959	919681	881974079	30.96773	9.86142	0.0010428	959
960	921600	884736000	30.98387	9.86485	0.0010417	960
961	923521	887503681	31.00000	9.86827	0.0010406	961
962	925444	890277128	31.01612	9.87169	0.0010395	962
963	927369	893056347	31.03224	9.87511	0.0010384	963
964	929296	895841344	31.04835	9.87853	0.0010373	964
965	931225	898632125	31.06445	9.88195	0.0010363	965
966	933156	901428696	31.08054	9.88536	0.0010352	966
967	935089	904231063	31.09662	9.88877	0.0010341	967
968	937024	907039232	31.11270	9.89217	0.0010331	968
969	938961	909853209	31.12876	9.89558	0.0010320	969
970	940900	912673000	31.14482	9.89898	0.0010309	970
971	942841	915498611	31.16087	9.90238	0.0010299	971
972	944784	918330048	31.17691	9.90578	0.0010288	972
973	946729	921167317	31.19295	9.90918	0.0010277	973
974	948676	924010424	31.20897	9.91257	0.0010267	974
975	950625	926859375	31.22499	9.91596	0.0010256	975
976	952576	929714176	31.24100	9.91935	0.0010246	976
977	954529	932574833	31.25700	9.92274	0.0010235	977
978	956484	935441352	31.27299	9.92612	0.0010225	978
979	958441	938313739	31.28898	9.92950	0.0010215	979
980	960400	941192000	31.30495	9.93288	0.0010204	980
981	962361	944076141	31.32092	9.93626	0.0010194	981
982	964324	946966168	31.33688	9.93964	0.0010183	982
983	966289	949862087	31.35283	9.94301	0.0010173	983
984	968256	952763904	31.36877	9.94638	0.0010163	984
985	970225	955671625	31.38471	9.94975	0.0010152	985
986	972196	958585256	31.40064	9.95311	0.0010142	986
987	974169	961504803	31.41656	9.95648	0.0010132	987
988	976144	964430272	31.43247	9.95984	0.0010121	988
989	978121	967361669	31.44837	9.96320	0.0010111	989
990	980100	970299000	31.46427	9.96655	0.0010101	990
991	982081	973242271	31.48015	9.96991	0.0010091	991
992	984064	976191488	31.49603	9.97326	0.0010081	992
993	986049	979146657	31.51190	9.97661	0.0010070	993
994	988036	982107784	31.52777	9.97996	0.0010060	994
995	990025	985074875	31.54362	9.98331	0.0010050	995
996	992016	988047936	31.55947	9.98665	0.0010040	996
997	994009	991026973	31.57531	9.98999	0.0010030	997
998	996004	994011992	31.59114	9.99333	0.0010020	998
999	998001	997002999	31.60696	9.99667	0.0010010	999
1000	1000000	1000000000	31.62278	10.00000	0.0010000	1000

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1001 to 1050

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1001	1002001	1003003001	31.63858	10.00333	0.0009990	1001
1002	1004004	1006012008	31.65438	10.00666	0.0009980	1002
1003	1006009	1009027027	31.67018	10.00999	0.0009970	1003
1004	1008016	1012048064	31.68596	10.01332	0.0009960	1004
1005	1010025	1015075125	31.70173	10.01664	0.0009950	1005
1006	1012036	1018108216	31.71750	10.01996	0.0009940	1006
1007	1014049	1021147343	31.73326	10.02328	0.0009930	1007
1008	1016064	1024192512	31.74902	10.02660	0.0009921	1008
1009	1018081	1027243729	31.76476	10.02991	0.0009911	1009
1010	1020100	1030301000	31.78050	10.03322	0.0009901	1010
1011	1022121	1033364331	31.79623	10.03653	0.0009891	1011
1012	1024144	1036433728	31.81195	10.03984	0.0009881	1012
1013	1026169	1039509197	31.82766	10.04315	0.0009872	1013
1014	1028196	1042590744	31.84337	10.04645	0.0009862	1014
1015	1030225	1045678375	31.85906	10.04975	0.0009852	1015
1016	1032256	1048772096	31.87475	10.05305	0.0009843	1016
1017	1034289	1051871913	31.89044	10.05635	0.0009833	1017
1018	1036324	1054977832	31.90611	10.05964	0.0009823	1018
1019	1038361	1058089859	31.92178	10.06294	0.0009814	1019
1020	1040400	1061208000	31.93744	10.06623	0.0009804	1020
1021	1042441	1064332261	31.95309	10.06952	0.0009794	1021
1022	1044484	1067462648	31.96873	10.07280	0.0009785	1022
1023	1046529	1070599167	31.98437	10.07609	0.0009775	1023
1024	1048576	1073741824	32.00000	10.07937	0.0009766	1024
1025	1050625	1076890625	32.01562	10.08265	0.0009756	1025
1026	1052676	1080045576	32.03123	10.08593	0.0009747	1026
1027	1054729	1083206683	32.04684	10.08920	0.0009737	1027
1028	1056784	1086373952	32.06244	10.09248	0.0009728	1028
1029	1058841	1089547389	32.07803	10.09575	0.0009718	1029
1030	1060900	1092727000	32.09361	10.09902	0.0009709	1030
1031	1062961	1095912791	32.10919	10.10228	0.0009699	1031
1032	1065024	1099104768	32.12476	10.10555	0.0009690	1032
1033	1067089	1102302937	32.14032	10.10881	0.0009681	1033
1034	1069156	1105507304	32.15587	10.11207	0.0009671	1034
1035	1071225	1108717875	32.17142	10.11533	0.0009662	1035
1036	1073296	1111934656	32.18695	10.11859	0.0009653	1036
1037	1075369	1115157653	32.20248	10.12184	0.0009643	1037
1038	1077444	1118386872	32.21801	10.12510	0.0009634	1038
1039	1079521	1121622319	32.23352	10.12835	0.0009625	1039
1040	1081600	1124864000	32.24903	10.13159	0.0009615	1040
1041	1083681	1128111921	32.26453	10.13484	0.0009606	1041
1042	1085764	1131366088	32.28002	10.13808	0.0009597	1042
1043	1087849	1134626507	32.29551	10.14133	0.0009588	1043
1044	1089936	1137893184	32.31099	10.14457	0.0009579	1044
1045	1092025	1141166125	32.32646	10.14780	0.0009569	1045
1046	1094116	1144445336	32.34192	10.15104	0.0009560	1046
1047	1096209	1147730823	32.35738	10.15427	0.0009551	1047
1048	1098304	1151022592	32.37283	10.15751	0.0009542	1048
1049	1100401	1154320649	32.38827	10.16074	0.0009533	1049
1050	1102500	1157625000	32.40370	10.16396	0.0009524	1050

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1051 to 1100

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1051	1104601	1160935651	32.41913	10.16719	0.0009515	1051
1052	1106704	1164252608	32.43455	10.17041	0.0009506	1052
1053	1108809	1167575877	32.44996	10.17363	0.0009497	1053
1054	1110916	1170905464	32.46537	10.17685	0.0009488	1054
1055	1113025	1174241375	32.48076	10.18007	0.0009479	1055
1056	1115136	1177583616	32.49615	10.18329	0.0009470	1056
1057	1117249	1180932193	32.51154	10.18650	0.0009461	1057
1058	1119364	1184287112	32.52691	10.18971	0.0009452	1058
1059	1121481	1187648379	32.54228	10.19292	0.0009443	1059
1060	1123600	1191016000	32.55764	10.19613	0.0009434	1060
1061	1125721	1194389981	32.57299	10.19933	0.0009425	1061
1062	1127844	1197770328	32.58834	10.20254	0.0009416	1062
1063	1129969	1201157047	32.60368	10.20574	0.0009407	1063
1064	1132096	1204550144	32.61901	10.20894	0.0009398	1064
1065	1134225	1207949625	32.63434	10.21213	0.0009390	1065
1066	1136356	1211355496	32.64966	10.21533	0.0009381	1066
1067	1138489	1214767763	32.66497	10.21852	0.0009372	1067
1068	1140624	1218186432	32.68027	10.22171	0.0009363	1068
1069	1142761	1221611509	32.69557	10.22490	0.0009355	1069
1070	1144900	1225043000	32.71085	10.22809	0.0009346	1070
1071	1147041	1228480911	32.72614	10.23128	0.0009337	1071
1072	1149184	1231925248	32.74141	10.23446	0.0009328	1072
1073	1151329	1235376017	32.75668	10.23764	0.0009320	1073
1074	1153476	1238833224	32.77194	10.24082	0.0009311	1074
1075	1155625	1242296875	32.78719	10.24400	0.0009302	1075
1076	1157776	1245766976	32.80244	10.24717	0.0009294	1076
1077	1159929	1249243533	32.81768	10.25035	0.0009285	1077
1078	1162084	1252726552	32.83291	10.25352	0.0009276	1078
1079	1164241	1256216039	32.84814	10.25669	0.0009268	1079
1080	1166400	1259712000	32.86335	10.25986	0.0009259	1080
1081	1168561	1263214441	32.87856	10.26302	0.0009251	1081
1082	1170724	1266723368	32.89377	10.26619	0.0009242	1082
1083	1172889	1270238787	32.90897	10.26935	0.0009234	1083
1084	1175056	1273760704	32.92416	10.27251	0.0009225	1084
1085	1177225	1277289125	32.93934	10.27566	0.0009217	1085
1086	1179396	1280824056	32.95451	10.27882	0.0009208	1086
1087	1181569	1284365503	32.96968	10.28197	0.0009200	1087
1088	1183744	1287913472	32.98485	10.28513	0.0009191	1088
1089	1185921	1291467969	33.00000	10.28828	0.0009183	1089
1090	1188100	1295029000	33.01515	10.29142	0.0009174	1090
1091	1190281	1298596571	33.03029	10.29457	0.0009166	1091
1092	1192464	1302170688	33.04542	10.29772	0.0009158	1092
1093	1194649	1305751357	33.06055	10.30086	0.0009149	1093
1094	1196836	1309338584	33.07567	10.30400	0.0009141	1094
1095	1199025	1312932375	33.09078	10.30714	0.0009132	1095
1096	1201216	1316532736	33.10589	10.31027	0.0009124	1096
1097	1203409	1320139673	33.12099	10.31341	0.0009116	1097
1098	1205604	1323753192	33.13608	10.31654	0.0009107	1098
1099	1207801	1327373299	33.15117	10.31967	0.0009099	1099
1100	1210000	1331000000	33.16625	10.32280	0.0009091	1100

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1101 to 1150

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1101	1212201	1334633301	33.18132	10.32593	0.0009083	1101
1102	1214404	1338273208	33.19639	10.32905	0.0009074	1102
1103	1216609	1341919727	33.21144	10.33218	0.0009066	1103
1104	1218816	1345572864	33.22650	10.33530	0.0009058	1104
1105	1221025	1349232625	33.24154	10.33842	0.0009050	1105
1106	1223236	1352899016	33.25658	10.34154	0.0009042	1106
1107	1225449	1356572043	33.27161	10.34465	0.0009033	1107
1108	1227664	1360251712	33.28663	10.34777	0.0009025	1108
1109	1229881	1363938029	33.30165	10.35088	0.0009017	1109
1110	1232100	1367631000	33.31666	10.35399	0.0009009	1110
1111	1234321	1371330631	33.33167	10.35710	0.0009001	1111
1112	1236544	1375036928	33.34666	10.36020	0.0008993	1112
1113	1238769	1378749897	33.36165	10.36331	0.0008985	1113
1114	1240996	1382469544	33.37664	10.36641	0.0008977	1114
1115	1243225	1386195875	33.39162	10.36951	0.0008969	1115
1116	1245456	1389928896	33.40659	10.37261	0.0008961	1116
1117	1247689	1393668613	33.42155	10.37571	0.0008953	1117
1118	1249924	1397415032	33.43651	10.37880	0.0008945	1118
1119	1252161	1401168159	33.45146	10.38190	0.0008937	1119
1120	1254400	1404928000	33.46640	10.38499	0.0008929	1120
1121	1256641	1408694561	33.48134	10.38808	0.0008921	1121
1122	1258884	1412467848	33.49627	10.39117	0.0008913	1122
1123	1261129	1416247867	33.51119	10.39425	0.0008905	1123
1124	1263376	1420034624	33.52611	10.39734	0.0008897	1124
1125	1265625	1423828125	33.54102	10.40042	0.0008889	1125
1126	1267876	1427628376	33.55592	10.40350	0.0008881	1126
1127	1270129	1431435383	33.57082	10.40658	0.0008873	1127
1128	1272384	1435249152	33.58571	10.40966	0.0008865	1128
1129	1274641	1439069689	33.60060	10.41273	0.0008857	1129
1130	1276900	1442897000	33.61547	10.41580	0.0008850	1130
1131	1279161	1446731091	33.63034	10.41888	0.0008842	1131
1132	1281424	1450571968	33.64521	10.42195	0.0008834	1132
1133	1283689	1454419637	33.66007	10.42501	0.0008826	1133
1134	1285956	1458274104	33.67492	10.42808	0.0008818	1134
1135	1288225	1462135375	33.68976	10.43114	0.0008811	1135
1136	1290496	1466003456	33.70460	10.43421	0.0008803	1136
1137	1292769	1469878353	33.71943	10.43727	0.0008795	1137
1138	1295044	1473760072	33.73426	10.44033	0.0008787	1138
1139	1297321	1477648619	33.74907	10.44338	0.0008780	1139
1140	1299600	1481544000	33.76389	10.44644	0.0008772	1140
1141	1301881	1485446221	33.77869	10.44949	0.0008764	1141
1142	1304164	1489355288	33.79349	10.45254	0.0008757	1142
1143	1306449	1493271207	33.80828	10.45559	0.0008749	1143
1144	1308736	1497193984	33.82307	10.45864	0.0008741	1144
1145	1311025	1501123625	33.83785	10.46169	0.0008734	1145
1146	1313316	1505060136	33.85262	10.46473	0.0008726	1146
1147	1315609	1509003523	33.86739	10.46778	0.0008718	1147
1148	1317904	1512953792	33.88215	10.47082	0.0008711	1148
1149	1320201	1516910949	33.89690	10.47386	0.0008703	1149
1150	1322500	1520875000	33.91165	10.47690	0.0008696	1150

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1151 to 1200

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1151	1324801	1524845951	33.92639	10.47993	0.0008688	1151
1152	1327104	1528823808	33.94113	10.48297	0.0008681	1152
1153	1329409	1532808577	33.95585	10.48600	0.0008673	1153
1154	1331716	1536800264	33.97058	10.48903	0.0008666	1154
1155	1334025	1540798875	33.98529	10.49206	0.0008658	1155
1156	1336336	1544804416	34.00000	10.49508	0.0008651	1156
1157	1338649	1548816893	34.01470	10.49811	0.0008643	1157
1158	1340964	1552836312	34.02940	10.50113	0.0008636	1158
1159	1343281	1556862679	34.04409	10.50416	0.0008628	1159
1160	1345600	1560896000	34.05877	10.50718	0.0008621	1160
1161	1347921	1564936281	34.07345	10.51019	0.0008613	1161
1162	1350244	1568983528	34.08812	10.51321	0.0008606	1162
1163	1352569	1573037747	34.10279	10.51623	0.0008598	1163
1164	1354896	1577098944	34.11744	10.51924	0.0008591	1164
1165	1357225	1581167125	34.13210	10.52225	0.0008584	1165
1166	1359556	1585242296	34.14674	10.52526	0.0008576	1166
1167	1361889	1589324463	34.16138	10.52827	0.0008569	1167
1168	1364224	1593413632	34.17601	10.53127	0.0008562	1168
1169	1366561	1597509809	34.19064	10.53428	0.0008554	1169
1170	1368900	1601613000	34.20526	10.53728	0.0008547	1170
1171	1371241	1605723211	34.21988	10.54028	0.0008540	1171
1172	1373584	1609840448	34.23449	10.54328	0.0008532	1172
1173	1375929	1613964717	34.24909	10.54628	0.0008525	1173
1174	1378276	1618096024	34.26368	10.54928	0.0008518	1174
1175	1380625	1622234375	34.27827	10.55227	0.0008511	1175
1176	1382976	1626379776	34.29286	10.55526	0.0008503	1176
1177	1385329	1630532233	34.30743	10.55826	0.0008496	1177
1178	1387684	1634691752	34.32200	10.56124	0.0008489	1178
1179	1390041	1638858339	34.33657	10.56423	0.0008482	1179
1180	1392400	1643032000	34.35113	10.56722	0.0008475	1180
1181	1394761	1647212741	34.36568	10.57020	0.0008467	1181
1182	1397124	1651400568	34.38023	10.57318	0.0008460	1182
1183	1399489	1655595487	34.39477	10.57617	0.0008453	1183
1184	1401856	1659797504	34.40930	10.57914	0.0008446	1184
1185	1404225	1664006625	34.42383	10.58212	0.0008439	1185
1186	1406596	1668222856	34.43835	10.58510	0.0008432	1186
1187	1408969	1672446203	34.45287	10.58807	0.0008425	1187
1188	1411344	1676676672	34.46738	10.59105	0.0008418	1188
1189	1413721	1680914269	34.48188	10.59402	0.0008410	1189
1190	1416100	1685159000	34.49638	10.59699	0.0008403	1190
1191	1418481	1689410871	34.51087	10.59995	0.0008396	1191
1192	1420864	1693669888	34.52535	10.60292	0.0008389	1192
1193	1423249	1697936057	34.53983	10.60588	0.0008382	1193
1194	1425636	1702209384	34.55431	10.60885	0.0008375	1194
1195	1428025	1706489875	34.56877	10.61181	0.0008368	1195
1196	1430416	1710777536	34.58323	10.61477	0.0008361	1196
1197	1432809	1715072373	34.59769	10.61772	0.0008354	1197
1198	1435204	1719374392	34.61214	10.62068	0.0008347	1198
1199	1437601	1723683599	34.62658	10.62363	0.0008340	1199
1200	1440000	1728000000	34.64102	10.62659	0.0008333	1200

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1201 to 1250

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1201	1442401	1732323601	34.65545	10.62954	0.0008326	1201
1202	1444804	1736654408	34.66987	10.63249	0.0008319	1202
1203	1447209	1740992427	34.68429	10.63543	0.0008313	1203
1204	1449616	1745337664	34.69870	10.63838	0.0008306	1204
1205	1452025	1749690125	34.71311	10.64132	0.0008299	1205
1206	1454436	1754049816	34.72751	10.64427	0.0008292	1206
1207	1456849	1758416743	34.74191	10.64721	0.0008285	1207
1208	1459264	1762790912	34.75629	10.65015	0.0008278	1208
1209	1461681	1767172329	34.77068	10.65309	0.0008271	1209
1210	1464100	1771561000	34.78505	10.65602	0.0008264	1210
1211	1466521	1775956931	34.79943	10.65896	0.0008258	1211
1212	1468944	1780360128	34.81379	10.66189	0.0008251	1212
1213	1471369	1784770597	34.82815	10.66482	0.0008244	1213
1214	1473796	1789188344	34.84250	10.66775	0.0008237	1214
1215	1476225	1793613375	34.85685	10.67068	0.0008230	1215
1216	1478656	1798045696	34.87119	10.67361	0.0008224	1216
1217	1481089	1802485313	34.88553	10.67653	0.0008217	1217
1218	1483524	1806932232	34.89986	10.67946	0.0008210	1218
1219	1485961	1811386459	34.91418	10.68238	0.0008203	1219
1220	1488400	1815848000	34.92850	10.68530	0.0008197	1220
1221	1490841	1820316861	34.94281	10.68822	0.0008190	1221
1222	1493284	1824793048	34.95712	10.69113	0.0008183	1222
1223	1495729	1829276567	34.97142	10.69405	0.0008177	1223
1224	1498176	1833767424	34.98571	10.69696	0.0008170	1224
1225	1500625	1838265625	35.00000	10.69987	0.0008163	1225
1226	1503076	1842771176	35.01428	10.70279	0.0008157	1226
1227	1505529	1847284083	35.02856	10.70569	0.0008150	1227
1228	1507984	1851804352	35.04283	10.70860	0.0008143	1228
1229	1510441	1856331989	35.05710	10.71151	0.0008137	1229
1230	1512900	1860867000	35.07136	10.71441	0.0008130	1230
1231	1515361	1865409391	35.08561	10.71732	0.0008123	1231
1232	1517824	1869959168	35.09986	10.72022	0.0008117	1232
1233	1520289	1874516337	35.11410	10.72312	0.0008110	1233
1234	1522756	1879080904	35.12834	10.72601	0.0008104	1234
1235	1525225	1883652875	35.14257	10.72891	0.0008097	1235
1236	1527696	1888232256	35.15679	10.73181	0.0008091	1236
1237	1530169	1892819053	35.17101	10.73470	0.0008084	1237
1238	1532644	1897413272	35.18522	10.73759	0.0008078	1238
1239	1535121	1902014919	35.19943	10.74048	0.0008071	1239
1240	1537600	1906624000	35.21363	10.74337	0.0008065	1240
1241	1540081	1911240521	35.22783	10.74626	0.0008058	1241
1242	1542564	1915864488	35.24202	10.74914	0.0008052	1242
1243	1545049	1920495907	35.25621	10.75203	0.0008045	1243
1244	1547536	1925134784	35.27038	10.75491	0.0008039	1244
1245	1550025	1929781125	35.28456	10.75779	0.0008032	1245
1246	1552516	1934434936	35.29873	10.76067	0.0008026	1246
1247	1555009	1939096223	35.31289	10.76355	0.0008019	1247
1248	1557504	1943764992	35.32704	10.76643	0.0008013	1248
1249	1560001	1948441249	35.34119	10.76930	0.0008006	1249
1250	1562500	1953125000	35.35534	10.77217	0.0008000	1250

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1251 to 1300

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1251	1565001	1957816251	35.36948	10.77505	0.0007994	1251
1252	1567504	1962515008	35.38361	10.77792	0.0007987	1252
1253	1570009	1967221277	35.39774	10.78078	0.0007981	1253
1254	1572516	1971935064	35.41186	10.78365	0.0007974	1254
1255	1575025	1976656375	35.42598	10.78652	0.0007968	1255
1256	1577536	1981385216	35.44009	10.78938	0.0007962	1256
1257	1580049	1986121593	35.45420	10.79224	0.0007955	1257
1258	1582564	1990865512	35.46830	10.79511	0.0007949	1258
1259	1585081	1995616979	35.48239	10.79796	0.0007943	1259
1260	1587600	2000376000	35.49648	10.80082	0.0007937	1260
1261	1590121	2005142581	35.51056	10.80368	0.0007930	1261
1262	1592644	2009916728	35.52464	10.80653	0.0007924	1262
1263	1595169	2014698447	35.53871	10.80939	0.0007918	1263
1264	1597696	2019487744	35.55278	10.81224	0.0007911	1264
1265	1600225	2024284625	35.56684	10.81509	0.0007905	1265
1266	1602756	2029089096	35.58089	10.81794	0.0007899	1266
1267	1605289	2033901163	35.59494	10.82079	0.0007893	1267
1268	1607824	2038720832	35.60899	10.82363	0.0007886	1268
1269	1610361	2043548109	35.62303	10.82648	0.0007880	1269
1270	1612900	2048383000	35.63706	10.82932	0.0007874	1270
1271	1615441	2053225511	35.65109	10.83216	0.0007868	1271
1272	1617984	2058075648	35.66511	10.83500	0.0007862	1272
1273	1620529	2062933417	35.67913	10.83784	0.0007855	1273
1274	1623076	2067798824	35.69314	10.84068	0.0007849	1274
1275	1625625	2072671875	35.70714	10.84351	0.0007843	1275
1276	1628176	2077552576	35.72114	10.84635	0.0007837	1276
1277	1630729	2082440933	35.73514	10.84918	0.0007831	1277
1278	1633284	2087336952	35.74913	10.85201	0.0007825	1278
1279	1635841	2092240639	35.76311	10.85484	0.0007819	1279
1280	1638400	2097152000	35.77709	10.85767	0.0007813	1280
1281	1640961	2102071041	35.79106	10.86050	0.0007806	1281
1282	1643524	2106997768	35.80503	10.86332	0.0007800	1282
1283	1646089	2111932187	35.81899	10.86615	0.0007794	1283
1284	1648656	2116874304	35.83295	10.86897	0.0007788	1284
1285	1651225	2121824125	35.84690	10.87179	0.0007782	1285
1286	1653796	2126781656	35.86084	10.87461	0.0007776	1286
1287	1656369	2131746903	35.87478	10.87743	0.0007770	1287
1288	1658944	2136719872	35.88872	10.88024	0.0007764	1288
1289	1661521	2141700569	35.90265	10.88306	0.0007758	1289
1290	1664100	2146689000	35.91657	10.88587	0.0007752	1290
1291	1666681	2151685171	35.93049	10.88868	0.0007746	1291
1292	1669264	2156689088	35.94440	10.89150	0.0007740	1292
1293	1671849	2161700757	35.95831	10.89430	0.0007734	1293
1294	1674436	2166720184	35.97221	10.89711	0.0007728	1294
1295	1677025	2171747375	35.98611	10.89992	0.0007722	1295
1296	1679616	2176782336	36.00000	10.90272	0.0007716	1296
1297	1682209	2181825073	36.01389	10.90553	0.0007710	1297
1298	1684804	2186875592	36.02777	10.90833	0.0007704	1298
1299	1687401	2191933899	36.04164	10.91113	0.0007698	1299
1300	1690000	2197000000	36.05551	10.91393	0.0007692	1300

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1301 to 1350

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1301	1692601	2202073901	36.06938	10.91673	0.0007686	1301
1302	1695204	2207155608	36.08324	10.91952	0.0007680	1302
1303	1697809	2212245127	36.09709	10.92232	0.0007675	1303
1304	1700416	2217342464	36.11094	10.92511	0.0007669	1304
1305	1703025	2222447625	36.12478	10.92790	0.0007663	1305
1306	1705636	2227560616	36.13862	10.93069	0.0007657	1306
1307	1708249	2232681443	36.15245	10.93348	0.0007651	1307
1308	1710864	2237810112	36.16628	10.93627	0.0007645	1308
1309	1713481	2242946629	36.18011	10.93906	0.0007639	1309
1310	1716100	2248091000	36.19392	10.94184	0.0007634	1310
1311	1718721	2253243231	36.20773	10.94463	0.0007628	1311
1312	1721344	2258403328	36.22154	10.94741	0.0007622	1312
1313	1723969	2263571297	36.23534	10.95019	0.0007616	1313
1314	1726596	2268747144	36.24914	10.95297	0.0007610	1314
1315	1729225	2273930875	36.26293	10.95575	0.0007605	1315
1316	1731856	2279122496	36.27671	10.95852	0.0007599	1316
1317	1734489	2284322013	36.29049	10.96130	0.0007593	1317
1318	1737124	2289529432	36.30427	10.96407	0.0007587	1318
1319	1739761	2294744759	36.31804	10.96684	0.0007582	1319
1320	1742400	2299968000	36.33180	10.96961	0.0007576	1320
1321	1745041	2305199161	36.34556	10.97238	0.0007570	1321
1322	1747684	2310438248	36.35932	10.97515	0.0007564	1322
1323	1750329	2315685267	36.37307	10.97792	0.0007559	1323
1324	1752976	2320940224	36.38681	10.98068	0.0007553	1324
1325	1755625	2326203125	36.40055	10.98345	0.0007547	1325
1326	1758276	2331473976	36.41428	10.98621	0.0007541	1326
1327	1760929	2336752783	36.42801	10.98897	0.0007536	1327
1328	1763584	2342039552	36.44173	10.99173	0.0007530	1328
1329	1766241	2347334289	36.45545	10.99449	0.0007524	1329
1330	1768900	2352637000	36.46917	10.99724	0.0007519	1330
1331	1771561	2357947691	36.48287	11.00000	0.0007513	1331
1332	1774224	2363266368	36.49658	11.00275	0.0007508	1332
1333	1776889	2368593037	36.51027	11.00551	0.0007502	1333
1334	1779556	2373927704	36.52396	11.00826	0.0007496	1334
1335	1782225	2379270375	36.53765	11.01101	0.0007491	1335
1336	1784896	2384621056	36.55133	11.01376	0.0007485	1336
1337	1787569	2389979753	36.56501	11.01650	0.0007479	1337
1338	1790244	2395346472	36.57868	11.01925	0.0007474	1338
1339	1792921	2400721219	36.59235	11.02199	0.0007468	1339
1340	1795600	2406104000	36.60601	11.02474	0.0007463	1340
1341	1798281	2411494821	36.61967	11.02748	0.0007457	1341
1342	1800964	2416893688	36.63332	11.03022	0.0007452	1342
1343	1803649	2422300607	36.64696	11.03296	0.0007446	1343
1344	1806336	2427715584	36.66061	11.03570	0.0007440	1344
1345	1809025	2433138625	36.67424	11.03843	0.0007435	1345
1346	1811716	2438569736	36.68787	11.04117	0.0007429	1346
1347	1814409	2444008923	36.70150	11.04390	0.0007424	1347
1348	1817104	2449456192	36.71512	11.04663	0.0007418	1348
1349	1819801	2454911549	36.72874	11.04936	0.0007413	1349
1350	1822500	2460375000	36.74235	11.05209	0.0007407	1350

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1351 to 1400

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1351	1825201	2465846551	36.75595	11.05482	0.0007402	1351
1352	1827904	2471326208	36.76955	11.05755	0.0007396	1352
1353	1830609	2476813977	36.78315	11.06028	0.0007391	1353
1354	1833316	2482309864	36.79674	11.06300	0.0007386	1354
1355	1836025	2487813875	36.81032	11.06572	0.0007380	1355
1356	1838736	2493326016	36.82391	11.06844	0.0007375	1356
1357	1841449	2498846293	36.83748	11.07116	0.0007369	1357
1358	1844164	2504374712	36.85105	11.07388	0.0007364	1358
1359	1846881	2509911279	36.86462	11.07660	0.0007358	1359
1360	1849600	2515456000	36.87818	11.07932	0.0007353	1360
1361	1852321	2521008881	36.89173	11.08203	0.0007348	1361
1362	1855044	2526569928	36.90528	11.08474	0.0007342	1362
1363	1857769	2532139147	36.91883	11.08746	0.0007337	1363
1364	1860496	2537716544	36.93237	11.09017	0.0007331	1364
1365	1863225	2543302125	36.94591	11.09288	0.0007326	1365
1366	1865956	2548895896	36.95944	11.09559	0.0007321	1366
1367	1868689	2554497863	36.97296	11.09829	0.0007315	1367
1368	1871424	2560108032	36.98648	11.10100	0.0007310	1368
1369	1874161	2565726409	37.00000	11.10370	0.0007305	1369
1370	1876900	2571353000	37.01351	11.10641	0.0007299	1370
1371	1879641	2576987811	37.02702	11.10911	0.0007294	1371
1372	1882384	2582630848	37.04052	11.11181	0.0007289	1372
1373	1885129	2588282117	37.05401	11.11451	0.0007283	1373
1374	1887876	2593941624	37.06751	11.11720	0.0007278	1374
1375	1890625	2599609375	37.08099	11.11990	0.0007273	1375
1376	1893376	2605285376	37.09447	11.12260	0.0007267	1376
1377	1896129	2610969633	37.10795	11.12529	0.0007262	1377
1378	1898884	2616662152	37.12142	11.12798	0.0007257	1378
1379	1901641	2622362939	37.13489	11.13067	0.0007252	1379
1380	1904400	2628072000	37.14835	11.13336	0.0007246	1380
1381	1907161	2633789341	37.16181	11.13605	0.0007241	1381
1382	1909924	2639514968	37.17526	11.13874	0.0007236	1382
1383	1912689	2645248887	37.18871	11.14142	0.0007231	1383
1384	1915456	2650991104	37.20215	11.14411	0.0007225	1384
1385	1918225	2656741625	37.21559	11.14679	0.0007220	1385
1386	1920996	2662500456	37.22902	11.14947	0.0007215	1386
1387	1923769	2668267603	37.24245	11.15216	0.0007210	1387
1388	1926544	2674043072	37.25587	11.15484	0.0007205	1388
1389	1929321	2679826869	37.26929	11.15751	0.0007199	1389
1390	1932100	2685619000	37.28270	11.16019	0.0007194	1390
1391	1934881	2691419471	37.29611	11.16287	0.0007189	1391
1392	1937664	2697228288	37.30952	11.16554	0.0007184	1392
1393	1940449	2703045457	37.32292	11.16821	0.0007179	1393
1394	1943236	2708870984	37.33631	11.17089	0.0007174	1394
1395	1946025	2714704875	37.34970	11.17356	0.0007168	1395
1396	1948816	2720547136	37.36308	11.17623	0.0007163	1396
1397	1951609	2726397773	37.37646	11.17889	0.0007158	1397
1398	1954404	2732256792	37.38984	11.18156	0.0007153	1398
1399	1957201	2738124199	37.40321	11.18423	0.0007148	1399
1400	1960000	2744000000	37.41657	11.18689	0.0007143	1400

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1401 to 1450

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1401	1962801	2749884201	37.42993	11.18955	0.0007138	1401
1402	1965604	2755776808	37.44329	11.19221	0.0007133	1402
1403	1968409	2761677827	37.45664	11.19487	0.0007128	1403
1404	1971216	2767587264	37.46999	11.19753	0.0007123	1404
1405	1974025	2773505125	37.48333	11.20019	0.0007117	1405
1406	1976836	2779431416	37.49667	11.20285	0.0007112	1406
1407	1979649	2785366143	37.51000	11.20550	0.0007107	1407
1408	1982464	2791309312	37.52333	11.20816	0.0007102	1408
1409	1985281	2797260929	37.53665	11.21081	0.0007097	1409
1410	1988100	2803221000	37.54997	11.21346	0.0007092	1410
1411	1990921	2809189531	37.56328	11.21611	0.0007087	1411
1412	1993744	2815166528	37.57659	11.21876	0.0007082	1412
1413	1996569	2821151997	37.58989	11.22141	0.0007077	1413
1414	1999396	2827145944	37.60319	11.22406	0.0007072	1414
1415	2002225	2833148375	37.61649	11.22670	0.0007067	1415
1416	2005056	2839159296	37.62978	11.22934	0.0007062	1416
1417	2007889	2845178713	37.64306	11.23199	0.0007057	1417
1418	2010724	2851206632	37.65634	11.23463	0.0007052	1418
1419	2013561	2857243059	37.66962	11.23727	0.0007047	1419
1420	2016400	2863288000	37.68289	11.23991	0.0007042	1420
1421	2019241	2869341461	37.69615	11.24255	0.0007037	1421
1422	2022084	2875403448	37.70942	11.24518	0.0007032	1422
1423	2024929	2881473967	37.72267	11.24782	0.0007027	1423
1424	2027776	2887553024	37.73592	11.25045	0.0007022	1424
1425	2030625	2893640625	37.74917	11.25309	0.0007018	1425
1426	2033476	2899736776	37.76242	11.25572	0.0007013	1426
1427	2036329	2905841483	37.77565	11.25835	0.0007008	1427
1428	2039184	2911954752	37.78889	11.26098	0.0007003	1428
1429	2042041	2918076589	37.80212	11.26360	0.0006998	1429
1430	2044900	2924207000	37.81534	11.26623	0.0006993	1430
1431	2047761	2930345991	37.82856	11.26886	0.0006988	1431
1432	2050624	2936493568	37.84178	11.27148	0.0006983	1432
1433	2053489	2942649737	37.85499	11.27410	0.0006978	1433
1434	2056356	2948814504	37.86819	11.27673	0.0006974	1434
1435	2059225	2954987875	37.88139	11.27935	0.0006969	1435
1436	2062096	2961169856	37.89459	11.28197	0.0006964	1436
1437	2064969	2967360453	37.90778	11.28458	0.0006959	1437
1438	2067844	2973559672	37.92097	11.28720	0.0006954	1438
1439	2070721	2979767519	37.93415	11.28982	0.0006949	1439
1440	2073600	2985984000	37.94733	11.29243	0.0006944	1440
1441	2076481	2992209121	37.96051	11.29505	0.0006940	1441
1442	2079364	2998442888	37.97368	11.29766	0.0006935	1442
1443	2082249	3004685307	37.98684	11.30027	0.0006930	1443
1444	2085136	3010936384	38.00000	11.30288	0.0006925	1444
1445	2088025	3017196125	38.01316	11.30549	0.0006920	1445
1446	2090916	3023464536	38.02631	11.30809	0.0006916	1446
1447	2093809	3029741623	38.03945	11.31070	0.0006911	1447
1448	2096704	3036027392	38.05260	11.31331	0.0006906	1448
1449	2099601	3042321849	38.06573	11.31591	0.0006901	1449
1450	2102500	3048625000	38.07887	11.31851	0.0006897	1450

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1451 to 1500

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1451	2105401	3054936851	38.09199	11.32111	0.0006892	1451
1452	2108304	3061257408	38.10512	11.32371	0.0006887	1452
1453	2111209	3067586677	38.11824	11.32631	0.0006882	1453
1454	2114116	3073924664	38.13135	11.32891	0.0006878	1454
1455	2117025	3080271375	38.14446	11.33151	0.0006873	1455
1456	2119936	3086626816	38.15757	11.33410	0.0006868	1456
1457	2122849	3092990993	38.17067	11.33670	0.0006863	1457
1458	2125764	3099363912	38.18377	11.33929	0.0006859	1458
1459	2128681	3105745579	38.19686	11.34188	0.0006854	1459
1460	2131600	3112136000	38.20995	11.34447	0.0006849	1460
1461	2134521	3118535181	38.22303	11.34706	0.0006845	1461
1462	2137444	3124943128	38.23611	11.34965	0.0006840	1462
1463	2140369	3131359847	38.24918	11.35224	0.0006835	1463
1464	2143296	3137785344	38.26225	11.35482	0.0006831	1464
1465	2146225	3144219625	38.27532	11.35741	0.0006826	1465
1466	2149156	3150662696	38.28838	11.35999	0.0006821	1466
1467	2152089	3157114563	38.30144	11.36257	0.0006817	1467
1468	2155024	3163575232	38.31449	11.36515	0.0006812	1468
1469	2157961	3170044709	38.32754	11.36773	0.0006807	1469
1470	2160900	3176523000	38.34058	11.37031	0.0006803	1470
1471	2163841	3183010111	38.35362	11.37289	0.0006798	1471
1472	2166784	3189506048	38.36665	11.37547	0.0006793	1472
1473	2169729	3196010817	38.37968	11.37804	0.0006789	1473
1474	2172676	3202524424	38.39271	11.38062	0.0006784	1474
1475	2175625	3209046875	38.40573	11.38319	0.0006780	1475
1476	2178576	3215578176	38.41875	11.38576	0.0006775	1476
1477	2181529	3222118333	38.43176	11.38833	0.0006770	1477
1478	2184484	3228667352	38.44477	11.39090	0.0006766	1478
1479	2187441	3235225239	38.45777	11.39347	0.0006761	1479
1480	2190400	3241792000	38.47077	11.39604	0.0006757	1480
1481	2193361	3248367641	38.48376	11.39860	0.0006752	1481
1482	2196324	3254952168	38.49675	11.40117	0.0006748	1482
1483	2199289	3261545587	38.50974	11.40373	0.0006743	1483
1484	2202256	3268147904	38.52272	11.40630	0.0006739	1484
1485	2205225	3274759125	38.53570	11.40886	0.0006734	1485
1486	2208196	3281379256	38.54867	11.41142	0.0006729	1486
1487	2211169	3288008303	38.56164	11.41398	0.0006725	1487
1488	2214144	3294646272	38.57460	11.41653	0.0006720	1488
1489	2217121	3301293169	38.58756	11.41909	0.0006716	1489
1490	2220100	3307949000	38.60052	11.42165	0.0006711	1490
1491	2223081	3314613771	38.61347	11.42420	0.0006707	1491
1492	2226064	3321287488	38.62642	11.42676	0.0006702	1492
1493	2229049	3327970157	38.63936	11.42931	0.0006698	1493
1494	2232036	3334661784	38.65230	11.43186	0.0006693	1494
1495	2235025	3341362375	38.66523	11.43441	0.0006689	1495
1496	2238016	3348071936	38.67816	11.43696	0.0006684	1496
1497	2241009	3354790473	38.69108	11.43951	0.0006680	1497
1498	2244004	3361517992	38.70400	11.44205	0.0006676	1498
1499	2247001	3368254499	38.71692	11.44460	0.0006671	1499
1500	2250000	3375000000	38.72983	11.44714	0.0006667	1500

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1501 to 1550

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1501	2253001	3381754501	38.74274	11.44969	0.0006662	1501
1502	2256004	3388518008	38.75564	11.45223	0.0006658	1502
1503	2259009	3395290527	38.76854	11.45477	0.0006653	1503
1504	2262016	3402072064	38.78144	11.45731	0.0006649	1504
1505	2265025	3408862625	38.79433	11.45985	0.0006645	1505
1506	2268036	3415662216	38.80722	11.46238	0.0006640	1506
1507	2271049	3422470843	38.82010	11.46492	0.0006636	1507
1508	2274064	3429288512	38.83298	11.46746	0.0006631	1508
1509	2277081	3436115229	38.84585	11.46999	0.0006627	1509
1510	2280100	3442951000	38.85872	11.47252	0.0006623	1510
1511	2283121	3449795831	38.87158	11.47506	0.0006618	1511
1512	2286144	3456649728	38.88444	11.47759	0.0006614	1512
1513	2289169	3463512697	38.89730	11.48012	0.0006609	1513
1514	2292196	3470384744	38.91015	11.48265	0.0006605	1514
1515	2295225	3477265875	38.92300	11.48517	0.0006601	1515
1516	2298256	3484156096	38.93584	11.48770	0.0006596	1516
1517	2301289	3491055413	38.94868	11.49022	0.0006592	1517
1518	2304324	3497963832	38.96152	11.49275	0.0006588	1518
1519	2307361	3504881359	38.97435	11.49527	0.0006583	1519
1520	2310400	3511808000	38.98718	11.49779	0.0006579	1520
1521	2313441	3518743761	39.00000	11.50032	0.0006575	1521
1522	2316484	3525688648	39.01282	11.50283	0.0006570	1522
1523	2319529	3532642667	39.02563	11.50535	0.0006566	1523
1524	2322576	3539605824	39.03844	11.50787	0.0006562	1524
1525	2325625	3546578125	39.05125	11.51039	0.0006557	1525
1526	2328676	3553559576	39.06405	11.51290	0.0006553	1526
1527	2331729	3560550183	39.07685	11.51542	0.0006549	1527
1528	2334784	3567549952	39.08964	11.51793	0.0006545	1528
1529	2337841	3574558889	39.10243	11.52044	0.0006540	1529
1530	2340900	3581577000	39.11521	11.52295	0.0006536	1530
1531	2343961	3588604291	39.12800	11.52546	0.0006532	1531
1532	2347024	3595640768	39.14077	11.52797	0.0006527	1532
1533	2350089	3602686437	39.15354	11.53048	0.0006523	1533
1534	2353156	3609741304	39.16631	11.53299	0.0006519	1534
1535	2356225	3616805375	39.17908	11.53549	0.0006515	1535
1536	2359296	3623878656	39.19184	11.53800	0.0006510	1536
1537	2362369	3630961153	39.20459	11.54050	0.0006506	1537
1538	2365444	3638052872	39.21734	11.54300	0.0006502	1538
1539	2368521	3645153819	39.23009	11.54550	0.0006498	1539
1540	2371600	3652264000	39.24283	11.54800	0.0006494	1540
1541	2374681	3659383421	39.25557	11.55050	0.0006489	1541
1542	2377764	3666512088	39.26831	11.55300	0.0006485	1542
1543	2380849	3673650007	39.28104	11.55550	0.0006481	1543
1544	2383936	3680797184	39.29377	11.55799	0.0006477	1544
1545	2387025	3687953625	39.30649	11.56049	0.0006472	1545
1546	2390116	3695119336	39.31921	11.56298	0.0006468	1546
1547	2393209	3702294323	39.33192	11.56547	0.0006464	1547
1548	2396304	3709478592	39.34463	11.56797	0.0006460	1548
1549	2399401	3716672149	39.35734	11.57046	0.0006456	1549
1550	2402500	3723875000	39.37004	11.57295	0.0006452	1550

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1551 to 1600

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1551	2405601	3731087151	39.38274	11.57543	0.0006447	1551
1552	2408704	3738308608	39.39543	11.57792	0.0006443	1552
1553	2411809	3745539377	39.40812	11.58041	0.0006439	1553
1554	2414916	3752779464	39.42081	11.58289	0.0006435	1554
1555	2418025	3760028875	39.43349	11.58538	0.0006431	1555
1556	2421136	3767287616	39.44617	11.58786	0.0006427	1556
1557	2424249	3774555693	39.45884	11.59034	0.0006423	1557
1558	2427364	3781833112	39.47151	11.59282	0.0006418	1558
1559	2430481	3789119879	39.48417	11.59530	0.0006414	1559
1560	2433600	3796416000	39.49684	11.59778	0.0006410	1560
1561	2436721	3803721481	39.50949	11.60026	0.0006406	1561
1562	2439844	3811036328	39.52215	11.60273	0.0006402	1562
1563	2442969	3818360547	39.53479	11.60521	0.0006398	1563
1564	2446096	3825694144	39.54744	11.60768	0.0006394	1564
1565	2449225	3833037125	39.56008	11.61016	0.0006390	1565
1566	2452356	3840389496	39.57272	11.61263	0.0006386	1566
1567	2455489	3847751263	39.58535	11.61510	0.0006382	1567
1568	2458624	3855122432	39.59798	11.61757	0.0006378	1568
1569	2461761	3862503009	39.61060	11.62004	0.0006373	1569
1570	2464900	3869893000	39.62323	11.62251	0.0006369	1570
1571	2468041	3877292411	39.63584	11.62498	0.0006365	1571
1572	2471184	3884701248	39.64846	11.62744	0.0006361	1572
1573	2474329	3892119517	39.66106	11.62991	0.0006357	1573
1574	2477476	3899547224	39.67367	11.63237	0.0006353	1574
1575	2480625	3906984375	39.68627	11.63483	0.0006349	1575
1576	2483776	3914430976	39.69887	11.63730	0.0006345	1576
1577	2486929	3921887033	39.71146	11.63976	0.0006341	1577
1578	2490084	3929352552	39.72405	11.64222	0.0006337	1578
1579	2493241	3936827539	39.73663	11.64468	0.0006333	1579
1580	2496400	3944312000	39.74921	11.64713	0.0006329	1580
1581	2499561	3951805941	39.76179	11.64959	0.0006325	1581
1582	2502724	3959309368	39.77436	11.65205	0.0006321	1582
1583	2505889	3966822287	39.78693	11.65450	0.0006317	1583
1584	2509056	3974344704	39.79950	11.65695	0.0006313	1584
1585	2512225	3981876625	39.81206	11.65941	0.0006309	1585
1586	2515396	3989418056	39.82462	11.66186	0.0006305	1586
1587	2518569	3996969003	39.83717	11.66431	0.0006301	1587
1588	2521744	4004529472	39.84972	11.66676	0.0006297	1588
1589	2524921	4012099469	39.86226	11.66921	0.0006293	1589
1590	2528100	4019679000	39.87480	11.67165	0.0006289	1590
1591	2531281	4027268071	39.88734	11.67410	0.0006285	1591
1592	2534464	4034866688	39.89987	11.67654	0.0006281	1592
1593	2537649	4042474857	39.91240	11.67899	0.0006277	1593
1594	2540836	4050092584	39.92493	11.68143	0.0006274	1594
1595	2544025	4057719875	39.93745	11.68387	0.0006270	1595
1596	2547216	4065356736	39.94997	11.68632	0.0006266	1596
1597	2550409	4073003173	39.96248	11.68876	0.0006262	1597
1598	2553604	4080659192	39.97499	11.69120	0.0006258	1598
1599	2556801	4088324799	39.98750	11.69363	0.0006254	1599
1600	2560000	4096000000	40.00000	11.69607	0.0006250	1600

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1601 to 1650

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1601	2563201	4103684801	40.01250	11.69851	0.0006246	1601
1602	2566404	4111379208	40.02499	11.70094	0.0006242	1602
1603	2569609	4119083227	40.03748	11.70338	0.0006238	1603
1604	2572816	4126796864	40.04997	11.70581	0.0006234	1604
1605	2576025	4134520125	40.06245	11.70824	0.0006231	1605
1606	2579236	4142253016	40.07493	11.71067	0.0006227	1606
1607	2582449	4149995543	40.08740	11.71310	0.0006223	1607
1608	2585664	4157747712	40.09988	11.71553	0.0006219	1608
1609	2588881	4165509529	40.11234	11.71796	0.0006215	1609
1610	2592100	4173281000	40.12481	11.72039	0.0006211	1610
1611	2595321	4181062131	40.13726	11.72281	0.0006207	1611
1612	2598544	4188852928	40.14972	11.72524	0.0006203	1612
1613	2601769	4196653397	40.16217	11.72766	0.0006200	1613
1614	2604996	4204463544	40.17462	11.73009	0.0006196	1614
1615	2608225	4212283375	40.18706	11.73251	0.0006192	1615
1616	2611456	4220112896	40.19950	11.73493	0.0006188	1616
1617	2614689	4227952113	40.21194	11.73735	0.0006184	1617
1618	2617924	4235801032	40.22437	11.73977	0.0006180	1618
1619	2621161	4243659659	40.23680	11.74219	0.0006177	1619
1620	2624400	4251528000	40.24922	11.74460	0.0006173	1620
1621	2627641	4259406061	40.26164	11.74702	0.0006169	1621
1622	2630884	4267293848	40.27406	11.74943	0.0006165	1622
1623	2634129	4275191367	40.28647	11.75185	0.0006161	1623
1624	2637376	4283098624	40.29888	11.75426	0.0006158	1624
1625	2640625	4291015625	40.31129	11.75667	0.0006154	1625
1626	2643876	4298942376	40.32369	11.75908	0.0006150	1626
1627	2647129	4306878883	40.33609	11.76149	0.0006146	1627
1628	2650384	4314825152	40.34848	11.76390	0.0006143	1628
1629	2653641	4322781189	40.36087	11.76631	0.0006139	1629
1630	2656900	4330747000	40.37326	11.76872	0.0006135	1630
1631	2660161	4338722591	40.38564	11.77113	0.0006131	1631
1632	2663424	4346707968	40.39802	11.77353	0.0006127	1632
1633	2666689	4354703137	40.41039	11.77593	0.0006124	1633
1634	2669956	4362708104	40.42277	11.77834	0.0006120	1634
1635	2673225	4370722875	40.43513	11.78074	0.0006116	1635
1636	2676496	4378747456	40.44750	11.78314	0.0006112	1636
1637	2679769	4386781853	40.45986	11.78554	0.0006109	1637
1638	2683044	4394826072	40.47221	11.78794	0.0006105	1638
1639	2686321	4402880119	40.48456	11.79034	0.0006101	1639
1640	2689600	4410944000	40.49691	11.79274	0.0006098	1640
1641	2692881	4419017721	40.50926	11.79513	0.0006094	1641
1642	2696164	4427101288	40.52160	11.79753	0.0006090	1642
1643	2699449	4435194707	40.53394	11.79992	0.0006086	1643
1644	2702736	4443297984	40.54627	11.80232	0.0006083	1644
1645	2706025	4451411125	40.55860	11.80471	0.0006079	1645
1646	2709316	4459534136	40.57093	11.80710	0.0006075	1646
1647	2712609	4467667023	40.58325	11.80949	0.0006072	1647
1648	2715904	4475809792	40.59557	11.81188	0.0006068	1648
1649	2719201	4483962449	40.60788	11.81427	0.0006064	1649
1650	2722500	4492125000	40.62019	11.81666	0.0006061	1650

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1651 to 1700

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1651	2725801	4500297451	40.63250	11.81904	0.0006057	1651
1652	2729104	4508479808	40.64480	11.82143	0.0006053	1652
1653	2732409	4516672077	40.65710	11.82381	0.0006050	1653
1654	2735716	4524874264	40.66940	11.82620	0.0006046	1654
1655	2739025	4533086375	40.68169	11.82858	0.0006042	1655
1656	2742336	4541308416	40.69398	11.83096	0.0006039	1656
1657	2745649	4549540393	40.70626	11.83334	0.0006035	1657
1658	2748964	4557782312	40.71855	11.83572	0.0006031	1658
1659	2752281	4566034179	40.73082	11.83810	0.0006028	1659
1660	2755600	4574296000	40.74310	11.84048	0.0006024	1660
1661	2758921	4582567781	40.75537	11.84286	0.0006020	1661
1662	2762244	4590849528	40.76763	11.84523	0.0006017	1662
1663	2765569	4599141247	40.77990	11.84761	0.0006013	1663
1664	2768896	4607442944	40.79216	11.84998	0.0006010	1664
1665	2772225	4615754625	40.80441	11.85236	0.0006006	1665
1666	2775556	4624076296	40.81666	11.85473	0.0006002	1666
1667	2778889	4632407963	40.82891	11.85710	0.0005999	1667
1668	2782224	4640749632	40.84116	11.85947	0.0005995	1668
1669	2785561	4649101309	40.85340	11.86184	0.0005992	1669
1670	2788900	4657463000	40.86563	11.86421	0.0005988	1670
1671	2792241	4665834711	40.87787	11.86658	0.0005984	1671
1672	2795584	4674216448	40.89010	11.86894	0.0005981	1672
1673	2798929	4682608217	40.90232	11.87131	0.0005977	1673
1674	2802276	4691010024	40.91455	11.87367	0.0005974	1674
1675	2805625	4699421875	40.92676	11.87604	0.0005970	1675
1676	2808976	4707843776	40.93898	11.87840	0.0005967	1676
1677	2812329	4716275733	40.95119	11.88076	0.0005963	1677
1678	2815684	4724717752	40.96340	11.88312	0.0005959	1678
1679	2819041	4733169839	40.97560	11.88548	0.0005956	1679
1680	2822400	4741632000	40.98780	11.88784	0.0005952	1680
1681	2825761	4750104241	41.00000	11.89020	0.0005949	1681
1682	2829124	4758586568	41.01219	11.89256	0.0005945	1682
1683	2832489	4767078987	41.02438	11.89492	0.0005942	1683
1684	2835856	4775581504	41.03657	11.89727	0.0005938	1684
1685	2839225	4784094125	41.04875	11.89963	0.0005935	1685
1686	2842596	4792616856	41.06093	11.90198	0.0005931	1686
1687	2845969	4801149703	41.07311	11.90433	0.0005928	1687
1688	2849344	4809692672	41.08528	11.90668	0.0005924	1688
1689	2852721	4818245769	41.09745	11.90903	0.0005921	1689
1690	2856100	4826809000	41.10961	11.91138	0.0005917	1690
1691	2859481	4835382371	41.12177	11.91373	0.0005914	1691
1692	2862864	4843965888	41.13393	11.91608	0.0005910	1692
1693	2866249	4852559557	41.14608	11.91843	0.0005907	1693
1694	2869636	4861163384	41.15823	11.92077	0.0005903	1694
1695	2873025	4869777375	41.17038	11.92312	0.0005900	1695
1696	2876416	4878401536	41.18252	11.92546	0.0005896	1696
1697	2879809	4887035873	41.19466	11.92781	0.0005893	1697
1698	2883204	4895680392	41.20680	11.93015	0.0005889	1698
1699	2886601	4904335099	41.21893	11.93249	0.0005886	1699
1700	2890000	4913000000	41.23106	11.93483	0.0005882	1700

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1701 to 1750

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1701	2893401	4921675101	41.24318	11.93717	0.0005879	1701
1702	2896804	4930360408	41.25530	11.93951	0.0005875	1702
1703	2900209	4939055927	41.26742	11.94185	0.0005872	1703
1704	2903616	4947761664	41.27953	11.94419	0.0005869	1704
1705	2907025	4956477625	41.29165	11.94652	0.0005865	1705
1706	2910436	4965203816	41.30375	11.94886	0.0005862	1706
1707	2913849	4973940243	41.31586	11.95119	0.0005858	1707
1708	2917264	4982686912	41.32796	11.95352	0.0005855	1708
1709	2920681	4991443829	41.34005	11.95586	0.0005851	1709
1710	2924100	5000211000	41.35215	11.95819	0.0005848	1710
1711	2927521	5008988431	41.36424	11.96052	0.0005845	1711
1712	2930944	5017776128	41.37632	11.96285	0.0005841	1712
1713	2934369	5026574097	41.38840	11.96518	0.0005838	1713
1714	2937796	5035382344	41.40048	11.96750	0.0005834	1714
1715	2941225	5044200875	41.41256	11.96983	0.0005831	1715
1716	2944656	5053029696	41.42463	11.97216	0.0005828	1716
1717	2948089	5061868813	41.43670	11.97448	0.0005824	1717
1718	2951524	5070718232	41.44876	11.97681	0.0005821	1718
1719	2954961	5079577959	41.46082	11.97913	0.0005817	1719
1720	2958400	5088448000	41.47288	11.98145	0.0005814	1720
1721	2961841	5097328361	41.48494	11.98377	0.0005811	1721
1722	2965284	5106219048	41.49699	11.98610	0.0005807	1722
1723	2968729	5115120067	41.50904	11.98841	0.0005804	1723
1724	2972176	5124031424	41.52108	11.99073	0.0005800	1724
1725	2975625	5132953125	41.53312	11.99305	0.0005797	1725
1726	2979076	5141885176	41.54516	11.99537	0.0005794	1726
1727	2982529	5150827583	41.55719	11.99768	0.0005790	1727
1728	2985984	5159780352	41.56922	12.00000	0.0005787	1728
1729	2989441	5168743489	41.58125	12.00231	0.0005784	1729
1730	2992900	5177717000	41.59327	12.00463	0.0005780	1730
1731	2996361	5186700891	41.60529	12.00694	0.0005777	1731
1732	2999824	5195695168	41.61730	12.00925	0.0005774	1732
1733	3003289	5204699837	41.62932	12.01156	0.0005770	1733
1734	3006756	5213714904	41.64133	12.01387	0.0005767	1734
1735	3010225	5222740375	41.65333	12.01618	0.0005764	1735
1736	3013696	5231776256	41.66533	12.01849	0.0005760	1736
1737	3017169	5240822553	41.67733	12.02080	0.0005757	1737
1738	3020644	5249879272	41.68933	12.02310	0.0005754	1738
1739	3024121	5258946419	41.70132	12.02541	0.0005750	1739
1740	3027600	5268024000	41.71331	12.02771	0.0005747	1740
1741	3031081	5277112021	41.72529	12.03002	0.0005744	1741
1742	3034564	5286210488	41.73727	12.03232	0.0005741	1742
1743	3038049	5295319407	41.74925	12.03462	0.0005737	1743
1744	3041536	5304438784	41.76123	12.03692	0.0005734	1744
1745	3045025	5313568625	41.77320	12.03922	0.0005731	1745
1746	3048516	5322708936	41.78516	12.04152	0.0005727	1746
1747	3052009	5331859723	41.79713	12.04382	0.0005724	1747
1748	3055504	5341020992	41.80909	12.04612	0.0005721	1748
1749	3059001	5350192749	41.82105	12.04842	0.0005718	1749
1750	3062500	5359375000	41.83300	12.05071	0.0005714	1750

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1751 to 1800

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1751	3066001	5368567751	41.84495	12.05301	0.0005711	1751
1752	3069504	5377771008	41.85690	12.05530	0.0005708	1752
1753	3073009	5386984777	41.86884	12.05759	0.0005705	1753
1754	3076516	5396209064	41.88078	12.05989	0.0005701	1754
1755	3080025	5405443875	41.89272	12.06218	0.0005698	1755
1756	3083536	5414689216	41.90465	12.06447	0.0005695	1756
1757	3087049	5423945093	41.91658	12.06676	0.0005692	1757
1758	3090564	5433211512	41.92851	12.06905	0.0005688	1758
1759	3094081	5442488479	41.94043	12.07133	0.0005685	1759
1760	3097600	5451776000	41.95235	12.07362	0.0005682	1760
1761	3101121	5461074081	41.96427	12.07591	0.0005679	1761
1762	3104644	5470382728	41.97618	12.07819	0.0005675	1762
1763	3108169	5479701947	41.98809	12.08048	0.0005672	1763
1764	3111696	5489031744	42.00000	12.08276	0.0005669	1764
1765	3115225	5498372125	42.01190	12.08504	0.0005666	1765
1766	3118756	5507723096	42.02380	12.08733	0.0005663	1766
1767	3122289	5517084663	42.03570	12.08961	0.0005659	1767
1768	3125824	5526456832	42.04759	12.09189	0.0005656	1768
1769	3129361	5535839609	42.05948	12.09417	0.0005653	1769
1770	3132900	5545233000	42.07137	12.09645	0.0005650	1770
1771	3136441	5554637011	42.08325	12.09872	0.0005647	1771
1772	3139984	5564051648	42.09513	12.10100	0.0005643	1772
1773	3143529	5573476917	42.10701	12.10328	0.0005640	1773
1774	3147076	5582912824	42.11888	12.10555	0.0005637	1774
1775	3150625	5592359375	42.13075	12.10782	0.0005634	1775
1776	3154176	5601816576	42.14262	12.11010	0.0005631	1776
1777	3157729	5611284433	42.15448	12.11237	0.0005627	1777
1778	3161284	5620762952	42.16634	12.11464	0.0005624	1778
1779	3164841	5630252139	42.17819	12.11691	0.0005621	1779
1780	3168400	5639752000	42.19005	12.11918	0.0005618	1780
1781	3171961	5649262541	42.20190	12.12145	0.0005615	1781
1782	3175524	5658783768	42.21374	12.12372	0.0005612	1782
1783	3179089	5668315687	42.22558	12.12599	0.0005609	1783
1784	3182656	5677858304	42.23742	12.12825	0.0005605	1784
1785	3186225	5687411625	42.24926	12.13052	0.0005602	1785
1786	3189796	5696975656	42.26109	12.13278	0.0005599	1786
1787	3193369	5706550403	42.27292	12.13505	0.0005596	1787
1788	3196944	5716135872	42.28475	12.13731	0.0005593	1788
1789	3200521	5725732069	42.29657	12.13957	0.0005590	1789
1790	3204100	5735339000	42.30839	12.14184	0.0005587	1790
1791	3207681	5744956671	42.32021	12.14410	0.0005583	1791
1792	3211264	5754585088	42.33202	12.14636	0.0005580	1792
1793	3214849	5764224257	42.34383	12.14861	0.0005577	1793
1794	3218436	5773874184	42.35564	12.15087	0.0005574	1794
1795	3222025	5783534875	42.36744	12.15313	0.0005571	1795
1796	3225616	5793206336	42.37924	12.15539	0.0005568	1796
1797	3229209	5802888573	42.39104	12.15764	0.0005565	1797
1798	3232804	5812581592	42.40283	12.15990	0.0005562	1798
1799	3236401	5822285399	42.41462	12.16215	0.0005559	1799
1800	3240000	5832000000	42.42641	12.16440	0.0005556	1800

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1801 to 1850

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1801	3243601	5841725401	42.43819	12.16666	0.0005552	1801
1802	3247204	5851461608	42.44997	12.16891	0.0005549	1802
1803	3250809	5861208627	42.46175	12.17116	0.0005546	1803
1804	3254416	5870966464	42.47352	12.17341	0.0005543	1804
1805	3258025	5880735125	42.48529	12.17566	0.0005540	1805
1806	3261636	5890514616	42.49706	12.17791	0.0005537	1806
1807	3265249	5900304943	42.50882	12.18015	0.0005534	1807
1808	3268864	5910106112	42.52058	12.18240	0.0005531	1808
1809	3272481	5919918129	42.53234	12.18464	0.0005528	1809
1810	3276100	5929741000	42.54409	12.18689	0.0005525	1810
1811	3279721	5939574731	42.55585	12.18913	0.0005522	1811
1812	3283344	5949419328	42.56759	12.19138	0.0005519	1812
1813	3286969	5959274797	42.57934	12.19362	0.0005516	1813
1814	3290596	5969141144	42.59108	12.19586	0.0005513	1814
1815	3294225	5979018375	42.60282	12.19810	0.0005510	1815
1816	3297856	5988906496	42.61455	12.20034	0.0005507	1816
1817	3301489	5998805513	42.62628	12.20258	0.0005504	1817
1818	3305124	6008715432	42.63801	12.20482	0.0005501	1818
1819	3308761	6018636259	42.64974	12.20705	0.0005498	1819
1820	3312400	6028568000	42.66146	12.20929	0.0005495	1820
1821	3316041	6038510661	42.67318	12.21153	0.0005491	1821
1822	3319684	6048464248	42.68489	12.21376	0.0005488	1822
1823	3323329	6058428767	42.69660	12.21600	0.0005485	1823
1824	3326976	6068404224	42.70831	12.21823	0.0005482	1824
1825	3330625	6078390625	42.72002	12.22046	0.0005479	1825
1826	3334276	6088387976	42.73172	12.22269	0.0005476	1826
1827	3337929	6098396283	42.74342	12.22492	0.0005473	1827
1828	3341584	6108415552	42.75512	12.22715	0.0005470	1828
1829	3345241	6118445789	42.76681	12.22938	0.0005467	1829
1830	3348900	6128487000	42.77850	12.23161	0.0005464	1830
1831	3352561	6138539191	42.79019	12.23384	0.0005461	1831
1832	3356224	6148602368	42.80187	12.23607	0.0005459	1832
1833	3359889	6158676537	42.81355	12.23829	0.0005456	1833
1834	3363556	6168761704	42.82523	12.24052	0.0005453	1834
1835	3367225	6178857875	42.83690	12.24274	0.0005450	1835
1836	3370896	6188965056	42.84857	12.24497	0.0005447	1836
1837	3374569	6199083253	42.86024	12.24719	0.0005444	1837
1838	3378244	6209212472	42.87190	12.24941	0.0005441	1838
1839	3381921	6219352719	42.88356	12.25163	0.0005438	1839
1840	3385600	6229504000	42.89522	12.25385	0.0005435	1840
1841	3389281	6239666321	42.90688	12.25607	0.0005432	1841
1842	3392964	6249839688	42.91853	12.25829	0.0005429	1842
1843	3396649	6260024107	42.93018	12.26051	0.0005426	1843
1844	3400336	6270219584	42.94182	12.26272	0.0005423	1844
1845	3404025	6280426125	42.95346	12.26494	0.0005420	1845
1846	3407716	6290643736	42.96510	12.26716	0.0005417	1846
1847	3411409	6300872423	42.97674	12.26937	0.0005414	1847
1848	3415104	6311112192	42.98837	12.27158	0.0005411	1848
1849	3418801	6321363049	43.00000	12.27380	0.0005408	1849
1850	3422500	6331625000	43.01163	12.27601	0.0005405	1850

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1851 to 1900

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1851	3426201	6341898051	43.02325	12.27822	0.0005402	1851
1852	3429904	6352182208	43.03487	12.28043	0.0005400	1852
1853	3433609	6362477477	43.04649	12.28264	0.0005397	1853
1854	3437316	6372783864	43.05810	12.28485	0.0005394	1854
1855	3441025	6383101375	43.06971	12.28706	0.0005391	1855
1856	3444736	6393430016	43.08132	12.28927	0.0005388	1856
1857	3448449	6403769793	43.09292	12.29147	0.0005385	1857
1858	3452164	6414120712	43.10452	12.29368	0.0005382	1858
1859	3455881	6424482779	43.11612	12.29589	0.0005379	1859
1860	3459600	6434856000	43.12772	12.29809	0.0005376	1860
1861	3463321	6445240381	43.13931	12.30029	0.0005373	1861
1862	3467044	6455635928	43.15090	12.30250	0.0005371	1862
1863	3470769	6466042647	43.16248	12.30470	0.0005368	1863
1864	3474496	6476460544	43.17407	12.30690	0.0005365	1864
1865	3478225	6486889625	43.18565	12.30910	0.0005362	1865
1866	3481956	6497329896	43.19722	12.31130	0.0005359	1866
1867	3485689	6507781363	43.20880	12.31350	0.0005356	1867
1868	3489424	6518244032	43.22037	12.31570	0.0005353	1868
1869	3493161	6528717909	43.23193	12.31789	0.0005350	1869
1870	3496900	6539203000	43.24350	12.32009	0.0005348	1870
1871	3500641	6549699311	43.25506	12.32229	0.0005345	1871
1872	3504384	6560206848	43.26662	12.32448	0.0005342	1872
1873	3508129	6570725617	43.27817	12.32667	0.0005339	1873
1874	3511876	6581255624	43.28972	12.32887	0.0005336	1874
1875	3515625	6591796875	43.30127	12.33106	0.0005333	1875
1876	3519376	6602349376	43.31282	12.33325	0.0005330	1876
1877	3523129	6612913133	43.32436	12.33544	0.0005328	1877
1878	3526884	6623488152	43.33590	12.33763	0.0005325	1878
1879	3530641	6634074439	43.34743	12.33982	0.0005322	1879
1880	3534400	6644672000	43.35897	12.34201	0.0005319	1880
1881	3538161	6655280841	43.37050	12.34420	0.0005316	1881
1882	3541924	6665900968	43.38202	12.34639	0.0005313	1882
1883	3545689	6676532387	43.39355	12.34857	0.0005311	1883
1884	3549456	6687175104	43.40507	12.35076	0.0005308	1884
1885	3553225	6697829125	43.41659	12.35294	0.0005305	1885
1886	3556996	6708494456	43.42810	12.35513	0.0005302	1886
1887	3560769	6719171103	43.43961	12.35731	0.0005299	1887
1888	3564544	6729859072	43.45112	12.35949	0.0005297	1888
1889	3568321	6740558369	43.46263	12.36167	0.0005294	1889
1890	3572100	6751269000	43.47413	12.36386	0.0005291	1890
1891	3575881	6761990971	43.48563	12.36604	0.0005288	1891
1892	3579664	6772724288	43.49713	12.36822	0.0005285	1892
1893	3583449	6783468957	43.50862	12.37039	0.0005283	1893
1894	3587236	6794224984	43.52011	12.37257	0.0005280	1894
1895	3591025	6804992375	43.53160	12.37475	0.0005277	1895
1896	3594816	6815771136	43.54308	12.37693	0.0005274	1896
1897	3598609	6826561273	43.55456	12.37910	0.0005271	1897
1898	3602404	6837362792	43.56604	12.38128	0.0005269	1898
1899	3606201	6848175699	43.57752	12.38345	0.0005266	1899
1900	3610000	6859000000	43.58899	12.38562	0.0005263	1900

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1901 to 1950

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1901	3613801	6869835701	43.60046	12.38780	0.0005260	1901
1902	3617604	6880682808	43.61192	12.38997	0.0005258	1902
1903	3621409	6891541327	43.62339	12.39214	0.0005255	1903
1904	3625216	6902411264	43.63485	12.39431	0.0005252	1904
1905	3629025	6913292625	43.64631	12.39648	0.0005249	1905
1906	3632836	6924185416	43.65776	12.39865	0.0005247	1906
1907	3636649	6935089643	43.66921	12.40082	0.0005244	1907
1908	3640464	6946005312	43.68066	12.40298	0.0005241	1908
1909	3644281	6956932429	43.69210	12.40515	0.0005238	1909
1910	3648100	6967871000	43.70355	12.40731	0.0005236	1910
1911	3651921	6978821031	43.71499	12.40948	0.0005233	1911
1912	3655744	6989782528	43.72642	12.41164	0.0005230	1912
1913	3659569	7000755497	43.73786	12.41381	0.0005227	1913
1914	3663396	7011739944	43.74929	12.41597	0.0005225	1914
1915	3667225	7022735875	43.76071	12.41813	0.0005222	1915
1916	3671056	7033743296	43.77214	12.42029	0.0005219	1916
1917	3674889	7044762213	43.78356	12.42245	0.0005216	1917
1918	3678724	7055792632	43.79498	12.42461	0.0005214	1918
1919	3682561	7066834559	43.80639	12.42677	0.0005211	1919
1920	3686400	7077888000	43.81780	12.42893	0.0005208	1920
1921	3690241	7088952961	43.82921	12.43109	0.0005206	1921
1922	3694084	7100029448	43.84062	12.43324	0.0005203	1922
1923	3697929	7111117467	43.85202	12.43540	0.0005200	1923
1924	3701776	7122217024	43.86342	12.43756	0.0005198	1924
1925	3705625	7133328125	43.87482	12.43971	0.0005195	1925
1926	3709476	7144450776	43.88622	12.44186	0.0005192	1926
1927	3713329	7155584983	43.89761	12.44402	0.0005189	1927
1928	3717184	7166730752	43.90900	12.44617	0.0005187	1928
1929	3721041	7177888089	43.92038	12.44832	0.0005184	1929
1930	3724900	7189057000	43.93177	12.45047	0.0005181	1930
1931	3728761	7200237491	43.94315	12.45262	0.0005179	1931
1932	3732624	7211429568	43.95452	12.45477	0.0005176	1932
1933	3736489	7222633237	43.96590	12.45692	0.0005173	1933
1934	3740356	7233848504	43.97727	12.45907	0.0005171	1934
1935	3744225	7245075375	43.98863	12.46121	0.0005168	1935
1936	3748096	7256313856	44.00000	12.46336	0.0005165	1936
1937	3751969	7267563953	44.01136	12.46550	0.0005163	1937
1938	3755844	7278825672	44.02272	12.46765	0.0005160	1938
1939	3759721	7290099019	44.03408	12.46979	0.0005157	1939
1940	3763600	7301384000	44.04543	12.47194	0.0005155	1940
1941	3767481	7312680621	44.05678	12.47408	0.0005152	1941
1942	3771364	7323988888	44.06813	12.47622	0.0005149	1942
1943	3775249	7335308807	44.07947	12.47836	0.0005147	1943
1944	3779136	7346640384	44.09082	12.48050	0.0005144	1944
1945	3783025	7357983625	44.10215	12.48264	0.0005141	1945
1946	3786916	7369338536	44.11349	12.48478	0.0005139	1946
1947	3790809	7380705123	44.12482	12.48692	0.0005136	1947
1948	3794704	7392083392	44.13615	12.48906	0.0005133	1948
1949	3798601	7403473349	44.14748	12.49119	0.0005131	1949
1950	3802500	7414875000	44.15880	12.49333	0.0005128	1950

Copyright 2004, Industrial Press, Inc., New York, NY

Powers, Roots, and Reciprocals From 1951 to 2000

No.	Square	Cube	Sq. Root	Cube Root	Reciprocal	No.
1951	3806401	7426288351	44.17013	12.49547	0.0005126	1951
1952	3810304	7437713408	44.18144	12.49760	0.0005123	1952
1953	3814209	7449150177	44.19276	12.49973	0.0005120	1953
1954	3818116	7460598664	44.20407	12.50187	0.0005118	1954
1955	3822025	7472058875	44.21538	12.50400	0.0005115	1955
1956	3825936	7483530816	44.22669	12.50613	0.0005112	1956
1957	3829849	7495014493	44.23799	12.50826	0.0005110	1957
1958	3833764	7506509912	44.24929	12.51039	0.0005107	1958
1959	3837681	7518017079	44.26059	12.51252	0.0005105	1959
1960	3841600	7529536000	44.27189	12.51465	0.0005102	1960
1961	3845521	7541066681	44.28318	12.51678	0.0005099	1961
1962	3849444	7552609128	44.29447	12.51890	0.0005097	1962
1963	3853369	7564163347	44.30576	12.52103	0.0005094	1963
1964	3857296	7575729344	44.31704	12.52316	0.0005092	1964
1965	3861225	7587307125	44.32832	12.52528	0.0005089	1965
1966	3865156	7598896696	44.33960	12.52741	0.0005086	1966
1967	3869089	7610498063	44.35087	12.52953	0.0005084	1967
1968	3873024	7622111232	44.36215	12.53165	0.0005081	1968
1969	3876961	7633736209	44.37342	12.53378	0.0005079	1969
1970	3880900	7645373000	44.38468	12.53590	0.0005076	1970
1971	3884841	7657021611	44.39595	12.53802	0.0005074	1971
1972	3888784	7668682048	44.40721	12.54014	0.0005071	1972
1973	3892729	7680354317	44.41846	12.54226	0.0005068	1973
1974	3896676	7692038424	44.42972	12.54438	0.0005066	1974
1975	3900625	7703734375	44.44097	12.54649	0.0005063	1975
1976	3904576	7715442176	44.45222	12.54861	0.0005061	1976
1977	3908529	7727161833	44.46347	12.55073	0.0005058	1977
1978	3912484	7738893352	44.47471	12.55284	0.0005056	1978
1979	3916441	7750636739	44.48595	12.55496	0.0005053	1979
1980	3920400	7762392000	44.49719	12.55707	0.0005051	1980
1981	3924361	7774159141	44.50843	12.55919	0.0005048	1981
1982	3928324	7785938168	44.51966	12.56130	0.0005045	1982
1983	3932289	7797729087	44.53089	12.56341	0.0005043	1983
1984	3936256	7809531904	44.54211	12.56552	0.0005040	1984
1985	3940225	7821346625	44.55334	12.56763	0.0005038	1985
1986	3944196	7833173256	44.56456	12.56974	0.0005035	1986
1987	3948169	7845011803	44.57578	12.57185	0.0005033	1987
1988	3952144	7856862272	44.58699	12.57396	0.0005030	1988
1989	3956121	7868724669	44.59821	12.57607	0.0005028	1989
1990	3960100	7880599000	44.60942	12.57818	0.0005025	1990
1991	3964081	7892485271	44.62062	12.58028	0.0005023	1991
1992	3968064	7904383488	44.63183	12.58239	0.0005020	1992
1993	3972049	7916293657	44.64303	12.58449	0.0005018	1993
1994	3976036	7928215784	44.65423	12.58660	0.0005015	1994
1995	3980025	7940149875	44.66542	12.58870	0.0005013	1995
1996	3984016	7952095936	44.67662	12.59081	0.0005010	1996
1997	3988009	7964053973	44.68781	12.59291	0.0005008	1997
1998	3992004	7976023992	44.69899	12.59501	0.0005005	1998
1999	3996001	7988005999	44.71018	12.59711	0.0005003	1999
2000	4000000	8000000000	44.72136	12.59921	0.0005000	2000

Copyright 2004, Industrial Press, Inc., New York, NY

Multiplication Tables for Fractions

Multiplication Table for Common Fractions and Whole Numbers From 1 to 9

	1	2	3	4	5	6	7	8	9
1/64	0.0156	0.0313	0.0469	0.0625	0.0781	0.0938	0.1094	0.1250	0.1406
1/32	0.0313	0.0625	0.0938	0.1250	0.1563	0.1875	0.2188	0.2500	0.2813
3/64	0.0469	0.0938	0.1406	0.1875	0.2344	0.2813	0.3281	0.3750	0.4219
1/16	0.0625	0.1250	0.1875	0.2500	0.3125	0.3750	0.4375	0.5000	0.5625
5/64	0.0781	0.1563	0.2344	0.3125	0.3906	0.4688	0.5469	0.6250	0.7031
3/32	0.0938	0.1875	0.2813	0.3750	0.4688	0.5625	0.6563	0.7500	0.8438
7/64	0.1094	0.2188	0.3281	0.4375	0.5469	0.6563	0.7656	0.8750	0.9844
1/8	0.1250	0.2500	0.3750	0.5000	0.6250	0.7500	0.8750	1.0000	1.1250
9/64	0.1406	0.2813	0.4219	0.5625	0.7031	0.8438	0.9844	1.1250	1.2656
5/32	0.1563	0.3125	0.4688	0.6250	0.7813	0.9375	1.0938	1.2500	1.4063
11/64	0.1719	0.3438	0.5156	0.6875	0.8594	1.0313	1.2031	1.3750	1.5469
3/16	0.1875	0.3750	0.5625	0.7500	0.9375	1.1250	1.3125	1.5000	1.6875
13/64	0.2031	0.4063	0.6094	0.8125	1.0156	1.2188	1.4219	1.6250	1.8281
7/32	0.2188	0.4375	0.6563	0.8750	1.0938	1.3125	1.5313	1.7500	1.9688
15/64	0.2344	0.4688	0.7031	0.9375	1.1719	1.4063	1.6406	1.8750	2.1094
1/4	0.2500	0.5000	0.7500	1.0000	1.2500	1.5000	1.7500	2.0000	2.2500
17/64	0.2656	0.5313	0.7969	1.0625	1.3281	1.5938	1.8594	2.1250	2.3906
9/32	0.2813	0.5625	0.8438	1.1250	1.4063	1.6875	1.9688	2.2500	2.5313
19/64	0.2969	0.5938	0.8906	1.1875	1.4844	1.7813	2.0781	2.3750	2.6719
5/16	0.3125	0.6250	0.9375	1.2500	1.5625	1.8750	2.1875	2.5000	2.8125
21/64	0.3281	0.6563	0.9844	1.3125	1.6406	1.9688	2.2969	2.6250	2.9531
11/32	0.3438	0.6875	1.0313	1.3750	1.7188	2.0625	2.4063	2.7500	3.0938
23/64	0.3594	0.7188	1.0781	1.4375	1.7969	2.1563	2.5156	2.8750	3.2344
3/8	0.3750	0.7500	1.1250	1.5000	1.8750	2.2500	2.6250	3.0000	3.3750
25/64	0.3906	0.7813	1.1719	1.5625	1.9531	2.3438	2.7344	3.1250	3.5156
13/32	0.4063	0.8125	1.2188	1.6250	2.0313	2.4375	2.8438	3.2500	3.6563
27/64	0.4219	0.8438	1.2656	1.6875	2.1094	2.5313	2.9531	3.3750	3.7969
7/16	0.4375	0.8750	1.3125	1.7500	2.1875	2.6250	3.0625	3.5000	3.9375
29/64	0.4531	0.9063	1.3594	1.8125	2.2656	2.7188	3.1719	3.6250	4.0781
15/32	0.4688	0.9375	1.4063	1.8750	2.3438	2.8125	3.2813	3.7500	4.2188
31/64	0.4844	0.9688	1.4531	1.9375	2.4219	2.9063	3.3906	3.8750	4.3594
1/2	0.5000	1.0000	1.5000	2.0000	2.5000	3.0000	3.5000	4.0000	4.5000
33/64	0.5156	1.0313	1.5469	2.0625	2.5781	3.0938	3.6094	4.1250	4.6406
17/32	0.5313	1.0625	1.5938	2.1250	2.6563	3.1875	3.7188	4.2500	4.7813
35/64	0.5469	1.0938	1.6406	2.1875	2.7344	3.2813	3.8281	4.3750	4.9219
9/16	0.5625	1.1250	1.6875	2.2500	2.8125	3.3750	3.9375	4.5000	5.0625
37/64	0.5781	1.1563	1.7344	2.3125	2.8906	3.4688	4.0469	4.6250	5.2031
19/32	0.5938	1.1875	1.7813	2.3750	2.9688	3.5625	4.1563	4.7500	5.3438
39/64	0.6094	1.2188	1.8281	2.4375	3.0469	3.6563	4.2656	4.8750	5.4844
5/8	0.6250	1.2500	1.8750	2.5000	3.1250	3.7500	4.3750	5.0000	5.6250
41/64	0.6406	1.2813	1.9219	2.5625	3.2031	3.8438	4.4844	5.1250	5.7656
21/32	0.6563	1.3125	1.9688	2.6250	3.2813	3.9375	4.5938	5.2500	5.9063
43/64	0.6719	1.3438	2.0156	2.6875	3.3594	4.0313	4.7031	5.3750	6.0469
11/16	0.6875	1.3750	2.0625	2.7500	3.4375	4.1250	4.8125	5.5000	6.1875
45/64	0.7031	1.4063	2.1094	2.8125	3.5156	4.2188	4.9219	5.6250	6.3281
23/32	0.7188	1.4375	2.1563	2.8750	3.5938	4.3125	5.0313	5.7500	6.4688
47/64	0.7344	1.4688	2.2031	2.9375	3.6719	4.4063	5.1406	5.8750	6.6094
3/4	0.7500	1.5000	2.2500	3.0000	3.7500	4.5000	5.2500	6.0000	6.7500
49/64	0.7656	1.5313	2.2969	3.0625	3.8281	4.5938	5.3594	6.1250	6.8906
25/32	0.7813	1.5625	2.3438	3.1250	3.9063	4.6875	5.4688	6.2500	7.0313
51/64	0.7969	1.5938	2.3906	3.1875	3.9844	4.7813	5.5781	6.3750	7.1719
13/16	0.8125	1.6250	2.4375	3.2500	4.0625	4.8750	5.6875	6.5000	7.3125
53/64	0.8281	1.6563	2.4844	3.3125	4.1406	4.9688	5.7969	6.6250	7.4531
27/32	0.8438	1.6875	2.5313	3.3750	4.2188	5.0625	5.9063	6.7500	7.5938
55/64	0.8594	1.7188	2.5781	3.4375	4.2969	5.1563	6.0156	6.8750	7.7344
7/8	0.8750	1.7500	2.6250	3.5000	4.3750	5.2500	6.1250	7.0000	7.8750
57/64	0.8906	1.7813	2.6719	3.5625	4.4531	5.3438	6.2344	7.1250	8.0156
29/32	0.9063	1.8125	2.7188	3.6250	4.5313	5.4375	6.3438	7.2500	8.1563
59/64	0.9219	1.8438	2.7656	3.6875	4.6094	5.5313	6.4531	7.3750	8.2969
15/16	0.9375	1.8750	2.8125	3.7500	4.6875	5.6250	6.5625	7.5000	8.4375
61/64	0.9531	1.9063	2.8594	3.8125	4.7656	5.7188	6.6719	7.6250	8.5781
31/32	0.9688	1.9375	2.9063	3.8750	4.8438	5.8125	6.7813	7.7500	8.7188
63/64	0.9844	1.9688	2.9531	3.9375	4.9219	5.9063	6.8906	7.8750	8.8594

Copyright 2004, Industrial Press, Inc., New York, NY

Multiplication Table for Common Fractions From 1/32 to 1/2

	1/32	1/16	3/32	1/8	5/32	3/16	7/32	1/4	9/32	5/16	11/32	3/8	13/32	7/16	15/32	1/2
1/32	0.00098	0.00195	0.00293	0.00391	0.00488	0.00586	0.00684	0.00781	0.00879	0.00977	0.01074	0.01172	0.01270	0.01367	0.01465	0.01563
1/16	0.00195	0.00391	0.00586	0.00781	0.00977	0.01172	0.01367	0.01563	0.01758	0.01953	0.02148	0.02344	0.02539	0.02734	0.02930	0.03125
3/32	0.00293	0.00586	0.00879	0.01172	0.01465	0.01758	0.02051	0.02344	0.02637	0.02930	0.03223	0.03516	0.03809	0.04102	0.04395	0.04688
1/8	0.00391	0.00781	0.01172	0.01563	0.01953	0.02344	0.02734	0.03125	0.03516	0.03906	0.04297	0.04688	0.05078	0.05469	0.05859	0.06250
5/32	0.00488	0.00977	0.01465	0.01953	0.02441	0.02930	0.03418	0.03906	0.04395	0.04883	0.05371	0.05859	0.06348	0.06836	0.07324	0.07813
3/16	0.00586	0.01172	0.01758	0.02344	0.02930	0.03516	0.04102	0.04688	0.05273	0.05859	0.06445	0.07031	0.07617	0.08203	0.08789	0.09375
7/32	0.00684	0.01367	0.02051	0.02734	0.03418	0.04102	0.04785	0.05469	0.06152	0.06836	0.07520	0.08203	0.08887	0.09570	0.10254	0.10938
1/4	0.00781	0.01563	0.02344	0.03125	0.03906	0.04688	0.05469	0.06250	0.07031	0.07813	0.08594	0.09375	0.10156	0.10938	0.11719	0.12500
9/32	0.00879	0.01758	0.02637	0.03516	0.04395	0.05273	0.06152	0.07031	0.07910	0.08789	0.09668	0.10547	0.11426	0.12305	0.13184	0.14063
5/16	0.00977	0.01953	0.02930	0.03906	0.04883	0.05859	0.06836	0.07813	0.08789	0.09766	0.10742	0.11719	0.12695	0.13672	0.14648	0.15625
11/32	0.01074	0.02148	0.03223	0.04297	0.05371	0.06445	0.07520	0.08594	0.09668	0.10742	0.11816	0.12891	0.13965	0.15039	0.16113	0.17188
3/8	0.01172	0.02344	0.03516	0.04688	0.05859	0.07031	0.08203	0.09375	0.10547	0.11719	0.12891	0.14063	0.15234	0.16406	0.17578	0.18750
13/32	0.01270	0.02539	0.03809	0.05078	0.06348	0.07617	0.08887	0.10156	0.11426	0.12695	0.13965	0.15234	0.16504	0.17773	0.19043	0.20313
7/16	0.01367	0.02734	0.04102	0.05469	0.06836	0.08203	0.09570	0.10938	0.12305	0.13672	0.15039	0.16406	0.17773	0.19141	0.20508	0.21875
15/32	0.01465	0.02930	0.04395	0.05859	0.07324	0.08789	0.10254	0.11719	0.13184	0.14648	0.16113	0.17578	0.19043	0.20508	0.21973	0.23438
1/2	0.01563	0.03125	0.04688	0.06250	0.07813	0.09375	0.10938	0.12500	0.14063	0.15625	0.17188	0.18750	0.20313	0.21875	0.23438	0.25000
17/32	0.01660	0.03320	0.04980	0.06641	0.08301	0.09961	0.11621	0.13281	0.14941	0.16602	0.18262	0.19922	0.21582	0.23242	0.24902	0.26563
9/16	0.01758	0.03516	0.05273	0.07031	0.08789	0.10547	0.12305	0.14063	0.15820	0.17578	0.19336	0.21094	0.22852	0.24609	0.26367	0.28125
19/32	0.01855	0.03711	0.05566	0.07422	0.09277	0.11133	0.12988	0.14844	0.16699	0.18555	0.20410	0.22266	0.24121	0.25977	0.27832	0.29688
5/8	0.01953	0.03906	0.05859	0.07813	0.09766	0.11719	0.13672	0.15625	0.17578	0.19531	0.21484	0.23438	0.25391	0.27344	0.29297	0.31250
21/32	0.02051	0.04102	0.06152	0.08203	0.10254	0.12305	0.14355	0.16406	0.18457	0.20508	0.22559	0.24609	0.26660	0.28711	0.30762	0.32813
11/16	0.02148	0.04297	0.06445	0.08594	0.10742	0.12891	0.15039	0.17188	0.19336	0.21484	0.23633	0.25781	0.27930	0.30078	0.32227	0.34375
23/32	0.02246	0.04492	0.06738	0.08984	0.11230	0.13477	0.15723	0.17969	0.20215	0.22461	0.24707	0.26953	0.29199	0.31445	0.33691	0.35938
3/4	0.02344	0.04688	0.07031	0.09375	0.11719	0.14063	0.16406	0.18750	0.21094	0.23438	0.25781	0.28125	0.30469	0.32813	0.35156	0.37500
25/32	0.02441	0.04883	0.07324	0.09766	0.12207	0.14648	0.17090	0.19531	0.21973	0.24414	0.26855	0.29297	0.31738	0.34180	0.36621	0.39063
13/16	0.02539	0.05078	0.07617	0.10156	0.12695	0.15234	0.17773	0.20313	0.22852	0.25391	0.27930	0.30469	0.33008	0.35547	0.38086	0.40625
27/32	0.02637	0.05273	0.07910	0.10547	0.13184	0.15820	0.18457	0.21094	0.23730	0.26367	0.29004	0.31641	0.34277	0.36914	0.39551	0.42188
7/8	0.02734	0.05469	0.08203	0.10938	0.13672	0.16406	0.19141	0.21875	0.24609	0.27344	0.30078	0.32813	0.35547	0.38281	0.41016	0.43750
29/32	0.02832	0.05664	0.08496	0.11328	0.14160	0.16992	0.19824	0.22656	0.25488	0.28320	0.31152	0.33984	0.36816	0.39648	0.42480	0.45313
15/16	0.02930	0.05859	0.08789	0.11719	0.14648	0.17578	0.20508	0.23438	0.26367	0.29297	0.32227	0.35156	0.38086	0.41016	0.43945	0.46875
31/32	0.03027	0.06055	0.09082	0.12109	0.15137	0.18164	0.21191	0.24219	0.27246	0.30273	0.33301	0.36328	0.39355	0.42383	0.45410	0.48438
1	0.03125	0.06250	0.09375	0.12500	0.15625	0.18750	0.21875	0.25000	0.28125	0.31250	0.34375	0.37500	0.40625	0.43750	0.46875	0.50000

Copyright 2004, Industrial Press, Inc., New York, NY

Multiplication Table for Common Fractions From 17/32 to 1

	17/32	9/16	19/32	5/8	21/32	11/16	23/32	3/4	25/32	13/16	27/32	7/8	29/32	15/16	31/32	1
1/32	0.01660	0.01758	0.01855	0.01953	0.02051	0.02148	0.02246	0.02344	0.02441	0.02539	0.02637	0.02734	0.02832	0.02930	0.03027	0.03125
1/16	0.03320	0.03516	0.03711	0.03906	0.04102	0.04297	0.04492	0.04688	0.04883	0.05078	0.05273	0.05469	0.05664	0.05859	0.06055	0.06250
3/32	0.04980	0.05273	0.05566	0.05859	0.06152	0.06445	0.06738	0.07031	0.07324	0.07617	0.07910	0.08203	0.08496	0.08789	0.09082	0.09375
1/8	0.06641	0.07031	0.07422	0.07813	0.08203	0.08594	0.08984	0.09375	0.09766	0.10156	0.10547	0.10938	0.11328	0.11719	0.12109	0.12500
5/32	0.08301	0.08789	0.09277	0.09766	0.10254	0.10742	0.11230	0.11719	0.12207	0.12695	0.13184	0.13672	0.14160	0.14648	0.15137	0.15625
3/16	0.09961	0.10547	0.11133	0.11719	0.12305	0.12891	0.13477	0.14063	0.14648	0.15234	0.15820	0.16406	0.16992	0.17578	0.18164	0.18750
7/32	0.11621	0.12305	0.12988	0.13672	0.14355	0.15039	0.15723	0.16406	0.17090	0.17773	0.18457	0.19141	0.19824	0.20508	0.21191	0.21875
1/4	0.13281	0.14063	0.14844	0.15625	0.16406	0.17188	0.17969	0.18750	0.19531	0.20313	0.21094	0.21875	0.22656	0.23438	0.24219	0.25000
9/32	0.14941	0.15820	0.16699	0.17578	0.18457	0.19336	0.20215	0.21094	0.21973	0.22852	0.23730	0.24609	0.25488	0.26367	0.27246	0.28125
5/16	0.16602	0.17578	0.18555	0.19531	0.20508	0.21484	0.22461	0.23438	0.24414	0.25391	0.26367	0.27344	0.28320	0.29297	0.30273	0.31250
11/32	0.18262	0.19336	0.20410	0.21484	0.22559	0.23633	0.24707	0.25781	0.26855	0.27930	0.29004	0.30078	0.31152	0.32227	0.33301	0.34375
3/8	0.19922	0.21094	0.22266	0.23438	0.24609	0.25781	0.26953	0.28125	0.29297	0.30469	0.31641	0.32813	0.33984	0.35156	0.36328	0.37500
13/32	0.21582	0.22852	0.24121	0.25391	0.26660	0.27930	0.29199	0.30469	0.31738	0.33008	0.34277	0.35547	0.36816	0.38086	0.39355	0.40625
7/16	0.23242	0.24609	0.25977	0.27344	0.28711	0.30078	0.31445	0.32813	0.34180	0.35547	0.36914	0.38281	0.39648	0.41016	0.42383	0.43750
15/32	0.24902	0.26367	0.27832	0.29297	0.30762	0.32227	0.33691	0.35156	0.36621	0.38086	0.39551	0.41016	0.42480	0.43945	0.45410	0.46875
1/2	0.26563	0.28125	0.29688	0.31250	0.32813	0.34375	0.35938	0.37500	0.39063	0.40625	0.42188	0.43750	0.45313	0.46875	0.48438	0.50000
17/32	0.28223	0.29883	0.31543	0.33203	0.34863	0.36523	0.38184	0.39844	0.41504	0.43164	0.44824	0.46484	0.48145	0.49805	0.51465	0.53125
9/16	0.29883	0.31641	0.33398	0.35156	0.36914	0.38672	0.40430	0.42188	0.43945	0.45703	0.47461	0.49219	0.50977	0.52734	0.54492	0.56250
19/32	0.31543	0.33398	0.35254	0.37109	0.38965	0.40820	0.42676	0.44531	0.46387	0.48242	0.50098	0.51953	0.53809	0.55664	0.57520	0.59375
5/8	0.33203	0.35156	0.37109	0.39063	0.41016	0.42969	0.44922	0.46875	0.48828	0.50781	0.52734	0.54688	0.56641	0.58594	0.60547	0.62500
21/32	0.34863	0.36914	0.38965	0.41016	0.43066	0.45117	0.47168	0.49219	0.51270	0.53320	0.55371	0.57422	0.59473	0.61523	0.63574	0.65625
11/16	0.36523	0.38672	0.40820	0.42969	0.45117	0.47266	0.49414	0.51563	0.53711	0.55859	0.58008	0.60156	0.62305	0.64453	0.66602	0.68750
23/32	0.38184	0.40430	0.42676	0.44922	0.47168	0.49414	0.51660	0.53906	0.56152	0.58398	0.60645	0.62891	0.65137	0.67383	0.69629	0.71875
3/4	0.39844	0.42188	0.44531	0.46875	0.49219	0.51563	0.53906	0.56250	0.58594	0.60938	0.63281	0.65625	0.67969	0.70313	0.72656	0.75000
25/32	0.41504	0.43945	0.46387	0.48828	0.51270	0.53711	0.56152	0.58594	0.61035	0.63477	0.65918	0.68359	0.70801	0.73242	0.75684	0.78125
13/16	0.43164	0.45703	0.48242	0.50781	0.53320	0.55859	0.58398	0.60938	0.63477	0.66016	0.68555	0.71094	0.73633	0.76172	0.78711	0.81250
27/32	0.44824	0.47461	0.50098	0.52734	0.55371	0.58008	0.60645	0.63281	0.65918	0.68555	0.71191	0.73828	0.76465	0.79102	0.81738	0.84375
7/8	0.46484	0.49219	0.51953	0.54688	0.57422	0.60156	0.62891	0.65625	0.68359	0.71094	0.73828	0.76563	0.79297	0.82031	0.84766	0.87500
29/32	0.48145	0.50977	0.53809	0.56641	0.59473	0.62305	0.65137	0.67969	0.70801	0.73633	0.76465	0.79297	0.82129	0.84961	0.87793	0.90625
15/16	0.49805	0.52734	0.55664	0.58594	0.61523	0.64453	0.67383	0.70313	0.73242	0.76172	0.79102	0.82031	0.84961	0.87891	0.90820	0.93750
31/32	0.51465	0.54492	0.57520	0.60547	0.63574	0.66602	0.69629	0.72656	0.75684	0.78711	0.81738	0.84766	0.87793	0.90820	0.93848	0.96875
1	0.53125	0.56250	0.59375	0.62500	0.65625	0.68750	0.71875	0.75000	0.78125	0.81250	0.84375	0.87500	0.90625	0.93750	0.96875	1.00000

Copyright 2004, Industrial Press, Inc., New York, NY

Area and Volume of Spheres*

Surface Area and Volume of Spheres From 1/64 to 14 3/4

d = diameter			Surface $= \pi d^2$			Volume $= \pi d^3 \div 6$		
Dia.	Surface	Volume	Dia.	Surface	Volume	Dia.	Surface	Volume
1/64	0.00077	0.000002	2	12.566	4.1888	6 1/2	132.73	143.79
1/32	0.00307	0.00002	2 1/16	13.364	4.5939	6 5/8	137.89	152.25
1/16	0.01227	0.00013	2 1/8	14.186	5.0243	6 3/4	143.14	161.03
3/32	0.02761	0.00043	2 3/16	15.033	5.4808	6 7/8	148.49	170.14
1/8	0.04909	0.00102	2 1/4	15.904	5.9641	7	153.94	179.59
5/32	0.07670	0.00200	2 5/16	16.800	6.4751	7 1/8	159.48	189.39
3/16	0.11045	0.00345	2 3/8	17.721	7.0144	7 1/4	165.13	199.53
7/32	0.15033	0.00548	2 7/16	18.665	7.5829	7 3/8	170.87	210.03
1/4	0.19635	0.00818	2 1/2	19.635	8.1812	7 1/2	176.71	220.89
9/32	0.24850	0.01165	2 9/16	20.629	8.8103	7 5/8	182.65	232.12
5/16	0.30680	0.01598	2 5/8	21.648	9.4708	7 3/4	188.69	243.73
11/32	0.37122	0.02127	2 11/16	22.691	10.164	7 7/8	194.83	255.71
3/8	0.44179	0.02761	2 3/4	23.758	10.889	8	201.06	268.08
13/32	0.51849	0.03511	2 13/16	24.850	11.649	8 1/8	207.39	280.85
7/16	0.60132	0.04385	2 7/8	25.967	12.443	8 1/4	213.82	294.01
15/32	0.69029	0.05393	2 15/16	27.109	13.272	8 3/8	220.35	307.58
1/2	0.78540	0.06545	3	28.274	14.137	8 1/2	226.98	321.56
17/32	0.88664	0.07850	3 1/16	29.465	15.039	8 5/8	233.71	335.95
9/16	0.99402	0.09319	3 1/8	30.680	15.979	8 3/4	240.53	350.77
19/32	1.1075	0.10960	3 3/16	31.919	16.957	8 7/8	247.45	366.02
5/8	1.2272	0.12783	3 1/4	33.183	17.974	9	254.47	381.70
21/32	1.3530	0.14798	3 5/16	34.472	19.031	9 1/8	261.59	397.83
11/16	1.4849	0.17014	3 3/8	35.785	20.129	9 1/4	268.80	414.40
23/32	1.6230	0.19442	3 7/16	37.122	21.268	9 3/8	276.12	431.43
3/4	1.7671	0.22089	3 1/2	38.485	22.449	9 1/2	283.53	448.92
25/32	1.9175	0.24967	3 5/8	41.282	24.942	9 5/8	291.04	466.88
13/16	2.0739	0.28085	3 3/4	44.179	27.612	9 3/4	298.65	485.30
27/32	2.2365	0.31451	3 7/8	47.173	30.466	9 7/8	306.35	504.21
7/8	2.4053	0.35077	4	50.265	33.510	10	314.16	523.60
29/32	2.5802	0.38971	4 1/8	53.456	36.751	10 1/4	330.06	563.86
15/16	2.7612	0.43143	4 1/4	56.745	40.194	10 1/2	346.36	606.13
31/32	2.9483	0.47603	4 3/8	60.132	43.846	10 3/4	363.05	650.47
1	3.1416	0.52360	4 1/2	63.617	47.713	11	380.13	696.91
1 1/16	3.5466	0.62804	4 5/8	67.201	51.800	11 1/4	397.61	745.51
1 1/8	3.9761	0.74551	4 3/4	70.882	56.115	11 1/2	415.48	796.33
1 3/16	4.4301	0.87680	4 7/8	74.662	60.663	11 3/4	433.74	849.40
1 1/4	4.9087	1.0227	5	78.540	65.450	12	452.39	904.78
1 5/16	5.4119	1.1838	5 1/8	82.516	70.482	12 1/4	471.44	962.51
1 3/8	5.9396	1.3612	5 1/4	86.590	75.766	12 1/2	490.87	1022.7
1 7/16	6.4918	1.5553	5 3/8	90.763	81.308	12 3/4	510.71	1085.2
1 1/2	7.0686	1.7671	5 1/2	95.033	87.114	13	530.93	1150.3
1 9/16	7.6699	1.9974	5 5/8	99.402	93.189	13 1/4	551.55	1218.0
1 5/8	8.2958	2.2468	5 3/4	103.87	99.541	13 1/2	572.56	1288.2
1 11/16	8.9462	2.5161	5 7/8	108.43	106.17	13 3/4	593.96	1361.2
1 3/4	9.6211	2.8062	6	113.10	113.10	14	615.75	1436.8
1 13/16	10.321	3.1177	6 1/8	117.86	120.31	14 1/4	637.94	1515.1
1 7/8	11.045	3.4515	6 1/4	122.72	127.83	14 1/2	660.52	1596.3
1 15/16	11.793	3.8082	6 3/8	127.68	135.66	14 3/4	683.49	1680.3

* The figures given in the table can be used for English and Metric (SI) units.

Copyright 2004, Industrial Press, Inc., New York, NY

Surface Area and Volume of Spheres From 15 to 75½

Dia.	Surface	Volume	Dia.	Surface	Volume	Dia.	Surface	Volume
15	706.86	1767.1	27½	2375.8	10,889	51	8171.3	69,456
15¼	730.62	1857.0	27¾	2419.2	11,189	51½	8332.3	71,519
15½	754.77	1949.8	28	2463.0	11,494	52	8494.9	73,622
15¾	779.31	2045.7	28¼	2507.2	11,805	52½	8659.0	75,766
16	804.25	2144.7	28½	2551.8	12,121	53	8824.7	77,952
16¼	829.58	2246.8	28¾	2596.7	12,443	53½	8992.0	80,179
16½	855.30	2352.1	29	2642.1	12,770	54	9160.9	82,448
16¾	881.41	2460.6	29½	2734.0	13,442	54½	9331.3	84,759
17	907.92	2572.4	30	2827.4	14,137	55	9503.3	87,114
17¼	934.82	2687.6	30½	2922.5	14,856	55½	9676.9	89,511
17½	962.11	2806.2	31	3019.1	15,599	56	9852.0	91,952
17¾	989.80	2928.2	31½	3117.2	16,366	56½	10,029	94,437
18	1017.9	3053.6	32	3217.0	17,157	57	10,207	96,967
18¼	1046.3	3182.6	32½	3318.3	17,974	57½	10,387	99,541
18½	1075.2	3315.2	33	3421.2	18,817	58	10,568	102,160
18¾	1104.5	3451.5	33½	3525.7	19,685	58½	10,751	104,825
19	1134.1	3591.4	34	3631.7	20,580	59	10,936	107,536
19¼	1164.2	3735.0	34½	3739.3	21,501	59½	11,122	110,293
19½	1194.6	3882.4	35	3848.5	22,449	60	11,310	113,097
19¾	1225.4	4033.7	35½	3959.2	23,425	60½	11,499	115,948
20	1256.6	4188.8	36	4071.5	24,429	61	11,690	118,847
20¼	1288.2	4347.8	36½	4185.4	25,461	61½	11,882	121,793
20½	1320.3	4510.9	37	4300.8	26,522	62	12,076	124,788
20¾	1352.7	4677.9	37½	4417.9	27,612	62½	12,272	127,832
21	1385.4	4849.0	38	4536.5	28,731	63	12,469	130,924
21¼	1418.6	5024.3	38½	4656.6	29,880	63½	12,668	134,066
21½	1452.2	5203.7	39	4778.4	31,059	64	12,868	137,258
21¾	1486.2	5387.4	39½	4901.7	32,269	64½	13,070	140,500
22	1520.5	5575.3	40	5026.5	33,510	65	13,273	143,793
22¼	1555.3	5767.5	40½	5153.0	34,783	65½	13,478	147,137
22½	1590.4	5964.1	41	5281.0	36,087	66	13,685	150,533
22¾	1626.0	6165.1	41½	5410.6	37,423	66½	13,893	153,980
23	1661.9	6370.6	42	5541.8	38,792	67	14,103	157,479
23¼	1698.2	6580.6	42½	5674.5	40,194	67½	14,314	161,031
23½	1734.9	6795.2	43	5808.8	41,630	68	14,527	164,636
23¾	1772.1	7014.4	43½	5944.7	43,099	68½	14,741	168,295
24	1809.6	7238.2	44	6082.1	44,602	69	14,957	172,007
24¼	1847.5	7466.8	44½	6221.1	46,140	69½	15,175	175,773
24½	1885.7	7700.1	45	6361.7	47,713	70	15,394	179,594
24¾	1924.4	7938.2	45½	6503.9	49,321	70½	15,615	183,470
25	1963.5	8181.2	46	6647.6	50,965	71	15,837	187,402
25¼	2003.0	8429.1	46½	6792.9	52,645	71½	16,061	191,389
25½	2042.8	8682.0	47	6939.8	54,362	72	16,286	195,432
25¾	2083.1	8939.9	47½	7088.2	56,115	72½	16,513	199,532
26	2123.7	9202.8	48	7238.2	57,906	73	16,742	203,689
26¼	2164.8	9470.8	48½	7389.8	59,734	73½	16,972	207,903
26½	2206.2	9744.0	49	7543.0	61,601	74	17,203	212,175
26¾	2248.0	10,022	49½	7697.7	63,506	74½	17,437	216,505
27	2290.2	10,306	50	7854.0	65,450	75	17,671	220,893
27¼	2332.8	10,595	50½	8011.8	67,433	75½	17,908	225,341

Copyright 2004, Industrial Press, Inc., New York, NY

Surface Area and Volume of Spheres From 76 to 200

Dia.	Surface	Volume	Dia.	Surface	Volume	Dia.	Surface	Volume
76	18,146	229,847	101	32,047	539,464	151	71,631	1,802,725
76 1/2	18,385	234,414	102	32,685	555,647	152	72,583	1,838,778
77	18,627	239,040	103	33,329	572,151	153	73,542	1,875,309
77 1/2	18,869	243,727	104	33,979	588,977	154	74,506	1,912,321
78	19,113	248,475	105	34,636	606,131	155	75,477	1,949,816
78 1/2	19,359	253,284	106	35,299	623,615	156	76,454	1,987,799
79	19,607	258,155	107	35,968	641,431	157	77,437	2,026,271
79 1/2	19,856	263,087	108	36,644	659,584	158	78,427	2,065,237
80	20,106	268,083	109	37,325	678,076	159	79,423	2,104,699
80 1/2	20,358	273,141	110	38,013	696,910	160	80,425	2,144,661
81	20,612	278,262	111	38,708	716,090	161	81,433	2,185,125
81 1/2	20,867	283,447	112	39,408	735,619	162	82,448	2,226,095
82	21,124	288,696	113	40,115	755,499	163	83,469	2,267,574
82 1/2	21,382	294,009	114	40,828	775,735	164	84,496	2,309,565
83	21,642	299,387	115	41,548	796,328	165	85,530	2,352,071
83 1/2	21,904	304,830	116	42,273	817,283	166	86,570	2,395,096
84	22,167	310,339	117	43,005	838,603	167	87,616	2,438,642
84 1/2	22,432	315,914	118	43,744	860,290	168	88,668	2,482,713
85	22,698	321,555	119	44,488	882,347	169	89,727	2,527,311
85 1/2	22,966	327,263	120	45,239	904,779	170	90,792	2,572,441
86	23,235	333,038	121	45,996	927,587	171	91,863	2,618,104
86 1/2	23,506	338,881	122	46,759	950,776	172	92,941	2,664,305
87	23,779	344,791	123	47,529	974,348	173	94,025	2,711,046
87 1/2	24,053	350,770	124	48,305	998,306	174	95,115	2,758,331
88	24,328	356,818	125	49,087	1,022,654	175	96,211	2,806,162
88 1/2	24,606	362,935	126	49,876	1,047,394	176	97,314	2,854,543
89	24,885	369,121	127	50,671	1,072,531	177	98,423	2,903,477
89 1/2	25,165	375,377	128	51,472	1,098,066	178	99,538	2,952,967
90	25,447	381,704	129	52,279	1,124,004	179	100,660	3,003,016
90 1/2	25,730	388,101	130	53,093	1,150,347	180	101,788	3,053,628
91	26,016	394,569	131	53,913	1,177,098	181	102,922	3,104,805
91 1/2	26,302	401,109	132	54,739	1,204,260	182	104,062	3,156,551
92	26,590	407,720	133	55,572	1,231,838	183	105,209	3,208,868
92 1/2	26,880	414,404	134	56,410	1,259,833	184	106,362	3,261,761
93	27,172	421,160	135	57,256	1,288,249	185	107,521	3,315,231
93 1/2	27,465	427,990	136	58,107	1,317,090	186	108,687	3,369,283
94	27,759	434,893	137	58,965	1,346,357	187	109,858	3,423,919
94 1/2	28,055	441,870	138	59,828	1,376,055	188	111,036	3,479,142
95	28,353	448,921	139	60,699	1,406,187	189	112,221	3,534,956
95 1/2	28,652	456,046	140	61,575	1,436,755	190	113,411	3,591,364
96	28,953	463,247	141	62,458	1,467,763	191	114,608	3,648,369
96 1/2	29,255	470,523	142	63,347	1,499,214	192	115,812	3,705,973
97	29,559	477,874	143	64,242	1,531,111	193	117,021	3,764,181
97 1/2	29,865	485,302	144	65,144	1,563,458	194	118,237	3,822,996
98	30,172	492,807	145	66,052	1,596,256	195	119,459	3,882,419
98 1/2	30,481	500,388	146	66,966	1,629,511	196	120,687	3,942,456
99	30,791	508,047	147	67,887	1,663,224	197	121,922	4,003,108
99 1/2	31,103	515,784	148	68,813	1,697,398	198	123,163	4,064,379
100	31,416	523,599	149	69,746	1,732,038	199	124,410	4,126,272
100 1/2	31,731	531,492	150	70,686	1,767,146	200	125,664	4,188,790

Copyright 2004, Industrial Press, Inc., New York, NY

Circumference and Area of Circles

Circumferences and Areas of Circles From 1/64 to 9 7/8

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
1/64	0.0491	0.0002	2	6.2832	3.1416	5	15.7080	19.635
1/32	0.0982	0.0008	2 1/16	6.4795	3.3410	5 1/16	15.9043	20.129
1/16	0.1963	0.0031	2 1/8	6.6759	3.5466	5 1/8	16.1007	20.629
3/32	0.2945	0.0069	2 3/16	6.8722	3.7583	5 3/16	16.2970	21.135
1/8	0.3927	0.0123	2 1/4	7.0686	3.9761	5 1/4	16.4934	21.648
5/32	0.4909	0.0192	2 5/16	7.2649	4.2000	5 5/16	16.6897	22.166
3/16	0.5890	0.0276	2 3/8	7.4613	4.4301	5 3/8	16.8861	22.691
7/32	0.6872	0.0376	2 7/16	7.6576	4.6664	5 7/16	17.0824	23.221
1/4	0.7854	0.0491	2 1/2	7.8540	4.9087	5 1/2	17.2788	23.758
9/32	0.8836	0.0621	2 9/16	8.0503	5.1572	5 9/16	17.4751	24.301
5/16	0.9817	0.0767	2 5/8	8.2467	5.4119	5 5/8	17.6715	24.850
11/32	1.0799	0.0928	2 11/16	8.4430	5.6727	5 11/16	17.8678	25.406
3/8	1.1781	0.1104	2 3/4	8.6394	5.9396	5 3/4	18.0642	25.967
13/32	1.2763	0.1296	2 13/16	8.8357	6.2126	5 13/16	18.2605	26.535
7/16	1.3744	0.1503	2 7/8	9.0321	6.4918	5 7/8	18.4569	27.109
15/32	1.4726	0.1726	2 15/16	9.2284	6.7771	5 15/16	18.6532	27.688
1/2	1.5708	0.1963	3	9.4248	7.0686	6	18.8496	28.274
17/32	1.6690	0.2217	3 1/16	9.6211	7.3662	6 1/8	19.2423	29.465
9/16	1.7671	0.2485	3 1/8	9.8175	7.6699	6 1/4	19.6350	30.680
19/32	1.8653	0.2769	3 3/16	10.0138	7.9798	6 3/8	20.0277	31.919
5/8	1.9635	0.3068	3 1/4	10.2102	8.2958	6 1/2	20.4204	33.183
21/32	2.0617	0.3382	3 5/16	10.4065	8.6179	6 5/8	20.8131	34.472
11/16	2.1598	0.3712	3 3/8	10.6029	8.9462	6 3/4	21.2058	35.785
23/32	2.2580	0.4057	3 7/16	10.7992	9.2806	6 7/8	21.5984	37.122
3/4	2.3562	0.4418	3 1/2	10.9956	9.6211	7	21.9911	38.485
25/32	2.4544	0.4794	3 9/16	11.1919	9.9678	7 1/8	22.3838	39.871
13/16	2.5525	0.5185	3 5/8	11.388	10.3206	7 1/4	22.7765	41.282
27/32	2.6507	0.5591	3 11/16	11.585	10.6796	7 3/8	23.1692	42.718
7/8	2.7489	0.6013	3 3/4	11.781	11.0447	7 1/2	23.5619	44.179
29/32	2.8471	0.6450	3 13/16	11.977	11.4159	7 5/8	23.9546	45.664
15/16	2.9452	0.6903	3 7/8	12.174	11.7932	7 3/4	24.3473	47.173
31/32	3.0434	0.7371	3 15/16	12.370	12.1767	7 7/8	24.7400	48.707
1	3.1416	0.7854	4	12.566	12.5664	8	25.1327	50.265
1 1/16	3.3379	0.8866	4 1/16	12.763	12.9621	8 1/8	25.5254	51.849
1 1/8	3.5343	0.9940	4 1/8	12.959	13.3640	8 1/4	25.9181	53.456
1 3/16	3.7306	1.1075	4 3/16	13.155	13.7721	8 3/8	26.3108	55.088
1 1/4	3.9270	1.2272	4 1/4	13.352	14.1863	8 1/2	26.7035	56.745
1 5/16	4.1233	1.3530	4 5/16	13.548	14.6066	8 5/8	27.0962	58.426
1 3/8	4.3197	1.4849	4 3/8	13.744	15.0330	8 3/4	27.4889	60.132
1 7/16	4.5160	1.6230	4 7/16	13.941	15.4656	8 7/8	27.8816	61.862
1 1/2	4.7124	1.7671	4 1/2	14.137	15.9043	9	28.2743	63.617
1 9/16	4.9087	1.9175	4 9/16	14.334	16.3492	9 1/8	28.6670	65.397
1 5/8	5.1051	2.0739	4 5/8	14.530	16.8002	9 1/4	29.0597	67.201
1 11/16	5.3014	2.2365	4 11/16	14.726	17.2573	9 3/8	29.4524	69.029
1 3/4	5.4978	2.4053	4 3/4	14.923	17.7205	9 1/2	29.8451	70.882
1 13/16	5.6941	2.5802	4 13/16	15.119	18.1899	9 5/8	30.2378	72.760
1 7/8	5.8905	2.7612	4 7/8	15.315	18.6655	9 3/4	30.6305	74.662
1 15/16	6.0868	2.9483	4 15/16	15.512	19.1471	9 7/8	31.0232	76.589

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 10 to 27⅞

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
10	31.41593	78.53983	16	50.26549	201.06195	22	69.11505	380.13275
⅛	31.80863	80.51559	⅛	50.65819	204.21582	⅛	69.50775	384.46472
¼	32.20133	82.51590	¼	51.05089	207.39423	¼	69.90044	388.82122
⅜	32.59403	84.54076	⅜	51.44359	210.59718	⅜	70.29314	393.20227
½	32.98673	86.59016	½	51.83628	213.82467	½	70.68584	397.60786
⅝	33.37943	88.66410	⅝	52.22898	217.07671	⅝	71.07854	402.03800
¾	33.77212	90.76259	¾	52.62168	220.35330	¾	71.47124	406.49268
⅞	34.16482	92.88561	⅞	53.01438	223.65442	⅞	71.86394	410.97191
11	34.55752	95.03319	17	53.40708	226.98009	23	72.25664	415.47567
⅛	34.95022	97.20531	⅛	53.79978	230.33031	⅛	72.64934	420.00399
¼	35.34292	99.40197	¼	54.19248	233.70507	¼	73.04204	424.55684
⅜	35.73562	101.62317	⅜	54.58518	237.10437	⅜	73.43474	429.13424
½	36.12832	103.86892	½	54.97788	240.52821	½	73.82744	433.73618
⅝	36.52102	106.13921	⅝	55.37058	243.97660	⅝	74.22013	438.36267
¾	36.91372	108.43405	¾	55.76328	247.44954	¾	74.61283	443.01370
⅞	37.30642	110.75343	⅞	56.15597	250.94701	⅞	75.00553	447.68927
12	37.69912	113.09735	18	56.54867	254.46903	24	75.39823	452.38939
⅛	38.09182	115.46581	⅛	56.94137	258.01560	⅛	75.79093	457.11405
¼	38.48451	117.85882	¼	57.33407	261.58670	¼	76.18363	461.86326
⅜	38.87721	120.27638	⅜	57.72677	265.18236	⅜	76.57633	466.63701
½	39.26991	122.71848	½	58.11947	268.80255	½	76.96903	471.43530
⅝	39.66261	125.18512	⅝	58.51217	272.44729	⅝	77.36173	476.25814
¾	40.05531	127.67630	¾	58.90487	276.11657	¾	77.75443	481.10552
⅞	40.44801	130.19203	⅞	59.29757	279.81040	⅞	78.14713	485.97744
13	40.84071	132.73230	19	59.69027	283.52877	25	78.53983	490.87391
⅛	41.23341	135.29712	⅛	60.08297	287.27168	⅛	78.93252	495.79492
¼	41.62611	137.88648	¼	60.47567	291.03914	¼	79.32522	500.74047
⅜	42.01881	140.50038	⅜	60.86836	294.83114	⅜	79.71792	505.71057
½	42.41151	143.13883	½	61.26106	298.64768	½	80.11062	510.70521
⅝	42.80420	145.80182	⅝	61.65376	302.48877	⅝	80.50332	515.72440
¾	43.19690	148.48936	¾	62.04646	306.35440	¾	80.89602	520.76813
⅞	43.58960	151.20143	⅞	62.43916	310.24458	⅞	81.28872	525.83640
14	43.98230	153.93806	20	62.83186	314.15930	26	81.68142	530.92922
⅛	44.37500	156.69922	⅛	63.22456	318.09856	⅛	82.07412	536.04658
¼	44.76770	159.48493	¼	63.61726	322.06237	¼	82.46682	541.18848
⅜	45.16040	162.29519	⅜	64.00996	326.05072	⅜	82.85952	546.35493
½	45.55310	165.12998	½	64.40266	330.06361	½	83.25221	551.54592
⅝	45.94580	167.98932	⅝	64.79536	334.10105	⅝	83.64491	556.76146
¾	46.33850	170.87321	¾	65.18805	338.16303	¾	84.03761	562.00154
⅞	46.73120	173.78163	⅞	65.58075	342.24956	⅞	84.43031	567.26616
15	47.12390	176.71461	21	65.97345	346.36063	27	84.82301	572.55532
⅛	47.51659	179.67212	⅛	66.36615	350.49624	⅛	85.21571	577.86903
¼	47.90929	182.65418	¼	66.75885	354.65640	¼	85.60841	583.20729
⅜	48.30199	185.66078	⅜	67.15155	358.84110	⅜	86.00111	588.57009
½	48.69469	188.69193	½	67.54425	363.05034	½	86.39381	593.95743
⅝	49.08739	191.74762	⅝	67.93695	367.28413	⅝	86.78651	599.36931
¾	49.48009	194.82785	¾	68.32965	371.54246	¾	87.17921	604.80574
⅞	49.87279	197.93263	⅞	68.72235	375.82533	⅞	87.57190	610.26671
16	50.26549	201.06195	22	69.11505	380.13275	28	87.96460	615.75223

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 28 to 45⅞

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
28	87.96460	615.75223	34	106.81416	907.92038	40	125.66372	1256.63720
1/8	88.35730	621.26229	1/8	107.20686	914.60853	1/8	126.05642	1264.50345
1/4	88.75000	626.79689	1/4	107.59956	921.32123	1/4	126.44912	1272.39425
3/8	89.14270	632.35604	3/8	107.99226	928.05848	3/8	126.84182	1280.30959
1/2	89.53540	637.93973	1/2	108.38496	934.82027	1/2	127.23452	1288.24948
5/8	89.92810	643.54796	5/8	108.77766	941.60660	5/8	127.62722	1296.21391
3/4	90.32080	649.18074	3/4	109.17036	948.41747	3/4	128.01991	1304.20288
7/8	90.71350	654.83806	7/8	109.56306	955.25289	7/8	128.41261	1312.21640
29	91.10620	660.51993	35	109.95576	962.11286	41	128.80531	1320.25446
1/8	91.49890	666.22634	1/8	110.34845	968.99736	1/8	129.19801	1328.31706
1/4	91.89160	671.95729	1/4	110.74115	975.90641	1/4	129.59071	1336.40421
3/8	92.28429	677.71279	3/8	111.13385	982.84001	3/8	129.98341	1344.51590
1/2	92.67699	683.49283	1/2	111.52655	989.79814	1/2	130.37611	1352.65214
5/8	93.06969	689.29741	5/8	111.91925	996.78083	5/8	130.76881	1360.81291
3/4	93.46239	695.12654	3/4	112.31195	1003.78805	3/4	131.16151	1368.99824
7/8	93.85509	700.98021	7/8	112.70465	1010.81982	7/8	131.55421	1377.20810
30	94.24779	706.85843	36	113.09735	1017.87613	42	131.94691	1385.44251
1/8	94.64049	712.76118	1/8	113.49005	1024.95699	1/8	132.33961	1393.70147
1/4	95.03319	718.68849	1/4	113.88275	1032.06239	1/4	132.73230	1401.98496
3/8	95.42589	724.64033	3/8	114.27545	1039.19233	3/8	133.12500	1410.29300
1/2	95.81859	730.61672	1/2	114.66814	1046.34682	1/2	133.51770	1418.62559
5/8	96.21129	736.61766	5/8	115.06084	1053.52585	5/8	133.91040	1426.98272
3/4	96.60398	742.64313	3/4	115.45354	1060.72942	3/4	134.30310	1435.36439
7/8	96.99668	748.69315	7/8	115.84624	1067.95754	7/8	134.69580	1443.77060
31	97.38938	754.76772	37	116.23894	1075.21020	43	135.08850	1452.20136
1/8	97.78208	760.86683	1/8	116.63164	1082.48741	1/8	135.48120	1460.65667
1/4	98.17478	766.99048	1/4	117.02434	1089.78916	1/4	135.87390	1469.13651
3/8	98.56748	773.13867	3/8	117.41704	1097.11545	3/8	136.26660	1477.64090
1/2	98.96018	779.31141	1/2	117.80974	1104.46629	1/2	136.65930	1486.16984
5/8	99.35288	785.50870	5/8	118.20244	1111.84167	5/8	137.05199	1494.72332
3/4	99.74558	791.73052	3/4	118.59514	1119.24159	3/4	137.44469	1503.30134
7/8	100.13828	797.97689	7/8	118.98783	1126.66606	7/8	137.83739	1511.90390
32	100.53098	804.24781	38	119.38053	1134.11507	44	138.23009	1520.53101
1/8	100.92368	810.54327	1/8	119.77323	1141.58863	1/8	138.62279	1529.18266
1/4	101.31637	816.86327	1/4	120.16593	1149.08673	1/4	139.01549	1537.85886
3/8	101.70907	823.20781	3/8	120.55863	1156.60937	3/8	139.40819	1546.55960
1/2	102.10177	829.57690	1/2	120.95133	1164.15656	1/2	139.80089	1555.28488
5/8	102.49447	835.97053	5/8	121.34403	1171.72829	5/8	140.19359	1564.03471
3/4	102.88717	842.38871	3/4	121.73673	1179.32456	3/4	140.58629	1572.80908
7/8	103.27987	848.83143	7/8	122.12943	1186.94538	7/8	140.97899	1581.60800
33	103.67257	855.29869	39	122.52213	1194.59074	45	141.37169	1590.43146
1/8	104.06527	861.79050	1/8	122.91483	1202.26064	1/8	141.76438	1599.27946
1/4	104.45797	868.30685	1/4	123.30753	1209.95509	1/4	142.15708	1608.15200
3/8	104.85067	874.84775	3/8	123.70022	1217.67408	3/8	142.54978	1617.04909
1/2	105.24337	881.41319	1/2	124.09292	1225.41762	1/2	142.94248	1625.97073
5/8	105.63606	888.00317	5/8	124.48562	1233.18570	5/8	143.33518	1634.91690
3/4	106.02876	894.61769	3/4	124.87832	1240.97832	3/4	143.72788	1643.88762
7/8	106.42146	901.25676	7/8	125.27102	1248.79549	7/8	144.12058	1652.88289
34	106.81416	907.92038	40	125.66372	1256.63720	46	144.51328	1661.90270

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 46 to 63⅞

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
46	144.51328	1661.90270	52	163.36284	2123.71687	58	182.21239	2642.07971
⅛	144.90598	1670.94705	⅛	163.75554	2133.93932	⅛	182.60509	2653.48026
¼	145.29868	1680.01594	¼	164.14823	2144.18631	¼	182.99779	2664.90535
⅜	145.69138	1689.10938	⅜	164.54093	2154.45785	⅜	183.39049	2676.35498
½	146.08407	1698.22737	½	164.93363	2164.75393	½	183.78319	2687.82916
⅝	146.47677	1707.36989	⅝	165.32633	2175.07455	⅝	184.17589	2699.32788
¾	146.86947	1716.53696	¾	165.71903	2185.41972	¾	184.56859	2710.85115
⅞	147.26217	1725.72858	⅞	166.11173	2195.78943	⅞	184.96129	2722.39896
47	147.65487	1734.94473	53	166.50443	2206.18368	59	185.35399	2733.97131
⅛	148.04757	1744.18544	⅛	166.89713	2216.60248	⅛	185.74669	2745.56820
¼	148.44027	1753.45068	¼	167.28983	2227.04583	¼	186.13939	2757.18964
⅜	148.83297	1762.74047	⅜	167.68253	2237.51371	⅜	186.53208	2768.83563
½	149.22567	1772.05480	½	168.07523	2248.00614	½	186.92478	2780.50615
⅝	149.61837	1781.39368	⅝	168.46792	2258.52311	⅝	187.31748	2792.20123
¾	150.01107	1790.75710	¾	168.86062	2269.06463	¾	187.71018	2803.92084
⅞	150.40376	1800.14506	⅞	169.25332	2279.63069	⅞	188.10288	2815.66500
48	150.79646	1809.55757	54	169.64602	2290.22130	60	188.49558	2827.43370
⅛	151.18916	1818.99462	⅛	170.03872	2300.83645	⅛	188.88828	2839.22695
¼	151.58186	1828.45621	¼	170.43142	2311.47614	¼	189.28098	2851.04473
⅜	151.97456	1837.94235	⅜	170.82412	2322.14037	⅜	189.67368	2862.88707
½	152.36726	1847.45303	½	171.21682	2332.82915	½	190.06638	2874.75394
⅝	152.75996	1856.98826	⅝	171.60952	2343.54248	⅝	190.45908	2886.64536
¾	153.15266	1866.54803	¾	172.00222	2354.28034	¾	190.85177	2898.56133
⅞	153.54536	1876.13234	⅞	172.39492	2365.04275	⅞	191.24447	2910.50184
49	153.93806	1885.74120	55	172.78762	2375.82971	61	191.63717	2922.46689
⅛	154.33076	1895.37460	⅛	173.18031	2386.64120	⅛	192.02987	2934.45648
¼	154.72346	1905.03254	¼	173.57301	2397.47725	¼	192.42257	2946.47062
⅜	155.11615	1914.71503	⅜	173.96571	2408.33783	⅜	192.81527	2958.50930
½	155.50885	1924.42206	½	174.35841	2419.22296	½	193.20797	2970.57253
⅝	155.90155	1934.15364	⅝	174.75111	2430.13263	⅝	193.60067	2982.66030
¾	156.29425	1943.90976	¾	175.14381	2441.06685	¾	193.99337	2994.77261
⅞	156.68695	1953.69042	⅞	175.53651	2452.02561	⅞	194.38607	3006.90947
50	157.07965	1963.49563	56	175.92921	2463.00891	62	194.77877	3019.07087
⅛	157.47235	1973.32537	⅛	176.32191	2474.01676	⅛	195.17147	3031.25682
¼	157.86505	1983.17967	¼	176.71461	2485.04915	¼	195.56416	3043.46731
⅜	158.25775	1993.05851	⅜	177.10731	2496.10609	⅜	195.95686	3055.70234
½	158.65045	2002.96189	½	177.50000	2507.18756	½	196.34956	3067.96191
⅝	159.04315	2012.88981	⅝	177.89270	2518.29359	⅝	196.74226	3080.24603
¾	159.43584	2022.84228	¾	178.28540	2529.42415	¾	197.13496	3092.55470
⅞	159.82854	2032.81929	⅞	178.67810	2540.57926	⅞	197.52766	3104.88790
51	160.22124	2042.82085	57	179.07080	2551.75891	63	197.92036	3117.24565
⅛	160.61394	2052.84695	⅛	179.46350	2562.96311	⅛	198.31306	3129.62795
¼	161.00664	2062.89759	¼	179.85620	2574.19185	¼	198.70576	3142.03479
⅜	161.39934	2072.97278	⅜	180.24890	2585.44514	⅜	199.09846	3154.46617
½	161.79204	2083.07251	½	180.64160	2596.72296	½	199.49116	3166.92209
⅝	162.18474	2093.19678	⅝	181.03430	2608.02534	⅝	199.88385	3179.40256
¾	162.57744	2103.34560	¾	181.42700	2619.35225	¾	200.27655	3191.90758
⅞	162.97014	2113.51896	⅞	181.81969	2630.70371	⅞	200.66925	3204.43713
52	163.36284	2123.71687	58	182.21239	2642.07971	64	201.06195	3216.99123

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 64 to 81⅞

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
64	201.06195	3216.99123	70	219.91151	3848.45143	76	238.76107	4536.46029
⅛	201.45465	3229.56988	⅛	220.30421	3862.20817	⅛	239.15377	4551.39513
¼	201.84735	3242.17306	¼	220.69691	3875.98945	¼	239.54647	4566.35451
⅜	202.24005	3254.80079	⅜	221.08961	3889.79528	⅜	239.93917	4581.33844
½	202.63275	3267.45307	½	221.48231	3903.62565	½	240.33186	4596.34691
⅝	203.02545	3280.12989	⅝	221.87501	3917.48057	⅝	240.72456	4611.37992
¾	203.41815	3292.83125	¾	222.26770	3931.36003	¾	241.11726	4626.43748
⅞	203.81085	3305.55716	⅞	222.66040	3945.26403	⅞	241.50996	4641.51958
65	204.20355	3318.30761	71	223.05310	3959.19258	77	241.90266	4656.62622
⅛	204.59624	3331.08260	⅛	223.44580	3973.14567	⅛	242.29536	4671.75741
¼	204.98894	3343.88214	¼	223.83850	3987.12330	¼	242.68806	4686.91314
⅜	205.38164	3356.70622	⅜	224.23120	4001.12548	⅜	243.08076	4702.09342
½	205.77434	3369.55484	½	224.62390	4015.15220	½	243.47346	4717.29824
⅝	206.16704	3382.42801	⅝	225.01660	4029.20347	⅝	243.86616	4732.52760
¾	206.55974	3395.32572	¾	225.40930	4043.27928	¾	244.25886	4747.78151
⅞	206.95244	3408.24798	⅞	225.80200	4057.37963	⅞	244.65155	4763.05996
66	207.34514	3421.19478	72	226.19470	4071.50453	78	245.04425	4778.36295
⅛	207.73784	3434.16612	⅛	226.58740	4085.65397	⅛	245.43695	4793.69049
¼	208.13054	3447.16201	¼	226.98009	4099.82795	¼	245.82965	4809.04257
⅜	208.52324	3460.18244	⅜	227.37279	4114.02648	⅜	246.22235	4824.41920
½	208.91593	3473.22741	½	227.76549	4128.24955	½	246.61505	4839.82037
⅝	209.30863	3486.29693	⅝	228.15819	4142.49717	⅝	247.00775	4855.24608
¾	209.70133	3499.39099	¾	228.55089	4156.76933	¾	247.40045	4870.69633
⅞	210.09403	3512.50960	⅞	228.94359	4171.06603	⅞	247.79315	4886.17113
67	210.48673	3525.65274	73	229.33629	4185.38727	79	248.18585	4901.67048
⅛	210.87943	3538.82044	⅛	229.72899	4199.73306	⅛	248.57855	4917.19437
¼	211.27213	3552.01267	¼	230.12169	4214.10340	¼	248.97125	4932.74280
⅜	211.66483	3565.22945	⅜	230.51439	4228.49828	⅜	249.36394	4948.31577
½	212.05753	3578.47078	½	230.90709	4242.91770	½	249.75664	4963.91329
⅝	212.45023	3591.73664	⅝	231.29978	4257.36166	⅝	250.14934	4979.53535
¾	212.84293	3605.02705	¾	231.69248	4271.83017	¾	250.54204	4995.18196
⅞	213.23562	3618.34201	⅞	232.08518	4286.32322	⅞	250.93474	5010.85311
68	213.62832	3631.68151	74	232.47788	4300.84082	80	251.32744	5026.54880
⅛	214.02102	3645.04555	⅛	232.87058	4315.38296	⅛	251.72014	5042.26904
¼	214.41372	3658.43414	¼	233.26328	4329.94964	¼	252.11284	5058.01382
⅜	214.80642	3671.84727	⅜	233.65598	4344.54087	⅜	252.50554	5073.78314
½	215.19912	3685.28494	½	234.04868	4359.15664	½	252.89824	5089.57701
⅝	215.59182	3698.74716	⅝	234.44138	4373.79695	⅝	253.29094	5105.39542
¾	215.98452	3712.23392	¾	234.83408	4388.46181	¾	253.68363	5121.23838
⅞	216.37722	3725.74522	⅞	235.22678	4403.15121	⅞	254.07633	5137.10588
69	216.76992	3739.28107	75	235.61948	4417.86516	81	254.46903	5152.99792
⅛	217.16262	3752.84146	⅛	236.01217	4432.60365	⅛	254.86173	5168.91450
¼	217.55532	3766.42640	¼	236.40487	4447.36668	¼	255.25443	5184.85563
⅜	217.94801	3780.03587	⅜	236.79757	4462.15425	⅜	255.64713	5200.82131
½	218.34071	3793.66990	½	237.19027	4476.96637	½	256.03983	5216.81153
⅝	218.73341	3807.32846	⅝	237.58297	4491.80304	⅝	256.43253	5232.82629
¾	219.12611	3821.01157	¾	237.97567	4506.66425	¾	256.82523	5248.86559
⅞	219.51881	3834.71923	⅞	238.36837	4521.55000	⅞	257.21793	5264.92944
70	219.91151	3848.45143	76	238.76107	4536.46029	82	257.61063	5281.01783

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 82 to 99⅞

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
82	257.61063	5281.01783	88	276.46018	6082.12405	94	295.30974	6939.77894
⅛	258.00333	5297.13077	⅛	276.85288	6099.41508	⅛	295.70244	6958.24807
¼	258.39602	5313.26825	¼	277.24558	6116.73066	¼	296.09514	6976.74174
⅜	258.78872	5329.43027	⅜	277.63828	6134.07078	⅜	296.48784	6995.25996
½	259.18142	5345.61684	½	278.03098	6151.43544	½	296.88054	7013.80272
⅝	259.57412	5361.82795	⅝	278.42368	6168.82465	⅝	297.27324	7032.37003
¾	259.96682	5378.06360	¾	278.81638	6186.23840	¾	297.66594	7050.96188
⅞	260.35952	5394.32380	⅞	279.20908	6203.67670	⅞	298.05864	7069.57827
83	260.75222	5410.60854	89	279.60178	6221.13954	95	298.45134	7088.21921
⅛	261.14492	5426.91783	⅛	279.99448	6238.62692	⅛	298.84403	7106.88469
¼	261.53762	5443.25166	¼	280.38718	6256.13885	¼	299.23673	7125.57471
⅜	261.93032	5459.61003	⅜	280.77987	6273.67532	⅜	299.62943	7144.28928
½	262.32302	5475.99295	½	281.17257	6291.23633	½	300.02213	7163.02839
⅝	262.71571	5492.40041	⅝	281.56527	6308.82189	⅝	300.41483	7181.79204
¾	263.10841	5508.83241	¾	281.95797	6326.43199	¾	300.80753	7200.58024
⅞	263.50111	5525.28896	⅞	282.35067	6344.06664	⅞	301.20023	7219.39299
84	263.89381	5541.77005	90	282.74337	6361.72583	96	301.59293	7238.23027
⅛	264.28651	5558.27569	⅛	283.13607	6379.40956	⅛	301.98563	7257.09210
¼	264.67921	5574.80587	¼	283.52877	6397.11783	¼	302.37833	7275.97848
⅜	265.07191	5591.36059	⅜	283.92147	6414.85065	⅜	302.77103	7294.88939
½	265.46461	5607.93985	½	284.31417	6432.60802	½	303.16372	7313.82485
⅝	265.85731	5624.54366	⅝	284.70687	6450.38992	⅝	303.55642	7332.78486
¾	266.25001	5641.17202	¾	285.09956	6468.19638	¾	303.94912	7351.76941
⅞	266.64271	5657.82492	⅞	285.49226	6486.02737	⅞	304.34182	7370.77850
85	267.03541	5674.50236	91	285.88496	6503.88291	97	304.73452	7389.81213
⅛	267.42810	5691.20434	⅛	286.27766	6521.76299	⅛	305.12722	7408.87031
¼	267.82080	5707.93087	¼	286.67036	6539.66762	¼	305.51992	7427.95304
⅜	268.21350	5724.68194	⅜	287.06306	6557.59679	⅜	305.91262	7447.06030
½	268.60620	5741.45756	½	287.45576	6575.55050	½	306.30532	7466.19211
⅝	268.99890	5758.25772	⅝	287.84846	6593.52876	⅝	306.69802	7485.34847
¾	269.39160	5775.08242	¾	288.24116	6611.53156	¾	307.09072	7504.52937
⅞	269.78430	5791.93167	⅞	288.63386	6629.55890	⅞	307.48341	7523.73481
86	270.17700	5808.80546	92	289.02656	6647.61079	98	307.87611	7542.96479
⅛	270.56970	5825.70379	⅛	289.41926	6665.68722	⅛	308.26881	7562.21932
¼	270.96240	5842.62667	¼	289.81195	6683.78819	¼	308.66151	7581.49839
⅜	271.35510	5859.57409	⅜	290.20465	6701.91371	⅜	309.05421	7600.80201
½	271.74779	5876.54606	½	290.59735	6720.06378	½	309.44691	7620.13017
⅝	272.14049	5893.54257	⅝	290.99005	6738.23838	⅝	309.83961	7639.48287
¾	272.53319	5910.56362	¾	291.38275	6756.43753	¾	310.23231	7658.86012
⅞	272.92589	5927.60921	⅞	291.77545	6774.66123	⅞	310.62501	7678.26191
87	273.31859	5944.67935	93	292.16815	6792.90946	99	311.01771	7697.68825
⅛	273.71129	5961.77404	⅛	292.56085	6811.18225	⅛	311.41041	7717.13913
¼	274.10399	5978.89327	¼	292.95355	6829.47957	¼	311.80311	7736.61455
⅜	274.49669	5996.03704	⅜	293.34625	6847.80144	⅜	312.19580	7756.11451
½	274.88939	6013.20535	½	293.73895	6866.14785	½	312.58850	7775.63902
⅝	275.28209	6030.39821	⅝	294.13164	6884.51881	⅝	312.98120	7795.18808
¾	275.67479	6047.61561	¾	294.52434	6902.91431	¾	313.37390	7814.76167
⅞	276.06748	6064.85756	⅞	294.91704	6921.33435	⅞	313.76660	7834.35982
88	276.46018	6082.12405	94	295.30974	6939.77894	100	314.15930	7853.98250

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 100 to 249

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
100	314.15930	7853.98250	150	471.23895	17671.46063	200	628.31860	31415.93000
101	317.30089	8011.84755	151	474.38054	17907.86550	201	631.46019	31730.87470
102	320.44249	8171.28339	152	477.52214	18145.84117	202	634.60179	32047.39019
103	323.58408	8332.29003	153	480.66373	18385.38763	203	637.74338	32365.47648
104	326.72567	8494.86747	154	483.80532	18626.50490	204	640.88497	32685.13357
105	329.86727	8659.01571	155	486.94692	18869.19296	205	644.02657	33006.36146
106	333.00886	8824.73474	156	490.08851	19113.45181	206	647.16816	33329.16014
107	336.15045	8992.02456	157	493.23010	19359.28146	207	650.30975	33653.52961
108	339.29204	9160.88519	158	496.37169	19606.68191	208	653.45134	33979.46989
109	342.43364	9331.31661	159	499.51329	19855.65316	209	656.59294	34306.98096
110	345.57523	9503.31883	160	502.65488	20106.19520	210	659.73453	34636.06283
111	348.71682	9676.89184	161	505.79647	20358.30804	211	662.87612	34966.71549
112	351.85842	9852.03565	162	508.93807	20611.99167	212	666.01772	35298.93895
113	355.00001	10028.75025	163	512.07966	20867.24610	213	669.15931	35632.73320
114	358.14160	10207.03566	164	515.22125	21124.07133	214	672.30090	35968.09826
115	361.28320	10386.89186	165	518.36285	21382.46736	215	675.44250	36305.03411
116	364.42479	10568.31885	166	521.50444	21642.43418	216	678.58409	36643.54075
117	367.56638	10751.31664	167	524.64603	21903.97179	217	681.72568	36983.61819
118	370.70797	10935.88523	168	527.78762	22167.08021	218	684.86727	37325.26643
119	373.84957	11122.02462	169	530.92922	22431.75942	219	688.00887	37668.48547
120	376.99116	11309.73480	170	534.07081	22698.00943	220	691.15046	38013.27530
121	380.13275	11499.01578	171	537.21240	22965.83023	221	694.29205	38359.63593
122	383.27435	11689.86755	172	540.35400	23235.22183	222	697.43365	38707.56735
123	386.41594	11882.29012	173	543.49559	23506.18422	223	700.57524	39057.06957
124	389.55753	12076.28349	174	546.63718	23778.71742	224	703.71683	39408.14259
125	392.69913	12271.84766	175	549.77878	24052.82141	225	706.85843	39760.78641
126	395.84072	12468.98262	176	552.92037	24328.49619	226	710.00002	40115.00102
127	398.98231	12667.68837	177	556.06196	24605.74177	227	713.14161	40470.78642
128	402.12390	12867.96493	178	559.20355	24884.55815	228	716.28320	40828.14263
129	405.26550	13069.81228	179	562.34515	25164.94533	229	719.42480	41187.06963
130	408.40709	13273.23043	180	565.48674	25446.90330	230	722.56639	41547.56743
131	411.54868	13478.21937	181	568.62833	25730.43207	231	725.70798	41909.63602
132	414.69028	13684.77911	182	571.76993	26015.53163	232	728.84958	42273.27541
133	417.83187	13892.90964	183	574.91152	26302.20199	233	731.99117	42638.48559
134	420.97346	14102.61098	184	578.05311	26590.44315	234	735.13276	43005.26658
135	424.11506	14313.88311	185	581.19471	26880.25511	235	738.27436	43373.61836
136	427.25665	14526.72603	186	584.33630	27171.63786	236	741.41595	43743.54093
137	430.39824	14741.13975	187	587.47789	27464.59140	237	744.55754	44115.03430
138	433.53983	14957.12427	188	590.61948	27759.11575	238	747.69913	44488.09847
139	436.68143	15174.67959	189	593.76108	28055.21089	239	750.84073	44862.73344
140	439.82302	15393.80570	190	596.90267	28352.87683	240	753.98232	45238.93920
141	442.96461	15614.50261	191	600.04426	28652.11356	241	757.12391	45616.71576
142	446.10621	15836.77031	192	603.18586	28952.92109	242	760.26551	45996.06311
143	449.24780	16060.60881	193	606.32745	29255.29941	243	763.40710	46376.98126
144	452.38939	16286.01811	194	609.46904	29559.24854	244	766.54869	46759.47021
145	455.53099	16512.99821	195	612.61064	29864.76846	245	769.69029	47143.52996
146	458.67258	16741.54910	196	615.75223	30171.85917	246	772.83188	47529.16050
147	461.81417	16971.67078	197	618.89382	30480.52068	247	775.97347	47916.36183
148	464.95576	17203.36327	198	622.03541	30790.75299	248	779.11506	48305.13397
149	468.09736	17436.62655	199	625.17701	31102.55610	249	782.25666	48695.47690

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 250 to 399

Diameter	Circumference	Area	Diameter	Circumfernce	Area	Diameter	Circumfernce	Area
250	785.39825	49087.39063	300	942.47790	70685.84250	350	1099.55755	96211.28563
251	788.53984	49480.87515	301	945.61949	71157.86685	351	1102.69914	96761.84980
252	791.68144	49875.93047	302	948.76109	71631.46199	352	1105.84074	97313.98477
253	794.82303	50272.55658	303	951.90268	72106.62793	353	1108.98233	97867.69053
254	797.96462	50670.75350	304	955.04427	72583.36467	354	1112.12392	98422.96710
255	801.10622	51070.52121	305	958.18587	73061.67221	355	1115.26552	98979.81446
256	804.24781	51471.85971	306	961.32746	73541.55054	356	1118.40711	99538.23261
257	807.38940	51874.76901	307	964.46905	74022.99966	357	1121.54870	100098.22156
258	810.53099	52279.24911	308	967.61064	74506.01959	358	1124.69029	100659.78131
259	813.67259	52685.30001	309	970.75224	74990.61031	359	1127.83189	101222.91186
260	816.81418	53092.92170	310	973.89383	75476.77183	360	1130.97348	101787.61320
261	819.95577	53502.11419	311	977.03542	75964.50414	361	1134.11507	102353.88534
262	823.09737	53912.87747	312	980.17702	76453.80725	362	1137.25667	102921.72827
263	826.23896	54325.21155	313	983.31861	76944.68115	363	1140.39826	103491.14200
264	829.38055	54739.11643	314	986.46020	77437.12586	364	1143.53985	104062.12653
265	832.52215	55154.59211	315	989.60180	77931.14136	365	1146.68145	104634.68186
266	835.66374	55571.63858	316	992.74339	78426.72765	366	1149.82304	105208.80798
267	838.80533	55990.25584	317	995.88498	78923.88474	367	1152.96463	105784.50489
268	841.94692	56410.44391	318	999.02657	79422.61263	368	1156.10622	106361.77261
269	845.08852	56832.20277	319	1002.16817	79922.91132	369	1159.24782	106940.61112
270	848.23011	57255.53243	320	1005.30976	80424.78080	370	1162.38941	107521.02043
271	851.37170	57680.43288	321	1008.45135	80928.22108	371	1165.53100	108103.00053
272	854.51330	58106.90413	322	1011.59295	81433.23215	372	1168.67260	108686.55143
273	857.65489	58534.94617	323	1014.73454	81939.81402	373	1171.81419	109271.67312
274	860.79648	58964.55902	324	1017.87613	82447.96669	374	1174.95578	109858.36562
275	863.93808	59395.74266	325	1021.01773	82957.69016	375	1178.09738	110446.62891
276	867.07967	59828.49709	326	1024.15932	83468.98442	376	1181.23897	111036.46299
277	870.22126	60262.82232	327	1027.30091	83981.84947	377	1184.38056	111627.86787
278	873.36285	60698.71835	328	1030.44250	84496.28533	378	1187.52215	112220.84355
279	876.50445	61136.18518	329	1033.58410	85012.29198	379	1190.66375	112815.39003
280	879.64604	61575.22280	330	1036.72569	85529.86943	380	1193.80534	113411.50730
281	882.78763	62015.83122	331	1039.86728	86049.01767	381	1196.94693	114009.19537
282	885.92923	62458.01043	332	1043.00888	86569.73671	382	1200.08853	114608.45423
283	889.07082	62901.76044	333	1046.15047	87092.02654	383	1203.23012	115209.28389
284	892.21241	63347.08125	334	1049.29206	87615.88718	384	1206.37171	115811.68435
285	895.35401	63793.97286	335	1052.43366	88141.31861	385	1209.51331	116415.65561
286	898.49560	64242.43526	336	1055.57525	88668.32083	386	1212.65490	117021.19766
287	901.63719	64692.46845	337	1058.71684	89196.89385	387	1215.79649	117628.31050
288	904.77878	65144.07245	338	1061.85843	89727.03767	388	1218.93808	118236.99415
289	907.92038	65597.24724	339	1065.00003	90258.75229	389	1222.07968	118847.24859
290	911.06197	66051.99283	340	1068.14162	90792.03770	390	1225.22127	119459.07383
291	914.20356	66508.30921	341	1071.28321	91326.89391	391	1228.36286	120072.46986
292	917.34516	66966.19639	342	1074.42481	91863.32091	392	1231.50446	120687.43669
293	920.48675	67425.65436	343	1077.56640	92401.31871	393	1234.64605	121303.97431
294	923.62834	67886.68314	344	1080.70799	92940.88731	394	1237.78764	121922.08274
295	926.76994	68349.28271	345	1083.84959	93482.02671	395	1240.92924	122541.76196
296	929.91153	68813.45307	346	1086.99118	94024.73690	396	1244.07083	123163.01197
297	933.05312	69279.19423	347	1090.13277	94569.01788	397	1247.21242	123785.83278
298	936.19471	69746.50619	348	1093.27436	95114.86967	398	1250.35401	124410.22439
299	939.33631	70215.38895	349	1096.41596	95662.29225	399	1253.49561	125036.18680

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 400 to 549

Dia-meter	Circum-ference	Area	Dia-meter	Circum-ference	Area	Dia-meter	Circum-ference	Area
400	1256.63720	125663.72000	450	1413.71685	159043.14563	500	1570.79650	196349.56250
401	1259.77879	126292.82400	451	1416.85844	159750.78945	501	1573.93809	197135.74615
402	1262.92039	126923.49879	452	1420.00004	160460.00407	502	1577.07969	197923.50059
403	1266.06198	127555.74438	453	1423.14163	161170.78948	503	1580.22128	198712.82583
404	1269.20357	128189.56077	454	1426.28322	161883.14570	504	1583.36287	199503.72187
405	1272.34517	128824.94796	455	1429.42482	162597.07271	505	1586.50447	200296.18871
406	1275.48676	129461.90594	456	1432.56641	163312.57051	506	1589.64606	201090.22634
407	1278.62835	130100.43471	457	1435.70800	164029.63911	507	1592.78765	201885.83476
408	1281.76994	130740.53429	458	1438.84959	164748.27851	508	1595.92924	202683.01399
409	1284.91154	131382.20466	459	1441.99119	165468.48871	509	1599.07084	203481.76401
410	1288.05313	132025.44583	460	1445.13278	166190.26970	510	1602.21243	204282.08483
411	1291.19472	132670.25779	461	1448.27437	166913.62149	511	1605.35402	205083.97644
412	1294.33632	133316.64055	462	1451.41597	167638.54407	512	1608.49562	205887.43885
413	1297.47791	133964.59410	463	1454.55756	168365.03745	513	1611.63721	206692.47205
414	1300.61950	134614.11846	464	1457.69915	169093.10163	514	1614.77880	207499.07606
415	1303.76110	135265.21361	465	1460.84075	169822.73661	515	1617.92040	208307.25086
416	1306.90269	135917.87955	466	1463.98234	170553.94238	516	1621.06199	209116.99645
417	1310.04428	136572.11629	467	1467.12393	171286.71894	517	1624.20358	209928.31284
418	1313.18587	137227.92383	468	1470.26552	172021.06631	518	1627.34517	210741.20003
419	1316.32747	137885.30217	469	1473.40712	172756.98447	519	1630.48677	211555.65802
420	1319.46906	138544.25130	470	1476.54871	173494.47343	520	1633.62836	212371.68680
421	1322.61065	139204.77123	471	1479.69030	174233.53318	521	1636.76995	213189.28638
422	1325.75225	139866.86195	472	1482.83190	174974.16373	522	1639.91155	214008.45675
423	1328.89384	140530.52347	473	1485.97349	175716.36507	523	1643.05314	214829.19792
424	1332.03543	141195.75579	474	1489.11508	176460.13722	524	1646.19473	215651.50989
425	1335.17703	141862.55891	475	1492.25668	177205.48016	525	1649.33633	216475.39266
426	1338.31862	142530.93282	476	1495.39827	177952.39389	526	1652.47792	217300.84622
427	1341.46021	143200.87752	477	1498.53986	178700.87842	527	1655.61951	218127.87057
428	1344.60180	143872.39303	478	1501.68145	179450.93375	528	1658.76110	218956.46573
429	1347.74340	144545.47933	479	1504.82305	180202.55988	529	1661.90270	219786.63168
430	1350.88499	145220.13643	480	1507.96464	180955.75680	530	1665.04429	220618.36843
431	1354.02658	145896.36432	481	1511.10623	181710.52452	531	1668.18588	221451.67597
432	1357.16818	146574.16301	482	1514.24783	182466.86303	532	1671.32748	222286.55431
433	1360.30977	147253.53249	483	1517.38942	183224.77234	533	1674.46907	223123.00344
434	1363.45136	147934.47278	484	1520.53101	183984.25245	534	1677.61066	223961.02338
435	1366.59296	148616.98386	485	1523.67261	184745.30336	535	1680.75226	224800.61411
436	1369.73455	149301.06573	486	1526.81420	185507.92506	536	1683.89385	225641.77563
437	1372.87614	149986.71840	487	1529.95579	186272.11755	537	1687.03544	226484.50795
438	1376.01773	150673.94187	488	1533.09738	187037.88085	538	1690.17703	227328.81107
439	1379.15933	151362.73614	489	1536.23898	187805.21494	539	1693.31863	228174.68499
440	1382.30092	152053.10120	490	1539.38057	188574.11983	540	1696.46022	229022.12970
441	1385.44251	152745.03706	491	1542.52216	189344.59551	541	1699.60181	229871.14521
442	1388.58411	153438.54371	492	1545.66376	190116.64199	542	1702.74341	230721.73151
443	1391.72570	154133.62116	493	1548.80535	190890.25926	543	1705.88500	231573.88861
444	1394.86729	154830.26941	494	1551.94694	191665.44734	544	1709.02659	232427.61651
445	1398.00889	155528.48846	495	1555.08854	192442.20621	545	1712.16819	233282.91521
446	1401.15048	156228.27830	496	1558.23013	193220.53587	546	1715.30978	234139.78470
447	1404.29207	156929.63893	497	1561.37172	194000.43633	547	1718.45137	234998.22498
448	1407.43366	157632.57037	498	1564.51331	194781.90759	548	1721.59296	235858.23607
449	1410.57526	158337.07260	499	1567.65491	195564.94965	549	1724.73456	236719.81795

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 550 to 699

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
550	1727.87615	237582.97063	600	1884.95580	282743.37000	650	2042.03545	331830.76063
551	1731.01774	238447.69410	601	1888.09739	283686.63330	651	2045.17704	332852.56375
552	1734.15934	239313.98837	602	1891.23899	284631.46739	652	2048.31864	333875.93767
553	1737.30093	240181.85343	603	1894.38058	285577.87228	653	2051.46023	334900.88238
554	1740.44252	241051.28930	604	1897.52217	286525.84797	654	2054.60182	335927.39790
555	1743.58412	241922.29596	605	1900.66377	287475.39446	655	2057.74342	336955.48421
556	1746.72571	242794.87341	606	1903.80536	288426.51174	656	2060.88501	337985.14131
557	1749.86730	243669.02166	607	1906.94695	289379.19981	657	2064.02660	339016.36921
558	1753.00889	244544.74071	608	1910.08854	290333.45869	658	2067.16819	340049.16791
559	1756.15049	245422.03056	609	1913.23014	291289.28836	659	2070.30979	341083.53741
560	1759.29208	246300.89120	610	1916.37173	292246.68883	660	2073.45138	342119.47770
561	1762.43367	247181.32264	611	1919.51332	293205.66009	661	2076.59297	343156.98879
562	1765.57527	248063.32487	612	1922.65492	294166.20215	662	2079.73457	344196.07067
563	1768.71686	248946.89790	613	1925.79651	295128.31500	663	2082.87616	345236.72335
564	1771.85845	249832.04173	614	1928.93810	296091.99866	664	2086.01775	346278.94683
565	1775.00005	250718.75636	615	1932.07970	297057.25311	665	2089.15935	347322.74111
566	1778.14164	251607.04178	616	1935.22129	298024.07835	666	2092.30094	348368.10618
567	1781.28323	252496.89799	617	1938.36288	298992.47439	667	2095.44253	349415.04204
568	1784.42482	253388.32501	618	1941.50447	299962.44123	668	2098.58412	350463.54871
569	1787.56642	254281.32282	619	1944.64607	300933.97887	669	2101.72572	351513.62617
570	1790.70801	255175.89143	620	1947.78766	301907.08730	670	2104.86731	352565.27443
571	1793.84960	256072.03083	621	1950.92925	302881.76653	671	2108.00890	353618.49348
572	1796.99120	256969.74103	622	1954.07085	303858.01655	672	2111.15050	354673.28333
573	1800.13279	257869.02202	623	1957.21244	304835.83737	673	2114.29209	355729.64397
574	1803.27438	258769.87382	624	1960.35403	305815.22899	674	2117.43368	356787.57542
575	1806.41598	259672.29641	625	1963.49563	306796.19141	675	2120.57528	357847.07766
576	1809.55757	260576.28979	626	1966.63722	307778.72462	676	2123.71687	358908.15069
577	1812.69916	261481.85397	627	1969.77881	308762.82862	677	2126.85846	359970.79452
578	1815.84075	262388.98895	628	1972.92040	309748.50343	678	2130.00005	361035.00915
579	1818.98235	263297.69473	629	1976.06200	310735.74903	679	2133.14165	362100.79458
580	1822.12394	264207.97130	630	1979.20359	311724.56543	680	2136.28324	363168.15080
581	1825.26553	265119.81867	631	1982.34518	312714.95262	681	2139.42483	364237.07782
582	1828.40713	266033.23683	632	1985.48678	313706.91061	682	2142.56643	365307.57563
583	1831.54872	266948.22579	633	1988.62837	314700.43939	683	2145.70802	366379.64424
584	1834.69031	267864.78555	634	1991.76996	315695.53898	684	2148.84961	367453.28365
585	1837.83191	268782.91611	635	1994.91156	316692.20936	685	2151.99121	368528.49386
586	1840.97350	269702.61746	636	1998.05315	317690.45053	686	2155.13280	369605.27486
587	1844.11509	270623.88960	637	2001.19474	318690.26250	687	2158.27439	370683.62665
588	1847.25668	271546.73255	638	2004.33633	319691.64527	688	2161.41598	371763.54925
589	1850.39828	272471.14629	639	2007.47793	320694.59884	689	2164.55758	372845.04264
590	1853.53987	273397.13083	640	2010.61952	321699.12320	690	2167.69917	373928.10683
591	1856.68146	274324.68616	641	2013.76111	322705.21836	691	2170.84076	375012.74181
592	1859.82306	275253.81229	642	2016.90271	323712.88431	692	2173.98236	376098.94759
593	1862.96465	276184.50921	643	2020.04430	324722.12106	693	2177.12395	377186.72416
594	1866.10624	277116.77694	644	2023.18589	325732.92861	694	2180.26554	378276.07154
595	1869.24784	278050.61546	645	2026.32749	326745.30696	695	2183.40714	379366.98971
596	1872.38943	278986.02477	646	2029.46908	327759.25610	696	2186.54873	380459.47867
597	1875.53102	279923.00488	647	2032.61067	328774.77603	697	2189.69032	381553.53843
598	1878.67261	280861.55579	648	2035.75226	329791.86677	698	2192.83191	382649.16899
599	1881.81421	281801.67750	649	2038.89386	330810.52830	699	2195.97351	383746.37035

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 700 to 849

Dia-meter	Circum-ference	Area	Dia-meter	Circum-ference	Area	Dia-meter	Circum-ference	Area
700	2199.11510	384845.14250	750	2356.19475	441786.51563	800	2513.27440	502654.88000
701	2202.25669	385945.48545	751	2359.33634	442965.39840	801	2516.41599	503912.30260
702	2205.39829	387047.39919	752	2362.47794	444145.85197	802	2519.55759	505171.29599
703	2208.53988	388150.88373	753	2365.61953	445327.87633	803	2522.69918	506431.86018
704	2211.68147	389255.93907	754	2368.76112	446511.47150	804	2525.84077	507693.99517
705	2214.82307	390362.56521	755	2371.90272	447696.63746	805	2528.98237	508957.70096
706	2217.96466	391470.76214	756	2375.04431	448883.37421	806	2532.12396	510222.97754
707	2221.10625	392580.52986	757	2378.18590	450071.68176	807	2535.26555	511489.82491
708	2224.24784	393691.86839	758	2381.32749	451261.56011	808	2538.40714	512758.24309
709	2227.38944	394804.77771	759	2384.46909	452453.00926	809	2541.54874	514028.23206
710	2230.53103	395919.25783	760	2387.61068	453646.02920	810	2544.69033	515299.79183
711	2233.67262	397035.30874	761	2390.75227	454840.61994	811	2547.83192	516572.92239
712	2236.81422	398152.93045	762	2393.89387	456036.78147	812	2550.97352	517847.62375
713	2239.95581	399272.12295	763	2397.03546	457234.51380	813	2554.11511	519123.89590
714	2243.09740	400392.88626	764	2400.17705	458433.81693	814	2557.25670	520401.73886
715	2246.23900	401515.22036	765	2403.31865	459634.69086	815	2560.39830	521681.15261
716	2249.38059	402639.12525	766	2406.46024	460837.13558	816	2563.53989	522962.13715
717	2252.52218	403764.60094	767	2409.60183	462041.15109	817	2566.68148	524244.69249
718	2255.66377	404891.64743	768	2412.74342	463246.73741	818	2569.82307	525528.81863
719	2258.80537	406020.26472	769	2415.88502	464453.89452	819	2572.96467	526814.51557
720	2261.94696	407150.45280	770	2419.02661	465662.62243	820	2576.10626	528101.78330
721	2265.08855	408282.21168	771	2422.16820	466872.92113	821	2579.24785	529390.62183
722	2268.23015	409415.54135	772	2425.30980	468084.79063	822	2582.38945	530681.03115
723	2271.37174	410550.44182	773	2428.45139	469298.23092	823	2585.53104	531973.01127
724	2274.51333	411686.91309	774	2431.59298	470513.24202	824	2588.67263	533266.56219
725	2277.65493	412824.95516	775	2434.73458	471729.82391	825	2591.81423	534561.68391
726	2280.79652	413964.56802	776	2437.87617	472947.97659	826	2594.95582	535858.37642
727	2283.93811	415105.75167	777	2441.01776	474167.70007	827	2598.09741	537156.63972
728	2287.07970	416248.50613	778	2444.15935	475388.99435	828	2601.23900	538456.47383
729	2290.22130	417392.83138	779	2447.30095	476611.85943	829	2604.38060	539757.87873
730	2293.36289	418538.72743	780	2450.44254	477836.29530	830	2607.52219	541060.85443
731	2296.50448	419686.19427	781	2453.58413	479062.30197	831	2610.66378	542365.40092
732	2299.64608	420835.23191	782	2456.72573	480289.87943	832	2613.80538	543671.51821
733	2302.78767	421985.84034	783	2459.86732	481519.02769	833	2616.94697	544979.20629
734	2305.92926	423138.01958	784	2463.00891	482749.74675	834	2620.08856	546288.46518
735	2309.07086	424291.76961	785	2466.15051	483982.03661	835	2623.23016	547599.29486
736	2312.21245	425447.09043	786	2469.29210	485215.89726	836	2626.37175	548911.69533
737	2315.35404	426603.98205	787	2472.43369	486451.32870	837	2629.51334	550225.66660
738	2318.49563	427762.44447	788	2475.57528	487688.33095	838	2632.65493	551541.20867
739	2321.63723	428922.47769	789	2478.71688	488926.90399	839	2635.79653	552858.32154
740	2324.77882	430084.08170	790	2481.85847	490167.04783	840	2638.93812	554177.00520
741	2327.92041	431247.25651	791	2485.00006	491408.76246	841	2642.07971	555497.25966
742	2331.06201	432412.00211	792	2488.14166	492652.04789	842	2645.22131	556819.08491
743	2334.20360	433578.31851	793	2491.28325	493896.90411	843	2648.36290	558142.48096
744	2337.34519	434746.20571	794	2494.42484	495143.33114	844	2651.50449	559467.44781
745	2340.48679	435915.66371	795	2497.56644	496391.32896	845	2654.64609	560793.98546
746	2343.62838	437086.69250	796	2500.70803	497640.89757	846	2657.78768	562122.09390
747	2346.76997	438259.29208	797	2503.84962	498892.03698	847	2660.92927	563451.77313
748	2349.91156	439433.46247	798	2506.99121	500144.74719	848	2664.07086	564783.02317
749	2353.05316	440609.20365	799	2510.13281	501399.02820	849	2667.21246	566115.84400

Copyright 2004, Industrial Press, Inc., New York, NY

Circumferences and Areas of Circles From 850-999

Diameter	Circumference	Area	Diameter	Circumference	Area	Diameter	Circumference	Area
850	2670.35405	567450.23563	900	2827.43370	636172.58250	950	2984.51335	708821.92063
851	2673.49564	568786.19805	901	2830.57529	637587.08475	951	2987.65494	710314.96270
852	2676.63724	570123.73127	902	2833.71689	639003.15779	952	2990.79654	711809.57557
853	2679.77883	571462.83528	903	2836.85848	640420.80163	953	2993.93813	713305.75923
854	2682.92042	572803.51010	904	2840.00007	641840.01627	954	2997.07972	714803.51370
855	2686.06202	574145.75571	905	2843.14167	643260.80171	955	3000.22132	716302.83896
856	2689.20361	575489.57211	906	2846.28326	644683.15794	956	3003.36291	717803.73501
857	2692.34520	576834.95931	907	2849.42485	646107.08496	957	3006.50450	719306.20186
858	2695.48679	578181.91731	908	2852.56644	647532.58279	958	3009.64609	720810.23951
859	2698.62839	579530.44611	909	2855.70804	648959.65141	959	3012.78769	722315.84796
860	2701.76998	580880.54570	910	2858.84963	650388.29083	960	3015.92928	723823.02720
861	2704.91157	582232.21609	911	2861.99122	651818.50104	961	3019.07087	725331.77724
862	2708.05317	583585.45727	912	2865.13282	653250.28205	962	3022.21247	726842.09807
863	2711.19476	584940.26925	913	2868.27441	654683.63385	963	3025.35406	728353.98970
864	2714.33635	586296.65203	914	2871.41600	656118.55646	964	3028.49565	729867.45213
865	2717.47795	587654.60561	915	2874.55760	657555.04986	965	3031.63725	731382.48536
866	2720.61954	589014.12998	916	2877.69919	658993.11405	966	3034.77884	732899.08938
867	2723.76113	590375.22514	917	2880.84078	660432.74904	967	3037.92043	734417.26419
868	2726.90272	591737.89111	918	2883.98237	661873.95483	968	3041.06202	735937.00981
869	2730.04432	593102.12787	919	2887.12397	663316.73142	969	3044.20362	737458.32622
870	2733.18591	594467.93543	920	2890.26556	664761.07880	970	3047.34521	738981.21343
871	2736.32750	595835.31378	921	2893.40715	666206.99698	971	3050.48680	740505.67143
872	2739.46910	597204.26293	922	2896.54875	667654.48595	972	3053.62840	742031.70023
873	2742.61069	598574.78287	923	2899.69034	669103.54572	973	3056.76999	743559.29982
874	2745.75228	599946.87362	924	2902.83193	670554.17629	974	3059.91158	745088.47022
875	2748.89388	601320.53516	925	2905.97353	672006.37766	975	3063.05318	746619.21141
876	2752.03547	602695.76749	926	2909.11512	673460.14982	976	3066.19477	748151.52339
877	2755.17706	604072.57062	927	2912.25671	674915.49277	977	3069.33636	749685.40617
878	2758.31865	605450.94455	928	2915.39830	676372.40653	978	3072.47795	751220.85975
879	2761.46025	606830.88928	929	2918.53990	677830.89108	979	3075.61955	752757.88413
880	2764.60184	608212.40480	930	2921.68149	679290.94643	980	3078.76114	754296.47930
881	2767.74343	609595.49112	931	2924.82308	680752.57257	981	3081.90273	755836.64527
882	2770.88503	610980.14823	932	2927.96468	682215.76951	982	3085.04433	757378.38203
883	2774.02662	612366.37614	933	2931.10627	683680.53724	983	3088.18592	758921.68959
884	2777.16821	613754.17485	934	2934.24786	685146.87578	984	3091.32751	760466.56795
885	2780.30981	615143.54436	935	2937.38946	686614.78511	985	3094.46911	762013.01711
886	2783.45140	616534.48466	936	2940.53105	688084.26523	986	3097.61070	763561.03706
887	2786.59299	617926.99575	937	2943.67264	689555.31615	987	3100.75229	765110.62780
888	2789.73458	619321.07765	938	2946.81423	691027.93787	988	3103.89388	766661.78935
889	2792.87618	620716.73034	939	2949.95583	692502.13039	989	3107.03548	768214.52169
890	2796.01777	622113.95383	940	2953.09742	693977.89370	990	3110.17707	769768.82483
891	2799.15936	623512.74811	941	2956.23901	695455.22781	991	3113.31866	771324.69876
892	2802.30096	624913.11319	942	2959.38061	696934.13271	992	3116.46026	772882.14349
893	2805.44255	626315.04906	943	2962.52220	698414.60841	993	3119.60185	774441.15901
894	2808.58414	627718.55574	944	2965.66379	699896.65491	994	3122.74344	776001.74534
895	2811.72574	629123.63321	945	2968.80539	701380.27221	995	3125.88504	777563.90246
896	2814.86733	630530.28147	946	2971.94698	702865.46030	996	3129.02663	779127.63037
897	2818.00892	631938.50053	947	2975.08857	704352.21918	997	3132.16822	780692.92908
898	2821.15051	633348.29039	948	2978.23016	705840.54887	998	3135.30981	782259.79859
899	2824.29211	634759.65105	949	2981.37176	707330.44935	999	3138.45141	783828.23890

Copyright 2004, Industrial Press, Inc., New York, NY

Table of Decimal Equivalents, Squares, Cubes, Square Roots, Cube Roots, and Logarithms of Fractions from 1/64 to 1, by 64ths

Fraction	Decimal	Log	Square	Log	Cube	Log	Sq. Root	Log	Cube Root	Log
1/64	0.015625	-1.80618	0.00024	-3.61236	0.00000	-5.41854	0.12500	-0.90309	0.25000	-0.60206
1/32	0.031250	-1.50515	0.00098	-3.01030	0.00003	-4.51545	0.17678	-0.75257	0.31498	-0.50172
3/64	0.046875	-1.32906	0.00220	-2.65812	0.00010	-3.98718	0.21651	-0.66453	0.36056	-0.44302
1/16	0.062500	-1.20412	0.00391	-2.40824	0.00024	-3.61236	0.25000	-0.60206	0.39685	-0.40137
5/64	0.078125	-1.10721	0.00610	-2.21442	0.00048	-3.32163	0.27951	-0.55361	0.42749	-0.36907
3/32	0.093750	-1.02803	0.00879	-2.05606	0.00082	-3.08409	0.30619	-0.51402	0.45428	-0.34268
7/64	0.109375	-0.96108	0.01196	-1.92216	0.00131	-2.88325	0.33072	-0.48054	0.47823	-0.32036
1/8	0.125000	-0.90309	0.01563	-1.80618	0.00195	-2.70927	0.35355	-0.45155	0.50000	-0.30103
9/64	0.140625	-0.85194	0.01978	-1.70388	0.00278	-2.55581	0.37500	-0.42597	0.52002	-0.28398
5/32	0.156250	-0.80618	0.02441	-1.61236	0.00381	-2.41854	0.39529	-0.40309	0.53861	-0.26873
11/64	0.171875	-0.76479	0.02954	-1.52958	0.00508	-2.29436	0.41458	-0.38239	0.55600	-0.25493
3/16	0.187500	-0.72700	0.03516	-1.45400	0.00659	-2.18100	0.43301	-0.36350	0.57236	-0.24233
13/64	0.203125	-0.69224	0.04126	-1.38447	0.00838	-2.07671	0.45069	-0.34612	0.58783	-0.23075
7/32	0.218750	-0.66005	0.04785	-1.32010	0.01047	-1.98016	0.46771	-0.33003	0.60254	-0.22002
15/64	0.234375	-0.63009	0.05493	-1.26018	0.01287	-1.89027	0.48412	-0.31504	0.61655	-0.21003
1/4	0.250000	-0.60206	0.06250	-1.20412	0.01563	-1.80618	0.50000	-0.30103	0.62996	-0.20069
17/64	0.265625	-0.57573	0.07056	-1.15146	0.01874	-1.72719	0.51539	-0.28787	0.64282	-0.19191
9/32	0.281250	-0.55091	0.07910	-1.10182	0.02225	-1.65272	0.53033	-0.27545	0.65519	-0.18364
19/64	0.296875	-0.52743	0.08813	-1.05485	0.02617	-1.58228	0.54486	-0.26371	0.66710	-0.17581
5/16	0.312500	-0.50515	0.09766	-1.01030	0.03052	-1.51545	0.55902	-0.25258	0.67860	-0.16838
21/64	0.328125	-0.48396	0.10767	-0.96792	0.03533	-1.45188	0.57282	-0.24198	0.68973	-0.16132
11/32	0.343750	-0.46376	0.11816	-0.92752	0.04062	-1.39127	0.58630	-0.23188	0.70051	-0.15459
23/64	0.359375	-0.44445	0.12915	-0.88890	0.04641	-1.33336	0.59948	-0.22223	0.71097	-0.14815
3/8	0.375000	-0.42597	0.14063	-0.85194	0.05273	-1.27791	0.61237	-0.21299	0.72113	-0.14199
25/64	0.390625	-0.40824	0.15259	-0.81648	0.05960	-1.22472	0.62500	-0.20412	0.73100	-0.13608
13/32	0.406250	-0.39121	0.16504	-0.78241	0.06705	-1.17362	0.63738	-0.19560	0.74062	-0.13040
27/64	0.421875	-0.37482	0.17798	-0.74963	0.07508	-1.12445	0.64952	-0.18741	0.75000	-0.12494
7/16	0.437500	-0.35902	0.19141	-0.71804	0.08374	-1.07707	0.66144	-0.17951	0.75915	-0.11967
29/64	0.453125	-0.34378	0.20532	-0.68756	0.09304	-1.03135	0.67315	-0.17189	0.76808	-0.11459
15/32	0.468750	-0.32906	0.21973	-0.65812	0.10300	-0.98718	0.68465	-0.16453	0.77681	-0.10969
31/64	0.484375	-0.31482	0.23462	-0.62964	0.11364	-0.94446	0.69597	-0.15741	0.78535	-0.10494
1/2	0.500000	-0.30103	0.25000	-0.60206	0.12500	-0.90309	0.70711	-0.15052	0.79370	-0.10034
33/64	0.515625	-0.28767	0.26587	-0.57533	0.13709	-0.86300	0.71807	-0.14383	0.80188	-0.09589
17/32	0.531250	-0.27470	0.28223	-0.54940	0.14993	-0.82410	0.72887	-0.13735	0.80990	-0.09157
35/64	0.546875	-0.26211	0.29907	-0.52422	0.16356	-0.78634	0.73951	-0.13106	0.81777	-0.08737
9/16	0.562500	-0.24988	0.31641	-0.49976	0.17798	-0.74963	0.75000	-0.12494	0.82548	-0.08329
37/64	0.578125	-0.23798	0.33423	-0.47596	0.19323	-0.71394	0.76035	-0.11899	0.83306	-0.07933
19/32	0.593750	-0.22640	0.35254	-0.45279	0.20932	-0.67919	0.77055	-0.11320	0.84049	-0.07547
39/64	0.609375	-0.21512	0.37134	-0.43023	0.22628	-0.64535	0.78063	-0.10756	0.84780	-0.07171
5/8	0.625000	-0.20412	0.39063	-0.40824	0.24414	-0.61236	0.79057	-0.10206	0.85499	-0.06804
41/64	0.640625	-0.19340	0.41040	-0.38679	0.26291	-0.58019	0.80039	-0.09670	0.86205	-0.06447
21/32	0.656250	-0.18293	0.43066	-0.36586	0.28262	-0.54879	0.81009	-0.09147	0.86901	-0.06098
43/64	0.671875	-0.17271	0.45142	-0.34542	0.30330	-0.51814	0.81968	-0.08636	0.87585	-0.05757
11/16	0.687500	-0.16273	0.47266	-0.32546	0.32495	-0.48818	0.82916	-0.08136	0.88259	-0.05424
45/64	0.703125	-0.15297	0.49438	-0.30594	0.34761	-0.45890	0.83853	-0.07648	0.88922	-0.05099
23/32	0.718750	-0.14342	0.51660	-0.28684	0.37131	-0.43027	0.84779	-0.07171	0.89576	-0.04781
47/64	0.734375	-0.13408	0.53931	-0.26816	0.39605	-0.40225	0.85696	-0.06704	0.90221	-0.04469
3/4	0.750000	-0.12494	0.56250	-0.24988	0.42188	-0.37482	0.86603	-0.06247	0.90856	-0.04165
49/64	0.765625	-0.11598	0.58618	-0.23197	0.44880	-0.34795	0.87500	-0.05799	0.91483	-0.03866
25/32	0.781250	-0.10721	0.61035	-0.21442	0.47684	-0.32163	0.88388	-0.05361	0.92101	-0.03574
51/64	0.796875	-0.09861	0.63501	-0.19722	0.50602	-0.29583	0.89268	-0.04931	0.92711	-0.03287
13/16	0.812500	-0.09018	0.66016	-0.18035	0.53638	-0.27053	0.90139	-0.04509	0.93313	-0.03006
53/64	0.828125	-0.08190	0.68579	-0.16381	0.56792	-0.24571	0.91001	-0.04095	0.93907	-0.02730
27/32	0.843750	-0.07379	0.71191	-0.14757	0.60068	-0.22136	0.91856	-0.03689	0.94494	-0.02460
55/64	0.859375	-0.06582	0.73853	-0.13164	0.63467	-0.19745	0.92703	-0.03291	0.95074	-0.02194
7/8	0.875000	-0.05799	0.76563	-0.11598	0.66992	-0.17398	0.93541	-0.02900	0.95647	-0.01933
57/64	0.890625	-0.05031	0.79321	-0.10061	0.70646	-0.15092	0.94373	-0.02515	0.96213	-0.01677
29/32	0.906250	-0.04275	0.82129	-0.08550	0.74429	-0.12826	0.95197	-0.02138	0.96772	-0.01425
59/64	0.921875	-0.03533	0.84985	-0.07066	0.78346	-0.10598	0.96014	-0.01766	0.97325	-0.01178
15/16	0.937500	-0.02803	0.87891	-0.05606	0.82397	-0.08409	0.96825	-0.01401	0.97872	-0.00934
61/64	0.953125	-0.02085	0.90845	-0.04170	0.86586	-0.06255	0.97628	-0.01043	0.98412	-0.00695
31/32	0.968750	-0.01379	0.93848	-0.02758	0.90915	-0.04137	0.98425	-0.00689	0.98947	-0.00460
63/64	0.984375	-0.00684	0.96899	-0.01368	0.95385	-0.02052	0.99216	-0.00342	0.99476	-0.00228
1	1.000000	0.00000	1.00000	0.00000	1.00000	0.00000	1.00000	0.00000	1.00000	0.00000

Copyright 2004, Industrial Press, Inc., New York, NY

CEMENT, CONCRETE, LUTES, ADHESIVES, AND SEALANTS

Cement

The cements used in concrete construction are classified as:

1) Portland cements.
2) Natural cements.
3) Pozzuolanic, pozzuolan, or slag cements.

These different classes are all hydraulic cements as they will set or harden under water. When the powdered cement is mixed with water to a plastic condition, the cement sets or solidifies as the result of chemical action. After the preliminary hardening or initial set, the cement slowly increases in strength, the increase extending over months or years.

Portland Cement.— Portland and natural cements are the kinds most commonly used. Portland cement should be used for all structures which must withstand stresses and for masonry that is either under water or heavily exposed to water or the weather. According to the specifications of the American Society for Testing Materials, the specific gravity of Portland cement must be not less than 8:1. If the tested cement is below this requirement. A second test should be made on a sample ignited at a low red heat. The ignited cement should not lose more than four per cent of its weight. A satisfactory Portland cement must not develop initial set in less than 30 minutes; it must not develop hard set in less than 1 hour; but the time required for developing hard set must not exceed 10 hours. The minimum requirements for tensile strength in pounds, for briquettes one square inch in cross-section, should be as follows:

For cement 24 hours old in moist air, 175 pounds.

For cement 7 days old, one day in moist air and six days in water, 500 pounds.

For cement 28 days old, one day in moist air and 27 days in water, 600 pounds.

For one part of cement and three parts of standard Ottawa sand, 7 days old, one day in moist air and six days in water, 200 pounds.

For one part of cement and three parts of standard Ottawa sand, 28 days old, one day in moist air and 27 days in water, 275 pounds.

The cements must under no circumstances show a decrease in strength during the time periods specified.

Natural Cement.— Natural cement is used in mortar for ordinary brick work and stone masonry, street sub-pavements, as a backing or filling for massive concrete or stone masonry, and for similar purposes. Natural cement does not develop its strength as quickly and is not as uniform in composition as Portland cement. It should not be used for columns, beams, floors or any structural members which must withstand considerable stress. Natural cement is also unsuitable for work that is exposed to water. Foundations which are subjected to moderate compressive stresses may be made of natural cement, which is also satisfactory for massive masonry where weight rather than strength is the essential feature.

The American Society for Testing Materials gives the following specifications for natural cement: An initial set must not develop in less than 10 minutes, and the hard set must not develop in less than 30 minutes, but must develop in less than three hours. The minimum requirements for tensile strength in pounds, for briquettes one inch in cross-section, are as follows:

For natural cement 24 hours old in moist air, 75 pounds.

For natural cement 7 days old, one day in moist air and six days in water, 150 pounds.

For natural cement 28 days old, one day in moist air and 27 days in water, 250 pounds.

For one part of cement and three parts of standard Ottawa sand, 7 days old, one day in moist air and six days in water, 50 pounds.

For one part of cement and three parts of standard Ottawa sand, 28 days old, one day in moist air and 27 days in water, 125 pounds.

Copyright 2004, Industrial Press, Inc., New York, NY

Pozzuolanic or Slag Cement.— This cement is adapted for structures which are constantly exposed to fresh or salt water and for drains, sewers, foundation work underground, etc. It is not suitable where masonry is exposed to dry air for long periods. Pozzuolanic cement sets slowly but its strength increases considerably with age. While this cement is relatively cheap, it is not as strong, uniform, or reliable as Portland and natural cements, and is not used extensively.

Concrete

Concrete.— The principal ingredients of concrete are the matrix or mortar and the "coarse aggregate." The matrix consists of cement and sand mixed with water, and the coarse aggregate is usually broken stone or gravel. What is known as *rubble concrete* or cyclopean masonry contains large stones which are used for reducing the cost of massive dams and walls. These rubble stones may vary from a few per cent to over one-half the volume. When concrete without much strength but light in weight is required, cinders may be used. This cinder concrete is porous and is used for light floor construction or fire-proofing.

Concrete Mixtures.— In the mixing of concrete, it is desirable to use as little cement as is consistent with the required strength, because the cement is much more expensive than the other ingredients. The proportioning of the ingredients is usually by volume and mixtures are generally designated by giving the amount of each ingredient in a fixed order, as 1 : 2: 5, the first figure indicating the amount of cement by volume, the second the amount of sand, and the third the amount of broken stone or gravel.

For ordinary machine foundations, retaining walls, bridge abutments, and piers exposed to the air, a 1 : 2½ : 5 concrete is satisfactory; and for ordinary foundations, heavy walls, etc., a lean mixture of 1 : 3 : 6 may be used. For reinforced floors, beams, columns, and arches, as well as for machine foundations which are subjected to vibration, a 1 : 2 : 4 concrete is generally used. This composition is also employed when concrete is used under water. For water tanks and similar structures subjected to considerable pressure and required to be water-tight, mixtures rich in cement and composed of either 1 : 1 : 2 or 1 : 1½: 3 concrete are used. Portland cement should preferably be used in concrete construction.

Sand, Gravel, and Stone for Concrete.— The sand used must be free from dust, loam, vegetable, or other organic matter; it should pass, when dry, through a screen with holes of ¼-inch mesh. The gravel should consist of clean pebbles free from foreign matter and should be of such coarseness that it will not pass through a screen of ¼-inch mesh. Gravel containing loam or clay should be washed by a hose before mixing. The broken stone should be of a hard and durable kind, such as granite or limestone. This stone should pass through a 2½-inch screen.

Amount of Water for Mixing Concrete.— The amount of water required to combine chemically with cement is about 16 per cent by weight, but in mixing concrete a greater amount than this must be used, because of losses and the difficulty of uniformly distributing the water. In hot weather more water is required than in cool weather because of the loss due to evaporation. The same applies when absorbent sand is used, or when the concrete is not rammed tightly. An excess of water is not desirable, because this excess will flow away and carry some of the cement with it. The water must be free from oils, acids, and impurities that would prevent a proper chemical combination with the cement. It is important to mix the ingredients thoroughly. Lime cement, sand and stone should be mixed while dry, preferably using a machine. Enough water should then be added to produce a mixture which will flow readily and fill different parts of the form.

Reinforced Concrete.— Concrete reinforced with steel is widely used, especially where the concrete must resist tensile as well as compressive stresses. This reinforcement may be in the form of round bars twisted square bars, corrugated bars, expanded metal, steel mesh, or wire fabric. The proportions for reinforced concrete structures are usually 1 : 2 : 4, or 1

Copyright 2004, Industrial Press, Inc., New York, NY

barrel of portland cement, 2 barrels of sand, and 4 barrels of broken stone or gravel. The lateral spacing between reinforcement bars should not be less than three times the bar diameter from center to center, with a clear space between the bars of at least one inch. The distance from the side of a beam to the center of the nearest bar should be not less than two diameters.

Strength of Concrete.— The strength varies greatly depending upon the quality and proportions of the ingredients and the care in mixing and depositing in the forms. The compressive strength of concrete which, after having been mixed and laid, has set 28 days, varies from 1000 to 3300 pounds per square inch, according to the mixture used. If made in the proportion 1 : 3 : 6, using soft limestone and sandstone a compressive strength of only 1000 pounds per square inch may be expected, whereas a mixture of 1 : 1 : 2, made with soft limestone and sandstone, will show a strength of 2200 pounds per square inch. A mixture of 1 : 3 : 6, made from granite or trap rock, will have a compressive strength of 1400 pounds per square inch, while a mixture of 1 : 1 : 2, made from granite or trap rock, will have a strength of 3300 pounds per square inch. Other mixtures will have values between those given. The richer in cement in proportion to sand, gravel, and stone, the stronger will be the concrete. The strongest concretes are also obtained by using granite or trap rock. A medium strength is obtained by using gravel, hard limestone, or hard sandstone, whereas the least strength is obtained by using soft limestone or sandstone. Concrete may also be mixed with cinders, but, in this case, very inferior strength is obtained; the richest mixtures will only give a strength of about 800 pounds per square inch.

Durability of Concrete in Sea Water.— Experiments have been made to determine the durability of different mixtures of concrete when exposed to sea water. It has been found that the mixtures that give the best results are those that are richest in cement. Mixtures of 1 : 1 : 2, for example, will give much better results than mixtures of 1 : 3 : 6. Also, very wet mixtures seem to give better results than those that are comparatively dry when deposited. It has also been found that, in order to insure the permanence of Portland cement concrete in sea water, the cement must contain as little lime and alumina as possible and must also be free from sulfates, and the proportion of sand and stones in the concrete must be such that the structure is practically non-porous. Natural cement should never be used for concrete exposed to sea water.

Waterproofing Concrete.— Several formulas for making concrete waterproof have been successfully used but some of them are too expensive for general application. One of the simplest, cheapest, and most effective is that developed by the U.S. Geological Survey. A heavy residual mineral oil of 0.93 specific gravity, mixed with Portland cement, makes it waterproof and does not weaken when the concrete consists of, say, cement, 1 part, sand, 3 parts, and oil, not more than 10 per cent, by weight, of the cement. Concrete mixed with oil requires about fifty per cent longer time to set hard, and the compressive strength is slightly decreased but not seriously. The bond or grip of oil concrete on steel is much decreased when plain bars are used, but formed bars, wire mesh, or expanded metal act as effectively in it as in ordinary concrete.

Resistance to Acids and Oils.— Concrete of a good quality, that has thoroughly hardened, resists the action of acids and mineral oils as well as other building materials, but vegetable oils containing fatty acids produce injurious effects by combining with the lime in the cement and causing disintegration of the concrete.

Lutes and Cements

Luting and cementing materials for various purposes in the laboratory and shops may be classified as follows: water- and steam-proof; oil-proof; acid-proof; proof to hydrocarbon gases; chlorine-proof; elastic; general purposes; marine glue; gaskets; machinists; leather (belting); crucible; iron; and stone.

Copyright 2004, Industrial Press, Inc., New York, NY

Water-proof Compositions.— The asphalt fluid coatings for reservoir wall, concrete foundations, brick, wood, etc., are often of use to engineers. Asphalt only partly dissolves in petroleum naphtha, but when heated in a steam-jacketed kettle and not thinned out too much, a mixture of the two may be obtained in which the part of the asphalt not dissolved is held in suspension. Asphalt is entirely soluble in benzol or toluol, which are about the cheapest solvents for all the constituents of asphalt. Tar and pitch are sometimes used in this connection, but tar contains water, light oils and free carbon, and does not wear as well as good refined asphalt; pitch also contains free carbon, which is sometimes objectionable when it is thinned out with a solvent. Asphalt alone is somewhat pervious to water, but it can be improved in this respect by adding about one-fourth its weight of paraffin; it is also well to add a little boiled linseed oil. For thicker compositions, where body is required, asbestos, stone powder, cement, etc., may be added as filters. Lutes of linseed oil thickened with clay, asbestos, red or white lead, etc., arc waterproof if made thick enough. These are much used for steam joints. Flaxseed meal made into a paste with water is often serviceable, the oil contained serving as a binder as the water evaporates.

Oil-proof Cements.— The well-known "hektograph composition" is the most useful lute for small leaks, etc. It consists of the following ingredients: Good glue or gelatin, 2 parts; glycerin, 1 part; water, 7 parts. This preparation is applied warm and stiffens quickly on cooling. Another very useful composition is a stiff paste of molasses and flour. Another preparation, impervious to oil vapors, is the "flaxseed poultice," mentioned in the preceding paragraph, which is proof to oil vapors. One of the strongest cements, and one which is really oil-proof, waterproof and acid-proof, is a stiff paste of glycerin and litharge. These form a chemical combination which sets in a few minutes. If a little water is added, it sets more slowly, which is often an advantage. This cement is mixed when required for use. A mixture of plaster-of-paris and water is useful, and it is sometimes advantageous to mix straw or hair with it. A solution of silicate of soda made into a stiff paste with carbonate of lime gets hard in six to eight hours.

Acid-proof Cements.— The asphalt compositions already mentioned, compositions of melted sulphur with fillers of stone powder, cement, sand, etc., may be used, and also the following, which withstands hydrochloric acid vapors: rosin, 1 part; sulphur, 1 part; fireclay, 2 parts. The lute composed of boiled linseed oil and fireclay acts well with most acid vapors. The composition of glycerin and litharge previously referred to is useful in this connection, especially when made up according to the following formula: Litharge, 80 pounds; red lead, 8 pounds; "flock" asbestos, 10 pounds. It should be fed into a mixer, a little at a time, with small quantities of boiled oil (about six quarts of oil being used). Sockets in 3-inch pipes carrying nitric acid, calked with this preparation, showed no leaks in nine months.

A particularly useful cement for withstanding acid vapors, which is tough and elastic, is composed of crude rubber, cut fine, 1 part; linseed oil, boiled, 4 parts; fireclay, 6 parts. The rubber is dissolved in carbon disulphide to the consistency of molasses and is then mixed with the oil. Other acid-proof cements are as follows: "Black putty" made by carefully mixing equal portions of china-clay, gas-tar and linseed oil. The china-clay must be well dried by placing it over a boiler or by other means. Barytes cement is composed of pure, finely ground sulfate of barium, and is made into a putty with a solution of silicate of soda. This sets very hard when moderately heated, and is then proof against acids. The gravity of the silicate of soda should be between 1.2 and 1.4, 24 degrees to 42 degrees Baume. If too thin, it does not hold; and when thicker than 1.4, it expands and breaks.

Gasket Compositions.— Almost any cementing substance may be used with rings of asbestos, etc., for gaskets, but some are especially adapted for the purpose. Asphalt, tar, petroleum residuum and soft or hard pitch are recommended. Silicate of soda is much used, and is sometimes advantageously mixed with casein, fine sand, clay, carbonate of lime, caustic lime, magnesia, oxides of heavy metals, such as lead, zinc, iron and powdered

Copyright 2004, Industrial Press, Inc., New York, NY

barytes. A few mixtures that might be selected are: Silicate of soda and asbestos; silicate of soda, asbestos and slaked lime; silicate of soda and fine sand; silicate of soda and fireclay.

Machinists Cements.— These are also known as red and white leads. The red lead is often diluted with an equal bulk of silica or other inert substance to make it less powdery. The best way to do this is to add rubber or gutta-percha to the oil as follows: Linseed oil, 6 parts, by weight; rubber or gutta-percha, 1 part by weight. The rubber or gutta-percha is dissolved in sufficient carbon disulphide to give it the consistency of molasses, mixed with the oil, and left exposed to the air for about twenty-four hours. The red lead is then mixed to a putty. Oxide of iron makes a less brittle cement than red lead.

Leather Cements.— a) Equal parts of good hide glue and American isinglass, softened in water for ten hours and then boiled with pure tannin until the whole mass is sticky. The surface of the joint should be roughened and the cement applied hot.

b) 1 pound of finely shredded gutta-percha digested over a water-bath with 10 pounds of benzol, until dissolved, and 12 pounds of linseed oil varnish stirred in.

c) 7 ½ pounds of finely shredded india-rubber is completely dissolved in 10 pounds of carbon disulphide by treating while hot; 1 pound of shellac and 1 pound of turpentine are added, and the hot solution heated until the two latter ingredients are also dissolved.

d) another leather cement is as follows: gutta-percha, 8 ounces; pitch, 1 ounce; shellac, 1 ounce; sweet oil, 1 ounce. These are melted together.

e) still another is as follows: fish glue is soaked in water twenty-four hours, allowed to drain for a like period, boiled well, and a previously melted mixture of 2 ounces of rosin and ½ ounce of boiled oil is added to every two pounds of glue solution.

Iron and Stone Cements.— When finely divided iron, such as filings or cast iron borings that have been powdered, is mixed with an oxidizing agent, such as manganese dioxide, or a substance electro-negative to iron, such as sulphur, in a good conducting solution like salt or sal-ammoniac, galvanic action sets in very rapidly and the iron swells, by forming iron oxide, and cements the mass together. It is best diluted with Portland cement, the proportions being as follows: iron filings, 40 parts; manganese dioxide or flowers of sulphur, 10 parts; sal-ammoniac, 1 part; Portland cement, 23 to 40 parts; water to form a paste. A hard stone-like composition is made as follows: zinc oxide, 2 parts; zinc chloride, 1 part; water to make a paste. Magnesium oxide and chloride may also be used in like proportions. When used in considerable quantity, this cement is mixed with powdered stone, for reasons of economy, the proportions depending upon the character of the work.

Cement Proof to Hydrocarbon Gases.— Compositions of plaster and cement, the former setting more quickly, are used; also compositions of casein, such as finely powdered casein, 2 parts; fresh slaked lime, 50 parts; fine sand, 50 parts. Water is added, when used, to form a thick mass. Various mixtures of silicate of soda are employed in which the thick silicate is absorbed in some inert material such as clay, sand or asbestos.

Cements Proof to Chlorine.— The best and only reliable compositions are a few made with Portland cement, and the following is used for electrolytic and chemical plants: powdered glass, 1 part; Portland cement, 1 part; silicate of soda, 1 part; a small amount of powdered slate. This lute withstands acids and alkalies, as well as the influences of chlorine. Linseed oil made into a paste with fireclay serves for a time.

Elastic Cements.— The various cements containing rubber are elastic, if the rubber is in a predominating amount; many containing boiled linseed oil and the hektograph composition already mentioned are quite elastic. The rubber and linseed-oil cement, given in *Acid-proof Cements* on page 2906, is very tough and useful for nearly all purposes except when oil vapors are to be confined. The most useful single rubber lute is probably the so-called Hart's india-rubber cement. Equal parts of raw linseed oil and pure masticated rubber are digested together by heating, and this mixture is made into a stiff putty with fine "paper stock" asbestos. It is more convenient, however, to dissolve the rubber first in carbon disulphide, and, after mixing the oil with it, to let the solvent evaporate spontaneously.

Copyright 2004, Industrial Press, Inc., New York, NY

General Purposes.— Plaster-of-paris, especially when mixed with straw, flush trimmings, hair, broken stone, etc., and used according to temperature strain and other conditions, is one of the most useful preparations for general purposes. A putty of flour and molasses is a good composition to keep in a works ready for quick application when needed. It serves, for a time, almost any purpose at moderate temperatures. Casein compositions have great strength. the white of an egg made into a paste with slaked lime is strong and efficient, but must be used promptly on account of its quick setting qualities.

Marine Glue.— This can be purchased almost as cheaply as made. It consists of crude rubber, 1 part; shellac, 2 parts; pitch, 3 parts. The rubber must first be dissolved in carbon disulphide or turpentine before mixing with the heated combination of the other two ingredients.

Acid-proof Lining.— A lining for protecting tanks from the influence of acids is made from a mixture consisting of 75 parts (by weight), of pitch; 9 parts plaster-of-paris; 9 parts ochre; 15 parts beeswax; and 3 parts litharge. The tanks are covered on the inside with a thick coat of this mixture.

Cements for Pipe Joints.— A strong cement which is oil-proof, waterproof, and acid-proof, consists of a stiff paste of glycerin and litharge. These form a chemical combination which sets in a few minutes. If a little water is added, it sets more slowly, which is often an advantage. This cement is mixed when required for use.

Mixture for Threaded Pipe Joints: A good material to apply to pipe threads before making up the joints, in order to obtain a tight joint that will resist the action of gases or liquids, is made of red lead mixed with pure boiled linseed oil. This mixture has been widely used and is very satisfactory. It should have a heavy fluid-like consistency, and if applied to a clean, well-cut thread will give an excellent joint.

Shellac for Pipe Connections: Shellac has proved to be a very satisfactory substitute for lead in sealing air and gas pipe connections. It is applied with a brush to the joints and hardens very rapidly, and being brittle, the pipes can be readily disconnected.

Graphic, Litharge, Chalk Cement: A good cement for use in making steam pipe joints is made in the following manner: Grind and wash in clean cold water 15 parts of chalk and 50 parts of graphite; mix the two together thoroughly and allow to dry. When dry regrind to a fine powder, to which add 20 parts of ground litharge and mix to a stiff paste with 15 parts of boiled linseed oil. The preparation may be set aside for future use, as it will remain plastic for a long time if placed in a cool place. It is applied to the joint packing as any ordinary cement.

White and Red Lead Mixture: Mix in ordinary white lead, enough powdered red lead to make a paste the consistency of putty. Spread this mixture on the joint, and when it hardens, the joint will be water tight. This mixture was used on stand-pipe flanges after testing all kinds of rubber gaskets without success. The mixture hardened and made a tight joint, never leaking afterward.

Adhesives

Adhesives Bonding.— By strict definition, an adhesive is any substance that fastens or bonds materials to be joined (adherends) by means of surface attachment. However, besides bonding a joint, an adhesive may serve as a seal against attack by or passage of foreign materials. When an adhesive performs both bonding and sealing functions, it is usually called an adhesive sealant.

Where the design of an assembly permits, bonding with adhesives can replace bolting, welding, and riveting. When considering other fastening methods for thin cross-sections, the joint loads might be of such an unacceptable concentration that adhesives bonding may provide the only viable alternative. Properly designed adhesive joints can minimize or eliminate irregularities and breaks in the contour of an assembly. Adhesives can also serve

Copyright 2004, Industrial Press, Inc., New York, NY

as dielectric insulation. An adhesive with dielectric properties can act as a barrier against galvanic corrosion when two dissimilar metals such as aluminum and magnesium are joined together. Conversely, adhesive products are available which also conduct electricity.

An adhesive can be classified as structural or non-structural. Agreement is not universal on the exact separation between both classifications. But, in a general way, an adhesive can be considered structural when it is capable of supporting heavy loads; non-structural when it cannot. Most adhesives are found in liquid, paste, or granular form, though film and fabric-backed tape varieties are available. Adhesive formulations are applied by brush, roller, trowel, or spatula. If application surfaces are particularly large or if high rates of production are required, power-fed flow guns, brushes, or sprays can be used.

The hot-melt adhesives are relatively new to the assembly field. In general, they permit fastening speeds that are much greater than water- or solvent-based adhesives. Supplied in solid form, the hot-melts liquefy when heated. After application, they cool quickly, solidifying and forming the adhesive bond. They have been used successfully for a wide variety of adherends, and can greatly reduce the need for clamping and lengths of time for curing storage.

If an adhesive bonding agent is to give the best results, time restrictions recommended by the manufacturer, such as shelf life and working life must be observed. The shelf life is considered as the period of time an adhesive can be stored after its manufacture. Working or "pot" life is the span of time between the mixing or making ready of an adhesive, on the job, and when it is no longer usable.

The actual performance of an adhesive-bonded joint depends on a wide range of factors, many of them quite complex. They include: the size and nature of the applied loads; environmental conditions such as moisture or contact with other fluids or vapors; the nature of prior surface treatment of adherends; temperatures, pressures and curing times in the bonding process.

A great number of adhesives, under various brand names, may be available for a particular bonding task. However, there can be substantial differences in the cost of purchase and difficulties in application. Therefore, it is always best to check with manufacturers' information before making a proper choice. Also, testing under conditions approximating those required of the assembly in service will help assure that joints meet expected performance.

Though not meant to be all-inclusive, the information which follows correlates classes of adherends and some successful adhesive compositions from the many that can be readily purchased.

Bonding Metal: Epoxy resin adhesives perform well in bonding metallic adherends. One type of epoxy formulation is a two-part adhesive which can be applied at room temperature. It takes, however, seven days at room temperature for full curing, achieving shear strengths as high as 2500 psi (17.2 MPa). Curing times for this adhesive can be greatly accelerated by elevating the bonding temperature. For example, curing takes only one hour at 160°F (71°C).

A structural adhesive-filler is available for metals which is composed of aluminum powder and epoxy resin. It is made ready by adding a catalyst to the base components, and can be used to repair structural defects. At a temperature of 140°F (60°C) it cures in approximately one hour. Depending on service temperatures and design of the joint, this adhesive-filler is capable of withstanding flexural stresses above 10,000 psi (69 MPa), tension above 5,000 psi (34 MPa), and compression over 30,000 psi (207 MPa).

Many non-structural adhesives for metal-to-metal bonding are also suitable for fastening combinations of types of materials. Polysulfide, neoprene, or rubber-based adhesives are used to bond metal foils. Ethylene cellulose cements, available in a selection of colors, are used to plug machined recesses in metal surfaces, such as with screw insets. They harden within 24 hours. Other, stronger adhesive fillers are available for the non-structural patch-

Copyright 2004, Industrial Press, Inc., New York, NY

ing of defects in metallic parts. One variety, used for iron and steel castings, is a cement that combines powdered iron with water-activated binding agents. The consistency of the prepared mix is such that it can be applied with a trowel and sets within 24 hours at room temperature. The filler comes in types that can be applied to both dry and wet castings, and is able to resist the quick changes of temperature during quenching operations.

Polyester cement can replace lead and other fillers for dents and openings in sheet metal. One type, used successfully on truck and auto bodies, is a two-part cement consisting of a paste resin that can be combined with a paste or powder extender. It is brushed or trowelled on, and is ready for finishing operations in one hour.

Adhesives can be used for both structural and non-structural applications which combine metals with non-metals. Structural polyester-based adhesives can bond reinforced plastic laminates to metal surfaces. One type has produced joints, between glass reinforced epoxy and stainless steel, that have tensile strengths of over 3000 psi (21 MPa). Elevated temperature service is not recommended for this adhesive. However, it is easily brushed on and bonds under slight pressure at room temperature, requiring several days for curing. The curing process accelerates when heat is added in a controlled environment, but there results a moderate reduction in tensile strength.

Low-density epoxy adhesives are successful in structurally adhering light plastics, such as polyurethane foam, to various metals. Applied by brush or spatula, the bonds cure within 24 hours at room temperatures

Metals can be bonded structurally to wood with a liquid adhesive made up of neoprene and synthetic resin. For the best surface coverage, the adhesive should be applied in a minimum of two coats. The joints formed are capable of reaching shear stresses of 125 psi, and can gain an additional 25 percent in shear strength with the passage of time. This adhesive also serves as a strong, general purpose bonding agent for other adherend combinations, including fabrics and ceramics.

For bonding strengths in shear over 500 psi (3.4 MPa) and at service temperatures slightly above 160°F (71°C), one- and two-part powder and jelly forms of metal-to-wood types are available.

Besides epoxy formulations, there are general purpose rubber, cellulose, and vinyl adhesives suitable for the non-structural bonding of metals to other adherends, which include glass and leather. These adhesives, however, are not limited only to applications in which one of the adherends is metal. The vinyl and cellulose types have similar bonding properties, however the vinyls are less flammable and are weaker in resistance to moisture than the comparable cellulosics. Rubber-based adhesives, in turn, have good resistance to moisture and lubricating oil. They can form non-structural bonds between metal and rubber.

One manufacturer has produced an acrylic-based adhesive that is highly suitable for rapidly bonding metal with other adherends at room temperature. For some applications it can be used as a structural adhesive, in the absence of moisture and high temperature. It cures within 24 hours and can be purchased in small bottles with dispenser tips.

A two-part epoxy adhesive is commercially available for non-structural bonding of joints or for patchwork in which one of the adherends is metal. Supplied in small tubes, it performs well even when temperatures vary between –50° to 200°F (–46° to 93°C). However, it is not recommended for use on assemblies that may experience heavy vibrations.

Bonding Plastic: Depending on the type of resin compound used in its manufacture, a plastic material can be classified as one of two types: a thermoplastic or a thermoset.

Thermoplastic materials have the capability of being repeatedly softened by heat and hardened by cooling. Common thermoplastics are nylon, polyethylene, acetal, polycarbonate, polyvinyl chloride, cellulose nitrate and cellulose acetate. Also, solvents can easily dissolve a number of thermoplastic materials. Because of these physical and chemical characteristics of thermoplastics, heat or solvent welding may in many instances offer a better bonding alternative than adhesives.

Copyright 2004, Industrial Press, Inc., New York, NY

Thermoplastics commonly require temperatures between 200° and 400°F (93° and 204°C) for successful heat welding. However, if the maximum temperature limit for a particular thermoplastic formulation is exceeded, the plastic material will experience permanent damage. Heat can be applied directly to thermoplastic adherends, as in hot-air welding. More sophisticated joining techniques employ processes in which the heat generated for fusing thermoplastics is activated by electrical, sonic, or frictional means.

In the solvent welding of thermoplastics, solvent is applied to the adherend surfaces with the bond forming as the solvent dries. Some common solvents for thermoplastics are: a solution of phenol and formic acid for nylon; methylene chloride for polycarbonate; and methyl alcohol for the cellulosics.

Many adhesive bonding agents for thermoplastics are "dope" cements. Dope or solvent cements combine solvent with a base material that is the same thermoplastic as the adherend. One type is used successfully on polyvinyl chloride water (PVC) pipe. This liquid adhesive, with a polyvinyl chloride base, is applied in at least two coats. The pipe joint, however, must be closed in less than a minute after the adhesive is applied. Resulting joint bonds can resist hydrostatic pressures over 400 psi (28 MPa), for limited periods, and also have good resistance to impact.

Previously mentioned general purpose adhesives, such as the cellulosics, vinyls, rubber cements, and epoxies are also used successfully on thermoplastics.

Thermoset plastics lack the fusibility and solubility of the thermoplastics and are usually joined by adhesive bonding. The phenolics, epoxies, and alkyds are common thermoset plastics. Epoxy-based adhesives can join most thermoset materials, as can neoprene, nitrile rubber, and polyester-based cements. Again, these adhesives are of a general purpose nature, and can bond both thermoplastics and thermosets to other materials which include ceramics, fabric, wood, and metal.

Bonding Rubber: Adhesives are available commercially which can bond natural, butyl, nitrile, neoprene, and silicone rubbers. Natural and synthetic rubber cements will provide flexible joints; some types resist lubricating and other oils. Certain general purpose adhesives, such as the acrylics or epoxies, can bond rubber to almost anything else, though joints will be rigid. Depending on the choice of adhesive as well as adherend types, the bonds can carry loadings that vary from weak non-structural to mild structural in description. One type of natural rubber with a benzene-naphtha solvent can resist shear stresses to 1252.5 psi (83 kPa).

Bonding Wood: Animal glues, available in liquid and powder form, are familiar types of wood-to-wood adhesives, commonly used in building laminated assemblies. Both forms, however, require heavy bonding pressures for joints capable of resisting substantial loadings. Also, animal glues are very sensitive to variations in temperature and moisture.

Casein types of adhesive offer moderate resistance to moisture and high temperature, but also require heavy bonding pressures, as much as 200 psi, for strong joints. Urea resin adhesives also offer moderate weather resistance, but are good for bonding wood to laminated plastics as well as to other wooden adherends. For outdoor service, under severe weather conditions, phenol-resorcinol adhesives are recommended.

Vinyl-acetate emulsions are excellent for bonding wood to other materials that have especially non-porous surfaces, such as metal and certain plastic laminates. These adhesives, too, tend to be sensitive to temperature and moisture, but are recommended for wooden pattern making.

Rubber, acrylic, and epoxy general-purpose adhesives also perform well with wood and other adherend combinations. Specific rubber-based formulations resist attack by oil.

Fabric and Paper Bonding: The general purpose adhesives, which include the rubber cements and epoxies previously mentioned, are capable of bonding fabrics together and fabrics with other adherend materials. A butadiene-acrylonitrile adhesive, suitable also for fastening metals, glass, plastic, and rubber, forms joints in fabric that are highly resistant to

Copyright 2004, Industrial Press, Inc., New York, NY

oil and which maintain bonding strength at temperatures up to 160°F (70°C). This adhesive, however, requires a long curing period, the first few hours of which are at an elevated temperature.

Commonly, when coated fabric materials must be joined, the base material forming the suitable adhesive is of the same type as that protecting the fabric. For example, a polyvinyl chloride-based adhesive is acceptable for vinyl-coated fabrics; and neoprene-based cements for neoprene-coated materials.

Rubber cements, gum mucilages, wheat pastes, and wood rosin adhesive can join paper as well as fabric assemblies. Solvent-based rosins can be used on glass and wood also. Rosin adhesives can also be treated as hot-melt adhesives for rapid curing. Generally, the rosins are water resistant, but usually weak against attack by organic solvents.

Sealants

Sealants.— Normally, the primary role of a sealant composition is the prevention of leakage or access by dust, fluid, and other materials in assembly structures. Nevertheless, many products are currently being manufactured that are capable of performing additional functions. For example, though a sealant is normally not an adhesive, there exists a family of adhesive sealants which in varying degrees can bond structural joints as well. Besides resisting chemical attack, some sealant surface coatings can protect against physical wear. Sealants can also dampen noise and vibration, or restrict the flow of heat or electricity. Many sealant products are available in decorative tints that can help improve the appearance of an assembly.

Most sealants tend to be limited by the operating temperatures and pressures under which they are capable of sustained performance. Also, before a suitable choice of sealant formulation is made, other properties have to be examined; these include: strength of the sealant; its degree of rigidity; ease of repair; curing characteristics; and even shelf and working life.

Dozens of manufacturers supply hundreds of sealant compounds, a number of which may fill the requirements for a particular application. The following information, however, lists common uses for sealants, along with types of compositions that have been employed successfully within each category.

Gasket Materials: Silicone rubber gasket compositions are supplied in tubes in a semiliquid form ready for manual application. They can also be obtained in larger containers for power-fed applications. Suppliers offer a silicone rubber-based composition that can replace preformed paper, cork, and rubber gaskets for many manufacturing operations. This composition has performed successfully in sealing water pumps, engine filter housings, and oil pans. It can also seal gear housings and other joints that require a flexible gasket material that besides resisting shock can sustain large temperature changes. Silicone rubber compositions can withstand temperatures that vary from –100°F to 450°F (–73°C to 232°C).

Gasket tapes, ropes, and strips can also be readily purchased to fit many assembly applications. One type of sealant tape combines a pressure-sensitive adhesive with a strip of silicone-rubber sponge. This tape has good cushioning properties for vibration damping and can stick to metal, plastic, ceramic, and glass combinations.

TFE-based gasketing strips are also available. This non-stick gasketing material can perform at pressures up to 200 psi (1.4 MPa) and temperatures to 250°F (120°C). Because of the TFE base, the strip does not adhere to or gum joint surfaces.

Sealing Pipe Joints: Phenolic-based sealants can seal threaded joints on high-pressure steam lines. One type, that is available in liquid or paste form, resists pressure up to 1200 psi (8.3 MPa) and temperatures to 950°F (510°C). This compound is brushed on and the joint closed and tightened to a torque of 135 in.-lb. (15.3 N m). The connection is then subjected to a 24-hour cure with superheated steam.

Copyright 2004, Industrial Press, Inc., New York, NY

The joining and sealing of plastic pipe is covered under the previous adhesives bonding section.

Sulfur-based compounds, though lacking the durability of caulking lead, can be used on bell and spigot sewer pipe. Available in a formulation that can resist temperatures up to 200°F (93°C), one sulfur-based sealant is applied as a hot-melt and allowed to flow into the bell and spigot connection. It quickly solidifies at room temperature, and can develop a joint tensile strength over 300 psi (2.1 MPa).

There are asphalt, coal-tar and plastic-based compositions that can be used on both cast-iron and ceramic bell and spigot pipe. Portland cement mortars also seal ceramic piping.

Copyright 2004, Industrial Press, Inc., New York, NY

SURFACE TREATMENTS FOR METALS

Coloring Metals

General Requirements in the Coloring of Metal Surfaces.— Copper is more susceptible to coloring processes and materials than any of the other metals, and hence the alloys containing large percentages of copper are readily given various shades of yellow, brown, red, blue, purple, and black. Alloys with smaller percentages of copper (or none at all) can be given various colors, but not as easily as if copper were the principal ingredient, and the higher the copper content, the more readily can the alloy be colored. The shades, and even the colors, can be altered by varying the density of the solution, its temperature and the length of time the object is immersed. They can also be altered by finishing the work in different ways. If a cotton buff is used, one shade will be produced; a scratch brush will produce another, etc. Thus to color work the same shade as that of a former lot, all the data in connection with these operations must be preserved so they can be repeated with exactness.

Cleaning Metals for Coloring.— Metal surfaces to be colored chemically must first be thoroughly cleaned. To remove grease from small parts, dip in benzine, ether or some other solvent for the grease. Boil large pieces in a solution of one part caustic soda and ten parts water. For zinc, tin or britannia metal, do not use caustic soda, but a bath composed of one part carbonate of soda or potash and ten parts water. After boiling, wash in clean water. Do not touch the clean surfaces with the fingers, but handle the objects by the use of tongs or wires.

Pickling Solutions or Dips for Coloring.— The grease removal should be followed by chemical cleansing, which principally serves the purpose of removing the greenish or brownish films which form on copper, brass, bronze, etc. The composition of the bath or mixture for pickling varies for different metals. For copper and its alloys, a mixture of 100 parts concentrated sulphuric acid (66 degrees Baume and 75 parts nitric acid (40 degrees Baume is sometimes used. If the metal is to be given a luster instead of a mat or dull finish, add about 1 part common salt to 100 parts of the pickling solution, by weight. A better dip for a mat surface consists of 90 parts nitric acid (36 degrees Baume 45 parts concentrated sulphuric acid, 1 part salt, and from 1 to 5 parts of sulphate of zinc, by weight. The composition of copper-zinc alloys will produce different color tones in the same dip and will affect the results of chemical coloring. After pickling, washing in water is necessary.

Another good method of removing these films is to soak the work in a pickle composed of spent aquafortis until a black scale is formed, and then dip it for a few minutes into a solution of 64 parts water, 64 parts commercial sulphuric acid, 32 parts aquafortis, and 1 part hydrochloric acid. After that the work should be thoroughly rinsed several times with distilled water.

Coloring Brass.— Polished brass pieces can be given various shades from golden yellow to orange by immersing them for a certain length of time in a solution composed of 5 parts, by weight, of caustic soda, 50 parts water and 10 parts copper carbonate. When the desired shade is reached, the work must be well washed with water and dried in sawdust. Golden yellow may be produced as follows: Dissolve 100 grains lead acetate in 1 pint of water and add a solution of sodium hydrate until the precipitate which first forms is re-dissolved; then add 300 grains red potassium ferro-cyanide. With the solution at ordinary temperatures, the work will assume a golden yellow, but heating the solution darkens the color, until at 125 degrees F. it has changed to a brown.

To Produce a Rich Gold Color.— Brass can be given a rich gold color by boiling it in a solution composed of 2 parts, by weight, of saltpeter, 1 part common salt, 1 part alum, 24 parts water and 1 part hydrochloric acid. Another method is to apply a mixture of 3 parts alum, 6 parts saltpeter, 3 parts sulphate of zinc, and 3 parts common salt. After applying

Copyright 2004, Industrial Press, Inc., New York, NY

this mixture the work is heated over a hot plate until it becomes black, after which it is washed with water, rubbed with vinegar, and again washed and dried.

White Colors or Coatings.— The white color or coating that is given to such brass articles as pins, hooks and eyes, buttons, etc., can be produced by dipping them in a solution made as follows: Dissolve 2 ounces fine-grain silver in nitric acid, then add 1 gallon distilled water, and put this into a strong solution of sodium chloride. The silver will precipitate in the form of chloride, and must be washed until all traces of the acid are removed. Testing the last rinse water with litmus paper will show when the acid has disappeared; then mix this chloride of silver with an equal amount of potassium bitartrate (cream of tartar), and add enough water to give it the consistency of cream. The work is then immersed in this solution and stirred around until properly coated, after which it is rinsed in hot water and dried in sawdust.

Silvering.— A solution for silvering, that is applicable to such work as gage or clock dials, etc., can be made by grinding together in a mortar 1 ounce of very dry chloride of silver, 2 ounces cream of tartar, and 3 ounces common salt, then add enough water to obtain the desired consistency and rub it onto the work with a soft cloth. This will give brass or bronze surfaces a dead-white thin silver coating, but it will tarnish and wear if not given a coat of lacquer. The ordinary silver lacquers that can be applied cold are the best. Before adding the water, the mixture, as it leaves the mortar, can be kept a long time if put in very dark colored bottles, but if left in the light it will decompose.

To Give Brass a Green Tint.— One solution that will produce the Verde antique, or rust green, is composed of 3 ounces crystallized chloride of iron, 1 pound ammonium chloride, 8 ounces verdigris, 10 ounces common salt, 4 ounces potassium bitartrate and 1 gallon of water. If the objects to be colored are large, the solution can be put on with a brush. Several applications may be required to give the desired depth of color. Small work should be immersed and the length of time it remains in the solution will govern the intensity of the color. After immersion, stippling the surface with a soft round brush, dampened with the solution, will give it the variegated appearance of the naturally aged brass or bronze.

Blackening Brass.— There are many different processes and solutions for blackening brass. Trioxide of arsenic, white arsenic or arsenious acid are different names for the chemical that is most commonly used. It is the cheapest chemical for producing black on brass, copper, nickel, German silver, etc., but has a tendency to fade, especially if not properly applied, although a coat of lacquer will preserve it a long time. A good black can be produced by immersing the work in a solution composed of 2 ounces white arsenic, 5 ounces cyanide of potassium, and 1 gallon of water. This should be boiled in an enamel or agate vessel, and used hot. Another cheap solution is composed of 8 ounces of sugar of lead, 8 ounces hyposulphite of soda and 1 gallon of water. This must also be used hot and the work afterwards lacquered to prevent fading. When immersed, the brass first turns yellow, then blue and then black, the latter being a deposit of sulphide of lead.

Preservation of Color.— After a part has been given the desired color, it is usually washed in water and then dried with clean sawdust. The colored surfaces of alloys are commonly protected and preserved by coating with a colorless lacquer, such as japan lacquer. Small parts are coated by dipping, and large ones by rubbing the lacquer on. The lacquer is hard after drying, and insoluble in most fluids; hence, it can be washed without injury.

Niter Process of Bluing Steel.— The niter process of bluing iron and steel is as follows: The niter or nitrate of potash (often called saltpeter) is melted in an iron pot and heated to about 600 degrees F. The parts to be blued are cleaned and polished and then immersed in the molten niter until a uniform color of the desired shade has been obtained. This requires only a few seconds. The articles are then removed and allowed to cool, after which the adhering niter is washed off in water. Parts which will not warp may be immersed immediately after removing from the niter bath. After cleaning, dry in sawdust, and then apply some suitable oil, such as linseed, to prevent rusting. To secure uniform coloring, a pyrom-

Copyright 2004, Industrial Press, Inc., New York, NY

eter should be used to gage the temperature of the niter, because a higher heat than 600 degrees F. will produce a dark color, whereas a lower heat will give a lighter shade.

Bluing Steel by Heat-treatment.— Polished steel parts can be given a blue color by heating in hot sand, wood ashes, or pulverized charcoal. Place the substance in an iron receptacle and stir constantly, while heating, in order to heat uniformly. Heat just hot enough to char a pine stick. The parts to be blued must be absolutely free from grease. They are placed in the heated substance until the desired color is obtained. Further coloring is then checked by immersing in oil. Small parts are sometimes heated by a Bunsen burner or by laying upon a heated plate. For a light blue color, heat in sand or wood ashes, and for a dark blue, use pulverized charcoal. The quality of the color depends largely upon the fineness of the finish. Still another method of coloring by heat is to immerse the parts in a molten bath of potassium nitrate and sodium nitrate. The coloring is then checked by plunging the work into boiling water.

Blue-black Finish.— To obtain a blue-black finish on small steel parts, use a mixture of 16 parts, by weight, of saltpeter and 2 parts of black oxide of manganese. This mixture is heated to a temperature of 750 degrees F. and the objects are immersed in it. The oxide of manganese is deposited on the work and must, therefore, be frequently replenished in the mixture.

Black Finish.— To obtain a black rust-protecting finish on hardened parts, temper, after hardening, in "heavy" cylinder oil; then immediately place the part with the oil on it in an oven having a temperature of from 300 to 350 degrees F. Remove the work in from to 8 minutes, when the black finish is baked onto it.

Gun Metal Finish.— Several different chemical solutions have been used successfully for giving steel a gun metal finish or black color. Among these are the following:

1) Bismuth chloride, one part; copper chloride, one part; mercury chloride, two parts; hydrochloric acid, six parts; and water, fifty parts.

2) Ferric chloride, one part; alcohol, eight parts; and water, eight parts.

3) Copper sulphate, two parts; hydrochloric acid, three parts; nitric acid, seven parts; and perchloride of iron, eighty-eight parts.

Other solutions have been prepared from nitric ether, nitric acid, copper sulphate, iron chloride, alcohol and water and from nitric acid, copper sulphate, iron chloride and water. The method of applying these and finishing the work is practically the same in all cases.

The surface is given a very thin coating with a soft brush or sponge that has been well squeezed, and is then allowed to dry. The work is then put in a closed retort to which steam is admitted and maintained at a temperature of about 100 degrees F., until the parts are covered with a slight rust. They are then boiled in clean water for about fifteen minutes and allowed to dry. A coating of black oxide will cover the surface, and this is scratch brushed. After brushing, the surface will show a grayish black. By repeating the sponging, steaming and brushing operations several times, a shiny black lasting surface will be obtained. For the best finishes, these operations are repeated as many as eight times.

Another process employs a solution of mercury chloride and ammonium chloride which is applied to the work three times and dried each time. A solution of copper sulphate, ferric chloride, nitric acid, alcohol and water is then applied three times and dried as before. A third solution of ferrous chloride, nitric acid and water is applied three times, and the work is boiled in clean water and dried each time. Finally, a solution of potassium chloride is applied and the work boiled and dried three times. The work is then scratch brushed and given a thin coating of oil. Ordnance for the French Government is treated in this way. The above methods are applicable to hardened and tempered steels, as a temperature of 100 degrees F. does not affect the hardness of the steel. For steels that will stand 600 degrees temperature without losing the desired hardness, better and much cheaper methods have been devised.

Copyright 2004, Industrial Press, Inc., New York, NY

The American Gas Furnace Co. has developed a process employing a furnace with a revolving retort. The work is charged in this, togther with well-burnt bone. A chemical solution that gasifies when it enters the furnace is then injected into this retort while the work is heated to the proper temperature. This solution has been named "Carbonia." The color does not form a coating on the outside, as with the other processes, but a thin layer of the metal itself is turned to the proper color. By varying the temperature of the furnace, the time the work is in it, and the chemical, different colors can be produced from light straw to brown, blue, purple and black, or gun metal finish. Rough or sand-blasted surfaces will have a frosted appearance, while smooth polished surfaces will have a shiny brilliant appearance.

Browning Iron and Steel.— A good brown color can be obtained as follows: Coat the steel with ammonia and dry it in a warm place; then coat it with muriatic or nitric acid and dry it in a warm place; then place the steel in a solution of tannin or gallic acid and again dry it. The color can be deepened by placing the work near the fire, but it should be withdrawn the minute the desired shade is reached or it will turn black.

To Produce a Bronze Color.— A bronze-like color can be produced by exposing iron or steel parts to the vapors of heated aquaregia, dipping them in melted petroleum jelly, and then heating them until it begins to decompose, when it is wiped off with a soft cloth. Another method of producing this bronze-brown color is to slightly heat the work, evenly cover the surfaces with a paste of antimony chloride (known as "bronzing salt"), and let the object stand until the desired color is obtained. The paste can be made more active by adding a little nitric acid.

To Produce a Gray Color.— A gray color on steel can be obtained by immersing the work in a heated solution of ten grains of antimony chloride, ten grains of gallic acid, 400 grains of ferric chloride and five fluid ounces of water. The first color to appear is pale blue, and this passes through the darker blues to the purple, and, finally, to the gray. If immersed long enough, the metal will assume the gray color, but any of the intermediate colors may be produced. When used cold, this is also one of the bronzing solutions.

Mottled Coloring.— Mottled colors on steel can be produced by heating the objects to a good cherry-red for several minutes in cyanide of potassium, then pouring the cyanide off, and placing the receptacle containing the work back on the tire for five minutes. The contents are then quickly dumped into clean water. To heighten the colors, boil afterward in water and oil.

Coppering Solution.— A coppering solution for coating finished surfaces in order that lay-out lines may be more easily seen, is composed of the following ingredients: To 4 ounces of distilled water (or rain water) add all the copper sulphate (blue vitriol) it will dissolve; then add 10 drops of sulphuric acid. Test by applying to a piece of steel, and, if necessary, add four or five drops of acid. The surface to be coppered should be polished and free from grease. Apply the solution with clean waste, and, if a bright copper coating is not obtained, add a few more drops of the solution; then scour the surface with fine emery cloth, and apply rapidly a small quantity of fresh solution.

White Coatings for Laying Out Lines.— Powdered chalk or whiting mixed with alcohol is commonly used for coating finished metal surfaces preparatory to laying out lines for machining operations. Alcohol is preferable to water, because it will dry quicker and does not tend to rust the surface. This mixture can be applied with a brush and is more convenient than a coppering solution for general work. For many purposes, the surface can be coated satisfactorily by simply rubbing dry chalk over it.

To Produce Gray Colors.— A solution of 1 ounce of arsenic chloride in 1 pint of water will produce a gray color on brass, but if the work is left in this solution too long it will become black. The brass objects are left in the bath until they have assumed the correct shade, and are then washed in clean warm water, dried in sawdust and finally in warm air.

Copyright 2004, Industrial Press, Inc., New York, NY

Blue and Violet Shades.— To give brass a blue color, dissolve 1 ounce of antimony chloride in 20 ounces of water, and add 3 ounces hydrochloric acid; then warm the work and immerse it in this solution, until the desired blue is obtained After that wash in clean water and dry in sawdust. A permanent and beautiful blue-black can be obtained by using just enough water to dissolve 2 ounces copper sulphate and then adding enough ammonia to neutralize and make it slightly alkaline. The work must be heated before immersion.

To Give Brass a Green Tint.— One solution that will produce the Verde antique, or rust green, is composed of 3 ounces crystallized chloride of iron, 1 pound ammonium chloride, 8 ounces verdigris, 10 ounces common salt, 4 ounces potassium bitartrate and 1 gallon of water. If the objects to be colored are large, the solution can be put on with a brush. Several applications may be required to give the desired depth of color. Small work should be immersed and the length of time it remains in the solution will govern the intensity of the color. After immersion, stippling the surface with a soft round brush, dampened with the solution, will give it the variegated appearance of the naturally aged brass or bronze.

Etching And Etching Fluids

Etching Fluids for Different Metals.— A common method of etching names or simple designs upon steel is to apply a thin, even coating of beeswax or some similar substance which will resist acid; then mark the required lines or letters in the wax with a sharp-pointed scriber, thus exposing the steel (where the wax has been removed by the scriber point) to the action of an acid, which is finally applied. To apply a very thin coating of beeswax, place the latter in a silk cloth, warm the piece to be etched, and rub the pad over it. Regular coach varnish is also used instead of wax, as a "resist."

An etching fluid ordinarily used for carbon steel consists of nitric acid, 1 part; water, 4 parts. It may be necessary to vary the amount of water, as the exact proportion depends upon the carbon in the steel and whether it is hard or soft. For hard steel, use nitric acid, 2 parts; acetic acid, 1 part. For high-speed steel, nickel or brass, use nitro-hydrochloric acid (nitric, 1 part; hydrochloric, 4 parts). For high-speed steel it is sometimes better to add a little more nitric acid. For etching bronze, use nitric acid, 100 parts; muriatic acid, parts. For brass, nitric acid, 16 parts; water, 160 parts; dissolve 6 parts potassium chlorate in 100 parts of water; then mix the two solutions and apply.

A fluid which may be used either for producing a frosted effect or for deep etching (depending upon the time it is allowed to act) is composed of 1 ounce sulphate of copper (blue vitriol); ¼ ounce alum; ½ teaspoonful of salt; 1 gill of vinegar, and 20 drops of nitric acid. For aluminum, use a solution composed of alcohol, 4 ounces; acetic acid, 6 ounces; antimony chloride, 4 ounces; water, 40 ounces.

The National Twist Drill Co. employs the following method for etching on cutters and other tools: The steel is brushed with asphaltum varnish which is allowed to stand until it thickens and hardens to the right degree; then the desired inscription is pressed through the asphaltum with a rubber stamp and the etching fluid (nitrohydrochloric acid or *aquaregia*) is applied with a medicine dropper. Practice and experience are required to judge just when the varnish has dried to the right consistency. A similar method, which has been successfully used for etching names on cutlery, is to coat the surface with gum guaiacum varnish. A rubber stamp having the name or design is then coated with a thin layer of potash solution. When this stamp is applied to the work, the varnish is "cut" by the potash wherever the coated stamp comes into contact with it; the surface is then brushed lightly with water to remove the loosened varnish and expose the lettering or design, which is then etched by applying dilute nitric acid. The rubber-stamp method is a very cheap and rapid process. One method of applying the potash is to press the stamp against a pad soaked with the solution. The action of etching fluids on steels varies somewhat according to the composition, high-carbon and alloy steels being acted upon more slowly than low-carbon steel or wrought iron.

Copyright 2004, Industrial Press, Inc., New York, NY

Etching Brass Nameplates.— Etched brass nameplates having a black background are now often used in preference to cast plates, as they are less expensive. The etched plate is produced by coating a flat and polished sheet of brass with a thin layer of bichromated albumen, and exposing it to the light for a few minutes under a glass negative upon which are a number of the desired nameplate designs. (In order to prepare the bichromated albumen, mix together 10 parts of the white of egg with 30 parts of water. A second mixture is then made consisting of 2 parts of potassium bichromate and 58 parts of water. The first mixture composed of the white of egg and water, and the second mixture containing potassium bichromate and water, are next mixed together in a dark room. The bichromated albumen thus obtained should be kept and used in the dark.) When the brass plate is developed, this removes the albumen not exposed to the light (or that which has been protected by the black portions of the negative), and leaves the brass free to be etched. The etching solution will not attack the parts protected by the albumen or "resist."

The etching is done by a solution of perchlorate of iron, or by making the plate the anode in an acid-copper solution. When the plate has been etched to the required depth, it is washed. If the etched surface is tarnished, as it usually is after drying, a solution made of 2 parts of water an 1 part of muriatic acid should be spread over the surface to remove the stains and leave it clean and uniform. The plate should then be rinsed, but not dried. Then, without removing the resist, it is treated in some manner to produce a black background. When this has been done, the resist is removed and the sheet is cut up to form the individual nameplates, which are then lacquered.

Producing a Black Background.— The use of a black nickel deposit is the best method of producing a black background on etched brass name-plates. This solution does not affect any of the various kinds of resist used, and a large number of plates can be treated in a tank at one time. The black nickel bath is composed of water, 1 gallon; double-nickel salts, 8 ounces; ammonium sulpho-cyanate, 2 ounces; zinc sulphate, 1 ounce. This solution is used cold, with a weak current of about 1 volt. With a greater voltage, the deposit will be streaked and gray. As soon as the deposit is black, remove the plates, rinse, dry and cut to the desired size; then lacquer immediately in order to prevent the brownish discoloration which will otherwise form on the surface of the deposit. This solution can be used for brass, copper, bronze, etc.

Etching Ornamental Designs in Metal.— When metal plates having an ornamental design are required in small quantities, the etching process is sometimes used. The photographic method which is employed for nearly all intricate designs is as follows: The design is first drawn on white paper to any convenient scale, in black and white. A photographic negative is then made, or this may be procured from photo engravers who make a specialty of such work. The blacks and whites must be, respectively, opaque and transparent. This negative is used to print the design on the work to be etched, the metal, in order to take the design, being coated with a sensitized emulsion of bi-chromated albumen which has the property of remaining insoluble in water after exposure to the light. The portions corresponding to the opaque parts of the negative thus wash out in warm water, leaving the metal bare. Just prior to washing, however, the surface is coated with special lithographic ink, by means of a roller. The design is now on the metal, surrounded by a resist of a bichromated albumen base covered with a sticky ink. This resist is further reinforced by sprinkling the surface with dragon's blood. The latter is melted by heating and adheres to the resist, but forms a powder on the unprotected surface which can readily be blown off. This resist is effective, provided the etching is not done too deeply. For brass and copper, a strong solution of perchloride of iron is generally preferred as an etching fluid, as this does not attack the resist like strong acids, although its action is comparatively slow. Nitric acid may be used with proper resists. While etching is usually employed for cutting into the surface of the metal, the same process can be used for perforating the design in the plate.

Various acid-resisting materials are used for covering the surfaces of steel rules, etc., prior to marking off the lines on a graduating machine. When the graduation lines are fine

Copyright 2004, Industrial Press, Inc., New York, NY

and very closely spaced, as on machinists' scales which are divided into hundredths or sixty-fourths, it is very important to use a thin resist that will cling to the metal and prevent any under-cutting of the acid; the resist should also enable fine lines to be drawn without tearing or crumbling as the tool passes through it. One resist that has been extensively used is composed of about 50 per cent of asphaltum, 25 per cent of beeswax, and, in addition, a small percentage of Burgundy pitch, black pitch, and turpentine. A thin covering of this resisting material is applied to the clean polished surface to be graduated and, after it is dry, the work is ready for the graduating machine. For some classes of work, paraffin is used for protecting the surface surrounding the graduation lines which are to be etched. The method of application consists in melting the paraffin and raising its temperature high enough so that it will flow freely; then the work is held at a slight angle and the paraffin is poured on its upper surface. The melted paraffin forms a thin protective coating.

Copyright 2004, Industrial Press, Inc., New York, NY

MANUFACTURING

Welding with Thermit

Thermit Process.— This process of welding metals is effected by pouring superheated thermit steel around the parts to be united. Thermit is a mixture of finely divided aluminium and iron oxide. This mixture is placed in a crucible and the steel is produced by igniting the thermit in one spot by means of a special powder, which generates the intense heat necessary to start the chemical reaction. When the reaction is once started it continues throughout the entire mass, the oxygen of the iron being taken up by the aluminum (which has a strong affinity for it), producing aluminum oxide (or slag) and superheated thermit steel. ordinarily, the reaction requires from 35 seconds to one minute, depending upon the amount of thermit used. As soon as it ceases, the steel sinks to the bottom of the crucible and is tapped into a mold surrounding the parts to be welded. As the temperature of the steel is about 5400 degrees F., it fuses and amalgamates with the broken sections, thus forming a homogeneous weld.

It is necessary to pre-heat the sections to be welded before pouring, to prevent chilling the steel. The principal steps of the welding operation are, to clean the sections to be welded, remove enough metal at the fracture to provide for a free flow of thermit steel, align the broken members and surround them with a mold to retain the steel, pre-heat by means of a gasoline torch to prevent chilling the steel, ignite the thermit and tap the molten steel into the mold. This process is especially applicable to the welding of large sections. It has been extensively used for welding locomotive frames, broken motor casings, rudder- and sternposts of ships, crankshafts, spokes of driving wheels, connecting rods, and heavy repair work in general. One of the great advantages of the thermit process is that broken parts can usually be welded in place. For example, locomotive frames are welded by simply removing parts that would interfere with the application of a suitable mold. Thermit is also used for pipe welding, rail welding, and in foundry practice, to prevent the "piping" of ingots.

Preparation of Part to be Welded.— The first step in the operation of thermit welding is to clean the fractured parts and cut away enough metal to insure an manufactured flow of the molten thermit. The oxy-acetylene or oxy-hydrogen cutting torch is very efficient for this operation. The amount that should be cut away depends upon the size of the work. Assuming that a locomotive frame is to be welded, the space should be about $\frac{3}{4}$ inch wide for a small frame, and 1 inch wide for a large frame. The frame sections are then jacked apart about $\frac{1}{4}$ inch to allow for contraction of the weld when cooling; trammel marks are scribed on each side of the fracture to show the normal length. If the weld is to be made on one member of a double-bar frame, the other parallel member should be heated with a torch to equalize the expansion in both sections and prevent unequal strains.

Mold for Thermit Welding.— The mold surrounding the fractured part should be so arranged that the molten thermit will run through a gate to the lowest part of the mold and rise through and around the parts to be welded into a large riser. The accompanying illustration shows a mold applied to a locomotive frame that is broken between the pedestals at *A*. The thermit steel is poured through gate *B*, and rises into space *C* after passing around and between the ends of frame *F*. The mold must allow for a reinforcing band or collar of thermit steel to be cast around the ends to be welded. Space *G*, for forming this collar, and the opening between the frame ends, must be filled before ramming up the mold. Yellow wax is ordinarily used for this purpose. The shape of this band or collar should be as indicated by the view of the completed weld at *D*. The thickest part is directly over the fracture and the band overlaps the edges of the fracture at least one inch.

Copyright 2004, Industrial Press, Inc., New York, NY



For a frame of average size, the collars are made about 4 inches wide and 1 inch thick at the center, the thickness being increased for comparatively large sections. An opening is also made at *E* for pre-heating the ends to be welded.

Patterns for the riser, pouring and heating gates can be made of wood. The riser *C* should be quite large because the steel that first enters the mold is chilled somewhat by coming into contact with the metal, even when pre-heated. This chilling effect is overcome by using enough thermit steel to force the chilled portion up into the riser and replacing it by metal which has practically the full temperature received during reaction. The mold must be made of a refractory material, owing to the intense heat. The best material is made of one part fire sand, one part fire-clay and one part ground firebrick, thoroughly mixed while dry and moistened just enough to pack well. If these ingredients cannot be obtained, one part fire-clay and one part clean, dry sand may be used. When the mold and box are filled and tamped. the wooden runner and riser patterns are withdrawn. The mold is then ready for the pre-heating and drying operation which causes the wax matrix to melt and run out.

Thermit Required for Welding.— The quantity of thermit required for making a weld can be determined from the cubic contents of the weld. Calculate the cubic contents of the weld and its reinforcement in cubic inclines; double this amount to allow for filling the gate and riser, and multiply by 0.56 to get the number of pounds of thermit required. When wax is used for filling, the weight of the thermit can be determined as follows: Weigh the wax supply before and after filling the fracture. The difference in weight (in pounds, or the quantity used, multiplied by 32 will give the weight of thermit in pounds.

Thermit Additions.— When a quantity of more than 10 pounds of thermit is to be used, add 10 per cent of steel punchings (not over ½ inch in diameter) or steel scrap, free from grease, into the thermit powder. If the thermit exceeds 50 pounds, 15 per cent of small mild steel rivets may be mixed with it. One per cent (by weight) of pure manganese and 1 per cent of nickel - thermit should be added to increase the strength of the thermit steel.

Pre-heating — Making a Weld.— The ends to be welded should be red hot at the moment the thermit steel is tapped into the mold. This pre-heating is done, preferably, by a gasoline, compressed-air torch, and, as previously mentioned, it melts the wax matrix used for filling the fracture to form the pattern for the reinforcing band. When the ends have been heated red, quickly remove the torch and plug the pre-heating hole *E* with a dry sand core, backing it up with a few shovelfuls of sand, well packed. The end of the cone-shaped crucible should be directly over the pouring gate and not more than 4 inches above it. To start the reaction, place one-half teaspoonful of ignition powder on top of the thermit and ignite with a storm match. It is important that sufficient time be allowed for the completion of the thermit reaction and for fusion of the steel punchings which have been

Copyright 2004, Industrial Press, Inc., New York, NY

mixed within the thermit. Within charges containing from 30 to 50 pounds of thermit, the crucible should not be tapped in less than 35 seconds; with charges containing from 50 to 75 pounds, 40 seconds; 75 to 100 pounds, 50 seconds to one minute.

When welding a frame broken as shown in the illustration previously referred to, the screw jack used for forcing the pedestals apart should be turned back somewhat to release the pressure gradually as the weld cools. After pouring, the mold should remain in place as long as possible (preferably 10 or 12 hours) to anneal the steel in the weld, and, in any case, it should not be disturbed for at least two hours after pouring.

When welding a broken spoke in a driving wheel, or a similar part, it is necessary to preheat the adjacent spokes in order to prevent undue strains due to expansion and contraction. If a section of a spoke is broken out, it can be cast in, but if the space is over 6 inches long, it is better to insert a piece of steel and make a weld at each end. Owing to the high temperature 5400 degrees F.) and the violent ebullition of thermit during reaction, the crucible must be lined with a very refractory material. The crucibles used for this purpose have a sheet-iron shell and are lined with magnesia.

Filling Shrinkage Holes and Surface Flaws.— The filling of surface flaws in castings and forgings usually requires from 2 to 10 pounds of thermit. To make a weld of this kind, place an open mold around the part to be filled, large enough to overlap it about ½ inch. Clean the hole thoroughly and heat to a red heat by means of a strong blow-torch. Use eighteen ounces of thermit for each cubic inch of space to be filled, but do not use less than two pounds for any one weld. Place a small amount of thermit in the crucible which, in this case, is of a small size for hand use. Ignite the thermit with ignition powder and as soon as it begins to burn, add the remainder, feeding it fast enough to keep the combustion going. When the reaction is completed, quickly pour the slag (which is about three-fourths of the total liquid) into dry sand; then pour the steel into the open mold and sprinkle loose thermit on top to prolong the reaction, as the casting, even when pre-heated, will have a chilling effect on the steel.

Composition of Thermit Steel.— An average analysis of thermit steel is as follows: carbon, 0.05 to 0.10 per cent; manganese, 0.08 to 0.10 per cent; silicon, 0.09 to 0.20 per cent; sulphur, 0.03 to 0.04 per cent; phosphorus, 0.04 to 0.05 per cent; aluminum, 0.07 to 0.18 per cent. The tensile strength is about 65,000 pounds per square inch.

High- and Low-pressure Torches.— The difference between high- and low-pressure welding and cutting torches, according to the generally accepted meaning of the term, is in the pressure of the acetylene. The first oxy-acetylene torches developed by Fouche were of the high-pressure type, using acetylene dissolved in acetone. Later, he developed a low-pressure torch, working on the injector principle, acetylene being drawn into the carburetor chamber where it mixed with the oxygen. The high pressures originally employed in the first torches could not be safely employed with the acetylene produced in generators, because the safe pressure of acetylene in volume should never exceed from 15 to 20 pounds per square inch, and the pressure is limited to 25 pounds per square inch by the Underwriters' Association in the United States: hence, the medium pressure which is in general use was developed. The proportion of oxygen to acetylene varies somewhat in the different torches. Usually from 1.04 to 1.12 times more oxygen is consumed than acetylene.

Welders and cutters should be provided with goggles or spectacles fitted with approved colored lenses that protect the eye from destructive light rays, flying sparks and globules of molten metal.

Copyright 2004, Industrial Press, Inc., New York, NY

SYMBOLS FOR DRAFTING

Symbols For Drafting

Table 58. Standard Graphical Symbols for Air Conditioning

Capillary tube		Filter line	
Compressor		Filter and strainer, line	
Compressor, rotary (Enclosed crankcase, belted)		Float, high side	
Compressor, reciprocating (open crankcase, belted)		Float, low side	
Compressor, reciprocating (open crankcase, direct-drive)		Gage	
Motor compressor, reciprocating (direct connected, enclosed crankcase)		Pressurestat	
Motor compressor, rotary (direct connected, enclosed crankcase)		Pressure switch	
Motor compressor, reciprocating (sealed crankcase)		Pressure switch (with high pressure cut-out)	
Motor compressor, rotary (sealed crankcase)		Receiver, horizontal	
Condensing Unit (air cooled)		Receiver, vertical	
Condensing Unit (water-cooled)		Scale trap	
Condenser air cooled (finned, forced air)		Spray pond	
Condenser air cooled (finned, static)		Thermal bulb	
Condenser water cooled (concentric tube in a tube)		Thermostat (remote bulb)	
Condenser water cooled (shell and coil)		Valve, expansion, automatic	
Condenser water cooled (shell and tube)		Valve, expansion, hand	
Condenser evaporative		Valve, expansion, thermostatic	
		Valve, compressor suction pressure limiting (throttling type, compressor side)	
Cooling unit, finned (natural convection)		Valve, constant pressure, suction	
Cooling unit (forced convection)		Valve, evaporator pressure regulating (snap action)	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 58. ***(Continued)*** **Standard Graphical Symbols for Air Conditioning**

Cooling unit, immersion		Valve, evaporator pressure regulating (thermostatic throttling type)	
Cooling tower		Valve, evaporator pressure regulating (throttling type, evaporator side)	
Dryer		Valve, magnetic stop	
Evaporator, circular (Ceiling type, finned)		Valve, snap action	
Evaporator, manifolded (Bare tube, gravity air)		Valve, suction vapor regulating	
Evaporator, manifolded (finned, forced air)		Valve suction	
Evaporator, manifolded (finned, gravity air)		Valve water	
Evaporator, plate coils (headered or manifolded)		Vibration absorver, line	

Table 59. Standard Graphical Symbols for Heating and Ventilation

Air eliminator		Access door	
Anchor		Adjustable blank off	
Expansion joint		Adjustable plaque	
Hanger or support			
Heat exchanger		Automatic damper	
Heat transfer surface (plan, indicate type, such as convector)			
Pump (Indicate type, such as vacuum)		Canvas connection	
Strainer		Deflecting damper	
Tank (designate type)		Direction of flow	
Thermometer		Duct (first figure is side shown)	
Thermostat		Duct section (exhaust or return)	
Trap, boiler return		Duct section (supply)	
Trap, blast thermostatic		Exhaust inlet, ceiling (indicate type)	
Trap, float		Exhaust inlet, wall (indicate type)	
Trap, float and thermostatic		Fan and motor (with belt guard)	
Trap, thermostatic			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 59. ***(Continued)*** **Standard Graphical Symbols for Heating and Ventilation**

Unit heater (centrifugal fan type- plan)		Inclined drop (with respect to air flow)	
Unit heater (propeller fan type- plan)		Inclined rise (with respect to air flow)	
Unit ventilator, plan		Intake louvers	
Valve, check			
Valve, diaphragm		Louber opening	
Valve, gate		Supply outlet, ceiling (Indicate type)	
Valve, glove		Supply outlet, wall (Indicate type)	
Valve, lock and shield			
Valve, motor operated		Vanes	
Valve, pressure reducing			
Valve relief (either pressure or vacuum)		Volume damper	
Vent point			

Table 60. Standard Graphical Symbols for Valves

Name of Valve	Flanged	Screwed	Bell & Spigot	Welded	Soldered
Angle valve, check					
Angle valve, gate (elevation)					
Angle valve, gate (plan)					
Angle valve, globe (elevation)					
Angle valve, globe (plan)					
Automatic by-pass valve					
Automatic governor operated valve					
Automatic reducing valve					
Check valve, straight way					
Cock					
Diaphragm valve					

Copyright 2004, Industrial Press, Inc., New York, NY

Table 60. ***(Continued)*** **Standard Graphical Symbols for Valves**

Name of Valve	Flanged	Screwed	Bell & Spigot	Welded	Soldered
Float valve					
Gate valve also used as Stop valve					
Gate valve motor operated					
Globe valve					
Globe valve motor operated					
Hose valve, angle					
Hose valve, gate					
Hose valve, glove					
Lockshield valve					
Quick opening valve					
Safety valve					

Table 61. Standard Graphical Symbols for Piping

Air Conditioning			
Brine return		Brine supply	
Chilled or hot water flow (circulating)		Chilled or hot water return (circulating)	
Condenser water flow		Condenser water return	
Drain		Humidification line	
Make-up water		Refrigerant discharge	
Refrigerant liquid		Refrigerant liquid	
Heating			
Air relief line		Boiler blow-off	
Compressed air		Condensate discharge	
Feed water pump discharge		Fuel -oil flow	
Fuel-oil return		Fuel-oil tank vent	
High pressure return		High pressure steam	
Hot water heating return		Hot water heating supply	
Low pressure return		Low pressure steam	
Make-up water		Medium pressure return	
Medium pressure steam			

Copyright 2004, Industrial Press, Inc., New York, NY

Table 61. ***(Continued)*** **Standard Graphical Symbols for Piping**

Plumbing			
Acid waste	ACID	Cold water	
Compressed air	A	Drinking water flow	
Drinking water return		Fire line	F F
Gas	G G		
Hot water		Hot water return	
Soil, waste, or leader (above grade)		Soil, waste, or leader (below grade)	
Vacuum cleaning	V V	Vent	
Pneumatic Tubes			
Tube runs			
Sprinklers			
Branch and head		Drain	S S
Main supplies	S		

Table 62. Standard Graphical Symbols for Pipe Fittings

Name of Fitting	Flanged	Screwed	Bell & Spigot	Welded	Soldered
Bushing					
Cap					
Cross, reducing					
Cross, straight size					
Cross					
Elbow, 45-degree					
Elbow, 90-degree					
Elbow, turned down					
Elbow, turned up					
Elbow, base					

Copyright 2004, Industrial Press, Inc., New York, NY

Table 62. ***(Continued)*** **Standard Graphical Symbols for Pipe Fittings**

Name of Fitting	Flanged	Screwed	Bell & Spigot	Welded	Soldered
Elbow, double branch					
Elbow, long branch					
Elbow, reducing					
Elbow, side outlet (outlet down)					
Elbow, side outlet (outlet up)					
Elbow, street					
Joint, connecting pipe					
Joint, expansion					

Copyright 2004, Industrial Press, Inc., New York, NY

FORGE SHOP EQUIPMENT

Hammer and Anvil

Blacksmiths' Anvils.— The quality of an anvil can generally be judged by its ring, a good anvil giving out a clear, sharp sound when struck with a hammer. If soft or defective, the sound will be dull. A good anvil so mounted that it gives out a full volume of sound is easier to work upon than one having a dead ring. Anvils ordinarily vary in weight from 150 to 300 pounds. A mistake is often made in selecting anvils that are too light for the service required. A 300-pound anvil is suitable for almost any kind of machine blacksmithing, and, if of this weight or heavier, it will not move around while in use or need to be strapped to its block. The square hole in the face of an anvil for receiving the cutting and forming tools is called the "hardie hole," and the small round hole near it is called the "pritchel hole." Anvils are usually made with a wrought-iron body to which is welded a hardened steel face.

Setting the Anvil.— The height of an anvil should be such that when standing beside if the knuckles of the hands will just reach the top surface or face. A solid oak block set endwise in the ground is often used as a foundation, but a cast-iron mounting block is preferable as it can easily be moved. The casting should have a fairly broad base, and a pocket at the top for receiving the anvil; a flat block of wood is provided to act as a cushion. An anvil should not be strapped rigidly to its foundation, as this checks the vibration which tends to keep the face free from scales, and renders a high-grade wrought-iron anvil little better than one made of cast iron. When a wooden block is used under the anvil, it is necessary to drive in a few spikes to keep the anvil in place, but these should be so placed that they do not bear directly upon or bind against the corners.

Steam Hammer Rating.— The capacity of a steam hammer or its rating is the weight of the ram and its attached parts, such as the piston and rod. The steam pressure behind the piston is not considered as far as the rating is concerned. For example, a 1000-pound hammer has reciprocating parts of that weight. The steam pressures for operating hammers usually vary from 75 to 100 pounds per square inch.

Capacity of Steam Hammers.— Capacity of a steam hammer or the proper size to use for working iron and steel of a given cross-sectional area can be determined approximately by the following rule: Multiply the area of the largest cross-section to be worked by 80, if of steel, or 60, if of iron, and the product will be the required rating of the hammer in pounds. For example, the capacity of a hammer for working steel billets 5 inches square would be determined as follows: $5 \times 5 = 25$; and $25 \times 80 = 2000$, which is the rating of the hammer in pounds. A hammer rated according to this rule is an economical size to use, although it can, of course, be employed for heavier work.

Power for Operating Steam Hammers.— The boiler horsepower for operating a steam hammer depends upon the service required and the number of hammers in use. Ordinarily, the boiler capacity can be less where there are a number of hammers, because all of the hammers are rarely, if ever, used at the same time; consequently, there is a reserve power; but with a single hammer, especially when in constant service, the boiler capacity should be proportionately greater. For average conditions, the boiler horsepower can be determined approximately by the following rule: Divide the rated capacity of the hammer in pounds by 100, and the quotient will be the boiler horsepower required for continuous operation. For example, if the hammer is rated at 2000 pounds, the boiler horsepower would equal $2000 \div 100 = 20$ H.P. This rule is also applicable in cases where the hammer is not used continually, by estimating the amount of idle time and making suitable allowance, but the boiler capacity must not be reduced to such an extent that there is a decided diminution in the pressure during the working period.

For foundations for steam hammers, see section on " Machinery and Hammer Foundations."

Copyright 2004, Industrial Press, Inc., New York, NY

Board Drop-hammers.— This type of hammer is generally considered superior to the steam hammer for producing drop-forgings of small and medium size. When the work is heavy and requires a great deal of "breaking down" or drawing, or even when the forgings are light, but have thin sections that cool quickly, thus requiring sharp, rapid blows, the steam hammer will usually give better results than aboard drop. The capacity of most of the board drop-hammers in use varies from 800 to 1500 pounds; the steam hammers found in drop forging plants usually range from 2000 to 5000 pounds capacity, for handling average work. It does not seem practicable to build board drops larger than 3000 pounds falling weight, and where the forgings are heavy enough to require a capacity over 1500 or 2000 pounds, steam hammers are usually preferred. The latter type is also preferred in some forge shops for all classes of work. It is generally conceded that the cost of operation and repairs is greater for steam hammers, but the latter has a greater output for a given capacity.

The power required for operating board drop-hammers varies considerably with the nature of the work. Very little power is required at the point of "pick up," if the work is practically "die to die; " but when the work is soft and there is no rebound, a great deal more power is required, as the rolls have to pick up a "dead load" from rest and there is tattle kinetic energy in the driving pulleys. When there is a good rebound, with the knock-off properly timed, the board will be moving upward with considerable velocity when engaged by the rolls, and much less power is required. Seasoned maple boards have proved superior to any other kind for board drop-hammers. Paper fiber has been tried with fair results, but at present the cost of this material is too high.

For foundations for drop-hammers, see section on "Machinery and Hammer Foundations."

Table 63. Dimensions of Flat-jawed Tongs



Capacity, Inches	*A*	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*I*	*K*	*L*	Rivet
0 – 1/8	5/8	3/8	1/4	5/8	1/16	2 1/8	1/2	5/16	5/16	1/4	14	1/4
3/16 – 5/16	3/4	7/16	5/16	5/8	1/16	2 1/4	9/16	5/16	5/16	1/4	15	1/4
3/8 – 7/16	7/8	1/2	5/16	3/4	1/16	2 1/2	5/8	3/8	3/8	5/16	16	5/16
1/2 – 5/8	1	9/16	3/8	7/8	3/32	2 3/4	11/16	7/16	3/8	5/16	18	3/8
3/4 – 7/8	1 1/8	5/8	3/8	1	5/32	3	3/4	1/2	7/16	3/8	20	7/16
1– 1 1/8	1 1/4	11/16	7/16	1 1/8	3/16	3 1/4	13/16	9/16	1/2	7/16	22	1/2
1 1/4 – 1 3/8	1 3/8	3/4	1/2	1 1/8	1/4	3 1/2	7/8	9/16	1/2	7/16	24	9/16
1 1/2 – 1 5/8	1 1/2	3/4	1/2	1 1/4	3/8	3 3/4	1	5/8	5/8	1/2	26	5/8
1 3/4 – 1 7/8	1 5/8	13/16	9/16	1 3/8	7/16	4	1 1/16	11/16	5/8	1/2	28	5/8
2	1 3/4	7/8	5/8	1 1/2	7/16	4 1/4	1 1/8	1 1/8	11/16	1/2	30	11/16

Copyright 2004, Industrial Press, Inc., New York, NY

Table 64. Dimensions of Goose-neck Tongs



Capacity, Inches	*A*	*B*	*C*	*D*	*E*	*F*	*G*	*H*	*I*	*L*	Rivet
1/4 – 5/16	5/8	1/2	7/16	5/16	1/8	1	1/2	5/16	1/4	14	1/4
3/8 – 7/16	3/4	9/16	1/2	5/16	3/16	1 1/8	9/16	5/16	1/4	16	5/16
1/2 – 5/8	7/8	5/8	9/16	3/8	1/4	1 1/4	5/8	3/8	5/16	18	3/8
3/4 – 7/8	1	3/4	5/8	7/16	3/8	1 1/2	3/4	3/8	5/16	20	7/16
1– 1 1/8	1 1/8	7/8	11/16	1/2	1/2	1 3/4	7/8	3/8	5/16	20	1/2
1 1/4 – 1 3/8	1 1/4	1	3/4	9/16	5/8	2	1	7/16	3/8	22	1/2
1 1/2 – 1 3/4	1 3/8	3/4	1/2	1 1/8	3/4	2 1/8	1 1/8	1/2	3/8	24	9/16
1 7/8 – 2 1/8	1 3/8	1 3/16	15/16	11/16	1	2 1/4	1 1/4	1/2	3/8	26	5/8
2 1/4 – 2 1/2	1 1/2	1 1/4	1	3/4	1 1/8	2 1/2	1 1/2	9/16	7/16	28	5/8
2 5/8 – 2 7/8	1 1/2	1 5/16	1 1/16	3/4	1 1/4	2 3/4	1 3/4	9/16	7/16	30	3/4
3 – 3 1/4	1 5/8	1 3/8	1 1/8	3/4	1 1/2	3	2	5/8	1/2	32	3/4
3 1/2 – 3 3/4	1 3/4	1 1/2	1 1/4	3/4	1 3/4	3 1/4	2 1/4	5/8	1/2	34	3/4
4 – 4 1/4	2	1 5/8	1 5/16	13/16	2	3 1/4	2 1/2	11/16	9/16	36	3/4
4 1/2 – 4 3/4	2 1/8	1 5/8	1 5/16	13/16	2 1/8	3 1/4	2 3/4	11/16	9/16	38	3/4
5	2 1/4	1 3/4	1 3/8	7/8	2 1/4	3 1/2	3 1/4	3/4	5/8	40	7/8

Forging Presses.— The power of forging presses for the average line of work is approximately as follows: For mild steel at a fair heat, a pressure of from 3 to 5 tons per square inch on the faces of the tools is generally sufficient, but when swages or dies are used, it may be necessary to double these pressures. For the very hardest steels, the pressure required may be as high as 10 or even 15 tons per square inch, but this is an exceptional case. For small forgings, including such parts as can be made from 8-inch square blooms or 12- by 6-inch flats, a press of 300 tons is sufficient, and for larger forgings, such as those used for heavy marine shafts and cranks, a 3000-ton press is generally considered sufficient and can readily handle a 60-inch ingot. The table above indicates, in a general way, the capacity of presses for handling ingots of various diameters.

Table 65. Capacity of Forging Presses

Capacity of Press, Tons	Maximum Diam. of Ingots, Inches	Capacity of Press, Tons	Maximum Diam. of Ingots, Inches
300	10	1500	36
500	14	2000	48
800	20	3000	60
1200	27	4000	72

Copyright 2004, Industrial Press, Inc., New York, NY

A press of comparatively small capacity may, with suitable appliances, handle work that is really too heavy for it, but at some sacrifice of speed; for economical operation, there should be ample power. As is generally known, the forging press is superior to the steam hammer for comparatively large forgings, because the hammer tends to spread the surface metal without acting upon the center of the ingot to the required degree. With a press, the forging action goes right to the center of the ingot, as evidenced by the bulging that takes place at the sides, and if there is a cavity in the ingot, forging under the press closes it, whereas a hammer, by spreading the surface metal, may tend to enlarge it. As forgings diminish in size, the difference in favor of the press is less marked. Owing to the recent increase in the operating speed of forging presses, however, they now compete with power hammers in the forging of comparatively light work, and the range of presses has been greatly extended.

Air Pressures and Pipe Sizes for Forges.— Blacksmiths' forges require air pressures varying from 1½ to 6 ounces per square inch. Small forges with the blower close to them are adequately supplied with 1½ ounce pressure. If the blower is some distance away and a long discharge pipe with many bends leads to the forge, even though the latter be small, it may be necessary to carry 3 ounces pressure or more, to overcome the friction in the air ducts. Large forges usually require from 3 to 6 ounces pressure. The table, "Air Pressures and Pipe Sizes for Forges," gives the diameters of discharge mains for various tuyere sizes and numbers of forges.

Table 66. Air Pressures and Pipe Sizes for Forges

Diam. Forge Tuyere, Inches	Number of Forges Supplied by Blower									
	1	2	3	4	5	6	7	8	9	10
	Diameter Discharge Main at Blower, Inches									
¾	1½	1½	2	2	2½	2½	3	3	3	3
1	1½	2	2½	3	3	3½	3½	4	4	4
1¼	2	2½	3	3½	4	4	4½	5	5	5
1½	2	3	3½	4	4½	5	6	6	6	6
1¾	2½	3½	4	4½	5	6	6	7	7	7
2	3	4	4½	5	6	7	7	8	8	8
2¼	3	4	5	6	7	7	8	9	9	9
2½	3½	5	6	7	8	8	9	9	10	10
2¾	4	5	6	7	8	9	10	10	11	11
3	4	6	7	8	9	10	11	11	12	12
3½	4½	7	8	9	10	11	12	13	14	14
4	6	8	9	11	12	13	14	15	16	17

American Blower Co.

The Cold Swaging Process.— Cold swaging is a method of reducing or forming steel or other material while cold, by drawing to a point or reducing the diameter, as may be required. This is performed by a machine that causes the work to be struck a large number of successive blows by a pair of dies shaped to give the required form. This process is principally applied to the reduction of wires, rods and tubes, and is the only method by which rolled or plated stock can be reduced without destroying the plating or coating. For this reason, it is largely employed for jewelers' work. It is also extensively used for pointing rods or tubes which are to be drawn. The process is used in the manufacture of needles, bicycle spokes, button hooks, crochet needles, etc.

Copyright 2004, Industrial Press, Inc., New York, NY

Forging Machines.— Some forging machines are intended especially for bolt and rivet heading, and others for more general work. The form or shape into which a part is forged is governed by dies of the required shape and also by a heading tool or plunger which bends or upsets the heated bar of metal and forces it into the die impression. The die may have a single impression, or two or three impressions may be required in order to forge the part by successive operations.

Dies for Bolt and Rivet Forging Machines.— Bolt and rivet dies used in forging machines are, as a rule, made from steel containing from 0.60 to 0.80 per cent carbon and are hardened and drawn. The heading tool, which must be tougher than the dies, is generally made from steel containing from 0.40 to 0.50 per cent carbon, and is drawn considerably more than the forming dies.

Dies and Tools Used in Hot-pressed Center-feed Nut Machines.— The dies used in hot-pressed center-feed nut machines are usually made from chilled iron castings, the dies being ground to size. It is claimed that dies made from this material will last fully eight times as long as those made from ordinary carbon steel, but as it is somewhat difficult to obtain the proper amount of chill, many manufacturers use a good grade of open-hearth crucible steel instead. A crucible steel which is found to give good results contains from 0.90 to 1.10 per cent carbon. In many cases, vanadium alloy steel is used for dies for nut forging machines. The composition of vanadium steel for dies varies. Two grades of vanadium tool steel are recommended for forging machine dies by the American Vanadium Co., of Pittsburgh, Pa. One is composed of carbon, 0.50 per cent; chromium, from 0.80 to 1.10 per cent; manganese, from 0.40 to 0.60 per cent; vanadium, not less than 0.16 per cent; silicon, not more than 0.20 per cent. The heat-treatment recommended for this steel is as follows: Heat to 1550 degrees F. and quench in oil; then reheat to from 1425 to 1450 degrees F., and quench in water, submerging the face of the die only.

The second kind of vanadium tool steel recommended has the following analysis: Carbon, from 0.65 to 0.75 per cent; manganese, from 0.40 to 0.60 per cent; vanadium, not less than 0.16 per cent; silicon, not more than 0.20 per cent. The heat-treatment for this steel should be as follows: Heat to 1525 degrees F. and quench in water, with only the face of the die submerged. Ordinary carbon tool steel dies should be drawn to a light straw color.

Bulldozer Dies.— Many of the tools or dies used on bulldozers are made of cast iron, in order to reduce the cost, and those parts of the dies which are subjected to wear are faced with hardened steel plates which may readily be replaced, if necessary. Whenever hot punching or cutting is done, high-speed self-hardening steel should be used for the working members of the tool.

Helve Hammers.— Power hammers of the helve type are adapted especially for relatively light forging operations, particularly when a rapid succession of blows is required. Ordinary helve hammers are usually built in sizes ranging from 15 to 200 pounds, this rating being based upon the weight of the hammer head. Some "upright helve" hammers are made in sizes up to 500 pounds.

Vertical Power Hammers.— Vertical power hammers of the crank- and pneumatically-operated types are used for general forging operations, especially on the lighter classes of work. Power hammers of the vertical type usually range in size from 25 pounds up to 500 pounds.

Efficiency of Forging Hammers.— The Heim method for determining the efficiency of forging hammers is based on the results of numerous tests conducted by allowing an ordinary drop-hammer to fall a predetermined distance upon a pure lead cylinder, the height of which is 1.5 times its diameter. The diameters of the cylinders which have been adopted for use in testing various sizes of hammers (with regard to their falling weight) are given in Table 67. The following formula gives the number of foot-pounds of work done by one blow of the hammer:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Work} = 36.75D^3[8.85A + 13.12(A^2 + A^4)] \text{ foot-pounds}$$

Where D = Diameter of the lead cylinder;

$$A = (H - H_1) \div H$$

H= Original height of the cylinder

H_1= height of the cylinder after being stuck by the hammer.

If the expression inside the brackets in the formula is designated by B, the formula may be expressed in the following form:

$$\text{Work} = 36.75D^3B$$

After the lead cylinder has been struck by the hammer, the value of A is calculated and the number of foot-pounds of work developed by the hammer is then obtained by taking the value of B from Table 68 and substituting in the formula.

Example: Suppose a 100-kilogram (220-pound) hammer striking 180 blows per minute is allowed to strike a lead cylinder, the original dimensions of which are 50 millimeters (1.97 inch) in diameter by 75 millimeters (2.95 inches) high. After the blow has been struck, the resulting height of the cylinder is 48 millimeters (1.90 inch). From the preceding formula:

$$A = \frac{2.95 - 1.90}{2.95} = 0.35$$

$B = 4.9$, from Table 68

Substituting the values of D and B in the formula for the work done by one blow of the hammer:

$$36.75 \times 1.97^3 \times 4.9 = 1376 \text{ foot-pounds} = \text{work done by one blow.}$$

$$\frac{1376 \times 180}{60} = 4128 \text{ foot-pounds} = \text{work done by one blow.}$$

The maximum power required to drive the hammer is 10.3 horsepower. As one horsepower is equivalent to 550 foot-pounds of work per second, the amount of power consumed by the hammer per second is: $10.3 \times 550 = 5665$ foot-pounds. The efficiency of the is found to be:

$$\text{Efficiency} = \frac{\text{useful work}}{\text{power supplied}} = \frac{4128}{5665} = 72 \text{ percent.}$$

The Heim formula and method of testing may be applied to all types of hammers, but, when used on steam hammers, the test must made while the hammer is running continuously and not when set to deliver a single blow.

Table 67. Dimensions of Lead Plugs Used for Testing Various Sizes of Hammers

Falling Weight of Hammer		Diameter of Lead Cylinder[a]		Falling Weight of Hammer		Diameter of Lead Cylinder	
Pounds	Kilograms	Inches	Millimeters	Pounds	Kilograms	Inches	Millimeters
66	30	1.18	30	330	150	2.36	60
110	50	1.38	35	506	230	2.76	70
165	75	1.57	40	770	350	3.15	80
220	100	1.97	50	1100	500	3.54	90

[a] Height equals 1.5 × diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 68. Values of Factors Used in Calculating Power of Hammers

A	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50	0.55	0.60
B	1.01	1.63	2.31	3.08	3.94	4.90	5.97	7.17	8.52	10.03	11.73

Machinery and Hammer Foundations

The materials commonly used are concrete, stone, brick, and wood in conjunction with concrete for machines subjected to considerable vertical shock. The principal characteristics of these materials are briefly as follows: Concrete is an ideal foundation material, as it becomes practically one solid piece and is much cheaper than a masonry foundation. Stone, in addition to being strong and durable, has great vibrations absorbing power, but is quite costly. Brick is not so durable as stone, but is cheaper and available everywhere. In building a foundation, provision should be made for the foundation bolts, when these are necessary. Sometimes the bolts are set permanently in the foundation, or they may be placed in pipes and have pockets at the lower ends, thus permitting adjustment or removal, if necessary. The bolts are usually located in the proper position by making a wooden templet in which holes are bored to coincide with the holes in the machine base. The inclination of the sides of a foundation should vary from 1½ to 3 inches per foot from the vertical. The foundation pit should be excavated below the frost line of the locality.

Concrete Foundations.— The timber used for making the forms in which concrete foundations are molded should be about 1 inch thick, dressed on the inner side to give a smooth surface. The form should be braced externally about every 2½ feet, and internally about every foot in height. As the form is being filled, the inside braces can be removed. If pocket molds are used for the lower ends of the bolts, they should be soaked in water two or three hours before using, to prevent their swelling and sticking in the concrete. Do not use concrete that has been mixed over twenty minutes. Ram with hammers weighing about 1 pound per square inch of face area, the ramming being continued until water just shows at the surface.



Fig. 1.



Fig. 2.

Put down the concrete in layers about 6 inches thick and work it onto the form with a shovel, to obtain a smooth, even surface. The foundation may be partly filled with stones about the size of a man's head, placed approximately one foot apart and not less than one foot from the foundation surfaces. These stones should be wet before laying. If the work is stopped at night before completion, make grooves in the surface and when starting the next

Copyright 2004, Industrial Press, Inc., New York, NY

day, sprinkle and dust over with dry cement. As soon as the concrete has set, remove the form, as it is much easier to patch when the cement is somewhat "green." Foundations are sometimes "slushed" instead of being rammed. In this case, the concrete is mixed just wet enough so that it cannot be piled up. It is then dumped into the molds and worked in them to prevent air bubbles. The first method gives a more homogeneous structure as there is no chance for the broken stones to settle. When the machine is in position, the space around the foundation bolts may be filled with liquid cement, lead or melted sulphur.

Drop Hammer Foundations.— The following drop-hammer foundations are recommended by the E. W. Bliss Company:

Concrete Foundation: : Excavate a hole from 10 to 14 feet deep and from 8 to 12 feet square; build up a block of concrete with tapering sides, as shown in Fig. 63,having a top about 6 to 12 inches wider, all around, than the base of the anvil. Place the anvil in position and wedge it level; then run a thin mixture of concrete the anvil and allow it to set. Next move the wedges and build up a wall of concrete from 4 to 6 inches thick around the anvil. (See Fig. 1 and Fig. 2) This will make the use of bolts unnecessary and the anvil will set solid and will not be likely to shift. Solid concrete makes an excellent foundation that does not deteriorate, as is the case with timber when subjected to dampness from the earth or atmospheric moisture. Another advantage is that it is almost impervious to sparks or hot pieces of metal.

Timber Concrete Foundations: Excavate a hole somewhat larger than the anvil or base of the hammer. At the bottom lay a bed of concrete from 1 to 2 feet thick, as shown in Fig. 2. On this concrete bed place, endwise, Georgia pine timbers 12 by 12 inches by 6 to 8 feet long. These should be securely strapped together by steel bands on the outside fastened with through bolts. The timber base should preferably be a little larger than the anvil. To preserve the timbers coat them with oil of tar or creosote. The tops of the timbers should be dazed off evenly to obtain a level surface for the anvil. Another method of making a foundation of this kind, for small and medium sized hammers, is to put the timbers upon a foot or more of gravel rammed down on a hard-pan bottom. When the timbers, which are also placed endwise and bolted, are in position, the space around the sides is filled with gravel tightly rammed.

Foundation for Steam Hammer.— To secure the greatest efficiency from steam power hammers, the foundations on which they are mounted must be solid concrete resting upon hard-pan has given better results than the combination of heavy wooden beams and concrete often used. When making solid concrete foundations, there should be several inches of cement placed over the concrete, and a cushion of wood, at least 3 inches tuck, between the cement and base of the anvil, to give the necessary resiliency and prevent the concrete from being pulverized by the impact of the blows. In the front and rear of the hammer there should be openings down to the level of the anvil base, so that it can be leveled or adjusted by wedging and grouting with cement, in case it should sag or get out of alignment with the upper parts of the hammer. These openings can be covered with hatches set level with the floor.

Machine and Forge Shop Floor Materials

Machine shop floors are commonly made of wood or concrete. Probably there is no floor for the machine shop as good as one made of selected hard maple, properly laid and supported, as it wears smoothly and evenly. Concrete, however, has its advantages, the most important of which is its fire-resisting qualities. There are few objections to a wooden floor, and from the standpoint of health it is generally considered superior to concrete. Where there is much heat, or large quantities of moisture or chemicals in bulk, wooden doors should not be used. In certain classes of store-rooms, or where there is a likelihood of considerable moisture, as in wash rooms, concrete floors are considered superior to wood.

Copyright 2004, Industrial Press, Inc., New York, NY

Concrete and Wooden Floors.— The following information on shop floors and their materials is abstracted from a paper by Mr. L. C. Wason read before the American Society of Mechanical Engineers. While the factor of cost is to be considered first, very often the maintenance and adaptability for the particular Service required is of first importance. The initial cost of a granolithic floor surface is at no disadvantage compared with a wooden floor, as the cost of such a surface laid in the best manner is about equal to the cost of seven-eighths maple flooring. In addition, the granolithic surface is fire-proof and will not decay or disintegrate as the result of moisture, which is one of the weak points of the wooden floor. On the other hand, a wooden floor is more easily repaired than a granolithic surface. In making a comparison between wooden and granolithic floors, it is also necessary to consider the workmanship. With a maple top floor, the wearing quality depends comparatively little on the skill of the one who lays the floor, but with a granolithic finish, the work must be done care fully and intelligently. Among the objections to the granolithic surface, one of the most prominent is the bad effect of a concrete floor upon the health and comfort of the workmen. This is not due to the hardness of the floor, but rather to its heat conductivity. When a workman stands for hours on a concrete floor, the heat of the body is conducted to the floor quite rapidly, which tends to disarrange the circulation and cause physical ailments, such as rheumatism, etc. For men working steadily at machines, and usually in one position, this objectionable feature can be overcome by the use of insulating foot-boards or wooden gratings upon which to stand.

The dust produced by the wear of some granolithic surfaces has proved harmful to delicate machinery, whereas a wooden floor does not of itself produce a dust capable of any appreciable abrasive action. It is possible, however, by gluing battleship linoleum to concrete floors, to obtain many of the advantages of a wooden surface. Linoleum is also an effective insulation against the loss of bodily heat.

High resistance to wear and practically complete dustlessness can be secured in a granolithic surface if properly made. To secure a durable and practically dustless floor, proceed as follows: Do not use sand, as sand grains are quickly broken by abrasion and form dust. The granolithic finish should contain the highest possible proportion of tough stone aggregate. Use stone suitable for macadam road, and of a size that will pass through a half-inch round mesh screen, but use nothing smaller than that passed by a 20-mesh screen. Mix the concrete dry, and of a consistency for making blocks, so that considerable tamping will be required to bring enough water to the surface for troweling. Finally, do the troweling before the mortar sets. Prolonged troweling of a wet mixture brings to the top the "laitance" of the concrete, which is the part incapable of a true set. A top layer of laitance is therefore porous and wears down quickly. Even the fine particles of good cement should not be brought to the surface, as they form a layer which is weakly bonded to the rest of the concrete and wears away rapidly, appearing in the air as dust.

To Prevent Dust on Concrete Floors.— The Aberthaw Construction Co. of Boston, contracting engineers specializing in concrete, recommends the following method of curing a dusty concrete floor: Have the surface entirely dry; then paint it with a mixture of boiled linseed oil thinned with gasoline. Apply several coats, until the oil shows glossy on the top. The theory of this is that the linseed oil, having been boiled, has lost most of its volatile components and is practically permanent. The gasoline thins this down enough so that it will strike into the pores. A little experimenting will show the proper proportions. The thinner it is, the more coats will be required and the deeper it will strike in. A floor that is causing serious trouble from dust can often be cured with very little trouble and expense in this way.

Floors for Forge Shops.— There is considerable difference in opinion as to the best material for blacksmith shop flooring. Wood is too inflammable, bricks crack and break from the heat, cement or concrete has the same objectionable features, and asphalt is out of the question. Perhaps nothing is superior to or cheaper than dirt mixed with ashes. If kept moist by sprinkling at least once a day, it is more comfortable to stand upon than the other mate-

Copyright 2004, Industrial Press, Inc., New York, NY

rials mentioned. It is easily repaired and leveled in case holes are worn in it, and is not affected by dropping heavy or hot pieces upon it. The space between the walls and forges, however, may be covered with concrete to facilitate the handle of such appliances as portable surface-plates and vises.

Drop-Forging Dies

Steel for Drop-forging Dies.— Practically all drop-forging dies are made of high-grade open-hearth steel. A 60-point carbon steel is mostly used, although steel as low as 40-point and as high as 85-point carbon is employed in some cases. A special hardening treatment is required for the low-carbon steel, which more than offsets the saving in price, and, except in special cases, there is no advantage in using high-carbon steels, owing to the expense. The average 60-point carbon steel die, if properly hardened, should last for from 15,000 to 40,000 forgings, and sometimes as many as 70,000 forgings can be made from one set of dies. When making dies for large forgings, it is often thought advisable to use 80-point carbon steel, and not harden the dies. This obviates the danger from "checking" or cracking in hardening, and the un-hardened steel is hard enough to resist the tendency to stretch. A steel that is quite high in carbon should always be used for dies that are intended for making forgings from tool steel or any other hard steel.

Allowance for Shrinkage.— When making dies for small cold-trimmed steel forgings, the proper allowance for shrinkage is $\frac{3}{16}$ inch to the foot, or 0.015 inch to the inch. Such forgings are finished at a bright red heat and the rate of shrinkage is considerable. When making dies for hot-trimmed steel forgings of medium and large sizes, the shrinkage allowance is $\frac{1}{8}$ inch to the foot, or 0.010 inch to the inch. Hot-trimmed forgings receive the finishing blow while comparatively cold, and shrink a smaller amount than the cold-trimmed forgings. The foregoing allowances are used for all dimensions of the die impression, such as depth, width or length. The shrinkage allowance for dies to be used in forging bronze or copper is practically the same as that for steel.

Draft Allowance.— The amount of draft in a drop-forging die varies from 3 to 10 degrees. If the die is for a thin forging of uniform section, 3 degrees is ample, but if the forging is deep and has narrow ribs which are apt to stick, at least 7 degrees is necessary. If a die is used for forging a piece that is ring-shaped or has an annular part, the central plug that forms the interior of the ring should have a draft of 10 degrees, because, as the forging cools while being worked, it tends to shrink around the plug and if the draft is insufficient, it will stick in the die. With the foregoing exception, most drop-forging dies have a 7-degree draft. For convenience in laying out, it is well to remember that a 7-degree taper is approximately equal to a $\frac{1}{8}$-inch taper to the inch, and a 10-degree taper, $\frac{3}{16}$ inch to the inch.

Locating Impression in the Die.— When laying out a drop-forging die, the impression should be located so that the heaviest end of the forging will be at the front of the die-block. This makes the forging easier to handle and also permits the use of a fairly large sprue. There should be at least $1\frac{1}{2}$ inch left all around between the impression and the outside edge of the block. This also holds true for any part of the die, such as the edger, anvil or forming impression. If the forging has a hub or other projection that extends some distance from the main part on one side, the upper or top die should contain this deeper impression.

Obtaining Weight of Forging from Lead Proof.— After the upper and lower dies have been completed, shrinkage allowances and the general finish of the impressions are ordinarily tested by taking a "lead proof," and by weighing the lead, an approximate idea of the weight of the finished forging can be obtained. Roughly speaking, the finished forging will weigh two-thirds as much as the lead proof. The shrinkage of lead is practically the same as that of steel, so that the finished forging will also measure about the same as the one made of lead. In case of dies for eye-bolts and similar work, this rule must be disregarded, because the plugs that form the central opening will prevent the lead from shrinking natu-

Copyright 2004, Industrial Press, Inc., New York, NY

rally. When taking the lead proof, the die impressions are dusted with powdered chalk, and after the dies are clamped together, the molten lead is poured.

Amount of Flash for Drop-forging Dies.— Theoretically, there should be just enough forging metal in a die to fill the impression, and no more, but this is, of course, not practicable, as there is always some stock that must be disposed of after the impression is filled. To take care of this excess metal, dies are relieved all around the impression by milling a flat shallow recess about $\frac{1}{64}$ inch deep and $\frac{5}{8}$ inch wide. These dimensions are for dies of average size; in comparatively large dies this recess or "flash" would be a little deeper and wider. Both the upper and lower dies are flashed in this way. In addition, the upper die is "back-flashed," which means that there is a deeper recess, sometimes called the "gutter," milled around the impression at a distance of $\frac{1}{4}$ inch from the impression at every point. This back-flash is $\frac{3}{64}$ inch deep and acts as a relief for the excess metal after it has been squeezed from the flash proper. Only the finishing impression is provided with a flash and back-flash.

The Break-down of Drop-forging Dies.— The width of section used as a break-down (also known as the edger or side cut) should be enough wider than the forging to give plenty of room for the work of forging. A forging 1 inch thick should have a break-down $1\frac{1}{2}$ inch wide, and about the same proportions should be followed for forgings of other widths. The break-down should have a section corresponding with the gate and sprue of the die impression, but it should be made slightly longer, so that the forging will not be stretched when struck in the impression.

Hardening Drop-forging Dies.— Dies to be carburized should always packed for hardening in cast-iron or sheet-iron boxes containing a mixture of fresh bone and charcoal. The ordinary mixture is half bone and half charcoal. More bone gives greater hardness and more charcoal, less hardness, for a given heat; hence, the proportions should be varied according to requirements. The die should be packed face down on a one- or two-inch layer of this mixture and be settled so that the impression is filled. Sometimes the face is coated, before packing, with a thick paste of linseed oil and powdered bone-black, to protect the delicate edges from oxidation when in contact with the air. Fill the space between the sides of the die and the box with the bone and charcoal mixture, and cover over with a thick layer of wet clay paste to prevent the charcoal from burning out. Dies made of steel having less than 60-point carbon content should always be carburized. Open-hearth steel dies containing 60-point carbon or over can be hardened without carburizing.

Heating the Die.— An oil or gas furnace is recommended for heating, although a coal or coke-fired muffle furnace, capable of maintaining a temperature of at least 1600 degrees F., may be used, provided the temperature can be held constant. A temperature indicating device is necessary. The die should be put into the furnace as soon as the latter is lighted. If the correct quenching temperature for the steel is, say, 1500 degrees F., the furnace should be checked when the pyrometer indicates 1400 degrees, the die being allowed to "soak" at that heat for three or four hours. Then the heat should be slowly raised to 1500 degrees and held at that point one or two hours longer, according to the size of the die. Five hours is the minimum total time for heating, and seven or eight hours is much safer. A 60-point carbon die should be quenched between 1425 and 1450 degrees F.

Cooling the Heated Die.— When cooling, the face of the die should receive a sufficient flow of cold water to cause it to harden to the greatest possible depth. The back of the die should, at the same time, be cooled to make the shrinkage of the face and back equal, and to prevent warping. A good form of cooling tank is one having a large supply pipe extending up through the bottom for cooling the die face, and a smaller pipe above the tank to cool the back. Unless a jet of water under pressure is applied to the face of the die, the sunken parts of the impression will not harden equally with the face. Dies should not be cooled in a tank of still water, because steam forms in the die cavity which prevents the water from enter-

Copyright 2004, Industrial Press, Inc., New York, NY

ing, thus causing the formation of soft spots. To overcome this, the water must be forced into the impression by pressure sufficient to overcome the resistance of the steam thus formed. Oil should not be used for hardening hammer dies, as its cooling action is not great enough to produce a sufficient depth of hardening. Hammer dies which are simply surface hardened will not withstand the heavy blows received in service. To secure a greater hardening effect, brine of about 40 per cent solution is used by some die-makers.

Tempering Dies.— Dies should be tempered and drawn as soon as they are cool enough to remove from the tank. The dies should be heated in an oil bath, and quenched in water or cool oil. Any high-grade cylinder oil of high flash-point is suitable. Low-grade oils smoke unpleasantly and will not stand high temperatures. The drawing temperature of die steels is about 450 degrees F., for average conditions. The corners of the die and the cut-off should be drawn to a purple color with the aid of a blow torch.

Dies for Bronze and Copper Forgings.— Dies for producing drop-forgings from bronze or copper differ from those used for steel or iron forgings principally in the matter of finish. Owing to the softness of copper and bronze, the metal is driven into very minute impressions in the surface of the dies; hence, these surfaces must be perfectly free from scratches, in order to insure a smooth finish on the work. Even though these metals are soft, the hammering necessary when forging is very hard on the dies, and to prevent them from dishing or spreading, tool steel is ordinarily used, unless the forgings are extra large and heavy. The shrinkage, draft and finish allowances on this class of drop-forging dies are practically the same as on dies for steel and iron.

Trimming Dies for Drop-forgings.— Hot-trimming dies are made of a special grade of steel known as hot-trimming die-stock. The objection to use ordinary tool steel for hot-trimming dies is that the edges of a hardened die check badly after the die has been used for a short time, and this checking is followed by a breaking away of the steel around the edges, thus rendering the die unfit for use. This special steel requires no hardening, and after the die is in use, the edges toughen and give better service than the best hardened tool steel. The usual form of punch for hot-trimming dies merely supports the forging while it is being pushed through. If the forging has a broad, flat top face, the punch need only be a little more than a flat piece that covers the forging and acts as a pusher. Such punches are commonly made of cast iron. Cold-trimming dies are made from good tool steel of from 1.00 to 1.25 per cent carbon, and hardened and drawn to a dark straw color. The punches for cold trimmers are also made of tool steel and are hardened and drawn to a very dark straw color. These punches are hardened to prevent them from upsetting at the edges. As with hot-trimming punches, the punch should fit the die loosely, but it should support the forging at every point while it is being pushed through the die. There are two instances in which trimming punches should fit the dies as closely as the average punching die for sheet metal work; first, when trimming forgings on which the fin comes at the corner of the forging; second, forgings that are formed all in one die, the other die being flat. In these two cases, unless the dies fit very well, there will be burrs at the trimmed edges.

Standard Tolerances for Forgings.— The tolerances adopted by the Drop Forging Association in 1937 (see accompanying Tables 69 through 73) apply to forgings under 100 pounds each. Forging tolerances may either be "special" or "regular." *Special tolerances* are those which are particularly noted in the specifications and may state any or all tolerances in any way as required. Special tolerances apply only to the particular dimensions noted. In all cases where special tolerances are not specified, regular tolerances apply.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 69. Standard Tolerances for Forgings Adopted, 1937, by Drop Forging Association for Forgings under 100 Pounds Each

Thickness Tolerances, Inch[a]									
Net Weights, Pounds, up to –	Commercial		Close		Net Weights, Pounds, up to –	Commercial		Close	
	–	+	–	+		–	+	–	+
.2	.008	.024	.004	.012	20	.026	.078	.013	.039
.4	.009	.027	.005	.015	30	.030	.090	.015	.045
.6	.010	.030	.005	.015	40	.034	.102	.017	.051
.8	.011	.033	.006	.018	50	.038	.114	.019	.057
1	.012	.036	.006	.018	60	.042	.126	.021	.063
2	.015	.045	.008	.024	70	.046	.138	.023	.069
3	.017	.051	.009	.027	80	.050	.150	.025	.075
4	.018	.054	.009	.027	90	.054	.162	.027	.081
5	.019	.057	.010	.030	100	.058	.174	.029	.087
10	.022	.066	.011	.033					

[a] Thickness tolerances apply to the over-all thickness. For drop-hammer forgings, they apply to the thickness in a direction perpendicular to the main or fundamental parting plane of the die. For upset forgings, they apply to the thickness in the direction parallel to the travel of the ram, but only to such dimensions as are enclosed by the actually formed by the die.

Table 70. Standard Tolerances for Forgings Adopted, 1937, by Drop Forging Association for Forgings under 100 Pounds Each

Shrinkage		Plus		Die Wear		Mismatching		
Lengths or widths up to – in.	Commercial + or –	Close + or –	Net wt. up to – lbs.	Commercial + or –	Close + or –	Net Weights, Pounds, up to –	Commercial	Close
1	.003	.002	1	.032	.016	1	.015	.010
2	.006	.003	3	.035	.018	7	.018	.012
3	.009	.005	5	.038	.019	13	.021	.014
4	.012	.006	7	.041	.021	19	.024	.016
5	.015	.008	9	.044	.022	25	.027	.018
6	.018	.009	11	.047	.024	31	.030	.020

For each additional inch under shrinkage, add 0.003 to the commercial tolerance and 0.0015 to the close tolerance. For example, if length or width is 12 inches, the commercial tolerance is plus or minus 0.036 and the close tolerance plus or minus 0.018.

For each additional 2 pounds under die wear, add 0.003 to the commercial tolerance and 0.0015 to the close tolerance. Thus, if the net weight is 21 pounds, the die wear commercial tolerance is 0.062 plus or minus, and the close tolerance 0.031 plus or minus.

For each additional 6 pounds under mismatching, add 0.003 to the commercial tolerance and 0.002 to the close tolerance. Thus, if the net weight is 37 pounds, the mismatching commercial tolerance is 0.033 and the close tolerance 0.022.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 71. Standard Tolerances for Forgings Adopted, 1937, by Drop Forging Association for Forgings under 100 Pounds Each

Draft angle tolerances — the permissible variations from the standard or nominal draft angle							
Drop-Hammer Forgings				Upset Forgings			
Location of Surface	Nominal Angle Degrees	Commercial Limits	Close Limits	Location of Surface	Nominal Angle Degrees	Commercial Limits	Close Limits
Outside	7	0–10	0–8	Outside	3	0–5	0–4
Holes and Depressions	10 7	0–13 …	… 0–8	Holes and Depressions	5	0–8	0–7

Table 72. Standard Tolerances for Forgings Adopted, 1937, by Drop Forging Association for Forgings under 100 Pounds Each

Quantity Tolerances					
Number of Pieces on Order	Permissible Variation		Number of Pieces on Order	Permissible Variation	
	Over-run, Pieces	Under-run, Pieces		Over-run, Per cent	Under-run, Per cent
1 – 2	1	0	100 – 199	10	5.0
3 – 5	2	1	200 – 299	9	4.5
6 – 19	3	1	300 – 599	8	4.0
20 – 29	4	2	600 – 1,249	7	3.5
30 – 39	5	2	1,259 – 2,999	6	3.0
40 – 49	6	3	3,000 – 9,999	5	2.5
50 – 59	7	3	10,000 – 39,999	4	2.0
60 – 69	8	4	40,000 – 299,999	3	1.5
70 – 79	9	4	300,000 up	2	1.0
80 – 99	10	5			

These quantity tolerances represent the permissible over-run or under-run allowed for each release or part shipment of an order. Any shipping quantity within the limits of over-run or under-run shall be considered as completing the order.

Table 73. Standard Tolerances for Forgings Adopted, 1937, by Drop Forging Association for Forgings under 100 Pounds Each

Maximum Radii of Fillets and Corners, Inch					
Net Weights, Pounds, up to —	Commercial	Close	Net Weights, Pounds, up to —	Commercial	Close
.3	3/32	3/64	10	3/16	3/32
1	1/8	1/16	30	7/32	7/64
3	5/32	5/64	100	1/4	1/8

Regular tolerances: are divided into two divisions — "Commercial Standard" and "Close Standard." "Commercial Standard" tolerances are for general forging practice, but when extra close work is desired involving additional expense and care in the production of forgings, "Close Standard" may be specified. When no standard is specified, "Commercial Standard" shall apply.

Regular tolerances are applicable to 1) thickness; 2) width, including shrinkage and die wear, mismatching, and trimmed size; 3) draft angle; 4) quantity in shipment; and 5) fillets and corners.

Thickness Tolerances: Thickness tolerances shall apply to the overall thickness of a forging. (See Table 69.)

Copyright 2004, Industrial Press, Inc., New York, NY

Width and Length Tolerances: Width and length tolerances shall be alike and shall apply to the width or length of a forging. When applied to drop hammer forgings, they shall apply to the width or length in a direction parallel to the main or fundamental parting plane of the die, but only to such dimensions as are enclosed by and actually formed by the die. When applied to upset forgings, they shall apply to the width or length in a direction perpendicular to the direction of travel of the ramp.

Width and length tolerances consist of the three subdivisions following: a) Shrinkage and die wear tolerance; b) mismatching tolerance; and c) trimmed size tolerance.

Welding Methods

Classes of Welds.— Welds are classified according to the way the ends are formed prior to making the weld. The different welds ordinarily made in hand forging practice are the scarf weld, butt weld, lap weld, cleft or split weld and jump weld. These welds are shown by the accompanying illustration. It will be seen that the surfaces, in most instances, are rounded or crowned. This is done so that when the heated ends are brought together they will unite first in the center. Any slag or dirt which may have adhered to the heated surfaces will then be forced out as the welding proceeds from the center outward. When making a lap weld, the hammering should begin at the center in order to work all the slag out, as the faces in this case are not rounded.

Welding Heat.— When two pieces of wrought iron or mild steel are heated until they become soft and plastic and will stick together when one is pressed or hammered against the other, they have reached what is commonly known as a welding heat. The quality of the weld depends largely upon the welding heat. If the ends to be heated are not hot enough, they will not stick together; inversely, if the work remains in the fire too long, it becomes overheated and burned, which greatly injures the metal. Iron which has been overheated has a rough, spongy appearance and is brittle. The danger of burning is increased when the air blast is too strong and the fire is oxidizing. It is important to heat the work slowly to secure a uniform temperature throughout the ends to be heated. With rapid heating, the outside may be raised to the welding temperature, while the interior is much below it; consequently, the weld will be defective.

Fire for Welding.— When heated iron comes into contact with the air it absorbs oxygen, thus forming a scale or oxide of iron on the surface, which prevents the formation of a good weld. A fire for heating parts to be welded should have a fairly thick bed between the tuyere and the work, so that the oxygen in the air blast will be consumed before it reaches the parts being heated. When there is only a thin bed of fuel beneath the work, or if too strong a blast is used, the excess of oxygen will pass through and oxidize the iron. The hotter the iron, the greater the formation of scale. The surface being heated can be given an additional protection by covering it with some substance that will exclude the air. (See " Fluxes for Welding.") Ordinarily, the air blast for a forge fire should have a pressure varying from 3 to 6 ounces per square inch. (See "Air Pressures and Pipe Sizes for Forges. ")

Fluxes for Welding.— When iron is being heated preparatory to welding, the heated surfaces are oxidized to some extent or covered with oxide of iron, which forms a black scale when the hot iron comes into contact with the air. If this scale is not removed, it will cause a defective weld. Wrought iron can be heated to a high enough temperature to melt this oxide so that the latter is forced out from between the surfaces by the hammer blows; but when welding machine steel, and especially tool steel, a temperature high enough to melt the oxide would burn the steel, and it is necessary to use what is called a flux. This is a substance, such as sand or borax, having a melting temperature below the welding temperature of the work, and it is sprinkled upon the heated ends when they have reached about a yellow heat. The flux serves two purposes: It melts and covers the heated surfaces, thus protecting them from oxidation, and, when molten, aids in dissolving any oxide that may have formed, the oxide melting at a lower temperature when combined with the flux. Wrought

Copyright 2004, Industrial Press, Inc., New York, NY

iron can be welded in a clean, well-kept fire without using a flux of any kind, except when the material is very thin. The fluxes commonly used are fine clean sand and borax. When borax is used, it will give better results if burned. This can be done by heating it in a crucible until reduced to the liquid state. It should then be poured onto a flat surface to form a sheet; when cold, it can easily be broken up and pulverized. The borax powder can be used plain or it can be mixed with an equal quantity of fine clean sand and about 25 per cent iron (not steel) filings. For tool steel, a flux made of one part sal-ammoniac and twelve parts borax is recommended. When pieces are put together previous to welding, as in split welds, or when taking a second heat (usually termed a "wash"), a flux that will flow easily should be used. There are many welding compounds on the market, some of which are suited for one class of welding and some for another.

Fuels for Forge.— Coke, coal, charcoal, oil and gas are used as fuels for heating iron and steel preparatory to forging or welding. For general work, a coke fire is the best, although bituminous coal is extensively used. With anthracite coal, it is difficult to get a hot enough fire, especially on a small forge. Coke or bituminous coal should be low in sulphur, because sulphur makes the iron "hot short" or brittle while hot. Sulphur, lead, bronze or brass must not be in the fuel or fire to be used for heating iron or steel. A weld may be spoiled by throwing brass filings into a fire before heating the work.

Machine Welding.— There are three common types of welds that can be made satisfactorily in a forging machine, simple examples of which are shown in the accompanying illustration.

Lap-welding: This is one of the most successful methods that can be used in joining pieces together in a forging machine, whenever requirements will permit. There are several applications of this type of welding: Two pieces can be joined together (as shown in the illustration) or several pieces can be welded together in one block. Machine lap-welding is also employed for enlarging the diameter of a bar, this being accomplished by welding a U-shaped piece of rectangular stock to the end, and then upsetting the mass into the shape desired. An end plunger is used to upset the bar after the latter is securely held between the opposing faces of the gripping dies.

Pin-welding: In order to make a pin weld, the end of the bar is reduced and inserted in a hole in the part to which it is to be joined (see illustration). The reduced end is usually made from one-quarter to one-half the diameter of the original bar. The U-shaped piece, or other part which is to be joined to it, is generally made thicker where the weld is made, in order to strengthen the weld. The welding operation is effected by a plunger in the ram of the machine, which upsets the "pin" and at the same time forms the joint.

Butt-welding: This method of machine welding is not as common as the other two methods referred to, but is satisfactory when properly applied. To make a butt weld, it is not necessary to prepare the stock beforehand, although the pieces should have practically the desired shape. The weld is effected by a plunger having a pointed end which is forced through the forward member to be joined, thus closely pressing together the material and insuring a solid weld (see illustration).

This method of welding is not considered as practicable as pin-welding, but when properly handled, it is satisfactory for many classes of work. Wrought iron is welded in a forging machine without using any flux but the parts to be joined must be clean and free from scale. As a rule, compressed air is used to remove the scale formed by oxidization. A small jet of air is directed against the work just before the machine is operated. For welding steel having a comparatively high carbon content, it is necessary to use a flux to make a satisfactory weld. (See "Fluxes for Welding.")

Copyright 2004, Industrial Press, Inc., New York, NY

Hydraulic Press

Rules and Formulas for Hydraulic Press Calculations.— To find the total pressure of a hydraulic press when the diameter of the ram in inches and the water pressure (gage pressure) in pounds per square inch are given, multiply the area of the cross-section of the ram by the pressure per square inch, and divide by 2000. The result is the capacity of the hydraulic press in tons. The same result may be obtained as follows: Multiply the square of the diameter of the ram by the pressure per square inch, and multiply this product by 0.00039. The result is the total pressure of the press in tons.

The pressure per square inch on the material under pressure in the press can be determined when the total pressure of the press and the area of the material under pressure are known. Multiply the total pressure of the press in tons by 2000, and divide the product by the area of the material to be pressed. The quotient is the pressure in pounds per square inch on the surface of the material.

Table 74. Capacity of Hydraulic Presses

Diam. of Ram, Inches	Area of Ram, Sq. Ins.	Pressure in Pounds per Square Inch on End of Ram										
		2000	2100	2200	2300	2400	2500	2600	2700	2800	2900	3000
		Capacity of Hydraulic Press in Tons										
1	0.785	0.8	0.8	0.9	0.9	0.9	1.0	1.0	1.1	1.1	1.1	1.2
2	3.142	3.1	3.3	3.5	3.6	3.8	3.9	4.1	4.2	4.4	4.5	4.7
3	7.069	7.0	7.4	7.8	8.1	8.5	8.8	9.2	9.5	9.9	10.2	10.6
4	12.566	12.5	13	14.0	14.5	15.0	15.5	16.0	17.0	17.5	18.0	19
5	19.635	20	21	21.5	22.5	23.5	24.5	25.5	26.5	27.5	28.5	29
6	28.274	28	30	31	33	34	35	37	38	40	41	42
7	38.484	38	40	42	44	46	48	50	52	54	56	58
8	50.265	50	53	55	58	60	63	65	68	70	73	75
9	63.617	63	67	70	73	76	80	83	86	89	92	95
10	78.540	78	82	86	90	94	98	102	106	110	114	118
11	95.033	95	100	105	109	114	119	124	128	133	138	143
12	113.097	113	119	124	130	136	141	147	153	158	164	170
13	132.732	132	139	146	153	159	166	172	179	186	193	199
14	153.938	154	162	169	177	185	192	200	208	216	223	231
15	176.715	177	185	194	203	212	221	230	239	247	256	265
16	201.062	201	211	221	231	241	251	261	271	281	292	302
17	226.980	227	238	250	261	272	284	295	306	318	329	340
18	254.469	254	267	280	293	305	318	331	344	356	369	382
19	283.529	284	298	312	326	340	354	369	383	397	411	425
20	314.160	314	330	346	361	377	393	408	424	440	456	471
21	346.361	346	364	381	398	416	433	450	468	485	502	520
22	380.133	380	399	418	437	456	475	494	513	532	551	570
23	415.476	415	436	457	478	499	519	540	561	582	602	623
24	452.390	452	475	498	520	543	565	588	611	633	656	679
25	490.875	491	515	540	565	589	614	638	663	687	712	736
26	530.930	531	557	584	612	637	664	690	717	743	770	796
27	572.556	573	601	630	658	687	716	744	773	802	830	859
28	615.753	616	647	677	708	739	770	800	831	862	893	924
29	660.521	661	694	727	760	793	826	859	892	925	958	991
30	706.860	707	742	778	813	848	884	919	954	990	1025	1060

Copyright 2004, Industrial Press, Inc., New York, NY

Table 75. Capacity of Hydraulic Presses

Diam. of Ram, Inches	Area of Ram, Sq. Ins.	Pressure in Pounds per Square Inch on End of Ram									
		3100	3200	3300	3400	3500	3600	3700	3800	3900	4000
		Capacity of Hydraulic Press in Tons									
1	0.785	1.2	1.3	1.3	1.3	1.4	1.4	1.4	1.5	1.5	1.6
2	3.142	4.9	5.0	5.2	5.3	5.5	5.7	5.8	6.0	6.1	6.3
3	7.069	10.9	11.3	11.7	12.0	12.4	12.7	13.1	13.4	13.8	14.1
4	12.566	19.5	20	20.5	21	22	22.5	23	24	24.5	25
5	19.635	30	31	32	33	34	35	36	37	38	39
6	28.274	44	45	47	48	49	51	52	54	55	56
7	38.484	60	62	64	66	67	69	71	73	75	77
8	50.265	78	80	83	85	88	90	93	95	98	100
9	63.617	99	102	105	108	111	115	118	121	124	127
10	78.540	122	126	130	134	137	141	145	149	153	157
11	95.033	147	152	157	162	166	171	176	181	185	190
12	113.097	175	181	187	192	198	204	209	215	221	226
13	132.732	206	212	219	226	232	238	245	252	259	265
14	153.938	239	246	254	262	269	277	285	293	300	308
15	176.715	274	283	292	300	309	318	327	336	345	353
16	201.062	312	322	332	342	352	362	372	382	392	402
17	226.980	352	363	375	386	397	409	420	431	443	454
18	254.469	394	407	420	433	445	458	471	483	496	509
19	283.529	439	454	468	482	496	510	525	539	553	567
20	314.160	487	503	518	534	550	566	581	597	613	628
21	346.361	537	554	571	589	606	623	641	658	675	693
22	380.133	589	608	627	646	665	684	703	722	741	760
23	415.476	644	665	686	706	727	748	769	789	810	831
24	452.390	701	724	746	769	792	814	837	860	882	905
25	490.875	761	785	810	834	859	884	908	933	957	982
26	530.930	823	850	876	903	929	956	982	1009	1035	1062
27	572.556	887	916	945	973	1002	1031	1059	1088	1116	1145
28	615.753	954	985	1016	1047	1078	1108	1139	1170	1201	1232
29	660.521	1024	1057	1090	1123	1156	1189	1222	1255	1288	1321
30	706.860	1096	1131	1166	1202	1237	1272	1308	1343	1378	1414

When a certain pressure per square inch on the material under pressure is required, the gage pressure of the press necessary to obtain this pressure may be calculated as follows: Multiply the area of the surface under pressure by the pressure per square inch desired on the material. Divide this product by 0.7854 times the square of the diameter of the ram. The quotient will be the desired gage pressure.

Expressing these rules as formulas, let D = diameter of ram in inches; P = water pressure in pounds per square inch (gage pressure); C = total pressure or capacity of press in tons; A = area of material to be pressed, in square inches; P_a = pressure in pounds per square inch on material under pressure; then:

$$C = 0.00039D^2 \times P \quad P_a = \frac{2000C}{A} \quad P = \frac{A \times P_a}{0.7854D^2}$$

Copyright 2004, Industrial Press, Inc., New York, NY

SILENT OR INVERTED TOOTH CHAIN

Silent or inverted tooth chain consists of a series of toothed links alternately assembled either with pins or with a combination of joint components in such a way that the joints articulate between adjoining pitches. Side Guide chain has guide links which straddle the sprocket sides to control the chain laterally. Center Guide chain has guide links that run within a circumferential groove or grooves for lateral control.

Characteristics of Silent Chain Drives

The silent or "inverted-tooth" driving chain has the following characteristics: The chain passes over the face of the wheel like a belt and the wheel teeth do not project through it; the chain engages the wheel by means of teeth extending across the full width of the under side, with the exception of those chains having a central guide link; the chain teeth and wheel teeth are of such a shape that as the chain pitch increases through wear at the joints, the chain shifts outward upon the teeth, thus engaging the wheel on a pitch circle of increasing diameter; the result of this action is that the pitch of the wheel teeth increases at the same rate as the chain pitch. The accompanying illustration shows an unworn chain to the left, and a worn chain to the right, which has moved outward as the result of wear. Another distinguishing feature of the silent chain is that the power is transmitted by and to all the teeth in the arc of contact, irrespective of the increasing pitch due to elongation. The links have no sliding action either on or off the teeth, which results in a smooth and practically noiseless action, the chain being originally designed for the transmission of power at higher speeds than are suitable for roller chains. The efficiency of the silent chain itself may be as high as 99 per cent, and for the complete drive, from 96 to 97 percent, under favorable conditions; from 94 to 96 per cent can be secured with well-designed drives under average conditions.



The life and upkeep of silent chains depend largely upon the design of the entire drive, including the provision for adjustment. If there is much slack, the whipping of the chain will greatly increase the wear, and means of adjustment may double the life of the chain. A slight amount of play is necessary for satisfactory operation. The minimum amount of sag should be about $\frac{1}{8}$ inch. Although the silent chain shifts outward from the teeth and adjusts itself for an increase of pitch, it cannot take up the increased pitch in that portion of the chain between the wheels; therefore, the wheel must lag to the extent of the increased pitch in the straight portion of the chain.

Standard Silent Chain Designation.— The standard chain number or designation for $\frac{3}{8}$-inch pitch or larger consists of:

1) a two letter symbol SC; 2) one or two numerical digits indicating the pitch in eighths of an inch; and 3) two or three numerical digits indicating the chain width in quarter-inches.

Thus, SC302 designates a silent chain of $\frac{3}{8}$-inch pitch and $\frac{1}{2}$-inch width, while SC1012 designates a silent chain of $1\frac{1}{4}$-inch pitch and 3-inch width.

The standard chain number or designation for $\frac{3}{16}$-inch pitch consists of:

a) a two letter symbol SC; b) a zero followed by a numerical digit indicating pitch in sixteenths of an inch; and c) two numerical digits indicating the chain width in thirty-seconds of an inch. Thus, SC0309 designates a silent chain of $\frac{3}{16}$-inch pitch and $\frac{9}{32}$-inch width.

Copyright 2004, Industrial Press, Inc., New York, NY

Silent Chain Links.— The joint components and link contours vary with each manufacturer's design. As shown in Table 1 minimum crotch height and pitch have been standardized for interchangeability. Chain link designations for ⅜-inch and larger pitch are given in Table 1

Table 1. American National Standard Silent Chain Links*



Min.Crotch Height = 0.062 ×Chain Pitch.

Link contour may vary but must engage standard sprocket tooth so that joint centers lie on pitch diameter of sprockets.

Chain Number	Chain Pitch		Stamp	Crotch Height, Min.	
	inch	mm		inch	mm
SC3 (Width in ¼ in.)	0.375	9.52	SC3 or 3	0.0232	0.589
SC4 (Width in ¼ in.)	0.500	12.70	SC4 or 4	0.0310	0.787
SC5 (Width in ¼ in.)	0.625	15.88	SC5 or 5	0.0388	0.985
SC6 (Width in ¼ in.)	0.750	19.05	SC6 or 6	0.0465	1.181
SC8 (Width in ¼ in.)	1.000	25.40	SC8 or 8	0.0620	1.574
SC10 (Width in ¼ in.)	1.250	31.76	SC10 or 10	0.0775	1.968
SC12 (Width in ¼ in.)	1.500	38.10	SC12 or 12	0.0930	2.302
SC16 (Width in ¼ in.)	2.000	50.80	SC16 or 16	0.1240	3.149

Silent Chain Sprocket Diameters.— The important sprocket diameters are:

1) outside diameter; 2) pitch diameter; 3) maximum guide groove diameter; and

4) over-pin diameter.

These are shown in the diagram in Table 2 and the symbols and formulas for each are also given in this table. Table 3a gives values of outside diameters for sprockets with rounded teeth and with square teeth, pitch diameters, and over-pin diameters for chains of 1-inch pitch and sprockets of various tooth numbers. Values for chains of other pitches (⅜ inch and larger) are found by multiplying the values shown by the pitch. Table 3b gives this information for ³⁄₁₆- in. pitch chains. Note that the over-pin diameter is measured over gage pins having a diameter D_p=0.625P in. for ⅜-in. and larger pitch and D_p=0.667P in. for ³⁄₁₆-in. pitch chains. Over-pin diameter tolerances are given in Table 4a and 4b.

Silent Chain Sprocket Profiles and Chain Widths.— Sprocket tooth face profiles for side guide chain, center guide chain and double guide chain are shown in Table 4c and 4d together with important dimensions for chains of various pitches and widths. Maximum over-all width M of the three types of chain are also given in this table for various pitches and widths. It should be noted that the sprocket tooth width W for the side guide chain is given in Table 5 for one-half-inch wide chains of ⅜-inch and ½-inch pitches. No values of W for other chain sizes are specified in American National Standard B29.2M-1982 (1987).

* For ⅜-inch and larger pitch chains.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. ANSI Silent Chain Sprocket Diameters *(ANSI B29.2M-1982, R1987)*



P = Chain Pitch
PD = Pitch Diameter
OD = Outside Diameter
D_P = Gage Pin Diameter
N = Number of Teeth
E = Diameter to center of Topping Curve
OPD = Over Pin Diameter
G = Max. Guide Groove Diameter

$$PD = \frac{P}{\sin\frac{180^\circ}{N}}$$

$D_P = 0.625P$, for $\frac{3}{8}$ in. and larger pitch chain

[$= 0.667P$ for $\frac{3}{16}$ in. pitch chain]

$$\text{OPD (For Even No. of Teeth)} = PD - 0.125P\csc\left(30 - \frac{180}{N}\right)^\circ + 0.625P$$

$$\left[= PD - 0.160P\csc\left(30 - \frac{180}{N}\right)^\circ + 0.667P\right]$$

$$\text{OPD (For Odd No. of Teeth)} = \cos\frac{90^\circ}{N}\left[PD - 0.125P\csc\left(30 - \frac{180}{N}\right)^\circ\right] + 0.625P$$

$$\left[= \cos\frac{90^\circ}{N}\left[PD - 0.160P\csc\left(30 - \frac{180}{N}\right)^\circ\right] + 0.625P\right]$$

$$\text{OD (For Round Teeth)} = P\left(\cot\frac{180^\circ}{N} + 0.08\right)$$

$$\left[\text{OD (For Nominal Round Teeth)} = P\left(\cot\frac{180^\circ}{N} - 0.032\right)\right]$$

$$\text{OD (For Square Teeth)} = 2\sqrt{X^2 + L^2 - 2XL\cos\alpha}$$

Where

$$X = Y\cos\alpha - \sqrt{(0.15P)^2 - (Y\sin\alpha)^2}$$

$$Y = P(0.500 - 0.375\sec\alpha)\cot\alpha + 0.11P$$

$$L = Y + \frac{E}{2} \text{ (See Table 8A for E);}$$

$$\alpha = \left(30 - \frac{360}{N}\right)^\circ$$

$$G(\text{max.}) = P\left(\cot\frac{180^\circ}{N} - 1.16\right) \qquad \left[G(\text{max.}) = P\left(\cot\frac{180^\circ}{N} - 1.20\right)\right]$$

Tolerance= +0, –0.030 in. (0.76 mm) [Tolerance= +0, –0.015 in. (0.38 mm)][a]

[a] All inside [ ] bracket applies to $\frac{3}{16}$- inch pitch main. All other equations apply to $\frac{3}{8}$- inch and larger pitch chains.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3a. American National Standard Silent Chain Sprocket Diameters *ANSI B29.2M-1982, R1987*

These diameters apply only to chain of 1-inch pitch.
For any other pitch (⅜-inch and larger) multiply the values given below by the pitch.

No. Teeth	Pitch Diameter	Outside Diameter		Over Pin Diameter[a]	No. Teeth	Pitch Diameter	Outside Diameter		Over Pin Diameter
		Rounded Teeth[b]	Square Teeth[c]				Rounded Teeth	Square Teeth	
17	5.442	5.430	5.302	5.669	56	17.835	17.887	17.835	18.182
18	5.759	5.751	5.627	6.018	57	18.153	18.205	18.154	18.494
19	6.076	6.073	5.951	6.324	58	18.471	18.524	18.473	18.820
20	6.392	6.394	6.275	6.669	59	18.789	18.843	18.793	19.132
21	6.710	6.715	6.599	6.975	60	19.107	19.161	19.112	19.457
22	7.027	7.035	6.923	7.315	61	19.425	19.480	19.431	19.769
23	7.344	7.356	7.247	7.621	62	19.744	19.798	19.750	20.094
24	7.661	7.676	7.570	7.960	63	20.062	20.117	20.070	20.407
25	7.979	7.996	7.894	8.266	64	20.380	20.435	20.389	20.731
26	8.296	8.316	8.217	8.602	65	20.698	20.754	20.708	21.044
27	8.614	8.636	8.539	8.909	66	21.016	21.073	21.027	21.369
28	8.931	8.955	8.862	9.244	67	21.335	21.391	21.346	21.681
29	9.249	9.275	9.184	9.551	68	21.653	21.710	21.665	22.006
30	9.567	9.594	9.506	9.884	69	21.971	22.028	21.984	22.319
31	9.885	9.914	9.828	10.192	70	22.289	22.347	22.303	22.643
32	10.202	10.233	10.150	10.524	71	22.607	22.665	22.622	22.956
33	10.520	10.552	10.471	10.833	72	22.926	22.984	22.941	23.280
34	10.838	10.872	10.793	11.164	73	23.244	23.302	23.260	23.593
35	11.156	11.191	11.114	11.473	74	23.562	23.621	23.579	23.917
36	11.474	11.510	11.435	11.803	75	23.880	23.939	23.898	24.230
37	11.792	11.829	11.756	12.112	76	24.198	24.258	24.217	24.554
38	12.110	12.148	12.076	12.442	77	24.517	24.576	24.535	24.867
39	12.428	12.467	12.397	12.751	78	24.835	24.895	24.854	25.191
40	12.745	12.786	12.717	13.080	79	25.153	25.213	25.173	25.504
41	13.063	13.105	13.038	13.390	80	25.471	25.532	25.492	25.828
42	13.381	13.424	13.358	13.718	81	25.790	25.850	25.811	26.142
43	13.700	13.743	13.678	14.028	82	26.108	26.169	26.129	26.465
44	14.018	14.062	13.998	14.356	83	26.426	26.487	26.448	26.779
45	14.336	14.381	14.319	14.667	84	26.744	26.806	26.767	27.102
46	14.654	14.699	14.638	14.994	85	27.063	27.124	27.086	27.416
47	14.972	15.018	14.958	15.305	86	27.381	27.442	27.405	27.739
48	15.290	15.337	15.278	15.632	87	27.699	27.761	27.723	28.053
49	15.608	15.656	15.598	15.943	88	28.017	28.079	28.042	28.376
50	15.926	15.975	15.918	16.270	89	28.335	28.398	28.361	28.690
51	16.244	16.293	16.237	16.581	90	28.654	28.716	28.679	29.012
52	16.562	16.612	16.557	16.907	91	28.972	29.035	28.998	29.327
53	16.880	16.931	16.876	17.219	92	29.290	29.353	29.317	29.649
54	17.198	17.249	17.196	17.545	93	29.608	29.672	29.635	29.964
55	17.517	17.568	17.515	17.857	94	29.927	29.990	29.954	30.286
56	17.835	17.887	17.835	18.182	95	30.245	30.308	30.273	30.600

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3a. ***(Continued)*** **American National Standard Silent Chain Sprocket Diameters** *ANSI B29.2M-1982, R1987*

These diameters apply only to chain of 1-inch pitch. For any other pitch (⅜-inch and larger) multiply the values given below by the pitch.									
		Outside Diameter					Outside Diameter		
No. Teeth	Pitch Diameter	Rounded Teeth[b]	Square Teeth[c]	Over Pin Diameter[a]	No. Teeth	Pitch Diameter	Rounded Teeth	Square Teeth	Over Pin Diameter
96	30.563	30.627	30.591	30.923	125	39.793	39.860	39.830	40.153
97	30.881	30.945	30.910	31.237	126	40.111	40.179	40.148	40.475
98	31.200	31.264	31.229	31.560	127	40.429	40.497	40.467	40.790
99	31.518	31.582	31.547	31.874	128	40.748	40.815	40.785	41.112
100	31.836	31.901	31.866	32.197	129	41.066	41.134	41.104	41.427
103	32.791	32.856	32.822	33.148	130	41.384	41.452	41.422	41.748
104	33.109	33.174	33.140	33.470	131	41.703	41.771	41.741	42.064
105	33.428	33.493	33.459	33.785	132	42.021	42.089	42.059	42.385
106	33.746	33.811	33.778	34.107	133	42.339	42.407	42.378	42.700
107	34.064	34.129	34.096	34.422	134	42.657	42.726	42.696	43.022
108	34.382	34.448	34.415	34.744	135	42.976	43.044	43.015	43.337
109	34.701	34.766	34.733	35.059	136	43.294	43.362	43.333	43.658
110	35.019	35.085	35.052	35.381	137	43.612	43.681	43.652	43.974
111	35.337	35.403	35.371	35.696	138	43.931	43.999	43.970	44.295
112	35.655	35.721	35.689	36.017	139	44.249	44.318	44.289	44.611
113	35.974	36.040	36.008	36.332	140	44.567	44.636	44.607	44.932
114	36.292	36.358	36.326	36.654	141	44.885	44.954	44.926	45.248
115	36.610	36.677	36.645	36.969	142	45.204	45.273	45.244	45.569
116	36.928	36.995	36.963	37.291	143	45.522	45.591	45.563	45.884
117	37.247	37.313	37.282	37.606	144	45.840	45.909	45.881	46.205
118	37.565	37.632	37.600	37.928	145	46.159	46.228	46.199	46.521
119	37.883	37.950	37.919	38.243	146	46.477	46.546	46.518	46.842
120	38.202	38.268	38.237	38.565	147	46.795	46.864	46.836	47.158
121	38.520	38.587	38.556	38.880	148	47.113	47.183	47.155	47.479
122	38.838	38.905	38.874	39.201	149	47.432	47.501	47.473	47.795
123	39.156	39.224	39.193	39.517	150	47.750	47.820	47.792	48.115
124	39.475	39.542	39.511	39.838	…	…	…	…	…

[a] For tolerances on over-pin diameters, see table 4.

[b] Blank diameters are 0.020 inch larger and maximum guide groove diameters G are 1.240 inches smaller than these outside diameters.

[c] These diameters are maximum; tolerance is +0,–0.50× pitch, inches.

Tolerance for maximum eccentricity (total indicator reading) of pitch diameter with respect to bore is 0.001 × PD, but not less than 0.006 nor more than 0.032 inch.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. American National Standard Silent Chain Sprocket Diameters for 3/16-in. Pitch Chain *ANSI B29.2M-1982, R1987*

No. Teeth	Pitch Diameter	Outside Diameter		Over Pin Diameter[a]	No. Teeth	Pitch Diameter	Outside Diameter		Over Pin Diameter[a]
		Rounded Teeth[b]	Square Teeth[c]				Rounded Teeth[b]	Square Teeth[c]	
11	0.666	0.633	0.691	0.414	53	3.165	3.153	3.232	2.934
12	0.724	0.694	0.762	0.475	54	3.225	3.213	3.293	2.994
13	0.783	0.755	0.820	0.536	55	3.284	3.273	3.351	3.054
14	0.843	0.815	0.888	0.596	56	3.344	3.333	3.412	3.114
15	0.902	0.876	0.946	0.657	57	3.404	3.392	3.471	3.173
16	0.961	0.937	1.012	0.718	58	3.463	3.452	3.532	3.233
17	1.020	0.997	1.069	0.778	59	3.523	3.512	3.590	3.293
18	1.080	1.057	1.134	0.838	60	3.583	3.572	3.651	3.353
19	1.139	1.118	1.191	0.899	61	3.642	3.631	3.710	3.412
20	1.199	1.178	1.255	0.959	62	3.702	3.691	3.771	3.472
21	1.258	1.238	1.312	1.019	63	3.762	3.751	3.829	3.532
22	1.318	1.298	1.376	1.079	64	3.821	3.811	3.890	3.592
23	1.377	1.358	1.433	1.139	65	3.881	3.870	3.949	3.651
24	1.436	1.418	1.497	1.199	66	3.941	3.930	4.009	3.711
25	1.496	1.478	1.554	1.259	67	4.000	3.990	4.068	3.771
26	1.556	1.538	1.617	1.319	68	4.060	4.050	4.129	3.831
27	1.615	1.598	1.674	1.379	69	4.120	4.109	4.188	3.890
28	1.675	1.658	1.737	1.439	70	4.179	4.169	4.248	3.950
29	1.734	1.718	1.795	1.499	71	4.239	4.229	4.307	4.010
30	1.794	1.778	1.857	1.559	72	4.299	4.288	4.368	4.069
31	1.853	1.838	1.915	1.619	73	4.358	4.348	4.426	4.129
32	1.913	1.898	1.977	1.679	74	4.418	4.408	4.487	4.189
33	1.973	1.958	2.035	1.739	75	4.478	4.468	4.546	4.249
34	2.032	2.017	2.097	1.798	76	4.537	4.527	4.607	4.308
35	2.092	2.077	2.154	1.858	77	4.597	4.587	4.665	4.368
36	2.151	2.137	2.216	1.918	78	4.657	4.647	4.726	4.428
37	2.211	2.197	2.274	1.978	79	4.716	4.706	4.785	4.487
38	2.271	2.257	2.336	2.038	80	4.776	4.766	4.845	4.547
39	2.330	2.317	2.394	2.098	81	4.836	4.826	4.904	4.607
40	2.390	2.376	2.456	2.157	82	4.895	4.886	4.965	4.667
41	2.449	2.436	2.514	2.217	83	4.955	4.945	5.024	4.726
42	2.509	2.496	2.575	2.277	84	5.015	5.005	5.084	4.786
43	2.569	2.556	2.633	2.337	85	5.074	5.065	5.143	4.846
44	2.628	2.616	2.695	2.397	86	5.134	5.124	5.204	4.905
45	2.688	2.675	2.753	2.456	87	5.194	5.184	5.263	4.965
46	2.748	2.735	2.815	2.516	88	5.253	5.244	5.323	5.025
47	2.807	2.795	2.873	2.576	89	5.313	5.304	5.382	5.085
48	2.867	2.855	2.934	2.636	90	5.373	5.363	5.443	5.144
49	2.926	2.914	2.992	2.695	91	5.432	5.423	5.501	5.204
50	2.986	2.974	3.054	2.755	92	5.492	5.483	5.562	5.264
51	3.046	3.034	3.112	2.815	93	5.552	5.542	5.621	5.323
52	3.105	3.094	3.173	2.875	94	5.611	5.602	5.681	5.383

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3b. American National Standard Silent Chain Sprocket Diameters for 3/16-in. Pitch Chain *ANSI B29.2M-1982, R1987*

No. Teeth	Pitch Diameter	Outside Diameter Rounded Teeth[b]	Outside Diameter Square Teeth[c]	Over Pin Diameter[a]	No. Teeth	Pitch Diameter	Outside Diameter Rounded Teeth[b]	Outside Diameter Square Teeth[c]	Over Pin Diameter[a]
95	5.671	5.662	5.740	5.443	108	6.447	6.438	6.517	6.219
96	5.731	5.722	5.801	5.503	109	6.506	6.498	6.576	6.279
97	5.790	5.781	5.860	5.562	110	6.566	6.557	6.637	6.338
98	5.850	5.841	5.920	5.622	111	6.626	6.617	6.696	6.398
99	5.910	5.901	5.979	5.682	112	6.685	6.677	6.756	6.458
100	5.969	5.960	6.040	5.741	113	6.745	6.736	6.815	6.517
101	6.029	6.020	6.099	5.801	114	6.805	6.796	6.875	6.577
102	6.089	6.080	6.159	5.861	115	6.864	6.856	6.934	6.637
103	6.148	6.139	6.218	5.920	116	6.924	6.916	6.995	6.697
104	6.208	6.199	6.278	5.980	117	6.984	6.975	7.054	6.756
105	6.268	6.259	6.337	6.040	118	7.043	7.035	7.114	6.816
106	6.327	6.319	6.398	6.100	119	7.103	7.095	7.173	6.876
107	6.387	6.378	6.457	6.159	120	7.163	7.154	7.233	6.935

[a] For tolerances on over-pin diameters, see table 4.

[b] Blank diameters are 0.020 inch larger and maximum guide groove diameters G are 1.240 inches smaller than these outside diameters.

[c] These diameters are maximum; tolerance is +0,–0.50 × pitch, inches.

Tolerance for maximum eccentricity (total indicator reading) of pitch diameter with respect to bore is 0.004 in. up to and including 4 in. diameter; and 0.008 in., over 4 in. diameter.

Table 4a. Over-Pin Diameter Tolerances for American National Standard 3/8- in. Pitch and Larger Silent Chain Sprocket Measurement *ANSI B29.2M-1982, 1987*

Pitch	Number of Teeth: Up to 15	16-24	25-35	36-48	49-63	64-80	81-99	100-120	121-143	144 up
Tolerance,[a] Inches										
0.375	0.005	0.006	0.006	0.006	0.007	0.007	0.008	0.008	0.008	0.009
0.500	0.006	0.006	0.007	0.007	0.008	0.008	0.009	0.009	0.010	0.010
0.625	0.006	0.007	0.007	0.008	0.009	0.009	0.010	0.011	0.011	0.012
0.750	0.006	0.007	0.008	0.009	0.010	0.010	0.011	0.012	0.013	0.013
1.000	0.008	0.009	0.010	0.011	0.012	0.013	0.014	0.015	0.016	0.016
1.250	0.008	0.009	0.010	0.012	0.013	0.015	0.016	0.017	0.018	0.019
1.500	0.009	0.010	0.012	0.014	0.015	0.017	0.018	0.020	0.021	0.022
2.000	0.012	0.014	0.017	0.019	0.021	0.023	0.025	0.027	0.028	0.028
Tolerances, Millimeters										
9.52	0.13	0.13	0.13	0.15	0.15	0.18	0.18	0.18	0.20	0.20
2.70	0.13	0.15	0.15	0.18	0.18	0.20	0.20	0.23	0.23	0.25
15.88	0.15	0.15	0.18	0.20	0.23	0.25	0.25	0.25	0.28	0.30
19.05	0.15	0.18	0.20	0.23	0.25	0.28	0.28	0.30	0.33	0.36
25.40	0.18	0.20	0.23	0.25	0.28	0.30	0.33	0.36	0.38	0.40
31.75	0.20	0.23	0.25	0.28	0.33	0.36	0.38	0.43	0.46	0.48
38.10	0.20	0.25	0.28	0.33	0.36	0.40	0.43	0.48	0.51	0.56
50.80	0.25	0.30	0.36	0.40	0.46	0.51	0.56	0.61	0.66	0.71

[a] All tolerances are negative. Tolerances $= (0.004 + 0.001P\sqrt{N})$, where P= chain pitch, N= number of teeth. See 3A for over pin diameters.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4b. Over-Pin Diameter Tolerances for ANSI $^{3}/_{16}$- in. Pitch and Larger Silent Chain Sprocket Measurement *(ANSI B29.2M-1982, R1987)*

Pitch	Number of Teeth									
	Up to 15	16 - 24	25 - 35	36 - 48	49 - 63	64 - 80	81 - 99	100 - 120	121-143	144 up
	Tolerances,[a] Inches									
0.1875	0.004	0.004	0.004	0.004	0.004	0.005	0.005	0.005	0.005	0.005
	Tolerances,[a] Millimerers									
4.76	0.10	0.10	0.10	0.10	0.10	0.13	0.13	0.13	0.13	0.13

[a] All tolerances are negative.



Grooving tool may be either square or round end but groove must be full width down to diameter of *G*. For values of *G* (max.) see footnote to Table 3a

Values of H (± 0.003 in.) = 0.051 in. are given only for chain numbers SC302 and SC402. M = Max. overall width of chain. The maximum radius over a new chain engaged on a sprocket will not exceed the sprocket pitch radius plus 75 per cent of the chain pitch. To obtain the chain widths and sprocket face dimensions in millimeters, multiply each entry by 25.4.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4c. ANSI ⅜- in. Pitch and Larger Silent Chain Widths and Sprocket Face Dimensions *(ANSI B29.2M-1982, R1987)*

Chain No	Chain Pitch	Type	M[a] Max.	A	C ±0.005	D ±0.010	F +0.125 −0.000	R ±0.003	W +0.010 −0.000
SC302	0.375	Side Guide[b]	0.594	0.133	...	…	…	0.200	0.410
SC303		Center Guide	0.844		0.100	…	0.750		…
SC304			1.094			…	1.000		…
SC305			1.344			…	1.250		…
SC306			1.594			…	1.500		…
SC307			1.844			…	1.750		…
SC308			2.094			…	2.000		…
SC309			2.344			…	2.250		…
SC310			2.594			…	2.500		…
SC312		Double-Guide	3.094			1.000	3.000		…
SC316			4.094				4.000		…
SC320			5.094				5.000		…
SC324			6.094				6.000		…
SC402	0.500	Side Guide[b]	0.750	0.133	…	…	...	0.200	0.410
SC403		Center Guide	0.875		0.100	…	0.750		…
SC404			1.125			…	1.000		…
SC405			1.375			…	1.250		…
SC406			1.625			…	1.500		…
SC407			1.875			…	1.750		…
SC408			2.125			…	2.000		…
SC409			2.375			…	2.250		…
SC410			2.625			…	2.500		…
SC411			2.875			…	2.750		…
SC412			3.125			…	3.000		…
SC414			3.625			…	3.500		…
SC416		Double-Guide	4.125			1.000	4.000		…
SC420			5.125				5.000		…
SC424			6.125				6.000		…
SC432			8.125				8.000		…
SC504	0.625	Center-Guide	1.156	0.177		…	1.000	0.250	…
SC505			1.406			…	1.250		…
SC506			1.656				1.500		…
SC507			1.906				1.750		…
SC508			2.156				2.000		…
SC510			2.656				2.500		…
SC512			3.156		0.125		3.000		…
SC516			4.156				4.000		…
SC520		Double-Guide	5.156				5.000		…
SC524			6.156				6.000		…
SC528			7.156			2.000	7.000		…
SC532			8.156				8.000		…
SC540			10.156				10.000		…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4c. ***(Continued)*** **ANSI ⅜- in. Pitch and Larger Silent Chain Widths and Sprocket Face Dimensions** *(ANSI B29.2M-1982, R1987)*

Chain No	Chain Pitch	Type	M[a] Max.	A	C ±0.005	D ±0.010	F +0.125 −0.000	R ±0.003	W +0.010 −0.000
SC604	0.750	Center-Guide	1.187	0.274	0.180	…	1.000	0.360	…
SC605			1.437			…	1.250		…
SC606			1.687			…	1.500		…
SC608			2.187			…	2.000		…
SC610			2.687			…	2.500		…
SC612			3.187			…	3.000		…
SC614			3.687			…	3.500		…
SC616			4.187			…	4.000		…
SC620			5.187			…	5.000		…
SC624			6.187			4.000	6.000		…
SC628		Double guide	7.187				7.000		…
SC632			8.187				8.000		…
SC636			9.187				9.000		…
SC640			10.187				10.000		…
SC648			12.187				12.000		…
SC808	1.000	Center Guide	2.250	0.177	0.125	…	2.000	0.250	…
SC810			2.750			…	2.500		…
SC812			3.250			…	3.000		…
SC816			4.250			…	4.000		…
SC820			5.250			…	5.000		…
SC824			6.250			…	6.000		…
SC828			7.250			…	7.000		…
SC832		Double guide	8.250			…	8.000		…
SC836			9.250			2.000	9.000		…
SC840			10.250				10.000		…
SC848			12.250				12.000		…
SC856			14.250				14.000		…
SC864			16.250				16.000		…
SC1010	1.25	Center Guide	2.812	0.274	0.180	…	2.500	0.360	…
SC1012			3.312			…	3.000		…
SC1016			4.312			…	4.000		…
SC1020			5.312			…	5.000		…
SC1024			6.312			…	6.000		…
SC1028			7.312			…	7.000		…
SC1032		Double guide	8.312			4.000	8.000		…
SC1036			9.312				9.000		…
SC1040			10.312				10.000		…
SC1048			12.312				12.000		…
SC1056			14.312				14.000		…
SC1064			16.312				16.000		…
SC1072			18.312				18.000		…
SC1080			20.312				20.000		…

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4c. ***(Continued)*** **ANSI ⅜- in. Pitch and Larger Silent Chain Widths and Sprocket Face Dimensions** *(ANSI B29.2M-1982, R1987)*

Chain No	Chain Pitch	Type	M[a] Max.	A	C ±0.005	D ±0.010	F +0.125 −0.000	R ±0.003	W +0.010 −0.000
SC1212	1.500	Center Guide	3.375	0.274	0.180	…	3.000	0.360	…
SC1216			4.375			…	4.000		…
SC1220			5.375			…	5.000		…
SC1224			6.375			…	6.000		…
SC1228			7.375			…	7.000		…
SC1232		Double guide	8.375			…	8.000		…
SC1236			9.375			4.000	9.000		…
SC1240			10.375				10.000		…
SC1248			12.375				12.000		…
SC1256			14.375				14.000		…
SC1264			16.375				16.000		…
SC1272			18.375				18.000		…
SC1280			20.375				20.000		…
SC1288			22.375				22.000		…
SC1296			24.375				24.000		…
SC1616	2.000	Center Guide	4.500	0.274	0.218	…	4.000	0.360	…
SC1620			5.500			…	5.000		…
SC1624			6.500			…	6.000		…
SC1628			7.500			4.000	7.000		…
SC1632		Double guide	8.500				8.000		…
SC1640			10.500				10.000		…
SC1648			12.500				12.000		…
SC1656			14.500				14.000		…
SC1664			16.500				16.000		…
SC1672			18.500				18.000		…
SC1680			20.500				20.000		…
SC1688			22.500				22.000		…
SC1696			24.500				24.000		…
SC16120			30.500				30.000		…

[a] Specify side guide or center guide type.
[b] Side Guide chains have single outside guides of same thickness as toothed links.
All dimensions in inches. M Max. overall width of chain.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4d. American National Standard 3/16- in. Pitch and Larger Silent Chain Widths and Sprocket Face Dimensions *ANSI B29.2M-1982,1987*



Values of H = 0.025 in. are given for chain numbers SC0305 through SC0315.

Chain No	Chain Pitch	Type	M Max.	A	C Max.	F Min.	R	W ±0.003
SC0305	0.1875	Side Guide	0.216	0.06	...	…	0.09	0.075
SC0307			0.278		...	…		0.138
SC0309			0.341		...	…		0.201
SC0311		Side Guide/ Center Guide	0.403		0.050	0.334		0.264
SC0313			0.466			0.396		0.327
SC0315			0.528			0.459		0.390
SC0317		Center Guide	0.591			0.521		…
SC0319			0.653			0.584		…
SC0321			0.716			0.646		…
SC0323			0.778			0.709		…
SC0325			0.850			0.771		…
SC0327			0.903			0.834		
SC0329			0.966			0.896		…
SC0331			1.028			0.959		…

All dimensions in inches. M = Max. overall width of chain.

To obtain chain width and sprocket face dimensions in millimeters, multiply each entry by 25.4.

Sprocket Hub Dimensions.— The important hub dimensions are the outside diameter, the bore, and the length. The maximum hub diameter is limited by the need to clear the chain guides and is of particular importance for sprockets with low numbers of teeth. The American National Standard for inverted tooth chains and sprocket teeth ANSI B29.2M-1982 (R1987) provides the following formulas for calculating maximum hub diameters, *MHD*.

$$MHD(\text{for hobbed teeth}) = P\left[\cot\left(\frac{180°}{N}\right) - 1.33\right]$$

$$MHD(\text{for stradle cut teeth}) = P\left[\cot\left(\frac{180°}{N}\right) - 1.25\right]$$

Copyright 2004, Industrial Press, Inc., New York, NY

Maximum hub diameters for sprockets with from 17 to 31 teeth are given in Table 5. Maximum hub diameters for other methods of cutting teeth may differ from thesevalues. Recommended maximum bores are given in Table 6.

Table 5. American National Standard Minimum Hub Diameters for Silent chain Sprockets (17 to 31 Teeth) *ANSI B29.2M-1982,1987*

No. Teeth	Hob cut	Straddle Cut	No. Teeth	Hob cut	Straddle Cut	No. Teeth	Hob cut	Straddle Cut
	Min. Hub Diam.			Min. Hub Diam.			Min. Hub Diam.	
17	4.019	4.099	22	5.626	5.706	27	7.226	7.306
18	4.341	4.421	23	5.946	6.026	28	7.546	7.626
19	4.662	4.742	24	6.265	6.345	29	7.865	7.945
20	4.983	5.063	25	6.586	6.666	30	8.185	8.265
21	5.304	5.384	26	6.905	6.985	31	8.503	8.583

All dimensions in inches.

Values shown are 1-inch pitch chain. For other pitches (⅜- inch and larger) multiply the values given by the pitch.

Good practice indicates that teeth of sprockets up to and including 31 teeth should have a Rockwell hardness of *C*50 min.

Table 6. Recommended maximum Sprocket Bores for Silent Chains

Number of Teeth	Chain Pitch, Inches							
	⅜	½	⅝	¾	1	1¼	1½	2
	Maximum Sprocket Bore. Inches							
17	1	1⅜	1¾	2	2¾	3⅜	4⅛	5¼
19	1¼	1⅝	2	2⅜	3¼	4	4⅞	6¾
21	1⅜	1⅞	2¼	2¾	3¾	4½	5½	7¾
23	1⅝	2⅛	2⅝	3¼	4⅜	5½	6½	9
25	1¾	2⅜	3	3⅝	4¾	6	7¼	10
27	2	2⅝	3⅜	3⅞	5⅜	6¾	8⅛	11¼
29	2⅛	2 13/16	3⅝	4⅜	5¾	7⅜	9⅛	12¼
31	2 5/16	3 1/16	3⅞	4⅝	6⅜	8	9⅞	13¼

American Chain Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7a. Tooth Form for ANSI 3/8- inch and larger Silent Tooth Sprocket
ANSI B29.2M-1982, R1987



P = Chain Pitch

N = Number of Teeth

E = Diameter to Center of Topping Curve

$$E = P\left(\cot\frac{180°}{N} - 0.22\right)$$

B = Diameter to Base of Working Face

$$B = P\sqrt{1.515213 + \left(\cot\frac{180°}{N} - 1.1\right)^2}$$

Table 7b. Tooth Form for ANSI 3/16- inch and larger Silent Tooth Sprocket *ANSI B29.2M-1982, R1987*



Copyright 2004, Industrial Press, Inc., New York, NY

Table 8. Straddle Cutters for American National Standard $\frac{3}{8}$- in. Pitch and Larger Silent Chain Sprocket Teeth



Chain Pitch P	Mark Cutter[a]	Outside Diam.	0.75P	α	θ	Bore[b]
0.375	SC3-15 thru 35 SC3-36 up	3.625	0.2813	22°-30′ 27°-30′	12° 5°	1.250
0.500	SC4-15 thru 35 SC4-36 up	3.875	0.3750	22°-30′ 27°-30′	12° 5°	1.250
0.625	SC5-15 thru 35 SC5-36 up	4.250	0.4688	22°-30′ 27°-30′	2° 5°	1.250
0.750	SC6-15 thru 35 SC6-36 up	4.625	0.5625	22°-30′ 27°-30′	12° 5°	1.250
1.000	SC8-15 thru 35 SC8-36 up	5.250	0.7500	22°-30′ 27°-30′	12° 5°	1.500
1.250	SC10-15 thru 35 SC10-36 up	5.750	0.9375	22°-30′ 27°-30′	12° 5°	1.500
1.500	SC12-15 thru 35 SC12-36 up	6.250	1.1250	22°-30′ 27°-30′	12° 5°	1.750
2.000	SC16-15 thru 35 SC16-36 up	6.500	1.5000	22°-30′ 27°-30′	12° 5°	1.750

[a] Range of teeth is indicated in the cutter marking.

[b] Suggested standard. Bores other than standard must be specified.

All dimensions in inches. To obtain values in millimeters, multiply inch values by 25.4.

These data are given as supplementary information in ANSI B29.2M-1982, R1987 and are made available by the American Chain Association.



Fig. 3. Identification of Inverted Tooth Chain Hobs.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 9. Hobs for ANSI ⅜- inch and larger Silent Tooth Sprocket*



P = Chain Pitch

N = Number of Teeth

$$HGD = P\left(\frac{1}{\sqrt{\sin\frac{180°^2}{N}}} + 0.5625 - \frac{1.5\sin\left(30 - \frac{180}{N}\right)^\circ}{\sin\frac{180°}{N}}\right)$$

Sprocket Design and Tooth Form.— Except for tooth form, silent chain sprocket design parallels the general design practice of roller chain sprockets as covered in the previous section.

As shown in Tables 7a and 7b, sprockets for American National Standard silent chains have teeth with straight-line working faces. The tops of teeth for ⅜-in. and larger pitch chains may be rounded or square. Bottom clearance below the working face is not specified but must be sufficient to clear the chain teeth. The standard tooth form for ⅜-in. and larger pitch chains is designed to mesh with link plate contours having an included angle of 60 degrees as shown in the diagram of Table 7a. The standard tooth form for 3/16-in. pitch chains has an included angle of 70 degrees as shown in Table 7b. It will be seen from these tables that the angle between the faces of a given tooth [60°–720°/*N* for ⅜-in. pitch and larger; 70°–720°/*N* for 3/16-in. pitch] becomes smaller as the number of teeth decreases. Therefore, for a ⅜-in. pitch or larger 12-tooth sprocket it will be zero. In other words the tooth faces will be parallel.

For smaller tooth numbers the teeth would be undercut. For best results, 21 or more teeth are recommended; less than 17 should not be used.

Cutting Silent Chain Sprocket Teeth.— Sprocket teeth may be cut by either a straddle cutter or a hob. Essential dimensions for straddle cutters are given in Table 8 and for hobs in Table 9 and 10. American National Standard silent chain hobs are stamped for identification as shown on page 2375.

* Source: American Chain Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 10. Hobs for American National Standard ⅜- in. Pitch and Larger Silent Chain Sprocket Teeth*

Chain Pitch	Hob Number	Basic Number of Teeth	Tooth Range of Hob	Generating Diameter	
				Inches	Millimeters
SC3 = 0.375 in. = 9.52 mm	1	20	17 - 23	2.311	58.70
	2	28	24 - 32	3.247	82.47
	3	38	33 - 43	4.428	112.47
	4	51	44 - 58	5.971	151.66
	5	69	29 - 79	8.114	206.10
	6	95	80 - 110	11.212	284.78
	7	130	111 - 150	15.385	390.78
SC4 = 0.500 in. = 12.70 mm	1	20	17 - 23	3.082	78.28
	2	28	24 - 32	4.329	109.96
	3	38	33 - 43	5.904	149.96
	4	51	44 - 58	7.962	202.23
	5	69	29 - 79	10.818	274.78
	6	95	80 - 110	14.950	379.73
	7	130	111 - 150	20.513	521.03
SC5 = 0.625in. = 15.88 mm	1	20	17 - 23	3.852	97.84
	2	28	24 - 32	5.412	137.46
	3	38	33 - 43	7.381	187.48
	4	51	44 - 58	9.952	252.78
	5	69	29 - 79	13.522	343.46
	6	95	80 - 110	18.687	474.65
	7	130	111 - 150	25.641	651.28
SC6 = 0.750 in. = 19.05 mm	1	20	17 - 23	4.623	117.42
	2	28	24 - 32	6.494	164.95
	3	38	33 - 43	8.857	224.97
	4	51	44 - 58	11.943	303.35
	5	69	29 - 79	16.227	412.17
	6	95	80 - 110	22.424	569.57
	7	130	111 - 150	30.770	781.56
SC8 = 1.000 in. = 25.40 mm	1	20	17 - 23	6.163	156.54
	2	28	24 - 32	8.659	219.94
	3	38	33 - 43	11.809	299.95
	4	51	44 - 58	15.924	404.47
	5	69	29 - 79	21.636	549.55
	6	95	80 - 110	29.899	759.43
	7	130	111 - 150	41.026	1042.06
SC10 = 1.250 in. = 31.75 mm	1	20	17 - 23	7.704	195.68
	2	28	24 - 32	10.823	274.90
	3	38	33 - 43	14.761	374.93
	4	51	44 - 58	19.905	505.59
	5	69	29 - 79	27.045	686.94
	6	95	80 - 110	37.374	949.30
	7	130	111 - 150	51.283	1302.59
SC12 = 1.500 in. = 9.52 mm	1	20	17-23	9.245	234.82
	2	28	24 - 32	12.988	329.90
	3	38	33 - 43	17.713	449.91
	4	51	44 - 58	23.886	606.70
	5	69	29 - 79	32.454	824.33
	6	95	80 - 110	44.849	1139.16
	7	130	111 - 150	61.539	1563.09
SC16= 2.000 in. = 50.80 mm	1	20	17 - 23	12.327	313.11
	2	28	24 - 32	17.317	439.85
	3	38	33 - 43	23.618	599.90
	4	51	44 - 58	31.848	808.94
	5	69	29 - 79	43.272	1099.11
	6	95	80 - 110	59.798	1518.87
	7	130	111 - 150	82.052	2.84.12

* Source: American Chain Association.

Copyright 2004, Industrial Press, Inc., New York, NY

Design of Silent Chain Drives.— The design of silent chain transmissions must be based not only upon the power to be transmitted and the ratio between driving and driven shafts, but also upon such factors as the speed of the faster running shaft, the available space, assuming that it affects the sprocket diameters, the character of the load and certain other factors. Determining the pitch of the chain and the number of teeth on the smallest sprocket are the important initial steps. Usually any one of several combinations of pitches and sprocket sizes may be employed for a given installation. In attempting to select the best combination, it is advisable to consult with the manufacturer of the chain to be used. Some of the more important fundamental points governing the design of silent chain transmissions will be summarized.

The design of a silent chain drive consists, primarily, of the selection of the chain size, sprockets, determination of chain length, center distance, lubrication method, and arrangement of casings.

Pitch of Silent Chain.— The pitch is selected with reference to the speed of the faster running shaft which ordinarily is the driver and holds the smaller sprocket. The following pitches are recommended: for a faster running shaft of 2000 to 5000 rpm, $\frac{3}{8}$-inch pitch; for 1500 to 2000 rpm, $\frac{1}{2}$-inch pitch; for 1200 to 1500 rpm, $\frac{5}{8}$-inch pitch, for 1000 to 1200 rpm, $\frac{3}{4}$-inch pitch; for 800 to 1000 rpm, 1-inch pitch; for 650 to 800 rpm, $1\frac{1}{4}$-inch pitch; for 300 to 600 rpm, $1\frac{1}{2}$-inch pitch; for 300 to 500 rpm, 2-inch pitch; and for below 300 rpm, $2\frac{1}{2}$-inch pitch. As the normal operating speeds increase, the allowable pitch decreases. Recommendations relating to the relationship between pitch and operating speed are intended for normal or average conditions. Speeds for a given pitch may be exceeded under favorable conditions and may have to be reduced when conditions are unfavorable. In general, smoother or quieter operation will result from using the smallest pitch suitable for a given speed and load. However, a larger pitch which might be applicable under the same conditions, will result in a narrower chain and a less expensive transmission. This relationship usually is true when there is a small speed reduction and comparatively long center distance. If there is a large speed reduction and short center distance, drives having the smaller pitches may be less expensive.

Maximum Ratios for Silent Chain Drives.— The maximum permissible ratios between driving and driven sprockets vary somewhat for different conditions and usually range from 6- or 7-to-1 up to 10-to-1. Some drives have even higher ratios, especially when the operating conditions are exceptionally favorable. When a large speed reduction is necessary, it is preferable as a general rule to use a double reduction or compound type of transmission instead of obtaining the entire reduction with two sprockets. Drives should be so proportioned that the angle between the two strands of a tight chain does not exceed 45 degrees. When the angle is larger, the chain does not have sufficient contact with the driving sprocket.

Sprocket Size and Chain Speed: A driving sprocket with not less than 17 teeth is generally recommended. For the driven sprocket, one manufacturer recommends 127 teeth as a maximum limit and less than 100 as preferable. If practicable, the sprocket sizes should be small enough to limit the chain speed to from 1200 to 1400 feet per minute. If the chain speed exceeds these figures, this may indicate that the pitch is too large or that a smaller pitch, and, consequently, a reduction in sprocket diameters (and chain speed) will result in better operating conditions. Both sprockets should preferably have a "hunting tooth ratio" relative to the number of chain links for uniform wear. See "Hunting Tooth Ratios," page 1867.

If there is a small reduction in speed between the driving and driven shafts, both sprockets may be made as small as is consistent with satisfactory operation, either to obtain a compact drive or possibly to avoid excessive chain speed in cases where the rotative speed is high for a given horsepower. Under such conditions, one manufacturer recommends driving sprockets ranging from 17 to 30 teeth, and driven sprockets ranging from 19 to 33

Copyright 2004, Industrial Press, Inc., New York, NY

teeth. If the number of revolutions per minute is low for a given horsepower and the center distance comparatively long, then the recommended range for driving sprockets is from 23 to iii teeth, and driven sprockets from 27 to 129 teeth. The preferable range is from 17 to 75 teeth for the driving sprockets, and 19 to 102 teeth for the driven sprockets.

Center Distance for Silent Chain Drives.— If the ratio of the drive is small, it is possible to locate the sprockets so close-that the teeth just clear; however, as a general rule, the minimum center-to-center distance should equal the sum of the diameters of both sprockets. According to the Whitney Chain & Mfg. Co., if the speed ratio is not over 2½-to-1, the center distance may be equal to one-half the sum of the sprocket diameters plus tooth clearance, providing this distance is not less than the minimum given in Table 11. If the speed ratio is greater than 2½-to-1, the center distance should not be less than the sum of the sprocket diameters.

Table 11. Minimum Center Distancesfor Various Pitches

Pitch, inches	⅜	½	⅝	¾	1	1¼	1½
Minimum Center Distances, inches	6	9	12	15	21	27	33

When the chain length in pitches is known, the equivalent center distance for a tight chain may be determined by the formula for roller chain found on page 2348.

In selecting chain length, factors determining length should be adjusted so that the use of offset links may be avoided wherever possible. Chain lengths of an uneven number of pitches are also to be avoided.

Silent Tooth Chain Horsepower Capacity.— The horsepower ratings given in Tables 12a, 12b, and 12c have been established on a life expectancy of approximately 15,000 hours under optimum drive conditions, i.e. for a uniform rate of work where there is relatively little shock or load variation throughout a single revolution of a driven sprocket. Using these horsepower ratings as a basis, engineering judgment should be exercised as to the severity of the operating conditions for the intended installation, taking into consideration the source of power, the nature of the load, and the resulting effects of inertia, strain, and shock. Thus, for other than optimum drive conditions, the specified horsepower must be multiplied by the applicable service factor to obtain a "design" horsepower value. This is the value used to enter Table 13 to obtain the required size of chain.

Service Factors: For a uniform type of load, a service factor of 1.0 for a 10-hour day and 1.3 for a 24-hour day are recommended. For a moderate shock load, service factors of 1.4 for a 10-hour day and 1.7 for a 24-hour day are recommended. For heavy shock loads, service factors of 1.7 for a 10-hour day and 2.0 for a 24-hour day are recommended. For extensive table of service factor applications, see supplementary information in ANSI B29.2M-1982.

Installation of Silent Chain Drives.— In installing chain transmissions of any kind, horizontal drives are .those having driving and driven shafts in a horizontal plane. These are always preferable to vertical drives, which have a vertical center line intersecting the driving and driven shafts. If one sprocket must be higher than the other, avoid a vertical drive if possible by so locating the two sprockets that the common center line inclines from the vertical as far as is permitted by other conditions which might govern the installation. If practicable, an adjustment should be provided for the center distance between the driving and driven shafts.

Slack Side of Chain: As a general rule, the slack strand of a chain should be on the lower side of a horizontal drive. If the drive is not horizontal but angular or at some angle less than 90 degrees from the vertical, the slack should preferably be on that side which causes the strand to curve outward or away from the center line of the driving and driven shafts. Whenever the slack strand is on the upper side of either a horizontal or inclined dnve,

Copyright 2004, Industrial Press, Inc., New York, NY

adjustment for the center distance is especially important to compensate for possible chain elongation.

Lubrication: The life of a silent chain subjected to conditions such as are common to automobile drives, depends largely upon the wear of the joints. On account of the high speed and whipping action, it is important to have the chains well oiled. When splash lubrication is employed, the supply pipe should be placed so that the oil will be directed against the inside of the chain. It is preferable that silent chains be operated in an oil-retaining casing with provisions for lubrication. Avoid using greases of any kind. The viscosity of the oil depends on temperature, as follows:

Ambient Temp. °F	Chain Pitch		Ambient Temp. °F	Chain Pitch	
	3/16 & 3/8 inch	1/2 inch & larger		3/16 & 3/8 inch	1/2 inch & larger
	Recommended Lubricant			Recommended Lubricant	
20-40	SAE 10	SAE 20	20-40	SAE 10	SAE 20
40-100	SAE 20	SAE 30	40-100	SAE 20	SAE 30

Double-Flexure Silent Chain.— In double-flexure chain, the teeth of the link plates project on both sides of the chain and the chain flexes in both directions. This chain is used where the drive arrangements require that sprockets contact both sides of the chain. Neither double-flexure chain nor sprockets are covered in American National Standard ANSI 29.2M-1982.

Horsepower Ratings Per Inch of Chain Width for Silent Chain Drives — 1982.— The following industrial standard horsepower ratings for silent chain drives have been supplied by the American Chain Association. These ratings are for American National Standard silent chain as covered by ANSI B29.2M-1982. These values may require modification by using the appropriate service factors (see page 2379). These factors, which apply to typical drives, are intended as a general guide only, and engineering judgment and experience may indicate different modifications to suit the nature of the load.

$$\text{Horsepower capacity of chain per inch of width} = \frac{\text{Rating in Table 12A,12B}}{\text{Service Factor}}$$

$$\text{chainwidth for given total hp capacity} = \frac{\text{hp} \times \text{Service factor}}{\text{Rating per inch, Table 12A, 12B}}$$

Lubrication: The horsepower established from the sprocket and speed combinations of the drive under consideration will indicate a method of lubrication. This method or a better one must be used to obtain optimum chain life. The types of lubrication as indicated on the tables are: Type I, manual, brush, or oil cup; Type II, bath or disk; Type III, circulating pump.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12a. Horse Power Ratings per Inch of Chain Width for Silent Chain Drives –1982

No. of Teeth Small Sprkt.	3/16- Inch Pitch Chain											
	Revolutions per Minute—Small Sprocket											
	500	600	700	800	900	1200	1800	2000	3500	5000	7000	9000
15	0.28	0.33	0.38	0.43	0.47	0.60	0.80	0.90	1.33	1.66	1.94	1.96
17	0.33	0.39	0.44	0.50	0.55	0.70	0.96	1.05	1.60	2.00	2.40	2.52
19	0.37	0.43	0.50	0.55	0.61	0.80	1.10	1.20	1.80	2.30	2.76	2.92
21	0.41	0.48	0.55	0.62	0.68	0.87	1.22	1.33	2.03	2.58	3.12	3.35
23	0.45	0.53	0.60	0.68	0.75	0.96	1.35	1.47	2.25	2.88	3.50	3.78
25	0.49	0.58	0.66	0.74	0.82	1.05	1.47	1.60	2.45	3.13	3.80	4.10
27	0.53	0.62	0.71	0.80	0.88	1.15	1.58	1.72	2.63	3.35	4.06	4.37
29	0.57	0.67	0.76	0.86	0.95	1.21	1.70	1.85	2.83	3.61	4.40	4.72
31	0.60	0.72	0.81	0.91	1.01	1.30	1.81	1.97	3.02	3.84	4.66	5.00
33	0.64	0.75	0.86	0.97	1.07	1.37	1.90	2.08	3.17	4.02	4.85	…
35	0.68	0.80	0.92	1.03	1.14	1.45	2.03	2.21	3.41	4.27	5.16	…
37	0.71	0.84	0.96	1.08	1.19	1.52	2.11	2.30	3.48	4.39	5.24	…
40	0.77	0.91	1.04	1.16	1.29	1.64	2.28	2.50	3.77	4.76	…	…
45	0.86	1.02	1.15	1.30	1.43	1.83	2.53	2.75	4.15	5.21	…	…
50	0.95	1.12	1.27	1.37	1.58	2.00	2.78	3.02	4.52	5.65	…	…
	Type I						Type II			Type III		

No. of Teeth Small Sprkt.	3/8- Inch Pitch Chain												
	Revolutions per Minute—Small Sprocket												
	100	500	1000	1200	1500	1800	2000	2500	3000	3500	4000	5000	6000
[a]17	0.46	2.1	4.6	4.9	5.3	6.5	6.9	7.9	8.5	8.8	8.8	…	…
[a]19	0.53	2.5	4.8	5.4	6.5	7.4	7.9	9.1	9.9	10	11	9.8	…
21	0.58	2.8	5.1	6.0	7.3	8.3	9.0	10	11	12	12	12	10
23	0.63	3.0	5.6	6.6	8.0	9.3	10	12	13	14	14	14	12
25	0.69	3.3	6.1	7.3	8.8	10	11	13	14	15	15	15	14
27	0.74	3.5	6.8	7.9	9.5	11	12	14	15	16	18	18	16
29	0.80	3.8	7.3	8.5	10	12	13	15	16	18	19	19	18
31	0.85	4.1	7.8	9.1	11	13	14	16	18	19	20	20	19
33	0.90	4.4	8.3	9.8	12	14	15	18	19	21	21	21	20
35	0.96	4.6	8.8	10	13	15	16	19	20	23	23	23	21
37	1.0	4.9	9.1	11	14	15	16	20	21	24	24	24	…
40	1.1	5.3	10	12	15	16	18	21	24	25	26	26	…
45	1.3	6.0	11	13	16	19	20	24	26	28	29	…	…
50	1.4	6.6	13	15	18	20	23	26	29	30	…	…	…
	Type I			Type II				Type III					

No. of Teeth Small Sprkt.	1/2- Inch Pitch Chain										
	Revolutions per Minute—Small Sprocket										
	100	500	700	1000	1200	1800	2000	2500	3000	3500	4000
[a]17	0.83	3.8	5.0	6.3	7.5	10	11	11	11	11	…
[a]19	0.93	3.8	5.0	7.5	8.8	11	13	14	14	14	…
21	1.0	5.0	6.3	8.8	10	14	14	15	16	16	…
23	1.1	5.0	7.5	10	11	15	16	18	19	19	18
25	1.2	5.0	7.5	10	13	16	18	20	21	21	20
27	1.3	6.3	8.8	11	13	18	19	21	24	24	23
29	1.4	6.3	8.8	13	14	19	21	24	25	25	25
31	1.5	7.5	10	13	15	21	23	25	28	28	28
33	1.6	7.5	10	14	16	23	24	28	29	30	29
35	1.8	7.5	11	15	18	24	25	29	31	31	30
37	1.9	8.8	11	16	19	25	26	30	33	33	…
40	2.0	8.8	13	18	20	28	29	33	35	35	…
45	2.5	10	14	19	23	30	30	36	39	…	…
50	2.5	11	15	21	25	34	36	40	…	…	…
	Type I			Type II				Type III			

[a] For best results, smaller sprocket should have at least 21 teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12b. Horse Power Ratings per Inch of Chain Width for Silent Chain Drives –1982

No. of Teeth Small Sprkt.	5/8- Inch Pitch Chain									
	Revolutions per Minute—Small Sprocket									
	100	500	700	1000	1200	1800	2000	2500	3000	3500
[a]17	1.3	6.3	7.5	10	11	14	15	14	…	…
[a]19	1.4	6.3	8.8	13	14	16	18	18	…	…
21	1.6	7.5	10	13	15	19	20	20	20	…
23	1.8	7.5	11	15	16	21	23	24	23	…
25	1.9	8.8	11	16	19	24	25	26	26	24
27	2.0	10	13	18	20	26	28	29	29	26
29	2.1	10	14	19	21	28	30	31	31	29
31	2.4	11	15	20	23	30	31	34	34	31
33	2.5	11	16	21	25	33	34	36	36	34
35	2.6	13	16	23	26	34	36	39	39	35
37	2.8	13	18	24	28	36	39	43	41	…
40	3.0	14	19	26	30	39	41	44	…	…
45	3.4	16	21	29	34	44	46	…	…	…
50	3.8	18	24	33	38	48	50	…	…	…
	Type I		Type II		Type III					

No. of Teeth Small Sprkt.	3/4- Inch Pitch Chain								
	Revolutions per Minute- Small Sprocket								
	100	500	700	1000	1200	1500	1800	2000	2500
[a]17	1.9	8.1	11	14	15	16	18	18	…
[a]19	2.0	9.3	13	15	18	20	21	21	…
21	2.3	10	14	18	20	23	24	25	24
23	2.5	11	15	20	23	25	28	28	28
25	2.8	13	16	21	25	29	31	31	30
27	2.9	14	18	24	28	31	34	35	35
29	3.1	15	20	26	30	34	36	38	38
31	3.4	15	21	28	31	36	40	41	41
33	3.6	16	23	30	34	39	43	44	44
35	3.8	18	24	31	36	41	45	46	46
37	4.0	19	25	34	39	44	48	49	49
40	4.4	20	28	36	41	48	51	53	53
45	4.9	23	30	40	46	53	56	58	…
50	5.4	25	34	45	51	58	61	…	…
	Type I		Type II		Type III				

No. of Teeth Small Sprkt.	1- Inch Pitch Chain									
	Revolutions per Minute- Small Sprocket									
	100	200	300	400	500	700	1000	1200	1500	1800	2000
[a]17	3.8	6.3	8.8	11	14	18	21	23	…	…	…
[a]19	3.8	7.5	10	13	15	20	25	26	28	…	…
21	3.8	7.5	11	15	18	23	29	31	33	33	…
23	3.8	8.8	13	16	19	25	31	35	38	38	…
25	5.0	8.8	14	18	21	28	35	39	41	41	41
27	5.0	10	15	19	24	30	39	43	46	46	45
29	5.0	11	16	20	25	33	41	46	50	51	50
31	6.3	11	16	23	28	35	45	50	54	55	54
33	6.3	13	18	24	29	38	49	54	59	59	58
35	6.3	13	19	25	30	40	51	56	61	63	61
37	6.8	14	20	26	33	43	54	60	65	66	…
40	7.5	15	23	29	35	45	59	65	70	…	…
45	8.8	16	25	31	39	51	65	71	76	…	…
50	10	19	28	35	43	56	71	78	…	…	…
	Type I			Type II				Type III			

[a] For best results, smaller sprocket should have at least 21 teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 12c. Horse Power Ratings per Inch of Chain Width for Silent Chain Drives –1982

No. of Teeth Small Sprkt.	1¼- Inch Pitch Chain										
	Revolutions per Minute- Small Sprocket										
	100	200	300	400	500	600	700	800	1000	1200	1500
[a]19	5.6	10	15	20	24	26	29	31	34	35	…
21	6.3	11	18	23	26	30	33	36	40	41	…
23	6.9	13	19	24	29	34	36	40	45	46	46
25	7.5	14	20	26	31	36	40	44	50	53	53
27	8.0	15	23	29	35	40	44	49	54	58	58
29	8.6	16	24	31	38	43	48	53	59	63	64
31	9.3	18	26	34	40	46	51	56	64	68	69
33	9.9	19	28	35	43	49	55	60	69	73	74
35	11	20	29	38	45	53	59	64	73	78	78
37	11	21	30	40	48	55	63	68	76	81	…
40	12	24	34	44	53	60	68	74	83	88	…
45	13	26	38	49	59	68	75	81	91	…	…
50	15	29	43	54	65	74	83	90	100	…	…
	Type I			Type II			Type III				

No. of Teeth Small Sprkt.	1½- Inch Pitch Chain										
	Revolutions per Minute- Small Sprocket										
	100	200	300	400	500	600	700	800	900	1000	1200
[a]19	8.0	15	21	28	31	35	39	40	41	43	…
21	8.8	16	24	30	36	40	44	46	49	49	…
23	10	19	26	34	40	45	49	53	55	56	55
25	10	20	29	38	44	50	55	59	61	65	64
27	11	23	31	40	48	54	60	64	68	70	70
29	13	24	34	44	51	59	65	70	74	75	76
31	14	25	36	46	55	64	70	75	79	81	83
33	14	28	39	50	59	68	75	80	85	88	89
35	15	29	41	53	63	71	79	85	90	93	94
37	16	30	44	59	66	76	84	90	96	99	…
40	18	33	48	66	73	83	90	98	105	…	…
45	19	38	54	68	81	93	101	108	113	…	…
50	21	41	59	75	89	101	111	118	…	…	…
	Type I			Type II			Type III				

No. of Teeth Small Sprkt.	2- Inch Pitch Chain								
	Revolutions per Minute- Small Sprocket								
	100	200	300	400	500	600	700	800	900
[a]19	14	26	36	44	50	54	56	…	…
21	16	29	40	50	53	63	65	…	…
23	17	33	45	55	64	70	74	75	…
25	18	35	49	61	70	78	83	85	85
27	20	38	54	66	78	85	91	94	94
29	21	41	58	73	84	93	99	103	103
31	23	44	63	78	90	100	106	110	110
33	25	46	66	83	96	106	114	118	118
35	26	50	71	88	103	114	121	125	125
37	28	53	75	93	110	124	128	131	…
40	30	58	81	101	118	129	138	141	…
45	34	64	90	113	131	144	151	…	…
50	38	71	100	125	144	156	…	…	…
	Type I		Type II			Type III			

[a] For best results, smaller sprocket should have at least 21 teeth.

Copyright 2004, Industrial Press, Inc., New York, NY

GEARS AND GEARING

Geometry Factors For Gear Teeth

Contact and Bending Stresses.— To calculate the contact and bending stresses acting between the teeth of a pair of gears meshing under load, it is necessary to include in the stress formulas a number of factors that account for the geometry of the teeth, the physical properties of the materials used, and the nature of the specific application.

AGMA 908-B89 Information Sheet* gives equations for calculating the pitting resistance geometry factor, *I*, for external and internal spur and helical gears; and the bending strength geometry factor, *J*, for external spur and helical gears that are generated by rack-type tools (hobs, rack cutters, or generating grinding wheels) or pinion-type tools (shaper cutters). The document includes 66 tables of geometry factors, *I* and *J*, for a range of typical gear sets and tooth forms of 14½-, 20-, and 25-deg pressure angles and 0-, 10-, 15-, 20-, 25-, and 30-deg helix angles.

The Information sheet was prepared to assist designers making preliminary design studies and to present data useful to those without access to computer programs. Not all tooth forms, pressure angles, and pinion and gear modifications are covered. Neither are these data applicable to all gear designs; however, the data should be helpful to the majority of gear designers. Data from this Information Sheet are used with the rating procedures described in AGMA 2001-B88, *Fundamental Rating Factors and Calculation Methods for Involute Spur and Helical Gear Teeth*, for evaluating various spur and helical gear designs produced by using a generating process (see page 1834).

Geometry Factors for Pitting Resistance and Bending Strength.— The AGMA Information Sheet includes a mathematical procedure to determine the pitting resistance geometry factor, *I*, for internal and external gear sets of spur, conventional helical, and low-axial-contact-ratio (LACR) helical design. A mathematical procedure is also included to determine the bending strength geometry factor, *J*, for external gear sets of spur, conventional helical, and low-axial-contact-ratio (LACR) helical designs. The calculation procedure is valid for generated root fillets produced by both rack- and pinion-type tools.

Exceptions to the Information Sheet Data and Procedures.— The formulas in the Information Sheet are not valid when any of the following conditions exist:
1) Spur gears with transverse contact ratio less than one, $m_p < 1.0$; 2) spur or helical gears with transverse contact ratio equal or greater than two, $m_p \geq 2.0$; 3) interference exists between the tips of teeth and root fillets; 4) the teeth are pointed; 5) backlash is zero; 6) undercut exists in an area above the theoretical start of the active profile (the effect of this undercut is to move the highest point of single tooth contact, negating the assumption of this calculation method; however, the reduction in tooth thickness due to protuberance below the active profile is handled correctly by this method); 7) the root profiles are stepped or irregular (the *J* factor calculation uses the stress correction factors developed by Dolan and Broghamer; the factors may not be valid for root forms that are not smooth curves; for root profiles that are stepped or irregular, other stress correction factors may be appropriate); 8) where root fillets of the gear teeth are produced by a process other than generating; and 9) the helix angle at the standard (reference) diameter is greater than 50 deg.

In addition to these exceptions, it is assumed that 1) the friction effect on the direction of force is neglected; and 2) the fillet radius is smooth (it is actually a series of scallops).

Basic Gear Geometry of Spur and Helical Gears.— The equations that follow apply to spur and helical gears. Where double signs are used (e.g., ±), the upper sign applies to exter-

* Extracted from AGMA 908-B89, Information Sheet, *Geometry Factors for Determining the Pitting Resistance and Bending Strength of Spur, Helical, and Herringbone Gear Teeth*, with the permission of the publisher, American Gear Manufacturers Association, 1500 King Street, Suite 201, Alexandria, Virginia 22314.

Copyright 2004, Industrial Press, Inc., New York, NY

nal gears and the lower sign to internal gears. The equations given are based on unity normal module (m_n =1) or unity normal diametral pitch (P_{nd} = 1) and are valid for any consistent set of units. All angles are in radians unless otherwise specified. *In using the given equations, certain variables must be made dimensionless by dividing by the normal module m_n or multiplying by the normal diametral pitch P_{nd}.* For example, if a face width F 0.5 in. and the normal diametral pitch is 4, then the value of F to be used in the equations is $0.5 \times 4 = 2$. The variables to be so adjusted are $F, R_{01}, R_{02}, R_{oc}, R_c, h_{ao}, \delta_{ao}, \rho_{ao}$, and Δ_{sn}.

$$\text{Gear ratio, } m_G = \frac{n_2}{n_1}, \text{ Where } n_1 \text{ and } n_2 \text{ are pinion and gear tooth numbers} \quad (1)$$

$$\text{Standard (reference) pinion pitch radius, } R_1 = \frac{n_1}{2\cos\psi} \quad (2)$$

Where ψ = standard helix angle.

$$\text{Standard (reference) gear pitch radius, } R_2 = R_1 m_G \quad (3)$$

$$\text{Standard transverse pressure angle, } \phi = \arctan\left(\frac{\tan\phi_n}{\cos\psi}\right) \quad (4)$$

Where ϕ_n = standard normal pressure angle.

$$\text{Pinion base radius, } R_{b1} = R_1\cos\phi \quad (5)$$

$$\text{Gear base radius, } R_{b2} = R_{b1} m_G \quad (6)$$

$$\text{Oparating transverse pressure angle, } \phi_r = \arccos\left(\frac{R_{b2} \pm R_{b1}}{C_r}\right) \quad (7)$$

Where C_r = Operating center distance.

$$\text{Transverse base pitch, } P_b = \frac{2\pi R_{b1}}{n_1} \quad (8)$$

$$\text{Normal base pitch, } P_N = \pi\cos\phi_n \quad (9)$$

$$\text{Base helix angle, } \psi_b = \arccos\left(\frac{P_N}{P_b}\right) \quad (10)$$

Fig. 1 shows a view of the line of action in the transverse plane of two meshing gears. The distances C_1, through C_6 are derived from this figure taking into account the exceptions noted previously with regard to undercut.

$$C_6 = C_r \sin\phi_r \quad (11)$$

$$C_1 = \pm[C_6 - (R_{02}^2 - R_{b2}^2)^{0.5}] \quad (12)$$

where R_{02} = addendum radius of gear, for internal or external gears.

$$C_3 = \frac{C_6}{(m_G \pm 1)} \quad (13)$$

$$C_4 = C_1 + P_b \quad (14)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$C_5 = (R_{01}^2 - R_{b1}^2)^{0.50} \tag{15}$$

Where R_{01} = addendum radius of pinion.

$$C_2 = C_5 - P_b \tag{16}$$

Active length of line of contact, $Z = C_5 - C_1$ (17)

Distance C_2 locates the lowest point of single tooth contact (LPSTC); distance C_4 locates the highest point of single tooth contact (HPSTC), where C_r, R_{01}, and R_{02} are values for m_n =1 or P_{nd}=1.



Fig. 1. Transverse Plane View of the Line of Action

Contact Ratios.— The contact ratios are as follows:

$$\text{Transverse Contact ratio, } m_p = \frac{Z}{P_b} \tag{18}$$

$$\text{Axial pitch, } P_x = \frac{\pi}{\sin\psi} \tag{19}$$

$$\text{Axial contact ratio, } m_F = \frac{F}{P_x} \tag{20}$$

where F = effective face width at m_n=1 or P_{nd}=1. For spur gears, $m_F = 0$.

Copyright 2004, Industrial Press, Inc., New York, NY

Minimum Lengths of Lines of Contact.— For spur gears with $m_p < 2.0$ the minimum length of contact lines, L_{min},

$$L_{min} = F \tag{21}$$

For helical gears, two cases must be considered:

$$CaseI\text{: For } n_a \le 1 - n_r, L_{min} = \frac{(m_p F - n_a n_r p_x)}{\cos\psi_b} \tag{22}$$

$$CaseII\text{: For } n_a > 1 - n_r, L_{min} = \frac{[m_p F - (1 - n_a)(1 - n_r)p_x]}{\cos\psi_b} \tag{23}$$

where n_r = fractional part of m_p, and n_a = fractional part of m_F. For example, if $m_p = 1.4$, then $n_r = 0.4$.

Load Sharing Ratio, m_N.— The load sharing ratio m_n, is calculated as follows:

$$\text{For helical gears, } m_N = \frac{F}{L_{min}} \tag{24}$$

$$\text{For spur gears with } m_p \le 2.0\text{, Eq. (21) has } L_{min} = F \text{ so that } m_N = 1.0 \tag{25}$$

For low axial contact ratio (LACR) helicals, $m_F \le 1.0$. Load sharing is accommodated by the helical overlap factor C_ψ [Equation (36)]; therefore,

$$m_N = 1.0 \tag{26}$$

$$\text{Operating helix angle, } \psi_r = \arctan\left(\frac{\tan\psi_b}{\cos\phi_r}\right) \tag{27}$$

$$\text{Operating normal pressure angle, } \phi_{nr} = \arcsin(\cos\psi_b \sin\phi_r) \tag{28}$$

Calculating the Pitting Resistance Geometry Factor, *I*.— The pitting resistance geometry factor I is a dimensionless number that takes into account the effects of the radii of curvature of the gear tooth surfaces, load sharing, and the normal component of the transmitted load:

$$I = \frac{\cos\phi_r C_\psi^2}{[(1/\rho_1 + 1/\rho_2)(dm_N)]} \tag{29}$$

where

ϕ_r = operating transverse pressure angle [Equation (7)];
C_ψ = helical overlap factor [Equation (36)];
d = pinion operating pitch diameter [Equation (30)];
m_N = load sharing ratio [Equation (24), (25), or (26)]; and
ρ_1 *and* ρ_2 = radii of curvature of pinion and gear profiles, respectively, at point of stress calculation.

$$\text{Operating pitch diameter of pinion, } d = \frac{2c_r}{(m_G + 1)} \tag{30}$$

Radii of Curvature of Profiles at Contact Stress Calculation Point: For conventional helical gears ($m_F > 1$) the radii of curvature are calculated at the mean radius or middle of the working profile of the pinion where

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Mean radius of pinion, } R_{m1} = \tfrac{1}{2}[R_{01} \pm (C_r - R_{02})] \tag{31}$$

where

R_{01} = addendum radius of pinion and;

R_{02} = addendum radius of gear, internal or external.

$$\text{radius of curvature of pinion profile, } \rho_1 = (R_{m1}^2 - R_{b1}^2)^{0.50} \tag{32}$$

Where R_{b1} = base radius of pinion.

$$\text{Radius of curvature of gear profile, } \rho_2 = C_6 \mp \rho_1 \tag{33}$$

For spurs and LACR helicals ($m_F \leq 1$), the radii of curvature are calculated at the LPSTC:

$$\rho_1 = C_2 \tag{34}$$

$$\rho_2 = C_6 \mp \rho_1 \tag{35}$$

Helical overlap factor for LACR ($m_F \leq 1$), helical gears,

$$C_\psi = \left[1 - m_F\left(1 - \frac{\rho_{m1}\rho_{m2}Z}{\rho_1\rho_2\rho_N}\right)\right]^{0.50} \tag{36}$$

where Z = Equation (17); p_N = Equation (9); ρ_{m1} = Equation (37) and, ρ_{m2} = Equation (38).
radius of curvature of pinion profile at mean radius of profile,

$$\rho_{m1} = (R_{m1}^2 - R_{b1}^2)^{0.50} \tag{37}$$

Radius of curvature of gear profile at mean radius of gear,

$$\rho_{m2} = C_6 \mp \rho_{m1} \tag{38}$$

$$\text{For spur and conventional helicals, } C_\psi = 1 \tag{39}$$

Bending Strength Geometry Factor,* *J*.— The bending strength geometry factor is a dimensionless number that takes into account: 1) shape of the tooth; 2) worst load position; 3) stress concentration; and 4) load sharing between oblique lines of contact in helical gears .

Both tangential (bending) and radial (compressive) components of the tooth load are included. The equations and calculation procedures for the bending stress geometry factor are not given here, but may be found in AGMA 908-B89. The procedures apply only to external gears and must be repeated for both the pinion and the gear using the appropriate dimensions for each.

Generating Tool Geometry: Details of the methods for calculating the geometry of the tools used to generate tooth profiles are provided in the Information Sheet as part of the J-factor calculation procedure.

* Included in the AGMA Information Sheet are the equations needed to write a computer program to calculate values not given in the tables of *J* factors.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Load Angle and Load Radius



Fig. 3. Pressure Angle Where Tooth Comes to Point

Virtual Spur Gear: Helical gears are considered to be virtual spur gears with the following virtual geometry:

$$\text{Virtual tooth number, } n = \frac{n_1}{\cos\psi^3} \tag{40}$$

$$\text{Standard (ref) pitch radius of virtual spur gear, } r_n = \frac{n}{2} \tag{41}$$

$$\text{Virtual base radius, } r_{nb} = r_n \cos\phi_n \tag{42}$$

$$\text{Virtual outside radius, } r_{na} = r_n + R_{01} - R_1 \tag{43}$$

For spur gears, the virtual geometry is the same as the actual geometry:

$$n = n_1 \tag{44}$$

$$r_n = R_1 \tag{45}$$

$$r_{nb} = R_{b1} \tag{46}$$

$$r_{na} = R_{01} \tag{47}$$

Pressure Angle at Load Application Point.— The critical bending stress on a spur gear tooth develops when all the applied load is carried at the highest point of single tooth contact on the tooth. Spur gears having variations that prevent two pairs of teeth from sharing the load may be stressed most heavily when the load is applied at the tips of the teeth. Table 1 has been used in previous standards to establish the variation in base pitch between the

Copyright 2004, Industrial Press, Inc., New York, NY

gear and pinion, which determines whether load sharing exists in steel spur gears. Values greater than those in the table require the use of tip loading in determining bending stress geometry factors described in AGMA 908-B89.

Table 1. Maximum Allowable Variation in Action for Steel Spur Gears for Load Sharing (Variation in Base Pitch)

Number of Pinion Teeth	Load Pounds per Inch of Face (Newtons Per Millimeter of Face)				
	500 lb (90N)	1000 lb (175N)	2000 lb (350N)	4000 lb (700N)	8000 lb (1400N)
	Maximum Allowable Variation in Inches and Millimeters when Teeth Share Load				
15	0.0004 in.	0.0007 in.	0.0014 in.	0.0024 in.	0.0042 in.
	0.01 mm	0.02 mm	0.04 mm	0.06 mm	0.11 mm
20	0.0003 in.	0.0006 in.	0.0011 in.	0.0020 in.	0.0036 in.
	0.01 mm	0.02 mm	0.03 mm	0.05 mm	0.09 mm
25	0.0002 in.	0.0005 in.	0.0009 in.	0.0017 in.	0.0030 in.
	0.01 mm	0.01 mm	0.02 mm	0.04 mm	0.08 mm

For helical gears and spur gears that are analyzed with the load applied at the tip of the tooth, the pressure angle at the load application point, ϕ_{nw}, is found from

$$\tan\phi_{nW} = \left[\left(\frac{r_{na}}{r_{nb}}\right)^2 - 1\right]^{0.50} \tag{48}$$

For spur gears, where the highest bending stress occurs when the load is at the highest point of single tooth contact (HPSTC), the pressure angle is found from

$$\tan\phi_{nW} = \frac{C_4}{r_{nb}} \tag{49}$$

Equation (49) may also be used for LACR helical gears, but distance C_4 must be based on the virtual spur gear. The following equations are from analogy with Equation (3), (6), (11), (12), (14), (44), and (49):

$$\text{Standard (ref) pitch radius of virtual spur gear, } r_{n2} = r_n m_G \tag{50}$$

$$\text{Virtual base radius, } r_{nb2} = r_{nb} m_G \tag{51}$$

$$\text{Virtual outside radius, } r_{na2} = r_{n2} + R_{02} - R_2 \tag{52}$$

$$\text{Sixth distance along line of action of virtual gear, } C_{n6} = (r_{nb2} + r_{nb})\tan\phi_{nr} \tag{53}$$

$$\text{First distance along line of action of virtual gear, } C_{n1} = [C_{n6} - (r_{na2}^2 - r_{nb2}^2)^{0.50}] \tag{54}$$

$$\text{Fourth distance along line of action of virtual gear, } C_{n4} = C_{n1} + \rho_N \tag{55}$$

The pressure angle at the load application point (tip), ϕ_{nW}

$$\tan\phi_{nW} = \frac{C_{n4}}{r_{nb}} \tag{56}$$

Generating-Rack Shift Coefficient.— The generating-rack shift coefficient, x_g, applies to the completely finished teeth. It includes the rack shift for addendum modification plus the rack shift for thinning the teeth to obtain backlash:

$$x_g = x - \frac{\Delta s_n}{2\tan\phi_n} \tag{57}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where ΔS_n = amount gear tooth is thinned for backlash and x = addendum modification coefficient at zero backlash,

$$x = \frac{\left(S_n + \Delta S_n - \frac{\pi}{2}\right)}{(2\tan\phi_n)} \tag{58}$$

where S_n= normal circular tooth thickness measured on the standard (ref) pitch cylinder,

$$S_n = \frac{\pi}{2} + 2x_g \tan\phi_n \tag{59}$$

Load Angle and Load Radius: Fig. 2 defines the load angle ϕ_{nl} and the load radius r_{nl}. The applied load is shown at an arbitrary point W such that:

$$\phi_{nl} = \tan\phi_{nw} - \text{INV}\phi_{np} \tag{60}$$

where ϕ_{np} = pressure angle where gear tooth is pointed, Fig. 3.

$$\text{INV}\phi_{np} = \text{INV}\phi_n + \frac{s_n}{2r_n} \tag{61}$$

but,

$$\text{INV}\phi_n = \tan\phi_n - \phi \tag{62}$$

and

$$2r_n = n \tag{63}$$

so that

$$\text{INV}\phi_{np} = \tan\phi_n - \phi_n + \frac{s_n}{n} \tag{64}$$

Then Equation (60) can be expressed as

$$\phi_{nl} = \tan\phi_{nW} - \tan\phi_n + \phi_n - \frac{s_n}{n} \tag{65}$$

Equation (65) gives the load angle ϕ_{nL} for any load position specified by tan ϕ_{nW} found from Equation (48) and (49).

As may be seen from Fig. 3, the virtual radius is

$$r_{nl} = \frac{r_{nb}}{\cos\phi_{nL}} \tag{66}$$

Tables of Geometry Factors, *I* and *J*.— Included here are some of the tables of precalculated values of *I* and *J* extracted from the Information Sheet. For additional data, tables, and related information for other combinations of gear sets, tooth forms, pressure angles, helix angles, cutting tool dimensions, and addendum coefficients, refer to the Information Sheet. It should be noted that the formulas and data in the Information Sheet are not applicable to bending stresses in internal gears, since no simplified model for calculating bending stresses in internal gears is available.

Using the Tables.— Each of the tables in the Information Sheet and those presented here were generated for a specific tool form (basic rack) defined by whole depth factor, normal pressure (profile) angle, and tool tip radius. Only those tables applicable to spur gears are presented here; those for helical gear sets are available in the Information Sheet.

Whole Depth: Whole depth is expressed in the tables as a "whole depth factor" and is the whole depth of a basic rack for *I* normal module or *I* normal diametral pitch. The actual generated depths will be slightly greater due to tooth thinning for backlash

Copyright 2004, Industrial Press, Inc., New York, NY

Outside Diameter: The tabulated values are for gears having an outside diameter (for normal module or normal diametral pitch = 1), equal to

$$D_{a1} = \frac{n_1}{\cos\psi} + 2(1 + x_1) \tag{67}$$

$$D_{a2} = \frac{n_2}{\cos\psi} + 2(1 + x_2) \tag{68}$$

where n_1 and n_2 are the pinion and gear tooth numbers, respectively; ψ = standard helix angle, deg.; and D_{a1} and D_{a2} are the pinion and gear addendum, respectively.

Center Distance: The tables apply to gearsets that operate at standard center distance. This center distance is the tight-mesh center distance for gears not yet thinned for backlash:

$$C = \frac{(n_1 + n_2)}{2\cos\psi} \tag{69}$$

where C = standard center distance. For this center distance the sum of the addendum modification coefficients for pinion and gear is zero:

$$x_1 + x_2 = 0 \tag{70}$$

Tooth Thickness Backlash Allowance: Values in the tables were calculated based on a backlash allowance. The circular tooth thickness for the pinion and gear are each thinned by an amount Δsn:

$$\Delta s_n = \frac{0.024}{P_{nd}} = 0.024 \quad \text{for} \quad P_{nd} = 1 \tag{71}$$

If the gears being evaluated have different minimum tooth thicknesses than from Equation (71), the bending strength geometry factor, J, can be approximated by using Equation (72). The pitting resistance geometry factor, I, is unaffected by variations in tooth thickness:

$$J_1 = J_S\left(\frac{s_{n1}}{s_{ns}}\right)^2 \tag{72}$$

where J_1 = adjusted geometry factor; J_s = geometry factor from table; s_{n1} = adjusted circular tooth thickness; and s_{ns} = standard tooth thickness thinned per Equation (71).

As an example, from Table 4, for 20-deg pressure angle spur gears loaded at the highest point of single tooth contact, the J factor for a 21-tooth pinion operating with a 35-tooth gear is found to be 0.31. The table values are based on a circular tooth thickness of $\pi/2 - 0.024 = 3.1416/2 - 0.024 = 1.547$ for diametral pitch.

For a 10 normal diametral pitch pinion or gear, the equivalent circular tooth thickness would be 1.547/10 = 0.155.

If a J value for a 0.010 in. thinner pinion, having a circular thickness of 0.155 –0.010= 0.145 in. is required, the approximate value is $0.34(0.145/0.155)^2 = 0.30 = J_1$ so that a 6.5 per cent reduction in tooth thickness reduces the J factor by 12 percent.

Undercutting: The tables do not include geometry factors that may be needed if an undercutting condition exists in either of the two gears. Undercutting can be evaluated using Equation (73) and Fig. 4 where the generating-rack shift coefficient, x_g, must be equal to or greater than the expression in Equation (73):

$$x_{gmin} = h_{ao} - \rho_{ao}(1 - \sin\phi_n) - \left(\frac{n}{2}\right)\sin^2\phi_n \tag{73}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where h_{ao} = nominal tool addendum; ρ_{ao} = tool tip radius; and n = pinion or gear tooth number.



Fig. 4. Undercutting Criteria

Top Land: The tables do not include geometry factors when either the pinion or the gear tooth top land is less than the value expressed in Equation (74) or (74a):

$$s_{namin} \geq \frac{0.3}{P_{nd}} \quad \text{in.} \tag{74}$$

$$s_{namin} \geq 0.3 m_n \quad \text{mm} \tag{74a}$$

in which s_{na} = tooth thickness at outside diameter.

Cutter Geometry: The hob geometry used in the calculation of *I* and *J* is as follows: Tool tooth number, $n_c = 10{,}000$; reference normal circular tooth thickness of tool, $s_{no} = 1.5708$; addendum modification coefficient of tool, $x_o = 0.0$; amount of protuberance, $\delta_o = 0.0$.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		14.5 -deg Pressure Angle 0.0-deg Helix Angle 0.0157 Tool Edge Radius		2.157 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at Tip of Gears							
		Number of Pinion Teeth									
		21		26		35		55		135	
		Pinion	Gear	Pinion	Gear	Pinion	Gear	Pinion	Gear	Pinion	Gear
Equal Addendum Coefficients ($x_1 = x_2 = 0$)											
35	*I*					0.061					
	J					0.29	0.29				
55	*I*					0.074		0.061			
	J					0.30	0.31	0.33	0.33		
135	*I*					0.096		0.088		0.061	
	J					0.31	0.34	0.35	0.35	0.38	0.38
25 percent Long Addendum Pinion ($x_1 = 0.25$)											
25 percent Short Addendum Gear ($x_2 = -0.25$)											
26	*I*			0.060							
	J			0.32	0.22						
35	*I*			0.071		0.059					
	J			0.32	0.24	0.34	0.24				
55	*I*			0.087		0.077		0.060			
	J			0.33	0.27	0.35	0.27	0.37	0.29		
135	*I*			0.111		0.106		0.092		0.060	
	J			0.35	0.29	0.36	0.30	0.39	0.32	0.41	0.35
50 percent Long Addendum Pinion ($x_1 = 0.50$)											
50 percent Short Addendum Gear ($x_2 = -0.50$)											
21	*I*	0.056									
	J	0.35	0.15								
26	*I*	0.067		0.056							
	J	0.36	0.17	0.37	0.17						
35	*I*	0.081		0.071		0.056					
	J	0.36	0.19	0.37	0.20	0.38	0.20				
55	*I*	0.100		0.091		0.078		0.057			
	J	0.37	0.22	0.38	0.23	0.39	0.24	0.41	0.25		
135	*I*	0.127		0.123		0.114		0.096		0.060	
	J	0.38	0.26	0.39	0.26	0.40	0.27	0.42	0.29	0.43	0.32

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		14.5 -deg Pressure Angle 0.0-deg Helix Angle 0.0157 Tool Edge Radius		2.157 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at HPSTC of Gears							
		Number of Pinion Teeth									
		21		26		35		55		135	
		Pinion	Gear	Pinion	Gear	Pinion	Gear	Pinion	Gear	Pinion	Gear
Equal Addendum Coefficients ($x_1 = x_2 = 0$)											
35	*I*					0.061					
	J					0.29	0.29				
55	*I*					0.074		0.061			
	J					0.30	0.31	0.33	0.33		
135	*I*					0.096		0.088		0.061	
	J					0.31	0.34	0.35	0.35	0.38	0.38
25 percent Long Addendum Pinion ($x_1 = 0.25$)											
25 percent Short Addendum Gear ($x_2 = -0.25$)											
26	*I*			0.060							
	J			0.32	0.22						
35	*I*			0.071		0.059					
	J			0.32	0.24	0.34	0.24				
55	*I*			0.087		0.077		0.060			
	J			0.33	0.27	0.35	0.27	0.37	0.29		
135	*I*			0.111		0.106		0.092		0.060	
	J			0.35	0.29	0.36	0.30	0.39	0.32	0.41	0.35
50 percent Long Addendum Pinion ($x_1 = 0.50$)											
50 percent Short Addendum Gear ($x_2 = -0.50$)											
21	*I*	0.056									
	J	0.35	0.15								
26	*I*	0.067		0.056							
	J	0.36	0.17	0.37	0.17						
35	*I*	0.081		0.071		0.056					
	J	0.36	0.19	0.37	0.20	0.38	0.20				
55	*I*	0.100		0.091		0.078		0.057			
	J	0.37	0.22	0.38	0.23	0.39	0.24	0.41	0.25		
135	*I*	0.127		0.123		0.114		0.096		0.060	
	J	0.38	0.26	0.39	0.26	0.40	0.27	0.42	0.29	0.43	0.32

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		14.5 -deg Pressure Angle 0.0-deg Helix Angle 0.0157 Tool Edge Radius				2.157 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at Tip of Gears									
		Number of Pinion Teeth													
		14		17		21		26		35		55		135	
		P	G	P	G	P	G	P	G	P	G	P	G	P	G
Equal Addendum Coefficients ($x_1 = x_2 = 0$)															
21	*I*					0.078									
	J					0.24	0.24								
26	*I*					0.084		0.079							
	J					0.24	0.25	0.25	0.25						
35	*I*					0.091		0.088		0.080					
	J					0.24	0.26	0.25	0.26	0.26	0.26				
55	*I*					0.102		0.101		0.095		0.080			
	J					0.24	0.28	0.25	0.28	0.26	0.28	0.28	0.28		
135	*I*					0.118		0.121		0.120		0.112		0.080	
	J					0.24	0.29	0.25	0.29	0.26	0.29	0.28	0.29	0.29	0.29
25 percent Long Addendum Pinion ($x_1 = 0.25$)															
25 percent Short Addendum Gear ($x_2 = -0.25$)															
17	*I*			0.080											
	J			0.27	0.19										
21	*I*			0.087		0.080									
	J			0.27	0.21	0.27	0.21								
26	*I*			0.094		0.088		0.080							
	J			0.27	0.22	0.27	0.22	0.27	0.22						
35	*I*			0.103		0.098		0.092		0.080					
	J			0.27	0.24	0.27	0.24	0.28	0.24	0.28	0.24				
55	*I*			0.115		0.113		0.108		0.099		0.080			
	J			0.27	0.26	0.27	0.26	0.28	0.26	0.28	0.26	0.29	0.26		
135	*I*			0.131		0.134		0.133		0.129		0.116		0.080	
	J			0.27	0.28	0.27	0.28	0.28	0.28	0.28	0.28	0.29	0.28	0.30	0.28
50 percent Long Addendum Pinion ($x_1 = 0.50$)															
50 percent Short Addendum Gear ($x_2 = -0.50$)															
14	*I*	0.080													
	J	0.30	0.12												
17	*I*	0.088		0.080											
	J	0.30	0.15	0.30	0.15										
21	*I*	0.097		0.090		0.080									
	J	0.30	0.17	0.30	0.17	0.31	0.17								
26	*I*	0.105		0.099		0.090		0.080							
	J	0.30	0.19	0.30	0.19	0.31	0.19	0.31	0.19						
35	*I*	0.116		0.111		0.103		0.094		0.080					
	J	0.30	0.21	0.30	0.21	0.31	0.21	0.31	0.21	0.30	0.21				
55	*I*	0.130		0.127		0.122		0.114		0.101		0.080			
	J	0.30	0.24	0.30	0.24	0.31	0.24	0.31	0.24	0.30	0.24	0.30	0.24		
135	*I*	0.148		0.149		0.148		0.145		0.136		0.120		0.080	
	J	0.30	0.27	0.30	0.27	0.31	0.27	0.31	0.27	0.30	0.27	0.30	0.27	0.30	0.27

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 5. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		14.5 -deg Pressure Angle 0.0-deg Helix Angle 0.250 Tool Edge Radius				2.25 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at HPSTC of Gears									
		Number of Pinion Teeth													
		14		17		21		26		35		55		135	
		P	G	P	G	P	G	P	G	P	G	P	G	P	G
Equal Addendum Coefficients ($x_1 = x_2 = 0$)															
21	*I*					0.078									
	J					0.33	0.33								
26	*I*					0.084		0.079							
	J					0.33	0.35	0.35	0.35						
35	*I*					0.091		0.088		0.080					
	J					0.34	0.37	0.36	0.38	0.39	0.39				
55	*I*					0.102		0.101		0.095		0.080			
	J					0.34	0.40	0.37	0.41	0.40	0.42	0.43	0.43		
135	*I*					0.118		0.121		0.120		0.112		0.080	
	J					0.35	0.43	0.38	0.44	0.41	0.45	0.45	0.47	0.49	0.49
25 percent Long Addendum Pinion ($x_1 = 0.25$)															
25 percent Short Addendum Gear ($x_2 = -0.25$)															
17	*I*			0.080											
	J			0.36	0.24										
21	*I*			0.087		0.080									
	J			0.37	0.26	0.39	0.27								
26	*I*			0.094		0.088		0.080							
	J			0.37	0.29	0.39	0.29	0.41	0.30						
35	*I*			0.103		0.106		0.092		0.080					
	J			0.37	0.32	0.40	0.32	0.41	0.33	0.43	0.34				
55	*I*			0.115		0.113		0.108		0.099		0.080			
	J			0.38	0.35	0.40	0.36	0.42	0.36	0.44	0.37	0.47	0.39		
135	*I*			0.131		0.134		0.133		0.129		0.116		0.080	
	J			0.39	0.39	0.41	0.40	0.43	0.41	0.45	0.42	0.48	0.44	0.51	0.46
50 percent Long Addendum Pinion ($x_1 = 0.50$)															
50 percent Short Addendum Gear ($x_2 = -0.50$)															
14	*I*	0.080													
	J	0.40	0.14												
17	*I*	0.088		0.080											
	J	0.41	0.17	0.42	0.18										
21	*I*	0.097		0.090		0.080									
	J	0.41	0.20	0.43	0.21	0.44	0.21								
26	*I*	0.105		0.099		0.090		0.080							
	J	0.41	0.23	0.43	0.23	0.45	0.24	0.46	0.24						
35	*I*	0.116		0.111		0.103		0.094		0.080					
	J	0.42	0.26	0.43	0.27	0.45	0.27	0.46	0.28	0.48	0.29				
55	*I*	0.130		0.127		0.122		0.114		0.101		0.080			
	J	0.42	0.30	0.44	0.31	0.45	0.31	0.47	0.32	0.48	0.33	0.50	0.34		
135	*I*	0.148		0.149		0.148		0.145		0.136		0.120		0.080	
	J	0.43	0.34	0.44	0.35	0.46	0.36	0.47	0.37	0.49	0.38	0.50	0.40	0.52	0.43

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		25 -deg Pressure Angle 0.0-deg Helix Angle 0.027 Tool Edge Radius				2.350 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at Tip ofGears											
		Number of Pinion Teeth															
		12		14		17		21		26		35		55		135	
		P	G	P	G	P	G	P	G	P	G	P	G	P	G	P	G
Equal Addendum Coefficients ($x_1 = x_2 = 0$)																	
14	*I*			0.086													
	J			0.28	0.28												
17	*I*			0.091		0.090											
	J			0.28	0.30	0.30	0.30										
21	*I*			0.095		0.096		0.092									
	J			0.28	0.31	0.30	0.31	0.31	0.31								
26	*I*			0.100		0.101		0.099		0.094							
	J			0.28	0.33	0.30	0.33	0.31	0.33	0.33	0.33						
35	*I*			0.106		0.109		0.108		0.104		0.095					
	J			0.28	0.34	0.30	0.34	0.31	0.34	0.33	0.34	0.34	0.34				
55	*I*			0.113		0.119		0.121		0.119		0.112		0.095			
	J			0.28	0.36	0.30	0.36	0.31	0.36	0.33	0.36	0.34	0.36	0.36	0.36		
135	*I*			0.123		0.132		0.139		0.142		0.141		0.131		0.096	
	J			0.28	0.38	0.30	0.38	0.31	0.38	0.33	0.38	0.34	0.38	0.36	0.38	0.49	0.49
25 percent Long Addendum Pinion ($x_1 = 0.25$)																	
25 percent Short Addendum Gear ($x_2 = -0.25$)																	
14	*I*	0.095		0.093													
	J	0.32	0.22	0.33	0.22												
17	*I*	0.100		0.099		0.094											
	J	0.32	0.25	0.33	0.25	0.34	0.25										
21	*I*	0.106		0.106		0.102		0.095									
	J	0.32	0.27	0.33	0.27	0.34	0.27	0.36	0.27								
26	*I*	0.111		0.112		0.109		0.103		0.095		0.095					
	J	0.32	0.29	0.33	0.29	0.34	0.29	0.36	0.29	0.36	0.29	0.36	0.29				
35	*I*	0.118		0.120		0.119		0.115		0.108		0.096					
	J	0.32	0.31	0.33	0.31	0.34	0.31	0.36	0.31	0.36	0.31	0.37	0.31				
55	*I*	0.127		0.131		0.133		0.131		0.126		0.116		0.096			
	J	0.32	0.34	0.33	0.34	0.34	0.34	0.36	0.34	0.36	0.34	0.37	0.34	0.38	0.34		
135	*I*	0.138		0.145		0.151		0.153		0.153		0.148		0.135		0.096	
	J	0.32	0.37	0.33	0.37	0.34	0.27	0.36	0.37	0.36	0.37	0.37	0.37	0.38	0.37	0.39	0.37
50 percent Long Addendum Pinion ($x_1 = 0.50$)																	
50 percent Short Addendum Gear ($x_2 = -0.50$)																	
21	*I*							0.096									
	J							0.40	0.23								
26	*I*							0.106		0.096							
	J							0.40	0.25	0.40	0.25						
35	*I*							0.120		0.110		0.096					
	J							0.40	0.28	0.40	0.28	0.40	0.28				
55	*I*							0.139		0.131		0.118		0.096			
	J							0.40	0.32	0.40	0.32	0.40	0.32	0.40	0.32		
135	*I*							0.167		0.163		0.155		0.138		0.096	
	J							0.40	0.36	0.40	0.36	0.40	0.36	0.40	0.36	0.40	0.36

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Geometry Factors *I* and *J* for Various Number Combinations for Module = 1 or Normal Diametral Pitch = 1

Number of Gear Teeth		25 -deg Pressure Angle 0.0-deg Helix Angle 0.270 Tool Edge Radius				2.350 Whole Depth Factor 0.024 Tooth Thinning for Backlash Loaded at HPSTC of Gears											
		Number of Pinion Teeth															
		12		14		17		21		26		35		55		135	
		P	G	P	G	P	G	P	G	P	G	P	G	P	G	P	G
Equal Addendum Coefficients ($x_1 = x_2 = 0$)																	
14	*I*			0.086													
	J			0.33	0.33												
17	*I*			0.091		0.090											
	J			0.33	0.36	0.36	0.36										
21	*I*			0.095		0.096		0.092									
	J			0.33	0.39	0.36	0.39	0.39	0.39								
26	*I*			0.100		0.101		0.099		0.094							
	J			0.33	0.41	0.37	0.42	0.40	0.42	0.43	0.43						
35	*I*			0.106		0.109		0.108		0.104		0.095					
	J			0.34	0.44	0.37	0.45	0.40	0.45	0.43	0.46	0.46	0.46				
55	*I*			0.113		0.119		0.121		0.119		0.112		0.095			
	J			0.34	0.47	0.38	0.48	0.41	0.49	0.43	0.49	0.47	0.50	0.51	0.51		
135	*I*			0.123		0.132		0.139		0.142		0.141		0.131		0.096	
	J			0.35	0.51	0.38	0.52	0.42	0.53	0.45	0.53	0.48	0.54	0.53	0.56	0.57	0.57
25 percent Long Addendum Pinion ($x_1 = 0.25$)																	
25 percent Short Addendum Gear ($x_2 = -0.25$)																	
14	*I*	0.095		0.093													
	J	0.38	0.25	0.40	0.25												
17	*I*	0.100		0.099		0.094											
	J	0.38	0.29	0.40	0.29	0.43	0.29										
21	*I*	0.106		0.106		0.102		0.095									
	J	0.38	0.32	0.41	0.32	0.43	0.33	0.46	0.33								
26	*I*	0.111		0.112		0.109		0.103		0.095							
	J	0.39	0.35	0.41	0.35	0.44	0.36	0.46	0.36	0.48	0.37						
35	*I*	0.118		0.120		0.119		0.115		0.108		0.096					
	J	0.39	0.38	0.41	0.39	0.44	0.39	0.47	0.40	0.49	0.41	0.51	0.41				
55	*I*	0.127		0.131		0.133		0.131		0.126		0.116		0.096			
	J	0.39	0.42	0.42	0.43	0.44	0.44	0.47	0.44	0.49	0.45	0.52	0.46	0.55	0.47		
135	*I*	0.138		0.145		0.151		0.153		0.153		0.148		0.135		0.096	
	J	0.40	0.47	0.42	0.48	0.45	0.49	0.48	0.49	0.50	0.50	0.53	0.51	0.56	0.53	0.59	0.55
50 percent Long Addendum Pinion ($x_1 = 0.50$)																	
50 percent Short Addendum Gear ($x_2 = -0.50$)																	
21	*I*							0.096									
	J							0.52	0.27								
26	*I*							0.106		0.096							
	J							0.52	0.30	0.53	0.31						
35	*I*							0.120		0.110		0.096					
	J							0.52	0.35	0.53	0.35	0.55	0.36				
55	*I*							0.139		0.131		0.118		0.096			
	J							0.52	0.40	0.54	0.41	0.56	0.42	0.58	0.43		
135	*I*							0.167		0.163		0.155		0.138		0.096	
	J							0.53	0.46	0.54	0.47	0.56	0.48	0.58	0.50	0.60	0.53

The addendum modification coefficients x_1 and x_2 are for zero backlash gears meshing at standard center distance.

Copyright 2004, Industrial Press, Inc., New York, NY

Power–Transmitting Capacity of Spur Gears

Modes of Failure.— When sets of spur gears are made, installed, and lubricated properly, they normally may be subject to three primary modes of failure, as discussed below.

Tooth Scoring: Tooth scoring is a scuffing or welding type of tooth failure, caused by high sliding speed combined with high contact stress. Scoring is not a fatigue failure but rather a failure of the lubricant caused by increases in lubricant viscosity with pressure. The lubricant must provide cooling to the gears as well as reducing friction. Well proportioned commercial gears with a pitchline velocity of less than 7000 ft/min will normally not score if they have a reasonably good surface finish and are properly lubricated. If scoring does occur or if it is suspected to be critical in a new high speed design, the scoring temperature index should be determined by the method shown in American Gear Manufacturers Standard AGMA 217.01 or by some similar method.

Pitting: In surface pitting, small cracks first develop on and under the surfaces of gear teeth as a result of metal fatigue. Pieces of the surface then break away, and those that do not fall clear cause further damage or broken teeth. Vacuummelted steels have gone far toward reducing pitting. Failure usually occurs at a point just below the pitch surface on the driving pinion and may be anticipated in the gear design by a determination of the gear set contact compressive stress.

Tooth Breakage: Tooth breakage is usually a tensile fatigue failure at the weakest section of the gear tooth when considered as a cantilever beam. The weakest point is normally the tensile side of the gear tooth fillet, and it may be anticipated in the gear design by determining the stress at this weakest section of the gear tooth.

Strength Calculations for Spur and Helical Gears.— Many standards and procedures for the design, manufacture, inspection, and application of gears have been published for the guidance of both the users and the manufacturers of gears and gear products. Among such publications, those of the American Gear Manufacturers Association (AGMA) represent an authoritative resource for information and standards on all phases of design, inspection, manufacture, application, and other aspects of gear technology.

American Gear Manufacturers Association Standard, AGMA 2001–B88, *Fundamental Rating Factors and Calculation Methods for Involute Spur and Helical Gear Teeth*, is a revision of, and supersedes, AGMA 218.01. The Standard presents general formulas for rating the pitting resistance and the bending strength of spur and helical involute gear teeth and is intended to establish a common base for rating various types of gears for differing applications and to encourage the maximum practical degree of uniformity and consistency between rating practices in the gear industry. Standard 2001–B88 provides the basis from which more detailed AGMA Application Standards are developed and is a means for calculation of approximate ratings in the absence of such standards. Where applicable AGMA standards exist, they should be used in preference to this Standard. Where no applicable standards exist, numerical values may be estimated for the factors used in the general equations presented in the standard. The values of these factors may vary significantly, depending on the application, system effects, gear accuracy, manufacturing practice, and definition of what constitutes gear failure. Proper evaluation of these factors is essential for realistic ratings.

Information on the geometry factors, I and J, used in pitting resistance and bending strength calculations has been amplified, and moved from the old AGMA 218.01 standard to AGMA 908–B89, *Geometry Factors for Determining the Pitting Resistance and Bending Strength of Spur, Helical, and Herringbone Gear Teeth*. AGMA Standard 908–B89 is covered on Handbook pages 1853–1866.

Copyright 2004, Industrial Press, Inc., New York, NY

Rating Formulas*.— AGMA 2001–B88 provides a method whereby different gear designs can be compared but it is not intended to ensure the performance of assembled gear drive systems. The formulas are applicable for rating the pitting resistance and bending strength of internal and external spur and helical involute gear teeth operating on parallel axes. Gear tooth capacity is influenced by the major factors that affect gear tooth pitting and gear tooth fracture at the fillet radius can be evaluated with these formulas.

Knowledge and judgment required to evaluate the various rating factors can be gained only from years of accumulated experience in designing, manufacturing, and operating gear units. Empirical factors given in the AGMA 2001–B88 standard are general in nature, and other AGMA application standards may use other empirical factors that are more closely suited to the particular field of application. AGMA 2001–B88 is intended for use by the experienced gear designer capable of selecting suitable values for the factors and not for use by engineers inexperienced in gear design and applications.

Exceptions.— The formulas in this Standard are not applicable to other types of gear tooth deterioration such as plastic yielding, wear, case crushing, and welding and are not applicable when vibratory conditions exceed the limits for the normal operation of the gears (see AGMA 6000–A88, *Specification for Measurement of Lateral Vibration on Gear Units*). The formulas are not applicable when any of the following conditions exist:

5) spur gears with transverse contact ratio less than 1.0; 6) spur or helical gears with transverse contact ratio equal to or greater than 2.0; 7) interference exists between the tips of the teeth and the root fillets; 8) the teeth are pointed; and 9) backlash is zero.

Additional Considerations.— When suitable test results or field data are not available, values for the rating factors should be chosen conservatively. Among other considerations, the following should be taken into account:

Manufacturing Tolerances: Rating factors should be evaluated on the basis of the expected variation of component parts in the production run.

Accuracy: Experimental data from actual gear unit measurements are seldom repeatable within a plus or minus 10 per cent band. Calculated gear ratings are intended to be conservative but the scatter in actual results may exceed 20 per cent.

Misalignment and Deflection of Foundations: Misalignment and deflection of foundations, on which many gear systems depend to maintain alignment of the gear mesh, will adversely affect overall performance.

Deflection due to External Loads: Deflection of supporting housings, shafts, and bearings, due to external overhang, transverse and thrust loads affects tooth contact across the mesh. Deflection varies with load, so it is difficult to obtain good tooth contact at different loads. Generally, deflection due to external loads reduces capacity.

Metallurgy: The allowable stress numbers included in the Standard are a function of melting, casting, forging, and heat treating practices. Hardness, tensile strength, and cleanliness are some of the criteria for determining allowable stress numbers; the allowable values in this Standard are based on 10,000,000 cycles of loading, 99 percent reliability, and unidirectional loading.

Variations in microstructure account for some variation in gear capacity. Higher levels of cleanliness and better metallurgical controls permit use of higher allowable stress values and, conversely, lower quality levels require the use of lower values.

Residual Stress: Any material having a case—core relationship is likely to have residual stresses. Properly managed, these stresses will be compressive at the surface and will enhance the bending strength performance of the gear teeth. Shot peening, case carburiz-

*Extracted from AGMA 2001–B88, Fundamental Rating Factors and Calculation Methods for Involute Spur and Helical Gear Teeth, with the permission of the publisher, American Gear Manufacturers Association, 1500 King Street, Suite 201, Alexandria, Virginia 22314.

Copyright 2004, Industrial Press, Inc., New York, NY

ing, nitriding, and induction hardening are common methods of inducing compressive prestress in the surfaces of gear teeth.

Grinding the tooth surfaces after heat treatment reduces residual compressive stresses; and grinding the tooth surfaces and the root fillet areas may introduce tensile stresses and possibly cracks in these areas if done incorrectly. Care is needed to avoid excessive reductions in hardness and changes in microstructure during the grinding process, and shot peening after grinding is often performed to ensure the presence of residual compressive stresses.

Lubrication: The ratings determined by the formulas in the Standard are only valid when a lubricant of proper viscosity for the load, gear-tooth surface finish, temperature, and pitchline velocity is used. Gears with pitchline velocities of less than 100 ft/min require special design considerations to avoid premature failure from inadequate lubrication.

Velocities greater than 100 ft/min but less than 1000 ft/min frequently require special design considerations even when the lubricants used conform to AGMA 250 recommendations.

With velocities in the range of 1000–0,000 ft/min, lubrication problems may be caused by high temperatures, unsuitable additives in the oil, size of the pinion, inadequate oil viscosity, or tooth finish characteristics. Problems in this speed range are not common in industrial gears but sometimes occur in aerospace and in marine gearing.

From a lubrication standpoint, the design of slower gears should be based on application criteria such as hours of life, degree of reliability needed, and acceptable increases in vibration and noise as the gear teeth wear or deform. At pitchline velocities below 100 ft/min, or 20 rpm input speed, the gear designer may allow for acceptable pitting and wear to occur during the gear life when using these rating practices for other than surface-hardened gearing. Rating of gear teeth due to wear is not covered by this Standard.

System Dynamics: The dynamic response of the system results in additional gear tooth loads due to the relative motions of the connected masses of the driver and the driven equipment. Application factors, C_a and K_a, are intended to account for the operating characteristics of the driving and driven equipment. However, if the operating roughness of the driver, gearbox, or driven equipment causes' an excitation with a frequency near to one of the system's major natural frequencies, resonant vibrations may cause severe overloads that may be several times higher than the nominal load. For more information, refer to AGMA 427.01, *Information Sheet–Systems Considerations for Critical Service Gear Drives*.

Corrosion: Corrosion of the gear tooth surface can have significant detrimental effects on the bending strength and pitting resistance of the teeth. The extent of these corrosion effects is not included in the Standard.

Cold Temperature Operation: For gears operated at temperatures below 320F, special care must be taken to select materials that will have adequate impact properties at the operating temperature. Consideration should be given to

1) low-temperature Charpy impact specification; 2) fracture appearance transition or nil ductility temperature specification; 3) reduction of carbon content to less than 0.4 per cent; and 4) use of higher nickel alloy steels.

Criteria for Gear Tooth Capacity

Relationship of Pitting Resistance and Bending Strength Ratings.— There are two major differences between the pitting resistance and the bending strength ratings. Pitting is a function of the Hertzian contact (compressive) stresses between two cylinders and is proportional to the square root of the applied load. Bending strength is measured in terms of the bending (tensile) stress in a cantilever plate and is directly proportional to this same load. The difference in the nature of the stresses induced in the tooth surface areas and at

Copyright 2004, Industrial Press, Inc., New York, NY

the tooth root is reflected in a corresponding difference in allowable limits of contact and bending stress numbers for identical materials and load intensities.

Analysis of the load and stress modifying factors is similar in each instance, so many of these factors have identical numerical values. The term "gear failure" is itself subjective and a source of considerable disagreement. One observer's "failure" may be another observer's "wearing in." A more complete discussion of "failure" is given in AGMA 110.04, Nomenclature of Gear Tooth Failure Modes.

Pitting Resistance: In most industrial practice, corrective and nonprogresssive initial pitting is not deemed serious. Initial pitting is characterized by small pits that do not extend over the entire face width or profile height of the affected teeth. The definition of acceptable pitting varies widely with gear application. Initial pitting occurs in localized, overstressed areas and tends to redistribute the load by progressively removing high contact spots. Generally, when the load has been reduced or redistributed, the pitting stops.

The pitting resistance formula aims to determine a load rating at which destructive pitting of the teeth does not occur during their design life. The ratings for pitting resistance are based on the formulas developed by Hertz for contact pressure between two curved surfaces, modified for the effect of load sharing between adjacent teeth.

Bending Strength: The bending strength of gear teeth is a fatigue phenomenon related to the resistance to cracking at the tooth root fillet in external gears and at the critical section in internal gears. The basic theory employed in this analysis assumes the gear tooth to be rigidly fixed at its base, thus, the critical stress occurs in the fillet. If the rim supporting the gear tooth is thin relative to the size of the tooth and the gear pitch diameter, another critical stress may occur not at the fillet but in the root area. The rim thickness factor, KB, adjusts the calculated bending stress number for thin rimmed gears.

The strength ratings determined by this Standard are based on plate theory that is modified to consider:

1) the compressive stress at tooth roots caused by the radial component of tooth loading; 2) nonuniform moment distribution resulting from the inclined angle of the load lines on the teeth; 3) stress concentrations at the tooth root fillets; and 4) the load sharing between adjacent teeth in contact.

The intent of the AGMA strength rating formula is to determine the load that can be transmitted for the design life of the gear drive without causing cracking or failure. Occasionally, wear, surface fatigue, or plastic flow may limit bending strength due to stress concentrations around large, sharp cornered pits or wear steps on the tooth surface.

Fundamental Rating Formulas.— The symbols and definitions used in the pitting resistance and bending strength formulas are shown in Table 1. SI units are shown in parentheses in Table 1 and in the text. Where equations require a different format or constant for use with SI units, a second expression is shown after the first and with M included in the equation number at the right.

Pitting Resistance.— The fundamental formula for pitting resistance of gear teeth is

$$S_c = C_p \sqrt{\frac{W_t \times C_a}{C_v} \frac{C_s}{dF} \frac{C_m \times C_f}{I}} \tag{1}$$

where the meaning of the symbols is as shown in Table 1 and,

$$d = \frac{2C}{m_G + 1.0} \quad \text{for external gears} \tag{2}$$

$$d = \frac{2C}{m_G - 1.0} \quad \text{for internal gears} \tag{3}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Symbols Used in Gear Rating Equations

Symbol	Description of Symbols and Units	Symbol	Description of Symbols and Units
C	Operating center distance, in. (mm)	K_R	Reliability factor for bending strength
C_a	Application factor for pitting resistance	K_s	Size factor for bending strength
Cc	Curvature factor at pitchline	K_{SF}	Service factor for bending strength
C_e	Mesh alignment correction factor	K_T	Temperature factor for bending strength
C_f	Surface condition factor for pitting resistance	K_v	Dynamic factor for bending strength
C_G	Gear ratio factor	K_y	Yield strength factor
C_H	Hardness ratio factor for pitting resistance	m	Metric module, nominal in plane of rotation (mm)
C_L	Life factor for pitting resistance	m_B	Back up ratio
C_m	Load distribution factor for pitting resistance	m_G	Gear ratio (never less than 1.0)
C_{ma}	Mesh alignment factor	m_N	Load sharing ratio
C_{mc}	Lead correction factor	m_n	Normal metric module, nominal (mm)
C_{mf}	Face load distribution factor	N	Number of load cycles
C_{mt}	Transverse load distribution factor	N_G	Number of teeth in gear
C_p	Elastic coefficient $[\text{lb/in.}^2]^{0.5}$ $([\text{MPa}]^{0.5})$	N_P	Number of teeth in pinion
C_{pf}	Pinion proportion factor	n_p	Pinion speed rpm
C_{pm}	Pinion proportion modifier	P	Transmitted power, hp (kW)
C_R	Reliability factor for pitting resistance	P_{ac}	Allowable transmitted power for pitting resistance, hp (kW)
C_s	Size factor for pitting resistance	P_{at}	Allowable transmitted power for bending strength, hp (kW)
C_{SF}	Service factor for pitting resistance	P_d	Diametral pitch, nominal, in plane of rotation, in^{-1}
C_T	Temperature factor for pitting resistance	P_{nd}	Normal diametral pitch, nominal, in^{-1}
C_v	Dynamic factor for pitting resistance	P_b	Transverse base pitch, in. (mm)
C_x	Contact height factor	P_x	Axial pitch, in. (mm)
C_ψ	Helical overlap factor	Q_v	Transmission accuracy level number
d	Operating pitch diameter of pinion, in. (mm)	S	Bearing span, in. (mm)
E_G	Modulus of elasticity for gear, lb/in.^2 (MPa)	S_I	Pinion offset, in. (mm)
E_p	Modulus of elasticity for pinion, lb/in.^2 (MPa)	S_{ac}	Allowable contact stress number, lb/in.^2 (MPa)
e_t	Total lead mismatch, in. (mm)	S_{at}	Allowable bending stress number, lb/in.^2 (MPa)

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. ***(Continued)*** **Symbols Used in Gear Rating Equations**

Symbol	Description of Symbols and Units	Symbol	Description of Symbols and Units
f_p	Pinion surface finish, microinches rms	S_{ay}	Allowable yield stress number, lb/in.^{2} (MPa)
F	Net face width of narrowest member, in. (mm)	S_c	Contact stress number, lb/in.^{2} (MPa)
G	Tooth stiffness constant, lb/in.^{2} (MPa)	S_t	Bending stress number, lb/in.^{2} (MPa)
H_{BG}	Brinell hardness of gear	T	Transmitted pinion torque, lb-in. (N-m)
H_{Bp}	Brinell hardness of pinion	t_R	Gear rim thickness, in. (mm)
h_c	Minimum total case depth for nitrided gears, in. (mm)	t_o	Normal tooth thickness at top land of gear, in. (mm)
h_e	Minimum effective case depth for carburized gears, in. (mm)	U_{at}	Allowable unit load for bending strength, lb/in.^{2} (MPa)
$h_{e\,max}$	Maximum effective case depth, in. (mm)	U_c	Core hardness coefficient
h_t	Gear tooth whole depth, in. (mm)	U_H	Hardening process factor
I	Geometry factor for pitting resistance	U_L	Unit load for bending strength, lb/in.^{2} (MPa)
J	Geometry factor for bending strength	v_t	Pitch line velocity at operating pitch diameter, ft/min (m/s)
K	Contact load factor for pitting resistance, lb/in.^{2} (MPa)	$v_{t\,max}$	Pitch line velocity maximum at operating pitch diameter, ft/min (m/s)
K_a	Application factor for bending strength	W_d	Incremental dynamic tooth load, lb (N)
K_{ac}	Allowable contact load factor, lb/in.^{2} (MPa)	W_{max}	Maximum peak tangential load, lb (N)
K_B	Rim thickness factor	W_t	Transmitted tangential load, lb (N)
K_f	Stress correction factor	Y	Tooth form factor
K_L	Life factor for bending strength	Z	Length of action in transverse plane, in. (mm)
K_m	Load distribution factor for bending strength	μ_G	Poisson's ratio for gear
		μ_P	Poisson's ratio for pinion
		ϕ_t	Operating transverse pressure angle
		ψ_s	Helix angle at standard pitch diameter
		ψ_b	Base helix angle

Allowable Contact Stress Number: The relation of calculated contact stress number (graphed in Fig. 1) to the allowable contact stress number is

$$S_c \le S_{ac}\frac{C_L C_H}{C_T C_R} \tag{4}$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Allowable Contact Stress Number for Steel Gears, S_{ac}

Pitting Resistance Power Rating.— The pitting resistance power rating is given by

$$P_{ac} = \frac{n_p \times F}{12600} \frac{I \times C_v}{C_s \times C_m \times C_f \times C_a} \left(\frac{d \times S_{ac}}{C_p} \frac{C_L \times C_H}{C_T \times C_R} \right)^2 \tag{5}$$

$$P_{ac} = \frac{n_p \times F}{1.91 \times 10^7} \frac{I \times C_v}{C_s \times C_m \times C_f \times C_a} \left(\frac{d \times S_{ac}}{C_p} \frac{C_L \times C_H}{C_T \times C_R} \right)^2 \tag{5a}$$

In using Formula (5) and (5a), the ratings of both pinion and gear must be calculated to evaluate differences in material properties and the number of cycles under load. The pitting resistance power rating is based on the lowest value of the product $S_{ac}\, C_L C_H$ for each of the mating gears.

Contact Load Factor, *K*.— In some industries, pitting resistance is rated in terms of a K factor:

$$K = \frac{W_t}{dF} \times \frac{1}{C_G} \tag{6}$$

$$\text{for external geras,} \quad C_G = \frac{N_G}{N_G + N_P} \tag{7}$$

$$\text{for internal geras,} \quad C_G = \frac{N_G}{N_G - N_P} \tag{8}$$

In terms of this Standard, the allowable K factor is defined as

$$K_{ac} = \frac{I}{C_G} \frac{C_v}{C_a \times C_s \times C_m \times C_f} \left(\frac{S_{ac} \times C_L \times C_H}{C_p \times C_T \times C_R} \right)^2 \tag{9}$$

The allowable contact load factor, K_{ac}, is the lowest of the ratings calculated using the different values of s_{ac},C_L, and C_H for pinion and gear.

Copyright 2004, Industrial Press, Inc., New York, NY

Bending Strength.— The fundamental formula for bending stress number in a gear tooth is

$$s_t = \frac{W_t \times K_a}{K_v}\frac{P_d}{F}\frac{K_s \times K_m \times K_B}{J} \tag{10}$$

where $P_d = P_{nd}$ for spur gears. For helical gears, P_d is given by Equation (11),

$$s_t = \frac{W_t \times K_a}{K_v}\frac{I}{F \times m}\frac{K_s \times K_m \times K_B}{J} \tag{10a}$$

where $m = m_n$ for spur gears. For helical gears m is given by Equation (11a):

$$P_d = \frac{\pi}{p_x \tan\psi_s} = P_{nd}\cos\psi_s \tag{11}$$

$$m = \frac{P_x \times \tan\psi_s}{\pi} = \frac{m_n}{\cos\psi_s} \tag{11a}$$

where ψ_s is given by Equation (12) or (12a)

$$\psi_s = \operatorname{asin}\left(\frac{\pi}{p_x \times P_{nd}}\right) \tag{12}$$

$$\psi_s = \operatorname{asin}\left(\frac{\pi \times m_n}{p_x}\right) \tag{12a}$$

Allowable Bending Stress Number.— The relation of calculated bending stress number to allowable bending stress number is

$$S_t \le \frac{S_{at} \times K_L}{K_T \times K_R} \tag{13}$$



Fig. 2. *Allowable Bending Stress Number for Steel Gears* s_{at}

Copyright 2004, Industrial Press, Inc., New York, NY

Bending Strength Power Rating.— The bending strength power rating is

$$P_{at} = \frac{n_p \times d \times K_v}{126000 \times K_a} \frac{F}{P_d} \frac{J}{K_s \times K_m \times K_B} \frac{s_{at} \times K_L}{K_R \times K_T} \tag{14}$$

$$P_{at} = \frac{n_p \times d \times K_v}{1.91 \times 10^7 \times K_a} \frac{F \times m \times J}{K_s \times K_m \times K_B} \frac{s_{at} \times K_L}{K_R \times K_T} \tag{14a}$$

The ratings of both pinion and gear must be calculated to evaluate differences in geometry factors, number of load cycles, and material properties. The bending strength power rating is based on the lowest value of the term $S_{at}K_LJ/K_B$ for each of the mating gears.

In some industries, the bending strength is rated in terms of unit load:

$$U_L = \frac{(W_t \times P_{nd})}{F} \tag{15}$$

$$U_L = \frac{W_t}{(F \times m)} \tag{15a}$$

The allowable unit load, U_{at}, is the lowest of the ratings calculated using the different values of S_{at}, K_B, K_L, and J for pinion and gearin Equation (16):

$$U_{at} = \frac{J}{\cos\psi} \frac{K_v}{K_a \times K_m \times K_s \times K_B} \frac{s_{at} \times K_L}{K_R \times K_T} \tag{16}$$

Values for Factors Applied in Fundamental Equations.— Values for the various factors used in the pitting resistance and bending strength rating equations are discussed and explained in greater detail in the Standard and its appendices than can be provided here. The following paragraphs are intended by the Editors to provide values for some of these factors suitable for making approximations to the ratings of pairs of mating gears without the refinements used by experienced gear designers.

Rim Thickness Factor K_B.— The rim thickness factor, K_B, is used to adjust the calculated bending stress number for thin rimmed gears, the value of the factor depending upon the backup ratio,

$$m_B = \frac{t_R}{h_t} \tag{17}$$

If m_B is equal to or greater than 1.2, then K_B may be taken as 1.0. For values of m_B less than 1.2, see the information in Appendix C following the Standard.

Geometry Factors *I* and *J*.— The geometry factors I and J for pitting resistance and bending strength, respectively, are described, along with selected typical values, beginning on **page 1853**.

Transmitted Tangential Load, W_t.— In most gear applications the torque is not constant, so the transmitted tangential load will vary. To obtain values of the operating transmitted tangential load, W_t, the values of power and speed at which the driven device will operate should be used. If the rating is calculated on the basis of uniform load, then the transmitted tangential load is

$$W_t = \frac{33000 \times P}{v_t} = \frac{2 \times T}{d} = \frac{126000 \times P}{n_p \times d} \tag{18}$$

$$W_t = \frac{1000 \times P}{v_t} = \frac{2000 \times T}{d} = \frac{1.91 \times 10^7 \times P}{n_p \times d} \tag{18a}$$

Copyright 2004, Industrial Press, Inc., New York, NY

where,

$$v_t = \frac{(\pi \times n_p \times d)}{12} \tag{19}$$

$$v_t = \frac{(\pi \times n_p \times d)}{60000} \tag{19a}$$

Nonuniform Load: When the transmitted load is not uniform, consideration should be given not only to the peak load and its anticipated number of cycles, but also to intermediate loads and their duration. This type of load is often considered a duty cycle and may be represented by a load spectrum. The cumulative fatigue effect of the duty cycle is then considered in rating the gearset, A method of calculating the effects of the loads under such conditions is given in Appendix B of the Standard.

Dynamic Factors, C_v and K_d.— Dynamic factors account for internally generated gear tooth loads, which are induced by nonconjugate meshing action of the gear teeth. Even if the input torque and speed are constant, significant vibration of the gear masses, and therefore dynamic tooth forces, can exist. These forces result from the relative displacements between the gears as they vibrate in response to an excitation known as "transmission error." Ideally, a gearset would have a uniform velocity ratio between the input and output rotation. Transmission error is defined as the departure from uniform relative angular motion of the pair of meshing gears. It is influenced by all the deviations from the ideal gear tooth form.

The dynamic factor relates the total tooth load, including internal dynamic effects, to the transmitted tangential tooth load:

$$C_v = K_v = \frac{W_t}{W_d \times W_t} \tag{20}$$

where W_d = incremental dynamic tooth load due to the dynamic response of the gear pair to the transmission error excitation, excluding the transmitted tangential load W_t.

Excitation: The transmission error contributing to the dynamic factors is influenced by:

1) Manufacturing variations such as spacing, profile, lead, and runout.

2) Gear mesh stiffness variation as the gear teeth pass through the meshing cycle. This source of excitation is especially pronounced in spur gears without profile modification. Spur gears with properly designed profile modification, and helical gears with axial contact ratios greater than 1.0, have a smaller stiffness variation.

3) Transmitted load. Since elastic deflections are load dependent, gear tooth profile modifications can be designed to give a uniform velocity ratio at only one load magnitude.

4) Pitchline velocity. The frequencies of the excitation depend on the pitchline velocity.

5) Dynamic imbalance of the gears and shafts.

6) Excessive wear and plastic deformation of the gear tooth profiles increase the amount of transmission error.

7) Shaft alignment. Gear tooth alignment is influenced by load and thermal distortions of the gears, shafts, bearings, and housings, and by manufacturing variations.

8) Tooth friction induced excitation.

Dynamic Response: The dynamic tooth forces are influenced by:

1) Mass of the gears, shafts, and other major internal components.

2) Stiffness of the gear teeth, gear blanks, shafts, bearings, and gear housings.

3) Damping. The principal source of coulomb or viscous damping is the shaft bearings. Generally, oil film bearings provide greater damping than rolling element bearings. Other sources of damping include the hysteresis of the gear shafts, and viscous damping at sliding interfaces and shaft couplings.

Copyright 2004, Industrial Press, Inc., New York, NY

Resonance: When an excitation frequency coincides with a natural frequency, the resonant response is limited only by the damping, and high dynamic loads may result. The dynamic factors C_v and K_d do not apply to resonance.

Gear Pair Resonance: If a particular frequency of the transmission error excitation is close to the natural frequency of the gear masses, or some multiple of the natural frequency such as ½ or 2, a resonant vibration may cause high dynamic tooth forces due to large relative displacements of the gear masses. The dynamic factors C_v and K_d do not account for gear pair resonance and operation in this regime is to be avoided.

Gear Blank Resonance: Gear blanks may have natural frequencies within the operating speed range. If the gear blank is excited by a frequency that is close to one of its natural frequencies, the resonant deflections may cause high dynamic tooth loads. This phenomenon occurs more frequently in high speed, light weight gear blanks, but can also occur in other thin rimmed or thinwebbed blanks. The dynamic factors C_v and K_d do not account for gear blank resonance. A separate investigation is recommended when these conditions arise.

System Resonance: The gearbox is one component of a system comprised of a power source, gearbox, driven equipment, and interconnecting shafts and couplings. The dynamic response of this system depends on the distribution of the masses, stiffness, and damping. In certain designs, a system may possess a torsional natural frequency close to an excitation frequency associated with an operating speed. Under these resonant conditions the dynamic tooth loads may be high, and operation near such a system resonance is to be avoided. The dynamic factors C_v and K_d do not include considerations of the dynamic loads due to torsional vibration of the gear system. These loads must be included with other externally applied forces in the application factors C_a and K_a. For critical drives, a separate dynamic analysis of the entire system is recommended.

Shaft Critical Speeds: Owing to their high bending stiffness, the natural frequency of lateral vibrations of the gear shafts are usually much higher than the operating speeds. However, for high speed gears it is recommended that the critical speeds be analyzed to ensure that they are well removed from the operating speed range. The dynamic factors C_v and K_d do not account for the dynamic tooth loads due to this mode of vibration.

Nonlinear Resonance: Large cyclical variation in gear mesh stiffness and impact loads may lead to additional regions of resonance and instability. This problem appears primarily with lightly loaded, lightly damped spur gears that do not have profile modifications.

Approximate Dynamic Factors: Fig. 3 shows dynamic factors that can be used in the absence of specific knowledge of the dynamic loads. The curves of Fig. 3 are based on equations in the Standard derived from empirical data and do not account for resonance.

Choice of which of curves 5 through 11 of Fig. 3 to use should be based on transmission error. When transmission error data are unavailable, it is reasonable to use pitch (spacing) and profile accuracy. Q_v is the transmission accuracy level number. It can be the same as the quality number for the lowest quality member in the mesh from AGMA 2000–A88 when manufacturing techniques ensure equivalent transmission accuracy, or when the pitch (spacing) and profile accuracy are the same as AGMA 2000–A88 tolerances.

Owing to the approximate nature of the empirical curves and the lack of measured tolerance values at the design stage, the dynamic factor curve should be selected based on experience with the manufacturing methods and operating considerations of the design.

The curves in Fig. 3 are referenced only by spacing and profile, and actual dynamic load is influenced by many other factors, so slight variations from the selected tolerances are not considered significant to the gearset rating.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 3. Dynamic Factors, C_v and K_d

Very Accurate Gearing: Where gearing is manufactured using process controls that correspond to $Q_v \geq 12$ limits, or where the design and manufacturing techniques ensure a low transmission error equivalent to this accuracy, values of C_v and K_d between 0.90 and 0.98 may be used, depending on the specifier's experience with similar applications and the degree of accuracy actually achieved. To use these values, the gearing must be maintained in accurate alignment and adequately lubricated so that its accuracy is maintained under the operating conditions. Spur gears should have properly designed profile modification and helical gears should have an axial contact ratio greater than 1.0.

Curves Numbered 6 through 11 on Fig. 3: These curves are generated by equations in the Standard for values of Q_v such that $6 \leq Q_v \geq 11$.

Unity Dynamic Factor: When the known dynamic loads (from analysis or experience) are added to the nominal transmitted load, then the dynamic factor can be taken to be 1.0.

Application Factors, C_a and K_a.— These application factors make allowance for any externally applied loads in excess of the nominal tangential load W_t. Application factors can only be established after considerable field experience is gained in a particular application.

In determining the application factor, consideration should be given to the fact that many prime movers develop momentary peak torques appreciably greater than those determined by the nominal ratings of either the prime mover or the driven equipment. Many possible sources of overload should be considered. Some of these are system vibrations, acceleration torques, overspeeds, variations in system operation, split path load sharing among multiple prime movers, and changes in process load conditions. When operating near a critical speed of the drive system, a careful analysis of conditions must be made.

Service Factors, C_{SF} and K_{SF}.— These service factors have been used to include the combined effects of C_L, C_R, C_a and K_L, K_R, K_a, respectively, in an empirically determined single factor. The mathematical contribution of each of these factors has not been established, so that, in the absence of more specific load data, a service factor may be used. When a ser-

Copyright 2004, Industrial Press, Inc., New York, NY

vice factor is used, the power rating formulas [Equation (5) and (5a)] would be modified as follows:

$$P_{ac} = \frac{n_p \times F}{126000} \frac{I \times C_v}{C_{sf} \times C_s \times C_m \times C_f} \left(\frac{d \times s_{ac}}{C_p} \frac{C_H}{C_T} \right) \quad (21)$$

$$P_{ac} = \frac{n_p \times F}{1.91 \times 10^7} \frac{I \times C_v}{C_{sf} \times C_s \times C_m \times C_f} \left(\frac{d \times s_{ac}}{C_p} \frac{C_H}{C_T} \right) \quad (21a)$$

$$P_{at} = \frac{n_p \times d \times K_v}{126000 \times K_{SF}} \frac{F}{P_d} \frac{J}{K_s \times K_m \times K_B} \frac{s_{at}}{K_T} \quad (22)$$

$$P_{at} = \frac{n_p \times d \times K_v}{1.91 \times 10^7 \times K_{SF}} \frac{F \times m \times J}{K_s \times K_m \times K_B} \frac{s_{at}}{K_T} \quad (22a)$$

where C_{SF} and K_{SF} are service factors for pitting resistance and bending strength, respectively.

Teeth of both the pinion and the gear must be checked to account for differences in material properties, geometry factors, and the number of cycles under load. The power rating is then based on the lowest values of the following expressions for each of the mating gears:

for pitting resistance $\frac{(s_{ac} \times C_H)^2}{C_{SF}}$, and for bending strength $\frac{s_{at} \times J}{K_{SF}}$.

Elastic Coefficient, C_p.— The elastic coefficient, C_p, is defined by the equation

$$C_p = \sqrt{\frac{1.0}{\pi \left[\left(\frac{1.0 - \mu_P^2}{E_p} \right) \div \left(\frac{1.0 - \mu_G^2}{E_G} \right) \right]}} \quad (23)$$

The value of C_p for a steel gear meshing with a steel pinion is 2300 $[\text{lb/in.}^2]^{0.5}$, or 191 $(\text{MPa})^{0.5}$, approximately. Approximate values for other combinations of materials are given in the Standard.

Surface Condition Factor, C_f.— The surface finish factor used only in the pitting resistance formulas has not yet been established for conditions where there is a detrimental surface finish effect. Where such effects are encountered, a surface condition factor greater than unity should be used.

Size Factors, C_s and K_s.— The size factor reflects nonuniformity of material properties and depends primarily on tooth size, diameter of parts, ratio of tooth size to diameter of part, face width, area of stress pattern, ratio of case depth to tooth size, and hardenability and heat treatment of materials. Size factors have not yet been established for conditions where there is a detrimental size effect, but the factor may be taken as unity for most gears provided that a proper choice of steel is made for the size of the part and its heat treatment and hardening processes.

Load Distribution Factors, C_m and K_m.— The load distribution factor modifies the rating equations to reflect the nonuniform distribution of the load along the lines of contact. The amount of nonuniformity of the load distribution is caused by, and is dependent on the following influences:

1) The gear tooth manufacturing accuracy: lead, profile, and spacing;
2) alignment of the axes of rotation of the pitch cylinders of the mating gear elements;

Copyright 2004, Industrial Press, Inc., New York, NY

3) elastic deflections of gear unit elements: shafts, bearings, housings, and foundations that support the gear elements;

4) bearing clearances;

5) Hertzian contact and bending deformations at the tooth surface;

6) thermal expansion and distortion due to operating temperature (especially on wide face gearing);

7) centrifugal deflections due to operating speed;

8) tooth crowning and end relief.

Any of these influences that affect a given application should be evaluated by appropriate analysis when possible.

Values for C_m and K_m: The load distribution factor is defined to be the peak load intensity divided by the average, or uniformly distributed load intensity; i.e., the ratio of peak to mean loading. The magnitude is influenced by two components, namely, C_{mf} = face load distribution factor and C_{mt} = transverse load distribution factor that accounts for nonuniform load sharing among load sharing teeth. The load distribution factor is affected primarily by the correctness of the profiles of mating teeth, i.e., profile modification and profile error. The value of the factor may be taken as 1.0 because the Standard has not yet established procedures to evaluate its influence. If C_{mt} is taken as 1.0, then $C_m = K_m = C_{mf}$.

The face load distribution factor C_{mf} accounts for the nonuniform distribution of load across the gearing face width. The magnitude of C_{mf} is defined as the peak load intensity divided by the average load intensity across the face width. Two methods of determining C_{mf} are given in the Standard, an empirical method and an analytical method. These two methods sometimes yield significantly different results.

Empirical Method: The empirical method requires a minimum amount of information and is recommended for relatively stiff designs that meet the following requirements:

1) Ratio of net face width to pinion pitch diameter is less than or equal to 2.0; 2) the gear elements are mounted between bearings (not overhung); 3) face width up to 40 in.; and ; and 4) contact across full face width of narrowest member when loaded.

Other restrictions apply to the use of this method. For details of these restrictions and how the method is applied, the Standard should be consulted.

Analytical Method: This method is based on theoretical calculation of values of elastic tooth deformation under load and lead mismatch. Knowledge of the design, manufacturing, and mounting are required to evaluate the load distribution factor. Calculated results should be compared with past experience as it may be necessary to reevaluate other rating factors to arrive at a rating consistent with past experience. As explained in the Standard, the analytical method assumes that mismatch between the teeth is a straight line. This approach usually yields load distribution factors larger than those used in the past. Another method, using true deflection between the teeth (which is not straight line deflection), has resulted in calculated values closer to those used in the past, but it has not been demonstrated that either method is more accurate. Further study may produce other, more accurate, methods.

In using the analytical method, if high values of the gear tooth stiffness constant are used ($G = 2{,}000{,}000$) or high values of total lead mismatch e_t are assumed, the C_{mf} values calculated will be much more conservative than those obtained by the empirical method. If C_{mf} values calculated are in excess of 2.0, indicating less than full face contact, it may be desirable to revise the design by improving the configuration of bearings, shaft diameters, aspect ratio, and center distance to lower C_{mf}. It may be possible to lower C_{mf} by modifying leads of the parts. The assumed values of e_t and G have a large effect on C_{mf}, so there are times when experimental verification of C_{mf} may be necessary.

Copyright 2004, Industrial Press, Inc., New York, NY

The analytical method is valid for any gear design and is recommended for the following conditions:
1) ratio of net face width to pinion pitch diameter, F/D, is equal or greater than 2.0 (for double helical gears the gap is not included in the face width); 2) applications with overhung gear elements; 3) applications with long shafts subject to large deflections or where deflections under load reduce width of contact; and 4) applications where contact does not extend across the full face of narrowest member when loaded.

For designs that have high crowns to centralize tooth contact under deflected conditions, the factors C_m and K_m may be conservatively approximated by this method. For the most commonly encountered condition, contact across the entire face width under normal operating load, the face load distribution factor expressions are

$$\text{for spur gearing:} \quad C_{mf} = 1.0 + \frac{G \times e_t \times F}{2 \times W_t} \tag{24}$$

$$\text{and, for helical gearing:} \quad C_{mf} = 1.0 + \frac{G \times e_t \times Z \times F}{1.8 \times W_t} \tag{25}$$

If the total contact length under normal operating load is less than the face width, the expressions for the load distribution factor are

$$\text{for spur gearing:} \quad C_{mf} = \sqrt{\frac{2.0 \times G \times e_t \times F}{W_t}} \tag{26}$$

$$\text{and, for helical gearing:} \quad C_{mf} = \sqrt{\frac{2.0 \times G \times e_t \times Z \times F}{W_t \times P_b}} \tag{27}$$

where G = tooth stiffness constant, lb/in./in. of face (MPa), the average mesh stiffness of a single pair of teeth in the normal direction. The usual range of this value that is compatible with this analysis is $1.5–2.0 \times 10^6$ lb/in.^{2} ($1.0–1.4 \times 10^4$ MPa). The most conservative value is the highest. e_t = total lead mismatch between mating teeth, in loaded condition, in. (mm). Z = length of action in transverse plane, from Equation (17) on page 2995, in. (mm). P_b = transverse base pitch, in. (mm).

The total mismatch, e_t, is a virtual separation between the tooth profiles at the end of the face width which is composed of the static, no load separation plus a component due to the elastic load deformations. This total mismatch is influenced by all the items listed under Load Distribution Factors except the Hertzian contact stress and bending deformations of the gear teeth, which are accounted for by the tooth stiffness constant G. Evaluation of e_t, is difficult but it is critical to the reliability of the analytical method. An iterative computer program may be used, but in critical applications full scale testing may be desirable.

Allowable Stress Numbers, S_{ac} and S_{at}.— The allowable stress numbers depend on 1) material composition and cleanliness; 2) mechanical properties; 3) residual stress; 4) hardness and; and 5) type of heat treatment, surface or through hardened.

An allowable stress number for unity application factor, 10 million cycles of load application, 99 per cent reliability and unidirectional loading, is determined or estimated from laboratory and field experience for each material and condition of that material. This stress number is designated S_{ac} and S_{at} .The allowable stress numbers are adjusted for design life cycles by the use of life factors.

The allowable stress numbers for gear materials vary with material composition, cleanliness, quality, heat treatment, and processing practices. For materials other than steel, a range is shown, and the lower values should be used for general design purposes. Data for materials other than steel are given in the Standard.

Copyright 2004, Industrial Press, Inc., New York, NY

Allowable stress numbers for steel gears are established by specific quality control requirements for each material type and grade. All requirements for the quality grade must be met in order to use the stress values for that grade. Details of these quality requirements are given in the Standard.

Reverse Loading: For idler gears and other gears where the teeth are completely reverse loaded on every cycle, 70 per cent of the S_{at} values should be used.



Fig. 4. Effective Case Depth for Carburized Gears, h_e

Case Depth of Surface–Hardened Gears.— The Standard provides formulas to guide the selection of minimum effective case depth at the pitchline for carburized and induction hardened teeth based on the maximum shear from contact loading.



Fig. 5. Minimum Total Case Depth for Nitrided Gears, h_c

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. 5 shows values that have a long history of successful use for carburized gears and can be used for such gears.

For nitrided gears, case depth is specified as the total case depth h_c, which is defined as the depth below the surface at which the hardness has dropped to110 per cent of the core hardness. Minimum total case depths for nitrided gears are shown in Fig. 5.

Momentary Overloads.— When the gear is subjected to less than 100 cycles of momentary overloads, the maximum allowable stress is determined by the allowable yield properties rather than the bending fatigue strength of the material. Fig. 6 shows suggested values of the allowable yield strength S_{ay} for through hardened steel. For case hardened gears, the core hardness should be used in conjunction with the table of metallurgical factors affecting the bending stress number for carburized gears shown in the Standard.



Fig. 6. Allowable Yield Strength Number for Steel Gears, S_{ay}

The design should be checked to make sure that the teeth are not permanently deformed. Also, when yield is the governing stress, the stress correction factor K_f is considered ineffective and therefore taken as unity.

Yield Strength.— For through hardened gears up to 400 BHN, a yield strength factor K_y can be applied to the allowable yield strength taken from Fig. 6. This factor is applied at the maximum peak load to which the gear is subjected:

$$S_{ay} \times K_y \geq \frac{W_{max} \times K_a}{K_v} \frac{P_d}{F} \frac{K_s \times K_m}{J \times K_f} \tag{28}$$

$$S_{ay} \times K_y \geq \frac{W_{max} \times K_a \times K_s \times K_m}{K_v \times F \times m \times J \times K_f} \tag{28a}$$

For conservative practice, K_y is taken as 0.5 and for industrial practice, K_y is 0.75.

Hardness Ratio Factor C_H.— The hardness ratio factor depends on (1) gear ratio and (2) Brinell hardness numbers of gear and pinion. When the pinion is substantially harder than the gear, the work hardening effect increases the gear capacity. Typical values of the hard-

Copyright 2004, Industrial Press, Inc., New York, NY

ness ratio factor, C_H, for through hardened gears are shown in Fig. 7. These values apply to the gear only, not to the pinion.

When surface hardened pinions (48 HRC or harder) are run with through hardened gears (180–400 BHN), a work hardening effect is achieved. The C_H factor varies with the surface finish of the pinion, K_p and the mating gear hardness as shown in Fig. 8.



Fig. 7. Hardness Ratio Factor, C_H (Through Hardened)

Life Factors C_L and K_L.— These life factors adjust the allowable stress numbers for the required number of cycles of operation. In the Standard, the number of cycles, N, is defined as the number of mesh contacts under load of the gear tooth being analyzed. Allowable stress numbers are established for 10,000,000 tooth load cycles at 99 per cent reliability. The life cycle factors adjust the allowable stress numbers for design lives other than 10,000,000 cycles.

The life factor accounts for the *S/N* characteristics of the gear material as well as for the gradually increased tooth stress that may occur from tooth wear, resulting in increased dynamic effects and from shifting load distributions that may occur during the design life of the gearing. A C_L or K_L value of 1.0 may be used beyond 10,000,000 cycles, where justified by experience.

Life Factors for Steel Gears: Insufficient data exist to provide accurate life curves for every gear and gear application. However, experience suggests life curves for pitting and strength of steel gears are as shown in Figs. 9 and 10. These figures do not include data for nitrided gears. The upper portions of the shaded zones are for general commercial applications. The lower portions of the shaded zones are typically used for critical service applications where little pitting and tooth wear are permissible and where smoothness of operation and low vibration levels are required. When gear service ratings are established by the use

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. Hardness Ratio Factor, C_H (Surface Hardened Pinions)

of service factors, life factors C_L and K_L should be set equal to 1.0 for the determination of the gear tooth rating.

Localized Yielding.— If the product of $S_{at}\,K_L$ exceeds the allowable yield stress S_{ay} of Fig. 6, localized yielding of the teeth may occur. In some applications this yielding is not acceptable. In others, where profile and motion transmission accuracies are not critical, the yielding may be acceptable for limited life.

Reliability Factors, C_R and K_R.— These reliability factors account for the effect of the normal statistical distribution of failures found in materials testing. The allowable stress numbers given in the tables in the Standard are based on a statistical probability of 1 failure in 100 at 10,000,000 cycles. Table 2 contains reliability factors which may be used to modify these allowable stresses to change that probability. These numbers are based on data developed for bending and pitting failure by the U.S. Navy. Other values may be used if specific data are available.

When strength rating is based on yield strength, S_{ay} the values of K_y given in the paragraph, Yield Strength, should be used instead of K_R.

Temperature Factors C_T and K_T.— The temperature factor is generally taken as 1 when gears operate with temperatures of oil or gear blank not over 250°F (120°C). At temperatures above 250°F, the factors are given a value greater than 1.0 to allow for the effect of temperature on oil film and material properties. Consideration must be given to the loss of hardness and strength of some materials due to the tempering effect of temperatures over 350°F (175°C).

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 9. Pitting Resistance Life Factor, C_L



Fig. 10. Bending Strength Life Factor, K_L

Table 2. Reliability Factors, C_R and K_R

Requirement of Application	C_R, K_R[a]	Requirement of Application	C_R, K_R
Fewer than 1failure in 10,000	1.50	Fewer than 1failure in 100	1.00
Fewer than 1failure in 1,000	1.25	Fewer than 1failure in 10	0.85[b]

[a] Tooth breakage is sometimes considered a greater hazard than pitting. In such instances a value of K_R greater than C_R is selected.

[b] At this value plastic flow might occur rather than pitting.

Copyright 2004, Industrial Press, Inc., New York, NY

Worm Gearing

Worm Gearing Classification.— Worm gearing may be divided into two general classes, fine-pitch worm gearing, and coarse-pitch worm gearing. Fine-pitch worm gearing is segregated from coarse-pitch worm gearing for the following reasons:

1) Fine-pitch worms and wormgears are used largely to transmit motion rather than power. Tooth strength except at the coarser end of the fine-pitch range is seldom an important factor; durability and accuracy, as they affect the transmission of uniform angular motion, are of greater importance.

2) Housing constructions and lubricating methods are, in general, quite different for fine-pitch worm gearing.

3) Because fine-pitch worms and wormgears are so small, profile deviations and tooth bearings cannot be measured with the same accuracy as can those of coarse pitches.

4) Equipment generally available for cutting fine-pitch wormgears has restrictions which limit the diameter, the lead range, the degree of accuracy attainable, and the kind of tooth bearing obtainable.

5) Special consideration must be given to top lands in fine-pitch hardened worms and wormgear-cutting tools.

6) Interchangeability and high production are important factors in fine-pitch worm gearing; individual matching of the worm to the gear, as often practiced with coarse-pitch precision worms, is impractical in the case of fine-pitch worm drives.

American Standard Design for Fine-pitch Worm Gearing (ANSI B6.9-1977).— This standard is intended as a design procedure for fine-pitch worms and wormgears having axes at right angles. It covers cylindrical worms with helical threads, and wormgears hobbed for fully conjugate tooth surfaces. It does not cover helical gears used as wormgears.

Hobs: The hob for producing the gear is a duplicate of the mating worm with regard to tooth profile, number of threads, and lead. The hob differs from the worm principally in that the outside diameter of the hob is larger to allow for resharpening and to provide bottom clearance in the wormgear.

Pitches: Eight standard axial pitches have been established to provide adequate coverage of the pitch range normally required: 0.030, 0.040, 0.050, 0.065, 0.080, 0.100, 0.130, and 0.160 inch.

Axial pitch is used as a basis for this design standard because: 1) Axial pitch establishes lead which is a basic dimension in the production and inspection of worms; 2) the axial pitch of the worm is equal to the circular pitch of the gear in the central plane; and 3) only one set of change gears or one master lead cam is required for a given lead, regardless of lead angle, on commonly-used worm-producing equipment.

Lead Angles: Fifteen standard lead angles have been established to provide adequate coverage: 0.5, 1, 1.5, 2, 3, 4, 5, 7, 9, 11, 14, 17, 21, 25, and 30 degrees.

This series of lead angles has been standardized to: 1) Minimize tooling; 2) permit obtaining geometric similarity between worms of different axial pitch by keeping the same lead angle; and 3) take into account the production distribution found in fine-pitch worm gearing applications.

For example, most fine-pitch worms have either one or two threads. This requires smaller increments at the low end of the lead angle series. For the less frequently used thread numbers, proportionately greater increments at the high end of the lead angle series are sufficient.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. Formulas for Proportions of American Standard Fine-pitch Worms and Wormgears *ANSI B6.9-1977*

LETTER SYMBOLS

P = Circular pitch of wormgear
P = axial pitch of the worm, P_x, in the central plane
P_x = Axial pitch of worm
P_n = Normal circular pitch of worm and wormgear = $P_x \cos \lambda = P \cos \psi$
λ = Lead angle of worm
ψ = Helix angle of wormgear
n = Number of threads in worm
N = Number of teeth in wormgear
$N = nm_G$
m_G = Ratio of gearing = $N \div n$



Item	Formula	Item	Formula
WORM DIMENSIONS		WORMGEAR DIMENSIONS[a]	
Lead	$l = nP_x$	Pitch Diameter	$D = NP \div \pi = NP_x \div \pi$
Pitch Diameter	$d = l \div (\pi \tan \lambda)$	Outside Diameter	$D_o = 2C - d + 2a$
Outside Diameter	$d_o = d + 2a$	Face Width	$F_{G\min} = 1.125 \times \sqrt{(d_o + 2c)^2 - (d_o - 4a)^2}$
Safe Minimum Length of Threaded Portion of Worm[b]	$F_W = \sqrt{D_o^2 - D^2}$		
DIMENSIONS FOR BOTH WORM AND WORMGEAR			
Addendum	$a = 0.3183P_n$	Tooth thickness	$t_n = 0.5P_n$
Whole Depth	$h_t = 0.7003P_n + 0.002$	Approximate normal pressure angle[c]	$\phi_n = 20$ degrees
Working Depth	$h_k = 0.6366P_n$		
Clearance	$c = h_t - h_k$	Center distance	$C = 0.5\,(d + D)$

[a] Current practice for fine-pitch worm gearing does not require the use of throated blanks. This results in the much simpler blank shown in the diagram which is quite similar to that for a spur or helical gear. The slight loss in contact resulting from the use of non-throated blanks has little effect on the load-carrying capacity of fine-pitch worm gears. It is sometimes desirable to use topping hobs for producing wormgears in which the size relation between the outside and pitch diameters must be closely controlled. In such cases the blank is made slightly larger than D_o by an amount (usually from 0.010 to 0.020) depending on the pitch. Topped wormgears will appear to have a small throat which is the result of the hobbing operation. For all intents and purposes, the throating is negligible and a blank so made is not to be considered as being a throated blank.

[b] This formula allows a sufficient length for fine-pitch worms.

[c] As stated in the text on page 3008, the actual pressure angle will be slightly greater due to the manufacturing process.

All dimensions in inches unless otherwise indicated.

Pressure Angle of Worm: A pressure angle of 20 degrees has been selected as standard for cutters and grinding wheels used to produce worms within the scope of this Standard because it avoids objectionable undercutting regardless of lead angle.

Although the pressure angle of the cutter or grinding wheel used to produce the worm is 20 degrees, the normal pressure angle produced in the worm will actually be slightly greater, and will vary with the worm diameter, lead angle, and diameter of cutter or grinding wheel. A method for calculating the pressure angle change is given under the heading *Effect of Production Method on Worm Profile and Pressure Angle*.

Copyright 2004, Industrial Press, Inc., New York, NY

Pitch Diameter Range of Worms: The minimum recommended worm pitch diameter is 0.250 inch and the maximum is 2.000 inches.Pitch diameters for all possible combinations of lead and lead angle, together with the number of threads for each lead, are given in Table 2a and 2b.

Tooth Form of Worm and Wormgear: The shape of the worm thread in the normal plane is defined as that which is produced by a symmetrical double-conical cutter or grinding wheel having straight elements and an included angle of 40 degrees.

Because worms and wormgears are closely related to their method of manufacture, it is impossible to specify clearly the tooth form of the wormgear without referring to the mating worm. For this reason, worm specifications should include the method of manufacture and the diameter of cutter or grinding wheel used. Similarly, for determining the shape of the generating tool, information about the method of producing the worm threads must be given to the manufacturer if the tools are to be designed correctly.

The worm profile will be a curve that departs from a straight line by varying amounts, depending on the worm diameter, lead angle, and the cutter or grinding wheel diameter. A method for calculating this deviation is given in the Standard. The tooth form of the wormgear is understood to be made fully conjugate to the mating worm thread.

Proportions of Fine-pitch Worms and Wormgears.— Hardened worms and cutting tools for wormgears should have adequate top lands. To automatically provide sufficient top lands, regardless of lead angle or axial pitch, the addendum and whole depth proportions of fine-pitch worm gearing are based on the normal circular pitch. Tooth proportions based on normal pitch for all combinations of standard axial pitches and lead angles are given in Table 3. Formulas for the proportions of worms and worm gears are given in Table 1.

Example 1: Determine the design of a worm and wormgear for a center distance of approximately 3 inches if the ratio is to be 10 to 1; axial pitch, 0.1600 inch; and lead angle, 30 degrees.

From Table 2a and 2b it can be determined that there are eight possible worm diameters that will satisfy the given conditions of lead angle and pitch. These worms have from 3 to 10 threads.

To satisfy the 3-inch center distance requirement it is now necessary to determine which of these eight worms, together with its mating wormgear, will come closest to making up this center distance. One way of doing this is as follows:

First use the formula given below to obtain the approximate number of threads necessary. Then from the eight possible worms in Table 2a and 2b, choose the one whose number of threads is nearest this approximate value:

Approximate number of threads needed for required center distance =

$$\frac{2\pi \times \text{ required center distance}}{P_x(\cot\lambda + m_G)}$$

Approximate number of threads =

$$\frac{2 \times 3.1416 \times 3}{0.1600 \times (1.7320 + 10)} = 10.04 \text{ threads}$$

Of the eight possible worms in Table 2a and 2b, the one having a number of threads nearest this value is the 10-thread worm with a pitch diameter of 0.8821 inch. Since the ratio of gearing is given as 10, N may now be computed as follows: $N = 10 \times 10 = 100$ teeth (from Table 1)

Other worm and wormgear dimensions may now be calculated using the formulas given in Table or may be taken from the data presented in Table 2a, 2b, and 3.

$l = 1.600$ inches (from Table 2b)

Copyright 2004, Industrial Press, Inc., New York, NY

$d = 0.8821$ inch (from Table 2b)
$D = 100 \times 0.1600 + 3.1416 = 5.0930$ inches (from Table 1)
$C = 0.5(0.8821 + 5.0930) = 2.9876$ inches (from Table 1)
$P_n = 0.1386$ inch (from Table 3)
$a = 0.0441$ inch (from Table 3)
$h_t = 0.0990$ inch (from Table 3)
$h_k = 0.6366 \times 0.1386 = 0.0882$ inch (from Table 1)
$c = 0.0990 - 0.0882 = 0.0108$ inch (from Table 1)
$t_n = 0.5 \times 0.1386 = 0.0693$ inch (from Table 1)
$d_0 = 0.8821 + (2 \times 0.0441) = 0.9703$ inch (from Table 1)
$D_0 = (2 \times 2.9876) - 0.8821 + (2 \times 0.0441) = 5.1813$ (from Table 1)

$$F_G = 1.125\sqrt{(0.9703 + 2 \times 0.0108)^2 - (0.9703 - 4 \times 0.0441)^2} = 0.6689 \text{ inch}$$

$$F_W = \sqrt{5.1813^2 - 5.0930^2} = 0.9525 \text{ inch}$$

Example 2: Determine the design of a worm and wormgear for a center distance of approximately 0.550 inch if the ratio is to be 50 to 1 and the axial pitch is to be 0.050 inch.

Assume that $n = 1$ (since most fine-pitch worms have either one or two threads). The lead of the worm will then be $nP_x = 1 \times 0.050 = 0.050$ inch. From Table 2a and 2b it can be determined that there are six possible lead angles and corresponding worm diameters that will satisfy this lead. The approximate lead angle required to meet the conditions of the example can be computed from the following formula:

$$\text{Cotangent of approx. lead angle} = \frac{2\pi \times \text{approximate center distance required}}{\text{assumed number of threads} \times \text{axial pitch}} - m_G$$

Using letter symbols, this formula becomes:

Of the six possible worms in Table 2a and 2b, the one with the 3-degree lead angle is closest to the calculated 2°59′ lead angle. This worm, which has a pitch diameter of 0.3037 inch, is therefore selected.

The remaining worm and wormgear dimensions may now be determined from the data in Table 2a, 2b and 3 and by computation using the formulas given in Table 1.

$N = 50 \times 1 = 50$ teeth (from Table 1)
$d = 0.3037$ inch (from Table 2b)
$D = 50 \times 0.050 \div 3.1416 = 0.7958$ inch (from Table 1)
$C = 0.5(0.3037 + 0.7958) = 0.5498$ inch (from Table 1)
$P_n = 0.0499$ inch (from Table 3)
$a = 0.0159$ inch (from Table 3)
$h_t = 0.0370$ inch (from Table 3)
$h_k = 0.6366 \times 0.0499 = 0.0318$ inch (from Table 1)
$c = 0.0370 - 0.0318 = 0.0052$ inch (from Table 1)
$t_n = 0.5 \times 0.0499 = 0.0250$ inch (from Table 1)
$d_0 = 0.3037 + (2 \times 0.0159) = 0.3355$ inch (from Table 1)
$D_0 = (2 \times 0.5498) - 0.3037 + (2 \times 0.0159) = 5.1813$ (from Table 1)

$$F_{Gmin} = 1.125\sqrt{(0.3355 + 2 \times 0.0052)^2 - (0.3355 - 4 \times 0.0159)^2} = 0.2405 \text{ inch}$$

$$F_W = \sqrt{0.8277^2 - 0.7958^2} = 0.2276 \text{ inch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2a. Pitch Diameters of Fine-pitch Worms for American Standard Combinations of Lead and Lead Angle *(ANSI B6.9-1977)*

Lead in Inches, l	Number of Threads n	Lead Angle in Degrees							
		0.5	1	1.5	2	3	4	5	7
		Pitch Diameter d in inches							
0.030	1	1.0942	0.5471	0.3647	0.2735	…	…	…	…
0.040	1	1.4590	0.7294	0.4862	0.3646	0.2429	…	…	…
0.050	1	1.8237	0.9118	0.6078	0.4558	0.3037	0.2276	…	…
0.060	2	2.1885	1.0942	0.7293	0.5469	0.3644	0.2731	…	…
0.065	1	…	1.1853	0.7901	0.5925	0.3948	0.2959	0.2365	…
0.080	1	…	1.4589	0.9725	0.7292	0.4859	0.3642	0.2911	…
0.090	3	…	1.6412	1.0940	0.8204	0.5466	0.4097	0.3274	0.2333
0.100	1	…	1.8236	1.2156	0.9115	0.6074	0.4552	0.3638	0.2592
0.120	3	…	2.1883	1.4587	1.0938	0.7288	0.5462	0.4366	0.3111
0.130	1	…	…	1.5802	1.1850	0.7896	0.5918	0.4730	0.3370
0.150	3	…	…	1.8234	1.3673	0.9111	0.6828	0.5457	0.3889
0.160	1	…	…	1.9449	1.4584	0.9718	0.7283	0.5821	0.4148
0.180	6	…	…	2.1880	1.6407	1.0933	0.8194	0.6549	0.4666
0.195	3	…	…	…	1.7775	1.1844	0.8876	0.7095	0.5055
0.200	2	…	…	…	1.8230	1.2147	0.9104	0.7277	0.5185
0.210	7	…	…	…	1.9142	1.2755	0.9559	0.7640	0.5444
0.240	3	…	…	…	2.1876	1.4577	1.0925	0.8732	0.6222
0.250	5	…	…	…	…	1.5184	1.1380	0.9096	0.6481
0.260	2	…	…	…	…	1.5792	1.1835	0.9460	0.6740
0.270	9	…	…	…	…	1.6399	1.2291	0.9823	0.7000
0.280	7	…	…	…	…	1.7006	1.2746	1.0187	0.7259
0.300	3	…	…	…	…	1.8221	1.3656	1.0915	0.7777
0.320	2	…	…	…	…	1.9436	1.4567	1.1643	0.8296
0.325	5	…	…	…	…	1.9740	1.4794	1.1824	0.8425
0.350	7	…	…	…	…	2.1258	1.5932	1.2734	0.9073
0.360	9	…	…	…	…	…	1.6387	1.3098	0.9333
0.390	3	…	…	…	…	…	1.7753	1.4189	1.0110
0.400	4	…	…	…	…	…	1.8208	1.4553	1.0370
0.450	9	…	…	…	…	…	2.0484	1.6372	1.1666
0.455	7	…	…	…	…	…	…	1.6554	1.1796
0.480	3	…	…	…	…	…	…	1.7464	1.2444
0.500	5	…	…	…	…	…	…	1.8191	1.2962
0.520	4	…	…	…	…	…	…	1.8919	1.3481
0.560	7	…	…	…	…	…	…	2.0374	1.4518
0.585	9	…	…	…	…	…	…	2.1284	1.5166
0.600	6	…	…	…	…	…	…	2.1830	1.5555
0.640	4	…	…	…	…	…	…	2.3285	1.6592
0.650	5	…	…	…	…	…	…	…	1.6851
0.700	7	…	…	…	…	…	…	…	1.8147
0.720	9	…	…	…	…	…	…	…	1.8665
0.780	6	…	…	…	…	…	…	…	2.0221

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2b. Pitch Diameters of Fine-pitch Worms for American Standard Combinations of Lead and Lead Angle *ANSI B6.9-1977*

Lead in Inches, l	Number of Threads n	Lead Angle in Degrees						
		9	11	14	17	21	25	30
		Pitch Diameter d in inches						
0.120	3	0.2412	…	…	…	…	…	…
0.130	1	0.2613	…	…	…	…	…	…
0.150	3	0.3015	0.2456	…	…	…	…	…
0.160	1	0.3216	0.2620	…	…	…	…	…
0.180	6	0.3618	0.2948	…	…	…	…	…
0.195	3	0.3919	0.3193	0.2490	…	…	…	…
0.200	2	0.4019	0.3275	0.2553	…	…	…	…
0.210	7	0.4220	0.3439	0.2681	0.2186	…	…	…
0.240	3	0.4823	0.3930	0.3064	0.2499	…	…	…
0.250	5	0.5024	0.4094	0.3192	0.2603	…	…	…
0.260	2	0.5225	0.4258	0.3319	0.2707	…	…	…
0.270	9	0.5426	0.4421	0.3447	0.2811	…	…	…
0.280	7	0.5627	0.4585	0.3575	0.2915	…	…	…
0.300	3	0.6029	0.4913	0.3830	0.3123	0.2488	…	…
0.320	2	0.6431	0.5240	0.4085	0.3332	0.2654	…	…
0.325	5	0.6532	0.5322	0.4149	0.3384	0.2695	…	…
0.350	7	0.7034	0.5731	0.4468	0.3644	0.2902	0.2389	…
0.360	9	0.7235	0.5895	0.4596	0.3748	0.2985	0.2457	…
0.390	3	0.7838	0.6386	0.4979	0.4060	0.3234	0.2662	…
0.400	4	0.8039	0.6550	0.5107	0.4165	0.3317	0.2730	…
0.450	9	0.9044	0.7369	0.5745	0.4685	0.3732	0.3072	0.2481
0.455	7	0.9144	0.7451	0.5809	0.4737	0.3773	0.3106	0.2509
0.480	3	0.9647	0.7860	0.6128	0.4997	0.3980	0.3277	0.2646
0.500	5	1.0049	0.8188	0.6383	0.5206	0.4146	0.3413	0.2757
0.520	4	1.0451	0.8515	0.6639	0.5414	0.4312	0.3550	0.2867
0.560	7	1.1254	0.9170	0.7149	0.5830	0.4644	0.3823	0.3087
0.585	9	1.1757	0.9580	0.7469	0.6091	0.4851	0.3993	0.3225
0.600	6	1.2058	0.9825	0.7660	0.6247	0.4975	0.4096	0.3308
0.640	4	1.2862	1.0480	0.8171	0.6663	0.5307	0.4369	0.3529
0.650	5	1.3063	1.0644	0.8298	0.6767	0.5390	0.4437	0.3584
0.700	7	1.4068	1.1463	0.8937	0.7288	0.5805	0.4778	0.3859
0.720	9	1.4470	1.1790	0.9192	0.7496	0.5970	0.4915	0.3970
0.780	6	1.5676	1.2773	0.9958	0.8121	0.6468	0.5324	0.4300
0.800	5	1.6078	1.3100	1.0213	0.8329	0.6634	0.5461	0.4411
0.900	9	1.8088	1.4738	1.1490	0.9370	0.7463	0.6144	0.4962
0.910	7	1.8289	1.4902	1.1618	0.9474	0.7546	0.6212	0.5017
0.960	6	1.9293	1.5721	1.2256	0.9995	0.7961	0.6553	0.5293
1.000	10	2.0097	1.6376	1.2767	1.0411	0.8292	0.6826	0.5513
1.040	8	…	1.7031	1.3277	1.0828	0.8624	0.7099	0.5734
1.120	7	…	1.8341	1.4299	1.1661	0.9287	0.7645	0.6175
1.170	9	…	1.9159	1.4937	1.2181	0.9702	0.7987	0.6451
1.280	8	…	2.0961	1.6341	1.3327	1.0614	0.8738	0.7057
1.300	10	…	…	1.6597	1.3535	1.0780	0.8874	0.7167
1.440	9	…	…	1.8384	1.4992	1.1941	0.9830	0.7939
1.600	10	…	…	2.0427	1.6658	1.3268	1.0922	0.8821

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. Tooth Proportions of American Standard Fine-Pitch Worms and WormGears *ANSI B6.9-1977*

Standard Axial Pitch in Inches,	Tooth Parts	Lead angle in λ in degrees														
		0.5	1	1.5	2	3	4	5	7	9	11	14	17	21	25	30
		Dimensions of Tooth Parts in Inches														
0.030	a	0.0095	0.0095	0.0095	0.0095	0.0095	0.0095	0.0095	0.0095	0.0094	0.0094	0.0093	0.0091	0.0089	…	…
	h_t	0.0230	0.0230	0.0230	0.0230	0.0230	0.0230	0.0229	0.0229	0.0228	0.0226	0.0224	0.0221	0.0216	…	…
	p_n	0.0300	0.0300	0.0300	0.0300	0.0300	0.0299	0.0299	0.0298	0.0296	0.0294	0.0291	0.0287	0.0280	…	…
0.040	a	0.0127	0.0127	0.0127	0.0127	0.0127	0.0127	0.0127	0.0126	0.0126	0.0125	0.0124	0.0122	0.0119	0.0115	…
	h_t	0.0300	0.0300	0.0300	0.0300	0.0300	0.0299	0.0299	0.0298	0.0297	0.0295	0.0292	0.0288	0.0282	0.0274	…
	p_n	0.0400	0.0400	0.0400	0.0400	0.0399	0.0399	0.0398	0.0397	0.0395	0.0393	0.0388	0.0383	0.0373	0.0363	…
0.050	a	0.0159	0.0159	0.0159	0.0159	0.0159	0.0159	0.0159	0.0158	0.0157	0.0156	0.0154	0.0152	0.0149	0.0144	0.0138
	h_t	0.0370	0.0370	0.0370	0.0370	0.0370	0.0369	0.0369	0.0368	0.0366	0.0364	0.0360	0.0355	0.0347	0.0337	0.0323
	p_n	0.0500	0.0500	0.0500	0.0500	0.0499	0.0499	0.0498	0.0496	0.0494	0.0491	0.0485	0.0478	0.0467	0.0453	0.0433
0.065	a	0.0207	0.0207	0.0207	0.0207	0.0207	0.0206	0.0206	0.0205	0.0204	0.0203	0.0201	0.0198	0.0193	0.0188	0.0179
	h_t	0.0475	0.0475	0.0475	0.0475	0.0475	0.0474	0.0473	0.0472	0.0470	0.0467	0.0462	0.0455	0.0445	0.0433	0.0414
	p_n	0.0650	0.0650	0.0650	0.0650	0.0649	0.0648	0.0648	0.0645	0.0642	0.0638	0.0631	0.0622	0.0607	0.0589	0.0563
0.080	a	0.0255	0.0255	0.0255	0.0254	0.0254	0.0254	0.0254	0.0253	0.0252	0.0250	0.0247	0.0244	0.0238	0.0231	0.0221
	h_t	0.0580	0.0580	0.0580	0.0580	0.0579	0.0579	0.0578	0.0576	0.0573	0.0570	0.0564	0.0556	0.0543	0.0528	0.0505
	p_n	0.0800	0.0800	0.0800	0.0800	0.0799	0.0798	0.0797	0.0794	0.0790	0.0785	0.0776	0.0765	0.0747	0.0725	0.0693
0.100	a	0.0318	0.0318	0.0318	0.0318	0.0318	0.0318	0.0317	0.0316	0.0314	0.0312	0.0309	0.0304	0.0297	0.0288	0.0276
	h_t	0.0720	0.0720	0.0720	0.0720	0.0719	0.0719	0.0718	0.0715	0.0712	0.0707	0.0699	0.0690	0.0674	0.0655	0.0626
	p_n	0.1000	0.1000	0.1000	0.0999	0.0999	0.0998	0.0996	0.0993	0.0988	0.0982	0.0970	0.0956	0.0934	0.0906	0.0866
0.130	a	0.0414	0.0414	0.0414	0.0414	0.0413	0.0413	0.0412	0.0411	0.0409	0.0406	0.0401	0.0396	0.0386	0.0375	0.0358
	h_t	0.0930	0.0930	0.0930	0.0930	0.0929	0.0928	0.0927	0.0924	0.0919	0.0914	0.0903	0.0891	0.0870	0.0845	0.0808
	p_n	0.1300	0.1300	0.1300	0.1299	0.1298	0.1297	0.1295	0.1290	0.1284	0.1276	0.1261	0.1243	0.1214	0.1178	0.1126
0.160	a	0.0509	0.0509	0.0509	0.0509	0.0509	0.0508	0.0507	0.0505	0.0503	0.0500	0.0494	0.0487	0.0475	0.0462	0.0441
	h_t	0.1140	0.1140	0.1140	0.1140	0.1139	0.1138	0.1136	0.1132	0.1127	0.1120	0.1107	0.1092	0.1066	0.1035	0.0990
	p_n	0.1600	0.1600	0.1599	0.1599	0.1598	0.1596	0.1594	0.1588	0.1580	0.1571	0.1552	0.1530	0.1494	0.1450	0.1386

Copyright 2004, Industrial Press, Inc., New York, NY

Effect of Production Method on Worm Profile and Pressure Angle.— In worm gearing, tooth bearing is usually used as the means of judging tooth profile accuracy since direct profile measurements on fine-pitch worms or wormgears is not practical. According to AGMA 370.01, Design Manual for Fine-Pitch Gearing, a minimum of 50 per cent initial area of contact is suitable for most fine-pitch worm gearing, although in some cases, such as when the load fluctuates widely, a more restricted initial area of contact may be desirable.

Except where single-pointed lathe tools, end mills, or cutters of special shape are used in the manufacture of worms, the pressure angle and profile produced by the cutter are different from those of the cutter itself. The amounts of these differences depend on several factors, namely, diameter and lead angle of the worm, thickness and depth of the worm thread, and diameter of the cutter or grinding wheel. The accompanying diagram shows the curvature and pressure angle effects produced in the worm by cutters and grinding wheels, and how the amount of variation in worm profile and pressure angle is influenced by the diameter of the cutting tool used.

Effect of Diameter of Cutting on Profile and Pressure Angle of Worms



Calculating Worm Deviations and Pressure Angle Changes: Included in American Standard ANSI B6.9-1977 is an extensive tabulation of profile deviations and pressure angle changes produced by cutters and grinding wheels of 2-inch and 20-inch diameters. These diameters represent the limits of the range commonly used, and the data given are useful in specifying worm profile tolerances. The data also aid in the selection of the method to be used in producing the worm and in specifying the hobs for wormgears. The formulas used to compute the data in the Standard are given here in slightly modified form, and may be used to calculate the profile deviations and pressure angle changes produced in the worm by cutters or grinding wheels.

$$\rho_{ni} = \frac{r \sin\phi_n}{(\sin\lambda)^2} \text{ inches} \tag{1}$$

$$\rho_n = \rho_{ni} + \frac{r\rho_{ni}}{R(\cos\lambda)^2} \text{ inches} \tag{2}$$

$$\Delta\phi = \frac{5400r(\sin\lambda)^3}{n(R(\cos\lambda)^2 + r)} \text{ minutes} \tag{3}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$q = a \sec \phi_n \text{ inches} \quad (4)$$

$$y = \frac{q^2}{2\rho_n} \text{ inches} \quad (5)$$

$$s = 0.000582 q \Delta\phi \text{ inches} \quad (6)$$

$$\Delta y = y_w - y_c \text{ inches} \quad (7)$$

$$\Delta s = s_c - s_w \text{ inches} \quad (8)$$

In these formulas,

ρ_{ni} = radius of curvature of normal thread profile for involute thread;
r = pitch radius of worm;
Φ_n = normal pressure angle of cutter or grinding wheel;
λ = lead angle of worm;
ρ_n = radius of curvature of normal thread profile;
R = radius of cutter or grinding wheel;
$\Delta\Phi$ = difference between the normal pressure angle of the thread and the normal pressure angle of the cutter or grinding wheel in minutes (see diagram). Subscripts c and w are used to denote the cutter and grinding wheel diameters, respectively;
n = number of threads in worm;
a = addendum of worm;
q = slant height of worm addendum;
y = amount normal worm profile departs from a straight side (see diagram). Subscripts c and w are used to denote the cutter and grinding wheel diameters, respectively;
s = effect along slant height of worm thread caused by change in pressure angle $\Delta\Phi$
Δy = difference in y values of two cutters or grinding wheels of different diameter (see diagram);
Δs = effect of $\Delta\Phi_c - \Delta\Phi_w$ along slant height of thread (see diagram).

Example 3: Assuming the worm dimensions are the same as in Example 1, determine the corrections for two worms, one milled by a 2-inch diameter cutter, the other ground by a 20-inch diameter wheel, both to be assembled with identical wormgears.

To make identical worms when using a 2-inch cutter and a 20-inch wheel, the pressure angle of either the cutter or the wheel must be corrected by an amount corresponding to Δs and the profile of the cutter or wheel must be a curve which departs from a straight line by an amount Δy. The calculations are as follows:

For the 2-inch diameter cutter, using Formula (1) to (6),

$$\rho_{ni} = \frac{0.4410 \times 0.3420}{0.5000^2} = 0.6033 \text{ inch} \quad (1)$$

$$\rho_n = 0.6033 + \frac{0.4410 \times 0.6033}{1 \times 0.8660^2} = 0.9581 \text{ inch} \quad (2)$$

$$\Delta\phi_c = \frac{5400 \times 0.4410 \times 0.5000^3}{10(1 \times 0.8660^2 + 0.4410)} = 24.99 \text{ inches} \quad (3)$$

$$q = 0.0441 \times 1.0642 = 0.0469 \text{ inch} \quad (4)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$y_c = \frac{0.0469^2}{2 \times 0.6387} = 0.00172 \text{ inches} \quad (5)$$

$$s_c = 0.000582 \times 0.0469 \times 24.99 = 0.000682 \text{ inch} \quad (6)$$

For the 20-inch diameter wheel, using Formula (1) to (6)

$$\rho_{ni} = \frac{0.4410 \times 0.3420}{0.5000^2} = 0.6033 \text{ inch} \quad (1)$$

$$\rho_n = 0.6033 + \frac{0.4410 \times 0.6033}{10 \times 0.8660^2} = 0.6387 \text{ inch} \quad (2)$$

$$\Delta\phi_w = \frac{5400 \times 0.4410 \times 0.5000^3}{10(10 \times 0.8660^2 + 0.4410)} = 3.749 \text{ inches} \quad (3)$$

$$q = 0.0441 \times 1.0642 = 0.0469 \text{ inch} \quad (4)$$

$$y_w = \frac{0.0469^2}{2 \times 0.6387} = 0.00172 \text{ inches} \quad (5)$$

$$s_w = 0.000582 \times 0.0469 \times 3.749 = 0.000102 \text{ inch} \quad (6)$$

Applying Formula (7) to (8):

$$\Delta y = 0.00172 - 0.00115 = 0.00057 \text{ inch} \quad (7)$$

$$\Delta s = 0.000682 - 0.000102 = 0.000580 \text{ inch} \quad (8)$$

Therefore the pressure angle of either the cutter or the wheel must be corrected by an amount corresponding to a Δs of 0.00580 inch and the profile of the cutter or wheel must be a curve which departs from a straight line by 0.00057 inch.

Industrial Worm Gearing.— The primary considerations in industrial worm gearing are usually:

1) To transmit power efficiently;
2) to transmit power at a considerable reduction in velocity; and
3) to provide a considerable "mechanical advantage" when a given applied force must overcome a comparatively high resisting force.

Worm gearing for use in such applications is usually of relatively coarse pitch. The notation below is used in the formulas on the following pages.

a	addendum, worm thread	m	module = 0.3183 × axial pitch
A	addendum, wormgear tooth	N	revolutions per minute of wormgear
B	dedendum, wormgear tooth	n	revolutions per minute of worm
b	dedendum, worm thread	P	axial pitch of worm and circular pitch of wormgear
C	center distance (Fig. 1, p. 1928)	P_n	normal pitch of worm
c	clearance	Q	arc length of wormgear tooth measured along root
D	pitch diameter of wormgear	R	ratio of worm gearing = No. of wormgear teeth ÷ No. of worm threads.
d	pitch diameter of worm	S_c	surface stress factor (Table 4)
d_0	outside diameter of worm	S_b	bending stress factors, lbs. per sq. in. (Table 4)
D_0	outside or over-all diameter of wormgear	T	number of teeth on wormgear

Copyright 2004, Industrial Press, Inc., New York, NY

D_t	throat diameter of wormgear	t	number of threads or "starts" and on worm-2 for double thread, 3 for triple thread, 4 for quadruple thread, etc.
E	efficiency of worm gearing, per cent	U	radius of wormgear throat (Fig. 11)
F	nominal face width of wormgear rim	V	rubbing speed of worm in feet per minute
F_e	effective face width (Fig. 11, p. 1928)	W	whole tooth depth (worm and-wormgear)
f	coefficient of friction	X_{cp} and X_{cw}	speed factor when load rating is limited by wear (Fig. 11)
G	length of worm threaded section	X_{bp} and X_{bw}	speed factor when load rating is limited by strength (Table 5)
H	horsepower rating	ϕ	angle of friction (tan ϕ = coefficient of friction)
L	lead of worm thread = pitch × number of threads or "starts"		
L_a	lead angle of worm = helix angle measured from a plane perpendicular to worm axis		
M	torque applied to wormgear, pound inches		

Materials for Worm Gearing.— Worm gearing, especially for power transmission, should have steel worms and phosphor bronze wormgears. This combination is used extensively. The worms should be hardened and ground to obtain accuracy and a smooth finish.

The phosphor bronze wormgears should contain from 10 to 12 per cent of tin. The S.A.E. phosphor gear bronze (No. 65) contains 88–90% copper, 10–12% tin, 0.50% lead, 0.50% zinc (but with a maximum total lead, zinc and nickel content of 1.0 percent), phosphorous 0.10–0.30%, aluminum 0.005%. The S.A.E. nickel phosphor gear bronze (No. 65 + Ni) contains 87% copper, 11% tin, 2% nickel and 0.2% phosphorous.

Single-thread Worms.— The ratio of the worm speed to the wormgear speed may range from 1.5 or even less up to 100 or more. Worm gearing having high ratios are not very efficient as transmitters of power; nevertheless high as well as low ratios often are required. Since the ratio equals the number of wormgear teeth divided by the number of threads or "starts" on the worm, single-thread worms are used to obtain a high ratio. As a general rule, a ratio of 50 is about the maximum recommended for a single worm and wormgear combination, although ratios up to 100 or higher are possible. When a high ratio is required, it may be preferable to use, in combination, two sets of worm gearing of the multi-thread type in preference to one set of the single-thread type in order to obtain the same total reduction and a higher combined efficiency.

Single-thread worms are comparatively inefficient because of the effect of the low lead angle; consequently, single-thread worms are not used when the primary purpose is to transmit power as efficiently as possible but they may be employed either when a large speed reduction with one set of gearing is necessary, or possibly as a means of adjustment, especially if "mechanical advantage" or self-locking are important factors.

Multi-thread Worms.— When worm gearing is designed primarily for transmitting power efficiently, the lead angle of the worm should be as high as is consistent with other requirements and preferably between, say, 25 or 30 and 45 degrees. This means that the worm must be multi-threaded. To obtain a given ratio, some number of wormgear teeth divided by some number of worm threads must equal the ratio. Thus, if the ratio is 6, combinations such as the following might be used:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{24}{4}, \frac{30}{5}, \frac{36}{6}, \frac{42}{7}$$

The numerators represent the number of wormgear teeth and the denominators, the number of worm threads or "starts." The number of wormgear teeth may not be an exact multiple of the number of threads on a multi-thread worm in order to obtain a "hunting tooth" action.

Number of Threads or "Starts" on Worm: The number of threads on the worm ordinarily varies from one to six or eight, depending upon the ratio of the gearing. As the ratio is increased, the number of worm threads is reduced, as a general rule. In some cases, however, the higher of two ratios may also have a larger number of threads. For example, a ratio of $6\frac{1}{5}$ would have 5 threads whereas a ratio of $6\frac{5}{6}$ would have 6 threads. Whenever the ratio is fractional, the number of threads on the worm equals the denominator of the fractional part of the ratio.

Table 4. Rules and Formulas for Worm Gearing

No.	To Find	Rule	Formula
1	Addendum	Addendum may be affected by lead angle. See paragraph, Addendum and Dedendum.	
2	Center Distance	Add pitch diameter of wormgear to pitch diameter of worm, and divide sum by 2	$C = \frac{D+d}{2}$
3		Divide number of worm threads by tangent lead angle, add number of wormgear teeth and multiply sum by quotient obtained by dividing pitch by 6.2832	$C = \frac{P}{6.2832}\left(\frac{t}{\tan L_a} + T\right)$
4	Dedendum	Dedendum may be affected by lead angle. See paragraph, Addendum and Dedendum	
5	Clearance	British Standard-multiply cosine lead angle by 0.2 times module.	$c = 0.2m\cos L_a$
6	Face width Wormgear	For single and double thread worms, multiply pitch by 2.38 and add 0.25. (shell type worm.)	$F = 2.38P + 0.25$
7		For triple and quadruple thread multiply pitch by 2.15 and add 0.2. (shell type)	$F = 2.15P + 0.20$
8		When worm threads are integral with shaft, face width of wormgear may be equal $C^{0.875}$ divided by 3.	$F = \frac{C^{0.875}}{3}$
9	Lead of Worm thread	Multiply pitch by number of worm threads or "starts"	$L = lP$
10		Multiply pitch circumference of worm by tangent of lead angle.	$L = \pi d \times \tan L_a$
11		Divide pitch circumference of wormgear by ratio.	$L = \pi D \div R$
12	Lead Angle, Worm	Divide lead by pitch circumference of worm; quotient is tangent of lead angle.	$\tan L_a = \frac{L}{3.1416d}$
13	Outside Diam., Worm	Add to pitch diameter twice the addendum. see paragraph, pitch diameter of worm; also Addendum and Dedendum.	$d_0 = d + 2a$
14	Outside Diam., Wormgear	For outside or over-all diameter of wormgear, see paragraph, outside diameter of wormgear.	

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4. ***(Continued)*** **Rules and Formulas for Worm Gearing**

No.	To Find	Rule	Formula
15	Pitch of Worm and Wormgear	Divide lead by number of threads or "starts" on worm = axial pitch of worm and circular pitch of wormgear.	$P = \frac{L}{t}$
16		Subtract the worm pitch diameter from twice the center distance. Multiply by 3.1416 and divide by number of wormgear teeth.	$P = \frac{(2C - d)3.1416}{T}$
17	Pitch of Worm, Normal	Multiply axial pitch by cosine of lead angle to find normal pitch.	$P_n = P \times \cos L_a$
18	Pitch Diameter, Worm	Subtract pitch diameter of worm gear from twice the center distance.	$d = 2C - D$
19		Subtract twice the addendum from outside diameter. See Addendum and Dedendum.	$D = d_0 - 2a$
20		Multiply lead by cotangent lead angle and divide product by 3.1416	$d = \frac{L \times \cot L_a}{3.1416}$
21	Pitch Diameter, Wormgear	Subtract pitch diameter of worm from twice the center distance.	$D = 2C - d$
22		Multiply number of wormgear teeth by axial pitch of worm and divide product by 3.1416.	$D = \frac{TP}{3.1416}$
23	Radius of Rim Corner, Wormgear	Multiply pitch by 0.25	Radius $= 0.25P$
24		British Standard: Radius = 0.5 × module.	Radius $= 0.50m$
25	Ratio	Divide number of wormgear teeth by by number of worm threads.	$R = T \div t$
26	Rubbing speed, ft. per minute	Divide wormgear pitch diameter by ratio; square quotient and add to square of worm pitch diameter; multiply square root of this sum by 0.262 × R.P.M. of worm.	$V = 0.262n\sqrt{d^2 + \left(\frac{D}{4}\right)^2}$
27		Multiply 0.262 × Pitch diameter of worm by worm R.P.M. of worm; then multiply product by secant of lead angle.	$V = 0.262dn \times \sec L_a$
28	Throat Diameter Wormgear	Add twice the addendum to pitch diameter. See paragraph, Addendum and Dedendum	$D_t = D + 2A$
29	Throat Radius Wormgear	Subtract twice the addendum from outside radius of worm.	$U = \frac{d_0}{2} - 2a$
30	Total Depth	Whole depth equals addendum + Dedendum. See paragraph, Addendum and Dedendum	$W = a + b$ or $A + B$
31	Worm Thread Length	Multiply the number of wormgear teeth by 0.02, add 4.5 and multiply sum by pitch.	$G = P(4.5 + 0.02T)$
32		British Standard subtract square of wormgear pitch diameter from square of outside diameter and extract square root of remainder.	$G = \sqrt{D_0^2 - D^2}$

Ratio for Obtaining "Hunting Tooth" Action.— In designing wormgears having multithread worms, it is common practice to select a number of wormgear teeth that is not an exact multiple of the number of worm threads. To illustrate, if the desired ratio is about 5 or 6, the actual ratio might be 5$^1/_6$, 5$^5/_6$, 5$^2/_7$, 6$^1/_5$, etc., so that combinations such as $^{31}/_6$, $^{35}/_6$, $^{37}/_7$ or $^{31}/_5$ would be obtained. Since the number of wormgear teeth and number of worm threads do not have a common divisor, the threads of the worm will mesh with all of the wormgear teeth in succession, thus obtaining a "hunting tooth" or self-indexing action. This progressive change will also occur during the wormgear hobbing operation, and its primary purpose is to produce more accurate wormgears by uniformly distributing among all of the teeth, any slight errors which might exist in the hob teeth. Another object is to improve the

Copyright 2004, Industrial Press, Inc., New York, NY

"running-in" action between the hardened and ground worm and the phosphor bronze wormgear, but in order to obtain this advantage, the threads on the worm must be accurately or uniformly spaced by precise indexing. With a "hunting tooth ratio," if the thread spacing of a multi-thread worm is inaccurate, load distribution on the threads will be unequal and some threads might not even make contact with the wormgear teeth. For this reason, if the indexing is inaccurate, it is preferable to avoid a hunting tooth ratio, but in that case, if the gearing is disassembled, the same worm and wormgear teeth should be mated when reassembled.



Fig. 11.

Pitch Diameter of Worm.— The worm must be strong enough to transmit its maximum load without excessive deflection but the diameter should be as small as is consistent with the necessary strength in order to minimize the rubbing speed. It is impracticable to give a rule or formula that is generally applicable, but the following empirical rules are based upon actual practice and may prove useful as a general guide. They apply to casehardened alloy steel worms which are integral with the shaft.

For ratios of 5, 6, or 7, the pitch diameter ranges approximately from 0.38 *C* when center distance *C* is 4 inches to 0.33 *C* when *C* is 20 inches.

For ratios of 8, 9,10, the pitch diameter ranges approximately from 0.38 *C* when center distance *C* is 4 inches to 0.25 *C* when *C* is 30 inches.

For ratios of 10 to 20, the pitch diameter ranges approximately from 0.37 *C* when center distance *C* is 4 inches to 0.24 *C* when *C* is 30 inches.

For ratios of 20 to 40, the pitch diameter ranges approximately from 0.36 *C* when center distance *C* is 4 inches to 0.23 *C* when C is 30 inches.

According to another empirical formula pitch diameter $d = C^{0.75} + 2.2$.

Addendum and Dedendum.— The following A.G.M.A. formulas are applicable to industrial worm gearing. For single and double thread worms, addendum $a = 0.318\ P$ and whole depth $W = 0.686\ P$; for triple and quadruple threads, addendum $a = 0.286\ P$ and whole depth $W = 0.623\ P$.

Copyright 2004, Industrial Press, Inc., New York, NY

According to the British standard, a = module $m = 0.3183\ P$; $b = m(2.2 \cos L_a - 1)$; $A = m(2.2 \cos L_a - 1)$; $B = m(1 + 0.2 \cos L_a)$.

Outside Diameter of Wormgear.— Practice varies somewhat in determining the outside or over-all diameter of the wormgear, as indicated by the following formulas. For usual rim shape, see Fig. 11.

1) For lead angles up to about 15 or 20 degrees, $D_0 = D + (3 \times 0.3183\ P)$

2) For lead angles over 20 degrees, $D_0 = \mathrm{D} + (3 \times 0.3\ 183\ P \times \cos L_a)$

3) For single and double thread, $D_0 = D_t + 0.4775P$

4) For triple and quadruple thread, $D_0 = D_t + 0.3183\ P$

Pressure Angles.— The pressure angle (one-half the included thread angle) ranges from 14½ to 30 degrees. While the practice varies somewhat, the following relationship between lead angle and pressure angle may be used as a general guide.

For lead angles up to about 10 or 12 degrees, pressure angle = 14½ degrees.

For lead angles from 10 or 12 to about 20 or 25 degrees, pressure angle = 20 degrees.

For lead angles from 25 to about 35 degrees, pressure angle= 25 degrees.

For lead angles over 35 degrees, pressure angle = 30 degrees.

In the British Standard specifications, the recommended thread form has a normal pressure angle of 20 degrees.

Designing Worm Gearing Relative to Center Distance and Ratio.— In designing worm gearing, three general cases or types of problems may be encountered in establishing the proportions of the worm and wormgear.

When Center Distance is Fixed and Ratio may be Varied: The ratio in this case is nominal and may be varied somewhat to meet other conditions. Assume that the required center distance is 6 inches, the desired ratio is about 7, and the pitch of the worm and wormgears is to be approximately 1 inch. Combinations of wormgears and worms such as the following might be used in this case:

$$\frac{28}{4}, \frac{35}{5}, \frac{42}{6}, \frac{56}{8}, \text{ etc.}$$

Suppose we select the $^{28}/_{4}$ combination for trial but change the number of worm-gear teeth from 28 to 29 to obtain a self-indexing or "hunting tooth" action. The ratio now equals $^{29}/_{4}$ or 7.25. Then, for trial purposes

$$\text{Pitch diameter } D \text{ of wormgear} = \frac{T \times P}{\pi} = \frac{29 \times 1}{3.1416} = 9.231 \text{ inches}$$

$$\text{Pitch diameter } d \text{ of wormgear} = 2C - D = 2 \times 6 - 9.231 = 2.769 \text{ inches}$$

Assume that experience, tests, or calculations show that a worm of smaller diameter will have the necessary bending and torsional strength and that a pitch of 1.0625 will be satisfactory. Then the pitch diameter of the worm will be decreased to 2.192 inches and the pitch diameter of the wormgear will be increased to 9.808 inches. A check of the lead-angle will show that it equals 31°41′ which is conducive to high efficiency.

When Ratio is Fixed and Center Distance may be Varied: Assume that the required ratio is 7¼ and that the center distance may be any value consistent with approved designing practice. This ratio may be obtained with a number of different worm and wormgear sizes. For example, in a series of commercial wormgears, the following combinations are employed for gearing having a ratio of 7¼ with center distances varying from 4 to 8.25 inches. The number of worm threads is 4 and the number of teeth on the wormgear is 29 in all cases.

$$\text{When } C = 4 \text{ inches}, d = 1.654; D = 6.346; P = 0.6875; L_a = 27°54'$$

Copyright 2004, Industrial Press, Inc., New York, NY

When $C = 5$ inches, $d = 1.923; D = 8.077; P = 0.875; L_a = 30°5'$

When $C = 6$ inches, $d = 2.192; D = 9.808; P = 1.0625; L_a = 31°41'$

When $C = 7$ inches, $d = 2.461; D = 11.539; P = 1.25; L_a = 32°53'$

When $C = 8.25$ inches, $d = 2.942; D = 13.558; P = 1.4687; L_a = 32°27'$

The horsepower rating increases considerably as the proportions of the worm gearing increase; hence if the gears are intended primarily for power transmission, the general proportions must be selected with reference to the power-transmitting capacity, and, usually the smallest and most compact design that will give satisfactory performance should be selected. The power capacity of the transmission, however, does not depend solely upon the proportions of the worm and wormgear. For example, the quality and viscosity of the lubricant is an important factor. The load transmitting capacity of the lubricant may also be increased decidedly when excessive temperature rises are prevented by special means such as forced air cooling. (See "Water and Forced-Air Cooling.")

When Both Ratio and Center Distance are Fixed: When both ratio and center distance are fixed, the problem usually is to obtain the best proportions of worm and wormgear conforming to these fixed values.

Example: The required ratio is 6 (6 to 1) and the center distance is fixed at 3.600 inches. Assume that experience or tests show that an axial pitch of 0.50 inch will meet strength requirements. If normal pitch P_n is given, change to axial pitch ($P = P_n \div \text{Cos } L_a$). With a ratio of 6, some of the combinations for trial are: $\frac{30}{5}, \frac{36}{6}, \frac{42}{7}$

Trial calculations will show that the $\frac{36}{6}$ combination gives the best proportions of worm and wheel for the center distance and pitch specified. Thus

$$D = \frac{TP}{\pi} = \frac{36 \times 0.5}{3.1416} = 5.729 ; \qquad d = 2C - D = 2 \times 3.6 - 5.729 = 1.471$$

The lead angle is about 33 degrees. The effect of lead angle on efficiency is dealt with in a following paragraph. The total obtained by adding the number of worm-gear teeth to the number of worm threads, equals 36 + 6 = 42 (a total of 40 is a desirable minimum). With the 42/7 combination of the same pitch, the worm would be too small (0.516 inch); and with the 30/5 combination it would be too large (2.426 inches). The present trend in gear designing practice is to use finer pitches than in the past. In the case of worm gearing, the pitch may, in certain instances, be changed somewhat either to permit cutting with available equipment or to improve the proportions of worm and wheel.

When Ratio, Pitch and Lead Angle are Fixed: Assume that $R = 10$, axial pitch $P = 0.16$ inch, $L_a = 30$ degrees and $C = 3$ inches, approximately.

The first step is to determine for the given ratio, pitch and lead angle, the number of worm threads t which will give a center distance nearest 3 inches.

The whole number nearest 10.04, or 10, is the required number of worm threads; hence number of teeth on wormgear equals $R \times 10 = 100$

$$d = (L \cot L_a) \div \pi = (10 \times 0.16 \times 1.732) \div \pi = 0.8821 \text{ inches}$$

$$D = (TP) \div \pi = (100 \times 0.16) \div \pi = 5.0929 \text{ inches}$$

$$C = (D + d) \div 2 = (5.0929 + 0.8821) \div 2 = 2.9875 \text{ inches}$$

Efficiency of Worm Gearing.— The efficiency at a given speed, depends upon the worm lead angle, the workmanship, the lubrication, and the general design of the transmission. When worm gearing consists of a hardened and ground worm running with an accurately hobbed wormgear properly lubricated, the efficiency depends chiefly upon the lead angle

Copyright 2004, Industrial Press, Inc., New York, NY

and coefficient of friction between the worm and worm-gear. In the lower range of lead angles, the efficiency increases considerably as the lead angle increases, as shown by Table 5 and . This increase in efficiency remains practically constant for lead angles between 30 and 45 degrees. Several formulas for obtaining efficiency percentage follow:
With worm driving:

$$E = 100 - \frac{R}{2}(\text{empirical rule}); E = \frac{100 \times \tan L_a}{\tan(L_a + \phi)}\ ;\ E = \frac{100 \times L}{L + f\pi d}$$

With wormgear driving

$$E = 100 - 2R(\text{empirical rule}); E = \frac{100 \times \tan(L_a - \phi)}{\tan L_a}$$

The efficiencies obtained by these formulas and other modifications of them differ somewhat and do not take into account bearing and oil-churning losses. The efficiency may be improved somewhat after the "running in" period.

Table 5. Efficiency of Worm Gearing for Different Lead Angles and Frictional Coefficients

Coefficient of friction	Lead angle of worm in degrees								
	5 Deg.	10 Deg.	15 Deg.	20 Deg.	25 Deg.	30 Deg.	35 Deg.	40 Deg.	45 Deg.
0.01	89.7	94.5	96.1	97.0	97.4	97.7	97.9	98.0	98.0
0.02	81.3	89.5	92.6	94.1	95.0	95.5	95.9	96.0	96.1
0.03	74.3	85.0	89.2	91.4	92.6	93.4	93.9	94.1	94.2
0.04	68.4	80.9	86.1	88.8	90.4	91.4	91.9	92.2	92.3
0.05	63.4	77.2	83.1	86.3	88.2	89.4	90.1	90.4	90.5
0.06	59.0	73.8	80.4	84.0	86.1	87.4	88.2	88.6	88.7
0.07	55.2	70.7	77.8	81.7	84.1	85.6	86.5	86.9	86.9
0.08	51.9	67.8	75.4	79.6	82.2	83.8	84.7	85.2	85.2
0.09	48.9	65.2	73.1	77.5	80.3	82.0	83.0	83.5	83.5
0.1	46.3	62.7	70.9	75.6	78.5	80.3	81.4	81.9	81.8

Table 6. AGMA Input Mechanical Horsepower Ratings of Cone-Drive Worm Gearing[a]

Ratio	Worm Speed, RPM					
	100	300	720	870	1150	1750
2-Inch Center Distance						
5:1	0.40	1.04	2.18	2.51	3.02	3.81
10:1	0.25	0.66	1.40	1.62	1.98	2.52
15:1	0.18	0.47	0.99	1.15	1.40	1.79
20:1	0.13	0.36	0.76	0.88	1.07	1.38
25:1	0.11	0.29	0.61	0.71	0.87	1.11
30:1	0.09	0.24	0.51	0.59	0.73	0.93
40:1	0.07	0.18	0.38	0.45	0.55	0.70
50:1	0.05	0.15	0.31	0.36	0.44	0.56

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ***(Continued)*** **AGMA Input Mechanical Horsepower Ratings of Cone-Drive Worm Gearing**[a]

Ratio	Worm Speed, RPM					
	100	300	720	870	1150	1750
2.5-Inch Center Distance						
5:1	0.78	2.04	4.13	4.68	5.48	6.87
10:1	0.49	1.30	2.67	3.05	3.62	4.54
15:1	0.35	0.91	1.89	2.16	2.57	3.22
20:1	0.27	0.70	1.44	1.65	1.97	2.48
25:1	0.21	0.56	1.16	1.33	1.59	2.00
30:1	0.18	0.47	0.98	1.12	1.33	1.68
40:1	0.13	0.35	0.73	0.84	1.00	1.26
50:1	0.11	0.28	0.59	0.68	0.81	1.01
3-Inch Center Distance						
5:1	1.38	3.60	6.99	7.79	9.06	11.30
10:1	0.88	2.31	4.65	5.26	6.16	7.72
15:1	0.62	1.62	3.29	3.74	4.38	5.49
20:1	0.47	1.24	2.52	2.87	3.37	4.22
25:1	0.38	1.00	2.04	2.31	2.72	3.41
30:1	0.32	0.84	1.71	1.94	2.28	2.86
40:1	0.24	0.63	1.28	1.46	1.72	2.15
50:1	0.19	0.51	1.03	1.17	1.38	1.73
60:1	0.16	0.42	0.86	0.98	1.15	1.44
3.5-Inch Center Distance						
5:1	2.55	6.60	12.30	13.70	15.90	19.70
10:1	1.63	4.24	8.27	9.21	10.70	13.40
15:1	1.14	2.99	5.85	6.54	7.62	9.53
20:1	0.88	2.28	4.49	5.03	5.86	7.33
25:1	0.71	1.84	3.62	4.06	4.73	5.92
30:1	0.59	1.54	3.04	3.40	3.96	4.96
40:1	0.44	1.16	2.29	2.56	2.99	3.74
50:1	0.36	0.93	1.83	2.06	2.40	3.00
60:1	0.30	0.78	1.53	1.72	2.00	2.51
4-Inch Center Distance						
5:1	3.66	9.40	16.90	18.70	21.70	26.70
10:1	2.35	6.09	11.50	12.70	14.80	18.40
15:1	1.65	4.29	8.15	9.06	10.50	13.10
20:1	1.26	3.28	6.26	6.96	8.09	10.10
25:1	1.02	2.65	5.05	5.62	6.53	8.13
30:1	0.85	2.22	4.24	4.71	5.48	6.82
40:1	0.64	1.67	3.19	3.55	4.12	5.14
50:1	0.51	1.34	2.56	2.85	3.31	4.12
60:1	0.43	1.12	2.14	2.38	2.76	3.44

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ***(Continued)*** **AGMA Input Mechanical Horsepower Ratings of Cone-Drive Worm Gearing**[a]

Ratio	Worm Speed, RPM					
	100	300	720	870	1150	1750
5-Inch Center Distance						
5:1	7.21	18.20	31.00	34.30	39.60	47.40
10:1	4.63	11.80	21.10	23.40	27.20	33.30
15:1	3.25	8.36	15.00	16.70	19.30	23.80
20:1	2.49	6.40	11.60	12.80	14.90	18.30
25:1	2.01	5.16	9.34	10.30	12.00	14.80
30:1	1.68	4.32	7.83	8.67	10.10	12.40
40:1	1.27	3.25	5.90	6.53	7.58	9.34
50:1	1.02	2.61	4.73	5.24	6.09	7.50
60:1	0.85	2.18	3.95	4.37	5.08	6.26
70:1	0.73	1.87	3.39	3.76	4.36	5.38
6-Inch Center Distance						
5:1	11.10	27.30	45.30	50.10	57.50	66.80
10:1	7.08	17.80	30.40	33.70	38.80	46.40
15:1	4.98	12.60	21.60	23.90	27.60	33.20
20:1	3.81	9.64	16.60	18.40	21.20	25.60
25:1	3.07	7.78	13.40	14.90	17.20	20.70
30:1	2.57	6.52	11.30	12.50	14.40	17.40
40:1	1.94	4.90	8.47	9.38	10.80	13.10
50:1	1.55	3.93	6.80	7.53	8.70	10.50
60:1	1.30	3.28	5.68	6.29	7.26	8.79
70:1	1.11	2.82	4.87	5.40	6.23	7.55
7-Inch Center Distance						
5:1	17.50	41.60	67.30	73.90	83.60	96.40
10:1	11.20	27.70	46.20	51.20	58.70	68.40
15:1	7.88	19.60	32.90	36.50	41.90	49.20
20:1	6.03	15.00	25.30	28.00	32.20	37.90
25:1	4.86	12.20	20.50	22.60	26.00	30.70
30:1	4.07	10.20	17.20	19.00	21.80	25.80
40:1	3.06	7.66	12.90	14.30	16.40	19.40
50:1	2.46	6.15	10.40	11.50	13.20	15.60
60:1	2.05	5.13	8.66	9.58	11.00	13.00
70:1	1.76	4.41	7.43	8.23	9.46	11.20
8-Inch Center Distance						
5:1	25.90	59.60	95.20	104.00	116.00	134.00
10:1	16.70	40.90	67.40	74.40	85.10	98.70
15:1	11.80	29.00	48.20	53.20	61.20	71.00
20:1	9.00	22.20	37.00	40.90	47.00	54.70
25:1	7.26	18.00	29.90	33.10	38.00	44.30
30:1	6.08	15.10	25.10	27.80	31.90	37.20
40:1	4.58	11.30	18.90	20.90	24.00	28.00
50:1	3.67	9.10	15.20	16.80	19.30	22.50
60:1	3.07	7.59	12.70	14.00	16.10	18.80
70:1	2.63	6.52	10.90	12.00	13.80	16.10

Copyright 2004, Industrial Press, Inc., New York, NY

Table 6. ***(Continued)*** **AGMA Input Mechanical Horsepower Ratings of Cone-Drive Worm Gearing**[a]

Ratio	Worm Speed, RPM					
	100	300	720	870	1150	1750
10-Inch Center Distance						
5:1	48.50	105.00	164.00	178.00	194.00	226.00
10:1	31.40	73.20	117.00	129.00	144.00	166.00
15:1	22.10	52.10	83.70	91.90	104.00	119.00
20:1	16.90	40.00	64.40	70.70	79.80	91.80
25:1	13.60	32.30	52.10	57.20	64.60	74.30
30:1	11.40	27.10	43.70	48.00	54.20	62.40
40:1	8.60	20.40	32.90	36.10	40.90	47.00
50:1	6.90	16.40	26.40	29.00	32.80	37.80
60:1	5.76	13.70	22.10	24.20	27.40	31.60
70:1	4.94	11.70	18.90	20.80	23.50	27.10
12-Inch Center Distance						
5:1	81.30	167.00	257.00	271.00	300.00	…
10:1	53.20	118.00	186.00	202.00	221.00	…
15:1	37.50	83.90	133.00	145.00	159.00	…
20:1	28.70	64.40	102.00	111.00	122.00	…
25:1	23.10	52.10	82.70	90.10	99.10	…
30:1	19.40	43.70	69.40	75.70	83.20	…
40:1	14.60	32.90	52.20	57.00	62.70	…
50:1	11.70	26.40	41.90	45.80	50.40	…
60:1	9.77	22.10	35.00	38.20	42.10	…
70:1	8.39	18.90	30.10	32.80	36.10	…

[a] These values for different rubbing speeds are based upon the use of phosphor bronze wormgears with case-hardened ground and polished steel worms lubricated with mineral oil.

Self-locking or Irreversible Worm Gearing.— Neglecting friction in the bearings, worm gearing is irreversible when the efficiency is zero or negative, the lead angle being equal to or less than the angle ϕ of friction ($\tan \phi$ = coefficient of friction). When worm gearing is self-locking or irreversible, this means that the worm-gear cannot drive the worm. Since the angle of friction changes rapidly with the rubbing speed, and the static angle of friction may be reduced by external vibration, it is usually impracticable to design irreversible worm gearing with any security. If irreversibility is desired, it is recommended that some form of brake be employed.

Worm Gearing Operating Temperatures.— The load capacity of a worm gearing lubricant at operating temperature is an important factor in establishing the continuous power-transmitting capacity of the gearing. If the churning or turbulence of the oil generates excessive heat, the viscosity of the lubricant may be reduced below its load-supporting capacity. The temperature measured in the oil sump should not, as a rule, exceed 180 to 200 degrees F. or rise more than 120 to 140 degrees F. above a surrounding air temperature of 60 degrees F. In rear axle motor vehicle transmissions, the maximum operating temperature may be somewhat higher than the figures given and usually is limited to about 220 degrees F.

Thermal Rating.— In some cases, especially when the worm speed is comparatively high, the horsepower capacity of worm gearing should be based upon its thermal rating instead of the mechanical rating. To illustrate, worm gearing may have a thermal rating of, say, 60 H.P., and mechanical ratings which are considerably higher than 60 for the higher

Copyright 2004, Industrial Press, Inc., New York, NY

speed ranges. This means that the gearing is capable of transmitting more than 60 H.P. so far as wear and strength are concerned but not without overheating; hence, in this case a rating of 60 should be considered maximum. Of course, if the power to be transmitted is less than the thermal rating for a given ratio, then the thermal rating may be ignored.

Water and Forced-Air Cooling.— One method of increasing the thermal rating of a speed-reducing unit of the worm gearing type, is by installing a water-cooling coil through which water is circulated to prevent an excessive rise of the oil temperature. According to one manufacturer, the thermal rating may be increased as much as 35 per cent in this manner. Much larger increases have been obtained by means of a forced air cooling system incorporated in the design of the speed-reducing unit. A fan which is mounted on the worm shaft draws air through a double walled housing, thus maintaining a comparatively low oil bath temperature. A fan cooling system makes it possible to transmit a given amount of power through a worm-gearing unit that is much smaller than one not equipped with a fan.

Double-enveloping Worm Gearing.— Contact between the worm and wormgear of the conventional type of worm gearing is theoretically a line contact; however, due to deflection of the materials under load, the line is increased to a narrow band or contact zone. In attempting to produce a double-enveloping type of worm gearing (with the worm curved longitudinally to fit the curvature of the gear as shown by illustration), the problem primarily was that of generating the worm and worm-gear in such a manner as to obtain area contact between the engaging teeth. A practical method of obtaining such contact was developed by Samuel I. Cone at the Norfolk Navy Yard, and this is known as "Cone-Drive" worm gearing. The Cone generating method makes it possible to cut the worm and wormgear without any interference which would alter the required tooth form. The larger tooth bearing area and multiple tooth contact obtained with this type of worm gearing, increases the load-carrying or horsepower capacity so that as compared with a conventional worm drive a double-enveloping worm drive may be considerably smaller in size. Table 6, which is intended as a general guide, gives input horsepower ratings for Cone-Drive worm gearing for various center distances of from 2 to 12 inches. These ratings are based on AGMA specifications 341, 441, and 641. They allow for starting and momentary peak overloads of up to 300 per cent of the values shown in Table 5 using a service factor of 1. Factors for various types of service are given in Table 7. To obtain the mechanical horsepower rating required, multiply the appropriate rating given in Table 6 by the service factor taken from Table 7.



*Horsepower ratings are for Class 1 service, using splash lubrication, except for that shown in italics, for which force feed lubrication is required. Other ratios and center distances are available.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 7. Service Factors for Cone-Drive Worm Gearing

Hours/Day	Uniform Motion	Moderate Shock	Heavy Shock	Extreme Shock
0.5	0.6	0.8	0.9	1.1
1	0.7	0.9	1	1.2
2	0.9	1	1.2	1.3
10	1	1.2	1.3	1.5
24	1.2	1.3	1.5	1.75

Thermal Horsepower Rating: When the operation is to be continuous, consideration must be given to the possibility of overheating. For this possibility, the thermal horsepower rating given in Ex-Cell-O Corporation, Cone Drive Operations catalog must be checked. The thermal rating defines the maximum horsepower which can be transmitted continuously (30 minutes or longer). This is based on an oil sump temperature rise of 100 deg. F above the ambient temperature. This rise must not exceed 200 deg. F. If the thermal rating is lower than the mechanical rating, the unit must be selected on the basis of the thermal rating.

Type of Drive Connection: If either input or output shaft is connected to driver or driven mechanism by other than a direct shaft coupling, the overhead load requirement (chain pull) must be calculated by dividing the torque demand by the pitch radius of the sprocket, sheave, spur gear, or helical gear used. The result is multiplied by the overhung load factor which is: for a chain sprocket, 1.00; for spur or helical gearing, 1.25; for a V-belt sheave, 1.50; and for a flat belt sheave, 2.50. As modified by the applicable overhung load factor, this load may not exceed the overhung load rating given in the company catalog.

Locking Considerations: It is a common misconception that all worm gears are self-locking or non-overhauling. Actually, wormgear ratios up 15 to 1 will overhaul quite freely. Ratios from 20:1 to 40:1 can generally be considered as overhauling with difficulty, particularly from rest. Ratios above 40:1 may or may not overhaul depending on the loading, lubrication, and amount of vibration present. Therefore it is not acceptable to rely on a wormgear to prevent movement in a system. Whenever a load must be stopped or held in place, a positive mechanical device must be incorporated into the system to prevent rotation of the gearset.

Backdriving or Overhauling: Applications such as wheel drives that require a brake on the motor or input shaft to decelerate a high inertial load require special attention to brake selection. Wherever possible, these applications should utilize freely overhauling ratios (15:1 or less). If higher ratios are used with a brake, the gearset can, under certain conditions, lockup during deceleration and impose severe shock loading on the reducer and driven equipment.

Stairstepping: Self-locking ratios (generally 40:1 and higher) are susceptible to the phenomenon of "stair stepping" when back driving or overhauling. This erratic rotation of the gear set occasionally occurs when the gear set is back driven at worm speeds less than the theoretical lockup speed of the gear set and can be amplified by the rest of the drive train creating a very undesirable operating condition. "Stair stepping" can occur on drives where there is a high inertial load at the output shaft.

Backlash: Defined as the amount of movement at the pitch line of the gear with the worm locked and the gear set on exact center distance, backlash normally ranges from 0.003 to 0.008 inch for a 2-inch center distance set up to 0.012 to 0.020 inch for a 12-inch center distance set. When the gear set is assembled into a machine or reducer, the assembled backlash may fall outside these limits depending upon worm and gear bearing looseness and the actual center distance used.

Lubrication: Lubricating oils for use in double-enveloping worm drive units should be well refined petroleum oils of high quality. They should not be corrosive to gears or bear-

Copyright 2004, Industrial Press, Inc., New York, NY

ings and they must be neutral in reaction and free from grit or abrasives. They should have good defoaming properties and good resistance to oxidation. For worm gears, add up to 3 to 10 per cent of acid less tallow or similar animal fat.

The oil bath temperature should not exceed 200 degrees F. Where worm speed exceeds 3600 revolutions per minute, or 2000 feet per minute rubbing speed, a force feed lubrication may be required. Auxiliary cooling by forced air, water coils in sump, or an oil heat exchanger may be provided in a unit where mechanical horsepower rating is in excess of the thermal rating, if full advantage of mechanical capacity is to be realized. The rubbing speed (V), in feet per minute, may be calculated from the formula: $V = 0.262 \times$ worm throat diameter in inches $\times$ worm RPM $\div$ cos lead angle.

Worm Thread Cutting.— Worm threads are cut either by using some form of thread-cutting lathe and a single-point tool, by using a thread milling machine and a disk type of cutter, or by using a gear-hobbing machine. Single-thread worms usually have an included angle of 29 degrees. Many worm gears used at the present time, especially for power transmission, have thread angles larger than 29 degrees because multiple-thread worms are used to obtain higher efficiency, and larger thread angles are necessary in order to avoid excessive under-cutting of the worm-wheel teeth. According to the recommended practice of the American Gear Manufacturers' Association, worms having triple and quadruple threads should have a thread angle of 40 degrees, and some manufacturers of worm gearing, especially when the helix or lead angle of the thread is quite large, use a thread angle of 60 degrees.

If the helix or lead angle of the worm thread exceeds 15 or 20 degrees, it is common practice to reduce the depth of the thread by using the normal instead of the axial pitch of the worm in the formulas. Thus, if P_n equals normal pitch, the total depth equals $P_n \times 0.6866$ instead of $P_n = 0.6866$. This normal pitch P_n, equals $P_n \times$ cosine of the helix angle. According to the recommended practice of the American Gear Manufacturers' Association, the whole depth for single- and double-thread worms equals $P_n \times 0.686$, and for triple and quadruple-thread worms equals $P_n \times 0.623$.

Wormgear Hobs.— An ideal hob would have exactly the same pitch diameter and lead angle as the worm; repeated sharpening, however, would reduce the hob size because of the form-relieved teeth. Hence, the general practice is to make hobs (especially the radial or in-feed type) "over-size" to provide a grinding allowance and increase the hob life. An over-size hob has a larger pitch diameter and smaller lead angle than the worm, but repeated sharpenings gradually reduce these differences. To compensate for the smaller lead angle of an over-size hob, the hob axis may be set 90-degrees relative to the wormgear axis plus the difference between the lead angle of the worm at the pitch line, and the lead angle of the over-size hob at its pitch line. This angular adjustment is in the direction required to increase the inclination of the wormgear teeth so that the axis of the assembled worm will be 90 degrees from the wormgear axis. ("Lead angle" is measured from a plane perpendicular to worm or hob axis.)

Hob Diameter Formulas: If

D = pitch diameter of worm;
D_h = pitch diameter of hob;
A = addendum of worm and wormgear;
C = clearance between worm and worm-gear;
S = increase in hob diameter or "over-size" allowance for sharpening.

Outside diameter O of hob = $D + 2A + 2C + S$

Root diameter of hob = $D - 2A$

Pitch diameter D_h of hob = O–$(2A + 2C)$

Sharpening Allowance: Hobs for ordinary commercial work are given the following sharpening allowance, according to the recommended practice of the AGMA: In this for-

Copyright 2004, Industrial Press, Inc., New York, NY

mula, h = helix angle of hob at outside diameter measured from axis; H= helix angle of hob at pitch diameter measured from axis.

$$\text{Sharpening allowance} = 0.075 \times \text{normal pitch} \times \left[\frac{16 - (h - H)}{16}\right] + 0.010$$

Number of Flutes or Gashes in Hobs: For finding the approximate number of flutes in a hob, the following rule may be used: Multiply the diameter of the hob by 3, and divide this product by twice the linear pitch. This rule gives suitable results for hobs for general purposes. Certain modifications, however, are necessary as explained in the following paragraph.

It is important that the number of flutes or gashes in hobs bear a certain relation to the number of threads in the hob and the number of teeth in the wormgear to be hobbed. In the first place, avoid having a common factor between the number of threads in the hob and the number of flutes; that is, if the worm is double-threaded, the number of gashes should be, say, 7 or 9, rather than 8. If it is triple threaded, the number of gashes should be 7 or 11, rather than 6 or 9. The second requirement is to avoid having a common factor between the number of threads in the hob and the number of teeth in the wormgear. For example, if the number of teeth in the wheel is 28, it would be best to have the hob triple-threaded, as 3 is not a factor of 28. Again, if there were to be 36 threads in the wormgear, it would be preferable to have 5 threads in the hob.

The cutter used in gashing hobs should be from $\frac{1}{8}$ to $\frac{1}{4}$ inch thick at the periphery, according to the pitch of the thread of the hob. The width of the gash at the periphery of the hob should be about 0.4 times the pitch of the flutes. The cutter should be sunk into the hob blank so that it reaches from $\frac{3}{16}$ to $\frac{1}{4}$ inch below the root of the thread.

Helical Fluted Hobs.— Hobs are generally fluted parallel with the axis, but it is obvious that the cutting action will be better if they are fluted on a helix at right angles with the thread helix. The difficulty of relieving the teeth with the ordinary backing-off attachment is the cause for using a flute parallel with the axis. Flutes cut at right angles to the direction of the thread can, however, also be relieved, if the angle of the flutes is slightly modified. In order to relieve hobs with a regular relieving attachment, it is necessary that the number of teeth in one revolution along the thread helix be such that the relieving attachment can be geared to suit it. The following method makes it possible to select an angle of flute that will make the flute come approximately at right angles to the thread, and at the same time the angle is so selected that the relieving attachment can be properly geared for relieving the hob.

Let

C = pitch circumference
T = developed length of thread in one turn;
N = number of teeth in one turn along thread helix;
F = number of flutes;
α = angle of thread helix.

Copyright 2004, Industrial Press, Inc., New York, NY



Then $C \div F$= length of each small division on pitch circumference;

$(C \div F) \times \cos \alpha$ = length of division on developed thread;

$C \div \cos \alpha = T$

Hence

$$\frac{T}{(C \div F)\cos\alpha} = N = \frac{F}{\cos\alpha^2}$$

Now, if

$$\alpha = 30 \text{ degrees}, N = 1\tfrac{1}{3}F;$$

$$\alpha = 45 \text{ degrees}, N = 2F;$$

$$\alpha = 60 \text{ degrees}, N = 4F.$$

In most cases, however, such simple relations are not obtained. Suppose for example that $F = 7$, and $\alpha = 35$ degrees. Then $N = 10.432$, and no gears could be selected that would relieve this hob. By a very slight change in the helix angle of the flute, however, we can change N to 10 or $10\frac{1}{2}$; in either case we can find suitable gears for the relieving attachment.

The rule for finding the modified helical lead of the flute is: Multiply the lead of the hob by F, and divide the product by the difference between the desired values of N and F.

Hence, the lead of flute required to make N = 10 is:

Lead of hob $\times (7 \div 3)$.

To make $N = 10\frac{1}{2}$, we have:

Lead of flute = lead of hob $\times (7 \div 3.5)$.

From this the angle of the flute can easily be found.

That the rule given is correct will be understood from the following consideration. Change the angle of the flute helix β so that AG contains the required number of parts N desired. Then EG contains $N–F$ parts. But $\cot\beta = BD \div ED$ and by the law of similar triangles,

$$BD = \frac{F}{N} \times BG, \text{ and } ED = \frac{N-F}{N}C$$

The lead of the helix of the flute, however, is $C \times \cot \beta$.

Hence, the required lead of the helix of the flute:

$$C \times \cot\beta = \frac{F}{N-F}L$$

This formula makes it possible always to flute hobs so that they can be conveniently relieved, and at the same time have the flutes at approximately right angles to the thread.

Copyright 2004, Industrial Press, Inc., New York, NY

Gear Shaving

The purpose of gear shaving is to correct errors in indexing, helix angle, tooth profile, and eccentricity by removing small amounts of material from the working surfaces of gear teeth. Special shaving cutters are used and have tooth flanks with sharp-edged grooves that traverse the tooth surfaces of the gear to be corrected as the hardened, driven cutter and the softer (30-35 Rockwell C) free-running gear are rotated in mesh on crossed axes in a special machine. The crossed angle is usually between 10 and 15 degrees, or half the difference between the helix angles of cutter and gear. In conventional shaving, the gear is held between live centers on the machine table, which is moved parallel to the gear axis, and is fed into contact with the cutter at each successive stroke of the table. Cutter speeds of up to 450 surface feet/min are commonly used.

The crossed axes cause the sharp-edged grooves on the cutter to traverse the tooth surfaces on the gear as cutter and gear rotate, resulting in a shearing action that cuts fine slivers from the gear tooth surfaces. At the same time, contact between the meshing sets of teeth has a burnishing action on the gear teeth, improving the surface finish. Shaving can remove 60-80 per cent of errors in a gear, and can produce accuracies of 0.0002 in. on the involute profile, 0.0003 in. on tooth-to-tooth spacing, and 0.0002 in. on lead or parallelism.

Gear-shaving machines have built-in mechanisms that can be used to rock the table as it traverses, producing crowned gear teeth that are slightly thicker at the center than at the ends. In the faster diagonal shaving method, the traversing movement of the table is at an angle to the gear axis, so that the cutter grooves move more rapidly across the gear, increasing the shaving action.

Copyright 2004, Industrial Press, Inc., New York, NY

MISCELLANEOUS TOPICS

Mathematics

Catenary Curve.— The catenary is the curve assumed by a string or chain of uniform weight hanging freely between two supports. The cables of a suspension bridge, if uniformly loaded, assume the form of the catenary curve. It has, therefore, considerable importance in structural engineering.

Mechanics

Running Balance.— When a part such as a drum, rotor, crankshaft, pulley, etc., is properly tested for balance while revolving, and any appreciable lack of balance is corrected on the basis of such test, the part is said to be in running or dynamic balance. Special balancing machines are used to determine the magnitude and location of unbalanced masses while the part is revolving; hence, the test is applied under operating conditions, which is not true of the test for static or standing balance.

Properties of Materials

Copper-Clad Steel.— A material generally used in the form of wire, in which a steel wire is covered with a coating of copper. It is produced either by alloying the copper with the surface of the metal or by welding it onto the surface. When the copper is alloyed with the surface, it is brought to a molten state before being applied, while, when welded to the surface, it is merely in a plastic state.

Truflex.— Thermostatic bimetal made in different types for automatically controlling temperature ranges of from —50 degrees F. to 1000 degrees F. Used for automatically controlling the operation of devices either heated or cooled by electricity, oil, or gas, as, for example: electric refrigerators, irons, toasters, gas ranges, water heaters, and domestic oil burners. Available in helical and spiral coils, rings, flat pieces, U-shapes, and in sheets up to 8 inches wide.

Firebrick Properties.— Brick intended for use in furnaces, flues, and cupolas, where the brickwork is subjected to very high temperatures, is generally known as "firebrick." There are several classes of firebrick, such as fireclay brick, silica brick, bauxite brick, chrome brick, and magnesia brick.

Ordinary firebricks are made from fireclay; that is, clays which will stand a high temperature without fusion, excessive shrinkage, or warping. There is no fixed standard of refractoriness for fireclay, but, as a general rule, no clay is classed as a fireclay that fuses below 2900 degrees F.

Fireclays vary in composition, but they all contain high percentages of alumina and silica, and only small percentages of such constituents as oxide of iron, magnesia, lime, soda, and potash. A great number of different kinds of firebrick are manufactured to meet the various conditions to which firebricks are subjected. Different classes of bricks are required to withstand different temperatures, as well as the corrosive action of gases, the chemical action of furnace charges, etc.

The most common firebrick will melt at a temperature ranging from 2830 to 3140 degrees F.; bauxite brick, from 2950 to 3245 degrees F.; silica brick, from 3090 to 3100 degrees F.; chromite brick, at 3720 degrees F.; and magnesia brick, at 4950 degrees F.

Inconel.— This heat resistant alloy retains its strength at high heats, resists oxidation and corrosion, has a high creep strength and is non-magnetic. It is used for high temperature applications (up to 2000 degrees F.) such as engine exhaust manifolds and furnace and heat treating equipment. Springs operating at temperatures up to 700 degrees F. are also made from it.

Copyright 2004, Industrial Press, Inc., New York, NY

Approximate Composition: Nickel, 76; copper, 0.20; iron, 7.5; chromium, 15.5; silicon, 0.25; manganese, 0.25; carbon, 0.08; and sulphur, 0.007.

Physical Properties: Wrought Inconel in the annealed, hot-rolled, cold-drawn, and hard temper cold-rolled conditions exhibits yield strengths (0.2 per cent offset) of 35,000, 60,000, 90,000, and 110,000 pounds per square inch, respectively; tensile strengths of 85,000, 100,000, 115,000, and 135,000 pounds per square inch, respectively; elongations in 2 inches of 45, 35, 20, and 5 per cent, respectively; and Brinell hardnesses of 150, 180, 200, and 260, respectively.

Inconel "X".— This alloy has a low creep rate, is age-hardenable and non-magnetic, resists oxidation and exhibits a high strength at elevated temperatures. Uses include the making of bolts and turbine rotors used at temperatures up to 1500 degrees F., aviation brake drum springs and relief valve and turbine springs with low load loss or relaxation for temperatures up to 1000 degrees F.

Approximate Composition: Nickel, 73; copper, 0.2 maximum; iron, 7; chromium, 15; aluminum, 0.7; silicon, 0.4; manganese, 0.5; carbon, 0.04; sulphur, 0.007; columbium, 1; and titanium, 2.5.

Average Physical Properties: Wrought Inconel "X" in the annealed and age-hardened hot-rolled conditions exhibits yield strengths (0.2 per cent offset) of 50,000 and 120,000 pounds per square inch, respectively; tensile strengths of 115,000 and 180,000 pounds per square inch, respectively; elongations in 2 inches of 50 and 25 per cent, respectively; and Brinell hardnesses of 200 and 360, respectively.

Lodestone.— The most highly magnetic substances are iron and steel. Nickel and cobalt are also magnetic, but in a less degree. The name "magnet" has been derived from that of Magnesia, a town in Asia Minor, where an iron ore was found in early days which had the power of attracting iron.

This ore is known as magnetite and consists of about 72 per cent, by weight, of iron and 28 per cent of oxygen, the chemical formula being Fe_3O_4. The ore possessing this magnetic property is also known as lodestone. If a bar of hardened steel is rubbed with a piece of lodestone, it will acquire magnetic properties similar to those of the lodestone itself.

Metallography.— The science or study of the microstructure of metal is known by most metallurgists as "metallography." The name "crystallography" is also used to some extent. The examination of metals and metal alloys by the aid of the microscope has become one of the most effective methods of studying their properties, and it is also a valuable means of controlling the quality of manufactured metallic articles and of testing the finished product. In preparing the specimen to be examined, a flat surface is first formed by filing or grinding, and this surface is then given a high polish, which is later subjected to the action of a suitable acid or etching reagent, in order to reveal clearly the internal structure of the metal when the specimen is examined under the microscope. This process shows clearly to an experienced observer the effect of variation in composition, heat-treatment, etc., and in many cases it has proved a correct means of determining certain properties of industrial products that a chemical analysis has failed to reveal.

Preparing Hardened Steel for Microscopic Study: To cause the constituents of the specimen to contrast with one another as seen through the microscope is the desired end, and a reagent is used which acts differently towards these elements; generally this reagent acts on one element more than on another so that the one least affected reflects the light from the faces of its crystals while the etched part absorbs the light, and, therefore, appears dark when photographed.

In etching specimens to develop the constituents of hardened anti tempered steels, very good results are obtained with sulphurous acid that is composed of 4 parts of sulphur dioxide to 96 parts of distilled water. The specimens are immersed in this, face upward, and removed as soon as the polished surface is frosted. This takes from 7 seconds to 1 minute.

Copyright 2004, Industrial Press, Inc., New York, NY

They are then rinsed with water and dried with alcohol. Very thin layers of iron sulphide are deposited on the different constituents in different thicknesses, and this gives them different colors. Austenite remains a pale brown; martensite is given a pale blue and deep blue and brown color; troostite is made very dark; sorbite is uncolored; cementite exhibits a brilliant white; and ferrite is made dark brown. When the etching has proceeded to the desired extent, the specimen is at once washed thoroughly in order to remove all trace of the etching reagent. Usually it is simply rinsed with water, but frequently the washing is done with absolute alcohol, while ether and chloroform are also sometimes used.

The apparatus used for examining the etched surfaces of metals is composed of a microscope and camera combined with an arc lamp or other means of illumination.

Microscopic Study of Steel: Steel, in particular, shows many changes of structure due to the mechanical and thermal treatment, so that the microscope has become a very valuable instrument with which to inspect steel. To one who understands what the different formations of crystalline structure denote, the magnified surface reveals the temperature at which the steel was hardened, or at which it was drawn, and the depth to which the hardness penetrated. It also shows whether the steel was annealed or casehardened, as well as the depth to which the carbon penetrated. The carbon content can be closely judged, when the steel is annealed, and also how much of it is in the graphitic state in the high carbon steels. The quantity of special elements that is added to steel, such as nickel, chromium, tungsten, etc., can also be estimated, when the alloy to be examined has been put through its prescribed heat-treatment. Likewise, the impurities that may be present are clearly seen, regardless of whether they are of solid or gaseous origin.

Micarta.— Micarta is a non-metallic laminated product of specially treated woven fabric. By means of the various processes through which it is passed, it becomes a homogenous structure with physical properties which make it especially adapted for use as gears and pinions. Micarta can be supplied either in plate form or cut into blanks. It may also be molded into rings or on metal hubs for applications such as timing gears, where quantity production is attained. Micarta may be machined in the ordinary manner with standard tools and equipment.

Micarta gears do not require shrouds or end plates except where it is desired to provide additional strength for keyway support or to protect the keyway and bore against rough usage in mounting drive fits and the like. When end plates for hub support are employed they should extend only to the root of the tooth or slightly less.

Properties: The physical and mechanical properties of Micarta are as follows: weight per cubic inch, 0.05 pound; specific gravity, 1.4; oil absorption, practically none; shrinkage, swelling or warping, practically none up to 100 degrees C.; coefficient of expansion per inch per degree Centigrade, 0.00002 inch in the direction parallel to the laminations (edgewise), 0.00009 inch in the direction perpendicular to the laminations (flat wise) ; tensile strength, edgewise, 10,000 pounds per square inch; compressive strength, flat wise, 40,000 pounds per square inch; compressive strength, edgewise, 20,000 pounds per square inch; bending strength, flatwise, 22,000 pounds per square inch; bending strength, edgewise, 20,000 pounds per square inch.

Monel.— This general purpose alloy is corrosion-resistant, strong, tough and has a silvery-white color. It is used for making abrasion- and heat-resistant valves and pump parts, propeller shafts, laundry machines, chemical processing equipment, etc.

Approximate Composition: Nickel, 67; copper, 30; iron, 1.4; silicon, 0.1; manganese, 1; carbon, 0.15; and sulphur 0.01.

Average Physical Properties: Wrought Monel in the annealed, hot-rolled, cold-drawn, and hard temper cold-rolled conditions exhibits yield strengths (0.2 per cent offset) of 35,000, 50,000, 80,000, and 100,000 pounds per square inch, respectively; tensile strengths of 75,000, 90,000, 100,000, and 110,000 pounds per square inch, respectively;

Copyright 2004, Industrial Press, Inc., New York, NY

elongations in 2 inches of 40, 35, 25, and 5 per cent, respectively; and Brinell hardnesses of 125, 150, 190, and 240, respectively.

"R" Monel.— This free-cutting, corrosion resistant alloy is used for automatic screw machine products such as bolts, screws and precision parts.

Approximate Composition: Nickel, 67; copper, 30; iron, 1.4; silicon, 0.05; manganese, 1; carbon, 0.15; and sulphur, 0.035.

Average Physical Properties: In the hot-rolled and cold-drawn conditions this alloy exhibits yield strengths (0.2 per cent offset) of 45,000 and 75,000 pounds per square inch, respectively; tensile strengths of 85,000 and 90,000 pounds per square inch, respectively; elongations in 2 inches of 35, and 25 per cent, respectively; and Brinell hardnesses of 145 and 180, respectively.

"K" Monel.— This strong and hard alloy, comparable to heat-treated alloy steel, is age-hardenable, non-magnetic and has low-sparking properties. It is used for corrosive applications where the material is to be machined or formed, then age hardened. Pump and valve parts, scrapers, and instrument parts are made from this alloy.

Approximate Composition: Nickel, 66; copper, 29; iron, 0.9; aluminum, 2.75; silicon, 0.5; manganese, 0.75; carbon, 0.15; and sulphur, 0.005.

Average Physical Properties: In the hot-rolled, hot-rolled and age-hardened, cold-drawn, and cold-drawn and age-hardened conditions the alloy exhibits yield strengths (0.2 per cent offset) of 45,000, 110,000, 85,000, and 115,000 pounds per square inch, respectively; tensile strengths of 100,000, 150,000, 115,000, and 155,000 pounds per square inch, respectively; elongations in 2 inches of 40, 25, 25, and 20 per cent, respectively; and Brinell hardnesses of 160, 280, 210, and 290, respectively.

"KR" Monel.— This strong, hard, age-hardenable and non-magnetic alloy is more readily machinable than "K" Monel. It is used for making valve stems, small parts for pumps, and screw machine products requiring an age-hardening material that is corrosion-resistant.

Approximate Composition: Nickel, 66; copper, 29; iron, 0.9; aluminum, 2.75; silicon, 0.5; manganese, 0.75; carbon, 0.28; and sulphur, 0.005.

Average Physical Properties: Essentially the same as "K" Monel.

"S" Monel.— This extra hard casting alloy is non-galling, corrosion-resisting, non-magnetic, age-hardenable and has low-sparking properties. It is used for gall-resistant pump and valve parts which have to withstand high temperatures, corrosive chemicals and severe abrasion.

Approximate Composition: Nickel, 63; copper, 30; iron, 2; silicon, 4; manganese, 0.75; carbon, 0.1; and sulphur, 0.015.

Average Physical Properties: In the annealed sand-cast, as-cast sand-cast, and age-hardened sand-cast conditions it exhibits yield strengths (0.2 per cent offset) of 70,000, 100,000, and 100,000 pounds per square inch, respectively; tensile strengths of 90,000, 130,000, and 130,000 pounds per square inch, respectively; elongations in 2 inches of and 3, 2, and 2 per cent, respectively; and Brinell hardnesses of 275, 320, and 350, respectively.

"H" Monel.— An extra hard casting alloy with good ductility, intermediate strength and hardness that is used for pumps, impellers and steam nozzles.

Approximate Composition: Nickel, 63; copper, 31; iron, 2; silicon, 3; manganese, 0.75; carbon, 0.1; and sulphur, 0.015.

Average Physical Properties: In the as-cast sand-cast condition this alloy exhibits a yield strength (0.2 per cent offset) of 60,000 pounds per square inch, a tensile strength of 100,000 pounds per square inch, an elongation in 2 inches of 15 per cent and a Brinell hardness of 210.

Nichrome.— "Nichrome" is the trade name of an alloy composed of nickel and chromium, which is practically non-corrosive and far superior to nickel in its ability to withstand high

Copyright 2004, Industrial Press, Inc., New York, NY

temperatures. Its melting point is about 1550 degrees C. (about 2800 degrees F.). Nichrome shows a remarkable resistance to sulphuric and lactic acids. In general, nichrome is adapted for annealing and carburizing boxes, heating retorts of various kinds, conveyor chains subjected to high temperatures, valves and valve seats of internal combustion engines, molds, plungers and conveyors for use in the working of glass, wire baskets or receptacles of other form that must resist the action of acids, etc. Nichrome may be used as a substitute for other materials, especially where there is difficulty from oxidation, pitting of surfaces, corrosion, change of form, or lack of strength at high temperatures. It can be used in electrically-heated appliances and resistance elements. Large plates of this alloy are used by some manufacturers for containers and furnace parts, and when perforated, as screens for use in chemical sifting and ore roasting apparatus, for services where temperatures between 1700 degrees F. and 2200 degrees F. are encountered.

Strength of Nichrome: The strength of a nichrome casting, when cold, varies from 45,000 to 50,000 pounds per square inch. The ultimate strength at 200 degrees F. is 94,000 pounds per square inch; at 400 degrees F., 91,000 pounds per square inch; at 600 degrees F., 59,000 pounds per square inch; and at 800 degrees F., 32,000 pounds per square inch. At a temperature of 1800 degrees F., nichrome has a tensile strength of about 30,000 pounds per square inch, and it is tough and will bend considerably before breaking, even when heated red or white hot.

Nichrome in Cast Iron: Because of the irregularity of the castings, the numerous cores required, and the necessity for sound castings, gray iron with a high silicon content has been the best cast iron available to the automotive industry. Attempts have been made to alloy this metal in such a way that the strength and hardness would be increased, but considerable difficulty has been experienced in obtaining uniform results. Nickel has been added to the cupola with success, but in the case of automotive castings, where a large quantity of silicon is present, the nickel has combined with the silicon in forming large flakes of graphite, which, of course, softens the product. To offset this, chromium has also been added, but it has been uncertain just what the chromium content of the poured mixture should be, as a considerable amount of the chromium oxidizes.

Nichrome (Grade B) may be added to the ladle to obtain chromium and nickel in definite controllable amounts. The analysis of this nichrome is, approximately: Nickel, 60 per cent; chromium, 12 per cent; and iron, 24 per cent. It is claimed that the process produces castings of closer grain, greater hardness, greater resistance to abrasion, increased durability, improved machinability, and decreased brittleness. Nichrome-processed iron is suitable for casting internal-combustion engine cylinders; electrical equipment, where a control of the magnetic properties is desired; cast-iron cams; iron castings of thin sections where machinability and durability are factors; electrical resistance grids; pistons; piston-rings; and water, steam, gas, and other valves.

Nickel Alloy for Resisting Acids.— The resistance of nickel to acids is considerably increased by an addition of tantalum. Ordinarily from 5 to 10 per cent may be added, but the resistance increases with an increasing percentage of tantalum. An alloy of nickel with 30 per cent tantalum, for example, can be boiled in aqua regia or any other acid without being affected. The alloy is claimed to be tough, easily rolled, capable of being hammered or drawn into wire. The nickel loses its magnetic quality when alloyed with tantalum. The alloy can be heated in the open air at a high temperature without oxidizing. The method of producing the alloy consists in mixing the two metals in a powdered form, compressing them at high pressure, and bringing them to a high heat in a crucible or quartz tube in a vacuum. For general purposes, the alloy is too expensive.

Duronze.— An alloy of high resistance to wear and corrosion, composed of aluminum, copper, and silicon, with a tensile strength of 90,000 pounds per square inch. Developed for the manufacture of valve bushings for valves that must operate satisfactorily at high pressures and high temperatures without lubrication.

Copyright 2004, Industrial Press, Inc., New York, NY

Aluminum Alloys, Wrought, Sheet.— *Physical Properties:* In the form of sheets, the tensile strength varies from 35,000 for soft temper to 62,000 pounds per square inch for heat-treated sheets, and the elongation in 2 inches from 12 to 18 per cent. The yield strength of a heat-treated sheet is about 40,000 pounds per square inch minimum.

Plow-steel Wire Rope.— The name "plow" steel originated in England and was applied to a strong grade of steel wire used in the construction of very strong ropes employed in the mechanical operation of plows. The name "plow" steel, however, has become a commercial trade name, and, applied to wire, simply means a high-grade open-hearth steel of a tensile strength in wire of from 200,000 to 260,000 pounds per square inch of sectional area. A strength of 200,000 pounds per square inch is obtained in wire about 0.200 inch in diameter. Plow steel when used for wire ropes has the advantage of combining lightness and great strength. It is a tough material, but not as pliable as crucible steel. The very highest grade of steel wire used for wire rope is made from special steels ranging in tensile strength in wire from 220,000 to 280,000 pounds per square inch of sectional area. This steel is especially useful when great strength, lightness, and abrasive resisting qualities are required.

Type Metal.— Antimony gives to metals the property of expansion on solidification, and hence, is used in type metal for casting type for the printing trades to insure completely filling the molds. Type metals are generally made with from 5 to 25 per cent of antimony, and with lead, tin and sometimes a small percentage of copper as the other alloying metals.

The compositions of a number of type metal alloys are as follows (figures given are percentages): lead 77.5, tin 6.5, antimony 16; lead 70, tin, 10, antimony 18, copper, 2; lead 63.2, tin 12, antimony 24, copper 0.8 ; lead 60.5, tin 14.5, antimony 24-25, copper 0.75; lead 60, tin 35, antimony 5; and lead 55.5, tin 40, antimony 4.5.

A high grade of type metal is composed of the following percentages: lead 50; tin 25; and antimony 25.

Vanadium Steel.— The two most marked characteristics of vanadium steel are its high tensile strength and its high elastic limit. Another equally important characteristic is its great resistance to shocks; vanadium steel is essentially a non-fatigue metal, and, therefore, does not become crystallized and break under repeated shocks like other steels. Tests of the various spring steels show that, when subjected to successive shocks for a considerable length of time, a crucible carbon-steel spring was broken by 125,000 alternations of the testing machine, while a chrome-vanadium steel spring withstood 5,000,000 alternations, remaining unbroken. Another characteristic of vanadium steel is its great ductility. Highly-tempered vanadium-steel springs may be bent sharply, in the cold state, to an angle of 90 degrees or more, and even straightened again, cold, without a sign of fracture; vanadium-steel shafts and axles may be twisted around several complete turns, in the cold state, without fracture. This property, combined with its great tensile strength, makes vanadium steel highly desirable for this class of work, as well as for gears which are subjected to heavy strains or shocks upon the teeth. Chromium gives to steel a brittle hardness which makes it very difficult to forge, machine, or work, but vanadium, when added to chrome-steel, reduces this brittle hardness to such an extent that it can be machined as readily as an 0.40-per-cent carbon steel, and it forges much more easily. Vanadium steels ordinarily contain from 0.16 to 0.25 per cent of vanadium. Steels of this composition are especially adapted for springs, car axles, gears subjected to severe service, and for all parts which must withstand constant vibration and varying stresses. Vanadium steels containing chromium are used for many automobile parts, particularly springs, axles, driving-shafts, and gears.

Wood's Metal.— The composition of Wood's metal, which is a so-called "fusible metal," is as follows: 50 parts of bismuth, 25 parts of lead, 12.5 parts of tin and 12.5 parts of cadmium. The melting point of this alloy is from 66 to 71 degrees centigrade (151 to 160 degrees F. approximately).

Copyright 2004, Industrial Press, Inc., New York, NY

Lumber.— Lumber is the product of the saw and planing mill not further manufactured than by sawing, resawing, and passing lengthwise through a standard planing machine, cross-cutting to length and working. When not in excess of one-quarter inch thickness and intended for use as veneering it is classified as veneer. According to the Simplified Practice Recommendations promulgated by the National Bureau of Standards, lumber is classified by its principal use as: yard lumber, factory and shop lumber, and structural lumber.

Yard lumber is defined as lumber of all sizes and patterns which is intended for general building purposes. Its grading is based on intended use and is applied to each piece without reference to size and length when graded and without consideration to further manufacture. As classified by size it includes: strips, which are yard lumber less than 2 inches thick and less than 8 inches wide; boards, which are yard lumber less than 2 inches thick but 8 inches or more wide; dimension, which includes all yard lumber except strips, boards and timbers; and timbers, which are yard lumber of 5 or more inches in the least dimension.

Factory and shop lumber is defined as lumber intended to be cut up for use in further manufacture. It is graded on the basis of the percentage of the area which will produce a limited number of cuttings of a specified, or of a given minimum, size and quality.

Structural lumber is defined as lumber that is 2 or more inches thick and 4 or more inches wide, intended for use where working stresses are required. The grading of structural lumber is based on the strength of the piece and the use of the entire piece. As classified by size and use it includes *joists* and *planks*—lumber from 2 inches to but not including 5 inches thick, and 4 or more inches wide, of rectangular cross section and graded with respect to its strength in bending, when loaded either on the narrow face as joist or on the wide face as plank; *beams* and *stringers*—lumber of rectangular cross section 5 or more inches thick and 8 or more inches wide and graded with respect to its strength in bending when loaded on the narrow face; and *posts* and *timbers*—pieces of square or approximately square cross section 5 by 5 inches and larger and graded primarily for use as posts or columns carrying longitudinal load, but adapted to miscellaneous uses in which strength in bending is not especially important.

Lumber, Manufactured.— According to the Simplified Practice Recommendations promulgated by the National Bureau of Standards, lumber may be classified according to the extent which It Is manufactured as:

Rough lumber which is lumber that is undressed as it comes from the saw.

Surfaced lumber which is lumber that is dressed by running it through a planer and may be surfaced on one or more sizes and edges.

Worked lumber which is lumber that has been run through a matching machine, sticker or molder and includes: *matched lumber* which has been worked to provide a close tongue-and-groove joint at the edges or, in the case of end-matched lumber, at the ends also; *shiplapped lumber* which has been worked to provide a close rabbetted or lapped joint at the edges; and *patterned lumber* which has been shaped to a patterned or molded form.

Lumber Water Content.— The origin of lumber has a noticeable effect on its water content. Lumber or veneer (thin lumber produced usually by rotary cutting or flat slicing, sometimes by sawing), when produced from the log, contains a large proportion of water, ranging from 25 to 75 per cent of the total weight. One square foot (board measure, one inch thick) of gum lumber, weighing approximately five pounds when sawed, will be reduced to about three pounds when its water content of approximately one quart has been evaporated. Oak grown on a hillside may contain only a pint (approximately 1 lb.) and swamp gum may have from 2 to 4 pints of water per square foot, board measure. This water content of wood exists in two forms—free moisture and cell moisture. The former is readily evaporable in ordinary air drying, but the latter requires extensive air drying (several years) or artificial treatment in kilns. It is possible to use artificial means to remove the free moisture, but a simple air exposure is usually more economical.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensioning, Gaging, and Measuring

Transfer Calipers.— Calipers provided with an auxiliary arm which can be located so that the calipers may be opened or closed to the original setting, if required. Calipers of this type are generally used for inside measurements, and are employed for measuring recesses where it is necessary to move the caliper points in order to remove the calipers from the place where the measurement is taken.

Wheatstone Bridge.— The most generally used method for the measurement of the ohmic resistance of conductors is by the use of the *Wheatstone bridge*. In a simple form (See Fig. 1.) it comprises two resistance coils the ratio of the resistances of which is known, and a third, generally adjustable, resistance of known value. These are connected in circuit with the unknown resistance to be measured, a galvanometer, and a source of current, as in the diagram.



Fig. 1. Wheatstone Bridge

The adjustable resistance and the "bridge arms," if necessary, are adjusted until the galvanometer indicates no flow of current. The value of the unknown resistance is thus measured in terms of the known resistance and the known ratio of the bridge arms. In the diagram, R_1, R_2, R_3, and R_4 are resistances, B a source of electromotive force and I_1, I_2, I_3 and I_4 currents through the resistances; G is a galvanometer. If the relation of the various resistances is such that no current flows through G, then I_1 equals I_2, and I_3 equals I_4; also I_1R_1 equals I_3R_3, and I_2R_2 equals I_4R_4, there being no electromotive forces in the triangles R_1R_3G and R_2R_4G. It follows, therefore, that

$$\frac{I_1}{I_3} = \frac{R_3}{R_1}, \qquad \text{and} \qquad \frac{I_2}{I_4} = \frac{R_4}{R_2}$$

and hence, as

$$\frac{I_1}{I_3} = \frac{I_2}{I_4}, \qquad \text{it follows that} \qquad \frac{R_3}{R_1} = \frac{R_4}{R_2}$$

If one of these resistances, R_1 for instance, is unknown, it may then be found through the equation:

Copyright 2004, Industrial Press, Inc., New York, NY

$$R_1 = \frac{R_2 R_3}{R_4}$$

Wheatstone bridges are made in many forms. The three known resistances are made adjustable and are usually made of many spools of special resistance wire. The resistances are usually varied by short-circuiting a greater or smaller number of these spools.

Tools and Tooling

Rotary Files and Burs.— Rotary files and burs are used with power-operated tools, such as flexible- or stationary-shaft machines, drilling machines, lathes, and portable electric or pneumatic tools, for abrading or smoothing metals and other materials. Corners can be broken and chamfered, burs and fins removed, holes and slots enlarged or elongated, and scale removed in die-sinking, metal patternmaking, mold finishing, toolmaking and casting operations.

The difference between rotary files and rotary burs, as defined by most companies, is that the former have teeth cut by hand with hammer and chisel, whereas the latter have teeth or flutes ground from the solid blank after hardening, or milled from the solid blank before hardening. (At least one company, however prefers to differentiate the two by use and size: The larger-sized general purpose tools with $\frac{1}{4}$-inch shanks, whether hand cut or ground, are referred to as rotary files; the smaller shanked – $\frac{1}{8}$-inch – and correspondingly smaller-headed tools used by diesinkers and jewelers are referred to as burs.) Rotary files are made from high-speed steel and rotary burs from high-speed steel or cemented carbide in various cuts such as double extra coarse, extra coarse or rough, coarse or standard, medium, fine, and smooth. Standard shanks are $\frac{1}{4}$ inch in diameter.

There is very little difference in the efficiency of rotary files or burs when used in electric tools and when used in air tools, provided the speeds have been reasonably well selected. Flexible-shaft and other machines used as a source of power for these tools have a limited number of speeds which govern the revolutions per minute at which the tools can be operated.

The carbide bur may be used on hard or soft materials with equally good results. The principal difference in construction of the carbide bur is that its teeth or flutes are provided with negative rather than a radial rake. Carbide burs are relatively brittle and must be treated more carefully than ordinary burs. They should be kept cutting freely, in order to prevent too much pressure, which might result in crumbling of the cutting edges.

At the same speeds, both high-speed steel and carbide burs remove approximately the same amount of metal. However, when carbide burs are used at their most efficient speeds, the rate of stock removal may be as much as four times that of ordinary burs. It has been demonstrated that a carbide bur will last up to 100 times as long as a high-speed steel bur of corresponding size and shape.

Tooth-rest for Cutter Grinding.— A tooth-rest is used to support a cutter while grinding the teeth. For grinding a cylindrical cutter having helical or "spiral" teeth, the tooth-rest must remain in a fixed position relative to the grinding wheel. The tooth being ground will then slide over the tooth-rest, thus causing the cutter to turn as it moves longitudinally, so that the edge of the helical tooth is ground to a uniform distance from the center, throughout its length. For grinding a straight-fluted cutter, it is also preferable to have the tooth-rest in a fixed position relative to the wheel, unless the cutter is quite narrow, because any warping of the cutter in hardening will result in inaccurate grinding, if the toothrest moves with the work. The tooth-rest should be placed as close to the cutting edge of the cutter as is practicable, and bear against the face of the tooth being ground.

Copyright 2004, Industrial Press, Inc., New York, NY

Machining Operations

Feed Rate on Machine Tools.— The rate of feed as applied to machine tools in general, usually indicates (1) the movement of a tool per work revolution, (2) the movement of a tool per tool revolution, (3) or the movement of the work per tool revolution.

Rate of Feed in Turning: The term "feed" as applied to a lathe indicates the distance that the tool moves during each revolution of the work. There are two ways of expressing the rate of feed. One is to give the actual tool movement per work revolution in thousandths of an inch. For example, the range of feeds may be given as 0.002 to 0.125 inch. This is the usual method. Another way of indicating a feed range is to give the number of cuts per inch or the number of ridges that would be left by a pointed tool after turning a length of one inch. For example, the feed range might be given as 8 to 400. In connection with turning and other lathe operations, the feed is regulated to suit the kind of material, depth of cut, and in some cases the finish desired.

Rate of Feed in Milling: The feed rate of milling indicates the movement of the work per cutter revolution.

Rate of Feed in Drilling: The rate of feed on drilling machines ordinarily indicates the feeding movement of the drill per drill revolution.

Rate of Feed in Planing: On planers, the rate of feed represents the tool movement per cutting stroke. On shapers, which are also machines of the planing type, the rate of feed represents the work movement per cutting stroke.

Rate of Feed on Gear Hobb era: The feed rate of a gear hobbing machine represents the feeding movement of the hob per revolution of the gear being hobbed.

Feed on Grinding Machines:: The traversing movement in grinding is equivalent to the feeding movement on other types of machine tools and represents either the axial movement of the work per work revolution or the traversing movement of the wheel per work revolution, depending upon the design of the machine.

Billet.— A "billet," as the term is applied in rolling mill practice, is square or round in section and from 1½ inches in diameter or square to almost 6 inches in diameter or square. Rolling mills used to prepare the ingot for the forming mills are termed "blooming mills," "billet mills," etc.

Milling Machines, Lincoln Type.— The well-known Lincoln type of milling machine is named after George S. Lincoln of the firm then known as George S. Lincoln & Co., Hartford, Conn. Mr. Lincoln, however, did not originate this type but he introduced an improved design. Milling machines constructed along the same general lines had previously been built by the Phoenix Iron Works of Hartford, Conn., and also by Robbins & Lawrence Co., of Windsor, Vt. Milling machines of this class are intended especially for manufacturing and are not adapted to a great variety of milling operations, but are designed for machining large numbers of duplicate parts. Some milling machines which are designed along the same lines as the Lincoln type are referred to as the *manufacturing type*. The distinguishing features of the Lincoln type are as follows: The work table, instead of being carried by an adjustable knee, is mounted on the solid bed of the machine and the outer arbor support is also attached directly to the bed. This construction gives a very rigid support both for the work and the cutter. The work is usually held in a fixture or vise attached to the table, and the milling is done as the table feeds longitudinally. The table is not adjustable vertically but the spindle head and spindles can be raised or lowered as may be required.

Saddle.— A machine tool saddle is a slide which is mounted upon the ways of a bed, cross-rail, arm, or other guiding surfaces, and the saddle metal-cutting tools or a work-holding table. On holding either metal-cutting tools or a work-holding table. On a knee-type milling machine the saddle is that part which slides upon the knee and which supports the work-holding table. The saddle of a planer or boring mill is mounted upon the cross-rail

Copyright 2004, Industrial Press, Inc., New York, NY

and supports the tool-holding slide. The saddle of a lathe is that part of a carriage which slide. The saddle of a lathe is that part of a carriage which slides directly upon the lathe bed and supports the cross-slide.

Cold Extrusion.— In simplest terms, cold extrusion can be defined as the forcing of unheated metal to flow through a shape-forming die. It is a method of shaping metal by plastically deforming it under compression at room temperature while the metal is within a die cavity formed by the tools. The metal issues from the die in at least one direction with the desired cross-sectional contour, as permitted by the orifice created by the tools.

Cold extrusion is always performed at a temperature well below the recrystallization temperature of the metal (about 1100 to 1300 degrees F. for steel) so that work-hardening always occurs. In hot extrusion, recrystallization eliminates the effects of work-hardening, unless rapid cooling of the extrusion prevents recrystallization from being completed.

Extrusion differs from other processes, such as drawing, in that the metal is always being pushed under compression and never pulled in tension. As a result, the material suffers much less from cracking. While coining is closely related to extrusion, it differs in that metal is completely confined in the die cavity instead of being forced through openings in the die. Some forging operations combine both coining and extrusion.

The pressure of the punch against the metal in an open die, and the resultant shaped part obtained by displacing the metal along paths of least resistance through an orifice formed between the punch and die, permits considerably higher deformation rates without tearing and large changes in the shape. Extrusion is characterized by a thorough kneading of the material. The cross-sectional shape of the part will not change due to expansion or contraction as it leaves the tool orifice. The term "cold extrusion" is not too descriptive and is not universally accepted. Other names for the same process include impact extrusion, extrusion-forging, cold forging, extrusion pressing, and heavy cold forming. Impact extrusion, however, is more frequently used to describe the production of non-ferrous parts, such as collapsible tubes and other components, while cold extrusion seems to be preferred by manufacturers of steel parts. In Germany, the practice is called Kaltspritzen-a literal translation of which is "cold-squirting."

One probable reason for not using impact extrusion in referring to the cold extrusion of steel is that the term implies plastic deformation by striking the metal an impact blow. Actually, the metal must be pushed through the die orifice, with pressure required over a definite period of time. One disadvantage of the terminology "cold extrusion" is the possible confusion with the older, more conventional direct extrusion process in which billets of hot metal are placed in a cylinder and pushed by a ram through a die (usually in a large, horizontal hydraulic press) to form rods, bars, tubes, or irregular shapes of considerable length.

Another possible disadvantage is the connotation of the word "cold." While the process is started with blanks, slugs, tubular sections, or pre-formed cups at room temperature, the internal, frictional resistance of the metal to plastic flow raises the surface temperature of the part to 400 degrees F. or more, and the internal temperature even higher (depending on the severity of the operation). These are still below the recrystallization temperature and the extrusions retain the advantages of improved physical properties resulting from the cold working.

Transfer Machines.— These specialized machine tools are used to perform various machining operations on parts or parts in fixtures as the parts are moved along on an automatic conveyor which is part of the machine tool set-up. In a set-up, the parts can move in a straight line from their entry point to their exit point, or the setup may be constructed in a U-shape so that the parts are expelled near where they start.

Copyright 2004, Industrial Press, Inc., New York, NY

Fasteners

Stove Bolt.— This bolt has been so named because of its use in stove building. It is made in a number of different forms, either with a round button, or flat countersunk head, the head having a slot for a screwdriver and the threaded end being provided with a square or hexagon nut.

Flattening Test.— This term as applied to tubing refers to a method of testing a section of tubing by flattening it until the inside walls are parallel and separated by a given distance-usually equal to three times the wall thickness for seamless tubes and five times the wall thickness for lap-welded tubes. Boiler tubes subjected to this test should show no cracks or flaws. The flattening test applied to rivets, consists in flattening a rivet head while hot to a diameter equal to $2\frac{1}{2}$ times the diameter of the shank or body of the rivet. Good rivet steel must not crack at the edges of the flattened head.

Rivets, Cold Formed.— In permanently assembling various Light parts, it is often possible to greatly reduce the cost and yet secure sufficient strength by cold forming in an assembling die, the rivet or rivets as an integral part of one of the assembled sections. Figures 1a, 1b, and 1c illustrate how a steel spring is cold riveted to the heavier section. Plain round punches descend and form the rivets by forcing metal down through the holes in the spring (see Fig. 1b) ; the metal at the edge is then turned back by the die as shown in Fig. 1c, thus completing the riveting at one stroke of the press. In this particular case, about sixty assemblies per minute are obtained.

Embossed Dowels and Hubs: When dowel-pins are required to insure the accurate location of parts relative to each other, small projections or bosses may be formed directly on many die-made products, the projection being an integral part of the work and serving as a dowel-pin. Figure 1d illustrates how the dowel is formed. The method may be described as a partial punching operation, as a punch penetrate about one-half the stock thickness and forces the boss into a pocket in the die which controls the diameter and compresses the metal, thus forming a stronger projection than would be obtained otherwise. The height h of the dowel or boss should not exceed one-half of the dowel diameter d and h. should not exceed one-half of the stock thickness t. This is a practical rule which may be applied either to steel or non-ferrous metals, such as brass.



Fig. 1a.



Fig. 1b.



Fig. 1c.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1d.

Expansion Bolt.— When a through bolt cannot be used for attaching a pipe hanger, bracket, or other part, to a wall or ceiling of brick or concrete, what are known as *expansion* bolts are often used. The body of an expansion bolt is divided and the arrangement is such that, when the head of the bolt is turned, the sections forming the body of the bolt are forced outward and against the wall of the hole which has been drilled into the brick, concrete, or stone, as the case may be. Bolts of this type are made in quite a variety of designs. The nominal size represents the diameter of the bolt proper and not the diameter of the casing or expansion member.



Fig. 2. Expansion Bolt

Washers.— Plain washers are made in standard sizes to suit standard screw threads, bolts and screws. The manufacturers' regular standard, adopted in 1935, is for bolt sizes ranging from ¼ inch up to 3 inches, inclusive. There is also an S.A.E. standard for plain washers. This includes screw and bolt sizes ranging from No. 2 machine screw up to, and including. 1½-inch bolts. These washers are somewhat smaller than the manufacturers' standard and also have smaller inside diameters or clearance spaces between the bolt and washer.

Threads and Threading

History of Briggs Pipe Thread (NPT).— The USA (American) Standard for Pipe Threads, originally known as the Briggs Standard, was formulated by Mr. Robert Briggs. For several years around 1862 Mr. Briggs was superintendent of the Pascal Iron Works of Morris, Tasker & Company, Philadelphia, Pa., and later engineering editor of the "Journal" of the Franklin Institute. After his death on July 24, 1882, a paper by Mr. Briggs containing detailed information regarding American pipe and pipe thread practice, as developed by him when superintendent of the Pascal Iron Works, was read before the Institution of Civil Engineers of Great Britain. This is recorded in the Excerpt Minutes, Volume LXXI, Session 1882–1883, Part 1, of that Society.

It is of interest to note that the nominal sizes (diameters) of pipe ten (10) inches and under, and the pitches of the thread were for the most part established between 1820 and 1840.

By publishing his data, based on years of practice, Mr. Briggs was the means of establishing definite detail dimensions. The Briggs formula did not provide for the internal threads or gaging requirements for making taper threaded joints. It established only the external thread on pipe, with no tolerance.

Copyright 2004, Industrial Press, Inc., New York, NY

In 1886 the large majority of American manufacturers threaded pipe to practically the Briggs Standard, and acting jointly with The American Society of Mechanical Engineers they adopted it as a standard practice that year, and master plug and ring gages were made.

Later at various conferences representatives of the manufacturers and the ASME established additional sizes, certain details of gaging, tolerances, special applications of the standard, and in addition tabulated the formulas and dimensions more completely than was done by Mr. Briggs.

Until the manufacturers adopted the Briggs thread in 1886, it seems that each manufacturer of necessity threaded his pipe and fittings according to his best judgment. After 1886 there was some attempt to work toward better interchangeability. However, the need for a better gaging practice resulted in the adoption of the thin ring gage and the truncation of the plug and ring gages to gage the flanks of the thread. This practice of threading fittings and couplings which provides threads to make up joints with a wrench was standardized about 1913.

In 1913 a Committee on the Standardization of Pipe Threads was organized for the purpose of re-editing and expanding the Briggs Standard. The American Gas Association and The American Society of Mechanical Engineers served as joint sponsors. After six years of work, this committee completed the revised standard for taper pipe thread which was published in the ASME "*Transactions*" of 1919, and was approved as an American Standard by the American Engineering Standards Committee, later named the American Standards Association in December 1919. It was the first standard to receive this designation under the ASA procedure, and was later published in pamphlet form.

In the years which followed, the need for a further revision of this American Standard became evident as well as the necessity of adding to it the recent developments in pipe threading practice. Accordingly, the Sectional Committee on the Standardization of Pipe Threads, B2, was organized in 1927 under the joint sponsorship of the A.G.A. and the ASME.

During the following 15 years, several meetings were held leading to approval by the members of the Sectional Committee, of the April 1941 draft. The revision was approved by the sponsors and ASA and published as an American Standard in October, 1942.

Shortly after publication of the 1942 standard, the Committee undertook preparation of a complete revision. The text and tables were rearranged and expanded to include Dryseal pipe threads, and an extensive appendix was added to provide additional data on the application of pipe threads and to record in abbreviated form the several special methods which were established for gaging some of the various applications of pipe threads.

The resulting proposal was approved by letter ballot of the Sectional Committee. Following its acceptance by the sponsor bodies, the draft was submitted to the American Standards Association and designated an American Standard on December 11, 1945.

At a subsequent meeting of the Sectional Committee it was agreed that for the convenience of users, the standards covering Dryseal pipe threads should be published under separate cover. Consequently, the section included in ASA B2.1-1945 on Dryseal pipe threads was deleted from the 1960 revision to that standard and used as a basis for the development of a separate proposal for Dryseal pipe threads. The text and tables were expanded to completely document the various series threads and gages, and appendices covering formulas, drilled hole sizes and special series threads were added. The E_1 internal diameter and the L_1 hand type engagements for the ⅛ and ¼ inch sizes were revised to correct for a disproportionate number of threads for hand tight engagement. This proposal was approved by letter ballot vote of the Sectional Committee and submitted to the A.G.A. and the ASME. Following approval by the sponsor organizations, it was approved by the American Standards Association on April 29, 1960, and designated as ASA B2.1-1960, Pipe Threads (Except Dryseal).

Copyright 2004, Industrial Press, Inc., New York, NY

The present revision of this standard constitutes a general updating. In line with their current policy, the A.G.A. has withdrawn sponsorship of this standard, while remaining active in the work of the standards committee. In compliance with the rules of the United States of America Standards Institute (formerly ASA) the previously designated Sectional Committees are now called Standards Committees.

Following approval by the Standards Committee B2 and the sponsor, ASME, the revision was approved by the United States of America Standards Institute on November 29, 1968.

Lock-Nut Pipe Thread.— The lock-nut pipe thread is a straight thread of the largest diameter which can be cut on a pipe. Its form is identical with that of the American or Briggs standard taper pipe thread. In general, "Go" gages only are required. These consist of a straight-threaded plug representing the minimum female lock-nut thread, and a straight-threaded ring representing the maximum male lock-nut thread. This thread is used only to hold parts together, or to retain a collar on the pipe. It is never used where a tight threaded joint is required.

Thread Grinding.— Thread grinding is applied both in the manufacture of duplicate parts and also in connection with precision thread work in the tool-room.

Single-edged Grinding Wheel: In grinding a thread, the general practice in the United States is to use a large grinding wheel (for external threads) having a diameter of possibly 18 to 20 inches. The width may be 5/16 or $\frac{3}{8}$ inch. The face or edge of this comparatively narrow wheel is accurately formed to the cross-sectional shape of the thread to be ground. The thread is ground to the correct shape and lead by traversing it relative to the grinding wheel. This traversing movement, which is equivalent to the lead of the screw thread for each of its revolutions, is obtained from a lead-screw. On one type of thread grinder, this lead-screw is attached directly to the work-spindle and has the same lead as the screw thread to be ground; hence, there is a separate lead-screw for each different lead of thread to be ground. On another design of machine, the lead-screw arrangement is similar to that on a lathe in that the required lead on the ground thread is obtained by selection of the proper change gears. The grinding wheel may have a surface speed of 7000 feet a minute, whereas the work speed may range from 3 to 10 feet per minute. The grinding wheel is inclined to suit the helix angle of the thread and either right- or left-hand threads may be ground. Provision is also made for grinding multiple threads and for relieving taps and hobs. The wheel shape is accurately maintained by means of diamond truing tools. On one type of machine, this truing is done automatically and the grinding wheel is also adjusted automatically to compensate for whatever slight reduction in wheel size may result from the truing operation.

An internal thread may also be ground with a single-edged wheel. The operation is the same in principle as external thread grinding. The single-edged wheel is used whenever the highest precision is required, grinding the work either from the solid or as a finishing operation.

Grinding "from the Solid": On some classes of work, the entire thread is formed by grinding "from the solid," especially if the time required is less than would be needed for a rough thread-cutting operation followed by finish-grinding after hardening. Grinding threads from the solid is applied to the finer pitches. In some plants, threads with pitches up to about 1/16 inch are always ground by this method.

Multi-edged Grinding Wheel: An entire screw thread, if not too long, may be ground completely in one revolution by using a multi-edged type of grinding wheel. The face of this wheel is formed of a series of annular thread-shaped ridges so that it is practically a number of wheels combined in one. The principle is the same as that of milling screw threads by the multiple-cutter method. If the length of the thread to be ground is less than the width of the wheel, it is possible to complete the grinding in practically one work revolution as in thread milling. A grinding wheel having a width of, say, $2\frac{1}{2}$ inches, is provided

Copyright 2004, Industrial Press, Inc., New York, NY

with annual ridges or threads across its entire width. The wheel is fed in to the thread depth, and, while the work makes one single revolution, the wheel moves axially a distance equal to the thread lead along the face of the work. Most threads which require grinding are not longer than the width of the wheel; hence, the thread is completed by one turn of the work.

If the thread is longer than the wheel width, one method is to grind part of the thread and then shift the wheel axially one or more times for grinding the remaining part. For example, with a wheel 2½ inches in width, a thread approximately 12 inches long might be ground in five successive steps. A second method is that of using a multi-edged tapering wheel which is fed axially along the work. The taper is to distribute the work of grinding over the different edges or ridges as the wheel feeds along.

Hand Chaser.— A hand chaser is a type of threading tool used either for cutting or chasing external or internal threads. The tool is supported upon a rest and is guided by the hand; it is used mainly on brass work, for slightly reducing the size of a thread that has been cut either by a die or threading tool. A hand chaser may also be used for truing up battered threads in repair work and for similar purposes.

Thread-Cutting Methods.— The two general methods of forming screw threads may be defined as the cutting method and the rolling or displacement method. The cutting methods as applied to external threads are briefly as follows:

1) By taking a number of successive cuts with a single-point tool that is traversed along the part to be threaded at a rate per revolution of the work depending upon the lead of the thread. (Common method of cutting screw threads in the engine lathe.)

2) By taking successive cuts with a multiple-point tool or chaser of the type used to some extent in conjunction with the engine lathe and on lathes of the Fox or monitor types.

3) By using a tool of the die class, which usually has four or more multiple-point cutting edges or chasers and generally finishes the thread in one cut or passage of the tool.

4) By a single rotating milling cutter, which forms the thread groove as either the cutter or the work is traversed axially at a rate depending upon the thread lead.

5) By a multiple rotating milling cutter which completes a thread in approximately one revolution of the work.

6) By a multiple rotating cutter which also has a planetary rotating movement about the work which is held stationary. See Planamilling and Planathreading.

7) By a grinding wheel having its edge shaped to conform to the groove of the screw thread.

8) By a multi-edged grinding wheel which, within certain limits as to thread length, will grind the complete thread in practically one revolution of the work.

Internal screw threads, or those in holes, may or may not be produced by the same general method that is applied to external work. There are three commercial methods of importance, namely:

1) By the use of a single-point traversing tool in the engine lathe or a multiple-point chaser in some cases.

2) By means of a tap which, in machine tapping, usually finishes the thread in one cut or passage of the tool.

3) By a rotating milling cutter of either the single or the multiple type.

Dies operated by hand are frequently used for small and medium-sized parts, especially when accuracy as to the lead of the thread and its relation to the screw axis is not essential and comparatively few parts need to be threaded at a time. When a large number of pieces must be threaded, power-driven machines equipped with dies are commonly employed. If the operation is simply that of threading the ends of bolts, studs, rods, etc., a "bolt cutter" would generally be used, but if cutting the thread were only one of several other operations necessary to complete the work, the thread would probably be cut in the same machine performing the additional operations. For instance, parts are threaded in turret lathes and automatic screw machines by means of dies and in conjunction with other operations. When

Copyright 2004, Industrial Press, Inc., New York, NY

screws are required which must be accurate as to the pitch or lead of the thread, and be true relative to the axis of the work, a lathe is generally used; lathes are also employed, ordinarily, when the threaded part is comparatively long and large in diameter. Many threads which formerly were cut in the lathe are now produced by the milling process in special thread-milling machines. The method often depends upon the equipment at hand and the number of parts to be threaded. Very precise threads may be produced by grinding.

Taps.— A tap is an internal thread-cutting tool having teeth which conform to the shape of the thread. Taps may be classified according to the kind of thread with which they are provided, as U. S. Standard thread taps, square thread taps, and Acme thread taps, etc. The most important classification of taps, however, is according to their use.

Hand taps: as the name implies, are intended primarily for tapping holes by hand but are often used in machines. All taps used by hand are not termed "hand" taps as there are many special taps used by hand which are known by specific names.

Tapper taps: are used for tapping nuts in tapping machines. They are provided with a long chamfered part on the end of the threaded portion, and a long shank.

Machine nut taps: are also used for tapping nuts in tapping machines. This type is designed for more severe duty than the tapper tap and is especially adapted for tapping holes in materials of tough structure. Machine nut taps are chamfered and relieved in a different, manner from tapper taps.

Machine screw taps: may be either hand taps or machine nut taps, but are known by the name "machine screw tap," because they constitute a class of special taps used for tapping holes for standard machine screw sizes.

Screw machine taps: for tapping in the screw machine are provided with shanks fitting either the turret holes of the machine or bushings inserted in these holes. As these taps ordinarily cut threads down to the bottom of the hole, they are provided with a very short chamfer.

Pulley taps: are simply a special type of taps used for tapping holes which cannot be reached by ordinary hand taps, as, for instance, the set-screw or oil-cup holes in the hubs of pulleys. They are simply hand taps with a very long shank.

Die taps: also known as long taper die taps, are used for cutting the thread in a die in a single operation from the blank, and are intended to be followed by a sizing hob tap. Die taps are similar to machine nut taps.

Hob taps: are used for sizing dies. They are intended only for the final finishing of the thread and can only take a slight chip. They are made to the same dimensions as regular hand taps, but fluted differently.

Pipe taps: are used for tapping holes for standard pipe sizes. These tans are taper taps. There is also a special form of pipe tap termed *straight* pipe tap, which is simply a hand corresponding in diameter and number of threads per inch to standard pipe sizes.

Pipe hobs: are similar to pipe taps, but are intended only for sizing pipe dies after the thread has been cut either by a pipe tap or in a lathe.

Boiler taps: are used in steam boiler work where a steam-tight fit is required. They are made either straight or tapered. The straight boiler tap is practically only a hand tap.

Mud or washout taps: are used in boiler or locomotive work. They are sometimes also called arch pipe taps. Patch bolt taps are used in boiler and locomotive work. These are taper taps similar to mud or washout taps.

Staybolt taps: are used on locomotive boiler work. They are usually provided with a reamer portion preceding the threaded part, and have generally a long threaded portion and a long shank. A special form of staybolt tap is known as a spindle staybolt tap which revolves on a central spindle with a taper guide on the front end.

Stove-bolt taps and *carriage-bolt taps* are taps which have derived their names from the uses to which they were originally put. These taps have special forms of threads.

Bit-brace taps differ in no essential from the hand tap on the threaded portion, but are provided with a special shank for use in a bit brace.

Copyright 2004, Industrial Press, Inc., New York, NY

Blacksmiths' taper taps are made for general rough threading and are used especially in repair work, where an accurately fitting thread is not required.

Inserted cutter taps may belong to any of the classes mentioned and constitute a separate type only because they are not solid, but have the cutting teeth on blades inserted and held rigidly in a tap body.

Machine Elements

Nordberg Key.— This is a taper key of circular cross-section. This type of key may be used for attaching hand wheels to their shafts or for other similar light work requiring an inexpensive type of key. The Nordberg key has a taper of 1/16 inch per foot. The center of the key hole is located at the joint line between the shaft and hub. A small hole may be drilled first to prevent the larger drill from crowding over into the cast-iron hub. A general rule for determining the size of the key is to make the large key diameter equal to one-fourth the shaft diameter.

Woodruff Keys.— In the Woodruff key system, half-circular disks of steel are used as keys, the half-circular side of the key being inserted into the keyseat. Part of the key projects and enters into a keyway in the part to be keyed to the shaft in the ordinary way. The advantage of this method of keys is that the keyway is easily milled by simply sinking a milling cutter, of the same diameter as the diameter of the stock from which the keys are made, into the shaft. The keys are also very cheaply made, as they are simply cut off from round bar stock and milled apart in the center. Dimensions of Woodruff keys are given in engineering handbooks.

Saddle Key.— This form of key has parallel sides and is curved on its under side to fit the shaft. it is slightly tapered on top so that, when it is driven tightly in place, the shaft is held by frictional resistance. This key should be fitted so that it bears lightly on the sides and heavily between the shaft and hub throughout its entire length. As the drive with this type of key is not positive, it is only used where there is little power to transmit. It is an inexpensive method of keying, as the shaft does not need to be machined.

Locomotive Development.— The first steam locomotive which ever ran on rails was built in 1804 by Richard Trevithick, an Englishman, and the first one to be used on a commercial basis was built by Matthew Murray, another Englishman. In 1811, Blenkinsop of Leeds, had several locomotives built by Murray in order to operate a railway extending from Middletown Colliers to Leeds, a distance of three and one-half miles. Trevithick's impracticable design had a single cylinder only, but Murray used two cylinders which were utilized in driving the same shaft on which cranks were set at right angles an important arrangement common to all modern locomotives. A cog-wheel, or gear, meshing with a continuous rack laid along the road-bed was employed. These locomotives were used daily for years and were examined by George Stephenson when he began his work on locomotive development. Several years after the construction of Murray's locomotives Hedley and Stephenson demonstrated that the gear and rack method of propulsion was unnecessary, and that the frictional resistance of smooth drivers would supply adequate tractive power. Stephenson's name will always be associated with locomotive development owing to his accomplishments in perfecting the locomotive and in establishing it on a commercial basis. His first locomotive was tried on the Killing worth Railway in 1814. The first locomotive to be used in the United States was imported from England in 1829.

Percentages of Radial and Thrust Loads.— There are three types of bearing that are combined load carriers: First, the annular ball bearing, which is primarily designed for radial loads and has no angle of contact incorporated in its design, therefore having minimum thrust capacity (approximately 20 per cent of its radial capacity). Second, the one-direction angular contact bearing, which has a thrust capacity depending upon race design and the angle incorporated, which is generally made so that the thrust capacity is 100 per cent of the radial capacity. (This bearing, however, when used for combined loads, can

Copyright 2004, Industrial Press, Inc., New York, NY

only be used in pairs, and must have a threaded or shim adjustment incorporated in the mounting design to allow for initial adjustment.) Third, the double angular type bearing which is really two of the previously mentioned bearings built as a self-contained unit. The functioning of this bearing is not dependent on any exterior adjustment, and the angle of contact is generally such that it will sustain approximately 150 per cent of its radial capacity as thrust.

Roller Bearing.— The load on roller bearings is supported by cylindrical or conical rollers interposed between two races, one race being mounted on the shaft and one other in the bearing proper. There are three principal designs of roller bearings. One is for straight radial loads, the lines of contact of the rollers with the races being parallel with the shaft axis, as shown by the left-hand diagram; another design is for combined radial and thrust loads (See Fig. 3b.). With this design, the rollers are tapering so that the lines of contact of the rollers with the races, and the axis of the rollers, will intersect, if extended, at the same point on the shaft axis. A third design is intended for thrust or axial loads exclusively. Bearings for radial loads may have solid rollers, or the hollow helically-wound type such as is used in the Hyatt bearing. Although anti-friction bearings have replaced a great many plain or sliding bearings, the trend is toward a much wider application, and evidently will include eventually the heaviest classes of service since modern anti-friction bearings not only greatly reduce friction losses, but lower maintenance and repair costs.



Fig. 3a. Bearing for Radial Load



Fig. 3b. Bearing for Radial and Thrust Loads

Ball Bearing Lubrication.— To obtain the full measure of efficiency and service from ball and roller bearing equipment, the kind and quality of the lubricant, as well as the system of applying it, must be adapted to the design of the bearing, the design of the machine, and the operating conditions.

Operating Temperatures: Under ordinary conditions the temperature of a bearing while running will be from 10 to 60 degrees F. above that of the room. If it exceeds 125 degrees F., ordinary greases will frequently prove unsatisfactory. They will tend to soften and flow continuously into the path of the rolling elements, causing a rise in the normal operating temperature due to the increased frictional resistance introduced. This may eventually result in the separation of the oil and soap base, with a complete loss of lubricating qualities. In some cases, greases developed for use at high temperatures may be employed. Care should be taken, however, to see that they meet all the requirements for adequate lubrication.

Mineral oil of proper physical and chemical properties is an ideal lubricant for ball and roller bearings when the housing is designed to control the quantity entering the bearing and to prevent leakage and protect the bearing from the entrance of foreign matter. A ball or roller bearing should not be subjected to temperature in excess of 300 degrees F., because of the danger of drawing the temper of the hardened steel races and balls.

Quantity of Lubricant Required: In no case does a ball or roller bearing require a large quantity of lubricant. On the contrary, a few drops of oil, or a corresponding amount of grease, properly distributed over the running surfaces of the bearing, will provide satisfactory lubrication for a considerable period of time. A large volume of lubricant within a

Copyright 2004, Industrial Press, Inc., New York, NY

bearing will usually result in high operating temperatures, due to the working or churning of the lubricant by the rolling elements and retainer. This may seriously impair the useful life of the lubricant through oxidation or sludging of the oil or actual disintegration of greases.

Use of Grease: If grease is used, the housing should not be kept more than one-fourth to one-half full of the lubricant. Unlike oil, there is no way of controlling with any degree of exactness the quantity of grease in a housing, and greater care must therefore be taken to avoid overloading. A bearing that runs at too high a temperature will often return to normal temperature if some of the lubricating grease is removed.

Grease is being used successfully for the lubrication of ball bearings at high speeds, but great care is necessary, both from the standpoint of housing design and selection of the lubricant, in order to obtain satisfactory results. Any system employed must be designed to feed only a limited amount of grease to the bearing. For the average application at operating speeds up to 3600 revolutions per minute, a grease of soft consistency, such as a No. 2 grease, will usually be found satisfactory, provided it is suitable in other respects. Hard greases, such as No. 3, may be used if the grease is to serve as a packing medium around the shaft to prevent the entrance of dirt, water, or other corrosive substances.

Sealed Bearings: : Bearings for certain classes of service must operate over long periods without relubrication, as, for example, a motor installation on an airplane beacon; hence the efforts of ball-bearing manufacturers to produce bearings so completely sealed as to enable them to retain their original charge of grease for many months. In appreciation of this requirement, the petroleum industry has developed lubricants that will maintain lubrication for a long period without change in structure, homogeneity, lubricating properties, or leakage.

Engine Governors.— Governors may be of a purely centrifugal type such as the fly-ball or pendulum design previously referred to, or the principle of inertia may be introduced to secure better speed regulation. Thus, there are two general classes of governors known as centrifugal and inertia governors. The method of utilizing the motion of the governing element for regulating the speed varies; as applied to steam engines, there is the general type of governor which controls the speed by operating a throttling valve which increases or diminishes the amount of steam admitted to the steam-chest, and another general type which regulates the speed by changing the point of cut-off and consequently the amount of expansion in the cylinders.

In the design of governors, the sensitiveness, effort, and stability of the governor are important factors. The sensitiveness of a fly-ball governor is indicated by the amount that the governing sleeve is displaced for a given change in speed, the displacement being relatively large for a given speed change if the governor is sensitive.

The term “effort” as applied to a governor relates to the energy it is capable of exerting upon the governing mechanism. Thus, in the case of a fly-ball governor, the effort indicates the energy exerted on the sleeve while the governor speed is increasing or diminishing. If the energy stored in a revolving governor is small, its sensitiveness will be reduced, because a larger speed change is necessary to obtain the power for operating the governing mechanism than would be required with a governor which exerts greater energy for a given speed change.

When a governor occupies a definite position of equilibrium for any speed within the range of speeds controlled by the governor, it is said to be “stable.” If the load on an engine having a fly-ball governor is diminished, the balls of a stable governor will move outward to a new position as the speed increases, although there will usually be a temporary oscillating movement on each side of this new position, the oscillations gradually diminishing. If the governor were instable (and therefore useless) the oscillations would increase until the limiting points were reached.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1.



Fig. 2.

Loaded or Weighted Fly-ball Governors.— As the arms of a governor of the conical pendulum type swing outward toward the horizontal position as the result of increasing speed, the change in height h (see Fig. 1) is small for given changes in speed. For instance, if the speed is changed from 50 to 70 revolutions per minute, the difference between the values of h is nearly 7 inches, whereas if the speed changes from 200 to 300 revolutions per minute, the difference in height h for the two speeds is only about ½ inch. Hence, the simple pendulum governor is not suitable for the higher speeds, because then the movement which accompanies the speed changes is too small to secure proper regulation through the governing mechanism. Fly-ball governors are adapted for much higher speeds by loading them. The load may be in the form of a weight which surrounds the spindle, as illustrated by Fig. 1. This is known as a Porter governor.

In the following formula, w = the weight of one governor ball in pounds; c = the weight of the additional load; h = the height in feet indicated by the diagram, Fig. 1; n = speed of governor in revolutions per minute:

$$h = \frac{2933}{n^2} \times \frac{e + w}{w}$$

If the governor is constructed as indicated by the diagram Fig. 2, the height h is not measured from the points at which the arms or rods are suspended, but from the point where the axes of the rods intersect with the vertical center line. The outward movement of the balls may be resisted by a spring instead of a weight, as in the case of the Hartnell governor, which is known as a spring-loaded type.

Sensitiveness and Stability of Governors.— The sensitiveness of one governor may be compared with that of another by determining the *coefficient of speed variations*. If C = the coefficient of speed variations, M = maximum speed within limits of the governor action; M_1 = minimum speed within limits of governor action; m = mean speed within these limits; then,

$$C = \frac{M - M_1}{m}$$

The minimum value of coefficient C necessary to obtain stability in a pendulum type of governor is given by the following formula in which y = distance the fly-balls move horizontally in feet; F = mean centrifugal force of fly-balls in pounds; H = indicated horsepower of engine; W = the weight of engine flywheel in pounds; S = revolutions per minute of main shaft; R = the flywheel radius in feet.

Copyright 2004, Industrial Press, Inc., New York, NY

$$C = 4000\sqrt[3]{\frac{xy}{F}} \times \sqrt[8]{\frac{H^2}{S^4R^4W^2}}$$

The factor x in this formula represents that weight which would be equivalent to the weights of the various moving parts, if it were centered at a point corresponding to the center of gravity of the fly-balls. To determine the value of x, first determine the weights of the different moving parts of the governor, such as the balls, the central weight or load (in the case of a Porter governor), the sleeve, etc.; multiply the weight of each part by the square of the distance it moves from one position to the other; add the various products thus obtained, and divide the total sum by the square of the corresponding movement of the fly-balls at right angles to the governor spindle.

Shaft Governors.— Shaft governors are so named because the governing mechanism is carried by the main shaft and is commonly attached in some way to the flywheel. One type is so arranged that, in the case of a steam engine, the action of centrifugal force on a pivoted and weighted lever, to which a spring is attached, changes the position of the eccentric which operates the slide valve, thus increasing or decreasing the valve travel and changing the point of cut-off. Another type is so designed that the inertia of a pivoted "weight arm" accelerates the governing action by acting in conjunction with the effect of centrifugal force, thus increasing the sensitiveness of the governor. With the inertia governor, the effort or force needed to actuate the governing mechanism increases as the rate of velocity change increases; hence this type is adapted to engines liable to sudden load changes. When the load remains practically constant, the centrifugal type of shaft governor is often employed in preference to the inertia type. The design of these governors depends upon the arrangement of the governing mechanism and upon varying factors.

Rope Splicing.— Splicing is the operation when two pieces of rope are joined by unlaying the strands and weaving or intertwining the strands of one end with those of the other.

Short Splice: The first step in making a short splice is to unlay or untwist the strands at the end of each rope. After the ropes are placed together, as shown at *A*, Fig. 1a, the strands on one side, as shown at *d*, *e*, and *f*, are either held together by the left hand or are fastened together with twine, in case the rope is too large to be held by the hand. The splicing operation is started by taking one of the strands as at *a*, and passing it across or over the adjacent strand *d* and then under the next strand *e*, after having made an opening beneath strand e. The strands *b* and *c* are next treated in the same manner, first one and then the other being passed over its adjoining strand and then under the next successive one. These same operations are then repeated for the strands *d*, *e* and *f* of the other rope. The splice will now appear as shown at *B*, Fig. 1b. In order to make it stronger and more secure, the projecting strands of each rope are again passed diagonally over the adjoining strands and under the next successive ones. The splice should then be subjected to a strong pull, in order to tighten the strands and make them more compact. The projecting ends of the strands should then be cut off, thus completing the splice as shown at *C*. For making the openings beneath the strands on the rope, what is known as a marlin spike is generally used. This is merely a tapering, pointed pin made of wood or iron.



Fig. 1a. Method of Making a Short Splice

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1b. Method of Making a Short Splice

Fig. 1c. Method of Making a Short Splice

Long Splice: When a rope has to pass through pulley blocks, or in case any increase in the size of the rope would be objectionable, the short splice is not suitable and the long splice should be employed. The diameter of a long splice is the same as that of the rope and, if the work is done carefully, the place where the ends are joined can scarcely be distinguished from the rest of the rope. The ends of each rope are first unlaid or untwisted the same as when making a short splice, but for a distance about three times as long. These ends are then placed together so that each strand lies between two strands of the other rope, the same as for a short splice. One of the strands is next unlaid and then a strand from the other rope is curled around into the groove thus made, as indicated at *A* Fig. 2a, strand a having been unlaid and strand *b* from the other rope end, put into its place. Care should be taken to twist strand *b* so that it will lie in its natural position into the groove previously occupied by strand *a*, as the neatness of the splice will depend partly upon the care with which this part of the work is done. This operation is then repeated in connection with strands *c* and *d*, strand *c* being unlaid and strand *d* twisted around to occupy the groove thus made. The splice will now be as shown at *B*, Fig. 2b, and the next step is that of disposing of the protruding ends of the strands. After these strands have been cut to about the length shown at *B*, two of the strands, as at *a* and *b*, are first reduced in size by removing about one-third of the fiber; these ends are then tied by an overhand knot as shown at e. After tightening this knot, the protruding ends may be disposed of the same as when making a short splice, or by passing them over the adjoining strand and through the rope, under the next one. By gradually removing the fiber each time the end is passed across an adjoining strand, the enlargement of the rope at this point may be made very slight and scarcely noticeable. The strands *f* and *g* which remain in their original positions in the center of the splice, and the strands *c* and *d* are disposed of in a similar manner, thus completing the splice as shown at Fig. 2c.



Fig. 2a. How a Long Splice is Made



Fig. 2b. How a Long Splice is Made

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2c. How a Long Splice is Made

Eye-Splice: When a loop is formed at the end of a rope by splicing the free end to the main or standing part of the rope, this is known as an *eye-splice*. The end of the rope is first unlaid about as far as it would be for making a short splice. After bending the end around to form a loop of the required size, the middle strand a, Fig. 3a, is tucked under a strand on the main part of the rope. The strand *b* is next inserted from the rear side under the strand on the main part which is just above the strand under which a was inserted. Since strand *b* is pushed under the strand on the main part from the rear side, it will come out at the point where strand *a* went in, as Fig. 3b. The third strand *c* is now passed over the strand under which strand a was inserted, and then under the next successive one, as Fig. 3c. These three strands are next pulled taut and then about one-third of the fiber should be cut from them; they are next tucked away by passing a strand over its adjoining one and under the next successive strand. Cutting away part of the fiber or yarns is to reduce the size of the splice and give it a neater appearance. By gradually thinning out the fiber, the over-lapping strands may be given a gradual taper, as Fig. 3d which shows the completed eye-splice.



Fig. 3a. Eye -Splice

Fig. 3b. Eye -Splice

Fig. 3c. Eye -Splice

Fig. 3d. Eye -Splice

Copyright 2004, Industrial Press, Inc., New York, NY

Guide to the Use of Tables and Formulas in Machinery's Handbook 27th Edition

BY JOHN M. AMISS, FRANKLIN D. JONES, AND HENRY H. RYFFEL

CHRISTOPHER J. MCCAULEY, EDITOR
RICCARDO HEALD, ASSOCIATE EDITOR
MUHAMMED IQBAL HUSSAIN, ASSOCIATE EDITOR

2004
INDUSTRIAL PRESS INC.
NEW YORK

Copyright 2004, Industrial Press, Inc., New York, NY

COPYRIGHT 1931, 1939, 1951, 1954, © 1959, © 1964, © 1968, © 1971,© 1975, © 1980, © 1984, © 1988, © 1992, © 1996, © 2000, © 2004 by Industrial Press Inc., New York, NY.

Library of Congress Cataloging-in-Publication Data

Amiss, John Milton, 1887-1968

Guide to the use of tables and formulas in Machinery's Handbook, 27th edition by John M. Amiss, Franklin D. Jones, and Henry H. Ryffel; Christopher J. McCauley, editor; Riccardo Heald, associate editor; Muhammed Iqbal Hussain, associate editor.

264 p. 12.1 × 17.8 cm.

Cover title: Machinery's handbook 27th guide.

Cover title: Machinery's handbook twenty seventh guide.

This book should be used in conjunction with the twenty-seventh edition of Machinery's Handbook.

ISBN 0-8311-2799-6

ISBN 0-8311-2788-0 (electronic edition with math)

1. Mechanical engineering—Handbook, manuals, etc. I. Title: Machinery's handbook 27 guide. II. Machinery's handbook twenty seventh guide. III Jones, Franklin Day, 1879-1967 IV. Ryffel, Henry H. I920- V. McCauley, Christopher J. VI. Heald, Riccardo VII. Hussain, Muhammed Iqbal VIII. Machinery's Handbook. 27th edition. IX. Title.

TJ151.A445 2000

621.8'0212–dc 21 00-038881

INDUSTRIAL PRESS, INC.
200 Madison Avenue
New York, New York 10016-4078

MACHINERY'S HANDBOOK GUIDE
27th Edition
First Printing

Printed and bound in the United States of America by
National Publishing Company, Philadelphia, Pa.

All rights reserved. This book or parts thereof may not be reproduced, stored in a retrieval system, or transmitted in any form without permission of the publishers.

Copyright 2004, Industrial Press, Inc., New York, NY

THE PURPOSE OF THIS BOOK

An engineering handbook is an essential part of the equipment of practically all engineers, machine designers, draftsmen, tool engineers and skilled mechanics in machine shops and toolrooms. The daily use of such a book, with its various tables and general data, saves a lot of time and labor. To obtain the full value of any handbook, however, the user must know enough about the contents to apply the tables, formulas, and other data, whenever they can be used to advantage.

One purpose of this Guide, which is based on MACHINERY'S HANDBOOK, is to show by examples, solutions, and test questions typical applications of handbook information in both drafting rooms and machine shops. Another function is to familiarize engineering students or other users with the HANDBOOK'S contents. A third objective is to provide test questions and drill work that will enable the HANDBOOK user, through practice, to obtain the required information quickly and easily.

MACHINERY'S HANDBOOK, as with all other handbooks, presents information in condensed form so that a large variety of subjects can be covered in a single volume. Because of this condensed treatment, any engineering handbook must be primarily a work of reference rather than a textbook, and the practical application of some parts will not always be apparent, especially to those who have had little experience in engineering work. The questions and examples in this book are intended not only to supplement some of the HANDBOOK material, but also to stimulate interest both in those parts that are used frequently and in the more special sections that may be very valuable even though seldom required.

Copyright 2004, Industrial Press, Inc., New York, NY

THE METRIC SYSTEM

MACHINERY'S HANDBOOK contains a considerable amount of metric material in terms of texts, tables, and formulas. This material is included because much of the world now uses the metric system, also known as the Système International (SI), and the movement in that direction continues in all countries that intend to compete in the international marketplace, including the United States.

An explanation of the SI metric system is found on Handbook **pages 142** to **144** and **2544** to **2548**. A brief history is given of the development of this system, and a description is provided for each of its seven basic units. Factors and prefixes for forming decimal multiples and submultiples of the SI units also are shown. Another table lists SI units with complex names and provides symbols for them.

Tables of SI units and conversion factors appear on **pages 2549** through **2587**. Factors are provided for converting English units to metric units, or vice versa, and cover units of length, area, volume (including capacity), velocity, acceleration, flow, mass, density, force, force per unit length, bending moment or torque, moment of inertia, section modulus, momentum, pressure, stress, energy, work, power, and viscosity. By using the factors in these tables, it is a simple matter of multiplication to convert from one system of units to the other. Where the conversion factors are exact, they are given to only 3 or 4 significant figures, but where they are not exact they are given to 7 significant figures to permit the maximum degree of accuracy to be obtained that is ordinarily required in the metalworking field.

To avoid the need to use some of the conversion factors, various conversion tables are given on **pages 2550** through **2579**. The tables for length conversion on **pages 2550** to **2562** will probably be the most frequently used. Two different types of tables are shown. The two tables on **page 2553** facilitate converting lengths

Copyright 2004, Industrial Press, Inc., New York, NY

up to 100 inches into millimeters, in steps of one ten-thousandth of an inch; and up to 1000 millimeters to inches, in steps of a thousandth of a millimeter.

The table starting on **page 2554** enables converting fractions and mixed number lengths up to 41 inches into millimeters, in steps of one sixty-fourth of an inch.

To make possible such a wide range in a compact table, the reader often must take two or more numbers from the table and add them together, as is explained in the accompanying text. The tables starting on **page 2556** and **2558** have a much more limited range of conversion for inches to millimeters and millimeters to inches. However, these table have the advantage of being direct-reading; that is, only a single value is taken from the table, and no addition is required.

For those who are engaged in design work where it is necessary to do computations in the fields of mechanics and strength of materials, a considerable amount of guidance will be found for the use of metric units. Thus, beginning on Handbook **page 141**, the use of the metric SI system in mechanics calculations is explained in detail. In succeeding pages, boldface type is used to highlight references to metric units in the combined Mechanics and Strength of Materials section. Metric formulas are provided also, to parallel the formulas for English units.

As another example, on **page 213**, it is explained in boldface type that SI metric units can be applied in the calculations in place of the English units of measurement without changes to the formulas for simple stresses.

The reader also should be aware that certain tables in the Handbook, such as that on **page 71**, which gives values for segments of circles for a radius = 1, can be used for either English or metric units, as is indicated directly under the table heading. There are other instances, however, where separate tables are needed, such as are shown on **pages 1018** to **1021** for the conversion of revolutions per minute, into cutting speed in feet per minute on **pages 1018** and **1019**, and into cutting speed in meters per minute on **pages 1020** and **1021**.

Copyright 2004, Industrial Press, Inc., New York, NY

The metric material in the Handbook will provide considerable useful data and assistance to engineers and technicians who are required to use metric units of measurements. It is strongly suggested that all readers, whether or not they are using metric units at the present time, become familiar with the SI System by reading the explanatory material in the Handbook and by studying the SI units and the ways of converting English units to them.

Copyright 2004, Industrial Press, Inc., New York, NY

Machinery's Handbook Guide 27th Edition

CONTENTS

SECTION		PAGE
	The Purpose Of This Book	**vii**
	The Metric System	**viii**
1	**Dimensions And Areas Of Circles**	**1**
2	**Chordal Dimensions, Segments, And Spheres**	**4**
3	**Formulas And Their Rearrangement**	**8**
4	**Spreadsheet Calculations**	**22**
5	**Calculations Involving Logarithms Of Numbers**	**32**
6	**Dimensions, Areas, And Volumes Of Geometrical Figures**	**42**
7	**Geometrical Propositions And Constructions**	**46**
8	**Functions Of Angles**	**50**
9	**Solution Of Right-angle Triangles**	**58**
10	**Solution of Oblique Triangles**	**78**
11	**Figuring Tapers**	**88**
12	**Tolerances And Allowances For Machine Parts**	**94**
13	**Using Standards Data And Information**	**108**
14	**Standard Screw And Pipe Threads**	**113**
15	**Problems In Mechanics**	**122**
16	**Strength Of Materials**	**138**
17	**Design Of Shafts And Keys For Power Transmission**	**150**
18	**Splines**	**159**
19	**Problems In Designing And Cutting Gears**	**169**
20	**Cutting Speeds, Feeds, And Machining Power**	**196**
21	**Numerical Control**	**205**
22	**General Review Questions**	**212**
23	**Answers To Practice Exercises**	**221**
	INDEX	**254**

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 1

DIMENSIONS AND AREAS OF CIRCLES

HANDBOOK Pages **66** and **76**

Circumferences of circles are used in calculating speeds of rotating machine parts, including drills, reamers, milling cutters, grinding wheels, gears, and pulleys. These speeds are variously referred to as surface speed, circumferential speed, and peripheral speed; meaning for each, the distance that a point on the surface or circumference would travel in one minute. This distance usually is expressed as feet per minute. Circumferences are also required in calculating the circular pitch of gears, laying out involute curves, finding the lengths of arcs, and in solving many geometrical problems. Letters from the Greek alphabet frequently are used to designate angles, and the Greek letter π (pi) always is used to indicate the ratio between the circumference and the diameter of a circle:

$$\pi = 3.14159265\ldots = \frac{\text{circumference of circle}}{\text{diameter of circle}}$$

For most practical purposes the value of $\pi = 3.1416$ may be used.

Example 1: Find the circumference and area of a circle whose diameter is 8 inches.

On Handbook **page 66**, the circumference C of a circle is given as $3.1416d$. Therefore, $3.1416 \times 8 = 25.1328$ inches.

On the same page, the area is given as $0.7854d^2$. Therefore, A (area) $= 0.7854 \times 8^2 = 0.7854 \times 64 = 50.2656$ square inches.

Example 2: From **page 76** of the Handbook, the area of a cylindrical surface equals $S = 3.1416 \times d \times h$. For a diameter of 8 inches and a height of 10 inches, the area is $3.1416 \times 8 \times 10 = 251.328$ square inches.

Example 3: For the cylinder in **Example 2** but with the area of both ends included, the total area is the sum of the area found in **Example 2** plus two times the area found in **Example 1**. Thus,

Copyright 2004, Industrial Press, Inc., New York, NY

251.328 + 2 × 50.2656 = 351.8592 square inches. The same result could have been obtained by using the formula for total area given on Handbook **page 76**: $A = 3.1416 \times d \times (\frac{1}{2}d + h) = 3.1416 \times 8 \times (\frac{1}{2} \times 8 + 10) = 351.8592$ square inches.

Example 4: If the circumference of a tree is 96 inches, what is its diameter? Since the circumference of a circle $C = 3.1416 \times d$, $96 = 3.1416 \times d$ so that $d = 96 \div 3.1416 = 30.558$ inches.

Example 5: The tables starting on **page 1018** of the Handbook provides values of revolutions per minute required producing various cutting speeds for workpieces of selected diameters. How are these speeds calculated? Cutting speed in feet per minute is calculated by multiplying the circumference in feet of a workpiece by the rpm of the spindle: cutting speed in fpm = circumference in feet × rpm. By transposing this formula as explained in *Formulas And Their Rearrangement* starting on **page 8**,

$$\text{rpm} = \frac{\text{cutting speed, fpm}}{\text{circumference in feet}}$$

For a 3-inch diameter workpiece ($\frac{1}{4}$-foot diameter) and for a cutting speed of 40 fpm, $\text{rpm} = 40 \div (3.1416 \times \frac{1}{4}) = 50.92 = 51$ rpm, approximately, which is the same as the value given on **page 1018** of the Handbook.

PRACTICE EXERCISES FOR SECTION 1

(See *Answers to Practice Exercises For Section 1* on page 221)

1) Find the area and circumference of a circle 10 mm in diameter.

2) On Handbook **page 1020**, for a 5-mm diameter tool or workpiece rotating at 318 rpm, the corresponding cutting speed is given as 5 meters per minute. Check this value.

3) For a cylinder 100 mm in diameter and 10 mm high, what is the surface area not including the top or bottom?

4) A steel column carrying a load of 10,000 pounds has a diameter of 10 inches. What is the pressure on the floor in pounds per square inch?

5) What is the ratio of the area of a square of any size to the area of a circle having the same diameter as one side of the square?

Copyright 2004, Industrial Press, Inc., New York, NY

6) What is the ratio of the area of a square of any size to the area of a circle having the same diameter as one side of the square?

7) The drilling speed for cast iron is assumed to be 70 feet per minute. Find the time required to drill two holes in each of 500 castings if each hole has a diameter of ¾ inch and is 1 inch deep. Use 0.010 inch feed and allow one-fourth minute per hole for setup.

8) Find the weight of a cast-iron column 10 inches in diameter and 10 feet high. Cast iron weighs 0.26 pound per cubic inch.

9) If machine steel has a tensile strength of 55,000 pounds per square inch, what should be the diameter of a rod to support 36,000 pounds if the safe working stress is assumed to be one-fifth of the tensile strength?

10) Moving the circumference of a 16-inch automobile flywheel 2 inches moves the camshaft through how many degrees? (The camshaft rotates at one-half the flywheel speed.)

11) The tables beginning on Handbook **page 990** give lengths of chords for spacing off circumferences of circles into equal parts. Is another method available?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 2

CHORDAL DIMENSIONS, SEGMENTS, AND SPHERES

HANDBOOK Pages **78**, **71**, and **989**— **991**

A chord of a circle is the distance along a straight line from one point to any other point on the circumference. A segment of a circle is that part or area between a chord and the arc it intercepts. The lengths of chords and the dimensions and areas of segments are often required in mechanical work.

Lengths of Chords.— The table of chords, Handbook **page 990**, can be applied to a circle of any diameter as explained and illustrated by examples on that page. This table is given to six decimal places so that it can be used in connection with precision tool work.

Example 1: A circle has 56 equal divisions and the chordal distance from one division to the next is 2.156 inches. What is the diameter of the circle?

The chordal length in the table for 56 divisions and a diameter of 1 equals 0.05607; therefore, in this example,

$$2.156 = 0.05607 \times \text{diameter}$$

$$\text{Diameter} = \frac{2.156}{0.05607} = 38.452 \text{ inches}$$

Example 2: A drill jig is to have eight holes equally spaced around a circle 6 inches in diameter. How can the chordal distance between adjacent holes be determined when the table, Handbook **page 990**, is not available?

One-half the angle between the radial center lines of adjacent holes = 180 ÷ number of holes. If the sine of this angle is multiplied by the diameter of the circle, the product equals the chordal distance. In this example, we have 180 ÷ 8 = 22.5 degrees. The sine of 22.5 degrees from a calculator is 0.38268; hence, the

Copyright 2004, Industrial Press, Inc., New York, NY

chordal distance = 0.38268 × 6 = 2.296 inches. The result is the same as would be obtained with the table on Handbook **page 990** because the figures in the column "Length of the Chord" represent the sines of angles equivalent to 180 divided by the different numbers of spaces.

Use of the Table of Segments of Circles—Handbook page 71 .— This table is of the unit type in that the values all apply to a radius of 1. As explained above the table, the value for any other radius can be obtained by multiplying the figures in the table by the given radius. For areas, the *square* of the given radius is used. Thus, the unit type of table is universal in its application.

Example 3: Find the area of a segment of a circle, the center angle of which is 57 degrees, and the radius 2½ inches.

First locate 57 degrees in the center angle column; opposite this figure in the area column will be found 0.0781. Since the area is required, this number is multiplied by the square of 2½. Thus, 0.0781 × $(2½)^2$ = 0.488 square inch

Example 4: A cylindrical oil tank is 4½ feet in diameter, 10 feet long, and is in a horizontal position. When the depth of the oil is 3 feet, 8 inches, what is the number of gallons of oil?

The total capacity of the tank equals 0.7854 × $(4½)^2$ × 10 = 159 cubic feet. One U.S. gallon equals 0.1337 cubic foot (see Handbook **page 2566**); hence, the total capacity of the tank equals 159 ÷ 0.1337 = 1190 gallons.

The unfilled area at the top of the tank is a segment having a height of 10 inches or $^{10}⁄_{27}$ (0.37037) of the tank radius. The nearest decimal equivalent to $^{10}⁄_{27}$ in Column *h* of the table starting on **page 71** is 0.3707; hence, the number of cubic feet in the segment-shaped space = (27^2 × 0.401 × 120) ÷ 1728 = 20.3 cubic feet and 20.3 ÷ 0.1337 = 152 gallons. Therefore, when the depth of oil is 3 feet, 8 inches, there are 1190 − 152 = 1038 gallons. (See also Handbook **page 61** for additional information on the capacity of cylindrical tanks.)

Spheres.— Handbook **page 78** gives formulas for calculating spherical volumes.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 5: If the diameter of a sphere is 24⅝ inches, what is the volume, given the formula:

$$\text{Volume} = 0.5236d^3$$

The cube of 24⅝ = 14,932.369; hence, the volume of this sphere = 0.5236 × 14,932.369 = 7818.5 cubic inches

PRACTICE EXERCISES FOR SECTION 2

(See *Answers to Practice Exercises For Section 2* on page 221)

1) Find the lengths of chords when the number of divisions of a circumference and the radii are as follows: 30 and 4; 14 and 2½; 18 and 3½.

2) Find the chordal distance between the graduations for thousandths on the following dial indicators: (a) Starrett has 100 divisions and 1⅜-inch dial. (b) Brown & Sharpe has 100 divisions and 1¾ inch dial. (c) Ames has 50 divisions and 1⅝ - inch dial.

3) The teeth of gears are evenly spaced on the pitch circumference. In making a drawing of a gear, how wide should the dividers be set to space 28 teeth on a 3-inch diameter pitch circle?

4) In a drill jig, 8 holes, each ½ inch diameter, were spaced evenly on a 6-inch diameter circle. To test the accuracy of the jig, plugs were placed in adjacent holes, and the distance over the plugs was measured with a micrometer. What should be the micrometer reading?

5) In the preceding problem, what should be the distance over plugs placed in alternate holes?

6) What is the length of the arc of contact of a belt over a pulley 2 feet, 3 inches in diameter if the arc of contact is 215 degrees?

7) Find the areas, lengths, and heights of chords of the following segments: (a) radius 2 inches, angle 45 degrees; (b) radius 6 inches, angle 27 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

8) Find the number of gallons of oil in a tank 6 feet in diameter and 12 feet long if the tank is in a horizontal position, and the oil measures 2 feet deep.

9) Find the surface area of the following spheres, the diameters of which are: $1\frac{1}{2}$; $3\frac{3}{8}$; 65; $20\frac{3}{4}$.

10) Find the volume of each sphere in the above exercise.

11) The volume of a sphere is 1,802,725 cubic inches. What are its surface area and diameter?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 3

FORMULAS AND THEIR REARRANGEMENT

HANDBOOK Page 29

A formula may be defined as a mathematical rule expressed by signs and symbols instead of in actual words. In formulas, letters are used to represent numbers or *quantities*, the term "quantity" being used to designate any number involved in a mathematical process. The use of letters in formulas, in place of the actual numbers, simplifies the solution of problems and makes it possible to condense into small space the information that otherwise would be imparted by long and cumbersome rules. The figures or values for a given problem are inserted in the formula according to the requirements in each specific case. When the values are thus inserted, in place of the letters, the result or answer is obtained by ordinary arithmetical methods. There are two reasons why a formula is preferable to a rule expressed in words. 1.) The formula is more concise, it occupies less space, and it is possible to see at a glance the whole meaning of the rule laid down. 2.) It is easier to remember a brief formula than a long rule, and it is, therefore, of greater value and convenience.

Example 1: In spur gears, the outside diameter of the gear can be found by adding 2 to the number of teeth and dividing the sum obtained by the diametral pitch of the gear. This rule can be expressed very simply by a formula. Assume that we write D for the outside diameter of the gear, N for the number of teeth, and P for the diametral pitch. Then the formula would be:

$$D = \frac{N + 2}{P}$$

This formula reads exactly as the rule given above. It says that the outside diameter (D) of the gear equals 2 added to the number of teeth (N), and this sum is divided by the pitch (P).

Copyright 2004, Industrial Press, Inc., New York, NY

If the number of teeth in a gear is 16 and the diametral pitch 6, then simply put these figures in the place of N and P in the formula, and the outside diameter as in ordinary arithmetic.

$$D = \frac{16 + 2}{6} = \frac{18}{6} = 3 \text{ inches}$$

Example 2: The formula for the horsepower generated by a steam engine is as follows:

$$H = \frac{P \times L \times A \times N}{33,000}$$

in which H = indicated horsepower of engine;
P = mean effective pressure on piston in pounds per square inch;
L = length of piston stroke in feet;
A = area of piston in square inches;
N = number of strokes of piston per minute.

Assume that $P = 90$, $L = 2$, $A = 320$, and $N = 110$; what would be the horsepower?

If we insert the given values in the formula, we have:

$$H = \frac{90 \times 2 \times 320 \times 110}{33,000} = 192$$

From the examples given, we may formulate the following general rule: *In formulas, each letter stands for a certain dimension or quantity; when using a formula for solving a problem, replace the letters in the formula by the figures given for a certain problem, and find the required answer as in ordinary arithmetic.*

Omitting Multiplication Signs in Formulas.— In formulas, the sign for multiplication (×) is often left out between letters the values of which are to be multiplied. Thus AB means $A \times B$, and the formula $H = \frac{P \times L \times A \times N}{33,000}$ can also be written $H = \frac{PLAN}{33,000}$.

If $A = 3$, and $B = 5$, then: $AB = A \times B = 3 \times 5 = 15$.

It is only the multiplication sign (×) that can be thus left out between the symbols or letters in a formula. All other signs must be indicated the same as in arithmetic. The multiplication sign can never be left out between two figures: 35 always means thirty-five, and "three times five" must be written 3 × 5 but "three times A"

Copyright 2004, Industrial Press, Inc., New York, NY

may be written 3A. As a general rule, the figure in an expression such as "3A" is written first and is known as the *coefficient* of A. If the letter is written first, the multiplication sign is not left out, but the expression is written "A × 3."

Rearrangement of Formulas.— A formula can be rearranged or"transposed" to determine the values represented by different letters of the formula. To illustrate by a simple example, the formula for determining the speed (s) of a driven pulley when its diameter (d), and the diameter (D) and speed (S) of the driving pulley are known is as follows: $s = (S \times D)/d$. If the speed of the driven pulley is known, and the problem is to find its diameter or the value of d instead of s, this formula can be rearranged or changed. Thus:

$$d = (S \times D)/s$$

Rearranging a formula in this way is governed by four general rules.

Rule 1. An independent term preceded by a plus sign (+) may be transposed to the other side of the equals sign (=) if the plus sign is changed to a minus sign (–).

Rule 2. An independent term preceded by a minus sign may be transposed to the other side of the equals sign if the minus sign is changed to a plus sign.

As an illustration of these rules, if $A = B - C$, then $C = B - A$, and if $A = C + D - B$, then $B = C + D - A$. That the foregoing are correct may be proved by substituting numerical values for the different letters and then transposing them as shown.

Rule 3. A term that multiplies all the other terms on one side of the equals sign may be moved to the other side if it is made to divide all the terms on that side.

As an illustration of this rule, if $A = BCD$, then $A/(BC) = D$ or according to the common arrangement $D = A/(BC)$. Suppose, in the preceding formula, that $B = 10$, $C = 5$, and $D = 3$; then $A = 10 \times 5 \times 3 = 150$ and $150/(10 \times 5) = 3$.

Rule 4. A term that divides all the other terms on one side of the equals sign may be moved to the other side if it is made to multiply all the terms on that side.

Copyright 2004, Industrial Press, Inc., New York, NY

To illustrate, if $s = SD/d$, then $sd = SD$, and, according to *Rule 3.*, $d = SD/s$. This formula may also be rearranged for determining the values of S and D; thus $ds/D = S$, and $ds/S = D$.

If, in the rearrangement of formulas, minus signs precede quantities, the signs may be changed to obtain positive rather than minus quantities. All the signs on both sides of the equals sign or on both sides of the equation may be changed. For example, if $-2A = -B + C$, then $2A = B - C$. The same result would be obtained by placing all the terms on the opposite side of the equals sign, which involves changing signs. For instance, if $-2A = -B + C$, then $B - C = 2A$.

Fundamental Laws Governing Rearrangement.— After a few fundamental laws that govern any formula or equation are understood, its solution usually is very simple. An equation states that one quantity equals another quantity. So long as both parts of the equation are treated exactly alike, the values remain equal. Thus, in the equation $A = \frac{1}{2}ab$, which states that the area A of a triangle equals one-half the product of the base a times the altitude b, each side of the equation would remain equal if we added the same amount: $A + 6 = \frac{1}{2}ab + 6$; or we could subtract an equal amount from both sides: $A - 8 = \frac{1}{2}ab - 8$; or multiply both parts by the same number: $7A = 7(\frac{1}{2}ab)$; or we could divide both parts by the same number, and we would still have a true equation.

One formula for the total area T of a cylinder is: $T = 2\pi r^2 + 2\pi rh$, where r = radius and h = height of the cylinder. Suppose we want to solve this equation for h. Transposing the part that does not contain h to the other side by changing its sign, we get: $2\pi rh = T - 2\pi r^2$. To obtain h, we can divide both sides of the equation by any quantity that will leave h on the left-hand side; thus:

$$\frac{2\pi rh}{2\pi r} = \frac{T - 2\pi r^2}{2\pi r}$$

It is clear that, in the left-hand member, the $2\pi r$ will cancel out, leaving: $h = (T - 2\pi r^2)/(2\pi r)$. The expression $2\pi r$ in the right-hand member cannot be cancelled because it is not an independent factor, since the numerator equals the difference between T and $2\pi r^2$.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 3: Rearrange the formula for a trapezoid (Handbook **page 64**) to obtain h.

$$A = \frac{(a+b)h}{2}$$

$2A = (a+b)h$	(multiply both members by 2)
$(a+b)h = 2A$	(transpose both members so as to get the multiple of h on the left-hand side)
$\frac{(a+b)h}{a+b} = \frac{2A}{a+b}$	(divide both members by $a+b$)
$h = \frac{2A}{a+b}$	(cancel $a+b$ from the left-hand member)

Example 4: The formula for determining the radius of a sphere (Handbook **page 78**) is as follows:

$$r = \sqrt[3]{\frac{3V}{4\pi}}$$

Rearrange to obtain a formula for finding the volume V.

$r^3 = \frac{3V}{4\pi}$	(cube each side)
$4\pi r^3 = 3V$	(multiply each side by 4π)
$3V = 4\pi r^3$	(transpose both members)
$\frac{3V}{3} = \frac{4\pi r^3}{3}$	(divide each side by 3)
$V = \frac{4\pi r^3}{3}$	(cancel 3 from left-hand member)

The procedure has been shown in detail to indicate the underlying principles involved. The rearrangement could be simplified somewhat by direct application of the rules previously given.To illustrate:

$r^3 = \frac{3V}{4\pi}$	(cube each side)

Copyright 2004, Industrial Press, Inc., New York, NY

$$4\pi r^3 = 3V \quad \text{(applying } \textit{Rule 4.} \text{ move } 4\pi \text{ to left-hand side)}$$

$$\frac{4\pi r^3}{3} = V \quad \text{(move 3 to left-hand side—}\textit{Rule 3.}\text{)}$$

This final equation would, of course, be reversed to locate V at the left of the equals sign as this is the usual position for whatever letter represents the quantity or value to be determined.

Example 5: It is required to determine the diameter of cylinder and length of stroke of a steam engine to deliver 150 horsepower. The mean effective steam pressure is 75 pounds, and the number of strokes per minute is 120. The length of the stroke is to be 1.4 times the diameter of the cylinder.

First, insert the known values into the horsepower formula (**Example 2**):

$$150 = \frac{75 \times L \times A \times 120}{33,000} = \frac{3 \times L \times A}{11}$$

The last expression is found by cancellation.

Assume now that the diameter of the cylinder in inches equals D. Then, $L = 1.4D/12 = 0.117D$ according to the requirements in the problem; the divisor 12 is introduced to change the inches to feet, L being in feet in the horsepower formula. The area $A = D^2 \times 0.7854$. If we insert these values in the last expression in our formula, we have:

$$150 = \frac{3 \times 0.117D \times 0.7854D^2}{11} = \frac{0.2757D^3}{11}$$

$$0.2757D^3 = 150 \times 11 = 1650$$

$$D^3 = \frac{1650}{0.2757} \quad D = \sqrt[3]{\frac{1650}{0.2757}} = \sqrt[3]{5984.8} = 18.15$$

Hence, the diameter of the cylinder should be about 18¼ inches, and the length of the stroke 18.15 × 1.4 = 25.41, or, say, 25½ inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Solving Equations or Formulas by Trial.— One of the equations used for spiral gear calculations, when the shafts are at right angles, the ratios are unequal, and the center distance must be exact, is as follows:

$$R\sec\alpha + \csc\alpha = \frac{2CP_n}{n}$$

In this equation

R = ratio of number of teeth in large gear to number in small gear
C = exact center distance
P_n = normal diametral pitch
n = number of teeth in small gear

The exact spiral angle α of the large gear is found by trial using the equation just given.

Equations of this form are solved by trial by selecting an angle assumed to be approximately correct and inserting the secant and cosecant of this angle in the equation, adding the values thus obtained, and comparing the sum with the known value to the right of the equals sign in the equation. An example will show this more clearly. By using the problem given in Machinery's Handbook (bottom of **page 2104**) as an example, $R = 3$; $C = 10$; $P_n = 8$; $n = 28$.

Hence, the whole expression $\frac{2CP_n}{n} = \frac{2 \times 10 \times 8}{28} = 5.714$

from which it follows that:

$$R \sec \alpha + \csc \alpha = 5.714$$

In the problem given, the spiral angle required is 45 degrees. The spiral gears, however, would not meet all the conditions given in the problem if the angle could not be slightly modified. To determine whether the angle should be greater or smaller than 45 degrees, insert the values of the secant and cosecant of 45 degrees in the formula. The secant of 45 degrees is 1.4142, and the cosecant is 1.4142. Then,

$$3 \times 1.4142 + 1.4142 = 5.6568$$

The value 5.6568 is too small, as it is less than 5.714 which is the required value. Hence, try 46 degrees. The secant of 46 degrees is 1.4395, and the cosecant, 1.3902. Then,

Copyright 2004, Industrial Press, Inc., New York, NY

$$3 \times 1.4395 + 1.3902 = 5.7087$$

Obviously, an angle of 46 degrees is too small. Proceed, therefore, to try an angle of 46 degrees, 30 minutes. This angle will be found too great. Similarly 46 degrees, 15 minutes, if tried, will be found too great, and by repeated trials it will finally be found that an angle of 46 degrees, 6 minutes, the secant of which is 1.4422, and the cosecant, 1.3878, meets the requirements. Then,

$$3 \times 1.4422 + 1.3878 = 5.7144$$

which is as close to the required value as necessary.

In general, when an equation must be solved by the trial-and-error method, all the known quantities may be written on the right-hand side of the equal sign, and all the unknown quantities on the left-hand side. A value is assumed for the unknown quantity. This value is substituted in the equation, and all the values thus obtained on the left-hand side are added. In general, if the result is greater than the values on the right-hand side, the assumed value of the unknown quantity is too great. If the result obtained is smaller than the sum of the known values, the assumed value for the unknown quantity is too small. By thus adjusting the value of the unknown quantity until the left-hand member of the equation with the assumed value of the unknown quantity will just equal the known quantities on the right-hand side of the equal sign, the correct value of the unknown quantity may be determined.

Derivation of Formulas.— Most formulas in engineering handbooks are given without showing how they have been derived or originated, because engineers and designers usually want only the final results; moreover, such derivations would require considerable additional space, and they belong in textbooks rather than in handbooks, which are primarily works of reference. Although Machinery's Handbook contains thousands of standard and special formulas, it is apparent that no handbook can include every kind of formula, because a great many formulas apply only to local designing or manufacturing problems. Such special formulas are derived by engineers and designers for their own use. The exact methods of deriving formulas are based upon mathematical principles as they are related to the particular factors that apply. A few examples will be given to show how several different types of special formulas have been derived.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 6: The problem is to deduce the general formula for finding the point of intersection of two tapers with reference to measured diameters on those tapers. In the diagram, **Fig. 1**,

L = the distance between the two measured diameters, D and d;

X = the required distance from one measured diameter to the intersection of tapers;

a = angle of long taper as measured from center line;

a_1 = angle of short taper as measured from center line.

Then,

$$E = \frac{D-d}{2} = Z + Y$$

$$Z = (L-X)\tan a_1$$

$$Y = X\tan a$$



Fig. 1. To find Dimension *X* from a Given Diameter *D* to the Intersection of Two Conical Surfaces

Therefore:

$$\frac{D-d}{2} = (L-X)\tan a_1 + X\tan a$$

and

Copyright 2004, Industrial Press, Inc., New York, NY

$$D - d = 2\tan a_1 (L - X) + 2X\tan a \quad (1)$$

But

$$2\tan a_1 = T_1 \qquad \text{and} \qquad 2\tan a = T$$

in which T and T_1 represent the long and short tapers per inch, respectively.

Therefore, from **Equation (1)**,

$$D - d = T_1 (L - X) + TX$$

$$D - d = T_1 L - T_1 X + TX$$

$$X(T_1 - T) = T_1 L - (D - d)$$

$$X = \frac{T_1 L - (D - d)}{T_1 - T}$$

Example 7: A flywheel is 16 feet in diameter (outside measurement), and the center of its shaft is 3 feet above the floor. Derive a formula for determining how long the hole in the floor must be to permit the flywheel to turn.



Fig. 2. To Find Length of Hole in Floor for Flywheel

The conditions are as represented in **Fig. 2**. The line *AB* is the floor level and is a chord of the arc *ABD*; it is parallel to the horizontal diameter through the center *O*. *CD* is the vertical diameter and is perpendicular to *AB*. It is shown in geometry that the diameter CD bisects the chord *AB* at the point of intersection *E*. One of the most useful theorems of geometry is that when a diameter bisects a chord, the product of the two parts of the diameter is equal to the square of one half the chord; in other words, $(AE)^2$ =

Copyright 2004, Industrial Press, Inc., New York, NY

$ED \times EC$. If AB is represented by L and OE by a, $ED = r - a$ and $EC = r + a$, in which r = the radius OC; hence,

$$\left(\frac{L}{2}\right)^2 = (r-a)(r+a) = r^2 - a^2$$

$$\frac{L}{2} = \sqrt{r^2 - a^2} \text{ and } L = 2\sqrt{r^2 - a^2}$$

By substituting the values given,

$$L = 2\sqrt{8^2 - 3^2} = 14.8324 \text{ feet} = 14 \text{ feet, } 10 \text{ inches.}$$

The length of the hole, therefore, should be at least 15 feet, to allow sufficient clearance.

Empirical Formulas.— Many formulas used in engineering calculations cannot be established fully by mathematical derivation but must be based upon actual tests instead of relying upon mere theories or assumptions that might introduce excessive errors. These formulas are known as "empirical formulas." Usually such a formula contains a constant (or constants) that represents the result of the tests; consequently, the value obtained by the formula is consistent with these tests or with actual practice.

A simple example of an empirical formula will be found on Handbook **page 386**. This particular formula contains the constant 54,000, which was established by tests, and the formula is used to obtain the breaking load of wrought-iron crane chains to which a factor of safety of 3, 4, or 5 is then applied to obtain the working load. Other examples of empirical formulas will be found on Handbook **page 281**.

Handbook **page 299** contains an example of an empirical formula based upon experiments made with power-transmitting shafts. This formula gives the diameter of shaft required to prevent excessive twisting during transmission of power.

Parentheses.— Two important rules relating to the use of parentheses are based upon the principles of positive and negative numbers:

1) If a parenthesis is preceded by a + sign, it may be removed, if the terms within the parentheses retain their signs.

$$a + (b - c) = a + b - c$$

Copyright 2004, Industrial Press, Inc., New York, NY

2) If a parenthesis is preceded by a − sign, it may be removed, if the signs preceding each of the terms inside of the parentheses are changed (+ changed to −, and − to +). Multiplication and division signs are not affected.

$$a - (b - c) = a - b + c$$

$$a - (-b + c) = a + b - c$$

Knowledge of algebra is not necessary to make successful use of formulas of the general type such as are found in engineering handbooks; it is only necessary to understand thoroughly the use of letters or symbols in place of numbers, and to be well versed in the methods, rules, and processes of ordinary arithmetic. Knowledge of algebra becomes necessary only where a general rule or formula that gives the answer to a problem directly is not available. In other words, algebra is useful in *developing* or originating a general rule or formula, but the formula can be *used* without recourse to algebraic processes.

Constants.— A constant is a value that does not change or is not variable. Constants at one stage of a mathematical investigation may be variables at another stage, but an *absolute constant* has the same value under all circumstances. The ratio of the circumference to the diameter of a circle, or 3.1416, is a simple example of an absolute constant. In a common formula used for determining the indicated horsepower of a reciprocating steam engine, the product of the mean effective pressure in psi, the length of the stroke in feet, the area of the piston in square inches, and the number of piston strokes per minute is divided by the constant 33,000, which represents the number of foot-pounds of work per minute equivalent to 1 horsepower. Constants occur in many mathematical formulas.

Mathematical Signs and Abbreviations.— Every division of mathematics has its traditions, customs, and signs that are frequently of ancient origin. Hence, we encounter Greek letters in many problems where it would seem that English letters would do as well or better. Most of the signs on Handbook **page 2542** will be used frequently. They should, therefore, be understood.

Copyright 2004, Industrial Press, Inc., New York, NY

Conversion Tables.— It may sometimes be necessity to convert English units of measurement into metric units and vice versa. The tables provided at the back of the Handbook will be found useful in this connection.

PRACTICE EXERCISES FOR SECTION 3

(See *Answers to Practice Exercises For Section 3* on page 222)

1) An approximate formula for determining the horsepower H of automobile engines is: $H = D^2SN/3$, where D = diameter of bore, inches; S = length of stroke, inches; and N = number of cylinders. Find the horsepower of the following automobile engine: a) bore, 3½ inches; stroke, 4¼ inches. b) By using the reciprocal of 3, how could this formula be stated?

2) Using the right-angle triangle formula: $C = \sqrt{a^2 + b^2}$, where a = one side, b = the other side, and C = the hypotenuse, find the hypotenuse of a right triangle whose sides are 16 inches and 63 inches.

3) The formula for finding the blank diameter of a cylindrical shell is: $D = \sqrt{d \times (d + 4h)}$, where D = blank diameter; d = diameter of the shell; h = height of the shell. Find the diameter of the blank to form a cylindrical shell of 3 inches diameter and 2 inches high.

4) If D = diagonal of a cube; d = diagonal of face of a cube; s = side of a cube; and V = volume of a cube; then $d = \sqrt{2D^2/3}$; $s = \sqrt{D^2/3}$; and $V = s^3$. Find the side, volume of a cube, and diagonal of the face of a cube if the diagonal of the cube is 10.

5) The area of an equilateral triangle equals one fourth of the square of the side times the square root of 3, or $A = (S^2/4)\sqrt{3} = 0.43301S^2$. Find the area of an equilateral triangle the side of which is 14.5 inches.

6) The formula for the volume of a sphere is: $4\pi r^3/3$ or $\pi d^3/6$. What constants may be used in place of $4\pi/3$ and $\pi/6$?

Copyright 2004, Industrial Press, Inc., New York, NY

7) The formula for the volume of a solid ring is $2\pi^2 Rr^2$, where r = radius of cross section and R = radius from the center of the ring to the center of the cross section. Find the volume of a solid ring made from 2-inch round stock if the mean diameter of the ring is 6 inches.

8) Explain these signs: $\pm, >, <, \sin^{-1}a, \tan, \angle, \sqrt[4]{\ }, \log, \theta, \beta, ::$

9) The area A of a trapezoid (see Handbook **page 64**) is found by the formula:

$$A = \frac{(a+b)h}{2}$$

Transpose the formula for determining width a.

10) $R = \sqrt{r^2 + s^2/4}$; solve for r.

11) $P = 3.1416\sqrt{2(a^2 + b^2)}$; solve for a.

12) $\cos A = \sqrt{1 - \sin^2 A}$; solve for $\sin A$.

13) $a/\sin A = b/\sin B$; solve for $a, b, \sin A, \sin B$.

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 4

SPREADSHEET CALCULATIONS

Spreadsheet computer programs or spreadsheets are versatile, powerful tools for doing repetitive or complicated algebraic calculations. They are used in diverse technological fields including manufacturing, design, and finance. Spreadsheets blend the power of high level computer languages with the simplicity of hand calculators. They are ideal for doing "what-if" calculations such as changing a problem's parameters and comparing the new result to the initial answer. The visual nature of spreadsheets allows the user to grasp quickly and simultaneously the interaction of many variables in a given problem.

Generally only 5 to 10% of a spreadsheet program functionality needs to be understood to begin doing productive spreadsheet calculations. Since the underlying concepts of all spreadsheets are the same, it is easy transfer this basic understanding from one spreadsheet program to another with very little learning curve. Only a small percentage of the actual spreadsheet commands will be covered in this section but understanding these core concepts will allow the reader to do productive work immediately.

There are many varieties of spreadsheet programs. It is impossible to cover all these spreadsheet programs individually in this brief overview. The formulas listed below are for conceptual understanding and may not work when plugged directly into a particular program.The user should consult the spreadsheet's manual or built in help system for examples. Generally for any given topic a spreadsheet's help system will list a properly constructed example of what the user is trying to do. The reader can use this as a guide and template to get started.

Spreadsheet Basic Concepts.— To begin using spreadsheets, several key spreadsheet concepts must be understood.

Copyright 2004, Industrial Press, Inc., New York, NY

Cell Content: The basic calculating unit of all spreadsheets are cells. Cells may either contain formulas, which are discussed further on; or numbers, words, dates, percentages, and currency. A cell normally has to be formatted using the spreadsheet's cell format commands to display its contents correctly. The formatting usually does not affect the internal representation of the cell, e.g. the actual value of the number. For example, a cell formatted as a *percentage* such as 12% would actually contain a value of "0.12" in the cell. If the cell were left unformatted "0.12" would be displayed. A cell formatted for currency would display "3.4" as "$3.40."

Number	Currency	Text	Percentage
12.7854	$12.05	Feed Rate	12% *or* 0.12

Cells containing numbers may be formatted to display an arbitrary level of precision. Again the displayed precision has no affect on actual calculations. For example, the contents of a particular cell containing "3.1415" could be formatted to display “3.141” or “3.14” or “3”. Regardless of what is displayed “3.1415” will be used internally by the program for all calculations that refer to that cell.

Formatting cells while not absolutely necessary, is usually a good idea for several reasons. Formatted cells help others understand your spreadsheet. 12% is easily identifiable as an interest rate, ".12" is not. Formatting can also help to avoid input mistakes in large spreadsheets such as accidently placing an interest rate percentage in a payment currency-formatted cell. The interest rate will be displayed as "$0.12" immediately telling the user something is wrong. For quick "back of the envelope calculations" formatting can be dispensed with to save time.

Cell Address: In addition to content, cells also have addresses. A cell address is created by combining the column and row names of that cell. In the spreadsheet in **Table 1a**, *Parts* would have an address of *A1*, *Machine 2* would be *C1*, and "$13.76" would be *B3*. Spreadsheets use these cell addresses to combine and manipulate the cell contents using formulas.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1a. Machine Cost Spreadsheet (Display)

	A	B	C	D
1	Parts	Machine 1	Machine 2	Total
2	Motor	12.89	$18.76	$31.65
3	Controls	13.76	$19.56	$33.32
4	Chassis	15	$21.87	$36.87
5	Rebate	–7.5	–$10.00	–$17.50
6	Total	34.15	$50.19	$84.34

Formulas: Instead of containing values, a cell may have a formula assigned to it. Spreadsheets use these formulas to manipulate, combine, and chain cells mathematically. The specific format or syntax for properly constructing a formula varies from spreadsheet to spreadsheet. The two most common formula construction techniques are illustrated using the spreadsheet in **Table 1b**.

Table 1b. Machine Cost Spreadsheet (Formulas)

	A	B	C	D
1	Parts	Machine 1	Machine 2	Total
2	Motor	12.89 [a]	$18.76	= +B2+C2[b] = $31.65
3	Controls	13.76 [a]	$19.56	= Sum(B3:C3)[b] = $33.32
4	Chassis	15[a]	$21.87	= Sum(B4:C4)[b] = $36.87
5	Rebate	–7.5[a]	–$10.00	= Sum (B5:C5)[b] = –$17.50
6	Total	=+B2+B3+B4 +B5[b] = Sum(B2:B5) = 34.15[a]	= Sum(C2:C5)[b] = $50.19	= Sum(D2:D5)[b,c] = Sum(B6:C6)[d] = $84.34

[a] This cell is unformatted. This does not change the value of the intermediate calculations or final results.

[b] Cells cannot contain more than one value or formula. The double values and formulas listed in this cell are for illustration only and would not be allowed in a working spreadsheet.

[c] Sum of the machine *Parts*.

[d] Sum of *Machine 1* and *Machine 2*.

Cell by Cell: Each cell is added, subtracted, multiplied or divided individually. For example in **Table 1b**, the total cost of *Machine 1*

Copyright 2004, Industrial Press, Inc., New York, NY

would be the values of each individual part cost in column *B* added vertically in cell *B6*.

B6 =+B2+B3+B4+B5 = $34.15

Sum Function: For long columns or rows of cells, individual cell addition becomes cumbersome. Built-in functions simplify multiple cell manipulation by applying a specific function, like addition, over a range of cells. All spreadsheets have a summation or *Sum* function that adds all the cells that are called out in the function's address range. The *Sum* function adds cells horizontally or vertically. Again in **Table 1b**, the total cost of *Machine 1* using the *Sum* function would be:

B6 = Sum(B2:B5) = $34.15

Either method yields the same result and may be used interchangeably. The cell by cell method must be used for cells that are not aligned horizontally or vertically. The compact *Sum* method is useful for long chains or ranges of cells. Spreadsheets contain many, many built-in functions that work with math, text strings, dates etc..

Adding Formulas: Cells containing formulas can themselves be combined, i.e. formulas containing formulas. In **Table 1b**, the total of the *motor* parts (row 2) for *Machine 1* and *Machine 2*, is calculated by the formula in cell *D2*, the total of the *control* parts *D3,* the total of all *chassis* parts *D4*, and the total of the *rebates* in *D5*. These formulas are summed together vertically in the first formula in cell *D6* to get the total cost of all the parts, in this case $84.34. Note that a spreadsheet cell may only contain one formula or value. The multiple formulas in *D6* are for illustration only.

Alternatively, the cost of *Machine 1*, *B6* and *Machine 2*, *C6* could be added together horizontally to get the cost of all the machines which, in this case, equals the cost of all parts $84.34. This illustrates that it is possible to set up a spreadsheet to find a solution in more than one way. In this case the total cost of all machines was calculated by adding the parts' subtotals or the individual machines' subtotals.

Positive and Negative: Spreadsheets usually display negative numbers with a minus sign "–" in front of them. Sometimes a negative cell number may be formatted to display parentheses around

Copyright 2004, Industrial Press, Inc., New York, NY

a number instead of a minus sign. For example, –12.874 would be equivalent to (12.874). As with general formatting, this has no effect on the actual cell value.

It is extremely important to treat positive and negative cell values consistently. For example, cell values representing a loan amount of $22,000.00 and a payment of $500.00 might be entered as +$22,000.00 and –$500.00 if you are receiving a loan or –$22,000.00 and +$500.00 if you are loaning the money to someone. Switching one of the signs will create an error in the spreadsheet.

Generally it doesn't matter how positive and negative numbers are assigned, so long as the user is consistent throughout the spread sheet and the people using the spreadsheet understand the positive-negative frame of reference. Failure to be consistent will lead to errors in your results.

Basic Mathematical Operators: Spreadsheets generally use the following conventions for basic mathematical operators. These operators may be applied to cell values or cell formulas.

Basic Spreadsheet Mathematical Operators

Function	Operator	Function	Operator
Add	+	Divide	/
Subtract	–	Square	^2
Multiply	*	Square Root	^.5
Grouping	((5+B2)/A2) –(6*((9+16)^0.5))		

Consult the spreadsheet's help system to properly construct other mathematical operations such as sine, cosine, tangent, logarithms, etc..

Built-In Functions: As previously mentioned, spreadsheets contain many built-in functions to aid the user in setting up equations. For example, most spreadsheets have built-in interest functions sometimes referred to as Time Value of Money or *TVM* equations. Generally the names of the variables in the built-in equations do not always exactly match the generally accepted mathematical names used in particular field such as economics.

To illustrate this point, let's compare the *TVM* terms found in **Interest Formulas** on **page 125** to the variable names found in a

Copyright 2004, Industrial Press, Inc., New York, NY

spreadsheet's Future Value (*FV*) built-in function. Then redo the *Compound Interest* problem found on Handbook **page 126**.

Example 1, Compound Interest: At 10 per cent interest compounded annually for 3 years, a principal amount *P* of $1000 becomes a sum $F = 1000(1+ 10 / 100)^3 = \$1{,}331.93$.

To solve this problem using a spreadsheet use the Future Value, *FV* built-in equation. *FV*(*Rate*,*Nper*, *Pmt*,*Pv*)

where

FV = *F* or the Future Value of the amount owed or received.

Rate = *I* or nominal annual interest rate per period. In this yearly case devide by 1, for monthy payments devide by 12.

Nper = *n* or number of interest periods. In this case 3. If the interest were compounded monthly then *Nper* = 3 years × 12 periods / yr. =36 periods

Pmt = *R* or the payments made or received. For a compound interest loan *Pmt* =$0.00

PV = *P* or principle amount lent or borrowed.

Plugging in the appropriate values give the answer. Again note that leaving column *B* unformatted or formatting column *C* makes no difference for the final answer but does make it easier to understand the spreadsheet values.

Table 2. Compound Interest Calculations Spreadsheet

	A	B	C	D
1		Value	Value	
2	*Rate*	.1[a]	10%[b]	
3	*Nper*	3[a]	3[b]	
4	*Pmt*	0[a]	$0.00[b]	
5	*PV*	–1000[a,c]	–$1,000.00[b,c]	
6	*FV*	= *FV*(B2,B3,B4,B5) = 1,331.93[a]	= $1,331.93[b]	

[a] Unformatted cell.
[b] Formatted cell.
[c] This number is negative because you are loaning the money out to collect interest.

Spreadsheet Advanced Concepts.— One of the great strengths of spreadsheets is their ability to quickly and easily do what-if calculations. The two key concepts required to do this are cell content

Copyright 2004, Industrial Press, Inc., New York, NY

and formula "copying and pasting" and "relative and absolute" cell addressing.

Copying and Pasting: Spreadsheets allow cells to be moved, or copied and pasted into new locations. Since a chain of cells can represent a complete problem and solution, copying these chains and pasting them repeatedly into adjacent areas allows several experimental "what-if" scenarios to be set up. It is then easy to vary the initial conditions of the problem and compare the results side by side. This is illustrated in the following example.

Example 2, What-if Compound Interest Comparison: Referring back to the compound interest problem in **Example 1**, compare the effects of different interest rates from three banks using the same loan amount and loan period. The banks offer a 10%, 11%, and 12% rate. In the spreadsheet, enter 10%, 11%, and 12% into *B2*, *C2*, and *D2* respectively. Instead of typing in the initial amounts and formulas for the other values for other banks type them in once in, *B3*, *B4*, *B5* and *B6*. Copy these cells one column over, into column *C* and column *D*. The spreadsheet will immediately solve all three interest rate solutions.

Table 3. Interest Calculations Spreadsheet Using Relative Addressing

	A	B	C	D	E
1	Term	Bank A	Bank B	Bank C	
2	*Rate*	10%	11%	12%	4 cells above "relative" to **E5**
3	*Nper*	3	3	3	3
4	*Pmt*	$0.00	$0.00	$0.00	2
5	*PV*	–$1,000	–$1,000	–$1,000	1
6	*FV*	=*FV*(**B2**,**B3**, **B4**,**B5**) =$1,331.93	=*FV*(**C2**,**C3**, **C4**,**C5**) =$1,367.63	=*FV*(**D2**,**D3**, **D4**,**D5**) =$1,404.93	Cell **E5**

Relative vs. Absolute Address: Notice in row 6 of **Table 3** how the *FV* function cell addresses were changed as they were copied

Copyright 2004, Industrial Press, Inc., New York, NY

from *B* column and pasted into the *C* and *D* columns. The formula cell addresses were changed from **B** to **C** in column *C* and **B** to **D** in column *D*. This is known as relative addressing. Instead of the formulas pointing to the original or "absolute" locations in the *B* column they were changed by the spreadsheet program as they were pasted to match a cell location with the same relative distance and direction as the original cell. To clarify, In column *E*, the cell *E2* is 4 cells up relative to *E5*. This is known as "relative" addressing. Relative addressing while pasting allows spreadsheets users to easily copy and paste multiple copies of a series of calculations. This easy what-if functionality is a cornerstone of spreadsheet usefulness.

Absolute Addressing: For large complicated spreadsheets the user may want to examine several what-if conditions while varying one basic parameter.For this type of problem it is useful to use "absolute" addressing. There are several formats for creating absolute addresses. Some spreadsheets require a "$" be placed in front of each address. The relative address "*B2*" would become and absolute address when entered as "*B2*." When a formula with an absolute address is copied and pasted the copied formula maintains the same address as the original. The power of this is best illustrated by an example.

Example 3, Absolute and Relative Addressing : Suppose in **Example 1** we wanted to find the future value of $1,000, $1,500 and $2,000 for 10% and 11% interest rates. Using the previous example as a starting point we enter values for *Rate*, *Nper*, *Pmt*, and *Pv*. We also enter the function *FV* into cell *B6*. This time we enter the absolute address *B2* for the *Rate* variable. Now when we copy cell *B6* into *C6* and *D6*, the Rate variable continues to point to cell B2 (absolute addresses) while the other variables *Nper*, *Pmt*, and *Pv* point to locations in columns *C* and *D* (relative addresses).

Copyright 2004, Industrial Press, Inc., New York, NY

Table 4a. 10% Interest Rate Calculations Spreadsheet Using Absolute Addressing

	A	B	C	D
1	Term	Loan Amount A	Loan Amount B	Loan Amount C
2	*Rate*	**10%**		
3	*Nper*	5	4	3
4	*Pmt*	$0.00	$0.00	$0.00
5	*PV*	–$1,000	–$1,500	–$2,000
6	*FV*	=*FV*(**B2**,B3,B4,B5) =$1,610.51	=*FV*(**B2**,C3,C4,C5) =$2,196.15	=*FV*(**B2**,D3,D4,D5) =$2,662.00

Table 4b. 11% Interest Rate Calculations Spreadsheet Using Absolute Addressing

	A	B	C	D
1	Term	Loan Amount A	Loan Amount B	Loan Amount C
2	*Rate*	**11%**		
3	*Nper*	5	4	3
4	*Pmt*	$0.00	$0.00	$0.00
5	*PV*	–$1,000	–$1,500	–$2,000
6	*FV*	=*FV*(**B2**,B3,B4,B5) =$1,685.06	=*FV*(**B2**,C3,C4,C5) =$2,277.11	=*FV*(**B2**,D3,D4,D5) =$2,735.26

From the **Table 4a** we find the future value for different starting amounts for a 10% rate. We change cell *B2* from 10% to 11% and the spreadsheet updates all the loan calculations based on the new interest rate. These new values are displayed in **Table 4b**. All we had to do was change one cell to try a new "what-if." By combining relative and absolute addresses we were able to compare the effects of three different loan amounts using two interest rates by changing one cell value.

Other Capabilities: In addition to mathematical manipulations, most spreadsheets can create graphs, work with dates and text strings, link results to other spreadsheets, create conditional programming algorithms to name a few advanced capabilities. While these features may be useful in some situations, many real world

Copyright 2004, Industrial Press, Inc., New York, NY

problems can be solved using spreadsheets by using a few simple operators and concepts.

PRACTICE EXERCISES FOR SECTION 4

(See *Answers to Practice Exercises For Section 4* on page 223)

1) Use a spreadsheet to format a cell in different ways. Enter the number 0.34 in the first cell. Using the spreadsheet menu bar and online help, change the formatting of the cell to display this number as a percentage, a dollar amount, and then back to a general number.

2) Use a spreadsheet to create a times table. Enter the numbers1-10 in the first column (A) and the first row (1). In cell B2 enter the formula for cell B1 × A2. Repeat this operation down the column. Use the spreadsheet's copy and paste function to copy all the formulas in column B, rows 2-10 and successively paste them into columns C-J making sure not to paste over the values in row 1. Use your spreadsheet to look up the value of 2 × 2, 5 × 7, and 8 × 9.

	A	B	C	D	E	F	G	H	I	J
1	1	2	3	4	5	6	7	8	9	10
2	2									
3	3									
4	4									
5	5									
6	6									
7	7									
8	8									
9	9									
10	10									

3) Using a spreadsheet to recreate Table 1b on **page 24**. Make sure to format currency cells where required.

4) Using your spreadsheet's online help for guidance, recreate the compound interest calculation, Table 2 on **page 27** using the spreadsheet's *Future Valu*e interest rate function. Make sure to format currency and percentage cells correctly.

5) Using the spreadsheet you created in the previous question, calculate the *Future Value* of $2,500 compounded annually for 12 years at 7.5% interest. What would the *Future Value* be if the interest was compounded monthly?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 5

CALCULATIONS INVOLVING LOGARITHMS OF NUMBERS

HANDBOOK Pages 111 to 118

The purpose of logarithms is to facilitate and shorten calculations involving multiplication and division, obtaining the powers of numbers, and extracting the roots of numbers. By means of logarithms, long multiplication problems become simple addition of logarithms; cumbersome division problems are easily solved by simple subtraction of logarithms; the fourth root or, say, the 10.4th root of a number can be extracted easily, and any number can be raised to the twelfth power as readily as it can be squared.

The availability of inexpensive hand-held calculators, and computers, has eliminated much of the need to use logarithms for such purposes; there are, however, many applications in which the logarithm of a number is used in obtaining the solution of a problem. For example, in the Handbook section, *Compound Interest* on page 125, there is a formula to find the number of years n required for a sum of money to grow a specified amount. The example accompanying the formula shows the necessary calculations that include the logarithms 3, 2.69897, and 0.025306, which correspond to the numbers 1000, 500, and 1.06, respectively. These logarithms were obtained directly from a hand-held electronic calculator and are the common or *Briggs* system logarithms, which have a base 10. Any other system of logarithms such as that of base e ($e = 2.71828\ldots$) could have been used in this problem with the same result. Base e logarithms are sometimes referred to as "natural logarithms."

There are other types of problems in which logarithms of a specific base, usually 10 or e, must be used to obtain the correct result. On the logarithm keys of most calculators, the base 10 logs are identified by the word "log" and those of base e are referred to as "ln."

Copyright 2004, Industrial Press, Inc., New York, NY

In the common or Briggs system of logarithms, which is used ordinarily, the base of the logarithms is 10; that is, the logarithm is the *exponent* that would be affixed to 10 to produce the number corresponding to the logarithm. To illustrate, by taking simple numbers:

$$\text{Logarithm of } 10 = 1 \text{ because } 10^1 = 10$$

$$\text{Logarithm of } 100 = 2 \text{ because } 10^2 = 100$$

$$\text{Logarithm of } 1000 = 3 \text{ because } 10^3 = 1000$$

In each case, it will be seen that the exponent of 10 equals the logarithm of the number. The logarithms of all numbers between 10 and 100 equal 1 plus some fraction. For example: The logarithm of 20 = 1.301030.

The logarithms of all numbers between 100 and 1000 = 2 plus some fraction; between 1000 and 10,000 = 3 plus some fraction; and so on. The tables of logarithms in engineering handbooks give only this fractional part of a logarithm, which is called the *mantissa*. The whole number part of a logarithm, which is called the *characteristic*, is not given in the tables because it can easily be determined by simple rules. The logarithm of 350 is 2.544068. The whole number 2 is the characteristic (see Handbook **page 111**) and the decimal part 0.544068, or the mantissa, is found in the table (Handbook **page 115**).

Principles Governing the Application of Logarithms.— When logarithms are used, the product of two numbers can be obtained as follows: Add the logarithms of the two numbers; the sum equals the logarithm of the product. For example: The logarithm of 10 (commonly abbreviated log 10) equals 1; log 100 = 2; 2 + 1 = 3, which is the logarithm of 1000 or the product of 100 × 10.

Logarithms would not be used for such a simple example of multiplication; these particular numbers are employed merely to illustrate the principle involved.

For division by logarithms, subtract the logarithm of the divisor from the logarithm of the dividend to obtain the logarithm of the quotient. To use another simple example, divide 1000 by 100 using logarithms. As the respective logarithms of these numbers are 3 and 2, the difference of equals the logarithm of the quotient 10.

Copyright 2004, Industrial Press, Inc., New York, NY

In using logarithms to raise a number to any power, simply multiply the logarithm of the number by the exponent of the number; the product equals the logarithm of the power. To illustrate, find the value of 10^3 using logarithms. The logarithm of 10 = 1 and the exponent is 3; hence, 3 × 1 = 3 = log of 1000; hence, $10^3 = 1000$.

To extract any root of a number, merely divide the logarithm of this number by the index of the root; the quotient is the logarithm of the root. Thus, to obtain the cube root of 1000 divide 3 (log 1000) by 3 (index of root); the quotient equals 1 which is the logarithm of 10. Therefore,

$$\sqrt[3]{1000} = 10$$

Logarithms are of great value in many engineering and shop calculations because they make it possible to solve readily cumbersome and also difficult problems that otherwise would require complicated formulas or higher mathematics. Keep constantly in mind that logarithms are merely exponents. Any number might be the base of a system of logarithms. Thus, if 2 were selected as a base, then the logarithm of 256 would equal 8 because $2^8 = 256$. However, unless otherwise mentioned, the term "logarithm" is used to apply to the common or Briggs system, which has 10 for a base.

The tables of common logarithms are found on Handbook **pages 115** and **116**. The natural logarithms, **pages 117** and **118**, are based upon the number 2.71828. These logarithms are used in higher mathematics and also in connection with the formula to determine the mean effective pressure of steam in engine cylinders.

Finding the Logarithms of Numbers.— There is nothing complicated about the use of logarithms, but a little practice is required to locate readily the logarithm of a given number or to reverse this process and find the number corresponding to a given logarithm. These corresponding numbers are sometimes called "antilogarithms."

Study carefully the rules for finding logarithms given on Handbook **pages 111** to **114** Although the characteristic or whole-number part of a logarithm is easily determined, the following table will assist the beginner in memorizing the rules.

Copyright 2004, Industrial Press, Inc., New York, NY

Sample Numbers and Their Characteristics

Characteristic	Number	Characteristic	Number
0.008	$\overline{3}$	88	1
0.08	$\overline{2}$	888	2
0.8	$\overline{1}$	8888	3
8.0	0	88888	4

Example of the use of the table of numbers and their characteristics: What number corresponds to the log $\overline{2}$.55145? Find 0.551450 in the log tables to correspond to 356. From the table of characteristics, note that a $\overline{2}$ characteristic calls for one zero in front of the first integer; hence, point off 0.0356 as the number corresponding to the log 2.55145. Evaluating logarithms with negative characteristics is explained more thoroughly later.

Example 1: Find the logarithm of 46.8.

The mantissa of this number is 0.670246. When there are two whole-number places, the characteristic is 1; hence, the log of 46.8 is 1.670246.

After a little practice with the above table, one becomes familiar with the rules governing the characteristic so that reference to the table is no longer necessary.

Obtaining More Accurate Values Than Given Directly by Tables.— The method of using the tables of logarithms to obtain more accurate values than are given directly, by means of interpolation, is explained on Handbook **page 112**. These instructions should be read carefully in order to understand the procedure in connection with the following example:

Example 2:

$$\frac{76824 \times 52.076}{435.21} =$$

log 76824 = 4.88549 log numerator = 6.60213

log 52.076 = 1.71664 − log 435.21 = 2.63870

log numerator = 6.60213 log quotient = 3.96343

Copyright 2004, Industrial Press, Inc., New York, NY

The number corresponding to the logarithm 3.96343 is 9192.4. The logarithms just given for the dividend and divisor are obtained by interpolation in the following manner:

In the log tables on **page 116** of the Handbook, find the mantissa corresponding to the first three digits of the number 76824, and the mantissa of the next higher 3-digit number in the table, 769. The mantissa of 76824 is the mantissa of 768 plus $^{24}/_{100}$ times the difference between the mantissas of 769 and 768.

Mantissa 769 = .885926

Mantissa 768 = .885361

Difference = .000565

Thus, log 76824 = 0.24 × 0.000565 + log 76800 = 4.885497. The characteristic 4 is obtained as previously illustrated in the table on **page 35**. By again using interpolation as explained in the Handbook, the corrected mantissas are found for the logarithms of 52.076 and 435.21.

After obtaining the logarithm of the quotient, which is 3.96343, interpolation is again used to determine the corresponding number more accurately than would be possible otherwise. The mantissa .96343 (see Handbook **page 116**) is found, in the table, between 0.963316 and 0.963788, the mantissas corresponding to 919 and 920, respectively.

0.963788 – 0.963316 = 0.000472

0.96343 – 0.963316 = 0.000114

Note that the first line gives the difference between the two mantissas nearest .96343, and the second line gives the difference between the mantissa of the quotient and the nearest smaller mantissa in the Handbook table. The characteristic 3 in the quotient 3.96343 indicates 4 digits before the decimal point in the answer, thus the number sought is 9190 + $^{114}/_{472}$(9200 –9190) = 9192.4.

Changing Form of Logarithm Having Negative Characteristic.— The characteristic is frequently rearranged for easier manipulation. Note that 8 – 8 is the same as 0; hence, the log of 4.56 could be stated: 0.658965 or 8.658965 – 8. Similarly, the log of 0.075 = $\overline{2}$.875061 or 8.875061 – 10 or 7.875061 – 9. Any similar

Copyright 2004, Industrial Press, Inc., New York, NY

arrangement could be made, as determined by case in multiplication or division.

Example 3:

$$\sqrt[3]{0.47} = ?$$

$$\log 0.47 = \overline{1}.672098 \text{ or } 8.672098 - 9$$

$$\log \sqrt[3]{0.47} = (8.672098 - 9) \div 3 = 2.890699 \div 3 = \overline{1}.89070$$

In the first line above, 9 – 9 was added to log 0.47 because 3 (the index of the root) will divide evenly into 9; 11 – 12 or 5 – 6 could have been used as well. (Refer also to Example 2 on Handbook **page 114**. The procedure differs from that just described but the same result is obtained.)

To find the number corresponding to $\overline{1}.89070$, locate the nearest mantissa. Mantissa .890421 is found in the table and corresponds to 777. The $\overline{1}$ characteristic indicates that the decimal point immediately precedes the first integer; therefore, the number equivalent to the log1.89070 is 0.777. If desired, additional accuracy can be obtained by interpolation, as explained previously. Thus,

$\sqrt[3]{0.47} = 0.777$.

Cologarithms.— The cologarithm of a number is the logarithm of the reciprocal of that number. "Cologs" have no properties different from those of ordinary logarithms, but they enable division to be earned out by addition because the addition of a colog is the same as the subtraction of a logarithm.

Example 4: $\dfrac{742 \times 6.31}{55 \times 0.92} = ?$

Note that this problem could be stated: 742 × 6.31 × 1/55 × 1/0.92. Then the logs of each number could be added because the process is one of multiplication only.

log 1/55 can be obtained readily in two ways

$$\begin{aligned} \log 1/55 &= \log 1 - \log 55 \\ \log 1 &= \quad 10.000000 \quad - 10 \\ -\log 55 &= \quad -1.740363 \\ &\quad\overline{\quad 8.259637 \quad - 10} \qquad = \overline{2}.259637 \end{aligned}$$

Copyright 2004, Industrial Press, Inc., New York, NY

or

$$\log 1/55 = \log 0.0181818 \text{ (see reciprocals)}$$
$$\log 0.0181818 = \overline{2}.25964$$

This number $\overline{2}.259637$ is called the colog of 55; hence, to find the colog of any number, subtract the logarithm of that number from 10.000000 – 10; this is the same as dividing 1 by the number whose colog is sought.

To find the colog of 0.92. subtract log 0.92 (or $\overline{1}.96379$) from 10.00000 – 10; thus:

$$\begin{aligned} & 10.000000 - 10 \\ \log 0.92 = & \ \overline{1}.963788 \\ \text{colog } 0.92 = & \ 9.963788 - 10 = 0.036212 \end{aligned}$$

(In subtracting negative characteristics, change the sign of the lower one and add.)

Another method is to use $\log 0.92 = \overline{1}.96379$ or 9.96379 – 10, and proceeding as above:

$$\begin{aligned} & 10.000000 - 10 \\ \log 0.92 = \overline{1}.96378 = & \ 9.963788 - 10 \\ \text{colog } 0.92 = & \ 0.036212 \end{aligned}$$

Example 4 may then be solved by adding logs; thus:

log 742	=	2.870404
log 6.31	=	0.800029
colog 55	=	$\overline{2}.259637$
colog 0.92	=	0.036212
log quotient	=	1.966282

The number corresponding to the logarithm of the quotient = 92.53.

Example 5: The initial absolute pressure of the steam in a steam engine cylinder is 120 psi; the length of the stroke is 26 inches; the clearance 1½ inches; and the period of admission, measured from

Copyright 2004, Industrial Press, Inc., New York, NY

the beginning of the stroke, 8 inches. Find the mean effective pressure.

The mean effective pressure is found by the formula:

$$p = \frac{P(1 + \log_e R)}{R}$$

in which p = mean effective pressure in pounds per square inch;
P = initial absolute pressure in pounds per square inch;
R = ratio of expansion, which in turn is found from the formula:

$$R = \frac{L + C}{l + C}$$

in which L = length of stroke in inches;
l = period of admission in inches;
C = clearance in inches.

The given values are $P = 120$; $L = 26$; $l = 8$; and $C = 1\frac{1}{2}$. By inserting the last three values in the formula for R, we have:

$$R = \frac{26 + 1\frac{1}{2}}{8 + 1\frac{1}{2}} = \frac{27.5}{9.5} = 2.89$$

If we now insert the value of P and the found value of R in the formula for p. we have:

$$p = \frac{120(1 + \log_e 2.89)}{2.89}$$

The natural logarithm (hyp. log.) may be found from tables or a calculator. The natural logarithm for 2.89 is 1.061257 (see Handbook **page 117**. Inserting this value in the formula, we have:

$$p = \frac{120(1 + 1.061257)}{2.89} = \frac{120 \times 2.061257}{2.89} = 85.6 \text{ lb/in}^2$$

PRACTICE EXERCISES FOR SECTION 5

(See *Answers to Practice Exercises For Section 5* on page 223)

1) What are the rules governing the characteristics?

2) Find the mantissas of: 762; 478; 26; 0.0098; 6743; 24.82.

3) What are the characteristics of the numbers just given?

Copyright 2004, Industrial Press, Inc., New York, NY

4) What numbers could correspond to the following mantissas: 0.085016; 0.88508; 0.22763?

5) (a) If the characteristic of each of the mantissas just given is 1, what would the corresponding numbers be? (b) Using the following characteristics (2, 0, 3) for each mantissa, find the antilogarithms or corresponding numbers.

6) log 765.4 = ? log 87.2 = ?; log 0.00874 = ?

7) What are the antilogarithms of: 2.89894; 1.24279; 0.18013; 2.68708?

8) Find by interpolation the logarithm of: 75186; 42.037.

9) Find the numbers corresponding to the following logarithms: 1.82997; 0.67712.

10) $(2.71)^5 = ?$ $(4.23)^{2.5} = ?$

11) $\sqrt{97.65} = ?$ $\sqrt[5]{4687} = ?$ $\sqrt[2.3]{44.5} = ?$

12) $\dfrac{62876 \times 54.2 \times 0.0326}{1728 \times 231} = ?$

13) $(2/19)^7 = ?$

14) $(9.16)^{2.47} = ?$

15) $\sqrt[3]{\dfrac{(75)^2 \times (5.23)^{2/3}}{0.00036 \times \sqrt{51.7}}} =$

16) The area of a circular sector = $0.008727ar^2$ where a = angle in degrees and r = radius of the circle. Find the area of a circular sector the radius of which is 6.25 inches and the central angle is 42° 15′.

17) The diameter of a lineshaft carrying pulleys may be found from the formula: $d = \sqrt[3]{53.5\text{hp/rpm}}$. Find the diameter of shafting necessary to transmit 50 hp at 250 rpm.

18) The horsepower of a steam engine is found from the formula: $hp = PLAN/33000$, where

Copyright 2004, Industrial Press, Inc., New York, NY

P = mean effective pressure in pounds per square inch;

L = length of stroke in feet;

A = area of piston in square inches;

N = number of strokes per minute = revolutions per minute × 2.

Find the horsepower of a steam engine if the pressure is 120 pounds, stroke 18 inches, piston 10 inches in diameter, and the number of revolutions per minute is 125.

19) Can the tables of logarithms be used for addition and subtraction?

20) Can logarithms be used to solve gear-ratio problems?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 6

DIMENSIONS, AREAS, AND VOLUMES OF GEOMETRICAL FIGURES

HANDBOOK Pages **36** to **74**

The formulas given for the solution of different problems relating to the areas of surfaces and volumes of various geometrical figures are derived from plane and solid geometry. For purposes of shop mathematics, all that is necessary is to select the appropriate figure and use the formula given. Keep in mind the tables that have been studied and use them in the solution of the formulas whenever such usage can be done to advantage.

Many rules may be developed directly from the table for polygons on Handbook **page 69**. These rules will permit easy solution of nearly every problem involving a regular polygon. For instance, in the first "*A*" columns at the left, $A/S^2 = 7.6942$ for a decagon; by transposition, $S = \sqrt{A \div 7.6942}$. In the first "*R*" column, $R = 1.3066S$ for an octagon; hence, $S = R \div 1.3066$.

The frequent occurrence of such geometrical figures as squares, hexagons, spheres, and spherical segments in shop calculations makes the tables dealing with these figures very useful.

Example 1: A rectangle 12 inches long has an area of 120 square inches; what is the length of its diagonal?

The area of a rectangle equals the product of the two sides; hence, the unknown side of this rectangle equals $^{120}/_{12} = 10$ inches.

$$\text{Length of diagonal} = \sqrt{12^2 + 10^2} = \sqrt{244} = 15.6205$$

Example 2: If the diameter of a sphere, the diameter of the base, and the height of a cone are all equal, find the volume of the sphere if the volume of the cone is 250 cubic inches.

Copyright 2004, Industrial Press, Inc., New York, NY

The formula on Handbook **page 77** for the volume of a cone shows that the value for $250 = 0.2618d^2h$, in which d = diameter of cone base and h = vertical height of cone; hence,

$$d^2 = \frac{250}{0.2618h}$$

Since in this example d and h are equal,

$$d^3 = \frac{250}{0.2618}$$

and

$$d = \sqrt[3]{\frac{250}{0.2618}} = 9.8474 \text{ inches}$$

By referring to the formula on Handbook **page 78**, the volume of a sphere $= 0.5236d^3 = 0.5236 \times (9.8474)^3 = 500$ cubic inches.

In solving the following exercises, first, construct the figure carefully, and then apply the formula. Use the examples in the Handbook as models.

PRACTICE EXERCISES FOR SECTION 6

(See *Answers to Practice Exercises For Section 6* on page 224)

1) Find the volume of a cylinder having a base radius of 12.5 and a height of 16.3 inches.

2) Find the area of a triangle with sides that are 12, 14, and 18 inches in length.

3) Find the volume of a torus or circular ring made from 1½ inch round stock if its outside diameter is 14 inches.

4) A bar of hexagonal screw stock measures 0.750 inch per side. What is the largest diameter that can be turned from this bar?

5) Using the prismoidal formula (Handbook **page 59**), find the volume of the frustum of a regular triangular pyramid if its lower base is 6 inches per side, upper base 2 inches per side, and height 3 inches. (Use the table on Handbook **page 69** for areas. The side of the midsection equals one-half the sum of one side of the lower base and one side of the upper base.)

Copyright 2004, Industrial Press, Inc., New York, NY

6) What is the diameter of a circle the area of which is equivalent to that of a spherical zone whose radius is 4 inches and height 2 inches?

7) Find the volume of a steel ball $\frac{3}{8}$ inch in diameter.

8) What is the length of the side of a cube if the volume equals the volume of a frustum of a pyramid with square bases, 4 inches and 6 inches per side, and 3 inches high?

9) Find the volume of a bronze bushing if its inside diameter is inch, outside diameter is $1\frac{1}{2}$ inches, and length is 2 inches.

10) Find the volume of material making up a hollow sphere with an outside diameter of 10 inches and an inside diameter of 6 inches.

11) Find the area of a 10-equal-sided polygon inscribed in a 6-inch diameter circle.

12) What is the radius of a fillet if its chord is 2 inches? What is its area?

13) Find the area of the conical surface and volume of a frustum of a cone if the diameter of its lower base is 3 feet, diameter of upper base 1 foot, and height 3 feet.

14) Find the total area of the sides and the volume of a triangular prism 10 feet high, having a base width of 8 feet.

15) The diagonal of a square is 16 inches. What is the length of its side?

16) How many gallons can be contained in a barrel having the following dimensions: height $2\frac{1}{2}$ feet; bottom diameter 18 inches; bilge diameter 21 inches? (The sides are formed to the arc of a circle.)

17) Find the area of a sector of a circle if the radius is 8 inches and the central angle is 32 degrees.

18) Find the height of a cone if its volume is 17.29 cubic inches and the radius of its base is 4 inches.

19) Find the volume of a rectangular pyramid having a base 4×5 inches and height 6 inches.

Copyright 2004, Industrial Press, Inc., New York, NY

20) Find the distance across the corners of both hexagons and squares when the distance across flats in each case is: $\frac{1}{2}$; $1\frac{5}{8}$; $3\frac{3}{10}$; 5; 8.

21) The diagonal of one square is 2.0329 and of the other square is 4.6846. Find the lengths of the sides of both squares.

22) In measuring the distance over plugs in a die that has six $\frac{3}{4}$-inch holes equally spaced on a circle, what should be the micrometer reading over opposite plugs if the distance over alternate plugs is $4\frac{1}{2}$ inches?

23) To what diameter should a shaft be turned in order to mill on one end a hexagon 2 inches on a side; an octagon 2 inches on a side?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 7

GEOMETRICAL PROPOSITIONS AND CONSTRUCTIONS

HANDBOOK Pages 49 to 58

Geometry is the branch of mathematics that deals with the relations of lines, angles, surfaces, and solids. Plane geometry treats the relations of lines, angles, and surfaces in one plane only, and since this branch of geometry is of special importance in mechanical work, the various propositions or fundamental principles are given in the Handbook, as well as various problems or constructions. This information is particularly useful in mechanical drafting and in solving problems in mensuration.

Example 1: A segment-shaped casting (see **Fig. 1**) has a chordal length of 12 inches, and the height of the chord is 2 inches; determine by the application of a geometrical principle the radius R of the segment.

This problem may be solved by the application of the second geometrical proposition given on Handbook **page 53**. In this example, one chord consists of two sections a and b, each 6 inches long; the other intersecting chord consists of one section d, 2 inches long; and the length of section c is to be determined in order to find radius R. Since $a \times b = c \times d$, it follows that:

$$c = \frac{a \times b}{d} = \frac{6 \times 6}{2} = 18 \quad \text{inches}$$

therefore,

$$R = \frac{c + d}{2} = \frac{18 + 2}{2} = 10 \quad \text{inches}$$

In this example, one chordal dimension, $c + d$ = the diameter; but, the geometrical principle given in the Handbook applies regardless of the relative lengths of the intersecting chords.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 2: The center lines of three holes in a jig plate form a triangle. The angle between two of these intersecting center lines is 52 degrees. Another angle between adjacent center lines is 63 degrees. What is the third angle?



Fig. 1.

This problem is solved by application of the first geometrical principle on Handbook **page 49**. The unknown angle = 180 – (63 + 52) = 65 degrees.

Example 3: The center lines of four holes in a jig plate form a four-sided figure. Three of the angles between the different intersecting center lines are 63 degrees, 105 degrees, and 58 degrees, respectively. What is the fourth angle?

According to the geometrical principle at the bottom of Handbook page 45, the unknown angle = 360 – (63 + 105 + 58) = 134 degrees.

Example 4: The centers of three holes are located on a circle. The angle between the radial center lines of the first and second holes is 22 degrees, and the center-to-center distance measured along the circle is 2½ inches. The angle between the second and third holes is 44 degrees. What is the center-to-center distance along the circle?

This problem is solved by application of the fourth principle on Handbook **page 53**. Since the lengths of the arcs are proportional to the angles, the center distance between the second and third

Copyright 2004, Industrial Press, Inc., New York, NY

holes = (44 × 2½)/22 = 5 inches. (See also rules governing proportion starting on Handbook **page 5**.)

The following practice exercises relate to the propositions and constructions given and should be answered without the aid of the Handbook.

PRACTICE EXERCISES FOR SECTION 7

(See *Answers to Practice Exercises For Section 7* on page 224)

1) If any two angles of a triangle are known, how can the third angle be determined?

2) State three instances where one triangle is equal to another.

3) When are triangles similar?

4) What is the purpose of proving triangles similar?

5) If a triangle is equilateral, what follows?

6) What are the properties of the bisector of any angle of an equilateral triangle?

7) What is an isosceles triangle?

8) How do the size of an angle and the length of a side of a triangle compare?

9) Can you draw a triangle whose sides are 5, 6, and 11 inches?

10) What is the length of the hypotenuse of a right triangle the sides of which are 12 and 16 inches?

11) What is the value of the exterior angle of any triangle?

12) What are the relations of angles formed by two intersecting lines?

13) Draw two intersecting straight lines and a circle tangent to these lines.

14) Construct a right triangle given the hypotenuse and one side.

15) When are the areas of two parallelograms equal?

16) When are the areas of two triangles equal?

17) If a radius of a circle is perpendicular to a chord, what follows?

Copyright 2004, Industrial Press, Inc., New York, NY

18) What is the relation between the radius and tangent of a circle?

19) What lines pass through the point of tangency of two tangent circles?

20) What are the attributes to two tangents drawn to a circle from an external point?

21) What is the value of an angle between a tangent and a chord drawn from the point of tangency?

22) Are all angles equal if their vertices are on the circumference of a circle, and they are subtended by the same chord?

23) If two chords intersect within a circle, what is the value of the product of their respective segments?

24) How can a right angle be drawn using a semicircle?

25) Upon what does the length of circular arcs in the same circle depend?

26) To what are the circumferences and areas of two circles proportional?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 8

FUNCTIONS OF ANGLES

HANDBOOK Pages **88** to **107**

The basis of trigonometry is proportion. If the sides of any angle are indefinitely extended and perpendiculars from various points on one side are drawn to intersect the other side, right triangles will be formed, and the ratios of the respective sides and hypotenuses will be identical. If the base of the smallest triangle thus formed is 1 inch, and the altitude is ½ inch (see **Fig. 1**), the ratio between these sides is 1 ÷ ½ = 2 or ½ ÷ 1 = ½ depending upon how the ratio is stated. If the next triangle is measured, the ratio between the base and altitude will likewise be either 2 or ½, and this will always be true for any number of triangles, if the angle remains unchanged. For example, 3 ÷ 1½ = 2 and 4½ ÷ 2¼ = 2 or 1½ ÷ 3 = ½ and 2¼ ÷ 4½ = ½.



Fig. 1. For a Given Angle, the Radio of the Base to the Altitude Is the Same for All Triangle Sizes

Copyright 2004, Industrial Press, Inc., New York, NY

This relationship explains why rules can be developed to find the length of any side of a triangle when the angle and one side are known or to find the angle when any two sides are known. Since there are two relations between any two sides of a triangle, there can be, therefore, a total of six ratios with three sides. These ratios are defined and explained in the Handbook. Refer to **pages 88** and **89** and note explanations of the terms *side adjacent*, *side opposite*, and *hypotenuse*.

The abbreviations of the trigonometric functions begin with a small letter and are not followed by periods.

Functions of Angles and Use of Trigonometric Tables.— On **page 88** of the Handbook are given certain rules for determining the functions of angles. These rules, which should be memorized, may also be expressed as simple formulas:

$$\text{sine} = \frac{\text{side opposite}}{\text{hypotenuse}} \qquad \text{cosecant} = \frac{\text{hypotenuse}}{\text{side opposide}}$$

$$\text{cosine} = \frac{\text{side adjacent}}{\text{hypotenuse}} \qquad \text{secant} = \frac{\text{hypotenuse}}{\text{side adjacent}}$$

$$\text{tangent} = \frac{\text{side opposite}}{\text{side adjacent}} \qquad \text{cotangent} = \frac{\text{side adjacent}}{\text{side opposite}}$$

Note that these functions are arranged in pairs to include sine and cosecant, cosine and secant, tangent and cotangent, and that each pair consists of a function and its reciprocal. Also, note that the different functions are merely ratios, the sine being the ratio of the *side opposite* to the *hypotenuse*, cosine the ratio of the *side adjacent* to the *hypotenuse*, etc. Tables of trigonometric functions are, therefore, tables of ratios and these functions can be obtained easily and quickly from most pocket calculators. For example, tan 20° 30′ = 0.37388; this means that in any right triangle having an acute angle of 20° 30′, the side opposite that angle is equal in length to 0.37388 times the length of the side adjacent. Cos 50°22′ = 0.63787; this means that in any right triangle having an angle of 50°22′, if the hypotenuse equals a certain length, say, 8, the side adjacent to the angle will equal 0.63787 × 8 or 5.10296.

Copyright 2004, Industrial Press, Inc., New York, NY

Referring to **Fig. 1**, tan angle $C = 2\frac{1}{4} \div 4\frac{1}{2} = 1\frac{1}{2} \div 3 = \frac{1}{2} \div 1 = 0.5$; therefore, for this particular angle C, the *side opposite* is always equal to 0.5 times *side adjacent*, thus: $1 \times 0.5 = \frac{1}{2}$; $3 \times 0.5 = 1\frac{1}{2}$; and $4\frac{1}{2} \times 0.5 = 2\frac{1}{4}$. The side opposite angle B equals $4\frac{1}{2}$; hence, tan $B = 4\frac{1}{2} \div 2\frac{1}{4} = 2$.

Finding Angle Equivalent to Given Function.— After determining the tangent of angle C or of angle B, the values of these angles can be determined readily. As tan $C = 0.5$, find the number nearest to this in the tangent column. On Handbook **page 101** will be found 0.498582, corresponding to 26 degrees, 30 minutes, and 0.502219 corresponding to the angle 26 degrees, 40 minutes. Because 0.5 is approximately midway between 0.498582 and 0.502219, angle C can be accurately estimated as 26 degrees, 35 minutes. This degree of accuracy is usually sufficient, however, improved accuracy may be obtained by interpolation, as explained in the examples to follow.

Since angle $A = 90$ degrees, and, as the sum of three angles of a triangle always equals 180 degrees, it is evident that angle $C + B = 90$ degrees; therefore, $B = 90$ degrees minus 26 degrees, 35 minutes = 63 degrees, 25 minutes. The table on Handbook **page 101** also shows that tan 63 degrees, 25 minutes is midway between 1.991164 and 2.005690, or approximately 2 within 0.0002.

Note that for angles 45° to 90°, Handbook **pages 100** to **102**, the table is used by reading from the bottom up, using the function labels across the bottom of the table, as explained on Handbook **page 99**.

In the foregoing example, the tangent is used to determine the unknown angles because the known sides are the side adjacent and the side opposite the unknown angles, these being the sides required for determining the tangent. If the side adjacent and the length of hypotenuse had been given instead, the unknown angles might have been determined by first finding the cosine because the cosine equals the side adjacent divided by the hypotenuse.

The acute angles (like B and C, **Fig. 1**) of any right triangle must be complementary, so the function of any angle equals the cofunction of its complement; thus, the sine of angle B = the cosine of

Copyright 2004, Industrial Press, Inc., New York, NY

angle *C*; the tangent of angle *B* = the cotangent of angle *C*; etc. Thus, tan b = $4\frac{1}{2} \div 2\frac{1}{4}$ and cotangent *C* also equals $4\frac{1}{2} \div 2\frac{1}{4}$. The tangent of 20° 30′ = 0.37388, which also equals the cotangent of 20°30′. For this reason, it is only necessary to calculate the trigonometric ratios to 45° when making a table of trigonometric functions for angles between 45° and 90°, and this is why the functions of angles between 45° and 90° are located in the table by reading it backwards or in reverse order, as previously mentioned.

Example 1: Find the tangent of 44 degrees, 59 minutes.

Following instructions given on **page 99** of the Handbook, find 44 degrees, 50 minutes, and 45 degrees, 0 minutes at the bottom of **page 102**; and find their respective tangents, 0.994199 and 1.0000000, in the column "tan" labeled across the top of the table. The tangent of 44°59′ is 0.994199 + 0.9 × (1 – 0.994199) = 0.99942.

Example 2: Find the tangent of 45 degrees, 5 minutes.

At the bottom of Handbook page 97, and above "tan" at the bottom of the table, are the tangents of 45° 0′ and 45° 10′, 1.000000 and 1.005835, respectively. The required tangent is midway between these two values and can be found from 1.000000 + 0.5 × (1.005835 – 1) = 1.00292.

How to Find More Accurate Functions and Angles Than Are Given in the Table.— In the Handbook, the values of trigonometric functions are given to degrees and 10-minute increments; hence, if the given angle is in degrees, minutes, and seconds, the value of the function is determined from the nearest given values by interpolation.

Example 3: Assume that the sine of 14°22′26″ is to be determined. It is evident that this value lies between the sine of 14°20′ and the sine of 14°30′.

Sine 14°20′ = 0.247563 and Sine 14°30′ = 0.250380; the difference = 0.250389 – 0.247563 = 0.002817. Consider this difference as a whole number (2817) and multiply it by a fraction having as its numerator the number of additional minutes and fractions of minutes (number of seconds divided by 60) in the given angle ($2 + {}^{26}\!/_{60}$), and as its denominator the number of minutes in the interval between 14°20′ and the sine of 14°30′. Thus, ($2 + {}^{26}\!/_{60}$)/10 × 2817

Copyright 2004, Industrial Press, Inc., New York, NY

= [(2 × 60) + 26]/(10 × 60) × 2817 = 685.47; hence, by adding 0.000685 to sine of 14°20′, we find that sine 14°22′ 26″ = 0.247563 + 0.000685 = 0.24825.

The correction value (represented in this example by 0.000685) is *added* to the function of the *smaller* angle nearest the given angle in dealing with sines or tangents, but this correction value is *subtracted* in dealing with cosines or cotangents.

Example 4: Find the angle whose cosine is 0.27052.

The table of trigonometric functions shows that the desired angle is between 74°10′ and 74°20′ because the cosines of these angles are, respectively, 0.272840 and 0.270040. The difference = 0.272840 – 0.270040 = 0.00280′. From the cosine of the smaller angle (i.e., the larger cosine) or 0.272840, subtract the given cosine; thus, 0.272840 – 0.27052 = 0.00232; hence 232/280 × 10 = 8.28571′ or the number of minutes to add to the smaller angle to obtain the required angle. Thus, the angle for a cosine of 0.27052 is 74°18.28571′, or 74°18′17″. Angles corresponding to given sines, tangents, or cotangents may be determined by the same method.

Trigonometric Functions of Angles Greater Than 90 Degrees.— In obtuse triangles, one angle is greater than 90 degrees, and the Handbook tables can be used for finding the functions of angles larger than 90 degrees, but the angle must be first expressed in terms of an angle less than 90 degrees.

The sine of an angle greater than 90 degrees but less than 180 degrees equals the sine of an angle that is the difference between 180 degrees and the given angle.

Example 5: Find the sine of 118 degrees.

sin 118° = sin (180° – 118°) = sin 62°. By referring to **page 101**, it will be seen that the sine given for 62 degrees is 0.882948.

The cosine, tangent, and cotangent of an angle greater than 90 but less than 180 degrees equals, respectively, the cosine, tangent, and cotangent of the difference between 180 degrees and the given angle; but the angular function has a negative value and must be preceded by a minus sign.

Example 6: Find tan 123 degrees, 20 minutes.

tan 123°20′ = –tan (180° – 123°20′) = –tan 56°40′ = –1.520426

Copyright 2004, Industrial Press, Inc., New York, NY

Example 7: Find csc 150 degrees.

Cosecent, abbreviated csc or cosec, equals 1/sin, and is positive for angels 90 to 180 degrees (see Handbook **page 99**)

csc 15° = 1/sin(180° – 150°) = 1/sin 30° = 1/0.5 = 2.0

In the calculation of triangles, it is very important to include the minus sign in connection with the sines, cosines, tangents, and cotangents of angles greater than 90 degrees. The diagram, *Signs of Trigonometric Functions, Fractions of p, and Degree–Radian Conversion* on **page 98** of the Handbook, shows clearly the negative and positive values of different functions and angles between 0 and 360 degrees. The table, *Useful Relationships Among Angles* on **page 99**, is also helpful in determining the function, sign, and angle less than 90 degrees that is equivalent to the function of an angle greater than 90 degrees.

Use of Functions for Laying Out Angles.— Trigonometric functions may be used for laying out angles accurately either on drawings or in connection with template work, etc. The following example illustrates the general method:

Example 8: Construct or lay out an angle of 27 degrees, 29 minutes by using its sine instead of a protractor.

First, draw two lines at right angles, as in **Fig. 2**, and to any convenient length. Find, from a calculator, the sine of 27 degrees, 29 minutes, which equals 0.46149. If there is space enough, lay out the diagram to an enlarged scale to obtain greater accuracy. Assume that the scale is to be 10 to 1: therefore, multiply the sine of the angle by 10, obtaining 4.6149 or about $4\frac{3}{64}$. Set the dividers or the compass to this dimension and with *a* (**Fig. 2**) as a center, draw an arc, thus obtaining one side of the triangle *ab*. Now set the compass to 10 inches (since the scale is 10 to 1) and, with *b* as the center, describe an arc so as to obtain intersection *c*. The hypotenuse of the triangle is now drawn through the intersections *c* and *b*, thus obtaining an angle *C* of 27 degrees, 29 minutes within fairly close limits. The angle *C*, laid out in this way, equals 27 degrees, 29 minutes because:

$$\frac{\text{Side Opposite}}{\text{Hypotenuse}} = \frac{4.6149}{10} = 0.46149 = \sin 27°29'$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 2. Method of Laying out Angle by Using Its Sine

Tables of Functions Used in Conjunction with Formulas.—

When milling keyways, it is often desirable to know the total depth from the outside of the shaft to the bottom of the keyway. With this depth known, the cutter can be fed down to the required depth without taking any measurements other than that indicated by the graduations on the machine. To determine the total depth, it is necessary to calculate the height of the arc, which is designated as dimension *A* in **Fig. 3**. The formula usually employed to determine *A* for a given diameter of shaft *D* and width of key *W* is as follows:

$$A = \frac{D}{2} - \sqrt{\left(\frac{D}{2}\right)^2 - \left(\frac{W}{2}\right)^2}$$

Another formula, which is simpler than the one above, is used in conjunction with a calculator, as follows:

$$A = \frac{D}{2} \times \text{versed sine of an angle whose sine is } \frac{W}{D}$$



Fig. 3. To Find Height *A* for Arc of Given Radius and Width *W*

Copyright 2004, Industrial Press, Inc., New York, NY

Example 9: To illustrate the application of this formula, let it be required to find the height A when the shaft diameter is $\frac{7}{8}$ inch and the width W of the key is $\frac{7}{32}$ inch. Then, $W/D = (\frac{7}{32})/(\frac{7}{8}) = \frac{7}{32} \times \frac{8}{7} = 0.25$. Using the formula at the bottom of Handbook **page 103** for versed sin $\theta = 1 - \cos \theta$, and a calculator, the angle corresponding to sin 0.25 = 14.4775 degrees, or 14 degrees, 28 minutes, 39 seconds. The cosine of this angle is 0.9682, and subtracting this value from 1 gives 0.03175 for the versed sine. Then, the height of the circular segment $A = D/2 \times 0.03175 = (7 \times 0.03175)/(8 \times 2) = 0.01389$, so the total depth of the keyway equals dimension H plus 0.01389 inch.

PRACTICE EXERCISES FOR SECTION 8

(See *Answers to Practice Exercises For Section 8* on page 225)

1) How should a scientific pocket calculator be used to solve triangles?

2) Explain the meaning of sin 30° = 0.50000.

3) Find sin 18°26′30″; tan 27°16′15″; cos 32°55′17″.

4) Find the angles that correspond to the following tangents: 0.52035; 0.13025; to the following cosines: 0.06826; 0.66330.

5) Give two rules for finding the *side opposite* a given angle.

6) Give two rules for finding the *side adjacent* to a given angle.

7) Explain the following terms: equilateral; isosceles; acute angle; obtuse angle; oblique angle.

8) What is meant by complement; side adjacent; side opposite?

9) Can the elements referred to in Exercise 8 be used in solving an isosceles triangle?

10) Without referring to the Handbook, show the relationship between the six trigonometric functions and an acute angle, using the terms *side opposite*, *side adjacent*, and *hypotenuse* or abbreviations *SO*, *SA*, and *Hyp*.

11) Construct by use of tangents an angle of 42°20′.

12) Construct by use of sines an angle of 68°15′.

13) Construct by use of cosines an angle of 55°5′.

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 9

SOLUTION OF RIGHT-ANGLE TRIANGLES

HANDBOOK Page **91** to **92**

A thorough knowledge of the solution of triangles or trigonometry is essential in drafting, layout work, bench work, and for convenient and rapid operation of some machine tools. Calculations concerning gears, screw threads, dovetails, angles, tapers, solution of polygons, gage design, cams, dies, and general inspection work are dependent upon trigonometry. Many geometrical problems may be solved more rapidly by trigonometry than by geometry.

In shop trigonometry, it is not necessary to develop and memorize the various rules and formulas, but it is essential that the six trigonometric functions be mastered thoroughly. It is well to remember that a thorough, working knowledge of trigonometry depends upon drill work; hence a large number of problems should be solved.

The various formulas for the solution of right-angle triangles are given on Handbook **page 91** and examples showing their application on **page 92**. These formulas may, of course, be applied to a large variety of practical problems in drafting rooms, tool rooms, and machine shops, as indicated by the following examples.

Whenever two sides of a right-angle triangle are given, the third side can always be found by a simple arithmetical calculation, as shown by the second and third examples on Handbook **page 92**. To find the angles, however, it is necessary to use tables of sines, cosines, tangents, and cotangents, or a calculator, and, if only one side and one of the acute angles are given, the natural trigonometric functions must be used for finding the lengths of the other sides.

Example 1: The Jarno taper is 0.600 inch per foot for all numbers. What is the included angle?

Copyright 2004, Industrial Press, Inc., New York, NY

As the angle measured from the axis or center line is 0.600 ÷ 2 = 0.300 inch per foot, the tangent of one-half the included angle = 0.300 ÷ 12 = 0.25 = tan 1° 26′; hence the included angle = 2° 52′. A more direct method is to find the angle whose tangent equals the taper per foot divided by 24 as explained on Handbook **page 715**.

Example 2: Determine the width *W* (see **Fig. 1**) of a cutter for milling a splined shaft having 6 splines 0.312 inch wide, and a diameter *B* of 1.060 inches.

This dimension *W* may be computed by using the following formula:

$$W = \sin\left(\frac{\frac{360^\circ}{N} - 2a}{2}\right) \times B$$

in which *N* = number of splines; *B* = diameter of body or of the shaft at the root of the spline groove.



Fig. 1. To Find Width *W* of Spline-Groove Milling Cutter

Copyright 2004, Industrial Press, Inc., New York, NY

Angle a must first be computed, as follows:

$$\sin a = \frac{T}{2} \div \frac{B}{2} \text{ or } \sin a = \frac{T}{B}$$

where T = width of spline; B = diameter at the root of the spline groove. In this example,

$$\sin a = \frac{0.312}{1.060} = 0.29434$$

$$a = 17°7'; \text{ hence}$$

$$W = \left(\frac{\sin \frac{360°}{6} - 2 \times 17°7'}{2} \right) \times 1.060 = 0.236 \text{ inch}$$

This formula has also been used frequently in connection with broach design, but it is capable of a more general application. If the splines are to be ground on the sides, suitable deduction must be made from dimension W to leave sufficient stock for grinding.

If the angle b is known or is first determined, then

$$W = B \times \sin \frac{b}{2}$$

As there are 6 splines in this example, angle $b = 60° - 2a = 60° - 34°14' = 25°46'$; hence,

$W = 1.060 \times \sin 12°53' = 1.060 \times 0.22297 = 0.236$ inch

Example 3: In sharpening the teeth of thread milling cutters, if the teeth have rake, it is necessary to position each tooth for the grinding operation so that the outside tip of the tooth is at a horizontal distance x from the vertical center line of the milling cutter as shown in **Fig. 2b**. What must this distance x be if the outside radius to the tooth tip is r, and the rake angle is to be A? What distance x off center must a 4½-inch diameter cutter be set if the teeth are to have a 3-degree rake angle?

In **Fig. 2a**, it will be seen that, assuming the tooth has been properly sharpened to rake angle A, if a line is drawn extending the front edge of the tooth, it will be at a perpendicular distance x from the center of the cutter. Let the cutter now be rotated until the tip of the tooth is at a horizontal distance x from the vertical center line

Copyright 2004, Industrial Press, Inc., New York, NY

of the cutter as shown in **Fig. 2b**. It will be noted that an extension of the front edge of the cutter is still at perpendicular distance x from the center of the cutter, indicating that the cutter face is parallel to the vertical center line or is itself vertical, which is the desired position for sharpening using a vertical wheel. Thus, x is the proper offset distance for grinding the tooth to rake angle A if the radius to the tooth tip is r. Since r is the hypotenuse, and x is one side of a right-angled triangle,

$$x = r \sin A$$

For a cutter diameter of 4½ inches and a rake angle of 3 degrees,

$$x = (4.5 \div 2) \sin 3° = 2.25 \times 0.05234$$
$$= 0.118 \text{ inch}$$

To Find Horizontal Distance for Positioning Milling Cutter Tooth for Grinding Rake Angle *A*



Fig. 2a.



Fig. 2b.

Example 4: Forming tools are to be made for different sizes of poppet valve heads, and a general formula is required for finding angle x from dimensions given in **Fig. 3**.

The values for b, h, and r can be determined easily from the given dimensions. Angle x can then be found in the following manner:

Referring to the lower diagram,

$$\tan A = \frac{h}{b} \quad (1)$$

$$c = \frac{h}{\sin A} \quad (2)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Also,

$$c = \frac{r}{\sin B} = \frac{r}{\sin(A - x)} \tag{3}$$



Fig. 3. To Find Angle *x*, Having the Dimensions Given on the Upper Diagram

From Equations (2) and (3) by comparison,

$$\frac{r}{\sin(A - x)} = \frac{h}{\sin A} \tag{4a}$$

$$\sin(A - x) = \frac{r \sin A}{h} \tag{4b}$$

From the dimensions given, it is obvious that $b = 0.392125$ inch, $h = 0.375$ inch, and $r = 0.3125$ inch. Substituting these values in **Equation (1)** and **(4b)** and solving, angle A will be found to be 43 degrees, 43 minutes and angle $(A - x)$ to be 35 degrees, 10 minutes. By subtracting these two values, angle x will be found to equal 8 degrees, 33 minutes.

Example 5: In tool designing, it frequently becomes necessary to determine the length of a tangent to two circles. In **Fig. 4**, R =

Copyright 2004, Industrial Press, Inc., New York, NY

radius of large circle = $^{13}/_{16}$ inch; r = radius of small circle = $^{3}/_{8}$ inch; W = center distance between circles = $1^{11}/_{16}$ inches.



Fig. 4. To Find Dimension E or Distance Between Points of Tangency

With the values given, it is required to find the following: E = length of tangent, B = length of horizontal line from point of tangency on large circle to the vertical line, and C = length of horizontal line from point of tangency on small circle to the vertical center line.

$$\sin a = \frac{R-r}{W} = \frac{13/16 - 3/8}{1\frac{11}{16}} = 0.25925$$

$$\text{Angle } a = 15°1' \text{ nearly}$$

$$E = W\cos a = 1\frac{11}{16} \times 0.9658 = 1.63 \text{ inches}$$

$$B = R\sin a \qquad \text{and} \qquad C = r\sin a$$

Example 6: A circle is inscribed in a right triangle having the dimensions shown in **Fig. 5**. Find the radius of the circle.

In **Fig. 5**, $BD = BE$ and $AD = AF$, because "tangents drawn to a circle from the same point are equal." $EC = CF$, and EC = radius OF. Then, let R = radius of inscribed circle. $AC - R = AD$ and $BC - R = DB$. Adding,

Copyright 2004, Industrial Press, Inc., New York, NY

$$AC + BC - 2R = AD + DB$$

$$AD + DB = AB$$

hence, $$AC + BC - AB = 2R$$



Fig. 5. To Find Radius of Circle Inscribed in Triangle

Stated as a rule: *The diameter of a circle inscribed in a right triangle is equal to the difference between the lengths of the hypotenuse and the sum of the lengths of the other sides*. Substituting the given dimensions, we have 1.396 + 1.8248 – 2.2975 = 0.9233 = 2*R*, and *R* = 0.4616.

Example 7: A part is to be machined to an angle *b* of 30 degrees (**Fig. 6**) by using a vertical forming tool having a clearance angle *a* of 10 degrees. Calculate the angle of the forming tool as measured in a plane *Z–Z*, which is perpendicular to the front or clearance surface of the tool.

Assume that *B* represents the angle in plane *Z–Z*.

$$\tan B = \frac{Y}{X} \text{ and } Y = y \times \cos a \tag{1}$$

Also,

$$y = X \times \tan b \text{ and } X = \frac{y}{\tan b} \tag{2}$$

Now substituting the values of *Y* and *X* in **Equation (1)**, we have:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\tan B = \frac{y \times \cos a}{\frac{y}{\tan b}}$$

Clearing this equation of fractions,

$$\tan B = \cos a \times \tan b$$



Fig. 6. The Problem is to Determine Angle of Forming Tool in Plane Z–Z

In this example, $\tan B = 0.98481 \times 0.57735 = 0.56858$; hence, $B = 29°37'$ nearly.

Example 8: A method of checking the diameter at the small end of a taper plug gage is shown by **Fig. 7**. The gage is first mounted on a sine bar so that the top of the gage is parallel with the surface

Copyright 2004, Industrial Press, Inc., New York, NY

plate. A disk of known radius *r* is then placed in the corner formed by the end of the plug gage and the top side of the sine bar. Now by determining the difference *X* in height between the top of the gage and the top edge of the disk, the accuracy of the diameter *B* can be checked readily. Derive formulas for determining dimension *X*.



Fig. 7. The Problem is to Determine Height *X* in Order to Check Diameter *B* of Taper Plug

The known dimensions are:

e = angle of taper

r = radius of disk

B = required diameter at end of plug gage

g = 90 degrees – ½*e* and *k* = ½*g*

By trigonometry,

Copyright 2004, Industrial Press, Inc., New York, NY

$$F = \frac{r}{\tan k};\ E = B - F;\ \text{and}\ \tan m = \frac{r}{E}$$

Also

$$P = \frac{r}{\sin m};\ n = g - m;\ \text{and}\ H = P \sin n$$

Therefore, $X = H - r$ or $r - H$, depending on whether or not the top edge of the disk is above or below the top of the plug gage. In **Fig. 7**, the top of the disk is below the top surface of the plug gage so that it is evident that $X = H - r$.

To illustrate the application of these formulas, assume that $e = 6$ degrees, $r = 1$ inch, and $B = 2.400$ inches. The dimension X is then found as follows:

$$g = 90 - \tfrac{6}{2} = 87°;\ \text{and}\ k = 43°30'$$

By trigonometry,

$$F = \frac{1}{0.9896} = 1.0538'';\ E = 2.400 - 1.0538 = 1.3462\ \text{inches}$$

$$\tan m = \frac{1}{1.3462} = 0.74283\ \text{and}\ m = 36°36'22''$$

$$P = \frac{1}{0.59631} = 1.6769'';\ n = 87° - 36°36'22'' = 50°23'38''$$

and $$H = 1.6769 \times 0.77044 = 1.2920\ \text{inches}$$

Therefore, $$X = H - r = 1.2920 - 1 = 0.2920\ \text{inch}$$

The disk here is below the top surface of the plug gage; hence, the formula $X = H - r$ was applied.

Example 9: In **Fig. 8**, $a = 1\frac{1}{4}$ inches, $h = 4$ inches, and angle $A = 12$ degrees. Find dimension x and angle B.

Draw an arc through points E, F, and G, as shown, with r as a radius. According to a well-known theorem of geometry, which is given on Handbook **page 52**, if an angle at the circumference of a circle, between two chords, is subtended by the same arc as the angle at the center, between two radii, then the angle at the circumference is equal to one-half the angle at the center. This being true, angle C is twice the magnitude of angle A, and angle D = angle A = 12 degrees. Thus,

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 8. Find Dimension *x* and Angle *B*, Given *a*, *h*, and Angle *A*

$$r = \frac{a}{2\sin D} = \frac{1.25}{2 \times 0.20791} = 3.0061$$

$$w = \frac{a}{2}\cot D = 0.625 \times 4.7046 = 2.9404$$

and

$$z = h - w = 4 - 2.9404 = 1.0596$$

Now

$$y = \sqrt{r^2 - z^2} = \sqrt{7.9138505} = 2.8131$$

and

$$x = y - \frac{a}{2} = 2.8131 - 0.625 = 2.1881 \quad \text{inches}$$

Finally,

$$\tan B = \frac{x}{h} = \frac{2.1881}{4} = 0.54703$$

and

$$B = 28 \text{ degrees, } 40 \text{ minutes, } 47 \text{ seconds}$$

Copyright 2004, Industrial Press, Inc., New York, NY

Example 10: A steel ball is placed inside a taper gage as shown in **Fig. 9**. If the angle of the taper, length of taper, radius of ball, and its position in the gage are known, how can the end diameters *X* and *Y* of the gage be determined by measuring dimension *C*?

The ball should be of such size as to project above the face of the gage. Although not necessary, this projection is preferable, as it permits the required measurements to be obtained more readily. After measuring the distance *C*, the calculation of dimension *X* is as follows: First obtain dimension *A*, which equals R multiplied by csc *a*. Then adding *R* to *A* and subtracting *C* we obtain dimension *B*. Dimension *X* may then be obtained by multiplying 2*B* by the tangent of angle *a*. The formulas for *X* and *Y* can therefore be written as follows:

$$X = 2(R\csc a + R - C)\tan a$$
$$= 2(R\sec a + 2\tan a(R - C))$$
$$Y = X - 2T\tan a$$



Fig. 9. Checking Dimensions *X* and *Y* by Using One Ball of Given Size

If, in **Fig. 9**, angle $a = 9$ degrees, $T = 1.250$ inches, $C = 0.250$ inch and $R = 0.500$ inch, what are the dimensions *X* and *Y*? Applying the formula,

$$X = 2 \times 0.500 \times 1.0125 + 2 \times 0.15838(0.500 - 0.250)$$

By solving this equation, $X = 1.0917$ inches. Then

$$Y = 1.0917 - (2.500 \times 0.15838) = 0.6957$$

Copyright 2004, Industrial Press, Inc., New York, NY

Example 11: In designing a motion of the type shown in **Fig. 10**, it is essential, usually, to have link *E* swing equally above and below the center line *M-M*. A mathematical solution of this problem follows. In the illustration, *G* represents the machine frame; *F*, a lever shown in extreme positions; *E*, a link; and *D*, a slide. The distances *A* and *B* are fixed, and the problem is to obtain $A + X$, or the required length of the lever. In the right triangle:

$$A + X = \sqrt{(A - X)^2 + \left(\frac{B}{2}\right)^2}$$

Squaring, we have:

$$A^2 + 2AX + X^2 = A^2 - 2AX + X^2 + \frac{B^2}{4}$$

$$4AX = \frac{B^2}{4}$$

$$X = \frac{B^2}{16A}$$

$$A + X = A + \frac{B^2}{16A} = \text{length of lever}$$



Fig. 10. Determining Length *F* so that Link *E* will Swing Equally Above and Below the Center Line

Copyright 2004, Industrial Press, Inc., New York, NY

To illustrate the application of this formula, assume that the length of a lever is required when the distance $A = 10$ inches, and the stroke B of the slide is 4 inches.

$$\text{Length of lever} = A + \frac{B^2}{16A} = 10 + \frac{16}{16 \times 10}$$
$$= 10.100 \text{ inches}$$

Thus, it is evident that the pin in the lower end of the lever will be 0.100 inch below the center line *M-M* when half the stroke has been made, and, at each end of the stroke, the pin will be 0.100 inch above this center line.

Example 12: The spherical hubs of bevel gears are checked by measuring the distance x (**Fig. 11**) over a ball or plug placed against a plug gage that fits into the bore. Determine this distance x.



Fig. 11. Method of Checking the Spherical Hub of a Bevel Gear with Plug Gages

Copyright 2004, Industrial Press, Inc., New York, NY

First find H by means of the formula for circular segments on Handbook page 62.

$$H = 2.531 - 1/2\sqrt{4 \times (2.531)^2 - (1.124)^2} = 0.0632 \text{ inch}$$

$$AB = \frac{1.124}{2} + 0.25 = 0.812 \text{ inch}$$

$$BC = 2.531 + 0.25 = 2.781 \text{ inches}$$

Applying one of the formulas for right triangles, on Handbook page 88,

$$AC = \sqrt{(2.781)^2 - (0.812)^2} = 2.6599 \text{ inches}$$

$$AD = AC - DC = 2.6599 - 2.531 = 0.1289 \text{ inch}$$

$$x = 1.094 + 0.0632 + 0.1289 + 0.25 = 1.536 \text{ inches}$$

Example 13: The accuracy of a gage is to be checked by placing a ball or plug between the gage jaws and measuring to the top of the ball or plug as shown by **Fig. 12**. Dimension x is required, and the known dimensions and angles are shown by the illustration.



Fig. 12. Finding Dimension *x* to Check Accuracy of Gage

Copyright 2004, Industrial Press, Inc., New York, NY

One-half of the included angle between the gage jaws equals one-half of 13° × 49′ or 6° × 54½′, and the latter equals angle *a*.

$$AB = \frac{0.500}{\sin 6°54\frac{1}{2}'} = 4.1569 \text{ inches}$$

DE is perpendicular to *AB* and angle *CDE* = angle *a*; hence,

$$DE = \frac{CD}{\cos 6°54\frac{1}{2}'} = \frac{0.792}{\cot 6°54\frac{1}{2}'} = 0.79779 \text{ inch}$$

$$AF = \frac{DE}{2} \times \cot 6°54\frac{1}{2}' = 3.2923 \text{ inches}$$

$$\text{Angle } CDK = 90° + 13°49' = 103°49'$$

$$\text{Angle } CDJ = 103°49' - 88°49' = 15°$$

$$\text{Angle } EDJ = 15° - 6°54\frac{1}{2}' = 8°5\frac{1}{2}'$$

$$GF = \frac{DE}{2} \times \tan 8°5\frac{1}{2}' = 0.056711 \text{ inch}$$

$$\text{Angle } HBG = \text{angle } EDJ = 8°5\frac{1}{2}'$$

$$BG = AB - (GF + AF) = 0.807889 \text{ inch}$$

$$BH = BG \times \cos 8°5\frac{1}{2}' = 0.79984 \text{ inch}$$

$$x = BH + 0.500 = 1.2998 \text{ inches}$$

If surface *JD* is parallel to the bottom surface of the gage, the distance between these surfaces might be added to *x* to make it possible to use a height gage from a surface plate.

Helix Angles of Screw Threads, Hobs, and Helical Gears.— The terms "helical" and "spiral" often are used interchangeably in drafting rooms and shops, although the two curves are entirely different. As the illustration on Handbook **page 58** shows, every point on a helix is equidistant from the axis, and the curve advances at a uniform rate around a cylindrical area. The helix is illustrated by the springs shown on Handbook **page 321**. A spiral is flat like a clock spring. A spiral may be defined mathematically as a curve having a constantly increasing radius of curvature.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 13. Helix Represented by a Triangular Piece of Paper Wound Upon a Cylinder

If a piece of paper is cut in the form of a right triangle and wrapped around a cylinder, as indicated by the diagram (**Fig. 13**), the hypotenuse will form a helix. The curvature of a screw thread represents a helix. From the properties of a right triangle, simple formulas can be derived for determining helix angles. Thus, if the circumference of a part is divided by the lead or distance that the helix advances axially in one turn, the quotient equals the tangent of the helix angle as measured from the axis. The angles of helical curves usually (but not always) are measured from the axis. The helix angle of a helical or "spiral" gear is measured from the axis, but the helix angle of a screw thread is measured from a plane perpendicular to the axis. In a helical gear, the angle is *a* (**Fig. 13**), whereas for a screw thread, the angle is *b*; hence, for helical gears, tan *a* of helix angle = *C*/*L*; for screw threads, tan *b* of helix angle = *L*/*C*. The helix angle of a hob, such as is used for gear cutting, also is measured as indicated at *b* and often is known as the "end angle" because it is measured from the plane of the end surface of the hob. In calculating helix angles of helical gears, screw threads, and bobs, the pitch circumference is used.

Example 14: If the pitch diameter of a helical gear = 3.818 inches and the lead = 12 inches, what is the helix angle?

Tan helix angle = (3.818 × 3.1416)/12 = 1 very nearly; hence the angle = 45 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

PRACTICE EXERCISES FOR SECTION 9

(See *Answers to Practice Exercises For Section 9* on page 226)

1) The No. 4 Morse taper is 0.6233 inch per foot; calculate the included angle.

2) ANSI Standard pipe threads have a taper of $\frac{3}{4}$ inch per foot. What is the angle on each side of the center line?

3) To what dimension should the dividers be set to space 8 holes evenly on a circle of 6 inches diameter?

4) Explain the derivation of the formula

$$W = \sin\left(\frac{\frac{360^\circ}{N} - 2a}{2}\right) \times B$$

For notation, see **Example 2** on **page 59** and the diagram **Fig. 1**.

5) The top of a male dovetail is 4 inches wide. If the angle is degrees, and the depth is $\frac{5}{8}$ inch, what is the width at the bottom of the dovetail?

6) Angles may be laid out accurately by describing an arc with a radius of given length and then determining the length of a chord of this arc. In laying out an angle of 25 degrees, 20 minutes, using a radius of 8 inches, what should the length of the chord opposite the named angle be?

7) What is the largest square that may be milled on the end of a 2½-inch bar of round stock?

8) A guy wire from a smoke stack is 120 feet long. How high is the stack if the wire is attached to feet from the top and makes an angle of 57 degrees with the stack?

9) In laying out a master jig plate, it is required that holes *F* and *H*, **Fig. 14**, shall be on a straight line that is $1\frac{3}{4}$ inch distant from hole *E*. The holes must also be on lines making, respectively, 40- and so-degree angles with line *EG*, drawn at right angles to the sides of the jig plate through *E*, as shown in the figure. Find the dimensions *a*, *b*, *c*, and *d*.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 14. Find Dimensions a, b, c, and d

10) Figure 15 shows a template for locating a pump body on a milling fixture, the inside contour of the template corresponding with the contour of the pump flange. Find the angle *a* from the values given.



Fig. 15. To find Angle a Having the Dimensions Given

11) Find the chordal distances as measured over plugs placed in holes located at different radii in the taximeter drive ring shown in Fig. 16. All holes are $\frac{7}{32}$ inch diameter; the angle between the center line of each pair of holes is 60 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 16. To Find the Chordal Distances of Irregularly Spaced Holes Drilled in a Taximeter Drive Ring

12) An Acme screw thread has an outside diameter of $1\frac{1}{4}$ inches and has 6 threads per inch. Find the helix angle using the pitch diameter as a base. Find, also, the helix angle if a double thread is cut on the screw.

13) What is the lead of the flutes in a $\frac{7}{8}$-inch drill if the helix angle, measured from the center line of the drill, is 27° 30′?

14) A 4-inch diameter milling cutter has a lead of 68.57 inches. What is the helix angle measured from the axis?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 10

SOLUTION OF OBLIQUE TRIANGLES

HANDBOOK Pages 94– 95

In solving problems for dimensions or angles, it is often convenient to work with oblique triangles. In an oblique triangle, none of the angles is a right angle. One of the angles may be over 90 degrees, or each of the three angles may be less than 90 degrees. Any oblique triangle may be solved by constructing perpendiculars to the sides from appropriate vertices, thus forming right triangles. The methods, previously explained, for solving right triangles, will then solve the oblique triangles. The objection to this method of solving oblique triangles is that it is a long, tedious process.

Two of the examples in the Handbook on **page 94**, which arc solved by the formulas for oblique triangles, will be solved by the right-angle triangle method. These triangles have been solved to show that all oblique triangles can be solved thus and to give an opportunity to compare the two methods. There are four classes of oblique triangles:

1) Given one side and two angles

2) Given two sides and the included angle

3) Given two sides and the angle opposite one of them

4) Given the three sides

Example 1: Solve the first example on Handbook **page 94** by the right-angle triangle method. By referring to the accompanying **Fig. 1**:

$$\text{Angle } C = 180° - (62° + 80°) = 38°$$

Draw a line DC perpendicular to AB.

In the right triangle BDC, $DC/BC = \sin 62°$.

$$\frac{DC}{5} = 0.88295;\ DC = 5 \times 0.88295 = 4.41475$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 1. Oblique Triangle Solved by Right-Angle Triangle Method

Angle $BCD = 90° - 62° = 28°$; $DCA = 38° - 28° = 10°$

$$\frac{BD}{5} = \cos 62°;\ BD = 5 \times 0.46947 = 2.34735$$

In triangle ADC, $AC/DC = \sec 10°$.

$$AC = 4.41475 \times 1.0154 = 4.4827$$

$$\frac{AD}{4.41475} = \tan 10°;\ AD = 4.41475 \times 0.17633 = 0.7785$$

$$\text{and } AB = AD + BD = 0.7785 + 2.34735 = 3.1258$$

$$C = 38°;\ b = 4.4827;\ c = 3.1258$$

Example 2: Apply the right-angle triangle method to the solution of the second example on Handbook **page 94**.
Referring to **Fig. 2**, draw a line BD perpendicular to CA.
In the right triangle BDC, $BD/9 = \sin 35°$.

$$BD = 9 \times 0.57358 = 5.16222$$

$$\frac{CD}{9} = \cos 35°;\ CD = 9 \times 0.81915 = 7.37235$$

$$DA = 8 - 7.37235 = 0.62765$$

In the right triangle BDA, $\frac{BD}{DA} = \frac{5.16222}{0.62765} = \tan A$.

Copyright 2004, Industrial Press, Inc., New York, NY

$\tan A = 8.2246$ and $A = 83°4'$

$B = 180° - (83°4' + 35°) = 61°56'$

$$\frac{BA}{BD} = \frac{BA}{5.1622} = \csc 83°4'; \qquad BA = 5.1622 \times 1.0074 = 5.2004$$

$BA = 5.1622 \times 1.0074 = 5.2004$

$A = 83°4'$; $B = 61°56'$; $C = 35°$

$a = 9$; $b = 8$; $c = 5.2004$



Fig. 2. Another Example of the Right-Angle Triangle Solution of an Oblique Triangle Equation

Use of Formulas for Oblique Triangles.— Oblique triangles are not encountered as frequently as right triangles, and, therefore, the methods of solving the latter may be fresh in the memory whereas methods for solving the former may be forgotten. All the formulas involved in the solution of the four classes of oblique triangles are derived from: (1) the law of sines; (2) the law of cosines; and (3) the sum of angles of a triangle equal 180°.

The law of sines is that, in any triangle, the lengths of the sides are proportional to the sines of the opposite angles. (See diagrams on Handbook **page 94**.)

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C} \qquad (1)$$

Solving this equation, we get:

Copyright 2004, Industrial Press, Inc., New York, NY

$\frac{a}{\sin A} = \frac{b}{\sin B}$; then $a \times \sin B = b \times \sin A$ and

$a = \frac{b \times \sin A}{\sin B}$; $\sin B = \frac{b \times \sin A}{a}$

$b = \frac{a \times \sin B}{\sin A}$; $\sin A = \frac{a \times \sin B}{b}$

In like manner, $\frac{a}{\sin A} = \frac{c}{\sin C}$ and

$a \times \sin C = c \times \text{Sin } A$; hence $\sin A = \frac{a \times \sin C}{c}$

and $\frac{b}{\sin B} = \frac{c}{\sin C}$ or $b \times \sin C = c \times \sin B$

Thus, twelve formulas may be derived. As a general rule, only **Formula (1)** is remembered, and special formulas are derived from it as required.

The law of cosines states that, in any triangle, the square of any side equals the sum of the squares of the other two sides minus twice their product multiplied by the cosine of the angle between them. These relations are stated as formulas thus:

$$a^2 = b^2 + c^2 - 2bc \times \cos A \quad \text{or} \quad a = \sqrt{b^2 + c^2 - 2bc \times \cos A} \tag{1}$$

$$b^2 = a^2 + c^2 - 2ac \times \cos B \quad \text{or} \quad b = \sqrt{a^2 + c^2 - 2ac \times \cos B} \tag{2}$$

$$c^2 = a^2 + b^2 - 2ab \times \cos C \quad \text{or} \quad c = \sqrt{a^2 + b^2 - 2ab \times \cos C} \tag{3}$$

By solving (1), $a^2 = b^2 + c^2 - 2bc \times \cos A$ for $\cos A$,

$$2bc \times \cos A = b^2 + c^2 - a^2 \quad \text{(transposing)}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$\cos A = \frac{b^2 + c^2 - a^2}{2bc}$$

In like manner, formulas for cos *B* and cos *C* may be found.



Fig. 3. Diagram Illustrating Example 3

Example 3: A problem quite often encountered in layout work is illustrated in **Fig. 3**. It is required to find the dimensions *x* and *y* between the holes, these dimensions being measured from the intersection of the perpendicular line with the center line of the two lower holes. The three center-to-center distances are the only known values.

The method that might first suggest itself is to find the angle *A* (or *B*) by some such formulas as:

$$\cos A = \frac{b^2 + c^2 - a^2}{2bc}$$

and then solve the right triangle for *y* by the formula

$$y = b \cos A$$

Formulas (1) and **(2)** can be combined as follows:

$$y = \frac{b^2 + c^2 - a^2}{2c}$$

Copyright 2004, Industrial Press, Inc., New York, NY

The value of x can be determined in a similar manner.

The second solution of this problem involves the following geometrical proposition: In any oblique triangle where the three sides are known, the ratio of the length of the base to the sum of the other two sides equals the ratio of the difference between the length of the two sides to the difference between the lengths x and y. Therefore, if $a = 14$, $b = 12$, and $c = 16$ inches, then

$$c:(a+b) = (a-b):(x-y)$$

$$16:26 = 2:(x-y)$$

$$(x-y) = \frac{26 \times 2}{16} = 3\tfrac{1}{4} \text{ inches}$$

$$x = \frac{(x+y)+(x-y)}{2} = \frac{16+3\frac{1}{4}}{2} = 9.625 \text{ inches}$$

$$y = \frac{(x+y)-(x-y)}{2} = \frac{16-3\frac{1}{4}}{2} = 6.375 \text{ inches}$$

When Angles Have Negative Values.— In the solution of oblique triangles having one angle larger than 90 degrees, it is sometimes necessary to use angles whose functions are negative. (Review Handbook **pages 4** and **99**.) Notice that for angles between 90 degrees and 180 degrees, the cosine, tangent, cotangent, and secant are negative.

Example 4: By referring to **Fig. 4**, two sides and the angle between them are shown. Find angles A and B. (See Handbook **page 94**.)

$$\tan A = \frac{4 \times \sin 20^\circ}{3 - 4 \times \cos 20^\circ} = \frac{4 \times 0.34202}{3 - 4 \times 0.93969} = \frac{1.36808}{3 - 3.75876}$$

It will be seen that in the denominator of the fraction above, the number to be subtracted from 3 is greater than 3; the numbers are therefore reversed, 3 being subtracted from 3.75876, the remainder then being negative. Hence:

$$\tan A = \frac{1.36808}{3 - 3.75876} = \frac{1.36808}{-0.75876} = -1.80305$$

The final result is negative because a positive number (1.36808) is divided by a negative number (–0.75876). The tangents of

Copyright 2004, Industrial Press, Inc., New York, NY

angles greater than 90 degrees and smaller than 180 degrees are negative. To illustrate an angle whose tangent is negative, enter the value –1.80305 in the calculator and find the corresponding angle, which –60.986558 degrees, or –60 degrees, 59 minutes, 59 seconds. Because the tangent is negative, angle *A* must be subtracted from 180 degrees, giving 119.01344 degrees, or 119 degrees, 0 minutes, 49 seconds as the angle. Now angle *B* is found from the formula,

$$B = 180° - (A + C) = 180° - (119°0′11″ + 20°)$$
$$= 180° - 139°0′11″ = 40°59′49″$$



Fig. 4. Finding Angles *A* and *B* from the Dimensions Given

When Either of Two Triangles Conforms to the Given Dimensions.— When two sides and the angle opposite one of the given sides are known, *if the side opposite the given angle is shorter than the other given side*, two triangles can be drawn, having sides of the required length (as shown by **Fig. 5**) and the required angle opposite one of the sides. The lengths of the two known sides of each triangle are 8 and 9 inches, and the angle opposite the 8-inch side is 49 degrees, 27 minutes in each triangle; but it will be seen that the angle *B* of the lower triangle is very much larger than the corresponding angle of the upper triangle, and there is a great difference in the area. When two sides and one of the opposite angles are given, the problem is capable of two solutions when (and only when) the side oppositethe given angle is shorter than the other given side. When the triangle to be calculated is drawn to scale, it

Copyright 2004, Industrial Press, Inc., New York, NY

is possible to determine from the shape of the triangle which of the two solutions applies.



Fig. 5. Diagrams Showing Two Possible Solutions of the Same Problem, Which Is to Find Angle *B*

Example 5: Find angle B, Fig. 5, from the formula, $\sin B = (b \times \sin A)/a$, where $b = 9$ inches; $A = 49$ degrees, 27 minutes; a is the side opposite angle $A = 8$ inches.

$\text{Sin}B = 9 \times 0.75984/8 = 0.85482 = \sin 58°44'34''$ or $\sin B = 121°15'36''$. The practical requirements of the problem doubtless will indicate which of the two triangles shown in Fig. 5 is the correct one.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 6. Another Example that Has Two Possible Solutions

Example 6: In **Fig. 6**, $a = 2$ inches, $b = 3$ inches, and $A = 30$ degrees. Find B.

$$\sin B = \frac{b \times \sin A}{a} = \frac{\sin 30^\circ}{2} = 0.75000$$

We find from the calculator that sine 0.75000 is the sine of 48°35′. From **Fig. 6** it is apparent, however, that B is greater than 90 degrees, and as 0.75000 is the sine not only of 48°35′, but also of 180° – 48°35′ = 131°25′, angle B in this triangle equals 131°25′.

This example illustrates how the practical requirements of the problem indicate which of two angles is correct.

PRACTICE EXERCISES FOR SECTION 10

(See *Answers to Practice Exercises For Section 10* on page 227)

1) Three holes in a jig are located as follows:

Hole No. 1 is 3.375 inches from hole No. 2 and 5.625 inches from hole No. 3; the distance between No. 2 and No. 3 is 6.250 inches. What three angles between the center lines are thus formed?

2) In **Fig. 7** is shown a triangle one side of which is 6.5 feet, and the two angles A and C are 78 and 73 degrees, respectively. Find angle B, sides b and c, and the area.

3) In **Fig. 8**, side a equals 3.2 inches, angle A, 118 degrees, and angle B, 40 degrees. Find angle C, sides b and c, and the area.

4) In **Fig. 9**, side $b = 0.3$ foot, angle $B = 35°40′$, and angle $C = 24°10′$. Find angle A, sides a and c, and the area.

5) Give two general rules for finding the areas of triangles.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Example for Practice Exercise No. 2



Fig. 8. Example for Practice Exercise No. 3



Fig. 9. Example for Practice Exercise No. 4

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 11

FIGURING TAPERS

HANDBOOK Pages **698 – 716**

The term "taper," as applied in shops and drafting rooms, means the difference between the large and small dimensions where the increase in size is uniform. Since tapering parts generally are conical, taper means the difference between the large and small diameters. Taper is ordinarily expressed as a certain number of inches per foot; thus, ½″ per ft; ¾″ per ft; etc. In certain kinds of work, taper is also expressed as a decimal part of an inch per inch, as: 0.050″ per inch. The length of the work is always measured parallel to the center line (axis) of the work, and never along the tapered surface.

Suppose that the diameter at one end of a tapering part is 1 inch, and the diameter at the other end, 1.5 inches, and that the length of the part is 1 foot. This piece, then, tapers ½ inch per foot, because the difference between the diameters at the ends is ½ inch. If the diameters at the ends of a part are 7/16 inch and ½ inch, and the length is 1 inch, this piece tapers 1/16 inch per inch. The usual problems met when figuring tapers may be divided into seven classes. The rule to be used is found on Handbook **page 715**.

Example 1: The diameter at the large end of a part is $2\frac{5}{8}$ inches, the diameter at the small end, $2\frac{3}{16}$ inches, and the length of the work, 7 inches. Find the taper per foot.

By referring to the third rule on Handbook **page 715**,

$$\text{Taper per foot} = \frac{2\frac{5}{8} - 2\frac{3}{16}}{7} \times 12 = \frac{3}{4} \text{ inch}$$

Example 2: The diameter at the large end of a tapering part is $1\frac{5}{8}$ inches, the length is $3\frac{1}{2}$ inches, and the taper is ¾ inch per foot. The problem is to find the diameter at the small end.

Copyright 2004, Industrial Press, Inc., New York, NY

By applying the fourth rule on Handbook **page 715**,

$$\text{Diameter at small end} = 1\tfrac{5}{8} - \left(\frac{\frac{3}{4}}{12} \times 3\tfrac{1}{2}\right) = 1\tfrac{13}{32}$$

Example 3: What is the length of the taper if the two end diameter are 2.875 inches and 2.542 inches, the taper being 1 inch per foot?

By applying the sixth rule on Handbook **page 715**,

$$\text{Distance between the two diameters} = \frac{2.875 - 2.542}{1} \times 12$$

$$= 4 \text{ inches nearly}$$

Example 4: If the length of the taper is 10 inches, and the taper is $\frac{3}{4}$ inch per foot, what is the taper in the given length?

By applying the last rule on Handbook **page 715**,

$$\text{Taper in given length} = \frac{\frac{3}{4}}{12} \times 10 = 0.625 \text{ inch}$$

Example 5: The small diameter is 1.636 inches, the length of the work is 5 inches, and the taper is $\frac{1}{4}$ inch per foot; what is the large diameter?

By referring to the fifth rule on Handbook **page 715**,

Example 6: Sketch *A*, **Fig. 1**, shows a part used as a clamp bolt. The diameter, $3\frac{1}{4}$ inches, is given 3 inches from the large end of the taper. The total length of the taper is 10 inches. The taper is $\frac{3}{8}$ inch per foot. Find the diameter at the large and small ends of the taper.

First find the diameter of the large and using the fifth rule on Handbook **page 715**.

$$\text{Diameter at large end} = \left(\frac{\frac{3}{8}}{12} \times 3\right) + 3\tfrac{1}{4} = 3\tfrac{11}{32} \text{ inches}$$

To find the diameter at the small and, use the fourth rule on Handbook **page 715**.

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Diameter at small end} = 3\tfrac{11}{32} - \left(\frac{\frac{3}{8}}{12} \times 10\right) = 3\tfrac{1}{32} \text{ inches}$$



Fig. 1. Illustrations for Examples 6 and 7

Example 7: At *B*, **Fig. 1**, is shown a taper master gage intended for inspecting taper ring gages of various dimensions. The smallest diameter of the smallest ring gage is 1¾ inches, and the largest diameter of the largest ring gage is 2¾ inches. The taper is 1½ inches per foot. It is required that the master gage extend 1 inch outside of the ring gages at both the small and the large ends, when these ring gages are tested. How long should the taper be on the master gage?

The sixth rule on Handbook **page 715** may be applied here.

$$\text{Distance between the two diameters} = \frac{2\frac{3}{4} - 1\frac{3}{4}}{1\frac{1}{2}} \times 12$$

$$= 8 \text{ inches}$$

$$\text{Total length of taper} = 8 + 2 = 10 \text{ inches}$$

Table for Converting Taper per Foot to Degrees.— Some types of machines, such as milling machines, are graduated in degrees, making it necessary to convert the taper per foot to the corresponding angle in degrees. This conversion is quickly done by means of the table, Handbook **page 715**.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 8: If a taper of 1½ inches per foot is to be milled on a piece of work, at what angle must the machine table be set if the taper is measured from the axis of the work?

By referring to the table on Handbook **page 715**, the angle corresponding to a taper of 1½ inches to the foot is 3° 34′ 35″ as measured from the center line.

Note that the taper per foot varies directly as *the tangent of one-half the included angle*. Two mistakes frequently made in figuring tapers are assuming that the taper per foot varies directly as the included angle or that it varies directly as the tangent of the included angle. In order to verify this point, refer to the table on Handbook **page 714**, where it will be seen that the included angle for a taper of 4 inches per foot (18° 55′ 29″) is not twice the included angle for a taper of 2 inches per foot (9° 31′ 38″). Neither is the tangent of 18° 55′ 29″ (0.3428587) twice the tangent of 9° 31′ 38″ (0.1678311).

Tapers for Machine Tool Spindles.— The holes in machine tool spindles, for receiving tool shanks, arbors, and centers, are tapered to ensure a tight grip, accuracy of location, and to facilitate removal of arbors, cutters, etc. The most common tapers are the Morse, the Brown & Sharpe, and the Jarno. The Morse has been very generally adopted for drilling machine spindles. Most engine lathe spindles also have the Morse taper, but some lathes have the Jarno or a modification of it, and others, a modified Morse taper, which is longer than the standard. A standard milling machine spindle was adopted in 1927 by the milling machine manufacturers of the National Machine Tool Builders' Association. A comparatively steep taper of 3½ inches per foot was adopted in connection with this standard spindle to ensure instant release of arbors. Prior to the adoption of the standard spindle, the Brown & Sharpe taper was used for practically all milling machines and is also the taper for dividing-head spindles. There is considerable variation in grinding machine spindles. The Brown & Sharpe taper is the most common, but the Morse and the Jarno have also been used. Tapers of ⅝ inch per foot and ¾ inch per foot also have been used to some extent on miscellaneous classes of machines requiring a taper hole in the spindle.

Copyright 2004, Industrial Press, Inc., New York, NY

PRACTICE EXERCISES FOR SECTION 11

(See *Answers to Practice Exercises For Section 11* on page 227)

1) What tapers, per foot, are used with the following tapers: a) Morse taper; b) Jarno taper; c) milling machine spindle; d) and taper pin?

2) What is the taper per foot on a part if the included angle is 10° 30′; 55° 45′?

3) In setting up a taper gage like that shown on Handbook **page 713**, what should be the center distance between 1.75-inch and 2-inch disks to check either the taper per foot or angle of a No. 4 Morse taper?

4) If it is required to check an angle of 14½°, using two disks in contact, and the smaller disk is 1-inch diameter, what should the diameter of the larger disk be?

5) What should be the center distance, using disks of 2-inch and 3-inch diameter, to check an angle of 18° 30′ if the taper is measured from one side?

6) In grinding a reamer shank to fit a standard No. 2 Morse taper gage, it was found that the reamer stopped ⅜ inch short of going into the gage to the gage mark. How much should be ground off the diameter?

7) A milling machine arbor has a shank 6½ inches long with a No. 10 B. & S. taper. What is the total taper in this length?



Fig. 2. Finding Angle *a* by Means of a Sine Bar and Handbook Instructions

Copyright 2004, Industrial Press, Inc., New York, NY

8) A taper bushing for a grinding machine has a small inside diameter of ⅞ inch. It is 3 inches long with ½-inch taper per toot. Find the large inside diameter.

9) If a 5-inch sine bar is used for finding the angle of the tapering bloc *A* (**Fig. 2**), and the heights of the sine-bar plug are as shown, find the corresponding angle *a* by means of the instructions beginning on Handbook **page 696**.

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 12

TOLERANCES AND ALLOWANCES FOR MACHINE PARTS

HANDBOOK Pages 645 – 690

In manufacturing machine parts according to modern methods, certain maximum and minimum dimensions are established, particularly for the more important members of whatever machine or mechanism is to be constructed. These limiting dimensions serve two purposes: they prevent both unnecessary accuracy and excessive inaccuracies. A certain degree of accuracy is essential to the proper functioning of the assembled parts of a mechanism, but it is useless and wasteful to make parts more precise than needed to meet practical requirements. Hence, the use of proper limiting dimensions promotes efficiency in manufacturing and ensures standards of accuracy and quality that are consistent with the functions of the different parts of a mechanical device.

Parts made to specified limits usually are considered interchangeable or capable of use without selection, but there are several degrees of interchangeability in machinery manufacture. Strictly speaking, interchangeability consists of making the different parts of a mechanism so uniform in size and contour that each part of a certain model will fit any mating part of the same model, regardless of the lot to which it belongs or when it was made. However, as often defined, interchangeability consists in making each part fit any mating part in a certain series; that is, the interchangeability exists only in the same series. Selective assembly is sometimes termed interchangeability, but it involves a selection or sorting of parts as explained later. It will be noted that the strict definition of interchangeability does not imply that the parts must always be assembled without handwork, although that is usually considered desirable. It does mean, however, that when whatever process finishes the mating parts, they must assemble and function properly without fitting individual parts one to the other.

Copyright 2004, Industrial Press, Inc., New York, NY

When a machine having interchangeable parts has been installed, possibly at some distant point, a broken part can readily be replaced by a new one sent by the manufacturer, but this feature is secondary as compared with the increased efficiency in manufacturing on an interchangeable basis. To make parts interchangeable, it is necessary to use gages and measuring tools, to provide some system of inspection, and to adopt suitable tolerances. Whether absolute interchangeability is practicable or not may depend upon the tolerances adopted the relation between the different parts, and their form.

Meanings of the Terms "Limit", "Tolerance", and "Allowance".— The terms "limit" and "tolerance" and "allowance" are often used interchangeably, but each of these three terms has a distinct meaning and refers to different dimensions. As shown by **Fig. 1**, the *limits* of a hole or shaft are its diameters. *Tolerance* is the difference between two *limits* and limiting dimensions of a given part, and the term means that a certain amount of error is tolerated for practical reasons. *Allowance* is the difference between limiting dimensions on mating parts that are to be assembled either loosely or tightly, depending upon the amount allowed for the fit.

Example 1: Limits and fits for cylindrical parts are given starting on **page 651** in the Handbook. These data provide a series of standard types and classes of fits. From the table on **page 658**, establish limits of size and clearance for a 2-inch diameter hole and shaft for a class RC-1 fit (whole H5, shaft g4).

$$\begin{aligned}
\text{Max. hole} &= 2 + 0.0005 = 2.0005\\
\text{Min. hole} &= 2 - 0 = 2\\
\text{Max. shaft} &= 2 - 0.0004 = 1.9996\\
\text{Min. shaft} &= 2 - 0.0007 = 1.9993\\
\text{Min. allow.} &= \text{min. hole} - \text{max. shaft} = 2 - 1.996 = 0.0004\\
\text{Max. allow.} &= \text{max. hole} - \text{min. shaft}\\
&= 2.0005 - 1.9993 = 0.0012
\end{aligned}$$

Example 2: Beginning on Handbook **page 1734**, there are tables of dimensions for the Standard Unified Screw Thread Series—Class 1A, 2A, and 3A and B Fits. Determine the pitch-diameter tolerance of both screw and nut and the minimum and maximum

Copyright 2004, Industrial Press, Inc., New York, NY

allowance between screw and nut at the pitch diameter, assuming that the nominal diameter is 1 inch, the pitch is 8 threads per inch, and the fits are Class 2A and 2B for screw and nut, respectively.

Diagram Showing Differences Among "Limit," "Tolerance," and "Allowance"



Fig. 1.

Limits

B = maximum limit of bore

b = minimum limit of bore

S = maximum limit of shaft

s = minimum limit of shaft

Tolerances

$B - b$ = maximum tolerance of bore

$S - s$ = maximum tolerance of shaft

Allowances

$B - s$ = maximum allowance, or if s is greater than B (as for tight or forced fits) then $s - B$ = minimum allowance for fit.

$b - S$ = minimum allowance, or if S is greater than b (as for tight or forced fits) then S − b = maximum allowance for fit.

The maximum pitch diameter or limit of the screw = 0.9168, and the minimum pitch diameter = 0.9100; hence, the tolerance = 0.9168 − 0.9100 = 0.0068 inch. The nut tolerance = 0.9276 − 0.9100 = 0.0176 inch. The maximum allowance for medium fit = maximum pitch diameter of nut − minimum pitch diameter of screw = 0.9276 − 0.9168 = 0.0108 inch. The minimum allowance = minimum pitch diameter of nut − maximum pitch diameter of screw = 0.9188 − 0.9168 = 0.0020.

Relation of Tolerances to Limiting Dimensions and How Basic Size Is Determined.— The absolute limits of the various dimensions and surfaces indicate danger points, in as much as parts made beyond these limits are unserviceable. A careful analysis of a mechanism shows that one of these danger points is more sharply

Copyright 2004, Industrial Press, Inc., New York, NY

defined than the other. For example, a certain stud must always assemble into a certain hole. If the stud is made beyond its maximum limit, it may be too large to assemble. If it is made beyond its minimum limit, it may be too loose or too weak to function. The absolute maximum limit in this case may cover a range of 0.001 inch, whereas the absolute minimum limit may have a range of at least 0.004 inch. In this case the maximum limit is the more sharply defined.



Fig. 2. Graphic Illustration of the Meaning of the Term Basic Size or Dimension

The basic size expressed on the component drawing is that limit that defines the more vital of the two danger points, while the tolerance defines the other. In general, the basic dimension of a male part such as a shaft is the maximum limit that requires a minus tolerance. Similarly, the basic dimension of a female part is the minimum limit requiring a plus tolerance, as shown in **Fig. 2**. There are, however, dimensions that define neither a male nor a female surface, such as, for example, dimensions for the location of holes. In a few such instances, a variation in one direction is less dangerous than a variation in the other. Under these conditions, the basic dimension represents the danger point, and the unilateral tolerance permits a variation only in the less dangerous direction. At other times, the conditions are such that any variation from a fixed point In either direction is equally dangerous. The basic size then represents this fixed point, and tolerances on the drawing are bilateral

Copyright 2004, Industrial Press, Inc., New York, NY

and extend equally in both directions. (See Handbook page 645 for explanation of unilateral and bilateral tolerances.)

When Allowance Provides Clearance Between Mating Parts.— When one part must fit freely into another part like a shaft in its bearing, the allowance between the shaft and bearing represents a clearance space. It is evident that the amount of clearance vanes widely for different classes of work. The minimum clearance should be as small as will permit the ready assembly and operation of the parts, while the maximum clearance should be as great as the functioning of the mechanism will allow. The difference between the maximum and minimum clearances defines the extent of the tolerances. In general, the difference between the basic sizes of companion parts equals the minimum clearance (see Fig. 3), and the term "allowance," if not defined as maximum or minimum, is quite commonly applied to the minimum clearance.



Fig. 3. Graphic Illustration of the Meaning of the Terms Maximum and Minimum Clearance

When "Interference of Metal" Is Result of Allowance.— If a shaft or pin is larger in diameter than the hole into which it is forced, there is, of course, interference between the two parts. The metal surrounding the hole is expanded and compressed as the shaft or other part is forced into place.

Engine crankpins, car axles, and various other parts are assembled in this way (see paragraph *Allowance for Forced Fits,* Hand-

Copyright 2004, Industrial Press, Inc., New York, NY

book **page 647**). The force and shrink fits in Table 11 (starting on Handbook **page 663**) all represent interference of metal.

If interchangeable parts are to be forced together, the minimum interference establishes the danger point. Thus, for force fits, the basic dimension of the shaft or pin is the minimum limit requiring a plus tolerance, and the basic dimension of the hole is the maximum limit requiring a minus tolerance, (See **Fig. 4**.)

Obtaining Allowance by Selection of Mating Parts.— The term "selective assembly" is applied to a method of manufacturing that is similar in many of its details to interchangeable manufacturing. In selective assembly, the mating parts are sorted according to size and assembled or interchanged with little or no further machining nor hand work.



Fig. 4. Illustration of the Meaning of the Terms Maximum and Minimum Interference

The chief purpose of manufacturing by selective assembly is the production of large quantities of duplicate parts as economically as possible. As a general rule, the smaller the tolerances, the more exacting and expensive will be the manufacturing processes. However, it is possible to use comparatively large tolerances and then reduce them, in effect, by selective assembly, provided the quantity of parts is large enough to make such selective fitting possible. To illustrate, the table that follows shows a plug or stud that has a plus tolerance of 0.001 inch and a hole that also has a plus tolerance of 0.001 inch. Assume that this tolerance of 0.001 inch repre-

Copyright 2004, Industrial Press, Inc., New York, NY

sents the normal size variation on each part when manufactured efficiently. With this tolerance, a minimum plug in a maximum hole would have a clearance 0.2510 – 0.2498 = 0.0012 inch, and a maximum plug in a minimum hole would have a "metal interference" of 0.2508 – 0.2500 = 0.0008 inch. Suppose, however, that the clearance required for these parts must range from zero to 0.0004 inch. This reduction can be obtained by dividing both plugs and holes into five groups. (See below.) Any studs in Group *A*, for example, will assemble in any hole in Group *A*, but the studs in one group will not assemble properly in the holes in another group. When the largest stud in Group *A* is assembled in the smallest hole in Group *A*, the clearance equals zero. When the smallest stud in Group *A* is assembled in the largest hole in Group *A*, the clearance equals 0.0004 inch. Thus, in selective assembly manufacturing, there is a double set of limits, the first being the manufacturing limits and the second the assembling limits. Often, two separate drawings are made of a part that is to be graded before **Fig. 3**. assembly. One shows the manufacturing tolerances only, so as not to confuse the operator, and the other gives the proper grading information.



GROUP A	0.2498″	+0.002″ −0.0000″	GROUP A	0.2500″	+0.002″ −0.0000″
GROUP B	0.2500″	+0.002″ −0.0000″	GROUP B	0.2502″	+0.002″ −0.0000″
GROUP C	0.2502″	+0.002″ −0.002″	GROUP C	0.2504″	+0.002″ −0.002″
GROUP D	0.2504″	+0.0000″ −0.002″	GROUP D	0.2506″	+0.0000″ −0.002″
GROUP E	02506″	+0.0000″ −0.002″	GROUP E	0.2508″	+0.0000″ −0.002″

Example 3: Data for force and shrink fits are given in the table starting on **page 663** in the Handbook. Establish the limits of size and interference of the hole and shaft for a Class FN-1 fit of 2-inch diameter.

Copyright 2004, Industrial Press, Inc., New York, NY

$$\text{Max. hole} = 2 + 0.0007 = 2.0007; \text{ min. shaft} = 2 - 0 = 2$$

$$\text{Max. shaft} = 2 + 0.0018 = 2.0018; \text{ min. shaft} = 2 + 0.0013 = 2.0013$$

In the second column of the table, the minimum and maximum interference are given as 0.0006 and 0.0018 inch, respectively, for a FN-1 fit of 2-inch diameter. For a "selected" fit, shafts are selected that are 0.0012 inch larger than the mating holes; that is, for any mating pair, the shaft is larger than the hole by an amount midway between the minimum (0.0006-inch) and maximum (0.0018 inch) interference.

Dimensioning Drawings to Ensure Obtaining Required Tolerances.— In dimensioning the drawings of parts requiring tolerances, there are certain fundamental rules that should be applied.

Rule 1: In interchangeable manufacturing there is only one dimension (or group of dimensions) in the same straight line that can be controlled within fixed tolerances. This dimension is the distance between the cutting surface of the tool and the locating or registering surface of the part being machined. Therefore, it is incorrect to locate any point or surface with tolerances from more than one point in the same straight line.

Rule 2: Dimensions should be given between those points that it is essential to hold in a specific relation to each other. Most dimensions, however, are relatively unimportant in this respect. It is good practice to establish common location points in each plane and to give, as far as possible, all such dimensions from these points.

Rule 3: The basic dimensions given on component drawings for interchangeable parts should he, except for force fits and other unusual conditions, the "maximum metal" size (maximum shaft or plug and minimum hole). The direct comparison of the basic sizes should check the danger zone, which is the minimum clearance condition in most instances. It is evident that these sizes are the most important ones, as they control the interchangeability, and they should be the first determined. Once established, they should remain fixed if the mechanism functions properly, and the design is unchanged. The direction of the tolerances, then, would be such as to recede from the danger zone. In most instances, this direc-

Copyright 2004, Industrial Press, Inc., New York, NY

tionality means that the direction of the tolerances is such as will increase the clearance. For force fits, the basic dimensions determine the minimum interference, and the tolerances limit the maximum interference.

Rule 4: Dimensions must not be duplicated between the same points. The duplication of dimensions causes much needless trouble, due to changes being made in one place and not in the others. It is easier to search a drawing to find a dimension than it is to have them duplicated and more readily found but inconsistent.

Rule 5: As far as possible, the dimensions on comparison parts should be given from the same relative locations. Such a procedure assists in detecting interference's and other improper conditions.

In attempting to work in accordance with general laws or principles, one other elementary rule should always be kept in mind. Special requirements need special consideration. The following detailed examples are given to illustrate the application of the five rules and to indicate results of their violation.

Violations of Rules for Dimensioning.— **Fig. 5** shows a very common method of dimensioning a part such as the stud shown, but one that is bad practice as it violates the first and second rules. The dimensions given for the diameters are correct, so they are eliminated from the discussion. The dimensions given for the various lengths are wrong: First, because they give no indication as to the essential lengths; second, because of several possible sequences of operations, some of which would not maintain the specified conditions.

Fig. 6 shows one possible sequence of operations indicated alphabetically. If we first finish the dimension *a* and then finish *b*, the dimension *c* will be within the specified limits. However, the dimension *c* is then superfluous. **Fig. 7** gives another possible sequence of operations. If we first establish *a*, and then *b*, the dimension *c* may vary 0.030 instead of 0.010 inch as is specified in **Fig. 5**. **Fig. 8** gives a third possible sequence of operations. If we first finish the overall length *a*, and then the length of the body *b*, the stem *c* may vary 0.030 inch instead of 0.010 inch as specified in **Fig. 5**.

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 5. Common but Incorrect Method of Dimensioning



Fig. 6. One Interpretation of Dimensioning in Fig. 5

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 7. Another Interpretation of Dimensioning in Fig. 5



Fig. 8. A Third Interpretation of Dimensioning in Fig. 5

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 9. Correct Dimensioning if Length of Body and Length of Stem Are Most Important



Fig. 10. Correct Dimensioning if Length of Body and Overall Length Are Most Important

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 11. Correct Dimensioning if Overall Length and Length of Stem Are Most Important

If three different plants were manufacturing this part, each one using a different sequence of operations, it is evident from the foregoing that a different product would be received from each plant. The example given is the simplest one possible. As the parts become more complex, and the number of dimensions increases, the number of different combinations possible and the extent of the variations in size that will develop also increase.

Fig. 9 shows the correct way to dimension this part if the length of the body and the length of the stem are the essential dimensions. **Fig. 10** is the correct way if the length of the body and the length overall are the most important. **Fig. 11** is correct if the length of the stem and the length overall are the most important. If the part is dimensioned in accordance with **Fig. 9**, **Fig. 10**, or **Fig. 11**, then the product from any number of factories should be alike.

PRACTICE EXERCISES FOR SECTION 12

(See *Answers to Practice Exercises For Section 12* on page 228)

1) What factors influence the allowance for a forced fit?

2) What is the general practice in applying tolerances to center distances between holes?

3) A 2-inch shaft is to have a tolerance of 0.003 inch on the diameter. Show, by examples, three ways of expressing the shaft dimensions.

Copyright 2004, Industrial Press, Inc., New York, NY

4) In what respect does a bilateral tolerance differ from a unilateral tolerance? Give an example that demonstrates this difference.

5) What is the relation ship between gagemaker's tolerance and workplace tolerance?

6) Name the different class of fits for screw thread included in the American standards.

7) How does the Unified screw for screw threads differ from the former American standard with regard to clearance between mating parts? With regard toward working tolerance?

8) Under what conditions is one limiting dimension or "limit" also a basic dimension?

9) What do the letter symbols RC, LC, LN, signify with regard American Standards

10) According to table at the bottom of Handbook **page 652**, broaching will produce work within tolerance grades 5 through 8. What does this mean in terms of thousands of an inch, considering a 1-inch diameter broached hole?

11) Does surface roughness affect the ability to work within the tolerance grades specified in Exercise 10?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 13

USING STANDARDS DATA AND INFORMATION

(References to Standards appear throughout the HANDBOOK)

Standards are needed in metalworking manufacturing to establish dimensional and physical property limits for parts that are to be interchangeable. Standards make it possible for parts such as nuts, screws, bolts, splines, gears, etc., to be manufactured at different times and places with the assurance that they will meet assembly requirements. Standards are also needed for tools such as twist drills, reamers, milling cutters, etc., so that only a given number of sizes need be made available to cover a given range and to ensure adequate performance. Also, performance standards often are established to make sure that machines and equipment will satisfy their application requirements.

A standard may be established by a company on a limited basis for its own use. An industry may find that a standard is needed, and its member companies working through their trade association come to an agreement as to what requirements should be included. Sometimes, industry standards sponsored by a trade association or an engineering society become acceptable by a wide range of consumers, manufacturers, and government agencies as national standards and are made available through a national agency such as the American National Standards Institute (ANSI). More and more countries are coming to find that standards should be universal and are working to this end through the International Standards Organization (ISO).

In the United States and some other English-speaking countries, there are two systems of measurement in use: the inch system and the metric system. As a result, standards for, say, bolts, nuts, and screws have been developed for both inch and metric dimensions as will be found in Machinery's Handbook. However, an increasing number of multinational corporations and their local suppliers

Copyright 2004, Industrial Press, Inc., New York, NY

are finding it prohibitively expensive to operate with two systems of measurements and standards. Thus, in order to use available expertise in one plant location, a machine may be designed in an "inch" nation only to be produced later in a "metric" country or vice versa. This situation generates additional costs in the conversion of drawings, substitution of equivalent standard steel sizes and fasteners, and conversion of testing and material specifications, etc. Because of these problems, more and more standards are being developed in the United States and throughout the world that are based, wherever practicable, upon ISO standards.

In the Handbook, the user will find that a large number of both inch and metric standards data and information are provided. It should be noted that at the head of each table of standards data the source is given in parentheses, such as (ANSI B18.3-1982). ANSI indicates the American National Standards Institute; B18.3 is the identifying number of the standard; and 1982 is the date the standard was published, or revised, and became effective.

Generally, new products are produced to the metric standards; older products and replacement parts for them may require reference to older inch standards, and some products such as inch-unit pipe threads are considered as standard for the near future because of widespread use throughout the world.

Important Objectives of Standardization.— The purpose of standardization is to manufacture goods for less direct and indirect costs and to provide finished products that meet the demands of the marketplace. A more detailed description of the objectives could be as follows:

Lower the production costs when the aim is to:

1) Facilitate and systematize the work of skilled designers;

2) Ensure optimum selection of materials, components, and semifinished products;

3) Reduce stocks of materials, semifinished products, and finished products;

4) Minimize the number of different products sold; and

5) Facilitate and reduce the cost of procurement of purchased goods.

Meet the demands of the market place, when the objective is to:

Copyright 2004, Industrial Press, Inc., New York, NY

1) Conform to regulations imposed by government and trade organizations;

2) Stay within safety regulations set forth by governments; and

3) Facilitate interchangeability requirements with existing products.

Standardization Technique.— The two commonly used basic principles for the preparation of a standard are:

1) Analytical standardization – Standard developed from scratch.

2) Conservative standardization – Standard based, so far as is possible, on existing practice.

In practice, it appears that a standard cannot be prepared completely by one or the other of the two methods but emerges from a compromise between the two. The goal of the standardization technique, then, should be to utilize the basic material and the rules and the aids available in such a way that a valid and practical compromise solution is reached.

The basic material could consist of such items as former company standards, vendor catalog data, national and international standards, requirements of the company's customers, and competitor's material. Increasingly important are the national and international standards in existence on the subject; they should always play an important part in any conservative standardization work. For example, it would be foolish to create a new metric standard without first considering some existing European metric standards.

Standards Information in the Handbook.— Among the many kinds of material and data to be found in the Handbook, the user will note that extensive coverage is given to standards of several types: American National Standards, British Standards, ISO Standards, engineering society standards, trade association standards, and, in certain instances, company product standards. Both inch and metric system standards are given wherever appropriate. Inch dimension standards sometimes are provided only for use during transition to metric standards or to provide information for the manufacture of replacement parts.

In selecting standards to be presented in the Handbook, the editors have chosen those standards most appropriate to the needs of Handbook users. Text, illustrations, formulas, tables of data, and

Copyright 2004, Industrial Press, Inc., New York, NY

examples have been arranged in the order best suitable for direct and quick use. As an example of this type of presentation, the section on bevel gearing, Handbook starting on **page 2081**, begins with text material that provides the basis for understanding information presented in the AGMA standards; the illustrations on Handbook **pages 2086** and **2087** provide visual definition of essential parts and dimensions of a bevel gear; the formulas on Handbook **page 2075** show how to calculate dimensions of milled bevel gears; the tables on Handbook, starting on **page 2089** give numbers of formed cutters used to mill teeth in mating bevel gear and pinion sets with shafts at right angles; and finally, the worked-out examples beginning on Handbook **page 2091** give a step-by-step procedure for selecting formed cutters for milling bevel gears. Also, where combinations of tables and formulas are given, the formulas have been arranged in the best sequence for computation with the aid of a pocket calculator.

"Soft" Conversion of Inch to Metric Dimensions.— The dimensions of certain products, when specified in inches, may be converted to metric dimensions, or vice versa, by multiplying by the appropriate conversion factor so that the parts can be fabricated either to inch or to the equivalent metric dimensions and still be fully interchangeable. Such a conversion is called a "soft" conversion. An example of a "soft" conversion is available on Handbook **page 2298**, which gives the inch dimensions of standard lockwashers for ball bearings. The footnote to the table indicates that multiplication of the tabulated inch dimensions by 25.4 and rounding the results to two decimal places will provide the equivalent metric dimensions.

"Hard" Metric or Inch Standard Systems.— In a "hard" system, those dimensions in the system that have been standardized cannot be converted to another dimensional system that has been standardized independently of the first system. As stated in the footnote on **page 2176** of the Handbook, "In a 'hard' system the tools of production, such as hobs, do not bear a usable relation to the tools in another system; i.e., a 10 diametral pitch hob calculates to be equal to a 2.54 module hob in the metric module system, a hob that does not exist in the metric standard."

Copyright 2004, Industrial Press, Inc., New York, NY

Interchangeability of Parts Made to Revised Standards.— Where a standard has been revised, there may still remain some degree of interchangeability between older parts and those made to the new standard. As an example, starting on **page 2167** of the Handbook, there are two tables showing which of the internal and external involute splines made to older standards will mate with those made to newer standards.

PRACTICE EXERCISES FOR SECTION 13

(See *Answers to Practice Exercises For Section 13* on page 229)

1) What is the breaking strength of a 6 × 7 fiber-core wire rope $\frac{1}{4}$ inch in diameter if the rope material is mild plow steel?

2) What factor of safety should be applied to the rope in Exersise 1?

3) How many carbon steel balls of $\frac{1}{4}$-inch diameter would weigh 1 lb?

4) For a 1-inch diameter of shaft, what size square key is appropriate?

5) Find the hole size needed for a $\frac{5}{32}$-inch standard cotter pin.

6) Find the limits of size for a 0.1250-inch diameter hardened and ground dowel pin.

7) For a 3AM1-17 retaining ring (snap ring), what is the maximum allowable speed of rotation?

8) Find the hole size required for a type AB steel thread-forming screw of number 6 size in 0.105-inch-thick stainless steel.

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 14

STANDARD SCREW AND PIPE THREADS

HANDBOOK Pages **1725** – **1919**

Different screw-thread forms and standards have been originated and adopted at various times, either because they were considered superior to other forms or because of the special requirements of screws used for a certain class of work.

A standard thread conforms to an adopted standard with regard to the form or contour of the thread itself and as to the pitches or numbers of threads per inch for different screw diameters.

The United States Standard formerly used in the United States was replaced by an American Standard having the same thread form as the former standard and a more extensive series of pitches, as well as tolerances and allowances for different classes of fits. This American Standard was revised in 1949 to include a Unified Thread Series, which was established to obtain screw-thread interchangeability among the United Kingdom, Canada, and the United States.

The Standard was revised again in 1959. The Unified threads are now the standard for use in the United States and the former American Standard threads are now used only in certain applications where the changeover in tools, gages, and manufacturing has not been completed. The differences between Unified and the former National Standard threads are explained on **pages 1725** and **1732** in the Handbook.

As may be seen in the table on Handbook **page 1735**, the Unified Series of screw threads consists of three standard series having graded pitches (UNC, UNF, and UNEF) and eight standard series of uniform (constant) pitch. In addition to these standard series. There are places in the table beginning on Handbook **page 1736** where special threads (UNS) are listed. These UNS threads are for use only if standard series threads do not meet requirements.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 1: The table on Handbook **page 1763** shows that the pitch diameter of a 2-inch screw thread is 1.8557 inches. What is meant by the term "pitch diameter" as applied to a screw thread and how is it determined?

According to a definition of "pitch diameter" given in connection with American Standard screw threads, the pitch diameter of a straight (nontapering) screw thread is the diameter of an imaginary cylinder, the surface of which would pass through the threads at such points as to make equal the width of the threads and the width of the spaces cut by the surface of the cylinder.

The basic pitch diameter equals the basic major (outside) diameter minus two times the addendum of the external thread (Handbook **page 1734**), so the basic pitch diameter for the 2-inch example, with 4½ threads per inch, is $2.00 - 2 \times 0.07217 = 1.8557$ inches.

Example 2: The tensile strength of a bolt, 3½ inches in diameter at a stress of 6000 pounds per square inch may be calculated by means of the formulas on Handbook **page 1510**. This formula uses the largest diameter of the bolt, avoiding the need to take account of the reduced diameter at the thread root, and gives a tensile strength of 35, 175 pounds for the conditions noted.

If the second formula on **page 1510**, based on the area of the smallest diameter, is used for the same bolt and stress, and the diameter of the thread root is taken as 3.1 inches, then the tensile strength is calculated as 40,636 pounds. The difference in these formulas is that the first uses a slightly greater factor of safety than the second, taking account of possible variations in thread depth.

Example 3: Handbook **page 1899** gives formulas for checking the pitch diameter of screw threads by the three-wire method (when effect of lead angle is ignored). Show how these formulas have been derived using the one for the American National Standard Unified thread as an example.

It is evident from the diagram, **Fig. 1**, that:

$$M = D - 2z + 2x \qquad (1)$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$x = R + \frac{R}{\sin a} \text{ and } 2x = 2R + \frac{2R}{0.5}\text{; hence,}$$

$$2x = \frac{(2 \times 0.5 + 2)R}{0.5} = \frac{3R}{0.5} = 6R = 3W$$

$$z = d + d_1 = 0.6495P + f \times \cot\alpha$$



Fig. 1. Diagram Illustrating the Derivation of Formulas for Three-Wire Measurements of Screw-Thread Pitch Diameters

$$f = 0.0625P\text{; therefore,}$$

$$z = 0.6495P + 0.10825P = 0.75775P$$

If, in **Formula (1)**, we substitute the value of 2z or $2 \times 0.75775P$ and the value of 2x, we have:

$$M = D - 1.5155 \times P + 3W \qquad (2)$$

This **Formula (2)** is the one found in previous editions of the Handbook. In the 22nd and subsequent editions of the Handbook use of the outside diameter D in **Formula (2)** above was eliminated to provide a formula in terms of the pitch diameter E. Such a formula is useful for finding the wire measurement corresponding to the actual pitch diameter, whether it be correct, undersize, or oversize.

Copyright 2004, Industrial Press, Inc., New York, NY

According to the last paragraph of **Example 1**, above, $E = D - 2 \times$ thread addendum. On Handbook **page 1734**, the formula for thread addendum given at the top of the last column is $0.32476P$. Therefore, $E = D - 2 \times 0.32476P$, or, transposing this formula, $D = E + 2 \times 0.32476P = E + 0.64952P$. Substituting this value of D into **Formula (2)** gives: $M = E + 0.64952P - 1.5155P + 3W = E - 0.8660P + 3W$, which is the current Handbook formula.

Example 4: On Handbook **page 1906**, a formula is given for checking the angle of a screw thread by a three-wire method. How is this formula derived? By referring to the diagram, **Fig. 2**,

$$\sin a = \frac{W}{S} \tag{1}$$

If D = diameter of larger wires and d = diameter of smaller wires,

$$W = \frac{D - d}{2}$$

If B = difference in measurement over wires, then the difference S between the centers of the wires is:

$$S = \frac{B - (D - d)}{2}$$



Fig. 2. Diagram Illustrating the Derivation of Formula for Checking the Thread Angle by the Three-Wire System

Copyright 2004, Industrial Press, Inc., New York, NY

By inserting these expressions for W and S in **Formula (1)** and canceling, the formula given in the Handbook is obtained if A is substituted for $D - d$.

$$\sin a = \frac{A}{B - A}$$

Example 5: A vernier gear-tooth caliper (like the one shown on Handbook **page 2052**) is to be used for checking the width of an Acme screw by measuring squarely across or perpendicular to the thread. Since standard screw-thread dimensions are in the plane of the axis, how is the width square or normal to the sides of the thread determined? Assume that the width is to be measured at the pitch line and that the number of threads per inch is two.

The table on Handbook **page 1827** shows that for two threads per inch, the depth is 0.260 inch; hence, if the measurement is to be at the pitch line, the vertical scale of the caliper is set to (0.260 – 0.010) ÷ 2 = 0.125 inch. The pitch equals

$$\frac{1}{\text{No. of threads per inch}} = \tfrac{1}{2} \text{ inch}$$

The width A, **Fig. 3**, in the plane of the axis equals ½ the pitch, or ¼ inch. The width B perpendicular to the sides of the thread = width in axial plane × cosine helix angle.



Fig. 3. Determining the Width Perpendicular to the sides of a Thread at the Pitch Line

(The helix angle, which equals angle a, is based upon the pitch diameter and is measured from a plane perpendicular to the axis of the screw thread.) The width A in the plane of the axis represents

Copyright 2004, Industrial Press, Inc., New York, NY

the hypotenuse of a right triangle, and the required width B equals the side adjacent; hence width $B = A \times$ cosine of helix angle. The angle of the thread itself (29° for an Acme Thread) does not affect the solution.

Width of Flat End of Unified Screw-Thread and American Standard Acme Screw-Thread Tools.— The widths of the flat or end of the threading tool for either of these threads may be measured by using a micrometer as illustrated at *A*, **Fig. 4**. In measuring the thread tool, a scale is held against the spindle and anvil of the micrometer, and the end of the tool is placed against this scale. The micrometer is then adjusted to the position shown and 0.2887 inch subtracted from the reading for an American Standard screw-thread tool. For American Standard Acme threads, 0.1293 inch is subtracted from the micrometer reading to obtain the width of the tool point. The constants (0.2887 and 0.1293), which are subtracted from the micrometer reading, are only correct when the micrometer spindle has the usual diameter of 0.25 inch.

An ordinary gear-tooth vernier caliper also may be used for testing the width of a thread tool point, as illustrated at *B*. If the measurement is made at a vertical distance x of $\frac{1}{4}$ inch from the points of the caliper jaws, the constants previously given for American Standard caliper reading to obtain the actual width of the cutting end of the tool.



Fig. 4. Measuring Width of Flat on Threading Tool (A) with a Micrometer; (B) with a Gear-Tooth Vernier

Example 6: Explain how the constants 0.2887 and 0.1293 referred to in a preceding paragraph are derived and deduce a general rule

Copyright 2004, Industrial Press, Inc., New York, NY

applicable regardless of the micrometer spindle diameter or vertical dimension *x*, **Fig. 4**.

The dimension *x* (which also is equivalent to the micrometer spindle diameter) represents one side of a right triangle (the side adjacent), having an angle of 29 ÷ 2 = 14 degrees and 30 minutes, in the case of an Acme thread. The side opposite or *y* = side adjacent × tangent = dimension *x* × tan 14° 30′.

If *x* equals 0.25 inch, then side opposite or *y* = 0.25 × 0.25862= 0.06465; hence, the caliper reading minus 2 × 0.06465 = width of the flat end (2 × 0.06465 = 0.1293 = constant).

The same result would be obtained by multiplying 0.25862 by 2*x*; hence, the following rule: To determine the width of the end of the threading tool, by the general method illustrated in **Fig. 4**, multiply twice the dimension *x* (or spindle diameter in the case of the micrometer) by the tangent of one-half the thread tool angle, and subtract this product from the width w to obtain the width at the end of the tool.

Example 7: A gear-tooth vernier caliper is to be used for measuring the width of the flat of an American Standard external screw-thread tool. The vertical scale is set to ⅛ inch (corresponding to the dimension *x*, **Fig. 4**). How much is subtracted from the reading on the horizontal scale to obtain the width of the flat end of the tool?

$$\tfrac{1}{8} \times 2 \times \tan 30^\circ = \tfrac{1}{4} \times 0.57735 = 0.1443 \text{ inch}$$

Hence, the width of the flat equals *w*, **Fig. 4**, minus 0.1443. This width should be equal to one-eighth of the pitch of the thread to be cut, since this is the width of flat at the minimum minor diameter of American Standard external screw threads.

PRACTICE EXERCISES FOR SECTION 14

(See *Answers to Practice Exercises For Section 14* on page 229)

1) What form of screw thread is most commonly used (*a*) in the United States? (*b*) in Britain?

2) What is the meaning of abbreviations 3″– 4NC-2?

3) What are the advantages of an Acme thread compared to a square thread?

4) For what reason would a Stub Acme thread be preferred in some applications?

Copyright 2004, Industrial Press, Inc., New York, NY

5) Find the pitch diameters of the following screw threads of American Standard Unified form: $\frac{1}{4}-28$ (meaning $\frac{1}{4}$-inch diameter and 28 threads per inch); $\frac{3}{4}-10$?

6) How much taper is used on a standard pipe thread?

7) Under what conditions are straight, or nontapering, pipe threads used?

8) In cutting a taper thread, what is the proper position for the lathe tool?

9) If a lathe is used for cutting a British Standard pipe thread, in what position is the tool set?

10) A thread tool is to be ground for cutting an Acme thread having 4 threads per inch; what is the correct width of the tool at the end?

11) What are the common shop and toolroom methods of checking the pitch diameters of American Standard screw threads requiring accuracy?

12) In using the formula, Handbook **page 1734**, for measuring an American Standard screw thread by the three-wire method, why should the constant 0.86603 be multiplied by the pitch before subtracting from measurement *M*, even if not enclosed by parentheses?

13) What is the difference between the pitch and the lead (*a*) of a double thread? (*b*) of a triple thread?

14) In using a lathe to cut American Standard Unified threads, what should be the truncations of the tool points and the thread depths for the following pitches: 0.1, 0.125, 0.2, and 0.25 inch?

15) In using the three-wire method of measuring a screw thread, what is the micrometer reading for a $\frac{3}{4}-12$ special thread of American Standard form if the wires have a diameter of 0.070 inch?

16) Are most nuts made to the United States Standard dimensions?

17) Is there, at the present time, a Manufacturing Standard for bolts and nuts?

18) The American standard for machine screws includes a coarse-thread series and a fine thread series as shown by the tables starting on Handbook **page 1763**. Which series is commonly used?

Copyright 2004, Industrial Press, Inc., New York, NY

19) How is the length (*a*) of a flat head or countersunk type of machine screw measured? (*b*) of a fillister head machine screw?

20) What size tap drill should be used for an American standard machine screw of No. 10 size, 24 threads per inch?

21) What is the diameter of a No. 10 drill?

22) Is a No. 6 drill larger than a No. 16?

23) What is the relation between the letter size drills and the numbered sizes?

24) Why is it common practice to use tap drills that leave about ¾ of the full thread depth after tapping, as shown by the tables starting on **page 1933** in the Handbook?

25) What form of a screw thread is used on (*a*) machine screws? (*b*) cap screws?

26) What standard governs the pitches of cap screw threads?

27) What form of thread is used on the National Standard fire hose couplings? How many standards diameters are there?

28) In what way do hand taps differ from machine screw taps?

29) What are tapper taps?

30) The diameter of a ¾ - 10 American Standard Thread is to be checked by the three wire method. What is the largest size wire that can be used?

31) Why is the advance of some threading dies positively controlled by a lead screw instead of relying upon the die to lead itself?

32) What is the included angle of the heads of American Standard (*a*) flat head Machine screws? (*b*) flat head cap screws? (*c*) flat head wood screws?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 15

PROBLEMS IN MECHANICS

HANDBOOK Pages 141 – 163

In the design of machines or other mechanical devices, it is often necessary to deal with the actions of forces and their effects. For example, the problem may be to determine what force is equivalent to two or more forces acting in the same plane but in different directions. Another type of problem is to determine the change in the magnitude of a force resulting from the application of mechanical appliances such as levers, pulleys, and screws used either separately or in combination. It also may be necessary to determine the magnitude of a force in order to proportion machine parts to resist the force safely; or, possibly, to ascertain if the force is great enough to perform a given amount of work. Determining the amount of energy stored in a moving body or its capacity to perform work, and the power developed by mechanical apparatus, or the rate at which work is performed, are additional examples of problems frequently encountered in originating or developing mechanical appliances. The section in Machinery's Handbook on Mechanics, beginning on **page 141**, deals with fundamental principles and formulas applicable to a wide variety of mechanical problems.

The Moment of a Force.— The tendency of a force acting upon a body is, in general, to produce either a motion of translation (that is, to cause every part of the body to move in a straight line) or to produce a motion of rotation. A moment, in mechanics, is the measure of the turning effect of a force that tends to produce rotation. For example, suppose a force acts upon a body that is supported by a pivot. Unless the line of action of the force happens to pass through the pivot, the body will tend to rotate. Its tendency to rotate, moreover, will depend upon two things: (1) the magnitude of the force acting, and (2) the distance of the force from the pivot, *measuring along a line at right angles to the line of action of the*

Copyright 2004, Industrial Press, Inc., New York, NY

force. (See Fig. 9 on Handbook **page 147** and the accompanying text.)



Fig. 1. Diagram Showing How the Turning Moment of a Crank Disk Varies from Zero to Maximum

Example 1: A force F of 300 pounds is applied to a crank disk A (**Fig. 1**) and in the direction of the arrow. If the radius $R = 5$ inches, what is the turning moment? Also, determine how much the turning moment is reduced when the crankpin is in the position shown by the dashed lines, assuming that the force is along line f and that $r = 2\frac{1}{2}$ inches.

When the crankpin is in the position shown by the solid lines, the maximum turning moment is obtained, and it equals $F \times R = 300 \times 5 = 1500$ inch-pounds or pound-inches. When the crankpin is in the position shown by the dashed lines, the turning moment is reduced one-half and equals $f \times r = 300 \times 2\frac{1}{2} = 750$ inch-pounds.

Note: Foot-pound is the unit for measurement of work and is in common use in horsepower calculations. However, torque, or turning moment, is also a unit of measurement of work. To differentiate between these two similar terms, which have the same essential meaning, it is convenient to express torque in terms of *pound-feet* (or *pound-inches*). This reversal of word sequence will readily indicate the different meanings of the two terms for units of measurement – the unit of horsepower and the unit of turning moment. A strong reason for expressing the unit of turning moment as *pound-inches* (rather than as *foot-pounds*) is because the dimensions of shafts and other machine parts ordinarily are stated in inches.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 2: Assume that the force F (diagram B, **Fig. 1**) is applied to the crank through a rod connecting with a crosshead that slides along center line c-c. If the crank radius $R = 5$ inches, What will be the maximum and minimum turning moments?

The maximum turning moment occurs when the radial line R is perpendicular to the force line F and equals in inch-pounds, $F \times 5$ in this example. When the radial line R is in line with the center line $c-c$, the turning moment is 0, because $F \times 0 = 0$. This is the "deadcenter" position for steam engines and explains why the crankpins on each side of a locomotive are located 90 degrees apart, or, in such a position that the maximum turning moment, approximately, occurs when the turning moment is zero on the opposite side. With this arrangement, it is always possible to start the locomotive since only one side at a time can be in the dead-center position.

The Principle of Moments in Mechanics.— When two or more forces act upon a rigid body and tend to turn it about an axis, then, for equilibrium to exist, the sum of the moments of the forces that tend to turn the body in one direction must be equal to the sum of the moments of those that tend to turn it in the opposite direction about the same axis.

Example 3: In **Fig. 2**, a lever 30 inches long is pivoted at the fulcrum F. At the right, and 10 inches from F, is a weight, B, of 12 pounds tending to turn the bar in a right-hand direction about its fulcrum F. At the left end, 12 inches from F, the weight A, of 4 pounds tends to turn the bar in a left-hand direction, while weight C, at the other end, 18 inches from F, has a like effect, through the use of the string and pulley P.



Fig. 2. Lever in Equilibrium Because the Turning Moment of a Crank Disk Varies from Zero to Maximum

Copyright 2004, Industrial Press, Inc., New York, NY

Taking moments about F, which is the center of rotation, we have:

$$\text{Moment of } B = 10 \times 12 = 120 \text{ inch-pounds}$$

Opposed to this are the moments of A and C:

$$\text{Moment of } A = 4 \times 12 = 48 \text{ inch-pounds}$$

$$\text{Moment of } C = 4 \times 18 = 72 \text{ inch-pounds}$$

$$\text{Sum of negative numbers} = 120 \text{ inch-pounds}$$

Hence, the moments are equal, and, if we suppose, for simplicity, that the lever is weightless, it will balance or be in equilibrium. Should weight A be increased, the negative moments would be greater, and the lever would turn to the left, while if B should be increased or its distance from F be made greater, the lever would turn to the right. (See Handbook Fig. 9 and the accompanying text on **page 147**.)

Example 4: Another application of the principle of moments is given in **Fig. 3**. A beam of uniform cross section, weighing 200 pounds, rests upon two supports, R and S, that are 12 feet apart. The weight of the beam is considered to be concentrated at its center of gravity G, at a distance 6 feet from each supports react or push upward, with a force equal to the downward pressure of the beam.

To make this clear, suppose two people take hold of the beam, one at each end, and that the supports are withdrawn. Then, in order to hold the beam in position, the two people must together lift or pull upward an amount equal to the weight of the beam and its load, or 250 pounds. Placing the supports in position again, and resting the beam upon them, does not change the conditions. The weight of the beam acts downward, and the supports react by an equal amount.



Fig. 3. The Weight on Each Support is Required

Copyright 2004, Industrial Press, Inc., New York, NY

Now, to solve the problem, assume the beam to be pivoted at one support, say, at *S*. The forces or weights of 50 pounds and 200 pounds tend to rotate the beam in a left-hand direction about this point, while the reaction of *R* in an upward direction tends to give it a right-hand rotation. As the beam is balanced and has no tendency to rotate, it is in equilibrium, and the opposing moments of these forces must balance; hence, taking moments,

$$9 \times 50 = 450 \text{ pound-feet}$$
$$6 \times 200 = \underline{1200 \text{ pound-feet}}$$
$$\text{Sum of negative numbers} = 1650 \text{ pound-feet}$$

By letting *R* represent the reaction of support,

$$\text{Moment of } R = R \times 12 = \text{ pound-feet}$$

By the principle of moments, $R \times 12 = 1650$. That is, if *R*, the quantity that we wish to obtain, is multiplied by 12, the result will be 1650; hence, to obtain *R*, divide 1650 by 12. Therefore, $R = 137.5$ pounds, which is also the weight of that end of the beam. As the total load is 250 pounds, the weight at the other end must be $250 - 137.5 = 112.5$ pounds.

The Principle of Work in Mechanics.— Another principle of more importance than the principle of moments, even in the study of machine elements, is the principle of work. According to this principle (neglecting frictional or other losses), the applied force, multiplied by the distance through which it moves, equals the resistance overcome, multiplied by the distance through which it is overcome. The principle of work may also be stated as follows:

$$\text{Work put in} = \text{lost work} + \text{work done by machine}$$

This principle holds absolutely in every case. It applies equally to a simple lever, the most complex mechanism, or to a so-called "perpetual motion" machine. No machine can be made to perform work unless a somewhat greater amount—enough to make up for the losses—is applied by some external agent. In the "perpetual motion" machine no such outside force is supposed to be applied, hence such a machine is impossible, and against all the laws of mechanics.

Example 5: Assume that a rope exerts a pull *F* of 500 pounds (upper diagram, Handbook **page 162**) and that the pulley radius

Copyright 2004, Industrial Press, Inc., New York, NY

$R = 10$ inches and the drum radius $r = 5$ inches. How much weight W can be lifted (ignoring frictional losses) and upon what mechanical principle is the solution based?

According to one of the formulas accompanying the diagram at the top of Handbook **page 162**,

$$W = \frac{F \times R}{r} = \frac{500 \times 10}{5} = 1000 \text{ pounds}$$

This formula (and the others for finding the values of F, R, etc.) agrees with the principle of moments, and with the principle of work. The principle of moments will be applied first.

The moment of the force F about the center of the pulley, which corresponds to the fulcrum of a lever, is F multiplied by the perpendicular distance R, it being a principle of geometry that a radius is perpendicular to a line drawn tangent to a circle, at the point of tangency. Also, the opposing moment of W is $W \times r$. Hence, by the principle of moments,

$$F \times R = W \times r$$

Now, for comparison, we will apply the principle of work. Assuming this principle to be true, force F multiplied by the distance traversed by this force or by a given point on the rim of the large pulley should equal the resistance W multiplied by the distance that the load is raised. In one revolution, force F passes through a distance equal to the circumference of the pulley, which is equal to $2 \times 3.1416 \times R = 6.2832 \times R$, and the hoisting rope passes through a distance equal to $2 \times 3.1416 \times r$. Hence, by the principle of work,

$$6.2832 \times F \times R = 6.2832 \times W \times r$$

The statement simply shows that $F \times R$ multiplied by 6.2832 equals $W \times r$ multiplied by the same number, and it is evident therefore, that the equality will not be altered by canceling the 6.2832 and writing:

$$F \times R = W \times r$$

However, this statement is the same as that obtained by applying the principle of moments; hence, we see that the principle of moments and the principle of work are in harmony.

Copyright 2004, Industrial Press, Inc., New York, NY

The basis of operation of a train of wheels is a continuation of the principle of work. For example, in the gear train represented by the diagram at the bottom of Handbook **page 162**, the continued product of the applied force F and the radii of the driven wheels equals the continued product of the resistance W and the radii of the drivers. In calculations, the pitch diameters or the numbers of teeth in gear wheels may be used instead of the radii.

Efficiency of a Machine or Mechanism.— The efficiency of a machine is the ratio of the power delivered by the machine to the power received by it. For example, the efficiency of an electric motor is the ratio between the power delivered by the motor to the machinery it drives and the power it receives from the generator. Assume, for example, that a motor receives 50 kilowatts from the generator, but that the output of the motor is only 47 kilowatts. Then, the efficiency of the motor is 47 ÷ 50 = 94 per cent. The efficiency of a machine tool is the ratio of the power consumed at the cutting tool to the power delivered by the driving belt. The efficiency of gearing is the ratio between the power obtained from the driven shaft to the power used by the driving shaft. Generally speaking, the efficiency of any machine or mechanism is the ratio of the "output" of power to the "input." The percentage of power representing the difference between the "input" and "output" has been dissipated through frictional and other mechanical losses.

Mechanical Efficiency: If E represents the energy that a machine transforms into useful work or delivers at the driven end, and L equals the energy loss through friction or dissipated in other ways, then,

$$\text{Mechanical efficiency} = \frac{E}{E + L}$$

In this equation, the total energy $F + L$ is assumed to be the amount of energy that is transformed into useful and useless work. The actual total amount of energy, however, may be considerably larger than the amount represented by $E + L$. For example, in a steam engine, there are heat losses due to radiation and steam condensation, and considerable heat energy supplied to an internal combustion engine is dissipated either through the cooling water or direct to the atmosphere. In other classes of mechanical and elec-

Copyright 2004, Industrial Press, Inc., New York, NY

trical machinery, the total energy is much larger than that represented by the amount transformed into useful and useless work.

Absolute Efficiency: If E_1 equals the full amount of energy or the true total, then,

$$\text{Absolute efficiency} = \frac{E}{E_1}$$

It is evident that absolute efficiency of a prime mover, such as a steam or gas engine, will be much lower than the mechanical efficiency. Ordinarily, the term efficiency as applied to engines and other classes of machinery means the mechanical efficiency. The mechanical efficiency of reciprocating steam engines may vary from 85 to 95 per cent, but the thermal efficiency may range from 5 to 25 per cent, the smaller figure representing noncondensing engines of the cheaper class and the higher figure the best types.

Example 6: Assume that a motor driving through a compound train of gearing (see diagram, **Fig. 4**) is to lift a weight W of 1000 pounds. The pitch radius $R = 6$ inches; $R_1 = 8$ inches; pitch radius of pinion $r = 2$ inches; and radius of winding drum $r_1 = 2\frac{1}{2}$ inches. What motor horsepower will be required if the frictional loss in the gear train and bearings is assumed to be 10 per cent? The pitch-line velocity of the motor pinion M is 1200 feet per minute.

The problem is to determine first the tangential force F required at the pitch line of the motor pinion; then, the equivalent horsepower is easily found. According to the formula at the bottom of Handbook **page 162**, which does not take into account frictional losses,

$$F = \frac{1000 \times 2 \times 2\frac{1}{2}}{6 \times 8} = 104 \text{ pounds}$$

The pitch-line velocity of the motor pinion is 1200 feet per minute and, as the friction loss is assumed to be 10 per cent, the mechanical efficiency equals $90 \div (90 + 10) = 0.90$ or 90 per cent as commonly written; thus,

$$\text{Horsepower} = \frac{104 \times 1200}{33,000 \times 0.90} = 4\frac{1}{4} \text{ approximately}$$

Copyright 2004, Industrial Press, Inc., New York, NY



Fig. 4. Determining the Power Required for Lifting a Weight by Means of a Motor and a Compound Train of Gearing

Example 7: In designing practice, a motor of horsepower, or larger, might be selected for the drive referred to in **Example 6** (depending upon conditions) to provide extra power should it be needed. However, to illustrate the procedure, assume that the gear train is to be modified so that the calculated horsepower will be 4 instead of 4¼; conditions otherwise are the same as in **Example 6**.

$$F = \frac{33,000 \times 4}{1200} = 110 \text{ pounds}$$

Hence, since $W = 1000$ pounds,

$$1000 = \frac{110 \times 0.90 \times R \times R_1}{r \times r_1}$$

Insert any values for the pitch radii R, R_1, etc., that will balance the equation, so that the right-hand side equals 1000, at least approximately. Several trial solutions may be necessary to obtain a total of about 1000, at the same time, secure properly proportional gears that meet other requirements of the design. Suppose the same radii are used here, except R_1, which is increased from 8 to 8½ inches. Then

Copyright 2004, Industrial Press, Inc., New York, NY

$$\frac{110 \times 0.90 \times 6 \times 8\frac{1}{2}}{2 \times 2\frac{1}{2}} = 1000 \text{ approximately}$$

This example shows that the increase in the radius of the last driven gear from 8 to 8½ inches makes it possible to use the 4-horsepower motor. The hoisting speed has been decreased somewhat, and the center distance between the gears has been increased. These changes might or might not be objectionable in actual designing practice, depending upon the particular requirements.

Force Required to Turn a Screw Used for Elevating or Lowering Loads.— In determining the force that must be applied at the end of a given lever arm in order to turn a screw (or nut surrounding it), there are two conditions to be considered: (1) when rotation is such that the load *resists* the movement of the screw, as in raising a load with a screw jack; (2) when rotation is such that the load *assists* the movement of the screw, as in lowering a load. The formulas at the bottom of the table on Handbook **page 163** apply to both these conditions. When the load resists the screw movement, use the formula "for motion in a direction opposite to *Q*." When the load assists the screw movement, use the formula "for motion in the same direction as *Q*."

If the lead of the thread is large in proportion to the diameter so that the helix angle is large, the force *F* may have a negative value, which indicates that the screw will turn due to the load alone, unless resisted by a force that is great enough to prevent rotation of a nonlocking screw.

Example 8: A screw is to be used for elevating a load *Q* of 6000 pounds. The pitch diameter is 4 inches, the lead is 0.75 inch, and the coefficient of friction μ between screw and nut is assumed to be 0.150. What force *F* will be required at the end of a lever arm *R* of 10 inches? In this example, the load is in the direction opposite to the arrow *Q* (see diagram at bottom of the table on Handbook **page 163**).

Copyright 2004, Industrial Press, Inc., New York, NY

$$F = 6000 \times \frac{0.75 + 6.2832 \times 0.150 \times 2}{6.2832 \times 2 - 0.150 \times 0.75} \times \frac{2}{10}$$
$$= 254 \text{ pounds}$$

Example 9: What force F will be required to lower a load of 6000 pounds using the screw referred to in **Example 8**? In this case, the load assists in turning the screw; hence,

$$F = 6000 \times \frac{6.2832 \times 0.150 \times 2 - 0.75}{6.2832 \times 2 + 0.150 \times 0.75} \times \frac{2}{10} = 107 \text{ pounds}$$

Coefficients of Friction for Screws and Their Efficiency.— According to experiments Professor Kingsbury made with square-threaded screws, a friction coefficient μ of 0.10 is about right for pressures less than 3000 pounds per square inch and velocities above 50 feet per minute, assuming that fair lubrication is maintained. If the pressures vary from 3000 to 10,000 pounds per square inch, a coefficient of 0.15 is recommended for low velocities. The coefficient of friction varies with lubrication and the materials used for the screw and nut. For pressures of 3000 pounds per square inch and by using heavy machinery oil as a lubricant, the coefficients were as follows: Mild steel screw and cast-iron nut, 0.132; mild-steel nut, 0.147; cast-brass nut, 0.127. For pressures of 10,000 pounds per square inch using a mild-steel screw, the coefficients were, for a cast-iron nut, 0.136; for a mild-steel nut, 0.141 for a cast-brass nut, 0.136. For dry screws, the coefficient may be 0.3 to 0.4 or higher.

Frictional resistance is proportional to the normal pressure, and for a thread of angular form, the increase in the coefficient of friction is equivalent practically to $\mu \sec\beta$, in which β equals one-half the included thread angle; hence, for a sixty-degree thread, a coefficient of 1.155μ may be used. The square form of thread has a somewhat higher efficiency than threads with sloping sides, although when the angle of the thread form is comparatively small, as in an Acme thread, there is little increase in frictional losses. Multiple-thread screws are much more efficient than single-thread screws, as the efficiency is affected by the helix angle of the thread.

Copyright 2004, Industrial Press, Inc., New York, NY

The efficiency between a screw and nut increases quite rapidly for helix angles up to 10 to 15 degrees (measured from a plane perpendicular to the screw axis). The efficiency remains nearly constant for angles between about 25 and 65 degrees, and the angle of maximum efficiency is between 40 and 50 degrees. A screw will not be self-locking if the efficiency exceeds 50 per cent. For example, the screw of a jack or other lifting or hoisting appliance would turn under the action of the load if the efficiency were over 50 per cent. It is evident that maximum efficiency for power transmission screws often is impractical, as for example, when the smaller helix angles are required to permit moving a given load by the application of a smaller force or turning moment than would be needed for a multiple screw thread.

In determining the efficiency of a screw and a nut, the helix angle of the thread and the coefficient of friction are the important factors. If E equals the efficiency, A equals the helix angle, measured from a plane perpendicular to the screw axis, and μ equals the coefficient of friction between the screw thread and nut, then the efficiency may be determined by the following formula, which does not take into account any additional friction losses, such as may occur between a thrust collar and its bearing surfaces:

$$E = \frac{\tan A(1 - \mu \tan A)}{\tan A + \mu}$$

This formula would be suitable for a screw having ball-bearing thrust collars. Where collar friction should be taken into account, a fair approximation may be obtained by changing the denominator of the foregoing formula to $\tan A + 2\mu$. Otherwise, the formula remains the same.

Angles and Angular Velocity Expressed in Radians.— There are three systems generally used to indicate the sizes of angles, which are ordinarily measured by the number of degrees in the arc subtended by the sides of the angle. Thus, if the arc subtended by the sides of the angle equals one-sixth of the circumference, the angle is said to be 60 degrees. Angles are also designated as multiples of a right angle. As an example, the sum of the interior angles of any polygon equals the number of sides less two, times two right angles. Thus the sum of the interior angles of an octagon

Copyright 2004, Industrial Press, Inc., New York, NY

equals (8 – 2) × 2 × 90 = 6 × 180 = 1080 degrees. Hence each interior angle equals 1080 ÷ 8 = 135 degrees.

A third method of designating the size of an angle is very helpful in certain problems. This method makes use of radians. A radian is defined as a central angle, the subtended arc of which equals the radius of the arc.

By using the symbols on Handbook **page 88**, v may represent the length of an arc as well as the velocity of a point on the periphery of a body. Then, according to the definition of a radian: $\omega = v/r$, or the angle in radians equals the length of the arc divided by the radius. Both the length of the arc and the radius must, of course, have the same unit of measurement – both must be in feet or inches or centimeters, etc. By rearranging the preceding equation:

$$v = \omega r \quad \text{and} \quad r = \frac{v}{\omega}$$

These three formulas will solve practically every problem involving radians.

The circumference of a circle equals πd or $2\pi r$, which equals $6.2832r$, which indicates that a radius is contained in a circumference 6.2832 times; hence there are 6.2832 radians in a circumference. Since a circumference represents 360 degrees, 1 radian equals 360 ÷ 6.2832 = 57.2958 degrees. Since 57.2958 degrees = 1 radian, 1 degree = 1 radian ÷ 57.2958 = 0.01745 radian.

Example 10: 2.5 radians equal how many degrees? One radian = 57.2958 degrees; hence, 2.5 radians = 57.2958 × 2.5 = 143.239 degrees.

Example 11: 22° 31′ 12″ = how many radians? 12 seconds = $^{12}/_{60}$ = $^{1}/_{5}$ = 0.2 minute; 31.2′ ÷ 60 = 0.52 degree. One radian = 57.3 degrees approximately. 22.52° = 22.52 + 57.3 = 0.393 radian.

Example 12: In the figure on Handbook **page 71**, let $l = v = 30$ inches; and radius $r = 50$ inches; find the central angle $\omega = v/r = {}^{30}/_{50}$ = $^{3}/_{5}$ = 0.6 radian.

$$57.2958 \times 0.6 = 34°22.6′$$

Example 13: $^{3\pi}/_{4}$ radians equal how many degrees? 2π radians = 360°; π radians = 180°. $^{3\pi}/_{4}$ = $^{3}/_{4}$ × 180 = 135 degrees.

Copyright 2004, Industrial Press, Inc., New York, NY

Example 14: A 20-inch grinding wheel has a surface speed of 6000 feet per minute. What is the angular velocity?

The radius (r) = $^{10}/_{12}$ foot; the velocity (n) in feet per second = $^{6000}/_{60}$; hence,

$$\omega = \frac{6000}{60 \times {}^{10}/_{12}} = 120 \text{ radians per second}$$

Example 15: Use the table on Handbook **page 96** to solve **Example 11**.

20°	= 0.349066 radian
2°	= 0.034907 radian
31′	= 0.009018 radian
12″	= 0.000058 radian
22°31′ 12″	= 0.393049 radian

Example 16: 7.23 radians equals how many degrees? On Handbook **page 97**, find:

7.0 radians =	401°	4′	14″
0.2 radian =	11°	27′	33″
0.03 radian =	1°	43′	8″
7.23 radians =	414°	14′	55″

PRACTICE EXERCISES FOR SECTION 15

(See *Answers to Practice Exercises For Section 15* on page 231)

1) In what respect does a foot-pound differ from a pound?

2) If a 100-pound weight is dropped, how much energy will it be capable of exerting after falling 10 feet?

3) Can the force of a hammer blow be expressed in pounds?

4) If a 2-pound hammer is moving 30 feet per second, what is its kinetic energy?

5) If the hammer referred to in Exercise 4 drives a nail into a ¼-inch board, what is the average force of the blow?

6) What relationship is there between the muzzle velocity of a projectile fired upward and the velocity with which the projectile strikes the ground?

7) What is the difference between the composition of forces and the resolution of forces?

Copyright 2004, Industrial Press, Inc., New York, NY

8) If four equal forces act along lines 90 degrees apart through a given point, what is the shape of the corresponding polygon of forces?

9) Skids are to be employed for transferring boxed machinery from one floor to the floor above. If these skids are inclined at an angle of 35 degrees, what force in pounds, applied parallel to the skids, will be required to slide a boxed machine weighing 2500 pounds up the incline, assuming that the coefficient of friction is 0.20?

10) Refer to Exercise 9. If the force or pull were applied in a horizontal direction instead of in line with the skids, what increase, if any, would be required?

11) Will the boxed machine referred to in Exercise 9 slide down the skids by gravity?

12) At what angle will the skids require to be before the boxed machine referred to in Exercise 9 begins to slide by gravity?

13) What name is applied to the angle that marks the dividing line between sliding and nonsliding when a body is placed on an inclined plane?

14) How is the "angle of repose" determined?

15) What figure or value is commonly used in engineering calculations for acceleration due to gravity?

16) Is the value commonly used for acceleration due to gravity strictly accurate for any locality?

17) A flywheel 3 feet in diameter has a rim speed of 1200 feet per minute, and another flywheel 6 feet in diameter has the same rim speed. Will the rim stress or the force tending to burst the larger flywheel be greater than the force in the rim of the smaller flywheel?

18) What factors of safety are commonly used in designing flywheels?

19) Does the stress in the rim of a flywheel increase in proportion to the rim velocity?

20) What is generally considered the maximum safe speed for the rim of a solid or one-piece cast-iron flywheel?

21) Why is a well-constructed wood flywheel better adapted to higher speeds than one made of cast iron?

Copyright 2004, Industrial Press, Inc., New York, NY

22) What is the meaning of the term "critical speed" as applied to a rotating body?

23) How is angular velocity generally expressed?

24) What is a radian, and how is its angle indicated?

25) How many degrees are there in 2.82 radians?

26) How many degrees are in the following radians: $\pi/3$; $2\pi/5$;

27) Reduce to radians: 63°; 45°32′; 6°37′46″; 22°22′ 22″.

28) Find the angular velocity in radians per second of the following: 157 rpm; 275 rpm; 324 rpm.

29) Why do the values in the *l* column starting on Handbook **page 71** equal those in the radian column on **page 96**?

30) If the length of the arc of a sector is $4\frac{7}{8}$ inches, and the radius is $6\frac{7}{8}$ inches, find the central angle.

31) A 12-inch grinding wheel has a surface speed of a mile a minute. Find its angular velocity and its revolutions per minute.

32) The radius of a circle is $1\frac{1}{2}$ inches, and the central angle is 60 degrees. Find the length of the arc.

33) If an angle of 34°12′ subtends an arc of 16.25 inches, find the radius of the arc.

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 16

STRENGTH OF MATERIALS

HANDBOOK Pages 203 – 225

The Strength of Materials section of Machinery's Handbook contains fundamental formulas and data for use in proportioning parts that are common to almost every type of machine or mechanical structure. In designing machine parts, factors other than strength often are of vital importance. For example, some parts are made much larger than required for strength alone to resist extreme vibrations, deflection, or wear; consequently, many machine parts cannot be designed merely by mathematical or strength calculations, and their proportions should, if possible, be based upon experience or upon similar designs that have proved successful. It is evident that no engineering handbook can take into account the endless variety of requirements relating to all types of mechanical apparatus, and it is necessary for the designer to determine these local requirements for each, but, even when the strength factor is secondary due to some other requirement, the strength, especially of the more important parts, should be calculated, in many instances, merely to prove that it will be sufficient.

In designing for strength, the part is so proportioned that the maximum working stress likely to be encountered will not exceed the strength of the material by a suitable margin. The design is accomplished by the use of a factor of safety. The relationship between the working stress s_w, the strength of the material, S_m, and the factor of safety, f_s is given by Equation (1) on page 208 of the Handbook:

$$s_w = \frac{S_m}{f_s} \qquad \text{(a)}$$

The value selected for the strength of the material, S_m depends on the type of material, whether failure is expected to occur

Copyright 2004, Industrial Press, Inc., New York, NY

because of tensile, compressive, or shear stress, and on whether the stresses are constant, fluctuating, or are abruptly applied as with shock loading. In general, the value of S_m is based on yield strength for ductile materials, ultimate strength for brittle materials, and fatigue strength for parts subject to cyclic stresses. Moreover, the value for S_m must be for the temperature at which the part operates. Values of S_m for common materials at 68°F can be obtained from the tables in Machinery's Handbook from **page 474** and **554**. Factors from the table given on Handbook **page 421**, *Influence of Temperature on the Strength of Metals,* can be used to convert strength values at 68°F to values applicable at elevated temperatures. For heat-treated carbon and alloy steel parts, see data starting on Handbook **page 468**.

The factor of safety depends on the relative importance of reliability, weight, and cost. General recommendations are given in the Handbook on **page 208**.

Working stress is dependent on the shape of the part, hence on a stress concentration factor, and on a nominal stress associated with the way in which the part is loaded. Equations and data for calculating nominal stresses, stress concentration factors, and working stresses are given starting on Handbook **page 208**.

Example 1: Determine the allowable working stress for a part that is to be made from SAE 1112 free-cutting steel; the part is loaded in such a way that failure is expected to occur in tension when the yield strength has been exceeded. A factor of safety of 3 is to be used.

From the table, *Strength Data for Iron and Steel,* on **page 474** of the Handbook, a value of 30,000 psi is selected for the strength of the material, S_m. Working stress S_w is calculated from **Equation (a)** as follows:

$$s_w = \frac{30,000}{3} = 10,000 \quad \text{psi}$$

Finding Diameter of Bar to Resist Safely Under a Given Load.— Assume that a direct tension load, F, is applied to a bar such that the force acts along the longitudinal axis of the bar. From Handbook **page 213**, the following equation is given for calculating the nominal stress:

Copyright 2004, Industrial Press, Inc., New York, NY

$$\sigma = \frac{F}{A} \tag{b}$$

where A is the cross-sectional area of the bar. Equation (2) on Handbook **page 208** related the nominal stress to the stress concentration factor, K, and working stress, S_w:

$$s_w = K\sigma \tag{c}$$

Combining **Equations (a)**, **(b)**, and **(c)** results in the following:

$$\frac{S_m}{Kf_s} = \frac{F}{A} \tag{d}$$

Example 2: A structural steel bar supports in tension a load of 40,000 pounds. The load is gradually applied and, then, after having reached its maximum value, is gradually removed. Find the diameter of round bar required.

According to the table on Handbook **page 474**, the yield strength of structural steel is 33,000 psi. Suppose that a factor of safety of 3 and a stress concentration factor of 1.1 are used. Then, inserting known values in **Equation (d)**:

$$\frac{33,000}{1.1 \times 3} = \frac{40,000}{A};\ A = \frac{40,000 \times 3.3}{33,000};\ A = 4 \text{ square inches}$$

Hence, the cross-section of the bar must be about 4 square inches. As the bar is circular in section, the diameter must then be about 2¼ inches.

Diameter of Bar to Resist Compression.— If a short bar is subjected to compression in such a way that the line of application of the load coincides with the longitudinal axis of the bar, the formula for nominal stress is the same as for direct tension loading. **Equation (b)** and hence **Equation (d)** also may be applied to direct compression loading.

Example 3: A short structural steel bar supports in compression a load of 40,000 pounds. (See Fig. 1.) The load is steady. Find the diameter of the bar required.

From **page 474** in the Handbook, the yield strength of structural steel is 33,000 psi. If a stress concentration factor of 1.1 and a fac-

Copyright 2004, Industrial Press, Inc., New York, NY

tor of safety of 2.5 are used, then, substituting values into **Equation (d)**:

$$\frac{33,000}{1.1 \times 2.5} = \frac{40,000}{A}; \; A = 3.33 \text{ square inches}$$



Fig. 1. Calculating Diameter *x* to Support a Given Load Safely

The diameter of a bar, the cross-section of which is 3.33 square inches, is about $2\frac{1}{16}$ inches.

According to a general rule, the simple formulas that apply to compression should be used only if the length of the member being compressed is not greater than 6 times the least cross-sectional dimension. For example, these formulas should be applied to round bars only when the length of the bar is less than 6 times the diameter. If the bar is rectangular, the formulas should be applied only to bars having a length less than 6 times the shortest side of the rectangle. When bars are longer than this, a compressive stress causes a sidewise bending action, and an even distribution of the compression stresses over the total area of the cross-section should no longer be depended upon. Special formulas for long bars or columns will be found on Handbook **page 287**; see also text beginning on **page 285**, *Strength of Columns or Struts*.

Diameter of Pin to Resist Shearing Stress.— The pin *E* shown in the illustration, **Fig. 2**, is subjected to shear. Parts *G* and *B* are held

Copyright 2004, Industrial Press, Inc., New York, NY

together by the pin and tend to shear it off at *C* and *D*. The areas resisting the shearing action are equal to the pin at these points.



Fig. 2. Finding the Diameter of Connecting-Rod Pin to Resist a Known Load G

From the *Table of Simple Stresses* on **page 213** of the Handbook, the equation for direct shear is:

$$\tau = \frac{F}{A} \qquad \text{(e)}$$

τ is a simple stress related to the working stress, s_w, by Equation (3) on Handbook **page 208**:

$$s_w = K\tau \qquad \text{(f)}$$

where K is a stress concentration factor. Combining **Equation (a)**, **(e)**, and **(f)** gives **Equation (d)** on page 140, where S_m is, of course, the shearing strength of the material.

If a pin is subjected to shear as in **Fig. 2**, so that two surfaces, as at *C* and *D*, must fail by shearing before breakage occurs, the areas of both surfaces must be taken into consideration when calculating the strength. The pin is then said to be in *double shear*. If the lower part *F* of connecting rod *B* were removed, so that member *G* were connected with *B* by a pin subjected to shear at *C* only, the pin would be said to be in *single shear*.

Example 4: Assume that in **Fig. 2** the load at *G* pulling on the connecting rod is 20,000 pounds. The material of the pin is SAE

Copyright 2004, Industrial Press, Inc., New York, NY

1025 steel. The load is applied in such a manner that shocks are liable to occur. Find the required dimensions for the pin.

Since the pins are subjected to shock loading, the nominal stress resulting from the application of the 20,000-pound load must be assumed to be twice as great (see Handbook starting on **page 282**) as it would be if the load were gradually applied or steady. From Handbook **page 474**, the ultimate strength in shear for SAE 1025 steel is 75 per cent of 60,000 or 45,000 psi. A factor of safety of 3 and a stress concentration factor of 1.8 are to be used. By substituting values into **Equation (d)**:

$$\frac{45,000}{1.8 \times 3} = \frac{2 \times 20,000}{A}; \quad A = \frac{10.8 \times 20,000}{45,000}$$

$$= 4.8 \quad \text{sq. in.}$$

As the pin is in double shear, that is, as there are two surfaces *C* and *D* over which the shearing stress is distributed, each surface must have an area of one-half the total shearing area *A*. Then, the cross-sectional area of the pin will be 2.4 square inches, and the diameter of the pin, to give a cross-sectional area of 2.4 square inches, must be $1\frac{3}{4}$ inches.

Beams, and Stresses to Which They Are Subjected.— Parts of machines and structures subjected to bending are known mechanically as *beams*. Hence, in this sense, a lever fixed at one end and subjected to a force at its other end, a rod supported at both ends and subjected to a load at its center, or the overhanging arm of a jib crane would all be known as beams.

The stresses in a beam are principally tension and compression stresses. If a beam is supported at the ends, and a load rests upon the upper side, the lower fibers will be stretched by the bending action and will be subjected to a tensile stress, while the upper fibers will be compressed and be subjected to a compressive stress. There will be a slight lengthening of the fibers in the lower part of the beam, while those on the upper side will be somewhat shorter, depending upon the amount of deflection. If we assume that the beam is either round or square in cross-section, there will be a layer or surface through its center line, which will be neither in compression nor in tension.

Copyright 2004, Industrial Press, Inc., New York, NY

This surface is known as the neutral surface. The stresses of the individual layers or fibers of the beam will be proportional to their distances from the neutral surface, the stresses being greater the farther away from the neutral surface the fiber is located. Hence, there is no stress on the fibers in the neutral surface, but there is a maximum tension on the fibers at the extreme lower side and a maximum compression on the fibers at the extreme upper side of the beam. In calculating the strength of beams, it is, therefore, only necessary to determine that the fibers of the beam that are at the greatest distance from the neutral surface are not stressed beyond the safe working stress of the material. If this condition exists, all the other parts of the section of the beam are not stressed beyond the safe working stress of the material.

In addition to the tension and compression stresses, a loaded beam is also subjected to a stress that tends to shear it. This shearing stress depends upon the magnitude and kind of load. In most instances, the shearing action can be ignored for metal beams, especially if the beams are long and the loads far from the supports. If the beams are very short and the load quite close to a support, then the shearing stress may become equal to or greater than the tension or compression stresses in the beam and the beam should then be calculated for shear.

Beam Formulas.— The bending action of a load upon a beam is called the *bending moment*. For example, in **Fig. 3** the load P acting downward on the free end of the cantilever beam has a moment or bending action about the support at A equal to the load multiplied by its distance from the support. The bending moment is commonly expressed in inch-pounds, the load being expressed in pounds and the lever arm or distance from the support in inches. The length of the lever arm should always be measured in a direction at right angles to the direction of the load. Thus, in **Fig. 4**, the bending moment is not $P \times a$, but is $P \times l$, because l is measured in a direction at right angles to the direction of the load P.

The property of a beam to resist the bending action or the bending moment is called the *moment of resistance* of the beam. It is evident that the bending moment must be equal to the moment of resistance. The moment of resistance, in turn, is equal to the stress in the fiber farthest away from the neutral plane multiplied by the

Copyright 2004, Industrial Press, Inc., New York, NY

section modulus. The *section modulus* is a factor that depends upon the shape and size of the cross-section of a beam and is given for different cross-sections in all engineering handbooks. (See table, *Moments of Inertia, Section Moduli, and Radii of Gyration* starting on Handbook **page 238**.) The section modulus, in turn, equals the moment of inertia of the cross-section, divided by the distance from the neutral surface to the most extreme fiber. The moment of inertia formulas for various cross-sections also will be found in the table just mentioned.



Fig. 3. Diagrams Illustrating Principle of Bending Moments

The following formula on Handbook **page 213** may be given as the fundamental formula for bending of beams:

$$\sigma = \pm\frac{M}{Z} = \pm\frac{My}{I} \qquad \text{(g)}$$

The moment of inertia I is a property of the cross-section that determines its relative strength. In calculations of strength of materials, a handbook is necessary because of the tabulated formulas and data relating to section moduli and moments of inertia, areas of cross-sections, etc., to be found therein.

There are many different ways in which a beam can be supported and loaded, and the bending moment caused by a given load varies greatly according to whether the beam is supported at one end only or at both ends, also whether it is freely supported at-the ends or is held firmly. The load may be equally distributed over the full length of the beam or may be applied at one point either in the center or near to one or the other of the supports. The point where stress is maximum is generally called the critical point. The stress at the critical point equals bending moment divided by section modulus.

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas for determining the stresses at the critical points will be found in the table of beam formulas, starting on Handbook **page 261**.

Example 5: A rectangular steel bar 2 inches thick and firmly built into a wall, as shown in **Fig. 4**, is to support 3000 pounds at its outer end 36 inches from the wall. What would be the necessary depth h of the beam to support this weight safely?

The bending moment equals the load times the distance from the point of support, or 3000 × 36 = 108,000 inch-pounds.

By combining **Equation (a)**, **(c)**, and **(g)**, the following equation is obtained:

$$\frac{S_m}{Kf_s} = \frac{M}{Z} \qquad \text{(h)}$$

If the beam is made from structural steel, the value for S_m, based on yield strength, from **page 474** in the Handbook, is 33,000 psi. By using a stress concentration factor of 1.1 and a factor of safety of 2.5, values may be inserted into the above equation:

$$\frac{33,000}{1.1 \times 2.5} = \frac{108,000}{Z};\quad Z = \frac{2.75 \times 108,000}{33,000};\quad Z = 9 \text{ inches}^3$$

The section modulus for a rectangle equals $bd^2/6$, in which b is the length of the shorter side and d of the longer side of the rectangle (see Handbook **page 239**), hence, $Z = bd^2/6$.



Fig. 4. Determining the Depth *h* of a Beam to Support a Known Weight

But $Z = 9$ and $b = 2$. Inserting these values into the formula, we have:

Copyright 2004, Industrial Press, Inc., New York, NY

$$9 = \frac{2d^2}{6}$$

from which $d^2 = 27$, and $d = 5.2$ inches. This value d corresponds to dimension h in **Fig. 4** Hence, the required depth of the beam to support a load of 3000 pounds at the outer end with a factor of safety of 3 would be 5.2 inches.

In calculating beams having either rectangular or circular cross-sections, the formulas on Handbook **page 273** are convenient to use. A beam loaded as shown by **Fig. 4** is similar to the first diagram on Handbook **page 273**. If the formula on this page in the Handbook for determining height h is applied to **Example 5**, **Fig. 4**, then,

$$h = \sqrt{\frac{6lW}{bf}} = \sqrt{\frac{6 \times 36 \times 3000}{2 \times 12,000}} = 5.2 \text{ inches}$$

In the above calculation the stress value f is equivalent to S_m/Kf_s.

Example 6: A steel I-beam is to be used as a crane trolley track. This I-beam is to be supported at the ends, and the unsupported span is 20 feet long. The maximum load is 6000 pounds, and the nominal stress is not to exceed 10,000 pounds per square inch. Determine the size of the standard I-beam; also determine the maximum deflection when the load is at the center of the beam.

The foregoing conditions are represented by Case 2, Handbook **page 261**. A formula for the stress at the critical point is $Wl/4Z$. As explained on Handbook **page 260**, all dimensions are in inches, and the minus sign preceding a formula merely denotes compression of the upper fibers and tension in the lower fibers.

By inserting the known values in the formula:

$$10,000 = \frac{6000 \times 240}{4Z}; \text{ hence}$$

$$Z = \frac{6000 \times 240}{10,000 \times 4} = 36$$

The table of standard I-beams on Handbook **page 2513** shows that a 12-inch I-beam, which weighs 31.8 pounds per foot, has a section modulus of 36.4.

Copyright 2004, Industrial Press, Inc., New York, NY

The formula for maximum deflection (see Handbook starting on **page 261**, Case 2) is $Wl^3/48EI$. According to the table on Handbook **page 474**, the modulus of elasticity (E) of structural steel is 29,000,000.

As Z = moment of inertia I ÷ distance from neutral axis to extreme fiber (see Handbook **page 260**), then for a 12-inch I-beam $I = 6Z = 216$; hence,

$$\text{Maximum deflection} = \frac{6000 \times (240)^3}{48 \times 29,000,000 \times 216} = 0.27 \text{ inch}$$

Example 7: All conditions are the same as in **Example 6**, except that the maximum deflection at the "critical point," or center of the I-beam, must not exceed ⅛ inch. What size I-beam is required?

To meet the requirement regarding deflection,

$$\frac{1}{8} = \frac{Wl^3}{48EI}; \quad \text{therefore,}$$

$$I = \frac{8Wl^3}{48E} = \frac{8 \times 6000 \times (240)^3}{48 \times 29,000,000} = 476$$

If x = distance from neutral axis to most remote fiber (½ beam depth in this case), then $Z = I/x$, and the table on Handbook **page 2513** shows that a 15-inch, 50-pound I-beam should be used because it has a section modulus of 64.8 and 476/7.5 = 63.5 nearly.

If 476 were divided by 6 (½ depth of a 12-inch I-beam), the result would be much higher than the section modulus of any standard 12-inch I-beam (476 ÷ 6 = 79.3); moreover, 576 ÷ 9 = 53, which shows that an 18-inch I-beam is larger than is necessary because the lightest beam of this size has a section modulus of 81.9.

Example 8: If the speed of a motor is 1200 revolutions per minute and if its driving pinion has a pitch diameter of 3 inches, determine the torsional moment to which the pinion shaft is subjected, assuming that 10 horsepower is being transmitted.

If W = tangential load in pounds, H = the number of horsepower, and V = pitch-line velocity in feet per minute,

Copyright 2004, Industrial Press, Inc., New York, NY

$$W = \frac{33,000 \times H}{V}$$
$$= \frac{33,000 \times 10}{943} = 350 \text{ pounds}$$

The torsional moment = $W \times$ pitch radius of pinion = 350×1.5 = 525 pound-inches (or inch-pounds).

Example 9: If the pinion referred to in **Example 8** drives a gear having a pitch diameter of 12 inches, to what torsional or turning moment is the gear shaft subjected?

The torque or torsional moment in any case = pitch radius of gear × tangential load. The latter is the same for both gear and pinion; hence, torsional moment of gear = $350 \times 6 = 2100$ inch-pounds.

The torsional moment or the turning effect of a force that tends to produce rotation depends upon (1) the magnitude of the force acting, and (2) the distance of the force from the axis of rotation, measuring along a line at right angles to the line of action of the force.

PRACTICE EXERCISES FOR SECTION 16

(See *Answers to Practice Exercises For Section 16* on page 233)

1) What is a "factor of safety," and why are different factors used in machine design?

2) If the ultimate strength of a steel rod is 60,000 pounds per square inch, and the factor of safety is 5, what is the equivalent working stress?

3) If a steel bar must withstand a maximum pull of 9000 pounds and if the maximum nominal stress must not exceed 12,000 pounds per square inch, what diameter bar is required?

4) Is a steel rod stronger when at ordinary room temperature or when heated to 500°F?

5) What is the meaning of the term "elastic limit"?

6) Approximately what percentages of copper and zinc in brass result in the greatest tensile strength?

7) If four 10-foot-long pipes are to be used to support a water tank installation weighing 100,000 pounds, what diameter standard weight pipe is required?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 17

DESIGN OF SHAFTS AND KEYS FOR POWER TRANSMISSION

HANDBOOK Pages 299 – 307 and Pages 2363 – 2387

This section is a review of the general procedure in designing shafts to resist both torsional and combined torsional and bending stresses. The diameter of a shaft through which power is transmitted depends, for a given shaft material, upon the amount and kind of stress or stresses to which the shaft is subjected. To illustrate the general procedure, we shall assume first that the shaft is subjected only to a uniform torsional or twisting stress and that there is no additional bending stress that needs to be considered in determining the diameter.

Example 1: A lineshaft carrying pulleys located close to the bearings is to transmit 50 horsepower at 1200 revolutions per minute. If the load is applied gradually and is steady, what diameter steel shaft is required, assuming that the pulleys are fastened to the shaft by means of keys and that the bending stresses caused by the pull of the belts are negligible?

According to the former American Standard Association's Code for the Design of Transmission Shafting, the diameter of shaft required to meet the stated conditions can be determined by using the following formula (Formula (16b), Handbook page 304).

$$D = B \times \sqrt[3]{\frac{321,000 K_t P}{S_s N}}$$

In this formula, D = required shaft diameter in inches; B = a factor, which for solid shafts is taken as 1; K_t = combined shock and fatigue factor; P = maximum horsepower transmitted by shaft; S_s = maximum allowable torsional shearing stress in pounds per square inch; and N = shaft speed in revolutions per minute.

Copyright 2004, Industrial Press, Inc., New York, NY

From Table 1 on Handbook **page 305**, $K_t = 1.0$ for gradually applied and steady loads, and from Table 2 the recommended maximum allowable working stress for "Commercial Steel" shafting with keyways subjected to pure torsion loads is 6000 pounds per square inch. By substituting in the formula,

$$D = 1 \times \sqrt[3]{\frac{321,000 \times 1.0 \times 50}{6000 \times 1200}} = 1.306 \text{ inches}$$

The nearest standard size transmission shafting from the table on Handbook **page 303** is $1\frac{7}{16}$ inches.

Example 2: If, in **Example 1**, the shaft diameter had been determined by using Formula (5b), Handbook **page 299**, what would the result have been and why?

$$D = \sqrt[3]{\frac{53.5P}{N}} = \sqrt[3]{\frac{53.5 \times 50}{1200}} = 1.306 \text{ inches}$$

This formula gives the same shaft diameter as was previously determined because it is simplified form of the first formula used and contains the same values of K_t and S_s, but combined as the single constant 53.5. For lineshafts carrying pulleys under conditions ordinarily encountered, this simplified formula is usually quite satisfactory; but, where conditions of shock loading are known to exist, it is safer to use Formula (16b), Handbook **page 304**, which takes such conditions into account.

Shafts Subjected to Combined Stresses.— The preceding formulas are based on the assumption that the shaft is subjected to torsional stresses only. However, many shafts must withstand stresses that result from combinations of torsion, bending, and shock loading. In such conditions it is necessary to use formulas that take such stresses into account.

Example 3: Suppose that, after the lineshaft in **Example 1** was installed, it became necessary to relocate a machine that was being driven by one of the pulleys on the shaft. Because of the new machine location, it was necessary to move the pulley on the lineshaft farther away from the nearest bearing, and, as a result, a bending moment of 2000 inch–pounds was introduced. Is the $1\frac{7}{16}$–

Copyright 2004, Industrial Press, Inc., New York, NY

inch diameter shaft sufficient to take this additional stress, or will it be necessary to relocate the bearing to provide better support?

Since there are now both bending and torsional loads acting on the shaft, Formula (18b), Handbook **page 304** should be used to compute the required shaft diameter. This diameter is then compared with the $1\frac{7}{16}$ inch diameter previously determined.

$$D = B \times \sqrt[3]{\frac{5.1}{p_t}\sqrt{(K_m M)^2 + \left(\frac{63{,}000 K_t P}{N}\right)^2}}$$

In this formula B, K_t, P, and N are quantities previously defined and p_t = maximum allowable shearing stress under combined loading conditions in pounds per square inch; K_m = combined shock and fatigue factor; and M = maximum bending moment in inch-pounds.

From Table 1 on Handbook **page 305**, $K_m = 1.5$ for gradually applied and steady loads and from Table 2, $p_t = 6000$ pounds per square inch. By substituting in the formula,

$$D = 1 \times \sqrt[3]{\frac{5.1}{6000}\sqrt{(1.5 \times 2000)^2 + \left(\frac{63{,}000 \times 1 \times 50}{1200}\right)^2}}$$

$$= \sqrt[3]{\frac{5.1}{6000}\sqrt{9000000 + 6,890,625}} = \sqrt[3]{\frac{5.1}{6000} \times 3986}$$

$$= \sqrt[3]{3.388} = 1.502 \text{ inches or about } 1\tfrac{1}{2} \text{ inches}$$

This diameter is larger than the $1\frac{7}{16}$-inch diameter used for the shaft in **Example 1**, so it will be necessary to relocate the bearing closer to the pulley, thus reducing the bending moment. The $1\frac{7}{16}$-inch diameter shaft will then be able to operate within the allowable working stress for which it was originally designed.

Design of Shafts to Resist Torsional Deflection.— Shafts must often be proportioned not only to provide the strength required to transmit a given torque, but also to prevent torsional deflection (twisting) through a greater angle than has been found satisfactory for a given type of service. This requirement is particularly true for machine shafts and machine–tool spindles.

Copyright 2004, Industrial Press, Inc., New York, NY

For ordinary service, it is customary that the angle of twist of machine shafts be limited to $\frac{1}{10}$ degree per foot of shaft length, and for machine shafts subject to load reversals, $\frac{1}{20}$ degree per foot of shaft length. As explained in the Handbook, the usual design procedure for shafting that is to have a specified maximum angular deflection is to compute the diameter of shaft required based on both deflection and strength considerations and then to choose the larger of the two diameters thus determined.

Example 4: A 6-foot-long feed shaft is to transmit a torque of 200 inch–pounds. If there are no bending stresses, and the shaft is to be limited to a torsional deflection of $\frac{1}{20}$ degree per foot of length, what diameter shaft should be used? The shaft is to be made of cold drawn steel and is to be designed for a maximum working stress of 6000 pounds per square inch in torsion.

The diameter of shaft required for a maximum angular deflection a is given by Formula (13), Handbook **page 301**.

$$D = 4.9 \sqrt[4]{\frac{Tl}{G\alpha}}$$

In this formula T = applied torque in inch–pounds; l = length of shaft in inches; G = torsional modulus of elasticity, which, for steel, is 11,500,000 pounds per square inch; and α = angular deflection of shaft in degrees.

In the problem at hand, $T = 200$ inch–pounds; $l = 6 \times 12 = 72$ inches; and $\alpha = 6 \times 1/20 = 0.3$ degree.

$$D = 4.9 \sqrt[4]{\frac{200 \times 72}{11,500,000 \times 0.3}} = 4.9 \sqrt[4]{0.0041739}$$

$$= 4.9 \times 0.254 = 1.24 \text{ inches}$$

The diameter of the shaft based on strength considerations is obtained by using Formula (3a), Handbook **page 299**.

$$D = \sqrt[3]{\frac{5.1T}{S_s}} = \sqrt[3]{\frac{5.1 \times 200}{6000}} = \sqrt[3]{0.17} = 0.55 \text{ inch}$$

From the above calculations, the diameter based on torsional deflection considerations is the larger of the two values obtained, so the nearest standard diameter, $1\frac{1}{4}$ inches, should be used.

Copyright 2004, Industrial Press, Inc., New York, NY

Selection of Key Size Based on Shaft Size.— Keys are generally proportioned in relation to shaft diameter instead of in relation to torsional load to be transmitted because of practical reasons such as standardization of keys and shafts. Standard sizes are listed in the table, *Key Size Versus Shaft Diameter ANSI B17.1-1967 (R1998)* on Handbook **page 2363**. Dimensions of both square and rectangular keys are given, but for shaft diameters up to and including 6½ inches, square keys are preferred. For larger shafts, rectangular keys are commonly used.

Two rules that base key length on shaft size are: (1) $L = 1.5D$ and (2) $L = 0.3D^2 \div T$, where L = length of key, D = diameter of shaft, and T = key thickness.

If the keyset is to have fillets, and the key is to be chamfered, suggested dimensions for these modifications are given on Handbook **page 2368**. If a set screw is to be used over the key, suggested sizes are given in the table on Handbook **page 2368**.

Example 5: If the maximum torque output of a 2–inch diameter shaft is to be transmitted to a keyed pulley, what should be the proportions of the key?

According to the table on Handbook **page 2363**, a ½–inch square key would be preferred. If a rectangular key were selected, its dimensions would be ½ inch by ⅜ inch. According to rule 1 above, its length would be 3 inches.

The key and kissed may be proportioned so as to provide a clearance or an interference fit. The table on Handbook **page 2367** gives tolerances for widths and depths of keys and caskets to provide Class 1 (clearance) and Class 2 (interference) fits. An additional Class 3 (interference) fit, which has not been standardized, is mentioned on Handbook **page 2363** together with suggested tolerances.

Keys Proportioned According to Transmitted Torque.— As previously stated, if key sizes are based on shaft diameter, the dimensions of the key sometimes will be excessive, usually when a gear or pulley transmits only a portion of the total torque capacity of the shaft to which it is keyed. If excessively large keys are to be avoided, it may be advantageous to base the determination on the torque to be transmitted rather than on the shaft diameter and to

Copyright 2004, Industrial Press, Inc., New York, NY

use the dimensions thus determined as a guide in selecting a standard size key.

A key proportioned to transmit a specified torque may fail in service either by shearing or by crushing, depending on the proportions of the key and the manner in which it is fitted to the shaft and hub. The best proportions for a key are those that make it equally resistant to failure by shearing and by crushing. The safe torque in inch–pounds that a key will transmit, based on the allowable shearing stress of the key material, may be found from the formula:

$$T_s = L \times W \times \frac{D}{2} \times S_s \quad (1)$$

The safe torque based on the allowable compressive stress of the key material is found from the formula:

$$T_c = L \times \frac{H}{2} \times \frac{D}{2} \times S_c \quad (2)$$

(For Woodruff keys the amount that the key projects above the shaft is substituted for *H*/2.)

In these formulas, T_s = safe torque in shear; T_c = safe torque in compression; S_s = allowable shearing stress; S_c = allowable compressive stress; L = key length in inches; W = key width in inches; H = key thickness in inches; and D = shaft diameter in inches.

To satisfy the condition that the key be equally resistant to shearing and crushing, T_s should equal T_c, Thus, by equating Formulas (1) and (2), it is found that the width of the keyway in terms of the height of the keyway is:

$$W = \frac{HS_c}{2S_s} \quad (3)$$

For the type of steel commonly used in making keys, the allowable compressive stress S_c may be taken as twice the allowable shearing stress S_s, of the material if the key is properly fitted on all four sides. By substituting $S_c = 2S_s$ in Formula (3) it will be found that $W = H$, so that for equal strength in compression and shear a square key should be used.

If a rectangular key is used, and the thickness H is less than the width W, then the key will be weaker in compression than in shear

Copyright 2004, Industrial Press, Inc., New York, NY

so that it is sufficient to check the torque capacity of the key using **Formula (2)**.

Example 6: A 3–inch shaft is to deliver 100 horsepower at 200 revolutions per minute through a gear keyed to the shaft. If the hub of the gear is 4 inches long, what size key, equally strong in shear and compression, should be used? The allowable compressive stress in the shaft is not to exceed 16,000 pounds per square inch and the key material has an allowable compressive stress of 20,000 pounds per square inch and an allowable shearing stress of 15,000 pounds per square inch.

The first step is to decide on the length of the key. Since the hub of the gear is 4 inches long, a key of the same length may be used. The next step is to determine the torque that the key will have to transmit. By using Formula (2), Handbook **page 299**,

$$T = \frac{63,000P}{N} = \frac{63,000 \times 100}{200} = 31,500 \text{ inch-pounds}$$

To determine the width of the key, based on the allowable shearing stress of the key material, **Equation (1)** above is used.

$$T_s = L \times W \times \frac{D}{2} \times S_s$$

$$31,500 = 4 \times W \times \frac{D}{2} \times 15,000$$

or

$$W = \frac{31,250 \times 2}{15,000 \times 4 \times 3} = 0.350, \text{ say, } \tfrac{3}{8} \text{ inch}$$

In using **Equation (2)** to determine the thickness of the key, however, it should be noted that, if the shaft material has a different allowable compressive stress than the key material, then the lower of the two values should be used. The shaft material then has the lower allowable compressive stress, and the keyway in the shaft would fail by crushing before the key would fail. Therefore,

Copyright 2004, Industrial Press, Inc., New York, NY

$$T_c = L \times \frac{H}{2} \times \frac{D}{2} \times S_c$$

$$31,250 = 4 \times \frac{H}{2} \times \frac{3}{2} \times 16,000$$

or

$$H = \frac{31,250 \times 2 \times 2}{16,000 \times 4 \times 3} = 0.656 = 21/32 \text{ inch}$$

Therefore, the dimensions of the key for equal resistance to failure by shearing and crushing are $\frac{3}{8}$ inch wide, $\frac{21}{32}$ inch thick, and 4 inches long. If, for some reason, it is desirable to use a key shorter than 4 inches, say, 2 inches, then it will be necessary to increase both the width and thickness by a factor of 4 ÷ 2 if equal resistance to shearing and crushing is to be maintained. Thus the width would be $\frac{3}{8} \times \frac{4}{2} = \frac{3}{4}$ inch, and the thickness would be $\frac{21}{32} \times \frac{4}{2} = 1\frac{5}{16}$ inch for a 2–inch–long key.

Set–Screws Used to Transmit Torque.— For certain applications it is common practice to use set–screws to transmit torque because they are relatively inexpensive to install and permit axial adjustment of the member mounted on the shaft. However, set–screws depend primarily on friction and the shearing force at the point of the screw, so they are not especially well–suited for high torques or where sudden load changes take place.

One rule for determining the proper size of a set–screw states that the diameter of the screw should equal $\frac{5}{16}$ inch plus one–eighth the shaft diameter. The holding power of set–screws selected by this rule can be checked using the formula on **page 1637** of the Handbook.

PRACTICE EXERCISES FOR SECTION 17

(See *Answers to Practice Exercises For Section 17* on page 233)

1) What is the polar section modulus of a shaft 2 inches in diameter?

2) If a 3–inch shaft is subjected to a torsional or twisting moment of 32,800 pound–inches, what is the equivalent torsional or shearing stress?

Copyright 2004, Industrial Press, Inc., New York, NY

3) Is the shaft referred to in Exercise 2 subjected to an excessive torsional stress?

4) If a 10–horsepower motor operating at its rated capacity connects by a belt with a 16–inch pulley on the driving shaft of a machine, what is the load tangential to the pulley rim and the resulting twisting moment on the shaft, assuming that the rim speed of the driven pulley is 600 feet per minute?

5) How is the maximum distance between bearings for steel lineshafting determined?

6) What are "gib–head" keys, and why are they used on some classes of work?

7) What is the distinctive feature of Woodruff keys?

8) What are the advantages of Woodruff keys?

9) If a $\frac{3}{8}$–inch wide keyseat is to be milled into a $1\frac{1}{2}$–inch diameter shaft and if the keyseat depth is $\frac{3}{16}$ inch (as measured at one side), what is the depth from the top surface of the shaft or the amount to sink the cutter after it grazes the top of the shaft?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 18

SPLINES

HANDBOOK Pages 2156 – 2188

This section of the Handbook shows how to calculate the dimensions of involute splines and how to provide specifications for manufacturing drawings. Many types of mechanical connections between shafts and hubs are available for both fixed and sliding applications. Among these connections are the ordinary key and keyway (Handbook page 2363 to 2388), multiple keys and keyways, three- and four-lobed polygon shaft and hub connections, and involute splines of both inch dimension and metric module sizes.

The major advantages of involute splines are that they may be manufactured on the same equipment used to manufacture gears, they may be used for fixed and interference fit connections as well as for sliding connections, and they are stronger than most other connections with the exception of polygon-shaped members.

The section in the Handbook on involute splines, page 2156 to 2175, provides tables, data, formulas, and diagrams for American Standard splines made to both inch and metric module systems. Both systems share common definitions of terms, although the symbols used to identify dimensions and angles may differ, as shown on Handbook page 2177. The two systems do not provide for interchangeability of parts; the new metric module standard is the American National Standards Institute version of the International Standards Organization involute spline standard, which is based upon metric, not inch, dimensions.

Example 1: A metric module involute spline pair is required to meet the following specification: pressure angle $\alpha_D = 30°$; module $m = 5$; number of teeth $Z = 32$; fit class = H/h; tolerance class 5 for both the internal and external splines; flat root design for both members; length of engagement of the splines is 100 mm.

Copyright 2004, Industrial Press, Inc., New York, NY

Table 13 beginning on Handbook **page 2179** provides all the formulas necessary to calculate the dimensions of these splines. Pitch diameter:

$$D = mZ = 5 \times 32 = 160 \text{ mm} \quad (1)$$

Base diameter:

$$DB = mZ\cos\alpha_D = 160 \times \cos\alpha_D = 160 \times \cos 30° = 160 \times 0.86603 = 138.5641 \text{ mm} \quad (2)$$

Circular pitch:

$$p = \pi m = 3.1416 \times 5 = 15.708 \quad (3)$$

Base pitch:

$$p_b = \pi m\cos\alpha_D = \pi \times 5 \times 0.86603 = 13.60350 \quad (4)$$

Tooth thickness modification:

$$es = 0 \quad (5)$$

in accordance with the footnote to Table 14, Handbook **page 2180**, and the Fit Classes paragraph on **page 2177** that refers to H/h fits.

Minimum major diameter, internal spline,

$$DEI \text{ min} = m(Z + 1.8) = 5 \times (32 + 1.8) = 169.000 \quad (6)$$

Maximum major diameter, internal spline,

$$DEI \text{ max} = DEI \text{ min} + (T + \lambda)/(\tan\alpha_D) = 169.000 + 0.248/\tan 30° = 169.4295 \text{ mm} \quad (7)$$

In this last calculation, the value of $(T + \lambda) = 0.248$ for class 7 was calculated using the formula in Table 15, Handbook **page 2180**, as follows:

$$\text{i*} = 0.001(0.45\sqrt[3]{D} + 0.001D) = 0.001(0.45\sqrt[3]{160} + 0.001 \times 160) = 0.00260 \quad (8a)$$

$$\text{i**} = 0.001(0.45\sqrt[3]{7.85398} + 0.001 \times 7.85398) = 0.00090 \quad (8b)$$

Copyright 2004, Industrial Press, Inc., New York, NY

In this calculation, 7.85398 is the value of S_{bsc} calculated from the formula $S_{bsc} = 0.5\pi m$ given in the table starting on Handbook **page 2179**.

$$\begin{aligned}(T + \lambda) &= 40\text{i}^* + 160\text{i}^* \\ &= 40 \times 0.00260 + 160 \times 0.00090 \\ &= 0.248 \text{ mm}\end{aligned} \quad (8c)$$

Form diameter, internal spline,

$$\begin{aligned}DFI &= m(Z + 1) + 2c_F \\ &= 5(32 + 1) + 2 \times 0.1m \\ &= 5(32 + 1) + 2 \times 0.1 \times 5 \\ &= 166 \text{ mm}\end{aligned} \quad (9)$$

In the above calculation the value of $c_F = 0.1m$ is taken from the diagram on Handbook **page 2181**, and the corresponding formula for form clearance on Handbook **page 2179**. Minimum minor diameter, internal spline,

$$\begin{aligned}DII \text{ min} &= DFE + 2c_F \\ &= 154.3502 + 2 \times 0.1 \times 5 \\ &= 155.3502 \text{ mm}\end{aligned} \quad (10)$$

The *DFE* value of 154.3502 used in this calculation was calculated from the formula on Handbook **page 2179** as follows: DB = 138.564 from step (2); D = 160 from step (1); $h_s = 0.6m = 3.0$ from the last formula in the table starting on Handbook **page 2179**; es = 0 from step (5); sin 30° = 0.50000; tan 30° = 0.57735. Therefore,

$$\begin{aligned}DFE &= 2 \times \sqrt{(0.5 \times 138.564)^2 + \left[0.5 \times 160 \times 0.50000 - \frac{0.6 \times 5 + \left(\frac{0.5 \times 0}{0.57735}\right)}{0.50000}\right]^2} \\ &= 154.3502\end{aligned} \quad (11)$$

Copyright 2004, Industrial Press, Inc., New York, NY

Maximum minor diameter, internal spline,

$$\begin{aligned} DII\ \text{max} &= DII\ \text{min} + (0.2m^{0.667} - 0.1m^{-0.5}) \\ &= 155.3502 + 0.58 \\ &= 155.9302\ \text{mm} \end{aligned} \tag{12}$$

The value 0.58 used in this calculation comes from the footnote c to the table on Handbook **page 2179**. Circular space width, basic,

$$E_{bsc} = 0.5\pi m = 0.5 \times 3.1416 \times 5 = 7.854\ \text{mm} \tag{13}$$

Circular space width, minimum effective,

$$EV\ \text{min} = E_{bsc} = 7.854\ \text{mm} \tag{14}$$

Circular space width, maximum actual,

$$\begin{aligned} E\ \text{max} &= EV\ \text{min} + (T + \lambda) \\ &= 7.854 + 0.0992 \quad \text{from step (16c)} \\ &= 7.9532\ \text{mm} \end{aligned} \tag{15}$$

The value of $(T + \lambda)$ calculated in step (16c) is based upon class 5 fit stated at the beginning of the example. The value calculated in step (8c), on the other hand, is based upon class 7 fit as required by the formula in step (7). For class 5 fit, using the formula given in Table 15, Handbook **page 2180**:

$$\text{i*} = 0.00260 \quad \text{from step (8a)} \tag{16a}$$

$$\text{i**} = 0.00090 \quad \text{from step (8b)} \tag{16b}$$

$$\begin{aligned} (T + \lambda) &= 16\text{i*} + 64\text{i**} = 16 \times 0.00260 + 64 \times 0.00090 \\ &= 0.0992\ \text{mm} \end{aligned} \tag{16c}$$

Circular space width, minimum actual,

$$E\ \text{min} = EV\ \text{min} + \lambda = 7.854 + 0.045 = 7.899\ \text{mm} \tag{17}$$

The value of λ used in this formula was calculated from the formulas for class 5 fit in the Table 16 and the formula in the text on Handbook **page 2181** as follows:

Copyright 2004, Industrial Press, Inc., New York, NY

$$F_p = 0.001(3.55\sqrt{5 \times 32 \times 3.1416/2} + 9) = 0.065 \text{ mm} \quad (18a)$$

$$f_f = 0.001[2.5 \times 5(1 + 0.0125 \times 32) + 16] = 0.034 \text{ mm} \quad (18b)$$

$$F_\beta = 0.001(1 \times \sqrt{100} \times 5) = 0.015 \text{ mm} \quad (18c)$$

$$\lambda = 0.6\sqrt{(0.065)^2 + (0.034)^2 + (0.015)^2} = 0.045 \text{ mm} \quad (18d)$$

Circular space width, maximum effective,

$$\begin{aligned} EV \text{ max} &= E \text{ max} - \lambda \\ &= 7.9532 \text{ from step (15)} - 0.045 \text{ from step (18d)} \\ &= 7.9082 \text{ mm} \end{aligned} \quad (19)$$

Maximum major diameter, external spline,

$$\begin{aligned} DEE \text{ max} &= m(Z+1) - es/\tan\alpha_D = 5(32+1) - 0 \\ &= 165 \text{ mm} \end{aligned} \quad (20)$$

The value 0 in this last calculation is from Table 17, Handbook **page 2181**, for h class fit.

Minimum major diameter, external spline, is calculated using the results of step **(20)** and footnote c on Handbook **page 2180**,

$$\begin{aligned} DEE \text{ min} &= DEE \text{ max} - (0.2m^{0.667} - 0.01m^{-0.5}) \\ &= 165 - 0.58 = 164.42 \text{ mm} \end{aligned} \quad (21)$$

Maximum minor diameter, external spline,

$$\begin{aligned} DIE \text{ max} &= m(Z - 1.8) - es/\tan\alpha_D \\ &= 5(32 - 1.8) - 0 \\ &= 151 \text{ mm} \end{aligned} \quad (22)$$

The value 0 in this calculation is from Table 17, Handbook **page 2181**, for h class fit.

Minimum minor diameter, external spline, is calculated using the results of steps **(22)** and **(7)**,

Copyright 2004, Industrial Press, Inc., New York, NY

$$\begin{aligned} DIE\ \text{min} &= DIE\ \text{max} - (T + \lambda)/\tan\alpha_D \\ &= 151 - 0.248/\tan 30^\circ \\ &= 151 - 0.4295 \\ &= 150.570\ \text{mm} \end{aligned} \quad (23)$$

Circular tooth thickness, basic, has been taken from the step **(13)**

$$S_{bsc} = 7.854\ \text{mm} \quad (24)$$

Circular tooth thickness, maximum effective, is calculated using the results of steps **(13)** and step **(5)**,

$$\begin{aligned} SV\ \text{max} &= S_{bsc} - es \\ &= 7.854 - 0 \\ &= 7.854\ \text{mm} \end{aligned} \quad (25)$$

Circular tooth thickness, minimum actual, is calculated using the results of steps **(25)** and **(16c)**,

$$S\ \text{min} = SV\ \text{max} - (T + \lambda) = 7.854 - 0.0992 = 7.7548\ \text{mm} \quad (26)$$

Circular tooth thickness, maximum actual, is calculated using the results of steps **(25)** and **(18d)**,

$$\begin{aligned} S\ \text{max} &= SV\ \text{max} - \lambda \\ &= 7.854 - 0.045 \\ &= 7.809\ \text{mm} \end{aligned} \quad (27)$$

Circular tooth thickness, minimum effective, is calculated using the results of steps **(26)** and **(18d)**,

$$\begin{aligned} SV\ \text{min} &= S\ \text{min} + \lambda \\ &= 7.754 + 0.045 \\ &= 7.799\ \text{mm} \end{aligned} \quad (28)$$

Example 2: As explained on Handbook **page 2174**, spline gages are used for routine inspection of production parts. However, as part of an analytical procedure to evaluate effective space width or effective tooth thickness, measurements with pins are often used. Measurements with pins are also used for checking the actual space width and tooth thickness of splines during the machining process. Such measurements help in making the necessary size

Copyright 2004, Industrial Press, Inc., New York, NY

adjustments both during the setup process and as manufacturing proceeds. For the splines calculated in **Example 1**, what are the pin measurements for the tooth thickness and space width?

The maximum space width for the internal spline is 7.953 mm from step **(15)** in **Example 1**. The minimum tooth thickness for the external spline is 7.755 mm from step **(26)**.

Handbook **page 2175** gives a method for calculating pin measurements for splines. This procedure was developed for inch-dimension splines. However, it may be used for metric module splines simply by replacing P wherever it appears in a formula by $1/m$; and by using millimeters instead of inches as dimensional units throughout.

For two-pin measurement *between* pins for the *internal* spline, steps 1, 2, and 3 on Handbook **page 2175** are used as follows:

$$\begin{aligned} \text{inv}\,\phi_i &= 7.953/160 + \text{inv}\,30^\circ - 8.64/138.564 \\ &= 0.049706 + 0.053751 - 0.062354 = 0.041103 \end{aligned} \tag{1}$$

The numbers used in this calculation are taken from the results in **Example 1** except for the involute of 30°, which is from the table on **page 105** of the Handbook, and 8.64 is the diameter of the wire as calculated from the formula on Handbook **page 2175**, $1.7280/P$ in which $1/m$ has been substituted for P to give $1.7280m = 1.7280 \times 5 = 8.64$. Note that the symbols on **page 2175** are not the same as those used in **Example 1**. This is because the metric standard for involute splines uses different symbols for the same dimensions. The table on **page 2177** of the Handbook shows how these different symbols compare.

The value of $\text{inv}\,\phi_i = 0.041103$ is used to enter the table on Handbook **page 105** to find, by interpolation,

$$\phi_i = 27^\circ 36' 20'' \tag{2}$$

From a calculator find

$$\sec 27^\circ 36' 20'' = 1.1285 \tag{3}$$

Calculate the measurement between wires:

$$\begin{aligned} M_i &= D_b \sec\phi_i - d_i = 138.564 \times 1.1285 - 8.64 \\ &= 147.729 \text{ mm} \end{aligned} \tag{4}$$

Copyright 2004, Industrial Press, Inc., New York, NY

For two-pin measurement *over* the teeth of *external* splines, steps 1, 2, and 3 on Handbook **page 2175** are used as follows:

$$\begin{aligned} \text{inv}\,\phi_e &= 7.755/160 + 0.053751 + 9.6/138.564 - 3.1416/32 \\ &= 0.073327 \end{aligned} \quad (5)$$

Therefore, from Handbook **page 106**, $\phi_e = 32°59'$ and, from a calculator, sec $32°59' = 1.1921$. From the formula in step 3 on Handbook **page 2175**:

$$M_e = 138.564 \times 1.1921 + 9.6 = 174.782 \text{ mm} \quad (6)$$

The pin diameter 9.6 in this calculation was calculated from the formula in step 3 on Handbook **page 2175** by substituting $1/m$ for P in the formula $d_e = 1.9200/P = 1.9200m$.

Specifying Spline Data on Drawings.— As stated on Handbook **page 2169**, if the data specified on a spline drawing are suitably arranged and presented in a consistent manner, it is usually not necessary to provide a graphic illustration of the spline teeth. Table 6 on Handbook **page 2168** illustrates a flat root spline similar to the one in **Example 1** except that it is an inch-dimension spline. The method of presenting drawing data for metric module splines differs somewhat from that shown on **page 2168** in that the number of decimal places used for metric spline data is sometimes less than that for the corresponding inch-dimension system.

Example 3: How much of the data calculated or given in **Example 1** and **2** should be presented on the spline drawing?

For the internal spline the data required to manufacture the spline should be presented as follows, including the number of decimal places shown:

Internal Involute Spline Data

Flat Root Side Fit	Tolerance class 5H
Number of Teeth	32
Module	5
Pressure Angle	30 deg
Base Diameter	138.5641 REF

Copyright 2004, Industrial Press, Inc., New York, NY

Internal Involute Spline Data *(Continued)*

Pitch Diameter	160.0000 REF
Major Diameter	169.42 Max
Form Diameter	166.00
Minor Diameter	155.35/155.93
Circular Space Width:	
Max Actual	7.953
Mm Effective	7.854
Max Measurement Between Pins	147.729 REF
Pin Diameter	8.640

For the external spline:

External Involute Spline Data

Flat Root Side Fit	Tolerance Class 5h
Number of Teeth	32
Module	5
Pressure Angle	30 deg
Base Diameter	138.5641 REF
Pitch Diameter	160.0000 REF
Major Diameter	164.42/165.00
Form Diameter	154.35
Minor Diameter	150.57 MIN
Circular Tooth Thickness:	
Mm Actual	7.854
Max Effective	7.809
Mm Measurement Over Pins:	74.782 REF
Pin Diameter	9.6

Copyright 2004, Industrial Press, Inc., New York, NY

PRACTICE EXERCISES FOR SECTION 18

(See *Answers to Practice Exercises For Section 18* on page 234)

1) What is the difference between a “soft” conversion of a standard and a “hard” system?

2) The standard for metric module splines does not include a major diameter fit. What standard does provide for a major diameter fit?

3) What is an involute serration and is it still called this in American standards?

4) What are some of the advantages of involute splines?

5) What is the meaning of the term “effective tooth thickness”?

6) What advantage is there in using an odd number of spline teeth?

7) If a spline connection is misaligned, fretting can occur at certain combinations of torque, speed, and misalignment angle. Is there any method for diminishing such damage?

8) For a given design of spline is there a method for estimating the torque capacity based upon wear? Based on shearing stress?

9) What does REF following a dimension of a spline mean?

10) Why are fillet root splines sometimes preferred over flat root splines?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 19

PROBLEMS IN DESIGNING AND CUTTING GEARS

HANDBOOK Pages 2029 – 2155

In the design of gearing, there may be three distinct types of problems. These are: (1) determining the relative sizes of two or more gears to obtain a given speed or series of speeds; (2) determining the pitch of the gear teeth so that they will be strong enough to transmit a given amount of power; and (3) calculating the dimensions of a gear of a given pitch, such as the outside diameter, the depth of the teeth, and other dimensions needed in cutting the gear.

When the term "diameter" is applied to a spur gear, the pitch diameter is generally referred to and not the outside diameter. In calculating the speeds of gearing, the pitch diameters are used and not the outside diameters, because when gears are in mesh, the imaginary pitch circles roll in contact with each other.

Calculating Gear Speeds.— The simple rules for calculating the speeds of pulleys beginning on Handbook **page 2388** may be applied to gearing, provided either the pitch diameters of the gears or the numbers of teeth are substituted for the pulley diameters. Information on gear speeds, especially as applied to compound trains of gearing, also will be found in the section dealing with lathe change gears beginning on Handbook **page 1946**. When gear trains must be designed to secure unusual or fractional gear ratios, the directions beginning on Handbook **page 1947** will be found very useful. A practical application of these methods is shown by examples beginning on Handbook **page 1951**.

Planetary or epicyclic gearing is an increasingly important class of power transmission in various industries because of compactness, efficiency, and versatility. The rules for calculating rotational speeds and ratios are different from those for other types of gear-

Copyright 2004, Industrial Press, Inc., New York, NY

ing. Formulas for the most commonly used types of planetary gears are provided on Handbook **pages 2116** to **2119**.



Fig. 1. Combination Pulley and Compound Gear Drive

Example 1: The following example illustrates the method of calculating the speed of a driven shaft in a combination belt and gear drive when the diameters of the pulleys and the pitch diameters of the gears are known, and the number of revolutions per minute of the driving shaft is given. If driving pulley *A*, **Fig. 1**, is 16 inches in diameter, and driven pulley *B*, 6 inches in diameter, and the pitch diameter of driving gear *C* is 12 inches, driving gear *D* is 14 inches, driven gear *E*, 7 inches, driven gear *F*, 6 inches, and driving pulley *A* makes 60 revolutions per minute, determine the number of revolutions per minute of *F*.

$$\frac{16 \times 12 \times 14}{6 \times 7 \times 6} \times 60 = 640 \text{ revolutions per minute}$$

The calculations required in solving problems of this kind can be simplified if the gears are considered as pulleys having diameters equal to their pitch diameters. When this is done, the rules that apply to compound belt drives can be used in determining the speed or size of the gears or pulleys.

Substituting the numbers of teeth in each gear for the pitch diameter gives the same result as when the pitch diameters are used.

Example 2: If driving spur gear *A* (**Fig. 2**) makes 336 revolutions per minute and has 42 teeth, driven spur gear *B*, 21 teeth, driving bevel gear *C*, 33 teeth, driven bevel gear *D*, 24 teeth, driving worm *E*, one thread, and driven worm-wheel *F*, 42 teeth, determine the number of revolutions per minute of *F*.

When a combination of spur, bevel, and wormgearing is employed to transmit motion and power from one shaft to another,

Copyright 2004, Industrial Press, Inc., New York, NY

the speed of the driven shaft can be found by the following method: Consider the worm as a gear having one tooth if it is single-threaded and as a gear having two teeth if double-threaded, etc. The speed of the driving shaft can then be found by applying the rules for ordinary compound spur gearing. In this example,

$$\frac{42 \times 33 \times 1}{21 \times 24 \times 42} \times 336 = 22 \text{ revolutions per minute}$$



Fig. 2. Combination of Spur, Bevel, and Worm Gearing

If the pitch diameters of the gears are used instead of the number of teeth in making calculations, the worm should be considered as a gear having a pitch diameter of 1 inch if single-threaded, and 2 inches if a double-threaded worm, etc.

Example 3: If a worm is triple-threaded and makes 180 revolutions per minute, and the worm-wheel is required to make 5 revolutions per minute, determine the number of teeth in the worm-wheel.

Rule: Multiply the number of threads in the worm by its number of revolutions per minute, and divide the product by the number of revolutions per minute of the worm-wheel. By applying this rule,

$$\frac{3 \times 180}{5} = 108 \text{ teeth}$$

Example 4: A 6-inch grinding machine with a spindle speed of 1773 revolutions per minute, for a recommended peripheral speed of 6500 feet per minute (as figured for a full-size 14-inch wheel for this size of machine), has two steps on the spindle pulley; the large step is 5.5 inches in diameter and the small step, 4 inches. What should be the minimum diameter of the wheel before the belt is shifted to the smaller step in order to select a peripheral wheel speed of 6500 feet per minute?

Copyright 2004, Industrial Press, Inc., New York, NY

As the spindle makes 1773 revolutions per minute when the belt is on the large pulley, its speed with the belt on the smaller pulley may be determined as follows: 5.5:4 = x:1773, or (5.5 × 1773)/4 = 2438 revolutions per minute, approximately. To obtain the same peripheral speed as when the belt is on the large pulley, the diameters of the grinding wheel should be 14:x = 2438:1773, or (14 × 1773)/2438 = 10.18 inches. Therefore, when the grinding wheel has been worn down to a diameter of 10.18 inches, or approximately $10\frac{3}{16}$ inches, the spindle belt should be shifted to the smaller step of the spindle pulley to obtain a peripheral speed of 6500 feet per minute. The method used in this example may be reduced to a formula for use with any make of grinding machine having a two-step spindle pulley.

Let

D = diameter of wheel, full size
D_1 = diameter of wheel, reduced size
d = diameter of large pulley step
d_1 = diameter of small pulley step
V = spindle rpm, using large pulley step
v = spindle rpm, using small pulley step

Then,

$$v = \frac{dV}{d_1}; \quad D_1 = \frac{DV}{v}$$

Example 5: Planetary gear sets are widely used in power transmission because of their compactness and relatively high efficiency when properly designed. The simple planetary configuration shown in Fig. 10 on Handbook **page 2117** is typical of high-efficiency designs. If A = 20 and C = 40, what is the rotation of the driver D per revolution of the follower?

Using the formula given on Handbook **page 2117**,

$$D = 1 + \frac{C}{A} = 1 + \frac{40}{20} = 3$$

Example 6: If, in **Example 5**, the diameter of the fixed gear is doubled to C = 80, what effect does that produce in the rotation of the drive D?

Copyright 2004, Industrial Press, Inc., New York, NY

$$D = 1 + \frac{80}{20} = 5$$

Note that doubling the size of the fixed gear C does not double the ratio or the driver speed of the gear set because the overall ratio is always plus the ratio of C to A.

Example 7: The compound type of planetary gear shown in Fig.13 on Handbook **page 2116** can provide high revolution ratios, although the efficiency decreases as the ratio increases. What is the rotation of the follower F when $B = 61$, $C = 60$, $x = 19$, and $y = 20$?

$$F = 1 - \left(\frac{C \times x}{y \times B}\right) = 1 - \left(\frac{60 \times 19}{20 \times 61}\right) = 1 - \frac{57}{61} = 0.06557$$

Example 8: In **Example 7**, what is the rotation of the driver per revolution of the follower?

$$\text{Driver} = \frac{1}{\text{follower}} = \frac{1}{0.06557} = 15.25$$

Note that in compound planetary gear drives the sum of meshing tooth pairs must be equal for proper meshing. Thus, $C + y = x + B$.

Diametral Pitch of a Gear.— The diametral pitch represents the number of gear teeth for each inch of pitch diameter and, therefore, equals the number of teeth divided by the pitch diameter. The term diametral pitch as applied to bevel gears has the same meaning as with spur gears. This method of basing the pitch on the relation between the number of teeth and the pitch diameter is used almost exclusively in connection with cut gearing and to some extent for cast gearing. The circular pitch or the distance between, the centers of adjacent teeth measured along the pitch circle is used for cast gearing but very little for cut gearing except very large sizes. If 3.1416 is divided by the diametral pitch, the quotient equals the circular pitch, or, if the circular pitch is known, the diametral pitch may be found by dividing 3.1416 by the circular pitch. The pitch of the gear teeth may depend primarily upon the strength required to transmit a given amount of power.

Power Transmitting Capacity of Bevel Gears.— The design of bevel gears to meet a set of operating conditions is best accomplished in four steps: (1) determine the design load upon which the

Copyright 2004, Industrial Press, Inc., New York, NY

bevel gear sizes will be based; (2) using design literature and charts available from gear manufacturers and distributors, select approximate gear and pinion sizes to satisfy the load requirements; (3) determine the maximum safe tooth load, based on gear geometry and material, using manufacturer's and/or AGMA formulas; and (4) determine the safe horsepower capacity of the gears, based on safe tooth load and tooth surface durability. The horsepower capacity of the gears should meet or exceed the design load requirements. To check the capacity of an existing bevel gear drive, only steps (3) and (4) are necessary.

Dimensions and Angles Required in Producing Gears.— Many of the rules and formulas given in the gear section of the Handbook beginning on **page 2029** are used in determining tooth dimensions, gear blank sizes, also angles in bevel, helical, and wormgearing. These dimensions or angles are required on the working drawings used in connection with machining operations, such as turning gear blanks and cutting the teeth.

Example 9: If a spur gear is to have 40 teeth of 8 diametral pitch, to what diameter should the blank be turned? By applying Formula (7a), Handbook **page 2035**, (40 + 2)/8 = 5.25 inches. Therefore, the outside diameter of this gear or the diameter to which the blank would be turned is $5\frac{1}{4}$ inches.

For internal spur gears, the inside diameter to which the gear blank would be bored may be obtained by subtracting 2 from the number of teeth and dividing the remainder by the diametral pitch.

Example 10: A sample spur gear has 22 teeth, and the outside diameter, or diameter measured across the tops of the teeth, is 6 inches. Determine the diametral pitch. According to Formula (7a), Handbook **page 2035**,

$$D_o = \frac{N + 2}{P}$$

Hence,

$$P = \frac{N + 2}{D_o} = \frac{22 + 2}{6} = 4 \text{ diametral pitch}$$

Copyright 2004, Industrial Press, Inc., New York, NY

The table, Handbook **page 2035**, also shows that when the sample gear has American Standard Stub teeth, Formula (8a) should be used to determine the outside diameter, or diametral pitch.

Example 11: A 25-degree involute full-depth spur gear is to be produced by hobbing. How is the hob tip radius found?

As shown on Handbook **page 2061**, the maximum hob tip radius, r_c (max), is found by the formula:

$$r_c\ (\text{max}) = \frac{0.785398\cos\phi - b\sin\phi}{1 - \sin\phi}$$

where ϕ is the pressure angle, here, 25°, and b is the dedendum constant, which is 1.250 according to Table 2 on Handbook **page 2035**. Thus,

$$r_c\ (\text{max}) = \frac{0.785398 \times 0.90631 - 1.25 \times 0.42262}{1 - 0.42262}$$

$$= 0.3179 \text{ inch for a 1 diametral pitch gear}$$

Example 12: If a 20-degree involute full-depth pinion having 24 teeth of 6 diametral pitch is to mesh with a rack, determine the whole depth of the rack teeth and the linear pitch of the teeth.

The teeth of a rack are of the same proportions as the teeth of a spur gear or pinion that is intended to mesh with the rack; hence the pitch of the rack teeth is equal to the circular pitch of the pinion and is found by dividing 3.1416 by the diametral pitch.

The pitch = 3.1416 ÷ 6 = 0.5236 inch = linear pitch of a rack to mesh with a pinion of 6 diametral pitch. This dimension (0.5236) represents the distance that the cutter would be indexed when milling rack teeth or the distance that the planer tool would be moved for cutting successive teeth if a planer were used. The whole depth of a full-depth rack tooth of 20-degree pressure angle equals 2.157 divided by the diametral pitch of the meshing gear, or the whole depth equals the circular pitch multiplied by 0.6866. Here, the circular pitch is 0.5236, and the whole depth equals 0.5236 × 0.6866 = 0.3595 inch.

Example 13: If the teeth of a spur gear are to be cut to a certain diametral pitch, is it possible to obtain any diameter that may be desired? Thus, if the diametral pitch is 4, is it possible to make the pitch diameter 5⅛ inches?

Copyright 2004, Industrial Press, Inc., New York, NY

The diametral pitch system is so arranged as to provide a series of tooth sizes, just as the pitches of screw threads are standardized. In as much as there must be a whole number of teeth in each gear, it is apparent that gears of a given pitch vary in diameter according to the number of teeth. Suppose, for example, that a series of gears are of 4 diametral pitch. Then the pitch diameter of a gear having, say, 20 teeth will be 5 inches; 21 teeth, 5¼ inches; 22 teeth, 5½ inches, and so on. It will be seen that the increase in diameter for each additional tooth is equal to ¼ inch for 4 diametral pitch. Similarly, for 2 diametral pitch, the variations for successive numbers of teeth would equal ½ inch, and for 10 diametral pitch the variations would equal 1/10 inch, etc.

The center-to-center distance between two gears is equal to one-half the total number of teeth in the gears divided by the diametral pitch. It may be desirable at times to have a center distance that cannot be obtained exactly by any combination of gearing of given diametral pitch, but this condition is unusual, and, ordinarily, the designer of a machine can alter the center distance whatever slight amount may be required for gearing of the desired ratio and pitch. By using a standard system of pitches, all calculations are simplified, and it is also possible to obtain the benefits of standardization in the manufacturing of gears and gear-cutters.

Proportioning Spur Gears When Center Distance Is Fixed.—

If the center-to-center distance between two shafts is fixed, and it is desired to use gears of a certain pitch, the number of teeth in each gear for a given speed may be determined as follows: Since the gears must be of a certain pitch, the total number of teeth available should be determined and then the number of teeth in the driving and the driven gears. The total number of teeth equals twice the product of the center distance multiplied by the diametral pitch. If the center distance is 6 inches, and the diametral pitch to, the total number of teeth equals $6 \times 2 \times 10 = 120$ teeth. The next step is to find the number of teeth in the driving and the driven gears for a given rate of speed.

Rule: Divide the speed of the driving gear in revolutions per minute by the speed of the driven gear and add one to the quotient. Next divide the total number of teeth in both gears by the sum pre-

Copyright 2004, Industrial Press, Inc., New York, NY

viously obtained, and the quotient will equal the number of teeth required in the driving gear. This number subtracted from the total number of teeth will equal the number of teeth required in the driven gear.

Example 14: If the center-to-center distance is 6 inches, and the diametral pitch is 10, the total number of teeth available will be 120. If the speeds of the driving and the driven gears are to be 100 and 60 revolutions per minute, respectively, find the number of teeth for each gear.

$^{100}/_{60} = 1\frac{2}{3}$ and $1\frac{2}{3} + 1 = 2\frac{2}{3}$

$120 \div 2\frac{2}{3} = {}^{120}/_{1} \times \frac{3}{8} = 45$ = number of teeth in driving gear

The number of teeth in the driven gear equals 120 – 45 = 75 teeth.

When the center distance and the velocity ratios are fixed by some essential construction of a machine, it is often impossible to use standard diametral pitch gear teeth. If cast gears are to be used, it does not matter so much, as a pattern maker can lay out the teeth according to the pitch desired, but if cut gears are required, an effort should be made to alter the center distance so that standard diametral pitch cutters can be used since these are usually carried in stock.

Dimensions in Generated Bevel gears.— *Example 15:* Find all the dimensions and angles necessary to manufacture a pair of straight bevel gears if the number of teeth in the pinion is 16, the number of teeth in the mating gear is 49, the diametral pitch is 5, and the face width is 1.5 inches. The gears are to have a 20-degree pressure angle, a 90 degree shaft angle, and must be in accordance with the Gleason System.

On **page 178** of this guide, **Table 1** gives formulas for Gleason System 20-degree pressure angle straight bevel gears with 90-degree shaft angle. These formulas are given in the same order as is normally used in computation. Computations of the gear dimensions should be arranged as shown in the table on the following pages to establish a consistent procedure when calculations for bevel gears are required frequently.

Copyright 2004, Industrial Press, Inc., New York, NY

Given:

Number of pinion teeth, n	= 16	(1)
Number of gear teeth, N	= 49	(2)
Diametral pitch, P	= 5	(3)
Face width, F	= 1.5	(4)
Pressure angle, $\phi = 20°$	= 20°	(5)
Shaft angle, $\Sigma = 90°$	= 90°	(6)

Table 1. Formulas for Gleason System 20-Degree Straight Bevel Gears—90-Degree Shaft Angle

To Find			
		Formula	
No.	Item	Pinion	Gear
7	Working Depth	$h_k = \frac{2.000}{P}$	Same as pinion
8	Whole Depth	$h_t = \frac{2.188}{P} + 0.002$	Same as pinion
9	Pitch Diameter	$d = \frac{n}{P}$	$D = \frac{N}{P}$
10	Pitch Angle	$\gamma = \tan^{-1}\frac{n}{N}$	$\Gamma = 90° - \gamma$
11	Cone Distance	$A_O = \frac{D}{2\sin\Gamma}$	Same as pinion
12	Circular Pitch	$p = \frac{3.1416}{P}$	Same as pinion
13	Addendum	$a_p = h_t - a_G$	$a_G = \frac{0.540}{P} + \frac{0.460}{P\left(\frac{N}{n}\right)^2}$
14	Dedendum[a]	$b_p = \frac{2.188}{P} - a_p$	$b_G = \frac{2.188}{P} - a_G$
15	Clearance	$c = h_t - h_k$	Same as pinion
16	Dedendum Angle	$\delta_P = \tan^{-1}\frac{b_p}{A_O}$	$\delta_G = \tan^{-1}\frac{b_G}{A_O}$
17	Face Angle of Blank	$\gamma_O = \gamma + \delta_G$	$\Gamma_O = \Gamma + \delta_p$
18	Root Angle	$\gamma_r = \gamma - \delta_p$	$\Gamma_R = \Gamma - \delta_G$
19	Outside Diameter	$d_O = d + 2a_p\cos\gamma$	$D_O = D + 2a_G\cos\Gamma$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 1. *(Continued)* **Formulas for Gleason System 20-Degree Straight Bevel Gears—90-Degree Shaft Angle**

No.	Item	To Find: Formula — Pinion	To Find: Formula — Gear
20	Pitch Apex to Crown	$x_O = \frac{D}{2} - a_p \sin\gamma$	$X_O = \frac{d}{2} - a_G \sin\Gamma$
21	Circular Thickness	$t = p - T$	$T = \frac{p}{2} - (a_p - a_G)\tan\phi - \frac{K}{P}$ K = (Chart 1)
22	Backlash	B = (See table on Handbook page 2068)	
23	Chordal Thickness	$t_c = t - \frac{t^3}{6d^2} - \frac{B}{2}$	$T_c = T - \frac{T^3}{6D^2} - \frac{B}{2}$
24	Chordal Addendum	$a_{cp} = a_p + \frac{t^2\cos\gamma}{4d}$	$a_{CG} = a_G + \frac{T^2\cos\gamma}{4D}$
25	Tooth Angle	$\frac{3438}{A_O}\left(\frac{t}{2} + b_p\tan\phi\right)$ minutes	$\frac{3438}{A_O}\left(\frac{T}{2} + b_G\tan\phi\right)$ minutes
26	Limit Point Width	$\frac{A_O - F}{A_O}(T - 2b_p\tan\phi) - 0.0015$	$\frac{A_O - F}{A_O}(t - 2b_G\tan\phi) - 0.0015$

[a] The actual dedendum will be 0.002-inch greater than calculated due to tool advance
All linear dimensions are in inches.

The tooth angle (Item 25, **Table 1**) is a machine setting and is only computed if a Gleason two-tool type straight bevel gear generator is to be used. Calculations continue on **page 180**.

Dimensions of Milled Bevel Gears.— As explained on Handbook **page 2085**, the tooth proportions of milled bevel gears differ in some respects from those of generated bevel gears. To take these differences into account, a separate table of formulas is given on Handbook **page 2087** for use in calculating dimensions of milled bevel gears.

Example 16: Compute the dimensions and angles of a pair of mating bevel gears that are to be cut on a milling machine using rotary formed milling cutters if the data given are as follows:

Copyright 2004, Industrial Press, Inc., New York, NY

Table 2. Calculations of Dimensions for Example 15

	Dimension	Pinion	Gear
(7)	Working depth	$2.000/5 = 0.400$	Same as Pinion
(8)	Whole depth	$2.188/5 + 0.002 = 0.440$	Same as Pinion
(9)	Pitch diameter	$^{16}/_{5} = 3.2000$	$^{49}/_{5} = 9.8000$
(10)	Pitch angle	$\tan^{-1}(^{16}/_{49}) = 18°\ 5'$	$90° - 18°5' = 71°55'$
(11)	Cone distance	$9.8000/(2 \times \sin 71°55') = 5.1546$	Same as pinion
(12)	Circular pitch	$3.1416 / 5 = 0.6283$	Same as pinion
(13)	Addendum	$0.400 - 0.118 = 0.282$	$0.540/5 + 0.460/(5(49/16)^2) = 0.118$
(14)	Dedendum	$2.188/5 - 0.282 = 0.1554$	$2.188/5 - 0.118 = 0.3196$
(15)	Clearance	$0.440 - 0.400 = 0.040$	Same as pinion
(16)	Dedendum angle	$\tan^{-1}(0.1536/5.1546) = 1°42'$	$\tan^{-1}(0.3214/5.1546) = 3°34'$
(17)	Face angle of blank	$18°5' + 3°34' = 21°39'$	$71°55' + 1°42' = 73°37'$
(18)	Root angle	$18°5' - 1°42' = 16°23'$	$71°55' - 3°34' = 68°21'$
(19)	Outside diameter	$3.2000 + 2 \times 0.282 \cos 18°5' = 3.735$	$9.8000 + 2 \times 0.118 \cos 71°55' = 9.875$
(20)	Pitch apex to crown	$9.8000/2 - 0.284 \sin 18°5' = 4.812$	$3.2000/2 - 0.118 \sin 71°55' = 1.488$
(21)	Circular thickness	$0.6283 - 0.2467 = 0.3816$	$0.6283/2 - (0.284 - 0.118)\tan 20° - (0.038(\text{chart } 1))/5 = 0.2467$
(22)	Backlash	0.006	0.006
(23)	Chordal thickness	$0.3816 - \frac{(0.3816)^3}{6 \times (3.2000)^2} - \frac{0.006}{2} = 0.378$	$0.2467 - \frac{(0.2467)^3}{6 \times (9.8000)^2} - \frac{0.006}{2} = 0.244$
(24)	Chordal addendum	$0.282 + \frac{0.3816^2 \cos 18°5'}{4 \times 3.2000} = 0.293$	$0.118 + \frac{0.2467^2 \cos 71°55'}{4 \times 9.8000} = 0.118$

Copyright 2004, Industrial Press, Inc., New York, NY

Number of pinion teeth	=	15
Number of gear teeth	=	60
Diametral pitch	=	3
Face width	=	1.5
Pressure angle	=	14½°
Shaft angle	=	90°

By using the formulas on Handbook **page 2087**,

$\tan\alpha_p = 15 \div 60 = 0.25 = \tan 14° 2.2', \text{ say, } 14° 2'$

$\alpha_G = 90° - 14° 2' = 75° 57.8', \text{ say, } 75° 58'$

$D_p = 15 \div 3 = 5.0000 \text{ inches}$

$D_G = 60 \div 3 = 20.0000 \text{ inches}$

$S = 1 \div 3 = 0.3333 \text{ inch}$

$S + A = 1.157 \div 3 = 0.3857 \text{ inch}$

$W = 2.157 \div 3 = 0.7190 \text{ inch}$

$T = 1.571 \div 3 = 0.5236 \text{ inch}$

$$C = \frac{5.000}{2 \times 0.24249} = 10.308 \text{ inches}$$

(In determining C, the sine of unrounded value of α_p, 14° 2.2′, is used.)

$F = 8 \div 3 = 2\frac{2}{3}, \text{ say, } 2\frac{5}{8} \text{ inches}$

$$s = 0.3333 \times \frac{10.308 - 2\frac{5}{8}}{10.308} = 0.2484 \text{ inch}$$

$$t = 0.5236 \times \frac{10.308 - 2\frac{5}{8}}{10.308} = 0.3903 \text{ inch}$$

$\tan\theta = 0.3333 \div 10.308 = \tan 1° 51'$

$\tan\phi = 0.3857 \div 10.308 = \tan 2° 9'$

$\gamma_P = 14° 2' + 1° 51' = 15° 53'$

$\gamma_G = 75° 58' + 1° 51' = 77° 49'$

$\delta_P = 90° - 15° 53' = 74° 7'$

$\delta_G = 90° - 77° 49' = 12° 11'$

$\xi_P = 14° 2' + 2° 9' = 11° 53'$

$\xi_G = 75° 582' + 2° 9' = 73° 49'$

$K_P = 0.3333 \times 0.97015 = 0.3234 \text{ inch}$

$K_G = 0.3333 \times 0.24249 = 0.0808 \text{ inch}$

$O_P = 5.000 + 2 \times 0.3234 = 5.6468 \text{ inches}$

Copyright 2004, Industrial Press, Inc., New York, NY

$$O_G = 20.000 + 2 \times 0.0808 = 20.1616 \text{ inches}$$

$$J_P = \frac{5.6468}{2} \times 3.5144 = 9.9226 \text{ inches}$$

$$J_G = \frac{20.1616}{2} \times 0.21590 = 2.1764 \text{ inches}$$

$$j_p = 9.9226 \times \frac{10.3097 - 2\frac{5}{8}}{10.3097} = 7.3961 \text{ inches}$$

$$j_g = 2.1764 \times \frac{10.3097 - 2\frac{5}{8}}{10.3097} = 1.6222 \text{ inches}$$

$$N'_P = \frac{15}{0.97015} = 15.4, \text{ say, } 15 \text{ teeth}$$

$$N'_G = \frac{60}{0.24249} = 247 \text{ teeth}$$

If these gears are to have uniform clearance at the bottom of the teeth, in accordance with the recommendation given in the last paragraph on Handbook **page 2085**, then the cutting angles ζ_P and ζ_G should be determined by subtracting the addendum angle from the pitch cone angles. Thus,

$$\zeta_P = 14°2' - 1°51' = 12°11'$$

$$\zeta_G = 75°58' - 1°51' = 74°7'$$

Selection of Formed Cutters for Bevel Gears.— *Example 17:* In **Example 16**, the numbers of teeth for which to select the cutters were calculated as 15 and 247 for the pinion and gear, respectively. Therefore, as explained on **page 2091** of the Handbook, the cutters selected from the table on **page 2054** are the No. 7. and the No.1 cutters. As further noted on **page 2091**, bevel gear milling cutters may be selected directly from the table beginning on **page 2089**, when the shaft angle is 90 degrees, instead of using the computed value of N′ to enter the table on **page 2054**. Thus, for a 15-tooth pinion and a 60-tooth gear, the table on **page 2089** shows that the numbers of the cutters to use are 1 and 7 for gear and pinion, respectively.

Copyright 2004, Industrial Press, Inc., New York, NY

Pitch of Hob for Helical Gears.— *Example 18:* A helical gear that is to be used for connecting shafts has 83 teeth, a helix angle of 7 degrees, and a pitch diameter of 47.78 inches. Determine the pitch of hob to use in cutting this gear.

As explained on Handbook **page 2100**, the normal diametral pitch and the pitch of the hob are determined as follows: the transverse diametral pitch equals 83 ÷ 47.78 = 1.737. The cosine of the helix angle of the gear (7 degrees) is 0.99255; hence the normal diametral pitch equals 1.737 ÷ 0.99255 = 1.75; therefore, a hob of $1\frac{3}{4}$ diametral pitch should be used. This hob is the same as would be used for spur gears of $1\frac{3}{4}$ diametral pitch, and it will cut any spur or helical gear of that pitch regardless of the number of teeth, provided $1\frac{3}{4}$ is the diametral pitch of the spur gear and the normal diametral pitch of the helical gear.

Determining Contact Ratio.— As pointed out on Handbook **page 2060**, if a smooth transfer of load is to be obtained from one pair of teeth to the next pair of teeth as two mating gears rotate under load, the contact ratio must be well over 1.0. Usually, this ratio should be 1.4 or more, although in extreme cases it may be as low as 1.15.

Example 19: Find the contact ratio for a pair of 18-diametral pitch, 20-degree pressure gears, one having 36 teeth and the other 90 teeth. From Formula (1) given on Handbook **page 2059**:

$$\cos A = \frac{90 \times \cos 20^\circ}{5.111 \times 18} = \frac{90 \times 0.93969}{91.9998} = 0.91926 \quad \text{and}$$

$$A = 23^\circ 11'$$

From Formula (4) given on Handbook **page 2059**:

$$\cos a = \frac{36 \times \cos 20^\circ}{2.111 \times 18} = \frac{36 \times 0.93969}{37.9998} = 0.89024 \quad \text{and}$$

$$a = 27^\circ 6'$$

From Formula (5) given on Handbook **page 2059**:

$$\tan B = \tan 20^\circ - \frac{36}{90}(\tan 27^\circ 6' - \tan 20^\circ)$$

$$= 0.36397 - \frac{36}{90}(0.51172 - 0.36397) = 0.30487$$

Copyright 2004, Industrial Press, Inc., New York, NY

From Formula (7a) given on Handbook **page 2059**, the contact ratio m_f is found:

$$m_f = \frac{90}{6.28318}(0.42826 - 0.30487)$$
$$= 1.77$$

which is satisfactory.

Dimensions Required When Using Enlarged Fine-Pitch Pinions.— On Handbook **pages 2055** to **2058**, there are tables of dimensions for enlarged fine-pitch pinions. These tables show how much the dimensions of enlarged pinions must differ from standard when the number of teeth is small, and undercutting of the teeth is to be avoided.

Example 20: If a 10- and a 31-tooth mating pinion and gear of 20 diametral pitch and 14½° pressure angle have both been enlarged to avoid undercutting of the teeth, what increase over the standard center distance is required?

$$\text{Standard center distance} = \frac{n+N}{2P} = \frac{10+31}{2\times 20} = 1.0250 \text{ inches}$$

The amount by which the center distance must be increased over standard can be obtained by taking the sum of the amounts shown in the eighth column of Table 9b on Handbook **page 2055** and dividing this sum by the diametral pitch. Thus, the increase over the standard center distance is (0.6866 + 0.0283)/20 = 0.0357 inch.

Example 21: At what center distance would the gears in **Example 20** have to be meshed if there were to be no backlash?

Obtaining the two thicknesses of both gears at the standard pitch diameters from Table 9b on Handbook **page 2055**, dividing them by 20, and using the formulas on Handbook **page 2059**:

$$\text{inv}\,\phi_1 = \text{inv}\,14\tfrac{1}{2}^\circ + \frac{20(0.09630 + 0.07927) - 3.1416}{10+31}$$

The involute of 14½° is found on Handbook **page 104** to be 0.0055448. Therefore,

$$\text{inv}\,\phi_1 = 0.0055448 + 0.0090195 = 0.0145643$$

Copyright 2004, Industrial Press, Inc., New York, NY

By referring to the table on Handbook **page 104**:

$$\phi_1 = 19°51'6''$$

$$C = \frac{10 + 31}{2 \times 20} = 1.025 \text{ inch}$$

$$C_1 = \frac{\cos 14\frac{1}{2}°}{\cos 19°51'6''} \times 1.025 = \frac{0.96815}{0.94057} \times 1.025 = 1.0551 \text{ inch}$$

End Thrust of Helical Gears Applied to Parallel Shafts.— *Example 22:* The diagrams on Handbook **pages 2101** to **2102** show the application of helical or spiral gears to parallel shaft drives. If a force of 7 horsepower is to be transmitted at a pitch-line velocity of 200 feet per minute, determine the end thrust in pounds, assuming that the helix angle of the gear is 15 degrees.

To determine the end thrust of helical gearing as applied to parallel shafts, first calculate the tangential load on the gear teeth.

$$\text{Tangential load} = \frac{33,000 \times 7}{200} = 1155 \text{ pounds}$$

(This formula is derived from the formulas for power given on Handbook **page 178**.)

The axial or end thrust may now be determined approximately by multiplying the tangential load by the tangent of the tooth angle. Thus, in this instance, the thrust = 1155 × tan 15 degrees = about 310 pounds. (Note that this formula agrees with the one on Handbook **page 161** for determining force P parallel to base of inclined plane.) The end thrust obtained by this calculation will be somewhat greater than the actual end thrust, because frictional losses in the shaft bearings, etc., have not been taken into account, although a test on a helical gear set, with a motor drive, showed that the actual thrust of the 7½-degree helical gears tested was not much below the values calculated as just explained.

According to most textbooks, the maximum angle for single helical gears should be about 20 degrees, although one prominent manufacturer mentions that the maximum angle for industrial drives ordinarily does not exceed 10 degrees, and this will give quiet running without excessive end thrust. On some of the heavier single helical gearing used for street railway transmissions, etc., an angle of 7 degrees is employed.

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions of Wormgear Blank and the Gashing Angle.— *Example 23:* A wormgear having 45 teeth is to be driven by a double threaded worm having an outside diameter of 2½ inches and a lead of 1 inch, the linear pitch being ½ inch. The throat diameter and throat radius of the wormgear are required as well as the angle for gashing the blank.

The throat diameter D_t equals the pitch diameter D plus twice the addendum A; thus, $D_t = D + 2A$. The addendum of the worm thread equals the linear pitch multiplied by 0.3183, and here, $0.5 \times 0.3183 = 0.1591$ inch. The pitch diameter of the wormgear = $45 \times 0.5 \div 3.1416 = 7.162$ inches; hence, the throat diameter equals $7.162 + 2 \times 0.1591 = 7.48$ inches.

The radius of the wormgear throat is found by subtracting twice the addendum of the worm thread from ½ the outside diameter of the worm. The addendum of the worm thread equals 0.1591 inch, and the radius of the throat, therefore, equals $(2.5 \div 2) - 2 \times 0.1591 = 0.931$ inch.

When a wormgear is hobbed in a milling machine, gashes are milled before the hobbing operation. The table must be swiveled around while gashing, the amount depending upon the relation between the lead of the worm thread and the pitch circumference. The first step is to find the circumference of the pitch circle of the worm. The pitch diameter equals the outside diameter minus twice the addendum of the worm thread; hence, the pitch diameter equals $2.5 - 2 \times 0.1591 = 2.18$ inches, and the pitch circumference equals $2.18 \times 3.1416 = 6.848$ inches.

Next, divide the lead of the worm thread by the pitch circumference to obtain the tangent of the desired angle, and then refer to a table of tangents or a calculator to determine what this angle is. For this example, it is $1 \div 6.848 = 0.1460$, which is the tangent of 8⅓ degrees from its normal position.

Change Gear Ratio for Diametral-Pitch Worms.— *Example 24:* In cutting worms to a given diametral pitch, the ratio of the change gears is 22 × threads per inch / 7 × diametral pitch.

The reason why the constants 22 and 7 are used in determining the ratio of change-gears for cutting worm threads is because $^{22}/_{7}$

Copyright 2004, Industrial Press, Inc., New York, NY

equals, very nearly, 3. 1416, which is the circular pitch equivalent to diametral pitch.

Assume that the diametral pitch of the wormgear is 5, and the lathe screw constant is 4. (See Handbook page 1836 for the meaning of "lathe screw constant.") Then, $(4 \times 22)/(5 \times 7) = 88/35$. If this simple combination of gearing were used, the gear on the stud would have 88 teeth and the gear on the lead screw, 35 teeth. Of course, any other combination of gearing having this same ratio could be used, as, for example, the following compound train of gearing: $(24\times 66)/(30 \times 21)$.

If the lathe screw constant is 4, as previously assumed, then the number of threads per inch obtained with gearing having a ratio of $88/35 = (4 \times 35)/88 = 1.5909$; hence, the pitch of the worm thread equals $1 \div 1.5909 = 0.6284$ inch, which is the circular pitch equivalent to 5 diametral pitch, correct to within 0.0001 inch.

Bearing Loads Produced by Bevel Gears.—In applications where bevel gears are used, not only must the gears be proportioned with regard to the power to be transmitted, but also the bearings supporting the gear shafts must be of adequate size and design to sustain the radial and thrust loads that will be imposed on them. Assuming that suitable gear and pinion proportions have been selected, the next step is to compute the loads needed to determine whether or not adequate bearings can be provided. To find the loads on the bearings, first, use the formulas on the following pages to compute the tangential, axial, and separating components of the load on the tooth surfaces. Second, use the principle of moments, together with the components determined in the first step, to find the radial loads on the bearings. To illustrate the procedure, the following example will be used.

Example 25: A 16-tooth left-hand spiral pinion rotating clockwise at 1800 rpm transmits 71 horsepower to a 49-tooth mating gear. If the pressure angle is 20 degrees, the spiral angle is 35 degrees, the face width is 1.5 inches, and the diametral pitch is 5 what are the radial and thrust loads that govern the selection of bearings?

In **Fig. 3**, the locations of the bearings for the gear shafts are shown. It should be noted that distances K, L, M, and N are measured from the center line of the bearings and from the midfaces of the gears at their mean pitch diameters. In this example, it will be

Copyright 2004, Industrial Press, Inc., New York, NY

assumed that these distances are given and are as follows: $K = 2.5$ inches; $N = 3.5$ inches; $L = 1.5$ inches; and $M = 5.0$ inches.

Also given:

Number of pinion teeth, n	= 16	(1)
Number of gear teeth, N	= 49	(2)
Diametral pitch, P	= 5	(3)
Face width, F	= 1.5	(4)
Pressure angle, $\phi = 20°$	= 20°	(5)
Shaft angle, $\sum = 90°$	= 90°	(6)

Table 3. Formulas for Gleason System 20-Degree Pressure Angle, Spiral Bevel Gears—90-Degree Shaft Angle

No	Item	Formula	
		Pinion	Gear
7	Working Depth	$h_k = \frac{1.700}{P}$	Same as pinion
8	Whole Depth	$h_t = \frac{2.188}{P}$	Same as pinion
9	Pitch Diameter	$d = \frac{n}{P}$	$D = \frac{N}{P}$
10	Pitch Angle	$\gamma = \tan^{-1}\frac{n}{N}$	$\Gamma = 90° - \gamma$
11	Cone Distance	$A_O = \frac{D}{2\sin\Gamma}$	Same as pinion
12	Circular Pitch	$p = \frac{3.1416}{P}$	Same as pinion
13	Addendum	$a_p = h_k - a_G$	$a_G = \frac{0.540}{P} + \frac{0.390}{P\left(\frac{N}{n}\right)^2}$
14	Dedendum	$b_p = h_t - a_p$	$b_G = h_t - a_G$
15	Clearance	$c = h_t - h_k$	Same as pinion
16	Dedendum Angle	$\delta_P = \tan^{-1}\frac{b_p}{A_O}$	$\delta_G = \tan^{-1}\frac{b_G}{A_O}$
17	Face Angle of Blank	$\gamma_O = \gamma + \delta_G$	$\Gamma_O = \Gamma + \delta_p$

Copyright 2004, Industrial Press, Inc., New York, NY

Table 3. *(Continued)* **Formulas for Gleason System 20-Degree Pressure Angle, Spiral Bevel Gears—90-Degree Shaft Angle**

No	Item	Formula	
		Pinion	Gear
18	Root Angle	$\gamma_R = \gamma - \delta_p$	$\Gamma_R = \Gamma - \delta_G$
19	Outside Diameter	$d_O = d + 2a_p \cos\gamma$	$D_O = D + 2a_G \cos\Gamma$
20	Pitch Apex to Crown	$x_O = \frac{D}{2} - a_p \sin\gamma$	$X_O = \frac{d}{2} - a_G \sin\Gamma$
21	Circular Thickness	$t = p - T$	$T = \frac{(1.5708 - K)}{P} - \frac{\tan\phi}{\cos\psi}(a_p - a_G)$
22	Backlash[a]	B = (See table on Handbook page 2067)	

[a] When the gear is cut spread-blade, all the backlash is taken from the pinion thickness. When both members are cut single-side, each thickness is reduced by half of the backlash. All linear dimensions are in inches.



Fig. 3. Diagram Showing Location of Bearings for Bevel Gear Drive in Example 25

Other quantities that will be required in the solution of this example are the pitch diameter, pitch angle, and mean pitch diameter of both the gear and pinion. These are computed using formulas given in **Table 3** on the previous page as follows:

By using Formula 9 in **Table 3**,

Pitch dia. of pinion $d = 3.2$ inches

Pitch dia. of gear $D = 9.8$ inches

By using Formula 10 in **Table 3**,

Pitch angle of pinion $\gamma = 18° 5'$

Copyright 2004, Industrial Press, Inc., New York, NY

Pitch angle of gear $\Gamma = 71° 55'$

By using the formula given below,

Mean pitch diameter of pinion

$$d_m = d - F\sin\gamma$$
$$= 3.2 - 1.5 \times 0.31040$$
$$= 2.734 \text{ inches}$$

Mean pitch diameter of gear

$$D_m = D - F\sin\Gamma$$
$$= 9.8 - 1.5 \times 0.95061$$
$$= 8.374 \text{ inches}$$

The first step in determining the bearing loads is to compute the tangential W_t, axial W_x, and separating W_s, components of the tooth load, using the formulas that follow.

$$W_t = \frac{126,050P}{nd_m} = \frac{126,050 \times 71}{1800 \times 2.734} = 1819 \text{ pounds}$$

$$W_x(\text{pinion}) = \frac{W_t}{\cos\psi}(\tan\phi\sin\gamma_d + \sin\psi\cos\gamma_d)$$
$$= \frac{1819}{0.81915}(0.36397 \times 0.31040 + 0.57358 \times 0.95061)$$
$$= 1462 \text{ pounds}$$

$$W_x \text{ (gear)} = \frac{W_t}{\cos\psi}(\tan\phi\sin\gamma_D - \sin\psi\cos\gamma_D)$$
$$= \frac{1819}{0.81915}(0.36397 \times 0.95061 - 0.57358 \times 0.31040)$$
$$= 373 \text{ pounds}$$

$$W_s(\text{pinion}) = \frac{W_t}{\cos\psi}(\tan\phi\cos\gamma_d - \sin\psi\cos\gamma_d)$$
$$= \frac{1819}{0.81915}(0.36397 \times 0.95061 - 0.57358 \times 0.31040)$$
$$= 373 \text{ pounds}$$

Copyright 2004, Industrial Press, Inc., New York, NY

$$W_s\ (\text{gear}) = \frac{W_t}{\cos\psi}(\tan\phi\cos\gamma_D + \sin\psi\cos\gamma_D)$$

$$= \frac{1819}{0.81915}(0.36397 \times 0.31040 + 0.57358 \times 0.95061)$$

$$= 1462 \text{ pounds}$$

The axial thrust load on the bearings is equal to the axial component of the tooth load W_x. Since thrust loads are always taken up at only one mounting point, either bearing *A* or bearing *B* must be a bearing capable of taking a thrust of 1462 pounds, and either bearing *C* or bearing *D* must be capable of taking a thrust of 373 pounds.

The next step is to determine the magnitudes of the radial loads on the bearings *A*, *B*, *C*, and *D*. For an overhung mounted gear, or pinion, it can be shown, using the principle of moments, that the radial load on bearing A is:

$$R_A = \frac{1}{M}\sqrt{[W_t(L+M)]^2 + [W_s(L+M) - W_x r]^2} \quad (1)$$

And the radial load on bearing *B* is:

$$R_B = \frac{1}{M}\sqrt{(W_t L)^2 + (W_s L - W_x r)^2} \quad (2)$$

For a *straddle mounted gear* or pinion the radial load on bearing *C* is:

$$R_C = \frac{1}{N+K}\sqrt{(W_t K)^2 + (W_s K - W_x r)^2} \quad (3)$$

And the radial load on bearing *D* is:

$$R_D = \frac{1}{N+K}\sqrt{(W_t N)^2 + (W_s N + W_x r)^2} \quad (4)$$

In these formulas, *r* is the mean pitch radius of the gear or pinion.

These formulas will now be applied to the gear and pinion bearings in the example. An overhung mounting is used for the pinion, so **Formula (1)** and **(2)** are used to determine the radial loads on the pinion bearings:

Copyright 2004, Industrial Press, Inc., New York, NY

$$R_A = \frac{1}{5}\sqrt{[1819(1.5+5)]^2 + [373(1.5+5) - 1462 \times 1.367]^2}$$

$$= 2365 \text{pounds}$$

$$R_B = \frac{1}{5}\sqrt{(1819 \times 1.5)^2 + [373 \times 1.5 - 1462 \times 1.367]^2}$$

$$= 618 \text{pounds}$$

Because of the straddle mounting used for the gear, **Formula (3)** to (4) are used to determine the radial loads on the gear bearings:

$$R_C = \frac{1}{3.5+2.5}\sqrt{(1819 \times 2.5)^2 + (1462 \times 2.5 - 373 \times 4.187)^2}$$

$$= 833 \text{pounds}$$

$$R_D = \frac{1}{3.5+2.5}\sqrt{(1819 \times 3.5)^2 + (1462 \times 3.5 + 373 \times 4.187)^2}$$

$$= 1533 \text{pounds}$$

These radial loads, and the thrust loads previously computed, are then used to select suitable bearings from manufacturers' catalogs.

It should be noted, in applying **Formula (1)** to **(4)**, that if both gear and pinion had overhung mountings, then **Formulas (1)** and **(2)** would have been used for both; if both gear and pinion had straddle mountings, then **Formulas (3)** and **(4)** would have been used for both. In any arrangement, the dimensions and loads for the corresponding member must be used. Also, in applying the formulas, the computed values of W_x and W_s, if they are negative, must be used in accordance with the rules applicable to negative numbers.

Gear Strength Calculations.— Methods of calculating the strength and power capacity for gears used in all types of applications are provided in American Gear Manufacturers Association (AGMA) standards. These standards are revised as needed by improvements in gear materials, calculation methods, and increased field experience with typical designs and application factors.

Copyright 2004, Industrial Press, Inc., New York, NY

AGMA Standard 2001-B88, *Fundamental Rating Factors and Calculation Methods for Involute Spur and Helical Gear Teeth,* is a revision of, and supersedes, AGMA 218.01.

The AGMA Standard presents general formulas for rating the pitting resistance and the bending strength of spur and helical involute gear teeth. It is intended to establish a common base for rating various types of gears for differing applications and to encourage the maximum practical degree of uniformity and consistency between rating practices in the gear industry. The Standard provides the basis from which more detailed AGMA Application Standards are developed and is a means for calculation of approximate ratings in the absence of such Standards. Where applicable AGMA standards exist, they should be used in preference to this Standard. Where no application standard exists, numerical values may be estimated for the factors used in the general equations presented in the Standard. The values of these factors may vary significantly, depending on the application, system effects, gear accuracy, manufacturing practice, and definition of what constitutes gear failure.

Information on geometry factors used in pitting resistance independent strength calculations for AGMA 908-B89, *Geometry Factors for Determining the Pitting Resistance and Bending Strength of Spur, Helical, and Herringbone Gear Teeth,* is used in conjunction with AGMA 2001–B88 formulas.

PRACTICE EXERCISES FOR SECTION 19

(See *Answers to Practice Exercises For Section 19* on page 235)

1) A spur gear of 6 diametral pitch has an outside diameter of 3.3333 inches. How many teeth has it? What is the pitch diameter? What is the tooth thickness measured along the pitch circle?

2) A gear of 6 diametral pitch has 14 teeth. Find the outside diameter, the pitch diameter, and the addendum.

3) When is the 25-degree tooth form standard preferred?

4) What dimension does a gear-tooth vernier caliper measure?

5) What are the principal 20-degree pressure angle tooth dimensions for the following diametral pitches: 4; 6; 8; 18?

Copyright 2004, Industrial Press, Inc., New York, NY

6) Give the important 14½ degree pressure angle tooth dimensions for the following circular pitches: ½ inch; ¾ inch; 9/16 inch.

7) What two principal factors are taken into consideration in determining the power transmitting capacity of spur gears?

8) The table on Handbook **page 2054** shows that a No. 8 formed cutter (involute system) would be used for milling either a12- or 13-tooth pinion, whereas a No. 7 would be used for tooth numbers from 14 to 16, inclusive. If the pitch is not changed, why is it necessary to use different cutter numbers?

9) Are hobs made in series or numbers for each pitch similar to formed cutters?

10) If the teeth of a gear have a ⅝ pitch, what name is applied to the tooth form?

11) A stub-tooth gear has 8/10 pitch. What do the figures 8 and 10 indicate?

12) What is the module of a gear?

13) Explain the use of the table of chordal thicknesses on Handbook **page 2047**.

14) Give the dimensions of a 20-degree stub tooth of 12 pitch.

15) What are the recommended diametral pitches for fine-pitch standard gears?

16) What tooth numbers could be used in pairs of gears having the following ratios: 0.2642; 0.9615?

17) What amount of backlash is provided for general-purpose gearing, and how is the excess depth of cut to obtain it calculated?

18) What diametral pitches correspond to the following modules: 2.75; 4; 8?

19) Can bevel gears be cut by formed milling cutters?

20) Can the formed cutters used for cutting spur gears also be used for bevel gears?

21) What is the pitch angle of a bevel gear?

22) When is the term “miter” applied to bevel gears?

Copyright 2004, Industrial Press, Inc., New York, NY

23) What is the difference between the terms “whole depth” and “working depth” as applied to gear teeth?

24) Why do perceived gears have a greater dedendum than gears that are finish-hobbled?

25) Are gear teeth of 8 diametral pitch larger or smaller than teeth of 4 diametral pitch, and how do these two pitches compare in regard to tooth depth and thickness?

26) Where is the pitch diameter of a bevel gear measured?

27) What is the relation between the circular pitch of a wormgear and the linear pitch of the mating worm?

28) In what respect does the helix angle of a worm differ from the helix angle of a helical or spiral gear?

29) How do the terms “pitch” and “lead,” as applied to a worm, compare with the same terms as applied to screw threads?

30) Why is the outside diameter of a hob for cutting a wormgear somewhat larger than the outside diameter of the worm?

31) Why are triple, quadruple, or other multiple-threaded worms used when an efficient transmission is required?

32) In designing worm drives having multi threaded worms, it is common practice to select a number of wormgear teeth that is not an exact multiple of the number of worm threads. Why is this done? When should this practice be avoided?

33) Explain the following terms used in connection with helical or spiral gears: transverse diametral pitch; normal diametral pitch. What is the relation between these terms?

34) Are helical gear calculations based upon diametral pitch or circular pitch?

35) Can helical gears be cut with the formed cutters used for spur gears?

36) In spiral gearing, the tangent of the tooth or helix angle = the circumference ÷ lead. Is this circumference calculated from the outside diameter, the pitch diameter, or the root diameter?

37) What advantages are claimed for gearing of the herringbone type?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 20

CUTTING SPEEDS, FEEDS, AND MACHINING POWER

HANDBOOK Pages **1009** – **1091**

Metal cutting operations such as turning and drilling may not be as productive as they could be unless the material removal rate is at or near the maximum permitted by the available power of the machine. It is not always possible to use the machine's full power owing to limitations imposed by a combination of part configuration, part material, tool material, surface finish and tolerance requirements, coolant employed, and tool life. However, even with such restrictions, it is practical to find a combination of depth of cut, feed rate, and cutting speed to achieve the best production rate for the job at hand.

The information on Handbook **pages 1009** to **1091** is useful in determining how to get the most out of machining operations. The tabular data are based on actual shop experience and extensive testing in machining laboratories. A list of machining data tables is given on Handbook **page 1022**, and these tables are referred to in the following.

Most materials can be machined over a wide range of speeds; however, there is usually a narrower spread of speeds within which the most economical results are obtained. This narrower spread is determined by the economical tool life for the job at hand as, for example, when a shorter tool life is tolerable the speed can be increased. On the other hand, if tool life is too short, causing excessive down time, then speed can be reduced to lengthen tool life.

To select the best cutting conditions for machining a part the following procedure may be followed:

1) Select the maximum depth of cut consistent with the job.

2) Select the maximum feed rate that can be used consistent with such job requirements as surface finish and the rigidity of the cut-

Copyright 2004, Industrial Press, Inc., New York, NY

ting tool, workpiece, and the machine tool. Use Table 15a to assist in feed selection for milling. When possible, use the combined feed/ speed portions of the tables to select two pairs of feed and speed data and determine the spindle speed as illustrated by **Example 1**.

3) If the combined feed/speed data are not used, select the cutting speed and determine the spindle speed (for turning use Table 5a also). This order of selection is based on the laws governing tool life; i.e., the life of a cutting tool is affected most by the cutting speed, then by the feed, and least by the depth of cut.

By using the same order of selection, when very heavy cuts are to be taken, the cutting speed that will utilize the maximum power available on the machine tool can be estimated by using a rearrangement of the machining power formulas on Handbook **pages 1084** to **1088**. These formulas are used together with those on Handbook **pages 1016** and **1040** which are used when taking ordinary cuts, as well as heavy cuts. Often, the available power on the machine will limit the size of the cut that can be taken. The maximum depth of cut and feed should then be used and the cutting speed adjusted to utilize the maximum available power. When the cutting speed determined in this manner is equal to or less than recommended, the maximum production and the best possible tool life will be achieved. When the estimated cutting speed is greater than recommended, the depth of cut or feed may be increased, but the cutting speed should not be increased beyond the value that will provide a reasonable tool life.

Example 1: An ASTM Class 25 (160–180 Bhn) grey-iron casting is to be turned on a geared head lathe using a cemented carbide cutting tool. The heaviest cut will be 0.250 inch (6.35 mm) deep, taken on an 8-inch (203.2-mm) diameter of the casting; a feed rate of 0.020 in/rev (0.51 mm/rev) is selected for this cut. Calculate the spindle speed of the lathe, and estimate the power required to take this cut.

Locate the selected work material in Table 4a, and select the feed/speed pairs that correspond to the chosen cutter material. For an uncoated carbide tool, the given feed/speed pairs are: optimum 28/240, and average 13/365.

Copyright 2004, Industrial Press, Inc., New York, NY

Factors to correct for feed and depth of cut are found in Table 5a. First, determine the ratios of $^{\text{chosen feed}}/_{\text{optimum feed}} = {}^{20}/_{28} = 0.71$ and $V_{avg}/V_{opt} = {}^{365}/_{240} = 1.52$, then, by estimation or interpolation, determine F_f and F_d, and calculate V and N as follows:

$F_f = 1.22;\ F_d = 0.86$

$V = V_{opt} \times F_f \times F_d = 240 \times 1.22 \times 0.86 = 252$ ft/min

$$N = \frac{12V}{\pi D} = \frac{12 \times 252}{\pi \times 8} = 120 \text{ rpm}$$

Next, estimate the power requirements using: $K_p = 0.52$ (Table 3a), $C = 0.90$ (Table), $Q = 12Vfd$ (Table 7), $W = 1.30$ (Table), and $E = 0.80$ (Table 6).

$Q = 12Vfd = 12 \times 252 \times 0.020 \times 0.250 = 15.12$ in^3/min

$$P_m = \frac{K_p C Q W}{E} = \frac{0.52 \times 0.90 \times 15.12 \times 1.30}{0.80} = 11.5 \text{ hp}$$

The equivalent results, expressed in the metric system, can be obtained by converting the cutting speed V, the metal removal rate Q, and the power at the motor P_m into metric units using factors found starting on **page 2549** of the Handbook, as illustrated in the following.

$V = 252$ ft/min $= 252 \times 0.3 = 76$ m/min

$Q = 15.12$ in^3/min $= 15.12 \times 16.4 \div 60 = 4.13$ cm^3/s

$P_m = 11.5$ hp $= 11.5 \times 0.745 = 8.6$ kw

Alternatively, if metric units are used throughout the problem, F_f and F_d are determined in the same manner as above. However, if V is in meters per minute, and D and d are in millimeters, then $N = 1000V/\pi D$, and $Q = Vfd/60$.

Example 2: If the lathe in **Example 1** has only a 10-hp motor, estimate the cutting speed and spindle speed that will utilize the maximum available power. Use inch units only.

Copyright 2004, Industrial Press, Inc., New York, NY

$$Q_{max} = \frac{P_m E}{K_p C W} = \frac{10 \times 0.80}{0.52 \times 0.90 \times 1.30} \quad \left(P_m = \frac{K_p C Q W}{E}\right)$$

$$= 13.15(\ \text{in}^3/\text{min})$$

$$V = \frac{Q_{max}}{12fd} = \frac{13.15}{12 \times 0.020 \times 0.250} \quad (Q = 12Vfd)$$

$$= 219\ \text{fpm}$$

$$N = \frac{12V}{\pi D} = \frac{12 \times 219}{\pi \times 8} = 105\ \text{rpm}$$

Example 3: A slab milling operation is to be performed on 120-140 HB AISI 1020 steel using a 3-inch diameter high-speed-steel plain milling cutter having 8 teeth. The width of this cut is 2 inches; the depth is 0.250 inch, and the feed rate is 0.004 in/tooth. Estimate the power at the motor required to take this cut.

$V = 110$ fpm (**Table 11, page 1045**) $Q = f_m wd$ (Table 7)
$K_p = 0.69$ (**Table 3b, page 1086**) $W = 1.10$ (Table 5)
$C = 1.25$ (Table 4) $E = 0.80$ (Table 6)

$$N = \frac{12V}{\pi D} = \frac{12 \times 110}{\pi \times 3} = 140\ \text{rpm}$$

$$f_m = f_t n_t N = 0.004 \times 8 \times 140 = 4.5\ \text{in/min}$$

$$P_m = \frac{K_p C Q W}{E} = \frac{0.69 \times 1.25 \times 2.25 \times 1.10}{0.80} = 2.67\ \text{hp}$$

Example 4: A 16-inch diameter cemented carbide face milling cutter having 18 teeth is to be used to take a 14-inch wide and 0.125-inch deep cut on an H12 tool steel die block having a hardness of 250–275 HB. The feed used will be 0.008 in/tooth, and the milling machine has a 20-hp motor. Estimate the cutting speed and the spindle speed to be used that will utilize the maximum horsepower available on the machine.

$K_p = 0.98$ fpm (Table 3a) $W = 1.25$ (Table 5)
$C = 1.08$ (**Table 4, page 1087**) $E = 0.80$ (Table 6)
$Q = f_m wd$ (Table 7)

Copyright 2004, Industrial Press, Inc., New York, NY

$$Q_{max} = \frac{P_m E}{K_p C W} = \frac{20 \times 0.80}{0.98 \times 1.08 \times 1.25} \qquad \left(P_m = \frac{K_p C Q W}{E}\right)$$

$$= 12.1 \ (\text{in}^3/\text{min})$$

$$f_m = \frac{Q_{max}}{wd} = \frac{12}{14 \times 0.125} \qquad (Q = f_m wd)$$

$$= 6.9 \ \text{in/min; use } 7 \text{ in/min}$$

$$N = \frac{f_m}{f_t n_t} = \frac{7}{0.008 \times 18} \qquad (f_m = f_t n_t N)$$

$$= 48.6 \ \text{rpm; use } 50 \text{ rpm}$$

$$V = \frac{\pi DN}{12} = \frac{\pi \times 16 \times 50}{12} = 209 \text{ fpm}$$

Formulas for estimating the thrust, torque, and power for drilling are given on Handbook **page 1090**. Thrust is the force required to push or feed the drill when drilling. This force can be very large. It is sometimes helpful to know the magnitude of this force and the torque exerted by the drill when designing drill jigs or work-holding fixtures; it is essential to have this information as well as the power required to drill when designing machine tools on which drilling operations are to be performed. In the ordinary shop, it is often helpful to be able to estimate the power required to drill larger holes in order to determine if the operation is within the capacity of the machine to be used.

Example 5: Estimate the thrust, torque, and power at the motor required to drill a ¾-inch diameter hole in a part made from AISI 1117 steel, using a conventional twist drill and a feed rate of 0.008 in/rev.

$K_d = 12{,}000$ (**Table 8, page 1090**)
$F_f = 0.021$ (Table 10)
$F_T = 0.794$ (Table 11)
$F_M = 0.596$ (Table 11)
$A = 1.085$ (Table 9)
$B = 1.355$ (Table 9)
$J = 0.030$ (Table 9)
$E = 0.80$ (Table 6)
$W = 1.30$ (Table 5)
$V = 101$ fpm (**Table 17, page 1061**)

Copyright 2004, Industrial Press, Inc., New York, NY

$$T = 2K_d F_f F_T BW + K_d d^2 JW$$
$$= 2 \times 12{,}000 \times 0.021 \times 0.794 \times 1.355 \times 1.30 + 12{,}000 \times 0.75^2 \times 0.030 \times 1.30$$
$$= 968 \text{ lb}$$
$$M = K_d F_f F_M AW$$
$$= 12{,}000 \times 0.021 \times 0.596 \times 1.085 \times 1.30$$
$$= 212 \text{ in-lb}$$

$$N = \frac{12V}{\pi D} = \frac{12 \times 101}{\pi \times 0.750} = 514 \text{ rpm}$$

$$P_c = \frac{MN}{63{,}025} = \frac{212 \times 514}{63{,}025} = 1.73 \text{ hp}$$

$$P_m = \frac{P_c}{E} = \frac{1.73}{0.80} = 2.16 \text{ hp}$$

PRACTICE EXERCISES FOR SECTION 20

(See *Answers to Practice Exercises For Section 20* on page 237)

1) Calculate the spindle speeds for turning 1½ inch and 4-inch bars made from the following steels, using a high-speed steel cutting tool and the cutting conditions given as follows:

Steel Designation	Feed, in/rev	Depth of Cut, inch
AISI 1108, Cold Drawn	0.012	0.062
12L13, 150 — 200 HB	0.008	0.250
1040, Hot Rolled	0.015	0.100
1040, 375 — 425 HB	0.015	0.100
41L40, 200 — 250 HB	0.015	0.100
4140, Hot Rolled	0.015	0.100
O2, Tool Steel	0.012	0.125
M2, Tool Steel	0.010	0.200

2) Calculate the spindle speeds for turning 6-inch diameter sections of the following materials, using a cemented carbide cutting tool and the cutting conditions given below:

Copyright 2004, Industrial Press, Inc., New York, NY

Material	Feed, in/rev	Depth of Cut, inch
AISI 1330, 200 HB	0.030	0.150
201 Stainless Steel, Cold Drawn	0.012	0.100
ASTM Class 50 Gray Cast Iron	0.016	0.125
6A1-4V Titanium Alloy	0.018	0.188
Waspaloy	0.020	0.062

3) A 200 HB AISI 1030 forged steel shaft is being turned at a constant spindle speed of 400 rpm, using a cemented carbide cutting tool. The as-forged diameters of the shaft are 1½, 3, and 4 inches. Calculate the cutting speeds (fpm) at these diameters, and check to see if they are within the recommended cutting speed.

4) A 75-mm diameter bar of cold drawn wrought aluminum is to be turned with a high-speed steel cutting tool, using a cutting speed of 180 in/mm. Calculate the spindle speed that should be used.

5) Calculate the spindle speed required to mill a 745 nickel silver part using a ½ inch end milling cutter.

6) An AISI 4118 part having a hardness of 200 HB is to be machined on a milling machine. Calculate the spindle speeds for each of the operations below and the milling machine table feed rates for Operations a) and b).

a) Face mill top surface, using an 8-inch diameter cemented carbide face milling cutter having to teeth. (Use $f_t = 0.008$ in/tooth.)

b) Mill ¼ inch deep slot, using a ¾ inch diameter two-fluted high-speed steel end milling cutter.

c) Drill a 23/64 inch hole.

d) Ream the hole ⅜ inch, using HSS reamer.

7) A 3-inch diameter high-speed steel end milling cutter having 12 teeth is used to mill a piece of D2 high carbon, high chromium cold work tool steel having a hardness of 220 HB. The spindle speed used is 75 rpm, and the milling machine table feed rate is 10 in/mm. Check the cutting conditions with respect to the recommended values, and make recommendations for improvements, if possible.

Copyright 2004, Industrial Press, Inc., New York, NY

8) A 100–150 HB low carbon steel casting is to be machined with a 12-inch diameter cemented carbide face milling cutter having 14 teeth, using a spindle speed of 6o rpm and a table feed rate of 5 in/mm. Check these cutting conditions and recommend improvements, if possible.

9) Estimate the cutting speed and the power at the cutter and at the motor required to turn 210 HB AISI 1040 steel in a geared head lathe, using an uncoated carbide tool, a depth of cut of 0.125 in., a feed of 0.015 in/rev, and efficiency E of 0.80.

10) A 165 HB A286 high temperature alloy, or superalloy, is to be turned on a 3-hp geared head lathe using a cemented carbide cutting tool. The depth of cut selected is 0.100 inch, and the feed is 0.020 in/rev. Estimate the cutting speed that will utilize the maximum power available on the lathe.

11) An AISI 8642 steel having a hardness of 210 HB is to be milled with a 6-inch diameter cemented carbide face milling cutter having 8 teeth on a 10 hp milling machine. The depth of cut is to be 0.200 inch, the width is 4 inches, and the feed is to be 0.010 in/tooth. Estimate the cutting speed that will utilize the maximum power available on the machine.

12) Estimate the thrust, torque, and power at the motor required to drill 200 HB steel using the following drill sizes, feeds, and spindle speeds.

Drill Size	Feed	Spindle Speed
$\frac{1}{4}$ in.	0.0005 in/rev	1500 rpm
$\frac{1}{2}$ in.	0.002 in/rev	750 rpm
1 in.	0.008 in/rev	375 rpm
19 mm	0.15 mm/rev	500 rpm

13) Estimate the thrust, torque, and power at the motor for the 1-inch drill in Exercise 12 if the drill is ground to have a split point.

14) Describe the general characteristics of high speed steels that make them suitable for use as cutting tool materials.

15) What guidelines should be followed in selecting a grade of cemented carbide?

16) How does the cutting speed, feed, and depth of cut influence tool life?

Copyright 2004, Industrial Press, Inc., New York, NY

17) List the steps for selecting the cutting conditions in their correct order and explain why.

18) What are the advantages of coated carbides, and how should they be used?

19) Name the factors that must be considered when selecting a cutting speed for tapping.

20) Why is it important to calculate the table feed rate for milling?

21) Name the factors that affect the basic feed rate for milling.

22) When should the power required to take a cut be estimated? Why?

23) Name the factors that affect the power constant, K_p This constant is unaffected by what?

24) Why is it necessary to have a separate method for estimating the drilling thrust, torque, and power?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 21

NUMERICAL CONTROL

HANDBOOK Pages 1254 – 1314

Numerical control (NC) is defined by the Electronic Industries Association as "a system in which actions are controlled by the direct insertion of numerical data at some point. The system must automatically interpret at least some portion of these data." Applied to machine tools, NC is used to tell the unit what to do in such explicit detail that it can produce a component part or parts in a completely automatic cycle without intervention from the operator. This cycle may extend from loading of a raw casting or other workpiece through unloading of a finished component ready for assembly and can be repeated precisely, as often as required. An important aspect of NC is that machines so equipped can often be set up to process even single components economically.

Apart from systems that are designed to load, locate, and clamp the part to be machined, and to select the tool and the spindle speed to be used, for instance, NC installations use programs designed to control movements of the cutting edge of the tool relative to the work (or the work relative to the tool). These machining control instructions, called part programs, may be put together by a machine operator with a push-button panel on the machine if the part is simple, or they may be written in an engineering office, often with the aid of a computer. Some part programs may provide for simply moving the tool or workpiece from one position, at which a fixed machining cycle (known as a subroutine or subprogram) is to be performed, to other positions where the same cycle is to be repeated and triggering the subroutine at each position. Such a program is called point-to-point positioning. There are subroutines for drilling, reaming, counterboring, and tapping, for which tools will be inserted into, clamped, and removed from the spindle automatically.

Copyright 2004, Industrial Press, Inc., New York, NY

Other, more complex, programs may be written to cause the workpiece to move past the cutting tool in a series of curves, to generate contoured surfaces on the work. Such a program is called continuous-path or contouring program. In the associated machining operation, the movement of the table carrying the workpiece along (usually) two axis, and (sometimes) of the spindle head holding the cutter along one axis, is coordinated by electronic signals in a binary digital code that are converted to DC or AC power and fed continuously to controllers connected to the units powering the slides. Measuring equipment attached to each lead screw or slide provides continuous feedback information of the slide position to the control system for comparison with the command program.

Information in the Handbook, **pages 1254** to **1314**, is arranged by subject matter for ease of reference and, because of the complexity of the subject, depends to some extent on definitions to explain the various aspects. Much attention is paid to the use of the Automatic Programmed Tool (APT) language in part programming, and examples of typical computational and geometric programs are discussed. For instance, the APT language can be used to specify the four arithmetical operations and the exponential and trigonometric computations used in many algebraic formulas. The APT language visualizes the part program as if it were designed to move the tool past a stationary workpiece, but the formulas for generation of the required shapes most often are translated by the control system into movements of the slides to carry the workpiece past the cutting tool.

Point-to-Point Programming.— As an example of the use of NC for point-to-point part programs, consider the rectangular plate shown in **Fig. 1**, in which it is required to machine eight holes as shown. Dimensions for the positions of the holes are here provided in terms of their distances from *X* and *Y* axes, which are conveniently located at a central point on the part. This positioning information is easily transferred to the punched paper tape or other means used to feed it to the machine. Instructions for the tooling to be loaded into the spindle for the work to be performed are also included in the part program, in accordance with the special codes, many of which are listed in the Handbook. The hole location infor-

Copyright 2004, Industrial Press, Inc., New York, NY

mation in the table following Fig. 1 is entered in a part programming manuscript, together with coded details such as spindle speed and feed rates, and is subsequently saved in a form that will be read by the NC machine when the machining work is started.

Continuous-Path Programming.— Surfaces at angles to the axes and curved surfaces are produced by continuous-path, or contouring, programs. These programs coordinate two or more machine motions simultaneously and precisely, so that the movement of the workpiece relative to the cutting tool generates the required curved shape. Angular shapes are generated by straight-line or linear interpolation programs that coordinate movements of two slides to produce the required angle. Circular arcs can be generated by means of a circular interpolation program that controls the slide movements automatically to produce the curved outline. Arcs that are not circular generally must be broken down into a sequence of straight-line segments. Surfaces generated by this method can be held within tolerance by using a large number of segments closely spaced together.



Fig. 1. Alternative Methods of Dimensioning for the Positions of Eight Holes to Be Machined in a Rectangular Plate

Copyright 2004, Industrial Press, Inc., New York, NY

Point	Dimensions on Axes		Point	Dimensions on Axes	
	X	Y		X	Y
A	+ 1.000	+ 0.750	E	– 1.000	+ 0.750
B	+ 1.000	– 0.750	F	– 1.000	– 0.750
C	+ 2.500	+ 2.250	G	– 2.500	+ 2.250
D	+ 2.500	– 2.250	H	– 2.500	– 2.250



Fig. 2. Curved Path of Cutter Produced by a Circular Interpolation

For example, in programming the movement of a cutter, relative to the workpiece, along the curved line shown in the diagram, **Fig. 2**, it is first necessary to indicate that the cutter is to move in a clockwise and circular path by inserting code GO_2 into the program. Next, the movements along the *X* and *Y* axes, which define the component lengths of the arc, are inserted. In **Fig. 2**, the *X* movement is +1.4000 inches and the *Y* movement is –1.5000 inches. The *I* dimension of 0.5000 inch parallel to the *X* axis is the horizontal distance of point *A* from the arc center and is next included in the program. The vertical distance *J* of 1.9000 inches from the arc center to the circle is next entered, and the feed rate also must be entered.

Copyright 2004, Industrial Press, Inc., New York, NY

Fig. 3 and **4** are included as the basis for practice exercises only.



Fig. 3. Dimensions of a pocket to Be Milled under Numerical Control



Fig. 4. Circles for Which APT Statements Are Required

Copyright 2004, Industrial Press, Inc., New York, NY

PRACTICE EXERCISES FOR SECTION 21

(See *Answers to Practice Exercises For Section 21* on page 239)

1) List five or more machine tools on which point-to-point programming is used.

2) List five or more applications of continuous-path, or contouring, programs.

3) Give some reasons why NC machines are being used increasingly.

4) Which of the following applications of NC is the most used? (a) Grinding, (b) turning, (c) broaching.

5) A ___ is a rotary device used to feed signals to the control system to close the servo loop of an NC installation.

6) CNC systems are far superior to their hardwire predecessors. Name several advantages of CNC systems.

7) What purpose is served by the feedbacks in an NC servo system?

8) If a stepping motor connected directly to a lead screw rotates1.8 degrees per pulse, how far would a 5-pitch lead screw move a slide if the motor received 254 pulses?

9) With a CNC system, the *F* or feedrate word is most commonly described as (a) Ratio of rpm feed divided by the distance moved. (b) Directly in rpm.

10) The word that identifies a block is called a _____ _____.

11) The word address letter for the velocity of a slide on an NC machine is _____.

12) What is the difference between cutter offset and cutter compensation?

13) Circular interpolation reduces the number of straight–line segments required to be calculated when a machine is moving about a circular arc. (True, False.)

14) With most control systems, how many blocks would be needed to move around a complete circle (360 degrees) when circular interpolation is used?

15) In the first column below are shown the various subroutines or canned cycles. In the second column are some preparatory codes. Match the functions with the codes.

Copyright 2004, Industrial Press, Inc., New York, NY

a. Drill plus dwell	1. G89
b. Deep hole drill	2. G81
c. Boring, spindle rotating on withdrawal at feedrate	3. G85
d. Drill	4. G84
e. Tapping	5. G82
f. Boring, spindle rotating on withdrawal at feedrate plus dwell	6. G83

16) A parametric subroutine is used exclusively for describing the path around the outside of a part. (True, False.)

17) Computer-aided part programming refers to the assistance offered by the computer within the CNC system. (True, False.)

18) The media used for transmitting data and instructions to an NC system is (a) floppy disc, (b) magnetic tape, (c) punched tape.

19) Name the three surfaces involved in an APT move.

20) Two of the three surfaces in APT appear as lines when viewed from directly above. What are these surfaces?

21) What is a G word?

22) What is an APT startup statement?

23) Explain the rule that describes the orientation and directions of the motions of slides and spindles on a machine tool.

24) Write APT statements for the lines L1, L2, L3, and L4 for the pocket shown in **Fig. 3**. Assume that C1, C2, C3, and C4 are defined.

25) Write APT statements for the circles C1 through C4, shown in **Fig. 4**. Assume that L1, L2, L3, P1, P2, and P3 are defined.

26) Write computation statements for the following mathematical terms:

$$\frac{1+25}{42};\ 6\times 8+8\div 2-52;\ 6\times\frac{8\times 8}{2-52}$$

$$\frac{4^2+\sqrt{(12+8)^3}}{2\times 6.8\div 2(1+3)^4};\ \text{sin 30 degrees; arctan 0.486}$$

27) Of the five APT sections in a computer, which is responsible for developing the G and M words for a particular machine tool?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 22

GENERAL REVIEW QUESTIONS

(See *Answers to General Review Questions* on page 242)

1) If a regular polygon of 20 sides is to have an area of 100 square inches what formula may be used to calculate the length of one side of the polygon?

2) What does the number of a Jarno taper indicate?

3) What is the general rule for determining the direction in which to apply tolerances?

4) Why is 1 horsepower equivalent to 33,000 foot-pounds of work per minute? Why not 30,000 or some other number?

5) What is the chief element in the composition of babbitt metals?

6) If the pitch of a stub-tooth gear is $^{8}/_{10}$, what is the tooth depth?

7) What does the figure 8 mean if the pitch of a stub-tooth gear is $^{8}/_{10}$?

8) Explain how to determine the diametral pitch of a spur gear from a sample gear.

9) If a sample gear is cut to circular pitch, how can this pitch be determined?

10) What gage is used for seamless tubing, and does it apply to all metals?

11) How does the strength of iron wire rope compare with steel rope?

12) Is the friction between two bearing surfaces proportional to the pressure?

13) If the surfaces are well lubricated, upon what does frictional resistance depend?

14) What is the general rule for subtracting a negative number from a positive number? For example, 8 – (– 4) =?

15) Is 1 meter longer than 1 yard?

Copyright 2004, Industrial Press, Inc., New York, NY

16) On Handbook **page 2578**, two of the equivalents of horsepower-hour are: 1,980,000 foot-pounds and 2.64 pounds of water evaporated at 212°F. How is this relationship between work and heat established?

17) Are "extra strong" and "double extra strong" wrought or steel pipe larger in diameter than standard weight pipe?

18) In the design of plain bearings, what is the general relationship between surface finish and hardness of journal?

19) Are the nominal sizes of wrought or steel pipe ever designated by giving the outside diameter?

20) What are the advantages of plastics pipe?

21) Will charcoal ignite at a lower temperature than dry pine?

22) What general classes of steel are referred to as "stainless"?

23) What are free cutting steels?

24) Does the nominal length of a file include the tang? For example, is a 12-inch file 12 inches long over all?

25) Is steel heavier (denser) than cast iron?

26) What is meant by specific heat?

27) What is the specific gravity (a) of solid bodies, (b) of liquids, (c) of gases?

28) A system of four-digit designations for wrought aluminum and aluminum alloys was adopted by The Aluminum Association in 1954. What do the various digits signify?

29) What alloys are known as "red brass," and how do they compare with "yellow brass"?

30) What is the difference between adiabatic expansion or compression and isothermal expansion or compression?

31) Are the sizes of all small twist drills designated by numbers?

32) Why are steel tools frequently heated in molten baths to harden them?

33) In hardening tool steel, what is the best temperature for refining the grain of the steel?

34) In cutting a screw thread on a tap assume that the pitch is to be increased from 0.125 inch to 0.1255 inch to compensate for shrinkage in hardening. How can this be done?

35) What is the general rule for reading a vernier scale (a) for linear measurements; (b) for angular measurements?

Copyright 2004, Industrial Press, Inc., New York, NY

36) The end of a shaft is to be turned to a taper of $\frac{3}{8}$ inch per foot for a length of inches without leaving a shoulder at the end of the cut. How is the diameter of the small end determined?

37) Is there a simple way of converting the function of 90° plus an angle to the function of the angle itself?

38) What decimal part of a degree is 53 minutes?

39) If $10x - 5 = 3x + 16$, what is the value of x?

40) Approximately what angle is required for a cone clutch to prevent either slipping or excessive wedging action?

41) What is the coefficient of friction?

42) Is Stub's steel wire gage used for the same purpose as Stub's iron wire gage?

43) Why are some ratchet mechanisms equipped with two pawls of different lengths?

44) How does the modulus of elasticity affect the application of flat belts?

45) What is the effect of centrifugal force on flat and V-belts?

46) Is the ultimate strength of a crane or hoisting chain equal to twice the ultimate strength of the bar or rod used for making the links?

47) How would you determine the size of chain required for lifting a given weight?

48) If a shaft $3\frac{1}{2}$inches in diameter is to be turned at a cutting speed of 90 feet per minute, what number of revolutions per minute will be required?

49) In lapping by the "wet method," what kind of lubricant is preferable (a) with a steel lap, (b) with a cast-iron lap?

50) What is the meaning of the terms right-hand and left-hand as applied to helical or spiral gears, and how is the "hand" of the gear determined?

51) Are mating helical or spiral gears always made to the same hand?

52) How would you determine the total weight of 100 feet of $1\frac{1}{2}$ inch standard weight pipe?

53) What is the difference between casehardening and packhardening?

Copyright 2004, Industrial Press, Inc., New York, NY

54) What is the nitriding process of heat-treating steel?

55) What is the difference between single-cut and double-cut files?

56) For general purposes, what is the usual height of work benches?

57) What do the terms “major diameter” and ‘minor diameter” mean as applied to screw threads in connection with the American Standard?

58) Is the present SAE Standard for screw threads the same as the Unified and American Standard?

59) Does the machinability of steel depend only upon its hardness?

60) Is there any direct relationship between the hardness of steel and its strength?

61) What is the millimeter equivalent of $^{33}/_{64}$ths of an inch?

62) How is the sevolute function of an angle calculated?

63) What is the recommended cutting speed in feet per minute for turning normalized AISI 4320 alloy steel with a Bhn hardness of 250, when using an uncoated, tough carbide tool?

64) The diametral pitch of a spur gear equals the number of teeth divided by pitch diameter. Is the diametral pitch of the cutter or hob for a helical or spiral gear determined in the same way?

65) Why are casehardening steels preferred for some gears and what special heat treatment is recommended?

66) Are the symbols for dimensions and angles used in spline calculations the same for both inch-dimension and metric module involute splines?

67) What kind of bearing surface and tool insert rake are provided by an indexable insert tool holder?

68) Is it necessary in making ordinary working drawings of gears to lay out the tooth curves? Why?

69) In milling plate cams on a milling machine, how is the cam rise varied other than by changing the gears between the dividing head and feed screw?

70) How is the angle of the dividing head spindle determined for milling plate cams?

Copyright 2004, Industrial Press, Inc., New York, NY

71) How is the center-to-center distance between two gears determined if the number of teeth and diametral pitch are known?

72) How is the center-to-center distance determined for internal gears?

73) In the failure of riveted joints, rivets may fail through one or two cross-sections or by crushing. How may plates fail?

74) What gage is used in Britain to designate wire sizes?

75) What is a transmission dynamometer?

76) What is the advantage of a dynamometer for measuring power?

77) If a beam supported at each end is uniformly loaded throughout its length, will its load capacity exceed that of a similar beam loaded at the center only?

78) Is there any relationship between Brinell hardness and tensile strength of steel?

79) Is the outside diameter of a 2-inch pipe about 2 inches?

80) The hub of a lever 10 inches long is secured to a 1-inch shaft by a taper pin. If the maximum pull at the end of the lever equals 60 pounds, what pin diameter is required? (Give mean diameter or diameter at center.)

81) What are the two laws that form the basis of all formulas relating to the solution of triangles?

82) What are the sine and the cosine of the angle 45 degrees?

83) How is the pressure of water in pounds per square inch determined for any depth?

84) When calculating the basic load rating for a unit consisting of two bearings mounted in tandem, is the rated load of the combination equal to 2 times the capacity of a single bearing?

85) If a machine producing 50 parts per day is replaced by a machine that produces 100 parts per day, what is the percentage of increase?

86) If production is decreased from 100 to 50, what is the percentage of reduction?

87) What kind of steel is used ordinarily for springs in the automotive industry?

88) What is the heat-treating process known as “normalizing”?

89) What important standards apply to electric motors?

Copyright 2004, Industrial Press, Inc., New York, NY

90) Is there an American standard for section linings to represent different materials on drawings?

91) Is the taper per foot of the Morse standard uniform for all numbers or sizes?

92) Is there more than one way to remove a tap that has broken in the hole during tapping?

93) The center-to-center distance between two bearings for gears is to be 10 inches, with a tolerance of 0.005 inch. Should this tolerance be (a) unilateral and plus, (b) unilateral and minus, (c) bilateral?

94) How are the available pitch diameter tolerances for Acme screw threads obtained?

95) On Handbook **page 1331**, there is a rule for determining the pressure required for punching circular holes into steel sheets or plates. Why is the product of the hole diameter and stock thickness multiplied by 80 to obtain the approximate pressure in tons?

96) What gage is used in the United States for cold-rolled sheet steel?

97) What gage is used for brass wire and is the same gage used for brass sheets?

98) Is the term "babbitt metal" applied to a single composition?

99) What are the chief elements in high-grade babbitt metal?

100) How many bars of stock 20 feet long will be needed to make 20,000 dowel-pins 2 inches long if the tool for cutting them off is 0.100 inch wide?

101) What is the melting point and density of cast iron; steel; lead; copper; nickel?

102) What lubricant is recommended for machining aluminum?

103) What relief angles are recommended for cutting copper, brass, bronze, and aluminum?

104) Why is stock annealed between drawing operations in producing parts in drawing dies?

105) When is it advisable to mill screw threads?

106) How does a fluted chucking reamer differ from a rose chucking reamer?

107) What kind of material is commonly used for gage blocks?

108) What grade of gage blocks is used as shop standards?

Copyright 2004, Industrial Press, Inc., New York, NY

109) What is the "lead" of a milling machine?

110) The table on Handbook **page 1972** shows that a lead of 9.625 inches will be obtained if the numbers of teeth in the *driven* gears are 44 and 28 and the numbers of teeth on the *driving* gears 32 and 40. Prove that this lead of 9.625 inches is correct.

111) Use the prime number and factor table beginning on Handbook **page 20** to reduce the following fractions to their lowest terms: $^{210}/_{462}$; $^{2765}/_{6405}$; $^{741}/_{1131}$.

112) If a bevel gear and a spur gear each have 30 teeth of 4 diametral pitch, how do the tooth sizes compare?

113) For what types of work are the following machinists' files used: (a) flat files? (b) half round files? (c) hand files? (d) knife files? (e) general-purpose files? (f) pillar files?

114) Referring to the illustration on Handbook **page 713**, what is the dimension *x* over the rods used for measuring the dovetail slide if a is 4 inches, angle α is 60 degrees, and the diameter of the rods used is $^{5}/_{8}$ inch?

115) Determine the diameter of the bar or rod for making the links of a single chain required to lift safely a load of 6 tons.

116) Why will a helical gear have a greater tendency to slip on an arbor while the teeth are being milled than when milling a straight tooth gear?

117) What is meant by "trepanning"?

118) When is a removable or "slip" bushing used in a jig?

119) What are the relative ratings and properties of an H43 molybdenum high–speed tool steel?

120) What systematic procedure may be used in designing a roller chain drive to meet certain requirements as to horsepower, center distance, etc.?

121) In the solution of oblique triangles having two sides and the angle opposite one of the sides known, it is possible to have no solution or more than one solution. Under what condition will there be no solution?

122) What gear steels would you use (1) for casehardened gears? (2) for fully hardened gears? (3) for gears that are to be machined after heat treatment?

Copyright 2004, Industrial Press, Inc., New York, NY

123) Is it practicable to tap holes and obtain (1) Class 2B fits? (2) Class 3B fits?

124) What is the maximum safe operating speed of an organic bonded Type grinding wheel when used in a bench grinder?

125) What is the recommended type of diamond wheel and abrasive specification for internal grinding?

126) Is there a standard direction of rotation for all types of nonreversing electric motors?

127) Antifriction bearings are normally grease-lubricated. Is oil ever used? If so, when?

128) In the example on Handbook **page 1945**, the side relief angle at the leading edge of the single–point Acme thread cutting tool was calculated to be 19.27°, or 19°16′, which provides an effective relief angle (a_e) between the flank of the tool and the side of the thread of 10° at the minor diameter. What is the effective relief angle of this tool at the pitch diameter (E) and at the major diameter (D)? The pitch diameter of the thread is 0.900 inch, the major diameter is 1.000 inch, and the lead of the thread is 0.400 inch.

129) Helical flute milling cutters having eccentric relief are known to provide better support of the cutting edge than cutters ground with straight or concave relief. For a 1-inch diameter milling cutter having a 35-degree helix angle, what is the measured indicator drop according to the methods described beginning on Handbook page 800 if the radial relief angle is to be 7°?

130) On Handbook **page 2265**, Table 6 shows that TFE fabric bearings have a load capacity of 60,000 pounds per square inch. Also shown in the table is a PV limit of 25,000 for this material. At what maximum surface speed in feet per minute can this material operate when the load is 60,000 psi?

131) Is there a standard for shaft diameter and housing bore tolerance limits that applies to rolling element bearings?

132) In designing an aluminum bronze plain bearing, what hardness should the steel journal have?

133) Steel balls are usually sold by the pound. How many pounds will provide 100 balls of $^{13}/_{32}$-inch diameter carbon steel?

Copyright 2004, Industrial Press, Inc., New York, NY

134) If a 3AM1–18 steel retaining ring were used on a rotating shaft, what is the maximum allowable speed of rotation?

135) What procedure applies to 3-wire measurements of Acme threads when the lead angle is greater than 5 degrees?

136) Twelve 1½-inch diameter rods are to be packed in a tube. What is the minimum inside diameter of the tube?

Copyright 2004, Industrial Press, Inc., New York, NY

SECTION 23

ANSWERS TO PRACTICE EXERCISES

All references are to Handbook page numbers

Answers to Practice Exercises For Section 1

Number of Question	Answers (Or where information is given in Handbook)
1	78.54 mm^2; 31.416 mm
2	4.995 or 5, approx.
3	3141.6 mm^2
4	127.3 psi
5	1.27
6	1.5708
7	8 hours, 50 minutes
8	2450.448 pounds
9	$2\frac{1}{16}$ inches
10	7 degrees, 10 minutes
11	Yes. The *x*, *y* coordinates given in the tables of Jig Boring coordinates, Handbook **pages 993** to **1002**, may be used

Answers to Practice Exercises For Section 2

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **page 989**
2	(a) 0.043 inch, (b) 0.055 inch, (c) 0.102 inch
3	0.336 inch
4	2.796 inches
5	4.743 inches
6	4.221 feet
7	Handbook **page 63** and **71**
8	740 gallons, approximately

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 2 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
9	Formula on Handbook **page 78**
10	Formula on Handbook **page 78**
11	Formulas on Handbook **page 78**

Answers to Practice Exercises For Section 3

Number of Question	Answers (Or where information is given in Handbook)
1	(a) 104 horsepower; (b) if reciprocal is used, $H = 0.33\ D^2\ SN$
2	65 inches
3	5.74 inches
4	Side $s = 5.77$ inches; diagonal $d = 8.165$ inches, and volume = 192.1 cubic inches
5	91.0408 square inches
6	4.1888 and 0.5236
7	59.217 cubic inches
8	Handbook **page 2542**
9	$a = \frac{2A}{h} - b$
10	$r = \sqrt{R^2 - \frac{s^2}{4}}$
11	$a = \sqrt{\frac{(P/\pi)^2}{2} - b^2}$
12	$\text{Sin A} = \sqrt{1 - \text{Cos}^2\ \text{A}}$
13	$a = \frac{b \times \text{Sin A}}{\text{Sin B}}$; $\text{b} = \frac{a \times \text{Sin B}}{\text{Sin A}}$ $\text{Sin A} = \frac{a \times \text{Sin B}}{b}$ $\text{Sin B} = \frac{b \times \text{Sin A}}{a}$

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 4

Number of Question	Answers (Or where information is given in Handbook)
2	4; 35; 72
5	$5,954.45; $6,131.81

Answers to Practice Exercises For Section 5

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **page 112**
2	Table beginning on Handbook **page 115**
3	2; 2; 1; $\overline{3}$; 3; 1
4	As location of decimal point is indicated by characteristic, which is not given, the number might be 7082, 708.20, 70.82, 7.082, 0.7082, 0.07082, etc.; 7675, 767.5, etc.; 1689, 168.9, etc.
5	(a) 70.82; 76.75; 16.89; (b) 708.2; 767.5, 168.9; 7.082, 7.675, 1.689; 7082, 7675, 1689
6	2.88389; 1.94052; $\overline{3}$.94151
7	792.4; 17.49; 1.514; 486.5
8	4.87614; 1.62363
9	67.603; 4.7547
10	146.17; 36.8
11	9.88; 5.422; 5.208
12	0.2783
13	0.0000001432
14	237.6
15	187.08
16	14.403 square inches
17	2.203 or, say, 2¼ inches
18	107 horsepower
19	No
20	Yes, See **page 1950**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 6

Number of Question	Answers (Or where information is given in Handbook)
1	8001.3 cubic inches
2	83.905 square inches
3	69.395 cubic inches
4	1.299 inches
5	22.516 cubic inches
6	8 inches
7	0.0276 cubic inch
8	4.2358 inches
9	1.9635 cubic inches
10	410.5024 cubic inches
11	26.4501 square inches
12	Radius; 1.4142 inches; area, 0.43 square inch
13	Area, 19.869 square feet; volume, 10.2102 cubic feet
14	Area, 240 square feet; volume, 277.12 cubic feet
15	11.3137 inches
16	41.03 gallons
17	17.872 square gallons
18	1.032 inches
19	40 cubic inches
20	Table Handbook **page 74**
21	Table Handbook **page 74**
22	5.0801 inches
23	4 inches; 5226 inches

Answers to Practice Exercises For Section 7

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **page 49**
2	Handbook **page 49**
3	Handbook **page 49**
4	Handbook **page 49**
5	Handbook **page 50**
6	Handbook **page 50**
7	Handbook **page 50**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 7 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
8	Handbook **page 50**
9	Handbook **page 51**
10	Handbook **page 51**
11	Handbook **page 51**
12	Handbook **page 51**
13	Handbook **page 52**
14	Handbook **page 51**
15	Handbook **page 51**
16	Handbook **page 51**
17	Handbook **page 51**
18	Handbook **page 51**
19	Handbook **page 51**
20	Handbook **page 52**
21	Handbook **page 52**
22	Handbook **page 52**
23	Handbook **page 53**
23	Handbook **page 53**
24	Handbook **page 53**
25	Handbook **page 53**
26	Handbook **page 53**

Answers to Practice Exercises For Section 8

Number of Question	Answers (Or where information is given in Handbook)
1	See Handbook **pages 91 – 96**
2	In any right-angle triangle having an acute angle of 30 degrees, the side opposite that angle equals 0.5 × hypotenuse
3	Sine = 0.31634; tangent = 0.51549; cosine = 0.83942
4	Angles equivalent to tangents are 27°29′24″ and 7°25′16″; angles equivalents to cosines are 86°5′8″ and 48°26′52″

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 8 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
5	Rule 1: Side opposite = hypotenuse × sine; Rule 2: Side opposite = side adjacent × tangent
6	Rule 1: Side adjacent = hypotenuse × cosine; Rule 2: Side adjacent = side opposite × cotangent
7	Handbook **page 91**
8	Handbook **page 89**
9	After dividing the isosceles triangle into two right angle triangles
10	Page **91**

Answers to Practice Exercises For Section 9

Number of Question	Answers (Or where information is given in Handbook)
1	2 degrees, 58 minutes
2	1 degree, 47 minutes
3	2.296 inches, as shown by the table on Handbook **page 992**
4	$360°/N - 2a$ = angle intercepted by width W. The sine of ½ this angle; $\frac{1}{2}B = \frac{1}{2}W$ hence, this sine × $B = W$
5	3.1247 inches
6	3.5085 inches
7	1.7677 inches
8	75 feet approximately
9	a = 1.0316 inches; b = 3.5540 inches; c = 2.2845 inches; d = 2.7225 inches
10	$a = 18°22'$. For solution of similar problem, see **Example 4** of Section 8

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 9 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
11	$A = 5.8758''$; $B = 6.0352''$; $C = 6.2851''$; $D = 6.4378''$; $E = 6.1549''$; $F = 5.8127''$. apply formula on Handbook page 94
12	2°37′33″; 5°15′6″
13	5.2805 inches
14	10 degrees, 23 minutes

Answers to Practice Exercises For Section 10

Number of Question	Answers (Or where information is given in Handbook)
1	84°; 63°31′; 32°29′
2	$B = 29°$; $b = 3.222$ feet; $c = 6.355$ feet; area = 10.013 square feet
3	$C = 22°$; $b = 2.33$ inches; $c = 1.358$ inches; area = 1.396 square inches
4	$A = 120°10′$; $a = 0.445$ foot; $c = 0.211$ foot; area = 0.027 square feet
5	The area of a triangle equals one-half the product of two of its sides multiplied by the sine of the angle between them. The area of a triangle may also be found by taking one-half of the product of the base and the altitude

Answers to Practice Exercises For Section 11

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook page 927 for Morse Handbook page 937 for Jarno Handbook page 937 for milling machine Handbook page 1677 for taper pins
2	2.205 inches; 12.694 inches

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 11 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
3	4.815 inches. Handbook **page 696**
4	1.289 inches. Handbook **page 696**
5	3.110 inches. Handbook **page 697**
6	0.0187 inch
7	0.2796 inch
8	1.000 inch
9	26 degrees, 7 minutes

Answers to Practice Exercises For Section 12

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **pages 647**, **649**
2	Handbook **page 646**
3	Handbook **page 646**
4	Handbook **page 645**
5	Handbook **page 678**
6	Handbook **page 1736**
7	Handbook **pages 1725**, **1736**
8	When the tolerance is unilateral
9	See Handbook **page 646**
10	It means that a tolerance of 0.0004 to 0.0012 inch could normally be worked to. See table on Handbook **page 652**
11	Yes. See Handbook **page 729**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 13

Number of Question	Answers (Or where information is given in Handbook)
1	4000 pounds. Handbook **page 372**
2	Handbook **page 377**
3	430 balls. Handbook **page 2330**
4	¼ inch. Handbook **page 2363**
5	0.172 inch. Handbook **page 1720**
6	0.1251 to 0.1252. Handbook **page 1670**
7	24,000 rpm. Handbook **page 1688**
8	0.128 inch. Handbook **page 1649**

Answers to Practice Exercises For Section 14

Number of Question	Answers (Or where information is given in Handbook)
1	Both countries have used the Unified Standard, but Britain is changing to the ISO Metric. See Handbook **page 1725** and **page 1814**
2	The symbol is used to specify an American Standard screw thread 3 inches in diameter, 4 threads per inch or the coarse series, and Class 2 fit
3	An Acme thread is stronger, easier to cut with a die, and more readily engaged by a split nut used with a lead screw
4	The Stub Acme form of thread is preferred for those applications where a coarse thread of shallow depth is required
5	See tables, Handbook **pages 1763**, **1764**
6	¾ inch per foot measured on the diameter–American and British standards
7	Handbook **page 1834**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 14 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
8	Center line of tool is set square to axis of screw thread
9	Present practice is to set center line of tool square to axis of pipe
10	See formulas for F_{rn} and F_{rs}, Handbook **page 1834**
11	By three-wire method or by use of special micrometers. See Handbook **pages 1893** to **1914**
12	Two quantities connected by a multiplication sign are the same as if enclosed by parantheses. See instructions about order of operations, Handbook **page 5**
13	(a) Lead of double thread equals twice the pitch; (b) lead of triple thread equals three times the pitch. See Handbook **page 1893**
14	See Handbook **page 1734**
15	0.8337 inch. See **page 1901**
16	No. Bulk of production is made to American Standard dimensions given in Handbook
17	This standard has been superseded by the American Standard
18	Most Machine screws (about 80% of the production) have the coarse series of pitches
19	(a) Length includes head; (b) Length does not include head
20	No. 25. See table, Handbook **page 1934**
21	0.1935 inch. See table, Handbook **page 856**
22	Yes. The diameters decrease as the numbers increase
23	The numbered sizes range in diameter from 0.0059 to 0.228 inch, and the letter sizes from 0.234 to 0.413 inch. See Handbook **pages 854** to **864**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 14 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
24	A thread of ¾ standard depth has sufficient strength, and tap breakage is reduced
25	(a) and (b) the American Standard Unified form
26	Cap-screws are made in the same pitches as the Coarse-, Fine-, and 8- thread series of the American standard, class 2A
27	For thread form, see Handbook **page 1872**. There are seven standard diameters as shown on **page 1873**.
28	Handbook **page 892**
29	Handbook **page 892**
30	0.90 × pitch. See Handbook **pages 1896**
31	To reduce errors in the finished thread
32	Included angle is 82° for each

Answers to Practice Exercises For Section 15

Number of Question	Answers (Or where information is given in Handbook)
1	A foot-pound in mechanics is a unit of work and is the work equivalent to raising 1 pound 1 foot high
2	1000 foot-pounds
3	Only as an average value. See Handbook **page 175**
4	28 foot-pounds. See Handbook **pages 173** and **175**
5	1346 pounds
6	Neglecting air resistance, the muzzle velocity is the same as the velocity with which the projectile strikes the ground. See Handbook **page 167**
7	See Handbook **page 148**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 15 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
8	Square
9	1843 pounds approximately
10	The pull will have been increased from 1843 pounds to about 2617 pounds. See Handbook **page 161**
11	Yes
12	About 11 degrees
13	The angle of repose
14	The coefficient of friction equals the tangent of the angle of repose
15	32.16 feet per second^2
16	No. 32.16 feet per second^2 is the value at sea level at a latitude of about 40 degrees, but this figure is commonly used. See Hand book **page 142**
17	No. The rim stress is independent of the diameter and depends upon the velocity. See Handbook **page 188**
18	10 to 13. See Handbook **page 190**
19	No. The increase in stress is proportional to the square of the rim velocity
20	110 feet per second or approximately 1.25 miles per minute
21	Because the strength of wood is greater in proportion to its weight than cast iron
22	See Handbook **page 195**
23	In radians per second
24	A radian equals the angle subtended by the arc of circle; this angle is 57.3 degrees nearly
25	Handbook **page 97**
26	60 degrees; 72 degrees; 360 degrees
27	Handbook **page 97**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 15 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
28	Handbook **page 195** (see Guide **page 135** for example illustrating method of using tables)
29	Length of arc = radians × radius. As radius = 1 in the table segments, l = radians
30	40 degrees, 37.5 minutes
31	176 radians per second; 1680.7 revolutions per minute
32	1.5705 inches
33	27.225 inches

Answers to Practice Exercises For Section 16

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **page 208**
2	12,000 pounds
3	1 inch
4	Handbook **page 554**
5	Handbook **page 203**
6	Handbook **page 554**
7	3-inch diameter. See Handbook **page 290**

Answers to Practice Exercises For Section 17

Number of Question	Answers (Or where information is given in Handbook)
1	1.568 (See formula on Handbook **page 249**)
2	6200 pounds per square inch approximately
3	It depends upon the class of service. See Handbook **page 303**
4	Tangential load = 550 pounds; twisting moment = 4400 inch-pounds
5	See formulas on Handbook **page 302**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 17 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
6	The head is useful for withdrawing the key, especially when it is not possible to drive against the inner end. See Handbook **page 2366**
7	Key is segment-shaped and fits into circular key-seat. See Handbook **pages 2369**, **2370**
8	These keys are inexpensive to make from round bar stock, and keyseats are easily formed by milling
9	0.211 inch. See table, Handbook **page 2375**

Answers to Practice Exercises For Section 18

Number of Question	Answers (Or where information is given in Handbook)
1	See text and footnote on Handbook **page 2156**
2	American Standard B92.1, Handbook **pages 2156** and **2162**
3	See text, Handbook **page 2156**
4	See text, Handbook **page 2156**
5	See definitions, Handbook **page 2158**
6	None. See text, Handbook **page 2162**
7	Yes, a crowned spline permits small amount of misalignment. See Handbook **page 2174**.
8	The torque capacity of splines may be calculated using the formulas and charts on Handbook **page 2170** to **2174**
9	Handbook **page 2169**
10	The fillet radius permits heavier loading and effects greater fatigue resistance than flat roots through absence of stress raisers

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 19

Number of Question	Answers (Or where information is given in Handbook)
1	18 teeth; 3 inches; 0.2618 inch
2	2.666 inches; 2.333 inches; 0.166 inches
3	Handbook **page 2039** and **page 2040**
4	Chordal thickness at intersections of pitch circle with sides of tooth
5	Table, Handbook **page 2038**
6	Calculate using table, Handbook **page 2040**
7	Surface durability stress and tooth fillet tensile stress are the two principle factors to be found in determining the power transmitting capacity of spur gears.
8	Because the tooth shape varies as the number of teeth is changed
9	No; one hob may be used for all tooth numbers, and the same applies to any generating process
10	Stub
11	Handbook (see *Fellows Stub Tooth* on **page 2041**)
12	Handbook **page 2121**
13	Handbook **page 2051**
14	Handbook **page 2041**
15	See table on Handbook **page 2040**
16	Handbook **page 1950**
17	Handbook **pages 2067** to **2072**
18	Handbook **page 2122**
19	Yes, but accurate tooth form is obtained only by a generating process
20	See paragraph on Handbook **page 2091**
21	Handbook **page 2085**
22	When the numbers of teeth in both the pinion and the gear are the same, the pitch angle being 45 degrees for each

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 19 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
23	The whole depth minus the clearance between the bottom of a tooth space and the end of a mating tooth = the working depth
24	See Handbook **page 2045**
25	See Handbook **pages 2033** and **2035**
26	See diagram, Handbook **page 2085**
27	Circular pitch of gear equals linear pitch of worm
28	Helix angle or lead angle of worm is measured from a plane perpendicular to the axis; helix angle of a helical gear is measured from the axis
29	These terms each have the same meaning
30	To provide a grinding allowance and to increase hob life over repeated sharpening
31	See explanation beginning on Handbook **page 2098**
32	Handbook **page 2098**
33	Handbook **page 2100**
34	Normal diameter pitch is commonly used
35	Yes (See Handbook **page 2100**), but the hobbing process is generally applied
36	Pitch diameter
37	Handbook **page 2114**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 20

Number of Question	Answers (Or where information is given in Handbook)
1	AISI 1108 CD ½ in. dia. = 1008 rpm 12L13, 150–200 HB : = 1192 rpm 1040, HR : = 611 rpm 1040, 375–425 HB : = 214 rpm 41L40, 200–250 HB : = 718 rpm 4140, HR : = 611 rpm O2, Tool Stee : = 535 rpm M2, Tool Steel : = 497 rpm AISI 1108 CD : 4 in.dia. = 126 rpm 12L13, 150–200 HB : = 149 rpm 1040, HR : = 576 rpm 1040, 375–425 HB : = 27 rpm 41L40, 200–250 HB : = 90 rpm 4140, HR : = 76 rpm O2, Tool Steel : = 67 rpm M2, Tool Steel : = 62 rpm
2	AISI 1330, 200 HB : 153 rpm 201 Stainless Steel, CD : 345 rpm ASTM Class 50 Gray Cast Iron : 145 rpm 6A1 – 4V Titanium Alloy : 52 rpm Waspaloy : 20 rpm (V = 60 fpm)
3	1½-in. Dia.: 157 fpm—OK 3-in. Dia. : 314 fpm—OK 4-in. Dia. : 419 fpm—Too Fast
4	764 rpm
5	840 rpm (V = 110 fpm)
6	Operation: 1: N = 167 rpm; f_m = 13 in./ min. 2: N = 127 rpm; f_m = 2.0 in./ min. 3: N = 744 rpm 4: N = 458 rpm

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 20 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
7	Existing operation: V = 59 fpm (Too Fast) f_t = 0.011 in./ tooth (Too Severe) Change to: V = 40 fpm N = 50 rpm f_t = 0.006 in./ tooth; f_m = 3.6 in/ min
8	Existing operation: V = 188 fpm (Too slow) f_t = 0.006 in./ tooth (Too Slow) Change to: V = 375 fpm N = 120 rpm f_t = 0.012 in/ tooth; f_m = 520 in/ min
9	V = 414 fpm, P_c = 9.0 hp, P_m = 11.24 hp
10	V = 104 fpm
11	V = 205 fpm (Q_{max} = 8.55 in^3/ min.; f_m = 10.5 in/ min; N = 131 rpm)
12	¼ in.:T = 123 lb; M = 6.38 in-lb; P_m = 0.19 up ½ in.: T = 574 lb; M = 68 in-lb; P_m = 1.0 hp 1 in.: T = 2712 lb; M = 711 in-lb; P_m = 5.3 hp 19 mm.: T = 7244 N; M = 37.12 N-m; P_m = 2.43 kw
13	T = 1473 lb; M = 655 in-lb; P_m = 4.9 hp
14	Handbook **page 1009**
15	Handbook **page 1010**
16	Handbook **page 1013**
17	Handbook **page 1014**
18	Handbook **page 776** and **1011**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 20 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
19	Handbook **pages 1072** and **1074**
20	Handbook **pages 1040** and **1043**
21	Handbook **page 1040**
22	Handbook **page 1084**
23	Handbook **pages 1084**, and **1085**
24	Handbook **page 1090**

Answers to Practice Exercises For Section 21

Number of Question	Answers (Or where information is given in Handbook)
1	Drill press, Jig-borer, turret punch press, spot welder, riveting machine, shear, inspection machine
2	Contour milling machine, lathe, grinder, vertical mill, flame cutting machine
3	NC machines are more productive, more accurate, and produce less scrap, see Handbook **page 1254**
4	(b)
5	Resolver. See Handbook **page 1262**
6	CNC systems are less costly, more reliable, and have greater capability than hardware. See Handbook **page 1254**
7	They provide data of slide position and velocity. See Handbook **page 1262**
8	At 1.8 degrees per pulse, 200 pulse would be needed to turn the lead screw 360 degrees, or one revolution. With a 5-pitch screw, the linear movement of the slide would be 0.200 inch, or 0.001 inch per pulse. With 254 pulses, the slide would move 0.254 inch.
9	(b). See Handbook **page 1280**
10	Sequence number. See Handbook **page 1274**
11	F. See Handbook **page 1278**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 21 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
12	Cutter offset is an adjustment parallel to one of the axes. (See Handbook **page 1280**.) Cutter compensation is an adjustment that is normal to the part, weather or not the adjustment is parallel to an axis. See Handbook **page 1282**
13	False. Circular interpolation eliminates the need for approximating straight lines.See Handbook **page 1282**
14	One. See Handbook **page 1282**
15	a–5, b–6, c–3, d–2, e–4, f–1. See Handbook **pages 1287 – 1291**
16	False. See Handbook **page 1286**
17	False. See Handbook **page 1287**
18	All three. See Handbook **page 1254**
19	Drive, part, and check surfaces. See Handbook **pages 1299 – 1304**
20	Drive, part, and check surfaces. See Handbook **page 1299**
21	A G word is a preparatory code word consisting of the three address G, and two digits, that is used to tell the control system to accept the remainder of the block in the required way. See Handbook **pages 1274 – 1278**
22	A startup statement consists of code instructions that will move the workplace into contact with one or more of the three guiding surfaces (drive, part, and check). See Handbook **pages 1292 – 1307**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 21 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
23	The "right hand rule" says that if a right hand is laid palm up on the table of a vertical milling machine, the thumb will point in the positive X direction, the forefinger in the positive Y direction, and the erect middle finger in the positive Z direction. See Handbook **page 1264**
24	L_1 = LINE/ RIGHT, TANTO, C_1, RIGHT, TANTO, C_2 *or* L_1 = LINE/ LEFT, TANTO, C_2, LEFT, TANTO, C_1 L_2 = LINE/ RIGHT, TANTO, C_2, RIGHT, TANTO, C_3 *or* L_2 = LINE/ LEFT, TANTO, C_3, LEFT, TANTO, C2 L_3 = LINE/ RIGHT, TANTO, C3, RIGHT, TANTO, C_4 *or* L_3 = LINE/ LEFT, TANTO, C_4, LEFT, TANTO, C_3 L_4 = LINE/ RIGHT, TANTO, C_4, RIGHT, TANTO, C_1 *or* L_4 = LINE/ LEFT, TANTO, C_1, LEFT, TANTO, C_4 See Handbook **page 1296**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to Practice Exercises For Section 21 *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
25	C_1 = CIRCLE/ XLARGE, L_1,YSMALL, L_2, RADIUS, C_2 = CIRCLE/ TANTO, L_2, XSMALL, P_1, RADIUS, .75 C_3 = CIRCLE/P_1, P_2, P_3 C_4 = CIRCLE/CENTER, P_3, TANTO, l_3 See Handbook **pages 1298**, **1301**
26	(1+25)/42 6*8 + 8/2–52 6*(8+8)/(2– 52) (4**2 +SQRTF((12+8)**3))/(2*6.8/(1+3)**4) SINF(30) ATANF(.486) See Handbook **page 1294**
27	Postprocessor. See Handbook **page 1294**

Answers to General Review Questions

Number of Question	Answers (Or where information is given in Handbook)
1	Handbook **page 69** gives the formula for length of side *S* in terms of the given area *A*
2	The diameter of each end and the length of the taper; see explanation on Handbook **page 926**, also table, **page 937**
3	Tolerance is applied in whatever direction is likely to be the least harmful; see **page 647**
4	It is said that James Watt found, by experiment, that an average carthorse can develop 22,000 foot-pounds per minute, and added 50 percent to ensure good measure to purchasers of his engines (22,000 × 1.50 = 33,000)
5	Tin in the high grades, and lead in the lower grades
6	Same depth as ordinary gear of 10 diametral pitch

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
7	The tooth thickness and the number of teeth are the as an ordinary gear of 8 diametral pitch
8	Add 2 to the number of teeth and divide by the outside diameter
9	Multiply the outside diameter by 3.1416 and divide the product by the number of teeth plus 2
10	Birmingham or Stub's iron wire gage is used for seamless steel, brass, copper, and aluminium tubing
11	Iron wire rope has the least strength of all wire rope materials. See Handbook **page 369**
12	If surfaces are well lubricated, the friction is almost independent of the pressure, but if the surfaces are unlubricated, the friction is directly proportional to the normal pressure except for the higher pressures
13	It depends very largely upon temperature. See Handbook section, *Lubricated Surfaces* on **page 157**
14	8 – (– 4) = 12. See rules for positive and negative numbers, Handbook **page 4**
15	Yes. One meter equals 3.2808 feet; see other equivalents on Handbook **page 2549**
16	Experiments have shown that there is a definite relationship between heat and work and that 1 British thermal unit equals 778 foot-pounds. To change 1 pound of water at 212°F into steam at that temperature requires about 966 British thermal units, or 966 × 788 = about 751,600 foot-pounds; hence, the number of pounds of water evaporated 212°F, equivalent to 1 horsepower-hour = 1,980,000 ÷ 751,600 = 2.64 pounds of water as given in Handbook, **page 2578**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
17	No. The thickness of the pipe is increased by reducing the inside diameter; compare thickness in the table on Handbook **page 2527**
18	As a general rule, smoother finishes are required for harder materials, for high loads, and for high speeds. See Handbook **page 2225**
19	Yes. The so-called "O.D. pipe" begins, usually, with the ¼-inch size
20	It is light in weight and resists deterioration from corrosive or caustic fluids. See Handbook **page 2532**
21	Yes. About 140 degrees lower. See Handbook **page 403**
22	Low-carbon alloy steels of high-chromium content. See Handbook **page 439**
23	Low-carbon steels containing 0.20% sulfur or less and usually from 0.90 to 1.20% manganese. See Handbook **page 454**
24	No. The nominal length of a file indicates the distance from the point to the "heel" and does not include the tang
25	Yes. See table, Handbook **page 407**
26	Specific heat is a ratio of the amount of heat required to raise the temperature of a certain weight of substance 1°F to the amount of heat required to raise the temperature of an equivalent of water 1°F. See Handbook **page 399**
27	(a) and (b) A number indicating how a given volume of the material or liquid compares in weight with an equal volume of water. (c) A number indicating a comparison in weight with an equal volume of air. See Handbook **pages 407 – 408**
28	The first digit identifies the alloy type; the second, the impurity control; etc. See Handbook **page 575**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
29	Red brass contains 84 to 86% copper, about 5% tin, 5% lead, and 5% zinc whereas yellow brass contains 62 to 67% copper, about 30% zinc, 1.5 to 3.5% lead and not even 1% tin. See UNS Designations on Handbook **pages 556**, **571**
30	See Handbook **pages 430** and **433**
31	No. Twenty-six sizes ranging from 0.234 to 0.413 inch are indicated by capital letters of the alphabet (see table, Handbook **page 856– 864**). Fractional sizes are also listed in manufacturers' catalogues beginning either at $\frac{1}{32}$ inch ,$\frac{1}{16}$ inch, or $\frac{1}{8}$ inch, the smallest size varying with different firms
32	To ensure uniform heating at a given temperature and protect the steel against oxidation. See Handbook **page 516**
33	Hardening temperature vary for different steels; see critical tempratures and how they are determined, Handbook **pages 515** and **516**
34	Set the taper attachment to an angle the cosine of which equals 0.125 ÷ 0.1255. See Handbook **page 1964**
35	See Handbook **page 692**
36	Divide $\frac{3}{4}$ by 12; multiply the taper per inch found by 5 and subtract the result from the large diameter. See rules for figuring tapers, Handbook **page 713**
37	Yes. See "Useful Relationships Among Angles," Handbook **page 99**
38	0.8833. See Handbook **page 97**
39	x = 3
40	About $12\frac{1}{2}$ degrees. See Handbook **page 2351**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
41	Ratio between resistance to the motion of a body due to friction, and the perpendicular pressure between the sliding and fixed surfaces. See formula, Handbook **page 157**
42	No. Stub's steel wire gage applies to tool steel rod and wire, and the most important applications of Stub's iron wire gage (also known as Birmingham) are to seamless tubing, steel strips, and telephone and telegraph wire
43	If the difference between the length of the pawls equals one-half of the pitch of the ratchet wheel teeth, the practical effect is that of reducing the pitch of one-half. See ratchet gearing, Handbook **page 2099**
44	The high modulus of elasticity eliminates the need for periodic retensioning that is normally required with V-belts. See Handbook **page 2388**
45	Increasing centrifugal force has less effect on flat belts because of the low center of gravity. See Handbook **page 2388**
46	The ultimate strength is less due to bending action. See formula, Handbook **page 386**, and also Handbook table, *Close-link Hoisting, Sling and Crane Chain* on **page 390**
47	Refer to Handbook **page 388**
48	Multiply 90 by 12 and divide the circumference of the shaft to obtain rpm. See cutting speed calculations, Handbook **pages 1016– 1018**
49	(a) Lard oil; (b) gasoline
50	If the teeth advance around the gear to the right, as viewed from one end, the gear is right handed; and, if they advance to the left, it is a left hand gear. See illustrations, Handbook **page 2099**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
51	No. They may be opposite hand depending upon the helix angle. See Handbook **pages 2099** and **2100**
52	Multiply the total length by the weight per foot for plain end and coupled pipe, given in the table, Handbook **page 2527**
53	The processes are similar but the term "packhardening" usually is applied to the casehardening of tool steel. See Handbook **page 526** and **page 516**
54	A gas process of surface hardening. See Handbook **page 526**
55	See definitions for these terms given on Handbook **page 962**
56	About 34 inches, but the height may vary from 32 to 36 inches for heavy and light assembling, respectively
57	Major diameter is the same as outside diameter, and the minor diameter is the same as root diameter. See definitions, on Handbook **page 1729**
58	The SAE Standards conforms, in general, with the Unified and American Standard Screw Thread Series as revised in 1959 and may, therefore, be considered to be the same for all purpose
59	See informations on work materials, Handbook **page 1009**
60	Yes. See Handbook **page 513** and **page 552**
61	13.097 millimeters. See the table on Handbook **page 2552**, which gives millimeter equivalents of inch fractions, inches, and feet

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
62	The sevolute of an angle is obtained by subtracting the involute of the angle from the secant of that angle. See Handbook **page 103**. The involute functions of angels are found in the tables beginning on handbook **page 104**
63	According to the table on Handbook page 990, the recommended cutting speed is 200 feet per minute at 0.017 in./rev. These speed is for average conditions and is intended as a starting point, so it is important to know the factors that's affect the cutting speed as covered in the "How to Use the Feeds and Speeds Tables" section on Handbook **page 1027**
64	No. First determine the diametral pitch the same as for a spur gear; then divide this "real diametral pitch" by the cosine of "real diametral pitch" by the cosine of the helix angle to obtain the "normal diametral pitch." which is the pitch of the cutter. See Handbook **page 2100**
65	Casehardening steels can have hard, fine grained surfaces and a soft, ductile core giving good strength combined with wear resistence.See Handbook **page 2144**
66	Not in every instance. See Handbook **page 2176**
67	A cemented carbide seat provides a flat bearing surface and a positive-, negative-, or neutral-rake orientation to the tool insert. See Handbook **page 758**
68	No. The size of the gear blank, the pitch of the teeth, and depth of cut are sufficient for the opearator in the shop. The tooth curvature is the result of the gear-cutting process. Tooth curves on the working drawing are of no practical value

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
69	By changing the inclination of the dividing head spindle. See Handbook **page 2212**
70	See formula and example on Handbook **page 2212**
71	Divide the total number of teeth in both gears by twice the diametral pitch to obtain the theoretical center-to-center distance. (See formula in the table of Formulas for Dimensions of Standard Spur Gears, Handbook **page 2035**)
72	Subtract number of teeth on pinion from number of teeth on gear and divide the remainder by two times the diametral pitch (See Rule at bottom of Handbook **page 2075**)
73	See Handbook **page 1479**
74	The Standard Wire Gage (S.W.G), also known as the Imperial Wire Gage and as the English Legal Standard, is used in Britain for all wires
75	A simple type of apparatus for measuring power
76	With a dynamometer, the actual amount of power delivered may be determined; that is, the power input minus losses. See Handbook **page 2360**
77	The uniformly loaded beam has double the load capacity of a beam loaded at the center only. See formulas, Handbook **page 261**
78	Refer to Handbook **page 514** for graph of SAE–determined relationships.
79	No. The nominal size of steel pipe, except for sizes above 12 inches, is approximately equal to the inside diameter. See tables, Handbook **pages 2527** and **2529**
80	0.357 inch. See formula, Handbook **page 224**
81	The laws of sines and cosines are stated on Handbook **page 89**
82	Both the sine and cosines of 45 degrees are 0.70711

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
83	Multiply depth in feet by 0.4335
84	No. See Handbook **page 2314**
85	100%
86	50%
87	Various steels are used, depending on kind of spring. See Handbook **page 450**
88	Normalizing is a special annealing process.The steel is heated above the critical range and allowed to cool in still air at ordinary temperature, Handbook **page 526**. Normalizing temperatures for steels are given on Handbook pages **page 532** – **533**
89	The standard mounting dimensions, frame sizes, horsepower, and speed ratings. See section beginning on Handbook **page 2465**
90	Yes. The American standard drafting room practice includes section lining, etc. See Handbook **page 632**
91	No. There are different tapers per foot, ranging from 0.5986 to 0.6315 inch. See table, Handbook **page 927**
92	Yes. See Handbook **page 1941**
93	Unilateral and plus. See Handbook **page 646**
94	See table, Handbook **page 1832**
95	If D = diameter of hole in inches; T = stock thickness in inches; shearing strength of steel = 51,000 pounds per square inch, then tonnage for punching = $51{,}000D\pi T/2000 = 80DT$
96	See Handbook **pages 2522** to **2523**
97	The Brown & Sharpe or American wire gage is used for each. See Handbook **pages 2519** to **2523**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
98	No, this name is applied to several compositions that vary widely
99	Antimony and copper
100	177 nearly. See table on Handbook **page 1137**
101	See Handbook pages **page 398**, **403**, to **407**
102	See Handbook **page 1147**
103	See Handbook **page 1148**
104	See Handbook **page 1330**
105	See Handbook **page 1964**
106	See Handbook **page 833**
107	Steel, chromium-plated steel, chromium carbide, tungsten carbide, and other materials. See Handbook **page 743**
108	See text on Handbook **page 743**
109	The lead of a milling machine equals lead of helix or spiral milled when gears of equal size are placed on feed screw and wormgear stud; see rule for finding lead on Handbook **page 1981**
110	Multiply product of driven gears by lead of machine and divide by product of driving gears. If lead of machine is 10, divide 10 times product of driven gears by product of drivers
111	$5/11$; $79/183$; $19/29$
112	The whole depth and tooth thickness at the large ends of the bevel gear teeth are the same as the whole depth and thickness of spur gear teeth of the same pitch
113	See Text on Handbook **page 963**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
114	5.7075 inches
115	Use the formula (Handbook **page 386**) for finding the breaking load, which in this case is taken as three times the actual load. Transposing, $D = \sqrt{\frac{6 \times 2000 \times 3}{54,000}} = 0.816$, say, $\frac{7}{8}$ inch diameter
116	Because the direction of the cutter thrust tends to cause the gear to rotate upon the arbor. See Handbook *Milling the Helical Teeth* on **page 2109**
117	Trepanning describes use of a fly-cutter or circular toothed cutter to cut a groove to the full depth of a plate, producing a hole of the required size. See Handbook **page 1081**
118	Chiefly when a hole is to be tapped or reamed after drilling. See Handbook **page 976**
119	See table on Handbook **page 492**
120	See Handbook **page 2464**
121	See Handbook **page 95**
122	See Handbook **page 2144** and **2145**
123	See Handbook **page 915**
124	See table Handbook **page 1210**
125	See table Handbook **page 1194**
126	Motor rotation has been standardized by the National Electrical Manufacturers Association. See Handbook **page 2467**

Copyright 2004, Industrial Press, Inc., New York, NY

Answers to General Review Questions *(Continued)*

Number of Question	Answers (Or where information is given in Handbook)
127	Yes.See last paragraph on Handbook **page 2340**
128	To solve this problem, the helix angle ϕ of the thread at the pitch and major diameters must be found, which is accomplished by substituting these diameters (E and D) for the minor diameters (K) in the formula for ϕ. Thus, at the pitch diameter: $\tan\phi = \frac{\text{lead of thread}}{\pi E} = \frac{0.400}{\pi \times 0.900}$ $\phi = 8.052^\circ = 8^\circ 3'$ $a = a_e + \phi$ $a_e = a - \phi = 19^\circ 16' - 8^\circ 3' = 11^\circ 13'$ At the major diameter: $\tan\phi = \frac{\text{lead of thread}}{\pi D} = \frac{0.400}{\pi \times 1.000}$ $\phi = 7.256^\circ = 7^\circ 15'$ $a_e = a - \phi = 19^\circ 16' - 7^\circ 15' = 12^\circ 1'$
129	0.0037 inch
130	$\frac{5}{12}$ foot (5 inches) per minute obtained by dividing 25,000 by 60,000. Note that this speed is considerably less than maximum surface speed at any load to prevent excess heat and wear
131	Yes. See Table 14, Handbook **page 2287**, and following tables
132	550 to 600 Bhn (Brinell hardness number) (See Handbook **page 2225**)
133	1 pound (See Table 6, Handbook **page 2330**)
134	23,000 rpm. See Handbook **page 1688**
135	See Handbook **page 1905**
136	See footnote, Table 2, Handbook **page 82**

Copyright 2004, Industrial Press, Inc., New York, NY

INDEX

A

Abbreviations and mathematical signs, 19
Absolute efficiency, 129
Acme screw thread, determing normal width, 118
Acme screw-thread tools, width of flat end, 118
Acme thread tool, checking width of end, 118
Allowance
  interference of metal, 98
  machine parts, 94
  provides clearance between mating parts, 98
  selection of mating parts, 99
Allowance and tolerances, 95
Allowance, limit and tolerance defined, 95
American and United States Standard thread form, 113
Angles
  and angular velocity, 133
  angular velocity expressed in radians, 133
  equivalent to given function, 52
  finding when sine, tangent, or some other function is known, 52
  functions of, 50
  negative values, 83
  use of functions for laying out, 55
Angular velocity expressed in radians, 133
Answers to "Practice Exercises" and "Review Questions", 221
Application of logarithms, 33
Areas of circles, 1

B

Bar to resist compression, 140
Beam design, examples, 146
Beam formulas, 144
Beams and stresses, 143

Copyright 2004, Industrial Press, Inc., New York, NY

Bearing loads produced by bevel gears, 187
Bevel gears
  bearing loads produced, 187
  checking spherical hub by measuring over plug gage, 71
  dimensions, 174
  formed cutter selection, 182
  power transmitting capacity, 173
  selection of formed cutters, 182
Bolts, calculating tensile strength, 114

C

Calculating gear speeds, 169
Calculations
  gear strength, 192
  involving logarithms of numbers, 32
  spreadsheets, 22–31
Capacity of bevel gears, power transmitting, 173
Change gear ratio for diametral-pitch worms, 186
Changing form of logarithm, 36
  negative characteristic, 36
Chordal dimensions, segments, and spheres, 4
Chordal thickness, bevel gear teeth, 179
Chords, lengths of, 4
Circles
  areas of, 1
  determining length of tangent when radii and center distance are known, 62
  obtaining given number of equal divisions, 4
  use of the table of segments of, 5
Circumferences of circles, 1
Clearance between mating parts, 98
Coefficients of friction for screws, 132
Cologarithms, 37
Combined stresses, shafts, 151
Compression, diameter of bar to resist, 140
Compressive strength calculation, 140

Copyright 2004, Industrial Press, Inc., New York, NY

Constants, 19
Contact ratio, 183
Continuous-path programming, 207
Control, numerical, 205
Conversion
inch to metric dimensions, 111
tables, 20
taper per foot to degrees, 90
Cosecent of an angle, 51
Cosine of an angle, 51, 101
Cotangent of an angle, 51
Cutters for bevel gears, 182

D

Data on drawings, 166
Deflection, design of shafts to resist torsional, 152
Derivation of formulas, 15
Design of shafts and keys for power transmission, 150
Design of shafts to resist torsional deflection, 152
Determining contact ratio, 183
Diameter of bar to resist compression, 140
Diameter of pin to resist shearing stress, 141
Diametral pitch
of a gear, 173
worms gear, 186
Dimensioning drawings to ensure required tolerances, 101
Dimensions
angles required in producing gears, 174
areas and volumes of geometrical figures, 42
areas of circles, 1
enlarged fine-pitch pinions, 184
generated bevel gears, 177
milled bevel gears, 179
soft conversion of inch to metric, 111
tolerances to limiting, 96
wormgear blank, 186

Copyright 2004, Industrial Press, Inc., New York, NY

Drawings
spline data, 166
tolerances, 101
violations of rules for dimensioning, 102
Drilling, estimating thrust, torque, and power, 200

E

Efficiency
absolute, 129
coefficients of friction for screws, 132
machine or mechanism, 128
mechanical, 128
Empirical formulas, 18
End thrust of helical gears, 185
applied to parallel shafts, 185
Epicyclic gearing examples, 171, 172
Equations or formulas, solving, 14
Equations, trial and error method of solution, 14

F

Factor of safety, 138
Feeds, cutting speeds, and machining power, 196
Figuring tapers, 88
Finding
diameter of bar, 139
logarithms of numbers, 34
Flat end of unified screw-thread threading tools, 118
Foot-pound or pound-foot to indicate turning moment, 123
Force
moment, 122
required to turn a screw, 131
Formed cutters for bevel gears, 182
Forming tool angle in plane perpendicular to front surface, 64
Formulas
beam, 144
derivation, 15

Copyright 2004, Industrial Press, Inc., New York, NY

Formulas *(continued)*
empirical, 18
examples illustrating derivation, 15
oblique triangles, 80
omitting multiplication signs, 9
rearrangement, 8
transposition of, 10
trial and error method of solution, 14
Friction, coefficients of, for screws, 132
Functions
and angles, 53
for laying out angles, 55
to find equivalent angle, 52
used in conjunction with formu las, 56
Functions and angles, 53
Functions of angles, 50
greater than 90 degrees, 54
trigonometric, greater than 90 degrees, 54
Fundamental laws governing rearrangement, 11

G

Gage, angular, checking accuracy by measuring over plug, 72
Gear
applied to parallel shafts, 185
bearing loads, 187
bending strength, 192
diametral pitch, 173
enlarged pinions to avoid undercut, 184
examples of dimension calculations, 174
pitch of hob, 183
power transmitted through gear train, 129
power transmitting capacity, 173
proportioning spur gears when center distance is fixed, 176
ratio for diametral-pitch, 186
selection of formed cutters, 182
speeds, 169

Copyright 2004, Industrial Press, Inc., New York, NY

Gear *(continued)*
strength calculations, 192
Geometrical figures, 42
Geometrical principles or propositions, examples illustrating application, 46
Geometrical propositions and constructions, 46

H

Helical gears
calculating end thrust, 185
helix angle, 73
parallel shafts, 185
pitch of hob, 183
Helix angles
helical gears, 73
screw thread, 73
Helix angles of screw threads, hobs, and helical gears, 73
Hobs and pitch for helical gears, 183
Horsepower
capacity for shafting, 150
determining amount when transmitted through a train of gearing, 130
equivalent turning moment or torque, 150
pitch of gearing for transmitting a given amount of power, 173
How basic size is determined for machining parts, 96
How to find more accurate functions and angles, 53

I

Important objectives of standardization, 109
Inch-pounds, turning or torsional moment expressed, 122
Inertia, moment of, 146
Information, using standards data, 108
Inscribed in triangle, radius, 64
Interchangeability of parts, 112
made to revised standards, 112
Interference of metal, 98

Copyright 2004, Industrial Press, Inc., New York, NY

Involute splines
calculating dimensions of, 159
specifying on drawings, 159

J—K

Jarno taper, determining included angle, 58
Keys
effect of strength on shaft, 154
for power transmission, 150
machine, size calculation, 154
proportioned, 154
size based on shaft size, 154
Keyway formula, depth from top of shaft, 56

L

Laying out angles, 55
Lengths of chords, 4
Limit, tolerance, and allowance, 95
Limiting dimensions, 96
Link designed to swing equally above and below centerline, 70
Loads produced by bevel gears, 187
Logarithms
calculations involving, 32
having negative characteristic, 36
how they are used, 32
of numbers, 32

M

Machine parts, tolerances and allowances, 94
Machine tool spindle tapers, 91
Machining power, cutting speeds, and feeds, 196
Materials, strength of, 138
Mathematical signs and abbreviations, 19
Mating parts, 99
Mechanical efficiency, 128

Copyright 2004, Industrial Press, Inc., New York, NY

Mechanics
moments, 124
work, 126
Mechanics, miscellaneous problems in, 122
Milling, estimating the cutting speed and spindle speed, 196
Moment of a force, 122
Moments
principle of, compared with principle of work, 126
principle of, in mechanics, 124
Moments in mechanics, 124
Motor horsepower required when train of gearing is used, 129

N

Negative values in solution of oblique triangles, 83
Numerical control, 205
continuous-path programming, 207
definition, 205
point-to-point programming, 206

O

Objectives of standardization, 109
Oblique triangles
formulas for, 80
solution when values are negative, 83
solved by right-angle method, 79
two solutions possible, 85
Obtaining allowance by selection of mating parts, 99
Obtaining more accurate values than given directly by tables, 35
Omitting multiplication signs in formulas, 9

P

Parallel shafts, end thrust of helical gears, 185
Pin measurement of splines, 164
Pin to resist shearing stress, 141
Pipe threads, 113
Pitch of a gear, 173

Copyright 2004, Industrial Press, Inc., New York, NY

Pitch of hob for helical gears, 183
Planetary gear sets, worked-out examples involving, 172
Point-to-point programming, 206
Pound-foot instead of foot-pound to indicate turning moment, 122
Power transmission, 150
Power transmitted through train of gearing, 129
Power transmitting capacity of bevel gears, 173
Principle
  governing the application of logarithms, 33
  of moments in mechanics, 124
  of work in mechanics, 126
Problems
  designing and cutting gears, 169
  mechanics, 122
Programming
  continuous-path, 207
  point-to-point, 206
  spreadsheets, 22–31
Proportioning spur gears, 176

Q—R

Questions, answers to general review, 221
Radians, angles, and angular velocity, 133
Radius of arc when chord and height are known, 46
Radius of circle inscribed in triangle, 63
Rake angle, positioning milling cutter tooth for grinding, 60
Ratio for diametral-pitch, 186
Rearrangement of formulas, 10
  fundamental laws, 11
Relation of tolerances to limiting dimensions, 96
Rules for dimensioning, 102

S

Screw and pipe threads, 113
Screw thread tools, checking widths of ends, 118

Copyright 2004, Industrial Press, Inc., New York, NY

Screw threads
Acme, determining normal width, 118
derivation of formula for checking angle, 116
determining pitch diameter, 115
helix angle, 73
pitch diameter, derivation of formula for checking by three-wire method, 115
Screws
coefficients of friction, 132
efficiency, 132
force required for elevating or lowering loads, 131
used to transmit torque, 157
Secant of an angle, 51
Segments of circles, 5
Selection of formed cutters for bevel gears, 182
Selection of key size based on shaft size, 154
Selection of mating parts, 99
Set screws used to transmit torque, 157
Shaft size, 154
Shafts
and keys for power transmission, 150
diameter for power transmission, 150
diameter when subjected to combined torsional and bending moments, 151
subjected to combined stresses, 151
to resist torsional deflection, 152
use of keys and set screws to transmit torque, 154
Shearing strength, example of calculation, 141
Shearing stress, 141
Signs and abbreviations, 19
Signs in formulas, 9
Sine of an angle, 51
Sines, law of, 80
Slab milling, estimating power required for, 199
Soft conversion of inch to metric dimensions, 111
Solution
oblique triangles, 78

Copyright 2004, Industrial Press, Inc., New York, NY

Solution *(continued)*
right-angle triangles, 58
Solving equations, 14
Specifying spline data on drawings, 166
Speeds, calculating gearing, 170
Spheres, 5
Spiral gear, helix angle, 73
Splined shaft cutter,determining width at bottom of spline, 59
Splines, 159
calculating dimensions of, 159
data on drawings, 166
pin measurements of, 159
Spreadsheets, 22–31
Spur gears
dimensions for enlarged fine pitch pinions, 184
examples of dimension calculations, 174
proportioning when center distance is fixed, 176
Standard screw and pipe threads, 113
Standardization technique, 110
Standards data and information, 108
Standards information in the Handbook, 110
Strength calculations, gear, 192
Strength of materials, 138
Stresses, combined, 151
Surface durability stress, 193

T

Table for converting taper per foot to degrees, 90
Table of segments of circles, 5
Tables of functions used in conjunction with formulas, 56
Tangent of an angle, 51
Taper hole,checking by means of ball or sphere, 69
Taper plug, checking diameter of small end, 66
Tapers
examples showing methods of figuring, 88
figuring, 88

Copyright 2004, Industrial Press, Inc., New York, NY

Tapers *(continued)*
for machine tool spindles, 91
per foot to degrees, 90
standards commonly used for machine tool spindles, 91
Tensile strength, example of calculation, 138
Thread tools, checking widths of ends, 60
Tolerances and allowances, 94
dimensioning drawings to ensure specified, 101
limit, and allowances defined, 95
relation to limiting dimensions, 96
Tolerances and allowances for machine parts, 94
Tolerances to limiting dimensions, 96
Tolerances, dimensioning drawings, 101
Tool spindles, 91
Torque and turning moment
how determined, 122
relation to horsepower, 149
Torsional deflection, 152
Transmitted torque, keys proportioned, 154
Transmitting capacity of bevel gears, 173
Trial-and-error solution of formulas, 14
Triangle, radius of circle inscribed in, 64
Triangles
oblique, formulas for, 80
right-angle, 58
solution when values are negative, 83
solved by right-angle method, 79
two solutions possible, 85
Trigonometric functions angles greater than 90 de grees, 54
Trigonometrical functions
laying out angles by means of, 55
Turning moment
for given horsepower, 148
how determined, 122
Turning, estimating spindle speed and power required in, 197

Copyright 2004, Industrial Press, Inc., New York, NY

U—V

Unified threads, 113
United States Standard thread forms, 113
Use of
formulas for oblique triangles, 80
functions for laying out angles, 55
table of segments of circles, 5
Using standards data and information, 108
Velocity expressed in radians, 133
Violations of rules for dimensioning, 102

W

When allowance provides clearance between mating parts, 98
When angles have negative values, 83
When interference of metal is result of allowance, 98
Width of flat end of unified screw-thread and American Standard Acme screw-thread tools, 118
Wire measurement of splines, 164
Work, principle of
compared with principle of moments, 128
in mechanics, 126
Wormgear blank dimensions, 186
Worms, diametral pitch, change gear ratio, 186

Copyright 2004, Industrial Press, Inc., New York, NY

LIST OF INTERACTIVE EQUATIONS

Dimensions And Areas Of Circles	1	Properties of Pi
	2	Cutting Speed to RPM Conversion
Chordal Dimensions, Segments, And Spheres	4	Chords and Diameters of Circles
Formulas And Their Rearrangement	8	Diameter of Gear Calculation
	9	Horsepower From Steam Engine
	10	Pulley Speed Calculation
	11	Height of Cylinder Given Area
	12	Height of Trapezoid Given Area
	12	Volume of Sphere Given Radius
	13	Diameter and Stroke of Steam Engine Cylinder
	14	Spiral Gear Calculations
	16	Intersection of Two Tapers
	17	Chord of Arc Calculation
	20	Pythagorean Theorem
	20	Diameter of Cylindrical Shell
	20	Geometry of Cube Calculations
	20	Area of Equilateral Triangle Given Side
	21	Area of Trapezoid
	21	Radius of Polygon
	21	Perimeter of Ellipse
	21	Pythagorean Identity
	21	Law of Sines
Calculations Involving Logarithms Of Numbers	38	Mean Effective Pressure in Steam Engine
	40	Diameter of Lineshaft Given HP and RPM

Copyright 2004, Industrial Press, Inc., New York, NY

Dimensions, Areas, And Volumes Of Geometrical Figures

42 Side of Decagon
42 Diagonal of Rectangle
42 Volume of Sphere Given Base and Height of Cone of Equal Diameter

Geometrical Propositions And Constructions

46 Radius of Segment

Functions Of Angles

56 Calculating Keyway Dimensions

Solution Of Right-angle Triangles

59 Calculating Spline Dimensions
60 Sharpening Teeth of Thread Milling Cutter
61 Forming Tool Calculations
62 Tangent to Two Circles
63 Radius of Circle Inscribed in Right Triangle
64 Calculate Angle of Forming Tool
65 Calculate Diameter of Taper Plug
67 Calculation Using Well-known Geometric Theorem
69 Checking Dimensions of Taper Gage Using Steel Ball
70 Design of Link Mechanism
71 Checking Spherical Hubs of Bevel Gears
72 Checking Accuracy of Gage Using Ball or Plug
75 Spline Problem

Solution of Oblique Triangles

78 Triangle, Side and Angles Known
79 Triangle, Sides and Angle Known
80 Law of Sines
81 Law of Cosines
82 Layout Problem
83 Triangle, Sides and Angle Known
86 Triangle, Sides and Angle Known

Copyright 2004, Industrial Press, Inc., New York, NY

LIST OF INTERACTIVE EQUATIONS

Figuring Tapers

88 Find Taper Per Foot
88 Given Taper, Find Diameter
89 Given Diameters, Find Length of Taper
89 Given Length of Taper and Taper Per Foot, Find Taper
89 Given Diameter, Length of Taper, and Taper Per Foot, Find Other Diameter
89 Given Diameter at a Point Along Taper, Length of Taper, and Taper Per Foot, Find Diameters
90 Given Diameters at Points Along Taper, Taper Per Foot, Find Length of Taper

Standard Screw And Pipe Threads

114 Checking Pitch Diameter of Screw Threads
116 Checking Angle of Screw Thread by Three-Wire Method
117 Measuring Acme Screw Thread
119 Measuring Width of Flat on Threading Tool

Problems In Mechanics

124 Calculating Moments Around Lever Arm
125 Calculating Moments Around Beam
126 Pulley Weight
129 Power Required for Gear Train
130 Designing Gear Train for Given Horsepower
131 Force toTurn Screw While Elevating Load
132 Force to Turn Screw While Lowering Load
133 Screw Efficiency with Respect to Helix Angle
135 Angular Velocity Given Surface Speed

Strength Of Materials

139 Working Stress of Steel
139 Diameter of Bar to Carry Tensile Load
140 Diameter of Bar to Resist Compression
142 Diameter of Bar to Resist Shearing Stress and Shock Loading
146 Depth of Beam to Support Load
147 Height of Beam to Support Load
147 Beam Size and Deflection
148 Beam Size and Deflection at Critical Point
148 Torsional Moment of Pinion Shaft

Copyright 2004, Industrial Press, Inc., New York, NY

LIST OF INTERACTIVE EQUATIONS

Design Of Shafts And Keys For Power Transmission

150 Diameter of Lineshaft to Carry Load
151 Diameter of Lineshaft to Carry Load
151 Diameter of Lineshaft to Resist Combined Stresses
153 Diameter of Shaft to Transmit Torque
156 Size of Key Required for Shaft

Splines

159 Design of Metric Module Spline
164 Measasurement of Spline Dimensions

Problems In Designing And Cutting Gears

170 Speed of Driven Shaft in Belt-Gear Drive
170 Speed of Mixed Gear Drive
171 Speed of Worm Wheel
171 Setting Spindle Speed with Step Pulleys
172 Speed of Planetary Gear Sets
172 Rotation of Planetary Gear Sets
173 Compound Planetary Gear Sets
173 Compound Planetary Gear Sets
174 Diametral Pitch of Spur Gear
175 Hob Tip Radius for Spur Gear
175 Whole Depth of Rack Teeth
177 Dimensions of Bevel Gears (Gleason System)
179 Dimensions of Milled Bevel Gears
183 Determine Contact Ratio
184 Center Distance for Gears
184 Center Distance for Gears to Reduce Backlash
185 End Thrust of Helical Gears
186 Dimensions of Wormgear Blank
187 Radial and Thrust Loads of Gear Drive

Cutting Speeds, Feeds, And Machining Power

197 Power Required for Turning
198 Cutting Speed to Utilize Maximum Available Power
199 Motor Power Required for Milling Operation
199 Cutting Speed to Utilize Maximum Available Power
200 Thrust , Torque and Motor Power for Drilling

General Review Questions

218 Diameter of Rod to Make Chain
219 Relief Angle of Thread Cutting Tool

Copyright 2004, Industrial Press, Inc., New York, NY